

START

U S
OFFICIAL GAZETTE
UNITED STATES
PATENT OFFICE

VOL NO 1011

OCTOBER

1981

MICRO PHOTO DIVISION



BELL & HOWELL

BH

Vol. 1011 Number 1

OFFICIAL GAZETTE

of the
UNITED STATES PATENT AND TRADEMARK OFFICE



October 6, 1981

U.S.
DEPARTMENT
OF COMMERCE

Patent
and
Trademark
Office

OFFICIAL GAZETTE of the
UNITED STATES PATENT and TRADEMARK OFFICE

October 6, 1981

Volume 1011

Number 1

CONTENTS

	Page
Patent and Trademark Office Notices	
Patent Cooperation Treaty (PCT) Information	1011 OG 2
Reissue Applications Filed	1011 OG 2
Requests for Reexamination Filed	1011 OG 2
Service by Publication	1011 OG 2
Patent Certificates of Correction	1011 OG 4
Patent Suits	1011 OG 4
Reference Collections of U.S. Patents Available for Public Use in Patent Depository Libraries	1011 OG 7
Condition of Patent Applications	1011 OG 8
Defensive Patent Publications (101,101)	1
Reissue Patents Granted (30,757)	3
Plant Patents Granted (4,772)	7
Patents Granted	
General and Mechanical (4,292,687)	9
Chemical (4,293,305)	219
Electrical (4,293,730)	345
Design Patents Granted (261,070)	425
Index of Patentees	PI 1
Indices of Reissue, Design and Plant Patentees	PI 46
Index of Applicants of Defensive Publications	PI 49
Classification of	
Patents (Including Reissues)	PI 51
Designs, Plants and Defensive Publications	PI 54
Geographical Index of Residence of Inventors	
Patents (Including Reissues)	PI 55
Designs, Plants and Applicants of Defensive Publications	PI 57
Change of Address Form and Subscription Order Form	Back Page

The following are mailed under direction of the Superintendent of Documents, Government Printing Office, Washington, D.C., 20402, to whom all subscriptions should be made payable and all communications addressed:

THE OFFICIAL GAZETTE (PATENT SECTION), issued weekly, subscription \$325.00 per annum for first-class mailing, also available as fourth-class mail at \$225.00 domestic; \$281.25 foreign; foreign first-class mailing rates will be furnished upon request; single copies each, \$5.50 domestic, \$6.90 foreign.

THE OFFICIAL GAZETTE (TRADEMARK SECTION), issued weekly, subscription \$105.00 per annum, foreign mailing \$131.25 per annum; single copies \$2.75 each domestic, \$3.45 foreign.

GENERAL INFORMATION concerning PATENTS, price \$2.25 each.

GENERAL INFORMATION concerning TRADEMARKS, price \$1.70 each.

PRINTED COPIES OF PATENTS are furnished by the Patent and Trademark Office at 50 cents each; PLANT PATENTS in color, \$1.00 each; copies of TRADEMARKS AND DESIGN PATENTS at 20 cents each. Address orders to the Commissioner of Patents and Trademarks, Washington, D.C., 20231.

PATENT AND TRADEMARK OFFICE NOTICES

Patent Cooperation Treaty Information

For information concerning the PCT, consult Chapter 1800 of the Manual of Patent Examining Procedure and notices 90-95 in the consolidated listing of notices appearing in the Official Gazette of Jan. 6, 1981.

The PCT fees in effect after May 19, 1981 are as follows:

Transmittal fee	\$ 35.00
Search fee	300.00
International Basic Fee (for the first 30 sheets of an international application)	215.00
Basic Supplemental Fee (for each sheet over 30)	4.00
International Designation Fee (for each State for which a national patent is sought, or group of States for which the same regional patent is sought)	50.00

RENE D. TEGTMEYER,
Assistant Commissioner
for Patents.

REISSUE APPLICATIONS FILED

Notice under 37 CFR 1.11(b). The reissue applications listed below are open to inspection by the general public in the indicated Examining Groups and copies may be obtained by paying the fee therefor (37 CFR 1.21(b)).

3,674,562, Re. S.N. 270,216, Filed June 3, 1981, Cl. 429/192, PRIMARY CELLS AND IODINE CONTAINING CATHODES THEREFOR, Alan A. Schneider, et al., Owner of Record: *Catalyst Research Corp., Baltimore, Md.*, Attorney or Agent: Stanton T. Lawrence, Jr., et al., Ex. Gp.: 114

4,057,703, Re. S.N. 271,561, Filed June 8, 1981, Cl. 219/69C, METHOD OF MACHINING BY EROSION ELECTRICAL DISCHARGES, Jean Pfau, Owner of Record: *Ateliers des Charmilles, S.A., Geneva, Switzerland*, Attorney or Agent: Claude A. Patalidis, et al., Ex. Gp.: 213

4,112,234, Re. S.N. 274,291, Filed June 16, 1981, Cl. 548/342, IMIDAZOLYLMETHYLTHIOETHYL ALKYNYL GUANIDINES, Ronnie Ray Crenshaw, et al., Owner of Record: *Bristol-Myers Co., New York, N.Y.*, Attorney or Agent: Joseph M. Fitzpatrick, et al., Ex. Gp.: 121

4,170,127, Re. S.N. 241,138, Filed Mar. 6, 1981, Cl. 073/28, CALIBRATED OIL BURNER FILTER PAPER, Anthony W. Butera, Owner of Record: *Inventor*, Attorney or Agent: None, Ex. Gp.: 244

4,197,654, Re. S.N. 243,856, Filed Mar. 16, 1981, Cl. 33/304, SURVEY APPARATUS AND METHOD EMPLOYING ALL LATITUDE, ALL ATTITUDE GYROCOMPASSING, Donald H. van Steenwyk, et al., Owner of Record: *Applied Technologies Associates, San Marino, Calif.*, Attorney or Agent: William W. Haefliger, Ex. Gp.: 243

4,221,267, Re. S.N. 272,626, Filed June 11, 1981, Cl. 172/804, ANGLE AND TILT IMPLEMENT ASSEMBLY, Jerrold R. Asal, et al., Owner of Record: *Caterpillar Tractor Co., Peoria, Ill.*, Attorney or Agent: Ralph E. Walters, et al., Ex. Gp.: 334

4,238,586, Re. S.N. 271,563, Filed June 8, 1981, Cl. 526/137, GROUP VA AND VII OXYGEN MINERAL ACIDS AS CATALYST MODIFIERS, Nikolaous K. Balint, Owner of Record: *Standard Oil Co., Chicago*,

Ill., Attorney or Agent: William T. McClain, et al., Ex. Gp.: 144

4,252,242, Re. S.N. 271,562, Filed June 8, 1981, Cl. 211/96, CLOTHING RACK, Charles L. Tudor, Owner of Record: *Inventor*, Attorney or Agent: Norman S. Blodgett, Ex. Gp.: 355

REQUESTS FOR REEXAMINATION FILED

Notice under 37 CFR 1.11(c). The requests for reexamination listed below are open to inspection by the general public in the indicated Examining Groups. Copies of the requests and related papers may be obtained by paying the fee therefor established in the Rules (37 CFR 1.21(b)).

In the event correspondence to the patent owner is not received, this notice will be considered to be constructive notice to the patent owner and reexamination will proceed (37 CFR 1.248(a)(5) and 1.525(b)).

3,518,946, Reexam. No. 90/000,059, Requested: Aug. 21, 1981, Cl. 104/174, PUSHER CONVEYOR FOR WHEELED CARRIERS, Sheldon M. Kavieff, Owner of Record: *Jervis B. Webb Co.*, Attorney or Agent: Joseph W. Farley, Ex. Gp.: 316, Requester: George E. Oram, Jr., Washington, D.C.

3,523,408, Reexam. No. 90/000,061, Requested: Sept. 1, 1981, Cl. 55/159, GAS SEPARATOR, David Rosenberg, Owner of Record: *Pall Corp.*, Attorney or Agent: Leydig, Voit, Osann, Mayer & Holt, Ltd., Ex. Gp.: 170, Requester: Pall Corp., Glen Cove, N.Y.

3,621,243, Reexam. No. 90/000,064, Requested: Sept. 8, 1981, Cl. 250/395, APPARATUS AND PROCESS FOR DETERMINING PARTICLE SIZE BY X-RAY ABSORPTION ANALYSIS, James Peter Olivier, et al., Owner of Record: *Freeport Minerals Co.*, Attorney or Agent: W. Philip Churchill, Ex. Gp.: 252, Requester: Micromeritics Instrument Corp., Norcross, Ga.

3,770,033, Reexam. No. 90/000,067, Requested: Sept. 9, 1981, Cl. 145/61C, MOLDED HANDLE FOR IMPACT TOOLS, Charles R. Gavillet, et al., Owner of Record: *Decker Manufacturing Co.*, Attorney or Agent: Austin P. Dodge, et al., Ex. Gp.: 323, Requester: Decker Manufacturing Co., c/o Robert A. Ostmann, Arlington, Va.

3,888,582, Reexam. No. 90/000,062, Requested: Sept. 2, 1981, Cl. 493/328, SEMI-AUTOMATIC DOCUMENT HANDLER, Augustus W. Griswold, Owner of Record: *Xerox Corp., Stamford, Conn.*, Attorney or Agent: Ralabate, et al., Ex. Gp.: 324, Requester: Xerox Corp., Rochester, N.Y.

4,157,161, Reexam. No. 90/000,066, Requested: Sept. 9, 1981, Cl. 239/11, WINDSHIELD WASHER, Peter Bauer, Owner of Record: *Bowles Fluidics Corp.*, Attorney or Agent: Rose & Edell, Ex. Gp.: 313, Requester: Peter Bauer, Germantown, Md.

Service by Publication

A petition to cancel each of the registrations identified below having been filed, and the notice of such proceedings sent by registered mail to each registrant at the last known address having been returned by the Post Office as undeliverable, notice is hereby given that unless the registrants listed herein, their assigns or legal representatives, shall enter an appearance within thirty days from

the date of this publication, the cancellation will be proceeded with as in the case of default.

Belgrade Shoe Co., Auburn, Me., Reg. Nos. 534,058 and 812,213, Canc. No. 12,934.

Appendagez, Inc., Norwood, Mass., Reg. No. 1,116,098, Canc. No. 12,964.

Cotton Club Frocks, Inc., New York, N.Y., Reg. No. 777,452, Canc. No. 12,978.

Stylon Corp., Milford, Mass., Reg. No. 727,653, Canc. No. 12,988.

Bedford Shirtmakers Corp., by change of name from **Bedford Shirt Corp.**, New York, N.Y., Reg. No. 761,115, Canc. No. 13,006.

EVELYN R. LOPEZ,
Clerk, Trademark
Trial and Appeal Board.
For MARGARET M. LAURENCE,
Assistant Commissioner
for Trademarks.

PATENT NOTICES

Certificates of Correction for the Week of Oct. 6, 1981

D. 259,045	4,245,057	4,265,035	4,275,105
3,931,195	4,245,761	4,265,072	4,275,197
3,999,386	4,246,682	4,265,095	4,275,654
4,030,091	4,248,780	4,265,885	4,275,739
4,099,638	4,251,498	4,265,993	4,275,880
4,107,390	4,252,238	4,267,086	4,275,905
4,128,043	4,253,043	4,267,095	4,275,935
4,130,481	4,253,789	4,267,223	4,276,362
4,133,877	4,254,241	4,267,322	4,276,427
4,134,903	4,254,883	4,267,364	4,276,745
4,156,144	4,255,349	4,267,671	4,276,914
4,159,104	4,255,721	4,267,843	4,277,311
4,169,990	4,255,907	4,267,882	4,277,318
4,184,551	4,256,316	4,268,591	4,277,645
4,185,511	4,256,471	4,268,870	4,278,005
4,189,758	4,257,106	4,269,100	4,278,190
4,193,885	4,257,188	4,269,236	4,278,215
4,194,948	4,257,539	4,269,517	4,278,366
4,202,625	4,257,968	4,269,675	4,278,439
4,219,191	4,258,019	4,269,945	4,278,858
4,220,792	4,258,041	4,270,028	4,279,500
4,221,677	4,259,103	4,270,450	4,279,594
4,227,648	4,259,250	4,270,975	4,279,873
4,228,191	4,259,528	4,271,094	4,280,185
4,228,232	4,260,469	4,271,191	4,280,201
4,230,773	4,260,955	4,271,405	4,280,231
4,232,113	4,261,056	4,271,536	4,280,442
4,232,369	4,261,511	4,271,693	4,280,588
4,233,430	4,261,983	4,273,055	4,280,811
4,234,763	4,262,147	4,273,188	4,280,943
4,237,082	4,263,091	4,273,563	4,280,969
4,238,345	4,263,269	4,273,627	4,281,247
4,239,128	4,263,392	4,273,774	4,281,307
4,239,177	4,263,748	4,274,155	4,281,346
4,239,299	4,264,070	4,274,272	4,281,358
4,244,626	4,264,135	4,274,403	
4,244,738	4,264,744	4,275,006	

Patent Suits

Notices under 35 U.S.C. 290; Patent Act of 1952

2,409,774, Mack and Klebsattel, A DRIER METAL SALT AND A PROCESS OF MAKING IT; **3,467,683**, Harson and Fogg, METAL ORGANOPHOSPHORUS COMPOUNDS; **Re. 30,553**, Harson and Fogg, METAL ORGANOPHOSPHORUS COMPOUNDS, filed June 8, 1981, D.C., N.D. Ohio (Cleveland), Doc. C81-1179, *Manchem Ltd. v. Mooney Chemicals, Inc.*

3,047,196, A & E Warbern, Inc. GARMENT HANGER, filed Nov. 10, 1979, D.C., S.D. Fla. (Miami), Doc. 79-6487-CIV-SMA, *Huron Machine Products, Inc. v. A & E Warbern, Inc. f/k/a Warbern Packaging Industries, Inc., et al.* Final Order of Dismissal with prejudice entered June 30, 1981.

3,155,539, Ransburg Corp. ELECTROSTATIC SPRAY COATING METHODS AND APPARATUS, filed July 2, 1981, D.C. Conn. (Bridgeport), Doc. B-81-299, *Ransburg Corp. v. Interrad Corp.*

3,221,588, Illinois Tool Works, Inc., DRILL SCREW AND AN ASSEMBLY INCLUDING THE SAME, filed June 26, 1981, D.C., N.D. Ill. (Chicago), Doc. 81 C 3592, *Illinois Tool Works, Inc. v. Construction Fasteners, Inc.*

3,279,141, Firman L. Carswell Manufacturing Co.,

Inc., SUB-STRUCTURE FOR BOAT DOCKS, filed June 5, 1981, D.C., N.D. Ga. (Atlanta), Doc. C81-1086 A, *Firman L. Carswell Manufacturing Co., Inc. v. Cherokee Metal Co., Inc., et al.*

3,319,289, Miles Laboratories, Inc., APPARATUS FOR MOUNTING A SPECIMEN, filed June 12, 1981, D.C., W.D. Pa. (Pittsburgh), Doc. 81-965, *Miles Laboratories, Inc. v. Fisher Scientific.*

3,319,515, E. I. du Pont de Nemours & Co., INTERFEROMETRIC OPTICAL PHASE DISCRIMINATION APPARATUS, filed June 22, 1981, D.C., N.D. Calif. (San Francisco), Doc. C 81-2553 SAW, *Bio-Rad Laboratories, Inc. v. Nicolet Instrument Corp.*

3,326,009, Archie R. Gagne, PLOW FOR LAYING CABLE, FLEXIBLE CONDUIT OR THE LIKE; **3,326,010**, same, SLIT TRENCHING AND CABLE LAYING MACHINE, filed June 1, 1981, D.C., N.D. Ill. (Chicago), Doc. 81 C 3040, *Archie R. Gagne v. North Star Concrete Co., Inc.*

3,326,010. (See **3,326,009**.)

3,465,889, F. B. Leopold Co., Inc., LIQUID CLARIFIER WEIR CONSTRUCTION, filed Nov. 21, 1977, D. C., N.D. Ohio (Youngstown), Doc. C-77-2339-Y, *Sybron Corp. v. Molded Fiber Glass Companies, Inc. U.S. Patent No. 3,465,889 is valid and infringed. Defendant is permanently enjoined from manufacturing the weir pan and otherwise infringing said patent. Filed May 27, 1981.*

3,467,683. (See **2,409,774**.)

3,528,124, Slade Gorton & Co., Inc., METHOD OF SHUCKING SHELLFISH; **3,662,432**, same, APPARATUS FOR EVISCERATING SCALLOPS; **3,665,554**, same, METHOD OF EVISCERATING SHELLFISH, filed Nov. 12, 1974, D.C., M.D. Fla. (Orlando), Doc. 74-343-ORL-CIV-R, *Slade Gorton & Co., Inc. v. Florida East Seafoods, Inc., et al.* Consent Judgment stating that Plaintiff's patents are valid and enforceable filed Feb. 16, 1977. *Same*, filed Dec. 27, 1972, D.C., M.D. Fla. (Orlando), Doc. 72-313-ORL-CIV-R, *Slade Gorton & Co., Inc. v. Willis Brothers of Florida, Inc., et al.* Motion for Voluntary Dismissal of Action Against Defendant granted without prejudice on Feb. 23, 1977.

3,555,593, Donald J. Scheier, METHOD OF EVISCERATING POULTRY; **3,653,093**, same, POULTRY EVISCERATING MACHINE, filed June 20, 1980, D.C., N.D. Ga. (Gainesville), Doc. 80-048G, *Simon-Johnson, Inc. v. Centennial Machine Co., Inc.* Defendant is permanently enjoined and restrained from infringing said patents. Filed June 30, 1981.

3,574,911, Milling Specialties, Inc., CUTTER AND INSERTS THEREFOR, filed June 10, 1981, D.C., W.D. Pa. (Erie), Doc. 81-130 ERIE, *Milling Specialties, Inc. v. Greenleaf Corp.*

3,584,562, Kenneth R. Wisner, PHOTOGRAPHIC FILM HOLDER, filed Nov. 13, 1980, D.C.N.J. (Newark), Doc. 80-3658, *Kenneth R. Wisner v. Victor Hasselblad*. Order of dismissal of action filed June 25, 1981.

3,617,613, Spaulding Fibre Co., PUNCHABLE PRINTED CIRCUIT BOARD BASE, filed Dec. 7, 1978, D.C.N.H. (Concord), Doc. C 78-434, *Spaulding Fibre Co. v. Oak Materials Group, Inc. U.S. Patent No. 3,617,613 is valid and infringed. Defendant is permanently restrained from infringing plaintiff's patent. Filed June 3, 1981.*

OCTOBER 6, 1981

U.S. PATENT AND TRADEMARK OFFICE

1011 O.G.—5

3,624,205, Burroughs Wellcome Co., TREATMENT OF HYPERURICEMIA IN HUMANS, filed Dec. 21, 1979, D.C.N.J. (Newark), Doc. 79-3643, *Burroughs Wellcome Co. v. Pharmadyne Laboratories, Inc.* Consent Judgment for permanent injunction in favor of plaintiff filed Mar. 30, 1981.

3,653,093. (See **3,555,593**.)

3,662,314, Piher S.A., ADJUSTABLE ANNULAR POTENTIOMETER WITH TERMINAL ATTACHMENT MEANS; **3,670,285**, CTS Corp., VARIABLE RESISTANCE CONTROL WITH END COLLECTOR, filed May 12, 1980, D.C., N.D. Ind. (South Bend), Doc. S80-126, *Piher Sociedad Anonima v. CTS Corp.* Order filed Mar. 9, 1981.

3,662,432. (See **3,528,124**.)

3,665,554. (See **3,528,124**.)

3,669,105, Lenox Hill Brace Shop, Inc., BRACE FOR ARTICULATED LIMBS; Reg. No. 957,912 (LENOX HILL), Lenox Hill Brace Shop, Inc., filed Aug. 8, 1980, D.C., N.D. Ga. (Atlanta), Doc. C80-1363A, *Lenox Hill Brace Shop, Inc. v. C. H. Martin Co., et al.* U.S. Patent No. 3,669,105 is valid and infringed. Defendants are permanently enjoined from further infringing plaintiff's patent and trademark. Filed Dec. 22, 1980.

3,670,285. (See **3,662,314**.)

3,744,655, Anchor Hocking Corp., SAFETY CLOSURE FOR CONTAINERS, filed Feb. 13, 1976, D.C.N.J. (Newark), Doc. 76-278, *Anchor Hocking Corp. v. Mack-Wayne Plastics Co.* Order of Dismissal of action, without costs, filed Nov. 16, 1976.

3,787,020, Aluma Systems, Inc., CONCRETE FORMING STRUCTURE; **3,899,152**, same, CONCRETE FORM INCLUDING EXTRUDED ALUMINUM SUPPORT STRUCTURE; **4,144,690**, same, CONCRETE FORMING STRUCTURES, filed Apr. 25, 1980, D.C.N.J. (Newark), Doc. 80-1199, *Patent Scaffolding Co., et al. v. Aluma Systems, Inc.* Consent Decree for Permanent Injunction filed Dec. 29, 1980.

3,787,020, Aluma Systems, Inc., CONCRETE FORMING STRUCTURE, filed Mar. 12, 1981, D.C., S.D. Tex. (Houston), Doc. H-81-575, *Aluma Systems, Inc. v. Anthes, Inc., et al.* *Same*, filed May 5, 1981, D.C., E.D. Pa. (Philadelphia), Doc. 81-1877, *Anthes, Inc., et al. v. Aluma Systems, Inc.*

3,803,660, Randomex, Inc., APPARATUS FOR CLEANING DISCS, filed June 22, 1981, D.C., C.D. Calif. (Los Angeles), Doc. 81 3071, *Randomex, Inc. v. Scopus Corp.*

3,811,414, Thunderbird Industries, Inc., HEAT EXCHANGER APPARATUS FOR PRODUCING STEAM OR THE LIKE, filed Oct. 8, 1980, D.C., M.D.N.C. (Greensboro), Doc. C-80-535-WS, *Thunderbird Industries, Inc. v. Spartan Manufacturing Corp., et al.* Stipulation and Notice of Dismissal with Prejudice filed July 1, 1981.

3,811,544, Luk Lamellen-Und Kupplungsbau GmbH, CLUTCH WITH SPRING LOADED OPERATOR FULCRUM, filed Sept. 21, 1979, D.C., E.D. Mich. (Detroit), Doc. 79-73691, *Luk Lamellen-Und Kupplungsbau GmbH v. Valeo, Inc.*

3,820,950, Sammy G. Hiatt, PROCESS AND APPARATUS FOR LIQUID TREATING OF TEXTILE FABRIC, filed July 8, 1981, D.C., M.D.N.C. (Greensboro), Doc. C-81-311-G, *Sammy G. Hiatt v. United Merchants and Manufacturers, Inc.*

3,829,335, Scientific Micro Systems, Inc., METHOD FOR PROCESSING SEMICONDUCTOR WAFERS, filed Nov. 7, 1980, D.C., N.D. Calif. (San Francisco), Doc. C 80 4150 RFP, *Scientific Micro Systems, Inc. v. Intersil, Inc.* Case dismissed with prejudice (with 90 day condition) on June 24, 1981.

3,843,052, Graco, Inc., PNEUMATICALLY ASSISTED HYDRAULIC SPRAY COATING APPARATUS, filed June 29, 1981, D.C., N.D. Ill. (Chicago), Doc. 81 C 3636, *Graco, Inc. v. Kremlin, Inc., et al.*

3,871,367, Marion E. Miller, PELVIC BRACE, filed July 14, 1981, D.C.N.J. (Newark), Doc. 81-2230, *Marion E. Miller v. Pope Brace, et al.*

3,879,188, Fritz, Evans and Cooke, GROWTH REGULATION PROCESS, filed June 17, 1975, D.C., E.D. Pa. (Philadelphia), Doc. 75-1730, *GAF Corp. v. Amchem Products, Inc., et al.* Order filed June 24, 1981.

3,893,127, Michael Kaplan, ELECTRON BEAM RECORDING MEDIA, filed Mar. 6, 1981, D.C.N.J. (Trenton), Doc. 81-681, *RCA Corp. v. Edmund Benjamin Davidson*. Summary judgment in favor of plaintiff declared that defendant is not sole inventor or co-inventor of patent no. 3,893,127. Filed Mar. 27, 1981.

3,899,152. (See **3,787,020**.)

3,910,434, Ebeling and Ebeling, MECHANICALLY ACTUATED SIDE LOADING ARRANGEMENT FOR A VEHICLE BODY; **3,944,092**, same, CONTAINER EMPTYING DEVICE, filed July 27, 1977, D.C., W.D. Tex. (San Antonio), Doc. SA-77-CA-226, *Franklin D. Ebeling, et al. v. Pak-Mor Manufacturing Co.* Judgment filed June 22, 1981.

3,944,092. (See **3,910,434**.)

3,973,282, Marvin I. May, WATER BED LINER HOLDER, filed July 2, 1981, D.C., N.D. Tex. (Dallas), Doc. CA3-81-1083-D, *Marvin I. May v. Vinylex Corp.*

3,973,282, Marvin I. May, WATER BED LINER HOLDER; Reg. No. 1,147,691 (TUCK-A-LINER), Marvin I. May, filed May 1, 1981, D.C., N.D. Tex. (Dallas), Doc. CA3-81-0717 D, *Tite Nites, Inc. & Marvin I. May v. Bedderest Corp.* Final Judgment in favor of plaintiff and against defendant filed July 15, 1981.

4,019,103, Davis, Jones and Eddy, ELECTROMAGNETIC MOTOR AND GENERATOR, filed Aug. 27, 1979, D.C., E.D. Tex. (Texarkana), Doc. TX-79-60-CA, *Ralph E. Lindsey v. United States Government, et al.*

4,048,496, Richard D. Albert, SELECTABLE WAVELENGTH X-RAY SOURCE, SPECTROMETER AND ASSAY METHOD; **4,260,885**, same, filed July 17, 1981, D.C., N.D. Calif. (San Francisco), Doc. C 81-3011 SAW, *Richard D. Albert v. Kevex Corp.*

4,081,091, Transportation Design & Technology, Inc., WHEELCHAIR LIFT, filed Mar. 30, 1979, D.C., C.D. Calif. (Los Angeles), Doc. 79-1217 (RJK) (PX), *Transportation Design & Technology, Inc. v. General Motors Corp., et al.*

4,108,303, E. W. Buschman Co., POWER TRANSMISSION ASSEMBLY FOR AN ACCUMULATOR CONVEYOR, filed June 3, 1981, D.C., S.D. Ohio (Dayton), Doc. C-3-81-296, *The E. W. Buschman Co. v. Rexnord, Inc.* Case transferred to Eastern District of Kentucky at Lexington on July 30, 1981. *Same*, filed Aug. 3, 1981, D.C., E.D. Ky. (Lexington), Doc. 81-149, *The E. W. Buschman Co. v. Rexnord, Inc.*

4,112,927, David I. Carlson, ULTRASONIC DETECTOR WITH AUDIBLE INDICATION SIGNAL, filed June 26, 1981, D.C. Minn. (Minneapolis), Doc. 4-81-351, *International Livestock Improvement Services Corp. v. Centech Corp.*

4,116,664, Leon R. Jones, FERTILIZER COMPOSITION AND METHOD OF MAKING SAME, filed Jan. 17, 1980, D.C., E.D. Calif. (Fresno), Doc. CV-80-18-EDP, *Leon R. Jones v. Verdegaa Brothers, Inc.* Patent held invalid and not infringed on June 29, 1981.

4,144,690. (See **3,787,020**.)

4,148,410, Omar L. Brown, TAB FOR EASY-OPEN ECOLOGY END, filed Mar. 11, 1981, D.C., S.D. Ohio (Dayton), Doc. C-3-81-183, *Ermal C. Frazee v. The Continental Group, Inc., et al.*

4,158,987, Excellon Industries, PRESSURE FOOT FOR MACHINE TOOL, filed May 20, 1981, D.C., C.D. Calif. (Los Angeles), Doc. 80 2455, *Excellon Industries v. Cooper Industries, doing business as Advanced Controls*.

4,162,092, L. R. Nelson Corp., HOSE COUPLING, filed July 7, 1981, D.C., C.D. Calif. (Los Angeles), Doc. 81 3349, *Rain Bird Sprinkler Mfg. Corp. v. L. R. Nelson Corp.*

4,182,755, Cargill, Inc., FEED INTAKE CONTROL OF ANIMALS, filed June 23, 1981, D.C., N.D. Ind.

(Fort Wayne), Doc. F81-168, *Cargill, Inc. v. Central Soya Co., Inc.*

4,192,163, Alan Martin, TOOL FOR SETTING BLIND FASTENERS, filed July 20, 1981, D.C. Mass. (Boston), Doc. 81-1833-G, *Alan Martin v. Marson Corp.*

4,260,885. (See 4,048,496.)

Re. 29,050, Louise Z. Hakim, TOY WITH SOUND PRODUCING MEANS, filed June 22, 1981, D.C.N.J. (Newark), Doc. 81-1916 *Louise Z. Hakim v. Sanitoy, Inc.*

Re. 30,553. (See 2,409,774.)

D. 248,329, Action Industries, Inc., SMOKING STAND, filed Mar. 14, 1979, D.C., W.D. Pa. (Pittsburgh), Doc. 79-343, *Action Industries, Inc. v. Hope Picture Frame Co.* Case closed on May 26, 1981.

Reference Collections of U.S. Patents Available for Public Use in Patent Depository Libraries

The libraries listed herein, designated as patent depository libraries, receive current issues of U.S. Patents and maintain collections of earlier issued patents. The scope of these collections varies from library to library, ranging from patents of only recent months or years in some libraries to all or most of the patents issued since 1870, or earlier, in other libraries.

These patent collections are open to public use and each of the patent depository libraries, in addition, offers the publications of the patent classification system (e.g. The Manual of Classification, Index to the U.S. Patent Classification, Classification Definitions, etc.) and provides technical staff assistance in their use to aid the public in gaining effective access to information contained in patents. With one exception, as noted in the

table following, the collections are organized in patent number sequence.

Depending upon the library, the patents may be available in microfilm, in bound volumes of paper copies, or in some combination of both. Facilities for making paper copies from either microfilm in reader-printers or from the bound volumes in paper-to-paper copiers are generally provided for a fee.

Owing to variations in the scope of patent collections among the patent depository libraries and in their hours of service to the public, anyone contemplating use of the patents at a particular library is advised to contact that library, in advance, about its collection and hours, so as to avert possible inconvenience.

State	Name of Library	Telephone Contact
Alabama	Birmingham Public Library	(205) 254-2555
Arizona	Tempe: Science Library, Arizona State University	(602) 965-7607
California	Los Angeles Public Library	(213) 626-7555 Ext. 273
	Sacramento: California State Library	(916) 322-4572
	Sunnyvale: Patent Information Clearinghouse*	(408) 738-5580
Colorado	Denver Public Library	(303) 573-5152 Ext. 222
Delaware	Newark: University of Delaware	(302) 738-2238
Georgia	Atlanta: Price Gilbert Memorial Library, Georgia Institute of Technology	(404) 894-4519
Illinois	Chicago Public Library	(312) 269-2814
Louisiana	Baton Rouge: Troy H. Middleton Library, Louisiana State University	(504) 388-2570
Massachusetts	Boston Public Library	(617) 536-5400 Ext. 265
Michigan	Detroit Public Library	(313) 833-1450
Minnesota	Minneapolis Public Library & Information Center	(612) 372-6552
Missouri	Kansas City: Linda Hall Library	(816) 363-4600
	St. Louis Public Library	(314) 241-2288 Ext. 214, 215
Nebraska	Lincoln: University of Nebraska-Lincoln, Engineering Library	(402) 472-3411
New Hampshire	Durham: University of New Hampshire Library	(603) 862-1777
New Jersey	Newark Public Library	(201) 733-7814
New York	Albany: New York State Library	(518) 474-5125
	Buffalo and Erie County Public Library	(716) 856-7525 Ext. 267
	New York Public Library (The Research Libraries)	(212) 790-6291
North Carolina	Raleigh: D. H. Hill Library, N.C. State University	(919) 737-3280
Ohio	Cincinnati & Hamilton County, Public Library of	(513) 369-6936
	Cleveland Public Library	(216) 623-2870
	Columbus: Ohio State University Libraries	(614) 422-6286
	Toledo/Lucas County Public Library	(419) 255-7055 Ext. 212
Oklahoma	Stillwater: Oklahoma State University Library	(405) 624-6546
Pennsylvania	Philadelphia: Franklin Institute Library	(215) 448-1321**
	Pittsburgh: Carnegie Library of Pittsburgh	(412) 622-3138
	University Park: Pattee Library, Pennsylvania State University	(814) 865-4861
Rhode Island	Providence Public Library	(401) 521-7722 Ext. 226
Tennessee	Memphis & Shelby County Public Library and Information Center	(901) 528-2957
Texas	Dallas Public Library	(214) 748-9071
	Houston: The Fondren Library, Rice University	(713) 527-8101 Ext. 2587
Washington	Seattle: Engineering Library, University of Washington	(206) 543-0740
Wisconsin	Madison: Kurt F. Wendt Engineering Library, University of Wisconsin	(608) 262-6845
	Milwaukee Public Library	(414) 278-3043

*Collection organized by subject matter.

**Call only between the hours of 10:00 a.m. and 5:00 p.m.

PATENT EXAMINING CORPS
RENE D. TEGTMEYER, Assistant Commissioner
WILLIAM FELDMAN, Deputy Assistant Commissioner
CONDITION OF PATENT APPLICATIONS AS OF August 22, 1981

PATENT EXAMINING GROUPS	Actual Filing Date of Oldest New Case Awaiting Action
CHEMICAL EXAMINING GROUPS	
GENERAL CHEMISTRY AND PETROLEUM CHEMISTRY, GROUP 110—D. E. TALBERT, Director	4-29-80
Inorganic Compounds; Inorganic Compositions; Organo-Metal and Organo-Metalloid Chemistry; Metallurgy; Metallurgical Apparatus; Metal Stock; Electro Chemistry; Batteries; Hydrocarbons; Mineral Oil Technology; Lubricating Compositions; Gaseous Compositions; Fuel and Igniting Devices.	
GENERAL ORGANIC CHEMISTRY, GROUP 120—C. E. VAN HORN, Director	10-11-79
Heterocyclic Amides; Alkaloids; Azo; Sulfur; Misc. Esters; Carbohydrates; Herbicides; Poisons; Medicines; Cosmetics; Steroids; Oxo and Oxy; Quinones; Acids; Carboxylic Acid Esters; Acid Anhydrides; Acid Halides.	
HIGH POLYMER CHEMISTRY, PLASTICS AND MOLDING, GROUP 140—J. O. THOMAS, JR., Director	7-07-80
Synthetic Resins; Rubber; Proteins; Macromolecular Carbohydrates; Mixed Synthetic Resin Compositions; Synthetic Resins With Natural Polymers and Resins; Reclaiming; Pore-Forming; Compositions (Part) e.g., Coating; Molding; Ink; Prosthetics; Adhesive and Abrading Compositions; Molding, Shaping, Treating Process, and Apparatus Therefor; Irradiation (Part); Bleaching; Dyeing; Leather, Fur and Textile Treating Compositions.	
COATING, LAMINATING AND PHOTOGRAPHY, GROUP 160—S. N. ZAHARNA, Director	2-02-80
Coating; Processes, Apparatus and Misc. Products; Laminating Methods and Apparatus; Stock Materials; Adhesive Bonding; Special Chemical Manufactures; Special Utility Compositions; and Photography.	
SPECIALIZED CHEMICAL INDUSTRIES AND CHEMICAL ENGINEERING, GROUP 170—	
R. F. WHITE, Director	5-06-80
Fertilizers; Foods; Fermentation; Analytical Chemistry; Reactors; Sugar and Starch; Paper Making; Glass Manufacture; Gas; Heating and Illuminating; Cleaning Processes; Liquid Purification; Distillation; Preserving; Liquid, Gas, and Solid Separation; Gas and Liquid Contact Apparatus; Refrigeration; Concentrative Evaporators; Mineral Oils Apparatus; Misc. Physical Processes.	
ELECTRICAL EXAMINING GROUPS	
INDUSTRIAL ELECTRONICS, PHYSICS AND RELATED ELEMENTS, GROUP 210—S. W. ENGLE, Director	1-07-80
Generation and Utilization; General Applications; Conversion and Distribution; Heating and Related Art Conductors; Switches; Photography; Motion Pictures; Horology; Acoustics; Recorders; Weighing Scales.	
SPECIAL LAWS ADMINISTRATION, GROUP 220—KENNETH L. CAGE, Director	1-18-80
Ordnance, Firearms and Ammunition; Lubrication; Illumination; Nuclear Reactors; Acoustics, Communications, Optics; Radar; Directional Radio; Torpedoes; Seismic Exploring; Cathode Ray Tube Circuitry; Cryptography; Laser Devices; Radioactive Materials; Powder Metallurgy, Rocket Fuels; Special, Fuel, Explosive and Thermic Compositions; Thermal and Photoelectric Batteries.	
INFORMATION TRANSMISSION, STORAGE, AND RETRIEVAL, GROUP 230—VACANT	1-23-80
Communications; Multiplexing Techniques; Television; Facsimile; Data Processing, Computation and Conversion; Storage Devices and Related Arts.	
RECEPTACLES, SANITATION AND CLEANING, WINDING, AND MEASURING, GROUP 240—	
A. L. SMITH, Director	6-08-79
Receptacles; Bearings; Joint Packing; Conduits; Switches; Presses; Plumbing Fixtures; Textile Spinning; Cleaning; Food Treating; Agitating; Centrifugal Separating; Geometrical Instruments; Sound Recording; Image Projectors; Web Feeding; Winding and Reeling; Cable Hoists; Measuring and Testing; Indicating; Fluent Material Handling.	
ELECTRONIC COMPONENT SYSTEMS AND DEVICES, GROUP 250—S. S. MATTHEWS, Director	4-20-79
Semi-Conductor and Space Discharge Systems and Devices; Electronic Component Circuits; Wave Transmission Lines and Networks; Optics; Radiant Energy; Measuring.	
DESIGN, GROUP 290—KENNETH L. CAGE, Director	12-07-79
Industrial Arts; Household, Personal and Fine Arts.	
MECHANICAL EXAMINING GROUPS	
HANDLING AND TRANSPORTING MEDIA, GROUP 310—B. R. GRAY, Director	1-09-80
Conveyors; Hoists; Elevators; Article Handling Implements; Store Service; Sheet Feeding; Dispensing; Fluid Sprinkling; Fire Extinguishers; Coin Handling; Check Controlled Apparatus; Classifying and Assorting Solids; Boats; Ships; Aeronautics; Motor and Land Vehicles and Appurtenances; Brakes; Railways and Railway Equipment.	
MATERIAL SHAPING, ARTICLE MANUFACTURING, TOOLS, GROUP 320—M. M. NEWMAN, Director	2-06-80
Manufacturing Processes, Assembling, Combined Machines, Special Article Making; Metal Deforming; Sheet Metal and Wire Working; Metal Fusion-Bonding; Metal Founding; Machine Tools for Shaping or Dividing; Work and Tool Holders, Woodworking; Tools; Cutlery; Jacks; Fishing, Etc.; Butchering; and Books and Printed Matter.	
AMUSEMENT, HUSBANDRY, PERSONAL TREATMENT, INFORMATION, GROUP 330—	
R. E. AEGERTER, Director	9-13-79
Amusement and Exercising Devices; Projectors; Animal and Plant Husbandry; Plants; Harvesting; Earth Working and Excavating; Tobacco; Artificial Body Members; Dentistry; Jewelry; Surgery; Toiletory; Printing; Typewriters; Information Dissemination.	
HEAT, POWER, AND FLUID ENGINEERING, GROUP 340—D. J. STOCKING, Director	10-22-79
Power Plants; Combustion Engines; Fluid Motors; Reaction Motors; Pumps; Rotary Engines and Pumps; Heat Generation and Exchange; Refrigeration; Ventilation; Drying; Temperature and Humidity Regulation; Couplings; Gearing; Fluid Handling and Control; Lubrication.	
GENERAL CONSTRUCTIONS, TEXTILES, MINING AND GEARING, GROUP 350—	
G. M. FORLENZA, Director	2-19-80
Building Structures; Racks; Cabinets; Closures; Supports; Furniture; Fasteners; Locks; Pipe Couplings; Joints; Miscellaneous Hardware; Textiles; Sewing Machines; Apparel; Footwear; Earth Engineering; Earth Drilling; Mining; Wells; Roads; Bridges; Tool Driving; Gearing; Machine Elements; Clutches.	

Expiration of patents: The patents within the range of numbers indicated below expire during August 1981, except those which may have expired earlier due to shortened terms under the provisions of Public Law 690, 79th Congress, approved August 8, 1946 (60 Stat. 940) and Public Law 619, 83rd Congress, approved August 23, 1954 (68 Stat. 764), or which may have had their terms curtailed by disclaimer under the provisions of 35 U.S.C. 253. Other patents, issued after the dates of the range of numbers indicated below, may have expired before the full term of 17 years for the same reasons, or have lapsed under the provisions of 35 U.S.C. 151.

Patents Numbers 3,142,841 to 3,146,458, inclusive
Plant Patents Numbers 2,431 to 2,443, inclusive

DEFENSIVE PUBLICATIONS

PUBLISHED OCTOBER 6, 1981

Published at the request of the applicant or owner in accordance with the Notice of Dec. 16, 1969, 869 O.G. 687. The abstracts of Defensive Publication applications are identified by distinctly numbered series and are arranged chronologically. The heading of each abstract indicates the number of pages of specification, including claims and sheets of drawings contained in the application as originally filed. The files of these applications are available to the public for inspection and reproduction may be purchased for 30 cents a sheet.

Defensive Publication applications have not been examined as to the merits of alleged invention. The Patent and Trademark Office makes no assertion as to the novelty of the disclosed subject matter.

T101,101
PROCESS FOR PREPARING A SMALL PARTICLE SIZE
DISPERSION OF A COMPLEX OF
4,4'-METHYLENEDIANILINE WITH A SALT
Irving C. Kogon, 1420 Drake Rd., Wilmington, Del. 19803
Continuation of Ser. No. 97,233, Nov. 26, 1979. This application
Dec. 29, 1980, Ser. No. 220,853
Int. Cl.³ C07C 87/50
U.S. Cl. 564—334

No Drawing. 13 Pages Specification

Preparing a dispersion of methylenedianiline/inorganic salt complex curing agent of small particle size which comprises: (a) agitating while reacting 3 moles of 4,4'-methylenedianiline with not less than 1 mole of a salt selected from the group consisting of sodium chloride, sodium bromide, sodium iodide, lithium chloride, lithium bromide and lithium iodide in the presence of water and a benzenoid hydrocarbon solvent for the methylenedianiline; (b) separating the resulting complex having an average particle size diameter of less than about 10 μ m from the bulk of the hydrocarbon solvent; (c) drying said complex; and (d) dispersing said complex in a substantially nonvolatile liquid carrier that is inert to the complex; with the proviso that steps (c) and (d) can be carried out in any order or substantially simultaneously.

T101,102
PIGMENTED COATING OF POLYESTER/COTTON
SPUN YARNS
John J. P. Turner, 2613 Marhill Dr., Wilmington, Del. 19810
Filed Dec. 29, 1980, Ser. No. 220,808
Int. Cl.³ B05D 1/00, 3/00, 3/02
U.S. Cl. 8—495

No Drawing. 8 Pages Specification

Polyester/cotton 50/50 spun yarns suitable for use as the warp yarns of denim fabric are obtained by first dyeing the yarns

with indigo dye, coating the yarns with a dispersion of a polyol binder and a pigment that imparts coloration similar to indigo-dyed cotton fibers and then drying the yarns, and where appropriate, curing the coated yarn and supplying heat as by singeing to thermosol some of the pigment into the polyester fiber on the surface of the yarn. The polyol binder may be starch but preferably is polyvinyl alcohol in combination with a water soluble polyamide containing secondary amino groups in the polymer chain which have been reacted with epichlorohydrin. The pigment preferably is a combination of Color Index Disperse Blue 56 dye and carbon black.

T101,103
ABSORBED HYDRAZIDE NUCLEATING AGENTS AND
PHOTOGRAPHIC ELEMENTS CONTAINING SUCH
AGENTS
Jasbir Sidhu, 29 Harley Rd., Harrow, Middlesex; Michael J. Simons, and Miroslav V. Mijovic, both of Kodak Works, Wealdstone, Harrow, Middlesex, all of England
Division of Ser. No. 60,549, Jul. 25, 1979, Pat. No. 4,278,748.
This application Feb. 26, 1981, Ser. No. 238,185
Int. Cl.³ C07D 249/00
U.S. Cl. 430—598

No Drawing. 68 Pages Specification

Novel triazole-substituted phenylhydrazide nucleating agents are disclosed as well as silver halide photographic emulsions and elements containing silver halide grains capable of forming an internal latent image having the nucleating agents adsorbed to the surface of the silver halide grains.

REISSUES


OCTOBER 6, 1981

Matter enclosed in heavy brackets [] appears in the original patent but forms no part of this reissue specification; matter printed in italics indicates additions made by reissue.

Re. 30,757 CLOSED LOOP APPARATUS FOR CUTTING SHEET MATERIAL

Heinz J. Gerber, West Hartford, Conn., assignor to Gerber Garment Technology, Inc., South Windsor, Conn.
Original No. 4,133,235, dated Jan. 9, 1979, Ser. No. 790,149, Apr. 22, 1977. Application for reissue Feb. 19, 1980, Ser. No. 122,495

Int. Cl.³ B26D 5/00; B26F 1/38; D06H 7/00
U.S. Cl. 83—74 27 Claims




1. An automatically controlled cutting machine for accurately cutting limp sheet material comprising:
 - a cutting blade having a leading cutting edge, a trailing edge and two sides extending between the leading and trailing edges, the two sides at the leading edge meeting at an angle to form a sharp knife edge for cutting the limp sheet material;
 - a cutting table defining a support surface on which sheet material is positioned in a spread condition for cutting by the cutting blade;
 - motor means for moving the cutting blade and the sheet material relative to one another in cutting engagement;
 - control means connected with the motor means and providing control signals to the motor means for guiding the cutting blade through the material along a predetermined cutting path;
 - sensing means operatively associated with the cutting blade and sheet material for detecting lateral forces applied to the sides of the blade by the material as the sharp leading knife edge of the blade advances through the material in cutting engagement, the sensing means also producing a signal corresponding to the detected lateral forces; and
 - feedback means interconnecting the sensing means and the control means for generating additional control signals to regulate the cutting of the material by the blade along the predetermined cutting path in response to the detected forces.

Re. 30,758
PEDAL-ACTUATED BICYCLE GEAR SHIFT MEANS
Richard A. Lang, 610 18th St., South, Arlington, Va. 22202
Original No. 4,061,046, dated Dec. 6, 1977, Ser. No. 720,396, Sep. 3, 1976. Application for reissue Dec. 14, 1978, Ser. No. 966,474

Int. Cl.³ F16H 7/22; B62M 9/00
U.S. Cl. 474—80 14 Claims

1. In a bicycle provided with front and rear sprockets defining multiple gears and a drive chain extending therebetween, a pair of foot pedals, a shifting mechanism, means to effect shifting of the chain with respect to the gears, the improvement comprising:
 - means cooperatively associated with the foot pedals of the bicycle for controlling the [gear-shifting] chain-shifting means, said [pedal] pedal-associated means including moveable elements on [the] a pedal whereby movement

of [the pedal] said moveable elements to any one of a plurality of preselected positions by the application of vary-




ing foot pressure will effect the requisite shifting of the chain with respect to the gears.

Re. 30,759 METHOD AND APPARATUS FOR PRODUCING AND TRANSPORTING SINGLE AND MULTILAYER CHIPBOARDS

Wolfgang Burkner, Darmstadt, Fed. Rep. of Germany, assignor to Carl Schenck AG, Darmstadt, Fed. Rep. of Germany
Original No. 3,542,629, dated Nov. 24, 1970, Ser. No. 719,924, Apr. 9, 1968. Application for reissue Jan. 24, 1980, Ser. No. 115,117

Claims priority, application Fed. Rep. of Germany, Apr. 11, 1967, 40517

Int. Cl.³ B29J 5/00; B30B 7/02, 15/30, 15/34
U.S. Cl. 264—118 6 Claims



15. Method of producing and transporting chipboards of material consisting primarily of wood particles, chips, fibers or the like and a binding agent, which comprises conveying a plurality of elongated cauls each of which has a main body portion of screen-like metal cloth construction and a ledge at the leading edge thereof extending beyond the main body portion, end to end sequentially past a material dispensing station with the ledge of one caul overlapping the trailing edge of the immediately preceding caul in the conveying direction, continuously spreading material dispensed from the device over the cauls so as to form a continuous mat of the material thereon, transversely severing the mat to form lengths thereof on the respective cauls corresponding substantially to the ultimate length of the chipboard to be formed, feeding the severed mat portions together with the respective cauls into a multitier heating press, subjecting the mat portions and cauls to pressure and heat in the heating press to form the mat portions into chipboards, withdrawing the chipboards and respective cauls together from the heating press, separating the chipboards from the cauls and continuously reconveying the cauls in closed circuit past the material dispensing device.

16. Apparatus for producing and transporting chipboards of material consisting primarily of wood particles, chips, fibers or the like and a binding agent, comprising a material-dispensing device, a plurality of elongated cauls, each of which has a main body

portion of screen-like metal cloth construction and a ledge at the leading edge thereof extending laterally beyond said main body portion, main conveyor means for conveying said cauls end-to-end sequentially past said material-dispensing device so that material is continuously spread from said device over said cauls to form a continuous mat of the material thereon, severing means located adjacent said main conveyor means downstream from said material-dispensing device for transversely severing the mat into lengths thereof on the respective cauls corresponding substantially to the ultimate length of the chipboard to be formed, a multitier heating press located downstream from said severing means for receiving said mat portions and respective cauls therein and subjecting them to heat and pressure to form the mat portions into chipboards, a multitier supply cage for feeding said mat portions and respective cauls to said heating press, means for withdrawing the chipboards and respective cauls together from said heating press, means for separating the chipboards from the respective cauls, and conveyor means for reconveying said cauls in a closed cycle past said material-dispensing device.

Re. 30,760

PROCESS FOR THE PRODUCTION OF SYNTHETIC RESINS CONTAINING ISOCYANURATE GROUPS

Rolf Kubens, Odenthal, and Heinrich Heine, Leverkusen, both of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany
Original No. 4,162,357, dated Jul. 24, 1979, Ser. No. 901,534, May 1, 1978. Application for reissue Jun. 19, 1980, Ser. No. 160,882

Claims priority, application Fed. Rep. of Germany, May 17, 1977, 2722400

Int. Cl.³ C08G 18/76

U.S. Cl. 528—67

9 Claims

1. In a process for the production of [heat-resistant] bubble-free synthetic resins containing isocyanurate groups by the polymerization of organic polyisocyanates in the presence of catalysts which accelerate the trimerization of isocyanate groups, the improvement wherein said polyisocyanate component is a mixture of isomers and/or homologs of polyisocyanates of the diphenylmethane series containing [more than 20%] from 30 to 70%, by weight, of 2,4'-diisocyanatodiphenylmethane.

Re. 30,761

THREE-PHASE DC MOTOR HAVING NON-SUPERIMPOSED ARMATURE COILS


Itsuki Ban, 829, Hizashioizumi-machi, Nerima-ku, Tokyo, and Manabu Shiraki, 171, Shimotsuruma, Yamato-shi, Kanagawa-ken, both of Japan
Original No. 4,107,587, dated Aug. 15, 1978, Ser. No. 614,318, Sep. 17, 1975. Application for reissue Jul. 24, 1980, Ser. No. 171,799

Claims priority, application Japan, Sep. 24, 1974, 49-108865; Sep. 24, 1974, 49-108866; Mar. 6, 1975, 50-26508; May 12, 1975, 50-54725; Jul. 31, 1975, 50-92553

Int. Cl.³ H02K 13/14

U.S. Cl. 318—439

15 Claims



1. In a coreless DC motor comprising a fixed field magnet

(27, 121) having four magnetic poles of N and S magnetized in equal angular widths; a magnetic material (2, 3, 12, 16, 70, 75-1) for closing magnetic paths of said field magnet; a rotating shaft (1, 15, 73) supported by bearings provided to a central portion of said magnetic material; an armature (5, 10, 57) of one of disc- and cylindrical-shapes secured to said rotating shaft so as to be rotatable in said magnetic paths to face against said field magnet poles; three-phase armature coils of lap winding arranged on said armature; and electric circuit means interconnecting said three-phase armature coils in a manner selected from the class consisting of delta-connection and Y-connection for supplying current to said coils, the improvement wherein: said three-phase armature coils comprise three windings (21, 22, 23, 122a-c) each arranged at equal angular interval so as to be non-superimposed with respect to one another on the armature by shifting the coil (23a, 122-1) of one-phase by 180°; each of said coils having an angular width equal to that of said field magnet pole.

Re. 30,762

METHOD AND APPARATUS FOR VIDEO SIGNAL RECORDING


Alexander R. Maxey, Redwood City, Calif., assignor to Arvin Industries, Inc., Columbus, Ind.

Original No. 4,139,873, dated Feb. 13, 1979, Ser. No. 874,118, Feb. 1, 1978. Application for reissue May 2, 1980, Ser. No. 145,937

Int. Cl.³ G11B 21/04, 15/66

U.S. Cl. 360—85

6 Claims



PLANT PATENTS

GRANTED OCTOBER 6, 1981

Illustrations for plant patents are usually in color and therefore it is not practicable to reproduce the drawing.

4,772

MUSCADINE GRAPE

Byard O. Fry, 612 Terrace St., Griffin, Ga. 30223

Filed Jul. 1, 1976, Ser. No. 701,792

The portion of the term of this patent subsequent to Oct. 6, 1998, has been disclaimed.

Int. Cl.³ A01H 5/03

U.S. Cl. Plt.—47

1 Claim

1. The new and distinct hybrid plant variety of muscadine grape as described and illustrated which is primarily distinguished as to novelty by the unique combination of very vigorous vine, large fruit of a light bright greyed orange color wherein said fruit occurs in large clusters of from about 10 to 25 berries having an individual berry diameter of about 0.9 inches, an individual berry fruit sugar content of from about 18.50 to about 22.00 percent and producing a yield of about four (4) tons per acre.

4,773

AFRICAN VIOLET PLANT

Reinhold Holtkamp, Werther Strasse 112, D-4294 Isselburg, Fed. Rep. of Germany

Filed Jul. 25, 1980, Ser. No. 172,219

Int. Cl.³ A01H 5/00

U.S. Cl. Plt.—69

1 Claim

1. A new and distinct cultivar of African violet known by the cultivar name Massachusetts, as described and illustrated,

and particularly characterized by its profuse flowering, with up to 15 stems carrying up to 12 or more individual flowers; lilac flower color, with a deeper purple color near the center; long lasting, non-dropping flowers, and by its compact, vigorous growth habit.

4,774

AFRICAN VIOLET PLANT

Reinhold Holtkamp, Werther Strasse 112, D-4294 Isselburg, Fed. Rep. of Germany

Filed Jul. 25, 1980, Ser. No. 172,397

Int. Cl.³ A01H 5/00

U.S. Cl. Plt.—69

1 Claim

1. A new and distinct cultivar of African violet known by the cultivar name Utah, as described and illustrated, and particularly characterized by its deep blue flower color, vigorous, compact and uniform growth habit, strong upright stems and carrying up to 15 non-dropping flowers, and by its heavy golden yellow pollen sacs which provide a pleasant contrast with the deep blue flowers.

PATENTS

GRANTED OCT. 6, 1981

ERRATA

For CLASS	See PATENT NO.
051-094 R	4,292,699
411-542	4,292,876
251-283	4,293,163
376-159	4,293,379
376-209	4,293,380
376-230	4,293,381
376-308	4,293,382
376-290	4,293,383
376-391	4,293,384
376-283	4,293,385
376-461	4,293,386
336-094	4,293,433
364-200	4,293,941

PATENTS

GRANTED OCTOBER 6, 1981

GENERAL AND MECHANICAL

4,292,687


PROTECTIVE SHOULDER PAD CONSTRUCTION
Stanley Davenport, Jr., Knoxville, Tenn., assignor to The Kendall Company, Boston, Mass.

Filed Jan. 28, 1980, Ser. No. 116,071

Int. Cl.³ A41D 13/00

U.S. Cl. 2-2

6 Claims



1. In a protective shoulder pad having various protective padding attached to two at least semi-rigid front and back panel portions thereof releasably secured to each other, the improvement comprising each of said front panels having at least two attachment means disposed thereon, including a first attachment means on each said front panels disposed on a lower third portion of said panel and a second attachment means on each of said front panels disposed on a middle third portion thereof; a first V-shaped connector strap for connecting one front panel and one back panel from a single common point on said back panel, and a second V-shaped connector strap connecting said other front and back panel from a single common point on said other back panel; said first and second connector straps, each having two free ends and a common crossover point disposed approximately midway between same, said free ends having attachment means disposed near the free end thereof for releasably engaging said connector straps on said attachment means in said front panels, said common crossover point being attached to said back panels at said single common point.

4,292,688

LATCH MECHANISMS

Stafford M. Ellis, East Preston, England, assignor to Elliott Brothers (London) Limited, Chelmsford, England


Filed Jul. 3, 1979, Ser. No. 54,423

Claims priority, application United Kingdom, Jul. 11, 1978, 29428/78

Int. Cl.³ A42B 3/00

U.S. Cl. 2-6

7 Claims



1. A latch mechanism for controlling the relative movement of two hinged members about an axis comprising:
(A) a first latch part fixed to one of the two hinged members;

(B) a second latch part comprising
(i) a first member fixed to the other of said two hinged members, and
(ii) a manually operable second member
(a) having two spaced portions adapted to contact spaced reaction surfaces on said first member; and
(C) a spring arrangement which biases said spaced portions and reaction surfaces toward contact with one another;
(D) the second member having a surface which engages a surface of the first latch part under the action of the spring arrangement, and
(E) the arrangement being such that
(i) pressure applied to the manually operable second member of the second latch part is reacted at one or other of the reaction surfaces accordingly as the applied pressure acts in a sense clockwise or counter-clockwise about the hinge axis to cause said second member to pivot against the bias of the spring arrangement about one or the other of its spaced portions with the result that the engaged surfaces are disengaged and
(ii) under continuing pressure at its second member the said second latch part moves angularly with respect to the said first latch part.

4,292,689

VISORED HAT CONSTRUCTION

Charles E. Townsend, Jr., 11 Ranch Rd., Orinda, Calif. 94563

Continuation-in-part of Ser. No. 943,888, Sep. 19, 1978,

abandoned, and a continuation of Ser. No. 743,749, Nov. 22,

1976, abandoned, which is a continuation-in-part of Ser. No.


585,266, Jun. 9, 1975, abandoned. This application Dec. 19,

1979, Ser. No. 105,462

Int. Cl.³ A42B 1/18

U.S. Cl. 2-12

9 Claims



9. In a hat construction of the described type, a visor formed of non-water-absorbing material outwardly projecting from the main hat body as a substantially flat surface perpendicularly from the surface of the wearer's forehead above eye level and within the horizontal plane of said wearer's forehead, said visor being formed of a section of relatively low density non-water-absorbing material having a thickness in the range between approximately 1/4" and 3/8", the said section being formed with a plurality of relatively large openings extending through the thickness of the section throughout a majority of the entire area of the visor section, the size and angular inclination of said cell openings and the thickness of said visor section being related to one another to substantially prohibit transmittal of direct rays of sunlight through the cellular visor to the eyes of a user and to thereby shade the user's eyes from overhead rays of light transmitted through said visor, the said flat section comprising said visor providing substantially unobstructed lateral vision to said user and said open cell configuration

thereof providing relatively minimal wind resistance to said visor section; the cell openings of said visor section being substantially arcuate elongate in plan with the arcuate length of the cells extending generally parallel to and in the same arcuate path as the arcuate periphery of the visor section.

4,292,690

METHOD OF MAKING A COMPOSITE FUR GARMENT


Michael R. Forrest, and Alfred Kohn, both of New York, N.Y., assignors to Michael Forrest, Inc., New York, N.Y.

Filed Feb. 21, 1978, Ser. No. 879,059

Int. Cl.³ A41D 5/00; C14B 1/00

U.S. Cl. 2—65

6 Claims



1. A method of making a composite fur pelt which comprises the steps of:

- (a) providing a fur pelt having a central area, a lateral portion on each side of said central area, a top portion and a bottom portion;
- (b) slitting said fur pelt with a plurality of rectilinear cuttings as follows:
 - (1) a first and second group of rectilinear cuttings consisting of a series of parallel slits in and on either side of the central area of said pelt extending from the top portion to adjacent the bottom portion of said pelt, said slits being oriented substantially parallel to said lateral portions;
 - (2) a third and fourth group of rectilinear cuttings consisting of a series of angular parallel slits in each of said lateral portions, each of said third and fourth group of rectilinear cuttings extending upwards and outwards from the lower terminus of one of said first or second group of rectilinear cuttings;
 - (3) a fifth and sixth group of rectilinear cuttings consisting of a series of cuttings in said lateral portions adjacent and parallel to said third and fourth group of rectilinear cuttings but lying outside thereof said fifth and sixth group of rectilinear cuttings extending into said bottom portion of said pelt;
- (c) stretching said fur pelt along said plurality of rectilinear cuttings so that said fur pelt is adjusted into a substantially rectangular shaped pelt having a length greater than its width;
- (d) sewing said rectangular shaped pelt along said plurality of rectilinear cuttings so that a rectangularly shaped pelt with structural integrity is formed with a length greater than its width;
- (e) slicing said rectangularly shaped pelt lengthwise into a plurality of substantially equal sized strips of fur of uniform and equal width;
- (f) providing a plurality of equal sized strips of base material;
- (g) alternately sewing together side-by-side fur strips and said base material strips, so that a composite fur pelt is formed, said base material being of a thickness and width

so that the fur in said fur strips overlaps said base material strips and renders said base material strips invisible;

- (h) cutting said composite fur pelt to the shape of at least a portion of a garment, the cut composite fur pelt being dimensioned to give a substantially continuous fur surface with vertical ribbing to said garment when worn by a human.

4,292,691

COMPOSITE FUR PELT AND GARMENT

Michael R. Forrest, and Alfred Kohn, both of New York, N.Y., assignors to Michael Forrest, Inc., N.Y.

Division of Ser. No. 879,059, Feb. 21, 1978. This application

Mar. 8, 1979, Ser. No. 18,709

Int. Cl.³ A41D 5/00; C14B 1/00

U.S. Cl. 2—65

5 Claims



1. A composite fur garment which comprises one or more composite fur pelts made in accordance with the method of:
 - (a) providing a fur pelt having a central area, a lateral portion on each side of said central area, a top portion and a bottom portion;
 - (b) slitting said fur pelt with a plurality of rectilinear cuttings as follows:
 - (1) a first and second group of rectilinear cuttings consisting of a series of parallel slits in and on either side of the central area of said pelt extending from the top portion to adjacent the bottom portion of said pelt, said slits being oriented substantially parallel to said lateral portions;
 - (2) a third and fourth group of rectilinear cuttings consisting of a series of angular parallel slits in each of said lateral portions, each of said third and fourth group of rectilinear cuttings extending upwards and outwards from the lower terminus of one of said first or second group of rectilinear cuttings;
 - (3) a fifth and sixth group of rectilinear cuttings consisting of a series of cuttings in said lateral portions adjacent and parallel to said third and fourth group of rectilinear cuttings but lying outside thereof said fifth and sixth group of rectilinear cuttings extending into said bottom portion of said pelt;
 - (c) stretching said fur pelt along said plurality of rectilinear cuttings so that said fur pelt is adjusted into a substantially rectangular shaped pelt having a length greater than its width;
 - (d) sewing said rectangular shaped pelt along said plurality of rectilinear cuttings so that a rectangularly shaped pelt with structural integrity is formed with a length greater than its width;
 - (e) slicing said rectangularly shaped pelt lengthwise into a plurality of substantially equal sized strips of fur of uniform and equal width;
 - (f) providing a plurality of equal sized strips of base material;
 - (g) alternately sewing together side-by-side fur strips and said base material strips, so that a composite fur pelt is formed, said base material being of a thickness and width
 - (h) cutting said composite fur pelt to the shape of at least a

portion of a garment, the cut composite fur pelt being dimensioned to give a substantially continuous fur surface with vertical ribbing to said garment when worn by a human.

4,292,692

SELF-SETTING ADJUSTABLE HEADBAND


Anthony L. Moretti, San Rafael, and Lester W. Ferris, Tiburon, both of Calif., assignors to E. D. Bullard Company, Sausalito, Calif.

Continuation-in-part of Ser. No. 33,549, Apr. 26, 1979, abandoned, which is a continuation-in-part of Ser. No. 953,481, Oct. 23, 1978, abandoned. This application Mar. 17, 1980, Ser. No. 131,252

Int. Cl.³ A42B 3/00

U.S. Cl. 2—418

17 Claims



1. A self-setting adjustable headband for use in a helmet suspension system or the like, said headband comprising
 - (a) an elongated flexible assembly adapted to be formed into an adjustable generally ring-like configuration with end portions thereof in overlapping relationship;
 - (b) one end portion of said elongated flexible assembly having generally parallel edges with one of said edges of said one end portion provided with a plurality of detent means;
 - (c) the other end portion of said elongated flexible assembly being provided with a buckle member projecting from one side thereof and adapted to receive said one end portion, said buckle member having end members spaced from each other to compressively engage the edges of said one end portion at points spaced further from each other along one edge than along the other edge thereof when received therebetween and a side member spaced from a surface of said other end portion so that the opposite surfaces of said one end portion are loosely engaged by said side member and said surface of said other end portion respectively when said one end portion is received therebetween; and
 - (d) said end members of said buckle being adapted to cooperate with said detent means of said one end portion of said elongated flexible assembly to provide self-setting detent action in the relative movement of said one end portion with respect to said other end portion of said elongated flexible assembly.

4,292,693

LOCKING BAIL STAPEDIAL PROSTHESIS

John J. Shea, Shelby County, and Calvin Griggs, Memphis, both of Tex., assignors to Richards Manufacturing Company, Inc., Memphis, Tenn.

Filed Oct. 5, 1979, Ser. No. 82,195


Int. Cl.³ A61F 1/24, 1/18

U.S. Cl. 3—19

8 Claims

1. In a prosthesis for replacing the stapes of the middle ear, said prosthesis being of the piston type and having a bucket end portion for receiving a portion of the lenticular process of the incus and a bail mounted to pivot about the open end of said bucket portion, the improvement comprising:

means mounted on said bucket portion for permitting overcenter pivotal movement of said bail in one direction and



thereafter preventing overcenter pivotal movement of said bail in the opposite direction.

4,292,694

PROSTHESIS ANCHORING MEANS


James B. Koeneman, Erie, Pa., assignor to Lord Corporation, Erie, Pa.

Filed Jun. 25, 1980, Ser. No. 162,714

Int. Cl.³ A61F 1/24

U.S. Cl. 3—191

8 Claims



1. A securing means for anchoring the stem portion of a joint prosthesis inserted within the medullary canal of the bone adjacent a damaged or diseased skeletal joint, comprising a plurality of resilient elastomeric rings disposed about the circumference of said stem portion at spaced intervals along the length thereof, and a plurality of sections of rigid material attaching at spaced intervals about each of said elastomeric rings and extending radially outwardly therefrom, the combined diameter of said stem portion, said elastomeric rings and said sections of rigid material being greater than the diameter of said medullary canal, said elastomeric rings being compressed upon insertion of said stem portion into said medullary canal and thereby urging said sections of rigid material into contact with said bone for resisting dislocation of said prosthesis within said medullary canal.

4,292,695

PROSTHESIS STEM

James B. Koeneman, Erie, Pa., assignor to Lord Corporation, Erie, Pa.

Filed Jun. 25, 1980, Ser. No. 162,715


Int. Cl.³ A61F 1/24

U.S. Cl. 3—191

9 Claims


1. In a joint prosthesis for replacing a skeletal joint in the human body, the improvement comprising a prosthesis stem having a longitudinal axis and being shaped for insertion into the medullary canal of the bone adjacent said skeletal joint, said stem including a plurality of individual sections formed of a layer of resilient elastomeric material attaching to a layer of rigid material, said individual sections being attached one on top of the other in an offset configuration to form said stem, the outer edges of at least two adjacent ones of said individual

sections defining the diameter of said stem, said diameter of said stem being greater than the diameter of said medullary canal whereby upon insertion of said stem into said medullary



4,292,696
SWIMMER ARRIVAL SIGNAL PANELS
INCORPORATED IN A SWIMMING POOL BULKHEAD
Gordon Berger, Quebec, Canada, assignor to Annesberg Associates N.V., Curacao, Netherlands Antilles
Filed Aug. 30, 1979, Ser. No. 71,370
Int. Cl.³ F04H 3/16, 3/18
U.S. Cl. 4—505

11 Claims




1. A movable swimming pool bulkhead comprising: a rigid structure having top members and bottom members extending lengthwise along the bulkhead; a walkway supported on the top members; roller support means at each end of the bulkhead; removable locating and anchoring means at each end of the bulkhead; a vertical side face on at least one side of the bulkhead which acts to partition the swimming pool, the vertical side face extending between the top members and the bottom members and being divided into substantially equal portions to establish individual swimming lanes, the vertical side face including at least one integrally formed swimmer arrival panel extending between the top members and bottom members within each of the portions of the vertical side face representing individual swimming lanes; means for mounting the integrally formed swimmer arrival panel to the rigid structure so as to be movable relative to the top members; and a switch means located between the rigid structure and the swimmer arrival panel for producing a signal when the swimmer arrival panel is pushed toward the top members as the panel is contacted by a swimmer.

4,292,697
FURNITURE FOR SITTING AND RECLINING
Alfred Alembik, Anastasius-Grüngasse 37/9, Vienna, 18, Austria

Filed Oct. 31, 1979, Ser. No. 89,786
Claims priority, application Austria, Nov. 2, 1978, 7845/78
Int. Cl.³ A47C 17/13
U.S. Cl. 5—18 R

11 Claims



1. In furniture for sitting and reclining with which on a carriage which is movable from the frame, in the seat position two cushions are laid down one above the other and in the reclining position they are placed one behind the other, with a back cushion rigidly connected with the frame and a wedge cushion being provided, which wedge cushion is displaceably and swingably guided on the frame from a maintaining position in the seating position behind the back cushion into a use position in the reclining position in connection with the two cushions which are laid one behind the other on the carriage, the improvement comprising suspension means for connecting an upper edge of the wedge cushion swingably with the back cushion, a lower edge of the back cushion is swingably connected with an inner part of the carriage, said inner part being formed as a bedding box, in the reclining position of the furniture said back cushion and said wedge cushion define a gap therebetween, a covering connected to said wedge cushion and said back cushion covers said gap, said covering is made of upholstery fabric, a wedge cushion frame in which said wedge cushion is mounted, said suspension means comprises pairs of connecting rods, one of said connecting rods of each said pair is swingably fastened to said frame, and the other of said connecting rods is swingably fastened to said wedge cushion frame, said one connecting rod is formed with a longitudinal slot, a joint is disposed between said connecting rods and has a pivot bolt laterally projecting between said connecting rods engaging in said longitudinal slot.

4,292,698
CONVERTIBLE SOFA-BED WITH BACK RESTRAINING MECHANISM


Donald J. Acker, Elkhart, Ind., assignor to J. F. Enterprises, Inc., Wakarusa, Ind.
Filed Aug. 22, 1979, Ser. No. 68,632
Int. Cl.³ A47C 17/00, 1/00

U.S. Cl. 5—45

4 Claims

1. A convertible sofa-bed unit for a vehicle comprising an elongated, horizontal seat section, a supporting frame for said seat section, a back section positioned vertically upwardly from the rear of said seat section in a sofa position and being moveable from said position to a horizontal position along the forward edge of said seat section with the front of the back facing upwardly in a bed position and being on a plane with the top surface of the seat section and with the bottom of the back facing forwardly, and a back section restraining device having a strap connected at one end to the rear of said back section near the top thereof when the back section is in its sofa position and lying over the upper surfaces of the seat and back sections when the back section is in its bed position, a reel mounted on said seat section near the rear thereof and connected to the


other end of said strap, and means for preventing the rotation of said reel upon sudden forward lurching of said back section



and thereby preventing movement of said back section from its vertical position on the rear of said seat section.

4,292,699
GRINDING MACHINE FOR DELIMITED GROOVE MACHINING ON CUTTING TOOLS
Tibor Szabo, 2506 West Ave., 130th, San Leandro, Calif. 94577
Filed Dec. 17, 1979, Ser. No. 104,262
Int. Cl.³ B24B 3/34
U.S. Cl. 51—94 R

13 Claims



1. A grinding device particularly designed for preparing cutting edges of cutting tools comprising: a rotary grinding wheel connected to rotary drive means for rotating said wheel about a rotation axis; said drive means having mounting means for positioning said grinding wheel with respect to a work piece; a work piece table having means for mounting a work piece thereon, said work piece table having articulation means with first and second articulation stops for freely articulating said table on a pivotal table axis generally perpendicular to said rotation axis of said grinding wheel between said stops, and table transport means for reciprocally transporting said table in a linear direction parallel to said table axis; table support means for pivotally supporting said table and said articulation and transport means with respect to said grinding wheel; and, base support means for supporting said table support means, said base support means having table support transport means for selectively transporting said table support means and said table in a linear direction generally parallel to said rotation axis of said grinding wheel and perpendicular to said direction of said table axis, wherein said articulation means and transport means comprise a tilt and slide mechanism having a combination tilt and slide rod enabling pivot articulation and linear transport of said table with respect to said table support means.

4,292,700
SLEEPING BAG LINER
Raymond A. Markel, 1606 Monte Dr., Mandan, N. Dak. 58554
Filed Feb. 11, 1980, Ser. No. 120,507
Int. Cl.³ A47G 9/08
U.S. Cl. 5—413


5 Claims



1. A liner for fitting within a sleeping bag having head and foot portions and for preventing the inside of said bag from becoming soiled, said liner comprising: top and bottom panels having head and foot portions, said panels being joined along foot portion edges and at least partially along both sets of side edges; means, attached to the head portions of said top and bottom panels, for engaging the head portion of said sleeping bag said engaging and retaining means including a hood panel covering the head portion of said top panel and underlying the head portion of said bottom panel, said hood panel having a first fold where a segment of a head portion edge of said hood panel joins a head portion edge of said top panel and a second fold where a different portion of the head portion edge of said hood panel having one side edge joined to the side edge of said top panel which is not completely joined to said bottom panel and a second side of said edge of said hood panel joined to the side edge of said bottom panel which is not completely joined to said top panel, said hood panel having a third fold approximately midway between said first and second side edges; and retaining said panels from moving undesirably toward the foot portion of said bag; means for attaching the foot portions of said panels to the foot portion of said bag to prevent the foot portions of said panels from becoming entangled with the feet of a person sleeping in said bag.

4,292,701
WATER BED CONSTRUCTION WITH ENCLOSURE
John Woychick, Wayzata, Minn., assignor to Land-O-Nod, Minneapolis, Minn.
Filed Jan. 16, 1980, Ser. No. 112,535
Int. Cl.³ A47C 27/08
U.S. Cl. 5—422

3 Claims



1. A water bed construction including: a. support frame; b. a flexible inner spring support member arranged on said frame; c. a water retaining member arranged upon the upper surface of said inner spring support member; d. said water retaining member including a first water retaining portion surrounded and enveloped by an air and water

impervious member having pocket means, with a removable heater, formed on its lower exterior surface; and
e. an enclosure member surrounding at least said inner spring support member and said water retaining member.

4,292,702

SURGE DAMPENED WATER BED MATTRESS


Raymond M. Phillips, 5500 W. 83rd St., Los Angeles, Calif. 90045

Filed Jul. 20, 1979, Ser. No. 59,250

Int. Cl.³ A47C 27/08

U.S. Cl. 5—451

7 Claims



1. A flotation mattress structure including an elongate bladder like envelope of flexible fluid medium impervious sheet material having normally flat horizontal top and bottom walls, vertical side and end walls about and extending between the perimeters of the top and bottom walls, a plurality of elongate vertical imperforate partitions of flexible sheet material in lateral spaced relationship within and extending longitudinally of the mattress with opposite ends spaced from the end walls and defining a plurality of laterally adjacent longitudinally extending tunnels and laterally extending transfer chambers at the ends of said communicating with the tunnels, a volume of fluid medium within and slackerly filling the tunnels and chambers and flow restricting means to slow the flow rate of the medium longitudinally through and into and out of the ends of the tunnels when portions of the mattress are depressed by externally applied forces on the top wall thereof and when said externally applied forces are reduced and removed from the mattress whereby surging and residual wave motion of the medium in the mattress is slowed and buffered, said partitions being serpentine throughout their longitudinal extent across their mean vertical planes whereby the opposing surfaces of adjacent partitions define alternate crests and troughs throughout their longitudinal extent, the crests of adjacent partitions being laterally aligned to define longitudinally spaced venturi in the tunnels and the troughs of adjacent partitions being laterally aligned to define enlarged circulating chambers between the venturi in the tunnels whereby the flow of the medium longitudinally in the tunnels is restricted and slowed entering the venturi and is circulated in and its longitudinal movement is slowed in the circulating chambers between the venturi, said venturi and circulating chambers establishing said flow restricting means.

4,292,703

VENTILATED CUSHIONS

Clarence J. Goguen, 29 Redstone Hill Rd., Sterling, Mass. 01564

Filed Feb. 21, 1979, Ser. No. 13,465

Int. Cl.³ A47C 27/00; B68G 7/00


U.S. Cl. 5—468

4 Claims

1. A tufted cushion comprising an enclosure including top and bottom flexible impervious panels, a connecting box edge of the same material.

compressible solid cushion filling material in the enclosure, and a series of buttons on one panel attached to fasteners

on the other panel, forming deep tufting at spaced intervals throughout the cushion, mutually spaced slits about the box edge, said slits being very small compared to the width of the box edge and being



almost invisible because of their small size and because no material of the box edge is removed, whereby explosion of the cushion in the buttoning process is obviated.

4,292,704

SEWER CLEANING BLADE STABILIZER


Marvin A. Joanis, Sr., 2211 Batson Ave., Rowland Heights, Calif. 91748

Filed May 2, 1980, Ser. No. 145,963

Int. Cl.³ B08B 9/02

U.S. Cl. 15—104.3 SN

3 Claims



1. A sewer cleaning blade stabilizer, comprising, in combination, a universal shaft assembly between a blade and chuck assembly, carrying rotating blades for scraping an inner side of a sewer pipeline, and a cable for pushing said blades through said pipeline; said universal shaft assembly comprising a row of links connected together by universal joints, and a stabilizer along said universal shaft assembly carrying spring loaded arms for frictionally engaging said pipeline inner side.

4,292,705

TONGUE TOOTHBRUSH


James F. Stouffer, Rte. 11, Box 443, Chambersburg, Pa. 17201

Filed May 21, 1979, Ser. No. 41,098

Int. Cl.³ A46B 5/04

U.S. Cl. 15—110

16 Claims



1. A tongue toothbrush, comprising:
a hollow cup-shaped body of a size and shape to envelope the outer portion of a human tongue;
said body being constructed of thin, pliable, continuous, elastic sheet material with opposed upper and lower portions, opposed side portions, a peripheral edge and a forward tip, with respect to the normal tongue position of a standing human;

a plurality of bristles secured to at least one of the upper and lower portions adjacent the tip;
an abrasive dentrifice material embedded within said bristles; said opposed side portions and said tip being completely free of said bristles;
said tip portion being constructed of harder and thicker material than the remainder of said body so as to provide a portion that may be used for the massage of the user's gums;
an easily water-soluble flavoring being secured to said body; a soft abrasive material being secured to one of said upper and lower portions on the opposite side of said bristles from said tip; and
the elasticity of said sheet material being sufficiently elastic to permit expansion and contraction of said body for secure engagement with different sized tongues.

4,292,706

HEAVY DUTY DESOLDERING TOOL


William S. Fortune, 29866 Cuthbert St., Malibu, Calif. 90265

Filed Aug. 20, 1979, Ser. No. 68,118

Int. Cl.³ A47L 5/04

U.S. Cl. 15—341

10 Claims



1. A heavy duty, pneumatically or manually operable hand held desoldering tool comprising:
(a) a hollow cylindrical barrel having tip and rear ends;
(b) a hollow plunger loading cylinder;
(c) a plunger assembly removably mounted on said plunger loading cylinder;
(d) a plunger loading piston concentric with said loading cylinder and including a hollow cylinder slidable within said loading cylinder;
(e) a plunger loading guide disposed concentric with and partially surrounding said plunger loading cylinder;
(f) spring means disposed within said plunger loading cylinder and urging said loading piston outwardly away from said loading cylinder;
(g) trigger means connected to said barrel and externally actuable for locking said plunger loading cylinder in its cocked position and for releasing it; and
(h) heavy duty spring means in said barrel and retained between said plunger and the rear end of said barrel for rapidly returning said plunger rearwards upon release of said trigger means.

4,292,707

FRICTIONAL RETAINER FOR HOLDING A DOOR OPEN

Clarence E. Williams, 2122 W. 450 N., LaPorte, Ind. 46350


Filed Dec. 31, 1979, Ser. No. 108,586

Int. Cl.³ E05F 15/20

U.S. Cl. 16—48.5

6 Claims

1. In combination, a door and a retainer member for holding said door in its open position, said door connected to a frame by a hinge and being rotatable about said hinge between its said open position and a closed position, said retainer member comprising a bracket connected to one of said door and said frame, a rotatable disc part carried by said bracket, and catch



means secured to the other of said door and said frame for engaging said disc part when said door is shifted to its said open position, the rotation of said disc part relative to said bracket being frictionally restrained, said disc part including an annular edge portion, said annular edge portion having a notch

means therein, said notch means for accepting said catch means upon shifting said door into its said open position with said disc being frictionally restrained against rotation to thereby retain said door in such open position, said catch means being released by the rotation of said disc part during urged movement of said door from its said open to said closed position.

4,292,708

HINGES WITH POSITION-LOCKING FILAMENTS


Miroslav Stefanovic, Willowbrook, Ill., assignor to Stocker Hinge Mfg. Co., Brookfield, Ill.

Filed Oct. 9, 1979, Ser. No. 82,638

Int. Cl.³ E05D 11/08, 5/10

U.S. Cl. 16—140

2 Claims



1. In a hinge comprising two hinge leaves, respectively, having knuckles, the inner walls of which form, when aligned, a substantially cylindrical passage in which a full-cylindrical hinge pin is seated, the knuckles of at least one of said leaves being rotatable about said hinge pin, the improvement comprising a piece of filamentary material laid along the hinge pin within said passage and being of a length, and having a thickness, sufficient to provide a frictional fit between the pin and the inner walls of at least one each of the relatively rotatable knuckles of said two hinge leaves, which frictional fit is capable to releasably hold said hinge in an open position.

4,292,709

PICKING ELEMENT FOR A POULTRY PICKING APPARATUS

Martinus P. G. van Mil, Boxmeer, Netherlands, assignor to Stork PMT B.V., Netherlands

Filed Apr. 30, 1980, Ser. No. 145,017

Claims priority, application Netherlands, May 11, 1979, 7903737


Int. Cl.³ A22C 21/02

U.S. Cl. 17—11.1 R

4 Claims

1. A picking element for a poultry picking apparatus, comprising a beaker-shaped support which is to be driven rotatably about the center line thereof and whose cylindrical casing surface and end face are provided with picking fingers and wherein the casing surface is a truncated conical surface of

which the end face is disposed substantially transversely to the axis of rotation, while between the casing surface and the end face are located a number of transition surface areas which lie



at a more acute angle to the center line of the casing surface than the end face and which each carry at least one picking finger, the end face carrying a number of picking fingers substantially parallel to the center line.


4,292,710

MEMBRANE SKINNER

Ray T. Townsend, Des Moines, Iowa, assignor to Townsend Engineering Company, Des Moines, Iowa
Filed Nov. 19, 1979, Ser. No. 95,621
Int. Cl.³ A22B 5/16

U.S. Cl. 17-21

4 Claims



1. A membrane skinning machine comprising, a frame, a gripper roll mounted on said frame, a shoe element mounted on said frame adjacent said gripper roll, said shoe element having a concave surface complementary to the surface of said gripper roll, a cutting blade mounted in said shoe and extending along said gripper roll, and a plurality of helically disposed serrations on the surface of said gripper roll.

4,292,711

PROCESS FOR THE SIMULTANEOUS FILLING AND TURNING OF A TUBULAR CASING WITH AN OUTSIDE COATING

Reinhold Becker, Wiesbaden, Fed. Rep. of Germany, assignor to Hoechst Aktiengesellschaft, Frankfurt am Main, Fed. Rep. of Germany

Filed Mar. 28, 1979, Ser. No. 24,763

Claims priority, application Fed. Rep. of Germany, Mar. 31, 1978, 2813847


Int. Cl.³ A22C 11/02, 13/00

U.S. Cl. 17-49

7 Claims

1. A method for filling a flexible shirred tubular casing with a filling mass, comprising the steps of:

- (a) providing a flexible shirred tubular casing having an inside surface and an outside surface;
- (b) deshirring an end section of the casing by stretching the shirred casing in the longitudinal direction;
- (c) closing the deshirred end section of the casing to form a closed end;
- (d) placing the shirred tubular casing onto the exterior of a substantially straight, dimensionally stable tubular body in such a way that the closed end of the casing covers the end of the tubular body, the deshirred end section of the casing extends along and surrounds the tubular body with the outside surface of the casing being turned toward the



- tubular body and the shirred casing is positioned on the portion of the tubular body surrounded by the deshirred end section of the casing;
- (e) forcing a filling mass under pressure through the interior of the tubular body into the deshirred end section of the casing in a direction toward the closed end of the casing, to fill the deshirred end section of the casing and force the filled casing off of the tubular body, whereby the shirred section of the casing is simultaneously deshirred and inverted to place its outside surface on the inside; and
- (f) during said step (e), preventing contact between the deshirred section of the casing and the inside surface of the shirred section of the casing.

4,292,712

CARD COILER CAN CHANGER


Alvin T. Bonner, Sr., Mauldin, S.C., assignor to John D. Hollingsworth on Wheels, Inc., Greenville, S.C.

Filed Apr. 23, 1979, Ser. No. 32,550

Int. Cl.³ B65H 54/80

U.S. Cl. 19-159 A

4 Claims



1. Automatic card coiler can changer apparatus for removing a full coiler can and positively positioning an empty can beneath a coiler head comprising: guide means for moving an empty coiler can along a predetermined substantially linear path to a position beneath a coiler head; power operated means engaging an empty coiler can on a power stroke thereof and moving same along said predetermined path; said empty coiler can dislodging a full can from position beneath said coiler can on said power stroke;

gripping means fixing said empty coiler can against rotation in said position beneath said coiler head; and wedging means receiving an empty can in a reserve position wedged against said guide means for engagement by said power operated means when the can beneath the coiler head has received a predetermined amount of sliver.

4,292,713

TOOL FOR APPLYING INSULATION TO PIPES


Clyde R. King, Joplin, Mo., assignor to Eagle-Picher Industries, Inc., Cincinnati, Ohio

Filed Sep. 13, 1979, Ser. No. 75,257

Int. Cl.³ B65D 63/06; F16L 33/00

U.S. Cl. 24-24

3 Claims



1. A tool for applying insulation to a pipe comprising, a strap, a keeper fixed to one end of said strap, said keeper including a receptacle to receive a latch, a handle pivoted at one end to the other end of said strap, said handle comprising, a tube closed at one end remote from the pivotal mounting of the handle on the strap, a compression spring in said tube adjacent the closed end thereof, and a rod slidable in said tube, said rod having an end pivoted to said strap, a latch pivoted at one end to said tube intermediate the ends of said tube, said latch having at its other end an element adapted to be received in said keeper, whereby said band may be applied to insulation or the jacket thereof, the latch inserted in said keeper, and the handle swung to lie generally tangential to said strap thereby clamping said band onto said insulation or jacket, said compression spring permitting said latch to accommodate various sizes of insulation.

4,292,714

EASY OPENING AND SECURE CLOSING CLOSURE


Robert J. Walker, 2942 Linden Ave., Berkeley, Calif. 94705

Filed Jan. 14, 1980, Ser. No. 111,901

Int. Cl.³ B65D 77/10, 33/16

U.S. Cl. 24-30.5 R

20 Claims



1. A fastener, which comprises flexible material having a dome-shaped portion which is reversibly deformable from a first fixed configuration extending in one direction above its surrounding material to a second configuration extending in an opposite direction, and a pair of projections formed in said

material, each projection being separated by a transverse bend from the dome-shaped portion, the bend being substantially tangent to an edge of the dome-shaped portion, the projections being spaced apart a sufficient amount to allow insertion and removal of a fastened article when the portion is in one of its configurations and sufficiently close when the portion is in its other configuration to prevent removal of a fastened article from the fastener.

4,292,715

JEWELRY CLUTCH

Lawrence T. Haddon, 22 Overhill Rd., Warwick, R.I.


Continuation-in-part of Ser. No. 916,552, Jun. 19, 1978,

abandoned. This application Jul. 16, 1979, Ser. No. 57,757

Int. Cl.³ A44B 9/10

U.S. Cl. 24-155 C

8 Claims



1. A jewelry clutch comprising a small hollow tubular housing having integral front and rear walls, a coil spring mounted in said housing having an outer diameter slightly smaller than the inner diameter of said housing, said front and rear walls having central openings communicating with the inside of said coil spring, and a pin adapted to fit into said openings and into said coil spring, the outer diameter of said pin being smaller than the inside diameter of said coil spring, said coil spring having means at each end for frictionally engaging said pin when said pin is pushed into said housing.

4,292,716

CONTROLLED DEFLECTION ROLL

Ignazio Marchiori, I-Schio, Italy, assignor to Escher Wyss Limited, Zürich, Switzerland


Filed Oct. 19, 1979, Ser. No. 86,538

Claims priority, application Switzerland, Oct. 25, 1978, 11030/78

Int. Cl.³ B21B 13/02

U.S. Cl. 29-116 AD

5 Claims



1. A controlled deflection roll comprising: a stationary support; a roll shell; means mounting said roll shell for rotatable movement about said stationary support; said roll shell and said stationary support defining therebetween an intermediate space; a plurality of pressure elements, activatable by a pressurized fluid medium, for supporting the roll shell upon the stationary support; said stationary support having a central bore; infeed tubes arranged in said central bore;

said pressure elements forming a number of pressure zones to which there is infed the pressurized fluid medium at different pressures by said infeed tubes arranged in the central bore of said stationary support;
supply line means connected with said infeed tubes at an end of said stationary support;
partition walls arranged in the bore of the stationary support;
said partition walls separating from one another sections of the bore, each of which is correlated to individual ones of said pressure zones and into which open the infeed tubes; said infeed tubes extending in adjacent non-concentric relationship with respect to one another; and
a first section of the bore, located between an end of the stationary support and a first one of said partition walls, containing an intermediate space between the outer walls of the infeed tubes and the inner wall of the bore for the withdrawal of the medium out of the intermediate space between the roll shell and the stationary support of the controlled deflection roll.

4,292,717

METHOD FOR MANUFACTURE OF BEARINGS


Gerald H. Mullen, Burlington, Conn., assignor to Virginia Industries, Inc., Rocky Hill, Conn.

Filed Dec. 26, 1978, Ser. No. 973,544

Int. Cl.³ B21D 53/10

U.S. Cl. 29—148.4 A

6 Claims



1. Apparatus for use in the fabrication of a bearing comprising:

means defining a bore having an axis, said bore having an upper portion with a minimum diameter selected to be larger than the maximum outer diameter of a bearing inner raceway defining member, said bore having a second portion which converges inwardly toward said axis from a first end of said upper portion to a diameter smaller than said maximum outer diameter of the bearing inner raceway defining member; and

a plurality of spaced recesses formed in the wall of said bore of said bore defining member, said recesses having axes which are parallel to the axis of the bore, said recesses each having an upper section which extends downwardly from the second end of said bore defining means upper portion and a second section which extends generally downwardly and inwardly from said upper section, said second sections of said recesses terminating in flat bottoms, said recesses each having a size and shape sufficient to guide balls delivered thereto past the raceway defining upper land of an inner raceway defining member supported in said bore second portion and thereafter inwardly into contact with the raceway surface.

4,292,718

METHOD OF PRODUCING METAL BEARINGS

Yoshio Iijima, Nagoya, Japan, assignor to Daido Metal Company Ltd., Japan

Filed Jul. 19, 1979, Ser. No. 58,992

Claims priority, application Japan, Jul. 27, 1978, 53-91712

Int. Cl.³ B21D 7/04, 53/10

U.S. Cl. 29—149.5 DP

3 Claims



1. A method of making composite metal bearings of semicircular or cylindrical shape from a composite strip of bearing plate consisting of a bearing alloy layer and a backing metal layer, which comprises the steps of:

- (a) feeding a composite strip of bearing plate lengthwise, step by step, past a number of stations arranged to perform necessary operations;
- (b) embossing on opposite sides of the strip in one stroke a pair of transverse grooves substantially V-shaped in cross section in such a manner that the groove on the surface of the backing metal layer is embossed to a depth less than the thickness of the backing metal layer, the groove on the surface of the bearing alloy layer is embossed to a depth equal to or less than the thickness of the bearing alloy layer, and the pair of grooves are formed in generally parallel alignment with each other;
- (c) additionally subjecting the groove formed by embossing by the preceding step on the surface of the bearing alloy layer to a cutting step so as to enlarge the size of the groove in both its depth and width so that the groove extends beyond the interface between the bearing alloy layer and the backing metal layer and further into the backing metal layer; and
- (d) bending and forming, between a set of punch and dies, a blank of the composite bearing plate provided with said grooves of desired shape and size directly into a partly severed blank having final cross sectional configuration, and then completely severing said blank from the rest of the strip of said composite bearing plate in such a manner that said bending, forming and subsequent severing of said blank are performed by a one stroke operation.

4,292,719

ENGINE VALVE LIFTER SERVICE TOOL


Francis D. Britton, Jr., 200 Railroad Ave., Henry, Ill. 61537

Filed Dec. 26, 1979, Ser. No. 106,559

Int. Cl.³ B26P 15/00

U.S. Cl. 29—156.4 R

9 Claims



9. A method of removing a defective hydraulic valve lifter (15) from an engine (16) and installing a new lifter (15) in said engine (16) comprising the steps of:

- providing a valve lifter service tool (10) having a valve lifter engaging portion (12) and an actuating portion (11);

inserting said service tool (10) into the distributor opening (20) of said engine (16);
encircling said defective lifter (15) with said engaging portion (12);
actuating said actuating portion (11) to engage said defective lifter (15) with said engaging portion (12);
removing said service tool (10) and said defective lifter (15) from said engine (16) through said opening (20);
removing said defective lifter (15) from said engaging portion (12);
installing a new lifter (15) in said engaging portion (12);
inserting said service tool (10) and said new lifter (15) into said opening (20);
p1 installing said new lifter (15) into position within said engine (16) using said tool (10);
releasing said new lifter (15) from said tool (10); and
removing said tool (10) from said opening (20).

4,292,720

METHOD OF MAKING REVERSING VALVE CONSTRUCTION AND PARTS THEREFOR

Werner R. Bauer, Richmond, Va., assignor to Robertshaw Controls Company, Richmond, Va.


Division of Ser. No. 958,030, Nov. 6, 1978, Pat. No. 4,240,469, which is a continuation-in-part of Ser. No. 825,958, Aug. 19, 1977, Pat. No. 4,188,975. This application Dec. 6, 1979, Ser. No. 100,729

The portion of the term of this patent subsequent to Dec. 30, 1997, has been disclaimed.

Int. Cl.³ B23P 15/00

U.S. Cl. 29—157.1 R

16 Claims



1. In a method of making a reversing valve construction having a housing means provided with a chamber carrying a movable valve member therein that controls port means of a valve seat means of said housing means through the relative position of passage means of said valve member relative to said port means, the improvement comprising the steps of forming a one-piece flexible sealing skirt to be carried by said valve member and extend outwardly therefrom in a cantilevered manner adjacent said valve seat means, providing said flexible sealing skirt with exposed surfaces so as to be exposed to fluid pressure in said chamber that will act directly thereon and cause said flexible skirt to flex and engage said valve seat means in a manner to tend to sealingly conform to the contour of said valve seat means and thereby seal said passage means to said valve seat means while permitting sliding movement therebetween, and disposing biasing means in said housing means to act on said flexible skirt to urge the same toward said valve seat means.

4,292,721

CRIMPING DEVICE FOR USE IN ASSEMBLING AN OVERTRAVEL SPRING ASSEMBLY FOR SLACK ADJUSTER

Roger J. Weseloh, South Holland; Wajih Kanjo, Midlothian, and Syed Karim, Sauk Village, all of Ill., assignors to American Standard Inc., Chicago, Ill.

Filed Apr. 21, 1980, Ser. No. 142,569

Int. Cl.³ B23P 11/00


U.S. Cl. 29—243.52

8 Claims

1. Crimping apparatus for crimping opposite annular ends of

a housing member for an overtravel spring assembly for use in a slack adjuster, said crimping apparatus comprising:

- (a) a support frame;
- (b) power chuck means mounted vertically on a lower portion of said support frame and having a plurality of equidistantly spaced, radially movable jaws on which respective crimping blades are removably secured for movement therewith, said blades being operable upon inward radial movement thereof for crimping said housing member at one end;
- (c) a base member concentrically secured to said chuck means;
- (d) a post member concentrically secured to said base member and on which said housing member is removably installed in a crimping position in which a lower end thereof rests against said base member;



- (e) power cylinder means including a piston rod and mounted vertically on an upper portion of said support frame opposite said chuck means and in axial alignment therewith; and
- (f) a spring pressure assembly secured to said piston rod and movable therewith;
- (g) said spring pressure assembly being operable, upon actuation of the power cylinder means, out of a retracted position to an extended position in which the upper annular rim of said housing member is engaged by the spring pressure assembly for securing the housing in said crimping position;
- (h) said power chuck means being operable responsively to actuating pressure for effecting radial inward movement of said jaws and blades.

4,292,722

RENEWABLE NUT FOR A LEAD SCREW DRIVE AND METHOD OF MAKING SAME

Daniel A. Worsham, San Jose, Calif., assignor to Pacific Western Systems, Inc., Mountain View, Calif.

Filed Aug. 13, 1979, Ser. No. 66,095

Int. Cl.³ B22D 19/10; B23P 7/00


U.S. Cl. 29—402.21

9 Claims

1. In a method for renewing a lead screw drive mechanism to remove backlash therefrom, the steps of:
threadably mating a lead screw with a nut, the threaded portion of said nut being made of a core material to be melted in place;
heating the threaded core portion of said nut while in threadable engagement with the threaded portion of said lead screw to cause said threaded portion of said nut to melt and to flow and to conform to the thread profile lead screw; and

allowing the melted core portion of said nut to cool and to solidify while threadably mated with said lead screw such that the threaded portion of said nut is renewed to conform to the thread profile of said lead screw, thereby renewing the thread of the nut and reducing backlash of the lead screw drive mechanism.

6. In a renewable lead screw drive mechanism:
lead screw means having an elongated externally threaded body;
nut means having an internally threaded core portion for threadably mating with the external thread of said lead



screw, said core portion of said nut being made of a material having a relatively low melting temperature;
heating means for heating said core portion of said nut means while said nut means is in threadable engagement with the thread of said lead screw to cause said core portion of said nut means to melt and to flow and to conform to the thread profile of said mated lead screw such that as said melted core portion of said nut means cools it will solidify for conforming the threaded portion of said nut to the thread profile of said lead screw means, thereby renewing the thread of said nut and reducing backlash of the lead screw mechanism.


4,292,723

SHEAVE AND METHOD OF PROVIDING SAME
David A. Rauscher, Columbia, S.C., assignor to Cable Conveyor Systems, Inc., Columbia, S.C.

Filed Nov. 1, 1979, Ser. No. 90,485
Int. Cl.³ B23P 6/00, 6/04; B29D 15/00

U.S. Cl. 29—402.01

8 Claims



1. A method of reconditioning a sheave having an annular rim body including first and second peripheral flanges between which a peripheral trough is defined, said method comprising the steps of removing a first annular portion of said rim body including said first peripheral flange and extending radially inwardly beyond the original location of the bottom of the peripheral trough, removing a second annular portion of said annular rim body including said peripheral trough and a portion of said second peripheral flange, said second annular portion extending radially inwardly beyond the original location of the bottom of said peripheral trough but extending radially inward a distance less than the inward extent of said first annular portion, removing a third annular portion of said annular rim body comprising a radially outermost portion of said second flange positioning said sheave in a mold, casting liquid uncured plastic in the mold to fill the space previously occupied by the removed portions of said annular rim body and to also extending radially therebeyond, permitting said liquid plastic to cure and harden and machining said plastic to define first and second peripheral flanges separated by a peripheral trough.


4,292,724 ARRANGEMENT FOR CONSTRUCTING SURFACES AND BODIES

Paul DiMatteo, Huntington, N.Y., assignor to Solid Photography, Inc., Melville, N.Y.

Filed Nov. 5, 1979, Ser. No. 91,142
Int. Cl.³ B23P 17/00; B32B 31/00

U.S. Cl. 29—418

8 Claims



1. A method for constructing a predetermined surface comprising the steps of: defining cross-sections of said surface; generating a substantially planar element for each cross-section from base material having a substantially rectangular cross-section by removing material within a gap following the outline of the cross-section, said gap being discontinuous and being interrupted by tabs connecting the planar element to the base material, said tabs comprising material not removed in said gap during said material removing step; arranging locations of said tabs so that said tabs are in staggered relationship to each other when the planar elements are stacked against each other; attaching the planar elements to one another and stacking the planar elements in predetermined sequence to form such surface, the sequence of the stacked elements corresponding to the sequence of the cross-sections of said surface.

4,292,725


METHOD OF PRODUCING AN OBJECT OF FIBER REINFORCED METAL MATERIAL

Leif Larsson, Trollhättan, and Richard Warren, Landvetter, both of Sweden, assignors to Volvo Flygmotor AB, Trollhättan, Sweden

Filed Apr. 12, 1979, Ser. No. 29,516
Claims priority, application Sweden, Apr. 17, 1978, 7804337
Int. Cl.³ B23P 17/04

U.S. Cl. 29—419 R

9 Claims



1. A method of manufacturing a fiber reinforced metal object having a substantially uniform density metallic matrix material throughout, comprising the following steps:
positioning each of a plurality of separate, previously drawn fibers of a tungsten-based metallic material in a separate tube of metallic matrix material;
positioning each of said fiber-filled tubes of metallic matrix material within a single casing having a configuration

substantially similar to the configuration of said metal object;
isostatically pressing said casing and said fiber-filled tubes positioned therein at a temperature above ambient room temperature and below the lowest temperature necessary for melting both said fibers and said matrix material, thereby causing plastic deformation of said fiber-filled tubes into an object having the desired configuration of said metal object with substantially uniform density metallic matrix material throughout.

4,292,726


INGOT MOLD RECONDITIONING PROCESS

Patsie C. Campana, 2614 Sherwood Dr., Lorain, Ohio 44053
Filed Jan. 28, 1980, Ser. No. 116,170

Int. Cl.³ B23P 6/00

U.S. Cl. 29—527.6

7 Claims



1. A process for reconditioning an ingot mold after some predetermined period of use for purposes of extending the useful life thereof wherein said mold is of a type having an external peripheral wall and opposed mold top and bottom ends with an internal mold cavity having at least one open end extending at least substantially between said mold top and bottom ends, said cavity having a predetermined first volume defined by a first length extending between opposed ends of said cavity and a predetermined first cross-sectional area disposed normal to said first length between cavity side walls, said process comprising the steps of:

- casting a plurality of first ingots in said mold having approximately said first volume;
- cutting each of said first ingots into a plurality of first bars generally equal to each other;
- machining said mold generally transversely of said first length following casting of a plurality of said first ingots therein for removing an area of mold deterioration adjacent said cavity open end while controlling said machining so that said cavity first length is reduced to some predetermined second length for providing said cavity with a second volume comprising some reduced multiple of said first volume;
- casting a plurality of second ingots having approximately said second volume; and,
- cutting each of said second ingots into a plurality of second bars which are lesser in number and which generally have the same dimensional and volume characteristics as said first bars.

4,292,727

AUTOMATIC INSERTION EQUIPMENT

Richard B. Maxner, Danvers, Mass., assignor to USM Corporation, Farmington, Conn.

Filed Feb. 25, 1980, Ser. No. 124,084

Int. Cl.³ H05K 3/30; B21F 11/00


U.S. Cl. 29—566.3

8 Claims

1. A cut-clinch mechanism including a fixed knife and a movable knife and means to drive said movable knife into cutting relationship with said fixed knife, the improvement which comprises:

means linking said movable knife to said drive means, said

linking means allowing a limited movement of said movable knife relative to said drive means and sensing means



to determine if said movable knife has achieved said limited movement.

4,292,728

METHOD FOR MANUFACTURING SEMICONDUCTOR INTEGRATED CIRCUITS UTILIZING SPECIAL CONTACT FORMATION

Norio Endo, Yokohama, Japan, assignor to Tokyo Shibaura Denki Kabushiki Kaisha, Kawasaki, Japan


Filed Jun. 13, 1979, Ser. No. 48,090

Claims priority, application Japan, Jun. 13, 1978, 53-71088

Int. Cl.³ H01L 21/283, 21/31

U.S. Cl. 29—571

6 Claims



1. A method for manufacturing semiconductor integrated circuits, comprising the steps of:

- forming a field oxide layer on a semiconductor substrate;
- partially removing the field oxide layer to expose a predetermined part of said semiconductor substrate;
- forming in said exposed part of the semiconductor substrate insulated gate field effect transistors having insulated gates and source and drain edge regions adjacent to said field oxide layer;
- forming a first insulating layer which has a different etching rate from said field oxide layer on the overall surface of said field oxide layer and said transistors;
- forming on the first insulating layer a second insulating layer which has a different etching rate from said first insulating layer;
- removing portions of said second insulating layer which are situated above the edge part of said field oxide layer and parts of said source and drain regions distant from the gate by using an etching material which substantially only etches said second insulating layer, and
- etching the first insulating layer by using the second insulating layer as a mask, thus forming contact holes to the field effect transistors.

4,292,729

ELECTRON-BEAM PROGRAMMABLE SEMICONDUCTOR DEVICE STRUCTURE


Michael W. Powell, Mesa, Ariz., assignor to Motorola, Inc., Schaumburg, Ill.

Division of Ser. No. 834,081, Sep. 19, 1977, Pat. No. 4,190,849. This application Aug. 23, 1979, Ser. No. 68,991

Int. Cl.³ H01L 21/04

U.S. Cl. 29—571

2 Claims



1. A method for manufacturing a semiconductor device comprising the steps of: providing a semiconductor substrate; providing a conductive region isolated from said substrate and capable of storing charge from an electron beam; forming an insulator layer overlying said conductive region and adapted to allow penetration of electrons from said electron beam; forming a registration element in said substrate, said registration element allowing registration between said conductive region and said electron beam; and charging said conductive region with an electron beam to alter operation of said semiconductor device.

4,292,730

METHOD OF FABRICATING MESA BIPOLAR MEMORY CELL UTILIZING EPITAXIAL DEPOSITION, SUBSTRATE REMOVAL AND SPECIAL METALLIZATION


Kenneth A. Ports, Indialantic, Fla., assignor to Harris Corporation, Melbourne, Fla.

Filed Mar. 12, 1980, Ser. No. 129,913

Int. Cl.³ H01L 21/283, 21/302

U.S. Cl. 29—577 C

5 Claims



1. In a method of fabricating an integrated circuit having mesa devices including forming an epitaxial layer on a substrate, forming a top support on said epitaxial layer and removing said substrate, the improvement comprising:

applying a backside metallic layer to the bottom of said epitaxial layer;

forming a bottom support on said backside metallic layer;

removing said top support;

etching said epitaxial layer to form a plurality of discrete mesa;

etching said backside metallic layer to form a discrete backside contact for each mesa;

forming a first top insulative layer;

applying first interconnect layer and delineating to form interconnects on said first insulating layer between said mesa and contacts to said mesa;

forming a second top insulative layer; and

applying a second interconnect layer and delineating to form interconnects on said second insulating layer between said mesa and contacts to surface regions of said mesa.

4,292,731

TUBE REMOVAL MACHINE


Burt Filer, New Hope, Pa., assignor to Sandra Lee Filer, New Hope, Pa.

Filed Mar. 31, 1980, Ser. No. 135,220

Int. Cl.³ B23P 15/26

U.S. Cl. 29—726

18 Claims



1. A tube removal machine for positioning in front of a tube sheet comprising

a housing,

a longitudinally elongated member carried in said housing and extending from said tube sheet for engagement under pressure along one side face portion of a tube to be removed, and

means in said housing for advancing the tube to be removed, said means including a driving member carried on an endless chain having a rigid portion for gripping engagement with the opposite side face portion of said tube from that with which said elongated member is in engagement.

4,292,732

APPLICATOR FOR METAL STRAIN RELIEF CLAMP

John J. Tucci, Winston-Salem, N.C., assignor to AMP Incorporated, Harrisburg, Pa.

Filed Jun. 7, 1979, Ser. No. 46,414

Int. Cl.³ B23P 19/00; H01R 43/04


U.S. Cl. 29—749

5 Claims

1. In a tool for closing a cable clamp portion of an electrical connector onto a multiple wire electrical cable, the tool having a work station supporting said connector and said clamp portion, a housing mounting: a ram carrying a toolhead for engaging and closing said clamp portion, a drive mechanism for reciprocating said toolhead toward and away from said clamp portion, a rotatable shaft mounting said pinion and mounting a lever which is manually pivotable for reciprocating said shaft in a first direction and a return mechanism for rotating said shaft in a second direction upon manual release of said lever, the improvement comprising:

a cable engaging first means projecting from said toolhead for engaging and thrusting a cable internally of said clamp portion prior to closure thereof by said toolhead,

said housing being pivotally mounted to said work station, second means for limiting pivotal movement of said housing in said first direction and for positioning said toolhead for reciprocation together with said rack toward said clamp portion, and



said housing being pivotable in a second direction by a shift in gravity resulting from manual release of said lever and pivoting of said lever by said return mechanism.

4,292,733

APPARATUS FOR COUPLING A PAIR OF ELONGATE SLIDE FASTENER STRINGERS

Yoshitaka Iimura, Kurobe, Japan, assignor to Yoshida Kogyo, K.K., Tokyo, Japan


Filed Feb. 14, 1980, Ser. No. 121,319

Claims priority, application Japan, Feb. 20, 1979, 54-20856[U]

Int. Cl.³ B23P 19/04

U.S. Cl. 29—766

9 Claims



1. An apparatus for coupling a pair of elongate slide fastener stringers while being fed longitudinally along a pair of respective paths, comprising:

- a frame;
- a pair of first spaced rolls rotatable on a first shaft on said frame;
- a pair of second spaced rolls rotatable respectively on a pair of second shafts on said frame, which extend transversely to said first shaft;
- a pair of third rolls rotatable respectively on a pair of third shafts on said frame, which extend substantially parallel to said second shafts and are spaced from each other by a greater distance than that between said pair of second shafts;
- a pair of fourth spaced rolls rotatable respectively on a pair of fourth shafts on said frame, which extend transversely to said third shafts;
- a coupling member on said frame, having a pair of converging guide channels for meshing the stringers as they pass therethrough;
- means for withdrawing the slide fastener stringers as they are coupled together by said coupling member; and
- said first, second, third, fourth rolls, said coupling member and said withdrawing means being arranged in the

order named for guiding the stringers along their respective paths into said coupling member, said third rolls enabling the stringers to pass along a pair of converging paths leading respectively to said converging guide channels in said coupling member, and said fourth rolls allowing the stringers by widthwise engagement therewith to advance in a plane in which said converging guide channels lie.

4,292,734

COMMONLY ACTUATED IN-LINE ASSEMBLY MACHINE


Douglas L. Swanson, McKean, Pa., and Norman H. Yeo, Georgetown, Mass., assignors to Swanson-Erie Corporation, Erie, Pa.

Filed May 25, 1979, Ser. No. 42,306

Int. Cl.³ B23P 19/00; B23Q 7/03

U.S. Cl. 29—791

11 Claims



1. An in-line assembly machine having a plurality of work stations, at least three of which are arranged in the same straight line, comprising:

- a camshaft oriented along an axis;
- two sets of cams fixed to said camshaft;
- an upper elongated tool plate oriented parallel to said camshaft axis;
- a lower elongated tool plate oriented parallel to said camshaft axis, said upper and lower tool plates each being mounted to move reciprocally with respect to one another to commonly actuate tooling associated with the machine at a plurality of work stations;
- a first set of lifting rods mounted to reciprocate said upper elongated tool plate;
- a second set of lifting rods mounted to reciprocate said lower elongated tool plate;
- a first set of cam followers mounted to said first set of lifting rods and mounted to follow one set of said cams;
- a second set of cam followers mounted to said second set of lifting rods and mounted to follow the other set of said cams, each of said sets of followers cooperating with a respective set of said cams to translate the rotational motion of said cams into reciprocation of said lifting rods, so that rotation of said camshaft causes said upper and lower elongated tool plates to reciprocate, thereby providing the common actuation desirable to perform operations on parts to be assembled.

4,292,735

METHOD OF MANUFACTURING A COPLANAR PHOTOCOUPLER

Jacques C. Thillays, Herouville St. Clair, France, assignor to U.S. Phillips Corporation, New York, N.Y.


Filed Jun. 15, 1979, Ser. No. 49,015

Claims priority, application France, Jun. 16, 1978, 78 18081

Int. Cl.³ G02B 27/00, 5/14; H01L 31/12

U.S. Cl. 29—854

7 Claims



1. A method of making a plurality of photoco-uplers each having a light emitter, a photosensitive receiver and an optical element comprised of a photoconductive plastic covered with a metal mirror for coupling light from said light emitter to said photosensitive receiver, said method comprising the steps of providing a sheet of deformable metal having a pattern of deep drawn recesses formed therein, said recesses each having a shape corresponding to that desired for the mirror, filling said recesses with said plastic in liquid form, curing said plastic so that it solidifies in and adheres to the metal surface of said recesses to thereby form a plurality of said elements wherein the metal surfaces of said recesses define said mirrors, thereafter separating said elements from each other, and attaching one of said light emitters and one of said photosensitive receivers to each of said elements to thereby form a plurality of said photoco-uplers.

4,292,736

METHOD FOR MAKING JACK TYPE RECEPTACLES


Donald W. K. Hughes, Mechanicsburg, and Ronald W. Myers, Landisburg, both of Pa., assignors to AMP Incorporated, Harrisburg, Pa.

Continuation-in-part of Ser. No. 940,536, Sep. 8, 1978, Pat. No. 4,221,458. This application Dec. 5, 1979, Ser. No. 100,669

Int. Cl.³ H01R 43/00

U.S. Cl. 29—884

11 Claims



1. A method of manufacturing an electrical connector receptacle of the type comprising an insulating housing having a plug-receiving end and a rearward end, a plug-receiving opening extending into said plug-receiving end, said opening having opposed internal sidewalls and opposed internal endwalls, said housing having oppositely facing external sidewalls which are substantially parallel to said internal sidewalls, a plurality of electrical conductors in side-by-side spaced-apart relationship, each of said conductors comprising a contact spring extending from one of said internal sidewalls at a location adjacent to said plug-receiving end diagonally into said opening and towards the opposite internal sidewall, and each conductor having a

lead portion extending from said plug-receiving end towards said rearward end, said method comprising the steps of:

producing said housing as a one-piece molded part having a plurality of side-by-side channels extending from said plug-receiving end towards said rearward end in the one of said external sidewalls which is adjacent to said one internal sidewall,

manufacturing said conductors as a continuous flat sheet metal strip comprising a carrier strip means having at spaced intervals groups of said conductors extending in side-by-side coplanar relationship from one side edge of said carrier strip means with each group containing the number of conductors required for one of said receptacles, positioning said housing adjacent to one of said groups of conductors with intermediate portions of said conductors in alignment with said channels, and

moving said one group of conductors normally of their axes towards said housing and inserting said intermediate portions into said channels, and bending first end portions of said conductors into said plug-receiving opening whereby said first end portions function as said contact springs and said intermediate portions of said conductors function as said lead portions.

4,292,737

DRY SHAVER WITH DIFFERENTIALLY BIASED INNER CUTTER AND BASE MEMBERS

Charles C. Packham, Berkshire, England, assignor to The Gillette Company, Boston, Mass.


Filed Dec. 3, 1979, Ser. No. 99,247

Claims priority, application United Kingdom, Dec. 11, 1978, 48009/78

Int. Cl.³ B26B 19/06

U.S. Cl. 30—43.92

8 Claims



1. A dry shaver having a drive means for providing reciprocating motion and including a casing on which is carried a cutter assembly comprising a reciprocating inner cutter driven by said drive means, said inner cutter co-operating with a flexible, arched foil against which said inner cutter is pressed by spring means, wherein said foil and said inner cutter are mounted on a common base member, said foil being attached along its longitudinal edges to said base member, said spring means acting between said base member and said inner cutter, wherein said base member is mounted on said casing for movement toward and away from said casing in directions transverse to the direction of reciprocation of said inner cutter, and said base member is urged away from said casing by resilient means whose spring force is less than that of the said spring means said resilient means being independent of said spring means and said drive means.

4,292,738
KNIFE

Hiroshi Osada, Seki, Japan, assignor to Kai Cutlery Center Co., Ltd., Seki, Japan


Filed Jan. 16, 1980, Ser. No. 112,515

Claims priority, application Japan, Jan. 20, 1979, 54-4540[U]; May 21, 1979, 54-66905[U]

Int. Cl.³ B26B 5/00

U.S. Cl. 30—162

6 Claims



1. A knife having an elongated holder having a front end, a rear end, a top wall, a bottom wall, and two side walls and being provided with an interior, longitudinally extending channel the frontwardmost end region of which is located rearwardly of said front end of said holder, said channel being open to the exterior through a longitudinal slot provided in said top wall of said holder and having its frontwardmost end located a predetermined distance rearwardly of said frontwardmost end region of said channel, said holder further being provided at said front end thereof with an opening which communicates with said frontwardmost end region of said channel, a blade carrier including a slider slidably received by said channel and having a front end portion and a body portion disposed within said channel and a finger portion which is unitary with said body portion through said slot and is located exteriorly of said holder in overlying relation to said top wall, and a blade extending into said channel through said opening and having a base portion detachably secured to said blade holder through an engagement of a projection formed on said front end portion of said slider and an aperture formed in said base portion of said blade; characterized in that:

said slider has a rear end portion in sliding contact with the interior surface of said bottom wall of said holder, and said body portion, said rear end portion and said front end portion of said slider constitute a unitary, substantially rigid structure that is entirely confined within said holder, resilient means located entirely within the confines of said holder is operatively interposed between said slider and at least one of the interior wall surfaces of said holder for resiliently biasing said front end portion of said slider having said projection located thereat away from said interior surface of said bottom wall of said holder and so as to bring said projection into engagement with said aperture in said base portion of said blade,

said finger portion in its forwardmost end region has a transverse extension overlying and in sliding contact with at least a portion of said top wall of said holder alongside said slot for normally inhibiting depression of said finger portion and therewith of said front end portion of said slider to prevent disengagement of said projection from said aperture, and

said slot adjacent said frontwardmost end thereof is provided with a transverse enlargement shaped and dimensioned to permit entry of said transverse extension of said finger portion therein when the latter is moved to dispose said transverse extension in overlying relation to said enlargement of said slot for enabling depression of said finger portion and therewith of said front end portion of said slider to disengage said projection from said aperture against the resilient biasing force of said resilient means.

4,292,739


LIQUID MEASURE DIP STICK

Hugh L. Dobbins, 110 Aspenwood Dr., Riverdale, Ga. 30296

Filed Aug. 3, 1979, Ser. No. 63,576

Int. Cl.³ G01B 5/18

7 Claims



1. A liquid height measuring device vertically insertable in a petroleum product storage tank for measuring depth comprising:

an elongated calibrated wood stick having an elongated vertical surface with a groove formed therein, said stick extending at least twelve feet;
a transparent narrow hollow tube mounted on said groove and extending between a bottom portal and a top end;
a valve element having an upper surface in confronting relationship with said portal;
lifting means for moving said valve element between an open and closed position including a wire connecting at one end to said element, a bracket mounted on said stick adjacent said top end and having two spaced apart L-shaped slots, and a handle having an axle attached to the other end of said wire and movable between an upper position in said slots holding said valve element in a closed position and a lower position holding said valve element in an open position;
spring means for biasing said valve element toward said open position.

4,292,740

SELF-ACTUATED DISPLACEMENT TRANSDUCER

Arthur D. Vis, Warren, and Billie Feinberg, Oak Park, both of Mich., assignors to Candid Logic, Inc., Hazel Park, Mich.

Filed Jun. 7, 1979, Ser. No. 46,586

Int. Cl.³ G01B 3/22

17 Claims

U.S. Cl. 33—172 E


1. A self-actuated displacement transducer probe assembly comprising:

a housing comprising a length of tubing having an internal bore of uniform internal diameter extending the full length of the tubing;
a displacement transducer mounted within said internal bore at one end of said tubular housing, said displacement transducer including a movable element means for generating an electrical signal corresponding to the position of said movable element;
an actuator arrangement mounted within said internal bore at the other end of said tubular housing, said actuator arrangement including a probe extension shaft slidably mounted in said tubular housing having one end extending out of said other end of said tubular housing;

means securing said probe extension shaft to said movable element;

said actuator arrangement further including means generating a force acting on said probe extension shaft urging said probe extension shaft in a direction out of said tubular housing;

return spring means urging said probe extension shaft to a return position within said tubular housing;



whereby actuation of said actuator arrangement causes said probe to be extended from said tubular housing in order to cause movement of said movable element therewith thereby generating electrical signals corresponding to the position of said probe extension shaft.

4,292,741

UNIVERSAL LEVEL VIAL HOLDER

Louis Scandella, Marnay, France, assignor to Stanley Mabo, S.A., Besancon, France


Filed Feb. 21, 1980, Ser. No. 123,193

Claims priority, application France, Feb. 26, 1979, 79 05430; Jan. 14, 1980, 80 00944

Int. Cl.³ G01C 9/28

U.S. Cl. 33—379

9 Claims



1. A holder for mounting a level vial within a slot in a web of an extruded or molded spirit level said holder comprising an elongated base plate having a generally planar back wall engageable with one face of the level web and a pair of support legs extending upwards from said base plate, each of said support legs having an end provided with a transversal perimeter for receiving said vial for positioning in said slot, said perimeters being spaced by a distance less than the longitudinal dimension of said slot and having a common axis offset from the plane of said back wall, said perimeter being provided with support means spaced laterally from said back wall approximately a distance equal to the thickness of said web and adapted to contact the opposite side of said web from that contacted by said back wall for supporting said holder on said level and said base plate being provided with means for locking the holder to the level web.

4,292,742

PLANT FOR DRYING FUEL

Hakan Ekberg, Norrköping, Sweden, assignor to STAL-LAVAL Turbin AB, Sweden


Filed Jun. 5, 1979, Ser. No. 45,708

Claims priority, application Sweden, Jun. 21, 1978, 7807117

Int. Cl.³ F26B 3/08

U.S. Cl. 34—35

10 Claims



1. A method for drying solid materials such as fuel and fuel additives used in thermal power plants, comprising the steps of:

- circulating a gas having a low oxygen content around a substantially closed loop;
- passing said gas in said loop through hot ashes from said power plant, to heat said gas;
- passing said gas in said loop through said materials to be dried; and
- removing moisture from said gas in said loop prior to passing said gas through said hot ashes.

4,292,743

CEREAL DRYER


Virgiliu T. Razus, 12, Avenue Gaspard-Valette, 1206 Geneva, Switzerland

Filed Nov. 27, 1979, Ser. No. 98,334

Int. Cl.³ F26B 17/16

U.S. Cl. 34—65

4 Claims



1. Cereal grain dryer, comprising: a casing defining an enclosure having an inlet and an outlet opening for movement of cereal grains through said casing and an admission and a discharge orifice, for the flow of hot air in said casing; means for moving said hot air flow from said admission to said discharge orifices; a heat exchanger mounted to span said admission orifice and means producing a flow of hot combustion gases and feeding them to said heat exchanger, said heat exchanger having exchange wall means exposed on the outer face thereof to said air to produce said hot air flow and, on the inner face, to said flow of hot combustion gases, wherein said casing stands upright with said inlet opening being provided at the top and said outlet opening being provided at the bottom whereby

said cereal grains circulate through said casing by gravity; wherein said casing has an upper section and a middle section below said upper section; wherein a heating coil lines the inner face of said upper section and means connect said coil to said means producing a flow of hot combustion gases to provide hot combustion gases to said heating coil, and wherein said admission and discharge orifices for said hot air flow are provided in facing walls of said middle section whereby said hot air flow circulates horizontally across said middle section of said casing.

4,292,744

SEPARATION APPARATUS FOR A CONDENSATION-DRYING PLANT


Hans U. Nabholz, Ennetbaden, Switzerland, assignor to Micafil AG, Zurich, Switzerland

Filed Nov. 21, 1978, Ser. No. 962,699

Int. Cl.³ F26B 21/08

U.S. Cl. 34—73

5 Claims



1. A separation apparatus for a drying plant wherein the material to be dried is heated by the heat of condensation of a readily volatile fluid, said separation apparatus comprising: an autoclave that is capable of being evacuated; a plurality of evaporators operably connected and consisting of a main evaporator and first and second stage evaporators;

- means to convey vapor from said main evaporator to said autoclave;
- means to convey vapor from said first stage evaporator to said autoclave;
- means to convey liquid condensate from said autoclave to said main evaporator;
- heating means to supply heat to said plurality of evaporators;
- means to convey liquid between said evaporators; and
- means to remove liquid from said second stage evaporator.

4,292,745

AIR FOIL NOZZLE DRYER

Hans-Peter Caratsch, Itenhardstrasse 16, 5620 Bremgarten, Switzerland

Filed Aug. 24, 1979, Ser. No. 69,392

Claims priority, application Switzerland, Aug. 29, 1978, 9103/78

Int. Cl.³ F26B 13/20


U.S. Cl. 34—156

6 Claims

1. An air foil dryer for drying webs of material moving through said dryer, comprising:

- a drying chamber;
- means arranged within said drying chamber for floatingly guiding said web of material during its movement;
- said guiding means comprising two pluralities of nozzle means spaced apart opposite one another relative to said web of material;
- each plurality of nozzle means comprising a plurality of nozzles which are provided with outlet orifices for a drying medium, said web of material being guided by the drying medium emanating from said nozzles without contacting said nozzles;

means for adjusting the space between the nozzles of the said two pluralities of nozzle means; and



means for adjusting the cross-sectional area of said outlet orifices.

4,292,746

LIGHT WEIGHT INSULATED ATHLETIC SHOE


Glen J. Delaney, 111 Oneida, Apt. 109, Pontiac, Mich. 48053

Filed Apr. 25, 1979, Ser. No. 33,129

Int. Cl.³ A43B 1/14, 5/00; A43C 15/00

U.S. Cl. 36—83

4 Claims



1. A light weight insulated athletic shoe comprising: a sole of flexible rubber having a skid resistant tread; an outer layer of semi-permeable material having a soft texture and insulating properties which allows the passage of air and excludes the passage of moisture allowing the shoe to breathe, bonded at a lower portion thereof to said sole;

- an intermediate layer of stretchable sponge rubber bonded to the outer layer to provide an insulating layer;
- a cloth inner lining bonded to said intermediate layer providing a friction reducing and comfort improving surface to contact the leg and stocking of the wearer;
- a front portion of the shoe slit from the top to a point midway along the length of the foot for ease in putting on and removal of the shoe;
- a tongue of semi-permeable material extending across the opening created by said slit when the shoe is opened to receive the foot, said tongue bonded along its edges to the edges of said slit;
- said inner lining extending across said tongue;
- a plurality of eyelets disposed along edges of said slit to receive a lace to close said slit;
- a plurality of hooks disposed along said slit between said eyelets to alternately retain said lace to secure the shoe to the wearer's foot;
- a plurality of recesses formed in the outer layer at the interface of the sole and outer layer;
- a plurality of apertures concentric with said recesses formed through said sole;
- a plurality of metallic inserts, each of said inserts disposed

between the sole and the outer layer including an enlarged inner head complementary to said recess and a projection; said projection being complementary to said aperture and including a threaded aperture formed in said projection, with said aperture through the sole being recessed beneath a lower surface of said sole so that no portion of said projection will contact the surface on which the wearer may walk; and

a plurality of removable studs engageable with the inserts, said studs comprising a threaded upper end to enter the aperture and threadingly engage the threaded aperture, a tapered projecting lower end projecting below the sole and terminating with a rounded point, and a pair of opposed wrench flats along the projecting portion for insertion and removal of said studs.

4,292,747

COMPRESSED AIR DREDGE


Walter Hoppe, Düren, Fed. Rep. of Germany, assignor to Zimmermann & Jansen GmbH, Düren, Fed. Rep. of Germany
Filed May 2, 1979, Ser. No. 35,165

Claims priority, application Fed. Rep. of Germany, May 8, 1978, 2820024

Int. Cl.³ F04F 1/08, 1/10; E02F 3/88

U.S. Cl. 37—58

4 Claims



1. In a compressed air dredge for removing gravel, sand, mud or the like from the sea floor of the type including a compressor which is installed on a dredging ship having a vertically-disposed feed pipe and which, via a compressed air line, blows compressed air into the bottom end of the feed pipe so as to provide the required suction force, the improvement comprising:

at least two vertically-disposed feed pipes, each of which is coupled to a separate compressor and each of which is provided with a separate compressed air line, said compressed air lines being coupled together via a coupling line having shut-off means for establishing and closing off communication between said two compressed air lines and said compressed air lines also each being provided with separate shut-off means disposed, in the flow direction of said compressed air line, downstream of said coupling line, for establishing and closing off communication between the compressed air line and its associated feed pipe.

4,292,748

CLAMP STAND FOR NEEDLEWORK FRAMES

Betty J. Miller, 1509 Ballard, East Brewton, Ala. 36426

Filed Sep. 19, 1978, Ser. No. 943,741

Int. Cl.³ D05C 1/04; A47B 97/04

U.S. Cl. 38—102

1 Claim

1. A portable needlecraft stand for supporting a needlecraft working frame, said stand comprising:


base means normally positionable on a seat so as to permit a

needlecraft craftsman to sit thereon thus supporting said needlecraft stand;

support means pivotally hingedly attached to said base means and being substantially orthogonally positioned relative thereto when said stand is being used by said needlecraft craftsman and being selectively collapsible into a folded position against said base means when it is desired to store or transport said stand;

locking means operable to secure said support means in substantially orthogonal alignment with said base means, said locking means including a latch means pivotally attached to said support means and being engageable in a recess formed on said base means, said recess being formed partially by a slot cut into a portion of said base means and further being formed by one surface of a hinge fixedly secured to said base means, said hinge being further attached to said support means so as to permit a pivotal movement of said support means relative to said base means, said latch means being directly engageable with one surface of said hinge, said latch means further being selectively movable out of engagement with said recess when it is desired to collapse said support means against said base means thereby to store or transport said stand;

working frame holding means to which said working frame is fixedly securable, said holding means including a clamp bar lying in substantially parallel alignment with said base means and being substantially orthogonally positioned relative to said support means, said holding means being



adjustably movable along a portion of said support means so as to vary a distance between said holding means and said base means thereby to accommodate the needs of a needlecraft craftsman sitting on said base means, said holding means further being rotatable along a horizontal axis thereof so as to vary an angle in space of said working frame fixedly secured thereto;

gripping means operably associated with said holding means and being selectively releasable to permit adjustable heightwise movement and rotation of said holding means, said adjustable heightwise movement of said holding means relative to said support means being afforded through the use of a longitudinal slot positioned within said support means, said gripping means being selectively releasable to permit said movement of said holding means within said slot, such selective release of said gripping means to afford a movement of said holding means within said longitudinal slot also permitting said holding means to be selectively rotated along said longitudinal axis thereof, said gripping means including a support shaft and a wingnut, said support shaft having machine screw threads on one end thereof to permit said wingnut to be threadably secured thereto and further having wood screw threads on another end thereof so as to permit said support shaft to be threadably secured to said holding means, said holding means being positioned on one side of said support means proximate to said longitudinal slot and said wingnut being positioned on another side of said support means proximate to said longitudinal slot, said support shaft extending

through said longitudinal slot whereby a tightening of said wingnut on said support shaft effects a gripping action of said holding means against said support means, said holding means being formed of a dowel portion and a flat bar portion, said dowel portion having said wood screw threads of said support shaft longitudinally positioned therein and further including a slot formed in one end thereof, said flat bar portion being fixedly secured within said dowel slot; and

clamping means for fixedly securing said working frame to said holding means, said clamping means being selectively removable from and attachable to said holding means to facilitate the attachment and removal of said working frame relative to said holding means, said clamping means comprising a C-clamp which is manually attachable to and removable from said holding means.

4,292,749

DISPLAY DEVICE FOR COUPON CLIP


Claude E. Thomas, Bldg. 36631, Apt. 104, Chatham Hills Apts., Grand River Ave., Farmington, Mich. 48024

Filed May 19, 1980, Ser. No. 151,388

Int. Cl.³ G09F 3/00

U.S. Cl. 40—308

13 Claims



1. A display device consisting of a coupon clip and an integrally formed holder adapted for attachment to said coupon clip and an elongated support member having a longitudinal axis extending horizontally and being of substantially circular cross section about said axis, said clip comprising

a clear thermoplastic material having a thickness in the range of about 1/16 inch comprising: a first leg and a second leg, said first leg being shorter than said second leg, a resilient hinge connecting said first and said second leg at one end and resiliently urging the opposite ends of said legs into engagement, said legs generally converging toward each other from said hinge toward the distal end of each leg for removably storing coupons therebetween, one of said legs having an edge generally extending across its width at its distal end, said edge facing the other of said legs and being relatively sharp and having a length in the range of at least 1 1/2 to 3 inches;

said holder comprising clamping member and a securing means of resilient material said clamping member having two integrally joined leg portions jointly defining an axially open channel for receiving said support member, said channel constituting a resilient wall of about more than 180 degrees but substantially less than 360 degrees of the circumference thereof, the respective terminal parts of said leg portions defining therebetween a radial entrance to said channel, said terminal parts being resiliently movable relative to each other in a substantially circumferential direction between a relaxed position in which said entrance is narrower than said cross sectional width of said support member and an extended position in which

4,292,750

WRITING INSTRUMENT WITH HOLDER OR GRIP PORTION INCORPORATING A PARTIALLY VISIBLE MOVABLE RIBBON


Giuseppe Zuffellato, Via Colombo no 90, Grugliasco, Torino, Italy

Filed Jan. 3, 1980, Ser. No. 109,454

Claims priority, application Italy, Jan. 17, 1979, 67094 A/79
Int. Cl.³ B43K 29/12, 29/14

U.S. Cl. 40—334

5 Claims



1. A writing instrument comprising a hollow body having a writing point at one end, a knob at the other end rotatable relative to the hollow body, a pair of flexible shafts extending lengthwise of the hollow body in side-by-side relationship, a flexible sheet wound on the shafts in such a way that turning one shaft in one direction winds up the sheet on said one shaft and unwinds the sheet from the other shaft, and turning the other shaft in the opposite direction winds up the sheet on the other shaft and unwinds it from the one shaft, and means interconnecting said knob and said shafts whereby turning said knob in one direction turns said one shaft in said one direction and turning said knob in the opposite direction turns said other shaft in said opposite direction, the ends of said flexible shafts opposite said knob being free to move in a direction perpendicular to the length of said shafts thereby to permit the rolls of sheet to shift laterally as they change in size during rolling and unrolling.

4,292,751

ROLL TYPE DISPLAY SIGN

H. Kent Snyder, Jr., River Forest, Ill., assignor to Chicago Display Company, Chicago, Ill.

Filed May 5, 1980, Ser. No. 146,226

Int. Cl.³ G09F 11/18, 23/00, 17/00

U.S. Cl. 40—517

13 Claims


1. A roll type display sign for a pump having a pump face, said sign comprising:

a message bearing display sheet;

means for mounting the display sheet to the pump such that the display sheet is movable across the pump face to a selected one of a plurality of mounting positions spaced across the pump face;

means for retracting the display sheet such that the display sheet is movable between an extended position, in which the sheet extends over a selected one of a plurality of

portions of the pump face, and a retracted position, in which the sheet exposes the selected one of the plurality of portions of the pump face, each of the plurality of portions of the pump face corresponding to a respective one of the plurality of mounting positions; and



means for releasably holding the display sheet in the extended position in any one of the plurality of mounting positions such that the display sheet simultaneously covers the portion of the pump face corresponding to the selected one of the mounting positions and displays the message on the display sheet.

4,292,752


DISPLAY SIGN

William D. Clark, 465 Alpine Heights Rd., Alpine, Calif. 92001
Continuation-in-part of Ser. No. 914,014, Jun. 9, 1978,
abandoned. This application Apr. 19, 1979, Ser. No. 31,437

Int. Cl.³ G09F 13/04

U.S. Cl. 40—576

6 Claims



1. A back-lighted display sign comprising:
 - a display housing having a substantially transparent outer face panel;
 - a light source mounted in said housing;
 - a copy frame positioned behind said outer face panel and having at least one aperture therethrough;
 - a plurality of relatively thin copy inserts having display characters and a background area with contrasting optical properties, said display characters being positioned in different desired locations over the surfaces of said inserts;
 - copy retaining means affixed to the rear face of said copy frame adjacent to said aperture to hold said copy inserts in a fully overlapping relationship in said copy frame, and to provide a desired, essentially two-dimensional arrangement of said display characters; and
 - copy insert registration means, including an integral tab on each of said copy inserts and tab retaining means defined at least in part by said copy retaining means.

4,292,753

FISH LANDING NET


Richard J. Yesuratnam, Apt. 15, 9002 Manchester Rd., Silver Spring, Md. 20901

Filed Jun. 2, 1980, Ser. No. 155,240

Int. Cl.³ A01K 77/00

U.S. Cl. 43—5

5 Claims



1. A fish landing net comprising:
 - a frame including top and bottom supports and a plurality of rib means secured between said supports, said top and bottom supports each having an open portion and at least two of said plurality of rib means cooperating with said supports to define an opening into the interior of said net;
 - first and second spaced, parallel slide bars secured at opposite ends to said top and bottom supports and cooperating with the open portions of said supports to define a slot adapted to receive a fishing line and guide it into the center of the fish landing net;
 - clip means securable to and slidable on said slide bars to close said slot and secure a fishing line within said net; and
 - shoulder means at the bottom of at least one of said slide bars, said shoulder means being adapted to engage said clip means to prevent said clip means from sliding upwardly on said slide bars, whereby lowering of said clip means and subsequent raising thereof inverts said net.

4,292,754

BAT-LIKE, BUBBLE-BLOWING DEVICE


Charles Lukaszewski, 178 William St., Port Ewen, N.Y. 12466

Filed Sep. 19, 1980, Ser. No. 188,816

Int. Cl.³ A63H 33/28

U.S. Cl. 46—6

3 Claims



1. A bat-like, bubble-blowing device in combination with a bubble solution for use in blowing bubbles, said device having a size and shape similar to a conventional baseball bat including a handle portion and a body portion, said device being of hollow-cylindrical construction, said handle portion having a blowing orifice at its end and said body portion having an open end, a residual film over and covering said open end of said

device being formed by dipping said open end in said bubble solution, and said blowing orifice being adaptable for a child to position and place his mouth over said handle portion such that his lips are disposed around said blowing orifice to thereby blow through said blowing orifice to form a bubble on said open end.

4,292,755

AIR FLOATING SAUCER TOY


Lin P. Houn, No. 6, La. 107, Sec. 1, Tzu Yen Rd., Shih Pai, Peitou, Taipei, Taiwan

Filed Jul. 25, 1979, Ser. No. 60,785

Int. Cl.³ A63H 29/16

U.S. Cl. 46—44

6 Claims



1. An air-floating saucer toy, comprising: an air pump; an electric motor; electric batteries for powering said motor and said pump; a speed-reducing device driven by said motor; a connector mounted on said speed-reducing device; a radially extending pneumatic tube journaled through said connector and operably associated with said speed-reducing device for rotation thereby, said tube having an outer end travelling in a generally horizontal circular path and connected pneumatically to said pump through said connector and tube; a housing in which said pump, motor, batteries, speed-reducing device, connector, and tube are contained, said housing having a circular slot coinciding with and superjacent the path of travel of said outer end of said tube; said outer end of said tube opening to said slot for pneumatic discharge therethrough; a saucer disposed for floating above said slot and outer end of said tube under the influence of the pneumatic discharge for spaced disposition above said housing and for generally horizontal circular movement with said end along an orbit corresponding to said circular slot; and control means for controlling operation of said pump and motor.

4,292,756

TOY LAUNCHING DEVICE


Eugene Jaworski, Park Ridge, and Jeffrey D. Breslow, Highland Park, both of Ill., assignors to Marvin Glass & Associates, Chicago, Ill.

Filed Oct. 20, 1980, Ser. No. 198,839

Int. Cl.³ A63H 1/00

U.S. Cl. 46—72

6 Claims



1. An egg spinning toy comprising a dish-shaped platform adapted to support one or more eggs to be spun, said platform being provided with a manually movable segment which is adapted to be manually operated to permit an egg spinning on said platform to move off of said platform onto an adjacent supporting surface, a friction wheel disposed at least in part

4,292,757

COLLAPSIBLE WING AIRCRAFT


George L. Cahen, Jr., 130 Appletree Rd., Charlottesville, Va. 22903

Continuation-in-part of Ser. No. 813,976, Jul. 8, 1977,
abandoned. This application Apr. 26, 1979, Ser. No. 33,805

Int. Cl.³ A63H 27/00

U.S. Cl. 46—80

20 Claims



1. An aircraft of the heavier than air type which comprises wings deployable between a launch configuration in which said wings are collapsed and a flight configuration in which said wings are extended and a power source for deploying said wings from the launch configuration to the flight configuration, said power source comprising a hairpin spring which is rotatably restorable in its entirety about an axis of the aircraft, as an adjunct to the removal of a restraint maintaining said wings in the collapsed configuration, from a first orientation in which energy is stored therein in potential form to a second orientation in which said means is in a condition which has, in the course of being arrived at, permitted the energy stored therein in potential form to be converted to kinetic form and thereby deploy said wings, said power source being housed in the wings of said aircraft.

4,292,758

JET TOY BOAT


Wayne A. Kuna, Oak Park; James G. Thibault, Chicago, and Palmer J. Schoenfeld, Evanston, all of Ill., assignors to Marvin Glass & Associates, Chicago, Ill.

Filed Jan. 30, 1980, Ser. No. 116,928

Int. Cl.³ A63H 23/02

U.S. Cl. 46—93

1 Claim



1. A tub toy comprising: a hull including a pair of laterally spaced rearward extensions;

member comprising a pair of channels disposed in back-to-back relationship on opposite sides of a bridge section, each of said channels including a pair of converging side sections integral with said bridge section and frictionally gripping one of said pair of mutually facing panel edges.


4,292,765

MACHINE FOR ABRADING OUTSIDE DIAMETERS AND THE METHOD OF MAKING SAME

Thomas S. Brawley, P.O. Box 82, Middletown, Conn. 06457
Continuation-in-part of Ser. No. 876,994, Feb. 13, 1978, abandoned. This application Mar. 26, 1979, Ser. No. 24,004
Int. Cl.³ B24B 5/18

U.S. Cl. 51—103 TF

21 Claims



1. An improved machine for high speed abrading of outside diameters of the type comprising:

- a frame;
- an abrading wheel rotatably mounted in the frame;
- drive means to rotate the abrading wheel; and
- workpiece support means affixed to the frame to hold a plurality of workpieces in abrading contact with the abrading wheel;

wherein the improvement comprises:

- a housing concentric to the abrading wheel rotatably attached to the frame in which the workpiece support means are attached; and
- drive means attached to the housing to rotate the housing in a direction opposite to that of the abrading wheel, whereby the counter rotation of the housing causes a revolution of the workpiece support means and the workpieces about the periphery of the abrading wheel in a direction opposite to the rotation of the abrading wheel, increasing the effective grinding speed.

4,292,766

METHOD AND APPARATUS FOR GRINDING A WORKPIECE


Calvin K. Kirk, Shrewsbury; Glover C. Joyce, and Francis L. Messier, both of Worcester, all of Mass., assignors to The Warner & Swasey Company, Cleveland, Ohio
Division of Ser. No. 886,996, Mar. 16, 1978, Pat. No. 4,201,016.
This application Dec. 31, 1979, Ser. No. 108,364
Int. Cl.³ B24B 5/42

U.S. Cl. 51—105 SP

27 Claims

1. An apparatus for use in grinding a plurality of crankshafts each of which has a plurality of crankpins, said apparatus comprising holder means for holding each of the crankshafts in turn during an initial grinding operation and during a second grinding operation when one of the crankpins on a crankshaft is out-of-round by more than a first distance and less than a second distance at the end of the initial grinding operation, grinding wheel means for grinding each of the crankpins on each of the crankshafts in turn during the initial grinding operation and for grinding each of the crankpins on a crankshaft when a second grinding operation is necessary, first means for detecting when the number of consecutive crankshafts requiring a second grinding operation exceeds a predetermined number,

and second means connected with said first means for initiating a control function upon detection by said first means



that the number of consecutive crankshafts requiring a second grinding operation exceeds the predetermined number.


4,292,767

BELT GRINDER FOR GRINDING NON-CIRCULAR WORKPIECE

James J. Fatula, New Beaver, Pa., assignor to Ryman Engineering Company, Elwood City, Pa.
Filed Feb. 1, 1980, Ser. No. 117,808
Int. Cl.³ B24B 21/16

U.S. Cl. 51—145 R

10 Claims



1. A belt grinder for grinding a workpiece mounted for rotation on a longitudinal axis and having a non-circular cross-section which comprises three rotatable rolls mounted on axes substantially parallel to each other, said rolls being arranged in a triangular manner with one of said rolls being the work roll and the other two being non-work rolls, an abrasive belt passing around said rolls, means for rotating said rolls to drive set abrasive belt, means mounting said work roll for substantially straight line movement toward and away from the axes of said workpiece, said non-work rolls being movable toward and away from each other as the work roll moves toward and away from the axis of said workpiece, and resilient means for applying a force to urge said work roll and belt against said workpiece with the force increasing as the work roll moves toward the axis of said workpiece, said work roll being movable away from the axis of said workpiece by said workpiece when the distance of the surface of said workpiece from its axis increases.

4,292,768

GRINDING TOOL


Romolo Panetti, Geneva, Switzerland, assignor to Speno International S.A., Geneva, Switzerland
Filed Oct. 29, 1979, Ser. No. 88,833

Claims priority, application Switzerland, Nov. 9, 1978, 11526/78

Int. Cl.³ B24D 5/00

U.S. Cl. 51—168

2 Claims



1. A grinding tool comprising:

- a support flange means adapted to be fastened to the end of a drive shaft;
- a cylindrical grinding wheel formed of a yoke-shaped plate means having abrasive material bonded and molded to shape therein;
- a clamping flange means for clamping said grinding wheel on said support flange means;
- retaining stud spindle means arranged on said support flange means;
- hole means located on said support flange means in the vicinity of said retaining stud spindle means;
- notch means arranged in said plate means for surrounding engagement over said retaining stud spindle means and said hole means; and
- locking spindle means on said clamping flange means for engagement within said notch means and said hole means.

4,292,769

BALANCING AND MONITORING APPARATUS


Willi Maag, Rheinau; Hans U. Baumgartner, Winterthur; Max Vollenweider, Winterthur, and Hans J. Wolf, Freienstein, all of Switzerland, assignors to Kistler Instrumente AG, Winterthur, Switzerland
Filed Sep. 29, 1978, Ser. No. 946,869

Claims priority, application Switzerland, Sep. 29, 1977, 011879/77

Int. Cl.³ G01M 1/34

U.S. Cl. 51—169

21 Claims



1. Apparatus for balancing and monitoring unbalanced vibrations of a rotating member comprising vibration pick-up means located on a mounting of the rotating member for producing an electrical signal which corresponds to a component of an unbalanced force of the rotating member and extending in

an axial direction of the vibration pick-up means, an abrasion tool, an electromechanical actuator means responsive to the electrical signal and having a part for supporting the abrasion tool, the electromechanical actuator means in response to the electrical signal controlling the abrasion tool to effect working vibration of the abrasion tool at a frequency corresponding to the speed of the rotating member to remove material from the rotating member in-phase with the working vibration in the same angular region of the rotating member for effecting a balancing of the rotating member, and means for enabling adjustment of a phase relationship of the vibration of the abrasion tool with respect to a phase relationship of the unbalanced electrical signal so as to effect shifting by any number of steps of $360^\circ/n$, n being a whole number >3 , irrespective of the speed of the rotating member, the means for enabling adjustment including a phase-locked loop circuit for producing a phase-locked oscillation at n -times an unbalanced frequency, the phase-locked loop circuit being connected to an n -factor frequency reducer, a signal from the frequency reducer being compared in the phase-locked loop circuit with the electrical signal from the vibration pick-up means, and the difference influencing the frequency of the phase-locked loop circuit such that the signal supplied to the frequency reducer corresponds to the electrical signal as regards frequency and phase.

4,292,770

YARN HEATER TRACK CLEANING APPARATUS AND METHOD

John C. Newton, Jr., Shelby, N.C., assignor to Ansley, Incorporated, Shelby, N.C.
Filed Mar. 17, 1980, Ser. No. 130,819
Int. Cl.³ B24B 23/02, 1/00

U.S. Cl. 51—170 PT

7 Claims



1. An apparatus particularly adapted for use in cleaning the yarn heaters of yarn processing machines of the type wherein each yarn passes through a relatively narrow and elongated yarn heating slot and the heating of the yarn causes deposits to be built up on the sidewalls and bottom of said slot in an amount sufficient to require periodic removal of the deposits, said apparatus comprising

- an abrasion wheel including a configuration on the outer peripheral surface corresponding to and positioned within said slot,
- means for rotating said abrasion wheel,
- a cover guard surrounding a major portion of said abrasion wheel and leaving a minor portion of the outer peripheral surface of said wheel exposed,
- handle means for manually supporting said rotating abrasion wheel and for guiding the outer peripheral surface of said abrasion wheel along said slot to dislodge the accumulated deposits and to polish said slot, and
- fluid directing means supported adjacent said abrasion wheel for simultaneously directing a fluid stream into said slot to aid in removal of the dislodged deposits from said slot, said fluid directing means including a fluid directing jet supported on said cover guard for directing the fluid stream in the direction of rotation of said abrasion wheel, a portable liquid supply tank for containing a supply of liquid, means for directing the liquid in said supply tank to

said fluid directing jet, and means for directing air under pressure into said supply tank to force the liquid from said supply tank and to said fluid directing jet.

4,292,771


SPLIT MULLION WINDOW FRAME DESIGN
James D. Ellis, Tigard, Ore., assignor to Viking Industries, Inc., Portland, Ore.

Filed Apr. 20, 1979, Ser. No. 31,984

Int. Cl.³ E04B 1/00; E06B 1/38

U.S. Cl. 52—98

16 Claims



1. A window frame comprising:

- a pair of opposed frame members defining opposite sides of a window opening, and having means for mounting a window panel in said opening;
- an attachment flange extending lengthwise of and outwardly from each of said frame members, for attaching opposite sides of said frame to a supporting structure;
- said flanges each having an inner portion and an outer portion, the outer portions being positionable in a common plane for attachment of said pair of frame members to a common face of said supporting structure;
- the outer portion of at least one of said flanges being removable and the inner portion thereof being laterally offset from the outer portion to an extent such that, when said outer portion is removed and said window frame is mounted side-by-side with another such frame, said inner portion overlies the adjoining flange of said other frame.

4,292,772


TRAILER MOUNTED HIGH FLOOR DRILLING MAST AND SUBSTRUCTURE ARRANGEMENT
Paul E. Borg, and Terry M. Lechinger, both of Houston, Tex., assignors to PRE Corporation, Houston, Tex.

Filed Jan. 14, 1980, Ser. No. 111,915

Int. Cl.³ B66B 23/06

U.S. Cl. 52—118

1 Claim



1. A trailer mounted high floor telescopic drilling mast and substructure arrangement comprising:

- a. first trailer means;
- b. telescoping drilling mast means pivotally connected to and transportable in reclined position on said first trailer means;
- c. setback tower means pivotally connected to said drilling mast means and to said first trailer means;
- d. said drilling mast means comprising a rectangular framed structure having four sides with one of said sides having an open face and which when in reclined position on said first trailer means has said open face side supported in part by said setback tower means on said first trailer means and

another of said sides laterally spaced and elevated in relation to said first trailer means;

- e. second trailer means;
- f. elevatable drawworks support means with drawworks, power source and rotary table thereon pivotally mounted and transportable on said second trailer means;
- g. means to secure said first and second trailer means in end to end relation to position said drawworks support means and drilling mast means in longitudinal alignment;
- h. load bearing means to support said first and second trailer means in position;
- i. lifting frame means connected to said drilling mast means; and
- j. cable means extending between said lifting frame means and drilling mast means to retain said lifting frame means in laterally and upwardly extending relation to said drilling mast means when lifting cable means are connected to said lifting frame means to simultaneously elevate said drilling mast means and setback tower means from a reclined position to an upright position on said first trailer means.

4,292,773

DOUBLE PANE SYSTEMS WITH LITTLE REFLECTION, IN PARTICULAR FOR GREENHOUSES

Karsten Laing, Herrenstrasse 57, 7500 Karlsruhe; Ingeborg Laing, Hofener Weg 37, 7148 Remseck 2 - Aldingen, and Oliver Laing, Weissdornweg 14, 7400 Tübingen, all of Fed. Rep. of Germany


Filed Aug. 21, 1979, Ser. No. 68,333

Claims priority, application Austria, Aug. 22, 1978, 6118/78; Sep. 21, 1978, 6831/78; May 15, 1979, 3606/79; Jun. 15, 1979, 4268/79

Int. Cl.³ E06B 7/12

U.S. Cl. 52—171

22 Claims



- 1. A transparent double pane construction forming a double webbed plate for use as a building panel comprising a first pane of a transparent organic material having a superficial layer of a hydrophilic material the surface of which is superficially saponified spaced from a second pane of a transparent material to form an enclosed space between said panes, where the first pane is adapted to be on the inside of a building, where the surface of the first pane which faces the inside of the building comprises said superficial layer and where the surface of the first pane which faces towards the enclosed space has regions along a fall line which are hydrophilic.

4,292,774

WINDOW MOUNTING FOR AUTOMOTIVE VEHICLES
Hans Mairle, Rennjngen, Fed. Rep. of Germany, assignor to Dr. Ing. h.c.F. Porsche Aktiengesellschaft, Stuttgart, Fed. Rep. of Germany

Filed Dec. 20, 1979, Ser. No. 105,705

Claims priority, application Fed. Rep. of Germany, Dec. 22, 1978, 2855526


Int. Cl.³ E06B 3/26; E04B 1/62

U.S. Cl. 52—208

11 Claims

- 1. Mounting arrangement for windowpanes of an automo-

tive vehicle comprising a cover strip and a column receiving windowpanes, said column including a flange, characterized in that windowpanes of the vehicle are arranged along a contour line of the vehicle and are placed adjacent each other with a joint formed therebetween, wherein the flange is a base leg of



a locking plate having a T-shaped cross section, top legs of the T-shaped locking plate being joined to a cap-shaped profile to define the column, said column being located adjacent to and outside of said joint except for its flange which extends within the joint and is fashioned for fastening the cover strip in a manner hiding the joint.

4,292,775

BUILDING WALL STRUCTURE

David Howard, P.O. Box 295, Alstead, N.H. 05602


Continuation of Ser. No. 680,063, Apr. 26, 1976, abandoned.

This application Aug. 21, 1978, Ser. No. 935,536

Int. Cl.³ E04B 5/48; E04F 17/00, 13/04

U.S. Cl. 52—220

6 Claims



1. A wall structure for enclosing a frame adapted to support a building, the frame including interconnected vertical and horizontal frame members and an inside surface and an outside surface, said wall structure comprising:

- A. a mesh secured to the outside surface of the frame,
- B. a plurality of rigid insulating panels,
- C. a plurality of reinforcing stringers, said panels and stringers being arranged alternatively to form a wall outside said mesh and adjacent the outside surface of the frame, the inside surface of the frame thereby being left exposed by the wall,
- D. means for securing said panels and said stringers to the frame, and
- E. a plaster finish layer applied to said mesh between the exposed members of the frame, said plaster finish layer adhering to and being reinforced by said mesh and being supported by said mesh and said insulating panels.

4,292,776

UNITARY COMBINED BACKER AND SIDING BOARD
Milton MacDonald, 5 Holly St., Woodsville, N.H. 03785

Filed Aug. 13, 1979, Ser. No. 66,030

Int. Cl.³ E04B 1/66

U.S. Cl. 52—394


7 Claims

- 1. A unitary combined backer board and clapboard comprising:

a standard wood board of uniform thickness having parallel front and rear faces, an upper edge and a lower edge; said board being sufficiently thick and strong to be affixed with other identical said boards, horizontally one upon another, each at a slight incline from the vertical, directly onto vertical studs of a building;

said upper edge having an integral, elongated, upstanding tongue, of predetermined curvature, extending along the front edge portion thereof to shed rainwater, and having an elongated, downward-sloping surface, extending along the rear edge portion thereof from said upstanding tongue to said rear face to shed rainwater;

and said lower edge having an elongated tongue groove of predetermined curvature, for receiving the upstanding tongue of the next lower board, said groove extending



longitudinally along the intermediate portion of said lower edge;

said lower edge having an integral, depending, rear, lower tongue extending longitudinally along the rear portion thereof and adapted to seat on the downward sloping surface of the next lower board and said lower edge having an integral, depending, front, lower, cover tongue extending longitudinally along the front portion thereof for covering the joint with the said next lower board; the upstanding tongue of each said lower board fitting in the tongue groove of the next higher board with a predetermined clearance to form a front, air space for ventilating said joint;

and said board being free of any upstanding rear upper tongue, and free of any groove in the upper edge thereof, capable of retaining water.

4,292,777

INSULATION-CONFINING PANEL AND METHOD OF USING THE SAME

Edward R. Story, 4985 N. Cascade Pl., Oak Harbor, Wash. 98277

Continuation-in-part of Ser. No. 949,895, Oct. 10, 1978, abandoned. This application Oct. 12, 1979, Ser. No. 84,517


Int. Cl.³ E04B 2/00

U.S. Cl. 52—407

20 Claims

- 1. A panel for confining blowable insulation material against a generally planar surface of a building structure comprising a sheet of substantially rigid material having two substantially parallel scores each spaced inward of an edge of said sheet, said scores dividing said sheet into a substantially rectangular central portion and opposite marginal tabs adjacent to said central portion which tabs are bendable along said scores so as to be disposed substantially perpendicular to said sheet central por-

tion, said sheet central portion having several ventilation apertures scattered substantially uniformly throughout the area of said sheet central portion for permitting circulation of air



through said sheet central portion, said apertures being small enough to prevent passage of a substantial amount of the blowable insulation material through said apertures.

4,292,778

Patent Not Issued For This Number

4,292,779

SUPPORTING SYSTEM FOR PANEL ASSEMBLY
Hugo A. J. Landheer, Rotterdam, Netherlands, assignor to Hunter Douglas International N.V., Netherlands


Filed Feb. 23, 1979, Ser. No. 14,712

Claims priority, application Fed. Rep. of Germany, Feb. 24, 1978, 2807942

Int. Cl.³ E06B 3/54

U.S. Cl. 52—486

11 Claims



1. In a panel assembly having a plurality of elongated panels, the improvement comprising a support member including a flange lying in a plane parallel to and spaced rearwardly of the

plane of the panels, a two part clamp, having a first part to engage a panel edge and a second part to engage the first part as well as said support member, said first clamp part being a securing member having a hook portion, a passage extending through said securing member, said second clamp part being a locking member having two locking legs, the hook of said securing member being engaged with one longitudinal edge of a panel on the rearward side thereof, one of said locking legs extending through the passage in said securing member, and the other of said locking legs being in bearing engagement with said flange; and the cross-member being uniform throughout its length, whereby each forms a cut-to-length part of an extruded profile.

4,292,780

STAGGERED BUTT SIDEWALL SHINGLE PANEL AND METHOD OF MAKING THE SAME


Craig S. Barker, Deerfield, Fla., and Joe L. Bockwinkel, Winlock, Wash., assignors to Shakertown Corporation, Winlock, Wash.

Filed Jan. 25, 1980, Ser. No. 115,212

Int. Cl.³ E04D 1/00

U.S. Cl. 52—541

4 Claims



1. In a process for making wood shingle sidewall panels of substantially uniform thickness including laying up a continuous sheet laminated shingle panel blank having a face layer of high quality tapered wood shingles in edge-abutting relationship arranged in a row transversely of their lengths and tapered in one direction, a backing layer of low quality tapered wood shingles opposite the face layer shingles and tapered in the direction opposite the direction of taper of the face layer shingles, and an intermediate veneer layer between the face and backing layers, bonding the face and backing layers of wood shingles to the opposite sides, respectively, of the intermediate veneer layer with the opposite rows of shingles substantially in registration lengthwise, severing the panel blank so formed along a line located generally centrally between its opposite edges, and cutting the panel blanks to length, the improvement comprising arranging the shingles in the face layer in staggered relationship prior to bonding the face layer to the veneer and thereby forming the sheet blank to be severed to form two sidewall panel blanks each of a width approximately one-half

the length of the sheet blank shingles, one sidewall panel blank having face layer butt edges in staggered relationship and the other sidewall panel blank having substantially even butt edges.

cally by distances equal to the distance between the second locking projections of siding panels in successive courses of said array.

4,292,781

SIDING PANEL SYSTEM WITH MODULAR INSULATING AND MOUNTING UNITS


Alexander A. Chalmers, Warren, and J. Lynn Gailey, Newton Falls, both of Ohio, assignors to Alcan Aluminum Corporation, Cleveland, Ohio

Filed Aug. 8, 1979, Ser. No. 64,927

Int. Cl.³ E04D 1/00

U.S. Cl. 52—547

14 Claims



1. A siding system for a building wall or the like, comprising
 - (a) a plurality of horizontally elongated siding panels mountable on the wall in an overlapping interlocked array in successive courses, one above another, each of said siding panels having a top edge with a first longitudinal locking projection and a bottom edge with a second longitudinal locking projection for interlocking with the first projection of an immediately subjacent siding panel in the array;
 - (b) a plurality of modular insulating and mounting units mountable on the wall in coplanar relation inwardly of the siding panels, each of said modular units having an outer surface with a vertical extent corresponding to the height of a plurality of the courses of siding panels; and
 - (c) means mountable in predetermined position on said outer surface for positioning and mounting the siding panels on the modular units, said mounting means comprising for each modular unit a plurality of horizontally elongated resiliently flexible retainer strips, each of said strips having a hook portion for snap-fittingly engaging a first locking projection of one of said siding panels along the length thereof to secure said one siding panel to an associated modular unit;
 - (d) each of said retainer strips having a horizontally extending inwardly projecting portion and the outer surface of each of the modular units defining a plurality of recesses extending inwardly from said outer surface for receiving the inwardly projecting portions of said strips to properly position said strips, said recesses being spaced apart vertically

4,292,782

SHEET METAL STRUCTURAL BEAM


Jack A. Schaeffer, Reading, Pa., assignor to Dana Corporation, Toledo, Ohio

Filed Jul. 18, 1979, Ser. No. 58,681

Int. Cl.³ E04C 3/02

U.S. Cl. 52—696

3 Claims



1. A structural element comprising: a first U-shaped elongate member having a first flat planar base with first and second spaced parallel planar sides extending integrally from said first base; a second U-shaped elongate member having a second flat planar base with first and second spaced parallel planar sides extending integrally from said second base, said first and said second U-shaped elongate members opening toward one another with said first sides coplanar and with said second sides coplanar; an elongate corrugated web extending between said first and second U-shaped members, said web having a plurality of spaced first coplanar flats and a plurality of second coplanar flats disposed parallel to and alternately spaced with said first coplanar flats, said first sides overlapping a portion of each of said first flats and said second sides overlapping a portion of each of said second flats; means permanently connecting said first flats to said first sides; and means permanently connecting said second flats to said second sides, and wherein said web has edges spaced from both said first base of said first U-shaped member and said second base of said second U-shaped member.

4,292,783

INSULATED BUILDING STRUCTURE AND METHOD FOR MAKING SAME

Dan R. Mulvihill, 603 W. 3rd St., Coffeyville, Kans. 67337

Filed May 21, 1979, Ser. No. 40,546


Int. Cl.³ E04B 1/00

U.S. Cl. 52—741

4 Claims

1. A method for constructing a building comprising the steps of:
 - vertically orienting performed slabs of insulating material removable temporary supports aligned to place a wall in location on a foundation member;

covering the at least one side of said slabs with structurally rigid wire mesh;



spraying gunite concrete onto said at least one surface of said wall over said mesh to form a structurally rigid insulated wall; and
removing said temporary supports.


4,292,784

FIELD CROP HARVESTING AND LOADING MACHINE
Cinto A. Abatti, 1296 W. Evan Hewes Hwy., El Centro, Calif. 92243, and Harold T. Ash, 1907 Orchard Rd., Holtville, Calif. 92250

Filed Jun. 16, 1980, Ser. No. 159,941
Int. Cl.³ A01D 67/00; B65B 67/00

U.S. Cl. 53—391

19 Claims



6. A harvesting and local transport system for field crops utilizing a plurality of substantially identical trucks any one of which is adaptable to become a field crop harvester with the balance of the trucks being shuttle trucks, said system comprising:

- a plurality of substantially identical trucks each having a loading bed with conveyor means therein disposed at substantially the same height and having mateable rear ends for facilitating the free longitudinal movement of containers therebetween;
- one of said trucks being designated a harvester truck and the rest of said trucks being shuttle trucks, said harvester truck having a pair of longitudinally extended sorter conveyors removably mounted along opposite sides of the bed;
- a pair of conveyor assemblies removably mounted to said harvester truck on opposite sides thereof and having wing conveyors extending laterally outwardly from said harvester truck over the field and also having elevator conveyors for delivering crops from said wing conveyors to said sorter conveyors; and
- powered means for translating containers from the loading bed of said harvester truck to the loading bed of the respective shuttle truck whereby said conveyor assemblies and sorter conveyors can be removed from said harvester truck and installed on one of said shuttle trucks such that the latter becomes the harvester truck.

4,292,785
TILE PACKAGING

Leslie G. Hammond, Leighton Buzzard, England, assignor to Anchor Building Products Limited, England


Filed Sep. 12, 1979, Ser. No. 75,283

Claims priority, application United Kingdom, Sep. 20, 1978, 37540/78

Int. Cl.³ B65B 13/18

U.S. Cl. 53—399

13 Claims



1. A method of packaging tiles, each having projections on at least one face thereof, said method comprising positioning said tiles one behind the other on one edge thereof to form an elongate stack having a top surface, a base surface and four side surfaces with opposite ends of said stack being formed by faces of the end tiles of the stack, conveying said stack of tiles in the direction of the longitudinal central line of the stack through a packaging station having inlet and outlet ends, supporting the stack of tiles, whilst being conveyed through the packaging station, along the base surface of the stack on one side only of the longitudinal central line of the stack leaving the base surface of the stack, on the opposite side of the longitudinal central line of the stack, unsupported and along another surface of the stack, thereby to maintain the integrity of the stack without interfering with the packaging operation, and, during the passage of the stack through the packaging station, wrapping a strap around that section of the stack which is unsupported along its base surface so that the strap extends around the top and base surface and end faces of the stack and then securing the strap.

4,292,786


CHOPPED LEAFY VEGETABLE PACKAGING MACHINE
Howard W. Long, and Robert L. Flowers, both of Wheeling, W. Va., assignors to Coronet Foods, Inc., Wheeling, W. Va.

Filed Sep. 28, 1979, Ser. No. 80,133

Int. Cl.³ B65B 1/24, 31/00

U.S. Cl. 53—434

9 Claims



1. A packaging machine for compressing and closing a flexi-

ble bag having a predetermined quantity of compressible product therein to reduce the volume of the product and provide a completed package of less volume than the product in its bulk form prior to compression, said machine comprising a supporting surface for the flexible bag and product with the lower end of the bag adapted to be supported by the surface, an overlying surface engaging the bag where it is in contact with the upper surface of the product in the bag, said supporting surface and overlying surface adapted to approach each other to compress the bag and product therein in a manner to leave the open upper end of the bag accessible for closing the bag after the product and bag have been reduced in volume thereby forming a completed package, said supporting surface being a vertically movable platform, said overlying surface including a pair of plates having adjacent edges slightly spaced from each other to define a slot for passage of the free, open upper end of the bag, and means for elevating the platform a predetermined distance to compress the product and bag after the bag has been positioned on the platform and the free upper end thereof positioned in the slot, said means for elevating the platform including a fluid pressure operated piston and cylinder assembly having one end connected to the platform, a supporting framework for the platform with the other end of the piston and cylinder assembly operatively associated with the framework, guide means interconnecting the framework and platform for guiding vertical reciprocation of the platform, and foot operated means for controlling operation of the piston and cylinder assembly for causing reciprocation of the platform, said framework including a supporting surface in alignment with each end of the platform when the platform is in lowered position to facilitate sliding movement of a bag with the product therein onto the platform, and sealing means for the open upper end of the bag disposed above the slot between the plates.

perimeter and top edges into a mutually aligned, face-to-face, sealing relationship, both said perimeter and said top edges being continuous and unbroken throughout their length; and
inducing ultrasonic energy into said perimeter and top edges to seal said end closure panel to said others of said side panels.

4,292,788


NUCLEAR FUEL ROD LOADING APPARATUS
Harold B. King, Wrightsville Beach, N.C., assignor to General Electric Company, San Jose, Calif.

Filed Feb. 11, 1980, Ser. No. 120,231

Int. Cl.³ B65B 5/10, 57/06, 57/14

U.S. Cl. 53—500

22 Claims



1. An apparatus for loading fuel rods with fuel pellets repetitively in first and second sequences of operation comprising:
- a first and second elongated members for receiving fuel pellets to be loaded alternately in first and second fuel rods;
 - a fuel rod indexer for positioning first and second fuel rods for receiving said fuel pellets, said fuel rod indexer being effective for positioning said first fuel rod to be loaded with pellets from said first elongated member and for positioning said second fuel rod to be loaded with pellets from said second elongated member;
 - first means for transferring pellets from said first elongated member into said first fuel rod in a first sequence of operation, and second means for transferring pellets from said second elongated member into said second fuel rod in a second sequence of operation subsequent to said first sequence of operation; and
 - means for actuating said fuel rod indexer upon completion of said second sequence to reinitiate said first and second sequences of operation.

4,292,787

PAPERBOARD CARTON


Josef J. Buschor, Los Gatos, and Frederick R. Jennings, Cupertino, both of Calif., assignors to Pneumatic Scale Corporation, Quincy, Mass.

Continuation-in-part of Ser. No. 911,990, Jun. 2, 1978, abandoned, which is a continuation-in-part of Ser. No. 822,500, Aug. 8, 1977, abandoned. This application Dec. 4, 1979, Ser. No. 100,092

Int. Cl.³ B65B 3/02, 7/20; B31B 49/02

U.S. Cl. 53—456

13 Claims



1. A method of closing the top end of a carton comprising: forming a carton as a tube having a polygonal cross-section and a closed bottom end, said carton having plural substantially flat side panels, one of which extends above the others, to form a polygonal top end closure panel, each of said others having a top perimeter edge which extends, unbroken, through the entire width of said side panel and, unbroken, into the top edge of an adjacent side panel; filling said carton with a liquid; folding said top end closure panel with respect to said one of said flat sides to a position wherein said top panel is substantially perpendicular to each of said side panels; pressing the perimeter edges of said top panel and said top edges of said other side panels together to crease said

4,292,789

SPRING WIRE BLADES FOR DRUM TYPE MOWERS
Bernard C. Mathews, 8606 Rte. 176, Crystal Lake, Ill. 60014

Filed Apr. 15, 1980, Ser. No. 140,617


Int. Cl.³ A01D 35/264

U.S. Cl. 56—12.7

11 Claims

1. A mower including rotatable drums, each drum constructed with a vertically disposed cylindrical sleeve and a large diameter horizontally disposed disc at the bottom of the cylindrical sleeve, a blade comprising an L-shaped spring wire, a vertically disposed leg of the L-shaped wire disposed adjacent the wall of the cylindrical sleeve, means attaching the upper end of said vertical leg to said cylindrical sleeve, said disc having a hole therethrough closely adjacent said cylindrical sleeve to permit passage of said vertical leg, a horizontally disposed leg of the L-shaped wire adjoining the vertical leg immediately beneath the disc, said horizontal leg extending

radially outwardly of the disc, said horizontal leg having a portion thereof arranged and constructed to cut hay, and



whereby when said horizontal leg strikes an obstruction it may yield rearwardly by a torsional twisting of said vertical leg.

4,292,790


BLADE ARRANGEMENT FOR MULTIPLE ROTOR MOWERS

Bernard C. Mathews, 8606 Rte. 176, Crystal Lake, Ill. 60014
Filed Sep. 18, 1980, Ser. No. 188,505

Int. Cl.³ A01D 55/18

U.S. Cl. 56—13.6

7 Claims



1. A mower comprising a frame structure, a series of adjacent, horizontally disposed discs carried on said frame structure, said discs arranged in a single horizontal plane and having the circumferences of adjacent discs spaced slightly apart from one another, mowing blades associated with each of said discs, said mowing blades in their cutting position having a radial extent greater than the circumferences of the discs and continuing radially outwardly through the space between adjacent discs, the mowing blades of alternate discs being disposed beneath the discs and the mowing blades of the intermediate alternate discs being disposed above the discs, whereby although the blades of adjacent discs overlap the extent of each other they do not contact one another by reason of their being vertically offset.

4,292,791

CUTTING AND MULCHING LAWN MOWER BLADE ASSEMBLY

Jean-Paul Lalonde, 2 ouest, rue Saint-Jean Baptist, Rigaud, Quebec, Canada (JOP IPO)

Continuation of Ser. No. 9,451, Feb. 6, 1979, abandoned. This application Oct. 6, 1980, Ser. No. 194,035


Int. Cl.³ A01D 55/18

U.S. Cl. 56—255

1 Claim

1. A cutting and mulching blade assembly for a rotary lawn mower having a motor and a depending shaft projection, said assembly comprising a mulching blade and a hub member operatively used in cooperation with a cutting blade, said assembly being operatively securable to said depending shaft projection, each of said blades being of substantially equal length and each having a pair of opposite end portions, said

hub member operatively connecting said blades at generally right angles to each other for bodily rotation about the axis defined by said shaft projection and with the mulching blade spaced above the cutting blade by said hub member which is located between the two blades, each of said end portions of said two blades having a cutting leading edge, each end portion of the cutting blade having, transversely of the cutting blade, a rearwardly and upwardly inclined trailing edge portion, which extends longitudinally of said cutting blade from the outer end of the respective end portions of said cutting blade to a termination point short of said hub member, each end portion of the mulching blade having, transversely of said mulching blade, a rearwardly and downwardly inclined trailing edge portion terminated by a trailing edge, said trailing edge portion of said



4,292,792

ADJUSTABLE HARVESTING MACHINE FOR BLUEBERRIES AND OTHER PLANTS


Charles G. Burton, Lewiston, N.Y., assignor to Chisholm-Ryder Company, Inc., Niagara Falls, N.Y.

Filed Jul. 2, 1979, Ser. No. 53,817

Int. Cl.³ A01D 46/00

U.S. Cl. 56—330

19 Claims



1. An adjustment mechanism for the spoke-carrying shaft of a harvesting machine comprising first shaft means for defining a first axis, a second shaft having a second axis offset from and substantially parallel to said first axis, a plurality of vertically spaced spokes on said second shaft, means mounting said second shaft for movement in an orbit about said first axis, and adjusting means for adjusting the position of said second axis relative to said first axis to thereby vary the size of said orbit.

4,292,793

HAY HARVESTING MACHINE

Hans-Ulrich Hauser, Niederweningen, Switzerland, assignor to Bucher-Guyer AG Maschinenfabrik, Niederweningen, Switzerland


Filed Nov. 15, 1979, Ser. No. 94,968

Claims priority, application Switzerland, Nov. 21, 1978, 11900/78

Int. Cl.³ A01D 81/00

U.S. Cl. 56—378

11 Claims



1. A hay harvesting machine comprising:
at least one rake wheel rotatable about an upright axis;
said rotatable rake wheel comprising:
an essentially upright shaft defining said upright axis;
a rotatable housing portion;
means for rotatably mounting said rotatable housing portion for rotation about said upright shaft;
a number of tine supports each having a lengthwise axis mounted for pivotable movement about their lengthwise axis at the rotatable housing portion;
each of said tine supports having rake tines;
each of said tine supports extending essentially in tangential direction with respect to said rotatable housing portion;
control track means connected non-rotatably with said upright shaft for pivoting said tine supports;
said control track means extending in a plane disposed essentially perpendicular to said upright shaft;
said control track means being arranged above said tine supports;
said tine supports extend rearwardly with respect to the direction of rotation; and
said control track means comprising a first track portion arranged essentially coaxially with respect to the upright shaft and a second track portion which, in relation to the first track portion, extends at a greater spacing from said upright shaft.

4,292,794

RAKE

Lorenzo Gascon, 175 Archambault St., Hull, Quebec, Canada
Filed Feb. 12, 1980, Ser. No. 120,787


Int. Cl.³ A01D 7/00

U.S. Cl. 56—400.16

2 Claims

1. A pick-up rake comprising a rake handle having a main rake head secured to its lowermost end,
and an auxiliary rake head assembly including an auxiliary rake head having a plurality of tines carried by the rake handle and selectively movable from an upper storage position enabling normal raking to a lower position enabling leaves, grass and debris to be gathered and held between the two rake heads,
the auxiliary rake head assembly also including a shaft pivotally secured at its upper end to a handle sleeve which is slidable along the rake handle,
the upper ends of the tines of the auxiliary rake head being secured closely together on a tine-plate which is secured to a shaft sleeve freely slidable along the shaft, the tines being slidably movable through a tine-guide which is fixedly secured to the lower end of the shaft,

and a pair of links pivotally interconnecting the rake handle and the shaft sleeve,
full upward movement of the handle sleeve along the handle moving the auxiliary rake head to storage position and downward movement moving the auxiliary rake head to gathering position,
in gathering position the shaft sleeve being downwardly positioned with respect to the shaft to extend the tines



4,292,795

STRAW AND CHAFF CHOPPER AND SPREADER


Orville J. Linn, Box 188, Lang, Saskatchewan, Canada

Filed Nov. 19, 1979, Ser. No. 95,671

Int. Cl.³ A01D 49/00

U.S. Cl. 56—503

22 Claims



1. A chopper and spreader for attachment below a straw and chaff discharge of a grain threshing machine such as a combine or the like and adapted to be driven by a source of power on the machine in which said grain threshing machine includes a straw walker assembly and a sieve assembly both situated spaced forwardly of the straw and chaff discharge of the threshing machine; said chopper and spreader comprising in combination a substantially horizontally located casing securable to said machine below the straw and chaff discharge thereof, straw and chaff intake means on the upper side of the casing operatively connected to the straw and chaff discharge, rotatable straw chopping means journaled for rotation substantially horizontally, in said casing and chopped straw discharge means through at least part of the wall of said casing, said straw chopping means being operatively connectable to the source of power on the associated machine, and a transverse divider in the upper side of said casing dividing said straw and chaff intake means into a front straw intake portion

and a rear chaff intake portion, said transverse divider being adjustable in height to vary the position of the upper edge thereof relative to said chaff discharge.

4,292,796

PNEUMATIC YARN SPLICING APPARATUS

Hiroshi Mima, Joyoshi, Japan, assignor to Murata Kikai Kabushiki Kaisha, Japan


Filed Feb. 5, 1980, Ser. No. 118,856

Claims priority, application Japan, Feb. 9, 1979, 54-14607

Int. Cl.³ D01H 15/00

U.S. Cl. 57-22

3 Claims



1. Yarn splicing apparatus comprising a yarn end cutting and holding device for the lower yarn end, a yarn end cutting and holding device for the upper yarn end, two air jet nozzles having an elongated yarn inserting hole into which spun yarn ends are introduced, said air jet nozzles being arranged between the yarn end cutting and holding devices so that a space is formed between the two air jet nozzles, and air jet means communicating with the hole to create a swirling air stream, wherein said air nozzles are disposed to produce jetted air streams swirling in directions opposite to each other in the respective holes.

4,292,797

DUBBING WINDER


Arnold J. Auger, 1482 Zener, Pocatello, Id. 83201

Filed Feb. 13, 1980, Ser. No. 121,302

Int. Cl.³ D02G 3/42

U.S. Cl. 57-24

12 Claims



1. A device for twisting dubbing on a thread, comprising: a base member having a substantially planar upper surface and opposite ends, a rotatable hook mounted on one of said ends of said base member, means for rotating said hook, said hook extending over said base member and being substantially parallel thereto; anchor means mounted on the other of said ends for tying two ends of the thread at fixed laterally spaced positions, and means on the base member for inserting the dubbing on the thread.

4,292,798

STRAND BREAK-OUT DEVICE

Colin E. Gore, Ilkley, and John P. Coulter, Shipley, both of England, assignors to Wool Development International Limited, London, England


Filed Jan. 29, 1980, Ser. No. 116,500

Claims priority, application United Kingdom, Feb. 6, 1979, 04177/79; Apr. 23, 1979, 14066/79; Aug. 1, 1979, 26777/79

Int. Cl.³ D01H 13/16

U.S. Cl. 57-86

32 Claims



1. A strand break-out device for prevention of faults due to strand breakage when combining two unspun fibrous strands into a yarn on a common twisting spindle, the device comprising a member having passage means to which, in use, said strands converge from opposite sides of a centre line of said passage means so that both said strands pass through said passage means and may bear thereon to apply force to the said member, a support, means mounting said member on said support, said support and said member being such that said member may move freely under forces applied by said strands in normal operation between limits of displacement from a mean, stable position relative to said support and may additionally move beyond either said limit on breakage of one of said strands only by overcoming a resistance to such additional movement, each such additional movement being to a further position wherein said passage means introduces a distortion into the path that the remaining one of said strands would normally take so causing said remaining strand to break.

4,292,799

SPUN YARN-LIKE TEXTURED YARNS AND PROCESS FOR PRODUCING SAME

Yukio Otaki, Kazuo Umeda, and Kiyoshi Nakagawa, all of Mishima, Japan, assignors to Toray Industries, Inc., Tokyo, Japan


Filed Oct. 17, 1979, Ser. No. 85,635

Claims priority, application Japan, Oct. 26, 1978, 53/131798; Nov. 24, 1978, 53/144254

Int. Cl.³ D02G 3/04, 3/24; D02J 3/02

U.S. Cl. 57-246

10 Claims



1. A spun yarn-like textured yarn comprised of two types of polyester multifilament component yarns A and B, the differ-

ence in monofilament denier $\Delta[d]_{B-A}$ of the component yarn B from the component yarn A being not less than 1.8 denier, the monofilament denier of the component yarn A being not more than 1.6 denier, and the textured yarn having a broken filament count of not more than 40 per meter of its length, a crimp stretchability of not more than 23%, a difference in length between the component yarns A and B of not less than 1% and a bulk factor of not less than 9 cc/g.

4,292,800

TEXTILE MACHINE DATA LINK APPARATUS



Lyman L. Werst, Acton, Mass., assignor to Parks-Cramer Company, Fitchburg, Mass.

Filed Sep. 28, 1979, Ser. No. 79,798

Int. Cl.³ D01H 13/32; H03K 13/24

U.S. Cl. 57-264

11 Claims



1. In the combination of a traveling unit, moving past spindle locations at which ends of yarn normally are formed along one or more textile yarn forming machines and having means responsive to certain operations such as formation of ends of yarn for signaling certain states of said operations such as an end down at a spindle location, with data link means having transmitter means for communicating data concerning said operations, the improvement in said data link means wherein said transmitter means comprises:

first and second oscillators generating signals of predetermined first and second frequencies, data signal input gates operatively connected to said oscillators for selectively passing signals of one of said frequencies and for frequency shift keying binary data, a phase locked loop circuit operatively connected to said gates for receiving signals passed therethrough as a reference signal and for generating an output signal of a predetermined frequency correlated to said reference signal and having programming means for selecting a channel of frequencies for operation of said data link means, said oscillators and said phase locked loop circuit cooperating to function as a frequency synthesizer, and radio frequency output means operatively connected to said phase locked loop circuit for emitting a radio frequency signal in response to and at a frequency determined by said output signal from said phase locked loop circuit.

4,292,801

DUAL STAGE-DUAL MODE LOW NOX COMBUSTOR


Colin Wilkes, Scotia, and Milton B. Hilt, Sloansville, both of N.Y., assignors to General Electric Company, Schenectady, N.Y.

Filed Jul. 11, 1979, Ser. No. 56,510

Int. Cl.³ F23R 3/34

U.S. Cl. 60-39.06

19 Claims



1. A method of operating a gas turbine combustor to achieve low emissions of nitrogen oxide, said combustor including first and second combustion stages separated by a throat region of reduced diameter relative to said combustion stages with a plurality of fuel nozzles and air swirlers for introducing fuel and air respectively into said first stage and a single fuel nozzle and air swirler positioned adjacent said throat region for introducing additional fuel and air respectively into said second stage, said method comprising:

introducing fuel and air into said first stage from said plurality of fuel nozzles and air swirlers for mixing therein to create a combustible fuel-air mixture; introducing additional fuel and air into said second stage from said single fuel nozzle and air swirler, said additional fuel and air mixing with the combustible fuel-air mixture in said second stage for combustion therein and wherein the step of introducing additional fuel and air into said second stage from said single fuel nozzle and air swirler includes locating said single fuel nozzle and air swirler relative to said throat region and dimensioning said throat region relative to said combustion stages to minimize flashback from said second combustion stage to said first combustion stage; introducing additional air into said second stage from said throat region for further reducing the possibility of flashback into said first stage from said second stage; introducing dilution air into the downstream end of said second stage to reduce residence time of the products of combustion at NOx producing temperatures in said second stage; and adjusting the fuel flow to said single fuel nozzle and said plurality of fuel nozzles while maintaining a substantially constant total fuel flow until a majority of the total fuel flow is equally distributed among said plurality of fuel nozzles.

4,292,802

METHOD AND APPARATUS FOR INCREASING COMPRESSOR INLET PRESSURE

Barton H. Snow, Wyoming, Ohio, assignor to General Electric Company, Cincinnati, Ohio

Filed Dec. 27, 1978, Ser. No. 973,766

Int. Cl.³ F02K 3/075


U.S. Cl. 60-204

5 Claims

1. A method of facilitating air starts in a turbofan engine of

the type having a core, a fan, and a bypass duct, comprising the steps of:

- (a) blocking the flow of air in the bypass duct; and



- (b) increasing the inlet pressure to the compressor to a level which will allow an air start.

4,292,803

TURBO FAN ENGINE MIXER


Barry Prior, San Diego, Calif., assignor to Rohr Industries, Inc., Chula Vista, Calif.

Filed Jan. 19, 1979, Ser. No. 4,674

Int. Cl.³ F02K 1/00

U.S. Cl. 60-230

3 Claims



1. Apparatus for a turbo-fan engine having a central core and an elongated cowl section spaced from said central core forming a fan duct therebetween, an engine plug attached to said central core and extending downstream thereof, the aft surface of said engine plug defining the aft boundary of said fan duct, said engine having primary and fan gas streams directing aft through said fan duct comprising:

nozzle means for introducing said primary gas stream into said fan duct, said nozzle means comprising a plurality of individual tubes attached around said central core by aerodynamic fairings whereby a substantial mixing of the gas streams is accomplished within said fan duct.

2. The apparatus as defined in claim 1, wherein said apparatus additionally includes blocker doors for reversing the direction of said gas streams, said nozzle means and said aerodynamic fairings being positioned so that when said blocker doors are displayed to their gas stream reversing position, a layer of fan gas impacts and insulates said blocker doors from the mixed gas streams.

4,292,804

METHOD AND APPARATUS FOR OPERATING AN ENGINE ON COMPRESSED GAS


Leroy K. Rogers, Sr., #5 Capistrano Ct., Ft. Myers, Fla. 33908

Filed Jun. 10, 1980, Ser. No. 158,303

Int. Cl.³ F15B 11/06

U.S. Cl. 60-407

22 Claims



1. An apparatus for operating an engine having at least one cylinder and a reciprocating piston therein comprising: a source of compressed gas; distributor means connected with the source of compressed gas for distributing the compressed gas to the at least one cylinder; valve means for admitting the compressed gas to the at least one cylinder when the piston is in approximately a top dead center position within the cylinder; altering means for increasing the duration of each engine cycle over which the valve means admits compressed gas to the at least one cylinder as the speed of the engine increases; and exhaust means for exhausting gas as the piston subsequently approaches approximately the top dead center position.

4,292,805

SERVO-VALVE CONVERTIBLE CONSTRUCTION


John L. Acheson, Franklin, Wis., assignor to Rexnord Inc., Milwaukee, Wis.

Filed Sep. 24, 1979, Ser. No. 78,332

Int. Cl.³ F04B 1/26, 49/08; F16H 39/46

U.S. Cl. 60-450

8 Claims



1. A control valve in combination with a hydraulic system which includes a variable displacement pump and a flow restrictor, an output line therebetween, a delivery line from the restrictor for connection to a load, a return line and a control displacement line to the pump, means responsive to output line pressure acting to reduce pump displacement, the pump displacement being varied directly by pressure variations in said displacement control line acting on pressure responsive displacement control means; said valve including a valve body

and a spool which is axially movable therein and defines therewith first and second restricted passages, said valve body having means for connection with said output, displacement controls, and return lines to provide a pilot flow of fluid from the output line and through said passages to the return line and to the displacement control of line for varying pump displacement by the pressure intermediate said passages, a spring biasing said spool in one direction and toward one end of the valve body to close said second passage to the return line to raise the pressure in the displacement control line whereby pump displacement is increased, and means for connecting said one end of the valve body with the output line whereby pump output pressure is effective to move the spool in the other direction and against said spring and to open said second passage to the return line to lower pressure in the displacement control line whereby pump displacement is decreased; said valve further including a spool abutment device comprising a cylinder, a piston movable therein, a spring biasing said piston in one direction and toward one end of the cylinder, an axially movable pin extending from the piston and through the other end of the cylinder, means removably connecting said other end of the cylinder to said one end of the valve body whereby the pin is engageable by abutting the spool and only limits movement of the spool in said one direction only, and means for connecting said one end of the cylinder with the output line and the other end of the cylinder with the delivery line such that the pressure differential effected by the restrictor and operating against said piston and last named spring positions said pin in accordance with said pressure differential and allows pump displacement to be varied only up to a selected maximum pump output and without otherwise interfering with the operation of the control valve.

4,292,806

TURBOCHARGER CONTROL SYSTEM


M. Samuel Moore, and Charles F. Paluka, both of Northridge, Calif., assignors to Semco Instruments, Inc., North Hollywood, Calif.

Filed Feb. 28, 1979, Ser. No. 15,956

Int. Cl.³ F02B 37/12

U.S. Cl. 60-600

4 Claims



1. A control system for a diesel engine having a turbocharger with a turbine section operated by the exhaust gases from said engine, and a compressor section powered by said turbine section for supplying air to the inlet manifold of said engine, and including means for variably controlling the flow of the gases passing through both the turbine and the compressor sections of said turbocharger, and means for independently adjusting the variable controlling means for said compressor and said turbine sections, comprising: first and second actuators for shifting the variable control-

ling means for the gases passing through said compressor and said turbine sections, respectively;

electronic circuit means for controlling said first compressor actuator in accordance with a substantially linear function of the speed of the engine, and with an incremental additional actuation in accordance with the inlet manifold pressure;

electronic circuit means for controlling said second, turbine actuator in accordance with the theoretical optimum or desired engine input manifold pressure as derived from the speed of the engine and the temperature at the input of the turbine, modified by an error signal obtained by comparing the actual manifold pressure with the derived manifold pressure, whereby said turbine and compressor are operated just below "stall" or "cavitation" conditions, whereby substantially optimum operation is achieved; and said turbine actuator controlling means including circuitry responsive to the product of the speed and the temperature for determining the theoretical engine input manifold pressure.

3. A control system for an engine having a turbocharger with a turbine section and a compressor section powered by said turbine section for supplying air to the inlet manifold of said engine, and including means for variably controlling the flow of gases passing through both the turbine and the compressor sections of said turbocharger, and means for independently adjusting the variable controlling means for said compressor and said turbine sections, said engine having a cooling fan and associated clutch means for actuating said cooling fan, comprising:

first actuator means for shifting the variable controlling means for the gases passing through said compressor sections of said turbocharger;

second actuator means for shifting the variable controlling means for the gases passing through said turbine section of said turbocharger;

electronic circuit means for controlling said first compressor actuator in accordance with a substantially linear function of the speed of the engine;

electronic circuit means for controlling said second, turbine actuator in accordance with the theoretical optimum or desired engine input manifold pressure as a function of the power output of said engine to operate said turbine and compressor just below "stall" or "cavitation" conditions, whereby substantially optimum operation is achieved; means included in said electronic circuit means for changing the control signal applied to said turbine actuator and maintaining desired operating conditions substantially continuously as the speed of said engine varies; and maximum acceleration electronic control means for de-clutching the engine cooling fan and for overriding said turbine actuator control circuitry and rapidly increasing the flow in the turbine section of the turbocharger, thereby increasing the input manifold pressure.

4,292,807

VARIABLE GEOMETRY TURBOSUPERCHARGER SYSTEM FOR INTERNAL COMBUSTION ENGINE

George C. Rannenberg, Canton, Conn., assignor to United Technologies Corporation, Hartford, Conn.

Filed May 2, 1979, Ser. No. 35,185

Int. Cl.³ F02B 37/12


U.S. Cl. 60-601

18 Claims

1. In a turbosupercharger system for an internal combustion engine, said turbosupercharger including a compressor having an outlet diffuser and a turbine having an inlet nozzle, said turbine being driven by exhaust gases from said engine and being connected to drive said compressor to raise the pressure of air supplied to said engine;

means including a first movable member connected to said compressor outlet diffuser and adapted to vary the geometry thereof such that the effective diffuser area at the exit

of said compressor is varied in response to said first member;
means including a second movable member connected to said turbine inlet nozzle and adapted to vary the geometry thereof such that the effective turbine nozzle area at the inlet to said turbine is varied in response to said second member;



means for sensing a condition of operation of said engine and producing a signal indicative thereof;
and actuator means connected to said first and second movable members and responsive to said signal for simultaneously moving said members and thereby varying the geometry of said compressor outlet diffuser and said turbine inlet nozzle in a fixed geometrical relationship.

4,292,808


ENERGY CONVERTER

Edward W. Lohmiller, 2445 S. 13th Ave., Broadview, Ill. 60153
Filed Apr. 2, 1979, Ser. No. 26,007

Int. Cl.³ F01K 25/06

U.S. Cl. 60-673

4 Claims



1. An energy converting system for converting energy from a relatively low thermal source into useful energy comprising:
a carrier fluid;
a compressible working medium absorbable by said carrier fluid and convertible between the liquid and gaseous states;
evaporator means receiving heat energy from a relatively low thermal source for transferring the working medium from the liquid to the gaseous states;
absorption means connected to receive the gaseous working medium from said evaporator and to receive said carrier fluid for absorbing the gaseous working medium into said carrier fluid to provide a concentrated fluid-medium mixture;
separator means receiving the concentrated fluid-medium mixture separating the working medium from said concentrated fluid-medium by compressing the concentrated fluid-medium mixture;

conduit means returning said carrier fluid from the separator to said absorption means;
condenser means discharging heat energy connected to receive the working medium from said separator means for converting the gaseous working medium to a liquid state;
conduit means connecting said condenser means to said evaporator means;
energy converting means operatively connected with said separator means between the said absorption means and the said condenser means for converting energy from said working medium to another form of energy.

4,292,809


PROCEDURE FOR CONVERTING LOW-GRADE THERMAL ENERGY INTO MECHANICAL ENERGY IN A TURBINE FOR FURTHER UTILIZATION AND PLANT FOR IMPLEMENTING THE PROCEDURE

Björn A. Björklund, Västerhaninge, Sweden, assignor to AB Svenska Fläktfabriken, Fack, Stockholm, Sweden
Filed Jul. 17, 1979, Ser. No. 58,135

Claims priority, application Sweden, Jul. 24, 1978, 7808104
Int. Cl.³ F01K 13/00, 25/08; F25B 27/02

U.S. Cl. 60-676

12 Claims



1. A method for converting low-grade thermal energy into mechanical energy in a turbine for further utilization, comprising evaporating a first cooling medium in a heating device by means of a low-grade heating medium coming from outside, carrying the evaporated steam from said heating device to at least one turbine for energy conversion, following which the moist steam leaving said turbine is carried to a first cooling device for condensing, pumping the condensate via a feed pump back to the heating device, the heat removed during condensing being absorbed by a second evaporating cooling medium, the steam of which created thereby is pumped via at least one heat pump in order to obtain a higher condensing temperature, after which condensing is caused to take place in a second cooling device which is cooled by outgoing cooled medium from the heating device, carrying the condensate via an expansion valve back to the first cooling device while outgoing cooled medium from the heating device is heated in its entirety to a level lower than the temperature level at the entrance of the heating device.

4,292,810

GAS TURBINE COMBUSTION CHAMBER

Robert G. Glenn, Lower Moreland Township, Montgomery County, Pa., assignor to Westinghouse Electric Corp., Pittsburgh, Pa.

Filed Feb. 1, 1979, Ser. No. 8,318


Int. Cl.³ F02C 7/20

U.S. Cl. 60-757

4 Claims

1. A combustion chamber for a combustion turbine engine, said chamber defining a generally cylindrical configuration having an inlet end and an opposed discharge end and with a portion intermediate the opposed ends defining an outwardly stepped configuration comprising a plurality of axially extending serially arranged cylindrical segments with each down-

stream segment having a larger diameter than the adjacent upstream segment and annular transition means integrally connecting the trailing edge of each downstream segment to the leading edge of each adjacent upstream segment,
said annular transition means defining apertures for admitting air therethrough into said chamber;
a cylindrical baffle means encircling each cylindrical segment in spaced relation therewith defining an annular airflow passage therebetween, said baffle means axially extending from generally adjacent the upstream transition means to generally adjacent the openings in the downstream transition means whereby air flowing through said passage is directed into said downstream openings in said transition piece;



a plurality of spring means interposed in said passage between each segment and said encircling baffle means and biased to maintain a separating force therebetween, said spring means attached only to either said baffle means or said segment to accommodate relative thermal growth both radially and axially between said segment and baffle means;

said plurality of spring means including a plurality of generally circumferentially oriented leaf spring elements forming an annular array, with a pair of such arrays respectively disposed generally adjacent the upstream and downstream portions of each baffle means; and
abutment means for limiting axial movement of the free ends of said leaf spring elements and thereby limiting relative axial movement of said baffle means and said segments.

4,292,811

OPERATING METHOD FOR REFRIGERATING MACHINE

Kohji Kamejima; Hideki Tanaka; Minoru Kano, and Toshihiko Fukushima, all of Shimoinayoshi, Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed Jul. 16, 1979, Ser. No. 57,651

Claims priority, application Japan, Jul. 14, 1978, 53-85115

Int. Cl.³ F24D 11/00; F25D 3/00

U.S. Cl. 62-56

7 Claims



1. An operating method for refrigerating machines having a load predictor for predicting a load on a prearranged day for refrigerating operation, an ambient temperature predictor for predicting a variation of the ambient temperature on the prear-

ranged day, and heat accumulating means for accumulating the output of the refrigerating machine, comprising the steps of operating the refrigerating machine during a predetermined air-conditioning period by:

- (1) operating said load predictor at a point in time prior to said predetermined air-conditioning period for producing a load variation pattern indicative of the load that would be experienced by said refrigerating machine during said air-conditioning period;
- (2) operating said ambient temperature predictor at a point in time prior to said predetermined air-conditioning period for producing an ambient temperature variation pattern indicative of the ambient temperatures that would be experienced during said air-conditioning period;
- (3) dividing said ambient temperature variation pattern into a plurality of time intervals and assigning a priority ranking to each interval as a function of a temperature value of said temperature variation pattern produced for each interval;
- (4) determining the output capacity of said refrigerating machine;
- (5) determining the number of said time intervals, in order of priority ranking, and the refrigerating output capacity producible therein for the output of said refrigerating machine to at least equal an integrated value of said load variation pattern and producing a refrigerating machine operating schedule in accordance therewith; and
- (6) controlling the operation of said refrigerating machine during said predetermined period in accordance with said operating schedule.

4,292,812

Mitsuru Kakinuma, Sakaimachi, and Yoshitaka Takahashi, Gumma, both of Japan, assignors to Sanyo Electric Co., Ltd. and Tokyo Sanyo Electric Co., Ltd., both of Osaka, Japan


Filed Apr. 29, 1980, Ser. No. 144,930

Claims priority, application Japan, May 2, 1979, 54-54494

Int. Cl.³ F25C 1/00

U.S. Cl. 62-157

8 Claims



1. In a control device for an ice making machine to make ice by circulating ice-making water to an ice making member having a refrigerating system, control device comprising a timer circuit to be operated to control a period of time during which an ice making operation is performed, and a temperature sensing element whose impedance varies with the variations of temperature for sensing an operating condition of said refrigerating system, so that an input voltage applied to said timer circuit varies with the variations of an impedance of said temperature sensing element, thereby to automatically control the period of time during which an ice making operation of one cycle is performed.

4,292,813

ADAPTIVE TEMPERATURE CONTROL SYSTEM



Stephen W. Paddock, Evansville, Ind., assignor to Whirlpool Corporation, Benton Harbor, Mich.

Filed Mar. 8, 1979, Ser. No. 18,762

Int. Cl.³ G05D 23/32; F23N 5/20

U.S. Cl. 62-158

27 Claims



1. A temperature control system for a heating or cooling device, comprising:
 - a temperature sensor for monitoring the temperature of a space;
 - means for repeatedly operating the device in cycles, each cycle having an on portion during which the device is energized and an off portion during which the device is deenergized;
 - means coupled to the temperature sensor for controlling the duration of one of the repeated portions of the cycle in accordance with the sensed temperature;
 - measurement means for measuring the temperature controlled portions of the cycle;
 - means operative during the normal cyclic operation of the device for varying the duration of the repeated other portion of the cycle in response to the measurement of at least one of the temperature controlled portions of the cycle.

4,292,814

HEAT PUMP

Anton Braun, 6421 Warren Ave., Minneapolis, Minn. 55435

Filed Jun. 13, 1979, Ser. No. 48,527


Int. Cl.³ B60H 3/04

U.S. Cl. 62-243

5 Claims

1. A heat pump having internal combustion engine driven compressor means, a condenser, an evaporator and closed fluid flow circuit means between said compressor means, condenser and evaporator, characterized in that said condenser has fluid actuable fan means arranged to force air through said con-

denser, said evaporator has fluid actuable fan means arranged to force air through said evaporator and each of said fluid



actuable fan means has a fluid flow connection with said compressor means.

4,292,815

DOOR ASSEMBLY FOR A SELF-CONTAINED AIR CONDITIONING UNIT


Theodore S. Bolton, Liverpool, N.Y., assignor to Carrier Corporation, Syracuse, N.Y.

Filed Jul. 25, 1979, Ser. No. 60,327

Int. Cl.³ F25D 23/12

U.S. Cl. 62-262

7 Claims



1. An air conditioning unit having a flow path through which conditioned air is discharged to a space which comprises:
 - a casing defining a discharge opening through which the conditioned air may flow, said opening having side surfaces which each define a pair of slots;
 - a door to cover the discharge opening, said door having a pair of pins extending from each end surface of the door, said pins being adapted to engage the slots defined by the side surface of the casing whereby the door may be rotated to various open positions; and
 - a friction wedge mounted to extend from the door to engage the side surface of the casing for securing the door in a position, said friction wedge including an inclined surface extending from the door to engage an edge of a slot in the casing such that the door may be partially opened to the position at which the inclined surface engages the slot edge by the force exerted against the door by the conditioned air conducted along the flow path through the opening.

4,292,816

ICE MAKING APPARATUS

Rudolph E. Gartzke, 2326 Superior St., Madison, Wis. 53704

Continuation-in-part of Ser. No. 936,233, Aug. 24, 1978, and Ser. No. 793,936, May 5, 1977, abandoned. This application Dec. 26, 1979, Ser. No. 106,706


Int. Cl.³ F25C 1/10

U.S. Cl. 62-345

12 Claims

1. An ice making machine for producing ice in discrete small pieces by use of mechanical refrigeration, comprising in combination,
 - (a) a stationary plate provided with at least two separate, integral passages containing fluid refrigerant wherein said

- passages are operably communicated by sealed connections to refrigerant lines external to said plate,
- (b) a refrigeration compressor wherein the outlet of said compressor is communicable to at least one said passage individually for providing hot, compressed vaporous refrigeration fluid in said passage to heat said plate and thaw ice deposited on a surface in proximity of said passage,
 - (c) a refrigerant condenser for liquifying refrigerant vapor wherein the outlet of said condenser is communicable to at least another said passage individually for providing cold, rarified vaporous refrigeration fluid in said passage through means of an expansion valve to refrigerate said plate and freeze moisture deposited on a surface in proximity of said passage,
 - (d) concavities configured in a surface underlying said plate,
 - (e) pressurized water spray means wherein water spray is directed to impinge against said concavities,
 - (f) means for effecting mutual progression of said concavities repetitively from proximity to one said passage heated to



like therein from the top surface with a peripheral portion of each stone extending over the contiguous connecting portions;

forming a deformably enlargeable and compressible securing slot at each connecting portion above the top surface of the setting and receptive of the peripheral portions of the stones by fixing one end of at least one elongated support member to the setting between the two rows of two adjacent cavities to dispose same in alignment with the connecting portions with the longitudinal axis thereof normal to the top surface and fixing an intermediate portion of at least one deformable securing rod to the other end of the support member to dispose same parallel to and spaced from the top surface and in alignment with the aligned connecting portions;

deforming the slots to enlarge same and inserting the stones in the cavities with the peripheral portions in the slots; and deforming the slots to compress same to secure the stones in place.

4,292,819

SHEAR PIN COUPLING

Ary van der Lely, Maasland, and Cornelis J. G. Bom, Rozenburg, both of Netherlands, assignors to C. van der Lely N.V., Maasland, Netherlands


Filed Jan. 17, 1979, Ser. No. 4,165

Claims priority, application Netherlands, Jan. 18, 1978, 7800577

Int. Cl.³ F16D 3/56, 7/00

U.S. Cl. 64—28 R

21 Claims



1. A shear pin coupling comprising a first coupling part connected to a second coupling part through a shear pin that prevents relative displacement between the two parts in at least one direction, said pin having a longitudinal axis and guide means urging the pin in a direction generally parallel to said axis to establish an operative connection between said two parts, said pin being fractured upon overload to permit relative movement between the parts in said one direction and the remainder of said pin being urged in the pin's axial direction by said guide means to re-establish said operative connection between the two parts, an end portion of said guide means cooperating with said pin to oppose non axial movements of the pin.

4,292,820
METHOD OF AND APPARATUS FOR KNITTING THE
HEEL OF A HOSIERY ARTICLE

Igor V. Ragoza, Moskovsky prospekt, 7, kv. 114; Petr M. Begunov, ulitsa Shirokaya, 30, kv. 5; Robert T. Tonikian, ulitsa Chkalova, 11, korpus 10, kv. 92, and Petr J. Vasiljuk, ulitsa Chkalova, 11, korpus 12, kv. 79, all of Vitebsk, U.S.S.R.


Filed Jul. 30, 1979, Ser. No. 62,181

Claims priority, application U.S.S.R., Oct. 20, 1978, 2686186; Jan. 17, 1979, 2704501; Jan. 23, 1979, 2707351

Int. Cl.³ D04B 9/00

U.S. Cl. 66—8

8 Claims



1. A method of knitting the heel of a hosiery article with two warp thread systems in a circular warp-knitting machine, including: guiding or laying two systems of warp threads on knitting needles by means of two systems of thread guides, actuating these thread guides for displacement both along the front presented by the knitting needles and intermediate these needles, knitting main loop courses and additional loop courses; knitting said additional loop courses between the main loop courses and making them shorter than the main loop courses, from some of the warp threads of the two warp thread systems, by disengaging some of the knitting needles along a portion of the circumference of the knitting cylinder; while knitting said additional loop courses, and actuating both systems of the thread guides along the front presented by the knitting needles, behind their backs, through steps which are greater than the steps through which these thread guides are actuated, while knitting the main loop courses.

4,292,821

NEEDLE SELECTION MECHANISM IN A
HAND-OPERATED KNITTING MACHINE

Mitsuhiro Koike, and Yasuhiro Iwasaki, both of Kodaira, Japan, assignors to Silver Seiko, Ltd., Kodaira, Japan


Filed Nov. 27, 1979, Ser. No. 98,335

Claims priority, application Japan, Dec. 4, 1978, 53/149002

Int. Cl.³ D04B 7/00, 15/66

U.S. Cl. 66—75.2

6 Claims



1. Needle selection mechanism in a hand-operated knitting machine of the type having a needle bed with a plurality of

knitting needles mounted therein and a carriage mounted for longitudinal slidable movement of the needle bed, the mechanism comprising a program carrier mounted alongside the needle bed and carrying a patterning program in the form of punched holes arranged in rows and columns thereon, the mechanism further comprising a first drum means having thereon a plurality of settable elements adapted to be set from their initial position in accordance with a row of the punched holes when the carriage passes over the program carrier in a direction, the first drum means being mounted for rotation about an upright shaft fixed on the carriage and having thereon an integral gear adapted to be engaged, at one diametrical position thereof, with a rack provided along the needle bed, the gear being engaged, at the other diametrical position thereof, with a second gear which is integrally attached to a second drum means, the second drum means being rotatable about an inclined shaft fixed on the carriage and having thereon a plurality of settable elements mounted for engagement with the corresponding settable elements on the first drum means to be set thereby from their initial position in accordance with the settings of the first drum means, the second drum means being operable to select the knitting needles in accordance with the settings of the settable elements thereon during movement of the carriage in the other direction on the needle bed, all the settable elements on the first and second drum means being restored to their initial positions by a clearing means mounted on the carriage after completion of selection of the knitting needles in accordance with the settings on the second drum means, and the clearing means including a common clearing member which is mounted for pivotal motion from an initial inoperative position to an operative position in which it is engaged with the settable elements of the first and the second drum means in their set positions to restore same to their initial positions.

4,292,822

APPARATUS FOR RANDOMLY COLORING PILE
FABRIC

James Toland, Dalton, Ga., assignor to World Carpets, Inc., Dalton, Ga.

Division of Ser. No. 832,905, Sep. 13, 1977, Pat. No. 4,189,302.

This application Jan. 4, 1978, Ser. No. 866,913

Int. Cl.³ D06B 21/00

U.S. Cl. 68—5 D

6 Claims



1. A system for coloring the pile yarns of a carpet web or the like including means for continuously conveying the web through several successive operating stations, means for pre-treating the pile yarns to be colored with a wetting agent at one of said operating stations, roll applicator means for applying to the surface tips of the pile yarns a continuous layer of viscous gum coating approximately $\frac{1}{8}$ to $\frac{1}{4}$ inch thick at a second operating station, roll applicator means at a third operating station for applying on said viscous gum coating a continuous layer of dyeing agent approximately $\frac{1}{8}$ to $\frac{1}{4}$ inch thick to color the surface of the lower body portion of the yarns beneath the tips of said pile yarns coated with said gum coating as said web is conveyed and steamer means at a fourth operating station for subjecting said web to an elevated temperature for setting said dye color, said steamer means being disposed downstream of said third station a sufficient distance such that said applied dyeing agent penetrates said gum layer before reaching said fourth station such that only the lower body portions of the pile yarns are colored and the tips of said pile yarns are substantially undyed.

4,292,823

CYLINDER LOCK WITH PLATE TUMBLERS

Theodor Reinhard, Böblingen; Rolf Krügener; Hermann W. Kurth, both of Sindelfingen; Diether Bläich, Stuttgart; Franz Rothmaier, Velbert; Dieter Kopperschlager, Sprockhövel; Heinz Schmitz, and Edgar Nill, both of Velbert, all of Fed. Rep. of Germany, assignors to Daimler-Benz Aktiengesellschaft, Stuttgart, Fed. Rep. of Germany


Filed Apr. 3, 1979, Ser. No. 26,602

Claims priority, application Fed. Rep. of Germany, Apr. 10, 1978, 2815380

Int. Cl.³ E05B 15/14, 29/02

U.S. Cl. 70—364 R

13 Claims



1. A cylinder lock including a plurality of plate tumblers disposed in a lock cylinder rotatably received in a lock casing; a locking channel means arranged in the lock casing; an escape channel means arranged in the lock casing at a position diametrically opposed to the locking channel means for enabling a free resetting motion of the plate tumblers during an insertion of a key into the cylinder lock; each of the plate tumblers including a locking end that is operable to be displaced a predetermined distance into the locking channel means when said key is removed from the cylinder lock; a counter end operable to be displaced a predetermined distance into the escape channel means during said resetting motion; and tumbler governing edges adapted to be arranged at levels corresponding with cutout depths of the key; and means for normally urging the locking ends of the plate tumblers into the locking channel means when the cylinder lock is in a locked position with the key removed, characterized in that security means are provided for preventing a determination of respective heights of the tumbler governing edges of the plate tumblers, said security means comprising stop means provided in at least the escape channel means for limiting said resetting motion of the individual plate tumblers to its respective predetermined distance into said escape channel in cooperation with blocking stop means on said counter ends that are cooperable with the stop means for controlling a positioning of the individual plate tumblers, the blocking stop means being arranged in dependence on the respective heights of associated tumbler governing edges, at least some of which are different, so that the tumbler governing edges of the at least some of the plate tumblers which have edges of different height are positioned at the same level when said plate tumblers are maximally displaced into said escape channel.

4,292,824

DOUBLE SIDED TUMBLER CYLINDER FOR A
SECURITY LOCK

Ernst Keller, Quersasse 6, Richterswil, Switzerland (8805)

Filed Apr. 30, 1979, Ser. No. 34,558

Claims priority, application Switzerland, May 12, 1978, 5239/78


Int. Cl.³ E05B 9/04

U.S. Cl. 70—373

1 Claim

1. A pin tumbler cylinder for a security lock including a cylinder housing and rotatably disposed therein a cylinder core, said core having recesses for receiving individual chambers in each of which are disposed a locking pin and a pin spring and wherein said cylinder housing is composed of an

axial stack of discs which are immovably joined, each of said discs having a tang portion, a plurality of said discs having an opening in said tang portion, said openings together constituting



ing a channel for receiving a reinforcing bar, and a reinforcing bar having an enlarged central portion provided with a radial threaded bore for receiving a locking screw.

4,292,825


GAUGE AND TENSION CONTROL SYSTEM FOR TANDEM ROLLING MILL

Yasuo Morooka; Shinya Tanifuji, and Masaya Tanuma, all of Hitachi, Japan, assignors to Hitachi, Ltd., Tokyo, Japan
Filed Feb. 21, 1980, Ser. No. 123,418

Claims priority, application Japan, Feb. 23, 1979, 54/19663
Int. Cl.³ B21B 37/00

U.S. Cl. 72-8

4 Claims



1. A control system for a continuous mill which includes at least two rolling stands, comprising means for detecting delivered strip thicknesses of a strip-like material rolled and delivered from each of said rolling stands; means for detecting interstand tensions applied to said strip-like material between every two successive ones of said rolling stands; transfer means for shifting signals representing said delivered strip thicknesses at said rolling stands in dependence on the feeding speed of said strip-like material; means for setting desired values of said delivered strip thicknesses and said interstand tensions; and means for correctively controlling a roll gap or a roll rotation speed at each of said rolling stands on the basis of the detected thicknesses, the delivered strip thicknesses as shifted by said transfer means, the detected interstand tensions and desired values set for said delivered strip thicknesses and said interstand tensions so that dispersion of deviations in the detected thickness and tension from said desired values is reduced to a minimum within a succeeding predetermined time interval.

4,292,826


WIRE DRAWING APPARATUS EMPLOYING MACROSONIC TECHNIQUES

Bertwin Langenecker, 8253 Waldbach (Steiermark), Austria
Division of Ser. No. 833,288, Sep. 14, 1977, abandoned. This application Jun. 27, 1979, Ser. No. 52,584

Claims priority, application Austria, Sep. 16, 1976, 6865/76
Int. Cl.³ B21C 9/00, 3/10

U.S. Cl. 72-45

8 Claims



1. Apparatus for the drawing of wire-like elements, such as, wires, rods, pipes and the like, employing macrosonics and hydrodynamic lubrication comprising:
means for supplying a wire-like element for drawing;
an ultrasonic transducer for generating ultrasonic waves;
a horn responsive to said ultrasonic transducer for amplifying the ultrasonic waves, said wire-like elements being passed along a longitudinal axis of the horn;
a pipe being disposed in said horn;
a drawing die arranged in the displacement antinode of the horn and extending substantially perpendicular to the drawing axis, said pipe having a channel of predetermined diameter arranged before the drawing die with respect to the drawing direction, said channel diameter being selected to be sufficiently larger than the diameter of the wire-like element ahead of the drawing die to assure hydrodynamic lubrication, said drawing die and pipe having respective end faces which closely and completely contact each other to prevent lubricant from acting on said end faces; and
means for supplying a lubricant to said channel.

4,292,827

METHOD FOR MAKING DECORATIVE EMBLEMS


Robert E. Waugh, Columbus, Ohio, assignor to The D. L. Auld Company, Columbus, Ohio

Continuation-in-part of Ser. No. 903,829, May 8, 1978, abandoned. This application Jul. 5, 1979, Ser. No. 54,548

Int. Cl.³ B21D 28/06, 53/44

U.S. Cl. 72-46

7 Claims



1. A method for producing decorative emblems, plaques or panels, comprising:
(a) providing a substrate having a top surface and a bottom surface and a series of designs applied to its top surface, said substrate having formed therein slits, embossed

ridges, or other sharp edges so as to provide within the substrate and around each area to be coated sharply defined peripheral sides which intersect with said top surface,

- (b) holding said substrate flat and horizontal on a supported surface free from surrounding side walls,
- (c) flow coating a clear viscous fluent curable plastic onto said top surface of said substrate from multiple orifices such that the area coated includes said designs, said plastic being one which only partially wets the surface of said substrate and which is sufficiently slow curing that it will flow on said substrate to said sharply defined peripheral sides said plastic being applied in an amount sufficient to form a uniform thickness coating approximately 0.020 to 0.030 inch thick,
- (d) allowing said fluent plastic to cure while maintaining said substrate flat and horizontal to bond said uniformly thick coating to said substrate, and
- (e) stamping said emblems, plaques, or panels out of said substrate having said cured plastic thereon by application of a cutting die to said bottom surface of said substrate so as to cut contiguous with each individual design of said series of designs, and impart a slightly convex shape to each said emblem, plaque or panel when viewed from the top surface thereof.

4,292,828

APPARATUS FOR MANUFACTURING COLD-WORK HARDENED CYLINDERS


Willy Germann, Würenlos, Switzerland, assignor to BBC Brown, Boveri & Company Ltd., Baden, Switzerland
Filed Jan. 8, 1979, Ser. No. 1,850

Claims priority, application Switzerland, Jan. 25, 1978, 787/78

Int. Cl.³ B21D 22/10

U.S. Cl. 72-54

1 Claim



1. Apparatus for cold-working a cylinder comprising two flanges, each having a central opening, a shaft extending through both of said openings, means supporting said cylinder concentrically with said shaft and said openings of the flanges, the opposite ends of said cylinder being in sealing relation with said flanges, said shaft having a head on one end and a threaded portion at the other end, one of said flanges being positioned in abutting relation with said head and the other of said flanges being restrained from axial movement away from the one of said flanges by a support plate threadedly engaged on said screw threads of said shaft, and hydraulic cylinder means between said support plate and the other of said flanges.

1011 O.G.—3

4,292,829

PROCESS FOR THE PRODUCTION OF METALLIC FORMED MEMBERS

Adolf Weber, Neunkirchen, and Siegfried Rhau, Nuremberg, both of Fed. Rep. of Germany, assignors to Diehl GmbH & Co., Fed. Rep. of Germany


Filed Nov. 19, 1979, Ser. No. 95,564

Claims priority, application Fed. Rep. of Germany, Dec. 6, 1978, 2852658

Int. Cl.³ B21J 7/16; F42B 13/48; B21J 7/18

U.S. Cl. 72-76

1 Claim



1. In a process for the production of a formed member, including discrete particles embedded in a metallic matrix, the improvement comprising: arranging said particles intermediate a metallic basic support member and a metallic outer casing; embedding said particles in said basic support member and said outer casing through annular cold working of said outer casing; and having shaping wedges which extend along and over only a partial number of said particles concurrently work over the full length of said outer casing in conformance with the length of the particle arrangement along the axial direction of said formed member during rotation of said formed member.

4,292,830

MILL FOR MAKING TRANSVERSE DEFORMATIONS ON SHEET METAL


Igor S. Trishevsky, ulitsa 23 Avgusta, 47, kv. 42; Oleg I. Trishevsky, ulitsa Dzerzhinskogo, 34, kv. 7; Vladimir N. Bosy, ulitsa Oktyabrskoi Revolutsii, 63, kv. 5; Rustem J. Deberdeev, ulitsa Bairona, 148, kv. 52, all of Kharkov; Leonid V. Radjuevich, ulitsa Tukhachevskogo, 22, korpus 2, kv. 253, Moscow; Vyacheslav I. Anisimov, ulitsa Metallurgov, 11, kv. 16, Magnitogorsk; Jury A. Plesnetsov, ulitsa Darvina, 20, kv. 6, and Valery V. Chukhno, ulitsa Darvina, 16, kv. 5, both of Kharkov, all of U.S.S.R.

Filed Nov. 30, 1979, Ser. No. 98,967

Int. Cl.³ B21B 45/00; B21D 37/16

U.S. Cl. 72-197

4 Claims



1. A mill for making transverse deformations on a sheet metal, comprising:
at least one rolling stand having rolls with congruent lengthwise arranged forming elements;
at least one drive stand with feed rolls;
means for locally heating the sheet metal at its portions to be transversely deformed, which means includes inductors and a cam mechanism which is adapted to move the inductors up to and down from the sheet metal and is provided with a horizontal distributing shaft having cams and pushers connected to said inductors; and
a transfer mechanism operatively connecting said horizontal distributing shaft of the cam mechanism with one of the rolls of said rolling stand, and the gear ratio of the transfer

mechanism being equal to the number of the forming elements on one of the rolls of said rolling stand.

4,292,831

PROCESS FOR EXTRUDING A METAL TUBE WITH INWARDLY THICKENED END PORTIONS

Joseph A. Simon, 237 Lothrop, Grosse Pointe Farms, Mich. 48236

Filed Oct. 24, 1979, Ser. No. 87,717
Int. Cl.³ B21C 25/08

U.S. Cl. 72-260

2 Claims



1. A process for extruding a metal tube with inwardly extending, annular, ring-like thickened end portions, comprising the steps of:

positioning a relatively short, tubular blank within an open ended, tubular die having an inlet end through which the blank is inserted and an opposite extrusion end formed by an annular, inwardly extending, continuous shoulder forming a die extrusion throat, through which the blank is extruded, with the throat diameter being larger than the inner diameter of the blank;

inserting a punch into the die inlet end, which punch has a portion closely fitted within the die and is provided with an annular shoulder for engaging against the free end of the blank, and also having a punch extension, axially aligned with the blank and die throat, with the punch extension having a series of successively smaller diameter extension portions;

arranging the largest diameter punch extension, i.e., the extension portion closely fitted within and in face to face contact with the inner wall of the blank, within the die throat while moving the punch towards the die throat so that its shoulder pushes the trailing end of the blank to thereby extrude a portion of the blank through the annular space between said larger diameter extension portion and the die throat to consequently form a relatively thin wall tube portion;

removing the punch and inserting a second blank within the die, and reinserting the punch into the die so that movement of the punch engages and pushes the trailing end of the second blank, which in turn, pushes the first, partially extruded blank through the die throat;

next, skipping the next smaller diameter punch extension portion and instead aligning the following smaller punch extension portion within the die throat while continuing to move the punch so as to extrude a portion of the blank through the annular space in the die throat formed thereby, to thereby form a thickened, ring-like formation within the interior of the tube;

then, aligning the previously skipped extension portion within the die throat and continuing the movement of the punch to extrude a successive portion of the blank through the die throat annular space formed thereby to produce a tube wall portion of greater interior diameter than the previously mentioned thickened ring-like interior formation.


4,292,832 METHOD OF PRODUCING VIBRATION ATTENUATING METALLIC MATERIAL

Hideo Nakae, Kashiwa; Toshinori Ozaki; Takashi Shimaguchi, both of Minorimachi, and Syogo Morimoto, Matsudo, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan
Filed Oct. 25, 1979, Ser. No. 88,142

Claims priority, application Japan, Oct. 27, 1978, 53-131652
Int. Cl.³ B21B 1/38

U.S. Cl. 72-365

9 Claims



1. A method of producing a vibration attenuating material having a high vibration attenuating performance, said method having the steps of forming a multiplicity of grooves in the surface of a ductile raw material, and subjecting said raw material to a drawing or a rolling work thereby to form a multiplicity of fine friction interfaces in the surface region of said vibration attenuating material, wherein the improvement comprises that said vibration attenuating material is formed such that each of said friction interfaces is composed of a vertical component perpendicular to the surface of said vibration attenuating material and inclined components inclined to said surface of said vibration attenuating material.

4,292,833


CRIMPING TOOL

Ellsworth W. Lapp, c/o Lapp Engineering, Inc., 4701 Hydraulic Rd., Rockford, Ill. 61109

Filed Jun. 22, 1979, Ser. No. 51,101
Int. Cl.³ B21D 37/4

U.S. Cl. 72-416

4 Claims



1. A tool for crimping a workpiece and comprising a head having a pair of opposing die holders, means for moving one of said die holders toward and away from the other of said die holders, each of said die holders having a pocket, a first die seated within each pocket, first means for securing each first die releasably to the respective die holder, each of said first dies having a concavely curved die cavity, a second die seated within the die cavity of each first die, each of said second dies having a concavely curved die cavity for crimping said workpiece and having a convex surface adapted to be received in the die cavity of the respective first die, a pair of laterally spaced arms extending from the convex surface of each second die and straddling the respective first die, notches opening out of the free ends of said arms, and second means comprising laterally shiftable pins supported by and extending laterally of said head and adapted to be received in said notches to secure said second dies releasably to said head, the die cavities of said

first dies being adapted to crimp said workpiece in the absence of said second dies.

4,292,834

IRREGULAR SHAPE ROD BENDING APPARATUS


Albert Tishler; Murray Tishler; William Tishler; Irving Tishler, and Joseph Lucchesi, all of Norwalk, Conn., assignors to Norwalk Investment Club, Norwalk, Conn.

Filed Mar. 28, 1980, Ser. No. 135,200

Int. Cl.³ B21D 7/024

U.S. Cl. 72-482

10 Claims



1. An apparatus operable to perform selected rod bending operations, said apparatus including a pair of generally parallel support members, a plurality of laterally spaced elongated transverse guide members extending between said support members, the opposite ends of said guide members and said support members including first coating clamp and guide structure supporting said guide member ends from said support members for adjustable shifting therealong and operative to releasably anchor said guide member ends in adjusted shifted positions along said support members, at least one post for each guide member, said posts and guide members including second coating clamp and guide structure supporting said posts from said guide members for adjustable shifting therealong and operative to releasably anchor said posts in adjusted shifted positions along said support members, said posts being disposed substantially normal to a plane paralleling said support members and guide members.

4,292,835

CALIBRATION APPARATUS AND METHOD FOR STRAIN MEASURING INSTRUMENTS


John H. Bickford, Middletown, Conn., assignor to Raymond Engineering, Inc., Middletown, Conn.

Filed Feb. 25, 1980, Ser. No. 124,300

Int. Cl.³ G01L 25/00

U.S. Cl. 73-1 B

17 Claims



1. Apparatus for calibrating a strain measuring instrument, the calibrating apparatus including:
test stand means;
first and second probe means mounted in spaced apart rela-

tionship on said test stand means, said probe means being capable of sensing elongation of a test specimen;
mounting means in said test stand for mounting a test specimen between said first and second probe means;
load cell means mounted in said test stand for imposing a tension load on a test specimen;
load measuring cell means mounted in said test stand for sensing the load imposed on a test specimen by said load cell means; and
coupling means for coupling to a test specimen a strain measuring instrument to be calibrated.

4,292,836

APPARATUS FOR MEASURING THE RATE OF AN ANALOG-DISPLAY ELECTRONIC TIMEPIECE

Fridolin Wiget, Neuchatel, Switzerland, assignor to Ebauches S.A., Switzerland


Filed Nov. 26, 1979, Ser. No. 97,531

Claims priority, application Switzerland, Nov. 24, 1978, 12063/78

Int. Cl.³ G04D 7/12

U.S. Cl. 73-6

4 Claims



1. Apparatus for measuring the rate of an electronic timepiece responding to an interrogation signal by emitting a wave formed by trains of pulses, said apparatus comprising means for detecting said wave, computing means responding to said detection means and providing a representation of the rate of the timepiece, and means for displaying said representation, wherein said computing means comprises means for producing a first number of pulses representing the period of said trains of pulses, means for producing a second number of pulses representing the content of said trains of pulses, and means for combining said first and second number of pulses and providing said representation.

4,292,837

LIQUID TESTING APPARATUS

Ronald A. Oakman, Wraysbury, near Staines, England, assignor to Stanhope-Seta Limited, Egham, England

Filed Feb. 4, 1980, Ser. No. 118,323

Claims priority, application United Kingdom, Feb. 2, 1979, 03772/79


Int. Cl.³ G01N 25/12

U.S. Cl. 73-17 R

9 Claims

1. Liquid testing apparatus, comprising
(a) housing means (10) including separable body block and cover plate members (12,13) which cooperate to define a closed testing chamber (11), an inlet (20) for introducing a

quantity of the liquid to be tested into said chamber, a vertical tubular divider (14) suspended from said cover member and terminating at its lower end beneath the level of the liquid in the chamber, said divider dividing the upper end of said chamber into concentrically arranged inner and annular outer chamber portions, and an outlet (17) communicating with one of said chamber portions;



- (b) means (30) connected with said housing means for establishing flow of the liquid along a flow path;
- (c) flow restricting means (15) arranged in said flow path;
- (d) detecting means (32) for detecting variations in the resistance to flow of the liquid produced by said flow restricting means; and
- (e) means (18) for indicating the temperature of the liquid.


4,292,838

CALIPER GAUGE FOR THE MEASUREMENT OF SHEET MEMBERS OVER A WIDE RANGE OF THICKNESSES
Tor G. Larsen, Saratoga, Calif., assignor to Measurex Corporation, Cupertino, Calif.

Filed Nov. 26, 1979, Ser. No. 97,394
Int. Cl.³ G01B 13/04

U.S. Cl. 73—37.7

6 Claims



1. An apparatus for measurement of the thickness of a sheet having a portion of said apparatus to one side of said sheet and another portion of said apparatus to the other side of said sheet comprising:
 - a housing;
 - a member coupled to said housing capable of being extended in a direction substantially perpendicular to the sheet, said member including:

- (i) a hollow shaft positioned to extend in the direction substantially perpendicular to the sheet;
- (ii) a cup, connected to one end of said shaft which is closer to the sheet, and with the concavity of the cup facing the sheet;
- (iii) said cup having a hole in line with the hollow portion of the shaft;
- (iv) a body comprising a dome and a flat cover with the flat cover covering the opening of the dome, said body having an opening in said dome near the apex, a plurality of outlets in said dome and a plurality of orifices in the flat cover;
- (v) means for pivotally attaching said body to said cup such that the dome of said body is inside the cup; and fluid means capable of directing fluid through said member.

4,292,839

CROWN RELEASE PRESSURE TESTER

Thomas S. Hartness, Greenville, S.C., assignor to Hartness International, Inc., Greenville, S.C.

Filed Sep. 4, 1979, Ser. No. 71,864

Int. Cl.³ G01M 3/32

U.S. Cl. 73—49.2

5 Claims



1. A crown release pressure tester for a container having a neck portion upon which said crown is placed for sealing said container, the neck portion and crown removed from said container, comprising:
 - an elongated housing;
 - an elongated bore provided in said housing;
 - means for securing said removed neck portion with said crown provided thereon on a top portion of said housing with the interior of said crown in communication with one end of said elongated bore and said interior of said crown and said elongated bore being sealed from the atmosphere;
 - a piston extending in said other end of said elongated bore;
 - a seal provided between said piston and housing surrounding said bore; and
 - means for moving said piston axially within said bore for gradually increasing the pressure on said crown for determining the pressure that said crown fails.

4,292,840

FUEL CONSUMPTION EFFICIENCY GAUGE

Liem Nguyen, Garden Grove, Calif., assignor to Orion Industries, Inc., Compton, Calif.

Filed May 7, 1980, Ser. No. 147,397

Int. Cl.³ G01L 3/26, 9/00


U.S. Cl. 73—115

12 Claims

1. A fuel consumption efficiency indicator for use with a direct current power source having d.c. terminals of opposite polarity and an internal combustion engine having a vacuum manifold with a monitoring connection thereto comprising:
 - a hollow, rigid casing,
 - a pressure gauge mounted in said casing and having a movable member responsive to pressure in said vacuum manifold to deflect in one direction responsive to pressure increases and in an opposite direction responsive to pressure decreases,
 - a hollow circuit leading from said pressure gauge to said monitoring connection,

an electrically conductive pointer mechanically coupled to said movable member of said pressure gauge for movement and electrically connected to a first of said opposite d.c. terminals,

a low vacuum electrical contact and a high vacuum electrical contact secured relative to said casing to transversely bracket said pointer at opposite limits of movement thereof,



- a first electrically actuated illuminator coupled between a second of said opposite d.c. terminals and said low vacuum electrical contact,
- a second electrically activated illuminator coupled between said second of said opposite d.c. terminals and said high vacuum electrical contact, and
- a third electrically actuated illuminator and a load coupled between said second and said first d.c. terminals.

4,292,841

COMPRESSION RATE ANALYZER


William M. Wesley, Kildeer, Ill., assignor to Creative Tool Company, Lyons, Ill.

Filed Jul. 11, 1979, Ser. No. 56,501

Int. Cl.³ G01M 15/00

U.S. Cl. 73—119 A

27 Claims



17. A method for monitoring the performance of an internal combustion engine comprising the steps of
 - attaching a piezoelectric transducer to a selected cylinder to develop a signal corresponding substantially to the first derivative of the pressure within the selected cylinder,
 - electrically quantizing the magnitude of said transducer signal to obtain a numerical manifestation of said transducer output signal as a measure of the performance of said selected cylinder.

4,292,842

TOOL FOR TESTING EARTH FORMATIONS IN BOREHOLES

Bobby J. Hallmark, Fort Worth, Tex., assignor to Gearhart Industries, Inc., Fort Worth, Tex.


Division of Ser. No. 42,431, May 25, 1979, Pat. No. 4,270,385.

This application May 5, 1980, Ser. No. 146,702

Int. Cl.³ E21B 49/00

U.S. Cl. 73—155

2 Claims



1. A tool for testing earth formations in boreholes, comprising:
 - formation isolation means including hydraulically controlled extendable and retractable seal pad means and backup pad means;
 - first electrically powered means controllable at above-ground equipment for generating and applying setting pressure to extend and set said seal pad means and said backup pad means to accomplish isolation of the formation at the seal pad location;
 - means for generating first signals to be transmitted to above-ground equipment, which signals are a measure of said hydraulic pressure;
 - a formation fluid mini-sample chamber having variable volume, and fluid passage means for communicating between said mini-sample chamber and the formation at said seal pad location;
 - second electrically powered means controllable at above-ground equipment to vary at the will of an operator the volume of said mini-sample chamber;
 - means for generating second signals to be transmitted to above-ground equipment, which second signals are a measure of fluid pressure within said mini-sample chamber; and
 - means for generating third signals to be transmitted to above-ground equipment, which third signals are a measure of the volume of said mini-sample chamber.

4,292,843

TEMPERATURE-COMPENSATED PRECIPITATION GAUGE

Charles E. Luchessa, San Rafael, and Timothy E. Brown, Danville, both of Calif., assignors to Sierra Misco, Inc., Berkeley, Calif.

Filed Jan. 16, 1980, Ser. No. 112,654


Int. Cl.³ G01W 1/14

U.S. Cl. 73—171

5 Claims

1. A precipitation gauge comprising a first cylindrical pipe, a second cylindrical pipe superimposed upon and concentric with said first pipe, said pipes meeting at a joint, said first pipe

having a water-tight compartment immediately above said joint, said first pipe having an open top admitting precipitation into said first pipe, a module in said first pipe comprising a body, a perforate bottom for said body and overflow collecting means, said overflow means comprising an inlet near the top of said body and a drain pipe receiving the liquid entering said inlet and extending through said compartment and having first coupling means at said joint, said second pipe having a tipping bucket liquid measuring member at its upper end having a top



having second coupling means cooperable with said first coupling means to secure said pipes together at said joint and also to conduct liquid into said tipping bucket member, a transmitter at the bottom of said second pipe, said tipping bucket member tipping as liquid enters same and emitting an electric signal as it tips, said transmitter emitting a radio signal dependent on the number of times said tipping bucket member tips, whereby upon uncoupling said coupling means, said first pipe may be lifted from said second pipe providing access to the contents of both said pipes.

4,292,844

TEMPERATURE DETECTING DEVICE

Hiroshi Sawa, Yokohama, and Yukio Yamauchi, Kawasaki, both of Japan, assignors to Hochiki Corporation, Tokyo, Japan


Filed Apr. 11, 1980, Ser. No. 139,527

Claims priority, application Japan, Apr. 11, 1979, 54-46986[U]

Int. Cl.³ G01K 7/00

U.S. Cl. 73-359 A

7 Claims



1. A temperature detecting device comprising: a protective tube; heat detecting means disposed within said tube, said heat detecting means including a stem member, a semiconductor device mounted in a resin package mounted upon one side of said stem, said resin package of said semiconductor device having a relatively thin portion with respect to a semiconductor pellet within said resin package on the side disposed away from said stem and said package having a plurality of electrodes extending therefrom, and a plurality of leads extending through said stem member and being connected to said electrodes of said semiconductor device; a heat collector disposed in thermal conduct with said protective tube in the vicinity of

said heat detecting device; casing means, said protective tube being mounted at the end thereof opposite said heat detecting device to said casing means, said casing means having a plurality of rib portions; and a protective member for holding said heat collector in engagement with said rib portions of said casing means.

4,292,845 CONNECTION ASSEMBLY FOR RIGID STEM DIAL GAUGE

John J. Gilbert, 98 W. Park Dr., Porthcawl, Mid Glamorgan, Wales


Filed Nov. 8, 1969, Ser. No. 92,474

Claims priority, application United Kingdom, Nov. 23, 1978, 45732/78

Int. Cl.³ G01K 5/50

U.S. Cl. 73-362.1

3 Claims



1. In a rigid-stem dial gauge comprising a pointer shaft, a thermometer stem, a flexible drive member connecting said pointer shaft and said thermometer stem and a coupling assembly mounting said stem and said shaft, the improvement wherein said coupling assembly comprises an outer housing, an inner housing coaxially and rotatably mounted within the outer housing, said pointer shaft extending radially through aperture means in one of said housings and said thermometer stem extending radially through aperture means in the other of said housings, said two aperture means being in spaced relation, and an arcuate slot in each of said housings whereby the relative angular position of the housings about their common axis can be adjusted to change the angle between said stem and said shaft.

4,292,846

LIQUID PROPORTIONING CONTAINER

Loren A. Barnett, P.O. Box 786, Grove, Okla. 74344

Filed Nov. 2, 1979, Ser. No. 90,877


Int. Cl.³ G01F 14/00

U.S. Cl. 73-427

8 Claims

1. A liquid proportioning container comprising:
a. a main reservoir having a given capacity, and constituting a container having a pouring neck,
b. a measuring vessel calibrated to be filled with a first liquid selectively to any of a series of predetermined levels, said levels being so determined that when filled to any selected level and its contents added to a second liquid to fill said main reservoir, said first and second liquids will be mixed in proportions determined by the selected calibration of said measuring vessel, said measuring vessel constituting a

pouring spout detachably connected at one end to said neck, and



c. a cap applied removably to the outer pouring end of said pouring spout, whereby to serve as a closure for the entire container.

4,292,847

TESTING THE MATERIAL OF A PRODUCT FOR DEFECTS THEREIN AND PROCESSING THE MATERIAL EMPLOYING SUCH A METHOD


William H. Tait, Hamilton, Canada, assignor to Dofasco Inc., Hamilton, Canada

Filed Jan. 28, 1980, Ser. No. 116,122

Int. Cl.³ G01N 29/04

U.S. Cl. 73-587

8 Claims



1. A method of testing a product for the presence of a defect in the material thereof, including the steps of:
(a) cutting a piece of the product;
(b) automatically detecting the noise of the cutting and producing an electric signal representative thereof; and
(c) examining the said electric signal to detect therein an acoustic component representative of a defect therein.

4,292,848

WALKING-GATE ULTRASONIC FLAW DETECTOR


J. Montgomery Rainey, Dayton, and Francis M. Taylor, Xenia, both of Ohio, assignors to Systems Research Laboratories, Inc., Dayton, Ohio

Filed Apr. 11, 1980, Ser. No. 139,537

Int. Cl.³ G01N 29/04

U.S. Cl. 73-602

4 Claims



3. Apparatus for ultrasonic detection of flaws located within solid material, said apparatus including
transducer means for transmitting a beam of ultrasonic energy into the material and for receiving signals reflected from within the material, which can be positioned at various angular and positional coordinates on the surface of said material,
means for indexing said transducer over the surface of the material, such that suspected defect areas are scanned,
means for sensing the angular and positional coordinates of said transducer means referenced to said material geometry,
means for sensing reflected signals received by said transducer within a limited period of time,
means for dividing said received signals within said period of time into a plurality of equally spaced segments,
means for causing said transducer to transmit a pulse or series of pulses each time the transducer indexes,
a plurality of memory means for storing said received signals and said angular and positional coordinates,
means for adding the representations of amplitude of the received signals from said time segments in such a manner that all ultrasonic signals received during a scan which are reflected from a small specific spacial volume within the material are summed together and stored in memory,
means for interrogating said memories after said transducer has scanned the suspected flaw locations and extracting the summed flaw amplitudes and the location of such flaws referenced to the material geometry,
means for displaying and/or transmitting to external devices said summed flaw amplitudes and location.

4,292,849

METHOD FOR CORRECTING THE SENSITIVITY OF AN ELECTROMAGNETIC ULTRASONIC PROBE

Hisao Yamaguchi, Akashi, and Kazuo Fujisawa, Nishinomiya, both of Japan, assignors to Sumitomo Metal Industries, Ltd., Osaka, Japan

Filed Dec. 17, 1979, Ser. No. 104,462

Claims priority, application Japan, Mar. 28, 1979, 54-37553


Int. Cl.³ G01N 29/00

U.S. Cl. 73-643

1 Claim

1. In ultrasonic flaw detection using an electromagnetic ultrasonic probe for both transmission and reception or for only reception, a method for correcting the sensitivity of the electromagnetic ultrasonic probe, comprising the steps of:
previously obtaining the relationship between resonance

frequency and transmission-reception sensitivity in the range between the maximum and the minimum lifts-off of said electromagnetic ultrasonic probe;
creating electrically a relationship therebetween having an inverse sensitivity-frequency characteristic to said relationship; and



adding said two relationships together, thereby obtaining a constant reference sensitivity;
wherein said correction of the sensitivity is performed by an amplifier which is added to a circuit on the reception side of said electromagnetic ultrasonic probe and wherein a frequency filter is disposed before said amplifier.

4,292,850

AIR PRESSURE TRANSMITTER

Christian Bachem, St. Andreasberg, Fed. Rep. of Germany, assignor to Albin Sprenger KG GmbH & Co., Andreasberg, Fed. Rep. of Germany


Filed Jan. 23, 1980, Ser. No. 114,614

Claims priority, application Fed. Rep. of Germany, Feb. 2, 1979, 2903994

Int. Cl.³ G01L 9/12

U.S. Cl. 73—702

7 Claims



1. An air pressure transmitter with a circular diaphragm arranged in a measuring chamber, said diaphragm being surrounded on both sides by thin layers of the air to be measured and limited by rigid walls, whereby the body of the air layers is influencing the natural frequency of the diaphragm, characterized thereby that the diaphragm (10) is configured as a plate of hard beaten material and at its edge is clamped between the rigid walls (12, 14) with distance rings (16) of such a thickness that the readjusting power of the air layers located within the distance rings (16), at atmospheric pressure will be three to ten times more than the readjusting power of the diaphragm (10).

4,292,851

COPPER GRID FOR STRAIN ANALYSIS OF SHEET METAL DEFORMATION

Earl G. Brewer, Warren, Mich., assignor to General Motors Corporation, Detroit, Mich.

Filed Apr. 4, 1980, Ser. No. 137,316

Int. Cl.³ G01B 5/30

U.S. Cl. 73—762

3 Claims

3. In the method of analyzing the deformation of a noncupreous base metal sheet comprising decorating at least a portion of the sheet surface prior to deformation with a grid pattern of noncontacting uniform solid circles in a matrix, deforming the sheet, and measuring distortion in the circles, said measurement being carried out by photographing the distorted grid

and analyzing the photograph with the aid of a computer, the improvement comprising

plating a thin film of metallic copper onto the portion of the sheet surface,
defining the pattern with a photoresist mask that overlies the copper film where circles are desired and exposes the copper film where the matrix is desired,
stripping the exposed copper to expose without etching the sheet surface thereunder while protecting the remaining copper with the photoresist mask,



removing the photoresist mask, whereupon the desired grid pattern is produced comprising circles formed of thin copper film and exposed sheet surface,
deforming the sheet, whereupon the copper circles are distorted, and
heating the deformed sheet in air to at least oxidize the copper to enhance the contrast between the distorted circles and the matrix and thereby produce a grid that is reliably photographable for computer analysis.

4,292,852

METHOD AND APPARATUS FOR PHYSICALLY TESTING THE INTEGRITY OF THE CONNECTION BETWEEN AN ELECTRODE ASSEMBLY AND A TERMINAL CONDUCTOR OF AN ELECTROCHEMICAL CELL


Jesse L. Morris, Archer, Fla., assignor to General Electric Company, Gainesville, Fla.

Filed Jan. 30, 1980, Ser. No. 116,844

Int. Cl.³ G01N 3/10

U.S. Cl. 73—827

14 Claims



13. Apparatus for physically testing the mechanical integrity of the joint formed between an electrode for an electrochemical cell and a terminal conductor mechanically attached thereto, comprising:

a first carriage having mounted thereto a restraining member, said carriage being controllably movable between a first position wherein said restraining member is remote from the electrode and a second position in which said restraining member is positioned closely adjacent the electrode so as to prevent longitudinal movement thereof; terminal conductor grasping means operable between a

conductor-engaging condition, in which said conductor is fixedly held, and a disengaged condition in which said conductor is released;
a second carriage slidably movable between a withdrawn position, in which the electrode and terminal conductor are free of said grasping means, and a longitudinally forward, operative position in which said conductor-grasping means may engage the conductor, said first and second carriage means being slidably movable independently of each other; and
first and second actuator means connected to said first and second carriages, respectively, for independently and controllably moving each thereof.

4,292,853

FLUID FLOW MEASURING APPARATUS

Garnet M. E. Williams, London; Stanley P. Hutton, Southampton, and John A. Bushman, London, all of England, assignors to Ferraris Development and Engineering Co., Ltd., London, England


Filed Apr. 22, 1980, Ser. No. 142,803

Claims priority, application United Kingdom, Apr. 23, 1979, 14015/79

Int. Cl.³ G01F 1/06

U.S. Cl. 73—861.79

24 Claims



1. Apparatus for measuring volume of flow of a fluid comprising a casing; a tubular stator which is housed within the casing so that the casing forms a circumferential gallery around it; inlet and outlet ports formed by the casing so that one of them communicates with the gallery and projects radially outwardly therefrom and the other one communicates with the bore of the tubular stator from which it projects axially; a rotor which is journaled within the casing for rotation within the bore of the stator coaxially therewith; oblique slots which are formed in the tubular wall of the stator so that a path for flow of fluid to be measured between the inlet and the outlet is formed by the bore of the tubular stator, the oblique slots and the gallery, the oblique slots being orientated so that fluid directed along said path forms a spirally swirling fluid flow which drives the rotor; and means by which a read-out indication of the fluid flow volume is derived from rotation of the rotor; wherein the effective cross-sectional area of one of the slots differs from the effective cross-sectional area of all the other slots.

4,292,854

GYROSCOPIC APPARATUS HAVING THREE-AXIS INERTIAL PLATFORM WITH RAPID WARM-UP

Alan P. Liebing, West Linton, Scotland, assignor to Ferranti Limited, Cheadle, England

Continuation-in-part of Ser. No. 733,884, Oct. 19, 1976, abandoned. This application Jan. 19, 1979, Ser. No. 4,871


Int. Cl.³ G01C 19/30

U.S. Cl. 74—5.34

6 Claims

1. Gyroscopic apparatus which includes a platform carried in three-axis gimbal system, a shaft encoder and a torque motor connected to each axis of the gimbal system, at least one dynamically-tuned free-rotor gyro-carried on the platform and having two sensitive axes, a gyro pick-off carried on each sensitive axis of the gyro, two accelerometers carried on the

platform and having their sensitive axes aligned with the two sensitive axes of the gyro, resolving means responsive to the outputs of the gyro pick-off on each sensitive axis of the gyro to apply resolved signals to the gimbal torque motors as appro-



4,292,855

TRANSMISSION FOR A FARM TRACTOR OF FOUR WHEEL DRIVE TYPE

Yoshinobu Murayama, Sakai, Japan, assignor to Kubota, Ltd., Osaka, Japan


Continuation-in-part of Ser. No. 909,790, May 26, 1978. This application Oct. 11, 1978, Ser. No. 950,297

Claims priority, application Japan, Jan. 28, 1978, 53-8646; Feb. 7, 1978, 53-13802; Feb. 7, 1978, 53-13803

Int. Cl.³ F16H 37/00, 3/08, 37/08

U.S. Cl. 74—15.4

6 Claims



1. A transmission for a farm tractor of four-wheel drive type comprising: a transmission case of substantially rectangular shape in side view extending longitudinally of a tractor body, a main shaft mounted in said case to extend from a front end to a rear end thereof and operatively connected to an engine disposed forwardly of the case, plural-step main speed change means disposed in a front position within the case and above the main shaft and operatively coupled to the main shaft, auxiliary speed change means disposed rearwardly of the main speed change means and beneath the main shaft and operatively connected to the main speed change means, differential speed change means for rear wheel drive disposed in a rear and lower position within the case and operatively connected to the auxiliary speed change means, a transmission shaft for front wheel drive disposed to extend forwardly of the case from a position beneath the auxiliary speed change means and adjacent a bottom inner surface of the case and operatively connected to the auxiliary speed change means, power takeoff shaft speed change means disposed in a rear end position of the case and operatively connected to the main shaft, a hydraulic cylinder disposed in an upper rear position within the case for vertically oscillating a lift arm attached to a rear portion of said case, and a hydraulic pump disposed in a lower front position

within the case for actuating said cylinder, said hydraulic pump being operatively connected to said main shaft and utilizing lubricating oil in said case as pumping oil.

4,292,856

CONTROLLED FILM ADVANCE APPARATUS WITH DIFFERENTIAL SPEED


Joel A. Hamilton, 101 Hardenburgh, Demarest, N.J. 07627

Filed Jun. 20, 1979, Ser. No. 50,308

Int. Cl.³ F16H 21/12, 25/08

U.S. Cl. 74-63

10 Claims



1. A film advancing apparatus in which the film is moved by a pitman arm mechanism, this improvement providing drive means by which a forward and rearward motion is imparted by the pitman arm at a differential speed, the improvement including:

- a support means;
- a motor drive with the output disposed to move said pitman arm mechanism and with it a film advance apparatus with and in a back and forth motion and at a selected speed;
- a support shaft carried by said support means;
- a disk-like driven member carried by bearing means and rotatable on said support shaft, this driven member movable at a reduced speed and operatively connected to the output of said motor drive;
- a short shaft carried by and in a web portion of said disk-like driven member;
- at least two substantially circular drive means carried on said short shaft and providing at least first and second drive means;
- a first circular driven means carried by first sleeve means rotatable on said support shaft and means for positively driving the first driven means by the first drive means;
- a second circular driven means carried by second sleeve means rotatable on said support shaft and means for positively driving said second driven means by said second drive means;
- a crankshaft supported by bearing means carried by the support means, said crankshaft carrying and moving said pitman arm;
- an eccentric carried by and secured to the crankshaft, said eccentric rotatably carrying a strap means thereabout;
- means for rotating said crankshaft by rotative forces derived from one of the circular driven means, and
- an arm having one end operatively connected to the other circular driven means and the other end operatively connected to the eccentric by the strap means, the movement of the crankshaft by said means for rotating causing the eccentric to move said arm to thereby speed up and then slow down the speed of revolution of the crankshaft.

4,292,857

CYLINDRICAL GEAR WITH HELICAL TOOTH WHEELS

Zbigniew Matusz, Warsaw, Poland, assignor to Fabryka Obrabiarek Precyzyjnych "Ponar-Pruszkow" Zaklad "1 Maja", Pruszkow, Poland


Filed Sep. 25, 1978, Ser. No. 946,207

Claims priority, application Poland, Sep. 29, 1977, 201125

Int. Cl.³ F16H 55/08

U.S. Cl. 74-466

3 Claims



1. A gear train comprising first and second cylindrical gears having helical teeth, each tooth having left hand and right hand sides with respective different pitch diameters, the teeth of the first and second gears having different nominal angles of inclination and different mesh correction for the left hand and right hand mating flanks of conjugate teeth whereby within the normal module range of 2 to 6 mm, corresponding to the normal pitch range of 2π (mm) to 6π (mm), and pitch diameters up to 500 mm, tooth convergencies up to 3° are provided, the addendum modification coefficient value not exceeding 0.8.

4,292,858

BRAKE CABLE OPERATING MEANS OF THE OVERCENTER TOGGLE TYPE

Eugene C. Lipshild, Moberly, Mo., assignor to Orscheln Brake Lever Mfg. Co., Moberly, Mo.


Division of Ser. No. 806,963, Jun. 16, 1977, Pat. No. 4,127,042.

This application Aug. 28, 1978, Ser. No. 937,539

Int. Cl.³ F16C 1/10; G05G 1/04

U.S. Cl. 74-501 R

3 Claims



1. In a brake cable operating device for operating a coaxial brake cable assembly having a tubular outer sheath member, and an inner cable member axially displaceable within said outer sheath member, said operating device including mounting plate means adapted for connection with a fixed support, said mounting plate means including a pair of spaced parallel mounting plates; anchor means rigidly connecting one end of the outer sheath member between said plates at one end of said mounting plate means, thereby to prevent axial displacement of said outer sheath member relative to said mounting plate means, said inner cable member extending axially beyond said outer sheath member and through said anchor means into the space between said plates; guide means connecting one end of the inner cable member with said mounting plate means for linear axial displacement relative to said outer sheath member; and an operating lever pivotally connected at one end about a

pivot axis with the other end of said mounting plate means, the pivot axis of said operating lever being normal to said plates; and a connecting link pivotally connected at opposite ends about pivot axes with an intermediate portion of said lever and with the one end of said inner cable member, respectively, the pivot axes of said connecting link being parallel with the pivot axis of said operating lever; the improvement wherein said anchor means comprises a first pair of coplanar tab portions bent inwardly from, and extending normal to, said mounting plates, respectively, each of said tab portions extending from the associated mounting plate transversely across the space between said mounting plates and including at its free end a projection that extends within a corresponding opening contained in the other mounting plate, thereby to maintain said mounting plates in spaced relation, said tab portions having adjacent parallel edges containing aligned recesses that define an opening (240) in which the end of the associated outer cable sheath is mounted.

4,292,859

STEERING DEVICE

Makoto Teraura, Takarazuka, Japan, assignor to Nippon Cable System Inc., Takarazuka, Japan


Filed Aug. 30, 1979, Ser. No. 71,231

Claims priority, application Japan, Jan. 24, 1979, 54-7962

Int. Cl.³ F16C 1/18

U.S. Cl. 74-501 R

3 Claims



1. In a steering device having a disc drive member rotatably mounted in a casing and an expansion and contraction-durable, flexible inner wire one end of which is fastened to an outer peripheral surface of said drive member, said device being improved in that

- said inner wire is fitted into an annular groove provided in the outer peripheral surface of said drive member,
- a series of bearings located or pivoted by a proper length of a flexible separator is interposed in a gap between the outer peripheral surface of said drive member and an inner surface of said casing,
- one end of the series of bearings is at substantially the same position as the fastening position of said inner wire, when the inner wire is completely wound in said groove about said drive member,
- the other end of the series of bearings is able to enter into a guide path which is provided in said casing so that the series of bearings separates from said inner wire near a tangential contact position of the inner wire with said drive member, and
- the series of bearings is provided with an engaging means at its one end, said engaging means being able to engage with a further engaging means provided on said one end of the inner wire or said drive member at least in the direction of winding the inner wire.

4,292,860

TRANSFER DEVICE ASSOCIATED WITH POWER TRANSMISSION

Hiroyoshi Kako, and Hajime Arai, both of Aichi, Japan, assignors to Toyota Jidosha Kogyo Kabushiki Kaisha, Aichi, Japan


Filed Dec. 1, 1978, Ser. No. 965,335

Claims priority, application Japan, Apr. 20, 1978, 53-47335

Int. Cl.³ F16H 3/08, 37/06; B60K 17/34

U.S. Cl. 74-665 GA

2 Claims



1. In a transfer device associated with a power transmission unit for an automotive vehicle, comprising:

- an input shaft for connection to an output shaft of said transmission unit;
 - a first output shaft rotatably coupled at the inner end thereof with said input shaft;
 - a countershaft arranged in parallel with said input and first output shafts and being integrally provided with low and high speed counter-gears;
 - a second output shaft arranged in parallel with said countershaft and being integrally provided with an output gear meshing with said high speed counter-gear;
 - a low speed drive gear rotatable on said input shaft and being in mesh with said low speed counter-gear; and
 - a high speed drive gear rotatable on said first output shaft and being in mesh with said high speed counter-gear, said high speed drive gear having the same number of teeth as those of said output gear;
- the improvement comprising:
- first and second selector gear units arranged adjacent to each other on a common axis between said low and high speed drive gears, said first selector unit being mounted on said input shaft for selectively connecting said input shaft to said low speed drive gear or to said first output shaft; and
 - said second selector gear unit being mounted on the inner end of said first output shaft for connecting said high speed drive gear to said first output shaft to provide four wheel drive and for disconnecting said high speed drive gear from said first output shaft to provide two wheel drive.

4,292,861

EARTH SELF-ORIENTING APPARATUS

John Thornhill, Jr., Tewksbury, and Richard B. Elder, Acton, both of Mass., assignors to RCA Corporation, New York, N.Y.

Filed Apr. 25, 1979, Ser. No. 33,266

Int. Cl.³ B23Q 17/00


U.S. Cl. 74-813 R

19 Claims

1. An earth self-orienting apparatus, comprising:

- a body including a plurality of spaced elements lying in a plane at least one of which corresponds to a predetermined orientation of said body with respect to the earth regardless the orientation of the body with respect to earth, said body including means for orientating said body about an axis approximately normal to the force of gravity,
- a member to be oriented to said predetermined orientation

rotatably mounted to said body for rotation in said plane including locking means having a first neutral position on said member as it rotates and a second locking position which when engaged with any of said elements locks said member to said body in accordance with the orientation of that element, said locking means including means respon-



sive to the earth orientation of said member for causing said locking means to move from said first to said second positions in response to the force of gravity and engage said at least one element and thereby lock said member to said body in said predetermined orientation, and means for rotating said orientating member with respect to said body.


4,292,862

METHOD AND APPARATUS FOR PRODUCTION OF A STREAM FEEDER

Thomas K. Thompson, Granville, Ohio, assignor to Owens-Corning Fiberglass Corporation, Toledo, Ohio
Filed Sep. 12, 1979, Ser. No. 74,585
Int. Cl.³ B21K 5/20

U.S. Cl. 76-4

5 Claims



1. A method of producing a stream feeder for flowing streams of molten mineral material from which filaments are attenuated comprising:

- providing two round locating pins;
- providing a workpiece which has two rows of locating holes wherein one row has round holes adapted to fit snugly around one of the round locating pins and the other row has elongated holes, the elongated holes being adapted to accommodate for the stretching of the workpiece between the rows of locating holes from formation of orificed projections;
- locating the workpiece such that one of the pins enters a first locating hole of one row and the other pin enters first locating hole of the other row;
- forming a first row of orificed projections in the workpiece between the first locating hole of the one row and the first locating hole of the other row;
- subsequently locating the workpiece such that the pin enters a second locating hole of the one row and the other pin enters a second locating hole of the other row; and
- forming a second row of orificed projections in the work-

piece between the second locating hole of the one row and the second locating hole of the other row.

4. Apparatus for producing a stream feeder for flowing streams of molten mineral material from which filaments are attenuated comprising:

- two round locating pins;
- means for locating a workpiece having two rows of locating holes such that one of the pins enters a first locating hole of one row and the other pin enters first locating hole of the other row, one row having round holes adapted to fit snugly around one of the round locating pins and the other row having elongated holes, the elongated holes being adapted to accommodate for the stretching of the workpiece between the rows of locating holes from the formation of orificed projections;
- means for forming a first row of orificed projection in the workpiece between the first locating hole of the one row and the first locating hole of the other row;
- means for subsequently locating the workpiece such that one of the pins enters a second locating hole of the one row and the other pin enters a second locating hole of the other row; and
- means for forming a second row of orificed projections in the workpiece between the second locating hole of the one row and the second locating hole of the other row.


4,292,863

AUTOMATIC SOCKET EJECTOR

Jack L. Hickman, 1809 Plaza Way, Walla Walla, Wash. 99362
Continuation-in-part of Ser. No. 119,932, Feb. 8, 1980, abandoned. This application Aug. 5, 1980, Ser. No. 175,431
Int. Cl.³ B25B 13/58

U.S. Cl. 81-184

10 Claims



1. In a tool for engaging interchangeable sockets each having a drive end with a polygonal drive opening and a working end with a socket opening;

a body having an outer face and an integral drive fitting projecting outward from said face, said drive fitting being complementary to the drive opening of a socket and being formed about a center axis;

an ejector pin having an inner end and an opposed outer end, said ejector pin being slidably mounted within the body for relative movement parallel to said axis between a retracted position wherein its outer end is adjacent said face and an extended position wherein its outer end protrudes outward from said face at a location alongside the drive fitting;

biasing means operably connected between the body and the ejector pin for urging said ejector pin to its extended position;

and latch means movably mounted on the body and operably engageable with the ejector pin when said pin is in its retracted position for normally retaining the ejector pin in the retracted position when a socket is mounted on the drive fitting; said latch means being manually actuable for selectively disengaging the ejector pin to permit said pin to move to its extended position by operation of said biasing means.

4,292,864


AUTOMATIC MAGAZINE AND FEEDER FOR AUTOMATIC MULTI-MANDREL LATHE

Pietro Cucchi, and Giovanni Cucchi, both of Bussero, Italy
Filed Oct. 3, 1979, Ser. No. 81,445

Claims priority, application Italy, Oct. 5, 1978, 28441 A/78; Mar. 16, 1979, 21041 A/79; Sep. 12, 1979, 25656 A/79
Int. Cl.³ B23B 13/00, 25/00

U.S. Cl. 82-2.7

5 Claims



1. An automatic feeder for a multi-mandrel lathe having as many channels as said lathe has mandrels, wherein: each of said channels comprise, a fixed channel forming element (3) and a movable channel forming element (4); each of said elements (3), (4) is modular being mechanically and functionally interchangeable with one other; further, each of said elements comprise a covering part formed of harmonic steel (25) stiffened with a continuous desounding dampening bar (27) of an elastomer.

4,292,866


TOOLHOLDER WITH EXPANSIBLE SHANK

Thomas E. Kaczynski, Willoughby, Ohio, assignor to Kennametal Inc., Latrobe, Pa.

Filed Jan. 10, 1980, Ser. No. 111,128

Int. Cl.³ B23B 29/00, 5/22; B26D 1/12
U.S. Cl. 82-36 R

11 Claims



1. A toolholder comprising: a tool body having an insert seat thereon and having an abutment surface thereon for abutting a tool support member and with means thereon to keep said tool body nonrotational with respect to the tool support member; expansible shank connected to said tool body and said expansible shank receivable in a bore of a tool support member; reciprocally movable means comprising a convex abutment surface for expanding said expansible shank so as to lock said shank in the bore of the tool support member.

4,292,867


APPARATUS AND METHOD FOR SLITTING ELONGATED ROLLS OF MATERIAL

Carl A. Stoffels, Flemington, and Nicholas J. Genovese, Union, both of N.J., assignors to Judelshon Industries Division, John Dusenberry Co., Inc., Randolph, N.J.

Filed Nov. 6, 1979, Ser. No. 91,697

Int. Cl.³ B23B 1/00, 7/00, 3/04
U.S. Cl. 82-47

25 Claims



1. A method of slitting elongated rolls of web material rolled upon a tubular core comprising the steps of:

- rotating a web of material rolled upon a tubular core about an axis of said core;
- cutting through said web of material with a rotating circular knife blade moving transversely to said axis of said core in a cutting plane;
- simultaneously sawing through said web of material with a powered rotary circular saw blade moving transversely to said axis of said core through a plane common with said cutting plane;
- cutting through said core with a rotating core cutting knife moving through said cutting plane subsequent to said simultaneous cutting and sawing through said web material.

4,292,865

TOOL HOLDER FOR VARYING TOOL RAKE ANGLE

Chunghong R. Liu, 765-8 San Antonio Rd., Palo Alto, Calif. 94303; Jnaneshwar H. Nayak, Stanford, Calif.; Herbjorn Stenberg; Felipe J. Huerta, both of Palo Alto, Calif., and Woodrow A. Hall, San Jose, Calif., assignors to Chunghong R. Liu, West Lafayette, Ind.


Continuation of Ser. No. 824,530, Aug. 15, 1977, abandoned.

This application Dec. 10, 1979, Ser. No. 101,980

Int. Cl.³ B23B 29/12

U.S. Cl. 82-36 R

2 Claims



1. Apparatus for removing material from a workpiece with a cutting member having a rake face and a cutting tip, the rake face and a line perpendicular to the relative movement of the workpiece and the cutting member forming a rake angle, comprising:

- rotatable means for holding the cutting member;
- means for rotating said rotatable holding means to change the rake angle; and
- brake means for releasably gripping said rotatable holding means to securely hold the cutting member when removing the material from the workpiece, including an energizable coil and brake pads movable in response to energization of said coil.

4,292,868

TEXTILE SPOOLING MACHINE, AN APPARATUS AND METHOD TO PREVENT THE FORMATION OF LOOSE CUT THREAD PIECES

Hermann Werffeli, Horgen, Switzerland, assignor to Maschinenfabrik Schweizer AG, Horgen, Switzerland


Filed Feb. 27, 1980, Ser. No. 125,137

Claims priority, application Switzerland, Mar. 8, 1979, 2243/79

Int. Cl.³ B65H 63/02, 63/06

U.S. Cl. 83—13

7 Claims



1. In a spooling machine, a method to prevent formation of stray cut filament pieces, wherein the filament is spooled with controlled tension from a payout spool (2) to a takeup spool (8), and which includes sensing means (50) and a thread cutting apparatus (56) positioned in the path of the thread from the payout spool to the takeup spool, and responsive to an "off-size" signal to sever the thread if an "off-size" signal is sensed, which comprises, in accordance with the invention, the steps of sensing thread tension and deriving a tension signal; and inhibiting application of the "off-size" signal to the thread cutting apparatus (56) upon failure to sense the tension signal, to prevent cutting of thread which has broken, resulting in failure of filament tension, regardless of the presence of an "off-size" signal from the thread size sensing means (5).

4,292,869

UNITARY PUNCH AND DIE ASSEMBLY


Bernard J. Wallis, 25200 Trowbridge Ave., Dearborn, Mich. 48124

Filed Apr. 18, 1980, Ser. No. 141,678

Int. Cl.³ B21D 45/00; B26D 7/00; B26F 1/00

U.S. Cl. 83—137

18 Claims



1. A unitary punch and die assembly comprising a generally C-shaped holder having a pair of vertically opposed jaws at one side thereof, the lower jaw having a die button secured thereon, the upper jaw having a vertical bore therein defining a main cylinder the lower end portion of which is adapted to be connected to a source of gas under pressure, said upper jaw having a smaller diameter bore concentric with the main cylinder and extending downwardly from the lower end of the main cylinder through the lower end of said upper jaw, a main

piston arranged for vertical sliding movement in said main cylinder and projecting upwardly through the upper end thereof, a punch secured to said main piston to move vertically therewith and extending downwardly through said main piston and said smaller bore in vertical alignment with said die button, said main piston having a vertical bore on the under side thereof which defines an auxiliary cylinder, a hold down sleeve slideably arranged on said punch and extending downwardly through said main cylinder and said smaller bore, the upper end of said hold down sleeve forming an auxiliary piston slideably arranged within said auxiliary cylinder, said auxiliary piston having an outer diameter larger than the outer diameter of the lower end portion of the sleeve so that the sleeve is biased upwardly on the punch by the pressure of the gas acting against the under side of the auxiliary piston, means acting between the main piston and said hold down sleeve and biasing said sleeve downwardly on the punch with a force greater than that exerted against the under side of the auxiliary piston by the gas pressure in said cylinder such that the lower end of the sleeve normally extends downwardly below the leading end of the punch, interengageable abutment means on said main and auxiliary piston for limiting the extent of downward movement of said sleeve relative to the punch and for lifting the sleeve with the punch when the abutments are interengaged whereby, when a downward force is applied to the upper end of the punch which is of sufficient magnitude to overcome the pressure exerted by the gas against the under side of the main piston, the punch and sleeve descend as a unit until the lower end of the sleeve engages and clamps a workpiece down on said die button and, thereafter, the punch continues to move downwardly to punch the workpiece and when said downward force on the upper end of the punch is relieved, the pressure of the gas in said main cylinder raises the punch and, upon interengagement of said abutments, lifts the hold down sleeve with the punch.

4,292,870

GUIDE PLATE FOR WOOD WORKING TOOLS


John E. Mericle, 2202 Torrey Pines, Tucson, Ariz. 85710

Filed Mar. 25, 1980, Ser. No. 132,506

Int. Cl.³ B27B 5/18

U.S. Cl. 83—471.2

10 Claims



1. Apparatus for working a true line in a workpiece with a tool, said apparatus comprising in combination: (a) a guide plate defining an upper plane for guiding relative movement between the workpiece and the tool, said guide plate including a plurality of parallel channels and a slot disposed in each of at least two of said channels; (b) a pair of tracks for slidably engaging two slotted ones of said channels; (c) means for interconnecting said tracks to preclude relative movement therebetween; (d) means for suspending the tool and an attached working member from said pair of tracks through said slots to locate the working member in penetrable relationship with the upper plane for working the workpiece; (e) means for interconnecting said suspending means and

said tracks to obtain translatable movement of the tool commensurate with translatable movement of said interconnecting means; and

(f) means for positioning and maintaining the workpiece in fixed relationship to said guide plate and in interfering relationship to the working member;

whereby, upon translation of said pair of tracks under urging by said interconnecting means the working member of the tool works the workpiece along a true line with a precision commensurate with the degree of fit of said pair of tracks in said channels.

4,292,871

WELDED EDGE BAND SAW TOOTH GEOMETRY


Tom A. Neumeyer, and Francis W. Foster, both of Athol, Mass., assignors to The L. S. Starrett Company, Athol, Mass.

Filed Feb. 1, 1979, Ser. No. 8,755

Int. Cl.³ B27B 33/02; B23D 61/12

U.S. Cl. 83—661

10 Claims



1. In a welded edge band saw blade for high speed, heavy duty cutting, said blade having a tooth structure wherein each tooth has a substantially triangular-shaped tip portion of a high hardness, high strength material welded along a plane parallel to the direction of blade movement to a band base of strong, flexible material, and at least some of said teeth have a positive rake angle, the improvement wherein at least some of said teeth with said positive rake angle have a rake angle of between about 4° and 7°, a wedge angle between about 53° and 61°, a first relief surface having a first relief angle between about 25° and 31°, said first relief surface lying in a plane substantially normal to lateral sides of said tip portion, and a second relief angle of between about 50° and 60° defining in part an associated gullet space which extends in part beneath a reference line extending from a tooth apex at said first relief angle, said gullet space having a configuration for promoting the formation of a curled chip in said gullet during metal cutting.

4,292,872

APPARATUS FOR PERFORATING HOLLOW CYLINDERS

Reiner G. Brinker, Mechanicsville, Va., assignor to Philip Morris Incorporated, New York, N.Y.

Filed Nov. 21, 1979, Ser. No. 96,432

Int. Cl.³ B26F 1/24

U.S. Cl. 83—866


2 Claims

1. Apparatus for perforating a hollow cylinder of relatively rigidized paper with a plurality of axially spaced circumferentially extending rows of perforations, said apparatus comprising:

a rotary drum, a rolling shoe disposed adjacent said drum and having a concave rolling surface spacedly juxtaposed with the periphery of said drum to define therewith an arcuate sectional passage of fixed dimension through which a hollow paper cylinder can be advanced in a sideways travel thereof, from an entry end of said passage toward an exit end of said passage, first needle perforating means comprising a plurality of

needles carried in the rolling surface of said rolling shoe, and

second needle perforating means comprising a plurality of needles carried on the periphery of said rolling drum, rotation of said rotary drum effecting rolling of the paper cylinder along said rolling surface and perforation thereof by both said needle perforating means, the positioning of the first needle perforating means being staggered axially of the hollow cylinder with respect to the positioning of the second perforating means whereby the perforations



formed in adjacent ones of the rows of perforations are produced at opposite sides of said passage, said rolling shoe comprising an assembly of side-by-side arranged plates each having an edge surface alignable with like surfaces of the other plates to define the shoe rolling surface, each needle of the first needle plurality being received in a bore carried in the meeting surfaces of adjacent pairs of said plates, and biasing means urging each plate into side face-to-face contact with an adjacent plate for fixedly securing the needles in their respective bores.

4,292,873

ELECTRONIC MUSICAL INSTRUMENT

Takatoshi Okumura, Seiya Hamada, and Akio Imamura, all of Hamamatsu, Japan, assignors to Nippon Gakki Seizo Kabushiki Kaisha, Hamamatsu, Japan


Filed Dec. 10, 1979, Ser. No. 101,904

Claims priority, application Japan, Dec. 12, 1978, 53/154411

Int. Cl.³ G10H 1/057, 5/00

U.S. Cl. 84—1.01

9 Claims



1. An electronic musical instrument comprising: keys for playing notes of the instrument;

a key detection circuit for producing per each of depressed ones of said keys a key identifying signal which represents a name of the key and a key-on signal which represents an on-off state of the key;

a tone generator circuit for generating musical tone signals each with a respective amplitude envelope and respectively corresponding to the key identifying signals;

a key on-off memory circuit for receiving said key-on signal and storing the on-off state of said key;
 a key-on pulse generation circuit for generating a key-on pulse at the beginning of the key depression;
 a counter which starts counting upon receipt of said key-on pulse;
 a control circuit for generating a control signal which controls the start of said amplitude envelope in response to a count value of said counter and on condition that said key on-off memory circuit stores an on-state of the key;
 a key-off pulse generation circuit for generating a key-off pulse at the beginning of a release of the depressed key, said counter being reset and its counting started again by this key-off pulse;
 a release finish signal generated circuit for generating a release finish signal when the count value of said counter has reached a preset value on condition that said key-on memory circuit stores an off-state of the key; and
 a prevention circuit for preventing, responsive to said release finish signal, generation of said musical tone signal corresponding to the key which has caused the key-off pulse to be generated.

4,292,874

AUTOMATIC CONTROL APPARATUS FOR CHORDS AND SEQUENCES


Edward M. Jones, Cincinnati, Ohio, and Carlton J. Simmons, Jr., Florence, Ky., assignors to Baldwin Piano & Organ Company, Cincinnati, Ohio

Filed May 18, 1979, Ser. No. 40,107

Int. Cl.³ G10H 1/38, 1/42

U.S. Cl. 84—1.03

40 Claims



1. In an electronic musical instrument, an automatic rhythm generating device for generating selectable rhythm patterns of musical tones comprising:
 an array of playing keys;
 a plurality of rhythm switches for selecting rhythm patterns of tones, each rhythm switch in said plurality of rhythm switches corresponding to a rhythm pattern of tones and being operable to select the corresponding rhythm pattern;
 rhythm counter means for providing timing signals to control the timing of the beats of the rhythm patterns generated by the automatic rhythm generating device;
 memory storage means in which is stored binary data for each beat of each rhythm pattern, said binary data for each beat including trigger signal data indicating whether a trigger signal is required by each rhythm pattern and frequency deviation data indicating the value of the frequency deviation for the tone specified by each selectable rhythm pattern;
 logic control circuit means responsive to the timing signals from said rhythm counter means for selecting said trigger signal data from said memory storage means in accordance with a rhythm pattern selected by operation of a rhythm switch in said plurality of rhythm switches and for

providing a trigger signal during the depression of a playing key during each beat on which a tone is specified by a selected rhythm pattern, and for selecting from said memory storage means in accordance with a selected rhythm pattern the frequency deviation data corresponding to each beat on which a tone is specified by a selected rhythm pattern;
 programmable signal generator means responsive to the actuation of a playing key in said array of playing keys and to said frequency deviation data selected by said logic control circuit means for generating a tone signal of a frequency related to the frequency of the actuated playing key by the frequency deviation value selected by said logic control circuit means for a selected rhythm pattern;
 gating means for receiving said tone signal from said programmable signal generator means and for receiving said trigger signal from said logic control circuit means, said gating means passing said tone signal in response to the receipt of said trigger signal; and
 audio output means for receiving said tone signal passed by said gating means, said audio output means converting said tone signal into an audible tone.

4,292,875


STRAIN-GAUGE SOUND PICKUP FOR STRING INSTRUMENT

Carl-Ernst Nourney, Am Wagenrast 6, D 4000 Düsseldorf 12, Fed. Rep. of Germany
 Continuation-in-part of Ser. No. 935,916, Aug. 23, 1978, Pat. No. 4,228,715. This application Mar. 27, 1980, Ser. No. 134,622
 Claims priority, application Fed. Rep. of Germany, Aug. 25, 1977, 2738256

Int. Cl.³ G10H 3/18

U.S. Cl. 84—1.14

9 Claims



1. A musical instrument comprising:
 an instrument body;
 a plurality of strings anchored under tension to said body while extending with major portions of their length in a plane generally parallel to a surface of said body;
 support means on said surface holding said strings separated from said body, said support means including a plurality of webs of hard elastic material engaged by respective strings under a pressure transverse to said plane, said webs being free to vibrate in a direction parallel to said major portions in response to changes in the effective lengths of the respective strings; and
 transducer means for converting vibrations of said strings into electrical signals, said transducer means including a plurality of strain gauges respectively disposed on said webs with a direction of maximum sensitivity inclined to said plane at an acute angle.

4,292,876

WASHER

Henry R. De Graan, 20520 Walnut Ave., Walnut, Calif. 91789

Filed Aug. 2, 1979, Ser. No. 63,269

Int. Cl.³ F16B 43/00


U.S. Cl. 411—542

6 Claims

1. An improved steel and neoprene bonded washer of the type having a crowned steel washer having an elastomeric

washer adjacent the concave surface of the crowned washer, wherein the improvement comprises:

a steel washer having a generally flat outer ring and a conical portion extending from the flat outer ring to an opening at the center thereof, the angle of the sides of said conical portion being between 30° and 50°, said conical portion meeting the undersurface of the head of the screw



with which it is used at an angle of between 30° and 50°, and wherein the flat portion is between 15% and 33% of the outside diameter of the washer; and
 an elastomeric washer bonded to the concave surface of the steel washer, said elastomeric washer having an outside diameter which extends under a portion of said flat outer ring.

4,292,877

AMMUNITION LOADER WITH IMPROVED CHARGE BAR


Richard J. Lee, Highway "U", Hartford, Wis. 53027

Filed Oct. 21, 1976, Ser. No. 734,397

Int. Cl.³ F42B 33/02

U.S. Cl. 86—31

14 Claims



1. In an ammunition loader:

- a head member having a feed opening therein,
- a hopper for containing shell loading material and with said hopper having a discharge opening disposed above said head member,
- a movable charge bar disposed between said feed opening and said discharge opening and with said charge bar having a passage adapted to selectively receive shell loading material from said discharge opening and to transfer said material to said feed opening,
- a sizing and material metering bushing adapted to be removably disposed in said passage; said bushing being adapted to receive, hold and discharge shell loading material therefrom,
- and means for spilling said shell loading material out of said passage when said bushing is not disposed in the latter,
- said material spilling means comprising a leakage opening communicating between said passage and the outside of said charge bar, said leakage opening being blocked by said bushing when the latter is disposed in said passage.

4,292,878

AMMUNITION ORIENTATION MECHANISM


George D. Brooks, Burlington, and Donald J. Bushey, Sr., Milton, both of Vt., assignors to General Electric Company, Burlington, Vt.

Filed Aug. 24, 1979, Ser. No. 69,461

Int. Cl.³ F42B 39/10

U.S. Cl. 86—48

2 Claims



1. An ammunition handling system for a plurality of fixed cased rounds of ammunition, each round having a center of gravity which is spaced a first distance from a first end thereof and a second distance from the second end thereof, the first distance being greater than the second distance, each said round having a removable sleeve disposed on a portion thereof adjacent one of said ends, said system comprising:

- a longitudinally advancing endless conveyor having an upper flight having a train of transversely elongated, open top and bottom passageways, each passageway for receiving through its open top a respective round of ammunition in either of a first or second end to end orientation, and for discharging through its open bottom such round of ammunition;
- a table surface disposed under said upper flight for precluding the discharge through said open bottoms of said passageways the rounds of ammunition respectively received therein;
- a longitudinally extending recess in said table surface having a floor surface disposed below said table surface and so located transversely, that when a round of ammunition is in a passageway passing over said recess and in said first orientation, its respective center of gravity lies over said recess, thereby causing said second end of such round of ammunition to tilt downwardly into said recess while such round of ammunition is advancing longitudinally with said passageway; and when a round of ammunition is in a passageway passing over said recess and in said second orientation, its respective center of gravity lies over said table surface, thereby causing such round of ammunition to remain undisturbed while such round of ammunition is advancing longitudinally with said passageway;
- a cam surface extending progressively longitudinally and transversely adjacent said conveyor for engaging in sequence any upwardly projecting of said first ends of any rounds of ammunition which have their said second ends tilted downwardly into said recess to shift the angle of tilt beyond the perpendicular, whereby to change the orientation of such round of ammunition within its respective passageway;
- a ramp surface providing a continuum between said floor surface and said table surface disposed adjacent said conveyor longitudinally downstream of said cam surface, for engaging in sequence any downwardly tilted said second ends of rounds of ammunition for restoring in sequence such rounds of ammunition back into their respective passageways; and

sleeve removing means disposed downstream of said ramp surface for automatically removing the sleeve from each round of ammunition in sequence.

4,292,879

HOOK ASSEMBLY FOR SPRING TENSION CARRIER IN BRAIDING MACHINE


Shusuke Kokubun, Shizuoka, Japan, assignor to Kokubun Inc., Shizuoka, Japan

Filed May 12, 1980, Ser. No. 149,055

Int. Cl.³ D04C 3/18; B65H 59/04

U.S. Cl. 87-57

9 Claims




1. In a spring tension carrier for a braiding machine comprising a main body having a leaf-shaped portion adapted to be guided along a meandering groove in the base of the braiding machine, a bobbin support shaft supported by and extending uprightly from the main body and rotatably mounting a bobbin thereon, the bottom of the bobbin having a ratchet, a stopper lever pivoted at a mid-point between the opposite ends thereof and having a pawl at one end adapted to engage and disengage from the ratchet, an operation frame guide rod supported by and extending uprightly from the main body and having an intermediate thread guide mounted thereon, a substantially U-shaped vertical operation frame mounted on the operation frame guide rod to be guided for movement therealong, the operation frame being operatively connected at the lower end thereof to the other end of the stopper lever, a first spring mounted on the operation frame guide rod in a compressed state between the upper leg of the operation frame and the intermediate thread guide to normally urge the pawl into engagement with the ratchet, a hook assembly support rod supported by and extending uprightly from the main body in parallel relation to the bobbin support shaft and operation frame guide rod, a thread hook assembly mounted on the hook assembly support rod, a rod support member fitted on the operation frame guide rod and hook assembly support rod, and a second spring mounted on the hook assembly support rod in a compressed state between the hook assembly and rod support member, the improvement comprising a hook assembly which comprises a substantially U-shaped weight including a pair of opposed legs having aligned through holes therein adapted to receive the hook assembly support rod and a hook body positioned removably in said weight, said hook body having a through hole alignable with said holes in the legs of the weight, said hook body having a hook portion extending horizontally and then bending downwardly to form a thread guide recess in the underside thereof, said hook body and hook portion being integral and formed of a wear resistant material.

5. A hook assembly for a spring tension carrier of a braiding machine comprising a substantially U-shaped weight including a pair of opposed legs, said legs having aligned holes extending therethrough, and a hook body positionable removably in said weight between said legs thereof, said hook body having a through hole therein alignable with the holes in the legs of said weight, said hook body having a hook portion extending horizontally and then bending downwardly to thereby form a thread guide recess in the underside thereof, said hook body and hook portion being integral and formed of a wear resistant material.

4,292,880
QUADRANT ELEVATION CONTROL DEVICE
Bennie F. Lopez; Billy H. Campbell; Bobby D. Collier; William J. Laird; Edward J. Debona, and James E. Eubanks, Jr., all of Huntsville, Ala., assignors to The United States of America as represented by the Secretary of the Army, Washington, D.C.
Filed Sep. 4, 1979, Ser. No. 72,507
Int. Cl.³ F41F 3/04

U.S. Cl. 89-1.815

3 Claims



1. A quadrant elevation control device for a rocket launcher for controlling actuation of the rocket launcher to a predetermined launch angle relative to gravity, said quadrant elevation control device including means for selecting a predetermined angle to which the launcher is to be elevated and automatic means for interrupting an electrical circuit when said predetermined angle has been reached, said means for selecting a predetermined angle including a support structure on which a gunner's quadrant is mounted, said support structure being pivotally and slidably mounted relative to a housing structure to allow said support structure to be moved in and out of said housing structure and to be adjusted to a vertical position, said support structure having a first level vial mounted horizontally thereon, and said gunner's quadrant including a triangular shaped body and an adjustable pivotable arm pivotally connected to said triangular shaped body at a base corner thereof, said pivotable arm having an index pointer for adjusting said pivotable arm relative to an arcuate surface of said triangular shaped body, said arcuate surface having indicia thereon for indicating the adjusted position of said pivotable arm, and said automatic means being mounted on said pivotable arm.


4,292,881
AUTOMATIC FIREARM CONSTRUCTION
Gerhard Hupp, Oberndorf, and Helmut Mäder, Schramberg, both of Fed. Rep. of Germany, assignors to Mauser-Werke Obendorf GmbH, Fed. Rep. of Germany
Filed Jun. 6, 1979, Ser. No. 45,965
Claims priority, application Fed. Rep. of Germany, Jun. 8, 1978, 2825091
Int. Cl.³ F41D 10/04

U.S. Cl. 89-33 CA

1 Claim

1. In an automatic firearm of the type having a reciprocating breech block, a cartridge feed mechanism which is driven by the gas pressure through a piston, which extends parallel to the longitudinal axis of the firearm, which is capable of receiving at least two different sorts of ammunition and which is operated to feed a plurality of different types of ammunition into the counter recoil path of the breech block, the improvement comprising a rotatable bushing mounted in the drive head having an end drive face adjacent the feed mechanism with a slot therein which tapers inwardly, means for pivotally mounting the cartridge feed mechanism to said drive head, the cartridge feed mechanism including a housing portion, a drive hub rotatably mounted in said housing portion, a transfer element in said drive hub having a coupling projecting outwardly therefrom and being tapered inwardly in an outward direction and being engageable in said slot of said end drive face for


transmitting the drive motion for the cartridge feed mechanism, and means operatively connecting said transfer element



to said drive hub for resiliently centering said transfer element for reception in said slot.

4,292,882
ARMOR COMPRISING A PLURALITY OF LOOSELY RELATED SHEETS IN ASSOCIATION WITH A FRONTAL SHEET COMPRISING METAL ABRADING PARTICLES
Carol W. Clausen, 1715 E. Florence, Los Angeles, Calif. 90001
Continuation-in-part of Ser. No. 804,230, Jun. 7, 1977, abandoned. This application Dec. 4, 1978, Ser. No. 966,385
Int. Cl.² B32B 5/28, 7/00; F41H 1/02, 5/04
U.S. Cl. 89-36 A

10 Claims




1. A bullet proof armor panel structure including a pad comprising a multiplicity of normally flat sheets of fabric in loosely related surface to surface relationship, said pad having front and rear surfaces, and a flat metal abrading means with front and rear surfaces arranged with its rear surface opposing the front surface of the pad, said abrading means including a mass of hard metal abrading particulate material arranged with its particles in substantial bridging contact with each other and binding means normally maintaining the particles in substantial fixed position.

4,292,883
WHEEL CYLINDER
Christian Riquart, Paris, and Roland Levrai, Starns, both of France, assignors to Societe Anonyme DBA, Drancy, France
Filed Jul. 2, 1979, Ser. No. 54,320
Int. Cl.³ F15B 13/042

U.S. Cl. 91-29

2 Claims



1. A wheel cylinder comprising:
a body defining a bore therein, said bore having at least one open end;
an actuating piston reciprocally received in said bore and sealingly cooperating with said body to define a pressure chamber;
supply passage means defined in said wheel cylinder for communicating pressurized fluid from a source thereof to said pressure chamber, said supply passage means including an inlet orifice communicating with said bore, an annular groove on said actuating piston communicating with said inlet orifice, an axially-extending blind stepped bore having an end wall in said actuating piston, said stepped bore defining a small diameter portion adjacent the end wall thereof and a large diameter portion opening to said pressure chamber, and a radially extending flow path communicating said annular groove and said stepped bore;
pressure-responsive valve means received in said stepped bore for opening and closing fluid communication through said supply passage means, said valve means including a stepped pressure-responsive piston reciprocally received in said stepped bore and sealingly cooperating with said actuating piston, said stepped piston including a large diameter part received in said large diameter portion of said bore and a small diameter part received in said small diameter portion and communicating with atmospheric pressure via a vent port defined in said actuating piston, said large and small diameter parts cooperating to define a differential area on said stepped piston;
said stepped piston defining an axially-extending blind bore opening to said pressure chamber and a radially-extending bore communicating said blind bore with said inlet orifice via said radially-extending flow path and said annular groove;
said blind bore of said stepped piston receiving a movable valve member, a resilient member biasing said valve member toward the open end of said blind bore, and an annular valve seat secured in said blind bore at the open end thereof for movement with said stepped piston, said valve seat being sealingly engageable with said valve member;
said valve means further including an annular abutment member mounted in said stepped bore and secured to said actuating piston for movement in unison therewith, said abutment member carrying an axially-extending projection extending through said annular valve seat and engaging said valve member;
a resilient member received in said stepped bore biasing said stepped piston to a first position in engagement with said annular abutment member in which said valve seat is disengaged from said valve member by said axially-extending projection so that said valve means is open;
said stepped piston moving toward the end wall of said stepped bore in response to pressurized fluid from said pressure source to engage said valve seat with said valve

member to close said valve means at a predetermined pressure level, said stepped piston reciprocating to open and close said valve means so as to allow a selected pressure increase in said pressure chamber responsive to a pressure increase above said predetermined pressure level.

4,292,884

CONTROL ARRANGEMENT FOR A HYDRAULICALLY OPERATED DEVICE

Werner Schumacher, Asperg, and Günther Schwerin, Möglingen, both of Fed. Rep. of Germany, assignors to Robert Bosch GmbH, Stuttgart, Fed. Rep. of Germany


Filed Feb. 2, 1979, Ser. No. 9,045

Claims priority, application Fed. Rep. of Germany, Apr. 14, 1978, 2816212

Int. Cl.³ F15B 11/08, 13/043

U.S. Cl. 91-445

7 Claims




1. A control arrangement comprising a hydraulically operated cylinder and piston unit having a cylinder and a piston reciprocable therein for raising a load during feeding of hydraulic fluid into said cylinder of the unit, and lowering a load during discharge of said fluid therefrom, said arrangement further comprising a source of hydraulic fluid under pressure; an outlet conduit leading to a tank; an inlet conduit connected to said source; first valve means connected to said inlet conduit and movable between a first position connecting said inlet conduit with said outlet conduit and a second position connecting said inlet conduit with working conduit means leading to said cylinder of the unit; precontrol valve means coordinated with said first valve means for controlling the position thereof, said precontrol valve means having a return terminal connected to a return conduit leading to said tank and inlet terminal means leading over said first valve means to said source; second valve means in said working conduit means including a release piston movable between a first position directing flow of fluid through said working conduit means to said cylinder of the unit and a plurality of second positions permitting flow of fluid from said cylinder to said return conduit, said second valve means including a damping compartment and a control compartment on opposite sides of said releasing piston; passage means connecting said damping compartment to said return conduit and conduit means connecting said control compartment to said precontrol valve means; and a throttle in said return conduit, said return terminal of said precontrol valve means being connected to a point of said return conduit located downstream of said throttle so that upon increase of outflow of fluid from said cylinder the pressure in said damping compartment rises and said second valve means being constructed to decrease outflow of fluid from said cylinder as the pressure in said damping compartment rises, whereby the speed of lowering of the load will be independent of the magnitude of the load.

4,292,885
BELLOWS APPARATUS
Takeshi Jinnouchi, 774, Tsukagoshi, Sakado-shi, Saitama-ken, Japan
Division of Ser. No. 834,445, Sep. 19, 1977, Pat. No. 4,183,289.
This application Jul. 19, 1979, Ser. No. 59,109
Claims priority, application Japan, Sep. 22, 1976, 51/128026
Int. Cl.³ F16J 3/04

U.S. Cl. 92-43

1 Claim



1. A bellows apparatus comprising a bellows main body and restriction means for restricting elongation and contraction, said restriction means comprising:
a plurality of annular, first, second and third guide metals arranged integrally with said bellows main body with a predetermined spacing therebetween in the axial direction;
a plurality of first, second and third guide members, each secured integrally to each of said first, second and third guide metals respectively and extending in the axial direction and terminating in edge sections;
a plurality of first, second and third stoppers, each integrally extending in the circumferential direction from the edge sections of each of said first, second and third guide members respectively;
a plurality of first, second and third protuberances, each integrally extending in the circumferential direction from near the edge sections of said first, second and third guide members respectively;
said first and third guide metals being positioned to interpose said second guide metal therebetween and provided, respectively, with said first and third guide members being displaced at said first and third guide metals with respect to each other in the circumferential direction and extending oppositely to each other in the axial direction; and
said first, second and third guide members being disposed such that they do not overlap each other in the circumferential direction and restrict the elongation and contraction of said bellows main body in cooperation with said first, second and third stoppers and protuberances, said first stoppers being abutted by said second protuberances and said second stoppers being abutted by said third protuberances when said bellows main body is fully contracted.

4,292,886
HYDRAULIC ACTUATOR CUSHIONING DEVICE
IMPROVEMENT
William R. Weber, 4200 - 50th Ave., NE., Seattle, Wash. 98105
Filed Dec. 31, 1979, Ser. No. 108,490
Int. Cl.³ F15B 15/22


U.S. Cl. 92-85 B

1 Claim

1. In a device for cushioning an actuator of the type wherein return fluid from the actuator passes through an expansion chamber and thence to drain through a restriction for cushioning, wherein the improvement comprises:

- a. A piston with an orifice, mounted slidably in the expansion chamber, and a resilient means to bias the piston toward drain,
- b. A valve mounted slidably in the orifice, with resilient means to bias the valve toward the restriction, and, The valve to hold return fluid pressure on the piston face as it

spheric pressure chamber and means associated with said annular groove for defining a path of fluid communication from the atmospheric pressure chamber to a space formed between said diaphragm and said disc.




4,292,887
POWER SERVO BOOSTER
Ryuji Ohta, Higashimatsuyama, and Yoshimichi Inoue, Kawasaki, both of Japan, assignors to Jidosha Kiki Co., Ltd., Tokyo, Japan
Filed Oct. 26, 1978, Ser. No. 954,952
Claims priority, application Japan, Nov. 8, 1977, 52-149809[U]

Int. Cl.³ F01B 19/00

U.S. Cl. 92-94

9 Claims



1. A power servo operable by differential pressure comprising: a housing, a unitary piston disposed in said housing, a control member coupled to said piston, said unitary piston including a disc element and a flange portion with an annular groove formed between said disc and said flange, a diaphragm member secured at its outer periphery to said housing to divide said housing into two compartments one compartment a negative pressure chamber and the other an atmospheric pressure chamber, said diaphragm member having a generally cylindrical section and an inner peripheral portion secured in said annular groove, means disposed in said negative pressure chamber for biasing said unitary piston toward said atmo-


4,292,888
FOUNTAIN PUMP FOR ELECTRIC COFFEE PERCOLATORS

Alton R. Wells, 1500 S.W. 40th St., Ft. Lauderdale, Fla. 33315; Robert M. Wells, 4371 Ira Rd., Akron, Ohio 44313, and James L. Heir, 11515 Stafford Rd., Trumbull County, Burton, Ohio 44021

Continuation-in-part of Ser. No. 877,315, Feb. 13, 1978, abandoned, which is a continuation-in-part of Ser. No. 704,461, Jul. 12, 1976, abandoned. This application Oct. 15, 1979, Ser. No. 84,666

Int. Cl.³ H05B 1/02; A47J 31/053; F04B 19/24
U.S. Cl. 99-312

3 Claims



1. Apparatus for making coffee brew from coffee grounds comprising:
a container having a top and a bottom;
an upwardly projecting, flat-topped, cylindrical encased heating element centrally received within the container and maintained at the bottom thereof;
a flat-topped, open bottom, cylindrical member supported on the heating element, said cylindrical member surrounding said heating element in spaced relation thereto, the cylindrical member having a hollow stem in communication with the interior thereof and extending upwardly from the center of the flat top, the flat-topped cylindrical member being spaced from the top of the heating element from between 1/16" and 1/4" to form a chamber for receiving and retaining a volume of steam bubbles therein, said stem having a lower end that protrudes into the said space between the top of said heating element and the flat top of said cylindrical member, and the side wall of the cylindrical member being characterized by a conically inwardly and downwardly extending lower end fluid-tightly circumferentially engaging the sidewall of the heating element and by six to ten uniformly circumferentially spaced uniform holes in the conical portion of said lower end such that said holes are downwardly and outwardly facing with relation to the heating element, the total area of said holes being between about 0.0258 and 0.043 square inches.

4,292,889

METHOD AND MEANS FOR INJECTING FLUIDS INTO MEAT PRODUCTS


Ray T. Townsend, Des Moines, Iowa, assignor to Townsend Engineering Company, Des Moines, Iowa

Filed May 25, 1979, Ser. No. 42,315

Int. Cl.³ A23B 4/02; A23L 3/34

U.S. Cl. 99—533

11 Claims



1. A machine for injecting fluid into a food product comprising meat, fish or poultry, said machine comprising:
 - a needle assembly having a needle manifold and a plurality of downwardly extending hollow needles each in communication adjacent its upper end with said needle manifold and each having an opening adjacent its lower end;
 - said needle assembly having a metering chamber therein, said metering chamber having an inlet opening in communication with a pressurized source of fluid and an outlet opening in communication with said manifold;
 - one way check valve means in said inlet and outlet openings for permitting fluid to enter into said chamber through said inlet opening and to pass from said chamber to said manifold through said outlet opening while at the same time preventing backflow of said fluid from said chamber through said inlet opening towards said fluid source and from said manifold through said outlet opening toward said chamber;
 - a metering piston within said metering chamber movable in a first direction for drawing fluid into said metering chamber and being movable in a second direction for forcing fluid from said chamber into said manifold and out through said lower ends of said needles;
 - ram means for moving said needle assembly downwardly to cause said needles to penetrate said meat and for moving said needle assembly upwardly to withdraw said needles from said meat;
 - sensing means for sensing the depth to which said needles penetrate said meat;
 - metering control means connected to said sensing means and said metering piston for controlling the stroke length of said piston in response to the depth of needle penetration into said meat whereby said piston will draw into and expel from said chamber a volume of fluid substantially equal to the volume of the cavities in said meat formed by said needles penetrating therein;
 - said sensing means comprising a stripper plate movably mounted to said needle assembly, first spring means yieldably holding said stripper plate against movement with respect to said needle assembly;
 - said stripper plate being positioned adjacent said lower ends of said needles so as to engage the upper surface of said meat when said needles begin penetration of said meat, said first spring means being yieldable to permit continued downward movement of said needles to penetrate said

meat while said stripper means is held against further downward movement by said upper surface of said meat.

4,292,890

GRAIN POLISHING AND WHITENING MACHINE
Felipe Salete-Garcés, Avenida Ano de Juárez 198, Granjas San Antonio, Iztapalapa, Mexico (13, D.F.)


Filed Nov. 21, 1979, Ser. No. 96,269

Claims priority, application Mexico, Jan. 24, 1979, 176383

Int. Cl.³ B02B 3/04, 3/06

U.S. Cl. 99—603

13 Claims



1. A grain polishing and whitening machine comprising base box means, housing means having first, second, third and fourth coaxially arranged separate housing sections, said first housing section being fixedly mounted on said base box means, said first and second housing sections having an inner concentric cylindrical member forming annular passage means therethrough, concentric hollow rotor means extending through said first, second and third housing sections and opening into said base box means, bearing means in said first housing section to rotatably support said rotor means, drive means in said base box means to rotate said rotor means, fan means to cause air to flow into and through said hollow rotor means and out of the machine through said annular passage means, grain inlet means arranged through the wall of said second housing section, screw conveyor means engaged to said rotor means within said second housing section and capable of pushing the grain from said grain inlet means to said third housing section, said screw conveyor means having a helical rib lined with an abrasive layer at least on its forward surface, cylindrical indented screen means in said third housing section and having inclined elongated slots and inwardly extending indentations throughout its surface, said screen means being concentrically arranged around said rotor means and forming a grain treating chamber therebetween, a plurality of radial bores in said rotor means to allow air to flow in said treating chamber and through the mass of grains and outwardly of the slots of said screen means, said rotor means having a pair of longitudinally arranged, diametrically opposed, tangentially mounted, adjustable diagonally fluted, removable knife means directly confronted and spaced from said screen means, the flutes of said fluted knife means being inclined in a direction such that rotation thereof will cause a flow of grain opposed to the flow of grain produced by said screw conveyor means in order to compact the mass of grains in said treating chamber, a pair of longitudinally arranged, diametrically opposed, diagonally fluted, removable knife means mounted on said screen means to cooperate with said knife means mounted on said rotor means, and grain outlet means arranged in said fourth housing section.

4,292,891

ALUMINUM CAN CRUSHER


James D. Shelley, 3574 Buena Vista, Lemon Grove, Calif. 92045

Filed Jun. 23, 1980, Ser. No. 162,014

Int. Cl.³ B30B 1/04

U.S. Cl. 100—193

5 Claims



1. A can crusher comprising:
 - (a) a base;
 - (b) a crusher plate having one end pivoted to said base and the other end free of said base;
 - (c) a lever arm being pivotally connected at a first pivot point along its length to the free end of said crusher plate, said lever arm being pivotally connected at a second pivot point to one end of a pivotal link, the other end of said pivotal link being pivoted to said base;
 - (e) said lever arm having an extended foot defined on the underside thereof on the side of said first pivot towards said second pivot, whereby, upon raising said lever arm said plate is raised, and upon inserting a can between said base and said plate and further raising said lever said foot buckles one end of said can, and upon subsequently lowering said lever arm said can is crushed against said base by said crusher plate.

4,292,892

CONVEYOR APPARATUS FOR PRESS MACHINES


William Combs, 6131 Canmoor, Troy, Mich. 48084

Filed Jul. 30, 1980, Ser. No. 173,466

Int. Cl.³ B30B 15/32

U.S. Cl. 100—218

8 Claims



1. A conveyor apparatus for use with a press machine having a movable head comprising:
 - means for conveying material from said press machine, said conveying means including a drive rod coupled to said conveying means for moving said conveying means; and
 - means for advancing said conveying means, said advancing means comprising:
 - a ratchet wheel fixedly mounted on said drive rod, said ratchet wheel including a plurality of circumferentially spaced finger engaging members; and
 - an arm adapted to be connected to said press head for movement therewith, said arm having a plurality of linearly spaced fingers extending outward therefrom, wherein successive ones of said fingers engage said finger engaging members on said

ratchet wheel causing rotation of said ratchet wheel and said drive rod to advance said conveying means upon movement of said press head.

4,292,893

ENDLESS BAND PRINTER WITH SPACERS BETWEEN DRIVE WHEELS


Raymond L. Kirby, Jr., Vandalia, Ohio, assignor to Monarch Marking Systems, Inc., Dayton, Ohio

Continuation of Ser. No. 941,352, Sep. 11, 1978, abandoned, which is a continuation-in-part of Ser. No. 811,239, Jun. 29, 1977, abandoned, which is a division of Ser. No. 642,037, Dec. 18, 1975, Pat. No. 4,052,938, which is a continuation-in-part of Ser. No. 537,630, Dec. 30, 1974, Pat. No. 3,933,092. This application Jul. 21, 1980, Ser. No. 170,409

Int. Cl.³ B41J 1/20

U.S. Cl. 101—111

14 Claims



1. Printing apparatus, comprising: a print head having a plurality of rotatably mounted drive wheels having gear teeth, a support, a series of printing bands trained about the support and the drive wheels, a shiftable drive gear selectively cooperable with the gear teeth on any drive wheel, the improvement comprising at least one non-printing spacer disposed between a pair of adjacent drive wheels, each spacer having adjacent tooth surfaces and an intervening space in line with a space between adjacent teeth on the drive wheels to enable a smooth transition as the gear is shifted from contact with the teeth of one drive wheel on one side of the spacer and the teeth of another drive wheel on the other side of the spacer.

4,292,894

CONSTANT PRINTING PRESSURE MECHANISMS FOR LABEL PRINTING MACHINE

Yo Sato, Tokyo, Japan, assignor to Kabushiki Kaisha Sato Kenkyusho, Japan


Division of Ser. No. 866,991, Jan. 5, 1978, Pat. No. 4,207,816, which is a continuation-in-part of Ser. No. 819,103, Jul. 26, 1977, abandoned. This application Oct. 22, 1979, Ser. No. 87,315

Claims priority, application Japan, Jul. 29, 1976, 51-089701; Jan. 8, 1977, 52-0505

Int. Cl.³ B41J 5/00

U.S. Cl. 101—291

15 Claims



1. A label printing machine, comprising:
 - a machine frame;
 - a printing lever supported to be movable

with respect to said machine frame; a printing head connected to said printing lever to be movable thereby; an operating lever rigidly connected to said printing lever for operating said printing lever in a print direction and in a return direction; said frame including a portion attached thereto toward which said operating lever is movable; a platen opposable to said printing head; said printing head being movable to said platen upon movement of said printing lever in said print direction; a constant printing pressure mechanism, comprising: pressure applying means attached to said frame portion; pressure receiving means attached on said operating lever to be movable with respect to said pressure applying means; said pressure receiving means being provided for being engaged by and being positioned to be engaged by said pressure applying means upon movement of said operating lever toward said frame portion; said pressure receiving means being adapted to resist its movement past said pressure applying means until said pressure applying means applies more than a predetermined pressure thereto and said pressure receiving means then passing said pressure applying means, whereupon said printing head is thereafter freed by said pressure receiving means to move to said platen for printing a label.

4,292,895


EXPLOSIVE SAFE-ARMING APPARATUS FOR PERFORATING GUNS

William T. Bell, and Jose B. Garcia, both of Houston, Tex., assignors to Schlumberger Technology Corporation, Houston, Tex.

Filed Oct. 9, 1979, Ser. No. 82,686
Int. Cl.³ F42C 15/34

U.S. Cl. 102—306

14 Claims



9. An explosive safe-arming apparatus, for use with a well bore perforator having a receptor detonating explosive and a donor detonating explosive adapted for detonating said receptor explosive, comprising:


- a fixed barrier adapted to be disposed between the donor detonating and receptor detonating explosives;
- a movable barrier adapted to be disposed between laterally facing portions of said donor detonating and receptor detonating explosives; and
- a movable barrier actuating means for selectively translating the movable barrier either into engagement with the fixed barrier whereby the donor detonating and receptor detonating explosives are separated by the fixed and movable barriers and are in a predetermined perforator disarming operating position, or into a spaced relationship from the fixed barrier whereby the laterally facing portions of said donor detonating and receptor detonating explosives are in a predetermined perforator-arming operating position.

4,292,896
DETONATING DEVICE

William B. Morrey, and David M. Welsh, both of Brownsburg, Canada, assignors to CXA Ltd./CXA Ltee, Montreal, Canada
Filed Apr. 21, 1980, Ser. No. 141,890
Claims priority, application Canada, May 31, 1979, 328796
Int. Cl.³ F42B 3/10

U.S. Cl. 102—275.8

1 Claim



1. An elongated, flexible, unitary detonating device of determinate length for detonating one or more explosive booster charges within an explosive-charged borehole, the said detonating device comprising in combination:

- (a) a core member consisting of a low energy shock wave conductor comprising a hollow, elongated flexible tube having a reactive substance distributed as a thin layer on the inner surface thereof; and
- (b) a sheath member surrounding said core member over substantially its whole length except for a short non-surrounding section at each end of said core member, said sheath member comprising a standard detonating cord construction capable of detonating a selected booster charge in contact therewith, the said core member being incapable of laterally explosively initiating the said surrounding standard detonating cord sheath member.

4,292,897


TROLLEY ROTATION STABILIZING DEVICE

Takao Wakabayashi, Toyonaka, Japan, assignor to Nakanishi Metal Works Co., Ltd., Osaka, Japan
Filed Apr. 25, 1979, Ser. No. 33,254

Claims priority, application Japan, Apr. 26, 1978, 53-56536[U]

Int. Cl.³ B61B 3/00, 13/12; B61C 13/04; B61F 5/00
U.S. Cl. 104—172 S

6 Claims



1. A device for preventing turn-around motions of free

trolleys in a power-and-free conveyor having a power rail and a free rail, the device comprising:

- (a) a connecting link which interconnects the free trolleys and has holes on the opposite ends thereof;
- (b) downwardly directed rods extending from the free trolleys, one from each trolley, each of the rods rotatably and slidably passing through a hole of the connecting link and having a stopper at its lower end, wherein the stopper receives and supports the connecting link when the free trolleys are on the free rail; and
- (c) turn-preventing means operatively coupled between the free trolleys and the connecting links for preventing rotation of the free trolleys when the connecting link is moved along the rods towards the free trolleys as the free trolleys are removed from the free rail.

3. A device for preventing turn-around motions of the free trolleys in a power-and-free conveyor having a power rail and a free rail, the device comprising:

- (a) a connecting link which interconnects the free trolleys and has holes on the opposite ends thereof;
- (b) downwardly directed arms extending from the free trolleys, one from each trolley;
- (c) downwardly directed rods extend from the lower portions of the arms, one from each trolley, each of the rods rotatably and slidably passing through a hole of the connecting link and having a stopper at its lower end, wherein the stopper receives and supports the connecting link when the free trolleys are on the free rail; and
- (d) turn-preventing means operatively coupled between the free trolleys and the connecting links for preventing rotation of the free trolleys when the connecting link is moved along the rods towards the free trolley as the free trolleys are removed from the free rail.

4,292,898

FILAMENT COMPOSITE RAILROAD CAR

Robert Gordon, Arcadia; Harry A. King, Yorba Linda, both of Calif.; James V. Springrose, Edina, and Robert W. Cuddihy, Fridley, both of Minn., assignors to Cargill, Incorporated, Minneapolis, Minn. and Structural Composite Industries, Inc., Azusa, Calif.

Continuation of Ser. No. 864,243, Dec. 27, 1977, abandoned.
This application Jan. 18, 1980, Ser. No. 113,240

Int. Cl.³ B61D 7/00

U.S. Cl. 105—238 R

3 Claims



1. A railway hopper car comprising: an elongated load bearing railroad car body having sloping end walls at each longitudinal end thereof and substantially continuous longitudinal side and bottom walls intermediate said sloping end walls, said longitudinal side and bottom walls being substantially straight in a direction along the railroad car longitudinal axis to form a car body, said end walls and said longitudinal side and bottom walls being formed of a fiber-reinforced organopolymeric resin composite comprising from about 60 to about 75 weight percent of glass reinforcing filaments and from about 25 to about 40 weight percent of a structural polyester organopolymeric matrix resin, said matrix having a heat distortion temperature of at least about 90° C., a flexural strength of at least about 20,000 psi, a flexural modulus of at least about 5.0×10⁵ psi, and a tensile elongation of at least about 3.0 percent, said glass reinforcing filaments of said resin composite of said car body being oriented in said car body at an angle such that said glass filaments and said matrix resin are capable of providing a composite comprising from about 70 to about 80

percent by weight of glass fibers and from about 20 to about 30 percent of said matrix resin and in the direction of winding having a tensile strength of at least about 100,000 psi, a flexural modulus of at least about 6×10⁶ psi, an interlaminar shear strength of at least about 5,000 psi, an interlaminar shear strength after 24 hour water boil of at least about 5,000 psi, a flexural strength at room temperature of at least about 100,000 psi, a flexural fatigue strength for 1×10⁶ completely reversed cycles of at least about 30,000 psi, and a density of from about 0.07 to about 0.08 pounds per cubic inch, a bearing strength of at least about 25,000 psi and a self-extinguishing flammability rating; coupling means at each end of the car for coupling the car to other cars; a truck at each end of the car body, and supporting means pivotally mounted on each of said trucks for supporting said car body at each respective sloping end wall thereof for transport on rails.

4,292,899


PROTECTIVE ELEMENT FOR FORK-LIFT PALLETS

Vincent B. Steffen, 321 E. Hamilton, New Hampton, Iowa 50659
Filed Sep. 11, 1978, Ser. No. 941,189

Int. Cl.³ B65D 19/38

U.S. Cl. 108—51.1

4 Claims



1. For use with a fork-lift pallet having an elongated, horizontal wooden stringer provided with an inverted U-shaped opening affording entry of a tine of a fork-lift truck, a protective element comprising:

- a generally rectangular plate having an inverted U-shaped opening for substantial register with the stringer opening, said plate having such length and height as to protectively overlie the front face of the stringer to both sides of and above the stringer opening, said plate opening affording entry of the fork-lift truck tine to the stringer opening while the remainder of the plate protects the front face of the stringer from damage by the tine, said plate provided with perforations to receive fasteners for affixation of the plate to the stringer, at least two of which said perforations lie above and within the confines of the ends of the plate opening extended, in order to reinforce the narrow portion of the plate and stringer against buckling and a lip integral with the plate and extending rearwardly from the upper edge of the plate opening so as to engage and underlie that portion of the stringer opening along the upper edge of the stringer opening, wherein the length of the lip is spaced an appreciable distance from the edges of the plate opening and is substantially centered therein.

4,292,900

ROTATABLE PALLET POST FOR PLASTIC PALLETS

Russell P. Bula, Whitby, Canada, assignor to E. I. Du Pont de Nemours and Company, Wilmington, Del.

Filed Sep. 7, 1979, Ser. No. 73,327

Claims priority, application Canada, Sep. 8, 1978, 310985


Int. Cl.³ B65D 19/32, 19/42; F16M 11/20

U.S. Cl. 108—51.1

19 Claims

1. A pallet post adapted to be positioned between a plastic upper deck and a plastic lower deck of a pallet, the pallet post having a longitudinal axis, means for rotatably mounting the pallet post about said axis between the upper deck and the lower deck of the pallet, and at least three winglike arms

projecting radially from the axis and extending longitudinally therealong, the winglike arms being substantially equally spaced about the axis, with each of said arms being joined to an adjacent arm by a smoothly curved concave surface, and each



arm having a smoothly curved convex surface along its outer edge when viewed from a direction parallel to the axis, and a concave surface at the mid portion of its outer edge when viewed from a direction perpendicular to its radial plane passing through the axis.

4,292,901

CORNERBOARD FOR PALLET


Clayton E. Cox, 1371 Eureka Canyon Rd., Watsonville, Calif. 95076

Continuation-in-part of Ser. No. 907,096, May 18, 1978, abandoned. This application Aug. 6, 1979, Ser. No. 63,949. The portion of the term of this patent subsequent to May 6, 1997, has been disclaimed.

Int. Cl.³ B65D 19/06

U.S. Cl. 108—55.1

6 Claims



1. A generally L-shaped corner structure for a pallet comprising in combination:

- a. a top member 21 or 68, said member having a top cap 25 or 82 adapted to extend over the corner of a loaded pallet and having a thin L-shaped fin extending downward from said top cap, said L-shaped fin being composed of two thin flat elements 31 and 33 or 76 and 78 held at right angles to each other;
- b. a bottom member 43 or 70 said bottom member having an L-shaped right angle configuration 47 or 86 to fit over the outside of the flat elements of said top member and having at least one inwardly extending member 45 or 90 and 92 to cover the edges and at least a portion of the inner surface of said side member by providing a bight (junction of 43 and 57) or 94 and 96 whereby
- c. said top member can telescope into said bottom member to form a load-supporting corner structure for pallet.


4,292,902

SHELF SYSTEM

Wade H. Barrineau, 5159 E. Shore Dr., Conyers, Ga. 30207
Continuation of Ser. No. 628,133, Nov. 3, 1975, abandoned. This application Nov. 1, 1976, Ser. No. 737,401
Int. Cl.³ A47B 57/16

U.S. Cl. 108—146

10 Claims



1. An adjustable and removable shelf assembly comprising: a pair of rear vertical spaced supports having a plurality of vertically spaced openings therein;
- a pair of opposed, spaced front vertical supports having a plurality of vertically spaced openings therein; and
- a removable shelf to be supported between the rear supports and the front supports, said shelf comprising: a first rigid, non-flexing unitary edge member defining the outermost rear edge of the shelf and terminating in outwardly facing hooked projections for insertion into the openings of the rear vertical supports;
- a second unitary edge member defining the outermost front edge of the shelf and terminating in outwardly facing hooked projections, said second edge member being a flat strap with resiliently flexural ends permitting the hooked projections on opposing ends to be flexed inwardly for inserting said hooked projections into the openings of the front vertical supports while the hooked projections of the first edge member are engaged in the openings of the rear vertical support;
- shelf means formed of a rigid, non-flexing network of transverse and longitudinal supports, said transverse supports rigidly interconnecting substantially the full length of said first unitary edge member to a partial centrally located length of the second unitary edge member to provide a rigid, non-flexing support surface of the shelf and to define resiliently flexural ends on only the second edge member.

4,292,903

ADJUSTABLE BOX STOOL


Robert J. Hockema, 1200 Ridgeway, Lafayette, Ind. 47904
Filed Nov. 2, 1979, Ser. No. 90,580
Int. Cl.³ A47B 9/12, 9/14, 9/20

U.S. Cl. 108—146

1 Claim

1. An adjustable box stool, comprising, in combination, an outer hollow box, an inner hollow box vertically slidable in said outer box, a vertical row of spaced-apart openings on opposite sides of said outer box, a horizontally slidable clevis pin latch in each opposite side wall of said inner box being outwardly slidable into selective of said openings in said outer box, for securement of said boxes together; each said clevis pin latch being connected by a first wire to a longitudinally intermediate portion of a first pair of link rods which at one ends are

attached to a bracket mounted on a bottom of said inner box; a second pair of link rods attached at their one ends to opposite ends of said first link rods, and opposite end of each said second pair of link rods being hooked together to one end of a singular, upwardly second wire extending slidably through a trans-



verse hole in a horizontal dowel secured between said side walls of said inner box, and an upper opposite end of said second wire being fitted with a pull ring; and an access hole in a top wall of said inner box for a person's hand to reach therein and pull said pull ring.

4,292,904

FURNACE AND BOILER SYSTEM AND METHOD OF OPERATION THEREOF


Cecil R. Brandt, P.O. Box 35, Westfield, Ill. 62474

Filed Mar. 13, 1980, Ser. No. 130,088

Int. Cl.³ F23B 1/10

U.S. Cl. 110—198

4 Claims



1. In a combination furnace system, combustion chamber means located adjacent the bottom of said furnace for supporting combustible fuel material to be burned, supply means for supplying combustible fuel material to said combustion chamber means, said supply means including compressed air means for carrying and directing combustible fuel material into said combustion chamber means in response to the demand of the furnace system, means for receiving burned fuel and ash for discharge from said furnace system, water source means for introducing distilled water into associated furnace boiler means to produce steam from said distilled water in the system in response to a demand generated by steam demand means connected to said furnace system, and means for generating a work output in response to steam pressure delivered by said furnace system in response to said steam demand means, a pair of spaced down-comer tube means for recirculation of gases and ash generated by said furnace system to said combustion chamber means, said down-comer tube means being located adjacent the furnace system in heat transfer relationship thereto and in part in proximity to said water source means and in heat transfer relation therewith, raw water tank means adjacent one side of and in heat transfer relationship with said

4,292,905

DATA DISPLAY DEVICE FOR SEWING MACHINE ADJUSTMENT AND SET-UP

Hans Widmer, Magglingen, Switzerland, assignor to Fritz Gegauf AG, Bernina-Nachmaschinenfabrik Steckborn, Steckborn, Switzerland



Filed Feb. 29, 1980, Ser. No. 126,158

Claims priority, application Switzerland, Mar. 15, 1979, 2442/79; May 2, 1979, 4084/79

Int. Cl.³ D05B 19/00

U.S. Cl. 112—121.11

15 Claims



1. A device for selecting and displaying optimum conditions for set-up of sewing machine controls and elements, comprising:

an input unit having a plurality of means for manually producing data fully characterizing a material type and any type of sewing operation desired to be performed;

a memory accessed by said data produced by said input unit and in which is stored all optimum sewing machine adjustment values including ranges for performing any selected sewing operation on different materials in addition to accessory data characterizing foot, needle and thread settings; and

means connected to said memory for displaying said optimum sewing machine adjustment values and said accessory data corresponding to said manually produced data, whereby the sewing machine can be fully set-up for optimum operation.

4,292,906

ROTATABLE LOOP TAKER AND BOBBIN CASE ASSEMBLY

Ralph E. Johnson, Convent Station, N.J., assignor to The Singer Company, Stamford, Conn.

Filed Dec. 10, 1979, Ser. No. 102,075


Int. Cl.³ D05B 57/14, 57/26

U.S. Cl. 112—184

9 Claims

1. In a lockstitch sewing machine, a work supporting bed, a loop taker mounted for rotation about a vertical axis in the bed and including a rim with a beak for seizing thread carried by a reciprocating needle, a bobbin case within the loop taker, a bracket affixed in the bed and loosely connected to the bobbin case to constrain the bobbin case rotationally and radially and permit the passage of said thread between the bobbin case and

bracket during the formation of the lockstitches on the machine, the bobbin case being vertically supported at one location on the bracket and at another location on the rim of the



loop taker, the bobbin case being tilted relative to the loop taker by the bracket to limit the area of contact between the bobbin case and looptaker rim.

4,292,907

PRESSER-FOOT APPARATUS


Andrew J. Gilbride, Swampscott, and Francis A. Wickers, Beverly, both of Mass., assignors to USM Corporation, Farmington, Conn.

Filed Jun. 28, 1979, Ser. No. 53,021

Int. Cl.³ D05B 29/00; D05C 9/02

U.S. Cl. 112—236

20 Claims



1. In a sewing machine having at least one reciprocating needle bar, apparatus for maintaining the workpiece in a proper position during sewing, said apparatus comprising: a presser-foot assembly including a presser-foot; means, affixed to said needle bar, for slidably holding said presser-foot assembly; means for biasing said presser-foot assembly initially against said slidably holding means until said presser-foot contacts the workpiece whereupon said biasing means exerts a steady pressure on the workpiece said biasing means being mounted to a stationary point which does not move in conjunction with the movement of said needle bar so as to thereby exert the steady pressure on the workpiece.

4,292,908

HEMMER-SEAMER

Hubert Blessing, Dallas, Tex., assignor to Levi Strauss & Co., San Francisco, Calif.

Filed Oct. 2, 1978, Ser. No. 947,598


Int. Cl.³ D05B 33/00, 35/10, 21/00

U.S. Cl. 112—306

7 Claims

6. Apparatus for seaming together two overlaid workpieces comprising a sewing machine, means acting transversely to the intended seam for guiding the edges of the workpieces independently of each other into a predetermined alignment, opposed, moving belt transport means for clasping the work-

pieces together as they leave the edge guiding means and drawing them in one direction through the sewing machine as it seams them together, means for grasping the trailing edges of the workpieces and for maintaining the workpieces in tension



while the workpieces are drawn by the belt transport means, and a loader carriage for inserting the leading edges of the workpieces into position for engagement with the belt transport means.

4,292,909

SPILL OVERFLOW PREVENTION SYSTEM FOR TANKER VESSELS


Charles S. Conway, Featherbed La., New Vernon, N.J. 07976

Filed Dec. 21, 1979, Ser. No. 106,276

Int. Cl.³ B63B 25/12

U.S. Cl. 114—74 R

9 Claims



1. In a tanker vessel for the transportation of fluid chemical and petroleum products in water, which vessel includes a hull comprising a bottom and sides, a top deck, a plurality of watertight cargo compartments disposed within the hull between the top deck and the hull bottom for receiving the fluid chemical and petroleum products, and means coupled to said cargo compartments for filling said compartments with said fluid chemical and petroleum products, the improvement comprising,

longitudinally disposed trunk line means, branch line means coupled at one end to said trunk line means and at the other end to said cargo compartments, valve means, coupled to said branch line means intermediate the ends thereof, for permitting the free flow of fluid chemical and petroleum products from said cargo compartments to said trunk line means through said branch line means, said branch line means being dimensioned so as to prevent overpressurization of said cargo compartments during the flow of said fluid chemical and petroleum products from said compartments to said trunk line means, retention tank means disposed in said vessel and coupled to said trunk line means for receiving fluid chemical and petroleum products from said trunk line means, vent means for said cargo compartments including bypass line means coupled to said branch line means intermediate the ends thereof and in parallel relationship therewith, and pressure/vacuum relief valve means, coupled to said bypass line means intermediate the ends thereof, whereby fluid chemical and petroleum products overflow from said cargo compartments during filling thereof are directed from said cargo compartments through said

branch line means and said trunk line means to said retention tank means thereby preventing the spillage of said fluid chemical and petroleum products externally of said cargo compartments.

4,292,910

SPINNAKER POST FOR SAILING VESSEL

John G. Hoyt, G.P.O. Box "CN", San Juan, P.R. 00936

Filed Apr. 28, 1980, Ser. No. 144,677

Int. Cl.³ B63H 9/4

U.S. Cl. 114—102

4 Claims



1. In a sailing vessel having a hull with a bow and stern sections, a mast mounted to be supported in a general vertical direction from the hull with a substantial area ahead of the mast, that improvement comprising a rigid post forward of and spaced from the mast rigidly fastened to the vessel and rising to a height above the sheer of the hull, a pole, means rotatably secured to the upper end of the post for releasably holding said pole to permit transverse sliding of the pole relative to the post, a triangular sail having head, tack and clew corners, said pole having fittings at each end thereof to which the tack and clew of said sail and suitable sheets or guys may be attached, said sheets and guys leading aft for trimming said pole and said sail and the head of said sail being supported by said mast.

4,292,911

ROLLER CHOCK

John Lindsay, 16 Harbor St., Manchester, Mass. 01944


Continuation of Ser. No. 879,726, Feb. 21, 1978, abandoned.

This application May 5, 1980, Ser. No. 146,914

Int. Cl.³ B63B 21/08

U.S. Cl. 114—218

1 Claim



1. A roller chock for use with a line on a boat comprising: A. an elongated base portion; B. an arm having a curved generally L-shaped vertical cross-section extending upwardly from said base portion and having a generally vertical portion having a generally linear line-contacting surface skewed with respect to said base portion to align said line-contacting surface with the normal orientation of the line through said chock when the line is in contact with said line-contacting surface, and a horizontal portion having a free end extending rear-

wardly from the top of the vertical portion generally parallel to the baseplate;

C. a stationary vertical shaft having a lower end mounted to the base portion spaced rearwardly from said arm and a free upper end;

D. A roller mounted for bidirectional rotation about said shaft, said roller having a smooth cylindrical line-contacting surface;

E. a plate supported solely by the free end of said shaft above said roller parallel to said base, said plate extending from said shaft laterally of said roller inwardly of the boat and forwardly of said roller toward, but spaced apart from, said free end of said curved arm, and

F. means for inhibiting rotation of said plate around said shaft, whereby said horizontal portion of said curved arm and said plate tend to capture the line passing through said chock, said vertical portion and said roller serving to limit lateral movement of the line.

4,292,912

TRANSFER AND DOCKING APPARATUS FOR USE ON VARIABLE DRAFT MARINE VESSELS


Andrew F. Hunter, Houston, Tex., assignor to Conoco, Inc., Ponca City, Okla.

Filed May 30, 1979, Ser. No. 43,718

Int. Cl.³ B63B 59/02

U.S. Cl. 114—219

14 Claims



11. A boarding and fender apparatus for use in transferring passengers to and from boats which reside at varying levels with respect to a marine structure, the apparatus comprising: at least two sloping fenders;

means for ascending and descending mounted adjacent and parallel to at least one of said two fenders and inboard of said at least one of said two fenders; and

means for fixedly attaching said two fenders and said ascending and descending means to said marine structure so that at least two fenders are presented to a docking boat and passengers from said docking boat may disembark directly from said docking vessel onto said means for ascending and descending.

4,292,913

BOAT RUB RAIL

Lee S. Siebert, Leawood, Kans., and Charles J. Ritsch, Odessa, Mo., assignors to Mark Twain Marine Industries, Inc., West Frankfort, Ill.

Filed Jun. 18, 1979, Ser. No. 49,434

Int. Cl.³ B63B 59/02

U.S. Cl. 114—219

6 Claims


1. A rub rail assembly for a vehicle, which may be employed to secure a device to said rub rail comprising:

a channel member adapted to be secured to the side of said vehicle to provide a channel thereon;

a resilient bumper strip disposed in the channel and projecting outwardly from the plane of said channel member;

a protrusion projecting downwardly from the bottom of said channel member to provide a first coupling member extending substantially continuously along the length of the channel member, said protrusion having a generally rounded exterior surface; and

means for presenting a second coupling member adapted to be complementally joined with said first coupling member and characterized by means for attaching said device, said



second coupling member presenting a channel recess therein substantially complementary to said protrusion to closely embrace the protrusion in a snap fit therewith.

4,292,914


METHOD AND APPARATUS FOR FACILITATING UNDERWATER WORK ON SHIP HULLS AND LIKE OBJECTS

Carldavid Jönsson, S-585, 90 Linköping, Sweden
Filed May 9, 1979, Ser. No. 37,272

Claims priority, application Sweden, May 9, 1978, 7805277
Int. Cl.³ B63B 59/00

U.S. Cl. 114—222

8 Claims



1. An apparatus for facilitating working on especially horizontal underwater portions of ship hulls, pontoons and other floating objects, comprising a screen structure having means for tightly fitting said screen structure against the edges of the surface on which operations are to be carried out, said screen structure projecting downwardly from said surface, said screen structure having a top edge which is sealed against said surface, said screen structure having a bottom which is open for a major portion of the area circumscribed by said screen structure so that said circumscribed area is filled with water, and means for introducing air into the volume associated with said circumscribed area and said screen structure with a pressure adapted to the water pressure prevailing at the actual depth into the volume within said screen structure in order to provide an air volume serving as a work-space under said surface, said pressurized air being essentially the sole means for preventing contact between said water and said surface within said circumscribed area.

4,292,915

OCEAN-GOING BARGE CARRIER

Frank A. Nemec, New Orleans, La., assignor to Lykes Bros. Steamship Co., Inc., New Orleans, La.


Division of Ser. No. 508,631, Oct. 22, 1965, Pat. No. 3,318,276, which is a continuation-in-part of Ser. No. 416,053, Dec. 4, 1964, abandoned. This application Jul. 7, 1966, Ser. No. 574,523
Int. Cl.³ B63B 35/40

U.S. Cl. 114—260

5 Claims

1. In a marine carrier of the type comprising a hull, a plurality of storage decks arranged one above the other and each having at least one loading opening extending through the carrier hull at the level thereof, elevator means fastened to said

hull and capable of submerging, receiving floating barges thereon, and lifting said barges to each respective storage deck level at the loading opening on said deck, means at said open-



ing on each of said decks for engaging and positioning said barges, and support means for said barges on each of said decks over which they may be easily re-positioned.

4,292,916

TIMER AND STORAGE CONDITION INDICATOR


Robert F. Bradley, and Lindell P. Bradley, both of New Buffalo, Mich., assignors to Micro-Circuits Company, New Buffalo, Mich.

Filed Jun. 18, 1979, Ser. No. 49,082

Int. Cl.³ G01K 01/02; G04F 01/00; G01N 31/22

U.S. Cl. 116—205

12 Claims



1. A device for indicating time lapse alone or time lapse integrated with various ambient physical environmental conditions: said device comprising a first layer to be placed on the article to be timed when timing is to begin, a carrier mixture contained in said first layer, a transfer layer of substantially the same size as said first layer adapted to accept said carrier mixture within various elapsed time limits, said transfer layer being initially separate and remote from said first layer and placed in contact with said first layer when the timing and integration are to begin, a component in said device responsive to one or more of the ambient physical conditions and said time limits varying as at least one of the ambient physical conditions varies, a means of notification of progress of said carrier mixture in said transfer layer, a cover layer larger than said first layer and said transfer layer for enclosing the top and sides of said layers against the article to be timed, said cover layer being initially separate and remote from said first and transfer layers and placed over said layers when the timing and integration are to begin, and an adhesive layer on said cover layer to seal said layers to the article when said device is assembled.

4,292,917

PASTRY TOPPING DEPOSITING MACHINE

Norio Ezaki, 2-7-33, Kohama-nishi Suminoe-ku, Osaka, Japan

Filed Apr. 8, 1980, Ser. No. 138,563

Claims priority, application Japan, Nov. 1, 1979, 54-142538


Int. Cl.³ B05C 5/02

U.S. Cl. 118—16

9 Claims

1. In a machine for automatically dispensing pastry topping materials to the top surfaces of successive articles of cake or pastry comprising nozzle means for intermittently depositing portions of pastry topping material, pastry supporting means for supporting cakes underneath said nozzle means to deposit successive portions of said topping material on said cakes, said pastry supporting means including first support means for

depositing topping on cakes in a circular pattern and also including second support means for conveying successive pastries underneath said nozzle means to deposit successive portions of said topping material on successive pastries, said first support means including vertically movable and selectively rotatable cake supporting plate means and said second support means including pastry supporting endless conveyor



means, and shaft means selectively coacting with said cake supporting plate means for controlling the vertical distance between a cake and the nozzle means and for rotating the cake under the nozzle means, said shaft means selectively coacting alternatively with said endless conveyor means to control the distance between the nozzle means and successive pastries positioned under the nozzle means.

4,292,918

APPARATUS FOR APPLYING LIQUID CHEMICALS TO A MOVING WEB


Gayron N. Davis, Opelika; Larry S. Sellers, Shawmut, both of Ala., and Winston E. Hagborg, Columbus, Ga., assignors to West Point Pepperell, Inc., West Point, Ga.

Continuation-in-part of Ser. No. 110,454, Jan. 8, 1980, abandoned. This application Jul. 22, 1980, Ser. No. 171,826

Int. Cl.³ B05C 3/18

U.S. Cl. 118—33

14 Claims



1. Apparatus for applying a liquid chemical to a movable web, comprising:

a manifold for receiving and discharging said chemical, said manifold including a pipe to receive said chemical, said pipe being provided with a plurality of spaced orifices located along its length for discharging the chemical;
a length of porous material positioned along said manifold adjacent the orifices for receiving and dissipating the jets of chemical discharged by the manifold;
a fixed member engaging said porous material and having a curved surface terminating in a straight edge, said member being oriented with respect to the porous member such that the chemical is transferred to the member from the porous material, said chemical moving under the force of gravity as a thin film along said curved surface to said edge; and
means for tensioning the web against said edge and for moving the web with respect to the fixed member whereby said chemical is applied to the web.

NON-METALLIC PASTE SECTORS AND METHODS OF FABRICATING AND UTILIZING SAME


Walter C. Taylor, 60690 Nine Mile Rd., South Lyon, Mich. 48178

Filed Sep. 24, 1979, Ser. No. 78,466

Int. Cl.³ B05C 1/00; B41F 13/10, 27/06; B32B 27/00

U.S. Cl. 118—212

7 Claims



1. A paste sector for mounting to a paste sector shaft of a bag making machine so as to apply paste to the open bottom of a bag being manufactured, said paste sector comprising:

a main body including a central non-pasting upper surface portion having a raised upper surface portion extending integrally upwardly therefrom along at least opposite end portions of said central upper surface portion for applying paste in a predetermined pattern to the open bottom of a bag being manufactured;

said main body including a lower surface which is concave and is curved so as to be directly closely fitted against a curved mounting surface portion of said paste sector shaft; said main body having a generally arcuate cross-sectional configuration;

said main body being substantially impermeable;

said main body including integral opposite end fastening portions for mounting said paste sector to said paste sector shaft; and

said main body of said paste sector, including said raised upper surface portion, said non-pasting upper surface portion and said end fastening portions being integrally injection molded from a substantially resilient non-metallic material comprising a rubber-like urethane material.

4,292,920

MAGNETIC ATTRACTION TRANSFER DEVICES FOR USE IN SOLID PHASE RADIOIMMUNOASSAYS AND IN OTHER ASSAY METHODS


Kendall O. Smith, 133 Trillium Ln., San Antonio, Tex. 78312, and Warren D. Gehle, 6815 Forest Haven, San Antonio, Tex. 78240

Division of Ser. No. 680,506, Apr. 26, 1976, abandoned. This application Dec. 20, 1979, Ser. No. 105,707

Int. Cl.³ B05C 3/00

U.S. Cl. 118—425

12 Claims



1. A device for use in solid phase immunoassays, for simultaneously transferring a plurality of antigen-antibody absorbent

units from one location to another, comprising a transfer element in combination with a tray of non-magnetic material having a plurality of spaced receptacles therein for containing an appropriate liquid and for containing units each comprising a core of ferromagnetic material, each said core being covered with at least one coating for preventing chemical interactions between said core and aqueous chemical solutions and for absorbing antigens or antibodies on the outer surface thereof, said transfer element having a first portion of ferromagnetic material overlying said spaced receptacles in a transfer condition of said element, and said element having a second portion of non-magnetic material overlying spaces between said receptacles when in said transfer condition, and one of said ferromagnetic core and transfer device materials having magnetic properties to effect a magnetic attraction between said units and said transfer device, whereby said units are removable from said receptacles by magnetic attraction while being maintained in spaced apart relationship by said non-magnetic material during said transfer condition.

4,292,921


ELECTROGRAPHIC DEVELOPMENT APPARATUS

Arthur S. Kroll, Spencerport, and Frank A. Shuster, Rochester, both of N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.

Filed Apr. 4, 1979, Ser. No. 27,115
Int. Cl.³ G03G 15/06

U.S. Cl. 118—648

17 Claims



1. In electrographic apparatus of the type constructed to move an electrostatic-image-bearing member in a first direction through a development zone at a predetermined absolute velocity, an improved developing device comprising:

- (a) first applicator means for transporting successive quantities of partially-conductive developer, at a predetermined transport rate, through one portion of said development zone in transfer relation with said member and in a direction generally opposite said first direction;
- (b) second applicator means for transporting successive quantities of partially-conductive developer, at a predetermined transport rate, through another portion of said development zone in transfer relation with said member and in a direction generally the same as said first direction; and
- (c) electrode means spaced opposite said development zone for electrically coupling each of such quantities of developer to reference potential while in transfer relation with said member;


at least one of: (1) the relative transport rate of said first and second applicator means and (2) the reference potential of said electrode means, being predeterminedly constructed to balance development of leading and trailing edge portions of solid-area electrostatic images.

4,292,922
DEVELOPING DEVICE FOR AN ELECTROPHOTOGRAPHIC COPYING MACHINE
Yoshio Yamazaki, Nin-ichi Kamogawa, and Yasuyuki Iwai, all of Hachioji, Japan, assignors to Konishiroku Photo Industry Co., Ltd., Tokyo, Japan

Filed Feb. 19, 1980, Ser. No. 122,769
Claims priority, application Japan, Feb. 24, 1979, 54-21101
Int. Cl.³ G03G 15/09

U.S. Cl. 118—657

10 Claims



1. In a magnetic brush type developing device for single component developer and including a casing, an axially elongated sleeve of a non-magnetic material in the casing, and a plurality of magnets disposed in the sleeve for relative rotation therebetween so as to form a layer of developer adhering to the peripheral surface of the sleeve, the improvement comprising: a regulating plate extending axially along and substantially adjacent the sleeve surface for regulating the height of the layer of developer adhering thereto; and a pair of partition plates, each arranged substantially perpendicular to the sleeve axis and predeterminedly adjacent a circumferentially-disposed portion of the sleeve surface proximate one of the axially opposite ends of the sleeve for preventing axial flow of developer along the sleeve beyond said partition plates.

4,292,923


DEVELOPMENT SYSTEM

Raymond W. Huggins, Pittsford, N.Y., assignor to Xerox Corporation, Stamford, Conn.

Filed Jul. 16, 1979, Ser. No. 57,868
Int. Cl.³ G03G 13/09

U.S. Cl. 118—658

16 Claims



1. An apparatus for developing image areas of a surface having image areas and background areas recorded thereon with the electrical potential of the image areas being greater than the electrical potential of the background areas, including: a tubular member made from a resistive material having conductive particles dispersed substantially uniformly therethrough, said tubular member being positioned adjacent the surface to define a development zone for transporting particles into contact with the surface; a magnetic member disposed interiorly of said tubular member;

a pair of voltage sources for supplying different fixed voltages; and
a pair of second conductors, having no other conductors interposed therebetween one of said conductors being positioned prior to the development zone with the other of said conductors being positioned after the development zone, each of said pair of conductors having one end region thereof slidably engaging said tubular member with the other end region thereof being connected to one of said pair of voltage sources to electrically bias said tubular member so that the electrical potential thereof, in the development zone, varies substantially continuously from a level substantially equal to the electrical potential of the background areas to a level greater than the electrical potential of the background areas so that particles deposited on the surface adhere to the image areas with the background areas being substantially particle free.

4,292,924


MAGNETIC BRUSH APPARATUS

Nero R. Lindblad, Palmyra; Ivan Rezanka, Pittsford, and John V. Cassidy, Rochester, all of N.Y., assignors to Xerox Corporation, Stamford, Conn.

Filed Oct. 3, 1979, Ser. No. 81,411
Int. Cl.³ G03G 15/09

U.S. Cl. 118—658

9 Claims



1. A magnetic brush apparatus for use in an electrostatic printing machine, including:
a tubular member journaled for rotation about the longitudinal axis thereof;
a magnetic member mounted stationarily and interiorly of said tubular member, said magnetic member generating a radial magnetic field extending outwardly therefrom in a direction substantially normal to the longitudinal axis of said tubular member and an axial magnetic field extending outwardly from opposed ends of said magnetic member in a direction substantially parallel to the longitudinal axis of said tubular member; and
means, positioned radially interiorly of said tubular member in the region of opposed ends of said magnetic member and cooperating therewith, for substantially suppressing the axial magnetic field.

4,292,925

TONER CONCENTRATION DETECTING APPARATUS

Isamu Terashima, Ibaraki, Japan, assignor to Hitachi, Ltd., Tokyo, Japan

Filed Oct. 12, 1979, Ser. No. 84,455
Claims priority, application Japan, Oct. 18, 1978, 53-127381


Int. Cl.³ G03G 15/09

U.S. Cl. 118—690

18 Claims

1. An apparatus for detecting a toner concentration of developing powder comprising:
a chamber for storing the developing powder therein;
means for transporting the developing powder to a photo-sensitive member to develop a latent image;

a hollow body having an inlet and outlet for passage of developing powder through said hollow body;
means for diverting a portion of the developing powder from said transporting means and directing the diverted portion of the developing powder to said hollow body;



detecting means for detecting the toner concentration of the developing powder within said hollow body and for detecting whether the developing powder is passing through said hollow body.

4,292,926

METHOD FOR THE AUTOMATIC FINISH MILKING DURING A MECHANICAL MILK REMOVAL PROCEDURE


Hoefelmayer Tilman, Niederteufen, Switzerland, assignor to Bio-Melktechnik Swiss Hoefelmayer & Co., Niederteufen, Switzerland

Filed Oct. 5, 1979, Ser. No. 82,202
Claims priority, application Fed. Rep. of Germany, Oct. 12, 1978, 2844562

Int. Cl.³ A01J 5/04

U.S. Cl. 119—14.02

7 Claims



1. In a method for the automatic finish milking during a mechanical milk removal procedure, in which the teat which is introduced into an elastic teat rubber of the milking cup is exposed to a predetermined underpressure, a pulsating underpressure is applied to a space between a milking cup housing and the teat rubber which encloses the teat, a continuous milk flow measurement is carried out and the milking intensity is reduced dependent on the result of the measurement, the improvement comprising wherein the continuous measurement detects the change of the milk flow per unit of time and the reduction of the milking intensity occurs directly after a reduction of the milk flow rate of more than 1 kg/min², which reduction was determined during a period of time of five to ten seconds.


4,292,927

SWINE SHELTER VENTILATING SYSTEM

Stanley W. Sassmann, Denver, Iowa, assignor to Farmstead Industries, Div. of Farmhand, Inc., Waterloo, Iowa
Filed Jun. 1, 1979, Ser. No. 44,378
Int. Cl.³ A01K 1/00; F24F 7/06

U.S. Cl. 119—16

6 Claims



1. A ventilation system for a swine shelter house having an interior space defined by a roof, first, second, third, and fourth sidewalls, the first and third sidewalls being disposed opposite to each other, and a manure pit; a slotted floor being disposed above the manure pit, said ventilation system comprising:

- a first air inlet means disposed approximately at the juncture of the first sidewall and the roof, for permitting air flow from the outside atmosphere into the interior space;
- a second air inlet means disposed in a lower portion of the first sidewall, for permitting flow of outside atmospheric air into the interior space;
- a first air exhaust means formed in the third sidewall above the level of the slotted floor, for permitting air flow into the outside atmosphere from only the interior air space within the manure pit below the floor;
- a second air exhaust means, formed in the upper portion of the third sidewall, for permitting air flow from the interior space into the outside atmosphere; said system being operable in a winter mode and a summer mode; said winter mode comprising a winter ventilation system wherein said first air inlet means is open and said second air inlet means is closed, and said first air exhaust means is open and said second air exhaust means is closed; said summer mode comprising a summer ventilation system wherein said first air inlet means is closed and said second air inlet means is open, and said first air exhaust means and said second air exhaust means are open; and only said first air exhaust means employs powered ventilation in the form of an exhaust fan disposed in said third sidewall to draw outside air through said first sidewall across said house into said manure pit and thru said third sidewall via a vent chamber which extends from said slotted floor and surrounds said exhaust fan.

4,292,928

POULTRY BROODING PLANT


Alexei A. Kopylov, ulitsa Lenina, 9/11, kv. 18; Valentin T. Kuzmenko, B. Bulvarnaya ulitsa, 8, kv. 29; Alexandr N. Stepanov, pereulok Turgenevsky, 23; Viktor P. Gaschenko, B. Prospekt, 46, kv. 45, all of, Taganrog; Nikolai A. Kaznacheevsky, ulitsa imeni Grecheskogo goroda Volos, 25/98, kv. 18, Rostov-na-Donu; Alexandr Y. Nosovitsky, ulitsa Pushkinskaya, 38, kv. 4, Rostov-na-Donu; Ivan I. Misikov, ulitsa Pushkinskaya, 181, kv. 18, Rostov-na-Donu; Alexandr I. Shapiro, ulitsa imeni Grecheskogo goroda Volos, 25/98, kv. 38, Rostov-na-Donu; Ivan G. Skakunov, ulitsa B. Cherkizovskaya, 8, kv. 10, Moscow; Valentin G. Markin, prospekt Kommunisticheskoy, 38/2, kv. 16, Rostov-na-Donu; Alexei K. Konstantinov, ulitsa Svobody 15 kv. 86, Taganrog; Eduard S. Abramian, ulitsa B. Cherkizovskaya, 9a, kv. 11, Moscow; Arseny M. Soroka, ulitsa Gerasima Kurina, 42, kv. 33, Moscow, and Yakov A. Zinchenko, ulitsa 2 Krasnodarskaya, 70/1, kv. 10, Rostov-na-Donu, all of U.S.S.R.

Filed Nov. 19, 1979, Ser. No. 95,389

Int. Cl.³ A01K 31/06

U.S. Cl. 119—17

12 Claims



1. A self-contained automated poultry brooding plant, comprising:

- a plurality of multilevel container cages with means for housing and rearing poultry from chicks until the end of the poultry growing period;
- said cages being rotatably mounted on a horizontal frame which is affixed to a conveyer system with means for automatically advancing the cages at a rate of movement in accordance with established poultry growth patterns;
- said cages having doors which open when the cage is horizontally rotated through a predetermined angle;
- said cages having means which engage with a bell crank located near the conveyer system at a location corresponding to the end of the poultry growing period, whereby the engagement of the cage with the bell crank serves to horizontally rotate the cage at the end of the poultry growing period to said predetermined angle which automatically opens the cage door and unloads the pountry.

4,292,929

CALF INCUBATOR


Donald W. Tellers, R.R. 2, Chaska, Minn. 55318
Filed Dec. 28, 1979, Ser. No. 108,238
Int. Cl.³ A01K 1/02, 5/01, 9/00

U.S. Cl. 119—27

14 Claims

- 1. An incubator particularly for calves and the like comprising:
 - a wheel supported box-like structure consisting of a single pen structure for a single calf or the like and having front, rear, top, bottom and opposing side walls, at least one of said front and rear walls including a door to permit place-

ment of the calf into, and removal of the calf from, the incubator and at least the front, rear, bottom and side walls constructed of an insulative material to substantially reduce drafts of air into the incubator; a heat source disposed in said top wall for providing heat to the interior of the incubator;



an opening in said front wall sufficiently large to permit the calf to poke its head through for eating purposes; and a pail support assembly for supporting a feeding pail proximate said opening.

4,292,930


HORSE-FEEDING APPARATUS

Edward C. Olsen, 1109 S. 17th St., Escanaba, Mich. 49829
Continuation-in-part of Ser. No. 818,736, Jul. 25, 1977, Pat. No. 4,183,327. This application Oct. 4, 1979, Ser. No. 81,863

Int. Cl.³ A01K 5/02

U.S. Cl. 119—51.11

7 Claims



1. A system for automatically dispensing horse feed comprising:

- a feed storage chamber having side surfaces which converge toward a lower aperture to channel feed to said aperture;
- feed transfer means including a substantially closed cylindrical housing aligned below said storage chamber, said housing having an upper surface with an inlet opening disposed below the aperture of said storage chamber, a lower surface having an outlet opening, and an impeller blade spanning the diameter of said cylindrical housing, said inlet and outlet openings being in non-overlapping segments of said upper and lower surfaces;
- a drive mechanism including a drive shaft coupled to said impeller blade to cause a continuous flow of feed from said storage chamber through said transfer means to said outlet opening during operation of said drive shaft;
- means driven by said impeller blade for agitating the feed within said storage chamber to facilitate feed flow near the lower aperture thereof, said agitating means comprising:

ing a freely turning base having a plurality of radial extensions adapted to sweep across an interior surface of the hopper in close proximity thereto; and means for channeling feed from said outlet opening to a feed area.

4,292,931


METHOD AND MEANS FOR HOLDING A SHEEP

Donald L. Hopkins, Heywood, Australia, assignor to Alf Hanford & Co. Pty. Ltd., Beverley, Australia
Filed Mar. 6, 1980, Ser. No. 127,756

Claims priority, application Australia, Mar. 7, 1979, PD7941
Int. Cl.³ A61D 3/00; A01K 15/00

U.S. Cl. 119—103

6 Claims



1. Apparatus for handling of sheep including the restraining of sheep for purposes such as shearing including a frame, a table positioned on said frame and adapted to support a sheep in a first instance on its back and subsequently in a position where the sheep is rolled over to its side while still being supported by the table and finally being fully supported in an upright position to a side of the table, an open ended yoke means adapted when the sheep is on the table on its back to push the rear legs jointly of the sheep while on its back at a location at the upper position of the legs forwardly into its body to such an extent as to restrain its movements while at such position, said yoke means being on said frame adjacent an end of said table, being spaced from said table in its normal inoperative position, and being open at its portion closest to said table, and means located at a side of the table and movably positioned to be adapted to engage jointly both front the rear legs at or about the upper end and hold these by engagement close to the body of the sheep and adapted so that the sheep while being maintained in the condition of having its legs held, can nonetheless be turned over so as to be upright although restrained by its holding of the legs.

4,292,932

VEHICULAR PET ANCHOR

Charles R. Wooderson, 5572 Baronridge, #5, Mehlville, Mo. 63129

Filed Dec. 13, 1979, Ser. No. 103,060

Int. Cl.³ A01K 27/00


U.S. Cl. 119—109

4 Claims

1. In combination with a vehicle, said vehicle having a body within which is located an openable door, a pet tether connectable with said vehicle, said pet tether comprising:

- an elongated, thin, integral, flexible member having an outer end and an inner end connected together by a middle section, said middle section being sufficiently thin to be locatable between said openable door and said body with said openable door closed and not hinder the opening and closing movement of said openable door, removal of said member from said openable door to occur upon opening of said openable door, said outer end having a substantially greater thickness than said middle section, whereby said outer end prevents disassociation of said member

from said openable door when said openable door is closed;
an attaching opening formed within said inner end, said inner end being substantially thicker than said middle section, the thickness of said inner end being for the purpose of providing extra strength about said attaching opening; and
attaching means connected to said attaching opening, said attaching means for connecting to a pet to restrict the movement of the pet defined by the length of said attaching means.




pose of providing extra strength about said attaching opening; and
attaching means connected to said attaching opening, said attaching means for connecting to a pet to restrict the movement of the pet defined by the length of said attaching means.

4,292,933
FURNACE

Daniel Meier, and Carl Maendel, both of Rifton, N.Y., assignors to Hutterian Society of Brothers, Rifton, N.Y.
Filed Nov. 8, 1979, Ser. No. 92,550
Int. Cl.³ F22B 9/02

U.S. Cl. 122-114

7 Claims



1. A furnace for burning solid fuel in the presence of air whereby products of combustion are produced, said furnace comprising:

- a fire-box compartment being rectangularly-shaped with four vertical walls, three of said four vertical walls being double walls to form a liquid chamber, said fire-box compartment having a means for supplying air into the fire-box compartment and for preheating the air so supplied, said fire-box compartment further including an opening for supplying solid fuel into the fire-box compartment;
- a lid pivotably mounted on said fire-box compartment over the opening in the fire-box compartment for sealing the opening in said fire-box compartment for supplying solid fuel into the fire-box compartment;
- a heat-exchanger compartment having a top and a bottom, said heat-exchanger compartment including a liquid container with a series of fire-tubes vertically oriented through the liquid container, the liquid container being located below the top of the heat-exchanger compartment to form an upper flue gas passage over the liquid container, said heat-exchanger compartment further including a lower flue gas passageway beneath said liquid container; and
a baffle located in said lower flue gas passageway of said


heat-exchanger compartment, said baffle having a damper pivotably mounted in it;
a means located partially outside said heat-exchanger compartment for pivoting said damper to open and close said damper;
a channel connecting the fire-box compartment with the lower flue gas passageway in the heat-exchanger compartment to supply products of combustion from the fire-box compartment to the heat exchanger compartment, said lower heat-exchanger compartment having a flue gas exit for discharging the products of combustion, said flue gas exit being located in said lower flue gas passageway opposite from said channel, said baffle being located substantially midway between the channel and the flue gas exit;
a secondary air inlet located in said channel for supplying additional air to the products of combustion in the channel for further combustion; and
means for supplying and removing liquid from said liquid chamber and said liquid container.

4,292,934

STARTING AIDS FOR INTERNAL COMBUSTION ENGINES

Richard P. Knowles, Farnborough, England, assignor to Lucas Industries Limited, Birmingham, England
Filed Oct. 18, 1976, Ser. No. 733,366
Claims priority, application United Kingdom, Oct. 24, 1975, 43736/75
Int. Cl.³ F02P 19/02; F02B 9/08
U.S. Cl. 123-145 A

11 Claims



1. A starting aid for a diesel engine the aid being of the kind which in use is mounted within the cylinder head of an engine so that the heated portion of the aid is exposed within a combustion space of the engine, the aid comprising a spirally coiled heating element formed from conductive tape which is located within and at the end of a tubular member, the outer end of the heating element being electrically connected to the tubular member, the inner end of the heating element being electrically connected to a conductive rod extending within the tubular member, and a length of tape connected to the outer end of the heating element extends in a direction transversely to the plane of the heating element, said length of tape being secured at or adjacent its free end to the tubular member or body of the aid at a position removed from the heating element.

4,292,935

LOW NITROUS OXIDE (NOX) PRECOMBUSTOR


William R. Wagner, Los Angeles, Calif., assignor to Rockwell International Corporation, El Segundo, Calif.
Filed Mar. 31, 1980, Ser. No. 136,140
Int. Cl.³ F02B 19/14

U.S. Cl. 123-285

5 Claims

1. A precombustor for use in diesel engines, wherein the improvement comprises defining the internal geometry of the

precombustion chamber in accordance with the following equation:



$$\left(\frac{dT}{T}\right) = \frac{(\gamma - 1)M^2}{1 - M^2} \left(\frac{dA}{A}\right) + \frac{(1 - \gamma M^2) \left(1 + \frac{\gamma - 1}{2} M^2\right)}{(1 - M^2)} \left(\frac{dT_o}{T_o}\right)$$

where T is static temperature, A is area of precombustion chamber, γ is ratio of specific heats, and M is mach number of the gas flow.


4,292,936

ALUMINUM BASED ALLOY PISTONS FOR INTERNAL COMBUSTION ENGINES

Tuyoshi Morishita; Kenji Miyake, and Kouji Tobita, all of Hiroshima, Japan, assignors to Toyo Kogyo Co., Ltd., Hiroshima, Japan
Filed May 15, 1979, Ser. No. 39,289
Claims priority, application Japan, May 16, 1978, 53-58367
Int. Cl.³ F02F 3/04

U.S. Cl. 123-193 P

9 Claims




1. A piston for internal combustion engines including a crown and peripheral wall, said piston being formed at the peripheral wall with a plurality of piston ring grooves including a top ring groove which is located closest to the crown among the piston ring grooves, insert means being casted in the piston to define at least partly at least said top ring groove, said insert means being made of a sintered particulate homogeneous alloy comprising in weight 8 to 25% of Ni, 4.5 to 7.5% of Cu, less than 2% of C and the balance substantially of Fe and having a density of 5.5 to 6.8 g/cm³ and a coefficient of thermal expansion of 17 to 23 $\times 10^{-6}$ cm³/°C.cm, and total amount of Ni and Cu being not less than 15% in weight.

4,292,937

PISTON FOR INTERNAL COMBUSTION ENGINES

Jean-Pierre Vallade, Orsay, France, assignor to Regie Nationale des Usines Renault, Boulogne Billancourt, France
Filed Sep. 18, 1979, Ser. No. 76,598
Claims priority, application France, Sep. 22, 1978, 78 27173
Int. Cl.³ F02F 3/24; F16J 1/00
U.S. Cl. 123-193 P

2 Claims



1. In a piston assembly having a piston crown, a side portion with grooves formed therein for receiving sealing piston rings, and at least one recessed portion in the piston crown, the improvement comprising means for reducing heat diffusion from the piston crown to the side portion, said means for reducing comprising:

- an internal partially circular groove formed in the piston assembly for reducing the thickness of a portion of the piston assembly connecting the piston crown and side portion, said internal partially circular groove having an interrupted portion adjacent said at least one recessed portion; and
- an external cut tangentially formed in the side portion above the grooves, said cut being positioned adjacent said interrupted portion whereby the at least one recessed portion in the piston crown in combination with the internal groove does not excessively reduce the thickness of the connecting portion.


4,292,938

INTERNAL COMBUSTION ENGINE

Toshiaki Tanaka, Fujisawa, and Yukihiko Etoh, Yokohama, both of Japan, assignors to Nissan Motor Company, Limited, Yokohama, Japan
Filed Dec. 6, 1979, Ser. No. 100,747
Claims priority, application Japan, Dec. 8, 1978, 53-169278
Int. Cl.³ F02D 17/03; F02M 25/06

U.S. Cl. 123-198 F

8 Claims



1. An internal combustion engine comprising:

- (a) a plurality of cylinders split into first and second groups;
- (b) an intake passage provided therein with a throttle valve and divided downstream of said throttle valve into first and second branches, said first branch communicating with said first group of cylinders, said second branch communicating with said second group of cylinders;
- (c) an exhaust passage;

- (d) first valve means provided in said second branch for opening and closing the same;
- (e) an EGR passage having its one end opening into said second branch and the other end opening into said exhaust passage for recirculation of a portion of exhaust gases thereinto;
- (f) second valve means provided in said EGR passage for opening and closing the same;
- (g) a fuel injection control unit for providing, in synchronism with rotation of said engine, a drive pulse signal having its pulse width varying as a function of intake air flow rate;
- (h) first and second fuel supply means responsive to the drive pulse signal for supplying fuel into said first and second groups of cylinders, respectively;
- (i) a load detector responsive to engine load conditions for allowing application of the drive pulse signal to said first and second fuel supply means and providing a first control signal under high load conditions, and for allowing application of the drive pulse signal to said first fuel supply means but stopping application of the drive pulse signal to said second fuel supply means and providing a second control signal under low load conditions;
- (j) first valve control means responsive to the first control signal from said load detector for opening said first valve means but holding said first valve means closed as long as the pressure in said second branch is substantially higher than the pressure in said first branch, said first valve control means responsive to the second control signal therefrom for closing said first valve means; and
- (k) second valve control means responsive to the first control signal from said load detector for closing said second valve means and responsive to the second control signal for opening said second valve means.

4,292,939


FAIL SAFE DEVICES FOR USE WITH DEVICES FOR LIMITING THE SPEED OF REVOLUTION OF AN INTERNAL COMBUSTION ENGINE

John P. Coates, London, England, and David H. Lewis, Swansea, Wales, assignors to Lumenition Limited, London, England

Filed Dec. 13, 1979, Ser. No. 102,907
Int. Cl.³ F02P 9/00

U.S. Cl. 123—335

10 Claims



1. A fail-safe device for isolating an electronic revolution limiter associated with an electronic ignition system for an internal combustion engine including a spark ignition coil, the revolution limiter being of the type having an output stage including a semiconductor breakdown device in series with a semiconductor switch for connection in parallel with an output stage of the electronic ignition system, wherein the semiconductor switch is rendered conductive at engine speeds above a predetermined limiting speed to prevent the generation of ignition pulses by limiting the voltage applied to operate the ignition coil; the fail-safe device comprising detecting means arranged to be coupled to the output stage of the revolution limiter for detecting if the semiconductor switch is conductive such as to prevent the generation of ignition pulses at an engine

speed lower than the predetermined limiting speed thus indicating that a fault has developed in the revolution limiter, and for providing a corresponding detecting signal containing pulses at a rate proportional to the engine speed; and interrupt means coupled to said detecting means and arranged to be connected to the revolution limiter for isolating the revolution limiter from the electronic ignition system in accordance with said detecting signal.

4,292,940

APPARATUS FOR CONTROLLING THE QUANTITY OF FUEL DELIVERY TO AN ENGINE AND ENGINE TIMING

John M. Bailey, Dunlap, Ill., assignor to Caterpillar Tractor Co., Peoria, Ill.


PCT No. PCT/US79/00657, § 371 Date Aug. 27, 1979, § 102(e)
Date Aug. 27, 1979

PCT Filed Aug. 27, 1979, Ser. No. 99,140

Int. Cl.³ F02D 7/00

U.S. Cl. 123—387

17 Claims



1. Apparatus (10) for controlling the quantity of fuel delivery to an engine in response to engine operating conditions, comprising:

- (a) first means (16, 22, 32, 34, 38) for controlling the maximum quantity of fuel delivery to the engine in response to engine load;
- (b) second means (16, 40, 70) for controlling the maximum quantity of fuel delivery to the engine in response to engine speed; and
- (c) wherein said first controlling means (16, 22, 32, 34, 38) and said second controlling means (16, 40, 70) include a control rod (16) having a control surface (25) of predetermined shape defining various axial rod lengths, said control rod (16) being rotatable to any one of a plurality of positions in response to engine speed and being axially movable in response to engine load and in dependence on the rotatable position of said control rod (16).

4,292,941

ELECTRONIC IGNITION CONTROL SYSTEMS

Seigo Suzuki, Yokohama, Japan, assignor to Tokyo Shibaura Electric Co., Ltd., Japan

Continuation of Ser. No. 876,176, Feb. 8, 1978, abandoned. This application Aug. 8, 1980, Ser. No. 176,292

Claims priority, application Japan, Feb. 8, 1977, 52-12833


Int. Cl.³ F02P 5/04

U.S. Cl. 123—416

5 Claims

1. An electronic ignition control system for an internal combustion engine comprising:
- timing pulse means for generating a plurality of timing pulse signals the interval between successive ones of said pulse signals corresponding to each of successive rotations of said engine;
- clock means for generating a plurality of clock pulses proportional to actual time;
- counting means connected to said timing pulse means and

- said clock means for measuring the number of said clock pulses between successive ones of said timing pulse signals, said number representing the actual speed of rotation of said engine for the preceding revolution thereof, said counting means including means for storing said measured number;
- a read-only memory containing a plurality of constants corresponding to the differences between the time a spark is generated in a cylinder of said engine and the time at which the flame generated by that spark has been propagated throughout the cylinder, each of said constants being correlated with a predetermined range in the speed of rotation of said engine;
- calculating means for reading out one of said constants from said memory corresponding to the measured number stored in said counting means at a given time, and calculat-



- ing from said measured number and said correlated constant, a value representing the time at which the next succeeding spark should be generated in a cylinder of said engine;
- latch means connected to said calculating means for temporarily storing said value;
- comparator means connected to said latch means and said counting means for comparing the number of said clock pulses occurring since the last of said timing pulse signals with the value in said latch means, and for producing a coincidence pulse when the number of clock pulses and the value coincide; and
- buffer means connected to said comparator means and responsive to receipt of said coincidence pulse for generating an output signal to create a spark in a cylinder of said engine.

4,292,942

IGNITION SYSTEM FOR INTERNAL COMBUSTION ENGINES

Hiroshi Katada, Katsuta, and Yoshito Kyogoku, Mito, both of Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed Jan. 4, 1980, Ser. No. 109,506

Claims priority, application Japan, Jan. 10, 1979, 54-681

Int. Cl.³ F02P 5/08

U.S. Cl. 123—418

4 Claims



a comparator circuit which produces said ignition signal when the output level of said adder means coincides with the output level of said second integrating circuit, said second integrating circuit including a constant current source, a first switching element and a capacitor connected in series with said constant current source, an output terminal connected to a junction of said first switching element and said capacitor, and a second switching element connected in parallel with said capacitor, wherein said constant current source starts charging said capacitor when said first switching element is rendered conductive by an output of said minimum advance angular position detecting means, the charging to said capacitor is stopped when said first switching element is rendered non-conductive by an output of said maximum advance angular position detecting means, and said capacitor is discharged when said second switching element is rendered conductive by the output of said minimum advance angular position detecting means, whereby said second triangular wave form is delivered out from said output terminal.

4,292,944

INTAKE CONTROL SYSTEM FOR INTERNAL COMBUSTION ENGINE

Hirimitsu Matsumoto, Haamatsu; Keiichi Sugiyama, Shizuoka, and Kazuo Uchiyama, Hamamatsu, all of Japan, assignors to Yamaha Hatsukoki Kabushiki Kaisha, Iwata, Japan


Filed Feb. 7, 1980, Ser. No. 119,211

Claims priority, application Japan, Feb. 8, 1979, 54-14066

Int. Cl.³ F02M 13/06

U.S. Cl. 123-432

7 Claims



1. In an induction system for an internal combustion engine having a chamber of variable volume in which combustion occurs, main induction passage for delivering a charge to said chamber, an auxiliary induction passage for delivering a charge to said chamber, said auxiliary induction passage having a substantially lesser effective cross-sectional area than said main induction passage so that a given mass flow of charge delivered to said chamber through said auxiliary induction passage will enter said chamber at a significantly greater velocity, valve means for controlling the ratio of communication between said induction passages and said chamber during a given cycle of operation, said valve means being effective to direct substantially all of the idle charge flow to said chamber through said auxiliary induction passage, said valve means comprising at least a butterfly type throttle valve for controlling the flow through said main induction passage, the improvement comprising a relief formed in said butterfly type throttle valve formed at a location spaced above its lower peripheral edge for reducing the velocity of the charge entering said chamber through said auxiliary induction passage when said engine is operating at its idle condition, said relief being oriented so that the charge flowing therethrough when said butterfly type throttle valve is substantially closed will

intersect the charge introduced to said chamber through said auxiliary induction passage to increase the turbulence in said chamber.

4,292,945

FUEL INJECTION APPARATUS AND SYSTEM


Norbert W. Kiesling, Mount Clemens, Mich., assignor to Colt Industries Operating Corp., New York, N.Y.

Filed May 2, 1980, Ser. No. 146,135

Int. Cl.³ F02B 33/00

U.S. Cl. 123-438

4 Claims



1. Fuel metering apparatus for supplying metered rates of fuel flow to a combustion engine, comprising body means, induction passage means formed through said body means for supplying motive fluid to said engine, throttle valve means situated in said induction passage means for variably controlling the rate of flow of air through said induction passage means, fuel-air mixture discharge means situated in said induction passage means downstream of said throttle valve means, air passage means communicating between a source of air and said fuel-air mixture discharge means, said air passage means comprising flow restriction means, said flow restriction means being calibrated as to provide for sonic flow therethrough at conditions of idle engine operation, fuel metering means for metering liquid fuel in response to engine demands and indicia of engine operation, said liquid fuel when metered by said fuel metering means being discharged into said air passage means at an area thereof downstream of said source of air and upstream of said flow restriction means, said flow restriction means comprising sonic venturi type restriction means, said fuel metering means for metering liquid fuel comprising a duty-cycle type metering solenoid assembly, said metering solenoid assembly comprising armature means, a valve member operatively carried by said armature means, and a field winding, said field winding being intermittently energizable during metering of said liquid fuel as to cause said armature means and said valve member to move toward and away from a closed position and thereby result in an average rate of flow of fuel past said valve member which constitutes the then metered rate of liquid fuel flow, unmetered fuel passage means for supplying unmetered fuel to said fuel metering means upstream of said fuel metering means, pressure regulator means operatively communicating with said unmetered fuel for regulating the pressure thereof to a reselected superatmospheric magnitude, said fuel-air mixture discharge means comprising generally annular means defining generally annular passage means, said air-passage means in communicating with said fuel-air mixture discharge means communicates with said generally annular passage means, and discharge port means communicating between said generally annular passage means and said induc-

tion passage means for directing the flow of the fuel-air mixture within said generally annular passage means to said induction passage means, said discharge port means comprising a plurality of discharge ports spaced from each other and directed generally radially inwardly of said induction passage means.

4,292,946

AIR-FUEL RATIO CONTROL SYSTEM

Kenji Masaki, Yokohama, Japan, assignor to Nissan Motor Company, Limited, Yokohama, Japan


Filed Oct. 5, 1979, Ser. No. 82,337

Claims priority, application Japan, Nov. 15, 1978, 53-140667; Nov. 15, 1978, 53-140668

Int. Cl.³ F02B 33/00

U.S. Cl. 123-440

5 Claims



1. An air-fuel ratio control system for use with an engine carburetor including an air-fuel induction passage provided therein with a throttle valve, a float chamber, and a main fuel passage connected at its one end to said float chamber and at the other end to said induction passage downstream of said throttle valve, comprising:

- a control unit responsive to various engine operating factors for judging the condition under which the engine is operating and providing first and second pulse signals each having a constant period and a pulse width corresponding to the engine operating condition;
- a main control valve provided in said main fuel passage, said main control valve responsive to the first pulse signal for opening and closing said main fuel passage so as to control the flow of fuel passing therethrough;
- fuel supply means for supplying fuel;
- an auxiliary fuel passage connected at its one end to said fuel supply means and at the other end to said induction passage downstream of said throttle valve;
- an auxiliary control valve provided in said auxiliary fuel passage, said auxiliary control valve responsive to the second pulse signal for opening and closing said auxiliary fuel passage so as to control the flow of fuel passing therethrough, thereby providing an optimum air-fuel ratio corresponding to the engine operating condition; and
- an air-fuel ratio sensor provided in said induction passage downstream of said throttle valve, said sensor responsive to the air-fuel ratio of a mixture flowing thereover to provide an air-fuel ratio indicative signal to said control unit for feedback control of the air-fuel ratio, said air-fuel ratio sensor comprises a heater responsive to a signal from said control unit for catalytic oxidization of the mixture flowing into contact therewith, an oxygen sensitive element for detecting the oxygen density of the gases resulting from the catalytic oxidization, and a perforated flame stabilizer covering said heater and said oxygen sensitive element.

4,292,947

SPILL TYPE SWIRL INJECTOR

Yasusi Tanasawa, Nagoya; Norio Muto, Aichi; Akinori Saito, and Kiyomi Kawamura, both of Nagoya, all of Japan, assignors to Kabushiki Kaisha Toyota Chuo Kenkyusho, Nagoya, Japan


Filed Nov. 7, 1979, Ser. No. 92,036

Claims priority, application Japan, Nov. 7, 1978, 53-137630

Int. Cl.³ B05B 1/32; F02B 3/00; F02G 3/00

U.S. Cl. 123-445

6 Claims



1. A spill type swirl injector comprising:
a nozzle body having an inner cylindrical wall;
a pressurized fluid supply source;
an injection port opening at one end of said nozzle body for injecting pressurized fluid;
pressurized fluid supply passage means;
a pressurized fluid induction passage provided within said nozzle body, said pressurized fluid induction passage being connected to said pressurized fluid supply source through said pressurized fluid supply passage means;
valve means including a movable member interposed into said injection port for controlling the fluid injection by on-off controlling the fuel supply to said injection port;
a swirl chamber comprising an annular chamber formed between said inner cylindrical wall of said end of said nozzle body and an outer cylindrical wall of said movable member of said valve means, at a position adjacent to said injection port within said nozzle body, said swirl chamber being connected to said injection port;
first and second tangential pressurized fluid supply passages formed within said nozzle body in communication with said pressurized fluid induction passage and opening into said inner cylinder wall of said nozzle body of said swirl chamber in the tangential direction thereof for forming swirling flow of said pressurized fluid within said swirl chamber; and
spill means comprising said movable member having first and second spill openings formed therein communicating with said outer cylindrical wall of said movable member of the valve means and opened into said outer cylindrical wall of said movable member in said swirl chamber;
said first and second spill openings being diametrically opposite each other, and
said first and second spill openings being positioned at a distance farther from said fuel injection port than said tangential pressurized fluid supply passages when said injection port is closed by said valve means; and
first spill passage means comprising said movable member having an axial hole formed therein communicating with said two spill openings, and said nozzle body having second spill passage means formed therein communicating with said axial hole and said pressurized fluid supply source, thereby spilling a predetermined quantity of the pressurized fluid from said outer cylindrical wall of said movable member in said swirl chamber through said first and second spill openings, said axial hole and said second spill passage means, without decreasing the swirling energy of the swirling flow in said swirl chamber, such that

the fluid is injected in the form of a liquid film flow having a sufficiently high swirling velocity immediately after the valve is opened so that the sprayed liquid droplets are fine and uniform and the atomizing characteristics and response of atomization to the injection pressure are improved.


4,292,948
METHOD FOR EXTENDING THE RANGE OF OPERATION OF AN ELECTROMAGNETIC FUEL INJECTOR

William J. Graessley, Ypsilanti, Mich., assignor to Ford Motor Company, Dearborn, Mich.

Filed Oct. 9, 1979, Ser. No. 83,016
 Int. Cl.³ F02M 51/00; F02D 5/02

U.S. Cl. 123—490

1 Claim



1. A method for extending the range of operation of an electromagnetic fuel injector having an inductive element which, when supplied with an electrical potential causes the fuel injector to open to permit delivery of pressurized fuel supplied to the injector, the opening rate of the fuel injector being a function of the magnitude of the electrical potential applied to the inductive element and the closing rate of the fuel injector being a function of the current in the inductive element upon reduction of the magnitude of the electrical potential to a level below that required to hold the fuel injector open, the method comprising the steps of applying substantially full available DC electrical supply potential across the inductive element of the fuel injector to cause it to open, sensing the current in the inductive element by a sensing resistor which generates a sensing voltage, applying the sensing voltage to a threshold detector, comparing the applied voltage to a reference voltage coupled to the threshold detector, continuing the current in the electromagnetic injector inductive element, establishing a reset logic state in a flip flop when the applied voltage exceeds the reference voltage, applying the flip flop output to a transistor so that the transistor becomes conductive and causing a reduced reference potential to be applied to the positive input of an operational amplifier, reducing the output voltage of the operational amplifier and the driving voltage for a Darlington transistor, reducing the conductivity of the Darlington transistor and decreasing the current level in the inductive element and thereafter holding the current in the inductive element at a level sufficient to maintain it open and at a current level less than that which occurs due to prolonged application of the substantially full available DC electrical supply potential, thereby reducing the time required to close the injector.

4,292,949
ELECTRONICALLY CONTROLLED COMBUSTION AIR MIXING VALVE FOR INTERNAL COMBUSTION ENGINES


Lothar Bendig, Ludwigsburg, Fed. Rep. of Germany, assignor to Filterwerk Mann & Hummel GmbH, Ludwigsburg, Fed. Rep. of Germany

Filed Sep. 2, 1980, Ser. No. 183,152
 Claims priority, application Fed. Rep. of Germany, Aug. 30, 1979, 2935009

Int. Cl.³ F02M 31/00

U.S. Cl. 123—556

8 Claims



1. A device for controlling the temperature of the combustion air in the air intake system of an internal combustion engine, the device comprising in combination:

a cold air intake duct for the intake of air of ambient temperature;

a warm air intake duct for the intake of preheated air coming from an air heater which is associated with the engine;

a duct junction where the cold air intake duct and the warm air intake duct are joined;

a combustion air duct leading from the duct junction to the cylinder or cylinders of the internal combustion engine;

an air flow proportioning valve associated with the cold air and warm air intake ducts, at the duct junction, the valve being adjustable in its position so as to progressively open one of the two ducts while correspondingly closing the other, thereby adjusting the relative flow rates at which cold air and preheated air are drawn into the combustion air duct;

means for sensing the combustion air temperature in the combustion air duct and for generating an electrical signal indicative of the temperature level; and

means for adjusting the position of the air flow proportioning valve in response to the electrical control signal supplied by the temperature sensing means so that, when the air temperature in the combustion air duct rises, the corresponding control signal induces the valve position adjusting means to adjust the position of the air flow proportioning valve in the direction of closing the warm air intake duct and opening the cold air intake duct; and wherein the valve position adjusting means includes a pneumatic actuator with an enclosed pressure chamber of variable volume and a return-biased drive linkage connecting a movable wall portion of the pressure chamber to the flow proportioning valve; and


the pneumatic actuator further includes a heat source of variable output arranged to adjustably raise the temperature in the pressure chamber above the ambient temperature, in response to changes in the electrical control signal.

4,292,950
GAS BURNER SYSTEM

George W. Schossow, 2316 Lilac Ln., White Bear Lake, Minn. 55110

Filed Jun. 3, 1977, Ser. No. 803,041
 Int. Cl.³ F23J 11/00; F24H 3/02
 U.S. Cl. 126—110 A

3 Claims



1. A gas burning furnace system comprising:

(a) a pressure box having downstream outlet providing fluid communication with a gas burner in a firebox, and an upstream inlet;

(b) a blower for pressurizing said pressure box with outside air, said blower having an inlet end and an outlet end in fluid communication with said upstream inlet end of said pressure box;

(c) a conduit extending from an outside air vent into said blower, whereby the blower draws air exclusively from outside the home and forces it into the pressure box;

(d) a baffle plate mounted within the pressure box between the pressure box inlet and outlet, dividing the interior of the pressure box into an upstream and a downstream chamber, said baffle plate having a plurality of apertures therein;

(e) a movable grate mounted on the baffle plate in superposed relationship to said plurality of apertures, whereby the grate may be moved to selectively adjust the size of the openings defined by the grate and the apertures;

(f) means extending outside the pressure box for moving the grate;

(g) a flapper plate pivotally mounted in an exterior wall of the downstream chamber of the pressure box, said flapper plate being adapted to swing in response to pressure changes within said downstream chamber;

(h) safety means for supplying air from inside the home to the burner, should the outside air supply become inadequate to satisfy the combustion air demands of the burner;

(i) means for preventing a back draft down a chimney from blowing out the burner flame, including at least one barometric draft regulator plate pivotally mounted in an exterior wall of the furnace and diverter means situated between the burner and the chimney for diverting any such drafts to said plate, whereby said plate may swing open to allow any such drafts to escape from the furnace before reaching the burner flame;

(j) means for preventing the ignition of the burner until a predetermined pressure has been reached within the pressure box, said ignition preventing means including a pressure sensitive switch mounted in said pressure box and operably connected with means for igniting the burner; and

(k) a normally open butterfly valve mounted in the outside

air conduit, and means for closing said valve after a time delay following shut-off of the burner.


4,292,951
FIREPLACES AND ATTACHMENTS

George E. Gould, 13406 Arctic Ave., Rockville, Md. 20853
 Filed Feb. 9, 1979, Ser. No. 10,805

Int. Cl.³ F24B 1/18; F 23L 11/00

U.S. Cl. 126—120

9 Claims



1. A fireplace in a building which substantially prevents smoke from entering the room in which the fireplace is situated, comprising,

a fireplace opening comprised of a cavity, a throat, and a flue, the flue being situated above the cavity and leading to the exterior of the building for the elimination of smoke, and the throat being situated at the transition between the cavity and the flue,

the cavity including a floor, side walls, a rear wall, and a front wall extending partially to the floor and forming a front opening,

movable damper means situated above the throat for selectively changing the size of a first opening to the flue, and adjustable controller means situated below the throat and operable independently of such damper means for controlling the size of a second opening to the flue disposed beneath and in series with the first opening,

the adjustable controller means being tiltable about its lower edge and being movable toward the rear wall at its upper portion to form in cooperation with such rear wall a venturi-type opening at said throat, whereby the second opening may be adjusted to ensure that substantially all smoke passes up the flue and not into the room.

4,292,952
FIREPLACE FURNACE

Charles B. McDonald, Rte. 1, Atkins, Ark. 72823
 Filed Aug. 16, 1979, Ser. No. 67,016

Int. Cl.³ F24B 7/00
 U.S. Cl. 126—121

9 Claims

1. A fireplace structure for use in heating a building environment, said fireplace structure comprising:


a firebox having enclosing opposite side walls, a rear wall and a top wall;

a first flue having an opening in said top wall and extending upwardly from said opening for removing products of combustion from said firebox;

a first damper disposed across said first flue for selectively closing said first flue; and

a second flue having an opening disposed below the opening of said first flue, said second flue extending upwardly from its respective opening, including jacket means defining a heat exchange area around said firebox for heating air passed therethrough, an air intake duct having an intake end positioned exteriorly of said building and an outlet

end positioned in said firebox for channeling combustion supporting air to said firebox, a damper disposed in said air intake duct; a building air circulation duct opening into said heat exchange area and having an intake end opening into said building for circulating building air through said heat exchange area, and an outlet port in said heat exchange area for reintroducing building air into said build-



ing interior, said building air circulation duct including a damper flap disposed therein, said damper flap and said air intake duct damper being connected to a common shaft, said damper flap being positioned across said air circulation duct so as to be displaced by air movement there-through, thereby causing displacement of said damper in said air intake duct.


4,292,953

POLLUTANT-FREE LOW TEMPERATURE SLURRY COMBUSTION PROCESS UTILIZING THE SUPER-CRITICAL STATE

Norman L. Dickinson, Box 211, Lavallette, N.J. 08735
Filed Oct. 5, 1978, Ser. No. 948,682
Int. Cl.³ F24J 3/00

U.S. Cl. 126-263


16 Claims



1. A process for converting the heating value of a fuel to useful heat comprising the steps of:
charging the fuel together with air and water to a pressurized combustion zone in which liberation of combustion heat causes the temperature to rise above the critical temperature of water;
extracting useful heat so as to cool the combustion products below their dewpoint;
separating an aqueous condensate from the cooled combustion products; and
recycling a portion of the aqueous condensate to the combustion zone as a source of the water charged thereto.

WOOD BURNING HEATER

Murray O. Wilhoite, Huntsville, Ala., assignor to Martin Industries, Inc., Florence, Ala.
Filed May 25, 1979, Ser. No. 42,560
Int. Cl.³ F23L 3/00; F01B 25/00; F27D 19/00
U.S. Cl. 126-290 11 Claims



1. A combustion type heater comprising:
a firebox comprising a combustion chamber heated by the burning of fuel therein;
a plenum around and over said firebox and forming in said plenum an air space, and said plenum having separate inlet and outlet openings;
a third opening in a top region between said inlet and outlet openings of said plenum; and
control means including a door movably positioned in said third opening and operable between positions of opening and closure of said third opening, and responsive to a selected magnitude of air movement between said inlet and outlet openings for operating said door to a said closed position, and responsive to less than said selected magnitude of air movement for operating said door to said open position, and said control means comprising:
means for supporting said door in a normally, without substantial air flow, open position with a region of said door extending into said plenum and in a path otherwise traversed by air movement between said inlet and outlet openings, whereby upon the occurrence of air movement, said region of said door is engaged by air movement and said door moved to a said closed position.


4,292,955

SOLAR ENERGY COLLECTOR

Harold W. Smith, 37 Moseley Ave., Needham, Mass. 02192
Filed Feb. 24, 1978, Ser. No. 880,806
Int. Cl.³ F24J 3/02

U.S. Cl. 126-417

12 Claims



1. A solar energy panel comprising
a frame having an aperture therein adapted to face the sun,
a continuous base member supported in said frame,
a solar energy absorber supported in said frame against said base member and adapted to be exposed to the sun's radiation through said aperture,
said absorber being formed of a thin, heat conducting sheet

material of high corrosion resistance formed into a convoluted absorber member which, together with said base member, defines walls of a multiplicity of fluid channels of small cross section positioned close to one another, each of said channels including a pair of upwardly converging side walls of said absorber sheet material, said side walls thereby adapted to absorb most of the sun's radiation which enters said aperture and reflect substantially all of the remainder away from said aperture, fluid inlet and outlet means connected to said channels to enable fluid to flow to and through said channels, a cover member substantially transparent to solar radiation positioned across said aperture and in close proximity to said absorber to define small air spaces between said cover and adjacent fluid channels, said fluid channels being spaced in proximity to each other such that the aggregate area defined by the inner surfaces of the walls of the channels as formed by the absorber member is substantially greater than the area of the frame aperture.

4,292,956


CORRUGATED PANEL SOLAR COLLECTOR

Kurt J. Wasserman, Westtown, N.Y., assignor to Insolar Inc., Port Jervis, N.Y.

Filed May 19, 1980, Ser. No. 150,819
Int. Cl.³ F24J 3/02

U.S. Cl. 126-439

5 Claims



1. A solar collector apparatus comprising:
generally planar top and bottom housing members, having opposed corrugated surfaces of substantially the same pitch facing each other so as to define a series of side-by-side longitudinally directed cavities between said housing members, said top housing member being translucent; and
a plurality of elongated elastomeric solar energy absorbing elements, each element being substantially centrally located in a different one of said cavities and running substantially the entire length of said cavities, each said element being an integral element of substantially constant transverse cross-section, each said element including a series of side-by-side longitudinally directed conduits for heat transfer fluid, a pair of generally planar left and right margins directed transversely respectively from the leftmost and rightmost conduits in said series respectively toward the cavities neighboring on the left and right of each said cavity in which each said solar energy absorbing element is substantially centrally located, each of said left and right margins carrying bead means respectively lying within said neighboring cavities on the left and right and respectively engaging said left and right neighboring cavities along substantially the entire length of said neighboring cavities, said left and right margins of said solar energy absorbing elements being transversely stretched to provide a force holding said bead means in substantially sealing engagement with said neighboring cavities.


4,292,957

SOLAR OVEN

John C. Golder, P.O. Box 854, Santa Cruz, Calif. 95061
Filed Nov. 23, 1979, Ser. No. 96,820
Int. Cl.³ F24J 3/02

U.S. Cl. 126-451

6 Claims



1. A portable foldable solar oven comprising in combination:
a. a base consisting primarily of a box-like member having four sides and a bottom and an open top;
b. insulating means within said box lining all four sides and the bottom of said box and forming the interior surfaces of the oven;
c. a glazing element supported over the top of said insulating material and
d. a generally funnel-shaped reflective element supported over said glazing element, said reflective element having downward extending flaps, said flaps extending between the sides of said box and said insulating material whereby friction between said flaps and said box holds said reflective member at a desired elevation angle.

4,292,958


SOLAR HEAT ABSORBER FOR SOLAR HEAT COLLECTORS

Marlow Lee, Clawson, Mich., assignor to H & H Tube & Mfg. Co., Southfield, Mich.

Filed Dec. 10, 1979, Ser. No. 102,117
Int. Cl.³ F24J 3/02

U.S. Cl. 126-448

5 Claims



1. A solar heat energy absorber panel comprising an inlet

header and an outlet header, a slot extending through a lateral wall of each of said headers, a plurality of separate elongated tubular members placing said headers in fluid communication, each of said elongated tubular members being in the form of a substantially flat thin walled tube having a pair of relatively wide sidewalls disposed substantially parallel and integrally interconnected by a pair of opposite relatively narrow sidewalls, said tubes being disposed side by side with their relatively wide sidewalls coplanar and each of their relatively narrow sidewalls contiguous with the relatively narrow sidewall of an adjoining tube, at least one reinforcing cross-member extending laterally on one side of said panel and affixed to a relatively wide sidewall of each of said tubes and maintaining said relatively wide sidewalls on each side of said panel substantially co-planar, wherein said headers are each a length of pipe, said slot is formed radially through the wall of said length of pipe, said slot extends from one end to the other of said length of pipe, each end of each of said tubes is disposed transverse said slot in one of said headers and is affixed to the edge of said slot, and each end of each of said headers has a tubular member affixed thereover and covering the end of said slot wherein said reinforcing cross-member is a length of said substantially flat thin walled tube having its relatively narrow sidewall affixed to the relatively wide sidewall of each of said tubes.

4,292,959

SOLAR ENERGY COLLECTION SYSTEM


John F. Coburn, Jr., Cranford, N.J., assignor to Exxon Research & Engineering Co., Florham Park, N.J.

Filed Feb. 25, 1980, Ser. No. 124,278

Int. Cl.³ F24J 3/02; G01J 1/00; G02B 17/00

U.S. Cl. 126—438

8 Claims



1. A system for the collection of solar radiation and the transmission thereof to a point of utilization in the form of light comprising:

- a solar collector for the receipt and concentration of solar radiation, said solar collector being a planar fluorescent concentrator having a major surface for receipt of instant solar radiation and an edge for transmission of the solar radiation collected and concentrated by said collector;
- second concentrator means optically coupled to said edge of said collector for receipt of concentrated solar radiation from said collector and for the further concentration of said solar radiation;
- a light transmission pipe optically connected to said second concentrator, whereby light from the collector which is concentrated in the second concentrator is introduced into said light transmission pipe for transmission to a point of use; and,
- a utilization device remote from said solar collector whereby solar radiation incident on said collector is transmitted to said point of utilization in the form of light.

4,292,960 APPARATUS AND METHOD FOR APPLICATION OF RADIOACTIVE AND MICROWAVE ENERGY TO THE BODY


Robert W. Paglione, Robbinsville, N.J., assignor to RCA Corporation, New York, N.Y.

Filed Apr. 30, 1979, Ser. No. 34,744

Int. Cl.³ A61N 5/12

U.S. Cl. 128—1.1

12 Claims



1. An apparatus for use with a radioactive substance for applying radioactive and microwave energy to the walls of a body cavity comprising:

- a source of microwave signals having a predetermined amplitude and frequency,
- means including a radiator responsive to said microwave signals for radiating said signals,
- means for coupling said microwave signals to said radiating means,
- a container having a first compartment adapted for receiving a quantity of said radioactive substance and having in a second compartment thereof said radiator, and
- means for supporting said container in said body cavity.

4,292,961

APPARATUS FOR AUTOMATICALLY CONTROLLING THE POSITION OF ENDOSCOPES OR SIMILAR DEVICES IN A CAVITY

Kazuma Kawashima, Tokyo, Japan, assignor to Olympus Optical Company Ltd., Tokyo, Japan


Filed Nov. 13, 1979, Ser. No. 93,160

Claims priority, application Japan, Dec. 26, 1978, 53-162730

Int. Cl.³ A61B 1/06

U.S. Cl. 128—6

23 Claims



1. Apparatus for controlling the position of a device adapted for insertion in a cavity, comprising a bendable distal portion on said device, light emitter means located on said distal portion of the device for directing light toward an internal wall of a cavity in which said distal portion is being inserted, light sensing means located on said distal portion for sensing light emitted from said light emitting means and reflected from an internal wall of a cavity in which said distal portion is being inserted and for producing signals in response to the amount of sensed light, control means located at the proximal portion of said device and responsive to the amount of reflected light sensed by said light sensing means, said control means includ-

ing comparison means for comparing signals produced by said light sensing means to determine the position of said distal portion in a cavity in which said distal portion is being inserted, and drive means responsive to the position determination made by said comparison means for automatically controlling the position of said distal portion in a cavity in which said distal portion is being inserted.

4,292,962

APPARATUS FOR POSTURAL TREATMENT OF HUMANS


Nicolaas J. P. R. Krause, 35 Machine St., Elsburg, Transvaal Province, South Africa

Filed Apr. 19, 1979, Ser. No. 31,518

Int. Cl.³ A61F 5/00

U.S. Cl. 128—68

24 Claims



1. An apparatus for effecting postural treatment of humans, the apparatus including

- a supporting structure;
- a platform structure that is pivotally mounted on the supporting structure to be pivotal about a horizontal pivotal axis;
- a platform adjustably secured on the platform structure, having a support surface on which a human may be supported in the region of his hip in a bent over, face down attitude;
- a first adjusting mechanism for adjusting the position of the platform relative to the platform support structure in a first direction transverse to the pivotal axis of the platform support structure; and
- a second adjusting mechanism for adjusting the position of the platform relative to the platform support structure in a second direction transverse to the pivotal axis of the platform support structure and substantially orthogonal to the first direction,

the position of the centre of gravity of the platform and a human supported thereon thus being adjustable relative to the pivotal axis of the platform support structure.

4,292,963

TRAINING SPLINT FOR WRIST-GANGLION

Robert S. Ford, 701 Beach Blvd., Pascagoula, Miss. 39567


Division of Ser. No. 875,940, Feb. 7, 1980, abandoned. This

application Jul. 25, 1979, Ser. No. 60,574

Int. Cl.³ A61F 5/04

U.S. Cl. 128—87 R

3 Claims



1. In an orthopedic appliance adapted for attachment to the

distal end of the forearm by lashing means embracing the said forearm adjacent to the wrist, an appliance having a shape analogous to the letter "T", combining a central base plate comparable to the stem of a T to be secured across the distal end of the forearm by lashing means including lashing attachment means provided on the said plate, an arcuate double-ended splint member comparable to the combined upper arms of a letter T extending across and containing the upper end of the said central base plate comparable to the T stem, the said arcuate member being formed in a curving shape with the tips drooping toward the base of the letter T, whereby one tip of the said arcuate splint arm will appose the dorsum of the hand to prevent dorsiflexion without contacting a wrist-ganglion, while the opposite tip will serve as a footing lever against the forearm, the whole device being reversible at will to obtain optional or right positions of the active splint arm upon either wrist, so as to permit dodging ganglions wherever they may lie.

4,292,964

METHOD OF AND APPARATUS FOR PINNING A FRACTURED PELVIS

Max B. Ulrich, Amselweg 55, 7900 Ulm, Fed. Rep. of Germany


Filed Jan. 17, 1980, Ser. No. 112,821

Claims priority, application Fed. Rep. of Germany, Jan. 19, 1979, 2901962

Int. Cl.³ A61F 5/04

U.S. Cl. 128—92 EB

10 Claims



1. A method of pinning a bone using a guide apparatus comprising an elongated member provided with a pair of longitudinally spaced and transversely projecting arms having outer ends provided with respective coaxially aligned cannulas having points directed at each other and separated by a space, said method comprising the steps of sequentially:

- positioning a fractured bone in said space between said cannulas with said points engaging said fractured bone;
- inserting a relatively small-diameter guide rod axially through said cannulas and through the fractured bone engaged therebetween;
- disengaging said apparatus from said bone while leaving said small-diameter guide rod in place in said bone;
- fitting a tubular drill bit over said guide rod engaged in said bone and drilling a bore through said bone along said guide rod while guiding said bit through said bone along said guide rod;
- withdrawing said guide rod from said bit while leaving same engaged through said bore in said fractured bone;
- axially retracting said bit from said bone while simultaneously and synchronously axially inserting a bone pin through said bore; and

bracing the ends of said bone pin axially oppositely on said fractured bone.

4,292,965

INTRAVAGINAL RING


Harold A. Nash, Harrington Park, N.J., and Daniel R. Mishell, Jr., Palos Verdes Estates, Calif., assignors to The Population Council, Inc., New York, N.Y.

Filed Dec. 29, 1978, Ser. No. 974,490

Int. Cl.³ A61M 7/00

U.S. Cl. 128—260

13 Claims



1. A shell design intravaginal ring comprising in combination a core made of an inert elastomer, a medicated layer encircling the core, and an outer inert elastomer layer having a thickness of about 0.1 to 0.6 mm, the medicated layer comprising an inert elastomer and a combination of estradiol with a progestogen selected from the group consisting of levonorgestrel, d,l-norgestrel and norethindrone and the medicated layer having a thickness of not more than twice the thickness of the outer layer.

4,292,966

AEROSOL INHALATION DEVICE

Rune G. Monö, Täby; Nils F. E. Moren, Malmö, and Kjell I. L. Wetterlin, S. Sandby, all of Sweden, assignors to Aktiebolaget Draco, Lund, Sweden


Filed Feb. 5, 1980, Ser. No. 118,750

Claims priority, application Sweden, Feb. 16, 1979, 7901417

Int. Cl.³ A61M 11/04

U.S. Cl. 128—200.23

2 Claims



1. An aerosol inhalation device comprising an elongated chamber, provided at one end with means for connection thereof to an aerosol dispenser and having an outlet opening at the opposite end which opening is arranged to be brought to the mouth of a patient, characterized in comprising an outer chamber part and an inner chamber part each having a substantially rectangular cross section, said outer chamber part comprises the outlet opening and is telescopically displaceable over said inner chamber part, said inner chamber part at its outer end being provided with a flexible tongue, which on telescoping said chamber parts together will guide close said outer chamber part including guide means said flexible tongue to said outlet opening.

4,292,967 RESPIRATOR HAVING OXYGEN DELIVERING CHEMICAL CARTRIDGE

Adalbert Pasternack, Bad Schwartau, Fed. Rep. of Germany, assignor to Drägerwerk Aktiengesellschaft, Fed. Rep. of Germany


Filed Dec. 14, 1979, Ser. No. 103,491

Claims priority, application Fed. Rep. of Germany, Dec. 27, 1978, 2856349

Int. Cl.³ A62B 7/08

U.S. Cl. 128—202.26

4 Claims



1. A respirator, comprising, a housing having a wall with a sealable opening, a chemical cartridge in said housing spaced from said sealable opening having a material capable of generating oxygen upon being started, breathing tube means connected into said cartridge for the circulation of respiratory gases therethrough, a first starter associated with said cartridge and located in said housing for starting the material so that it will generate oxygen, and a control element disposed in said housing adjacent to said sealable opening in said wall so as to be accessible from the outside of the housing upon the opening of the sealable opening, said control element having a starting material therein which is spaced from said cartridge and which may be actuated to generate oxygen so as to provide an indication of the operability of said chemical cartridge while not starting the material of said cartridge.

4,292,968

ELECTRIC SUPPLY FOR ION THERAPY


Franklin H. Ellis, Rochester, N.Y., assignor to Sybron Corporation, Rochester, N.Y.

Filed Nov. 26, 1979, Ser. No. 97,535

Int. Cl.³ A61N 1/30

U.S. Cl. 128—207.21

1 Claim



1. Apparatus for ion therapy characterized by having two modes of operation and comprised of: two electrodes for making electrical contact with a patient; current means electrically connected to said electrodes for

providing constant direct current flow through the electrodes during a first mode; voltage means electrically connected to said electrodes for providing a constant predetermined direct current voltage of less than 1.1 volts across the electrodes during a second mode; and voltage responsive means for causing an abrupt transition from the first mode to the second mode if the voltage across the electrodes reaches said predetermined voltage.

4,292,969

FLUID REGULATING DEVICE WITH TORSIONAL CONTROL


Donald A. Raible, 1262 Camden Dr., Santa Ana, Calif. 92705; Stuart M. Poticha, 2800 N. Lake Shore Dr., Apt. 2216, Chicago, Ill. 60613, and Rita Stauffer, 1016 W. Hollywood, Chicago, Ill. 60660

Filed Dec. 19, 1979, Ser. No. 105,028

Int. Cl.³ A61M 5/00; E16L 55/14

U.S. Cl. 128—214 R

10 Claims



1. An improved fluid regulating device for use in a parenteral administration system having a fluid supply container, a parenteral needle and torsionally flexible tubing, comprising: a first body member having a first channel wall and a first channel wall, the first channel wall defining a first channel for a first tubing portion of flexible tubing and the first chamber wall defining a first open-ended portion of a chamber along the first channel, the first chamber wall having a minimum diametric dimension greater than the maximum outer dimension of the flexible tubing; first securing means on the first body member for securing the first body member to the first tubing portion for common rotation about a first axis through the chamber; a second body member having a second channel wall and a second chamber wall, the second channel wall defining a second channel for a second tubing portion of the flexible tubing and the second chamber wall defining a second open-ended portion of the chamber along the second channel, the second chamber wall having a minimum diametric dimension greater than the maximum outer dimension of the flexible tubing; second securing means on the first body member for securing the second body member to the second tubular portion for common rotation about a second axis through the chamber; mounting means on the first body member and the second body member for mounting the first body member to the second body member with the axes coincident for rotation about the axes, and with the first portion of the chamber open to the second portion of the chamber such that an unsecured portion of flexible tubing that is intermediate and jointed to the first tubing portion and the second tubing portion passes through the chamber, and with the first body member being rotatable relative to the second body member such that in a first relative rotational position, the unsecured tubing portion is in a first condition of torsional flexure and in a second relative rotational position,

tion, the unsecured tubing portion is in a second condition of torsional flexure; whereby the unsecured portion of the flexible tubing is torsionally flexed by relative rotation of the first and second body member so as to regulate fluid flow there-through.

4,292,970

APPARATUS FOR INTRAVENOUS CATHETER STARTER


William M. Hession, Jr., 317 Lee Dr., Thibodaux, La. 70301

Filed Jan. 24, 1980, Ser. No. 115,123

Int. Cl.³ A61M 5/00

U.S. Cl. 128—214.4

3 Claims



1. An I.V. placement needle with plastic outside catheter comprising: (a) a backflow chamber within a chamber guard, (b) a vein puncture needle in communication with the backflow chamber, (c) a catheter hub, (d) a catheter tube secured to said hub and receivable over said vein puncture needle concentrically therewith, and (e) a plastic drive plate upstanding from said catheter hub and having its major plane transverse to the axis of said hub and catheter tube for engagement by a driving force to advance the hub and catheter tube coaxially over said vein puncture needle, and a resilient potentially biased striking means carried by said backflow chamber guard positioned to when released engage said plastic drive plate and with an energy thrust to advance the catheter tube and its hub axially over the vein puncture needle to cause the catheter tube to be introduced in a vein following entry of the vein puncture needle into the vein.

4,292,971

ACNE SKIN TREATMENT APPLIANCE AND METHOD


Helen Smit, and Julie Smit, both of 1045 Hinman Ave., Evanston, Ill. 60202

Continuation-in-part of Ser. No. 801,850, May 31, 1977, Pat. No. 4,182,329. This application Aug. 8, 1979, Ser. No. 64,730

Int. Cl.³ A61M 1/00

U.S. Cl. 128—256

11 Claims



1. Apparatus for treating human skin, said apparatus comprising heater means for producing a draft of heated air directed against an area of skin, the heat of said air being sufficient to cause a physical change to occur within the pores of the heated skin without damage to said skin, said heater means being disposed within a passageway which is in direct communication with said area of skin to be heated in order to direct the heat directly on to only said area of skin, said passageway

guarding said draft of air to prevent an ambient cooling thereof and to prevent any change of state of the heated air within said passageway, said physical change in said pores being an enlargement of their openings and a melting and softening of solidified debris within a follicle in said pore respective to said heated air, vacuum-producing means for applying an air suction through said passageway to said area of skin to draw the melted and softened debris out of the enlarged skin pores, said removed debris being drawn by said vacuum-producing means from said heated area of skin through said passageway and into means for collecting said removed debris, said last-named means being removable so that it may be washed and cleaned, the apparatus further comprising a motor chamber sealed and separated from the sauna chamber by a vertical wall, an air directing conduit extending from the wall to the water container within the sauna chamber, the said conduit formed by an upper horizontal wall and a lower inclined wall to define a tapering air path in the direction toward the water container, a blower positioned within the conduit at the wider extremity of the taper, the said closed passageway extending from the steaming area being provided with a funnel stream applicator at its extremity with a smaller dimension of the funnel secured to the passageway and the wider dimension having a sponge material around its peripheral circumference.

4,292,972

LYOPHILIZED HYDROCOLLOID FOAM

John M. Pawelchak, Belle Mead; Yu-Chang J. Wang, North Brunswick, and Anthony L. LaVia, East Brunswick, all of N.J., assignors to E. R. Squibb & Sons, Inc., Princeton, N.J.
Filed Jul. 9, 1980, Ser. No. 167,257

Int. Cl.³ A61F 13/00

U.S. Cl. 128—296

30 Claims

1. A medically useful lyophilized sponge product having a density of from about 0.01 to about 0.10 gm/cc, said sponge product comprising a mixture of the hydrocolloids, gelatin, pectin, and sodium carboxymethylcellulose, said pectin and sodium carboxymethylcellulose each being at from about 10% to about 50% by weight of the final product and said gelatin being present at from about 20% to about 80% by weight of the final product.

4,292,973

APPARATUS FOR REFRIGERATION TREATMENT


Toshima Yamauchi, Oita; Sadao Nogami, Beppu; Kengi Sawada, Oita; Jyunichiro Moriya, Kokubunji; Hiroomi Sawada, Ichikawa, and Keizou Kobayashi, Hanno, all of Japan, assignors to Kabushiki Kaisha Kurio-Medikaru, Tokyo, Japan
Continuation of Ser. No. 944,079, Sep. 20, 1978, abandoned. This application Jan. 3, 1980, Ser. No. 109,271

Claims priority, application Japan, Sep. 25, 1977, 52-114967; Feb. 28, 1978, 53-22900

Int. Cl.³ A61B 17/36

U.S. Cl. 128—303.1

2 Claims



1. An apparatus for refrigeration treatment comprising a liquefied gas source, an evaporator for evaporating the liquefied gas at an optimum temperature, an exhaust tube connected between said gas source and said evaporator to conduct the liquefied gas from said gas source to said evaporator, a conduit for introducing the gas vaporized by said evaporator, and a cup provided with a non-return expansion valve attached at

the end of said conduit, said cup adapted to apply said vaporized gas to an affected portion of a patient in order to refrigerate said portion with said vaporized gas, said evaporator being provided with an evaporator chamber for evaporating the liquefied gas to a gaseous state to be blown out from the cup at a specified temperature and said conduit being connected to said evaporator by means of an outflow port, wherein said exhaust tube is provided with an electromagnetic valve for preventing the inflow of liquefied gas into said evaporating chamber and said evaporating chamber is provided with a detector element which actuates said electromagnetic valve by sensing a specified level height of the liquid of the liquefied gas fed to said chamber.

4,292,974


DILATATION CATHETER APPARATUS AND METHOD
Thomas J. Fogarty, 770 Welch Rd., Palo Alto, Calif. 94304, and Albert K. Chin, San Francisco, Calif., assignors to Thomas J. Fogarty, Palo Alto, Calif.

Filed Jan. 30, 1980, Ser. No. 116,816

Int. Cl.³ A61M 29/02

U.S. Cl. 128—344

8 Claims



1. A dilatation catheter comprising an elongated flexible tubular body member, a tip member in spaced relation to the distal end of said body member, an annular inflatable bag interconnecting said tip member and said distal end of said body member, a wire extending through said body member and said bag and secured to said tip member, and knob means attached to the proximal end of said wire enabling said wire to be rotated about its longitudinal axis to rotate said tip member and axially twist said bag and thereby decrease the diameter of said bag in its noninflated condition.

4,292,975

BRASSIERE

Carolyn Champion, 34 Theroux Dr., Chicopee, Mass. 01020; Judith Wolcott, 107 Clairmont Ave., Chicopee, Mass. 01013; Barbara Hart, 131 Woodbridge St., South Hadley, Mass. 01075, and Zulma C. Garcia, 114-40 22 1st St., Queens Village, N.Y. 11429

Filed Aug. 20, 1979, Ser. No. 67,724


Int. Cl.³ A41C 3/00

U.S. Cl. 128—498

2 Claims

1. An exercise brassiere comprising: first and second upper cup members; first and second lower cup members; first and second compression seams joining each of said first and second upper cup members respectively to said first and second lower cup members, said first and second compression seams extending horizontally at a position located over the nipples of the wearer, said first and second upper and lower cup members each having an outer side portion, an innerside portion, a top and a bottom; attachment means positioned at the top of each of said first and second upper cup members; first and second strap members extending respectively from the inner side of the bottom of said first and second lower cup members crossing over one another to said attachment means;

a wide midriff band extending and affixed beneath each of said first and second lower cup members;
a triangular panel positioned between said first and second strap members and said midriff band;
an outer strap member extending along the outer side of said first and second upper and lower cup members from said midriff band to said attachment means;
first and second stretchable side panels affixed to said outer strap member and said midriff band;
first and second rear closure members affixed to said midriff band and said first and second rear side panels adapted to



extend around behind the wearer and include means for removably attaching one rear closure member to the other; and

first and second 2 1/4" wide shoulder straps, each affixed to a section of said first and second rear closure members respectively adapted to be crossed over the back and passed over the wearer's shoulders over the trapezius muscles rather than over the acromio clavicular joints as in standard brassieres with each strap having attachment means at its opposite end adapted to be affixed to said attachment means on the top of each of said upper cup members.

4,292,976


RIGHT VENTRICULAR INJECTION CATHETER; RIGHT VENTRICULAR ANGIOGRAPHIC METHOD; AND METHOD OF MONITORING SEPTAL WALL MOTION
Vidya S. Banka, 237 Stacey Rd., Penn Valley, Narberth, Pa.

Filed Aug. 8, 1979, Ser. No. 64,973

Int. Cl.³ A61B 6/00

U.S. Cl. 128—656

7 Claims



1. A method of right ventricular angiographic catheterization comprising the steps of:

(a) providing a catheter of sufficient length for insertion through the right ventricle and into the pulmonary artery of a patient to be catheterized, said catheter having at least one lumen therein, and said lumen communicating with a plurality of injection orifices 4-10 cm from the tip of said catheter, so that the tip of said catheter when inserted into

the pulmonary artery positions said orifices in the ventricle;
(b) inserting said catheter, tip end first, through said right ventricle and into said pulmonary artery to a point where said injection orifices are located within said right ventricle; and
(c) injecting a contrast medium through said catheter and out said orifices into said right ventricle.

4,292,977

METHOD AND DEVICE FOR REPRESENTING ELECTRICAL SPATIAL LINES AND SPATIAL IMAGES
Heinz Krause, and Bert Sanner, both of Freiburg, Fed. Rep. of Germany, assignors to J. F. Tönnies Erben K.G., Freiburg im Breisgau, Fed. Rep. of Germany


Filed May 8, 1979, Ser. No. 37,119

Claims priority, application Fed. Rep. of Germany, May 8, 1978, 2819999; Mar. 2, 1979, 2908424

Int. Cl.³ A61B 5/04

U.S. Cl. 128—712

3 Claims



1. Method for representing electrical spatial curves and spatial images of electrically reproduced ultrasonic images, X-ray images or cardiac vector loops to a stationary viewer on a fixed screen, which comprises separately storing in an electronic memory amplitude value coordinates occurring in time for the spatial curves or images to be represented, calculating transformed coordinates of the spatial curves or images of the amplitude values in a computer after tilting and rotating relative to the earth by desired angles, two-dimensionally displaying a line from the transformed coordinates on an oscilloscope screen, viewing three-dimensionally through the tilting and rotating relative to the earth, inserting time markers in the form of arrow-shaped lateral jags pointing in the traverse direction of the spatial curves for marking the course in time and direction of traversal of the spatial curves, and determining the size of the jags in dependence on the velocity of the curves.

4,292,978

BREATH TEST MOUTHPIECE

Richard U. Guth, 439 N. 46th St., Harrisburg, Pa. 17111

Filed Dec. 26, 1979, Ser. No. 107,429


Int. Cl.³ A61B 10/00

U.S. Cl. 128—730

23 Claims

1. A handheld mouthpiece of the type used in conducting a breath test including a hollow central collector, a mouth pipe and a tube pipe extending from the collector and communicating with the interior of the collector, a breath baffle within the interior of the collector for changing the direction of the breath blown through the mouthpiece and trapping solids and liquid entrained with the breath, wherein the improvement comprises said pipes being located on opposite sides of the collector, the collector adjacent the mouth pipe including a first wall, a second wall and an edge joining the two walls, the mouth pipe extending outwardly of the collector at the edge between the walls, and the first and second walls joining the edge at an

interior angle of about 90°, whereby the mouth pipe may be held within the mouth of a subject taking a breath test with the



lips of the subject seated on the walls of the collector to form a breath-tight seal on the mouthpiece.

4,292,979

ALLERGY TESTING APPARATUS


Joseph T. Inglefield, Jr., 210 E. Broad St., Falls Church, Va. 22046, and William L. Mahood, 3404 Executive Ave., Falls Church, Va. 22042

Filed Apr. 9, 1979, Ser. No. 28,344

Int. Cl.³ A61B 10/00

U.S. Cl. 128—743

13 Claims



4,292,981

COMBINE HARVESTER CONVEYOR

Cyriel R. J. De Busscher, Sijsele-Damme, and Francois Van Herpe, Houtem (Vlierzele), both of Belgium, assignors to Sperry Corporation, New Holland, Pa.


Filed Jul. 1, 1980, Ser. No. 165,152

Claims priority, application United Kingdom, Jul. 6, 1979, 23774/79

Int. Cl.³ A01D 45/02; A01F 12/18

U.S. Cl. 130—27 F

6 Claims



1. Allergy-testing apparatus comprising:
 - a needle block comprising a block member having a plurality of separately-located-needle members extending from one side thereof, each of said needle members having a point on the distal end thereof;
 - vial-holding apparatus comprising a planar-plate member with a plurality of apertures formed therein, each aperture holding a single removable vial adapted to hold a liquid allergen; said apertures being positioned so that if said needle block is inserted on said holding apparatus with said one side of said block member facing said holding apparatus, then each of said needle members is separately received in a vial held in said plate member.

4,292,980

ELECTRODE ASSEMBLY FOR USE IN ELECTRIC FIELD THERAPY APPARATUS

Shotaro Suzuki, Chofu, Japan, assignor to Hakuju Institute for Health Science Co., Ltd., Tokyo, Japan

Filed Oct. 31, 1979, Ser. No. 89,923

Claims priority, application Japan, Oct. 31, 1978, 53-148924[U]

Int. Cl.³ A61N 1/04

U.S. Cl. 128—783

2 Claims

1. An electric field therapy apparatus comprising electrode means and a high voltage source, said electrode means including an insulating member on which the body of a patient being treated is received, and a plurality of elongate electrical conductors incorporated in said insulating member and extending transversely to the longitudinal axis of said member, said con-

ductors being spaced apart in serial relationship along the longitudinal axis of said insulating member and being insulated from one another by the insulation of said insulating member, and said apparatus further comprising means for selectively connecting said conductors at least two at a time to said high

voltage source such that an electric field is produced between the two connected conductors and the unconnected conductor or conductors located between the at least two connected conductors serve to confine the electric field to an area between the at least two connected conductors.

1. A combine harvester conveyor comprising:
 - a cylindrical rethresher portion having a rethresher rotor;
 - an auger portion including an auger tube extending from a first end adjacent said rethresher portion to a second end adjacent a grain pan;
 - means for guiding crop material to said auger portion, said means including a chute connected to said auger tube between said first and second ends; and
 - a shaft rotatably mounted in said harvester, said shaft extending between said first and second ends, said shaft rotatably mounted in said auger portion and carrying an auger member and an impeller, and said auger member having a first diameter portion and a second diameter portion greater than said first diameter portion, said first diameter portion extending from said first end to said chute and said second diameter portion extending from said chute to said second end.

4,292,982

LEAF STRIPPER FOR TOBACCO STALKS AND THE LIKE


Lawrence D. Butcher, P.O. Box 465, Point Pleasant, W. Va. 25550

Continuation-in-part of Ser. No. 846,664, Oct. 28, 1977, abandoned. This application Nov. 1, 1978, Ser. No. 956,667

Int. Cl.³ A01D 1/00

U.S. Cl. 130—30 R

74 Claims



1. A leaf stripper for tobacco stalks and the like including:
 - (a) generally horizontally disposed cooperating leaf stripping means
 - (b) means for moving said stripping means to form a generally horizontal nip
 - (c) means for supporting said stalk in a generally horizontal position having a generally horizontal axis
 - (d) stalk in-feeding means
 - (e) said means for supporting said stalk in a generally horizontal position mounted adjacent said leaf stripping means, and
 - (f) the axis of said nip and the horizontal axis of said stalk supporting means fixed in spaced relation relative to each other,
 - (g) whereby when said stalk is fed into said stalk supporting and in-feeding means, said leaves are engaged by said nip and angularly stripped from said stalk with respect to the direction of in-feeding.

4,292,983

FILTER CARTRIDGE ASSEMBLY


John A. Mensik, 124 Creekdale Rd., Walnut Creek, Calif. 94595

Filed Apr. 4, 1980, Ser. No. 137,513

Int. Cl.³ A24F 5/04

U.S. Cl. 131—187

4 Claims



1. A filter cartridge assembly for filtering tars from tobacco smoke comprising:
 - a cylindrical sleeve having an integral obstruction formed at one end, coaxial restricted inlet passage extending through said obstruction; and a filter core member received within said sleeve, said core member being formed with a central body portion including an annular enlargement, a stand-off contact projecting from an impingement surface at one end, and a cylindrical plug having a restricted outlet passage at the other end, the central body portion of said core member and inner surface of said sleeve defining a smoke passageway between the restricted inlet passage and the cylindrical plug, a transverse passage being

formed through the central body portion of said core member communicating the restricted outlet passage with the interior of said sleeve on the downstream side of said annular enlargement, said stand-off contact engaging the obstruction within said sleeve and spacing the impingement surface of said core in predetermined spaced relation to the opening of said restricted inlet passage, said cylindrical plug being received within the sleeve in sealing relation thereto and supporting said filter core member therefrom, the cross sectional area of the restricted outlet passage being smaller than the area between the inner surface of said cylindrical sleeve and the annular enlargement of said core member and selected to control the quality of filtration.

4,292,984

FILTER FOR CIGARETTE SMOKE

Hideo Sawada, Osaka; Koji Shinohara, Kawachinagano, and Makoto Shiga, Sakai, all of Japan, assignors to Daicel Ltd., Osaka, Japan

Filed Apr. 23, 1979, Ser. No. 32,428

Claims priority, application Japan, Apr. 22, 1978, 53/48245

Int. Cl.³ A24D 3/02, 3/04

U.S. Cl. 131—345

5 Claims

1. A cigarette filter comprising a bundle of cellulose acetate filaments, each filament being substantially uniform in its denier size, said bundle being composed of a plurality of filaments having at least two different filament denier sizes, said filaments running parallel to the longitudinal axis of said filter and being randomly distributed in the direction perpendicular to the longitudinal axis of said filter and wherein said filaments having at least two different filament denier sizes have a number average filament denier of not more than about 4 denier, and wherein the ratio of the weight average filament denier to the number average filament denier size of the bundle is at least about 1.03.

4,292,985

HAIR WAVING APPLIANCE

Zirou Itogawa, Takaishi, and Yoshiyuki Aoto, Yoa, both of Japan, assignors to Sharp Kabushiki Kaisha, Osaka, Japan


Filed Apr. 16, 1979, Ser. No. 30,434

Claims priority, application Japan, Apr. 14, 1978, 53-49907

Int. Cl.³ A45D 20/00

U.S. Cl. 132—9

11 Claims



a movable prop structure for securing said bonnet, said atomizer means and said controller means, said controller means being movable with respect to said bonnet; a supporting structure including a base member, adapted to be positioned on a floor surface, a stationary prop structure attached to said base member and extending upwardly therefrom, and said movable prop structure being slidable mounted within said stationary prop structure and attached to said bonnet to permit an adjustment of the height of said bonnet relative to said floor surface; and a rotatable supporting means including a sleeve extending through a housing for said controller and being rotatably positioned on said movable prop structure, a slide fitting being positioned adjacent to said sleeve including at least one raised strip extending therefrom, a restricting means including at least one protrusion adapted to mate with said raised strip of said slide fitting to limit the rotation of said controller housing relative to said bonnet.

4,292,986

ELECTRIC HAIR BRUSH

Nevenka Ergaver, and Rayko Ergaver, both of Toronto, Canada, assignors to Capella Inc., Freeport, The Bahamas


Filed Feb. 22, 1977, Ser. No. 770,549

Claims priority, application Canada, Feb. 2, 1977, 270926

Int. Cl.³ A45D 24/00

U.S. Cl. 132-11 R

6 Claims



1. In a hair styling brush having a handle and a heating element, an improved attachment therefor consisting of an open ended tube of heat conducting material securable over the heating element, a plurality of rows of radially projecting heat conducting teeth extending from the outer surface of said tube, each tooth having a base with a substantially rectangular cross section, parallel transverse faces and longitudinal edges convergent towards an apex, the length of each tooth from its base to its apex being from $\frac{1}{4}$ " to $\frac{1}{2}$ ", and a non-heat conducting cap secured to the end of said tube which is furthest from said handle to prevent inadvertent burning of the person using said brush, said teeth being disposed on that portion of said tube which is adjacent to said cap.

4,292,987

FINGERNAIL HONE


David W. Alley, Houston, Tex., assignor to Neal J. Mosely, Houston, Tex., a part interest

Filed May 1, 1980, Ser. No. 145,441

Int. Cl.³ A45D 29/00

U.S. Cl. 132-73

8 Claims



1. A fingernail hone for polishing and smoothing fingernails comprising
a body of ceramic material having a concave unglazed surface of substantially spherical curvature, and
said unglazed surface being substantially smooth, uncoated

and free from additional abrasive and constituting the sole abrasive surface for use in polishing and smoothing fingernails.

4,292,988

SOFT SHOCK PRESSURE PLUG


James W. Montgomery, Houston, Tex., assignor to Brown Oil Tools, Inc., Houston, Tex.

Filed Jun. 6, 1979, Ser. No. 45,988

Int. Cl.³ F16K 13/04

U.S. Cl. 137-68 R

15 Claims



1. Releasable closure apparatus for selectively closing and opening a flowway in a tubular conduit comprising:
a seating body having a main passage therethrough and adapted to be mounted in said tubular conduit with said main passage in register with said flowway, said seating body defining a seat for receipt of a plug member operative to close said main passage and support a pressure differential across said seat;
release control means releasably connected to one of said seating body or said tubular conduit and releasable upon the presence of a pressure differential across said seat in excess of a first magnitude to open bypass passageway means bypassing said seat to permit a relatively slow decrease in said pressure differential;
and lock means releasably locking said seating body to said tubular conduit, said lock means being releasable upon decrease of said pressure differential to a second magnitude to release said seating body from said tubular conduit.

4,292,989

FIRE SAFE SEAL

Italo Cazzaniga, and Ottorino Pasquinelli, both of Milan, Italy, assignors to Grove Valve and Regulator Company, Oakland, Calif.

Filed Dec. 3, 1979, Ser. No. 99,932

Claims priority, application Canada, Jun. 1, 1979, 328898

Int. Cl.³ F16K 13/04


U.S. Cl. 137-72

5 Claims

1. For a valve having a valve body, a closure member mounted in said body for movement between open and closed positions, a cylindrical, internal surface in said body adjacent to said closure member, a metallic seat ring slidable in said internal surface, the leading face of said seat ring being finished to seal off fluid flow when urged against said closure member, biasing means urging said seat ring against said closure member, and a resilient elastomer seal ring sealing between the outer surface of said seat ring and said internal surface; a fire-safe seal comprising:

- a metallic, emergency seal ring slidable in said internal surface and interposed between said seat ring and said biasing means;
- a sharp, internally chamfered, annular lip around the pe-

riphery of said emergency seal ring extending forwardly thereof;
an external chamfer around the trailing end of said seat ring at the periphery thereof;
said annular lip being receivable in the sliding clearance around said seat ring;



said external chamfer being at a slightly greater angle than said internal chamfer so that when said emergency seal ring is driven forward said annular lip is cammed radially outward by said external chamfer into said sliding clearance; and,
means to prevent operation of said emergency seal at temperatures below that which will destroy said elastomer seal ring.

4,292,990

HIGH PRESSURE UNLOADER VALVE


Ramon Pareja, Edina, Minn., assignor to Lear Siegler, Inc., Santa Monica, Calif.

Filed Feb. 7, 1980, Ser. No. 119,364

Int. Cl.³ F16K 11/00, 31/12

U.S. Cl. 137-115

6 Claims



1. A bypass/unloader valve comprising:

- (a) a valve body having an inlet port, an outlet port and a bypass port, said inlet port communicating with an inlet chamber formed in said valve body, said outlet port communicating with an outlet chamber formed in said valve body and said bypass port communicating with a bypass chamber formed in said valve body, said inlet, outlet and bypass chambers being generally aligned along the longitudinal axis of said valve body with said bypass chamber being disposed intermediate said inlet and outlet chambers, said valve body including an axially extending bore connecting said chambers;
- (b) a tubular plunger member disposed in said bore and journaled along its length for reciprocal motion therein, said tubular plunger having a radial aperture through its side wall in communication with said inlet chamber and an open end disposed in said outlet chamber;
- (c) a poppet valve carried by said plunger adjacent abutment means and disposed in said axially extending bore which, when closed, isolates said inlet chamber from said bypass chamber;
- (d) an axially displaceable seal assembly concentrically mounted on said tubular plunger for isolating said bypass chamber from said outlet chamber and exposed to the

pressure of fluid in said outlet chamber when fluid, under pressure, is introduced through said inlet port into said chamber and made to flow through said radial aperture and said tubular plunger;

(e) a ball check valve assembly disposed in said outlet chamber and secured to said open end of said tubular plunger for blocking fluid flow through said open end when the pressure in said outlet chamber exceeds that in said inlet chamber;

(f) means coupling said axially displaceable seal assembly to said poppet valve for urging said poppet valve to an open position when said outlet pressure exceeds a predetermined value; and

(g) spring means for applying a compressive force to said tubular plunger for urging said poppet valve through said abutment means to its closed position.

4,292,991

EROSION RESISTANT VALVE


Paul Wing, Hingham, Mass., assignor to Masoneilan International, Inc., Norwood, Mass.

Filed Dec. 17, 1979, Ser. No. 104,301

Int. Cl.³ F16K 43/00, 47/00

U.S. Cl. 137-329.05

15 Claims



1. A throttling valve comprising:

- A. a valve housing defining a chamber,
- B. means in the housing wall defining a first fluid passage into the chamber,
- C. means in the housing wall defining a second fluid passage into the chamber, said second passage being spaced from said first passage,
- D. tubular throttling means mounted to the housing wall, said throttling means being in fluid communication with the first passage, and having a mouth projecting into the chamber,
- E. a throttling plug having an end,
- F. means for positioning the plug inside the chamber substantially in line with the throttling means,
- G. means for moving an uneroded segment of the plug end between a first, extended position and a second, retracted position, such extended and retracted positions defining the plug stroke, and
- H. means for moving the plug progressively further toward the throttling means, independent of plug stroke, as fluid flowing into the valve erodes the end of the plug, thereby compensating for erosion of the plug end and changing the portion of the plug stroked between said extended and retracted positions whereby in the first, extended position the uneroded segment of the plug end obstructs the mouth of the throttling means to achieve maximum throttling effect.

4,292,992
VALVE FOR HANDLING SOLIDS CAPABLE OF
GAS-PRESSURE-TIGHT CLOSURE AGAINST A GAS
PRESSURE DIFFERENTIAL


Yeshwant K. Bhide, New Berlin, Wis., assignor to Allis-Chalmers Corporation, Milwaukee, Wis.

Filed Jul. 23, 1979, Ser. No. 59,966

Int. Cl.³ F16K 49/00, 25/00

U.S. Cl. 137—340

3 Claims



1. A valve,
 - a first plate member having an opening therein;
 - a second plate member having an opening therein, said first and second plate members cooperating to define a space therebetween and having their openings in axial alignment;
 - a slide gate having an opening therein movably supported with the space defined by said first and second plate members, said slide gate being selectively positionable within the space defined by said cooperating plate members in a manner to have its opening positioned in axial alignment with the openings in said first and second plate members, or into a position wherein a solid surface portion of said slide gate interrupts the communication between the axial aligned openings in said first and second plate members;
 - a first valve body portion having an axial opening, said first valve body portion having one end thereof secured in the opening in said first plate member in a manner to have the axis of its opening coincide with the axis of the opening in said first plate member;
 - a second valve body portion having an axial opening, said second valve body portion having one end thereof secured within the opening in said second plate member in a manner to have the axis of its opening coincide with the axis of the opening in said second plate member to thereby establish a flow through opening in the valve wherein the engagements of said first and second valve body portions in the openings in said first and second plate members cooperate to define first and second circular chambers;
 - a plurality of radially extending, spaced-apart passages formed in said first plate member constructed and arranged so as to communicate with said first circular chamber and an area at one side of said slide gate around the said flow through opening;
 - a plurality of radially extending passages formed in said second plate member constructed and arranged so as to communicate with said second circular chamber and an area at the other side of said slide gate around said flow through opening;
- means operably connected to selectively supply a fluid under pressure to said first and second chambers, whereby the area around said flow through opening may be purged of particle fines as desired regardless of said slide gate position to ensure a clear slide gate surface for the engagement of said inflatable seals;
- a first inflatable seal carried by said first valve body portion in a position surrounding the axial opening therein and to be engageable with the adjacent surface of said slide gate;
- a second inflatable seal carried by said second valve body

portion in a position surrounding the axial opening therein and to be engageable with the adjacent surface of said slide gate;

pressure fluid supply means operably connected to supply a fluid under pressure to said first and second inflatable seals to effect their engagement with the adjacent surface of said slide gate to effect a gas tight seal therebetween; and, actuating means operably connected to effect a selective positioning movement of said slide gate.

4,292,993
CLOSURE PLATE FOR HOT BLAST SLIDE VALVES
 Jacob Felthuis, Alkmaar, and Jacobus A. Rumphorst, Uitgeest, both of Netherlands, assignors to Hoogovens IJmuiden B.V., IJmuiden, Netherlands and Zimmermann & Jansen GmbH, Duren/Thld, Fed. Rep. of Germany, a part interest


Filed Nov. 9, 1979, Ser. No. 92,863

Claims priority, application Fed. Rep. of Germany, Nov. 9, 1978, 2848570

Int. Cl.³ F16K 49/00, 3/00

U.S. Cl. 137—340

6 Claims



1. In a closure plate for hot blast slide valves of the type having a hollow ring of box-like cross section cooled by running water, to whose inner circumference a body is attached by welding, which is formed by parallel plates and is likewise cooled by running water, the thickness of the body in axial direction being smaller than the axial length of the hollow ring, and the outer surfaces being coated to about the height of the front faces of the ring with refractory concrete, the coating being secured to these outer surfaces by anchoring means, the improvement comprising:

- (a) said anchoring means being attached to the outer surfaces of the plate body, and being V-shaped and extending into the refractory coating with their free flanks for at least $\frac{1}{2}$ and at the most $\frac{3}{4}$ of the coating thickness;
- (b) said anchoring means being arranged in regular distances in rows and columns extending normally to each other, the extending planes being alternately parallel and transverse to the direction of the respective row or column; and
- (c) the distance between the centers of said anchoring means corresponding to at least the thickness of the refractory coating layer.

4,292,994
RAW MILK TRANSFER SYSTEMS
 Julius T. Johnson, 348 - 20th St., S.E., Cedar Rapids, Iowa 52406, and Robert R. Johnson, 416 Jacolyn Dr., N.W., Cedar Rapids, Iowa 52405

Filed Feb. 25, 1980, Ser. No. 124,597


Int. Cl.³ B67D 5/02

U.S. Cl. 137—351

7 Claims

1. A system for transferring milk from a holding tank having an electric motor driven agitator to the tank of a milk transport vehicle which comprises milk transfer conduit means for conveying milk from the holding tank to the vehicle's tank, a pump driven by an electric motor for pumping milk through

said conduit means, an electrical circuit including power wires for energizing the electric motor of said agitator through an on-off switch, an electrical socket having a first set of socket contacts wired to said power wires whereby said first set of contacts are energized when said on-off switch is closed and are deenergized when said switch is open, an electrical connector having a first set of connector contacts removably engageable with said first set of socket contacts, an electrical component enclosure, an electrical timer in said enclosure, an electric cable with wires connecting said first set of connector contacts



with said timer whereby said timer is energized when said agitator's electric motor is energized, and wires connecting said pump's electric motor to a power source through open-close contacts closeable by said timer after it has run a predetermined time whereby said pump's electric motor is idle during the initial agitation of said milk in said holding tank while the timer runs its predetermined time and becomes energized at the expiration of said predetermined time by the closing of said open-close contacts by said timer to pump the milk from said holding tank to the vehicle tank.


4,292,995
LOCKING VALVE APPARATUS
 Mario Mazzola, New Canaan, Conn., assignor to Richardson-Vicks Inc., Wilton, Conn.

Filed Feb. 13, 1980, Ser. No. 121,028

Int. Cl.³ F16K 35/06

U.S. Cl. 137—384.2

11 Claims



1. In locking valve apparatus including a housing containing a flow control valve and a rotatable lock cylinder for locking the valve, said lock cylinder having a keyway extending therein from one end into which a key must be engagingly inserted when said lock cylinder is in an initial locked position in order to unlock the lock cylinder for turning the lock cylinder into a different position for unlocking the valve and wherein said housing includes a stationary cylindrical portion encircling the lock cylinder, the invention comprising:

a removable handle unit including a hollow portion defining a socket,

said hollow socket portion having an effective inside diameter (ID) slightly larger than the outside diameter (OD) of said stationary cylindrical portion of the valve housing for seating thereon in snug freely turning relationship,

a key mounted in said socket,

interengageable alignment means on said valve housing and on said hollow portion of the handle unit in predetermined positions for preventing said socket from being fully seated onto said portion of the valve housing unless said alignment means are interengaged for assuring insertion of the key into said keyway in proper position when said lock cylinder is in its initial position,

keeper means for preventing said handle unit from being removed from the valve housing when the handle unit is turned away from its initial position, and

stop means for limiting the turning movement of the handle to correspond with the desired turning limit of the lock cylinder.

4,292,996
STOP VALVE
 Jozsef Pataki, Jozsef Bucsi, István Bóna, Endre Szilvasi, András Gazdag, Antal Kóty, all of Budapest, and Ferenc Hidvegi, Torokbalint, all of Hungary, assignors to OMOV Orvosi Muszer es Vasipari Szovetkezet, Torokbalint, Hungary


Filed Oct. 24, 1979, Ser. No. 87,714

Claims priority, application Hungary, Oct. 24, 1978, PA 1331

Int. Cl.³ F15C 1/14; F16K 21/18

U.S. Cl. 137—393

3 Claims



1. A stop valve of the liquid level sensor type comprising a housing having an input stub, an exit opening (21) formed as a valve seat, characterized by a membrane space (1) opening upward and located in the valve housing (41), an auxiliary valve housing (42) with a membrane space (2) opening downward, on the upper side of the auxiliary valve housing (42) there is formed a membrane space (4) opening upward, and communicating with the lower membrane space (2) of the auxiliary valve housing (42) through a passage including the auxiliary valve seat (17), the auxiliary valve housing (42) is closed by a valve cover (43) including a membrane space (5) opening also downward, and the membrane spaces (1,2) located between the valve housing (41) and the auxiliary valve housing (42) are separated from each other by a membrane (3) carrying a main valve disc (14) and having a transit flow opening (23) therethrough, the membrane spaces (4,5) located between the auxiliary valve housing (42) and the valve cover (43) are separated from each other by a membrane (6) carrying auxiliary valve disc (7), a liquid level sensor means located within the valve housing and comprising said exit opening (21) constructed in a tapered fashion and extending beyond a portion of a suction pipe (11) and to the bottom part of which said suction pipe (11) reaching to the desired fluid level at the other end thereof is connected and, is in communication with the membrane space (5) located in the valve cover (43), said tapered exit opening (21) exerting an injector-like suction effect through said suction pipe (11) for sucking in only air as long as

the mouth of said suction pipe (11) is open, the membrane space (4) located at the upper side of the auxiliary valve housing (42) communicates with a fluid removal passage (20) when the rising fluid level closes the lower opening of said suction pipe (11), a low pressure condition is created in the membrane space (5) of the auxiliary valve housing (42) for closing said auxiliary valve disc (7), when the pressure increases in membrane space (2) for forcing the membrane (3) with the disc (14) thereof against the valve seat of exit opening (21), thereby closing said main valve disc 14.

4,292,997 CARTRIDGE VALVE

Georg Bernat, Menden, Fed. Rep. of Germany, assignor to Friedrich Grohe Armaturenfabrik GmbH & Co., Hemer, Fed. Rep. of Germany
PCT No. PCT/DE78/00014, § 371 Date Apr. 30, 1979, § 102(e) Date Apr. 30, 1979, PCT Pub. No. WO79/00114, PCT Pub. Date Mar. 8, 1979


PCT Filed Jul. 26, 1978, Ser. No. 47,713

Claims priority, application Fed. Rep. of Germany, Aug. 31, 1977, 27391547

Int. Cl.³ F16K 11/06

U.S. Cl. 137—454.6

6 Claims



1. A valve assembly comprising:

- a valve body having a central bore having a mean longitudinal axis, and having a plurality of inlet apertures and an outlet aperture;
- a valve cartridge adapted to be inserted into said central bore, said valve cartridge comprising first and second semicylindrical members, said second member, having a plurality of first apertures, each of said first apertures in communication with a corresponding one of said plurality of inlet apertures and a first outlet aperture in communication with said outlet aperture, said first and second members each having corresponding mating surfaces which are bonded together, said first and second members jointly forming a chamber about said mean axis; and
- first and second valve plates disposed within said chamber parallel to said mean axis, said first valve plate having a first plurality of in flow apertures each in communication with one of said first apertures and an outflow aperture in communication with said first outlet aperture, said second valve plate having a mixing passage adapted for communicating between said first plurality of inflow apertures and said outflow aperture, said second plate being movable relative to said first plate to control the flow and mixture of fluids; and means for moving said second plate parallel to said axis, said first and second members being arranged such that the interior surfaces of said first and second members pretension said first and second valve plates.

4,292,998 PRESSURE REDUCING VALVE

Michael E. Winiasz, Lorain, Ohio, assignor to The Clark-Reliance Corp., Cleveland, Ohio


Division of Ser. No. 867,114, Jan. 5, 1978, Pat. No. 4,197,877.

This application Jul. 30, 1979, Ser. No. 61,635

Int. Cl.³ F16K 31/34

U.S. Cl. 137—489.5

2 Claims



1. A pressure reducing valve for an expandable fluid at high pressure comprising a housing having an inlet passage leading to an inlet chamber, an outlet chamber and a discharge passage leading therefrom, a partition separating the inlet chamber from said outlet chamber, an opening in said partition providing communication between said inlet chamber and said outlet chamber, means for controlling the flow of said expandable fluid through said opening comprising a removable valve seat member disposed in said opening, said valve seat member having a valve seat positioned adjacent said inlet chamber, and a flow control portion extending downstream of said partition and into said outlet chamber, a valve spool slidably mounted relative to said valve seat member and having a valve head extending upstream from said valve seat, said valve head having a portion adapted to make sealing engagement with said main valve seat, means for controlling the position of said valve spool with respect to said valve seat comprising a spring in said inlet chamber urging said valve head into engagement with said valve seat, a sleeve disposed in said outlet chamber, and a piston operatively connected to said main valve spool and reciprocable in said sleeve, said valve seat member being slidably received in said housing and seated against an annular shoulder provided in the downstream side of said partition, said sleeve being disposed in said outlet chamber coaxial with said valve seat member, the upstream end of said sleeve engaging a shoulder on said valve seat to retain said valve seat member in position, the portion of said sleeve remote from said valve seat member being disposed in and fitting closely within an opening concentric with said valve seat member and being retained in said opening by a closure plate secured to said housing, said sleeve being dimensioned to retain said valve seat member firmly in place when said sleeve is engaged by said closure plate, and wherein upon removal of said closure plate from said housing, said sleeve, piston, valve spool, valve seat member and spring can all be removed from said housing through the opening that is normally closed by said closure plate, said flow control portion of said valve seat member comprises a plurality of radially extending, circumferentially spaced, internal grooves disposed downstream from said main valve seat, said grooves being separated by intermediate lands having arcuate inner surfaces lying in a circle that is coaxial with said main valve seat, said lands being in sliding engagement with a portion of said valve spool whereby said valve spool is slidably supported with respect to said valve seat member for movement coaxial with the axis of said main valve seat.

4,292,999

VALVE FOR TOY BALLOONS

Anton Szollmann, Augartenstrasse 21, 7500 Karlsruhe, Fed. Rep. of Germany


Filed Feb. 7, 1980, Ser. No. 119,351

Claims priority, application Fed. Rep. of Germany, Feb. 7, 1979, 2904514

Int. Cl.³ F16K 15/20; G09F 21/06; A63H 27/10

U.S. Cl. 137—560

5 Claims



1. A valve assembly for toy balloons and the like, comprising a container (6) having a bottom (5) and an upper open rim (9), a ring (1) having a bore, a thin valve flap (2) connected on one end of said ring by a flexible connecting portion (3), said valve flap extending laterally of and spaced from the bore of said ring, a tube (8), an annular valve seat (4) in said tube adjacent the inner end thereof, said tube (8) and annular valve seat (4) connected at the inner end and on the side of said tube to the bottom (5) of said container (6), said container (6) flaring conically in the upward direction and spaced in surrounding relation to said tube (8) forming an open top interior cavity therebetween, said ring connected in the inner end of said tube such that said annular valve seat (4) is disposed in front of and in moveable contact with said valve flap (2), said tube having an outer end projecting above the upper open rim (9) of said container, and a removable cap (10) adapted for sealing engagement with the outer end of said tube.

4,293,000

LOAD RESPONSIVE FLUID CONTROL VALVE

Tadeusz Budzich, 80 Murwood Dr., Moreland Hills, Ohio 44022

Continuation of Ser. No. 949,250, Oct. 6, 1978, Pat. No. 4,222,409.

This application Nov. 1, 1979, Ser. No. 90,249

The portion of the term of this patent subsequent to Sep. 16, 1997, has been disclaimed.


Int. Cl.³ F15B 13/08

U.S. Cl. 137—596.2

9 Claims

1. A valve assembly supplied with pressure fluid by a pump, said valve assembly comprising a housing having a fluid inlet chamber, a fluid supply chamber, first and second load chambers, positive load pressure sensing means, negative load pressure sensing means, and exhaust means, first valve means for selectively interconnecting said fluid load chambers with said positive load pressure sensing means and said negative load pressure sensing means, said supply chamber, and said exhaust means, first variable metering orifice means responsive to movement of said first valve means between said fluid supply chamber and said load chambers, second variable metering orifice means responsive to movement of said first valve means between said load chambers and said exhaust means, second valve means having inlet fluid throttling means between said fluid inlet chamber and said fluid supply chamber and control means of said fluid throttling means having force means responsive to fluid pressure in said positive load pressure sensing means, deactivating means of said force means having valve means operable to connect said second valve means with said

exhaust means, exhaust relief valve means in said exhaust means, and isolating means on said second valve means having



means responsive to pressure upstream of said exhaust relief valve means.

4,293,001

LOAD RESPONSIVE FLUID CONTROL VALVE

Tadeusz Budzich, 80 Murwood Dr., Moreland Hills, Ohio 44022

Division of Ser. No. 949,250, Oct. 6, 1978, Pat. No. 4,222,409.


This application Jan. 30, 1980, Ser. No. 104,083

The portion of the term of this patent subsequent to Oct. 31, 1995, has been disclaimed.

Int. Cl.³ F15B 13/08

U.S. Cl. 137—596.13

8 Claims



1. A valve assembly supplied with pressure fluid by a pump, said valve assembly comprising a housing having a fluid inlet chamber, a fluid supply chamber, first and second load chambers, at least one outlet chamber, positive load pressure sensing means operable to transmit a control signal to said pump, negative load pressure sensing means between one of said load chambers and said outlet chamber, and fluid exhaust means, first valve means for selectively interconnecting said fluid load chambers with said positive load pressure sensing means, said negative load pressure sensing means, said fluid supply chamber and said fluid outlet chamber, first variable metering orifice means responsive to movement to said first valve means between said fluid supply chamber and said load chambers, sec-

ond variable metering orifice means responsive to movement of said first valve means between at least one of said load chambers and said outlet chamber, second valve means having inlet fluid throttling means between said fluid inlet chamber and said fluid supply chamber responsive to pressure differential across said first variable metering orifice means, said second valve means having inlet fluid isolating means between said fluid inlet chamber and said fluid supply chamber, synchronizing means having means responsive to pressure in said negative load pressure sensing means and means responsive to pressure in said supply chamber, said synchronizing means having actuating means of said inlet fluid isolating means, and fluid replenishing means operable to supply fluid flow from said fluid exhaust means to one of said load chambers which is not pressurized when said fluid isolating means isolate said fluid supply chamber from said fluid inlet chamber.

4,293,002

ELECTRICALLY OPERATED FLUID CONTROL DEVICE
Yoshiki Moriyama, Okazaki, and Masayuki Kuwana, Aichi, both of Japan, assignors to Toyooki Kogyo Kabushiki Kaisha, Okazaki, Japan


Filed Dec. 4, 1979, Ser. No. 100,134

Claims priority, application Japan, Dec. 7, 1978, 53-151835

Int. Cl.³ F15B 13/043

U.S. Cl. 137—625.64

7 Claims



1. In an electrically operated fluid control device for controlling fluid flow under high pressure to be supplied into a fluid actuator, the control device comprising:

- (a) a housing provided with: (i) an inlet passage for connection to a source of fluid under high pressure, (ii) an outlet passage for connection to said fluid actuator, (iii) a drain passage for connection to a low pressure area, and (iv) a cylindrical main bore, said main bore being, at the intermediate portion thereof, in open communication with each of said inlet, outlet and drain passages;
- (b) first and second pilot passages provided through said housing for communicating one end portion of said main bore with said inlet and drain passages respectively;
- (c) a main spool axially reciprocable within the intermediate portion of said main bore to control the flow of fluid passing through said inlet, outlet and drain passages, said main spool forming a fluid chamber at one end thereof within said end portion of said main bore;
- (d) valve means disposed within said end portion of said main bore for selectively connecting said fluid chamber to said first and second pilot passages;
- (e) resilient means for biasing said main spool towards said fluid chamber; and
- (f) an electromagnetic actuator fitted to said housing and including a movable core operatively connected with said valve means upon energization of said electromagnetic actuator; the improvement wherein said valve means comprises:

(A) a stationary pilot valve body disposed within said end portion of said main bore to define said fluid chamber at its inner wall, said pilot valve body comprising (i) an inner bore coaxial with said main spool, and (ii) inlet, outlet and drain ports respectively communicating said inner bore with said first pilot passage, said fluid chamber, and said second pilot passages;

(B) a pilot spool axially slidable within the inner bore of said pilot valve body for selectively connecting said outlet port with said inlet and drain ports through said inner bore,

said pilot spool being operatively connected to said movable core of said electromagnetic actuator; and
(C) a spring disposed within the inner bore of said valve body for biasing said pilot spool toward said movable core.

4,293,003

MIXTURE CONTROL DEVICE FOR SERVICE WATER INSTALLATIONS HAVING A LOW SUPPLY TEMPERATURE

Karlheinz Raetz, Brunswick, Fed. Rep. of Germany


Filed Sep. 6, 1979, Ser. No. 72,923

Claims priority, application Fed. Rep. of Germany, Sep. 8, 1978, 2839152

Int. Cl.³ F16K 11/22

U.S. Cl. 137—637.4

8 Claims



1. A mixture control device for use in connection with a service water installation having a relatively low supply temperature, comprising:

- a housing enclosing a mixing chamber and having three inlets and an outlet, said inlets being connectable respectively to a hot water conduit, a warm water conduit and a cold water conduit and said outlet communicating with said mixing chamber;

control means arranged between said inlets and said chamber, said control means being operable between a first temperature control range in which it establishes a communication of said hot water inlet and said warm water inlet with said chamber while closing said cold water inlet and a second control range in which it establishes a communication of said warm water water inlet and of said cold water inlet with the chamber while closing said hot water inlet; said control means including two superimposed disks, one of the disks being a stationary one having three inlet bore holes arranged on a concentric circle at predetermined angular intervals relative to the center of the disk and each communicating with one of said inlets, the other disk being rotatable about its center and having three control bore holes arranged on a similar concentric circle at such angular intervals relative to each other as to overlap always two adjacent inlet bore holes in said stationary disk.

4,293,004

ELECTRONIC VALVE ASSEMBLY FOR GLASSWARE FORMING MACHINERY

Earl L. Lowe, Winchester, Ind., assignor to Ball Corporation, Muncie, Ind.

Continuation-in-part of Ser. No. 12,862, Feb. 16, 1979. This application Aug. 20, 1979, Ser. No. 68,276


Int. Cl.³ F15B 13/08

U.S. Cl. 137—884

32 Claims

1. A valve block for an IS glassware forming machine, adapted for cooperation with at least one valve means for selectively effecting fluid communication between a first port and a second port thereof, and for selectively effecting fluid communication between said second port and a third port thereof, said valve block comprising:

a body;
first, and second plenums formed in said body, said first and second plenums being respectively coupled to fluid supplies at differing pressures;
a first fluid passageway formed in said body, communicating with said valve means first port;
an output passageway, formed in said body, communicating



with said valve means second port, said output passageway being adapted for connection to said IS glassware forming machine;
an exhaust means for exhausting said fluid, communicating with said valve means third port; and
selector means, disposed in said valve means for selectively coupling said first or second plenums to said first fluid passageway.

4,293,005


APPARATUS FOR FASTENING INSULATION TO A PIPE
James J. Kelly, 2310 Clearview La., Aston Township, Delaware County, Pa. 19014

Filed Apr. 23, 1979, Ser. No. 32,169

Int. Cl.³ F16L 9/14, 9/22

U.S. Cl. 138—149

9 Claims



1. An insulation fastening system for a pipe surrounded by a layer of insulation comprising at least one crib, said crib including a sleeve and first and second members, said sleeve lying along the outer wall of the pipe that is being insulated, each of said members including first and second portions, said first and second portions being laterally spaced from each other and being connected by a third portion, said first portions being disposed adjacent to the outer wall of said layer of insulation, means for securing said first portions to said pipe, means for securing said second portions to the outer wall of said layer of insulation, at least the second portion of each of said members

being spaced from each other on said layer of insulation, and said first portion of each of said members are rotatably supported by said sleeve so that said members can be pivoted to bring said second portions adjacent the outer wall of said layer of insulation.

4,293,006

PILE WARP THREAD UNWINDING DEVICE FOR A TERRY CLOTH LOOM


Erich Peter, Lindau, Fed. Rep. of Germany, assignor to Lindauer Dornier Gesellschaft mbH., Fed. Rep. of Germany

Filed Mar. 5, 1979, Ser. No. 17,336

Int. Cl.³ D03D 49/10

U.S. Cl. 139—102

7 Claims



1. In a pile warp thread-unwinding device for a terry cloth weaving machine with an intermittent drive for a pile warp beam controlled by an oscillatable feeler for the pile warp threads, the improvement comprising two rotatable reversing means mounted in a stationary manner following the pile warp beam in the drawingoff direction of the threads, said oscillatable feeler being positioned therebetween and movable between two limit positions, said feeler in one limit position thereof being located essentially in a plane formed by the pile warp thread extending in a straight path between said two reversing means, means urging said feeler in a direction out of said one limit position toward said other limit position so as to deflect said pile warp threads from said straight path, and means on said feeler for influencing electrical control switches for the pile warp beam drive in the limit positions of the feeler.

4,293,007

HOLDING DEVICE FOR THE ELECTRICAL CONTACT ELEMENTS OF A WRAP STOP MOTION OF A WEAVING MACHINE

Hans Baumann, Horgen, Switzerland, assignor to Sulzer Brothers Limited, Winterthur, Switzerland

Filed Apr. 25, 1980, Ser. No. 143,772

Claims priority, application Switzerland, May 8, 1979, 4299/79

Int. Cl.³ D03D 51/28


U.S. Cl. 139—358

15 Claims

1. A holding device for electrical contact elements of a warp stop motion of a weaving machine, said holding device comprising

- a fixedly mounted support;
- a plate-shaped element movably mounted on said support

and having a plurality of slots at one end for receiving a plurality of contact elements therein; and



a shaped body movably mounted between said element and said support for displacing said element relative to said support.

4,293,008

RATIO GRADUATE FOR USE WITH POST-MIX BEVERAGE DISPENSER


Charles E. Coleman, Atlanta, Ga., assignor to The Coca-Cola Company, Atlanta, Ga.

Filed Dec. 10, 1979, Ser. No. 101,523

Int. Cl.³ B67D 5/22; B65B 1/04

U.S. Cl. 141—95

8 Claims



1. In a system for measuring the volume ratio of a first fluid to a second fluid using a ratio graduate and an on-off valve means by dispensing the first fluid and second fluid into said graduate, the improvement comprising:

- said ratio graduate having;
- (a) a first fluid chamber for containing said first fluid having a minimum line and a maximum line disposed thereon at a predetermined distance from each other; and
 - (b) a second fluid chamber for containing said second fluid adjacent to said first fluid chamber, said second fluid chamber having graduations indicative of various first fluid to second fluid volume ratios disposed thereon;
 - (c) said minimum and maximum lines and said first fluid to second fluid ratio graduations being related such that when said first fluid is at a level between said minimum line and said maximum line, the first fluid to second fluid ratio may be read directly off said first fluid to second fluid ratio graduation to provide a first fluid to second fluid ratio within a predetermined accuracy determined by the predetermined distance between said minimum line and said maximum line, wherein said valve means is turned off to stop the flow of said first and second fluids when said first fluid level reaches said minimum line.

4,293,009
PRESSURIZED GAS FILLING HEAD
Hugh C. Fulton, 2A Akatea Rd., Glen Eden, Auckland, New Zealand


Filed Sep. 11, 1979, Ser. No. 74,333

Claims priority, application New Zealand, Sep. 12, 1978, 188395

Int. Cl.³ B65B 3/04

U.S. Cl. 141—311 R

2 Claims



1. A gas cylinder filling head having a body incorporating a clamp bar spaced outwardly thereof; said body including:
 - a gas inlet port adapted for connection to a pressurized gas supply, and a gas outlet port disposed towards and spaced inwardly of the clamp bar;
 - a control bore between said inlet and said outlet ports, said control bore housing a two position, ON and OFF respectively, reciprocally operative control valve member, the ends thereof being disposed on the exterior of the body to form control buttons;
 - a delay chamber having a spool valve reciprocally mounted therein, said spool valve dividing said delay chamber into:
 - (i) an inlet-sub-chamber
 - (ii) an outlet-sub-chamber, and
 - (iii) a bobbin-sub-chamber;
 the inlet-sub-chamber being at one end of the delay chamber with the bobbin-sub-chamber at the other end of the delay chamber, the bobbin-sub-chamber having a larger cross-sectional area than the inlet-sub-chamber, a restricted passage extending through said spool connecting said inlet-sub-chamber to said bobbin-sub-chamber; means for biasing said spool valve towards said bobbin-sub-chamber; the outlet-sub-chamber being adapted to interconnect the inlet-sub-chamber to the gas outlet when the spool valve moves away from the bobbin-sub-chamber and towards the inlet-sub-chamber; an annular shaped recess formed in said body and adjacent the gas outlet port; said recess communicating with said bobbin-sub-chamber; a bobbin slidably mounted within said recess and capable of extending and clamping against the inlet of a gas cylinder to be charged when gas pressure is applied to said bobbin-sub-chamber and hence to said recess; the bobbin having a bore therethrough which forms an extension of the gas outlet port when the bobbin is extended;
 - a gas inlet passage extending from said gas inlet port to said inlet-sub-chamber of the delay chamber and capable of being switched ON or OFF by said control valve member; and
 - a pressure release passage connecting the gas outlet port to atmosphere and capable of being switched ON or OFF by said control valve member in opposition to the switching of said gas inlet passage;
- whereby in use, switching of the control valve member to the ON position will allow gas pressure applied to the inlet port to firstly extend the bobbin into its clamping position and then to move the spool valve away from the bobbin-sub-chamber to connect the inlet-sub-chamber via the outlet-sub-chamber to the gas outlet port to enable gas to flow from said inlet port to said outlet port.


4,293,010
ADJUSTABLE VOLUMETRIC FILLER HEAD
Michael E. Winiasz, Lorain, Ohio, assignor to A-T-O Inc., Willoughby, Ohio

Filed Oct. 25, 1979, Ser. No. 88,134

Int. Cl.³ B65B 3/32

U.S. Cl. 141—392

15 Claims



1. A filler head for delivering a preselected volume of product to a container comprising a charging cylinder, piston means movable in said cylinder to define therewith a product chamber, means for delivering product under pressure to said chamber, said piston means being movable under product pressure in a direction enlarging said chamber, means limiting movement of said piston means in said chamber-enlarging direction thereby determining said preselected volume, a tubular body, means defining a first product passage between said body and said chamber, a first valve seat around said first passage, a piston valve movable in said tubular body, said valve having a first valve seal at one end engageable against said first valve seat in a first position of said valve, means defining a second product passage from said body, a second valve seat around said second passage, a second valve seal at the opposite end of said piston valve engageable against said second valve seat in a second position of said valve, means defining a third product passage through said valve, said third passage having a product inlet opening through said first valve seal and a product outlet opening adjacent said opposite end of said valve, means for moving said valve between said first and second positions, said product delivering means communicating with said body between said valve and said first passage for delivery of product to said chamber in said second position of said valve, said valve interrupting the delivery of product to said chamber when in said first position, and means for moving said piston means in a direction discharging product through said first and third passages and through said second passage when said valve is in said first position.

4,293,011

RAFTER CUTTING MACHINE

Thomas M. White, Hartland, Vt.; Edwin A. Barton, East Hampton, Conn., and Jesse P. Ware, Kittery Point, Me., assignors to Vermont Log Buildings, Inc., Hartland, Vt.

Filed May 21, 1979, Ser. No. 40,686


Int. Cl.³ B27C 9/04; B27M 3/00

U.S. Cl. 144—3 R

18 Claims

1. Apparatus for cutting and notching beams to predetermined specification comprising spaced loading and discharge stations for receiving a beam for treatment and for discharging the beam which has been treated, conveyor means at the receiving station for moving a single beam longitudinally onto

the receiving station, conveyor means at the discharge station for moving a single treated beam longitudinally of the discharge station, transfer means supported for reciprocal movement between the receiving and discharge stations, said transfer means being structured to, at the receiving station, take hold of a single beam at longitudinally-spaced position lengthwise thereof and, at the discharge station, to release the beam, means operably connected to the transfer means for effecting its reciprocation and for causing the transfer means to on the one hand take hold of a mean at the receiving station and on the other hand to release the treated beam at the discharge



station, a plurality of operating instrumentalities, means supporting the operating instrumentalities above the path of travel of the beam from the receiving station to the discharge station in a position to be engaged by the beam as it is moved from one station to the other, said instrumentalities being positioned to produce the required cuts in precisely predetermined positions as controlled by the position of the beam at the receiving station and the transfer of said prepositioned beam from said predetermined position at the receiving station relative to the operating instrumentalities, and means at the receiving station for controlling the longitudinal portion of the beam relative to said instrumentalities.

4,293,012


LOG SPLITTER WITH OVERLOAD PROTECTION

Michel A. Pierrat, 48 Farrwood Dr., Andover, Mass. 01810
Continuation-in-part of Ser. No. 873,060, Jan. 27, 1978, abandoned. This application Jun. 29, 1979, Ser. No. 53,198

Int. Cl.³ B27L 7/00

U.S. Cl. 144—193 A

6 Claims



1. In a log splitter comprising first and second guide members, means supporting said guide members in spaced parallel relationship, a support positioned between said guide members for supporting a log to be split, a carriage extending between

said guide members, and a splitting wedge carried by said carriage, the improvement comprising drive means for moving said support into closing relationship with said wedge including a hydraulic jack having a supply of hydraulic fluid, a high pressure compartment, a one-way valve communicating with said high pressure compartment and arranged to permit the flow of hydraulic fluid into said high pressure compartment, a low pressure reservoir, a cylinder communicating with said one-way valve, a piston in said cylinder, arranged to pump said fluid from said low pressure reservoir through said one-way valve into said high pressure compartment, and pressure-responsive relief valve means communicating with said cylinder at a point on the side of said one-way valve opposite from said high pressure compartment and arranged to permit the flow of said fluid from said cylinder into said low pressure reservoir whenever the pressure in said cylinder exceeds a predetermined level.

4,293,013


LOG SPLITTER

Harold E. Phelps, 1916 Cornett Place, and Byron J. Gansley, 1049 Spring Meadows, both of Kissimmee, Fla. 32741
Filed Jul. 30, 1979, Ser. No. 61,843

Int. Cl.³ B27L 7/00

U.S. Cl. 144—193 A

2 Claims



1. A portable log splitter comprising: a longitudinally extending base member, a blade assembly fixed on said base member for penetrating one end of a log, a hydraulic actuator mounted on said base member, a source of hydraulic fluid pressure including a rotatable hydraulic pump, power means for said pump including a sprocket drivingly connected to said pump, a guide bar in alignment with said sprocket and having a mounting slot, said slot receiving a chain saw engine on said guide bar for driving said pump and a chain extending over said guide bar and between said engine and said sprocket for driving said pump, valve control means disposed between said pump and said actuator and being manually operable to control the delivery of hydraulic fluid to extend said actuator into engagement with a log and force it into engagement with said blade assembly to split said log and being operable in an opposite direction to retract said actuator said engine being radially detachable from said guide bar for transport purposes and for use in a chain saw assembly.

4,293,014

BARKING DRUM

Lorentz Lundmark, Ersmark, Sweden, assignor to Skega Aktiebolag, Ersmark, Sweden
Filed Oct. 23, 1979, Ser. No. 87,563

Claims priority, application Sweden, Feb. 11, 1978, 7811372


Int. Cl.³ B02C 17/22

U.S. Cl. 144—208 B

7 Claims

1. In a rotary barking drum having a shell plate, internal longitudinal laterally spaced-apart barking means, longitudinally spaced-apart bark outlets in the shell plate at locations between the barking means and wear rubber elements on the barking means, an improved device for attaching the wear rubber elements comprising: pairs of laterally spaced-apart mounting bars located parallel to the barking means and inside the shell plate between the barking means so as to form channels extending between the mounting bars to the respective bark outlets, said channels having widths which increase

toward the bark outlets, said mounting bars having flanges which engage in grooves in adjacent rubber wear elements and thereby retain the elements against the barking means; means



connecting the mounting bars of each pair together; and means attaching each pair of mounting bars to the shell plate, said attaching means including elements extending through the bark outlets and locked against the outside of the bark outlets.

4,293,015


INSULATED BEVERAGE COZY

Bonnie McGough, 1104 Teton Ave., Caldwell, Id. 83605
Filed Jun. 10, 1980, Ser. No. 158,168

Int. Cl.³ B65B 11/00

U.S. Cl. 150—52 R

4 Claims



1. A jacket for use with cold drinking utensils comprising: a cylindrical body open at its top and having a bottom; and said cylindrical body having an inner and outer wall formed of resilient fabric material fastened together so as to form a plurality of compartments between said inner and outer wall; and insulation material disposed within said compartments formed of resilient fabric; and a circular elastic band attached to the opening of said cylindrical body for snugly fitting around the drinking utensil.

4,293,016

PNEUMATIC TIRE ASSEMBLY

Dennis E. Bible, Stow; Richard N. Crano, Akron, and John A. Welch, Cuyahoga Falls, all of Ohio, assignors to The General Tire & Rubber Co., Akron, Ohio

Filed Mar. 24, 1980, Ser. No. 133,178

Int. Cl.³ B60C 17/04

U.S. Cl. 152—158

3 Claims

1. A pneumatic tire assembly capable of supporting a vehicle wheel rolling for a limited distance when the air contained in said assembly has escaped, including a wheel rim with flanges forming bead seats on the lateral sides of said rim, a pneumatic tire having bead portions mounted on said bead seats, and an annular elastomeric insert extending around the circumference of said rim inside said pneumatic tire, said insert having radially inner edges mounted on the flanges of the rim and engaging said beads of the said pneumatic tire, said pneumatic tire assembly characterized by said annular insert having

(1) a plurality of spaced apart first sections disposed about the circumference of said insert, each of said first sections having a rectangular radially outward wall substantially concentric with the tread of said pneumatic tire and hav-

ing four side edges, two of said side edges being each substantially parallel with one of said radially inner edges of the insert engaging said beads of said tire, each of said first sections also having a first pair of sidewalls extending between said two side edges of said radially outward wall and said radially inner edges of the insert, and further having a second pair of sidewalls extending radially inwardly from the other two of said four side edges of said rectangular radially outward wall, each of said sidewalls



being substantially perpendicular to said radially outward wall, and

(2) a plurality of circumferentially spaced second sections connecting said first sections together, said second sections having lateral walls extending between said second pairs of side walls of said first sections and extending radially outwardly and axially toward each other from the radially inner edges of said insert engaging said beads of said tire.

4,293,017

DUAL-CHAMBER PNEUMATIC TIRE

Donald M. Lambe, 111 Abbey, Birmingham, Mich. 48008

Continuation-in-part of Ser. No. 856,294, Dec. 1, 1977,

abandoned. This application Sep. 27, 1979, Ser. No. 79,315

Int. Cl.³ B60C 5/06, 17/00

U.S. Cl. 152—339

2 Claims



1. A dual-chamber tubeless pneumatic tire consisting of a single casing mounted on a conventional wheel rim, said casing comprising a tread portion forming a rolling surface for engagement with the ground, relatively flexible sidewalls integrally attached at edges of said tread portion, a peripheral substantially toroidal outer chamber in said casing disposed internally proximate the rolling surface of said casing, said toroidal outer chamber being substantially elliptical in cross-section, an annular inner air chamber in said casing disposed concentrically to said outer toroidal chamber, an annular elastically deformable resilient partition wall extending internally from one sidewall to the other sidewall of said casing and separating said outer air chamber from said inner air chamber, said partition wall having a width substantially larger than the width of said tread portion and being elastically bowed toward said inner air chamber, and means for separately inflating said outer air chamber and said inner air chamber at different pressures whereby the pressure in said outer chamber is greater

than the pressure in said inner chamber, said inflating means comprising a first air valve disposed through said rim in direct communication with said inner air chamber and a second air valve disposed through said rim placed in communication with said outer air chamber by a flexible conduit disposed through said inner air chamber and connected to an orifice through said partition wall, wherein said outer chamber is formed by a toroidal inner tube peripherally disposed in said casing and held in position by a pair of symmetrically disposed projecting annular beads on the internal surface of the sidewalls of said casing and said inner tube has a pair of lateral projecting annular beads engaged each in a corresponding annular groove in the surface of said beads on the internal surface of the sidewalls of said casing.

4,293,018

TIRE FOR TWO-WHEEL VEHICLE

Gerard Dubois, Sayat, France, assignor to Compagnie Generale des Etablissements Michelin, Clermont-Ferrand, France


Filed Apr. 8, 1980, Ser. No. 138,339

Claims priority, application France, Apr. 9, 1979, 79 09122

Int. Cl.³ B60C 5/04, 15/04, 21/08

U.S. Cl. 152—347

5 Claims



1. A tire for two-wheel vehicles comprising a casing formed of a crown with a tread and two sidewalls each terminating in a bead intended to rest on a tire rim and an inner tube glued in manually removable manner to the inner wall of the casing in the region of the crown, said tire being characterized by the fact that, in uninflated state, the glued inner tube has a wall of constant thickness and is glued under circumferential tension to the casing so that the inside equatorial radius of the glued inner tube is greater than the outside radius of the flanges of the rim and so that the cross section of the glued inner tube has an oval contour whose equatorial radial height is less than both the maximum axial width of said contour and the average diameter of said contour.

4,293,019

BREAKER FOR RADIAL TIRE

Luigi Maiocchi, Milan, Italy, assignor to Industrie Pirelli S.p.A., Milan, Italy

Filed Mar. 8, 1979, Ser. No. 18,666

Claims priority, application Italy, Mar. 9, 1978, 20994 A/78

The portion of the term of this patent subsequent to Oct. 2, 1996, has been disclaimed.


Int. Cl.³ B60C 9/20

U.S. Cl. 152—361 R

6 Claims

1. A pneumatic tire for motor vehicles comprising a carcass, a tread band and a reinforcing annular structure inserted between said carcass and said tread band, said reinforcing annular structure comprising at least three layers of metal cords, said layers being substantially as wide as the tread band, two layers which are arranged in a radially inner position with respect to the third layer comprising metal cords having an ultimate elongation of about 3%, said metal cords being parallel to one

another in each layer and crossed with respect to those of the other layer, said cords in said two layers being symmetrically inclined with respect to the longitudinal direction of the tire and forming an angle between 5° and 30°, the third layer being arranged in a radially outer position and comprising metal cords having an ultimate elongation between 4% and 8%, the cords of said third layer being substantially parallel to one



another and arranged substantially parallel to the longitudinal direction of the tire, said third layer consisting essentially of a central portion extending astride of the center line and having a width between 40% and 80% of the total width of said layer, and two lateral portions extended side by side with said central portion, each of said lateral portions having a greater resistance to tension and compression stresses than that of said central portion.

4,293,020


TIRE CHANGING APPARATUS

Charles G. Leeper, Antioch, and John F. Wood, Nashville, both of Tenn., assignors to Hennessy Industries, Inc., Elk Grove Village, Ill.

Filed Sep. 7, 1978, Ser. No. 940,831
Int. Cl.³ B60C 25/06

U.S. Cl. 157—1.28

11 Claims



1. A tire changer comprising: a base having a lower extremity to support the base on an underlying surface; a table top having wheel securing means; means mounting said tabletop on said base for pivotal movement about a generally horizontal axis between a generally horizontal, tire changing position and a generally vertical, wheel loading and unloading position whereat said securing means is in sufficiently close proximity to the underlying surface supporting the base so as to be engageable with and securable to an upright wheel and tire on the underlying surface; and means for selectively pivoting said table top between said position.


4,293,021
SUPPORT FOR TRAVERSING WINDOW COVERING DEVICE

Joseph P. Arena, 254-43 Pembroke Ave., Great Neck, N.Y. 11020

Filed Jun. 6, 1979, Ser. No. 45,938
Int. Cl.³ E06B 9/38

U.S. Cl. 160—178 R

18 Claims



1. In a vertical blind which includes a plurality of vanes, a plurality of carriers for transversely supporting the vanes, a track structure in which the carriers are transversely mounted, means including a horizontally-extending rod for rotating the vanes and means including a cord for traversing the carriers, the improvement comprising a support for supporting the horizontally-extending rod between predetermined locations in the track structure, the support comprising means for transversely mounting the support in the track structure, an opening in the support through which the horizontally-extending rod extends such that the support in cooperation with the track structure slidably supports the rod between the predetermined locations, means for frictionally engaging the cord such that the support is traversed between the predetermined locations upon movement of the cord, and cooperating means associated with the support and the track structure for limiting movement of the support between the predetermined locations, the engaging means frictionally engaging the cord to traverse the support between the predetermined locations upon movement of the cord to traverse the carriers along a portion of the track structure and releasing the support from engagement with the cord in cooperation with the limiting means at the predetermined locations such that the support remains stationary with respect to the track structure at the predetermined locations upon further movement of the cord.

4,293,022

METHOD FOR CONTINUOUS CASTING OF METAL STRIPS

Salvador Arena, Caminho do Mar Ave., 2562 Rudge Ramos, Sao Bernardo do Campo - Sao Paulo, Brazil


Continuation-in-part of Ser. No. 859,263, Dec. 9, 1977, abandoned. This application Oct. 10, 1979, Ser. No. 83,269
Claims priority, application Brazil, Sep. 20, 1977, 7608417
Int. Cl.³ B22D 11/12; B21B 1/24; B21C 47/02

U.S. Cl. 164—476

1 Claim

1. A method of continuously forming flat metal strips comprising the steps of: continuously casting two semi-cylindrical members simultaneously from one circular die provided with a generally cylindrical mandrel extending into a cylindrical casting cavity defined by said die, said mandrel having external surface portions in contact with said cylindrical die thereby cooperating to define two semi-cylindrical cavities for casting said two semi-cylindrical members, continuously drawing the two semi-cylindrical members between a first set of rollers disposed downstream of said die with the rollers exerting pressure on exterior surfaces of said two members to press them together to form two flat metal strips,

continuously withdrawing and separating the two flat metal strips by pulling on each of said strips by a respective second set of at least one pair of rollers arranged downstream of said first set of rollers,



winding each said separated flat metal strip around a respective spool, and cutting the flat metal strips after winding to a preselected length with a cutting tool positioned between the first and second sets of rollers.

4,293,023

METHOD AND DEVICE FOR THE MANUFACTURE OF METAL BANDS


Hans-Reiner Hiltzinger, Maintal, and Hans Hillmann, Rodenbach, both of Fed. Rep. of Germany, assignors to Vacuumschmelze GmbH, Fed. Rep. of Germany

Filed Sep. 4, 1979, Ser. No. 72,094

Claims priority, application Fed. Rep. of Germany, Sep. 29, 1978, 2842421; Oct. 26, 1978, 2846628
Int. Cl.³ B72D 11/06

U.S. Cl. 164—479

8 Claims



1. In a method for the manufacture of straight metal bands, particularly of an amorphous metal alloy, where a stream of the molten metal from a supply container strikes a quickly moving surface of a cooling body having a width transverse to said melt stream from which it is then removed as a substantially straight band after solidification, the improvement comprising:

additionally moving said supply container transversely relative to and substantially across the entire width of said cooling body at right angles to the direction of the melt stream for optimum utilization of the cooling property of the entire surface of said cooling body, wherein the velocity of the transverse movement of the melt stream is sufficiently small with respect to the surface velocity of the cooling body for generating a substantially straight metal band on said cooling body.

6. A device for manufacturing a straight metal band comprising: a supply container for dispensing a stream of molten metal alloy; a drum disposed below said supply container having a cylindrical cooling surface extending a full width of said drum;

a means for rotating said drum; a means for moving said supply container in a slowly reciprocating path transverse to said stream across substantially the entire width of said cooling surface for optimum utilization of the cooling property of substantially the entire cooling surface, the velocity of said supply container being substantially less than the rotational velocity of said drum and cooling surface for applying said stream thereto such that said stream is cooled by said surface for removal as a substantially straight band.

4,293,024


SPRAY DEVICE FOR A DIE CASTING MACHINE
Tsuyoshi Kikuchi, Atsugi, and Kiyoshi Takusagawa, Zama, both of Japan, assignors to Toshiba Kikai Kabushiki Kaisha, Tokyo, Japan

Filed Dec. 10, 1979, Ser. No. 102,126

Int. Cl.³ B22D 17/20

U.S. Cl. 164—303

3 Claims



1. In a die casting machine of the type comprising a pair of relatively movable die plates, a pair of mold halves attached to the opposing surfaces of said die plates, respectively, and means for spraying mold releasing agent to inner surfaces of said mold halves, the improvement in which said spray means comprises a support movably mounted on one of said die plates, a cylinder-piston assembly secured to said support, a link mechanism consisting of a quadrilateral linkage connected to a piston rod of said cylinder-piston assembly and pivotally attached to said support, and a spray head supported by and fixed relative to one end of said link mechanism and provided with a plurality of spray guns, said spray guns being positioned in a space between said mold halves when said link mechanism is moved to a predetermined inclined position by the operation of said cylinder-piston assembly.

4,293,025

METHOD AND APPARATUS FOR THE DISTRIBUTION OF LIQUID-VAPOR MIXTURE

Stanley Ohlswager, Robert R. Edison, both of Olympia Fields, and Thorpe Dresser, Markham, all of Ill., assignors to Atlantic Richfield Company, Philadelphia, Pa.

Division of Ser. No. 561,441, Mar. 24, 1975, Pat. No. 4,140,178, and a continuation-in-part of Ser. No. 399,204, Sep. 20, 1973, Pat. No. 3,899,000. This application Jan. 8, 1979, Ser. No. 1,981
Int. Cl.³ F28F 9/22; B01D 45/08; F25B 39/04

U.S. Cl. 165—1

22 Claims

1. A method for distributing a mass of fluid comprising a liquid-vapor mixture into at least two (2) separate streams which comprises:

A. providing an apparatus comprising:
1. a hollow vessel having at least one fluid inlet means;
2. at least two hollow distributor pipe means each having a top opening located at a first end of said pipe means which extends into said vessel, each of said pipe means providing outlet means from said vessel for a different


portion of said fluid, provided that said fluid inlet means is located at a level above said top openings of said pipe means;

3. at least one aperture located in that part of each said pipe means extending into said vessel below said first end of said pipe means to provide fluid communication between the interior of said vessel and the hollow space of said pipe means;

and

4. restrictive means located within said hollow vessel at a level above the top openings of said pipe means to restrict the flow of fluid from said fluid inlet means directly into the hollow space of said pipe means through the top openings of said pipe means; and

B. causing said fluid to enter said vessel through said fluid inlet means and forming a liquid level up to at least the level of said aperture whereby at least a major portion of said liquid enters said pipe means through said aperture.



9. A distribution apparatus for distributing a mass of fluid comprising a liquid-vapor mixture into at least two separate streams each of which flows to a different chemical reaction zone which comprises:

1. a hollow vessel having at least one fluid inlet means
2. at least two hollow distributor pipe means each having a top opening located at a first end of said pipe means which extends into said vessel, each of said pipe means providing outlet means from said vessel for a different portion of said fluid each of said pipe means being in fluid communication with a different chemical reaction zone;
3. at least one aperture located in that part of each said pipe means extending into said vessel below said first end of said pipe means to provide fluid communication between the interior of said vessel and the hollow space of said pipe means; and
4. restrictive means located at a level above the top openings of said pipe means to restrict the flow of fluid from said fluid inlet means directly into the hollow space of said pipe means through the top openings of said pipe means.


4,293,026 ENERGY CONSERVER

Jerome A. Day, 14205 Les Palms Cir., No. 3, Lutz, Fla. 33549
Filed Dec. 10, 1979, Ser. No. 101,835

Int. Cl.³ G05D 23/00

U.S. Cl. 165—11

1 Claim



1. An energy conserver for use with a heating and air condi-

tioning unit, said energy conserver comprising a three position lock switch electrically coupled to the heating and air conditioning unit, selectively moveable between a first, second and third position and a thermostatic control unit including a cooling control switch and a heating control switch electrically coupled between the heating and air conditioning unit and said third position lock switch, each said cooling control switch and heating conditioning control switch selectively moveable between a first and second position such that the heating and air conditioning unit operates continuously in the cooling mode and heating mode when the three position lock switch is in said first and third position respectively and selectively operates in the cooling or heating mode when within either of two preselected temperature ranges when in said second position.

4,293,027 CONTROL SYSTEM FOR HEATING AND COOLING UNITS


James R. Tepe, Montgomery; Robert P. Sandor, Fairfield, both of Ohio; Bernard W. Wesselman, Independence, Ky., and David R. Woeste, Williamsburg, Ohio, assignors to Energetics Systems Corp., Cincinnati, Ohio

Filed Oct. 25, 1977, Ser. No. 845,459

Int. Cl.³ F25B 29/00

U.S. Cl. 165—12

37 Claims



1. In combination with a cooling system for an enclosed space which includes a cooling stage, a conduit for directing return air from the space to the cooling stage, a conduit for directing outside air to the cooling stage, damper means in the conduits for controlling flow in the conduits, and vent means for the space, a control unit which includes means for sensing outside air temperature, means for sensing return air temperature, means for sensing space temperature, a comparing device connected to the outside air temperature sensing means and to the return air temperature sensing means for providing a first signal when the outside air temperature is at least a selected amount cooler than the return air temperature and means for modulating the damper means connected to the comparing device and to the space temperature sensing means so as to increase the flow of outside air and decrease the flow of return air as the space temperature rises above a minimum selected space temperature when said first signal is provided.

23. In combination with a cooling system for an enclosed space which includes a cooling stage, a conduit for directing return air from the space to the cooling stage, a conduit for directing outside air to the cooling stage, damper means in the conduits for controlling flow in the conduits, and vent means for the space, a control unit which includes means for sensing outside air temperature, return air temperature, and space temperature, a plurality of heating stages, and means for modulating the damper means to increase the flow of outside air and decrease the flow of return air as the space temperature rises above a minimum selected space temperature when the outside air temperature is at least a selected amount cooler than the return air temperature, stages of heating above one stage being delayed on startup for a period of time in excess of 30 minutes regardless of space temperature requirements.

4,293,028 ARRANGEMENT FOR CONTROLLING ROOM TEMPERATURE

Alois Knoll, Schönaich, Fed. Rep. of Germany, assignor to Centra-Burkle GmbH & Co., Schönaich, Fed. Rep. of Germany
Filed Oct. 9, 1979, Ser. No. 82,494


Claims priority, application Fed. Rep. of Germany, Oct. 9, 1979, 2843929

Int. Cl.³ F23N 5/20; F24F 3/00

U.S. Cl. 165—12

21 Claims U.S. Cl. 165—29

3 Claims



1. An arrangement in the form of an electrical circuit or the like for controlling in common the room temperature of a group of rooms intended for human occupancy in a building or the like in accordance with the weather including the outside temperature by controlling the output of a heat transfer system, such as a heating system or a cooling system, for said group of rooms, including:


- timing means for defining a series of predetermined first and second time intervals, each of said second time intervals beginning at the end of a first time interval and ending at the beginning of the next successive first time interval;
 - first system control means for controlling the output of said heat transfer system, i.e. the transfer of heat energy with respect to said group of rooms, during said first time intervals to maintain a normal room temperature value; system shut-off means for reducing the output of said heat transfer system to a minimum value at the beginning of said second time interval;
 - maximum output means for increasing the output of said heat transfer means to a maximum value before the termination of said second time interval to effect a rapid transfer of heat energy with respect to said group of rooms, whereby as a result of the rapid heat transfer, the normal value for the room temperature is at least substantially attained toward the end of said second time interval;
 - first computer means for computing the change to be expected in the room temperature as a result of said rapid heat transfer as a rapid heat transfer curve, taking into consideration building values, values of said heat transfer system and the instantaneous weather; and
 - second computer means for computing an actual value curve (T_R) of the room temperature (T_R) from the beginning of each second time interval until the beginning of said rapid heat transfer, taking into consideration the building values, the values of said heat transfer system and the instantaneous weather;
- wherein said maximum output means includes first comparator means for initiating said rapid heat transfer whenever the actual value curve at that time attains the computed rapid heat transfer curve.

4,293,029 TEMPERATURE CONTROL DEVICE FOR A HEAT PUMP

Pierre Godard, Tremblay Les Gonesse, and Jean-Claude Geoffroy, Drancy, both of France, assignors to Saft-Société des Accumulateurs Fixes et de Traction, Romainville, France
Filed Jul. 24, 1979, Ser. No. 60,185

Claims priority, application France, Jul. 31, 1978, 78 22616

Int. Cl.³ F25B 29/00



1. A device for controlling the ambient temperature t of a space heated by means of an electrically actuated heat pump operating with an exchange fluid at a temperature θ , the value of which must not drop below a temperature θ_1 , and by means of an electrically actuated makeup heater, t_1 being the ambient space temperature desired to be achieved, the device including first means for limiting the current of the heat pump to the lower of two values, the first value being determined by an increasing function $f_1(\theta)$ when θ is between θ_1 and $(\theta_1 + \delta\theta_1)$, $\delta\theta_1$ being a predetermined constant temperature interval of a few degrees, and the second value being determined by a decreasing function $f_2(t)$ when t is between a temperature $t_1 - \delta t_1$ and t_1 , δt_1 being a predetermined constant temperature interval of a few degrees, and for shutting off the heat pump current when t reaches t_1 , and second means for controlling the current of the makeup heater, as a decreasing function of t when t is between $t_1 - \delta t_2$ and $t_1 - (\delta t_2 - \delta t_3)$, δt_2 and δt_3 being predetermined intervals of a few degrees of temperature, and $\delta t_2 - \delta t_3$ being always positive, and for shutting off the current of the makeup heater when t reaches the value $t_1 - (\delta t_2 - \delta t_3)$, wherein the improvement comprises means for maintaining δt_3 at a predetermined constant value and means for varying the value of δt_2 as a function of the current of the heat pump when said pump operates in the predetermined temperature limitation zone for the exchange fluid between θ_1 and $(\theta_1 + \delta\theta_1)$.

4,293,030 METHOD OF AND MEANS FOR PASSIVELY COOLING A SHELTER CONTAINING A HEAT SOURCE

Claude Rambach, Rehovot, Israel, assignor to Ormat Turbines, Ltd., Yavne, Israel

Filed Dec. 13, 1978, Ser. No. 969,153

Claims priority, application United Kingdom, Dec. 14, 1977, 51979/77

Int. Cl.³ F28D 15/00; F28F 27/00


U.S. Cl. 165—40

8 Claims

1. Apparatus for passively cooling the interior of a shelter containing a heat source and located in a diurnal environment

which is periodically hotter and cooler than the interior of the shelter comprising:

- (a) an accumulator containing a thermal liquid;
- (b) a first heat transfer loop, including thermosyphonic means, for transferring heat by transferring the liquid from the interior of the shelter to the liquid in the accumulator



when the liquid is cooler than the interior of the shelter; and

- (c) a second heat transfer loop, including thermosyphonic means, for transferring heat by transferring the liquid from the liquid in the accumulator to the environment when the latter is cooler than the thermal liquid in the accumulator.

4,293,031

ENGINE COOLING SYSTEM FLUSHING APPARATUS AND METHOD

John A. Babish, Glendora; Larry K. Arnot, Duarte, and Douglas C. Appel, Glendora, all of Calif., assignors to Wynn Oil Company, Fullerton, Calif.


Division of Ser. No. 856,537, Dec. 1, 1977, Pat. No. 4,209,063.

This application Nov. 20, 1978, Ser. No. 962,389

Int. Cl.³ F28G 9/00; F16L 55/14

U.S. Cl. 165—95

1 Claim



1. A special adapter useful to connect flushing apparatus with a vehicle heater and water pump, said vehicle heater and water pump being components normally connected in the engine cooling system, said apparatus having a first outlet to be connected to the water pump and a second outlet to be connected to the vehicle heater, said adapter comprising

- (a) a pair of tees, each having three ports, and
- (b) a flexible hose interconnecting a first port of one tee and a first port of the other tee, said hose adapted to be pinched off to stop said interconnection, the hose removably connected to said tees,
- (c) the second and third ports to one tee being respectively connected with the vehicle heater and said second outlet

of said apparatus, and the second and third ports of the other tee being respectively connected with the water pump and the first outlet of said apparatus,

- (d) and a clamp clamping said hose to stop communication between said tees via said hose.

4,293,032

COMBINATION FORCED AIR FURNACE AND AIR COOLER


Donald J. Asp, 1140 E. Hawthorne, St. Paul, Minn. 55106

Filed Dec. 6, 1979, Ser. No. 100,738

Int. Cl.³ F23F 27/02

U.S. Cl. 165—101

5 Claims



1. A combination forced air furnace and cooling unit, comprising:

- a. a main housing having a separate heating chamber, cooling chamber and a compartment containing a single blower;
- b. a separate inlet opening for blowing air into said heating chamber and said cooling chamber from the blower;
- c. a separate outlet opening for passing air out of said heating chamber and said cooling chamber to a common plenum;
- d. means for selectively positioning said blower to blow air into the inlet opening of only one of said chambers; and
- e. means for automatically closing off the outlet opening from the other of said chambers to the common plenum when the blower is blowing air into said one chamber.

4,293,033

PLATE-TYPE HEAT EXCHANGER


Gamal E. D. Nasser, Puchheim, Fed. Rep. of Germany, assignor to Linde Aktiengesellschaft, Wiesbaden, Fed. Rep. of Germany

Filed Jun. 29, 1979, Ser. No. 53,277

Int. Cl.³ F28F 3/08

U.S. Cl. 165—166

5 Claims



1. A plate-type heat exchanger comprising:
a plate stack composed of a multiplicity of substantially identical elongated sheet metal plates each formed with longitudinal and transverse intersecting arrays of corruga-

tions having a generally sinusoidal cross section, each two plates forming a plate pair, and being disposed in mirror-image relationship with troughs of corresponding transverse corrugations opening toward one another and defining tubular transverse passages for one fluid medium, the corrugations in the longitudinal direction of the plates of each plate pair lying above one another, the corrugations in the transverse direction of each plate of one plate pair being offset from the transverse corrugations of a juxtaposed plate of the next plate pair by a half wavelength; bars disposed between juxtaposed plates of successive plate pairs and in continuous contact with crests of the respective longitudinal corrugations whereby undulating longitudinal flow passages are formed between said bars for another fluid medium and said longitudinal flow passages are separated from one another by said bars; and means for feeding at least one of said mediums to the corresponding passages of said stack.

4,293,034

WELL SAFETY SYSTEM METHOD AND APPARATUS


James D. Mott, Houston, Tex., assignor to Hydril Company, Los Angeles, Calif.

Division of Ser. No. 2,197, Jan. 9, 1979. This application Dec. 12, 1979, Ser. No. 102,751

Int. Cl.³ E21B 23/04

U.S. Cl. 166—208

3 Claims



1. A subsurface tubing hanger apparatus, including:
a tubular housing having a flow passage formed therein;
means for connecting a string of well tubing below said tubular housing with said flow passages in communication with the bore of the well tubing;
slip means movably mounted on said housing for releasably securing said tubular housing at a subsurface location in a well to support a string of well tubing connected therebelow in the well;
means for moving said slip means between positions for securing said tubular housing in the well and for enabling movement of said tubular housing in the well, said means for moving including a first expansible setting chamber communicating with said flow passage through a first port for moving said slip means to secure said tubular housing in the well;
a tubular stinger for sealingly engaging said flow passage for forming a flow passageway above said tubular housing;
means for releasably connecting said stinger and said tubular housing to enable said stinger to sealingly engage said flow passage to block communication of well fluid pres-

sure in said flow passage to said first port when said tubular housing is secured in the well; and
said means for releasably blocking relative rotation is disengaged when said stinger moves to isolate said first port from the fluid pressure in said passageway.

4,293,035

SOLVENT CONVECTION TECHNIQUE FOR RECOVERING VISCOUS PETROLEUM

John L. Fitch, Dallas, Tex., assignor to Mobil Oil Corporation, New York, N.Y.

Filed Jun. 7, 1979, Ser. No. 46,275

Int. Cl.³ E21B 43/22

U.S. Cl. 166—273

3 Claims

1. A method of recovering viscous petroleum from a viscous petroleum-bearing subsurface formation penetrated by at least one injection well and one production well comprising:

- (a) establishing a high mobility channel through the lower portion of said subsurface formation intermediate said injection well and said production well wherein said high mobility channel is established by injecting a brine having a density greater than the density of said petroleum into the lower portion of said subsurface formation and continuing to inject said brine until breakthrough at said production well;
- (b) injecting a solvent for said viscous petroleum via said injection well into said high mobility channel and producing petroleum from said formation via said production well;
- (c) continuing step (b) until the ratio of produced petroleum to solvent becomes unfavorable and thereafter terminating the injection of solvent; and
- (d) thereafter injecting gas via said injection well into said high mobility channel and producing solvent and petroleum from said formation.

4,293,036

SHEAR-THICKENING COMPOSITIONS

Billy L. Swanson, Bartlesville, Okla., assignor to Phillips Petroleum Co., Bartlesville, Okla.

Division of Ser. No. 868,965, Jan. 12, 1978, Pat. No. 4,212,747.

This application Jan. 8, 1980, Ser. No. 110,439

Int. Cl.³ E21B 43/26, 43/22

U.S. Cl. 166—302

6 Claims

1. A process for hydraulically fracturing a subterranean formation penetrated by at least one well which comprises injecting into the formation at a pressure sufficient to fracture the formation an aqueous shear-thickening composition containing as essential ingredients:

- (a) a small but effective amount in the range of 0.1 to 3 weight percent of a high molecular weight polyalkylene oxide selected from the group consisting of polyethylene oxides, polypropylene oxides, and polybutylene oxides having a molecular weight of about 10,000 to about 10,000,000 and
- (b) a small but effective amount in the range of 0.025 to 2.5 weight percent of a synthetic resin comprising the reaction product formed by heating an aqueous alkaline mixture of an aldehyde having from one to four carbon atoms and a phenol compound selected from the group consisting of phenol, catechol, resorcinol and cresol at a reaction temperature in the range of 100° F. to 212° F. for a period of time in the range of 5 minutes to 48 hours and a molar ratio of aldehyde to phenol in the range 0.1:1 to 2:1 and a pH of about 7 to 12,

the amounts of (a) and (b) being sufficient to form a shear-thickening composition that is fluid in a quiescent state but becomes gel-like in character on agitation, and

- (c) the balance of the composition being water maintaining said composition in said formation in contact therewith for a period of time sufficient to significantly

increase formation permeability and fracturing said formation to stimulate the production of fluids therefrom.

4,293,037

METHOD OF FORMING AND ASSEMBLING A SELF-CLEANING HELICAL SPRING SCREEN

Reynaldo Calderon, Houston, Tex., assignor to Texaco Inc., White Plains, N.Y.


Division of Ser. No. 12,934, Feb. 16, 1979, Pat. No. 4,227,576.

This application Feb. 28, 1980, Ser. No. 125,418

Int. Cl.³ B01D 25/34; E03B 3/20; E21B 37/08, 43/08

U.S. Cl. 166—312

7 Claims



1. A method for assembling a self-cleaning helical spring sand screen comprising,
 - (a) attaching a helical spring sand screen to the lower end of a production tube for being lowered into a well to the liquid level for producing sand-free liquid from the production tube,
 - (b) mounting a spring biased valve means on the production tube,
 - (c) providing valve means for the production tube for controlling the outlet thereof, and
 - (d) connecting a source of high pressure liquid to the spring biased valve means for storing energy in the spring biased valve means, for opening the spring biased valve means, and for injecting high pressure liquid into the helical spring sand screen for expansion and cleaning thereof.

4,293,038

BALL VALVE ASSEMBLY


Robert W. Evans, Houston, Tex., assignor to Baker International Corporation, Orange, Calif.

Filed May 24, 1979, Ser. No. 42,257

Int. Cl.³ E21B 34/12

U.S. Cl. 166—331

15 Claims



1. A rotary ball valve, comprising: a valve housing defining a fluid passage; a ball having an axially disposed fluid passage extending therethrough; a pair of diametrically opposed trunnion bearings fixedly mounted in said housing and supporting

said ball for rotational movement between an open position wherein said ball passage is aligned with and open relative to said housing passage and a closed position wherein said ball passage is closed relative to said housing passage; an annular seal structure axially slidably mounted in said housing passage on the normally upstream side of said ball, said structure including an annular surface engageable with said ball in sealing relationship, said seal structure being axially biased toward said ball by the fluid pressure produced in said housing passage by movement of said ball to closed position; an actuator mounted in said housing passage; means for shifting said actuator relative to said housing in an opening or closing stroke, said actuator being first engageable with said seal structure in its opening stroke to axially shift said seal structure out of engagement with said ball; and means on said actuator for rotating said ball to its open position during the remainder of the opening stroke of said actuator.

4,293,039

NON-ROTATING STABILIZER FOR DRILL STRING


John M. Mullins, and Joseph L. Kelly, Jr., both of Houston, Tex., assignors to Hughes Tool Company, Houston, Tex.

Filed Feb. 15, 1979, Ser. No. 12,277

Int. Cl.³ F16C 1/26; F21B 17/10

U.S. Cl. 166—341

9 Claims



1. An apparatus for maintaining a drill string in the center of a shaft while drilling, comprising:
 - a hub carried by the drill string for rotation therewith;
 - centralizing means extended laterally outward of the hub and having a width substantially the diameter of the shaft for preventing the drill string from moving substantially from the center of the shaft;
 - the centralizing means having passage means for allowing fluid in the shaft to flow past the centralizing means; and
 - bearing means mounted between the hub and the centralizing means for allowing the drill pipe and hub to rotate with respect to the centralizing means;
 - the bearing means including a metal bearing surface and a plurality of individual resilient pads spaced apart from each other and in sliding contact with the bearing surface, the pads and bearing surface being exposed to the fluid in the shaft.

4,293,040

HYDRAULIC DRAFT LOAD SENSING SYSTEM INCLUDING QUILL SHAFT BENDABLE IN RESPONSE TO DRAFT LOADS


John W. O'Connor, Hales Corners, Wis., assignor to Allis-Chalmers Corporation, Milwaukee, Wis.

Filed Aug. 6, 1979, Ser. No. 64,097

Int. Cl.³ A01B 63/112

U.S. Cl. 172—7

10 Claims



1. A hydraulic draft load sensing system on a draft vehicle comprising, a source of constant pressure hydraulic fluid, a sump, at least one path of fluid flow from said source of constant pressure hydraulic fluid to said sump, including, a pilot valve controlling flow of hydraulic fluid through said hydraulic system, a variable orifice in series with said pilot valve to vary the rate of flow of hydraulic fluid through said system, a control valve adapted for controlling flow of hydraulic fluid to a hydraulic actuator, a hydraulic valve operator connected intermediate said pilot valve and said variable orifice operating said control valve responsive to pressure changes, at least one draft arm, means connecting said draft arm to said pilot valve including a quill shaft defining a fluid passage, a rod coaxially supported within said quill shaft to form said pilot valve, said connecting means being so connected to said draft arm that said quill shaft bends responsive to draft loads on said draft arm, said pilot valve controlling the rate of flow through said hydraulic system upon the bending of said quill shaft responsive to draft loads on said draft arm and thereby controlling the raising and lowering of an implement responsive to draft loads on said draft vehicle.

4,293,041

POWER CULTIVATOR WITH DEBRIS EXCLUDING BARRIER AND SCRAPER

Ronald J. Holmstadt, Bloomington, and Robert C. Comer, Hopkins, both of Minn., assignors to The Toro Company, Minneapolis, Minn.

Filed May 17, 1979, Ser. No. 39,944



Int. Cl.³ A01B 1/06, 33/06

U.S. Cl. 172—39

9 Claims

1. A hand held power driven ground working tool, which comprises:
 - (a) a housing having an upwardly extending handle suited to be held by an operator;
 - (b) an elongated rotatably mounted shaft projecting vertically downwardly from the housing;
 - (c) a ground working head fixed on the shaft, exteriorly of the housing, for rotation therewith, the working head being oriented on the lower end of the shaft with the housing thereabove;
 - (d) power means within the housing engaged with the shaft for a rotational driving of the shaft and the working head thereon;
 - (e) barrier means extending between the working head and

the housing, the barrier means freely and rotatably surrounding the shaft in outwardly spaced relation thereto with the shaft being independently rotatable relative to the barrier means, wherein the barrier means comprises an annular member of a length substantially coextensive with the length of the shaft between the working head and the housing, wherein the annular member rests by gravity on top of the working head and has sufficient frictional engagement with the working head to be rotated thereby



- until debris engages the annular member to prevent rotation thereof; and
- (f) scraper means fixed to the housing and projecting inwardly toward the annular member between the working head and the housing, the scraper means including an inner edge positioned in closely spaced relation to the annular member for effecting a scraping action against the annular member during rotation of the member precluding accumulation of debris thereon.

4,293,042

PORTABLE OSCILLATING-RING HARROW


August M. Reuber, 2840 S. Railroad, Albany, Oreg. 97321

Filed Jan. 21, 1980, Ser. No. 113,817

Int. Cl.³ A01B 19/10, 33/06

U.S. Cl. 172—110

4 Claims



3. An oscillating-ring harrow comprising:

an elongate frame and means on the frame for supporting the frame for movement over the ground,
 a harrow ring disposed under and spaced below said frame having a plurality of spaced downwardly projecting tines secured thereto, said ring being mounted for oscillatory movement relative to said frame,
 oscillating means interposed between the frame and said ring for producing such oscillatory movement,
 said ring including a central portion disposed directly under said frame and a pair of opposed side segments pivotally connected to opposite sides of said central portion for swinging movement between laterally outwardly extending positions and upwardly extending positions,
 a pair of wing members pivotally mounted on opposed sides of said frame for pivotal movement between operative positions extending substantially laterally of said frame and transport positions extending substantially upwardly relative to said frame, one wing member being spaced above and associated with one side segment and the other wing member being spaced above and associated with the other side segment,
 power-operated means operatively connecting said frame and said wing members for shifting the wing members between their operative and transport positions, and means coupling each wing member to its associated side segment whereby the side segment swings from its laterally outwardly extending position to its upwardly extending position and is drawn toward the wing member upon the wing member being shifted from its operative to its transport position.

4,293,043


SOIL UNDERCUTTER WITH TRIP RELEASE FOR PIVOTALLY MOUNTED SHANK

Chester G. Neukom, Jamestown, and Iyul D. Kopecky, Ypsilanti, both of N. Dak., assignors to Haybuster Manufacturing, Inc., Jamestown, N. Dak.

Filed Sep. 12, 1979, Ser. No. 74,818
 Int. Cl.³ A01B 61/04

U.S. Cl. 172-267

7 Claims



1. A shank assembly for a cultivator or the like which must be held rigidly in place but being permitted to release under excessive loads when striking an obstacle comprising a mounting bracket, a shank, an earth working sweep mounted at the lower end of said shank, the upper end of said shank being pivotally mounted on said mounting bracket, and a toggle linkage extending between said shank and portions of said mounting bracket, including first and second links, said first link being pivotally mounted to said mounting bracket at a first end thereof, and said second link being pivotally mounted to said shank at a first end thereof, and said first and second links being pivotally mounted together at second ends thereof at a center pivot between the first ends of the respective links, spring means, means to mount said spring means to the assembly including a spring support pivotally mounted on the same pivot axis as the pivotal mounting of said shank, said spring support having an end portion remote from its pivot to support the spring means from movement in direction away from the pivot, and means slidably carried by said spring support and

connected to portions of the toggle linkage and supporting the end of the spring means adjacent said spring support pivot, the spring means acting to urge the toggle linkage toward a position wherein the center pivot approaches a plane defined by the pivots of the first ends of the first and second links, and stop means to prevent the center pivot from moving toward said plane more than a desired amount.

4,293,044


MANUALLY-ACTUATED ROTARY-IMPACT TOOL

J. Edward C. Anderson, Moreland Hills, Ohio, assignor to Marquette Metal Products Co., Fountain Inn, S.C.

Filed Dec. 5, 1979, Ser. No. 100,365
 Int. Cl.³ B25D 15/02

U.S. Cl. 173-93.5

5 Claims



1. In a manually operable impact tool comprising a rotatable tool head for engaging a fastening member, a rotational inertia member surrounding said tool head and capable of rotation relative to said tool head, a driving connection between said inertia member and tool head, an operating handle having its longitudinal axis extending through the rotational axis of said inertia member disposed adjacent to and capable of movement relative to said inertia member, means coaxing with said driving connections for effecting disengagement of said driving connections when movement of said tool head is resisted by a predetermined force and the handle moves relative to the inertia member and for effecting reengagement of said driving connections in another operative condition, spring means disposed in said handle, force transmission means coaxing with said handle and inertia member to actuate said spring for the storage of energy upon said relative movement of the handle and inertia member and to transmit such stored energy to the inertia member to rotate said inertia member and thereby effect the application of an impact force on said tool head upon re-engagement of said driving connections, said force transmission means includes a lever arm pivotally connected to said handle so as to engage said inertia member and connected to be rotationally accelerated about the pivotal connection by said spring means to thereby rotatively drive said inertia member, and said lever arm pivotal connection being offset from the longitudinal axis of said handle.

4,293,045

IMPACTING DEVICE

Zvi Zeidman, 81 Hacarmel St., Carol Goldenberg, 21/21 Jerusalem St., and Zvi Grinbaum, 50 Ben-Gurion St., all of Kfar Saba, Israel


Filed Dec. 6, 1979, Ser. No. 100,980
 Int. Cl.³ B25D 9/04

U.S. Cl. 173-121

10 Claims

1. An impacting device comprising:
 a housing formed with a first cylindrical bore at one end and with a second cylindrical bore at the opposite end coaxial with but of smaller diameter than said first bore so as to define an internal annular shoulder at the juncture of the two bores;
 a driving element movable within said first cylindrical bore and having an outer diameter greater than that of said internal annular shoulder so as to limit thereagainst;
 a plunger movable within said first and second cylindrical bores and having its inner end face engageable with the inner end face of said driving element;

an impacting element carried by the opposite end face of said plunger;
 a spring interposed between said housing and said plunger urging the plunger into engagement with the driving element, and also urging said driving element to an initial position away from said internal annular shoulder;



and an air-vent opening formed through the housing wall communicating with said first bore at a location thereof so as to be between the inner face of the driving element and the internal annular shoulder when the driving element is in its initial position, and to be at the opposite face of the driving element when the latter is in its driven position limiting against the internal annular shoulder.

4,293,046


SURVEY APPARATUS, METHOD EMPLOYING ANGULAR ACCELEROMETER

Donald H. Van Steenwyk, San Marino, Calif., assignor to Applied Technologies Associates, San Marino, Calif.

Filed May 31, 1979, Ser. No. 44,047
 Int. Cl.³ G01P 15/00; G01C 9/00

U.S. Cl. 175-45

28 Claims



1. In the method of determining azimuth, and employing an angular accelerometer, the steps that include
 (a) rotating the accelerometer about a first axis while the accelerometer is carried on a body which is itself rotating about a second axis, and
 (b) detecting the acceleration output of the accelerometer which is caused by said rotation about the second axis.

4,293,047


DRILLING HEAD

David E. Young, Friendswood, Tex., assignor to Smith International, Inc., Newport Beach, Calif.

Filed Aug. 24, 1979, Ser. No. 69,324
 Int. Cl.³ E21B 3/04

U.S. Cl. 175-195

23 Claims



1. Drilling head comprising:
 a tubular body adapted at its lower end for connection to a lower well control element,
 closure means for closing the annulus between the body and a drive tube when extended axially through the body, and securement means for releasably securing said closure means to said body,
 said closure means including a stator, a rotor rotatably mounted relative to the stator, and seal means to seal between the stator and rotor,
 said seal means comprising annular packing means carried by the rotor and an annular sealing surface on the stator in sealing engagement with said packing means,
 said rotor including sealing means to seal between the rotor and said drive tube,
 said rotor including a metal annular body,
 said sealing means and said packing means each including a metal annular support member having a metal radial annular flange for securement to said metal annular body, the metal flange on said sealing means extending radially outwardly and the metal flange on said packing means extending radially inwardly between the sealing means flange and said annular body, and means securing said flanges to said body.

4,293,048

JET DUAL BIT

Joseph A. Kloesel, Jr., Midland, Tex., assignor to Smith International, Inc., Newport Beach, Calif.


Filed Jan. 25, 1980, Ser. No. 115,228
 Int. Cl.³ E21B 9/10

U.S. Cl. 175-340

7 Claims

1. Dual flow passage jet bit comprising
 an annular body providing a central flow passage,
 a tubular pin coaxial with said body and rising therefrom and connected thereto, said pin being externally threaded, said pin having a smaller outer diameter than said body forming an annular upwardly facing shoulder at the juncture of said pin and body,
 a plurality of legs connected to and extending down from said body and symmetrically spaced therearound, the envelope of said legs having a smaller diameter than that of said body, the portion of said body extending radially outwardly beyond said legs providing a seal belt,
 a generally radially inwardly pointing cone rotatably

mounted on the inwardly facing side of each leg, each cone having earth formation reducing means on its outer periphery, the axis of each cone pointing inwardly downwardly whereby the bottom edges of the cones as the cones roll in the bottom of a well bore define a surface that is nearly flat, being in a range between conical pointing up and conical pointing down, at least one of said cones having a portion carrying earth formation reducing means extending radially outwardly beyond said seal belt a dis-



tance sufficient to provide a rotating clearance between the seal belt end and an earth bore drilled with said bit, a plurality of off-axial passages extending from said shoulder downwardly through said annular body, and a nozzle connected to the lower end of each passage, each said nozzle being disposed in between said legs to carry fluid in between said cones and direct it to said bottom, said nozzles lying radially outside the cylindrical volume defined by a downward continuation of said central passage.

4,293,049

METERING AND BALANCING DEVICE AND FILLING MACHINE INCLUDING SUCH A DEVICE


Noël Launay, Beauvais, France, assignor to Societe d'Assistance Technique pour Produits Nestle S.A., Lausanne, Switzerland
PCT No. PCT/CH79/00085, § 371 Date Mar. 17, 1980, § 102(e)
Date Mar. 17, 1980, PCT Pub. No. WO80/00245, PCT Pub. Date Feb. 21, 1980

PCT Filed Jun. 7, 1979, Ser. No. 192,507

Claims priority, application France, Jul. 20, 1978, 78 21507
Int. Cl.³ G01G 1/38, 1/36

U.S. Cl. 177—212

4 Claims



1. A device for metering and balancing the total load of a container during filling, characterized in that it comprises a beam rotatable about a fixed horizontal axis constituting a

simple lever, on the end of the first arm of which rests the end of a vertical rod guided for axial movement and of which the other end is affixed to the inside surface of the platform supporting the container during filling, and of which the other arm is made up of two mutually pivoted parts the first being directly attached to the first arm and rotatable simultaneously therewith about the axis of the beam and provided, at its free end, with a rail in which may slide a counterweight pivoted for rotation about a horizontal axis parallel to the axis of the beam, a bearing acting as the support of the axis of the counterweight being provided with means for allowing it to slide in the rail and being connected to an element forming the second part of the second arm of the beam, which part comprises, at its free end opposed to that provided with the bearing, a slide movable along a straight inclined rail acting as a guide, the straight rail being disposed in a vertical plane perpendicular to the axis of rotation of the beam and the counterweight and being inclined at a pre-determined angle related to the amount of product to be discharged into each container, the lengths of the arms of the beam and the weight of the counterweight and the slope of the straight rail co-operating with the second arm being selected so that the moments of the forces acting on each of the arms are at all times substantially equal.

4,293,050

TRANSMISSION-DIFFERENTIAL COMBINATION


Alexander Goloff, East Peoria, and Ralph E. Denning, Washington, both of Ill., assignors to Caterpillar Tractor Co., Peoria, Ill.

Filed Feb. 27, 1978, Ser. No. 881,218

Int. Cl.³ B62D 11/12

U.S. Cl. 180—6,26

11 Claims



1. A transmission-differential combination having a steering capability, comprising:

- a drive wheel;
 - means for imparting rotary motion to said drive wheel;
 - a first output shaft spaced from said drive wheel;
 - a first transmission delivering rotary motion from said drive wheel to drive said first output shaft;
 - means for selectively varying the drive ratio of said first transmission;
 - a second output shaft spaced from said drive wheel;
 - a second transmission delivering rotary motion from said drive wheel to drive said second output shaft; and
 - means for selectively varying the drive ratio of said second transmission,
- both of said drive ratio selective varying means providing infinite drive ratio variation within a selected range, said first and second transmissions including frictional mechanical transmissions, said combination driving a pair of generally parallel ground engaging means of a vehicle, and including means for simultaneously setting said first and second transmission drive ratios varying means to provide higher speed to a first of said ground engaging means which moves a greater distance and lower speed to a second of said ground engaging means which moves a lesser distance, said drive wheel including first bearing means at the first side thereof spaced from an axis thereof and second bearing

means at the second side thereof spaced from said axis thereof;

said first transmission including a first generally conically surface roller having a shaft extending from an apex end thereof to rotatably fit in said first bearing means and a base end thereof having universal joint means drivingly connected to said first output shaft;

said first transmission selective drive ratio varying means including a first ring having an infacing friction surface fitting about said first roller coaxially with said drive wheel, said first roller nutating within said first ring in contact with said friction surface; and means for selectively axially adjusting the position of said first ring relative to said first roller;

said second transmission including a second generally conically surfaced roller having a shaft extending from an apex end thereof to rotatably fit in said second bearing means and a base end thereof having universal joint means drivingly connected to said second output shaft; and

said second transmission selective drive ratio varying means including a second ring having an infacing friction surface fitting about said second roller coaxially with said drive wheel, said second roller nutating within said second ring in contact with said friction surface; and means for selectively axially adjusting the position of said second ring relative to said second roller.

4. A transmission-differential combination having a steering capability, comprising:

- a drive wheel;
 - means for imparting rotary motion to said drive wheel;
 - a first output shaft spaced from said drive wheel;
 - a first transmission delivering rotary motion from said drive wheel to drive said first output shaft;
 - means for selectively varying the drive ratio of said first transmission;
 - a second output shaft spaced from said drive wheel;
 - a second transmission delivering rotary motion from said drive wheel to drive said second output shaft; and
 - means for selectively varying the drive ratio of said second transmission,
- said first transmission including a first driven wheel having a first output shaft extending axially therefrom, a lateral surface of said first driven wheel frictionally engaging a first peripheral portion of said drive wheel;
- said second transmission including a second driven wheel having a second output shaft extending axially therefrom, a lateral surface of said second driven wheel frictionally engaging a second peripheral portion of said drive wheel;

means for selectively moving said first driven wheel parallel to the rotational axis of said drive wheel to thereby adjust the speed of said first output shaft; and

means for selectively moving said second driven wheel parallel to the axis of said drive wheel to thereby adjust the speed of said second output shaft.

4,293,051

POWER STEERING DEVICE FOR VEHICLES

Masao Nishikawa, Tokyo, Japan, assignor to Honda Giken Kogyo Kabushiki Kaisha, Tokyo, Japan

Filed Oct. 17, 1978, Ser. No. 952,097

Claims priority, application Japan, Oct. 17, 1977, 52-124316
Int. Cl.³ B62D 5/08

U.S. Cl. 180—133


6 Claims

1. In a power steering device for vehicles having a directional control valve movable in either one of two directions in accordance with the turning of a steering shaft so that an oil passage connected to a delivery side of an engine-operated main hydraulic pump is selectively connected to one of two chambers of a hydraulic cylinder, a hydraulic motor driven in proportion to vehicle speed while being supplied with pressure fluid from said main pump, a pressure control valve being arranged so as to modify the flow of pressure fluid from said main pump in accordance with the rotation of said hydraulic motor, a plurality of hydraulic reaction chambers arranged

around said directional control valve and operatively cooperating therewith so as to resist movement of said directional control valve in either direction, said hydraulic reaction chambers being supplied with pressure fluid from said main pump modified by said pressure control valve so as to vary the resistance to movement of said directional control valve in accordance with vehicle speed, the improvement comprising:

means for switching over to use of said hydraulic motor as a substitute power source in response to significant reduction or interruption of oil supply from said main pump, including:

a pipe line (c) connected between the delivery side of said main pump and said pressure control valve for supplying fluid under pressure from said main pump to normally



hold said pressure control valve against movement to a first end position thereof and to permit said pressure control valve to move to said first end position thereof upon any significant reduction or interruption of said main pump supply through said pipe line (c);

a communicating passage (j) arranged so as to provide communication between said hydraulic reaction chambers;

a groove (k) provided in said pressure control valve; and

a delivery side of said hydraulic motor being connected through said groove (k) of said pressure control valve with said communicating passage (j) and a pipe line (d) connected with said directional control valve when said pressure control valve is released to move to said first end position thereof.

4,293,052

LIGHTWEIGHT TWO-WHEELED VEHICLE


Alexander C. Daswick, 647 Orange Grove, S. Pasadena, Calif. 91030, and Archie C. Landry, 7855 Oakdale Ave., Canoga Park, Calif. 91306

Filed Jul. 17, 1978, Ser. No. 925,422

Int. Cl.³ B62D 61/02; B60R 21/02

U.S. Cl. 180—219

8 Claims



1. A lightweight vehicle comprising a frame, a single rear drive wheel, means rotatably securing the wheel to the frame at the rear and above the frame, a front wheel rotatably secured to the front of the frame, means including a seat sup-

ported on the frame between the front and rear wheels for carrying a passenger, an engine mounted on the frame, transmission means drivably connected the engine to the rear wheel, the center of mass of the vehicle being below the horizontal plane of the axis of rotation of the rear wheel, means for turning the plane of the front wheel to steer the vehicle and means securing the means for carrying a passenger to the frame including a first pair of parallel links pivotally connected at one end to the passenger carrying means along a first common axis parallel to the axis of rotation of the rear wheel and at the other end to the frame to the rear of the seat along a second common axis, the first pair of links extending substantially horizontally, a second pair of links pivotally connected at one end to the passenger carrying means along a third common axis parallel to the first common axis, the third common axis being positioned forward of and below the first common axis, the other end of the links of said second pair being pivotally connected to the frame along a fourth common axis parallel to the other common axes below and to the rear of the second common axis, and means responsive to frontal impact for rotating the first and second links relative to the frame to lift and tilt back the passenger carrying means to protect the passenger.

4,293,053

SOUND ABSORBING STRUCTURE


Richard G. Shuttleworth, South Windsor, and Gene R. Snyder, Vernon, both of Conn., assignors to United Technologies Corporation, Hartford, Conn.

Filed Dec. 18, 1979, Ser. No. 105,009

Int. Cl.³ E04B 1/82; F02K 1/00

U.S. Cl. 181-213

4 Claims



1. A sound absorbing structure for a gas turbine engine having an axially extending flowpath which comprises: an engine case, a liner extending coextensively with the engine case which has at least one sound absorbing panel having one or more first cavities therein and spaced from the engine case to form one or more second cavities between the panel and the case, a first plurality of passages in the liner connecting each first cavity with one or more second cavities, a second plurality of passages in the liner connecting each first cavity with the working medium flowpath; a means for removing fluid from each second cavity; wherein the first cavity and the second cavity cooperate to absorb acoustic vibrations and wherein liquid which enters the liner and the second cavity enables the drainage of fluid from the first cavity.

4,293,054

SCAFFOLDING FOR SUPPORTING LIFTING WORKING BRIDGES AND PLATFORMS

Antonio Pieri, Montebelluna, Italy, assignor to PIAT Impalcature Automatiche S.p.A., Italy

Filed May 19, 1980, Ser. No. 150,975


Int. Cl.³ E04G 1/20, 7/20

U.S. Cl. 182-63

6 Claims

1. A disassemblable scaffolding for supporting lifting working bridges and platforms comprising uprights or posts and at least one lift bridge or platform which can be let ascend or descend along said posts, each bridge including at least two carrying frameworks and each platform including one carry-

ing framework, each framework supporting a motor unit and a braking unit, said motor units serving to move the respective bridge or the platform up and down along a respective post and the braking units serving to the locking thereof at any desired level, characterized by the fact that the scaffolding is constituted of modular elements which can be assembled to each other by means of releasable joint means, each post (1) having a lattice structure and being formed; by a base section (7) made integral with a first base frame (12) mounted on wheels (13), and this first base frame (12) being mounted on and connected, in disassemblable manner, to a wider second frame (14) provided with other wheels (15) and with feet (15) of adjustable height, so that each post (1) and the parts connected thereto and supported thereby can selectively let slide along the ground or respectively rest stably thereon; by a plurality of other post sections (7a) to be mounted in superimposed relationship on the base section (7a), said post sections (7, 7a) being triangular in horizontal cross section and including a vertical corner bar 9a and two tubular corner vertical rods (9) forming in their assembled condition vertical guide rails for engaging sliding guide wheels (36) supported by respective frameworks (31), forming a part of the carrying struc-



ture of each bridge (2) or platform (3), this carrying structure also comprising modular lattice carrying elements (46, 47a, 47b) connectable to each other in longitudinal alignment, each carrying structure supporting a footplane (148), as well as a front (149) and a rear parapet (150), each parapet (149 or 150) being constituted of frames (56), the frames (56) forming each front parapet (149) being connected to the carrying elements (46, 47a, 47b and 31) by means of joints comprising tubular seats designed to receive the lower ends of the posts of the frames (56), and arranged in bodies (57) fixed to the carrying structure close upper longitudinal front edges of the elements (46, 47a, 47b, 31) while the frames (56) forming the parapet (150) designed to face the building is connected to the elements (46, 47a, 47b, 31) by joints comprising tubular seats arranged into bodies (57a) connected to the opposite upper longitudinal edges of said elements with the interposition of telescopic connections so as to allow to vary the distance of each parapets (150) from the building and as result thereof, the width of each bridge (3) or platform (2), each post element (7a) comprising a device for contemporaneously inserting surety locking pins (17 and 29) through the female and male joint members (8 and 8a) connecting the post members (7 and 7a).

4,251,055

RETRACTABLE SAFETY HANDLE MEANS FOR A LADDER

Oneida O. Hooser, 313 N. Church (Brooklyn), Mooresville, Ind. 46158

Filed Feb. 21, 1980, Ser. No. 123,301


Int. Cl.³ E06C 7/18

U.S. Cl. 182-106

15 Claims

1. Retractable safety handle means for a ladder, comprising, in combination:

an elongated handle member of a length to span a plurality of steps of the ladder; support means securely supporting the handle member to the ladder at at least two locations vertically spaced along the ladder; the support means including attaching means attaching the handle's support means to the ladder at the said locations; a hinge means associated with each of the said support means, and located with respect to the ladder and handle member in a manner such that the handle member may be positioned in and between a handle-operable position, relatively non-adjacent the ladder and a retracted position relatively adjacent the ladder; the parts thereby providing, that in the handle-position of the handle member, the handle member may be manually



grasped by the user of the ladder as a sturdy and sturdily-supported handle for the ladder, but providing that in the retracted position of the handle member it is retracted operatively adjacent the ladder thereby providing a reduced shape and size of the combination of ladder and handle member as for storage and/or transport thereof, but not requiring dis-assembly of the handle member from the ladder, nor re-assembly thereof to the ladder when desiring to use the ladder with a handle provided therefor; the hinge means and support means providing that the axis of the hinge means is generally vertical and that the movement of the handle member between its said handle-operable position and its said retracted position is generally horizontal without any significant amount of vertical movement, and thereby avoiding any significant amount of handle-raising effort or handle-lowering effort.

4,293,056

DEVICE FOR LUBRICATING A HUB WITH BEARINGS

Robert R. Setree, II, 820 S. Buckeye, Kokomo, Ind. 46901

Filed Feb. 26, 1979, Ser. No. 14,970


Int. Cl.³ F01M 11/00

U.S. Cl. 184-1 D

6 Claims

1. A device for lubricating a hub and bearings mounted therein comprising: a one-piece main body sized to fit through said bearings and into said hub, said main body having a first end and second end; a grease fitting mounted on said first end to receive and apply a flow of grease through said main body; passage means in said main body and having an outlet opening between said first end and second end and aligned and in communication with said fitting to receive a flow of

grease and direct same out of said main body to the bearing being lubricated; sealing means on said main body and located adjacent the bearing being lubricated when said main body is located in said hub and being operable to stop grease from flowing out of said hub; and



locating means connected to said main body and having a first surface adjustable to and from said sealing means to locate said sealing means on opposite sides of the bearing being lubricated when said main body is positioned within said hub and said first surface is in contact with said hub while also positioning said outlet adjacent the bearing being lubricated.

4,293,057

SPRING MOTOR ESPECIALLY SUITABLE FOR USE IN A PANORAMIC CAMERA

Ronald P. Globus; Richard D. Globus, and Stephen E. Globus, all of New York, N.Y., assignors to Globuscope, Inc., New York, N.Y.


Division of Ser. No. 963,739, Nov. 27, 1978, Pat. No. 4,241,985.

This application Apr. 25, 1979, Ser. No. 33,317

Int. Cl.³ F03G 1/00; F16D 57/02

U.S. Cl. 185-37

14 Claims



1. A motor, comprising: a first member; a second member rotatably connected to the first member; drive means for selectively rotating the first member with respect to the second member including a ribbon spring and first and second spring spools, the ribbon spring being reversely wound on the first spring spool; speed governing means for limiting the speed of rotation of the first member relative to the second member, the speed governing means including a chamber containing a fluid and brush means for contacting the fluid, the brush means including a brush which is rotatably mounted within the chamber; and one-way clutch means for operatively connecting the speed

governing means to the drive means during a forward rotation of the first member with respect to the second member and for permitting the ribbon spring of the drive means to be freely rewound during a reverse rotation of the first member with respect to the second member.

4,293,058 BRAKE


Stanley J. Burton, Leigh-on-Sea, England, assignor to Fisco Products Limited, Essex, England

Filed Nov. 8, 1979, Ser. No. 92,286

Claims priority, application United Kingdom, Nov. 14, 1978, 44349/78

Int. Cl.³ B65H 75/48

U.S. Cl. 188—65.1



1. A brake for an elongate member wound on a drum, comprising a control member having a cam portion, and a non-linear recoverable elongate brake member having a cam surface coactable with said cam portion, said brake member being mounted at one end and having its other end free to engage and effect braking of the elongate member; in which the control member is movable in a direction generally parallel to the elongate orientation of said brake member to a braking position to effect braking of the elongate member by an increase in the effective linear length of the brake member and to a brake release position at which the free end of the brake member is disengaged from the elongate member and the brake member has returned to its original unstrained condition.

4,293,059


DETENT MECHANISM AND TRANSMISSION SPEED RANGE SELECTOR VALVE

James H. Lucas, Milwaukee, Wis., assignor to Allis-Chalmers Corporation, Milwaukee, Wis.

Filed Sep. 5, 1979, Ser. No. 72,362

Int. Cl.³ B60K 41/24; F16D 67/04; F16K 11/10; F15B 11/15
U.S. Cl. 192—3.57

10 Claims



1. A transmission selector valve having a detent mechanism and operating in a pressurized hydraulic fluid system compris-

ing, a valve housing defining a central opening, a spool reciprocally mounted in said central opening selectively defining at least three speed range positions including a high and a low position, resilient means normally biasing said spool to the low speed range position, said housing and spool defining a fluid pressure chamber receiving pressurized fluid from the hydraulic system for biasing said spool against the resilient means to the high speed range and holding said spool in the high speed range position when the valve spool is in the high speed range position, a plurality of grooves in said housing defining reverse, low and high detent stop positions of said valve spool, a detent mechanism including detent elements biased radially for selective reception in said grooves, throttling means in said hydraulic fluid system upstream from said selector valve for reducing pressure of hydraulic fluid supplied to said selector valve and the hydraulic fluid in said pressurizing chamber thereby releasing said spool allowing said resilient means of said valve to return said spool from the high speed range position to the low speed range position, said detent mechanism arresting movement of said valve spool and retaining said valve spool in the low speed range position responsive to the predetermined decrease in pressure in said pressurizing chamber.

4,293,060

ELECTROMAGNETIC FRICTION CLUTCH WITH OVERLOAD RELEASE


Donald L. Miller, Horseheads, N.Y., assignor to Facet Enterprises, Inc., Tulsa, Okla.

Filed Oct. 24, 1978, Ser. No. 954,372

Int. Cl.³ F16D 7/02, 27/10

U.S. Cl. 192—56 R

7 Claims



1. A torque overload electromagnetically operated friction clutch for establishing drive between a pair of primary clutch members, said clutch comprising:

- a ferromagnetic inner body rotatably connected to one of said primary clutch members, said inner body having a radially extending portion formed with radial friction face portions;
- a ferromagnetic armature disposed opposite and adjacent to said inner body friction face portions, said armature having corresponding radial surfaces constituting mating friction face surface;
- means of mounting said inner body and said armature for relative axial movement to bring said friction faces into and out of frictional engagement;
- electromagnetic coil means for generating magnetic flux drawing said inner body and armature into frictional engagement;
- means for rotatably connecting said armature to said other primary clutch members, said means including:
 - a backing plate disposed adjacent said armature;
 - a torque booster means interconnecting said backing plate and said armature, said torque boosting means including a plurality of balls disposed in corresponding conical

pockets formed in opposite radial face portions formed on said armature and said backing plate;

means rotatably connecting said backing plate to said other primary clutch member;

means mounted for rotation with said backing plate, for allowing limited axial movement of said backing plate away from said armature member while exerting a corresponding spring force resisting said relative axial movement and providing an axial spring force restraining the movement of said backing plate; and

torque overload means including a means for deenergizing said electromagnetic coil means upon the attainment of a predetermined torque level through said clutch unit, said means including means responsive to a predetermined extent of said relative axial travel of said backing plate relative said armature whereby drive through said unit is discontinued.

4,293,061


REMOTE CONTROLLED HUB CLUTCH
Arthur K. Brown, South Bend, Ind., assignor to The Bendix Corporation, Southfield, Mich.

Filed Jul. 11, 1979, Ser. No. 56,483

Int. Cl.³ F16D 1/06, 11/00, 25/061

U.S. Cl. 192—67 R

5 Claims



1. In a vehicle:
 - wheel support means rotatably mounted on said vehicle;
 - an axle assembly rotatably mounted on said vehicle for transmitting torque to said wheel support means;
 - clutch means interconnecting said wheel support means and said axle for engaging and disengaging said wheel support means with said axle;
 - control means remote from said wheel support means for engaging or disengaging said clutch means when the vehicle is stationary, said control means including operator actuated means in an operator's compartment in the vehicle;
 - structure interconnecting said operator-actuated means and said clutch means to engage and disengage the latter from said operator's compartment by operation of said operator-actuated means;
 - said axle assembly defining a bore therewithin, said bore comprising a portion of said interconnecting structure, said interconnecting structure further comprising a mechanical linkage,
 - said mechanical linkage comprising a rod slidable within said bore in response to actuation of said operator-actuated means, one end of said rod having a portion operatively engageable with said clutch means;
 - said axle assembly defining a slot extending from said bore to a surface of said axle assembly;
 - said mechanical linkage further comprising an arm connected to said rod and extending through said slot, a bell crank with an arm pivotal in response to actuation of said operator-actuated means, and a ring coaxially mounted on

4,293,062


CONVEYOR BELT ASSEMBLY FOR A DISPLAY RACK
Rafael T. Bustos, Clarkston, Ga., assignor to Leggett & Platt, Inc., Carthage, Mo.

Filed Feb. 21, 1979, Ser. No. 13,246

Int. Cl.³ A47F 5/00

U.S. Cl. 193—2 D

11 Claims



1. An improved conveyor belt assembly for use with a display rack, said assembly functioning to gravity feed a column of containers one after another to the front edge of a shelf as that column's lead containers are successively removed by a customer, said assembly comprising
 - a conveyor belt positionable on said rack at an angle relative to the horizontal, said conveyor belt sloping generally upward from the front edge of said shelf, each container in said column being positioned in generally vertical fashion on said belt during use of said rack,
 - a support floor disposed beneath said conveyor belt, said conveyor belt and said support floor cooperating to support said containers in said column on the upper surface of said conveyor belt, the upper surface of said conveyor belt having a frictional relation with said containers that inhibits movement on said belt of said containers relative one to the other, said support floor and the undersurface of said conveyor belt having a friction relation with one another that allows movement of said belt over said support floor when said belt is at least partially loaded with containers and when not restrained against movement, said friction relationships being such that said belt can slide over said support floor while said containers remain generally stationary relative one to the other on said conveyor belt after removal of the column's lead container during use of said rack,
 - a molded plastic end cap mounted on each end of said support floor, each end cap including an idler spool connected in freely rotating relation therewith, said conveyor belt being an endless conveyor belt carried on said idler spools, and said support floor being disposed beneath the upper run of said conveyor belt,
 - latch means partially carried by said end cap and partially carried by said floor, said latch means being flexible to permit easy snap-on assembly of said end cap with said floor, and
 - a bumper mounted in one of said end caps and positionable adjacent the front edge of said assembly, said conveyor belt conveying all of said containers in said column forward together toward said bumper in response to gravity on the remaining containers in said column after removal

of the lead container from said column, said conveyor belt and said container column being stopped by contact of the container in back of the lead container with said bumper, thereby positioning a new lead container adjacent the front edge of said shelf.

4,293,063

APPARATUS FOR INVERTING AND TRANSPORTING ARTICLES


Walter Shields, 181-41 Henley Rd., Jamaica, N.Y. 11432

Filed Jun. 22, 1979, Ser. No. 51,327

Int. Cl.³ B65G 47/24

U.S. Cl. 198—404

12 Claims



1. An apparatus for receiving articles at a first station and discharging them with different orientation at a second station, comprising an endless conveyor having article holding means affixed thereto at equally spaced apart locations in the direction of movement of the conveyor, each holding means having N article holders spaced normal to said direction, wherein N is an integer at least equal to two, N article feeders positioned to feed articles to separate article holders of each holding means, said feeders being spaced in said direction to be alignable with different holding means to enable simultaneous feeding of articles to the article holders of different holding means by the different feeders, and a holding station positioned adjacent said conveyor spaced from said feeders, for receiving articles from said article holders.

4,293,064

ROLL CONVEYOR


James A. L. Robinson, Fayetteville, N.Y., assignor to Syracuse Supply Company, Syracuse, N.Y.

Filed Apr. 11, 1980, Ser. No. 139,573

Int. Cl.³ B65G 17/00, 17/24

U.S. Cl. 198—779

14 Claims



1. Apparatus for conveying articles that includes a frame having a planar conveying zone situated in the top portion thereof, an endless transport movably mounted within said frame

having a flat upper run which passes through the conveying zone,

two parallel rows of equally-spaced rollers rotatably supported in the endless transport for movement therewith wherein the rollers in one row are axially aligned with the rollers in the other row along a common axis of rotation that is perpendicular to the path of travel of said endless transport, and

a series of elongated cylinders seated upon the top of the endless transport over the two rows of rollers, said cylinders resting in contact with two adjacent rollers in each row whereby the cylinders create a moving platform within the conveying zone.

4,293,065

DRIVE/TAKE-UP ASSEMBLY FOR ACCUMULATING LIVE ROLLER CONVEYOR SYSTEMS


Thomas A. Dyer, Greenwood, and Richard L. Huelster, Indianapolis, both of Ind., assignors to Pentek Corporation, Indianapolis, Ind.

Filed Apr. 28, 1980, Ser. No. 144,236

Int. Cl.³ B65G 13/07, 15/20

U.S. Cl. 198—781

20 Claims



13. In a live conveyor system of the type including a power-driven endless conveying means having an upper frictional driving pass for engaging a plurality of load-carrying rollers and a lower return pass, means for propelling the conveying means, and means for tensioning the conveying means, an accumulating section comprising laterally spaced outer support members for supporting a plurality of load-carrying rollers for rotation about transverse axes which are suitably spaced apart and arranged in a common load-transporting array in the longitudinal direction of the conveyor, inner frame members for supporting one of the propelling means and the tensioning means, means for mounting the inner frame members to a portion of the outer support members to allow movement of the inner frame members relative to the load-carrying rollers, laterally spaced inner support members for supporting a plurality of pressure rollers for carrying the upper frictional driving pass of the endless conveying means, means for mounting the inner support members to the portion of the outer support members to allow movement of the inner support members relative to the load-carrying rollers independent of the movement of the inner frame members, and jack means for raising and lowering the inner frame members and the inner support members.

4,293,066

EGG TRANSPORTING SYSTEM

Jerome J. Kennedy, Marietta; Harold S. Wayne, Douglasville, and Charles A. White, Woodstock, all of Ga., assignors to U.S. Industries, Inc., New York, N.Y.

Filed Jan. 22, 1980, Ser. No. 114,341

Int. Cl.³ B65G 23/44


U.S. Cl. 198—813

8 Claims

7. In a system for tensioning an endless loop conveying element which includes frame means including an axle for rotatably supporting first rotatable endless loop guide and support means, second rotatable endless loop guide and support means movable with respect to said frame means and positioned remotely from said first endless loop guide and

support means, an endless loop conveying element extending between said first and second endless loop guide and support means and supported thereby, the improvement comprising:

roller means engaging said second endless loop guide and support means for rotatably supporting said second end-



less loop guide and support means with respect to said frame, wherein said roller means is movable with respect to said frame to shift said second endless loop guide and support means with respect to said first endless loop guide and support means to adjust the tension of said conveying element means.

4,293,067

CONVEYOR ASSEMBLY FOR A WRAPPING MACHINE


Andrew W. Anderson, West Caldwell, N.J., assignor to Scandia Packaging Machinery Co., Clifton, N.J.

Filed Jul. 3, 1979, Ser. No. 54,499

Int. Cl.³ B65G 17/06, 17/38, 29/00, 25/00

U.S. Cl. 198—851

30 Claims



23. A link member longitudinally self-adjustable along a fixed longitudinal axis, said link member comprising:

- two separated linking element end sections having outer opposed ends and inner opposed ends,
- bearing means mounted only on said outer opposed ends of each end section, and
- coupling means fixedly secured to one of the inner opposed ends and shiftably secured to the other inner opposed end to cause the end sections to be movable only in a direction parallel to the fixed longitudinal axis of the link member.

4,293,068

MULTI-LAYERED FOIL CIGARETTE PACK WITH STRIP SEALED TEAR FLAP

Heinz Focke, and Kurt Liedtke, both of Verden, Fed. Rep. of Germany, assignors to Focke & Co., Verden, Fed. Rep. of Germany


Filed Oct. 2, 1979, Ser. No. 81,241

Claims priority, application Fed. Rep. of Germany, Oct. 30, 1978, 2847161

Int. Cl.³ B65D 75/20, 75/26, 85/10

U.S. Cl. 206—264

5 Claims



1. A cigarette pack, comprising:

- a rectangular container folded from a laminated blank including an outer layer (10) of metal foil and an inner layer (11) of paper bonded thereto,
- an opening flap (22) disposed on adjoining top and upper front surfaces of the container, said flap being defined by a tear line (23) formed by aligned but discontinuous perforations (24) extending completely through the metal foil and paper layers, and
- a localized band-like layer (27) of aroma and moisture-proof, severable adhesive material bonded to the interior surface of said paper layer, overlying and straddling the tear line, and extending laterally outwardly therefrom to a limited degree on the interior of the container, whereby said opening flap may be torn off from the container to gain access to the contents thereof.

4,293,069

WARDROBE CONTAINER


James H. Partain, Norcross, Ga., assignor to Stone Container Corporation, Chicago, Ill.

Filed Feb. 27, 1980, Ser. No. 125,155

Int. Cl.³ B65D 85/18

U.S. Cl. 206—279

4 Claims



1. In a wardrobe container formed from a one piece blank having at least two side walls, two end walls and a bottom wall connected together and including a hanger bar having opposed

end portions each defined by inside and outside legs and a connecting top portion, the improvement comprising:

a pair of top flaps each hingedly connected along a top free edge of one of said two side walls and having a uniform thickness, each of said flaps including first and second panels connected together along a double score line segment spaced from a said free edge with said first panel connected to said side wall, said first and second panels being folded in planes parallel to said side wall adjacent said top free edge thereof and being spaced apart by said segment, each of said top flaps including a third panel connected to said second panel and foldable across the top of the container, said third panel including hinged support flap means foldable to a position sandwiched between said first and second panels to form a four ply assemblage adjacent said top free edge, said flap means defining an opening in said third panel through which said hanger bar end portions are inserted with said inner and outer legs containing at least a part of said four ply assemblage therebetween and said top portion engaged adjacent said top free edge and on said support flap means, said support flap means reaching to adjacent said double score line segment so that the weight of said hanger bar carried by said end portions is transmitted in part by said support flap means to said segment.

4,293,070

FOR PROTECTING PRINTED CIRCUIT BOARDS AND OTHER ITEMS AGAINST THE RAVAGES OF A DISCHARGE OF STATIC ELECTRICITY


Ralph C. Ohlbach, 417 Green Park Ct., Deerfield, Ill. 60015

Continuation-in-part of Ser. No. 25,336, Mar. 30, 1979, abandoned. This application Jul. 19, 1979, Ser. No. 58,786. The portion of the term of this patent subsequent to Jul. 10, 1996, has been disclaimed.

Int. Cl.³ B65B 81/24, 85/42

U.S. Cl. 206—328

14 Claims



12. An inexpensive but effective carbon black circumvallate trap for static electricity originating outside the trap so that goods inside the trap, which may be ruined by a discharge of static electricity, are protected by the carbon black circumvallate, said trap comprising:

a paper board box having on the bottom wall and four side walls a carbon black facing layer deposited from a liquid dispersion on the side facing the interior of the box, a partitioner means inserted into the box, opposed surfaces of said partitioner means respectively facing one of said sides also being faced with a carbon black layer deposited from a liquid dispersion, the opposed surfaces of the partitioner means and each of said walls being characterized in that at least the interior thereof is not penetrated by the carbon black so deposited, so that the interior of the box is divided into individual cells each having at least a five-sided circumvallate of carbon black.

4,293,071 SLANT STACKING TRAY SYSTEM


John A. Bridges, Nashville, Tenn., assignor to Aladdin Industries, Incorporated, Nashville, Tenn.

Continuation of Ser. No. 704,357, Jul. 12, 1976, abandoned. This application Nov. 4, 1977, Ser. No. 848,763

Int. Cl.³ B65D 21/02

U.S. Cl. 206—503

6 Claims



1. A stack of trays, each tray having a tray body with a continuous upper surface for holding food holding containers and a lower surface, a stacking element extending from said upper surface above every other portion of said upper surface and above any food holding containers which may be placed thereon and wherein each tray positioned relative to each other in the stack so that a stacking element on a tray under another tray engages a portion of the lower surface of the tray above while another portion of the upper surface of a tray under another tray engages still another portion of the lower surface of the tray above to cause the body of each tray to be at an angle to the horizontal, said upper surface of each tray provided with at least two discrete item holding areas.

4,293,072

STACKABLE EQUIPMENT CONTAINERS

David A. Hill, and Abraham Lomnitzer, both of Johannesburg, South Africa, assignors to Qualetron (PTY) Ltd., Germiston, South Africa


Filed Aug. 21, 1979, Ser. No. 68,353

Claims priority, application South Africa, Aug. 23, 1978, 78/4787

Int. Cl.³ B65D 21/02

U.S. Cl. 206—512

27 Claims



1. A parallelepipedal container comprising
(a) at least two grooves extending along the length of each of its upper and lower sides,
(b) each said groove having a base and a pair of inclined sides extending therefrom and leading to a lip that extends over the grooves,
(c) end closure means at the ends of the grooves closing off the said ends of the grooves,
(d) a pair of removable engagement means in each of the grooves on one of said sides of the container, each said engagement means, having a base contained within a groove, a narrow resilient leg extending from the base and

lying parallel to the groove, and a nose at the end of the leg and

(e) spacers respectively within the grooves on the upper side extending between and engaging the bases of the engagement means and holding them against the end closure means at the ends of the grooves.

4,293,073

CONTAINER WITH COLLAR


George Yates, Jr., Glendale, Calif., assignor to Growth International Industries Corp., Cleveland, Ohio

Continuation of Ser. No. 649,712, Jan. 16, 1976, abandoned. This application Jun. 20, 1977, Ser. No. 807,862

Int. Cl.³ B65D 21/02

U.S. Cl. 206—519

5 Claims



1. A container comprising:

a side wall in the shape of a tapered cylinder including an open upper end and a lower closed end smaller than said upper end, said upper end terminating in an outwardly extending bead having an outer surface; and an annular integral collar extending outwardly around said sidewall, said annular collar comprising a downwardly extending first section including an upper end and a free lower end, and a second section interconnecting the upper end of said first section and said side wall; said collar at the free end of said first section being spaced outwardly of said side wall by a distance substantially equal to the outward extension of the bead; and a plurality of radial ribs interconnecting said first section of said collar and said side wall, said ribs terminating in coplanar free ends spaced from the free lower end of said collar and disposed within said collar; said collar having an inner surface facing said side wall and extending below the coplanar free ends of said ribs, said inner surface having a configuration corresponding to the outer surface of said bead; said container being configured to nest with another like container, wherein the upper end of one container is received within the collar of the other container in abutting relationship with the free ends of said radial ribs and said inner surface of said collar is in sealing engagement with the outer surface of said bead.

4,293,074

ROOT CANAL EQUIPMENT PACKAGING

Joel L. Dunskey, 665 Beacon St., Boston, Mass. 02215

Filed Dec. 4, 1979, Ser. No. 99,994


Int. Cl.³ B65D 1/34; A45C 11/26

U.S. Cl. 206—572

10 Claims

1. A root canal treatment kit comprising,
first reusable tray means of plastic material resistant to chemicals used in root canal treatment formed with recesses for accommodating apparatus and materials used in root canal treatment,
second reusable tray means of said plastic material formed with recesses for accommodating said apparatus and materials for root canal treatment formed with means for support by said first tray means spaced above said first tray

means by an amount sufficient to allow apparatus and materials for root canal treatment to be accommodated in said recesses in said first tray means when said second tray means is seated thereon,



said second tray means being readily removable from said first tray means,
said recesses accommodating in one package substantially all the instruments and supplies needed by a dentist for performing root canal work.

4,293,075

CABINET FOR HOLDING MAGNETIC TAPE CARTRIDGES AND CASSETTES


Guy G. Veralrud, Canoga Park, Calif., assignor to Kustom Kreations, Inc., Northridge, Calif.

Filed Oct. 11, 1979, Ser. No. 83,790

Int. Cl.³ A47B 81/00

U.S. Cl. 211—40

9 Claims



1. A holder for receiving and supporting magnetic tape cartridges, cassettes or containers for the cassettes each having a particular height and width dimension and with the holder including

a pair of spaced sidewalls and with the distance between the spaced sidewalls approximately equal to the width of the containers for the cassettes,
a plurality of pairs of spaced shelf supports extending from the sidewalls and forming a column of separate openings for receiving and supporting the cartridges, cassettes and containers for the cassettes and with the distance between the adjacent shelf supports on the same sidewall approximately equal to the height of the cartridges,
a plurality of pairs of spaced stepped portions each extending from a sidewall and one shelf support and within an opening and with the distance between each stepped

portion and the other adjacent shelf support on the same sidewall approximately equal to the height of the containers for the cassettes and with the distance between each pair of spaced stepped portions on opposite sidewalls approximately equal to the width of the cartridge, and a plurality of pairs of spaced projecting locking portions each extending from a sidewall and within one opening and with the height of each locking portion approximately equal to the height of the cassette and the distance between each pair of spaced locking portions on opposite sidewalls approximately equal to the width of the cassette.


4,293,076

HANGER BAR

Herbert S. Collin, 35 Lombard St., Newton, Mass. 02158
Filed Apr. 30, 1979, Ser. No. 34,270
Int. Cl.³ A47B 47/00

U.S. Cl. 211—124

15 Claims



1. A garment hanger bar for a portable clothes container or the like comprising:

an elongate channel-shaped main bar having a top wall and a pair of downwardly extending sidewalls;

an end support formed at each end of and integrally with the main bar, each end support defining a downwardly opening channel which extends along a direction transverse to the longitudinal dimension of the main bar, each end support being adapted to receive and rest on the upper end of a wall of the container;

each end support having a top wall and a downwardly extending outer sidewall adapted to face the outer surface of the container wall;

each end support having inner sidewall segments which extend downwardly from the top wall of the end support, the inner sidewall segments being integrally connected to and forming a continuation of the sidewalls of the main bar;

said inner sidewall segments having at least portions lying in a plane substantially parallel to that of the outer sidewall of the end support, said inner sidewall members being adapted to face the inner wall surface of the container;

a depression formed in the top wall of the main bar adjacent its juncture with the end support;

said main bar and end support being formed from a single unitary sheet of metal.

4,293,077

CONTAINER HANDLING APPARATUS

Kazuhiro Makino, Kudamatsu, Japan, assignor to Hitachi, Ltd., Tokyo, Japan

Filed Aug. 13, 1979, Ser. No. 66,237

Claims priority, application Japan, Aug. 30, 1978, 53-104924
Int. Cl.³ B66C 17/00; B65G 67/60


U.S. Cl. 212—219

2 Claims

1. A container handling apparatus comprising:

a container crane with elongated legs capable of travelling, a self-supporting portal frame having leg portions and being disposed within a region defined by said elongated legs of said container crane, travelling wheels being mounted to said leg portions of said portal frame,

connecting means being connected between said portal frame and said container crane, said portal frame comprising an elevating device thereon and a container transfer space, said portal frame further comprising first and second pluralities of guides located in the vicinity of said container transfer space,



wherein said second plurality of guides comprises a plurality of low guides disposed remote from said elevating device and a plurality of high guides more proximate to said elevating device, whereby a container delivered to said guides by said container crane is first positioned by said high guides.

4,293,078

VACUUM INDICATOR CLOSURE FOR A BLOOD COLLECTION TUBE


Edward P. Percarpio, North Haledon, and William J. Holderith, Wyckoff, both of N.J., assignors to Becton, Dickinson and Company, Paramus, N.J.

Filed Nov. 1, 1979, Ser. No. 90,389

Int. Cl.³ B65D 47/36

U.S. Cl. 215—247

14 Claims



1. A readily penetrable vacuum indicator closure for sealing an open end of an air evacuated blood collection tube comprising:

a tubular elastomeric body having flexible, elastic side walls, an open first end and a closed second end formed by a cannula-penetrable, flexible, elastic end wall integral with said side walls, said end wall having an outer surface and an inner surface, said outer surface being convexly curved and said inner surface being concavely curved when pressure on said inner and outer surfaces is equal, said end wall being sufficiently flexible to deflect under the influence of a pressure differential on said end wall so that when pressure against said outer surface substantially exceeds the pressure against said inner surface, said outer surface becomes concavely curved and said inner surface becomes convexly curved, said outer surface being readily visible to an observer with its changeable nature serving as an indicator of relative pressures on opposite sides of said end wall, said outer surface being only slightly displaced from the flattened condition when concave to

attribute a radially directed outward force to said end wall; and
a flange annularly disposed about the periphery of said side walls adjacent to said second end.

4,293,079

HINGED CLOSURE


Thomas G. Lytle, Norwalk, Conn., assignor to TLB Plastics Corporation, Brewster, N.Y.

Filed Mar. 24, 1980, Ser. No. 133,623

Int. Cl.³ B65D 41/16, 41/18

U.S. Cl. 220—306

10 Claims



1. A receptacle comprising a receptacle body member including a peripheral wall with a top border delineating an opening and having formed in said top border, a plurality of resilient, hollow open bottomed, inwardly directed locking elements each of which includes an inwardly projecting downwardly outwardly tapering wall integrally joined along its side edges to said body member border and terminating at its bottom in a horizontally extending edge, a coupling member including a frame member telescoping said body member border and having an outerface substantially corresponding to the body member border inner face and having recesses in said outer face with upwardly directed bottom faces engaging the said bottom edges of said locking elements and a closure member movable between closed and open positions in and out of closing engagement with said frame member.

4,293,080

CONTAINER CONSTRUCTION

Ilija Letica, Oxford, Mich., assignor to Letica Corporation, Rochester, Mich.

Filed Jul. 16, 1980, Ser. No. 169,330

Int. Cl.³ B65D 41/16, 41/18

U.S. Cl. 220—306

19 Claims

1. A resealable plastic container assembly, comprising:

a generally cylindrical container having a bottom, a sidewall extending upwardly from said bottom and an open top, said container including:

(1) a plurality of circumferential reinforcement ribs adjacent said top thereof, said ribs being defined within a radially inset area in said sidewall, the outside diameter of each of said ribs being substantially equal to or less than the outside diameter of said side wall below said inset area,


(2) a connecting flange above said circumferential ribs extending upwardly toward said open top, and

(3) a rim connected to and disposed above said connecting flange, said rim having an arcuately shaped bead on the

upper extremity thereof extending radially outward and defining said open top, a locking lip on the opposite end of said rim and interior of said container, and a substantially flat sealing surface essentially interior of said container and extending between said container and extending said bead and said locking lip to provide a continuous seal between said bead and said locking lip; and,

a lid for removable attachment to said container comprising a substantially flat disc having a channel in the periphery thereof adapted to receive said rim therewithin, said channel being defined by—

(1) a substantially flat wall surface adapted to sealingly engage said flat sealing surface and being essentially coextensive with the latter,



(2) an interior locking portion on the lower extremity of said flat wall surface and including an arcuately shaped interior locking edge adapted to conformingly grip said locking lip, and

(3) an exterior locking portion on the upper extremity of said flat wall surface and including an arcuately shaped exterior locking edge adapted to conformingly engage and grip said bead, said exterior locking edge being spaced from said connecting flange to define a pry opening between said lid and said container rim into which a tool may be inserted for removing said lid,

said rim and said channel providing a tight, continuous lid-to-container seal between said exterior and interior locking portions of said lid.

4,293,081

METHOD AND DEVICE FOR METERED DISPENSING OF LIQUIDS, IN PARTICULAR CONCENTRATES OR SYRUPS, FOR THE PRODUCTION OF BEVERAGES

Alexander Kückens, Hamburg, Fed. Rep. of Germany, assignor to Dagma Deutsche Automaten und Getrankemaschinen GmbH & Co. KG, Fed. Rep. of Germany

Filed Aug. 1, 1979, Ser. No. 62,695

Claims priority, application Fed. Rep. of Germany, Aug. 3, 1978, 2834095; May 22, 1979, 2920747


Int. Cl.³ B67B 7/26

U.S. Cl. 222—83

12 Claims

1. A device for metered dispensing of liquids, in particular concentrates or syrups, for the production of beverages, comprising a conveying and dispensing container for the liquid having at least two oppositely arranged flexible wall portions, a hood-like compensating vessel constantly connected with the outlet opening of the container and arranged within said container and being open towards said outlet opening only, and a dosing means which, before the device is put into operation, can be connected with the outlet opening of the container and is provided with a dosing means of which the inlet and outlet is controlled by a valve, said dosing means being provided with venting passages which, when the dosing means is connected with the container, open into the compensating vessel, con-

necting the same at the one side with the ambient atmosphere and at the other side with the dosing chamber, characterized in that the container and the dosing means are provided with



rigid supporting members which, in connected condition of container and dosing means, form a continuous reinforcing bridge between the two opposed flexible wall portions of the container.

4,293,082

LIQUID DISPENSING STAND WITH COOLING SUPPORT

Shinji Matsueda, Yokohama, Japan, assignor to Nippon Light Metal Co., Ltd., Tokyo, Japan


Filed Feb. 7, 1980, Ser. No. 119,436

Claims priority, application Japan, Feb. 13, 1979, 54-15883

Int. Cl.³ B67D 3/00; B65D 5/62

U.S. Cl. 222—131

8 Claims



1. Liquid dispensing stand for use with a liquid containing vessel having a mouth piece to which a manual liquid dispensing means is attached, wherein the improvement comprises a supporting seat member having a central opening, a pair of legs having the upper portions thereof secured to said supporting seat member and a base member to which the lower ends of said legs are secured so as to support said supporting seat member in position above said base member by means of said legs, said supporting seat member being adapted to support thereon said liquid containing vessel in upside-down position so that said liquid dispensing means of said vessel projects downwardly through said central opening of said supporting seat member with an appropriate vertical distance held between said liquid dispensing means and said base member thereby permitting the liquid in said vessel to be dispensed in a receiving member located on said base member underneath said liquid dispensing means by operating the same, and cooling medium located between said supporting seat member and said vessel, said cooling medium supporting said vessel and cooling the liquid therein.

4,293,083

SHOWER DISPENSER


Harry E. Meares, Jr., Coral Gables, Fla., assignor to Walter S. Klements, Coral Gables, Fla.

Filed Mar. 13, 1979, Ser. No. 20,137

Int. Cl.³ B05B 7/26

U.S. Cl. 222—133

2 Claims



1. A shower dispenser comprising housing means having a water passage extending therethrough, means for connecting said water passage at one end to a water supply pipe and at the opposite end to a shower head, a transverse bore extending through said housing and intersecting said water passage at right angles thereto, a reservoir disposed in said housing adjacent said bore, spool valve means slidably mounted in said bore, a measuring chamber having inlet and outlet ports located in said spool valve means adjacent one end thereof, said spool valve means having a reduced thickness portion adjacent said measuring chamber which is always disposed in at least partial alignment with said water passage to permit the flow of water in said water passage past said spool valve, a dispensing port in said housing communicating said reservoir with said bore and said inlet and outlet ports in said spool valve means communicating said chamber with said bore, said ports being located such that said inlet port is disposed in communication with said dispensing port when said reduced thickness portion of said spool valve means is in full alignment with said water passage and said inlet and outlet ports are in communication with said water passage when said reduced thickness portion of said spool valve is only partially aligned with said water passage to allow a portion of the water passing through said water passage to flow through said chamber, said housing being comprised of an upper and lower housing which are detachably secured together to define said reservoir, auxiliary reservoir means mounted on said upper housing and having a substantially U-shaped configuration adapted to partially surround the water supply pipe, complementary passage means formed in said upper housing and said auxiliary reservoir and conduit means extending through said housing means for communicating the interior of said auxiliary reservoir with said dispensing port.

4,293,084

DISPENSING CONTAINER WITH INGREDIENT LEVEL INDICIA

Claude Lussier, 2825 Place Darlington, Apt. 3, Montreal, Quebec, Canada

Filed Oct. 26, 1979, Ser. No. 88,374


Int. Cl.³ G01F 11/26

U.S. Cl. 222—158

1 Claim

1. A dispensing and volume-measuring container for pourable ingredients comprising a body having relatively uniform,

light-permeable sidewalls, a bottom wall and a top having a free-pouring open spout, a single series of dual-functioning calibrated separate indicia on at least one of the sidewalls which always indicate the volume of pourable ingredients in relation to the level of the ingredients in said container, said



single series of indicia being arranged so that the plane of the horizontal level of said ingredients at a given volume always passes through a common point of intersection in the series of indicia at any position of the container when the container is moved between an upright and the pouring positions of the container.

4,293,085

TONER FEEDING DEVICE

Shunichi Nakajima, Yokohama, and Haruyoshi Hasegawa, Matsudo, both of Japan, assignors to Tokyo Shibaura Denki Kabushiki Kaisha, Kawasaki, Japan


Filed Jun. 12, 1979, Ser. No. 47,930

Claims priority, application Japan, Sep. 14, 1978, 53-126221[U]; Sep. 14, 1978, 53-126222[U]; Sep. 14, 1978, 53-126223[U]

Int. Cl.³ B65D 88/54; G01F 11/42

U.S. Cl. 222—311

13 Claims



1. A toner feeding device comprising:
a toner box having a toner outlet port formed at the bottom thereof;
a roller housed in the toner box in a manner to close the toner outlet port;
said roller being formed of a porous elastic material and serving to carry the toner housed in the toner box to the toner outlet port;
a toner catching plate engageable with said roller so as to bite a surface region of said roller so as to free toner from the pores thereof, said toner catching plate being mounted on a slidable member such that its degree of engagement with said roller is adjustable to control the flow of toner; and
at least a second toner catching plate, the biting edges of said toner catching plates being superimposed on one another.

4,293,086

APPARATUS AND METHOD FOR SEPARATING CASE FLAPS


Paul A. Fincher, 1042 #3 Reed Ter., Sunnyvale, Calif. 94086, and David R. Eklund, 3407 Victoria Ave., Santa Clara, Calif. 95051

Filed Apr. 11, 1980, Ser. No. 139,543

Int. Cl.³ B26F 3/02

U.S. Cl. 225—1

16 Claims



7. Apparatus for separating downturned flaps of a case joined by a tab and lying over sides of said case, which comprises:

a conveyor for moving the case through said apparatus, a first means for engaging one of the flaps, a first thrust means positioned proximate to said conveyor and connected to said flap engaging means for moving said flap engaging means against the side of the case over which the one of the flaps lies and below the one of the flaps, a first means for moving said flap engaging means along the side of the case until at least a portion of said flap engaging means extends between the one of the flaps and the side against which it lies, and a first means for retracting said flap engaging means with sufficient force to break the tab.

4,293,087

APPARATUS FOR INTRODUCING THE HEAD END OF A WEB INTO A TREATING STATION

Rolf Schmitz, Monchengladbach, Fed. Rep. of Germany, assignor to Jagenberg Werke, Dusseldorf, Fed. Rep. of Germany


Filed Mar. 28, 1980, Ser. No. 135,015

Claims priority, application Fed. Rep. of Germany, Apr. 19, 1979, 2915747

Int. Cl.³ B65H 17/34

U.S. Cl. 226—172

7 Claims



1. In an apparatus for the treatment of a web of material having rolls defining a conveying path for the web, the improvement comprising means for leading the head end of a web along the conveying path comprising means forming an endless loop on both sides of the conveying path, each having a run thereof extending along the conveying path and means connected across the two loops for securing the head end of a

web during the leading thereof along the conveying path, wherein the means for securing comprises a crossbeam connecting the two loops, the crossbeam comprising two rods and means mounting the rods with parallel axes for movement relative to each other between a closed position wherein the head end of a web is clamped therebetween and an open position wherein a clearance is obtained through which the head end can be threaded.

4,293,088

ELECTRONICALLY OPERATED PORTABLE FASTENER DRIVING TOOL


Edward E. Barrett, Massapequa Park; Steven Hahn, East Hampton; Albert Lensky, Fresh Meadow; Morris Pinczewski, New York, and Seymour Sobelman, Brooklyn, all of N.Y., assignors to Swingline Inc., Long Island City, N.Y.

Filed Oct. 12, 1979, Ser. No. 84,450

Int. Cl.³ B25C 1/06

U.S. Cl. 227-131

14 Claims



1. In an electrically powered driving tool having a hollow body comprising an elongated head portion for housing a cylinder, a solenoid, a magnetic plunger positionable in the cylinder, a driver blade and comprising a hollow handle portion projecting rearwardly from said head portion having trigger means and an electronic trigger control circuit mounted therein for producing two driving strokes to a fastener in response to actuation of said trigger means, a magazine for holding a plurality of fasteners secured to said head portion in driving engagement with said driver blade, means for preventing the advancement of a second fastener into the axial path of said driver blade while a first fastener is being driven the improvement comprising:

- (a) said hollow body being made of electrically insulating material;
- (b) a cavity in the magnetic plunger; and
- (c) a molded blade cap which is secured to the blade and in turn positioned in fitting engagement into a cavity in the plunger to structurally hold the cap and blade and to electrically insulate the blade from the plunger, whereby the blade is supported and insulated to prevent the conduct of electricity from the tool interior to the blade.

7. In an electrically powered portable fastener driving tool, the combination comprising: driving means for driving a fastener, a solenoid including a coil for producing a magnetic field and an armature connected to said driving means for propelling said driving means axially of the coil when the coil is energized, an electronic trigger control circuit connected to the solenoid for supplying the solenoid with two unidirectional current pulses from a source of alternating current supplied to the trigger control circuit, and means for preventing more than

one fastener from being driven during a single actuation of the tool, said trigger control circuit including:

- (a) unidirectional controlled conduction means for rectifying alternating current comprising at least three terminals including a gate;
- (b) first circuit means connecting said solenoid and said controlled conduction means in series with said source of alternating current;
- (c) switch means operable at random times relative to the cycles of said alternating current;
- (d) second circuit means controlled by said switch means for supplying current to said gate upon actuation of said switch means to place said controlled conduction means in a conductive state two times, firstly immediately following a properly poled half-cycle of said alternating current and secondly, immediately following the next such half-cycle, said circuit including a capacitor which supplies such current;
- (e) third circuit means for providing sufficient holding current to the controlled conduction means to enable the controlled conduction means to conduct during two successive like-poled half-cycles of said alternating current; and
- (f) fourth circuit means for draining sufficient current during the first two successive like-poled half-cycles of said alternating current to assure that no more than two successive current pulses are transmitted to the solenoid during a single actuation of the tool, said fourth circuit means including pulse means which pulses the gate and deactivating means which deactivates the pulse means.

4,293,089

BRAZING METHOD

James T. McCormick, Simi; Paul B. Ferry, Encino, both of Calif., and John C. Hall, Schaumburg, Ill., assignors to The United States of America as represented by the United States Department of Energy, Washington, D.C.

Filed May 8, 1979, Ser. No. 37,076

Int. Cl.³ B23K 1/04, 1/20

U.S. Cl. 228-215

14 Claims

1. A method of brazing a thin porous membrane selected from the class consisting of iron, nickel, copper and alloys thereof to a backing material comprising preselecting the surface area of the thin porous membrane to be brazed, soaking the thin porous membrane in a braze flow barrier dispersed in a volatile carrier and thereafter removing the braze flow barrier from the preselected porous surface area, preselecting the surface area of the backing material to be brazed, electrolessly plating a metal alloy on the backing material, placing said preselected surface areas in registered contact, heating in the absence of oxygen to a temperature in excess of the melting point of the electroless plated metal alloy for a time sufficient to volatilize the carrier and to form a braze joint between the preselected surface areas, and thereafter cooling to ambient temperatures to provide a brazed backing and porous membrane with the pores of the membrane being open except at the braze joint.

4,293,090

CONTAINER SEAM

Roland C. Gardner, Doylestown, Pa., and Ronald Mortellito, Monmouth Junction, N.J., assignors to Clevepak Corporation, White Plains, N.Y.

Filed Mar. 28, 1980, Ser. No. 135,146


Int. Cl.³ B65D 6/34, 3/10

U.S. Cl. 229-5.6

6 Claims

1. A sealed container having primary container wall means for defining an internal space and an opening at least at one end thereof, edge means extending about the opening at said at least one end for cooperating with an end closure for forming a seam about the opening; an end closure for closing the opening at said at least one end and forming together with said edge

means a seal sealing said container, said end closure having a substantially planar central section and a crimpable sealing periphery, said periphery having an outer reinforced area extending about said end closure in a predetermined area, said



seam having a vertically extending outer wall, said outer wall containing a plurality of spaced apart vertically extending reinforcing grooves extending around the entire outer wall and across the height thereof.

4,293,091

REINFORCED CONTAINER WITH INTEGRAL DIVIDER


Thomas J. Gerard, Winter Haven, Fla., assignor to Weyerhaeuser Company, Tacoma, Wash.

Filed Jan. 2, 1980, Ser. No. 108,976

Int. Cl.³ B65D 5/48, 5/50

U.S. Cl. 229-27

3 Claims



1. A container having an integral divider panel and reinforcing panels comprising

- first, second, third and fourth upstanding side walls, said first and third side walls being of equal width and said second and fourth side walls being of equal width,
- a divider panel extending between said first and third side walls,
- a first reinforcing panel extending along said first side wall from the junction of said first and fourth side walls to said divider panel, said reinforcing panel being the same height as said first side wall and being completely adhered to said first side wall, said reinforcing panel being attached to said divider panel;
- a second reinforcing panel extending along said third side wall from said divider panel to the juncture of the third side wall with the second side wall, said second reinforcing panel being the same height as said third side wall and being completely adhered to said third side wall, said second reinforcing panel being attached to said divider panel.

4,293,092

HEATING SYSTEM WITH HEAT PUMP AND AUXILIARY HEATER

Ernst Hatz; Heinz Eibl, both of Ruhstorf; Erwin Peter, Wendlingen, and Rolf Blumhardt, Wernau, all of Fed. Rep. of Germany, assignors to Motorenfabrik Hatz GmbH & Co. KG, Ruhstorf, Fed. Rep. of Germany


Filed Jul. 5, 1979, Ser. No. 54,913

Claims priority, application Fed. Rep. of Germany, Aug. 25, 1978, 2837248

Int. Cl.³ B60H 1/02; F24C 9/00

U.S. Cl. 237-12.1

6 Claims



1. In a heating system comprising a main heating network including a heat carrier and an internal combustion engine and a heat pump having a condenser, said condenser of said heat pump being driven by the internal combustion engine for supplying heat to said heat carrier of said main heating network, said internal combustion engine also driving an additional aggregate which transforms the mechanical drive power fed to it by the engine into heating power and transmits such heating power as additional heat to the heat carrier of said main heating network, the improvement comprising a circulating system which is self-contained and is separate from said main heating network, which circulating system incorporates said additional aggregate, said circulating system further incorporating a heat exchanger for transmitting the heat provided by the additional aggregate by way of a fluid which circulates in said circulating system to said heat carrier in said main heating network, means for scavenging heat energy from the coolant and exhaust gas of said internal combustion engine and supplying said heat to said main heating network, said additional aggregate being a fluid brake, said brake being mechanically driven by said internal combustion engine for operation at a speed proportional thereto, said separate self-contained circulating system including a regulating member associated with said fluid brake, said regulating member being a valve responsive to the surrounding temperature and hence to the heat required to be supplied by the main heating network, there being a relatively low surrounding temperature below which heat pump gas pressure and gas specific weight and therefore heat pump efficiency fall below a preselected limit and accordingly reduce loading of the engine to below a preselected limit, said regulating member being arranged for actuating said fluid brake at said relatively low temperature for thereby increasing the heat fed to said main heating network, by adding heat to said main heating network from said fluid brake and its separate circulating system, and also by increasing the amount of heat added to said main heating network from the exhaust gas and coolant of said engine due to increased engine loading.

4,293,093

CO-AXIAL FITTING FOR USE WITH A REFRIGERATION CIRCUIT HEAT RECLAIM APPARATUS


Glendon A. Raymond, Fulton; Fred V. Honnold, Fayetteville, and Herbert J. Spath, Clay, all of N.Y., assignors to Carrier Corporation, Syracuse, N.Y.

Filed Oct. 25, 1979, Ser. No. 88,319

Int. Cl.³ F24H 1/22; F25B 27/02

U.S. Cl. 237-19

7 Claims



1. Apparatus for preheating hot water for a hot water system using heat energy from a refrigeration circuit including a refrigerant to water heat exchanger, the hot water system including a tank adapted to contain a reservoir of stratified water such that warmer water is at the top of the tank and colder water is at the bottom of the tank, a tank outlet located in the top of the tank through which heated water is withdrawn and inlet means located in the top of the tank adapted to provide water to the tank which comprises:

- a fitting adapted to be connected to the tank outlet in the top of the tank, the fitting including;
- a conduit portion through which heated water from the tank may flow;
- a return line connected to the water outlet for supplying heated water from the heat exchanger to the tank, and
- a return line extension connected to the return line and extending through the top of the tank into the reservoir of water in the tank such that water from the heat exchanger is discharged into the reservoir a sufficient distance from the conduit portion to allow for mixing of the water from the heat exchanger with the water in the reservoir prior to the water from the heat exchanger being withdrawn from the tank outlet.

4,293,094

SUPPLEMENTAL HEATING SYSTEM


Hugh D. McGillis, 78 Manomet St., Brockton, Mass. 02401, assignor to Hugh D. McGillis, Brockton, Mass.

Filed Aug. 20, 1979, Ser. No. 67,815

Int. Cl.³ F24B 7/00

U.S. Cl. 237-55

6 Claims



1. A supplemental heating system for installation in a furnace flue which includes a flue pipe and a chimney, connecting the furnace to the atmosphere, said system comprising an inner pipe section, arranged to be connected in the flue, a sleeve

having a diameter appreciably larger than that of the pipe section and positioned concentric therewith, closure means connected between the ends of the sleeve and the wall of the pipe section for defining with the section and the sleeve an annular space; means defining a first opening in the sleeve; a blower mounted to the sleeve, said blower having its outlet communicating with said first opening such that air can be forced into said first opening in a direction substantially normal to the wall of the sleeve; one or more additional openings in the sleeve being circumferentially positioned from said first opening; a baffle connected between the outer wall of the pipe section and the inner wall of the sleeve and being circumferentially positioned approximately midway between said first opening and said one or more additional openings in said sleeve, said baffle extending longitudinally along said pipe section and substantially abutting said closure means whereby when the system is connected in said flue pipe between the furnace and the flue and the furnace is turned on, the hot products of combustion therefrom pass through the inner pipe section thereby heating it so that when the blower is turned on, the air discharged thereby into said annular space is forced in one direction around the outer surface of the inner pipe section thereby to heat the air as it is discharged through said additional openings.

4,293,095

AIR TREATING DEVICE


Peter W. Hamilton, Cincinnati, and William P. Lewis, Westchester, both of Ohio, assignors to The Procter & Gamble Company, Cincinnati, Ohio

Filed Nov. 9, 1979, Ser. No. 93,090

Int. Cl.³ A61L 9/04

U.S. Cl. 239-35

8 Claims



1. An air treating device having an indicator system to signal exhaustion of the operative fluid therein, said device comprising a reservoir containing the operative fluid and a signal fluid having a hue different from that of the operative fluid, and a substrate that is capable of capillary transport of each of said fluids from said reservoir to an evaporative surface portion of said substrate and that is in contact with both fluids simultaneously in use, at least a part of said substrate being visible when the device is in its operative mode, said fluids being immiscible and having relative surface tension properties and interfacial tension properties which require that the substrate in use first selectively transport substantially all of the operative fluid toward said evaporative surface portion prior to commencing transport of said signal fluid.

4,293,096

ARRANGEMENT IN A BURNER

Stellan Braun, Dalby, Sweden, assignor to AGA Aktiebolag, Lidings, Sweden

Filed Feb. 29, 1980, Ser. No. 125,924

Claims priority, application Sweden, Mar. 1, 1979, 7901836

Int. Cl.³ F23D 11/16

U.S. Cl. 239-419.3

3 Claims



1. In a cutting burner comprising a burner body for connection with a valve body to which supply lines for respective gases are connected, a nozzle, and a cutting oxygen gas channel, a heating oxygen gas channel and a burner gas channel being provided in the burner and connected with the nozzle, the improvement comprising a connection channel between the heating oxygen gas channel and the cutting oxygen gas channel, at least a part of the connection channel being of cross section much smaller than the cross section of the heating oxygen channel, and a check valve member located in said cutting oxygen gas channel before the connection channel, said connection channel and check valve member enabling a certain portion of the heating oxygen gas flow to permanently pass from the heating oxygen gas channel through the connection channel and the front part of the cutting oxygen channel toward the nozzle orifice, said certain portion of the heating oxygen gas flow preventing hot gases from passing up into the cutting oxygen gas channel from the heating procedure during use of the burner.

4,293,097

METHOD FOR BRIGHTENING NATURAL CALCITIC ORES

Herbert I. Lewis, Wrens; Anthony D. McConnell, Sandersville, both of Ga., and William M. Price, St. Austell, England, assignors to Anglo-American Clays Corporation, Sandersville, Ga.

Continuation-in-part of Ser. No. 868,392, Jan. 10, 1978, Pat. No. 4,165,840, and Ser. No. 892,931, Aug. 3, 1978, abandoned. This application Apr. 2, 1979, Ser. No. 26,362

The portion of the term of this patent subsequent to Aug. 28, 1996, has been disclaimed.

Int. Cl.³ B02C 23/18, 23/36, 23/38

U.S. Cl. 241-16

17 Claims

1. A method for processing a natural calcitic ore to yield a finely divided calcium carbonate particulate of relatively very high brightness characteristics, comprising in sequence the steps of:

- coarse-milling said natural calcitic ores to produce a coarse-milled product;
- subjecting said coarse-milled product as an aqueous slurry including less than 40% solids to a froth flotation, and separating with the froth discoloring contaminants;
- dewatering the underflow product from said froth flotation to at least 60% solids by weight; and
- wet-milling the dewatered product to yield an output prod-

uct wherein at least 80% by weight of the resultant particulate has an E.S.D. of less than 2 microns; said flotation step being conducted utilizing as a collector agent a 1-substituted-2-alkyl imidazoline or salt derivative thereof; and said collector agent being employed in conjunction with a promoter comprising a substantially non-polar aliphatic compound having from 10 to 20 carbon atoms in its longest straight chain.

4,293,098

RECOVERY OF ACTIVE CHITIN AND ENHANCED PROTEIN MEAL


H. S. Muralidhara, Falls Church, Va., assignor to Systems Consultants, Inc., Washington, D.C.

Filed Apr. 20, 1979, Ser. No. 31,846

Int. Cl.³ B02C 19/00

U.S. Cl. 241-19

4 Claims



1. In a process for recovering active chitin from shellfish waste consisting essentially of the steps:

- (a) drying said shellfish waste,
- (b) mechanically reducing the particle size of said dried shellfish waste to within the range of 10 to 400 microns,
- (c) subjecting the dried, reduced shellfish waste to the action of a gaseous stream to classify and separate a lighter fraction comprising active chitin and residual salts and a heavier fraction comprising protein and salts.

4,293,099

RECOVERY OF SILICON CARBIDE WHISKERS FROM COKED, CONVERTED RICE HULLS BY FROTH FLOTATION


Bhupendra K. Parekh, and William M. Goldberger, both of Columbus, Ohio, assignors to Silag, Inc., Greer, S.C.

Filed Jul. 2, 1979, Ser. No. 53,737

Int. Cl.³ B02C 23/18

U.S. Cl. 241-24

7 Claims



1. A method for separating silicon carbide whiskers produced from a high temperature conversion of rice hulls and

containing a mixture of silicon carbide whiskers with carbonaceous silicon carbide particles, consisting:

- (i) shredding the mixture in a controlled manner down to a specified particle size of approximately — 10 mesh in order to liberate the silicon carbide whiskers from the carbonaceous silicon carbide particles without removing the carbonaceous material coating from said carbonaceous silicon carbide particles;
- (ii) dispersing the shredded mixture in water so as to contain about 1 to 15% by weight of solids to form an aqueous mixture of hydrophilic silicon carbide whiskers and hydrophobic carbonaceous silicon carbide particles;
- (iii) agitating the aqueous mixture to further liberate said hydrophilic silicon carbide whiskers from said hydrophobic carbonaceous silicon carbide particles;
- (iv) adding surface active reagents to the aqueous mixture, which surface active reagents wet the carbon surface of said carbonaceous silicon carbide particles;
- (v) agitating the resulting water-reagent mixture;
- (vi) subjecting the water-reagent mixture to froth flotation having at least three stages;
- (vii) removing tailings therefrom containing water and silicon carbide whiskers and removing float therefrom containing reagents and carbonaceous silicon carbide particles; and
- (viii) performing a solid-liquid separation on the tailings, thereby obtaining silicon carbide whiskers from the aqueous mixture tailings.

4,293,100

APPARATUS FOR GANGING AND CUTTING A PLURALITY OF LAYERS OF STRIP MATERIAL

Roger C. Sharlow, Plano, Tex., assignor to Liquid Paper Corporation, Dallas, Tex.


Division of Ser. No. 906,441, May 17, 1978, Pat. No. 4,218,945.

This application May 29, 1979, Ser. No. 42,894

Int. Cl.³ B65H 19/04, 23/00, 23/10

U.S. Cl. 242—55

12 Claims



1. An apparatus for ganging and transporting a plurality of layers of strip material, comprising:

- supply means for feeding the layers of material therefrom, said supply means comprising rack means for supporting a plurality of rolls each with one of the layers of material thereon, roller guide means for receiving the layers of material thereover in a stacked relationship, and second roller guide means for maintaining the alignment of the stacked layers of strip material, said second roller guide means being aligned between said rack means and said drive roller means, said second guide means including a convex roller spaced from a concave roller with said rollers in contact with and on opposite sides of the layers of strip material as the layers move from said rack means to said guide plate means, said convex roller having a diameter intermediate of the ends greater than the diameter at the ends and said

concave roller having a diameter intermediate of the ends less than the diameter at the ends,

drive roller means for receiving a plurality of layers of strip material from said supply means in a stacked relationship, said drive roller means including a drive roller engaged against an adjacent driven roller for grabbing the layers of material therebetween to simultaneously draw all the layers of material beyond said drive roller means, and tension means associated with each layer of material for applying tension to said layers of material as the layers are fed into said drive roller means.

4,293,101

APPARATUS FOR HELICALLY COILING BANDS AFTER SLITTING WIDE STRIP


Vladimir I. Dunaevsky, ulitsa Oktyabrskoi revolutsii, 27, kv. 9; Nikolai G. Boidenko, ulitsa Lenina, 39, kv. 20, both of Slavyansk Donetskoi oblasti; Alexei P. Samarin, ulitsa Bolshaya Sadovaya, 60, kv. 4, Kramatorsk; Viktor M. Levit, pereulok Silikatny, 10, Slavyansk Donetskoi oblasti; Boris M. Zapara, ulitsa Vrachebnaya, 23, kv. 59, Kramatorsk; Boris N. Ivanov, ulitsa Profintern, 42; Sergel A. Frolov, pereulok Generala Batjuka, 3, kv. 54, both of Slavyansk Donetskoi oblasti; Rosislav A. Voronin, ulitsa Komsomolskaya, 25, Kramatorsk; Nikolai P. Belozerov, ulitsa Sotsialisticheskaya, 71, kv. 14, Kramatorsk; Valery I. Momot, ulitsa Voznesenskogo, 19, kv. 78, Kramatorsk; Jury A. Stusenko, ulitsa Yasnaya, 25, kv. 42, Slavyansk Donetskoi oblasti, and Vladimir A. Samoilov, ulitsa Vorovskogo, 233, Kramatorsk, all of U.S.S.R.

Filed Dec. 21, 1979, Ser. No. 105,960

Int. Cl.³ B65H 35/02; B21C 47/00

U.S. Cl. 242—56.4

4 Claims



1. In an apparatus for helically coiling bands after slitting a wide strip, comprising:

- a strip uncoiler, a strip-joining device, a slit for lengthwise slitting strips into bands, a coiler installed on a support for rectilinear movement and including a coiling drum having an axis arranged in a horizontal plane, a drum shaft freely carrying said coiling drum for rotation thereof on said shaft, a friction drive for said coiling drum actuating from said drum shaft, a hydraulic cylinder for reciprocal movement of said coiling drum in the direction of the axis of said coiling drum, and an electrohydraulic converter for controlling by said hydraulic cylinder the reciprocal movement of said coiling drum; a device for maintaining a constant slip in the friction drive of said coiling drum, including: a first ring and a second ring, each having ports in a portion adjacent their periphery, the first ring being installed on said coiling drum, and the second ring being installed on said drum shaft, a first yoke and a second yoke, each of which spacedly receives respective said portion of the first ring and of the second ring, said first yoke and said second yoke each having ports, and each being mounted on a support, and light transmitters and light receivers, one of said light transmitters and one of said light receivers being installed, respectively, at opposite portions of said first yoke and of said second yoke, respectively, on both sides of said first

ring and said second ring for transmitting and receiving, respectively, pulses representing the rotation speed of said coiling drum and of said drum shaft, respectively; a comparison circuit connected to each of said light receivers for comparing the number of said pulses representing the rotation speed of said coiling drum and of said drum shaft to deliver a control signal; a circuit for receiving the control signal from said comparison circuit and for controlling drive of said drum shaft and the rotation speed of said drum shaft; an electric control circuit for controlling said hydraulic cylinder for reciprocating movement of said coiler drum, and connected to said light receiver of said first yoke, and comprising: a comparison device for comparing an actual movement of said coiler drum with a predetermined movement, and connected to said electrohydraulic converter for regulating hydraulic mixture supply to said hydraulic cylinder for reciprocating said coiling drum, a pulse converter for converting said pulses from said light receivers into electric signals corresponding to said predetermined movement of said coiler drum, a coiling pitch setting device connected to said pulse converter, a setting device connected to said pulse converter for setting the number of convolutions in one layer of the coil being wound, and a coiler position detector for detecting actual movement of said coiler, and providing a corresponding signal as an input to said comparison device; a band tension regulator including a double-arm lever pivotally mounted on a support; a deflecting roller carried on one end of said lever; and control means connected to the other end of said double-arm lever, and having a control output, and responsive to a decline in tension of the bands passing around said deflecting roller for adjusting said control output; said control means comprising a hydraulic control circuit for controlling said hydraulic cylinder to control said friction drive, and comprising: a pressure regulator, and a further hydraulic cylinder having a piston provided with a first rod and a second rod, said rods being disposed on opposite sides of said piston, the first rod being pivotally connected with the other end of said double-arm lever, and the second rod being coupled with said pressure regulator.

4,293,102

REEL WEIGHT ASSEMBLY


Gerald J. Niles, St. Paul, and Norman C. Ritter, Mounds View, both of Minn., assignors to Minnesota Mining and Manufacturing Company, St. Paul, Minn.

Filed Jun. 13, 1980, Ser. No. 159,290

Int. Cl.³ B65H 75/18

U.S. Cl. 242—71.8

6 Claims



1. A weight assembly adapted for use with a polymeric reel

comprising a hub portion having opposite side surfaces, a through central opening between said side surfaces, and a plurality of sockets opening through one side surface of said reel and spaced around said through opening, said weight assembly comprising:

- a support plate having a central opening; a plurality of weights spaced around and projecting axially from one side of said support plate, said weights being shaped and spaced along said support plate so as to enter the sockets in a said reel hub portion when said weight assembly is brought coaxially adjacent one side surface of a said reel; and means for releasably attaching said weight assembly to a said reel with said weights in said sockets and said support plate adjacent said one side surface.

4,293,103

METAL WIRE WINDING APPARATUS


Kotaro Tsukamoto, 7-8, Kashima 4-chome, Yodogawa-ku, Osaka City, Osaka Prefecture, Japan

Filed Dec. 17, 1979, Ser. No. 104,463

Int. Cl.³ B21C 47/00; B65H 54/80

U.S. Cl. 242—83

2 Claims



1. A winding apparatus for metal wire comprising:

- a winding drum horizontally disposed on a base for winding turns of wire therearound; at least one carrier table disposed below said winding drum; a carrier guide mounted on said at least one carrier table for guiding said wire turns from said winding drum therealong onto said table, thereby forming a coil of said turns of wire on said table; a motor means mechanically connected to said winding drum for rotating said winding drum at a fixed rotational speed; an additional motor means mechanically connected to said at least one carrier table for rotating said table independently of said winding drum; wherein said rotational speed of said at least one carrier table is periodically varied in a step wise fashion in accordance with the following equation:

$$n(t_1+t_2)=n_1t_1+n_2t_2$$

where

- n =the rotational speed of said winding drum;
 n_1 =the maximum rotational speed of said at least one carrier table;
 n_2 =the minimum rotational speed of said carrier table;
 t_1 =the time during which said at least one carrier table rotates at the maximum rotational speed;
 t_2 =the time during which said at least one carrier table rotates at the minimum rotational speed.



4,293,104

HAND-HELD FISHING REEL

Armando Guim, 803 SW. 36 Ave., Miami, Fla. 33135
 Filed Apr. 28, 1980, Ser. No. 144,602
 Int. Cl.³ B65H 75/40

U.S. Cl. 242—96

6 Claims



1. A hand-held fishing reel comprising:
 a reel of predetermined diameter having an outer recessed circumferential surface defining a seat for a fishing line and a predetermined radius of curvature and an inner surface having an annular groove with a recessed surface of a predetermined diameter,
 said reel having a first side surface and a second side surface spaced from said first side surface and said side surfaces sandwiching the outer and inner surfaces at rim zones of juncture, defining a first and a second rim zone, respectively,
 the reel having a plurality of equispaced, generally coplanar, radially extending sockets extending depthwise into the inner surface,
 an assembly extending diametrically across the inner surface, said assembly having a first end and a second end, said assembly comprising,
 a first member having a first end, a second member having a first end, said first ends being of common size and dimension and each having an outer surface of a radius of curvature substantial equal to but slightly less than the radius of curvature of the recessed surface,
 each of said members extending toward but not to one another, and
 hand-grip means securing said members together with said first ends rotatably received in said annular groove for spinning movement of the reel relative to said assembly,
 a line guide means carried by said assembly and extending radially outwardly of said circumferential seat to guide a line, and
 detent means carried by said assembly and including a generally diametrically movable pin including means normally biasing said pin into an extended position and into one of said equispaced sockets and retractable to permit, selectively, free spinning of said reel relative to said assembly for normally maintaining said reel and assembly in a fixed position relative to one another.

4,293,105

BI-LEVEL WEB SENSITIVE RETRACTOR

Per O. Weman, Heverlee, Belgium, assignor to Allied Chemical Corporation, Morris Township, Morris County, N.J.
 Continuation of Ser. No. 753,764, Dec. 23, 1976, abandoned.
 This application May 19, 1978, Ser. No. 907,427
 Int. Cl.³ B65H 75/48; A62B 35/00

U.S. Cl. 242—107.4 B

7 Claims

1. In a safety belt retractor having a rotatable reel to which a seat belt is attached, said reel being journaled in a support adapted for attachment to the frame of a vehicle, said reel having as a flange at least one ratchet wheel, said reel being biased in the wind direction, and a pawl adapted to engage the ratchet wheel in the unwind direction in response to the action of an inertial device sensitive to an accelerating rate of rotation

of the reel, to halt rotation of the reel, the improvement which comprises: a webbing follower sharing the biasing means with the inertial device, whereby, when the reel of webbing is substantially full, the shared biasing means is under considerable tension, rendering the inertial device relatively insensitive

to an accelerating rate of rotation of the reel in the unwind direction, and when the roll of webbing on the reel has been substantially diminished by the withdrawal of webbing from the retractor, the bias is slight, rendering the inertial device more sensitive to an accelerating rate of rotation of the reel in the unwind direction.

4,293,106

EMERGENCY LOCKING SEAT BELT RETRACTOR

David L. Standing, Carlisle, England, assignor to Kangol Magnet Limited, Carlisle, England


Filed Sep. 11, 1979, Ser. No. 74,335

Claims priority, application United Kingdom, Sep. 11, 1978, 36311/78

Int. Cl.³ A62B 35/02; B65H 75/48

U.S. Cl. 242—107.4 A

4 Claims



1. A vehicle seat belt retractor, said retractor comprising:
 seat belt means;
 reel means rotatable in a first direction to wind said seat belt means thereon and in a second direction to unwind said seat belt means therefrom;
 spring means urging said reel means to rotate in said first direction;
 ratchet means carried by said reel means for rotation therewith;
 pawl means movable from a normal inoperative position spaced from said ratchet means to an operative position engaging said ratchet means to prevent rotation of said reel means in said second direction;
 a first rotatable member;
 means linking said first rotatable member to said pawl means so that rotation of said first rotatable member in a locking direction effects movement of said pawl means to said operative position thereof;
 a second member rotatable coaxially of said first rotatable member;

acceleration sensitive means responsive to at least one of a predetermined acceleration of the belt means in the unwinding direction and a predetermined acceleration of the retractor to rotate said second rotatable member in the locking direction;
 drive means operable between said first and said second rotatable members so that said rotation of said second rotatable member in the locking direction drives said first rotatable member to rotate in the locking direction,
 said drive means incorporating spring means acting between said first and said second rotatable members in opposition to said drive to thereby accommodate relative movement of said first and said second rotatable members needed to effect full engagement of said pawl means with said ratchet means.

4,293,107

TENSION RELIEVING SELECTIVE ENGAGEMENT MECHANISM WITH MEMORY


Avraham Ziv, Sepulveda, Calif., assignor to American Safety Equipment Corporation, San Fernando, Calif.

Filed Aug. 23, 1979, Ser. No. 68,944

Int. Cl.³ A62B 35/02; B65H 75/48

U.S. Cl. 242—107.7

23 Claims



12. An improved tension-relieving mechanism for use with a vehicle seat belt system having a rotatably journaled spool for windably retracting a seat belt and emergency locking means for preventing protraction of said seat belt in an emergency condition, said mechanism comprising:
 tension-relieving means operable in response to a single spool protractive movement for preventing retractive rotation of said spool;
 means for mounting said entire tension-relieving means for movement between spool connected and spool unconnected positions, said tension-relieving means being operable only when in said spool connected position; and
 manually operated means for selectively moving said tension-relieving means between said positions.

4,293,108

TAKE-UP DEVICE SPEED CONTROLLER USING MAGNETIC SENSING MEANS

Harry M. Randel, 574 W. Court, Scotch Plains, N.J. 07076

Filed Mar. 7, 1980, Ser. No. 128,141


Int. Cl.³ B65H 59/38

U.S. Cl. 242—189

14 Claims

1. A control system for controlling the speed of a take-up device upon which an elongated strip is being wound from a supply means, comprising:
 a slack indicating means provided between the supply means and the take-up device so that the strip passes over the slack indicating means, wherein the position of the slack indicating means along a predetermined path is determined by the amount of slack in the strip as it passes from the supply means to the take-up device;
 means for sensing the position of the slack indicating means

including a magnet coupled to the slack indicating means for movement with it, and a plurality of magnetically actuable means arranged along the predetermined path, wherein the operative condition of the magnetically actuable means is controlled by the position of the magnet relative to the magnetically actuable means; and



speed control means coupled to the magnetically actuable means for controlling the take-up device in accordance with the operative state of the magnetically actuable means.

4,293,109

PIVOTABLE CABLE GUARD FOR RETAINING A SWINGABLE-MOVABLE CABLE


Frank Bramwell, Hamden, Conn., assignor to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Sep. 19, 1979, Ser. No. 76,896

Int. Cl.³ B64C 27/04, 27/50

U.S. Cl. 244—17.11

6 Claims



1. Cable retaining apparatus for use in a system utilizing a tensioned cable passed around at least a pair of pulleys one of which is arcuately swingable relative to the other between open and closed positions comprising:
 an elongate radius arm mounted at one end on a pivotal axis and carrying at its other end an arcuately swingable pulley,
 an elongate cable guard member having a cable-retaining flange at one of its ends and an abutment flange at the other,
 said member extending lengthwise of said radius arm and being pivotally mounted medially of its ends on said arm with its retaining flange end closest to said pivotal axis of the arm; said arm and its guard member being so disposed that said retaining flange is carried into close proximity with the cable on the other of said pair of pulleys when said swingable pulley is in its closed position,
 a stop means for engaging said abutment flange in said closed position and pivotally fixing said retaining flange proximity, and

means for limiting the range of the pivotal movement of said retaining flange relative to said arm, said guard member disposition further being such that its retaining flange engages said cable as it moves from said closed to said open position and said pivotal range being such that the retaining flange can pivot responsively to said engagement an amount sufficient to relieve the engagement pressure and prevent undue cable bending.

4,293,110

LEADING EDGE VORTEX FLAP FOR WINGS


Wilbur D. Middleton, and John A. Paulson, both of Bellevue, Wash., assignors to The Boeing Company, Seattle, Wash.

Filed Mar. 8, 1979, Ser. No. 18,497

Int. Cl.³ B64C 23/06

U.S. Cl. 244—199

65 Claims



1. Apparatus for streamwise airflow control over the upper surface of an airfoil, comprising: said airfoil having a drooped leading edge segment; and means mounted forward on said drooped leading edge segment for generating a vortex airflow circulation on the forward facing surface of said drooped leading edge segment; said drooped leading edge segment being positioned at a forward and downward angle-of-deflection relative to said airfoil for confining said vortex airflow circulation to the forward facing surface area of said drooped leading edge segment, so as to control both the separation of the streamwise airflow and its re-attachment to the upper surface of the airfoil, downstream of said drooped leading edge segment.

4,293,111

BAG FILTER SUPPORT CAGE

Paul Henri, Sarnia, Canada, assignor to Kennecott Corporation, Stamford, Conn.


Continuation of Ser. No. 388,180, Aug. 14, 1973, abandoned.

This application Mar. 31, 1975, Ser. No. 563,537

Int. Cl.³ B01D 46/02

U.S. Cl. 248—95

2 Claims



1. A support cage for insertion into a filter bag for supporting said bag in an open condition, said support cage being

comprised of an elongated double ended tube formed of a bent sheet of open wire mesh and having opposite marginal portions disposed adjacent to each other and extending longitudinally of said tube, a fillet having channel means formed therein, said opposite marginal portions of said tube being disposed within said channel means, said fillet being clinched upon said opposite marginal portions and forming a smooth seam for minimizing snagging of said filter bag during contact of said support cage with said filter bag, said wire mesh including a plurality of wires extending longitudinally of said support cage and a plurality of wires extending peripherally of said support cage, wherein said wires extending peripherally of said support cage include hook-shaped end portions with said end portions being clinched by said fillet, and wherein said wires extending longitudinally of said support cage are disposed outwardly of and overlie the wires extending peripherally of said support cage such that said fillet, when engaged with said hook-shaped end portions, lies substantially flush with said wires extending longitudinally to form said smooth seam.

4,293,112

COMPACT MIRROR MOUNT


James A. Horton, Kennewick, Wash., assignor to Jersey Nuclear-Avco Isotopes, Inc., Bellevue, Wash.

Filed Oct. 29, 1979, Ser. No. 89,160

Int. Cl.³ G02B 7/18

U.S. Cl. 248—487

7 Claims



1. Apparatus for mounting and aligning an optical member on a support structure comprising: means for pivotally mounting such optical member onto such support structure in such a manner that the member can pivot about axes in two substantially orthogonal directions; first alignment means for pivoting said member about a first of said axes comprising (a) first and second surfaces on said member and said support structure, respectively, said surfaces being inclined to each other and being oriented for guiding said plunger means generally along a line through said pivotal mounting, and (b) first plunger means for moving between said surfaces thereby to rotate said member; and second alignment means for pivoting said member about the second of said axes.

4,293,113

UNIVERSAL FISHING ROD SUPPORT

David L. Gray, 720 Courtland, Richmond, Calif. 94805

Filed Nov. 5, 1979, Ser. No. 91,302

Int. Cl.³ F16M 13/00

U.S. Cl. 248—518


12 Claims

1. A fishing rod support comprising: means for receiving the handle of a fishing rod and restricting motion of said handle transverse to the axis of said rod; upper bracket means attached at a first end thereof to a normally upper portion of said receiving means, said

upper bracket means being capable of withstanding tension;

lower bracket means attached at a first end thereof to a normally lower portion of said receiving means, said lower bracket means being capable of withstanding compression, said lower bracket means being configured to straddle a vertical portion of a railing;

hooking means carried by said upper bracket means at a second end thereof, said hooking means being configured to pass over the outer portion of a vehicle door and downwardly into the space between the vehicle door and the vehicle window, said hooking means being further configured to fit over a horizontal portion of said railing to provide spaced support points; and



footing means carried by said lower bracket means at a second end thereof for confronting the outer surface of said vehicle door;

said fishing rod support being thus adapted to support said fishing rod from said vehicle door with said hooking means and said footing means together providing at least three points of contact with said vehicle door to provide a spaced stable attachment thereto, downward forces on said rod putting said upper bracket means in tension and said lower bracket means generally in compression to enhance the stability of said support; said fishing rod support being thus further adapted to support said fishing rod from said railing.

4,293,114

FLEXIBLE MOTOR MOUNTING


Robert E. Lykes, Troy, Ohio, assignor to A. O. Smith Corporation, Milwaukee, Wis.

Filed Oct. 10, 1978, Ser. No. 950,152

Int. Cl.³ F16M 13/00

U.S. Cl. 248—604

7 Claims



1. A flexible vibration dampening assembly for securing an electric motor having a main frame to a housing having bolt hole means therein to receive bolts and the dampening assembly being adapted to lie against the motor frame during shipping of the motor, which comprises at least one mounting arm of generally thin heat treated steel extending from the main

frame of the motor, an elongated hook disposed at the inner end of the arm with the axis of said hook being generally parallel to the axis of the motor, a mounting pad having bolt holes therein secured to the outer end of the arm and extending circumferentially of the axis of the motor, and a cold formed non-rotatable hinge pin fixed to the main frame of the motor prior to assembly of the mounting arm with the hinge pin and in slightly spaced relation therefrom, and the hook at the inner end of the arm being of substantially the same length as the hinge pin and latched over the hinge pin to secure the inner end of the arm to the latter but permitting rotation of the hinge pin to line up at least one bolt hole in the pad with the bolt hole means in the housing to receive a bolt to secure the mounting arm and housing together and at the same time permit the attachment of the generally thin heat treated steel mounting arm to the frame of the electric motor so as to completely eliminate the possibility of embrittlement of the mounting arm due to heat generated by a welding operation.

4,293,115

TESTING MECHANISM FOR BLOWOUT PREVENTER RAM LOCK


Glenn C. Parks, Jr., and Clark W. Beam, both of Houston, Tex., assignors to Hydril Company, Houston, Tex.

Filed Sep. 24, 1979, Ser. No. 78,092

Int. Cl.³ E21B 33/06; F15B 15/26

U.S. Cl. 251—1 A

8 Claims



1. In a blowout preventer having at least one blowout preventer ram movable therein to adjustable closed positions for sealing contact with a well pipe or the like in a bore of the blowout preventer, and having a ram lock comprising:

- (a) ram carrier means comprising a ram piston having a piston rod with a threaded surface formed thereon for moving the ram to the adjustable closed positions in the blowout preventer;
- (b) cylinder means for receiving opening and closing fluid pressures to operate against said piston to move the ram to and from open and closed positions, respectively;
- (c) lock means for locking said ram carrier means at the closed positions, comprising:
 - (1) a lock nut having a threaded surface formed thereon and engaged by said threaded surface on said ram piston tail shaft for rotational movement with respect thereto during movement of the ram;
 - (2) a ram carrier clutch plate mounted with said lock nut for rotational movement therewith, said clutch plate having ratchet teeth formed thereon;
 - (3) a body clutch plate having ratchet teeth formed thereon; and
 - (4) means for mounting said body clutch plate with the blowout preventer against relative rotational movement with respect thereto; and
- (d) means for urging said ratchet teeth of said body clutch plate and said lock nut clutch plate into engagement to lock said ram carrier means; and
- (e) means for unlocking comprising cylinder sleeve means

mounted in said cylinder enclosing said piston of said ram carrier means;

- (f) said cylinder sleeve means including surface means responding to the opening fluid pressure to engage said body clutch plate to disable said means for urging and unlock said ram lock;
- (g) the improvement comprising locking plug means for locking said cylinder sleeve means to permit testing of said lock means without allowing said lock means to become unlocked.

4,293,116

METALLIC SEAT ASSEMBLY FOR VALVES


John M. Hinrichs, Bryan, Tex., assignor to ACF Industries, Incorporated, New York, N.Y.

Continuation of Ser. No. 214, Jan. 2, 1979, abandoned. This application Sep. 19, 1979, Ser. No. 77,076

Int. Cl.³ F16K 25/00

U.S. Cl. 251-173

20 Claims



1. A seat assembly adapted to fit within an inner annular groove in a valve body having a closure member with a peripheral sealing surface movable between open and closed positions, said seat assembly comprising an annular metal housing having spaced inner end portions extending radially inwardly beyond the groove and a base portion at the bottom of the groove, each end portion flaring laterally outwardly of the groove and terminating at an end spaced laterally of the groove; and

a resilient soft seal mounted within the metal housing between the spaced inner end portions at a location to seal with said peripheral sealing surface in the closed position of the closure member, each end portion having a free unrestrained length and being flexible in both a radial direction and a lateral direction, each end portion adapted to contact in metal-to-metal sealing relation the adjacent peripheral sealing surface of the closure member when the closure member moves to a closed position and to be flexed radially and laterally outwardly by the closure member to maintain a tight sealing relation therewith.

4,293,117

PLUG VALVE ACTUATOR

John H. Mueller, Houston, Tex., assignor to Intercontinental Valve Manufacturing Company, Cincinnati, Ohio

Filed Apr. 13, 1979, Ser. No. 29,678


Int. Cl.³ F16K 31/50, 31/52

U.S. Cl. 251-229

8 Claims

1. In a plug-type valve having a body with a plug chamber and diametrically opposed inlet and outlet ports communicating with said chamber, a plug in said chamber having a transverse passage therethrough and an upstanding stem, said plug being shiftable between a first, upper, valve-open position with its transverse passage in alignment with said inlet and outlet ports and a second, lower, valve-closed position wherein the axis of said transverse plug passage is oriented at 90° to the axes of said inlet and outlet ports, seal means on said plug, said seal means being in engagement with the interior surface of said chamber about said inlet and outlet ports when said plug is in said second, valve closed position, a bonnet closing the upper end of said chamber, a packing gland mounted in said bonnet through which said plug stem extends, the improvement comprising

a yoke having a vertical axial bore therethrough, said yoke having a lower end affixed to said bonnet with the stem of said plug extending into said axial bore of said yoke, said yoke having an upper end, a bearing cap mounted on said upper end of said yoke, a drive nut having a vertical, threaded, axial bore, said drive nut being rotatively mounted in said bearing cap, a valve stem, the upper portion of said valve stem being threaded and being engaged in said threaded axial bore of said drive nut, said valve stem and said plug stem being coaxial, a single cylindrical coupling located within said axial bore of said yoke and being both rotatable and shiftable vertically therein, the lower end of said valve stem and the upper end of said plug stem both being non-rotatively affixed to said coupling, one of said yoke and said coupling having a single pair of diametrically opposed identical cam slots formed



therein, a cam follower for each of said cam slots being supported by the other of said yoke and said coupling, said cam slots being so configured that when said cam slots are located in said yoke they are in an inverted position from that which they occupy when located in said coupling, such that upon turning said drive nut in one direction, said plug in said valve-open position will be simultaneously partially lowered and turned 90° and thereafter lowered without rotation to said valve-closed position with said plug seals in engagement with said chamber interior surface about said inlet and outlet ports, and upon turning said drive nut in the opposite direction, said plug will first be lifted vertically without rotation out of sealing relationship with said chamber inlet and outlet ports and thereafter will be simultaneously lifted and rotated 90° to said valve-open position, whereby to provide a structure which is simple in construction, compact and self-locking.

4,293,118

MULTI-FUNCTION OPERATOR FOR CONTROL VALVE DEVICE

Paul E. Olson, and Michael D. Lyons, both of Lexington, Ky., assignors to American Standard Inc., Lexington, Ky.

Filed Nov. 26, 1979, Ser. No. 97,265

Int. Cl.³ F16K 31/524; F15B 13/04; F16H 53/00

U.S. Cl. 251-297


5 Claims

1. A control valve device comprising:

- (a) a valve assembly operable to deliver fluid pressure in accordance with the degree of deflection of said valve assembly from a normal position;
- (b) an operating handle assembly;
- (c) a cam member connected to said operating handle assembly for rotation in response to actuation thereof, the outer periphery of said cam member being engageable with said valve assembly and having a contour to effect said deflection of said valve assembly in response to rotation of said cam member; wherein the improvement comprises:
- (d) said cam member having adjusting means for altering the contour of said outer periphery thereof to accordingly

vary said deflection of said valve assembly and consequently the output fluid pressure of said valve assembly, said adjusting means comprising:

- (i) a carrier member connected to said handle assembly for rotation therewith;
- (ii) a pin projecting from one face of said carrier member;
- (iii) at least one cam segment pivotally connected to said pin and providing said outer periphery of said cam member; and



(iv) an adjusting screw threadedly carried by said carrier member and having a ball formed at one end for connection with said at least one cam segment at a socket thereof spaced apart from said pin, whereby said adjusting screw is adapted to effect rotation of said cam segment about said pin to vary the contour of the periphery of said cam member for a given position of said handle assembly.

4,293,119

TOOL FOR REMOVING STAPLES


John M. Diederichs, 3011 Ala Ilima, Apt. #203, Honolulu, Hi. 96818

Filed Jul. 31, 1980, Ser. No. 173,978

Int. Cl.³ B25C 11/00

U.S. Cl. 254-28

1 Claim



1. A tool for removing staples from wood and the like by clamping the staple to the tool as the staple is pried loose from the wood comprising:

- a. a first substantially rectilinear lever;
- b. a first tapered needle nose jaw;
- c. a first pivot operably connecting said first jaw to said first lever;
- d. a second tapered needle nose jaw;
- e. a second pivot operably connecting said second jaw to said first jaw in such a position that the end of said first lever adjacent to said first pivot can engage the end of said second jaw distant from the tapered needle nose whereby

relative movement of the first lever and the first jaw will open or close the space between said first and second jaws;

- f. a spring bias operably attached to the first and second jaws so as to normally open the space between the first and second jaws; whereby when the first jaw is forced between the bridge of a staple and the material to which the staple is anchored, and the second end of the first lever is forced in such a direction as to pry the staple out of said anchoring material, the relative movement between the first lever and first jaw will close the space between the first and second jaws thus clamping the jaws against the staple bridge as the staple is pried loose;
- g. a second rectilinear lever; and
- h. a third pivot operably connecting the second lever to the first lever at a point on the first lever near the end of the first jaw which is distant from the tapered needle nose and near the end of said second lever to which the second lever is pivotally connected whereby said first and second levers lie alongside one another and as they are squeezed together, the second lever abuts the first jaw to close the space between said jaws in a clamping action.

4,293,120

TIRE HOLDER AND BEAD EXPANDER


Robert R. Robins, 721 N. Woodland, Minneapolis, Kans. 67467

Filed Mar. 3, 1980, Ser. No. 126,923

Int. Cl.³ G01M 17/02; B60C 25/14

U.S. Cl. 254-50.2

1 Claim



1. A tire holder and bead expander, comprising: an upright generally rectangular frame, said frame including a standard at the respective corner of the frame interconnected at their upper limits by horizontal cross bars at respective lateral sides of the frame, a pair of horizontal elongated parallel spaced-apart base members respectively underlying the interconnected standards and having inclined upper edge surfaces at their respective ends projecting beyond the vertical axis of the respective standard,

an upwardly inclined ramp at one end of the frame supported by the base member inclined surfaces and terminating upwardly in the horizontal plane of the upper limit of the base members,

a pair of sleeves respectively connected in horizontal alignment to the interconnected standards intermediate their ends, and a pair of tubes respectively supported by said pairs of sleeves;

tire support roller means substantially coextensive with the spacing between said base members and transversely journaled by said base members intermediate their ends, said tire support roller means including, a pair of support rollers disposed in spaced relation, each support roller of said pair of support rollers having an axle journaled at its respective end portions by bearings overlying said base members, a pair of truncated conical members surrounding the axle adjacent the respective bearing with the truncated ends disposed in spaced confronting relation, and,

a cylindrical tread member loosely surrounding said axle and secured to the respective truncated conical member;

motor means drivably connected with at least one said support roller means;

tire bead engaging means pivotally supported by said base members for vertical pivoting movement toward and away from the central portion of said frame,

said tire bead engaging means including a pair of upstanding links pivotally supported intermediate their ends by said base members medially the spacing between said pair of support rollers,

a pair of arms respectively pivotally connected at one end portion with the upper end portion of the respective link of said pair of links,

the other end portion of each arm of said pair of arms being bifurcated and disposed in lateral diverging relation, and,

a tire bead engaging roller journaled by the end portion of the respective diverging arm opposite the respective said link;

fluid pressure operated means for moving said tire bead engaging means in opposing directions,

said fluid pressure means comprising, a pair of brake chambers respectively supported by said base members, each brake chamber of said pair of chambers having a piston pivotally connected with the depending end portion of the respective link of said pair of links;

a cross brace extending horizontally between said standards at the end of said frame opposite said ramp; and,

tire guiding means including a pair of elongated guide rollers journaled at one end portion by said cross brace and projecting in diverging relation into said frame on opposing sides of a tire when support by said support rollers.

4,293,121

WINCH ARRANGEMENT

Carl O. H. Wallin, Bergliden 20, S-131 42 Nacka, Sweden


Filed Sep. 11, 1979, Ser. No. 74,417

Claims priority, application Sweden, Aug. 10, 1979, 7906716

Int. Cl.³ B66D 3/02

U.S. Cl. 254-370

10 Claims



1. A winch arrangement comprising:

a feed device for feeding a hauling line through the winch arrangement, the hauling line having an ingoing part coupled to a load and feeding into the feed device, and an outgoing part leaving the feed device;

drive means for reciprocatingly driving said feed device;

said drive means including a pivotable lever for engaging the outgoing part of the hauling line and arranged to be pivoted from a first position to a second position by means of tension applied to the outgoing part of the hauling line for driving the feed device in the feed direction; and means coupled to said pivotable lever for automatically returning said pivotable lever from its second position back to its first position after each working stroke of said pivotable lever; and

said feed device including a non-return latch for selectively

preventing return movement of the hauling line through the feed device, and means for automatically releasing said non-return latch immediately upon commencement of each working stroke and for reengaging said non-return latch at the latest when said working stroke is completed.

4,293,122

PIPE RAILING SYSTEM

William J. Coleman, 645 Loudon Ave., Dunedin, Fla. 33528, and


Jay Logue, 2339 Orangeside Rd., Palm Harbor, Fla. 33563

Filed Jun. 13, 1979, Ser. No. 48,262

Int. Cl.³ E04H 17/14

U.S. Cl. 256-69

10 Claims



1. An improved pipe railing structure, comprising:

a first half-cylindrical, hollow body member having first and second terminal edges parallel with a cylindrical axis;

a first fastening member disposed along said first terminal edge of said body member, having a first fastening contour;

a second fastening member disposed along said second terminal edge of said body member, having a second fastening contour;

a first fastener anchorage member disposed along an inner surface of said body member, having a longitudinal recess therein parallel with said axis, for receiving and anchoring a fastener in said axial direction;

said first fastener anchorage member further comprising: an annular cylinder connected along one side to said inner surface of said first body member, having a longitudinal slot in the surface thereof to enable a threaded fastener to be axially anchored therein;

the structure further comprising:

a second half-cylindrical, hollow body member having first and second terminal edges parallel with said cylindrical axis;

a third fastening member disposed along said first terminal edge of said second body member, having a third fastening contour complementary to said first fastening contour of said first fastening member on said first body member;

a fourth fastening member disposed along said second terminal edge of said second body member, having a fourth fastening contour complementary to said second fastening contour of said second fastening member on said first body member;

a second fastener anchorage member disposed along an inner surface of said second body member, having a longitudinal recess therein parallel with said axis, for receiving and anchoring a fastener in said axial direction;

said first and third fastening members joining along their respective, complementary contours and said second and fourth fastening members joining along their respective, complementary contours to thereby join said first and second body members to form a unitary, cylindrical pipe railing;

said second fastener anchorage member further comprising: an annular cylinder connected along one side to said inner surface of said second body member, having a longitudinal

nal slot in the surface thereof to enable a threaded fastener to be axially anchored therein;

said first fastening contour of said first fastening member and said second fastening contour of said second fastening member being a male fastening contour;

said third fastening contour of said third fastening member and said fourth fastening contour of said fourth fastening member being a female fastening contour;

said first and second terminal edges of said first body member defining a reference plane;

said male fastening contour having a first planar surface approximately parallel with said reference plane, extending from said inner surface of said cylindrical body member from which it depends, a second planar surface intersecting said first planar surface at an acute angle forming an edge parallel with said axis, and a third planar surface intersecting said second planar surface at approximately a right angle and coincident with said terminal edge of said cylindrical body member from which it depends;

said female fastening contour having a first cantilever portion extending from said inner surface of said cylindrical body member from which it depends and terminating in a segment approximately perpendicular to said reference plane, a second cantilever portion extending from said segment and terminating in a second planar surface approximately parallel with said second planar surface of said male fastening contour, said first cantilever portion, said inner surface from which it depends, and said second cantilever portion forming a cavity with said body member inner surface therein forming a third planar surface approximately parallel with said third planar surface of said male fastening contour and said second cantilever portion having an inwardly facing first planar surface approximately parallel with said first planar surface of said male contour member, said first and third planar surfaces of said female fastening contour terminating in an opening for said cavity;

said male fastening contour being joined to said female fastening contour by forcing said second surface of said male contour against said second surface of said female contour thereby bending said first cantilever portion and said second cantilever portion of said female contour to enlarge said opening of said cavity to enable said edge of said male contour to enter said cavity through said opening and said first and third surfaces of said female contour to clamp against said first and third surfaces of said male contour, respectively.

4,293,123

BLOW LANCE

Fried Sauert, Bergisch-Gladbach, Fed. Rep. of Germany, assignor to Klöckner-Humboldt-Deutz AG, Fed. Rep. of Germany

Filed Dec. 20, 1979, Ser. No. 105,495

Claims priority, application Fed. Rep. of Germany, Dec. 22, 1978, 2855499

Int. Cl.³ C21B 7/16


U.S. Cl. 266-268

13 Claims

1. A lance assembly for directing treatment gas flows onto the surface of a molten metal bath, said assembly comprising:

a lance comprised of a casing having mounted therein a plurality of concentric feed tubes and a separate nozzle block having channels therethrough in direct, sealed fluid communication with downstream ends of said feed tubes,

a center channel in said nozzle block in fluid communication with a center feed tube, and



a removable, interchangeable central nozzle means mounted in said nozzle block and having a passage therethrough to receive fluid from said center channel.

4,293,124

SYSTEM FOR AUTOMATICALLY LOADING PLANAR FILM SHEETS ONTO A FILM POSITIONING DEVICE


David C. Bailey, Cocoa Beach, and Floyd F. Kessler, Indialantic, both of Fla., assignors to Harris Corporation, Melbourne, Fla.

Filed Aug. 24, 1978, Ser. No. 936,365

Int. Cl.³ B65H 9/10

U.S. Cl. 271-233

10 Claims



1. Apparatus for precisely positioning a planar film sheet at a known location, comprising: transporting means for transporting said film sheet along a film path; film stop means for blocking said path at a first location so as to prevent movement of said film sheet past said first location; film guide means for contacting the trailing portion of said film sheet after the leading portion has contacted said stop means so as to thereby confine said film sheet to a known location along said path; film locator means located transversely adjacent said known location; means for mechanically contacting said film sheet so as to force said film sheet transversely against said film locator means, whereby said apparatus precisely positions said film sheet precisely in two dimensions; film holding means for grasping said film sheet after said film sheet has been positioned; means for positioning said film holding means; and means for disengaging said film stop means, film guide means, and film contacting means from said film sheet after said film sheet has been grasped by said film holding means, so as to thereby permit said film sheet to be withdrawn by said positioning means; wherein said film holding means has a planar surface adapted to receive a portion of said film sheet, said holding means including means for applying a vacuum between said surface and said portion of said film sheet and further wherein said apparatus includes cam means for forcing said portion of said film against said surface so that said portion of said film sheet will be held firmly against said surface of said film holding means by said vacuum.


4,293,125

JUMP ROPE HANDLE

Robert S. Hinds, 1803 Regent St., Madison, Wis. 53705
Continuation-in-part of Ser. No. 866,818, Jan. 4, 1978,
abandoned. This application Jul. 27, 1979, Ser. No. 60,994
Int. Cl.³ A63B 5/20

U.S. Cl. 272-75

5 Claims



1. In a jump rope comprising a cord, two handles, said handles comprising apertures extending therethrough, said cord received in said apertures, said handles retained on said cord by an enlarged portion associated with said cord at each end and a plurality of bead members strung substantially solidly on said cord between said handles, each of said handles having an inner end and an outer end, the combination of a deep recess in the outer end of each of said handles, an annular surface portion at the inner end of each of said handles for retaining said cord in said handle by said enlarged portion bearing thereon disposed near the center of said handle, the inner end of each said aperture diverging substantially in the form of a bell to receive in engagement the adjacent portion of said cord during use of said jump rope, said bead members disposed next adjacent said handles configured with at least the handle-facing portions thereof configured substantially hemispherically to perform in contact with said handles in the manner of a ball and a hollow bell.


4,293,126

LEG WEIGHTS

Donald F. Havens, 1225 S. Chace Ct., Lakewood, Colo. 80226
Filed Mar. 20, 1980, Ser. No. 132,339
Int. Cl.³ A01B 21/26

U.S. Cl. 272-119

2 Claims



1. A one-piece latex rubber belt having a plurality of weights completely sealed therein, said weights including openings extending entirely therethrough, a layer of gauze positioned over said weights, a layer of liquid latex covering said gauze and filling the openings in said weights to completely seal said gauze and said weights, means for securing the ends of said belt around the ankle of a user comprising a plurality of openings in one end of said belt and a plurality of buttons secured to the opposite end thereof.


4,293,127

MONO-KINETIC EXERCISE DEVICE

Peter B. Dudley, Los Gatos, Calif., assignor to Mono-Kinetics, Los Gatos, Calif.
Continuation-in-part of Ser. No. 970,486, Dec. 18, 1978,
abandoned. This application Apr. 4, 1980, Ser. No. 137,809
Int. Cl.³ A63B 21/00

U.S. Cl. 272-133

21 Claims



1. An exercise device for mounting within a generally rectangular frame comprising:
a first elongated rope member extending in the plane of the frame;
a second elongated rope member extending within the plane of the frame;
fastening means for securely and rigidly fastening one end of the first and one end of the second rope member at opposite points within the frame with respect to the major axis of the frame;
support means for supporting the remote portions of the first and second elongated rope members at positions within the frame displaced in the direction of the major axis from the fastening means;
an exercise bar assembly slidably mounted upon the first elongated rope member and the second elongated rope member so as to provide frictional resistance to movement of said assembly at points on said rope members intermediate the fastening means and the support means said exercise bar assembly being substantially perpendicular to the major axis of the frame during an exercise; and
tensioning means for tensioning said rope members, said tensioning means being attached to the first elongated rope member and second elongated rope member such that the exercise bar assembly is intermediate the tensioning means and the fastening means.

4,293,128

CENTER OF GRAVITY-APPRAISAL BLOCK GAME

John C. Ebel, 525 Anchor Dr., Joppa, Md. 21085
Filed Nov. 5, 1979, Ser. No. 91,386
Int. Cl.³ A63F 9/00

U.S. Cl. 273-1 GF

2 Claims



1. In game apparatus employing a plurality of blocks for balancing, the improvement comprising: all said blocks being

respective identical oblique quadrangular prisms in shape; the proportions of each block being such as to permit stacking first and second of said blocks on the oblique faces thereof with the rectangular shape faces in-plane, without tipping over, but such as to cause tipping over of the stack when a third said block is added to the top of said stack with the rectangular shape faces thereof in-plane with those of the first and second blocks, a plurality of parallel-spaced indicia on each block parallel with one or more faces thereof but vertically inclined, said parallel spacing of the indicia being uniform; said proportions of each block being as follows: the ratio of the standing height to the perpendicular distance between rectangular faces being three-to-two, and the acute angles of the bases of the prism shape being substantially 75.5 degrees.

2. The method of playing a balancing game consisting of the steps:

- forming a stack of a plurality of identical blocks of oblique quadrangular prism shape;
- lifting the stack by the lowermost block thereof; and
- depositing the stack upon a single said block in balance preventing the stack from toppling over; thereby playing said balancing game.


4,293,129

GAME RACKETS AND PADDLES WITH NONPARALLEL PLAYING SURFACES

Leo N. Planakis, 1701 Pebble Beach Dr., Vienna, Va. 22180
Filed May 21, 1979, Ser. No. 40,924
Int. Cl.³ A63B 49/02, 59/04

U.S. Cl. 273-67 R

10 Claims



1. A game racket comprising a head and a handle, said head having two discrete, nonparallel strung surfaces, each of said strung surfaces being a mesh of tensioned stringing, said handle comprising a hand grip portion and a shank portion, said shank portion joined to the shoulder portion of said head, and the line of intersection of the planes of said strung surfaces being generally normal to and intersecting the longitudinal axis of said racket generally at the crown portion of said head, said head being formed of two generally oval frames, and said frames being fixedly joined at said crown portion.

4,293,130

GUARD FOR TENNIS RACKETS AND LIKE ARTICLES



Miroslav Beranek, 847 Constitution Dr., Foster City, Calif. 94404
Filed Feb. 12, 1979, Ser. No. 11,218
Int. Cl.³ A63B 49/14

U.S. Cl. 273-73 R

4 Claims

1. In combination with a racket having a frame, a length of resilient flexible homogenous material of sufficient thickness to act as a bumper and having a portion intermediate its ends of a thickness equal to at least one-third its width, said length being formed adjacent its ends with interengag-

ing elements to permit said length to be looped around the frame of a racket at the upper portion thereof with said interengaging elements holding said loop on said frame thereby providing a sufficient length of the material to protect the frame from damage due to striking an object,



said interengaging elements comprising an opening at one end adapted to receive the opposite end of said length therethrough and a protruberance at the opposite end adapted to engage the material of said length adjacent said opening.


4,293,131

ELECTRICAL AWARD SIGNALING MEANS FOR A PINBALL MACHINE

Marc M. Fellman, 1010 S. 67th St., and Wade S. Wright, 5648 Jones, both of Omaha, Nebr. 68106
Filed Dec. 27, 1977, Ser. No. 864,595
Int. Cl.³ A63D 13/00

U.S. Cl. 273-121 A

7 Claims



1. In combination, a pinball machine which includes an internal electrical circuit having an electronic award means including a solenoid actuated upon the accomplishment of a predetermined feat, a first electrical wire means electrically connected at one end to said internal electrical circuit and adapted for connection at the other end to a source of electric power, an award signaling circuit including a magnetic operated switch means positioned within the magnetic field of said solenoid for closing of said switch means in response to actuation of the solenoid, a relay, means operatively electrically connecting said switch means to said relay whereby the relay is energized in response to closing of said switch means, a signal means actuable for signaling to the area surrounding the machine that an award has been won, means for operatively electrically connecting said signal means to the relay for actuating said signal means when the relay is energized, and a second electrical wire means electrically connected at one end to said award signaling circuit and adapted for connection at the other end to a source of electric power, said award signaling circuit being free of any electrical

connection to said pinball machine circuit apart from said first and second electrical wire means.

4,293,132

SKIDWHEEL GAME


Louis J. Starr, 1460 S. Norton Ave., Los Angeles, Calif. 90019

Filed Jul. 30, 1979, Ser. No. 61,630

Int. Cl.³ A63F 3/00

U.S. Cl. 273-126 R

6 Claims



1. A skidwheel game comprising:
a longitudinally disposed generally flat surface having a design thereon;
said design comprising a plurality of zones, said zones being defined and separated from each other by boundary markers, said game including value indicating indicia associated with individual ones of said zones; and an automobile steering wheel having a central axis and a periphery, said wheel being adapted to be projected linearly with a reverse spin along the longitudinal axis of said surface so that the periphery of said wheel normally travels in contact with said longitudinally disposed generally flat surface whereby said wheel normally travels over said surface in first one direction and then rolls in a reverse direction in such a fashion that said wheel remains within said design and comes to rest within one of said zones, said reverse spin being about the central axis of said wheel and being in a direction which is opposite to that induced by the periphery of said wheel traveling over said surface in said first direction.

4,293,133
GAME DEVICE


Martin Baron, 7804 Skander Dr., Box 28222, Sacramento, Calif. 95828, and Ronald J. Retterer, 9030 Leatham Ave., Fair Oaks, Calif. 95628

Filed Jul. 7, 1980, Ser. No. 165,984

Int. Cl.³ F41J 1/00

U.S. Cl. 273-345

11 Claims



1. A game device comprising in combination:
a playing surface having game scoring indicia thereon defined by plural regions each having discreet values thereon,
a sealed chamber underlying and coextensive with said playing surface,
first magnetic means disposed within said chamber ran-

domly deployed and having a single polarity proximate to said playing surface,
and marker means magnetized of a polarity opposite to said first magnetic means proximate to said playing surface castable on said playing surface whereby when so cast, said marker means migrates towards said first magnetic means and on said regions thereby providing an indication.

10. A method for playing a game having a playing surface, and underlying chamber with plural magnets therein, the steps including:
shaking the chamber to reorient the magnets,
casting markers on the playing surface and computing a value reflective of the marker's relative disposition on the playing surface.

4,293,134
TOY

Andries Retief, 207 Nedholm Flats, Devenish St., Sunnyside, Pretoria, and Gert J. Zovitsky, 220 Uppingtonia Ave., Grootfontein, both of South Africa


Filed Dec. 20, 1979, Ser. No. 105,675

Claims priority, application South Africa, Dec. 28, 1978, 78/7361

Int. Cl.³ A63B 65/00

U.S. Cl. 273-428

11 Claims



1. A flight article comprising a rod; a weight; a flexible element connected to one end (referred to as the head end) of the rod and to the weight; and a flight (also referred to as the larger flight) of a manufactured material connected to the rod, in which the ratio of the surface area of one side of the larger flight to the total mass of the article is about 1000 square millimeters to one gram.

9. A flight article comprising a rod, a weight, a flexible element, and a flight of manufactured material (also referred to as the larger flight), said flexible element is connected to one end of said rod (referred to as the head end) and to the said weight, said flight is connected entirely asymmetrically to said rod, an additional flight connected to that end of the rod (the tail end) which is remote from the head end, said two flights are spaced apart along the axis of the rod, the spacing being between one-fifth and two-fifths of the rod length.

4,293,135
SEGMENTED SEAL

Joseph E. Wallace, Calabasas, Calif., assignor to Parker-Hannifin Corporation, Cleveland, Ohio

Filed Feb. 25, 1980, Ser. No. 124,391


Int. Cl.³ F16J 15/02

U.S. Cl. 277-9

9 Claims

1. A sectional gasket comprising a junction member, an extension member, said junction member having a center region and two end portions, said end regions each having a recess, said recesses each having parallel laterally inwardly facing sealing surfaces spaced a predetermined distance apart, and said extension member having parallel laterally outwardly facing sealing surfaces spaced a predetermined distance apart

and extending continuously along its entire axial extent, whereby said extension member is adapted to be laterally



severed at any location along its entire axial extent and sealingly received in one of said recesses.

4,293,137

MAGNETIC LIQUID SHAFT SEALING


Frederick D. Ezekiel, 75 Allen St., Lexington, Mass. 02173

Filed Dec. 11, 1978, Ser. No. 968,370

Int. Cl.³ F16J 15/16, 15/40

U.S. Cl. 277-80

10 Claims



1. Magnetic liquid shaft sealing apparatus for sealing between a shaft and a housing comprising,
thin permanent magnet means characterized by a cross section having a thickness dimension between opposed end faces of the magnet means that is smaller than a height dimension and magnetized along an axis parallel to said thickness dimension for establishing a magnetic field along at least one exposed surface thereof between said end faces which magnetic field is generally parallel to said axis, and a closed loop of magnetic fluid along said at least one exposed surface maintained thereat by said magnetic field thereat,
said magnetic liquid sealing apparatus forming a sealed assembly which consists of in combination a housing member and a shaft member in relative rotational relationship wherein said thin permanent magnet means is a single thin permanent magnetic disc formed with an opening enclosed by a peripheral exposed surface closely adjacent to and surrounding said shaft member and being axially magnetized,
said magnetic disc being mounted on said housing with said peripheral surface being in closely spaced, rotatable relationship with said shaft member,
said closed loop of magnetic fluid being a quantity of magnetic liquid occupying and limited to the space between said shaft member and said peripheral surface by the field of said magnetic disc,
whereby said shaft member is arranged for rotating in contact with said closed loop of magnetic liquid whereby relative rotation with said permanent magnetic disc may occur while said closed loop of magnetic liquid seals the gap therebetween.

4,293,138

SEALING DEVICE

Klaus B. M. Swantee, Mt. Eemnes, Netherlands, assignor to Pidou B.V., Mt. Eemnes, Netherlands

Filed Sep. 11, 1979, Ser. No. 74,322

Claims priority, application Netherlands, Sep. 12, 1978, 7809260

Int. Cl.³ F16J 15/10; F16L 17/02


U.S. Cl. 277-207 A

6 Claims

1. A seal construction for a rotating hub nose seal for the nose of the hub of a torsional vibration damper of the type having an outer inertia ring, a radially intermediate elastomer member, and an innermost hub member, the seal being of the type including an elastomer seal lip having a portion surrounding and being in surface engagement with the hub nose at an axial portion of the hub, the improvement comprising, the hub being formed of aluminum, the hub nose having an anodized solid lubricant coating at least at its surface of contact with the said elastomer seal lip, the said coated hub nose having a surface roughness in the range of 60-70 micro inches, whereby the rotary seal between the elastomer seal lip and the rotating hub nose functions in a manner equivalent to a conventional rotating hub nose construction wherein the hub is formed of cast iron having an uncoated surface roughness in the range of 10-20 micro inches.

1. A cylindrical sealing device which seals in an excellent manner though easy to mount and remaining reliably in place without extra fixation means being provided for sealingly connecting coaxial conduits and the like of a conduit arrangement including a first conduit and a second conduit sealed mutually in situ, wherein said second conduit is disposed a predetermined distance coaxially in said first conduit to provide between them an annular space adapted to receive said sealing device radially between the first and second conduits having different diameters, said sealing device comprising in combination:
a longitudinal hollow body member of elastic material un-

compressible per se and including two separate parts together being cylindrical in complementary relationship to each other with a central axis therein;
a plurality of first unflexible projections only compressibly arranged circumferentially on and projecting radially outwardly from said hollow body member, with the outer diameter of said first projections being selected to be greater than the inner diameter of said first conduit to effect said sealing connection; and



a plurality of second unflexible projections only compressibly arranged circumferentially in and projecting radially inwardly towards the central axis of said hollow body member, said second projections projecting to an imaginary circle having a diameter which is at most equal to the outer diameter of said second conduit, with at least one of said first projections and at least one of said second projections being arranged when pressed together to transmit compression forces at least in part in a common radial section of a predetermined axial length.


4,293,139

POWER STEERING PUMP POWERED LOAD LEVELER
Arthur K. Brown, South Bend, Ind., assignor to The Bendix Corporation, Southfield, Mich.

Filed Dec. 17, 1979, Ser. No. 104,597
Int. Cl.³ B60G 17/04

U.S. Cl. 280—6 H

10 Claims



1. A load-leveling mechanism for controlling the separation of a sprung mass and an unsprung mass of a vehicle, the load-leveling mechanism comprising:

- a source of fluid pressure;
- a fluid-receiving extendible strut connected between the masses for controlling the separation of the masses depending upon the fluid pressure within the strut;
- a housing defining a first chamber communicated with the fluid pressure source and with a fluid reservoir and defining a second chamber communicated with the first chamber and with the strut;

first valve means for controlling communication between the second chamber and the strut;
first servo means for operating the first valve means;
second valve means movable within the first chamber for controlling communication of the second chamber with the reservoir and with the fluid pressure source;
second servo means for operating the second valve means; and
sensor means for sensing the separation of the masses and operatively connected to the first and second servo means, the sensor means and the first and second servo means cooperating with the first and second valve means to control the fluid pressure within the extendible strut to thereby maintain the separation of the sprung and unsprung masses substantially within a predetermined range.


4,293,140

AUTOMOBILE SPLASH GUARD AND ATTACHMENT MEANS THEREFOR

Ted A. Bell, Coshocton, and Daniel F. Lehner, Lafayette, both of Ohio, assignors to Pretty Products, Inc., Coshocton, Ohio
Filed Dec. 4, 1978, Ser. No. 966,505
Int. Cl.³ B62D 25/16

U.S. Cl. 280—154.5 R

22 Claims



1. A splash guard assembly for an automotive vehicle having a thin, sheet-form mounting plate extending in a generally vertically oriented direction at a wheel opening thereof comprising

a sheet-form guard member adapted to be supported on said mounting plate and having an elongated marginal edge portion of a configuration to be co-extensive with said mounting plate, said guard member provided with at least two sockets formed in the marginal edge portion and disposed in relatively vertically spaced relationship along the marginal edge portion and a predetermined distance relatively inward of a peripheral edge thereof, and

fastening means for securing said guard member to the vehicle mounting plate including a fastening clip secured in each of said sockets, each of said clips being fabricated from an elongated, flat strip of resilient material folded into a predetermined shaped configuration having first and second legs defining respective independent clamping elements, said fastening clips each including an interconnecting bar with said first and second legs connected to opposite ends thereof and extending in superposed relationship thereto to receive the guard member and mounting plate between respective ones of said first and second legs and said interconnecting bar, said first leg adapted to project through a selected one of said sockets to frictionally engage with said guard member in clamped relationship and said second leg adapted to mechanically couple with the vehicle mounting plate in clamped relationship.

22. A splash guard assembly for an automotive vehicle having a thin, sheet-form mounting plate extending in a generally vertically oriented direction at a wheel opening thereof comprising

a sheet-form guard member adapted to be supported on said mounting plate and having an elongated marginal edge

portion of a configuration to be coextensive with at least a portion of said mounting plate, said guard member provided with at least two sockets formed in the marginal edge portion and disposed in relatively vertically spaced relationship along the marginal edge portion and a predetermined distance relatively inward of a peripheral edge thereof, and

fastening means for securing said guard member to said mounting plate including a fastening clip secured in each of said sockets, each of said clips having first and second legs and an elongated interconnecting bar carrying said first and second legs, said interconnecting bar and said first leg formed from an elongated, flat strip of resilient material folded into a U-shaped configuration, thereby defining a clamping element adapted to receive a sheet-form mounting plate in edgewise clamped relationship therebetween and to mechanically interengage therewith, said first leg secured to and resiliently biased toward said interconnecting bar and extending in superposed, substantially coplanar relationship thereto at one side thereof, said second leg carried by said interconnecting bar at a side thereof opposite to said first leg and adapted to project through a selected one of said sockets, said second leg including a clamping surface extending in superposed relationship to said interconnecting bar to mechanically engage with said guard member and clamp said guard member in secured relationship to said interconnecting bar and to thereby secure said guard member with said mounting plate in supported relationship.


4,293,141

FRAME FOR LIGHTWEIGHT BICYCLE
Frank Brilando, Niles, Ill., assignor to Schwinn Bicycle Company, Chicago, Ill.

Filed Feb. 22, 1979, Ser. No. 14,075
Int. Cl.³ B62K 3/04, 19/06

U.S. Cl. 280—281 R

2 Claims



1. A frame for a high performance light weight bicycle, comprising a head tube, and top and bottom tubes having their forward ends secured to said head tube and extending rearwardly therefrom, with the major portions of said top and bottom tubes being round, and the forward end portions thereof being oval with a lateral width the same as the diameter of said round portions as a minor axis and tapering rearwardly from a maximum major axis adjacent said head tube.

4,293,142

VIBRATION DAMPED SKI

Alan J. Davignon, Vashon, Wash., assignor to K-2 Corporation, Vashon Island, Wash.

Filed Jul. 16, 1979, Ser. No. 57,576
Int. Cl.³ A63C 5/12

U.S. Cl. 280—610

6 Claims

1. In a ski having a top surface and a bottom surface, the improvement comprising a vibration damping core disposed between the top and bottom surfaces, said core including a thin layer of viscoelastic material fixedly positioned at the neutral

axis of the ski at every point along the length of said core, wherein:

said core includes an upper constraining layer of high modulus of elasticity material which is bonded to the upper surface of said layer of viscoelastic material; and a lower constraining layer of high modulus of elasticity material which is bonded to the lower surface of said layer of viscoelastic material; and



said core further includes an upper core layer of lightweight, low modulus of elasticity material disposed above said upper constraining layer of rigid material; and a lower core layer of lightweight, low modulus of elasticity material disposed below said lower constraining layer of rigid material.

4,293,143


SKI BINDING FOR CROSS-COUNTRY SKIS

Arne W. Johansen, Oslo, Norway, assignor to Adidas Fabrique de Chaussures de Sport, Dettwiller, France

Filed Apr. 19, 1977, Ser. No. 788,880
Int. Cl.³ A63C 9/08

U.S. Cl. 280—615

2 Claims



1. A ski binding for a boot having a converging toe and laterally opening slots at each side of a forward portion of the sole of the boot comprising: a toe iron to be fixed to a ski, said toe iron being adapted to receive the forward portion of the boot upon forward movement of the boot relative to the toe iron; a locking device comprising a U-shaped bowed rod of spring material having rearwardly extending legs resiliently urged toward each other, each leg having an end bent to extend downwardly substantially perpendicular to the ski; mounting means mounting said locking device for pivotal movement of said legs from a lowered boot retaining position in which said ends of the legs engage in said slots, to an elevated boot releasing position in which said ends of the legs are vertically above said slots to permit rearward withdrawal of the boot; said mounting means including means mounting said legs while in said lowered position, to flex outwardly in response to forward insertion of the boot between the leg ends and to resiliently engage in said slots upon alignment of the slots with the leg ends, so that the boot can be moved into and locked in the toe iron without first moving said leg ends upwardly to said released position; and spring means for urging said leg ends to said lowered boot retaining position.

4,293,144

PROTECTIVE HANDRAIL FOR FOLDING BABY CARRIAGE

Minoru Ida, Yamatokoriyama, Japan, assignor to Manten Co., Ltd., Osaka, Japan


Filed Mar. 4, 1980, Ser. No. 127,061
Int. Cl.³ B62B 7/08

U.S. Cl. 280—644

3 Claims

1. A folding baby carriage or the like structure comprising a

pair of side frames each having an upper bar and a lower bar pivoted to said upper bar and carrying a wheel at lower end thereof, a pair of leg members pivoted to said upper bar near the lower end thereof and carrying a wheel at lower end thereof, two X-shape coupling elements each having two intersecting members, said X-shape coupling elements each having their inner corresponding ends pivoted to said leg members near the lower end thereof and their outer end piv-



oted to said side frames, and a lockable toggle bar pivoted to and between said leg members for keeping said coupling elements extended, further comprising a protective means comprising a pair of first bars having their one end pivoted to said upper bars, a pair of second bars pivoted to the other end of the first bars, a coupling bar pivoted to and between said second bars, and a flexible tube for covering the protective means to protect the baby's finger.

4,293,145


AUXILIARY LIFT AXLE WHEEL ASSEMBLY

Glenn E. Taylor, 1345 Bankhead Ave. NW., Atlanta, Ga. 30318
Continuation-in-part of Ser. No. 882,234, Feb. 28, 1978, Pat. No. 4,166,639. This application May 8, 1979, Ser. No. 37,326

Int. Cl.³ B60G 11/56

U.S. Cl. 280—704

10 Claims



9. A lift axle wheel assembly comprising an axle, and at each end of said axle a wheel for engaging the ground surface, a housing for connection to the frame of a vehicle, an approximately L-shaped lift lever pivotally mounted at the intersection of its arms to said housing about an axis approximately parallel to the axis of rotation of said wheel, said L-shaped lift lever including an upwardly extending arm and an arm extending longitudinally with respect to the direction of travel of said wheel, a saddle assembly mounted on the longitudinally extending arm of said lift lever, resilient connection means connecting said saddle assembly to said lift lever, said axle being mounted at one of its ends to said saddle assembly, a pneumatically inflatable means mounted on said saddle assembly and

bearing against said housing to urge said lift lever in a first pivotal direction with respect to said housing to move the wheel downwardly toward the ground surface, and spring means mounted in said housing and positioned over the longitudinally extending arm of said lift lever and having one end portion thereof resiliently bearing against the upwardly extending arm of said lift lever to urge said lift lever in a second pivotal direction with respect to said housing to move the wheel upwardly away from the ground surface.

4,293,146

VMP CASING TIEBACK


Pierre A. Beynet, Tulsa, Okla.; James E. Lucksinger, Carbonale, Colo., and Martin B. Jansen, Jr., Houston, Tex., assignors to Standard Oil Company (Indiana), Chicago, Ill.

Filed Oct. 4, 1978, Ser. No. 948,466

Int. Cl.³ F16L 35/00

U.S. Cl. 285—24

11 Claims



1. A tieback tool with self-energizing seal for sealingly securing a first tubular member suspended from a vessel floating on a body of water to a casing hung in a wellbore in the bottom of the body of water comprising:

- a male tubular member having a J-slot on its exterior and a neck having a wall thickness t_1 and an outer cylindrical surface;
 - a female tubular member adapted to fit over said male tubular member and having a lug on the interior thereof insertable into said J-slot to prevent relative longitudinal movement of said members, said female tubular member having a section overlying the neck of said tubular member with a wall thickness of t_2 which is greater than t_1 , the inner surface of said neck of said male tubular member being free of contact with said section of said female tubular member; and
 - a seal sealingly engaging the outer cylindrical surface of said neck of said male tubular member and said section of said female tubular member
- the thickness t_1 to extend from terminal end of said neck to beyond said seal whereby for a given internal pressure said neck of said male tubular member expands radially more than said section of said female tubular member.

4,293,147

METHOD AND APPARATUS FOR SECURING A PIPE TO A FITTING


Ronald S. Metcalfe, Sale, and John M. Greig, Whitley Bay, both of England, assignors to RM Fabrications Limited, Skelmersdale and British Gas Corporation, London, both of, England
Filed Mar. 30, 1979, Ser. No. 26,138

Claims priority, application United Kingdom, Mar. 31, 1978, 12782/78

Int. Cl.³ F16L 35/00

U.S. Cl. 285—39

2 Claims



1. A method for connecting a plastic pipe to a fitting incorporating an externally grooved insert, the insert being a tight fit in the pipe, comprising pushing a sleeve onto the pipe and away from the pipe end, forcing the insert into the end of the pipe by gripping the pipe in a first element of a clamp, supporting the fitting in a second element of the clamp with the insert coaxial with the end of the gripped pipe, and moving the first and second elements of the clamp towards each other; wherein said sleeve is positioned on the pipe between said first and second elements of the clamp, and thereafter forcing the sleeve to the end of the pipe by releasing the grip of the first clamp element on the pipe, and again moving said first and second clamp elements towards each other such that the first clamp element slides along the pipe, engages the sleeve and pushes the sleeve onto the pipe end, so that the pipe end is tightly gripped between the insert and the sleeve.

4,293,148

PILE CONNECTOR

Lionel J. Milberger, Spring, Tex., assignor to FMC Corporation, Chicago, Ill.

Filed Feb. 20, 1980, Ser. No. 123,158

Claims priority, application United Kingdom, Feb. 22, 1979, 06369/79


Int. Cl.³ F16L 37/14

U.S. Cl. 285—90

10 Claims

1. A mechanical pipe connector comprising:
a tubular inner member having a wall with a first groove cut in an outside face thereof;
a tubular outer member having a wall with a second groove cut in an inside face thereof and at least one hole extending through said outer member wall and communicating with said second groove, said outer member also having a passage to receive said inner element with said first and said second grooves juxtaposed to form a common annular channel between said inner and said outer members;
a flexible locking tape insertable through said hole into said annular channel, said tape having a shape to fill said channel and lock said inner and said outer members together, said tape and said annular channel each having a polygon cross-sectional shape with internal obtuse angles to minimize the stress concentration on said tape and on the walls

of said channel as a separating force is applied between said inner and said outer members; and



4,293,149

RAPID COUPLING FOR PLASTIC PIPES

Federico A. Bonel, Barcelona, Spain, assignor to Industrias Neoplast, S.A., Barcelona, Spain


Filed Sep. 27, 1979, Ser. No. 79,593

Claims priority, application Spain, Oct. 2, 1978, 238468

Int. Cl.³ F16L 17/02

U.S. Cl. 285—111

5 Claims



1. A coupling device for a pipe comprising:

- (a) a male piece of generally cylindrical cross-section, said male piece having an end portion, said end portion having slots therein defining tongues;
- (b) a female piece of generally cylindrical cross-section, said female piece having an opening for receiving said pipe and a longitudinally extending seat for receiving the end portion of said male piece, the end portion and the seat being arranged to cause the tongues of said end portion to be deflected radially inwardly when said end portion is received by said seat, said female piece further including an inner wall disposed substantially concentrically inwardly of said seat said inner wall having slots therein defining tongues and being arranged to deflect outwardly in response to said pipe penetrating said female piece, the tongued inner wall and said end portion interlocking to form a fluid-tight seal.

4,293,150

FLUID CONDUIT ASSEMBLY

Irving D. Press, West Orange, N.J., assignor to Resistoflex Corporation, Roseland, N.J.

Filed Jan. 17, 1977, Ser. No. 760,108


Int. Cl.³ F16L 39/00, 33/20

U.S. Cl. 285—149

9 Claims

1. A fluid conduit assembly comprising a fluid conduit with end fittings at opposite ends, characterized in that said conduit

includes at least two snug-fitting concentric pipes each of which is independently impervious to fluid, the outermost being solid metallic and the innermost being non-metallic, and



said end fittings each have separate portions joined, respectively, to a different one of both of said pipes with a separate fluid tight seal therebetween.

4,293,151


CONNECTORS FOR ELECTRICAL CABLES

Ernest V. Manzel, 2235 76th Ct., Elmwood Park, Ill. 60635

Filed Sep. 22, 1977, Ser. No. 835,482

Int. Cl.³ F16L 3/04

U.S. Cl. 285—161



1. A connector for an electrical cable having an electrically conductive sheath, said connector comprising a tubular electrically conductive generally cylindrical connector body, said connector body having a rear end portion with clamping means thereon for clamping the sheath of the electrical cable within said connector body to afford solid electrical contact between said connector body and the sheath, said connector body having a threaded front end portion with external screw threads thereon, and an internally threaded nut in screw threaded engagement with said front end portion, said connector body having an intermediate portion with a plurality of conductive latching arms slanting outwardly and forwardly therefrom, said intermediate portion of said connector body being between said front end portion and said rear end portion which are at opposite ends of said connector body, said conductive latching arms having front ends, said latching arms being resiliently yieldable to pass through an opening in a conductive mounting wall and to snap outwardly behind such wall, said nut being operable to bring said nut and the front ends of said latching arms into clamping arrangement with the opposite sides of such wall to afford solid electrical contact between said arms and the wall, the front end portion of the cable being insertable into said rear end portion of said connector body with the cable threaded forwardly through the opening in the mounting wall, said clamping means being operable from the front side of the mounting wall for clamping the sheath of the electrical cable within said connector body, said rear end portion and said intermediate portion of said connector body and the cable clamped therein being movable rearwardly through the opening in the mounting wall to cause the latching arms to pass rearwardly

through the opening and to snap outwardly behind the wall, said rear end portion of said connector body and said clamping means being of a cross-sectional size smaller than the cross-sectional size of said intermediate portion with said latching arms whereby said rear end portion and said clamping means are adapted to fit through the opening in the mounting wall, said nut being operable from the front side of the mounting wall to tighten the nut and the front ends of said latching arms into clamping engagement with the front and rear sides of such wall to afford solid electrical contact between said arms and the wall, whereby access to the front of the mounting wall is all that is needed for clamping the connector body to the conductive sheath and for solid clamping of the mounting wall between said latching arms and said nut, there being no need for access to the rear of the mounting wall.

4,293,152

FLEXIBLE PIPE-CONNECTING FITTING

Hans Berghöfer, Alte Landstrasse 274, 2000 Hamburg 65, Fed. Rep. of Germany


Filed Apr. 3, 1978, Ser. No. 892,387

Claims priority, application Fed. Rep. of Germany, Apr. 4, 1977, 2714963

Int. Cl.³ F16L 51/02

U.S. Cl. 285—229

30 Claims



1. A flexible pipe-connecting fitting for connecting two pipe ends located opposite to and at an axial distance from each other, comprising an elastically deformable tubular hose member having a radially outwardly bulging central portion, two substantially cylindrical transition portions adjoining said central portion at the opposite axial ends thereof, and two holding portions each adjoining a corresponding transition portion at the axially outer end thereof and projecting radially outwardly beyond its corresponding transition portion, each of said holding portions having at its radially outer end a radially inwardly projecting sealing web which sealingly abuts upon assembly an annular end face of the respective pipe end and together with the respective holding portion forms an inner annular groove; a separate reinforcing bellows of elastomeric material surrounding said bulging central portion of said hose member in surface contact therewith and having two end portions each abutting the respective transition portion of said hose member and having a conical outer surface; and two annular connecting members each engaging behind the respective holding portion of said hose member and arranged to be secured to a corresponding pipe end, each of said connecting members having an abutment web for abutting upon assembly directly against an end face of the respective pipe end, an inner annular

groove provided at its side remote from said central portion of said hose member and accommodating the respective holding portion of the latter, an inner margin abutting the respective transition portion of said hose member, and a support collar having an outwardly projecting resiliently deflectable lip resiliently abutting said conical outer surface of the respective end portion of said reinforcing bellows in an axial direction thereof.

by said arc gases whereby venting of said gases is accomplished:

4,293,153

PANELBOARD VENT ASSEMBLY


Harris I. Stanback; Theodore L. Brann, and Larry D. Polston, all of Lexington, Ky., assignors to Square D Company, Palatine, Ill.

Filed May 7, 1979, Ser. No. 36,954

Int. Cl.³ E05C 19/06


U.S. Cl. 292—85

10 Claims



1. An improved vent assembly for an enclosure including a door pivotally supported on said enclosure adjacent one edge of said door to move another edge of said door to a closed position and to an open position to enable access to a circuit interrupting device in said enclosure, said device generating arc gases exerting pressure for moving said door from said closed position to said open position in response to a fault current passing through said device, the improvement comprising:

an elongate planar spring steel member assuming a serpentine configuration and having a main body portion, a projecting main latch portion and a resilient bend having a reduced cross section from said main body portion resiliently connecting said latch portion to said body portion, said main latch portion having a latch shoulder located between said main latch portion and said body portion; support means for supporting said member in a first position on said door with said latch portion located adjacent said other edge and projecting toward said enclosure in response to the movement of said other edge to said closed position; means for optionally moving said latch portion towards said other edge, said spring member automatically returning said latch portion to said first position; a latch passage in said enclosure with said latch passage spaced for receiving said latch portion in response to movement of said other edge to a closed position; and detent means located between said latch passage and said one door edge for interlocking engagement between said latch shoulder and body portion in response to the engagement of said latch portion in said latch passage with said member in said first position, said latch portion including a nose in camming relationship with said detent means urging said latch portion towards said other edge and aligning said latch with said latch passage in response to movement of said other edge to a closed position, said latch being received by said passage upon movement of said other edge to a closed position and said latch automatically returning to said first position whereby said latch shoulder engages said detent means, said resilient latch portion adapted to flex to provide limited movement of said door from said closed position in response to the generation of a predetermined amount of pressure caused



4,293,154
SAFETY LOCK FOR WINDOW SASHES AND THE LIKE
Melvin K. Cassells, 67 Vinehill Rd., Elmwood, Conn. 06110
Filed Sep. 28, 1979, Ser. No. 79,793

Int. Cl.³ E05C 1/04

U.S. Cl. 292—144

8 Claims

1. In combination, a pair of relatively movable members having a selected position in which portions of said members overlap, a safety lock for preventing relative movement of said members away from said selected position comprising a cylindrical sleeve, an elongated bolt of greater length than the sleeve slidably received in the sleeve, an enlarged head at one end of the bolt adapted to abut against one end of the sleeve and having substantially the same outer diameter as the sleeve, one of said positions which overlap at the selected position of the members having a through hole registering with a mating hole partially extending through the other of said portions, said sleeve having a press fit with the said through hole and being of shorter length than the drilled hole and being positioned in the hole with its outer end spaced inwardly from the outer surface of the member surrounding the periphery of the hole with the head of the bolt substantially flush with said outer surface, said bolt being of sufficient length to extend into the mating hole when the head of the bolt is flush with said outer surface and also when the bolt is partially withdrawn sufficiently to permit the head of the bolt to be grasped manually, and detent means operative between the sleeve and bolt for yieldably retaining the bolt in a fully inserted locking position in the sleeve, a partially withdrawn locking position in the sleeve, and a further withdrawn unlocking position.

4,293,155

LOG HANDLING AND TRANSPORT SYSTEM


Peter S. Grant, Federal Way, Wash., assignor to Weyerhaeuser Company, Tacoma, Wash.

Filed Nov. 19, 1979, Ser. No. 95,859

Int. Cl.³ B66C 1/12

U.S. Cl. 294—75

11 Claims



1. An apparatus for handling and transporting loads of elongated objects, comprising: transport means having space on board for receiving and stowing flexibly unitized loads of elongated objects, at least a pair of slings, each extending about the load of

objects and having lengths greater than the peripheral distance about the load and spaced toward the ends of the objects, having eyes in each end and means for releasably connecting the eyes together into a unitary sling, an elongated frame having spaced pairs of releasable grasping means depending downwardly therefrom for sequential attachment and detachment to individual eyes in corresponding slings, and means for lifting the frame with a load of elongated objects resting within the slings and having the grasping means attached to the eyes of the slings.

4,293,156
HOOK

Jean-Pierre Chapalain, 8-18, rue de Mery, 95310 Saint-Ouen L'Aumone, France


Filed Jul. 11, 1979, Ser. No. 56,616

Claims priority, application France, Aug. 3, 1978, 78 22949

Int. Cl.³ B66C 1/36

U.S. Cl. 294—82 R

3 Claims



1. A load hoisting hook pivotally mounted under a suspension ring having a convex hub-like portion surrounding a pivot member and a depending shank extension adapted to act as a safety pawl of which the free end is adapted to engage the free end of the hook in order to convert the latter into a closed ring, said hub portion having a blind hole and a recess formed therein in spaced relation to one another, means for locking said pawl in a closed hook position with the free end of said pawl engaging the free end of said hook comprising a rectilinear lock bolt having an inner end and adapted to slide in a rectilinear bore formed in the thickness of a backward extension of the hook, and a coaxial spring encircling said bolt and constantly urging said inner end of said bolt into said blind hole, a handle pivotally attached to the backward extension of the hook and to the rear end of said sliding lock bolt to facilitate the retraction of said bolt against said spring to withdraw the inner end of said bolt from said blind hole to permit the inner end of said bolt to engage said recess under the action of said spring to lock said pawl in an open hook position.

4,293,157

SPLIT CABLE GRIP CLOSURE AND METHOD OF FORMING SAME

Alfred W. Fidrych, Stonington, Conn., assignor to Harvey Hubbell Incorporated, Orange, Conn.

Filed Oct. 22, 1979, Ser. No. 87,150


Int. Cl.³ F16L 3/00

U.S. Cl. 294—86 CG

18 Claims

1. A cable grip comprising: a tubular body portion comprising a split sleeve adapted to enclose a cable and formed of a plurality of flexible, elongated members interwoven to form an open mesh structure with two series of loops, one series along each longitudinal edge of said split sleeve, said mesh structure of said body portion being capable of varying in a radial direction to increase and decrease the cross-sectional area enclosed thereby, said two series of loops being longitudinally aligned and

interfingered except for two adjacent end loops at one end of said two longitudinal edges; and locking means for interconnecting said two series of loops, said locking means comprising a flexible locking member coupling said two adjacent end loops together and extend-



ing through each of the remaining longitudinally aligned and interfingered loops, said flexible locking member comprising two elongated elements, both of which extend through each of the remaining longitudinally aligned and interfingered loops in a side-by-side relationship.

4,293,158

GATE WITH RAMP DEVICE FOR LIVESTOCK TRAILER WITH LIFT DECK


Mack A. Lewis, Sioux City, Iowa, and Mike R. Spencer, Hubbard, Nebr., assignors to Wilson Trailer Company, Sioux City, Iowa

Filed Oct. 12, 1979, Ser. No. 84,117

Int. Cl.³ B62D 33/04

U.S. Cl. 296—24 C

3 Claims



1. In a compartment for transporting and storing livestock having two sidewalls, a base floor and at least one platform disposed between said sidewalls and being vertically movable within said compartment; a framework pivotally connected to one of said sidewalls for movement between a first position transversely of said compartment and a second position adjacent one of said sidewalls; a lower gate; a first hinge means connecting said lower gate to said framework for movement about a horizontal axis; an upper gate; a second hinge means connected to said framework and vertically spaced from said first hinge means, said second hinge means being connected to said upper gate for pivoting said upper gate about a horizontal axis; a rod hingedly connected to said upper gate and to said lower gate; a ramp hingedly connected to said at least one platform, and further including a plurality of gates hingedly connected to a second one of said sidewalls, said plurality of

gates being vertically spaced and capable of movement between a position transverse of said compartment aligned with said framework and a position adjacent said second of said sidewalls, and a deck support member attached to and movable with said framework, said deck support member including height adjustment means for effecting vertical adjustment of said deck support member, said deck support member further including one angle member having a plurality of keyhole slots formed therein and a pair of support plates attached to said framework and containing a plurality of projections for interconnection with said keyhole slots, said angle member being transversely positionable with respect to said support plates so as to optionally locate said deck support member in positions whereby the same will not interfere with rotational movement of the operably associated gates.

4,293,159


FLEXIBLE WIND DEFLECTOR

John A. Bott, 931 Lakeshore Dr., Grosse Pointe Shores, Mich. 48236

Filed May 16, 1979, Ser. No. 39,263

Int. Cl.³ B62D 37/02

U.S. Cl. 296—91



1. In an article carrier for roof top mounting on an automotive type vehicle, a pair of mounting rails for mounting on the surface of the vehicle roof to extend lengthwise of the vehicle, and a relatively resilient wind deflector to extend transversely of the length of the vehicle and adapted to direct air flow down across the rear side of the vehicle, means attached to said deflector along the entire length thereof for mounting the wind deflector on said mounting rails so that it extends transversely of the length of the vehicle and so that it is deformable under influence of wind in the direction of the length of the vehicle.

4,293,160

SIDE GUARD FOR MOTOR VEHICLE

Hans Lütze, Aidlingen; Helmut Weisschappel, Sindelfingen; Wolfgang Klie, Korntal, and Dieter Weidemann, Weil der Stadt, all of Fed. Rep. of Germany, assignors to Daimler-Benz Aktiengesellschaft, Stuttgart, Fed. Rep. of Germany

Filed Jul. 25, 1979, Ser. No. 60,479

Claims priority, application Fed. Rep. of Germany, Aug. 18, 1978, 2836213


Int. Cl.³ B62D 25/02

U.S. Cl. 296—188

8 Claims

1. A lateral protection arrangement for side doors of a motor vehicle, the arrangement including at least one reinforcement means arranged within each of the side doors of the vehicle so as to extend substantially in a longitudinal direction of the vehicle, each of the reinforcement means being adapted to be braced responsive to an application of a compressive force effective in a longitudinal direction of the vehicle, one of directly and indirectly against a fixed vehicle component,

characterized in that means are provided for adjusting a length of the reinforcement means so as to bridge a space between an



end of the reinforcement means and the fixed vehicle component.

4,293,161

VEHICLE ROOF

Alfons Lutz, Emmering, Fed. Rep. of Germany, assignor to Webasto-Werk W. Baier GmbH & Co., Munich, Fed. Rep. of Germany


Filed Dec. 14, 1979, Ser. No. 103,713

Claims priority, application Fed. Rep. of Germany, Dec. 23, 1978, 2856015

Int. Cl.³ B60J 7/10

U.S. Cl. 296—213

19 Claims



1. Vehicle roof with an aperture surrounded by a frame, a sliding top displaceable by drive cables being guided by means of sliding blocks in said frame, and with a headliner covering the vehicle roof on an interior side thereof, characterized in that the frame is formed of synthetic resin and comprises, on the one hand, sliding surfaces for the sliding blocks and, on the other hand, guide ducts for the drive cables; and that an underside of the frame facing the interior of the vehicle constitutes at least in part the headliner, wherein portions of the frame constituting said headliner, at least in part, are unitarily formed with parts of said frame comprising said sliding surfaces and guiding ducts.

4,293,162

SUN SHADE FOR INFANT SEAT AND THE LIKE

Joe P. Pap; Marilyn D. Pap, both of 19742 Trident La., Huntington Beach, Calif. 92646; Arvil L. Beyler, and Doris M. Beyler, both of 10331 Calle Independencia, Fountain Valley, Calif. 92708

Filed Mar. 17, 1980, Ser. No. 130,750


Int. Cl.³ A47C 7/62

U.S. Cl. 297—184

4 Claims

1. A sun-shade device for infant seats and the like defining a canopy that is adjustable vertically, horizontally and angularly, wherein the device comprises: a frame structure having a peripheral frame member, including a pair of parallel longitudinal strut members; a canopy cover adapted to be removably supported by said frame structure; a linear-adjusting means slidably mounted to said strut member, whereby said frame structure may be adjusted longi-

itudinally along said strut members, wherein said linear-adjusting means comprises:
 a housing having an upper plate and a lower plate secured together by support members; and
 restraining means mounted in said housing and adapted to slidably receive said strut members for longitudinal movement therein;



a universal connecting means mounted to said linear adjusting means to allow said canopy to be arranged at a selected angular position; and
 a multi-adjustable support structure attached between said universal connecting means and said seat.

4,293,163

VALVE FOR CLOSING THE FLUID PASSAGE OF A WELL BORE TUBULAR MEMBER WITH BALANCED OPERATING ARRANGEMENT


Britt O. Braddick, Houston, Tex., assignor to Texas Iron Works, Inc., Houston, Tex.

Filed Apr. 26, 1977, Ser. No. 790,959

Int. Cl.³ F16K 39/00

U.S. Cl. 251-283

3 Claims



1. A valve arrangement for the fluid passage of a tubular member used in a well bore wherein the tubular member has a lateral, circular opening with an annular shoulder intermediate the ends of the opening, the valve arrangement including:

- spherical core means rotatably mounted in the tubular member;
- operating means connected to said spherical core means and rotatably supported in the tubular member to open and close said spherical core means for controlling flow through the fluid passage of the tubular member;
- seal means between said spherical core means and tubular

member and between said operating means and tubular member;

- said spherical core means and operating means having fluid passage means for conducting fluid from the fluid passage of the tubular member to act on said seal means between said operating means and tubular member for substantially counterbalancing the fluid pressure in the tubular member acting on said operating means;
- said operating means fitting in the circular opening in the tubular member and including:
 - disc means having a non-circular opening therein and a projection extending laterally thereof;
 - retainer means having a circular opening therein;
 - a cylindrical member having a first annular portion fitting on one side of the shoulder in the circular opening in the tubular member; a second annular portion of larger diameter than the first annular portion and abutting the shoulder in the circular opening in the tubular member; a third annular portion having a diameter smaller than the first annular portion and fitting in the circular opening of said retainer means; and a non-circular portion extending from said third annular portion and fitting in the non-circular opening of said disc means;
- said spherical core means having a recess on the outer surface thereof with which said projection on said disc means is engaged; and
- said first annular portion of said cylindrical member having a non-circular surface facing outwardly of the lateral opening in the tubular member whereby said cylindrical member of said operating means may be engaged and rotated whereupon said spherical core means may be rotated to open and close the fluid passage in the tubular member.

4,293,164

BRAKE CONTROL CIRCUIT WITH PARKING AND RETARDING VALVES


Wayne A. Hoefer, Blue Springs, Mo., and Paul J. Tanty, Manhattan, Ill., assignors to Caterpillar Tractor Co., Peoria, Ill.
 PCT No. PCT/US79/00599, § 371 Date Aug. 13, 1979, § 102(e)
 Date Aug. 13, 1979, PCT Pub. No. WO81/00387, PCT Pub. Date Feb. 19, 1981

PCT Filed Aug. 13, 1979, Ser. No. 93,075

Int. Cl.³ B60T 15/16

U.S. Cl. 303-13

29 Claims



1. In a fluid control circuit (10) having fluid actuated coupling means (15) for being actuated upon controlled communication of pressurized fluid thereto, and first valve means (25) for controlling the level of pressurized fluid in said coupling

means (15) and the degree of engagement thereof, said first valve means (25) having an inlet (28) connected to said coupling means (15), the improvement comprising

- a pilot line (20),
- second valve means (47) for actuation between a closed position and an open position venting pressurized fluid at the inlet (28) of said first valve means (25) and connected to said pilot line (20), and
- third valve means (19 or 22) for closing said pilot line (20) and said second valve means (47), or for venting said pilot line (20) to open said second valve means (47) to vent pressurized fluid at the inlet (28) of said first valve means (25) and in said coupling means (15).

4,293,165

ELECTRONIC CONTROL BRAKE AND SKID CONTROL SYSTEM


Edgar A. Hirzel, Granada Hills, Calif., assignor to Crane Co., New York, N.Y.

Filed Jan. 26, 1978, Ser. No. 872,654

Int. Cl.³ B60T 8/20

U.S. Cl. 303-93

27 Claims



1. In a braking system having a valve driver and a brake pressure modulating servo valve, a brake and skid control comprising:

- brake command means for generating a brake command signal indicative of a commanded brake pressure;
- skid control means for generating a skid control signal which is independent of said brake command signal; and
- modification means responsive to said brake command signal and said skid control signal for providing to the valve driver a modified brake command signal indicative of a modified brake pressure, wherein said modification means includes means for setting said modified brake pressure to a value less than said commanded brake pressure by an amount which is a function of both said brake command signal and said skid control signal.

4,293,166

ROLLING BEARING FOR RELATIVE LINEAR MOVEMENT ON A SHAFT

Horst M. Ernst, Eltingshausen; Armin Olschewski, Schweinfurt; Rainer Schürger, Schwanfeld; Lothar Walter, Schweinfurt; Manfred Brandenstein, Aschfeld, and Erich Burkl, Stammheim, all of Fed. Rep. of Germany, assignors to SKF Kugellagerfabriken GmbH, Schweinfurt, Fed. Rep. of Germany
 Continuation of Ser. No. 925,947, Jul. 19, 1978, abandoned. This application Mar. 31, 1980, Ser. No. 135,317

Claims priority, application Fed. Rep. of Germany, Aug. 23, 1977, 260312; Jul. 19, 1978, 925947

Int. Cl.³ F16C 29/06


U.S. Cl. 308-6 C

12 Claims

1. In a rolling bearing for relative linear movement between the bearing and a cylindrical machine element, with several continuous courses of spool shaped rolling bodies distributed about the circumference of a multipart annular body, the improvement wherein barrel shaped guide rollers are positioned to float between the spool shaped rolling bodies, the guide

rollers held in continuous line contact with the roll surfaces of adjacent rolling bodies, the distance between the longitudinal axes of adjacent rolling bodies being less than the sum of the distances between the longitudinal axis of a guide roller between said adjacent rolling bodies and the longitudinal axes of said adjacent rolling bodies continuously throughout said courses.

12. In a rolling bearing for linear movement with respect to a machine element having a cylindrical surface, wherein a plurality of rolling elements are mounted to engage said surface, the central portions of the rolling elements having longitudinal cross sections with concave central portions, and the rolling bearing having means for guiding said rolling elements to follow a continuous path including linear path sections for



loaded and unloaded elements joined by turn-around path sections; the improvement wherein said bearing further comprises a plurality of separating rollers having convex longitudinal cross section adapted to engage the concave regions of said rolling elements in mutually continuous line contact, with one of said separating rollers between each pair of adjacent rolling elements and separating said rolling elements from mutual contact, the axes of said rolling elements and separating rollers being parallel, wherein said rolling elements and rollers are packed to hold the axes of said rollers closer to said machine element than the axes of said rolling elements in said linear path for loaded elements and to hold the axes of said rollers further from said machine element than the axes of said rolling elements in said linear path for unloaded elements.

4,293,167

ROLLING CUTTER DRILL BIT WITH IMPROVED JOURNAL CONFIGURATION


Terry H. Mayo, and John D. Parrish, both of Houston, Tex., assignors to Reed Tool Company, Houston, Tex.

Continuation of Ser. No. 876,969, Feb. 13, 1978. This application Mar. 24, 1980, Ser. No. 133,221

Int. Cl.³ F16C 17/12

U.S. Cl. 308-8.2

5 Claims



1. A rolling cutter drill bit comprising:
 a bit body;

at least one lug extending downward from said body; each said lug having a journal shaft formed thereon, said shaft extending downward and comprising: a cylindrical radial bearing portion defining the main diameter of said shaft, a single, generally flat, free end on said radial bearing portion covering substantially the entire diameter thereof and being substantially perpendicular thereto, and an axial bearing portion on said free end of said journal shaft, extending across substantially all of said main diameter of said shaft;

a cutter rotatably mounted on each said journal shaft and having formed therein a radial bearing portion arranged to be located over said journal shaft radial bearing portion, and an axial bearing portion arranged for rotatable bearing action with said shaft axial bearing portion;

first bearing means located between and rotatably joining said shaft radial bearing portion and said cutter radial bearing portion;

second bearing means arranged for rotatable interaction with said cutter axial bearing portion and said shaft axial bearing portion; and,

retention means between said cutter and said journal shaft arranged to retain said cutter on said shaft.

4,293,168

HOUSING FOR Y-BEARING

Hendrikus J. M. Timmer, Tiel, Netherlands, assignor to SKF Industrial Trading & Development, B.V., Nieuwegein, Netherlands


Division of Ser. No. 814,349, Jul. 11, 1977, Pat. No. 4,213,225. This application Mar. 18, 1980, Ser. No. 131,504

Claims priority, application Netherlands, Jul. 9, 1976, 7607602

Int. Cl.³ F16C 23/04, 23/08, 33/66

U.S. Cl. 308—72

3 Claims



1. A housing for a Y-bearing comprising a plate member having a central aperture split and shaped to define a bearing seat, a radially directed flange spaced axially from the bearing seat and means defining an annular groove in approximately the middle of the bearing seat defining a lubrication channel.

4,293,169

WATER BEARING


Harold G. Inhofer, Hopkins, Minn., assignor to Aeration Industries, Inc., Chaska, Minn.

Filed Oct. 22, 1979, Ser. No. 87,004

Int. Cl.³ F16C 17/14, 33/20

U.S. Cl. 308—121

18 Claims



1. A bearing for supporting a rotating shaft in a liquid environment, said bearing comprising a sleeve including a circularly

larly cylindrical inner support surface having a first axial end, a second axial end, and a channel formed in said surface spiraling from said first axial end about the shaft for at least 300° and less than 360°, said channel communicating at said first axial end with the liquid environment in which said bearing is disposed.

9. A bearing for supporting a rotating shaft within an outer housing in a liquid environment, comprising a sheet of material with first and second lateral edges, first and second opposing sides, and one smooth face having formed therein a channel extending diagonally from said first side, proximate said first lateral edge, said sheet being flexible so that it can be mounted within the housing closely encircling the rotating shaft with said smooth face inwardly disposed.

4,293,170

THRUST BEARING ASSEMBLY


Bernard J. Brezovsky, Louisville, Ky., assignor to General Electric Company, Louisville, Ky.

Filed Nov. 21, 1979, Ser. No. 96,713

Int. Cl.³ F16C 17/08

U.S. Cl. 308—161

7 Claims



1. A thrust bearing assembly for use in a motor structure to absorb the axial thrust of the motor drive shaft, the shaft being rotatably supported by at least one nonrotating support bearing, said thrust bearing assembly comprising:

an annular thrust bearing loosely carried on the drive shaft adjacent the support bearing, having a first thrust bearing surface facing the support bearing, a second thrust bearing surface facing opposite from said first thrust bearing surface, and at least one slot formed on the outer periphery of said thrust bearing;

a drive ring carried on the drive shaft, having a thrust transmitting surface facing said second thrust bearing surface of said thrust bearing and having at least one bearing engaging finger projecting from the outer periphery of said drive ring and engaging said one slot on said thrust bearing for rotating said bearing with said drive ring; and

a collet fixedly mounted to the drive shaft, said collet having one end disposed adjacent said drive ring opposite said thrust bearing and having at least one longitudinal slot formed in said one end, and at least one collet engaging finger projecting from the inner periphery of said drive ring and received in said at least one longitudinal slot in said collet for rotating said drive ring with the drive shaft whereby said thrust bearing rotates with the drive shaft and absorbs axial thrust exerted by the drive shaft toward the support bearing.

4,293,171

ANTI-FRICTION BEARING

Ken-Ichi Kakumoto, Kashihara, and Yoshiki Fujita, Andomura, both of Japan, assignors to Koyo Seiko Company Limited, Osaka, Japan


Filed Oct. 19, 1979, Ser. No. 86,676

Claims priority, application Japan, Oct. 25, 1978, 53-132041

Int. Cl.³ F16C 19/02, 33/32

U.S. Cl. 308—188

1 Claim



1. An anti-friction bearing comprising metal components to be subjected to rolling friction or sliding friction, at least one of the rolling elements included in the metal components being coated with at least one intermediate metal layer by ion plating, the intermediate layer being coated by ion plating with an uppermost layer of a soft metal with lubricating property, the solid solubility of the metal of the intermediate layer in each metal adjacent thereto being higher than the solid solubility of the soft metal in the metal material of the rolling element metal, wherein the metal components are made of an iron alloy, and the rolling elements are coated with a lower intermediate layer of nickel and an upper intermediate layer of copper, the uppermost layer being made of gold or silver.

4,293,172

CASE FOR ELECTRICAL MULTIPLE OUTLET


Bhartoor Lingaraju, Allentown, Pa., assignor to Square D Company, Palatine, Ill.

Filed Oct. 23, 1979, Ser. No. 88,195

Int. Cl.³ H01R 4/66, 13/514

U.S. Cl. 339—14 P

8 Claims



1. An improved thin wall correlative case for use with an electrical multiple outlet having: a grounding contact assembly having a ground prong and at least two ground contact elements, two live contact assemblies each having a live contact blade and at least two live contact elements, two insulative partitions for preventing contact between the grounding contact assembly and the two live contact assemblies, and a means for holding said case together, said correlative case comprising:

a bottom section and a top section, each of said top and bottom sections having:

a floor, first and second side walls, and first and second end walls,

a receiving slot in said first end wall, said receiving slot having a rectangular notch in its bottom portion,

a planar projection extending from said second end wall with a semi-circular notch in its far end and two rectangular

gular notches positioned in said second end wall on either side of said planar projection;

first and second substantially rectangular apertures in said floor of said bottom section, said apertures being positioned parallel to each other and parallel to said end walls, and a substantially circular aperture in said floor of said bottom section, said circular aperture being located near said first side wall;

means for positioning the grounding contact assembly, the two live contact assemblies, and the two insulative partitions within said case; and

wherein, when said top and bottom sections of said case are assembled, each of said end walls forms a surface having two rectangular apertures parallel to each other and a D-shaped aperture,

and also wherein, when said multiple outlet is completely assembled, said ground prong and said two live contact blades extend through said circular aperture and said first and second rectangular apertures, respectively, in said floor of said bottom section, and wherein said ground contact elements align with said D-shaped apertures and said live contact elements align with said rectangular apertures in said end walls.

4,293,173

ELECTRICAL OUTLET INSULATION SYSTEM


Raymond A. Tricca, Farmington Hills, Mich., assignor to Armstrong Cork Company, Lancaster, Pa.

Continuation-in-part of Ser. No. 878,412, Feb. 16, 1978, abandoned. This application Jan. 8, 1979, Ser. No. 1,732

Int. Cl.³ H01R 13/44

U.S. Cl. 339—38

3 Claims



1. In an electrical wall outlet of the type wherein there is at least one electrical receptacle having a raised socket with slots therein adapted for receiving the blades of an appliance plug, a faceplate secured to the electrical receptacle and said raised socket extends through said faceplate, and said electrical receptacle and faceplate are mounted on an electrical box which is positioned within a wall, the improvement comprising:

(a) a first large plate of thermal insulation having a compressible and resilient character secured behind said faceplate, between said faceplate and said wall, said large plate of thermal insulation extending to the exterior edges of said faceplate and having at least one aperture therein which has the edges thereof engaging the sides of the raised socket of the electrical receptacle, said outer edges of said faceplate forming a seal around the outer edges of said faceplate between said faceplate and said wall, said edges of said aperture snugly fit around the raised socket whereby said large plate of thermal insulation functions to reduce heat conduction and reduce air infiltration through said outlet around the exterior edges of the faceplate and around the edges of the faceplate through which the socket passes;

(b) at least one non-electrically conductive dummy plug having a backing with blades adapted to fit into said receptacle slots, said dummy plug functions to prevent air infiltration through said slots, said dummy plug having a raised ridge around the edge of its backing to provide a recess in backing on the side of the backing containing the blades;

(c) at least one second small plate of thermal insulation adapted to fit removably over the front face of said receptacle socket, said small plate having slots through which the blades of said dummy plug may extend, said small plate of thermal insulation being sized to fit in and being positioned in said plug recess, said second plate also functions to reduce heat conduction and air infiltration through said outlet.

4,293,174

ELECTRICAL CIRCUIT TESTER

Robert H. Knickerbocker, Cheshire, Conn., assignor to The Siemon Company, Watertown, Conn.

Filed Sep. 18, 1978, Ser. No. 943,231


Int. Cl.³ H01R 21/28

U.S. Cl. 339—64 M

4 Claims

U.S. Cl. 339—75 MP

23 Claims



1. Apparatus for simultaneously establishing electrical contact with a plurality of linearly arranged conductive terminals of uneven height which protrude from a substrate, said apparatus enabling the testing of circuitry connected to said terminals, the apparatus comprising:

elongated bar means, said bar means being comprised of a non-conductive material, said bar means defining a linear array of chambers, said chambers each having an axis and the axes of said chambers being substantially parallel, said bar means further defining extensions of said chambers having a variable cross-sectional area, the first larger cross-sectional area ends of said chamber extensions lying in the plane of a first exterior surface of said bar means whereby terminals protruding from a substrate may be guided by a wall of said chamber extensions toward the chamber axis, first ends of the said chambers and the second ends of said chamber extension being in communication via apertures having a smaller cross-sectional area than the adjacent chamber whereby a shoulder is defined at the said first ends of said chambers;

electrically conductive piston means disposed for axial movement in each of said chambers, said piston means being dimensioned such that movement thereof in a first direction will be limited by said shoulders, said piston means being of shorter axial length than each of said chambers;

electrically conductive piston rod means, said piston rod means comprising conductive extensions of said piston means, said piston rod means extending into said chamber extensions via said apertures for contacting a terminal, said piston rod means being of smaller diameter than said piston means;

electrically conductive spring means positioned in said chambers to resiliently bias said piston means toward the first ends of said chambers, said spring means allowing said piston means to retract when said piston rod means contact a terminal, said spring means defining conductive paths from said piston rod means to the second ends of said chambers;

means cooperating with said bar means to define an elongated cavity, at least a portion of a second exterior surface of said bar means disposed oppositely to first exterior surface being located within said cavity; and means extending into the second ends of said chambers for electrically connecting said spring means to individual

conductors of a multi-conductor cable of a test instrument, said cable being partly positioned in said cavity.

4,293,175

CONNECTOR FOR INTEGRATED CIRCUIT PACKAGES

John M. Cutchaw, Scottsdale, Ariz.

Continuation-in-part of Ser. No. 913,871, Jun. 8, 1978, Pat. No.

4,166,665, which is a continuation-in-part of Ser. No. 862,582,

Dec. 20, 1977, Pat. No. 4,164,003, which is a

continuation-in-part of Ser. No. 754,368, Dec. 27, 1976, Pat. No.


4,063,791. This application Aug. 6, 1979, Ser. No. 64,057

Int. Cl.³ H01R 13/62

4 Claims

U.S. Cl. 339—75 MP

23 Claims



1. A connector for removably mounting an integrated circuit package on a backpanel having at least one hole formed therethrough and for electrically coupling the integrated circuit package to the terminal pads of the backpanel, said connector comprising:

(a) a carrier member of planar configuration for positioning adjacent one of the planar surfaces of the backpanel and movable toward the backpanel, said carrier member having at least one boss extending normally from one planar surface thereof for slidable positioning in the hole formed in the backpanel when said carrier member is positioned adjacent thereto;

(b) at least one integrated circuit package mounted on the other planar surface of said carrier member and having electrical contact means thereon;

(c) electrical interconnecting means on said carrier member in conductive contact with the electrical contact means of said integrated circuit package and for pressurized conductive contact with the terminal pads of the backpanel when said carrier member is positioned adjacent thereto;

(d) stud means extending axially from the boss of said carrier member so as to extend through the hole of the backpanel when said carrier member is positioned adjacent thereto; and

(e) a mounting plate positionable in contiguous contact with the opposite planar surface of the backpanel and laterally movable relative thereto, said mounting plate having at least one aperture means formed therethrough for receiving said stud means when said carrier member and said mounting plate are positioned adjacent the opposite planar surfaces of the backpanel, said stud means interacting with the aperture means of said mounting plate upon lateral movement thereof to pull said carrier member toward the backpanel to provide the pressurized conductive contact between said electrical interconnecting means and the terminal pads of the backpanel.

4,293,176

ELECTRICAL CONNECTION


Martti Lindlöf, Telakkatie 10, 06150 Porvoo 15, Finland

Filed Feb. 28, 1980, Ser. No. 125,659

Int. Cl.³ H01R 4/44

U.S. Cl. 339—98

4 Claims



1. An electrical connector including two jaws, each jaw having a first side facing the other jaw and a second side facing away from the other jaw, the first side of at least one of the jaws having two approximately parallel zones of teeth and the second side of said one jaw having a bead opposite each zone of teeth, and a clamping means for said jaws, said means comprising at least one bolt extending through aligned openings in said jaws and being provided with axially spaced apart shoulders, and a plate spring located between at least one of said shoulders and the second side of said one jaw, said plate spring pressing against said beads.

4,293,177

FLAT CABLE CONNECTOR

Lawrence P. Weisenburger, Kernersville, N.C., assignor to AMP

Incorporated, Harrisburg, Pa.


Division of Ser. No. 853,608, Nov. 21, 1977, Pat. No. 4,160,573.

This application Jan. 8, 1979, Ser. No. 1,551

Int. Cl.³ H01R 13/514

U.S. Cl. 339—99 R

4 Claims



1. A stamped and formed metal electrical contact, comprising:

a pair of plate portions joined entirely along first sides by an elongated common bight and facing each other to define a conductor receiving passageway elongated parallel to said bight, said passageway having an elongated open side defined by spaced apart second sides of said plate portions for receiving a conductor laterally of its axis, said plate portions having first edge margins opposing each

other across one end of said passageway and extending from said bight to said open side of said passageway, said first edge margins projecting, at obverse angles with the remainder of respective said plate portions, diagonally toward each other and defining therebetween a first conductor receiving opening at one end of said passageway and having a width less than the width of an elongated conductor to be received along said passageway and said first conductor receiving opening, said plate portions having second edge margins opposing each other across a second end of said passageway and extending from said bight to said open side of said passageway, said second edge margins projecting, at obverse angles with the remainder of respective said plate portions, diagonally toward each other and defining therebetween a second conductor receiving opening having a width less than the width of a conductor to be received along said passageway and said first and second conductor receiving openings, said first and second edge margins comprising resiliently deflectable, conductor engaging jaws for resiliently engaging a conductor inserted laterally of its axis into and along said passageway and said first and second conductor receiving openings, and means on said contact for connecting the same electrically to an electrical circuit.

4,293,178

COUPLING FOR AN ELECTRIC CABLE


Hop Lee, 2455 - 24th Ave., San Francisco, Calif. 94116

Filed Aug. 3, 1979, Ser. No. 63,393

Int. Cl.³ H01R 13/585

U.S. Cl. 339—103 R

2 Claims



1. In a coupling for an electric cable; the improvement comprising:

(a) a sleeve receiving the cable in extension therethrough;

(b) a liner received within the sleeve and having longitudinally extending wedge-shaped grooves, the portions of the liner lying between adjacent grooves having their inner faces contacting the cable; and

(c) wedges received in the grooves and having teeth on their inner surfaces for gripping the cable, the teeth being inclined for digging into the cable when the cable is pulled away from the coupling, whereby the teeth prevent any longitudinal movement in the sleeve.

4,293,179

CIRCUIT BOARD INTERCONNECTION SYSTEM

David L. Vonder, Addison, Ill., assignor to GTE Automatic Electric Labs Inc., Northlake, Ill.

Filed Oct. 3, 1979, Ser. No. 81,516


Int. Cl.³ H01R 23/70

U.S. Cl. 339—176 MP

8 Claims

1. A circuit board interconnection system for electrically interconnecting a plurality of conductors to one edge of a printed circuit board, said interconnection system comprising: a circuit board connector including an elongated body having a plurality of apertures, each of said apertures includ-

ing an electrical contact retained therein, each of said contacts including a circuit board engaging portion and a terminal engaging portion, said circuit board engaging portions in contact with said circuit board and electrically connecting said contacts to said circuit board, said circuit board connector further including at least one female receptacle portion defined by spaced side walls extending from said body about said terminal engaging portions; and



a cable connector including a body having a male portion, said male portion including a plurality of terminals on one face thereof, each of said terminals electrically interconnected to one of said plurality of conductors, and said male portion inserted into said circuit board connector receptacle portion with said face engaging said circuit board connector terminal engaging portions, electrically interconnecting respective terminals to respective contacts.

4,293,180

RESILIENT BIASING MEANS

Derek Taylor, Whitstable, England, assignor to Bunker Ramo Corporation, Oak Brook, Ill.


Filed May 29, 1979, Ser. No. 43,604

Claims priority, application United Kingdom, May 31, 1978, 25338/78

Int. Cl.³ H01R 13/422

U.S. Cl. 339—217 R

7 Claims



1. An optical fibre or electrical connector, comprising:
a connector body member; means defining a passageway extending through said body member; a termination member, suitable for terminating an electrical conductor or an optical fibre, said termination member being mounted for sliding movement within said passageway; means resiliently biasing said termination member against sliding movement in a first direction in said passageway relative to said connector body member, said biasing means comprising at least one resilient tine acting between said termi-

nation member and said connector body member with a free end of said tine in sliding engagement with a surface on said termination member, said surface being non-parallel with said first direction and causing said tine to be deflected about its root transverse to said first direction upon the occurrence of relative movement between said termination member and said connector body member in said first direction; and means independent of said biasing means for limiting sliding movement of said termination member in said passageway, said movement limiting means limiting sliding movement of said termination member in said passageway between spaced-apart forward and rearward limit positions.

4,293,181

LOW INSERTION FORCE ELECTRICAL SOCKET CONNECTOR

Leonard Lacaze, Jr., San Juan Capistrano, Calif., assignor to International Telephone and Telegraph Corporation, New York, N.Y.


Continuation of Ser. No. 850,629, Nov. 11, 1977, abandoned.

This application Nov. 7, 1979, Ser. No. 91,960

Int. Cl.³ H01R 13/11

U.S. Cl. 339—258 R

6 Claims



1. An electrical connector socket member for receiving a conductive pin of generally circular cross-section inserted longitudinally and extending into said socket member from a forward end thereof;
a rear longitudinal portion of said socket member extending from a rear end of said socket member to an intermediate point thereof;
a forward, hollow longitudinal portion of said socket member having generally conically converging inside and outside diameters and embodying a plurality of integral tines extending from said intermediate point to said forward end, said tines being arranged to elastically deflect radially outwardly when a pin is inserted, for maintaining a radially inward contact pressure against the pin;
said tines having longitudinally extending edges spaced from each other throughout the entire length of said tines, and the distance between said edges over a substantial length of said tines commencing from said intermediate point being substantially constant; and
the region about said intermediate point comprising the tine root region, the material of said tine root region having substantially uniform modulus of elasticity throughout.

4,293,182

ELECTRICAL CONNECTOR BODY AND METHOD OF MAKING SAME

Lawrence Schwartz, Huntington Beach, Calif., assignor to International Telephone and Telegraph Corporation, New York, N.Y.

Filed Jan. 21, 1980, Ser. No. 113,610


Int. Cl.³ H01R 13/504

U.S. Cl. 339—275 R

2 Claims

1. A method of making a unitary electrical connector body having a shell portion surrounding an inner portion of predetermined axial length comprising the steps of:
providing a first insulation material and a second insulation material containing a conductive filler;
providing a mold cavity having a side wall and an end wall;

inserting a core into said cavity spaced from said side wall defining therebetween a shell mold cavity, with said core closing said end wall of said cavity;
thereafter injecting said second material into said shell mold cavity while said core is in said cavity to form the shell portion of said connector body;
partially retracting said core in said cavity said predetermined length to provide an inner mold cavity within said shell portion defined by the inner surface of said shell portion, said cavity end wall and the inner end of said core;



thereafter injecting said first material into said inner mold cavity to form the inner portion of said connector body; said first and second materials being in substantially uncured, liquid form when injected and being curable to a solid form, said first material being injected so as to flow into intimate contact with said second material while said second material is in substantially uncured condition; and curing said materials together in said mold cavity to form said unitary electrical connector body.

4,293,183

METHOD OF HOLOGRAPHIC RECORDING AND RECONSTRUCTION OF SPATIAL WAVES

Okan K. Ersoy, Li, Norway, assignor to Sentralinstitutt for Industriell Forskning, Oslo, Norway


Filed Mar. 9, 1979, Ser. No. 19,188

Claims priority, application Norway, Mar. 9, 1978, 780833

Int. Cl.³ G03H 1/28


U.S. Cl. 350—3.77

3 Claims



1. A method for the production of a hologram of at least one object wavefront and reconstruction of the same by means of a spherical reference/reconstruction wave, said method comprising:

locating a point source of the reference/reconstruction wave a very short distance from the hologram;
slightly adjusting said distance during the reconstruction process, whereby only one reconstructed image selected from a group consisting of a real image, a virtual image, images of different order of the same object, and images of different objects is focused with said source in a given position close to said hologram, while the other images are simultaneously defocused by being located very close to said hologram; and
determining said distance on the basis of the signal to noise ratio desired at the image position, geometrical dimensions which per se are known to cause defocusing, such as hologram size, distance between the hologram and the object, and the area of hologram apertures.



1. An optical attachment adapted for use with an objective camera exchangeable lens which includes a diaphragm interlocking member movable between a first position to maximize an aperture size of a diaphragm mechanism and a second position to minimize the aperture size, said diaphragm interlocking member being biased toward said second position, the optical

4,293,184

SCANNING PROJECTION DEVICE

Kazuo Minoura, Yokohama; Muneharu Sugiura, Tokyo; Setsuo Minami, Kawasaki, and Tadashi Sato, Kokubunji, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan


Filed Dec. 20, 1979, Ser. No. 105,881

Claims priority, application Japan, Dec. 28, 1978, 53-164826; May 14, 1979, 54-58975

Int. Cl.³ G02B 27/17

U.S. Cl. 350—6.3

6 Claims



1. A scanning projection device comprising:
a fixed first plane having a surface to be scanned;
a second plane upon which the image of said first plane is projected;
a deflector disposed between said first plane and said second plane to project the image of said first plane at a predetermined position on said second plane with lapse of time;
a projection optical system disposed between said deflector and said second plane to place said first plane and said second plane in an optically conjugate positional relation; means for swinging and tilting said projection optical system in synchronism with the deflecting action of said deflector, wherein the center of swing and tilting of said projection optical system lies on the deflecting-reflecting surface of said deflector; and
means for varying the distance between said deflector and said projection optical system in synchronism with the deflecting action of said deflector.

4,293,185

OPTICAL CONVERSION ASSEMBLY FOR OBJECTIVE CAMERA LENSES

Yasuo Yamazaki, Kawachinagano, and Takeshi Egawa, Sennan, both of Japan, assignors to Minolta Camera Kabushiki Kaisha, Osaka, Japan

Filed Dec. 26, 1979, Ser. No. 106,444

Claims priority, application Japan, Jan. 12, 1979, 54-3276[U]

Int. Cl.³ G02B 21/00

U.S. Cl. 350—18

8 Claims

attachment capable of providing a view of an object without the necessity of a camera body comprising:

- lens mounting means on which said camera exchangeable lens can be detachably mounted, said lens mounting means having an axis capable of alignment with an optical axis of a camera exchangeable lens when mounted thereon;
- a prism erecting system for rotating an image about vertical and horizontal axes, said prism erecting system provided on said axis and including a light entrance surface perpendicular to said axis and a light emitting surface in parallel with said light entrance surface;
- retaining means for retaining said diaphragm interlocking member in its first position when said camera exchangeable lens is operatively connected, and
- an ocular system provided in the light path of the light emitted from said light emitting surface.


4,293,186

RESTRICTED OFF-AXIS FIELD OPTICAL SYSTEM
Abe Offner, Darien, Conn., assignor to The Perkin-Elmer Corporation, Norwalk, Conn.

Continuation-in-part of Ser. No. 938,569, Aug. 31, 1978, abandoned, which is a continuation-in-part of Ser. No. 767,906, Feb. 11, 1977, abandoned. This application Dec. 21, 1979, Ser. No. 106,415

Int. Cl.³ G02B 17/08

U.S. Cl. 350—27



1. In a restricted off-axis field optical system having a broad spectral range, which includes refracting means, the improvement comprising:

- said optical system being constructed and arranged so that the Petzval sum is substantially zero, and said refracting means including means for balancing the effects of the variation in said Petzval sum due to variation in color by introducing axial chromatic aberration of the opposite sense so that the position of focus at the off-axis field remains substantially constant.

4,293,187

BINOCULAR OPTICAL SYSTEM WITH AUTOMATIC FOCUSING

Isao Ishibai, Machida, and Kunimitsu Kobayashi, Higashimurayama, both of Japan, assignors to Hoya Corporation, Tokyo, Japan

Filed Sep. 10, 1979, Ser. No. 74,354

Claims priority, application Japan, Sep. 11, 1978, 53-111430
Int. Cl.³ G02B 7/11, 23/04

U.S. Cl. 350—36


16 Claims

1. A binocular optical system for viewing an object, said system comprising:

- first and second optical paths for respectively providing first and second light fluxes of an object to be viewed by said binocular optical system;
- means for directing first portions of said first and second light fluxes through non-focused lenses to an image screen

along first and second optical paths to produce first and second images, respectively;

means for aligning said first and second images with one another on said image screen; and



means for focussing third and fourth images to be viewed through said binocular optical system in response to said aligning means, said third and fourth images being formed by second portions of said first and second light fluxes, respectively.

4,293,188

FIBER OPTIC SMALL DISPLACEMENT SENSOR



Donald H. McMahon, Carlisle, Mass., assignor to Sperry Corporation, New York, N.Y.

Filed Mar. 24, 1980, Ser. No. 133,171

Int. Cl.³ G02B 5/172, 5/18

U.S. Cl. 350—96.29

37 Claims



1. Optical transducer means including:

- mounting means having at least first casing means with an inert damping fluid disposed therewithin, said first casing means including first pressure sensing diaphragm means which has a first time constant,

first optical wave guide means disposed upon said mounting means and having a first longitudinal axis and a first end face,

second optical wave guide means disposed upon said mounting means and having a second longitudinal axis and a second end face,

said first and second axes being normally coincident at least in the unexcited state of said transducer means, whereby said first and second end faces then lie in substantially parallel relation and form a gap therebetween,

first and second regular grating array means interposed in substantially parallel spaced relation within said gap sub-

stantially perpendicular to said first and second longitudinal axes, and

suspension means adapted to permit relative displacement between said first and second regular grating array means in response to deflections of said first pressure sensing diaphragm means for modulation of light passing through said first and second regular grating array means.

4,293,189

LIGHT REFLECTING DEVICE


Yoshiharu Morikawa, Toyonaka, Japan, assignor to Solid Corporation, Hyogo, Japan

Filed Mar. 20, 1979, Ser. No. 22,106

Claims priority, application Japan, Mar. 31, 1978, 53-42826[U]; Nov. 10, 1978, 53-154731[U]; Nov. 10, 1978, 53-154732[U]

Int. Cl.³ G02B 5/128

U.S. Cl. 350—105



1. A light reflective device comprising:

- a support member having a surface having a substantially constant roughness defining dents within the range of 10 to 100 microns;
- a continuous light reflecting layer covering the support member surface and having a light reflecting outer surface coextensive with and formed in conformity with the contours of the underlying uneven dented surface of the support member, said light reflecting outer surface thus having a substantially constant roughness defining dents within the range of 10 to 100 microns;

substantially transparent fine spherical glass beads having a high refractive index and spaced from the light reflecting surface by a distance approximately equal to the focal distance of the glass beads, the glass beads being sized to fit in dents of the light reflecting surface; and

a resin layer covering the glass beads and light reflecting layer, said resin layer comprising a first layer portion and a second layer portion each having light transmitting properties and each comprising a synthetic resin, the first layer portion having a thickness approximately equal to the focal distance of the glass beads and covering the light reflecting layer, the glass beads being dispersed over the first layer portion whereby the glass beads are spaced from the light reflecting layer by a distance approximately equal to the focal distance of the glass beads, the second layer portion covering the first layer portion and the glass beads and forming an outer surface having projections and indentations substantially conforming to the contours of the glass beads.

4,293,190

TRANSPARENCY VIEWERS

George R. Clover, London, England, assignor to Oakeridge Management Services B.V., Netherlands

Filed May 30, 1979, Ser. No. 43,620

Claims priority, application United Kingdom, May 31, 1978, 25865/78


Int. Cl.³ G02B 27/02

U.S. Cl. 350—241

8 Claims

1. A transparency viewer comprising a screen for supporting transparencies, and respective individual carrier modules secured over said screen in an array for retaining such transpar-

encies on said screen in said array, each said carrier module constituting a frame to extend over and around the periphery of a transparency, and adjacent carrier modules defining with



13 Claims one another and with the screen guides along which a viewing member can be slid for registration with any selected transparency in said array.

4,293,191

ADJUSTABLE CONVEX REARVIEW MIRROR


Matthew S. Kim, 114 S. 6th St., Bangor, Pa. 18013

Filed May 9, 1980, Ser. No. 148,516

Int. Cl.³ G02B 5/12

U.S. Cl. 350—293

7 Claims



1. An adjustable convex rearview mirror comprising:

- a support housing adapted to be rigidly secured to a surface and having a first hinge member at one end and a cantilever arm at the other end with a pin at the distal end of said arm;
- a convex mirror;
- a mirror housing having a slot for receiving the periphery of said convex mirror;
- said mirror housing having a second hinge member at one end hingedly coupled to said first hinge member to hingedly couple said support housing and said mirror housing for adjusting the angular alignment of said mirror relative to said support housing,
- said mirror housing having a plurality of apertures defined therein at the other end for selectively receiving said pin as said mirror housing is pivoted relative to said support housing about said hinge members,
- said mirror housing telescopically receiving a part of said support housing therein.

4,293,192

SOLAR REFLECTOR WITH FLEXIBLE SHEET TIGHTLY SECURED AROUND FORM SURFACES

Allen I. Bronstein, 541 Bryson Ave., Palo Alto, Calif. 94306

Filed May 27, 1980, Ser. No. 153,016

Int. Cl.³ G02B 7/18, 5/10


U.S. Cl. 350—296

14 Claims

1. A solar reflector comprising:

- a longitudinal slideway;
- a pair of parallel form members carried on said slideway;
- said form members having identical, form surfaces along a portion of the periphery thereof;

a flexible sheet of a material having a reflective surface; means on said form members securing opposite edges of said flexible sheet tightly around said form surfaces; a slide member slidable along said slideway;



one of said form members being supported on said slide member; and positive mechanical means for moving said slide member to tension said flexible sheet.

4,293,193

AMINE-SUBSTITUTED LIQUID CRYSTAL COMPOSITIONS

Mortimer M. Labes, Philadelphia, and John H. MacMillan, Ambler, both of Pa., assignors to Temple University, Philadelphia, Pa.

Filed Aug. 15, 1979, Ser. No. 66,811
Int. Cl.³ C09K 3/34; G02F 1/13


U.S. Cl. 350—350 R

14 Claims

1. A liquid crystalline composition comprising at least two liquid crystalline compounds including one or more liquid crystal compounds from the group consisting of:




Formula 5




Formula 6




Formula 8




Formula 9




Formula 10



Formula 11



Formula 12



Formula 13

where R_1 is an alkyl or alkoxy group having 1-10 carbon atoms, and where R_2 is an alkyl group of 1-10 carbon atoms.

12. A liquid crystalline composition consisting of a miscible mixture of:

(a) A first material consisting of p-(trans-4-n-alkyl(or alkoxy)cyclohexyl) aniline (Formula 16); and

(b) A second liquid crystalline material consisting of p-(trans-4-n-alkyl(or alkoxy)cyclohexyl) benzonitrile, the alkyl or alkoxy groups having 1-10 carbon atoms (Formula 14) or 4-n-alkyl(or alkoxy)-4'-cyanobiphenyls (For-

mula 15), the first material being present in an amount sufficient to broaden the mesogenic range of the second liquid crystalline material.

4,293,194

SOLID ELECTROCHROMIC ELEMENT

Yosuke Takahashi, Sagami, Japan, assignor to Nippon Kogaku K.K., Tokyo, Japan


Filed Dec. 20, 1979, Ser. No. 105,505

Claims priority, application Japan, Dec. 27, 1978, 53-159927

Int. Cl.³ G02F 1/17

U.S. Cl. 350—357

5 Claims



1. A solid electrochromic element which comprises a dielectric material layer, an electron blocking layer, a solid electrochromic substance layer and a second electrode successively laminated on a first electrode and in which a voltage is applied between said first and said second electrode to thereby cause coloration of said solid electrochromic substance layer, the improvement residing in that said electron blocking layer is formed by at least two layers, of which the layer adjacent to the electrode to which a positive voltage is applied is formed by an N-type semiconductor and the layer adjacent to the electrode to which a negative voltage is applied is formed by a P-type semiconductor.

4,293,195

SIMULTANEOUS MULTI-BEAM OPTICAL MODULATION SYSTEM

Masaaki Mori, Kawasaki, Japan, assignor to Ricoh Company, Ltd., Japan


Filed Oct. 17, 1979, Ser. No. 85,488

Claims priority, application Japan, Oct. 20, 1978, 53-129174

Int. Cl.³ G02F 1/11

U.S. Cl. 350—358

4 Claims



1. In a simultaneous multi-beam optical modulation process of the type having the steps of obtaining a plurality of modulated signals with the amplitude of carriers having different frequencies modulated by a plurality of signals, and driving an acoustic optical element by said modulated signals, whereby a light modulation is performed by the acoustic optical element, the improvement comprising the steps of producing a dummy signal by squaring a plurality of said signals, adding and then inverting said squared signals and a setting voltage for setting an overall deflection efficiency of the acoustic optical element,

modulating the amplitude of an assigned carrier by said dummy signal to obtain a modulated output, summing said modulated output and said modulated signals into a summed signal, and applying said summed signal to the acoustic optical element.

4,293,196

OBJECTIVE LENS SYSTEM WITH ASPHERIC FRESNEL ELEMENTS


Robert S. Hilbert, La Canada, Calif., assignor to Fantacia, Del Mar, Calif.

Filed Aug. 13, 1979, Ser. No. 65,994

Int. Cl.³ G02B 3/04, 3/08

U.S. Cl. 350—452

31 Claims



1. A high speed objective lens system capable of forming images that is particularly adaptable for a television projection system comprising from a viewing screen object side to a video image side on an optical axis;

a first thin meniscus lens element convex to the object side having a curvilinear configuration on one side and a Fresnel type surface on the other side;

a second thin meniscus lens element concave to the object side having a curvilinear configuration on one side and a Fresnel type surface on the other side, and

a third weak thin aspherical meniscus lens element convex to the object side.

4,293,197

TELEPHOTO LENS WITH SMALL TELEPHOTO RATIO

Koichi Kobayashi, Tokyo, and Sadao Okudaira, Ranzan, both of Japan, assignors to Asahi Kogaku Kogyo Kabushiki Kaisha, Tokyo, Japan


Filed Feb. 27, 1980, Ser. No. 125,051

Claims priority, application Japan, Mar. 12, 1979, 54-28394

Int. Cl.³ G02B 13/02

U.S. Cl. 350—454

4 Claims



1. A high performance telephoto lens having a small telephoto ratio and being composed of eight lenses grouped into seven lens groups wherein said lenses satisfy the following conditions:

F/4	f = 100	viewing angle $\pm 4.5^\circ$	telephoto ratio 0.60
	r_i	d_i	N_i
1	28.45	3.79	1.49700
2	-373.8	0.03	81.3
3	27.31	3.08	1.49700

-continued

F/4	f = 100	viewing angle $\pm 4.5^\circ$	telephoto ratio 0.60
	r_i	d_i	N_i
4	162.76	1.88	1.80610
5	-335.17	1.64	40.9
6	27.03	0.03	1.49700
7	14.07	3.79	42.2
8	46.93	14.96	35.3
9	-13.97	1.11	1.79952
10	7.12	0	1.59270
11	7.12	1.81	40.8
12	-29.56	11.71	30.1
13	-15.42	0.76	1.88300
14	-178.50	0.64	1.69895
15	59.84	1.87	
16	-16.86		

where r_i is the radius of curvature of the i-th lens surface, d_i is the distance between the i-th lens surface and the next lens in sequence, and v_i is the Abbe number of the i-th lens.

4,293,198

EYE REFRACTOMETER

Yoshimi Kohayakawa, Yokohama; Yasuyuki Ishikawa, Kawaguchi, and Shigeo Maruyama, Kawasaki, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan


Filed Sep. 21, 1978, Ser. No. 944,304

Claims priority, application Japan, Sep. 21, 1977, 52/114348; Dec. 1, 1977, 52/144309

Int. Cl.³ A61B 3/10

U.S. Cl. 351—13

26 Claims



1. An eye refractometer, comprising: a projection system having test pattern generating means for generating test beams and having slits in three meridians arranged in the illumination path such that three test marks are projected into the eye and projection optical means for projecting said test beams to an eye to be inspected and forming an image of the test pattern corresponding to each of the meridians;

an inspecting system having beam detecting means for independently detecting the test beams from the eye to be inspected, and inspecting optical system for transmitting the beams to said beam detecting means;

focus adjusting means coupled to said projection system and said inspecting system for focusing of said two systems; and

beam splitting means for optically coupling said projection optical system and said inspecting optical system.

4,293,199

APPARATUS FOR DETECTING ASTIGMATIC AXES AND MEASURING REFRACTIVE POWERS

Shinzi Wada; Ikuo Kitao; Yoshinori Oana; Yasuo Kato, and Taketoshi Ishihara, all of Tokyo, Japan, assignors to Tokyo Kogaku Kikai Kakushiki Kaisha, Tokyo, Japan

Filed Nov. 13, 1978, Ser. No. 960,056

Claims priority, application Japan, Nov. 14, 1977, 52-136488


Int. Cl.³ A61B 3/10

U.S. Cl. 351—13

4 Claims

1. An eye refractometer apparatus for detecting astigmatic axes and measuring refractive powers of a patient's eye, said apparatus comprising refractive power measuring target means including a first group of slits oriented in a first direction and

a second group of slits coplanar with the first group of slits and oriented in a second direction which is perpendicular to the first direction, each slit being associated with deflecting means having a direction of deflection perpendicular to the lengthwise direction of that slit, the direction of deflection of the deflecting means for at least one of the slits in each group being opposite to that of the deflecting means for the remainder of the slits in the same group, astigmatic axis detecting target means including at least one group of slits oriented in one direction, each of the slits in the astigmatic axis detecting target



means being associated with deflecting means having a direction of deflection parallel with the lengthwise direction of the slit, the direction of deflection of the deflecting means for at least one of the slits in the astigmatic axis detecting target means being opposite to that of the deflecting means for remainder of the slits, means for projecting images of the target means on the retina of the patient's eye along a projecting optical path, means for focusing the projected images, and means for rotating the projected images about the projecting optical path; observing optical means for observing the projected image through the pupil of the patient's eye.

4,293,200

VISUAL FACULTY TESTING APPARATUS

John S. Dobson, 6 Broadacres, Cathorpe Park, Fleet, Hampshire, England, and Peter A. Davison, Sea View, Seapoint Rd., Bray, County Wicklow, Ireland

Filed Mar. 10, 1980, Ser. No. 128,816

Claims priority, application United Kingdom, Mar. 12, 1979, 08598/79

Int. Cl.³ A61B 3/02

U.S. Cl. 351—36

8 Claims



1. Visual faculty testing apparatus comprising: means for presenting a visual target to a subject under test, said target including an array of two sets of areas of respectively different luminance in an alternating sequence in one co-ordinate direction across said array, with the areas of at least one of said sets being of progressively varying luminance towards the luminance of the other of said sets in another co-ordinate direction across said array; and control means adjustable by said subject to alter the rate of said luminance variation.

4,293,201

RUBBER-PADDED FRAMES OF EYE SPECTACLES AND METHOD FOR PREPARING SAME

Takeshi Fukuda, Annaka, and Tomiyoshi Tutida, Takasaki, both of Japan, assignors to Shin-Etsu Chemical Co., Ltd., Tokyo, Japan

Filed Mar. 13, 1980, Ser. No. 129,901

Claims priority, application Japan, Mar. 22, 1979, 54-33616

Int. Cl.³ G02C 5/12, 5/16, 13/00

U.S. Cl. 351—178

3 Claims

1. A method for providing a covering pad member of a silicone rubber on to a portion of a frame of eye spectacles coming into contact with the human body of the wearer which comprises

(a) swelling a shaped member of a silicone rubber with a volatilizable swelling agent and placing said swollen member on the portion of the frame, wherein the swelling agent is an organosilicon compound having a boiling point in the range from 20° to 200° C., and

(b) removing the swelling agent by evaporation from the swollen shaped member of the silicone rubber to dryness whereby the shaped member shrinks to fit the portion of the frame tightly.

4,293,202

LIGHT BEAM RECORDING DEVICE

Masahiro Ohnishi, and Tsutomu Kimura, both of Asaka, Japan, assignors to Fuji Photo Film Co., Ltd., Minami-ashigara, Japan


Filed Oct. 17, 1979, Ser. No. 85,661

Claims priority, application Japan, Nov. 16, 1978, 53-141612

Int. Cl.³ B41B 21/08

U.S. Cl. 354—5

7 Claims



1. A light beam recording system for carrying out a recording operation on a recording material by modulating a recording light beam, in which (i) a reading light beam and said recording light beam are deflected by the same two-dimensional optical deflection system, (ii) a form is subjected to raster scanning with a part of said reading light beam to provide a form signal while a linear encoder is subjected to raster scanning with a part of said reading light beam to provide a video clock signal, and (iii) said recording material is subjected to raster scanning with a video signal which is produced by combining a data signal and said form signal by means of said video clock signal, the improvement comprising means for detecting the drift of vertical deflection means in said two-dimensional optical deflection system from a number of scanning lines by vertically scanning said linear encoder, and means for correcting timing of generation of said data signal in accordance with the amount of drift thus detected.

4,293,203

PHOTOTYPESETTER, METHOD AND APPARATUS


Walter E. Peery, 7-74 Pendleton, Londonderry, N.H. 03053

Filed Jan. 23, 1980, Ser. No. 114,710

Int. Cl.³ B41B 17/12

U.S. Cl. 354—17

9 Claims



1. A method of phototypesetting comprising:

- illuminating an aperture to provide an illuminating beam therefrom;
- directing said illuminating beam by one or more rotatable reflectors to illuminate a succession of characters on a character font;
- optically focusing an image of said aperture on each of said characters;
- directing light from each illuminated character back to said one or more reflectors so as to generate an aligned image beam on a common axis for each character of said succession;
- disposing a photosensitive medium at an exposure station; and
- optically directing and focusing said aligned image beam so as to focus images of said succession of characters at selected locations on said medium.

4,293,204

PHOTOGRAPHIC CAMERA HAVING AN AUTOMATIC EXPOSURE CONTROL

Karl Wagner, Munich; Dieter Engelsmann, Unterhaching; Hubert Hackenberg, Holzkirchen, and Peter Stiefel, Munich, all of Fed. Rep. of Germany, assignors to AGFA-Gevaert Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany


Filed Jan. 30, 1980, Ser. No. 116,803

Claims priority, application Fed. Rep. of Germany, Feb. 12, 1979, 2905248

Int. Cl.³ G03B 7/00, 15/02

U.S. Cl. 354—21

16 Claims



1. A photographic camera, comprising a manually operated control member for setting at least one exposure parameter; an axially movable objective for setting the exposure distance; a film cartridge provided with coded marks indicative of the

sensitivity of the contained film; a scanner movable against said marks and being coupled to said control member to displace the same according to said marks; a stationary cam surface engaging said movable objective; transmission means coupled between said control member and said objective to move the latter according to a distance set by said control member and according to a predetermined curve of said stationary cam, said curve including a portion defining a distance range for a flash exposure; and a scale provided on said control member to display at least the exposure range and the applicable flash distance limits for the employed film sensitivity.

4,293,205

CAMERA FOCUS DETECTING DEVICE

Seiji Tokutomi, Tokyo; Masao Jyojiki, Tsurugashima, and Kazuo Nakamura, Tokyo, all of Japan, assignors to Asahi Kogaku Kogyo Kabushiki Kaisha, Tokyo, Japan


Filed Jun. 4, 1979, Ser. No. 45,498

Claims priority, application Japan, Jun. 14, 1978, 53-71958

Int. Cl.³ G03B 13/18; G01J 1/36

U.S. Cl. 354—23 D

14 Claims



1. A focus detecting device for a lens system comprising: means for dividing the image of an object into two optically equal images of the object; means for shifting at least one of the two images of that object with respect to the other image; first and second photoelectric conversion element groups adapted to convert the variations in relative position of the two images of the object into electrical signals, each of said first and second groups including n photoelectric conversion elements, each photoelectric conversion element in said first group providing a current output i_m and each photoelectric conversion element in said second group providing a current output i'_m , where $m=1, 2, 3, \dots, n$ is the number in order of each photoelectric conversion element in its respective group and the outputs i_1 through i_n and i'_1 through i'_n are proportional to the quantities of light applied to respective photoelectric conversion elements; an optical system for projecting the images of the object onto the two photoelectric conversion element groups; and a calculation circuit means for receiving outputs from said conversion elements and for calculating a first voltage from the differential comparison of the outputs of conversion elements in opposite groups which are laterally offset in a first direction with respect to one another, a second voltage from the differential comparison of the outputs of conversion elements in opposite groups which are laterally offset in a second direction, opposite to said first direction, with respect to one another, and for generating a third voltage corresponding to the difference between said first and second voltages, which third voltage differs in polarity on opposite sides of the proper focalization point of said lens system.

4,293,206
ELECTRICALLY OPERATED AUTOMATIC
FOCALIZING CAMERA

Seiji Tokutomi, Tokyo; Masao Jyojiki, Tsurugashima; Harumi Aoki, Kiyose; Kazuo Nakamura, Shiki, and Koichiro Watanabe, Funabashi, all of Japan, assignors to Asahi Kogaku Kogyo Kabushiki Kaisha, Tokyo, Japan


Filed Jan. 22, 1980, Ser. No. 114,174

Claims priority, application Japan, Feb. 16, 1979, 54/18641[U]

Int. Cl.³ G03B 3/10

U.S. Cl. 354—25

3 Claims



1. An electrically operated automatic focalizing camera comprising: an electrical focus detecting device for providing a focus detection signal; means for positioning a photographing lens in response to a signal at an input thereto; means for converting a position of said photographing lens into a voltage; means for setting a range of voltage corresponding to a range of amount of extension; means for determining whether or not a voltage corresponding to an amount of extension is in said range of voltage; and means for receiving a decision output from said determining means for controlling transmission of said focus detection signal, said transmission controlling means being operatively coupled between said focus detecting device and said input of said positioning means.

4,293,207
CAMERA FOCUS DETECTING DEVICE

Harumi Aoki, Kiyose; Masahiro Kawasaki, and Yoshio Sawada, both of Tokyo, all of Japan, assignors to Asahi Kogaku Kogyo Kabushiki Kaisha, Tokyo, Japan


Filed Jan. 31, 1980, Ser. No. 117,336

Claims priority, application Japan, Feb. 9, 1979, 54/14042

Int. Cl.³ G03B 3/00

U.S. Cl. 354—25

3 Claims



1. A focus detecting device for a camera comprising: a self-scanning type photoelectric element having a plurality of microphotoelectric elements and a scanning circuit for producing a contrast signal of the image of an object to be photographed to automatically detect a point of proper focus; an average illumination detecting photoelectric element disposed at least near a position which is optically equivalent to the position of said microphotoelectric elements; a low-pass filter coupled to an output of said average illumination detecting element for removing a vibration component in an output signal thereof; and a clock pulse generator for generating a clock pulse signal of which the frequency is varied according to an output of said low-pass filter, said clock pulse generator being coupled to drive self-scanning type photoelectric element so that as the brightness of said object increases, the frequency of said clock pulse signal increases thereby to produce a contrast signal free from variations in brightness of said

object and to remove variation components of said contrast signal due to movement of said object.

4,293,208
PREBIAS FOR DIGITAL LIGHT INTEGRATOR


Judy Bagdis, Bradford, Mass., assignor to Polaroid Corporation, Cambridge, Mass.

Filed Oct. 20, 1980, Ser. No. 198,781

Int. Cl.³ G03B 7/083, 7/087

U.S. Cl. 354—29

11 Claims



1. A photographic camera apparatus of the type adapted to be energized at least in part by a source of electrical energy and including means for defining a film plane comprises:

- a source of artificial illumination;
- a photoresponsive element stationed to receive light from the scene to be photographed and said source of artificial illumination and to provide an output signal having an electrical characteristic which varies as a function of the intensity of light incident thereon;
- means for integrating the output signal from the photoresponsive element;
- shutter means for controlling the admission of scene light to the film plane to define an exposure interval and for controlling the admission of artificial light to said photoresponsive element to coincide with the commencement of said exposure interval;
- circuit means for controlling the energization of said source of artificial illumination so as to illuminate said photoresponsive element prior to the commencement of said exposure interval to assure a minimum integrated output signal level from said integration means at the commencement of said exposure interval and for subsequently powering said source of artificial illumination at the commencement of said exposure interval; and
- means responsive to a select change in said integrating means output signal from said minimum integrated output signal level at the commencement of said exposure interval for providing an initiation control signal in substantial correspondence with the commencement of the exposure interval so as to control an exposure influencing operation.

4,293,209
MIRROR OPERATING MECHANISM IN SINGLE LENS
REFLEX CAMERA

Hiroshi Kurei, Kawagoe, Japan, assignor to Asahi Kogaku Kogyo Kabushiki Kaisha, Tokyo, Japan

Filed Feb. 26, 1979, Ser. No. 14,791

Claims priority, application Japan, Feb. 28, 1978, 53-22316


Int. Cl.³ G03B 19/12

U.S. Cl. 354—153

8 Claims

1. In a mirror operating mechanism in a single lens reflex camera having a first reflecting mirror swinging from a view

finder observation position to a photographing retraction position, said first reflecting mirror having a light transmitting portion, and a second reflecting mirror for transmitting light passing through said first reflecting mirror at the view finder observation position to a light measuring element, said second reflecting mirror being swingingly mounted on said first reflecting mirror, the improvement comprising: a frame for supporting said first mirror, a rotary shaft around which said second reflecting mirror swings, both ends of said rotary shaft being rotatably mounted on both sides of said frame supporting



said first reflecting mirror, said second reflecting mirror having an operating arm with an end portion, cam means for pre-setting the position of said second mirror relative to said first mirror in both said observation and retracted positions, said cam means being secured to a stationary member but adjustable relative thereto to individually adjust either of two pre-set points of contact between said cam means and said end portion in said observation and retracted positions, respectively, without changing the other point of contact, and a spring member for urging said end portion of said operating arm into contact with said cam means at said points.

4,293,210
RELEASE BUTTON DEVICE FOR CAMERA

Toru Kando, Tokyo, and Tahei Morisawa, Matsudo, both of Japan, assignors to Asahi Kogaku Kogyo Kabushiki Kaisha, Tokyo, Japan


Filed Sep. 25, 1980, Ser. No. 190,768

Claims priority, application Japan, Oct. 23, 1979, 54/136537

Int. Cl.³ G03B 17/38

U.S. Cl. 354—269

3 Claims



1. A release button device for an electromagnetic release type camera in which the operation of a shutter member is energized electrically comprising:

- an electrically conductive release button adapted for receiving a cable release unit, said release button being mounted on said camera with the rotation of said release button being limited;
- an electrically insulative central core frame coupled to said release button, said central core frame having an aperture formed therein aligned with an aperture in said release button, the diameter of said aperture in said core frame being sufficiently large to pass the plunger of a cable release unit connected to said release button;

an electrically conductive central core slidably disposed in said aperture in said core frame;

a protrusion positioned below a lower end of said central core, said protrusion serving as a first contact of a release switch for switchably connecting a power source to operate said shutter member, said protrusion being electrically connected to said release button; and

a contact piece disposed between said central core and said protrusion, electrically insulated from said protrusion in a normal position of said release button, and movable into contact with said protrusion upon depression of said release button or plunger, said contact piece forming a second contact of said release switch.

4,293,211
AUTOMATIC REPLENISHMENT CONTROL SYSTEM


Kenneth M. Kaufmann, Minneapolis, Minn., assignor to Pako Corporation, Minneapolis, Minn.

Filed Jul. 14, 1980, Ser. No. 168,019

Int. Cl.³ G03D 13/00, 3/06

U.S. Cl. 354—298

26 Claims



1. In a processor of photosensitive material having replenishment means for replenishment of processor chemistry, an automatic replenishment control system comprising:

- means for storing a replenishment rate;
- means for controlling replenishment as a function of the replenishment rate;
- means for storing values indicative of desired parameter values of control strips of photosensitive material processed in the processor;
- means for providing signals indicative of measured parameter values of the control strips processed in the processor;
- means for automatically making a short term replenishment correction if the measured parameter value deviates from the desired parameter value; and
- means for automatically adjusting the stored replenishment rate if a deviation between the measured and desired parameter values persists in a subsequent control strip processed by the processor despite a previous short term replenishment correction.

4,293,212
THERMAL PROCESSOR IN AN APPARATUS FOR
DEVELOPING PHOTOGRAPHIC FILM

Bohdan W. Stryj, Cinnaminson; Richard D. Scott, Cherry Hill, and Charles R. Horton, Maple Shade, all of N.J., assignors to RCA Corporation, New York, N.Y.

Filed Apr. 25, 1977, Ser. No. 790,196


Int. Cl.² G03D 7/00

U.S. Cl. 354—299

5 Claims

1. A thermal processor in an apparatus for heat development of a fixed photographic image on a strip of photographic film, said film including a latent image formed on an emulsion layer coated on a film base, comprising:

means for heating a supply of gas to a substantially uniform predetermined temperature;
 a housing arranged to receive said gas;
 means for supplying said gas to said housing;
 gas distribution means responsive to said supply means for uniformly distributing said gas to said film at a predetermined pressure, said gas distribution means being supported by said housing and disposed adjacent to and on opposite surfaces of said film at a spacing such that said pressure of gas supplied to the respective surfaces of said film is sufficient to establish a gas bearing on said respec-



tive film surfaces to thereby support said film while being passed through said processor, and to transfer heat from said heating means to said respective surfaces of said film; and
 a thermofoil heater disposed around said housing to provide a heat source around the housing surface in contact with said gas tending to minimize heat loss from said heated gas;
 whereby said heated gas heats both surfaces of said film substantially uniformly for development of said fixed photographic image.

4,293,213

BIAS VOLTAGE ADJUSTING MEANS FOR ELECTROPHOTOGRAPHIC APPARATUS

Masaji Nishikawa, and Munee Kasuga, both of Hachioji, Japan, assignors to Olympus Optical Company Limited, Tokyo, Japan


Continuation of Ser. No. 826,673, Aug. 22, 1977, Pat. No. 4,148,577. This application Jan. 8, 1979, Ser. No. 1,927

Claims priority, application Japan, Sep. 2, 1976, 51-104223

Int. Cl.³ G03G 15/00

U.S. Cl. 355—14 R

2 Claims



1. In an electrographic apparatus comprising a photosensitive screen composed of an insulating layer, two electrically conductive layers coated on opposite sides of said insulating layer and a photosensitive layer coated on one of said electrically conductive layers, a corona discharge device arranged at one side of said photosensitive screen and emitting a flow of corona ions, and a dielectric coated record sheet arranged at

the other side of said photosensitive screen, whereby an electrostatic latent image produced on said photosensitive layer of said photosensitive screen causes said flow of corona ions directed from said corona discharge device through said photosensitive screen toward said dielectric coated record sheet to modulate so as to produce, on said dielectric coated record sheet, an electrostatic charge image corresponding to said electrostatic latent image on said photosensitive layer of said photosensitive screen, the improvement comprising means for adjusting a bias voltage applied between said two electrically conductive layers of said photosensitive screen, said means for adjusting said bias voltage being automatically operable in response to an electric potential built up on said electrostatic latent image produced on said photosensitive layer.

4,293,214

SHEET SET SEPARATION DEVICE


Clifford L. George, Macedon, and Jon S. Olson, Palmyra, both of N.Y., assignors to Xerox Corporation, Stamford, Conn.

Filed Oct. 30, 1979, Ser. No. 89,338

Int. Cl.³ G03G 15/00; B65H 39/06

U.S. Cl. 355—14 R

2 Claims



2. In an electrostatographic reproduction system having a document handling apparatus for advancing individual document sheets to an exposure station, an electrostatographic processor for processing copy sheets, and an arrangement for producing identifiable collated sets of copy sheets, the improvement comprising,

a compiler station for collecting copy sheets,
 transport means for conveying processed copy sheets from the processor along a path of movement to said compiler station,
 gate means adjacent said compiler station and movable from an inoperative position out of the path of movement of copy sheets to a position into said path to arrest movement of copy sheets being conveyed to said station,
 means for actuating said gate means to said inoperative position and for effecting the ejection of a set of collected copy sheets,
 a catch tray positioned into said path of movement for receiving sets of copy sheets ejected from the compiler station,
 programming means for selectively enabling simplex or duplex modes of operation, and
 drive means associated with said catch tray and said programming means for moving the same laterally in either direction alternately when the system is in the simplex mode of operation and to inhibit movement of tray when in the duplex mode of operation.

4,293,215

PRINT INSPECTION AND PACKAGING METHOD AND APPARATUS


Robert S. Rosborough, Jr., Rochester, N.Y., and Luther M. Wright, deceased, late of Brockport, N.Y. (by Edna B. Lang, nee Wright executrix), assignors to Eastman Kodak Company, Rochester, N.Y.

Filed Aug. 15, 1979, Ser. No. 66,760

Int. Cl.³ G03B 27/52

U.S. Cl. 355—40

16 Claims



1. Apparatus for processing photographic prints through an inspection operation where particular prints made from corresponding photographic negatives are selected for remaking using recorded negative-related information, said apparatus comprising:

means for storing the negative-related information corresponding to the prints being inspected;
 an inspection work surface having a plurality of identifiable positions for the prints;
 means for positioning a plurality of the prints in at least some of the identifiable positions;
 means for correlating the negative-related information with the identifiable positions in which prints corresponding to the negatives are positioned;
 means for generating a selection signal corresponding to the position on said surface of a print selected for remaking; and
 means responsive to said selection signal for retrieving negative-related information corresponding to the selected print for use in remaking of the print.

4,293,216

METHOD OF PRODUCING COLOR SEPARATION NEGATIVES WITH REDUCED CONTRAST

Joseph E. Moore, Rte. 4, Box 159, Northport, Ala. 35476

Filed Dec. 6, 1979, Ser. No. 101,017

Int. Cl.³ G03B 27/32


U.S. Cl. 355—77

4 Claims

1. The method of preparing color separation negatives for color printing reproduction of a positive color transparency, said method including:

A. Inspection of the positive color transparency to determine the greater density detail areas to be reproduced;
 B. Enlarger exposing a trial color separation negative film sheet through said positive color transparency and a half-tone screen (independent of a negative mask) with that exposure time which will properly expose those areas of the film sheet corresponding to said greater density detail areas and, due to the proper exposure of the greater density detail areas, at the same time overexpose those areas of said film sheet corresponding to the lesser density detail areas thereof;
 C. Developing said trial film sheet with such less than norm developing time and greater than norm developer strength (together compensating for the less developing time) to achieve the desired "dot size" in said areas corre-

sponding to said greater density detail areas as well as in the areas of the resultant trial color separation negative



corresponding to the lesser dense detail areas of said color transparency.

4,293,217

CONTINUOUS-FLOW CONDENSATION NUCLEI COUNTER AND PROCESS


Alvin N. Bird, Jr., Norman L. Francis, and Albert L. Thomas, Jr., all of Birmingham, Ala., assignors to The United States of America as represented by the Secretary of the Army, Washington, D.C.

Filed Feb. 6, 1980, Ser. No. 118,946

Int. Cl.³ G01N 1/00

U.S. Cl. 356—37

6 Claims



1. A portable continuous-flow device for detecting and counting nuclei in sampled air, said device comprising:

an upstanding tubular humidifier housing;
 an upstanding and axially elongated humidifier tube centrally disposed within said humidifier housing and cooperating with said humidifier housing to define an annular passageway therebetween in which to accommodate an upward flow of a portion of a continuous flow of sampled air; said humidifier tube defining a longitudinal interior passageway therewithin in which to accommodate an upward flow of another portion of the said continuous flow of sampled air;
 means for continuously delivering a forced upward flow of nuclei containing sampled air to a lower region of said annular passageway and a lower region of the interior passageway in said humidifier tube;
 a wetted wick disposed within the interior passageway in said humidifier tube for saturating the portion of the continuous upward flow of sampled air therewithin;
 means for heating the continuous upward flow of saturated sampled air within said humidifier tube to a temperature higher than the portion of sampled air with said annular

passageway between said humidifier tube and humidifier housing;

a plume chamber communicating with the upper regions of the interior passageway in said humidifier tube and the upper regions of annular passageway between said humidifier tube and said humidifier housing, said plume chamber thereby receiving therein both of the aforementioned upwardly flowing portions of sampled air and whereby the heated and saturated portion of the sampled air flowing upwardly from within said humidifier tube is caused to mix with and condense upon airborne nuclei by the portion of sampled air flowing upwardly from within said annular passageway;

means for illuminating said plume chamber to illuminate the condensation nuclei;

means for detecting and counting the illuminated condensation nuclei;

means for continuously exhausting the condensation nuclei from said plume chamber; and

a manually transportable enclosure means for mounting each of the foregoing in operative assembled relationship within said enclosure means.

4,293,218

REFERENCE LIGHT BEAM PROJECTOR


Edward G. Nielsen; Kenneth C. Mosley, and Louis M. Chatterton, all of Grand Rapids, Mich., assignors to Laser Alignment, Inc., Grand Rapids, Mich.

Filed Dec. 28, 1978, Ser. No. 974,019

Int. Cl.³ G01B 11/26; G02B 27/17

U.S. Cl. 356—138

16 Claims



1. A reference light beam projector for producing a modulated plane of light comprising: a narrow light beam source for projecting a light beam along a predetermined path; an expanding lens located forwardly of said projector on said path, and a collimating lens located forwardly of said expanding lens from said projector on said path, the improvement comprising a variable light refracting means located between said lenses in the path of said beam for variably bending said beam along a plane; and means for actuating said light refracting means to variably bend said beam to produce a modulated plane of light.

4,293,219

METHOD AND APPARATUS FOR INSPECTING TRANSPARENT OBJECTS

Marcel Ducloux, Le Pecq, France, assignor to Societe Generale Pour L'Emballage, Paris, France

Filed Aug. 18, 1978, Ser. No. 934,827

Claims priority, application France, Aug. 24, 1977, 77 25859

Int. Cl.³ G01N 21/90

U.S. Cl. 356—240

33 Claims


1. Apparatus for continuously inspecting transparent objects having at least a localized region with symmetry of revolution about an axis comprising:

a plurality of fixed light beam emitters for directing light

beams at the position where a transparent object is located for inspection;

a plurality of light-detecting means generally oriented with respect to said light beam emitters so that at least some light-detecting means receive light from said light beam emitters when a transparent object is located at said inspection position;

electronic means for sequentially activating said light beam emitters and for interrogating said light-detecting means



in a circular scanning examination cycle, said electronic means further comprising first and second looped counters, said first counter transmitting cycles of excitation orders to said light beam emitters and said second counter transmitting cycles of interrogation orders to said light-detecting means, said counters being interconnected so that one of said counters transmits incrementing instructions to the other of said counters after transmitting a cycle of orders.

4,293,220

APPLICATION OF INDUCTIVELY COUPLED PLASMA EMISSION SPECTROMETRY TO THE ELEMENTAL ANALYSIS OF ORGANIC COMPOUNDS AND TO THE DETERMINATION OF THE EMPIRICAL FORMULAS FOR THESE AND OTHER COMPOUNDS


Medona B. Denton, Tucson, Ariz., and David L. Windsor, Cincinnati, Ohio, assignors to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Jul. 2, 1979, Ser. No. 53,664

Int. Cl.³ G01N 21/73

U.S. Cl. 356—316

3 Claims



1. A method employing a gas chromatograph and an inductively-coupled plasma torch for evaluating the atomic elements of molecular compounds comprising;

processing said compound through said chromatograph for obtaining an effluent gas flow continuing for the period of time required for the vaporization of the compound,

energizing said torch sufficiently to produce a thermal re-

gion capable of degrading the compound into its atomic elements,

exposing said continuous effluent flow to said region to produce said atomization and to excite each of said atomic elements into radiation emission at its characteristic wavelength, said emissions each having an emission intensity responsive to the unit weight of the element independently of the physical structure of the compound,

continuously with said exposure scanning a selected plurality of said wavelengths for producing outputs proportional to the emission intensities, said selection being with regard both to their intensity and their relative freedom from spectral interference, and

utilizing the retention time in said chromatograph to determine the molecular formula of said compound according to the relationship $n = k \log Tr$, where n is the approximate carbon number, k is an experimental constant and Tr is the elution period of the compound from the chromatograph.

4,293,221

MULTIDIMENSIONAL SLIT-SCAN FLOW SYSTEM


David B. Kay, Rochester; Leon L. Wheelless, Jr., Webster, and James L. Cambier, Rome, all of N.Y., assignors to Research Corporation, New York, N.Y.

Filed Apr. 17, 1979, Ser. No. 30,880

Int. Cl.³ G01J 21/64

U.S. Cl. 356—318

63 Claims



1. A flow cytometer for obtaining multidimensional slit-scan type fluorescence contours of a biological cell, comprising:

means for conveying the cell along a flow axis;

means for providing a substantially planar beam of electromagnetic radiation for exciting secondary fluorescence in the cell, the flow axis intersecting but not lying within the plane of the beam such that the cell passes through the beam and a plurality of first substantially planar parallel cross-sections of the cell are successively excited to secondary fluorescence;

means for measuring secondary fluorescence from the first cellular cross-sections as the cell passes through the beam so as to generate a slit-scan type contour along a first axis perpendicular to the first cellular cross-sections; and

means for measuring secondary fluorescence from each of a first plurality of substantially linear portions of the cell as the cell passes through the beam, the linear portions of the first plurality being defined by the intersections of each of a plurality of second substantially planar parallel cross-sections of the cell with each of the first cross-sections, the cell second cross-sections being parallel to the flow axis, and for generating first integrations for each individual second cross-section of the measured secondary fluorescence of all the linear portions therein, such that the resultant first integrations collectively represent a slit-scan type contour along a second axis perpendicular to the second cross-sections.

4,293,222

CONTROL APPARATUS FOR SPECTROPHOTOMETER

Stephen Caruso, Columbia, and Kamalak D. Dighe, Laurel, both of Md., assignors to Baxter Travenol Laboratories, Inc., Deerfield, Ill.


Continuation-in-part of Ser. No. 881,826, Feb. 27, 1978,

abandoned. This application Feb. 9, 1979, Ser. No. 10,734

Int. Cl.³ G01J 3/42; G06F 15/20

U.S. Cl. 356—319

3 Claims



1. A control apparatus for use with a dual beam spectrophotometer of the type in which light from a light source is split into two beams which are directed along respective first and second optical paths to a photosensitive device, the first optical path passing through a reference station and the second optical path passing through a sample station, and of the type which includes means for changing the wavelength of the light from a light source over a predetermined time period through a span of at least 75 nanometers and up to 600 nanometers or some segment thereof, starting at a wavelength of 200 nanometers or greater and proceeding up to a wavelength of 825 nanometers or less, means associated with the wavelength changing means for producing an output signal indicative of a particular wavelength of the light beams at any point in time and signal generating means coupled to the photosensitive device for subtracting the log of each signal generated by the light received by the photosensitive device from the second optical path from the log of each signal generated by the light received by the photosensitive device from the first optical path and then producing a log difference signal indicative of absorbance, said control apparatus comprising electric circuit means including control, processing and memory circuits adapted to be coupled to the spectrophotometer for receiving and storing signals therefrom, said electric circuit means including first memory circuit means and second memory circuit means for receiving and storing the varying log difference signals, control and processing means for manipulating the data comprised of signal values stored in said memory circuit means, said manipulations including transferring data in one memory circuit means to the other memory circuit means, adding data from one to the data of the other, subtracting data in one from data in the other and taking the derivative of data stored in one of the memory circuit means, wavelength digital display means, absorbance digital display means, and said control and processing circuit means being coupled to a recorder in the spectrophotometer and being operable to cause movement of a pen of the recorder to plot a spectrum of wavelength v. absorbance on the recorder from a spectrum of varying log difference signals which are related to absorbance and which are stored in said one of said memory circuit means, and said control and processing means including control means coupled to said one of said memory circuit means for causing a cursor operation on the curve plotted on the recorder, said cursor being seen as a holding of the pen at a particular point on the curve and said control and processing means being operable to cause a display on said respective wavelength and absorbance digital display means of the wavelength and absorbance at the particular position of the pen on the curve plotted on the recorder and

said control means including means for moving said pen in increments along the curve plotted on the recorder.


4,293,223

METHOD AND APPARATUS FOR CONTROLLING RESONANT FREQUENCY OF AN OPTICAL INTERFEROMETER CAVITY

Norman T. Seaton, 5431 College Ave., Oakland, Calif. 94618
Filed Sep. 27, 1979, Ser. No. 79,324
Int. Cl.³ H01S 3/086

U.S. Cl. 356—352

11 Claims



1. A frequency control apparatus for an optical interferometer cavity having a part having a dimension defining resonant frequency comprising:

- a plurality of substantially straight electrical conductors adapted for connection to a source of electrical potential and mounted on and mechanically secured to said part and providing a conduction path substantially parallel to said dimension and having a coefficient of thermal expansion and functioning to transmit mechanical force to said part as a function of electro-thermally induced change in length of said conductors for changing said resonant frequency.


4,293,224

OPTICAL SYSTEM AND TECHNIQUE FOR UNAMBIGUOUS FILM THICKNESS MONITORING

Charles A. Gaston, Poughkeepsie; Joseph P. Kirk, Chelsea, and Chester A. Wasik, Poughkeepsie, all of N.Y., assignors to International Business Machines Corporation, Armonk, N.Y.
Filed Dec. 4, 1978, Ser. No. 966,415
Int. Cl.³ G01B 9/02

U.S. Cl. 356—357

10 Claims



1. An optical instrument for monitoring the increasing or decreasing thickness of a transparent film having an initial thickness within a predetermined range, and especially for eliminating ambiguity in the knowledge of the absolute thickness of said transparent film, comprising
- means for illuminating said film with at least two substantially different wavelengths of light,
 - photodetecting means for receiving said light and providing at least two output signals responsive to the changing intensity of optical interference in said film as said film increases or decreases in thickness, and
 - means for comparing the phase relationship of said output signals by recognition of coincident extrema of said output signals whereby an unambiguous indication of the abso-

lute thickness of said film having an initial thickness within said predetermined range is provided.

4,293,225

UNDERWATER FLUOROMETER MEASURING SYSTEM


John E. G. Wheaton, London; David Griffiths, Surrey, and Richard C. M. Learner, London, all of England, assignors to Chelsea Instruments Limited, London, England
Filed Jun. 29, 1979, Ser. No. 53,340

Claims priority, application United Kingdom, Jun. 30, 1978, 28464/78

Int. Cl.³ G01N 21/64

U.S. Cl. 356—417

9 Claims



1. A submersible fluorometer instrument comprising a fluid-tight pressure case containing a light transmitter adjacent to a first window in an exterior wall of the case and a light receiver adjacent to a second window in an exterior wall of the case, said windows arranged substantially orthogonally and having axes which intersect externally of said case and in a common plane, said light transmitter comprising a controllable pulsed light source for emitting flashes of fluorescent stimulating light, a first optical system which beams the flashes of light from said source through said first window into the fluid in which the instrument is immersed and a first light detecting means arranged to detect the intensity of light emitted by the said pulsed light source, and said light receiver comprising a second optical system arranged coaxially with said second window to receive light emissions from a specific volume of the fluid illuminated by said flash of light and to transmit said light emissions to a second detector, wherein said first optical system incorporates a filter which removes from the light transmitted through the first said system any light having a wavelength equal to or longer than that produced by the fluorescence and the second optical system incorporates a filter which removes from the light transmitted through the second said system any light having a wavelength shorter than that produced by the fluorescence, said fluid-tight pressure case further containing a synchronising control means for enabling the flashes of light, a first synchronised sampling means coupled to the said control means so as to be enabled thereby in synchronism with the said flashes of light, said first synchronised sampling means being connected to sample the output of the first detecting means, a second synchronised sampling means coupled to the control means so as to be enabled thereby in synchronism with the said flashes of light and the said first synchronised sampling means, said second synchronised sampling means being connected to sample the output of the second detecting means, ratioing means coupled to said first and second sampling means for determining a ratio of the synchronised samples of the said first and second sampling means, said ratioing means providing an output signal proportional to the value of the said ratio, and output means for providing a signal representative of the fluorescence detected by the second detector relative to the energy in the respective flashes of light transmitted into the said fluid.

4,293,226

PHOTOGRAPHIC FILM BLACKENING AREA MEASURING DEVICE

Minoru Kinoshita, Kyoto; Kiyoshi Sugou, Yokohama, and Yukio Onoda, Kusatsu, all of Japan, assignors to Dainippon Screen Seizo Kabushiki Kaisha, Kyoto, Japan

Filed May 19, 1980, Ser. No. 151,400

Claims priority, application Japan, Jun. 21, 1979, 54-85762[U]

Int. Cl.³ G01N 21/59; G02B 5/14

U.S. Cl. 356—443

5 Claims



1. In an automatic photographic film development device in which a developed photographic film is moved along a transport path,

a photographic film blackening area measuring device, comprising:

- (a) two rod shaped light conducting members formed of transparent material, the longitudinal surface of each of which is smooth except for a roughened portion elongated parallel to the axis of said rod shaped light conducting member, said rod shaped light conducting members being arranged parallel to one another on opposite sides of the developed photographic film transport path;
- (b) a single light emitting device, disposed proximate to a first end of a first one of said rod shaped light conducting members, so as to illuminate said first rod shaped light conducting member, substantially no other light source being disposed so as to illuminate said first rod shaped light conducting member; and
- (c) a single light sensitive device, disposed proximate to a first end of the other rod shaped light conducting member, said first end of said other light conducting member being the most distant end thereof from said first end of said first rod shaped light conducting member, and said light sensitive element being arranged so as to be able to receive light from said first end of said other rod shaped light conducting member, no other light sensitive element being arranged so as to receive light from said other rod shaped light conducting member.

4,293,227

SPRAYING UNIT FOR UNHARDENED CONCRETE AND THE LIKE

Katsushi Tanaka, Takarazuka, and Taro Okamoto, Miki, both of Japan, assignors to Kyokuto Kaihatsu Kogyo Co., Ltd., Nishinomiya, Japan

Filed Sep. 11, 1979, Ser. No. 74,805

Claims priority, application Japan, Oct. 2, 1978, 53-121711

Int. Cl.³ B28C 5/46

U.S. Cl. 366—11

6 Claims


1. A spraying unit for spraying a mixture of unhardened concrete and a quick-set particulate concrete additive, said unit comprising:

- an injection gun having a first and second inlet and an outlet for spraying a mixture of unhardened concrete and particulate additive;
- an unhardened concrete supply apparatus having a motor, and a pump, powered by said motor for pumping unhardened concrete, wherein said pump has an inlet for receiving unhardened concrete and an outlet communicating with said first injection gun inlet and for supplying unhardened concrete to said injection gun; and
- an apparatus for providing a particulate additive at a substantially consistent density and under a positive pressure to said injection gun, said additive apparatus including: a pneumatic conveying means having an air compressor and

a chamber, wherein said chamber has an inlet port for receiving a particulate additive of a substantially consistent density, and air inlet port for receiving compressed air from said compressor, and an outlet port communicating with said second injection gun inlet, whereby, when said chamber receives compressed air and a particulate additive at a substantially consistent density, said means conveys a mixture of particulate additive, at a substantially consistent density, and compressed air to said injection gun;

a particulate additive container for holding a supply of particulate additive;

a second particulate transporting device in said container



and having an inlet for receiving a first maximum volume rate of particulate additive, a screw conveyor means for conveying particulate additive of a substantially consistent density and at a second maximum volume rate, which is less than said first maximum volume rate, and an outlet opening communicating with said first chamber inlet port exteriorly of said container and for discharging particulate additive from said conveyor means to said pneumatic conveying means; and

a first particulate transporting device in said container for transporting particulate additive from a lower portion of said container, and for depositing the same at said first maximum volume rate and at a substantially consistent density to said second device inlet.

4,293,228

DRUM FOR AN ASPHALT MIXING APPARATUS


George W. Swisher, Jr., Oklahoma City; David L. Garbelman, Edmond, and Arthur G. Shaw, Mustang, all of Okla., assignors to CMI Corporation, Oklahoma City, Okla.

Filed Oct. 29, 1979, Ser. No. 89,212

Int. Cl.³ B28C 5/20

U.S. Cl. 366—25

9 Claims



7. In an apparatus for producing hot mix asphalt in a rotating drum disposed on a slant with an input end thereof higher than an opposed discharge end thereof, said apparatus including means for introducing aggregate into the input end of the drum, means for receiving asphalt from the discharge end of the drum, means for introducing a flame into the input end of the drum, means for introducing asphaltic oil into a medial portion of the drum, and flighting arranged in rows about the inner periphery of the drum for lifting and dropping aggregate and asphalt in a veil across the drum so as to transport the

aggregate and asphalt toward the discharge end of the drum, an improved drum comprising:

- a cylindrical shell extending between the input end of the drum and the discharge end thereof; and
- means forming an annular land on the inner periphery of said shell between the input end thereof and the medial portion of the drum where asphaltic oil is introduced into the drum, wherein at least one row of said flighting is carried by portions of the inner periphery of said shell between the means forming the annular land and the input end of the drum and at least one row of flighting is carried by the means forming the annular land.

4,293,229


HYDRAULIC CONTROLS FOR INJECTION UNIT OF INJECTION MOLDING MACHINE

Karl Hehl, Arthur-Hehl-Strasse, 7298 Lossburg 1, Fed. Rep. of Germany

Filed Apr. 15, 1980, Ser. No. 140,615
Int. Cl.³ B29B 1/06

U.S. Cl. 366-78

7 Claims



1. Hydraulic controls for the injection unit of an injection molding machine processing plastic raw materials, which injection unit has a plastification cylinder defining an injection axis and a cooperating plastification screw reaching into the plastification cylinder from behind, including means for rotating the plastification screw in a plastification stroke and means for axially advancing it in an injection stroke, the hydraulic controls for said injection unit being associated with the means for advancing the plastification screw and comprising:

- a hydraulic cylinder assembly of which the cylinder cavity is formed by a bore in a movable member which is connected to the plastification screw for axial movements therewith, and of which the piston is connected to the plastification cylinder by means of a piston rod extending forwardly from the cylinder assembly, so that pressurization of the cylinder space forward of the piston produces an injection stroke of the plastification screw; and wherein the cylinder assembly is convertible so that, in a first assembly configuration, the piston forms the rearward extremity of the piston rod and the cylinder assembly operates in the manner of a single-acting cylinder, suitable for the connection thereto of a hydraulic supply circuit which has presettable proportional-response control valves for the adjustment of the fluid pressure and flow rate which determine the injection stroke and return movement of the plastification screw, and so that, in a second assembly configuration, the piston is adjoined by a rearwardly oriented piston rod extension of a diameter larger than the diameter of the piston rod, and the associated rear cylinder cover has a matching bore forming a seal with the piston rod extension, whereby the cylinder assembly operates in the manner of a double-acting cylinder of the differential-piston type, suitable for the connection thereto of a hydraulic supply circuit which includes an electronically controlled servo-valve receiving electronic input signals from a signal generator which receives feedback

signals from pressure transducers measuring the fluid pressure on both sides of the piston.

4,293,230


APPARATUS FOR PROVIDING FUEL FOR AN OIL BURNER

Lu J. Tan; David Tan, and Jeff Tan, all of 37-53 102st St., Corona, N.Y. 11368

Filed Apr. 12, 1978, Ser. No. 895,071
Int. Cl.³ B01F 3/08, 13/02

U.S. Cl. 366-101

14 Claims



1. Apparatus for preparing a fuel for an oil burner comprising an oil conduit adapted to receive fuel oil under pressure, a water conduit adapted to receive water under pressure and communicating with the oil conduit to flow the oil and water together in the oil conduit with 30 to 60% by volume of water, a first chamber formed with a first baffle, means for introducing the oil and water flow into the first chamber and for directing it against the first baffle for creating turbulence and for mixing of the oil and water, wherein said first baffle is disposed in the flow stream of said oil and water mixture for dispersing said mixture, outlet means in said first chamber on the downstream side of said baffle, a second chamber formed with a second baffle and communicating with the outlet of the first chamber to receive and direct the oil and water mixture against the second baffle to further mix the oil and water, wherein said second baffle is disposed in said second chamber in the flow-stream of said oil and water mixture for dispersing said oil and water mixture, an air conduit communicating with the second chamber downstream of said baffle and adapted to receive air under pressure, the air conduit directing the compressed air into the further mixed oil and water for creating an efficient fuel, and an outlet conduit communicating with the second chamber downstream of said baffle for delivering the fuel to the oil burner.

4,293,231

BEARINGLESS VIBRATOR

John S. Lyle, 671 Cody St., Lakewood, Colo. 80215


Filed Jan. 7, 1980, Ser. No. 109,782
Int. Cl.³ B01F 11/00

U.S. Cl. 366-120

21 Claims

- 21. A bearingless vibrator devoid of chamber forming means and having a rotor acting as a turbine upon communication with a pressurized fluid, said vibrator comprising:
 - a housing having a center axis and an inner wall, said housing including inlet means for receiving the pressurized fluid and outlet means for discharging the fluid; and
 - a rotor having a center axis and contained for rolling movement within said housing, said rotor including a plurality of jets formed adjacent the periphery of said rotor, each jet having an inlet end and an outlet end at the periphery of said rotor, an inlet end of each jet communicating in sequence with said inlet means as said rotor rolls in said

housing to receive the pressurized fluid so that thrust produced by the velocity of the pressurized fluid sequentially exiting each of said outlet means of said jets drives



said rotor eccentrically relative to said center axis of said housing, said rotor impacting against said housing to produce vibrations.

4,293,232

BEARING FOR THE PRINTING HEAD OF A MATRIX PRINTER, AND PRINTING HEAD COMPRISING SUCH A BEARING


Uno K. E. Linder, Stockholm, Sweden, assignor to U.S. Phillips Corporation, New York, N.Y.

Continuation of Ser. No. 885,793, Mar. 13, 1978, Pat. No. 4,180,333. This application Sep. 4, 1979, Ser. No. 72,276
Claims priority, application Sweden, Mar. 15, 1977, 7702881
The portion of the term of this patent subsequent to Dec. 25, 1996, has been disclaimed.

Int. Cl.³ B41J 3/12

U.S. Cl. 400-124

1 Claim



- 1. A bearing for use with an associated printing head of an associated matrix printer having an associated plurality of slidable printing pins which are journaled in the printing head and whose printing ends are situated in the vicinity of each other on a straight line which extends transversely of the direction of a line to be printed, and an associated means for axially displacing each of said printing pins, which comprises:
 - an individual substantially straight guide channel for each printing pin, each printing being guided near the printing pin end thereof, said bearing having a first portion made of a first material and a second portion made of a second material which is harder than said first material, wherein said first portion has at least two substantially straight insert channels formed therein parallel to the

guide channels and also disposed on said straight line, viewed in a cross-section of the guide channels, and said second portion includes at least two pin-shaped inserts manufactured of said second material and two insert channels in which said two pin-shaped inserts are respectively disposed, one of the pin-shaped inserts substantially adjoining one outer printing pin, and the other pin-shaped insert substantially adjoining the other outer printing pin, each pin-shaped insert not being connected to the associated means for axially displacing each of said printing pins.

4,293,233

PRINTER CONTROL SYSTEM


Mark H. Hoffman, Huntsville, Ala., assignor to SCI Systems, Inc., Huntsville, Ala.

Division of Ser. No. 967,090, Dec. 6, 1978, Pat. No. 4,226,546.
This application Jan. 23, 1980, Ser. No. 114,561

Int. Cl.³ B41J 1/30

U.S. Cl. 400-144.2

4 Claims



- 1. In a printer having an electromagnet for driving a print hammer, means for energizing said electromagnet with a pulsating electrical drive signal, the duty cycle of said drive signal being set to produce a hammer impact of a predetermined magnitude, the dwell time of said hammer being substantially greater than the period of said drive signal.

4,293,234

RIBBON CARTRIDGE FOR BAND PRINTER

Edward H. Yonkers, Newton, and Gilbert A. LeDoux, East Taunton, both of Mass., assignors to Data Packaging Corporation, Cambridge, Mass.

Continuation of Ser. No. 897,861, Apr. 19, 1978, abandoned.
This application Aug. 20, 1979, Ser. No. 67,770

Int. Cl.³ B41J 33/10


U.S. Cl. 400-196.1

7 Claims

- 1. A ribbon cartridge for a high speed printer comprising:
 - an elongated body and a pair of arms extending from opposite ends of the body and to one side thereof to form a generally U-shaped ribbon container and an endless ribbon packaged in the container with an exposed loop extending between the ends of the arms;
 - a ribbon passage in each arm extending from the body to the ends of the arms and a chamber in the body for storing a substantial portion of the endless ribbon and in communication with the passages in the arms;
 - an opening in the bottom of the body for receiving a pair of

drive rollers within the body when the cartridge is mounted on the printer;

a ribbon control assembly mounted in the body for movement between a first position which disposes the ribbon between the rollers when the cartridge is mounted on the printer, and a second position in which the ribbon portion



between the rollers is exposed to the rollers thereby to enable the rollers to grip and drive the ribbon; and said ribbon control assembly further including means defining a ribbon dam disposed beyond the location of the rollers for preventing the ribbon from falling out of the body through said opening.

4,293,235

STRUCTURE FOR A LINEAR MOTOR FOR A PRINTER
Yoshifumi Gomi, Shiojiri, Japan, assignor to Kabushiki Kaisha Suwa Seikosha, Tokyo, Japan


Filed Apr. 19, 1979, Ser. No. 31,690

Claims priority, application Japan, Apr. 19, 1978, 53-46195; Apr. 19, 1978, 53-46196

Int. Cl.³ B41J 19/50

U.S. Cl. 400—322

4 Claims



1. A linear pulse motor for a printer comprising:
 - a linear stator having stator teeth on a surface thereof, said surface being perpendicular to the bottom of said printer, said stator teeth extending horizontally from said stator surface;
 - a translating member including a plurality of poles, said poles being spaced apart and inserted into electrical coils, each of said poles having pole teeth in a surface thereof, said pole teeth opposing said stator teeth;
 - a printing mechanism mounted to said translating member and moving side to side in a horizontal direction the horizontal centers of said translating member and said printing mechanism being substantially aligned with the horizontal center line of said linear stator, whereby the force of printing acts perpendicularly on said stator surface having said stator teeth thereon;
- mean for aligning and spacing whereby a gap is maintained between said stator teeth and said pole teeth, and said translating member moves linearly relative to said stator when said pole coils are electrically energized, whereby motor and printing vibrations are reduced and dust and debris do not fall upon said stator teeth.

4,293,236

PRINTER

Munetaka Shimizu, Kawagoe, Japan, assignor to Copal Company Limited, Tokyo, Japan


Filed Nov. 6, 1979, Ser. No. 91,742

Claims priority, application Japan, Nov. 20, 1978, 53-143033; Nov. 20, 1978, 53-159795[U]; Nov. 20, 1978, 53-159796[U]; Nov. 20, 1978, 53-159797[U]

Int. Cl.³ B41J 11/48

U.S. Cl. 400—593

11 Claims



1. A printer of the type in which printing is effected on a receipt paper and a journal paper disposed in parallel to each other, characterized by means for transferring said receipt and journal papers in a horizontal direction, a cutter device adapted to move vertically so as to cut said receipt paper into receipt paper sections after the transfer of the receipt paper, means for guiding said cut receipt paper sections out of said printer in a horizontal direction, a take-up roll for winding said journal paper about the roll after the journal paper has been turned upwardly, separate printing drums for said receipt and journal papers disposed below a horizontal paper transfer plane and separate printing hammers for said receipt and journal papers disposed above said horizontal transfer plane to effect printing on the undersurface of the papers in cooperation with said printing drums, respectively.

4,293,237

IRRIGATION AND DRAINAGE APPARATUS


Melvin J. Robey, 4507 Fortuna, Salt Lake City, Utah 84117; David E. Bingaman, 462 W. 3600 South, Bountiful, Utah 84010, and Arthur E. Read, 24 Hockley Pl., Don Mills, Ontario, Canada (M3A2S4)

Filed Jun. 29, 1979, Ser. No. 53,352

Int. Cl.³ E02B 13/00

U.S. Cl. 405—39

14 Claims



1. An irrigation and drainage apparatus comprising,
 - a main line arranged for subsurface installation in an area to be irrigated to pass water therethrough;
 - a source of water connected to pass water into said main line;

a lateral line for subsurface installation connected to receive water from said main line;

weir means secured in said lateral line for partially blocking a flow of water therethrough consisting of, a half circular wedge shaped plate that is secured across said lateral so as to block a lower portion thereof, said plate having a profile triangular shape with upstanding sides thereof sloping towards one another from ends of a base thereof that meet in a common apex that extends across said lateral line as the weir means crest, which wedge shaped plate contains an internal passage formed therein that is arranged to be capable of being opened through an outer wall of said lateral line to receive, when appropriately connected, a liquid flow therethrough and exhausts such flow through an opening formed in an upstanding side thereof downstream to the water flow from said main line; and means formed in said lateral line below a level of a flow of water therein for passing water therethrough into a surrounding area.

4,293,238

DITCHLESS DRAINLAYER


Eduard N. Kuzin, ulitsa III Internatsionala, 74, kv. 199; Vladimir F. Korelin, Belgradskaya ulitsa, 20, kv. 123; Mikhail L. Fainzilber, ulitsa Budapeshtskaya, 17, korpus 5, kv. 62; Jury P. Egorov, Moskovsky prospekt, 205, kv. 64; Igor V. Erofeenko, Belgradskaya ulitsa, 36, korpus 2, kv. 17; Nikolai V. Karev, Moskovsky prospekt, 138, kv. 159; Jury S. Kozlov, ulitsa Dimitrova, 10, korpus 1, kv. 160; Viktor B. Kudish, ulitsa partizana Germana, 26, kv. 44; Valery K. Kolbasov, Basseinaya ulitsa, 82, korpus 4, kv. 84, and Meri I. Bobchenok, prospekt Kosmonavtov, 13, kv. 40, all of Leningrad, U.S.S.R.

Filed Oct. 23, 1978, Ser. No. 953,450

Int. Cl.³ E02F 5/10; F16L 1/02

U.S. Cl. 405—175

8 Claims



1. A ditchless drainlayer comprising:
 - a frame;
 - a cutter-type working element for laying drains, mounted on said frame;
 - a hydraulic cylinder for changing the angular position of said cutter-type working element, connected to said frame;
 - a transmitter of the angular position of the cutter-type working element connected to said element and to said hydraulic cylinder for changing the angular position of the cutter-type working element;
 - an amplifier-converter for actuating said hydraulic cylinder adapted to change the angular position on signals of said angular position transmitter;
 - a support swivelling around a transverse horizontal axis, adapted to change the height of said cutter-type working element, and being provided with a connecting link and a pair of blades secured thereto and extending outwardly on opposite sides of said link, said connecting link being rotatably connected with said cutter-type working element;

ment by two rods arranged one above the other whose extensions converge in front as the machine goes;

a hydraulic cylinder for turning said support, articulated between said connecting link and said cutter-type working element;

a transmitter for indicating the height of said cutter-type working element connected to said element and to said support-turning hydraulic cylinder; and

another amplifier-converter for actuating said hydraulic cylinder intended to turn the support on signals from the height position transmitter.

4,293,239

METHOD OF ERECTING A VERY LARGE DIAMETER OFFSHORE COLUMN


Terry D. Petty, New Orleans; Carmon R. Costello, Kenner; Gude P. Rao, New Orleans, and David Gansar, Metairie, all of La., assignors to Odeco Engineers Inc., New Orleans, La.

Filed Apr. 2, 1979, Ser. No. 25,961

Int. Cl.³ E02B 9/00

U.S. Cl. 405—195

3 Claims



1. A method for erecting a very large submerged columnar buoyant structure and anchoring the submerged columnar structure above a selected site on the sea bed to allow the structure to draw clean cold water from the sea bottom, comprising in combination the steps of:

- (1) providing a plurality of cylindrical columnar members for assembly one on top of the other, each partially assembled columnar members forming a sub-structure, said columnar members including a lowermost member having a plurality of hooks on the bottom end thereof, a second columnar member shorter than said lowermost columnar member, and an uppermost columnar member having a plurality of circumferentially spaced hooks, each columnar member having an inherent net positive buoyancy and defining therein watertight chambers;
- (2) providing a platform having on a portion of its periphery a plurality of operatively positioned wireline winches;
- (3) providing a transport barge adapted to become partially submerged;
- (4) providing a plurality of anchor weights, each weight having a sheave thereon;
- (5) transporting with said barge and deploying said weights on said selected site by suspending said weights from said wirelines;
- (6) consecutively erecting said columnar members utilizing said suspended weights to pull down each assembled sub-structure;
- (7) securely interconnecting said members and fluidly connecting the chambers of said columnar members utilizing said inherent positive buoyancy to lift the columnar members out of the water for the purpose of making said connections above the water surface;

- (8) ballasting said columnar members with sea water, whereby said fully erected columnar structure is at a desired distance above the seabed; and
- (9) anchoring the submerged columnar structure to the seabed using said weights attached to said wirelines.

4,293,240


METHOD FOR INSTALLING AN ELECTRIC POWER PLANT

Kazuo Ogimoto, Fujisawa; Tomohiro Inoue, Yokohama; Susumu Tanaka, Ushiku, and Yoshio Kobayashi, Ooi, all of Japan, assignors to Tokyo Shibaura Denki Kabushiki Kaisha, Japan
Filed Sep. 27, 1979, Ser. No. 79,465

Claims priority, application Japan, Oct. 5, 1978, 53-122013
Int. Cl.³ E02D 21/00

U.S. Cl. 405—195

6 Claims



1. A method for installing an electric power plant comprising the steps of:

- preparing, at a site where the plant is to be installed, a plant yard in the form of a shallow pool having a foundation forming at least part of the bottom of said pool, said plant yard being connected to a water area whose level varies with time due to ebb and flow, the bottom of said pool being at a lower level of said water area at least when said water level is at a high water level,
- mounting, in a dockyard, equipment forming the plant on a floatable base to form a floatable package,
- submerging a submersible barge having ballast tanks, moving said package over said submersible barge for support thereon, said barge including ballast tanks,
- towing said barge with said package supported thereon to said water area,
- unloading said package from said barge by submerging said barge whereby said package floats,
- moving said package into said plant yard when the water is at a high level, and
- introducing water into said ballast tank of said base of said package to cause said package to sink onto said foundation.

4,293,241

BARGE BUMPER ASSEMBLY

Wilton L. Helveston, and Richard J. Pecoraro, both of New Iberia, La., assignors to International Moorings & Marine, Inc., New Iberia, La.

Filed Feb. 26, 1979, Ser. No. 14,806

Int. Cl.³ E02B 3/22

U.S. Cl. 405—213


2 Claims

1. Offshore platform structures to prevent damage to such structures by vessels and the like comprising:

- (a) an upper shock cell assembly including a rigid cylinder mounted with such structure and a movable piston for moving in and out of said rigid cylinder and further including a resistant resilient material for positioning said piston inside said rigid cylinder and wherein said shock cell assembly operates such that movement of said piston relative to said rigid cylinder by vessels and the like must overcome the resistant resilient force and wherein cessation of the pressure by such vessel enables said resistant

resilient material to return said piston to its original position relative to said rigid cylinder;

- (b) a second lower shock cell assembly including a rigid cylinder mounted with such structure and a movable piston for moving in and out of said rigid cylinder and further including a resistant resilient material for positioning said piston inside said rigid cylinder and wherein said lower shock cell assembly operates such that movement of said piston relative to said rigid cylinder by vessels and the like must overcome the resistant resilient force and wherein cessation of the pressure by such vessel enables said resistant resilient material to return said piston to its original position relative to said rigid cylinder;
- (c) a stabbing member being attached to the opposite end of said piston of said lower shock cell assembly, said stabbing member including a cylindrical stabbing base, an inwardly tapered portion above said stabbing base, and an upwardly extending stinger attached to said tapered portion;
- (d) a cylindrical, hollow bumper assembly member pivotally mounted at its upper end to the opposite end of said upper



shock cell assembly to said piston of said upper shock cell assembly and depending downwardly therefrom to concentrically fit around said stabbing base for maintaining said hollow cylindrical member and stabbing member in a vertical manner relative to each other, said bumper assembly including a rigid support plate fixed thereto adjacent the lower end thereof;

- (e) a bumper support plate supported by said rigid support plate, said bumper support plate having an opening there-through to fit loosely about said bumper assembly; and
- (f) a plurality of cylindrical shaped resilient bumper members supported about said bumper assembly on said bumper support plate having openings therein for fitting rotatably around said bumper assembly member wherein contact on the outer surface of said bumpers with a vessel and the like causes one or both of said upper and lower shock cell assemblies to operate such that each of said pistons is driven inwardly relative to said leg or structure and wherein cessation or elimination of pressure on said bumpers enables said resilient, resistant means to return said pistons to their original positions.

4,293,242

PILES


Stanley Merjan, 16 Beacon Dr., Port Washington, N.Y. 11050

Continuation-in-part of Ser. No. 792,354, Apr. 29, 1977, abandoned. This application Sep. 29, 1978, Ser. No. 947,184

Int. Cl.³ E02D 5/50

U.S. Cl. 405—239

23 Claims



1. Process which comprises driving a pile having a hollow stem and an enlarged preformed lower tip, which tip has a diameter of at least 19 inches, through overlying non-bearing soil into an underlying bearing layer of sand in which the driving causes said enlarged tip to penetrate into said underlying layer and the driving is continued into said underlying layer until the resistance to the driving force shows that the designed load bearing capacity of the pile has been attained, said tip having a central, upwardly open, socket and the bottom part of said stem being fitted in said socket, the driving of said enlarged tip forming an annular space around said stem above said tip and above said underlying layer, said method including the steps of supplying wet, flowable, concrete to said annular space during said driving to form an annular body of said flowable concrete in said annular space and in contact with said stem and with the soil surrounding said annular space, permitting said flowable concrete to set after said driving is completed, providing tying means for transmitting uplift forces at the top of said stem and including reinforcing rods extending through said stem from the top of said stem into said bottom part of said stem within said socket, filling said hollow stem with unhardened concrete and permitting said concrete to set in said stem and around said reinforcing rods, said stem being secured to said tip in such fashion that uplift forces are transmitted to said tip, forming a group of piles by driving at least one other pile adjacent to the first-mentioned pile and casting concrete over said group and around said tying means to form a pile-supported structure, said hardened concrete in said annular space increasing the uplift capacity of said first-mentioned pile, the relationship between said pile and the soil being such that any load bearing support contributed by the concrete surrounding the stem by frictional contact between said surrounding concrete and the soil is less than 5% of the load bearing support contributed by said tip; the dimensions or said tip and stem being such that the width of the annular space around the stem is at least about 6 inches and the length of the stem in the soil is not over about 30 feet, said tying means being constructed and arranged so as to have sufficient strengths to transmit an uplift force of 52.5 tons per pile to said stem.

4,293,243

MINE ROOF BOLT ASSEMBLY GUARD

Carl N. Graybeal, General Delivery, Wolf Pen, W. Va. 24896; Basil E. Rogers, Beckley, W. Va.; Joseph V. Cox, Stanaford, W. Va., and Roy R. Rogers, Beckley, W. Va., assignors to Carl N. Graybeal, Wolf Pen, W. Va.

Filed Feb. 14, 1979, Ser. No. 12,145

Int. Cl.³ A47G 3/00; E21D 21/00

U.S. Cl. 405—259

3 Claims


1. In combination with a mine roof bolt assembly comprising a mine roof bolt having a head and a mine roof bolt plate adapted to fit around said bolt, a guard comprising:

- a cap adapted to fit over the head of said bolt, said cap

including an upper surface, a lower surface and a cavity in said upper surface into which said mine roof bolt head may be inserted;

fixing means associated with said cavity for removably fixing said cap to said bolt head; and

an annular skirt, depending from said cap and extending outward from adjacent said lower surface for a distance at



least sufficient to completely cover said bolt plate, said skirt gradually curving towards said bolt plate;

wherein said mine roof bolt assembly includes hanger loops and said skirt includes cut-outs in positions corresponding to said loops;

wherein said guard presents a substantially continuous surface, having a curved periphery, to a passing miner.

4,293,244

PICK ARM ANCHOR ASSEMBLY


David C. Donan, Jr., Manitou, Ky., assignor to Waimea Company Inc., Manitou, Ky.

Filed Jul. 30, 1979, Ser. No. 61,595

Int. Cl.³ E21D 21/00

U.S. Cl. 405—259

5 Claims



1. A pick arm anchor assembly comprising, in combination:
- (a) a bolt having a threaded stem for insertion into a bolt hole;
- (b) a bolt base plate operably engaged to one end of the threaded stem of said bolt;
- (c) a threaded wedge nut having an inner surface adapted for engagement upon the threaded stem of said bolt, and having an outer surface of larger diameter at the upper end thereof and tapering to a smaller diameter at the lower end thereof, said inner surface being adapted for engagement upon the threaded stem of said bolt such that as the bolt is rotated in a first direction, said threaded base nut advances upon said threaded stem;
- (d) an expandable outer expansion shell unit having an inner surface for selective engagement with the wedge-shaped outer surfaces of said threaded wedge nut such that as the threaded wedge nut is selectively engaged upon the

threaded stem of the bolt as aforesaid, the threaded wedge nut advances down the threaded stem of the bolt, causing the outer surface of the lower end of said threaded wedge nut to selectively engage against the inner surface of the outer expansion shell unit such that as there is more engagement of said wedge nut and outer expansion shell unit, said outer expansion shell unit is expanded radially outward to engage the walls of the bolt hole;

(e) a threaded base nut adapted for selective engagement with the threaded stem of said bolt, such that said base nut is placed on said threaded stem above the larger diameter end of the aforesaid wedge nut;

(f) a pick arm comprising a lower end having a foot for engaging the threaded stem of the bolt between said wedge nut and said base nut and for engaging said base nut to prevent rotation of said base nut as the threaded stem of said bolt is rotated, and further having one or more attachment loops adaptable to receiving additional pick arms, a middle portion having a generally longitudinally concave inner surface, an upper portion having a biased sloped inner surface, and an upper-most portion having a protrusion for engagement with the walls of a bolt hole, as said pick arm is expanded radially outwardly;

(g) a back up wing comprising a lower end having a foot for engagement of the threaded stem of said bolt between said wedge nut and said base nut, a middle portion having a biased sloped inner surface and a generally straight outer surface adapted for positive engagement against the walls of a bolt hole;

(h) a bias thrust wedge adapted for positioning between the inner surface of said back up wing and said longitudinally concave inner surface of said pick arm and having a lower portion adaptable for engagement upon the upper end of the threaded stem of the bolt, a middle portion, and an upper end having outer surfaces with a major bias for engaging the biased sloped inner surface of the upper portion of said pick arm and a minor bias for engaging the bias sloped inner surface of said back up wing, such that as the threaded stem of said bolt is rotated in a first direction as aforesaid, said bias thrust wedge moves in a first longitudinal direction opposite to the aforesaid advancement of said threaded wedge nut causing said major and minor biased outer surfaces of said thrust wedge to engage the inner surfaces of the pick arm and the back up wing respectively as aforesaid, such that said pick arm and back up wing are expanded radially outward to engage the walls of a bolt hole contemporaneously with the advancement of said threaded wedge nut down the threaded stem of said bolt to engage said inner surfaces of said expansion shell unit as aforesaid to cause radial expansion of the outer expansion shell unit;

(i) a stabilizer having a lower end adapted for engagement with the threaded stem of said bolt and positioned below the outer expansion shell unit, one or more legs for engaging the lower portion of the bias thrust wedge and adapted to prevent rotation of the pick arm, back up wing and bias thrust wedge while the threaded stem of the bolt is being rotated; and

(j) an elastic expansion band adaptable to contain said pick arm and said back up wing around said bias thrust wedge so as to prevent said pick arm and back up wing from expanding to a greater diameter than that of the bolt hole prior to insertion of the pick arm anchor assembly therein.

4,293,245 STRUCTURAL SYSTEM AND STRUCTURAL ELEMENTS FOR USE AND CONSTRUCTION OF EARTH FILLED WALLS

Felix P. Jaecklin, Geissbergstrasse, 59, 5400 Ennetbaden, Switzerland


Filed Jun. 8, 1979, Ser. No. 46,847

Claims priority, application Switzerland, Jun. 13, 1978, 6411/78; Nov. 21, 1978, 8313/78

Int. Cl.³ E02D 5/00

U.S. Cl. 405—272

27 Claims



1. A structural system for the construction of walls comprising a framework consisting of solid frame elements and being filled with earth material, said frame elements extending in at least one plane and having at least one support area on at least one side, said frame elements further including at least one longitudinal beam having a cross-section with at least one portion thereof arranged at an acute angle against the main plane of the frame or slab, the upper surface thereof forming a substantially flat support for said earth material, at least one such longitudinal beam being located at the front side of said wall and having an upper front edge portion being positioned at a greater height compared with said flat support and forming a board for retaining a portion of said earth material resting on said flat support, the system further including holes extending at least partly vertically through said framework and distance elements between at least two of said frame or slab elements which are positioned one above the other such that the earth material at least partially filling said vertically extending openings forms at least one sloped surface extending at least partly through the scope between said frame or slab elements positioned one above the other.

4,293,246 MINE ROOF SUPPORT STRUCTURE

Werner Boer, Castrop-Rauxel; Hans Lachner, Herne; Guenter Maschon, Dortmund; Joerg Richter, Wattenscheid; Heinrich Schulte, Witten, and Hans Warnke, Herne, all of Fed. Rep. of Germany, assignors to Klockner-Werke AG, Duisburg, Fed. Rep. of Germany


Filed Sep. 20, 1979, Ser. No. 77,478

Claims priority, application Fed. Rep. of Germany, Sep. 20, 1978, 2840835

Int. Cl.³ E21D 15/44

U.S. Cl. 405—291

4 Claims



1. In a mine roof support structure comprising a floor skid, a supporting shield, a roof cap pivotally connected at a roof cap joint to a forward end of said shield, said shield being

pivotally supported on said skid at the backfilling end of the structure by a pair of rocker arms forming a lemniscate guide, hydraulic props supporting said roof cap being pivotally connected at opposite ends to said cap and to said skid, and a hydraulic actuator pivotally connected at opposite ends to said skid and to one of said arms which is inextensible, said actuator capable of being rendered rigid, the improvement wherein the other of said rocker arms is disposed nearer the coal-face end of the support structure than said one rocker arm, said other arm being longitudinally adjustable and being pivotally connected at opposite ends to said skid and to said shield, and said other arm being so constructed that said opposite ends thereof may be adjusted relative to one another to enable said cap and said roof cap joint to follow a lemniscate path during settling of the roof while said actuator is made rigid, and to follow a circular arc during a lowering of said cap toward said skid upon actuation of said hydraulic actuator.

4,293,247

SEALS FOR MINE ROOF SUPPORTS

Harry Rosenberg, Lüdinghausen, and Norbert Hölken, Lünen, both of Fed. Rep. of Germany, assignors to Gewerkschaft Eisenhütte Westfalen, Lünen, Fed. Rep. of Germany


Filed Nov. 28, 1979, Ser. No. 98,187

Claims priority, application Fed. Rep. of Germany, Dec. 8, 1978, 2853050

Int. Cl.³ E21D 15/44

U.S. Cl. 405—296

23 Claims



1. A mine roof support which includes a roof-engageable frame structure, a goaf shield pivotally connected to the frame structure, gap sealing means composed of plates displaceably arranged at the sides of the frame structure and the goaf shield, the plates at the sides of the frame structure overlapping the plates at the respective associated side of the goaf shield in the zone of pivotable connection between the frame structure and the goaf shield, piston and cylinder units for effecting relative adjustable displacement between the plates at the opposite sides of the frame structure and goaf shield, spring means for urging the plates at the opposite sides of the frame structure and goaf shield apart and detachable locking elements for fixing the plates in a set position.

4,293,248

WALKING ROOF SUPPORT

Wincenty Pretor, Gliwice; Edward Rozmus, Katowice; Zbigniew Korecki, Gliwice, and Stanislaw Karmanski, Tarnowskie Gory, all of Poland, assignors to Centralny Ośrodek Projektowo-Konstrukcyjny Maszyn Górnictwa "Komag", Gliwice, Poland

Filed Feb. 21, 1979, Ser. No. 13,312

Claims priority, application Poland, Feb. 23, 1978, 204847


Int. Cl.³ E21D 23/08

U.S. Cl. 405—300

3 Claims

1. A walking roof support unit comprising first and second support means disposed adjacent one another for being selectively spragged and released between the floor and the roof of a structure, each support means including a base, hydraulically operated first and second props extending vertically from said base in spaced parallel relation thereon, and a roof beam supported on said props, and coupling means connecting said first and second support means for longitudinally advancing said

first and second support means stepwise and in sequence parallel to one another, said coupling means comprising a guide secured to the props of the first support means, a guide shoe slidably mounted on said guide for relative movement in the longitudinal direction, said guide having a longitudinal T-shaped slot and said guide shoe including a longitudinal T-shaped end slidably engaged in said slot, two parallel, trans-



versely extending pull rods respectively pivotally connected to the props of the second support means and to said guide shoe, an inclined pull rod pivotally connected to one of the props of said second support means and to said guide shoe and extending diagonally between said two pull rods, and a longitudinally extending hydraulic cylinder means connecting said guide and guide shoe for relatively displacing the same longitudinally.

4,293,249

MATERIAL HANDLING SYSTEM AND METHOD FOR MANUFACTURING LINE


Paul L. Whelan, Dallas, Tex., assignor to Texas Instruments Incorporated, Dallas, Tex.

Filed Mar. 3, 1980, Ser. No. 126,597

Int. Cl.³ B65G 51/02

U.S. Cl. 406—72

29 Claims



1. A line for manufacturing an article comprising: a plurality of work stations, each of said work stations performs at least one manufacturing operation and at least one of said plurality of stations operates at subatmospheric pressures, storage means operatively connected to said subatmospheric work station for loading and unloading articles therefrom at atmospheric and subatmospheric pressures, and pressurized gas transport means for transporting said article at subatmospheric pressures between said storage means and said subatmospheric work station.

4,293,250

APPARATUS FOR TRANSFERRING SOLIDS

Takeshi Hayashi, No. 85-3, Mitsucho, Bezaiten, Muya-cho, Naruto-shi, Tokushima-ken, Japan


Filed Dec. 10, 1979, Ser. No. 101,793

Claims priority, application Japan, Dec. 8, 1978, 53-152890

Int. Cl.³ B65G 53/30

U.S. Cl. 406—109

10 Claims



1. An apparatus for transferring solids while preventing damage to such solids due to the shock of transfer comprising a sealed chamber of a water-tight structure, a decompressing means for exhausting air out of the sealed chamber, a feeding means for feeding to the sealed chamber a liquid transfer medium, and a solids transfer pump for transferring the solids together with said liquid out of the sealed chamber, in which the sealed chamber is provided with an inlet opening to which an inlet pipe is connected, an outlet opening positioned above the level of the liquid in the sealed chamber and to which the suction side of the decompressing means is connected, and a delivery opening for delivering solids therethrough positioned below the level of the liquid in the sealed chamber and communicating with the suction side of the solids transfer pump, and in which air is exhausted out of the sealed chamber by means of the decompressing means, and thereby solids being introduced through the inlet pipe into the sealed chamber, dropped in and mixed with the liquid stored in the sealed chamber, and then transferred together with the liquid as a transfer medium by the solids transfer pump to a predetermined location.

4,293,251

DEVICE FOR TRANSFERRING FLUID TO A ROTATING UNIT

Kjell Anderson, Fagersta, Sweden, assignor to Seco Tools AB, Fagersta, Sweden


Filed Apr. 25, 1980, Ser. No. 143,858

Claims priority, application Sweden, Jun. 12, 1979, 7905152

Int. Cl.³ B23B 27/10; F16L 27/08

U.S. Cl. 408—59

4 Claims



1. A device for transferring fluid such as a cooling or flushing medium from a fluid source to a rotating member, said device including a housing mountable on said rotating member which comprises:

- a first member non-rotatably attachable to said rotating member,
- a second member rotatably mounted on the outside of said first member,
- said first and second members forming first passage means for fluidly connecting the fluid source with a fluid passage in the rotating member,
- connecting means for securing said first member non-rotatably to the rotating member, said connecting means disposed in said first passage means and including a through-flow passage to conduct fluid to the fluid passage in the rotating member, and
- means retaining said second member rotatably on said first member such that said first and second members are installable as a unit onto said rotating member and securable to the latter by said connecting means.

4,293,252

DRILL BIT

Dieter Kress, Aalen, and Friedrich Häberle, Lauchheim, both of Fed. Rep. of Germany, assignors to Mapal Fabrik für Präzisionswerkzeuge, Aalen, Fed. Rep. of Germany


Filed Jan. 29, 1980, Ser. No. 116,389

Claims priority, application Fed. Rep. of Germany, Feb. 1, 1979, 2903814

Int. Cl.³ B23B 51/00

U.S. Cl. 408—224

7 Claims



1. Drill bit having an axis of rotation with a first end extending transversely of the axis of rotation, said first end having a recess therein forming a drill bit mouth for chip removal, a plurality of turnable cutting plates located in the cutting position in a plane extending generally in the direction of the axis of rotation and also radially outwardly from the axis of rotation, each said cutting plate having a plurality of cutting edges with the active cutting edges arranged in the cutting position being disposed in a step-wise manner in the axial plane of said cutting plates, wherein the improvement comprises that in the axial plane in the cutting position said cutting plates have a parallelogram shape and said cutting edges on said cutting plates include main cutting edges with at least certain of said main cutting edges on one of said cutting plates being in parallel relation with at least certain of said main cutting edges on an adjacent one of said cutting plates, a parallel said main cutting edge on one of said cutting plates being disposed in contact with a corresponding parallel said main cutting edge on the adjacent one of said cutting plates, said recess in said first end of said drill bit having a shoulder formed therein providing a support for said cutting plates, and means for radially adjustably positioning said cutting plates in the cutting position.

4,293,253

TOOL HOLDER AND CARBIDE INSERT


Clyde E. Ott, c/o Pace Precision Tool & Die Co., Inc., Ohio Ave., DuBois, Pa. 15801

Filed Jun. 13, 1979, Ser. No. 48,096

Int. Cl.³ B23B 51/12

U.S. Cl. 408—226

3 Claims



1. A tool holder and bit construction comprising a rotatable holder body, means to connect said body to rotating mechanism, and a carbide insert.

nism at one end, a tool shank receiving cavity at the other end, said cavity being of flattened rectangular cross-section, diminishing uniformly in area from its widest dimension at the entrance, to the inner end on a total taper of 8 degrees with minimum tolerance therefrom, the tool bit being a preformed carbide composition member having a shank with corresponding cross-section and taper tolerance substantially identical to that of the cavity, shank being frictionally positioned in the cavity, and means to effect removal of said shank from the cavity.

4,293,254

COUNTERSINKING TOOL WITH REMOVABLE CUTTING INSERTS


Michael Markovics, Lindenhurst, Ill., assignor to Everede Tool Company, Chicago, Ill.

Filed Sep. 17, 1979, Ser. No. 76,175

Int. Cl.³ B23B 51/00; B26D 1/12

U.S. Cl. 408—229

15 Claims



1. In combination, a rotatable holder and a plurality of cutting inserts for use with said holder as a countersinking tool, said combination comprising:

- a frusto-conical portion on said holder;
- said frusto-conical portion tapering toward a terminal end thereof constituting the terminal end of said holder;
- a plurality of seating surfaces, one for each of said inserts;
- each of said seating surfaces being located at least partially on said frusto-conical portion;
- each of said seating surfaces lying in a plane parallel to the axis of said holder and extending inwardly from the periphery of said holder to an inner end of said seating surface;
- a locating recess at the inner end of each seating surface;
- each insert having a body, a cutting edge portion and an inner end portion opposite and spaced from said cutting edge portion;
- said locating recess comprising means for receiving said inner end portion of an insert and for cooperating with said seating surface to mount said insert on said holder;
- each locating recess comprising a locating surface disposed angularly to said seating surface and joining the latter along an interior edge;
- said inner end portion of the insert comprising means for seating on said locating surface;
- said recesses and their respective locating surfaces converging toward each other with said recesses meeting at said terminal end;
- said recesses terminating at said terminal end without intersection or overlapping of the recesses;
- said inserts and their respective inner end portions converging toward each other in the direction of said terminal end of the holder;
- each insert having a forward end portion adjacent said cutting edge portion and extending from the latter toward a projected junction with said inner end portion;
- said forward end portion of the insert being located adjacent said terminal end of the holder;
- said projected junctions overlapping at said terminal end;

said holder having a predetermined radius at said terminal end;

the distance from the junction of said cutting edge portion and said forward end portion to said projected junction being greater than said predetermined radius;

the junction of said cutting edge portion and said forward end portion being radially spaced from the axis of said holder;

each insert being cut-away from said projected junction to accommodate the inner end portions of the inserts as they converge in said holder and to prevent said inner end portions from interfering with each other at said terminal end of the holder;

said forward end portion of the insert having a length less than said predetermined radius.

4,293,255

LOAD CARRYING PLATFORM OR BACK FOR VEHICLES

Heinrich Hrasche, Dietikon, Switzerland, assignor to Swiss Aluminium Ltd., Chippis, Switzerland

Division of Ser. No. 850,155, Nov. 10, 1977, Pat. No. 4,167,273.


This application Apr. 30, 1979, Ser. No. 34,766

Claims priority, application Switzerland, Dec. 8, 1976, 15459/76

Int. Cl.³ B60P 7/00

U.S. Cl. 410—104

7 Claims



1. Load carrying platforms or backs of vehicles, in particular such platforms made out of light metal elements in a platform frame and for vehicles with at least one ring-shaped holding device which is hinged to the load carrying platform and is for attaching ropes or the like clamping facilities for securing loads in place, in which the load carrying surface is provided with at least one groove-shaped recess which has a constricted opening, into which a bearing part of the hinged holding device, pivotable about the long axis of the recess, fits and from which it can be removed, wherein said holding device comprises an arc-shaped part and at least one transverse rod or the like projecting out from said part and having at its free end the bearing part in bolt form.

4,293,256

LOAD INDICATING FASTENER

Walter R. Pamer, Parma, Ohio, assignor to The Lamson & Sessions Co., Cleveland, Ohio

Filed Nov. 9, 1979, Ser. No. 92,648


Int. Cl.³ F16B 31/02

U.S. Cl. 411—11

21 Claims

1. A load indicating fastener for indicating when a predetermined preload has been applied to said fastener to thereby apply a force against a member and for indicating when the predetermined force against the member is reduced, said load indicating fastener comprising a thread convolution, a body section connected with said thread convolution, and a load transmitting and indicating section connected with said body section, said load transmitting and indicating section including a bearing section having a flat annular bottom surface which extends perpendicular to a central axis of said thread convolution.

tion, is adapted to abuttingly engage the member and is disposed in a coaxial relationship with said thread convolution, said body section being disposed on a first axial side of said load transmitting and indicating section and said bottom surface being disposed on a second axial side of said load transmitting and indicating section, said load transmitting and indicating section further including an undulating annular spring section circumscribing said bearing section and disposed in a coaxial relationship with said bearing section and thread convolution, said spring section having undulations which have a first amplitude when said spring section is in an unloaded condition prior to the application of the predetermined preload to said fastener and which are resiliently flattened upon the application of the predetermined preload to said fastener to indicate that the predetermined preload has been applied to said fastener, said spring section being returnable from the flattened condition toward the unloaded condition to increase the amplitude of said undulations upon a reduction in the force applied to the spring section to indicate the reduction in the preload applied to said fastener, said spring section having a circular rim portion which is disposed in a coaxial relationship



with said thread convolution and having an undulating bottom surface disposed on the second side of said load transmitting and indicating section, said bottom surface of said spring section having crest portions and trough portions which have amplitudes which increase from zero to a maximum amplitude at the rim portion of said load transmitting and indicating section as the radial distance outwardly from said bearing section increases, said crest portions of said bottom surface of said spring section extending tangentially to the plane of the bottom surface of said bearing section throughout the radial extent of said crest portions, said trough portions sloping radially and axially outwardly from said bearing section in an axial direction away from said body section, said trough portions being engageable with the member, said spring section being resiliently deflectable toward said body section to flatten the undulations in said spring section under the influence of forces applied against said trough portions upon application of the predetermined preload to said body section, said spring section being resiliently returnable to increase the amplitude of said trough portions upon a reduction in the force applied to said trough portions by the member to provide a visual indication of the reduction in force.

4,293,257

TENSION INDICATING WASHER


Francis C. Peterson, St. Charles, Ill., assignor to Illinois Tool Works Inc., Chicago, Ill.

Filed Mar. 17, 1980, Ser. No. 130,670

Int. Cl.³ F16B 31/02, 39/24

U.S. Cl. 411-11

3 Claims



1. A tension indicating washer to indicate a predetermined loading in a joint, said washer comprising an annular disc-like

body portion having first and second opposed faces with said second face defining a bearing surface, said body portion having an aperture adapted for receiving the shank of a threaded fastener; a pair of arm members projecting outwardly from the outer periphery of said body portion, each said arm having an elbow and an outer extremity extending in a direction axially away from bearing surface from said elbow to a position above said first face of said body portion; each elbow having a circumferentially inner and a circumferentially outer section, said circumferentially inner sections being adjacent each other, the circumferentially outer section of each elbow being displaced to a horizontal plane below the horizontal plane of said circumferentially inner section such that as tension is applied to the joint, the elbow will cause rotation of at least a portion of each arm so that the outer extremities thereof will approach each other and will touch when the predetermined proper loading is achieved in the joint.

4,293,258

SELF DRILLING BLIND RIVET


Arthur J. McKewan, Rochester, Mich., assignor to Microdot Inc., Darien, Conn.

Continuation of Ser. No. 839,340, Oct. 4, 1977, abandoned. This application Jul. 10, 1979, Ser. No. 56,209

Int. Cl.³ F16B 13/06; E04B 1/49

U.S. Cl. 411-30

5 Claims



1. A self drilling blind rivet comprising a hollow elongated rotatable one piece body of hardenable metal having flange means and torque receiving means formed therein at one end and having a thick second end with a hardened drill bit formed therein capable of drilling through metal parts, said torque receiving means enabling said body to be rotated whereby said drill bit may drill a hole through metal parts to be held together by the rivet, said body including a plastically deformable sleeve section extending between said flange means and torque receiving means and said drill bit and having a hardness significantly lower than said drill bit and low enough to enable it to be upset into a radial flange pleat by the application of axial compression to it whereby parts may be clamped between said flange means and said flange pleat, said body having a blind bore opening out of said one end, and a mandrel in and extending out of said bore and having a radially enlarged head located near the blind end of the bore and being slidable inside the bore, said sleeve section having a reduced diameter portion forming a radial shoulder engageable with said enlarged head for blocking removal of the mandrel from the bore and serving to transmit tension on the mandrel into axial compression on the sleeve section to enable said compression to cause it to collapse and form said flange pleat, said drill bit being a permanent part of the body and remaining integral with said body after said collapse of said sleeve section.

4,293,259

LOCKING TOGGLE BOLT

Heinrich Liebig, Wormserstrasse 23, D-6102 Pfungstadt, Fed. Rep. of Germany


Filed Dec. 1, 1978, Ser. No. 965,472

Claims priority, application Fed. Rep. of Germany, Dec. 24, 1977, 2758091; May 2, 1978, 2819289

Int. Cl.³ F16B 13/08

U.S. Cl. 411-32

13 Claims



1. A form-fitting connecting arrangement comprising in combination: a workpiece having an opening therethrough, an article having a cylindrical blind bore being axially aligned with said opening and an undercut surface extending essentially radially outwardly from said blind bore and at a certain distance from the orifice of said bore, and a toggle having an elongated bolt and a toggle body having a diameter corresponding substantially to the diameter of the bore, said opening having a transverse dimension at least as great as said diameter of the bore, said toggle being introducible through the opening into the bore, locking elements mounted on said toggle body and having ends facing the bore orifice, said elements being adapted to be swung from a position lying within the diameter of the bore into a position in which they project at least partially beyond the diameter of the toggle body and engage locking elements of the bore, said toggle body being of relatively low height and being mounted on the bore-internal end of said bolt at the blind end of the bore, said locking elements having bore-internal ends closing together on said bottom piece to form a thick-walled cylindrical sleeve enveloping said bolt, an elongated cylindrical sleeve arranged longitudinally displaceably around said bolt and having an end tapering conically towards the interior of the bore and engaging between the ends of the locking elements facing the bore orifice, so that, upon a displacement of the bottom piece in the direction of the bore orifice, the ends of the locking elements are swung positively radially outwardly, the length of said elongated sleeve equalling substantially said certain distance of said undercut surface from the orifice of said bore plus the thickness of the workpiece at said opening plus the length of said displacement of said bottom piece necessary for swinging said locking elements radially outwardly into locking engagement with said undercut surface, said bolt having on its outer end remote from said blind end of said bore means on said bolt for effecting said displacement and including means for providing a bearing surface with said workpiece.

4,293,260

SCREW GROMMET

Masaharu Kojima, and Seiji Mitomi, both of Toyota, Japan, assignors to Nifco Inc., Yokohama, Japan

Filed Nov. 13, 1979, Ser. No. 93,783

Claims priority, application Japan, Nov. 21, 1978, 53-142795


Int. Cl.³ F16B 13/06

U.S. Cl. 411-44

5 Claims

1. An improvement in a screw grommet adapted to accept a screw of a predetermined diameter and to be inserted in a polygonal hole of the type including a head portion, a barrel

portion extended downwardly from the head portion having an external cross-section substantially matching said polygonal hole, and a continuous axial bore through the head portion and a substantial portion of the barrel portion and possessed of an inside diameter smaller than the diameter of said screw, external means provided on the barrel portion so as to match to at least one of the corners of said polygonal fitting hole punched in a given panel for acceptance of the grommet, said external means defining a flexible portion extending angularly relative to adjacent sides of said barrel portion and further extending



4,293,261

REINFORCING SEALING SHEET METAL FASTENER ANCHOR

Francis G. Frano, Hoffman Estates, Ill., assignor to Illinois Tool Works Inc., Chicago, Ill.

Filed Nov. 19, 1979, Ser. No. 95,288

Int. Cl.³ F16B 37/04

U.S. Cl. 411-85

9 Claims



1. A reinforcing sealing system for use with at least two fasteners mounted in a multi-apertured thin work panel, including in combination a work panel having at least two through apertures spaced a predetermined distance, a sheet metal fastener anchor having a generally planar base, a plurality of fastener accepting apertures in said base equal in number to said work panel apertures and spaced apart said predetermined distance, gripping means extending in a first direction upwardly beyond one surface of the plane of said base, locating means comprising at least two tabs struck from within the margins of and extending generally normally to said base in a second opposite direction downwardly beyond a second surface of the plane of said base opposite said gripping means, said locating means being positioned in spaced relation to one another with only one of said tabs being positioned adjacent to each one of said spaced fastener accepting apertures and thereby adapted to engage the margins of said at least two

spaced work panel apertures and positively locate and orient said anchor fastener accepting apertures relative to said at least two work panel apertures, and continuous initially imperforate double-faced adhesive tape having one face thereof covering a substantial portion of the second surface of said base, said tape adapted to cover and seal both of said work panel and fastener accepting apertures, said spaced tabs piercing said tape and extending outwardly beyond the second face of said tape to permit blind locating and orientation of said fastener anchor apertures relative to said work panel apertures.

4,293,262


REUSABLE PREVAILING TORQUE NUT

Horace D. Holmes, 28576 Green Willow, Farmington Hills, Mich. 48018

Filed Jun. 8, 1979, Ser. No. 46,736

Int. Cl.³ F16B 39/30

U.S. Cl. 411—311



1. A prevailing torque female fastener element for use in combination with a male threaded element having a standard thread form with standard flank angles, said female element comprising a nut body having a threaded hole at least partly therethrough, the threaded hole being characterized by a thread form having a first depth along a first portion thereof and a second reduced thread depth along a second portion contiguous with the first portion, said second reduced depth being formed by a truncation of the thread flanks thereby to define a flat surface of truncation at the major diameter of said second portion, the nut body being constructed to exhibit greater radial compliance in the portion of reduced thread depth, the increased radial compliance being achieved by a reduced wall thickness in the nut body surrounding the portion of reduced thread depth, thus to permit radial and circumferential expansion of the nut body when engaged with a male fastener element or standard thread form, at least the trailing flank angle of the nut body being greater than the corresponding mating flank angle of a standard male thread form so as to provide longitudinal clearance therebetween when threadedly engaged.

4,293,263


SCREW LOCK RIVET

Robert H. Zankl, 5410 Banyan Dr., Miami, Fla. 33156

Filed Nov. 26, 1979, Ser. No. 97,522

Int. Cl.³ F16B 19/04

U.S. Cl. 411—500



1. In a screw lock rivet for use in adjustably securing a

riveted member to a sheet metal companion member having an adjustment slot and an opening communicating with the adjustment slot for admitting a screw lock rivet head, the combination with said sheet metal companion member of a rivet head, a rivet shank integrally formed with and extending axially outwardly of the underside of said rivet head, said underside of said head being formed with a flange comprising a flat, transversely-extending portion and an axially outwardly-projecting arcuate ramp portion, said shank comprising a shank base portion extending into a cylindrical shank outer end portion of decreased cross-sectional size to define with said shank base portion a shoulder against which a member to be riveted to seats upon the riveting deformation of said shank outer end portion, the axial distance between the outwardmost projection zone of said ramp portion and said shoulder being less than the thickness of the companion member to be riveted to, and tool engaging means at the outer end of said rivet head to facilitate turning of the lock screw rivet with respect to a companion member to be riveted to, said shank base portion being ovoid in transverse cross-sectional shape, the arcuate extent of said axially outwardly-projecting arcuate ramp portion being no greater than the maximum diameter of said shank portion, the major axis of said ovoid shank portion and the radial direction of said arcuate ramp portion lying along the same transverse diameter as that of said cylindrical shank outer end portion, said major axis having a length greater than the width of the companion member adjustment slot.

4,293,264

PIVOTAL SHIPPING RACK SUPPORTING APPARATUS


Richard G. Gilts, Walbridge; Earl A. Hille, Elmore; Albert W. Kleine, Jr., Sylvania, and Donald E. Shamp, Millbury, all of Ohio, assignors to Libbey-Owens-Ford Company, Toledo, Ohio

Filed Dec. 7, 1979, Ser. No. 101,124

Int. Cl.³ B65G 57/28

U.S. Cl. 414—38

6 Claims



1. An apparatus for tilting a sheet-carrying shipping container from an upright transporting attitude to a container packing attitude, comprising:

- a flat pivotable member for carrying the shipping container and pivotable between a container loading/unloading attitude and a container packing attitude;
- a pair of spaced-apart upright members with their lower ends affixed to and normal to one edge of said flat pivotable member for supporting the shipping container in said container packing attitude;
- a base for pivotably supporting said pivotable member;
- means for pivotably mounting said one edge of said pivotable member to said base;
- first upstanding means affixed to said base for supporting said pivotable member in the container loading/unloading attitude;
- second upstanding means affixed to said base for supporting said pair of spaced-apart members affixed to said pivotable member in the container packing attitude;

g. means pivotably attached between the upper ends of said spaced-apart members and said base for rotating said flat pivotable member between said container loading/unloading attitude and said container packing attitude; and

h. a platform and means affixed to said flat pivotable member for supporting said platform when said pivotable member is in said container packing attitude.

4,293,266

ANTI-THEFT SECURITY ENCLOSURE AND RELEASING MECHANISM


David S. St. Lawrence, Dania; Robert Morris, Plantation, and James G. Farrar, Coral Springs, all of Fla., assignors to Sensormatic Electronics Corporation, Deerfield Beach, Fla.

Filed Sep. 8, 1978, Ser. No. 940,595

Int. Cl.³ B65G 65/00

U.S. Cl. 414—411

19 Claims



4,293,265

HYDRAULICALLY OPERATED HOISTING APPARATUS FOR A SHIP FOR PICKING FLOATING OBJECTS UP OUT OF THE SEA

Klaus Lück, Wenningsen, and Fritz-Otto Poeppel, Wunstorf, both of Fed. Rep. of Germany, assignors to Preussag Aktiengesellschaft, Hanover, Fed. Rep. of Germany


Filed Sep. 8, 1978, Ser. No. 940,745

Claims priority, application Fed. Rep. of Germany, Sep. 9, 1977, 2740608

Int. Cl.³ B63B 27/10

U.S. Cl. 414—140

6 Claims



1. In a hydraulically-operated hoisting apparatus on a ship for picking floating objects from the sea, including a lifting arm mounted on the ship and having means articulated at its inner end to pivot about a horizontal axis, the outer end of said arm projecting freely over the side of the ship, gripping means for firmly holding said objects, said gripping means being connected to said outer end of and suspended from said lifting arm and including a member having a first end and a second end, said first end being connected to said object to be picked up and said second end being connected to means for drawing said object into said gripping means, a hydraulic cylinder connected to said lifting arm near said inner end to raise said arm upwardly about said horizontal axis, a body of liquid in a storage container, control means connecting and controlling the flow of said liquid to said hydraulic cylinder, said control means including a valve for controlling liquid flow to the cylinder, and presence sensing means for activating said control means in response to the presence of an object within said gripping means to cause said valve to open, thereby supplying said liquid to the cylinder to raise said lifting arm, the improvement comprising, in combination:

low energy drive power means for pressurizing said body of liquid to drive said hydraulic cylinder rapidly initially and raise said lifting arm quickly thereby hoisting said object suddenly and securely from the surface of the sea at the moment said object is gripped by said gripping means, said low energy drive power means including low energy pump means for compressing air, said body of said liquid being acted upon by said compressed air to provide a source of highly pressurized liquid.

4,293,267

MANUALLY OPERABLE CHAIN DRIVE FOR A BOAT LOADER


Russell E. Grove, 5679 N. Van Ness Blvd., Fresno, Calif. 93711

Filed Mar. 10, 1980, Ser. No. 129,021

Int. Cl.³ B60R 9/04

U.S. Cl. 414—462

2 Claims



1. In combination with a boat handling apparatus particularly suited for use in stowing boats aboard overland vehicles characterized by a first means including a windlass adapted to be mounted atop an overland vehicle and a hoisting line adapted to be connected to the bow of a boat positioned in spaced relation with the vehicle and below the level of the top thereof for pivotally advancing the boat along an arcuate path into a received relationship atop said vehicle, the improvement comprising:

a pair of sprocket wheels;

a rigid bar supported in suspension by said windlass having at each end of its opposite ends one sprocket wheel of said pair supported for rotation, an endless chain arranged in coplanar relation with the pair of sprocket wheels and trained thereabout interconnecting one of the sprocket wheels of the pair in a driving relationship with the other sprocket wheel of said pair, first coupling means for releasably coupling the other sprocket wheel to said windlass in a driving relationship, a crank handle, second coupling means for releasably connecting said crank handle in a driving relationship with said one sprocket wheel, a support member for restraining said bar from pivotal motion relative to the axis of rotation for the windlass comprising a yoke adapted to be mounted on a side surface of the vehicle and supported for pivotal displacement into capturing relation with said rigid bar, and means for securing said yoke in a fixed relationship with said bar.

4,293,268

MATERIAL HANDLING DEVICE


George Mink, 38296 Horseshoe Dr., Mt. Clemens, Mich. 48043

Filed Sep. 21, 1979, Ser. No. 77,678

Int. Cl.³ B65G 47/90

U.S. Cl. 414—591

8 Claims



1. A material handling device for moving a workpiece comprising gripping means for selectively gripping a workpiece to be moved, first supporting means for supporting movement along a first path, second supporting means for supporting said gripping means upon said first supporting means for movement relative thereto along a second path, a cam shaft supported for rotation, a barrel cam affixed for rotation with said cam shaft, a second cam affixed for rotation with said cam shaft, a first follower supported for oscillation about an axis disposed transversely to the axis of said camshaft and continuously engaged with said barrel cam for oscillation about said follower axis upon rotation of said camshaft, a second follower continuously engaged with said second cam and movable upon rotation of said cam shaft, first motion transfer means for transferring oscillation of said first follower about its axis into movement of said gripping means along the first path, and second motion transfer means for transferring movement of said second follower into movement of said gripping means along said second path.

4,293,269

CONVERSION OR EXTENSION BEAM

Grant W. Zook, 436 Smokepipe Rd., Souderton, Pa. 18964

Filed Jul. 30, 1979, Ser. No. 62,167


Int. Cl.³ B66C 23/44

U.S. Cl. 414—686

3 Claims

1. An extension beam for replacement of the scoop bucket of a hydraulic excavator to convert it from a power shovel operation to a power hoist operation, comprising two spaced side plates joined along their lengths by a top plate and a bottom plate which together form an elongated beam which is box-like in cross section, the side plates having aligned sheave bearings at one end for receiving a transverse sheave supporting pin, the other ends of the side plates having aligned pivot bearings for

receiving a transverse pivot pin about which the beam swings up and down, and said side plates having upward extensions above said pivot bearings through the top portions of which are aligned motive bearings for receiving a transverse pin of a driving linkage, said sheave bearings, pivot bearings and mo-



tive bearings being parallel to each other and at right angles to the length of the beam, the upper edges of said upward extensions sloping downwardly and forwardly toward said sheave bearings and having notches therein to form seats to receive a winch.

4,293,270

EXCAVATORS

Derek A. Prime, Burton on Trent, England, assignor to J. C.

Bamford Excavators Limited, Great Britain


Filed Jan. 15, 1979, Ser. No. 3,596

Claims priority, application United Kingdom, Jan. 17, 1978, 1745/78

Int. Cl.³ E02F 3/38

U.S. Cl. 414—690

12 Claims



1. A mechanical excavator comprising a support part and a boom, said boom comprising a base part and a beam part, means pivotally to connect said base part to said support part, means to pivot said base part about a horizontal axis, a dipper arm, means to pivot said dipper arm on said beam part about a second horizontal axis, an excavating tool and means carrying said excavating tool on one end of the dipper arm, bearing means to connect together said base part and said beam part for relative movement in a first direction, said bearing means comprises a pair of parallel channel section guide means, spaced apart transversely of the direction of relative movement between the boom parts, provided on one boom part, opposed flange parts provided on the other boom part and slidably engaged in said guide means to permit relative sliding movement between said parts to vary the distance between said first and second horizontal axes and clamping means comprising at least one wedge member, and means to move said wedge member into wedging engagement with said boom parts in a direction transverse to the direction in which the resultant forces between the wedge member and boom parts act.

4,293,271

DEVICE FOR TRANSLATING A MOVEMENT IN ONE PLANE TO A MOVEMENT IN A PLANE ESSENTIALLY PERPENDICULAR THERETO

Arne I. Rönbeck, Olofström, Sweden, assignor to AB Volvo, Göteborg, Sweden


Filed Oct. 16, 1979, Ser. No. 85,288

Claims priority, application Sweden, Oct. 19, 1978, 7810901

Int. Cl.³ G05G 5/04

U.S. Cl. 414—737

6 Claims



1. Device for translating a movement in one plane to a movement in a plane essentially perpendicular thereto, the device comprising a frame with a reversible drive means for the device, a first member which is movably on the frame, said first member being provided with at least one arm with gripping means, the arm being articulated to the first member, a second movable member which is also articulated to the first member which is also articulated to the first provided with a lock mechanism for the second member, the lock mechanism being arranged to also interact with stops arranged on the frame, the drive means being connected to the second member; a releasable connection between the first member and the second member by means of the lock mechanism; and the connection of the second member to the arms being by means of a connecting means so that, when the first member and the arm have been displaced to an end position, the second member is released from the lock mechanism so that, depending on the setting of the drive means, the movement of the second member continues, so that the arm, via the connecting means, is made to carry out a movement in a plane essentially perpendicular to the plane of movement of the first and the second members.

4,293,272

METHOD AND APPARATUS FOR DENESTING A PLURALITY OF CONTAINERS FILLED WITH ARTICLES


Anke Jellema, Aalten, Netherlands, assignor to Staalkat B.V., Aalten, Netherlands

Filed Nov. 20, 1978, Ser. No. 963,565

Int. Cl.³ B65G 59/04

U.S. Cl. 414—744 B

3 Claims



1. Apparatus for denesting a plurality of stacked containers filled with articles and traveling on a conveyor, said apparatus

comprising at least two denester assemblies for removing containers and articles from the conveyor and for separately discharging the containers and the articles; each denester assembly including a first arm movable upwardly and downwardly relative to a stationary frame and pivotable for swinging movement in a horizontal plane in either direction and fitted with article-gripping means and each denester assembly including a second arm likewise movable up and down and fitted with container-gripping means, said first and second arms being arranged such that during discharge of articles from the top container of a first stack by said article-gripping means on said first arm, said second arm moves toward another stack and such that during discharge of a container from said other stack, said first arm moves toward said first stack; and one of said denester assemblies being arranged to remove containers from the upper half of a stack and the other denester assembly being arranged to remove containers from the lower half of the same stack.

4,293,273

AXIAL-FLOW REVERSIBLE TURBINE

Viktor I. Romanov, Oktyabrsky prospekt, 38, kv. 6; Felix I. Kirzner, prospekt Lenina, 69, kv. 85, and Yakov K. Soroka, ulitsa Dekabristov, 38/2, kv. 4, all of Nikolaev, U.S.S.R.


Continuation of Ser. No. 746,150, Nov. 30, 1976, Pat. No.

4,124,329. This application Nov. 3, 1978, Ser. No. 958,568

Int. Cl.³ F01D 1/30

U.S. Cl. 415—78

3 Claims



1. An axial-flow reversible turbine according to claim 1 having a casing; a nozzle assembly accommodated in said casing provided with two-section blades for controlling the rate of flow of the working medium through said turbine; a wheel rotor with two-section blades for converting the kinetic energy of the flow of the working medium into mechanical work, mounted in the direction of the flow of the working medium after said nozzle assembly, one section of said blades of said nozzle assembly and of said wheel rotor forming the flow duct of the direct-rotating turbine and the other section of said blades of said nozzle assembly and said wheel rotor forming the flow duct of the counter turbine, the inside diameter of said flow duct of counter-rotating turbine being larger than outside diameter of said flow duct of direct rotating turbine, a valve in the form of variable-incidence airfoil vanes intended to deny the access of the working medium into said flow duct of the direct-rotating turbine; located in said casing at the entrance into said flow duct; a cylindrical bushing with ports for intercommunicating said flow ducts, installed in said casing coaxially with said wheel rotor at the entrance of the flow into said flow duct before said nozzle assembly and having an inside diameter which is substantially equal to outside diameter of said flow duct of direct rotating turbine of the entrance into said flow duct; a band which is sufficiently wide for overlapping said ports and arranged along the periphery of said bush-

ing; a device for moving said band radially to at least two fixed positions, said device being installed on the external surface of said casing and connected with said band and comprising: at least one additional single-section stage located in said flow duct of the direct-rotating turbine and installed before said nozzle assembly, the maximum number of said additional stages not exceeding the number of stages obtained from the relation:

$$i_{max} = AN^3 + BN^2 + CN + D$$

where

A = -2000

B = 2000

C = -690

D = 91

$$\overline{N} = \frac{N \text{ counter-rotating turbine}}{N \text{ direct-rotating turbine}}$$

4,293,274


VERTICAL AXIS WIND TURBINE FOR GENERATING USABLE ENERGY

Frederick C. Gilman, 4th and Market, Box 395, Osceola, Mo. 64776

Filed Sep. 24, 1979, Ser. No. 78,643
Int. Cl.³ F03D 7/06

U.S. Cl. 416-51

11 Claims



1. A vertical axis wind turbine for generating usable energy comprising:

- a. driven shaft means,
- b. cylindrical rotor means symmetrically disposed about said driven shaft including paired complementary vanes mounted on said driven shaft and disposed in the closed position to define a right circular cylinder,
- c. support and transmission assembly means connecting said vanes and said driven shaft for self varying, essentially linear sidewise movement of said vanes with respect to each other relative the vertical axis of said driven shaft to vary the surface available for contact by the wind,
- d. said vanes normally disposed in the open position, and
- e. means for controlling the rate of rotation of said vertical axis wind turbine by moving the said vanes to the closed position in a predetermined range of wind velocities,
- f. wherein each of said vanes is longitudinally extended and spiraled in the longitudinal direction through an arc of up to 180° from one end of said vane to the other, and said

vanes are adapted to undergo axial distortion during said sidewise movement.

4,293,275


GAS TURBINE BLADE COOLING STRUCTURE

Nariyoshi Kobayashi, Ibaraki; Takeshi Sakamoto, Tokai; Shunichi Anzai, and Manabu Matsumoto, both of Ibaraki, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Filed Sep. 14, 1979, Ser. No. 75,584
Claims priority, application Japan, Sep. 14, 1978, 53-112242
Int. Cl.³ F01D 5/18

U.S. Cl. 416-97 R

10 Claims



1. A turbine blade comprising: vortex means within the blade for whirling a cooling medium to make a portion of the cooling medium lower in temperature and the other portion of the cooling medium higher in temperature; first passage means communicating with said vortex means for introducing the cooling medium into the blade; second passage means communicating with said vortex means for leading the lower temperature cooling medium to a higher temperature portion of the blade; and third passage means communicating with said vortex means for leading the higher temperature cooling gas to a lower temperature portion of the blade.

4,293,276


LAMINATED COMPOSITE ROTOR YOKE

Vas H. Brogdon, Hurst, and David L. Williams, Smithfield, both of Tex., assignors to Textron Inc., Providence, R.I.

Filed Oct. 27, 1978, Ser. No. 955,332
Int. Cl.³ B64C 27/36

U.S. Cl. 416-134 A

12 Claims



1. A yoke for coupling helicopter blades to a mast, the longitudinal axis of the blades coupled transversely to the longitudinal axis of the mast, comprising: a plurality of first layers formed of continuous filaments defining flat loops, each of said first layers having a width in cross section greater than the depth in cross section, and where the width of each layer lies substantially along the longitudinal axis of the blades and the depth of each layer at the mast lies substantially along the longitudinal axis of the mast; and a plurality of second layers formed of cross-wise filaments interposed between the layers formed by continuous filaments, each of said second layers having a width in cross

section greater than a depth in cross section and where the width of each of the second layers lies substantially along the longitudinal axis of the blades and the depth of each of the second layers at the mast lies substantially along the longitudinal axis of the mast; said layers being substantially parallel and defining a flat, elongated loop with side and outboard end portions.

4,293,277


SUPPLE MOUNTING ARRANGEMENT FOR HELICOPTER ROTOR WITH THROUGH STRIP

Jacques A. Aubry, Cabries, France, assignor to Societe Nationale Ind. Aerospatiale, Paris, France

Filed Jun. 1, 1979, Ser. No. 44,365
Claims priority, application France, Jun. 5, 1978, 78 16730
Int. Cl.³ B64C 27/38

U.S. Cl. 416-134 A

11 Claims



1. A helicopter rotor comprising a driveshaft, a hub secured to the end of said driveshaft comprising a pair of spaced plates arranged parallel to each other and perpendicular to the axis of rotation of said driveshaft, a rotor blade assembly comprising at least one pair of opposed blades formed by a common stringer having a central portion passing between the spaced plates of said hub and oppositely extending spars and a shaped blade shell surrounding each of said spars and connected thereto solely in the area of the outer end thereof and extending inwardly toward the central portion of the stringer progressively evolving in cross-section into a cylindrical sleeve proximate said hub, and means for resiliently mounting said blade assembly to said hub comprising two pair of conically laminated elastic stud means, the stud means of each pair being interposed in opposition to each other on either side of said stringer between said stringer and the corresponding one of the plates of said hub, said pair of stud means being arranged symmetrically with respect to and extending parallel to the axis of rotation of the driveshaft, and a resilient ball joint arranged between the cylindrical sleeve of each of said blade shells and the plates forming said hub.

4,293,278

FLUID-FLOW MACHINE

Herbert Bachl, Munich, Fed. Rep. of Germany, assignor to Getewent Gesellschaft fur technische und Wissenschaftlichs Energieumsatzentwicklungen m.b.H., Kaufbeuren-Neugablonz, Fed. Rep. of Germany

Filed Feb. 21, 1979, Ser. No. 13,537
Claims priority, application Fed. Rep. of Germany, May 16, 1978, 2821233; European Patent Office, Jan. 26, 1979, 79.100227.2


Int. Cl.³ F01D 5/14

U.S. Cl. 416-186 R

8 Claims

1. In a fluid-flow machine having at least one substantially disk-shaped rotor including flow channels for a flow medium, the intake openings of which are disposed in one axial surface

of said rotor while the associated exit openings are disposed in the other axial surface, all intake openings being located at a predetermined distance from the axis of rotation, said distance being different from the distance of the respective exit openings from said axis of rotation, each flow channel having a radially outer and a radially inner deflector elbow, each said elbow having two legs forming an angle of approximately 90 degrees, one leg of the radially outer, or inner, respectively, elbow leading towards the intake opening and extending in the direction of the relative velocity of the intake flow of the flow medium prevailing thereat, and one leg of the radially inner, or outer, respectively, elbow leading towards said exit opening



and extending in the direction of the relative velocity of the exit flow, the other legs of said elbows being directed towards a substantially radial common connecting section connecting the two elbows with one another, the improvement comprising wherein the leg openings through said one axial surface and the leg openings through said other axial surface are directed such that the relative velocities (w) at said one axial surface openings have a tangential component (Wu) of magnitude greater than zero and at the other axial surface openings have a tangential component (Wu) in the same direction as said tangential component (Wu) at said one axial surface openings and of magnitude greater than or equal to zero.

4,293,279


VERTICAL AXIS WIND TURBINE

Victor W. Bolie, 7504 American Heritage, Albuquerque, N. Mex. 87109

Filed Mar. 13, 1980, Ser. No. 129,833
Int. Cl.³ F03D 3/06

U.S. Cl. 416-227 A

30 Claims



1. A vertical axis windmill comprising:

- (a) a tower structure supported on the earth; a vertical shaft supported inside said tower structure from a bearing means at the top of said structure;
- (b) a rotating structure having a central hub, rotating on said bearing means and connected to said shaft, said structure comprising at least two radial arms extending from said hub, the axes of said arms circumferentially equally spaced, in the same horizontal plane;
- (c) an oval ring airfoil system or assembly, attached symmet-

rically to the outer ends of each of said arms, each of said airfoil systems oriented with its major axis in the vertical direction; and wherein

- (d) the inertial center, the aerodynamic center, and the support center are all positioned at the center of rotation of said rotating structure; and in which each of said oval ring airfoil assemblies comprises two identical arched spars, the curvature of said arches designed such that there is no tendency for the curvature to change under a uniformly distributed centrifugal force being applied along the lengths of said spars, said spars are connected together at the top and bottom edges, with their concave surfaces facing each other; the center of the outer surface of one spar attached to the end of one arm.

4,293,280


TRANSCAVITATING PROPELLER

Bohyun Yim, Rockville, Md., assignor to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Aug. 27, 1980, Ser. No. 181,583
Int. Cl.³ B63H 1/18

U.S. Cl. 416—237

13 Claims



1. A propeller blade for attachment to a central propeller hub comprises:

- a radial inner blade portion, wherein said inner blade portion includes a rounded leading edge portion and a tapered trailing edge portion with arcuate pressure and suction surfaces extending therebetween;
- a radial outer blade portion, wherein said outer blade portion includes a tapered leading edge portion and a blunt trailing edge portion with arcuate pressure and suction surfaces extending therebetween; and
- a transition portion blade portion extending between said inner and outer blade portions, wherein said transition blade portion includes a leading edge portion and a trailing edge portion, said transition blade portion generally increases in thickness from said leading edge portion to said trailing edge portion, said leading edge portions of said inner, outer and transition blade portions are substantially colinear with each other, and said trailing edge portions of said inner and outer blade portions are offset from each other.

4,293,281

MOBILE AIR CHARGING SYSTEM

Charles L. Lamoreaux, 28012 Santana Dr., Rancho Palos Verdes, Calif. 90274
Continuation of Ser. No. 29,740, Apr. 13, 1979, abandoned, which is a continuation of Ser. No. 766,081, Feb. 7, 1977, abandoned. This application Mar. 31, 1980, Ser. No. 135,357
Int. Cl.³ F04B 49/10

U.S. Cl. 417—9

11 Claims


1. A compressor system coupled to be driven by a selected one of alternative power sources comprising:
- a compressor;
 - an electric motor having a rotor shaft extending there-through and having coupling means at both ends thereof,

the rotor shaft being coupled via a first one of the coupling means to drive the compressor;

first means for selectively energizing the motor;

an internal combustion engine mounted in driving relationship with the rotor shaft, said engine being selectively operable independently of said rotor shaft;

second means including an electromagnetic clutch for selectively coupling the engine to the rotor shaft via a second one of the coupling means at the end of the rotor shaft



remote from the first coupling means to drive the compressor via said rotor shaft, the clutch being engageable independently of the engine to couple the engine and the rotor shaft together; and

independent manually operable electrical switching means coupled respectively to the first and second means for selectively activating one and only one of the first and second means at a time and for disabling the clutch from engagement at all times except when the engine is to be operated to drive the compressor.

4,293,282


MANURE HANDLING SYSTEM HAVING RECIRCULATING PUMP

Clinton A. Nesselth, and Clifford B. Nesselth, both of Barron, Wis., assignors to Nesselth, Inc., Barron, Wis.

Filed Apr. 27, 1979, Ser. No. 34,169
Int. Cl.³ F04B 39/00

U.S. Cl. 417—53

12 Claims



1. An improved manure handling system of the type having a manure collection hopper; a pump cylinder connected to the collection hopper, the pump cylinder having an interior, a discharge end and a check valve for allowing one way movement of manure from the discharge end of the cylinder into a manure transfer line; and means for pumping the manure contained in the collection hopper into and through the pump cylinder; and wherein the improvement comprises: selectively operable means for simultaneously causing a flow of manure through the interior of the pump cylinder, around the discharge end of the pump cylinder, and back along the exterior of the pump cylinder in a reverse direction, said means being actuable whenever the check valve is jammed in an open

position to allow the reverse manure flow to clear the jammed check valve.

4,293,283

JET WITH VARIABLE THROAT AREAS USING A DEFLECTOR

George K. Roeder, P.O. Box 4335, Odessa, Tex. 79760
Continuation-in-part of Ser. No. 803,977, Jun. 6, 1977, Pat. No. 4,183,722. This application Dec. 3, 1979, Ser. No. 99,841
Int. Cl.³ F04F 5/00

U.S. Cl. 417—172

6 Claims



1. A jet pump for producing a well comprising a main body having an axial bore formed therethrough; a power fluid inlet connected to said axial bore at one end of said main body, a nozzle axially aligned with said main body and having a jet end spaced from an inlet end, a suction annulus formed concentrically about the jet end of said nozzle and within said main body, said inlet end being connected to said power fluid inlet such that power fluid can flow into said inlet end, through the interior of said nozzle, and out of said jet end;

means, including a formation fluid inlet connected to the other end of said main body, which forms a flow passageway extending from the last said inlet into said suction annulus;

a venturi axially aligned with said nozzle and having an inlet end and an outlet end, said inlet end of said venturi being placed adjacent to said jet end of said nozzle, said venturi having sidewalls which describe a frustum of a cone;

a conical deflector having a large diameter end supported by said main body and a free end extending away therefrom and received within the venturi, with the apex of the deflector being positioned adjacent to the throat; with there being an annular passageway formed between the outer surface of the deflector and the inner surface of the venturi; an annular outlet chamber underlying and in communication with said annular passageway;

said annular passageway commences in proximity of the nozzle outlet and extends into communication with said annular outlet chamber; the area of said annular passageway increases in a downstream direction, a marginal length of said deflector extends through said annular outlet chamber;

an outlet port connected to said annular outlet chamber for conducting mixed fluid flow away from the pump and towards the surface of the ground.

4,293,284


POWER LIMITING CONTROL APPARATUS FOR PRESSURE-FLOW COMPENSATED VARIABLE DISPLACEMENT PUMP ASSEMBLIES

Allen J. Carlson, Tecumseh, and Henry A. Vander Kaay, Ann Arbor, both of Mich., assignors to Double A Products Company, Manchester, Mich.

Filed Oct. 9, 1979, Ser. No. 82,975
Int. Cl.³ F04B 49/08

U.S. Cl. 417—218

10 Claims



1. A horsepower limiting control apparatus for a variable displacement pump assembly that has a flow compensator for sensing the load pressure of the fluid and for adjusting the displacement of the pump to whatever is required to maintain a constant pressure differential of the fluid of a selected magnitude across the horsepower limiting control apparatus, characterized in that said horsepower limiting control apparatus, comprises a pressure regulated variable orifice means through the orifice of which said pumped fluid flows to the load, said variable orifice means being responsive to changes in pressure of the pumped fluid from the pump assembly to vary inversely the effective area of the orifice means, said flow compensator functioning to hold the pressure drop across said orifice means constant so that the flow across the orifice means also varies inversely with the pressure of the pumped fluid from the pump assembly thereby to limit to a preselected value the horsepower supplied by the pump assembly to load, and an adjustable pilot means is associated with said variable orifice means for setting selectively a minimum pressure of the fluid required to actuate said variable orifice means for reducing the effective area thereof and thereby to establish the upper limit of the horsepower that can be transmitted to load.

4,293,285

PUMP

John D. Burton, Andover, England, assignor to William R. Selwood Limited, Hampshire, England

Filed Oct. 31, 1979, Ser. No. 90,157

Claims priority, application United Kingdom, Oct. 31, 1978, 42685/78


Int. Cl.³ F04F 7/02

U.S. Cl. 417—240

4 Claims

1. In or for a pump comprising a duct having an inlet at a lower position and an outlet at a higher position, an inlet valve at the inlet, which valve opens when the pressure in the duct adjacent to the inlet is below the pressure outside the duct adjacent to the inlet, storage means for storing potential energy which can be applied to liquid in the duct as kinetic energy and pressurising means for causing cyclic changes in pressure in a liquid in the duct, improved pressurising means comprising a pumping chamber defined, at least in part, by a lateral wall, an annulus of elastomeric material having its outer periphery in non-sliding contact with the lateral wall and a centre portion in non-sliding contact with the inner periphery of the annulus, wherein the lateral wall and the centre portion are formed of

relatively rigid material and are reciprocable relative to each other to vary the volume of the pumping chamber, wherein the annulus is stressed in compression between the lateral wall and the centre portion, wherein an outlet valve is provided for controlling the flow of liquid through the outlet which outlet valve is a non-return valve adapted to open only when the pressure in the pumping chamber exceeds the pressure in the outlet at the downstream side of the outlet valve and wherein there is provided in the centre portion an aperture through which liquid can leave the pumping chamber when the outlet



valve is open, and the outlet valve is operatively associated with the centre portion for controlling the flow of liquid through the aperture therein, the pressuring means further comprising closing means for maintaining the outlet valve closed while the pressure in the pumping chamber is increasing, wherein said closing means is connected with the centre portion for limited movement relative thereto and is adapted for transmitting to the centre portion driving forces which cause relative reciprocation of the centre portion and the lateral wall.

4,293,286

DOUBLE ACTION PUMP


Joel W. Hawkins, Rte. 2, Marietta, S.C. 29661

Filed Jan. 22, 1979, Ser. No. 5,224

Int. Cl.³ F04B 3/00

U.S. Cl. 417-253

3 Claims



1. A pump having a housing carrying a cylinder with a manually operable piston having a large diameter and a small diameter delivering a large volume of fluid flow at low pressure when operated in one direction and a lesser volume of

fluid flow at high pressure when operated in the other direction comprising:

- an inlet duct in said housing opposite said large piston diameter;
- a first check valve in said housing checking the flow of fluid outwardly through said inlet duct;
- a second check valve in said housing allowing for the flow of low-pressure fluid through said inlet duct for delivery through said delivery duct while checking flow of high-pressure fluid therethrough during high-pressure fluid delivery;
- a delivery duct in said housing communicating with said inlet duct;
- a third check valve in said delivery duct to check the flow of fluid from said delivery duct into the inlet duct; and
- a fluid pressure actuated plunger means operated responsive to the fluid pressure in the delivery duct to open said first check valve and render same ineffective.

4,293,287

REVERSING VALVE ASSEMBLY FOR A FLUID OPERATED WELL PUMP

Donald E. Carrens, Tulsa, Okla., assignor to Dresser Industries, Inc., Dallas, Tex.

Filed Mar. 21, 1979, Ser. No. 22,590

Int. Cl.³ F04B 47/08; F01L 25/06

U.S. Cl. 417-393

26 Claims



8. A pump control means for a hydraulically powered down-hole oil well pump having upper and lower piston means connected by a pump rod, a well fluid inlet, a power fluid inlet and a pumped fluid outlet, said pump control means comprising:

- (a) a valve means to receive power fluid and to alternately direct it to said upper and said lower piston means in conjunction with alternately directing spent power fluid from said upper and lower piston means to said outlet and directing pumped well fluid to said outlet in order to cause reciprocating motion of said piston means and pumping of well fluid;
- (b) power fluid throttling means having means with said valve means to regulate fluid flow in the flow path of the power fluid in order to operably regulate the velocity of said piston means; and
- (c) means to control said power fluid throttling means having pressure-sensing means connected to both said upper and lower piston means simultaneously to sense the pressures of said power fluid and said spent power fluid as applied to said upper and lower piston means for both directions of travel of said piston means and to accordingly actuate said power fluid throttling means to in turn

control the velocity of said piston means and thereby preventing operation induced excessive shock stresses in said oil well pump which could be damaging to the structure thereof.

4,293,288

SUBMERSIBLE PUMP HOUSING


Walter L. Weber, St. Louis County, Mo., assignor to Weber Industries, Inc., St. Louis, Mo.

Filed Feb. 5, 1979, Ser. No. 9,245

Int. Cl.³ F04B 21/00, 39/00

U.S. Cl. 417-434

5 Claims



1. For use with a submersible pump having a pump assembly, means defining a tubular housing integrally fabricated of a single material of construction, there being a motor mounting bracket plate fixedly provided at the normally lower end of said housing, and pump assembly support means provided internally of said housing upwardly of said bracket plate formed unitarily with said housing for supporting said pump assembly and comprising a plurality of discrete finger-like projections constituted by portions of said housing turned inwardly from conformity with the wall thereof, each providing an upper edge constituting a shoulder for supported disposition thereon of the pump assembly, each of said finger-like projections being bent inwardly along a lower circumferential line and with the resultant opening constituting a liquid outlet port for liquid escaping downwardly along the housing between same and the pump assembly.

4,293,289

LUBRICATING MEANS FOR ROTARY PISTON ENGINES WITH PRESSURE AND TEMPERATURE RESPONSIVE VALVE MEANS IN THE ECCENTRIC SHAFT

Yasuyuki Morita, Hiroshima, Japan, assignor to Toyo Kogyo Co., Ltd., Hiroshima, Japan

Filed Jun. 5, 1979, Ser. No. 45,693

Claims priority, application Japan, Jun. 7, 1978, 53-69186


Int. Cl.³ F01C 21/04, 21/06; F16K 17/04, 17/38

U.S. Cl. 418-84

5 Claims

1. Rotary piston engine comprising a casing which includes a rotor housing having an inner wall of trochoidal configuration and a pair of side housings secured to the opposite sides of the rotor housing to define a rotor cavity of a trochoidal configuration, and a substantially polygonal rotor disposed in said rotor cavity and carried by an eccentric shaft for rotation with apex portions in sliding contact with the inner wall of the rotor housing, a lubricating system including oil passage means extending substantially axially in said eccentric shaft, oil pump means for supplying lubricant oil under pressure to said oil

passage means, and pressure regulating valve means provided in said oil passage means in the eccentric shaft means for determining oil pressure in the oil passage means, said rotor having interior cooling cavity means, oil supply passage means branched from said oil passage means in said eccentric shaft for supplying rotor cooling oil to said cooling cavity means, said



pressure regulating valve means including temperature responsive means provided in said eccentric shaft for controlling the oil pressure in accordance with a surrounding temperature so that the oil pressure in said eccentric shaft is decreased in response to a decrease in said surrounding temperature to thereby decrease the rotor cooling oil supplied to said cooling cavity.

4,293,290

POSITIVE DISPLACEMENT ROTARY PUMP WITH BEARINGS IN COUNTERSUNK PORTIONS OF THE ROTORS


Victor E. Swanson, Fort Atkinson, Wis., assignor to Crepac, Inc., Lake Mills, Wis.

Filed May 4, 1979, Ser. No. 36,030

Int. Cl.³ F04C 2/18, 15/00

U.S. Cl. 418-94

1 Claim



1. A positive displacement rotary pump for circulating a viscous product, comprising a housing having an interior cavity through which the product is pumped, one wall of said cavity being defined by a removable cover; a pair of spaced substantially parallel shafts extending into said cavity, each shaft having one end thereof supported by said cover and a second end extending through a wall of said cavity opposite said cover; first means for driving and supporting the second ends of said shafts; meshing rotors mounted on said shafts, each rotor having internal means in driving engagement with said

shaft on which the rotor is mounted, said internal means being located between planes defined by opposing walls forming the cavity, said rotors being disposed entirely within said cavity, the endface of each rotor adjacent said shaft one end having a substantial countersunk portion with a terminus adjacent said rotor internal means; bearing means substantially isolated from the product and disposed entirely within the countersunk portion of said rotor and supportingly engaging segments of said shaft one end, said bearing means having at least a portion thereof disposed adjacent the rotor internal means; and second means fixedly carried by said cover and extending into said countersunk portion and supporting said bearing means; each shaft being provided with an exterior shoulder adjacent the cavity-forming surface of the wall opposite said cover and against which one endface of a rotor engages and adjustable means carried on said shaft and spaced from said shoulder for engaging said rotor whereby the shoulder and adjustable means coact to restrain relative movement of said rotor on said shaft; said adjustable means including an elongated liner disposed within the countersunk portion and encompassing a segment of the shaft, one end of the liner abutting the terminus of the rotor countersunk portion, and a longitudinally adjustable element removably mounted on the shaft one end and engaging an opposite end of said liner and retaining the latter in abutting relation with said rotor terminus.

4,293,291

GEAR PUMP WITH IMPROVED SHAFT SEAL

John R. Link, Portage, Mich., assignor to General Signal Corporation, Stamford, Conn.


Continuation of Ser. No. 861,745, Dec. 19, 1977, abandoned.

This application Aug. 1, 1979, Ser. No. 62,837

Int. Cl.³ F04C 2/18, 15/00; F16J 15/46; F16C 33/74

U.S. Cl. 418-104

5 Claims



1. A gear pump for pumping hydraulic fluid under high pressure, comprising a housing, a pair of gears mounted for rotation within said housing, a drive shaft affixed to one of said gears for transmitting a rotational input force to said one gear, said drive shaft including a portion extending outwardly beyond said housing, and a bushing surrounding said drive shaft and secured to said housing so that said drive shaft is free to rotate within said bushing, said bushing being positioned along said drive shaft between said one gear and the portion of said drive shaft that extends beyond said housing, said bushing including an end surface facing said one gear, an annular recess in said end surface adjacent to said drive shaft for supporting and retaining a dynamic sealing member, and a unitary dynamic sealing member formed of resilient material positioned within said annular recess, and exposed to said high pressure hydraulic fluid which forces said dynamic sealing member into said annular recess thereby aiding in the creation of a dynamic seal between the drive shaft and the dynamic sealing member for minimizing the amount of leakage of said pumped high pressure fluid along said drive shaft.


4,293,292
CANDY FLOSS MACHINE
Benjamin Israel, Bensalem Township, Bucks County, Pa., assignor to North Eastern Timber (U.S.A.) Incorporated, Camden, N.J.

Filed Nov. 19, 1979, Ser. No. 95,831

Int. Cl.³ A23G 3/20

U.S. Cl. 425-9

15 Claims



1. In a candy floss machine for dispensing candy floss on a stick including a rotary head for producing the floss, and means for automatically dispensing stored sticks at least one stick at a time to a location spaced from the rotary head at which the floss is collected, the combination comprising: an annular storage facility in which one or more of said sticks may be stored, said storage facility having an opening at a preselected location through which a stick may be ejected, means for urging said one or more sticks towards said preselected location in said storage facility to cause said one or more sticks to enter into alignment with said opening at said preselected location, means for retaining said stick in alignment with said opening at said preselected location in said storage facility in preparation for dispensing the stick.

4,293,293

TIRE RETREADING BLADDER

Kenneth T. MacMillan, Macon, Ga., assignor to Donald MacMillan & Son, Inc., Macon, Ga.

Continuation-in-part of Ser. No. 35,207, May 2, 1979, Pat. No. 4,197,064, which is a division of Ser. No. 919,475, Jun. 27, 1978, Pat. No. 4,172,868, which is a division of Ser. No. 628,902, Nov. 5, 1975, Pat. No. 4,035,118, which is a division of Ser. No. 391,816, Aug. 27, 1973, Pat. No. 3,997,284. This application Sep. 15, 1980, Ser. No. 187,339


Int. Cl.³ B29H 5/04, 5/02

U.S. Cl. 425-23

10 Claims

1. A tire retreading bladder comprising a generally annular member of a U-shaped cross-section defined by a bight portion and a pair of legs, said annular member defining an interior volume, each leg terminating in a terminal edge of a generally circular configuration, each leg having interior and exterior surfaces, means disposed along each of said exterior surfaces for venting air from between such exterior surfaces and an interior surface of an associated tire adapted to receive there-within said bladder, each of said venting means on each of said exterior surfaces having a radially inboard portion terminating radially short of the associated terminal edge, each exterior surface defining between said radially inboard portions of each venting means and the associated terminal edge a generally smooth uninterrupted annular sealing surface, said venting

means being in the form of a plurality of pairs of closely adjacent ribs with each pair of ribs setting off a venting groove means for separating the collected attenuated material from at least the fixed support of said collecting means.



4,293,294

CIRCULAR EXTRUSION APPARATUS PROVIDING FOR ROTATION AROUND THE EXTRUSION OPENING

Ole-Bendt Rasmussen, 7, Topstykke, 3460 Birkerød, Denmark
Division of Ser. No. 841,481, Oct. 12, 1977, abandoned, which is a continuation of Ser. No. 657,649, Feb. 12, 1976, abandoned.


This application Oct. 10, 1979, Ser. No. 83,277

Claims priority, application United Kingdom, Feb. 12, 1975, 5971/75

Int. Cl.³ B29F 3/10; B29D 23/04

U.S. Cl. 425-112

16 Claims



1. An apparatus for extruding an extrudable polymeric material in generally annular continuous or discontinuous form which apparatus comprises (a) a rotatable hollow centered extrusion die; (b) means for supplying a flow of extrudable polymeric material to said die, said die having a feed passage therein for receiving at one of its ends said polymeric material flow from said supplying means and a generally annular exit orifice at the other end of said passage for discharging said polymeric material in continuous or discontinuous generally annular extending form; (c) means for rotating at least said die exit orifice bodily about its axis; and (d) collecting means defining a zone of collection extending through the hollow center of said die for receiving thereon the polymeric material emerging from said die orifice, said collecting means comprising a fixed support and a collecting surface having at least in said collecting zone a generally cylindrical configuration and upon which said discharged material is received as a generally tubular layer form, said collecting surface being adapted to be advanced continuously in said zone in a direction generally axially of said die; (e) means for advancing at least said collecting surface generally axially of said die while said die exit orifice is rotated at a sufficient rate relative to the rate of advance of the collecting surface to subject the polymeric material emerging from said die orifice to significant attenuation in a helical direction and impart to said generally tubular layer a helical grain relative to the direction of advance; and (f)

1011 O.G.—8

4,293,295

PELLETING PRESS

Franciscus van Deuren, Bortel, Netherlands, assignor to Simon-Heesen B.V., Bortel, Netherlands


Division of Ser. No. 901,825, May 1, 1978, abandoned. This application Nov. 28, 1979, Ser. No. 98,361

Claims priority, application Netherlands, May 11, 1977, 7705231

Int. Cl.³ B28B 3/20

U.S. Cl. 425-331

9 Claims



1. A pelletizing press comprising a rotatably mounted annular die having material extrusion bores therethrough, at least one freely rotatable pelletizing roller mounted on a fixed axis and disposed in operative association with the inner periphery of said annular die whereby to extrude material through the rotating die, and means for rotating said annular die including at least two motors each drive connected separately to a common endless flexible driving member also drive connected to said die.

4,293,296

APPARATUS AND METHODS FOR MAKING CHEESE TOPPING, AND CHEESE MOLD ASSEMBLIES


Joseph A. Caiello, 21 W. Las Flores, Arcadia, Calif. 91006, and Ronald J. Caiello, Arcadia, Calif., assignors to Joseph A. Caiello, Arcadia, Calif.

Continuation-in-part of Ser. No. 847,361, Oct. 31, 1977, abandoned. This application Oct. 13, 1978, Ser. No. 951,213

Int. Cl.³ B29F 1/06

U.S. Cl. 425-547

6 Claims



1. In apparatus for making a piece of cheese having parallel elongate holes from a solidifiable fluid mass of cheese, the improvement comprising in combination: a sleeve extending between an open bottom and an open top; means for closing said bottom including a table for supporting said sleeve at said bottom and for jointly providing with said sleeve a cavity for receiving said solidifiable fluid mass of cheese, said table having an opening communicating with said cavity; a lid covering the top of said sleeve; a number of mutually spaced, parallel rods mounted on said lid and extending from said top to said bottom through said sleeve for providing said elongate holes;

means releasably coupled to said lid for applying said sleeve to said table; and
means connected to said table for extruding said fluid mass of cheese through said opening into said cavity and in-between said spaced rods.

4,293,297

GAS BURNER, IN PARTICULAR FOR LIQUID GASES

Aldo Polidoro, Vicolo del Convento, Schio (Vicenza), Italy

Filed Jul. 19, 1979, Ser. No. 58,803

Claims priority, application Italy, Jul. 28, 1978, 85589 A/78; Nov. 6, 1978, 85622 A/78

Int. Cl.³ F23D 13/36

U.S. Cl. 431-286

4 Claims



1. A burner for gas particularly suitable for liquified gas comprising an extended cylindrical tube body, means for supplying the interior of said body through one end thereof with a suitable combustible mixture of gas fuel and primary air, means closing the opposite end of said body, and means forming a plurality of spaced flame fronts in a row along the length and outer surface of said body when the burner is in use, the latter said means consisting along the length of said body of a series of aligned groups of parallel slits penetrating said body to permit flow therethrough of the burning combustible mixture of primary air and gas, all of said slits extending transverse to the length of said cylindrical body, said groups of slits being arranged at a distance apart of 1.4-1.2 mm, each of said slits having a width of 0.5-0.7 mm, said slits being further arranged in sub-groups along an axis transverse to the length of said body and also parallel to each other and being all aligned among themselves, each group being separated from the adjacent groups so as to establish a series of separate flame fronts being fan-shaped to present a unified flame front whereby a substantial reduction in the vibrations produced during the combustion is achieved and substantial stabilization of the flame and improvement in the efficiency of the burner result.

4,293,298

COMBINED AIR AND FUEL NOZZLE FOR FLUIDIZED BED COMBUSTION CHAMBER

Jörgen Bergkvist, Finnspong, Sweden, assignor to Stal-Laval Turbin AB, Sweden

Filed Dec. 4, 1979, Ser. No. 100,090

Claims priority, application Sweden, Dec. 5, 1978, 7812481

Int. Cl.³ F27B 15/14

U.S. Cl. 432-58


6 Claims

1. An improved fuel and air nozzle for a fluidized bed combustion chamber of the type having an air chamber at its lower end, comprising:

a nozzle unit fixed to extend upwardly from the air chamber into the fluidized bed, said nozzle unit being closed at its upper end and having openings through its side wall at two different levels within said fluidized bed;

a cylinder unit passing through said air chamber and extending upwardly into said nozzle unit, said cylinder unit having openings at three different levels to permit airflow

from the air chamber into said cylinder unit and from said cylinder unit through said openings in said nozzle unit; and
a fuel conduit passing through said cylinder unit; and



means for removably sealing said cylinder unit to the bottom of the air chamber.

4,293,299

LOAD SUPPORT DEVICE FOR HEAT FURNACES


Robert N. Gaddes, 3222 Stuart La., Dearborn, Mich. 48120

Filed Apr. 4, 1980, Ser. No. 137,117

Int. Cl.³ F27D 3/02

U.S. Cl. 432-234

2 Claims



1. A load support device for heat furnaces having a plurality of pipe beams through which coolant is circulated, such support device comprising a saddle member mountable on the pipe beams and having therethrough a central opening, a replaceable core in the central opening of the saddle member, an upwardly disposed annular seat in the central opening through the saddle member, a lateral shoulder on the replaceable core supported on the upwardly disposed annular seat, an inwardly and downwardly disposed bevel around the lower end of the saddle member to receive a weld for mounting such member on a pipe beam in said heat furnace, an upwardly disposed bevel around the upper end of the central opening to receive a weld for detachably and sealably joining the replaceable core to the saddle member, an upwardly disposed flared section in the central opening through the saddle member below the annular seat therein, a tapered segment on the replaceable core in seating engagement with such flared section, an upwardly disposed flared section in the central opening through the saddle member above the annular seat therein, a tapered segment on the replaceable core in seating engagement with such flared section, a head on the upper end of the replaceable core for directly supporting load, and a projection on the lower end of the replaceable core extending below the saddle member so as to extend into a pipe beam in said heat furnace when the saddle member is thereon mounted.

4,293,300

LIQUID SEPARATING AND EVACUATING DEVICE FOR FLUID SUCTION EQUIPMENT

Augusto Cattani, Parma, Italy, assignor to Officine Augusto Cattani & C. S.A.S., Parma, Italy


Filed Dec. 31, 1979, Ser. No. 109,200

Claims priority, application Italy, Jan. 15, 1979, 4005 A/79

Int. Cl.³ A61C 17/04

U.S. Cl. 433-92

3 Claims



1. A liquid separating and evacuating device for dental surgery fluid suction equipment comprising a first chamber connected to a vacuum source, a fluid inlet pipe connected to the first chamber for directing fluid into the first chamber which is kept at sub-atmospheric pressure during the operation of the device, a second chamber positioned beneath said first chamber, automatic means responsive to the level of liquid present in the first chamber for causing the second chamber to be vented to atmosphere so as to be at a pressure approximately identical to that of the atmosphere in response to the level of the liquid in the first chamber being lower than a pre-set value and for causing the second chamber to communicate with the first chamber so as to be at sub-atmospheric pressure approximately identical to that of the first chamber in response to the level of liquid in the first chamber being above said pre-set value, first valve means for preventing liquid from passing from the first chamber to the second chamber in response to the second chamber being at a higher pressure than the first chamber and for permitting liquid flow from the first chamber to the second chamber when the pressure in the first chamber is approximately the same as pressure in the second chamber and second valve means for allowing liquid to be discharged from the second chamber to the outside in response to pressure inside the second chamber being approximately equal to atmospheric pressure and for precluding such discharge when pressure in the second chamber is less than atmospheric pressure, wherein said automatic means includes a pneumatic distributor and a pneumatic valve including a diaphragm actuated by the said pneumatic distributor, said diaphragm being movable between a first position in which said second chamber is placed in communication with the first chamber and a second position in which said second chamber is placed in communication with the outside, a float contained in said first chamber, a rigid vertical rod having upper and lower ends and connected on its lower end to said float for vertical movement therewith and a movable valve spool connected to the upper end of said rod for movement in said pneumatic distributor in accordance with the liquid level in said first chamber.

4,293,301

DENTAL ABSORPTIVE PADS AND DISPENSING MEANS THEREFOR

Bengt Mattsson, Hässjövägen 4, Upsala, Sweden


Filed Jun. 18, 1979, Ser. No. 49,746

Claims priority, application Sweden, Jun. 22, 1978, 7807145

Int. Cl.³ A61C 5/14

U.S. Cl. 433-136

11 Claims



1. A supply tape of dental absorptive pads comprising a series of said absorptive pads connected together end to end by score lines and in a detachable manner, each said pad having an inside face and an outside face, the inside face comprising a layer formed of an absorbent material and the outside face being formed of a layer of non-absorbent material, said inside layer formed of absorbent material constituting means to place against the parotid of a patient to lower the mean rate of discharge of saliva from the parotid and to absorb saliva therefrom;

each said pad having a fore end and a rear end, said fore end having two peripheral rounded points or corners separated by a central recess, said rear end having a central rounded point or corner generally complementary to and configurative with said fore end, whereby the central point of each pad is inserted into and separately attached to the central recess of a next adjacent pad.

4,293,302

TOOTH IMPLANTS


Craig R. Hassler, Columbus, Ohio, and Gary L. Messing, State College, Pa., assignors to Scientific Advances, Inc., Columbus, Ohio

Filed Mar. 26, 1980, Ser. No. 134,082

Int. Cl.³ A61C 7/00

U.S. Cl. 433-173

32 Claims



1. A dental, prosthetic, endosteal implant comprising:
a base comprised of a bio-compatible material, said base having first and second ends axially spaced along the longitudinal axis of said base and sidewalls which include serrations comprising alternating oblique and substantially planar surfaces, said substantially planar surfaces being substantially perpendicular to both the longitudinal axis of said base and the direction of the intended occlusal load and said oblique surfaces being disposed at an angle to the longitudinal axis of said base, the surface area of said planar surfaces nearest said second end being greater than the surface area of said planar surfaces nearest said first end, said first end being the outermost end upon implantation and said second end being the implanted end; and

a core extending from the first end of said base and configured to permit cooperative engagement with at least one prosthetic crown.

4,293,303

JOINT FOR CONNECTING A PARTIAL DENTAL PROSTHESIS TO THE REMAINING NATURAL HUMAN TEETH


Hans Dalla Bona, Rousseauweg 9, 2563 Ipsach, Switzerland
Filed Apr. 29, 1980, Ser. No. 145,193

Claims priority, application Switzerland, Jun. 12, 1979, 5466/79

Int. Cl.³ A61C 13/22

U.S. Cl. 433-177

6 Claims



1. A joint for connecting a partial dental prosthesis with remaining natural teeth, having joint members connectable to an anchor tooth and with a part of the dental prosthesis and adapted to be telescoped in each other without clearance and capable of carrying out relative movements in one plane only, and a spring located between the two joint members and adapted to act therebetween in order with the unstressed partial dental prosthesis to relieve its support, the improvement wherein said joint comprises a stop on at least one of the joint members to limit the relative movement of the joint members in the direction of the spring force.

4,293,304 FLEXIBLY MOUNTED DRIVE ARRANGEMENT FOR SHIPS

Anders Sandström, Nynäshamn, Sweden, and Erich Aucktor, Offenbach, Fed. Rep. of Germany, assignors to Scatra Ab, Nynäshamn, Sweden


Filed Oct. 24, 1978, Ser. No. 954,117

Claims priority, application Fed. Rep. of Germany, Oct. 28, 1977, 2748359

Int. Cl.³ B63H 1/14, 5/06

U.S. Cl. 440-83

6 Claims



1. Drive arrangement for a ship comprising a drive unit, said drive unit including a drive motor, and at least a first drive shaft, a propeller shaft for driving a ship's propeller, said first drive shaft arranged to receive rotational driving force from said drive motor and connected to said propeller shaft for transmitting torque thereto for driving the propeller, wherein the improvement comprises means for individually flexibly mounting said drive motor within the ship, means for connecting said drive unit to said first drive shaft and said first drive shaft to said propeller shaft for providing uniform running operation and for permitting said drive motor of said unit and said propeller shaft to be positioned out of axial alignment, said first drive shaft comprises a rigid shaft, said connecting means comprises a constant velocity universal joint at each end of said rigid shaft with one said universal joint connecting said rigid shaft to said drive unit and the other said universal joint connecting said rigid shaft to said propeller shaft, with each of said universal joints being capable of absorbing angular movement and at least one of said universal joints being cable of absorbing relative axial movement therein.

CHEMICAL

4,293,305

DIESTER COMPOSITION AND TEXTILE PROCESSING COMPOSITIONS THEREFROM

Robert B. Wilson, Greenville, S.C., assignor to Northwestern Laboratories, Inc., Greenville, S.C.

Continuation-in-part of Ser. No. 90,092, Nov. 1, 1979. This application Nov. 3, 1980, Ser. No. 203,636

Int. Cl.³ D06M 1/00


U.S. Cl. 8-115.6

5 Claims



CONVENTIONAL SPIN FINISH (200X)

1. A method for lowering heat history characteristics and the degree of crystallinity of a synthetic fiber, lowering the temperature at which the fiber can be texturized and lowering the temperature at which the fiber absorbs dye comprising applying to the fiber to a pick-up of 0.4-0.75% by weight of a composition comprising a cycloaliphatic diester of the formula



wherein R is straight or branched chain alkyl of 4-20 carbon atoms, polyoxyalkylene of the formula $\text{HO}(\text{CH}_2\text{C}(\text{H}_2)\text{O})_n\text{CH}_2\text{CH}_2-$, $\text{HO}(\text{C}_3\text{H}_6\text{O})_n\text{C}_6\text{H}_5-$, $\text{HO}(\text{CH}_2\text{C}(\text{H}_2)\text{O})_p(\text{CH}_3\text{H}_6\text{O})_q\text{C}_3\text{H}_6-$ or $\text{HO}(\text{C}_3\text{H}_6\text{O})_p(\text{C}_2\text{H}_4\text{O})_q\text{C}_2\text{H}_4$ or phosphated polyoxyalkylene, wherein n is 2-22 and the sum of p+q is n; and a high boiling aromatic ester of the formula $\text{ArCOO-R}_1\text{-OOC-Ar}$ or ArCOOR_2 , wherein Ar is a substituted or unsubstituted monocyclic aryl of; R_1 is alkylene of 2-8 carbon atoms or polyoxyalkylene of the formula $-\text{C}_r\text{H}_2(\text{O}-\text{C}_s\text{H}_2)_s-$ in which r is 2 or 3 and s is up to 15; and R_2 is alkyl or alkenyl of 8-30 carbon atoms;

wherein the ratio of cycloaliphatic diester to high boiling aromatic ester is 0.1:1 to 2:1 and wherein the combination of cycloaliphatic diester and high boiling aromatic ester constitutes 10-90% by weight of the composition and texturing the thus-coated fiber at 180°-230° C.

4,293,306

PROCESS FOR THE DYEING AND PRINTING OF HYDROPHOBIC SYNTHETIC ORGANIC FIBER MATERIALS WITH WATER-INSOLUBLE AZO DYE STUFFS

Ernst Hoyer, Frankfurt am Main, Fed. Rep. of Germany; Willi Steckelberg, Coventry, R.I.; Walter Deucker, Bad Soden am Taunus, and Rudolf Schickfluss, Kelkheim, both of Fed. Rep. of Germany, assignors to Hoechst Aktiengesellschaft, Frankfurt am Main, Fed. Rep. of Germany

Filed Feb. 6, 1980, Ser. No. 118,902


Claims priority, application Fed. Rep. of Germany, Feb. 8, 1979, 2904752

Int. Cl.³ C09B 29/36


U.S. Cl. 8-471

1 Claim


1. A process for the dyeing or printing of a hydrophobic organic fibrous material containing or consisting of a polyester, which comprises dyeing said fibrous material from an aqueous dispersion with a dyestuff of the formula




in which X is alkyl of from 1 to 4 carbon atoms, phenyl, lower alkyl-phenyl, lower alkoxy-phenyl, nitrophenyl, chlorophenyl or bromophenyl, and D is phenyl, lower alkyl-phenyl, lower alkoxy-phenyl, nitro-phenyl, chlorophenyl, benzoyl-phenyl, phenyl-phenyl, phenoxy-phenyl, lower alkylsulfonyl-phenyl, aminocarbonyl-phenyl, aminosulfonyl-phenyl,



chloro-nitro-phenyl, lower alkyl-nitro-phenyl, lower alkoxy-nitro-phenyl, di(cyano)-phenyl, trifluoromethyl-nitro-phenyl or hydroxyalkoxy-nitro-phenyl at a pH value of from 2 to 9 and at a temperature above 100° C. under pressure, or at about 100° C. in the presence of a carrier, or by impregnating said fibrous material with an aqueous dispersion of a dyestuff of said formula



said dispersion having a pH-value of from 2 to 9, and subsequently exposing the impregnated fibrous material to a short heat treatment between about 180° and 210° C., or which comprises, in accordance with the transfer printing method, printing an inert carrier material consisting of paper, a foil of a heat resistant resin or aluminum with a printing ink containing as essential ingredients water or an organic solvent, a common binding agent and a dyestuff of said formula



in a finely divided state, bringing the printed side of the carrier material in close contact with the fibrous material, exposing said materials to a short heat treatment between 170° and 210° C. while still in contact and separating the fibrous material from the carrier material.

4,293,307

METHOD AND APPARATUS FOR ANALYZING LIQUID

Roger J. Simpson, Sevenoaks; Janet A. Gawthorpe, Orpington, and C. Alexander Lawrence, London, all of England, assignors to Saint Peter's Research Trust Limited, England

Filed Mar. 15, 1979, Ser. No. 20,777

Claims priority, application United Kingdom, Apr. 5, 1978, 13293/78


Int. Cl.³ G01N 27/40, 33/48

U.S. Cl. 23-230 B

14 Claims

12. A method for continuously analyzing blood comprising, continuously supplying blood, continuously separating from the blood by means of a semi-permeable membrane at least part of the ions to be analyzed with some water,

continuously analyzing the water and ions by means of at least one ion selective electrode and reference electrode



and continuously measuring the potentials of the electrodes for determining the concentrations of the ions.

4,293,308

METHOD AND APPARATUS FOR THE ANALYSIS OF SULPHUR CONTENTS IN SAMPLES


Giorgio Sisti, Melzo, and Bruno Colombo, Cologno Monzese, both of Italy, assignors to Carlo Erba Strumentazione S.p.A., Milan, Italy

Filed Oct. 5, 1979, Ser. No. 82,251

Claims priority, application Italy, Oct. 13, 1978, 28744 A/78
Int. Cl.³ G01N 31/08, 21/72, 25/24

U.S. Cl. 23—230 PC

10 Claims



1. A method for determining the sulphur content of a sample comprising combusting the sample in a helium current temporarily enriched with oxygen, catalytically oxidizing and reducing the resultant combustion gases inside the same reactor thereby forming a N_2 , CO_2 , H_2O and SO_2 gas mixture, separating the components of the mixture by gas chromatography, removing water from the gases emanating from the gas chromatographic separation step and passing the resulting water-free gases into a flame photometric detection system for selective detection of sulphur, whereby a single sulphur peak is formed.

4,293,309

METHOD OF OBTAINING AND RECORDING SEISMIC AND GEOCHEMICAL DATA

Sylvester T. Miller, Midland, Tex., assignor to STM Corporation, Midland, Tex.

Filed Feb. 27, 1980, Ser. No. 125,178


Int. Cl.³ G01N 33/24

U.S. Cl. 23—230 EP

11 Claims

1. A method for locating hydrocarbon deposits beneath the ground comprising the steps of:

drilling a plurality of boreholes in a test area to a predetermined depth;
collecting samples from selected ones of each of said plurality of boreholes at said predetermined depth;
generating a pressure pulse within each of said plurality of boreholes at said predetermined depth at discrete time intervals to thereby generate pressure waves through the ground at the surface of said plurality of boreholes to determine geological structure at said plurality of boreholes;



analyzing said samples from selected ones of each of said plurality of boreholes for constituents indicating the presence of hydrocarbon deposits; and
processing said pressure waves at selected ones of said plurality of boreholes and said analyses of constituents in said samples from corresponding ones of said plurality of boreholes to determine the presence and location of hydrocarbon deposits within the test area.

4,293,310

PHOTOELECTROCHEMICAL IMMUNOASSAY


Stephen G. Weber, Pittsburgh, Pa., assignor to University of Pittsburgh, Pittsburgh, Pa.

Filed Mar. 14, 1980, Ser. No. 130,555

Int. Cl.³ G01N 33/54, 27/00, 27/52

U.S. Cl. 23—230 B

20 Claims



1. Immunoassay apparatus comprising:
(i) a catalytic photoelectrochemical label capable of photoexcitation such that a photocurrent is generated at an electrode of appropriate potential;
(ii) a quencher; and
(iii) an electrochemical flow cell having,
at least one wall transparent to light of a spectrum which will excite said photoelectrochemically active label, and
(iv) light means which further comprise,
a light source having a spectrum capable of exciting said photoelectrochemically active label, and means for isolating said spectrum, wherein the relative planes of orientation of the electrodes of said cell, and said spectrum are disposed such that said photoelectrochemically active

label will react with said quencher to generate said photocurrent, and
means for distinguishing between said photocurrent and non-photocurrent.

4,293,311

PHOSPHORIC ACID CRYSTALLIZER UNDERFLOW RETURN

Richard N. Hill, Lakeland, Fla., assignor to W. R. Grace & Co., New York, N.Y.


Filed Jan. 10, 1980, Ser. No. 110,805

The portion of the term of this patent subsequent to Aug. 29, 1995, has been disclaimed.

Int. Cl.³ B01D 9/02; C01B 25/234

U.S. Cl. 23—301

2 Claims



1. In the method of making wet process phosphoric acid analyzing about 57–63% P_2O_5 prepared by steps including
(a) clarifying crude feed acid in a clarifier, said feed acid analyzing about 26–36% P_2O_5 , having an Fe (as Fe_2O_3): P_2O_5 weight ratio in the range of 0.03–0.04; and at least some of said Fe being present as Fe^{++} ;
(b) treating the clarified acid with aluminum silicate in an aluminum silicate treatment zone in the absence of an added oxidant;
(c) concentrating the treated acid to about 46–51% P_2O_5 ;
(d) settling solids in the concentrated acid in a crystallizer-settler providing an overflow and an underflow;
(e) sending crystallizer-settler underflow to the clarifier in (a);
(f) further concentrating the overflow in (d) to about 57–63% P_2O_5 ; the improvement in which the underflow in (d) is divided into a major stream comprising 80–95% of the underflow, and a minor stream comprising the balance; and sending the major stream to the clarifier in (a) and the minor stream to the aluminum silicate treatment zone in (b), whereby the post-precipitation characteristics of the acid are improved.

4,293,312

COMBUSTIBLE COMPOSITIONS AND PROCESSES FOR THEIR PRODUCTION

Rodney T. Fox, North Humberside, England, assignor to Reckitt & Colman Products Limited, England

Filed Jul. 30, 1980, Ser. No. 173,615

Claims priority, application United Kingdom, Aug. 2, 1979, 26915/79

Int. Cl.³ C10L 7/02, 11/02

U.S. Cl. 44—1 R

10 Claims

1. An ignitable combustible composition comprising a matrix of solid resin having distributed therethrough combustible liquid, water and up to 25% by weight of a particulate non-combustible solid having a specific surface area of not greater than $8 \text{ m}^2/\text{g}$.
4. A combustible composition as claimed in claim 1, wherein the non-combustible material is selected from the group consisting of vermiculite, expanded vermiculite, sand, glass microspheres, and diatomaceous earth.

7. A combustible composition as claimed in claim 1, wherein the combustible liquid comprises kerosene.

9. A process for producing a combustible composition as claimed in claim 1 which process comprises mixing a non-combustible particulate material as defined in claim 1 with an aqueous emulsion of combustible liquid, curable resin and emulsifying agent, adding a catalyst for the curing of the resin and allowing the mixture to set.

4,293,313

COMBUSTIBLE COMPOSITIONS AND PROCESSES FOR THEIR PRODUCTION

Rodney T. Fox, North Humberside, England, assignor to Reckitt & Colman Products Limited, England

Filed Jul. 30, 1980, Ser. No. 173,625

Claims priority, application United Kingdom, Aug. 2, 1979, 26914/79

Int. Cl.³ C10L 7/02, 11/02

U.S. Cl. 44—1 R

10 Claims

1. An ignitable combustible composition comprising a matrix of solid resin having distributed therethrough combustible liquid, water and up to 25% by weight of expanded perlite.

5. A combustible composition as claimed in claim 1 wherein the combustible liquid comprises kerosene.

8. A process for producing a combustible composition as claimed in claim 1 which process comprises mixing the expanded perlite with an aqueous emulsion of combustible liquid, curable resin and emulsifying agent, adding a catalyst for the curing of the resin and allowing the mixture to set.

4,293,314

GELLED FUEL-AIR EXPLOSIVE METHOD

Bertram O. Stull, Ridgecrest, Calif., assignor to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Jan. 11, 1980, Ser. No. 111,453

Int. Cl.³ C10L 7/00

U.S. Cl. 44—7 A

3 Claims

1. In a method for producing an explosion comprising the steps of dispersing a cloud of liquid particles in the air and detonating the cloud, the improvement residing in utilizing 1,2-butylene oxide in gel form as said liquid.

4,293,315

REACTION APPARATUS FOR PRODUCING A HYDROGEN CONTAINING GAS

Richard A. Sederquist, Newington, Conn., assignor to United Technologies Corporation, Hartford, Conn.

Division of Ser. No. 21,393, Mar. 16, 1980, Pat. No. 4,240,805.

This application Jul. 2, 1980, Ser. No. 165,180

The portion of the term of this patent subsequent to Apr. 29, 1997, has been disclaimed.


Int. Cl.³ B01J 7/00, 8/06

U.S. Cl. 48—94

6 Claims

1. Reaction apparatus constructed to alternately:
(a) make a hydrogen containing gas by the cracking and catalytic steam reforming of a hydrocarbon feedstock; and
(b) be regenerated, comprising: at least one reaction vessel having an upstream end and downstream end, said vessel having disposed therein, in sequence from its upstream to downstream end, a first volume of inert packing material containing no reform catalyst, a second volume of material substantially adjacent said first volume and including a first region of reform catalyst material, and a third volume of material substantially adjacent said second volume; said vessel including first inlet means upstream of said second volume for introducing a hydrocarbon feedstock and steam into said first volume during the making of the hydrocarbon containing gas, and first outlet means at said downstream end of said vessel for exhausting the hydrogen containing gas produced in the vessel;
said vessel including second inlet means at its downstream

end for introducing a hydrogen purge gas into said third volume during the regeneration of the apparatus, and second outlet means at said upstream end for exhausting gases produced during regeneration; and conduit means disposed in said vessel and surrounded by at least some of said materials, said conduit means having an inlet means communicating outside said vessel for carrying an oxygen containing gas from outside said vessel into



indirect heat exchange relationship with said surrounding materials during regeneration of the apparatus, said conduit means including outlet means within said second volume of material located upstream of said first region of reform catalyst material, said conduit means constructed and arranged with respect to said first region of reform catalyst material to prevent mixing of the oxygen containing gas and hydrogen purge gas downstream of or within said first region of reform catalyst material.

4,293,316

INLET SYSTEM FOR A GAS ANALYZER


Barry Block, Los Altos Hills, Calif., assignor to Harry E. Aine, Los Altos, Calif., a part interest

Filed Sep. 30, 1977, Ser. No. 838,310

Int. Cl.³ B01D 53/04, 53/22; G01N 5/02

U.S. Cl. 55—16

13 Claims



1. The method for introducing gaseous material from a source of an initial gaseous mixture of first and second constituents at initial respective partial pressures into a gas analyzer, the steps of:

adsorbing onto an adsorbent surface said first gaseous con-

stituent of said mixture for collecting and concentrating said first gaseous constituent on said adsorbent surface; desorbing said adsorbed first gaseous constituent from said adsorbent surface; feeding the desorbed first gaseous constituent to the input of a membrane separator at a partial pressure in excess of said initial partial pressure and diffusing said first gaseous constituent through said membrane separator with a higher value of diffusion conductance than that of the second gaseous constituent of said initial mixture; and conducting said desorbed and separated first gaseous constituent of said gas mixture into the detection region of a gas analyzer.

5. In an inlet system for introducing gaseous material from a source of an initial gaseous mixture of first and second constituents at initial respective partial pressures into a gas analyzer: adsorber means for adsorbing onto an adsorbent surface thereof said first gaseous constituent of said mixture; membrane separator means having a membrane of the type which has a higher value of diffusion conductance to said first gaseous constituent than to said second gaseous constituent of said gaseous mixture to be analyzed; means for desorbing said adsorbed first gaseous constituent from said adsorber means; means for conducting said desorbed gaseous constituent, at a partial pressure higher than that of said initial partial pressure of said first gaseous constituent in said initial gaseous mixture, into contact with said membrane separator means so as to conduct said first gaseous constituent through said membrane of said separator means with a higher value of diffusion conductance than that of said second gaseous constituent thereby separating said first and second gaseous constituents; and means for conducting said desorbed and separated first gaseous constituent of said gas mixture into the detection region of the gas analyzer.

4,293,317

FISSION PRODUCT ADSORBENT IMPREGNATED WITH QUINUCRIDENE

Julius L. Kovach, 2948 Brookdown Dr., Worthington, Ohio 43085

Filed Jan. 17, 1980, Ser. No. 112,934

Int. Cl.³ B01D 53/02

U.S. Cl. 55—71

17 Claims

1. A method for removing an alkyl halide from a gas stream contaminated therewith comprising contacting said gas stream with a particulate adsorbent impregnated with quinuclidene.

4,293,318

WET PURIFICATION OF GASEOUS MIXTURES CONTAINING DETERGENT POWDERS IN SUSPENSION

Fausto A. Bertini, and Sergio Noe', both of Milan, Italy, assignors to Ballestra Chimica, S.p.A., Milan, Italy

Filed May 6, 1980, Ser. No. 147,244

Claims priority, application Italy, May 16, 1979, 12598 A/79


Int. Cl.³ B01D 47/00

U.S. Cl. 55—85

4 Claims

1. A method for the wet purification of a gaseous mixture coming from the production of detergent insoluble in a saline solution and containing powder of said detergent in suspension in a gas, comprising washing said gaseous mixture with an aqueous sodium chloride solution containing 18 to 22 wt. % of sodium chloride to form a solid-liquid suspension of said deter-

gent powder in said sodium chloride solution, separating detergent from said solid-liquid suspension and recycling said so-



dium chloride solution, and exhausting the washed gas from which detergent powder has been removed by said washing.

4,293,319

ELECTROSTATIC PRECIPITATOR APPARATUS USING LIQUID COLLECTION ELECTRODES


Ben J. Claassen, Jr., New Orleans, La., assignor to The United States of America as represented by the Secretary of Agriculture, Washington, D.C.

Filed Sep. 28, 1977, Ser. No. 837,488

Int. Cl.³ B03C 3/53

U.S. Cl. 55—122

5 Claims



1. An apparatus for electrostatically imparting a charge to particles in particle-laden gas comprising:

- a duct for conveying said particle-laden gas;
- a high voltage electrode within said duct to create a corona discharge and thereby charge said particles;
- a grounded electrode within said duct adjacent said high voltage electrode; said grounded electrode consisting essentially of a column of free-falling liquid in laminar flow, said grounded electrode positioned within said duct in such a manner as to intercept and remove charged particles from said gas; and
- a field electrode within said duct adjacent said high voltage electrode and said grounded electrode to deflect charged particles into said grounded electrode.


4,293,320
HIGH ENERGY REVERSE AIR DUST COLLECTOR
James W. Robinson, Woodridge, Ill., assignor to Research-Cottrell, Somerville, N.J.

Filed Nov. 23, 1979, Ser. No. 96,906

Int. Cl.³ B01D 46/04

U.S. Cl. 55—273

13 Claims



1. In a dust collector baghouse having upper and lower chambers, a plurality of tubular dust-collecting filter bags suspended in the lower chamber in an array of uniformly spaced rows, said filter bags having open mouths at their upper ends, and means causing a flow of process air upwardly from said lower chamber through the walls of said filter bags and through said open mouths into said upper chamber, the improvement comprising:

- a flat support plate supporting said bags and separating said upper and lower chambers;
 - an air-distribution manifold in said upper chamber, said manifold having a length in the widthwise direction of said baghouse corresponding to the width of said upper chamber, said manifold having a width in the lengthwise direction of said baghouse sufficient to register with but a single row of bags;
 - a source of continuous pressurized air which flows in a reverse direction relative to that of said process air;
 - means directing said reverse-direction air continuously into said manifold;
 - drive means for causing said manifold to travel back and forth the length of said baghouse for injecting pressurized reverse-direction air into said filter bags, one row at a time, said pressurized air flowing through the walls of said filter bags in said row in a reverse direction relative to that of said process air, whereby dust which has been collected on the outer surface of said tubular filter bags is blown off;
 - seal means on said traveling manifold for inhibiting flow of pressurized reverse-direction air into said upper chamber;
 - said upper chamber of said baghouse having a track extending along each longitudinal side of said baghouse;
 - said traveling manifold having grooved wheels adapted to ride on said tracks;
 - said air-distribution manifold being comprised of first and second half sections connected together; and
 - guide rollers between said half sections for maintaining said manifold on said tracks.
12. In a dust collector baghouse having upper and lower chambers, a plurality of tubular dust-collecting filter bags suspended in the lower chamber in an array of uniformly spaced rows, said filter bags having open mouths at their upper ends, and means causing a flow of process air upwardly from said lower chamber through the walls of said filter bags and through said open mouths into said upper chamber, the improvement comprising:
- a flat support plate supporting said bags and separating said upper and lower chambers;
 - an air-distribution manifold in said upper chamber, said

manifold having a length in the widthwise direction of said baghouse corresponding to the width of said upper chamber, said manifold having a width in the lengthwise direction of said baghouse sufficient to register with but a single row of bags;

c. a source of continuous pressurized air which flows in a reverse direction relative to that of said process air;

d. means directing said reverse-direction air continuously into said manifold;

e. drive means for causing said manifold to travel back and forth the length of said baghouse for injecting pressurized reverse direction air into said filter bags, one row at a time, said pressurized air flowing through the walls of said filter bags in said row in a reverse direction relative to that of said process air, whereby dust which has been collected on the outer surface of said tubular filter bags is blown off;

f. seal means on said traveling manifold for inhibiting flow of pressurized reverse-direction air into said upper chamber;

g. said air-distribution manifold being comprised of first and second half sections connected together;

h. a diverter valve fixed to said source of pressurized air;

i. a first and second duct extending from said diverter valve to said first and second half-sections of said manifold;

j. said diverter valve between said source of pressurized reverse-direction air flow and said manifold functioning to restrict said air flow in any one time period to one half the length of said manifold and to inject during any one time period pressurized reverse-direction air into the open mouths of only that half of a single row of bags located on the same one side of the axial center line of the baghouse; and

k. means, including an electrical actuator and an electric control system, for controlling said diverter valve such that at the end of the travel of said manifold in one lengthwise direction of said baghouse said diverter valve is operated so that during the return travel of said manifold pressurized reverse-direction air is injected into the open mouths of bags on the opposite side of the center line of said baghouse.

4,293,321

FASTENING DEVICE FOR FILTER BAGS IN DUST-LADEN GAS FILTERS

Friedel Kordas, Recklinghausen, Fed. Rep. of Germany, assignor to Intensiv-Filter GmbH & Co. KG, Velbert, Fed. Rep. of Germany


Filed Jul. 7, 1980, Ser. No. 166,735

Claims priority, application Fed. Rep. of Germany, Feb. 6, 1980, 3004222

Int. Cl.³ B01D 46/02

U.S. Cl. 55—357

11 Claims



1. A fastening device for the dust-tight attachment of a filter bag having an open end in a separation plate between crude gas and purified gas chambers in dust-laden gas filters, comprising

an elastic socket,

a clamping ring being swingably mounted in said elastic socket is adapted to be disposed at the open end of the filter bag with said elastic socket pressing the open end of the filter bag into holding engagement onto the separation plate,

said clamping ring being formed with flattened portions on two sides which are opposite each other.

4,293,322

DISTILLATIVE SEPARATION OF CARBON DIOXIDE FROM HYDROGEN SULFIDE


James M. Ryan, Weston, and Arthur S. Holmes, Shrewsbury, both of Mass., assignors to Helix Technology Corporation, Waltham, Mass.

Filed Apr. 23, 1980, Ser. No. 143,099

Int. Cl.³ F25J 3/00

U.S. Cl. 62—17

2 Claims



1. In a separation of carbon dioxide from hydrogen sulfide in a distillation column, the improvement of adding an agent for raising the relative volatility of carbon dioxide to hydrogen sulfide to said column at a point above the feed, said agent comprising a C₃-C₆ alkane, a mixture of C₃-C₆ alkanes, SO₂ or SO₃.

4,293,323

WASTE HEAT ENERGY RECOVERY SYSTEM


Frederick Cohen, 1500 W. Church St., Orlando, Fla. 32805

Filed Aug. 30, 1979, Ser. No. 71,363

Int. Cl.³ F25B 27/02, 13/00

U.S. Cl. 62—238.6

6 Claims



1. A water heating system utilizing waste heat from a refrigeration system comprising:
a water storage tank having a cold water inlet line and a hot water outlet line, said water storage tank having a boss having a threaded opening therethrough;
a heat exchange unit disposed in said water storage tank and having an inlet port for connecting to the outlet of the compressor of said refrigeration system and an outlet port for connecting to the inlet of the condenser of said refrigeration system, said heat exchange unit having a threaded portion thereof adapted to match said threaded opening in

said water storage tank for installation of said heat exchange unit in said water storage tank;
means for controlling the temperature of water issuing from said hot water outlet line to be below a predetermined temperature; and

said heat exchange unit comprising:

an outlet chamber attached to said threaded portion;

an elongate outer tube having a closed end and an open end thereof, said open end of said outer tube communicating with said outlet port via said outlet chamber; and

an elongate inner tube disposed within said outer tube, said inner tube having a first open end adjacent said closed end of said outer tube, and a second open end communicating with said inlet port.

4,293,324

PROCESS FOR THE PRODUCTION OF LAYERED GLASS BATCH PELLETS


Walter C. Saeman, Cleveland, Tenn., assignor to Olin Corporation, New Haven, Conn.

Filed Feb. 21, 1980, Ser. No. 123,153

Int. Cl.³ C03B 1/00; C03C 1/02

U.S. Cl. 65—27

10 Claims



1. A continuous process for the production of layered pellets for glass production which comprises the following steps:

(a) maintaining in a pelletizing zone of a rotary apparatus a moving bed of recycle pellets,

(b) feeding sand and particles of a calcium oxide source into said pelletizing zone,

(c) feeding a solution of sodium hydroxide into said pelletizing zone, said recycle pellets being coated with a layer comprised of said solution of sodium hydroxide, said sand and said calcium oxide source and forming layered pellets,

(d) passing said layered pellets into a heated drying zone exposed to an atmosphere containing carbon dioxide gas,

(e) lifting said layered pellets to the upper part of said drying zone and releasing said layered pellets to separately fall through the drying zone,

(f) simultaneously absorbing carbon dioxide onto said layered pellets while evaporating and removing water from said falling layered pellets to form dried layered pellets, said dried layered pellets having a residual moisture content of less than 15 percent by weight,

(g) passing said dried layered pellets from the drying zone to a recycling zone,

(h) recycling a portion of said dried layered pellets to said pelletizing zone as said recycle pellets, and

(i) recovering a portion of said dried layered pellets from said recycle zone.

4,293,325

METHOD OF FORMING HERMETIC SEALS

Agustin M. Chirino, Elmira, and Gerald H. Yost, Corning, both of N.Y., assignors to Corning Glass Works, Corning, N.Y.

Division of Ser. No. 908,003, May 22, 1978, Pat. No. 4,221,604.

This application Nov. 13, 1979, Ser. No. 93,064

Int. Cl.³ C03C 27/00; C08K 3/10

U.S. Cl. 65—43

14 Claims

1. A method of producing a mechanically strong, hermetic

seal between and bonding together ceramic materials having dissimilar thermal expansions, which comprises:

preparing a mixture consisting of glass frit having a softening point of less than 750° C. and

a metal powder selected from the group consisting of 2-40 wt.% aluminum powder, 2-23 wt.% antimony powder and 2-17 wt.% zirconium powder, said wt.% based on the glass frit plus metal powder,

the frit having a sufficiently compatible coefficient of thermal expansion and the metal powder being in an effective amount when mixed with the frit such that the mixture, when reacted, will yield a seal characterized by a coefficient of thermal expansion closely matching or similar to that of the materials being sealed, and by a use temperature of up to 1000° C. when antimony or zirconium powder is chosen, and greater than 1000° C. when aluminum powder is chosen,

adding sufficient vehicle to provide a sealing mixture with viscosity to effect coating of the materials being sealed, applying an amount of the sealing mixture to the sealing surfaces of the materials being sealed to effect a seal therebetween, and

firing the sealed materials to a temperature sufficient to complete the reaction and form the seal.

4,293,326

GLASS COATING

Robert Terneu, Thiméon, and Albert Van Cauter, Charleroi, both of Belgium, assignors to BFG Glassgroup, Paris, France


Filed Jun. 18, 1979, Ser. No. 49,155

Claims priority, application United Kingdom, Jul. 20, 1978, 30589/78

Int. Cl.³ C03C 17/245; G02B 1/10

U.S. Cl. 65—60 D

17 Claims



1. A process for forming a tin oxide coating on a face of a glass substrate or of a previously formed coating thereon, comprising contacting said face, while said face is at elevated temperature, with a gaseous medium containing tin tetrachloride which undergoes chemical reaction and/or decomposition to form said tin oxide coating, wherein said gaseous medium contains tin tetrachloride in a concentration corresponding to a partial pressure of at least 2.5×10^{-3} atm. and contains water vapour in a concentration corresponding to a partial pressure of between 50×10^{-3} and 200×10^{-3} atm. and is caused to contact said face while the temperature of the gaseous medium is at least 300° C. and the temperature of the glass where said contact occurs is above 550° C.

4,293,327

METHOD FOR MANUFACTURING GLASS BOTTLES

John D. Northup, 2460 Underhill Rd., Toledo, Ohio 43615

Division of Ser. No. 964,739, Nov. 29, 1978, Pat. No. 4,244,726,

which is a continuation-in-part of Ser. No. 906,048, May 15,

1978, abandoned. This application May 25, 1979, Ser. No. 42,455


Int. Cl.³ C03B 9/14, 9/20

U.S. Cl. 65—64

7 Claims

1. A method of manufacturing glass containers including the steps of reciprocating first and second blow molds along a

comprises contacting said aqueous medium with at least one live fungus from the molds family for a period of time sufficient



to allow the fungus to extract metal from said solution in water insoluble form.

4,293,334

RECOVERY OF METALS


Walter Drobot, Montclair, and Hubert A. Lechavellier, Piscataway, both of N.J., assignors to Engelhard Minerals & Chemicals Corporation, Iselin, N.J.

Filed Feb. 12, 1980, Ser. No. 120,800

Int. Cl.³ C22B 11/04, 15/12, 21/00, 23/04

U.S. Cl. 75—101 BE

13 Claims



1. A process for removing metal from an aqueous medium containing in solution one or more metals selected from the group consisting of platinum, rhodium, palladium, ruthenium, gold, rhenium, silver, iridium, zinc, aluminum, iron, copper, nickel, cobalt, manganese, chromium, boron and tin; which comprises contacting said aqueous medium containing at least one of said metals with a killed fungus or a mixture of killed fungi from the family of molds for a period of time sufficient to convert said metal from soluble form to an insoluble form followed by the separation of the resulting aqueous medium from the killed fungus or killed fungi containing said removed metal.

4,293,335

ROLL FOR MANUFACTURING FLOAT GLASS

Ryo Tamamura, Yokohama, and Yukinori Kutsukake, Tokyo, both of Japan, assignors to Asahi Glass Company, Ltd., Tokyo, Japan

Continuation of Ser. No. 962,713, Nov. 21, 1978, abandoned.


This application Mar. 21, 1980, Ser. No. 132,628

Claims priority, application Japan, Dec. 8, 1977, 52/146604

Int. Cl.³ C23F 7/04

U.S. Cl. 75—124

3 Claims



1. A roll for conveying a float glass ribbon formed on a bath of molten metal, having excellent corrosion resistance to molten tin and high oxidation resistance, at least the surface of said roll being made of a heat-resistant cast steel consisting essentially of 0.01–2.0 wt.% of a rare earth metal mixture, and 0.1–3.0 wt.% of Al, 0.2–0.45 wt.% of C, up to 2.0 wt.% of Si, up to 2 wt.% of Mn, up to 0.04 wt.% of P, up to 0.04 wt.% of S, 19–22 wt.% of Ni, 23–27 wt.% of Cr, and the balance of Fe, said rare earth metal mixture comprising about 86.8 wt.% of Ce, about 3.0 wt.% of La, about 4.0 wt.% of Nd, about 6.2 wt.% of Sm plus Pr, and with main impurities of about 3.2 wt.% of Fe, about 0.37 wt.% of Mg, about 0.27 wt.% of Al and about 0.73 wt.% of Si.

4,293,336

COLD ROLLED NON-ORIENTED ELECTRICAL STEEL SHEET

Ko Matsumura, Ichihara; Hiroto Nakamura, and Toshio Irie, both of Chiba, all of Japan, assignors to Kawasaki Steel Corporation, Kobe, Japan

Filed May 27, 1980, Ser. No. 153,029

Claims priority, application Japan, May 30, 1979, 54-66087

Int. Cl.³ C22C 38/06

U.S. Cl. 75—124

1 Claim

1. A cold rolled non-oriented electrical steel sheet having a low iron loss, which consists of not more than 0.02% by weight of C, 0.1–3.5% by weight of Si, not more than 1.0% by weight of Al, 0.1–1.0% by weight of Mn, 0.03–0.40% by weight of Sn and the remainder being essentially iron.

4,293,337

SILVER, CADMIUM OXIDE, LITHIUM CARBONATE CONTACT MATERIAL AND METHOD OF MAKING THE MATERIAL

Frank S. Brugner, Jr., Mequon, Wis., assignor to Square D Company, Palatine, Ill.

Filed Aug. 20, 1979, Ser. No. 68,038

Int. Cl.³ B22F 3/00; C22C 29/00

U.S. Cl. 75—232

12 Claims



1. A process of forming an improved electrical contact for

electrical power applications and made with a first starting material selected from a group essentially consisting of a first metal in powder form and reducible compounds of the first metal in powder form both having a selected maximum particle size, and with a second starting material selected from a group essentially consisting of a second metal in powder form, reducible compounds of the second metal in powder form, and mixtures of the second metal in powder form all having a selected maximum particle size with said second metal selected to be more readily oxidizable than the first metal under similar environmental conditions and added in an amount from a minimum effective amount up to the maximum limit of solubility of the second metal in the first metal by mixing the first and second starting materials together to obtain a mixture having a substantially even dispersion of the first and second starting materials, heating the mixture in a reducing atmosphere at a temperature below the melting temperature of the alloy of the first and second metals in the proportions present to alloy the first and second metals in a powder form; sieving the alloyed mixture to produce a selected maximum particle size; heating the sieved mixture in an oxidizing atmosphere at a temperature and under conditions selected to substantially completely oxidize the second metal and with said temperature below the melting temperature of the alloy of the first and second metals in the proportions present to thereby maintain the mixture in a powder form; and sieving the oxidized mixture to produce a selected maximum particle size, said process comprising adding at a selected time during the process lithium metal in the form of lithium carbonate particles with the lithium carbonate particles uniformly distributed throughout material, forming a compact of the powdered material to provide an electrical contact having a desired shape, size and density, and sintering the compact for a predetermined time at a temperature less than the decomposition temperature of the lithium carbonate to provide a sintered electrical contact.

6. A sintered electrical contact for use as switching contacts in power circuits consisting essentially of silver, cadmium and lithium with silver present in a metallic form, the cadmium present as cadmium oxide and the lithium present as lithium carbonate.

4,293,338

DIFFUSION COATING COMPOSITION OF IMPROVED FLOWABILITY

Bernard R. Rose, Ipswich, Mass., and John K. Willis, Salem, N.H., assignors to Walbar Metals, Inc., Peabody, Mass.

Filed Jul. 26, 1979, Ser. No. 60,891

Int. Cl.³ B22F 9/00

U.S. Cl. 75—253

9 Claims

1. A particulate composition of matter forming means from which to expel aluminum and chromium at elevated temperatures, said composition comprising an inert filler, effective quantities of a halide carrier, chromium metal powder, and an aluminum-contributing powder of the compound Co_2Al_9 .

4,293,339

UNDERWATER WAX FORMULATION AND METHOD

Robert F. Supcoe, and Thomas Radakovich, both of Annapolis, Md., assignors to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Feb. 28, 1980, Ser. No. 125,733

Int. Cl.³ C09D 5/08, 5/14

U.S. Cl. 106—18.29

4 Claims

1. A wax coating material for application to submerged surfaces consisting essentially of a mixture, by weight percent, of from about 2% to about 18% of a fluorinatedchlorinated aliphatic polymer having a recurring unit of $-\text{C}_2\text{F}_3\text{Cl}-$ and an average molecular weight range of between about 500 to about 1200;

from about 20% to about 40% of a microcrystalline wax; from about 40% to about 70% of a chlorinated paraffinic

hydrocarbon having a chlorine content, by weight percent, of from about 40% to about 70% and up to about 5% of a surfactant for improving the displacement of the water molecules from the surface.

4. A method of coating submerged surfaces for preventing marine growth comprises applying a wax mixture directly to the submerged surfaces, said wax mixture having a formulation substantially as follows:

from about 2% to about 18% of a fluorinated-chlorinated aliphatic polymer having a recurring structural unit $-\text{C}_2\text{F}_3\text{Cl}-$ and an average molecular weight range of between about 500 to about 1200;

from about 20% to about 40% of a microcrystalline wax; from about 40% to about 70% of a chlorinated paraffinic hydrocarbon having a chlorine content, by weight percent, of from about 40% to about 70%; and up to about 5% of a surfactant for improving the displacement of the molecules from the surface.

4,293,340

COMPOSITION AND PROCESS FOR STABILIZING SOIL

Fred L. Metz, Concord, Ohio, assignor to Diamond Shamrock Corporation, Dallas, Tex.


Continuation-in-part of Ser. No. 91,056, Nov. 5, 1979, abandoned. This application Oct. 20, 1980, Ser. No. 198,634

Int. Cl.³ C09J 1/02

U.S. Cl. 106—74

15 Claims

AVERAGE COMPRESSIVE STRENGTH
(Kilograms/cm²)



1. In a liquid alkali metal silicate composition curable to a solid upon standing and comprising water, an alkali metal silicate and glyoxal, the improvement which comprises incorporating from 0.02 to 0.7 mole of hydrogen peroxide per mole of glyoxal, whereby the resulting composition exhibits, upon curing, improved compressive strength.

10. In a method of stabilizing soil which comprises contacting said soil with a sole liquid composition comprising 10 to 70 percent, by volume, of an aqueous alkali metal silicate having an alkali metal oxide:silicon dioxide ratio of 1.0:3.0–4.0; about 0.25 to 1.05 moles of glyoxal per liter of composition; and water, the improvement which comprises adding to said composition about 0.025 to 0.18 mole of hydrogen peroxide per liter of composition, whereby enhanced load-bearing capacity is exhibited by soil treated with the composition.

4,293,341

THIN SECTION INSULATING CONCRETE OF HIGH STRENGTH AND LOW WATER REQUIREMENT

Hubert T. Dudley, Chelmsford, and Ralph J. Bragg, Townsend, both of Mass., assignors to W. R. Grace & Co., Cambridge, Mass.

Filed Nov. 7, 1979, Ser. No. 92,157
Int. Cl.³ C04B 7/35

U.S. Cl. 106—88

14 Claims

1. A hydratable lightweight concrete composition which when pumped and cast as a wet fluid layer hardens into a lightweight, strong porous thermal insulating mass having a density of less than 50 pounds per cubic foot comprising (a) 1 part by volume of hydratable cementitious binder; (b) about 2 to about 5 parts by volume of expanded vermiculite or expanded perlite per part by volume of said binder, said vermiculite or perlite having a density less than 10 pounds per cubic foot; (c) at least about 0.03 to about 0.08 percent by weight of said binder of air-entraining surface active agent; (d) at least about 0.005 to about 0.20 percent by weight of said binder of polyelectrolytic sulfonate dispersing agent; (e) up to about 20 percent by weight of said binder of an inert particulate having a density of from about 50 to about 100 pounds/cu. ft.; and, (f) water in an amount of from about 90 to about 110 percent by weight of the total dry weight of the said components (a) to (e).

4,293,342

LIGNOSULFONATE DERIVATIVES

William J. Detroit, Schofield, Wis., assignor to American Can Company, Greenwich, Conn.

Division of Ser. No. 876,327, Feb. 9, 1978, Pat. No. 4,219,471.
This application Dec. 17, 1979, Ser. No. 104,169

Int. Cl.³ C04B 7/35

U.S. Cl. 106—90

18 Claims

1. A cementing composition comprising a hydraulic cement, a retarding agent therefor, in an amount of at least 0.5 percent based on the weight of the cement composition before dilution into a slurry,

said retarding agent comprising

a lignosulfonate or an alkali metal salt derivative thereof derived from sulfite waste liquor that has been subjected to alkaline oxidation, hydrolysis and partial desulfonation with subsequent resulfonation;

with subsequent reaction of said resulfonated lignosulfonate with:

- a halocarboxylic acid;
- a halocarboxylic acid and a hydroxy-substituted lactone;
- a hydroxy-substituted lactone as aforesaid;
- a halocarboxylic acid and sequentially the derivative of a sugar acid containing spent sulfite liquor derived from the reaction of a spent sulfite liquor with a cyanide followed by hydrolysis of the resulting reaction product; or
- said derivative of a sugar acid-containing spent sulfite liquor.

4,293,343

MORTARS AND CEMENTS HAVING IMPROVED FREEZE-THAW PROPERTIES AND METHOD OF ACHIEVING SAME

Richard F. Shannon, Lancaster, Ohio, assignor to Owens-Corning Fiberglass Corporation, Toledo, Ohio

Continuation of Ser. No. 874,735, Feb. 3, 1978, abandoned. This application Nov. 13, 1979, Ser. No. 93,770

Int. Cl.³ C04B 7/02

U.S. Cl. 106—99

3 Claims

1. Insulation materials formed from the following ingredients in parts by weight:

Mineral fiber	19-39
Particulate filler	0-60

-continued

Hydraulic setting binder	3-60
Glass monofilaments	0.01-1.0

said monofilaments forming a three dimensional monofilament network therein.

4,293,344

SETTING RETARDATIVES FOR COMPOSITIONS WITH A GYPSUM PLASTER BASE OR ANHYDRITE


Christian M. Joseph, Auzouer, France, assignor to Manufacture de Produits Chimiques Protex, Paris, France

Filed Nov. 6, 1979, Ser. No. 92,055
Int. Cl.³ C04B 13/00, 43/00; E04C 2/00

U.S. Cl. 106—111

9 Claims

1. A plaster composition having a long setting time which comprises a gypsum-based plaster and 0.001-2 percent of a polymer having a molecular weight of less than 1000 of the formula I, as a setting retarding agent:



wherein


R₁ is hydrogen or methyl,

R₂ is —COOH, COOR₄ wherein R₄ is C₁ to C₄ alkyl, —CONH₂, or —CN,


R₃ is hydrogen or methyl,

X is a sodium, potassium, lithium, calcium, magnesium, or ammonium ion, and

x and y designate the molar ratio of the two monomers forming the setting retarding agent of the formula I, so that x indicates that 0 to 40 moles of the monomer of the formula II



are present per 100 moles of the setting retarding agent of the formula I and so that y indicates that 60 to 100 moles of the monomer of the formula III



are present per 100 moles of the setting retarding agent of the formula I.

4,293,345

WAX COMPOSITION FOR ENTIRELY OR PARTLY REPLACING CARNAUBA WAX OR MONTAN WAX

Jacobus J. Zeilstra, Wijnbergen; Willem J. de Klein, Dieren, and Joannes D. Bik, Eerbeek, all of Netherlands, assignors to Akzona Incorporated, Asheville, N.C.

Filed Oct. 26, 1979, Ser. No. 88,646

Claims priority, application Netherlands, Oct. 26, 1978, 7810670

Int. Cl.³ C08L 91/06

U.S. Cl. 106—270

3 Claims

1. A wax composition for entirely or partly replacing car-


nauba wax or montan wax and substantially consisting of one or more acids and/or derivatives thereof selected from the group consisting of

A. ester of phenols or aromatic, aliphatic or cycloaliphatic alcohols having at least 1 to 10 primary or secondary hydroxyl groups;

B. amides of aliphatic, cycloaliphatic or aromatic mono- or diamines having 1 or 2 primary or secondary amino groups;

C. salts of alkali metals or alkaline earth metals, emphoeric metals, heavy metals, of ammonium or of a compound containing a tertiary amino group;

characterized in that at least 40% by weight of the acid present as such, or at least 40% by weight of the acid from which the derivatives are prepared has a branched-chain structure and at least 10% by weight thereof corresponds to the formula:



where

x=0, if y=2


or x=2, if y=0

R=CH₃(CH₂)_n, where n represents an integer from 17 to 42;

b is 0 or 1, where, if b=0, Q represents a hydrogen atom, and if b=1, Q represents a CH₂-group, and

a=0 or 1, where if a=0, Z represents a hydrogen atom, and if a=1, Z represents a CH₂-group.

3. A wax composition according to the claims 1 or 2, characterized in that besides the branched-chain acids or derivatives thereof having the formulae given for these acids in claims 1 or 2 there is present an amount of 40 to 60 percent by weight of linear aliphatic monocarboxylic acids or derivatives thereof, with the acid having the formula RCH₂CH₂CH₂COOH, where R has the meaning given in claim 1 and about 30 to 40 percent by weight of γ-branched carboxylic acids or derivatives thereof, with the acid having the formula:



where R₁ and R₂ represent linear alkyl groups which together have the same number of carbon atoms as the group R.

4,293,346

SIMULATED COUNTERCURRENT SORPTION PROCESS EMPLOYING ION EXCHANGE RESINS WITH BACKFLUSHING

Arthur M. Landis, Carpentersville; Donald B. Broughton, Evanston, and R. Gene Fickel, Roselle, all of Ill., assignors to UOP Inc., Des Plaines, Ill.

Filed Nov. 5, 1979, Ser. No. 91,303

Int. Cl.³ C13D 3/14

U.S. Cl. 127—46 A

21 Claims

1. A process for separating an extract component from a fluid feed mixture comprising said extract component and a raffinate component in a simulated moving-bed system by employment of a stationary adsorbent consisting essentially of an ion exchange resin having a greater selectivity for said extract component than for said raffinate component which process comprises the steps of:


(a) maintaining fluid flow through a column of said adsor-

bent, which column contains at least an adsorption zone, a purification zone, and a desorption zone, each such zone comprising a separation zone having separate separation functions occurring therein, said column also containing a backflushing zone in which backflushing is effected, said zones being serially interconnected with the terminal zones of said column connected to provide a continuous connection of said zones, said fluid flow in said separation zones being in a single direction and the fluid flow in said backflushing zone being in a direction opposite said single direction;

(b) maintaining said adsorption zone in said column defined by the adsorbent located between a feed input stream at an upstream boundary of said zone and a raffinate output stream at a downstream boundary of said zone;

(c) maintaining said purification zone as the nearest separation zone upstream, with respect to said single direction, of said adsorption zone, said purification zone defined by the adsorbent located between an extract output stream at an upstream boundary of said purification zone and said feed input stream at a downstream boundary of said purification zone;

(d) maintaining said desorption zone immediately upstream, with respect to said single direction, of said purification zone, said desorption zone defined by the adsorbent lo-



cated between a desorbent input stream at an upstream boundary of said zone and said extract output stream at a downstream boundary of said zone;

(e) maintaining said backflushing zone immediately upstream, with respect to said single direction, of said feed input stream to said column, said backflushing zone defined by the adsorbent located between said feed input stream at an upstream boundary of said zone and a backflushing output stream at a downstream boundary of said zone;

(f) passing said feed mixture into said adsorption zone at adsorption conditions to effect the selective adsorption of said extract component by said adsorbent in said adsorption zone and withdrawing a raffinate output stream from said adsorption zone;

(g) passing a desorbent material into said desorption zone at desorption conditions to effect the displacement of said extract component from the adsorbent in said desorption zone;

(h) withdrawing an extract output stream comprising said extract component and desorbent material from said desorption zone;

(i) withdrawing said backflushing output stream from said backflushing zone;

(j) periodically advancing through said column of adsorbent in a downstream direction with respect to fluid flow in

said adsorption zone the feed input steam, raffinate output stream, desorbent input stream, extract output stream, and backflushing output stream to effect the shifting of zones through said adsorbent and the production of extract output and raffinate output streams.

4,293,347

PROCESS FOR DEPOLYMERIZATION OF ACRYLIC ACID POLYMERS

Elliot M. Haschke, and Bennie J. Lewis, both of Lake Jackson, Tex., assignors to The Dow Chemical Company, Midland, Mich.

Filed Jan. 21, 1980, Ser. No. 114,133
Int. Cl.³ B08B 3/08, 7/00, 9/08

U.S. Cl. 134—11

5 Claims

1. A method for removing polymers of acrylic acid from distillation vessels which comprises contacting said polymer with a solvent selected from the group of dialkyl phthalates wherein each alkyl group contains from one to four carbon atoms at a temperature which will decompose or dissolve said polymer without appreciable decomposition of said solvent.

4,293,348

METHOD FOR REMOVING OIL-BASED MATERIALS FROM WATER SURFACE

James E. Shewmaker, Scotch Plains, N.J., assignor to Exxon Research & Engineering Co., Florham Park, N.J.

Filed Mar. 10, 1980, Ser. No. 128,726
Int. Cl.³ B01D 17/02; B08B 9/00

U.S. Cl. 134—22 R

13 Claims

10. A method for the direct loading and discharge of clean ballast from a crude oil depleted tank of a cargo carrier having vertical steel surfaces comprising:

- (a) crude oil washing and water rinsing said tank;
- (b) stripping said tank to remove residual-oil heel;
- (c) adding clean ballast water to said tank wherein any residual oil-based material remaining in said tank floats on the surface of said ballast water;
- (d) adding to the surface of said ballast water a spreading agent having a spreading force greater than about 38 mN/M in an amount sufficient to force substantially all said material against said steel surfaces; and
- (e) discharging said ballast water from said tank at a point below the surface of said water; said oil-based material being forced to deposit on said steel surfaces vacated by said discharged water.

4,293,349

PROTECTIVE COMPOSITIONS FOR STEEL SURFACES AND THE PROCESS FOR THEIR PREPARATION

Giuseppe Pedrazzini, Milan, Italy, assignor to Parker Italiana S.a.s., Milan, Italy

Filed Mar. 17, 1980, Ser. No. 131,112

Claims priority, application Italy, Mar. 16, 1979, 21079 A/79
Int. Cl.³ C23F 7/10

U.S. Cl. 148—6.15 R

7 Claims

1. A composition for protecting steel surfaces from the oxidizing action of the atmosphere, comprising as essential actual components:

- an acid of molecular weight between 270 and 1200 selected from the group consisting of pyrogallous acid glucosides, ellagic acid glucosides and combinations thereof in a quantity between about 15 and about 30% phosphoric acid in a quantity between about 2 and about 3.2% by weight;
- a phosphate selected from the group consisting of zinc phosphate, manganese phosphate and combinations thereof in a quantity between about 1.1 and about 2% by weight; and
- a nitrate selected from the group consisting of zinc nitrate, manganese nitrate and combinations thereof in a quantity between about 0.5 and about 1% by weight.

4,293,350

GRAIN-ORIENTED ELECTROMAGNETIC STEEL SHEET WITH IMPROVED WATT LOSS

Tadashi Ichiyama, Sagami-hara; Shigehiro Yamaguchi, Fujisawa; Tohru Iuchi, Kawasaki, and Katsuro Kuroki, Kitakyushu, all of Japan, assignors to Nippon Steel Corporation, Tokyo, Japan


Filed Jul. 19, 1979, Ser. No. 58,757

Claims priority, application Japan, Jul. 26, 1978, 53-91217

Int. Cl.³ H01F 1/04

U.S. Cl. 148—111

15 Claims



1. In a method of producing a grain-oriented silicon-steel electrical sheet by cold rolling a silicon-steel sheet, with intermediate annealing if necessary, to a standard electrical sheet thickness, decarbonizing the sheet if necessary, and subjecting the sheet to a final high-temperature anneal, so as to produce a grain-oriented silicon-steel electrical sheet having a plurality of magnetic domains; wherein the improvement comprises momentarily irradiating the finally annealed sheet by a laser beam so as to subdivide said domains to an extent appreciably improving the watt loss of the finally annealed sheet as compared to the watt loss it had prior to said irradiating.

4,293,351

SILICONE RUBBER EXPLOSIVE AND METHOD OF MAKING

Gerald E. Johannes, 565 Frank Ave., SE., Huron, S. Dak. 57350

Filed Aug. 6, 1979, Ser. No. 63,689

Int. Cl.³ C06B 45/10

U.S. Cl. 149—19.2

2 Claims

1. The method of making an explosive product wherein a particulate explosive material containing mainly a composition selected from the group consisting of PETN and RDX is mixed with a pourable silicone rubber in the ratio of 20–50 parts by weight of silicone rubber to 80–50 parts by weight of explosive material and about 1–5% by weight of glacial acetic acid or an equivalent amount of weaker acetic acid as a catalyst, to form a tacky viscous paste wherein the explosive material is uniformly distributed.

4,293,352

DEGRADABLE BINDER EXPLOSIVES

Benjamin Y. S. Lee; Russell Reed, Jr., both of Ridgecrest, Calif., and Roger L. Miller, Brigham City, Utah, assignors to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Aug. 23, 1979, Ser. No. 69,215

Int. Cl.³ C06B 45/10

U.S. Cl. 149—19.4

1 Claim

1. An easily degradable explosive composition containing about 82 percent explosive solids and about 18 weight percent of a polyurethane binder made from the reaction of from 16.56 weight percent polyester and from 1.44 weight percent of said curative;

said binder being prepared by reaction of a hydroxyl terminated polyester having a functionality of 2.33 with a curative comprising Lysine diisocyanate methyl ester; and said binder being degradable in aqueous ammonia or dilute acid, yielding reusable explosive solids and non-toxic binder-degradation products, and being not degradable upon contact with water.

4,293,353

SEALING-ATTACHING SYSTEM FOR BAG TYPE AEROSOL CONTAINERS


Peter G. Pelton, St. Louis, Mo., and Sam C. Pulcinani, Norridge, Ill., assignors to The Continental Group, Inc., New York, N.Y.

Filed Nov. 3, 1978, Ser. No. 957,382

Int. Cl.³ B29C 27/00; C09J 5/02, 5/06, 5/10

U.S. Cl. 156—69

5 Claims



1. A method of installing a product bag in an aerosol container having an upper end defining a reduced diameter opening and wherein said bag is of a cross section greater than said opening, said method comprising the steps of gathering an upper part of said bag and having the gathered bag part pass through said opening, and then heating and molding the gathered bag part against that part of said upper end defining said opening to form a unitary substantially constant thickness seal defining part aligned with and conforming to said opening, seating a valve cup in said opening and sealing said valve cup relative to said opening by said seal defining part, said valve cup being seated in said opening in advance of said heating and molding step, and said valve cup being utilized in conjunction with said upper end to effect said molding.

5. A method of installing a product bag in an aerosol container having an upper end defining a reduced diameter opening and wherein said bag is of a cross section greater than said opening, said method comprising the steps of gathering an upper part of said bag and having the gathered bag part pass through said opening, and then heating and molding the gathered bag part against that part of said upper end defining said opening to form a unitary substantially constant thickness seal defining part aligned with and conforming to said opening, the container having a body, said bag having a bag form prior to being inserted into the container, and the bag cross section generally approaching the cross section of the container body.

4,293,354

PROCESS AND MACHINE FOR FASTENING A CLOSURE MEMBER TO A CONTAINER


Richard G. Haas, South Haven, Mich., assignor to Brown Company, Kalamazoo, Mich.

Filed Aug. 30, 1979, Ser. No. 71,243

Int. Cl.³ B29C 27/12; B30B 15/34; B65B 7/28

U.S. Cl. 156—69

32 Claims



1. A machine useful for fastening a closure member to a container with an upstanding tubular wall, an edge of which is folded over onto itself to form a folded-over, reinforced portion.

tion of double thickness at that end, said closure member having an upstanding tubular inner wall conforming to the inner surface of said folded-over, reinforced portion and a downstanding tubular outer wall connected thereto and conforming to the outer surface of said folded-over, reinforced portion, thereby forming a tubular channel in which said folded-over, reinforced portion is seated in frictional engagement, which machine comprises:

a fastening head; anvil means; positioning means for positioning said fastening head and said anvil means in fastening position with the downstanding tubular outer wall of said channel juxtaposed to said anvil means and with the upstanding tubular inner wall of said channel apposed to said fastening head; and, actuating means for actuating said fastening head, while it is in fastening position, to fasten the upstanding inner tubular wall of said channel to the inner surface of said folded-over, reinforced portion, said fastening head comprising means for pressing selected portions of the upstanding tubular inner wall of said channel into the inner surface of said folded-over, reinforced portion against anvil means apposed to said selected portions; in which said fastening head comprises a plurality of punching points arranged about the periphery of said fastening head, and said actuating means comprises punching means for causing said punching points to move radially outwardly and to punch the upstanding tubular inner wall of said tubular channel into the inner surface of the folded-over, reinforced portion of the upstanding tubular wall of said container; and in which the inner surface of the folded-over, reinforced portion of the upstanding tubular wall of said container has areas of low resistance to the punching-in of the upstanding tubular inner wall of said tubular channel, which areas of low resistance are opposite said punching points and as to which said punching means is operative to punch the portions of said upstanding tubular inner wall which are apposed to said areas of low resistance into the same.

22. A process for fastening a closure member to a container with an upstanding tubular wall, an edge of which is folded over onto itself to form a folded-over, reinforced portion of double thickness at that end, said closure member having an upstanding tubular inner wall conforming to the inner surface of said folded-over, reinforced portion and a downstanding tubular outer wall connected thereto and conforming to the outer surface of said folded-over, reinforced portion, thereby forming a tubular channel in which said folded-over, reinforced portion is seated in frictional engagement, which process comprises:

positioning the end of said container which is closed with said closure member in a position juxtaposed to a fastening head and anvil means; effecting a relative movement of said container with respect to said fastening head and said anvil means operative to seat said fastening head on the closed end of said container with said upstanding tubular inner wall apposed to said fastening head and said downstanding tubular outer wall juxtaposed to said anvil means, and then actuating said fastening head to fasten said upstanding tubular inner wall to the inner surface of said folded over, reinforced portion by pressing selected portions of said upstanding tubular inner wall into the inner surface of said folded-over, reinforced portion against anvil means apposed to said selected portions; in which the fastening of said closure member is effected by punching-in portions of said upstanding tubular inner wall into the inner surface of said folded-over, reinforced portion; and in which the inner surface of said folded-over, reinforced portion has preformed areas of low resistance to the punching-in of said upstanding tubular inner wall into which corresponding portions of said upstanding tubular inner wall are punched.

4,293,355

METHOD FOR ULTRASONICALLY WELDING PLASTICIZED THERMOPLASTIC POLYMERIC FOAM WARES

Albert R. Wacker, Zionsville, Ind., assignor to Cabot Corporation, Kokomo, Ind.

Division of Ser. No. 900,982, Apr. 28, 1978, Pat. No. 4,193,396.

This application Sep. 10, 1979, Ser. No. 73,928

Int. Cl.³ A61F 11/02; B23K 19/04

U.S. Cl. 156—73.2

6 Claims



1. A method for thermally welding an element composed of a flexible plasticized thermoplastic material to a ware composed of a plasticized thermoplastic polymeric foam which comprises:

- supporting the polymeric foam;
- bringing said element into abutting relationship with said foam;
- applying an ultrasonic transducer and spacing said transducer from said support so as to define a fixed gap therebetween within which said element is biased against said foam;
- energizing said transducer with sufficient power and for a sufficient period of time as to flux the plasticized thermoplastic materials of said element and said foam; and
- cooling the resulting weldment to below fluxing temperature, a portion of said foam forming a part of said weldment not being completely fluxed into a solid continuous state.

4,293,356

METHOD FOR ADHESION OF CERAMICS

Yoshihiro Ebata, Kawanishi; Yasuo Toibana, Ikeda; Tsuneo Uetsuki, Kawanishi; Saburo Kose, and Makoto Kinoshita, both of Ikeda, all of Japan, assignors to Agency of Industrial Science & Technology and Ministry of International Trade & Industry, both of Tokyo, Japan

Division of Ser. No. 87,064, Oct. 22, 1979, Pat. No. 4,269,641.

This application Apr. 25, 1980, Ser. No. 143,758

Claims priority, application Japan, Nov. 10, 1978, 53-138991; Dec. 1, 1978, 53-149421

Int. Cl.³ B32B 31/12; C04B 39/12

U.S. Cl. 156—89

6 Claims

1. A method for the adhesion of two ceramic articles, which comprises interposing between the opposed surfaces of the two ceramic articles a powder mixture of $\text{CuS-LaCrO}_3\text{-SiO}_2\text{-Cu}$ wherein the proportion of CuS to $\text{LaCrO}_3\text{-SiO}_2$ is in the range of from 80:20 to 90:20 by weight and the proportion of LaCrO_3 to SiO_2 is in the range of from 25:75 to 50:50 by weight, pressing the two ceramic articles into fast contact with each other across the interposed layer of powder mixture, and heating these two ceramic articles in the resultant state of fast contact in an oxidizing atmosphere at a temperature in the range of from 1000° to 1200° C. for a period of from 10 to 20 minutes.

4,293,357

METHOD FOR PRODUCING CERAMIC HONEYCOMB FILTERS

Noboru Higuchi; Tetsuo Yano, both of Nagoya, and Masahiro Ohnishi, Kuwana, all of Japan, assignors to NGK Insulators, Ltd., Nagoya, Japan


Filed Jul. 14, 1980, Ser. No. 167,731

Claims priority, application Japan, Jun. 16, 1980, 55-80107

Int. Cl.³ C03B 29/00

U.S. Cl. 156—89

14 Claims



1. A method for producing a ceramic honeycomb filter comprises adhering a film on an opening end surface of a porous ceramic honeycomb structural body having a large number of channels extending therethrough, boring holes through the film at a given portion, charging a sealing material into the channels through the bores in the film to seal an end portion of the given channels.

4,293,358

METHOD AND APPARATUS FOR ACCURATELY POSITIONING A BEAD BUNDLE


Earl F. Loeffler, Uniontown, and Harley P. Weyand, Jr., Doylestown, both of Ohio, assignors to The Firestone Tire & Rubber Company, Akron, Ohio

Filed May 7, 1980, Ser. No. 147,669

Int. Cl.³ B29H 17/22

U.S. Cl. 156—131

10 Claims



2. A method for accurately positioning the axially facing surfaces of a pair of axially spaced, annular bead bundles with respect to the body ply assembly on a tire building drum, comprising the steps of:

- supporting each bead bundle generally co-axially with the drum;
- moving a plurality of first clamping elements into engagement with the facing surfaces of the bead bundles;
- stopping the engaging movement of the first clamping elements accurately with respect to an axial reference datum;
- moving a plurality of second clamping elements against the opposite axial surfaces of the bead bundles and driving the bundles fully against their respective first clamping elements; and
- applying a retaining force to said first clamping elements which is greater than the force applied by said second clamping elements against the bead bundles.

4,293,359

METHOD FOR FASTENING A STABILIZING ARRANGEMENT ON A CONTAINER

Kjell M. Jakobsen, Hjalte, Denmark, assignor to Aktiebolaget Platmanufaktur AB, Malmo, Sweden

Division of Ser. No. 928,539, Jul. 27, 1978, Pat. No. 4,196,039,

which is a continuation-in-part of Ser. No. 793,737, May 4, 1977, abandoned. This application Jul. 11, 1979, Ser. No. 56,557

Claims priority, application Sweden, May 10, 1976, 7605265

Int. Cl.³ B32B 31/00

U.S. Cl. 156—156

6 Claims



1. A method of securing a tubular stabilizing arrangement of plastic material on a container of plastic material, said method comprising inserting the container into the tubular stabilizing arrangement into a position in which a middle portion of the bottom of the stabilizing arrangement is axially spaced from the bottom of the container while side walls of the stabilizing arrangement are in axial contact with the container, applying a force against the middle portion of the bottom of the stabilizing arrangement in order to cause it to lie against the middle portion of the bottom of the container while the walls of the tubular stabilizing arrangement axially abut against and engage the container, and simultaneously supplying energy in the region in which the middle portion of the bottom of the stabilizing arrangement lies against the middle portion of the bottom of the container, whereby the stabilizing arrangement is secured to the container in the middle portions of the arrangement and container respectively, wherein during the securing of the stabilizing arrangement to the container, the walls of said stabilizing arrangement are subjected to bending by the application of said force against the middle portion of the bottom of the stabilizing arrangement which displaces that portion axially relative to the other parts of the stabilizing arrangement to cause said bottom of the stabilizing arrangement to lie against the middle portion of the bottom of the container, the middle portion of the bottom of the stabilizing arrangement remaining, after securing, in this position in which it is displaced relative to the other parts of the arrangement while said walls of said stabilizing arrangement are subjected to bending stress and tightly engage said container while being axially slidable with respect thereto.

4,293,360

COATED SHEET MATERIAL FOR USE IN MAKING DECORATIVE LAMINATES

Fredrick A. Loft, South Windham, and John O. H. Peterson, Standish, both of Me., assignors to Scott Paper Company, Philadelphia, Pa.

Filed Nov. 16, 1978, Ser. No. 961,463

Int. Cl.³ B32B 31/00

U.S. Cl. 156—230

10 Claims

6. In a method of forming a decorative heat-and-pressure consolidated laminate by assembling between platens a plurality of superimposed plies of thermosetting resin impregnated sheets and a release medium having a transferable, glueable coating on the side of the release medium placed against an outermost ply, and applying heat and pressure through the platens to consolidate the laminate and to transfer the glueable coating from the release medium to the outermost ply, the improvement wherein the glueable coating comprises a linear copolymer of (A) maleic acid or maleic anhydride or maleic acid salt and (B) ethylene, or a vinyl monomer having one side chain of either an aliphatic group with up

to four carbon atoms or an alkoxy group with up to four carbon atoms.

4,293,361

WORK SUPPORT FOR FORMING LAMINATIONS


Ferdinando Savio, Farmingdale, and William Peterson, East Nassau, both of N.Y., assignors to Grumman Aerospace Corporation, Bethpage, N.Y.

Filed Jan. 21, 1980, Ser. No. 113,830

Int. Cl.³ B32B 31/04

U.S. Cl. 156—242

22 Claims



1. A means to mechanize the lay-up and forming of structures, said means comprising:

- a split table including movable portions operatively related to each other so as to move relatively to each other, said movable portions comprising flat surfaces adapted to move away from each other;
- a mold located between said movable portions such that said flat surfaces are on opposite sides of said mold whereby the mold will receive structures to be formed thereby as the flat surfaces move away from the mold leaving the structures to fall over the mold; and
- application rollers associated with said flat surfaces so as to be movable to expose the flat surfaces of the split table to allow deposit thereon of said structures and movable thereafter to overlay said structures at the edges of said flat surfaces adjacent said mold on opposite sides thereof to press the structures onto said mold as said flat surfaces separate and expose more and more and finally all of said mold.

4,293,362

METHOD OF FORMING DECORATIVE PANELS


Dezso D. Drobina, #204 - 25 E. 12 Ave., Vancouver, British Columbia, Canada (V5T 2G6)

Filed Dec. 10, 1979, Ser. No. 102,242

Int. Cl.³ B27M 1/08; B32B 3/14

U.S. Cl. 156—264

2 Claims



1. A method of forming decorative wooden panels comprising:

- (a) edge-gluing a plurality of long thin strips of wood in side-by-side relationship to form a single composite sheet,
- (b) cutting the sheet into pieces of predetermined size and shape wherein each piece has a portion of said plurality of strips,
- (c) gluing the pieces in edge-to-edge relationship in a predetermined pattern on a backing member, said backing member being of laminated wood construction with a central

layer of said backing member being of hard wood with the grain of said hard wood oriented at 90° to the grain of the remaining core members.

4,293,363

PANEL ASSEMBLING METHOD

Makoto Wakabayashi, Koshigaya, and Haruyoshi Takagishi, Yamato, both of Japan, assignors to Nissan Motor Company Limited, Kanagawa, Japan


Filed Jun. 4, 1979, Ser. No. 45,437

Claims priority, application Japan, Jun. 8, 1978, 53/69191; Jun. 8, 1978, 53/69192

Int. Cl.³ B29C 19/02

U.S. Cl. 156—272

4 Claims



1. A method of assembling metal panels, comprising the steps of:
 - coating a thermosetting adhesive on a connection area of a first panel;
 - matting this connection area of the first panel to the connection area of a second panel; and
 - forming an adhesive bond between the connection areas of the first and second panels, said forming being carried out by the step of heating the adhesive by passing electricity substantially only through at least one region of one of said first and second panels to heat said region so as to provide a desired degree of setting of the adhesive in said region of said one panel.

4,293,364

METHOD AND MACHINE FOR OPENING UP A CYLINDRICAL FILM TUBE AND FITTING IT OVER AN OBJECT

Masaaki Fujio, Suita, Japan, assignor to Fuji Seal Industry Co., Ltd., Osaka, Japan

Filed Sep. 4, 1979, Ser. No. 72,106

Claims priority, application Japan, Sep. 14, 1978, 53-113473


Int. Cl.³ B32B 31/02

U.S. Cl. 156—344

5 Claims

1. A method for putting a cylindrical film tube over an object, the tube being initially in a collapsed state with its opposite sides flattened together so as to be in contact, comprising the steps in the specified order of:
 - (a) contacting two vacuum suckers to the collapsed tube, one on each of its sides, in axial opposition to one another, and supplying vacuum to these suckers so that they suck and grip the tube;
 - (b) moving the suckers relative to one another in a direction which is parallel to the surfaces of the tube which they are gripping and perpendicular to the axis of said suckers, and breaking the contact of the two sides of the collapsed tube by so doing;

- (c) moving these suckers apart from one another in the direction perpendicular to the surfaces of the tube which



- they are gripping, and opening up the tube by so doing; and
- (d) putting the opened-up tube over the object.

4,293,365

APPARATUS FOR APPLYING LABELS OR THE LIKE


Joseph E. Geyser, Brentwood; Henry W. Rehr, Clayton; Rudolph W. Schutz, Walnut Creek, and Rudolf R. Weis, Antioch, all of Calif., assignors to Crown Zellerbach Corporation, San Francisco, Calif.

Filed Aug. 1, 1980, Ser. No. 174,413

Int. Cl.³ B65C 9/10, 9/14, 9/36

U.S. Cl. 156—364

9 Claims



1. Apparatus for applying items such as labels or the like to articles transported serially along a predetermined path of movement comprising:
 - storage means for said items;
 - delivery means including item retaining means for removing individual items from said storage means and bringing said items into contact with said articles;
 - applicator means including a moveable element having a contact surface forming a nip with said articles for positively engaging said items and holding them on said articles after delivery of said items to said articles by said delivery means during transport thereof; and
 - means for moving said delivery means past said applicator means with said item retaining means in close proximity to said nip and adjacent thereto, said article and contact surface cooperable to receive said item in said nip and

remove said item from said item retaining means as said delivery means moves past said applicator means.

4,293,366

PUNCHING AND BINDING MACHINE


Elmer G. Szanto, Saratoga; George Wu, San Jose, and Charles J. Ulrich, Santa Barbara, all of Calif., assignors to Velo-Bind, Inc., Sunnyvale, Calif.

Filed May 15, 1980, Ser. No. 149,997

Int. Cl.³ B42C 19/00

U.S. Cl. 156—477 B

2 Claims



1. An apparatus for binding sheets together, said apparatus being of the type having a frame having a pair of spaced sides and a platen to support said sheets, a pressure bar, cooperating means on said sides and bar for guiding movement of said bar from a first position above said platen to a second position adjacent said platen and resting on top of said sheets and actuating means for moving said pressure bar, a motor, and a shaft turned by said motor, said shaft driving said actuating means, the improvement which comprises first means on said shaft, a linkage mounted on said frame, said linkage including means connected to said pressure bar and second means to engage said first means, said first means being oriented relative to said shaft to engage said second means only after said shaft has been turned through almost a full cycle of rotation of said shaft, said second means being arranged to lift said pressure bar to first position.

4,293,367

APPARATUS FOR EFFECTING SECUREMENT OF A TRANSVERSELY MOVED ELASTIC RIBBON TO A MOVING WEB

Ladislav J. Klasek, North Riverside; Clarence F. Lamber, Country Club Hills, and Anthony Passafiume, Burbank, all of Ill., assignors to Johnson & Johnson Baby Products Company, New Brunswick, N.J.

Filed May 16, 1980, Ser. No. 150,516

Int. Cl.³ B32B 31/08


U.S. Cl. 156—494

5 Claims

5. An apparatus for securing an elastic member to a flexible web of material in a non-linear configuration, said apparatus comprising:

- (a) a pair of rotatable depositing rolls adapted to deposit said elastic member to the surface of a web traveling in a fixed path beneath said depositing rolls;
- (b) a pair of spaced apart vertical shafts;
- (c) a right angle drive at the bottom of each vertical shaft;
- (d) a frame member from which the first of said vertical shafts is mounted;
- (e) a gear train connecting the right angle drive of the first vertical shaft to the depositing rolls;
- (f) means for driving the right angle drive at the second of said vertical shafts;
- (g) a pair of timing gears mounted at the top of said vertical shafts;
- (h) a timing belt connecting said timing gears for imparting drive from the second vertical shaft to the first vertical shaft;

- (i) a cam mounted at the top of the second vertical shaft;
- (j) a cam follower cooperating with said cam and being linked to said frame member to skew the frame member and hence the first vertical shaft and the depositing rolls with respect to said flexible web of material;
- (k) slidably movable frame means from which the second vertical shaft, its right angle drive, and the frame member are mounted;



4,293,368

FILM SPLICING DEVICES

Leo Catozzo, S. Severa, Italy, assignor to Costruzione Incollatrici Rapide C.I.R. S.r.L., S. Severa, Italy


Filed Sep. 3, 1980, Ser. No. 183,712

Claims priority, application Italy, Sep. 14, 1979, 50274 A/79

Int. Cl.³ B31F 5/06; G03D 15/04

U.S. Cl. 156—506

3 Claims



1. An improved splicing device for connecting film, magnetic tape or the like, end to end with an adhesive tape (18) of the type having a base (2), a lower dieplate (8) fixed upon the base (2), a supporting wall (38) integral with said base (2) in order to rotatably sustain a roll (20) of said adhesive tape (18), an extractor (6) provided with a tape depressor (51) fastened upon a lid (4) hinged to said base (2), a lever (16) hinged in turn to said lid (4) and fitted with knives acting with the edges of said lower dieplate (8) in order to trim in coincidence with the edges of said lower dieplate (8) a piece of adhesive tape placed above film ends to be joined, and a movable bridge (24) on a fore edge of the lower dieplate (8) and a fixed bridge (22) on an opposite edge of said lower dieplate, the improvement which comprises means for moving said movable bridge (24) from a retracted position removed from said fore edge of said lower dieplate (8) to a position close to said fore edge of said lower dieplate (8), said means including a pair of tonguelets (30) on

each end of said moveable bridge (24), each said end being pressed by a respective spring (28) against a lower end of a respective pushing rod (32), which is slidable within said base (2), an upper end of each said rod projecting beyond said base (2), whereby lowering of said lid (4) upon said base, by lowering said rods (32), causes a rotatory movement of said bridge towards said fore edge of the lower dieplate (8) and lifting of the lid (4), after the shearing of adhesive tape (18) causes, under the action of the springs (28), the rotation of the movable bridge (24) away from the edge of said lower dieplate (8), thereby permitting an operator to easily grip an end (36) of adhesive tape (18) projecting from the moveable bridge (24) in order to pull it and press it against the fixed bridge (22) for any further production of a joint between other film or tape ends.

4,293,369

MACHINE FOR THE APPLICATION OF SUCTION TUBES TO PACKING CONTAINERS

Rolf M. Dilot, Lund, and Jan T. Hakansson, Eslöv, both of Sweden, assignors to Tetra Pak International AB, Lund, Sweden


Filed Jan. 23, 1979, Ser. No. 5,903

Claims priority, application Sweden, Jan. 30, 1978, 7801067

Int. Cl.³ B65B 19/34

U.S. Cl. 156—521

10 Claims



1. An apparatus for the application of suction tubes to pre-fabricated packing containers wherein said tubes are wrapped in protective casings and arranged in the form of a continuous band, said apparatus comprising:

- conveying means to convey packing containers along a predetermined path;
- supplying means to supply a continuous band of the suction tubes to a location adjacent said path;
- separating means to separate individual suction tubes from said continuous band;
- advancing means to advance said separated individual suction tubes including a rotatable element having recesses along a periphery thereof for receiving individual suction tubes;
- orienting means to orient and place said individual suction tubes in contact with a packing container, said means including sliding surfaces disposed along the periphery of the rotatable element which cooperate with suction tubes located in the recesses to displace said suction tubes to the desired position relative to the packing containers; and
- attaching means to attach said suction tubes to said packing containers.

4,293,370 METHOD FOR THE EPITAXIAL GROWTH OF BORON PHOSPHOROUS SEMICONDUCTORS

Katsuto Nagano, Yokohama; Kazuhiko Ihaya, Tokyo; Syozo Sasa, Ichikawa, and Takeshi Nakada, Tokyo, all of Japan, assignors to TDK Electronics Co., Ltd., Tokyo, Japan

Continuation of Ser. No. 6,220, Jan. 24, 1979, abandoned, which is a continuation-in-part of Ser. No. 806,858, Jun. 15, 1977, abandoned. This application Feb. 13, 1980, Ser. No. 120,993

Int. Cl.³ C30B 25/10

U.S. Cl. 156—612

4 Claims

1. A process for the epitaxial growth of boron phosphorous semiconductors having improved carrier density comprising the steps of growing the boron phosphorous semiconductors on an N-type silicon substrate having a single crystal layer, at a temperature of 880° C. to 1110° C., using a reaction gas consisting mainly of diborane and phosphorous trichloride, the constituent ratio of phosphorous trichloride to diborane being 2 to 200 in mol, and the concentration of the diborane being 2×10^{-6} to 5×10^{-3} mol/mm, wherein said substrate is a composite substrate having an N-type silicon substrate with a boron phosphide single crystal layer on the (100) plane thereof and said boron phosphide single crystal layer being formed by a hydride system of phosphine (PH₃) and diborane (B₂H₆).

4,293,371

METHOD OF MAKING MAGNETIC FILM-SUBSTRATE COMPOSITES


Milan R. Kokta, and Roger W. Taylor, both of San Diego, Calif., assignors to Union Carbide Corporation, New York, N.Y.

Filed Mar. 27, 1980, Ser. No. 134,640

Int. Cl.³ C30B 19/00

U.S. Cl. 156—624

3 Claims



1. In a method of growing a magnetic film on a garnet substrate wherein a garnet substrate of a first composition is immersed and rotated in a melt of a different composition comprising at least two different oxides which will form a film characterized by magnetic ordering in a plane substantially parallel to the surface of the melt and is withdrawn from the melt when a suitable thickness of film growth is provided on the substrate, the improvement which comprises maintaining the immersed substrate stationary in the melt after a suitable thickness of film growth is provided on the substrate for from about 0.5 seconds to 5 minutes.

4,293,372

GROWTH OF SINGLE-CRYSTAL MAGNETOPLUMBITE

Howard L. Glass, Orange, Calif., assignor to Rockwell International Corporation, El Segundo, Calif.

Filed Jul. 15, 1980, Ser. No. 168,927

Int. Cl.³ C30B 19/04

U.S. Cl. 156—624

4 Claims

1. A method of growing single-crystal magnetoplumbite, comprising the steps of: forming a fluxed melt comprising boron oxide (B₂O₃), lead oxide (PbO) and iron oxide (Fe₂O₃), wherein the mole ratio of boron oxide to lead oxide in said melt is at least about 0.06, wherein the concentration of iron oxide in said melt is at least about 15 mole percent, and wherein the concentration of iron oxide in said melt is limited to less than that which would cause the melt to have a crystallization temperature at or over 1000° C.; and cooling said fluxed melt to a temperature at or below 943° C., whereby said flux will be in a supersaturated state capable of supporting the growth of single crystals of magnetoplumbite by spontaneous nucleation, by growth on seed crystal, and by growth on a single-crystal substrate placed in contact with said melt.

4,293,373

METHOD OF MAKING TRANSDUCER

John C. Greenwood, Harlow, England, assignor to International Standard Electric Corporation, New York, N.Y.


Division of Ser. No. 43,466, May 29, 1979. This application Feb. 26, 1980, Ser. No. 124,781

Claims priority, application United Kingdom, May 30, 1978, 24186/78

Int. Cl.³ H01L 21/306

U.S. Cl. 156—628

2 Claims



1. The method of making a silicon pressure transducer, said method comprising the steps of: selectively boron doping both faces of a silicon wafer; etching one face of said wafer to define a cavity within a frame forming a closed loop and two lands spaced from each other and from said frame, said diaphragm connecting said lands; and selectively etching the other face of said wafer opposite said groove so as to define a silicon diaphragm to which both of said lands are fixed, said etching steps leaving at least two filaments having a first pair of adjacent ends fixed to one land and a second pair of adjacent ends fixed to the other land in a plane spaced from said diaphragm.

4,293,374

HIGH ASPECT RATIO, HIGH RESOLUTION MASK FABRICATION

Praveen Chaudhari, Briarcliff Manor; Ned J. Chou, Yorktown Heights; Ralph Feder, Hyde Park; Alan B. Fowler, Yorktown Heights, and James A. VanVechten, Ossining, all of N.Y., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Mar. 10, 1980, Ser. No. 128,710


Int. Cl.³ B44C 1/22; C03C 15/00, 25/06; H01L 21/425

U.S. Cl. 156—628

6 Claims

1. The process of making a high aspect ratio collimating mask comprising the step of: forming on a first thin plate of damage-trail-forming material,

a preliminary mask of particle-arresting material configured to leave unmasked regions where openings are to be formed, irradiating said first plate through said preliminary mask with particles having sufficient energy to pass through said first plate with negligible deflection and form damage trails therethrough, etching said first plate to enlarge said damage trails,



mounting a second thin plate of damage-trail-forming material spaced from and superimposed with said first plate, irradiating said second plate through said preliminary mask and the enlarged damage trails in said first plate, with particles energized sufficiently to pass through said second plate with negligible deflection and form damage trails therethrough, and etching said second plate to enlarge said damage trails.

4,293,375

METHOD OF MANUFACTURING A DEVICE AND DEVICE MANUFACTURED ACCORDING TO THE METHOD

Hans-Rudolf Neukomm, Thalwil, Switzerland, assignor to U.S. Philips Corporation, New York, N.Y.

Continuation of Ser. No. 810,088, Jun. 27, 1977, abandoned. This application Jun. 13, 1979, Ser. No. 47,979

Claims priority, application Netherlands, Feb. 7, 1976, 7607298

Int. Cl.³ H01L 21/306; C03C 15/00, 25/06

U.S. Cl. 156—643

4 Claims

1. A method of manufacturing a device with etch patterns of predetermined dimensions comprising providing a body including an underlying substrate and a surface layer having a thickness D, covering portions of said surface layer with a photolacquer mask having a thickness d, said covered portions having dimensions exceeding predetermined etch pattern dimensions by a uniform width b, plasma etching uncovered portions of said surface layer and said photolacquer mask to obtain said predetermined pattern of dimensions at said underlying substrate by laterally etching said photolacquer mask at a faster rate than said surface layer, thereby obtaining an etch profile with an inclined side having an angle α with said underlying substrate, wherein said uniform width b is at least equal to $D \tan \alpha$, and said thickness d is at least equal to $2D/\sin 2\alpha$.

4,293,376

METHOD OF PRODUCING PERFORATED GLASS PLATE

Kaspar Weingand, Dürnbach, Fed. Rep. of Germany, assignor to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany

Filed Jan. 24, 1979, Ser. No. 6,204

Claims priority, application Fed. Rep. of Germany, Jan. 24, 1978, 2802976


Int. Cl.³ B23P 15/00, 25/06; B44C 1/22; C03C 15/00

U.S. Cl. 156—644

5 Claims

1. A process for etching relatively fine size perforations in glass plates, comprising: coating opposite surfaces of glass plates with a select pattern

composed of a hydrofluoric acid-resistant metal so that glass surface areas corresponding to desired locations of perforations are free of said resist metal; and etching perforations having an average depth dimension which is greater by a factor of at least two relative to the



average lateral dimension thereof through the glass surface areas free of said resist metal by contacting said coated glass plates with a gas having hydrofluoric acid therein for a period of time sufficient to etch said perforations.

4,293,377

MANUFACTURING METHOD FOR CIRCUIT BOARD
Masanobu Miyajima, Tsuchiura, Japan, assignor to Rogers Corporation, Rogers, Conn.

Filed Jun. 27, 1979, Ser. No. 52,475

Claims priority, application Japan, Jun. 29, 1978, 53-78954

Int. Cl.³ C23F 1/02

U.S. Cl. 156—656

7 Claims



1. A method for the manufacture of a circuit board from an intermediate comprising a laminate of a non-conductive substrate and a layer of electrically conductive material secured to at least a first surface of the substrate, said method comprising the steps of:

- defining a conductor pattern on the exposed surface of the conductive layer by screen printing a hot-melt resin onto the said conductive material surface;
- curing the resin by the application of heat; and
- removing the conductive layer in areas not covered by the cured resin to form discrete conductors.

4,293,378

ENHANCED WET STRENGTH FILTER MATS TO SEPARATE PARTICULATES FROM FLUIDS AND/OR COALESCE ENTRAINED DROPLETS FROM GASES
Max Klein, 257 Riveredge Rd., Tinton Falls, N.J. 07724

Filed Jan. 10, 1980, Ser. No. 110,844

Int. Cl.³ D21H 5/18

U.S. Cl. 162—145

12 Claims

1. A glass fiber filter mat which is a wet laid, non-woven matrix of randomly arranged, haphazardly intersecting and overlapping at least at the intersections primarily glass fibers, which mat comprises, in percents by weight,

- (a) from about 64.1% to about 83.5% of glass fibers composed of from about equal parts, to all of one, of (i) glass fibers of about one inch long and of about 12 microns in diameter and (ii) glass fibers of about three-eighths inch long and about 6 microns in diameter, and providing a network thereof in a matrix, and intermingles with said glass fibers network
- (b) from about 5.5% to about 12.8% of polymer micro-bits produced from a polymer selected from the group of (i) an expanded, thermoplastic styrene-polymer, (ii) an expanded lower polyolefin from polyethylene to polymethylpentene, said polyolefin being the polymer of any of the homologs from ethylene to methylpentene, (iii) a copolymer of propylene with from about 20 to about 30 percent by weight of ethylene, (iv) a melt alloy of polyethylene

with up to about 10 percent by weight of polystyrene, (v) a melt alloy composed of at least 50 percent by weight of polypropylene and the balance being a copolymer of ethylene with up to about 30 percent (of the copolymer) being vinyl acetate, and (vi) a flexible foamed polyurethane, each said polymer being non-brittle in the form used to produce said micro-bits, said polymer micro-bits of (i) to (v) being from about 40 to about 325 microns long and from about 20 to about 325 microns wide, from substantially completely to entirely completely free of intact cells of the expanded polymer from which said micro-bits were produced, substantially without any uniformity in outline of the individual micro-bit particles, and having a density from about 85 percent of, to about substantially the same as, the specific unexpanded polymer from which there was provided the aforesaid expanded thermoplastic polymer from which said micro-bits were produced, said polymer micro-bits of (vi) being in the form of tripodal particles with generally uneven length legs, said particles being broken and inter-connected strand portions from adjacent cells of said flexible foamed polyurethane, said strand portions being substantially free of intact cell windows and having hook-like projections, indentations and flutes extending therefrom, said hook-like projections, indentations and flutes having been formed by the destruction of the cell windows of said flexible foam, and the amount of said micro-bits present in said filter mat being sufficient to provide the mat with the degree of porosity and flow-rate level required for the application wherein the mat is to be used; and comprises also

- (c) from about 2.8% to about 8.1% of polyvinyl alcohol participating as a binder in the matrix, and
- (d) from about 6.6 to about 9.5% of a cobalt composed of (i) one part of any of said polymer micro-bits intermixed with (ii) from about one to about two parts of cellulose fibers, and (iii) non-shrinkable, non-slip polymer fibers in an amount from zero to about 7% of the sum of said (i) and (ii); and
- (e) from about 3.35% to about 5.5% of a melamine-formaldehyde resin to function as a wet strength enhancing binder.

4,293,379


NEUTRON ACTIVATION ANALYSIS METHOD AND APPARATUS FOR DETERMINING SODIUM AND SODIUM COMPOUNDS IN LIQUID SAMPLES
Kerry J. Kelly, Midland, Mich., and Arthur J. Kamp, Oakley, Calif., assignors to The Dow Chemical Company, Midland, Mich.

Filed Mar. 26, 1980, Ser. No. 134,046

Int. Cl.³ G01N 23/222

U.S. Cl. 376—159

20 Claims



1. Analytical method for determining total sodium which comprises exposing sodium containing liquid sample to a neutron flux effective to produce ²³Ne radioactive gas activation product, sparging the liquid sample effective to evolve and separate from the sample a detectable concentration of ²³Ne admixed with sparging gas, flow removing said evolved gas mixture to a space remote from the neutron flux emission, monitoring said removed gas mixture for radiation emission, and quantifying based on radiation count, total sodium of the analyzed sample.

4,293,380

REACTOR AND FUEL ASSEMBLY DESIGN FOR IMPROVED FUEL UTILIZATION IN LIQUID MODERATED THERMAL REACTORS


Thomas R. Robbins, 1528 Crofton Pkwy., Crofton, Md. 21144

Filed Nov. 25, 1977, Ser. No. 854,970

Int. Cl.³ G21C 7/00

U.S. Cl. 376—209

15 Claims



1. A method for operating a liquid moderated thermal reactor which comprises:

- (a) initially irradiating with all or a portion of the fuel assemblies in the core of the reactor operating in an undermoderated boiling mode, said fuel assemblies being uranium fuel assemblies enriched with fissile uranium material, and said undermoderated condition resulting in increased production of fission plutonium with reduced uranium burn-up which increases the degree of undermoderation during said irradiation, and,
- (b) after one or more fuel cycles, converting all or a portion of said undermoderated boiling fuel assemblies to operation in a near optimum moderated non-boiling mode for the fuel composition at the time of said conversion, the undermoderated boiling mode and the moderated non-boiling mode being practiced on a system which does not rely on D₂O to shift the neutron spectrum but wherein undermoderated operation results from a low H/fuel ratio due to the initial boiling mode of operation and moderated operation results from an increased H/fuel ratio due to the subsequent non-boiling mode of operation.

4,293,381

NUCLEAR REACTOR HAVING CONTROL ROD HOLDING LATCH

Claus Goetzmann, Erlangen, and Peter Rau, Mittelehrenbach, both of Fed. Rep. of Germany, assignors to Kraftwerk Union Aktiengesellschaft, Mulheim an der Ruhr, Fed. Rep. of Germany

Continuation of Ser. No. 549,827, Feb. 13, 1976, abandoned.


This application Jul. 15, 1976, Ser. No. 705,434

Claims priority, application Fed. Rep. of Germany, Feb. 26, 1974, 2409181

Int. Cl.³ G21C 7/08

U.S. Cl. 376—230

6 Claims



1. A reactor comprising a pressure vessel containing a core and having at least one vertically movable control rod assembly having a neutron-absorbing portion adapted for vertical insertion and removal from said core and a solid rod portion

adapted to actuate the neutron-absorbing portion, said solid rod portion being surrounded by an integrally internally threaded sleeve which is vertically immovable and said solid rod portion carrying latch means engaging said screw thread with a ratchet and pawl action permitting said solid rod portion to be moved freely and rapidly towards said core so as to insert said neutron-absorbing portion into said core but positively preventing said solid rod portion from moving freely and rapidly away from said core, said sleeve and solid rod portion being relatively rotative so as to provide a screw drive for said solid portion.

4,293,382

METHOD OF STARTING UP A NUCLEAR REACTOR
Katsumi Ohsumi, and Minoru Miki, both of Hitachi, Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed Aug. 29, 1978, Ser. No. 937,863

Claims priority, application Japan, Sep. 2, 1977, 52-106149

Int. Cl.³ G21C 19/32

U.S. Cl. 376—308

14 Claims



1. A method of starting-up a nuclear reactor having a reactor pressure vessel containing cooling water therein having an oxygen content greater than 5 ppm and a fission mass in a non-critical condition comprising the steps of reducing the oxygen concentration in the cooling water of the reactor pressure vessel to a concentration less than 0.5 ppm, causing the fission mass of the nuclear reactor to become critical, and raising the water temperature to at least 150° C.

4,293,383

NUCLEAR REACTOR WITH EQUIPMENT FOR PREVENTING CONVECTION OF METAL VAPORS

Ruhama J. Lakra, Cologne; Jürgen Freund, Bonn-Bad Godesberg, and Gerd Rauschert, Bergisch Gladbach, all of Fed. Rep. of Germany, assignors to Interatom, Internationale Atomreaktorbau GmbH, Bergisch Gladbach, Fed. Rep. of Germany

Filed Mar. 7, 1978, Ser. No. 884,115

Claims priority, application Fed. Rep. of Germany, Mar. 8, 1977, 2709914


Int. Cl.³ G21C 13/06

U.S. Cl. 376—290

3 Claims

1. In a liquid metal-cooled nuclear reactor having a reactor vessel with a cover at the top thereof and being partly filled with liquid metal up to a given surface level, the liquid metal surface and the reactor-vessel cover defining therebetween a gas-filled space, at least one convection barrier permeable to the gas being disposed in said space and subdividing said space

into at least two parts, the parts of said space having respective thermal flow systems therein, said convection barrier being of



conical construction and extending across substantially an entire horizontal sectional area of the reactor vessel.

4,293,384

NUCLEAR REACTOR PLANT FOR GENERATING PROCESS HEAT

Max Weber, Wiesendangen, Switzerland, assignor to Sulzer Brothers Limited, Winterthur, Switzerland


Filed Jun. 8, 1979, Ser. No. 46,637

Claims priority, application Switzerland, Jun. 13, 1978, 6420/78

Int. Cl.³ G21C 3/56; F01K 9/00

U.S. Cl. 376—391

21 Claims



1. In combination, a nuclear reactor plant having a primary medium circuit comprising a nuclear reactor for generating a flow of heated primary working medium and a heat exchanger having a primary side to receive the flow of heated working medium and a secondary side to receive a flow of a secondary working medium in heat exchange relation with the primary working medium; and a compressor connected to said secondary side of said heat exchanger to receive a heated flow of the secondary working medium directly therefrom for heating under compression to a given temperature.

4,293,385

SECONDARY COOLANT CIRCUIT FOR NUCLEAR-REACTORS

Alain Brachet, Orsay, France, assignor to Electricite de France (Service National), Paris, France

Filed Feb. 1, 1980, Ser. No. 117,814

Claims priority, application France, Feb. 9, 1979, 79 03335; Mar. 15, 1979, 79 06595


Int. Cl.³ G21C 15/00

U.S. Cl. 376—283

15 Claims

1. A secondary coolant circuit for nuclear-reactors of the liquid-metal cooled type, said circuit comprising at least one

intermediate exchanger mounted in the vessel of said reactor, outside said vessel a steam-generator for the exchange of calories between the secondary liquid-metal flowing through said secondary circuit and water-stream, at least one pump for circulating said secondary sodium and one tank for storing said secondary liquid-metal and recovering those products generated by a possible liquid-metal-water reaction in said steam-generator, said liquid-metal being likely to occupy the lowest possible level in said tank, said secondary coolant circuit being characterized in that said tank is situated at the lowest possible



level in the nuclear installation, in that the lower extremity of the liquid-metal outlet duct of said steam-generator is directly dipped into said tank, in that, in said tank above the liquid-metal, is maintained an inert gas cover at such a pressure that it balances the liquid-metal pressure in the whole secondary loop, said tank, in addition, acting as the downstream ram-effect preventing tank for said steam-generator and as an expansion tank during the temperature variations of said liquid-metal, and in that the rotor of said pump is situated above said lowest level.

4,293,386

NUCLEAR REACTOR WITH A CYLINDRICAL REACTOR PRESSURE VESSEL

Elmar Harand, Höchststadt, and Eberhard Michel, Nuremberg, both of Fed. Rep. of Germany, assignors to Kraftwerk Union Aktiengesellschaft, Mulheim an der Ruhr, Fed. Rep. of Germany


Filed Feb. 23, 1979, Ser. No. 14,366

Claims priority, application Fed. Rep. of Germany, Feb. 24, 1978, 2808104

Int. Cl.³ G21C 13/02

U.S. Cl. 376—461

7 Claims



1. In a nuclear reactor with a cylindrical reactor pressure vessel disposed in a reactor cavity formed in a concrete biolog-

ical shield surrounding and spaced from the pressure vessel, means for suspending the reactor pressure vessel from the concrete biological shield comprising a plurality of tension bolts distributed about the periphery of the cylindrical reactor pressure vessel and secured to a corresponding plurality of brackets attached to the cylindrical reactor pressure vessel for suspending the pressure vessel from said tension bolts, said tension bolts extending from said brackets at an inclined angle through the biological shield and being anchored to the biological shield.

4,293,387

APPARATUS FOR THE SOLVENT EXTRACTION OF AROMATIC HYDROCARBONS FROM A HYDROCARBON MIXTURE


George R. Winter, III, Mt. Prospect, Ill., assignor to UOP Inc., Des Plaines, Ill.

Filed Oct. 17, 1980, Ser. No. 198,035

Int. Cl.³ B01D 11/04; C10C 3/08

U.S. Cl. 196—14.52

4 Claims



1. A multiple stage contactor column for countercurrent contact of an upwardly moving hydrocarbon phase and a downwardly moving solvent phase which comprises:

- (a) an enclosed vertically elongated shell having an overhead raffinate outlet means, an upper lean solvent inlet means, an intermediate hydrocarbon feedstock inlet means, a lower hydrocarbon reflux inlet means, and a bottom aromatic-rich solvent outlet means;
- (b) a first plurality of vertically spaced apart extraction trays traversing said shell in a horizontal plane and situated above said intermediate inlet means;
- (c) each of said first plurality of trays having an upcomer means associated therewith, and a number of uniform perforations of pre-selected cross-sectional area distributed across the contacting area thereof;
- (d) a second plurality of vertically spaced apart extraction trays traversing said shell in a horizontal plane and situated below said intermediate inlet means;
- (e) each of said second plurality of trays having an upcomer means associated therewith, and a number of uniform perforations distributed across the contacting area thereof; and
- (f) the individual perforations in said second plurality of extraction trays having a greater cross-sectional area than the individual perforations of said first plurality of extraction trays.

4,293,388 APPARATUS FOR PRODUCING ABRASION-PROOF COKE FORMS FROM BITUMINOUS COAL, BROWN COAL OR PEAT BRIQUETS

Kurt Lorenz, Hattingen; Horst Dungs, Herne; Hans B. Koenigs, Bergheim, and Roman Kurtz, Frechen, all of Fed. Rep. of Germany, assignors to Firma Carl Still GmbH & Co. KG, Fed. Rep. of Germany

Division of Ser. No. 30,939, Apr. 17, 1979, Pat. No. 4,259,157.


This application Dec. 13, 1979, Ser. No. 103,235

Claims priority, application Fed. Rep. of Germany, Apr. 27, 1978, 2818456

Int. Cl.³ C10B 1/04, 3/00

U.S. Cl. 202—126

2 Claims



1. An apparatus for treating coal and peat briquets so as to produce abrasion-proof coke forms, comprising, a vertically elongated drying shaft made up of a plurality of individual parallel spaced plate shaped radiators, each having spaced apart tubes through which a heating medium is directed, arranged so that the tubes of the various radiators of the stack are aligned vertically and they form vertical passages therebetween for briquets, means for directing the briquets downwardly into the shaft into the passages while circulating a heating medium through said heating elements of said radiators so as to indirectly preheat and predry the coke as it is falling downwardly, a carbonization shaft located below said drying shaft and receiving briquets therefrom, means for circulating a heating medium around the outside of said carbonization shaft to effect the carbonization of briquets which are directed downwardly therethrough, means for establishing a cooling zone in the lower end of said carbonization shaft for circulating cooling gas around the outside of said cooling zone, and discharge means for the briquets at the lower end of the carbonization shaft below the cooling means for the discharge of the briquets, one of said tubes of each radiator comprising a distributor header with a steam heating fluid inlet into said distributor header, the other tube of each radiator comprising a condenser header for receiving condensing fluid from each radiator and a discharge connected to said condenser header, and a protective plate disposed exteriorly of each of said inlet header and discharge header for preventing the coke from passing to the walls of said drying shaft.

4,293,389

DOOR CLOSURE CONSTRUCTION FOR SEALING THE SEALING EDGE OF A COKE OVEN DOOR IN A FRAMED COKE OVEN OPENING

Heinrich-Josef Clement, Oer-Erkenschwick, Fed. Rep. of Germany, assignor to Firma Carl Still GmbH & Co. KG, Fed. Rep. of Germany


Filed May 16, 1980, Ser. No. 150,361

Claims priority, application Fed. Rep. of Germany, May 17, 1979, 7914228

Int. Cl.³ C10B 25/06

U.S. Cl. 202-248

2 Claims



1. An improved sealing device for a coke oven of the type having an opening, a door and a door sealing frame for closing the opening, the door having a door body and a sealing edge extending along the periphery of the door body, the door sealing frame being of the type having a fixed outer frame and an inner frame inserted within and mounted to the outer frame, and the inner frame having a sealing surface adapted to sealingly receive the sealing edge of the door body, the improvement comprising means for adjustably mounting the inner frame to the outer frame in spaced-apart relationship therefrom to define a spacing therebetween, said adjusting means including screw means for detachably connecting the inner frame to the outer frame, and a plurality of spacers having unequal thickness exchangeably mounted within said spacing to maintain the inner and outer frame in said spaced-apart relationship.

4,293,390

APPARATUS FOR TREATMENT OF HYDROCARBON-CONTAINING MINERAL MATERIAL


Franklin S. Chalmers, Bethesda, Md.; Charles A. Czako, Seven Hills, and Carl J. Nelson, Lakewood, both of Ohio, assignors to Davy McKee Corporation, Cleveland, Ohio

Division of Ser. No. 857,131, Dec. 5, 1977, Pat. No. 4,200,517. This application Oct. 31, 1979, Ser. No. 90,076

Int. Cl.³ C10B 5/02, 7/06, 35/00

U.S. Cl. 202-100

9 Claims



1. Apparatus for recovering oil and fuel gases from particulate hydrocarbon-containing mineral material.

late hydrocarbon containing mineral ore in the form of discrete pieces of substantial strength, comprising a traveling gas-permeable grate, said grate having a charging location at which said pieces are deposited on the grate and a discharge location at which spent pieces are removed from the grate, means providing along said grate between said charging location and said discharging location a plurality of enclosed treating zones through which the grate travels and carries said pieces deposited thereon, said treating zones including means substantially completely preventing leakage of gas from said zones to ambient atmospheric air or leakage of atmospheric air into said zones and also preventing substantial leakage of gases between adjacent zones, said zones including a distillation zone and a coke burn-off zone, means for forming on said grate at said charging location a gas-permeable bed of substantial depth of said pieces, means for moving said grate between said charging location and said discharge location to move said pieces in said bed sequentially through said zones for sequential treatment of said pieces in said bed, means for passing heated gas through said bed and said grate in said distillation zone to heat said pieces in said bed in said zone to an oil-educting temperature and to form coke between the particles of said mineral in said pieces in said distillation zone, means for cooling the hot gases leaving said distillation zone to condense the thus-educted oil and to separate oil from said gases, means for removing and collecting hydrocarbon gas produced in said distillation zone, means for passing hot oxidizing gas in said coke burn-off zone through said grate and through said bed of oil-depleted coke-containing pieces that have passed through said distillation zone to cause combustion of said coke in said pieces and to cause substantial sintering of said pieces in said coke burn-off zone, means for cooling said spent pieces after they have left said coke burn-off zone by transferring heat from said spent pieces to said cooled gas and means for passing the thus heated gas to said distillation zone, and means for removing the spent pieces from said grate at said discharge location, said pieces having sufficient strength to form said bed and to withstand treatments in said zones without substantial breakage of said pieces.

4,293,391

CADMIUM PLATING BATHS AND METHODS FOR ELECTRODEPOSITING BRIGHT CADMIUM DEPOSITS


Valerie M. Canaris, Parma, Ohio, assignor to Rohco, Inc., Cleveland, Ohio

Filed Apr. 2, 1980, Ser. No. 136,515

Int. Cl.³ C25D 3/26

U.S. Cl. 204-50 R

1. An aqueous electroplating bath for the electrodeposition of cadmium comprising
(a) cadmium ions,
(b) a free acid,
(c) at least one non-sulfur containing organic brightener compound, and
(d) at least one thiourea compound having the formula



wherein each R is independently hydrogen or an alkyl, alkenyl or aryl group.

4,293,392

ALKYLATION OF NITRILES USING AN ELECTROGENERATED BASE AND AN ALKYLATING AGENT

Richard C. Halcher, Maryland Heights; Richard D. Goodin, St. Louis, both of Mo., and Manuel M. Baizer, Santa Monica, Calif., assignors to Monsanto Company, St. Louis, Mo.


Filed Jan. 17, 1980, Ser. No. 112,879

Int. Cl.³ C25B 3/04, 3/10

U.S. Cl. 204-59 R

4 Claims

1. A process for alkylating nitriles using an alkylating agent and an electrogenerated base comprising
(a) electro-reducing an azobenzene probase of the formula



where n is at least one and each R is branched-chain alkyl having from 3 to 6 carbon atoms with at least one R on each phenyl ring being in an ortho position, at a cathode in an electrolysis medium solvent containing a nitrile of the formula $\text{R}'\text{CH}_2\text{CN}$ wherein R' is H or hydrocarbyl having not more than 10 carbon atoms, comprising the probase, the nitrile and a supporting electrolyte to produce an electrogenerated base;
(b) deprotonating the nitrile with the electrogenerated base to produce a nitrile anion; and
(c) reacting the nitrile anion with an alkylating agent of the formula $\text{R}'\text{CH}_2\text{CH}_2\text{CH}_2\text{Z}$ wherein Z is a leaving group and R' is H, Z or hydrocarbyl having not more than 10 carbon atoms, to produce an alkylated nitrile; the aforesaid probase being more easily electro-reducible than the nitrile and producing an electro-generated base strong enough to deprotonate the nitrile which is sufficiently acidic to permit such deprotonation, and the electro-generated base not reacting readily, unless rapidly reversible, with the alkylating agent.

4,293,393

USE OF ELECTROGENERATED BASES IN CONDENSATION REACTIONS

Richard C. Halcher, Maryland Heights; Richard D. Goodin, St. Louis, both of Mo., and Manuel M. Baizer, Santa Monica, Calif., assignors to Monsanto Company, St. Louis, Mo.


Filed Jan. 18, 1980, Ser. No. 113,157

Int. Cl.³ C25B 3/02, 3/10

U.S. Cl. 204-59 R

4 Claims

1. A process for using electrogenerated bases in condensation reactions comprising
(a) electro-reducing an azobenzene probase of the formula



wherein n is at least one, each R is branched-chain alkyl having from 3 to 6 carbon atoms and at least one R on each phenyl ring must be in an ortho position, by electrolysis in an aprotic liquid electrolysis medium comprising said probase, an anhydrous aprotic solvent and supporting electrolyte to produce an electrogenerated base;
(b) deprotonating a compound of the formula




wherein X is OR'' , NR''_2 , Cl, Br, I or




R'' is hydrocarbyl having not more than 10 carbon atoms, and R' is H or hydrocarbyl having not more than 10 carbon atoms, with said electrogenerated base to produce an anion of the formula



wherein X and R' are as defined hereinabove; and,
(c) reacting said anion with a compound of the formula



wherein X and R' are as defined hereinabove, to give a condensation product of the electrolysis of the formula



wherein R' and X are as defined hereinabove; the aforesaid probase being more easily electro-reducible than the compound to be deprotonated and producing an electro-generated base strong enough to deprotonate the compound which is sufficiently acidic to permit deprotonation.

4,293,394

ELECTROLYTICALLY PRODUCING CHLORINE USING A SOLID POLYMER ELECTROLYTE-CATHODE UNIT


William B. Darlington, Portland; Donald W. DuBois, and Preston S. White, both of Corpus Christi, all of Tex., assignors to PPG Industries, Inc., Pittsburgh, Pa.

Filed Mar. 31, 1980, Ser. No. 135,960

Int. Cl.³ C25B 1/16, 1/26, 1/46, 13/04

U.S. Cl. 204-98

16 Claims



1. In a solid polymer electrolyte electrolytic cell having an anolyte compartment separated from a catholyte compartment by a solid polymer electrolyte, said solid polymer electrolyte having a permionic membrane, anode means contacting one surface thereof, and cathode means contacting the opposite surface thereof, the improvement wherein the cathode means comprise oriented particles bonded to and embedded in the permionic membrane and having a lower hydrogen evolution overvoltage catalytic area, and a higher hydrogen overvoltage non-catalytic area, the non-catalytic area being a major portion of the particle bonded to and embedded in the permionic membrane, and the catalytic area being a major portion of the particle extending outwardly from the permionic membrane.

4,293,395

PROCESS FOR ELECTROLYSIS OF AN AQUEOUS ALKALI METAL CHLORIDE SOLUTION


Tokuzo Iijima, Kobe; Yasushi Samejima, Kakogawa; Kazuo Kishimoto; Takamichi Komabashiri, both of Takasago, and Toshiji Kano, Kobe, all of Japan, assignors to Kanegafuchi Kagaku Kogyo Kabushiki Kaisha, Osaka, Japan
Division of Ser. No. 104,773, Dec. 18, 1979. This application May 9, 1980, Ser. No. 148,394

Claims priority, application Japan, Dec. 28, 1978, 53-163590; Jul. 2, 1979, 54-91757

Int. Cl.³ C25G 1/34

U.S. Cl. 204—98

3 Claims



1. Process for the electrolysis of an aqueous alkali metal chloride solution using an electrolytic cell which is partitioned by a cation exchange membrane into an anode chamber and a cathode chamber, the improvement which comprises connecting unit anode chambers with adjoining unit anode chambers through upper and lower contiguous connecting anode chamber portions, providing a gas-liquid interface having a surface area, at which halogen gas generated in the anode chamber is separated from the anolyte solution, larger than the sum total of the horizontal cross-section areas of unit anode chambers opposing to cathodes, supplying salt water into the lower connecting anode chamber portion containing substantially no halogen gas, and electrolyzing salt water under the condition that the upper connecting anode chamber portion is filled with salt water containing bubbles of halogen gas and halogen gas generated in the anode chamber.

4,293,396

THIN CARBON-CLOTH-BASED ELECTROCATALYTIC GAS DIFFUSION ELECTRODES, AND ELECTROCHEMICAL CELLS COMPRISING THE SAME


Robert J. Allen, Saugus; Robert Lindstrom, Gloucester, and Walter Juda, Lexington, all of Mass., assignors to Prototech Company, Newton Highlands, Mass.

Filed Sep. 27, 1979, Ser. No. 79,470

Int. Cl.³ C25C 1/12

U.S. Cl. 204—106

17 Claims



1. A thin electrocatalytic gas diffusion electrode comprising an open pore electrically conducting carbon cloth having a coating of a uniform mixture of catalytic carbon particles and hydrophobic binder particles evenly deposited on said cloth, with said mixture of particles adhered within the cloth pores and to the yarns of the cloth.

4,293,397

PHOTOCURABLE ORGANOPOLYSILOXANE COMPOSITIONS


Yasuhiko Sato, and Hiroshi Inomata, both of Annaka, Japan, assignors to Shin-Etsu Chemical Co., Ltd., Tokyo, Japan
Filed Feb. 8, 1980, Ser. No. 120,084

Claims priority, application Japan, Feb. 23, 1979, 54-20472
Int. Cl.³ C08F 2/46, 30/08


U.S. Cl. 204—159.13

3 Claims

1. A photocurable organopolysiloxane composition which comprises (a) 100 parts by weight of an acryloyloxy-containing organopolysiloxane represented by the general formula



where R¹ is a divalent hydrocarbon group, R² is a monovalent hydrocarbon group, X is a hydroxy group or a hydrolyzable group, k is zero or a positive integer not exceeding 4, m is a positive integer from 50 to 10,000, a is zero, 1 or 2 and at least two of the groups denoted by A in a molecule are each an acryloyloxy-containing group represented by the formula



R³ being a hydrogen atom or an alkyl group having from 1 to 4 carbon atoms and n being a positive integer from 1 to 10, the remainder of A being each a hydrogen atom, and (b) from 0.1 to 30 parts by weight of a photosensitizer.

4,293,398

PROCESS FOR CATHODICALLY ELECTRODEPOSITING POLYMERS HAVING TERTIARY AMINE OXIDE GROUPS

Paul J. Prucnal, Monroeville, Pa., assignor to PPG Industries, Inc., Pittsburgh, Pa.

Continuation-in-part of Ser. No. 8,297, Feb. 1, 1979, abandoned.
This application Oct. 23, 1980, Ser. No. 199,754

Int. Cl.³ C25D 13/06

U.S. Cl. 204—181 C

2 Claims

1. In a method of electrocoating a conductive substrate serving as a cathode, which method comprises passing an electric current between an anode and said cathode in electrical contact with a water-dispersed composition, the improvement wherein said water-dispersed composition comprises cathodically electrodepositable polymer having tertiary amine oxide groups.

4,293,399

DEVICE FOR DETECTING AND MEASURING THE CONCENTRATION OF GASEOUS HYDROGEN DISSOLVED IN A FLUID

Guy Belanger, and Gilles Missout, both of Quebec, Canada, assignors to Hydro-Quebec, Montreal, Canada

Filed Apr. 17, 1980, Ser. No. 141,048

Claims priority, application Canada, Jun. 22, 1979, 330653
Int. Cl.³ G01N 27/28, 27/46

U.S. Cl. 204—195 P

10 Claims

1. A device for detecting and measuring the concentration of gaseous hydrogen dissolved in a fluid, said fluid contained in a receptacle having a wall, said wall including means defining an aperture therein, said device providing an electrical signal indicative of said concentration, said device comprising: means for providing a base, said base including a central channel therein; means for sealingly mounting said base on said wall, said cen-

tral channel of said base in fluid communication with said aperture and said fluid in said receptacle;
a polymeric membrane in contact with said fluid and permeable to hydrogen gas, said membrane covering said central channel;

means for defining a bucket-shaped, hollow housing having a bottom, said housing including means defining an aperture in said bottom;

means for sealingly mounting said housing on said base with said polymeric membrane mounted between said housing and said base, said membrane preventing the passage of fluid and permitting the passage of hydrogen gas from said channel to and through said aperture in said hollow housing;

first and second electrodes;


means, insertable in said hollow housing, for mounting said electrodes and defining a space therebetween, said means mounting said first electrode adjacent said aperture in said hollow housing;

means defining an electrolyte, disposed at least in said space between said electrodes, capable of producing oxidation of said hydrogen gas at said first electrode and reduction of an oxygen-containing gas at said second electrode;

said electrode mounting means comprising:

a hollow, bucket-shaped container, insertable into said hollow housing, having a bottom, said container including means defining an opening in said container bottom;

means defining a cap for removably closing said container, said cap including means defining an opening therein;



a first, bucket-shaped holding element, insertable in said container, said element having a bottom, said element including means defining an opening in said element bottom;

a second, cap-shaped holding element, insertable in said container, said second holding element including means defining an opening therein, said second holding element for tightly closing said first holding element;

a third holding element, insertable in said first holding element and held by said second holding element, said third holding element including means defining a central channel therein;

means for removably mounting said cap on said container, said first electrode removably mounted between said first and third holding elements and said second electrode removably mounted between said second and third holding elements, said openings in said cap and said first holding element, said central channel in said third holding element, and said openings in said second holding element and said container combine to define a central channel disposed in said electrode mounting means with said gap opening adjacent said aperture in said hollow housing at one end and said container opening in gaseous communication with said oxygen-containing gas, said cap, container and means for removably mounting said cap on said container combining to securely sandwich said holding elements and electrodes between said cap and container, said space between said electrodes de-

fined by said central channel in said third holding element; and
means for removably fixing said electrode mounting means in said hollow housing.

4,293,400

ELECTROLYTIC TREATMENT OF WATER


James J. Liggett, 576 Crestview Dr., Twin Falls, Id. 83301

Filed Feb. 1, 1980, Ser. No. 117,490

Int. Cl.³ C02F 1/46; B01D 17/06

U.S. Cl. 204—302

6 Claims



1. Precipitating apparatus, comprising in combination an elongated, tubular housing closed at one end, a first metallic tube having a closed end disposed within said housing,

means interposed between said tube and said housing and supporting said tube with the principal longitudinal axis of said tube lying substantially parallel to the principal longitudinal axis of said housing,

a second metallic tube disposed within said first tube and having an open end disposed in proximity with said closed end of said first tube

said first and second tubes having different electrochemical equivalents,

means for introducing a liquid into said second tube,

means for removing a liquid from the space between said first and second tubes

means for applying a D.C. voltage between said first and second tubes.

4,293,401

SHALE RETORTING WITH SUPPLEMENTAL COMBUSTION FUEL


Robert P. Sieg, Walnut Creek, and Byron G. Spars, Mill Valley, both of Calif., assignors to Chevron Research Company, San Francisco, Calif.

Filed Feb. 21, 1980, Ser. No. 123,149

Int. Cl.³ C10G 1/00; C10B 49/22

U.S. Cl. 208—11 R

7 Claims



1. In a process for retorting lean oil shale wherein the process involves the steps of mixing raw oil shale with hot spent shale in the upper portion of a vertically elongated retorting vessel characterized by internal means to limit substantial vertical backmixing of solids passing downward therethrough; passing the mixture of raw shale and spent shale downward through the retorting vessel as a continuous moving bed of material; retorting the raw shale in the presence of a generally countercurrent flow of a stripping gas entering the bottom of the retorting vessel to carry away shale oil vapor and fines

present in the retorting vessel; and burning the residual carbonaceous material adhering to the retorted shale in a liftpipe to heat the spent shale, the improvement comprising concentrating said fines in a portion of the shale oil liquid product; and combusting said portion of the shale oil liquid product with the residual carbonaceous material adhering to the retorted shale.

4,293,402

HYDROCARBON HEATING


John S. Olson, Borger, Tex., assignor to Phillips Petroleum Company, Bartlesville, Okla.

Filed Mar. 10, 1980, Ser. No. 128,991

Int. Cl.³ C10G 45/04, 7/00

U.S. Cl. 208—93

5 Claims



1. A process for generating a hydrocarbon feedstream at a given input temperature comprising

- heating a hydrocarbon stream to a temperature below said input temperature to evaporate lighter hydrocarbons from said hydrocarbon stream, thus generating a hydrocarbon vapor phase;
- separating said hydrocarbon vapor phase from the remaining liquid phase of said heated hydrocarbon stream;
- super heating at least a portion of said hydrocarbon vapor phase to a temperature above said input temperature;
- mixing at least a portion of the super heated hydrocarbon vapor phase with at least a portion of the hydrocarbon liquid phase to generate a hydrocarbon feedstream, the temperatures and quantities of the hydrocarbon vapor phase and the hydrocarbon liquid phase being such that the hydrocarbon feedstream has the given input temperature;
- passing said hydrocarbon feedstream through a process zone in which it is subjected to one or more process steps and from which a process effluent stream having a temperature above that of the hydrocarbon stream is withdrawn;
- subjecting said process effluent stream to indirect heat exchange with said hydrocarbon stream such as to effect at least a portion of said evaporation of the lighter hydrocarbons from said hydrocarbon stream.

3. A process in accordance with claim 2 comprising passing at least a portion of said hydrosulfurization effluent stream into indirect heat exchange relationship with said hydrocarbon comprising stream.

4,293,403

CATALYST DEMETALLIZATION BY CONVERTING THE METAL POISONS TO A SULFUR CONTAINING METAL COMPOUND HAVING A DEFINED LOW AMOUNT OF SULFUR



Emmett H. Burk, Jr.; Jin S. Yoo; John A. Karch, and Jui-Yuan Sun, all of 400 E. Sibley Blvd., Harvey, Ill. 60426

Continuation-in-part of Ser. No. 695,602, Jun. 14, 1976, Pat. No. 4,243,550, and a continuation-in-part of Ser. No. 695,662, Jun. 14, 1976, Pat. No. 4,101,444, and a continuation-in-part of Ser. No. 695,687, Jun. 14, 1976, Pat. No. 4,102,811. This application Jan. 3, 1977, Ser. No. 756,581

Int. Cl.³ C10G 11/05, 11/00; B01J 29/38, 21/20

U.S. Cl. 208—120

40 Claims



21. In a catalytic cracking process for converting a metals contaminated hydrocarbon feedstock to more valuable, lower boiling hydrocarbon products in a cracking reaction zone wherein the cracking catalyst is poisoned and contaminated by metals including iron, nickel and vanadium present in the feedstock, the improvement which comprises

- withdrawing at least a portion of said metal contaminated catalyst from the cracking reaction zone;
- contacting at least a portion of said metal contaminated catalyst with at least one sulfur containing compound to provide a catalyst containing sulfur containing metals compounds wherein the amount of sulfur present on the resultant catalyst is about 40 to about 90% of the total amount of iron, nickel and vanadium initially present on the catalyst;
- contacting said catalyst containing sulfur containing metal compound with an oxygen-containing medium to promote subsequent metals removal by converting at least a portion of said catalyst metals to a dispersible form;
- contacting said oxygen treated catalyst with an aqueous reductive wash medium and subjecting said reductively washed catalyst to an aqueous oxidative wash to remove at least a portion of the metal poisons from the oxygen treated catalyst;
- recovering a catalyst of reduced metal poison content and improved catalytic activity; and
- returning at least a portion of said recovered catalyst to the catalytic cracking process.

27. A process as in claim 21 wherein the reductive aqueous wash medium is a solution of SO_2 in water.

37. A process as in claim 21 wherein said sulfur containing compound is hydrogen sulfide or a sulfur containing compound capable of being converted to hydrogen sulfide.

4,293,404

DEHYDROXYLATION AND/OR DEMERCAPTOLATION OF HEAVY PETROLEUM OILS

Malvina Farcasiu, Princeton, and Darrell D. Whitehurst, Titusville, both of N.J., assignors to Mobil Oil Corporation, New York, N.Y.

Filed Jul. 21, 1980, Ser. No. 170,406

Int. Cl.³ C10G 45/24, 45/28

U.S. Cl. 208—214

15 Claims

1. A process for removing phenolic oxygen and/or thiol sulfur from heavy petroleum oils which comprises:

- contacting heavy petroleum oils containing polycyclic hydroxy and/or thio aromatic compounds with effective amounts of a hydrogen donor, and a catalyst of an iron-containing porous solid, coal or coal liquefaction residue;
- heating the mixture of (a) at elevated temperatures to evolve H_2O and/or H_2S from said mixture.

4,293,405

FECAL EXAMINATION DEVICE (B)

Robert J. Greenwald, 4771 N. Federal Hwy., Pompano Beach, Fla. 33064


Continuation of Ser. No. 455,016, Mar. 26, 1974, Pat. No. 4,032,437, which is a continuation-in-part of Ser. No. 150,357, Jun. 7, 1971, abandoned, and Ser. No. 255,857, May 22, 1972, Pat. No. 3,819,045. This application Jun. 24, 1977, Ser. No. 809,928

The portion of the term of this patent subsequent to Jun. 25, 1991, has been disclaimed.

Int. Cl.³ B03B 7/00

U.S. Cl. 209—17

2 Claims



1. A knit for a fecal examining device comprising a cylindrical vessel for receiving a sample of feces introduced into the lower portion thereof and for receiving liquid flotation diluent for mixing with said sample of feces in said lower portion, said vessel being open at the top, a molded plastic strainer having open holes providing direct passage through said plastic, said strainer being constructed and arranged to be inserted through the open top of said vessel, said strainer having an integral upper portion, adapted to be held by one's hand, for manipulating said strainer to insert said strainer, through said open top, into said vessel,

the construction and arrangement being such that

- after said insertion a further quantity of liquid diluent can be added to form a convex meniscus,
- said vessel, having said inserted strainer, can stably support a microscopic slide with the lower portion of said slide being in contact with said meniscus and covering the whole area of said meniscus,

(c) said meniscus has a diameter of more than 1 cm and less than 3 cm,

(d) said unitary plastic strainer is stably positioned by contact with said vessel, and

(e) said plastic strainer serves as a barrier for passage of fecal material from the liquid below said strainer to the liquid above said strainer but permits ova to rise through said open holes to said slide, said holes having diameters of about 1 mm.

4,293,406

SYNERGISTIC PROMOTER COMBINATION FOR ZINC SULFIDE ORES

Michael F. Werneke, Orange, Conn., and James A. Jones, Viburnum, Mo., assignors to American Cyanamid Company, Stamford, Conn.

Filed Nov. 3, 1977, Ser. No. 848,162

Int. Cl.³ B03D 1/02

U.S. Cl. 209—166

2 Claims

1. A promoter combination for the froth flotation of sphalerite ores which comprises from about 25 to 75 weight percent of an iso-octyl thioglycolate and, accordingly, from about 75 to 25 weight percent of p-menthane-2,9-dithiol.

4,293,407

SIEVE DEVICE FOR SEPARATING A MIXTURE OF PARTICULATE MATERIAL IN COMPONENTS OF DIFFERENT SIZES

Jan A. K. Locker, Steenwijk, Netherlands, assignor to Machinefabriek A. Wijnveen B.V., Ede and Cooperatieve Landbouw aan- en verkoopcombinatie, B.A. "C.L.C.", Steenwijk, both of, Netherlands


Filed Oct. 10, 1980, Ser. No. 196,089

Claims priority, application Netherlands, Oct. 12, 1979, 7907587

Int. Cl.³ B07B 1/08

U.S. Cl. 209—253

15 Claims



1. Sieve device for separating a mixture of particulate material in components of different sizes, comprising a perforated sieve surface that rotates around a central, vertical shaft, said sieve surface having the shape of a hollow, truncated cone casing with a downwardly directed apex, on which an imperforate distributor cone with an upwardly directed apex has been mounted in the middle, of which distributor cone the base connects to the sieve surface, whereas the supply of the mixture to be separated takes place via a central supply tube placed above the distributor cone, whereas the removal of the coarse component takes place near the circumference of the sieve surface, wherein at least one additional sieve surface of which the diameter of the perforations differs from that of the former sieve surface, which additional sieve surface is displaceable between a non-operative position, in which it is removed from the former sieve surface and cannot receive mixture, and an operative position, in which it is placed on top of the former sieve surface and receives the supply of mixture.


4,293,408

BAR END SEPARATOR

Gary A. Herder, Kalamazoo, Mich., assignor to Prab Conveyors, Inc., Kalamazoo, Mich.
Division of Ser. No. 960,921, Nov. 15, 1978, Pat. No. 4,219,410.
This application Jan. 14, 1980, Ser. No. 111,720
Int. Cl.³ B07B 3/00

U.S. Cl. 209—638

8 Claims



1. The method of separating chips from a mixture of such chips and tramp objects heavier than said chips, said method comprising:

moving said mixture of chips and tramp objects along a generally horizontally disposed oscillating mixture feeder tray defining a conveying path and defining an aperture disposed (1) between substantially coplanar upstream and downstream regions of said path and (2) transverse to said conveying path;

conveying said mixture off of said conveying path and into a free-fall region in said aperture;

providing an abutment means at the downstream side of said aperture and along said aperture, said abutment means including a member having a contact surface for deflecting a leading portion of a tramp object to one side of said conveying path, at least a portion of said contact surface located within said aperture, one end of said contact surface being closer to said path upstream region than the other end;

deflecting a leading portion of a tramp object present in said mixture away from said downstream region of said path with said abutment member contact surface while continuing to convey the trailing portion of said object over said aperture into said free-fall region whereby the tramp object is turned at an angle with respect to said conveying path and is oriented for passage through said aperture; and providing a blower means for producing a gas stream and directing a stream of gas from said blower means through said aperture to blow said chips away from said aperture free-fall region and into a separate chip processing path while said tramp object falls through said aperture free-fall region under the influence of gravity.

4,293,409

ARTIFICIAL KIDNEY DIALYSATE PREPARATION SYSTEM

Gerhard Riede, Vellinge; Lars-Ake L. Larsson, Lödöcköpinge; Roland J. E. Andersson, Bjärred; Sven A. Jönsson, Staffanstorp, and Lars J. C. Traven, Lund, all of Sweden, assignors to Gambro AB, Sweden

Continuation of Ser. No. 841,899, Oct. 13, 1977, abandoned.

This application Nov. 28, 1978, Ser. No. 964,275


Claims priority, application Sweden, Oct. 14, 1976, 7611389
Int. Cl.³ B01D 31/00

U.S. Cl. 210—96.2

9 Claims

1. A dialysis system for treating a first fluid with dialysis fluid, the dialysis fluid being a mixture of water and dialysis concentrate, said system comprising:
a dialyzer;

a source of water;
a source of dialysis concentrate;
first fluid conducting means communicating with said source of water;
second fluid conducting means communicating with said source of dialysis concentrate;
a single pump in fluid communication with said first and second fluid conducting means for drawing water from said source of water through said first fluid conducting means, for drawing dialysis concentrate from said source of dialysis concentrate through said second fluid conduct-



ing means, and for mixing water and said dialysis concentrate prior to its introduction into said dialyzer;
third fluid conducting means for conducting said mixture of water and dialysis concentrate from said single pump to and through said dialyzer;
gas removal means in said third fluid conducting means for removing gas bubbles from said mixture of water and dialysis concentrate; and
throttling means interposed in said first conducting means; said throttling means, said single pump and said gas removal means cooperating with one another to deaerate said mixture of water and dialysis concentrate.

4,293,410

MAGNETIC FILTER


Hans Streuli, Baar, and Joseph Rüedi, Zurich, both of Switzerland, assignors to Hans Streuli AG, Baar, Switzerland
Filed Sep. 13, 1979, Ser. No. 75,031

Claims priority, application Switzerland, Sep. 21, 1978, 9892/78

Int. Cl.³ B01D 35/06

U.S. Cl. 210—107

1 Claim



1. Apparatus for filtering both magnetic and non-magnetic particles from a liquid medium comprising:

a. a chamber for receiving the liquid medium, said chamber having one wall defining a horizontal weir over which the liquid medium flows;

b. means defining a conduit for the medium passing over the weir, including:

1. a magnetic cylinder rotatable about a horizontal axis and having a surface spaced from the weir;
2. a first conduit wall section spaced from and concentric

with the surface of the cylinder, said first wall section being fixed in position and having its upper end connected to the weir, so that all the liquid medium flowing over the weir passes between the wall section and the cylinder;

3. a second conduit wall section pivotally connected to the downstream end of the first conduit wall section, said first and second sections having the same radius of curvature; and

4. means for adjusting the position of said second wall section on its pivotal connection;
5. the magnetic particles in said medium being attracted by the magnetic cylinder as they pass through the conduit and forming a beard-shaped screen effective to trap non-magnetic particles, said screen and the trapped particles cooperating to impede the flow of the medium and thereby to raise the level of the medium in the chamber; and

c. rotation control means for initiating rotation of the magnetic cylinder in a direction opposite to the direction of flow when the medium in said conduit exceeds a predetermined level, and for stopping said rotation when the medium falls below said level, said rotation control means comprising:

1. means for driving the cylinder in a direction opposite to the direction of flow of the medium; and

2. capacitive means responsive to the level of the liquid medium in the chamber and controlling the driving means to initiate rotation of the cylinder when the medium exceeds said predetermined level and to stop the rotation of said cylinder when the medium falls below said predetermined level; and

d. a stripper sheet having one end engaging the upper surface of the cylinder and slanting upwardly from said one end, for removing accumulated magnetic and non-magnetic particles from the cylinder, the upward slant of the stripper sheet being effective to allow liquid remaining in the accumulated particles to drain back into the conduit.

4,293,411

STEAM SEAL FOR DISC FILTER

Steven S. Davis, Bountiful, Utah, assignor to Envirotech Corporation, Menlo Park, Calif.

Continuation of Ser. No. 984,844, Oct. 5, 1978, abandoned,


which is a continuation of Ser. No. 783,099, Mar. 31, 1977,

abandoned. This application Jan. 24, 1980, Ser. No. 114,855

Int. Cl.³ B01D 35/18, 33/26

U.S. Cl. 210—178

1 Claim



1. An improved filter apparatus comprising a tank with upstanding sidewalls for containing slurry to be filtered, a plurality of generally circular discs, said discs being mounted spaced apart from each other on a center barrel for rotation through the slurry in the tank, each disc comprising a plurality of sectors, each sector of each disc being immersed in said slurry for a first portion of each rotation and being withdrawn from said slurry for a second portion of each rotation of said disc, means being provided to enable vacuum communication

between each sector and said center barrel so as to cause formation of a cake on a surface of each sector when the sector is immersed in said slurry, said cake comprising material to be filtered from said slurry, and means being provided for removing said cake from said surface of the sector when the sector is withdrawn from said slurry;

said filter apparatus further having means for steam drying said cake on each sector of each disc after the sector is withdrawn from said slurry and before said cake is removed from the sector, said steam drying means including:

a plurality of steam hood assemblies, each steam hood assembly defining an enclosed region above the surface of said slurry over a portion of a corresponding one of said discs, said steam hood assembly being positioned so that each sector of said corresponding disc passes through said enclosed region during part of the second portion of each rotation of said disc, and

means for introducing dry steam into said enclosed region to dry said cake on the surface of the sector as the sector passes through said enclosed region;

said steam hood assembly comprising first and second sidewalls, and a spine wall, said first and second sidewalls being spaced apart from each other to accommodate passage of said corresponding disc therebetween during said rotation of said disc, said spine wall joining said first and second sidewalls, said spine wall being curved to have an inside surface that is substantially concentric with said disc, each of said first and second sidewalls and said spine wall having a bottom edge that extends below the surface of said slurry to form a steam seal for said enclosed region along the surface of said slurry, and seals attached in opposed relation to the sidewalls so as to press sealingly against the cake material on said disc as said disc rotates, said seals extending below the surface of said slurry; wherein the improvement comprises: said seals being solely comprised of a pair of straight flexible flaps that are respectively mounted to said first and second sidewalls in opposed relationship and said flaps extending vertically from a position on said spine wall that is remote from the surface of said slurry to below the surface of said slurry on the side of said tank with respect to the center barrel from which the filter sectors rotate out of the slurry such that the center barrel is excluded from the enclosed region;

said first and second sidewalls, said spine wall and said flaps forming said enclosed region into which each sector of said corresponding disc enters immediately upon being withdrawn from said slurry, and in which each sector of said disc remains until being rotated past said flaps with said center barrel being entirely excluded from said enclosed region.

4,293,412

ANAEROBIC FERMENTER-DECANTER FOR THE PURIFICATION OF RESIDUAL WATER FROM SUGAR REFINERIES, WITH RECOVERY OF COMBUSTIBLE METHANE

Jean-Pierre Lescure, Mons-En-Baroeul, France, assignor to Syndicat National des Fabricants de Sucre de France, Paris, France


Filed Jan. 22, 1980, Ser. No. 114,426

Claims priority, application France, Jan. 24, 1979, 79 01775

Int. Cl.³ C02F 3/28

U.S. Cl. 210—179

4 Claims



1. An anaerobic fermenter-decanter for digesting and clari-

fying sludge from sugar manufacturing and refining plants and for recovering fermentation gases, said anaerobic fermenter-decanter comprising an upwardly opening inverted truncated pyramid shape tank having a substantially flat bottom wall and a fluidtight skin covering the sidewalls and the bottom wall thereof, an intake pipe passing through a heater and delivering heated sludge to the bottom of said tank adjacent an impeller carried by a vertical shaft of a rotary agitator, a flexible cover anchored at its periphery midway along the height of the side walls of the tank and extending inwardly to a central opening, said cover being tensioned between the central opening and its peripheral anchoring, a metal collecting bell having free edges adapted to be immersed in the sludge and attached at the central opening of the cover, whereby fermentation gas produced during digestion is collected at the center of the cover, an evacuation tube for removing the fermentation gas from the center of the cover, the peripheral edges of the cover and the adjacent side walls of the tank defining between them a marginal peripheral space for the flow of digested sludge upwardly to a decantation area disposed in the upper part of the tank above the cover so that the cover is entirely immersed in said tank, means for removing the digested sludge from the upper part of the tank, and means for removing clarified liquid from the upper part of the tank.

4,293,413

DIALYZER BLOOD CIRCUIT AND BUBBLE TRAPS


William J. Schnell, Wheeling, Ill., assignor to Baxter Travenol Laboratories, Inc., Deerfield, Ill.

Filed Dec. 28, 1979, Ser. No. 108,118

Int. Cl.³ B01D 31/00

U.S. Cl. 210—188

7 Claims



1. A blood dialyzer system which comprises a membrane dialyzer carried by dialysis solution delivery means, said membrane dialyzer defining a blood inlet and outlet communicating with blood flow conduits, and also defining a dialysis solution inlet and outlet communicating through solution flow conduit means with said dialysis solution delivery means, said membrane dialyzer being carried in a position whereby said blood inlet is vertically lower than said blood outlet, and said dialysis solution outlet is vertically lower than said dialysis solution inlet, and bubble trap means in direct communication with said blood outlet and blood flow conduits, said bubble trap means being attached to and carried by said membrane dialyzer, said dialysis solution delivery means being adapted to intermittently reverse the normal flow of dialysis solution through said membrane dialyzer to remove air bubbles trapped in said membrane dialyzer.

4,293,414 SLOTTED SHEET FILTER ELEMENT


Joseph F. Giannelli, Paterson, N.J., assignor to Ecodyne Corporation, Lincolnshire, Ill.

Continuation of Ser. No. 902,988, May 4, 1978, abandoned. This application Nov. 7, 1979, Ser. No. 92,047

Int. Cl.³ B01D 37/02

U.S. Cl. 210—193

15 Claims



12. In a liquid filtering apparatus including a filter tank, a plate separating said tank into an influent compartment and a filtrate compartment, at least one filter element vertically mounted in said influent compartment and having a porous tubular core, and precoat means for distributing precoat particles on each filter element, the improvement to each filter element comprising:

means for supporting the filter medium precoat, said precoat support means positioned about said tubular core and terminating a distance from an end of said tubular core so that a relatively low bubble point pressure element section is defined; and discontinuously slotted sheet means positioned over the relatively low bubble point pressure element section and sealed to said precoat support means, said discontinuously slotted sheet means having elongated slots, each slot having a width of up to about 50 microns and a length of at least about one and one-half times the width of the slot.

4,293,415

SILICA CHROMATOGRAPHIC COLUMN

Paul F. Bente, III, Landenberg, Pa.; Ernest H. Zerenner, Newark, and Raymond D. Dandeneau, Wilmington, both of Del., assignors to Hewlett-Packard Company, Palo Alto, Calif.

Filed Apr. 27, 1979, Ser. No. 34,103

Int. Cl.³ B01D 15/08

U.S. Cl. 210—198.2

23 Claims



1. A chromatographic column for separating components of sample material flowing through it, comprising a hollow tube of drawn silica of thin wall construction with a high degree of flexibility, the inner surface of said tube being coated with a stationary phase material and there being an unobstructed passage along the axis of the tube, and a coating formed on the outer surface of the tube as it is drawn for protecting the said outer surface from abrasion and moisture.


4,293,416 APPARATUS FOR TREATING PLANT EFFLUENT

Hagop Keoteklian, Islip, N.Y., assignor to Entenmann's, Inc., Bay Shore, N.Y.

Division of Ser. No. 801,375, May 27, 1977, Pat. No. 4,173,532, which is a continuation-in-part of Ser. No. 662,286, Feb. 27, 1976, abandoned, which is a continuation of Ser. No. 449,003, Mar. 7, 1974, abandoned. This application May 4, 1979, Ser. No. 35,809

Int. Cl.³ B01D 21/01

U.S. Cl. 210—208



1. A clarifier in which suspended and dissolved solids are separated from liquid waste and purified effluent is produced comprising:

- a vertically extending tank with a generally conical lower portion with the apex thereof at the bottom of the tank,
- an opaque baffle extending about the vertical axis of the tank, the baffle having a cylindrical upper portion and a frusto-conical lower portion extending outwardly and downwardly from the cylindrical upper portion toward the inner surface of the conical lower portion of the tank, the periphery of the lower portion adjacent the inner surface of the tank being spaced apart therefrom to form an annular flow passage, the interior of the frusto-conical lower portion forming a primary mixing zone, the interior of the cylindrical upper portion forming a secondary mixing zone, the region between the outer surface of the opaque baffle and the inner surface of the tank forming a clarified water zone, the primary mixing zone being in communication with said clarified water zone by the annular flow passage,
- an impeller rotatably mounted about the vertical axis of the tank, and disposed within the primary mixing zone adjacent the junction of the cylindrical upper portion of the baffle and the lower portion thereof, the impeller when actuated causing a substantially toroidal flow within primary mixing zone and extending about the vertical axis of the tank, the impeller also causing additional flow upwardly into the secondary mixing zone, outwardly therefrom into the clarified water zone, downwardly toward the annular flow passage, and back into the primary mixing zone,
- a plurality of means for the addition of reactant materials into the tank,
- a perforated plate mounted laterally adjacent the bottom of the tank for defining a sludge zone below the primary mixing zone in the tank,
- means for discharging flocs from the bottom of the sludge zone,
- a structure forming a concentration zone for trapping lighter flocs including a pair of vertically and radially extending partitions mounted in the clarified water zone, the partitions being spaced apart and extending from the frusto-conical portion of the baffle to the inner surface of the tank, and a bottom plate in the concentration zone for

isolating the concentration zone from the primary mixing zone, (h) means for withdrawing trapped flocs from the concentration zone, and (i) means for removing clarified water from the upper portion of the clarified water zone.

4,293,417
FILTER PRESS


6 Claims Murray M. Guttman, Sandy, Utah, and William L. Fisser, Verona, N.J., assignors to Envirotech Corporation, Menlo Park, Calif.

Continuation of Ser. No. 35,651, May 3, 1979, abandoned. This application Apr. 28, 1980, Ser. No. 143,991

Int. Cl.³ B01D 25/12

U.S. Cl. 210—230

6 Claims



1. An improved filter press for removing solids from liquid comprising:

- a plurality of vertically-disposed filter plates;
- a frame inclusive of a pair of horizontal filter plate support beams, said beams having an inside flange and an outside flange; and
- a pair of filter plate hanger assemblies attached to each of said filter plates, each of said hanger assemblies inclusive of a bracket and a roller rotatably attached to said bracket, said rollers positioned on said support beams to ride thereon such that said filter plates are moveably suspended from said beams, said rollers for adjacent filter plates alternating in transverse position on said beams between engagement with said outside flanges of said beams and engagement with said inside flanges of said beams such that the diameter of said rollers can be greater than the thickness of one of said filter plates.

4,293,418

FLUID SEPARATION APPARATUS


Yoshihige Fujii, Ohtsu; Syozo Nagao, Shiga, and Shunji Kumazawa, Ashiya, all of Japan, assignors to Toray Industries, Inc., Tokyo, Japan

Filed Mar. 28, 1979, Ser. No. 24,512

Int. Cl.³ B01D 31/00, 53/22

U.S. Cl. 210—321.1

18 Claims



1. A fluid separation apparatus comprising a bundle of a plurality of hollow fiber elements, each of which consists of one or two permselective hollow fibers, the fibers having an outer diameter of 50 to 600 microns and a spacer yarn composed of a textured yarn, which is spirally wound around said one or two hollow fibers wherein the apparent thickness of the

spacer yarn is 0.5 to 3 times the outer diameter of the hollow fiber, and the number of windings of spacer yarn around each hollow fiber element is 0.5 to 20 per 10 mm of the length of the hollow fiber element, said fiber element bundle being contained in the interior of a casing at a hollow fiber packing ratio of 30 to 78%.

4,293,419

HOLLOW FIBER MEMBRANE SEPARATION APPARATUS


Masaaki Sekino; Kenichi Chikanari, both of Otsu, and Tsukasa Taniyama, Kyoto, all of Japan, assignors to Toyo Boseki Kabushiki Kaisha, Japan

Filed Feb. 6, 1980, Ser. No. 119,235

Int. Cl.³ B01D 31/00

U.S. Cl. 210—321.1

4 Claims



1. A hollow fiber membrane separation apparatus which comprises:

- a pressure container composed of a cylindrical shell and end plates which seal both opening ends of the tube, respectively;
- a dividing member provided at the substantial center portion in the container which divides the container into two longitudinally aligning compartments;
- two columnar hollow fiber assemblies which are longitudinally aligning and placed in the compartments, respectively;
- each of said columnar hollow fiber assemblies having an elongate member through which fluid to be treated can flow, hollow fiber layers formed by a plurality of hollow fibers having a selective permeability to fluid axially and radially extending at the peripheral portion of the elongate member, a conduit connected to the elongate member at the end thereof faced to the dividing member, and a resin wall radially extending at the other end faced to the end plate;
- the terminals of said hollow fibers being open outward thrusting through the resin wall and said terminal openings of the hollow fibers being connected to the space formed by the surrounding wall, inner surface of the cylindrical shell and end plate;
- said dividing member having therein an inlet passage through which fluid to be treated is feeded and an outlet passage through which the fluid treated in the compartment is discharged;
- said dividing member being set within the shell with a clearance between the dividing member and the inner surface of the shell, said clearance being sealed with a plurality of sealing members so that the compartments are fluid-sealed from outside, and external pipings being directly connected to the passages in the dividing member through openings of the shell; and
- said end plate having an opening through which the fluid permeated through the hollow fiber membrane is discharged.

4,293,420

TREATMENT OF REVERSE OSMOSIS MEMBRANES

Lynn E. Applegate, Wilmington, and Charles J. Brown, Jr., Hockessin, both of Del., assignors to E. I. Du Pont de Nemours and Company, Wilmington, Del.

Filed Apr. 18, 1980, Ser. No. 141,661

Int. Cl.³ B01D 13/00

U.S. Cl. 210—500.2

6 Claims

1. In the process for storing polyamide reverse osmosis membranes by immersing the membrane in an aqueous medium, the improvement which comprises adding to the aqueous medium at least one metal ion selected from the group consisting of about from 8×10^{-4} to 8×10^{-2} moles per liter of an alkaline earth metal ion and about from 8×10^{-3} to 4×10^{-1} moles per liter of an alkali metal ion.

4,293,421

METHOD AND EQUIPMENT FOR A WRAP-AROUND UPFLOW SUBMERGED ANAEROBIC FILTER FOR SEWAGE


Alvin W. Green, 7310 85th St. N.W., Gig Harbor, Wash. 98335

Filed Apr. 30, 1980, Ser. No. 145,243

Int. Cl.³ C02F 3/28

U.S. Cl. 210—603

10 Claims



1. Equipment for the treatment of sewage comprising:

- a septic tank having an inlet for raw sewage and an outlet for effluent, an anaerobic filter composed of a bed of surface contact material including void spaces for filamentous zoogloea growth laterally surrounding said septic tank, the inner boundary of said anaerobic filter being defined by said septic tank and the outer boundary being defined by a means for retaining the surrounding earth which prevents fine aggregates in the earth from entering said anaerobic filter, an effluent discharge line connecting said outlet to a perforated distribution line outlet for distributing said effluent into said anaerobic filter at approximately the lowest elevation in said anaerobic filter, a perforated discharge riser positioned diametrically opposite said distribution line outlet for collecting effluent which has passed through the filter, overflow weirs positioned on said effluent discharge line and said discharge riser for bypassing the filter and directing said effluent from said outlet to said discharge riser, said overflow weirs being connected to a vent system for venting the gaseous products produced in said anaerobic filter, and means for connecting said discharge riser to a final treatment system.
- 8. A method for treatment of effluent discharged from a septic tank prior to delivery of the effluent to the final treatment phase comprising the steps of:
 - directing said effluent from said septic tank through an effluent discharge line into a perforated distribution line outlet at approximately the lowest elevation in an upflow anaerobic filter laterally surrounding said septic tank, said anaerobic filter composed of a bed of surface contact material including void spaces for filamentous zoogloea growth, the inner boundary of said anaerobic filter being defined by said septic tank, and the outer boundary being defined by a means for retaining the surrounding earth which prevents fine aggregates in the earth from entering

the filter, passing said effluent upwardly and horizontally through said void spaces to contact said filamentous zoogloea growth, collecting said effluent which has passed through the filter in a perforated discharge riser positioned diametrically opposite said distribution line outlet to maximize the detention time of said effluent in the filter, directing the collected effluent to a final treatment phase, continuously venting gaseous products produced in said anaerobic filter through overflow weirs positioned on said effluent discharge line and said discharge riser into a vent system, bypassing said anaerobic filter by directing said effluent from said septic tank through said overflow weirs into said discharge riser when the filter becomes clogged, and washing the filter to restore the flow of said effluent through the filter.

4,293,422

FLASH CHROMATOGRAPHY

W. Clark Still, 560 Riverside Dr., New York, N.Y. 10027

Filed Jul. 5, 1979, Ser. No. 54,982

Int. Cl.³ B01B 15/08

U.S. Cl. 210—656

3 Claims



1. A method of adsorption chromatography for separation of organic compounds in liquid solvent therefor, which includes:

- a. establishing an horizontally confined, vertically defined bed of adsorbent particles having a horizontally confined zone thereabove,
- b. placing said liquid solvent in said zone above said bed,
- c. applying positive gas pressure to said solvent above said bed to wet said bed whereby and until gases entrapped in said bed are driven out of said bed,
- d. lowering the level of solvent to the upper level of said bed,
- e. placing said solvent containing said compounds in said zone above said bed,
- f. applying positive gas pressure to said solvent containing said compounds above said bed to drive said solvent and compounds into said bed while withdrawing solvent displaced from said bed from beneath said bed,
- g. placing solvent (eluant) in said zone above said bed,
- h. applying positive gas pressure to said eluant above said bed to drive said eluant into said bed at a rate in excess of 1.0 inches per minute, and
- i. withdrawing from beneath said bed and separating into fractions eluant containing said compounds displaced from said bed.

4,293,423

PROCESS AND APPARATUS FOR ION EXCHANGE BY USE OF THERMALLY REGENERABLE RESIN


Kenji Kosaka, Mitaka; Takeshi Iwatsuka, Funabashi; Ikuro Shindo, Mitaka, and Akira Hotogi, Ichikawa, all of Japan, assignors to Rohm and Haas Company, Philadelphia, Pa.

Filed Oct. 18, 1977, Ser. No. 843,197

Int. Cl.³ B01D 15/04

U.S. Cl. 210—676

16 Claims



1. A process for continuous ion exchange treatment utilizing a column packed with a single bed of heterogeneous thermally regenerable ion exchange resin, said bed having a regeneration zone in the upper portion of the bed, a loading zone in the lower portion of the bed, and a heat displacement zone between said regeneration and loading zones for minimizing heat dispersion, said process comprising the steps of:

- (a) flowing an aqueous feed liquid having an undesirably high concentration of ions upwardly through said loading zone to substantially reduce the concentration of ions, and withdrawing resultant treated liquid as product liquid from the vicinity of the top of the loading zone with the remainder of product liquid flowing upwardly into the heat displacement zone;
- (b) flowing an aqueous liquid regenerant at a higher temperature than the temperature of the feed liquid, through the resin in the regeneration zone to regenerate the resin;
- (c) controlling the flow of aqueous liquid in the heat displacement zone to the extent necessary to maintain a temperature differential between the loading zone and the regeneration zone;
- (d) transferring loaded resin from the loading zone to the regeneration zone; and
- (e) displacing regenerated resin downwardly in said column to replace said transferred resin.

4,293,424

PROCESS FOR CLEANING ROLLING LUBRICANT

Rudolf Baur; Emil Merki, and Hanspeter Krähenbühl, all of Kreuzlingen, Switzerland, assignors to Swiss Aluminium Ltd., Chippis, Switzerland

Continuation of Ser. No. 672,061, Mar. 31, 1976, abandoned.

This application Sep. 19, 1977, Ser. No. 834,130

Claims priority, application Switzerland, Apr. 10, 1975, 4554/75


Int. Cl.³ B01D 21/01

U.S. Cl. 210—737

10 Claims

1. A process for cleaning a rolling lubricant oil contaminated with fine particles of aluminum which consists essentially in: heating a stream of said oil;

mixing into said stream a stream of aqueous alkali metal carbonate solution having a pH above 9 and having a concentration of about 150 to about 250 grams of Na_2CO_3 per liter, wherein the ratio of said contaminated oil to said



solution is about 400 to 1200 liters of said oil to about 0.5 to about 1.5 liters of said solution, thereby coagulating said particles in said stream; and removing said coagulated particles from said oil to provide cleaned rolling lubricant.


4,293,425

METHOD OF CHLORINATING SWIMMING POOLS AND THE LIKE

Kenneth E. Price, 1534 Channelwood Dr., Whittier, Calif. 90601, assignor to Kenneth E. Price, Whittier, Calif. Division of Ser. No. 906,673, May 15, 1978, Pat. No. 4,210,624, which is a continuation of Ser. No. 735,964, Oct. 27, 1976, abandoned. This application Jan. 14, 1980, Ser. No. 112,097

Int. Cl.³ E04H 3/20

U.S. Cl. 210—754



1. A method of chlorinating water in a swimming pool and the like comprising the steps of

- providing an openable airtight chamber having a water inlet to and a water outlet from the chamber at the bottom therein, the outlet being equipped with a check valve operable to prevent flow of water into the chamber through the outlet, the inlet being equipped with a closable water flow regulating valve,
- connecting the chamber into a water circulation system for a swimming pool and the like, which system includes a pump, so that the inlet and the outlet are connected to separate points in the system and the inlet is connected to a point at which water in the system, during operation of the pump, is at a higher pressure than the point to which the outlet is connected,
- initially loading a quantity of dry water-soluble chlorinat-

ing material into the chamber at a time when the pump is not operating, the regulating valve is closed, and the chamber is dry, and then sealing the chamber in an airtight manner to entrap air in the chamber with said material,

(d) operating the pump and opening the regulating valve to establish a desired water flowrate into and through the chamber and to cause the air entrapped in the chamber to be compressed in the upper portion of the chamber by an amount related to the pressure of water applied to the chamber through the inlet,

(e) the air in the chamber expanding therein to force water from the chamber during periods when the pump is not operating, and

(f) periodically, as needed, recharging chlorinating material into the chamber by a procedure which includes the steps of

- interrupting operation of the pump, and closing the regulating valve to enable air entrapped in the chamber to force water from the chamber through the outlet,
- opening the chamber and introducing a desired quantity of chlorinating material into the chamber,
- closing the chamber in an airtight manner to entrap air therein as aforesaid,
- opening the regulating valve to re-establish the desired water flowrate into and through the chamber, and
- re-establishing operation of the pump.

4,293,426

COATED CALCIUM PEROXIDE PARTICLES USEFUL IN THE TREATMENT OF WATER

Ignace Gago, Braine-l'Alleud, Belgium, assignor to Interlox, Brussels, Belgium

Filed Nov. 17, 1978, Ser. No. 961,699

Claims priority, application Luxembourg, Nov. 18, 1977, 78545

Int. Cl.³ C02F 1/72; B32B 19/04; B05D 7/00

U.S. Cl. 210—759

30 Claims

1. Solid particles comprising calcium peroxide, and a coating agent coating the calcium peroxide, said coating agent being predominantly a water-insoluble solid compound which is an organic polymer or an inorganic compound, said water-insoluble solid compound having a solubility in water of less than 1% by weight and a melting point of at least 50° C.

13. Process for the production of solid particles in a medium containing, the solid particles comprising calcium peroxide and a coating agent coating the calcium peroxide, said coating agent being predominantly a water insoluble solid compound having a solubility in water of less than 1% by weight and a melting point of at least 50° C., comprising spraying a solution, emulsion or suspension of a composition forming the coating agent in a liquid medium onto moving calcium peroxide granules, and evaporating the liquid medium.

14. Process for the oxygenation of water, comprising treating each m³ of water with 0.05 to 1,000 g of solid particles comprising calcium peroxide and a coating agent coating the calcium peroxide, said coating agent being predominantly a water insoluble solid compound having a solubility in water of less than 1% by weight and a melting point of at least 50° C.

4,293,427

DRILLING FLUID CONTAINING A COPOLYMER FILTRATION CONTROL AGENT

James M. Lucas; Dorothy P. Enright, and Alphonse C. Perricone, all of Houston, Tex., assignors to Milchem Incorporated, Houston, Tex.

Continuation-in-part of Ser. No. 19,219, Mar. 9, 1979, abandoned. This application Mar. 18, 1980, Ser. No. 131,329

Int. Cl.³ C09K 7/02

U.S. Cl. 252—8.5 C

25 Claims

13. An aqueous drilling fluid comprising water, a clayey substance suspended in said water, and at least about 0.25 pounds per 42 gallon barrel of a copolymer of: (a) from be-

tween about 8 mole percent and about 70 mole percent of a (meth) acrylamido alkyl sulfonic acid or alkali metal salt thereof; and (b) from between about 30 mole percent and about 91 mole percent of a (meth) acrylamide or N-alkyl (meth) acrylamide, a 0.5% by weight aqueous solution of said copolymer having a viscosity of about 25° C. of from between about 18 centipoises and about 44 centipoises, as determined at a shear rate of 511 reciprocal seconds, the number of carbon atoms in the alkyl portion of the acrylamidoalkyl sulfonic acid or alkali metal salt thereof being about four, and the number of carbon atoms in the alkyl portion of the N-alkyl (meth) acrylamide being from between about 1 and about 3.

4,293,428

PROPOXYLATED ETHOXYLATED SURFACTANTS AND METHOD OF RECOVERING OIL THEREWITH

Walter W. Gale; Maura C. Puerto, both of Houston; Thomas L. Ashcraft, Baytown; Rhoderick K. Saunders, Sinton, and Ronald L. Reed, Houston, all of Tex., assignors to Exxon Production Research Company, Houston, Tex.


Filed Jan. 18, 1978, Ser. No. 870,313

Int. Cl.³ C09K 3/00

U.S. Cl. 252—8.55 D

26 Claims

1. A method for recovering oil from an oil-bearing formation which comprises injecting into said formation a fluid containing an effective amount of surface-active agent having the general formula:



wherein

R_1 is a linear or branched alkyl radical, an alkenyl radical, or an alkyl or alkenyl substituted benzene radical, the non-aromatic portion of the radical containing from 6 to 24 carbon atoms;

m has an average value of from about 1 to about 10;

n has an average value of from about 1 to about 10;

Y is a sulfate, sulfonate, phosphate, or carboxylate group; and

X is a cation; and

driving said fluid through said formation to displace oil from said formation and recovering the displaced oil.

4,293,429

MGO DISPERSIONS

William J. Cheng; David B. Guthrie, and Donald M. Leindecker, all of St. Louis, Mo., assignors to Petrolite Corporation, St. Louis, Mo.

Filed Jan. 16, 1980, Ser. No. 112,495

Int. Cl.³ C10M 1/24, 3/18, 1/10; C10L 1/18

U.S. Cl. 252—18

12 Claims

1. A process of preparing a stable, fluid magnesium oxide containing dispersion which comprises heating MgO powder at a temperature greater than 230° C. in a relatively stable, relatively non-volatile process fluid capable of being heated to a temperature greater than about 230° C. in the presence of less than a stoichiometric amount of carboxylic acid, based on MgO, whereby the carboxylate is formed in situ and decomposes to form said MgO.

4,293,430

SULFURIZED METALLIC DITHIOPHOSPHATES AND THEIR USE AS ADDITIVES FOR LUBRICATING OILS

Georges Rivier, Bron, France, assignor to Orogil, Courbevoie, France

Filed Feb. 29, 1980, Ser. No. 126,161

Claims priority, application France, Mar. 9, 1979, 79/06059


Int. Cl.³ C10M 1/48, 1/38, 3/42, 3/32

U.S. Cl. 252—32.7 E

12 Claims

1. A sulfurized metallic dithiophosphate comprising the product obtained by sulfurization of a composition containing:

(A) from about 100 to 20 percent of a metallic dithiophosphate of formula (I);



in which formula:

R_1 represents:

(a) a linear or branched alkenyl radical containing from about 2 to 24 carbon atoms;


(b) an unsaturated cycloaliphatic or polycycloaliphatic radical containing from about 3 to 20 carbon atoms;

R_2 and R_3 are similar or different and represent an alkyl radical containing from about 1 to 12 carbon atoms;

m represents the valence of the metal M;

M represents a metal of group IIB, IIIB, IVB, or VIII of the Periodic System of the Elements; and

(B) from about zero to 80 percent of an alkyl ester of formula (II):



in which:

R_4 represents a linear or branched alkenyl radical containing from about 2 to 24 carbon atoms, and R_5 represents an alkyl radical containing from about 1 to 12 carbon atoms, by means of a sulfurization agent in an amount corresponding to a weight of sulfur of between about 0.5 and 10 percent, referred to the weight of composition to be sulfurized.

11. A novel lubricating composition comprising a major proportion of at least one lubricating oil and between about 0.3 and 15 percent by weight of a sulfurized metallic dithiophosphate according to claim 1.

4,293,431

PROCESS OF PREPARING METALLIC DETERGENT-DISPERSANT ADDITIVES OF HIGH ALKALINITY IN PARTICULAR FOR LUBRICATING OILS, AND PRODUCT OBTAINED THEREBY

Bernard Demoures, Puteaux, and Jean-Louis Le Coent, Le Havre, both of France, assignors to Orogil, Courbevoie, France

Filed Jun. 19, 1979, Ser. No. 49,959

Claims priority, application France, Jun. 26, 1978, 78 18946

Int. Cl.³ C10M 1/40

U.S. Cl. 252—33.2

18 Claims

1. A process of preparing metallic detergent-dispersant compositions from alkylbenzene sulfonates of alkaline earth metals, alkylphenols, and alkaline earth compound, an alkylene glycol and carbon dioxide, which process comprises:

(1) reacting sulfur with an alkylphenol bearing at least one C_6-C_{60} alkyl substituent in the presence of a dilution oil, an alkaline earth metal alkylbenzene sulfonate of a molecular weight greater than about 300 and TBN less than or equal to about 150, an alkaline earth metal compound, optionally an alkali metal hydroxide, a base component of a metallic detergent-dispersant of a TBN greater than or equal to about 200 selected from among superalkalinized and sulfurized alkaline earth metal alkylphenates, alkylbenzene sulfonates of alkaline earth metals and mixtures of superalkalinized sulfurized alkylphenates of alkaline earth mixtures and alkylbenzene sulfonates of alkaline earth metals, and an alkylene glycol, at a temperature of between about 100 and 190° C., employing the following quantities of reagents:

- at least about 5 parts by weight of alkylphenol for 100 parts by weight of mixture of alkylphenol plus alkylbenzene sulfonate;
- up to about 95 parts by weight of alkylbenzene sulfonate

- for 100 parts by weight of mixture of alkylphenol plus alkylbenzene sulfonate;
- (c) from about 1 to 18 parts by weight of sulfur for 100 parts by weight of mixture of alkylphenol plus alkylbenzene sulfonate;
- (d) from about 4 to 45 parts by weight of alkaline earth compound for 100 parts by weight of mixture of alkylphenol plus alkylbenzene sulfonate;
- (e) up to about 10 parts by weight of alkali metal hydroxide for 100 parts by weight of mixture of alkylphenol plus alkylbenzene sulfonate;
- (f) from about 2 to 35 parts by weight of said base component for 100 parts by weight of mixture of alkylphenol plus alkylbenzene sulfonate; and
- (g) from about 8 to 200 parts by weight of alkylene glycol for 100 parts by weight of mixture of alkylphenol plus alkylbenzene sulfonate.
- (2) carbonating the resultant mixture by means of carbon dioxide at a temperature of between about 100 and 200° C., the amount of CO₂ being between that which can be completely absorbed and an excess of 30% of said amount;
- (3) removing the alkylene glycol; and
- (4) separating the metallic detergent-dispersant of high alkalinity thus obtained.

4,293,432

LUBRICATING OIL COMPOSITION

Andrew G. Papay, Manchester, and Joseph P. O'Brien, Kirkwood, both of Mo., assignors to Ethyl Corporation, Richmond, Va.

Filed Oct. 18, 1979, Ser. No. 85,968

Int. Cl.³ C10M 1/46, 1/36, 3/40, 3/20

U.S. Cl. 252—49.9

8 Claims

1. A lubricating oil composition formulated for use in the crankcase of an internal combustion engine, said composition containing an ashless dispersant and a friction-reducing amount of about 0.1–1.5 weight percent of a product consisting mainly of N-(2-hydroxyethyl)fatty acid amide wherein said fatty acid contains about 12–22 carbon atoms.

4. A lubricating oil composition of claim 1 also containing about 0.005–0.75 weight percent of a di-C₁₄ alkyl C_{12–36} aliphatic hydrocarbylphosphonate.

4,293,433

PERCHLOROETHYLENE DIELECTRIC FLUID CONTAINING PYRROLE AND PHENOL

Jack A. Borrer, Chesterland, and Edward A. Rowe, Jr., North Perry, both of Ohio, assignors to Diamond Shamrock Corporation, Dallas, Tex.

Filed Jun. 2, 1980, Ser. No. 155,070

Int. Cl.³ H01B 3/18, 3/24

U.S. Cl. 336—94

14 Claims

8. A dielectric fluid composition which is resistant to decomposition at elevated temperatures in the presence of oxygen, comprising perchlorethylene containing less than about 0.005 percent chlorinated ethanes, and a synergistic mixture of N-methyl pyrrole and p-tertiary amyl phenol.

4,293,434

LIQUID CRYSTAL COMPOUNDS

Hans-Joachim Deutscher, Halle; Herrmann Schubert, Nehlitz; Christina Seidel, Halle; Dietrich Demus, Halle, and Horst Kresse, Halle, all of German Democratic Rep., assignors to VEB Werk für Fernsehelektronik Berlin im VEB Kombinat Mikroelektronik, Berlin-Oberschöneweide, German Democratic Rep.

Continuation-in-part of Ser. No. 877,557, Aug. 8, 1978, abandoned. This application Feb. 13, 1979, Ser. No. 11,952



Int. Cl.³ C09K 3/34; G02F 1/13

U.S. Cl. 252—299.63




2 Claims

1. Nematic composition for electro-optical devices for the modulation of transmitted or incident light and the rendition of numbers, symbols and images, or as orientation medium in

spectroscopy and gas chromatography comprising liquid crystalline compounds, non-liquid crystalline dyestuffs and at least one compound having the following general formula:




wherein

R¹ equals C_nH_{2n+1} with n being 1 to 9;R² equals C_nH_{2n+1}— or C_nH_{2n+1}O— when X isand R² equals C_nH_{2n+1}O— or —CN when X isR³ equals —CH₃, —C₂H₅, —Cl or —Br; andR and R⁴ each equals C_nH_{2n+1} or C_nH_{2n+1}O—, with n being 1 to 9 and

represents cyclohexyl.

2. The compound having the formula:



4,293,435

LIQUID-CRYSTALLINE POLYMER PHASE HAVING A CHOLESTERIC STRUCTURE, PROCESSES FOR ITS PREPARATION AND ITS USE

Michael Portugall, Eltville; Heino Finkelmann, Clausthal-Zellerfeld, and Helmut Ringsdorf, Mainz-Gonsenheim, all of Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Fed. Rep. of Germany

Filed Jul. 19, 1979, Ser. No. 58,943

Claims priority, application Fed. Rep. of Germany, Jul. 20, 1978, 2831909


Int. Cl.³ C09K 3/34; G02F 1/13

U.S. Cl. 252—299.01





9 Claims

1. A composition of matter exhibiting a liquid-crystalline cholesteric polymer phase consisting essentially of (1) at least one copolymer which contains (a) nematogenic units of the formula (I)


-continued






where R₁ is hydrogen or methyl, n is an integer from 1 to 6 and R₃ is



where Z is COO— or OCO—, R₂ is —O(CH₂)_mH, —(CH₂)_mH or —COO—(CH₂)_mH, m being an integer from 1 to 6, and R₇ is hydrogen or R₂, and (b) chiral units of the formula (II)



in which R₁ is hydrogen or methyl, n is an integer from 1 to 10 and R₄ is



where Z is COO— or OCO— and R₅ is —CH=N—R₆, —OR₆, —COOR₆, —CH=CH—COOR₆ or —R₆, R₆ being alkyl or alkaryl of 4 to 10 carbon atoms and having at least one asymmetric carbon atom or (2) a mixture of (a) a polymer having a nematic structure and containing units of the formula (I) and (b) a compound having a chiral structure.

4,293,436

AUTOFLUOROGRAPH AND COMPOSITION AND METHOD FOR MAKING THE SAME

Dennis L. Fost, Franklin, Mass., assignor to New England Nuclear Corporation, Boston, Mass.

Filed Mar. 30, 1979, Ser. No. 25,653

Int. Cl.³ C09K 11/06

U.S. Cl. 252—301.1 R

38 Claims

1. A method of impregnating an autofluorographic medium for use in an autofluorographic method comprising impregnating an absorbent or adsorbent autofluorographic medium with at least 0.01% by weight of a fluor in a solution having between 47.5 and 95% by weight of a water-soluble or water-miscible carboxylic acid carrier.

4,293,437

PROCESS FOR THE TREATMENT AND PACKAGING OF LOW OR AVERAGE ACTIVITY RADIO-ACTIVE WASTE

Jean Taponier, Asnieres sur Seine, and Rene Pierlas, Antony, both of France, assignors to Societe Generale pour les Techniques Nouvelles S.G.N., Montigny le Bretonneux, France

Filed Apr. 9, 1979, Ser. No. 28,453

Claims priority, application France, Apr. 13, 1978, 78 10963; Jul. 13, 1978, 78 20988

Int. Cl.³ G21F 9/16

U.S. Cl. 252—301.1 W

7 Claims

1. A process for the treatment of low- and average-activity radioactive waste comprising:

- (a) obtaining a homogeneous mixture of effluents containing said waste,
- (b) forming from said mixture a stable suspension of precipitated solid matter by precipitation of radioactive compounds,
- (c) adjusting the quantity of said solid matter to between about 40 to 400 grams per liter of precipitated suspension and adding from about 0.2 to 6 grams per liter of alkaline silicate, and a quantity of asbestos fibers such that the final mixture obtained in step (d) below comprises from about 0.5 to 5% by weight of asbestos fibers with respect to cement,
- (d) adding to said suspension from about 0.6 to 2 parts by weight of cement for each part by weight of said suspension, so as to obtain a homogeneous mixture, and
- (e) casting said homogeneous mixture into a container.

4,293,438

METHOD OF PROCESSING RADIOACTIVE WASTES

Friedrich-Wilhelm Ledebink, Maintal; Wolfgang Stoll, Hanau, and Dieter Schäfer, Aschaffenburg, all of Fed. Rep. of Germany, assignors to Alkem GmbH, Hanau, Fed. Rep. of Germany

Filed Jan. 30, 1980, Ser. No. 116,933

Claims priority, application Fed. Rep. of Germany, Feb. 7, 1979, 2904627

Int. Cl.³ G21F 9/30

U.S. Cl. 252—301.1 W

6 Claims

1. Method for treating solid raw wastes containing as a major component plastic soluble in a liquid organic solvent, a minor component of a solid material insoluble in the liquid

the coated net in a solution of a salt of an active component, and drying and baking the immersed body.

4,293,448

PREPARATION OF A CATALYST CARRIER FROM ALUMINA MIXTURES

Peter R. Laurer, Ludwigshafen, Fed. Rep. of Germany, assignor to BASF Aktiengesellschaft, Fed. Rep. of Germany
Filed Nov. 27, 1979, Ser. No. 97,836
Claims priority, application Fed. Rep. of Germany, Dec. 7, 1978, 2852947

Int. Cl.³ B01J 21/04

U.S. Cl. 252—463 4 Claims

1. A process for the preparation of a very hard catalyst carrier from a mixture of aluminum oxides which comprises pretreating α -Al₂O₃ with an acid, base and/or metal salt solution, mixing the pretreated α -Al₂O₃ with at least one member selected from the group consisting of γ -Al₂O₃, χ -Al₂O₃, transition oxides of aluminum or hydrated aluminum oxides, kneading the mixture with the addition of water, extruding the resulting mass and drying and heating the extrudate to form the desired catalyst carrier.

4,293,449

HIGH-SURFACE AREA COATED SUPPORT FOR CATALYSTS AND PROCESS FOR THEIR PREPARATION

Daniel R. Herrington, Bainbridge, and Albert P. Schwerko, Solon, both of Ohio, assignors to The Standard Oil Company, Cleveland, Ohio

Filed Aug. 7, 1980, Ser. No. 176,215

Int. Cl.³ B01J 21/04, 23/88

U.S. Cl. 252—465 7 Claims

1. A process for preparing a high-surface area catalyst support, the process comprising:

- partially wetting an inert core with a wetting agent,
- applying a powdered high-surface area coating to the inert core,
- drying and calcining the coated core to form a support, and
- adding catalytic elements to the support.

4,293,450

PROCESS FOR CONDUCTING ELECTRICITY UTILIZING A SPECIFICALLY DEFINED GRAPHITE INTERCALATION COMPOUND

F. Lincoln Vogel, R.D. 3, Voorhees Rd., Whitehouse Station, N.J. 08889

Filed Apr. 18, 1978, Ser. No. 897,443

Int. Cl.³ H01B 1/04

U.S. Cl. 252—503 30 Claims

1. A process for conducting electricity comprising providing an electrically conductive composition which comprises a graphite intercalation compound formed under anhydrous conditions of:

- graphite,
- a sulfur-containing reactant selected from the group consisting of fluorosulfonic acid, chlorosulfonic acid, and mixtures thereof, and
- a halide reactant selected from the group consisting of a boron trihalide, a tetrahalide of a Group IV element, a pentahalide of a Group V element, and mixtures thereof, wherein the molar ratio of said sulfur-containing reactant to said halide reactant is within the range of approximately 0.01:1 to 200:1, and connecting an electrical source to said electrically conductive composition.

4,293,451

SCREENABLE CONTACT STRUCTURE AND METHOD FOR SEMICONDUCTOR DEVICES

Bernd Ross, 2154 Blackmore Ct., San Diego, Calif. 92109
Continuation-in-part of Ser. No. 913,872, Jun. 8, 1978, Pat. No. 4,219,448. This application Dec. 27, 1979, Ser. No. 107,657

Int. Cl.³ H01B 1/02, 5/14

U.S. Cl. 252—512 25 Claims

1. A method of fabricating an electrical contact upon a substrate, comprising the steps of screening a metal frit ink comprising a metal powder and a metal frit in a predetermined pattern upon said substrate, said ink containing a fluxing agent capable of dissolving insulating substances on said substrate, dissolving any insulating substances present on said substrate by activating said fluxing agent, and sintering said ink by firing to a temperature above the melting point of the metal frit and below the melting point of the metal powder to create a coherent metal contact.

3. A metal powder composition for deposition and firing upon a substrate, comprising a screenable metal powder, a binder, a vehicle, a metal frit for use as a liquid medium to transport the metal powder in a liquid sintering process and thereby create a coherent metal structure, and a fluxing agent comprising silver fluoride for dissolving insulating substances from said substrate.

4,293,452

ELECTRICALLY CONDUCTIVE POLYMERIC COMPOSITIONS

Robert B. Fox, Washington, D.C., and Oh-Kil Kim, Burke, Va., assignors to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Jan. 31, 1980, Ser. No. 117,162

Int. Cl.³ H01B 1/06

U.S. Cl. 252—518 7 Claims

1. An electrically conductive polymeric composition consisting essentially of a polymer selected from the class consisting of polycarbonates and poly(alkyl alkacrylates) wherein the alkyl radicals have from one to 10 carbons and, dispersed therein, an effective amount of a crown ether complex represented by the formula:



wherein m is 1 or 2, n is 0 or 1, TCNQ is 7,7,8,8-tetracyano-p-quinodimethane, M is selected from the group consisting of lithium, sodium, potassium, rubidium, cesium, strontium, and barium, and (OA)_x is a macrocycle wherein x is an integer from 4 to 10, 0 represents oxygen and A is a bivalent hydrocarbon radical having from 2 to 8 carbon atoms in which the free valences are separated by two carbon atoms.

4,293,453

PROCESS FOR USING BRIDGED KETONES IN AUGMENTING OR ENHANCING THE ORGANOLEPTIC PROPERTIES OF CONSUMABLE MATERIALS

Mark A. Sprecker, Sea Bright; James M. Sanders, Eatontown; William L. Schreiber, Jackson; Hugh Watkins, Lincroft; Joaquin F. Vinals, Red Bank, all of N.J.; Edward J. Shuster, Brooklyn, N.Y.; Thomas J. O'Rourke, Red Bank, N.J.; Myrna L. Hagedorn, Highland Park, N.J., and Philip Klemarczyk, Old Bridge, N.J., assignors to International Flavors & Fragrances Inc., New York, N.Y.

Division of Ser. No. 95,149, Nov. 16, 1979, Pat. No. 4,250,338.


This application Oct. 23, 1980, Ser. No. 200,060

Int. Cl.³ C07C 13/30

U.S. Cl. 252—522 R 2 Claims

1. A process for augmenting or enhancing the aroma or taste of a perfume composition or cologne comprising the step of

adding to a perfume composition, a perfume base or a cologne base, an aroma augmenting or enhancing quantity of at least one substantially pure tricyclic ketone having the structure:



wherein R₁, R₂ and R₃ are the same or different and each represents hydrogen or C₁—C₃ lower alkyl.

4,293,454

PROCESS FOR REACTING CHLORAL WITH NITROGEN COMPOSITIONS


Harold G. Monsimer, East Norriton, and Stanley R. Sandler, Springfield, both of Pa., assignors to Pennwalt Corporation, Philadelphia, Pa.

Filed Feb. 4, 1980, Ser. No. 118,297

Int. Cl.³ C09K 3/28; C07C 127/15, 127/22, 143/72, 157/05, 157/12; C08J 9/00

U.S. Cl. 252—609 6 Claims

1. A process for preparing an anhydrous flame retardant composition comprising reacting 0.5 to 4 moles of chloral with 0.5 to 2.0 moles of a nitrogen compound having the formula:



wherein:

(a) X =

or, —SO₂—;

(b) Z is selected from O or S;

(c) R₁, R₂, R₃ and R₄ are independently selected from the group consisting of H, alkyl of 1 to 6 carbons, and substituted or unsubstituted hydroxyalkyl of 2 to 4 carbons and mixtures thereof in a temperature range of 25° to 100° C. with efficient mixing in the absence of a catalyst and of a solvent.

4,293,455

N^α-DESACETYLTHYMOSIN_{α1} AND PROCESS

Robert B. Merrifield, Cresskill, N.J., and Tai W. Wong, New York, N.Y., assignors to Rockefeller University, New York, N.Y.

Filed Apr. 7, 1980, Ser. No. 137,939

Int. Cl.³ C08L 37/00; C07C 103/52

U.S. Cl. 260—8 6 Claims

1. [Lys(Tfa)]^{14,17,19,20}desacetylthymosin_{α1}.

4,293,456

PROCESS FOR THE PRODUCTION OF POLYURETHANE PLASTICS

Artur Reischl, Leverkusen, Fed. Rep. of Germany, assignor to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany
Division of Ser. No. 89,322, Oct. 29, 1979, Pat. No. 4,251,638.
This application Sep. 9, 1980, Ser. No. 185,635

Claims priority, application Fed. Rep. of Germany, Oct. 27, 1978, 2846809

Int. Cl.³ C08J 5/00

U.S. Cl. 260—9 4 Claims

1. A process for the production of boards and moldings by hot-pressing starting materials containing ligno-cellulose with

liquid polyisocyanates as binders, wherein, the improvement comprises a substantially monomerfree, crosslinked distillation residue which is insoluble in inert organic solvents and which cannot be melted without decomposing, of the type accumulating as slag in the distillation of monomeric tolylene diisocyanates from the crude phosgenation products of tolylene diamines and which has been size reduced to a mean particle size of less than 800 μm being used as an additional binder in a quantity of from 2% to 60% by weight.

4,293,457

SEALERLESS PRIMERS

Martin J. Simon, Natrona Heights, Pa., assignor to PPG Industries, Inc., Pittsburgh, Pa.

Division of Ser. No. 34,514, Apr. 30, 1979, Pat. No. 4,232,090, which is a division of Ser. No. 348,771, Apr. 6, 1973, Pat. No. 4,187,258, which is a continuation-in-part of Ser. No. 156,923, Jun. 25, 1971, abandoned, which is a continuation-in-part of Ser. No. 887,333, Dec. 22, 1969, abandoned. This application Nov. 14, 1979, Ser. No. 94,394

Int. Cl.³ C08L 1/14

U.S. Cl. 260—15 5 Claims

1. A primer composition comprising:

- an aminoplast curing agent produced from the condensation products of amines or amides with aldehydes;
- an oil-free saturated polyester having hydroxyl functionality which is curable with said curing agent to form a thermoset polymer; and
- a thermoplastic acrylic polymer which

- (1) is selected from the group consisting of addition polymers of esters of alpha-beta ethylenically unsaturated acids and interpolymers of esters of alpha-beta ethylenically unsaturated acids with other ethylenically unsaturated compounds;
- (2) is essentially non-curable with said aminoplast curing agent;
- (3) after curing of the primer composition, is soluble in solvents in which it was soluble before said curing; and
- d. cellulose acetate butyrate.

4,293,458

THERMOPLASTIC POLYMER COMPOSITION MATERIALS FOR PRETREATING PAPER

Eberhard Gruenberger, Hilden, and Roswitha Müller, Erkrath, both of Fed. Rep. of Germany, assignors to Henkel Kommanditgesellschaft auf Aktien, Düsseldorf-Holthausen, Fed. Rep. of Germany

Filed Jan. 17, 1980, Ser. No. 112,829

Claims priority, application Fed. Rep. of Germany, Jan. 22, 1979, 2902293

Int. Cl.³ C08L 3/02

U.S. Cl. 260—17.4 GC 10 Claims

1. A composition for pretreating the back of paper to be glued to a surface, which comprises a mixture of:

- a fine-grained dispersion of film-forming, non-blocking thermoplastic polymer;
- a paraffin dispersion;
- natural or synthetic zeolite;
- optionally, additional conventional additives; and
- e. water.

4,293,459

ASPHALT EMULSION-CONDITIONER

William J. Detroit, Schofield, Wis., assignor to American Can Company, Greenwich, Conn.

Filed Jun. 7, 1979, Ser. No. 46,377

Int. Cl.³ C08L 1/26, 89/00, 95/00, 97/00

U.S. Cl. 260—17.5 21 Claims

1. An anionic asphalt emulsion-conditioner composition consisting essentially of an admixture of (a) from about 80 to 90 percent by weight of a partially desulfonated lignosulfonate,

derived from spent sulfite liquor and that has been subjected to alkaline hydrolysis and partial desulfonation, or mixture of such lignosulfonates, said lignosulfonates containing combined organic sulfonic sulfur after partial desulfonation of less than about 3 weight percent; (b) from about 5 to 15 weight percent of a nonionic or anionic emulsifying agent; and (c) from 0 to about 5 weight percent of a thickener.

9. An anionic asphalt emulsion comprising at least 57 weight percent of an asphaltic material having a penetration between about 40 and 250 and from about 0.5 to 1.5 weight percent of an emulsion-conditioner composition as claimed in claim 1.

4,293,460

POLYAMIDE YARN SPIN FINISH CONTAINING A REARRANGED GLYCERIDE AND OXIDIZED POLYETHYLENE

Robert M. Marshall, Chester, and Kimon C. Dardoufas, Richmond, both of Va., assignors to Allied Chemical Corporation, New York, N.Y.

Filed May 5, 1980, Ser. No. 146,588

Int. Cl.³ D06M 13/10, 16/00

U.S. Cl. 260—18 PF

49 Claims

1. A spin finish for application to polyamide yarn, the spin finish having a pH of about 7 to 12 and being an oil in water emulsion, the oil portion of which comprises:

about 24.7 to 65 weight percent of a rearranged glyceride, about 5 to 30 weight percent of ethoxylated oleyl alcohol, about 1 to 10 weight percent of ethoxylated nonyl phenol, about 5 to 30 weight percent of ethoxylated castor oil, about 1 to 7.4 weight percent of an oxidized polyethylene, about 0.2 to 2.0 weight percent of a non-nitrogen nonionic emulsifier for the oxidized polyethylene, and about 0.04 to 0.3 weight percent of an alkali hydroxide; wherein said rearranged glyceride is a triglyceride rich in C₁₈ unsaturated oleic acid chain, formed by alcoholysis using oleyl alcohol in the presence of an acid catalyst or transesterification of coconut oil with glycerol trioleate.

38. In a process for the production of polyamide yarn the improvement which comprises treating the yarn during spinning with a spin finish, the spin finish having a pH of about 7 to 12 and being an oil in water emulsion, the oil portion of which comprises:

about 24.7 to 65 weight percent of a rearranged glyceride, about 5 to 30 weight percent of ethoxylated oleyl alcohol, about 1 to 10 weight percent of ethoxylated nonyl phenol, about 5 to 30 weight percent of ethoxylated castor oil, about 1 to 7.4 weight percent of an oxidized polyethylene, about 0.2 to 2.0 weight percent of a non-nitrogen nonionic emulsifier for the oxidized polyethylene, and about 0.04 to 0.3 weight percent of an alkali hydroxide; wherein said rearranged glyceride is a triglyceride rich in C₁₈ unsaturated oleic acid chain, formed by alcoholysis using oleyl alcohol in the presence of an acid catalyst or transesterification of coconut oil with glycerol trioleate.

4,293,461

UNSATURATED MELAMINE CONDENSATES

William F. Strazik, John R. LeBlanc, both of Wilbraham, and J. Owen Santer, East Longmeadow, all of Mass., assignors to Monsanto Company, St. Louis, Mich.

Filed Jun. 9, 1980, Ser. No. 157,720

Int. Cl.³ C08L 91/00

U.S. Cl. 260—18 N

22 Claims

1. An unsaturated condensate of a methylolmelamine, an acrylamide, an ethylenically unsaturated fatty acid amide and a C₁ to C₁₀ alcohol wherein the methylolmelamine has at least about 5 methylol groups per melamine ring, wherein substantially all the methylol groups are condensed with the acrylamide, the unsaturated fatty acid amide or the alcohol, wherein the number of the acrylamide moieties of the condensate is in the range of about 1 to about 4 per melamine ring and the number of unsaturated fatty acid amide moieties is in the range of about 0.5 to about 2 per melamine ring, wherein the ratio of

the acrylamide moieties to unsaturated fatty acid amide moieties is in the range of about 1:1 to about 3:1 and wherein the unsaturated fatty acid amide is an amide of ammonia or methylamine and an ethylenically unsaturated fatty acid containing from 4 to 32 carbon atoms and at least one allylic hydrogen atom per fatty acid moiety.

4,293,462

PROCESS FOR THE MANUFACTURE OF ENOL DERIVATIVES, AND INTERMEDIATES

Robert B. Woodward, Cambridge, Mass., and Hans Bickel, Binningen, Switzerland, assignors to Ciba-Geigy Corporation, Ardsley, N.Y.

Continuation of Ser. No. 913,429, Jun. 7, 1978, abandoned, which is a division of Ser. No. 671,193, Feb. 10, 1976, Pat. No. 4,110,533. This application Dec. 10, 1979, Ser. No. 102,461


Claims priority, application Switzerland, Feb. 20, 1975, 2157/75; Aug. 25, 1975, 10962/75

Int. Cl.³ C07D 205/08, 403/14, 403/04, 403/12


U.S. Cl. 260—239 A

15 Claims


1. A compound of the formula



wherein R₁^a represents an acyl group of the formula




wherein R¹ represents hydrogen, cyclopentyl, cyclohexyl or cycloheptyl, or such cycloalkyl which is mono-substituted in the 1-position by amino, lower alkoxy, carbonylamino, 2-halogeno-lower alkoxy, carbonylamino or phenyl-lower alkoxy, carbonylamino, sulfoamino or sulphonylamino in the form of an alkali metal salt, or R¹ represents phenyl, naphthyl or tetrahydronaphthyl, group or phenyl, naphthyl or tetrahydronaphthyl mono-substituted by hydroxyl, lower alkoxy, carbonyloxy, 2-halogeno-lower alkoxy, carbonyloxy or phenyl-lower alkoxy, carbonyloxy, and/or by halogen or R¹ represents 4-isoxazolyl, or R¹ represents an amino group which is N-mono-substituted by lower alkyl or halogen substituted lower alkyl, or R₁^a represents an acyl group of the formula




wherein R¹ represents lower alkyl, halogeno-lower alkyl, phenoxy-lower alkyl, hydroxyphenoxy-lower alkyl, protected hydroxy-phenoxy-lower alkyl protected by lower alkoxy carbonyl, 2-halogeno-lower alkoxy, carbonyl or phenyl-lower alkoxy, carbonyl, halogeno-phenoxy-lower alkyl, or lower alkyl mono-substituted by amino and/or carboxyl, wherein amino is free or protected by tri-lower alkylsilyl, lower alkanoyl, halogeno-lower alkanoyl or phthaloyl and carboxyl is free or protected by tri-lower alkylsilyl, lower alkyl, 2-halogeno-lower alkyl or phenyl-lower alkyl or R¹ represents lower alkenyl, phenyl, hydroxyphenyl, protected hydroxyphenyl protected by lower alkoxy, carbonyl, 2-halogeno-lower alkoxy, carbonyl or phenyl-lower alkoxy, carbonyl, halogeno-phenoxy, hydroxyhalogeno-phenoxy, protected hydroxy-halogeno-phenoxy protected by lower alkoxy, carbonyl, 2-halogeno-lower alkoxy, carbonyl or phenyl-lower alkoxy, carbonyl, amino-lower alkyl-phenyl, protected amino-lower alkyl-phenyl protected by lower alkanoyl, halogeno-lower al-


kanoyl or phthaloyl, phenoxy-phenyl, or R¹ represents pyridyl, pyridinium, thienyl, furyl, imidazolyl or tetrazolyl, or said heterocyclic groups mono-substituted by lower alkyl, amino, protected amino protected by tri-lower alkylsilyl, lower alkanoyl, halogeno-lower alkanoyl or phthaloyl, aminomethyl or protected aminomethyl protected by lower alkanoyl, halogeno-lower alkanoyl or phthaloyl or R¹ represents lower alkoxy, phenoxy, hydroxy-phenoxy, protected hydroxy-phenoxy protected by lower alkoxy, carbonyl, 2-halogeno-lower alkoxy, carbonyl or phenyl-lower alkoxy, carbonyl, halogeno-phenoxy, lower alkylthio, lower alkenylthio, phenylthio, pyridylthio, 2-imidazolylthio, 1,2,4-triazol-3-ylthio, 1,3,4-triazol-2-ylthio, 1,2,4-thiadiazol-3-ylthio, 1,3,4-thiadiazol-2-ylthio, or 5-tetrazolylthio and said heterocyclylthio groups, mono-substituted by lower alkyl, or R¹ represents halogeno, lower alkoxy, carbonyl, cyano, carbamoyl, N-lower alkyl-carbamoyl, N-phenylcarbamoyl, lower alkanoyl, benzoyl or azido, or R₁^a represents an acyl group of the formula



wherein R¹ represents lower alkyl, phenyl, hydroxyphenyl, protected hydroxyphenyl protected by lower alkoxy, carbonyl, 2-halogeno-lower alkoxy, carbonyl or phenyl-lower alkoxy, carbonyl, halogeno-phenoxy, hydroxy-halogenophenoxy, protected hydroxy-halogeno-phenoxy protected by lower alkoxy, carbonyl, 2-halogeno-lower alkoxy, carbonyl or phenyl-lower alkoxy, carbonyl, furyl, thienyl, or isothiazolyl, and also represents 1,4-cyclohexadienyl, and R¹ represents amino, lower alkoxy, carbonylamino, 2-halogeno-lower alkoxy, carbonylamino, phenyl-lower alkoxy, carbonylamino, wherein phenyl is optionally substituted by lower alkoxy or nitro, tritylamino, nitrophenylthioamino, tritylthioamino or 2-propylideneamino, wherein the propylidene group is optionally substituted by lower alkoxy, carbonyl or lower alkanoyl, carbamoylamino or guanidino-carbamoylamino, guanidinocarbonyl-amino, sulphonylamino, sulphonylamino in alkali-metal salt form, azido, carboxyl, carboxyl in alkali-metal salt form, lower alkoxy, carbonyl, or diphenylmethoxycarbonyl, cyano, sulphonyl, hydroxyl, protected hydroxyl protected by lower alkoxy, carbonyl, 2-halogeno-lower alkoxy, carbonyl, or phenyl-lower alkoxy, carbonyl, wherein phenyl is optionally substituted by lower alkoxy or nitro, 0-lower alkylphosphono, 0,0'-di-lower alkyl-phosphono or halogeno or R₁^a represents a group of the formula




wherein R¹ and R¹ each represent halogeno, or lower alkoxy, carbonyl, or R₁^a represents a group of the formula



wherein R¹ represents phenyl, hydroxyphenyl, protected hydroxyphenyl protected by lower alkoxy, carbonyl, 2-halogeno-lower alkoxy, carbonyl or phenyl-lower alkoxy, carbonyl, hydroxy-halogeno-phenoxy, protected hydroxy-halogeno-phenoxy protected by lower alkoxy, carbonyl, 2-halogeno-lower alkoxy, carbonyl or phenyl-lower alkoxy, carbonyl, furyl, thienyl, isothiazolyl or 1,4-cyclohexadienyl, and R¹ represents aminomethyl or protected aminomethyl protected by lower alkan-

oyl, halogeno-lower alkanoyl or phthaloyl, or R₁^a represents a group of the formula



wherein each of the groups R¹, R^{II} and R^{III} represents lower alkyl, and R₁^b represents hydrogen, or R₁^a and R₁^b together represent 1-oxo-3-aza-1,4-butylene, such group monosubstituted in the 2-position by a group R¹ as defined under formula (A₃) and such group mono- or disubstituted in the 4-position by lower alkyl, the group —N(R₄^a) (R₄^b) denotes a secondary amino group, wherein one of the substituents R₄^a and R₄^b represents hydrogen and the other represents lower alkyl, lower alkoxy-lower alkyl, lower alkyl thio-lower alkyl, cyclohexyl-lower alkyl, phenyl-lower alkyl, thienyl-lower alkyl, cycloalkyl with 3 to 7 carbon atoms, or such cycloalkyl substituted by lower alkyl, lower alkoxy, lower alkylthio, cyclohexyl, phenyl, or furyl, or wherein —N(R₄^a) (R₄^b) denotes a tertiary amino group, wherein each of the substituents R₄^a and R₄^b, independent of each other is lower alkyl, lower alkoxy-lower alkyl, lower alkylthio-lower alkyl, cyclohexyl-lower alkyl, phenyl-lower alkyl, thienyl-lower alkyl, cycloalkyl with 3 to 7 carbon atoms, or such cycloalkyl monosubstituted by lower alkyl, lower alkoxy, lower alkylthio, cyclohexyl, phenyl, or furyl, or wherein N-(R₄^a) (R₄^b) is 1-aziridinyl, 1-pyrrolidinyl, 1-piperidinyl, 1H-2,3,4,5,6,7-hexahydroazepinyl, 4-morpholinyl, 4-thio-morpholinyl, 1-piperazinyl, or 4-methyl-1-piperazinyl, Y represents a leaving group of the formula —S-R₄, wherein R₄ is a monocyclic five membered diazacyclic, oxazacyclic, thiazacyclic, thiadiazacyclic, thiazacyclic, oxadiazacyclic or oxatriazacyclic or a corresponding dicyclic benzodiazacyclic, benzoxazacyclic or benzthiazacyclic radical of aromatic character which radical is bonded to the thio group —S— by one of its ring carbon atoms, which is bonded to a ring nitrogen atom by a double bond, or such group mono-substituted by lower alkyl, lower alkoxy, halogen or phenyl, or wherein R₄ denotes lower alkanoyl, lower thioalkanoxy, cycloalkane carbonyl, cycloalkane thio-carbonyl, benzoyl, thio-benzoyl, naphthylcarbonyl, naphthylthio-carbonyl, pyridylcarbonyl, thenoyl, furoyl, pyridylthiocarbonyl, thio-thenoyl or thiofuroyl, or represents such an acyl or thioacyl group which is mono-substituted by lower alkyl, halogen, lower alkoxy, phenyl or phenoxy, which groups R₄ have up to 18 carbon atoms, or Y represents a leaving group of the formula —SO₂—R₅, wherein R₅ represents unsubstituted or lower alkoxy-, halogeno, phenyl-, or phenoxy-mono-substituted by lower alkyl, lower alkenyl, cyclopentyl or cyclohexyl or R₅ represents naphthyl, or phenyl, or naphthyl or phenyl monosubstituted by lower alkyl, lower alkoxy, halogen, phenyl, phenoxy, or nitro, which groups R₅ have up to 18 carbon atoms, and R₂^a represents lower alkoxy, 2-halogeno-lower alkoxy, phenylcarbonyl-methoxy, mono- or diphenyl-lower alkoxy, wherein phenyl is optionally substituted by lower alkoxy and/or nitro, 1-adamantyloxy, 2-tetrahydrofuryloxy, 2-tetrahydropyranyloxy, 2,3-dihydro-2-pyranyloxy, nitrophenoxy, 2,4,6-trichlorophenoxy, pentachlorophenoxy, cyanomethoxy, phthaliminomethoxy, succinyliminomethoxy, lower alkanoyloxymethoxy, aminolower alkanoyloxymethoxy, phthalidylloxy, tri-lower alkylsilyloxy, halogeno-lower alkoxy-lower alkylsilyloxy, tri-lower alkylstannyloxy, or halogen.

4,293,463

SULPHUR CEMENTS, PROCESS FOR MAKING SAME AND SULPHUR CONCRETES MADE THEREFROM
 Alan H. Vroom, 10728 Willowfern Dr. SE., Calgary, Alberta, Canada

Division of Ser. No. 659,659, Feb. 20, 1976, Pat. No. 4,058,500, which is a continuation of Ser. No. 581,735, May 29, 1975, abandoned. This application Sep. 12, 1977, Ser. No. 832,413
 Int. Cl.³ C08K 3/06

U.S. Cl. 260—42.24

28 Claims

1. A composition for use in the preparation of a sulphur concrete comprising:

- (A) a sulphur cement composition comprising
 (a) sulphur, and
 (b) a bonding agent which is adapted to stabilize said sulphur cement against progressive embrittlement and subsequent crumbling under thermal stress, said bonding agent comprising from about 10 to about 150% by weight of said sulphur of a fly ash of a size of minus 100 mesh; and
 (B) natural or manufactured aggregates.

4,293,464

PHOSPHINE OXIDE FLAME RETARDED, RUBBER-MODIFIED, POLYPHENYLENE ETHER RESIN COMPOSITIONS

Albrecht H. Granzow, Somerset, N.J., assignor to American Cyanamid Company, Stamford, Conn.


Filed Sep. 24, 1979, Ser. No. 78,531

Int. Cl.³ C08K 5/51

U.S. Cl. 260—45.7 P

6 Claims

1. A flame retardant composition comprising a homogeneous blend of polymers containing about 50 to 80 parts by weight of polyphenylene ether resin, about 50 to 20 parts by weight of a polystyrene, and 6% by weight down to a flame retarding effective amount of a compound represented by the formula:



wherein R is selected from the group consisting of from alkyl (1 to 4 carbon atoms), cycloalkyl (5 to 8 carbon atoms), carboxyalkyl (1 to 4 carbon atoms), phenyl, halophenyl (1 to 3 halogen atoms), alkoxyphenyl (1 to 4 carbon alkoxy); R' is selected from the group consisting of from hydrogen, alkyl (1 to 12 carbon atoms), omega-cyano alkyl (1 to 4 carbon alkyl), benzyl, alkylbenzyl (1 to 5 alkyl substituents each containing 1 to 4 carbon atoms), and hydroxyalkyl (1 to 4 carbon alkyl), with the proviso that when R is carboxyalkyl, R' is not hydrogen or benzyl.

4,293,465

BIS PHOSPHINE OXIDE FLAME RETARDED, RUBBER-MODIFIED, POLYPHENYLENE ETHER RESIN COMPOSITIONS

Albrecht H. Granzow, Somerset, N.J., assignor to American Cyanamid Company, Stamford, Conn.


Filed Sep. 24, 1979, Ser. No. 78,534

Int. Cl.³ C08K 5/51

U.S. Cl. 260—45.7 P


8 Claims

1. A flame retardant composition comprising a homogeneous blend of polymers containing about 50 to 80 parts by weight of polyphenylene ether resin, about 50 to 20 parts by weight of a polystyrene, and 6% by weight down to a flame retarding, effective amount of a compound represented by the formula:




wherein R is selected from the group consisting of cycloalkyl


of 5 to 8 carbon atoms, phenyl, carbamoyl ethyl and carboalkoxyethyl wherein the alkoxy group contains 1 to 4 carbon atoms; and wherein Y is selected from the group consisting of alkylene of 1 to 6 carbon atoms, the group,



wherein R' is alkyl of 1 to 4 carbon atoms and n is an integer from 1 to 4, or the group,



with the proviso that when R is carboalkoxyethyl and Y is



then n is 4.

4,293,466

PIPERIDINE PHOSPHITE STABILIZERS FOR POLYMERS AND POLYMERS STABILIZED THEREBY
 Piero Di Battista, San Donato Milanese; Renzo Fontanelli, Milan; Francesco Gratani, Sesto San Giovanni, and Giuseppe Nelli, Milan, all of Italy, assignors to Montedison S.p.A., Milan, Italy

Filed Dec. 5, 1978, Ser. No. 966,562


Claims priority, application Italy, Dec. 2, 1977, 30331 A/77

Int. Cl.³ C07D 401/12; C08K 5/34

U.S. Cl. 260—45.8 N

11 Claims

1. Compositions comprising synthetic thermoplastic polymers stabilized to sunlight, to heat and to ageing, and having incorporated therein, in an amount sufficient to prevent degradation of the polymer, a compound having general formula:



wherein: each of R₁, R₂, R₃ and R₄, which may be the same or different, may be an alkyl having 1 to 4 carbon atoms; R₅ may be a hydrogen atom or an alkyl having 1 to 4 carbon atoms; A is an alkylene group having 2 to 12 carbon atoms or a cycloalkylene group containing 3 to 12 carbon atoms; x is an integer from 1 to 10, and R₆, R₇, R₈ and R₉, which may be the same or different, are each a linear or branched alkyl group having 1 to 20 carbon atoms or a simple or substituted aryl group having 6 to 20 carbon atoms or R₆ and R₇ together and R₈ and R₉ together may form a linear or branched alkylene group having 2 to 20 carbon atoms, or a simple or substituted arylene group having 6 to 20 carbon atoms or a simple or substituted cycloalkylene group having 3 to 20 carbon atoms.

4,293,467

ISOPROPYLIDENEDICYCLOHEXYLENE ESTERS AND THEIR USE AS LIGHT STABILIZERS

William B. Hardy, Bound Brook, and Frank F. Loffelman, Bridgewater, both of N.J., assignors to American Cyanamid Company, Stamford, Conn.


Filed Jan. 16, 1980, Ser. No. 112,390

Int. Cl.³ C07D 401/12; C08K 5/34


U.S. Cl. 260—45.8 N

16 Claims

5. A composition comprising a synthetic polymer subject to oxidative degradation and an effective stabilizing amount of a compound represented by the formula



wherein R is hydrogen or alkyl (C₁-C₈); R' is hydrogen, hydroxyl or alkoxy (C₁-C₈); and R'' is the group:



4,293,468

MALONATE DERIVATIVES AS STABILIZERS FOR ORGANIC MATERIALS

Jean Rody, Basel, Switzerland, assignor to Ciba-Geigy AG, Basel, Switzerland

Continuation of Ser. No. 958,447, Nov. 7, 1978, abandoned, which is a continuation of Ser. No. 792,179, Apr. 29, 1977, abandoned. This application Feb. 4, 1980, Ser. No. 118,219


Claims priority, application Switzerland, May 4, 1976, 5558/76

Int. Cl.³ C08K 5/34; C07D 401/12

U.S. Cl. 260—45.8 N

16 Claims

1. A malonate of the formula I



in which R₁ is hydrogen or C₁-C₄-alkyl, R₂ is C₃-C₄-alkenyl, benzyl or phenyl, cyano or phenyl substituted by C₁-C₈-alkyl or C₁-C₈-alkoxy, R₃ is C₃-C₄-alkenyl or benzyl and X denotes hydrogen, oxyl, C₁-C₁₂-alkyl, C₃-C₆-alkenyl, C₃-C₄-alkinyl, C₂-C₂₁-alkoxyalkyl, C₇-C₁₁-aralkyl, 2,3-epoxypropyl, an aliphatic acyl group selected from formyl, acetyl, acryloyl or crotonyl, or one of the groups —CH₂COOR₄, —CH₂—CH(R₅)—OR₆, —COOR₇ or —CONHR₇, in which R₄ is C₁-C₈-alkyl, C₃-C₆-alkenyl, phenyl, C₇-C₈-aralkyl or cyclohexyl and R₅ is hydrogen, methyl or phenyl and R₆ denotes hydrogen or acetyl, propionyl, butyryl, octanoyl, dodecanoyl, stearoyl, acryloyl, benzoyl, chlorobenzoyl, toluoyl, isopropylbenzoyl, 2,4-dichlorobenzoyl, 4-methoxybenzoyl, 3-butoxybenzoyl, 2-hydroxybenzoyl, 3,5-di-t-butyl-4-hydroxybenzoyl, β-(3,5-di-t-butyl-4-hydroxyphenyl)propionyl, phenylacetyl, cinnamoyl

or hexahydrobenzoyl and R₇ is C₁-C₁₂-alkyl, cyclohexyl, phenyl or benzyl.

13. A method of stabilizing an organic material ordinarily subject to light- and thermal-induced degradation which comprises adding to the organic material a stabilizing amount of a malonate of claim 1 to prevent said degradation.

4,293,469

PRODUCTION OF AN IMPROVED NON-REINFORCED POLYOXYMETHYLENE MOLDING COMPOSITION WHICH FORMS REDUCED MOLD DEPOSITS UPON MOLDING

Robert Edelman, Staten Island, N.Y., assignor to Celanese Corporation, New York, N.Y.

Continuation-in-part of Ser. No. 752,212, Dec. 17, 1976, abandoned. This application Oct. 28, 1977, Ser. No. 846,661

Int. Cl.³ C08K 5/16; C08L 59/02

U.S. Cl. 260—45.9 P

16 Claims

1. A process for improving the thermal stability at molding temperatures of from about 150° to about 240° C. of a polyoxymethylene molding composition which is free of fibrous reinforcement comprising heating a mixture of:

- (1) a polyoxymethylene polymer which exhibits a propensity to form mold deposits upon molding, and
- (2) about 0.25 to about 3 percent by weight based on the weight of the polyoxymethylene polymer of a polycarbodiimide which is (a) derived from an aromatic diisocyanate which is unsubstituted or substituted with up to one methyl group per aromatic ring and (b) contains at least three carbodiimide units per polycarbodiimide molecule, for at least about two minutes at a temperature at which the polyoxymethylene polymer is molten to yield a molding composition which forms a reduced quantity of mold deposits upon molding.

4,293,470

STABILIZING POLYUREA POLYMER POLYOLS BY TREATING WITH A SECONDARY AMINE

Michael Cuscirida, Austin, Tex., assignor to Texaco Inc., White Plains, N.Y.

Filed Jul. 11, 1980, Ser. No. 168,898

Int. Cl.³ C08G 18/32

U.S. Cl. 260—45.9 R

17 Claims

- (1) A polyurea polymer polyol made by reacting a hydroxyl-containing amine, a polyether polyol of about 3000 to 8000 molecular weight and an organic polyisocyanate wherein the amount of polyisocyanate reacted is less than the stoichiometric amount needed to satisfy the hydroxyl group of the hydroxyl-containing amine and the polyether polyol and adding to the reaction product an amount of secondary amine effective to improve the storage stability of said polyurea polymer polyol.

4,293,471

FAST-DRYING ALKYD LATEX

Philip Heiberger, Broomall, Pa., assignor to E. I. Du Pont de Nemours and Company, Wilmington, Del.

Continuation of Ser. No. 20,985, Mar. 16, 1979, abandoned. This application Jun. 16, 1980, Ser. No. 159,793

Int. Cl.³ C09D 3/64, 3/66, 5/02

U.S. Cl. 260—22 CB

10 Claims


1. An aqueous dispersion of a preformed unsaturated fatty acid alkyd resin having an emulsion polymer formed therein by means of a water-soluble emulsion catalyst, said dispersion containing 0.005-2% by weight of an oil-soluble catalyst for oxidative crosslinking.

4,293,472


STABILIZED SYNTHETIC RESIN COMPOSITION
 Motonobu Minagawa, 1-207-3 Shichizacho, Koshigaya; Yutaka Nakahara, 406-71 Minamishimoarai, Iwatsuki, and Tohru Haruna, 969-4 Shimohideya, Okegawa, all of Japan
 Filed Apr. 24, 1979, Ser. No. 33,024

Claims priority, application Japan, Apr. 24, 1978, 53-48599
 Int. Cl.³ C08K 5/36; C07C 65/04

U.S. Cl. 260—23 XA 18 Claims
 1. An ortho-alkylhydroxybenzylpropane-1,3-diol compound having the formula



in which R₁ is an alkyl group having 1 to 8 carbon atoms, R₂ and R₃ are hydrogen or alkyl groups having 1 to 8 carbon atoms, R is hydrogen, an alkyl group having 1 to 8 carbon atoms, an alkenyl group having 2 to 8 carbon atoms, or an ortho-alkylhydroxybenzyl group



X and X' are each independently hydrogen, alkyl groups, aryl groups, aralkyl groups, or alkaryl groups having 1 to 18 carbon atoms, provided that X and X' are not simultaneously hydrogen; and R₉ is an alkyl group having 1 to 30 carbon atoms.

14. A stabilizer synthetic resin composition comprising a synthetic resin and 0.01 to 5% by weight of an ortho-alkylhydroxybenzylpropanediol compound according to claim 1.

4,293,473

POLYVINYL ALCOHOL - CRYSTALLINE SOLVENT SYSTEM BASED COMPOSITIONS MODIFIED WITH ETHYLENE POLYMER

Ernest F. Eastman, Wilmington, Del., assignor to E. I. Du Pont de Nemours and Company, Wilmington, Del.

Filed Jul. 25, 1980, Ser. No. 172,243

Int. Cl.³ C08L 93/00, 93/04

U.S. Cl. 260—27 R 15 Claims

1. Solid adhesive composition consisting essentially of (1) from about 2 to about 35 percent by weight of a vinyl alcohol polymer selected from the group consisting of polyvinyl alcohol and ethylene/vinyl alcohol copolymers containing at least 50 mol percent vinyl alcohol; (2) from about 10 to about 80 percent by weight of an at least two component crystalline solvent system wherein component (a) is selected from the group consisting of urea, solid alkyl substituted ureas containing a total of up to 9 carbon atoms, thiourea, biuret, and solid aliphatic amides containing up to 6 carbon atoms, and component (b) is ε-caprolactam, the ratio of component (a) to component (b) being from about 80/20 to about 20/80; (3) from about 1 to about 15 percent by weight of at least one ethylene polymer selected from the group consisting of ethylene homopolymer and ethylene copolymers with vinyl esters, acrylates, methacrylates and their terpolymers with carbon monoxide, and their terpolymers with acids selected from the group

consisting of acrylic acid and methacrylic acid, provided that when said ethylene polymer is ethylene homopolymer it is present in an amount of up to about 5 percent by weight; (4) from 0 to about 15 percent by weight of thermoplastic tackifier; and (5) from 0 to about 5 percent by weight of normally solid, saturated aliphatic carboxylic acid.

4,293,474

POLYURETHANE IONOMER DISPERSIONS CONTAINING ELECTROLYTES

Dieter Dieterich, Leverkusen, Fed. Rep. of Germany, and Peter Markusch, New Martinsville, W. Va., assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany
 Continuation of Ser. No. 862,455, Dec. 20, 1977, abandoned.

This application Jan. 21, 1980, Ser. No. 113,920

Claims priority, application Fed. Rep. of Germany, Dec. 30, 1976, 2659617

Int. Cl.³ C08G 18/12, 18/32; C08L 75/08, 75/12

U.S. Cl. 260—29.2 TN 3 Claims

1. Aqueous dispersions or solutions of polyurethane ionomers which are stable at room temperature, characterized by (a) hydrophilic polyalkylene oxide-polyether chains in the polyurethane, having an ethylene oxide unit content of from 1.2 to 50% by weight, based on the polyurethane solid content; (b) containing 5 to 250 milliequivalents, per 100 g of polyurethane solid content, of ionic groups built into the polyurethane; and (c) containing from 0.5 to 100% by weight, based on the polyurethane solid content, of water-soluble electrolytes dissolved in the water, wherein said water-soluble electrolytes are salts of (i) inorganic or organic acids having a pK_a-value of from 0 to 3 with (ii) inorganic or organic bases having a pK_b-value of from 0 to 3

with the proviso that where organic compounds are used as said organic acids or said organic bases, they should not form mycellae in their salt form, should not have surface active properties and should not contain hydrocarbon groups with more than eight carbon atoms.

4,293,475

PIGMENT DISPERSIONS FOR SURFACE-COATING COMPOSITIONS AND SURFACE-COATING COMPOSITIONS CONTAINING SAME

Henri Sidi, Paramus, N.J., assignor to Tenneco Chemicals, Inc., Saddle Brook, N.J.

Filed Sep. 12, 1980, Ser. No. 186,890

Int. Cl.³ C08F 220/20

U.S. Cl. 260—29.6 TA

19 Claims

1. A pigment dispersion that comprises (a) 10% to 75% by weight of a pigment component; (b) 5% to 35% by weight of a dispersant that is a water-soluble salt of a polymer derived from (1) 30% to 75% by weight of at least one hydroxyalkyl methacrylate wherein the hydroxyalkyl group has from 2 to 4 carbon atoms; (2) 20% to 65% by weight of methacrylic acid; and (3) 2% to 20% by weight of at least one ethylenically-unsaturated monomer selected from the group consisting of styrene, vinyltoluene, glycidyl acrylate, and glycidyl methacrylate, said polymer having an acid value in the range of 160 to 400 and a hydroxyl value in the range of 150 to 320; and (c) 15% to 70% by weight of a solvent selected from the group consisting of water, water-miscible organic solvents, and mixtures thereof.

4,293,476

INTERFACIAL CROSS-LINKING OF LATEX FILMS
 Carl Moore, and Robert A. Kirchoff, both of Midland, Mich., assignors to The Dow Chemical Company, Midland, Mich.

Filed Aug. 2, 1979, Ser. No. 63,279

Int. Cl.³ C08L 51/04

U.S. Cl. 260—29.7 W

17 Claims

1. A cross-linkable, synthetic polymer composition comprising an aqueous polymer dispersion of (1) heterogeneous polymer particles which comprise a water-insoluble polymeric core of a polymer of a conjugated diene or a copolymer of a conjugated diene with a monovinylidene aromatic and having on its surface a reactive polymer domain, said reactive polymer domain having an average thickness of up to about 100 Å and being derived from an amount of a reactive monomer bearing a non- or weakly ionic reactive halo, amino or substituted amino, or epoxy group such that the reactive groups are more concentrated in the reactive polymer domain than in the polymeric core of the heterogeneous polymer particle and (2) a water-soluble coreactive component bearing a plurality of a second non- or weakly ionic reactive group coreactive with the reactive groups of the reactive polymer domain of the heterogeneous polymer particles.

4,293,477

HIGHLY FILLED THERMALLY CONDUCTIVE ELASTOMERS III

Ares N. Theodore, Farmington Hills, Mich., assignor to Ford Motor Company, Dearborn, Mich.

Filed Jan. 4, 1980, Ser. No. 109,446


Int. Cl.³ C08K 3/08, 3/10, 3/20; C08L 83/14

U.S. Cl. 260—29.1 SB


7 Claims

1. A thick, highly filled, shaped elastomeric body made by filling a cavity with a dispensable elastomer precursor consisting essentially of:

1. 100 parts by weight of an olefinically unsaturated cross-linkable polysiloxane having the formula:



wherein at least most of the Ra's and Rb's are selected from (A) saturated hydrocarbyl and hydrocarbyloxy groups having 1 to about 10 carbon atoms that are alkyl or aryl or alkyl and aryl and (B) allyl or vinyl groups, but wherein up to about 25% of the Rb's may be



wherein at least most of the Rc's and Rd's are selected from (A) and (B) above but up to about 10% of the Rd's may contain additional siloxane units with substituents selected from (A) and (B) or still additional siloxane units; and still further wherein (1) the average number of siloxane units per polymer is between 150 and 250 and (2) there is an average of above about 1.5 but lower than 2.5 crosslinking sites selected from the vinyl, allyl or vinyl and allyl groups per polymer molecule;

II. about 60–500 parts by weight of finely divided particulate comprising:

(A) silica 60–500 parts by weight ratio to the polysiloxane of I. of between about 0.3 and 2.5:1 wherein the silica particulate comprises:

1. ground silica having an average particulate diameter between about 0.5 and 10 microns; and
 2. fumed silica having an average particulate diameter between about 0.010 and 0.014 microns;

(B) thermally conductive alloy powder at a weight ratio

to the polysiloxane of I. of between 0.3 to 2.5:1 wherein the alloy is an alloy of a first row transition metal;

III. a viscosity modifier comprising a silicone oil having a viscosity between about 1000–1,000,000 centistokes at 25° C. at a weight ratio to the particulate of II of between about 1:20–1:4 oil to particulate; and

IV. a silyl hydride functional polysiloxane oligomer containing between about 5 and about 50 siloxane groups at a weight ratio with respect to the polysiloxane of I. of between about 1:3 to 1:20, the silyl hydride functional polysiloxane oligomer having an average of more than 1 and less than 20 silyl hydride groups per polymer chain.

4,293,478

PROCESS FOR PRODUCING POLYPHENYLENE ETHER COMPOSITION CONTAINING INORGANIC PIGMENT

Akitoshi Sugio, Ohmiya; Masanobu Masu, Kanamachi; Hiroshi Nakai, Matsudo, and Yukio Sasaki, Tokyo, all of Japan, assignors to Mitsubishi Gas Chemical Co., Inc., Tokyo, Japan
 Filed Oct. 3, 1979, Ser. No. 81,620

Claims priority, application Japan, Oct. 4, 1978, 53-122436
 Int. Cl.³ C08L 71/04

U.S. Cl. 260—37 R

3 Claims

1. In a method for preparing a resin composition composed of a polyphenylene ether alone or a polyphenylene ether and a styrene polymer, and an inorganic pigment, the improvement which comprises intimately mixing the polyphenylene ether and the inorganic pigment in a weight ratio of from 0.5:1 to 2:1 by a high-speed mixer wherein the linear speed of the tips of the stirring impellers is maintained at 5 to 50 m/sec to form a pre-blend, and admixing in an extruder the pre-blend intimately with the polyphenylene ether alone or the polyphenylene ether and the styrene polymer.

4,293,479

HEAT CURABLE MOLDING COMPOSITION

Tsuneco Hanada; Taro Koshii, and Hideo Shinmi, all of Ichihara, Japan, assignors to Toray Silicone Company, Ltd., Tokyo, Japan

Continuation-in-part of Ser. No. 867,067, Jan. 5, 1978. This application Dec. 6, 1979, Ser. No. 101,324

Claims priority, application Japan, Feb. 18, 1977, 52-16072
 Int. Cl.³ C08L 63/00

U.S. Cl. 260—37 EP

4 Claims

1. An improved heat curable molding composition which consists of

(A) 100 parts of a heat curable molding resin;
 (B) up to 400 parts of a filler;

the improvement comprising replacing 5–80 weight percent of (B) with a spherical non-crystalline silica filler having an average particle size of 1–800 millimicrons which has been prepared by vaporization of high purity sand or quartz in the absence of hydrogen or natural gas and subsequently condensed.

4,293,480

URETHANE BINDER COMPOSITIONS FOR NO-BAKE AND COLD BOX FOUNDRY APPLICATION UTILIZING ISOCYANATO-URETHANE POLYMERS

Ralph D. Martin; William R. Dunnavant, both of Columbus; Gregory P. Sturtz, Worthington, and Heimo J. Langer, Columbus, all of Ohio, assignors to Ashland Oil, Inc., Ashland, Ky.

Filed May 11, 1979, Ser. No. 38,158

Int. Cl.³ C08L 61/10, 75/08

U.S. Cl. 260—38

24 Claims

1. A binder composition useful for making shaped foundry articles for use in casting lightweight metals, which articles collapse after casting of said lightweight metals, comprising in admixture a polyol component, an isocyanate component com-

prising an isocyanato urethane polymer wherein all hydroxy groups of said polymer are capped and a curing agent.

4,293,481

TRIPEPTIDE INHIBITORS OF ANGIOTENSIN-CONVERTING ENZYME


Michael E. Condon, Lawrenceville, and Miguel A. Ondetti, Princeton, both of N.J., assignors to E. R. Squibb & Sons, Inc., Princeton, N.J.

Filed Jul. 24, 1980, Ser. No. 171,772

Int. Cl.³ C07C 103/52

U.S. Cl. 260—112.5 R

1. A tripeptide having the formula



or a salt thereof, wherein R₁ is hydrogen and R₂ is hydroxyl, alkyl, aryl, arylalkyl, alkoxy, alkylthio, arylthio, halogen, or azido, or R₁ and R₂ are the same and each is hydrogen, halogen, alkoxy or alkylthio, or R₁ and R₂ together are oxo, —O—(CH₂)_n—O—, or —S—(CH₂)_n—S—, wherein n is 1 or 2;

R₃ is hydrogen, alkyl or trifluoromethyl;
R₄ is hydrogen or an acyl protecting group; and
R₅ is hydrogen or alkyl.

4,293,482

A-30912A NUCLEUS

Bernard J. Abbott, Greenwood, and David S. Fukuda, Brownsburg, both of Ind., assignors to Eli Lilly and Company, Indianapolis, Ind.


Continuation-in-part of Ser. No. 103,017, Dec. 13, 1979, abandoned. This application Aug. 25, 1980, Ser. No. 181,029

Int. Cl.³ C07C 103/52; H61K 37/00; C12P 21/04

U.S. Cl. 260—112.5 R

22 Claims

1. A-30912A nucleus of the formula



and the acid addition salts thereof.

4,293,483

DERIVATIVES OF A-30912A NUCLEUS

Manuel Debono, Indianapolis, Ind., assignor to Eli Lilly and Company, Indianapolis, Ind.


Continuation-in-part of Ser. No. 103,149, Dec. 13, 1979, abandoned. This application Aug. 25, 1980, Ser. No. 181,030

Int. Cl.³ C07C 103/52

U.S. Cl. 260—112.5 R


25 Claims

1. A compound of the formula:




wherein

R¹ is an N-alkanoyl amino acyl group of the formula




wherein:


W is a divalent aminoacyl radical of the formula:




wherein A is C₁-C₁₀ alkylene or C₅-C₆ cycloalkylene;




wherein R³ is hydroxymethyl, hydroxyethyl, mercaptomethyl, mercaptoethyl, methylthioethyl, 2-thienyl, 3-indole-methyl, phenyl, benzyl, or substituted phenyl or substituted benzyl in which the benzene ring thereof is substituted with chloro, bromo, iodo, nitro, C₁-C₃ alkyl, hydroxy, C₁-C₃ alkylthio, carbamyl, or C₁-C₃ alkylcarbamyl;




wherein X is hydrogen, chloro, bromo, iodo, nitro, C₁-C₃ alkyl, hydroxy, C₁-C₃ alkoxy, mercapto, C₁-C₃ alkylthio, carbamoyl, or C₁-C₃ alkylcarbamyl;






wherein X¹ is chloro, bromo, or iodo;



wherein B is a divalent radical of the formula: —(CH₂)_n—, wherein n is an integer from 1 to 3; —CH=CH—; —CH=CH—CH₂—; or



and R² is C₁-C₁₇ alkyl or C₂-C₁₇ alkenyl.



wherein A is divalent oxygen, sulfur, sulfinyl, or sulfonyl; A¹ is divalent oxygen, sulfur, sulfinyl, sulfonyl or —NH—; X is hydrogen, chloro, bromo, iodo, nitro, C₁-C₃ alkyl, hydroxy, C₁-C₃ alkoxy, mercapto, C₁-C₃ alkylthio, carbamyl or C₁-C₃ alkylcarbamyl; X¹ is chloro, bromo or iodo; R² is hydrogen C₁-C₁₈ alkyl or C₂-C₁₈ alkenyl; W is C₁-C₁₀ alkylene or C₂-C₁₀ alkenylene; m, n and p are 0 or 1, but if m=0, n must=0; provided: that the sum of the carbon atoms in the R² and W groups must be greater than 4 but cannot exceed 21; that when X is mercapto, A and A¹ cannot be sulfinyl or sulfonyl and that when A and A¹ are sulfinyl or sulfonyl, they must be in equal oxidation states.

4,293,485

DERIVATIVES OF S31794/F-1 NUCLEUS

Manuel Debono, Indianapolis, Ind., assignor to Eli Lilly and Company, Indianapolis, Ind.


Continuation-in-part of Ser. No. 103,148, Dec. 13, 1979, abandoned. This application Aug. 25, 1980, Ser. No. 181,436

Int. Cl.³ C07C 103/52; A61K 37/00; C12P 21/04


U.S. Cl. 260—112.5 R

25 Claims

1. A compound of the formula:



wherein R¹ is an N-alkanoyl amino acyl group of the formula



wherein:

W is a divalent aminoacyl radical of the formula:

4,293,484

DERIVATIVES OF A-30912H NUCLEUS

Manuel Debono, Indianapolis, Ind., assignor to Eli Lilly and Company, Indianapolis, Ind.


Continuation-in-part of Ser. No. 103,146, Dec. 13, 1979, abandoned. This application Aug. 25, 1980, Ser. No. 181,034

Int. Cl.³ C07C 103/52

U.S. Cl. 260—112.5 R

40 Claims

1. A compound of the formula:



wherein R³ is C₁-C₆ alkyl and R¹ is a group of the formula:

4,293,486

DERIVATIVES OF S31794/F-1 NUCLEUS

Manuel Debono, Indianapolis, Ind., assignor to Eli Lilly and Company, Indianapolis, Ind.



Continuation-in-part of Ser. No. 103,150, Dec. 13, 1979. This application Aug. 25, 1980, Ser. No. 181,037

Int. Cl.³ C07C 103/52


U.S. Cl. 260—112.5 R

40 Claims




1. A compound of the formula:

wherein A is C₁-C₁₀ alkylene or C₅-C₆ cycloalkylene:

wherein R³ is hydroxymethyl, hydroxyethyl, mercaptoethyl, mercaptoethyl, methylthioethyl, 2-thienyl, 3-indolemethyl, phenyl, benzyl, or substituted benzyl in which the benzene ring thereof is substituted with chloro, bromo, iodo, nitro, C₁-C₃ alkyl, hydroxy, C₁-C₃ alkylthio, carbamyl, or C₁-C₃ alkylcarbamyl;







wherein X is hydrogen, chloro, bromo, iodo, nitro, C₁-C₃ alkyl, hydroxy, C₁-C₃ alkoxy, mercapto, C₁-C₃ alkylthio, carbamyl, or C₁-C₃ alkylcarbamyl;

wherein X¹ is chloro, bromo, or iodo;

wherein B is a divalent radical of the formula: $-(\text{CH}_2)_n-$, wherein n is an integer from 1 to 3; $-\text{CH}=\text{CH}-$; $-\text{CH}=\text{CH}-\text{CH}_2-$; or



and R² is C₁-C₁₇ alkyl or C₂-C₁₇ alkenyl.

wherein R¹ is a group of the formula:

wherein A is divalent oxygen, sulfur, sulfinyl, or sulfonyl; A¹ is divalent oxygen, sulfur, sulfinyl, sulfonyl or $-\text{NH}-$; X is hydrogen, chloro, bromo, iodo, nitro, C₁-C₃ alkyl, hydroxy, C₁-C₃ alkoxy, mercapto, C₁-C₃ alkylthio, carbamyl or C₁-C₃ alkylcarbamyl; X¹ is chloro, bromo or iodo; R² is hydrogen, C₁-C₁₈ alkyl or C₂-C₁₈ alkenyl; W is C₁-C₁₀ alkylene or C₂-C₁₀ alkenylene; m, n and p are 0 or 1, but if m=0, n must=0; provided: that the sum of the carbon atoms in the R² and W groups must be greater than 4 but cannot exceed 21; that when X is mercapto, A and A¹ cannot be sulfinyl or sulfonyl and that when A and A¹ are sulfinyl or sulfonyl, they must be in equal oxidation states.

4,293,487

DERIVATIVES OF A-30912D NUCLEUS

Manuel Debono, Indianapolis, Ind., assignor to Eli Lilly and Company, Indianapolis, Ind.



Continuation-in-part of Ser. No. 103,015, Dec. 13, 1979, abandoned. This application Aug. 25, 1980, Ser. No. 181,040

Int. Cl.³ C07C 103/52; A61K 37/00; C12P 21/04

U.S. Cl. 260—112.5 R

25 Claims


1. A compound of the formula:

wherein R¹ is an N-alkanoyl amino acyl group of the formula


wherein:

W is a divalent aminoacyl radical of the formula:

(a)


wherein A is C₁-C₁₀ alkylene or C₅-C₆ cycloalkylene;

(b)




wherein R³ is hydroxymethyl, hydroxyethyl, mercaptoethyl, mercaptoethyl, methylthioethyl, 2-thienyl, 3-indolemethyl, phenyl, benzyl, or substituted benzyl in which the benzene ring thereof is substituted with chloro, bromo, iodo, nitro, C₁-C₃ alkyl, hydroxy, C₁-C₃ alkylthio, carbamyl, or C₁-C₃ alkylcarbamyl;

(c)




wherein X is hydrogen, chloro, bromo, iodo, nitro,


C₁-C₃ alkyl, hydroxy, C₁-C₃ alkoxy, mercapto, C₁-C₃ alkylthio, carbamyl, or C₁-C₃ alkylcarbamyl;

wherein X¹ is chloro, bromo, or iodo;


(e)



(f)



wherein B is a divalent radical of the formula: $-(\text{CH}_2)_n-$, wherein n is an integer from 1 to 3; $-\text{CH}=\text{CH}-$; $-\text{CH}=\text{CH}-\text{CH}_2-$; or

and R² is C₁-C₁₇ alkyl or C₂-C₁₇ alkenyl.

4,293,488

DERIVATIVES OF A-30912B NUCLEUS

Manuel Debono, Indianapolis, Ind., assignor to Eli Lilly and Company, Indianapolis, Ind.


Continuation-in-part of Ser. No. 103,131, Dec. 13, 1979, abandoned. This application Aug. 25, 1980, Ser. No. 181,435

Int. Cl.³ C07C 103/52; A61K 37/00; C12P 21/04


U.S. Cl. 260—112.5 R

25 Claims

1. A compound of the formula:




wherein R^1 is an N-alkanoyl amino acyl group of the formula




wherein:


W is a divalent aminoacyl radical of the formula:




wherein A is C_1 - C_{10} alkylene or C_5 - C_6 cycloalkylene;




wherein R^3 is hydroxymethyl, hydroxyethyl, mercaptomethyl, mercaptoethyl, methylthioethyl, 2-thienyl, 3-indolemethyl, phenyl, benzyl, or substituted phenyl or substituted benzyl in which the benzene ring thereof is substituted with chloro, bromo, iodo, nitro, C_1 - C_3 alkyl, hydroxy, C_1 - C_3 alkylthio, carbamyl, or C_1 - C_3 alkylcarbamyl;




wherein X is hydrogen, chloro, bromo, iodo, nitro, C_1 - C_3 alkyl, hydroxy, C_1 - C_3 alkoxy, mercapto, C_1 - C_3 alkylthio, carbamyl, or C_1 - C_3 alkylcarbamyl;



wherein X^1 is chloro, bromo, or iodo;



wherein B is a divalent radical of the formula: $-(CH_2)_n-$, wherein n is an integer from 1 to 3;



and R^2 is C_1 - C_{17} alkyl or C_2 - C_{17} alkenyl.


(a)

(b)

(c)

4,293,489
DERIVATIVES OF A-30912A NUCLEUS
Manuel Debono, Indianapolis, Ind., assignor to Eli Lilly and Company, Indianapolis, Ind.
Continuation-in-part of Ser. No. 103,012, Dec. 13, 1979, abandoned. This application Aug. 25, 1980, Ser. No. 181,442
Int. Cl.³ C07C 103/52
U.S. Cl. 260—112.5 R
1. A compound of the formula:

40 Claims



wherein R^1 is a group of the formula:

(d)

(e)


(f)

4,293,491

DERIVATIVES OF A-30912H NUCLEUS


(a) Manuel Debono, Indianapolis, Ind., assignor to Eli Lilly and Company, Indianapolis, Ind.
Continuation-in-part of Ser. No. 103,147, Dec. 13, 1979, abandoned. This application Aug. 25, 1980, Ser. No. 182,248
Int. Cl.³ C07C 103/52
U.S. Cl. 260—112.5 R
25 Claims

(b) 1. A compound of the formula:




wherein A is divalent oxygen, sulfur, sulfinyl, or sulfonyl; A^1 is divalent oxygen, sulfur, sulfinyl, sulfonyl or $-NH-$; X is hydrogen, chloro, bromo, iodo, nitro, C_1 - C_3 alkyl, hydroxy, C_1 - C_3 alkoxy, mercapto, C_1 - C_3 alkylthio, carbamyl or C_1 - C_3 alkylcarbamyl; X^1 is chloro, bromo or iodo; R^2 is hydrogen C_1 - C_{18} alkyl or C_2 - C_{18} alkenyl; W is C_1 - C_{10} alkylene or C_2 - C_{10} alkenylene; m, n and p are 0 or 1, but if m=0, n must=0; provided: that the sum of the carbon atoms in the R^2 and W groups must be greater than 4 but cannot exceed 21; that when X is mercapto, A and A^1 cannot be sulfinyl or sulfonyl and that when A and A^1 are sulfinyl or sulfonyl, they must be in equal oxidation states.

(c)




wherein R^4 is C_1 - C_6 alkyl and R^1 is an N-alkanoyl amino acyl group of the formula




wherein:


W is a divalent aminoacyl radical of the formula:



wherein A is C_1 - C_{10} alkylene or C_5 - C_6 cycloalkylene;



wherein R^3 is hydroxymethyl, hydroxyethyl, mercaptomethyl, mercaptoethyl, methylthioethyl, 2-thienyl, 3-indolemethyl, phenyl, benzyl, or substituted phenyl or substituted benzyl in which the benzene ring thereof is substituted with chloro, bromo, iodo, nitro, C_1 - C_3 alkyl, hydroxy, C_1 - C_3 alkylthio, carbamyl, or C_1 - C_3 alkylcarbamyl;




wherein X is hydrogen, chloro, bromo, iodo, nitro, C_1 - C_3 alkyl, hydroxy, C_1 - C_3 alkoxy, mercapto, C_1 - C_3 alkylthio, carbamyl, or C_1 - C_3 alkylcarbamyl;

4,293,490

A-30912H NUCLEI

Bernard J. Abbott, Greenwood, and David S. Fukuda, Brownsburg, both of Ind., assignors to Eli Lilly and Company, Indianapolis, Ind.
Continuation-in-part of Ser. No. 103,016, Dec. 13, 1979, abandoned. This application Aug. 25, 1980, Ser. No. 181,443
Int. Cl.³ C07C 103/52; C12P 21/04; H61K 37/00
U.S. Cl. 260—112.5 K
33 Claims

1. A-30912H-type compounds of the formula




wherein R is C_1 - C_6 alkyl and the acid addition salts thereof.


(a)

(b)


(c)




wherein X¹ is chloro, bromo, or iodo;




wherein B is a divalent radical of the formula: $-(CH_2)_n-$, wherein n is an integer from 1 to 3; $-CH=CH-$;



and R² is C₁-C₁₇ alkyl or C₂-C₁₇ alkenyl.



(e)




(f) wherein R is alkyl, alkoxy, nitro, dialkylamino or halogen, n is zero or the integer 1, 2 or 3, and R is either the same or different when n is the integer 2 or 3.


4,293,493 AZETIDINONE ALCOHOL DISULFIDES AND PROCESS FOR CYCLIZATION

Stjepan Kukolja, Carmel, and Janice L. Pfeil, Indianapolis, both of Ind., assignors to Eli Lilly and Company, Indianapolis, Ind. Filed Apr. 7, 1980, Ser. No. 137,862

Int. Cl.³ C07D 205/08, 403/12, 403/14, 405/14
U.S. Cl. 260-239 A 25 Claims
1. A compound of the formula;




wherein R₁ is an acyl group of the formula




wherein R' is

- C₁-C₇ alkyl, cyanomethyl, C₁-C₆ haloalkyl, 4-protected amino-4-protected carboxybutyl; or
- C₁-C₆ alkoxy, phenoxy, benzyloxy or 4-methoxybenzyloxy; or
- the group $-R''$ wherein R'' is phenyl or substituted phenyl wherein the substituents are 1 or 2 halogens, protected hydroxy, cyano, trifluoromethyl, C₁-C₄ alkyl, C₁-C₄ alkoxy, protected carboxy, protected carboxymethyl, protected hydroxymethyl or protected aminomethyl; or
- an arylalkyl group of the formula




wherein R'' is as defined above, and m is 0 or 1; or
(e) a substituted arylalkyl group of the formula

4,293,492
DISAZO COMPOUNDS DERIVED FROM
3,6-BIS(STYRYL)-9-ETHYLCARBAZOLE
Masaomi Sasaki, Kawasaki; Kiyoshi Sakai, Tokyo; Mitsuru Hashimoto, Hino; Masafumi Ohta, Yokohama, and Kyoji Tsutsui, Tokyo, all of Japan, assignors to Ricoh Co., Ltd., Tokyo, Japan
Division of Ser. No. 921,086, Jun. 30, 1978, Pat. No. 4,251,614.
This application May 20, 1980, Ser. No. 152,061
Claims priority, application Japan, Jul. 5, 1977, 52-80116; Jul. 8, 1977, 52-81791
Int. Cl.³ C09B 35/24, 35/34
U.S. Cl. 260-160 26 Claims
1. A disazo compound having the formula



in which A' is



wherein

R''' is R'' as defined above, 2-thienyl, 3-thienyl, 2-furyl or 3-furyl; W is protected hydroxy, protected carboxy, protected amino, or

(f) a heteroarylmethyl groups of the formula



wherein

R''' is 2-thienyl, 3-thienyl, 2-furyl, 3-furyl, 2-thiazolyl, 5-tetrazolyl, 1-tetrazolyl;


R₂ is a carboxy protecting group and R₃ is another identically substituted azetidinone alcohol moiety bonded to the opposite end of the disulfide group or is phenyl or a monosubstituted phenyl group, where the substituents are chloro, methoxy, methyl or acetoxy.

4,293,494 METHOD FOR THE PURIFICATION OF RAW CAPROLACTAM WHICH CONTAINS AMIDES AND OTHER BY-PRODUCTS

Paolo Senni, Colleferro, and Domenico Astarita, Segni, both of Italy, assignors to Snia Viscosa S.p.A., Milan, Italy
Filed Apr. 24, 1980, Ser. No. 143,418

Claims priority, application Italy, May 4, 1979, 22355 A/79
Int. Cl.³ C07D 201/16
U.S. Cl. 260-239.3 A 9 Claims

1. A method for the purification of raw caprolactam, which contains as impurities one or more primary amides according to formula I:



(I)


wherein R is a hydrocarbon radical having from 1 to 14 carbon atoms, and other by-products, comprising performing the following operations in the order indicated hereinbelow:

- treating a solution of said raw caprolactam in which the solvent is a substantially water insoluble organic solvent with water in such a way as to extract the greater part of the caprolactam in purified form;
- separating the aqueous caprolactam solution from the water insoluble organic solvent and isolating the caprolactam from the aqueous solution;
- treating the remaining solution containing the organic solvent with a mineral acid in a concentration as to be inert with respect to the organic solvent and to cause the formation of two separate phases;
- separating the two phases into a heavy phase, containing the mineral acid, its respective dilution water and the greater part or all the amides according to formula I and said by-products; and a light phase containing said organic solvent; and
- recycling said light phase to (a).


4,293,495 SYMMETRICAL AZETIDINONE ALDEHYDE DISULFIDES AND PROCESS

Stjepan Kukolja, Carmel, and Janice L. Pfeil, Indianapolis, both of Ind., assignors to Eli Lilly and Company, Indianapolis, Ind. Filed Apr. 7, 1980, Ser. No. 138,023

Int. Cl.³ C07D 205/08, 403/12, 403/14, 405/14
U.S. Cl. 260-245.4 9 Claims
1. A compound of the formula;



wherein R₁ is an acyl group of the formula




wherein R' is

- C₁-C₇ alkyl, cyanomethyl, C₁-C₆ haloalkyl, 4-protected amino-4-protected carboxybutyl; or
- C₁-C₆ alkoxy, phenoxy, benzyloxy or 4-methoxybenzyloxy; or
- the group $-R''$ wherein R'' is phenyl or substituted phenyl wherein the substituents are 1 or 2 halogens, protected hydroxy, cyano, trifluoromethyl, C₁-C₄ alkyl, C₁-C₄ alkoxy, protected carboxy, protected carboxymethyl, protected hydroxymethyl or protected aminomethyl; or
- an arylalkyl group of the formula




wherein R'' is as defined above, and m is 0 or 1; or
(e) a substituted arylalkyl group of the formula




wherein R''' is R'' as defined above, 2-thienyl, 3-thienyl, 2-furyl or 3-furyl; W is protected hydroxy, protected carboxy, protected amino or

(f) a heteroarylmethyl group of the formula



wherein R''' is 2-thienyl, 3-thienyl, 2-furyl, 3-furyl, 2-thiazolyl, 5-tetrazolyl, 1-tetrazolyl; and R₂ is a carboxy protecting group.

4,293,496
6(R)-[2-(8-HYDROXY-2,6-DIMETHYLPOLYHYDRO-
NAPHTHYL-1)-ETHYL]-4(R)-HYDROXY-3,4,5,6-
TETRAHYDRO-2H-PYRAN-2-ONES
Alvin K. Willard, Lansdale, Pa., assignor to Merck & Co., Inc.,
Rahway, N.J.
Continuation-in-part of Ser. No. 118,049, Feb. 4, 1980,
abandoned. This application Aug. 5, 1980, Ser. No. 175,232
Int. Cl.³ C07D 309/30; C07C 59/11
U.S. Cl. 260-343.5 6 Claims
1. A compound of the formula



in which the dotted lines X, Y and Z represent possible double bonds, said double bonds, when any are present, being either X and Z in combination or one of X, Y or Z alone.

4,293,497

COUPLING REACTION INVOLVING A GRIGNARD AND ALLYLIC HALIDE

Carlos G. Cardenas, and Zia U. Din, both of Jacksonville, Fla., assignors to SCM Corporation, New York, N.Y.
Division of Ser. No. 865,668, Dec. 29, 1977, Pat. No. 4,228,313, which is a division of Ser. No. 786,983, Apr. 13, 1977, which is a continuation-in-part of Ser. No. 596,273, Jul. 16, 1975, abandoned, and a continuation-in-part of Ser. No. 596,426, Jul. 16, 1975, abandoned, and a continuation-in-part of Ser. No. 596,274, Jul. 16, 1975, abandoned, and a continuation-in-part of Ser. No. 596,361, Jul. 16, 1975, abandoned. This application Mar. 18, 1980, Ser. No. 131,421

Int. Cl.³ C07D 311/72; C07C 27/02

U.S. Cl. 260—345.5

3 Claims

1. A process for the synthesis of dehydrophytol or a polydehydro-phytol from a C₁₀ acyclic terpene hydrocarbon compound of the 2,6-dimethyloctane series, having a terminal isopropenyl or isopropylidene group, and a C₁₀ aliphatic compound comprising the steps of:

- halogenating said C₁₀ acyclic terpene hydrocarbon to produce an allylic halide having a halogen allylic to a terminal olefinic site;
- forming the Grignard reagent RMgX of said C₁₀ aliphatic compound, RMgX being 3,7-dimethyloctyl-magnesium halide or a compound having the same arrangement of carbon atoms and one or more points of unsaturation;
- preparing a reaction mixture comprising adding said Grignard reagent to said allylic halide said reaction mixture including a transition metal catalyst and a dipolar aprotic solvent;
- removing from said reaction mixture a C₂₀ compound in which coupling of the Grignard reagent and allylic halide occurs by displacement by R of the Grignard reagent at the terminal olefinic site of the allylic halide accompanied by double bond migration and loss of halide; and
- converting the coupling product to a polydehydrophytol or dehydrophytol.

4,293,498

PREPARATION OF MALEIC ANHYDRIDE

Michael F. Lemanski, Cleveland; Noel J. Bremer, Stow, and Ernest C. Milberger, Solon, all of Ohio, assignors to Standard Oil Co., Cleveland, Ohio

Filed Oct. 22, 1980, Ser. No. 199,148

Int. Cl.³ C07D 307/60

U.S. Cl. 260—346.75

10 Claims

1. A process for the production of maleic anhydride by the oxidation of n-butane, n-butene, 1,3-butadiene or a mixture thereof with molecular oxygen or oxygen-containing gas in the vapor phase at a reaction temperature of 250° C.-600° C. in the presence of a catalyst containing the mixed oxides of vanadium and phosphorus, wherein said catalyst is prepared by

- introducing a pentavalent vanadium-containing compound into an olefinic, halogenated organic liquid-containing liquid medium,
- effecting reduction of at least a portion of said vanadium to a valence state of about +4;
- adding a phosphorus-containing compound to said medium before or after effecting said reduction to form a catalyst precursor;
- recovering the catalyst precursor;
- drying the catalyst precursor;
- calcining the catalyst precursor.

4,293,499

PROCESS FOR PRODUCING A CARBOXYLATE ESTER USING A SUPPORTED ACIDIC CATALYST

O. Richard Hughes, Chatham, N.J., assignor to Celanese Corporation, New York, N.Y.

Filed Feb. 8, 1980, Ser. No. 119,682

Int. Cl.³ C07C 67/05

U.S. Cl. 260—410.9 R

19 Claims

1. A process for producing a carboxylate ester which comprises contacting a mixture of a monoolefin containing between about 2-12 carbon atoms and a carboxylic acid containing between about 1-20 carbon atoms with a strongly acidic solid catalyst at a temperature in the range between about 100°-400° C., wherein said solid catalyst comprises a composite of between about 0.5-40 weight percent, based on catalyst weight, of 5-sulfoisophthalic acid in combination with a carrier substrate having a surface area between about 1-1000 m²/gram.

4,293,500

UNSATURATED ESTERS AND METHOD OF PREPARING THEM

Didier Morel, Lyon, France, assignor to Rhone-Poulenc Industries, Saint-Fons, France

Filed Mar. 4, 1980, Ser. No. 127,047


Claims priority, application France, Mar. 12, 1979, 79 06214

Int. Cl.³ C07C 67/28

U.S. Cl. 260—410.9 R

15 Claims

1. A mixture of unsaturated esters of the formula ACOOR₁, in which R₁ represents an alkyl group having from about 1 to 6 carbon atoms and "A" is selected from the group consisting of hydrocarbon radicals of the formulae:



4,293,502

NICKEL YLIDES

David L. Beach, Gibsonsia, and James J. Harrison, Glenshaw, both of Pa., assignors to Gulf Research & Development Company, Pittsburgh, Pa.


Filed Aug. 18, 1980, Ser. No. 179,079

Int. Cl.³ C07F 15/04

U.S. Cl. 260—439 R

19 Claims

1. A nickel ylide defined by the following formula:



wherein R₁, R₂, R₃, R₄, R₅, R₆, R₇ and R₈ are either alike or different members selected from the group consisting of hydrogen, alkyl radicals having from about one to about 24 carbon atoms, aryl radicals having from about six to about 20 carbon atoms, alkenyl radicals having from about two to about 30 carbon atoms, cycloalkyl radicals having from about three to about 40 carbon atoms, aralkyl and alkaryl radicals having from about six to about 40 carbon atoms, halogen radicals, hydroxyl, alkoxy and aryloxy groups, and hydrocarbyl groups carrying halogen, hydroxyl, alkoxy or aryloxy, provided that at least one of each of R₁ to R₈ radicals is a sulfonate group or an alkyl, aryl, alkenyl, cycloalkyl, aralkyl or alkaryl carrying a sulfonate group, M is sulfur or oxygen, E is phosphorus, arsenic, antimony or nitrogen and F is phosphorus, arsenic or antimony.

4,293,503

SYNTHESIS OF POLYOL BIS(ALLYL CARBONATE) UTILIZING REAGENT RECOVERY AND RECYCLE

Elgin E. Young, Norton, Ohio, assignor to PPG Industries, Inc., Pittsburgh, Pa.


Filed Jan. 10, 1980, Ser. No. 111,146

Int. Cl.³ C07C 69/96


U.S. Cl. 260—463

13 Claims

1. In a method of forming bis(allyl carbonate) monomer represented by the formula:




where R₁ and R₃ are allyl groups represented by the formula:




where R' is chosen from the group consisting of H, a halogen, and a 1 to 4 carbon alkyl group, and R₂ is chosen from the group consisting of alkylene groups, alkylene ether groups, and alkylene polyether groups, comprising:

- forming a first reaction solution of bis(chloroformate) and allyl alcohol;
- adding aqueous alkali metal hydroxide to the reaction solution whereby to form bis(allyl carbonate); and
- recovering (1) an organic phase containing bis(allyl carbonate) monomer, and (2) an aqueous phase containing water soluble organics and unreacted allyl alcohol reagent: the improvement comprising:
 - distilling said aqueous phase into a high-boiling residue and a low-boiling distillate, wherein said distillate contains a water-allyl alcohol azeotrope; and



in which R₂ to R₁₇, inclusive, being identical or different, represent a member selected from the class consisting of a hydrogen atom and an alkyl radical having from about 1 to 3 carbon atoms, wherein said unsaturated ester in which hydrocarbon radical "A" has the formula:



is the major component of said mixture.

4,293,501

β-LACTAM ANTIBIOTICS, A PROCESS FOR THEIR PREPARATION AND THEIR USE IN PHARMACEUTICAL COMPOSITIONS

Roger J. Ponsford, Horsham; Andrew J. G. Baxter, Hull, and Robert Southgate, Warnham, all of England, assignors to Beecham Group Limited, England

Division of Ser. No. 4,896, Jan. 19, 1979, Pat. No. 4,255,441.

This application Dec. 14, 1979, Ser. No. 103,562


Claims priority, application United Kingdom, Mar. 14, 1978, 0998578

Int. Cl.³ C07F 1/10, 1/02, 1/04

U.S. Cl. 260—430

6 Claims

1. The sodium, thallium, silver or lithium salt of a compound of the formula:



wherein

n is 1 or 2, and

R₆ is lower alkyl, phenyl or phenyl substituted by one or two members selected from the group consisting of halo, lower alkyl or lower alkoxy.

(b) feeding said distillate to a second reaction solution containing bis(chloroformate).

4,293,504

PROCESS FOR PREPARING OPTICALLY ACTIVE α -CYANO-3-(4-HALOGENOPHENOXY)-BENZYL 2-(4-CHLOROPHENYL)ISOVALERATE


Yukio Suzuki, Toyonaka; Kiyoshi Kasamatsu, Takarazuka, and Kohichi Aketa, Kawanishi, all of Japan, assignors to Sumitomo Chemical Company, Limited, Osaka, Japan
Filed Feb. 5, 1980, Ser. No. 118,716

Claims priority, application Japan, Feb. 5, 1979, 54-12500
Int. Cl.³ C07C 121/75

U.S. Cl. 260—465 D

9 Claims

1. A process for preparing the compound (S)- α -cyano-3-(4-halogenophenoxy)benzyl (S)-2-(4-chlorophenyl)isovalerate, substantially free of other isomers, which comprises crystallizing said compound from a solution of the compound of the formula



wherein X is a fluorine atom, a chlorine atom or a bromine atom, and * indicates an asymmetric carbon atom, having an (S)-configuration on the acid moiety with or without being seeded with crystals in the presence or absence of a basic catalyst, and separating the crystal of said compound from the mother liquor.

4,293,505

PREPARATION OF β -HALOETHYLPHOSPHONIC ACIDS AND HALF ESTERS THEREOF


David I. Randall, 417 Dogwood Ter., Easton, Pa. 18042
Division of Ser. No. 872,766, Oct. 30, 1969, which is a continuation-in-part of Ser. No. 628,839, Apr. 6, 1967. This application Jan. 31, 1980, Ser. No. 117,334

Int. Cl.³ C07F 9/40


U.S. Cl. 260—983

10 Claims

1. A process for producing β -haloethylphosphonic acid which comprises introducing anhydrous HCl or HBr from an outside source into a diester stable at a temperature above 140° C. and having the formula



wherein R₁ is haloethyl and R₂ and R₃ represent alkyl or haloalkyl containing no more than 6 carbon atoms, at a temperature of about 140° C. to 165° C. until a product is obtained containing about 3 to 40% of the corresponding monoester of the formula



no more than 5% of dehydrohalogenated impurities, no more than about 5% of other impurities, and the balance β -haloethylphosphonic acid or anhydride.

4,293,506

LIQUID CIRCULATING DEVICE

Peter Lipert, Dollard des Ormeaux, Canada, assignor to Atara Corporation, Dorval, Canada


Continuation-in-part of Ser. No. 3,707, Jan. 15, 1979, Pat. No. 4,187,263. This application Jul. 5, 1979, Ser. No. 54,826

The portion of the term of this patent subsequent to Feb. 5, 1997, has been disclaimed.

Int. Cl.³ B01F 3/04

U.S. Cl. 261—77

18 Claims



1. A device for creating circulation within a body of liquid, the device comprising a substantially vertically extending stackpipe means designed to be wholly submerged within the liquid, the stackpipe having an upper discharge opening and a lower inlet opening; a large-bubble generator means located adjacent the stackpipe and comprising a gas-accumulator chamber having a peripheral wall, a top wall, and an opening at the chamber bottom; a substantially vertically extending standpipe adjacent the accumulator chamber and the stackpipe; an inverted siphon defining fluid flow connecting means between the upper portion of the accumulator chamber and the standpipe; means for delivering gas under pressure into the accumulator chamber; transverse gas flow conduit means between the upper end of the standpipe and the stackpipe, the transverse conduit connecting through the peripheral wall of the stackpipe; and secondary liquid inlet means into the transverse conduit between the standpipe and the stackpipe.

4,293,507

PREPARATION OF SHAPED BODIES

Peter W. Sutcliffe, Abingdon; Jim W. Isaacs, Harwell; Robert L. Nelson, Kingston; Colin E. Lyon, Charlton Heights, and Brian Stringer, East Hendred, all of England, assignors to United Kingdom Atomic Energy Authority, London, England
Filed May 17, 1979, Ser. No. 39,964

Claims priority, application United Kingdom, May 26, 1978, 23671/78

Int. Cl.³ G21C 21/02

U.S. Cl. 264—0.5

14 Claims

1. A method for the preparation of a shaped body comprising cold pressing a material consisting essentially of gel particles produced by the gel precipitation process to give the shaped body, wherein the material has not been substantially comminuted prior to cold pressing.

4,293,508

METHOD AND APPARATUS FOR LONGITUDINALLY STRETCHING A SUBSTANTIALLY AMORPHOUS POLYETHYLENE TEREPHTHALATE FILM

Wilfried A. Heirbaut, Haasdonk, and Walter J. Rens, Kontich, both of Belgium, assignors to AGFA-GEVAERT N.V., Mortsel, Belgium


Filed Apr. 11, 1980, Ser. No. 139,558

Claims priority, application United Kingdom, Apr. 11, 1979, 12859/79

Int. Cl.³ B29C 17/02; B29D 9/00; B32B 27/06

U.S. Cl. 264—25

24 Claims



1. A process of longitudinally stretching a substantially amorphous polyethylene terephthalate film during its longitudinal conveyance in which longitudinal stretching forces are applied to the film by first and second traction means located at spaced positions along the path of conveyance of the film, while heating the film between said first and second traction means by means of infrared radiation to a temperature such that the film undergoes plastic elongation under said stretching forces, and then cooling the stretched film, characterized by the steps of maintaining the temperature of the first traction means not higher than 65° C., carrying out said heating by directly and symmetrically exposing both sides of the film first to diffused IR-radiation to increase the film temperature but not sufficient for plastic elongation to occur, thereby preheating the film, and then to concentrated infrared radiation to heat the film to a temperature between 100° and 120° C. whereby rapid plastic elongation of the film occurs under said stretching forces, and then rapidly cooling the film to below its second order transition temperature, before it reaches the second traction means, by bringing the two sides of the film symmetrically into contact with a cooling liquid.

13. Apparatus for longitudinally stretching a substantially amorphous polyethylene terephthalate film comprising:

first driven roller means for feeding said film at a first speed in a zone where the film is freely supported, means for maintaining the temperature of said first roller means lower than 65° C.,

second driven roller means for removing the cooled film from said zone at a second speed that is higher than said first speed to cause the film to be stretched in said zone, first IR-heaters disposed symmetrically at both sides of the film path through said zone for producing IR-radiation thereby to heat the film to a temperature at which it does not yet become stretched,

second IR-heaters disposed transversely and symmetrically at both sides of the film path, for heating the film to a temperature between 100° and 120° C. to effect stretching thereof,

a bath of cooling liquid into which the stretched film is immersed,

means in said bath for keeping the free surface of said cooling liquid at the entry region of the film quiescent, and roller means disposed below the level of the cooling liquid in said bath for terminating the zone where the film is free supported.

4,293,509

PROCESS FOR THE PRODUCTION OF CHIPBOARDS, FIBERBOARDS, OR LIKE BOARDS

Günter Bücking, Spring, Fed. Rep. of Germany, assignor to Bison-werke Bähre & Greten GmbH & Co. KG, Spring, Fed. Rep. of Germany


Filed Dec. 17, 1979, Ser. No. 104,703

Claims priority, application Fed. Rep. of Germany, Dec. 15, 1978, 2854336

Int. Cl.³ B29J 5/02

U.S. Cl. 264—26

15 Claims



1. Process for the production of chipboards, fiberboards, and like boards from particles which are electrically nonconductive and have a poor thermal conductivity, comprising the steps of combining the particles with at least one binder and with water, forming a chip or like layer on a moving support, preheating said layer by high-frequency and thereafter pressing the layer into boards with the use of contact heat that produces a steam blast that is effective from the outside of the layer toward the inside, characterized in that the layer is provided initially with the same amount of moisture throughout, which amount is sufficient to produce, by means of and during the high-frequency preheating step, a steam blast which proceeds from the inside of the layer into the surface zone thereof.

4,293,510

METHOD OF LINING CLOSURES


Robert W. George, Naperville; Casper W. Miller, Mundelein, and Kenneth Rapey, Chicago, all of Ill., assignors to National Can Corporation, Chicago, Ill.

Division of Ser. No. 906,770, May 18, 1978, abandoned. This application May 18, 1980, Ser. No. 133,261

Int. Cl.³ B29C 13/02

U.S. Cl. 264—40.7

3 Claims



1. A method of producing lined cap closures at a rate of more than one-thousand per minute with a continuously rotating feed wheel having a plurality of pockets, a molding and curing head having a plurality of stations and a take-off wheel having a plurality of pockets all rotating at said rate, aligning a dispensing unit above the path of movement of the pockets for

said feed wheel with the dispensing unit having an elongated generally circular chamber having an upper inlet and a lower outlet with a polygonal plunger reciprocated in said chamber to open and close said outlet and a solenoid surrounding said chamber, a surface of said chamber and said polygonal plunger defining flow paths between said upper inlet and said lower outlet, delivering unlined closures to the respective pockets of said feed wheel, delivering a continuous supply of pressurized liquid lining compound at substantially room temperature under pressure to said upper inlet of said dispensing unit, sensing the position of the pockets of the feed wheel with respect to the path for said pockets, actuating said solenoid each time a pocket is aligned therewith to raise said plunger and open said outlet to cause said compound to flow through said flow paths along said surface of said chamber and said lower outlet toward said closures while maintaining said dispensing unit at substantially room temperature, and heating each of said stations sufficiently to cure said compound between the inlet and outlet for said closures from the head to cure said compound.

4,293,511


PROCESSES AND PRODUCTION APPARATUS FOR RIGID CELLULAR MATERIALS COMPRISING POLYVINYL CHLORIDE

Michel Vernon, Trilport, France, assignor to K.R.P. Plastiques, Trilport, France

Continuation-in-part of Ser. No. 958,026, Nov. 6, 1978, abandoned. This application Oct. 10, 1980, Ser. No. 195,760
Claims priority, application France, Nov. 9, 1977, 77 33693
Int. Cl.³ B29D 27/00

U.S. Cl. 264—55

28 Claims



1. In a process for producing rigid cellular plastic by treatment of an embryonic block of PVC containing a polyisocyanate, with a hot fluid comprising water selected from the group consisting of liquid water and water vapor, the improvement comprising:

introducing said embryonic block into a closable expansion box into which the hot fluid can pass and having side walls, a bottom wall and a top wall, and further containing a centering and holding means for the embryonic block, said expansion box being of predetermined, fixed internal maximum dimensions, closing said expansion box and centering and holding said embryonic block in place with said centering and holding means;

introducing said closed box containing said embryonic block into a first bath of said hot fluid at a temperature of about 80°–85° C. for a sufficiently long period to pre-heat said embryonic block to a uniform temperature;

removing said closed expansion box from said first bath and immersing it into a second bath of said hot fluid at a temperature of about 90°–95° C. for a period sufficient to cause pre-expansion of said block;

removing said expansion box from said second bath and immersing it into a third bath of said hot fluid held at a temperature of about 95°–100° C. for a period sufficiently long to bring about expansion of said block to the internal dimensions of said expansion box and also to bring about hardening of said expanded block by reaction between said water and said polyisocyanate, the expansion of said block being performed in said closed expansion box and being controlled by means of said centering and holding means and without transferring of said block from one expansion box to another; and

cooling said expansion box containing said expanded block

for a period sufficiently long to dimensionally stabilize said expanded block.

4,293,512

MAKING TEMPERATURE-STABLE PROTECTIVELY COATED GRAPHITE MOLDED BODY

Hartmut Lühleisch, Düren; Peter Pflaum; Francisco J. Dias, both of Jülich; Aristides Nauomidis, Jülich-Koslar; Arno Schirbach, Stolberg, and Hubertus Nickel, Jülich-Koslar, all of Fed. Rep. of Germany, assignors to Kernforschungsanlage Jülich GmbH, Jülich, Fed. Rep. of Germany
Filed Nov. 14, 1979, Ser. No. 94,120

Claims priority, application Fed. Rep. of Germany, Apr. 23, 1977, 2718142; Apr. 23, 1977, 2718143

Int. Cl.³ F27B 9/14; C01B 31/36

U.S. Cl. 264—58

3 Claims

1. A method of making a temperature-stable protectively coated graphite molded body, comprising the steps of:

making a molded body by conglomerating in a mold particles of at least one carbonaceous material of at least partly graphitic composition, said particles being coated with a synthetic resin binder;

applying to said body, before any heating thereof to a coking temperature, successive layers of one or more materials of the kind or kinds used in the conglomerating step mixed with an admixture of between nearly zero atomic % and about 50 atomic % of a substance selected from the group consisting of silicon and zirconium, said substance being in the form of particles coated with said synthetic resin binder, said layers being applied in such a way that the layer nearest said molded body contains the smallest proportion of said substance and the outermost layer the highest proportional content thereof, with the other layers providing intermediate gradations of such proportional content, to produce a coated body;

heating the body after each layer application to a heat treatment sufficient to harden the binder; and

after the application of the last layer, further heating the body, first to coke the body including the layers and then, by a rapid rise of temperature to a temperature in the range of from 1500° C. to 1800° C., to convert said substance at least partially into its carbide.

4,293,513

METHOD OF MAKING HONEYCOMB STRUCTURES


Robert C. Langley, Millington; Herbert Myers, Newark, and Muriel Abrash, Paterson, all of N.J., assignors to Engelhard Minerals & Chemicals Corporation, Edison, N.J.

Continuation of Ser. No. 344,510, Mar. 26, 1973, abandoned, which is a continuation-in-part of Ser. No. 86,127, Nov. 2, 1970, abandoned. This application May 12, 1975, Ser. No. 576,640

Int. Cl.³ C04B 35/64

U.S. Cl. 264—60

10 Claims



1. A process for making a monolithic structure having a plurality of channels comprising:

(a) admixing an inorganic powder and a temporary vehicle to provide an admixture which is solid and self-supporting at room temperature and is fluid at an elevated temperature,

ture, said inorganic powder being capable of being sintered;

(b) depositing the admixture on a stencil having a plurality of masking islands;

(c) providing the admixture deposited on said stencil in a heated fluid condition;

(d) forcing the resulting heated, fluidized admixture through said stencil, thereby forming a thin lamina beneath and in contact with the bottom of said stencil, and immediately cooling said lamina by loss of heat to the ambient surroundings to form a reproduction of said stencil such that said masking islands define openings in said lamina;

(e) repeating step (d) at least about 20 times in a manner such that each lamina is formed on the top surface of the lamina previously formed so as to produce successive, overlying, cohesive laminae forming a substantially monolithic structure having a plurality of channels formed therethrough, said channels having a cross-sectional area defined by said openings provided by said masking islands, said successive, overlying, cohesive laminae being formed as a continuous structure of at least about 1/4 inch in length;

(f) heating gradually the monolithic structure to remove said vehicle and to prevent distortion of the monolithic structure; and

(g) thereafter heating said monolithic structure to a sintering temperature, and then permitting the monolithic structure to cool, said structure exhibiting a condition of mechanical strength sufficient to be self-supporting.

4,293,514

METHOD OF PRODUCING HONEYCOMB STRUCTURAL BODIES CONSISTING OF BARIUM TITANATE SERIES CERAMICS HAVING A POSITIVE TEMPERATURE COEFFICIENT OF ELECTRIC RESISTANCE

Shigetaka Wada, Kuwana, Japan, assignor to NGK Insulators, Ltd., Nagaya, Japan

Continuation of Ser. No. 851,705, Nov. 15, 1977, abandoned.

This application Mar. 2, 1979, Ser. No. 16,832

Claims priority, application Japan, Nov. 26, 1976, 51-141093

Int. Cl.³ C04B 35/46

U.S. Cl. 264—61

6 Claims

1. A method of producing a honeycomb structural body consisting of barium titanate series ceramics having a positive temperature coefficient of electric resistance, comprising kneading raw material powders, which contain at least 50% by weight of powders having perovskite type crystal structure and have a particle size distribution that 5–50% by weight of the raw material powders has a particle size of not smaller than 10 μm and 10–60% by weight thereof has a particle size of not larger than 2 μm, together with water and at least two kinds of organic binders to prepare a green mass, extruding the green mass into a honeycomb shaped article, drying the extruded article by blowing air through the channels of the honeycomb article at a rate of at least 50 cm/sec until the water content of the article becomes less than 5% by weight wherein the temperature of the air employed is less than 40° C., and firing the dried article, wherein said at least two kinds of organic binder are different by at least 50° C. in the decomposition temperature or weight decreasing temperature between a binder having the highest decomposition temperature or weight decreasing temperature and another binder having the lowest decomposition temperature of weight decreasing temperature.

4,293,515

MANUFACTURE OF PLASTICS PRODUCTS

William J. Mair, Merrow, near Guildford, England, assignor to Plastic Recycling Limited, England


Filed Sep. 10, 1979, Ser. No. 73,615

Claims priority, application United Kingdom, May 11, 1979, 16510/79

Int. Cl.³ B27J 5/00

U.S. Cl. 264—120

5 Claims



1. A method of manufacturing a plastics product from a raw material containing at least 50% by weight reclaimed synthetic thermoplastics material, comprising the steps of:

forming a mat of the raw material in particulate form on a conveyor belt;

heating the mat of material by conveying the mat through an oven on the conveyor belt to cause the thermoplastics material in the mat to soften; and

compressing the softened mat downstream of the oven between said conveyor belt and a further belt passing around three rollers arranged generally one above the other to define a first passage between the upper and middle rollers and a second passage between the middle and lower rollers, the mat passing from the oven through said first passage, around the middle roller to said second passage, and then around the lower roller to continue in the direction away from the oven, the middle and lower rollers being of substantially greater diameter than the upper roller, while cooling the mat at least as it passes around said middle roller, whereby the softened thermoplastics material binds the pieces of other material in the mat to thus produce a unitary, continuous, indefinite length sheet.

4,293,516

PROCESS FOR SPINNING BICOMPONENT FILAMENTS

Paul C. Parkin, Harrogate, England, assignor to Imperial Chemical Industries, Limited, London, England

Division of Ser. No. 97,067, Nov. 23, 1979, Pat. No. 4,251,200.


This application Jun. 24, 1980, Ser. No. 162,354

Claims priority, application United Kingdom, Nov. 30, 1978, 46637/78

Int. Cl.³ D01D 5/22

U.S. Cl. 264—168

4 Claims



1. A process for the production of sheath/core bicomponent fibers using a spinning assembly comprising a spinneret plate

having at least one counter-bore terminating in an extrusion orifice, a distributor plate spaced apart from but facing the spinneret plate to provide a liquid channel therebetween, the distributor plate being provided with an aperture opposite each orifice in the spinneret plate, and a plateau like protrusion extending about the axis common to the aperture of the distributor plate and the extrusion orifice of the spinneret plate to constrict the liquid channel in a region surrounding the entrance to the counter-bore of the extrusion orifice, in which core forming material flows into the apertures provided in the distributor plate and sheath forming material flows into the liquid channel between the distributor plate and the spinneret plate, the improvement being that the flow of the sheath forming material into the entrance to the counter-bore of the extrusion orifice is restricted by an orifice plate provided in the spinning assembly.

4,293,517

DIE WITH INSERT AND ITS USE


Kenneth L. Knox, Circleville, Ohio, assignor to E. I. Du Pont de Nemours and Company, Wilmington, Del.

Filed Apr. 14, 1980, Ser. No. 139,796

Int. Cl.³ B25F 3/04

U.S. Cl. 264—176 R

9 Claims



1. An extrusion die comprising:

- (a) a die structure having an internal chamber with at least one inlet and an outlet of parallel, spaced-apart, die lands extending along the length of the die structure to form an outlet slit; the internal chamber having two opposing inner walls of substantially flat surfaces, each with one edge parallel with the die lands and diverging away from the die lands at an acute angle with respect to the plane of the die land surfaces; and
- (b) an insert for at least one end of the die, located in, and extending into, the internal chamber, between the inner walls from the end of the die to the end of the insert; the insert, (i) having a downstream edge directed toward the outlet slit and formed as a result of the intersection of two downstream surfaces, (ii) having diminishing downstream surfaces from the end of the die to a point at the end of the insert, and (iii) having a spaced-apart relationship with the inner walls such that the downstream surfaces are spaced apart from the neighboring inner walls substantially the same distance.

9. A process for making a film of thermoplastic material having indefinite length, large lateral extension, substantially constant center thickness, and edges with thickened beads by forming a molten stream of thermoplastic material in laminar flow and conducting it to a chilled surface

wherein the improvement comprises, in forming the molten thermoplastic material before conducting it to the chilled surface; separating the stream of molten thermoplastic material, at the edges, by means of a streamlined insert having diminished surface area from the edge of a point at the end of the insert to divert a portion of the material toward the center and pass the remainder of the material in separated streams; conducting the separated streams toward each other at

substantially equal acute angles with the direction of flow; and rejoining the separated streams immediately beyond the insert in a line perpendicular to the direction of flow.

4,293,518

CONTROL OF SYNTHETIC YARNS DURING DRAWING WITH HEATED ROLLS


Willis D. Bethay, Jr., Camden, S.C., assignor to E. I. Du Pont de Nemours and Company, Wilmington, Del.

Filed Jul. 31, 1980, Ser. No. 174,254

Int. Cl.³ D01D 5/12

U.S. Cl. 264—210.2

3 Claims



1. An improved coupled spin-draw-bulking process for making a synthetic bulked continuous multifilament yarn in which process the yarn is melt-spun, and then drawn in frictional contact with one or more draw pins which are located between and are substantially parallel to a feed roll and a pair of heated draw rolls on which the drawn yarn is preheated in preparation for bulking, wherein the improvement comprises stabilizing the path of the yarn on the one or more draw pins and on the heated draw rolls by passing the yarn just before it contacts the one or more draw pins, between two fixed substantially parallel guide pins in tandem in a zig-zag path such that each pin creates a change of direction break angle in the yarn path of from about 0° to 14° while maintaining the yarn in substantially ribbon form, with the axes of the pins being oriented with respect to the yarn path between the feed roll and the one or more draw pins so as to cause the plane of the yarn ribbon to rotate about the yarn axis by an angle of from about 50° to 90° with respect to the plane of the ribbon as it leaves the feed roll surface and as it first contacts a draw pin, and then forwarding the yarn to the heated draw rolls from the last draw pin without further contact with any guiding surface.

4,293,519

METHOD FOR POTTING AND ENCAPSULATING ELECTRONIC CIRCUITS

Thomas A. Knappenberger, Phoenix, and James F. Landers, Jr., Tempe, both of Ariz., assignors to Motorola Inc., Schaumburg, Ill.

Division of Ser. No. 890,434, Mar. 27, 1978, abandoned. This application Oct. 4, 1979, Ser. No. 81,703

Int. Cl.³ B29D 6/02

U.S. Cl. 264—272.13

2 Claims

1. A method of potting an electronic circuit utilized in high acceleration and high thermal cycling environments comprising the steps of:

- (a) selecting an uncured compound consisting essentially of thermosetting resin and curing agent in a flowable powder form with a particle size in the range of approximately 60 mesh to 200 mesh, curable in a temperature range of approximately 125° F. to 212° F. at approximately ambient pressure and which produces, in a vacuum of less than 10⁻⁵ Torr, outgassing of a maximum of 0.1 percent vola-

tile condensable materials and a maximum of 1.0 percent weight loss;

- (b) selecting a quantity of hollow microspheres having a diameter in the range of approximately 5 microns to 300 microns;
- (c) mixing said compound and said microspheres into a substantially homogeneous mixture consisting essentially of said compound and said microspheres in a predetermined ratio in the range of approximately 35 percent to 45 percent resin-curing agent to microspheres by weight;
- (d) partially enclosing the electronic circuit with a form to limit the flow of potting material;
- (e) pouring the homogeneous mixture in the form to surround the electronic circuit with mixture; and
- (f) heating the mixture to the required temperature for curing in a temperature range of approximately 125° to 212° F. at approximately ambient pressure.

4,293,520

PROCESS FOR MOLDING PARISON FOR MAKING STRETCH MOLDED BOTTLE


Masao Akutsu, Tokyo, Japan, assignor to Yoshino Kogyosho Co., Ltd., Tokyo, Japan

Filed Sep. 18, 1979, Ser. No. 76,750

Int. Cl.³ B29C 17/04, 17/07, 17/10; B29D 23/02

U.S. Cl. 264—513

2 Claims



1. A process for molding a parison for making a stretch molded bottle, comprising heating a material of a saturated polyester resin, particularly polyethylene terephthalate, in the form of a relatively thick flat plate to a temperature at which said material may be biaxially stretched, stretching said material biaxially in four directions to form a stretched material, heating said stretched material again to a temperature at which said material may be biaxially stretched, impact or vacuum molding said stretched material into a short cylindrically shaped, closed bottomed article having a neck portion and a bottom portion, removing said bottom of said article, inserting said neck portion over the base portion of a core, placing about said core and neck portion a mold to define a mold cavity, and molding within said cavity a cylindrically shaped body portion having a closed bottom from the same resinous material as that of which said neck portion is made, said body portion having an inside diameter equal to the inside diameter of said neck portion and being integrally united with said neck portion to form a parison.

4,293,521

APPARATUS FOR CLEANING WASTE FLUE GASES

Fumio Isahaya, Hitachi, and Tugihito Yukitake, Ibaraki, both of Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Division of Ser. No. 801,328, May 27, 1977, Pat. No. 4,208,381, which is a continuation of Ser. No. 197,356, Nov. 10, 1971, abandoned. This application Dec. 14, 1979, Ser. No. 103,572

Claims priority, application Japan, Dec. 4, 1970, 45/107811


Int. Cl.³ G01N 25/56, 25/66; B01D 53/54

U.S. Cl. 422—62

13 Claims

1. A waste flue gas cleaning apparatus comprising a vaporizing tower having an inlet and an outlet for a waste flue gas and

equipped with spray means for spraying a reactant solution in an atomized state into the waste flue gas introduced into said tower, detectors for detecting the flow rate of the inlet gas and the concentration of a toxic component contained in the waste flue gas at the inlet of the tower, respectively, and means for supplying the reactant solution to said spray means after adjusting the ratio between an amount of water, to be admixed



with the reactant solution, and the reactant solution, said reactant solution supplying means being operative in response to signals from said detectors and to a signal from a gas temperature or humidity detector provided at the outlet of said tower whereby the reaction products produced within said tower are formed into solid particles at a temperature above the dew point of the waste flue gas.

4,293,522

ELECTROPHOTOLYSIS OXIDATION SYSTEM FOR MEASUREMENT OF ORGANIC CONCENTRATION IN WATER


H. Eugene Winkler, Friendswood, Tex., assignor to The United States of America as represented by the Administrator of the National Aeronautics and Space Administration, Washington, D.C.

Filed May 21, 1979, Ser. No. 41,145

Int. Cl.³ G01N 31/12

U.S. Cl. 422—80

7 Claims



1. An oxidation cell for oxidizing organic carbon contained in aqueous solution comprising, in combination:

- (a) an ultraviolet radiation source in radioactive communication with said aqueous solution;
- (b) means for forming a chamber to contain said aqueous solution;
- (c) electrolytic cell means adjacent said chamber forming means for electrolyzing water and for forming a barrier to maintain said aqueous solution within said chamber, said

electrolytic cell means comprising an anode adjacent said aqueous solution chamber, a solid, water impermeable electrolyte member in electrical contact with said anode and a cathode in electrical contact with said electrolyte member;

- (d) hydrogen cavity forming means adjacent said cathode;
- (e) means for admitting aqueous solution to said chamber;
- (f) means for removing aqueous solution from said chamber; and
- (g) means for removing hydrogen from the hydrogen cavity.

4,293,523

APPARATUS FOR PRODUCING POTASSIUM SILICATE FERTILIZER


Hiroshi Segawa, Tokyo, and Katsufumi Akizuki, Yokohama, both of Japan, assignors to Denpatsu Fly Ash, Tokyo, Japan Division of Ser. No. 48,121, Jun. 13, 1979. This application Aug. 12, 1980, Ser. No. 177,698

Claims priority, application Japan, Jun. 13, 1978, 53-70380

Int. Cl.³ B01J 6/00, 8/26, 8/24; F27B 15/08

U.S. Cl. 422-139

11 Claims



1. An apparatus for producing a citric acid soluble potassium silicate fertilizer comprising:

- (a) a plurality of continuous quantitative feeders for supplying a binder, a potassium source, fly ash and pulverized coal for forming a mixture;
- (b) a continuous kneader for continuously kneading said mixture;
- (c) an extruder for forming the resulting kneaded mixture into granules;
- (d) a fluidized dryer for drying the granules to a state of substantially absolute dryness;
- (e) a fluidized calcining furnace for calcining dried granules in order to chemically react potassium with silicon present in the fly ash and thereby form a citric acid soluble potassium silicate; and
- (f) a cooling device for cooling the resulting calcined product.

4,293,524

METHOD AND APPARATUS FOR COOLING AND NEUTRALIZING ACID GASES

Aaron J. Teller, Westboro; Denis R. J. Roy, and Shih K. Lin, both of Shrewsbury, all of Mass., assignors to Teller Environmental Systems, Inc., Worcester, Mass.

Continuation of Ser. No. 944,076, Sep. 20, 1978, abandoned. This application Jun. 18, 1980, Ser. No. 160,443

Int. Cl.³ B01J 10/00; B01D 53/34

U.S. Cl. 422-169


4 Claims

1. An apparatus for treating an effluent gas which gas contains acidic components of varying particle size which comprises:

- (a) a first chamber having an inlet and an outlet, the outlet being positioned above the inlet, the chamber being configured as a truncated cone, the inlet in communication with the base of the chamber and substantially perpendicular to the longitudinal axis of the chamber, the inside walls of the chamber sloping upwardly and inwardly

whereby the effluent gas introduced into the first chamber moves upwardly in a spiral path within said chamber effecting removal of the larger particles from the gas;

- (b) a particle collection means disposed below the base of the first chamber to receive the particles removed in the first chamber;
- (c) a second cylindrical-shaped chamber downstream of the first chamber and in communication therewith, the chamber configured to cause the gas to flow in an upward direction; and being free of structural interference from one end to the other;
- (d) adjustable spray nozzle means to introduce a spray of a basic material in a direction



- cocurrent with the upwardly moving effluent gas, said means including a discharge end, said end positioned at the apex of the first chamber such that the stream contacts the effluent gas after it has followed its spiral path and flowed into the second chamber; and
- to control the residence time and to cause reaction of the basic spray and acidic components while the spray and the acidic components move upwardly in the second chamber to evaporate substantially all of the spray; and to form a dry stream with entrained acid salts, the dry stream exiting from the chamber being substantially free of acid gases;
- (e) means for removing products of said reaction from the effluent stream after the stream has left the chamber.

4,293,525

APPARATUS FOR RECOVERING SULFUR FROM GASES CONTAINING HYDROGEN SULFIDE

Hermann Reitzenstein, No. 9, Amselweg, 8213 Aschau, Fed. Rep. of Germany

Filed Jun. 4, 1980, Ser. No. 156,453

Claims priority, application Fed. Rep. of Germany, Nov. 30, 1978, 2851802

Int. Cl.³ B01J 8/02, 10/00, 12/02


U.S. Cl. 422-176

12 Claims

1. An apparatus for recovering sulfur from gases containing hydrogen sulfide, said apparatus comprising:

- (a) a first reaction chamber for the reaction of liquid sulfur with oxygen;
- (b) a plurality of nozzles installed one on top of another loosely in said first reaction chamber in the direction of flow of the materials flowing into said chamber to give as complete mixing and circulation of the constituents of a mixture as possible, slit-shaped orifices being provided

- between said nozzles in order to mix and circulate the reactants, and
- (c) a second reaction chamber for the subsequent mixing and reaction of the sulfur dioxide formed in said first reaction chamber with the hydrogen sulfide content of the gas mixture to be treated, containing hydrogen sulfide,



- (d) said two reaction chambers being connected to one another by means of orifices in such a way that the reactions of sulfur with oxygen and of sulfur dioxide with hydrogen sulfide take place at separate locations and successively.

4,293,526

PROCESS AND APPARATUS FOR THE CONDENSATION OF SOLIDS

Klaus Sommer, Heidelberg; Walter Klemm, Weinheim Ortsteil Rippenweier; Hermann Weber, Hemsbach; Frederick Meinhardt, Birkenheide; Gerhard Schönmann, Ludwigshafen, and Wilhelm Spatz, Ober-Kainsbach, all of Fed. Rep. of Germany, assignors to Benckiser-Knapsack GmbH, Ladenburg, Fed. Rep. of Germany


Filed Feb. 22, 1980, Ser. No. 123,754

Claims priority, application Fed. Rep. of Germany, Feb. 26, 1979, 2907453

Int. Cl.³ F28D 21/00

U.S. Cl. 422-205

6 Claims



- 1. Apparatus for condensing solid materials which tend to sinter and adhere during condensation in a heated reactor, said apparatus comprising: a reactor housing having an exterior wall, means for heating the exterior wall of said reactor housing; at least one set of rotatable paddles disposed in the interior of said reactor housing for agitating solid material in said reactor housing, at least one paddle of each set being provided with blade means which passes closely adjacent the wall of said reactor housing when said set of paddles is rotated for stripping sintered material from said reactor wall; duct means communicating with the interior of said reactor housing for withdrawing waste gases from said reactor housing; means for drawing waste gases through said duct means; and means for introduc-

4,293,527 METALS EXTRACTION FROM SEA WATER


Dean T. Morgan, Sudbury; Chrysostomos Chrysostomidis, Cambridge, and George J. LaRue, Wayland, all of Mass., assignors to Thermo Electron Corporation, Waltham, Mass.

Filed May 14, 1980, Ser. No. 149,866

Int. Cl.³ C02F 1/28

U.S. Cl. 423-6

14 Claims



- 1. A method of extracting uranium from sea water which utilizes adsorber sheets comprising the steps of deploying said sheets in a current of sea water, moving said deployed sheets through said sea water to adsorb uranium, winding said sheets on perforated hollow bobbins to form rolls, and eluting uranium from said wound sheets by passing elutant from inside said bobbins through said rolls.

4,293,528

YELLOWCAKE PROCESSING IN URANIUM RECOVERY

James M. Paul, DeSoto, Tex., assignor to Mobil Oil Corporation, New York, N.Y.

Filed Nov. 19, 1979, Ser. No. 95,709

Int. Cl.³ C01G 43/01

U.S. Cl. 423-7

8 Claims

- 1. In a method for the recovery of uranium wherein uranium yellowcake produced by precipitation with hydrogen peroxide and containing sodium chloride as an impurity is calcined at an elevated temperature to effect decomposition of the yellowcake to uranium oxide with the evolution of free oxygen, the improvement comprising carrying out said calcination procedure in the presence of a reducing agent which reacts with said free oxygen to retard the evolution of chlorine gas.

4,293,529

PROCESS FOR RECOVERING URANIUM FROM WET-PROCESS PHOSPHORIC ACID USING ALKYL PYROPHOSPHORIC ACID EXTRACTANTS

Stanton L. Reese, and William E. Schroeder, both of Lakeland, Fla., assignors to Uranium Recovery Corporation, Mulberry, Fla.

Filed Oct. 27, 1978, Ser. No. 955,340

Int. Cl.³ C01G 43/00

U.S. Cl. 423-10

22 Claims

- 1. Process for obtaining uranium values from an extractant consisting essentially of an alkyl pyrophosphoric acid dissolved in a water immiscible organic solvent and containing said uranium values, which comprises (1) heating said extractant to lower the distribution coefficient for uranium from phosphoric acid; and (2) stripping said extractant with a phos-

thereto as the first layer with a proteinaceous material capable of being adsorbed to the surface; contacting the surface having adsorbed thereto the hepatitis A antibody and proteinaceous material with a sample containing hepatitis A antigen; incubating the surface under conditions effective to form a complex of hepatitis A antigen and hepatitis A antibody; incubating the surface in the presence of an excess amount of radioactively labelled hepatitis A antibody, and measuring the resulting radionuclide on the surface.

4,293,539

CONTROLLED RELEASE FORMULATIONS AND METHOD OF TREATMENT

Nelson H. Ludwig, and Earl E. Ose, both of Greenfield, Ind., assignors to Eli Lilly and Company, Indianapolis, Ind.
Filed Sep. 12, 1979, Ser. No. 74,684
Int. Cl.³ A61K 9/22

U.S. Cl. 424—19

48 Claims

1. A controlled release formulation capable of delivering an effective dose of active ingredient over a prolonged period of time and biodegradable into readily metabolized substances and normal active ingredient metabolic products comprising about 5 to about 85 percent by weight of active ingredient intimately dispersed throughout a copolymer derived from about 60 to about 95 weight percent lactic acid and about 40 to about 5 weight percent glycolic acid, said copolymer having an inherent viscosity of about 0.08 to about 0.30 when measured in chloroform, a molecular weight of about 6000 to about 35000, and said copolymer being substantially free of polymerization catalyst.

4,293,540

GRANULAR CERAMIC CARRIER FOR ADMINISTRATION OF MEDICINES AND MEDICINE SUPPORTED THEREIN

Takuji Shikita, Matsubara, and Masaya Hirabayashi, Yokaichi, both of Japan, assignors to Kyoto Ceramic Co., Ltd., Kyoto, Japan

Filed Feb. 12, 1980, Ser. No. 120,916

Claims priority, application Japan, Feb. 13, 1979, 54-15917

Int. Cl.³ A61K 9/22, 33/08; A61J 3/00, 3/10

U.S. Cl. 424—26

3 Claims

3. A medicine-administering agent for the remedy of osteomyelitis to be embedded in an affected bone texture or in the vicinity thereof, comprising:
a porous ceramic carrier comprising a fired granular body of α -alumina or apatite having a particle size of from about 0.1 to 20 mm;
wherein said body has communicating pores disposed therein wherein said pores have an average size of about 1 to 200 microns and said body has a porosity of from about 5 to 50 percent; and
from about 0.1 to 30 percent by weight, based on the weight of said carrier, of an antibiotic supported on said carrier.

4,293,541

COMPOUNDS

Hugh Cairns, and Thomas B. Lee, both of Loughborough, England, assignors to Fisons Limited, London, England
Continuation of Ser. No. 963,812, Nov. 27, 1978, abandoned.
This application Apr. 25, 1980, Ser. No. 143,627

Claims priority, application United Kingdom, Nov. 30, 1977, 49761/77

Int. Cl.³ A61K 31/35; C07D 311/24; A61L 9/04

U.S. Cl. 424—45

10 Claims

1. A salt of 2,8-dicarboxy-4,6-dioxo-10-propyl-4H,6H-benzo-(1,2-b:5,4-b')dipyran with a pharmaceutically acceptable organic cation, the salt having a solubility of less than 3% w/w in water at 20.5° C.

10. A method of treatment of asthma or hay fever, which

comprises administration of a salt according to claim 1 to a patient suffering from such a condition.

4,293,542

COSMETIC COMPOSITION FOR IMPARTING TO HUMAN SKIN A COLORATION RESEMBLING A NATURAL TAN

Gerard Lang, Epinay-sur-Seine, and Serge Forestier, Claye-Souilly, both of France, assignors to L'Oreal, Paris, France
Filed May 3, 1977, Ser. No. 793,316

Claims priority, application France, May 3, 1976, 76 13164


Int. Cl.³ A61K 7/00, 7/021, 7/44, 31/44

U.S. Cl. 424—47

35 Claims

1. A cosmetic composition for imparting to human skin after exposure to sunlight a coloration resembling a natural tan comprising a cosmetic vehicle, suitable for topical application to the skin, selected from the group consisting of (i) a hydroalcoholic solution, (ii) a glycerin-alcoholic solution and (iii) a glycerine hydroalcoholic solution of at least one compound selected from the group consisting of

(a) a compound of the formula



wherein

R₁ represents hydrogen or amino,
R₂ represents hydrogen, lower alkyl or amino,
R₃ represents hydrogen, lower alkyl or amino,
R₄ represents hydrogen, lower alkyl or chlorine,
R₅ represents hydrogen, lower alkyl or hydroxy, or when R₁ is amino, R₅ can also represent amino, with the proviso that R₁, R₂ and R₃ are not simultaneously amino, and at least one of R₁, R₂ and R₃ is amino, and
(b) an acid addition salt of the compound in (a), said alcohol being ethanol or isopropanol and being present in said cosmetic vehicles (i), (ii) and (iii) in an amount between 10 and 90 weight percent thereof and said glycerine being present in said cosmetic vehicles (ii) and (iii) in an amount between 0.5 and 5 weight percent thereof, and said compound being present in an amount of 0.5–10 weight percent of said composition.

4,293,543

PROCESS AND COMPOSITION FOR THE COLORATION OF KERATIN-CONTAINING SUBSTANCES

Jean-Marie Cotte, Saint-Cyr-Au-Mont, and Philippe Potin, Billere, both of France, assignors to Societe Nationale Elf Aquitaine, Courbevoie, France

Filed Oct. 2, 1980, Ser. No. 193,397

Claims priority, application France, Oct. 3, 1979, 79 24627; Ser. 26, 1980, 80 20720

Int. Cl.² A61K 7/42, 7/12, 7/13

U.S. Cl. 424—59

14 Claims

1. A process for the coloration of a keratin-containing substance or tissue by means of a coloration agent having a ketone or aldehyde function favouring the development of coloration in the substance or tissue, in which an amino-acid is applied to the latter before, during or after treatment with the coloration agent, wherein the amino-acid contains a sulphonyl group.

4,293,544

FLUID AND SEMI-FLUID COMPOSITIONS INCLUDING BENZOATE ESTERS

Steele J. Elmi, Midland Park, N.J., assignor to Finetex Incorporated, Elmwood Park, N.J.

Continuation-in-part of Ser. No. 18,250, Mar. 7, 1979. This

application Dec. 6, 1979, Ser. No. 100,917

Int. Cl.³ A61K 7/44, 7/42, 7/15

U.S. Cl. 424—60

6 Claims

1. In a suncreening composition for application to the skin comprising a liquid vehicle together with an effective sunscreening amount of a suncreening agent dissolved in the vehicle or emulsified along with the vehicle in the composition, the improvement comprising wherein the vehicle comprises the benzoic acid esters of a mixture of C₁₂, C₁₃, C₁₄ and C₁₅ linear primary alcohols, the alcohol mixture comprising by weight from about 23% to 31% of the C₁₂ alcohol, 32% to 44% of the C₁₃ alcohol, 17% to 23% of the C₁₄ alcohol, and 12% to 18% of the C₁₅ alcohol.

4,293,545

MODIFIED PASTEURILLA MULTOCIDA BACTERIA VACCINES

Carrell J. Kucera, Lincoln, Nebr., assignor to Norden Laboratories, Inc., Lincoln, Nebr.

Filed Mar. 31, 1980, Ser. No. 135,828

Int. Cl.³ A61K 39/02

U.S. Cl. 424—92

12 Claims

1. A modified live *Pasteurella multocida* vaccine capable of inducing immunity in bovine, porcine and ovine animal species without serious side effects comprising a vaccinal amount of modified live *Pasteurella multocida* bacteria prepared by chemical modification of virulent *Pasteurella multocida* strain ATCC No. 31609 with an acridinium salt, and a carrier therefor.

9. A method of vaccinating bovine, porcine and ovine animal species comprising administering to said animals the modified live *Pasteurella multocida* vaccine of claim 1.

4,293,546

ANTHRACYCLINE ANTIBIOTICS PRODUCED BY STREPTOSPORANGIUM FRAGILIS SHEARER SP. NOV. ATCC 31519

Claude H. Nash, III, Audubon; Marcia C. Shearer, Conshohocken; Kenneth M. Snader, Hatboro; Joseph R. Valenta, Strafford, and David Cooper, Phoenixville, all of Pa., assignors to SmithKline Corporation, Philadelphia, Pa.


Filed Jul. 24, 1980, Ser. No. 171,852

Int. Cl.³ A61K 35/00

U.S. Cl. 424—119

9 Claims

1. An antibiotic, fragilomycin A of the formula



in which R represents sugars of unknown structure and wherein fragilomycin A is characterized as follows:

- red-orange solid having a melting point of 197°–199° C. (dec.);
- approximate elemental composition of 55.07 percent carbon, 6.92 percent hydrogen and 2.37 percent nitrogen;
- proposed empirical formula of C₅₄H₈₂N₂O₂₆;
- specific optical rotation: $[\alpha]_D^{25} = +29.5^\circ$ (C=0.1 methanol);
- solubility: soluble in methanol, methylene chloride and dimethyl sulfoxide; sparingly soluble in water at a pH of 6.0 or lower;
- ultraviolet absorption spectrum in methanol exhibits

absorption maxima at 438 nm, 296 (sh) nm, 264 nm, 231 nm, and 208 nm, as shown in FIG. 1;

(g) infrared absorption spectrum in KBr exhibits peaks at the following wavelengths in cm⁻¹: 3430, 2970, 2930, 2820, 1671, 1613, 1547, 1455, 1430, 1385, 1300, 1105 and 1045 as shown in FIG. 2;

(h) proton magnetic resonance spectrum in CDCl₃—CD₃OD (80 MHz) shows the following chemical shifts (ppm) 7.4–8.2 (multiplet), 4.0 (singlet), 3.8 (doublet), 3.5 (multiplet) 3.2 (singlet) and 1.2 (doublet) as shown in FIG. 3;

(i) field desorption mass spectrum at 20 ma exhibits the following fragmentation pattern (m/e) 892, 872–871, 824 and 392.

4,293,547

METHOD OF TREATING MALARIA

Charles Lewis, Kalamazoo Township, Kalamazoo County, and Robert D. Birkenmeyer, Comstock Township, Kalamazoo County, both of Mich., assignors to The Upjohn Company, Kalamazoo, Mich.


Filed Aug. 25, 1980, Ser. No. 180,986

Int. Cl.³ C07H 15/16; A61K 31/71


U.S. Cl. 424—180

34 Claims

1. A method of treating malaria comprising the systemic administration of an effective amount of a compound having the formula



wherein R₁, which can be singly or multiply substituted in any position of the pyridine ring not already substituted by R₂, is selected from the group consisting of hydrogen, alkyl and substituted alkyl wherein the alkyl portion is from 1 to 8 carbon atoms, inclusive, and isomeric forms thereof, cycloalkyl and substituted cycloalkyl, substituted oxygen, substituted nitrogen, halogen, phenyl, and substituted phenyl, —(CH₂)_n—OH, —(CH₂)_n—NR₄R₅, and isomeric forms thereof, wherein n is an integer of from 1 to 8, inclusive, R₄ and R₅ are H or alkyl of from 1 to 8 carbon atoms, inclusive, and isomeric forms thereof; wherein R₂, which can be singly substituted in any position of the pyridine ring not already substituted by R₁, is



and X is the amino function of a compound selected from the group consisting of 7(S)-halo-methyl 1-thio- α -lincosaminide and 7(R)-halo-methyl 1-thio- α -lincosaminide; the 2-phosphate; the 2-palmitate; and the pharmaceutically acceptable acid-addition salts thereof, to a mammal hosting a malarial parasite.

4,293,548

18-SUBSTITUTED PREGN-4-ENE-3,20-DIONES

Brian W. Metcalf, Mason, and J. O'Neal Johnston, Cincinnati, both of Ohio, assignors to Merrell Dow Pharmaceuticals Inc., Cincinnati, Ohio


Filed Sep. 2, 1980, Ser. No. 183,534

Int. Cl.³ C07J 5/00; A61K 31/56

U.S. Cl. 424—242

16 Claims

1. A compound of the formula:



wherein Y is hydrogen or hydroxy; Z is hydrogen or hydroxy; and R is 1,2-propadienyl, 2-alkenyl containing up to 6 carbon atoms, or 1-hydroxy-2-propynyl.

16. A method for producing a diuretic effect which comprises administering to a patient in need of such treatment an effective amount of a compound of claim 1.

4,293,549

QUINOLINYL GUANIDINES HAVING ANTIINFLAMMATORY, ANALGESIC OR ANTIPYRETIC ACTIVITY

Schneur Rachlin, Vaerlose, and Edoardo Arrigoni-Martelli, Farum, both of Denmark, assignors to Leo Pharmaceutical Products Ltd. A/S (Lovens Kemiske Fabrik Produktion-saktieselskab), Ballerup, Denmark

Filed Oct. 27, 1978, Ser. No. 955,228


Claims priority, application United Kingdom, Nov. 7, 1977, 46166/77

Int. Cl.³ A61K 31/47, 31/555; C07D 215/42

U.S. Cl. 424-245

25 Claims

1. A compound of the formula I having anti-inflammatory, analgesic or antipyretic activity and characterized by its low acute toxicity and low gastro ulcerogenic activity



in which R₁ represents hydrogen, C₁-C₆-alkyl, C₁-C₆-alkoxy, hydroxy, halogen, trifluoromethyl, or phenyl; R₂ represents hydrogen, C₁-C₆-alkyl, C₁-C₆-alkoxy, halogen, trifluoromethyl, or hydroxy; R₃ represents C₁-C₁₈-alkyl, C₃-C₈-cycloalkyl which is unsubstituted or mono- or di-substituted with methyl or ethyl, or phenyl or phenyl-C₁-C₃-alkyl in which the phenyl is unsubstituted or substituted with a methyl, methoxy, halo or trifluoromethyl group; and R₄ represents a heterocyclic ring system selected from thiazolyl, thienyl, pyrrol, thiazolyl, isothiazolyl, pyrazolyl, imidazolyl, oxazolyl, isoxazolyl, triazolyl, thiadiazolyl, tetrazolyl, pyridyl, pyridazinyl, pyrimidyl, pyrazinyl, triazinyl, oxazinyl, benzoxazolyl, benzothiazolyl and benzoimidazolyl, said ring system being unsubstituted or substituted with from 1 to 2 members of the group consisting of C₁-C₃-alkyl, C₁-C₃-alkoxy, carboxy, carbalkoxy, halogen, trifluoromethyl, hydroxy and mercapto; and pharmaceutically acceptable, non-toxic salts thereof, pharmaceutically-acceptable non-toxic metal complexes thereof or the products wherein the H of -NHR₄ is replaced by the acyl group of a carboxylic acid.

16. A pharmaceutical composition in dosage unit form for enteral, parenteral or topical treatment of humans or domestic animals suffering from arthritic diseases, which comprises as an active ingredient 0.01 g to 1 g of a compound as claimed in

claim 1 calculated as the free base together with a pharmaceutically acceptable, non-toxic carrier.

25. In the treatment of humans or domestic animals suffering from arthritic diseases, the administration of a compound as claimed in claim 1, alone or in combination with another active ingredient, in daily doses from 1 mg/kg body weight/day to 30 mg/kg body weight/day of the active ingredient(s).

4,293,550

CEPHALOSPORIN DERIVATIVES

Jürgen Blumbach, Frankfurt am Main; Walter Dürckheimer, Hattersheim am Main, and Elmar Schrinner, Wiesbaden, all of Fed. Rep. of Germany, assignors to Hoechst Aktiengesellschaft, Frankfurt am Main, Fed. Rep. of Germany

Filed Dec. 20, 1978, Ser. No. 971,558


Claims priority, application Fed. Rep. of Germany, Dec. 24, 1977, 2758001

Int. Cl.³ A61K 31/545; C07D 501/34

U.S. Cl. 424-246

4 Claims

1. A compound of the formula



wherein A is hydrogen, a cleavable ester group, or a physiologically acceptable cation, and wherein, in the formula, =N-OCH₃ is present in the syn form.

3. An antibacterial composition comprising an effective amount of a compound as in claim 1 in dosage form or in dosage form with a pharmaceutical carrier therefor.

4,293,551

N-AMINO-3,4,5-TRIHYDROXYPIPERIDINES, THEIR PRODUCTION AND THEIR MEDICINAL USE

Günther Kinast; Lutz Müller; Walter Puls, and Rüdiger Sitt, all of Wuppertal, Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Jul. 17, 1979, Ser. No. 58,348


Claims priority, application Fed. Rep. of Germany, Aug. 10, 1978, 2835069

Int. Cl.³ C07C 211/98; A61K 31/445

U.S. Cl. 424-249

15 Claims


1. A compound which is an N-amino-3,4,5-trihydroxypiperidine of the formula



or a salt thereof, in which

R₁ is a hydrogen atom, a formyl or carboxamido group, or a R₅, COR₅, CO₂R₅, CONHR₅, CONR₅R₆, CSR₅, CSNH₂, CSNHR₅, CSNR₅R₆, SO₃H or SO₂R₅ group.

R₂ is a hydrogen atom or an R₅ group, or R₁ and R₂ together represent the grouping



R₃ denotes a hydrogen atom, a hydroxyl, mercapto, amine, cyano, carboxyl, carboxamido, aminomethyl, sulfo hydroxymethyl group or an OR₅, SR₅, NHR₅, NR₅R₆, CO₂R₅, CONHR₅, CONR₅R₆, CH₂NHR₅, CH₂NR₅R₆, CH₂NHR₅, CH₂NR₅COR₆, CH₂NHSO₂R₅, CH₂NR₅SO₂R₆, CH₂OR₅ or CH₂OCOR₅ group,

R₄ denotes a hydrogen atom, a hydroxymethyl, formyl, carboxyl or carboxamido group or a R₅, CH₂OR₅, CHR₅OH, CHR₅OR₆, CR₅R₆OH, CR₅R₆OR₇, CR₅O, CO₂R₅, CONHR₅, CONR₅R₆ or CH₂X group wherein X is fluoro chloro, bromo,

R₅, R₆ and R₇ independently of one another denote a straight-chain, branched or cyclic saturated or unsaturated aliphatic hydrocarbon group or an aromatic or a heterocyclic group derived from furane, pyrane, pyrrolidine, piperidine, pyrazole, imidazole, pyrimidine, pyridazine, pyrazine, triazine, pyrrole, pyridine, benzimidazole, quinoline, isoquinoline or purine, and

R₈ and R₉ independently of each other denote a hydrogen atom or an R₅ group.

4,293,552

NOVEL 1-(MONO-O-SUBSTITUTED BENZOYL)-3-(SUBSTITUTED PYRAZINYL) UREAS

John L. Miesel, Indianapolis, Ind., assignor to Eli Lilly and Company, Indianapolis, Ind.


Continuation-in-part of Ser. No. 881,300, Feb. 27, 1978, abandoned. This application Jul. 31, 1979, Ser. No. 62,393

Int. Cl.³ C07D 241/20, 241/26; A01N 43/60

U.S. Cl. 424-250

22 Claims


1. A compound of the formula



wherein

A is bromo or chloro;

R¹ is hydrogen, trifluoromethyl, or



R² is hydrogen, chloro, methyl, or trifluoromethyl;

R³ is hydrogen, halo, methoxy, trifluoromethyl, or phenyl;

m is 1; and

n is 0;

and 1-(2-chlorobenzoyl)-3-(5-cyclohexyl-6-methyl-2-pyrazinyl) urea.

7. A method for the control of ova of insects of an order selected from the group consisting of Coleoptera, Diptera, Lepidoptera, and Orthoptera, which comprises applying to the loci of the insects an insecticidally effective amount of a 1-(mono-o-substituted benzoyl)-3-(substituted pyrazinyl)urea compound of claim 1, except for 1-(2-chlorobenzoyl)-3-(5-cyclohexyl-6-methyl-2-pyrazinyl)urea.

4,293,553

1-PHTHALAZONE DERIVATIVES, AND USE THEREOF

Masayuki Ishikawa, 14-13, Akazutsumi 3-chome, Setagaya-ku, Tokyo 156, Japan; Hiromichi Tanaka, Yokohama, Japan; Yukuo Eguchi, Chiba, Japan; Shigeru Ito, Nagareyama, Japan; Yoshimi Takashima, Akishima, Japan, and Masahiko Kobayashi, Kokubunji, Japan, assignors to Masayuki Ishikawa, Tokyo, Japan

Filed Aug. 7, 1979, Ser. No. 64,368


Claims priority, application Japan, Aug. 11, 1978, 53-97186; Sep. 22, 1978, 53-116006; Sep. 22, 1978, 53-116007; Sep. 22, 1978, 53-116009; Oct. 2, 1978, 53-120387; Oct. 2, 1978, 53-120388

Int. Cl.³ C07D 237/32

U.S. Cl. 424-250

28 Claims

1. 1-Phthalazone derivatives of the following formula:




wherein


R₁ is a member selected from the group consisting of a hydrogen atom, alkyl groups having 1 to 4 carbon atoms and a hydroxymethyl group,

R₂ is an alkyl group having 1 to 4 carbon atoms, and

R₃ is a group having the formula



in which R₄ and R₅ are identical or different and each represents a member selected from the group consisting of a hydrogen atom, halogen atoms, alkyl groups having 1 to 4 carbon atoms and alkoxy groups having 1 to 4 carbon atoms, and R₆ represents a member selected from the group consisting of a hydrogen atom, halogen atoms, alkyl groups having 1 to 4 carbon atoms, alkoxy groups having 1 to 4 carbon atoms, a hydroxyl group, a carboxyl group, alkoxy carbonyl groups having 2 to 5 carbon atoms, a nitro group and an amino group; or a group having the formula



in which R₇ represents a hydrogen atom or an alkyl group having 1 to 4 carbon atoms; and pharmaceutically acceptable inorganic acid addition salts thereof.

4,293,554

METHOD OF TREATING ASTHMA

George R. Allen, Jr., Old Tappan, N.J.; John W. Hanifin, Jr.; Daniel B. Moran, both of Suffern, N.Y., and Jay D. Albright, Nanuet, N.Y., assignors to American Cyanamid Company, Stamford, Conn.

Filed Feb. 21, 1980, Ser. No. 122,958

Int. Cl.³ A61K 31/495

U.S. Cl. 424—250

1 Claim

1. A method of preventing the development of asthmatic conditions in a warm-blooded animal, which comprises administering to said animal a prophylactically effective amount of 6-phenyl-1,2,4-triazolo-[4,3-b]pyridazin-3(2H)-one.

4,293,555

6- AND

6,6-DISUBSTITUTED-2-SUBSTITUTED-OXAPEN-2-EM-3-CARBOXYLIC ACIDS

Burton G. Christensen, Scotch Plains, and Frank P. DiNinno, Old Bridge, both of N.J., assignors to Merck & Co., Inc., Rahway, N.J.

Continuation-in-part of Ser. No. 30,970, Apr. 17, 1979, abandoned, and Ser. No. 30,788, Apr. 17, 1979, abandoned, which is a continuation of Ser. No. 865,277, Dec. 28, 1977, abandoned, and Ser. No. 865,109, Dec. 28, 1977, abandoned.


This application Oct. 10, 1979, Ser. No. 83,721

The portion of the term of this patent subsequent to Oct. 30, 1996, has been disclaimed.

Int. Cl.³ C07D 498/04, 205/08; A61K 31/42; C07D 409/06
U.S. Cl. 424—263

5 Claims

1. A compound having the structural formula:








wherein:






R⁴ is hydrogen, pharmaceutically acceptable salts, or benzyl, p-nitrobenzyl, o-nitrobenzyl, t-butyl, bromo-t-butyl, t-butyl-dimethylsilyl, trimethylsilyl, trichloroethyl, pivaloyloxymethyl, allyl, methallyl, (2-methylthio)ethyl, or 3-buten-1-yl;

R¹ and R² are independently selected from: hydrogen, hydroxymethyl, 1-hydroxyethyl, 1-hydroxy-3-phenylpropyl, 1-hydroxy-3-phenyl-3-carboxypropyl, 1-hydroxy-2,2,2-trifluoroethyl, methoxyl, phenyl, methyl, 2-thienyl, 2-pyridyl, benzyl, p-methoxyphenyl; and

R³ is



-continued



—NHCH₂CH₃; except that when both R¹ and R² are hydrogen, R³ cannot be methyl; and, except that R³ cannot be —SCH₂CH₂NH₂ when R² is hydrogen and R¹ is 1-hydroxyethyl.

5. An antibiotic pharmaceutical composition comprising in unitary dosage form, an antibacterially effective amount of a compound according to claim 1 and a pharmaceutically acceptable carrier therefor.

4,293,556

ANALGESIC

2-(2-ALKOXY-ETHYL)-2'-HYDROXY-6,7-BENZOMORPHANS AND SALTS THEREOF

Herbert Merz, Ingelheim am Rhein, and Klaus Stockhaus, Bingen, both of Fed. Rep. of Germany, assignors to Boehringer Ingelheim GmbH, Ingelheim, Fed. Rep. of Germany
Continuation of Ser. No. 52,433, Jun. 26, 1979, abandoned. This application May 28, 1980, Ser. No. 154,067


Claims priority, application Fed. Rep. of Germany, Jun. 26, 1978, 2828039

Int. Cl.³ A61K 31/445; C07D 221/26

U.S. Cl. 424—267

4 Claims

1. A racemic or optically active compound of the formula



wherein

R₁ is methyl, ethyl or propyl;
R₂ is hydrogen, methyl or ethyl; and
R₃ is

4,293,558

(a) ANTIVIRAL THIAZOLINYL BENZIMIDAZOLES AND DERIVATIVES

Charles J. Paget; James W. Chamberlin, both of Indianapolis, and James W. Wikel, Greenwood, all of Ind., assignors to Eli Lilly and Company, Indianapolis, Ind.


Division of Ser. No. 2,836, Jan. 12, 1979, Pat. No. 4,216,313, which is a division of Ser. No. 769,358, Feb. 16, 1977, Pat. No. 4,150,028, which is a continuation-in-part of Ser. No. 626,014, Oct. 28, 1975, abandoned. This application Nov. 14, 1979, Ser. No. 94,129

Int. Cl.³ A61K 31/425; A01N 43/52, 43/78


U.S. Cl. 424—270

33 Claims

1. A method of suppressing the growth of a virus which comprises adding an antivirally effective amount of an active agent to a medium in which the virus is growing, said active agent being a compound of the formula



or




where

R₄ is hydrogen or methyl,
R₅ is methyl, ethyl or propyl, and
n is 1 or 2,


or a non-toxic, pharmacologically acceptable acid addition salt thereof.

4. The method of relieving pain in a warm-blooded animal in need thereof, which comprises perorally, parenterally or rectally administering to said animal an effective analgesic amount of a compound of claim 1.




wherein

R₁ is hydrogen, C₁–C₃ alkyl, phenyl, or benzyl;
R₂ is hydrogen, or C₁–C₄ alkanoyl;
R₃ is at the 5 or 6 position and is 1-(C₁–C₃ alkyl)tetrazol-5-yl, 1,3-dithiolan-2-yl,



wherein R₅ is C₁–C₃ alkyl, C₃–C₇ cycloalkyl, (C₃–C₇ cycloalkyl)methyl, 1-(C₃–C₇ cycloalkyl)ethyl, thienyl, or phenyl; R₆ is C₁–C₇ alkyl; R₇ is C₁–C₇ alkylidene; or



wherein R₄ is hydrogen, C₁–C₇ alkyl, C₃–C₇ cycloalkyl, (C₃–C₇ cycloalkyl)methyl, 1-(C₃–C₇ cycloalkyl)ethyl, thienyl, benzyl, phenyl or mono substituted phenyl wherein said substituents are selected from the group consisting of C₁–C₄ alkyl, C₁–C₄ alkoxy, chloro, bromo, iodo, nitro or trifluoromethyl and Z is hydroxyimino, C₁–C₄ alkoxyimino, C₁–C₄ alkanoyloxyimino, hydrazono, α-methoxycarbonylhydrazono, α-hydroxycarbonyl-methoxyhydrazono, ethoxycarbonylhydrazono, carbamyl-hydrazono or thiocarbamylhydrazono; and

n is 2.

23. A method of suppressing the growth of a virus which comprises administering an antivirally effective amount of an active agent intranasally to a warmblooded animal, said active agent being a compound of the formula

4,293,557

ANTIULCER PHENOXYPROPYLAMINE DERIVATIVES
Kenyu Shibata, Inagi; Toshihisa Itaya; Nobuaki Yamakoshi, both of Kawasaki; Shigeru Kurata, Tokyo; Naoyuki Koizumi, Kawasaki; Masaaki Tarutani; Hideki Sakuma, both of Yokohama, and Kunihiro Konishi, Kawasaki, all of Japan, assignors to Teikoku Hormone Mfg. Co., Ltd., Tokyo, Japan
Filed Jun. 30, 1980, Ser. No. 164,017


Claims priority, application Japan, Jul. 3, 1979, 54-83426; Feb. 20, 1980, 55-19088

Int. Cl.³ A61K 31/445; C07D 295/14

U.S. Cl. 424—267


12 Claims

1. A phenoxypropylamine derivative of the following formula




wherein R₁ represents a hydrogen atom or a methyl or ethyl group, R₂ and R₃, independently from each other, represent a lower alkyl group, or together form a linear alkylene group having 4 to 7 carbon atoms which may be optionally substituted by a hydroxyl or hydroxymethyl group, and R₄ represents a hydrogen atom or a group of the formula —R₅—Z in which R₅ represents a lower alkylene group, and Z represents a hydrogen atom or an amino, mono- or di-(lower alkyl)amino, hydroxy lower alkylamino, lower alkanoylamino, hydroxyl, lower alkoxy, lower alkanoyloxy, phenoxy, halophenoxy, benzoyloxy or halobenzoyloxy group, or a pharmaceutically acceptable salt thereof.

12. Method for the treatment of ulcers of the stomach or duodenum, which comprises administering to a patient suffering therefrom an antiulcer effective amount of a compound according to any one of claims 1 to 10 or a pharmaceutically acceptable salt thereof.




wherein

R₁ is hydrogen, C₁-C₃ alkyl, phenyl, or benzyl;
R₂ is hydrogen, or C₁-C₄ alkanoyl;
R₃ is at the 5 or 6 position and is 1-(C₁-C₃ alkyl)-tetrazol-5-yl, 1,3-dithiolan-2-yl,



wherein R₅ is C₁-C₃ alkyl, C₃-C₇ cycloalkyl, (C₃-C₇ cycloalkyl)methyl, 1-(C₃-C₇ cycloalkyl)ethyl, thienyl, or phenyl; R₆ is C₁-C₇ alkyl; R₇ is C₁-C₇ alkylidene; or



wherein R₄ is hydrogen, C₁-C₇ alkyl, C₃-C₇ cycloalkyl, (C₃-C₇ cycloalkyl)methyl, 1-(C₃-C₇ cycloalkyl)ethyl, thienyl, benzyl, phenyl or mono substituted phenyl wherein said substituents are selected from the group consisting of C₁-C₄ alkyl, C₁-C₄ alkoxy, chloro, bromo, iodo, nitro or trifluoromethyl and Z is hydroxyimino, C₁-C₄ alkoxyimino, C₁-C₄ alkanoyloxyimino, hydrazono, α-methoxycarbonylhydrazono, α-hydroxycarbonyl-methoxyhydrazono, ethoxycarbonylhydrazono, carbamyl-hydrazono or thiocarbamylhydrazono; and n is 2.

4,293,559

SLIME CONTROL COMPOSITIONS AND METHODS OF USING THE SAME

John D. Buckman; Stanley J. Buckman; Betty S. Johnson, and John D. Pera, all of Memphis, Tenn., assignors to Buckman Laboratories, Inc., Memphis, Tenn.

Filed Mar. 29, 1978, Ser. No. 891,435

Int. Cl.³ A01N 43/78

U.S. Cl. 424-270

8 Claims

1. A bactericidal and fungicidal synergistic composition consisting essentially of about 15 to about 85 parts by weight of 2-(thiocyanomethylthio)benzothiazole and about 85 to about 15 parts by weight of a compound selected from 2'-hydroxyethyl 2,3-dibromopropionate and 2'-hydroxyethyl 2-bromoacrylate.

4,293,560

TALAMPICILLIN 2-METHOXYPHENOXYACETATE AND PHARMACEUTICAL COMPOSITIONS CONTAINING IT

Andrea Pedrazzoli, Milan, and Sergio Boveri, Monza, both of Italy, assignors to C M Industries, France

Filed Jun. 23, 1980, Ser. No. 161,687

Int. Cl.³ A61K 31/34; C07D 499/68

U.S. Cl. 424-271

7 Claims

2. A pharmaceutical composition in unit dosage form, for use in the treatment of infections sensitive to ampicillin, comprising about 20-1000 mg per dosage unit of the 2-methoxyphenoxyacetate of the phthalidyl ester of 6-[D(-)-α-amino-

phenylacetamido]penicillanic acid in admixture with a pharmaceutical carrier.

4,293,561

1-(NAPHTHYL-N-PROPYL)IMIDAZOLE DERIVATIVES

Keith A. M. Walker, Los Altos Hills, Calif., assignor to Syntex (U.S.A.) Inc., Palo Alto, Calif.

Filed Mar. 9, 1979, Ser. No. 19,201


The portion of the term of this patent subsequent to Apr. 17, 1996, has been disclaimed.

Int. Cl.³ A61K 31/415; C07D 233/60, 405/06

U.S. Cl. 424-273 R


7 Claims

1. A compound of the formula




wherein Z is a carbonyl group protected as an acyclic ketal derived from a monohydric straight chain alkanol having from one to four carbon atoms, or a carbonyl group protected as a cyclic ketal wherein the cyclic ketal is selected from the group consisting of ethylenedioxy, 1,3-propylenedioxy, 1,2-propylenedioxy, 2,2-dimethyl-1,3-propylenedioxy, 1-methyl-1,3-propylenedioxy, 1,3-dimethyl-1,3-propylenedioxy, and 2,3-butylenedioxy and the pharmaceutically acceptable acid addition salts thereof.

6. A method for treating and preventing convulsions in a mammalian subject comprising administering to said subject in need thereof a therapeutically effective amount of a compound of the formula



wherein Z is carbonyl, a carbonyl group protected as an acyclic ketal derived from a monohydric straight chain alkanol having from one to four carbon atoms, or a carbonyl group protected as a cyclic ketal derived from a dihydric alcohol having two or three carbon atoms which may be optionally substituted by one or more methyl groups or a pharmaceutically acceptable acid addition salt thereof.

7. A method for inhibiting gastric secretion in a mammalian subject comprising administering to said subject in need thereof a therapeutically effective amount of a compound of the formula



wherein Z is carbonyl, a carbonyl group protected as an acyclic ketal derived from a monohydric straight chain alkanol having from one to four carbon atoms, or a carbonyl group protected as a cyclic ketal derived from a dihydric alcohol having two or three carbon atoms which may be optionally substituted by one or more methyl groups or a pharmaceutically acceptable acid addition said thereof.

4,293,562

METHODS OF OBTAINING ANOREXIC EFFECTS USING A COMBINATION OF AMPHETAMINES AND CIMETIDINE

Arnold Ritter, 18402 N. 19th Ave., Phoenix, Ariz. 85023

Filed Jul. 2, 1979, Ser. No. 53,766

Int. Cl.³ A61K 31/415, 31/135

U.S. Cl. 424-273 R

5 Claims

1. A method of suppressing the appetite of a mammalian host as an adjunct to a weight control program comprising administering orally to said host once daily (a) up to 5 mg of an anorexant which is substantially less than the normal daily dosage of said anorexant concurrently with (b) from 150 mg to 300 mg of cimetidine, said anorexant being selected from the group consisting of amphetamines, biphetamines and the non-toxic biologically acceptable salts thereof.

4,293,563

THENYL HYDANTOINS AND ANTI-ASTHMATIC COMPOSITIONS THEREOF

William B. Jamieson, Woking; William J. Ross, Lightwater; Robin G. Simmonds, Wokingham, and John P. Verge, Henley-on-Thames, all of England, assignors to Lilly Industries Limited, London, England

Division of Ser. No. 39,075, May 14, 1979, Pat. No. 4,241,073.

This application May 12, 1980, Ser. No. 148,633


Claims priority, application United Kingdom, May 23, 1978, 21352/78

Int. Cl.³ A61K 31/415; C07D 409/06

U.S. Cl. 424-273 R

4 Claims

1. A compound of the formula



wherein

R³ is H, C₁-C₆ alkyl or C₂-C₄ alkenyl;
R⁴ is C₁-C₆ alkyl, C₂-C₄ alkenyl, benzyl or phenyl;
R⁵ is phenyl or C₁-C₄ alkyl; and n is 0, 1 and 2 but n is 1 when R⁵ is phenyl and 1 or 2 when R⁵ is C₁-C₄ alkyl.
3. A solid or aerosol pharmaceutical formulation in unit dosage form adapted for administration to treat asthma or other immediate hypersensitivity condition which comprise per dosage unit an amount of a compound of claim 1 effective to treat asthma associated with a pharmaceutically-acceptable carrier therefor.

4,293,564

2-(3,5-DIBROMO-4-AMINO-PHENYLIMINO)-IMIDAZOLIDINE, SALTS AND COMPOSITIONS THEREOF

Helmut Stähle; Herbert Köppe; Werner Kummer, all of Ingelheim am Rhein; Wolfgang Hoefke, Budenheim; Wolfram Gaida, Ingelheim am Rhein, all of Fed. Rep. of Germany, and Ludwig Pichler, Vienna, Austria, assignors to Boehringer Ingelheim GmbH, Ingelheim, Fed. Rep. of Germany

Continuation-in-part of Ser. No. 12,650, Feb. 16, 1979, Pat. No. 4,250,186. This application Aug. 20, 1980, Ser. No. 179,839

Claims priority, application Fed. Rep. of Germany, Feb. 17, 1978, 2806775

Int. Cl.³ A61K 31/415; C07D 233/50

U.S. Cl. 424-273 R

2 Claims

1. 2-(3,5-Dibromo-4-amino-phenylimino)imidazolidine or a non-toxic, pharmacologically acceptable acid addition salt thereof.

2. A bradycardiac pharmaceutical dosage unit composition

consisting essentially of an inert pharmaceutical carrier and an effective bradycardiac amount of a compound of claim 1.

4,293,565

TRANSDERMAL MEDICATION SYSTEM FOR ISOSORBIDE DINITRATE

Günter Cordes, Leichlingen; Ewald Giesselmann, and Ulrich Münch, both of Monheim, all of Fed. Rep. of Germany, assignors to Sanol Schwarz-Monheim GmbH, Monheim, Fed. Rep. of Germany

Filed Oct. 9, 1979, Ser. No. 82,490

Claims priority, application Fed. Rep. of Germany, Jun. 13, 1979, 2924005

Int. Cl.³ A61K 31/34

U.S. Cl. 424-285

10 Claims

1. A pharmaceutical preparation consisting essentially of
(a) isosorbide dinitrate as active ingredient,
(b) a non-aqueous solvent for isosorbide dinitrate which dissolves at least 5% by weight of isosorbide dinitrate, based on the solvent, has an ointment-like consistency and is miscible with water, where said solvent is an ester of a C₈-18 fatty acid with glycerin ethoxylated with from 3 to 10 mols of ethylene oxide,
(c) an ointment consistency agent selected from the group consisting of glycerin monostearate, hardened castor oil, cetyl alcohol, stearyl alcohol, stearic acid, and mixtures thereof, and
(d) water,
where the weight ratio of water to consistency agent to solvent is 30 to 80:3 to 35:3 to 35 and the amount of isosorbide dinitrate in the preparation is from 2% to 20% by weight.

4,293,566

PESTICIDALLY ACTIVE

1-ARYLAMINO-2,4-DINITRONAPHTHALENES

Rainer Hamprecht, Cologne; Alfons Hartmann, Beckingen; Erich Klauke, Odenthal-Hahnenberg; Ingeborg Hammann, Cologne; Peter Roessler, Bergisch-Gladbach, and Wilhelm Brandes, Cologne, all of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Division of Ser. No. 876,456, Feb. 1, 1978, Pat. No. 4,183,949.

This application Jul. 12, 1979, Ser. No. 57,056

Claims priority, application Fed. Rep. of Germany, Feb. 26, 1977, 2708440

The portion of the term of this patent subsequent to Jan. 15, 1997, has been disclaimed.

Int. Cl.³ A01N 33/18, 37/34; C07C 87/00, 121/78

U.S. Cl. 424-304

25 Claims

1. A compound selected from the group consisting of
1-(2-cyano-4-trifluoromethylphenylamino)-2,4-dinitronaphthalene,
1-(4-chloro-2-trifluoromethylphenylamino)-2,4-dinitronaphthalene,
1-(4-nitro-2-trifluoromethylphenylamino)-2,4-dinitronaphthalene,
1-(2,6-dichloro-4-trifluoromethylphenylamino)-2,4-dinitronaphthalene,
1-(4,6-dinitro-2-trifluoromethylphenylamino)-2,4-dinitronaphthalene,
1-(2,4,6-trichlorophenylamino)-2,4-dinitronaphthalene,
1-(2,4-dicyanophenylamino)-2,4-dinitronaphthalene,
1-(2-bromo-4-nitro-6-trifluoromethylphenylamino)-2,4-dinitronaphthalene,
1-(2,6-dichloro-4-nitrophenylamino)-2,4-dinitronaphthalene,
1-(4-nitro-2-bromophenylamino)-2,4-dinitronaphthalene,
1-(3-chloro-4-nitrophenylamino)-2,4-dinitronaphthalene,
1-(2-nitro-4-chlorophenylamino)-2,4-dinitronaphthalene,
1-(3-nitro-4-chlorophenylamino)-2,4-dinitronaphthalene,
1-(2,4-dinitro-6-bromophenylamino)-2,4-dinitronaphthalene,
1-(2-methyl-4-nitro-5-chlorophenylamino)-2,4-dinitronaphthalene,

1-(2-methoxy-4-nitro-5-chlorophenylamino)-2,4-dinitronaphthalene,
 1-(2-nitro-4-methylphenylamino)-2,4-dinitronaphthalene,
 1-(2,6-dinitrophenylamino)-2,4-dinitronaphthalene,
 1-(3-chloro-4-methoxycarbonylphenylamino)-2,4-dinitronaphthalene,
 1-(2-chloro-4-nitrophenylamino)-2,4-dinitronaphthalene,
 1-(3-chloro-4-fluorophenylamino)-2,4-dinitronaphthalene
 and
 1-(2,4-difluorophenylamino)-2,4-dinitronaphthalene.

25. A method of combating arthropods, fungi or bacteria which comprises applying to the arthropods, fungi or bacteria, or to a habitat thereof, an arthropodically, fungicidally or bactericidally effective amount of a compound according to claim 1.

4,293,567

ANTI-FEEDANT FOR BOLL WEEVILS

Martin Jacobson, Silver Spring, Md., assignor to The United States of America as represented by the Secretary of Agriculture, Washington, D.C.

Filed Apr. 16, 1980, Ser. No. 140,911

Int. Cl.³ A01N 37/06

U.S. Cl. 424—312

3 Claims

1. A method of deterring boll weevils from feeding on growing cotton plants comprising applying methyl α -eleostearate to growing cotton plants in an amount sufficient to deter boll weevils from feeding thereon.

4,293,568


METHOD FOR TREATMENT OF HUMAN EYE DISEASE
 Emil Wirotko, E. 208 Midland Ave., Paramus, N.J. 07652, and
 Lewis A. Johnson, 1050 Park Ave., New York, N.Y. 10028

Division of Ser. No. 932,904, Aug. 11, 1978, Pat. No. 4,220,657, which is a division of Ser. No. 453,463, Aug. 23, 1974, abandoned. This application Apr. 1, 1980, Ser. No. 136,297

Int. Cl.³ A61K 31/135, 31/10

U.S. Cl. 424—330

20 Claims



1. A method of treating active endogenous uveitis caused by MICROMYCES intracellularis comprising administering to a patient having endogenous uveitis an effective amount thereof of a therapeutic agent comprising 4,4'-sulfonyldianiline.

6. A method of treating chronic conjunctivitis caused by MICROMYCES intracellularis comprising administering to a patient having chronic conjunctivitis an effective amount thereof of a therapeutic agent comprising 4,4'-sulfonyldianiline.

11. A method of treating kerato-conjunctivitis caused by MICROMYCES intracellularis comprising administering to a

patient having kerato-conjunctivitis an effective amount thereof of a therapeutic agent comprising 4,4'-sulfonyldianiline.

16. A method of treating keratitis caused by MICROMYCES intracellularis comprising administering to a patient having keratitis an effective amount thereof of a therapeutic agent comprising 4,4'-sulfonyldianiline.

4,293,569

SUBSTITUTED PHENYLGUANINDINES AND METHOD
 Rudiger D. Haugwitz, Titusville; Peter C. Wade, Pennington, and Barbara V. Maurer, Titusville, all of N.J., assignors to E. R. Squibb & Sons, Inc., Princeton, N.J.


Filed May 12, 1978, Ser. No. 905,265

Int. Cl.³ C07C 155/02, 149/437, 147/14; A61K 31/325

U.S. Cl. 424—300

9 Claims

1. A compound of the structure



wherein R is hydrogen, lower alkyl, cycloalkyl, lower alkoxy, phenyl, phenylalkyl, lower alkoxyalkyl, phenoxy, phenylalkoxy, phenoxyalkyl, dialkylaminoalkyl, alkylthio, phenylthio, phenylthioalkyl, alkylthioalkyl or cycloalkyl substituted with 1, 2, 3 or 4 halogen groups and/or 1, 2, 3 or 4 lower alkyl groups; R¹ is lower alkyl or benzyl, R² is hydrogen lower alkoxy carbonyl, or lower alkanoyl; R³ is cycloalkylalkyl, benzyl or cycloalkylalkyl wherein the cycloalkyl portion is substituted with 1, 2, 3 or 4 halogen groups and/or 1, 2, 3 or 4 lower alkyl groups; and n is 0 or 1, or a physiologically acceptable salt thereof.

4,293,570

PROCESS FOR THE PREPARATION OF SWEETENER CONTAINING PRODUCT

Kalman Vadasz, South Wharton, N.J., assignor to Chemicasa GmbH, Chur, Switzerland

Filed Apr. 2, 1979, Ser. No. 26,357


Int. Cl.³ A23G 3/30, 3/00

U.S. Cl. 426—3

6 Claims

1. A process of preparing a cryptocrystalline sweetener containing product, which process comprises:
 spraying in a fine liquid spray within a vessel and into the cooler atmosphere within the vessel, through heated spray nozzles, a heated, aqueous, low-viscosity, high-solids, sweetener solution selected from the group consisting of an aqueous solution of sorbitol, sucrose fructose, mannitol, glucose, and combinations thereof, having a temperature of from about 180° F. to 315° F., and containing about 70% to 99.5% by weight of sweetener, and employing in the spraying operation cool, compressed, dry, air, which cool, compressed air is introduced into the heated spray nozzles, and wherein the heated solution is maintained in a heated condition up to the point of spraying, and wherein the compressed air has a temperature of from about 40° F. to 120° F. and is employed at a pressure of from about 40 to 125 psi, and wherein the change in phase from a liquid to a solid of the sweetener solution occurs without the substantial loss of moisture during the spraying operation, to provide for the formation in the atmo-

sphere within the vessel of a fine particle-size, cryptocrystalline, sweetener product having a particle size of less



than about 5 microns, and admixing the fine-particle-size product with a food or confectionary product.

4,293,571

PROCESS FOR THE PREPARATION OF A PURIFIED PROTEIN HYDROLYSATE

Mats Olofsson, Astorp, Sweden; Marcel Buhler, Tolochenaz, and Robert Wood, Le Mont-s/Lausanne, both of Switzerland, assignors to Societe d'Assistance Technique pour Produits Nestle S.A., Lausanne, Switzerland

Filed Feb. 28, 1980, Ser. No. 125,480

Claims priority, application Switzerland, Mar. 9, 1979, 2278/79

Int. Cl.³ A23J 3/00

U.S. Cl. 426—7

10 Claims

1. A process for the preparation of a purified protein hydrolysate comprising:
 (a) subjecting an aqueous solution of proteins to a hydrolysis treatment to yield at least hydrolysate products free of original protein and protein fragments capable of acting as allergens;
 (b) subjecting the treated aqueous solution to a heat treatment to denature the proteins not hydrolysed in step (a); and
 (c) eliminating the denatured proteins from the heat treated hydrolysate by ultrafiltration and obtaining an ultrafiltration permeate constituting the purified protein hydrolysate free of said original protein and protein fragments.

4,293,572

PROCESS FOR APPLYING A MOISTURE BARRIER COATING TO BAKED AND FRIED FOOD PRODUCTS

Roy Silva; David J. Ash, both of Norwalk, Conn., and Clement E. Scheible, Rye, N.Y., assignors to International Telephone and Telegraph Corporation, New York, N.Y.

Continuation-in-part of Ser. No. 881,935, Feb. 28, 1978, abandoned. This application Sep. 14, 1979, Ser. No. 75,615

Int. Cl.³ A21D 13/00

U.S. Cl. 426—19

4 Claims

1. A method of providing a multicomponent baked or fried bakery food product with an edible effective moisture barrier which comprises:

(a) preparing a substantially salt-free coating material of a water in oil emulsion comprising a uniform dispersion of droplets of a solution of 6% to 40% material selected from the group consisting of saccharide, polysaccharide or dextrin in 12% to 43% water in 25% to 75% oily substance selected from the group consisting of acetylated

monoglycerides, or a triglyceride combined with an emulsifying agent and holding said emulsion at a first temperature at which it remains a stable liquid;

(b) cooking said bakery food product and reducing the temperature of the surface thereof to a temperature which is less than the first temperature of said coating material;
 (c) applying said emulsion to the cooler surfaces of said product to provide a thin uniform coating on said surface whereby moisture migration is inhibited;
 (d) setting said uniform coating prior to any further processing of said product; and
 (e) icing said food product with said uniform coating being present between said product and said icing.

4,293,573

PREPARATION OF FROZEN YOGURT

Robert L. Bradley, Jr., Madison, Wis., and Majid Hekmati, Karay Iran, assignors to Wisconsin Alumni Research Foundation, Madison, Wis.

Filed Mar. 30, 1979, Ser. No. 25,615

Int. Cl.³ A23C 9/12

U.S. Cl. 426—43

1 Claim

1. A method for preparing a frozen yogurt containing in admixture cream, condensed skim milk, sucrose, corn sweetener, stabilizers and 30-50% fluid acid whey based on the total weight of the admixture obtained from the manufacture of cottage cheese, said method comprising preparing a first mixture consisting essentially of a major amount of said condensed skim milk and a minor amount of said cream, pasteurizing the mixture, cooling the mixture to incubation temperature, inoculating the cooled mixture with a yogurt culture, incubating the inoculated mixture to acidify the mixture, preparing a second mixture consisting essentially of said sucrose, corn sweetener, stabilizers and 30-50% fluid acid whey, pasteurizing the second mixture, cooling the pasteurized second mixture, mixing the cooled second mixture with the first acidified mixture to produce a third mixture containing a total solid content of 22-35% by weight, homogenizing the third mixture and freezing the third mixture to produce said frozen yogurt.

4,293,574

PROCESS FOR PREPARING MAYONNAISE-LIKE FOODS

Yasuo Mikami, Yokohama; Hiroshi Kanda, Zushi, and Akio Uno, Yokohama, all of Japan, assignors to The Nisshin Oil Mills, Ltd., Tokyo, Japan

Filed Feb. 21, 1980, Ser. No. 123,250

Claims priority, application Japan, Aug. 10, 1979, 54-101306

Int. Cl.³ A23L 1/24

U.S. Cl. 426—46

3 Claims

1. A process for preparing a mayonnaise food which comprises solubilizing an alcohol-denatured soybean protein with protease until the solubility of the protein in a 10% aqueous solution of trichloroacetic acid has reached about 15-35% by weight, separating water-insoluble materials to obtain refined soybean proteins and emulsifying the refined soybean proteins together with edible oils, vinegars, seasonings.

4,293,575

METHOD AND APPARATUS FOR TEXTURIZING A PROTEINACEOUS SUBSTANCE

Geoffrey N. Cockram, Henley on Thames, and Jeffrey E. Munden, High Wycombe, both of England, assignors to E. I. Du Pont de Nemours and Company, Wilmington, Del.

Continuation of Ser. No. 889,041, Mar. 22, 1978, abandoned, which is a continuation of Ser. No. 694,989, Jun. 11, 1976, abandoned. This application Dec. 31, 1979, Ser. No. 108,841 Claims priority, application United Kingdom, Jun. 13, 1975, 25387/75

Int. Cl.³ A23J 3/00; A23L 1/28

U.S. Cl. 426—104

8 Claims

1. A method of texturizing a mass consisting essentially of fungal mycelia having reduced turgor and a solids content of between 20% and 35% by weight, consisting solely of the steps of passing the mass under pressure through at least one member containing a plurality of apertures whereby the mass is filamented and compacting the resulting filaments to form a textured structure.

4,293,576

FOOD PRODUCT AND PROCESS OF MANUFACTURE

Christopher B. Sentance, Wodonga, Australia, assignor to Effem Foods Pty. Ltd., Wodonga, Australia

Filed Aug. 10, 1978, Ser. No. 932,650

Claims priority, application Australia, Aug. 15, 1977, PD1233 Int. Cl.³ A23K 1/04

U.S. Cl. 426—104

9 Claims

1. A process for producing a food product simulating meat from an anticoagulant-treated, coagulable blood fluid by the controlled, chemically-stimulated coagulation of said blood fluid under controlled temperature conditions, said process comprising the steps of:

- (a) coagulating an anticoagulant-treated, coagulable blood fluid selected from the group consisting of
- whole animal blood,
 - a plasma phase of animal blood,
 - a mixture of up to about 40% of a haemoglobin phase of animal blood and a plasma phase of animal blood,
 - a mixture of whole animal blood and a plasma phase of animal blood,
 - a mixture of whole animal blood and up to about 20% of a haemoglobin phase of animal blood and
 - a mixture of whole animal blood, a plasma phase of animal blood and up to about 40% of a haemoglobin phase of animal blood,

in the presence of an exudation-inhibiting agent and a coagulation stimulant, both present in effective amounts, while maintaining said blood fluid at a temperature within about 10° C. either above or below the physiological temperature of the animal from which the blood has been derived to chemically induce coagulation and

- (b) then recovering the resultant coagulate.

4,293,577

PRESERVABLE BAKED PASTRY PRODUCT, SUBSTANTIALLY FREE FROM SUCROSE AND SWEETENED WITH FRUCTOSE

Renzo Cillario, Alba, Italy, assignor to P. Ferrero & C. S.p.A., Alba, Italy

Filed Jun. 27, 1980, Ser. No. 163,893

Claims priority, application Italy, Nov. 22, 1979, 69262 A/79 Int. Cl.³ A23G 3/00


U.S. Cl. 426—244

34 Claims

1. Baked pastry product substantially free from sucrose and formed by a wheat flour-based cellular matrix, the said matrix being sweetened with fructose, either alone or in association with sorbitol, wherein the said cellular matrix is soft, is not crisp, is artificially leavened and is formed essentially, in addition to the wheat flour, from 50 to 80 parts by weight of starch, 15 to 25 parts by weight of gluten, 40 to 60 parts by weight of powdered skimmed milk and 50 to 100 parts by weight of egg

solids for every 100 parts by weight of wheat flour, the said product being obtainable by the steps of:

- (a) dissolving crystalline fructose in water and emulsifying in the obtained solution the said egg solids, in the form of powder or fresh eggs, thereby to obtain an emulsion containing from 150 to 200 parts by weight of water and at least 55 parts by weight of fructose for every 100 parts by weight of flour;



- (b) introducing all the remaining ingredients in the proportions specified above, and a synthetic leavening agent, into the said emulsion under mixing conditions, to obtain a homogeneous, unleavened dough which is substantially unknaded; and
- (c) baking the said dough in an oven to obtain a final product having a moisture content of 17 to 22% by weight.

4,293,578

METHOD OF TREATING FRESH SHRIMP TO REDUCE MOISTURE AND NUTRIENT LOSS

Everett W. Stone, P.O. Box 2168, Kodiak, Ak. 99615

Filed Mar. 31, 1980, Ser. No. 135,474

Int. Cl.³ A22C 25/00

U.S. Cl. 426—332

16 Claims

8. A method of treating shrimp while in the shell to reduce moisture and nutrient loss, comprising:

- delivering water to a flake ice machine, admixing an amount effective to reduce moisture and nutrient loss of a moisture binding phosphate compound with the water while delivering the water to the flake ice machine, so that such compound will be incorporated into the ice, resulting in colder ice with a greater cooling capacity than plain water ice, and

collecting flakes of ice from such machine; mixing such flake ice with shrimp within a storage region aboard a fishing vessel, as such shrimp is caught, said mixed ice and shrimp resulting in shrimp being wetted by water containing moisture binding phosphate compound, as the ice melts.

4,293,579

FLAVORING WITH

3,5-DI-(2-METHYLPROPYL)-1,2,4-TRITHIOLANE

Chi-Kuen Shu, Cliffwood; Braja D. Mookherjee, Holmdel, and Manfred H. Vock, Locust, all of N.J., assignors to International Flavors & Fragrances Inc., New York, N.Y.

Continuation of Ser. No. 63,377, Aug. 3, 1979, Pat. No. 4,259,507, which is a division of Ser. No. 963,176, Nov. 24, 1978, abandoned. This application Jul. 31, 1980, Ser. No. 174,252


Int. Cl.³ A23L 1/226, 1/231, 1/234

U.S. Cl. 426—535

3 Claims

1. A process for augmenting or enhancing the flavor of a foodstuff comprising the step of adding to said foodstuff from about 0.0005 ppm up to about 250 ppm of the compound 3,5-di-

(2-methylpropyl)-1,2,4-trithiolane or its "cis" or "trans" isomers having a structure selected from the group consisting of:



4,293,580

FROZEN FRUIT AND VEGETABLE JUICES

Irving H. Rubenstein, Owings Mills, Md., assignor to Maryland Cup Corporation, Owings Mills, Md.

Filed Nov. 23, 1979, Ser. No. 96,889

Int. Cl.³ A23L 2/02, 2/16; A23G 9/00

U.S. Cl. 426—565

17 Claims

1. A method for the preparation of a soft-frozen whipped fruit or vegetable juice concentrate which comprises the steps of:

- adding one or more whipping proteins or emulsifiers to single strength juice in an amount effective to whip the resulting juice concentrate mixture;
- blending the single strength juice containing the whipping proteins or emulsifiers in an amount ranging from greater than 0% to 90% by weight of the total with a fruit or vegetable juice concentrate; and
- subjecting the resulting mixture to simultaneous whipping and freezing at a temperature of about 18° to 30° F. to provide said soft-frozen whipped concentrate.

4,293,581

SAPONIFICATION TREATMENT OF SPENT COFFEE GROUNDS

Pierre Hirsbrunner, Corseaux, and Raymond Bertholet, La Tour-de-Peilz, both of Switzerland, assignors to Societe d'Assistance Technique Pour Produits Nestle S.A., Lausanne, Switzerland

Continuation-in-part of Ser. No. 90,148, Nov. 1, 1979, abandoned. This application Dec. 16, 1980, Ser. No. 216,960

Claims priority, application Switzerland, Nov. 3, 1978, 11332/78

Int. Cl.³ A23K 1/14

U.S. Cl. 426—630

9 Claims

1. Process for producing an animal feed component which comprises subjecting spent coffee grounds to a saponification treatment in an aqueous reaction medium which effectively saponifies cafestol and kahweol esters contained therein, acidifying the medium to a pH below 5 and recovering an animal feed component by drying the acidified medium.

4,293,582

POTATO DOUGH WITH PROCESS OIL FOR FORMED AND EXTRUDED POTATO PRODUCTS

Michael L. Hamann, and Richard K. Pinegar, both of Caldwell, Id., assignors to J. R. Simplot Company, Boise, Id.

Filed Jun. 9, 1980, Ser. No. 157,257

Int. Cl.³ A23L 1/216

U.S. Cl. 426—637

17 Claims

1. A potato dough for formed and extruded potato products, the dough composed of a mixture consisting essentially of:

- from about 45 to about 75 weight percent cooked mashed potatoes;
- from about 9 to about 20 weight percent dehydrated potato flakes;
- from about 0.12 to less than about 2.0 weight percent of liquid process oil selected from the group consisting of vegetable oils, animal fats and blends thereof; and
- from about 17 to about 27 weight percent of an aqueous slurry of an effective amount of binding agent.

4,293,583

PROCESS FOR DEBITTERING A PROTEIN HYDROLYSATE AND THE DEBITTERED HYDROLYSATE OBTAINED BY THIS PROCESS

David R. Farr, Brent, and Daniele Magnolato, Chardonne, both of Switzerland, assignors to Societe d'Assistance Technique pour Produits Nestle S.A., Lausanne, Switzerland

Filed Jan. 23, 1980, Ser. No. 114,680

Claims priority, application Switzerland, Jan. 26, 1979, 788/79

Int. Cl.³ A23J 3/00

U.S. Cl. 426—657

7 Claims

1. A process for debittering an enzymatic hydrolysate of whey protein which comprises contacting the hydrolysate with an adsorbent consisting of desugared carob particles at a temperature of from 10° to 60° C.

4,293,584

METHOD OF PLATING WITH A PORTABLE MECHANICAL PLATER


Erith T. Clayton, 3100 Elm Ave., Baltimore, Md. 21211

Filed Apr. 14, 1980, Ser. No. 112,108

Int. Cl.³ C23C 17/00

U.S. Cl. 427—11

22 Claims



1. A method of mechanically applying a metal coating onto the surface of an object comprising:

- providing a portable plating device comprising: a housing; a mechanical plating member moveable relative to said housing and having a plating surface adapted to be urged against and moved relative to said object surface; means for moving said plating member relative to said housing with said plating surface urged against said object surface; and means for holding and guiding said device for movement by an operator over said surface, said device being portable and capable of being moved to said object for plating thereof;
- moving said device into operative position with said plating surface of said plating member urged against said object surface;
- supplying an admixture of mechanical plating promoter and particles of plating metal to said plating surface; and
- moving said plating member relative to said housing and relative to said object surface to provide a solid metallurgically integrated metallic coating derived from said plating metal particles onto said surface.

4,293,585

METHOD FOR THE PREPARATION OF POLARIZING FILMS OR SHEETS

Kiyoshi Imada, Omiya; Susumu Ueno, Ibaraki; Yasuhide Ni-shina, Ibaraki, and Hirokazu Nomura, Ibaraki, all of Japan, assignors to Shin-etsu Chemical Co., Ltd., Tokyo, Japan
Filed Jul. 10, 1980, Ser. No. 168,082

Claims priority, application Japan, Jul. 16, 1979, 54-90221
Int. Cl.³ B05D 3/06

U.S. Cl. 427—40

6 Claims

1. A method for the preparation of a polarizing film or sheet which comprises the steps of

- (a) subjecting a substrate film or sheet of a vinyl chloride-based resin to exposure to an atmosphere of low temperature plasma of a gas having no polymerizability in a plasma condition,
- (b) coating the plasma-treated substrate film or sheet with an aqueous solution of a polyvinyl alcohol,
- (c) drying the thus coated film or sheet to form a coating layer of the polyvinyl alcohol firmly bonded to the surface of the substrate film or sheet,
- (d) stretching unidirectionally the polyvinyl alcohol-clad film or sheet, and
- (e) subjecting the thus stretched film or sheet to an iodine treatment.

4,293,586


METHOD FOR FORMING A FLUORESCENT SCREEN

Takaaki Unnai; Akiya Izumi, and Misturu Hinosugi, all of Mobara, Japan, assignors to Hitachi, Ltd., Tokyo, Japan
Filed Jan. 16, 1980, Ser. No. 112,613

Claims priority, application Japan, Jan. 19, 1979, 54-3954
Int. Cl.³ H01J 29/22; B05D 1/36, 7/22

U.S. Cl. 427—68

5 Claims



1. A method for forming a fluorescent screen on a panel of a cathode ray tube comprising the steps of coating on the inner face of the panel an undercoat layer containing at least polystyrene particles and having a film weight of 0.002 to 0.04 mg/cm², wherein the undercoat layer is made from an aqueous emulsion containing polystyrene particles of an average grain size of about 0.1 to 0.4 μ m whose solid content is from about 0.3 to 4 weight %, and coating phosphor slurry on the undercoat layer.

4,293,587

LOW RESISTANCE BACKSIDE PREPARATION FOR SEMICONDUCTOR INTEGRATED CIRCUIT CHIPS

Richard K. Trueblood, San Jose, Calif., assignor to Zilog, Inc., Cupertino, Calif.

Filed Nov. 9, 1978, Ser. No. 959,344
Int. Cl.³ H01L 21/285

U.S. Cl. 427—90

5 Claims

1. A process for preparing the surface of a semiconductor integrated circuit chip for conductive attachment to a receiving surface comprising removing substantially all surface contaminants and silicon dioxide from a surface of said chip, applying a layer of aluminum to said surface, applying a layer of gold to said aluminum layer, having a thickness in the range of twenty to forty times thicker than said aluminum layer, and alloying said aluminum and gold layers at a temperature

range between 380° and 440° C. for a time of four to six minutes in a nitrogen atmosphere, whereby gold is driven through said aluminum layer to penetrate said silicon surface, pulling traces of aluminum therewith.

4,293,588

METHOD OF MANUFACTURING A SEMICONDUCTOR DEVICE USING DIFFERENT ETCH RATES

Hans-Rudolf Neukomm, Thalwil, Switzerland, assignor to U.S. Philips Corporation, New York, N.Y.


Continuation of Ser. No. 914,750, Jun. 12, 1978, abandoned.
This application Aug. 30, 1979, Ser. No. 71,226

Claims priority, application Netherlands, Jun. 21, 1977, 7706802

Int. Cl.³ B05D 5/12; B44C 1/22; C03C 15/00, 25/06; H01L 21/95

U.S. Cl. 427—93

6 Claims



1. A method of manufacturing a semiconductor device having a sunken oxide pattern, which comprises: providing a silicon body having a major surface; providing a silicon oxide layer on said surface; providing a silicon nitride layer on said oxide layer; removing like portions of said oxide and nitride layers to form a patterned oxidation mask which exposes selected areas of the surface;

oxidizing said exposed areas of the surface to obtain a sunken oxide pattern in an oxidation step in which a small silicon nitride strip is formed beneath said nitride layer adjacent the edges of said patterned oxidation mask defining said sunken oxide pattern and at the interface between said oxide layer and the surface of said silicon body; and then removing said patterned oxidation mask to expose further areas of the surface adjacent the sunken oxide pattern by an etching treatment in which the silicon nitride layer is etched more rapidly than the silicon oxide layer and the silicon body material, the silicon oxide layer and the silicon body material are etched at approximately the same rate, and the small silicon nitride strip is removed, the exposed further areas of the surface being substantially flat at the edges of the oxide pattern.

3. A method as claimed in claim 1, further comprising the step of providing a layer of insulating material on said further areas of the major surface and adjoining said sunken oxide pattern to form a field effect transistor gate insulation layer.

4,293,589

PROCESS FOR HIGH PRESSURE OXIDATION OF SILICON

Mikio Takagi; Mamoru Maeda, both of Kawasaki, and Hajime Kamioka, Yokohama, all of Japan, assignors to Fujitsu Limited, Kawasaki, Japan

Division of Ser. No. 955,755, Oct. 30, 1978. This application Oct. 1, 1980, Ser. No. 192,812

Claims priority, application Japan, Oct. 31, 1977, 52-130651; Oct. 31, 1977, 52-130652; Oct. 31, 1977, 52-130653


Int. Cl.³ H01L 2/316

U.S. Cl. 427—93

16 Claims

1. A process for high pressure oxidation of silicon with high uniformity in the thickness of the oxide film, said process comprising the steps of: spacing silicon wafers apart from each other in a quartz capsule in the form of a tube with one end closed;

feeding a predetermined pressure of an oxidizing gas into said quartz capsule;
sealing said quartz capsule gas-tightly by fusing; and



heating said quartz capsule to an elevated temperature to generate a high pressure oxidizing atmosphere therein and to form said high uniformity oxide film on said silicon wafers.

4,293,590

PROCESS FOR HIGH PRESSURE OXIDATION OF SILICON

Mikio Takagi, Kawasaki; Mamoru Maeda, Tama, and Hajime Kamioka, Yokohama, all of Japan, assignors to Fujitsu Limited, Kawasaki, Japan


Division of Ser. No. 955,755, Oct. 30, 1978. This application Oct. 1, 1980, Ser. No. 192,813

Claims priority, application Japan, Oct. 31, 1977, 52-130651; Oct. 31, 1977, 52-130652; Oct. 31, 1977, 52-130653

Int. Cl.³ H01L 21/316

U.S. Cl. 427—93

7 Claims



1. A process for high pressure oxidation of silicon with high uniformity in the oxide thickness, said process comprising the steps of:

- introducing silicon wafers and a predetermined amount of an oxidizing substance into a quartz capsule in the form of a tube with one end closed;
- sealing said quartz capsule gas-tightly by fusing;
- introducing said sealed quartz capsule into a furnace placed in a pressure chamber; and
- heating said quartz capsule to an elevated temperature to simultaneously generate a high pressure oxidizing atmosphere therein to form an oxide film on said silicon wafers with said high uniformity; and
- simultaneously with said heating operation, increasing the pressure in said pressure chamber.

4,293,591

PROCESS USING ACTIVATED ELECTROLESS PLATING CATALYSTS

Nathan Feldstein, 63 Hemlock Cir., Princeton, N.J. 08540

Continuation-in-part of Ser. No. 105,865, Feb. 21, 1979, which is a division of Ser. No. 941,044, Sep. 11, 1978, Pat. No. 4,180,600, which is a continuation-in-part of Ser. No. 820,904, Aug. 1, 1977, Pat. No. 4,131,699, which is a continuation of Ser. No. 625,326, Oct. 23, 1975, Pat. No. 4,048,354. This application Mar. 31, 1980, Ser. No. 135,237

The portion of the term of this patent subsequent to Sep. 13, 1994, has been disclaimed.

Int. Cl.³ C23C 3/02

U.S. Cl. 427—97

10 Claims

1. A process for electroless or chemical plating onto a non-conductor substrate comprising the step of contacting said substrate with an activated colloidal dispersion wherein said colloidal dispersion comprises a metal which in one of its oxidation states is capable of electroless or chemical plating initiation and wherein said metal may be in an elemental state or alloy or compound and mixtures thereof and further wherein said activated colloidal dispersion comprises at least one primary stabilizer which alone renders the dispersion weakly active and at least one reactivity modifier and wherein said primary stabilizer and said reactivity modifier are inherently colloid stabilizers however they are different materials and further wherein said reactivity modifier is a non-ionic surfactant.

4,293,592

METHOD FOR PRODUCTION OF PRINTED CIRCUITS BY ELECTROLESS METAL PLATING


Hirosada Morishita; Mineo Kawamoto, and Kanzi Murakami, all of Hitachi, Japan, assignors to Hitachi, Ltd., Tokyo, Japan
Continuation of Ser. No. 549,673, Feb. 13, 1975, abandoned.

This application Dec. 6, 1976, Ser. No. 747,723
Claims priority, application Japan, Feb. 15, 1974, 49-17567

Int. Cl.³ C23C 3/02

U.S. Cl. 427—98

11 Claims




1. A method for producing a printed circuit by electroless metal plating wherein an insulating substrate having initiator for electroless metal plating on a negative pattern area of a thermo-setting resin, said thermosetting resin comprising a thermo-setting resin composition containing at least one of epoxy resin, polyester resin and phenol resin and at least one of silicone resin and wax, activity of said resin for deposition of the initiator for electroless metal plating being substantially reduced, and a positive pattern area on which electroless plated film of the circuit is to be formed is allowed to contact with an initiator washing liquid of an aqueous solution consisting essentially of 5 to 100 grams of at least one organic acid selected from the group consisting of tartaric acid, citric acid, oxalic acid and maleic acid, and 1 to 4 N hydrochloric acid or 0.1 to 0.5 N nitric acid per one liter of said aqueous solution to dissolve and remove said initiator deposited on the negative pattern area before said insulating substrate is immersed in an electroless metal plating solution to form a circuit conductor by electroless plating on said positive pattern area.

4,293,593

METHOD OF FABRICATING HEAT MIRROR FOR INCANDESCENT LAMP ENVELOPE

Bulent E. Yoldas, Churchill, Pa., assignor to Westinghouse Electric Corp., Pittsburgh, Pa.

Continuation-in-part of Ser. No. 931,346, Aug. 8, 1978, abandoned. This application Oct. 12, 1979, Ser. No. 84,217
Int. Cl.³ C03C 17/36; G02B 1/10; H01K 1/32
U.S. Cl. 427-106 9 Claims



1. The method of applying a heat mirror which is transmissive for visible radiations and reflective for infrared radiations to the interior surface of a regularly conformed hollow thin-walled vitreous light-transmitting member intended for use as an envelope for an incandescent light source, which method comprises:

- applying to the interior surface of said envelope, to a substantially uniform predetermined thickness, a clear solution having contained therein partially hydrolyzed metallic alkoxide which in the metallic alkoxide form prior to hydrolyzation is expressed as $M(OR)_n$, wherein M at least substantially comprises titanium, R is alkyl with from 1 to 6 carbon atoms, and n is the valence of M; total reacted and unreacted water in said solution being present in amount of from 0.6 mole to 8 moles per mole of said metallic alkoxide; the solution solvent being liquid aliphatic alcohol present in amount to provide a solution solids content, expressed as equivalent metallic oxide, of from about 0.1% to about 3% by weight; and as an optional constituent, said solution is acidified with at least one of hydrochloric, nitric and perchloric acid in amount of up to about 0.3 mole per mole of said metallic alkoxide;
- heating said envelope and first applied solution to a temperature of from about 300° C. to about 600° C. but not exceeding the strain point of said envelope for a sufficient period of time to convert said applied clear solution to an adherent thin continuous metallic oxide layer;
- applying over said first applied metallic oxide layer a thin continuous silver layer of predetermined thickness sufficient to be substantially transmissive for visible radiations and substantially reflective for infrared radiations;
- applying over the applied silver layer to a thin substantially uniform predetermined thickness a second clear solution as used to apply said first-applied metallic oxide layer; and
- heating said envelope and applied second clear solution to a temperature of from about 300° C. to about 425° C. under conditions which are non-reactive for silver for a sufficient period of time to convert said second applied clear solution to an adherent clear metallic oxide layer.

4,293,594

METHOD FOR FORMING CONDUCTIVE, TRANSPARENT COATING ON A SUBSTRATE

Bulent E. Yoldas, Churchill, and Douglas M. Mattox, Forest Hills, both of Pa., assignors to Westinghouse Electric Corp., Pittsburgh, Pa.


Filed Aug. 22, 1980, Ser. No. 180,768
Int. Cl.³ B05D 7/22, 5/12; C03C 17/245
U.S. Cl. 427-107 12 Claims

1. The method of forming a conductive, transparent coating on the interior surface of a vitreous tubular member of predetermined dimensions, which method comprises:

- in a carrier gas comprising oxygen and exterior to said

member to be coated, forming a vapor from a material substantially comprising organic tin halide compound having a predetermined condensation temperature and a predetermined decomposition temperature, with the temperature of said carrier gas and said formed vapor maintained between the condensation temperature and the decomposition temperature of said organic tin halide compound;

- heating said member to be coated to a temperature greater than the decomposition temperature of said organic tin halide compound, flowing said heated carrier gas and said formed vapor at a predetermined rate into one



end portion of said heated member and longitudinally through said heated member to cause a predetermined amount of said formed vapor to contact the interior surface of said heated member where the contacting vapor decomposes and forms said transparent conductive coating;

and

- flowing said carrier gas and residual heated vapor out of the other end portion of said heated member, and cooling said carrier gas and said residual vapor to less than the condensation temperature of said organic tin halide compound to recover same.

4,293,595


AQUEOUS PROCESS FOR MAKING A CONDUCTIVE MEDIUM FOR ELECTROSTATIC PRINTING

William H. Kreiling, Longmeadow, Mass., and Edward S. Jones, Bellvale, N.Y., assignors to International Paper Company, New York, N.Y.

Filed Mar. 28, 1979, Ser. No. 24,584
Int. Cl.³ B05D 5/12

U.S. Cl. 427-121

14 Claims



1. An improved process for making a conductive medium for electrostatic printing comprising applying to a first side of a high density basestock a partially insolubilizable aqueous conductive latex precoat comprising an interpolymers of a butadienebased polymer latex and a $\alpha\beta$ -olefinically unsaturated carboxylic acid monomer, the insolubilization of the conductive latex resulting from partial insolubilization of the major conductive component of the latex; applying to the other side of the basestock a first aqueous low-resistance coating; partially insolubilizing the conductive latex precoat, the extent of said partial insolubilization being controlled so as to provide to said first side of the basestock a surface resistivity of about 1×10^{10} ohm/square at 50% relative humidity; applying

to the partially insolubilized conductive latex precoat an aqueous dielectric coating; and applying to the first aqueous low-resistance coating a second aqueous low-resistance coating.

4,293,596

SURFACE COATING METHOD EMPLOYING A TEMPORARY BONDING

Allan R. B. Furendal; Bernt Larsson, and Erik R. Nilsson, all of Karlskoga, Sweden, assignors to AB Bofors, Bofors, Sweden

Filed Apr. 5, 1976, Ser. No. 673,843

Claims priority, application Sweden, Apr. 11, 1975, 7504193
Int. Cl.³ B05B 5/00; B05D 3/04

U.S. Cl. 427-160

30 Claims

1. A method of coating a surface with a coherent coating containing a polymeric material as the main bonding agent wherein said main bonding agent is not film forming at room temperature, but forms the coherent phase of the finished coating which comprises:

- applying to said surface a dispersion containing said main bonding agent dispersed in an inert liquid forming the continuous phase in relation to the dispersed main bonding agent, said dispersion also containing a second and temporary bonding agent in an amount of 0.5-25% by volume based upon the total quantity of solids in the dispersion;
- then allowing the continuous phase of the dispersion to evaporate or be driven off;
- causing said main bonding agent to precipitate in the form of polymer particles having a diameter of 0.1-30 μ m wherein the minimum film forming temperature (MFT) of said bonding agent is at least 20° C. above the temperature prevailing in the coating during step B above;
- causing said temporary bonding agent to precipitate at the same time as said main bonding agent to form a porous powder layer on said surface, and wherein the minimum film forming temperature (MFT) of said temporary bonding agent is at least 20° C. below the MFT for said main bonding agent and is below the temperature prevailing in the coating during step B above, and wherein said temporary bonding agent is present in an amount sufficient to bond the particles of said main bonding agent to said surface with sufficiently strong adhesion forces to permit a certain handling of the porous powder layer thus obtained;
- then exposing said porous powder layer to a solvent capable of dissolving said main bonding agent and causing the bonding agent particles to flow together to form a coherent coating;
- then driving off any excess solvent and drying said coherent coating.

4,293,597

METHOD OF FORMING A ROOFING COMPOSITE USING SILICONE RUBBER COMPOSITION

Stanley J. Bessmer, Cohoes, and Warren R. Lampe, Ballston Lake, both of N.Y., assignors to General Electric Company, Waterford, N.Y.

Continuation of Ser. No. 537,085, Dec. 30, 1974, abandoned, which is a division of Ser. No. 478,824, Jun. 12, 1974, Pat. No. 3,888,815, which is a continuation of Ser. No. 389,733, Aug. 20, 1973, abandoned, which is a continuation of Ser. No. 180,068, Sep. 13, 1971, abandoned. This application Sep. 28, 1979, Ser. No. 80,143

Int. Cl.³ B05D 7/14, 3/00

U.S. Cl. 427-186

8 Claims


1. A process for forming a composite of a silicone rubber composition and a substrate wherein the bond between said silicone rubber composition and said substrate is hydrolytically stable, said process comprising:

- applying to a substrate a self-bonding room temperature vulcanizable silicone rubber composition consisting essentially of (a) a linear, fluid organopolysiloxane containing terminal silicon-bonded hydroxy groups and having a viscosity of 500 to 10,000,000 centipoise when measured at

25° C., the organic groups of the aforesaid organopolysiloxane representing monovalent hydrocarbon radicals; (b) 5 to 300% by weight of said linear organopolysiloxane of a filler; (c) from 0.1-10% by weight based on the linear organopolysiloxane of an alkyl silicate selected from the group consisting of (1) a monomeric organosilicate corresponding to the general formula,



where R^4 is a radical selected from the group consisting of monovalent hydrocarbon radicals and halogenated monovalent hydrocarbon radicals and R^4 is selected from the group consisting of alkyl, haloalkyl, aryl, haloaryl, alkenyl, cycloalkyl, cycloalkenyl, cyanoalkyl, alkoxy and acyloxy radicals, and (2) a liquid partial hydrolysis product of the aforesaid organosilicate monomeric compounds; (d) from 0.1 to 5% by weight of the linear organopolysiloxane of a catalyst which is a metallic salt of an organic monocarboxylic or dicarboxylic acid in which the metal ion is selected from the group consisting of lead, tin, zirconium, antimony, iron, cadmium, barium, calcium, titanium, bismuth and manganese with the exception of manganese naphthenate and calcium stearate and (e) an amount in the range of from 0.5 to 4% by weight based on the linear organopolysiloxane, that is sufficient to form a hydrolytically stable bond with a substrate, of a nitrogen-functional silane of the formula,



where R is selected from the group consisting of monovalent hydrocarbon radicals and halogenated monovalent hydrocarbon radicals, Σ is a hydrolyzable group selected from the group consisting of alkoxy, phenoxy, amino and dialkylamino and θ is a nitrogen-functional radical which is a saturated, unsaturated or aromatic hydrocarbon residue which in addition to nitrogen-functionality may be functionalized by a radical selected from the group consisting of amino, cyano, thio, oxo, and ester, and multiples and combinations thereof and a is a whole number that varies from 0 to 2, and where there is present 5 to 50% by weight of the total composition of a hydrocarbon solvent and an amount of an oxygenated solvent selected from the group consisting of alcohols, ethers, ketones and esters that will prolong the work life of the composition without retarding the final cure; and

- permitting said composition to cure.

4,293,598

METHOD FOR INCREASING BORON¹⁰ CONTENTS OF NEUTRON ABSORBING ARTICLES

Michael T. Hortman, Tonawanda, and Robert G. Naum, Lewiston, both of N.Y., assignors to The Carborundum Company, Niagara Falls, N.Y.

Filed Nov. 13, 1978, Ser. No. 960,150
Int. Cl.³ G21F 1/10

U.S. Cl. 427-203

9 Claims



1. A method for increasing the B¹⁰ content of a neutron absorbing article which includes neutron absorbing boron carbide particles in a matrix of cured solid polymeric material which comprises coating a surface of such article with a curable liquid synthetic organic polymeric material, applying boron carbide particles to the curable polymeric material so

that portions of such particles project beyond the surface of the curable polymeric material, and curing and solidifying the polymer to solid form so that it holds the boron carbide particles in place on the neutron absorbing article, with portions of said particles projecting beyond the surface of the cured polymeric material.

4,293,599

METHOD OF FORMING DECORATIVE RELIEF PATTERN AND PATTERN-FORMING DEVICE THEREFOR

Kiyoshi Hori, Osaka, and Nobuyoshi Nagata, Nara, both of Japan, assignors to Nippon Paint Co., Ltd., Osaka, Japan
Filed Oct. 28, 1975, Ser. No. 626,446

Claims priority, application Japan, Oct. 29, 1974, 49-125247; Nov. 5, 1974, 49-127764

Int. Cl.³ B05D 3/12, 5/02

U.S. Cl. 427—274

19 Claims

1. In the method of forming a relief pattern on the surface of an article or substrate which comprises coating the surface thereof with a coating composition and applying thereto, during the course of the drying of the coating, a pattern-forming device with a design to be patterned thereon once or a plurality of times, the improvement according to which the pattern-forming device is composed of a rigid or semi-rigid material having air-permeable pores therein and having a percent water or liquid absorption of from about 15 to 99 percent and the pattern-forming device contains a releasing agent therein, the said releasing agent being the same material as the solvent employed in the coating composition, and the said coating composition having a viscosity in the range of from about 20 to 1000 poises.

4,293,600

METHOD OF FINISHING FIBERS OR FABRICS WITH DISPERSIONS OF HYDROPHILIC ACRYLIC RESINS

Herbert Fink, Bickenbach; Klaus Huebner, Ober-Ramstadt-Eiche; Horst Dinklage, Darmstadt-Arheilgen, and Hans Otto-frickenstein, Darmstadt-Eberstadt, all of Fed. Rep. of Germany, assignors to Röhm GmbH, Darmstadt, Fed. Rep. of Germany


Division of Ser. No. 20,037, Mar. 13, 1979, Pat. No. 4,239,671, which is a continuation-in-part of Ser. No. 955,796, Oct. 30, 1978, abandoned. This application Jun. 6, 1980, Ser. No. 157,177
Claims priority, application Fed. Rep. of Germany, Nov. 4, 1977, 2749386

Int. Cl.³ B05D 3/02

U.S. Cl. 427—385.5

9 Claims

1. The method of finishing fibers or fabrics which comprises applying thereto an aqueous dispersion of a hydrophilic copolymer prepared by polymerizing, in an aqueous medium, a monomer mixture comprising: (1) from 65 to 94.5 percent, by weight of said copolymer, of a member selected from the group consisting of lower alkyl acrylates and methacrylates; (2) a compound of the formula



wherein

R is hydrogen or methyl,

R¹ is hydrogen or alkyl having 1 to 4 carbon atoms,

Y is oxygen or —NR²—,

R² is hydrogen or alkyl having 1 to 4 carbon atoms, and

n is an integer from 1 to 25; (3) up to 8 percent, by weight of the copolymer, of a member selected from the group consisting of copolymerizable carboxylic acids and salts of such acids; and (4) at least one monomer capable of cross-linking said copolymer, and cross-linking said copolymer by drying said dispersion and heating the dried treated fiber or fabric.

4,293,601

FLOWER-LIKE DECORATIVE ORNAMENT


Bernard M. Cole, 7 Park Dr. East, Old Westbury, N.Y. 11568

Filed Sep. 5, 1980, Ser. No. 184,417

Int. Cl.³ A41G 1/00

U.S. Cl. 428—24

8 Claims



1. A flower-like decorative ornament for use in gift-wrapping a package comprising:

(A) an artificial flower comprising a base, a pattern of petals extending at least partially upwardly from said base, and a passage extending longitudinally through said base; and

(B) an elasticized cord having its end portions knotted together to define a section of enlarged diameter incapable of passing through said passage, a pair of free ends to one side of said enlarged section and a loop to the other side thereof; said loop passing longitudinally through said passage with said enlarged section being at least partially disposed above said passage to slidably mount said flower on said loop, said cord being configured and dimensioned such that when said loop is stretched about a package so that said enlarged section is disposed immediately atop said passage, said free ends extend at least partially upwardly from said enlarged section and terminate closely adjacent the uppermost portions of said petals, whereby said free ends have the appearance of stamens.

4,293,602

NATURAL BOTANICAL ORNAMENT

James P. Coffey, and Bettie L. Coffey, both of 137 South St., Ext., Warwick, N.Y. 10990

Filed Dec. 17, 1979, Ser. No. 104,010

Int. Cl.³ A01N 3/00; A44C 25/00

U.S. Cl. 428—28

8 Claims

1. A fragrant ornament molded in a compression molding process from a mixture comprising, in combination:

(a) a naturally fragrant botanical material comminuted into a particulate form,

(b) an essential oil, which is capable of complementing the fragrance of said botanical material, and which is absorbed on the botanical material or an optional absorbent fixative, and

(c) a fiber reinforced fluorocarbon resin binder, which binds the botanical material together without masking or sealing the botanical material, allowing the release of the fragrance from said botanical material and said absorbed essential oil, said resin binder being dispersed through the botanical material from an aqueous suspension of the fluorocarbon resin.

4,293,603

ACRYLIC SHEET-LACQUER LAMINATES AND ARTICLES OF FURNITURE MADE THEREFROM


Charles R. Hayman-Chaffey, and Frederick W. Hayman-Chaffey, both of New York, N.Y.

Filed Jan. 9, 1980, Ser. No. 110,559

Int. Cl.³ B32B 3/00, 27/00, 27/08; B05B 5/00

U.S. Cl. 428—86

23 Claims



1. A method of making a decorative laminate comprising the steps of:

(a) providing as a starting material an acrylic composition sheet which includes a pair of opposed spaced surfaces;

(b) applying an acrylic paint coating composition in a selected color to at least a portion of one surface of the acrylic composition sheet;

(c) applying an acrylic primer coating composition over at least that portion of the surface of the sheet to which the acrylic paint coating has been applied; and

(d) adhesively bonding the surface of said sheet to which the acrylic paint coating composition and the primer acrylic coating have been applied to a backing member, whereby the uncoated surface of the acrylic sheet layer forms the outer layer of the laminated article.

19. An article of furniture comprising at least one member thereof which includes:

an acrylic composition sheet which includes a pair of opposed spaced surfaces;

a thin layer of acrylic paint coating composition in a selected color on at least a portion of one surface of the acrylic composition sheet;

a thin layer of acrylic primer coating composition over at least that portion of the one surface of the acrylic composition sheet to which the acrylic paint coating has been applied; and

a backing member adhesively secured to said acrylic composition sheet on the same side thereof to which the acrylic paint coating composition and the acrylic primer coating composition has been applied.

4,293,604

FLOCKED THREE-DIMENSIONAL NETWORK MAT


Douglas D. Campbell, Minneapolis, Minn., assignor to Minnesota Mining and Manufacturing Company, Saint Paul, Minn.

Filed Jul. 11, 1980, Ser. No. 168,683

Int. Cl.³ B32B 5/28

U.S. Cl. 428—90

11 Claims



1. A flocked mat especially suited for pedestrain traffic particularly to wipe wet and/or dirty feet, said mat comprising:

(1) a web formed of a three-dimensional, lofty, open, porous, network comprising strands of water-resistant, organic

polymer material generally defining connecting open spaces capable of receiving dirt, said web being at least 0.5 cm in thickness, having a void volume of at least about 75% and being resiliently compressible underfoot by about at least 10% of its thickness;

(2) a continuous backing layer of organic polymeric material having a thickness on the order of 0.2 to 2.5 mm attached to one major surface of said web and forming one major surface of said mat;

(3) a resinous water-resistant bonding adhesive substantially entirely coating the surfaces of said strands of said network without filling said open spaces substantially throughout said web; and

(4) water-resistant, wear-resistant organic textile flocking material having a denier in the range of about 0.5 to 25 and a length in the range of about 0.25 to 2.5 mm and being uniformly distributed substantially throughout said web and adhesively bonded to said web by said resinous bonding adhesive substantially entirely covering the surfaces of each of said strands of said network substantially without filling said open spaces to provide a flocked web capable of providing a wiping surface for dirt and water, receiving, obscuring and holding dirt therein and facilitating the evaporation of water.

4,293,605

TIE FOR WOOD PILES


Alf Persson, Badhusgatan 10, 686 00, Sunne, and Nils O. Söderberg, Skogsberg 680 15, Backalund, both of Sweden

Filed Jul. 12, 1979, Ser. No. 56,941

Int. Cl.³ B32B 3/04; B65D 85/62

U.S. Cl. 428—126

6 Claims



1. A device for inserting between layers of wooden boards or like rigid structures, comprising:

a longitudinally elongated strip of stiff cellulosic material having a bottom layer of predetermined constant width and formed with a pair of top layers over the majority of the width thereof, and defining a plane;

means for maintaining the layers together;

means for imparting bending resistance to said strip so that

when held at one end with that end horizontal the free end does not deflect significantly from the horizontal, said

means consisting of a pair of longitudinally extending single layer deformable projections formed from said stiff

cellulosic material, one provided at each of the lateral edges of said strip, and each standing upright from said

plane substantially the entire length of said strip; each said projection being defined by a longitudinally extending

channel that is substantially triangular in cross-section with two legs of the triangle formed from one of said top

layers joining at an obtuse angle and defining an apex upstanding from said one layer, and the third leg of the

triangle formed from the bottom layer with said third leg coplanar with said bottom layer; and

means for preventing buckling of said channels, comprising a fibrous material bundle disposed in each of said channels.

4,293,606

LOW FRICTION, ABRASION RESISTANT COATING FOR TRANSPARENT FILM

J. Lamar Zollinger, Maplewood, and Larry A. Lien, Forest Lake, both of Minn., assignors to Minnesota Mining and Manufacturing Company, St. Paul, Minn.


Filed Mar. 13, 1978, Ser. No. 885,762
Int. Cl.³ B32B 3/00, 7/14, 27/38, 9/04

U.S. Cl. 428-203


3 Claims

1. A transparent, imaged motion picture film having on at least one face thereof a mottle free abrasion resistance coating of from 0.5 to 15.0 μ on at least one face of said film, said coating resulting from the cure of a composition comprising at least 30% by weight of an epoxy-terminated silane, said coating:

- (1) having a coefficient of friction against tin-plated steel of from 0.05 to 0.30, as measured by ANSI PH 1.47-1972,
- (2) having a dynamic coefficient of friction against said coating of less than 0.41, and
- (3) allowing at least 75% transmission of all radiation between 400 and 780 nm which is transmitted by said imaged film without said coating, wherein said epoxy-terminated silane is represented by the formula:



wherein R^2 and R^3 are independently alkylene groups of 1 to 4 carbon atoms, and R^4 is alkyl of 1 to 4 carbon atoms, and wherein said coating contains from 0.05 to 15.0% by weight of the coating of an oligomeric or polymeric material having at least 5% by weight of said material comprised of siloxane units of the formula:



wherein R^5 and R^6 are independently selected from alkyl groups of 1 to 4 carbon atoms and phenyl groups having no more than 10 carbon atoms, and p is a positive whole integer of at least 1.

4,293,607

FLEXIBLE SHEET COVERING MATERIAL FOR WRAPPING HEAT, COLD AND SOUND INSULATION

Ulf J. Millgardh, Stora Mellösa; Ulf W. Lindberg, Örebro; Weimar A. Annelöf, Örebro; Nils H. Werner, Örebro, and Björn Wilmelius, Örebro, all of Sweden, assignors to Örebro Pappersbruks AB, Örebro, Sweden


Division of Ser. No. 884,299, Mar. 7, 1978, Pat. No. 4,188,248.
This application Aug. 29, 1979, Ser. No. 70,577

Claims priority, application Sweden, Mar. 14, 1977, 7702865
The portion of the term of this patent subsequent to Feb. 12, 1997, has been disclaimed.

Int. Cl.³ B32B 7/02

U.S. Cl. 428-212

6 Claims



1. A continuous flexible self curling sheet material intended

as a semifinished product for wrapping around heat, cold or sound insulation on piping, said sheet material comprising a multilayer laminate containing at least two layer groups, the first group forming the outer part of the sheet material when rolled up, and containing a supporting layer consisting of a kraft paper with minor extensibility, covered on its outwardly facing surface with a polyethylene layer and similarly on its inner surface with a polyethylene or glue layer, while the second group, forming the inner part of the material when rolled up, containing a layer consisting of a highly extensible kraft paper, which is given a contracting tendency due to its striving to retain its original shape, by being given a high tensional load during manufacture, the highly extensible kraft paper having a polyethylene or glue layer on its surface facing towards the first layer group, said glue layer being bonded to the corresponding layer in the first layer group or constituting said corresponding layer, and on its surface facing the opposite direction being protected by a polyethylene layer, both layer groups being bonded to each other such that the sheet material has an enduring precurvature characteristic for the sheet material.

4,293,608

OLEFIN PACKAGING LAMINATE


Tsutomu Isaka, Inuyama, and Saburoh Kumada, Kawanishi, both of Japan, assignors to Toyo Baseki Kabushiki Kaisha, Japan

Filed Oct. 15, 1979, Ser. No. 84,498

Int. Cl.³ B32B 27/08

U.S. Cl. 428-220

19 Claims



1. A heat sealable material comprising (A) a stretched base layer comprising a propylene polymer and (B) on at least one surface of said base layer a stretched surface layer comprising a blend of a propylene-ethylene copolymer and a C_4 - $\text{C}_{10}\alpha$ -olefin-propylene copolymer comprising units of C_4 - $\text{C}_{10}\alpha$ -olefin and units of propylene in a weight proportion of 30:70 to 5:95, said blend being present in a weight proportion of 20:80 to 94:6 by weight.

4,293,609

FLEXIBLE ABSORBENT LAMINATES

Robert E. Erickson, Midland, Mich., assignor to The Dow Chemical Company, Midland, Mich.

Continuation-in-part of Ser. No. 55,586, Jul. 9, 1979, abandoned.
This application Jun. 30, 1980, Ser. No. 164,644

Int. Cl.³ B32B 7/00

U.S. Cl. 428-246

28 Claims

1. A flexible hydrophilic absorbent laminate which has a rapid absorption rate and is soft and flexible at low and high relative humidities which comprises

- (a) a central, substantially discontinuous and crushed film consisting of a water-swellaible hydrophilic polymer, and



- (b) a layer of wicking substrates bonded to both sides of said film.

4,293,610

ELECTROSTATIC PRINTING MEDIUM


William H. Kreiling, Longmeadow, Mass., and Edward S. Jones, Bellvale, N.Y., assignors to International Paper Company, New York, N.Y.

Division of Ser. No. 24,584, Mar. 28, 1979, This application Nov. 30, 1979, Ser. No. 99,006

Int. Cl.³ B32B 7/00

U.S. Cl. 428-246

16 Claims



1. An improved conductive medium for electrostatic printing comprising on a first side of a high density basestock a partially insolubilized aqueous conductive latex precoat comprising an interpolymer of a butadiene-based polymer latex and a $\alpha\beta$ -olefinically unsaturated carboxylic acid monomer, the insolubilization of the conductive latex resulting from partial insolubilization of the major conductive component of the latex, the extent of said partial insolubilization being controlled so as to provide to said first side of the basestock a surface resistivity of about 1×10^{10} ohm/square at 50% relative humidity, and on top thereof a dielectric coating and comprising on the other side of the high density basestock at least two low-resistance coatings.

4,293,611

SILICONE POLYETHER COPOLYMERS

Eugene R. Martin, Onsted, Mich., assignor to SWS Silicones Corporation, Adrian, Mich.


Division of Ser. No. 86,906, Oct. 22, 1979, Pat. No. 4,246,423.
This application May 20, 1980, Ser. No. 152,054

Int. Cl.³ B32B 7/00, 25/00


U.S. Cl. 428-266

14 Claims


1. A process for treating a textile material which comprises coating a textile material with a composition containing a silicone polyether copolymer having the general formula



where R is a radical selected from the group consisting of



in which the radical R is linked to the polyether through an ester linkage, R^1 is a divalent hydrocarbon radical selected from the group consisting of $(-\text{CH}_2)_n$, $-\text{CH}=\text{CH}-$ and a cyclic radical selected from the group consisting of C_6H_4 , C_6H_8 and C_{10}H_6 ; A is a silicone containing monovalent or divalent radical selected from the group consisting of



R^2 is selected from the group consisting of saturated divalent hydrocarbon radicals, hydrocarbonoxy radicals in which the hydrocarbon group is linked to the silicon by a carbon bond and the oxygen is in the form of an ether linkage, and unsaturated divalent hydrocarbon radicals, R^3 is selected from the

group consisting of monovalent hydrocarbon radicals having from 1 to 18 carbon atoms, alkoxy radicals having from 1 to 18 carbon atoms and $\text{OSi}(\text{R}^4)_3$ radicals, R^4 is a monovalent hydrocarbon radical having from 1 to 18 carbon atoms, R^5 is a monovalent radical selected from the group consisting of $\text{O}_0.5\text{Si}(\text{R}^4)_3$ and $\text{O}_0.5\text{R}^4$, where R^4 is the same as above, and when R is cationic, then A must be anionic and when R is nonionic then A must be nonionic, a is a number of from 0 to 4, b , c and d are each numbers of from 0 to 1, the sum of b , c and d must be at least 1 when A is a monovalent radical and when A is a divalent radical b , c and d must be at least 0.5 and up to 3, with the proviso that when c is greater than 0, then a must be at least 1, e is a number of from 1 to 200, m is a number of from 1 to 20,000, n is 2, 3 or 4, x is a number of from 1 to 400, and y is a number of from 0 to 8, and thereafter drying the coated material at a temperature of from 50° to 200° C. in the presence of atmospheric moisture.

5. The process of claim 1, wherein the textile material is polyester.

4,293,612

NEEDLE-PUNCH CARPET WITH BINDER CONTAINING ALKALI-STABILIZED SILICIC ACID
Kjell R. Andersson, Surte, and Hans E. Johansson, Kungälv, both of Sweden, assignors to Elektrokemiska Aktiebolaget, Surte, Sweden

Filed Jan. 16, 1980, Ser. No. 112,443

Claims priority, application Sweden, Jan. 18, 1979, 7900451
Int. Cl.³ D04H 1/08

U.S. Cl. 428—281

8 Claims

7. A needle punch carpet comprising synthetic fibers which are mechanically bound together by needling and which are further chemically bound together by the dried residue of an aqueous mixture of an organic binder latex and an alkali-stabilized silicic acid sol having particles of a size between 1 and 100 nm, the particles being present in an amount comprising between 0.1 to 12 percent by weight, calculated as dry SiO_2 , based upon the weight of the synthetic fibers, and the amount of dry SiO_2 being between 1 and 30 weight percent of the organic binder solids, said residue being dispersed throughout the body of the carpet whereby said carpet exhibits an improved abrasion resistance and chalking is minimized.

4,293,613

ACRYLIC FIBER HAVING IMPROVED BASIC DYEABILITY

Hartwig C. Bach, and Helmut E. Hinderer, both of Pensacola, Fla., assignors to Monsanto Company, St. Louis, Mo.

Filed Jun. 6, 1980, Ser. No. 157,129

Int. Cl.³ D02G 3/00

U.S. Cl. 428—364

5 Claims

1. An acrylic fiber having improved basic dyeability, said fiber being formed from a blend of
a. an acrylic polymer containing at least about 35 weight percent acrylonitrile and 1 to 20 weight percent of a sulfonated vinyl monomer, said sulfonated vinyl monomer being polymerized with said acrylonitrile, and
b. 1-20 weight percent of polystyrene, said polystyrene being present in the form of a separate phase dispersed throughout the fiber.

4,293,614

CRIMPED POLYESTER FILAMENT

LeMoyné W. Plischke; Harold M. Familant, both of Pensacola, and Darrell A. Kelly, Milton, all of Fla., assignors to Monsanto Company, St. Louis, Mo.

Filed Nov. 2, 1979, Ser. No. 90,823

Int. Cl.³ D02G 3/00

U.S. Cl. 428—370

4 Claims

1. A melt spun filament having a crimp level of at least 5 crimps per inch and being composed of two polyester components arranged in a side-by-side relation, wherein the polyester

of one component contains CaF_2 uniformly dispersed therein at a concentration of at least 200 parts per million based on the weight of the polyester of said component and the polyester of the other component contains no CaF_2 and wherein the weight ratio of the CaF_2 -containing component to the other component is 5:95 to 70:30, said filament being characterized in that the polyester of both components is of the same chemical structure and thermal history.

4,293,615

POLYVINYL BUTYRAL LAMINATES

Griffith Bowen, Wilmington, Del., and Peter A. Fowell, Chadds Ford, Pa., assignors to E. I. Du Pont de Nemours and Company, Wilmington, Del.


Filed May 30, 1980, Ser. No. 154,853

Int. Cl.³ B32B 27/36, 27/42

U.S. Cl. 428—412

5 Claims

1. A laminar structure comprising at least one layer of glazing material and a sheet of plasticized polyvinyl butyral having a hydroxyl content of about from 15 to 30% by weight, calculated as vinyl alcohol, and, in compatible admixture therewith, about from 10 to 70 parts per hundred parts by weight of at least one propylene oxide oligomer of the general formula



wherein R is a linear or a branched aliphatic, cycloaliphatic, aralkyl, aromatic, alkoxy alkyl or heterocyclic radical of 1 to 14 carbon atoms, n is an integer of 1 to 30 and has an average value of about from 1 to 20, and m is an integer of from 1 to 3 wherein the average molecular weight of the propylene oxide oligomers is about from 300 to 2500.

3. A laminar structure of claim 1 wherein the glazing material is polycarbonate sheeting.

4,293,616

PAINTABLE ONE-COMPONENT RTV SYSTEMS

Alfred H. Smith, Jr., Ballston Lake, and M. Dale Beers, Schenectady, both of N.Y., assignors to General Electric Company, Waterford, N.Y.

Division of Ser. No. 16,255, Feb. 28, 1979, Pat. No. 4,247,445.

This application May 21, 1980, Ser. No. 152,077

Int. Cl.³ B32B 15/08

U.S. Cl. 428—447

22 Claims

1. A painted laminate structure comprising (i) a substrate selected from the class consisting of masonry surfaces, cellulosic substrates, metal surfaces and plastic surfaces; (ii) cured silicone elastomer over the substrate surface which is formed by exposing to atmospheric moisture a mixture of ingredients, comprising (A) 100 parts by weight of a silanol end-stopped diorganopolysiloxane polymer where the organo groups are monovalent hydrocarbon radicals and the polymer has a viscosity that varies from 50 to 1,000,000 centipoise at 25° C.; (B) from 200 to 500 parts by weight of calcium carbonate; (C) from 1 to 10 parts by weight of a cross-linking agent of the formula,



where R is a monovalent hydrocarbon radical of 1 to 8 carbon atoms and R^1 is a monovalent hydrocarbon radical of 2 to 30 carbon atoms and m is 0 or 1; and (D) from 0.01 to 5 parts by weight of a curing catalyst comprising an organic tin salt of an organic acid or a tin salt of an organic acid; and (iii) over the cured silicone elastomer there being present a coating of an

organic paint selected from the class consisting of organic latex paints and organic oil base paints.

4,293,617

PROCESS FOR PRODUCING STRIPPABLE COPPER ON AN ALUMINUM CARRIER AND THE ARTICLE SO OBTAINED

Albert E. Nagy, Mentor-on-the-Lake, Ohio, assignor to Gould Inc., Rolling Meadows, Ill.

Filed Dec. 26, 1979, Ser. No. 106,477

Int. Cl.³ C25D 5/44

U.S. Cl. 428—469

10 Claims

1. A process for producing a composite structure suitable for use in connection with the manufacture of printed circuits which includes a carrier layer of aluminum and a covering layer of copper which structure is characterized by the fact that the copper layer is tenaciously bonded to said carrier layer of aluminum but readily separable therefrom by mechanical means without destroying the integrity of the copper layer which process comprises the steps of: (a) providing a layer of aluminum foil, (b) cleaning at least one major surface of said aluminum foil to remove surface contaminants therefrom, (c) positioning said aluminum foil in a suitable electrolyte and passing electrical current therethrough in such a manner that said foil is rendered cathodic to activate the surface of said aluminum foil, (d) positioning said activated foil in a suitable electrolyte comprising, in volume percent, from about 53 to 73% phosphoric acid, from about 5 to about 25% sulfuric acid, and from about 12 to about 32% water, and passing electrical current therethrough in such a manner that said foil is rendered anodic so as to form a thin layer of aluminum oxide on the surface thereof, and (e) electrodepositing a thin layer of copper on the anodized surface of aluminum foil.

4,293,618

SINTERED BODY FOR USE IN A CUTTING TOOL AND THE METHOD FOR PRODUCING THE SAME

Akio Hara, and Shuji Yazu, both of Itami, Japan, assignors to Sumitomo Electric Industries, Ltd., Osaka, Japan

Filed May 7, 1979, Ser. No. 36,989

Claims priority, application Japan, May 17, 1978, 53/58546

Int. Cl.³ C22C 29/00; B22F 7/06

U.S. Cl. 428—551

4 Claims

1. In a diamond sintered body or high pressure from boron nitride sintered body for use in a cutting tool, the improvement wherein said sintered body is supported by cermet in which carbide crystals in the form of (Mo, W)C chiefly consisting of molybdenum are bonded by iron group metals.

4,293,619

SILICON-NITRIDE AND METAL COMPOSITE

Richard L. Landingham, Livermore, Calif., and Sarah A. Huffsmith, Urbana, Ill., assignors to The United States of America as represented by the United States Department of Energy, Washington, D.C.

Filed Jun. 11, 1979, Ser. No. 47,597

Int. Cl.³ B32B 15/04

U.S. Cl. 428—623

6 Claims

1. A composite formed in part from a ceramic substrate of silicon nitride and from a refractory metal substrate, said composite comprising:

- (i) the ceramic substrate of silicon nitride;
 - (ii) the refractory metal substrate which comprises Mo, Ti and Zr; and
 - (iii) a layer greater than 0.1 mm in thickness consisting essentially of MoSi_2 between the ceramic substrate and refractory metal substrate, said layer bonded to the ceramic substrate by a first reacted sublayer on the order of 0.01 mm in thickness and bonded to the metal substrate by a second reacted sublayer on the order of 0.01 mm in thickness;
- whereby the composite will remain intact as a composite during thermal cycling up to pressures of 240 MPa and temperatures of 1000° C.

thermal thermal cycling up to pressures of 240 MPa and temperatures of 1000° C.

4. A composite comprising:
 - a ceramic substrate of silicon nitride;
 - a refractory metal substrate selected from Mo, W, Ta and their associated alloys; and
 - a layer greater than 0.1 mm in thickness consisting essentially of MoSi_2 between the ceramic substrate and refractory metal substrate;

with said layer bonded to the ceramic substrate by a first reacted sublayer on the order of 0.01 mm in thickness and bonded to the metal substrate by a second reacted sublayer on the order of 0.01 mm in thickness, wherein said composite is prepared by:

- (a) contacting as a bonding agent, the layer of MoSi_2 with a portion of the silicon nitride substrate and with a portion of the refractory metal substrate;
- (b) heating the layer of MoSi_2 to a temperature of between about 1000° C. to about 1300° C.; and
- (c) compressing the layer with said portions of said substrates, simultaneously with said heating, such that said compression of the layer is with a pressure of at least 30 MPa.

4,293,620

PROCESS FOR THE DEPOSITION OF THICK CHROMIUM FILMS FROM TRIVALENT CHROMIUM PLATING SOLUTIONS AND ARTICLE SO PRODUCED

James M. L. Vigar, Winchester, England, assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Jun. 9, 1980, Ser. No. 157,714

Claims priority, application United Kingdom, Jun. 29, 1979, 22791/79

Int. Cl.³ C25D 3/06, 5/12, 5/14

U.S. Cl. 428—667

10 Claims

1. A process of electroplating an article with a layer of chromium exceeding five microns in thickness comprising the step of electroplating the article with an initial relatively thin layer of chromium from a first equilibrated aqueous solution of chromium (III)—thiocyanate complexes of relatively low chromium concentration of about 0.003 M, and plating the major proportion of the remaining thickness in one or more steps from a second equilibrated aqueous solution of chromium (III)—thiocyanate complexes of relatively higher concentration of about 0.1 M.

9. An article plated by a process as claimed in claim 1.

4,293,621

RECORDING MEDIUM

Yuji Togami, Isehara, Japan, assignor to Nippon Hosokawa Kyokai, Tokyo, Japan


Filed Oct. 5, 1979, Ser. No. 82,238

Claims priority, application Japan, Oct. 12, 1978, 53-125298; May 4, 1979, 54-54153

Int. Cl.³ B32B 15/00

U.S. Cl. 428—678

4 Claims



1. A recording medium comprising a recording carrier for magnetically recording a binary code signal, said carrier being formed of an amorphous magnetic layer consisting of at least a rare earth metal and an iron family metal, said amorphous magnetic layer comprising a plurality of thin amorphous magnetic layers stacked on each other, the composition ratio between the rare earth metal and the iron family metal in each of said thin layers being different from the composition ratio in an

adjacent one of said thin layers, the thickness of a first one of said plurality of amorphous magnetic thin layers, which has a larger perpendicular magnetic anisotropy, being larger than a thickness of an adjacent second one of said plurality of amorphous magnetic thin layers, which has a smaller perpendicular magnetic anisotropy, said amorphous magnetic layer enabling said recording carrier to magnetically and thermally stably record a binary code signal even if the diameter of a recorded information bit is on the order of one micrometer.

4,293,622 STEP CELL

Nikola Marincic, Winchester, and James Epstein, Sharon, both of Mass., assignors to Battery Engineering, Inc., Newton, Mass.

Continuation-in-part of Ser. No. 104,157, Dec. 17, 1979, abandoned. This application Feb. 25, 1980, Ser. No. 124,568 Int. Cl.³ H01M 10/44

U.S. Cl. 429—50 12 Claims

1. An electrochemical cell which exhibits a general step change in output voltage at a predetermined discharge level from a first substantially constant voltage to a second substantially constant voltage, and comprising:


- an alkali metal anode;
 - an electrolyte including an oxyhalide cathode depolarizer together with a Lewis acid and a Lewis base and;
 - a cathode structure of catalytic material suitable for providing oxyhalide-reducing sites,
- the quantity of electrolyte being proportioned relative to the remaining electrochemically active cell components so as to be the first exhausted.

4,293,623 ELECTROLYTES FOR ALKALI-METAL ELECTROCHEMICAL DEVICES

Lawrence P. Klemann, Somerville; Gerald H. Newman, Westfield; Eugene L. Stogryn, Edison; Thomas A. Whitney, Roselle, and Dan Farcasiu, Princeton, all of N.J., assignors to Exxon Research & Engineering Co., Florham Park, N.J.

Filed Jul. 3, 1980, Ser. No. 165,412
Int. Cl.³ H01M 6/16

U.S. Cl. 429—194 20 Claims



(MATERIAL UTILIZATION (T_{1/2}, %) vs. DISCHARGE CYCLE NUMBER FOR A Li-TiS₂ CELL OPERATING WITH A 1.6 mM/L SOLVENT, U₁(C₂H₅)₂IN DMF/DMC: 54/46)

1. An electrolyte for an alkali-metal electrochemical device, comprising:

- (a) an organic solvent selected from a group consisting of ethers, esters, sulfones, organic sulfites, organic sulfates, organic nitrites and organic nitro compounds; and
- (b) at least one electrolytically active alkali-metal complex anion salt having the formula:



wherein Z is an alkali metal;
wherein M is an element selected from a group consisting of B, Al, Ga, In, Tl, P, As, Zn, Cd and Sn (stannous);

wherein Q represents at least one heteroatom grouping bonded to M, the core element, through a carbon-M bond; wherein R is selected from the group consisting of: heteroatom-containing groups bonded to M, the core element, through the heteroatom site, alkyls, aryls, alkaryl, aralkyls, halogens, halogen substituted aryls, halogen substituted alkaryl, and pseudohalides; and wherein x and y are positive integers, a sum of x plus y being equal to one plus the valence of the core element M, and further, wherein x can be zero.


4,293,624

METHOD FOR MAKING A MASK USEFUL IN X-RAY LITHOGRAPHY

William D. Buckley, Easton, Conn., assignor to The Perkin-Elmer Corporation, Norwalk, Conn.

Filed Jun. 26, 1979, Ser. No. 52,292
Int. Cl.³ H05G 1/00; G21F 1/12

U.S. Cl. 430—5 12 Claims



1. A method of making a lithography mask comprising:
 - (a) depositing on a substrate which is transparent to the radiation to be used in the lithography process a thin layer of a material which is reflective to ultraviolet radiation;
 - (b) covering said reflective layer with a layer of photoresist;
 - (c) exposing the photoresist with UV radiation through a master mask to thereby expose areas at which radiation absorbers are to be located;
 - (d) developing the photoresist to expose the reflective layer in said areas;
 - (e) etching the reflective layer away to expose the substrate and to provide an undercut;
 - (f) depositing a layer of a material which is opaque to the radiation with which the mask is to be used on the substrate; and
 - (g) lifting off the resist and unwanted portions of said opaque material.

4,293,625

ANCHOR LAYER IN PHOTOLITHOGRAPHIC RECEPTOR BASE CONTAINS OXIDE SURFACE TREATED TITANIUM DIOXIDE

Joseph F. Myers, Lake Elmo, Minn., assignor to Minnesota Mining and Manufacturing Company, Saint Paul, Minn.

Continuation of Ser. No. 782,174, Mar. 28, 1977, abandoned. This application Oct. 15, 1980, Ser. No. 197,198

Int. Cl.³ G03C 1/04

U.S. Cl. 430—9 15 Claims

1. A hydrophilic-surfaced photolithographic receptor sheet comprising a support having an anchor layer thereon, said anchor layer comprising a dispersion of rutile crystalline titanium dioxide in a binder resin, said titanium dioxide having an oxide surface treatment of at least about 10 percent by weight, said oxide surface treatment comprising the oxides of silica and alumina, the major proportion thereof being the oxide of silica, and overlying said anchor layer a hydrophilic layer comprising hydrophilic colloidal silica, said hydrophilic layer having a coating weight of from about 200 to about 500 milligrams per square foot.

6. A light-sensitive photolithographic printing plate capable of being imaged by the silver salt diffusion transfer process comprising a support having an anchor layer thereon, said

anchor layer comprising a dispersion of rutile crystalline titanium dioxide in a binder resin, said titanium dioxide having an oxide surface treatment of at least about 10 percent by weight, said oxide surface treatment comprising the oxides of silica and alumina, the major proportion thereof being the oxide of silica, and overlying said anchor layer a hydrophilic layer comprising hydrophilic colloidal silica, and overlying said hydrophilic layer a light-sensitive layer, comprising a silver halide emulsion.

4,293,626

ELECTROPHOTOSENSITIVE MATERIALS FOR MIGRATION IMAGING PROCESSES


Frank G. Webster, Rochester; Michael T. Regan, Fairport, and Louis J. Rossi, Rochester, all of N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.

Division of Ser. No. 12,172, Dec. 14, 1979, Pat. No. 4,272,595, which is a continuation-in-part of Ser. No. 899,186, Apr. 24, 1978, abandoned, which is a continuation-in-part of Ser. No. 818,697, Jul. 25, 1977, abandoned. This application Oct. 31, 1980, Ser. No. 202,406

Int. Cl.³ G03G 5/06, 17/04

U.S. Cl. 430—17 5 Claims

1. An electrophoretic migration image comprising a material having the structure:



wherein:

M and N may be zero, one or two;
L¹, L², L³, L⁴, L⁵, L⁶ and L⁷ may be cyano, hydrogen, substituted or unsubstituted alkyl, alkoxy, aralkyl, aryl or heterocycyl and in addition any two of L¹, L² and L³ and any two of L⁴, L⁵, L⁶ and L⁷ may together represent the elements needed to complete a carbocyclic or heterocyclic ring having from 5-12 carbon atoms;

A¹ may be the same as A² and in addition may represent an aryl or diarylamino aryl substituted, or unsubstituted aryl group or a substituted or unsubstituted heterocyclic nucleus such as thiophene, benzo[b]thiophene, naphtho[2,3-b]thiophene, furan, isobenzofuran, chromene, pyran, xanthene, pyrrole, 2H-pyrrole, pyrazole, indolizine, indole, indazole, carbazole, pyrimidine, isothiazole, isoxazole, furazan, chroman, isochroman, 1,2,3,4-tetrahydroquinoline, 1,2-dihydro-4H-pyrrolo[3,2,1-ij]quinoline; 4H-pyrrolo[3,2,1-ij]quinoline; 1,2,5,6-tetrahydro-4H-pyrrolo[3,2,1-ij]quinoline; 1H,5H-benzo[ij]quinolizine; 2,3-dihydro-1H,5H-benzo[ij]quinolizine; 2,3-dihydro-1H,5H-benzo[ij]quinolizine and 2,3,6,7-tetrahydro-1H,5H-benzo[ij]quinolizine; 10,11-dihydro-9H-benzo[a]xanthene-8-yl; 6,7-dihydro-5H-benzo[b]pyran-7-yl and pyrrolo[2,1-b]-benzothiazole;

A² represents a basic substituted or unsubstituted heterocyclic nucleus selected from the group consisting of substituted or unsubstituted imidazole, thiazole, benzothiazole, naphthothiazole, thianaphtheno-7',6',4,5-thiazole, oxazole, benzoxazole, naphthoxazole, benzoselenazole, naphthoselenazole, thiazoline, 2-quinoline, 4-quinoline, 1-isoquinoline, benzimidazole, 2-pyridine, 4-pyridine, pyrrolo[1,2-a]pyridine, 3H-indole, tetrazole, and acenaphthothiazole; and

B¹ and B² represent cyano, cyanoaryl, carboxy, alkoxycarbonyl, aryloxycarbonyl, alkylsulfonyl, acyl, arylsulfonyl, benzofuroyl, nitro, nitro-substituted aryl, sulfonyl, fluoro-sulfonyl, trifluoromethylsulfonyl, carbamoyl, arylcarbamoyl, and alkylcarbamoyl, or B² may be combined with $-\text{CL}^4-\text{CL}^5-$ or $-\text{CL}^6-\text{CL}^7-$

to provide sufficient atoms to form a substituted pyridine nucleus.

4,293,627

PROCESS OF DEVELOPING MAGNETIC IMAGES AND DRY MAGNETIC TONER COMPOSITIONS

Cornelius B. Murphy, and Donald S. Sypula, both of Fairport, N.Y., assignors to Xerox Corporation, Stamford, Conn.

Filed Apr. 30, 1980, Ser. No. 145,171

Int. Cl.³ G03G 9/08

U.S. Cl. 430—39 3 Claims

1. A process for causing the development of magnetic images which comprises forming a magnetic image on an imaging member, contacting the image with a dry magnetic toner composition consisting of from about 25 percent to about 50 percent by weight of a resin of a polymeric esterification product of 1,4-benzene dicarboxylic acid polymerized with 1,2,4-benzene tricarboxylic acid-cyclic, 1,2-anhydride and 2,2-dimethyl-1,3-propane diol, and from about 50 percent to about 75 percent by weight of a magnetic material selected from magnetites, metals, metal oxides, ferrites, and alloy materials, followed by transferring the developed image to a suitable substrate and permanently affixing the image thereon at a fusing temperature which ranges from about 300° F. to about 390° F., and at a fusing speed of from about 20 inches per second to about 50 inches per second.

4,293,628

ELECTROPHOTOGRAPHIC ELEMENTS CONTAINING DISAZO COMPOUNDS


Mitsuru Hashimoto, Hino; Masafumi Ohta; Akio Kozima, both of Yokohama; Kiyoshi Sakai, Tokyo, and Masaomi Sasaki, Kawasaki, all of Japan, assignors to Ricoh Co., Ltd., Tokyo, Japan

Filed Jan. 26, 1978, Ser. No. 872,679


Claims priority, application Japan, Jan. 31, 1977, 52/8740; Jan. 31, 1977, 52/8471

Int. Cl.³ G03G 5/06


U.S. Cl. 430—58 24 Claims



1. An electrophotographic material which comprises an electrically conductive support and a photosensitive layer formed thereon, said photosensitive layer consisting of fine particles of a disazo pigment having the formula



wherein R' is a member selected from the group consisting of hydrogen, ethyl, chloroethyl and hydroxyethyl, A' is a member selected from the group consisting of



wherein



is a fused ring selected from the group consisting of benzene ring, bromobenzene ring, naphthalene ring, indole ring, carbazole ring and benzofuran ring; Ar₁ is a member selected from the group consisting of phenyl, methylphenyl, methoxyphenyl, chlorophenyl, nitrophenyl, ethoxyphenyl, methylchlorophenyl, dimethylphenyl, methoxychlorophenyl, methoxybromophenyl, methoxymethylphenyl, dimethoxyphenyl, dimethoxychlorophenyl, dimethylaminophenyl, cyanophenyl, carboxyphenyl, benzenesulfonic acid sodium salt, tert-butoxyphenyl, naphthyl, methoxydibenzofuryl and carbazolyl; each of Ar₂ and Ar₃ is a member selected from the group consisting of phenyl, naphthyl, methoxyphenyl, methylphenyl, acetylaminophenyl, dimethylaminophenyl, cyanophenyl, nitrophenyl, dinitrophenyl, chlorophenyl, trichlorobenzenesulfonic acid, benzenesulfonic acid and benzenesulfonamide; each of R₁ and R₃ is a member selected from the group consisting of hydrogen, methyl, ethyl, phenyl and chlorophenyl; and R₂ is a member selected from the group consisting of methyl, carboxyl and —COOC₂H₅; and a resinous binder.

4,293,629

ELECTROSTATIC MASTER AND METHOD FOR MAKING THE SAME

Michael J. Shaw, Paw Paw, and Robert J. Thiessen, Richland, both of Mich., assignors to Allied Paper Incorporated, Kalamazoo, Mich.

Continuation-in-part of Ser. No. 930,329, Aug. 2, 1978, abandoned, which is a division of Ser. No. 827,127, Aug. 24, 1977, abandoned. This application Oct. 12, 1979, Ser. No. 84,409 Int. Cl.³ G03F 7/02; B41M 5/00; B41N 1/00

U.S. Cl. 430—64

21 Claims

1. An electrostatic master having improved water resistance for lithographic printing comprising
a base;
a barrier coat; and
a photoconductive layer containing a photoconductive material and a binder;

said barrier coat comprising a binding amount of a natural or synthetic binder and a filler at least a portion of which is an amount of plastic polymeric particles sensitive to the solvent used in the application of the photoconductive layer, said plastic polymeric particles being in an at least partially coalesced state in said barrier coat.

4,293,630

ELECTROPHOTOGRAPHIC PHOTOSENSITIVE MEMBER

Kozo Oka, Ebina, Japan, assignor to Rank Xerox Limited, London, England

Filed Apr. 21, 1980, Ser. No. 142,199

Claims priority, application Japan, May 29, 1979, 54-65672


Int. Cl.³ G03G 5/14

U.S. Cl. 430—59


2 Claims

1. An electrophotographic photosensitive body comprising a conductive support having provided thereon, in sequence, a photoconductive layer and a protective layer, said protective layer containing in a binder resin an aromatic amine compound

wherein said compound is of the following general formula (I) or (II) an organic halogen compound capable of producing a free halogen atom:



(I)



(II)

wherein X₁, X₂, Y₁, and Y₂ each is an alkyl group or a substituted or unsubstituted aryl group, R₁ and R₂ each is a hydrogen atom, an alkyl group containing 1-6 carbon atoms, or a halogen atom, and —(A)— represents a member selected from the group consisting of Members (III)-(IX) wherein

is (III)

is (IV)

is (V)

is (VI)

is (VII)

is (VIII)

is (IX)

is (X)

is (XI)

is (XII)

is (XIII)

is (XIV)

is (XV)

is (XVI)

is (XVII)

is (XVIII)

is (XIX)

is (XX)

is (XXI)

is (XXII)

is (XXIII)

is (XXIV)

is (XXV)

is (XXVI)

is (XXVII)

is (XXVIII)

is (XXIX)

is (XXX)

is (XXXI)

is (XXXII)

is (XXXIII)

is (XXXIV)

is (XXXV)

is (XXXVI)

is (XXXVII)

is (XXXVIII)

is (XXXIX)

is (XXXX)

is (XXXXI)

is (XXXXII)

is (XXXXIII)

is (XXXXIV)

is (XXXXV)

is (XXXXVI)

is (XXXXVII)

is (XXXXVIII)

is (XXXXIX)

is (XXXXX)

is (XXXXXI)


is (XXXXXII)

is (XXXXXIII)

is (XXXXXIV)

is (XXXXXV)

wherein R₄ represents an alkyl group containing 1-6 carbon atoms and



(IX)

4,293,631

ELECTROGRAPHIC TONER COMPOSITIONS

Chin H. Lu, Webster, N.Y., assignor to Xerox Corporation, Stamford, Conn.

Filed Mar. 12, 1979, Ser. No. 19,694

Int. Cl.³ G03G 9/10

U.S. Cl. 430—106

1 Claim

1. A developer composition comprised of a resin component, a carrier component, a colorant, and a charge inducing material wherein the resin is selected from the group consisting of a styrene/n-butyl methacrylate copolymer, and polystyrene, the carrier is selected from polyvinylidene fluoride coated Hoeganaes steel carrier, and vinyl fluoride resin coated steel carrier materials, the colorant is carbon black and the charge inducing material is stearamidopropyl dimethyl beta-hydroxyethyl ammonium dihydrogen phosphate, or stearamidopropyl dimethyl beta-hydroxyethyl ammonium nitrate, said charge inducing material being present in an amount of from 0.1 percent to 10 percent based on the weight of toner, wherein the toner is charged positively and the carrier is charged negatively.

4,293,632

ATTRITION PROCESS FOR ALTERATION OF TONER PARTICLES CONTAINING CONDUCTIVE MATERIALS



Charles G. Dickerson, Farmington, and Peter F. Erhardt, Webster, both of N.Y., assignors to Xerox Corporation, Stamford, Conn.

Filed Apr. 3, 1978, Ser. No. 892,717

Int. Cl.³ G03G 9/08

U.S. Cl. 430—137

5 Claims



1. A process for lowering the minimum fuse temperature of

a toner material containing a resin and a conductive coating by subjecting the toner material to a minor amount of attrition, thereby causing the removal of small amounts of the toner conductive coating material, thus exposing the inner portions of the toner particles and rendering such particles less conductive whereby the altered particles have a minimum fuse temperature greater than 10° F. below the fuse temperature of unaltered particles.

4,293,633

REFLEX COPYING PROCESS ONTO LIGHT-SENSITIVE RECORDING MATERIALS

Roy F. Hufey, Manningtree, and John A. Pope, Colchester, both of England, assignors to Bexford Limited, London, England

Filed Nov. 23, 1979, Ser. No. 96,648

Claims priority, application United Kingdom, Dec. 11, 1978, 47952/78

Int. Cl.³ G03C 5/10, 5/20

U.S. Cl. 430—152

7 Claims

1. A copying process for recording an image of an original material upon a light-sensitive vesicular imaging material by reflex exposure to imaging light, the light-sensitive vesicular imaging material having an imaging layer comprising a polymeric vehicle which is softenable upon heating above ambient temperature to permit the formation of a recorded image in the form of light-scattering or reflecting gas vesicles in those areas struck by imaging light, said process comprising the steps of:

selecting a screen;
interposing the screen between the source of imaging light and the light-sensitive vesicular imaging material, the screen transmitting the light incident from the source of imaging light in separate bundles of light rays;
reflex imaging the light-sensitive vesicular imaging material by means of the bundles of light rays transmitted through the light-sensitive vesicular imaging material and reflected from the original material and;
softening the polymeric vehicle of the light-sensitive vesicular imaging material by heating said vesicular imaging material to record an image of the original material in the form of gas vesicles in the imaging layer.

4,293,634

METHOD OF RECORDING IMAGES ON A RADIATION SENSITIVE MATERIAL

Yakov A. Monosov, prospekt Vernadskogo, 99, korpus 1, kv. 204, Moscow, U.S.S.R.

Continuation of Ser. No. 916,363, Jun. 16, 1978, abandoned.

This application Apr. 10, 1980, Ser. No. 139,139


Claims priority, application U.S.S.R., Nov. 25, 1977, 2543210;

Dec. 21, 1977, 2555201; Dec. 22, 1977, 2553262

Int. Cl.³ G03C 5/24

U.S. Cl. 430—269

17 Claims




1. A method of recording images of a radiation sensitive material comprising the steps of:


forming a layer of radiation sensitive material comprised of a heterogeneous mixture of substances, at least one of said substances being used as a binder and being capable of converting its states of aggregation in the mixture of the type of crystal-liquid or crystal-gas under the action of intrinsic or reflected radiation obtainable from the object

developing agent for silver halide after exposure, said material containing an interlayer to prevent color mixing positioned between said emulsion layers, wherein the improvement comprises


an interlayer containing gelatin and a complex which is formed by dissolving a mixture of hydroquinone derivatives having a solidifying point of 100° C. or less in a low boiling point solvent, which are different from the developing agent for silver halide used in the treatment of the material and which do not substantially develop silver halide and a homopolymer or copolymer containing a recurring unit represented by formula (I):




wherein R₁ represents a hydrogen atom or a methyl group; Q represents a chemical bond, —COOR₂— or —CONHR₂—; A represents a chemical bond or an oxygen atom; B represents a chemical bond or




D represents —CH=CH₂— or —(CH₂)_n— wherein n represents an integer of 3 to 5 when A and B are both chemical bonds, an integer of 2 or 3 when A is an oxygen atom and B is a chemical bond, or an integer of 2 to 4 when A is a chemical bond and B is



or D represents



when A is a chemical bond and B is



and R₂ represents a substituted or unsubstituted divalent hydrocarbon group having 2 to 8 carbon atoms.

4,293,642

IN PHOTOGRAPHIC EMULSION ADHESION TO A POLYESTER FILM BASE

Elton L. Beavan, Binghamton, N.Y., and E. Bradley Moynahan, Saratoga, Calif., assignors to GAF Corporation, New York, N.Y.

Filed May 13, 1980, Ser. No. 149,355

Int. Cl.³ G03C 1/78

U.S. Cl. 430—534

8 Claims

1. A photographic film element comprising a gelatin-con-

taining silver halide emulsion chemically cross-linked to a hydrophobic film base substrate having active functional group sites which are cross-linked with the amino groups of the gelatin by a carbodiimide cross-linking agent.

4,293,643

ROTARY SHAKING CULTURE MEASURING METHOD AND APPARATUS

Yukio Ohtake, and Masahiro Nakamura, both of Tokyo, Japan, assignors to Ohtake Works Company, Ltd., Tokyo, Japan


Filed Jan. 28, 1980, Ser. No. 116,184

Claims priority, application Japan, Jan. 31, 1979, 54-9174

Int. Cl.³ C12Q 1/06

U.S. Cl. 435—39

12 Claims



1. A rotary shaking culture measuring apparatus comprising a rotatable turntable means rotatable about an axis which is disposed at an acute angle relative to vertical, said turntable means comprising a turntable element rotatable in a plane generally perpendicular to said axis, a plurality of radially spaced culture means carried on said turntable means, said culture means each being generally L-shaped and each having an upright portion joined to a lateral portion, said upright portion being disposed generally parallel to said axis and said lateral portion being generally parallel to said turntable element such that upon rotation of said turntable means, said culture means is stirred by the resultant force of gravity and centrifugal force, retaining means retaining said culture means on said turntable means, said turntable element having a plurality of concentration detection openings, a concentration measuring device disposed adjacent to said turntable means comprising a light source and a light detector device operable in association with said concentration detection openings to provide a concentration signal indicative of the concentration in said culture means, and a synchronizing device disposed adjacent to said turntable means operable to detect passage of said culture means past a predetermined position and thereby provide a synchronization signal for synchronizing the measuring of said concentration by said concentration measuring device as said culture means pass successively by said concentration measuring device.

4,293,644

PROCESS FOR PREPARING ANDROST-4-ENE-3,17-DIONE

Merle G. Wovcha, and Candice B. Biggs, both of Kalamazoo, Mich., assignors to The Upjohn Company, Kalamazoo, Mich.

Continuation-in-part of Ser. No. 735,075, Oct. 22, 1976,

abandoned. This application Oct. 9, 1977, Ser. No. 849,525

Int. Cl.³ C12P 33/16

U.S. Cl. 435—55

8 Claims

8. A process for preparing androst-4-ene-3,17-dione which comprises cultivating a mutant microorganism of *Mycobacterium fortuitum*, said mutant being characterized by its ability to selectively degrade steroids having 17-alkyl side chains of from 2 to 10 carbon atoms, inclusive, and accumulate androst-4-ene-3,17-dione in the fermentation beer, in an aqueous nutrient medium under aerobic conditions in the presence of a steroid

containing from 2 to 10 carbon atoms, inclusive, in the 17-alkyl side chain, and recovering the produced androst-4-ene-3,17-dione.

4,293,645

PROCESS FOR PREPARING ANDROSTA-1,4-DIENE-3,17-DIONE AND ANDROST-4-ENE-3,17-DIONE

Merle G. Wovcha; Candice B. Biggs, both of Kalamazoo, and Thomas R. Pyke, Portage, all of Mich., assignors to The Upjohn Company, Kalamazoo, Mich.

Continuation-in-part of Ser. No. 662,563, Mar. 1, 1976. This

application Nov. 9, 1977, Ser. No. 849,526

Int. Cl.³ C12P 33/16

U.S. Cl. 435—55

8 Claims

8. A process for preparing a mixture of androsta-1,4-diene-3,17-dione and androst-4-ene-3,17-dione which comprises cultivating a mutant microorganism of *Mycobacterium fortuitum*, said mutant being characterized by its ability to selectively degrade steroids having 17-alkyl side chains of from 2 to 10 carbon atoms, inclusive, and accumulate androsta-1,4-diene-3,17-dione and androst-4-ene-3,17-dione in the fermentation beer, in an aqueous nutrient medium under aerobic conditions in the presence of a steroid containing from 2 to 10 carbon atoms, inclusive, in the 17-alkyl side chain, and recovering the produced androsta-1,4-diene-3,17-dione and androst-4-ene-3,17-dione.

4,293,646

COMPOSITION OF MATTER AND PROCESS

Merle G. Wovcha, and Kevin E. Brooks, both of Kalamazoo, Mich., assignors to The Upjohn Company, Kalamazoo, Mich.

Filed Aug. 7, 1978, Ser. No. 931,741

Int. Cl.³ C12P 33/16

U.S. Cl. 435—55

7 Claims

1. A process for preparing androst-4-ene-3,17-dione which comprises cultivating *Mycobacterium fortuitum* NRRL B-11359 in an aqueous nutrient medium under aerobic conditions in the presence of a steroid containing from 2 to 10 carbon atoms, inclusive, in the 17-alkyl side chain, and recovering the produced androst-4-ene-3,17-dione.

4,293,647

METHOD OF DISSOLVING COLLAGEN-CONTAINING TISSUES

Rolf Monsheimer, Darmstadt-Eberstadt, and Ernst Pfeleiderer, Darmstadt-Arheilgen, both of Fed. Rep. of Germany, assignors to Röhm GmbH, Darmstadt, Fed. Rep. of Germany

Filed Feb. 28, 1978, Ser. No. 882,616

Claims priority, application Fed. Rep. of Germany, Mar. 2, 1977, 2709035

Int. Cl.³ C12P 21/06

U.S. Cl. 435—69

11 Claims

1. A method for dissolving collagen-containing tissue to form soluble decomposed products of low viscosity, which method consists essentially of enzymatically hydrolyzing said tissue by treatment with at least one acid protease at a pH within the acid region and in the presence of urea at a concentration between 0.01 mol/liter and 0.3 mol/liter.

4,293,648

PROCESS FOR ESTERIFICATION OF α-L-ASPARTYL-L-PHENYLALANINE

Arthur A. Davino, Skokie, Ill., assignor to G. D. Searle & Co., Skokie, Ill.

Continuation-in-part of Ser. No. 102,807, Dec. 12, 1979, abandoned, which is a continuation-in-part of Ser. No. 27,196, Apr. 5, 1979, abandoned. This application Sep. 2, 1980, Ser. No.

183,556

Int. Cl.³ C12P 21/02

U.S. Cl. 435—70

12 Claims

1. A process for esterifying α-L-aspartyl-L-phenylalanine

which comprises contacting α-L-aspartyl-L-phenylalanine with an alcohol in the presence of an effective amount of a proteolytic enzyme with specific esterase activity in an aqueous alcohol medium at a pH of 4 to 7 in which the alcohol concentration is sufficient to reverse the hydrolytic activity of the protease.

4,293,649

PROCESS FOR PRODUCTION OF ANTIBIOTIC A-33853

Marvin M. Hoehn, and Karl H. Michel, both of Indianapolis, Ind., assignors to Eli Lilly and Company, Indianapolis, Ind.


Filed Feb. 21, 1980, Ser. No. 123,330

Int. Cl.³ C12P 17/16

U.S. Cl. 435—118

2 Claims

1. The method of producing the A-33853 antibiotic having the structure



which comprises cultivating *Streptomyces* sp. NRRL 12068, or an A-33853-producing variant or mutant thereof, in a culture medium containing assimilable sources of carbon, nitrogen, and inorganic salts under submerged aerobic fermentation conditions until said antibiotic in the culture medium is produced.

4,293,650

ANTI-COCCIDIAL SUBSTANCE AND ITS PREPARATION

Jean Florent, Hauts de Seine; Jean Lunel, Paris, and Denise Mancy, Charenton, all of France, assignors to Rhone-Poulenc Industries, France

Filed Oct. 5, 1978, Ser. No. 948,786


Claims priority, application France, Oct. 7, 1977, 77 30236

Int. Cl.³ C12P 17/18; C12N 1/20; C12R 1/465

U.S. Cl. 435—119

10 Claims

1. A process for the preparation of the anticoccidial substance hereinbefore designated 37,454 RP of the formula:



which, in the form of its sodium salt, has the following properties: it is a white crystalline powder which is soluble in methylene

chloride and chloroform, methanol, dimethyl formamide, acetone and ethyl acetate, sparingly soluble in hexane and virtually insoluble in water;

it has the following approximate elementary composition; C% 59.27, H% 8.45, O% 28.32 and Na% 2.36; which is compatible with the empirical formula $C_{48}H_{81}O_{18}Na$; its melting point (determined in a capillary tube) is $198^{\circ}\text{--}199.5^{\circ}\text{C}$;

its optical rotation (determined in methanolic solution at a concentration of 0.974%) is approximately: $[\alpha]_D^{20} = +2.3 \pm 0.6^{\circ}$; $[\alpha]_{436}^{20} = +1.3 \pm 0.6^{\circ}$;

it does not exhibit a characteristic absorption in its ultraviolet spectrum;

it exhibits the following characteristic absorption bands in its infra-red spectrum (determined on tablets of a mixture with potassium bromide): 3,560 (shoulder), 3,420 (strong) (H_2O), 3,300 (medium), 3,260 (shoulder), 3,000 (shoulder), 2,980 (strong), 2,955 (shoulder), 2,940 (medium), 2,915 (medium), 2,898 (shoulder), 2,865 (shoulder), 2,860 (shoulder), 2,838 (medium), 2,660 (very weak), 2,360 (very weak) (CO_2), 2,080 (very weak), 1,718 (very weak), 1,620 (strong), 1,460 (strong), 1,450 (shoulder), 1,438 (shoulder), 1,428 (shoulder), 1,410 (shoulder), 1,405 (medium), 1,375 (medium), 1,362 (strong), 1,345 (shoulder), 1,335 (shoulder), 1,320 (shoulder), 1,310 (medium), 1,300 (shoulder), 1,288 (medium), 1,262 (very weak), 1,245 (medium), 1,230 (medium), 1,215 (shoulder), 1,200 (shoulder), 1,188 (strong), 1,162 (strong), 1,140 (shoulder), 1,130 (shoulder), 1,120 (strong), 1,105 (very strong), 1,098 (shoulder), 1,082 (strong), 1,070 (very strong), 1,060 (shoulder), 1,052 (strong), 1,045 (shoulder), 1,040 (shoulder), 1,035 (shoulder), 1,020 (strong), 1,010 (shoulder), 995 (medium), 985 (strong), 970 (shoulder), 955 (strong), 950 (medium), 945 (shoulder), 915 (medium), 900 (medium), 895 (shoulder), 880 (weak), 860 (weak), 858 (shoulder), 830 (very weak), 808 (weak), 780 (weak), 720 (shoulder), 710 (medium), 690 (shoulder), 665 (weak), 660 (shoulder), 630 (medium), 615 (weak), 580 (weak), 550 (shoulder), 540 (medium), 525 (very weak), 518 (very weak), 500 (medium), 470 (shoulder), 452 (weak), 412 (weak), 400 (shoulder), and 340 (medium) cm^{-1} ;

it has a proton nuclear magnetic resonance spectrum which shows that it contains 5 methoxy groups;

it has a ^{13}C nuclear magnetic resonance spectrum which shows that it contains 48 carbon atoms;

it has a field desorption mass spectrum which shows a molecular peak corresponding to a mass of 968; and it has an Rf of 0.75 in ascending thin layer chromatography on silica gel, using as eluent a mixture of methylene chloride and methanol (94:6 by volume); or a non-toxic salt of 37,454 RP with a metal or a nitrogen-containing base which process comprises cultivating *Streptomyces gypseus* DS 27,461 (NRRL 11,168) or a productive mutant thereof, aerobically in a culture medium containing assimilable sources of carbon, nitrogen, and inorganic substances, and isolating the 37,354 RP formed during the culture as such or as a non-toxic salt thereof.

10. A biologically pure culture of the microorganism *Streptomyces gypseus* DS 27,461 having the identifying characteristics of NRRL 11,168, said culture being capable of producing the antibiotic 37,454 RP in a recoverable quantity upon fermentation in an aqueous nutrient medium containing assimilable sources of carbon, nitrogen and inorganic substances.

4,293,651

PROCESS FOR PRODUCING ANTIBIOTIC USING SACCHAROPOLYSPORA

Howard A. Whaley, Portage, and John H. Coats, Kalamazoo, Mich., assignors to The Upjohn Company, Kalamazoo, Mich.

Filed Oct. 2, 1979, Ser. No. 81,211

Int. Cl.³ C12P 1/06

U.S. Cl. 435—169

2 Claims

1. A process for preparing antibiotic U-59,760, which com-

prises cultivating *Saccharopolyspora hirsuta* strain 367, having the identifying characteristic of NRRL 12045, in an aqueous nutrient medium under aerobic conditions until substantial antibiotic U-59,760 activity is imparted to said medium and separating antibiotic U-59,760 from said medium.

4,293,652

METHOD FOR SYNTHESIZING DNA SEQUENTIALLY

Stanley N. Cohen, Portola Valley, Calif., assignor to Cetus Corporation, Berkeley, Calif.

Filed May 25, 1979, Ser. No. 42,403

Int. Cl.³ C12N 15/00

U.S. Cl. 435—172

4 Claims

1. A method for producing a cloning vector containing a synthesized gene of a predetermined composition and length, comprising, preparing or selecting a cloning vector having a single restriction enzyme recognition sequence for a restriction enzyme of the type which cuts at a site outside said recognition sequence, chemically synthesizing a fragment of double-stranded DNA corresponding to a preselected portion of said gene, inserting said fragment in said cloning vector, respectively, at the site cut by the restriction enzyme recognized by said restriction enzyme recognition sequence, placing said cloning vector in an appropriate host and providing growth conditions for said host to amplify and purify said inserted fragment, and repeating the foregoing said synthesis, insertion, and amplification steps for preselected portions of said gene immediately adjacent the previously cloned fragment until a gene is complete.

4,293,653

METHOD FOR PROPAGATING FELINE INFECTIOUS PERITONITIS VIRUS

Marian C. Horzinek, Kramsvogellaan 128, Bilthoven, and Albertus D. M. E. Osterhaus, Dr. Breveestraat 16, Bunnik, both of Netherlands

Filed Apr. 12, 1979, Ser. No. 29,591

Int. Cl.³ C12N 7/08

U.S. Cl. 435—237

5 Claims

1. A process for propagating feline infectious peritonitis virus which comprises the steps of:

- (a) inoculating suckling rodents intracerebrally with infectious cat material;
- (b) replicating the virus in the brain of said inoculated rodents;
- (c) harvesting FIP virus containing brain material from said inoculated rodents; and
- (d) optionally inoculating rodents, with the so obtained virus containing brain material for further passages.

4,293,654

CELL CULTURE MICROCARRIERS

David W. Levine, Somerville; William G. Thilly, Cambridge; Daniel I. C. Wang, Belmont, all of Mass., and Jason S. Wong, Toledo, Ohio, assignors to Massachusetts Institute of Technology, Cambridge, Mass.

Division of Ser. No. 842,696, Oct. 17, 1977, Pat. No. 4,189,534, which is a continuation-in-part of Ser. No. 740,993, Nov. 11, 1976, abandoned. This application Jul. 2, 1979, Ser. No. 54,319

Int. Cl.³ C12N 5/02; C08B 37/00

U.S. Cl. 435—241

9 Claims

1. Cell culture microcarriers having a degree of substitution thereon with positively-charged chemical moieties sufficient to provide a charge capacity of from about 0.1 to about 4.5 meq/gram of dry, untreated microcarriers.

7. A method of producing cell culture microcarriers comprising soaking crosslinked dextran beads in an aqueous solution of a tertiary or quaternary amine and a base until said beads are substituted with a sufficient amount of amine moieties to produce an exchange capacity thereon of from about 0.1 to about 4.5 meq/gram of dry dextran.

4,293,655

APPARATUS FOR ENSILAGING AND FERMENTING

Charles Christ, 65 rue de Paris, 72160 Connerre, France; Jean-Michel LeBeault, Villiers/Coudun, and Claude Noël, Compiègne, both of France, assignors to Charles Christ, Connerre, France

Division of Ser. No. 825,487, Aug. 17, 1977, Pat. No. 4,242,361.


This application Jul. 2, 1979, Ser. No. 53,801

Claims priority, application France, Oct. 14, 1976, 76 30874

Int. Cl.³ C12M 1/02

U.S. Cl. 435—316

10 Claims



1. In a device for manufacturing and ensilaging sauerkraut, comprising a closable container adapted to be stored on a pallet and to receive through an upper open end of the container cabbage material to be fermented, and a flexible cover member of tightly sealing said open end of the container, the improvement comprising rehydration means for adding rehydration liquid to said cabbage material in the container, said rehydration means comprising recycling means connected to the bottom and to the upper section of said container for removing juice from the bottom of the container and recirculating said juice by introducing the removed juice into said upper section of said container, said rehydration means further comprising feeding means adapted to admit a controlled amount of a fresh rehydrating liquid with the recirculated juice prior to introducing said juice into said upper container section.

4,293,656

FLAME RETARDANT POLYSTYRENE

Klaus Hahn, Lampertheim; Herbert Naarmann, Wattenheim, and Klaus Penzien, Frankenthal, all of Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Ludwigshafen, Fed. Rep. of Germany

Filed Nov. 28, 1980, Ser. No. 211,378

Claims priority, application Fed. Rep. of Germany, Dec. 13, 1979, 2950098

Int. Cl.³ C08J 9/18; C08K 5/06

U.S. Cl. 521—88

3 Claims

1. A thermoplastic molding material comprising polystyrene containing a halogen-containing organic flame retardant other than 2,2-bis(4-allyloxy-3,5-dibromophenyl)-propane and 2,2-bis(4-allyloxy-3,5-dibromophenyl)-propane, which is a synergist, present in the molding material in an amount between 0.01 percent by weight and 1.0 percent by weight based on the weight of the polystyrene.

4,293,657

STABLE MELAMINE POLYOL DISPERSIONS, A PROCESS FOR THEIR MANUFACTURE AND FOR THE PREPARATION OF FOAMED POLYURETHANE PLASTICS

Dietmar Nissen, Heidelberg; Matthias Marx, Bad Duerkheim; Wolfgang Jarre, Ludwigshafen; Ernst Schoen, Neustadt, and Walter Decker, Ludwigshafen, all of Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Ludwigshafen, Fed. Rep. of Germany

Filed Jul. 7, 1980, Ser. No. 166,636

Claims priority, application Fed. Rep. of Germany, Aug. 9, 1979, 2932304

Int. Cl.³ C08G 18/14

U.S. Cl. 521—121

12 Claims

1. A stable melamine-polyol dispersion consisting of (A) 5 to 70 percent by weight of melamine based on the total weight of melamine and polyoxyalkylene polyether polyol with 90 percent of the melamine particles having a particle size of less than 10 microns, (B) 95 to 30 percent by weight of a polyoxyalkylene polyether polyol based on the weight of melamine and polyol, said polyoxyalkylene polyether polyol having a molecular weight of 200 to 16,000, and (C) an effective amount of a stabilizer selected from the group consisting of (a) silicic acids and silicates, (b) salts of perfluorinated alkyl carboxylic acids having 4 to 20 carbon atoms; salts of alkyl sulfonic acids and perfluorinated alkylsulfonic acids having 4 to 20 carbon atoms and polyperfluoroether polyols having molecular weights of 300 to 6000, and (c) salts of fatty alcohol sulfates having 6 to 30 carbon atoms.

4,293,658

PROCESS FOR RIGID FOAMS OF IMPROVED FRIABILITY

Daniel S. Raden, Hawthorn Woods, and Francis W. Arbir, Itasca, both of Ill., assignors to Abbott Laboratories, North Chicago, Ill.

Filed May 12, 1980, Ser. No. 148,634

Int. Cl.³ C08G 18/14, 18/18, 18/24, 18/32

U.S. Cl. 521—129

21 Claims

1. The process of making a rigid, cellular polyurethane with improved friability, comprising reacting a polyisocyanate with a polyol in the presence of a fully neutralized salt of a tertiary amine, a surfactant, a blowing agent, and at least a minor proportion of butyl benzyl phthalate, said polyol being prepared by reacting a phenol and formaldehyde under substantially anhydrous conditions with continuous removal of water, said polyol having a water content of no more than about 5% and having at least four phenyl groups per mole.

11. The process of making a rigid cellular polyurethane from one molar equivalent of a polyol which is prepared by reacting a phenol and formaldehyde under substantially anhydrous conditions with continuous removal of water and said polyol having a water content of no more than about 5% and having at least four phenyl groups per mole, and 0.95 to 1.25 molar equivalents of a polyisocyanate, in the presence of 0.001–0.05 molar equivalents of a fully neutralized tertiary amine salt, 0.5–5.0% of benzyl butyl phthalate, 0.5–4.0% of a surfactant and 0.4–40% of a blowing agent, said percentage figures being taken as a weight-by-weight amount based on said polyol.

4,293,659

COMPOSITION FOR COATING MOLDED ARTICLES

Glenn R. Svoboda, Grafton, Wis., assignor to Freeman Chemical Corporation, Port Washington, Wis.

Filed May 1, 1980, Ser. No. 145,799

Int. Cl.³ C08G 18/04, 18/42, 18/80

U.S. Cl. 525—28

1 Claim

1. A storage stable composition for the in-mold coating of a molded, fiber-reinforced thermoset plastic article comprising a resin system including

- (A) a blocked polyisocyanate which is the reaction product, essentially free of unreacted -NCO radicals, of ϵ -caprolactam and organic polyisocyanate;
 (B) a polyepoxide-polyacrylate which is the reaction product, essentially free of unreacted epoxy radicals of a polyepoxide and acrylic or methacrylic acid;
 (C) ethylenically unsaturated polyester resin;
 (D) copolymerizable alpha-beta ethylenically unsaturated monomer;

wherein the said ethylenically unsaturated polyester resin and the said copolymerizable alpha-beta ethylenically unsaturated monomer comprise more than 50 weight percent of the said resin system and the said blocked isocyanate is present in sufficient quantity that the ratio of NCO/OH radicals in the resin system after unblocking of the said blocked polyisocyanate is from 0.2 to 0.8;

said composition also including an initiator for addition polymerization; a catalyst for the reaction of -NCO radicals and -OH radicals; and fillers.

4,293,660

POLYPHENYLENE ETHER RESIN COMPOSITION
 Akitoshi Sugio, Ohmiya; Masanobu Masu, Tokyo, and Masatugu Matunaga, Matsudo, all of Japan, assignors to Mitsubishi Gas Chemical Co., Inc., Tokyo, Japan

Filed Apr. 16, 1980, Ser. No. 140,865

Claims priority, application Japan, Apr. 18, 1979, 54-47411
 Int. Cl.³ C08L 53/00; C09L 61/04

U.S. Cl. 525-68

7 Claims

1. A resin composition comprising
 (a) a polyphenylene ether resin, and
 (b) a grafted block copolymer of an unsaturated polyolefin and butyl rubber obtained by graft copolymerization in the presence of a bifunctional phenolic compound as a grafting vehicle.

4,293,661

LOW MOLECULAR WEIGHT ACRYLATE RESINS CONTAINING HYDROXYL AND TERTIARY AMINO GROUPS

Joachim Probst, Cologne; Michael Sonntag, Odenthal, and Günter Kolb, Leverkusen, all of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Fed. Rep. of Germany

Filed Dec. 31, 1979, Ser. No. 108,349

Claims priority, application Fed. Rep. of Germany, Jan. 9, 1979, 2900592

Int. Cl.³ C08F 8/08, 8/32; C08G 18/62


U.S. Cl. 525-127

1 Claim

1. A composition comprising a compound which contains or is capable of forming more than one isocyanate group and; as a crosslinking component a reaction product of an acrylate resin containing glycidyl groups and a secondary mono-amine containing hydroxyl groups, obtained by reaction of said acrylate resin of copolymerised, statistically distributed units of

- (A) 3 to 30% by weight of the glycidyl ester of acrylic acid or methacrylic acid or of vinyl glycidyl ether, or any mixture thereof;
 (B) 0 to 20% by weight of a hydroxyalkyl ester of acrylic acid or methacrylic acid containing from 2 to 4 carbon atoms in the hydroxyalkyl radical, or any mixture thereof;
 (C) 5 to 80% by weight of styrene, α -methyl styrene, o-chlorostyrene, p-chlorostyrene o-, m- or p-methyl styrene, p-tert-butyl styrene, methyl methacrylate, acrylonitrile or methacrylonitrile, or any mixture thereof;
 (D) 5 to 70% by weight of an acrylic acid ester containing from 1 to 12 carbon atoms in the alcohol radical or of a methacrylic acid ester containing from 2 to 12 carbon atoms in the alcohol radical, or any mixture thereof; and
 (E) 0 to 10% by weight of an α,β -mono-olefinically unsaturated monocarboxylic or dicarboxylic acid containing from 3 to 5 carbon atoms or of a maleic acid mono-ester

containing from 2 to 14 carbon atoms in the alcohol radical, or any mixture thereof, with at least one amine containing hydroxyl groups corresponding to the formula:




in which

n=1 to 4,

R=a single bond or an alkylene group containing from 1 to 4 carbon atoms,


R'=alkyl containing from 1 to 4 carbon atoms,

R''=alkyl containing from 1 to 4 carbon atoms or




or in which


R and R' together with



represent an alicyclic 5- or 6-membered ring



or R' and R'' together with



represent a pyrrolidine or piperidine ring, at a temperature of from 50° to 200° C. in such a ratio that one epoxide equivalent of the acrylate resin has been reacted with from 0.7 to 1 NH equivalent of the amine containing hydroxyl groups with the OH function remaining largely intact.

4,293,662

POLYAMIDES CONTAINING OXIDIZED POLYETHYLENE

Frieder Heydenreich, Ratingen; Helmut Korber, Odenthal; Peter Tacke, Krefeld; Friedrich Fahnler, Krefeld, and Dieter Neuray, Krefeld, all of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Fed. Rep. of Germany

Continuation-in-part of Ser. No. 971,386, Dec. 20, 1978, abandoned. This application Dec. 3, 1979, Ser. No. 99,844

Claims priority, application Fed. Rep. of Germany, Feb. 13, 1978, 2805892

Int. Cl.³ C08L 77/00

U.S. Cl. 525-184

6 Claims

1. A high-impact resistant polyamide moulding composition consisting of a mixture of

- (1) 70 to 99% by weight, based on the mixture as a whole, of at least one polyamide and
 (2) 1 to 30% by weight, based on the mixture as a whole, of oxidized polyethylene, the oxidized polyethylene having a number average molecular weight of from 15,000 to

25,000 and having been obtained by oxidising polyethylene in the melt with oxygen or an oxygen-containing gas, under intensive mixing and kneading under a pressure of from 1 to 150 bars, at a temperature in the range of from 100° to 300° C. and over a reaction time of at most 20 minutes.

4,293,663

FLUOROELASTOMER/POLYEPICHLOROHYDRIN ELASTOMER ARTICLES

David A. Stivers, St. Paul, Minn., assignor to Minnesota Mining and Manufacturing Company, St. Paul, Minn.

Filed Oct. 23, 1979, Ser. No. 87,501


Int. Cl.³ C08L 63/00, 27/16, 27/12

U.S. Cl. 525-187


31 Claims

1. A gum stock composition, comprising a blend of:


- (a) fluoropolymer gum comprising a copolymer of (1) terminally ethylenically unsaturated olefin which has 2 to 4 carbon atoms and can be homopolymerized by emulsion polymerization in the presence of a water soluble free radical catalyst such as $\text{K}_2\text{S}_2\text{O}_8$, and (2) at least one terminally unsaturated fluoromonoolefin, each of the doubly bonded chain carbon atoms of said fluoromonoolefin being bonded to at least one fluorine atom substituent and any remaining valence of any chain carbon atom of said fluoromonoolefin being satisfied by hydrogen, fluorine, chlorine, bromine, or a fluoroalkyl or fluoroalkoxy radical of 1 to 4 carbon atoms, with at least 10 percent of the chain carbon atoms of said copolymer being $-\text{CH}_2-$ units, at least 10 percent of the chain carbon atoms of said copolymer being bonded to alkyl or alkoxy radicals with the proviso that only one such radical is bonded to a given carbon atom, and with at least 50 percent of the total number of carbon-bonded moieties in said copolymer being fluorine, but with no chain carbon atom of said copolymer being bonded to more than one chlorine or bromine atom;
 (b) polyepichlorohydrin gum;
 (c) polyphenol curing agent; and
 (d) organo-onium cocuring agent selected from compounds of the formulas



wherein Q is a nitrogen, arsenic or phosphorus atom; X is an anion of valence m; each R^1 is a monovalent organic radical containing 1 to 20 carbon atoms, is the same as or different from any other R^1 , and can combine with another R^1 to form a cyclic structure containing a Q atom; and R^2 is a divalent organic radical containing 2 to 12 carbon atoms;



or



wherein S is sulfur; X is an anion of valence m; each R^3 is a monovalent organic radical containing 1 to 20 carbon atoms, is the same as or different from any other R^3 , and can combine with another R^3 to form a cyclic structure containing an S atom; R^4 is a divalent organic radical containing 2 to 12 carbon atoms; and at least one R^3 or R^4 group is aromatic;

which composition in reactive association with an acid acceptor will, upon exposure to heat, cure into an elastomer.

4,293,664

COOK-IN FILM CONTAINING A BLEND OF IONOMER AND ELASTOMER

Stanley Lustig, Park Forest, and Stephen J. Vicik, Darien, both of Ill., assignors to Union Carbide Corporation, New York, N.Y.

Filed Dec. 27, 1979, Ser. No. 107,568

Int. Cl.³ C08L 23/16, 33/02

U.S. Cl. 525-196

10 Claims

1. A stretchable monolayer film adapted for packaging and cooking poultry, consisting essentially of a blend of (1) ionomer(s) of α -olefin(s) having a carbon number of 2 to 4 and α,β -ethylenically unsaturated carboxylic acid(s) having a carbon number of 3 to 6 containing one or more metallic ions connected to the side chains of the copolymer, and (2) an elastomer selected from the group consisting of a saturated ethylene-propylene copolymer elastomer having a Mooney viscosity greater than about 45 at 125° C. or an unsaturated ethylene-propylene non-conjugated diene terpolymer elastomer having a Mooney viscosity greater than about 65 at 125° C., said film having a thickness of from about 1.0 to about 3.0 mils.

4,293,665

STRUCTURAL ADHESIVE FORMULATIONS

Denis J. Zalucha, Waterford; Frederick H. Sexsmith, Erie; Ernest C. Hornaman, Girard, and Terrance H. Dawdy, Erie, all of Pa., assignors to Lord Corporation, Erie, Pa.

Continuation-in-part of Ser. No. 899,621, Apr. 24, 1978, Pat. No. 4,223,115. This application Jan. 11, 1980, Ser. No. 111,504

Int. Cl.³ C08K 5/52

U.S. Cl. 525-255

4 Claims


1. A room temperature-curable adhesive system comprising
 1. as a polymerizable adhesive composition, a mixture of
 (i) a polymer-in-monomer syrup consisting essentially of
 (i) from about 2 to about 60 percent by weight of at least one addition polymer;
 (ii) from about 10 to about 98 percent by weight of at least one polymerizable olefinically unsaturated compound having at least one $>\text{C}=\text{C}<$ group; and
 (iii) from zero to about 30 percent by weight of a polymer containing the group $-\text{CH}_2\text{CCl}=\text{CH}-\text{CH}_2-$,
 wherein n is an integer;
 wherein (i) and (ii) are present as a partial polymerization product of (ii) or of (ii) in the presence of (iii), the mixture of (i) and (ii) or of (i), (ii) and (iii) being a syrup of polymeric materials dissolved or dispersed in monomer, in which syrup the amount of (i) derived from (ii) is in the range from about 2 to about 90 percent by weight, based on the total weight of (i), (ii) and (iii);
 (2) from zero to about 5 percent by weight of polymerizable adhesive composition of at least one unsaturated dicarboxylic acid ester;
 (3) from zero to about 10 percent by weight of polymerizable adhesive composition of at least one unsaturated polyester resin;
 (4) from zero to about 20 percent by weight of polymerizable adhesive composition of at least one unsaturated carboxylic acid;

(5) from zero to about 40 percent by weight of polymerizable adhesive composition of at least one monomeric acrylic or methacrylic acid ester, said ester (5) being in addition to any such ester employed in (1) (ii);


(6) from zero to about 50 percent by weight of polymerizable adhesive composition of at least one polyvinyl alkyl ether;

(7) from zero to about 1 percent by weight of polymerizable adhesive composition of at least one waxy substance selected from the group consisting of paraffin wax, montan wax, beeswax, ceresine wax and spermaceti wax;


(8) an effective amount of at least one phosphorus-containing compound having the formulae



wherein each R is the same or different, and each R is independently a divalent organic radical directly bonded to the phosphorus atom through a carbon-phosphorus bond, said divalent radical being selected from the group consisting of divalent unsubstituted organic radical and divalent organic radical having at least one substituent group selected from the class consisting of halogen, hydroxyl amino, alkyl radical containing from 1 to 8 carbon atoms and aryl radical having at least one moiety containing at least one aromatic nucleus; and wherein each X is the same or different, and each X is independently a functional group selected from the class consisting of hydrogen, hydroxyl, amino, mercapto, halogen and $\text{CH}_2=\text{C}\equiv$;




wherein R and X are as previously defined; and R^1 is hydrogen or $-\text{R}^2-\text{X}$, wherein R^2 is a divalent organic radical directly bonded to the oxygen radical through a carbon-oxygen bond, said divalent radical R^2 being selected from the group consisting of divalent unsubstituted organic radical and divalent organic radical having at least one substituent group selected from the class consisting of halogen, hydroxyl, amino, alkyl radical containing from 1 to 8 carbon atoms and aryl radical having at least one moiety containing at least one aromatic nucleus and X is as previously defined; and



wherein R^1 is as previously described;

- (9) an effective amount of at least one reducing agent;
(10) from 0.01 to about 10 percent by weight of polymerizable adhesive composition of at least one tertiary amine having the formula



wherein Z is methylene; Y is selected from the group consisting of hydrogen, hydroxy, amino, halogen, alkyl radical having from one to 8 carbon atoms, and alkoxy radicals wherein the alkyl moiety has from one to 8 carbon atoms; and a is zero or 1; and b is one or two;

- (11) from zero to about 15 percent by weight of polymerizable adhesive composition of a mixture of a metal molybdate selected from the group consisting of zinc molybdate, calcium molybdate, barium molybdate, strontium molybdate and mixtures thereof and a metal phosphate selected from the group consisting of zinc phosphate, calcium phosphate, magnesium phosphate and mixtures thereof; said metal molybdate being pres-

ent on a volume concentration basis of from about 2 to about 3 parts per part of said metal phosphate; and (12) from zero to about 15 percent by weight of polymerizable adhesive composition of at least one compound selected from the group consisting of polybasic lead salts of phosphorus acid, polybasic lead salts of unsaturated organic dicarboxylic acids and acid anhydrides, polybasic lead salts of unsaturated organic dicarboxylic acids and acid anhydrides, zinc oxide, and mixtures thereof;

the amount (1), in weight percent, being 100 minus the combined weight percent of (2) through (12); and

- II. as a bonding accelerator, an effective amount of at least one oxidizing agent, said oxidizing agent being reactive at room temperature with said reducing agent to generate free radicals effective to initiate addition polymerization of said polymerizable adhesive composition.

4,293,666

ORGANIC PIGMENTS

William W. Maslanka, London-Britain Township, Chester County, Pa., and Gavin G. Spence, New Castle County, Del., assignors to Hercules Incorporated, Wilmington, Del.

Division of Ser. No. 909,606, May 25, 1978, Pat. No. 4,235,982, which is a continuation-in-part of Ser. No. 803,330, Jun. 3, 1977, abandoned. This application Jun. 23, 1980, Ser. No. 161,803


Int. Cl.³ C08F 267/10

U.S. Cl. 525-284


24 Claims

1. Water-insoluble graft copolymer particles consisting essentially of the free radical catalyzed graft copolymerization product of (1) at least one ethylenically unsaturated monomer (a) and at least one polyethylenically unsaturated monomer (b) in an amount at least sufficient to provide cross linked graft copolymer particles, and (2) a water-soluble cationic prepolymer having an RSV of about 0.1 to about 2.5 (1 M NaCl, 1%, 25° C.), the prepolymer moiety of the graft copolymer particles being present on the surface of the particles,

said monomer (a) being selected from the group consisting of methyl alpha-chloroacrylate, ethyl alpha-chloroacrylate, methyl methacrylate, isopropyl methacrylate, phenyl methacrylate, vinyl chloride, acrylonitrile, methacrylonitrile, and monomers having the formula




wherein R is hydrogen or methyl, Y is methyl or chlorine, and n is 0, 1, 2, or 3, said monomer (b) being selected from the group consisting of divinylbenzene; diallyl phthalate; ethylene glycol dimethacrylate; 1,3-butylene glycol dimethacrylate; 1,6-hexanediol dimethacrylate; polyethylene glycol dimethacrylate; polypropylene glycol dimethacrylate; trivinylbenzene; divinylbenzophenone; diallyl maleate; diallyl fumarate; trimethylol propane trimethacrylate; and pentaerythritol tetraacrylate, and said prepolymer (2) being the addition polymerization product of (i) about 5 mole percent to 100 mole percent of a cationic monomer having the formula




wherein

R_1 is hydrogen or methyl,
 R_2 is hydrogen, or a C_1 - C_4 alkyl,
 R_3 is hydrogen, a C_1 - C_4 alkyl,



where Y is hydroxyl or halogen,



or $-(\text{CH}_2\text{CH}_2\text{O})_n\text{H}$ where n is an integer 1 or more and X^- is an anion, and

- (ii) from about 95 mole percent to 0 mole percent of at least one monoethylenically unsaturated amide monomer, the amount of prepolymer (2) employed in preparing the graft copolymer particles being from about 1 part to about 25 parts by weight for each 100 parts by weight of monomers (1) employed, said prepolymer moiety of the particles having chemically bonded thereto a cellulose reactive group.

4,293,667

ORGANIC PIGMENTS

William W. Maslanka, London-Britain Township, Chester County, and Gavin G. Spence, New Castle County, both of Pa., assignors to Hercules Incorporated, Wilmington, Del.

Division of Ser. No. 909,606, May 25, 1978, Pat. No. 4,235,982, which is a continuation-in-part of Ser. No. 803,330, Jun. 3, 1977, abandoned. This application Jun. 23, 1980, Ser. No. 161,804


Int. Cl.³ C08F 267/10

U.S. Cl. 525-284


28 Claims

1. Water-insoluble graft copolymer particles consisting essentially of the free radical catalyzed graft copolymerization product of (1) at least one ethylenically unsaturated monomer (a) and at least one polyethylenically unsaturated monomer (b) in an amount at least sufficient to provide cross linked graft copolymer particles, and (2) a water-soluble cationic prepolymer having an RSV of about 0.1 to about 2.5 (1 M NaCl, 1%, 25° C.), the prepolymer moiety of the graft copolymer particles being present on the surface of the particles,

said monomer (a) being selected from the group consisting of methyl alpha-chloroacrylate, ethyl alpha-chloroacrylate, methyl methacrylate, isopropyl methacrylate, phenyl methacrylate, vinyl chloride, acrylonitrile, methacrylonitrile, and monomers having the formula




wherein R is hydrogen or methyl, Y is methyl or chlorine, and n is 0, 1, 2, or 3, said monomer (b) being selected from the group consisting of divinylbenzene; diallyl phthalate; ethylene glycol dimethacrylate; 1,3-butylene glycol dimethacrylate; 1,6-hexanediol dimethacrylate; polyethylene glycol dimethacrylate; polypropylene glycol dimethacrylate; trivinylbenzene; divinylbenzophenone; diallyl maleate; diallyl fumarate; trimethylol propane trimethacrylate; and pentaerythritol tetraacrylate, and said prepolymer (2) being the addition polymerization product of (i) about 5 mole percent to 100 mole percent of a cationic monomer having the formula




wherein

R_1 is hydrogen or a C_1 - C_4 alkyl,
 R_2 is hydrogen, alkyl or substituted alkyl,
 R_3 is hydrogen, a C_1 - C_4 alkyl,



where Y is hydroxyl or halogen,



or $-(\text{CH}_2\text{CH}_2\text{O})_n\text{H}$ where n is an integer 1 or more and X^- is an anion, and

- (ii) from about 95 mole percent to 0 mole percent of at least one monoethylenically unsaturated amide monomer,

the amount of prepolymer (2) employed in preparing the graft copolymer particles being from about 1 part to about 25 parts by weight for each 100 parts by weight of monomers (1) employed.

4,293,668

REFINING OLEFIN/MALEIC ACID COPOLYMERS BY EXTRACTION WITH ALKANES

Robert A. Heimsch, St. Louis, Mo., assignor to Monsanto Company, St. Louis, Mo.

Filed Dec. 26, 1979, Ser. No. 94,417

Int. Cl.³ C08F 8/42, 6/10, 6/00

U.S. Cl. 525-369

8 Claims

1. A method of refining octadecene-1/maleic acid copolymer which comprises extracting monomeric and low molecular weight polymer material from such copolymer in a procedure involving contacting the copolymer in the form of particles in the range of about 20 to about 100 mesh with liquid alkane having 5 to 8 carbon atoms for an extended period of time sufficient for the alkane to permeate through copolymer particles and extract such material, and separating the alkane from the copolymer, with the resulting copolymer having less than 0.1% of its molecules of less than 2000 molecular weight and no more than 400 parts per million of monomeric olefin.

4,293,669

HEAT-RESISTANT CROSS-LINKED POLYMERS AND THE USE THEREOF AS BINDERS

Ludwig Rottmaier, Odenthal; Rudolf Merten, Leverkusen; Jürgen Lewalter, Odenthal; Wilfried Zecher, and Willi Dünwald, both of Leverkusen, all of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Mar. 3, 1980, Ser. No. 126,950

Claims priority, application Fed. Rep. of Germany, Mar. 6, 1979, 2908626


Int. Cl.³ C08G 18/32, 18/38, 18/16

U.S. Cl. 525-452

5 Claims

1. Cross-linked polymers which are linked by ester and/or urethane groups and which optionally contain amide and/or imide groups and/or isocyanurate and/or hydantoin rings in co-condensed form or are mixed with the corresponding poly-

mers, wherein said cross-linking component is derived from N,N',N''-tris-hydroxyalkyl triazolidine-3,5-diones corresponding to the following general formula:



wherein

R¹, R², R³ and R⁴ each independently represents hydrogen, an optionally substituted aliphatic, cycloaliphatic or aromatic radical and X represents O or S.

4,293,670

BLEND OF POLY(ARYL ETHER) RESINS AND POLYETHERIMIDE RESINS

Lloyd M. Robeson, Whitehouse Station; Markus Matzner, Edison, and Louis M. Maresca, Belle Mead, all of N.J., assignors to Union Carbide Corporation, New York, N.Y.


Filed Dec. 26, 1979, Ser. No. 106,505

Int. Cl.³ C08L 81/06, 79/08


U.S. Cl. 525-436

9 Claims


1. A molding composition comprising a blend of from about 95 to about 5 weight percent of a poly(aryl ether) and from about 5 to about 95 weight percent of a polyetherimide of the following formulae:



wherein a is an integer greater than 1, to about 10,000 or more, —O—R₄—O— is attached to the 3 or 4 and 3' and 4' positions and R₄ is selected from (a) a substituted or unsubstituted aromatic radical such as




(b) a divalent radical of the formula:




wherein R₆ is independently C₁ to C₆ alkyl, or halogen and R₇ is selected from —O—,



alkylene of 1 to 6 carbon atoms, cycloalkylene of 4 to 8 carbon atoms, alkylidene of 1 to 6 carbon atoms or cycloalkylidene of 4 to 8 carbon atoms, R₅ is selected from an aromatic hydrocarbon radical having from 6-20 carbon atoms and halogenated derivatives thereof, or alkyl substituted derivatives thereof, wherein the alkyl group contains 1 to 6 carbon atoms, alkylene and cycloalkylene radicals having from 2 to 20 carbon atoms, C₂-C₈ alkylene terminated polydiorganosiloxane and a divalent radical of the formula





wherein R₆ and R₇ are as previously defined and R₇ may be a direct bond;



wherein —O—Z— is a member selected from



wherein R₈ is independently hydrogen, lower alkyl or lower alkoxy



wherein the oxygen may be attached to either ring and located ortho or para to one of the bonds to the anhydride carbonyl group wherein a, R₄ and R₅ are as previously defined.

4,293,671

ORGANOPOLYSILOXANE COMPOSITION FOR PREPARING PEELABLE FILM

Shosaku Sasaki, and Nobuo Kaiya, both of Ichihara, Japan, assignors to Toray Silicone Company, Ltd., Ichihara, Japan

Filed Jan. 17, 1980, Ser. No. 112,871

Claims priority, application Japan, Feb. 16, 1979, 54-15988

Int. Cl.³ C08L 83/06; C08G 77/12

U.S. Cl. 525-478

2 Claims

1. An organopolysiloxane composition, curable to a peelable film, said composition being obtained by mixing components consisting essentially of

- 100 parts by weight of an organopolysiloxane having the formula R₃SiO_{(4-a)/2} and a viscosity at 25° C. of from 40 to 3000 centipoise, wherein each R' denotes a monovalent hydrocarbon or fluorinated hydrocarbon group and a is a number from 1.9 to 2.05, at least two R' groups being vinyl and at least 70 percent of all R' groups being methyl,
- 0.5 to 20 parts by weight of an organohydrogenpolysiloxane having at least 3 silicon-bonded hydrogen atoms per molecule and a viscosity at 25° C. of from 1 to 1000 centipoise,
- 2 to 200 parts by weight of a copolymer composed of RSiO_{3/2} siloxane units in addition to R₃SiO_{1/2} siloxane units and SiO_{4/2} siloxane units wherein each R denotes a monovalent hydrocarbon group, at least two R groups per molecule being vinyl, the molar ratio of (R₃SiO_{1/2})/(RSiO_{3/2})/(SiO_{4/2}) being (0.1 to 1.5)/(0.1 to 1.0)/(1.0), and
- a catalytic amount of a hydrosilylation catalyst, the viscosity of said organopolysiloxane composition, curable to a peelable film, having a value of from 50 to 6000 centipoise at 25° C.

4,293,672

PROCESS FOR STABILIZING POLYESTER COMPOSITIONS

Roy J. Jackson, Houston, Tex., assignor to Shell Oil Company, Houston, Tex.

Filed Jun. 27, 1980, Ser. No. 163,464

Int. Cl.³ C08G 59/16

U.S. Cl. 525-507

13 Claims

1. A process for reducing the premature gelation of unsaturated polyester prepared by esterifying an epoxy compound containing tertiary, allylic or benzylic hydrogens with an ethylenically unsaturated monocarboxylic acid which comprises prereacting the epoxy compound with a hydroxylamine prior to the esterification step.

4,293,673

SPHEROIDAL POLYMERIZATION CATALYST, PROCESS FOR PREPARING, AND USE FOR ETHYLENE POLYMERIZATION

Anthony D. Hamer, and Frederick J. Karol, both of Belle Mead, N.J., assignors to Union Carbide Corporation, New York, N.Y.

Continuation-in-part of Ser. No. 974,013, Dec. 28, 1978, abandoned. This application Nov. 28, 1979, Ser. No. 95,010

Int. Cl.³ C08F 2/34, 4/02, 10/02

U.S. Cl. 526-88


8 Claims

1. A catalytic process for producing ethylene polymers selected from the group consisting of ethylene homopolymers and copolymers with a Ti containing catalyst at a productivity of $\geq 50,000$ pounds of polymer per pound of Ti under a pressure of ≤ 1000 psi in the gas phase

said polymer being produced in granular spherical form having a particle size of from about 250 to about 2550 microns and having a density of ≥ 0.91 to ≤ 0.97 and melt flow ratio of ≥ 22 to ≤ 32

which comprises homopolymerizing or copolymerizing ethylene at a temperature of about 30° to 115° C. by contacting the monomer charge with spherical particles of an activated catalyst composition produced by

(A) forming a spherical precursor composition of the formula:



wherein

R is a C₁ to C₁₄ aliphatic or aromatic hydrocarbon radical, or COR' wherein R' is a C₁ to C₁₄ aliphatic or aromatic hydrocarbon radical, X is Cl, Br, I, or mixtures thereof, ED is an electron donor compound, Filler is an inert filler compound, and, based on the total weight of said composition,

m is ≥ 0.5 to ≤ 56 ,

n is 0 or 1,

p is ≥ 2 to ≤ 116 ,


q is ≥ 2 to ≤ 85 , and

r has a value such that the percent filler is from about 10 to about 95 weight percent based on the total weight of said composition, by forming a slurry or solution of at least one magnesium compound and at least one titanium compound and at least one filler compound in at least one electron donor compound so as to thereby form a slurry or solution of said precursor composition in said electron donor compound and spray drying said slurry or solution by atomization to form spherical particles of said precursor composition which have a particle size of from about 10 to about 200 microns,

said magnesium compound having the structure MgX₂, said titanium compound having the structure Ti(OR)_aX_b wherein a is 0, 1 or 2, b is 1 to 4 inclusive and a+b=3 or 4, said electron donor compound being a liquid organic compound in which said magnesium compound and said titanium compound are soluble and which is selected from the group consisting of alkyl esters of aliphatic and aromatic carboxylic acids, aliphatic ethers, cyclic ethers and aliphatic ketones and,

(B) completely activating said precursor composition with 10 to 500 mols of activator compound per mol of Ti in said precursor composition,

said activator compound having the formula



wherein X' is Cl or OR''', R' and R''' are the same or different, and are C₁ to C₁₄ saturated hydrocarbon radicals, d is 0 to 1.5, e is 1 or 0 and c+d+e=3, said activating being conducted after the recovery of said particles of said precursor composition.

4,293,674

DIENYL METHACRYLATES

Gerald D. Andrews, Hockessin, Del., assignor to E. I. Du Pont de Nemours and Company, Wilmington, Del.

Filed Jun. 3, 1980, Ser. No. 155,978

Int. Cl.³ C08F 20/40; C07C 67/03; C08F 118/12

U.S. Cl. 526-327

16 Claims

10. Copolymer, prepared by direct polymerization, of the compound of the formula CH₂=C(CH₃)CO₂R wherein R is an alkadienyl or cycloalkadienyl group which contains the 1,3- or 1,4-diene carbon skeleton and at least one anionically polymerizable methacrylic acid ester.

11. Copolymer of claim 10 wherein the ester is methyl methacrylate.

12. Copolymer of claim 10 wherein the ester is butyl methacrylate.

4,293,675

ANTIMONY HALIDE-ORGANIC PHOSPHONATE ESTER CATIONIC POLYMERIZATION CATALYSTS
Robert J. Blachunis, St. Paul, and Stephen W. Bany, North St. Paul, both of Minn., assignors to Minnesota Mining and Manufacturing Company, St. Paul, Minn.


Filed Feb. 26, 1980, Ser. No. 124,836
Int. Cl.³ C08G 77/06

U.S. Cl. 528—14

8 Claims

1. A method for polymerizing at least one cationically polymerizable organic monomer the method comprising:

- (a) admixing with said organic monomer a catalytically effective amount of a trivalent or pentavalent antimony halide-organic phosphorus ester complex catalyst of the formula:



wherein R² and R³ are independently selected from phenyl, alkenyl, halogenated alkyl, or alkyl of one to 18 carbon atoms, and

- (b) effecting polymerization of said organic monomer.

4,293,676

OXYGEN-CURABLE MERCAPTOORGANOSILOXANE COMPOSITIONS CONTAINING BOTH REDOX AND IRON CARBONYL COMPOUNDS AND METHOD OF FORMING HIGHER MOLECULAR WEIGHT PRODUCTS THEREFROM

Gary R. Homan, and Chi-Long Lee, both of Midland, Mich., assignors to Dow Corning Corporation, Midland, Mich.


Filed Dec. 3, 1979, Ser. No. 99,253
Int. Cl.³ C08G 77/06

U.S. Cl. 528—15

24 Claims

1. A composition of matter, stable in the absence of oxygen, which consists essentially of a product obtained by mixing the following substantially in the absence of oxygen

- (A) 100 parts by weight of at least one mercapto-functional organosiloxane, said mercapto-functional organosiloxane having an average of at least two mercapto-functional siloxane units per molecule selected from the group consisting of mercapto-functional siloxane units of the average unit formula




any other siloxane units present having the average unit formula



wherein

- each R² is a hydroxyl radical or an organic radical selected from the group consisting of R⁴ and 3,3,3-trifluoropropyl radicals,
each R⁴ is R³ or OR¹,
each R³ is an alkyl radical of 1 to 4 inclusive carbon atoms or phenyl radical,
each R¹ is an alkyl radical of 1 to 4 inclusive carbon atoms,
n has a value of from 2 to 4 inclusive,
w has a value of from 0 to 1 inclusive,
x has a value of from 1 to 2 inclusive,

y has a value of from 0 to 2 inclusive,
z has a value of from 0 to 3 inclusive and the sum of x+y has a value of from 1 to 3 inclusive,
and the ratio of the total R³, HSC_nH_{2n}—,



and 3,3,3-trifluoropropyl radicals to silicon atoms in the mercapto-functional organosiloxane is in the range of 0.98/1 to 3.00/1;

- (B) a catalytic amount of an iron carbonyl catalyst selected from the group consisting of Fe(CO)₅, Fe₂(CO)₉, Fe₃(CO)₁₂, dicyclopentadienyldiiron tetracarbonyl, butadieneiron tricarbonyl, and cyclohexadieneiron tricarbonyl;
(C) 0 to 200 parts by weight of at least one filler; and
(D) 0.1 to 6 parts by weight of a redox compound selected from the group consisting of copper (II) sulfate and iron (III) oxide.

4,293,677

CURABLE ORGANOPOLYSILOXANE COMPOSITION CONTAINING MICROCAPSULES

Takeshi Imai, Ichihara, Japan, assignor to Toray Silicone Company, Ltd., Tokyo, Japan

Filed Jun. 9, 1980, Ser. No. 157,928

Claims priority, application Japan, Jun. 4, 1979, 54-68841
Int. Cl.³ C08G 77/08, 77/20

U.S. Cl. 528—15

6 Claims

1. An organopolysiloxane composition comprising
(A) an organopolysiloxane having an average unit formula



wherein R represents a substituted or unsubstituted monovalent hydrocarbon radical and a has a value in the range of from 0.5 to 3, and said organopolysiloxane having at least two silicon-bonded alkenyl radicals per molecule,

- (B) an organohydrogenpolysiloxane having at least two silicon-bonded hydrogen atoms per molecule and the organic radicals bonded to silicon atoms are substituted or unsubstituted monovalent hydrocarbon radicals, said organohydrogenpolysiloxane being contained in microcapsules with a nonpermeable film, and
(C) a catalyst for the addition reaction between (A) and (B).

4,293,678

RADIATION-CURABLE ACRYLATED EPOXY SILICONE COMPOSITIONS

Richard G. Carter, Charleston; Stuart L. Watson, Jr., South Charleston, both of W. Va., and Arthur N. Pines, Katonah, N.Y., assignors to Union Carbide Corporation, New York, N.Y.

Filed Nov. 26, 1979, Ser. No. 97,446
Int. Cl.³ C08G 77/20

U.S. Cl. 528—32


5 Claims

1. Acrylated epoxy silicones of the general formula:



wherein

- M is an R₃SiO_{0.5} group;
D is an



4,293,680

PROCESS FOR THE PRODUCTION OF DIISOCYANATO TOLUENE MIXTURES HAVING AN INCREASED CONTENT OF 2,6-DIISOCYANATO TOLUENE, AND THE USE THEREOF AS SYNTHESIS COMPONENTS IN THE PRODUCTION OF POLYURETHANE ELASTOMERS

Jan Mazanek, Munich, and Hanns P. Nüller, Odenthal, both of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Aug. 6, 1980, Ser. No. 175,601

Claims priority, application Fed. Rep. of Germany, Aug. 8, 1979, 2932095


Int. Cl.³ C08G 18/76

U.S. Cl. 528—67


5 Claims

1. A process for the production of diisocyanate mixtures of 2,4-diisocyanato toluene and 2,6-diisocyanato toluene, having from 36 to 90% by weight, based on the total mixture, of 2,6-diisocyanato toluene, comprising: trimerizing some of the isocyanate groups of a diisocyanate mixture of 2,4-diisocyanato toluene and 2,6-diisocyanato toluene, having a maximum content of 2,6-diisocyanato toluene of 35% by weight based on the total mixture and isolating from the reaction mixture which is thus obtained, a diisocyanate mixture having an increased content of 2,6-diisocyanato toluene.


group;
D'' is an



group;
D''' is an



or an



group;

X is hydrogen;

R is an alkyl group having from 1 to 5 carbon atoms, a cycloalkyl group having from 5 to 7 carbon atoms, an aryl group having 6 ring carbon atoms, or an alkoxy group having from 1 to 3 carbon atoms;

R' is an alkyl group having from 1 to 5 carbon atoms;

m is an integer having a value of from about 0 to 25;

n is an integer having a value of from 0 to 25;

x is an integer having a value of from 0 to about 100;

y is an integer having a value of from 1 to about 5; and

z is an integer having a value of from 0 to about 10; and

wherein the silicone backbone may be linear, branched or cyclic and may be continuous or discontinuous being a random arrangement of the D, D'' and D''' groups.

4,293,679

COMPOSITION AND METHOD OF CONTROLLING SOLID POLYURETHANE PARTICLE SIZE WITH WATER REACTANT

Joseph A. Cogliano, Pasadena, Md., assignor to W. R. Grace & Co., New York, N.Y.

Continuation-in-part of Ser. No. 47,973, Jun. 13, 1979, abandoned. This application May 27, 1980, Ser. No. 153,307
Int. Cl.³ C08G 18/08

U.S. Cl. 528—48


12 Claims

1. A process for forming solid, discrete, hydrophilic, cross-linked, polyurethane particles of reduced size which comprises adding


(a) a hydrophilic prepolymer comprising an isocyanate-capped polyol or mixture of isocyanate-capped polyols wherein said isocyanate-capped polyol or mixture of polyols has a reaction functionality greater than 2, the total of said polyol present having an ethylene oxide content of at least 40 weight percent before capping;

(b) said prepolymer (a) being dissolved in a water soluble solvent, to

(c) an agitated water reactant, the volume ratio of (c):(a) being at least 2:1.




wherein R₁ and R₂ are lower alkyl and R₃ is selected from hydrogen, lower alkyl, aryl and




wherein R₄ is selected from H and lower alkyl.

8. A curable epoxy resin composition comprising an epoxy resin and an epoxy resin curing agent, wherein the epoxy resin curing agent is represented by the formula:



wherein R₁ and R₂ are each independently selected from hydrogen and lower alkyl and R₃ is selected from hydrogen, lower alkyl, aryl and




4,293,683
METHOD FOR MAKING POLYETHERIMIDES USING CARBOXYLIC ACID SALTS OF ALKALI METALS OR ZINC AS CATALYSTS


Tohru Takekoshi, Scotia, and Howard J. Klopfer, Clifton Park, both of N.Y., assignors to General Electric Company, Schenectady, N.Y.

Filed Jul. 11, 1980, Ser. No. 168,660
Int. Cl.³ C08G 69/04, 73/10

U.S. Cl. 528-180 10 Claims
1. A method for making polyetherimide consisting essentially of chemically combined units of the formula,



which comprises effecting the reaction under melt polymerization conditions or solution polymerization conditions, between an aromatic bis(ether anhydride) of the formula,



and an organic diamine of the formula,




in the presence of a metal catalyst selected from the class consisting of Group IA metal carboxylic acid salts and Group IIB metal carboxylic acid salts, where R is a divalent aromatic organic radical having from 6-30 carbon atoms, R¹ is a divalent organic radical selected from R radicals, alkylene radicals having from 2-20 carbon atoms, cycloalkylene radicals, and C₍₂₋₈₎ alkylene terminated polydiorganosiloxane radicals.

4,293,684
POLYETHERIMIDE HAVING LONG CHAIN ALIPHATIC END GROUPS AND METHOD FOR MAKING

Tohru Takekoshi, Scotia, N.Y., assignor to General Electric Company, Schenectady, N.Y.

This application Mar. 26, 1980, Ser. No. 134,071
Int. Cl.³ C08G 73/10


U.S. Cl. 528-185 10 Claims
1. Polyetherimides consisting essentially of chemically combined units of the formula,




and terminal radicals of the formula,




where Z is a member selected from




and divalent organic radicals of the general formula,



where X is a member selected from the class consisting of divalent radicals of the formula,



where y is an integer from 1 to 5, and R is a divalent organic radical selected from the class consisting of aromatic hydrocarbon radicals having from 6 to about 20 carbon atoms and halogenated derivatives thereof, alkylene radicals having from 2 to about 20 carbon atoms, cycloalkylene radicals having from 3 to about 20 carbon atoms, from C₂ to about C₈ alkylene terminated polydiorganosiloxane and divalent radicals of the formula,




where Q is a member selected from $-\text{O}-$, $-\text{S}-$, $-\text{SO}_2-$, $-\text{CO}-$ and $-\text{C}_x\text{H}_{2x}-$, x is an integer from 1 to 5, a is 0 or 1 and R¹ is an aliphatic radical having from 12-20 carbon atoms.

4,293,685
METHOD FOR MANUFACTURING CROSSLINKED POLYETHERESTER RESINS

Zbigniew Jedlinski, Gliwice; Bogdan Thomalla; Antoni Kotas, both of Zabrze; Stanislaw Jedlinski, Debica; Wladyslaw Pilat, and Jan Jach, both of Nowa Sarzyna, all of Poland, assignors to Polska Akademia Nauk Zaklad Polimerow, Zabrze, Poland
Filed Oct. 25, 1979, Ser. No. 88,278

Claims priority, application Poland, Oct. 20, 1978, 210406
Int. Cl.³ G08G 63/02, 63/18

U.S. Cl. 528-190 8 Claims
1. A method for the production of cross-linked polyether polyester resins comprising polycondensing of saturated dicarboxylic acids or their anhydrides and unsaturated dicarboxylic acids or their anhydrides with glycols and then copolymerizing with a cross-linking monomer wherein as a saturated carboxylic acid, the Diels-Alder adduct of 2-naphthol with maleic anhydride is used, and wherein as a glycol is used a mixture of low molecular weight glycol and a high molecular weight glycol-hydroxyoligoether of the formula




wherein

R=H, CH₃, C₂H₅,
n=2-15,
and m=0-4.

4,293,686
THERMOSETTING POLYESTER RESIN COMPOSITION
Hugh C. Gardner, Somerville, N.J., assignor to Union Carbide Corporation, New York, N.Y.

Filed Apr. 18, 1980, Ser. No. 141,311
Int. Cl.³ C08G 63/02, 63/54

U.S. Cl. 528-192 33 Claims
1. A polymerizable composition comprising a mixture of:
(a) an unsaturated polyester, (b) a half ester characterized by the following empirical formula:




wherein n is a number having an average value of about 1.5 to less than about 4, m is equal to the free valence of A less the average value of n, A is the hydroxyl-free residue of an organic polyol which contained from 2 to 4, inclusive, hydroxyl groups, OH, in formula (I), (c) maleic anhydride and (d) an ethylenically unsaturated monomer.

4,293,687
TETRAALKYLATED BISCYCLOHEXYLAMINE DERIVATIVES

Oskar Weissel; Volker Serini, and Hans-Josef Buysch, all of Krefeld, Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany
Continuation of Ser. No. 818,261, Jul. 22, 1977, abandoned. This application May 5, 1980, Ser. No. 146,842


Claims priority, application Fed. Rep. of Germany, Jul. 22, 1976, 2632956; Aug. 17, 1976, 2637009
Int. Cl.³ C08F 12/02; C07C 83/00

U.S. Cl. 528-346 22 Claims
1. A bicyclohexylamine having the formula



wherein:

R¹ to R⁴ each represents identical or different alkyl groups having 1 to 6 carbon atoms;
X represents a single bond,
a divalent straight-chain or branched-chain aliphatic group having from 2 to 10 carbon atoms,
a methylene group, when at least one of said substituents R¹ to R⁴ has more than 1 carbon atom,
a divalent cycloaliphatic group having from 6 to 12 carbon atoms,
a divalent aliphatic straight or branched chain group with cycloaliphatic substituents having from 6 to 8 carbon atoms,
a divalent straight-chain or branched-chain dialkyl cyclohexane group having from 8 to 12 carbon atoms and a divalent straight-chain or branched-chain dialkyl benzene group having from 8 to 12 carbon atoms.
13. A polyamide obtained by reacting a bicyclohexylamine of the Formula



wherein:


R¹ to R⁴ each represent identical or different alkyl groups having 1 to 6 carbon atoms;
X represents a single bond,
a divalent straight-chain or branched-chain aliphatic group having from 2 to 10 carbon atoms,
a methylene group, when at least one of said substituents R¹ to R⁴ has more than 1 carbon atom,
a divalent cycloaliphatic group having from 6 to 12 carbon atoms,
a divalent aliphatic straight or branched-chain group with cycloaliphatic substituents having from 6 to 8 carbon atoms, a divalent straight-chain or branched-chain dialkyl cyclohexane group having from 8 to 12 carbon atoms and a divalent straight-chain or branched-chain dialkyl benzene group having from 8 to 12 carbon atoms with an aliphatic and/or aromatic dicarboxylic acid with up to 16 C-atoms.

4,293,688
POLYAMIDES OF 1,4-CYCLOHEXANE DICARBOXYLIC ACID AND 5-METHYL-1,9-NONANEDIAMINE AND FIBERS THEREOF


Robert W. Campbell, and H. Wayne Hill, Jr., both of Bartlesville, Okla., assignors to Phillips Petroleum Co., Bartlesville, Okla.

Filed Aug. 31, 1973, Ser. No. 393,493
Int. Cl.² C08G 69/26

U.S. Cl. 528-346 18 Claims
1. A normally solid, resinous polyamide with at least 80 weight percent thereof being composed of primary recurring structural units of the formula



wherein the R in each of at least 50 percent of said primary recurring structural units is 5-methylnonamethylene, and the R in each of the balance, if any, of said primary recurring structural units is individually selected from the group consisting of 2,4-dimethyloctamethylene and 2,4,6-trimethylheptamethylene; the balance, if any, of the recurring structural units of said polyamide having the formula



wherein each R' is individually selected from the group consisting of hydrogen and alkyl radicals having from 1 to 4 carbon atoms per radical, each R² is a divalent hydrocarbon radical having from 6 to 16 carbon atoms, and each R³ is a divalent hydrocarbon radical having from 4 to 14 carbon atoms; said polyamide containing less than 5 olefinic double bonds per 100 R groups.

4,293,689

METHOD OF PRODUCING

3-O-DEMETHYLFORTIMICIN B FROM FORTIMICIN AN

John H. Seely, Lake Forest, Ill., assignor to Abbott Laboratories, North Chicago, Ill.

Division of Ser. No. 25,250, Mar. 29, 1979, Pat. No. 4,219,643. This application Mar. 24, 1980, Ser. No. 133,177

Int. Cl.³ C07H 15/22

U.S. Cl. 536-17 R

1 Claim

1. A method of producing 3-O-demethylfortimicin B from fortimicin AN comprising the steps of subjecting fortimicin AN to hydrolysis in the presence of base and recovering 3-O-demethylfortimicin B from the reaction.

4,293,690

PRODUCTION OF 2,6-DIAMINONEBULARINES

Yoichi Sawa, Sengokuhigashimachi; Yoshiyuki Kawakami, Tsurumai Higashi, and Ryuji Marumoto, Osaka, all of Japan, assignors to Takeda Chemical Industries, Ltd., Osaka, Japan


Filed Mar. 28, 1980, Ser. No. 136,072

Claims priority, application Japan, Apr. 2, 1979, 54-39562 Int. Cl.³ C07H 19/16, 19/18

U.S. Cl. 536-24

16 Claims


1. A method for producing a compound of the formula



wherein


R is phenyl or phenyl substituted on the ring by halogen, C₁₋₄ alkyl, C₁₋₄ alkoxy, carbamoyl, lower alkyl carbamoyl, phenylcarbamoyl, morpholinocarbamoyl, piperidinocarbamoyl or C₂₋₅ alkanoyl; or an acid addition salt

thereof, which consists of reacting a compound of the formula



wherein

R¹, R² and R³, independently of one another, are hydroxyl or protected hydroxyl, with a compound of the formula,



wherein

R has the same meaning as defined above;

X is amino, amino substituted by R as defined above or C₁₋₄ alkylthio;

and removing the hydroxyl protecting groups of the resulting compound when such protective groups remain.

4,293,691

METHOD FOR PREPARING MAGENTA COUPLERS HAVING THIOETHER GROUPS

Nobuo Furutachi, and Nobuo Seto, both of Minami-ashigara, Japan, assignors to Fuji Photo Film Co., Ltd., Minami-ashigara, Japan

Filed Aug. 10, 1979, Ser. No. 65,407

Claims priority, application Japan, Aug. 10, 1978, 53-97574 Int. Cl.³ C07D 413/12, 401/12, 403/12, 231/48

U.S. Cl. 544-140


11 Claims

1. A method for preparing a coupler represented by the formula (I):




(I)

which comprises reacting a disulfide compound represented by the formulae (IIa) or (IIb) with a compound of the formula A-H



(IIa)



(IIb)

wherein A is a magenta coupler in which a hydrogen atom at the coupling active position is removed, wherein A is represented by the formula (IV):

4,293,692

CONTINUOUS PROCESS FOR MANUFACTURING SUBSTANTIALLY FULLY METHYLATED SUBSTANTIALLY FULLY METHYLOLATED MELAMINE COMPOSITIONS

Venkatrao K. Pai, and Joseph F. Skirvan, both of Stamford, Conn., assignors to American Cyanamid Company, Stamford, Conn.

Filed Nov. 17, 1977, Ser. No. 852,380

Int. Cl.³ C07D 251/70

U.S. Cl. 544-196

11 Claims

1. A continuous process for making a substantially fully methylated, substantially fully methylolated melamine composition comprising the steps of:

(1) conducting the methylation of melamine in two stages as follows: (a) in a first stage, continuously charging melamine and aqueous formaldehyde to a first reaction zone in a ratio of from about 9 to about 18 moles of formaldehyde per mole of melamine while controlling the pH of the reaction mixture thus formed in the reaction zone at from about 4 to 6 and also controlling the temperature of the reaction mixture at from about 45° C. to about 75° C. and the residence time of the mixture in said zone for a period sufficiently long to allow the melamine to become methylolated to an average of about 4.5 to 5.5, said methylolated product being from about 40% to about 70% in the oligomeric state and from about 30% to about 60% in the monomeric state, then (b), in a second stage, passing the reaction mixture from the first reaction zone to a second reaction zone and adjusting the pH of the mixture in the second zone to from above 7 to about 10 and holding the temperature at about 45° C. to about 75° C. for a residence time sufficient for the melamine monomers and oligomers to become substantially fully methylolated;

(2) withdrawing the methylolated reaction mixture from the second reactor and removing about 70-95% of the water content thereof;

(3) passing the concentrated reaction mixture to a third reaction zone along with from about 20 to about 30 moles of methanol per mole of melamine utilized in step 1(a) while controlling the pH of the mixture at from about 1.2 to about 2.5, the temperature of the reaction mixture at from about 30° C. to about 55° C. and the residence time of the mixture in the reaction zone for a period sufficient to effect an average degree of methylation of the methylolmelamine of at least 4.5;

(4) withdrawing the reaction mixture from the third reaction zone into a neutralization zone and adjusting the pH thereof to from about 9 to 12;

(5) withdrawing the mixture from the neutralization zone to a distillation column and distilling off unreacted methanol therefrom;

(6) passing the bottoms from the distillation column to a stripping zone and stripping off substantially all of the water and unreacted formaldehyde therefrom; and

(7) treating the bottoms from step 6 in a solids separation unit to remove precipitated salts therefrom and provide the substantially fully methylated, substantially fully methylolated melamine composition product.

4,293,693

HEMIACETALS OF ADDUCTS OF ACROLEIN AND ISOCYANURIC ACID

Saul M. Cohen, Springfield, and John R. LeBlanc, Wilbraham, both of Mass., assignors to Monsanto Company, St. Louis, Mo.


Filed Dec. 22, 1980, Ser. No. 219,018

Int. Cl.³ C07D 251/34

U.S. Cl. 544-221


21 Claims

1. A process for the preparation of a hemiacetal which comprises reacting isocyanuric acid with at least one mole of acrolein per mole of isocyanuric acid under mildly acid condition to form an aldehyde and reacting the aldehyde with a




(IV)


wherein R₇ represents an anilino group, an acylamino group or a ureido group; and R₈ represents a group of the formula




wherein A₁, A₂ and A₃, which may be the same or different, each represents a hydrogen atom, an alkyl group, a halogen atom, an alkoxy group, an aryloxy group, an acylamino group, a carbamoyl group, a sulfamoyl group, a sulfonyl group or a cyano group and wherein any R₇ or R₈ group of an aliphatic nature has 1-22 carbon atoms and any R₇ or R₈ group of an aromatic nature has 6-32 carbon atoms, R is a straight chain or branched chain alkyl group having 1 to 22 carbon atoms or a cyclic alkyl group having 5 to 22 carbon atoms, a cyclic alkenyl group having 6 to 22 carbon atoms, or an aralkyl group having up to



group, where B is -Y, -D-Y or



and D is an oxygen atom or



R₄ is a hydrogen atom, an alkyl group having 1 to 22 carbon atoms or an aryl group having 6 to 32 carbon atoms, Y is a straight chain or branched chain alkyl group having 1 to 22 carbon atoms or a cyclic alkyl group having 5 to 22 carbon atoms, a straight chain or branched chain alkenyl group having up to 22 carbon atoms or a cyclic alkenyl group having 5 to 22 carbon atoms, as aralkyl group having up to 32 carbon atoms, an aryl group having 6 to 32 carbon atoms, or a non-metallic heterocyclic group containing at least one carbon atom and comprising a 5 to 7-membered heterocyclic ring, Q is a non-metallic atom group necessary to complete a 5- or 6-membered nitrogen-containing heterocyclic ring containing at least one carbon atom, Z is an oxygen atom or a sulfur atom, R₁, R₂ and R₃ each is a hydrogen atom, an alkyl group having 1 to 22 carbon atoms, a cycloalkyl group having 5 to 22 carbon atoms or a substituted or unsubstituted phenyl group and R₁ and R₃ or R₂ and R₃ can combine to form a 5-, 6- or 7-membered nitrogen-containing heterocyclic ring containing at least one carbon atom and X is a halogen atom, said disulfide being reacted with said compound in the presence of a base and a solvent.

monohydric primary or secondary alcohol to form the hemiacetal.

4,293,694

PYRIDO[3,2,1-JK]CARBAZOLS

Hiroshi Ishikawa, and Kazuyuki Nakagawa, both of Tokushima, Japan, assignors to Otsuka Pharmaceutical Co., Ltd., Tokyo, Japan


Filed Apr. 10, 1979, Ser. No. 28,771

Int. Cl.³ C07D 221/04


U.S. Cl. 546—72

14 Claims

1. A pyrido[3,2,1-jk]carbazol having the formula (I)



wherein R represents a hydroxy group, an alkoxy group having 1 to 4 carbon atoms, an alkoxy group having 1 to 4 carbon atoms and substituted with a halogen atom, an alkoxy group having 1 to 4 carbon atoms and substituted with a 4-methyl-1-piperidinyl group, a hydrazino group or a



wherein Y represents a hydroxy group, an alkoxy group having 1 to 4 carbon atoms, a halogen atom, a nitro group, an amino group, an alkanoylamino group having 1 to 4 carbon atoms or non-sterically hindering alkyl group having 1 to 4 carbon atoms, and n is 0, 1 or 2; and the pharmaceutically acceptable salts thereof.

4,293,695

FURONAPHTHYRIDINE COMPOUNDS

Yoshiaki Tanaka, and Isao Hayakawa, both of Minamifunabori, Japan, assignors to Daiichi Seiyaku Co., Ltd., Tokyo, Japan

Continuation of Ser. No. 8,205, Jan. 31, 1979, abandoned. This application Sep. 29, 1980, Ser. No. 191,620


Claims priority, application Japan, Jun. 9, 1978, 53-69685

Int. Cl.³ C07D 491/147

U.S. Cl. 546—83

6 Claims

1. A compound of the formula (I)



wherein R¹ represents an alkyl group having 1 to 6 carbon atoms, and M represents a hydrogen atom, an alkali metal or an alkaline earth metal.

4,293,696

3-SUBSTITUTED

PHENYLTHIAZOLO[3,2':1,2]IMIDAZO[4,5-B]PYRIDINE-2-ALKANOIC ACIDS

Peter H. L. Wei, Springfield, and Stanley C. Bell, Penn Valley, both of Pa., assignors to American Home Products Corporation, New York, N.Y.


Filed Dec. 22, 1980, Ser. No. 218,903

Int. Cl.³ C07D 513/14

U.S. Cl. 546—83

2 Claims

1. A compound of the formula:



wherein

R₁ is hydrogen, lower alkyl of 1-4 carbon atoms, CF₃, NO₂ or halo;

R₂ is hydrogen, lower alkyl of 1-4 carbon atoms, lower alkoxy of 1-4 carbon atoms, hydroxy, CF₃, halo, cycloalkyl of 5-7 carbon atoms or phenyl;

R₃ is lower alkoxy of 1-4 carbon atoms, hydroxy or amino; and

n is 1-3.

4,293,697

PHARMACOLOGICALLY ACTIVE THIOUREA AND UREA COMPOUNDS

Graham J. Durant, Welwyn Garden City; John C. Emmett, Codicote, and Charon R. Ganellin, Welwyn Garden City, all of England, assignors to Smith, Kline & French Laboratories Limited, Welwyn Garden City, England


Division of Ser. No. 940,547, Sep. 8, 1978, Pat. No. 4,230,865, which is a division of Ser. No. 805,491, Jun. 10, 1977, Pat. No. 4,137,234, which is a division of Ser. No. 638,005, Dec. 5, 1975, Pat. No. 4,053,473, which is a division of Ser. No. 451,333, Mar. 14, 1974, Pat. No. 3,950,353, which is a continuation-in-part of Ser. No. 290,584, Sep. 20, 1972, abandoned, which is a continuation-in-part of Ser. No. 230,451, Feb. 29, 1972, abandoned. This application Apr. 9, 1980, Ser. No. 138,637

Claims priority, application United Kingdom, Mar. 9, 1971, 6352/71; Jul. 22, 1971, 34334/71; Feb. 3, 1972, 136/72; Aug. 8, 1972, 37015/72


U.S. Cl. 546—121

6 Claims

1. A compound of the formula:



(I) wherein A is such that there is formed together with the carbon atom shown an unsaturated heterocyclic nucleus, said unsaturated heterocyclic nucleus being a 3-(5,6,7,8-tetrahydroimidazo[1,5-a]pyridine) ring; X₁ is hydrogen, lower alkyl, hydroxyl, trifluoromethyl, benzyl, halogen, amino or



X₂ is hydrogen or when X₁ is lower alkyl, lower alkyl or halogen; k is 0 to 2 and m is 2 or 3, provided that the sum of k and m is 3 or 4; Y is oxygen, sulphur or NH; E is oxygen or sulphur; and R₁ is hydrogen, lower alkyl, benzoyl or di-lower alkylamino-lower alkyl or a pharmaceutically acceptable addition salt thereof.

4,293,698

COMPOUND FOR CONTROLLING DIELECTRIC CONSTANT OF LIQUID CRYSTAL

Kazuhisa Toriyama, Mobara; Tsujiaki Hata, Yokohama; Shinji Hasegawa, and Ken Sasaki, both of Mobara, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Filed Jan. 10, 1980, Ser. No. 111,104


Claims priority, application Japan, Jan. 12, 1979, 54-1351

Int. Cl.³ C09K 3/34; G02F 1/13; C07D 213/02

U.S. Cl. 546—301

10 Claims

1. A compound for controlling the dielectric constant of liquid crystals consisting of a 4-p-alkylbenzoyloxy pyridine oxide represented by the general formula



wherein R is a normal alkyl group having 1 to 9 carbon atoms.

4,293,699

PHARMACOLOGICALLY ACTIVE GUANIDINE COMPOUNDS

Graham J. Durant, Welwyn Garden City; John C. Emmett, Codicote, and Charon R. Ganellin, Welwyn Garden City, all of England, assignors to Smith Kline & French Laboratories Limited, Welwyn Garden City, England

Division of Ser. No. 948,358, Oct. 4, 1978, Pat. No. 4,228,291, which is a division of Ser. No. 764,921, Feb. 2, 1977, Pat. No. 4,137,237, which is a division of Ser. No. 637,496, Dec. 4, 1975, Pat. No. 4,022,797, which is a division of Ser. No. 450,957, Mar. 14, 1974, Pat. No. 3,950,333, which is a continuation-in-part of Ser. No. 290,584, Sep. 20, 1972, abandoned, which is a continuation-in-part of Ser. No. 230,451, Feb. 29, 1972, abandoned. This application Mar. 21, 1980, Ser. No. 132,605


Claims priority, application Ireland, Feb. 3, 1972, 136/72

Int. Cl.³ C07C 235/04, 235/06, 471/02


U.S. Cl. 546—121

7 Claims

1. A compound of the formula:



wherein A is such that there is formed together with the carbon atom shown an unsaturated heterocyclic nucleus, said unsaturated heterocyclic nucleus being a benzimidazole or 3-(5,6,7,8-tetrahydroimidazo[1,5-a]pyridine) ring; X₁ is hydrogen, lower alkyl, hydroxyl, trifluoromethyl, benzyl, halogen, amino or



X₂ is hydrogen or when X₁ is lower alkyl, lower alkyl or halogen; k is 0 to 2 and m is 2 or 3, provided that the sum of k and m is 3 or 4; Y is oxygen, sulphur or NH; E is NR₂; R₁ is hydrogen, lower alkyl or di-lower alkylamino-lower alkyl; and

R₂ is hydrogen, nitro or cyano, or a pharmaceutically acceptable addition salt thereof.

4,293,700

2,6-DIMETHYL-1,4-DIHYDROPYRIDINE-3,5-DICARBOXYLIC ACID ESTERS AND METHOD FOR PREPARING SAME

Yan R. Uldriks, ulitsa Darza, 2, kv. 2, Elgava; Ieva E. Preisa, ulitsa Lachplesha, 44/46, kv. 14, Riga; Gunar Y. Dubur, ulitsa Ierikju, 43, kv. 2, Riga; Aina A. Zidermane, ulitsa F. Engelsa, 11-a, kv. 9, Riga; Egils A. Biseniex, Talavas Gatve, 11, kv. 15, Riga, and Gunar D. Tirzits, ulitsa Zhagatu, 22, kv. 33, Riga, all of U.S.S.R.

Filed Apr. 3, 1980, Ser. No. 137,012


Claims priority, application U.S.S.R., Aug. 8, 1978, 2655083[I]

Int. Cl.³ C07D 213/80, 211/90

U.S. Cl. 546—321

2 Claims

1. 2,6-dimethyl-1,4-dihydropyridine-3,5-dicarboxylic acid esters of the general formula:



wherein R is cycloterpenyl, or branched or linear C₁-C₅ alkyl substituted by COOX wherein X is hydrogen or a salt forming cation, or methyl substituted by phenyl or carboxylate.

4,293,701

N-(BENZENESULFONYL) CARBAMATES - HERBICIDAL ANTIDOTES

Ferenc M. Pallos, Walnut Creek, and Edmund J. Gaughan, Berkeley, both of Calif., assignors to Stauffer Chemical Company, Westport, Conn.


Division of Ser. No. 721,721, Sep. 13, 1976, Pat. No. 4,230,874, which is a continuation-in-part of Ser. No. 619,114, Oct. 2, 1975, abandoned. This application Dec. 31, 1979, Ser. No. 108,889

Int. Cl.³ C07D 213/55; C07C 143/67

U.S. Cl. 546—335

6 Claims

1. Compounds according to the formula



in which X is chloro, and methyl;

n is an integer from 1 to 3 inclusive, provided that when X is bromo, trifluoromethyl, or methoxy, n is 1; and R is selected from 4-chlorophenylthiomethyl, 4-chlorobenzyl, 4-methoxybenzyl, 3-pyridylmethyl, and phenoxyethyl.

4,293,702

METHOD FOR PREPARING 4-SUBSTITUTED-N-METHYLBENZOTHAZOLONE DERIVATIVES

Takeaki Umemura; Haruki Morino, both of Takarazuka; Tetsubiko Watanabe, Minoo, and Tamon Uematsu, Toyonaka, all of Japan, assignors to Sumitomo Chemical Company, Limited, Osaka, Japan

Filed Jun. 18, 1979, Ser. No. 49,634


Claims priority, application Japan, Jun. 19, 1978, 53-74614; Jun. 20, 1978, 53-75111; Jun. 20, 1978, 53-75112; Jul. 10, 1978, 53-84161; Jul. 11, 1978, 53-84859

Int. Cl.³ C07D 277/68; A61K 31/425


U.S. Cl. 548-165

9 Claims

1. A process for producing N-alkylbenzothiazolone derivatives having the formula:



wherein R₁ is a hydrogen atom, chlorine atom, bromine atom, fluorine atom or methyl group, and R₂ is a C₁-C₅ alkyl group by heating a 2-alkoxybenzothiazole derivative at temperatures of 100°-150° C. without a solvent or by heating said derivative in a solvent at about the refluxing temperature of the solvent, said derivative having the formula:



wherein R₁ and R₂ are defined above, in the presence of a catalytic amount of a catalyst selected from (1) tertiary amines and salts thereof, which amines are selected from the group consisting of saturated hydrocarbyl aliphatic amines and diamines, dimethylaniline, N, N-diethylaniline, pyridine, 1,5-diazabicyclo[3.4.0], and 1,5-diazabicyclo[5.4.0]undecene-5 and the HCl and HBr and H₂SO₄ salts thereof; (2) a quaternary ammonium compound selected from the groups consisting of tetra-n-butylammonium bromide, tetra-n-butylammonium chloride, tetra-n-butylammonium iodide, tetra-n-butylammonium hydroxide, triethylbenzylammonium chloride, triethylbenzylammonium bromide, triethylbenzylammonium iodide, trimethylbenzylammonium chloride, n-cetylpyridinium bromide, tetra-n-butylammonium hydrogen sulfate and tetra-n-butylammonium perchlorate; and (3) a dialkyl sulfate selected from the group consisting of dimethyl sulfate and diethyl sulfate.

4,293,703

IMIDAZOLE OR IMIDAZOLINE SUBSTITUTED UREAS

William A. Bolhofer, Frederick, Pa., assignor to Merck & Co., Inc., Rahway, N.J.

Division of Ser. No. 4,252, Jan. 18, 1979, Pat. No. 4,241,072.


This application Jul. 7, 1980, Ser. No. 166,670

Int. Cl.³ C07D 471/04, 235/30, 233/48, 233/88

U.S. Cl. 548-337

4 Claims

1. A compound having the formula:



wherein R is imidazole or imidazoline, and wherein said heterocyclic rings may be fused to a benzo or pyridyl moiety and also wherein said groups may be substituted with one, two or three loweralkyl groups; and R₁, R₂, R₃ and R₄ are independently loweralkyl, and the pharmaceutically acceptable acid addition salts thereof.

4,293,704

NOVEL

2-SUBSTITUTED-3,4-EPOXYCYCLOPENTAN-1-ONES, 2-SUBSTITUTED-3,4-EPOXYCYCLOPENTAN-1-OLS, AND VARIOUS 2-SUBSTITUTED-CYCLOPENTENONES

Karel F. Bernady, Somerville, N.J.; Middleton B. Floyd, Jr., Suffern; John F. Poletto, Nanuet, both of N.Y.; Robert E. Schaub, Upper Saddle River, and Martin J. Weiss, Oradell, both of N.J., assignors to American Cyanamid Company, Stamford, Conn.


Continuation of Ser. No. 616,790, Sep. 25, 1975, which is a continuation-in-part of Ser. No. 355,101, Apr. 27, 1973, abandoned. This application Jan. 28, 1980, Ser. No. 115,833

Int. Cl.³ C07F 7/18

U.S. Cl. 556-442

7 Claims

1. A compound of the formula:



wherein p is an integer from 2 to 6, inclusive, and J is tri(lower alkyl)silyl.

4,293,705

13,14-DEHYDRO-11-DEOXY-PROSTAGLANDINS AND PROCESS FOR THEIR PREPARATION

Carmelo Gandolfi; Renato Pellegata; Franco Faustini, and Angelo Fumagalli, all of Milan, Italy, assignors to Farmitalia Carlo Erba S.p.A., Milan, Italy

Division of Ser. No. 825,783, Aug. 18, 1977, which is a division of Ser. No. 664,472, Mar. 8, 1976. This application Feb. 19, 1980, Ser. No. 122,276


Claims priority, application Italy, Mar. 14, 1975, 21264 A/75

Int. Cl.³ C07C 177/00

U.S. Cl. 560-53

16 Claims

1. Optically active compounds of the formula:



wherein

R is a member selected from the group consisting of hydrogen, a C₁-C₁₂ alkyl group, and a cation of a pharmaceutically acceptable base;

one of R₁ and R₂ is hydrogen and the other is hydroxy or acyloxy or R₁ and R₂ together form an oxo group; one of R₃ and R₄ is hydrogen and the other is hydroxy; R₅ and R₆ are independently selected from the group consisting of hydrogen, fluorine and C₁-C₄ alkyl, provided that when one of them is C₁-C₄ alkyl, the other is hydrogen or fluorine and when one of them is fluorine, the other is C₁-C₄ alkyl;

E is selected from the group consisting of -(CH₂)_n-, wherein n is an integer of 1 to 6, and -(CH₂)_n-O-(CH₂)_n- where n₁ and n₂ are independently selected from the group consisting of zero, 1, 2 and 3 provided that at least one of n₁ and n₂ is at least 1;

φ is a member selected from the group consisting of phenyl and phenyl substituted by at least one substituent selected from the group consisting of halogen, C₁-C₄ alkoxy, phenyl, and trihalomethyl;

and wherein the chains bound to the carbon atoms in the 8- and 12-positions have a trans-configuration.

4,293,706

PREPARATION OF N-BENZYLOXYCARBONYL ASPARTIC ACID

Susan B. Gorman, Barrington; Ralph B. Thompson, Oakbrook, and Edward E. Yonan, Carol Stream, all of Ill., assignors to PPG Industries, Inc., Pittsburgh, Pa.

Filed Jun. 19, 1980, Ser. No. 161,175

Int. Cl.³ C07C 125/06

U.S. Cl. 560-163

15 Claims

1. A method for preparing N-benzoyloxycarbonyl aspartic acid substantially free of N-benzoyloxycarbonyl aspartyl aspartic acid, which comprises:

- introducing a stoichiometric amount of benzyl chloroformate gradually into an aqueous solution of alkali metal salt of aspartic acid at temperatures of between about 10° C. and about 45° C. while maintaining the pH of the aqueous solution at between 10.75 and 11.75, and
- acidifying the resulting reaction mixture, thereby to produce N-benzoyloxycarbonyl aspartic acid substantially free of N-benzoyloxycarbonyl aspartyl aspartic acid.

4,293,707

PROCESS FOR PREPARING TRICHLOROPHENOXY ALKANOIC ACID AND HYDROLYZABLE DERIVATIVES THEREOF FREE OF CHLORINATED DIBENZO-P-DIOXINS

Sidney B. Richter, Akron, and William S. Grove, Doylestown, both of Ohio, assignors to PPG Industries, Inc., Pittsburgh, Pa.


Filed Jun. 4, 1979, Ser. No. 45,549

Int. Cl.³ C07C 59/56

U.S. Cl. 562-472

5 Claims

1. In a process for preparing 2,4,5-trichlorophenoxy alkanolic acid, selected from 2,4,5-trichlorophenoxy acetic acid and 2-(2,4,5-trichlorophenoxy) propionic acid including hydrolyzable aliphatic esters and amides of said acids, by reacting in a liquid alkaline reaction medium containing an inorganic or organic base, a chlorinated phenol with at least an equimolar amount of alpha halo compound represented by the formula:



wherein X represents bromine, chlorine or iodine; R represents hydrogen or methyl; and Y represents hydroxy or a hydrolyzable substituent selected from an aliphatic radical containing up to 20 carbon atoms, amide or mono- or disubstituted amide the substituent of which contains up to 20 carbon atoms, and chlorinating the reaction product in the liquid phase, the improvement wherein the alpha halo compound is reacted with a chlorophenol selected from 3-chlorophenol and 3,4-dichloro-

phenol so as to obtain a pure product that is free of analytically detectable amounts of chlorinated dibenzo-p-dioxins.

4,293,708

13,14-DIDEHYDRO-11-DEOXY-11-HYDROXYMETHYL- 19-OXO-PGE₁ COMPOUNDS

John C. Sih, Kalamazoo, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.


Division of Ser. No. 25,879, Apr. 2, 1979. This application Mar. 20, 1980, Ser. No. 131,969

Int. Cl.³ C07C 177/00

U.S. Cl. 562-503

4 Claims

1. A compound of the formula



wherein D is

- (CH₂)₃-(CH₂)_g-CH₂-, or
 - (CH₂)₃-(CH₂)_g-CF₂-;
- wherein g is zero, one, two, or three; wherein Q is α-OH;β-R₅ or α-R₅;β-OH, wherein R₅ is hydrogen or methyl; wherein R₆ is
- hydrogen,
 - alkyl of one to 12 carbon atoms, inclusive,
 - cycloalkyl of 3 to 10 carbon atoms, inclusive,
 - aralkyl of 7 to 12 carbon atoms, inclusive,
 - phenyl,
 - phenyl substituted with one, 2, or 3 chloro or alkyl groups of one to 3 carbon atoms, inclusive,
 - (p-Ph)-CO-CH₃,
 - (p-Ph)-NH-CO-(p-Ph)-NH-CO-CH₃,
 - (p-Ph)-NH-CO-(p-Ph),
 - (p-Ph)-NH-CO-CH₃,
 - (p-Ph)-NH-CO-NH₂,
 - (p-Ph)-CH=N-NH-CO-NH₂,
 - β-naphthyl,
 - CH₂-CO-R₂₈,
- wherein (p-Ph) is para-phenyl or inter-para-phenylene, wherein R₂₈ is phenyl, p-bromophenyl, p-biphenyl, p-nitrophenyl, p-benzamidophenyl, or 2-naphthyl, or
- a pharmacologically acceptable cation;
- wherein R₃ and R₄ are hydrogen, methyl, or fluoro, being the same or different, with the proviso that one of R₃ and R₄ is fluoro only when the other is hydrogen or fluoro; and wherein X is -C≡C-.

4,293,709

13,14-DIHYDRO-9-DEOXY-9-METHYLENE-19-OXO- PGF₂ COMPOUNDS

John C. Sih, Kalamazoo, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.


Division of Ser. No. 25,879, Apr. 2, 1979. This application Mar. 20, 1980, Ser. No. 131,986

Int. Cl.³ C07C 177/00

U.S. Cl. 562-503

4 Claims

1. A compound of the formula



wherein D is

- (1) $\text{cis-CH=CH-CH}_2\text{-(CH}_2\text{)}_g\text{-CH}_2\text{-}$,
- (2) $\text{cis-CH=CH-CH}_2\text{-(CH}_2\text{)}_g\text{-CF}_2\text{-}$,
- (3) $\text{cis-CH}_2\text{-CH=CH-CH}_2\text{-CH}_2\text{-}$, or
- (4) $\text{trans-(CH}_2\text{)}_3\text{-CH=CH-}$;

wherein g is zero, one, two, or three;

wherein Q is $\alpha\text{-OH}:\beta\text{-R}_5$ or $\alpha\text{-R}_5:\beta\text{-OH}$, wherein R_5 is hydrogen or methyl;

wherein R_6 is

- (a) hydrogen,
- (b) alkyl of one to 12 carbon atoms, inclusive,
- (c) cycloalkyl of 3 to 10 carbon atoms, inclusive,
- (d) aralkyl of 7 to 12 carbon atoms, inclusive,
- (e) phenyl,
- (f) phenyl substituted with one, 2, or 3 chloro or alkyl groups of one to 3 carbon atoms, inclusive,
- (g) -(p-Ph)-CO-CH_3 ,
- (h) $\text{-(p-Ph)-NH-CO-(p-Ph)-NH-CO-CH}_3$,
- (i) $\text{-(p-Ph)-NH-CO-(p-Ph)-}$,
- (j) $\text{-(p-Ph)-NH-CO-CH}_3$,
- (k) $\text{-(p-Ph)-NH-CO-NH}_2$,
- (l) $\text{-(p-Ph)-CH=N-NH-CO-NH}_2$,
- (m) $\beta\text{-naphthyl}$,
- (n) $\text{-CH}_2\text{-CO-R}_{28}$,

wherein (p-Ph) is para-phenyl or inter-para-phenylene, wherein R_{28} is phenyl, p-bromophenyl, p-biphenyl, p-nitrophenyl, p-benzamidophenyl, or 2-naphthyl, or

(o) a pharmacologically acceptable cation; wherein R_3 and R_4 are hydrogen, methyl, or fluoro, being the same or different, with the proviso that one of R_3 and R_4 is fluoro only when the other is hydrogen or fluoro; and wherein X is $\text{-CH}_2\text{CH}_2\text{-}$.

4,293,710

13,14-DIHYDRO-11-DEOXY-11-HYDROXYMETHYL-19-OXO-PGF₁ COMPOUNDS

John C. Sih, Kalamazoo, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.


Division of Ser. No. 25,879, Apr. 2, 1979. This application Mar. 20, 1980, Ser. No. 131,987

Int. Cl.³ C07C 177/00

U.S. Cl. 562-503

4 Claims

1. A compound of the formula



wherein D is

- (1) $\text{cis-CH=CH-CH}_2\text{-(CH}_2\text{)}_g\text{-CH}_2\text{-}$,
- (2) $\text{cis-CH=CH-CH}_2\text{-(CH}_2\text{)}_g\text{-CF}_2\text{-}$,
- (3) $\text{cis-CH}_2\text{-CH=CH-CH}_2\text{-CH}_2\text{-}$, or
- (4) $\text{trans-(CH}_2\text{)}_3\text{-CH=CH-}$;

wherein g is zero, one, two, or three;

wherein Q is $\alpha\text{-OH}:\beta\text{-R}_5$ or $\alpha\text{-R}_5:\beta\text{-OH}$, wherein R_5 is hydrogen or methyl;

wherein R_6 is

- (a) hydrogen,

- (b) alkyl of one to 12 carbon atoms, inclusive,
- (c) cycloalkyl of 3 to 10 carbon atoms, inclusive,
- (d) aralkyl of 7 to 12 carbon atoms, inclusive,
- (e) phenyl,
- (f) phenyl substituted with one, 2, or 3 chloro or alkyl groups of one to 3 carbon atoms, inclusive,
- (g) -(p-Ph)-CO-CH_3 ,
- (h) $\text{-(p-Ph)-NH-CO-(p-Ph)-NH-CO-CH}_3$,
- (i) $\text{-(p-Ph)-NH-CO-(p-Ph)-}$,
- (j) $\text{-(p-Ph)-NH-CO-CH}_3$,
- (k) $\text{-(p-Ph)-NH-CO-NH}_2$,
- (l) $\text{-(p-Ph)-CH=N-NH-CO-NH}_2$,
- (m) $\beta\text{-naphthyl}$,
- (n) $\text{-CH}_2\text{-CO-R}_{28}$,

wherein (p-Ph) is para-phenyl or inter-para-phenylene, wherein R_{28} is phenyl, p-bromophenyl, p-biphenyl, p-nitrophenyl, p-benzamidophenyl, or 2-naphthyl, or

(o) a pharmacologically acceptable cation;

wherein R_3 and R_4 are hydrogen, methyl, or fluoro, being the same or different, with the proviso that one of R_3 and R_4 is fluoro only when the other is hydrogen or fluoro; and

wherein X is $\text{-CH}_2\text{CH}_2\text{-}$.

4,293,711

INTER-OXA-19-OXO-PGE₁ COMPOUNDS

John C. Sih, Kalamazoo, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.


Division of Ser. No. 25,879, Apr. 2, 1979. This application Mar. 20, 1980, Ser. No. 132,209

Int. Cl.³ C07C 177/00

U.S. Cl. 562-503

4 Claims

1. A compound of the formula



wherein D is

- (1) $\text{(CH}_2\text{)}_3\text{-O-CH}_2\text{-}$,
- (2) $\text{(CH}_2\text{)}_3\text{-O-CF}_2\text{-}$, or
- (3) $\text{-CH}_2\text{-O-(CH}_2\text{)}_3\text{-}$;

wherein Q is $\alpha\text{-OH}:\beta\text{-R}_5$ or $\alpha\text{-R}_5:\beta\text{-OH}$, wherein R_5 is hydrogen or methyl;

wherein R_6 is

- (a) hydrogen,
- (b) alkyl of one to 12 carbon atoms, inclusive,
- (c) cycloalkyl of 3 to 10 carbon atoms, inclusive,
- (d) aralkyl of 7 to 12 carbon atoms, inclusive,
- (e) phenyl,
- (f) phenyl substituted with one, 2, or 3 chloro or alkyl groups of one to 3 carbon atoms, inclusive,
- (g) -(p-Ph)-CO-CH_3 ,
- (h) $\text{-(p-Ph)-NH-CO-(p-Ph)-NH-CO-CH}_3$,
- (i) $\text{-(p-Ph)-NH-CO-(p-Ph)-}$,
- (j) $\text{-(p-Ph)-NH-CO-CH}_3$,
- (k) $\text{-(p-Ph)-NH-CO-NH}_2$,
- (l) $\text{-(p-Ph)-CH=N-NH-CO-NH}_2$,
- (m) $\beta\text{-naphthyl}$,
- (n) $\text{-CH}_2\text{-CO-R}_{28}$,

wherein (p-Ph) is para-phenyl or inter-para-phenylene, wherein R_{28} is phenyl, p-bromophenyl, p-biphenyl, p-nitrophenyl, p-benzamidophenyl, or 2-naphthyl, or

(o) a pharmacologically acceptable cation;

wherein R_3 and R_4 are hydrogen, methyl, or fluoro, being the same or different, with the proviso that one of R_3 and R_4 is fluoro only when the other is hydrogen or fluoro; and

wherein X is cis- or trans- CH=CH- .

4,293,712

INTER-OXA-19-OXO-PGF₁ COMPOUNDS

John C. Sih, Kalamazoo, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.


Division of Ser. No. 25,879, Apr. 2, 1979. This application Mar. 20, 1980, Ser. No. 132,210

Int. Cl.³ C07C 177/00

U.S. Cl. 562-503

4 Claims

1. A compound of the formula



wherein D is

- (1) $\text{-(CH}_2\text{)}_3\text{-O-CH}_2\text{-}$,
- (2) $\text{-(CH}_2\text{)}_3\text{-O-CF}_2\text{-}$, or
- (3) $\text{-CH}_2\text{-O-(CH}_2\text{)}_3\text{-}$;

wherein Q is $\alpha\text{-OH}:\beta\text{-R}_5$ or $\alpha\text{-R}_5:\beta\text{-OH}$, wherein R_5 is hydrogen or methyl;

wherein R_6 is

- (a) hydrogen,
- (b) alkyl of one to 12 carbon atoms, inclusive,
- (c) cycloalkyl of 3 to 10 carbon atoms, inclusive,
- (d) aralkyl of 7 to 12 carbon atoms, inclusive,
- (e) phenyl,
- (f) phenyl substituted with one, 2, or 3 chloro or alkyl groups of one to 3 carbon atoms, inclusive,
- (g) -(p-Ph)-CO-CH_3 ,
- (h) $\text{-(p-Ph)-NH-CO-(p-Ph)-NH-CO-CH}_3$,
- (i) $\text{-(p-Ph)-NH-CO-(p-Ph)-}$,
- (j) $\text{-(p-Ph)-NH-CO-CH}_3$,
- (k) $\text{-(p-Ph)-NH-CO-NH}_2$,
- (l) $\text{-(p-Ph)-CH=N-NH-CO-NH}_2$,
- (m) $\beta\text{-naphthyl}$,
- (n) $\text{-CH}_2\text{-CO-R}_{28}$,

wherein (p-Ph) is para-phenyl or inter-para-phenylene, wherein R_{28} is phenyl, p-bromophenyl, p-biphenyl, p-nitrophenyl, p-benzamidophenyl, or 2-naphthyl, or

(o) a pharmacologically acceptable cation;

wherein R_3 and R_4 are hydrogen, methyl, or fluoro, being the same or different, with the proviso that one of R_3 and R_4 is fluoro only when the other is hydrogen or fluoro; and

wherein X is cis- or trans- CH=CH- .

4,293,713

NOVEL 1,1,3,5-SUBSTITUTED BIURET COMPOUND AND A PHARMACEUTICAL COMPOSITION CONTAINING THE SAME

Hajime Fujimura, Kyoto; Yasuzo Hiramatsu, Otsu; Takahiro Yabuuchi, Takarazuka; Masakatu Hisaki, Hikone; Katsuo Takikawa, Naruto; Takaji Honna, Tokushima; Hidekazu Miyake, Tokushima, and Makoto Kajitani, Tokushima, all of Japan, assignors to Taiho Pharmaceutical Company Limited, Tokyo, Japan

Filed Mar. 27, 1980, Ser. No. 134,556


Claims priority, application Japan, Mar. 31, 1979, 54-38790

Int. Cl.³ A61K 31/17; C07C 127/24

U.S. Cl. 564-38

33 Claims

1. A 1,1,3-trimethyl-5-substituted biuret compound of the formula:



wherein

R^3 is a cyclohexyl group or a phenyl group which may be unsubstituted or may have at least one substituent selected from the group consisting of chlorine, bromine, fluorine, methyl, trifluoromethyl, dimethylamino, methoxy, methylthio, nitro and acetyl.

4,293,714

COPOLYMERIZABLE, ULTRAVIOLET LIGHT ABSORBER 4-ALKOXY-2'-ALLYLOXYBENZAZINES

Bruce A. Gruber, Worthington, Ohio, and Donald H. Lorenz, Basking Ridge, N.J., assignors to GAF Corporation, New York, N.Y.


Filed Mar. 20, 1980, Ser. No. 132,194

Int. Cl.³ C07C 109/04

U.S. Cl. 564-249

10 Claims

1. A copolymerizable ultraviolet light absorber compound having the formula:



where R is alkylene, oxyalkylene, alkyleneoxyalkylene, said alkylene group being attached to the oxygen of the phenolic, or phenylene, which R groups are of up to 10 carbon atoms and are unsubstituted or substituted with hydroxy;

R' and R'' are independently hydrogen or alkyl $\text{C}_1\text{-C}_6$; and R''' is alkyl $\text{C}_1\text{-C}_6$, or alkoxy $\text{C}_1\text{-C}_6$.

4,293,715

PREPARATION OF ω -AZOLYL-ACETOPHENONE OXIDE ETHERS EMPLOYING ω -HALOGENO-ACETOPHENONE OXIDE ETHERS

Wolfgang Krämer, Wuppertal, Fed. Rep. of Germany, assignor to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Feb. 11, 1980, Ser. No. 120,168


Claims priority, application Fed. Rep. of Germany, Mar. 1, 1979, 2907972

Int. Cl.³ C07C 131/00; C07D 233/61, 249/08

U.S. Cl. 564-256

6 Claims

1. An ω -halogeno-acetophenone oxime ether of the formula



in which

R is fluorine, chlorine, bromine, nitro, cyano, alkyl or alkylsulphonyl with 1 to 4 carbon atoms, alkoxy or alkylthio with 1 to 2 carbon atoms, halogenoalkyl with up to 4 carbon atoms and up to 5 halogen atoms,

R' is alkyl, alkenyl or alkynyl with up to 4 carbon atoms, cycloalkylalkyl with 5 to 7 carbon atoms in the cycloalkyl moiety and 1 to 2 carbon atoms in the alkyl moiety, the cycloalkyl moiety being optionally substituted by alkyl

with 1 to 4 carbon atoms, benzyl, styryl, or benzyl or styryl substituted by halogen, cyano, nitro, amino, alkyl with 1 to 4 carbon atoms, phenyl, phenoxy and/or halogenoalkyl with up to 2 carbon atoms and up to 3 identical or different halogen atoms,
n is 1, 2 or 3, and
Hal is halogen.

4,293,716 PROCESS FOR PREPARING ALKYLDIMETHYLAMINES

Harold E. Swift, Gibsonia; Robert A. Innes, Monroeville, both of Pa., and Phillip Adams, Murray Hill, N.J., assignors to Gulf Research & Development Company, Pittsburgh, Pa. and Kewanee Industries, New York, N.Y.

Filed Dec. 31, 1979, Ser. No. 108,479
Int. Cl.³ C07C 85/06

U.S. Cl. 564—480

22 Claims

1. In a process wherein an alcohol or mixture of alcohols is reacted with dimethylamine in the presence of copper catalyst to obtain alkyldimethylamine or alkenyldimethylamine by passing said reactants in the vapor phase through a fixed bed of such catalyst, the improvement which comprises substantially decreasing the formation of byproduct alkyldimethylamine by introducing into the reaction zone the dimethylamine and alcohol in a molar ratio of about 3:1 to about 1:1 and carrying out the reaction in the additional presence of about 0.5 to about 1.5 weight percent of an oxide of a Group I metal.


4,293,717
PROCESS FOR PREPARING ALDEHYDES AND DIOLS
Helmut Waldmann; Wulf Schwerdtel, both of Leverkusen, and Wolfgang Swodenk, Odenthal-Glöbusch, all of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany
Continuation of Ser. No. 743,546, Nov. 22, 1976, abandoned, which is a continuation of Ser. No. 563,263, Mar. 28, 1975, abandoned, which is a continuation of Ser. No. 322,321, Jan. 10, 1973, abandoned. This application Feb. 5, 1979, Ser. No. 9,019
Claims priority, application Fed. Rep. of Germany, Jan. 13, 1972, 2201456

Int. Cl.³ C07C 47/21, 47/20, 29/03

U.S. Cl. 568—485

19 Claims

1. Process for preparing a diol and an aldehyde which comprises reacting an olefin having the formula



wherein R_1 and R_2 , which may be the same or different, are:
hydrogen;
phenyl which can be substituted by C_1 - C_6 alkyl, C_1 - C_6 alkoxy;
a straight-chain or branched alkyl, which can be substituted by C_1 - C_6 alkoxy or phenyl;
or wherein the radicals R_1 and R_2 together with the C—C double bond represent a carbocyclic ring with up to 24 carbon atoms; with a non-aqueous solution of between 3 and 30% by weight hydrogen peroxide in an alcohol, ester, acid alkylamide or an ester of alkylamide or phosphoric, phosphonic or phosphinic acid solvent, in the presence of an acetate, benzoate, carbonyl, acetylacetone or a naphthenate of a metal selected from the group of vanadium and molybdenum, at a temperature in the range of from -80° to $+100^\circ$ C., said metal compound being added in quantity of from 0.01 to 10 mol percent relative to the quantity of hydrogen peroxide.

4,293,718
PREPARATION OF ACETALDEHYDE
Jean Gauthier-Lafaye, Lyons, and Robert Perron, Charly, both of France, assignors to Rhone-Poulenc Industries, Paris, France

Filed Oct. 23, 1979, Ser. No. 87,631
Claims priority, application France, Oct. 31, 1978, 78 31634
Int. Cl.³ C07C 45/49

U.S. Cl. 568—487

22 Claims

1. In a process for the preparation of acetaldehyde by carbonylation of methanol, the improvement which comprises (i) carbonylating methanol with a gaseous admixture of hydrogen and carbon monoxide, (ii) with the hydrogen comprising at least 25 mol percent of said admixture, and in the presence of (iii) a catalytic amount of a catalyst system comprising (iiia) cobalt, (iiib) an iodide selected from the group consisting of alkali metal iodides, alkaline earth metal iodides, ammonium iodides, quaternary ammonium iodides, phosphonium iodides and quaternary phosphonium iodides, and (iiic) a halogen-containing promoter differing from said iodide (iiib), said halogen-containing promoter being a compound formed by replacing at least one hydrogen atom of an organic molecule which only contains carbon and hydrogen with a halogen or being a compound which, under the reaction conditions, is capable of leading to the production of a methyl halide in the reaction medium and which is selected from the group consisting of Cl_2 , Br_2 , I_2 , HCl , HBr , HI , $CoBr_2$ and CoI_2 .

22. A process for the preparation of acetaldehyde which comprises carbonylating methanol in the liquid phase with a gaseous admixture of hydrogen and carbon monoxide with the hydrogen comprising at least 25 mol percent of the admixture, at a temperature in the range of about 180° - 230° C. and under a total pressure in the range of about 75-350 bars, and

in the presence of a catalyst system comprising (i) cobalt, which is employed in an amount in the range of about 0.01 to about 1 milligram-atom of cobalt per mol of methanol, (ii) an alkali metal iodide and (iii) methyl iodide, wherein the ratio of gram-ions of I^- originating from the alkali metal iodide (ii) to gram-atoms of cobalt (i) is in the range of about 20 to 200 and the ratio of gram-molecules of CH_3I (iii) to gram-ions of I^- originating from the alkali metal iodide (ii) is in the range of about 0.01 to 0.08.


4,293,719
MANUFACTURE OF HYDROPEROXIDES
Louis J. Velenyi, Lyndhurst; Serge R. Dolhyj, Parma, and Marcia H. Sundeen, Cleveland Hts., all of Ohio, assignors to The Standard Oil Company, Cleveland, Ohio

Filed Mar. 31, 1980, Ser. No. 135,306
Int. Cl.³ C07C 179/035


U.S. Cl. 568—573

12 Claims

1. A process for manufacturing an aryl hydroperoxide of the formula




from a corresponding aryl compound of the formula




where

Ar is an aryl radical, each R is independently hydrogen or a radical of the formula



each R' is a radical of the formula



R'' and R''' are independently hydrogen or alkyl radicals of 1 to 3 carbon atoms with the proviso that both cannot be simultaneously hydrogen,
m is 1 or 2 with the proviso that when m is 1, R is not hydrogen, and when m is 2, at least one R is not hydrogen, and
n is 1 or 2,

the process comprising contacting (II) with molecular oxygen at hydroperoxidative conditions in the presence of an initiator and a catalyst selected from the group consisting of C_{14} - C_{16} straight-chain, primary alkyl amines amine and poly(vinyl)pyrrolidone having a weight average molecular weight of at least about 1,000.


4,293,720
PROCESS FOR PREPARATION OF HYDROPEROXIDES
Tetsuo Iwaki; Yukio Takahashi, both of Ohtake; Shuji Moriu-chi, and Hisamitsu Kaneko, both of Iwakuni, all of Japan, assignors to Mitsui Petrochemical Industries, Ltd., Tokyo, Japan

Filed May 2, 1980, Ser. No. 146,080
Claims priority, application Japan, May 9, 1979, 54-55664
Int. Cl.³ C07C 179/035

U.S. Cl. 568—575

8 Claims

1. A process for the preparation of aromatic hydroperoxides which comprises reacting an aromatic compound represented by the following formula:



wherein R_1 stands for a secondary alkyl group having 3 to 4 carbon atoms, R_2 stands for a primary alkyl group having up to 4 carbon atoms, and n and m are numbers of 1 or 2 with the proviso that the sum of n and m does not exceed 3, with a molecular oxygen-containing gas in the presence of a basic aqueous solution and a copper compound catalyst at a temperature of 50° to 150° C., wherein an aqueous solution containing (A) cupric carbonate and (B) at least one member of the group consisting of alkali metal carbonate and an alkali metal bicarbonate is prepared outside the oxidation system and said aqueous solution is supplied to the oxidation system, and the concentration of cupric carbonate in the aqueous phase in the oxidation system is maintained at 0.01 to 5 ppm as the copper atom.

4,293,721
PROCESS FOR THE PURIFICATION OF ALKALINE
SOLUTION OF LOWER ALKYL ALCOHOLS
CONTAINING ALKALI METAL ALKOXIDES
Sudhir K. Mendiratta, Cleveland, Tenn., assignor to Olin Corporation, New Haven, Conn.

Filed Aug. 4, 1980, Ser. No. 175,175
Int. Cl.³ C07C 29/76, 29/88

U.S. Cl. 568—916

14 Claims

1. A process for purifying an alkaline solution of a lower alkyl alcohol containing as impurities an alkali metal alkoxide and an alkali metal hydroxide which comprises:

(a) treating said alkaline solution of a lower alkyl alcohol with an anhydrous hydrogen halide to react with said alkali metal alkoxide and said alkali metal hydroxide to

provide a neutral solution comprised of said lower alkyl alcohol, an alkali metal halide and water;
(b) removing said alkali metal halide from said neutral solution to obtain a substantially salt-free solution comprised of said lower alkyl alcohol and water; and
(c) contacting said substantially salt-free solution with a zeolite molecular sieve to remove said water and to recover a substantially anhydrous solution of said lower alkyl alcohol.


4,293,722
PROCESS FOR CONVERSION OF PROPANE TO
GASOLINE

Dennis J. Ward, South Barrington, and Bipin V. Vora, Elk Grove Village, both of Ill., assignors to UOP Inc., Des Plaines, Ill.

Filed Feb. 14, 1980, Ser. No. 121,353
Int. Cl.³ C07C 2/08, 5/32

U.S. Cl. 585—330

4 Claims



1. A hydrocarbon conversion process which comprises the steps of:

- passing a feed stream comprising propane and a hereinafter characterized recycle stream into a dehydrogenation zone operated at propane dehydrogenation conditions and thereby forming a dehydrogenation zone effluent stream comprising hydrogen, propane and propylene;
- passing the entire dehydrogenation zone effluent stream into a catalytic condensation zone operated at conditions which effect the conversion of propylene into C_9 hydrocarbons and thereby forming a catalytic condensation zone effluent stream which comprises hydrogen, propane, C_6 hydrocarbons and C_9 hydrocarbons;
- passing the catalytic condensation zone effluent stream, a first absorber bottoms stream and a stripping column overhead stream into a vapor-liquid separation zone;
- passing a vapor stream comprising hydrogen and propane and which is withdrawn from the vapor-liquid separation zone into a first absorber and contacting the vapor stream at absorption-promoting conditions with a first lean liquid hydrocarbon stream comprising C_6 and C_9 hydrocarbons and thereby producing the first absorber bottoms stream, which comprises propane and C_9 hydrocarbons, and a first absorber vapor stream comprising hydrogen, propane and C_6 hydrocarbons;
- passing a liquid stream comprising C_6 and C_9 hydrocarbons and which is withdrawn from the vapor-liquid separation zone into a stripping column operated at conditions which effect the separation of the liquid stream into a stripping column overhead stream comprising hydrogen and propane and a stripping column bottoms stream which comprises propane, C_6 hydrocarbons and C_9 hydrocarbons;
- passing a first portion of the stripping column bottoms stream into the first absorber as the previously specified first lean liquid hydrocarbon stream, and passing a second portion of the stripping column bottoms stream into a depropanizer column operated at conditions which effect the separation of the entering hydrocarbons into a depro-

pantizer overhead stream comprising propane and a net depropanizer bottoms stream removed from the process as a product stream which comprises C₆ and C₉ hydrocarbons and is substantially free of propane;

- (g) removing a first portion of the first absorber vapor stream from the process as an off gas stream, and passing a second portion of the first absorber vapor stream into a second absorber and contacting the second portion of the first absorber vapor stream with a second lean liquid hydrocarbon stream at absorption-promoting conditions and thereby producing a second absorber bottoms stream, which comprises propane and a second adsorber vapor stream;
- (h) passing the second absorber bottoms stream into the stripping column; and,
- (i) passing a first portion of the depropanizer overhead stream into the second absorber as the previously specified second lean liquid hydrocarbon stream, and combining a second portion of the depropanizer overhead stream and the second absorber vapor stream with the feed stream as the previously referred to recycle stream of step (a).

4,293,723

CONVERSION OF ISOBUTENE TO AROMATICS OR POLYISOBUTYLENE WITH MODIFIED GAMMA ALUMINA COMPOSITION

Lynn H. Slaugh, Houston, Tex., assignor to Shell Oil Company, Houston, Tex.

Division of Ser. No. 61,221, Jul. 27, 1979, Pat. No. 4,235,756.

This application Apr. 21, 1980, Ser. No. 142,591

Int. Cl.³ C07C 2/04; B01J 21/04

U.S. Cl. 585-407

2 Claims

1. A process for dehydrocoupling isobutene to aromatics which comprises contacting the isobutene at about 450° C.-650° C. with an aluminous composition prepared by a process which comprises impregnating a substantially dehydrated gamma alumina with aluminum hydride dissolved in an anhydrous, non-hydroxyl containing organic solvent, drying the impregnated alumina to remove the solvent and subsequently heating the impregnated alumina at a temperature of about 300° to about 900° C. in a nonoxidizing atmosphere wherein the aluminum hydride added ranges from about 3 to about 7 percent by weight measured as aluminum metal.

4,293,724

ALKYLATION OF AROMATICS WITH PROPYLENE AND HIGHER OLEFINS

David L. Beach, and Thaddeus P. Kobylinski, both of Gibsonia, Pa., assignors to Gulf Research & Development Company, Pittsburgh, Pa.

Filed May 21, 1980, Ser. No. 151,953

Int. Cl.³ C07C 2/66

U.S. Cl. 585-457

61 Claims

1. A process for alkylating an aromatic hydrocarbon with an alpha olefin which comprises contacting an alpha olefin having at least three carbon atoms and an aromatic hydrocarbon with a catalyst composition obtained by contacting (a) a refractory metal oxide/silica support wherein the silica content of said support is from about 2 to about 95 weight percent and the metal oxide content of said support is from about 5 to about 98 weight percent with (b) a tris(cyclopentadienyl)trinicke dicarbonyl.

4,293,725

USE OF METAL MODIFIED REFRACTORY METAL OXIDE/SILICA SUPPORTED NICKEL CLUSTER CATALYST TO OLIGOMERIZE ETHYLENE

David L. Beach, and Thaddeus P. Kobylinski, both of Gibsonia, Pa., assignors to Gulf Research & Development Company, Pittsburgh, Pa.

Filed May 21, 1980, Ser. No. 151,952

Int. Cl.³ C07C 2/02, 2/26

U.S. Cl. 585-523

85 Claims

1. A process for oligomerizing ethylene which comprises contacting ethylene with a catalyst composition obtained by contacting (1) a refractory metal oxide/silica support wherein the silica content of said support is from about 2 to about 95 weight percent and the metal oxide content of said support is from about 5 to about 98 weight percent with (2) a solution of a soluble salt whose cationic portion is selected from the group consisting of an alkali metal, an alkaline earth metal and a lanthanide and whose anionic portion is selected from the group consisting of a halide, a nitrate, an acetate and an acetylacetonate and (3) then contacting the metal modified support with a tris(cyclopentadienyl)trinicke dicarbonyl.

4,293,726

PROCESS FOR THE OLIGOMERIZATION OF PROPYLENE AND HIGHER OLEFINS

David L. Beach, and Thaddeus P. Kobylinski, both of Gibsonia, Pa., assignors to Gulf Research & Development Company, Pittsburgh, Pa.

Filed May 21, 1980, Ser. No. 151,950

Int. Cl.³ C07C 2/02, 2/26

U.S. Cl. 585-523

70 Claims

1. A process for oligomerizing an alpha olefin which comprises contacting an alpha olefin having at least three carbon atoms with a catalyst composition obtained by contacting (a) a refractory metal oxide/silica support wherein the silica content of said support is from about 2 to about 95 weight percent and the metal oxide content of said support is from about 5 to about 98 weight percent with (b) a tris(cyclopentadienyl)trinicke dicarbonyl.

4,293,727

PROCESS FOR THE OLIGOMERIZATION OF ETHYLENE

David L. Beach, Gibsonia, and James J. Harrison, Glenshaw, both of Pa., assignors to Gulf Research & Development Company, Pittsburgh, Pa.


Filed Aug. 18, 1980, Ser. No. 179,076

Int. Cl.³ C07C 2/02

U.S. Cl. 585-526

59 Claims

1. A process for oligomerizing ethylene which comprises contacting ethylene under oligomerization conditions with a nickel ylide defined by the following formula:



wherein R₁, R₂, R₃, R₄, R₅, R₆, R₇ and R₈ are either alike or different members selected from the group consisting of hydrogen, alkyl radicals having from about one to about 24 carbon atoms, aryl radicals having from about six to about 20 carbon atoms, alkenyl radicals having from about two to about 30 carbon atoms, cycloalkyl radicals having from about three to about 40 carbon atoms, aralkyl and alkaryl radicals having from about six to about 40 carbon atoms, halogen radicals, hydroxyl, alkoxy and aryloxy groups, and hydrocarbyl groups

carrying halogen, hydroxyl, alkoxy or aryloxy groups, provided that at least one of each of R₁ to R₈ radicals is a sulfonate group or an alkyl, aryl, alkenyl, cycloalkyl, aralkyl or alkaryl carrying a sulfonate group, M is sulfur or oxygen, E is phosphorus, arsenic, antimony or nitrogen and F is phosphorus, arsenic or antimony.

4,293,728

PRETREATMENT OF BUTENE-1 IN ISOMERIZATION OF IT TO BUTENE-2

Dean P. Montgomery, Bartlesville, Okla., assignor to Phillips Petroleum Co., Bartlesville, Okla.

Filed Mar. 31, 1980, Ser. No. 135,606

Int. Cl.³ C07C 5/23

U.S. Cl. 585-670

4 Claims

1. In the isomerization of isomerizable olefins in the presence of a catalyst the activity of which is adversely affected by an impurity such as sulfur or arsenic, the step of pretreating the feedstream by contacting the same at a temperature of the order of about 190° F. in a guard chamber or pretreatment bed containing an activated alumina contact mass adapted to remove from the feedstream the objectionable impurity.

4,293,729

ALKYLATION WITH DIB VAPOR ACID WASH

Norman P. Kolb, Overland Park, Kans., and Orlando Webb, Lee's Summit, Mo., assignors to Stratford/Graham Engineering Corp., Kansas City, Mo.

Filed Jul. 8, 1980, Ser. No. 166,768

Int. Cl.³ C07C 3/54


U.S. Cl. 585-715

8 Claims

1. In a sulfuric alkylation process, wherein an olefin is reacted with isobutane in the presence of sulfuric acid catalyst in the reaction zone to produce a liquid hydrocarbon effluent

containing the alkylate product and a vaporous hydrocarbon effluent,

the liquid hydrocarbon effluent is first neutralized and then passed to a distillation zone wherein low boiling material are removed as a vaporous fraction from the liquid alkylate product and the liquid alkylate product is removed from the distillation zone, the vaporous hydrocarbon effluent having sulfur dioxide vapors therein and the vaporous fraction from the distillation zone having some water therein, the improvement which comprises:




ELECTRICAL

4,293,730 METHOD AND APPARATUS FOR DETECTING A GROUND ON ELECTRIC FURNACES

Robert W. Myers, Newark, Ohio, assignor to Owens-Corning
Fiberglass Corporation, Toledo, Ohio
Filed Nov. 13, 1979, Ser. No. 93,772
Int. Cl.³ C03B 5/02

U.S. Cl. 13—6



1. A method of detecting a ground on an electric furnace, said method comprising the steps of: connecting an electrode, which is located in said furnace, to ground potential; sensing the current flowing from said electrode to ground; comparing the sensed current with a first reference signal indicative of the maximum desired current flowing to ground through said grounded electrode; and providing a first alarm signal when said sensed current is greater than said first reference signal.

4,293,731 SOLAR GENERATOR, ESPECIALLY FOR SPACE CRAFT


Helmut Schweig, Hohenkirchen, and Henning von Bassewitz,
Munich, both of Fed. Rep. of Germany, assignors to Mes-
serschmitt-Boelkow-Blohm Gesellschaft mit beschränkter
Haftung, Munich, Fed. Rep. of Germany

Filed Jun. 2, 1980, Ser. No. 155,649
Claims priority, application Fed. Rep. of Germany, Jun. 9,
1979, 2923535

U.S. Cl. 136—245

Int. Cl.³ H01L 31/06

16 Claims



1. A solar generator, comprising flexible panel means, solar cells secured to said flexible panel means, frame means for holding said panel means, said frame means (10) comprising longitudinal bars (11) made of fiber compound materials and crossbars (12) also made of fiber compound materials, each frame means enclosing one of said flexible panel means, first adjustable tensioning means operatively interposed between said crossbars and said flexible panel means for coupling said flexible panel means to said frame means at the ends of said panel, and second adjustable tensioning means comprising stay wires means coupled to the sides of said flexible panel means

and adjustable biasing means (26) operatively connecting said wire means to said crossbars (12).


4,293,732 SILICON SOLAR CELL AND 350 NANOMETER CUT-ON FILTER FOR USE THEREIN

James D. Rancourt, and Richard I. Seddon, both of Santa Rosa,
Calif., assignors to Optical Coating Laboratory, Inc., Santa
Rosa, Calif.

Continuation of Ser. No. 945,433, Sep. 25, 1978, abandoned,
which is a continuation of Ser. No. 823,843, Aug. 11, 1977,
abandoned. This application Jun. 25, 1979, Ser. No. 51,379
Int. Cl.³ H01L 31/06

U.S. Cl. 136—257

18 Claims



1. In a solar cell construction, a body formed essentially of silicon having a surface with a photovoltaic junction applied thereon, an anti-reflection coating formed on said surface, a transparent protective cover, a reflective cut-on filter carried by the cover and a layer of substantially transparent cement securing said protective cover to said body so that it overlies the junction and the anti-reflection coating, the reflective cut-on filter comprising a stack of layers formed alternately of higher and lower refractive index materials for reflecting a substantial portion of the light energy in the ultraviolet region below a predetermined cut-on wavelength, the cut-on filter also comprising a layer formed of an absorbing material which has an absorption band commencing at approximately the cut-on wavelength for blocking the passage of solar energy in the ultraviolet region below approximately the cut-on wavelength, said cut-on filter having a transmission cut-on which is angle insensitive to the angle of incidence of solar energy at the cut-on wavelength, said cut-on filter providing angle insensitivity without substantial sacrifice of the capability of reflecting solar energy below the cut-on wavelength at normal incidence.


4,293,733 SAFETY COVER FOR ELECTRICAL OUTLETS

George R. Royer, Toledo, Ohio, assignor to John A. Weithman,
Genoa, Ohio, a part interest

Filed Nov. 13, 1979, Ser. No. 93,608
Int. Cl.³ H01R 13/44

U.S. Cl. 174—67

4 Claims



1. A protective covering device for electrical plugs with two prongs for insertion in a wall affixed electrical outlet, said protective device comprising:
(a) a plate member, said plate member having one or more

a transmit signal path for coupling voice band signals at the loudspeaker to the signalling terminal; and switch means for alternately connecting one and the other of the transmit and receive signal paths in series between the loudspeaker and the signal terminal, in response to one and the other of first and second d.c. signal states received at the signal terminal; whereby the station set is remotely controllable to operate in a hands free receiving mode and in a hands free transmitting mode, providing a hands free answer intercom function.

4,293,741

MAGNET ASSEMBLY


Clifford B. Digre, 4745 Vincent Ave. South, Minneapolis, Minn. 55410

Filed Jun. 21, 1979, Ser. No. 50,873

Int. Cl.³ H04R 9/02

U.S. Cl. 179—115.5 PC

16 Claims



7. A magnetic assembly for attachment to a loudspeaker basket of predetermined thickness comprising:

- a back plate having a solid cylindrical pole projecting from one face thereof;
- an annular magnet having a face and an axial bore therethrough, said projecting pole being disposed centrally within said axial bore;
- means affixing said face of said magnet to said face of said back plate; and
- a front plate having a face disposed against said magnet, said front plate having a circular aperture of a diameter less than said axial bore in said magnet but greater than the diameter of said projecting pole, said second plate further having a lip having generally vertical walls projecting outwardly and substantially perpendicularly from the other face of said front plate whereby a concentric ring is formed around said projecting pole to be received within said basket opening and wherein said lip extends outwardly beyond said basket.

4,293,742

MICROPHONE DEVICE

Masanobu Sato, Hachioji, and Ken Sato, Akigawa, both of Japan, assignors to Olympus Optical Company Limited, Tokyo, Japan

Filed Sep. 21, 1979, Ser. No. 77,721

Claims priority, application Japan, Sep. 25, 1978, 53-131512[U]


Int. Cl.³ G11B 31/00; H04B 1/06

U.S. Cl. 179—178

6 Claims

1. A microphone device for use with acoustic equipment, comprising a body detachably mountable on the acoustic equipment, an extensible and contractable elongated arm on

the body, a microphone fitted to the free end of the arm, and extensible and contractable elongated conductor means dis-



posed in the arm for electrically connecting the microphone with the body.

4,293,743

COMBINATION SWITCHING MEANS OF LEVER TYPE FOR MOTOR VEHICLES

Masayosi Iwata, Hashima, and Harumi Douke, Komaki, both of Japan, assignors to Kabushiki Kaisha Tokai Rika Denki Seisakusho, Aichi, Japan


Filed Oct. 5, 1979, Ser. No. 82,404

Claims priority, application Japan, Oct. 6, 1978, 53-138472

Int. Cl.³ H01H 3/16, 9/00

U.S. Cl. 200—4

9 Claims



1. A combination switching assembly of the lever type for use in a motor vehicle, said assembly comprising: a support frame adapted to be mounted on a steering column of a motor vehicle, said support frame having projecting therefrom a pivot shaft; a lever support member mounted to pivot about said pivot shaft; a hollow operating lever;

supporting shaft member means for connecting said operating lever to said lever support member such that upon application to said operating lever of a first tilting pivotal movement in a first direction said operating lever and said lever support member together pivot about said pivot shaft, and such that upon application to said operating lever of a second tilting pivotal movement in a second direction substantially perpendicular to said first direction said operating lever pivots with respect to said lever support member about an axis of said supporting shaft member means;

first, second and third switching means, fixed with respect to said support frame, for achieving first, second and third switching operations, respectively; first operating member means, connected to said lever support member, for, upon movement of said operating lever and said lever support member about said pivot shaft in said first direction, actuating said first switching means; first sliding member means, mounted for sliding movement with respect to said support frame, for actuating said second switching means;

second operating member means, connected to said operating lever, for, upon movement of said operating lever in said second direction, causing said first sliding member means to actuate said second switching means, and for, upon movement of said operating lever in said first direction, preventing sliding movement of said first sliding member means and thus preventing actuation of said second switching means; an operating shaft extending coaxially through the interior of said operating lever and being mounted therein for twisting rotational movement with respect thereto; second sliding member means, mounted for sliding movement with respect to said support frame, for actuating said third switching means; and third operating member means, connected to said operating shaft for, upon twisting rotational movement of said operating shaft with respect to said operating lever, causing said second sliding member means to actuate said third switching means, and for, upon movement of said operating lever in said first or second directions, preventing sliding movement of said second sliding member means and thus preventing actuation of said third switching means.

4,293,744

ALIGNMENT DEVICES FOR REMOVABLE SPARK PLUG TERMINALS IN AN IGNITION COMMUTATION DISTRIBUTOR


Robert L. Kuhn, Dearborn, and Charles C. Kostan, Canton, both of Mich., assignors to Ford Motor Company, Dearborn, Mich.

Filed Dec. 14, 1979, Ser. No. 103,634

Int. Cl.³ H01H 19/00

U.S. Cl. 200—19 R

11 Claims



1. An ignition commutation distributor for an internal combustion engine comprising: a distributor base, for mounting on said internal combustion engine, defining a portion of a commutation cavity; a distributor cap for mounting on said distributor base and defining the remaining portion of said commutation cavity; a rotor mounted within said commutation cavity, in rotational driving communication with said engine, said rotor containing at least one commutation conductor which rotates with said rotor about a central axis of said commutation cavity; a common high voltage supply electrode fixedly mounted to said base in said commutation cavity to be in arc-gap communication with said at least one commutation con-

ductor over several distinct portions of said electrode, when said rotor is rotationally driven; a plurality of open ended hollow spark plug wire terminal connectors permanently attached to spark plug wires and removably mounted on said distributor cap to extend therethrough into said commutation cavity; and means within said commutation cavity for entering said open end and aligning said removably mounted spark plug wire terminal connectors about said central axis to be in predetermined locations so that each is in arc-gap registration with said at least one commutation conductor during a portion of each rotation of said rotor.

4,293,745

CAPACITANCE TYPE CONTACT SWITCH

Takehiko Matsuda, Matsudo, and Kyoichi Izawa, Tokyo, both of Japan, assignors to Toyostar Corporation, Tokyo, Japan


Filed Jun. 5, 1979, Ser. No. 45,755

Claims priority, application Japan, Jun. 23, 1978, 53/86265[U]

Int. Cl.³ H01H 35/00

U.S. Cl. 200—52 R

7 Claims



1. A capacitance type contact switch comprising: a conductive front contact plate mounted to a front panel, a support plate attached to said front panel, fitting means attached to said support plate and containing a conductive push button in the form of a conductive bottomed cylinder, a conductive seat member, and a conductive spring member interposed between said bottomed cylinder of said push button and said seat member and biasing said push button toward the back of said front contact plate, a switch case coupled to said support plate and containing an electrical circuit substrate, and lead wire means electrically connecting said electrical circuit substrate with said seat member, thereby providing electrical conduction between said substrate and said conductive contact plate through said seat member, spring member and push button.

4,293,746

FOOT OPERATED CONTROL UNIT

Ronald J. Braaten, P.O. Box 161, Woodstock, Conn. 06281

Continuation of Ser. No. 765,896, Feb. 7, 1977, abandoned. This application Nov. 24, 1978, Ser. No. 963,453

Int. Cl.³ H01H 3/14; G05G 1/14


U.S. Cl. 200—86.5

6 Claims

1. A self-contained foot operated unit for controlling a power circuit of an associated power driven device comprising:

- a substantially flat base adapted to be placed on a horizontal supporting surface and having means to retain the base in a fixed position thereon,
- an elongate foot operated actuating member having an upper surface for receiving and supporting the entire bottom surface of the foot of an operator,
- bearing means mounting the foot operated actuating member on the base for limited reciprocating forward and

backward movement relative thereto only in a linear direction longitudinally of the actuating member responsive to movement of an operator's foot resting on the actuating member, said member together with the base providing an enclosed space therebetween,
(d) a control mechanism of the switch or valve type



mounted on the base within said enclosed space for connection to the power circuit of an associated power driven device for controlling the operation thereof, and
(e) actuating means within said enclosed space and arranged to cooperate with the actuating member for actuating the control mechanism responsive to longitudinal movement of the actuating member relative to the base.

4,293,747

HIGH-VOLTAGE PUFFER-TYPE COMPRESSED-GAS CIRCUIT-INTERRUPTER ASSEMBLAGE

John R. Perulfi, Monroeville, Pa., assignor to Westinghouse Electric Corp., Pittsburgh, Pa.


Continuation of Ser. No. 713,559, Aug. 11, 1976, abandoned.

This application Jan. 29, 1979, Ser. No. 7,052

Int. Cl.³ H01N 33/14, 9/40

U.S. Cl. 200—145

1 Claim



1. A high-voltage circuit-interrupting assembly comprising an upstanding supporting columnar structure; a first horizontally-extending supporting structure secured to, and supported by, said upstanding supporting columnar structure, said first horizontally-extending supporting structure having disposed therein a first common operating mechanism; a pair of second horizontally-extending supporting structures one each of which is secured to each end of said first horizontally-extending supporting structure, each of said second supporting structures having disposed therein a second common operating mechanism operatively connected to said first common operating mechanism such that said first and second operating mechanisms operate simultaneously; a first hollow leg secured to each second supporting structure disposed generally parallel to

said upstanding supporting columnar structure and a second hollow leg secured to each second supporting structure disposed along the axis of said first horizontally-extending supporting structure; an interrupting unit disposed in each of said first and second hollow legs, said interrupting units being operatively connected to said second common operating mechanisms and effecting simultaneous opening and closing of all of said interrupting units; and means for connecting said interrupting units in electrical series.

4,293,748

VACUUM CIRCUIT INTERRUPTER ELECTRODES

Shinzo Sakuma, Yokohama, and Hifumi Yanagisawa, Sagami-hara, both of Japan, assignors to Kabushiki Kaisha Meidensha and Kabushiki Kaisha GEMVAC, both of Tokyo, Japan


Filed Dec. 19, 1978, Ser. No. 970,912

Claims priority, application Japan, Dec. 28, 1977, 52-160560

Int. Cl.³ H01H 33/66

U.S. Cl. 200—144 B

9 Claims



1. In a circuit interrupter having a pair of electrodes, one of said electrodes being relatively movable with respect to the other between a closed position in engagement with the other and an open position separated from the other to form a circuit-interrupting arc column between said electrodes, wherein the improvement comprises:

at least one of said electrodes comprises an annular contact section and a disc-shaped arc driving section surrounding said annular contact section, said arc driving section being formed with a plurality of slots extending inwardly from its outer periphery to divide it into arc driving segments, said slots being inclined at an angle with respect to the radius of said arc driving section and also being inclined at an angle with respect to the axis of said arc driving section such that said arc driving segments can overlap the adjacent arc driving segments across said inclined slots, said arc driving segments together with said slots between adjacent ones of said arc driving segments being interrelated such that an arc column generated during circuit interruption moves in the direction which makes an acute angle with respect to said slots in the plane facing the other electrode.

4,293,749

PUFFER TYPE GAS CIRCUIT BREAKER

Tuneo Kishi, and Koji Sasaki, both of Hitachi, Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Filed Jul. 25, 1979, Ser. No. 60,480

Claims priority, application Japan, Jul. 26, 1978, 53/90439


Int. Cl.³ H01H 33/16

U.S. Cl. 200—144 AP

5 Claims

1. A puffer type gas circuit breaker including:
an interrupting unit having a main fixed contact, a main movable contact movably disposed in opposed relation with said main fixed contact between a position where it is in contact with and a position where it is separated from said main fixed contact, and a puffer device for compressing and flowing arc-affecting gases across the arc estab-

lished between the main fixed and movable contacts when the same are separated from each other;
a preinsertion resistor contact unit electrically connected in parallel with the main fixed and movable contacts of the interrupting unit, said preinsertion resistor contact unit having a fixed resistor contact a dash-pot cylinder slidably mounted on the outer surface of said fixed resistor contact for normally biasing said fixed resistor contact toward its closing position, said dash-pot cylinder being of electrically conductive material including a duct for creating the dash-pot effect, a preinsertion resistor assembly electrically connected in series with a dash-pot cylinder and a fixed resistor contact, and a movable resistor contact fixed to said puffer cylinder and adapted to be selectively contacted with said fixed resistor contact;
operating means for actuating said main movable contact and said puffer device; and
a sealed container including a grounded tank filled with



arc-affecting gas and provided with an opening for maintenance for accommodating said interrupting unit, said preinsertion resistor unit and said operating means; said sealed container, said interrupting unit, said preinsertion resistor contact unit and said operating means being isolated from each other by insulator means; said puffer type gas circuit breaker comprising:
a support arm extending from the outer surface of said puffer cylinder in a direction substantially perpendicular to the axis of said puffer cylinder, and
a plurality of adjustment plates disposed along the axis of said main movable contact between said support arm and said movable resistor contact, wherein the number of said adjustment plates are selectively increased or decreased to adjust the time interval between the close of said main fixed and movable contacts and the close of said fixed and movable resistor contacts or the time interval between the open of said main fixed and movable contacts and the open of said fixed and movable resistor contacts.

4,293,750

ELECTRIC GAS BLAST CIRCUIT BREAKER

Heiner Marin, Berlin, Fed. Rep. of Germany, assignor to Siemens Aktiengesellschaft, Berlin and Munich, Fed. Rep. of Germany

Filed Feb. 22, 1980, Ser. No. 123,553

Claims priority, application Fed. Rep. of Germany, Feb. 27, 1979, 2907691


Int. Cl.³ H01H 33/88

U.S. Cl. 200—148 A

8 Claims

1. In an electric gas blast circuit breaker comprising:
(a) an electric contact system having a movable cylindrical contact member; and
(b) a gas arc quenching system surrounding the electric contact system, having:
(1) an annular piston;
(2) a movable cylinder;
(3) two sealing rings arranged, respectively between said piston and said movable cylinder on one side, and between said piston and said cylindrical contact member on the other side; and
(4) a one-way valve for the control of quenching gas, which valve is closed during the compression phase and open during the intake phase of the circuit breaker;
the improvement wherein said sealing rings are disposed on a

common plane in annular grooves of said piston; wherein means are arranged between said two sealing rings for constraining said rings to be displaced jointly in the direction of



said plane; wherein said sealing rings are dimensioned to provide axial play within said grooves; and wherein said piston includes flow paths to and from said grooves for the quenching gas such that said sealing rings form said one-way valve.

4,293,751

PROCESS FOR PRODUCING AN ON-OFF PUSH SWITCH AND RESULTING ARTICLE


John D. Van Benthuyzen, and Carlton M. Osburn, both of Elkhart, Ind., assignors to CTS Corporation, Elkhart, Ind.

Filed Feb. 8, 1980, Ser. No. 119,643

Int. Cl.³ H01H 19/14

U.S. Cl. 200—156

4 Claims



1. A control switch comprising a switch housing having a base plate, an internal socket opening with a plurality of circumferentially spaced internal ribs each having a beveled surface and formed integrally with the inner surface of said socket opening, means forming a plunger disposed in said socket opening and having a stem fitting through a central opening of said housing at one end of said socket opening and including a plurality of crowned teeth and external ribbing means in coating slidable and abutting relation with the internal ribs of said housing to preclude relative rotation therebetween, a rotor having complementary crowned teeth engageable with correspondingly opposed teeth of said plunger and external ribs slidably engageable and disengageable with respective internal ribs, a spring means for yieldably opposing axial movement of said plunger and rotor in one direction and for providing an opposite restoring axial movement to said

rotor and plunger, a contactor plate circumposing the other end of said socket opening, and an annular drive arm including a plurality of resilient contactor paddles secured to said annular drive arm retained in said housing by said base plate and key means to rotate said drive arm with said rotor to effect one of a plurality of electrical circuits with said contactor plate, whereby upon axial movement of the plunger and rotor in the one direction there is effected an angular stepping movement of the rotor in a switch-operating direction, the external ribs of said rotor engaging beveled surfaces of respective internal ribs whereby upon the opposite, restoring axial movement of said plunger and rotor the rotor is indexed a further angular incremental movement thereby completing a positioning of the rotor to its initial axial position.


4,293,752

SELF ADHERING TAPE SWITCH

Robert H. Koenig, Huntington Hills, N.Y., assignor to Tapeswitch Corporation of America, Farmingdale, N.Y.
Filed Jan. 11, 1980, Ser. No. 111,279
Int. Cl.³ H01H 13/16, 3/14

U.S. Cl. 200—295

4 Claims




1. Self adhering tape switch assembly comprising: a tape switch having a pair of switch contacts, a layer of deformable material bonded to the underside of said tape switch, a layer of pressure sensitive adhesive connected to the underside of said deformable material layer, a strip of paper adhering to the underside of the pressure sensitive adhesive, said paper strip being removable, a plurality of spaced notches cut through the paper and pressure sensitive adhesive layer so that the tape switch assembly can be easily coiled.

4,293,753
SWITCH

Hiroshi Kanada, Tsu, Japan, assignor to Matsushita Electric Works, Ltd., Osaka, Japan
Filed Sep. 13, 1979, Ser. No. 75,261
Claims priority, application Japan, Sep. 13, 1978, 53-113428
Int. Cl.³ H01H 9/18

U.S. Cl. 200—315

4 Claims



1. A switch for indicating an activated condition of a load circuit, said switch comprising: a body including first, second, third, and fourth chambers, said first and second chambers disposed adjacent one another in a widthwise direction of said body, and said

third and fourth chambers disposed at opposite lengthwise ends of said first and second chambers, said second and third chambers being separated by a partition,

- a transformer disposed in said first chamber and including primary and secondary windings,
- a conductive fulcrum member connected to one lead of said primary winding and forming a fulcrum disposed in said second chamber,
- a movable contact member carrying a movable contact and rockably supported on said fulcrum for rocking movement to either side thereof,
- a first spring for yieldably retaining said movable contact member in position,
- a fixed contact member disposed in said third chamber and carrying a fixed contact, said fixed contact member extending over said partition to locate said fixed contact in said second chamber for being contacted by said movable contact,
- a contacting element connected to another lead of said primary winding and disposed in said fourth chamber,
- second springs disposed in said third and fourth chambers, respectively, on opposite sides of said fulcrum and in opposing relation to said fixed contact member and contacting element, said second springs each including a wedge portion and arranged to urge an exterior load connecting wire against said fixed contact member and contacting element, respectively,
- a switch button rockably mounted on said body and resiliently abutting said first spring, and
- a light emitting diode connected to said secondary winding and being housed visibly within said button to provide a visual indication when the load circuit is activated.

4,293,754

THIN AND FLAT KEYBOARD INTEGRAL WITH A METALLIC HOUSING

Shigeki Komaki, Nara, Japan, assignor to Sharp Kabushiki Kaisha, Osaka, Japan


Filed Dec. 28, 1979, Ser. No. 107,888

Claims priority, application Japan, Dec. 28, 1978, 53-179785[U]

Int. Cl.³ H01H 3/12

U.S. Cl. 200—340

3 Claims



1. A thin keyboard construction for a handheld calculator which comprises a housing member and a key actuator sheet containing a plurality of key actuators which are integral with said key actuator sheet, said housing member being made of a sheetlike flat material having a portion of its area with a reduced thickness, said key actuator sheet being disposed in said area of reduced thickness, said area of reduced thickness having apertures

disposed therein in positions corresponding to said plurality of key actuators, said key actuator sheet being made of a sheet like flat material having cutout portions defining said plurality of key actuators, said cutout portions enabling said key actuator to move in a vertical direction, and said cutout portions being concealed behind said housing member.

4,293,755

METHOD OF COOLING INDUCTION-HEATED VAPOR DEPOSITION APPARATUS AND COOLING APPARATUS THEREFOR

Lawrence Hill, Short Hills; Dennis Garbis, Dix Hills, and Robert Heller, Levittown, all of N.Y., assignors to General Instrument Corporation, Clifton, N.J.


Continuation of Ser. No. 953,575, Oct. 23, 1978, abandoned.

This application Apr. 14, 1980, Ser. No. 140,293

Int. Cl.³ H05B 6/42; C23C 13/08

U.S. Cl. 219—10.41

2 Claims



1. A method of cooling induction-heated horizontal epitaxy tube vapor deposition apparatus including an electrically grounded deposition enclosure and an RF induction heating coil having essentially electrically uninsulated turns thereof disposed about said deposition enclosure, comprising the step of spraying deionized liquid having a resistivity of at least 14 megohms-centimeter directly onto said deposition enclosure and said coil turns of said apparatus in a pattern such that hotter parts of said deposition enclosure receive greater volumes of said deionized liquid than cooler parts thereof.

2. In apparatus for cooling induction-heated horizontal epitaxy tube vapor deposition apparatus including an electrically grounded deposition enclosure and an RF induction heating coil having essentially electrically uninsulated turns thereof disposed about said deposition enclosure, the improvement comprising

- (a) means positioned in a location having access to said enclosure for spraying deionized liquid having a resistivity of at least 14 megohms-centimeter directly onto said enclosure and said coil turns of said apparatus, said spray means being so arranged as to spray said deionized liquid in a pattern such that hotter parts of said deposition enclosure receive greater volumes of said deionized liquid than cooler parts thereof;
- (b) means for collecting the sprayed liquid, said collecting means comprising a receptacle adapted to receive liquid, and said deposition apparatus being disposed above the bottom of said receptacle with end portions of said coil passing through the bottom of said receptacle, said end portions being grounded and encapsulated in polytetrafluoroethylene to electrically isolate said coil end portions from said receptacle and the liquid contents thereof;
- (c) means for maintaining within said receptacle a liquid level below the top of said encapsulated coil end portions but above the bottom of said receptacle; and
- (d) means for independently grounding said spray means and said collecting means.

4,293,756

ELECTRIC WELDER


Harold C. Hoyt, Jr., St. Louis, Mo., and William J. Greene, Warren, N.J., assignors to Teledyne Walterboro, Walterboro, S.C.

Filed Sep. 22, 1978, Ser. No. 944,962

Int. Cl.³ B23K 9/10

U.S. Cl. 219—133

12 Claims



1. An electric welder which comprises output terminals, a D.C. generator that can selectively develop a positive voltage or a negative voltage at one of said output terminals, an energizing circuit for the field winding of said D.C. generator, a polarity-controlling switch that can be set in one position to enable said energizing circuit to cause current to flow through said field winding in a direction which will enable said D.C. generator to develop said positive voltage at said one output terminal, said polarity-controlling switch being adapted to be set in a second position to enable said energizing circuit to cause current to flow through said field winding in the opposite direction and thereby enable said D.C. generator to develop said negative voltage at said one output terminal, a sensing circuit which senses a condition that is representative of the operating level of the D.C. generator and which can develop a first signal when the D.C. generator is operating below a predetermined level and which can develop a second and different signal when said generator is operating above said predetermined level, means to establish and maintain different selected levels of current flow through said field winding, and a control circuit which automatically responds to the development of said first signal by said sensing circuit to force all current flow through said field winding to be in the first said direction irrespective of the position in which said polarity-controlling switch is set, said control circuit subsequently and automatically responding to the development of said second signal by said sensing circuit to permit the current flow through said field winding to be in the direction called for by the setting of said polarity-controlling switch, whereby said D.C. generator will automatically develop said positive voltage at said one output terminal whenever said D.C. generator is operating below said predetermined level but will subsequently and automatically permit said D.C. generator to respond to the setting of said polarity-controlling switch to develop either said positive voltage or said negative voltage at said one output terminal whenever said D.C. generator is operating above said level.

4,293,757

AUTOMATIC WELDER'S HELMET HAVING VENTILATION MEANS

Francis J. Niemi, 3933 W. Ellis Ave., Chicago, Ill. 60653

Filed Sep. 17, 1979, Ser. No. 76,409


Int. Cl.³ B23K 9/32; A61F 9/06; F16P 1/06

U.S. Cl. 219—147

5 Claims

1. In an automatic welder's helmet for use with a welding machine, the combination comprising: an open back headshield, head harness means pivotally connected to said headshield for supporting the same on the head of an operator, a movable dark eye lens slidably mounted in a frame secured about an opening in said headshield and operable to slide over

said opening between open and closed positions, pneumatic operating means protectively mounted within said headshield for opening said dark eye lens, spring means associated with said pneumatic means and operable to effect closing of said dark eye lens; electrical control means for controlling operation of the welding machine and said pneumatic means, said electrical control means including a first time delay means for delaying energization of the welding machine for a period of time until after said dark eye lens has moved to its closed position, and a second time delay means for delaying the movement of said dark lens to its open position for a period of time at least until after the welding cycle has been completed; and helmet ventilation means communicating with the interior of said headshield and operably controlled by said control means to supply fresh air to the interior thereof whenever said lens is in its closed position.



5. A welding helmet for use with an electric arc welding system, comprising: an open back headshield member, a head harness, pivotal means joining said harness to said headshield member whereby to support the latter on the head of an operator and provide for its pivotal movements between raised and lowered positions; helmet ventilation means communicating directly with the interior walls of said headshield member and comprising air distribution means protectively mounted within said headshield member and air supply means located exteriorly thereof; said pivotal means comprising rotary valve means in communication with said air distribution means and said air supply means and operable in response to pivotal movements of said headshield member, whereby when said headshield member is in its lowered position, the air supply means is in direct communication with said air distribution means and when said headshield member is in its said raised position, said air supply means is isolated from said air distribution means.

4,293,758

WELDING APPARATUS INCLUDING MEANS FOR DEPOSITING THE WELD METAL ALONG PARALLEL PATHS

Clyde M. Slavens; Edward A. Clavin, and James E. Alleman, all of Houston, Tex., assignors to Midcon Pipeline Equipment Co., Houston, Tex.


Filed Aug. 1, 1979, Ser. No. 62,686
Int. Cl.³ B23K 9/09

U.S. Cl. 219—125.12

34 Claims

1. Welding apparatus, comprising a welding torch having a consumable welding electrode, a pivotal support for said welding torch, electromagnetic means for oscillating said pivotal support and said welding torch supported thereby in back and forth movements, means for supplying DC welding current of pulsating amplitude to said welding electrode, said pulsating amplitude of said welding current having a frequency equal to the frequency of emissions of weld metal droplets from said welding electrode, electrical circuit means for ener-

gizing said electromagnetic means in correlation with the welding current amplitude pulse frequency so that a selected number of weld metal droplets are emitted at each of the ends of said back and forth movements of said welding torch,




whereby a selected number of weld metal droplets are emitted along a pair of parallel paths along opposite sides of a welding joint, and whereby no weld metal droplets are emitted between said parallel paths.

4,293,759

ELECTRIC HEATING SYSTEM FOR HEATING THE INTERIOR OF A MOTOR VEHICLE PRIOR TO STARTING

Pink M. Higgins, 136 Moore La. 5, Billings, Mont. 59101
Filed Dec. 19, 1979, Ser. No. 105,133

Int. Cl.³ H05B 1/02; F02N 17/02; F24H 3/04
U.S. Cl. 219—202 2 Claims



1. In a motor vehicle having a passenger compartment with at least one seat, a windshield, a rear window, a trunk, a battery and a horizontal shelf behind the rearmost seat over the trunk, the improvement comprising a heating system for heating the passenger compartment and defrosting the rear window and windshield of the vehicle prior to starting, said heating system including:

a electric air heater means fixedly mounted under and to the horizontal shelf for heating air, said air heater having an air outlet in the shelf and an air inlet communicating with the interior of the trunk;

a blower means also positioned underneath the shelf for conveying air through the electric heater means from the trunk and upwardly through the air outlet into the interior of the motor vehicle over the rear window;

a conductive power cord conductively connected to the electric heater means and blower means at one end and having a terminal at another end compatible with a conventional electrical receptacle external of the vehicle for energizing said heater means and said blower from ordinary commercial power of approximately 110 volts, said power cord being retractable into a storage reel in the trunk beneath the horizontal shelf when not in use;

a manually settable timer switch mounted in the trunk beneath said shelf, and including a switch for interrupting the connection between the conductive cord and the electric heater means and blower means, said timer switch having an electric motor for driving the same, and permanent electrical connections between the battery of the vehicle and the timer motor to cause the timer motor to run continuously regardless of whether the vehicle is in

use or not whereby the operation of the timer motor is independent of whether the power cord is connected to a commercial power source or not.

4,293,760

APPARATUS FOR ELECTRICALLY HEATING HAIR CURLERS

Henri Smal, Oupeye, Belgium, assignor to Societe Anonyme FACO, Herstal, Belgium


Filed Jul. 31, 1978, Ser. No. 929,532

Claims priority, application Luxembourg, Apr. 7, 1978, 79402

Int. Cl.³ A45D 4/12; H05B 1/00

U.S. Cl. 219—222

10 Claims



1. Apparatus, comprising a hair curler support having a hollow interior and a support surface formed with a central hot air inlet opening and a plurality of hot air discharge ports arranged radially about in spaced relationship from and centered around said inlet opening, said opening and said discharge ports communicating with the interior of said support, means for holding a hair curler on said support surface at each of said ports in the path of air discharged from the port, a hot air generating means for supplying hot air into said support through said opening for discharge from each of said ports.

4,293,761

CIGARETTE LIGHTERS, PARTICULARLY FOR MOTOR VEHICLES

Luigi Pramaggiore, Strada Statale 26, 11010 Sarre (Aosta), Italy


Filed Dec. 4, 1979, Ser. No. 100,261

Claims priority, application Italy, Dec. 19, 1978, 6989 A/78

Int. Cl.³ F23Q 7/22

U.S. Cl. 219—269

5 Claims



1. A cigarette lighter, particularly for motor vehicles, having a control knob mounted for sliding movement within a cylin-

drical casing and acting through a control rod upon a pivotally mounted contact plate for opening and closing an electric circuit including an electrical heating resistance incorporated in a hot plate adapted to light a cigarette when it is held against;

a bimetal tongue positioned adjacent said hot plate; so as to be heated thereby and having a resilient shaped end projecting toward and in engagement with an edge of said pivotally mounted contact plate to release the latter when the cigarette is lighted and said bimetal tongue has been heated;

a light emitting diode mounted in said cylindrical casing for emission of light to indicate the position of the lighter on an instrument panel;

said electric circuit comprising an input connection plate connectable to a source of current secured to a lower end of an upright stem extending through a lower portion of said lighter and supporting at its upper end said hot plate, said electric circuit further comprising said bimetal tongue, said pivotally mounted contact plate, mounting lugs for said contact plate, a bottom disc supporting said mounting lugs and a connection lug extending downwardly from said bottom disc and connectable to a ground side of said source of current;

said electric circuit, for energization of said light emitting diode, further comprising a support plate secured to and extending perpendicularly from said upright stem, a central stem extending perpendicularly upwardly from a free end of said support plate and through a diode body of said light emitting diode to a cathode thereof, a conductor extending parallel to said central stem from an anode of said diode located opposite said cathode to a single coil spring peripherally surrounding said diode body in a position intermediate the ends thereof, said coil spring engaging the under side and being electrically connected to said bottom disc which through said connection lug extending downwardly therefrom is connected to the ground side of said source of current; and

resilient means peripherally surrounding the end of said cylindrical casing adjacent said control knob for detachably mounting the lighter on the instrument panel.

4,293,762

TEMPERATURE-CONTROLLED ELECTRIC HEATING DEVICE FOR HEATING INSTILLATION OR TRANSFUSION LIQUIDS

Genshirou Ogawa, 13-3, Inuyama Nishikoken, Inuyama, Aichi-ken, Japan


Filed Nov. 30, 1978, Ser. No. 964,861

Claims priority, application Japan, Feb. 16, 1978, 53-16909

Int. Cl.³ H05B 1/02; A61M 5/14; F24H 1/14

U.S. Cl. 219—302

3 Claims



1. A heating device for instillation comprising a casing having means at one end thereof for vertically supporting the

casing during use of the device, said casing including a circuit element receiving chamber and a heater receiving chamber having a front opening, a lid for at least covering said front opening of the heater receiving chamber, a heater situated in said heater receiving chamber, said heater including a heater segment coextensive with, disposed in and filling said front opening and an electric heating element attached to a back side of the heater segment for heating the segment, said heater segment having a tortuous groove on a front side thereof for receiving therein a liquid feed pipe through which an instillation liquid to be heated flows, said lid being arranged to cover said groove and feed pipe received therein when in closed position, said groove having upper and lower curves and extending from an upper portion of the heater segment to a lower portion thereof to keep the instillation liquid in the liquid feed pipe between the upper and lower curves for a period sufficient to heat the liquid, and electric circuit means situated in said circuit element receiving chamber, said electric circuit means including first and second temperature control thermistors, the first thermistor sensing temperature of the instillation liquid after passing through the length of the heater segment groove for operating said circuit means to intermittently energize the heating element to heat the instillation liquid flowing through the feed pipe to a predetermined temperature, the second thermistor being provided at the electric heating element for operating said circuit means to turn off the electric circuit means when the electrical heating element is heated beyond a predetermined temperature due to excess flow of the instillation liquid to thereby override the control of the heating element by the first thermistor.


4,293,763

ELECTRICALLY INSULATED RESISTANCE HEATER
James P. McMullan, 12300 Monarch St., Garden Grove, Calif. 92641

Filed Jun. 2, 1980, Ser. No. 155,475
Int. Cl.³ H05B 3/34

U.S. Cl. 219—528

6 Claims



1. An electrically insulated resistance heater comprising an elongate metallic resistance element, terminals at the ends of the element to connect said element in a power supply circuit for the heater, an electric insulating envelope structure comprising a pair of laminates of dielectric material having a low dielectric constant with inside portions between which said element is arranged and outside portions defining outer work-engaging surfaces in predetermined spaced relationship from said element and a multiplicity of particulate components of material having a high dielectric constant between the laminates in substantial bridging engagement with each other and with said element and enhancing the electric insulating capacity of the envelope structure and supporting the outside portions and work-engaging surfaces thereof spaced from the element, said laminates are joined together with the element and particulate components held secure therebetween.

4,293,764

CONTROL CONSOLE

Herbert Amrhein, Moehrendorf, Fed. Rep. of Germany, assignor to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany


Filed Aug. 20, 1979, Ser. No. 68,091

Claims priority, application Fed. Rep. of Germany, Sep. 29, 1978, 2842622

Int. Cl.³ H01H 9/04, 9/16, 3/12

U.S. Cl. 200—302

13 Claims



1. A control console with installed microswitches having respective actuating elements, particularly for the control of apparatus in the operating room, characterized in that a cover plate (8) has a continuous stiff plastic sheet (9) in covering relation thereto which sheet is arched so as to be raised to form depressible bubble-like portions in the region of said individual actuating elements of the installed microswitches, plastic cylinders being disposed in an intermediate space between the individual bubble-like portions of the plastic sheet (9) and the respectively allocated actuating elements of the microswitch for transmitting depression of each respective bubble-like portion to the associated actuating element, said plastic cylinders being matched to the diameter of the bubble-like portions and having convexly protrudingly curved end portions thereof facing the plastic sheet (9), a light source (42, 59) being allocated to each plastic cylinder (48, 56), and a separate plate (41, 51) connected with said cover plate (8) and mounted at a defined distance therefrom, the microswitches (7) being mounted on said separate plate (41, 51) the cover plate (8) having guide means (46, 55) in alignment with the respective bubble-like portions (20, 24) and said plastic cylinders (48, 56) being guided by said guide means (46, 55), said guide means comprising a sleeve (55) for each plastic cylinder (56) mounted by said cover plate (8), each sleeve (55) having at the end thereof remote from said cover plate (8) a spring plate (57) which is secured to said end of said sleeve (55) at its one end and acts, at its other end, against the associated actuating element (45) of the associated microswitch (7), each plastic cylinder (56) being reciprocally movable in its associated sleeve (55) and engaging with the associated spring plate (57), and said spring plate (57) having means (58) for transmitting light from said light source to the interior of said sleeve (55) for passage axially thereof via the associated plastic cylinder (56).

4,293,765

COUNTER

Tutomu Kashiwagi, Tokyo, Japan, assignor to Dai-Ichi Seiko Co., Ltd., Kawaguchi, Japan

Filed Feb. 4, 1980, Ser. No. 118,635

Claims priority, application Japan, Feb. 15, 1979, 54-16428; Oct. 4, 1979, 54-136693


Int. Cl.³ G06C 15/42

U.S. Cl. 235—144 R

12 Claims

1. A counter comprising a worm wheel and a plural number of digit wheels which are supported on a shaft attached to a frame, driven gears supported on said shaft and arranged between individual pairs of said digit wheels, intermittent mechanisms arranged between said worm wheels and the lowermost digit wheel adjacent thereto and between each digit wheel and the next lower digit wheel and pinions which are supported on another shaft attached to said frame and so positioned as to engage with two teeth formed on each digit wheel and each

driven gear at the same time, said counter being so adapted in such a manner that when each of said intermittent transmission mechanisms and each of said driven gears are rotated, their rotation is transmitted to said digit wheels to rotate them inter-



grally with said members, whereas when the digit wheels are rotated for resetting them at the zero position, said driven gear are made immovable by said pinions and only said digit wheels are rotated.

4,293,766

RAIL CAR IDENTIFICATION APPARATUS


Lennart E. Long, Waltham, and Robert L. Wiseman, Lexington, both of Mass., assignors to The United States of America as represented by the Secretary of Transportation, Washington, D.C.

Filed Oct. 30, 1979, Ser. No. 89,431

Int. Cl.³ G06K 7/10, 13/00

U.S. Cl. 235—462

8 Claims



1. Apparatus for simulating a rail car identification system comprising:

- a plurality of coded labels;
- transport means for sequentially moving each of said coded labels through a viewing zone;
- optical scanning means for scanning said coded labels in said viewing zone;
- control circuit means for controlling said transport means comprising endless conveyor means and wherein said coded labels are mounted at spaced apart locations on said endless conveyor means;
- processor means for processing the output of said optical scanning means;
- label sensor means for detecting the entry of each of said labels into said viewing zone and supplying label position signals to said control circuit means in response thereto;
- conveyor position sensor means for detecting the entry into said viewing zone of a particular portion of said endless conveyor means and supplying conveyor position signals to said control circuit means in response thereto; and
- wherein said control circuit means comprises speed control means for selectively controlling the speed of said endless conveyor means.

4,293,767

APPARATUS FOR MEASURING THE THICKNESS OF THIN LAYERS


Helmut Fischer, Bergwaldstrasse 28, 7261 Gechingen; Albert Ott, Am Weinberg 22, 6200 Wiesbaden, Auringen, and Willi Steegmüller, Tulpenstrasse 18, 7407 Rottenburg 15, all of Fed. Rep. of Germany

Filed Aug. 24, 1979, Ser. No. 69,610

Int. Cl.³ G01N 23/00

U.S. Cl. 250—308

14 Claims



1. In an apparatus for measuring the thickness of a thin layer on strip-shaped, wire-shaped or like material, which can be moved from a first point past the apparatus to a second point, comprising a beta emitter directed towards said thin layer and a windowed beta radiation detector arranged to the rear of the beta emitter for counting the backscattered beta radiation, the counting taking place while the material is being moved, the improvement wherein:

- (a) the apparatus is stationary;
- (b) the apparatus is provided with a guide for guiding the material at a specified distance from the beta emitter;
- (c) the ratio of the characteristic cross-sectional dimension (D) of the window of the beta radiation detector, to the intersecting surface diameter (d) of the intersecting surface layer/intensity distribution curve of the beta emitter, being expressed as D/d coming within the range 15...2;
- (d) the distance between the layer and the beta emitter is in the plateau region of the counting rate/distance characteristic which is obtained by (c) above.

4,293,768

INFRARED RADIATION DETECTING APPARATUS AND METHOD OF MANUFACTURING

Hideo Adachi, Kyoto; Kiichi Minai, Shiga; Kozo Moriyasu, and Shunjiro Imagawa, both of Muko, all of Japan, assignors to Murata Manufacturing Co., Ltd., Japan


Filed Apr. 18, 1979, Ser. No. 31,048

Claims priority, application Japan, Apr. 26, 1978, 53-50373

Int. Cl.³ G01J 1/00; H04N 9/27

U.S. Cl. 250—338

27 Claims



1. An infrared radiation detecting apparatus, comprising: a substrate made of an insulating material; a thermal type infrared radiation sensing device having first and second opposing main surfaces; said first main surface

constituting a radiation receiving surface; said thermal type sensing device being thermally responsive to heat caused by infrared radiation incident upon said radiation receiving surface, and generating an electrical signal responsive to infrared radiation incident upon said radiation receiving surface;

external connection lead means secured to said insulating substrate and electrically connected to said thermal type infrared radiation sensing device;

a first resin layer covering said thermal type infrared radiation sensing device except for said radiation receiving surface thereof, and covering said insulating substrate and a portion of said external connection lead means; and

a second resin layer covering said first resin layer and said radiation receiving surface, and being transparent to infrared radiation of frequencies it is desired to detect.

4,293,769

DETECTING IR AND MM RADIATION


Daniel Kleppner, Belmont, Mass., assignor to Massachusetts Institute of Technology, Cambridge, Mass.

Continuation of Ser. No. 869,345, Jan. 13, 1978, abandoned. This application Nov. 16, 1979, Ser. No. 94,959

Int. Cl.³ G01J 1/00

U.S. Cl. 250-338

5 Claims



1. IR and mm energy detecting apparatus comprising, a source of a beam of atoms, means for establishing an electric field, means for causing said beam of atoms to enter said electric field, a source of essentially monochromatic energy for exciting atoms in said beam that enter said electric field into a predetermined energy level, means for illuminating said excited atoms in said electric field with IR or mm electromagnetic radiation and establishing the intensity of said electric field to step the energy level of said excited atoms in said electric field from said predetermined energy level to a higher level when the wavelength of said electromagnetic radiation is a predetermined value related to the contemporary intensity of said electric field to thereby produce particles stripped from those atoms at said higher level and emitted from said electric field representative of said radiation, and means for detecting the emitted particles to provide an indication of said radiation.

4,293,770

X-RAY TABLE FOR OBTAINING LONGITUDINAL AND LATERAL OBLIQUE CARDIOVASCULAR VIEWS

Robert M. Vavrek, Waukesha, Wis., assignor to General Electric Company, Schenectady, N.Y.

Filed Nov. 29, 1979, Ser. No. 99,132

Int. Cl.³ G01N 21/00

U.S. Cl. 250-445 R

3 Claims

1. Apparatus for making x-ray cardiovascular examinations comprising:

- an overhead carriage movable horizontally in opposite longitudinal directions,
- an x-ray image receiver and means for mounting said receiver to move vertically and to tilt in a single vertical


plane through opposite angles from vertical about a first laterally extending axis that is transverse to the longitudinal direction,

a longitudinally extending x-ray transmissive table top located below said receiver to support a body for examination and housing means below said table top, said housing means being adapted for mounting fixedly on a floor and comprising opposed pairs of side walls defining a top opening,

enclosure means mounted for moving vertically within said housing, and comprising a bottom member and opposed pairs of side walls joined to said bottom member, said walls defining a top opening across which said x-ray transmissive table top extends for being supported from said side walls,

an x-ray tube casing in said enclosure means and a base supporting said tube casing for tilting in said single vertical plane through opposite angles from vertical about a second laterally extending axis in opposite angular correspondence with said image receiver,

a rotary anode x-ray tube in said casing having an x-ray target disk rotatable about a generally longitudinally di-



rected axis, said disk having a beveled annular focal spot track surface on one of its faces and said disk being offset generally longitudinally from said second laterally extending axis to thereby offset the focal spot to one side of said second axis, the central ray of the x-ray beam emanating from said focal spot being moved in said single plane for all corresponding tilting angles of said x-ray tube and said image receiver, and

the improvement for enabling said x-ray beam to be directed obliquely to said plane comprising,

bearing means interposed between said base and said bottom member of the vertically movable enclosure, said bearing means supporting said base and x-ray tube casing thereon for rotation about a vertical axis, motor means mounted to said enclosure and means for coupling said motor means in driving relation to said base to effect rotation of the base about said vertical axis and thereby enable said tube casing to tilt in a vertical plane which is at an angle relative to the aforementioned vertical plane and to simultaneously offset said focal spot in a lateral direction so the central ray of said x-ray beam will be directed obliquely to said aforementioned plane.

4,293,771

INDICATOR FOR USE WITH PROJECTED BEAM OF RADIATION


Charles Lescrenier, 660 Crescent Ct., Wauwatosa, Wis. 53213

Filed Jun. 7, 1979, Ser. No. 46,435

Int. Cl.³ G01N 21/00, 23/00

U.S. Cl. 250-491

13 Claims



1. Apparatus for defining the relationship of a projected beam with respect to an object comprising:

a first light source means (36, 82) for establishing a first plane of light (44, 84) containing the projected beam (34, 76) and applicable to the object (14, 16, 24, 90); and

a second light source means (46, 86) for establishing a second plane of light (50, 88) containing at least one of the projected beam and object and applicable to the latter, said first light source means (36, 82) being movable with respect to said second light plane (50, 88) and object (14, 16, 24, 90) while maintaining the projected beam (34, 76) therein, said first and second light planes intersecting, the intersection of said light planes defining the projected beam-object relationship.

4,293,772

WOBLING DEVICE FOR A CHARGED PARTICLE ACCELERATOR


Volker A. W. Stieber, Erlangen, Fed. Rep. of Germany, assignor to Siemens Medical Laboratories, Inc., Walnut Creek, Calif.

Filed Mar. 31, 1980, Ser. No. 135,300

Int. Cl.³ G01J 1/42

U.S. Cl. 250-492.2

9 Claims



1. A linear accelerator for medical treatment comprising, in combination:

- (a) an accelerator chamber including wall means made of a non-ferromagnetic material;
- (b) means arranged in said chamber for accelerating a narrow beam of electrons in a forward direction therethrough, said electrons forming beam pulses having a predetermined pulse frequency;
- (c) a discharge window disposed on said chamber for receiving said beam of electrons at a striking location and for discharging said electrons therethrough; and
- (d) means for wobbling said beam of electrons before the electrons strike said discharge window, wherein said wobbling means comprises three magnetic coils which are arranged 120° apart from each other around said beam of electrons on the outside of said wall means near said discharge window, said three magnetic coils being adapted for connection to a three-phase current supply having a predetermined supply frequency, said supply frequency being lower than said pulse frequency of said electron beam pulses, said coils thereby being provided for generating a magnetic field in the vicinity of said striking location near said discharge window, which magnetic field causes said electrons to impinge on said discharge window in a circular path, thereby enlarging said striking location and reducing the number of secondary electrons being accelerated in a backward direction through said accelerator chamber.

4,293,773

METHOD FOR CONTAINING SPENT NUCLEAR FUEL RODS IN A PROTECTIVE CONTAINER TO FACILITATE DISPOSAL

Jan Lundren, Robertsfors, Sweden, assignor to ASEA Aktiebolag, Vasteras, Sweden


Filed May 8, 1978, Ser. No. 903,946

Claims priority, application Sweden, May 10, 1977, 7705417

Int. Cl.³ G21F 5/00

U.S. Cl. 250-506

3 Claims



1. A method for preventing the scattering of radioactive material in spent nuclear fuel rods in the environment comprising (a) placing one or more of the fuel rods within a casing of ductile metal, (b) sealing the casing so as to be gastight, (c) bending the casing into a U-shape such that the distance between the legs of the U-shape is equal to or somewhat greater than the thickness of the casing, and (d) placing a number of the bent U-shaped casings within a protective container such that a leg of each casing extends between the legs of another casing.

4,293,774

METHOD AND DEVICES FOR REGULATION OF THE FORWARD TRAVEL OF A STRIP BEARING MARKS AT REGULAR INTERVALS, AND A WRAPPING-MACHINE EMPLOYING SUCH A DEVICE

Endre Pongracz, Vaud, Switzerland, assignor to SAPAL Societe Anonyme des Plieuses Automatiques, Switzerland


Filed Oct. 16, 1979, Ser. No. 85,207

Claims priority, application Switzerland, Nov. 20, 1978, 11868/78

Int. Cl.³ G01N 21/86

U.S. Cl. 250-548

14 Claims



1. A method for regulating the forward travel of a strip (70) which at regular intervals bears section marks (71) and which is cut into sections (73) and used to individually wrap a succession of articles (61) comprising the steps of:

- cyclically cutting said strip (70) into sections and using a cut section (73) to wrap one of said succession of articles (61);
- detecting the passing of each mark (71) of said strip and providing a signal (LECTREP) indicating said detection;
- generating from each cutting and wrapping cycle a phase reference signal (SYNCHR) indicating at what time said mark (71) should be detected;
- measuring the phase error between the signal indicating detected passing of the mark (LECTREP) and the phase reference signal (SYNCHR);
- temporarily modifying the driving speed of the strip (70) so that it adopts either a lead or lag correction for compensating the measured phase error; and
- limiting the lead or lag correction to a maximum amplitude of correction such that a cut-off section (73) has a length sufficient to wrap an article.

4,293,775

OZONE PIPE FOR OZONE PRODUCTION PLANT

Ewald Feuerstake, Dorsten, and Klaus Schwarz, Neukirchen-Vluyn, both of Fed. Rep. of Germany, assignors to Mannesmann DeMag AG, Duisburg, Fed. Rep. of Germany


Filed Nov. 13, 1979, Ser. No. 93,384

Claims priority, application Fed. Rep. of Germany, Dec. 13, 1978, 2853749

Int. Cl.³ C01B 13/11; B01J 19/12

U.S. Cl. 250-535

5 Claims



1. In an ozone production pipe for use with a plurality of such pipes in parallel in a large ozone production plant employing several hundred pipes, said production pipe comprising

- (a) a tubular body comprised of a dielectric material;
- (b) a metal jacket electrode encasing said body;
- (c) a counter-electrode in the form of a metal coating on the inside of said tubular body;

- (d) an electrical current supply connection mounted in one end of said tubular body;
- (e) means in said body providing electrical flow communication between said electrical current supply connection and said counter-electrode;
- (f) a high voltage fuse mounted in said flow communication means; the improvement characterized by
- (g) said high voltage fuse having a capacity within the range of between about 0.15 to 0.63 amperes; and
- (h) a resistance is mounted in said flow communication means in series with said fuse.

4,293,776

BANKNOTE CONDITION MONITORING APPARATUS

Erwin Sick, Icking, and Siegfried Mankel, Geretsried, both of Fed. Rep. of Germany, assignors to Erwin Sick GmbH-Optik-Elektronik, Waldkirch, Fed. Rep. of Germany


Filed Apr. 8, 1980, Ser. No. 138,337

Claims priority, application Fed. Rep. of Germany, May 3, 1979, 2917875

Int. Cl.³ G01N 21/88

U.S. Cl. 250-572

8 Claims



1. Banknote condition monitoring apparatus comprising a rotating drum on the peripheral surface of which the banknotes to be examined are held, for example by means of air suction, an optical scanning device which generates a scanning light beam which forms a scanning light bead on the banknote which cyclically scans the banknote transversely to its direction of movement substantially without gaps, a cylindrical lens extending in the scanning direction in front of the banknote and which concentrates with a portion of its width the transmitted light beam onto the banknote and directs light remitted from the banknote via another part of its width to a light receiving device and wherein the transmitted light beam is narrow and passes through the cylindrical lens at a portion of its periphery, the rotational axis of the drum is so displaced relative to the optical axis of the cylindrical lens that specularly reflected light enters the same half of the cylindrical lens as the transmitted light beam, but however separated from the same, and the specularly reflected beam is deflected in a distance substantially the same as the distance of the scanning device from the point of incidence of the light bead on the banknote directly onto a photodetection device without contacting the scanning member of the optical scanning device.

4,293,777

TURBO-ELECTRIC POWER PLANT AND PROCESS

Joseph A. Gamell, Kalamazoo, Mich., assignor to Joseph Gamell Industries, Inc., Kalamazoo, Mich.

Filed Jul. 30, 1979, Ser. No. 62,322


Int. Cl.³ H02K 7/18; F01D 5/30

U.S. Cl. 290-52

18 Claims

1. A turbo-electric power plant which comprises (1) a stationary housing supported by a base member and having an annular member provided with depending sides which form with said annular member an annular channel, said annular channel having a smooth cylindrical inner surface;

- (2) a hollow rotor mounted for rotation in said housing about the axis thereof, with the outer portion thereof disposed in said annular channel and having a roughened outer cylindrical surface and sides conforming essentially to the shape of said annular channel, said hollow rotor having an inner cylindrical surface in said outer portion thereof which is concentric with the other said cylindrical surfaces;
- (3) electric generator elements disposed in said hollow rotor in electricity-generating relation to each other, one said element being affixed to the inner cylindrical surface of said hollow rotor and functioning as the rotor element of said electric generator, and the other said element being anchored to said base member and functioning as the stator element of said electric generator;
- (4) a plurality of jet orifices disposed in and around said



- annular member and oriented to jet propellant fluid into the space between the smooth inner cylindrical surface of said annular channel and the apposed roughened outer cylindrical surface of said hollow rotor and onto the said roughened outer cylindrical surface;
- (5) outlet means at spaced intervals around and in the side walls of said housing below the said annular channel, whereby the propellant fluid jetted onto the outer cylindrical surface of said hollow rotor, fans out to the edges thereof and moves down between the sides of said annular channel and the sides of the outer portion of said hollow rotor and out said outlet means, thereby functioning as a coolant fluid for cooling said electric generator elements; and,
- (6) collecting means for collecting the electricity generated by said electric generator elements and leading it to the exterior of said housing.

4,293,778

ANTI-THEFT SCREEN CONSTRUCTION

William H. Williams, Palos Verdes Peninsula, Calif., assignor to Sandstone, Inc., La Mirada, Calif.

Continuation-in-part of Ser. No. 883,488, Mar. 6, 1978, abandoned. This application Feb. 12, 1979, Ser. No. 11,099

Int. Cl.³ G08B 13/12


U.S. Cl. 307-147

28 Claims

1. A partially conductive security screen arrangement for use with an intrusion alarm system designed to operate in a normally closed sensing circuit condition and to produce a warning signal when the sensing circuit is broken, said arrangement comprising:

screen apparatus including a frame defining a central aperture, screening material comprising a mesh of interwoven strands covering said aperture and having a plastic coating, and means for securing the periphery of said screening material to said frame to close said aperture, said screen apparatus positionable to cover an opening in a building; electrically conductive means continuous between two ends

thereof, including wire means having a plastic coating and, at least partially overlying said screen apparatus, said wire means being bonded to the screening material by thermal fusing of the respective plastic coatings to prevent passage of a human being through said aperture unless said conductive means is severed,



means for connecting said conductive means at the two ends thereof into the sensing circuit as a series element thereof; whereby passage of a human being through the opening for said screen apparatus in position to cover said opening breaks the sensing circuit.

4,293,779

CONTROL OF POWER SEMICONDUCTORS THROUGH CENTER-TAPPED TRANSFORMER WITH SELF-DEMAGNETIZING CIRCUITRY

Johannes Nestler, and Hans Wrede, both of Berlin, Fed. Rep. of Germany, assignors to Licentia Patent-Verwaltungs-G.m.b.H., Frankfurt am Main, Fed. Rep. of Germany


Filed Feb. 22, 1979, Ser. No. 14,281

Claims priority, application Fed. Rep. of Germany, Feb. 23, 1978, 2808000

Int. Cl.³ H03K 17/60

U.S. Cl. 307-252 C

5 Claims



1. In a method for controlling a power semiconductor which can be triggered into conduction by pulses of one polarity and quenched again by pulses of the opposite polarity, by transmitting such pulses via a transformer to the power semiconductor connected at the secondary side of the transformer, the improvement comprising forming such a pulse by turning on a first transistor connected between one pole of a voltage source and a tap which divides the primary winding of the transformer into two partial windings, and by selectively turning on either one of second and third transistors each connected to the end of a respective partial winding, and terminating such a pulse by switching off the first transistor, while maintaining on the selected second or third transistor in order to cause the demagnetization current of the transformer to flow through the selected transistor and a first Zener diode connected between the tap of the primary winding and the other pole of the

voltage source, the anode side of the first Zener diode being connected to the tap of the primary winding.

4,293,780

DIGITAL INTEGRATED SEMICONDUCTOR CIRCUIT
Helmut Roesler, Munich, Fed. Rep. of Germany, assignor to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany


Filed Sep. 6, 1979, Ser. No. 72,975

Claims priority, application Fed. Rep. of Germany, Oct. 18, 1978, 2845379

Int. Cl.³ H03K 3/02

U.S. Cl. 307—262

12 Claims



1. In a digital integrated semiconductor circuit arrangement of the type having a clock pulse generator for supplying a first sequence of first clock pulses, a second sequence of second clock pulses and a third sequence of third pulses in phase with said second pulses, the sequences having the same frequency with the leading edge of each second pulse time-spaced from the trailing edge of the previous first pulse, and a circuit to be operated into a predetermined digital condition, the improvement therein comprising:

- a control pulse generator connected to the circuit to be operated for producing a control pulse to operate that circuit into the predetermined condition, said control pulse generator including
- an input transistor circuit including a first transistor having a controlled conduction path with input and output electrodes and a control electrode, a first logic circuit including first and second inputs and an output,
- an inverting second logic circuit including a first input a second input and an output which serves to provide said control pulse,
- said first inputs of said logic circuits connected to said output electrode of said first transistor circuit,
- a switch connected to apply a first potential to said input electrode,
- said control electrode connected to receive a first pulse to clock said input transistor circuit to apply a first logic signal pulse to said first inputs of said logic circuits,
- said output of said first logic circuit connected to said second input of said second logic circuit, said second input of said second logic circuit connected to receive the second pulse which follows the mentioned first pulse to clock said first logic circuit to provide a second logic signal pulse to said second logic circuit, said second logic circuit responsive to produce said control pulse defined by the leading edges of said first and second logic signal pulses, and
- a second transistor circuit including a second transistor having a controlled conduction path connected between said output electrode of said first transistor and a second potential and a control electrode connected to receive and operable in response to a third pulse to connect said first transistor to said second potential.

4,293,781

MONOSTABLE MULTIVIBRATOR

Tsuneo Yamada, and Yukihiko Miyamoto, both of c/o Trio Kabushiki Kaisha, 6-17, 3-Chome, Aobadai, Meguro-ku, Tokyo 153, Japan



Filed Dec. 8, 1978, Ser. No. 967,636

Claims priority, application Japan, Mar. 15, 1978, 53-29654; Mar. 15, 1978, 53-29655; Mar. 15, 1978, 53-29656

Int. Cl.³ H03K 3/284, 5/08, 17/16

U.S. Cl. 307—273

20 Claims



- 1. In a monostable multivibrator including a gate circuit having first and second inputs, a driver circuit responsive to the output of said gate circuit, a differentiating circuit responsive to the output of said driver circuit and a voltage comparison circuit responsive to the output of the said differentiating circuit where said gate circuit is adapted to have a trigger pulse applied to said first input thereof and the output of said voltage comparison circuit fed back to said second input thereof, the improvement in said monostable multivibrator where said driver circuit includes (a) at least one transistor of a differential transistor pair responsive to said output of the gate circuit for producing said output of the driver circuit, (b) a constant current source in circuit with said one transistor and (c) means for preventing saturation of said one transistor and where a clipping circuit clips the output of said driver circuit to lessen the effect of noise produced by said constant current source on the output of said multivibrator.

4,293,782

VOLTAGE DETECTING CIRCUIT

Kojiro Tanaka, Shozo Ochiai, and Hideki Noda, all of Tokyo, Japan, assignors to Kabushiki Kaisha Daini Seikosha, Tokyo, Japan

Filed Jan. 28, 1977, Ser. No. 763,598

Claims priority, application Japan, Jan. 28, 1976, 51/8237


Int. Cl.³ H03K 5/153

U.S. Cl. 307—350

3 Claims

- 1. A voltage detecting circuit comprising first and second lines connected respectively to terminals of a voltage source of which a predetermined drop in voltage is to be detected, a voltage divider and a first MOS transistor having a gate connected in series with one another between said lines, said voltage divider comprising first and second resistance means connected in series with one another with an intermediate tap

between them, first inverter means comprising a second MOS transistor having a gate and third resistance means connected in series with one another between said first and second lines with an output between said second MOS transistor and said third resistance means, means connecting the gate of said second MOS transistor with said tap, second inverter means comprising an N-MOS transistor and a P-MOS transistor each having a gate connected in series with one another between said first and second lines with an output providing a voltage



indicating signal between said N-MOS transistor and said P-MOS transistor, means connecting the output of said first inverter means with the gates of said N-MOS transistor and said P-MOS transistor and means for periodically applying a signal pulse to the gate of said first MOS transistor, the ratio of current to the conductive constant of said MOS transistor being above 0.1 whereby said predetermined drop in voltage is determined by the dividing ratio of said voltage divider with compensation for temperature variation.

4,293,783

STORAGE/LOGIC ARRAY


Sahas S. Patil, Salt Lake City, Utah, assignor to Massachusetts Institute of Technology, Cambridge, Mass.

Filed Nov. 1, 1978, Ser. No. 956,794

Int. Cl.³ H03K 19/177, 19/091; H04Q 3/00

U.S. Cl. 307—465

37 Claims



- 1. A programmable storage/logic array comprising
- A. a set of substantially parallel column conductors including a plurality of non-intersecting subsets,
- B. a set of substantially parallel row conductors including a plurality of non-intersecting subsets, said row conductors being orthogonal to said column conductors,
- C. a plurality of cell networks, each of said cell networks being associated with one of said subsets of column conductors, and one of said subsets of row conductors, wherein at least one of said cell networks includes a storage element, and
- wherein at least one of said cell networks includes programmable cell contact means for selectively coupling said cell network to its associated row and column conductors, and wherein said storage element includes means for storing a signal representative of the binary state of one of the conductors of said coupled subsets of column and row conductors, and means for coupling said stored signal to

one of the conductors of said coupled subsets of column and row conductors.

4,293,784

INSULATED POLE AND COIL ASSEMBLY AND METHOD OF MAKING SAME


Joseph J. Zdaniewski; William B. Penn, and Roy L. Balke, all of Erie, Pa., assignors to General Electric Co., Schenectady, N.Y.

Filed May 21, 1979, Ser. No. 41,170

Int. Cl.³ H02K 15/12

U.S. Cl. 310—45

9 Claims



- 1. An insulated pole and coil assembly for a dynamoelectric machine, said assembly comprising a pole member having a base portion and two tip portions that protrude respectively from opposite sides of said base portion, a coil of insulated magnet wire having a central opening formed therein and fitted closely around said pole base portion, a plurality of formed sheets of insulating material each including a back part and a lip part, each of said sheets being positioned with its back part extending around and a predetermined distance beyond a respective corner of said pole base portion with the lip parts of the respective sheets facing and conforming closely to the adjacent coil surface and the respective surfaces of the pole tip portions that are juxtaposed with said coil, thereby to insulate the coil from the pole member by positioning the ends of each of said sheets in overlapping relationship with the ends of adjacent sheets and to cover all of the sides and corners of said pole base portion that are surrounded by said coil and to cover the surfaces of said pole tip portions closest to said coil.

4,293,785

ROTATING ELECTRIC MACHINES WITH ENHANCED RADIATION COOLING


John T. Jackson, Jr., St. Paul, Ore., assignor to Jackson Research, Inc., St. Paul, Ore.

Continuation-in-part of Ser. No. 939,804, Sep. 5, 1978, abandoned. This application Oct. 1, 1979, Ser. No. 80,452

Int. Cl.³ H02K 9/00; F28F 27/00; B05D 5/12

U.S. Cl. 310—64

6 Claims



- 1. A rotary electrical machine having a cylindrical rotor and a stator encompassing said rotor, said rotor having an outer

surface and said stator having an inner surface opposing said outer surface of said rotor, each of said surfaces having a respective coating thereon having a higher emissivity for thermal radiation than the emissivity of the respective surface of said rotor or stator which underlies the respective coating, the respective emissivities for thermal radiation of said coatings being such that the effective emissivity for thermal radiation between said coatings is at least about 0.65 in a temperature range for said coatings of about 75° C.-150° C., the absorptivity for thermal radiation of the coating on the inner surface of said stator being greater than the absorptivity of said inner surface of said stator and being at least about 0.65 in said temperature range.

4,293,786

CARRYING AND GUIDING SPIDER FOR THE SUPPORT OF A ROTOR OF A VERTICAL ELECTRICAL MACHINE Mihailo Starcevic, Mellingen, Switzerland, assignor to BBC Brown, Boveri & Company, Limited, Baden, Switzerland


Filed Nov. 14, 1979, Ser. No. 93,973

Claims priority, application Switzerland, Nov. 15, 1978, 11728/78

Int. Cl.³ H02K 5/00

U.S. Cl. 310—157

7 Claims



1. A carrying and guiding spider for supporting a rotor of a vertical electrical machine, said machine including an annular foundation surrounding a central body supporting said rotor, said spider comprising:

at least one first arm having one end clamped to said central body at a first clamping point and having another end extending to said foundation and horizontally slidably resting on said foundation;

at least one second arm having one arm clamped to said central body at a second clamping point and having another end extending to said foundation and fixed to said foundation;

wherein said at least one first arm forms a first acute circumferential angle with a radial line passing through said first clamping point and wherein said at least one second arm forms a second circumferential angle with a radial line passing through said second clamping point, said first and second angles being of equal magnitude but of opposite sense.

4,293,787

STATOR WINDING HOLDING STRUCTURE FOR ROTARY ELECTRIC MACHINE

Motoya Ito; Masaki Sato; Masatoshi Watanabe, and Hironori Okuda, all of Hitachi, Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Filed Jan. 12, 1979, Ser. No. 3,012

Claims priority, application Japan, Feb. 24, 1978, 53/19697


Int. Cl.³ H02K 1/00

U.S. Cl. 310—181

9 Claims

1. In a rotary electric machine comprising an annular stator core having a plurality of axially extended core teeth to form coil slots therebetween at regular intervals in the circumferential direction in the inner surface of said annular stator core, a

stator winding mounted in said coil slots of said stator core through a predetermined insulating material, a plurality of non-magnetic wedges fitted into said coil slots for securely holding said stator winding in said coil slots, a rotor core mounted in the annular hollow portion of said stator core and formed axially shorter than said stator core, a rotor winding wound on said rotor core and having an end portion protruded axially from said core, a coil retaining ring of an electrically



conductive material for securely holding the end portion of said rotor winding and a rotary shaft for holding said rotor core; the improvement further comprising magnetic transmission means for magnetically connecting adjacent teeth of said stator core, said magnetic transmission means being provided in said stator slots only at portions opposed to said coil retaining ring for facilitating transmission of magnetic flux from said stator to said rotor through said portions of said stator slots having said magnetic transmission means.

4,293,788

THREE-PHASE VEHICULAR GENERATOR CONSTRUCTION

Georg Binder, Bechhofen, Fed. Rep. of Germany, assignor to Robert Bosch GmbH, Stuttgart, Fed. Rep. of Germany


Filed May 25, 1979, Ser. No. 42,361

Claims priority, application Fed. Rep. of Germany, Jun. 20, 1978, 2826930

Int. Cl.³ H02K 9/28

U.S. Cl. 310—227

5 Claims



1. Generator structure for use in mobile or vehicular application to supply on-board power for a self-contained network, in combination with a voltage regulator, wherein the generator has end bells (1, 2) defining a housing, a stator (7) located in the housing; a shaft (13) rotatable in the housing; a rotor (10) secured to the shaft and rotatable within the stator; slip rings (12a, 12b) secured to the shaft; a brush holder (16a) located within the housing; brushes (17a, 17b) located in the brush holder and engaging the slip rings; wherein a holder plate (19) is provided said brush holder (16a) and the brushes therein, and said voltage regulator (16b) being secured to said plate and forming a brush holder—voltage regulator assembly (16);

the end bell (2) adjacent the slip rings is formed with an opening (20) therein of such size that the brush holder—regulator assembly can pass therethrough from the outside for positioning of the brushes in the brush holder against the slip rings, and the entire assembly within the housing,

said plate being larger than said opening (20) in the end bell and being fitted against and closing off said opening; and means (15) supplying cooling air to the interior of the housing and positioned to direct cooling air to said brush holder—regulator assembly within the housing to place the brush holder and the regulator in the stream of cooling air being supplied into the housing comprising a duct element extending radially outwardly from the end bell (2) adjacent the slip rings and at least approximately aligned with said brush holder—voltage regulator assembly (16).

4,293,789

DYNAMOELECTRIC MACHINE BRUSH RIGGING


Dallas E. King, Dayton, Ohio, assignor to General Motors Corporation, Detroit, Mich.

Filed Sep. 10, 1979, Ser. No. 74,387

Int. Cl.³ H02K 13/00

U.S. Cl. 310—239

4 Claims



1. An end cap assembly for a dynamoelectric machine comprising, an end cap having bearing means adapted to receive the shaft of a dynamoelectric machine rotor, at least one brush holder extending radially of said end cap, a brush slidably supported by said brush holder, resilient means for urging said brush radially of said end cap, and an annular brush retainer having outer wall means engaging and slidably supported by internal wall means of said end cap for movement axially of said end cap, said retainer having a central opening, said internal wall means of said end cap extending axially of said bearing means, a portion of the outer wall means of said brush retainer engaging an end of said brush to hold said brush in a retracted position against the force of said resilient means, said brush retainer being axially movable toward said bearing means along said internal wall means by engagement with a dynamoelectric machine rotor when the shaft of the rotor is inserted through said central opening in said retainer and into said bearing means to thereby move said brush retainer to an assembled position in contact with said internal wall means and out of engagement with the end of said brush to permit said brush to contact a rotary current conducting means of said dynamoelectric machine rotor.

4,293,790

IMAGE CONVERTER HAVING CYLINDRICAL HOUSING AND PHOTOCATHODE SEPARATED BY SPACING ELEMENT FROM LUMINESCENT SCREEN ON FRUSTUM

Hans-Wolfgang Funk, Hirschberg; Kurt Frank, and Günter Flasche, both of Darmstadt, all of Fed. Rep. of Germany, assignors to Robert Bosch GmbH, Stuttgart, Fed. Rep. of Germany

Continuation of Ser. No. 748,502, Dec. 18, 1976, abandoned.


This application Dec. 6, 1978, Ser. No. 967,620

Claims priority, application Fed. Rep. of Germany, Dec. 10, 1975, 2555438; Nov. 15, 1976, 2652070

Int. Cl.³ H01J 40/02, 40/18

U.S. Cl. 313—101

8 Claims



1. An image converter which is designed to prevent arcing caused by avalanche discharge from taking place during operation, comprising:

a flat and circular entrance window with an inner surface and an outer surface;
a flat and circular photocathode centered on and attached to the inner surface of the entrance window;
a flat and circular exit window with an inner surface and an outer surface and having a central frustum-shaped platform extending towards the entrance window;
a flat and circular luminescent screen centered on top of the platform and parallel to the windows and being sized substantially equally to the photocathode; and
a hollow, unitary and generally cylindrical housing connected to the entrance window and the exit window in a manner that the windows are aligned and parallel to each other, the housing having an interior surface which is circular in cross-section and further having a minimum internal diameter adjacent the entrance window and the photocathode, a maximum internal diameter adjacent the exit window and an intermediate internal diameter which increases linearly between said minimum internal diameter and said maximum internal diameter, the diameters of the housing being such that avalanche discharge around the interior surface of the housing is minimized.

4,293,791

COLOR PICTURE TUBE HAVING IMPROVED CORRUGATED APERTURE MASK

Ralph J. D'Amato, Lancaster, Pa., assignor to RCA Corporation, New York, N.Y.

Filed Nov. 15, 1979, Ser. No. 94,464


Int. Cl.³ H01J 29/07

U.S. Cl. 313—403

4 Claims

1. In a color picture tube having a corrugated mask wherein the mask corrugations are substantially parallel, said mask having slit shaped apertures aligned in columns parallel to the mask corrugations, the slits in each column being separated by web portions of the mask, said tube including an electron gun for generating a plurality of electron beams and means for

scanning said beams in lines across the mask the improvement comprising



the web repeat distance within a slit column being proportional to the distance from the major axis of the mask to the mask intercept of any particular scan line.

4,293,792

COLOR PICTURE TUBE HAVING IMPROVED SLIT TYPE SHADOW MASK


Donald L. Roberts, Conestoga, Pa., assignor to RCA Corporation, New York, N.Y.

Filed Dec. 18, 1979, Ser. No. 104,828

Int. Cl.³ H01J 29/07, 29/18

U.S. Cl. 313-403

4 Claims



1. In a color picture tube having a cathodoluminescent screen, an electron gun, and a slit type apertured mask located between the screen and gun, wherein the slits in said mask are arranged in vertical columns and the slits in each column are vertically separated by webs, the improvement comprising alternate webs within a column being of lesser thickness than the general mask thickness with the geometric center of the alternate webs being offset toward the screen side of the mask.

4,293,793

FLUORESCENT DISPLAY TUBE

Masayuki Kojima; Masaki Kobayakawa, and Kozo Tanaka, all of Izumi, Japan, assignors to Nippon Electric Co., Ltd., Tokyo, Japan


Filed May 7, 1979, Ser. No. 36,510

Claims priority, application Japan, May 10, 1978, 53-63100[U]

Int. Cl.³ H01J 19/38, 63/06

U.S. Cl. 313-497

8 Claims



1. In a fluorescent display tube, an anode substrate having at least one display pattern of anode segments mounted thereon, said anode segments being excitable to emit light by electron

bombardment, said anode substrate having insulating regions within the pattern of anode segments, a cathode member extending over said anode substrate and said anode segments, and a grid member disposed between said anode substrate and said cathode member, said grid member having electron passage regions of relatively open mesh structure lying over said anode segments for permitting electrons to pass through to said anode segments, said grid member having shielding regions of relatively fine mesh structure lying over said anode substrate insulating regions within said pattern of anode segments, said shielding regions being characterized in that they inhibit passage of electrons to said anode substrate while permitting light to pass therethrough.

4,293,794

GENERATION OF INTENSE, HIGH-ENERGY ION PULSES BY MAGNETIC COMPRESSION OF ION RINGS


Christos A. Kapetanakis, 6101 Overlea Rd., Bethesda, Md. 20016

Filed Apr. 1, 1980, Ser. No. 136,227

Int. Cl.³ H01J 3/04

U.S. Cl. 315-111.81

13 Claims



1. A system for generating intense (high-current), high-energy ion pulses, and propagating the pulses independent from a requirement for an applied external magnetic field, guide tube, or other applied guiding means, comprising:
means for forming a magnetic field, said field having axial and radial components, and said field including a magnetic mirror having near and far mirror peaks;
means for forming a hollow beam of ions, the axis of said beam coinciding with the axis of said magnetic field, said ions having translational energy and translational velocity, v_z ;
means for providing rotational energy and a rotational velocity, v_θ , to said ions and causing the ions to rotate;
means for forming a ring of ions, inside the magnetic mirror, said ions having rotational and translational energy;
means for increasing the rotational energy of said ions;
means for extracting said ring of ions;
means for separating the ions from any electrons which may be intermixed with the ions; and
means for increasing said translational energy of the ions, said extracted ions having rotational and translational energy, said ions forming rotational and translational current densities, J_θ and J_z , respectively, said J_θ producing a self-magnetic field, B_θ , and said J_z producing a self-magnetic field, B_z , said J_z and B_θ producing an inward force, $J_z B_\theta$, for inhibiting radial expansion of the beam and maintaining equilibrium of the beam during propagation.

4,293,795

SOLID STATE FLASHER RELAY

Carlo Fields, Woodland, Calif., assignor to Southern Pacific Transportation Company, San Francisco, Calif.

Filed Jan. 11, 1980, Ser. No. 111,320


Int. Cl.³ H05B 39/06

U.S. Cl. 315-200 A

21 Claims

1. A flasher relay of the type wherein an AC or DC input voltage provided across first and second loads interconnected

in series at a common junction can be selectively applied across said first load or said second load,
said input voltage is applied to said first and second loads via first and second input, lines, said relay comprising:
first solid state shunting means for shunting said first load so that said input voltage is applied across said second load;
second solid state shunting means for shunting said second load so that said input voltage is applied across said first load;
means for selectively controlling said first and second means so as to alternately shunt said first and second loads;
said first solid state shunting means comprising,
a first shunting transistor connected between said first input line and said common junction, said first transistor being chosen to conduct when a voltage potential across said first and second loads is of one polarity and said first transistor is biased on and a second shunting transistor connected between said first input line and said common junction, said second transistor being chosen to conduct when a voltage potential across said first and second loads is of the other polarity and said second transistor is biased on;
said means for selectively controlling comprises means for biasing said first and second transistors so that said first input



line is continually shunted to said common junction by either said first or second transistor regardless of the polarity of the input voltage across said first and second loads; and
said second solid state shunting means comprises,
a third shunting transistor connected between said second input line and said common junction, said third transistor being chosen to conduct when a voltage potential across said first and second loads is of one polarity and said third transistor is biased on;
a fourth shunting transistor connected between said second input line and said common junction, said fourth transistor being chosen to conduct when a voltage potential across said first and second loads is of the other polarity and said fourth transistor is biased on; and
said means for selectively controlling further comprises means for preventing said third or fourth transistor from conducting when either said first or second transistor is conducting, means for biasing said third and fourth transistors so that said second input line is continuously shunted to said common junction by either said third or fourth transistor regardless of the polarity of the input voltage across said first and second loads, and means for preventing said first or second transistor from conducting when either said third or fourth transistor is conducting.

4,293,796

TRAFFIC LIGHT DIMMING TECHNIQUE AND CIRCUITRY


Clyde H. McMorow, 1701 Fortune Dr., San Jose, Calif. 95131

Filed Jan. 7, 1980, Ser. No. 110,140

Int. Cl.³ H05B 37/02, 39/06

U.S. Cl. 315-205

2 Claims



1. A traffic light switching circuit for connecting to an alternating current power source at least one conductor to which a traffic light is connected for energization in response to an input control signal, comprising:
a three-terminal switching device connected to provide an electrical connection between said conductor and said alternating current source through two terminals of said switching device in response to a control signal applied to a third terminal thereof, said three-terminal switching device being characterized by conducting between its said two terminals after an appropriate control signal is applied to its control terminal and continuing to conduct until the current therethrough goes to zero at which time the switching device ceases to conduct until another appropriate signal is applied to its control terminal, and said control signal generating means including a full wave rectifier connected for one leg to be disabled in response to one state of said external signal, whereby such disablement causes said switching device to conduct for only one-half of each cycle of said alternating current power source, and
means connected to said alternating current power source and responsive to an external signal for generating said control signal in a manner to apply either a full wave alternating current signal to said control terminal or a half-wave signal thereto depending upon the state of said external signal, whereby a light connected to said at least one conductor may be operated at one of two brightness levels depending upon the state of said external signal.

4,293,797

INDUCTIVE-CAPACITIVE CYCLIC CHARGE-DISCHARGE IGNITION SYSTEM

Martin E. Gerry, 13452 Winthrop St., Santa Ana, Calif. 92705

Continuation-in-part of Ser. No. 35,013, May 1, 1979,

abandoned. This application Jan. 16, 1980, Ser. No. 112,533

Int. Cl.³ H05B 37/02, 39/04, 41/36


U.S. Cl. 315-209 R

8 Claims

1. An inductive-capacitive cyclic charge-discharge ignition system for providing a plurality of ignition periods, comprising the combination of:

an ignition transformer having a primary winding;
a capacitor connected to the primary winding and forming a parallel circuit with said primary winding;
AC generating means having an output winding in series with said parallel circuit for powering said parallel circuit with AC energy during each said ignition period, said


output winding and parallel circuit forming a passive switchless network; and



timing means coupled to said AC generating means for controlling DC bias current to said generating means so as to duty cycle said generating means.

4,293,798
INDUCTIVE-CAPACITIVE CYCLIC CHARGE-DISCHARGE IGNITION SYSTEM
 Martin E. Gerry, 13452 Winthrop St., Santa Ana, Calif. 92705
 Continuation-in-part of Ser. No. 35,013, May 1, 1979, abandoned. This application Jan. 16, 1980, Ser. No. 112,714
 Int. Cl.³ H05B 37/02, 39/04, 41/36
 U.S. Cl. 315—209 R

10 Claims



1. An inductive-capacitive cyclic charge-discharge ignition system for providing a plurality of ignition periods, comprising the combination of:

- an ignition transformer having a primary winding;
- a first capacitor connected to the primary winding and forming a parallel circuit with said primary winding;
- a second capacitor in series with the parallel circuit;
- AC generating means having an output winding in series with the second capacitor for powering said second capacitor and parallel circuit with AC energy during each said ignition period, said output winding, second capacitor and parallel circuit forming a switchless output network; and


timing means coupled to said AC generating means for controlling DC bias current to said generating means so as to duty cycle said generating means.

9. The method as stated in claim 8, including the further step of:

- (e) creating an electrical arc between an electrically conductive tubular base and an electrode of said igniter, said arc having a filament of luminous particles extending between said base and electrode and a mass of luminous particles of lesser density than said filament which surrounds said filament.

4,293,799
POWER SUPPLY SYSTEMS
 Frank B. Roberts, Gateshead, England, assignor to Victor Products (Wallsend) Limited, Wallsend, England
 Filed Nov. 19, 1979, Ser. No. 95,384
 Claims priority, application United Kingdom, Oct. 5, 1979, 34722/79


Int. Cl.³ H05B 41/24
 U.S. Cl. 315—256 9 Claims



1. A power supply system for supplying electrical power to a plurality of fluorescent lamps in a potentially hazardous atmosphere, comprising a power supply which produces a substantially constant current output at a frequency in a range of about 1 kHz to about 500 kHz; a plurality of transformers each having a primary winding and a secondary winding; means to couple said primary windings of all of said transformers together in a series circuit; means to couple at least one respective fluorescent lamp across each said transformer secondary winding; voltage control means connected between said power supply and said series circuit to control the voltage level applied to said series circuit by said power supply to ensure that the amount of electrical energy supplied to said transformer primary windings by said power supply cannot be incandive to the atmosphere; and capacitance means coupled in said series circuit to reduce the reactance of said series circuit whereby an increased number of said lamps can be started for a given value of said applied voltage level.

4,293,800
DOUBLE-ENDED THYRATRON HAVING AT LEAST THREE GRIDS
 Hugh Menown, Writtle, England, assignor to English Electric Valve Company, Chelmsford, England
 Continuation of Ser. No. 909,259, May 24, 1978, abandoned, and a continuation of Ser. No. 780,486, Mar. 23, 1977, abandoned.
 This application Jun. 8, 1979, Ser. No. 46,902
 Claims priority, application United Kingdom, Mar. 27, 1976, 12415/76

Int. Cl.³ H01J 17/12
 U.S. Cl. 315—350 9 Claims




9. A double-ended thyatron comprising, in combination: an envelope having a pair of cathodes disposed in spaced apart relation therewithin; and a first set of at least three grids adjacent one of said cathodes and a second set of at least three grids adjacent the other of said cathodes, the grids of each set being disposed in serially spaced fashion with the final grids of the two sets being disposed in remotely spaced, opposing relation and there being means providing at least one voltage with-

standing gap between said first and second sets of grids, each set being exclusive of said means and comprising a first grid disposed closest to the associated cathode and adapted to receive an electrical potential independently of the remainder of the grids of that set whereby independently to receive a current bias, an intermediary grid between such first grid and the final grid of that set and adapted to receive an electrical potential independently of the remainder of the grids of that set whereby independently to receive a trigger pulse, and said final grid which is electrically connected to its associated cathode.


4,293,801
CATHODE RAY TUBE ASSEMBLIES
 Frank Cook, Rochdale, and Gordon H. Davies, Wilmslow, both of England, assignors to Thorn EMI Limited, Rochdale, England
 Filed Mar. 5, 1980, Ser. No. 127,527
 Claims priority, application United Kingdom, Mar. 6, 1979, 07913/79

Int. Cl.³ H01J 29/56
 U.S. Cl. 315—370 6 Claims



1. A cathode ray tube assembly having a circuit arrangement to connect the heater of the cathode ray tube to an associated D.C. supply, to energise the heater, there also being included in the circuit arrangement at least one component of the cathode ray tube assembly to be energized by the associated D.C. supply, together with a matrix of asymmetrical conducting devices arranged such that the current flow through each of said at least one component individually is in one predetermined direction, irrespective of the direction of the flow of current from the associated D.C. supply to the circuit arrangement.


4,293,802
TRANSRESONANT DEFLECTION YOKE OPERATIONS
 Trung Le, Austin, Tex., assignor to International Business Machines Corporation, Armonk, N.Y.
 Filed Dec. 19, 1979, Ser. No. 105,322
 Int. Cl.³ H01J 29/70
 U.S. Cl. 315—387 10 Claims



1. In a CRT display system having a deflection yoke having frequency characteristics defined by the inductance of and the distributed capacitance across said yoke and a driving amplifier circuit therefor, said circuit having an output connected to a first end of said yoke and a summing node receiving a signal corresponding to a desired CRT beam deflection and a feed-

back signal related to deflection yoke current, the improvement comprising:
 a second-order feedback network including the equivalent of only two energy storage devices, said feedback network being tuned to said yoke frequency characteristics and having only one input terminal, one output terminal, and a ground terminal;
 means for connecting said input terminal to a second end of said deflection yoke and said output terminal to said summing node; and
 means for applying a signal from said feedback network to said summing node of said driver amplifier circuit, said signal being related by a constant factor to the instantaneous inductive current flow through said deflection yoke.

4,293,803
VERTICAL DEFLECTION CIRCUIT
 William V. Fitzgerald, Indianapolis, Ind., assignor to RCA Corporation, New York, N.Y.
 Filed Feb. 4, 1980, Ser. No. 118,120
 Int. Cl.³ H01J 29/70
 U.S. Cl. 315—397 4 Claims




1. A resonant retrace vertical deflection circuit for a television receiver comprising:
 a source of vertical deflection signals;
 a yoke coupled to said signal source for providing vertical deflection of an electron beam in accordance with a deflection cycle having trace and retrace intervals;
 a first source of potential;
 means for utilizing a diode to complete a path for current flow from said first potential source to said yoke during a given portion of said trace interval and to disrupt said path during the remainder of said trace interval and during at least a major portion of said retrace interval;
 a capacitor coupled for resonating with said yoke during said retrace interval portion;
 a second source of potential, providing a potential of greater magnitude than the potential provided by said first source; and
 means including first and second impedance means respectively coupled to said first and second sources, and to said capacitor for coupling a portion of the potential of said second source to said capacitor for charging said capacitor during said remainder of said trace interval, said portion of said second source potential determined by the ratio of said first and second impedance means.

4,293,804
RASTER-CENTERING CIRCUIT
 Joseph F. Yello, Wooddale, Ill., assignor to Zenith Radio Corporation, Glenview, Ill.
 Filed Feb. 22, 1980, Ser. No. 123,546
 Int. Cl.³ H01J 29/54
 U.S. Cl. 315—398 2 Claims

1. A cathode ray tube raster-generating and centering circuit comprising:

deflection drive means for providing a varying sweep current;
deflection coil means having one end coupled to said deflection drive means in such manner that said sweep current flows through said deflection coil means and the voltage of said one end is controlled entirely by the output of said deflection drive means;



means forming a voltage divider with opposite ends clamped at respective different D.C. voltages and center tap means adjustable within a voltage range between said D.C. voltages;
and means connecting said center tap means to the other end of said deflection coil means whereby to control the D.C. voltage of said other end.


4,293,805

SENSING AND CONTROL APPARATUS FOR A COMMUTATOR

Allan S. Warner, 50 Haliday St., Clark, N.J. 07066
Filed Jun. 25, 1979, Ser. No. 52,122
Int. Cl.³ B23Q 5/10, 5/28

U.S. Cl. 318—39

13 Claims



1. Apparatus for sensing a predetermined location on a commutator and, in response thereto, actuating a tool for performing an operation on said commutator, comprising:
means for mounting and rotating said commutator;
a light source positioned a predetermined distance from the surface of said commutator;
first means for directing light from said light source to the surface of said commutator;
means for sensing the reflection of light from said commutator surface;
second means for directing light reflected from said commutator surface to said sensing means;
means responsive to said sensing means for actuating said tool for performing an operation on said commutator;
protective means at least partially enclosing said first and second light-directing means for preventing the interference of ambient and/or stray light with the operation of said sensing means, said protective means including a housing having a first end in rubbing engagement with said commutator surface and a second end for receiving the ends of said first and second light-directing means and spacing said ends of said first and second light-directing means from said first end of said housing to form a space within said housing between said ends of said first and second light-directing means and said first end of said housing; and

supplying means for supplying air under pressure into said space and directly onto said commutator surface.


4,293,806

SINGLE AND MULTICYCLE CONTROL DEVICE FOR ELECTRIC MOTORS

Leo Kull, 58 Westover Ave., West Caldwell, N.J. 07006, and
Vello H. Ebrok, 376 Prospect St., East Orange, N.J. 07017
Filed May 21, 1979, Ser. No. 40,720
Int. Cl.³ G05B 11/14

U.S. Cl. 318—673

16 Claims



1. A cycle control device for controlling the rotation of an electric motor driven output shaft comprising:
a parallel switching circuit for energizing said electric motor, said circuit having normally open first and second switching means in each branch of said circuit, a latchable actuating means for closing and maintaining the closure of said first switching means for starting the rotation of said output shaft,
an actuating means controlled by the motion generated by said output shaft, said actuating by means closing said second switching means before the opening of said first switching means and thereafter opening said second switching means to terminate the rotation of said output shaft, and a feedback means actuated by the rotation of said output shaft, said feedback means unlatching said latchable actuating means leading to an opening of said first switching means.


4,293,807

STEPPING MOTOR CONTROL APPARATUS

George W. Foster, Middleton, Wis., and Alain M. Bonneyrat, St-Martin-du-Tertre, France, assignors to Gilson Medical Electronics (France), Villiers-le-Bel, France
Filed Oct. 29, 1979, Ser. No. 89,191
Claims priority, application France, Nov. 2, 1978, 78 31023
Int. Cl.³ G05B 19/40

U.S. Cl. 318—696

6 Claims



1. In an apparatus for controlling a stepping motor having its

windings grouped by pairs while two windings of the same pair cannot be supplied simultaneously, said apparatus comprising means receiving a control signal, supply circuits adapted to controllably feed the individual windings of the stepping motor with respective electric currents, and a selection circuit adapted to selectively actuate the supply circuits depending upon said control signal, and adapted to further define an indication of gradation of the control current of each winding in accordance with the control signal, the improvement comprising a resistor associated with each pair of windings and a pair of switch means respectively arranged between one end of the two windings of a pair thereof and the associated resistor, said supply circuits feed in common the other end of the two windings of a respective pair thereof, with a current, the amplitude of which is defined by said indication of gradation and the fed current energizing the one of said windings being selected by said switch means.

4,293,809

Patent Not Issued For This Number

4,293,810

CONTROL SYSTEMS FOR ELECTRIC GENERATORS

Michael J. Wright, Stamford, England, assignor to Newage Engineers Limited, Stamford, England
Filed Apr. 10, 1979, Ser. No. 28,697
Claims priority, application United Kingdom, Apr. 12, 1978, 14358/78

Int. Cl.³ H02P 9/10, 9/30

U.S. Cl. 322—28

21 Claims

4,293,808


BATTERY CHARGING DEVICE EMPLOYING SOLAR CELLS

Peter F. Varadi, and Ramon Dominguez, both of Rockville, Md., assignors to Solarex Corporation, Rockville, Md.
Filed Apr. 14, 1978, Ser. No. 896,451


Int. Cl.³ H02J 7/00

U.S. Cl. 320—2

15 Claims



1. A device for charging a battery, comprising a container having parts movable between open and closed positions and having an array of solar cells disposed in light-receiving position thereon, said array having positive and negative electrical terminals, said container being formed with at least one part adapted to receive a battery therein, and the other of said parts including a first electrical contact connected to one of said array terminals and adapted to contact one terminal of said battery, a second electrical contact in said battery receiving part, the other terminal of said battery in said receiving portion being in contact with said second electrical contact, a third movable contact is electrically connected to said second electrical contact and adapted to be electrically connected to the other terminal of said solar array, and said third movable electrical contact moving into electrical connecting relationship with said other terminal of said solar cell array in a plane transverse to said first electrical contact and said first electrical



1. In a control system including a thyristor for controlling a generator having an excitation winding by which the excitation of the generator is produced or controlled, the excitation winding being connected, through the thyristor forming part of the control system, to at least one alternating current output terminal of the generator, the output terminal or terminals to which the excitation winding is connected together providing a waveform which is interrupted or changes polarity during each cycle of the waveform, thereby allowing the thyristor to turn off, the control system also including firing means arranged to fire the thyristor at a moment during the waveform which varies with variations in the required excitation, and the control system also including a starting excitation current path leading from an alternating current output terminal or terminals of the generator to the excitation winding, the improvement comprising providing in the said starting excitation cur-

rent path, means arranged, by varying the conductivity of the said means, to limit the current in the path to a value which is greater than the latching current of the thyristor.

4,293,811

VOLTAGE REGULATOR SYSTEM FOR VEHICLE GENERATOR

Katsuya Muto, Kariya; Kazumasa Mori, Aichi; Akira Mase, Handa; Takayasu Nimura, Nagoya; Katsumi Itoh, Obu, and Yoshio Akita, Ichinomiya, all of Japan, assignors to Nippondenso Co., Ltd., Kariya, Japan


Filed Mar. 19, 1979, Ser. No. 21,805

Claims priority, application Japan, Apr. 20, 1978, 53-47545

Int. Cl.³ H02J 7/16

U.S. Cl. 322-60

6 Claims



1. A voltage regulator for battery charging generator having a field exciting coil for an internal combustion engine having a starter motor comprising:

a switching circuit for supplying field exciting current in a controlled manner,

a battery voltage regulating circuit for controlling the switching operation of said switching circuit in response to the battery voltage,

first means for generating a first signal for a predetermined period of time in response to engine starting,

second means connected to said first means for causing said switching circuit to be nonconductive normally and to be conductive when said first signal is applied thereto, and

third means for causing said switching circuit to be conductive in response to operation of said generator independently of said first means until said battery voltage regulating circuit starts controlling.

4,293,812

CONTROLLED D-C CURRENT SUPPLY SYSTEM, WITH CONTROLLED CURRENT FLOW THROUGH A CHOKE

Hans Kubach, Korntal-Münchingen, and Hartmann Rupp, Kornwestheim, both of Fed. Rep. of Germany, assignors to Robert Bosch GmbH, Stuttgart, Fed. Rep. of Germany

Filed Sep. 26, 1979, Ser. No. 79,159

Claims priority, application Fed. Rep. of Germany, Sep. 23, 1978, 2841569

Int. Cl.³ H03K 3/01, 17/84

U.S. Cl. 323-272

10 Claims

1. Controlled d-c current supply system for connection to a d-c source (10) and to supply current to a load having


a controlled semiconductor switch (11) having a control terminal;

a choke coil (13) having windings serially connected with the switching path of the semiconductor switch;

a free-wheeling diode (12) connected between the switching path of the semiconductor switch and the choke coil;

a capacitor (14) connected to the choke coil at the side thereof remote from the free-wheeling diode;

means (20, 21, 22) providing conduction controlling pulses to the control terminal of the semiconductor switch to render the semiconductor switch cyclically conductive for controlled periods;



and means to sense current flow to the load to additionally control said pulse providing means comprising, in accordance with the invention, means (16, 16a, 16b, 15) connected across the choke and including a low-pass filter (15) to derive a signal representative of the d-c voltage drop (U_R) in the choke (13) due to the inherent resistance (R_{Cu}) of the windings thereof; and a current control stage (17) having said voltage-drop-representative-signal applied thereto and connected to said pulse providing means (20, 21, 22) to control the duty cycle of the pulse providing means as a function of the output of the current control stage.

4,293,813

CURRENT MEASURING SYSTEM

Maarten Groenenboom, Enter, Netherlands, assignor to Hazemeijer B.V., Hengelo, Netherlands

Continuation of Ser. No. 815,274, Jul. 13, 1977, abandoned. This application Feb. 22, 1979, Ser. No. 14,089

Claims priority, application Netherlands, Jul. 13, 1976, 7607752; Jun. 8, 1977, 7706316; Jun. 8, 1977, 7706317


Int. Cl.³ G01R 33/02, 1/20, 31/02

U.S. Cl. 324-117 R

7 Claims

1. A current measuring system, more particularly suitable for use as an earth leakage detection system, comprising a weak magnetic circuit having a primary winding to be traversed by a current to be measured and having a secondary winding, a reversible transistor switch network comprising four transistors connected in a bridge such that the emitter/collector paths of one pair of the transistors are connected between a first pair of points of said bridge whereas the emitter/collector paths of the other pair of the transistors are also connected between said first pair of points, in parallel with the

one pair of transistors, the bases of said one pair of transistors being connected through respective bias resistor means to a third point of said bridge and the bases of said other pair of transistors being connected through respective bias resistor means to a fourth point of said bridge, the transistors of each pair being of opposite conductivity type and the collectors of said one pair of transistors being connected to said fourth point and the collectors of said other pair of transistors being connected to said third point whereby only two of said transistors, one from each pair, are conducting at any one time and the polarity across said third and fourth points in relatively reversed when conduction is switched between those two transistors which are one transistor of each pair and those two transistors which are the other transistor of each pair, integrating load impedance means for producing an output signal in



response to unbalanced switching of said transistors, said secondary winding being connected in series with said load impedance means between said third and fourth points of said bridge, and a current limiting circuit means, for initiating switching of said transistors, a voltage source, said current limiting circuit means being connected across said source and in series with the source between said first pair of points of the bridge whereby the voltage across said first pair of points is abruptly reduced, when a predetermined limiting current value is reached by those two transistors conducting at that time, so that those two transistors conducting at that time are rendered non-conducting whereas the other two transistors are rendered conducting by the self inductance of said secondary winding thereby to switch the polarity across said secondary winding and the integrating load impedance.

4,293,814

CRANKSHAFT POSITION SENSOR CIRCUITRY FOR PROVIDING STABLE CYCLICAL OUTPUT SIGNALS WITHOUT REGARD TO PEAK TO PEAK VARIATIONS IN SENSOR SIGNALS


Wesley D. Boyer, Dearborn Heights, Mich., assignor to Ford Motor Company, Dearborn, Mich.

Filed Aug. 8, 1979, Ser. No. 64,699

Int. Cl.³ G01P 3/48, 3/54; G01B 7/14

U.S. Cl. 324-166

2 Claims



1. In an ignition system for an internal combustion engine, utilizing an electromagnetic sensor to monitor the crankshaft position in said engine, an improved circuit connected to said sensor for receiving a cyclical signal therefrom and generating

a corresponding output signal that is a synchronized replica of said cyclical signal having constant high and low peak values wherein said circuit includes:

a first differential amplifier having opposite polarity input ports connected to said electromagnetic sensor to amplify said input cyclical signal;

a negative feedback circuit which includes a plurality of diode connected transistors connected in series between the output of said first differential amplifier and one of its input ports to provide said amplified input cyclical signal at a plurality of junctions at incrementally separated D.C. voltage levels;

a first peak detection circuit connected to one of said diode connected transistors for sampling the high peak values of said amplified input cyclical signal output from said first differential amplifier to derive a high peak voltage level;

a second peak detection circuit connected to the output of said first differential amplifier for sampling the low peak values of said amplified input cyclical signal to derive a low peak voltage level;

a voltage divider circuit connected between said first peak detection circuit and said second peak detection circuit to supply a threshold voltage level at a preselected fractional value between said high and low peak voltage levels;

a comparator circuit having a first input port of one polarity connected to said voltage divider circuit to receive said threshold voltage level and a second input port of an opposite polarity connected to a junction between two of said diode connected transistors in said negative feedback circuit to receive said amplified input cyclical signal at a D.C. level intermediate that of said signal supplied to said first peak detection circuit and that of said signal output from said first differential amplifier, whereby the output of said comparator circuit switches between two distinct voltage levels whenever the amplified input cyclical signal crosses the threshold voltage level and is a voltage replica of said cyclical input signal having constant peak values.

4,293,815

FLUXGATE MAGNETOMETER CIRCUIT WITH EARTH'S FIELD ELIMINATION


Jerry B. West; John L. Kretzschmar, and Bing-Fai Fung, all of Tulsa, Okla., assignors to Century Geophysical Corporation, Tulsa, Okla.

Filed May 1, 1978, Ser. No. 901,778

Int. Cl.³ G01R 33/04; G01V 3/26

U.S. Cl. 324-254

4 Claims



3. An improved fluxgate magnetometer for operating at a stabilized point including an oscillator and a driver, a fluxgate ring core sensor and a drive coil excited by the oscillator and driver, a sense winding differentially wound around said core for sensing the difference in saturations of the earth's flux linkages in the core and circuit means for determining the polarity and magnitude of an error signal to be fed through the sense winding to eliminate the earth's field in the sensor for operating the magnetometer at a stabilized null point, wherein the improvement comprises:

means for integrating the error signal to be fed through the

sensor to provide the phase stability and memory for the magnitude of current to eliminate the earth's field, and high impedance current source driven by said integrating means for summing a DC current into the output of the sense winding in a direction and magnitude determined by the error signal circuit means to eliminate the effect of the earth's field in the fluxgate sensor to improve the operational stability of the magnetometer by operating at a null point.

4,293,816


BALANCED SEARCH LOOP FOR METAL DETECTOR
Douglas L. Johnson, Lebanon, Oreg., assignor to White's Electronics, Inc., Sweet Home, Oreg.

Filed Jul. 9, 1979, Ser. No. 55,696

Int. Cl.³ G01V 3/11

U.S. Cl. 324—329

13 Claims



1. A balanced search loop device, comprising:
a transmit inductor coil means;
means for applying an electrical signal to said transmit coil means to produce magnetic flux around the transmit coil;
a receive inductor coil means;
a magnetic flux feedback coil connected to said transmit coil so that its electromagnetic flux opposes the flux of the transmit coil in the region of the receive coil, the turns ratio of said transmit coil to said feedback coil being substantially the same as the ratio of the areas bounded by these coils to null balance the search loop in air; and
support means for supporting said feedback coil on said receive coil means throughout at least a major portion of its length to prevent movement of the feedback coil relative to the receive coil due to temperature changes or mechanical movement of said coils, and to position at least a major portion of said feedback coil between said receive coil and said transmit coil.

4,293,817

SIGNAL AMPLITUDE RANGE COMPRESSION EMPLOYING PULSE MODULATION
Glenn A. DeMichele, Melbourne, Fla., assignor to Rockwell International Corporation, El Segundo, Calif.

Filed Sep. 12, 1979, Ser. No. 74,642

Int. Cl.³ H03G 7/00; H03L 5/00


U.S. Cl. 328—169

1 Claim

1. For use with an amplitude varying signal which contains intelligence in its amplitude variations, a compressor comprising:

variable gain first means for receiving said amplitude varying signal and comprising (i) modulation means, responsive to said amplitude varying signal and a feedback signal, for outputting a signal comprising a train of pulses whose widths and heights are controlled, respectively, by said amplitude varying signal and said feedback signal, and (ii) demodulation means for converting said modulation means output signal into an amplitude varying, compressor output signal having a smaller range of amplitude variations than said amplitude varying signal, and feedback second means for developing said feedback signal

in response to input received from said first means, said feedback signal being appropriate for controlling the modulation means output signal pulse heights so as to effect in said first means gain change appropriate to reduce the range of amplitude variations in said compressor output signal relative to the range of amplitude variations



in said amplitude varying signal, said modulation means comprising (a) a comparator means for receiving said amplitude varying signal and a substantially triangular waveform, and for outputting a pulse width modulated signal and (b) pulse height control means responsive to said feedback signal for converting said comparator means output signal into said modulation means output signal.

4,293,818


FREQUENCY MODULATION THRESHOLD EXTENSION DEMODULATOR UTILIZING FREQUENCY COMPRESSION FEEDBACK WITH FREQUENCY DRIFT CORRECTION
Harold F. Jager, Rochelle Park, N.J., assignor to International Telephone and Telegraph Corporation, New York, N.Y.

Filed Jan. 22, 1979, Ser. No. 5,060

Int. Cl.³ H03D 3/18

U.S. Cl. 329—50

10 Claims



1. In a threshold extension receiver:
a source of frequency modulated radio frequency signals having a frequency deviation therebetween;
a mixer;
a local oscillator supplying local oscillations;
an intermediate frequency filter having a pass band substantially narrower than the frequency deviation of the said frequency modulated radio frequency signals;
means for feeding said source of frequency modulated radio frequency signals and the local oscillations to said mixer, to thereby produce intermediate frequency oscillations in said mixer, said intermediate frequency oscillations having an average frequency within the pass band of said intermediate frequency filter;

means for feeding the intermediate frequency oscillations of said mixer to said intermediate frequency filter, whereby the intermediate frequency filter will pass such components of said intermediate frequency oscillations as lie within the pass band;
negative frequency feedback means, responsive to the signals which are passed by the pass band of said intermediate frequency filter, for modulating the frequency of said local oscillator such as to cause the intermediate frequency oscillations produced by said mixer to have a reduced frequency deviation, compared to the frequency deviation of said radio frequency signals;
said negative feedback means having two independent feedback loops acting in parallel;
said first feedback loop comprising means, responsive to the average frequency of said intermediate frequency oscillations, for slowly causing said local oscillator to change frequency in such a sense as to maintain said average frequency at a desired value;
said second feedback loop comprising means, responsive to the instantaneous frequency of said intermediate frequency oscillations, for quickly causing said local oscillator to change frequency in such a sense as to drive the instantaneous frequency of said intermediate frequency oscillations towards said desired value; wherein
said first feedback loop comprises a band pass filter; and
said second feedback loop comprises a low pass filter; and
wherein
the pass bands of the low pass filter and the band pass filter have no pass band in common; wherein
said first feedback loop comprises:
a resonant tank circuit tuned to said desired value;
means to reactively and loosely couple said resonant tank circuit to the signals passed by said intermediate frequency filter;
whereby said resonant circuit will sympathetically resonate approximately in quadrature to said signals when the instantaneous frequency of said signals is at said desired value; and
whereby as the instantaneous frequency of said signals departs from said value, the phase relationship between said signals and the resulting sympathetic oscillations varies rapidly and monotonically with the departure;
a phase detector having a first and second input and whose output is the vector cross product of two inputs;
means to feed the voltage across said resonant circuit to the first input of said phase detector;
means to feed the signals passed by said intermediate frequency filter to the second input of said phase detector; and
means to feed the output of said phase detector to said local oscillator.

4,293,819

HIGH-SPEED LOW-DRIFT OPERATIONAL AMPLIFIER
Akinori Shibayama, Shakujidai; Kenji Maio, Hinode, and Norio Yokozawa, Fuchu, all of Japan, assignors to Nippon Telegraph and Telephone Public Corporation and Hitachi, Ltd., both of Tokyo, Japan

Filed Sep. 17, 1979, Ser. No. 76,428


Claims priority, application Japan, Sep. 20, 1978, 53-114629
Int. Cl.³ H03F 1/02

U.S. Cl. 330—9

5 Claims

1. An operational amplifier comprising:
first and second input terminals;
a coefficient circuit connected to said first and second input terminals and including a first operational amplifier, said first operational amplifier having a low drift characteristic;
a low pass filter connected to receive the output of said coefficient circuit; and
a second wide-band operational amplifier having first and second inputs and being connected to receive at one of the inputs thereof the output of said low pass filter and con-

nected to receive at the other input thereof a signal applied to said first input terminal; wherein said coefficient circuit includes said first operational amplifier having first and second inputs and being connected to receive at one of the inputs thereof a signal applied to said second input



terminal, a resistive element connected between said first input terminal and the other input of said first operational amplifier, and an impedance element connected between the said other input and the output of said first operational amplifier.

4,293,820


POSITIVE FEEDBACK BIQUAD FILTER
Chon T. L. Dinh, Brossard, Canada, assignor to Centre de Recherche Industrielle du Quebec, Pointe-Claire, Canada

Filed Aug. 23, 1979, Ser. No. 69,092

Int. Cl.³ H03F 1/34

U.S. Cl. 330—85

22 Claims



22. A positive feedback RC filter circuit comprising a passive input RC section, and an active amplification output section having at least one operational amplifier, said RC section having two true resistive T-networks and a true capacitive T-network and a single resistive feedback connection to realize a true second order function.

4,293,821

AUDIO CHANNEL SEPARATING APPARATUS
Angelo Boudouris, Sylvania, Ohio, and Edwin F. Peters, Lambertville, Mich., assignors to Eprad Incorporated, Toledo, Ohio

Filed Jun. 15, 1979, Ser. No. 48,840


Int. Cl.³ H04R 5/00

U.S. Cl. 330—126

3 Claims

1. Apparatus for separating two audio signals of varying

amplitudes appearing on two input channels into output audio signals on at least three output channels comprising first amplifier means for applying the signal on a first of said input channels to a first of said output channels, second amplifier means for applying the signal on the second input channel to a second of said output channels, third amplifier means for applying the sum of the signals on said first and second input channels to a third output channel, means for attenuating the signals to said third output channel when the signal on said first input channel is appreciably larger in amplitude than the signal on said second input channel, means for attenuating the signals to said third output channel when the signal on said second input channel is appreciably larger in amplitude than the signal on said first input channel, means for attenuating the signals to



said first and second output channels when the signals on said first and second input channels are substantially identical in amplitude, frequency and phase, means for generating a first control signal having an amplitude responsive to the average absolute value of the highest amplitude audio signal on said first and second input channels, means for generating a second control signal having an amplitude responsive to the average absolute value of the difference between the audio signals on said first and second input channels, differential amplifier means for generating a third control signal having an amplitude responsive to the absolute value of the difference between said first and second control signals, and wherein said means for attenuating signals to said first, second and third output channels are responsive to said third control signal.

4,293,822

GATED AGC AMPLIFIER WITH DC FEEDBACK


Robert J. McFadyen, Syracuse, N.Y., assignor to General Electric Company, Syracuse, N.Y.

Filed Nov. 9, 1979, Ser. No. 93,098

Int. Cl.³ H03F 3/45; H03G 3/30

U.S. Cl. 330-254

17 Claims



11. An amplifier circuit in the form of a cascade arrangement of amplification stages each including a differentially connected pair of first and second transistors, said circuit comprising:

- an input stage and at least one other stage,
- input means for applying an ac input signal to the base of the first transistor of said input stage,
- a dc bus coupled to the base of the second transistor of each stage of said amplifier circuit,
- a capacitor coupled to said dc bus for providing a virtual

ac ground to the base of each second transistor, said signal creating an ac imbalance between the first and second transistor of each stage, and

- dc feedback means coupled to said dc bus comprising bias control means for simultaneously charging and discharging said capacitor by currents respectively responsive to the currents flowing in said first and second transistors of said other stage, said charging and discharging currents being in a sense to achieve dc balance between the first and second transistors of said amplification stages.

4,293,823

BALANCED INPUT PHONOGRAPH PREAMPLIFIER CIRCUIT


Lindsey S. Hochberg, and Montague C. Borland, both of Houston, Tex., assignors to Logitek Electronic Systems, Inc., Houston, Tex.

Filed Aug. 28, 1979, Ser. No. 70,508

Int. Cl.³ H03F 3/45

U.S. Cl. 330-260

4 Claims



1. A balanced-input preamplifier circuit for phonographs for use with balanced and unbalanced input signals, said preamplifier circuit comprising:

- a differential voltage amplifier having a pair of inputs adapted to be coupled to the output of a phonograph cartridge having a pair of sides, one of said inputs being connectable to one of said sides and the other of said inputs being connectable to the other of said sides without referencing either of said inputs to ground;
- an input load resistance being coupled to said differential voltage amplifier, said load being applied to the output of a phonographic cartridge to which said preamplifier circuit is connected;
- a voltage amplifier having the input thereof coupled to the output of said differential voltage amplifier and the output thereof adapted to be interconnected with other amplifier circuitry of said phonograph;
- a feedback loop network bridging said input and output of said voltage amplifier, said feedback loop network being isolated from said cartridge and being designed in accordance with the specific curve characteristics specified by the Record Industry Association of America for deemphasis of signals received from phonographic recordings.

4,293,824

LINEAR DIFFERENTIAL AMPLIFIER WITH UNBALANCED OUTPUT

Bruno Murari, Monza, and Marco Siligoni, Vittuone, both of Italy, assignors to SGS-ATES Componenti Elettronici S.p.A., Agrate Brianza, Italy

Filed Nov. 2, 1979, Ser. No. 90,619

Claims priority, application Italy, Nov. 3, 1978, 29388 A/78

Int. Cl.³ H03F 3/04, 3/45


U.S. Cl. 330-301

6 Claims

- A linear differential amplifier for converting an input signal into an unbalanced output signal, comprising:
 - a supply of direct current having a grounded terminal and an ungrounded terminal;
 - a first and a second main transistor for one conductivity type having emitters connected in parallel to said ungrounded terminal by way of a first constant-current generator and

further having collectors respectively connected to said grounded terminal via substantially identical first and second biasing resistors, said main transistors having respective bases between which said input signal is differentially applied;

voltage-control means inserted between said terminals in series with said first biasing resistor for maintaining across the latter a predetermined voltage drop in the absence of said input signal;



an ancillary transistor of opposite conductivity type having an emitter connected to ground through said second biasing resistor, a collector connected to said ungrounded terminal, and a base connected to said voltage-control means; and

a second constant-current generator inserted between said ungrounded terminal and the collector of said ancillary transistor, said output signal being available at the last-mentioned collector.

4,293,825

FREQUENCY-SHIFTING SYSTEMS FOR FREQUENCY MODULATED SIGNALS

Raffaele Cerra, Naples, Italy, assignor to Selenia Industrie Elettroniche Associate S.p.A., Italy


Filed Apr. 13, 1979, Ser. No. 30,267

Claims priority, application Italy, Apr. 18, 1978, 48945 A/78

Int. Cl.³ H03L 7/06

U.S. Cl. 331-2

1 Claim



1. A system of frequency shifting of frequency modulated signals, continuously above or below a pre-established frequency, said shift being possibly also null, characterized in comprising: a source of frequency modulated signals, the frequency of which is to be shifted; a reference oscillator; a first phase locked loop to which is applied the signals from said source and the output of said reference oscillator, the arrangement being such that said first phase locked loop is locked to a first conversion frequency differing by the oscillator output frequency from the frequency of said signal source; a controlled frequency oscillator; a second phase locked loop having the output of said first phase locked loop applied thereto together with the output of said controlled frequency oscillator, the arrangement being such that said second phase locked loop is locked to a second conversion frequency differing from that of said first phase locked loop such that the output frequency of said second phase locked loop is greater than, equal to, or less than the frequency of said signal source according to the value of the frequency of said controlled frequency oscillator.

4,293,826

HYBRID SEMICONDUCTOR LASER/DETECTORS


Donald R. Scifres, Los Altos; Robert D. Burnham, Los Altos Hills, and William Streifer, Palo Alto, all of Calif., assignors to Xerox Corporation, Stamford, Conn.

Filed Apr. 30, 1979, Ser. No. 34,237

Int. Cl.³ H01S 3/19

U.S. Cl. 331-94.5 H

8 Claims



1. A hybrid semiconductor laser/detector on a single semi-conductive substrate, said laser having front and rear light emitting facets and being mounted on a flat surface of said substrate, an optical detector integral to said substrate, said detector being adjacent to one of said light emitting facets to detect a small portion of the light emitted therefrom, a bias circuit connected to supply an operating current to said laser, said detector being connected to said bias circuit to provide a feedback signal proportional to the detected light from said one facet to adjust and maintain said operating current to provide a predetermined optical power output level, said detector characterized by being positioned at an oblique angle relative to and dissecting the path of light emitted from said one facet to form a light receiving and reflecting surface, a portion of the facet light being reflected by said surface and another portion thereof being refracted into said detector to provide said feedback signal.

4,293,827

MULTIWAVELENGTH DYE LASER


Gary L. McAllister, and V. G. Draggoo, both of Richland, Wash., assignors to Jersey Nuclear-Avco Isotopes, Inc., Bellevue, Wash.

Filed Sep. 14, 1979, Ser. No. 75,402

Int. Cl.³ H01S 3/082

U.S. Cl. 331-94.5 ML

14 Claims



1. A laser beam generating system for generating a composite laser beam comprised of at least two separate laser beams and having at least two separate wavelength components, said system comprising:

- at least one multiwavelength laser for emitting a first multi-wavelength laser beam having at least two separated wavelength components;
- at least one additional laser for emitting a second laser beam;
- means for polarizing said first and second laser beams;

means for directing the polarized beams onto polarization combining means; and polarization combining means for receiving said polarized beams and combining them into a substantially colinear composite beam.

4,293,828

ARRANGEMENT FOR SUPPRESSING INTERFERENCE WAVES AND HARMONIC WAVES IN TRAVELING WAVE TUBES WITH A SHORT CIRCUITING SLIDE IN THE OUTPUT WAVE GUIDE

Franz Gross, Loerrach, Fed. Rep. of Germany, assignor to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany


Filed Feb. 4, 1980, Ser. No. 117,979

Claims priority, application Fed. Rep. of Germany, Mar. 2, 1979, 2908218

Int. Cl.³ H01P 1/212, 1/26, 1/28

U.S. Cl. 333—27

10 Claims



1. An arrangement for suppressing interfering waves and harmonic waves in a traveling wave tube, comprising: an output wave guide coupled to the traveling wave tube; said output wave guide including a member therein comprising a frontal surface which is an effective short circuit plane which reflects the fundamental mode; a groove in said frontal surface as a $\lambda/4$ wave guide element; and attenuation means mounted in said wave guide element.

4,293,829

POLARIZATION SEPARATOR

Eberhard Schuegraf, Munich, Fed. Rep. of Germany, assignor to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany


Filed Sep. 20, 1979, Ser. No. 77,190

Claims priority, application Fed. Rep. of Germany, Sep. 29, 1978, 2842576

Int. Cl.³ H01P 1/16, 5/08

U.S. Cl. 333—125

12 Claims



1. A polarization separator for upper and lower of two frequency range devices having waveguide sections of rectangular and round cross-section, with a double branching waveguide, which is symmetrically constructed and has five-arms with a first arm lying in the longitudinal axis of the separator for connecting a continuing waveguide of round cross-section and four partial branching arms of rectangular cross-section and which are mounted 90 degrees with respect to each other and extend generally parallel to the longitudinal axis of the separator and said four partial arms extending in a direction

opposite to the first arm and with a first pair of said partial arms mounted opposite one another and each connected with one of a first pair of separator arm sections which connect said partial arms to a first pair of identically formed series waveguides, a second pair of said partial arms mounted opposite one another and each connected to one of a second pair of separator arm sections, and wherein two separator arm sections which lie opposite each other and the series waveguides are formed as E-offset waveguides and as H-offset waveguides, respectively and the E-offset waveguides are designed as rectangular waveguide sections which are provided on both sides with a waveguide bend and are respectively bent across the broad side of the waveguide in opposite directions on both sides and both E-offset waveguides are aligned with respect to their narrow sides obliquely to the longitudinal axis of the separator and extend parallel to each other and the H-offset waveguides are respectively designed as rectangular waveguide sections which have on both sides a waveguide bend and are respectively bent across the narrow side of the waveguide in opposite directions and one of the E-offset waveguide sections is mounted between the two H-offset waveguides in such manner that the series waveguides connected to the E-offset waveguide and the H-offset waveguides are formed so that their partial arms do not penetrate each other, characterized in that the partial arms (6 through 9) of the series waveguides (SV1, SV2) and the E-offset and H-offset waveguides (10 through 13) have a side ratio of at least approximately 1:4 with respect to their cross-section dimensions; and the partial arms (2 through 5) of the double branching waveguides consist of waveguides which have the same impedance as the E- and H-offset waveguides, and the first arm (18) of the double branching waveguides (DV) is connected to a continuing waveguide (17) which is formed as a coaxial waveguide and the transition from waveguide (18) to the continuing waveguide (17) is designed as an impedance level transformer by means of cross-section variations (18a, 18b) of the inner conductor (18') of the coaxial waveguide.

4,293,830

MICROSTRIP DELAY LINE COMPENSATED FOR THERMAL PHASE VARIATIONS

Luciano Accatino, Turin, Italy, assignor to CSELT, Centro Studi e Laboratori Telecomunicazioni S.p.A., Turin, Italy


Filed Oct. 23, 1979, Ser. No. 87,647

Claims priority, application Italy, Dec. 29, 1978, 69976 A/78

Int. Cl.³ H01P 9/00, 1/30

U.S. Cl. 333—161

5 Claims



1. A method of transmitting microwaves along a signal path with a substantially temperature-independent phase shift within a predetermined temperature range, comprising the steps of cascading a microstrip delay line having a first thermal coefficient of dielectric-constant variation with a microstrip transmission line having a second thermal coefficient of dielectric-constant variation of a sign opposite that of said first thermal coefficient, and making said transmission line of a length substantially compensating for thermal phase variations of said delay line within said predetermined temperature range.

4,293,831

MONOLITHICALLY INTEGRATED CHARGE TRANSFER CIRCUIT

Rainer Lueder, Oberhaching, Fed. Rep. of Germany, assignor to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany


Filed Feb. 25, 1980, Ser. No. 124,128

Claims priority, application Fed. Rep. of Germany, Mar. 30, 1979, 2912745

Int. Cl.³ H03H 17/06; G11C 19/28, 27/02

U.S. Cl. 333—165

4 Claims



1. In a monolithically-integrated charge transfer device with a single scanner, a first clock-controlled metal-insulator-semiconductor charge transfer and which is supplied with charge packets by the signal scanner, and which has a clock-controlled output stage connected to the first charge transfer system, the improvement therein comprising:

at least two additional metal-insulator-semiconductor clock-controlled charge transfer systems each including an input connected in common to the first charge transfer system and an output connected in common with each other so as to be in parallel;

each of said parallel charge transfer systems forming a filter and each constructed to have a respective different delay time;

sampling means connected to said common outputs for sampling the same at a frequency that is higher than that of the scanner; and

a low pass filter connected to said sampling means for smoothing the output of the sampling means.

4,293,832

TRANSVERSAL CHARGE TRANSFER FILTER

Jean L. Berger, Paris, France, assignor to Thomson-CSF, Paris, France


Filed Apr. 1, 1980, Ser. No. 136,375

Claims priority, application France, Apr. 6, 1979, 79 08789

Int. Cl.³ H03H 15/02, 17/02; G11C 19/28

U.S. Cl. 333—165

6 Claims



1. A transversal charge transfer filter comprising a semicon-

ductor substrate covered by an insulating layer on which transfer electrodes alternate with charge-storing electrodes, wherein one storage electrode out of two is cut into two parts and the weighting coefficients are elaborated by reading means connected at a point P to a part of each cut storage electrode, which read negatively the charges leaving a so-called negative cut storage electrode and positively the charges arriving under the next so-called positive cut storage electrode.

4,293,833

MILLIMETER WAVE TRANSMISSION LINE USING THALLIUM BROMO-IODIDE FIBER


Adrian E. Popa, Newbury Park, Calif., assignor to Hughes Aircraft Company, Culver City, Calif.

Filed Nov. 1, 1979, Ser. No. 90,233

Int. Cl.³ H01P 3/16

U.S. Cl. 333—239

14 Claims



1. A transmission line comprising: a fiber of co-crystallized thallium bromo-iodide consisting of from about 40 mole percent to about 46 mole percent thallium bromide and from about 60 mole percent to about 54 mole percent thallium iodide, and means for launching electromagnetic waves of a wavelength ranging from about 10 millimeters to about 0.4 millimeter onto said fiber.

4,293,834

LOAD BREAK SWITCH


K. Henry Date, and Ronald Wainio, both of South Milwaukee, Wis., assignors to McGraw-Edison Company, Rolling Meadows, Ill.

Filed Sep. 6, 1978, Ser. No. 940,104

Int. Cl.³ H01H 3/30

U.S. Cl. 335—76

4 Claims



1. An operating mechanism for operating a disconnect switch having at least one pair of separable contacts movable to open and closed positions, which comprises:

a frame; an operating shaft supported by the frame for rotation between a closed position and an open position, an output shaft being operably connected to effect opening of the disconnect switch when the output shaft is rotated from its closed position to its open position, and to effect closing of the disconnect switch when the output shaft is rotated from its open position to its closed position; releasable latching means, for stopping and holding the output shaft in either its closed or opened positions; solenoid actuated latch releasing means for momentarily releasing the latching means;

manually actuated latch releasing means for momentarily releasing the latching means;
 torsion spring means for rotating the output shaft in one direction between its opened and closed positions;
 motor actuated spring charging means for charging the torsion spring in one direction to a preset value of stored energy after each opening or closing operation;
 manually actuated spring charging means for charging the torsion spring in one direction to said preset value of stored energy; and
 latch locking means, for locking the latching means so that it can not be released by either the solenoid actuated or manually actuated latch releasing means, whenever the operating shaft is in its opened position and the energy stored by the torsion spring means is less than a preset value.

4,293,835

SOLENOID FOR AN ELECTRIC STARTING MOTOR FOR GARDEN TRACTOR OR THE LIKE


Robert K. Davis, Kankakee, Ill., and Michael J. Myers, Goshen, Ind., assignors to Roper Corporation, Kankakee, Ill. and Electromotion, Inc., Elkhart, Ind.

Filed Jan. 28, 1980, Ser. No. 115,875

Int. Cl.³ H01H 50/02

U.S. Cl. 335—131

14 Claims



1. A solenoid for an electric starting motor for a garden tractor or the like comprising, in combination a housing in the form of a generally cylindrical inverted cup of molded plastic having a closed end wall and having an outwardly extending flange at its open end, a pair of diametrically arranged fixed contacts having a substantial cross section penetrating the end wall and being threaded externally thereof to form binding posts for a load circuit, a magnetic assembly including a cylindrical wound bobbin having an armature axially slidable therein with the bobbin being completely surrounded by a hollow magnetic annulus having axial clearance openings at its respective ends, means for holding the annulus axially within the open end of the cup, a movable contact assembly including a conductive disc for completing a circuit between the fixed contacts and having an axial plunger which projects from one side of the disc through the adjacent one of the clearance openings in the annulus and also having a return coil spring extending axially from the opposite side of the disc to the end wall, the end of the plunger being seated against the adjacent end of the armature, the armature when in its normal retracted position extending through the remote one of the clearance openings to a position outside of the annulus so that when control current is applied to the winding on the bobbin the armature is sucked into the annulus overcoming the force of the return spring and shifting the conductive disc into seated engagement with the fixed contacts thereby completing the load circuit, the disc and fixed contacts both having substantial axial thickness to provide high heat capacity and formed of a metal having high conductivity for flow of heat to the binding posts thereby to reduce the rise in temperature within the

housing, the fixed contacts being spaced from the disc axis at a sufficient distance so that only a portion of the presented area of the fixed contacts is engaged by the edge portion of the disc thereby to develop a high contact pressure per unit area, the disc being freely rotatable with respect to the fixed contacts so that contact with the latter occurs in random positions on the disc for constant renewal of the contacting surface thereon.

4,293,836

ELECTRICAL FUSE WITH AN IMPROVED FUSIBLE ELEMENT


Hiroo Arikawa, Tokyo, Japan, assignor to San-O Industrial Co., Ltd., Tokyo, Japan

Filed Jul. 11, 1979, Ser. No. 56,533

Int. Cl.³ H01H 85/04

U.S. Cl. 337—290

2 Claims



1. A fusible element for use in electrical fuses, said fusible element consisting of a support member made from a monofilament yarn of glass quartz fiber and a metallic alloy coating on the exterior surface of said support member, said metallic alloy consisting essentially of silver, copper, tin and antimony.

4,293,837

HALL EFFECT POTENTIOMETER


Wolfgang Jaffe, Roselle Park, and Bruce R. Rogan, Somerville, both of N.J., assignors to The Singer Company, Stamford, Conn.

Filed Jul. 23, 1980, Ser. No. 171,512

Int. Cl.³ H01L 43/04

U.S. Cl. 338—32 H

8 Claims



1. A potentiometer comprising a pair of magnets having their fields in quadrature, and a solid state Hall effect sensor with input and output terminals connected thereto, the magnets and sensor being located in a fixed spatial relationship with the sensor between the magnets and the magnets having their axes mutually perpendicular but parallel and perpendicular respectively with respect to the broad plane of the sensor in positions wherein flux from the magnets at least partially cancels in the sensor, said potentiometer further including a ferromagnetic member movable in a defined manner relative to the sensor and flux from the magnet, the ferromagnetic member having a predetermined asymmetrical shape resulting in a linearly varying voltage across said output leads throughout a range of movement of the ferromagnetic member while a constant voltage is applied to the input terminals.

4,293,838

RESISTANCE MATERIAL, RESISTOR AND METHOD OF MAKING THE SAME



Richard L. Wahlers, Churchville, Pa., and Vernon E. Osborne, Boone, N.C., assignors to TRW, Inc., Cleveland, Ohio

Filed Jan. 29, 1979, Ser. No. 7,433

Int. Cl.³ H01C 1/012

U.S. Cl. 338—308

23 Claims



1. An electrical resistor of relatively high resistivity and rugged physical characteristics comprising an insulating substrate and a layer of resistor material on a surface of the substrate, the resistor material including a conductive phase of particles of tin oxide embedded in and dispersed throughout a glass which includes an insulating material containing an oxide of zirconium, the glass and insulating material being present in an amount up to about 70% by volume of the resistor material.

4,293,839

THICK FILM RESISTOR

Eiichi Asada, Tokyo; Toshio Inokuma, Fujisawa, and Isao Egawa, Tachikawa, all of Japan, assignors to Shoei Chemical Incorporated, Tokyo, Japan


Filed Mar. 12, 1980, Ser. No. 129,784

Claims priority, application Japan, Mar. 13, 1979, 54-29081

Int. Cl.³ H01C 1/012

U.S. Cl. 338—309

6 Claims



1. A thick film resistor, comprising: an electrically insulating substrate; a resistive film element on said substrate, said resistive film element consisting essentially of (A) 100 parts by weight of RuO₂ and glass, and (B) 0.1 to 15 parts by weight of Au, wherein the ratio of RuO₂ to glass is effective to provide the desired resistance of said thick film resistor; and electrodes on said substrate and overlapped with the terminal portions of said resistive film element, said electrodes containing not less than 50 weight percent of Ag.

4,293,840

EXCESSIVE DESCENT-RATE WARNING SYSTEM PARTICULARLY USEFUL FOR HELICOPTERS

Gideon Hadari, Ramat Hasharon, Israel, assignor to Israel Aircraft Industries Ltd. and Ben Gurion Industries Ltd., both of, Israel


Filed Sep. 11, 1979, Ser. No. 74,524

Claims priority, application Israel, May 25, 1978, 57402; Sep. 20, 1978, 55605

Int. Cl.³ G08B 21/00; G01C 5/00

U.S. Cl. 340—27 AT

11 Claims



1. An excessive descent-rate warning system particularly useful for helicopter aircraft, characterized in that it includes means for measuring the aircraft altitude and for producing an altitude signal corresponding thereto; means for differentiating the altitude signal and for producing a descent-rate signal corresponding to the rate of change of the altitude signal; comparator means for comparing the altitude and descent-rate signals and for producing a warning signal whenever the descent-rate exceeds the maximum one for the respective altitude according to a predetermined relationship, which relationship includes an offset value defining the maximum descent-rate at "0" altitude; means for measuring the forward speed of the aircraft and for producing a forward-speed signal corresponding thereto; and forward-speed controlled means for causing an increase in said forward-speed signal to reduce said offset and thereby to decrease the maximum descent-rate at "0" altitude which produces said warning signal; said forward-speed controlled means including a sensitivity selector presettable by the pilot to permit him to preset the rate at which said latter means will reduce said offset.

4,293,841

PEDESTRIAN TRAFFIC CONTROL SYSTEM

Thomas R. Potter, Los Alamitos, Calif., assignor to Detector Systems, Inc., Cypress, Calif.

Filed Aug. 3, 1978, Ser. No. 930,576

Int. Cl.³ G08G 1/09; G09F 11/28, 11/16; G08B 21/00

U.S. Cl. 340—44

18 Claims

1. A pedestrian traffic signal for displaying a traffic sign in a display position comprising:

an endless sign with indicia thereon;
 support means to support the endless sign to place at least one of the indicia in the display position;
 motion means connected to the endless sign and to a power supply to move the endless sign past the display position;
 position detection means to detect the position of the indicia with respect to the display position; and
 control means responsive to the position detection means to control the motion means to place a desired indicia on the

strings interlaced with said first resistor strings, said first ladder coupled to said second ladder; comparator means coupled to receive said capacitively divided signal from said input means and said reference signals for comparing said signals; logic means for controlling said digital-to-analog converter so as to select one of said reference signals most comparable to said analog signal, said logic means coupled to said digital-to-analog converter and to said comparator means; whereby said second ladder provides a consistent reduction of a potential applied to said digital-to-analog converter and permits switching of said reference signals without bootstrapping.

4,293,849


KEYBOARD ENCODER USING PRIORITY ENCODERS
Robert H. Lacy, Bartlesville, Okla., assignor to Phillips Petroleum Company, Bartlesville, Okla.

Filed May 23, 1979, Ser. No. 41,590

Int. Cl.³ G06F 3/02

U.S. Cl. 340—365 S

8 Claims



1. A keyboard encoder comprising:
a plurality of switching means, each of said plurality of switching means having at least two outputs;
a first priority encoder having a plurality of data inputs and a plurality of data outputs;
a second priority encoder having a plurality of data inputs and a plurality of data outputs;
a voltage supply;
means for electrically connecting the data inputs of said first priority encoder to said voltage supply;
means for electrically connecting the data inputs of said second priority encoder to said voltage supply;
means for connecting a first one of the outputs from each of said plurality of switching means to a respective one of the data inputs of said first priority encoder;
means for electrically connecting a second one of the outputs from each of said plurality of switching means to a respective one of the data inputs of said second priority encoder;
means for combining the data outputs of said first priority encoder with the data outputs of said second priority encoder to form a combined binary output, the closure of one of said plurality of switching means enabling said first priority encoder to provide a binary output representative of the particular data input of said first priority encoder which is electrically connected to said one of said plurality of switching means which is closed and enabling said second priority encoder to provide a binary output which is representative of the particular data input of said second priority encoder which is electrically connected to said one of said plurality of switching means which is closed.

4,293,850 TEMPERATURE COMPENSATED ROTARY POSITIONER


Lothar H. Bullinga, Marion, Iowa, assignor to Rockwell International Corporation, El Segundo, Calif.

Filed Feb. 25, 1980, Ser. No. 124,195

Int. Cl.³ G08B 5/00

U.S. Cl. 340—378.5

5 Claims



1. In a rotary positioning system of the type comprising (i) prime movement means comprising a rotor, stator, and a plurality of windings disposed at different angular positions around one of said stator and rotor, and (ii) selecting means for selectively connecting at least one winding to an energizing source thereby causing the rotor to rotate to a predetermined position, an improved energizing source comprising means for supplying a temperature-variable voltage or current which automatically varies in a predetermined manner with temperature so as to lessen inherent temperature-caused variation in damping of the prime movement means rotor.

4,293,851

SOUND ACTUATOR


Earl Beyl, Jr., 4803 S. 5th St., Louisville, Ky. 40202

Filed Oct. 29, 1979, Ser. No. 88,779

Int. Cl.³ G08B 3/00

U.S. Cl. 340—384 E


11 Claims



1. A horn and actuator circuit to provide selective actuation and deactuation of horn means including:
(a) horn means located on a vehicle adapted to travel on cooperative track means;

(b) power supply means to supply direct current electric power to said horn means;
(c) switch means carried by said vehicle to control supply of power from said power supply means to said horn means;
(d) magnetic field sensitive switch actuator means carried by said vehicle to actuate said switch means between first conductive state and second nonconductive state and including magnetic field sensing, means where said actuator means is sensitive to magnetic fields of first and second polarity to position said switch in said first state in response to magnetic field of said first polarity and to position said switch in said second position in response to magnetic field of said second polarity; and
(e) at least two spaced magnetic field sources of different polarity positioned adjacent said tract means to relatively provide magnetic fields of said first and second polarity to said switch actuator means.

detecting the difference between the water pressure in a feedwater pipe and the steam pressure in a steam pipe of the steam generator; a bias signal generator which responds to a flow rate signal transmitted from a flow meter installed in the feedwater pipe and generates a signal corresponding to a limit value on the differential pressure between the waterside inlet and outlet,



4,293,852

CAPACITIVE ARTICLE REMOVAL ALARM

Groby W. Rogers, London, England, assignor to Lawrence Security Services Ltd., London, England


Filed Dec. 5, 1979, Ser. No. 100,372

Claims priority, application United Kingdom, Dec. 8, 1978, 47724/78

Int. Cl.³ G08B 13/14

U.S. Cl. 340—568

5 Claims



1. An alarm system for indicating the removal of an article from a predetermined position comprising:
(a) sensing circuit means including
(i) two electrical conductors spaced from but adjacent each other and for positioning adjacent to the predetermined position to be occupied by at least one article when in use, and
(ii) signal generating means responsive to the capacitance present between these conductors to provide a first output condition indicative of substantially constant capacitance present between these conductors due to the undisturbed presence of said at least one article and to provide a second output condition indicative of a change in capacitance value present due to the disturbance of said at least one article, and
(b) alarm actuator means responsive to the output of said sensing circuit means to provide an alarm indication responsive to said second output condition of said sensing circuit means.

4,293,853

METHOD AND APPARATUS FOR DETECTING FLOW INSTABILITY IN STEAM GENERATOR

Jun Kubota, Tokyo, Japan, assignor to Doryokuro Kakunenryo Kaihatsu Jigyodan, Tokyo, Japan

Filed Feb. 27, 1980, Ser. No. 125,176

Claims priority, application Japan, Mar. 8, 1979, 54/26983

Int. Cl.³ G08B 21/00

U.S. Cl. 340—611

5 Claims

2. An apparatus for detecting the flow instability in steam generators comprising: a differential pressure detector for

said limit value defining the onset of the flow instability at a measured feedwater flow rate; a comparator for comparing the output from the differential pressure detector with that from the bias signal generator and outputting a comparison result; and an alarm means which responds to the comparison result obtained by the comparator.

4,293,854

MONITOR MEANS AND METHOD FOR GRAIN BIN


William L. Gookins, R.R. 1, Box 49, Attica, Ind. 47918, and Junior K. King, R.R. 1, Box 106A, Russiaville, Ind. 46799

Filed Jul. 30, 1979, Ser. No. 61,770

Int. Cl.³ G08B 21/00; G01N 11/14

U.S. Cl. 340—615

17 Claims



1. A method of monitoring condition of stored contents of a storage vessel comprising the steps of:
locating a contents condition sensor in said stored contents; power driving and thereby transferring said sensor primarily horizontally through said contents and at a substantially uniform depth below the surface of said contents; using the surface of the contents for at least partially supporting the sensor so that the sensor elevation is coordinated with the content surface elevation to follow surface contour and maintain said depth as said sensor is driven; and producing a signal in response to change of condition of said contents sensed by said sensor.

4,293,855

COMMUNICATION DEVICE


Arthur T. Perkins, 3120 107th Ave. SE., Bellevue, Wash. 98004

Filed Dec. 31, 1979, Ser. No. 108,412

Int. Cl.³ G06F 3/14

U.S. Cl. 340—712

19 Claims



1. A communication device comprising:
 - (a) keyboard means having a plurality of keys operable to establish the communication device operational mode and entry code to thereby create the alphanumeric characters forming the message to be communicated, or to select one of a plurality of predetermined messages to be communicated;
 - (b) user operable feedback switch means including a display sequentially presenting to the user a representation of each key on said keyboard means, said feedback switch means being operable during the time a key is represented to replicate actuation of the corresponding key on said keyboard means;
 - (c) display means presenting either the message to be communicated as it is being created by the user or the selected predetermined message; and,
 - (d) housing means having a first face for mounting said keyboard means and said user operable feedback switch means including said sequential display means, and a second face at an acute angle with respect to said first face for mounting said display means.

4,293,856

DIGITAL CFAR SIGNAL PROCESSOR FOR PHASE CODED RADARS


Andrew G. Chressanthis, Philadelphia, Pa.; Henry M. Halpern, Cherry Hill, and Brian P. Gaffney, Medford Lakes, both of N.J., assignors to RCA Corporation, New York, N.Y.

Filed Oct. 26, 1979, Ser. No. 88,565

Int. Cl.³ G01S 13/00, 13/52

U.S. Cl. 343—5 CF

6 Claims



1. In the combination of a moving target indicator (MTI) radar and a digital constant false alarm rate (CFAR) signal processor for use with an automatic control system, wherein said radar derives separate in-phase and quadrature-phase detected signals in response to received echoes of transmitted exploratory pulses each of which pulses is phase-coded at a given frequency in accordance with a serial code of no more than n bits, wherein n is a first predetermined plural integer, said serial code having a duration which is short relative to that of a given range interval, the improvement wherein said digital CFAR signal processor comprises:

first means having said in-phase detected signal applied as an

input thereto and second means having said quadrature-phase detected signal applied as an input thereto, each of said first and second means including an analog-to-digital converter and an MTI canceller for sampling its applied detected signal at a rate at least twice that of said given frequency over substantially said given range interval of each of a plurality of successive exploratory pulses to derive an MTI residue output signal in the form of a series of m -bit digital numbers each corresponding to the algebraic value of the respective samples of the instantaneous amplitude of the residue over said given range interval, wherein m is a second predetermined plural integer and one of said m bits represents the sign of the polarity of the instantaneous amplitude of said residue,

digital function-generator means responsive to the absolute digital value of the m -bits of the first-means residue output signal corresponding to each successive sample and to the absolute digital value of the m -bits of the second-means residue output signal corresponding to that sample for deriving a first p -bit digital signal corresponding to the absolute value of the cosine of the arctangent of the phase angle defined by the residue output signals of said first and second means for that sample and for deriving a second p -bit digital signal corresponding to the absolute value of the sine of the arctangent of the phase angle defined by the residue output signals of said first and second means for that sample,

third means for digitally adding the sign bit of the m -bits of the first-means residue output signal of each successive sample to the first p -bit digital signal for that sample to derive a first $(p+1)$ bit digital signal for that sample and for adding the sign bit of the m -bits of the second-means residue output signal of each successive sample to the second p -bit digital signal for that sample to derive a second $(p+1)$ bit digital signal for that sample,

correlation means including a first n -bit correlator for digitally correlating successive running sequences of n successive ones of said first $(p+1)$ bit digital signals with said n -bit serial code and a second n -bit correlator for digitally correlating successive running sequences of n successive ones of said second $(p+1)$ bit digital signals with said n -bit serial code,

fourth means for digitally summing the squares of each successive digital correlation by said first and second correlators to produce a digital valued output signal therefrom for each of said successive correlations, and threshold comparator means having the output of said fourth means and a variable-threshold digital-valued signal applied as respective inputs thereto for deriving a digital CFAR output therefrom only when the digital value of the output signal from said fourth means exceeds the digital value of said threshold signal.

4,293,857

COLLISION AVOIDANCE WARNING SYSTEM

Edwin L. Baldwin, Oakwood Garden Apts. So., Apt. Z-204 & 60 Saratoga Ave., San Jose, Calif. 95129

Filed Aug. 10, 1979, Ser. No. 65,749

Int. Cl.³ G01S 13/74


U.S. Cl. 343—6.5 R

13 Claims

1. A method of detecting a potential collision between a primary aircraft and a secondary aircraft flying in an area containing a known-location standard very-high-frequency omni-directional range-distance measuring ground station (or equivalent) and a known-location air surveillance radar of the rotating antenna type provided with an interrogator, the steps of:

- (1) determining on the primary aircraft the bearing angle and distance from said omnidirectional range-distance measuring ground station, whereby to establish the position of the primary aircraft,
- (2) calculating the radar range distance c between the radar

- and the primary aircraft, based on the known positions of the primary aircraft, the radar and the ground station,
- (3) receiving an interrogation pulse at the primary aircraft from the radar,
- (4) receiving at the primary aircraft the resultant transponder response signal from the secondary aircraft,
- (5) measuring the time difference between receipt of said interrogator pulse and said transponder response signal at the primary aircraft,
- (6) calculating the angle B between the bearing vector from the radar to the primary aircraft and the bearing vector from the radar to the secondary aircraft in accordance with said time difference as related to the known rotational period of the radar antenna,
- (7) receiving at the primary aircraft the side lobe energy of each primary radar pulse from the radar,
- (8) calculating the value x , which is the sum of the radar



- range distance between the radar and the secondary aircraft and the distance between the two aircraft, in accordance with the time difference at the primary aircraft between receipt at the primary aircraft of the side lobe energy of the primary radar pulse synchronous with the interrogation to which the secondary aircraft responds and receipt at the primary aircraft of the transponder response signal from the secondary aircraft,
- (9) calculating the distance from the secondary aircraft to the primary aircraft based on the known or previously calculated values of x , c and angle B , and
- (10) calculating the bearing angle from the secondary aircraft to the primary aircraft based on the known angle B , the known bearing angle from the radar to the primary aircraft and the previously calculated distances between the primary aircraft, the secondary aircraft and the radar, whereby to establish the positional data of the secondary aircraft with respect to the primary aircraft.

4,293,858

POLARIZATION AGILE MEANDER LINE ARRAY


George A. Hockham, Valencia, Calif., assignor to International Telephone and Telegraph Corporation, New York, N.Y.

Filed Nov. 23, 1979, Ser. No. 97,000

Int. Cl.³ H01Q 11/04, 15/24

U.S. Cl. 343—731

10 Claims



1. A polarization agile system with a meander line antenna array, comprising:
 - at least one periodic linear array having a first longitudinally

extending meander line and a second relatively close-spaced longitudinally extending meander line, said lines being mirror images of each other and both lying in a first plane;

means within each of said meander lines comprising a plurality of longitudinally spaced radiating strips disposed in said first plane and each at the same angle with respect to the longitudinal center line of said linear array, and connecting conductors between adjacent ones of said radiating portions to provide a continuous series conductive path throughout each of said meander lines;

a conductive ground plane substantially parallel to said first plane and spaced therefrom by a first spacing;

and radio frequency feed means for end feeding said meander lines in a predetermined phase relationship to provide a corresponding plane of polarization for said array.

4,293,859

TRAFFIC RADAR UNIT


Edward W. Sergeant, Chanute, Kans., assignor to M. P. H. Industries, Inc., Chanute, Kans.

Filed Sep. 14, 1979, Ser. No. 75,425

Int. Cl.³ H01Q 1/32

U.S. Cl. 343—702

12 Claims



1. A one-piece traffic radar unit comprising:
 - a housing having a top and containing Doppler radar apparatus capable of generating a microwave radar signal and processing return signals to provide an output that indicates the speed of a target vehicle;
 - a boom secured to said housing adjacent said top and extending therefrom for mounting the housing in a patrol vehicle to install the radar unit therein said boom being adapted to overlie the dashboard of the patrol vehicle with the housing depending from the boom in front of the dashboard;
 - means for securing said boom to said patrol vehicle on said dashboard thereof;
 - a directional antenna device connected with said apparatus for transmitting said radar signal and receiving said return signals, and mounted in said housing in a disposition to beam the transmitted signal along an upwardly extending path through said top of the housing; and
 - a reflector mounted on said top in said path for redirecting said transmitted signal along a generally horizontal path, whereby to beam the transmitted signal and receive the return signals through the windshield or a window of a patrol vehicle in which the unit is installed.

4,293,860

ANTENNA ALARM ASSEMBLY FOR VEHICLE

Keisuke Iwata, Tokyo, Japan, assignor to Iwata Electric Co., Ltd., Tokyo, Japan

Filed Aug. 14, 1980, Ser. No. 177,842

Claims priority, application Japan, Jan. 16, 1980, 55-3409[U]


Int. Cl.³ H01Q 1/32

U.S. Cl. 343—715

4 Claims

1. An antenna assembly for vehicle radio transceiver, comprising
 - an antenna;

a casing supporting the lower end of the antenna and including an internal space which is enclosed by a top plate, a side plate and a bottomplate;
 a magnet mounted on the casing for securing the casing to a body of the vehicle by magnetic attraction;
 a vibration detector for detecting any vibration caused to the casing, the detector including a d.c. power supply circuit, a printed circuit board mounted on the bottomplate of the casing, and a conductive spherical body placed on the printed circuit board, the printed circuit board being provided with a first and a second electrode each having



a plurality of mutually interdigitated fingers, one of the electrodes being connected to one terminal of the d.c. power supply circuit and the other electrode being connected to the other terminal thereof, the spherical body having a diameter which is sufficient to provide an electrical interconnection between two adjacent fingers of the both electrodes whenever it is located therebetween; and an alarm circuit for producing an audible alarm in response to a change in the voltage which is developed in the d.c. power supply circuit as a result of a movement of the spherical body over the printed circuit board in response to the vibration applied to the casing.

4,293,861

COMPACT TELEVISION ANTENNA SYSTEM


John R. Winegard, Evergreen; Carey W. Shelledy, Lakewood, and Keith B. Cowan, Arvada, all of Colo., assignors to Winegard Company, Burlington, Iowa

Filed Jan. 8, 1980, Ser. No. 110,493

Int. Cl.³ H01Q 3/00, 21/00

U.S. Cl. 343-766

30 Claims



29. A low and high band VHF antenna comprising:
 a longitudinal support,
 a first element means mounted on said support,
 a second element means mounted on said support, said first and second element means cooperating to receive low band VHF signals, said first and second element means each comprising:
 (a) opposing element half sections having their inboard ends mounted to said support, and
 (b) A lengthening coil connected to each inboard end and in substantial alignment with said connected half section, and a third element means mounted on said support, said second and third element means cooperating to receive high band

VHF signals, the physical spacings between said first and said second element and between said second and said third elements on said support being less than one-tenth the wavelength of the highest frequency in the high VHF band said half sections of said first element means being connected to said support and oriented to lay in a plane substantially perpendicular to the longitudinal axis of said support, said half sections of said second element means being connected to said support and oriented to form an open V-shaped configuration having an apex angle of substantially 135 degrees, the open end of the aforesaid V-shaped configuration being directed toward the front of said support, and said half sections of said third element being connected to said support and oriented to form an open V-shaped configuration having an apex angle of substantially 60 degrees, the open end of the aforesaid V-shaped configuration being directed toward the front of said support.

4,293,862

CANOPY ASSEMBLY FOR PATCHED RADAR DOMES


Allan E. Beavers, Littleton, Colo., assignor to T. A. Pelsue Company, Englewood, Colo.

Filed Jun. 6, 1980, Ser. No. 157,019

Int. Cl.³ H01Q 1/42; B32B 35/00

U.S. Cl. 343-872

7 Claims



1. The canopy assembly for use with a force-fed supply of hot moist air as to cure repair patches on airborne radar domes temporarily housed therebeneath which comprises: a flexible donut-shaped air distribution sheath sized to enclose the repair patch to be cured while conforming in essentially air-tight sealed relation to the contours of the dome surrounding the latter, said sheath having an inlet on its outer surface connectable to the air supply and a plurality of air discharge openings being positioned and adapted to take the hot moist air circulating within the sheath and direct same across the patch so as to define an environment conducive to the curing thereof; anchoring means for temporarily anchoring the air distribution sheath in encircling relation to the patch, said means comprising a plurality of suction cup and strap subassemblies spaced around the sheath, the suction cup of each subassembly being detachably connectable to the surface of the dome while the strap defines a detachable connection between said cup and an adjacent portion of the sheath fastening the latter to said dome; and a shroud defining a loose-fitting protective cover over the sheath capable of permitting the air issuing from the latter to escape therefrom.

4,293,863

INK JET PRINTER WITH LATERALLY MOVABLE PRINT HEAD


James W. Davis, Richardson, and Suresh C. Paranjpe, Dallas, both of Tex., assignors to The Mead Corporation, Dayton, Ohio

Filed Sep. 12, 1979, Ser. No. 75,056

Int. Cl.³ G01D 15/18

U.S. Cl. 346-75

14 Claims



1. An ink jet printer for depositing ink drops from a plurality of jet drop streams along a plurality of parallel adjacent print lines on a sheet of paper, comprising:

a sheet supporting drum,
 means for rotating said drum,
 print head means, slidably mounted adjacent said drum for linear movement in a direction parallel to the axis of rotation of said drum, said print head means generating a plurality of jet drop streams directed toward said drum, with adjacent streams being spaced apart in a direction parallel to the axis of rotation of said drum by a distance greater than the distance between adjacent print lines on said sheet of paper,
 rotatable cam means defining a continuous camming surface, cam drive means, interconnecting said rotatable cam means and said means for rotating said drum, for rotating said rotatable cam means, and
 cam follower means for following said continuous camming surface and moving said print head means in a direction parallel to the axis of rotation of said paper supporting drum, said cam follower means comprising motion reducing means for moving said print head means in a direction parallel to the axis of rotation of said paper supporting drum by a distance substantially less than the distance which said cam follower means is moved by said rotatable cam means, such that said jet streams are directed to deposit drops along respective ones of said print lines during successive rotations of said drum.

4,293,864

LASER SCANNER TRANSPORT

Richard D. Scott, Cherry Hill, N.J., assignor to The United States of America as represented by the Secretary of the Army, Washington, D.C.

Filed Jan. 24, 1980, Ser. No. 114,916


Int. Cl.³ G01D 15/14

U.S. Cl. 346-76 L

12 Claims

1. A high speed printer comprising, a transparent cylinder adapted to have wound on the periphery thereof a carrier containing an ink or dye with printing paper wound on top of said carrier, means to direct a modulated laser beam containing intelligence to be printed along the axis of said transparent cylinder from one side thereof, a laser scanner transport mechanism adjacent to and on the other side of said transparent cylinder, said laser scanner transport comprising, a hollow stationary frame with the center of its cross-section disposed

along the axis of said transparent cylinder, a moveable housing adapted to reciprocate back and forth within said stationary frame, a rotating 45 degree mirror mounted at the end of said moveable housing nearest to said transparent cylinder, and on the axis thereof, means to rotate said 45 degree mirror around its axis, a translation motor mounted within said moveable housing, said translation motor driving a mechanical system



for providing traction between said moveable housing and said stationary frame, whereby said moveable housing will reciprocate so that said 45 degree mirror will periodically traverse the inside of said transparent cylinder from one end thereof to the other, along the axis thereof, to provide helical scanning patterns on said transparent cylinder and the paper and carrier mounted thereon.

4,293,865

INK-JET RECORDING APPARATUS

Koichiro Jinnai, Kawasaki; Masanori Horike, Tokyo; Kyuhachiro Iwasaki, Kanagawa, and Yutaka Kodama, Fujisawa, all of Japan, assignors to Ricoh Co., Ltd., Tokyo, Japan


Filed Sep. 25, 1979, Ser. No. 78,903

Claims priority, application Japan, Apr. 10, 1978, 53-121430

Int. Cl.³ G01D 15/18

U.S. Cl. 346-140 R

7 Claims



1. A multiple nozzle ink jet printing apparatus, comprising: a plurality of ink jet nozzles;
 a corresponding plurality of electromechanical transducers, each transducer being coupled to a corresponding nozzle to selectively apply sufficient pressure to ink therein to cause the ink to form a convex meniscus extending out of the corresponding nozzle, said ink being contained within said nozzle in the absence of a print signal applied to the corresponding transducer; and
 supplemental ink ejection means for applying sufficient force to said meniscus to cause said meniscus to form an ink drop, and to propel said ink drop toward a recording surface, said supplemental ink ejection means affecting only the ink associated with a nozzle or nozzles having a convex meniscus extending therefrom.

4,293,866

RECORDING APPARATUS


Seiki Takita, and Kiyomi Ichizuka, both of Tokyo, Japan, assignors to Ricoh Co., Ltd., Tokyo, Japan

Filed Dec. 3, 1979, Ser. No. 99,835

Claims priority, application Japan, Dec. 13, 1978, 53-154790
Int. Cl.³ G01D 15/18

U.S. Cl. 346—140 R

5 Claims



1. Liquid jet recording apparatus, comprising: an intermediate recording member comprising a supporting substrate, and a color developing layer of a liquid soluble pigment composition on said substrate, said pigment composition comprising a comminuted pigment dispersed in a binder comprising at least one liquid-soluble resin and at least one surface-active agent, said pigment being insoluble in said liquid; liquid jet generating means, including a piezoelectric element responsive to a print control signal for issuing a stream of liquid drops in accordance with a pattern to be printed, and means for directing said drops to impinge upon corresponding selected parts of said layer, so that said drops dissolve said binder at said selected parts, thereby rendering the associated pigment separable from said layer; and means for transferring said separable pigment from said layer of said intermediate recording member to a recording sheet in accordance with said pattern, and for fixing the transferred pigment to said sheet.

4,293,867

DEVICE FOR REMOVING AIR BUBBLES FORMED AND TRAPPED IN INK CHAMBER OF PRINT HEAD OF INK-JET PRINTER


Takuro Isayama, Tokyo, Japan, assignor to Ricoh Co., Ltd., Tokyo, Japan

Filed May 6, 1980, Ser. No. 147,277

Claims priority, application Japan, May 14, 1979, 54-58025
Int. Cl.³ G01D 15/18

U.S. Cl. 346—140 R

1 Claim



1. A device for removing air bubbles formed and trapped in an ink chamber of a print head of an ink-jet printer comprising: (a) a means for detecting the existence of air bubbles in said ink chamber, (b) a means responsive to the output signal from said detection means for replacing the ink in the ink chamber with a liquid with a small surface tension and a low viscosity, and (c) a means for replacing said liquid in said ink chamber with the ink.

4,293,868

SEMICONDUCTOR DEVICE, METHOD OF MANUFACTURING THE SAME AND APPLICATION THEREOF



Takashi Iizuka, Takasaki, and Masayuki Horie, Maebashi, both of Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Filed Feb. 6, 1979, Ser. No. 9,968

Claims priority, application Japan, Oct. 30, 1978, 53-132677
Int. Cl.³ H01L 27/02

U.S. Cl. 357—46

12 Claims



1. A monolithic semiconductor device having a transistor and a Zener diode comprising: a semiconductor substrate of a first conductivity type, having a low impurity concentration, serving as the collector of said transistor, and having a plane major surface; a first semiconductor region of a second conductivity type opposite to said first conductivity type, disposed in a first prescribed area of said major surface except a second prescribed area of said major surface adjacent to said first prescribed area, said first semiconductor region extending to a first predetermined depth into said semiconductor substrate from said major surface, and serving as the base of said transistor; a second semiconductor region of said first conductivity type, formed in said first semiconductor region, extending to a second predetermined depth into said first semiconductor region from said major surface, and serving as the emitter of said transistor; a third semiconductor region of said second conductivity type, formed in said first semiconductor region except said second semiconductor region formed therein, having an impurity concentration higher than that of said first semiconductor region, said third semiconductor region extending to a third predetermined depth into said first semiconductor region from said major surface, and serving as the base contact region of said transistor; a fourth semiconductor region of said second conductivity type, disposed in said second prescribed area of the major surface, extending to a fourth predetermined depth into said semiconductor substrate from said major surface, said fourth semiconductor region having an impurity concentration higher than that of said first semiconductor region, and serving as the contact region for one electrode of said Zener diode; a fifth semiconductor region of said first conductivity type,

- formed in a portion of said semiconductor substrate immediately beneath said fourth semiconductor region adjacent to said fourth semiconductor region, said fifth semiconductor region defining a PN junction with said fourth semiconductor region, and having an impurity concentration higher than that of said semiconductor substrate, said PN junction defining the Zener-voltage of said Zener diode;
- a first metal electrode disposed on said second semiconductor region and serving as the emitter electrode of said transistor;
- a second metal electrode disposed on said third semiconductor region and serving as the base electrode of said transistor; and
- a third metal electrode disposed on said fourth semiconductor region and serving as the electrode of said Zener diode.

4,293,869

CIRCUIT FOR REDUCING DROP-OUT ERRORS IN A VIDEO SIGNAL DERIVED FROM A RECORDING DEVICE

Werner Scholz, Gehrden, Fed. Rep. of Germany, assignor to TED Bildplatten Aktiengesellschaft, Switzerland


Filed May 23, 1979, Ser. No. 41,623

Claims priority, application Fed. Rep. of Germany, May 26, 1978, 2822873

Int. Cl.³ H04N 5/76, 5/795

U.S. Cl. 358—8

13 Claims



1. A circuit for reducing drop-out errors in a video signal from a video recording apparatus comprising: first switch means connected to the video recording apparatus for receiving the video signal and for receiving a marker pulse, said first switch means having at least one control input; transit time means connected to said first switch means for receiving and passing at least one of the video signal and the marker pulse with a controllable transit time; drop-out recognition means connected between the video recording apparatus and said first switch means control input for producing a flag signal with the occurrence of drop-out in the video signal, the flag signal operating on said first switch means control input to pass the marker pulse to said transit time means; detection means connected to said transit time means for detecting the marker pulse and producing a switching pulse; second switch means connected to said transit time means and having a control input connected to said detection means for receiving the switching pulse; and signal forming means connected to said second switch means for producing an equivalent signal, said second switch means passing the equivalent signal to an output thereof when the switching pulse is applied to said second switch means control input.
13. A method of compensating for drop-out in a video signal from a video signal recording apparatus, comprising: supplying the video signal to a transit time circuit having a

4,293,870

CIRCUIT ARRANGEMENT FOR MULTIPLEXING AN INPUT FUNCTION AND AN OUTPUT FUNCTION AT A SINGLE TERMINAL


Steven A. Steckler, Clark, and Alvin R. Balaban, Lebanon, both of N.J., assignors to RCA Corporation, New York, N.Y.

Filed Jan. 31, 1980, Ser. No. 117,237

Int. Cl.³ H04N 9/62

U.S. Cl. 358—10

10 Claims



4. In a television receiver, a circuit arrangement for multiplexing recurrent signals and a service mode indication signal through a common circuit terminal comprising: a source of service mode indication signals, coupled to said terminal, for selectively applying a signal indicative of the service mode to said terminal which has a signal level included within a first range of signals; a source of recurrent signals; means, including a first transistor having an input electrode responsive to said recurrent signals and an output electrode coupled to said terminal for producing, in the absence of said service mode indication signal, replicas of said recurrent signals at said terminal which occupy a second range of signal levels which is exclusive of said first range; a second transistor having an input electrode coupled to said terminal and an output electrode; and means coupled to said second transistor, for biasing said second transistor to be responsive to input signals occupying said first range of signal levels, and to be nonresponsive to input signals occupying said second range of signal levels.

4,293,871

SOLID STATE COLOR TELEVISION CAMERA WITH
MULTIPLE LINE READOUT


Albert Macovski, 2505 Alpine Rd., Menlo Park, Calif. 94025

Filed Dec. 3, 1979, Ser. No. 99,939

Int. Cl.³ H04N 9/07

U.S. Cl. 358-44

10 Claims



1. Apparatus for providing standard color television signals from a scene comprising:

an array of photosensitive elements arranged in horizontal lines;

color filters covering the horizontal lines of photosensitive elements arranged in a vertical sequence consisting of three primary colors where one color is repeated every alternate horizontal line and the other two are each repeated every fourth horizontal line;

means for imaging the scene, through the color filters, onto the array of photosensitive elements to provide stored information at each element;

means for simultaneously reading out the stored information from three adjacent lines consisting of three different colors to provide scanned signals; and

means for combining the scanned signals to provide the standard color television signals.

4,293,872

PRODUCTION OF PRINTING BLOCKS OR FORMS

Hans Keller, Kiel, and Hans-Georg Knop, Heikendorf, both of Fed. Rep. of Germany, assignors to Dr.-Ing. Rudolf Hell GmbH, Kiel, Fed. Rep. of Germany


Filed Jul. 20, 1979, Ser. No. 59,214

Claims priority, application Fed. Rep. of Germany, Jul. 24, 1978, 2832467

Int. Cl.³ H04N 1/38

U.S. Cl. 358-75

13 Claims



1. A method for producing printing blocks or formes, in which at least two image signals are mixed electronically to generate a composite signal having a gradual or smooth transition within a mixing range, the method comprising the steps of:

(a) scanning at least one image opto-electronically point-by-

point by means of a first scanning device to generate at least two image signals to be mixed;

(b) generating a coloured control mask including at least one mask area, said mask and said mask area having different colour information;

(c) scanning said control mask opto-electronically point-by-point by means of a second scanning device to obtain primary mask colour signals;

(d) generating an unsharp control signal from at least one mask colour signal by evaluating the colour signals of the actual point and the surrounding points scanned from said control mask, said unsharp control signal having a first level during scanning said control mask, a second level during scanning said at least one mask area and a gradual transition between the levels during scanning the contours of said mask area, said gradual transition defining the gradual transition of said composite signal within the mixing range;

(e) modulating one of said image signals by said control signals;

(f) modulating said other image signal by the amplitude-inverted control signal;

(g) combining the modulated image signal so as to obtain said composite signal, and

(h) producing printing blocks or formes from said composite signal.

4,293,873

METHOD AND A DEVICE FOR PRODUCING
SEPARATION IMAGES HAVING THE EFFECT OF
BEING ORTHOGONALLY SCREENED

Frank Barendregt, and Leendert A. Boogaard, both of Boxmeer, Netherlands, assignors to Stork Brabant B.V., Boxmeer, Netherlands


Filed Sep. 28, 1979, Ser. No. 79,799

Claims priority, application Netherlands, Oct. 4, 1978, 7810032

Int. Cl.³ H04N 1/46

U.S. Cl. 358-75

8 Claims



1. A method of synthesizing a set of effective screened color separation images from an original composed of at least two different colors through the use of optical scanning in which the original is carried on a cylindrical surface which is rotated while a scanning beam is caused to move in two directions over the cylinder surface carrying said original, one direction being substantially parallel with the axis of the cylinder and the other direction being substantially perpendicular to said axis, the scanning mechanism being arranged to produce scanning points for reproduction at locations along the path of movement in said perpendicular direction, each separation image being synthesized in a program of movements of said beam relative to said cylinder which scans a predetermined area comprising at most all of said original and there being as many programs as separation images, said method comprising the following steps:

A. Establishing a base line on said cylinder which is parallel to the cylinder axis,

B. Scanning the surface of said cylinder in a first program of movements of said beam which program will include said

area of said original image and which is composed of movements in said two directions, one being axial and unilateral and the other being substantially perpendicular to the axis and unilateral in such a manner that consecutive perpendicular lines of movement are traced by said beam which are spaced by a second spacing (l_2) equal distances apart along the length of the cylinder, each perpendicular line of movement being a full circle of said cylinder,

C. sequentially generating discrete scanning point signals from scanning points spaced along the lengths of the consecutive perpendicular lines, said points having a certain first spacing (l_1) relative to one another and the first point of each perpendicular line which is defined by the beam after passing the base line to start scanning having a certain third spacing (l_3) above said base line, the resulting field of scanning points if developed in a plane from the surface of the cylinder being rectangular and including said area, the lower horizontal edge of said field being coincident with said base line and one of its end edges comprising a coordinate perpendicular to said base line, all of the scanning points occurring above the base line and forming two sets of parallel lines, each set being orthogonal relative to the other, one set being at an angle (α) relative to said coordinate, there being a fourth spacing (a) between the lines of each set and said fourth spacing being equal for both sets,

(i) the first, second and fourth spacings not necessarily being equal to one another but all distances of each respective spacing being the same for that particular spacing,

(ii) the third spacing being not necessarily the same for each particular line and being related to the order of scanning occurrence of said line with respect to the adjacent lines,

D. the program of movement being effected by driving said scanning mechanism in accordance with a certain trigonometrical relationship which takes the spacings and said angle into consideration to achieve said field of scanning points,

E. producing a first separation image from the scanning point signals derived from said field which fall on said area of said original, each signal adapted to form a printing element and the printing elements being respectively coincident with the scanning points of said field which fall on said image whereby said image area is reproduced on said separation image,

F. repeating steps A through E utilizing the identical base line and commencing the scanning at the identical point at which the first scanning program was commenced, but the second separation image differing from the first in that the angle relative to said perpendicular coordinate of the second field is a certain angle (α_2) different from the first mentioned certain angle (α) whereby there is a predetermined angular disposition of said one set of parallel lines of the one separation image relative to the corresponding set of parallel lines of said second separation image,

G. the fourth spacing (a) of both fields being equal and the dimensions of the separation images having the same proportional dimensions as said fields, the corresponding field dimensions being equal, respectively.

4,293,874

DC RESTORATION CIRCUIT FOR TELEVISION
RECEIVER

Daniel L. Reneau, Elmhurst, Ill., assignor to Zenith Radio Corporation, Glenview, Ill.

Filed Feb. 4, 1980, Ser. No. 118,127

Int. Cl.³ H04N 5/18

U.S. Cl. 358-172


13 Claims

1. In a television receiver of the type having means for developing a DC black level reference voltage and means for developing a transmitted video voltage signal with a DC volt-

age component, an improved black level clamp circuit comprising:

means for converting said video voltage signal to a corresponding video current signal with a DC current component;

means for abstracting from said video current signal a DC current feedback signal representing a fraction of said DC current component of said video current signal;



means for reconvert said video current signal to a corresponding output video voltage signal; and

gating means operable during a constant level portion of the horizontal blanking interval of said video voltage signal for directly adjusting said DC current feedback signal to equalize the values of said black level reference voltage and the DC component of said output video voltage signal.

4,293,875

WIDE BANDWIDTH VIDEO AMPLIFIER


Bernard R. Katz, Rockaway, N.J., assignor to Telegram Communications Corp., Denville, N.J.

Filed Jan. 3, 1980, Ser. No. 109,195

Int. Cl.³ H04N 5/14

U.S. Cl. 358-184

11 Claims



1. A wide bandwidth video amplifier circuit for driving a CRT or other electro-optical device in response to alphanumeric or other digital video signal input information comprising:

first and second solid state transistor amplifier elements connected in a complementary symmetrical configuration with a common collector output terminal adapted for connection to the cathode or grid of the cathode ray tube and with each transistor element having a base and emitter terminal;

level shifting circuit means coupling the base terminal of said first amplifier element to the video signal input such that said first amplifier element is enabled when said second amplifier element is disabled and vice versa;

DC shift means coupling the base terminal of said second amplifier element to the video signal input;

means for clamping the base to collector terminals of said first and second amplifier elements to prevent said ele-

ments from being driven deep into saturation in response to the video signal input;
a source of DC potential;
contrast control means coupling said source of DC potential across said first and second amplifier elements; and
capacitor means for bypassing said source of DC potential at video frequencies.

4,293,876

TELEVISION MONITORING SYSTEM


Jarvis L. Williams, 901 Satterlee, Bloomfield Hills, Mich. 48013

Filed Jan. 11, 1980, Ser. No. 111,300

Int. Cl.³ H04N 7/18

U.S. Cl. 358—211

28 Claims



1. A camera unit for a television monitoring system, comprising:

- a first camera, for monitoring principally during day-light conditions;
- a second camera, for monitoring principally during low-light conditions;
- a light intensifier in association with said second camera for intensifying the light received by said second camera; and
- control circuit means for selectively energizing, utilizing, and de-energizing either said first camera or said second camera and said light intensifier in response to a predetermined variation in ambient light intensity, so that a time delay is provided between said energizing and said utilizing of said cameras and said light intensifier.

4,293,877

PHOTO-SENSOR DEVICE AND IMAGE SCANNING SYSTEM EMPLOYING THE SAME

Tokuichi Tsunekawa, Yokohama; Makoto Masunaga, Tokyo; Kazuya Hosoe, Machida; Yukichi Niwa; Mitsutoshi Owada, both of Yokohama, and Noriyuki Asano, Kawasaki, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan


Filed Mar. 30, 1979, Ser. No. 25,542

Claims priority, application Japan, Mar. 31, 1978, 53-38565

Int. Cl.³ H04N 3/15; H01L 27/14

U.S. Cl. 358—213

25 Claims



17. A radiation sensing device comprising:

- (a) radiation sensitive means for providing electrical signals corresponding to received radiations;
- (b) means for providing an electrical signal indicative of a dark current of the sensing device;
- (c) means for receiving a bias voltage to be supplied to said device; and
- (d) means electrically coupled with said bias voltage receiving means so as to provide an electrical signal informing of internal voltage variation in said device relative to variation of said bias voltage,

wherein said radiation sensitive means, said dark current signal providing means, said bias voltage receiving means and said internal voltage variation information providing means are formed on or in the same semi-conductive substrate.

4,293,878

IMAGE PROJECTOR FOR A TELEVISION RECEIVER


Jacinto Sanchez, 692 W. 29 St., Apt. 12, Hialeah, Fla. 33012

Filed May 12, 1980, Ser. No. 148,774

Int. Cl.³ H04N 5/74, 9/31

U.S. Cl. 358—231

9 Claims



1. In combination a television receiver having an image screen and an image projection device, said device comprising a housing sized to receive the television receiver, said housing including a front wall and said front wall having an opening sized and shaped to fit compatibly over the television receiver screen, means for supporting the housing and a television receiver in the housing with the opening of the screen of the television receiver and the housing tilted at a common angle with respect to a horizontal reference line through the screen,

an inner projection shroud fixedly mounted to the television receiver screen, said inner shroud extending a predetermined distance from the screen, and said inner shroud having tapered side walls converging to a terminal end at a common plane,

an outer shroud fitted over the open wall of the housing and enclosing said inner shroud, said outer shroud having an open terminal end spaced a predetermined distance from said open housing wall and said outer shroud having tapered side walls converging to a terminal end at a common plane spaced from said first mentioned common plane, and

lens extension means fixedly connected to the open terminal end of the outer shroud and said lens extension means including a lens.

4,293,879

METHOD AND APPARATUS FOR THE VARIABLE SPEED REPRODUCTION OF A VIDEO SIGNAL STORED ON MAGNETIC TAPE

Jürgen Heitmann, Seeheim; Hans-Peter Maly, Darmstadt, and Rudolf Wilhelm, Büttelborn, all of Fed. Rep. of Germany, assignors to Robert Bosch GmbH, Stuttgart, Fed. Rep. of Germany


Filed Sep. 17, 1979, Ser. No. 75,978

Claims priority, application Fed. Rep. of Germany, Sep. 26, 1978, 2841728

Int. Cl.³ H04N 5/78

U.S. Cl. 360—10

12 Claims



1. A method of reproducing, at a selectable magnetic tape speed different from that used in recording, a video signal recorded on a tape in a multiplicity of separate parallel tracks, each containing only a fraction of the total number of picture lines making up a television field and obliquely directed across the tape, the reproducing method being performed with a head wheel carrying peripherally arranged magnetic pick-up heads scanning across the tape as the tape is advanced in such a way as to follow the recorded tracks with substantial accuracy in normal sequence when the tape is moved at the speed used in recording, so that at other playback speeds portions of the picked up signals are subject to cross-modulation moire disturbances and amplitude variations as the active pick-up head shifts off one track and onto another, said method comprising the steps of:

- generating a sequence of pulses at the frequency at which the active pick-up head shifts from one track to an adjacent track and synchronizing said track-shift pulses in frequency and phase by detected cross-modulation amplitude variations picked up by the active pick-up head;
- generating a sequence of pulses at the picked-up horizontal synchronizing pulse frequency and substantially in phase with the picked up horizontal synchronizing pulses;
- producing an uninterrupted series of horizontal synchronizing pulses by blanking any pick-up of horizontal synchronizing pulses during a gated interval derived from said track-shift pulses, while utilizing the unblanked picked-up horizontal synchronizing pulses to correct the phase of said generated horizontal synchronizing frequency pulses, thereby making available substitute pulses for utilization during blanking intervals;
- counting the pulses of said uninterrupted series of horizontal synchronizing pulses in a counter;
- detecting picked-up vertical synchronizing pulses and resetting said counter with each detected vertical synchronizing pulse;
- determining the value and sign of a numerical alteration of the content of said counter necessary at the time of appearance of a track-shift pulse in order to enable the counter content to continue to represent the address of each picked-up horizontal line with reference to a television picture;
- using a pulse derived from each said track-shift pulse to

enable the content of said counter to be altered by said numerical value and sign;
storing picked-up video signal lines individually for a period of a plurality of picture fields;
utilizing the content of said counter to provide an address for each stored individual video signal line;
reproducing a picture from stored lines picked up over a plurality of field periods by reproducing the lines in a sequence determined by the addresses provided for the stored lines by the content of said counter.

4,293,880

APPARATUS FOR RECORDING AND REPRODUCING VIDEO SIGNALS AT SELECTABLE DIFFERENT TAPE TRAVELING SPEEDS FROM A PLURALITY OF PAIRS OF VIDEO HEADS

Haruo Tsukada, and Yohichiro Nakatani, both of Mito, Japan, assignors to Victor Company of Japan, Ltd., Yokohama, Japan


Filed Oct. 10, 1979, Ser. No. 83,326

Claims priority, application Japan, Oct. 16, 1978, 53-141979[U]

Int. Cl.³ H04N 5/78; G11B 15/44

U.S. Cl. 360—10

6 Claims



1. An apparatus which selectively records and reproduces video signals on and from a tape in parallel tracks which are disposed obliquely relative to the longitudinal direction of the tape, and in any of a plurality of different tape speed modes, every field of the video signals being recorded and reproduced in a normal speed of picture motion for each of said different tape speed modes, said apparatus comprising:

- a rotary member rotating at a predetermined speed;
- a plurality of pairs of video heads for recording and reproducing the video signals on and from the tape, each of said pairs of video heads corresponding to one of said tape speed modes respectively and being mounted at different positions on a periphery of the rotary member with two video heads of each of said pairs diametrically disposed on opposite sides of the rotary member;
- means for selecting one of said pairs of video heads to operate in conformance with one of the selected tape speed modes; and
- means for driving the tape at a speed which is selected in conformance with said one selected tape speed mode; the pair of video heads operating in conformance with the selected tape speed mode and having a track width selected for forming contiguous tracks without gaps therebetween on said tape traveling at the selected tape speed mode.

4,293,881

SYSTEM FOR PRIORITY TRANSCRIBING OF DICTATION

Paul C. Mason, Thomaston, Ga., assignor to Lanier Business Products, Inc., Atlanta, Ga.

Continuation of Ser. No. 781,357, Mar. 25, 1977, Pat. No.


4,150,261. This application Nov. 6, 1978, Ser. No. 957,910

The portion of the term of this patent subsequent to Apr. 17, 1996, has been disclaimed.

Int. Cl.³ G11B 15/04, 15/22

U.S. Cl. 360—60

9 Claims



7. In a recording system having a transcribe location at which units of dictation recorded in sequence on a recording medium are transcribed as said recording medium is moved in a first direction relative to said transcribe location and subsequently is moved in said first direction along a path of motion extending from said transcribe location into a holding location within said recording system from which said recording medium is withdrawn for the recording of additional units of dictation:

selectively operative diverting means for diverting said recording medium from said path of motion into a retaining location discrete from said holding location within said recording system as said recording medium is moved in said first direction relative to said transcribe location, said retaining location being located between said transcribe location and said holding location; and means responsive to presence of recording medium in said retaining location for preventing said recording medium in said retaining location from being removed from said retaining location by motion of said recording medium in said first direction.

4,293,882

ENDLESS LOOP TAPE MAGAZINE, AND A RECORDING AND/OR PLAYBACK MACHINE UTILIZING THE MAGAZINE

Alfred H. Moris, St. Paul, Minn., assignor to Minnesota Mining and Manufacturing Company, St. Paul, Minn.

Continuation of Ser. No. 820,250, Jul. 29, 1977, abandoned. This application Apr. 5, 1979, Ser. No. 27,312


Int. Cl.³ G11B 23/02

U.S. Cl. 360—93

1 Claim

1. In a tape magazine including a fixed hub having an axis, a peripheral surface, a central opening, and a through slot extending axially across the hub between the peripheral surface and central opening; and an endless length of tape having a major portion wrapped around the peripheral surface of the hub to form a coil and a minor portion extending along a path from the innermost wrap of the coil through said slot, partially across the central opening and around the side surface of the coil to the outermost wrap of the coil to afford engagement of a drive mechanism with the tape along the path to pull the tape from the innermost wrap of the coil past a transducer positioned along the path, the improvement wherein said hub includes a plurality of axially spaced annular ribs extending

around said axis and defining said peripheral surface for the hub, which ribs both reduce the surface area on which the inner wrap of the tape bears against the hub to reduce friction therebetween, and reduce the areas of adjacent wraps of tape



4,293,883

MAGNETIC HEAD MOUNT ASSEMBLY


Allen R. Cox, Chandlers Ford, England, and Edmond W. Smathers, Boulder, Colo., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Dec. 26, 1979, Ser. No. 107,103

Int. Cl.³ G11B 5/48, 5/105, 21/20

U.S. Cl. 360—104

7 Claims



1. A magnetic head mount assembly comprising: a mounting post having a slotted portion at one end; an arm element having two opposing apertures for receiving said post in a close fit engagement; and an air bearing slider for supporting a magnetic transducing means mounted to said one end of said post at said slotted portion.

4,293,884

MULTIPLE LEG MAGNETIC TRANSDUCER STRUCTURE

Edward Schiller, Sunnyvale, Calif., assignor to Ampex Corporation, Redwood City, Calif.

Filed Dec. 26, 1979, Ser. No. 106,792

Int. Cl.³ G11B 5/12, 5/27, 5/105


U.S. Cl. 360—121

18 Claims

1. A magnetic transducer assembly having at least one pair of poles defining a transducing gap and a multiple leg back core contiguous with the poles, each leg providing a separate

flux path, the assembly being supported by a nonmagnetic core holder, comprising in combination:

- at least one magnetic core having two corresponding core portions made of a generally flexible magnetic material, each core portion comprising a pole and at least two leg portions contiguous with the pole, said pole and leg portions having smoothly lapped end faces defining a transducing gap plane;
- a nonmagnetic core holder having two corresponding side pieces each supporting one of said two corresponding magnetic core portions at the pole and intermediate leg



portions, while a rear leg portion most distant from said pole is unsupported by said holder; and

- the corresponding magnetic core portions being held in juxtaposition with corresponding end faces in registration at the transducing gap plane and with a transducing gap material disposed between said poles, said corresponding magnetic core portions being pressed together at said poles and intermediate leg portions supported by said core holder in a direction substantially normal to and towards said transducing gap plane while said rear leg portions unsupported by said core holder flex in a substantially opposite direction.

4,293,885

PAD SPRING FOR A TAPE CASSETTE


Hideo Shirako, Olympus Apartment House 146, No. 7-14-11, Owada-cho, Hachioji City, Tokyo, and Shoichi Saito, No. 2-49-13, Minami-dai, Nakano-ku, Tokyo, both of Japan

Filed Oct. 16, 1979, Ser. No. 85,304

Int. Cl.³ G11B 15/60

U.S. Cl. 360—130.33

3 Claims



1. A pad spring for use in a tape cassette to press a magnetic tape in the cassette against a magnetic head which enters the cassette, the cassette including a pair of fulcrum supporting members, said pad spring comprising a generally U-shaped center portion and a pad supporting portion joined to said center portion at each free end thereof to form a generally elongated spring body, each said pad supporting portion including a substantially flat, free end section fixed to a different one of free ends of said center portion and extending in the long direction of said spring body away from said center portion, a pair of pads each secured to a different one of said free end sections on the surfaces of said free end sections which face toward the magnetic head, and a projection formed on the surface of each of said free end sections which surface faces toward the fulcrum supporting members in the cassette for

contacting the fulcrum supporting members to provide a working fulcrum for each of said free end sections when the magnetic head is inserted into the cassette to contact one side of the tape and said pads contact the other side of the tape to press the tape against the magnetic head.

4,293,886

NETWORK PROTECTOR RELAY


Larry L. Church, Washington Township, Armstrong County; David R. Smith, McKeesport, and Shan C. Sun, Bell Township, Indiana County, all of Pa., assignors to Westinghouse Electric Corp., Pittsburgh, Pa.

Filed Dec. 17, 1979, Ser. No. 104,647

Int. Cl.³ H02H 3/26

U.S. Cl. 361—71

14 Claims



1. A network protector relay producing, entirely from sequence components, signals for opening and closing a connection between a polyphase feeder bus and a polyphase network bus, comprising:

input means producing signals representative of the positive and negative sequence components of the phase-to-ground voltages on the network side of said protector relay, the positive sequence component of the phasing voltages, and the positive sequence component of the phase currents;

first circuit means producing an $I_1 \cos \phi$ signal representative of the multiplication of said positive sequence component of said phase currents and the cosine of the phase angle between said positive sequence component of said phase currents and said positive sequence component of the phase-to-ground voltages;

means providing a first reference signal;

means comparing said $I_1 \cos \phi$ signal and said first reference signal, providing a trip signal opening said connection in response to a predetermined relationship therebetween;

second circuit means comparing the magnitude and the phase angle of said positive sequence component of said phase-to-ground voltages to the magnitude and the phase angle of said positive sequence component of said phasing voltages, providing a close signal closing said connection in response to a predetermined relationship therebetween;

means providing a second reference signal; and


third circuit means comparing said negative sequence component of said phase-to-ground voltages and said second reference signal, said means inhibiting said close signal from closing said connection in response to a predetermined relationship therebetween.

4,293,887

SURGE ARRESTER WITH IMPROVED IMPULSE RATIO
Frank G. Splitt, Mount Prospect, and Donald B. Turner, Des Plaines, both of Ill., assignors to Northern Telecom Inc., Nashville, Tenn.

Filed May 4, 1979, Ser. No. 36,088
Int. Cl.³ H02H 9/06

U.S. Cl. 361-120



1. A gas filled surge arrester having a design breakdown voltage value and having first and second electrodes defining a gaseous spark gap therebetween, characterized by:
a surface coating of ion source material outside of said spark gap adapted to emit ions into the spark gap region in response to an electric field;
said surface coating being conductive and in electrical contact with said first electrode;
said surface coating being insulated from said second electrode by a continuous solid insulator, and having an exposed surface facing said second electrode, a gap being present between said coating and said insulator; and
said surface coating cooperating with the second electrode to establish said electric field across said solid insulator in response to a rising surge voltage across the surge arrester, such that ions attracted from said surface coating are accelerated in the direction of said second electrode and exit into the spark gap region.


4,293,888

PRINT HAMMER DRIVE CIRCUIT WITH COMPENSATION FOR VOLTAGE VARIATION
Vincent D. McCarty, Austin, Tex., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Jun. 25, 1979, Ser. No. 51,580
Int. Cl.³ H01H 47/32

U.S. Cl. 361-152

2 Claims



1. A control circuit for a solenoid for controlling the application of a current of a preselected magnitude to the coil of the solenoid for a preselected time, said circuit comprising:
a current source selectively connected to said coil;
means for connecting said current source to said coil; and
means for interrupting current to said coil a predetermined time after said current in said coil has reached a predetermined level;
said interrupting means including a current sensor for sens-

ing said predetermined level, a current reference source and a comparator connected to both said current sensor and said current reference source.


4,293,889

DEVICE FOR GROUNDING AN ELEVATOR WINDER
Eiki Watanabe, Inazawa, Japan, assignor to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan

Filed Jul. 9, 1979, Ser. No. 55,837
Claims priority, application Japan, Jul. 11, 1978, 53/84323
Int. Cl.³ H02H 1/00

U.S. Cl. 361-212

8 Claims



1. A system for grounding an elevator winder comprising: an electric motor controlled by a semiconductor switching element; a first rotary element coupled to said electric motor; a main rope wound on said first rotary element; bearings adapted to support said electric motor and said first rotary element; a first grounding circuit for grounding said bearings through a resistor; and a second grounding circuit for grounding said main rope without a resistor.


4,293,890

CERAMIC CAPACITOR WITH END TERMINALS
Robert G. Varsane, Oxford, Conn., assignor to Vitramon Incorporated, Monroe, Conn.

Filed Oct. 1, 1979, Ser. No. 80,174
Int. Cl.³ H01G 1/14

U.S. Cl. 361-310

4 Claims



1. In combination a carrier for a monolithic ceramic capacitor and such capacitor, the capacitor comprising a dielectric material body, a first and a second major surface, two side surfaces and a first and a second end terminal; the carrier comprising a first conductive lead holding the capacitor adjacent the first end terminal and a second conductive lead holding the capacitor adjacent the second end terminal, each conductive lead having a first leg, said first leg having a first end and a second end, wherein the first end abuts against the first major surface of the capacitor and the second end is removably attached to a ribbon having a series of regularly spaced openings therein, a base extending outwardly from the first leg and abutting against a side surface of the capacitor and a second leg, connected at one end thereof to the base and abutting against the second major surface of the capacitor.


4,293,891

NATURAL AIR COOLED RACK FOR VERTICALLY DISPOSED PRINTED BOARDS
Kiyoshi Matsui, Katsuyuki Arai, and Suetoshi Shinbashi, all of Kawasaki, Japan, assignors to Fujitsu Limited, Kawasaki, Japan

Filed May 23, 1980, Ser. No. 152,559
Claims priority, application Japan, May 28, 1979, 54-64959
Int. Cl.³ H05K 7/20

U.S. Cl. 361-383

5 Claims



1. A natural air cooled rack for supplying cooling air to vertically disposed printed circuit boards comprising at least one vertical stack of cases, each case holding a plurality of said printed circuit boards in a vertical position, and, each case having draft openings on the upper surface and the lower surface thereof, said cases being arranged on said stack so that an interspace is formed between at least one upper case and a respective lower case;
a front member formed in the front portion of each said stack at each interspace to have at least one supply opening and at least one exhaust opening in the front portion of each said stack, said supply opening communicating with said draft opening on the lower surface of the respective upper case and said exhaust opening communicating with said draft opening on the upper surface of the respective lower case and said exhaust opening being located substantially above said supply opening in each said front member.


4,293,892

ZOOM LIGHT APPARATUS
William T. Plummer, Concord, Mass., assignor to Polaroid Corporation, Cambridge, Mass.

Filed Dec. 18, 1979, Ser. No. 104,860
Int. Cl.³ G03B 15/02

U.S. Cl. 362-17

28 Claims



1. Optical apparatus for selectively changing the angular spread of a projected light beam, said apparatus comprising:
a pair of optical refracting elements; and
means for positioning said elements in the projected light beam so that at least part of the light from the light beam can pass successively through said elements and for mounting said elements for relative movement with re-

spect to one another along an axis parallel to the general direction of projection of the beam,
said elements being optically structured to change the initial angular spread of the beam of light by a predetermined amount when said elements are separated by a predetermined distance along said axis and to continuously further change the initial angular spread of the beam of light as the distance separating said elements is made smaller than said predetermined separation distance.

4,293,893


APPARATUS FOR CONTROLLING LIGHT PROJECTION ANGLE OF HEAD LAMP OF MOTOR VEHICLE

Yoshihiko Tsuzuki, Anjo; Sumihiro Kaga, Inazawa, and Nobuhito Hobo, Inuyama, all of Japan, assignors to Nippon-denso Co., Ltd., Kariya, Japan

Filed Aug. 31, 1979, Ser. No. 71,568
Claims priority, application Japan, Oct. 20, 1978, 53-129655
Int. Cl.³ B60Q 1/10; F21V 21/30; B60Q 1/06

U.S. Cl. 362-38

3 Claims



1. An apparatus for controlling the optical axis of a head lamp assembly of a motor vehicle, comprising:
a head lamp assembly supported so that the light projecting axis thereof can be angularly varied in upward and downward directions;
an actuator adapted to be selectively supplied with the atmospheric pressure and a negative pressure available from an intake conduit of an internal combustion engine of said motor vehicle through associated electromagnetic valves and produce mechanical displacements in dependence of said pressures;
a linkage mechanism for transmitting said mechanical displacements for bringing about corresponding variations in the angular position of said light projecting optical axis of said head lamp assembly;
first switch means for detecting angular position of said light projecting optical axis of said head lamp assembly, said first switch means including paired electric contacts, the contacting states of which are sequentially changed over in response to the operation of said linkage mechanism;
second switch means for setting angular position of said light projecting optical axis of said head lamp assembly in response to command, said second switch means including paired electric contacts, the contacting states of which are sequentially changed over to produce said command;
and an electric circuit which responds to difference in the contacting states between said first and second switch means thereby to produce correspondingly energizing signals for said electromagnetic valves.

4,293,894

BATTERY OPERATED ILLUMINATING DEVICE
Nolan D. Blank, 2294 Stow Ave., Simi Valley, Calif. 93063


Filed Mar. 17, 1980, Ser. No. 130,604
Int. Cl.³ E05B 17/10

U.S. Cl. 362-100

10 Claims

1. In a device adapted for mounting to a surface for illuminating an adjacent area, the combination comprising:

a base member having means for securing to a surface;
a housing having a closed end and at least one sidewall extending therefrom defining an open end, said closed end being deformable upon depression thereof;



coacting means on said base member and the open end of said sidewall for securing said housing to said base member;

lens means in said at least one sidewall; and electrically operable illumination means within said housing operable upon depression of said closed end.

4,293,895

MOUNTING ARRANGEMENT FOR RECESSED LIGHT FIXTURE HOUSING


Paul J. Kristofek, Hickory Hills, Ill., assignor to McGraw-Edison Company, Rolling Meadows, Ill.

Filed Aug. 23, 1979, Ser. No. 68,934

Int. Cl.³ F21V 33/00

U.S. Cl. 362-147

6 Claims



1. An arrangement for mounting an enclosed light fixture housing having an open end with a flange formed about the periphery thereof, in an aperture defined in a planar member having first and second surfaces, said housing being receivable in said aperture with said flange engaging said second surface, said arrangement including in combination:

a side wall of said light fixture housing defining a slotted aperture, locking means provided on said side wall adjacent said slotted aperture, said locking means including ratchet teeth formed along said housing wall adjacent said slotted aperture, support frame means mounted along the first surface of said planar member and defining an aperture dimensioned for receipt of said light fixture housing and being aligned with the aperture defined in said planar member and resilient mounting clip means extending outwardly from said support frame means toward said aperture, the free end of said mounting clip means being receivable in said slotted aperture in said housing side wall upon insertion of said housing into said aligned apertures of said planar member and support frame means, said mounting clip means further including means cooperating with said ratchet teeth for removably securing said housing on said support frame means.

4,293,896 BATTERY-OPERATED LANTERN

Chung-Chee Wong, Kowloon, Hong Kong, assignor to San P. Kong, Kowloon, Hong Kong


Filed Jul. 16, 1979, Ser. No. 57,675

Claims priority, application United Kingdom, Jul. 20, 1978, 30445/78

Int. Cl.³ F21L 7/00

U.S. Cl. 362-200

4 Claims



1. A battery operated lantern comprising: a hollow body having therein an elongated tubular compartment for a plurality of single-cell batteries arranged end-to-end in two side-by-side rows and all electrically connected in series with each other, said body including a bottom wall having an aperture therein opening into one end of said compartment and through which aperture batteries can be inserted into and removed from the compartment lengthwise of the batteries; a closure member mounted in said aperture, which closure member is made from an electrically insulating material and which extends in a plane normal to the lengthwise dimension of said elongated compartment, said closure member being movable out of said aperture; a rigid metal contact plate mounted on and electrically insulated from the inner face of said closure member and adapted to make electrical contact with the base of the adjacent battery in one of said rows and with the central electrode of the adjacent battery in the other of said rows; a pair of contact elements at the end of said elongated compartment remote from the closure plate and arranged respectively to make electrical contact with the central electrode of the adjacent battery in said other row and said contact elements being resilient for pressing the batteries in the respective rows resiliently lengthwise of the batteries towards the closure member; a spring loaded catch at one edge of said closure member for automatically securing the member in its closed position as the plate is moved into said closed position; and a manually operable element for moving the catch into an inoperative position against the restraint of its spring loading.

4,293,897

MOTOR VEHICLE HEADLIGHT

Alain Deverreware, La Varenne, France, assignor to Cibie Projecteurs, France

Filed Jan. 31, 1980, Ser. No. 117,090

Claims priority, application France, Jan. 31, 1979, 79 02483


Int. Cl.³ F21V 7/00

U.S. Cl. 362-284

6 Claims

1. A motor vehicle headlight comprising a casing closed by a front glass, a mirror mounted to pivot inside the casing, said casing being formed with an aperture serving for mounting a control member constituting an end of a remote control chain, said control member having an active part comprising a movable member which passes through the aperture, said pivoting mirror being provided with connecting means opposite said aperture, said connecting means being arranged for cooperation with said movable active part, and the aperture, the con-

necting means and the control member being arranged so that the mounting of the control member on the casing brings about



operational connection of said movable active part and the mirror.

4,293,898

GARDEN LIGHT FIXTURE


William F. Budnovitch, Summit; Salvatore C. Petralia, Sayreville, and Louis F. Silvestris, Bayonne, all of N.J., assignors to Keene Corporation, Union, N.J.

Filed Nov. 13, 1979, Ser. No. 93,273

Int. Cl.³ F21J 7/00

U.S. Cl. 362-291

8 Claims



1. A light fixture comprising:

a transparent cylindrical housing having open top and bottom ends;

at least one groove extending circumferentially about said housing intermediate said top and bottom ends;

at least one groove extending axially along said cylinder from said circumferential groove to one of said ends;

and at least one shade having a generally annular member including an inner opening substantially equal in diameter to that of said cylinder and at least one keyway extending into said inner opening, said keyway being dimensioned to fit into said cylindrical housing axially and circumferential grooves;

whereby said one shade may be locked into position about said housing when said one keyway is in said circumferential groove but not within said axial groove and said one shade may be positioned for removal by rotating said shade until said keyway is positioned within said axial groove.

4,293,899

LUMINAIRE

George E. Sanner, Cypress Hill, Sparks, Md. 21152

Filed Dec. 21, 1978, Ser. No. 971,739


Int. Cl.³ F21V 29/00

U.S. Cl. 362-294

1 Claim

1. A luminaire comprising: a transparent or translucent quadric globe telescoped over a transparent or translucent circular flat base member; said globe having a cylindrical section intersecting the lower base of a closed frustoconical

section at a plane generally coincident with the plane of the flat base member; said flat base member spanning the opening of said cylindrical section of said globe, and a flange around the periphery of said flat portion abutting the interior of said cylindrical portion of said globe; means for securing said globe to said base providing for easy removal and replacement of said globe; a cylindrical cap centrally abutting and attached to the exterior surface of said base member; a lamp socket and lamp protruding through concentrically aligned center holes in said base member and in said cap, and attached to said cylindrical cap; means defining a first plurality of circumferentially spaced sets of vertical intake holes in said flat base in an annular area thereof abutting the peripheral extremity of said lamp socket; means defining a second plurality of circumferentially spaced sets of vertical exhaust holes in said flat base in an annular area thereof circumferentially abutting the external periphery of



said flat base; said first and second sets of holes being equal in number and radially aligned with respect to the center of said flat base and spaced, radially, from each other to thereby define an annular, flat, closed area between said first and second sets of holes, whereby a convection air current system is defined by said base and within said globe for admission of air through the intake holes, past the lamp and out said exhaust holes to cool the luminaire during use and prevent its overheating; electrical connection means for energizing said lamp from an electrical source externally of said luminaire; and an open topped cylindrical partition located in the interior of said quadric globe, the lower end of said partition resting on said annular, flat closed area of said base member, and the upper, open end of said partition extending near to but being spaced from the interior surface of the frustoconical upper base of said globe thereby providing a convective intake flue and exhaust plenum for cooling of said luminaire.

4,293,900

LUMINAIRE REFLECTOR


Theodore D. Dziubaty, Gibsonia, Pa., assignor to Forum, Inc., Pittsburgh, Pa.

Filed Oct. 9, 1979, Ser. No. 82,577

Int. Cl.³ F21V 7/00

U.S. Cl. 362-342

15 Claims



1. A luminaire reflector comprising a side-by-side series of vertically-curved reflector segments forming in combination at least a larger segment of a bowl-like reflector with reflective surfaces on the inside thereof and having a mouth at its upper end which forms the largest diameter thereof, each of said

reflector segments consisting of a stepped vertical series of reflector sections pre-focused to direct light coming from a source within the bowl-like reflector out over said mouth into a predetermined radiation zone, said reflector sections having inwardly-convex curvature in the horizontal direction.

4,293,901

REFLECTOR SYSTEM HAVING SHARP LIGHT CUTOFF CHARACTERISTICS


Jose A. Hernandez, San Marcos, Tex., assignor to Esquire, Inc., New York, N.Y.

Filed Dec. 17, 1979, Ser. No. 104,011

Int. Cl.³ F21V 7/06

U.S. Cl. 362-346

12 Claims



1. A sharp cutoff reflector including a plurality of parabolic segments and housing a lamp therein so that its center is at the concentric focal point of the parabolic segments of the reflector, comprising
 - a top parabolic reflector segment having a narrow beam reflective surface,
 - a bottom parabolic reflector segment having a narrow beam reflective surface,
 - said top and bottom parabolic reflectors terminating in a window opening plane approximately 60 degrees to the parabolic elongate axis,
 - a reflective shield above and parallel with the elongate axis, the window end thereof being at a position in the range of approximately 5-40 degrees to the horizontal with respect to the focal points, the rearward end thereof being on a line between the focal points and the exit pupil of the window opening at said top reflector segment.

4,293,902

TRANSFORMERLESS FAST CURRENT LIMITER WITH SYMETRY CORRECTION FOR A SWITCHED-MODE POWER SUPPLY

John E. White, Port Moody, Canada, assignor to AEL Mirrotel, Ltd., Burnaby, Canada

Filed Dec. 4, 1979, Ser. No. 102,207

Int. Cl.³ H02P 13/22


U.S. Cl. 363-26

4 Claims

1. In a switched mode power supply which operates from a DC power source, a fast current limiter comprising:
 - a DC-to-DC converter adapted for connection to said DC power source includes a pair of switching transistors connected in push-pull wherein the emitters are connected together and to one terminal of the power source, the collectors are connected to the opposite ends of a primary winding of a center-tapped transformer, the center-tap is connected to the other terminal of the power source and the secondary winding is connected to a rectifier-filter circuit in which the pulsed output from the inverter is changed into a DC voltage which is available at output terminals thereof and in which a voltage representative of

the output voltage is provided at a feedback output terminal;

- a pulse width modulator having first and second gating circuits, the output terminals of which are connected to the bases of said first and second switching transistors, respectively, and provide the drive thereof, a clock for establishing a pulse repetition rate of the transistors and means connected to the output of said clock for alternately enabling said first and second gating circuits, a sawtooth generator operating at said predetermined pulse repetition rate for providing a sawtooth reference voltage at an output, and a first comparator having a first input connected to the output of said sawtooth generator, a second input connected to said feedback output terminal of said converter and an output connected to an input of each said gating circuit so as to control the on-time of the switching transistor connected to an enabled gating circuit as long as there is no overcurrent present;
- a transformerless current-sensing means, adapted for connection in the path between said DC power source and



- said converter, for providing, at an output terminal, an output signal representative of the current flowing in said path; and
- a current-limiter control comprising:
 - a second comparator responsive to said sawtooth voltage and to the output signal of said transformerless current-sensing means for changing the second comparator output of a first binary state to the other binary state at an output terminal when the sensed current exceeds a predetermined value;
 - a third gating circuit responsive to the output condition from said second comparator means and a timing signal from said clock to provide an enable or pulse termination state at said output, depending upon whether the sensed current is below or exceeds said predetermined value; and
 - means for connecting the output of said third gating circuit to a third input of each of said first and second gating circuits, whereby said first and second switching transistors are turned off if an overcurrent occurs in either of the clock enabled states.

4,293,903

HIGH VOLTAGE RECTIFIER FOR TELEVISION RECEIVER SETS

Hideyuki Mochida; Shingo Tamura, and Etsuo Tsurumi, all of Yokohama, Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Filed Apr. 29, 1980, Ser. No. 144,919

Claims priority, application Japan, May 2, 1979, 54-58234[U]


Int. Cl.³ H02M 7/10; H04N 3/18

U.S. Cl. 363-68

5 Claims

1. A high voltage rectifier for use in a television receiver set comprising:
 - (a) a core;
 - (b) a primary coil wound on a primary coil bobbin mounted on the core;
 - (c) rectifier means including a plurality of secondary coils wound on a secondary coil bobbin which surrounds the

- primary coil bobbin, and one or more diodes connected in series with the plurality of secondary coils;
- (d) a casing which houses said primary and secondary coils and said diodes;
- (e) an insulating resin material filled in the casing to make integral the primary coil, secondary coils and diodes and to provide electrical insulation therebetween;
- (f) a resistor block, electrically connected to said rectifier means, for dividing voltage developing at said rectifier means so as to generate a first voltage and a second voltage which is lower than the first voltage;
- (g) means for fixing the resistor block to said casing near said secondary coils;



- (h) a first electrical conductor, electrically connected to said resistor block, for picking up the first voltage from said resistor block;
- (i) a second electrical conductor, electrically connected to said resistor block, for picking up the second voltage from said resistor block, said second electrical conductor surrounding the first electrical conductor to sealingly cover it and extending in the same direction as the first electrical conductor;
- (j) a first insulating member, interposed between the first and second electrical conductors, for insulating the two conductors under the application of DC voltage; and
- (k) a second insulating member covering the second electrical conductor.

4,293,904

POWER FREQUENCY CONVERTER


James L. Brooks, Oxnard, Calif.; James C. Bowers, and Harry A. Nienhaus, both of Tampa, Fla., assignors to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Nov. 21, 1979, Ser. No. 97,028

Int. Cl.³ H02M 5/45, 5/458

U.S. Cl. 363-86

14 Claims




chopping said rectified current to produce direct current pulses, and applying said direct current pulses to said load.

4,293,906 CONVERTER

Lawrence E. Trowbridge, 4806 Oak St., Seabrook, Tex. 77658
Filed Mar. 5, 1979, Ser. No. 17,257
Int. Cl.³ H02M 7/515

U.S. Cl. 363—135

8 Claims



1. Power converting apparatus for changing direct current to a chosen frequency alternating current,

- a transformer having
- a primary winding with the direct current supplied intermediate its ends; and
 - a secondary winding being grounded intermediate its ends;

means mounted with the primary of said transformer for converting the direct current to a series of pulses in the primary winding which includes a pulse train forming an effective current with reciprocal positive and negative sine wave components for each half cycle of the chosen frequency wherein said converting means includes first and second silicon controlled rectifiers mounted in series with one end of the primary winding of said transformer, third and fourth silicon controlled rectifiers mounted in series with the other end of the primary, first signal generating means for alternatively firing the first and third silicon controlled rectifiers, and second signal generating means for simultaneously firing the second and fourth silicon controlled rectifiers, wherein said first and second signal generating means provide firing signals of different frequencies and chosen frequency of the effective current being proportionate to the difference between the firing signal frequencies;

gating means mounted with the secondary of said transformer for sequentially passing the pulses in the negative sine wave component of the effective current followed by the pulses in the positive sine wave component, said gating means passing the pulses received in the secondary winding synchronously with the pulses in each half cycle of the pulse train to form a chosen frequency alternating current component; and

- a filter mounted with the said gating means for removing selected components of the gated signal while providing an output of the chosen frequency alternating current.

4,293,907

DATA PROCESSING APPARATUS HAVING OP-CODE EXTENSION REGISTER

Victor K. Huang, Scotch Plains, and Richard L. Rath, Summit, both of N.J., assignors to Bell Telephone Laboratories, Incorporated, Murray Hill, N.J.

Filed Dec. 29, 1978, Ser. No. 974,426


Int. Cl.³ G06F 13/00

U.S. Cl. 364—200

6 Claims

1. A processor designed for executing a program of stored instructions through a sequence of instruction cycles, the processor being adapted to be coupled to memory means having a multiplicity of addressable locations for storing instructions and data, each instruction having an op-code portion and an address portion, and the data including operands and op-code extension words, the processor comprising:

- (a) instruction register means for storing an instruction;
- (b) instruction retrieval means for transferring a current instruction from the memory means to the instruction register means in each instruction cycle;
- (c) an op-code extension register for receiving and storing an op-code extension word;
- (d) control means responsive to the combination of the op-code portion of the current instruction and the contents of the op-code extension register for generating control signals corresponding to processor operations specified by the combination; and



- (e) data retrieval means responsive to particular control signals and to the address portion of the current instruction for transferring data specified by the address portion of the current instruction from the memory means to the processor, the data retrieval means transferring a specified op-code extension word from the memory means to the op-code extension register when the current instruction is a special instruction for transferring the specified op-code extension word to the op-code extension register.

4,293,908

DATA PROCESSING SYSTEM HAVING DIRECT MEMORY ACCESS BUS CYCLE


John J. Bradley, Framingham; Thomas O. Holtey, Newton Lower Falls; Robert C. Miller, Braintree; Ming T. Miu, Chelmsford; Jian-Kuo Shen, Watertown, and Theodore R. Staplin, Jr., Chelmsford, all of Mass., assignors to Honeywell Information Systems Inc., Waltham, Mass.

Filed Jan. 31, 1979, Ser. No. 8,001

Int. Cl.³ G06F 13/00

U.S. Cl. 364—200

11 Claims



1. A data processing system comprising a main memory capable of storing a plurality of data words, each data word of said plurality of data words having a unique memory address, said main memory coupled to a central processing unit (CPU) and an input/output controller (IOC) over a common bus for the bidirectional transfer of information between said main memory and said IOC during information transfer cycles, said system further comprising:

- A. first means, included in said IOC and coupled to said common bus, for enabling the transfer of a request signal via said common bus, said request signal indicating a

request for a transfer of data between said main memory and said IOC;

- B. second means, included in said CPU and coupled to said common bus, responsive to said request signal for enabling the transfer of an address information from a third means via said common bus to said main memory during an address cycle generated at a point in time following receipt of said request signal, said address cycle being a particular type of said information transfer cycles;
- C. said third means, included in said IOC and coupled to said common bus, for transmitting said address information to said main memory via said common bus;
- D. fourth means, included in said IOC and coupled to said common bus, for enabling the receipt of data information transmitted from said main memory to said IOC via said common bus if a read operation or for enabling the transmission of said data information by said IOC via said common bus to said main memory if a write operation during a data transfer cycle generated at a point in time following said address cycle, said data transfer cycle being a particular type of said information transfer cycles;
- E. fifth means, included in said IOC and coupled to said second means and said third means, for generating said address information, wherein said address information comprises a memory address and an indication of whether the addressed location is to be written into or read from said main memory;
- F. sixth means, included in said IOC and coupled to said fifth means, for storing and augmenting said memory address, by one location said augmentation taking place once per address cycle;
- G. seventh means, included in said IOC and coupled to said first means, for storing and decrementing a range as to the number of data words yet to be transferred, said range to be decremented by one once per address cycle;
- H. an other IOC, coupled to said common bus, said other IOC including means for generating said request signal;
- I. eighth means, included in said IOC and coupled to said first means and said common bus, for inhibiting the generating of said request signal when said other IOC has already generated said request signal; and
- J. ninth means, included in said IOC and coupled to said first means and said eighth means, for receiving a synchronization signal via said common bus and enabling said first means to generate said request signal only if said synchronization signal indicates that it is said IOC's unique time to request allocation of said common bus, whereby said request signal will be generated on said common bus by said IOC only if it is said IOC's unique time to make requests and said other IOC is not already making a request for allocation of said common bus.

4,293,909

DIGITAL SYSTEM FOR DATA TRANSFER USING UNIVERSAL INPUT-OUTPUT MICROPROCESSOR

Robert D. Catiller, Garden Grove, and Brian K. Forbes, Huntington Beach, both of Calif., assignors to Burroughs Corporation, Detroit, Mich.

Filed Jun. 27, 1979, Ser. No. 52,336

Int. Cl.³ G06F 3/04


U.S. Cl. 364—200

10 Claims

1. In a digital system for the transfer of data between a main host computer, having a main memory, and a plurality of remote peripheral terminal devices wherein each peripheral terminal device is connected with its own dedicated peripheral-controller, and wherein a plurality of said peripheral-controllers are organized into groups designated as base modules such that each base module has its own message level interface bus connecting it, via a main system interface unit designated as an input-output translator, to a main host computer having a main processor and said main memory, and wherein said input-output translator provides means to connect and disconnect selected peripheral controllers, in each base module, with said main memory without interrupting the main processor,

and further provides an I/O data transfer command word, an I/O descriptor-link word to identify each particular data transfer task for each peripheral-controller in said system, said peripheral-controller comprising:

- (A) an Application Dependent Logic Module for interfacing a selected peripheral terminal device, and including:
 - (a) an external RAM memory for temporary storage of data undergoing transfer and for storing program data used for controlling data transfers to/from said peripheral terminal device and selected external registers;
 - (b) said plurality of external registers for temporary storage of data to be transferred to/from said peripheral terminal device, and data to be transferred to/from a microprocessor system, and including a message level interface bus to said main host system;
 - (c) a control logic unit, connected to a decoder-controller, for executing data transfers to/from said peripheral terminal device and for providing control signals to said microprocessor system;
- (B) said microprocessor system operating in cooperation with said Application Dependent Logic Module, said microprocessor system including:
 - (a) data processing means including:
 - (a1) an arithmetic logic unit providing an output to a shift logic circuit and to a byte-swap circuit;
 - (a2) said shift logic circuit providing output to an I/O bus said shift logic circuit functioning to rotate one or more bits of a word being processed, to the right or to the left;
 - (a3) said byte-swap circuit providing output to said I/O bus said byte-swap circuit functioning to exchange the sequential positions of the higher order byte and the lower order byte of a received two-byte word;
- (b) said I/O bus providing connecting lines from said data processing means to said external registers, to said external memory, to an accumulator register means, and to an addressing means;
- (c) said addressing means receiving input data from said I/O bus and storing addresses useful for accessing data from an internal memory or said external memory storage, said addressing means including:
 - (c1) a program counter storing consecutive addresses of data located in said internal program memory;
 - (c2) a memory reference register for storing addresses of data located in said external memory, and including:
 - (c2-1) a memory address bus which connects to said external memory;
 - (c2-2) and wherein a dedicated non-address bit in said memory reference register may be set to signal said decoder-controller to initiate a byte-swap circuit, or when not-set, to pass data without a byte-swap operation;
 - (c2-3) a bus connection from said memory reference register to said decoder-controller
 - (c3) an address register in said decoder-controller con-



4,293,914

AUTOMATIC CONTROL SYSTEM FOR CARWASH INSTALLATIONS


Nguyen Van Trang, 139 Alta Ave., Santa Monica, Calif. 90402

Filed May 24, 1979, Ser. No. 42,128

Int. Cl.³ G05B 19/00

U.S. Cl. 364-478

4 Claims



1. A control system for carwash installations incorporating a plurality of task-performing devices disposed along a conveyor adapted to bear vehicles from an entrance station towards a discharge station, comprising:

input control means, responsive to an enter switch disposed proximate to said entrance station and activated by the passage of a vehicle therethrough;

a plurality of program control units, each comprising timer control means adapted to be operative or inoperative and gate control means, responsive to signals from said input control means when said timer control means are inoperative, said program control units disposed sequentially along control paths between said input control means and said task-performing devices;

each of said timer control means operative to activate said task-performing devices in a pre-determined time sequence corresponding to the transit time of said conveyor between said entrance station and said discharge station; each of said gate control means adapted to activate the timer control means associated therewith or to transfer said signals sequentially to another of said program control units,

whereby said task performing devices incorporated in said carwash installation are activated in a time-synchronized manner as one or more vehicles transit said conveyor, with one of said program control units controlling the operation of the task-performing devices for each such vehicle.

4,293,915

PROGRAMMABLE ELECTRONIC REAL-TIME LOAD CONTROLLER

Edward J. Carpenter, Lynnwood; William W. Korff, Seattle, both of Wash.; Alan E. Zoerb, deceased, late of Seattle, Wash. (by Delores E. Zoerb); Lawrence J. Barelli, Bellevue, Wash.; Donald R. Hall, Edmonds, Wash., and Orlin N. Becker, Lynnwood, Wash., assignors to Pacific Technology, Inc., Renton, Wash.

Filed Apr. 16, 1979, Ser. No. 30,348

Int. Cl.³ G01R 21/00; G06F 15/06

U.S. Cl. 364-493

25 Claims

1. An electronic controller for controlling the energization states of each of a plurality of electrical loads in real-time, said controller comprising:

a plurality of load control circuits, each said load control circuit being adapted to be interconnected with a load, and having a load-on state when its load is to be on, and a load-off state when its load is to be off;


clock means for accumulating real-time information; and, a data processor, including:

an event memory for storing a plurality of load groups of information, each said load group being uniquely associated with one of the plurality of electrical loads and comprising one or more control events and an event

time corresponding to each said control event, said control events in each said load group representing: an on control function in which the associated load is to be on for the entirety of each predetermined control interval successive to the corresponding event time; an off control function in which the associated load is to be off for the entirety of each predetermined control interval successive to the corresponding event time; and, a duty-cycle control function in which the associated load is to be on for a predetermined portion of each predetermined control interval successive to the corresponding event time;

a program memory storing a set of program instructions; and,

a processing means operative in response to said set of



program instructions stored in said program memory, said processing means including: means operative to enter said control events and corresponding event times for each load into the associated load group in said event memory; means for obtaining said real-time information from said clock means; means for addressing and searching the associated load group for each load in said event memory to effect comparison of said event times therein with said real-time information obtained from said clock means; and, means for placing said load control circuit for each load in said load-on state or said load-off state in accordance with that one of said control events in said associated load group whose corresponding event time is at or immediately precedes the time represented by said real-time information obtained from said clock means.

4,293,916

APPARATUS FOR GENERATING SIGNALS SIMULATING THE OUTPUT OF A DEVICE FOR MEASURING A PHYSICAL VARIABLE

Pietrantonio Del Re, Bra, and Pietro Fracassi, Milan, both of Italy, assignors to Carlo Gavazzi S.p.A., Milan, Italy

Filed Oct. 9, 1979, Ser. No. 82,479

Claims priority, application Italy, Oct. 31, 1978, 29297 A/78


Int. Cl.³ G06F 15/20

U.S. Cl. 364-571

9 Claims

1. An apparatus for generating electric signals for simulating the output of a measuring apparatus sensitive to a physical variable and providing an output electric signal indicative of the measured physical variable comprising a selector for choosing the type of measuring apparatus to be simulated, a measuring unit selector, a selector for selecting the value of a physical variable the measurement of which is to be simulated,

a computer circuit controlled by said selectors and including a memory to contain information concerning the types of measuring apparatus that can be selected, and means controlled by said computer circuit for supplying a simulated output signal to output terminals.



means controlled by said computer circuit for supplying a simulated output signal to output terminals.

4,293,917

NON-LINEAR FUNCTION GENERATOR


Philip D. Wasserman, Cupertino, Calif., assignor to Stanford Associates, Inc., Menlo Park, Calif.

Filed Nov. 28, 1979, Ser. No. 97,913

Int. Cl.³ G06F 1/02, 15/31

U.S. Cl. 364-701

16 Claims



13. A function generator comprising:

- (a) a rate multiplier circuit having a constant multiplicand;
- (b) a memory circuit connected to said rate multiplier circuit for selecting the multiplier for said rate multiplier circuit;
- (c) first means connected to the output of said rate multiplier circuit and to said memory circuit for addressing said memory circuit in response to the output of said rate multiplier circuit to select a multiplier for said rate multiplier circuit; and
- (d) second means responsive to the output of said first means for presenting a non-linear function with respect to a time interval.

4,293,918

DIGITAL DIFFERENTIAL ANALYZER WITH AN INCREMENT OUTPUT FUNCTION

Yukio Asakawa, Hitachi, Ltd., Japan, assignor to Hitachi, Ltd., Tokyo, Japan

Filed Oct. 19, 1979, Ser. No. 86,444


Claims priority, application Japan, Oct. 20, 1978, 53-128487

Int. Cl.³ G06F 7/64

U.S. Cl. 364-702

6 Claims

1. A digital differential analyzer having a function of pro-



with respect to said second value, and for determining the sign of any such increment from the signs of said first and second values, the sign of the result of said first operation and the determination by said second operation,

a second register coupled to said logic circuit for storing a first signal indicative of the sign of said increment determined by said logic circuit,

a third register coupled to said logic circuit for storing a second signal indicative of the result of the determination by said logic circuit as to the presence of any increment in said first value,

a second arithmetic logic unit coupled to said second and third registers for performing a third operation in which the value of said second data latched in said second latch register is modified by an increment determined according to said first and second signals stored in said second and third registers, and

means coupled between said second arithmetic logic unit and said first register for renewing the value of said second data stored in said first register by the result of said third operation.

- plurality of instructions, and for storing a plurality of words of I/O status data in a storage area, and
- (b) main processor means located in the main processor, the main processor means being connected to the bidirectional data port and to the main memory means, and the main processor means being operable to sequentially read and execute the instructions stored in the main memory means to couple a plurality of words of I/O status data between the bidirectional data port and the storage area in the main memory means during a main I/O scan; and
- a high density I/O interface module coupled to the main processor of the controller through the bidirectional data port and including:
- (c) high density memory means for storing a plurality of words of I/O status data, for storing a first group of machine instructions for coupling the words of I/O status data between the high density I/O interface module and the I/O device circuits during a peripheral I/O scan, and for storing a second group of machine instructions for inter-processor communication through the data port;
- (d) a module I/O bus;
- (e) sequencing means, connecting a plurality of the word-oriented I/O device circuits to the module I/O bus, for coupling the plurality of words of I/O status data therebetween; and
- (f) high density processor means coupled to the bidirectional data port, connected to the high density memory means, and connected to the sequencing means through the module I/O bus and through sequencing control lines, the high density processor means being operable to sequentially read and execute the second group of machine instructions in the high density memory means to couple words of I/O status data between the high density memory means and the bidirectional data port during the main I/O scan, and being operable to sequentially read and execute the first group of machine instructions in the high density memory means to operate the sequencing means through the sequencing control lines and sequentially couple the plurality of words of I/O status data between the high density memory means and a corresponding plurality of word-oriented I/O device circuits to accomplish the peripheral I/O scan,

whereby the plurality of words of I/O status data are coupled between the storage area in the main memory means and the word-oriented I/O device circuits through the peripheral I/O scan at the I/O interface to monitor and control the I/O devices on the controlled system.

4,293,925

APPARATUS AND METHOD FOR INDICATING A MINIMUM DEGREE OF ACTIVITY OF DIGITAL SIGNALS

George A. Haag, Colorado Spring; O. Douglas Fogg, Loveland; Gordon A. Greenley, Colorado Spring; Steve A. Shepard, Colorado Spring, all of Colo., and F. Duncan Terry, Meridan, Id., assignors to Hewlett-Packard Company, Palo Alto, Calif. Division of Ser. No. 828,138, Aug. 29, 1977, abandoned, which is a continuation of Ser. No. 75,787, Sep. 17, 1979, abandoned, which is a continuation of Ser. No. 210,462, Nov. 25, 1980. This application May 31, 1979, Ser. No. 43,987

Int. Cl. G06F 3/14, 7/02


U.S. Cl. 364—900

4 Claims

1. A method of indicating the existence of at least a minimum amount of activity of individual digital signals among a collection of digital signals, the method comprising the steps of: monitoring the individual digital signals to determine in accordance with preselected thresholds and polarities the logical value of each of the individual digital signals; periodically capturing the logical values of the individual digital signals determined by the monitoring step; comparing after each capturing step each set of newly cap-

tured logical values with the most recent previously captured set, each such comparison being between the old and new logical values for each of the individual digital signals, for producing a set of indications indicating which individual digital signals have a newly captured logical value that differs from the most recent previously captured corresponding logical value;

combining after each comparing step the newest set of indications with a most recent cumulative result from previously combined previous sets of indications to provide a new cumulative result, the combining being the forming of the plurality of logical conjunctions between each



individual value in the newest set of indications and the corresponding value in the most recent previous cumulative result and the subsequent taking of the outcome of each of those logical conjunctions as a corresponding portion of the new cumulative result; and displaying the cumulative result of the combining step in a series of annunciator locations each associated with an individual digital signal, each annunciator location displaying one of first and second indications respectively representing the two possible outcomes of each of the logical conjunctions of the combining step, thereby indicating which digital signals are experiencing a minimum amount of activity and which are not.

4,293,926

DYNAMIC TYPE SEMICONDUCTOR MEMORY EQUIPMENT

Yutaka Amano, Tokyo, Japan, assignor to Hitachi, Ltd., Tokyo, Japan

Filed Feb. 13, 1979, Ser. No. 11,846

Claims priority, application Japan, Feb. 13, 1978, 53-14099

Int. Cl. G11C 7/00, 8/00, 11/00

U.S. Cl. 364—900

16 Claims

1. A data processing system comprising at least a central processing unit and a plurality of dynamic type semiconductor memory equipments operative in an asynchronous refresh mode and connected in common to a memory address bus, a memory data bus and a memory busy signal bus, respectively, which extend to said central processing unit, each of said memory equipments including:


- (a) means for receiving a memory starting synchronous signal from said central processing unit and fetching therein a designated memory address,
- (b) memory busy signal sender means for sending a memory busy signal to said central processing unit through said busy signal bus,
- (c) means for effecting transaction of memory data with said central processing unit through said memory data bus in accordance with said memory address,

wherein said dynamic type semiconductor memory equipment operative in an asynchronous refresh mode includes:

- (i) a memory starting register for receiving at the input thereof said memory starting synchronous signal from said central processing unit, latching said memory start-

ing synchronous signal and sending a memory access request signal, and adapted to be reset upon reception of a first reset signal produced when said refresh operation indicating signal is absent,

- (ii) an address register for fetching therein said memory address from said central processing unit through said memory address bus in response to said memory starting synchronous signal, latching said memory address and sending an addressing output signal therefrom to a memory block incorporated in each of said dynamic type semiconductor memory equipments, and adapted to be reset upon reception of said first reset signal produced when said refresh operation indicating signal is absent,
- (iii) a refresh request circuit including means for producing a refresh request pulse at a predetermined refresh period, means for latching said refresh request pulse to send a refresh request signal and means for resetting said refresh request signal by said first reset signal when a refresh operation indicating signal for indicating that refresh operation takes place is present,
- (iv) a preference control circuit including a memory access flip-flop and a refresh operation indicating flip-flop for producing said refresh operation indicating signal, said flip-flops being so adapted that either one of them is set with preference over the other in response to



either one of said memory access request signal and said refresh request signal, while both of said flip-flops are adapted to be reset by said second reset signal, and a timing start flip-flop adapted to be set in dependence on the logical sum of the output signals from both of said memory access flip-flop and said refresh operation indicating flip-flop and reset by a third reset signal, (v) a timing circuit adapted to be started in response to said output signal from said timing start flip-flop thereby to produce a predetermined memory block drive signal, said timing circuit being further adapted to produce said first reset signal at a given time after termination of said memory block drive signal, to produce said second reset signal at a given time after termination of said first reset signal and to produce said third reset signal after a predetermined time elapse required for producing said memory block drive signal, and

- (vi) means for transmitting said memory busy signal to said central processing unit through said memory busy bus by controlling said memory busy signal sender means with the aid of the output signal from said memory access flip-flop,

wherein said preference control circuit includes means for selecting said memory access request signal with preference over said refresh request signal upon concurrent occurrence of both said request signals by utilizing as said refresh operation indicating signal a logical product of the

output of said refresh operation indicating flip-flop and the inverted output of said memory access flip-flop.

4,293,927

POWER CONSUMPTION CONTROL SYSTEM FOR ELECTRONIC DIGITAL DATA PROCESSING DEVICES


Toshifumi Hoshii, Fussa, Japan, assignor to Casio Computer Co., Ltd., Tokyo, Japan

Filed Dec. 12, 1979, Ser. No. 102,768

Int. Cl. G06F 11/30; H03K 5/13

U.S. Cl. 364—900

9 Claims



1. A power consumption system for electronic digital data processing devices comprising: an oscillating circuit for producing a basis clock driving signal; a key input section having a plurality of key switches; counting means coupled to said key input section for updating and initiating a count operation every time any one of the key switches is operated; and control means coupled to said oscillating circuit to cause said oscillating circuit to stop oscillating and to thereby stop producing said basic clock driving signal when none of said key switches is operated before said count means completes counting for a given period of time after initiation of said count operation.

4,293,928

PERIPHERAL DEPENDENT CIRCUIT FOR PERIPHERAL CONTROLLER


Kenneth W. Baun, El Toro, Calif., assignor to Burroughs Corporation, Detroit, Mich.

Filed Dec. 14, 1979, Ser. No. 103,452

Int. Cl. G06F 3/04, 3/06

U.S. Cl. 364—900

10 Claims




1. A peripheral dependent circuit board, which when combined with a common control circuit card having a RAM buffer storage memory, forms a peripheral-controller operat-

ing to control data transfers between a host computer system and a peripheral terminal unit, said peripheral dependent circuit board comprising:

- (a) bi-directional data path means to said peripheral terminal unit;
- (b) address logic means for formulating addresses for the reading out and writing in of data in said RAM buffer storage memory;
- (c) multiplexor means for selecting a source of data that is to be transmitted to said RAM buffer storage memory;
- (d) error detection means for checking messages sent between said peripheral-controller and said host system and for checking messages between said peripheral controller and said peripheral terminal unit;
- (e) means to set a unique address to identify said peripheral-controller;
- (f) word-generation shift register means to provide control and information data to said peripheral terminal unit and/or said host computer system;
- (g) logic means for executing micro-code word operators received from said common control circuit card.

(said) signals produced by said dual strobing within a specified time period,



whereby the detection of said bubble signal twice indicates the presence of a bubble, and the failure to detect a bubble signal twice indicates the absence of a bubble signal.

4,293,931

MEMORY REFRESH CONTROL SYSTEM

Yoshikazu Tanaka, Kawasaki; Hitoshi Shirai, and Yoshiharu Kan'o, both of Yokohama, all of Japan, assignors to Fujitsu Limited, Kawasaki, Japan



Filed Mar. 28, 1980, Ser. No. 135,184

Claims priority, application Japan, Apr. 2, 1979, 54-39550

Int. Cl.³ G11C 7/00

U.S. Cl. 365-222

10 Claims



1. A memory refresh control system comprising: refresh control circuit means for generating refresh addresses respectively corresponding to combinations of n bits, and for producing in a limited period of time 2^n refresh clocks corresponding to said refresh addresses; means for dividing each of said refresh clocks into 2^N sub-intervals; and overhead bit generator means, supplied with said sub-intervals, for yielding successive N bit outputs respectively corresponding to all combinations of N bits, for each sub-interval; wherein the n bits available from said refresh control circuit means are conjoined with said N bit outputs generated by the overhead bit generator means, and are provided as a refresh address corresponding to the respective sub-interval.

4,293,929

MAGNETIC BUBBLE MEMORY DEVICES

Hirofumi Ohta, Mobara, Japan, assignor to Hitachi, Ltd., Tokyo, Japan


Filed Aug. 16, 1979, Ser. No. 67,121

Claims priority, application Japan, Aug. 23, 1978, 53-101774

Int. Cl.³ G11C 19/08

U.S. Cl. 365-2

6 Claims



1. In a magnetic bubble memory device comprising an insulating substrate, a magnetic bubble memory chip placed within a recess formed in the approximate center of said insulating substrate, and rotating magnetic field generating coils wound around the outer periphery of the insulating substrate so as to encircle the chip, said device operating under a bias magnetic field vertical to said magnetic bubble memory chip and a rotating magnetic field parallel to said chip, the improvement which comprises a plurality of rod-like members made of soft ferromagnetic material and placed in a second recess formed in said substrate to surround said chip, being on a plane substantially the same as the major surface of said chip.

4,293,930

BUBBLE DETECTION SYSTEM

Joseph Van Reymersdal, Fairless Hills, Pa., assignor to Sperry Corporation, New York, N.Y.

Filed Oct. 24, 1979, Ser. No. 87,911

Int. Cl.³ G11C 7/02, 19/08

U.S. Cl. 365-8

6 Claims

1. Apparatus for determining presence or absence of a magnetic bubble comprising:
 - (a) means for twice strobing a signal produced by said magnetic bubble;
 - (b) means coupled to said sensing means for twice detecting

4,293,932

REFRESH OPERATIONS FOR SEMICONDUCTOR MEMORY


Hugh P. McAdams, Houston, Tex., assignor to Texas Instruments Incorporated, Dallas, Tex.

Filed Feb. 11, 1980, Ser. No. 120,594

Int. Cl.³ G11C 7/00

U.S. Cl. 365-222

9 Claims



5. An electronic device comprising: an array of elements; means for accessing the array by a first address along with a first strobe signal and by a second address along with a second strobe signal, said means being activated by either said first strobe signal only or by both said first and second strobe signals; and clock generator means in said device for generating clock voltages for use with said second address and boosted in voltage by said first strobe signal.

4,293,933

WELL LOGGING APPARATUS AND METHOD: SYNTHETIC LOGS AND SYNTHETIC SEISMOGRAMS WITH EXTRAPOLATED REFLECTOR DIP FROM LOG MEASUREMENTS


Sung K. Park, Bethel, and William E. Kenyon, Ridgefield, both of Conn., assignors to Schlumberger Technology Corporation, New York, N.Y.

Filed Mar. 17, 1975, Ser. No. 558,832

Int. Cl.³ G01V 1/32, 1/40

U.S. Cl. 367-25

46 Claims



15. A method of exploring a subsurface earth formation comprising the steps of: providing log and dip signals derived from an investigating device passed through an actual borehole traversing the earth formation, and providing location signals defining the spatial relationship between said actual borehole and a virtual borehole spaced therefrom; and automatically combining said log, dip, and location signals in

automatic signal processing means to provide synthetic log signals characterizing the earth formation adjacent said virtual borehole.

36. A system for exploring a subsurface earth formation comprising:

means for providing log and dip signals derived from an investigating device passed through an actual borehole traversing the earth formation, and for providing location signals defining the spatial relationship between said actual borehole and a virtual borehole spaced therefrom; and automatic means for combining said log, dip, and location signals to provide synthetic log signals characterizing the earth formation adjacent said virtual borehole.

4,293,934

CIRCUMFERENTIAL ACOUSTIC DEVICE



Robert A. Herolz, Willis, and Charles B. Vogel, Houston, both of Tex., assignors to Shell Oil Company, Houston, Tex.

Filed Jun. 18, 1979, Ser. No. 49,753

Int. Cl.³ G01V 1/40

U.S. Cl. 367-27

21 Claims



1. An apparatus for obtaining a circumferential acoustic well log of a borehole comprising: an elongated logging tool adaptable for passing through the borehole; a plurality of transducers attached to said logging tool so as to define a path concentric with said borehole, at least two of said transducers functioning as transmitters, and at least two of said transducers functioning as receivers; wave generating means for generating electrical signals

which define measurement intervals, said wave-generating means including an alternating wave source for providing an alternating wave comprised of parts of a wave cycle and, a pulse source for providing one or more synchronizing pulses of short duration during each part of said wave cycle, each pulse being approximately equal in amplitude and duration;

means for transmitting both said alternating wave and said synchronizing pulses to said logging tool over a single conductor;

controlling means for selectively actuating said transmitters and receivers during said measurement intervals, said controlling means being synchronized by said electrical signals such that only one transmitter and one receiver, forming a transmitter-receiver pair, is operative during said measurement interval;

means responsive of said electrical signals for actuating a transmitter to provide a pulse of acoustic energy to be transmitted about an arcuate path between a transmitter and receiver of a transmitter-receiver pair, said path defining at least a portion of the circumference of said borehole, said pulse of acoustic energy generating a transient acoustic wave comprised of shear waves and compressional direct fluid waves and compressional guided fluid waves, one of said last-mentioned waves arriving at the receiver of said transmitter-receiver pair in one time period, the other wave arriving in a successive time period, both acoustic waves arriving at said receiver during a measurement interval;

latching means for preventing any other transmitter from becoming actuated during, or within a measurement interval immediately following, the actuation of said transmitter;

means for providing an electrical response indicative of variations in acoustic energy amplitude caused by said pulse of acoustic energy passing through the wall of said borehole and arriving at a receiver which is actuated during said measurement interval;

means for selectively processing said electrical response from either of said shear waves, said guided fluid waves, or parts or all of each, during each measurement interval, providing recorded signals; and,

means for displaying said recorded signals so as to provide an acoustical well log that can be used to detect the presence of vertical fractures or anomalies in the borehole wall.

4,293,935

METHOD OF SEISMIC EXPLORATION

Pierre Gros, Buc; Jean Millouet, La Celle Saint Cloud, and Philippe Staron, Mennecy, all of France, assignors to Societe Nationale Elf Aquitaine (Production), France

Filed Jun. 16, 1978, Ser. No. 916,352

Claims priority, application France, Jun. 30, 1977, 77 20098
Int. Cl.³ G01V 1/02, 1/28


U.S. Cl. 367-43

16 Claims

1. A method of improving the signal-to-noise ratio of a final seismogram in seismic exploration of a medium to be explored having different reflectors, said method comprising the steps of:

- determining a maximum frequency to be emitted in a frequency spectrum for the medium to be explored;
- determining a minimum frequency to be emitted in said frequency spectrum for the medium to be explored;
- emitting, in said medium from at least one emission source, vibrational acoustic signals of long time-duration, the frequencies of said emitted signals being within said frequency spectrum, said frequency spectrum divided into a number of separate, contiguous, non-overlapping bands, each band having a different bandwidth than immediately adjacent bands, each bandwidth a function of the ratio V_s/CV_B , where said number of bands is at least equal to

a whole number which is immediately below and closest to the value of the ratio



$$N = \left(\frac{F_{max}}{F_{min}} \right) \frac{CV_B}{V_s}$$

where

F_{max} is the highest frequency of said desired spectrum,

F_{min} is the lowest frequency of said desired spectrum,

C is a coefficient higher than 1 and dependent upon the cutoff of a wave-number filter,

V_B is the apparent velocity of sound within said medium, and

V_s is the lowest apparent velocity of waves refelected within said medium;

(d) receiving, in at least on receiver, the waves reflected by the different reflectors of said medium, said receiver defining with said source emission, said wave number filter;

(e) processing the received signals in order to determine the detected reflectors by: (1) forming the complex spectrum for each band of frequencies of the received signal corresponding to the emitted signal, (2) forming the complex spectrum for each band of frequencies corresponding to a reference of the emitted signal, (3) dividing the complex spectrum of the received signal by the complex spectrum of the reference of the emitted signal to obtain an elementary complex spectrum for each band of frequencies, and (4) setting the amplitude of at least one portion of the elementary complex spectrum to zero if that portion is external to the band; and

(f) producing a seismogram from said received processed signals in which, for each of said frequency bands, an improved signal-to-noise ratio is obtained, whereby said final seismogram has an improved signal-to-noise ratio.

4,293,936

TELEMETRY SYSTEM

William H. Cox, Groves, and Preston E. Chaney, Dallas, both of Tex., assignors to Sperry-Sun, Inc., Sugar Land, Tex.

Continuation-in-part of Ser. No. 755,620, Dec. 30, 1976, abandoned. This application Dec. 13, 1978, Ser. No. 968,879

Int. Cl.³ G01V 1/40

U.S. Cl. 367-82


33 Claims

1. A telemetry system for transmitting acoustical signals over a string of standard drill pipe positioned in a borehole and having pipe sections of approximately 31.3 feet including:

acoustical transmitting and receiving means occurring at first and second spaced locations on the string of pipe; and

means for operating said transmitting means at a frequency above 600 Hz and occurring within passbands having a

minute indication drum and provided on the outer periphery with hour-scale alarm signaling time graduations; at least first and second detection members provided in correspondence with the hour and minute time wheels respectively for detect-



frequency band width of 130 Hz and base frequencies which are 20 Hz above integral multiples of 283 Hz.

4,293,937

BOREHOLE ACOUSTIC TELEMETRY SYSTEM


H. Eugene Sharp, Missouri City; Octavio A. Vela, and Miles A. Smither, both of Houston, all of Tex., assignors to Sperry-Sun, Inc., Sugar Land, Tex.

Filed Aug. 10, 1979, Ser. No. 65,476

Int. Cl.³ G01V 1/40

U.S. Cl. 367-82

4 Claims



1. In an acoustic telemetry system including a first transmitter clocked by a first crystal controlled oscillator for transmitting an acoustic signal at a first frequency over an elongated column acting as an acoustic path in the borehole, such acoustic signal having a data component embedded in a noise background, circuit means forming a circuit path to receive, and retransmit said acoustic signal, which means comprises:

AGC means for amplifying the received acoustic signal; filter means for filtering noise from said received acoustic signals to provide a clean data component; feedback means for passing the signal to said AGC means for controlling the AGC gain; means for retransmitting the received signal at a frequency other than the first frequency; clock means having a second crystal controlled oscillator for operating said retransmitting means, said first and second crystal controlled oscillators being operated at substantially the same precise frequency.

4,293,938

ALARM SIGNALING TIME DETECTING DEVICE FOR DIGITAL CLOCK

Masuo Ogihara; Kozo Chimura; Nobuo Shinozaki, and Yoichi Seki, all of Yotsukaido, Japan, assignors to Seiko Koki Kabushiki Kaisha, Tokyo, Japan


Filed Dec. 27, 1979, Ser. No. 107,516

Claims priority, application Japan, Dec. 28, 1978, 53-163743
Int. Cl.³ G04B 23/02, 19/02; G04C 21/16

U.S. Cl. 368-72

10 Claims

1. In an alarm signaling time indicating device for a digital clock having an alarm device and hour and minute time wheels, said time indicating device comprising: an alarm signaling time setting member; a minute indication drum positionable by said alarm signaling time setting member and provided on the outer periphery with minute-scale alarm signaling time graduations; an hour indication drum intermittently fed by said



ing the alarm time; and a gear train coupling said first detection member to said minute indication drum to permit continuous setting of said first detection member by setting said minute indicating drum.

4,293,939

ELECTRONIC TIMEPIECE HAVING AN ALARM SYSTEM

Yasuhiko Nishikubo, Iruma, and Mitsuo Sekine, Tokorozawa, both of Japan, assignors to Citizen Watch Company Limited, Tokyo, Japan


Filed Jul. 5, 1978, Ser. No. 921,956

Claims priority, application Japan, Jul. 8, 1977, 52/81803; Jul. 25, 1977, 52/89117; Jul. 27, 1977, 52/89982

Int. Cl.³ G04B 23/02; G04C 21/16

U.S. Cl. 368-74

2 Claims



1. An electronic timepiece comprising, in combination: a source of standard frequency signal; drive circuit means responsive to said standard frequency signal for producing a drive signal; a motor driven by said drive signal; time indicating hands driven by said motor to indicate current time;

an alarm system including at least one external operating member, switch means coupled to said external operating member, alarm timekeeping circuit means responsive to said standard frequency signal for counting at least the hours of time, alarm time memory circuit means responsive to a signal generated by actuation of said external operating member for counting and storing at least the hours of alarm time, coincidence detection circuit means coupled to said alarm timekeeping circuit means and to said alarm time memory circuit means for generating a coincidence signal when the contents of said alarm timekeeping circuit means and of said alarm time memory circuit means become identical, alarm signal generation means responsive to said coincidence signal for generating an alarm signal, and gate circuit means coupled to said switch means and responsive to actuation of said external operating member for resetting said alarm timekeeping circuit means and said alarm time memory circuit means and for applying an input alarm time count into said alarm time memory circuit; and

drive input signal generation means coupled between said source of at least one standard frequency signal and said

drive circuit means and responsive to said standard frequency signal and a control signal from said gate circuit means for generating a first drive input signal applied to said drive circuit means when said electronic timepiece is in a normal timekeeping mode of operation and for generating a second drive input signal applied to said drive circuit means when said electronic timepiece is in an alarm time setting mode of operation, said first drive input signal and said second drive input signal having different waveforms.

4,293,940


TIME SOUND GENERATING DEVICE

Satoshi Noguchi, Fujisawa, and Takaya Kitao, Kamakura, both of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Filed Jun. 5, 1978, Ser. No. 912,535

Claims priority, application Japan, Jun. 16, 1977, 52-79568[U]; Aug. 25, 1977, 52-114362[U]; Aug. 26, 1977, 52-115041[U]

Int. Cl.³ G04B 21/02; G04C 23/00; G04B 23/02; G04C 21/16
U.S. Cl. 368—75 8 Claims



1. A time sound generating device comprising:
 - a time display element having a display portion for a 10-minute digit having seven display segments, one segment of said seven segments being at a high-level light on state during display of the numbers "0" to "4" and at a low-level light off state during display of the number "5";
 - a time signal generating device for dividing a reference frequency supplied from a reference frequency source and generating a time display driving signal from a resulting frequency-divided output signal to drive said time display element;
 - a first differentiation time constant circuit connected to said one segment for detecting a change of time by detecting a change in state of the display element driving signal applied to said one segment and for generating a pulse of a predetermined duration upon detection of said change in state;
 - a switch circuit which changes on-off states in response to said pulse;
 - a second time constant circuit responsive to said switch circuit changing to a particular on-off state for generating a gradually changing output signal;
 - an audio frequency signal generating circuit for generating an audio signal;
 - a gain control circuit having an input terminal receiving said audio signal and an output terminal, said gain control circuit changing the amplitude of the audio signal applied to said input terminal and producing the amplitude changed signal from said output terminal in response to the output signal of said second time constant circuit; and
 - loudspeaker means connected to receive the amplitude changed signal from said output terminal.

4,293,941
MEMORY ACCESS CONTROL SYSTEM IN VECTOR PROCESSING SYSTEM

Takatoshi Muraoka, Kyoto; Keiichi Uchida, Kawasaki; Minoru Koshino, Yokohama; Masanori Motegi, Kawasaki, and Shigeru Nagasawa, Yokohama, all of Japan, assignors to Fujitsu Limited, Kawasaki, Japan


Continuation of Ser. No. 624,915, Oct. 22, 1975, abandoned.

This application May 21, 1979, Ser. No. 40,994

Claims priority, application Japan, Oct. 25, 1974, 49-122438
Int. Cl.³ G06F 13/00

U.S. Cl. 364—200

2 Claims



1. A memory access control system for a memory unit in a data processing system for reading out element data from the memory unit and providing sequential data processing, especially for vector processing, said memory access control system comprising:
 - address holding register means for holding addresses which indicate where the element data is stored when an element address is set in said address holding register means;
 - memory means for storing sequence data indicating the sequence of an element data stored in the memory unit;
 - shift register means connected to the memory means at least for storing the contents of the memory means corresponding to the address which is in use for accessing to said memory unit in accordance with a selected content of said address holding register means, said shift register means having outputs; and
 - data buffer register means connected to said memory unit and controlled by the outputs of said shift register means whereby the element data read out from said memory unit is stored at a location of said data buffer register means by means of the outputs of said shift register means.

4,293,942

WATERPROOF WATCH AND METHOD FOR MAKING

Hans Baumgartner, Niederrohrdorf, Switzerland, assignor to BBC Brown, Boveri & Company, Limited, Baden, Switzerland


Filed Nov. 29, 1979, Ser. No. 98,684

Claims priority, application Switzerland, Dec. 15, 1978, 12782/78

Int. Cl.³ G04B 37/00; B23P 13/00, 11/02

U.S. Cl. 368—280

10 Claims



1. A watch comprising:

an encasement; and
a base adapted for detachable water tight sealing connection to said encasement, wherein said base is comprised of a reversible memory form alloy.

4,293,943

WATCH STAND


Victor S. Avery, c/o George Spector, 3615 Woolworth Bldg., and George Spector, 3615 Woolworth Bldg., both of New York, N.Y. 10007

Filed Jun. 15, 1979, Ser. No. 48,718

Int. Cl.³ G04B 37/00; A47F 7/00

U.S. Cl. 368—316

4 Claims



1. A watch stand, for supporting a wrist watch in a utility position on a table comprising a triangular shaped base having an encompassing outer surface between parallel triangular side surfaces in combination with a pad mounted on said outer surface said pad being slidable inwardly and outwardly of said surfaces to provide an adjustable outer support platform for said watch body said outer surface being adapted to support the wrist watch band including peripheral extensions beyond said outer surface to form a channel thereabout for the wrist-band.

4,293,944

INFORMATION PLAY-BACK APPARATUS WITH ASTIGMATIC AUTO-FOCUSING

Morishi Izumita, Hachioji; Takeshi Maeda, Kokubunji, both of Japan; Yoshito Tsunoda, Stanford, Conn., and Susumu Sawano, Tachikawa, Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed Jun. 27, 1977, Ser. No. 810,166

Claims priority, application Japan, Jun. 25, 1976, 51-74353; Aug. 9, 1976, 51-94000

Int. Cl.³ G11B 7/12, 17/00

U.S. Cl. 369—45

11 Claims



1. An information play-back apparatus comprising a laser source, a recording medium on which information is recorded in the form of a track, first optical means for projecting a laser beam from said laser source onto the information track on said recording medium, detection means for detecting a reflected laser beam from the information track as an electric signal, second optical means for guiding the reflected laser beam to said detection means through an optical element having a unidirectional lens action, and control means for processing outputs of said detection means to control the operation of said first optical means, said information play-back apparatus characterized in that said optical element is arranged with its opti-

cal axis defining an angle of about 45 degrees with respect to a direction of the information track, and that said detection means has at least four light receiving portions divided symmetrically about two axes such that at least one light receiving portion is in each of the four quadrants formed by the two axes, wherein one of the axes for the division is arranged in parallel with the direction of the information track.

11. Apparatus for reading a radiation-reflecting record carrier on which information is stored in an optically readable information structure arranged in tracks, comprising radiation source means for providing a read beam of radiation, radiation-sensitive detection system means for converting modulated radiation reflected from said record carrier into an electrical signal, an objective system means for focussing the read beam on an area of the record carrier and for passing the read beam reflected from the record carrier to said radiation-sensitive detection system means, said tracks being oriented in a particular direction in the area of the record carrier on which the read beam is focussed, astigmatic element means in the path of the radiation reflected from the record carrier for imparting astigmatism to said reflected radiation beam, and an array of four sub-detectors disposed in four different quadrants of an imaginary X-Y coordinate system, the X and Y axes being disposed at an angle of 45° with astigmatic focal lines of the astigmatic element means, one of the axes of the coordinate system in whose quadrants the sub-detectors are disposed being parallel to the effective track direction, the astigmatic focal lines being disposed at an angle of 45° to the effective track direction.

4,293,945

MULTICHANNEL CORRELATION RECEIVER FOR DETERMINING DEPOLARIZATION OF SIGNALS ALONG SIGNAL PROPAGATION PATHS


Ali E. E. Atia, Gaithersburg; Arnold L. Berman, Kensington, both of Md., and Christoph Mahle, Washington, D.C., assignors to Communications Satellite Corporation, Washington, D.C.

Filed Aug. 29, 1979, Ser. No. 70,554

Int. Cl.³ H04B 7/10; H04J 11/00

U.S. Cl. 370—17

10 Claims



1. A multichannel correlation receiver comprising:
 - (a) means for receiving a first signal having a first polarization;
 - (b) means for receiving a second signal having a second polarization orthogonal to said first polarization, said second signal being produced by depolarization of said first signal along a first propagation path;
 - (c) local oscillator means;
 - (d) first and second mixers for converting said first and second signals to first and second IF signals under the control of said local oscillator;
 - (e) phase locked means for providing a relatively noise-free replica of said first IF signal;
 - (f) means for correlating said first IF signal replica with a

signal related to said second IF signal to produce a correlated signal; and
(g) means for providing the levels of said first IF signal and said correlated signal to thereby indicate the amount of said depolarization of said first signal along said first propagation path.

4,293,946


TRILATERAL DUPLEX PATH CONFERENCING SYSTEM WITH BROADCAST CAPABILITY

Michael L. Kuras, Stratford; Daniel C. Upp, Easton, and Herbert J. Toegel, Fairfield, all of Conn., assignors to International Telephone and Telegraph Corporation, New York, N.Y.
Filed Nov. 21, 1979, Ser. No. 96,599

Int. Cl.³ H04M 3/56

U.S. Cl. 370—62

14 Claims



10. A digital telecommunication system for providing a plurality of conferencing functions simultaneously between a plurality of terminals having frames of digitally encoded data in a plurality of channels originating at one or more sources coupled thereto, comprising:

- a plurality of terminal port means for receiving frames of said digitally encoded data from a plurality of terminals;
- means for providing a plurality of duplex paths over a plurality of time division multiplex bus means between said terminal ports to be interconnected thru a digital switching network;
- memory means coupled to said bus means for selectively storing frames of data coupled to said bus means from one or more of said plurality of terminal port means;
- means at each terminal port for coupling said frames of digitally encoded data of each channel into said memory means coupled to said bus means, said bus means being coupled to a plurality of terminal ports;
- means for recalling said frames of digitally encoded data from said memory means such that the contents of a plurality of said memory locations are combined to form a sum; and
- means for transmitting a signal representative of said sum over said established communication path.

4,293,947

INFORMATION HANDLING SYSTEM

William J. Brittain, Westcliff-On-Sea, England, assignor to Ford Motor Company, Dearborn, Mich.

Filed Oct. 10, 1978, Ser. No. 950,095

Claims priority, application United Kingdom, Oct. 12, 1977, 42402/77; Oct. 12, 1977, 42403/77; Oct. 12, 1977, 42404/77


Int. Cl.³ H04J 6/00

U.S. Cl. 370—89

1 Claim

1. An improved information handling system of the type which comprises a signal bus, a master station arranged to transmit on the signal bus pulse signals divided into serial information frames, a plurality of sensors or controlled devices, a plurality of peripheral stations, having address decoding circuitry, each connected to the signal bus for actuation in response to a given information frame, and a connector connecting each of the peripheral stations to at least one of the sensors or controlled devices, wherein the improvement comprises:

an address setting means in the connector, the address setting means setting a code determining the information frame to which the peripheral station associated with the connector responds, the connector comprising a housing



through which the signal bus passes to facilitate electrical connection thereto, the connector further including a printed circuit having conductive strips located within the connector housing, the conductive strips being drilled or punched to set the code for the peripheral station, and the connector housing having contacts cooperating with the conductive strips and address decoding circuitry of the peripheral station.

4,293,948

DATA TRANSMISSION SYSTEM

Olof Soderblom, Kragensavagen 21, 181 62 Lidings, Sweden
Continuation of Ser. No. 391,717, Aug. 27, 1973, abandoned,


which is a continuation of Ser. No. 773,056, Nov. 4, 1968, abandoned. This application Oct. 29, 1974, Ser. No. 518,450

Claims priority, application Sweden, Nov. 23, 1967, 16077/67; May 15, 1968, 6589/68

Int. Cl.³ H04J 3/16

U.S. Cl. 370—90

22 Claims



1. Apparatus for the transmission of data characters in pulse form from a plurality of terminal units to a master unit comprising in combination:

- pulse input and pulse output means for each said terminal unit and for said master unit,
- a single series loop connecting said terminal units in series along said loop between the pulse output means and pulse input means of said master unit and over which pulses originating either with said master unit or any terminal unit are transmitted always in the same predetermined direction,
- each said terminal unit including:
 - (a) pulse responsive means connected to said pulse input means for receiving pulses appearing at said pulse input means,
 - (b) decoding means distinctively responsive to pulses received by said pulse responsive means,

- (c) and logic means responsive to said decoding means for normally interconnecting said pulse input and pulse output means to thereby complete the loop at said terminal unit,
- (d) said logic means in response to a distinctive pattern of said pulses appearing at the associated pulse input means interrupting the loop between said pulse input and pulse output means only at a terminal unit having data to transmit and enabling the application to the associated pulse output means of stored data of arbitrary variable length as required by said terminal unit for transmission over the loop to said master unit,
- (e) said logic means being effective upon the opening of said loop at the first upstream terminal unit having data to send for inhibiting the receipt at any downstream terminal unit of pulses otherwise effective to control said downstream terminal unit to transmit data.

4,293,950

TEST PATTERN GENERATING APPARATUS

Masao Shimizu; Takashi Tokuno, both of Gyoda; Kohji Ishikawa, Funabashi; Naoki Narumi, Tokyo, and Osamu Ohguchi, Sayama, all of Japan, assignors to Nippon Telegraph and Telephone Public Corporation and Takeda Riken Kogyo Kabushikikaisha, both of Tokyo, Japan


Filed Apr. 2, 1979, Ser. No. 26,246

Claims priority, application Japan, Apr. 3, 1978, 53-038949; Apr. 3, 1978, 53-038950; Apr. 3, 1978, 53-038951; Apr. 3, 1978, 53-038952; May 18, 1978, 53-059381; May 18, 1978, 53-059382; May 18, 1978, 53-059383; Oct. 13, 1978, 53-126523; Oct. 30, 1978, 53-133936

Int. Cl.³ G06F 11/00; G01R 31/28

U.S. Cl. 371—21

21 Claims



1. A test pattern generating apparatus comprising:

- a program control section comprising an instruction memory into which is loaded a microprogram for determining a test pattern to be generated by the test pattern generating apparatus, means for reading the loaded microprogram, for interpretation and execution, and for outputting an address pattern generate instruction, a data pattern generate instruction, a memory control instruction and a status information select instruction, and means for receiving status information to control the order of the execution of the microprogram;

an address pattern generation section connected to the program control section and comprising means for receiving therefrom the address pattern generate instruction and means for performing an arithmetic operation in response thereto for generating an address pattern;

a memory control signal generation section connected to the program control section and comprising means for receiving therefrom the memory control instruction and means for generating memory control signals responsive thereto;

a status information generation section connected to the program control section and comprising means for receiving therefrom the status information select instruction and for receiving from selected components of said generating apparatus a plurality of data including at least the address pattern from the address pattern generation section, said status information comprising said address pattern data in a form derived from said microprogram, and said status information generation section comprising means for comparing the two sets of address pattern data to provide the result of comparison as the status information to the program control section in response to the status information select information; and

a data pattern generation section connected to the program control section and the address pattern generation section and comprising

an arithmetic operation part which is supplied with the data pattern generate instruction, said arithmetic operation part comprising means for performing an arithmetic operation in response to the data pattern generate instruction for generating a data pattern,

4,293,949

CLOCK INVARIANT SYNCHRONIZATION FOR RANDOM BINARY SEQUENCES


Constantinos Philippides, Columbia, Md., assignor to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Oct. 30, 1979, Ser. No. 89,672

Int. Cl.³ G06F 11/00; H03K 13/34

U.S. Cl. 371—6

14 Claims



1. Apparatus for clocking digital marks and spaces of equal period into a data register and for deriving the data register clock directly from the digital mark and space data itself, comprising:

- means for periodically sampling the digital mark and space data a plurality (p) of times for each mark and space and for providing a digital signal corresponding to each sample, and
- means for gating the digital signals of selected samples and for generating pulses when the digital signals of the selected samples are in a desired logic configuration which indicates the presence of either a valid mark or a valid space.

an area inversion control signal generator comprising means for receiving the address pattern from the address pattern generation section and means for generating an inversion control signal selectively indicating inversion of the data pattern in accordance with the address pattern, and

an inverter connected to the output of the area inversion control signal generator and of the arithmetic operation part to selectively invert the data pattern from the arithmetic operation part dependent upon the inversion control signal to provide output data corresponding to the test pattern of said generating apparatus.

4,293,951


METHOD AND APPARATUS FOR ENCODING/DECODING A CONVOLUTIONAL CODE TO A PERIODIC CONVOLUTIONAL CODE BLOCK
Smith A. Rhodes, Chantilly, Va., assignor to Communications Satellite Corporation, Washington, D.C.

Filed Mar. 16, 1979, Ser. No. 21,296

Int. Cl.³ G06F 11/10

U.S. Cl. 371-43

15 Claims



1. In a method of encoding a bit stream of B_1 information symbols in a convolutional encoder of the type in which said bits are serially fed through a K_1 stage shift register and in which r parity symbols are generated for every k information symbols to achieve a code rate of $\rho = k/n$ defined as the ratio of the number of information symbols k to the total number of symbols n in the code, where $n = k + r$, the improvement comprising feeding back the output of said encoder shift register with a delay $D_1 = B_1 - K_1$ to the input of said shift register by re-introducing the first $K_1 - 1$ information symbols into the encoder shift register.

4,293,952

SAMPLING FUNCTION TYPE EQUALIZER
Michitoshi Tamori, Tokyo, and Kazuo Kawai, Yokohama, both of Japan, assignors to Kokusai Denshin Denwa Co., Ltd., Tokyo, Japan

Filed Jul. 27, 1979, Ser. No. 61,398

Claims priority, application Japan, Jul. 27, 1978, 53-90988


Int. Cl.³ H04B 3/04; H03H 21/00; G06F 15/34

U.S. Cl. 375-14

3 Claims

1. A sampling function type equalizer having a transversal filter with a plurality of automatically adjusted potentiometers, said equalizer comprising means for converting the amplitude-frequency characteristic and the delay-frequency characteristic to a sampling function type characteristic with the peak value $A_p(n)$ and $\tau_p(n)$, wherein the desired amplitude-frequency characteristic and the delay-frequency characteristic are obtained by superimposing the sampling function type characteristics, first and second multiplying means for multiplying each input $A_p(n)$ and $\tau_p(n)$ by the output of a predetermined discrete function generator, a first convolution integrator means for performing convolution integration on the output of said first multiplying means for obtaining the amplitude equalization characteristic, Bessel function generator means for providing a Bessel function in response to the output of said second multiplying means, a second convolution integrator

means for performing convolution integration on the output of said Bessel function generator means, and means for adjusting



the tap weight of said potentiometers as a function of the outputs of said first and second convolution integrator means.

4,293,953


BI-ORTHOGONAL PCM COMMUNICATIONS SYSTEM EMPLOYING MULTIPLEXED NOISE CODES
Frank S. Gutleber, Little Silver, N.J., assignor to The United States of America as represented by the Secretary of the Army, Washington, D.C.

Filed Dec. 28, 1979, Ser. No. 108,195

Int. Cl.³ H03K 13/01; H04J 1/04

U.S. Cl. 375-25

9 Claims



1. In a pulse code modulation communications system operative in conjunction with a timing reference signal, the combination therewith of:

first means for generating a first pair of coded pulse signals for transmission during a predetermined period;

second means for generating a time related second pair of coded pulse signals for transmission during said predetermined period;

delay means for delaying each of said coded pulse signals of each said pair to occur during respective different intervals of time during said predetermined period;

means coupling said pairs of coded pulse signals directly to respective said delay means;

inverter means for inverting said pairs of coded pulse signals and coupling the inverted signals to respective said delay means;

a source of message signals;

means for multiplexing said message signals with said first and second pairs of delayed coded pulse signals into two channels for transmission to users accessing said system at predetermined intervals of time; and

means for receiving and detecting said coded pulse signals to produce an output signal having an impulse correlation function during an assigned predetermined interval of time within said predetermined period, said receiving and detecting means including demultiplexing means separat-

ing the transmitted signals into two channels, matched filter detector means for detecting predetermined pairs of coded pulse signals from each said channel, adder means connected to said filter detector means of each channel for combining said coded pulse signals from each of said pairs of signals from each of said channels, and amplitude detector means for detecting the maximum amplitude signal from said adder means of each channel and pairs of signals to provide said output signal.

4,293,954

RECEIVING SYSTEM FOR TRANSMITTING INFORMATION TRANSMITTED BY A MOBILE TRANSMITTER TO A CENTRAL STATION
Jean-Pierre Vilatte, Villebon, France, assignor to U.S. Philips Corporation, New York, N.Y.


Filed Jan. 10, 1979, Ser. No. 2,271

Claims priority, application France, Jan. 13, 1978, 78 00894

Int. Cl.³ H04B 7/26

U.S. Cl. 455-54

8 Claims



8. In a receiving system for transmitting information from a mobile station to a fixed central station via one sub-station out of a plurality of sub-stations connected to the central station by means of a transmission line wherein each sub-station comprises, a radio receiving circuit having an output coupled to the transmission line, a device for measuring the quality of a received signal and having an output connected to a first input terminal of a delayed-signal generator, said delayed-signal generator having a second input terminal and an output terminal, a frequency generator, means including said frequency generator for coupling the output terminal of the delayed-signal generator to the transmission line for applying a rest condition signal to the other sub-stations, means coupling the second input terminal of the delayed-signal generator to the transmission line via a frequency detection device for applying a rest condition signal, generated by one of the other sub-stations, to said one substation, and means further connecting the output terminal of the delayed-signal generator to an input of the receiving circuit for applying a signal thereto for releasing the receiving circuit.

4,293,955

DIVERSITY RECEPTION SYSTEM
Marvin M. Gehr, and Howell D. Pabian, both of Lincoln, Nebr., assignors to Telex Communications, Inc., Minneapolis, Minn.

Filed Mar. 17, 1980, Ser. No. 131,029

Int. Cl.³ H04B 1/16, 7/08


U.S. Cl. 455-276

25 Claims

1. A method of processing signals transmitted over multipath routes on a carrier frequency comprising the steps of: receiving said signals through at least two antennas; adding the signals received on said antennas; selecting one of a first mode for adding the signals received on said antennas in which there is a first phase shift in the

signals from a first of said antennas and a second mode in which there is a second phase shift more than 90° of the carrier frequency difference from said first phase shift of said signal received from said one of said antennas before said signals are added;

the step of selecting further including the steps of comparing the amplitude of the sum of the added signals to a predetermined threshold value; determining which of said first and second modes provides the highest amplitude signal and switching to the mode which provides the highest amplitude signal;



said step of determining comprising the steps of switching from one of said modes to the other mode when said amplitude is lower than said predetermined threshold value; and comparing the amplitude of the sum of the added signals after switching to said other mode with the sum before switching; and

the step of switching to the mode that provides the highest amplitude signal including the step of returning to the one of said first and second modes if the strength of said sum of the signals is below that amplitude at the time of switching between one and other of said first and second modes.

4,293,956


DOUBLE-BALANCED MIXER
John E. Altstadt, Palo Alto, Calif., assignor to California Microwave, Inc., Sunnyvale, Calif.

Filed Nov. 23, 1979, Ser. No. 96,845

Int. Cl.³ H04B 1/26; H03H 7/42

U.S. Cl. 455-327

6 Claims



3. In a double-balanced mixer device including first conductive means disposed upon surfaces of a dielectric substrate and forming a first balun for receiving an input LO signal, second conductive means likewise disposed upon surfaces of said substrate and forming a second balun for receiving an input RF signal, diode means coupling said first balun to said second balun, and output means coupled to said first balun and said second balun to form an output port for IF signals, and improved second balun and output means comprising:

a first body of conductive material having first and second portions disposed on one side of said substrate, said second portion being elongated and narrow relative to said first

portion and having a length equal to one quarter of the wavelength of said IF signal; and
a second body of conductive material having third and fourth portions disposed on an opposite side of said substrate in overlying relationship to said first and second portions, said fourth portion being elongated and narrow

relative to said third portion and having a length equal to one quarter of the wavelength of said IF signal, the distal ends of said second and fourth portions being connected together to form a terminal of said output port.

DESIGN PATENTS

GRANTED OCT. 6, 1981

ERRATA



For	See
CLASS	PATENT NO.
D34-024	261,125
D34-034	261,126
D34-034	261,127
D34-045	261,193
D34-046	261,194

DESIGNS

OCTOBER 6, 1981

261,070
FIELD AND WINTER SPORTS JACKET
 Robert E. Pettibone, 1925 Sunset Ave. SW., Seattle, Wash. 98116
 Filed Jan. 15, 1980, Ser. No. 112,356
 Term of patent 14 years
 Int. Cl. D2—02
 U.S. Cl. D2—185


261,072
PLEATED NURSE CAP
 Pamela Barich, 690 NE. 160th Ter., North Miami Beach, Fla. 33162
 Filed Dec. 29, 1978, Ser. No. 974,323
 Term of patent 14 years
 Int. Cl. D02—03
 U.S. Cl. D2—230



261,071
JACKET
 Pierluigi Rolando, Viculungo, Italy, assignor to Maglificio Biellese Fratelli S.p.A., Italy
 Filed Mar. 28, 1978, Ser. No. 891,165
 Claims priority, application Italy, Nov. 15, 1977, 22721 A/77
 Term of patent 14 years
 Int. Cl. D2—02
 U.S. Cl. D2—187



261,073
COMBINED FIREMAN'S HOOD AND FACE MASK
 Mark C. Spruill, 503 Windsor Ave., Goleta, Calif. 93017; Michael D. Hipes, 3839 Sunset Rd., Santa Barbara, Calif. 93110; Carl J. Durtche, 4546 El Carro, Carpinteria, Calif. 93013, and Keith D. Cullom, 164 Lancaster Pl., Goleta, Calif. 93017
 Filed Feb. 5, 1979, Ser. No. 9,748
 Term of patent 14 years
 Int. Cl. D02—03
 U.S. Cl. D2—232



261,074

VISOR FOR ATTACHMENT TO HELMET OR THE LIKE

Jan L. Grönberg, Fullerstavigen 42, S-141 44 Huddinge, Sweden



Filed Feb. 5, 1979, Ser. No. 9,503

Claims priority, application Sweden, Aug. 7, 1978, 781815

Term of patent 7 years

Int. Cl. D02—03

U.S. Cl. D2—233



261,076

TOTE BAG

Maxwell B. Chernoff, Midlothian, Va., assignor to Dart Industries Inc., Los Angeles, Calif.

Filed Oct. 9, 1979, Ser. No. 82,827

Term of patent 14 years

Int. Cl. D3—01

U.S. Cl. D3—42



261,077

NECKWEAR PURSE

Judith J. Loomis, 232 Lafayette St., Memphis, Tenn. 38111

Filed Jun. 1, 1979, Ser. No. 44,705

Term of patent 14 years

Int. Cl. D3—01

U.S. Cl. D3—52



261,075

MONEY POUCH

Michael Dolas, 1164 Crestline Dr., Santa Barbara, Calif. 93105

Filed Apr. 13, 1978, Ser. No. 896,191

Term of patent 14 years

Int. Cl. D3—01

U.S. Cl. D3—41



261,078

BAR STOOL


Robert L. Wilson, Memphis, Tenn., assignor to Chromcraft Corporation, Amsterdam, N.Y.

Filed Oct. 11, 1979, Ser. No. 84,007

Term of patent 14 years

Int. Cl. D6—01

U.S. Cl. D6—35



261,080

CHAIR


Robert L. Wilson, Memphis, Tenn., assignor to Chromcraft Corporation, Amsterdam, N.Y.

Filed Oct. 11, 1979, Ser. No. 83,919

Term of patent 14 years

Int. Cl. D6—01

U.S. Cl. D6—70



261,081

SOAP-DISH


Anita Nagel, 3 Anchorage La., Oyster Bay, N.Y. 11771

Filed Jun. 22, 1979, Ser. No. 50,862

Term of patent 14 years

Int. Cl. D23—02

U.S. Cl. D6—89



261,082

DISPLAY STAND


Var E. Lordahl, Chicago, Ill., assignor to T.S.G. Mfg. Co., Chicago, Ill.

Filed May 23, 1979, Ser. No. 41,690

Term of patent 14 years

Int. Cl. D20—02

U.S. Cl. D6—114



261,079

SEAT


Samuel T. Collins, Bassett, Va., assignor to Trend Line Furniture Corporation, Amsterdam, N.Y.

Filed Oct. 5, 1979, Ser. No. 82,393

Term of patent 14 years

Int. Cl. D6—01

U.S. Cl. D6—63



261,083

COMPUTER TERMINAL DESK


Theodore L. Bogert, and Frances P. Bogert, both of 300 Thalia Dr., Orlando, Fla. 32807

Filed Jan. 21, 1980, Ser. No. 114,129

Term of patent 14 years

Int. Cl. D06—04

U.S. Cl. D6—161



261,086

TUMBLER


Edgar F. Trombly, Grosse Pointe Farms, Mich., assignor to Dart Industries Inc., Los Angeles, Calif.

Filed Apr. 13, 1979, Ser. No. 29,609

Term of patent 14 years

Int. Cl. D07—01

U.S. Cl. D7—15



261,084

PORTABLE BACK REST

Janet Scott, 18502 Haas Ave., Torrance, Calif. 90504

Filed May 29, 1979, Ser. No. 43,354

Term of patent 14 years

Int. Cl. D6—99

U.S. Cl. D6—200



261,085

DRINKING CUP

Frank Ventura, 9932 Lindo Lake Pl., Lakeside, Calif. 92040

Filed Feb. 2, 1979, Ser. No. 8,922

Term of patent 3½ years

Int. Cl. D07—01

U.S. Cl. D7—6



261,087

KETTLE


Kenichi Myodo, Tsubame, Japan, assignor to Shinko Kinzoku Kabushiki Kaisha, Japan

Filed Oct. 24, 1979, Ser. No. 87,749

Term of patent 7 years

Int. Cl. D07—02

U.S. Cl. D7—66



261,088

VACUUM VESSEL FOR COMESTIBLES OR THE LIKE


Boris M. Akimov, ulitsa Dzerzhinskogo, 81/85, kv. 16; Viktor I. Morozov, ulitsa Zernovaya, 6/6, kv. 90; Vitaly I. Shalaev, ulitsa Bairona, 161-G, kv. 32; Viktor V. Telegin, prospekt Gagarina, 175-A, kv. 61; Alexandr M. Vasiltsov, ulitsa Chernoglazovskaya, 12, kv. 24; Georgy S. Tsoglin, ulitsa Geroev Truda, 38, kv. 68, and Vladimir I. Vasiliev, ulitsa Bljukhera, 26, kv. 172, all of Kharkov, U.S.S.R.

Filed Nov. 3, 1977, Ser. No. 848,367

Term of patent 14 years

Int. Cl. D7—02

U.S. Cl. D7—77



261,090

PAN INSERT


Melodee A. Kapolas, 2 S. 041 Sheffield Rd., Glen Ellyn, Ill. 60137

Filed Jun. 8, 1979, Ser. No. 46,654

Term of patent 14 years

Int. Cl. D07—99

U.S. Cl. D7—102



261,091

SHELL-FISH UTENSIL

Weldon W. Stiggers, 2730 NE. 16th, Oklahoma City, Okla. 73117

Filed Oct. 1, 1979, Ser. No. 80,990

Term of patent 14 years

Int. Cl. D07—04

U.S. Cl. D7—106



261,089

TENDERIZER


Jessop I. McDonnell, P.O. Box 156, Seaview, Wash. 98644, and Rodney Maxwell-Muir, Box 124, Chinook, Wash. 98614

Filed Jul. 9, 1979, Ser. No. 55,340

Term of patent 14 years

Int. Cl. D07—04

U.S. Cl. D7—101



261,092

ROTATING MULTIPLE SKEWER ASSEMBLY

Gerald J. Menard, 1116 Juniper Ct., Fort Collins, Colo. 80521

Filed Aug. 7, 1979, Ser. No. 64,567

Term of patent 14 years

Int. Cl. D7—02

U.S. Cl. D7—129



261,093

EATING UTENSIL


William J. Segal, 13010 Debby St., Van Nuys, Calif. 91401

Filed Mar. 5, 1979, Ser. No. 17,088

Term of patent 14 years

Int. Cl. D07-03

U.S. Cl. D7-151



261,095

ALL PURPOSE BEATER

Ng-Fai A. Tsang, Kowloon, Hong Kong, assignor to Man-mouhong Manufacturing Co., Kowloon, Hong Kong


Filed Dec. 26, 1978, Ser. No. 973,655

Claims priority, application United Kingdom, Dec. 5, 1978, 987538/78

Term of patent 14 years

Int. Cl. D07-04

U.S. Cl. D7-157



261,096

HAND TOOL

Christian Petersen, DeWitt, Nebr., assignor to Petersen Manufacturing Co., Inc., DeWitt, Nebr.

Filed Sep. 18, 1978, Ser. No. 943,180

Term of patent 14 years

Int. Cl. D8-05

U.S. Cl. D8-22



261,094

CASING FOR FOOD GRINDER


Ralph E. Reiner, 6474 Chestnut La., Orchard Park, N.Y. 14127

Filed Nov. 4, 1977, Ser. No. 848,454

Term of patent 14 years

Int. Cl. D7-04; D15-08

U.S. Cl. D7-155



261,097

PNEUMATIC NUT RUNNER WITH TORQUE INDICATOR

William K. Wallace, Barneveld, and David A. Giardino, Deerfield, both of N.Y., assignors to Chicago Pneumatic Tool Company, New York, N.Y.

Filed Jun. 25, 1979, Ser. No. 51,497

Term of patent 14 years

Int. Cl. D8-04

U.S. Cl. D8-61



261,098

FENCE POST SETTING CHUCK

Benny J. Hendon, 327 N. McKinley St., and Julius Malinowski, Jr., 4514 Middleton Dr., both of Joplin, Mo. 64801

Filed Nov. 9, 1978, Ser. No. 959,439

Term of patent 14 years

Int. Cl. D8-05, 99

U.S. Cl. D8-70



261,101

FLOOR OUTLET HOUSING


Thomas J. Sotolongo, Clearwater Beach, Fla., assignor to AMP Incorporated, Harrisburg, Pa.

Filed Jul. 26, 1979, Ser. No. 61,102

Term of patent 14 years

Int. Cl. D8-09; D13-03

U.S. Cl. D8-353



261,099

DOOR CLOSER


Richard H. Russell, Farmington, Conn., assignor to Emhart Industries, Inc., Farmington, Conn.

Filed May 16, 1979, Ser. No. 39,695

Term of patent 14 years

Int. Cl. D8-07

U.S. Cl. D8-330



261,102

CHOKER LINE COUPLER


Charles J. Hoover, P.O. Box 713, Mill City, Oreg. 97360

Filed Jun. 11, 1979, Ser. No. 47,788

Term of patent 14 years

Int. Cl. D8-07

U.S. Cl. D8-383



261,103

COMBINED FLUIDS CONTAINER AND APPLICATOR

Lowell T. Fears, 2716 Echo St., The Woodlands, Tex. 77380

Filed Apr. 3, 1978, Ser. No. 893,125

Term of patent 14 years

Int. Cl. D9-01

U.S. Cl. D9-300



261,100

LATCH


Robert S. Wallace, Los Angeles, Calif., assignor to Dan F. Wallace, Karlua-Kona, Hi.

Filed Jun. 28, 1979, Ser. No. 53,085

Term of patent 14 years

Int. Cl. D08-07

U.S. Cl. D8-336



261,104
BOTTLE

Robert A. Cohen Skalli, 72, Rte. Montpellier, Sete, France (34204)

Filed Mar. 19, 1979, Ser. No. 22,077
Claims priority, application France, Oct. 24, 1978, 78 053
Term of patent 14 years
Int. Cl. D9—01


U.S. Cl. D9—329

261,105
DISPENSING CONTAINER

Ira Schwartz, New York, N.Y., assignor to Revlon, Inc., New York, N.Y.

Filed Feb. 14, 1979, Ser. No. 11,792
Term of patent 14 years
Int. Cl. D9—01


U.S. Cl. D9—353

261,106
BOTTLE

David A. Winchell, Twin Lakes, Wis., and William M. Evans, Mundelein, Ill., assignors to Baxter Travenol Laboratories, Inc., Deerfield, Ill.

Filed Apr. 24, 1978, Ser. No. 899,381
Term of patent 7 years
Int. Cl. D9—01

U.S. Cl. D9—369

261,107
COMBINED BOTTLE AND CAP

Ned Harris, New City, N.Y., assignor to Charles of the Ritz Group Ltd., New York, N.Y.

Filed Oct. 12, 1979, Ser. No. 84,224
Term of patent 14 years
Int. Cl. D9—01

U.S. Cl. D9—370

261,108
COMBINED BOTTLE AND CAP

Ned Harris, New City, N.Y., assignor to Charles of the Ritz Group Ltd., New York, N.Y.

Filed Oct. 12, 1979, Ser. No. 84,225
Term of patent 14 years
Int. Cl. D9—01


U.S. Cl. D9—370

261,109
BOTTLE

Aaron A. Rosenblatt, New York; Walter J. Mann, Little Neck, and James C. Adkins, Chappaqua, all of N.Y., assignors to QED, Chappaqua, N.Y.

Filed Aug. 24, 1979, Ser. No. 69,604
Term of patent 14 years
Int. Cl. D9—01


U.S. Cl. D9—384

261,110
PILLBOX

Noboru Yoshimoto, Kyoto, Japan, assignor to Morishita Jintan Co., Ltd., Osaka, Japan

Filed Apr. 2, 1979, Ser. No. 26,218
Term of patent 14 years
Int. Cl. D9—03

U.S. Cl. D9—432

261,111
WRIST WATCH

Yutaka Fukumura, Higashimurayama, Japan, assignor to Citizen Watch Co. Ltd., Tokyo, Japan

Filed Jun. 15, 1979, Ser. No. 49,486
Claims priority, application Japan, Mar. 2, 1979, 54-7732
Term of patent 14 years
Int. Cl. D10—04


U.S. Cl. D10—38

261,112
WRIST WATCH

Yutaka Fukumura, Higashimurayama, Japan, assignor to Citizen Watch Co., Ltd., Tokyo, Japan

Filed Oct. 10, 1979, Ser. No. 83,531
Claims priority, application Japan, Apr. 17, 1979, 54-15333
Term of patent 14 years
Int. Cl. D10—02

U.S. Cl. D10—38

261,113
WRIST WATCH

Yutaka Fukumura, Higashimurayama, Japan, assignor to Citizen Watch Co., Ltd., Tokyo, Japan

Filed May 30, 1979, Ser. No. 43,889
Claims priority, application Japan, Dec. 21, 1978, 53-54082
Term of patent 14 years
Int. Cl. D10—02

U.S. Cl. D10—39

261,114
LEVEL INDICATING FLOAT

Eugene Kask, Willimantic, Conn., assignor to Rogers Corporation, Rogers, Conn.

Filed Oct. 18, 1978, Ser. No. 952,578
Term of patent 14 years
Int. Cl. D10—07


U.S. Cl. D10—103

261,115
TIMING LIGHT

Hugh T. Greenlee, Gates Mills; Roy P. Hess, Vermillion, both of Ohio, and Donald C. McKinnon, Cheboygan, Mich., assignors to Fox Valley Instrument Company, Cheboygan, Mich.

Filed May 31, 1979, Ser. No. 44,055
Term of patent 14 years
Int. Cl. D10—05

U.S. Cl. D10—112



261,116

WARNING FLASHER OR SIMILAR ARTICLE

Wayne R. Repak, Park Ridge, Ill., assignor to Safe-T-Signal, Inc., Park Ridge, Ill.

Filed Oct. 10, 1978, Ser. No. 950,216

Term of patent 14 years

Int. Cl. D10-06

U.S. Cl. D10-114



261,119

NECKLACE OR SIMILAR ARTICLE

Josef J. Barr, 125 Worth Ave., Palm Beach, Fla. 33480

Filed Dec. 17, 1979, Ser. No. 104,053

Term of patent 14 years

Int. Cl. D11-01

U.S. Cl. D11-7



261,117

DOOR ANNUNCIATOR HOUSING


Kenneth T. Lewis, 300 N. Sixth, Longview, Tex. 75601

Filed Feb. 5, 1979, Ser. No. 9,160

Term of patent 14 years

Int. Cl. D10-05

U.S. Cl. D10-118



261,120

NECKLACE OR SIMILAR ARTICLE


Josef J. Barr, 125 Worth Ave., Palm Beach, Fla. 33480

Filed Dec. 17, 1979, Ser. No. 104,052

Term of patent 14 years

Int. Cl. D11-01

U.S. Cl. D11-15



261,118

SONIC SIGNAL GENERATOR


Leslie Perhacs, Jr., Port Ludlow, Wash., assignor to Proctor & Associates Company, Redmond, Wash.

Filed Jun. 4, 1979, Ser. No. 44,977

Term of patent 14 years

Int. Cl. D10-05

U.S. Cl. D10-121



261,121

NECKLACE OR SIMILAR ARTICLE


Josef J. Barr, 125 Worth Ave., Palm Beach, Fla. 33480

Filed Dec. 17, 1979, Ser. No. 104,054

Term of patent 14 years

Int. Cl. D11-01

U.S. Cl. D11-15



261,123

BRACELET SUPPORT


Mortimer Saffran, 2 Derbyshire, Derby, Conn. 06418, and Emil Turcek, 9 Garden Ter., Shelton, Conn. 06484

Filed Aug. 29, 1979, Ser. No. 70,852

Term of patent 14 years

Int. Cl. D11-01

U.S. Cl. D11-86



261,124

TEST TUBE BABY FIGURINE

Scott Dunham, 9 Briarcliff Rd., Mt. Lakes, N.J. 07046

Filed Aug. 6, 1979, Ser. No. 64,199

Term of patent 7 years

Int. Cl. D11-02

U.S. Cl. D11-160



261,122

FINGER RING




Josef J. Barr, 125 Worth Ave., Palm Beach, Fla. 33480

Filed Jun. 29, 1979, Ser. No. 54,302

Term of patent 14 years

Int. Cl. D11-01

U.S. Cl. D11-34



261,125

HAND CART

Donald J. Gordon, Rockwood; Frank H. Johnson, Cambridge, both of Canada; George L. Schick, Easton, Conn., and J. David Smart, Cambridge, Canada, assignors to Slater Steel Industries Limited, Ontario, Canada


Filed Feb. 12, 1979, Ser. No. 11,371

Claims priority, application Canada, Dec. 21, 1978, 2112781

Term of patent 14 years

Int. Cl. D12-02

U.S. Cl. D34-24



261,127

MOBILE SELF-POWERED HYDRAULIC LIFT

Rallie P. Rallis; Richard E. Cullity, both of Los Angeles County, and Lyle R. Tamplin, Orange County, all of Calif., assignors to Mark Industries, Carson, Calif.


Continuation of Ser. No. 880,300, Feb. 22, 1978, abandoned.

This application Jan. 31, 1980, Ser. No. 117,255

Term of patent 14 years

Int. Cl. D12-05

U.S. Cl. D34-34



261,126

REMOTE CONTROLLED FORK TRUCK

Olof H. Lindfors, Gothenburg, Sweden, assignor to Aktiebolaget Volvo, Gothenburg, Sweden


Filed Nov. 24, 1978, Ser. No. 963,568

Claims priority, application Sweden, May 25, 1978, 78-1361

Term of patent 14 years

Int. Cl. D12-05

U.S. Cl. D34-34



261,128

BOAT


George D. Fowler, Maryville, Tenn., assignor to Supreme Industries, Inc., Louisville, Tenn.

Filed Dec. 11, 1978, Ser. No. 968,115

Term of patent 14 years

Int. Cl. D12-06

U.S. Cl. D12-300



261,129

FOLDABLE BABY STROLLER

Giuseppe Perego, Via De Gasperi, Arcore (Milano), Italy (20043)

Filed Apr. 12, 1979, Ser. No. 29,482

Claims priority, application Italy, Oct. 30, 1978, 23166/78[U]

Term of patent 14 years

Int. Cl. D12-12

U.S. Cl. D12-129



261,131

ARTICLE CARRIER STANCHION


Ray G. Mareydt, Warren, and Daniel J. Kowalski, Ortonville, both of Mich., assignors to Four Star Corporation, Troy, Mich.

Filed Jun. 11, 1979, Ser. No. 46,996

Term of patent 14 years

Int. Cl. D12-16

U.S. Cl. D12-157



261,130

TIRE

Guy Amarger, Clermont-Ferrand, France, assignor to Compagnie Generale des Etablissements Michelin, Clermont-Ferrand, France


Filed Oct. 16, 1978, Ser. No. 951,843

Claims priority, application France, Apr. 25, 1978, 78 557

Term of patent 14 years

Int. Cl. D12-15

U.S. Cl. D12-147



261,132

MOTORCYCLE FAIRING


Craig W. Vetter, Manitou Springs, Colo.; Charles M. Perethian, Arroyo Grande, and Kenneth W. Cummings, San Luis Obispo, both of Calif., assignors to First Champaign Corporation, Rantoul, Ill.

Filed Oct. 31, 1979, Ser. No. 89,913

Term of patent 14 years

Int. Cl. D12-11

U.S. Cl. D12-182




261,133

COMBINED RUNNING BOARD AND SPLASH GUARD
 Martin A. Makela, Waconia, Minn., assignor to J-Mark, Inc.,
 Minneapolis, Minn.

Filed May 3, 1979, Ser. No. 35,896
 Term of patent 14 years
 Int. Cl. D12-16

U.S. Cl. D12-203




261,134

ELECTRICAL CURRENT SUPPLY TRACK
 Robert Heritage, London, England, assignor to Rotaflex (Great
 Britain) Limited, London, England

Filed Jun. 14, 1979, Ser. No. 48,679
 Claims priority, application United Kingdom, Dec. 22, 1978,
 987816/78

Term of patent 14 years
 Int. Cl. D13-03

U.S. Cl. D13-13




261,135

SAFETY COVER FOR ELECTRICAL OUTLETS
 James Horne, 42 Duncaster Rd., Bloomfield, Conn. 06002

Filed Feb. 14, 1979, Ser. No. 12,136
 Term of patent 14 years
 Int. Cl. D13-03

U.S. Cl. D13-30




261,136

**COMBINED AUTOMOBILE CARTRIDGE PLAYER AND
 RADIO RECEIVER OR THE LIKE**

Nobuo Yamada, Kobe; Masayoshi Kamikubo, Akashi; Koichi
 Chikaishi, and Junichi Terahata, both of Kobe, all of Japan,
 assignors to Rujitsu Ten Limited, Hyogo, Japan

Filed Nov. 23, 1979, Ser. No. 96,687
 Claims priority, application Japan, May 29, 1979, 54-21908
 Term of patent 14 years
 Int. Cl. D14-01, 03

U.S. Cl. D14-5



261,137

AUTOMOTIVE AUDIO SYSTEM SPEAKER ENCLOSURE
 Peter G. De Lillo, 161 3rd St., Staten Island, N.Y. 10306

Filed Dec. 15, 1978, Ser. No. 969,875
 Term of patent 7 years
 Int. Cl. D14-01

U.S. Cl. D14-33




261,138

MAGNETIC TAPE UNIT

Myron F. Davis, Jr., Boca Raton, Fla., assignor to International
 Business Machines Corporation, Armonk, N.Y.

Filed Jan. 8, 1979, Ser. No. 2,032
 Term of patent 14 years
 Int. Cl. D14-02

U.S. Cl. D14-108



261,139

TELEPHONE APPARATUS

Knud Jakobsen, Horsens, Denmark, assignor to International
 Standard Electric Corporation, New York, N.Y.

Filed Apr. 5, 1979, Ser. No. 27,348
 Term of patent 14 years
 Int. Cl. D14-03

U.S. Cl. D14-53




261,140

TELEVISION CAMERA

Tameaki Ikeda, Tokyo, Japan, assignor to Sony Corporation,
 Tokyo, Japan

Filed Mar. 6, 1978, Ser. No. 884,042
 Claims priority, application Japan, Sep. 6, 1977, 52-35514
 Term of patent 14 years
 Int. Cl. D14-03

U.S. Cl. D14-78




261,141

AGRICULTURAL TRACTOR

Teizo Takahashi, and Kazuo Toyokuni, both of Sakai, Japan,
 assignors to Kubota, Ltd., Naniwa, Japan

Filed Jul. 3, 1979, Ser. No. 54,617
 Claims priority, application Japan, Jan. 11, 1979, 54-873
 Term of patent 14 years
 Int. Cl. D15-03

U.S. Cl. D15-23




261,142

FOOD DEHYDRATOR

Chad S. Erickson, Minneapolis, and W. Robert Worrell, Hop-
 kins, both of Minn., assignors to Alternative Pioneering Sys-
 tems, Inc., Minneapolis, Minn.

Filed Jan. 15, 1979, Ser. No. 3,472
 Term of patent 14 years
 Int. Cl. D15-08

U.S. Cl. D15-110




261,143

WOOD SPLITTER

Robert H. Green, 16967 Bowling Green, West, Bowling Green,
 Ohio 43402

Filed Dec. 16, 1977, Ser. No. 861,443
 Term of patent 14 years
 Int. Cl. D15-09

U.S. Cl. D15-127




261,144

MOVING TARGET PROJECTOR CONSOLE

Brian T. Brooksby, 156 Earlsbrook Rd., Redhill, Surrey; Harold J. Murray, 32 New Odham Rd., Alton, Hampshire; Anthony Simpson, 65 South Hill, Godalming, Surrey, and Stuart M. Peterkin, 30 Leewood Way, Effingham, Surrey, all of England
 Filed Feb. 21, 1979, Ser. No. 13,393
 Claims priority, application United Kingdom, Aug. 24, 1978, 986058/78

Term of patent 14 years
 Int. Cl. D16—02

U.S. Cl. D16—11




261,146

ELECTROSTATIC COPIER OR SIMILAR ARTICLE

Masaaki Sakai, Toyokawa, Japan, and Toshihiko Sakow, Teaneck, N.J., assignors to Minolta Camera Kabushiki Kaisha, Osaka, Japan

Filed Sep. 7, 1979, Ser. No. 73,349
 Claims priority, application Japan, Mar. 8, 1979, 54/9247
 Term of patent 14 years
 Int. Cl. D16—03

U.S. Cl. D16—31




261,147

COMBINED COPYING AND SORTING APPARATUS

Frederick J. Lawrence, Tustin, Calif., assignor to Gradco/Dendoki, Inc., Newport Beach, Calif.

Filed Sep. 24, 1979, Ser. No. 78,399
 Term of patent 14 years
 Int. Cl. D16—03

U.S. Cl. D16—32




261,145

COPIER OR SIMILAR ARTICLE

Taro Etoh, Okazaki, and Sadao Ishihara, Toyokawa, both of Japan, assignors to Minolta Camera Kabushiki Kaisha, Osaka, Japan

Filed Nov. 13, 1979, Ser. No. 93,482
 Claims priority, application Japan, May 21, 1979, 54-20774
 Term of patent 14 years
 Int. Cl. D16—03

U.S. Cl. D16—30




261,148

COMBINED COPYING AND SORTING APPARATUS

Frederick J. Lawrence, Tustin, Calif., assignor to Gradco/Dendoki, Inc., Newport Beach, Calif.

Filed Nov. 29, 1979, Ser. No. 98,538
 Term of patent 14 years
 Int. Cl. D16—03

U.S. Cl. D16—32



261,149


SCREEN UNIT

Brian T. Brooksby, 156 Earlsbrook Rd., Redhill, Surrey; Harold J. Murray, 32 New Odham Rd., Alton, Hampshire; Anthony Simpson, 65 South Hill, Godalming, Surrey, and Stuart M. Peterkin, 30 Leewood Way, Effingham, Surrey, all of England
 Filed Feb. 21, 1979, Ser. No. 13,391

Claims priority, application United Kingdom, Aug. 24, 1978, 986060/78

Term of patent 14 years
 Int. Cl. D16—05

U.S. Cl. D16—43




261,151

HANDLE AND CAP ASSEMBLY FOR THE PRINT HEAD OF IMPRINTING MACHINES

William P. Barbour, Mount Prospect, Ill., assignor to Security Imprinter Corporation, Walkersville, Md.
 Filed Jan. 16, 1980, Ser. No. 114,057

Term of patent 14 years
 Int. Cl. D18—02

U.S. Cl. D18—14




261,152

PRINTING BED ASSEMBLY FOR IMPRINTING MACHINES

William P. Barbour, Mount Prospect, Ill., assignor to Security Imprinter Corporation, Walkersville, Md.

Filed Jan. 16, 1980, Ser. No. 114,058
 Term of patent 14 years
 Int. Cl. D18—02

U.S. Cl. D18—14




261,150

COMBINED GUITAR AND SYNTHESIZER SOUND BOX, OR SIMILAR ARTICLE

Forest L. Terry, Jr., 90 Brunswick St., Boston, Mass. 02121

Filed Jan. 23, 1980, Ser. No. 114,639
 Term of patent 14 years
 Int. Cl. D17—01, 03

U.S. Cl. D17—2




261,153

ACOUSTICAL HOOD ASSEMBLY FOR A PRINTER APPARATUS

Wayne C. Cathey, Bedford, Tex., assignor to Xerox Corporation, Stamford, Conn.

Filed Jul. 20, 1979, Ser. No. 58,961
 Term of patent 14 years
 Int. Cl. D18—02

U.S. Cl. D18—22




261,154
ENVELOPE

Glenn A. Thresher, Pineville, N.C., assignor to Rexham Corporation, Pineville, N.C.

Filed Sep. 10, 1979, Ser. No. 73,618
Term of patent 14 years
Int. Cl. D19-07

U.S. Cl. D19-4



261,156
BELT ELEVATOR TYPE EDUCATIONAL TOY

Emmet Crawford, 2602 Central Ave., Kearney, Nebr. 68847

Filed Sep. 25, 1980, Ser. No. 190,836
Term of patent 14 years
Int. Cl. D19-07

U.S. Cl. D19-59




261,157
COMBINED KALEIDOSCOPE AND TOY MAIL BOX

Tobin Wolf, 285 Aycrigg Ave., Passaic, N.J. 07055

Filed Feb. 12, 1979, Ser. No. 11,524
Term of patent 14 years
Int. Cl. D21-01

U.S. Cl. D21-60




261,158
KINETIC SCULPTURE

Hidetoshi Matsui, 6-27-311, Imazunaka 3-chome, Tsurumi-ku, Osaka, Japan

Filed Sep. 12, 1979, Ser. No. 75,303
Claims priority, application Japan, May 25, 1979, 54-21552
Term of patent 14 years
Int. Cl. D21-01

U.S. Cl. D21-102



261,155
TRANSPARENT STORAGE ENVELOPE FOR A
FLEXIBLE MAGNETIC COMPUTER DISC

Richard Nast, 309 Whipoorwill La., Brentwood, Tenn. 37027

Filed Oct. 15, 1979, Ser. No. 84,871
Term of patent 14 years
Int. Cl. D19-04

U.S. Cl. D19-33




261,159
TOY KITCHEN SINK

Gerald M. Rapaport, 5933 N. Lincoln Ave., Chicago, Ill. 60659

Filed Sep. 21, 1979, Ser. No. 77,747
Term of patent 14 years
Int. Cl. D21-01

U.S. Cl. D21-122



261,161
TOY BEAR FIGURINE

Hiroshi Ohkawa, Tokyo, Japan, assignor to Tomy Kogyo Co., Inc., Tokyo, Japan

Filed Sep. 27, 1979, Ser. No. 79,250
Claims priority, application Japan, Mar. 30, 1979, 54/12725
Term of patent 14 years
Int. Cl. D21-01

U.S. Cl. D21-150




261,162
TOY DOG FIGURINE

Hiroshi Ohkawa, Tokyo, Japan, assignor to Tomy Kogyo Co., Inc., Tokyo, Japan

Filed Sep. 27, 1979, Ser. No. 79,344
Claims priority, application Japan, Mar. 30, 1979, 54-12724
Term of patent 14 years
Int. Cl. D21-01

U.S. Cl. D21-150




261,160
TOY STOVE

Gerald M. Rapaport, 5933 N. Lincoln Ave., Chicago, Ill. 60659

Filed Sep. 21, 1979, Ser. No. 77,752
Term of patent 14 years
Int. Cl. D21-01

U.S. Cl. D21-122




261,163
ANIMATED SEAL FIGURINE

Toshiaki Takizawa, Tokyo, Japan, assignor to Tomy Kogyo Co., Inc., Tokyo, Japan

Filed Oct. 15, 1979, Ser. No. 85,062
Claims priority, application Japan, Apr. 13, 1979, 54-15225
Term of patent 14 years
Int. Cl. D21-01

U.S. Cl. D21-150



261,164

ANIMATED FROG FIGURINE

Kazue Kudo, Tokyo, Japan, assignor to Tomy Kogyo Co., Inc., Arthur P. Swanson, 1454 Estate La., Glenview, Ill. 60025
Tokyo, Japan

Filed Oct. 15, 1979, Ser. No. 85,060

Claims priority, application Japan, Apr. 13, 1979, 54-15223

Term of patent 14 years

Int. Cl. D21-01

U.S. Cl. D21-158



261,167

GOLF CLUB HEAD

Filed Nov. 12, 1980, Ser. No. 206,270

Term of patent 14 years

Int. Cl. D21-02

U.S. Cl. D21-220



261,165

TOY ANIMAL FIGURE


Kenzo Kurosawa, and Fukuji Hachimura, both of Tokyo, Japan,
assignors to Gakken Co., Ltd, Tokyo, Japan

Filed Jun. 4, 1979, Ser. No. 45,431

Term of patent 14 years

Int. Cl. D21-01

U.S. Cl. D21-160



261,168

SKATEBOARD ICE BLADE


Kenneth Rice, Jr., Cerritos, Calif., assignor to Donald B. Allen,
Oklahoma City, Okla.

Filed Oct. 20, 1978, Ser. No. 953,840

Term of patent 14 years

Int. Cl. D21-02

U.S. Cl. D21-225



261,166

ANIMATED PENGUIN FIGURINE

Kazue Kudo, Tokyo, Japan, assignor to Tomy Kogyo Co., Inc.,
Tokyo, Japan

Filed Oct. 15, 1979, Ser. No. 85,061

Claims priority, application Japan, Apr. 13, 1979, 54-15224

Term of patent 14 years

Int. Cl. D21-01

U.S. Cl. D21-160



261,169

FISHING LURE

Larry R. Snyder, 5909 Clark Ave., Lakewood, Calif. 90712

Filed Jan. 11, 1980, Ser. No. 111,271

Term of patent 14 years

Int. Cl. D22-05

U.S. Cl. D22-27



261,170

SHAMPOO SINK


James S. McFarlane, 413 S. 284th, Redondo Beach, Wash. 98054

Filed Jan. 7, 1980, Ser. No. 109,771

Term of patent 14 years

Int. Cl. D23-02

U.S. Cl. D23-64



261,171

WATER CLOSET


Richard J. Cuttriss, Fillmore, Calif., assignor to Gruber Sys-
tems, Inc., Valencia, Calif.

Filed Sep. 12, 1980, Ser. No. 186,689

Term of patent 14 years

Int. Cl. D23-02

U.S. Cl. D23-65



261,172

PULMONARY FUNCTION MEASUREMENT
APPARATUS OR THE LIKE


Tsvi Lissack, Englewood, Colo., assignor to Hospal Medical
Corp., Littleton, Colo.

Filed Sep. 5, 1978, Ser. No. 939,889

Term of patent 14 years

Int. Cl. D24-02

U.S. Cl. D24-17



261,173

BILIRUBINOMETER


John T. Armbruster, Niagara Falls, N.Y., assignor to American
Optical Corporation, Southbridge, Mass.

Filed Feb. 5, 1979, Ser. No. 9,339

Term of patent 14 years

Int. Cl. D24-02

U.S. Cl. D24-21



261,174

BOTTOM PLATE FOR A SPHYGMOMANOMETER


Emanuel Berliner, Valley Stream, N.Y., assignor to Bristoline
Inc., Freeport, N.Y.

Filed Sep. 5, 1978, Ser. No. 939,677

Term of patent 14 years

Int. Cl. D24-99

U.S. Cl. D24-29



261,175

MEDICAL CONTAINER HANGER


David L. O'Day, Canoga Park, Calif., assignor to American Hospital Supply Corporation, Evanston, Ill.

Filed Aug. 25, 1978, Ser. No. 936,820

Term of patent 14 years

Int. Cl. D24-99

U.S. Cl. D24-99



261,176

BUILDING


Samuel Chernin, 300 E. 54th St., New York, N.Y. 10022

Filed Mar. 14, 1979, Ser. No. 20,261

Term of patent 3½ years

Int. Cl. D25-03

U.S. Cl. D25-11



261,177

BUILDING STRUCTURE OR THE LIKE


Eric Gachwandtner, 5413 Sylvan La., Raleigh, N.C. 27612

Filed Dec. 14, 1979, Ser. No. 104,030

Term of patent 14 years

Int. Cl. D25-03

U.S. Cl. D25-17



261,178

FIRE ESCAPE PLATFORM


Cheyenne A. Reinhard, 29372 Providence Way, Hayward, Calif. 94544

Filed Dec. 14, 1978, Ser. No. 969,566

Term of patent 14 years

Int. Cl. D6-99

U.S. Cl. D25-62



261,179

CANDLE SCONCE


John P. Alley, Sr., 10841 Meadow La., Philadelphia, Pa. 19154

Filed Aug. 9, 1979, Ser. No. 65,266

Term of patent 14 years

Int. Cl. D26-01

U.S. Cl. D26-9



261,180

TRACK LIGHT SYSTEM

Herbert Lugin, 31 Deer Park Rd., Great Neck, N.Y. 11024

Filed Apr. 16, 1979, Ser. No. 30,555

Term of patent 14 years

Int. Cl. D26-05

U.S. Cl. D26-66



261,181

COMB WITH ARTIFICIAL FLOWERS AND SEASHELLS


Gloria J. Sands, 21805 Ulmus Dr., Woodland Hills, Calif. 91364

Filed Jun. 16, 1980, Ser. No. 160,126

Term of patent 14 years

Int. Cl. D28-03

U.S. Cl. D28-32



261,182

BEE FRAME END BAR


John L. Guilfoyle, 772 Boundary Rd., Darra, Queensland, 4076, Australia

Filed Feb. 28, 1979, Ser. No. 16,040

Term of patent 14 years

Int. Cl. D30-02

U.S. Cl. D30-2



261,183

FLUME PLATFORM FOR ANIMAL CONFINEMENT PENS


Richard E. Bunger, 5202 E. Washington St., Phoenix, Ariz. 85034

Filed Aug. 9, 1979, Ser. No. 65,356

Term of patent 14 years

Int. Cl. D30-02

U.S. Cl. D30-2



261,184

FLUME PLATFORM FOR ANIMAL CONFINEMENT PENS


Richard E. Bunger, 5202 E. Washington St., Phoenix, Ariz. 85034

Filed Aug. 10, 1979, Ser. No. 65,716

Term of patent 14 years

Int. Cl. D30-02

U.S. Cl. D30-2



261,185

FLUME PLATFORM FOR ANIMAL CONFINEMENT PENS


Richard E. Bunger, 5202 E. Washington St., Phoenix, Ariz. 85034

Filed Aug. 10, 1979, Ser. No. 65,717

Term of patent 14 years

Int. Cl. D30-02

U.S. Cl. D30-2



261,186

COMBINED CAT PLAYGROUND AND EXERCISER

Robert J. Michalski, Paramus, N.J., assignor to Abeta Pet Supply, Inc., Dumont, N.J.

Division of Ser. No. 5,695, Jan. 23, 1979. This application Jul. 14, 1980, Ser. No. 168,161

Term of patent 14 years

Int. Cl. D30-99

U.S. Cl. D30-42



261,187

CURTAIN MATERIAL

Hans Stöcker, Wil, Switzerland, assignor to Gardisette International AG, Lucerne, Switzerland

Filed May 30, 1979, Ser. No. 43,687

Claims priority, application Fed. Rep. of Germany, Nov. 30, 1978, 1187

Term of patent 14 years

Int. Cl. D5—05

U.S. Cl. D47—6 E



261,189

LAMINATE SHEET

Harry R. Ford, Parkdale, Ohio, and Yasuo Yoshihashi, Tokyo, Japan, assignors to Formica Corporation, Cincinnati, Ohio

Filed Jul. 11, 1978, Ser. No. 923,615

Term of patent 14 years

Int. Cl. D5—06

U.S. Cl. D92—1 R



261,188

DESIGN FOR CURTAIN MATERIAL

Hans Stöcker, Wil, Switzerland, assignor to Gardisette International AG, Luzern, Switzerland

Filed Jan. 9, 1980, Ser. No. 110,750

Claims priority, application Fed. Rep. of Germany, Jul. 10, 1979, 752

Term of patent 14 years

Int. Cl. D5—05

U.S. Cl. D47—6 E



261,190

LAMINATE SHEET

Harry R. Ford, Parkdale, Ohio, and Yasuo Yoshihashi, Tokyo, Japan, assignors to Formica Corporation, Cincinnati, Ohio

Filed Jul. 11, 1978, Ser. No. 923,617

Term of patent 14 years

Int. Cl. D5—06

U.S. Cl. D92—1 R



261,191

LAMINATE SHEET

Harry R. Ford, Parkdale, Ohio, and Yasuo Yoshihashi, Tokyo, Japan, assignors to Formica Corporation, Cincinnati, Ohio

Filed Jul. 11, 1978, Ser. No. 923,618

Term of patent 14 years

Int. Cl. D5—06

U.S. Cl. D92—1 Y



261,193

TOTE TRAY

Jean Cornou, Verrieres-le-Buisson, France, assignor to Allibert Exploitation Societe Anonyme, Grenoble, France


Filed Dec. 1, 1978, Ser. No. 965,483

Claims priority, application France, Jun. 1, 1978, 78 2491

Term of patent 14 years

Int. Cl. D99—99

U.S. Cl. D34—45



261,192

CURTAIN MATERIAL

Hans Stöcker, Wil, Switzerland, assignor to Gardisette International AG, Lucerne, Switzerland

Filed Jan. 23, 1980, Ser. No. 114,582

Claims priority, application Fed. Rep. of Germany, Jul. 27, 1979, URA 813

Term of patent 14 years

Int. Cl. D5—05

U.S. Cl. D92—1 A



261,194

BEVERAGE CASE


Theodor M. Box, Brielle, N.J., assignor to Cities Service Company, Tulsa, Okla.

Filed Dec. 6, 1978, Ser. No. 967,053

Term of patent 14 years

Int. Cl. D99—99

U.S. Cl. D34—46



LIST OF PATENTEES

TO WHOM

PATENTS WERE ISSUED ON THE 6TH DAY OF OCTOBER, 1981

NOTE.—Arranged in accordance with the first significant character or word of the name
(in accordance with city and telephone directory practice).

- A. O. Smith Corporation: See—
Lykes, Robert E., 4,293,114, Cl. 248-604.000.
- A-T-O Inc.: See—
Winiasz, Michael E., 4,293,010, Cl. 141-392.000.
- AB Bofors: See—
Furendal, Allan R. B.; Larsson, Bernt; and Nilsson, Erik R., 4,293,596, Cl. 427-160.000.
- AB Svenska Flackfabriken, Fack: See—
Bjorklund, Bjorn A., 4,292,809, Cl. 60-676.000.
- AB Volvo: See—
Ronbeck, Arne I., 4,293,271, Cl. 414-737.000.
- Abatti, Cinto A.; and Ash, Harold T. Field crop harvesting and loading machine. 4,292,784, Cl. 53-391.000.
- Abbott, Bernard J.; and Fukuda, David S., to Eli Lilly and Company. A-30912A Nucleus. 4,293,482, Cl. 260-112.50R.
- Abbott, Bernard J.; and Fukuda, David S., to Eli Lilly and Company. A-30912H Nuclei. 4,293,490, Cl. 260-112.50K.
- Abbott Laboratories: See—
Raden, Daniel S.; and Arbir, Francis W., 4,293,658, Cl. 521-129.000.
- Seely, John H., 4,293,689, Cl. 536-17.00R.
- Abramian, Eduard S.: See—
Kopylov, Alexei A.; Kuzmenko, Valentin T.; Stepanov, Alexandr N.; Gaschenko, Viktor P.; Kaznacheevsky, Nikolai A.; Nosovitsky, Alexandr Y.; Misikov, Ivan I.; Shapiro, Alexandr I.; Skakunov, Ivan G.; Markin, Valentin G.; Konstantinov, Alexei K.; Abramian, Eduard S.; Soroka, Arseny M.; and Zinchenko, Yakov A., 4,292,928, Cl. 119-17.000.
- Abrash, Muriel: See—
Langley, Robert C.; Myers, Herbert; and Abrash, Muriel, 4,293,513, Cl. 264-60.000.
- Accatino, Luciano, to CSELT, Centro Studi e Laboratori Telecomunicazioni S.p.A. Microstrip delay line compensated for thermal phase variations. 4,293,830, Cl. 333-161.000.
- ACF Industries, Incorporated: See—
Hinrichs, John M., 4,293,116, Cl. 251-173.000.
- Acheson, John L., to Rexnord Inc. Servo-valve convertible construction. 4,292,805, Cl. 60-450.000.
- Acker, Donald J., to J. F. Enterprises, Inc. Convertible sofa-bed with back restraining mechanism. 4,292,698, Cl. 5-45.000.
- Adachi, Hideo; Minai, Kiichi; Moriyasu, Kozo; and Imagawa, Shunjiro, to Murata Manufacturing Co., Ltd. Infrared radiation detecting apparatus and method of manufacturing. 4,293,768, Cl. 250-338.000.
- Adams, Phillip: See—
Swift, Harold E.; Innes, Robert A.; and Adams, Phillip, 4,293,716, Cl. 564-480.000.
- Adidas Fabrique de Chaussures de Sport: See—
Johansen, Arne W., 4,293,143, Cl. 280-615.000.
- AEL Mirrotel, Ltd.: See—
White, John E., 4,293,902, Cl. 363-26.000.
- Aeration Industries, Inc.: See—
Inhofer, Harold G., 4,293,169, Cl. 308-121.000.
- AGA Aktiebolag: See—
Braun, Stellan, 4,293,096, Cl. 239-419.300.
- Agency of Industrial Science & Technology: See—
Ebata, Yoshihiro; Toibana, Yasuo; Uetsuki, Tsuneo; Kose, Saburo; and Kinoshita, Makoto, 4,293,356, Cl. 156-89.000.
- AGFA-Gevaert Aktiengesellschaft: See—
Wagner, Karl; Engelsmann, Dieter; Hackenberg, Hubert; and Stiefel, Peter, 4,293,204, Cl. 354-21.000.
- AGFA-GEVAERT N.V.: See—
Heirbaut, Wilfried A.; and Rens, Walter J., 4,293,508, Cl. 264-25.000.
- Aine, Harry E.: See—
Block, Barry, 4,293,316, Cl. 55-16.000.
- Aketa, Kohichi: See—
Suzuki, Yukio; Kasamatsu, Kiyoshi; and Aketa, Kohichi, 4,293,504, Cl. 260-465.00D.
- Akita, Yoshio: See—
Muto, Katsuya; Mori, Kazumasa; Mase, Akira; Nimura, Takayasu; Itoh, Katsumi; and Akita, Yoshio, 4,293,811, Cl. 322-60.000.
- Akizuki, Katsufumi: See—
Segawa, Hiroshi; and Akizuki, Katsufumi, 4,293,523, Cl. 422-139.000.
- Aktiebolaget Draco: See—
Mono, Rune G.; Moren, Nils F. E.; and Wetterlin, Kjell I. L., 4,292,966, Cl. 128-200.230.
- Aktiebolaget Platmanufaktur AB: See—
Jakobsen, Kjell M., 4,293,359, Cl. 156-156.000.
- Akutsu, Masao, to Yoshino Kogyosho Co., Ltd. Process for molding parison for making stretch molded bottle. 4,293,520, Cl. 264-513.000.
- Akzona Incorporated: See—
Zeilstra, Jacobus J.; de Klein, Willem J.; and Bik, Joannes D., 4,293,345, Cl. 106-270.000.
- Aladdin Industries, Incorporated: See—
Bridges, John A., 4,293,071, Cl. 206-503.000.
- Albin Sprenger KG GmbH & Co.: See—
Bachem, Christian, 4,292,850, Cl. 73-702.000.
- Albright, Jay D.: See—
Allen, George R., Jr.; Hanifin, John W., Jr.; Moran, Daniel B.; and Albright, Jay D., 4,293,554, Cl. 424-250.000.
- Alcan Aluminum Corporation: See—
Chalmers, Alexander A.; and Gailey, J. Lynn, 4,292,781, Cl. 52-547.000.
- Alembik, Alfred. Furniture for sitting and reclining. 4,292,697, Cl. 5-18.00R.
- Alf Hannaford & Co. Pty. Ltd.: See—
Hopkins, Donald L., 4,292,931, Cl. 119-103.000.
- Alfa Romeo S.p.A.: See—
Bertoloni, Luciano; Rogora, Edoardo; and Cressoni, Ermanno, 4,293,843, Cl. 340-52.00F.
- Alkem GmbH: See—
Ledebrink, Friedrich-Wilhelm; Stoll, Wolfgang; and Schafer, Dieter, 4,293,438, Cl. 252-301.10W.
- Alleman, James E.: See—
Slavens, Clyde M.; Clavin, Edward A.; and Alleman, James E., 4,293,758, Cl. 219-125.120.
- Allen-Bradley Company: See—
Struger, Odo J.; Brown, Ronald A.; and Black, Craig A., 4,293,924, Cl. 364-900.000.
- Allen, George R., Jr.; Hanifin, John W., Jr.; Moran, Daniel B.; and Albright, Jay D., to American Cyanamid Company. Method of treating asthma. 4,293,554, Cl. 424-250.000.
- Allen, Robert J.; Lindstrom, Robert; and Juda, Walter, to Prototech Company. Thin carbon-cloth-based electrocatalytic gas diffusion electrodes, and electrochemical cells comprising the same. 4,293,396, Cl. 204-106.000.
- Alley, David W., to Mosely, Neal J., a part interest. Fingernail hone. 4,292,987, Cl. 132-73.000.
- Allied Chemical Corporation: See—
Marshall, Robert M.; and Dardoufas, Kimon C., 4,293,460, Cl. 260-18.00F.
- Weman, Per O., 4,293,105, Cl. 242-107.40B.
- Allied Paper Incorporated: See—
Shaw, Michael J.; and Thiessen, Robert J., 4,293,629, Cl. 430-64.000.
- Allis-Chalmers Corporation: See—
Bhide, Yeshwant K., 4,292,992, Cl. 137-340.000.
- Lucas, James H., 4,293,059, Cl. 192-3.570.
- O'Connor, John W., 4,293,040, Cl. 172-7.000.
- Allison, William W., to Pilgrim Electric Company. Remote selective switching system for use with AC power line. 4,293,846, Cl. 340-310.00A.
- Altstatt, John E., to California Microwave, Inc. Double-balanced mixer. 4,293,956, Cl. 455-327.000.
- Amano, Yutaka, to Hitachi, Ltd. Dynamic type semiconductor memory equipment. 4,293,926, Cl. 364-900.000.
- American Can Company: See—
Detroit, William J., 4,293,342, Cl. 106-90.000.
- Detroit, William J., 4,293,459, Cl. 260-17.500.
- American Cyanamid Company: See—
Allen, George R., Jr.; Hanifin, John W., Jr.; Moran, Daniel B.; and Albright, Jay D., 4,293,554, Cl. 424-250.000.
- Bermady, Karel F.; Floyd, Middleton B., Jr.; Poletto, John F.; Schaub, Robert E.; and Weiss, Martin J., 4,293,704, Cl. 556-442.000.
- Granzow, Albrecht H., 4,293,464, Cl. 260-45.70P.
- Granzow, Albrecht H., 4,293,465, Cl. 260-45.70P.
- Hardy, William B.; and Loffelman, Frank F., 4,293,467, Cl. 260-45.80N.
- Pai, Venkatrao K.; and Skrivan, Joseph F., 4,293,692, Cl. 544-196.000.
- Werneke, Michael F.; and Jones, James A., 4,293,406, Cl. 209-166.000.
- American Home Products Corporation: See—
Wei, Peter H. L.; and Bell, Stanley C., 4,293,696, Cl. 546-83.000.
- American Safety Equipment Corporation: See—
Ziv, Avraham, 4,293,107, Cl. 242-107.700.
- American Standard Inc.: See—
Olson, Paul E.; and Lyons, Michael D., 4,293,118, Cl. 251-297.000.
- Weseloh, Roger J.; Kanjo, Wajih; and Karim, Syed, 4,292,721, Cl. 29-243.520.

AMP Incorporated: See—
Hughes, Donald W. K.; and Myers, Ronald W., 4,292,736, Cl. 29-884.000.
Tucci, John J., 4,292,732, Cl. 29-749.000.
Weisenburger, Lawrence P., 4,293,177, Cl. 339-99.00R.
Ampex Corporation: See—
Schiller, Edward, 4,293,884, Cl. 360-121.000.
Amrhein, Herbert, to Siemens Aktiengesellschaft. Control console. 4,293,764, Cl. 200-302.000.
Anchor Building Products Limited: See—
Hammond, Leslie G., 4,292,785, Cl. 53-399.000.
Anderson, Andrew W., to Scandia Packaging Machinery Co. Conveyor assembly for a wrapping machine. 4,293,067, Cl. 198-851.000.
Anderson, J. Edward C., to Marquette Metal Products Co. Manually-actuated rotary-impact tool. 4,293,044, Cl. 173-93.500.
Anderson, Kjell, to Seco Tools AB. Device for transferring fluid to a rotating unit. 4,293,251, Cl. 408-59.000.
Andersson, Kjell R.; and Johansson, Hans E., to Elektrokemiska Aktiebolaget. Needle-punch carpet with binder containing alkali-stabilized silicic acid. 4,293,612, Cl. 428-281.000.
Andersson, Roland J. E.: See—
Riede, Gerhard; Larsson, Lars-Ake L.; Andersson, Roland J. E.; Jossan, Sven A.; and Traven, Lars J. C., 4,293,409, Cl. 210-96.200.
Andrews, Gerald D., to Du Pont de Nemours, E. I., and Company. Diethyl methacrylates. 4,293,674, Cl. 526-327.000.
Anglo-American Clays Corporation: See—
Lewis, Herbert I.; McConnell, Anthony D.; and Price, William M., 4,293,097, Cl. 241-16.000.
Anisimov, Vyacheslav I.: See—
Trishevsky, Igor S.; Trishevsky, Oleg I.; Bost, Vladimir N.; Deber-deev, Rustem J.; Radjuevich, Leonid V.; Anisimov, Vyacheslav I.; Plesnetsov, Yuri A.; and Chukhno, Valery V., 4,292,830, Cl. 72-197.000.
Annelod, Weimar A.: See—
Millgardh, Ulf J.; Lindberg, Ulf W.; Annelod, Weimar A.; Werner, Nils H.; and Wilmelius, Bjorn, 4,293,607, Cl. 428-212.000.
Annesberg Associates N.V.: See—
Berger, Gordon, 4,292,696, Cl. 4-505.000.
Ansley, Incorporated: See—
Newton, John C., Jr., 4,292,770, Cl. 51-170.0PT.
Anzai, Shunichi: See—
Kobayashi, Nariyoshi; Sakamoto, Takeshi; Anzai, Shunichi; and Matsumoto, Manabu, 4,293,275, Cl. 416-97.00R.
Aoki, Harumi; Kawasaki, Masahiro; and Sawada, Yoshio, to Asahi Kogaku Kogyo Kabushiki Kaisha. Camera focus detecting device. 4,293,207, Cl. 354-25.000.
Aoki, Harumi: See—
Tokutomi, Seiji; Jyojiki, Masao; Aoki, Harumi; Nakamura, Kazuo; and Watanabe, Koichiro, 4,293,206, Cl. 354-25.000.
Aoto, Yoshiyuki: See—
Itogawa, Ziro; and Aoto, Yoshiyuki, 4,292,985, Cl. 132-9.000.
Appel, Douglas C.: See—
Babish, John A.; Arnot, Larry K.; and Appel, Douglas C., 4,293,031, Cl. 165-95.000.
Applegate, Lynn E.; and Brown, Charles J., Jr., to Du Pont de Nemours, E. I., and Company. Treatment of reverse osmosis membranes. 4,293,420, Cl. 210-500.200.
Applied Technologies Associates: See—
Van Steenwyk, Donald H., 4,293,046, Cl. 175-45.000.
Arai, Hajime: See—
Kako, Hiroyoshi; and Arai, Hajime, 4,292,860, Cl. 74-665.0GA.
Arai, Katsuyuki: See—
Matsui, Kiyoshi; Arai, Katsuyuki; and Shinbashi, Suet, 4,293,891, Cl. 361-383.000.
Arbir, Francis W.: See—
Raden, Daniel S.; and Arbir, Francis W., 4,293,658, Cl. 521-129.000.
Arena, Joseph P. Support for traversing window covering device. 4,293,021, Cl. 160-178.00R.
Arena, Salvador. Method for continuous casting of metal strips. 4,293,022, Cl. 164-476.000.
Arendt, Ronald H., to General Electric Company. Molten salt synthesis of alkaline earth titanates, zirconates and their solid solutions. 4,293,534, Cl. 423-593.000.
Arendt, Ronald H., to General Electric Company. Molten salt synthesis of alkaline zirconate powder. 4,293,535, Cl. 423-593.000.
Arikawa, Hiroo, to San-O Industrial Co., Ltd. Electrical fuse with an improved fusible element. 4,293,836, Cl. 337-290.000.
Armstrong Cork Company: See—
Tricca, Raymond A., 4,293,173, Cl. 339-38.000.
Arnot, Larry K.: See—
Babish, John A.; Arnot, Larry K.; and Appel, Douglas C., 4,293,031, Cl. 165-95.000.
Arrigoni-Martelli, Edoardo: See—
Rachlin, Schneur; and Arrigoni-Martelli, Edoardo, 4,293,549, Cl. 424-245.000.
Asada, Eiichi; Inokuma, Toshio; and Egawa, Isao, to Shoei Chemical Incorporated. Thick film resistor. 4,293,839, Cl. 338-309.000.
Asahi Glass Company, Ltd.: See—
Tamamura, Ryo; and Kutsukake, Yukinori, 4,293,335, Cl. 75-124.000.
Asahi Kogaku Kogyo Kabushiki Kaisha: See—
Aoki, Harumi; Kawasaki, Masahiro; and Sawada, Yoshio, 4,293,207, Cl. 354-25.000.
Kando, Toru; and Morisawa, Taihei, 4,293,210, Cl. 354-269.000.
Kobayashi, Koichi; and Okudaira, Sadao, 4,293,197, Cl. 350-454.000.
Kurei, Hiroshi, 4,293,209, Cl. 354-153.000.
Tokutomi, Seiji; Jyojiki, Masao; and Nakamura, Kazuo, 4,293,205, Cl. 354-23.00D.
Tokutomi, Seiji; Jyojiki, Masao; Aoki, Harumi; Nakamura, Kazuo; and Watanabe, Koichiro, 4,293,206, Cl. 354-25.000.
Asakawa, Yukio, to Hitachi, Ltd. Digital differential analyzer with an increment output function. 4,293,918, Cl. 364-702.000.
Asano, Kiro; Tamura, Humio; Nezu, Yushi; Saito, Tsuyoshi; and Kawai, Yoshio, to Kureha Kagaku Kogyo Kabushiki Kaisha. Method for producing solid carbon material having high flexural strength. 4,293,533, Cl. 423-449.000.
Asano, Noriyuki: See—
Tsunekawa, Tokuchichi; Masunaga, Makoto; Hosoe, Kazuya; Niwa, Yukichi; Owada, Mitsutoshi; and Asano, Noriyuki, 4,293,877, Cl. 358-213.000.
ASEA Aktiebolag: See—
Lundren, Jan, 4,293,773, Cl. 250-506.000.
Ash, David J.: See—
Silva, Roy; Ash, David J.; and Scheible, Clement E., 4,293,572, Cl. 426-19.000.
Ash, Harold T.: See—
Abatti, Cinto A.; and Ash, Harold T., 4,292,784, Cl. 53-391.000.
Ashcraft, Thomas L.: See—
Gale, Walter W.; Puerto, Maura C.; Ashcraft, Thomas L.; Saunders, Rhoderick K.; and Reed, Ronald L., 4,293,428, Cl. 252-8.55D.
Ashland Oil, Inc.: See—
Martin, Ralph D.; Dunnivant, William R.; Sturtz, Gregory P.; and Langer, Heimo J., 4,293,480, Cl. 260-38.000.
Asp, Donald J. Combination forced air furnace and air cooler. 4,293,032, Cl. 165-101.000.
Astarita, Domenico: See—
Senni, Paolo; and Astarita, Domenico, 4,293,494, Cl. 260-239.30A.
Atara Corporation: See—
Lipert, Peter, 4,293,506, Cl. 261-77.000.
Atia, Ali E. E.; Berman, Arnold L.; and Mahle, Christoph, to Communications Satellite Corporation. Multichannel correlation receiver for determining depolarization of signals along signal propagation paths. 4,293,945, Cl. 370-17.000.
Atlantic Richfield Company: See—
Ohlswager, Stanley; Edison, Robert R.; and Dresser, Thorpe, 4,293,025, Cl. 165-1.000.
Aubry, Jacques A., to Societe Nationale Ind. Aerospatiale. Supple mounting arrangement for helicopter rotor with through strip. 4,293,277, Cl. 416-134.00A.
Aucktor, Erich: See—
Sandstrom, Anders; and Aucktor, Erich, 4,293,304, Cl. 440-83.000.
Auger, Arnold J. Dubbing winder. 4,292,797, Cl. 57-24.000.
Aziz, Victor; and Spector, George. Watch stand. 4,293,943, Cl. 368-316.000.
Babish, John A.; Arnot, Larry K.; and Appel, Douglas C., to Wynn Oil Company. Engine cooling system flushing apparatus and method. 4,293,031, Cl. 165-95.000.
Bach, Hartwig C.; and Hinderer, Helmut E., to Monsanto Company. Acrylic fiber having improved basic dyeability. 4,293,613, Cl. 428-364.000.
Bachem, Christian, to Albin Sprenger KG GmbH & Co. Air pressure transmitter. 4,292,850, Cl. 73-702.000.
Bachl, Herbert, to Getewent Gesellschaft fur technische und Wissenschaftliche Energieumsatzentwicklungen m.b.H. Fluid-flow machine. 4,293,278, Cl. 416-186.00R.
Bagdis, Judy, to Polaroid Corporation. Prebias for digital light integrator. 4,293,208, Cl. 354-29.000.
Bailey, David C.; and Keesler, Floyd F., to Harris Corporation. System for automatically loading planar film sheets onto a film positioning device. 4,293,124, Cl. 271-233.000.
Bailey, John M., to Caterpillar Tractor Co. Apparatus for controlling the quantity of fuel delivery to an engine and engine timing. 4,292,940, Cl. 123-387.000.
Baizer, Manuel M.: See—
Hallcher, Richard C.; Goodin, Richard D.; and Baizer, Manuel M., 4,293,392, Cl. 204-59.00R.
Hallcher, Richard C.; Goodin, Richard D.; and Baizer, Manuel M., 4,293,393, Cl. 204-59.00R.
Baker International Corporation: See—
Evans, Robert W., 4,293,038, Cl. 166-331.000.
Balaban, Alvin R.: See—
Steckler, Steven A.; and Balaban, Alvin R., 4,293,870, Cl. 358-10.000.
Baldwin, Edwin L. Collision avoidance warning system. 4,293,857, Cl. 343-6.50R.
Baldwin Piano & Organ Company: See—
Jones, Edward M.; and Simmons, Carlton J., Jr., 4,292,874, Cl. 84-1.030.
Balke, Roy L.: See—
Zdaniewski, Joseph J.; Penn, William B.; and Balke, Roy L., 4,293,784, Cl. 310-45.000.
Ball Corporation: See—
Lowe, Earl L., 4,293,004, Cl. 137-884.000.
Ballestra Chemica, S.p.A.: See—
Bertini, Fausto A.; and Noe, Sergio, 4,293,318, Cl. 55-85.000.
Banka, Vidya S. Right ventricular injection catheter; right ventricular angiographic method; and method of monitoring septal wall motion. 4,292,976, Cl. 128-656.000.

Bany, Stephen W.: See—
Blachunis, Robert J.; and Bany, Stephen W., 4,293,675, Cl. 528-14.000.
Barello, Lawrence J.: See—
Carpenter, Edward J.; Korff, William W.; Zoerb, Alan E., deceased; Barello, Lawrence J.; Hall, Donald R.; and Becker, Orlien N., 4,293,915, Cl. 364-493.000.
Barendregt, Frank; and Boogaard, Leendert A., to Stork Brabant B.V. Method and a device for producing separation images having the effect of being orthogonally screened. 4,293,873, Cl. 358-75.000.
Barker, Craig S.; and Bockwinkel, Joe L., to Shakertown Corporation. Staggered butt sidewall shingle panel and method of making the same. 4,292,780, Cl. 52-541.000.
Barnes, Paul R.; and Shapira, Hanna B., to United States of America, Energy. Reflective insulating blinds for windows and the like. 4,292,763, Cl. 49-64.000.
Barnett, Loren A. Liquid proportioning container. 4,292,846, Cl. 73-427.000.
Baron, Martin; and Retterer, Ronald J. Game device. 4,293,133, Cl. 273-345.000.
Barrett, Edward E.; Hahn, Steven; Lensky, Albert; Pinczewski, Morris; and Sobelman, Seymour, to Swingline Inc. Electronically operated portable fastener driving tool. 4,293,088, Cl. 227-131.000.
Barrineau, Wade H. Shelf system. 4,292,902, Cl. 108-146.000.
Barton, Edwin A.: See—
White, Thomas M.; Barton, Edwin A.; and Ware, Jesse P., 4,293,011, Cl. 144-3.00R.
BASF Aktiengesellschaft: See—
Hahn, Klaus; Naarmann, Herbert; and Penzien, Klaus, 4,293,656, Cl. 521-88.000.
Laurer, Peter R., 4,293,448, Cl. 252-463.000.
Nissen, Dieter; Marx, Matthias; Jarre, Wolfgang; Schoen, Ernst; and Decker, Walter, 4,293,657, Cl. 521-121.000.
Portugall, Michael; Finkelmann, Heino; and Ringsdorf, Helmut, 4,293,435, Cl. 252-299.010.
Battery Engineering, Inc.: See—
Marincic, Nikola; and Epstein, James, 4,293,622, Cl. 429-50.000.
Bauer, Werner R., to Robertshaw Controls Company. Method of making reversing valve construction and parts therefor. 4,292,720, Cl. 29-157.10R.
Baumann, Hans, to Sulzer Brothers Limited. Holding device for the electrical contact elements of a wrap stop motion of a weaving machine. 4,293,007, Cl. 139-358.000.
Baumgartner, Hans, to BBC Brown, Boveri & Company, Limited. Waterproof watch and method for making. 4,293,942, Cl. 368-280.000.
Baumgartner, Hans U.: See—
Maag, Willi; Baumgartner, Hans U.; Vollenweider, Max; and Wolf, Hans J., 4,292,769, Cl. 51-169.000.
Baun, Kenneth W., to Burroughs Corporation. Peripheral dependent circuit for peripheral controller. 4,293,928, Cl. 364-900.000.
Baur, Rudolf; Merki, Emil; and Krahenbuhl, Hanspeter, to Swiss Aluminium Ltd. Process for cleaning rolling lubricant. 4,293,424, Cl. 210-737.000.
Baxter, Andrew J. G.: See—
Ponsford, Roger J.; Baxter, Andrew J. G.; and Southgate, Robert, 4,293,501, Cl. 260-430.000.
Baxter Travenol Laboratories, Inc.: See—
Caruso, Stephen; and Dighe, Kamalakar D., 4,293,222, Cl. 356-319.000.
Schnell, William J., 4,293,413, Cl. 210-188.000.
Bayer Aktiengesellschaft: See—
Beck, Gunther; Heitzer, Helmut; and Lurssen, Klaus, 4,293,331, Cl. 71-118.000.
Dieterich, Dieter; and Markusch, Peter, 4,293,474, Cl. 260-29.2TN.
Hamprecht, Rainer; Hartmann, Alfons; Klauke, Erich; Hammann, Ingeborg; Roessler, Peter; and Brandes, Wilhelm, 4,293,566, Cl. 424-304.000.
Heydenreich, Frieder; Korber, Helmut; Tacke, Peter; Fahnler, Friedrich; and Neuray, Dieter, 4,293,662, Cl. 525-184.000.
Kinast, Gunther; Muller, Lutz; Puls, Walter; and Sitt, Rudiger, 4,293,551, Cl. 424-249.000.
Kramer, Wolfgang, 4,293,715, Cl. 564-256.000.
Mazanek, Jan; and Nuller, Hanns P., 4,293,680, Cl. 528-67.000.
Probst, Joachim; Sonntag, Michael; and Kolb, Gunter, 4,293,661, Cl. 525-127.000.
Reischl, Artur, 4,293,456, Cl. 260-9.000.
Rottmaier, Ludwig; Merten, Rudolf; Lewalter, Jurgen; Zecher, Wilfried; and Dunwald, Willi, 4,293,669, Cl. 525-452.000.
Waldmann, Helmut; Schwerdtel, Wulf; and Swodenk, Wolfgang, 4,293,717, Cl. 568-485.000.
Weissel, Oskar; Serini, Volker; and Buysch, Hans-Josef, 4,293,687, Cl. 528-346.000.
BBC Brown, Boveri & Company, Limited: See—
Baumgartner, Hans, 4,293,942, Cl. 368-280.000.
Germann, Willy, 4,292,828, Cl. 72-54.000.
Starcevic, Mihailo, 4,293,786, Cl. 310-157.000.
Beach, David L.; and Harrison, James J., to Gulf Research & Development Company. Nickel ylides. 4,293,502, Cl. 260-439.00R.
Beach, David L.; and Kobylinski, Thaddeus P., to Gulf Research & Development Company. Alkylation of aromatics with propylene and higher olefins. 4,293,724, Cl. 585-457.000.
Beach, David L.; and Kobylinski, Thaddeus P., to Gulf Research & Development Company. Use of metal modified refractory metal oxide/silica supported nickel cluster catalyst to oligomerize ethylene. 4,293,725, Cl. 585-523.000.
Beach, David L.; and Kobylinski, Thaddeus P., to Gulf Research & Development Company. Process for the oligomerization of propylene and higher olefins. 4,293,726, Cl. 585-523.000.
Beach, David L.; and Harrison, James J., to Gulf Research & Development Company. Process for the oligomerization of ethylene. 4,293,727, Cl. 585-526.000.
Beam, Clark W.: See—
Parks, Glenn C., Jr.; and Beam, Clark W., 4,293,115, Cl. 251-1.00A.
Beavan, Elton L.; and Moynahan, E. Bradley, to GAF Corporation. In photographic emulsion adhesion to a polyester film base. 4,293,642, Cl. 430-534.000.
Beavers, Allan E., to T. A. Pelsue Company. Canopy assembly for patched radar domes. 4,293,862, Cl. 343-872.000.
Beck, Gunther; Heitzer, Helmut; and Lurssen, Klaus, to Bayer Aktiengesellschaft. Novel acyloxamides and plant growth regulant compositions. 4,293,331, Cl. 71-118.000.
Becker, Orlien N.: See—
Carpenter, Edward J.; Korff, William W.; Zoerb, Alan E., deceased; Barello, Lawrence J.; Hall, Donald R.; and Becker, Orlien N., 4,293,915, Cl. 364-493.000.
Becker, Reinhold, to Hoechst Aktiengesellschaft. Process for the simultaneous filling and turning of a tubular casing with an outside coating. 4,292,711, Cl. 17-49.000.
Becton, Dickinson and Company: See—
Percarpio, Edward P.; and Holderith, William J., 4,293,078, Cl. 215-247.000.
Beecham Group Limited: See—
Ponsford, Roger J.; Baxter, Andrew J. G.; and Southgate, Robert, 4,293,501, Cl. 260-430.000.
Beers, M. Dale: See—
Smith, Alfred H., Jr.; and Beers, M. Dale, 4,293,616, Cl. 428-447.000.
Begunov, Petr M.: See—
Ragoza, Igor V.; Begunov, Petr M.; Tonikian, Robert T.; and Vasiljuk, Petr J., 4,292,820, Cl. 66-8.000.
Belanger, Guy; and Missout, Gilles, to Hydro-Quebec. Device for detecting and measuring the concentration of gaseous hydrogen dissolved in a fluid. 4,293,399, Cl. 204-195.00P.
Bell, Stanley C.: See—
Wei, Peter H. L.; and Bell, Stanley C., 4,293,696, Cl. 546-83.000.
Bell, Ted A.; and Lehner, Daniel F., to Pretty Products, Inc. Automobile splash guard and attachment means therefor. 4,293,140, Cl. 280-154.50R.
Bell Telephone Laboratories, Incorporated: See—
Huang, Victor K.; and Ruth, Richard L., 4,293,907, Cl. 364-200.000.
Bell, William T.; and Garcia, Jose B., to Schlumberger Technology Corporation. Explosive safe-arming apparatus for perforating guns. 4,292,895, Cl. 102-306.000.
Belozorov, Nikolai P.: See—
Dunsevsky, Vladimir I.; Boidenko, Nikolai G.; Samarin, Alexei P.; Levit, Viktor M.; Zapara, Boris M.; Ivanov, Boris N.; Frolov, Sergei A.; Voronin, Rostislav A.; Belozorov, Nikolai P.; Momot, Valery I.; Stusenko, Yuri A.; and Samoilov, Vladimir A., 4,293,101, Cl. 242-56.400.
Ben Gurion Industries Ltd.: See—
Hadari, Gideon, 4,293,840, Cl. 340-27.0AT.
Benckiser-Knapsack GmbH: See—
Sommer, Klaus; Klemm, Walter; Weber, Hermann; Meinhardt, Friedrich; Schonmann, Gerhard; and Spatz, Wilhelm, 4,293,526, Cl. 422-205.000.
Bendig, Lothar, to Filterwerk Mann & Hummel GmbH. Electronically controlled combustion air mixing valve for internal combustion engines. 4,292,949, Cl. 123-556.000.
Bendix Corporation, The: See—
Brown, Arthur K., 4,293,061, Cl. 192-67.00R.
Brown, Arthur K., 4,293,139, Cl. 280-6.00H.
Benfield Corporation: See—
Field, Joseph H.; and McCrea, Donald H., 4,293,531, Cl. 423-232.000.
Bente, Paul F., III; Zerenner, Ernest H.; and Dandaneau, Raymond D., to Hewlett-Packard Company. Silica chromatographic column. 4,293,415, Cl. 210-198.200.
Beranek, Miroslav. Guard for tennis rackets and like articles. 4,293,130, Cl. 273-73.00R.
Berger, Gordon, to Annesberg Associates N.V. Swimmer arrival signal panels incorporated in a swimming pool bulkhead. 4,292,696, Cl. 4-505.000.
Berger, Jean L., to Thomson-CSF. Transversal charge transfer filter. 4,293,832, Cl. 333-165.000.
Berghofer, Hans. Flexible pipe-connecting fitting. 4,293,152, Cl. 285-229.000.
Bergkvist, Jorgen, to Stal-Laval Turbin AB. Combined air and fuel nozzle for fluidized bed combustion chamber. 4,293,298, Cl. 432-58.000.
Berman, Arnold L.: See—
Atia, Ali E. E.; Berman, Arnold L.; and Mahle, Christoph, 4,293,945, Cl. 370-17.000.
Bernady, Karel F.; Floyd, Middleton B., Jr.; Poletto, John F.; Schaub, Robert E.; and Weiss, Martin J., to American Cyanamid Company. Novel 2-substituted-3,4-epoxycyclopentan-1-ones, 2-substituted-3,4-epoxycyclopentan-1-ols, and various 2-substituted-cyclopentenones. 4,293,704, Cl. 556-442.000.
Bernat, Georg, to Friedrich Grohe Armaturenfabrik GmbH & Co. Cartridge valve. 4,292,997, Cl. 137-454.600.

- Bertholet, Raymond: See—
Hirsbrunner, Pierre; and Bertholet, Raymond, 4,293,581, Cl. 426-630.000.
- Bertini, Fausto A.; and Noe, Sergio, to Ballestra Chemica, S.p.A. Wet purification of gaseous mixtures containing detergent powders in suspension. 4,293,318, Cl. 55-85.000.
- Bertoloni, Luciano; Rogora, Edoardo; and Cressoni, Ermanno, to Alfa Romeo S.p.A. Motorcar dashboard. 4,293,843, Cl. 340-52.00F.
- Bessmer, Stanley J.; and Lampe, Warren R., to General Electric Company. Method of forming a roofing composite using silicone rubber composition. 4,293,597, Cl. 427-186.000.
- Bethay, Willis D., Jr., to Du Pont de Nemours, E. I., and Company. Control of synthetic yarns during drawing with heated rolls. 4,293,518, Cl. 264-210.200.
- Bexford Limited: See—
Huffey, Roy F.; and Pope, John A., 4,293,633, Cl. 430-152.000.
- Beyl, Earl, Jr. Sound actuator. 4,293,851, Cl. 340-384.00E.
- Beyler, Arvil L.: See—
Pap, Joe P.; Pap, Marilyn D.; Beyler, Arvil L.; and Beyler, Doris M., 4,293,162, Cl. 297-184.000.
- Beyler, Doris M.: See—
Pap, Joe P.; Pap, Marilyn D.; Beyler, Arvil L.; and Beyler, Doris M., 4,293,162, Cl. 297-184.000.
- Beynet, Pierre A.; Lucksinger, James E.; and Jansen, Martin B., Jr., to Standard Oil Company (Indiana). VMP Casing tieback. 4,293,146, Cl. 285-24.000.
- BFG Glassgroup: See—
Terneu, Robert; and Van Cauter, Albert, 4,293,326, Cl. 65-60.00D.
- Bhide, Yeshwant K., to Allis-Chalmers Corporation. Valve for handling solids capable of gas-pressure-tight closure against a gas pressure differential. 4,292,992, Cl. 137-340.000.
- Bible, Dennis E.; Crano, Richard N.; and Welch, John A., to General Tire & Rubber Co., The. Pneumatic tire assembly. 4,293,016, Cl. 152-158.000.
- Bickel, Hans: See—
Woodward, Robert B.; and Bickel, Hans, 4,293,462, Cl. 260-239.00A.
- Bickford, John H., to Raymond Engineering, Inc. Calibration apparatus and method for strain measuring instruments. 4,292,835, Cl. 73-1.00B.
- Biggs, Candice B.: See—
Wovcha, Merle G.; and Biggs, Candice B., 4,293,644, Cl. 435-55.000.
- Wovcha, Merle G.; Biggs, Candice B.; and Pyke, Thomas R., 4,293,645, Cl. 435-55.000.
- Bik, Joannes D.: See—
Zeistra, Jacobus J.; de Klein, Willem J.; and Bik, Joannes D., 4,293,345, Cl. 106-270.000.
- Binder, Georg, to Robert Bosch GmbH. Three-phase vehicular generator construction. 4,293,788, Cl. 310-227.000.
- Bingaman, David E.: See—
Robey, Melvin J.; Bingaman, David E.; and Read, Arthur E., 4,293,237, Cl. 405-39.000.
- Bio-Melktechnik Swiss Hoefelmayer & Co.: See—
Tilman, Hoefelmayer, 4,292,926, Cl. 119-14.020.
- Bioul, Gery J. A.: See—
Davio, Marc; and Bioul, Gery J. A., 4,293,922, Cl. 364-757.000.
- Bird, Alvin N., Jr.; Francis, Norman L.; and Thomas, Albert L., Jr., to United States of America, Army. Continuous-flow condensation nuclei counter and process. 4,293,217, Cl. 356-37.000.
- Birkenmeyer, Robert D.: See—
Lewis, Charles; and Birkenmeyer, Robert D., 4,293,547, Cl. 424-180.000.
- Bisenix, Egils A.: See—
Uldriks, Yan R.; Preisa, Ieva E.; Dubur, Gunar Y.; Zidermane, Aina A.; Bisenix, Egils A.; and Tirzits, Gunar D., 4,293,700, Cl. 546-321.000.
- Bison-werke Bahre & Greden GmbH & Co. KG: See—
Bucking, Gunter, 4,293,509, Cl. 264-26.000.
- Bjorklund, Bjorn A., to AB Svenska Flackfabriken, Fack. Procedure for converting low-grade thermal energy into mechanical energy in a turbine for further utilization and plant for implementing the procedure. 4,292,809, Cl. 60-676.000.
- Blachunis, Robert J.; and Bany, Stephen W., to Minnesota Mining and Manufacturing Company. Antimony halide-organic phosphonate ester cationic polymerization catalysts. 4,293,675, Cl. 528-14.000.
- Black, Craig A.: See—
Struger, Odo J.; Brown, Ronald A.; and Black, Craig A., 4,293,924, Cl. 364-900.000.
- Blaich, Dieter: See—
Reinhard, Theodor; Krugener, Rolf; Kurth, Hermann W.; Blaich, Dieter; Rothmaier, Franz; Kopperschlager, Dieter; Schmitz, Heinz; and Nill, Edgar, 4,292,823, Cl. 70-364.00R.
- Blank, Nolan D. Battery operated illuminating device. 4,293,894, Cl. 362-100.000.
- Blessing, Hubert, to Levi Strauss & Co. Hemmer-seamer. 4,292,908, Cl. 112-306.000.
- Block, Barry, to Aine, Harry E., a part interest. Inlet system for a gas analyzer. 4,293,316, Cl. 55-16.000.
- Blumbach, Jurgen; Durckheimer, Walter; and Schrinner, Elmar, to Hoechst Aktiengesellschaft. Cephalosporin derivatives. 4,293,550, Cl. 424-246.000.
- Blumhardt, Rolf: See—
Hatz, Ernst; Eibl, Heinz; Peter, Erwin; and Blumhardt, Rolf, 4,293,092, Cl. 237-12.100.
- Bobchenok, Meri I.: See—
Kuzin, Eduard N.; Korelin, Vladimir F.; Fainzilber, Mikhail L.; Egorov, Jury P.; Erofenko, Igor V.; Karev, Nikolai V.; Kozlov, Jury S.; Kudish, Viktor B.; Kolbasov, Valery K.; and Bobchenok, Meri I., 4,293,238, Cl. 405-175.000.
- Bockwinkel, Joe L.: See—
Barker, Craig S.; and Bockwinkel, Joe L., 4,292,780, Cl. 52-541.000.
- Boehringer Ingelheim GmbH: See—
Merz, Herbert; and Stockhaus, Klaus, 4,293,556, Cl. 424-267.000.
- Stahle, Helmut; Koppe, Herbert; Kummer, Werner; Hoeffke, Wolfgang; Gaida, Wolfram; and Pichler, Ludwig, 4,293,564, Cl. 424-273.00R.
- Boeing Company, The: See—
Middleton, Wilbur D.; and Paulson, John A., 4,293,110, Cl. 244-199.000.
- Boer, Werner; Lachner, Hans; Maschon, Guenter; Richter, Joerg; Schulte, Heinrich; and Warnke, Hans, to Klockner-Werke AG. Mine roof support structure. 4,293,246, Cl. 405-291.000.
- Boidenko, Nikolai G.: See—
Dunaevsky, Vladimir I.; Boidenko, Nikolai G.; Samarin, Alexei P.; Levit, Viktor M.; Zapara, Boris M.; Ivanov, Boris N.; Frolov, Sergei A.; Voronin, Rostislav A.; Belozero, Nikolai P.; Momot, Valery I.; Stusenko, Jury A.; and Samoilov, Vladimir A., 4,293,101, Cl. 242-56.400.
- Bolhofer, William A., to Merck & Co., Inc. Imidazole or imidazoline substituted ureas. 4,293,703, Cl. 548-337.000.
- Bolie, Victor W. Vertical axis wind turbine. 4,293,279, Cl. 416-227.00A.
- Bolton, Theodore S., to Carrier Corporation. Door assembly for a self-contained air conditioning unit. 4,292,815, Cl. 62-262.000.
- Bom, Cornelis J. G.: See—
van der Lely, Ary; and Bom, Cornelis J. G., 4,292,819, Cl. 64-28.00R.
- Bona, Istvan: See—
Pataki, Jozsef; Bucsi, Jozsef; Bona, Istvan; Szilvasi, Endre; Gazdag, Andras; Koty, Antal; and Hidvegi, Ferenc, 4,292,996, Cl. 137-393.000.
- Bonel, Federico A., to Industrias Neoplast, S.A. Rapid coupling for plastic pipes. 4,293,149, Cl. 285-111.000.
- Bonner, Alvin T., Sr., to John D. Hollingsworth on Wheels, Inc. Card coiler can changer. 4,292,712, Cl. 19-159.00A.
- Bonneyrat, Alain M.: See—
Foster, George W.; and Bonneyrat, Alain M., 4,293,807, Cl. 318-696.000.
- Boogaard, Leendert A.: See—
Barendregt, Frank; and Boogaard, Leendert A., 4,293,873, Cl. 358-75.000.
- Borg, Paul E.; and Lechinger, Terry M., to PRE Corporation. Trailer mounted high floor drilling mast and substructure arrangement. 4,292,772, Cl. 52-118.000.
- Borland, Montague C.: See—
Hochberg, Lindsey S.; and Borland, Montague C., 4,293,823, Cl. 330-260.000.
- Borrer, Jack A.; and Rowe, Edward A., Jr., to Diamond Shamrock Corporation. Perchloroethylene dielectric fluid containing pyrrole and phenol. 4,293,433, Cl. 336-94.000.
- Bosy, Vladimir N.: See—
Trishevsky, Igor S.; Trishevsky, Oleg I.; Bosy, Vladimir N.; Deberdeev, Rustem J.; Radjukevich, Leonid V.; Anisimov, Vyacheslav I.; Plesnetsov, Jury A.; and Chukhno, Valery V., 4,292,830, Cl. 72-197.000.
- Bott, John A. Flexible wind deflector. 4,293,159, Cl. 296-91.000.
- Boudouris, Angelo; and Peters, Edwin F., to Eprad Incorporated. Audio channel separating apparatus. 4,293,821, Cl. 330-126.000.
- Boveri, Sergio: See—
Pedrazzoli, Andrea; and Boveri, Sergio, 4,293,560, Cl. 424-271.000.
- Bowen, Griffith; and Fowell, Peter A., to Du Pont de Nemours, E. I., and Company. Polyvinyl butyral laminates. 4,293,615, Cl. 428-412.000.
- Bowers, James C.: See—
Brooks, James L.; Bowers, James C.; and Nienhaus, Harry A., 4,293,904, Cl. 363-86.000.
- Bowles, John P.: See—
Jasmin, Gilles; and Bowles, John P., 4,293,923, Cl. 364-802.000.
- Boyer, Wesley D., to Ford Motor Company. Crankshaft position sensor circuitry for providing stable cyclical output signals without regard to peak to peak variations in sensor signals. 4,293,814, Cl. 324-166.000.
- Braaten, Ronald J. Foot operated control unit. 4,293,746, Cl. 200-86.500.
- Brachet, Alain, to Electricite de France (Service National). Secondary coolant circuit for nuclear-reactors. 4,293,385, Cl. 376-283.000.
- Braddick, Britt O., to Texas Iron Works, Inc. Valve for closing the fluid passage of a well bore tubular member with balanced operating arrangement. 4,293,163, Cl. 251-283.000.
- Bradley, John J.; Holtey, Thomas O.; Miller, Robert C.; Miu, Ming T.; Shen, Jian-Kuo; and Staplin, Theodore R., Jr., to Honeywell Information Systems Inc. Data processing system having direct memory access bus cycle. 4,293,908, Cl. 364-200.000.
- Bradley, Lindell P.: See—
Bradley, Robert F.; and Bradley, Lindell P., 4,292,916, Cl. 116-205.000.
- Bradley, Robert F.; and Bradley, Lindell P., to Micro-Circuits Company. Timer and storage condition indicator. 4,292,916, Cl. 116-205.000.
- Bradley, Robert L., Jr.; and Hekmati, Majid, to Wisconsin Alumni Research Foundation. Preparation of frozen yogurt. 4,293,573, Cl. 426-43.000.
- Bragg, Ralph J.: See—
Dudley, Hubert T.; and Bragg, Ralph J., 4,293,341, Cl. 106-88.000.

- Bramwell, Frank, to United States of America, Navy. Pivotal cable guard for retaining a swingable-movable cable. 4,293,109, Cl. 244-17.110.
- Brandenstein, Manfred: See—
Ernst, Horst M.; Olschewski, Armin; Schurger, Rainer; Walter, Lothar; Brandenstein, Manfred; and Burkl, Erich, 4,293,166, Cl. 308-6.00C.
- Brandes, Wilhelm: See—
Hamprecht, Rainer; Hartmann, Alfons; Klauke, Erich; Hammann, Ingeborg; Roessler, Peter; and Brandes, Wilhelm, 4,293,566, Cl. 424-304.000.
- Brandt, Cecil R. Furnace and boiler system and method of operation thereof. 4,292,904, Cl. 110-198.000.
- Brann, Theodore L.: See—
Stanback, Harris I.; Brann, Theodore L.; and Polston, Larry D., 4,293,153, Cl. 292-85.000.
- Braun, Anton. Heat pump. 4,292,814, Cl. 62-243.000.
- Braun, Stellan, to AGA Aktiebolag. Arrangement in a burner. 4,293,096, Cl. 239-419.300.
- Brawley, Thomas S. Machine for abrading outside diameters and the method of making same. 4,292,765, Cl. 51-103.0TF.
- Bremer, Noel J.: See—
Lemanski, Michael F.; Bremer, Noel J.; and Milberger, Ernest C., 4,293,498, Cl. 260-346.750.
- Suresh, Dev D.; Bremer, Noel J.; and Grasselli, Robert K., 4,293,443, Cl. 252-432.000.
- Breslow, Jeffrey D.: See—
Jaworski, Eugene; and Breslow, Jeffrey D., 4,292,756, Cl. 46-72.000.
- Brewer, Earl G., to General Motors Corporation. Copper grid for strain analysis of sheet metal deformation. 4,292,851, Cl. 73-762.000.
- Brezosky, Bernard J., to General Electric Company. Thrust bearing assembly. 4,293,170, Cl. 308-161.000.
- Bridges, John A., to Aladdin Industries, Incorporated. Slant stacking tray system. 4,293,071, Cl. 206-503.000.
- Brilando, Frank, to Schwinn Bicycle Company. Frame for lightweight bicycle. 4,293,141, Cl. 280-281.00R.
- Brinker, Reiner G., to Philip Morris Incorporated. Apparatus for perforating hollow cylinders. 4,292,872, Cl. 83-866.000.
- British Gas Corporation: See—
Metcalf, Ronald S.; and Greig, John M., 4,293,147, Cl. 285-39.000.
- Brittain, William J., to Ford Motor Company. Information handling system. 4,293,947, Cl. 370-89.000.
- Britton, Francis D., Jr. Engine valve lifter service tool. 4,292,719, Cl. 29-156.40R.
- Brogdon, Vas H.; and Williams, David L., to Textron Inc. Laminated composite rotor yoke. 4,293,276, Cl. 416-134.00A.
- Bronstein, Allen I. Solar reflector with flexible sheet tightly secured around form surfaces. 4,293,192, Cl. 350-296.000.
- Brooks, George D.; and Bushey, Donald J., Sr., to General Electric Company. Ammunition orientation mechanism. 4,292,878, Cl. 86-48.000.
- Brooks, James L.; Bowers, James C.; and Nienhaus, Harry A., to United States of America, Navy. Power frequency converter. 4,293,904, Cl. 363-86.000.
- Brooks, Kevin E.: See—
Wovcha, Merle G.; and Brooks, Kevin E., 4,293,646, Cl. 435-55.000.
- Broughton, Donald B.: See—
Landis, Arthur M.; Broughton, Donald B.; and Fickel, R. Gene, 4,293,346, Cl. 127-46.00A.
- Brown, Arthur K., to Bendix Corporation. The. Remote controlled hub clutch. 4,293,061, Cl. 192-67.00R.
- Brown, Arthur K., to Bendix Corporation. The. Power steering pump powered load leveler. 4,293,139, Cl. 280-6.00H.
- Brown, Charles J., Jr.: See—
Applegate, Lynn E.; and Brown, Charles J., Jr., 4,293,420, Cl. 210-500.200.
- Brown Company: See—
Haas, Richard G., 4,293,354, Cl. 156-69.000.
- Brown Oil Tools, Inc.: See—
Montgomery, James W., 4,292,988, Cl. 137-68.00R.
- Brown, Ronald A.: See—
Struger, Odo J.; Brown, Ronald A.; and Black, Craig A., 4,293,924, Cl. 364-900.000.
- Brown, Timothy E.: See—
Luchessa, Charles E.; and Brown, Timothy E., 4,292,843, Cl. 73-171.000.
- Bugner, Frank S., Jr., to Square D Company. Silver, cadmium oxide, lithium carbonate contact material and method of making the material. 4,293,337, Cl. 75-232.000.
- Bucher-Guyer AG Maschinenfabrik: See—
Hauser, Hans-Ulrich, 4,292,793, Cl. 56-378.000.
- Bucking, Gunter, to Bison-werke Bahre & Greden GmbH & Co. KG. Process for the production of chipboards, fiberboards, or like boards. 4,293,509, Cl. 264-26.000.
- Buckley, William D., to Perkin-Elmer Corporation. The. Method for making a mask useful in X-ray lithography. 4,293,624, Cl. 430-5.000.
- Buckman, John D.; Buckman, Stanley J.; Johnson, Betty S.; and Pera, John D., to Buckman Laboratories, Inc. Slime control compositions and methods of using the same. 4,293,559, Cl. 424-270.000.
- Buckman Laboratories, Inc.: See—
Buckman, John D.; Buckman, Stanley J.; Johnson, Betty S.; and Pera, John D., 4,293,559, Cl. 424-270.000.
- Buckman, Stanley J.: See—
Buckman, John D.; Buckman, Stanley J.; Johnson, Betty S.; and Pera, John D., 4,293,559, Cl. 424-270.000.
- Bucsi, Jozsef: See—
Pataki, Jozsef; Bucsi, Jozsef; Bona, Istvan; Szilvasi, Endre; Gazdag, Andras; Koty, Antal; and Hidvegi, Ferenc, 4,292,996, Cl. 137-393.000.
- Budnovitch, William F.; Petralia, Salvatore C.; and Silvestris, Louis F., to Keene Corporation. Garden light fixture. 4,293,898, Cl. 362-291.000.
- Budzich, Tadeusz. Load responsive fluid control valve. 4,293,000, Cl. 137-596.200.
- Budzich, Tadeusz. Load responsive fluid control valve. 4,293,001, Cl. 137-596.130.
- Buffalo Color Corporation: See—
Malik, Edward P., 4,293,681, Cl. 528-115.000.
- Buhler, Marcel: See—
Olofsson, Mats; Buhler, Marcel; and Wood, Robert, 4,293,571, Cl. 426-7.000.
- Bula, Russell P., to Du Pont de Nemours, E. I., and Company. Rotatable pallet post for plastic pallets. 4,292,900, Cl. 108-51.100.
- Bullinga, Lothar H., to Rockwell International Corporation. Temperature compensated rotary positioner. 4,293,850, Cl. 340-378.500.
- Bunker Ramo Corporation: See—
Taylor, Derek, 4,293,180, Cl. 339-217.00R.
- Burk, Emmett H., Jr.; Yoo, Jin S.; Karch, John A.; and Sun, Jui-Yuan. Catalyst demetallization by converting the metal poisons to a sulfur containing metal compound having a defined low amount of sulfur. 4,293,403, Cl. 208-120.000.
- Burkl, Erich: See—
Ernst, Horst M.; Olschewski, Armin; Schurger, Rainer; Walter, Lothar; Brandenstein, Manfred; and Burkl, Erich, 4,293,166, Cl. 308-6.00C.
- Burnham, Robert D.: See—
Scifres, Donald R.; Burnham, Robert D.; and Streifer, William, 4,293,826, Cl. 331-94.50H.
- Burrighs Corporation: See—
Baun, Kenneth W., 4,293,928, Cl. 364-900.000.
- Catiller, Robert D.; and Forbes, Brian K., 4,293,909, Cl. 364-200.000.
- Burton, Charles G., to Chisholm-Ryder Company, Inc. Adjustable harvesting machine for blueberries and other plants. 4,292,792, Cl. 56-330.000.
- Burton, John D., to William R. Selwood Limited. Pump. 4,293,285, Cl. 417-240.000.
- Burton, Stanley J., to Fisco Products Limited. Brake. 4,293,058, Cl. 188-65.100.
- Buschor, Josef J.; and Jennings, Frederick R., to Pneumatic Scale Corporation. Paperboard carton. 4,292,787, Cl. 53-456.000.
- Bushey, Donald J., Sr.: See—
Brooks, George D.; and Bushey, Donald J., Sr., 4,292,878, Cl. 86-48.000.
- Bushman, John A.: See—
Williams, Garnet M. E.; Hutton, Stanley P.; and Bushman, John A., 4,292,853, Cl. 73-861.790.
- Bustos, Rafael T., to Leggett & Platt, Inc. Conveyor belt assembly for a display rack. 4,293,062, Cl. 193-2.00D.
- Butcher, Lawrence D. Leaf stripper for tobacco stalks and the like. 4,292,982, Cl. 130-30.00R.
- Butter, Stephen A.; and Chester, Arthur W., to Mobil Oil Corporation. Conversion of synthesis gas with iron-containing catalyst. 4,293,446, Cl. 252-455.00Z.
- Buysch, Hans-Josef: See—
Weissel, Oskar; Serini, Volker; and Buysch, Hans-Josef, 4,293,687, Cl. 528-346.000.
- C M Industries: See—
Pedrazzoli, Andrea; and Boveri, Sergio, 4,293,560, Cl. 424-271.000.
- C. van der Lely N.V.: See—
van der Lely, Ary; and Bom, Cornelis J. G., 4,292,819, Cl. 64-28.00R.
- Cable Conveyor Systems, Inc.: See—
Rauscher, David A., 4,292,723, Cl. 29-402.010.
- Cabot Corporation: See—
Wacker, Albert R., 4,293,355, Cl. 156-73.200.
- Cahen, George L., Jr. Collapsible wing aircraft. 4,292,757, Cl. 46-80.000.
- Caiello, Joseph A.; and Caiello, Ronald J., to Caiello, Joseph A. Apparatus and methods for making cheese topping, and cheese mold assemblies. 4,293,296, Cl. 425-547.000.
- Caiello, Ronald J.: See—
Caiello, Joseph A.; and Caiello, Ronald J., 4,293,296, Cl. 425-547.000.
- Cairns, Hugh; and Lee, Thomas B., to Fisons Limited. Compounds. 4,293,541, Cl. 424-45.000.
- Calderon, Reynaldo, to Texaco Inc. Method of forming and assembling a self-cleaning helical spring screen. 4,293,037, Cl. 166-312.000.
- California Microwave, Inc.: See—
Altstatt, John E., 4,293,956, Cl. 455-327.000.
- Cambier, James L.: See—
Kay, David B.; Wheelless, Leon L., Jr.; and Cambier, James L., 4,293,221, Cl. 356-318.000.
- Campana, Patsie C. Ingot mold reconditioning process. 4,292,726, Cl. 29-527.600.

- Campbell, Billy H.: See—
Lopez, Bennie F.; Campbell, Billy H.; Collier, Bobby D.; Laird, William J.; Debona, Edward J.; and Eubanks, James E., Jr., 4,292,880, Cl. 89-1.815.
- Campbell, Douglas D., to Minnesota Mining and Manufacturing Company. Flocked three-dimensional network mat. 4,293,604, Cl. 428-90.000.
- Campbell, Robert W.; and Hill, H. Wayne, Jr., to Phillips Petroleum Co. Polyamides of 1,4-cyclohexane dicarboxylic acid and 5-methyl-1,9-nonanediamine and fibers thereof. 4,293,688, Cl. 528-346.000.
- Canaris, Valerie M., to Rohco, Inc. Cadmium plating baths and methods for electrodeposition bright cadmium deposits. 4,293,391, Cl. 204-50.00R.
- Candid Logic, Inc.: See—
Vis, Arthur D.; and Feinberg, Billie, 4,292,740, Cl. 33-172.00E.
- Canon Kabushiki Kaisha: See—
Kohayakawa, Yoshimi; Ishikawa, Yasuyuki; and Maruyama, Shigeo, 4,293,198, Cl. 351-13.000.
Minoura, Kazuo; Sugiyama, Muneharu; Minami, Setsuo; and Sato, Tadashi, 4,293,184, Cl. 350-6.300.
Tsunekawa, Tokuchi; Masunaga, Makoto; Hosoe, Kazuya; Niwa, Yukichi; Owada, Mitsutoshi; and Asano, Noriyuki, 4,293,877, Cl. 358-213.000.
- Capella Inc.: See—
Ergaver, Nevenka; and Ergaver, Rayko, 4,292,986, Cl. 132-11.00R.
Caratsch, Hans-Peter. Air foil nozzle dryer. 4,292,745, Cl. 34-156.000.
- Carborundum Company, The: See—
Hortman, Michael T.; and Naum, Robert G., 4,293,598, Cl. 427-203.000.
- Cardenas, Carlos G.; and Din, Zia U., to SCM Corporation. Coupling reaction involving a grignard and allylic halide. 4,293,497, Cl. 260-345.500.
- Cargill, Incorporated: See—
Gordon, Robert; King, Harry A.; Springrose, James V.; and Cud-dihy, Robert W., 4,292,898, Cl. 105-238.00R.
- Carl Still GmbH & Co. KG, Firma: See—
Clement, Heinrich-Josef, 4,293,389, Cl. 202-248.000.
Lorenz, Kurt; Dungs, Horst; Koenigs, Hans B.; and Kurtz, Roman, 4,293,388, Cl. 202-126.000.
- Carlo Erba Strumentazione S.p.A.: See—
Sisti, Giorgio; and Colombo, Bruno, 4,293,308, Cl. 23-230.0PC.
- Carlo Gavazzi S.p.A.: See—
Del Re, Pietrantonio; and Fracassi, Pietro, 4,293,916, Cl. 364-571.000.
- Carlson, Allen J.; and Vander Kaay, Henry A., to Double A Products Company. Power limiting control apparatus for pressure-flow compensated variable displacement pump assemblies. 4,293,284, Cl. 417-218.000.
- Carpenter, Edward J.; Korff, William W.; Zoerb, Alan E., deceased (by Zoerb, Delores E.); Barelo, Lawrence J.; Hall, Donald R.; and Becker, Orlien N., to Pacific Technology, Inc. Programmable electronic real-time load controller. 4,293,915, Cl. 364-493.000.
- Carrens, Donald E., to Dresser Industries, Inc. Reversing valve assembly for a fluid operated well pump. 4,293,287, Cl. 417-393.000.
- Carrier Corporation: See—
Bolton, Theodore S., 4,292,815, Cl. 62-262.000.
Raymond, Glendon A.; Honnold, Fred V.; and Spath, Herbert J., 4,293,093, Cl. 237-19.000.
- Carter, Richard G.; Watson, Stuart L., Jr.; and Pines, Arthur N., to Union Carbide Corporation. Radiation-curable acrylated epoxy silicone compositions. 4,293,678, Cl. 528-32.000.
- Caruso, Stephen; and Dighe, Kamalakar D., to Baxter Travenol Laboratories, Inc. Control apparatus for spectrophotometer. 4,293,222, Cl. 356-319.000.
- Casio Computer Co., Ltd.: See—
Hoshii, Toshifumi, 4,293,927, Cl. 364-900.000.
- Cassells, Melvin K. Safety lock for window sashes and the like. 4,293,154, Cl. 292-144.000.
- Cassidy, John V.: See—
Lindblad, Nero R.; Rezanka, Ivan; and Cassidy, John V., 4,292,924, Cl. 118-658.000.
- Caterpillar Tractor Co.: See—
Bailey, John M., 4,292,940, Cl. 123-387.000.
Goloff, Alexander; and Denning, Ralph E., 4,293,050, Cl. 180-6.260.
Hoefler, Wayne A.; and Tanty, Paul J., 4,293,164, Cl. 303-13.000.
- Catiller, Robert D.; and Forbes, Brian K., to Burroughs Corporation. Digital system for data transfer using universal input-output micro-processor. 4,293,909, Cl. 364-200.000.
- Catozzo, Leo, to Costruzione Incollatrici Rapide C.I.R. S.r.L. Film splicing devices. 4,293,368, Cl. 156-506.000.
- Cattani, Augusto, to Officine Augusto Cattani & C. S.A.S. Liquid separating and evacuating device for fluid suction equipment. 4,293,300, Cl. 433-92.000.
- Cazzaniga, Italo; and Pasquinelli, Ottorino, to Grove Valve and Regulator Company. Fire safe seal. 4,292,989, Cl. 137-72.000.
- Celanese Corporation: See—
Edelman, Robert, 4,293,469, Cl. 260-45.90P.
Hughes, O. Richard, 4,293,499, Cl. 260-410.90R.
- Centra-Burkle GmbH & Co.: See—
Knoll, Alois, 4,293,028, Cl. 165-12.000.
- Central Glass Company, Limited: See—
Sasaki, Hiromi; and Takahara, Yoshiyuki, 4,293,532, Cl. 423-356.000.
- Centralny Ośrodek Projektowo-Konstrukcyjny Maszyn Gorniczych "Komag": See—
Pretor, Wincenty; Rozmus, Edward; Korecki, Zbigniew; and Karmanski, Stanislaw, 4,293,248, Cl. 405-300.000.
- Centre de Recherche Industrielle du Quebec: See—
Dinh, Chon T. L., 4,293,820, Cl. 330-85.000.
- Century Geophysical Corporation: See—
West, Jerry B.; Kretzschmar, John L.; and Fung, Bing, 4,293,815, Cl. 324-254.000.
- Cepelinski, Jacob, to Mitel Corporation. Ringing decoder circuit. 4,293,737, Cl. 179-17.00E.
- Cerra, Raffaele, to Selenia Industrie Elettroniche Associate S.p.A. Frequency-shifting systems for frequency modulated signals. 4,293,825, Cl. 331-2.000.
- Cetus Corporation: See—
Cohen, Stanley N., 4,293,652, Cl. 435-172.000.
- Chalmers, Alexander A.; and Gailey, J. Lynn, to Alcan Aluminum Corporation. Siding panel system with modular insulating and mounting units. 4,292,781, Cl. 52-547.000.
- Chalmers, Franklin S.; Czako, Charles A.; and Nelson, Carl J., to Davy McKee Corporation. Apparatus for treatment of hydrocarbon-containing mineral material. 4,293,390, Cl. 202-100.000.
- Chamberlin, James W.: See—
Paget, Charles J.; Chamberlin, James W.; and Wikel, James W., 4,293,558, Cl. 424-270.000.
- Champion, Carolyn; Wolcott, Judith; Hart, Barbara; and Garcia, Zulma C. Brassiere. 4,292,975, Cl. 128-498.000.
- Chaney, Preston E.: See—
Cox, William H.; and Chaney, Preston E., 4,293,936, Cl. 367-82.000.
- Chapalain, Jean-Pierre. Hook. 4,293,156, Cl. 294-82.00R.
- Chatterson, Louis M.: See—
Nielsen, Edward G.; Mosley, Kenneth C.; and Chatterson, Louis M., 4,293,218, Cl. 356-138.000.
- Chaudhari, Praveen; Chou, Ned J.; Feder, Ralph; Fowler, Alan B.; and VanVechten, James A., to International Business Machines Corporation. High aspect ratio, high resolution mask fabrication. 4,293,374, Cl. 156-628.000.
- Chelsea Instruments Limited: See—
Wheaton, John E. G.; Griffiths, David; and Learner, Richard C. M., 4,293,225, Cl. 356-417.000.
- Cheng, Edmund K.; and Hill, Wiley E., to Intel Corporation. MOS Analog-to-digital converter. 4,293,848, Cl. 340-347.0AD.
- Cheng, William J.; Guthrie, David B.; and Leindecker, Donald M., to Petrolite Corporation. MgO Dispensions. 4,293,429, Cl. 252-18.000.
- Chester, Arthur W.: See—
Butter, Stephen A.; and Chester, Arthur W., 4,293,446, Cl. 252-455.00Z.
- Chevron Research Company: See—
Sieg, Robert P.; and Spars, Byron G., 4,293,401, Cl. 208-11.00R.
- Chicago Display Company: See—
Snyder, H. Kent, Jr., 4,292,751, Cl. 40-517.000.
- Chikanari, Kenichi: See—
Sekino, Masaaki; Chikanari, Kenichi; and Taniyama, Tsukasa, 4,293,419, Cl. 210-321.100.
- Chimicasa GmbH: See—
Vadasz, Kalman, 4,293,570, Cl. 426-3.000.
- Chimura, Kozo: See—
Ogihara, Masuo; Chimura, Kozo; Shinozaki, Nobuo; and Seki, Yoichi, 4,293,938, Cl. 368-72.000.
- Chin, Albert K.: See—
Fogarty, Thomas J.; and Chin, Albert K., 4,292,974, Cl. 128-344.000.
- Chirino, Agustin M.; and Yost, Gerald H., to Corning Glass Works. Method of forming hermetic seals. 4,293,325, Cl. 65-43.000.
- Chisholm-Ryder Company, Inc.: See—
Burton, Charles G., 4,292,792, Cl. 56-330.000.
- Chou, Ned J.: See—
Chaudhari, Praveen; Chou, Ned J.; Feder, Ralph; Fowler, Alan B.; and VanVechten, James A., 4,293,374, Cl. 156-628.000.
- Chressanthis, Andrew G.; Halpern, Henry M.; and Gaffney, Brian P., to RCA Corporation. Digital CFAR signal processor for phase coded radars. 4,293,856, Cl. 343-5.0CF.
- Christ, Charles; LeBeault, Jean-Michel; and Noel, Claude, to Christ, Charles. Apparatus for ensilaging and fermenting. 4,293,655, Cl. 435-316.000.
- Christensen, Burton G.; and DiNinno, Frank P., to Merck & Co., Inc. 6- and 6,6-Disubstituted-2-substituted-oxapen-2-em-3-carboxylic acids. 4,293,555, Cl. 424-263.000.
- Chrysosomidis, Chrysosomidos: See—
Morgan, Dean T.; Chrysosomidis, Chrysosomidos; and LaRue, George J., 4,293,527, Cl. 423-6.000.
- Chuang, Wen-Shou: See—
Wang, Wei Ko; Hoh, Ying-Chu; Chuang, Wen-Shou; and Shaw, I-Sine, 4,293,332, Cl. 75-99.000.
- Chukhno, Valery V.: See—
Trishevsky, Igor S.; Trishevsky, Oleg I.; Basy, Vladimir N.; Deber-deev, Rustem J.; Radjuevich, Leonid V.; Anisimov, Vyacheslav I.; Plesnetsov, Jury A.; and Chukhno, Valery V., 4,292,830, Cl. 72-197.000.
- Church, Larry L.; Smith, David R.; and Sun, Shan C., to Westinghouse Electric Corp. Network protector relay. 4,293,886, Cl. 361-71.000.
- Ciba-Geigy AG: See—
Rody, Jean, 4,293,468, Cl. 260-45.80N.
- Ciba-Geigy Corporation: See—
Woodward, Robert B.; and Bickel, Hans, 4,293,462, Cl. 260-239.00A.

- Cibie Projecteurs: See—
Deverreware, Alain, 4,293,897, Cl. 362-284.000.
- Cillario, Renzo, to P. Ferrero & C. S.p.A. Preservable baked pastry product, substantially free from sucrose and sweetened with fructose. 4,293,577, Cl. 426-244.000.
- Citizen Watch Company Limited: See—
Nishikubo, Yasuhiko; and Sekine, Mitsuo, 4,293,939, Cl. 368-74.000.
- Claassen, Ben J., Jr., to United States of America, Agriculture. Electrostatic precipitator apparatus using liquid collection electrodes. 4,293,319, Cl. 55-122.000.
- Clark-Reliance Corp., The: See—
Winiasz, Michael E., 4,292,998, Cl. 137-489.500.
- Clark, William D. Display sign. 4,292,752, Cl. 40-576.000.
- Clausen, Carol W. Armor comprising a plurality of loosely related sheets in association with a frontal sheet comprising metal abrading particles. 4,292,882, Cl. 89-36.00A.
- Clavin, Edward A.: See—
Slavens, Clyde M.; Clavin, Edward A.; and Alleman, James E., 4,293,758, Cl. 219-125.120.
- Clayton, Erith T. Method of plating with a portable mechanical plater. 4,293,584, Cl. 427-11.000.
- Clement, Donald E.: See—
Gibb, William D.; and Clement, Donald E., 4,293,740, Cl. 179-99.00A.
- Clement, Heinrich-Josef, to Carl Still GmbH & Co. KG, Firma. Door closure construction for sealing the sealing edge of a coke oven door in a framed coke oven opening. 4,293,389, Cl. 202-248.000.
- Cleopak Corporation: See—
Gardner, Roland C.; and Mortellito, Ronald, 4,293,090, Cl. 229-5.600.
- Clover, George R., to Oakeridge Management Services B.V. Transparency viewers. 4,293,190, Cl. 350-241.000.
- CMI Corporation: See—
Swisher, George W., Jr.; Garbelman, David L.; and Shaw, Arthur G., 4,293,228, Cl. 366-25.000.
- Coates, John P.; and Lewis, David H., to Lumenition Limited. Fail safe devices for use with devices for limiting the speed of revolution of an internal combustion engine. 4,292,939, Cl. 123-335.000.
- Coats, John H.: See—
Whaley, Howard A.; and Coats, John H., 4,293,651, Cl. 435-169.000.
- Coburn, John F., Jr., to Exxon Research & Engineering Co. Solar energy collection system. 4,292,959, Cl. 126-438.000.
- Coca-Cola Company, The: See—
Coleman, Charles E., 4,293,008, Cl. 141-95.000.
- Cockram, Geoffrey N.; and Munden, Jeffrey E., to Du Pont de Nemours, E. I., and Company. Method and apparatus for texturizing a proteinaceous substance. 4,293,575, Cl. 426-104.000.
- Coffey, Bettie L.: See—
Coffey, James P.; and Coffey, Bettie L., 4,293,602, Cl. 428-28.000.
- Coffey, James P.; and Coffey, Bettie L. Natural botanical ornament. 4,293,602, Cl. 428-28.000.
- Cogliano, Joseph A., to W. R. Grace & Co. Composition and method of controlling solid polyurethane particle size with water reactant. 4,293,679, Cl. 528-48.000.
- Cohen, Frederick. Waste heat energy recovery system. 4,293,323, Cl. 62-238.600.
- Cohen, Saul M.; and LeBlanc, John R., to Monsanto Company. Hemiacetals of adducts of acrolein and isocyanuric acid. 4,293,693, Cl. 544-221.000.
- Cohen, Stanley N., to Cetus Corporation. Method for synthesizing DNA sequentially. 4,293,652, Cl. 435-172.000.
- Cole, Bernard M. Flower-like decorative ornament. 4,293,601, Cl. 428-24.000.
- Coleman, Charles E., to Coca-Cola Company, The. Ratio graduate for use with post-mix beverage dispenser. 4,293,008, Cl. 141-95.000.
- Coleman, William J.; and Logue, Jay. Pipe railing system. 4,293,122, Cl. 256-69.000.
- Collier, Bobby D.: See—
Lopez, Bennie F.; Campbell, Billy H.; Collier, Bobby D.; Laird, William J.; Debona, Edward J.; and Eubanks, James E., Jr., 4,292,880, Cl. 89-1.815.
- Collin, Herbert S. Hanger bar. 4,293,076, Cl. 211-124.000.
- Colombo, Bruno: See—
Sisti, Giorgio; and Colombo, Bruno, 4,293,308, Cl. 23-230.0PC.
- Colt Industries Operating Corp.: See—
Kiesling, Norbert W., 4,292,945, Cl. 123-438.000.
- Combs, William. Conveyor apparatus for press machines. 4,292,892, Cl. 100-218.000.
- Comer, Robert C.: See—
Holmstadt, Ronald J.; and Comer, Robert C., 4,293,041, Cl. 172-39.000.
- Communications Satellite Corporation: See—
Atia, Ali E. E.; Berman, Arnold L.; and Mahle, Christoph, 4,293,945, Cl. 370-17.000.
- Rhodes, Smith A., 4,293,951, Cl. 371-43.000.
- Compagnie Generale des Etablissements Michelin: See—
Dubois, Gerard, 4,293,018, Cl. 152-347.000.
- Condon, Michael E.; and Ondetti, Miguel A., to E. R. Squibb & Sons, Inc. Tripeptide inhibitors of angiotensin-converting enzyme. 4,293,481, Cl. 260-112.50R.
- Conoco, Inc.: See—
Hunter, Andrew F., 4,292,912, Cl. 114-219.000.
- Continental Group, Inc., The: See—
Pelton, Peter G.; and Pulciani, Sam C., 4,293,353, Cl. 156-69.000.
- Control Data Corporation: See—
Fogg, Lewis W.; Metzler, Robert W.; Satterfield, H. Eugene; and Scott, Eion G., 4,292,762, Cl. 47-17.000.
- Conway, Charles S. Spill overflow prevention system for tanker vessels. 4,292,909, Cl. 114-74.00R.
- Cook, Frank; and Davies, Gordon H., to Thorn EMI Limited. Cathode ray tube assemblies. 4,293,801, Cl. 315-370.000.
- Cooper, David: See—
Nash, Claude H., III; Shearer, Marcia C.; Snader, Kenneth M.; Valenta, Joseph R.; and Cooper, David, 4,293,546, Cl. 424-119.000.
- Coöperatieve Landbouw aan- en verkoopcombinatie, B.A. "C.L.C.": See—
Locker, Jan A. K., 4,293,407, Cl. 209-253.000.
- Copal Company Limited: See—
Shimizu, Munetaka, 4,293,236, Cl. 400-593.000.
- Corbett, Daniel W.; and Guile, Donald L., to Corning Glass Works. Gelled solder glass suspensions for sealing glass or ceramic parts. 4,293,439, Cl. 252-316.000.
- Cordes, Gunter; Giesselmann, Ewald; and Munch, Ulrich, to Sanol Schwarz-Monheim GmbH. Transdermal medication system for isosorbide dinitrate. 4,293,565, Cl. 424-285.000.
- Corning Glass Works: See—
Chirino, Agustin M.; and Yost, Gerald H., 4,293,325, Cl. 65-43.000.
Corbett, Daniel W.; and Guile, Donald L., 4,293,439, Cl. 252-316.000.
- Coronet Foods, Inc.: See—
Long, Howard W.; and Flowers, Robert L., 4,292,786, Cl. 53-434.000.
- Costello, Carmon R.: See—
Petty, Terry D.; Costello, Carmon R.; Rao, Gude P.; and Gansar, David, 4,293,239, Cl. 405-195.000.
- Costruzione Incollatrici Rapide C.I.R. S.r.L.: See—
Catozzo, Leo, 4,293,368, Cl. 156-506.000.
- Cotte, Jean-Marie; and Potin, Philippe, to Societe Nationale Elf Aquitaine. Process and composition for the coloration of keratin-containing substances. 4,293,543, Cl. 424-59.000.
- Coulter, John P.: See—
Gore, Colin E.; and Coulter, John P., 4,292,798, Cl. 57-86.000.
- Cowan, Keith B.: See—
Winegard, John R.; Shelledy, Carey W.; and Cowan, Keith B., 4,293,861, Cl. 343-766.000.
- Cox, Allen R.; and Smathers, Edmond W., to International Business Machines Corporation. Magnetic head mount assembly. 4,293,883, Cl. 360-104.000.
- Cox, Clayton E. Cornerboard for pallets. 4,292,901, Cl. 108-55.100.
- Cox, Joseph V.: See—
Graybeal, Carl N.; Rogers, Basil E.; Cox, Joseph V.; and Rogers, Roy R., 4,293,243, Cl. 405-259.000.
- Cox, William H.; and Chaney, Preston E., to Sperry-Sun, Inc. Telemetry system. 4,293,936, Cl. 367-82.000.
- Crane Co.: See—
Hirzel, Edgar A., 4,293,165, Cl. 303-93.000.
- Crano, Richard N.: See—
Bible, Dennis E.; Crano, Richard N.; and Welch, John A., 4,293,016, Cl. 152-158.000.
- Creative Tool Company: See—
Wesley, William M., 4,292,841, Cl. 73-119.00A.
- Crepaco, Inc.: See—
Swanson, Victor E., 4,293,290, Cl. 418-94.000.
- Cressoni, Ermanno: See—
Bertoloni, Luciano; Rogora, Edoardo; and Cressoni, Ermanno, 4,293,843, Cl. 340-52.00F.
- Crown Zellerbach Corporation: See—
Geyser, Joseph E.; Rehr, Henry W.; Schutz, Rudolph W.; and Weis, Rudolf R., 4,293,365, Cl. 156-364.000.
- CSELT, Centro Studi e Laboratori Telecomunicazioni S.p.A.: See—
Accatino, Luciano, 4,293,830, Cl. 333-161.000.
- CTS Corporation: See—
Van Benthuyzen, John D.; and Osburn, Carlton M., 4,293,751, Cl. 200-156.000.
- Cucchi, Giovanni: See—
Cucchi, Pietro; and Cucchi, Giovanni, 4,292,864, Cl. 82-2.700.
- Cucchi, Pietro; and Cucchi, Giovanni. Automatic magazine and feeder for automatic multi-mandrel lathe. 4,292,864, Cl. 82-2.700.
- Cuddihy, Robert W.: See—
Gordon, Robert; King, Harry A.; Springrose, James V.; and Cud-dihy, Robert W., 4,292,898, Cl. 105-238.00R.
- Cuscudra, Michael, to Texaco Inc. Stabilizing polyurea polymer polyols by treating with a secondary amine. 4,293,470, Cl. 260-45.90R.
- Cutchaw, John M. Connector for integrated circuit packages. 4,293,175, Cl. 339-75.0MP.
- CXA Ltd./CXA Ltee: See—
Morrey, William B.; and Welsh, David M., 4,292,896, Cl. 102-275.800.
- Czako, Charles A.: See—
Chalmers, Franklin S.; Czako, Charles A.; and Nelson, Carl J., 4,293,390, Cl. 202-100.000.
- D. L. Auld Company, The: See—
Waugh, Robert E., 4,292,827, Cl. 72-46.000.
- Dagma Deutsche Automaten und Getrankemaschinen GmbH & Co. KG: See—
Kuckens, Alexander, 4,293,081, Cl. 222-83.000.

Dai-Ichi Seiko Co., Ltd.: See—
Kashiwagi, Tutomu, 4,293,765, Cl. 235-144.00R.
Daicel Ltd.: See—
Sawada, Hideo; Shinohara, Koji; and Shiga, Makoto, 4,292,984, Cl. 131-345.000.
Daido Metal Company Ltd.: See—
Iijima, Yoshio, 4,292,718, Cl. 29-149.5DP.
Daichi Seiyaku Co., Ltd.: See—
Tanaka, Yoshiaki; and Hayakawa, Isao, 4,293,695, Cl. 546-83.000.
Daimler-Benz Aktiengesellschaft: See—
Lutze, Hans; Weissappel, Helmut; Klie, Wolfgang; and Weidemann, Dieter, 4,293,160, Cl. 296-188.000.
Reinhard, Theodor; Krugener, Rolf; Kurth, Hermann W.; Blaich, Diether; Rothmaier, Franz; Kopperschlager, Dieter; Schmitz, Heinz; and Nill, Edgar, 4,292,823, Cl. 70-364.00R.
Dainippon Screen Seizo Kabushiki Kaisha: See—
Kinoshita, Minoru; Sugou, Kiyoshi; and Onoda, Yukio, 4,293,226, Cl. 356-443.000.
Dalla Bona, Hans. Joint for connecting a partial dental prosthesis to the remaining natural human teeth. 4,293,303, Cl. 433-177.000.
D'Amato, Ralph J., to RCA Corporation. Color picture tube having improved corrugated apertured mask. 4,293,791, Cl. 313-403.000.
Dana Corporation: See—
Schaeffer, Jack A., 4,292,782, Cl. 52-696.000.
Dandeneau, Raymond D.: See—
Bente, Paul F., III; Zerenner, Ernest H.; and Dandeneau, Raymond D., 4,293,415, Cl. 210-198.200.
Dardoufas, Kimon C.: See—
Marshall, Robert M.; and Dardoufas, Kimon C., 4,293,460, Cl. 260-18.00PF.
Darlington, William B.; DuBois, Donald W.; and White, Preston S., to PPG Industries, Inc. Electrolytically producing chlorine using a solid polymer electrolyte-cathode unit. 4,293,394, Cl. 204-98.000.
Dasgupta, Sumit; Goel, Prabhakar; and Williams, Thomas W., to International Business Machines Corporation. Level sensitive scan design (LSSD) system. 4,293,919, Cl. 364-716.000.
Daswick, Alexander C.; and Landry, Archie C. Lightweight two-wheeled vehicle. 4,293,052, Cl. 180-219.000.
Data Packaging Corporation: See—
Yonkers, Edward H.; and LeDoux, Gilbert A., 4,293,234, Cl. 400-196.100.
Date, K. Henry; and Wainio, Ronald, to McGraw-Edison Company. Load break switch. 4,293,834, Cl. 335-76.000.
Davenport, Stanley, Jr., to Kendall Company, The. Protective shoulder pad construction. 4,292,687, Cl. 2-2.000.
Davies, Gordon H.: See—
Cook, Frank; and Davies, Gordon H., 4,293,801, Cl. 315-370.000.
Davignon, Alan J., to K-2 Corporation. Vibration damped ski. 4,293,142, Cl. 280-610.000.
Davino, Arthur A., to G. D. Searle & Co. Process for esterification of α -L-aspartyl-L-phenylalanine. 4,293,648, Cl. 435-70.000.
Davio, Marc; and Bioul, Gery J. A., to U.S. Philips Corporation. Device for multiplying binary numbers. 4,293,922, Cl. 364-757.000.
Davis, Gayron N.; Sellers, Larry S.; and Hagborg, Winston E., to West Point Pepperell, Inc. Apparatus for applying liquid chemicals to a moving web. 4,292,918, Cl. 118-33.000.
Davis, James W.; and Paranjpe, Suresh C., to Mead Corporation, The. Ink jet printer with laterally movable print head. 4,293,863, Cl. 346-75.000.
Davis, Robert K.; and Myers, Michael J., to Roper Corporation; and Electromotion, Inc. Solenoid for an electric starting motor for garden tractor or the like. 4,293,835, Cl. 335-131.000.
Davis, Steven S., to Envirotech Corporation. Steam seal for disc filter. 4,293,411, Cl. 210-178.000.
Davison, Peter A.: See—
Dobson, John S.; and Davison, Peter A., 4,293,200, Cl. 351-36.000.
Davy McKee Corporation: See—
Chalmers, Franklin S.; Czako, Charles A.; and Nelson, Carl J., 4,293,390, Cl. 202-100.000.
Dawdy, Terrance H.: See—
Zalucha, Denis J.; Sexsmith, Frederick H.; Hornaman, Ernest C.; and Dawdy, Terrance H., 4,293,665, Cl. 525-255.000.
Day, Jerome A. Energy conserver. 4,293,026, Cl. 165-11.000.
Deberdeev, Rustem J.: See—
Trishevsky, Igor S.; Trishevsky, Oleg I.; Bosy, Vladimir N.; Deberdeev, Rustem J.; Radjuevich, Leonid V.; Anisimov, Vyacheslav I.; Plesnetsov, Jury A.; and Chukhno, Valery V., 4,292,830, Cl. 72-197.000.
Debona, Edward J.: See—
Lopez, Bennie F.; Campbell, Billy H.; Collier, Bobby D.; Laird, William J.; Debona, Edward J.; and Eubanks, James E., Jr., 4,292,880, Cl. 89-1.815.
Debono, Manuel, to Eli Lilly and Company. Derivatives of A-30912A nucleus. 4,293,483, Cl. 260-112.50R.
Debono, Manuel, to Eli Lilly and Company. Derivatives of A-30912H nucleus. 4,293,484, Cl. 260-112.50R.
Debono, Manuel, to Eli Lilly and Company. Derivatives of S31794/F-1 nucleus. 4,293,485, Cl. 260-112.50R.
Debono, Manuel, to Eli Lilly and Company. Derivatives of S31794/F-1 nucleus. 4,293,486, Cl. 260-112.50R.
Debono, Manuel, to Eli Lilly and Company. Derivatives of A-30912D nucleus. 4,293,487, Cl. 260-112.50R.
Debono, Manuel, to Eli Lilly and Company. Derivatives of A-30912B nucleus. 4,293,488, Cl. 260-112.50R.
Debono, Manuel, to Eli Lilly and Company. Derivatives of A-30912A nucleus. 4,293,489, Cl. 260-112.50R.

Debono, Manuel, to Eli Lilly and Company. Derivatives of A-30912H nucleus. 4,293,491, Cl. 260-112.50R.
De Busscher, Cyriel R. J.; and Van Herpe, Francois, to Sperry Corporation. Combine harvester conveyor. 4,292,981, Cl. 130-27.00F.
Decker, Walter: See—
Nissen, Dietmar; Marx, Matthias; Jarre, Wolfgang; Schoen, Ernst; and Decker, Walter, 4,293,657, Cl. 521-121.000.
De Graan, Henry R. Washer. 4,292,876, Cl. 411-542.000.
de Klein, Willem J.: See—
Zeilstra, Jacobus J.; de Klein, Willem J.; and Bik, Joannes D., 4,293,345, Cl. 106-270.000.
Delaney, Glen J. Light weight insulated athletic shoe. 4,292,746, Cl. 36-83.000.
Del Re, Pietrantonio; and Fracassi, Pietro, to Carlo Gavazzi S.p.A. Apparatus for generating signals simulating the output of a device for measuring a physical variable. 4,293,916, Cl. 364-571.000.
DeMichele, Glenn A., to Rockwell International Corporation. Signal amplitude range compression employing pulse modulation. 4,293,817, Cl. 328-169.000.
Demoures, Bernard; and Le Coent, Jean-Louis, to Orogil. Process of preparing metallic detergent-dispersant additives of high alkalinity in particular for lubricating oils, and product obtained thereby. 4,293,431, Cl. 252-33.200.
Demos, Dietrich: See—
Deutscher, Hans-Joachim; Schubert, Herrmann; Seidel, Christina; Demus, Dietrich; and Kresse, Horst, 4,293,434, Cl. 252-299.630.
Denning, Ralph E.: See—
Goloff, Alexander; and Denning, Ralph E., 4,293,050, Cl. 180-6.260.
Denpatsu Fly Ash: See—
Segawa, Hiroshi; and Akizuki, Katsufumi, 4,293,523, Cl. 422-139.000.
Denton, Medona B.; and Windsor, David L., to United States of America, Navy. Application of inductively coupled plasma emission spectrometry to the elemental analysis of organic compounds and to the determination of the empirical formulas for these and other compounds. 4,293,220, Cl. 356-316.000.
Detector Systems, Inc.: See—
Potter, Thomas R., 4,293,841, Cl. 340-44.000.
Detroit, William J., to American Can Company. Lignosulfonate derivatives. 4,293,342, Cl. 106-90.000.
Detroit, William J., to American Can Company. Asphalt emulsion-conditioner. 4,293,459, Cl. 260-17.500.
Deucker, Walter: See—
Hoyer, Ernst; Steckelberg, Willi; Deucker, Walter; and Schickfluss, Rudolf, 4,293,306, Cl. 8-471.000.
Deutscher, Hans-Joachim; Schubert, Herrmann; Seidel, Christina; Demus, Dietrich; and Kresse, Horst, to VEB Werk für Fernsehelektronik Berlin im VEB Kombinat Mikroelektronik. Liquid crystal compounds. 4,293,434, Cl. 252-299.630.
Deverrewaere, Alain, to Cibie Projecteurs. Motor vehicle headlight. 4,293,897, Cl. 362-284.000.
Diamond Shamrock Corporation: See—
Borror, Jack A.; and Rowe, Edward A., Jr., 4,293,433, Cl. 336-94.000.
Metz, Fred L., 4,293,340, Cl. 106-74.000.
Dias, Francisco J.: See—
Luhleisch, Hartmut; Pflaum, Peter; Dias, Francisco J.; Nauomidis, Aristides; Schirbach, Arno; and Nickel, Hubertus, 4,293,512, Cl. 264-58.000.
Di Battista, Piero; Fontanelli, Renzo; Gratani, Francesco; and Nelli, Giuseppe, to Montedison S.p.A. Piperidine phosphite stabilizers for polymers and polymers stabilized thereby. 4,293,466, Cl. 260-45.80N.
Dickerson, Charles G.; and Erhardt, Peter F., to Xerox Corporation. Attrition process for alteration of toner particles containing conductive materials. 4,293,632, Cl. 430-137.000.
Dickinson, Norman L. Pollutant-free low temperature slurry combustion process utilizing the super-critical state. 4,292,953, Cl. 126-263.000.
Diederichs, John M. Tool for removing staples. 4,293,119, Cl. 254-28.000.
Diehl GmbH & Co.: See—
Weber, Adolf; and Rhau, Siegfried, 4,292,829, Cl. 72-76.000.
Dieterich, Dieter; and Markus, Peter, to Bayer Aktiengesellschaft. Polyurethane ionomer dispersions containing electrolytes. 4,293,474, Cl. 260-29.2TN.
Dighe, Kamalakar D.: See—
Caruso, Stephen; and Dighe, Kamalakar D., 4,293,222, Cl. 356-319.000.
Digre, Clifford B. Magnet assembly. 4,293,741, Cl. 179-115.5PC.
Dilot, Rolf M.; and Hakansson, Jan T., to Tetra Pak International AB. Machine for the application of suction tubes to packing containers. 4,293,369, Cl. 156-521.000.
DiMatteo, Paul, to Solid Photography, Inc. Arrangement for constructing surfaces and bodies. 4,292,724, Cl. 29-418.000.
Din, Zia U.: See—
Cardenas, Carlos G.; and Din, Zia U., 4,293,497, Cl. 260-345.500.
Dinh, Chon T. L., to Centre de Recherche Industrielle du Quebec. Positive feedback biquad filter. 4,293,820, Cl. 330-85.000.
DiNinno, Frank P.: See—
Christensen, Burton G.; and DiNinno, Frank P., 4,293,555, Cl. 424-263.000.
Dinklage, Horst: See—
Fink, Herbert; Huebner, Klaus; Dinklage, Horst; and Ottofrickenstein, Hans, 4,293,600, Cl. 427-385.500.
Dobbins, Hugh L. Liquid measure dip stick. 4,292,739, Cl. 33-126.40R.

Dobson, John S.; and Davison, Peter A. Visual faculty testing apparatus. 4,293,200, Cl. 351-36.000.
Dr. Ing. h.c.F. Porsche Aktiengesellschaft: See—
Mairle, Hans, 4,292,774, Cl. 52-208.000.
Dr.-Ing. Rudolf Hell GmbH: See—
Keller, Hans; and Knop, Hans-Georg, 4,293,872, Cl. 358-75.000.
Dofasco Inc.: See—
Tait, William H., 4,292,847, Cl. 73-587.000.
Dolhyj, Serge R.: See—
Velenyi, Louis J.; Dolhyj, Serge R.; and Sundeen, Marcia H., 4,293,719, Cl. 568-573.000.
Dominguez, Ramon: See—
Varadi, Peter F.; and Dominguez, Ramon, 4,293,808, Cl. 320-2.000.
Donald MacMillan & Son, Inc.: See—
MacMillan, Kenneth T., 4,293,293, Cl. 425-23.000.
Donan, David C., Jr., to Waimea Company Inc. Pick arm anchor assembly. 4,293,244, Cl. 405-259.000.
Doryokuro Kakuneryo Kaihatsu Jigyodan: See—
Kubota, Jun, 4,293,853, Cl. 340-611.000.
Double A Products Company: See—
Carlson, Allen J.; and Vander Kaay, Henry A., 4,293,284, Cl. 417-218.000.
Douke, Harumi: See—
Iwata, Masayoshi; and Douke, Harumi, 4,293,743, Cl. 200-4.000.
Dow Chemical Company, The: See—
Erickson, Robert E., 4,293,609, Cl. 428-246.000.
Haschke, Elliot M.; and Lewis, Bennie J., 4,293,347, Cl. 134-11.000.
Kelly, Kerry J.; and Kamp, Arthur J., 4,293,379, Cl. 376-159.000.
Moore, Carl; and Kirchoff, Robert A., 4,293,476, Cl. 260-29.70W.
Dow Corning Corporation: See—
Homan, Gary R.; and Lee, Chi-Long, 4,293,676, Cl. 528-15.000.
Dragerwerk Aktiengesellschaft: See—
Pasternack, Adalbert, 4,292,967, Cl. 128-202.260.
Draggoc, V. G.: See—
McAllister, Gary L.; and Draggoc, V. G., 4,293,827, Cl. 331-94.5ML.
Dresser Industries, Inc.: See—
Carrens, Donald E., 4,293,287, Cl. 417-393.000.
Dresser, Thorpe: See—
Ohlswager, Stanley; Edison, Robert R.; and Dresser, Thorpe, 4,293,025, Cl. 165-1.000.
Drobina, Deszo D. Method of forming decorative panels. 4,293,362, Cl. 156-264.000.
Drobot, Walter, to Engelhard Minerals & Chemicals Corporation. Microbiological recovery of metals. 4,293,333, Cl. 75-101.0BE.
Drobot, Walter; and Lechavelier, Hubert A., to Engelhard Minerals & Chemicals Corporation. Recovery of metals. 4,293,334, Cl. 75-101.0BE.
DuBois, Donald W.: See—
Darlington, William B.; DuBois, Donald W.; and White, Preston S., 4,293,394, Cl. 204-98.000.
Dubois, Gerard, to Compagnie Generale des Etablissements Michelin. Tire for two-wheel vehicle. 4,293,018, Cl. 152-347.000.
Dubur, Gunar Y.: See—
Uldriks, Yan R.; Preisa, Ieva E.; Dubur, Gunar Y.; Zidermane, Aina A.; Biseniex, Egils A.; and Tirtiz, Gunar D., 4,293,700, Cl. 546-321.000.
Ducloux, Marcel, to Societe Generale Pour L'Emballage. Method and apparatus for inspecting transparent objects. 4,293,219, Cl. 356-240.000.
Dudley, Hubert T.; and Bragg, Ralph J., to W. R. Grace & Co. Thin section insulating concrete of high strength and low water requirement. 4,293,341, Cl. 106-88.000.
Dudley, Peter B., to Mono-Kinetics. Mono-kinetic exercise device. 4,293,127, Cl. 272-133.000.
Dunaevsky, Vladimir I.; Boidenko, Nikolai G.; Samarin, Alexei P.; Levit, Viktor M.; Zapara, Boris M.; Ivanov, Boris N.; Frolov, Sergei A.; Voronin, Rostislav A.; Belozero, Nikolai P.; Momot, Valery I.; Stusenko, Jury A.; and Samoilov, Vladimir A. Apparatus for helically coiling bands after slitting wide strip. 4,293,101, Cl. 242-56.400.
Dungs, Horst: See—
Lorenz, Kurt; Dungs, Horst; Koenigs, Hans B.; and Kurtz, Roman, 4,293,388, Cl. 202-126.000.
Dunnavant, William R.: See—
Martin, Ralph D.; Dunnavant, William R.; Sturtz, Gregory P.; and Langer, Heimo J., 4,293,480, Cl. 260-38.000.
Dunsky, Joel L. Root canal equipment packaging. 4,293,074, Cl. 206-572.000.
Dunwald, Willi: See—
Rottmaier, Ludwig; Merten, Rudolf; Lewalter, Jurgen; Zecher, Wilfried; and Dunwald, Willi, 4,293,669, Cl. 525-452.000.
Du Pont de Nemours, E. I., and Company: See—
Andrews, Gerald D., 4,293,674, Cl. 526-327.000.
Applegate, Lynn E.; and Brown, Charles J., Jr., 4,293,420, Cl. 210-500.200.
Bethay, Willis D., Jr., 4,293,518, Cl. 264-210.200.
Bowen, Griffith; and Fowell, Peter A., 4,293,615, Cl. 428-412.000.
Bula, Russell P., 4,292,900, Cl. 108-51.100.
Cockram, Geoffrey N.; and Munden, Jeffrey E., 4,293,575, Cl. 426-104.000.
Eastman, Ernest F., 4,293,473, Cl. 260-27.00R.
Flint, William L.; and Pilette, Yvan P., 4,293,635, Cl. 430-271.000.
Heiberger, Philip, 4,293,471, Cl. 260-22.0CB.
Knox, Kenneth L., 4,293,517, Cl. 264-176.00R.
Levitt, George, 4,293,330, Cl. 71-94.000.
Durant, Graham J.; Emmett, John C.; and Ganellin, Charon R., to Smith, Kline & French Laboratories Limited. Pharmacologically active thiourea and urea compounds. 4,293,697, Cl. 546-121.000.
Durant, Graham J.; Emmett, John C.; and Ganellin, Charon R., to Smith Kline & French Laboratories Limited. Pharmacologically active guanidine compounds. 4,293,699, Cl. 546-121.000.
Durckheimer, Walter: See—
Blumbach, Jurgen; Durckheimer, Walter; and Schrinner, Elmar, 4,293,550, Cl. 424-246.000.
Duret, Christian H. Nodal structure switching network. 4,293,735, Cl. 179-18.0GE.
Dyer, Thomas A.; and Huelster, Richard L., to Pentek Corporation. Drive/take-up assembly for accumulating live roller conveyor systems. 4,293,065, Cl. 198-781.000.
Dziubaty, Theodore D., to Forum, Inc. Luminaire reflector. 4,293,900, Cl. 362-342.000.
E. D. Bullard Company: See—
Moretti, Anthony L.; and Ferris, Lester W., 4,292,692, Cl. 2-418.000.
E. R. Squibb & Sons, Inc.: See—
Condon, Michael E.; and Ondetti, Miguel A., 4,293,481, Cl. 260-112.50R.
Haugwitz, Rudiger D.; Wade, Peter C.; and Maurer, Barbara V., 4,293,569, Cl. 424-300.000.
Pawelchak, John M.; Wang, Yu-Chang J.; and LaVia, Anthony L., 4,292,972, Cl. 128-296.000.
Eagle-Picher Industries, Inc.: See—
King, Clyde R., 4,292,713, Cl. 24-24.000.
Eastman, Ernest F., to Du Pont de Nemours, E. I., and Company. Polyvinyl alcohol - crystalline solvent system based compositions modified with ethylene polymer. 4,293,473, Cl. 260-27.00R.
Eastman Kodak Company: See—
Fyson, John R.; and Levenson, Gerald I. P., 4,293,638, Cl. 430-373.000.
Kroll, Arthur S.; and Shuster, Frank A., 4,292,921, Cl. 118-648.000.
Rosborough, Robert S., Jr.; and Wright, Luther M., deceased, 4,293,215, Cl. 355-40.000.
Webster, Frank G.; Regan, Michael T.; and Rossi, Louis J., 4,293,626, Cl. 430-17.000.
Ebata, Yoshihiro; Toibana, Yasuo; Uetsuki, Tsuneo; Kose, Saburo; and Kinoshita, Makoto, to Agency of Industrial Science & Technology; and Ministry of International Trade & Industry. Method for adhesion of ceramics. 4,293,356, Cl. 156-89.000.
Ebauches S.A.: See—
Wiget, Fridolin, 4,292,836, Cl. 73-6.000.
Ebel, John C. Center of gravity-appraisal block game. 4,293,128, Cl. 273-1.0GF.
Ebrok, Vello H.: See—
Kull, Leo; and Ebrok, Vello H., 4,293,806, Cl. 318-673.000.
Ecodyne Corporation: See—
Giannelli, Joseph F., 4,293,414, Cl. 210-193.000.
Edelman, Robert, to Celanese Corporation. Production of an improved non-reinforced polyoxymethylene molding composition which forms reduced mold deposits upon molding. 4,293,469, Cl. 260-45.90P.
Edison, Robert R.: See—
Ohlswager, Stanley; Edison, Robert R.; and Dresser, Thorpe, 4,293,025, Cl. 165-1.000.
Effem Foods Pty. Ltd.: See—
Sentance, Christopher B., 4,293,576, Cl. 426-104.000.
Egawa, Isao: See—
Asada, Eiichi; Inokuma, Toshio; and Egawa, Isao, 4,293,839, Cl. 338-309.000.
Egawa, Takeshi: See—
Yamazaki, Yasuo; and Egawa, Takeshi, 4,293,185, Cl. 350-18.000.
Egorov, Jury P.: See—
Kuzin, Eduard N.; Korelin, Vladimir F.; Fainzilber, Mikhail L.; Egorov, Jury P.; Erofeenko, Igor V.; Karev, Nikolai V.; Kozlov, Jury S.; Kudish, Viktor B.; Kolbasov, Valery K.; and Bobchenok, Meri I., 4,293,238, Cl. 405-175.000.
Eguchi, Yukuo: See—
Ishikawa, Masayuki; Tanaka, Hiromichi; Eguchi, Yukuo; Ito, Shigeru; Takashima, Yoshimi; and Kobayashi, Masahiko, 4,293,553, Cl. 424-250.000.
Eibl, Heinz: See—
Hatz, Ernst; Eibl, Heinz; Peter, Erwin; and Blumhardt, Rolf, 4,293,092, Cl. 237-12.100.
Ekberg, Hakan, to STAL-LAVAL Turbin AB. Plant for drying fuel. 4,292,742, Cl. 34-35.000.
Eklund, David R.: See—
Fincher, Paul A.; and Eklund, David R., 4,293,086, Cl. 225-1.000.
Elder, Richard B.: See—
Thornhill, John, Jr.; and Elder, Richard B., 4,292,861, Cl. 74-813.00R.
Electricite de France (Service National): See—
Brachet, Alain, 4,293,385, Cl. 376-283.000.
Electromotion, Inc.: See—
Davis, Robert K.; and Myers, Michael J., 4,293,835, Cl. 335-131.000.
Elektrokemiska Aktiebolaget: See—
Andersson, Kjell R.; and Johansson, Hans E., 4,293,612, Cl. 428-281.000.
Eli Lilly and Company: See—
Abbott, Bernard J.; and Fukuda, David S., 4,293,482, Cl. 260-112.50R.
Abbott, Bernard J.; and Fukuda, David S., 4,293,490, Cl. 260-112.50K.

- Debono, Manuel, 4,293,483, Cl. 260-112.50R.
Debono, Manuel, 4,293,484, Cl. 260-112.50R.
Debono, Manuel, 4,293,485, Cl. 260-112.50R.
Debono, Manuel, 4,293,486, Cl. 260-112.50R.
Debono, Manuel, 4,293,487, Cl. 260-112.50R.
Debono, Manuel, 4,293,488, Cl. 260-112.50R.
Debono, Manuel, 4,293,489, Cl. 260-112.50R.
Debono, Manuel, 4,293,491, Cl. 260-112.50R.
Hoehn, Marvin M.; and Michel, Karl H., 4,293,649, Cl. 435-118.000.
Kukolja, Stjepan; and Pfeil, Janice L., 4,293,493, Cl. 260-239.00A.
Kukolja, Stjepan; and Pfeil, Janice L., 4,293,495, Cl. 260-245.400.
Ludwig, Nelson H.; and Ose, Earl E., 4,293,539, Cl. 424-19.000.
Miesel, John L., 4,293,552, Cl. 424-250.000.
Paget, Charles J.; Chamberlin, James W.; and Wikel, James W., 4,293,558, Cl. 424-270.000.
Elliott Brothers (London) Limited: See—
Ellis, Stafford M., 4,292,688, Cl. 2-6.000.
Ellis, Franklin H., to Sybron Corporation. Electric supply for ion therapy. 4,292,968, Cl. 128-207.210.
Ellis, James D., to Viking Industries, Inc. Split mullion window frame design. 4,292,771, Cl. 52-98.000.
Ellis, Stafford M., to Elliott Brothers (London) Limited. Latch mechanisms. 4,292,688, Cl. 2-6.000.
Elmi, Steele J., to Finetex Incorporated. Fluid and semi-fluid compositions including benzoate esters. 4,293,544, Cl. 424-60.000.
Elphinstone, Eugene A.; McLaughlin, Homer C.; and Smith, Charles W., to Halliburton Company. Temperature gelation activated aqueous silicate mixtures and process of forming impermeable gels. 4,293,440, Cl. 252-317.000.
Emmett, John C.: See—
Durant, Graham J.; Emmett, John C.; and Ganellin, Charon R., 4,293,697, Cl. 546-121.000.
Durant, Graham J.; Emmett, John C.; and Ganellin, Charon R., 4,293,699, Cl. 546-121.000.
Endo, Norio, to Tokyo Shibaura Denki Kabushiki Kaisha. Method for manufacturing semiconductor integrated circuits utilizing special contact formation. 4,292,728, Cl. 29-571.000.
Energetics Systems Corp.: See—
Tepe, James R.; Sandor, Robert P.; Wesselman, Bernard W.; and Woeste, David R., 4,293,027, Cl. 165-12.000.
Engelhard Minerals & Chemicals Corporation: See—
Drobot, Walter, 4,293,333, Cl. 75-101.0BE.
Drobot, Walter; and Lechavelier, Hubert A., 4,293,334, Cl. 75-101.0BE.
Langley, Robert C.; Myers, Herbert; and Abrash, Muriel, 4,293,513, Cl. 264-60.000.
Engelsmann, Dieter: See—
Wagner, Karl; Engelsmann, Dieter; Hackenberg, Hubert; and Stiefel, Peter, 4,293,204, Cl. 354-21.000.
English Electric Valve Company: See—
Menown, Hugh, 4,293,800, Cl. 315-350.000.
Enomoto, Minoru: See—
Nishimura, Hideo; Yoneda, Takao; and Enomoto, Minoru, 4,293,913, Cl. 364-474.000.
Enright, Dorothy P.: See—
Lucas, James M.; Enright, Dorothy P.; and Perricone, Alphonse C., 4,293,427, Cl. 252-8.50C.
Entenmann's, Inc.: See—
Keoteklian, Hagop, 4,293,416, Cl. 210-208.000.
Envirotech Corporation: See—
Davis, Steven S., 4,293,411, Cl. 210-178.000.
Guttman, Murray M.; and Fisser, William L., 4,293,417, Cl. 210-230.000.
Eprad Incorporated: See—
Boudouris, Angelo; and Peters, Edwin F., 4,293,821, Cl. 330-126.000.
Epstein, James: See—
Marincic, Nikola; and Epstein, James, 4,293,622, Cl. 429-50.000.
Ergaver, Nevenka; and Ergaver, Rayko, to Capella Inc. Electric hair brush. 4,292,986, Cl. 132-11.00R.
Ergaver, Rayko: See—
Ergaver, Nevenka; and Ergaver, Rayko, 4,292,986, Cl. 132-11.00R.
Erhardt, Peter F.: See—
Dickerson, Charles G.; and Erhardt, Peter F., 4,293,632, Cl. 430-137.000.
Erickson, Robert E., to Dow Chemical Company, The. Flexible absorbent laminates. 4,293,609, Cl. 428-246.000.
Ernst, Horst M.; Olschewski, Armin; Schurger, Rainer; Walter, Lothar; Brandenstein, Manfred; and Burkl, Erich, to SKF Kugellagerfabriken GmbH. Rolling bearing for relative linear movement on a shaft. 4,293,166, Cl. 308-6.00C.
Erofeenko, Igor V.: See—
Kuzin, Eduard N.; Korelin, Vladimir F.; Fainzilber, Mikhail L.; Egorov, Yuri P.; Erofeenko, Igor V.; Karev, Nikolai V.; Kozlov, Yuri S.; Kudish, Viktor B.; Kolbasov, Valery K.; and Bobchenok, Meri I., 4,293,238, Cl. 405-175.000.
Ersay, Okan K., to Sentralinstitutt for Industriell Forskning. Method of holographic recording and reconstruction of spatial waves. 4,293,183, Cl. 350-3.770.
Erwin Sick GmbH-Optik-Elektronik: See—
Sick, Erwin; and Mankel, Siegfried, 4,293,776, Cl. 250-572.000.
Escher Wyss Limited: See—
Marchioro, Ignazio, 4,292,716, Cl. 29-116.0AD.
Esquire, Inc.: See—
Hernandez, Jose A., 4,293,901, Cl. 362-346.000.

- Ethyl Corporation: See—
Papay, Andrew G.; and O'Brien, Joseph P., 4,293,432, Cl. 252-49.900.
Etoh, Yukihiko: See—
Tanaka, Toshiaki; and Etoh, Yukihiko, 4,292,938, Cl. 123-198.00F.
Eubanks, James E., Jr.: See—
Lopez, Bennie F.; Campbell, Billy H.; Collier, Bobby D.; Laird, William J.; Debona, Edward J.; and Eubanks, James E., Jr., 4,292,880, Cl. 89-1.815.
Evans, Robert W., to Baker International Corporation. Ball valve assembly. 4,293,038, Cl. 166-331.000.
Everede Tool Company: See—
Markovics, Michael, 4,293,254, Cl. 408-229.000.
Exxon Production Research Company: See—
Gale, Walter W.; Puerto, Maura C.; Ashcraft, Thomas L.; Saunders, Rhoderick K.; and Reed, Ronald L., 4,293,428, Cl. 252-8.55D.
Exxon Research & Engineering Co.: See—
Coburn, John F., Jr., 4,292,959, Cl. 126-438.000.
Klemann, Lawrence P.; Newman, Gerald H.; Stogryn, Eugene L.; Whitney, Thomas A.; and Farcasiu, Dan, 4,293,623, Cl. 429-194.000.
Shewmaker, James E., 4,293,348, Cl. 134-22.00R.
Ezaki, Norio. Pastry topping depositing machine. 4,292,917, Cl. 118-16.000.
Ezekiel, Frederick D. Magnetic liquid shaft sealing. 4,293,137, Cl. 277-80.000.
Fabryka Obrabiarek Precyzyjnych "Ponar-Pruszkow" Zaklad "i Maja": See—
Matusz, Zbigniew, 4,292,857, Cl. 74-466.000.
Facet Enterprises, Inc.: See—
Miller, Donald L., 4,293,060, Cl. 192-56.00R.
Fahner, Friedrich: See—
Heydenreich, Frieder; Korber, Helmut; Tacke, Peter; Fahner, Friedrich; and Neuray, Dieter, 4,293,662, Cl. 525-184.000.
Fainzilber, Mikhail L.: See—
Kuzin, Eduard N.; Korelin, Vladimir F.; Fainzilber, Mikhail L.; Egorov, Yuri P.; Erofeenko, Igor V.; Karev, Nikolai V.; Kozlov, Yuri S.; Kudish, Viktor B.; Kolbasov, Valery K.; and Bobchenok, Meri I., 4,293,238, Cl. 405-175.000.
Familiant, Harold M.: See—
Plischke, LeMoyné W.; Familiant, Harold M.; and Kelly, Darrell A., 4,293,614, Cl. 428-370.000.
Fantasia: See—
Hilbert, Robert S., 4,293,196, Cl. 350-452.000.
Farcasiu, Dan: See—
Klemann, Lawrence P.; Newman, Gerald H.; Stogryn, Eugene L.; Whitney, Thomas A.; and Farcasiu, Dan, 4,293,623, Cl. 429-194.000.
Farcasiu, Malvina; and Whitehurst, Darrell D., to Mobil Oil Corporation. Dehydroxylation and/or demercaptolation of heavy petroleum oils. 4,293,404, Cl. 208-214.000.
Farmitalia Carlo Erba S.p.A.: See—
Gandolfi, Carmelo; Pellegata, Renato; Faustini, Franco; and Fumagalli, Angelo, 4,293,705, Cl. 560-53.000.
Farmstead Industries, Div. of Farmhand, Inc.: See—
Sassmann, Stanley W., 4,292,927, Cl. 119-16.000.
Farr, David R.; and Magnolato, Daniele, to Societe d'Assistance Technique pour Produits Nestle S.A. Process for debittering a protein hydrolysate and the debittered hydrolysate obtained by this process. 4,293,583, Cl. 426-657.000.
Farrar, James G.: See—
St. Lawrence, David S.; Morris, Robert; and Farrar, James G., 4,293,266, Cl. 414-411.000.
Fatula, James J., to Ryman Engineering Company. Belt grinder for grinding non-circular workpiece. 4,292,767, Cl. 51-145.00R.
Faustini, Franco: See—
Gandolfi, Carmelo; Pellegata, Renato; Faustini, Franco; and Fumagalli, Angelo, 4,293,705, Cl. 560-53.000.
Feder, Ralph: See—
Chaudhari, Praveen; Chou, Ned J.; Feder, Ralph; Fowler, Alan B.; and VanVechten, James A., 4,293,374, Cl. 156-628.000.
Feinberg, Billie: See—
Vis, Arthur D.; and Feinberg, Billie, 4,292,740, Cl. 33-172.00E.
Feldstein, Nathan. Process using activated electroless plating catalysts. 4,293,591, Cl. 427-97.000.
Fellman, Marc M.; and Wright, Wade S. Electrical award signaling means for a pinball machine. 4,293,131, Cl. 273-121.00A.
Felthuis, Jacob; and Rumphorst, Jacobus A., to Hoogovens Ijmuiden B.V.; and Zimmermann & Jansen GmbH, a part interest. Closure plate for hot blast slide valves. 4,292,993, Cl. 137-340.000.
Ferranti Limited: See—
Liebing, Alan P., 4,292,854, Cl. 74-5.340.
Ferraris Development and Engineering Co., Ltd.: See—
Williams, Garnet M. E.; Hutton, Stanley P.; and Bushman, John A., 4,292,853, Cl. 73-861.790.
Ferris, Lester W.: See—
Moretti, Anthony L.; and Ferris, Lester W., 4,292,692, Cl. 2-418.000.
Ferry, Paul B.: See—
McCormick, James T.; Ferry, Paul B.; and Hall, John C., 4,293,089, Cl. 228-215.000.
Feuerstake, Ewald; and Schwarz, Klaus, to Mannesmann DeMag AG. Ozone pipe for ozone production plant. 4,293,775, Cl. 250-535.000.

- Fickel, R. Gene: See—
Landis, Arthur M.; Broughton, Donald B.; and Fickel, R. Gene, 4,293,346, Cl. 127-46.00A.
Fidrych, Alfred W., to Harvey Hubbell Incorporated. Split cable grip closure and method of forming same. 4,293,157, Cl. 294-86.00G.
Field, Joseph H.; and McCrea, Donald H., to Benfield Corporation. Selective removal of H₂S from gas mixtures containing CO₂ and H₂S. 4,293,531, Cl. 423-232.000.
Fields, Carlo, to Southern Pacific Transportation Company. Solid state flasher relay. 4,293,795, Cl. 315-200.00A.
Filer, Burt, to Filer, Sandra Lee. Tube removal machine. 4,292,731, Cl. 29-726.000.
Filer, Sandra Lee: See—
Filer, Burt, 4,292,731, Cl. 29-726.000.
Filterwerk Mann & Hummel GmbH: See—
Bendig, Lothar, 4,292,949, Cl. 123-556.000.
Fincher, Paul A.; and Eklund, David R. Apparatus and method for separating case flaps. 4,293,086, Cl. 225-1.000.
Finetex Incorporated: See—
Elmi, Steele J., 4,293,544, Cl. 424-60.000.
Fink, Herbert; Huebner, Klaus; Dinklage, Horst; and Ottofrickestein, Hans, to Rohm GmbH. Method of finishing fibers or fabrics with dispersions of hydrophilic acrylic resins. 4,293,600, Cl. 427-385.500.
Finkelmann, Heino: See—
Portugall, Michael; Finkelmann, Heino; and Ringsdorf, Helmut, 4,293,435, Cl. 252-299.010.
Firestone Tire & Rubber Company, The: See—
Loeffler, Earl F.; and Weyand, Harley P., Jr., 4,293,358, Cl. 156-131.000.
Fischer, Helmut; Ott, Albert; and Stegmüller, Willi. Apparatus for measuring the thickness of thin layers. 4,293,767, Cl. 250-308.000.
Fisco Products Limited: See—
Burton, Stanley J., 4,293,058, Cl. 188-65.100.
Fisner, William L.: See—
Guttman, Murray M.; and Fisner, William L., 4,293,417, Cl. 210-230.000.
Fisons Limited: See—
Cairns, Hugh; and Lee, Thomas B., 4,293,541, Cl. 424-45.000.
Fitch, John L., to Mobil Oil Corporation. Solvent convection technique for recovering viscous petroleum. 4,293,035, Cl. 166-273.000.
Fitzgerald, William V., to RCA Corporation. Vertical deflection circuit. 4,293,803, Cl. 315-397.000.
Flasche, Gunter: See—
Funk, Hans-Wolfgang; Frank, Kurt; and Flasche, Gunter, 4,293,790, Cl. 313-101.000.
Flint, William L.; and Pilette, Yvan P., to Du Pont de Nemours, E. I., and Company. Photopolymerizable composition with polymeric binder. 4,293,635, Cl. 430-271.000.
Florent, Jean; Lunel, Jean; and Maney, Denise, to Rhone-Poulenc Industries. Anti-coccidial substance and its preparation. 4,293,650, Cl. 435-119.000.
Flowers, Robert L.: See—
Long, Howard W.; and Flowers, Robert L., 4,292,786, Cl. 53-434.000.
Floyd, Middleton B., Jr.: See—
Bernady, Karel F.; Floyd, Middleton B., Jr.; Poletto, John F.; Schaub, Robert E.; and Weiss, Martin J., 4,293,704, Cl. 556-442.000.
Flusche, Frederick O.; Tan, Kwang G.; and Wright, Ralph W., to International Business Machines Corporation. Reconfigurable key-in-storage means for protecting interleaved main storage. 4,293,910, Cl. 364-200.000.
FMC Corporation: See—
Milberger, Lionel J., 4,293,148, Cl. 285-90.000.
Focke & Co.: See—
Focke, Heinz; and Liedtke, Kurt, 4,293,068, Cl. 206-264.000.
Focke, Heinz; and Liedtke, Kurt, to Focke & Co. Multi-layered foil cigarette pack with strip sealed tear flap. 4,293,068, Cl. 206-264.000.
Fogarty, Thomas J.; and Chin, Albert K., to Fogarty, Thomas J. Dilatation catheter apparatus and method. 4,292,974, Cl. 128-344.000.
Fogg, Lewis W.; Metzler, Robert W.; Satterfield, H. Eugene; and Scott, Eion G., to Control Data Corporation. Modular transportable controlled environment agriculture facility. 4,292,762, Cl. 47-17.000.
Fogg, O. Douglas: See—
Haag, George A.; Fogg, O. Douglas; Greenley, Gordon A.; Shepard, Steve A.; and Terry, F. Duncan, 4,293,925, Cl. 364-900.000.
Fontanelli, Renzo: See—
Di Battista, Piero; Fontanelli, Renzo; Gratani, Francesco; and Nelli, Giuseppe, 4,293,466, Cl. 260-45.80N.
Forbes, Brian K.: See—
Cattler, Robert D.; and Forbes, Brian K., 4,293,909, Cl. 364-200.000.
Ford Motor Company: See—
Boyer, Wesley D., 4,293,814, Cl. 324-166.000.
Brittain, William J., 4,293,947, Cl. 370-89.000.
Graessley, William J., 4,292,948, Cl. 123-490.000.
Kuhn, Robert L.; and Koston, Charles C., 4,293,744, Cl. 200-19.00R.
Theodore, Ares N., 4,293,477, Cl. 260-29.15B.
Ford, Robert S. Training splint for wrist-ganglion. 4,292,963, Cl. 128-87.00R.
Forestier, Serge: See—
Lang, Gerard; and Forestier, Serge, 4,293,542, Cl. 424-47.000.
Forrest, Michael R.; and Kohn, Alfred, to Michael Forrest, Inc. Method of making a composite fur garment. 4,292,690, Cl. 2-65.000.

- Forrest, Michael R.; and Kohn, Alfred, to Michael Forrest, Inc. Composite fur pelt and garment. 4,292,691, Cl. 2-65.000.
Fortune, William S. Heavy duty desoldering tool. 4,292,706, Cl. 15-341.000.
Forum, Inc.: See—
Dziubaty, Theodore J., 4,293,900, Cl. 362-342.000.
Fost, Dennis L., to New England Nuclear Corporation. Autofluorogram and composition and method for making the same. 4,293,436, Cl. 252-301.10R.
Foster, Francis W.: See—
Neumeyer, Tom A.; and Foster, Francis W., 4,292,871, Cl. 83-661.000.
Foster, George W.; and Bonneyrat, Alain M., to Gilson Medical Electronics (France). Stepping motor control apparatus. 4,293,807, Cl. 318-696.000.
Fowell, Peter A.: See—
Bowen, Griffith; and Fowell, Peter A., 4,293,615, Cl. 428-412.000.
Fowler, Alan B.: See—
Chaudhari, Praveen; Chou, Ned J.; Feder, Ralph; Fowler, Alan B.; and VanVechten, James A., 4,293,374, Cl. 156-628.000.
Fox, Robert B.; and Kim, Oh-Kil, to United States of America, Navy. Electrically conductive polymeric compositions. 4,293,452, Cl. 252-518.000.
Fox, Rodney T., to Reckitt & Colman Products Limited. Combustible compositions and processes for their production. 4,293,312, Cl. 44-1.00R.
Fox, Rodney T., to Reckitt & Colman Products Limited. Combustible compositions and processes for their production. 4,293,313, Cl. 44-1.00R.
Fracassi, Pietro: See—
Del Re, Pietrantonio; and Fracassi, Pietro, 4,293,916, Cl. 364-571.000.
Frame, Robert R., to UOP Inc. Catalytic composite, method of manufacture, and process for use. 4,293,442, Cl. 252-428.000.
Francis, Norman L.: See—
Bird, Alvin N., Jr.; Francis, Norman L.; and Thomas, Albert L., Jr., 4,293,217, Cl. 356-37.000.
Frank, Kurt: See—
Funk, Hans-Wolfgang; Frank, Kurt; and Flasche, Gunter, 4,293,790, Cl. 313-101.000.
Frano, Francis G., to Illinois Tool Works Inc. Reinforcing sealing sheet metal fastener anchor. 4,293,261, Cl. 411-85.000.
Freeman Chemical Corporation: See—
Svoboda, Glenn R., 4,293,659, Cl. 525-28.000.
Freund, Jürgen: See—
Lakra, Ruhama J.; Freund, Jürgen; and Rauschert, Gerd, 4,293,383, Cl. 376-290.000.
Friedrich Grohe Armaturenfabrik GmbH & Co.: See—
Bernat, Georg, 4,292,997, Cl. 137-454.600.
Fritz Gegauf AG, Bernina-Nachmaschinenfabrik Steckborn: See—
Widmer, Hans, 4,292,905, Cl. 112-121.110.
Frolov, Sergei A.: See—
Dunaevsky, Vladimir I.; Boidenko, Nikolai G.; Samarjin, Alexei P.; Levit, Viktor M.; Zapara, Boris M.; Ivanov, Boris N.; Frolov, Sergei A.; Voronin, Rostislav A.; Belozero, Nikolai P.; Momot, Valery I.; Stusenko, Yuri A.; and Samoilov, Vladimir A., 4,293,101, Cl. 242-56.400.
Fuji Photo Film Co., Ltd.: See—
Furutachi, Nobuo; and Seto, Nobuo, 4,293,691, Cl. 544-140.000.
Itoh, Isamu; Hashimura, Taiji; and Ishikawa, Takatoshi, 4,293,639, Cl. 430-393.000.
Ohnishi, Masahiro; and Kimura, Tsutomu, 4,293,202, Cl. 354-5.000.
Takahashi, Osamu; and Sakaguchi, Shinji, 4,293,641, Cl. 430-502.000.
Fuji Seal Industry Co., Ltd.: See—
Fujio, Masaaki, 4,293,364, Cl. 156-344.000.
Fujii, Yoshishige; Nagao, Syozo; and Kumazawa, Shunji, to Toray Industries, Inc. Fluid separation apparatus. 4,293,418, Cl. 210-321.100.
Fujimura, Hajime; Hiramatsu, Yasuzo; Yabuuchi, Takahiro; Hisaki, Masakatu; Takikawa, Katsuo; Honna, Takaji; Miyake, Hidekazu; and Kajitani, Makoto, to Taiho Pharmaceutical Company Limited. Novel 1,1,3,5-substituted biuret compound and a pharmaceutical composition containing the same. 4,293,713, Cl. 564-38.000.
Fujio, Masaaki, to Fuji Seal Industry Co., Ltd. Method and machine for opening up a cylindrical film tube and fitting it over an object. 4,293,364, Cl. 156-344.000.
Fujisawa, Kazuo: See—
Yamaguchi, Hisao; and Fujisawa, Kazuo, 4,292,849, Cl. 73-643.000.
Fujita, Yoshiki: See—
Kakumoto, Ken-Ichi; and Fujita, Yoshiki, 4,293,171, Cl. 308-188.000.
Fujitsu Limited: See—
Matsui, Kiyoshi; Arai, Katsuyuki; and Shinbashi, Sueo, 4,293,891, Cl. 361-383.000.
Muraoka, Takatoshi; Uchida, Keiichi; Koshino, Minoru; Motegi, Masanori; and Nagasawa, Shigeru, 4,293,941, Cl. 364-200.000.
Takagi, Mikio; Maeda, Mamoru; and Kamioka, Hajime, 4,293,589, Cl. 427-93.000.
Takagi, Mikio; Maeda, Mamoru; and Kamioka, Hajime, 4,293,590, Cl. 427-93.000.
Tanaka, Yoshikazu; Shirai, Hitoshi; and Kan'o, Yoshiharu, 4,293,931, Cl. 365-222.000.
Fukuda, David S.: See—
Abbott, Bernard J.; and Fukuda, David S., 4,293,482, Cl. 260-112.50R.

- Abbott, Bernard J.; and Fukuda, David S., 4,293,490, Cl. 260-112.50K.
- Fukuda, Takeshi; and Tutida, Tomiyoshi, to Shin-Etsu Chemical Co., Ltd. Rubber-padded frames of eye spectacles and method for preparing same. 4,293,201, Cl. 351-178.000.
- Fukushima, Toshihiko: See—
Kamejima, Kohji; Tanaka, Hideki; Kano, Minoru; and Fukushima, Toshihiko, 4,292,811, Cl. 62-56.000.
- Fulton, Hugh C. Pressurized gas filling head. 4,293,009, Cl. 141-311.00R.
- Fumagalli, Angelo: See—
Gandolfi, Carmelo; Pellegata, Renato; Faustini, Franco; and Fumagalli, Angelo, 4,293,705, Cl. 560-53.000.
- Fung, Bing: See—
West, Jerry B.; Kretzschmar, John L.; and Fung, Bing, 4,293,815, Cl. 324-254.000.
- Funk, Hans-Wolfgang; Frank, Kurt; and Flasche, Gunter, to Robert Bosch GmbH. Image converter having cylindrical housing and photocathode separated by spacing element from luminescent screen on frustum. 4,293,790, Cl. 313-101.000.
- Furendal, Allan R. B.; Larsson, Bernt; and Nilsson, Erik R., to AB Bofors. Surface coating method employing a temporary bonding. 4,293,596, Cl. 427-160.000.
- Furutachi, Nobuo; and Seto, Nobuo, to Fuji Photo Film Co., Ltd. Method for preparing magenta couplers having thioether groups. 4,293,691, Cl. 544-140.000.
- Fyson, John R.; and Levenson, Gerald I. P., to Eastman Kodak Company. Method for alleviating partial inactivation of color couplers. 4,293,638, Cl. 430-373.000.
- G. D. Searle & Co.: See—
Davino, Arthur A., 4,293,648, Cl. 435-70.000.
- Gaddes, Robert N. Load support device for heat furnaces. 4,293,299, Cl. 432-234.000.
- GAF Corporation: See—
Beavan, Elton L.; and Moynahan, E. Bradley, 4,293,642, Cl. 430-534.000.
- Gruber, Bruce A.; and Lorenz, Donald H., 4,293,714, Cl. 564-249.000.
- Parthasarathy, R.; and Hort, Eugene V., 4,293,444, Cl. 252-432.000.
- Gaffney, Brian P.: See—
Chressanthis, Andrew G.; Halpern, Henry M.; and Gaffney, Brian P., 4,293,856, Cl. 343-5.0CF.
- Gago, Ignace, to Interlox. Coated calcium peroxide particles useful in the treatment of water. 4,293,426, Cl. 210-759.000.
- Gaida, Wolfram: See—
Stahle, Helmut; Koppe, Herbert; Kummer, Werner; Hoeske, Wolfgang; Gaida, Wolfram; and Pichler, Ludwig, 4,293,564, Cl. 424-273.00R.
- Gailey, J. Lynn: See—
Chalmers, Alexander A.; and Gailey, J. Lynn, 4,292,781, Cl. 52-547.000.
- Gale, Walter W.; Puerto, Maura C.; Ashcraft, Thomas L.; Saunders, Rhoderick K.; and Reed, Ronald L., to Exxon Production Research Company. Propoxylated ethoxylated surfactants and method of recovering oil therefrom. 4,293,428, Cl. 252-8.55D.
- Gambro AB: See—
Riede, Gerhard; Larsson, Lars-Ake L.; Andersson, Roland J. E.; Jossan, Sven A.; and Traven, Lars J. C., 4,293,409, Cl. 210-96.200.
- Gamell, Joseph A., to Joseph Gamell Industries, Inc. Turbo-electric power plant and process. 4,293,777, Cl. 290-52.000.
- Gandolfi, Carmelo; Pellegata, Renato; Faustini, Franco; and Fumagalli, Angelo, to Farmitalia Carlo Erba S.p.A. 13,14-Dehydro-11-deoxy-prostaglandins and process for their preparation. 4,293,705, Cl. 560-53.000.
- Ganellin, Charon R.: See—
Durant, Graham J.; Emmett, John C.; and Ganellin, Charon R., 4,293,697, Cl. 546-121.000.
- Durant, Graham J.; Emmett, John C.; and Ganellin, Charon R., 4,293,699, Cl. 546-121.000.
- Gansar, David: See—
Petty, Terry D.; Costello, Carmon R.; Rao, Gude P.; and Gansar, David, 4,293,239, Cl. 405-195.000.
- Gansley, Byron J.: See—
Phelps, Harold E.; and Gansley, Byron J., 4,293,013, Cl. 144-193.00A.
- Garbelman, David L.: See—
Swisher, George W., Jr.; Garbelman, David L.; and Shaw, Arthur G., 4,293,228, Cl. 366-25.000.
- Garbis, Dennis: See—
Hill, Lawrence; Garbis, Dennis; and Heller, Robert, 4,293,755, Cl. 219-10.410.
- Garcia, Jose B.: See—
Bell, William T.; and Garcia, Jose B., 4,292,895, Cl. 102-306.000.
- Garcia, Zulma C.: See—
Champion, Carolyn; Wolcott, Judith; Hart, Barbara; and Garcia, Zulma C., 4,292,975, Cl. 128-498.000.
- Gardner, Hugh C., to Union Carbide Corporation. Thermosetting polyester resin composition. 4,293,686, Cl. 528-192.000.
- Gardner, Roland C.; and Mortellito, Ronald, to Clevepak Corporation. Container seam. 4,293,090, Cl. 229-5.600.
- Gartzke, Rudolph E. Ice making apparatus. 4,292,816, Cl. 62-345.000.
- Gaschenko, Viktor P.: See—
Kopylov, Alexei A.; Kuzmenko, Valentin T.; Stepanov, Alexandr N.; Gaschenko, Viktor P.; Kaznachevsky, Nikolai A.; Nosovitsky, Alexandr Y.; Misikov, Ivan I.; Shapiro, Alexandr I.; Skakunov, Ivan G.; Markin, Valentin G.; Konstantinov, Alexei K.; Abramian, Eduard S.; Soroka, Arseny M.; and Zinchenko, Yakov A., 4,292,928, Cl. 119-17.000.
- Gascon, Lorenzo. Rake. 4,292,794, Cl. 56-400.160.
- Gaston, Charles A.; Kirk, Joseph P.; and Wasik, Chester A., to International Business Machines Corporation. Optical system and technique for unambiguous film thickness monitoring. 4,293,224, Cl. 356-357.000.
- Gaughan, Edmund J.: See—
Pallos, Ferenc M.; and Gaughan, Edmund J., 4,293,701, Cl. 546-335.000.
- Gauthier-Lafaye, Jean; and Perron, Robert, to Rhone-Poulenc Industries. Preparation of acetaldehyde. 4,293,718, Cl. 568-487.000.
- Gawthorpe, Janet A.: See—
Simpson, Roger J.; Gawthorpe, Janet A.; and Lawrence, C. Alexander, 4,293,307, Cl. 23-230.00B.
- Gazdag, Andras: See—
Pataki, Jozsef; Bucsi, Jozsef; Bona, Istvan; Szilvasi, Endre; Gazdag, Andras; Koty, Antal; and Hidvegi, Ferenc, 4,292,996, Cl. 137-393.000.
- Gearhart Industries, Inc.: See—
Hallmark, Bobby J., 4,292,842, Cl. 73-155.000.
- Gehle, Warren D.: See—
Smith, Kendall O.; and Gehle, Warren D., 4,292,920, Cl. 118-425.000.
- Gehr, Marvin M.; and Pabian, Howell D., to Telex Communications, Inc. Diversity reception system. 4,293,955, Cl. 455-276.000.
- General Electric Company: See—
Arendt, Ronald H., 4,293,534, Cl. 423-593.000.
- Arendt, Ronald H., 4,293,535, Cl. 423-593.000.
- Bessmer, Stanley J.; and Lampe, Warren R., 4,293,597, Cl. 427-186.000.
- Brezosky, Bernard J., 4,293,170, Cl. 308-161.000.
- Brooks, George D.; and Bushey, Donald J., Sr., 4,292,878, Cl. 86-48.000.
- King, Harold B., 4,292,788, Cl. 53-500.000.
- McFadyen, Robert J., 4,293,822, Cl. 330-254.000.
- Morris, Jesse L., 4,292,852, Cl. 73-827.000.
- Smith, Alfred H., Jr.; and Beers, M. Dale, 4,293,616, Cl. 428-447.000.
- Snow, Barton H., 4,292,802, Cl. 60-204.000.
- Takekoshi, Tohru; and Klopfer, Howard J., 4,293,683, Cl. 528-180.000.
- Takekoshi, Tohru, 4,293,684, Cl. 528-185.000.
- Vavrek, Robert M., 4,293,770, Cl. 250-445.00R.
- Wilkes, Colin; and Hilt, Milton B., 4,292,801, Cl. 60-39.060.
- Zdaniewski, Joseph J.; Penn, William B.; and Balke, Roy L., 4,293,784, Cl. 310-45.000.
- General Instrument Corporation: See—
Hill, Lawrence; Garbis, Dennis; and Heller, Robert, 4,293,755, Cl. 219-10.410.
- General Motors Corporation: See—
Brewer, Earl G., 4,292,851, Cl. 73-762.000.
- King, Dallas E., 4,293,789, Cl. 310-239.000.
- General Signal Corporation: See—
Link, John R., 4,293,291, Cl. 418-104.000.
- General Tire & Rubber Co., The: See—
Bible, Dennis E.; Crano, Richard N.; and Welch, John A., 4,293,016, Cl. 152-158.000.
- Genovese, Nicholas J.: See—
Stoffels, Carl A.; and Genovese, Nicholas J., 4,292,867, Cl. 82-47.000.
- Geoffroy, Jean-Claude: See—
Godard, Pierre; and Geoffroy, Jean-Claude, 4,293,029, Cl. 165-29.000.
- George, Clifford L.; and Olson, Jon S., to Xerox Corporation. Sheet set separation device. 4,293,214, Cl. 355-14.00R.
- George, Larry T., to Wallace Murray Corporation. Anodized seal nose for damper. 4,293,136, Cl. 277-12.000.
- George, Robert W.; Miller, Casper W.; and Rapey, Kenneth, to National Can Corporation. Method of lining closures. 4,293,510, Cl. 264-40.700.
- Gerard, Thomas J., to Weyerhaeuser Company. Reinforced container with integral divider. 4,293,091, Cl. 229-27.000.
- Germann, Willy, to BBC Brown, Boveri & Company Ltd. Apparatus for manufacturing cold-work hardened cylinders. 4,292,828, Cl. 72-54.000.
- Gerry, Martin E. Inductive-capacitive cyclic charge-discharge ignition system. 4,293,797, Cl. 315-209.00R.
- Gerry, Martin E. Inductive-capacitive cyclic charge-discharge ignition system. 4,293,798, Cl. 315-209.00R.
- Getewent Gesellschaft für technische und wissenschaftliche Energieumsatzentwicklungen m.b.H.: See—
Bachl, Herbert, 4,293,278, Cl. 416-186.00R.
- Gewerkschaft Eisenhütte Westfalen: See—
Rosenberg, Harry; and Holken, Norbert, 4,293,247, Cl. 405-296.000.
- Geyer, Joseph E.; Rehr, Henry W.; Schutz, Rudolph W.; and Weis, Rudolf R., to Crown Zellerbach Corporation. Apparatus for applying labels or the like. 4,293,365, Cl. 156-364.000.
- Giannelli, Joseph F., to Ecodyne Corporation. Slotted sheet filter element. 4,293,414, Cl. 210-193.000.
- Gibb, William D.; and Clement, Donald E., to Northern Telecom Limited. Hands free answer intercom. 4,293,740, Cl. 179-99.00A.
- Giesselmann, Ewald: See—
Cordes, Gunter; Giesselmann, Ewald; and Munch, Ulrich, 4,293,565, Cl. 424-285.000.

- Gilbert, John J. Connection assembly for rigid stem dial gauge. 4,292,845, Cl. 73-362.100.
- Gilbride, Andrew J.; and Wickers, Francis A., to USM Corporation. Presser-foot apparatus. 4,292,907, Cl. 112-236.000.
- Gillette Company, The: See—
Packham, Charles C., 4,292,737, Cl. 30-43.920.
- Gilman, Frederick C. Vertical axis wind turbine for generating usable energy. 4,293,274, Cl. 416-51.000.
- Gilson Medical Electronics (France): See—
Foster, George W.; and Bonneyrat, Alain M., 4,293,807, Cl. 318-696.000.
- Gilts, Richard G.; Hille, Earl A.; Kleine, Albert W., Jr.; and Shamp, Donald E., to Libbey-Owens-Ford Company. Pivotal shipping rack supporting apparatus. 4,293,264, Cl. 414-38.000.
- Glass, Howard L., to Rockwell International Corporation. Growth of single-crystal magnetoplumbite. 4,293,372, Cl. 156-624.000.
- Glenn, Robert G., to Westinghouse Electric Corp. Gas turbine combustion chamber. 4,292,810, Cl. 60-757.000.
- Globus, Richard D.: See—
Globus, Ronald P.; Globus, Richard D.; and Globus, Stephen E., 4,293,057, Cl. 185-37.000.
- Globus, Ronald P.; Globus, Richard D.; and Globus, Stephen E., to Globuscope, Inc. Spring motor especially suitable for use in a panoramic camera. 4,293,057, Cl. 185-37.000.
- Globus, Stephen E.: See—
Globus, Ronald P.; Globus, Richard D.; and Globus, Stephen E., 4,293,057, Cl. 185-37.000.
- Globuscope, Inc.: See—
Globus, Ronald P.; Globus, Richard D.; and Globus, Stephen E., 4,293,057, Cl. 185-37.000.
- Godard, Pierre; and Geoffroy, Jean-Claude, to Saft-Societe des Accumulateurs Fixes et de Traction. Temperature control device for a heat pump. 4,293,029, Cl. 165-29.000.
- Goel, Prabhakar: See—
Dasgupta, Sumit; Goel, Prabhakar; and Williams, Thomas W., 4,293,919, Cl. 364-716.000.
- Goetzmann, Claus; and Rau, Peter, to Kraftwerk Union Aktiengesellschaft. Nuclear reactor having control rod holding latch. 4,293,381, Cl. 376-230.000.
- Goguen, Clarence J. Ventilated cushions. 4,292,703, Cl. 5-468.000.
- Goldberger, William M.: See—
Parekh, Bhupendra K.; and Goldberger, William M., 4,293,099, Cl. 241-24.000.
- Goldenberg, Carol: See—
Zeidman, Zvi; Goldenberg, Carol; and Grinbaum, Zvi, 4,293,045, Cl. 173-121.000.
- Golder, John C. Solar oven. 4,292,957, Cl. 126-451.000.
- Goloff, Alexander; and Denning, Ralph E., to Caterpillar Tractor Co. Transmission-differential combination. 4,293,050, Cl. 180-6.260.
- Gomi, Yoshifumi, to Kabushiki Kaisha Suwa Seikosha. Structure for a linear motor for a printer. 4,293,235, Cl. 400-322.000.
- Goodin, Richard D.: See—
Hallcher, Richard C.; Goodin, Richard D.; and Baizer, Manuel M., 4,293,392, Cl. 204-59.00R.
- Hallcher, Richard C.; Goodin, Richard D.; and Baizer, Manuel M., 4,293,393, Cl. 204-59.00R.
- Gookins, William L.; and King, Junior K. Monitor means and method for grain bin. 4,293,854, Cl. 340-615.000.
- Gordon, Robert; King, Harry A.; Springrose, James V.; and Cuddihy, Robert W., to Cargill, Incorporated; and Structural Composite Industries, Inc. Filament composite railroad car. 4,292,898, Cl. 105-238.00R.
- Gore, Colin E.; and Coulter, John P., to Wool Development International Limited. Strand break-out device. 4,292,798, Cl. 57-86.000.
- Gorman, Susan B.; Thompson, Ralph B.; and Yonan, Edward E., to PPG Industries, Inc. Preparation of N-benzoyloxycarbonyl aspartic acid. 4,293,706, Cl. 560-163.000.
- Gould, George E. Fireplaces and attachments. 4,292,951, Cl. 126-120.000.
- Gould Inc.: See—
Nagy, Albert E., 4,293,617, Cl. 428-469.000.
- Graessley, William J., to Ford Motor Company. Method for extending the range of operation of an electromagnetic fuel injector. 4,292,948, Cl. 123-490.000.
- Grant, Peter S., to Weyerhaeuser Company. Log handling and transport system. 4,293,155, Cl. 294-75.000.
- Granzow, Albrecht H., to American Cyanamid Company. Phosphine oxide flame retarded, rubber-modified, polyphenylene ether resin compositions. 4,293,464, Cl. 260-45.70P.
- Granzow, Albrecht H., to American Cyanamid Company. Bis phosphine oxide flame retarded, rubber-modified, polyphenylene ether resin compositions. 4,293,465, Cl. 260-45.70P.
- Grasselli, Robert K.: See—
Suresh, Dev D.; Bremer, Noel J.; and Grasselli, Robert K., 4,293,443, Cl. 252-432.000.
- Gratani, Francesco: See—
Di Battista, Piero; Fontanelli, Renzo; Gratani, Francesco; and Nelli, Giuseppe, 4,293,466, Cl. 260-45.80N.
- Gray, David L. Universal fishing rod support. 4,293,113, Cl. 248-518.000.
- Graybeal, Carl N.; Rogers, Basil E.; Cox, Joseph V.; and Rogers, Roy R., to Graybeal, Carl N. Mine roof bolt assembly guard. 4,293,243, Cl. 405-259.000.
- Green, Alvin W. Method and equipment for a wrap-around upflow submerged anaerobic filter for sewage. 4,293,421, Cl. 210-603.000.
- Greene, William J.: See—
Hoyt, Harold C., Jr.; and Greene, William J., 4,293,756, Cl. 219-133.000.
- Greenley, Gordon A.: See—
Haag, George A.; Fogg, O. Douglas; Greenley, Gordon A.; Shepard, Steve A.; and Terry, F. Duncan, 4,293,925, Cl. 364-900.000.
- Greenwald, Robert J. Fecal examination device (B). 4,293,405, Cl. 209-17.000.
- Greenwood, John C., to International Standard Electric Corporation. Method of making transducer. 4,293,373, Cl. 156-628.000.
- Greig, John M.: See—
Metcalfe, Ronald S.; and Greig, John M., 4,293,147, Cl. 285-39.000.
- Griffiths, David: See—
Wheaton, John E. G.; Griffiths, David; and Learner, Richard C. M., 4,293,225, Cl. 356-417.000.
- Griggs, Calvin: See—
Shea, John J.; and Griggs, Calvin, 4,292,693, Cl. 3-1.900.
- Grinbaum, Zvi: See—
Zeidman, Zvi; Goldenberg, Carol; and Grinbaum, Zvi, 4,293,045, Cl. 173-121.000.
- Groenenboom, Maarten, to Hazemeijer B.V. Current measuring system. 4,293,813, Cl. 324-117.00R.
- Gros, Pierre; Millouet, Jean; and Staron, Philippe, to Societe Nationale Elf Aquitaine (Production). Method of seismic exploration. 4,293,935, Cl. 367-43.000.
- Gross, Franz, to Siemens Aktiengesellschaft. Arrangement for suppressing interference waves and harmonic waves in traveling wave tubes with a short circuiting slide in the output wave guide. 4,293,828, Cl. 333-27.000.
- Grove, Russell E. Manually operable chain drive for a boat loader. 4,293,267, Cl. 414-462.000.
- Grove Valve and Regulator Company: See—
Cazzaniga, Italo; and Pasquini, Ottorino, 4,292,989, Cl. 137-72.000.
- Grove, William S., to PPG Industries, Inc. Substituted diphenyl ethers having herbicidal activity. 4,293,329, Cl. 71-88.000.
- Grove, William S.: See—
Richter, Sidney B.; and Grove, William S., 4,293,707, Cl. 562-472.000.
- Growth International Industries Corp.: See—
Yates, George, Jr., 4,293,073, Cl. 206-519.000.
- Gruber, Bruce A.; and Lorenz, Donald H., to GAF Corporation. Copolymerizable, ultraviolet light absorber 4-alkoxy-2'-allyloxybenzazines. 4,293,714, Cl. 564-249.000.
- Gruenberg, Eberhard; and Muller, Roswitha, to Henkel Kommanditgesellschaft auf Aktien. Thermoplastic polymer composition materials for pretreating paper. 4,293,458, Cl. 260-17.4GC.
- Grumman Aerospace Corporation: See—
Savio, Ferdinando; and Peterson, William, 4,293,361, Cl. 156-242.000.
- GTE Automatic Electric Labs Inc.: See—
Stelte, David J.; and Kobylar, Alex W., 4,293,738, Cl. 179-18.0FC.
- Vonder, David L., 4,293,179, Cl. 339-176.0MP.
- Guile, Donald L.: See—
Corbett, Daniel W.; and Guile, Donald L., 4,293,439, Cl. 252-316.000.
- Guim, Armando. Hand-held fishing reel. 4,293,104, Cl. 242-96.000.
- Gulf Research & Development Company: See—
Beach, David L.; and Harrison, James J., 4,293,502, Cl. 260-439.00R.
- Beach, David L.; and Kobylinski, Thaddeus P., 4,293,724, Cl. 585-457.000.
- Beach, David L.; and Kobylinski, Thaddeus P., 4,293,725, Cl. 585-523.000.
- Beach, David L.; and Kobylinski, Thaddeus P., 4,293,726, Cl. 585-523.000.
- Beach, David L.; and Harrison, James J., 4,293,727, Cl. 585-526.000.
- Swift, Harold E.; Innes, Robert A.; and Adams, Phillip, 4,293,716, Cl. 564-480.000.
- Guth, Richard U. Breath test mouthpiece. 4,292,978, Cl. 128-730.000.
- Guthrie, David B.: See—
Cheng, William J.; Guthrie, David B.; and Leindecker, Donald M., 4,293,429, Cl. 252-18.000.
- Gutleber, Frank S., to United States of America, Army. Bi-orthogonal PCM communications system employing multiplexed noise codes. 4,293,953, Cl. 375-25.000.
- Guttman, Murray M.; and Fisser, William L., to Envirotech Corporation. Filter press. 4,293,417, Cl. 210-230.000.
- H & H Tube & Mfg. Co.: See—
Lee, Marlow, 4,292,958, Cl. 126-448.000.
- Haag, George A.; Fogg, O. Douglas; Greenley, Gordon A.; Shepard, Steve A.; and Terry, F. Duncan, to Hewlett-Packard Company. Apparatus and method for indicating a minimum degree of activity of digital signals. 4,293,925, Cl. 364-900.000.
- Haas, Richard G., to Brown Company. Process and machine for fastening a closure member to a container. 4,293,354, Cl. 156-69.000.
- Haberle, Friedrich: See—
Kress, Dieter; and Haberle, Friedrich, 4,293,252, Cl. 408-224.000.
- Hackenberg, Hubert: See—
Wagner, Karl; Engelsmann, Dieter; Hackenberg, Hubert; and Stiefel, Peter, 4,293,204, Cl. 354-21.000.
- Hadari, Gideon, to Israel Aircraft Industries Ltd.; and Ben Gurion Industries Ltd. Excessive descent-rate warning system particularly useful for helicopters. 4,293,840, Cl. 340-27.0AT.

- Hagborg, Winston E.: See—
Davis, Gayron N.; Sellers, Larry S.; and Hagborg, Winston E., 4,292,918, Cl. 118-33.000.
- Hagedorn, Myrna L.: See—
Sprecker, Mark A.; Sanders, James M.; Schreiber, William L.; Watkins, Hugh; Vinals, Joaquin F.; Shuster, Edward J.; O'Rourke, Thomas J.; Hagedorn, Myrna L.; and Klemarczyk, Philip, 4,293,453, Cl. 252-522.00R.
- Hahn, Klaus; Naarmann, Herbert; and Penzien, Klaus, to BASF Aktiengesellschaft. Flame retardant polystyrene, 4,293,656, Cl. 521-88.000.
- Hahn, Steven: See—
Barrett, Edward E.; Hahn, Steven; Lensky, Albert; Pinczewski, Morris; and Sobelman, Seymour, 4,293,088, Cl. 227-131.000.
- Hakansson, Jan T.: See—
Dilot, Rolf M.; and Hakansson, Jan T., 4,293,369, Cl. 156-521.000.
- Hakuju Institute for Health Science Co., Ltd.: See—
Suzuki, Shotaro, 4,292,980, Cl. 128-783.000.
- Hall, Donald R.: See—
Carpenter, Edward J.; Korff, William W.; Zoer, Alan E., deceased; Barelo, Lawrence J.; Hall, Donald R.; and Becker, Orlien N., 4,293,915, Cl. 364-493.000.
- Hall, John C.: See—
McCormick, James T.; Ferry, Paul B.; and Hall, John C., 4,293,089, Cl. 228-215.000.
- Hall, Woodrow A.: See—
Liu, Chungghong R.; Nayak, Jnaneshwar H.; Stenberg, Herbjorn; Huerta, Felipe J.; and Hall, Woodrow A., 4,292,865, Cl. 82-36.00R.
- Hallcher, Richard C.; Goodin, Richard D.; and Baizer, Manuel M., to Monsanto Company. Alkylation of nitriles using an electrogenerated base and an alkylating agent, 4,293,392, Cl. 204-59.00R.
- Hallcher, Richard C.; Goodin, Richard D.; and Baizer, Manuel M., to Monsanto Company. Use of electrogenerated bases in condensation reactions, 4,293,393, Cl. 204-59.00R.
- Halliburton Company: See—
Elphinstone, Eugene A.; McLaughlin, Homer C.; and Smith, Charles W., 4,293,440, Cl. 252-317.000.
- Hallmark, Bobby J., to Gearhart Industries, Inc. Tool for testing earth formations in boreholes, 4,292,842, Cl. 73-155.000.
- Halpern, Henry M.: See—
Chressanthis, Andrew G.; Halpern, Henry M.; and Gaffney, Brian P., 4,293,856, Cl. 343-5.0CF.
- Hamada, Seiya: See—
Okumura, Takatoshi; Hamada, Seiya; and Imamura, Akio, 4,292,873, Cl. 84-1.010.
- Hamann, Michael L.; and Pinegar, Richard K., to J. R. Simplot Company. Potato dough with process oil for formed and extruded potato products, 4,293,582, Cl. 426-637.000.
- Hamer, Anthony D.; and Karol, Frederick J., to Union Carbide Corporation. Spheroidal polymerization catalyst, process for preparing, and use for ethylene polymerization, 4,293,673, Cl. 526-88.000.
- Hamilton, Joel A. Controlled film advance apparatus with differential speed, 4,292,856, Cl. 74-63.000.
- Hamilton, Peter W.; and Lewis, William P., to Procter & Gamble Company. The Air treating device, 4,293,095, Cl. 239-35.000.
- Hammann, Ingeborg: See—
Hamprecht, Rainer; Hartmann, Alfons; Klauke, Erich; Hammann, Ingeborg; Roessler, Peter; and Brandes, Wilhelm, 4,293,566, Cl. 424-304.000.
- Hammond, Leslie G., to Anchor Building Products Limited. Tile packaging, 4,292,785, Cl. 53-399.000.
- Hamprecht, Rainer; Hartmann, Alfons; Klauke, Erich; Hammann, Ingeborg; Roessler, Peter; and Brandes, Wilhelm, to Bayer Aktiengesellschaft. Pesticidally active 1-arylamino-2,4-dinitronaphthalenes, 4,293,566, Cl. 424-304.000.
- Hanada, Tsuneo; Koshii, Taro; and Shinmi, Hideo, to Toray Silicone Company, Ltd. Heat curable molding composition, 4,293,479, Cl. 260-37.0EP.
- Hanifin, John W., Jr.: See—
Allen, George R., Jr.; Hanifin, John W., Jr.; Moran, Daniel B.; and Albright, Jay D., 4,293,554, Cl. 424-250.000.
- Hans Streuli AG: See—
Streuli, Hans; and Ruedi, Joseph, 4,293,410, Cl. 210-107.000.
- Hara, Akio; and Yazu, Shuji, to Sumitomo Electric Industries, Ltd. Sintered body for use in a cutting tool and the method for producing the same, 4,293,618, Cl. 428-551.000.
- Harand, Elmar; and Michel, Eberhard, to Kraftwerk Union Aktiengesellschaft. Nuclear reactor with a cylindrical reactor pressure vessel, 4,293,386, Cl. 376-461.000.
- Hardy, William B.; and Loffelman, Frank F., to American Cyanamid Company. Isopropylidenedicyclohexylene esters and their use as light stabilizers, 4,293,467, Cl. 260-45.80N.
- Harris Corporation: See—
Bailey, David C.; and Keesler, Floyd F., 4,293,124, Cl. 271-233.000.
- Ports, Kenneth A., 4,292,730, Cl. 29-577.00C.
- Harrison, James J.: See—
Beach, David L.; and Harrison, James J., 4,293,502, Cl. 260-439.00R.
- Beach, David L.; and Harrison, James J., 4,293,727, Cl. 585-526.000.
- Hart, Barbara: See—
Champion, Carolyn; Wolcott, Judith; Hart, Barbara; and Garcia, Zulma C., 4,292,975, Cl. 128-498.000.
- Hartmann, Alfons: See—
Hamprecht, Rainer; Hartmann, Alfons; Klauke, Erich; Hammann, Ingeborg; Roessler, Peter; and Brandes, Wilhelm, 4,293,566, Cl. 424-304.000.
- Hartness International, Inc.: See—
Hartness, Thomas S., 4,292,839, Cl. 73-49.200.
- Hartness, Thomas S., to Hartness International, Inc. Crown release pressure tester, 4,292,839, Cl. 73-49.200.
- Haruna, Tohru: See—
Minagawa, Motonobu; Nakahara, Yutaka; and Haruna, Tohru, 4,293,472, Cl. 260-23.0XA.
- Harvey Hubbell Incorporated: See—
Fidrych, Alfred W., 4,293,157, Cl. 294-86.0CG.
- Haschke, Elliot M.; and Lewis, Bennie J., to Dow Chemical Company. The Process for depolymerization of acrylic acid polymers, 4,293,347, Cl. 134-11.000.
- Hasegawa, Haruyoshi: See—
Nakajima, Shunichi; and Hasegawa, Haruyoshi, 4,293,085, Cl. 222-311.000.
- Hasegawa, Shinji: See—
Toriyama, Kazuhisa; Hata, Tsujiaki; Hasegawa, Shinji; and Sasaki, Ken, 4,293,698, Cl. 546-301.000.
- Hashimoto, Mitsuru; Ohta, Masafumi; Kozima, Akio; Sakai, Kiyoshi; and Sasaki, Masaomi, to Ricoh Co., Ltd. Electrophotographic elements containing disazo compounds, 4,293,628, Cl. 430-58.000.
- Hashimoto, Mitsuru: See—
Sasaki, Masaomi; Sakai, Kiyoshi; Hashimoto, Mitsuru; Ohta, Masafumi; and Tsutsui, Kyoji, 4,293,492, Cl. 260-160.000.
- Hashimura, Taiji: See—
Itoh, Isamu; Hashimura, Taiji; and Ishikawa, Takatoshi, 4,293,639, Cl. 430-393.000.
- Hassler, Craig R.; and Messing, Gary L., to Scientific Advances, Inc. Tooth implants, 4,293,302, Cl. 433-173.000.
- Hata, Tsujiaki: See—
Toriyama, Kazuhisa; Hata, Tsujiaki; Hasegawa, Shinji; and Sasaki, Ken, 4,293,698, Cl. 546-301.000.
- Hatada, Kenzo; and Kajiura, Takao, to Matsushita Electric Industrial Co., Ltd. Method of making metal electrode of semiconductor device, 4,293,637, Cl. 430-314.000.
- Hatz, Ernst; Eibl, Heinz; Peter, Erwin; and Blumhardt, Rolf, to Motorenfabrik Hatz GmbH & Co. KG. Heating system with heat pump and auxiliary heater, 4,293,092, Cl. 237-12.100.
- Haugwitz, Rudiger D.; Wade, Peter C.; and Maurer, Barbara V., to E. R. Squibb & Sons, Inc. Substituted phenylguanidines and method, 4,293,569, Cl. 424-300.000.
- Hauser, Hans-Ulrich, to Bucher-Guyer AG Maschinenfabrik. Hay harvesting machine, 4,292,793, Cl. 56-378.000.
- Havens, Donald F. Leg weights, 4,293,126, Cl. 272-119.000.
- Hawkins, Joel W. Double action pump, 4,293,286, Cl. 417-253.000.
- Hayakawa, Isao: See—
Tanaka, Yoshiaki; and Hayakawa, Isao, 4,293,695, Cl. 546-83.000.
- Hayashi, Takeshi. Apparatus for transferring solids, 4,293,250, Cl. 406-109.000.
- Haybuster Manufacturing, Inc.: See—
Neukom, Chester G.; and Kopecky, Ivyl D., 4,293,043, Cl. 172-267.000.
- Hayman-Chaffey, Charles R.; and Hayman-Chaffey, Frederick W. Acrylic sheet-lacquer laminates and articles of furniture made therefrom, 4,293,603, Cl. 428-86.000.
- Hayman-Chaffey, Frederick W.: See—
Hayman-Chaffey, Charles R.; and Hayman-Chaffey, Frederick W., 4,293,603, Cl. 428-86.000.
- Hazemeijer B.V.: See—
Groenenboom, Maarten, 4,293,813, Cl. 324-117.00R.
- Hehl, Karl. Hydraulic controls for injection unit of injection molding machine, 4,293,229, Cl. 366-78.000.
- Heiberger, Philip, to Du Pont de Nemours, E. I., and Company. Fast-drying alkyd latex, 4,293,471, Cl. 260-22.0CB.
- Heimsch, Robert A., to Monsanto Company. Refining olefin/maleic acid copolymers by extraction with alkanes, 4,293,668, Cl. 525-369.000.
- Heir, James L.: See—
Wells, Alton R.; Wells, Robert M.; and Heir, James L., 4,292,888, Cl. 99-312.000.
- Heirbaut, Wilfried A.; and Rens, Walter J., to AGFA-GEVAERT N.V. Method and apparatus for longitudinally stretching a substantially amorphous polyethylene terephthalate film, 4,293,508, Cl. 264-25.000.
- Heitmann, Jurgen; Maly, Hans-Peter; and Wilhelm, Rudolf, to Robert Bosch GmbH. Method and apparatus for the variable speed reproduction of a video signal stored on magnetic tape, 4,293,879, Cl. 360-10.000.
- Heitzer, Helmut: See—
Beck, Gunther; Heitzer, Helmut; and Lurssen, Klaus, 4,293,331, Cl. 71-118.000.
- Hekmati, Majid: See—
Bradley, Robert L., Jr.; and Hekmati, Majid, 4,293,573, Cl. 426-43.000.
- Helix Technology Corporation: See—
Ryan, James M.; and Holmes, Arthur S., 4,293,322, Cl. 62-17.000.
- Heller, Robert: See—
Hill, Lawrence; Garbis, Dennis; and Heller, Robert, 4,293,755, Cl. 219-10.410.
- Helveston, Wilton L.; and Pecoraro, Richard J., to International Moorings & Marine, Inc. Barge bumper assembly, 4,293,241, Cl. 405-213.000.

- Henkel Kommanditgesellschaft auf Aktien: See—
Gruenberg, Eberhard; and Muller, Roswitha, 4,293,458, Cl. 260-17.4GC.
- Hennessy Industries, Inc.: See—
Leeper, Charles G.; and Wood, John F., 4,293,020, Cl. 157-1.280.
- Henri, Paul, to Kennecott Corporation. Bag filter support cage, 4,293,111, Cl. 248-95.000.
- Hercules Incorporated: See—
Maslanka, William W.; and Spence, Gavin G., 4,293,666, Cl. 525-284.000.
- Maslanka, William W.; and Spence, Gavin G., 4,293,667, Cl. 525-284.000.
- Herder, Gary A., to Prab Conveyors, Inc. Bar end separator, 4,293,408, Cl. 209-638.000.
- Hernandez, Jose A., to Esquire, Inc. Reflector system having sharp light cutoff characteristics, 4,293,901, Cl. 362-346.000.
- Herolz, Robert A.; and Vogel, Charles B., to Shell Oil Company. Circumferential acoustic device, 4,293,934, Cl. 367-27.000.
- Herrington, Daniel R.; and Schwewer, Albert P., to Standard Oil Company. The High-surface area coated support for catalysts and process for their preparation, 4,293,449, Cl. 252-465.000.
- Hession, William M., Jr. Apparatus for intravenous catheter starter, 4,292,970, Cl. 128-214.400.
- Hewlett-Packard Company: See—
Bente, Paul F., III; Zerenner, Ernest H.; and Dandeneau, Raymond D., 4,293,415, Cl. 210-198.200.
- Haag, George A.; Fogg, O. Douglas; Greenley, Gordon A.; Shepherd, Steve A.; and Terry, F. Duncan, 4,293,925, Cl. 364-900.000.
- Heydenreich, Frieder; Korber, Helmut; Tacke, Peter; Fahlner, Friedrich; and Neuray, Dieter, to Bayer Aktiengesellschaft. Polyamides containing oxidized polyethylene, 4,293,662, Cl. 525-184.000.
- Hickman, Jack L. Automatic socket ejector, 4,292,863, Cl. 81-184.000.
- Hidvegi, Ferenc: See—
Pataki, Jozsef; Bucsi, Jozsef; Bona, Istvan; Szilvasi, Endre; Gazdag, Andras; Koly, Antal; and Hidvegi, Ferenc, 4,292,996, Cl. 137-393.000.
- Higgins, Pink M. Electric heating system for heating the interior of a motor vehicle prior to starting, 4,293,759, Cl. 219-202.000.
- Higuchi, Noboru; Yano, Teruo; and Ohnishi, Masahiro, to NGK Insulators, Ltd. Method for producing ceramic honeycomb filters, 4,293,357, Cl. 156-89.000.
- Hilbert, Robert S., to Fantacia. Objective lens system with aspheric Fresnel elements, 4,293,196, Cl. 350-452.000.
- Hill, David A.; and Lomnitz, Abraham, to Qualettron (PTY) Ltd. Stackable equipment containers, 4,293,072, Cl. 206-512.000.
- Hill, H. Wayne, Jr.: See—
Campbell, Robert W.; and Hill, H. Wayne, Jr., 4,293,688, Cl. 528-346.000.
- Hill, Lawrence; Garbis, Dennis; and Heller, Robert, to General Instrument Corporation. Method of cooling induction-heated vapor deposition apparatus and cooling apparatus therefor, 4,293,755, Cl. 219-10.410.
- Hill, Richard N., to W. R. Grace & Co. Phosphoric acid crystallizer underflow return, 4,293,311, Cl. 23-301.000.
- Hill, Wiley E.: See—
Cheng, Edmund K.; and Hill, Wiley E., 4,293,848, Cl. 340-347.0AD.
- Hille, Earl A.: See—
Gills, Richard G.; Hille, Earl A.; Kleine, Albert W., Jr.; and Shamp, Donald E., 4,293,264, Cl. 414-38.000.
- Hillmann, Hans: See—
Hilzinger, Hans-Reiner; and Hillmann, Hans, 4,293,023, Cl. 164-479.000.
- Hilt, Milton B.: See—
Wilkes, Colin; and Hilt, Milton B., 4,292,801, Cl. 60-39.060.
- Hilzinger, Hans-Reiner; and Hillmann, Hans, to Vacuum-Schmelze GmbH. Method and device for the manufacture of metal bands, 4,293,023, Cl. 164-479.000.
- Hinderer, Helmut E.: See—
Bach, Hartwig C.; and Hinderer, Helmut E., 4,293,613, Cl. 428-364.000.
- Hinds, Robert S. Jump rope handle, 4,293,125, Cl. 272-75.000.
- Hinosugi, Misturu: See—
Unnai, Takaaki; Izumi, Akiya; and Hinosugi, Misturu, 4,293,586, Cl. 427-68.000.
- Hinrichs, John M., to ACF Industries, Incorporated. Metallic seat assembly for valves, 4,293,116, Cl. 251-173.000.
- Hirabayashi, Masaya: See—
Shikita, Takuji; and Hirabayashi, Masaya, 4,293,540, Cl. 424-26.000.
- Hiramatsu, Yasuzo: See—
Fujimura, Hajime; Hiramatsu, Yasuzo; Yabuuchi, Takahiro; Hisaki, Masakatu; Takikawa, Katsuo; Honna, Takaji; Miyake, Hidekazu; and Kajitani, Makoto, 4,293,713, Cl. 564-38.000.
- Hirsbrunner, Pierre; and Bertholet, Raymond, to Societe d'Assistance Technique Pour Produits Nestle S.A. Saponification treatment of spent coffee grounds, 4,293,581, Cl. 426-630.000.
- Hirzel, Edgar A., to Crane Co. Electronic control brake and skid control system, 4,293,165, Cl. 303-93.000.
- Hisaki, Masakatu: See—
Fujimura, Hajime; Hiramatsu, Yasuzo; Yabuuchi, Takahiro; Hisaki, Masakatu; Takikawa, Katsuo; Honna, Takaji; Miyake, Hidekazu; and Kajitani, Makoto, 4,293,713, Cl. 564-38.000.
- Hitachi, Ltd.: See—
Amano, Yutaka, 4,293,926, Cl. 364-900.000.
- Asakawa, Yukio, 4,293,918, Cl. 364-702.000.
- Izuka, Takashi; and Horie, Masayuki, 4,293,868, Cl. 357-46.000.
- Ishaya, Fumio; and Yukitake, Tugihito, 4,293,521, Cl. 422-62.000.
- Ito, Motoya; Sato, Masaki; Watanabe, Masatoshi; and Okuda, Hironori, 4,293,787, Cl. 310-181.000.
- Izumita, Morishi; Maeda, Takeshi; Tsunoda, Yoshito; and Sawano, Susumu, 4,293,944, Cl. 369-45.000.
- Kamejima, Kohji; Tanaka, Hideki; Kano, Minoru; and Fukushima, Toshihiko, 4,292,811, Cl. 62-56.000.
- Katada, Hiroshi; and Kyogoku, Yoshito, 4,292,942, Cl. 123-418.000.
- Kishi, Tuneso; and Sasaki, Koji, 4,293,749, Cl. 200-144.0AP.
- Kobayashi, Nariyoshi; Sakamoto, Takeshi; Anzai, Shunichi; and Matsumoto, Manabu, 4,293,275, Cl. 416-97.00R.
- Kyogoku, Yoshito; and Katada, Hiroshi, 4,292,943, Cl. 123-427.000.
- Makino, Kazuhiro, 4,293,077, Cl. 212-219.000.
- Mochida, Hideyuki; Tamura, Shingo; and Tsurumi, Etsuo, 4,293,903, Cl. 363-68.000.
- Morishita, Hirosada; Kawamoto, Mineo; and Murakami, Kanzi, 4,293,592, Cl. 427-98.000.
- Morooka, Yasuo; Tanifuji, Shinya; and Tanuma, Masaya, 4,292,825, Cl. 72-8.000.
- Nakae, Hideo; Ozaki, Toshinori; Shimaguchi, Takashi; and Morimoto, Syogo, 4,292,832, Cl. 72-365.000.
- Ohsumi, Katsumi; and Miki, Minoru, 4,293,382, Cl. 376-308.000.
- Ohta, Hirofumi, 4,293,929, Cl. 365-2.000.
- Shibayama, Akinori; Maio, Kenji; and Yokozawa, Norio, 4,293,819, Cl. 330-9.000.
- Terashima, Isamu, 4,292,925, Cl. 118-690.000.
- Toriyama, Kazuhisa; Hata, Tsujiaki; Hasegawa, Shinji; and Sasaki, Ken, 4,293,698, Cl. 546-301.000.
- Unnai, Takaaki; Izumi, Akiya; and Hinosugi, Misturu, 4,293,586, Cl. 427-68.000.
- Hitachi Shipbuilding & Engineering Co. Ltd.: See—
Inaba, Hideya; Nagai, Kenichi; Ichiki, Masayoshi; Kamino, Yasumi; and Maeda, Kazuo, 4,293,447, Cl. 252-461.000.
- Hobo, Nobuhito: See—
Tsuzuki, Yoshihiko; Kaga, Sumihito; and Hobo, Nobuhito, 4,293,893, Cl. 362-38.000.
- Hochberg, Lindsey S.; and Borland, Montague C., to Logitek Electronic Systems, Inc. Balanced input phonograph preamplifier circuit, 4,293,823, Cl. 330-260.000.
- Hochiki Corporation: See—
Sawa, Hiroshi; and Yamauchi, Yukio, 4,292,844, Cl. 73-359.00A.
- Hockema, Robert J. Adjustable box stool, 4,292,903, Cl. 108-146.000.
- Hockham, George A., to International Telephone and Telegraph Corporation. Polarization agile meander line array, 4,293,858, Cl. 343-731.000.
- Hoechst Aktiengesellschaft: See—
Becker, Reinhold, 4,292,711, Cl. 17-49.000.
- Blumbach, Jurgen; Durckheimer, Walter; and Schrinner, Elmar, 4,293,550, Cl. 424-246.000.
- Hoyer, Ernst; Steckelberg, Willi; Deucker, Walter; and Schick-fluss, Rudolf, 4,293,306, Cl. 8-471.000.
- Hofer, Wayne A.; and Tanty, Paul J., to Caterpillar Tractor Co. Brake control circuit with parking and retarding valves, 4,293,164, Cl. 303-13.000.
- Hoefke, Wolfgang: See—
Stahle, Helmut; Koppe, Herbert; Kummer, Werner; Hoefke, Wolfgang; Gaida, Wolfram; and Pichler, Ludwig, 4,293,564, Cl. 424-273.00R.
- Hoehn, Marvin M.; and Michel, Karl H., to Eli Lilly and Company. Process for production of antibiotic A-33853, 4,293,649, Cl. 435-118.000.
- Hoffman, Mark H., to SCI Systems, Inc. Printer control system, 4,293,233, Cl. 400-144.200.
- Hoh, Ying-Chu: See—
Wang, Wei Ko; Hoh, Ying-Chu; Chuang, Wen-Shou; and Shaw, I-Sine, 4,293,332, Cl. 75-99.000.
- Holderith, William J.: See—
Percarpio, Edward P.; and Holderith, William J., 4,293,078, Cl. 215-247.000.
- Holken, Norbert: See—
Rosenberg, Harry; and Holken, Norbert, 4,293,247, Cl. 405-296.000.
- Holmes, Arthur S.: See—
Ryan, James M.; and Holmes, Arthur S., 4,293,322, Cl. 62-17.000.
- Holmes, Horace D. Reusable prevailing torque nut, 4,293,262, Cl. 411-311.000.
- Holmstadt, Ronald J.; and Comer, Robert C., to Toro Company. The Power cultivator with debris excluding barrier and scraper, 4,293,041, Cl. 172-39.000.
- Holtey, Thomas O.: See—
Bradley, John J.; Holtey, Thomas O.; Miller, Robert C.; Miu, Ming T.; Shen, Jian-Kuo; and Staplin, Theodore R., Jr., 4,293,908, Cl. 364-200.000.
- Homan, Gary R.; and Lee, Chi-Long, to Dow Corning Corporation. Oxygen-curable mercaptoorganosiloxane compositions containing both redox and iron carbonyl compounds and method of forming higher molecular weight products therefrom, 4,293,676, Cl. 528-15.000.
- Honda Giken Kogyo Kabushiki Kaisha: See—
Nishikawa, Masao, 4,293,051, Cl. 180-133.000.
- Honeywell Information Systems Inc.: See—
Bradley, John J.; Holtey, Thomas O.; Miller, Robert C.; Miu, Ming T.; Shen, Jian-Kuo; and Staplin, Theodore R., Jr., 4,293,908, Cl. 364-200.000.

- Honna, Takaji: See—
Fujimura, Hajime; Hiramatsu, Yasuzo; Yabuuchi, Takahiro; Hisaki, Masakazu; Takikawa, Katsuo; Honna, Takaji; Miyake, Hidekazu; and Kajitani, Makoto, 4,293,713, Cl. 564-38.000.
- Honnold, Fred V.: See—
Raymond, Glendon A.; Honnold, Fred V.; and Spath, Herbert J., 4,293,093, Cl. 237-19.000.
- Hoogovens Ijmuiden B.V.: See—
Felthuis, Jacob; and Rumphorst, Jacobus A., 4,292,993, Cl. 137-340.000.
- Hooser, Oneida O. Retractable safety handle means for a ladder. 4,293,055, Cl. 182-106.000.
- Hopkins, Donald L., to Alf Hannaford & Co. Pty. Ltd. Method and means for holding a sheep. 4,292,931, Cl. 119-103.000.
- Hoppe, Walter, to Zimmermann & Jansen GmbH. Compressed air dredge. 4,292,747, Cl. 37-58.000.
- Hori, Kiyoshi; and Nagata, Nobuyoshi, to Nippon Paint Co., Ltd. Method of forming decorative relief pattern and pattern-forming device therefor. 4,293,599, Cl. 427-274.000.
- Horie, Masayuki: See—
Iizuka, Takashi; and Horie, Masayuki, 4,293,868, Cl. 357-46.000.
- Horike, Masanori: See—
Jinnai, Koichiro; Horike, Masanori; Iwasaki, Kyuhachiro; and Kodama, Yutaka, 4,293,865, Cl. 346-140.00R.
- Hornaman, Ernest C.: See—
Zalucha, Denis J.; Sexsmith, Frederick H.; Hornaman, Ernest C.; and Dawdy, Terrance H., 4,293,665, Cl. 525-255.000.
- Hort, Eugene V.: See—
Parthasarathy, R.; and Hort, Eugene V., 4,293,444, Cl. 252-432.000.
- Hortman, Michael T.; and Naum, Robert G., to Carborundum Company, The. Method for increasing boron¹⁰ contents of neutron absorbing articles. 4,293,598, Cl. 427-203.000.
- Horton, Charles R.: See—
Siryj, Bohdan W.; Scott, Richard D.; and Horton, Charles R., 4,293,212, Cl. 354-299.000.
- Horton, James A., to Jersey Nuclear-Avco Isotopes, Inc. Compact mirror mount. 4,293,112, Cl. 248-487.000.
- Horzinek, Marian C.; and Osterhaus, Albertus D. M. E. Method for propagating feline infectious peritonitis virus. 4,293,653, Cl. 435-237.000.
- Hoshii, Toshifumi, to Casio Computer Co., Ltd. Power consumption control system for electronic digital data processing devices. 4,293,927, Cl. 364-900.000.
- Hosoe, Kazuya: See—
Tsunekawa, Tokuchi; Masunaga, Makoto; Hosoe, Kazuya; Niwa, Yukichi; Owada, Mitsutoshi; and Asano, Noriyuki, 4,293,877, Cl. 358-213.000.
- Hospelhorn, Verne D.: See—
Jensen, Elwood V.; and Hospelhorn, Verne D., 4,293,536, Cl. 424-1.000.
- Hotogi, Akira: See—
Kosaka, Kenji; Iwatsuka, Takeshi; Shindo, Ikuo; and Hotogi, Akira, 4,293,423, Cl. 210-676.000.
- Houn, Lin P. Air floating saucer toy. 4,292,755, Cl. 46-44.000.
- Howard, David. Building wall structure. 4,292,775, Cl. 52-220.000.
- Hoya Corporation: See—
Ishibai, Isao; and Kobayashi, Kunimitsu, 4,293,187, Cl. 350-36.000.
- Hoyer, Ernst; Steckelberg, Willi; Deucker, Walter; and Schickflus, Rudolf, to Hoechst Aktiengesellschaft. Process for the dyeing and printing of hydrophobic synthetic organic fiber materials with water-insoluble azo dyestuffs. 4,293,306, Cl. 8-471.000.
- Hoyt, Harold C., Jr.; and Greene, William J., to Teledyne Walterboro. Electric welder. 4,293,756, Cl. 219-133.000.
- Hoyt, John G. Spinnaker post for sailing vessel. 4,292,910, Cl. 114-102.000.
- Hrasche, Heinrich, to Swiss Aluminium Ltd. Load carrying platform or back for vehicles. 4,293,255, Cl. 410-104.000.
- Huang, Victor K.; and Ruth, Richard L., to Bell Telephone Laboratories, Incorporated. Data processing apparatus having op-code extension register. 4,293,907, Cl. 364-200.000.
- Huddon, Lawrence T. Jewelry clutch. 4,292,715, Cl. 24-155.00C.
- Huebner, Klaus: See—
Fink, Herbert; Huebner, Klaus; Dinklage, Horst; and Ottofrickenstein, Hans, 4,293,600, Cl. 427-385.500.
- Huelster, Richard L.: See—
Dyer, Thomas A.; and Huelster, Richard L., 4,293,065, Cl. 198-781.000.
- Huerta, Felipe J.: See—
Liu, Chung-hong R.; Nayak, Jnaneshwar H.; Stenberg, Herbjorn; Huerta, Felipe J.; and Hall, Woodrow A., 4,292,865, Cl. 82-36.00R.
- Huffey, Roy F.; and Pope, John A., to Bexford Limited. Reflex copying process onto light-sensitive recording materials. 4,293,633, Cl. 430-152.000.
- Huffsmith, Sarah A.: See—
Landingham, Richard L.; and Huffsmith, Sarah A., 4,293,619, Cl. 428-623.000.
- Huggins, Raymond W., to Xerox Corporation. Development system. 4,292,923, Cl. 118-658.000.
- Hughes Aircraft Company: See—
Papa, Adrian E., 4,293,833, Cl. 333-239.000.
- Hughes, Donald W. K.; and Myers, Ronald W., to AMP Incorporated. Method for making jack type receptacles. 4,292,736, Cl. 29-884.000.
- Hughes, O. Richard, to Celanese Corporation. Process for producing a carboxylate ester using a supported acidic catalyst. 4,293,499, Cl. 260-410.90R.
- Hughes Tool Company: See—
Mullins, John M.; and Kelly, Joseph L., Jr., 4,293,039, Cl. 166-341.000.
- Hunter, Andrew F., to Conoco, Inc. Transfer and docking apparatus for use on variable draft marine vessels. 4,292,912, Cl. 114-219.000.
- Hunter Douglas International N.V.: See—
Landheer, Hugo A. J., 4,292,779, Cl. 52-486.000.
- Hupp, Gerhard; and Mader, Helmut, to Mauser-Werke Obendorf GmbH. Automatic firearm construction. 4,292,881, Cl. 89-33.0CA.
- Hurni, William M.: See—
McAleer, William J.; Hurni, William M.; and Miller, William J., 4,293,538, Cl. 424-1.000.
- Hutterian Society of Brothers: See—
Meier, Daniel; and Maendel, Carl, 4,292,933, Cl. 122-114.000.
- Hutton, Stanley P.: See—
Williams, Garnet M. E.; Hutton, Stanley P.; and Bushman, John A., 4,292,853, Cl. 73-861.790.
- Hydril Company: See—
Mott, James D., 4,293,034, Cl. 166-208.000.
- Parks, Glenn C., Jr.; and Beam, Clark W., 4,293,115, Cl. 251-1.00A.
- Hydro-Quebec: See—
Belanger, Guy; and Missout, Gilles, 4,293,399, Cl. 204-195.00P.
- Jasmin, Gilles; and Bowles, John P., 4,293,923, Cl. 364-802.000.
- Ichiki, Masayoshi: See—
Inaba, Hideya; Nagai, Kenichi; Ichiki, Masayoshi; Kamino, Yasumi; and Maeda, Kazuo, 4,293,447, Cl. 252-461.000.
- Ichiyama, Tadashi; Yamaguchi, Shigehiro; Iuchi, Tohru; and Kuroki, Katsuro, to Nippon Steel Corporation. Grain-oriented electromagnetic steel sheet with improved watt loss. 4,293,350, Cl. 148-111.000.
- Ichizuka, Kiyomi: See—
Takita, Seiki; and Ichizuka, Kiyomi, 4,293,866, Cl. 346-140.00R.
- Ida, Minoru, to Manten Co., Ltd. Protective handrail for folding baby carriage. 4,293,144, Cl. 280-644.000.
- Ihaya, Kazuhiko: See—
Nagano, Katsuto; Ihaya, Kazuhiko; Sasa, Syozo; and Nakada, Takeshi, 4,293,370, Cl. 156-612.000.
- Iijima, Tokuzo; Samejima, Yasushi; Kishimoto, Kazuo; Komabashiri, Takamichi; and Kano, Toshiji, to Kanegafuchi Kagaku Kogyo Kabushiki Kaisha. Process for electrolysis of an aqueous alkali metal chloride solution. 4,293,395, Cl. 204-98.000.
- Iijima, Yasuo, to Nippon Electric Co., Ltd. Circuit with crosstalk elimination capability. 4,293,739, Cl. 179-18.0GF.
- Iijima, Yoshio, to Daido Metal Company Ltd. Method of producing metal bearings. 4,292,718, Cl. 29-149.5DP.
- Iimura, Yoshitaka, to Yoshida Kogyo, K.K. Apparatus for coupling a pair of elongate slide fastener stringers. 4,292,733, Cl. 29-766.000.
- Iizuka, Takashi; and Horie, Masayuki, to Hitachi, Ltd. Semiconductor device, method of manufacturing the same and application thereof. 4,293,868, Cl. 357-46.000.
- Illinois Tool Works Inc.: See—
Frano, Francis G., 4,293,261, Cl. 411-85.000.
- Peterson, Francis C., 4,293,257, Cl. 411-11.000.
- Imada, Kiyoshi; Ueno, Susumu; Nishina, Yasuhide; and Nomura, Hirokazu, to Shin-etsu Chemical Co., Ltd. Method for the preparation of polarizing films or sheets. 4,293,585, Cl. 427-40.000.
- Imagawa, Shunjiro: See—
Adachi, Hideo; Minai, Kiichi; Moriyasu, Kojo; and Imagawa, Shunjiro, 4,293,768, Cl. 250-338.000.
- Imai, Takeshi, to Toray Silicone Company, Ltd. Curable organopolysiloxane composition containing microcapsules. 4,293,677, Cl. 528-15.000.
- Imamura, Akio: See—
Okumura, Takatoshi; Hamada, Seiya; and Imamura, Akio, 4,292,873, Cl. 84-1.010.
- Imperial Chemical Industries, Limited: See—
Parkin, Paul C., 4,293,516, Cl. 264-168.000.
- Inaba, Hideya; Nagai, Kenichi; Ichiki, Masayoshi; Kamino, Yasumi; and Maeda, Kazuo, to Hitachi Shipbuilding & Engineering Co. Ltd. Process for repairing plate-shaped denitrating catalysts. 4,293,447, Cl. 252-461.000.
- Industrias Neoplast, S.A.: See—
Bonel, Federico A., 4,293,149, Cl. 285-111.000.
- Industrie Pirelli S.p.A.: See—
Maiocchi, Luigi, 4,293,019, Cl. 152-361.00R.
- Inglefield, Joseph T., Jr.; and Mahood, William L. Allergy testing apparatus. 4,292,979, Cl. 128-743.000.
- Inhofer, Harold G., to Aeration Industries, Inc. Water bearing. 4,293,169, Cl. 308-121.000.
- Innes, Robert A.: See—
Swift, Harold E.; Innes, Robert A.; and Adams, Phillip, 4,293,716, Cl. 564-480.000.
- Inokuma, Toshio: See—
Asada, Eiichi; Inokuma, Toshio; and Egawa, Isao, 4,293,839, Cl. 338-309.000.
- Inomata, Hiroshi: See—
Sato, Yasuhiko; and Inomata, Hiroshi, 4,293,397, Cl. 204-159.130.
- Inoue, Tomohiro: See—
Ogimoto, Kazuo; Inoue, Tomohiro; Tanaka, Susumu; and Kobayashi, Yoshio, 4,293,240, Cl. 405-195.000.
- Inoue, Yoshimichi: See—
Ohta, Ryuji; and Inoue, Yoshimichi, 4,292,887, Cl. 92-94.000.
- Insolar Inc.: See—
Wasserman, Kurt J., 4,292,956, Cl. 126-439.000.
- Institute of Nuclear Energy Research: See—
Wang, Wei Ko; Hoh, Ying-Chu; Chuang, Wen-Shou; and Shaw, I-Sine, 4,293,332, Cl. 75-99.000.

- Intel Corporation: See—
Cheng, Edmund K.; and Hill, Wiley E., 4,293,848, Cl. 340-347.0AD.
- Intensiv-Filter GmbH & Co. KG: See—
Kordas, Friedel, 4,293,321, Cl. 55-357.000.
- Interatom, Internationale Atomreaktorbau GmbH: See—
Lakra, Ruhama J.; Freund, Jurgen; and Rauschert, Gerd, 4,293,383, Cl. 376-290.000.
- Intercontinental Valve Manufacturing Company: See—
Mueller, John H., 4,293,117, Cl. 251-229.000.
- International Business Machines Corporation: See—
Chaudhari, Praveen; Chou, Ned J.; Feder, Ralph; Fowler, Alan B.; and VanVechten, James A., 4,293,374, Cl. 156-628.000.
- Cox, Allen R.; and Smathers, Edmond W., 4,293,883, Cl. 360-104.000.
- Dasgupta, Sumit; Goel, Prabhakar; and Williams, Thomas W., 4,293,919, Cl. 364-716.000.
- Flusche, Frederick O.; Tan, Kwang G.; and Wright, Ralph W., 4,293,910, Cl. 364-200.000.
- Gaston, Charles A.; Kirk, Joseph P.; and Wasik, Chester A., 4,293,224, Cl. 356-357.000.
- Le, Trung, 4,293,802, Cl. 315-387.000.
- McCarty, Vincent D., 4,293,888, Cl. 361-152.000.
- Vigar, James M. L., 4,293,620, Cl. 428-667.000.
- International Flavors & Fragrances Inc.: See—
Shu, Chi-Kuen; Mookherjee, Braja D.; and Vock, Manfred H., 4,293,579, Cl. 426-535.000.
- Sprecker, Mark A.; Sanders, James M.; Schreiber, William L.; Watkins, Hugh; Vinals, Joaquin F.; Shuster, Edward J.; O'Rourke, Thomas J.; Hagedorn, Myrna L.; and Klemarczyk, Philip, 4,293,453, Cl. 252-522.00R.
- International Moorings & Marine, Inc.: See—
Helveston, Wilton L.; and Pecoraro, Richard J., 4,293,241, Cl. 405-213.000.
- International Paper Company: See—
Kreiling, William H.; and Jones, Edward S., 4,293,595, Cl. 427-121.000.
- Kreiling, William H.; and Jones, Edward S., 4,293,610, Cl. 428-246.000.
- International Standard Electric Corporation: See—
Greenwood, John C., 4,293,373, Cl. 156-628.000.
- International Telephone and Telegraph Corporation: See—
Hockman, George A., 4,293,858, Cl. 343-731.000.
- Jarger, Harold F., 4,293,818, Cl. 329-50.000.
- Kuras, Michael L.; Upp, Daniel C.; and Toegel, Herbert J., 4,293,946, Cl. 370-62.000.
- Lacaze, Leonard, Jr., 4,293,181, Cl. 339-258.00R.
- Schwartz, Lawrence, 4,293,182, Cl. 339-275.00R.
- Silva, Roy; Ash, David J.; and Scheible, Clement E., 4,293,572, Cl. 426-19.000.
- Interox: See—
Gago, Ignace, 4,293,426, Cl. 210-759.000.
- Irie, Toshio: See—
Matsumura, Ko; Nakamura, Hiroto; and Irie, Toshio, 4,293,336, Cl. 75-124.000.
- Isaacs, Jim W.: See—
Sutcliffe, Peter W.; Isaacs, Jim W.; Nelson, Robert L.; Lyon, Colin E.; and Stringer, Brian, 4,293,507, Cl. 264-0.500.
- Isahaya, Fumio; and Yukitake, Tugihiro, to Hitachi, Ltd. Apparatus for cleaning waste flue gases. 4,293,521, Cl. 422-62.000.
- Isaka, Tsutomu; and Kumada, Saburoh, to Toyo Baski Kabushiki Kaisha. Olefin packaging laminate. 4,293,608, Cl. 428-220.000.
- Isayama, Takuro, to Ricoh Co., Ltd. Device for removing air bubbles formed and trapped in ink chamber of print head of ink-jet printer. 4,293,867, Cl. 346-140.00R.
- Ishibai, Isao; and Kobayashi, Kunimitsu, to Hoya Corporation. Binocular optical system with automatic focussing. 4,293,187, Cl. 350-36.000.
- Ishihara, Takatoshi: See—
Wada, Shinji; Kitao, Ikuo; Oana, Yoshinori; Kato, Yasuo; and Ishihara, Takatoshi, 4,293,199, Cl. 351-13.000.
- Ishikawa, Hiroshi; and Nakagawa, Kazuyuki, to Otsuka Pharmaceutical Co., Ltd. Pyrido[3,2-i-jk]carbazols. 4,293,694, Cl. 546-72.000.
- Ishikawa, Kohji: See—
Shimizu, Masao; Tokuno, Takashi; Ishikawa, Kohji; Narumi, Naoki; and Ohguchi, Osamu, 4,293,950, Cl. 371-21.000.
- Ishikawa, Masayuki; Tanaka, Hiromichi; Eguchi, Yukuo; Ito, Shigeru; Takashima, Yoshimi; and Kobayashi, Masahiko, to Ishikawa, Masayuki. 1-Phthalazone derivatives, and use thereof. 4,293,553, Cl. 424-250.000.
- Ishikawa, Takatoshi: See—
Itoh, Isamu; Hashimura, Taiji; and Ishikawa, Takatoshi, 4,293,639, Cl. 430-393.000.
- Ishikawa, Yasuyuki: See—
Kohayakawa, Yoshimi; Ishikawa, Yasuyuki; and Maruyama, Shigeo, 4,293,198, Cl. 351-13.000.
- Ishizuka, Ichiro: See—
Yukinaga, Hisajiro; Sumimoto, Shinzaburo; Ishizuka, Ichiro; and Sugita, Jitsuo, 4,293,328, Cl. 71-88.000.
- Israel Aircraft Industries Ltd.: See—
Hadari, Gideon, 4,293,840, Cl. 340-27.0AT.
- Israel, Benjamin, to North Eastern Timber (U.S.A.) Incorporated. Candy floss machine. 4,293,292, Cl. 425-9.000.
- Itaya, Toshihisa: See—
Shibata, Kenyu; Itaya, Toshihisa; Yamakoshi, Nobuaki; Kurata, Shigeru; Koizumi, Naoyuki; Tarutani, Masaaki; Sakuma, Hideki; and Konishi, Kunihiro, 4,293,557, Cl. 424-267.000.
- Ito, Motoya; Sato, Masaki; Watanabe, Masatoshi; and Okuda, Hironori, to Hitachi, Ltd. Stator winding holding structure for rotary electric machine. 4,293,787, Cl. 310-181.000.
- Ito, Shigeru: See—
Ishikawa, Masayuki; Tanaka, Hiromichi; Eguchi, Yukuo; Ito, Shigeru; Takashima, Yoshimi; and Kobayashi, Masahiko, 4,293,553, Cl. 424-250.000.
- Ito, Isamu; Hashimura, Taiji; and Ishikawa, Takatoshi, to Fuji Photo Film Co., Ltd. Bleaching compositions for photographic processing. 4,293,639, Cl. 430-393.000.
- Itoh, Katsumi: See—
Muto, Katsuya; Mori, Kazumasa; Mase, Akira; Nimura, Takayasu; Itoh, Katsumi; and Akita, Yoshio, 4,293,811, Cl. 322-60.000.
- Iuchi, Tohru: See—
Ichiyama, Tadashi; Yamaguchi, Shigehiro; Iuchi, Tohru; and Kuroki, Katsuro, 4,293,350, Cl. 148-111.000.
- Ivanov, Boris N.: See—
Dunaevsky, Vladimir I.; Boidenko, Nikolai G.; Samar, Alexei P.; Levit, Viktor M.; Zapara, Boris M.; Ivanov, Boris N.; Frolov, Sergei A.; Voronin, Rostislav A.; Belozorov, Nikolai P.; Momot, Valery I.; Stusenko, Jury A.; and Samoilov, Vladimir A., 4,293,101, Cl. 242-56.400.
- Iwai, Yasuyuki: See—
Yamazaki, Yoshio; Kamogawa, Nin-ichi; and Iwai, Yasuyuki, 4,292,922, Cl. 118-657.000.
- Iwaki, Tetsuo; Takahashi, Yukio; Moriuchi, Shuji; and Kaneko, Hisamitsu, to Mitsui Petrochemical Industries, Ltd. Process for preparation of hydroperoxides. 4,293,720, Cl. 568-575.000.
- Iwasaki, Kyuhachiro: See—
Jinnai, Koichiro; Horike, Masanori; Iwasaki, Kyuhachiro; and Kodama, Yutaka, 4,293,865, Cl. 346-140.00R.
- Iwasaki, Yasuhiro: See—
Koike, Mitsuhiro; and Iwasaki, Yasuhiro, 4,292,821, Cl. 66-75.200.
- Iwata Electric Co., Ltd.: See—
Iwata, Keisuke, 4,293,860, Cl. 343-715.000.
- Iwata, Keisuke, to Iwata Electric Co., Ltd. Antenna alarm assembly for vehicle. 4,293,860, Cl. 343-715.000.
- Iwata, Masayoshi; and Douke, Harumi, to Kabushiki Kaisha Tokai Rika Denki Seisakusho. Combination switching means of lever type for motor vehicles. 4,293,743, Cl. 200-4.000.
- Iwatsuka, Takeshi: See—
Kosaka, Kenji; Iwatsuka, Takeshi; Shindo, Ikuo; and Hotogi, Akira, 4,293,423, Cl. 210-676.000.
- Izawa, Kyoichi: See—
Matsuda, Takehiko; and Izawa, Kyoichi, 4,293,745, Cl. 200-52.00R.
- Izumi, Akiya: See—
Unnai, Takaaki; Izumi, Akiya; and Hinotsugi, Misturu, 4,293,586, Cl. 427-68.000.
- Izumita, Morishi; Maeda, Takeshi; Tsunoda, Yoshito; and Sawano, Susumu, to Hitachi, Ltd. Information play-back apparatus with astigmatic auto-focusing. 4,293,944, Cl. 369-45.000.
- J. C. Bamford Excavators Limited: See—
Prime, Derek A., 4,293,270, Cl. 414-690.000.
- J. F. Enterprises, Inc.: See—
Acker, Donald J., 4,292,698, Cl. 5-45.000.
- J. F. Tonnes Erben K.G.: See—
Krause, Heinz; and Sanner, Bert, 4,292,977, Cl. 128-712.000.
- J. R. Simplot Company: See—
Hamann, Michael L.; and Pinegar, Richard K., 4,293,582, Cl. 426-637.000.
- Jach, Jan: See—
Jedlinski, Zbigniew; Thomalla, Bogdan; Kotas, Antoni; Jedlinski, Stanislaw; Pilat, Wladyslaw; and Jach, Jan, 4,293,685, Cl. 528-190.000.
- Jackson, John T., Jr., to Jackson Research, Inc. Rotating electric machines with enhanced radiation cooling. 4,293,785, Cl. 310-64.000.
- Jackson Research, Inc.: See—
Jackson, John T., Jr., 4,293,785, Cl. 310-64.000.
- Jackson, Roy J., to Shell Oil Company. Process for stabilizing polyester compositions. 4,293,672, Cl. 525-507.000.
- Jacobson, Martin, to United States of America, Agriculture. Anti-feedant for boll weevils. 4,293,567, Cl. 424-312.000.
- Jaeklin, Felix P. Structural system and structural elements for use and construction of earth filled walls. 4,293,245, Cl. 405-272.000.
- Jaffe, Wolfgang; and Rogan, Bruce R., to Singer Company, The. Hall effect potentiometer. 4,293,837, Cl. 338-32.00H.
- Jagenberg Werke: See—
Schmitz, Rolf, 4,293,087, Cl. 226-172.000.
- Jakobsen, Kjell M., to Aktiebolaget Platanufaktur AB. Method for fastening a stabilizing arrangement on a container. 4,293,359, Cl. 156-156.000.
- Jamieson, William B.; Ross, William J.; Simmonds, Robin G.; and Verge, John P., to Lilly Industries Limited. Thienyl hydantoins and anti-asthmatic compositions thereof. 4,293,563, Cl. 424-273.00R.
- Jansen, Martin B., Jr.: See—
Beynet, Pierre A.; Lucksinger, James E.; and Jansen, Martin B., Jr., 4,293,146, Cl. 285-24.000.
- Jarger, Harold F., to International Telephone and Telegraph Corporation. Frequency modulation threshold extension demodulator utilizing frequency compression feedback with frequency drift correction. 4,293,818, Cl. 329-50.000.
- Jarre, Wolfgang: See—
Nissen, Dietmar; Marx, Matthias; Jarre, Wolfgang; Schoen, Ernst; and Decker, Walter, 4,293,657, Cl. 521-121.000.

- Jasmin, Gilles; and Bowles, John P., to Hydro-Quebec. System for simulating the operating characteristics of electric machines. 4,293,923, Cl. 364-802.000.
- Jaworski, Eugene; and Breslow, Jeffrey D., to Marvin Glass & Associates. Toy launching device. 4,292,756, Cl. 46-72.000.
- Jeco Co., Ltd.: See—
Tanaka, Toyonaru; and Naito, Hideki, 4,293,842, Cl. 340-52.00F.
- Jedlinski, Stanislaw: See—
Jedlinski, Zbigniew; Thomalla, Bogdan; Kotas, Antoni; Jedlinski, Stanislaw; Pilat, Wladyslaw; and Jach, Jan, 4,293,685, Cl. 528-190.000.
- Jedlinski, Zbigniew; Thomalla, Bogdan; Kotas, Antoni; Jedlinski, Stanislaw; Pilat, Wladyslaw; and Jach, Jan, to Polska Akademia Nauk Zaklad Polimerow. Method for manufacturing crosslinked polyether-ester resins. 4,293,685, Cl. 528-190.000.
- Jellema, Auke, to Staalkat B.V. Method and apparatus for denesting a plurality of containers filled with articles. 4,293,272, Cl. 414-744.00B.
- Jennings, Frederick R.: See—
Buschor, Josef J.; and Jennings, Frederick R., 4,292,787, Cl. 53-456.000.
- Jensen, Elwood V.; and Hospelhorn, Verne D., to University Patents, Inc. Estrophilin detection. 4,293,536, Cl. 424-1.000.
- Jersey Nuclear-Avco Isotopes, Inc.: See—
Horton, James A., 4,293,112, Cl. 248-487.000.
- McAllister, Gary L.; and Draggoo, V. G., 4,293,827, Cl. 331-94.5ML.
- Jidosha Kiki Co., Ltd.: See—
Ohta, Ryuji; and Inoue, Yoshimichi, 4,292,887, Cl. 92-94.000.
- Jinnai, Koichiro; Horike, Masanori; Iwasaki, Kyuhachiro; and Kodama, Yutaka, to Ricoh Co., Ltd. Ink-jet recording apparatus. 4,293,865, Cl. 346-140.00R.
- Jinnouchi, Takeshi. Bellows apparatus. 4,292,885, Cl. 92-43.000.
- Joanis, Marvin A., Sr. Sewer cleaning blade stabilizer. 4,292,704, Cl. 15-104.35N.
- Johannes, Gerald E. Silicone rubber explosive and method of making. 4,293,351, Cl. 149-19.200.
- Johansen, Arne W., to Adidas Fabrique de Chaussures de Sport. Ski binding for cross-country skis. 4,293,143, Cl. 280-615.000.
- Johansson, Hans E.: See—
Andersson, Kjell R.; and Johansson, Hans E., 4,293,612, Cl. 428-281.000.
- John D. Hollingsworth on Wheels, Inc.: See—
Bonner, Alvin T., Sr., 4,292,712, Cl. 19-159.00A.
- Johnson, Betty S.: See—
Buckman, John D.; Buckman, Stanley J.; Johnson, Betty S.; and Pera, John D., 4,293,559, Cl. 424-270.000.
- Johnson, Douglas L., to White's Electronics, Inc. Balanced search loop for metal detector. 4,293,816, Cl. 324-329.000.
- Johnson & Johnson Baby Products Company: See—
Klasek, Ladislav J.; Lamber, Clarence F.; and Passafiume, Anthony, 4,293,367, Cl. 156-494.000.
- Johnson, Julius T.; and Johnson, Robert R. Raw milk transfer systems. 4,292,994, Cl. 137-351.000.
- Johnson, Lewis A.: See—
Wirostko, Emil; and Johnson, Lewis A., 4,293,568, Cl. 424-330.000.
- Johnson, Ralph E., to Singer Company, The. Rotatable loop taker and bobbin case assembly. 4,292,906, Cl. 112-184.000.
- Johnson, Robert R.: See—
Johnson, Julius T.; and Johnson, Robert R., 4,292,994, Cl. 137-351.000.
- Johnston, J. O'Neal: See—
Metcalf, Brian W.; and Johnston, J. O'Neal, 4,293,548, Cl. 424-242.000.
- Jones, Edward M.; and Simmons, Carlton J., Jr., to Baldwin Piano & Organ Company. Automatic control apparatus for chords and sequences. 4,292,874, Cl. 84-1.030.
- Jones, Edward S.: See—
Krelling, William H.; and Jones, Edward S., 4,293,595, Cl. 427-121.000.
- Krelling, William H.; and Jones, Edward S., 4,293,610, Cl. 428-246.000.
- Jones, James A.: See—
Werneke, Michael F.; and Jones, James A., 4,293,406, Cl. 209-166.000.
- Jonsson, Carl David. Method and apparatus for facilitating underwater work on ship hulls and like objects. 4,292,914, Cl. 114-222.000.
- Joseph, Christian M., to Manufacture de Produits Chimiques Protex. Setting retardatives for compositions with a gypsum plaster base or anhydrite. 4,293,344, Cl. 106-111.000.
- Joseph Gamell Industries, Inc.: See—
Gamell, Joseph A., 4,293,777, Cl. 290-52.000.
- Josson, Sven A.: See—
Riede, Gerhard; Larsson, Lars-Ake L.; Andersson, Roland J. E.; Josson, Sven A.; and Traven, Lars J. C., 4,293,409, Cl. 210-96.200.
- Joyce, Glover C.: See—
Kirk, Calvin K.; Joyce, Glover C.; and Messier, Francis L., 4,292,766, Cl. 51-105.0SP.
- Juda, Walter: See—
Allen, Robert J.; Lindstrom, Robert; and Juda, Walter, 4,293,396, Cl. 204-106.000.
- Judelson Industries Division, John Dusenbery Co., Inc.: See—
Stoffels, Carl A.; and Genovese, Nicholas J., 4,292,867, Cl. 82-47.000.
- Jyojiki, Masao: See—
Tokutomi, Seiji; Jyojiki, Masao; and Nakamura, Kazuo, 4,293,205, Cl. 354-23.00D.
- Tokutomi, Seiji; Jyojiki, Masao; Aoki, Harumi; Nakamura, Kazuo; and Watanabe, Koichiro, 4,293,206, Cl. 354-25.000.
- K.R.P. Plastiques: See—
Vernon, Michel, 4,293,511, Cl. 264-55.000.
- K-2 Corporation: See—
Davignon, Alan J., 4,293,142, Cl. 280-610.000.
- Kabushiki Kaisha Daini Seikoshu: See—
Tanaka, Kojiro; Ochiai, Shozo; and Noda, Hideki, 4,293,782, Cl. 307-350.000.
- Kabushiki Kaisha GEMVAC: See—
Sakuma, Shinzo; and Yanagisawa, Hifumi, 4,293,748, Cl. 200-144.00B.
- Kabushiki Kaisha Kurio-Medikaru: See—
Yamauchi, Toshima; Nogami, Sadao; Sawada, Kengi; Moriya, Jyunichiro; Sawada, Hiroomi; and Kobayashi, Keizou, 4,292,973, Cl. 128-303.100.
- Kabushiki Kaisha Meidensha: See—
Sakuma, Shinzo; and Yanagisawa, Hifumi, 4,293,748, Cl. 200-144.00B.
- Kabushiki Kaisha Sato Kenkyusho: See—
Sato, Yo, 4,292,894, Cl. 101-291.000.
- Kabushiki Kaisha Suwa Seikoshu: See—
Gomi, Yoshifumi, 4,293,235, Cl. 400-322.000.
- Kabushiki Kaisha Tokai Rika Denki Seisakusho: See—
Iwata, Masayoshi; and Douke, Harumi, 4,293,743, Cl. 200-4.000.
- Kabushiki Kaisha Toyota Chuo Kenkyusho: See—
Tanasawa, Yasusi; Muto, Norio; Saito, Akinori; and Kawamura, Kiyomi, 4,292,947, Cl. 123-445.000.
- Kaczynski, Thomas E., to Kennametal Inc. Toolholder with expansible shank. 4,292,866, Cl. 82-36.00R.
- Kaga, Sumihiko: See—
Tsuzuki, Yoshihiko; Kaga, Sumihiko; and Hobo, Nobuhito, 4,293,893, Cl. 362-38.000.
- Kai Cutlery Center Co., Ltd.: See—
Osada, Hiroshi, 4,292,738, Cl. 30-162.000.
- Kaiya, Nobuo: See—
Sasaki, Shosaku; and Kaiya, Nobuo, 4,293,671, Cl. 525-478.000.
- Kajitani, Makoto: See—
Fujimura, Hajime; Hiramatsu, Yasuzo; Yabuuchi, Takahiro; Hisaki, Masakatu; Takikawa, Katsuo; Honna, Takaji; Miyake, Hidekazu; and Kajitani, Makoto, 4,293,713, Cl. 564-38.000.
- Kajiwara, Takao: See—
Hatada, Kenzo; and Kajiwara, Takao, 4,293,637, Cl. 430-314.000.
- Kakinuma, Mitsuru; and Takahashi, Yoshitaka, to Sanyo Electric Co., Ltd.; and Tokyo Sanyo Electric Co., Ltd. Control device for ice making machine. 4,292,812, Cl. 62-157.000.
- Kako, Hiroyoshi; and Arai, Hajime, to Toyota Jidosha Kogyo Kabushiki Kaisha. Transfer device associated with power transmission. 4,292,860, Cl. 74-665.0GA.
- Kakumoto, Ken-ichi; and Fujita, Yoshiki, to Koyo Seiko Company Limited. Anti-friction bearing. 4,293,171, Cl. 308-188.000.
- Kamejima, Kohji; Tanaka, Hideki; Kano, Minoru; and Fukushima, Toshihiko, to Hitachi, Ltd. Operating method for refrigerating machine. 4,292,811, Cl. 62-56.000.
- Kamino, Yasumi: See—
Inaba, Hideya; Nagai, Kenichi; Ichiki, Masayoshi; Kamino, Yasumi; and Maeda, Kazuo, 4,293,447, Cl. 252-461.000.
- Kamioka, Hajime: See—
Takagi, Mikio; Maeda, Mamoru; and Kamioka, Hajime, 4,293,589, Cl. 427-93.000.
- Takagi, Mikio; Maeda, Mamoru; and Kamioka, Hajime, 4,293,590, Cl. 427-93.000.
- Kamogawa, Nin-ichi: See—
Yamazaki, Yoshio; Kamogawa, Nin-ichi; and Iwai, Yasuyuki, 4,292,922, Cl. 118-657.000.
- Kamp, Arthur J.: See—
Kelly, Kerry J.; and Kamp, Arthur J., 4,293,379, Cl. 376-159.000.
- Kanada, Hiroshi, to Matsushita Electric Works, Ltd. Switch. 4,293,753, Cl. 200-315.000.
- Kanda, Hiroshi: See—
Mikami, Yasuo; Kanda, Hiroshi; and Uno, Akio, 4,293,574, Cl. 426-46.000.
- Kando, Toru; and Morisawa, Tahei, to Asahi Kogaku Kogyo Kabushiki Kaisha. Release button device for camera. 4,293,210, Cl. 354-269.000.
- Kanegafuchi Kagaku Kogyo Kabushiki Kaisha: See—
Iijima, Tokuzo; Samejima, Yasushi; Kishimoto, Kazuo; Komabashiri, Takamichi; and Kano, Toshiji, 4,293,395, Cl. 204-98.000.
- Kaneko, Hisamitsu: See—
Iwaki, Tetsuo; Takahashi, Yukio; Moriuchi, Shuji; and Kaneko, Hisamitsu, 4,293,720, Cl. 568-575.000.
- Kangol Magnet Limited: See—
Standing, David L., 4,293,106, Cl. 242-107.40A.
- Kanjo, Wajih: See—
Weseloh, Roger J.; Kanjo, Wajih; and Karim, Syed, 4,292,721, Cl. 29-243.520.
- Kano, Minoru: See—
Kamejima, Kohji; Tanaka, Hideki; Kano, Minoru; and Fukushima, Toshihiko, 4,292,811, Cl. 62-56.000.

- Kano, Toshiji: See—
Iijima, Tokuzo; Samejima, Yasushi; Kishimoto, Kazuo; Komabashiri, Takamichi; and Kano, Toshiji, 4,293,395, Cl. 204-98.000.
- Kan'o, Yoshiharu: See—
Tanaka, Yoshikazu; Shirai, Hitoshi; and Kan'o, Yoshiharu, 4,293,931, Cl. 365-222.000.
- Kapetanacos, Christos A. Generation of intense, high-energy ion pulses by magnetic compression of ion rings. 4,293,794, Cl. 315-111.810.
- Karch, John A.: See—
Burk, Emmett H., Jr.; Yoo, Jin S.; Karch, John A.; and Sun, Jui-Yuan, 4,293,403, Cl. 208-120.000.
- Karev, Nikolai V.: See—
Kuzin, Eduard N.; Korelin, Vladimir F.; Fainzilber, Mikhail L.; Egorov, Jury P.; Erofeenko, Igor V.; Karev, Nikolai V.; Kozlov, Jury S.; Kudish, Viktor B.; Kolbasov, Valery K.; and Bobchenok, Meri I., 4,293,238, Cl. 405-175.000.
- Karim, Syed: See—
Weseloh, Roger J.; Kanjo, Wajih; and Karim, Syed, 4,292,721, Cl. 29-243.520.
- Karmanski, Stanislaw: See—
Pretor, Wincenty; Rozmus, Edward; Korecki, Zbigniew; and Karmanski, Stanislaw, 4,293,248, Cl. 405-300.000.
- Karol, Frederick J.: See—
Hamer, Anthony D.; and Karol, Frederick J., 4,293,673, Cl. 526-88.000.
- Kasamatsu, Kiyoshi: See—
Suzuki, Yukio; Kasamatsu, Kiyoshi; and Aketa, Kohichi, 4,293,504, Cl. 260-465.00D.
- Kashiwagi, Tutomu, to Dai-Ichi Seiko Co., Ltd. Counter. 4,293,765, Cl. 235-144.00R.
- Kasuga, Munee: See—
Nishikawa, Masaji; and Kasuga, Munee, 4,293,213, Cl. 355-14.00R.
- Katada, Hiroshi; and Kyogoku, Yoshito, to Hitachi, Ltd. Ignition system for internal combustion engines. 4,292,942, Cl. 123-418.000.
- Katada, Hiroshi: See—
Kyogoku, Yoshito; and Katada, Hiroshi, 4,292,943, Cl. 123-427.000.
- Kato, Yasuo: See—
Wada, Shinji; Kitao, Ikuo; Oana, Yoshinori; Kato, Yasuo; and Ishihara, Taketoshi, 4,293,199, Cl. 351-13.000.
- Katz, Bernard R., to Telegram Communications Corp. Wide bandwidth video amplifier. 4,293,875, Cl. 358-184.000.
- Kaufmann, Kenneth M., to Pako Corporation. Automatic replenisher control system. 4,293,211, Cl. 354-298.000.
- Kawai, Kazuo: See—
Tamori, Michitoshi; and Kawai, Kazuo, 4,293,952, Cl. 375-14.000.
- Kawai, Yoshio: See—
Asano, Kiro; Tamura, Humio; Nezu, Yushi; Saito, Tsuyoshi; and Kawai, Yoshio, 4,293,533, Cl. 423-449.000.
- Kawakami, Yoshiyuki: See—
Sawa, Yoichi; Kawakami, Yoshiyuki; and Marumoto, Ryuji, 4,293,690, Cl. 536-24.000.
- Kawamoto, Mineo: See—
Morishita, Hirosada; Kawamoto, Mineo; and Murakami, Kanzi, 4,293,592, Cl. 427-98.000.
- Kawamura, Kiyomi: See—
Tanasawa, Yasusi; Muto, Norio; Saito, Akinori; and Kawamura, Kiyomi, 4,292,947, Cl. 123-445.000.
- Kawasaki, Masahiro: See—
Aoki, Harumi; Kawasaki, Masahiro; and Sawada, Yoshio, 4,293,207, Cl. 354-25.000.
- Kawasaki Steel Corporation: See—
Matsumura, Ko; Nakamura, Hiroto; and Irie, Toshio, 4,293,336, Cl. 75-124.000.
- Kawashima, Kazuma, to Olympus Optical Company Ltd. Apparatus for automatically controlling the position of endoscopes or similar devices in a cavity. 4,292,961, Cl. 128-6.000.
- Kay, David B.; Wheelless, Leon L., Jr.; and Cambier, James L., to Research Corporation. Multidimensional slit-scan flow system. 4,293,221, Cl. 356-318.000.
- Kaznachevsky, Nikolai A.: See—
Kopylov, Alexei A.; Kuzmenko, Valentin T.; Stepanov, Alexandr N.; Gaschenko, Viktor P.; Kaznachevsky, Nikolai A.; Nosovitsky, Alexandr Y.; Misikov, Ivan I.; Shapiro, Alexandr I.; Skakunov, Ivan G.; Markin, Valentin G.; Konstantinov, Alexei K.; Abramian, Eduard S.; Soroka, Arseny M.; and Zinchenko, Yakov A., 4,292,928, Cl. 119-17.000.
- Keene Corporation: See—
Budnovitch, William F.; Petralia, Salvatore C.; and Silvestris, Louis F., 4,293,898, Cl. 362-291.000.
- Keessler, Floyd F.: See—
Bailey, David C.; and Keessler, Floyd F., 4,293,124, Cl. 271-233.000.
- Keller, Ernst. Double sided tumbler cylinder for a security lock. 4,292,824, Cl. 70-373.000.
- Keller, Hans; and Knop, Hans-Georg, to Dr.-Ing. Rudolf Hell GmbH. Production of printing blocks or forms. 4,293,872, Cl. 358-75.000.
- Kelly, Darrell A.: See—
Plischke, LeMoyné W.; Familant, Harold M.; and Kelly, Darrell A., 4,293,614, Cl. 428-370.000.
- Kelly, James J. Apparatus for fastening insulation to a pipe. 4,293,005, Cl. 138-149.000.
- Kelly, Joseph L., Jr.: See—
Mullins, John M.; and Kelly, Joseph L., Jr., 4,293,039, Cl. 166-341.000.
- Kelly, Kerry J.; and Kamp, Arthur J., to Dow Chemical Company. The Neutron activation analysis method and apparatus for determining sodium and sodium compounds in liquid samples. 4,293,379, Cl. 376-159.000.
- Kendall Company, The: See—
Davenport, Stanley, Jr., 4,292,687, Cl. 2-2.000.
- Kennametal Inc.: See—
Kaczynski, Thomas E., 4,292,866, Cl. 82-36.00R.
- Kennecott Corporation: See—
Henri, Paul, 4,293,111, Cl. 248-95.000.
- Kennedy, Jerome J.; Wayne, Harold S.; and White, Charles A., to U.S. Industries, Inc. Egg transporting system. 4,293,066, Cl. 198-813.000.
- Kenyon, William E.: See—
Park, Sung K.; and Kenyon, William E., 4,293,933, Cl. 367-25.000.
- Keoteklian, Hagop, to Entenmann's, Inc. Apparatus for treating plant effluent. 4,293,416, Cl. 210-208.000.
- Kernforschungsanlage Julich GmbH: See—
Luhleisch, Hartmut; Pfau, Peter; Dias, Francisco J.; Nauomidis, Aristides; Schirbach, Arno; and Nickel, Hubertus, 4,293,512, Cl. 264-58.000.
- Kewanee Industries: See—
Swift, Harold E.; Innes, Robert A.; and Adams, Phillip, 4,293,716, Cl. 564-480.000.
- Kiesling, Norbert W., to Colt Industries Operating Corp. Fuel injection apparatus and system. 4,292,945, Cl. 123-438.000.
- Kikuchi, Tsuyoshi; and Takusagawa, Kiyoshi, to Toshiba Kikai Kabushiki Kaisha. Spray device for a die casting machine. 4,293,024, Cl. 164-303.000.
- Kim, Matthew S. Adjustable convex rearview mirror. 4,293,191, Cl. 350-293.000.
- Kim, Oh-Kil: See—
Fox, Robert B.; and Kim, Oh-Kil, 4,293,452, Cl. 252-518.000.
- Kimura, Tsutomu: See—
Ohnishi, Masahiro; and Kimura, Tsutomu, 4,293,202, Cl. 354-5.000.
- Kinast, Gunther; Muller, Lutz; Puls, Walter; and Sitt, Rudiger, to Bayer Aktiengesellschaft. N-Amino-3,4,5-trihydroxypiperidines, their production and their medicinal use. 4,293,551, Cl. 424-249.000.
- King, Clyde R., to Eagle-Picher Industries, Inc. Tool for applying insulation to pipes. 4,292,713, Cl. 24-24.000.
- King, Dallas E., to General Motors Corporation. Dynamoelectric machine brush rigging. 4,293,789, Cl. 310-239.000.
- King, Harold B., to General Electric Company. Nuclear fuel rod loading apparatus. 4,292,788, Cl. 53-500.000.
- King, Harry A.: See—
Gordon, Robert; King, Harry A.; Springrose, James V.; and Cud-dihy, Robert W., 4,292,898, Cl. 105-238.00R.
- King, Junior K.: See—
Gookins, William L.; and King, Junior K., 4,293,854, Cl. 340-615.000.
- Kinoshita, Makoto: See—
Ebata, Yoshihiro; Toibana, Yasuo; Uetsuki, Tsuneo; Kose, Saburo; and Kinoshita, Makoto, 4,293,356, Cl. 156-89.000.
- Kinoshita, Minoru; Sugou, Kiyoshi; and Onoda, Yukio, to Dainippon Screen Seizo Kabushiki Kaisha. Photographic film blackening area measuring device. 4,293,226, Cl. 356-443.000.
- Kirby, Raymond L., Jr., to Monarch Marking Systems, Inc. Endless band printer with spacers between drive wheels. 4,292,893, Cl. 101-111.000.
- Kirchoff, Robert A.: See—
Moore, Carl; and Kirchoff, Robert A., 4,293,476, Cl. 260-29.70W.
- Kirk, Calvin K.; Joyce, Glover C.; and Messier, Francis L., to Warner & Swasey Company, The. Method and apparatus for grinding a workpiece. 4,292,766, Cl. 51-105.0SP.
- Kirk, Joseph P.: See—
Gaston, Charles A.; Kirk, Joseph P.; and Wasik, Chester A., 4,293,224, Cl. 356-357.000.
- Kirzner, Felix I.: See—
Romanov, Viktor I.; Kirzner, Felix I.; and Soroka, Yakov K., 4,293,273, Cl. 415-78.000.
- Kishi, Tunes; and Sasaki, Koji, to Hitachi, Ltd. Puffer type gas circuit breaker. 4,293,749, Cl. 200-144.0AP.
- Kishimoto, Kazuo: See—
Iijima, Tokuzo; Samejima, Yasushi; Kishimoto, Kazuo; Komabashiri, Takamichi; and Kano, Toshiji, 4,293,395, Cl. 204-98.000.
- Kistler Instrumente AG: See—
Maag, Willi; Baumgartner, Hans U.; Vollenweider, Max; and Wolf, Hans J., 4,292,769, Cl. 51-169.000.
- Kitao, Ikuo: See—
Wada, Shinji; Kitao, Ikuo; Oana, Yoshinori; Kato, Yasuo; and Ishihara, Taketoshi, 4,293,199, Cl. 351-13.000.
- Kitao, Takaya: See—
Noguchi, Satoshi; and Kitao, Takaya, 4,293,940, Cl. 368-75.000.
- Klasek, Ladislav J.; Lamber, Clarence F.; and Passafiume, Anthony, to Johnson & Johnson Baby Products Company. Apparatus for effecting securement of a transversely moved elastic ribbon to a moving web. 4,293,367, Cl. 156-494.000.
- Klauke, Erich: See—
Hamprecht, Rainer; Hartmann, Alfons; Klauke, Erich; Hammann, Ingeborg; Roessler, Peter; and Brandes, Wilhelm, 4,293,566, Cl. 424-304.000.
- Klein, Max. Enhanced wet strength filter mats to separate particulates from fluids and/or coalesce entrained droplets from gases. 4,293,378, Cl. 162-145.000.
- Kleine, Albert W., Jr.: See—
Gills, Richard G.; Hille, Earl A.; Kleine, Albert W., Jr.; and Shamp, Donald E., 4,293,264, Cl. 414-38.000.
- Klemann, Lawrence P.; Newman, Gerald H.; Stogryn, Eugene L.; Whitney, Thomas A.; and Farcastu, Dan, to Exxon Research &

- Engineering Co. Electrolytes for alkali-metal electrochemical devices. 4,293,623, Cl. 429-194.000.
- Klemarczyk, Philip: See—
Sprecker, Mark A.; Sanders, James M.; Schreiber, William L.; Watkins, Hugh; Vinals, Joaquin F.; Shuster, Edward J.; O'Rourke, Thomas J.; Hagedorn, Myrna L.; and Klemarczyk, Philip, 4,293,453, Cl. 252-522.00R.
- Klements, Walter S.: See—
Meares, Harry E., Jr., 4,293,083, Cl. 222-133.000.
- Klemm, Walter: See—
Sommer, Klaus; Klemm, Walter; Weber, Hermann; Meinhardt, Friedrich; Schonmann, Gerhard; and Spatz, Wilhelm, 4,293,526, Cl. 422-205.000.
- Kleppner, Daniel, to Massachusetts Institute of Technology. Detecting IR and mm radiation. 4,293,769, Cl. 250-338.000.
- Klie, Wolfgang: See—
Lutze, Hans; Weishappel, Helmut; Klie, Wolfgang; and Weidemann, Dieter, 4,293,160, Cl. 296-188.000.
- Klockner-Humboldt-Deutz AG: See—
Sauer, Fried, 4,293,123, Cl. 266-268.000.
- Klockner-Werke AG: See—
Boer, Werner; Lachner, Hans; Maschon, Guenter; Richter, Joerg; Schulte, Heinrich; and Warnke, Hans, 4,293,246, Cl. 405-291.000.
- Kloesel, Joseph A., Jr., to Smith International, Inc. Jet dual bit. 4,293,048, Cl. 175-340.000.
- Klopper, Howard J.: See—
Takekoshi, Tohru; and Klopfer, Howard J., 4,293,683, Cl. 528-180.000.
- Kluger, Edward W.; and Su, Tien-Kuei, to Milliken Research Corporation. Nitrogen containing compounds and compositions. 4,293,682, Cl. 528-123.000.
- Knappenberger, Thomas A.; and Landers, James F., Jr., to Motorola Inc. Method for potting and encapsulating electronic circuits. 4,293,519, Cl. 264-272.130.
- Knickerbocker, Robert H., to Siemon Company, The. Electrical circuit tester. 4,293,174, Cl. 339-64.00M.
- Knoll, Alois, to Centra-Burkle GmbH & Co. Arrangement for controlling room temperature. 4,293,028, Cl. 165-12.000.
- Knop, Hans-Georg: See—
Keller, Hans; and Knop, Hans-Georg, 4,293,872, Cl. 358-75.000.
- Knowles, Richard P., to Lucas Industries Limited. Starting aids for internal combustion engines. 4,292,934, Cl. 123-145.00A.
- Knox, Kenneth L., to Du Pont de Nemours, E. I., and Company. Die with insert and its use. 4,293,517, Cl. 264-176.00R.
- Kobayakawa, Masaki: See—
Kojima, Masayuki; Kobayakawa, Masaki; and Tanaka, Kozo, 4,293,793, Cl. 313-497.000.
- Kobayashi, Keizou: See—
Yamauchi, Toshima; Nogami, Sadao; Sawada, Kengi; Moriya, Junichiro; Sawada, Hiroomi; and Kobayashi, Keizou, 4,292,973, Cl. 128-303.100.
- Kobayashi, Koichi; and Okudaira, Sadao, to Asahi Kogaku Kogyo Kabushiki Kaisha. Telephoto lens with small telephoto ratio. 4,293,197, Cl. 350-454.000.
- Kobayashi, Kunimitsu: See—
Ishibai, Isao; and Kobayashi, Kunimitsu, 4,293,187, Cl. 350-36.000.
- Kobayashi, Masahiko: See—
Ishikawa, Masayuki; Tanaka, Hiromichi; Eguchi, Yukuo; Ito, Shigeru; Takashima, Yoshimi; and Kobayashi, Masahiko, 4,293,553, Cl. 424-250.000.
- Kobayashi, Nariyoshi; Sakamoto, Takeshi; Anzai, Shunichi; and Matsumoto, Manabu, to Hitachi, Ltd. Gas turbine blade cooling structure. 4,293,275, Cl. 416-97.00R.
- Kobayashi, Yoshio: See—
Ogimoto, Kazuo; Inoue, Tomohiro; Tanaka, Susumu; and Kobayashi, Yoshio, 4,293,240, Cl. 405-195.000.
- Kobylar, Alex W.: See—
Stelte, David J.; and Kobylar, Alex W., 4,293,738, Cl. 179-18.0FC.
- Kobyliniski, Thaddeus P.: See—
Beach, David L.; and Kobyliniski, Thaddeus P., 4,293,724, Cl. 585-457.000.
- Beach, David L.; and Kobyliniski, Thaddeus P., 4,293,725, Cl. 585-523.000.
- Beach, David L.; and Kobyliniski, Thaddeus P., 4,293,726, Cl. 585-523.000.
- Kochis, August J. Multi-panel closures. 4,292,764, Cl. 49-237.000.
- Kodama, Yutaka: See—
Jinnai, Koichi; Horike, Masanori; Iwasaki, Kiyuhiro; and Kodama, Yutaka, 4,293,865, Cl. 346-140.00R.
- Koeman, James B., to Lord Corporation. Prosthesis anchoring means. 4,292,694, Cl. 3-1.910.
- Koeman, James B., to Lord Corporation. Prosthesis stem. 4,292,695, Cl. 3-1.910.
- Koenig, Robert H., to Tapeswitch Corporation of America. Self adhering tape switch. 4,293,752, Cl. 200-295.000.
- Koenigs, Hans B.: See—
Lorenz, Kurt; Dungs, Horst; Koenigs, Hans B.; and Kurtz, Roman, 4,293,388, Cl. 202-126.000.
- Kohayakawa, Yoshimi; Ishikawa, Yasuyuki; and Maruyama, Shigeo, to Canon Kabushiki Kaisha. Eye refractometer. 4,293,198, Cl. 351-13.000.
- Kohn, Alfred: See—
Forrest, Michael R.; and Kohn, Alfred, 4,292,690, Cl. 2-65.000.
- Forrest, Michael R.; and Kohn, Alfred, 4,292,691, Cl. 2-65.000.
- Koike, Mitsuhiro; and Iwasaki, Yasuhiro, to Silver Seiko, Ltd. Needle selection mechanism in a hand-operated knitting machine. 4,292,821, Cl. 66-75.200.
- Koizumi, Naoyuki: See—
Shibata, Kenyu; Itaya, Toshihisa; Yamakoshi, Nobuaki; Kurata, Shigeru; Koizumi, Naoyuki; Tarutani, Masaaki; Sakuma, Hideki; and Konishi, Kunihiro, 4,293,557, Cl. 424-267.000.
- Kojima, Masaharu; and Mitomi, Seiji, to Nifco Inc. Screw grommet. 4,293,260, Cl. 411-44.000.
- Kojima, Masayuki; Kobayakawa, Masaki; and Tanaka, Kozo, to Nippon Electric Co., Ltd. Fluorescent display tube. 4,293,793, Cl. 313-497.000.
- Kokta, Milan R.; and Taylor, Roger W., to Union Carbide Corporation. Method of making magnetic film-substrate composites. 4,293,371, Cl. 156-624.000.
- Kokubun Inc.: See—
Kokubun, Shusuke, 4,292,879, Cl. 87-57.000.
- Kokubun, Shusuke, to Kokubun Inc. Hook assembly for spring tension carrier in braiding machine. 4,292,879, Cl. 87-57.000.
- Kokusai Denshin Denwa Co., Ltd.: See—
Tamori, Michitoshi; and Kawai, Kazuo, 4,293,952, Cl. 375-14.000.
- Kolb, Gunter: See—
Probst, Joachim; Sonntag, Michael; and Kolb, Gunter, 4,293,661, Cl. 525-127.000.
- Kolb, Norman P.; and Webb, Orlando, to Stratford/Graham Engineering Corp. Alkylation with DIB vapor acid wash. 4,293,729, Cl. 585-715.000.
- Kolbasov, Valery K.: See—
Kuzin, Eduard N.; Korelin, Vladimir F.; Fainzilber, Mikhail L.; Egorov, Yuri P.; Erofeenko, Igor V.; Karev, Nikolai V.; Kozlov, Yuri S.; Kudish, Viktor B.; Kolbasov, Valery K.; and Bobchenok, Meri I., 4,293,238, Cl. 405-175.000.
- Komabashiri, Takamichi: See—
Iijima, Tokuzo; Samejima, Yasushi; Kishimoto, Kazuo; Komabashiri, Takamichi; and Kano, Toshiji, 4,293,395, Cl. 204-98.000.
- Komaki, Shigeki, to Sharp Kabushiki Kaisha. Thin and flat keyboard integral with a metallic housing. 4,293,754, Cl. 200-340.000.
- Kong, San P.: See—
Wong, Chung-Chee, 4,293,896, Cl. 362-200.000.
- Konishi, Kunihiro: See—
Shibata, Kenyu; Itaya, Toshihisa; Yamakoshi, Nobuaki; Kurata, Shigeru; Koizumi, Naoyuki; Tarutani, Masaaki; Sakuma, Hideki; and Konishi, Kunihiro, 4,293,557, Cl. 424-267.000.
- Konishiroku Photo Industry Co., Ltd.: See—
Yamazaki, Yoshio; Kamogawa, Nin-ichi; and Iwai, Yasuyuki, 4,292,922, Cl. 118-657.000.
- Konstantinov, Alexei K.: See—
Kopylov, Alexei A.; Kuzmenko, Valentin T.; Stepanov, Alexandr N.; Gaschenko, Viktor P.; Kaznacheyevsky, Nikolai A.; Nosovitsky, Alexandr Y.; Misikov, Ivan I.; Shapiro, Alexandr I.; Skakunov, Ivan G.; Markin, Valentin G.; Konstantinov, Alexei K.; Abramian, Eduard S.; Soroka, Arseny M.; and Zinchenko, Yakov A., 4,292,928, Cl. 119-17.000.
- Kopecky, Ivyl D.: See—
Neukom, Chester G.; and Kopecky, Ivyl D., 4,293,043, Cl. 172-267.000.
- Koppe, Herbert: See—
Stahle, Helmut; Koppe, Herbert; Kummer, Werner; Hoefke, Wolfgang; Gaida, Wolfram; and Pichler, Ludwig, 4,293,564, Cl. 424-273.00R.
- Kopperschlager, Dieter: See—
Reinhard, Theodor; Krugener, Rolf; Kurth, Hermann W.; Blaich, Diether; Rothmaier, Franz; Kopperschlager, Dieter; Schmitz, Heinz; and Nill, Edgar, 4,292,823, Cl. 70-364.00R.
- Kopylov, Alexei A.; Kuzmenko, Valentin T.; Stepanov, Alexandr N.; Gaschenko, Viktor P.; Kaznacheyevsky, Nikolai A.; Nosovitsky, Alexandr Y.; Misikov, Ivan I.; Shapiro, Alexandr I.; Skakunov, Ivan G.; Markin, Valentin G.; Konstantinov, Alexei K.; Abramian, Eduard S.; Soroka, Arseny M.; and Zinchenko, Yakov A., 4,292,928, Cl. 119-17.000.
- Korber, Helmut: See—
Heydenreich, Frieder; Korber, Helmut; Tacke, Peter; Fahner, Friedrich; and Neuray, Dieter, 4,293,662, Cl. 525-184.000.
- Kordas, Friedel, to Intensiv-Filter GmbH & Co. KG. Fastening device for filter bags in dust-laden gas filters. 4,293,321, Cl. 55-357.000.
- Korecki, Zbigniew: See—
Pretor, Wincenty; Rozmus, Edward; Korecki, Zbigniew; and Karmanski, Stanislaw, 4,293,248, Cl. 405-300.000.
- Korelin, Vladimir F.: See—
Kuzin, Eduard N.; Korelin, Vladimir F.; Fainzilber, Mikhail L.; Egorov, Yuri P.; Erofeenko, Igor V.; Karev, Nikolai V.; Kozlov, Yuri S.; Kudish, Viktor B.; Kolbasov, Valery K.; and Bobchenok, Meri I., 4,293,238, Cl. 405-175.000.
- Korff, William W.: See—
Carpenter, Edward J.; Korff, William W.; Zoerb, Alan E., deceased; Barelo, Lawrence J.; Hall, Donald R.; and Becker, Orlien N., 4,293,915, Cl. 364-493.000.
- Kosaka, Kenji; Iwatsuka, Takeshi; Shindo, Ikuro; and Hotogi, Akira, to Rohm and Haas Company. Process and apparatus for ion exchange by use of thermally regenerable resin. 4,293,423, Cl. 210-676.000.
- Kose, Saburo: See—
Ebata, Yoshihiro; Toibana, Yasuo; Uetsuki, Tsuneo; Kose, Saburo; and Kinoshita, Makoto, 4,293,356, Cl. 156-89.000.
- Koshii, Taro: See—
Hanada, Tsuneo; Koshii, Taro; and Shinmi, Hideo, 4,293,479, Cl. 260-37.0EP.

- Koshino, Minoru: See—
Muraoka, Takatoshi; Uchida, Keiichiro; Koshino, Minoru; Motegi, Masanori; and Nagasawa, Shigeru, 4,293,941, Cl. 364-200.000.
- Kostan, Charles C.: See—
Kuhn, Robert L.; and Kostan, Charles C., 4,293,744, Cl. 200-19.00R.
- Kotas, Antoni: See—
Jedlinski, Zbigniew; Thomalla, Bogdan; Kotas, Antoni; Jedlinski, Stanislaw; Pilat, Wladyslaw; and Jach, Jan, 4,293,685, Cl. 528-190.000.
- Koty, Antal: See—
Pataki, Jozsef; Bucsi, Jozsef; Bona, Istvan; Szilvasi, Endre; Gazdag, Andras; Koty, Antal; and Hidvegi, Ferenc, 4,292,996, Cl. 137-393.000.
- Kovach, Julius L. Fission product adsorbent impregnated with quinuclidene. 4,293,317, Cl. 55-71.000.
- Koyo Seiko Company Limited: See—
Kakumoto, Ken-Ichi; and Fujita, Yoshiki, 4,293,171, Cl. 308-188.000.
- Kozima, Akio: See—
Hashimoto, Mitsuru; Ohta, Masafumi; Kozima, Akio; Sakai, Kiyoshi; and Sasaki, Masaomi, 4,293,628, Cl. 430-58.000.
- Kozlov, Yuri S.: See—
Kuzin, Eduard N.; Korelin, Vladimir F.; Fainzilber, Mikhail L.; Egorov, Yuri P.; Erofeenko, Igor V.; Karev, Nikolai V.; Kozlov, Yuri S.; Kudish, Viktor B.; Kolbasov, Valery K.; and Bobchenok, Meri I., 4,293,238, Cl. 405-175.000.
- Kraftwerk Union Aktiengesellschaft: See—
Goetzmann, Claus; and Rau, Peter, 4,293,381, Cl. 376-230.000.
- Harand, Elmar; and Michel, Eberhard, 4,293,386, Cl. 376-461.000.
- Krahenbuhl, Hanspeter: See—
Baur, Rudolf; Merki, Emil; and Krahenbuhl, Hanspeter, 4,293,424, Cl. 210-737.000.
- Kramer, Wolfgang, to Bayer Aktiengesellschaft. Preparation of ω -azoly-acetophenone oxide ethers employing ω -halogeno-acetophenone oxide ethers. 4,293,715, Cl. 564-256.000.
- Krause, Heinz; and Sanner, Bert, to J. F. Tonnes Erben K.G. Method and device for representing electrical spatial lines and spatial images. 4,292,977, Cl. 128-712.000.
- Krause, Nicolaas J. P. R. Apparatus for postural treatment of humans. 4,292,962, Cl. 128-68.000.
- Krave, Carl A. Method, apparatus and package for sprouting seeds. 4,292,760, Cl. 47-14.000.
- Krave, Carl A. Method, apparatus and package for sprouting seeds. 4,292,761, Cl. 47-14.000.
- Kreiling, William H.; and Jones, Edward S., to International Paper Company. Aqueous process for making a conductive medium for electrostatic printing. 4,293,595, Cl. 427-121.000.
- Kreiling, William H.; and Jones, Edward S., to International Paper Company. Electrostatic printing medium. 4,293,610, Cl. 428-246.000.
- Kress, Dieter; and Haberle, Friedrich, to Mapal Fabrik fur Präzisionswerkzeuge. Drill bit. 4,293,252, Cl. 408-224.000.
- Kresse, Horst: See—
Deutscher, Hans-Joachim; Schubert, Herrmann; Seidel, Christina; Demus, Dietrich; and Kresse, Horst, 4,293,434, Cl. 252-299.630.
- Kretzschmar, John L.: See—
West, Jerry B.; Kretzschmar, John L.; and Fung, Bing, 4,293,815, Cl. 324-254.000.
- Kristofek, Paul J., to McGraw-Edison Company. Mounting arrangement for recessed light fixture housing. 4,293,895, Cl. 362-147.000.
- Kroll, Arthur S.; and Shuster, Frank A., to Eastman Kodak Company. Electrophoretic development apparatus. 4,292,921, Cl. 118-648.000.
- Krugener, Rolf: See—
Reinhard, Theodor; Krugener, Rolf; Kurth, Hermann W.; Blaich, Diether; Rothmaier, Franz; Kopperschlager, Dieter; Schmitz, Heinz; and Nill, Edgar, 4,292,823, Cl. 70-364.00R.
- Kubach, Hans; and Rupp, Hartmann, to Robert Bosch GmbH. Controlled d-c current supply system, with controlled current flow through a choke. 4,293,812, Cl. 323-272.000.
- Kubota, Jun, to Doryokuro Kakuenryu Kaihatsu Jigyodan. Method and apparatus for detecting flow instability in steam generator. 4,293,853, Cl. 340-611.000.
- Kubota, Ltd.: See—
Murayama, Yoshinobu, 4,292,855, Cl. 74-15.400.
- Kucera, Carrell J., to Norden Laboratories, Inc. Modified *Pasteurella multocida* bacteria vaccines. 4,293,545, Cl. 424-92.000.
- Kuckens, Alexander, to Dagma Deutsche Automaten und Getrankemaschinen GmbH & Co. KG. Method and device for metered dispensing of liquids, in particular concentrates or syrups, for the production of beverages. 4,293,081, Cl. 222-83.000.
- Kudish, Viktor B.: See—
Kuzin, Eduard N.; Korelin, Vladimir F.; Fainzilber, Mikhail L.; Egorov, Yuri P.; Erofeenko, Igor V.; Karev, Nikolai V.; Kozlov, Yuri S.; Kudish, Viktor B.; Kolbasov, Valery K.; and Bobchenok, Meri I., 4,293,238, Cl. 405-175.000.
- Kuhn, Robert L.; and Kostan, Charles C., to Ford Motor Company. Alignment devices for removable spark plug terminals in an ignition commutation distributor. 4,293,744, Cl. 200-19.00R.
- Kukolja, Stjepan; and Pfeil, Janice L., to Eli Lilly and Company. Azetidinone alcohol disulfides and process for cyclization. 4,293,493, Cl. 260-239.00A.
- Kukolja, Stjepan; and Pfeil, Janice L., to Eli Lilly and Company. Symmetrical azetidinone aldehyde disulfides and process. 4,293,495, Cl. 260-245.400.
- Kull, Leo; and Ebok, Vello H. Single and multicycle control device for electric motors. 4,293,806, Cl. 318-673.000.
- Kumada, Saburoh: See—
Isaka, Tsutomu; and Kumada, Saburoh, 4,293,608, Cl. 428-220.000.
- Kumazawa, Shunji: See—
Fujii, Yoshishige; Nagao, Syozo; and Kumazawa, Shunji, 4,293,418, Cl. 210-321.100.
- Kummer, Werner: See—
Stahle, Helmut; Koppe, Herbert; Kummer, Werner; Hoefke, Wolfgang; Gaida, Wolfram; and Pichler, Ludwig, 4,293,564, Cl. 424-273.00R.
- Kuna, Wayne A.; Thibault, James G.; and Schoenfield, Palmer J., to Marvin Glass & Associates. Jet toy boat. 4,292,758, Cl. 46-93.000.
- Kuras, Michael L.; Upp, Daniel C.; and Toegel, Herbert J., to International Telephone and Telegraph Corporation. Trilateral duplex path conferencing system with broadcast capability. 4,293,946, Cl. 370-62.000.
- Kurata, Shigeru: See—
Shibata, Kenyu; Itaya, Toshihisa; Yamakoshi, Nobuaki; Kurata, Shigeru; Koizumi, Naoyuki; Tarutani, Masaaki; Sakuma, Hideki; and Konishi, Kunihiro, 4,293,557, Cl. 424-267.000.
- Kureha Kagaku Kogyo Kabushiki Kaisha: See—
Asano, Kiro; Tamura, Humio; Nezu, Yushi; Saito, Tsuyoshi; and Kawai, Yoshio, 4,293,533, Cl. 423-449.000.
- Kurei, Hiroshi, to Asahi Kogaku Kogyo Kabushiki Kaisha. Mirror operating mechanism in single lens reflex camera. 4,293,209, Cl. 354-153.000.
- Kuroki, Katsuro: See—
Ichiyama, Tadashi; Yamaguchi, Shigehiro; Iuchi, Tohru; and Kuroki, Katsuro, 4,293,350, Cl. 148-111.000.
- Kurth, Hermann W.: See—
Reinhard, Theodor; Krugener, Rolf; Kurth, Hermann W.; Blaich, Diether; Rothmaier, Franz; Kopperschlager, Dieter; Schmitz, Heinz; and Nill, Edgar, 4,292,823, Cl. 70-364.00R.
- Kurtz, Roman: See—
Lorenz, Kurt; Dungs, Horst; Koenigs, Hans B.; and Kurtz, Roman, 4,293,388, Cl. 202-126.000.
- Kustom Kreations, Inc.: See—
Vernalud, Guy G., 4,293,075, Cl. 211-40.000.
- Kutsukake, Yukinori: See—
Tamamura, Ryo; and Kutsukake, Yukinori, 4,293,335, Cl. 75-124.000.
- Kuwana, Masayuki: See—
Moriyama, Yoshiki; and Kuwana, Masayuki, 4,293,002, Cl. 137-625.640.
- Kuzin, Eduard N.; Korelin, Vladimir F.; Fainzilber, Mikhail L.; Egorov, Yuri P.; Erofeenko, Igor V.; Karev, Nikolai V.; Kozlov, Yuri S.; Kudish, Viktor B.; Kolbasov, Valery K.; and Bobchenok, Meri I., 4,293,238, Cl. 405-175.000.
- Kuzmenko, Valentin T.: See—
Kopylov, Alexei A.; Kuzmenko, Valentin T.; Stepanov, Alexandr N.; Gaschenko, Viktor P.; Kaznacheyevsky, Nikolai A.; Nosovitsky, Alexandr Y.; Misikov, Ivan I.; Shapiro, Alexandr I.; Skakunov, Ivan G.; Markin, Valentin G.; Konstantinov, Alexei K.; Abramian, Eduard S.; Soroka, Arseny M.; and Zinchenko, Yakov A., 4,292,928, Cl. 119-17.000.
- Kyogoku, Yoshito; and Katada, Hiroshi, to Hitachi, Ltd. Contactless ignition system for use with internal combustion engines. 4,292,943, Cl. 123-427.000.
- Kyogoku, Yoshito: See—
Katada, Hiroshi; and Kyogoku, Yoshito, 4,292,942, Cl. 123-418.000.
- Kyokuto Kaihatsu Kogyo Co., Ltd.: See—
Tanaka, Katsushi; and Okamoto, Taro, 4,293,227, Cl. 366-11.000.
- Kyoto Ceramic Co., Ltd.: See—
Shikita, Takuji; and Hirabayashi, Masaya, 4,293,540, Cl. 424-26.000.
- L. S. Starrett Company, The: See—
Neumeyer, Tom A.; and Foster, Francis W., 4,292,871, Cl. 83-661.000.
- Labes, Mortimer M.; and MacMillan, John H., to Temple University. Amine-substituted liquid crystal compositions. 4,293,193, Cl. 350-350.00R.
- Lacaze, Leonard, Jr., to International Telephone and Telegraph Corporation. Low insertion force electrical socket connector. 4,293,181, Cl. 339-258.00R.
- Lachner, Hans: See—
Boer, Werner; Lachner, Hans; Maschon, Guenter; Richter, Joerg; Schulte, Heinrich; and Warnke, Hans, 4,293,246, Cl. 405-291.000.
- Lacy, Robert H., to Phillips Petroleum Company. Keyboard encoder using priority encoders. 4,293,849, Cl. 340-365.00S.
- Laing, Ingeborg: See—
Laing, Karsten; Laing, Ingeborg; and Laing, Oliver, 4,292,773, Cl. 52-171.000.
- Laing, Karsten; Laing, Ingeborg; and Laing, Oliver. Double pane systems with little reflection, in particular for greenhouses. 4,292,773, Cl. 52-171.000.
- Laing, Oliver: See—
Laing, Karsten; Laing, Ingeborg; and Laing, Oliver, 4,292,773, Cl. 52-171.000.
- Laird, William J.: See—
Lopez, Bennie F.; Campbell, Billy H.; Collier, Bobby D.; Laird, William J.; Debona, Edward J.; and Eubanks, James E., Jr., 4,292,880, Cl. 89-1.815.
- Lakra, Ruhama J.; Freund, Jurgen; and Rauschert, Gerd, to Interatom, Internationale Atomreaktorbau GmbH. Nuclear reactor with equip-

- ment for preventing convection of metal vapors. 4,293,383, Cl. 376-290.000.
- Lalonde, Jean-Paul. Cutting and mulching lawn mower blade assembly. 4,292,791, Cl. 56-255.000.
- Lambe, Donald M. Dual-chamber pneumatic tire. 4,293,017, Cl. 152-339.000.
- Lamber, Clarence F.: See—
Klasek, Ladislav J.; Lamber, Clarence F.; and Passafiume, Anthony, 4,293,367, Cl. 156-494.000.
- Lamoreaux, Charles L. Mobile air charging system. 4,293,281, Cl. 417-9.000.
- Lampe, Warren R.: See—
Bessmer, Stanley J.; and Lampe, Warren R., 4,293,597, Cl. 427-186.000.
- Lamson & Sessions Co., The: See—
Pamer, Walter R., 4,293,256, Cl. 411-11.000.
- Land-O-Nod: See—
Woychick, John, 4,292,701, Cl. 5-422.000.
- Landers, James F., Jr.: See—
Knappenberger, Thomas A.; and Landers, James F., Jr., 4,293,519, Cl. 264-272.130.
- Landheer, Hugo A. J., to Hunter Douglas International N.V. Supporting system for panel assembly. 4,292,779, Cl. 52-486.000.
- Landingham, Richard L.; and Huffsmith, Sarah A., to United States of America, Energy. Silicon-nitride and metal composite. 4,293,619, Cl. 428-623.000.
- Landis, Arthur M.; Broughton, Donald B.; and Fickel, R. Gene, to UOP Inc. Simulated countercurrent sorption process employing ion exchange resins with backflushing. 4,293,346, Cl. 127-46.00A.
- Landry, Archie C.: See—
Daswick, Alexander C.; and Landry, Archie C., 4,293,052, Cl. 180-219.000.
- Lang, Edna B., nee Wright executrix: See—
Rosborough, Robert S., Jr.; and Wright, Luther M., deceased, 4,293,215, Cl. 355-40.000.
- Lang, Gerard; and Forestier, Serge, to L'Oreal. Cosmetic composition for imparting to human skin a coloration resembling a natural tan. 4,293,542, Cl. 424-47.000.
- Langenecker, Bertwin. Wire drawing apparatus employing macrosonic techniques. 4,292,826, Cl. 72-45.000.
- Langer, Heimo J.: See—
Martin, Ralph D.; Dunnivant, William R.; Sturtz, Gregory P.; and Langer, Heimo J., 4,293,480, Cl. 260-38.000.
- Langley, Robert C.; Myers, Herbert; and Abrash, Muriel, to Engelhard Minerals & Chemicals Corporation. Method of making honeycomb structures. 4,293,513, Cl. 264-60.000.
- Lanier Business Products, Inc.: See—
Mason, Paul C., 4,293,881, Cl. 360-60.000.
- Lapp, Ellsworth W. Crimping tool. 4,292,833, Cl. 72-416.000.
- Larsen, Tor G., to Measurex Corporation. Caliper gauge for the measurement of sheet members over a wide range of thicknesses. 4,292,838, Cl. 73-37.700.
- Larsson, Bernt: See—
Furendal, Allan R. B.; Larsson, Bernt; and Nilsson, Erik R., 4,293,596, Cl. 427-160.000.
- Larsson, Lars-Ake L.: See—
Riede, Gerhard; Larsson, Lars-Ake L.; Andersson, Roland J. E.; Jossion, Sven A.; and Traven, Lars J. C., 4,293,409, Cl. 210-96.200.
- Larsson, Leif; and Warren, Richard, to Volvo Flygmotor AB. Method of producing an object of fiber reinforced metal material. 4,292,725, Cl. 29-419.00R.
- LaRue, George J.: See—
Morgan, Dean T.; Chrysostomidis, Chrysostomos; and LaRue, George J., 4,293,527, Cl. 423-6.000.
- Laser Alignment, Inc.: See—
Nielsen, Edward G.; Mosley, Kenneth C.; and Chatterson, Louis M., 4,293,218, Cl. 356-138.000.
- Launay, Noel, to Societe d'Assistance Technique pour Produits Nestle S.A. Metering and balancing device and filling machine including such a device. 4,293,049, Cl. 177-212.000.
- Laurer, Peter R., to BASF Aktiengesellschaft. Preparation of a catalyst carrier from alumina mixtures. 4,293,448, Cl. 252-463.000.
- LaVia, Anthony L.: See—
Pawelchak, John M.; Wang, Yu-Chang J.; and LaVia, Anthony L., 4,292,972, Cl. 128-296.000.
- Lawrence, C. Alexander: See—
Simpson, Roger J.; Gawthorpe, Janet A.; and Lawrence, C. Alexander, 4,293,307, Cl. 23-230.00B.
- Lawrence Security Services Ltd.: See—
Rogers, Groby W., 4,293,852, Cl. 340-568.000.
- Le, Trung, to International Business Machines Corporation. Transresonant deflection yoke operations. 4,293,802, Cl. 315-387.000.
- Lear Siegler, Inc.: See—
Pareja, Ramon, 4,292,990, Cl. 137-115.000.
- Learner, Richard C. M.: See—
Wheaton, John E. G.; Griffiths, David; and Learner, Richard C. M., 4,293,225, Cl. 356-417.000.
- LeBeault, Jean-Michel: See—
Christ, Charles; LeBeault, Jean-Michel; and Noel, Claude, 4,293,655, Cl. 435-316.000.
- LeBlanc, John R.: See—
Cohen, Saul M.; and LeBlanc, John R., 4,293,693, Cl. 544-221.000.
- Strazik, William F.; LeBlanc, John R.; and Santer, J. Owen, 4,293,461, Cl. 260-18.00N.
- Lechavelier, Hubert A.: See—
Drobot, Walter; and Lechavelier, Hubert A., 4,293,334, Cl. 75-101.0BE.
- Lechinger, Terry M.: See—
Borg, Paul E.; and Lechinger, Terry M., 4,292,772, Cl. 52-118.000.
- Le Coent, Jean-Louis: See—
Demoures, Bernard; and Le Coent, Jean-Louis, 4,293,431, Cl. 252-33.200.
- Ledebrink, Friedrich-Wilhelm; Stoll, Wolfgang; and Schafer, Dieter, to Alkem GmbH. Method of processing radioactive wastes. 4,293,438, Cl. 252-301.10W.
- LeDoux, Gilbert A.: See—
Yonkers, Edward H.; and LeDoux, Gilbert A., 4,293,234, Cl. 400-196.100.
- Lee, Benjamin Y. S.; Reed, Russell, Jr.; and Miller, Roger L., to United States of America, Navy. Degradable binder explosives. 4,293,352, Cl. 149-19.400.
- Lee, Chi-Long: See—
Homan, Gary R.; and Lee, Chi-Long, 4,293,676, Cl. 528-15.000.
- Lee, Hop. Coupling for an electric cable. 4,293,178, Cl. 339-103.00R.
- Lee, Marlow, to H & H Tube & Mfg. Co. Solar heat absorber for solar heat collectors. 4,292,958, Cl. 126-448.000.
- Lee, Richard J. Ammunition loader with improved charge bar. 4,292,877, Cl. 86-31.000.
- Lee, Thomas B.: See—
Cairns, Hugh; and Lee, Thomas B., 4,293,541, Cl. 424-45.000.
- Leeper, Charles G.; and Wood, John F., to Hennessy Industries, Inc. Tire changing apparatus. 4,293,020, Cl. 157-1.280.
- Leggett & Platt, Inc.: See—
Bustos, Rafael T., 4,293,062, Cl. 193-2.00D.
- Lehner, Daniel F.: See—
Bell, Ted A.; and Lehner, Daniel F., 4,293,140, Cl. 280-154.50R.
- Leindecker, Donald M.: See—
Cheng, William J.; Guthrie, David B.; and Leindecker, Donald M., 4,293,429, Cl. 252-18.000.
- Lemanski, Michael F.; Bremer, Noel J.; and Milberger, Ernest C., to Standard Oil Co. Preparation of maleic anhydride. 4,293,498, Cl. 260-346.750.
- Lensky, Albert: See—
Barrett, Edward E.; Hahn, Steven; Lensky, Albert; Pinczewski, Morris; and Sobelman, Seymour, 4,293,088, Cl. 227-131.000.
- Leo Pharmaceutical Products Ltd. A/S (Lovens Kemiske Fabrik Produktion-saktieselskab): See—
Rachlin, Schneur; and Arrigoni-Martelli, Edoardo, 4,293,549, Cl. 424-245.000.
- Lescrenier, Charles. Indicator for use with projected beam of radiation. 4,293,771, Cl. 250-491.000.
- Lescure, Jean-Pierre, to Syndicat National des Fabricants de Sucre de France. Anaerobic fermenter-decanter for the purification of residual water from sugar refineries, with recovery of combustible methane. 4,293,412, Cl. 210-179.000.
- Letica Corporation: See—
Letica, Ilija, 4,293,080, Cl. 220-306.000.
- Letica, Ilija, to Letica Corporation. Container construction. 4,293,080, Cl. 220-306.000.
- Levenson, Gerald I. P.: See—
Fyson, John R.; and Levenson, Gerald I. P., 4,293,638, Cl. 430-373.000.
- Levi Strauss & Co.: See—
Blessing, Hubert, 4,292,908, Cl. 112-306.000.
- Levine, David W.; Thilly, William G.; Wang, Daniel I. C.; and Wong, Jason S., to Massachusetts Institute of Technology. Cell culture microcarriers. 4,293,654, Cl. 435-241.000.
- Levit, Viktor M.: See—
Dunaevsky, Vladimir I.; Boidenko, Nikolai G.; Samarin, Alexei P.; Levit, Viktor M.; Zapara, Boris M.; Ivanov, Boris N.; Frolov, Sergei A.; Voronin, Rostislav A.; Belozarov, Nikolai P.; Momot, Valery I.; Stusenko, Jury A.; and Samoilov, Vladimir A., 4,293,101, Cl. 242-56.400.
- Levitt, George, to Du Pont de Nemours, E. I., and Company. Herbicidal N-(pyridinylaminocarbonyl)benzenesulfonamides. 4,293,330, Cl. 71-94.000.
- Levrai, Roland: See—
Riquart, Christian; and Levrai, Roland, 4,292,883, Cl. 91-29.000.
- Lewalter, Jürgen: See—
Rottmaier, Ludwig; Merten, Rudolf; Lewalter, Jürgen; Zecher, Wilfried; and Dunwald, Willi, 4,293,669, Cl. 525-452.000.
- Lewis, Bennie J.: See—
Haschke, Elliot M.; and Lewis, Bennie J., 4,293,347, Cl. 134-11.000.
- Lewis, Charles; and Birkenmeyer, Robert D., to Upjohn Company, The. Method of treating malaria. 4,293,547, Cl. 424-180.000.
- Lewis, David H.: See—
Coates, John P.; and Lewis, David H., 4,292,939, Cl. 123-335.000.
- Lewis, Herbert I.; McConnell, Anthony D.; and Price, William M., to Anglo-American Clays Corporation. Method for brightening natural calcitic ores. 4,293,097, Cl. 241-16.000.
- Lewis, Mack A.; and Spencer, Mike R., to Wilson Trailer Company. Gate with ramp device for livestock trailer with lift deck. 4,293,158, Cl. 296-24.00C.
- Lewis, William P.: See—
Hamilton, Peter W.; and Lewis, William P., 4,293,095, Cl. 239-35.000.
- Libbey-Owens-Ford Company: See—
Gills, Richard G.; Hille, Earl A.; Kleine, Albert W., Jr.; and Shamp, Donald E., 4,293,264, Cl. 414-38.000.

- Licentia Patent-Verwaltungs-G.m.b.H.: See—
Nestler, Johannes; and Wrede, Hans, 4,293,779, Cl. 307-252.00C.
- Liebig, Heinrich. Locking toggle bolt. 4,293,259, Cl. 411-32.000.
- Liebing, Alan P., to Ferranti Limited. Gyroscopic apparatus having three-axis inertial platform with rapid warm-up. 4,292,854, Cl. 74-5.340.
- Liedtke, Kurt: See—
Focke, Heinz; and Liedtke, Kurt, 4,293,068, Cl. 206-264.000.
- Lien, Larry A.: See—
Zollinger, J. Lamar; and Lien, Larry A., 4,293,606, Cl. 428-203.000.
- Liggett, James J. Electrolytic treatment of water. 4,293,400, Cl. 204-302.000.
- Lilly Industries Limited: See—
Jamieson, William B.; Ross, William J.; Simmonds, Robin G.; and Verge, John P., 4,293,563, Cl. 424-273.00R.
- Lin, Shih K.: See—
Teller, Aaron J.; Roy, Denis R. J.; and Lin, Shih K., 4,293,524, Cl. 422-169.000.
- Lindauer Dornier Gesellschaft mbH.: See—
Peter, Erich, 4,293,006, Cl. 139-102.000.
- Lindberg, Ulf W.: See—
Millgard, Ulf J.; Lindberg, Ulf W.; Annelod, Weimar A.; Werner, Nils H.; and Wemlius, Bjorn, 4,293,607, Cl. 428-212.000.
- Lindblad, Nero R.; Rezanka, Ivan; and Cassidy, John V., to Xerox Corporation. Magnetic brush apparatus. 4,292,924, Cl. 118-658.000.
- Linde Aktiengesellschaft: See—
Nasser, Gamal E. D., 4,293,033, Cl. 165-166.000.
- Linder, Uno K. E., to U.S. Philips Corporation. Bearing for the printing head of a matrix printer, and printing head comprising such a bearing. 4,293,232, Cl. 400-124.000.
- Lindlof, Martti. Electrical connection. 4,293,176, Cl. 339-98.000.
- Lindsay, John. Roller chock. 4,292,911, Cl. 114-218.000.
- Lindstrom, Robert: See—
Allen, Robert J.; Lindstrom, Robert; and Juda, Walter, 4,293,396, Cl. 204-106.000.
- Lingaraju, Bhartoor, to Square D Company. Case for electrical multiple outlet. 4,293,172, Cl. 339-14.00P.
- Link, John R., to General Signal Corporation. Gear pump with improved shaft seal. 4,293,291, Cl. 418-104.000.
- Linn, Orville J. Straw and chaff chopper and spreader. 4,292,795, Cl. 56-503.000.
- Lipert, Peter, to Atara Corporation. Liquid circulating device. 4,293,506, Cl. 261-77.000.
- Lipshild, Eugene C., to Orscheln Brake Lever Mfg. Co. Brake cable operating means of the overcenter toggle type. 4,292,858, Cl. 74-501.00R.
- Liquid Paper Corporation: See—
Sharlow, Roger C., 4,293,100, Cl. 242-55.000.
- Liu, Chung-hong R.; Nayak, Jnaneshwar H.; Stenberg, Herbjorn; Huerta, Felipe J.; and Hall, Woodrow A., to Liu, Chung-hong R. Tool holder for varying tool rake angle. 4,292,865, Cl. 82-36.00R.
- Livesey-Goldblatt, Eric, to Livesey-Goldblatt, Eric. Recovery of gold and uranium from calcines. 4,293,330, Cl. 423-18.000.
- Locker, Jan A. K., to Machinefabriek A. Wijnveen B.V.; and Coöperatieve Landbouw aan- en verkoopcombinatie, B.A. "C.L.C.". Sieve device for separating a mixture of particulate material in components of different sizes. 4,293,407, Cl. 209-253.000.
- Loeffler, Earl F.; and Weyand, Harley P., Jr., to Firestone Tire & Rubber Company, The. Method and apparatus for accurately positioning a bead bundle. 4,293,358, Cl. 156-131.000.
- Loffelman, Frank F.: See—
Hardy, William B.; and Loffelman, Frank F., 4,293,467, Cl. 260-45.80N.
- Loft, Fredrick A.; and Peterson, John O. H., to Scott Paper Company. Coated sheet material for use in making decorative laminates. 4,293,360, Cl. 156-230.000.
- Logitek Electronic Systems, Inc.: See—
Hochberg, Lindsey S.; and Borland, Montague C., 4,293,823, Cl. 330-260.000.
- Logue, Jay: See—
Coleman, William J.; and Logue, Jay, 4,293,122, Cl. 256-69.000.
- Lohmiller, Edward W. Energy converter. 4,292,808, Cl. 60-673.000.
- Lomitzer, Abraham: See—
Hill, David A.; and Lomitzer, Abraham, 4,293,072, Cl. 206-512.000.
- Long, Howard W.; and Flowers, Robert L., to Coronet Foods, Inc. Chopped leafy vegetable packaging machine. 4,292,786, Cl. 53-434.000.
- Long, Lennart E.; and Wiseman, Robert L., to United States of America, Transportation. Rail car identification apparatus. 4,293,766, Cl. 235-462.000.
- Lopez, Bennie F.; Campbell, Billy H.; Collier, Bobby D.; Laird, William J.; Debona, Edward J.; and Eubanks, James E., Jr., to United States of America, Army. Quadrant elevation control device. 4,292,880, Cl. 89-1.815.
- Lord Corporation: See—
Koeman, James B., 4,292,694, Cl. 3-1.910.
- Koeman, James B., 4,292,695, Cl. 3-1.910.
- Zalucha, Denis J.; Sexsmith, Frederick H.; Hornaman, Ernest C.; and Dawdy, Terrance H., 4,293,665, Cl. 525-255.000.
- L'Oreal: See—
Lang, Gerard; and Forestier, Serge, 4,293,542, Cl. 424-47.000.
- Lorenz, Donald H.: See—
Gruber, Bruce A.; and Lorenz, Donald H., 4,293,714, Cl. 564-249.000.
- Lorenz, Kurt; Dungs, Horst; Koenigs, Hans B.; and Kurtz, Roman, to Carl Still GmbH & Co. KG, Firma. Apparatus for producing abrasion-proof coke forms from bituminous coal, brown coal or peat briquets. 4,293,388, Cl. 202-126.000.
- Loucks, Terry L., to Mead Corporation. The. Controlled temperature shipping assembly. 4,292,817, Cl. 62-457.000.
- Lowe, Earl L., to Ball Corporation. Electronic valve assembly for glassware forming machinery. 4,293,004, Cl. 137-884.000.
- Lu, Chin H., to Xerox Corporation. Electrographic toner compositions. 4,293,631, Cl. 430-106.000.
- Lucas Industries Limited: See—
Knowles, Richard P., 4,292,934, Cl. 123-145.00A.
- Lucas, James H., to Allis-Chalmers Corporation. Detent mechanism and transmission speed range selector valve. 4,293,059, Cl. 192-3.570.
- Lucas, James M.; Enright, Dorothy P.; and Perricone, Alphonse C., to Milchem Incorporated. Drilling fluid containing a copolymer filtration control agent. 4,293,427, Cl. 252-8.50C.
- Lucchini, Joseph: See—
Tishler, Albert; Tishler, Murray; Tishler, William; Tishler, Irving; and Lucchesi, Joseph, 4,292,834, Cl. 72-482.000.
- Lucchesi, Charles E.; and Brown, Timothy E., to Sierra Misco, Inc. Temperature-compensated precipitation gauge. 4,292,843, Cl. 73-171.000.
- Luck, Klaus; and Poeppel, Fritz-Otto, to Preussag Aktiengesellschaft. Hydraulically operated hoisting apparatus for a ship for picking floating objects up out of the sea. 4,293,265, Cl. 414-140.000.
- Lucksinger, James E.: See—
Beynet, Pierre A.; Lucksinger, James E.; and Jansen, Martin B., Jr., 4,293,146, Cl. 285-24.000.
- Ludwig, Nelson H.; and Ose, Earl E., to Eli Lilly and Company. Controlled release formulations and method of treatment. 4,293,539, Cl. 424-19.000.
- Lueder, Rainer, to Siemens Aktiengesellschaft. Monolithically integrated charge transfer circuit. 4,293,831, Cl. 333-165.000.
- Luhleisch, Hartmut; Pflaum, Peter; Dias, Francisco J.; Nauomidis, Aristides; Schirbach, Arno; and Nickel, Hubertus, to Kernforschungsanlage Jülich GmbH. Making temperature-stable protectively coated graphite molded body. 4,293,512, Cl. 264-58.000.
- Lukaszewski, Charles. Bat-like, bubble-blowing device. 4,292,754, Cl. 46-6.000.
- Lumention Limited: See—
Coates, John P.; and Lewis, David H., 4,292,939, Cl. 123-335.000.
- Lundmark, Lorentz, to Skega Aktiebolag. Barking drum. 4,293,014, Cl. 144-208.00B.
- Lundren, Jan, to ASEA Aktiebolag. Method for containing spent nuclear fuel rods in a protective container to facilitate disposal. 4,293,773, Cl. 250-506.000.
- Lunel, Jean: See—
Florent, Jean; Lunel, Jean; and Mancy, Denise, 4,293,650, Cl. 435-119.000.
- Lurssen, Klaus: See—
Beck, Gunther; Heitzer, Helmut; and Lurssen, Klaus, 4,293,331, Cl. 71-118.000.
- Lussier, Claude. Dispensing container with ingredient level indicia. 4,293,084, Cl. 222-158.000.
- Lustig, Stanley; and Vick, Stephen J., to Union Carbide Corporation. Cook-in film containing a blend of ionomer and elastomer. 4,293,664, Cl. 525-196.000.
- Lutz, Alfons, to Webasto-Werk W. Baier GmbH & Co. Vehicle roof. 4,293,161, Cl. 296-213.000.
- Lutze, Hans; Weissappel, Helmut; Klie, Wolfgang; and Weidemann, Dieter, to Daimler-Benz Aktiengesellschaft. Side guard for motor vehicle. 4,293,160, Cl. 296-188.000.
- Lykes Bros. Steamship Co., Inc.: See—
Nemec, Frank A.; and Pearson, Raymond, 4,292,915, Cl. 114-260.000.
- Lykes, Robert E., to A. O. Smith Corporation. Flexible motor mounting. 4,293,114, Cl. 248-604.000.
- Lyle, John S. Bearingless vibrator. 4,293,231, Cl. 366-120.000.
- Lyon, Colin E.: See—
Sutcliffe, Peter W.; Isaacs, Jim W.; Nelson, Robert L.; Lyon, Colin E.; and Stringer, Brian, 4,293,507, Cl. 264-0.500.
- Lyons, Michael D.: See—
Olson, Paul E.; and Lyons, Michael D., 4,293,118, Cl. 251-297.000.
- Lytle, Thomas G., to TLB Plastics Corporation. Hinged closure. 4,293,079, Cl. 220-306.000.
- M. P. H. Industries, Inc.: See—
Sergent, Edward W., 4,293,859, Cl. 343-702.000.
- Maag, Willi; Baumgartner, Hans U.; Vollenweider, Max; and Wolf, Hans J., to Kistler Instrumente AG. Balancing and monitoring apparatus. 4,292,769, Cl. 51-169.000.
- MacDonald, Milton. Unitary combined backer and siding board. 4,292,776, Cl. 52-394.000.
- Machinefabriek A. Wijnveen B.V.: See—
Locker, Jan A. K., 4,293,407, Cl. 209-253.000.
- MacMillan, John H.: See—
Labs, Mortimer M.; and MacMillan, John H., 4,293,193, Cl. 350-350.00R.
- MacMillan, Kenneth T., to Donald MacMillan & Son, Inc. Tire retreading bladder. 4,293,293, Cl. 425-23.000.
- Macovski, Albert. Solid state color television camera with multiple line readout. 4,293,871, Cl. 358-44.000.
- Mader, Helmut: See—
Hupp, Gerhard; and Mader, Helmut, 4,292,881, Cl. 89-33.00A.
- Maeda, Kazuo: See—
Inaba, Hideya; Nagai, Kenichi; Ichiki, Masayoshi; Kamino, Yasumi; and Maeda, Kazuo, 4,293,447, Cl. 252-461.000.

- Maeda, Mamoru: See—
Takagi, Mikio; Maeda, Mamoru; and Kamioka, Hajime, 4,293,589, Cl. 427-93.000.
Takagi, Mikio; Maeda, Mamoru; and Kamioka, Hajime, 4,293,590, Cl. 427-93.000.
Maeda, Takeshi: See—
Izumita, Morishi; Maeda, Takeshi; Tsunoda, Yoshito; and Sawano, Susumu, 4,293,944, Cl. 369-45.000.
Maendel, Carl: See—
Meier, Daniel; and Maendel, Carl, 4,292,933, Cl. 122-114.000.
Magnolato, Daniele: See—
Farr, David R.; and Magnolato, Daniele, 4,293,583, Cl. 426-657.000.
Mahle, Christoph: See—
Atia, Ali E. E.; Berman, Arnold L.; and Mahle, Christoph, 4,293,945, Cl. 370-17.000.
Mahood, William L.: See—
Inglefield, Joseph T., Jr.; and Mahood, William L., 4,292,979, Cl. 128-743.000.
Maio, Kenji: See—
Shibayama, Akinori; Maio, Kenji; and Yokozawa, Norio, 4,293,819, Cl. 330-9.000.
Maiocchi, Luigi, to Industrie Pirelli S.p.A. Breaker for radial tire, 4,293,019, Cl. 152-361.00R.
Mair, William J., to Plastic Recycling Limited. Manufacture of plastics products, 4,293,515, Cl. 264-120.000.
Mairle, Hans, to Dr. Ing. h.c.F. Porsche Aktiengesellschaft. Window mounting for automotive vehicles, 4,292,774, Cl. 52-208.000.
Makino, Kazuhiro, to Hitachi, Ltd. Container handling apparatus, 4,293,077, Cl. 212-219.000.
Malik, Edward P., to Buffalo Color Corporation. Liquid anhydride blends, 4,293,681, Cl. 528-115.000.
Maly, Hans-Peter: See—
Heitmann, Jürgen; Maly, Hans-Peter; and Wilhelm, Rudolf, 4,293,879, Cl. 360-10.000.
Mancy, Denise: See—
Florent, Jean; Lunel, Jean; and Mancy, Denise, 4,293,650, Cl. 435-119.000.
Mankel, Siegfried: See—
Sick, Erwin; and Mankel, Siegfried, 4,293,776, Cl. 250-572.000.
Mannesmann Demag AG: See—
Feuerstake, Ewald; and Schwarz, Klaus, 4,293,775, Cl. 250-535.000.
Manten Co., Ltd.: See—
Ida, Minoru, 4,293,144, Cl. 280-644.000.
Manufacture de Produits Chimiques Protex: See—
Joseph, Christian M., 4,293,344, Cl. 106-111.000.
Manzel, Ernest V. Connectors for electrical cables, 4,293,151, Cl. 285-161.000.
Mapal Fabrik für Präzisionswerkzeuge: See—
Kress, Dieter; and Haberle, Friedrich, 4,293,252, Cl. 408-224.000.
Marchioro, Ignazio, to Escher Wyss Limited. Controlled deflection roll, 4,292,716, Cl. 29-116.00AD.
Maresca, Louis M.: See—
Robeson, Lloyd M.; Matzner, Markus; and Maresca, Louis M., 4,293,670, Cl. 525-436.000.
Marin, Heiner, to Siemens Aktiengesellschaft. Electric gas blast circuit breaker, 4,293,750, Cl. 200-148.00A.
Marincic, Nikola; and Epstein, James, to Battery Engineering, Inc. Step cell, 4,293,622, Cl. 429-50.000.
Mark Twain Marine Industries, Inc.: See—
Siebert, Lee S.; and Ritsch, Charles J., 4,292,913, Cl. 114-219.000.
Markel, Raymond A. Sleeping bag liner, 4,292,700, Cl. 5-413.000.
Markin, Valentin G.: See—
Kopylov, Alexei A.; Kuzmenko, Valentin T.; Stepanov, Alexandr N.; Gaschenko, Viktor P.; Kaznachevsky, Nikolai A.; Nosovitsky, Alexandr Y.; Misikov, Ivan I.; Shapiro, Alexandr I.; Skakunov, Ivan G.; Markin, Valentin G.; Konstantinov, Alexei K.; Abramian, Eduard S.; Soroka, Arseny M.; and Zinchenko, Yakov A., 4,292,928, Cl. 119-17.000.
Markovics, Michael, to Evered Tool Company. Countersinking tool with removable cutting inserts, 4,293,254, Cl. 408-229.000.
Markusch, Peter: See—
Dieterich, Dieter; and Markusch, Peter, 4,293,474, Cl. 260-29.2TN.
Marquette Metal Products Co.: See—
Anderson, J. Edward C., 4,293,044, Cl. 173-93.500.
Marshall, Robert M.; and Dardoufas, Kimon C., to Allied Chemical Corporation. Polyamide yarn spin finish containing a rearranged glyceride and oxidized polyethylene, 4,293,460, Cl. 260-18.0PF.
Martin, Eugene R., to SWS Silicones Corporation. Silicone polyether copolymers, 4,293,611, Cl. 428-266.000.
Martin Industries, Inc.: See—
Wilhoite, Murray O., 4,292,954, Cl. 126-290.000.
Martin Marietta Corporation: See—
Smith, Winthrop W., Jr., 4,293,921, Cl. 364-726.000.
Martin, Ralph D.; Dunnivant, William R.; Sturtz, Gregory P.; and Langer, Heimo J., to Ashland Oil, Inc. Urethane binder compositions for no-bake and cold box foundry application utilizing isocyanato-urethane polymers, 4,293,480, Cl. 260-38.000.
Marumoto, Ryuji: See—
Sawa, Yoichi; Kawakami, Yoshiyuki; and Marumoto, Ryuji, 4,293,690, Cl. 536-24.000.
Maruyama, Shigeo: See—
Kohayakawa, Yoshimi; Ishikawa, Yasuyuki; and Maruyama, Shigeo, 4,293,198, Cl. 351-13.000.
- Marvin Glass & Associates: See—
Jaworski, Eugene; and Breslow, Jeffrey D., 4,292,756, Cl. 46-72.000.
Kuna, Wayne A.; Thibault, James G.; and Schoenfeld, Palmer J., 4,292,758, Cl. 46-93.000.
Marx, Matthias: See—
Nissen, Dietmar; Marx, Matthias; Jarre, Wolfgang; Schoen, Ernst; and Decker, Walter, 4,293,657, Cl. 521-121.000.
Maryland Cup Corporation: See—
Rubenstein, Irving H., 4,293,580, Cl. 426-565.000.
Masaki, Kenji, to Nissan Motor Company, Limited. Air-fuel ratio control system, 4,292,946, Cl. 123-440.000.
Maschinenfabrik Schweiter AG: See—
Werffeli, Hermann, 4,292,868, Cl. 83-13.000.
Maschonat, Guenter: See—
Boer, Werner; Lachner, Hans; Maschonat, Guenter; Richter, Joerg; Schulte, Heinrich; and Warnke, Hans, 4,293,246, Cl. 405-291.000.
Mase, Akira: See—
Muto, Katsuya; Mori, Kazumasa; Mase, Akira; Nimura, Takayasu; Itoh, Katsumi; and Akita, Yoshio, 4,293,811, Cl. 322-60.000.
Maslanka, William W.; and Spence, Gavin G., to Hercules Incorporated. Organic pigments, 4,293,666, Cl. 525-284.000.
Maslanka, William W.; and Spence, Gavin G., to Hercules Incorporated. Organic pigments, 4,293,667, Cl. 525-284.000.
Mason, Paul C., to Lanier Business Products, Inc. System for priority transcribing of dictation, 4,293,881, Cl. 360-60.000.
Masoneilan International, Inc.: See—
Wing, Paul, 4,292,991, Cl. 137-329.050.
Massachusetts Institute of Technology: See—
Kleppner, Daniel, 4,293,769, Cl. 250-338.000.
Levine, David W.; Thilly, William G.; Wang, Daniel I. C.; and Wong, Jason S., 4,293,654, Cl. 435-241.000.
Patil, Suhas S., 4,293,783, Cl. 307-465.000.
Masu, Masanobu: See—
Sugio, Akitoshi; Masu, Masanobu; Nakai, Hiroshi; and Sasaki, Yukio, 4,293,478, Cl. 260-37.00R.
Sugio, Akitoshi; Masu, Masanobu; and Matunaga, Masatugu, 4,293,660, Cl. 525-68.000.
Masunaga, Makoto: See—
Tsunekawa, Tokuchi; Masunaga, Makoto; Hosoe, Kazuya; Niwa, Yukichi; Owada, Mitsutoshi; and Asano, Noriyuki, 4,293,877, Cl. 358-213.000.
Mathews, Bernard C. Spring wire blades for drum type mowers, 4,292,789, Cl. 56-12.700.
Mathews, Bernard C. Blade arrangement for multiple rotor mowers, 4,292,790, Cl. 56-13.600.
Matsuda, Takehiko; and Izawa, Kyoichi, to Toyostar Corporation. Capacitance type contact switch, 4,293,745, Cl. 200-52.00R.
Matsueda, Shinji, to Nippon Light Metal Co., Ltd. Liquid dispensing stand with cooling support, 4,293,082, Cl. 222-131.000.
Matsui, Kiyoshi; Arai, Katsuyuki; and Shinbashi, Sueo, to Fujitsu Limited. Natural air cooled rack for vertically disposed printed boards, 4,293,891, Cl. 361-383.000.
Matsumoto, Hiromitsu; Sugiyama, Keiichi; and Uchiyama, Kazuo, to Yamaha Hatsukoki Kabushiki Kaisha. Intake control system for internal combustion engine, 4,292,944, Cl. 123-432.000.
Matsumoto, Manabu: See—
Kobayashi, Nariyoshi; Sakamoto, Takeshi; Anzai, Shunichi; and Matsumoto, Manabu, 4,293,275, Cl. 416-97.00R.
Matsumura, Ko; Nakamura, Hiroto; and Irie, Toshio, to Kawasaki Steel Corporation. Cold rolled non-oriented electrical steel sheet, 4,293,336, Cl. 75-124.000.
Matsushita Electric Industrial Co., Ltd.: See—
Hatada, Kenzo; and Kajiura, Takao, 4,293,637, Cl. 430-314.000.
Noguchi, Satoshi; and Kitao, Takaya, 4,293,940, Cl. 368-75.000.
Matsushita Electric Works, Ltd.: See—
Kanada, Hiroshi, 4,293,753, Cl. 200-315.000.
Mattox, Douglas M.: See—
Yoldas, Bulent E.; and Mattox, Douglas M., 4,293,594, Cl. 427-107.000.
Mattsson, Bengt. Dental absorptive pads and dispensing means therefor, 4,293,301, Cl. 433-136.000.
Matunaga, Masatugu: See—
Sugio, Akitoshi; Masu, Masanobu; and Matunaga, Masatugu, 4,293,660, Cl. 525-68.000.
Matusz, Zbigniew, to Fabryka Obrabiarek Precyzyjnych "Ponar-Pruszkow" Zaklad "i Maja". Cylindrical gear with helical tooth wheels, 4,292,857, Cl. 74-466.000.
Matzner, Markus: See—
Robeson, Lloyd M.; Matzner, Markus; and Maresca, Louis M., 4,293,670, Cl. 525-436.000.
Maurer, Barbara V.: See—
Haugwitz, Rudiger D.; Wade, Peter C.; and Maurer, Barbara V., 4,293,569, Cl. 424-300.000.
Mausser-Werke Obendorf GmbH: See—
Hupp, Gerhard; and Mader, Helmut, 4,292,881, Cl. 89-33.0CA.
Maxner, Richard B., to USM Corporation. Automatic insertion equipment, 4,292,727, Cl. 29-566.300.
Mayo, Terry H.; and Parrish, John D., to Reed Tool Company. Rolling cutter drill bit with improved journal configuration, 4,293,167, Cl. 308-8.200.
Mazanek, Jan; and Nuller, Hanns P., to Bayer Aktiengesellschaft. Process for the production of diisocyanato toluene mixtures having an increased content of 2,6-diisocyanato toluene, and the use thereof as synthesis components in the production of polyurethane elastomers, 4,293,680, Cl. 528-67.000.

- Mazzola, Mario, to Richardson-Vicks Inc. Locking valve apparatus, 4,292,995, Cl. 137-384.200.
McAdams, Hugh P., to Texas Instruments Incorporated. Refresh operations for semiconductor memory, 4,293,932, Cl. 365-222.000.
McAleer, William J.; Hurni, William M.; and Miller, William J., to Merck & Co. Inc. Assay for hepatitis A antigen, 4,293,538, Cl. 424-1.000.
McAllister, Gary L.; and Draggoo, V. G., to Jersey Nuclear-Avco Isotopes, Inc. Multiwavelength dye laser, 4,293,827, Cl. 331-94.5ML.
McCarty, Daniel A. Waterproof signal light, 4,293,847, Cl. 340-332.000.
McCarty, Vincent D., to International Business Machines Corporation. Print hammer drive circuit with compensation for voltage variation, 4,293,888, Cl. 361-152.000.
McConnell, Anthony D.: See—
Lewis, Herbert I.; McConnell, Anthony D.; and Price, William M., 4,293,097, Cl. 241-16.000.
McCormick, James T.; Ferry, Paul B.; and Hall, John C., to United States of America, Energy. Brazing method, 4,293,089, Cl. 228-215.000.
McCrea, Donald H.: See—
Field, Joseph H.; and McCrea, Donald H., 4,293,531, Cl. 423-232.000.
McDonald, Charles B. Fireplace furnace, 4,292,952, Cl. 126-121.000.
McFadyen, Robert J., to General Electric Company. Gated AGC amplifier with dc feedback, 4,293,822, Cl. 330-254.000.
McGillis, Hugh D., to McGillis, Hugh D. Supplemental heating system, 4,293,094, Cl. 237-55.000.
McGough, Bonnie. Insulated beverage cozy, 4,293,015, Cl. 150-52.00R.
McGraw-Edison Company: See—
Date, K. Henry; and Wainio, Ronald, 4,293,834, Cl. 335-76.000.
Kristofek, Paul J., 4,293,895, Cl. 362-147.000.
McKewan, Arthur J., to Microdot Inc. Self drilling blind rivet, 4,293,258, Cl. 411-30.000.
McLaughlin, Homer C.: See—
Elphinstone, Eugene A.; McLaughlin, Homer C.; and Smith, Charles W., 4,293,440, Cl. 252-317.000.
McMahon, Donald H., to Sperry Corporation. Fiber optic small displacement sensor, 4,293,188, Cl. 350-96.290.
McMorrow, Clyde H. Traffic light dimming technique and circuitry, 4,293,796, Cl. 315-205.000.
McMullan, James P. Electrically insulated resistance heater, 4,293,763, Cl. 219-528.000.
Mead Corporation, The: See—
Davis, James W.; and Paranjpe, Suresh C., 4,293,863, Cl. 346-75.000.
Loucks, Terry L., 4,292,817, Cl. 62-457.000.
Meares, Harry E., Jr., to Klements, Walter S. Shower dispenser, 4,293,083, Cl. 222-133.000.
Measurix Corporation: See—
Larsen, Tor G., 4,292,838, Cl. 73-37.700.
Meier, Daniel; and Maendel, Carl, to Hutterian Society of Brothers. Furnace, 4,292,933, Cl. 122-114.000.
Meinhardt, Frederick: See—
Sommer, Klaus; Klemm, Walter; Weber, Hermann; Meinhardt, Frederick; Schonmann, Gerhard; and Spatz, Wilhelm, 4,293,526, Cl. 422-205.000.
Mendiratta, Sudhir K., to Olin Corporation. Process for the purification of alkaline solution of lower alkyl alcohols containing alkali metal alkoxides, 4,293,721, Cl. 568-916.000.
Menown, Hugh, to English Electric Valve Company. Double-ended thyatron having at least three grids, 4,293,800, Cl. 315-350.000.
Mensik, John A. Filter cartridge assembly, 4,292,983, Cl. 131-187.000.
Merck & Co., Inc.: See—
Bolhofer, William A., 4,293,703, Cl. 548-337.000.
Christensen, Burton G.; and DiNinno, Frank P., 4,293,555, Cl. 424-263.000.
McAleer, William J.; Hurni, William M.; and Miller, William J., 4,293,538, Cl. 424-1.000.
Willard, Alvin K., 4,293,496, Cl. 260-343.500.
Mericle, John E. Guide plate for wood working tools, 4,292,870, Cl. 83-471.200.
Merjan, Stanley. Piles, 4,293,242, Cl. 405-239.000.
Merki, Emil: See—
Baur, Rudolf; Merki, Emil; and Krahenbuhl, Hanspeter, 4,293,424, Cl. 210-737.000.
Merola, Pasquale A. Two-dimensional transform processor, 4,293,920, Cl. 364-725.000.
Merrell Dow Pharmaceuticals Inc.: See—
Metcalfe, Brian W.; and Johnston, J. O'Neal, 4,293,548, Cl. 424-242.000.
Merrifield, Robert B.; and Wong, Tai W., to Rockefeller University. N⁶-Desacetylthymosin α and process, 4,293,455, Cl. 260-8.000.
Merten, Rudolf: See—
Rottmaier, Ludwig; Merten, Rudolf; Lewalter, Jürgen; Zecher, Wilfried; and Dunwald, Willi, 4,293,669, Cl. 525-452.000.
Merz, Herbert; and Stockhaus, Klaus, to Boehringer Ingelheim GmbH. Analgesic 2-(2-alkoxy-ethyl)-2'-hydroxy-6,7-benzomorphans and salts thereof, 4,293,556, Cl. 424-267.000.
Messerschmitt-Boelkow-Blohm Gesellschaft mit beschränkter Haftung: See—
Schweig, Helmut; and von Bassewitz, Henning, 4,293,731, Cl. 136-245.000.
Messier, Francis L.: See—
Kirk, Calvin K.; Joyce, Glover C.; and Messier, Francis L., 4,292,766, Cl. 51-105.0SP.
- Messing, Gary L.: See—
Hassler, Craig R.; and Messing, Gary L., 4,293,302, Cl. 433-173.000.
Metcalfe, Brian W.; and Johnston, J. O'Neal, to Merrell Dow Pharmaceuticals Inc. 18-Substituted pregn-4-ene-3,20-diones, 4,293,548, Cl. 424-242.000.
Metcalfe, Ronald S.; and Greig, John M., to RM Fabrications Limited; and British Gas Corporation. Method and apparatus for securing a pipe to a fitting, 4,293,147, Cl. 285-39.000.
Metz, Fred L., to Diamond Shamrock Corporation. Composition and process for stabilizing soil, 4,293,340, Cl. 106-74.000.
Metzler, Robert W.: See—
Fogg, Lewis W.; Metzler, Robert W.; Satterfield, H. Eugene; and Scott, Eion G., 4,292,762, Cl. 47-17.000.
Micafil AG: See—
Nabholz, Hans U., 4,292,744, Cl. 34-73.000.
Michael Forrest, Inc.: See—
Forrest, Michael R.; and Kohn, Alfred, 4,292,690, Cl. 2-65.000.
Forrest, Michael R.; and Kohn, Alfred, 4,292,691, Cl. 2-65.000.
Michel, Eberhard: See—
Harand, Elmar; and Michel, Eberhard, 4,293,386, Cl. 376-461.000.
Michel, Karl H.: See—
Hoehn, Marvin M.; and Michel, Karl H., 4,293,649, Cl. 435-118.000.
Micro-Circuits Company: See—
Bradley, Robert F.; and Bradley, Lindell P., 4,292,916, Cl. 116-205.000.
Microdot Inc.: See—
McKewan, Arthur J., 4,293,258, Cl. 411-30.000.
Midcon Pipeline Equipment Co.: See—
Slavens, Clyde M.; Clavin, Edward A.; and Alleman, James E., 4,293,758, Cl. 219-125.120.
Middleton, Wilbur D.; and Paulson, John A., to Boeing Company, The. Leading edge vortex flap for wings, 4,293,110, Cl. 244-199.000.
Miesel, John L., to Eli Lilly and Company. Novel 1-(mono-o-substituted benzoyl)-3-(substituted pyrazinyl) ureas, 4,293,552, Cl. 424-250.000.
Mikami, Yasuo; Kanda, Hiroshi; and Uno, Akio, to Nisshin Oil Mills, Ltd., The. Process for preparing mayonnaise-like foods, 4,293,574, Cl. 426-46.000.
Miki, Minoru: See—
Ohsumi, Katsumi; and Miki, Minoru, 4,293,382, Cl. 376-308.000.
Milberger, Ernest C.: See—
Lemanski, Michael F.; Bremer, Noel J.; and Milberger, Ernest C., 4,293,498, Cl. 260-346.750.
Milberger, Lionel J., to FMC Corporation. Pile connector, 4,293,148, Cl. 285-90.000.
Milchem Incorporated: See—
Lucas, James M.; Enright, Dorothy P.; and Perricone, Alphonse C., 4,293,427, Cl. 252-8.50C.
Miller, Betty J. Clamp stand for needlework frames, 4,292,748, Cl. 38-102.000.
Miller, Casper W.: See—
George, Robert W.; Miller, Casper W.; and Rapey, Kenneth, 4,293,510, Cl. 264-40.700.
Miller, Donald L., to Facet Enterprises, Inc. Electromagnetic friction clutch with overload release, 4,293,060, Cl. 192-56.00R.
Miller, Robert C.: See—
Bradley, John J.; Holtey, Thomas O.; Miller, Robert C.; Miu, Ming T.; Shen, Jian-Kuo; and Staplin, Theodore R., Jr., 4,293,908, Cl. 364-200.000.
Miller, Roger L.: See—
Lee, Benjamin Y. S.; Reed, Russell, Jr.; and Miller, Roger L., 4,293,352, Cl. 149-19.400.
Miller, Sylvester T., to STM Corporation. Method of obtaining and recording seismic and geochemical data, 4,293,309, Cl. 23-230.0EP.
Miller, William J.: See—
McAleer, William J.; Hurni, William M.; and Miller, William J., 4,293,538, Cl. 424-1.000.
Millgardh, Ulf J.; Lindberg, Ulf W.; Anneslod, Weimar A.; Werner, Nils H.; and Wemelin, Bjorn, to Orebro Pappersbruks AB. Flexible sheet covering material for wrapping heat, cold and sound insulation, 4,293,607, Cl. 428-212.000.
Milliken Research Corporation: See—
Kluger, Edward W.; and Su, Tien-Kuei, 4,293,682, Cl. 528-123.000.
Millouet, Jean: See—
Gros, Pierre; Millouet, Jean; and Staron, Philippe, 4,293,935, Cl. 367-43.000.
Mima, Hiroshi, to Murata Kikai Kabushiki Kaisha. Pneumatic yarn splicing apparatus, 4,292,796, Cl. 57-22.000.
Minagawa, Motonobu; Nakahara, Yutaka; and Haruna, Tohru. Stabilized synthetic resin composition, 4,293,472, Cl. 260-23.0XA.
Minai, Kiichi: See—
Adachi, Hideo; Minai, Kiichi; Moriyasu, Kozo; and Imagawa, Shunjiro, 4,293,768, Cl. 250-338.000.
Minami, Setsuo: See—
Minoura, Kazuo; Sugiyama, Muneharu; Minami, Setsuo; and Sato, Tadashi, 4,293,184, Cl. 350-6.300.
Ministry of International Trade & Industry: See—
Ebata, Yoshihiro; Toibana, Yasuo; Uetsuki, Tsuneo; Kose, Saburo; and Kinoshita, Makoto, 4,293,356, Cl. 156-89.000.
Mink, George. Material handling device, 4,293,268, Cl. 414-591.000.
Minnesota Mining and Manufacturing Company: See—
Blachunis, Robert J.; and Bany, Stephen W., 4,293,675, Cl. 528-14.000.
Campbell, Douglas D., 4,293,604, Cl. 428-90.000.
Moris, Alfred H., 4,293,882, Cl. 360-93.000.
Myers, Joseph F., 4,293,625, Cl. 430-9.000.

- Newell, Richard G.; and Perry, Dale C., 4,293,441, Cl. 252-389.00A.
- Niles, Gerald J.; and Ritter, Norman C., 4,293,102, Cl. 242-71.800.
- Stivers, David A., 4,293,663, Cl. 525-187.000.
- Zollinger, J. Lamar; and Lien, Larry A., 4,293,606, Cl. 428-203.000.
- Minolta Camera Kabushiki Kaisha: See—
- Yamazaki, Yasuo; and Egawa, Takeshi, 4,293,185, Cl. 350-18.000.
- Minoura, Kazuo; Sugiura, Muneharu; Minami, Seisuo; and Sato, Tadashi, to Canon Kabushiki Kaisha. Scanning projection device. 4,293,184, Cl. 350-6.300.
- Minrad Corporation: See—
- Weinberg, Norman L., 4,293,640, Cl. 430-421.000.
- Mishell, Daniel R., Jr.: See—
- Nash, Harold A.; and Mishell, Daniel R., Jr., 4,292,965, Cl. 128-260.000.
- Misikov, Ivan I.: See—
- Kopylov, Alexei A.; Kuzmenko, Valentin T.; Stepanov, Alexandr N.; Gaschenko, Viktor P.; Kaznachevsky, Nikolai A.; Nosovitsky, Alexandr Y.; Misikov, Ivan I.; Shapiro, Alexandr I.; Skakunov, Ivan G.; Markin, Valentin G.; Konstantinov, Alexei K.; Abramian, Eduard S.; Soroka, Arseny M.; and Zinchenko, Yakov A., 4,292,928, Cl. 119-17.000.
- Missout, Gilles: See—
- Belanger, Guy; and Missout, Gilles, 4,293,399, Cl. 204-195.00P.
- Mitel Corporation: See—
- Cepelinski, Jacob, 4,293,737, Cl. 179-17.00E.
- Mitomi, Seiji: See—
- Kojima, Masaharu; and Mitomi, Seiji, 4,293,260, Cl. 411-44.000.
- Mitsubishi Denki Kabushiki Kaisha: See—
- Watanabe, Eiki, 4,293,889, Cl. 361-212.000.
- Mitsubishi Gas Chemical Co., Inc.: See—
- Sugio, Akitoshi; Masu, Masanobu; Nakai, Hiroshi; and Sasaki, Yukio, 4,293,478, Cl. 260-37.00R.
- Sugio, Akitoshi; Masu, Masanobu; and Matunaga, Masatugu, 4,293,660, Cl. 525-68.000.
- Mitsui Petrochemical Industries, Ltd.: See—
- Iwaki, Tetsuo; Takahashi, Yukio; Moriuchi, Shuji; and Kaneko, Hisamitsu, 4,293,720, Cl. 568-575.000.
- Miu, Ming T.: See—
- Bradley, John J.; Holtey, Thomas O.; Miller, Robert C.; Miu, Ming T.; Shen, Jian-Kuo; and Staplin, Theodore R., Jr., 4,293,908, Cl. 364-200.000.
- Miyajima, Masanobu, to Rogers Corporation. Manufacturing method for circuit board. 4,293,377, Cl. 156-656.000.
- Miyake, Hidekazu: See—
- Fujimura, Hajime; Hiramatsu, Yasuzo; Yabuuchi, Takahiro; Hisaki, Masakatu; Takikawa, Katsuo; Honna, Takaji; Miyake, Hidekazu; and Kajitani, Makoto, 4,293,713, Cl. 564-38.000.
- Miyake, Kenji: See—
- Morishita, Tuiyoshi; Miyake, Kenji; and Tobita, Kouji, 4,292,936, Cl. 123-193.00P.
- Miyamoto, Yukihiko: See—
- Yamada, Tsuneo; and Miyamoto, Yukihiko, 4,293,781, Cl. 307-273.000.
- Mobil Oil Corporation: See—
- Butter, Stephen A.; and Chester, Arthur W., 4,293,446, Cl. 252-455.00Z.
- Farcasio, Malvina; and Whitehurst, Darrell D., 4,293,404, Cl. 208-214.000.
- Fitch, John L., 4,293,035, Cl. 166-273.000.
- Paul, James M., 4,293,528, Cl. 423-7.000.
- Mochida, Hideyuki; Tamura, Shingo; and Tsurumi, Etsuo, to Hitachi, Ltd. High voltage rectifier for television receiver sets. 4,293,903, Cl. 363-68.000.
- Momot, Valery I.: See—
- Dunaevsky, Vladimir I.; Boidenko, Nikolai G.; Samarin, Alexei P.; Levit, Viktor M.; Zapara, Boris M.; Ivanov, Boris N.; Frolov, Sergei A.; Voronin, Rostislav A.; Belozero, Nikolai P.; Momot, Valery I.; Stusenko, Jury A.; and Samoilov, Vladimir A., 4,293,101, Cl. 242-56.400.
- Monarch Marking Systems, Inc.: See—
- Kirby, Raymond L., Jr., 4,292,893, Cl. 101-111.000.
- Mono-Kinetics: See—
- Dudley, Peter B., 4,293,127, Cl. 272-133.000.
- Mono, Rune G.; Moren, Nils F. E.; and Wetterlin, Kjell I. L., to Aktiebolaget Draco. Aerosol inhalation device. 4,292,966, Cl. 128-200.230.
- Monosov, Yakov A. Method of recording images on a radiation sensitive material. 4,293,634, Cl. 430-269.000.
- Monsanto Company: See—
- Bach, Hartwig C.; and Hinderer, Helmuth E., 4,293,613, Cl. 428-364.000.
- Cohen, Saul M.; and LeBlanc, John R., 4,293,693, Cl. 544-221.000.
- Hallcher, Richard C.; Goodin, Richard D.; and Baizer, Manuel M., 4,293,392, Cl. 204-59.00R.
- Hallcher, Richard C.; Goodin, Richard D.; and Baizer, Manuel M., 4,293,393, Cl. 204-59.00R.
- Heimsch, Robert A., 4,293,668, Cl. 525-369.000.
- Plischke, LeMoyné W.; Familant, Harold M.; and Kelly, Darrell A., 4,293,614, Cl. 428-370.000.
- Strazik, William F.; LeBlanc, John R.; and Santer, J. Owen, 4,293,461, Cl. 260-18.00N.
- Monsheimer, Rolf; and Pfeleiderer, Ernst, to Rohm GmbH. Method of dissolving collagen-containing tissues. 4,293,647, Cl. 435-69.000.
- Monsimer, Harold G.; and Sandler, Stanley R., to Pennwalt Corporation. Process for reacting chloral with nitrogen compositions. 4,293,454, Cl. 252-609.000.
- Montedison S.p.A.: See—
- Di Battista, Piero; Fontanelli, Renzo; Gratani, Francesco; and Nelli, Giuseppe, 4,293,466, Cl. 260-45.80N.
- Montgomery, Dean P., to Phillips Petroleum Co. Pretreatment of butene-1 in isomerization of it to butene-2. 4,293,728, Cl. 585-670.000.
- Montgomery, James W., to Brown Oil Tools, Inc. Soft shock pressure plug. 4,292,988, Cl. 137-68.00R.
- Mookherjee, Braja D.: See—
- Shu, Chi-Kuen; Mookherjee, Braja D.; and Vock, Manfred H., 4,293,579, Cl. 426-535.000.
- Moore, Carl; and Kirchoff, Robert A., to Dow Chemical Company. The. Interfacial cross-linking of latex films. 4,293,476, Cl. 260-29.70W.
- Moore, Joseph E. Method of producing color separation negatives with reduced contrast. 4,293,216, Cl. 355-77.000.
- Moore, M. Samuel; and Paluka, Charles F., to Semco Instruments, Inc. Turbocharger control system. 4,292,806, Cl. 60-600.000.
- Moran, Daniel B.: See—
- Allen, George R., Jr.; Hanfin, John W., Jr.; Moran, Daniel B.; and Albright, Jay D., 4,293,554, Cl. 424-250.000.
- Morel, Didier, to Rhone-Poulenc Industries. Unsaturated esters and method of preparing them. 4,293,500, Cl. 260-410.90R.
- Moren, Nils F. E.: See—
- Mono, Rune G.; Moren, Nils F. E.; and Wetterlin, Kjell I. L., 4,292,966, Cl. 128-200.230.
- Moretti, Anthony L.; and Ferris, Lester W., to E. D. Bullard Company. Self-setting adjustable headband. 4,292,692, Cl. 2-418.000.
- Morgan, Dean T.; Chrysostomidis, Chrysostomos; and LaRue, George J., to Thermo Electron Corporation. Metals extraction from sea water. 4,293,527, Cl. 423-6.000.
- Mori, Kazumasa: See—
- Muto, Katsuya; Mori, Kazumasa; Mase, Akira; Nimura, Takayasu; Itoh, Katsumi; and Akita, Yoshio, 4,293,811, Cl. 322-60.000.
- Mori, Masaaki, to Ricoh Company, Ltd. Simultaneous multi-beam optical modulation system. 4,293,195, Cl. 350-358.000.
- Morikawa, Yoshiharu, to Solid Corporation. Light reflecting device. 4,293,189, Cl. 350-105.000.
- Morimoto, Syogo: See—
- Nakae, Hideo; Ozaki, Toshinori; Shimaguchi, Takashi; and Morimoto, Syogo, 4,292,832, Cl. 72-365.000.
- Morino, Haruki: See—
- Umemura, Takeaki; Morino, Haruki; Watanabe, Tetsuhiko; and Uematsu, Tamon, 4,293,702, Cl. 548-165.000.
- Moris, Alfred H., to Minnesota Mining and Manufacturing Company. Endless loop tape magazine, and a recording and/or playback machine utilizing the magazine. 4,293,882, Cl. 360-93.000.
- Morisawa, Taihei: See—
- Kando, Toru; and Morisawa, Taihei, 4,293,210, Cl. 354-269.000.
- Morishita, Hirosada; Kawamoto, Mineo; and Murakami, Kanzi, to Hitachi, Ltd. Method for production of printed circuits by electroless metal plating. 4,293,592, Cl. 427-98.000.
- Morishita, Tuiyoshi; Miyake, Kenji; and Tobita, Kouji, to Toyo Kogyo Co., Ltd. Aluminum based alloy pistons for internal combustion engines. 4,292,936, Cl. 123-193.00P.
- Morita, Yasuyuki, to Toyo Kogyo Co., Ltd. Lubricating means for rotary piston engines with pressure and temperature responsive valve means in the eccentric shaft. 4,293,289, Cl. 418-84.000.
- Moriuchi, Shuji: See—
- Iwaki, Tetsuo; Takahashi, Yukio; Moriuchi, Shuji; and Kaneko, Hisamitsu, 4,293,720, Cl. 568-575.000.
- Moriya, Junichiro: See—
- Yamauchi, Toshima; Nogami, Sadao; Sawada, Kengi; Moriya, Junichiro; Sawada, Hiroomi; and Kobayashi, Keizou, 4,292,973, Cl. 128-303.100.
- Moriyama, Yoshiki; and Kuwana, Masayuki, to Toyooki Kogyo Kabushiki Kaisha. Electrically operated fluid control device. 4,293,002, Cl. 137-625.640.
- Moriyasu, Kozo: See—
- Adachi, Hideo; Minai, Kiichi; Moriyasu, Kozo; and Imagawa, Shunjiro, 4,293,768, Cl. 250-338.000.
- Morooka, Yasuo; Tanifuji, Shinya; and Tanuma, Masaya, to Hitachi, Ltd. Gauge and tension control system for tandem rolling mill. 4,292,825, Cl. 72-8.000.
- Morrey, William B.; and Welsh, David M., to CXA Ltd./CXA Ltee. Detonating device. 4,292,896, Cl. 102-275.800.
- Morris, Jesse L., to General Electric Company. Method and apparatus for physically testing the integrity of the connection between an electrode assembly and a terminal conductor of an electrochemical cell. 4,292,852, Cl. 73-827.000.
- Morris, Robert: See—
- St. Lawrence, David S.; Morris, Robert; and Farrar, James G., 4,293,266, Cl. 414-411.000.
- Mortellito, Ronald: See—
- Gardner, Roland C.; and Mortellito, Ronald, 4,293,090, Cl. 229-5.600.
- Mosely, Neal J.: See—
- Alley, David W., 4,292,987, Cl. 132-73.000.
- Mosley, Kenneth C.: See—
- Nielsen, Edward G.; Mosley, Kenneth C.; and Chatterson, Louis M., 4,293,218, Cl. 356-138.000.
- Motegi, Masanori: See—
- Muraoka, Takatoshi; Uchida, Keiichiro; Koshino, Minoru; Motegi, Masanori; and Nagasawa, Shigeru, 4,293,941, Cl. 364-200.000.

- Motorenfabrik Hatz GmbH & Co. KG: See—
- Hatz, Ernst; Eibl, Heinz; Peter, Erwin; and Blumhardt, Rolf, 4,293,092, Cl. 237-12.100.
- Motorola Inc.: See—
- Knappenberger, Thomas A.; and Landers, James F., Jr., 4,293,519, Cl. 264-272.130.
- Powell, Michael W., 4,292,729, Cl. 29-571.000.
- Mott, James D., to Hydral Company. Well safety system method and apparatus. 4,293,034, Cl. 166-208.000.
- Moynahan, E. Bradley: See—
- Beavan, Elton L.; and Moynahan, E. Bradley, 4,293,642, Cl. 430-534.000.
- Mueller, John H., to Intercontinental Valve Manufacturing Company. Plug valve actuator. 4,293,117, Cl. 251-229.000.
- Mullen, H. Gerald, to Virginia Industries, Inc. Method for manufacturing of bearings. 4,292,717, Cl. 29-148.40A.
- Muller, Lutz: See—
- Kinast, Gunther; Muller, Lutz; Puls, Walter; and Sitt, Rudiger, 4,293,551, Cl. 424-249.000.
- Muller, Roswitha: See—
- Gruenberger, Eberhard; and Muller, Roswitha, 4,293,458, Cl. 260-17.4GC.
- Mullins, John M.; and Kelly, Joseph L., Jr., to Hughes Tool Company. Non-rotating stabilizer for drill string. 4,293,039, Cl. 166-341.000.
- Mulvihill, Dan R. Insulated building structure and method for making same. 4,292,783, Cl. 52-741.000.
- Munch, Ulrich: See—
- Cordes, Gunter; Giesselmann, Ewald; and Munch, Ulrich, 4,293,565, Cl. 424-285.000.
- Munden, Jeffrey E.: See—
- Cockram, Geoffrey N.; and Munden, Jeffrey E., 4,293,575, Cl. 426-104.000.
- Murakami, Kanzi: See—
- Morishita, Hirosada; Kawamoto, Mineo; and Murakami, Kanzi, 4,293,592, Cl. 427-98.000.
- Muralidhara, H. S., to Systems Consultants, Inc. Recovery of active chitin and enhanced protein meal. 4,293,098, Cl. 241-19.000.
- Muraoka, Takatoshi; Uchida, Keiichiro; Koshino, Minoru; Motegi, Masanori; and Nagasawa, Shigeru, to Fujitsu Limited. Memory access control system in vector processing system. 4,293,941, Cl. 364-200.000.
- Murari, Bruno; and Siligoni, Marco, to SGS-ATES Componenti Elettronici S.p.A. Linear differential amplifier with unbalanced output. 4,293,824, Cl. 330-301.000.
- Murata Kikai Kabushiki Kaisha: See—
- Adachi, Hideo; Minai, Kiichi; Moriyasu, Kozo; and Imagawa, Shunjiro, 4,293,768, Cl. 250-338.000.
- Murayama, Yoshinobu, to Kubota, Ltd. Transmission for a farm tractor of four wheel drive type. 4,292,855, Cl. 74-15.400.
- Murphy, Cornelius B.; and Sypula, Donald S., to Xerox Corporation. Process of developing magnetic images and dry magnetic toner compositions. 4,293,627, Cl. 430-39.000.
- Muto, Katsuya; Mori, Kazumasa; Mase, Akira; Nimura, Takayasu; Itoh, Katsumi; and Akita, Yoshio, to Nippondenso Co., Ltd. Voltage regulator system for vehicle generator. 4,293,811, Cl. 322-60.000.
- Muto, Norio: See—
- Tanawasa, Yasusi; Muto, Norio; Saito, Akinori; and Kawamura, Kiyomi, 4,292,947, Cl. 123-445.000.
- Myers, Herbert: See—
- Langley, Robert C.; Myers, Herbert; and Abrash, Muriel, 4,293,513, Cl. 264-60.000.
- Myers, Joseph F., to Minnesota Mining and Manufacturing Company. Anchor layer in photolithographic receptor base contains oxide surface treated titanium dioxide. 4,293,625, Cl. 430-9.000.
- Myers, Michael J.: See—
- Davis, Robert K.; and Myers, Michael J., 4,293,835, Cl. 335-131.000.
- Myers, Robert W., to Owens-Corning Fiberglass Corporation. Method and apparatus for detecting a ground on electric furnaces. 4,293,730, Cl. 13-6.000.
- Myers, Ronald W.: See—
- Hughes, Donald W. K.; and Myers, Ronald W., 4,292,736, Cl. 29-884.000.
- Naarmann, Herbert: See—
- Hahn, Klaus; Naarmann, Herbert; and Penzien, Klaus, 4,293,656, Cl. 521-88.000.
- Nabholz, Hans U., to Micafil AG. Separation apparatus for a condensation-drying plant. 4,292,744, Cl. 34-73.000.
- Nagai, Kenichi: See—
- Inaba, Hideya; Nagai, Kenichi; Ichiki, Masayoshi; Kamino, Yasumi; and Maeda, Kazuo, 4,293,447, Cl. 252-461.000.
- Nagano, Katsuo; Ihaya, Kazuhiko; Sasa, Syozo; and Nakada, Takeshi, to TDK Electronics Co., Ltd. Method for the epitaxial growth of boron phosphorus semiconductors. 4,293,370, Cl. 156-612.000.
- Nagao, Syozo: See—
- Fujii, Yoshishige; Nagao, Syozo; and Kumazawa, Shunji, 4,293,418, Cl. 210-321.100.
- Nagasawa, Shigeru: See—
- Muraoka, Takatoshi; Uchida, Keiichiro; Koshino, Minoru; Motegi, Masanori; and Nagasawa, Shigeru, 4,293,941, Cl. 364-200.000.
- Nagata, Nobuyoshi: See—
- Hori, Kiyoshi; and Nagata, Nobuyoshi, 4,293,599, Cl. 427-274.000.
- Nagode, Larry R., to Quaker Oats Company, The. Push-pull wheel action toy. 4,292,759, Cl. 46-205.000.
- Nagy, Albert E., to Gould Inc. Process for producing strippable copper on an aluminum carrier and the article so obtained. 4,293,617, Cl. 428-469.000.
- Naito, Hideki: See—
- Tanaka, Toyonaru; and Naito, Hideki, 4,293,842, Cl. 340-52.00F.
- Nakada, Takeshi: See—
- Nagano, Katsuo; Ihaya, Kazuhiko; Sasa, Syozo; and Nakada, Takeshi, 4,293,370, Cl. 156-612.000.
- Nakae, Hideo; Ozaki, Toshinori; Shimaguchi, Takashi; and Morimoto, Syogo, to Hitachi, Ltd. Method of producing vibration attenuating metallic material. 4,292,832, Cl. 72-365.000.
- Nakagawa, Kazuyuki: See—
- Ishikawa, Hiroshi; and Nakagawa, Kazuyuki, 4,293,694, Cl. 546-72.000.
- Nakagawa, Kiyoshi: See—
- Otaki, Yukio; Umeda, Kazuo; and Nakagawa, Kiyoshi, 4,292,799, Cl. 57-246.000.
- Nakahara, Yutaka: See—
- Minagawa, Motonobu; Nakahara, Yutaka; and Haruna, Tohru, 4,293,472, Cl. 260-23.0XA.
- Nakai, Hiroshi: See—
- Sugio, Akitoshi; Masu, Masanobu; Nakai, Hiroshi; and Sasaki, Yukio, 4,293,478, Cl. 260-37.00R.
- Nakajima, Shunichi; and Hasegawa, Haruyoshi, to Tokyo Shibaura Denki Kabushiki Kaisha. Toner feeding device. 4,293,085, Cl. 222-311.000.
- Nakamura, Hiroto: See—
- Matsumura, Ko; Nakamura, Hiroto; and Irie, Toshio, 4,293,336, Cl. 75-124.000.
- Nakamura, Kazuo: See—
- Tokutomi, Seiji; Jyojiki, Masao; and Nakamura, Kazuo, 4,293,205, Cl. 354-23.00D.
- Tokutomi, Seiji; Jyojiki, Masao; Aoki, Harumi; Nakamura, Kazuo; and Watanabe, Koichiro, 4,293,206, Cl. 354-25.000.
- Nakamura, Masahiro: See—
- Ohtake, Yukio; and Nakamura, Masahiro, 4,293,643, Cl. 435-39.000.
- Nakanishi Metal Works Co., Ltd.: See—
- Wakabayashi, Takao, 4,292,897, Cl. 104-172.00S.
- Nakatani, Yohichiro: See—
- Tsukada, Haruo; and Nakatani, Yohichiro, 4,293,880, Cl. 360-10.000.
- Narumi, Naoki: See—
- Shimizu, Masao; Tokuno, Takashi; Ishikawa, Kohji; Narumi, Naoki; and Ohguchi, Osamu, 4,293,950, Cl. 371-21.000.
- Nash, Claude H., III; Shearer, Marcia C.; Snader, Kenneth M.; Valenta, Joseph R.; and Cooper, David, to SmithKline Corporation. Anthracycline antibiotics produced by *Streptopogonium fragilis* Shearer sp. nov. ATCC 31519. 4,293,546, Cl. 424-119.000.
- Nash, Harold A.; and Mishell, Daniel R., Jr., to Population Council, Inc., The. Intravaginal ring. 4,292,965, Cl. 128-260.000.
- Nasser, Gamal E. D., to Linde Aktiengesellschaft. Plate-type heat exchanger. 4,293,033, Cl. 165-166.000.
- National Can Corporation: See—
- George, Robert W.; Miller, Casper W.; and Rapey, Kenneth, 4,293,510, Cl. 264-40.700.
- Naum, Robert G.: See—
- Hortman, Michael T.; and Naum, Robert G., 4,293,598, Cl. 427-203.000.
- Nauomidis, Aristides: See—
- Luhleisch, Hartmut; Pflaum, Peter; Dias, Francisco J.; Nauomidis, Aristides; Schirbach, Arno; and Nickel, Hubertus, 4,293,512, Cl. 264-58.000.
- Nayak, Jnaneshwar H.: See—
- Liu, Chunghorng R.; Nayak, Jnaneshwar H.; Stenberg, Herbjorn; Huerta, Felipe J.; and Hall, Woodrow A., 4,292,865, Cl. 82-36.00R.
- Nelli, Giuseppe: See—
- Di Battista, Piero; Fontanelli, Renzo; Gratani, Francesco; and Nelli, Giuseppe, 4,293,466, Cl. 260-45.80N.
- Nelson, Carl J.: See—
- Chalmers, Franklin S.; Czako, Charles A.; and Nelson, Carl J., 4,293,390, Cl. 202-100.000.
- Nelson, Robert L.: See—
- Sutcliffe, Peter W.; Isaacs, Jim W.; Nelson, Robert L.; Lyon, Colin E.; and Stringer, Brian, 4,293,507, Cl. 264-0.500.
- Nemec, Frank A.; and Pearson, Raymond, to Lykes Bros. Steamship Co., Inc. Ocean-going barge carrier. 4,292,915, Cl. 114-260.000.
- Neseth, Clifford B.: See—
- Neseth, Clinton A.; and Neseth, Clifford B., 4,293,282, Cl. 417-53.000.
- Neseth, Clinton A.; and Neseth, Clifford B., to Neseth, Inc. Manure handling system having recirculating pump. 4,293,282, Cl. 417-53.000.
- Neseth, Inc.: See—
- Neseth, Clinton A.; and Neseth, Clifford B., 4,293,282, Cl. 417-53.000.
- Nestler, Johannes; and Wrede, Hans, to Licentia Patent-Verwaltungs-G.m.b.H. Control of power semiconductors through center-tapped transformer with self-demagnetizing circuitry. 4,293,779, Cl. 307-252.00C.
- Neukom, Chester G.; and Kopecky, Ivyl D., to Haybuster Manufacturing, Inc. Soil undercutter with trip release for pivotally mounted shank. 4,293,043, Cl. 172-267.000.
- Neukomm, Hans-Rudolf, to U.S. Philips Corporation. Method of manufacturing a device and device manufactured according to the method. 4,293,375, Cl. 156-643.000.

- Neukomm, Hans-Rudolf, to U.S. Philips Corporation. Method of manufacturing a semiconductor device using different etch rates. 4,293,588, Cl. 427-93.000.
- Neumeyer, Tom A.; and Foster, Francis W., to L. S. Starrett Company, The. Welded edge band saw tooth geometry. 4,292,871, Cl. 83-661.000.
- Neuray, Dieter: See—
Heydenreich, Frieder; Korber, Helmut; Tacke, Peter; Fahnler, Friedrich; and Neuray, Dieter, 4,293,662, Cl. 525-184.000.
- New England Nuclear Corporation: See—
Post, Dennis L., 4,293,436, Cl. 252-301.10R.
- Newage Engineers Limited: See—
Wright, Michael J., 4,293,810, Cl. 322-28.000.
- Newell, Richard G.; and Perry, Dale C., to Minnesota Mining and Manufacturing Company. Corrosion inhibiting heat transfer liquid. 4,293,441, Cl. 252-389.00A.
- Newman, Gerald H.: See—
Klemann, Lawrence P.; Newman, Gerald H.; Stogryn, Eugene L.; Whitney, Thomas A.; and Farcasiu, Dan, 4,293,623, Cl. 429-194.000.
- Newton, John C., Jr., to Ansley, Incorporated. Yarn heater track cleaning apparatus and method. 4,292,770, Cl. 51-170.0PT.
- Nezu, Yushi: See—
Asano, Kiro; Tamura, Humio; Nezu, Yushi; Saito, Tsuyoshi; and Kawai, Yoshio, 4,293,533, Cl. 423-449.000.
- NGK Insulators, Ltd.: See—
Higuchi, Noboru; Yano, Teruo; and Ohnishi, Masahiro, 4,293,357, Cl. 156-89.000.
- Wada, Shigetaka, 4,293,514, Cl. 264-61.000.
- Nguyen, Liem, to Orion Industries, Inc. Fuel consumption efficiency gauge. 4,292,840, Cl. 73-115.000.
- Nickel, Hubertus: See—
Luhleisch, Hartmut; Pflaum, Peter; Dias, Francisco J.; Nauomidis, Aristides; Schirbach, Arno; and Nickel, Hubertus, 4,293,512, Cl. 264-58.000.
- Nielsen, Edward G.; Mosley, Kenneth C.; and Chatterson, Louis M., to Laser Alignment, Inc. Reference light beam projector. 4,293,218, Cl. 356-138.000.
- Niemi, Francis J. Automatic welder's helmet having ventilation means. 4,293,757, Cl. 219-147.000.
- Nienhaus, Harry A.: See—
Brooks, James L.; Bowers, James C.; and Nienhaus, Harry A., 4,293,904, Cl. 363-86.000.
- Nifco Inc.: See—
Kojima, Masaharu; and Mitomi, Seiji, 4,293,260, Cl. 411-44.000.
- Niles, Gerald J.; and Ritter, Norman C., to Minnesota Mining and Manufacturing Company. Reel weight assembly. 4,293,102, Cl. 242-71.800.
- Nill, Edgar: See—
Reinhard, Theodor; Krugener, Rolf; Kurth, Hermann W.; Blaich, Diether; Rothmaier, Franz; Kopperschlager, Dieter; Schmitz, Heinz; and Nill, Edgar, 4,292,823, Cl. 70-364.00R.
- Nilsson, Erik R.: See—
Furendal, Allan R. B.; Larsson, Bernt; and Nilsson, Erik R., 4,293,596, Cl. 427-160.000.
- Nimura, Takayasu: See—
Muto, Katsuya; Mori, Kazumasa; Mase, Akira; Nimura, Takayasu; Itoh, Katsumi; and Akita, Yoshio, 4,293,811, Cl. 322-60.000.
- Nippon Cable System Inc.: See—
Teraura, Makoto, 4,292,859, Cl. 74-501.00R.
- Nippon Electric Co., Ltd.: See—
Iijima, Yasuo, 4,293,739, Cl. 179-18.0GF.
- Kojima, Masayuki; Kobayakawa, Masaki; and Tanaka, Kozo, 4,293,793, Cl. 313-497.000.
- Nippon Gakki Seizo Kabushiki Kaisha: See—
Okumura, Takatoshi; Hamada, Seiya; and Imamura, Akio, 4,292,873, Cl. 84-1.010.
- Nippon Hosokyo Kyoikai: See—
Togami, Yuji, 4,293,621, Cl. 428-678.000.
- Nippon Kogaku K.K.: See—
Takahashi, Yosuke, 4,293,194, Cl. 350-357.000.
- Nippon Light Metal Co., Ltd.: See—
Matsueda, Shinji, 4,293,082, Cl. 222-131.000.
- Nippon Paint Co., Ltd.: See—
Hori, Kiyoshi; and Nagata, Nobuyoshi, 4,293,599, Cl. 427-274.000.
- Nippon Steel Corporation: See—
Ichijima, Tadashi; Yamaguchi, Shigehiro; Iuchi, Tohru; and Kuroki, Katsuro, 4,293,350, Cl. 148-111.000.
- Nippon Telegraph and Telephone Public Corporation: See—
Shibayama, Akinori; Maio, Kenji; and Yokozawa, Norio, 4,293,819, Cl. 330-9.000.
- Shimizu, Masao; Tokuno, Takashi; Ishikawa, Kohji; Narumi, Naoki; and Ohguchi, Osamu, 4,293,950, Cl. 371-21.000.
- Nippondenso Co., Ltd.: See—
Muto, Katsuya; Mori, Kazumasa; Mase, Akira; Nimura, Takayasu; Itoh, Katsumi; and Akita, Yoshio, 4,293,811, Cl. 322-60.000.
- Tsuzuki, Yoshihiko; Kaga, Sumihiko; and Hobo, Nobuhito, 4,293,893, Cl. 362-38.000.
- Nishikawa, Masaji; and Kasuga, Muneco, to Olympus Optical Company Limited. Bias voltage adjusting means for electrophotographic apparatus. 4,293,213, Cl. 355-14.00R.
- Nishikawa, Masao, to Honda Giken Kogyo Kabushiki Kaisha. Power steering device for vehicles. 4,293,051, Cl. 180-133.000.
- Nishikubo, Yasuhiko; and Sekine, Mitsuo, to Citizen Watch Company Limited. Electronic timepiece having an alarm system. 4,293,939, Cl. 368-74.000.
- Nishimura, Hideo; Yoneda, Takao; and Enomoto, Minoru, to Toyoda Koki Kabushiki Kaisha. Numerical controller for a grinding machine. 4,293,913, Cl. 364-474.000.
- Nishina, Yasuhide: See—
Imada, Kiyoshi; Ueno, Susumu; Nishina, Yasuhide; and Nomura, Hirokazu, 4,293,585, Cl. 427-40.000.
- Nishizaki, Tadao: See—
Shimizu, Shinkichi; Nishizaki, Tadao; and Tsuda, Masabumi, 4,293,445, Cl. 252-438.000.
- Nissan Motor Company, Limited: See—
Masaki, Kenji, 4,292,946, Cl. 123-440.000.
- Tanaka, Toshiaki; and Etoh, Yukihiro, 4,292,938, Cl. 123-198.00F.
- Wakabayashi, Makoto; and Takagishi, Haruyoshi, 4,293,363, Cl. 156-272.000.
- Nissen, Dietmar; Marx, Matthias; Jarre, Wolfgang; Schoen, Ernst; and Decker, Walter, to BASF Aktiengesellschaft. Stable melamine polyol dispersions, a process for their manufacture and for the preparation of foamed polyurethane plastics. 4,293,657, Cl. 521-121.000.
- Nisshin Oil Mills, Ltd., The: See—
Mikami, Yasuo; Kanda, Hiroshi; and Uno, Akio, 4,293,574, Cl. 426-46.000.
- Niwa, Yukichi: See—
Tsunekawa, Tokuchi; Masunaga, Makoto; Hosoe, Kazuya; Niwa, Yukichi; Owada, Mitsutoshi; and Asano, Noriyuki, 4,293,877, Cl. 358-213.000.
- Noda, Hideki: See—
Tanaka, Kojiro; Ochiai, Shozo; and Noda, Hideki, 4,293,782, Cl. 307-350.000.
- Noe, Sergio: See—
Bertini, Fausto A.; and Noe, Sergio, 4,293,318, Cl. 55-85.000.
- Noel, Claude: See—
Christ, Charles; LeBeault, Jean-Michel; and Noel, Claude, 4,293,655, Cl. 435-316.000.
- Nogami, Sadao: See—
Yamauchi, Toshima; Nogami, Sadao; Sawada, Kengi; Moriya, Jyunichiro; Sawada, Hiroomi; and Kobayashi, Keizou, 4,292,973, Cl. 128-303.100.
- Noguchi, Satoshi; and Kitao, Takaya, to Matsushita Electric Industrial Co., Ltd. Time sound generating device. 4,293,940, Cl. 368-75.000.
- Nomura, Hirokazu: See—
Imada, Kiyoshi; Ueno, Susumu; Nishina, Yasuhide; and Nomura, Hirokazu, 4,293,585, Cl. 427-40.000.
- Norden Laboratories, Inc.: See—
Kucera, Carrell J., 4,293,545, Cl. 424-92.000.
- North Eastern Timber (U.S.A.) Incorporated: See—
Israel, Benjamin, 4,293,292, Cl. 425-9.000.
- Northern Telecom Inc.: See—
Splitt, Frank G.; and Turner, Donald B., 4,293,887, Cl. 361-120.000.
- Northern Telecom Limited: See—
Gibb, William D.; and Clement, Donald E., 4,293,740, Cl. 179-99.00A.
- Northup, John D. Method for manufacturing glass bottles. 4,293,327, Cl. 65-64.000.
- Northwestern Laboratories, Inc.: See—
Wilson, Robert B., 4,293,305, Cl. 8-115.600.
- Norwalk Investment Club: See—
Tishler, Albert; Tishler, Murray; Tishler, William; Tishler, Irving; and Lucchesi, Joseph, 4,292,834, Cl. 72-482.000.
- Nosovitsky, Alexander Y.: See—
Kopylov, Alexei A.; Kuzmenko, Valentin T.; Stepanov, Alexandr N.; Gaschenko, Viktor P.; Kaznacheyevsky, Nikolai A.; Nosovitsky, Alexandr Y.; Misikov, Ivan I.; Shapiro, Alexandr I.; Skakunov, Ivan G.; Markin, Valentin G.; Konstantinov, Alexei K.; Abramian, Eduard S.; Soroka, Arseny M.; and Zinchenko, Yakov A., 4,292,928, Cl. 119-17.000.
- Nourney, Carl-Ernst. Strain-gauge sound pickup for string instrument. 4,292,875, Cl. 84-1.140.
- Nuller, Hanns P.: See—
Mazanek, Jan; and Nuller, Hanns P., 4,293,680, Cl. 528-67.000.
- Oakeridge Management Services B.V.: See—
Clover, George R., 4,293,190, Cl. 350-241.000.
- Oakman, Ronald A., to Stanhope-Seta Limited. Liquid testing apparatus. 4,292,837, Cl. 73-17.00R.
- Oana, Yoshinori: See—
Wada, Shinji; Kitao, Ikuro; Oana, Yoshinori; Kato, Yasuo; and Ishihara, Takatoshi, 4,293,199, Cl. 351-13.000.
- O'Brien, Joseph P.: See—
Papay, Andrew G.; and O'Brien, Joseph P., 4,293,432, Cl. 252-49.900.
- Ochiai, Shozo: See—
Tanaka, Kojiro; Ochiai, Shozo; and Noda, Hideki, 4,293,782, Cl. 307-350.000.
- O'Connor, John W., to Allis-Chalmers Corporation. Hydraulic draft load sensing system including quill shaft bendable in response to draft loads. 4,293,040, Cl. 172-7.000.
- Odeco Engineers Inc.: See—
Petty, Terry D.; Costello, Carmon R.; Rao, Gude P.; and Gansar, David, 4,293,239, Cl. 405-195.000.
- Officine Augusto Cattani & C. S.A.S.: See—
Cattani, Augusto, 4,293,300, Cl. 433-92.000.
- Offner, Abe, to Perkin-Elmer Corporation. The. Restricted off-axis field optical system. 4,293,186, Cl. 350-27.000.
- Ogawa, Genshiro. Temperature-controlled electric heating device for heating instillation or transfusion liquids. 4,293,762, Cl. 219-302.000.

- Ogihara, Masuo; Chimura, Kozo; Shinozaki, Nobuo; and Seki, Yoichi, to Seiko Koki Kabushiki Kaisha. Alarm signaling time detecting device for digital clock. 4,293,938, Cl. 368-72.000.
- Ogimoto, Kazuo; Inoue, Tomohiro; Tanaka, Susumu; and Kobayashi, Yoshio, to Tokyo Shibaura Denki Kabushiki Kaisha. Method for installing an electric power plant. 4,293,240, Cl. 405-195.000.
- Ogita, Minoru. Noise eliminator for radio receiver. 4,293,736, Cl. 179-1.0GD.
- Ohguchi, Osamu: See—
Shimizu, Masao; Tokuno, Takashi; Ishikawa, Kohji; Narumi, Naoki; and Ohguchi, Osamu, 4,293,950, Cl. 371-21.000.
- Ohlbach, Ralph C. For protecting printed circuit boards and other items against the ravages of a discharge of static electricity. 4,293,070, Cl. 206-328.000.
- Ohlswager, Stanley; Edison, Robert R.; and Dresser, Thorpe, to Atlantic Richfield Company. Method and apparatus for the distribution of liquid-vapor mixture. 4,293,025, Cl. 165-1.000.
- Ohnishi, Masahiro; and Kimura, Tsutomu, to Fuji Photo Film Co., Ltd. Light beam recording device. 4,293,202, Cl. 354-5.000.
- Ohnishi, Masahiro: See—
Higuchi, Noboru; Yano, Teruo; and Ohnishi, Masahiro, 4,293,357, Cl. 156-89.000.
- Ohsumi, Katsumi; and Miki, Minoru, to Hitachi, Ltd. Method of starting up a nuclear reactor. 4,293,382, Cl. 376-308.000.
- Ohta, Hirofumi, to Hitachi, Ltd. Magnetic bubble memory devices. 4,293,929, Cl. 365-2.000.
- Ohta, Masafumi: See—
Hashimoto, Mitsuru; Ohta, Masafumi; Kozima, Akio; Sakai, Kiyoshi; and Sasaki, Masao, 4,293,628, Cl. 430-58.000.
- Sasaki, Masao; Sakai, Kiyoshi; Hashimoto, Mitsuru; Ohta, Masafumi; and Tsutsui, Kyoji, 4,293,492, Cl. 260-160.000.
- Ohta, Ryuji; and Inoue, Yoshimichi, to Jidosha Kiki Co., Ltd. Power servo booster. 4,292,887, Cl. 92-94.000.
- Ohtake Works Company, Ltd.: See—
Ohtake, Yukio; and Nakamura, Masahiro, 4,293,643, Cl. 435-39.000.
- Ohtake, Yukio; and Nakamura, Masahiro, to Ohtake Works Company, Ltd. Rotary shaking culture measuring method and apparatus. 4,293,643, Cl. 435-39.000.
- Oka, Kozo, to Rank Xerox Limited. Electrophotographic photosensitive member. 4,293,630, Cl. 430-59.000.
- Okamoto, Taro: See—
Tanaka, Katsushi; and Okamoto, Taro, 4,293,227, Cl. 366-11.000.
- Okuda, Hironori: See—
Ito, Motoya; Sato, Masaki; Watanabe, Masatoshi; and Okuda, Hironori, 4,293,787, Cl. 310-181.000.
- Okudaira, Sadao: See—
Kobayashi, Koichi; and Okudaira, Sadao, 4,293,197, Cl. 350-454.000.
- Okumura, Takatoshi; Hamada, Seiya; and Imamura, Akio, to Nippon Gakki Seizo Kabushiki Kaisha. Electronic musical instrument. 4,292,873, Cl. 84-1.010.
- Okuya, Ken, to Tamura Kaken Co., Ltd. Photopolymerizable polyester containing compositions. 4,293,636, Cl. 430-281.000.
- Olin Corporation: See—
Mendiratta, Sudhir K., 4,293,721, Cl. 568-916.000.
- Sacman, Walter C., 4,293,324, Cl. 65-27.000.
- Olofsson, Mats; Buhler, Marcel; and Wood, Robert, to Societe d'Assistance Technique pour Produits Nestle S.A. Process for the preparation of a purified protein hydrolysate. 4,293,571, Cl. 426-7.000.
- Olshewski, Armin: See—
Ernst, Horst M.; Olshewski, Armin; Schurger, Rainer; Walter, Lothar; Brandenstein, Manfred; and Burkl, Erich, 4,293,166, Cl. 308-6.00C.
- Olsen, Edward C. Horse-feeding apparatus. 4,292,930, Cl. 119-51.110.
- Olson, John S., to Phillips Petroleum Company. Hydrocarbon heating. 4,293,402, Cl. 208-93.000.
- Olson, Jon S.: See—
George, Clifford L.; and Olson, Jon S., 4,293,214, Cl. 355-14.00R.
- Olson, Paul E.; and Lyons, Michael D., to American Standard Inc. Multi-function operator for control valve device. 4,293,118, Cl. 251-297.000.
- Olympus Optical Company Ltd.: See—
Kawashima, Kazuma, 4,292,961, Cl. 128-6.000.
- Nishikawa, Masaji; and Kasuga, Muneco, 4,293,213, Cl. 355-14.00R.
- Sato, Masanobu; and Satoh, Ken, 4,293,742, Cl. 179-178.000.
- OMUV Orvosi Muszer es Vasipari Szovetkezet: See—
Pataki, Jozsef; Bucsi, Jozsef; Bona, Istvan; Szilvasi, Endre; Gazdag, Andras; Koty, Antal; and Hidvegi, Ferenc, 4,292,996, Cl. 137-393.000.
- Ondetti, Miguel A.: See—
Condon, Michael E.; and Ondetti, Miguel A., 4,293,481, Cl. 260-112.50R.
- Onoda, Yukio: See—
Kinoshita, Minoru; Sugou, Kiyoshi; and Onoda, Yukio, 4,293,226, Cl. 356-443.000.
- Oonishi, Souichi, to Sharp Kabushiki Kaisha. Electronic cash register with facilities of storing merchandise information. 4,293,911, Cl. 364-405.000.
- Opal, Kenneth E., to Power Control Corporation. Method and apparatus for controlling power and optimizing power factor in an AC-to-DC converter. 4,293,905, Cl. 363-124.000.
- Optical Coating Laboratory, Inc.: See—
Rancourt, James D.; and Seddon, Richard I., 4,293,732, Cl. 136-257.000.
- Orebro Pappersbruks AB: See—
Millgardh, Ulf J.; Lindberg, Ulf W.; Annelod, Weimar A.; Werner, Nils H.; and Wemelius, Bjorn, 4,293,607, Cl. 428-212.000.
- Orion Industries, Inc.: See—
Nguyen, Liem, 4,292,840, Cl. 73-115.000.
- Ormat Turbines, Ltd.: See—
Rambach, Claude, 4,293,030, Cl. 165-40.000.
- Orogil: See—
Demoures, Bernard; and Le Coent, Jean-Louis, 4,293,431, Cl. 252-33.200.
- Rivier, Georges, 4,293,430, Cl. 252-32.70E.
- O'Rourke, Thomas J.: See—
Sprecker, Mark A.; Sanders, James M.; Schreiber, William L.; Watkins, Hugh; Vinals, Joaquin F.; Shuster, Edward J.; O'Rourke, Thomas J.; Hagedorn, Myrna L.; and Klemarczyk, Philip, 4,293,453, Cl. 252-522.00R.
- Oerscheln Brake Lever Mfg. Co.: See—
Lipshild, Eugene C., 4,292,858, Cl. 74-501.00R.
- Osada, Hiroshi, to Kai Cutlery Center Co., Ltd. Knife. 4,292,738, Cl. 30-162.000.
- Osborne, Vernon E.: See—
Wahlers, Richard L.; and Osborne, Vernon E., 4,293,838, Cl. 338-308.000.
- Osburn, Carlton M.: See—
Van Benthuyzen, John D.; and Osburn, Carlton M., 4,293,751, Cl. 200-156.000.
- Ose, Earl E.: See—
Ludwig, Nelson H.; and Ose, Earl E., 4,293,539, Cl. 424-19.000.
- Osterhaus, Albertus D. M. E.: See—
Horzinek, Marian C.; and Osterhaus, Albertus D. M. E., 4,293,653, Cl. 435-237.000.
- Otake, Yukio; Umeda, Kazuo; and Nakagawa, Kiyoshi, to Toray Industries, Inc. Spun yarn-like textured yarns and process for producing same. 4,292,799, Cl. 57-246.000.
- Otsuka Pharmaceutical Co., Ltd.: See—
Ishikawa, Hiroshi; and Nakagawa, Kazuyuki, 4,293,694, Cl. 546-72.000.
- Ott, Albert: See—
Fischer, Helmut; Ott, Albert; and Stegmuller, Willi, 4,293,767, Cl. 250-308.000.
- Ott, Clyde E. Tool holder and carbide insert. 4,293,253, Cl. 408-226.000.
- Ottofrickenstein, Hans: See—
Fink, Herbert; Huebner, Klaus; Dinklage, Horst; and Ottofrickenstein, Hans, 4,293,600, Cl. 427-385.500.
- Owada, Mitsutoshi: See—
Tsunekawa, Tokuchi; Masunaga, Makoto; Hosoe, Kazuya; Niwa, Yukichi; Owada, Mitsutoshi; and Asano, Noriyuki, 4,293,877, Cl. 358-213.000.
- Owens-Corning Fiberglass Corporation: See—
Myers, Robert W., 4,293,730, Cl. 13-6.000.
- Shannon, Richard F., 4,293,343, Cl. 106-99.000.
- Thompson, Thomas K., 4,292,862, Cl. 76-4.000.
- Ozaki, Toshinori: See—
Nakae, Hideo; Ozaki, Toshinori; Shimaguchi, Takashi; and Morimoto, Syogo, 4,292,832, Cl. 72-365.000.
- P. Ferrero & C. S.p.A.: See—
Cillario, Renzo, 4,293,577, Cl. 426-244.000.
- Pabian, Howell D.: See—
Gehr, Marvin M.; and Pabian, Howell D., 4,293,955, Cl. 455-276.000.
- Pacific Technology, Inc.: See—
Carpenter, Edward J.; Korff, William W.; Zoerb, Alan E., deceased; Barello, Lawrence J.; Hall, Donald R.; and Becker, Orlien N., 4,293,915, Cl. 364-493.000.
- Pacific Western Systems, Inc.: See—
Worsham, Daniel A., 4,292,722, Cl. 29-402.210.
- Packham, Charles C., to Gillette Company, The. Dry shaver with differentially biased inner cutter and base members. 4,292,737, Cl. 30-43.920.
- Paddock, Stephen W., to Whirlpool Corporation. Adaptive temperature control system. 4,292,813, Cl. 62-158.000.
- Paget, Charles J.; Chamberlin, James W.; and Wikel, James W., to Eli Lilly and Company. Antiviral thiazolyl benzimidazoles and derivatives. 4,293,558, Cl. 424-270.000.
- Pagione, Robert W., to RCA Corporation. Apparatus and method for application of radioactive and microwave energy to the body. 4,292,960, Cl. 128-1.100.
- Pai, Venkatrao K.; and Skrivan, Joseph F., to American Cyanamid Company. Continuous process for manufacturing substantially fully methylated substantially fully methylolated melamine compositions. 4,293,692, Cl. 544-196.000.
- Pako Corporation: See—
Kaufmann, Kenneth M., 4,293,211, Cl. 354-298.000.
- Pallos, Ferenc M.; and Gaughan, Edmund J., to Stauffer Chemical Company. N-(Benzenesulfonyl) carbamates - herbicidal antidotes. 4,293,701, Cl. 546-335.000.
- Paluka, Charles F.: See—
Moore, M. Samuel; and Paluka, Charles F., 4,292,806, Cl. 60-600.000.
- Pamer, Walter R., to Lamson & Sessions Co., The. Load indicating fastener. 4,293,256, Cl. 411-11.000.
- Panetti, Romolo, to Speno International S.A. Grinding tool. 4,292,768, Cl. 51-168.000.
- Pap, Joe P.; Pap, Marilyn D.; Beyler, Arvil L.; and Beyler, Doris M. Sun shade for infant seat and the like. 4,293,162, Cl. 297-184.000.

- Pap, Marilyn D.: See—
Pap, Joe P.; Pap, Marilyn D.; Beyler, Arvil L.; and Beyler, Doris M., 4,293,162, Cl. 297-184.000.
- Papay, Andrew G.; and O'Brien, Joseph P., to Ethyl Corporation. Lubricating oil composition. 4,293,432, Cl. 252-49.900.
- Paranjpe, Suresh C.: See—
Davis, James W.; and Paranjpe, Suresh C., 4,293,863, Cl. 346-75.000.
- Pareja, Ramon, to Lear Siegler, Inc. High pressure unloader valve. 4,292,990, Cl. 137-115.000.
- Parekh, Bhupendra K.; and Goldberger, William M., to Silag, Inc. Recovery of silicon carbide whiskers from coked, converted rice hulls by froth flotation. 4,293,099, Cl. 241-24.000.
- Park, Sung K.; and Kenyon, William E., to Schlumberger Technology Corporation. Well logging apparatus and method: synthetic logs and synthetic seismograms with extrapolated reflector dip from log measurements. 4,293,933, Cl. 367-25.000.
- Parker-Hannifin Corporation: See—
Wallace, Joseph E., 4,293,135, Cl. 277-9.000.
- Parker Italiana S.a.s.: See—
Pedrazzini, Giuseppe, 4,293,349, Cl. 148-6.15R.
- Parkin, Paul C., to Imperial Chemical Industries, Limited. Process for spinning bicomponent filaments. 4,293,516, Cl. 264-168.000.
- Parks-Cramer Company: See—
Werst, Lyman L., 4,292,800, Cl. 57-264.000.
- Parks, Glenn C., Jr.; and Beam, Clark W., to Hydril Company. Testing mechanism for blowout preventer ram lock. 4,293,115, Cl. 251-1.00A.
- Parrish, John D.: See—
Mayo, Terry H.; and Parrish, John D., 4,293,167, Cl. 308-8.200.
- Partain, James H., to Stone Container Corporation. Wardrobe container. 4,293,069, Cl. 206-279.000.
- Parthasarathy, R.; and Hort, Eugene V., to GAF Corporation. Solid catalysts for oxidative dehydrogenation of alkenes or alkadienes to furan compounds. 4,293,444, Cl. 252-432.000.
- Pasquinelli, Ottorino: See—
Cazzaniga, Italo; and Pasquinelli, Ottorino, 4,292,989, Cl. 137-72.000.
- Passafiume, Anthony: See—
Klasek, Ladislav J.; Lamber, Clarence F.; and Passafiume, Anthony, 4,293,367, Cl. 156-494.000.
- Pasternack, Adalbert, to Drägerwerk Aktiengesellschaft. Respirator having oxygen delivering chemical cartridge. 4,292,967, Cl. 128-202.260.
- Pataki, Jozsef; Bucsi, Jozsef; Bona, Istvan; Szilvasi, Endre; Gazdag, Andras; Koty, Antal; and Hidvegi, Ferenc, to OMUV Orvosi Muszer es Vasipari Szovetkezet. Stop valve. 4,292,996, Cl. 137-393.000.
- Patil, Suhas S., to Massachusetts Institute of Technology. Storage/logic array. 4,293,783, Cl. 307-465.000.
- Paul, James M., to Mobil Oil Corporation. Yellowcake processing in uranium recovery. 4,293,528, Cl. 423-7.000.
- Paulson, John A.: See—
Middleton, Wilbur D.; and Paulson, John A., 4,293,110, Cl. 244-199.000.
- Pawelchak, John M.; Wang, Yu-Chang J.; and LaVia, Anthony L., to E. R. Squibb & Sons, Inc. Lyophilized hydrocolloid foam. 4,292,972, Cl. 128-296.000.
- Pearlson, Raymond: See—
Nemec, Frank A.; and Pearlson, Raymond, 4,292,915, Cl. 114-260.000.
- Pecoraro, Richard J.: See—
Helveston, Wilton L.; and Pecoraro, Richard J., 4,293,241, Cl. 405-213.000.
- Pedrazzini, Giuseppe, to Parker Italiana S.a.s. Protective compositions for steel surfaces and the process for their preparation. 4,293,349, Cl. 148-6.15R.
- Pedrazzoli, Andrea; and Boveri, Sergio, to C.M. Industries. Talampicilin 2-methoxyphenoxyacetate and pharmaceutical compositions containing it. 4,293,560, Cl. 424-271.000.
- Peery, Walter E. Phototypesetter, method and apparatus. 4,293,203, Cl. 354-17.000.
- Pellegata, Renato: See—
Gandolfi, Carmelo; Pellegata, Renato; Faustini, Franco; and Fumagalli, Angelo, 4,293,705, Cl. 560-53.000.
- Pelton, Peter G.; and Pulciani, Sam C., to Continental Group, Inc., The. Sealing-attaching system for bag type aerosol containers. 4,293,353, Cl. 156-69.000.
- Penn, William B.: See—
Zdaniewski, Joseph J.; Penn, William B.; and Balke, Roy L., 4,293,784, Cl. 310-45.000.
- Pennwalt Corporation: See—
Monsimer, Harold G.; and Sandler, Stanley R., 4,293,454, Cl. 252-609.000.
- Pentek Corporation: See—
Dyer, Thomas A.; and Huelster, Richard L., 4,293,065, Cl. 198-781.000.
- Penzien, Klaus: See—
Hahn, Klaus; Naarmann, Herbert; and Penzien, Klaus, 4,293,656, Cl. 521-88.000.
- Pepper, William, Jr., to Peptek, Incorporated. Touch panel system and method. 4,293,734, Cl. 178-18.000.
- Peptek, Incorporated: See—
Pepper, William, Jr., 4,293,734, Cl. 178-18.000.
- Pera, John D.: See—
Buckman, John D.; Buckman, Stanley J.; Johnson, Betty S.; and Pera, John D., 4,293,559, Cl. 424-270.000.
- Percarpio, Edward P.; and Holderith, William J., to Becton, Dickinson and Company. Vacuum indicator closure for a blood collection tube. 4,293,078, Cl. 215-247.000.
- Perkin-Elmer Corporation, The: See—
Buckley, William D., 4,293,624, Cl. 430-5.000.
- Offner, Abe, 4,293,186, Cl. 350-27.000.
- Perkins, Arthur T. Communication device. 4,293,855, Cl. 340-712.000.
- Perricone, Alphonse C.: See—
Lucas, James M.; Enright, Dorothy P.; and Perricone, Alphonse C., 4,293,427, Cl. 252-8.50C.
- Perron, Robert: See—
Gauthier-Lafaye, Jean; and Perron, Robert, 4,293,718, Cl. 568-487.000.
- Perry, Dale C.: See—
Newell, Richard G.; and Perry, Dale C., 4,293,441, Cl. 252-389.00A.
- Persson, Alf; and Soderberg, Nils O. Tie for wood piles. 4,293,605, Cl. 428-126.000.
- Perulli, John R., to Westinghouse Electric Corp. High-voltage puffer-type compressed-gas circuit-interrupter assemblage. 4,293,747, Cl. 200-145.000.
- Peter, Erich, to Lindauer Dornier Gesellschaft mbH. Pile warp thread unwinding device for a terry cloth loom. 4,293,006, Cl. 139-102.000.
- Peter, Erwin: See—
Hatz, Ernst; Eibl, Heinz; Peter, Erwin; and Blumhardt, Rolf, 4,293,092, Cl. 237-12.100.
- Peters, Edwin F.: See—
Boudouris, Angelo; and Peters, Edwin F., 4,293,821, Cl. 330-126.000.
- Peterson, Francis C., to Illinois Tool Works Inc. Tension indicating washer. 4,293,257, Cl. 411-11.000.
- Peterson, John O. H.: See—
Loft, Frederick A.; and Peterson, John O. H., 4,293,360, Cl. 156-230.000.
- Peterson, William: See—
Savio, Ferdinando; and Peterson, William, 4,293,361, Cl. 156-242.000.
- Petralia, Salvatore C.: See—
Budnovitch, William F.; Petralia, Salvatore C.; and Silvestris, Louis F., 4,293,898, Cl. 362-291.000.
- Petrolite Corporation: See—
Cheng, William J.; Guthrie, David B.; and Leidecker, Donald M., 4,293,429, Cl. 252-18.000.
- Petty, Terry D.; Costello, Carmon R.; Rao, Gude P.; and Gansar, David, to Odeco Engineers Inc. Method of erecting a very large diameter offshore column. 4,293,239, Cl. 405-195.000.
- Pfeil, Janice L.: See—
Kukulja, Stjepan; and Pfeil, Janice L., 4,293,493, Cl. 260-239.00A.
- Kukulja, Stjepan; and Pfeil, Janice L., 4,293,495, Cl. 260-245.400.
- Pflaum, Peter: See—
Luhle, Hartmut; Pflaum, Peter; Dias, Francisco J.; Nauomidis, Aristides; Schirbach, Arno; and Nickel, Hubertus, 4,293,512, Cl. 264-58.000.
- Pfleiderer, Ernst: See—
Monsheimer, Rolf; and Pfeiderer, Ernst, 4,293,647, Cl. 435-69.000.
- Phelps, Harold E.; and Gansley, Byron J. Log splitter. 4,293,013, Cl. 144-193.00A.
- Philip Morris Incorporated: See—
Brinker, Reiner G., 4,292,872, Cl. 83-866.000.
- Philippides, Constantinos, to United States of America, Navy. Clock invariant synchronization for random binary sequences. 4,293,949, Cl. 371-6.000.
- Phillips Petroleum Co.: See—
Campbell, Robert W.; and Hill, H. Wayne, Jr., 4,293,688, Cl. 528-346.000.
- Lacy, Robert H., 4,293,849, Cl. 340-365.00S.
- Montgomery, Dean P., 4,293,728, Cl. 585-670.000.
- Olson, John S., 4,293,402, Cl. 208-93.000.
- Swanson, Billy L., 4,293,036, Cl. 166-302.000.
- Phillips, Raymond M. Surge dampened water bed mattress. 4,292,702, Cl. 5-451.000.
- PIAT Impalcature Automatische S.p.A.: See—
Pieri, Antonio, 4,293,054, Cl. 182-63.000.
- Pichler, Ludwig: See—
Stahle, Helmut; Koppe, Herbert; Kummer, Werner; Hoefke, Wolfgang; Gaida, Wolfram; and Pichler, Ludwig, 4,293,564, Cl. 424-273.00R.
- Pidou, B.V.: See—
Swantee, Klaus B. M., 4,293,138, Cl. 277-207.00A.
- Pieri, Antonio, to PIAT Impalcature Automatische S.p.A. Scaffolding for supporting lifting working bridges and platforms. 4,293,054, Cl. 182-63.000.
- Pierlas, Rene: See—
Taponier, Jean; and Pierlas, Rene, 4,293,437, Cl. 252-301.10W.
- Pierrat, Michel A. Log splitter with overload protection. 4,293,012, Cl. 144-193.00A.
- Pilat, Wladyslaw: See—
Jedlinski, Zbigniew; Thomalla, Bogdan; Kotas, Antoni; Jedlinski, Stanislaw; Pilat, Wladyslaw; and Jach, Jan, 4,293,685, Cl. 528-190.000.
- Pilette, Yvan P.: See—
Flint, William L.; and Pilette, Yvan P., 4,293,635, Cl. 430-271.000.
- Pilgrim Electric Company: See—
Allison, William W., 4,293,846, Cl. 340-310.00A.

- Pinczewski, Morris: See—
Barrett, Edward E.; Hahn, Steven; Lensky, Albert; Pinczewski, Morris; and Sobelman, Seymour, 4,293,088, Cl. 227-131.000.
- Pinegar, Richard K.: See—
Hamann, Michael L.; and Pinegar, Richard K., 4,293,582, Cl. 426-637.000.
- Pines, Arthur N.: See—
Carter, Richard G.; Watson, Stuart L., Jr.; and Pines, Arthur N., 4,293,678, Cl. 528-32.000.
- Planakis, Leo N. Game rackets and paddles with nonparallel playing surfaces. 4,293,129, Cl. 273-67.00R.
- Plastic Recycling Limited: See—
Mair, William J., 4,293,515, Cl. 264-120.000.
- Plesnetsov, Jury A.: See—
Trishevsky, Igor S.; Trishevsky, Oleg I.; Bosy, Vladimir N.; Deber-deev, Rustem J.; Radjukevich, Leonid V.; Anisimov, Vyacheslav I.; Plesnetsov, Jury A.; and Chukhno, Valery V., 4,292,830, Cl. 72-197.000.
- Plischke, LeMoyné W.; Familant, Harold M.; and Kelly, Darrell A., to Monsanto Company. Crimped polyester filament. 4,293,614, Cl. 428-370.000.
- Plummer, William T., to Polaroid Corporation. Zoom light apparatus. 4,293,892, Cl. 362-17.000.
- Pneumatic Scale Corporation: See—
Buschor, Josef J.; and Jennings, Frederick R., 4,292,787, Cl. 53-456.000.
- Poeppel, Fritz-Otto: See—
Luck, Klaus; and Poeppel, Fritz-Otto, 4,293,265, Cl. 414-140.000.
- Polaroid Corporation: See—
Bagdis, Judy, 4,293,208, Cl. 354-29.000.
- Plummer, William T., 4,293,892, Cl. 362-17.000.
- Poletto, John F.: See—
Bernady, Karel F.; Floyd, Middleton B., Jr.; Poletto, John F.; Schaub, Robert E.; and Weiss, Martin J., 4,293,704, Cl. 556-442.000.
- Polidoro, Aldo. Gas burner, in particular for liquid gases. 4,293,297, Cl. 431-286.000.
- Polska Akademia Nauk Zaklad Polimerow: See—
Jedlinski, Zbigniew; Thomalla, Bogdan; Kotas, Antoni; Jedlinski, Stanislaw; Pilat, Wladyslaw; and Jach, Jan, 4,293,685, Cl. 528-190.000.
- Polston, Larry D.: See—
Stanback, Harris L.; Brann, Theodore L.; and Polston, Larry D., 4,293,153, Cl. 292-85.000.
- Pongracz, Endre, to SAPAL Societe Anonyme des Plieuses Automatiques. Method and devices for regulation of the forward travel of a strip bearing marks at regular intervals, and a wrapping-machine employing such a device. 4,293,774, Cl. 250-548.000.
- Ponsford, Roger J.; Baxter, Andrew J. G.; and Southgate, Robert, to Beecham Group Limited. β -Lactam antibiotics, a process for their preparation and their use in pharmaceutical compositions. 4,293,501, Cl. 260-430.000.
- Popa, Adrian E., to Hughes Aircraft Company. Millimeter wave transmission line using thallium bromo-iodide fiber. 4,293,833, Cl. 333-239.000.
- Pope, John A.: See—
Huffey, Roy F.; and Pope, John A., 4,293,633, Cl. 430-152.000.
- Population Council, Inc., The: See—
Nash, Harold A.; and Mishell, Daniel R., Jr., 4,292,965, Cl. 128-260.000.
- Ports, Kenneth A., to Harris Corporation. Method of fabricating mesa bipolar memory cell utilizing epitaxial deposition, substrate removal and special metallization. 4,292,730, Cl. 29-577.00C.
- Portugall, Michael; Finkelmann, Heino; and Ringsdorf, Helmut, to BASF Aktiengesellschaft. Liquid-crystalline polymer phase having a cholesteric structure, processes for its preparation and its use. 4,293,435, Cl. 252-299.010.
- Poticha, Stuart M.: See—
Raible, Donald A.; Poticha, Stuart M.; and Stauffer, Rita, 4,292,969, Cl. 128-214.00R.
- Potin, Philippe: See—
Cotte, Jean-Marie; and Potin, Philippe, 4,293,543, Cl. 424-59.000.
- Potter, Thomas R., to Detector Systems, Inc. Pedestrian traffic control system. 4,293,841, Cl. 340-44.000.
- Powell, Michael W., to Motorola, Inc. Electron-beam programmable semiconductor device structure. 4,292,729, Cl. 29-571.000.
- Power Control Corporation: See—
Opal, Kenneth E., 4,293,905, Cl. 363-124.000.
- PPG Industries, Inc.: See—
Darlington, William B.; DuBois, Donald W.; and White, Preston S., 4,293,394, Cl. 204-98.000.
- Gorman, Susan B.; Thompson, Ralph B.; and Yonan, Edward E., 4,293,706, Cl. 560-163.000.
- Grove, William S., 4,293,329, Cl. 71-88.000.
- Prucnal, Paul J., 4,293,398, Cl. 204-181.00C.
- Richter, Sidney B.; and Grove, William S., 4,293,707, Cl. 562-472.000.
- Simon, Martin J., 4,293,457, Cl. 260-15.000.
- Young, Elgin E., 4,293,503, Cl. 260-463.000.
- Prab Conveyors, Inc.: See—
Herder, Gary A., 4,293,408, Cl. 209-638.000.
- Pramaggiore, Luigi. Cigarette lighters, particularly for motor vehicles. 4,293,761, Cl. 219-269.000.
- PRE Corporation: See—
Borg, Paul E.; and Lechinger, Terry M., 4,292,772, Cl. 52-118.000.
- Preisa, Ieva E.: See—
Uldriks, Yan R.; Preisa, Ieva E.; Dubur, Gunar Y.; Zidermane, Aina A.; Biseniex, Egils A.; and Tirzīt, Gunar D., 4,293,700, Cl. 546-321.000.
- Press, Irving D., to Resistoflex Corporation. Fluid conduit assembly. 4,293,150, Cl. 285-149.000.
- Pretor, Wincenty; Rozmus, Edward; Korecki, Zbigniew; and Karman-ski, Stanislaw, to Centralny Ośrodek Projektowo-Konstrukcyjny Maszyn Gorniczych "Komag". Walking roof support. 4,293,248, Cl. 405-300.000.
- Pretty Products, Inc.: See—
Bell, Ted A.; and Lehner, Daniel F., 4,293,140, Cl. 280-154.50R.
- Preussag Aktiengesellschaft: See—
Luck, Klaus; and Poeppel, Fritz-Otto, 4,293,265, Cl. 414-140.000.
- Price, Kenneth E., to Price, Kenneth E. Method of chlorinating swimming pools and the like. 4,293,425, Cl. 210-754.000.
- Price, William M.: See—
Lewis, Herbert I.; McConnell, Anthony D.; and Price, William M., 4,293,097, Cl. 241-16.000.
- Prime, Derek A., to J. C. Bamford Excavators Limited. Excavators. 4,293,270, Cl. 414-690.000.
- Prior, Barry, to Rohr Industries, Inc. Turbo fan engine mixer. 4,292,803, Cl. 60-230.000.
- Probst, Joachim; Sonntag, Michael; and Kolb, Gunter, to Bayer Aktiengesellschaft. Low molecular weight acrylate resins containing hydroxyl and tertiary amino groups. 4,293,661, Cl. 525-127.000.
- Procter & Gamble Company, The: See—
Hamilton, Peter W.; and Lewis, William P., 4,293,095, Cl. 239-35.000.
- Prototech Company: See—
Allen, Robert J.; Lindstrom, Robert; and Juda, Walter, 4,293,396, Cl. 204-106.000.
- Prucnal, Paul J., to PPG Industries, Inc. Process for cathodically electrodepositing polymers having tertiary amine oxide groups. 4,293,398, Cl. 204-181.00C.
- Puerto, Maura C.: See—
Gale, Walter W.; Puerto, Maura C.; Ashcraft, Thomas L.; Saunders, Roderick K.; and Reed, Ronald L., 4,293,428, Cl. 252-8.55D.
- Pulciani, Sam C.: See—
Pelton, Peter G.; and Pulciani, Sam C., 4,293,353, Cl. 156-69.000.
- Puls, Walter: See—
Kinast, Gunther; Muller, Lutz; Puls, Walter; and Sitt, Rudiger, 4,293,551, Cl. 424-249.000.
- Pyke, Thomas R.: See—
Wovcha, Merle G.; Biggs, Candice B.; and Pyke, Thomas R., 4,293,645, Cl. 435-55.000.
- Quaker Oats Company, The: See—
Nagode, Larry R., 4,292,759, Cl. 46-205.000.
- Qualitron (PTY) Ltd.: See—
Hill, David A.; and Lomnitzer, Abraham, 4,293,072, Cl. 206-512.000.
- Rachlin, Schneur; and Arrigoni-Martelli, Edoardo, to Leo Pharmaceutical Products Ltd. A/S (Lovens Kemiske Fabrik Produktion-saktieselskab). Quinoliny guanidines having antiinflammatory, analgesic or antipyretic activity. 4,293,549, Cl. 424-245.000.
- Radakovich, Thomas: See—
Supcoe, Robert F.; and Radakovich, Thomas, 4,293,339, Cl. 106-18.290.
- Raden, Daniel S.; and Arbir, Francis W., to Abbott Laboratories. Process for rigid foams of improved friability. 4,293,658, Cl. 521-129.000.
- Radjukevich, Leonid V.: See—
Trishevsky, Igor S.; Trishevsky, Oleg I.; Bosy, Vladimir N.; Deber-deev, Rustem J.; Radjukevich, Leonid V.; Anisimov, Vyacheslav I.; Plesnetsov, Jury A.; and Chukhno, Valery V., 4,292,830, Cl. 72-197.000.
- Raetz, Karlheinz. Mixture control device for service water installations having a low supply temperature. 4,293,003, Cl. 137-637.400.
- Ragoza, Igor V.; Begunov, Petr M.; Tonikian, Robert T.; and Vasiljuk, Petr J. Method of and apparatus for knitting the heel of a hosiery article. 4,292,820, Cl. 66-8.000.
- Raible, Donald A.; Poticha, Stuart M.; and Stauffer, Rita. Fluid regulating device with torsional control. 4,292,969, Cl. 128-214.00R.
- Rainey, J. Montgomery; and Taylor, Francis M., to Systems Research Laboratories, Inc. Walking-gate ultrasonic flaw detector. 4,292,848, Cl. 73-602.000.
- Rambach, Claude, to Ormat Turbines, Ltd. Method of and means for passively cooling a shelter containing a heat source. 4,293,030, Cl. 165-40.000.
- Rancourt, James D.; and Seddon, Richard I., to Optical Coating Laboratory, Inc. Silicon solar cell and 350 nanometer cut-on filter for use therein. 4,293,732, Cl. 136-257.000.
- Randall, David I. Preparation of β -haloethylphosphonic acids and half esters thereof. 4,293,505, Cl. 260-983.000.
- Randel, Harry M. Take-up device speed controller using magnetic sensing means. 4,293,108, Cl. 242-189.000.
- Rank Xerox Limited: See—
Oka, Kozo, 4,293,630, Cl. 430-59.000.
- Rannenber, George C., to United Technologies Corporation. Variable geometry turbosupercharger system for internal combustion engine. 4,292,807, Cl. 60-601.000.
- Rao, Gude P.: See—
Petty, Terry D.; Costello, Carmon R.; Rao, Gude P.; and Gansar, David, 4,293,239, Cl. 405-195.000.

- Rapey, Kenneth: See—
George, Robert W.; Miller, Casper W.; and Rapey, Kenneth, 4,293,510, Cl. 264-40.700.
- Rasmussen, Ole-Bendt. Circular extrusion apparatus providing for rotation around the extrusion opening. 4,293,294, Cl. 425-112.000.
- Rau, Peter: See—
Goetzmann, Claus; and Rau, Peter, 4,293,381, Cl. 376-230.000.
- Rauscher, David A., to Cable Conveyor Systems, Inc. Sheave and method of providing same. 4,292,723, Cl. 29-402.010.
- Rauschert, Gerd: See—
Lakra, Ruhama J.; Freund, Jurgen; and Rauschert, Gerd, 4,293,383, Cl. 376-290.000.
- Raymond Engineering, Inc.: See—
Bickford, John H., 4,292,835, Cl. 73-1.00B.
- Raymond, Glendon A.; Honnold, Fred V.; and Spath, Herbert J., to Carrier Corporation. Co-axial fitting for use with a refrigeration circuit heat reclaim apparatus. 4,293,093, Cl. 237-19.000.
- Razus, Virgiliu T. Cereal dryer. 4,292,743, Cl. 34-65.000.
- RCA Corporation: See—
Chressanthis, Andrew G.; Halpern, Henry M.; and Gaffney, Brian P., 4,293,856, Cl. 343-5.0CF.
- D'Amato, Ralph J., 4,293,791, Cl. 313-403.000.
- Fitzgerald, William V., 4,293,803, Cl. 315-397.000.
- Paglione, Robert W., 4,292,960, Cl. 128-1.100.
- Roberts, Donald L., 4,293,792, Cl. 313-403.000.
- Siryj, Bohdan W.; Scott, Richard D.; and Horton, Charles R., 4,293,212, Cl. 354-299.000.
- Steckler, Steven A.; and Balaban, Alvin R., 4,293,870, Cl. 358-10.000.
- Thornhill, John, Jr.; and Elder, Richard B., 4,292,861, Cl. 74-813.00R.
- Read, Arthur E.: See—
Robey, Melvin J.; Bingaman, David E.; and Read, Arthur E., 4,293,237, Cl. 405-39.000.
- Reckitt & Colman Products Limited: See—
Fox, Rodney T., 4,293,312, Cl. 44-1.00R.
- Fox, Rodney T., 4,293,313, Cl. 44-1.00R.
- Reed, Ronald L.: See—
Gale, Walter W.; Puerto, Maura C.; Ashcraft, Thomas L.; Saunders, Rhoderick K.; and Reed, Ronald L., 4,293,428, Cl. 252-8.55D.
- Reed, Russell, Jr.: See—
Lee, Benjamin Y. S.; Reed, Russell, Jr.; and Miller, Roger L., 4,293,352, Cl. 149-19.400.
- Reed Tool Company: See—
Mayo, Terry H.; and Parrish, John D., 4,293,167, Cl. 308-8.200.
- Reese, Stanton L.; and Schroeder, William E., to Uranium Recovery Corporation. Process for recovering uranium from wet-process phosphoric acid using alkyl pyrophosphoric acid extractants. 4,293,529, Cl. 423-10.000.
- Regan, Michael T.: See—
Webster, Frank G.; Regan, Michael T.; and Rossi, Louis J., 4,293,626, Cl. 430-17.000.
- Regie Nationale des Usines Renault: See—
Vallade, Jean-Pierre, 4,292,937, Cl. 123-193.00P.
- Rehr, Henry W.: See—
Geyser, Joseph E.; Rehr, Henry W.; Schutz, Rudolph W.; and Weis, Rudolf R., 4,293,365, Cl. 156-364.000.
- Reinhard, Theodor; Krugener, Rolf; Kurth, Hermann W.; Blaich, Dieter; Rothmaier, Franz; Kopperschlager, Dieter; Schmitz, Heinz; and Nill, Edgar, to Daimler-Benz Aktiengesellschaft. Cylinder lock with plate tumblers. 4,292,823, Cl. 70-364.00R.
- Reischl, Artur, to Bayer Aktiengesellschaft. Process for the production of polyurethane plastics. 4,293,456, Cl. 260-9.000.
- Reitzenstein, Hermann. Apparatus for recovering sulfur from gases containing hydrogen sulfide. 4,293,525, Cl. 422-176.000.
- Reneau, Daniel L., to Zenith Radio Corporation. DC Restoration circuit for television receiver. 4,293,874, Cl. 358-172.000.
- Rens, Walter J.: See—
Heirbaut, Wilfried A.; and Rens, Walter J., 4,293,508, Cl. 264-25.000.
- Research Corporation: See—
Kay, David B.; Wheelless, Leon L., Jr.; and Cambier, James L., 4,293,221, Cl. 356-318.000.
- Research-Cottrell: See—
Robinson, James W., 4,293,320, Cl. 55-273.000.
- Resistoflex Corporation: See—
Press, Irving D., 4,293,150, Cl. 285-149.000.
- Retief, Andries; and Zovitsky, Gert J. Toy, 4,293,134, Cl. 273-428.000.
- Retterer, Ronald J.: See—
Baron, Martin; and Retterer, Ronald J., 4,293,133, Cl. 273-345.000.
- Reuber, August M. Portable oscillating-ring harrow. 4,293,042, Cl. 172-110.000.
- Rexnord Inc.: See—
Acheson, John L., 4,292,805, Cl. 60-450.000.
- Rezanka, Ivan: See—
Lindblad, Nero R.; Rezanka, Ivan; and Cassidy, John V., 4,292,924, Cl. 118-658.000.
- Rhau, Siegfried: See—
Weber, Adolf; and Rhau, Siegfried, 4,292,829, Cl. 72-76.000.
- Rhodes, Smith A., to Communications Satellite Corporation. Method and apparatus for encoding/decoding a convolutional code to a periodic convolutional code block. 4,293,951, Cl. 371-43.000.
- Rhone-Poulenc Industries: See—
Florent, Jean; Lunel, Jean; and Mancy, Denise, 4,293,650, Cl. 435-119.000.
- Gauthier-Lafaye, Jean; and Perron, Robert, 4,293,718, Cl. 568-487.000.
- Morel, Didier, 4,293,500, Cl. 260-410.90R.
- Richards Manufacturing Company, Inc.: See—
Shea, John J.; and Griggs, Calvin, 4,292,693, Cl. 3-1.900.
- Richardson-Vicks Inc.: See—
Mazzola, Mario, 4,292,995, Cl. 137-384.200.
- Richter, Joerg: See—
Boer, Werner; Lachner, Hans; Maschon, Guenter; Richter, Joerg; Schulte, Heinrich; and Warnke, Hans, 4,293,246, Cl. 405-291.000.
- Richter, Sidney B.; and Grove, William S., to PPG Industries, Inc. Process for preparing trichlorophenoxy alkanolic acid and hydrolyzable derivatives thereof free of chlorinated dibenzo-p-dioxins. 4,293,707, Cl. 562-472.000.
- Ricoh Co., Ltd.: See—
Hashimoto, Mitsuru; Ohta, Masafumi; Kozima, Akio; Sakai, Kiyoshi; and Sasaki, Masaomi, 4,293,628, Cl. 430-58.000.
- Isayama, Takuro, 4,293,867, Cl. 346-140.00R.
- Jinnai, Koichiro; Horike, Masanori; Iwasaki, Kyuhachiro; and Kodama, Yutaka, 4,293,865, Cl. 346-140.00R.
- Mori, Masaaki, 4,293,195, Cl. 350-358.000.
- Sasaki, Masaomi; Sakai, Kiyoshi; Hashimoto, Mitsuru; Ohta, Masafumi; and Tsutsui, Kyoji, 4,293,492, Cl. 260-160.000.
- Takita, Seiki; and Ichizuka, Kiyomi, 4,293,866, Cl. 346-140.00R.
- Riede, Gerhard; Larsson, Lars-Ake L.; Andersson, Roland J. E.; Jossion, Sven A.; and Traven, Lars J. C., to Gambro AB. Artificial kidney dialysate preparation system. 4,293,409, Cl. 210-96.200.
- Ringsdorf, Helmut: See—
Portugall, Michael; Finkelmann, Heino; and Ringsdorf, Helmut, 4,293,435, Cl. 252-299.010.
- Riquart, Christian; and Levrai, Roland, to Societe Anonyme DBA. Wheel cylinder. 4,292,883, Cl. 91-29.000.
- Ritsch, Charles J.: See—
Siebert, Lee S.; and Ritsch, Charles J., 4,292,913, Cl. 114-219.000.
- Ritter, Arnold. Methods of obtaining anorexic effects using a combination of amphetamines and cimetidine. 4,293,562, Cl. 424-273.00R.
- Ritter, Norman C.: See—
Niles, Gerald J.; and Ritter, Norman C., 4,293,102, Cl. 242-71.800.
- Rivier, Georges, to Orogil. Sulfurized metallic dithiophosphates and their use as additives for lubricating oils. 4,293,430, Cl. 252-32.70E.
- RM Fabrications Limited: See—
Metcalfe, Ronald S.; and Greig, John M., 4,293,147, Cl. 285-39.000.
- Robbins, Thomas R. Reactor and fuel assembly design for improved fuel utilization in liquid moderated thermal reactors. 4,293,380, Cl. 376-209.000.
- Robert Bosch GmbH: See—
Binder, Georg, 4,293,788, Cl. 310-227.000.
- Funk, Hans-Wolfgang; Frank, Kurt; and Flasche, Gunter, 4,293,790, Cl. 313-101.000.
- Heitmann, Jurgen; Maly, Hans-Peter; and Wilhelm, Rudolf, 4,293,879, Cl. 360-10.000.
- Kubach, Hans; and Rupp, Hartmann, 4,293,812, Cl. 323-272.000.
- Schumacher, Werner; and Schwerin, Gunther, 4,292,884, Cl. 91-445.000.
- Roberts, Donald L., to RCA Corporation. Color picture tube having improved slit type shadow mask. 4,293,792, Cl. 313-403.000.
- Roberts, Frank B., to Victor Products (Wallsend) Limited. Power supply systems. 4,293,799, Cl. 315-256.000.
- Robertshaw Controls Company: See—
Bauer, Werner R., 4,292,720, Cl. 29-157.10R.
- Robeson, Lloyd M.; Matzner, Markus; and Maresca, Louis M., to Union Carbide Corporation. Blends of poly(aryl ether) resins and polyetherimide resins. 4,293,670, Cl. 525-436.000.
- Robey, Melvin J.; Bingaman, David E.; and Read, Arthur E. Irrigation and drainage apparatus. 4,293,237, Cl. 405-39.000.
- Robins, Robert R. Tire holder and bead expander. 4,293,120, Cl. 254-50.200.
- Robinson, James A. L., to Syracuse Supply Company. Roll conveyor. 4,293,064, Cl. 198-779.000.
- Robinson, James W., to Research-Cottrell. High energy reverse air dust collector. 4,293,320, Cl. 55-273.000.
- Rockefeller University: See—
Merrifield, Robert B.; and Wong, Tai W., 4,293,455, Cl. 260-8.000.
- Rockwell International Corporation: See—
Bullinga, Lothar H., 4,293,850, Cl. 340-378.500.
- DeMichele, Glenn A., 4,293,817, Cl. 328-169.000.
- Glass, Howard L., 4,293,372, Cl. 156-624.000.
- Wagner, William R., 4,292,935, Cl. 123-285.000.
- Rody, Jean, to Ciba-Geigy AG. Malonate derivatives as stabilizers for organic materials. 4,293,468, Cl. 260-45.80N.
- Roeder, George K. Jet with variable throat areas using a deflector. 4,293,283, Cl. 417-172.000.
- Roesler, Helmut, to Siemens Aktiengesellschaft. Digital integrated semiconductor circuit. 4,293,780, Cl. 307-262.000.
- Roessler, Peter: See—
Hamprecht, Rainer; Hartmann, Alfons; Klauke, Erich; Hammann, Ingeborg; Roessler, Peter; and Brandes, Wilhelm, 4,293,566, Cl. 424-304.000.
- Rogan, Bruce R.: See—
Jaffe, Wolfgang; and Rogan, Bruce R., 4,293,837, Cl. 338-32.00H.
- Rogers, Basil E.: See—
Graybeal, Carl N.; Rogers, Basil E.; Cox, Joseph V.; and Rogers, Roy R., 4,293,243, Cl. 405-259.000.
- Rogers Corporation: See—
Miyajima, Masanobu, 4,293,377, Cl. 156-656.000.

- Rogers, Groby W., to Lawrence Security Services Ltd. Capacitive article removal alarm. 4,293,852, Cl. 340-568.000.
- Rogers, Leroy K., Sr. Method and apparatus for operating an engine on compressed gas. 4,292,804, Cl. 60-407.000.
- Rogers, Roy R.: See—
Graybeal, Carl N.; Rogers, Basil E.; Cox, Joseph V.; and Rogers, Roy R., 4,293,243, Cl. 405-259.000.
- Rogora, Edoardo: See—
Bertoloni, Luciano; Rogora, Edoardo; and Cressoni, Ermanno, 4,293,843, Cl. 340-52.00F.
- Rohco, Inc.: See—
Canaris, Valerie M., 4,293,391, Cl. 204-50.00R.
- Rohm GmbH: See—
Fink, Herbert; Huebner, Klaus; Dinklage, Horst; and Ottofrickenstein, Hans, 4,293,600, Cl. 427-385.500.
- Monsheimer, Rolf; and Pfeiderer, Ernst, 4,293,647, Cl. 435-69.000.
- Rohm and Haas Company: See—
Kosaka, Kenji; Iwatsuka, Takeshi; Shindo, Ikuo; and Hotogi, Akira, 4,293,423, Cl. 210-676.000.
- Rohr Industries, Inc.: See—
Prior, Barry, 4,292,803, Cl. 60-230.000.
- Romanov, Viktor I.; Kirzner, Felix I.; and Soroka, Yakov K. Axial-flow reversible turbine. 4,293,273, Cl. 415-78.000.
- Ronbeck, Arne I., to AB Volvo. Device for translating a movement in one plane to a movement in a plane essentially perpendicular thereto. 4,293,271, Cl. 414-737.000.
- Roper Corporation: See—
Davis, Robert K.; and Myers, Michael J., 4,293,835, Cl. 335-131.000.
- Rosborough, Robert S., Jr.; and Wright, Luther M., deceased (by Lang, Edna B., nee Wright executrix), to Eastman Kodak Company. Print inspection and packaging method and apparatus. 4,293,215, Cl. 355-40.000.
- Rose, Bernard R.; and Willis, John K., to Walbar Metals, Inc. Diffusion coating composition of improved flowability. 4,293,338, Cl. 75-253.000.
- Rosenberg, Harry; and Holken, Norbert, to Gewerkschaft Eisenhutte Westfalia. Seals for mine roof supports. 4,293,247, Cl. 405-296.000.
- Ross, Bernd. Screenable contact structure and method for semiconductor devices. 4,293,451, Cl. 252-512.000.
- Ross, William J.: See—
Jamieson, William B.; Ross, William J.; Simmonds, Robin G.; and Verge, John P., 4,293,563, Cl. 424-273.00R.
- Rossi, Louis J.: See—
Webster, Frank G.; Regan, Michael T.; and Rossi, Louis J., 4,293,626, Cl. 430-17.000.
- Rothmaier, Franz: See—
Reinhard, Theodor; Krugener, Rolf; Kurth, Hermann W.; Blaich, Dieter; Rothmaier, Franz; Kopperschlager, Dieter; Schmitz, Heinz; and Nill, Edgar, 4,292,823, Cl. 70-364.00R.
- Rottmaier, Ludwig; Merten, Rudolf; Lewalter, Jurgen; Zecher, Wilfried; and Dunwald, Willi, to Bayer Aktiengesellschaft. Heat-resistant cross-linked polymers and the use thereof as binders. 4,293,669, Cl. 525-452.000.
- Rowe, Edward A., Jr.: See—
Borror, Jack A.; and Rowe, Edward A., Jr., 4,293,433, Cl. 336-94.000.
- Roy, Denis R. J.: See—
Teller, Aaron J.; Roy, Denis R. J.; and Lin, Shih K., 4,293,524, Cl. 422-169.000.
- Royer, George R., to Weithman, John A., a part interest. Safety cover for electrical outlets. 4,293,733, Cl. 174-67.000.
- Rozmus, Edward: See—
Pretor, Wincenty; Rozmus, Edward; Korecki, Zbigniew; and Karmanski, Stanislaw, 4,293,248, Cl. 405-300.000.
- Rubenstein, Irving H., to Maryland Cup Corporation. Frozen fruit and vegetable juices. 4,293,580, Cl. 426-565.000.
- Ruedi, Joseph: See—
Streuli, Hans; and Ruedi, Joseph, 4,293,410, Cl. 210-107.000.
- Ruhl, Hermann. Variable acceleration monitoring system. 4,293,844, Cl. 340-52.00R.
- Rumphorst, Jacobus A.: See—
Felthuis, Jacob; and Rumphorst, Jacobus A., 4,292,993, Cl. 137-340.000.
- Rupp, Hartmann: See—
Kubach, Hans; and Rupp, Hartmann, 4,293,812, Cl. 323-272.000.
- Ruth, Richard L.: See—
Huang, Victor K.; and Ruth, Richard L., 4,293,907, Cl. 364-200.000.
- Ryan, James M.; and Holmes, Arthur S., to Helix Technology Corporation. Distillate separation of carbon dioxide from hydrogen sulfide. 4,293,322, Cl. 62-17.000.
- Ryman Engineering Company: See—
Fatula, James J., 4,292,767, Cl. 51-145.00R.
- Saeman, Walter C., to Olin Corporation. Process for the production of layered glass batch pellets. 4,293,324, Cl. 65-27.000.
- Saft-Societe des Accumulateurs Fixes et de Traction: See—
Godard, Pierre; and Geoffroy, Jean-Claude, 4,293,029, Cl. 165-29.000.
- St. Lawrence, David S.; Morris, Robert; and Farrar, James G., to Sensormatic Electronics Corporation. Anti-theft security enclosure and releasing mechanism. 4,293,266, Cl. 414-411.000.
- Saint Peter's Research Trust Limited: See—
Simpson, Roger J.; Gawthorpe, Janet A.; and Lawrence, C. Alexander, 4,293,307, Cl. 23-230.00B.
- Saito, Akinori: See—
Tanasawa, Yasuji; Muto, Norio; Saito, Akinori; and Kawamura, Kiyomi, 4,292,947, Cl. 123-445.000.
- Saito, Shoichi: See—
Shirako, Hideo; and Saito, Shoichi, 4,293,885, Cl. 360-130.330.
- Saito, Tsuyoshi: See—
Asano, Kiro; Tamura, Humio; Nezu, Yushi; Saito, Tsuyoshi; and Kawai, Yoshio, 4,293,533, Cl. 423-449.000.
- Sakaguchi, Shinji: See—
Takahashi, Osamu; and Sakaguchi, Shinji, 4,293,641, Cl. 430-502.000.
- Sakai, Kiyoshi: See—
Hashimoto, Mitsuru; Ohta, Masafumi; Kozima, Akio; Sakai, Kiyoshi; and Sasaki, Masaomi, 4,293,628, Cl. 430-58.000.
- Sasaki, Masaomi; Sakai, Kiyoshi; Hashimoto, Mitsuru; Ohta, Masafumi; and Tsutsui, Kyoji, 4,293,492, Cl. 260-160.000.
- Sakamoto, Takeshi: See—
Kobayashi, Nariyoshi; Sakamoto, Takeshi; Anzai, Shunichi; and Matsumoto, Manabu, 4,293,275, Cl. 416-97.00R.
- Sakuma, Hideki: See—
Shibata, Kenyu; Itaya, Toshihisa; Yamakoshi, Nobuaki; Kurata, Shigeru; Koizumi, Naoyuki; Tarutani, Masaaki; Sakuma, Hideki; and Konishi, Kunihiro, 4,293,557, Cl. 424-267.000.
- Sakuma, Shinzo; and Yanagisawa, Hifumi, to Kabushiki Kaisha Meiden-sha; and Kabushiki Kaisha GEMVAC. Vacuum circuit interrupter electrodes. 4,293,748, Cl. 200-144.00B.
- Salete-Garces, Felipe. Grain polishing and whitening machine. 4,292,890, Cl. 99-603.000.
- Samarin, Alexei P.: See—
Dunaevsky, Vladimir I.; Boidenko, Nikolai G.; Samarin, Alexei P.; Levit, Viktor M.; Zapara, Boris M.; Ivanov, Boris N.; Frolov, Sergei A.; Voronin, Rostislav A.; Belozero, Nikolai P.; Momot, Valery I.; Stusenko, Jury A.; and Samoilov, Vladimir A., 4,293,101, Cl. 242-56.400.
- Samejima, Yasushi: See—
Iijima, Tokuzo; Samejima, Yasushi; Kishimoto, Kazuo; Komaba-shiri, Takamichi; and Kano, Toshiji, 4,293,395, Cl. 204-98.000.
- Samoilov, Vladimir A.: See—
Dunaevsky, Vladimir I.; Boidenko, Nikolai G.; Samarin, Alexei P.; Levit, Viktor M.; Zapara, Boris M.; Ivanov, Boris N.; Frolov, Sergei A.; Voronin, Rostislav A.; Belozero, Nikolai P.; Momot, Valery I.; Stusenko, Jury A.; and Samoilov, Vladimir A., 4,293,101, Cl. 242-56.400.
- San-O Industrial Co., Ltd.: See—
Arikawa, Hiroo, 4,293,836, Cl. 337-290.000.
- Sanchez, Jacinto. Image projector for a television receiver. 4,293,878, Cl. 358-231.000.
- Sanders, James M.: See—
Sprecker, Mark A.; Sanders, James M.; Schreiber, William L.; Watkins, Hugh; Vinals, Joaquin F.; Shuster, Edward J.; O'Rourke, Thomas J.; Hagedorn, Myrna L.; and Klemarczyk, Philip, 4,293,453, Cl. 252-522.00R.
- Sandler, Stanley R.: See—
Monsimer, Harold G.; and Sandler, Stanley R., 4,293,454, Cl. 252-609.000.
- Sandor, Robert P.: See—
Tepe, James R.; Sandor, Robert P.; Wesselman, Bernard W.; and Woeste, David R., 4,293,027, Cl. 165-12.000.
- Sandstone, Inc.: See—
Williams, William H., 4,293,778, Cl. 307-147.000.
- Sandstrom, Anders; and Aucktor, Erich, to Scatra Ab. Flexibly mounted drive arrangement for ships. 4,293,304, Cl. 440-83.000.
- Sanner, Bert: See—
Krause, Heinz; and Sanner, Bert, 4,292,977, Cl. 128-712.000.
- Sanner, George E. Luminaire. 4,293,899, Cl. 362-294.000.
- Sanol Schwarz-Monheim GmbH: See—
Cordes, Gunter; Giesselmann, Ewald; and Munch, Ulrich, 4,293,565, Cl. 424-285.000.
- Santer, J. Owen: See—
Strazik, William F.; LeBlanc, John R.; and Santer, J. Owen, 4,293,461, Cl. 260-18.00N.
- Sanyo Electric Co., Ltd.: See—
Kakinuma, Mitsuru; and Takahashi, Yoshitaka, 4,292,812, Cl. 62-157.000.
- SAPAL Societe Anonyme des Plieuses Automatiques: See—
Pongracz, Endre, 4,293,774, Cl. 250-548.000.
- Sasa, Syozo: See—
Nagano, Katsuto; Ihaya, Kazuhiko; Sasa, Syozo; and Nakada, Takeshi, 4,293,370, Cl. 156-612.000.
- Sasaki, Hiromi; and Takahara, Yoshiyuki, to Central Glass Company, Limited. Process for producing hydrogen chloride and ammonia. 4,293,532, Cl. 423-356.000.
- Sasaki, Ken: See—
Toriyama, Kazuhisa; Hata, Tsujiaki; Hasegawa, Shinji; and Sasaki, Ken, 4,293,698, Cl. 546-301.000.
- Sasaki, Koji: See—
Kishi, Tuneso; and Sasaki, Koji, 4,293,749, Cl. 200-144.00A.P.
- Sasaki, Masaomi; Sakai, Kiyoshi; Hashimoto, Mitsuru; Ohta, Masafumi; and Tsutsui, Kyoji, to Ricoh Co., Ltd. Disazo compounds derived from 3,6-bis(styryl)-9-ethylcarbazole. 4,293,492, Cl. 260-160.000.
- Sasaki, Masaomi: See—
Hashimoto, Mitsuru; Ohta, Masafumi; Kozima, Akio; Sakai, Kiyoshi; and Sasaki, Masaomi, 4,293,628, Cl. 430-58.000.

- Sasaki, Shosaku; and Kaiya, Nobuo, to Toray Silicone Company, Ltd. Organopolysiloxane composition for preparing peelable film. 4,293,671, Cl. 525-478.000.
- Sasaki, Yukio: See—
Sugio, Akitoshi; Masu, Masanobu; Nakai, Hiroshi; and Sasaki, Yukio, 4,293,478, Cl. 260-37.00R.
- Sassmann, Stanley W., to Farmstead Industries, Div. of Farmhand, Inc. Swine shelter ventilating system. 4,292,927, Cl. 119-16.000.
- Sato, Masaki: See—
Ito, Motoya; Sato, Masaki; Watanabe, Masatoshi; and Okuda, Hironori, 4,293,787, Cl. 310-181.000.
- Sato, Masanobu; and Satoh, Ken, to Olympus Optical Company Limited. Microphone device. 4,293,742, Cl. 179-178.000.
- Sato, Tadashi: See—
Minoura, Kazuo; Sugiyama, Muneharu; Minami, Setsuo; and Sato, Tadashi, 4,293,184, Cl. 350-6.300.
- Sato, Yasuhiko; and Inomata, Hiroshi, to Shin-Etsu Chemical Co., Ltd. Photocurable organopolysiloxane compositions. 4,293,397, Cl. 204-159.130.
- Sato, Yo, to Kabushiki Kaisha Sato Kenkyusho. Constant printing pressure mechanisms for label printing machine. 4,292,894, Cl. 101-291.000.
- Satoh, Ken: See—
Sato, Masanobu; and Satoh, Ken, 4,293,742, Cl. 179-178.000.
- Satterfield, H. Eugene: See—
Fogg, Lewis W.; Metzler, Robert W.; Satterfield, H. Eugene; and Scott, Eion G., 4,292,762, Cl. 47-17.000.
- Sauer, Fried, to Klockner-Humboldt-Deutz AG. Blow lance. 4,293,123, Cl. 266-268.000.
- Saunders, Rhoderick K.: See—
Gale, Walter W.; Puerto, Maura C.; Ashcraft, Thomas L.; Saunders, Rhoderick K.; and Reed, Ronald L., 4,293,428, Cl. 252-8.55D.
- Savio, Ferdinando; and Peterson, William, to Grumman Aerospace Corporation. Work support for forming laminations. 4,293,361, Cl. 156-242.000.
- Sawa, Hiroshi; and Yamauchi, Yukio, to Hochiki Corporation. Temperature detecting device. 4,292,844, Cl. 73-359.00A.
- Sawa, Yoichi; Kawakami, Yoshiyuki; and Marumoto, Ryuji, to Takeda Chemical Industries, Ltd. Production of 2,6-diaminonebularines. 4,293,690, Cl. 536-24.000.
- Sawada, Hideo; Shinohara, Koji; and Shiga, Makoto, to Daicel Ltd. Filter for cigarette smoke. 4,292,984, Cl. 131-345.000.
- Sawada, Hiroomi: See—
Yamauchi, Toshima; Nogami, Sadao; Sawada, Kengi; Moriya, Jyunichiro; Sawada, Hiroomi; and Kobayashi, Keizou, 4,292,973, Cl. 128-303.100.
- Sawada, Kengi: See—
Yamauchi, Toshima; Nogami, Sadao; Sawada, Kengi; Moriya, Jyunichiro; Sawada, Hiroomi; and Kobayashi, Keizou, 4,292,973, Cl. 128-303.100.
- Sawada, Yoshio: See—
Aoki, Harumi; Kawasaki, Masahiro; and Sawada, Yoshio, 4,293,207, Cl. 354-25.000.
- Sawano, Susumu: See—
Izumita, Morishi; Maeda, Takeshi; Tsunoda, Yoshito; and Sawano, Susumu, 4,293,944, Cl. 369-45.000.
- Scandella, Louis, to Stanley Mabo, S.A. Universal level vial holder. 4,292,741, Cl. 33-379.000.
- Scandia Packaging Machinery Co.: See—
Anderson, Andrew W., 4,293,067, Cl. 198-851.000.
- Scatra Ab: See—
Sandstrom, Anders; and Aucktor, Erich, 4,293,304, Cl. 440-83.000.
- Schaeffer, Jack A., to Dana Corporation. Sheet metal structural beam. 4,292,782, Cl. 52-696.000.
- Schafer, Dieter: See—
Ledebrink, Friedrich-Wilhelm; Stoll, Wolfgang; and Schafer, Dieter, 4,293,438, Cl. 252-301.10W.
- Schaub, Robert E.: See—
Bernady, Karel F.; Floyd, Middleton B., Jr.; Poletto, John F.; Schaub, Robert E.; and Weiss, Martin J., 4,293,704, Cl. 556-442.000.
- Scheible, Clement E.: See—
Silva, Roy; Ash, David J.; and Scheible, Clement E., 4,293,572, Cl. 426-19.000.
- Schickflus, Rudolf: See—
Hoyer, Ernst; Steckelberg, Willi; Deucker, Walter; and Schickflus, Rudolf, 4,293,306, Cl. 8-471.000.
- Schiller, Edward, to Ampex Corporation. Multiple leg magnetic transducer structure. 4,293,884, Cl. 360-121.000.
- Schirbach, Arno: See—
Luhleisch, Hartmut; Pflaum, Peter; Dias, Francisco J.; Nauomidis, Aristides; Schirbach, Arno; and Nickel, Hubertus, 4,293,512, Cl. 264-58.000.
- Schlumberger Technology Corporation: See—
Bell, William T.; and Garcia, Jose B., 4,292,895, Cl. 102-306.000.
- Park, Sung K.; and Kenyon, William E., 4,293,933, Cl. 367-25.000.
- Schmitz, Heinz: See—
Reinhard, Theodor; Krugener, Rolf; Kurth, Hermann W.; Blaich, Dieter; Rothmaier, Franz; Kopperschlager, Dieter; Schmitz, Heinz; and Nill, Edgar, 4,292,823, Cl. 70-364.00R.
- Schmitz, Rolf, to Jagenberg Werke. Apparatus for introducing the head end of a web into a treating station. 4,293,087, Cl. 226-172.000.
- Schnell, William J., to Baxter Travenol Laboratories, Inc. Dialyzer blood circuit and bubble traps. 4,293,413, Cl. 210-188.000.
- Schoen, Ernst: See—
Nissen, Dietmar; Marx, Matthias; Jarre, Wolfgang; Schoen, Ernst; and Decker, Walter, 4,293,657, Cl. 521-121.000.
- Schoenfeld, Palmer J.: See—
Kuna, Wayne A.; Thibault, James G.; and Schoenfeld, Palmer J., 4,292,758, Cl. 46-93.000.
- Scholz, Werner, to TED Bildplatten Aktiengesellschaft. Circuit for reducing drop-out errors in a video signal derived from a recording device. 4,293,869, Cl. 358-8.000.
- Schonnmann, Gerhard: See—
Sommer, Klaus; Klemm, Walter; Weber, Hermann; Meinhardt, Frederich; Schonnmann, Gerhard; and Spatz, Wilhelm, 4,293,526, Cl. 422-205.000.
- Schossow, George W. Gas burner system. 4,292,950, Cl. 126-110.00A.
- Schreiber, William L.: See—
Sprecker, Mark A.; Sanders, James M.; Schreiber, William L.; Watkins, Hugh; Vinals, Joaquin F.; Shuster, Edward J.; O'Rourke, Thomas J.; Hagedorn, Myrna L.; and Klemarczyk, Philip, 4,293,453, Cl. 252-522.00R.
- Schrinner, Elmar: See—
Blumbach, Jurgen; Durckheimer, Walter; and Schrinner, Elmar, 4,293,550, Cl. 424-246.000.
- Schroeder, William E.: See—
Reese, Stanton L.; and Schroeder, William E., 4,293,529, Cl. 423-10.000.
- Schubert, Herrmann: See—
Deutscher, Hans-Joachim; Schubert, Herrmann; Seidel, Christina; Demus, Dietrich; and Kresse, Horst, 4,293,434, Cl. 252-299.630.
- Schuegraf, Eberhard, to Siemens Aktiengesellschaft. Polarization separator. 4,293,829, Cl. 333-125.000.
- Schulte, Heinrich: See—
Boer, Werner; Lachner, Hans; Maschon, Guenter; Richter, Joerg; Schulte, Heinrich; and Warnke, Hans, 4,293,246, Cl. 405-291.000.
- Schumacher, Werner; and Schwerin, Gunther, to Robert Bosch GmbH. Control arrangement for a hydraulically operated device. 4,292,884, Cl. 91-445.000.
- Schurger, Rainer: See—
Ernst, Horst M.; Olschewski, Armin; Schurger, Rainer; Walter, Lothar; Brandenstein, Manfred; and Burkl, Erich, 4,293,166, Cl. 308-6.00C.
- Schutz, Rudolph W.: See—
Geyser, Joseph E.; Rehr, Henry W.; Schutz, Rudolph W.; and Weis, Rudolf R., 4,293,365, Cl. 156-364.000.
- Schwartz, Lawrence, to International Telephone and Telegraph Corporation. Electrical connector body and method of making same. 4,293,182, Cl. 339-275.00R.
- Schwarz, Klaus: See—
Feuerstake, Ewald; and Schwarz, Klaus, 4,293,775, Cl. 250-535.000.
- Schweig, Helmut; and von Bassewitz, Henning, to Messerschmitt-Boelkow-Blohm Gesellschaft mit beschraenkter Haftung. Solar generator, especially for space craft. 4,293,731, Cl. 136-245.000.
- Schwerdtel, Wulf: See—
Waldmann, Helmut; Schwerdtel, Wulf; and Swodenk, Wolfgang, 4,293,717, Cl. 568-485.000.
- Schwerin, Gunther: See—
Schumacher, Werner; and Schwerin, Gunther, 4,292,884, Cl. 91-445.000.
- Schwerko, Albert P.: See—
Herrington, Daniel R.; and Schwerko, Albert P., 4,293,449, Cl. 252-465.000.
- Schwinn Bicycle Company: See—
Brilando, Frank, 4,293,141, Cl. 280-281.00R.
- SCI Systems, Inc.: See—
Hoffman, Mark H., 4,293,233, Cl. 400-144.200.
- Scientific Advances, Inc.: See—
Hassler, Craig R.; and Messing, Gary L., 4,293,302, Cl. 433-173.000.
- Scifres, Donald R.; Burnham, Robert D.; and Streifer, William, to Xerox Corporation. Hybrid semiconductor laser/detectors. 4,293,826, Cl. 331-94.50H.
- SCM Corporation: See—
Cardenas, Carlos G.; and Din, Zia U., 4,293,497, Cl. 260-345.500.
- Scott, Eion G.: See—
Fogg, Lewis W.; Metzler, Robert W.; Satterfield, H. Eugene; and Scott, Eion G., 4,292,762, Cl. 47-17.000.
- Scott Paper Company: See—
Loft, Fredrick A.; and Peterson, John O. H., 4,293,360, Cl. 156-230.000.
- Scott, Richard D., to United States of America, Army. Laser scanner transport. 4,293,864, Cl. 346-76.00L.
- Scott, Richard D.: See—
Siriy, Bohdan W.; Scott, Richard D.; and Horton, Charles R., 4,293,212, Cl. 354-299.000.
- Seaton, Norman T. Method and apparatus for controlling resonant frequency of an optical interferometer cavity. 4,293,223, Cl. 356-352.000.
- Seco Tools AB: See—
Anderson, Kjell, 4,293,251, Cl. 408-59.000.
- Seddon, Richard I.: See—
Rancourt, James D.; and Seddon, Richard I., 4,293,732, Cl. 136-257.000.
- Sederquist, Richard A., to United Technologies Corporation. Reaction apparatus for producing a hydrogen containing gas. 4,293,315, Cl. 48-94.000.
- Seely, John H., to Abbott Laboratories. Method of producing 3-O-demethylfortimicin B from fortimicin AN. 4,293,689, Cl. 536-17.00R.

- Segawa, Hiroshi; and Akizuki, Katsufumi, to Denpatsu Fly Ash. Apparatus for producing potassium silicate fertilizer. 4,293,523, Cl. 422-139.000.
- Seidel, Christina: See—
Deutscher, Hans-Joachim; Schubert, Herrmann; Seidel, Christina; Demus, Dietrich; and Kresse, Horst, 4,293,434, Cl. 252-299.630.
- Seiko Koki Kabushiki Kaisha: See—
Ogihara, Masuo; Chimura, Kozo; Shinozaki, Nobuo; and Seki, Yoichi, 4,293,938, Cl. 368-72.000.
- Seki, Yoichi: See—
Ogihara, Masuo; Chimura, Kozo; Shinozaki, Nobuo; and Seki, Yoichi, 4,293,938, Cl. 368-72.000.
- Sekine, Mitsuo: See—
Nishikubo, Yasuhiko; and Sekine, Mitsuo, 4,293,939, Cl. 368-74.000.
- Sekino, Masaaki; Chikanari, Kenichi; and Taniyama, Tsukasa, to Toyo Boseki Kabushiki Kaisha. Hollow fiber membrane separation apparatus. 4,293,419, Cl. 210-321.100.
- Selenia Industrie Elettroniche Associate S.p.A.: See—
Cerra, Raffaele, 4,293,825, Cl. 331-2.000.
- Sellers, Larry S.: See—
Davis, Gayron N.; Sellers, Larry S.; and Hagborg, Winston E., 4,292,918, Cl. 118-33.000.
- Semco Instruments, Inc.: See—
Moore, M. Samuel; and Paluka, Charles F., 4,292,806, Cl. 60-600.000.
- Senni, Paolo; and Astarita, Domenico, to Snia Viscosa S.p.A. Method for the purification of raw caprolactam which contains amides and other by-products. 4,293,494, Cl. 260-239.30A.
- Sensomatic Electronics Corporation: See—
St. Lawrence, David S.; Morris, Robert; and Farrar, James G., 4,293,266, Cl. 414-411.000.
- Sentance, Christopher B., to Effem Foods Pty. Ltd. Food product and process of manufacture. 4,293,576, Cl. 426-104.000.
- Sentralinstitut for Industriell Forskning: See—
Ersoy, Olan K., 4,293,183, Cl. 350-3.770.
- Sergent, Edward W., to M. P. H. Industries, Inc. Traffic radar unit. 4,293,859, Cl. 343-702.000.
- Serini, Volker: See—
Weissel, Oskar; Serini, Volker; and Buysch, Hans-Josef, 4,293,687, Cl. 528-346.000.
- Seto, Nobuo: See—
Furutachi, Nobuo; and Seto, Nobuo, 4,293,691, Cl. 544-140.000.
- Setree, Robert R., II. Device for lubricating a hub with bearings. 4,293,056, Cl. 184-1.00D.
- Sexsmith, Frederick H.: See—
Zalucha, Denis J.; Sexsmith, Frederick H.; Hornaman, Ernest C.; and Dawdy, Terrance H., 4,293,665, Cl. 525-255.000.
- SGS-ATES Componenti Elettronici S.p.A.: See—
Murari, Bruno; and Siligoni, Marco, 4,293,824, Cl. 330-301.000.
- Shakertown Corporation: See—
Barker, Craig S.; and Bockwinkel, Joe L., 4,292,780, Cl. 52-541.000.
- Shamp, Donald E.: See—
Gills, Richard G.; Hille, Earl A.; Kleine, Albert W., Jr.; and Shamp, Donald E., 4,293,264, Cl. 414-38.000.
- Shannon, Richard F., to Owens-Corning Fiberglass Corporation. Mortars and cements having improved freeze-thaw properties and method of achieving same. 4,293,343, Cl. 106-99.000.
- Shapira, Hanna B.: See—
Barnes, Paul R.; and Shapira, Hanna B., 4,292,763, Cl. 49-64.000.
- Shapiro, Alexandr I.: See—
Kopylov, Alexei A.; Kuzmenko, Valentin T.; Stepanov, Alexandr N.; Gaschenko, Viktor P.; Kaznacheevsky, Nikolai A.; Nosovitsky, Alexandr Y.; Misikov, Ivan I.; Shapiro, Alexandr I.; Skakunov, Ivan G.; Markin, Valentin G.; Konstantinov, Alexei K.; Abramian, Eduard S.; Soroka, Arseny M.; and Zinchenko, Yakov A., 4,292,928, Cl. 119-17.000.
- Sharlow, Roger C., to Liquid Paper Corporation. Apparatus for ganging and cutting a plurality of layers of strip material. 4,293,100, Cl. 242-55.000.
- Sharp, H. Eugene; Vela, Octavio A.; and Smither, Mils A., to Sperry-Sun, Inc. Borehole acoustic telemetry system. 4,293,937, Cl. 367-82.000.
- Sharp Kabushiki Kaisha: See—
Itogawa, Ziro; and Aoto, Yoshiyuki, 4,292,985, Cl. 132-9.000.
- Komaki, Shigeki, 4,293,754, Cl. 200-340.000.
- Oonishi, Souichi, 4,293,911, Cl. 364-405.000.
- Shaw, Arthur G.: See—
Swisher, George W., Jr.; Garbelman, David L.; and Shaw, Arthur G., 4,293,228, Cl. 366-25.000.
- Shaw, I-Sine: See—
Wang, Wei Ko; Hoh, Ying-Chu; Chuang, Wen-Shou; and Shaw, I-Sine, 4,293,332, Cl. 75-99.000.
- Shaw, Michael J.; and Thiessen, Robert J., to Allied Paper Incorporated. Electrostatic master and method for making the same. 4,293,629, Cl. 430-64.000.
- Shea, John J.; and Griggs, Calvin, to Richards Manufacturing Company, Inc. Locking ball stapedial prosthesis. 4,292,693, Cl. 3-1.900.
- Shearer, Marcia C.: See—
Nash, Claude H., III; Shearer, Marcia C.; Snader, Kenneth M.; Valenta, Joseph R.; and Cooper, David, 4,293,546, Cl. 424-119.000.
- Shell Oil Company: See—
Herolz, Robert A.; and Vogel, Charles B., 4,293,934, Cl. 367-27.000.
- Jackson, Roy J., 4,293,672, Cl. 525-507.000.
- Slaugh, Lynn H., 4,293,723, Cl. 585-407.000.
- Shelledy, Carey W.: See—
Winegard, John R.; Shelledy, Carey W.; and Cowan, Keith B., 4,293,861, Cl. 343-766.000.
- Shelley, James D. Aluminum can crusher. 4,292,891, Cl. 100-193.000.
- Shen, Jian-Kuo: See—
Bradley, John J.; Holtey, Thomas O.; Miller, Robert C.; Miu, Ming T.; Shen, Jian-Kuo; and Staplin, Theodore R., Jr., 4,293,908, Cl. 364-200.000.
- Shepard, Steve A.: See—
Haag, George A.; Fogg, O. Douglas; Greenley, Gordon A.; Shepard, Steve A.; and Terry, F. Duncan, 4,293,925, Cl. 364-900.000.
- Shewmaker, James E., to Exxon Research & Engineering Co. Method for removing oil-based materials from water surface. 4,293,348, Cl. 134-22.00R.
- Shibata, Kenyu; Itaya, Toshihisa; Yamakoshi, Nobuaki; Kurata, Shigeru; Koizumi, Naoyuki; Tarutani, Masaaki; Sakuma, Hideki; and Konishi, Kunihiro, to Teikoku Hormone Mfg. Co., Ltd. Antiulcer phenoxypyrrolamine derivatives. 4,293,557, Cl. 424-267.000.
- Shibayama, Akinori; Maio, Kenji; and Yokozawa, Norio, to Nippon Telegraph and Telephone Public Corporation; and Hitachi, Ltd. High-speed low-drift operational amplifier. 4,293,819, Cl. 330-9.000.
- Shields, Walter. Apparatus for inverting and transporting articles. 4,293,063, Cl. 198-404.000.
- Shiga, Makoto: See—
Sawada, Hideo; Shinohara, Koji; and Shiga, Makoto, 4,292,984, Cl. 131-345.000.
- Shikita, Takuji; and Hirabayashi, Masaya, to Kyoto Ceramic Co., Ltd. Granular ceramic carrier for administration of medicines and medicine supported therein. 4,293,540, Cl. 424-26.000.
- Shimaguchi, Takashi: See—
Nakae, Hideo; Ozaki, Toshinori; Shimaguchi, Takashi; and Morimoto, Syogo, 4,292,832, Cl. 72-365.000.
- Shimizu, Masao; Tokuno, Takashi; Ishikawa, Kohji; Narumi, Naoki; and Ohguchi, Osamu, to Nippon Telegraph and Telephone Public Corporation; and Takeda Riken Kogyo Kabushiki Kaisha. Test pattern generating apparatus. 4,293,950, Cl. 371-21.000.
- Shimizu, Munetaka, to Copal Company Limited. Printer. 4,293,236, Cl. 400-593.000.
- Shimizu, Shinkichi; Nishizaki, Tadao; and Tsuda, Masabumi, to Sumitomo Chemical Company, Limited. Method for production of molded product containing titanium oxide. 4,293,445, Cl. 252-438.000.
- Shin-Etsu Chemical Co., Ltd.: See—
Fukuda, Takeshi; and Tutida, Tomiyoshi, 4,293,201, Cl. 351-178.000.
- Imada, Kiyoshi; Ueno, Susumu; Nishina, Yasuhide; and Nomura, Hirokazu, 4,293,585, Cl. 427-40.000.
- Sato, Yasuhiko; and Inomata, Hiroshi, 4,293,397, Cl. 204-159.130.
- Shinbashi, Suet: See—
Matsui, Kiyoshi; Arai, Katsuyuki; and Shinbashi, Suet, 4,293,891, Cl. 361-383.000.
- Shindo, Ikuo: See—
Kosaka, Kenji; Iwatsuka, Takeshi; Shindo, Ikuo; and Hotogi, Akira, 4,293,423, Cl. 210-676.000.
- Shinmi, Hideo: See—
Hanada, Tsuneo; Koshii, Taro; and Shinmi, Hideo, 4,293,479, Cl. 260-37.0EP.
- Shinohara, Koji: See—
Sawada, Hideo; Shinohara, Koji; and Shiga, Makoto, 4,292,984, Cl. 131-345.000.
- Shinozaki, Nobuo: See—
Ogihara, Masuo; Chimura, Kozo; Shinozaki, Nobuo; and Seki, Yoichi, 4,293,938, Cl. 368-72.000.
- Shionogi & Co., Ltd.: See—
Yukinaga, Hisajiro; Sumimoto, Shinzaburo; Ishizuka, Ichiro; and Sugita, Jitsuo, 4,293,328, Cl. 71-88.000.
- Shirai, Hitoshi: See—
Tanaka, Yoshikazu; Shirai, Hitoshi; and Kan'o, Yoshiharu, 4,293,931, Cl. 365-222.000.
- Shirako, Hideo; and Saito, Shoichi. Pad spring for a tape cassette. 4,293,885, Cl. 360-130.330.
- Shoei Chemical Incorporated: See—
Asada, Eiichi; Inokuma, Toshio; and Egawa, Isao, 4,293,839, Cl. 338-309.000.
- Shu, Chi-Kuen; Mookherjee, Braja D.; and Vock, Manfred H., to International Flavors & Fragrances Inc. Flavoring with 3,5-di-(2-methylpropyl)-1,2,4-trithiolane. 4,293,579, Cl. 426-535.000.
- Shuster, Edward J.: See—
Sprecker, Mark A.; Sanders, James M.; Schreiber, William L.; Watkins, Hugh; Vinals, Joaquin F.; Shuster, Edward J.; O'Rourke, Thomas J.; Hagedorn, Myrna L.; and Klemarczyk, Philip, 4,293,453, Cl. 252-522.00R.
- Shuster, Frank A.: See—
Kroll, Arthur S.; and Shuster, Frank A., 4,292,921, Cl. 118-648.000.
- Shuttleworth, Richard G.; and Snyder, Gene R., to United Technologies Corporation. Sound absorbing structure. 4,293,053, Cl. 181-213.000.
- Sick, Erwin; and Mankel, Siegfried, to Erwin Sick GmbH-Optik-Elektronik. Banknote condition monitoring apparatus. 4,293,776, Cl. 250-572.000.
- Sidi, Henri, to Tenneco Chemicals, Inc. Pigment dispersions for surface-coating compositions and surface-coating compositions containing same. 4,293,475, Cl. 260-29.6TA.
- Siebert, Lee S.; and Ritsch, Charles J., to Mark Twain Marine Industries, Inc. Boat rub rail. 4,292,913, Cl. 114-219.000.

- Sieg, Robert P.; and Spars, Byron G., to Chevron Research Company. Shale retorting with supplemental combustion fuel. 4,293,401, Cl. 208-11.00R.
- Siemens Aktiengesellschaft: See—
Amrhein, Herbert, 4,293,764, Cl. 200-302.000.
Gross, Franz, 4,293,828, Cl. 333-27.000.
Lueder, Rainer, 4,293,831, Cl. 333-165.000.
Marin, Heiner, 4,293,750, Cl. 200-148.00A.
Roesler, Helmut, 4,293,780, Cl. 307-262.000.
Schuegraf, Eberhard, 4,293,829, Cl. 333-125.000.
Weingand, Kaspar, 4,293,376, Cl. 156-644.000.
- Siemens Medical Laboratories, Inc.: See—
Stieber, Volker A. W., 4,293,772, Cl. 250-492.200.
- Siemon Company, The: See—
Knickerbocker, Robert H., 4,293,174, Cl. 339-64.00M.
- Sierra Misco, Inc.: See—
Luchessa, Charles E.; and Brown, Timothy E., 4,292,843, Cl. 73-171.000.
- Sih, John C., to Upjohn Company, The. 13,14-Didehydro-11-deoxy-11-hydroxymethyl-19-oxo-PGE₁ compounds. 4,293,708, Cl. 562-503.000.
- Sih, John C., to Upjohn Company, The. 13,14-Dihydro-9-deoxy-9-methylene-19-oxo-PGF₂ compounds. 4,293,709, Cl. 562-503.000.
- Sih, John C., to Upjohn Company, The. 13,14-Dihydro-11-deoxy-11-hydroxymethyl-19-oxo-PGF₂ compounds. 4,293,710, Cl. 562-503.000.
- Sih, John C., to Upjohn Company, The. Inter-oxa-19-oxo-PGE₁ compounds. 4,293,711, Cl. 562-503.000.
- Sih, John C., to Upjohn Company, The. Inter-oxa-19-oxo-PGF₁ compounds. 4,293,712, Cl. 562-503.000.
- Silag, Inc.: See—
Parekh, Bhupendra K.; and Goldberger, William M., 4,293,099, Cl. 241-24.000.
- Siligoni, Marco: See—
Murari, Bruno; and Siligoni, Marco, 4,293,824, Cl. 330-301.000.
- Silva, Roy; Ash, David J.; and Scheible, Clement E., to International Telephone and Telegraph Corporation. Process for applying a moisture barrier coating to baked and fried food products. 4,293,572, Cl. 426-19.000.
- Silver Seiko, Ltd.: See—
Koike, Mitsuhito; and Iwasaki, Yasuhiro, 4,292,821, Cl. 66-75.200.
- Silvestris, Louis F.: See—
Budnovitch, William F.; Petralia, Salvatore C.; and Silvestris, Louis F., 4,293,898, Cl. 362-291.000.
- Simmonds, Robin G.: See—
Jamieson, William B.; Ross, William J.; Simmonds, Robin G.; and Verge, John P., 4,293,563, Cl. 424-273.00R.
- Simmons, Carlton J., Jr.: See—
Jones, Edward M.; and Simmons, Carlton J., Jr., 4,292,874, Cl. 84-1.030.
- Simon-Heesen B.V.: See—
van Deuren, Franciscus, 4,293,295, Cl. 425-331.000.
- Simon, Joseph A. Process for extruding a metal tube with inwardly thickened end portions. 4,292,831, Cl. 72-260.000.
- Simon, Martin J., to PPG Industries, Inc. Sealerless primers. 4,293,457, Cl. 260-15.000.
- Simpson, Roger J.; Gawthorpe, Janet A.; and Lawrence, C. Alexander, to Saint Peter's Research Trust Limited. Method and apparatus for analyzing liquid. 4,293,307, Cl. 23-230.00B.
- Singer Company, The: See—
Jaffe, Wolfgang; and Rogan, Bruce R., 4,293,837, Cl. 338-32.00H.
- Johnson, Ralph E., 4,292,906, Cl. 112-184.000.
- Sirij, Bohdan W.; Scott, Richard D.; and Horton, Charles R., to RCA Corporation. Thermal processor in an apparatus for developing photographic film. 4,293,212, Cl. 354-299.000.
- Sisti, Giorgio; and Colombo, Bruno, to Carlo Erba Strumentazione S.p.A. Method and apparatus for the analysis of sulphur contents in samples. 4,293,308, Cl. 23-230.00C.
- Sitt, Rudiger: See—
Kinast, Gunther; Muller, Lutz; Puls, Walter; and Sitt, Rudiger, 4,293,551, Cl. 424-249.000.
- Skakunov, Ivan G.: See—
Kopylov, Alexei A.; Kuzmenko, Valentin T.; Stepanov, Alexandr N.; Gaschenko, Viktor P.; Kaznachevsky, Nikolai A.; Nosovitsky, Alexandr Y.; Misikov, Ivan I.; Shapiro, Alexandr I.; Skakunov, Ivan G.; Markin, Valentin G.; Konstantinov, Alexei K.; Abramian, Eduard S.; Soroka, Arseny M.; and Zinchenko, Yakov A., 4,292,928, Cl. 119-17.000.
- Skega Aktiebolag: See—
Lundmark, Lorentz, 4,293,014, Cl. 144-208.00B.
- SKF Industrial Trading & Development, B.V.: See—
Timmer, Hendrikus J. M., 4,293,168, Cl. 308-72.000.
- SKF Kugellagerfabriken GmbH: See—
Ernst, Horst M.; Olshewski, Armin; Schurger, Rainer; Walter, Lothar; Brandenstein, Manfred; and Burkl, Erich, 4,293,166, Cl. 308-6.00C.
- Skrivan, Joseph F.: See—
Pai, Venkatrao K.; and Skrivan, Joseph F., 4,293,692, Cl. 544-196.000.
- Slaugh, Lynn H., to Shell Oil Company. Conversion of isobutene to aromatics or polyisobutylene with modified gamma alumina composition. 4,293,723, Cl. 585-407.000.
- Slavens, Clyde M.; Clavin, Edward A.; and Alleman, James E., to Midcon Pipeline Equipment Co. Welding apparatus including means for depositing the weld metal along parallel paths. 4,293,758, Cl. 219-125.120.
- Smal, Henri, to Societe Anonyme FACO. Apparatus for electrically heating hair curlers. 4,293,760, Cl. 219-222.000.
- Smathers, Edmond W.: See—
Cox, Allen R.; and Smathers, Edmond W., 4,293,883, Cl. 360-104.000.
- Smit, Helen; and Smit, Julie. Acne skin treatment appliance and method. 4,292,971, Cl. 128-256.000.
- Smit, Julie: See—
Smit, Helen; and Smit, Julie, 4,292,971, Cl. 128-256.000.
- Smith, Alfred H., Jr.; and Beers, M. Dale, to General Electric Company. Paintable one-component RTV systems. 4,293,616, Cl. 428-447.000.
- Smith, Charles W.: See—
Elphinstone, Eugene A.; McLaughlin, Homer C.; and Smith, Charles W., 4,293,440, Cl. 252-317.000.
- Smith, David R.: See—
Church, Larry L.; Smith, David R.; and Sun, Shan C., 4,293,886, Cl. 361-71.000.
- Smith, Harold W. Solar energy collector. 4,292,955, Cl. 126-417.000.
- Smith International, Inc.: See—
Kloesel, Joseph A., Jr., 4,293,048, Cl. 175-340.000.
Young, David E., 4,293,047, Cl. 175-195.000.
- Smith, Kendall O.; and Gehle, Warren D. Magnetic attraction transfer devices for use in solid phase radioimmunoassays and in other assay methods. 4,292,920, Cl. 118-425.000.
- Smith, Kline & French Laboratories Limited: See—
Durant, Graham J.; Emmett, John C.; and Ganellin, Charon R., 4,293,697, Cl. 546-121.000.
Durant, Graham J.; Emmett, John C.; and Ganellin, Charon R., 4,293,699, Cl. 546-121.000.
- Smith, Winthrop W., Jr., to Martin Marietta Corporation. Method and signal processor for frequency analysis of time domain signals. 4,293,921, Cl. 364-726.000.
- Smither, Mils A.: See—
Sharp, H. Eugene; Vela, Octavio A.; and Smither, Mils A., 4,293,937, Cl. 367-82.000.
- SmithKline Corporation: See—
Nash, Claude H., III; Shearer, Marcia C.; Snader, Kenneth M.; Valenta, Joseph R.; and Cooper, David, 4,293,546, Cl. 424-119.000.
- Snader, Kenneth M.: See—
Nash, Claude H., III; Shearer, Marcia C.; Snader, Kenneth M.; Valenta, Joseph R.; and Cooper, David, 4,293,546, Cl. 424-119.000.
- Snia Viscosa S.p.A.: See—
Senni, Paolo; and Astarita, Domenico, 4,293,494, Cl. 260-239.30A.
- Snow, Barton H., to General Electric Company. Method and apparatus for increasing compressor inlet pressure. 4,292,802, Cl. 60-204.000.
- Snyder, Gene R.: See—
Shuttleworth, Richard G.; and Snyder, Gene R., 4,293,053, Cl. 181-213.000.
- Snyder, H. Kent, Jr., to Chicago Display Company. Roll type display sign. 4,292,751, Cl. 40-517.000.
- Sobelman, Seymour: See—
Barrett, Edward E.; Hahn, Steven; Lensky, Albert; Pinczewski, Morris; and Sobelman, Seymour, 4,293,088, Cl. 227-131.000.
- Societe Anonyme DBA: See—
Riquart, Christian; and Levrai, Roland, 4,292,883, Cl. 91-29.000.
- Societe Anonyme FACO: See—
Smal, Henri, 4,293,760, Cl. 219-222.000.
- Societe d'Assistance Technique pour Produits Nestle S.A.: See—
Farr, David R.; and Magnolato, Daniele, 4,293,583, Cl. 426-657.000.
- Hirsbrunner, Pierre; and Bertholet, Raymond, 4,293,581, Cl. 426-630.000.
- Launay, Noel, 4,293,049, Cl. 177-212.000.
- Olofsson, Mats; Buhler, Marcel; and Wood, Robert, 4,293,571, Cl. 426-7.000.
- Societe Generale Pour L'Emballage: See—
Ducoux, Marcel, 4,293,219, Cl. 356-240.000.
- Societe Generale pour les Techniques Nouvelles S.G.N.: See—
Taponier, Jean; and Pierlas, Rene, 4,293,437, Cl. 252-301.10W.
- Societe Nationale Elf Aquitaine: See—
Cotte, Jean-Marie; and Potin, Philippe, 4,293,543, Cl. 424-59.000.
- Societe Nationale Elf Aquitaine (Production): See—
Gros, Pierre; Millouet, Jean; and Staron, Philippe, 4,293,935, Cl. 367-43.000.
- Societe Nationale Ind. Aerospaciale: See—
Aubry, Jacques A., 4,293,277, Cl. 416-134.00A.
- Soderberg, Nils O.: See—
Persson, Alf; and Soderberg, Nils O., 4,293,605, Cl. 428-126.000.
- Soderblom, Olof. Data transmission system. 4,293,948, Cl. 370-90.000.
- Solarex Corporation: See—
Varadi, Peter F.; and Dominguez, Ramon, 4,293,808, Cl. 320-2.000.
- Solid Corporation: See—
Morikawa, Yoshiharu, 4,293,189, Cl. 350-105.000.
- Solid Photography, Inc.: See—
DiMatteo, Paul, 4,292,724, Cl. 29-418.000.
- Sommer, Klaus; Klemm, Walter; Weber, Hermann; Meinhardt, Friedrich; Schonmann, Gerhard; and Spatz, Wilhelm, to Benckiser-Knapack GmbH. Process and apparatus for the condensation of solids. 4,293,526, Cl. 422-205.000.
- Sonntag, Michael: See—
Probst, Joachim; Sonntag, Michael; and Kolb, Gunter, 4,293,661, Cl. 525-127.000.

- Soroka, Arseny M.: See—
Kopylov, Alexei A.; Kuzmenko, Valentin T.; Stepanov, Alexandr N.; Gaschenko, Viktor P.; Kaznachevsky, Nikolai A.; Nosovitsky, Alexandr Y.; Misikov, Ivan I.; Shapiro, Alexandr I.; Skakunov, Ivan G.; Markin, Valentin G.; Konstantinov, Alexei K.; Abramian, Eduard S.; Soroka, Arseny M.; and Zinchenko, Yakov A., 4,292,928, Cl. 119-17.000.
- Soroka, Yakov K.: See—
Romanov, Viktor I.; Kirzner, Felix I.; and Soroka, Yakov K., 4,293,273, Cl. 415-78.000.
- Southern Pacific Transportation Company: See—
Fields, Carlo, 4,293,795, Cl. 315-200.00A.
- Southgate, Robert: See—
Ponsford, Roger J.; Baxter, Andrew J. G.; and Southgate, Robert, 4,293,501, Cl. 260-430.000.
- Spars, Byron G.: See—
Sieg, Robert P.; and Spars, Byron G., 4,293,401, Cl. 208-11.00R.
- Spath, Herbert J.: See—
Raymond, Glendon A.; Honnold, Fred V.; and Spath, Herbert J., 4,293,093, Cl. 237-19.000.
- Spatz, Wilhelm: See—
Sommer, Klaus; Klemm, Walter; Weber, Hermann; Meinhardt, Friedrich; Schonmann, Gerhard; and Spatz, Wilhelm, 4,293,526, Cl. 422-205.000.
- Spector, George: See—
Aziz, Victor; and Spector, George, 4,293,943, Cl. 368-316.000.
- Spence, Gavin G.: See—
Maslanka, William W.; and Spence, Gavin G., 4,293,666, Cl. 525-284.000.
Maslanka, William W.; and Spence, Gavin G., 4,293,667, Cl. 525-284.000.
- Spencer, Mike R.: See—
Lewis, Mack A.; and Spencer, Mike R., 4,293,158, Cl. 296-24.00C.
- Speno International S.A.: See—
Panetti, Romolo, 4,292,768, Cl. 51-168.000.
- Sperry Corporation: See—
De Busscher, Cyriel R. J.; and Van Herpe, Francois, 4,292,981, Cl. 130-27.00F.
- McMahon, Donald H., 4,293,188, Cl. 350-96.290.
- Van Reyersdal, Joseph, 4,293,930, Cl. 365-8.000.
- Sperry-Sun, Inc.: See—
Cox, William H.; and Chaney, Preston E., 4,293,936, Cl. 367-82.000.
Sharp, H. Eugene; Vela, Octavio A.; and Smither, Mils A., 4,293,937, Cl. 367-82.000.
- Split, Frank G.; and Turner, Donald B., to Northern Telecom Inc. Surge arrester with improved impulse ratio. 4,293,887, Cl. 361-120.000.
- Sprecker, Mark A.; Sanders, James M.; Schreiber, William L.; Watkins, Hugh; Vinals, Joaquin F.; Shuster, Edward J.; O'Rourke, Thomas J.; Hagedorn, Myrna L.; and Klemarczyk, Philip, to International Flavors & Fragrances Inc. Process for using bridged ketones in augmenting or enhancing the organoleptic properties of consumable materials. 4,293,453, Cl. 252-522.00R.
- Springrose, James V.: See—
Gordon, Robert; King, Harry A.; Springrose, James V.; and Cud-dihy, Robert W., 4,292,898, Cl. 105-238.00R.
- Square D Company: See—
Brugner, Frank S., Jr., 4,293,337, Cl. 75-232.000.
Lingaraju, Bhartoor, 4,293,172, Cl. 339-14.00P.
- Stanback, Harris I.; Brann, Theodore L.; and Polston, Larry D., 4,293,153, Cl. 292-85.000.
- Staalkat B.V.: See—
Jellema, Auke, 4,293,272, Cl. 414-744.00B.
- Stahle, Helmut; Koppe, Herbert; Kummer, Werner; Hoefke, Wolfgang; Gaida, Wolfram; and Pichler, Ludwig, to Boehringer Ingelheim GmbH. 2-(3,5-Dibromo-4-amino-phenylimino)-imidazolidine, salts and compositions thereof. 4,293,564, Cl. 424-273.00R.
- Stal-Laval Turbin AB: See—
Bergkvist, Jorgen, 4,293,298, Cl. 432-58.000.
Ekberg, Hakan, 4,292,742, Cl. 34-35.000.
- Stanback, Harris I.; Brann, Theodore L.; and Polston, Larry D., to Square D Company. Panelboard vent assembly. 4,293,153, Cl. 292-85.000.
- Standard Oil Company, The: See—
Herrington, Daniel R.; and Schwerko, Albert P., 4,293,449, Cl. 252-465.000.
Lemanski, Michael F.; Bremer, Noel J.; and Milberger, Ernest C., 4,293,498, Cl. 260-346.750.
Suresh, Dev D.; Bremer, Noel J.; and Grasselli, Robert K., 4,293,443, Cl. 252-432.000.
Velenyi, Louis J.; Dolhyj, Serge R.; and Sundeen, Marcia H., 4,293,719, Cl. 568-573.000.
- Standard Oil Company (Indiana): See—
Beynet, Pierre A.; Lucksinger, James E.; and Jansen, Martin B., Jr., 4,293,146, Cl. 285-24.000.
- Standing, David L., to Kangol Magnet Limited. Emergency locking seat belt retractor. 4,293,106, Cl. 242-107.40A.
- Stanford Associates, Inc.: See—
Wasserman, Philip D., 4,293,917, Cl. 364-701.000.
- Stanhope-Seta Limited: See—
Oakman, Ronald A., 4,292,837, Cl. 73-17.00R.
- Stanley Mabo, S.A.: See—
Scandella, Louis, 4,292,741, Cl. 33-379.000.
- Staplin, Theodore R., Jr.: See—
Bradley, John J.; Holtey, Thomas O.; Miller, Robert C.; Miu, Ming T.; Shen, Jian-Kuo; and Staplin, Theodore R., Jr., 4,293,908, Cl. 364-200.000.
- Starcevic, Mihailo, to BBC Brown, Boveri & Company, Limited. Carrying and guiding spider for the support of a rotor of a vertical electrical machine. 4,293,786, Cl. 310-157.000.
- Staron, Philippe: See—
Gros, Pierre; Millouet, Jean; and Staron, Philippe, 4,293,935, Cl. 367-43.000.
- Starr, Louis J. Skidwheel game. 4,293,132, Cl. 273-126.00R.
- Stauffer Chemical Company: See—
Pallos, Ferenc M.; and Gaughan, Edmund J., 4,293,701, Cl. 546-335.000.
- Stauffer, Rita: See—
Raible, Donald A.; Poticha, Stuart M.; and Stauffer, Rita, 4,292,969, Cl. 128-214.00R.
- Steckelberg, Willi: See—
Hoyer, Ernst; Steckelberg, Willi; Deucker, Walter; and Schick-fluss, Rudolf, 4,293,306, Cl. 8-471.000.
- Steckler, Steven A.; and Balaban, Alvin R., to RCA Corporation. Circuit arrangement for multiplexing an input function and an output function at a single terminal. 4,293,870, Cl. 358-10.000.
- Stegmuller, Willi: See—
Fischer, Helmut; Ott, Albert; and Stegmuller, Willi, 4,293,767, Cl. 250-308.000.
- Stefanovic, Miroslav, to Stocker Hinge Mfg. Co. Hinges with position-locking filaments. 4,292,708, Cl. 16-140.000.
- Steffen, Vincent B. Protective element for fork-lift pallets. 4,292,899, Cl. 108-51.100.
- Stelte, David J.; and Kobylar, Alex W., to GTE Automatic Electric Labs Inc. Analog access arrangement for a digital telephone office. 4,293,738, Cl. 179-18.00C.
- Stenberg, Herbjorn: See—
Liu, Chunghong R.; Nayak, Jnaneshwar H.; Stenberg, Herbjorn; Huerta, Felipe J.; and Hall, Woodrow A., 4,292,865, Cl. 82-36.00R.
- Stepanov, Alexandr N.: See—
Kopylov, Alexei A.; Kuzmenko, Valentin T.; Stepanov, Alexandr N.; Gaschenko, Viktor P.; Kaznachevsky, Nikolai A.; Nosovitsky, Alexandr Y.; Misikov, Ivan I.; Shapiro, Alexandr I.; Skakunov, Ivan G.; Markin, Valentin G.; Konstantinov, Alexei K.; Abramian, Eduard S.; Soroka, Arseny M.; and Zinchenko, Yakov A., 4,292,928, Cl. 119-17.000.
- Stieber, Volker A. W., to Siemens Medical Laboratories, Inc. Wobbling device for a charged particle accelerator. 4,293,772, Cl. 250-492.200.
- Stiefel, Peter: See—
Wagner, Karl; Engelsmann, Dieter; Hackenberg, Hubert; and Stiefel, Peter, 4,293,204, Cl. 354-21.000.
- Still, W. Clark. Flash chromatography. 4,293,422, Cl. 210-656.000.
- Stivers, David A., to Minnesota Mining and Manufacturing Company. Fluoroelastomer/polyepichlorohydrin elastomer articles. 4,293,663, Cl. 525-187.000.
- STM Corporation: See—
Miller, Sylvester T., 4,293,309, Cl. 23-230.00EP.
- Stocker Hinge Mfg. Co.: See—
Stefanovic, Miroslav, 4,292,708, Cl. 16-140.000.
- Stockhaus, Klaus: See—
Merz, Herbert; and Stockhaus, Klaus, 4,293,556, Cl. 424-267.000.
- Stoffels, Carl A.; and Genovese, Nicholas J., to Judelson Industries Division, John Dusenberry Co., Inc. Apparatus and method for slitting elongated rolls of material. 4,292,867, Cl. 82-47.000.
- Stogryn, Eugene L.: See—
Klemann, Lawrence P.; Newman, Gerald H.; Stogryn, Eugene L.; Whitney, Thomas A.; and Farcasiu, Dan, 4,293,623, Cl. 429-194.000.
- Stoll, Wolfgang: See—
Ledebrink, Friedrich-Wilhelm; Stoll, Wolfgang; and Schafer, Dieter, 4,293,438, Cl. 252-301.10W.
- Stone Container Corporation: See—
Partain, James H., 4,293,069, Cl. 206-279.000.
- Stone, Everett W. Method of treating fresh shrimp to reduce moisture and nutrient loss. 4,293,578, Cl. 426-332.000.
- Stork Brabant B.V.: See—
Barendregt, Frank; and Boogaard, Leendert A., 4,293,873, Cl. 358-75.000.
- Stork PMT B.V.: See—
van Mil, Martinus P. G., 4,292,709, Cl. 17-11.10R.
- Story, Edward R. Insulation-confining panel and method of using the same. 4,292,777, Cl. 52-407.000.
- Stouffer, James F. Tongue toothbrush. 4,292,705, Cl. 15-110.000.
- Stratford/Graham Engineering Corp.: See—
Kolb, Norman P.; and Webb, Orlando, 4,293,729, Cl. 585-715.000.
- Strazik, William F.; LeBlanc, John R.; and Santer, J. Owen, to Monsanto Company. Unsaturated melamine condensates. 4,293,461, Cl. 260-18.00N.
- Streifer, William: See—
Sciffres, Donald R.; Burnham, Robert D.; and Streifer, William, 4,293,826, Cl. 331-94.50H.
- Streuli, Hans; and Ruedi, Joseph, to Hans Streuli AG. Magnetic filter. 4,293,410, Cl. 210-107.000.
- Stringer, Brian: See—
Sutcliffe, Peter W.; Isaacs, Jim W.; Nelson, Robert L.; Lyon, Colin E.; and Stringer, Brian, 4,293,507, Cl. 264-0.500.

Structural Composite Industries, Inc.: See—
Gordon, Robert King, Harry A.; Springrose, James V.; and Cud-dihy, Robert W., 4,292,898, Cl. 105-238.00R.

Struger, Odo J.; Brown, Ronald A.; and Black, Craig A., to Allen-Brad-ley Company. Programmable controller with high density intelligent I/O interface. 4,293,924, Cl. 364-900.000.

Stull, Bertram O., to United States of America, Navy. Gelled fuel-air explosive method. 4,293,314, Cl. 44-7.00A.

Sturtz, Gregory P.: See—
Martin, Ralph D.; Dunnavant, William R.; Sturtz, Gregory P.; and Langer, Heimo J., 4,293,480, Cl. 260-38.000.

Stusenko, Jury A.: See—
Dunaevsky, Vladimir I.; Boidenko, Nikolai G.; Samarin, Alexei P.; Levit, Viktor M.; Zapara, Boris M.; Ivanov, Boris N.; Frolov, Sergei A.; Voronin, Rostislav A.; Belozero, Nikolai P.; Momot, Valery I.; Stusenko, Jury A.; and Samoilov, Vladimir A., 4,293,101, Cl. 242-56.400.

Su, Tien-Kuei: See—
Kluger, Edward W.; and Su, Tien-Kuei, 4,293,682, Cl. 528-123.000.

Sugio, Akitoshi; Masu, Masanobu; Nakai, Hiroshi; and Sasaki, Yukio, to Mitsubishi Gas Chemical Co., Inc. Process for producing polyphen-ylene ether composition containing inorganic pigment. 4,293,478, Cl. 260-37.00R.

Sugio, Akitoshi; Masu, Masanobu; and Matunaga, Masatugu, to Mit-subushi Gas Chemical Co., Inc. Polyphenylene ether resin composi-tion. 4,293,660, Cl. 525-68.000.

Sugita, Jitsuo: See—
Yukinaga, Hisajiro; Sumimoto, Shinzaburo; Ishizuka, Ichiro; and Sugita, Jitsuo, 4,293,328, Cl. 71-88.000.

Sugiura, Muneharu: See—
Minoura, Kazuo; Sugiura, Muneharu; Minami, Setsuo; and Sato, Tadashi, 4,293,184, Cl. 350-6.300.

Sugiyama, Keiichi: See—
Matsumoto, Hiromitsu; Sugiyama, Keiichi; and Uchiyama, Kazuo, 4,292,944, Cl. 123-432.000.

Sugou, Kiyoshi: See—
Kinoshita, Minoru; Sugou, Kiyoshi; and Onoda, Yukio, 4,293,226, Cl. 356-443.000.

Sulzer Brothers Limited: See—
Baumann, Hans, 4,293,007, Cl. 139-358.000.
Weber, Max, 4,293,384, Cl. 376-391.000.

Sumimoto, Shinzaburo: See—
Yukinaga, Hisajiro; Sumimoto, Shinzaburo; Ishizuka, Ichiro; and Sugita, Jitsuo, 4,293,328, Cl. 71-88.000.

Sumitomo Chemical Company, Limited: See—
Shimizu, Shinkichi; Nishizaki, Tadao; and Tsuda, Masabumi, 4,293,445, Cl. 252-438.000.
Suzuki, Yukio; Kasamatsu, Kiyoshi; and Aketa, Kohichi, 4,293,504, Cl. 260-465.00D.

Umemura, Takeaki; Morino, Haruki; Watanabe, Tetsuhiko; and Uematsu, Tamon, 4,293,702, Cl. 548-165.000.

Sumitomo Electric Industries, Ltd.: See—
Hara, Akio; and Yazu, Shuji, 4,293,618, Cl. 428-551.000.

Sumitomo Metal Industries, Ltd.: See—
Yamaguchi, Hisao; and Fujisawa, Kazuo, 4,292,849, Cl. 73-643.000.

Sun, Jui-Yuan: See—
Burk, Emmett H., Jr.; Yoo, Jin S.; Karch, John A.; and Sun, Jui-Yuan, 4,293,403, Cl. 208-120.000.

Sun, Shan C.: See—
Church, Larry L.; Smith, David R.; and Sun, Shan C., 4,293,886, Cl. 361-71.000.

Sundeen, Marcia H.: See—
Veleny, Louis J.; Dolhy, Serge R.; and Sundeen, Marcia H., 4,293,719, Cl. 568-573.000.

Supcoe, Robert F.; and Radakovich, Thomas, to United States of America, Navy. Underwater wax formulation and method. 4,293,339, Cl. 106-18.290.

Suresh, Dev D.; Bremer, Noel J.; and Grasselli, Robert K., to Standard Oil Company. Oxidation catalysts. 4,293,443, Cl. 252-432.000.

Sutcliffe, Peter W.; Isaacs, Jim W.; Nelson, Robert L.; Lyon, Colin E.; and Stringer, Brian, to United Kingdom Atomic Energy Authority. Preparation of shaped bodies. 4,293,507, Cl. 264-0.500.

Suzuki, Seigo, to Tokyo Shibaura Electric Co., Ltd. Electronic ignition control systems. 4,292,941, Cl. 123-416.000.

Suzuki, Shotaro, to Hakuju Institute for Health Science Co., Ltd. Electrode assembly for use in electric field therapy apparatus. 4,292,980, Cl. 128-783.000.

Suzuki, Yukio; Kasamatsu, Kiyoshi; and Aketa, Kohichi, to Sumitomo Chemical Company, Limited. Process for preparing optically active α -cyano-3-(4-halogenophenoxy)-benzyl 2-(4-chlorophenyl)isovaler-ate. 4,293,504, Cl. 260-465.00D.

Svoboda, Glenn R., to Freeman Chemical Corporation. Composition for coating molded articles. 4,293,659, Cl. 525-28.000.

Swanson, Billy L., to Phillips Petroleum Co. Shear-thickening composi-tions. 4,293,036, Cl. 166-302.000.

Swanson, Douglas L.; and Yeo, Norman H., to Swanson-Erie Corpora-tion. Commonly actuated in-line assembly machine. 4,292,734, Cl. 29-791.000.

Swanson-Erie Corporation: See—
Swanson, Douglas L.; and Yeo, Norman H., 4,292,734, Cl. 29-791.000.

Swanson, Victor E., to Crepac, Inc. Positive displacement rotary pump with bearings in countersunk portions of the rotors. 4,293,290, Cl. 418-94.000.

Swantee, Klaus B. M., to Pidou B.V. Sealing device. 4,293,138, Cl. 277-207.00A.

Swift, Harold E.; Innes, Robert A.; and Adams, Phillip, to Gulf Re-search & Development Company; and Kewanee Industries. Process for preparing alkyldimethylamines. 4,293,716, Cl. 564-480.000.

Swingline Inc.: See—
Barrett, Edward E.; Hahn, Steven; Lensky, Albert; Pinczewski, Morris; and Sobelman, Seymour, 4,293,088, Cl. 227-131.000.

Swisher, George W., Jr.; Garbelman, David L.; and Shaw, Arthur G., to CMI Corporation. Drum for an asphalt mixing apparatus. 4,293,228, Cl. 366-25.000.

Swiss Aluminium Ltd.: See—
Baur, Rudolf; Merki, Emil; and Krahenbuhl, Hanspeter, 4,293,424, Cl. 210-737.000.
Hrasche, Heinrich, 4,293,255, Cl. 410-104.000.

Swodenk, Wolfgang: See—
Waldmann, Helmut; Schwerdtel, Wulf; and Swodenk, Wolfgang, 4,293,717, Cl. 568-485.000.

SWS Silicones Corporation: See—
Martin, Eugene R., 4,293,611, Cl. 428-266.000.

Sybron Corporation: See—
Ellis, Franklin H., 4,292,968, Cl. 128-207.210.

Syndicat National des Fabricants de Sucre de France: See—
Lescure, Jean-Pierre, 4,293,412, Cl. 210-179.000.

Syntax (U.S.A.) Inc.: See—
Walker, Keith A. M., 4,293,561, Cl. 424-273.00R.

Sypula, Donald S.: See—
Murphy, Cornelius B.; and Sypula, Donald S., 4,293,627, Cl. 430-39.000.

Syracuse Supply Company: See—
Robinson, James A. L., 4,293,064, Cl. 198-779.000.

Systems Consultants, Inc.: See—
Muralidhara, H. S., 4,293,098, Cl. 241-19.000.

Systems Research Laboratories, Inc.: See—
Rainey, J. Montgomery; and Taylor, Francis M., 4,292,848, Cl. 73-602.000.

Szabo, Tibor. Grinding machine for delimited groove machining on cutting tools. 4,292,699, Cl. 51-94.00R.

Szanto, Elmer G.; Wu, George; and Ulrich, Charles J., to Velo-Bind, Inc. Punching and binding machine. 4,293,366, Cl. 156-477.00B.

Szilvasi, Endre: See—
Pataki, Jozsef; Bucsi, Jozsef; Bona, Istvan; Szilvasi, Endre; Gazdag, Andras; Koty, Antal; and Hidvegi, Ferenc, 4,292,996, Cl. 137-393.000.

Szollmann, Anton. Valve for toy balloons. 4,292,999, Cl. 137-560.000.

T. A. Pelsue Company: See—
Beavers, Allan E., 4,293,862, Cl. 343-872.000.

Tacke, Peter: See—
Heydenreich, Frieder; Korber, Helmut; Tacke, Peter; Fahner, Friedrich; and Neuray, Dieter, 4,293,662, Cl. 525-184.000.

Taiho Pharmaceutical Company Limited: See—
Fujimura, Hajime; Hiramatsu, Yasuzo; Yabuuchi, Takahiro; Hisaki, Masakatu; Takikawa, Katsuo; Honna, Takaji; Miyake, Hidekazu; and Kajitani, Makoto, 4,293,713, Cl. 564-38.000.

Tait, William H., to Dofasco Inc. Testing the material of a product for defects therein and processing the material employing such a method. 4,292,847, Cl. 73-587.000.

Takagi, Mikio; Maeda, Mamoru; and Kamioka, Hajime, to Fujitsu Limited. Process for high pressure oxidation of silicon. 4,293,589, Cl. 427-93.000.

Takagi, Mikio; Maeda, Mamoru; and Kamioka, Hajime, to Fujitsu Limited. Process for high pressure oxidation of silicon. 4,293,590, Cl. 427-93.000.

Takagishi, Haruyoshi: See—
Wakabayashi, Makoto; and Takagishi, Haruyoshi, 4,293,363, Cl. 156-272.000.

Takahara, Yoshiyuki: See—
Sasaki, Hiromi; and Takahara, Yoshiyuki, 4,293,532, Cl. 423-356.000.

Takahashi, Osamu; and Sakaguchi, Shinji, to Fuji Photo Film Co., Ltd. Photographic light-sensitive material. 4,293,641, Cl. 430-502.000.

Takahashi, Yoshitaka: See—
Kakinuma, Mitsuru; and Takahashi, Yoshitaka, 4,292,812, Cl. 62-157.000.

Takahashi, Yosuke, to Nippon Kogaku K.K. Solid electrochromic element. 4,293,194, Cl. 350-357.000.

Takahashi, Yukio: See—
Iwaki, Tetsuo; Takahashi, Yukio; Moriuchi, Shuji; and Kaneko, Hisamitsu, 4,293,720, Cl. 568-575.000.

Takashima, Yoshimi: See—
Ishikawa, Masayuki; Tanaka, Hiromichi; Eguchi, Yukuo; Ito, Shigeru; Takashima, Yoshimi; and Kobayashi, Masahiko, 4,293,553, Cl. 424-250.000.

Takeda Chemical Industries, Ltd.: See—
Sawa, Yoichi; Kawakami, Yoshiyuki; and Marumoto, Ryuji, 4,293,690, Cl. 536-24.000.

Takeda Riken Kogyo Kabushikikaisha: See—
Kokta, Milan R.; and Taylor, Roger W., 4,293,371, Cl. 156-624.000.

Takemoto, Masao; Tokuno, Takashi; Ishikawa, Kohji; Narumi, Naoki; and Ohguchi, Osamu, 4,293,950, Cl. 371-21.000.

Takekoshi, Tohru; and Klopfer, Howard J., to General Electric Com-pany. Method for making polyetherimides using carboxylic acid salts of alkali metals or zinc as catalysts. 4,293,683, Cl. 528-180.000.

Takekoshi, Tohru, to General Electric Company. Polyetherimide having long chain aliphatic end groups and method for making. 4,293,684, Cl. 528-185.000.

Takikawa, Katsuo: See—
Fujimura, Hajime; Hiramatsu, Yasuzo; Yabuuchi, Takahiro; Hisaki, Masakatu; Takikawa, Katsuo; Honna, Takaji; Miyake, Hidekazu; and Kajitani, Makoto, 4,293,713, Cl. 564-38.000.

Takita, Seiki; and Ichizuka, Kiyomi, to Ricoh Co., Ltd. Recording apparatus. 4,293,866, Cl. 346-140.00R.

Takusagawa, Kiyoshi: See—
Kikuchi, Tsuyoshi; and Takusagawa, Kiyoshi, 4,293,024, Cl. 164-303.000.

Tamamura, Ryo; and Kutsukake, Yukinori, to Asahi Glass Company, Ltd. Roll for manufacturing float glass. 4,293,335, Cl. 75-124.000.

Tamori, Michitoshi; and Kawai, Kazuo, to Kokusai Denshin Denwa Co., Ltd. Sampling function type equalizer. 4,293,952, Cl. 375-14.000.

Tamura, Humio: See—
Asano, Kiro; Tamura, Humio; Nezu, Yushi; Saito, Tsuyoshi; and Kawai, Yoshio, 4,293,533, Cl. 423-449.000.

Tamura Kaken Co., Ltd.: See—
Okuya, Ken, 4,293,636, Cl. 430-281.000.

Tamura, Shingo: See—
Mochida, Hideyuki; Tamura, Shingo; and Tsurumi, Etsuo, 4,293,903, Cl. 363-68.000.

Tan, David: See—
Tan, Lu J.; Tan, David; and Tan, Jeff, 4,293,230, Cl. 366-101.000.

Tan, Jeff: See—
Tan, Lu J.; Tan, David; and Tan, Jeff, 4,293,230, Cl. 366-101.000.

Tan, Lu J.; Tan, David; and Tan, Jeff, 4,293,230, Cl. 366-101.000.

Tan, Kwang G.: See—
Flusche, Frederick O.; Tan, Kwang G.; and Wright, Ralph W., 4,293,910, Cl. 364-200.000.

Tan, Lu J.; Tan, David; and Tan, Jeff, Apparatus for providing fuel for an oil burner. 4,293,230, Cl. 366-101.000.

Tanaka, Hideki: See—
Kamejima, Kohji; Tanaka, Hideki; Kano, Minoru; and Fukushima, Toshihiko, 4,292,811, Cl. 62-56.000.

Tanaka, Hiromichi: See—
Ishikawa, Masayuki; Tanaka, Hiromichi; Eguchi, Yukuo; Ito, Shigeru; Takashima, Yoshimi; and Kobayashi, Masahiko, 4,293,553, Cl. 424-250.000.

Tanaka, Katsushi; and Okamoto, Taro, to Kyokuto Kaihatsu Kogyo Co., Ltd. Spraying unit for unhardened concrete and the like. 4,293,227, Cl. 366-11.000.

Tanaka, Kojiro; Ochiai, Shozo; and Noda, Hideki, to Kabushiki Kaisha Daini Seikosha. Voltage detecting circuit. 4,293,782, Cl. 307-350.000.

Tanaka, Kozo: See—
Kojima, Masayuki; Kobayakawa, Masaki; and Tanaka, Kozo, 4,293,793, Cl. 313-497.000.

Tanaka, Susumu: See—
Ogimoto, Kazuo; Inoue, Tomohiro; Tanaka, Susumu; and Kobaya-shi, Yoshio, 4,293,240, Cl. 405-195.000.

Tanaka, Toshiaki; and Etou, Yukihiro, to Nissan Motor Company, Limited. Internal combustion engine. 4,292,938, Cl. 123-198.00F.

Tanaka, Toyonaru; and Naito, Hideki, to Jeco Co., Ltd. Electronic display device for use in motor cars. 4,293,842, Cl. 340-52.00F.

Tanaka, Yoshiaki; and Hayakawa, Isao, to Daiichi Seiyaku Co., Ltd. Furonaphthyridine compounds. 4,293,695, Cl. 546-83.000.

Tanaka, Yoshikazu; Shirai, Hitoshi; and Kan'o, Yoshiharu, to Fujitsu Limited. Memory refresh control system. 4,293,931, Cl. 365-222.000.

Tanasawa, Yasui; Muto, Norio; Saito, Akinori; and Kawamura, Kiyomi, to Kabushiki Kaisha Toyota Chuo Kenkyusho. Spill type swirl injector. 4,292,947, Cl. 123-445.000.

Tanifuji, Shinya: See—
Morooka, Yasuo; Tanifuji, Shinya; and Tanuma, Masaya, 4,292,825, Cl. 72-8.000.

Taniyama, Tsukasa: See—
Sekino, Masaaki; Chikanari, Kenichi; and Taniyama, Tsukasa, 4,293,419, Cl. 210-321.100.

Tanty, Paul J.: See—
Hofer, Wayne A.; and Tanty, Paul J., 4,293,164, Cl. 303-13.000.

Tanuma, Masaya: See—
Morooka, Yasuo; Tanifuji, Shinya; and Tanuma, Masaya, 4,292,825, Cl. 72-8.000.

Tapeswitch Corporation of America: See—
Koenig, Robert H., 4,293,752, Cl. 200-295.000.

Taponier, Jean; and Pierlas, Rene, to Societe Generale pour les Tech-niques Nouvelles S.G.N. Process for the treatment and packaging of low or average activity radio-active waste. 4,293,437, Cl. 252-301.10W.

Tarutani, Masaaki: See—
Shibata, Kenyu; Itaya, Toshihisa; Yamakoshi, Nobuaki; Kurata, Shigeru; Koizumi, Naoyuki; Tarutani, Masaaki; Sakuma, Hideki; and Konishi, Kunihiro, 4,293,557, Cl. 424-267.000.

Taylor, Derek, to Bunker Ramo Corporation. Resilient biasing means. 4,293,180, Cl. 339-217.00R.

Taylor, Francis M.: See—
Rainey, J. Montgomery; and Taylor, Francis M., 4,292,848, Cl. 73-602.000.

Taylor, Glenn E. Auxiliary lift axle wheel assembly. 4,293,145, Cl. 280-704.000.

Taylor, Roger W.: See—
Kokta, Milan R.; and Taylor, Roger W., 4,293,371, Cl. 156-624.000.

Taylor, Walter C. Non-metallic paste sectors and methods of fabricat-ing and utilizing same. 4,292,919, Cl. 118-212.000.

TDK Electronics Co., Ltd.: See—
Nagano, Katsuo; Ihaya, Kazuhiko; Sasa, Syozo; and Nakada, Takeshi, 4,293,370, Cl. 156-612.000.

Technicare Corporation: See—
Walters, Ronald G., 4,293,912, Cl. 364-414.000.

TED Bildplatten Aktiengesellschaft: See—
Scholz, Werner, 4,293,869, Cl. 358-8.000.

Teikoku Hormone Mfg. Co., Ltd.: See—
Shibata, Kenyu; Itaya, Toshihisa; Yamakoshi, Nobuaki; Kurata, Shigeru; Koizumi, Naoyuki; Tarutani, Masaaki; Sakuma, Hideki; and Konishi, Kunihiro, 4,293,557, Cl. 424-267.000.

Teledyne Walterboro: See—
Hoyt, Harold C., Jr.; and Greene, William J., 4,293,756, Cl. 219-133.000.

Telegram Communications Corp.: See—
Katz, Bernard R., 4,293,875, Cl. 358-184.000.

Telex Communications, Inc.: See—
Gehr, Marvin M.; and Pabian, Howell D., 4,293,955, Cl. 455-276.000.

Teller, Aaron J.; Roy, Denis R. J.; and Lin, Shih K., to Teller Environ-mental Systems, Inc. Method and apparatus for cooling and neutraliz-ing acid gases. 4,293,524, Cl. 422-169.000.

Teller Environmental Systems, Inc.: See—
Teller, Aaron J.; Roy, Denis R. J.; and Lin, Shih K., 4,293,524, Cl. 422-169.000.

Tellers, Donald W. Calf incubator. 4,292,929, Cl. 119-27.000.

Temple University: See—
Labs, Mortimer M.; and MacMillan, John H., 4,293,193, Cl. 350-350.00R.

Tenneco Chemicals, Inc.: See—
Sidi, Henri, 4,293,475, Cl. 260-29.6TA.

Tepe, James R.; Sandor, Robert P.; Wesselman, Bernard W.; and Woeste, David R., to Energetics Systems Corp. Control system for heating and cooling units. 4,293,027, Cl. 165-12.000.

Terashima, Isamu, to Hitachi, Ltd. Toner concentration detecting apparatus. 4,292,925, Cl. 118-690.000.

Teraura, Makoto, to Nippon Cable System Inc. Steering device. 4,292,859, Cl. 74-501.00R.

Terneu, Robert; and Van Cauter, Albert, to BFG Glassgroup. Glass coating. 4,293,326, Cl. 65-60.00D.

Terry, F. Duncan: See—
Haag, George A.; Fogg, O. Douglas; Greenley, Gordon A.; Shep-ard, Steve A.; and Terry, F. Duncan, 4,293,925, Cl. 364-900.000.

Tetra Pak International AB: See—
Dilot, Rolf M.; and Hakansson, Jan T., 4,293,369, Cl. 156-521.000.

Texaco Inc.: See—
Calderon, Reynaldo, 4,293,037, Cl. 166-312.000.
Cuscrida, Michael, 4,293,470, Cl. 260-45.90R.

Texas Instruments Incorporated: See—
McAdams, Hugh P., 4,293,932, Cl. 365-222.000.
Whelan, Paul L., 4,293,249, Cl. 406-72.000.

Texas Iron Works, Inc.: See—
Braddick, Britt O., 4,293,163, Cl. 251-283.000.

Textron Inc.: See—
Brogdon, Vas H.; and Williams, David L., 4,293,276, Cl. 416-134.00A.

Theodore, Ares N., to Ford Motor Company. Highly filled thermally conductive elastomers III. 4,293,477, Cl. 260-29.15B.

Thermo Electron Corporation: See—
Morgan, Dean T.; Chrysostomidis, Chrysostomos; and LaRue, George J., 4,293,527, Cl. 423-6.000.

Thibault, James G.: See—
Kuna, Wayne A.; Thibault, James G.; and Schoenfeld, Palmer J., 4,292,758, Cl. 46-93.000.

Thiessen, Robert J.: See—
Shaw, Michael J.; and Thiessen, Robert J., 4,293,629, Cl. 430-64.000.

Thillays, Jacques C., to U.S. Philips Corporation. Method of manufac-turing a coplanar photocoupler. 4,292,735, Cl. 29-854.000.

Thilly, William G.: See—
Levine, David W.; Thilly, William G.; Wang, Daniel I. C.; and Wong, Jason S., 4,293,654, Cl. 435-241.000.

Thomalla, Bogdan: See—
Jedlinski, Zbigniew; Thomalla, Bogdan; Kotas, Antoni; Jedlinski, Stanislaw; Pilat, Wladyslaw; and Jach, Jan, 4,293,685, Cl. 528-190.000.

Thomas, Albert L., Jr.: See—
Bird, Alvin N., Jr.; Francis, Norman L.; and Thomas, Albert L., Jr., 4,293,217, Cl. 356-37.000.

Thomas, Claude E. Display device for coupon clip. 4,292,749, Cl. 40-308.000.

Thompson, Ralph B.: See—
Gorman, Susan B.; Thompson, Ralph B.; and Yonan, Edward E., 4,293,706, Cl. 560-163.000.

Thompson, Thomas K., to Owens-Corning Fiberglas Corporation. Method and apparatus for production of a stream feeder. 4,292,862, Cl. 76-4.000.

Thomson-CSF: See—
Berger, Jean L., 4,293,832, Cl. 333-165.000.

Thorn EMI Limited: See—
Cook, Frank; and Davies, Gordon H., 4,293,801, Cl. 315-370.000.

Thornhill, John, Jr.; and Elder, Richard B., to RCA Corporation. Earth self-orienting apparatus. 4,292,861, Cl. 74-813.00R.

Tilman, Hoefelmayer, to Bio-Melktechnik Swiss Hoefelmayer & Co. Method for the automatic finish milking during a mechanical milk removal procedure. 4,292,926, Cl. 119-14.020.

Timmer, Hendrikus J. M., to SKF Industrial Trading & Development, B.V. Housing for Y-bearing. 4,293,168, Cl. 308-72.000.

- Tirzit, Gunar D.: See—
Uldrikis, Yan R.; Preisa, Ieva E.; Dubur, Gunar Y.; Zidermane, Aina A.; Bisenix, Egils A.; and Tirzit, Gunar D., 4,293,700, Cl. 546-321.000.
- Tishler, Albert; Tishler, Murray; Tishler, William; Tishler, Irving; and Lucchesi, Joseph, to Norwalk Investment Club. Irregular shape rod bending apparatus. 4,292,834, Cl. 72-482.000.
- Tishler, Irving: See—
Tishler, Albert; Tishler, Murray; Tishler, William; Tishler, Irving; and Lucchesi, Joseph, 4,292,834, Cl. 72-482.000.
- Tishler, Murray: See—
Tishler, Albert; Tishler, Murray; Tishler, William; Tishler, Irving; and Lucchesi, Joseph, 4,292,834, Cl. 72-482.000.
- Tishler, William: See—
Tishler, Albert; Tishler, Murray; Tishler, William; Tishler, Irving; and Lucchesi, Joseph, 4,292,834, Cl. 72-482.000.
- TLB Plastics Corporation: See—
Lytle, Thomas G., 4,293,079, Cl. 220-306.000.
- Tobita, Kouji: See—
Morishita, Teyoshi; Miyake, Kenji; and Tobita, Kouji, 4,292,936, Cl. 123-193.00P.
- Toegel, Herbert J.: See—
Kuras, Michael L.; Upp, Daniel C.; and Toegel, Herbert J., 4,293,946, Cl. 370-62.000.
- Togami, Yuji, to Nippon Hoso Kyokai. Recording medium. 4,293,621, Cl. 428-678.000.
- Toibana, Yasuo: See—
Ebata, Yoshihiro; Toibana, Yasuo; Uetsuki, Tsuneo; Kose, Saburo; and Kinoshita, Makoto, 4,293,356, Cl. 156-89.000.
- Tokuno, Takashi: See—
Shimizu, Masao; Tokuno, Takashi; Ishikawa, Kohji; Narumi, Naoki; and Ohguchi, Osamu, 4,293,950, Cl. 371-21.000.
- Tokutomi, Seiji; Jyojiki, Masao; and Nakamura, Kazuo, to Asahi Kogaku Kogyo Kabushiki Kaisha. Camera focus detecting device. 4,293,205, Cl. 354-23.00D.
- Tokutomi, Seiji; Jyojiki, Masao; Aoki, Harumi; Nakamura, Kazuo; and Watanabe, Koichiro, to Asahi Kogaku Kogyo Kabushiki Kaisha. Electrically operated automatic focalizing camera. 4,293,206, Cl. 354-25.000.
- Tokyo Kogaku Kikai Kabushiki Kaisha: See—
Wada, Shinji; Kitao, Ikuo; Oana, Yoshinori; Kato, Yasuo; and Ishihara, Taketoshi, 4,293,199, Cl. 351-13.000.
- Tokyo Sanyo Electric Co., Ltd.: See—
Kakinuma, Mitsuru; and Takahashi, Yoshitaka, 4,292,812, Cl. 62-157.000.
- Tokyo Shibaura Denki Kabushiki Kaisha: See—
Endo, Norio, 4,292,728, Cl. 29-571.000.
- Nakajima, Shunichi; and Hasegawa, Haruyoshi, 4,293,085, Cl. 222-311.000.
- Ogimoto, Kazuo; Inoue, Tomohiro; Tanaka, Susumu; and Kobayashi, Yoshio, 4,293,240, Cl. 405-195.000.
- Tokyo Shibaura Electric Co., Ltd.: See—
Suzuki, Seigo, 4,292,941, Cl. 123-416.000.
- Toland, James, to World Carpets, Inc. Apparatus for randomly coloring pile fabric. 4,292,822, Cl. 68-5.00D.
- Tonikian, Robert T.: See—
Ragoza, Igor V.; Begunov, Petr M.; Tonikian, Robert T.; and Vasiljuk, Petr J., 4,292,820, Cl. 66-8.000.
- Toray Industries, Inc.: See—
Fujii, Yoshishige; Nagao, Syozo; and Kumazawa, Shunji, 4,293,418, Cl. 210-321.100.
- Otaki, Yukio; Umeda, Kazuo; and Nakagawa, Kiyoshi, 4,292,799, Cl. 57-246.000.
- Toray Silicone Company, Ltd.: See—
Hanada, Tsuneo; Koshii, Taro; and Shinmi, Hideo, 4,293,479, Cl. 260-37.00P.
- Imai, Takeshi, 4,293,677, Cl. 528-15.000.
- Sasaki, Shosaku; and Kaiya, Nobuo, 4,293,671, Cl. 525-478.000.
- Toriyama, Kazuhisa; Hata, Tsujiaki; Hasegawa, Shinji; and Sasaki, Ken, to Hitachi, Ltd. Compound for controlling dielectric constant of liquid crystal. 4,293,698, Cl. 546-301.000.
- Toro Company, The: See—
Holmstadt, Ronald J.; and Comer, Robert C., 4,293,041, Cl. 172-39.000.
- Toshiba Kikai Kabushiki Kaisha: See—
Kikuchi, Tsuyoshi; and Takusagawa, Kiyoshi, 4,293,024, Cl. 164-303.000.
- Townsend, Charles E., Jr. Visored hat construction. 4,292,689, Cl. 2-12.000.
- Townsend Engineering Company: See—
Townsend, Ray T., 4,292,710, Cl. 17-21.000.
- Townsend, Ray T., 4,292,889, Cl. 99-533.000.
- Townsend, Ray T., to Townsend Engineering Company. Membrane skinner. 4,292,710, Cl. 17-21.000.
- Townsend, Ray T., to Townsend Engineering Company. Method and means for injecting fluids into meat products. 4,292,889, Cl. 99-533.000.
- Toyo Biseki Kabushiki Kaisha: See—
Isaka, Tsutomu; and Kumada, Saburoh, 4,293,608, Cl. 428-220.000.
- Toyo Biseki Kabushiki Kaisha: See—
Sekino, Masaaki; Chikanari, Kenichi; and Taniyama, Tsukasa, 4,293,419, Cl. 210-321.100.
- Toyo Kogyo Co., Ltd.: See—
Morishita, Teyoshi; Miyake, Kenji; and Tobita, Kouji, 4,292,936, Cl. 123-193.00P.
- Morita, Yasuyuki, 4,293,289, Cl. 418-84.000.
- Toyoda Koki Kabushiki Kaisha: See—
Nishimura, Hideo; Yoneda, Takao; and Enomoto, Minoru, 4,293,913, Cl. 364-474.000.
- Toyooki Kogyo Kabushiki Kaisha: See—
Moriyama, Yoshiki; and Kuwana, Masayuki, 4,293,002, Cl. 137-625.640.
- Toyostar Corporation: See—
Matsuda, Takehiko; and Izawa, Kyoichi, 4,293,745, Cl. 200-52.00R.
- Toyota Jidosha Kogyo Kabushiki Kaisha: See—
Kako, Hiroyoshi; and Arai, Hajime, 4,292,860, Cl. 74-665.0GA.
- Traven, Lars J. C.: See—
Riede, Gerhard; Larsson, Lars-Ake L.; Andersson, Roland J. E.; Jossan, Sven A.; and Traven, Lars J. C., 4,293,409, Cl. 210-96.200.
- Tricca, Raymond A., to Armstrong Cork Company. Electrical outlet insulation system. 4,293,173, Cl. 339-38.000.
- Trishevsky, Igor S.; Trishevsky, Oleg I.; Basy, Vladimir N.; Deber-deev, Rustem J.; Radjukevich, Leonid V.; Anisimov, Vyacheslav I.; Plesnetsov, Jury A.; and Chukhno, Valery V. Mill for making transverse deformations on sheet metal. 4,292,830, Cl. 72-197.000.
- Trishevsky, Oleg I.: See—
Trishevsky, Igor S.; Trishevsky, Oleg I.; Basy, Vladimir N.; Deber-deev, Rustem J.; Radjukevich, Leonid V.; Anisimov, Vyacheslav I.; Plesnetsov, Jury A.; and Chukhno, Valery V., 4,292,830, Cl. 72-197.000.
- Trowbridge, Lawrence E. Converter. 4,293,906, Cl. 363-135.000.
- Trueblood, Richard K., to Zilog, Inc. Low resistance backside preparation for semiconductor integrated circuit chips. 4,293,587, Cl. 427-90.000.
- TRW, Inc.: See—
Wahlers, Richard L.; and Osborne, Vernon E., 4,293,838, Cl. 338-308.000.
- Tsuda, Masabumi: See—
Shimizu, Shinkichi; Nishizaki, Tadao; and Tsuda, Masabumi, 4,293,445, Cl. 252-438.000.
- Tsukada, Haruo; and Nakatani, Yohichiro, to Victor Company of Japan, Ltd. Apparatus for recording and reproducing video signals at selectable different tape traveling speeds from a plurality of pairs of video heads. 4,293,880, Cl. 360-10.000.
- Tsukamoto, Kotaro. Metal wire winding apparatus. 4,293,103, Cl. 242-83.000.
- Tsunekawa, Tokuchi; Masunaga, Makoto; Hosoe, Kazuya; Niwa, Yukichi; Owada, Mitsutoshi; and Asano, Noriyuki, to Canon Kabushiki Kaisha. Photo-sensor device and image scanning system employing the same. 4,293,877, Cl. 358-213.000.
- Tsunoda, Yoshito: See—
Izumita, Morishi; Maeda, Takeshi; Tsunoda, Yoshito; and Sawano, Susumu, 4,293,944, Cl. 369-45.000.
- Tsurumi, Etsuo: See—
Mochida, Hideyuki; Tamura, Shingo; and Tsurumi, Etsuo, 4,293,903, Cl. 363-68.000.
- Tsutsui, Kyoji: See—
Sasaki, Masaomi; Sakai, Kiyoshi; Hashimoto, Mitsuru; Ohta, Masafumi; and Tsutsui, Kyoji, 4,293,492, Cl. 260-160.000.
- Tsuzuki, Yoshihiko; Kaga, Sumihiko; and Hobo, Nobuhito, to Nippondenso Co., Ltd. Apparatus for controlling light projection angle of head lamp of motor vehicle. 4,293,893, Cl. 362-38.000.
- Tucci, John J., to AMP Incorporated. Applicator for metal strain relief clamp. 4,292,732, Cl. 29-749.000.
- Turner, Donald B.: See—
Splitt, Frank G.; and Turner, Donald B., 4,293,887, Cl. 361-120.000.
- Tutida, Tomiyoshi: See—
Fukuda, Takeshi; and Tutida, Tomiyoshi, 4,293,201, Cl. 351-178.000.
- Uchida, Keiichi: See—
Muraoka, Takatoshi; Uchida, Keiichi; Koshino, Minoru; Motegi, Masanori; and Nagasawa, Shigeru, 4,293,941, Cl. 364-200.000.
- Uchiyama, Kazuo: See—
Matsumoto, Hiromitsu; Sugiyama, Keichi; and Uchiyama, Kazuo, 4,292,944, Cl. 123-432.000.
- Uematsu, Tamon: See—
Uemura, Takeaki; Morino, Haruki; Watanabe, Tetsuhiko; and Uematsu, Tamon, 4,293,702, Cl. 548-165.000.
- Ueno, Susumu: See—
Imada, Kiyoshi; Ueno, Susumu; Nishina, Yasuhide; and Nomura, Hirokazu, 4,293,585, Cl. 427-40.000.
- Uetsuki, Tsuneo: See—
Ebata, Yoshihiro; Toibana, Yasuo; Uetsuki, Tsuneo; Kose, Saburo; and Kinoshita, Makoto, 4,293,356, Cl. 156-89.000.
- Uldrikis, Yan R.; Preisa, Ieva E.; Dubur, Gunar Y.; Zidermane, Aina A.; Bisenix, Egils A.; and Tirzit, Gunar D. 2,6-Dimethyl-1,4-dihydroxy-3,5-dicarboxylic acid esters and method for preparing same. 4,293,700, Cl. 546-321.000.
- Ulrich, Charles J.: See—
Szanto, Elmer G.; Wu, George; and Ulrich, Charles J., 4,293,366, Cl. 156-477.00B.
- Ulrich, Max B. Method of and apparatus for pinning a fractured pelvis. 4,292,964, Cl. 128-92.0EB.
- Umeda, Kazuo: See—
Otaki, Yukio; Umeda, Kazuo; and Nakagawa, Kiyoshi, 4,292,799, Cl. 57-246.000.
- Umemura, Takeaki; Morino, Haruki; Watanabe, Tetsuhiko; and Uematsu, Tamon, to Sumitomo Chemical Company, Limited. Method for preparing 4-substituted-N-methylbenzothiazolone derivatives. 4,293,702, Cl. 548-165.000.

- Union Carbide Corporation: See—
Carter, Richard G.; Watson, Stuart L., Jr.; and Pines, Arthur N., 4,293,678, Cl. 528-32.000.
- Gardner, Hugh C., 4,293,686, Cl. 528-192.000.
- Hamer, Anthony D.; and Karol, Frederick J., 4,293,673, Cl. 526-88.000.
- Kokta, Milan R.; and Taylor, Roger W., 4,293,371, Cl. 156-624.000.
- Lustig, Stanley; and Vicik, Stephen J., 4,293,664, Cl. 525-196.000.
- Robeson, Lloyd M.; Matzner, Markus; and Maresca, Louis M., 4,293,670, Cl. 525-436.000.
- United Kingdom Atomic Energy Authority: See—
Sutcliffe, Peter W.; Isaacs, Jim W.; Nelson, Robert L.; Lyon, Colin E.; and Stringer, Brian, 4,293,507, Cl. 264-0.500.
- U.S. Industries, Inc.: See—
Kennedy, Jerome J.; Wayne, Harold S.; and White, Charles A., 4,293,066, Cl. 198-813.000.
- United States of America
Agriculture: See—
Claassen, Ben J., Jr., 4,293,319, Cl. 55-122.000.
- Jacobson, Martin, 4,293,567, Cl. 424-312.000.
- Army: See—
Bird, Alvin N., Jr.; Francis, Norman L.; and Thomas, Albert L., Jr., 4,293,217, Cl. 356-37.000.
- Gutleber, Frank S., 4,293,953, Cl. 375-25.000.
- Lopez, Bennie F.; Campbell, Billy H.; Collier, Bobby D.; Laird, William J.; Debona, Edward J.; and Eubanks, James E., Jr., 4,292,880, Cl. 89-1.815.
- Scott, Richard D., 4,293,864, Cl. 346-76.00L.
- Energy: See—
Barnes, Paul R.; and Shapira, Hanna B., 4,292,763, Cl. 49-64.000.
- Landingham, Richard L.; and Huffsmith, Sarah A., 4,293,619, Cl. 428-623.000.
- McCormick, James T.; Ferry, Paul B.; and Hall, John C., 4,293,089, Cl. 228-215.000.
- National Aeronautics and Space Administration: See—
Winkler, H. Eugene, 4,293,522, Cl. 422-80.000.
- Navy: See—
Bramwell, Frank, 4,293,109, Cl. 244-17.110.
- Brooks, James L.; Bowers, James C.; and Nienhaus, Harry A., 4,293,904, Cl. 363-86.000.
- Denton, Medona B.; and Windsor, David L., 4,293,220, Cl. 356-316.000.
- Fox, Robert B.; and Kim, Oh-Kil, 4,293,452, Cl. 252-518.000.
- Lee, Benjamin Y. S.; Reed, Russell, Jr.; and Miller, Roger L., 4,293,352, Cl. 149-19.400.
- Philippides, Constantinos, 4,293,949, Cl. 371-6.000.
- Stull, Bertram O., 4,293,314, Cl. 44-7.00A.
- Supcoe, Robert F.; and Radakovich, Thomas, 4,293,339, Cl. 106-18.290.
- Yim, Bohyun, 4,293,280, Cl. 416-237.000.
- Transportation: See—
Long, Lennart E.; and Wiseman, Robert L., 4,293,766, Cl. 235-462.000.
- U.S. Philips Corporation: See—
Davio, Marc; and Bioul, Gery J. A., 4,293,922, Cl. 364-757.000.
- Linder, Uno K. E., 4,293,232, Cl. 400-124.000.
- Neukomm, Hans-Rudolf, 4,293,375, Cl. 156-643.000.
- Neukomm, Hans-Rudolf, 4,293,588, Cl. 427-93.000.
- Thillays, Jacques C., 4,292,735, Cl. 29-854.000.
- Vialte, Jean-Pierre, 4,293,954, Cl. 455-54.000.
- United Technologies Corporation: See—
Rannenberg, George C., 4,292,807, Cl. 60-601.000.
- Sederquist, Richard A., 4,293,315, Cl. 48-94.000.
- Shuttleworth, Richard G.; and Snyder, Gene R., 4,293,053, Cl. 181-213.000.
- University of Pittsburgh: See—
Weber, Stephen G., 4,293,310, Cl. 23-230.00B.
- University Patents, Inc.: See—
Jensen, Elwood V.; and Hospelhorn, Verne D., 4,293,536, Cl. 424-1.000.
- Unnai, Takaaki; Izumi, Akiya; and Hinosugi, Misturu, to Hitachi, Ltd. Method for forming a fluorescent screen. 4,293,586, Cl. 427-68.000.
- Uno, Akio: See—
Mikami, Yasuo; Kanda, Hiroshi; and Uno, Akio, 4,293,574, Cl. 426-46.000.
- UOP Inc.: See—
Frame, Robert R., 4,293,442, Cl. 252-428.000.
- Landis, Arthur M.; Broughton, Donald B.; and Fickel, R. Gene, 4,293,346, Cl. 127-46.00A.
- Ward, Dennis J.; and Vora, Bipin V., 4,293,722, Cl. 585-330.000.
- Winter, George R., III, 4,293,387, Cl. 196-14.520.
- Upjohn Company, The: See—
Lewis, Charles; and Birkenmeyer, Robert D., 4,293,547, Cl. 424-180.000.
- Sih, John C., 4,293,708, Cl. 562-503.000.
- Sih, John C., 4,293,709, Cl. 562-503.000.
- Sih, John C., 4,293,710, Cl. 562-503.000.
- Sih, John C., 4,293,711, Cl. 562-503.000.
- Sih, John C., 4,293,712, Cl. 562-503.000.
- Whaley, Howard A.; and Coats, John H., 4,293,651, Cl. 435-169.000.
- Wovcha, Merle G.; and Biggs, Candice B., 4,293,644, Cl. 435-55.000.
- Wovcha, Merle G.; Biggs, Candice B.; and Pyke, Thomas R., 4,293,645, Cl. 435-55.000.
- Wovcha, Merle G.; and Brooks, Kevin E., 4,293,646, Cl. 435-55.000.
- Upp, Daniel C.: See—
Kuras, Michael L.; Upp, Daniel C.; and Toegel, Herbert J., 4,293,946, Cl. 370-62.000.
- Uranium Recovery Corporation: See—
Reese, Stanton L.; and Schroeder, William E., 4,293,529, Cl. 423-10.000.
- USM Corporation: See—
Gilbride, Andrew J.; and Wickers, Francis A., 4,292,907, Cl. 112-236.000.
- Maxner, Richard B., 4,292,727, Cl. 29-566.300.
- Vacuumschmelze GmbH: See—
Hilzinger, Hans-Reiner; and Hillmann, Hans, 4,293,023, Cl. 164-479.000.
- Vadasz, Kalman, to Chemicasa GmbH. Process for the preparation of sweetener containing product. 4,293,570, Cl. 426-3.000.
- Valenta, Joseph R.: See—
Nash, Claude H., III; Shearer, Marcia C.; Snader, Kenneth M.; Valenta, Joseph R.; and Cooper, David, 4,293,546, Cl. 424-119.000.
- Vallaude, Jean-Pierre, to Regie Nationale des Usines Renault. Piston for internal combustion engines. 4,292,937, Cl. 123-193.00P.
- Van Benthuyssen, John D.; and Osburn, Carlton M., to CTS Corporation. Process for producing an on-off push switch and resulting article. 4,293,751, Cl. 200-156.000.
- Van Cauter, Albert: See—
Terneu, Robert; and Van Cauter, Albert, 4,293,326, Cl. 65-60.00D.
- Vander Kaay, Henry A.: See—
Carlson, Allen J.; and Vander Kaay, Henry A., 4,293,284, Cl. 417-218.000.
- van der Lely, Ary; and Bom, Cornelis J. G., to C. van der Lely N.V. Shear pin coupling. 4,292,819, Cl. 64-28.00R.
- van Deuren, Franciscus, to Simon-Heesen B.V. Pelleting press. 4,293,295, Cl. 425-331.000.
- Van Herpe, Francois: See—
De Busscher, Cyriel R. J.; and Van Herpe, Francois, 4,292,981, Cl. 130-27.00F.
- van Mil, Martinus P. G., to Stork PMT B.V. Picking element for a poultry picking apparatus. 4,292,709, Cl. 17-11.10R.
- Van Reyersdal, Joseph, to Sperry Corporation. Bubble detection system. 4,293,930, Cl. 365-8.000.
- Van Steenwyk, Donald H., to Applied Technologies Associates. Survey apparatus, method employing angular accelerometer. 4,293,046, Cl. 175-45.000.
- Van Trang, Nguyen. Automatic control system for carwash installations. 4,293,914, Cl. 364-478.000.
- Van Vechten, James A.: See—
Chaudhari, Praveen; Chou, Ned J.; Feder, Ralph; Fowler, Alan B.; and Van Vechten, James A., 4,293,374, Cl. 156-628.000.
- Varadi, Peter F.; and Dominguez, Ramon, to Solarex Corporation. Battery charging device employing solar cells. 4,293,808, Cl. 320-2.000.
- Varsane, Robert G., to Vitramon Incorporated. Ceramic capacitor with end terminals. 4,293,890, Cl. 361-310.000.
- Vasiljuk, Petr J.: See—
Ragoza, Igor V.; Begunov, Petr M.; Tonikian, Robert T.; and Vasiljuk, Petr J., 4,292,820, Cl. 66-8.000.
- Vavrek, Robert M., to General Electric Company. X-Ray table for obtaining longitudinal and lateral oblique cardiovascular views. 4,293,770, Cl. 250-445.00R.
- VEB Werk fur Fernsehlektronik Berlin im VEB Kombinat Mikroelektronik: See—
Deutscher, Hans-Joachim; Schubert, Hermann; Seidel, Christina; Demus, Dietrich; and Kresse, Horst, 4,293,434, Cl. 252-299.630.
- Vela, Octavio A.: See—
Sharp, H. Eugene; Vela, Octavio A.; and Smither, Mils A., 4,293,937, Cl. 367-82.000.
- Velenyi, Louis J.; Dolhyj, Serge R.; and Sundeen, Marcia H., to Standard Oil Company, The. Manufacture of hydroperoxides. 4,293,719, Cl. 568-573.000.
- Velo-Bind, Inc.: See—
Szanto, Elmer G.; Wu, George; and Ulrich, Charles J., 4,293,366, Cl. 156-477.00B.
- Veralrud, Guy G., to Kustom Kreations, Inc. Cabinet for holding magnetic tape cartridges and cassettes. 4,293,075, Cl. 211-40.000.
- Verge, John P.: See—
Jamieson, William B.; Ross, William J.; Simmonds, Robin G.; and Verge, John P., 4,293,563, Cl. 424-273.00R.
- Vermont Log Buildings, Inc.: See—
White, Thomas M.; Barton, Edwin A.; and Ware, Jesse P., 4,293,011, Cl. 144-3.00R.
- Vernon, Michel, to K.R.P. Plastiques. Processes and production apparatus for rigid cellular materials comprising polyvinyl chloride. 4,293,511, Cl. 264-55.000.
- Vicik, Stephen J.: See—
Lustig, Stanley; and Vicik, Stephen J., 4,293,664, Cl. 525-196.000.
- Victor Company of Japan, Ltd.: See—
Tsukada, Haruo; and Nakatani, Yohichiro, 4,293,880, Cl. 360-10.000.
- Victor Products (Wallend) Limited: See—
Roberts, Frank B., 4,293,799, Cl. 315-256.000.
- Vigar, James M. L., to International Business Machines Corporation. Process for the deposition of thick chromium films from trivalent chromium plating solutions and article so produced. 4,293,620, Cl. 428-667.000.

- Viking Industries, Inc.: See—
Ellis, James D., 4,292,771, Cl. 52-98.000.
- Vilatte, Jean-Pierre, to U.S. Philips Corporation. Receiving system for transmitting information transmitted by a mobile transmitter to a central station. 4,293,954, Cl. 455-54.000.
- Villa-Real, Antony-Euclid C. Electronic multi-patient medication-time-intake programmer and alarm system. 4,293,845, Cl. 340-309.300.
- Vinals, Joaquin F.: See—
Sprecker, Mark A.; Sanders, James M.; Schreiber, William L.; Watkins, Hugh; Vinals, Joaquin F.; Shuster, Edward J.; O'Rourke, Thomas J.; Hagedorn, Myrna L.; and Klemarczyk, Philip, 4,293,453, Cl. 252-522.00R.
- Virginia Industries, Inc.: See—
Mullen, H. Gerald, 4,292,717, Cl. 29-148.40A.
- Vis, Arthur D.; and Feinberg, Billie, to Candid Logic, Inc. Self-actuated displacement transducer. 4,292,740, Cl. 33-172.00E.
- Vitau, Jean. Setting and method for mounting precious stones and the like therein. 4,292,818, Cl. 63-28.000.
- Vitramon Incorporated: See—
Varsane, Robert G., 4,293,890, Cl. 361-310.000.
- Vock, Manfred H.: See—
Shu, Chi-Kuen; Mookherjee, Braja D.; and Vock, Manfred H., 4,293,579, Cl. 426-535.000.
- Vogel, Charles B.: See—
Herolz, Robert A.; and Vogel, Charles B., 4,293,934, Cl. 367-27.000.
- Vogel, F. Lincoln. Process for conducting electricity utilizing a specifically defined graphite intercalation compound. 4,293,450, Cl. 252-503.000.
- Vollenweider, Max: See—
Maag, Willi; Baumgartner, Hans U.; Vollenweider, Max; and Wolf, Hans J., 4,292,769, Cl. 51-169.000.
- Volvo Flygmotor AB: See—
Larsson, Leif; and Warren, Richard, 4,292,725, Cl. 29-419.00R.
- von Basewitz, Henning: See—
Schweig, Helmut; and von Basewitz, Henning, 4,293,731, Cl. 136-245.000.
- Vonder, David L., to GTE Automatic Electric Labs Inc. Circuit board interconnection system. 4,293,179, Cl. 339-176.0MP.
- Vora, Bipin V.: See—
Ward, Dennis J.; and Vora, Bipin V., 4,293,722, Cl. 585-330.000.
- Voronin, Rostislav A.: See—
Dunaevsky, Vladimir I.; Boidenko, Nikolai G.; Samarin, Alexei P.; Levit, Viktor M.; Zapara, Boris M.; Ivanov, Boris N.; Frolov, Sergei A.; Voronin, Rostislav A.; Belozero, Nikolai P.; Momot, Valery I.; Stusenko, Jury A.; and Samoilov, Vladimir A., 4,293,101, Cl. 242-56.400.
- Vroom, Alan H. Sulphur cements, process for making same and sulphur concretes made therefrom. 4,293,463, Cl. 260-42.240.
- W. R. Grace & Co.: See—
Cogliano, Joseph A., 4,293,679, Cl. 528-48.000.
- Dudley, Hubert T.; and Bragg, Ralph J., 4,293,341, Cl. 106-88.000.
- Hill, Richard N., 4,293,311, Cl. 23-301.000.
- Wacker, Albert R., to Cabot Corporation. Method for ultrasonically welding plasticized thermoplastic polymeric foam wares. 4,293,355, Cl. 156-73.200.
- Wada, Shigetaka, to NGK Insulators, Ltd. Method of producing honeycomb structural bodies consisting of barium titanate series ceramics having a positive temperature coefficient of electric resistance. 4,293,514, Cl. 264-61.000.
- Wada, Shinzi; Kitao, Ikuo; Oana, Yoshinori; Kato, Yasuo; and Ishihara, Takatoshi, to Tokyo Kogaku Kikai Kaisha. Apparatus for detecting astigmatic axes and measuring refractive powers. 4,293,199, Cl. 351-13.000.
- Wade, Peter C.: See—
Haugwitz, Rudiger D.; Wade, Peter C.; and Maurer, Barbara V., 4,293,569, Cl. 424-300.000.
- Wagner, Karl; Engelsmann, Dieter; Hackenberg, Hubert; and Stiefel, Peter, to AGFA-Gevaert Aktiengesellschaft. Photographic camera having an automatic exposure control. 4,293,204, Cl. 354-21.000.
- Wagner, William R., to Rockwell International Corporation. Low nitrous oxide (NOX) precombustor. 4,292,935, Cl. 123-285.000.
- Wahlers, Richard L.; and Osborne, Vernon E., to TRW, Inc. Resistance material, resistor and method of making the same. 4,293,838, Cl. 338-308.000.
- Waimea Company Inc.: See—
Donan, David C., Jr., 4,293,244, Cl. 405-259.000.
- Wainio, Ronald: See—
Date, K. Henry; and Wainio, Ronald, 4,293,834, Cl. 335-76.000.
- Wakabayashi, Makoto; and Takagishi, Haruyoshi, to Nissan Motor Company Limited. Panel assembling method. 4,293,363, Cl. 156-272.000.
- Wakabayashi, Takao, to Nakanishi Metal Works Co., Ltd. Trolley rotation stabilizing device. 4,292,897, Cl. 104-172.00S.
- Walbar Metals, Inc.: See—
Rose, Bernard R.; and Willis, John K., 4,293,338, Cl. 75-253.000.
- Waldmann, Helmut; Schwerdtel, Wulf; and Swodenk, Wolfgang, to Bayer Aktiengesellschaft. Process for preparing aldehydes and diols. 4,293,717, Cl. 568-485.000.
- Walker, Keith A. M., to Syntex (U.S.A.) Inc. 1-(Naphthyl-n-propyl)-imidazole derivatives. 4,293,561, Cl. 424-273.00R.
- Walker, Robert J. Easy opening and secure closing closure. 4,292,714, Cl. 24-30.50R.
- Wallace, Joseph E., to Parker-Hannifin Corporation. Segmented seal. 4,293,135, Cl. 277-9.000.
- Wallace Murray Corporation: See—
George, Larry T., 4,293,136, Cl. 277-12.000.
- Wallin, Carl O. H. Winch arrangement. 4,293,121, Cl. 254-370.000.
- Wallis, Bernard J. Unitary punch and die assembly. 4,292,869, Cl. 83-137.000.
- Walter, Lothar: See—
Ernst, Horst M.; Olschewski, Armin; Schurger, Rainer; Walter, Lothar; Brandenstein, Manfred; and Burkl, Erich, 4,293,166, Cl. 308-6.00C.
- Walters, Ronald G., to Technicare Corporation. Tomographic apparatus. 4,293,912, Cl. 364-414.000.
- Wang, Daniel I. C.: See—
Levine, David W.; Thilly, William G.; Wang, Daniel I. C.; and Wong, Jason S., 4,293,654, Cl. 435-241.000.
- Wang, Wei Ko; Hoh, Ying-Chu; Chuang, Wen-Shou; and Shaw, I-Sine, to Institute of Nuclear Energy Research. Hydrometallurgical process for recovering precious metals from anode slime. 4,293,332, Cl. 75-99.000.
- Wang, Yu-Chang J.: See—
Fawelchak, John M.; Wang, Yu-Chang J.; and LaVia, Anthony L., 4,292,972, Cl. 128-296.000.
- Ward, Dennis J.; and Vora, Bipin V., to UOP Inc. Process for conversion of propane to gasoline. 4,293,722, Cl. 585-330.000.
- Ware, Jesse P.: See—
White, Thomas M.; Barton, Edwin A.; and Ware, Jesse P., 4,293,011, Cl. 144-3.00R.
- Warner, Allan S. Sensing and control apparatus for a commutator. 4,293,805, Cl. 318-39.000.
- Warner & Swasey Company, The: See—
Kirk, Calvin K.; Joyce, Glover C.; and Messier, Francis L., 4,292,766, Cl. 51-105.0SP.
- Warnke, Hans: See—
Boer, Werner; Lachner, Hans; Maschon, Guenter; Richter, Joerg; Schulte, Heinrich; and Warnke, Hans, 4,293,246, Cl. 405-291.000.
- Warren, Richard: See—
Larsson, Leif; and Warren, Richard, 4,292,725, Cl. 29-419.00R.
- Wasik, Chester A.: See—
Gaston, Charles A.; Kirk, Joseph P.; and Wasik, Chester A., 4,293,224, Cl. 356-357.000.
- Wasserman, Kurt J., to Insolar Inc. Corrugated panel solar collector. 4,292,956, Cl. 126-439.000.
- Wasserman, Philip D., to Stanford Associates, Inc. Non-linear function generator. 4,293,917, Cl. 364-701.000.
- Watanabe, Eiki, to Mitsubishi Denki Kabushiki Kaisha. Device for grounding an elevator winder. 4,293,889, Cl. 361-212.000.
- Watanabe, Koichiro: See—
Tokutomi, Seiji; Jyojiki, Masao; Aoki, Harumi; Nakamura, Kazuo; and Watanabe, Koichiro, 4,293,206, Cl. 354-25.000.
- Watanabe, Masatoshi: See—
Ito, Motoya; Sato, Masaki; Watanabe, Masatoshi; and Okuda, Hironori, 4,293,787, Cl. 310-181.000.
- Watanabe, Tetsuhiko: See—
Umamura, Takeaki; Morino, Haruki; Watanabe, Tetsuhiko; and Uematsu, Tamon, 4,293,702, Cl. 548-165.000.
- Watkins, Hugh: See—
Sprecker, Mark A.; Sanders, James M.; Schreiber, William L.; Watkins, Hugh; Vinals, Joaquin F.; Shuster, Edward J.; O'Rourke, Thomas J.; Hagedorn, Myrna L.; and Klemarczyk, Philip, 4,293,453, Cl. 252-522.00R.
- Watson, Stuart L., Jr.: See—
Carter, Richard G.; Watson, Stuart L., Jr.; and Pines, Arthur N., 4,293,678, Cl. 528-32.000.
- Waugh, Robert E., to D. L. Auld Company, The. Method for making decorative emblems. 4,292,827, Cl. 72-46.000.
- Wayne, Harold S.: See—
Kennedy, Jerome J.; Wayne, Harold S.; and White, Charles A., 4,293,066, Cl. 198-813.000.
- Webasto-Werk W. Baier GmbH & Co.: See—
Lutz, Alfons, 4,293,161, Cl. 296-213.000.
- Webb, Orlando: See—
Kolb, Norman P.; and Webb, Orlando, 4,293,729, Cl. 585-715.000.
- Weber, Adolf; and Rhau, Siegfried, to Diehl GmbH & Co. Process for the production of metallic formed members. 4,292,829, Cl. 72-76.000.
- Weber, Hermann: See—
Sommer, Klaus; Klemm, Walter; Weber, Hermann; Meinhardt, Frederick; Schonmann, Gerhard; and Spatz, Wilhelm, 4,293,526, Cl. 422-205.000.
- Weber Industries, Inc.: See—
Weber, Walter L., 4,293,288, Cl. 417-434.000.
- Weber, Max, to Sulzer Brothers Limited. Nuclear reactor plant for generating process heat. 4,293,384, Cl. 376-391.000.
- Weber, Stephen G., to University of Pittsburgh. Photoelectrochemical immunoassay. 4,293,310, Cl. 23-230.00B.
- Weber, Walter L., to Weber Industries, Inc. Submersible pump housing. 4,293,288, Cl. 417-434.000.
- Weber, William R. Hydraulic actuator cushioning device improvement. 4,292,886, Cl. 92-85.00B.
- Webster, Frank G.; Regan, Michael T.; and Rossi, Louis J., to Eastman Kodak Company. Electrophotosensitive materials for migration imaging processes. 4,293,626, Cl. 430-17.000.
- Wei, Peter H. L.; and Bell, Stanley C., to American Home Products Corporation. 3-Substituted phenylthiazolo[3,2':1,2]imidazo[4,5-b]pyridine-2-alkanoic acids. 4,293,696, Cl. 546-83.000.
- Weidemann, Dieter: See—
Lutze, Hans; Weissappel, Helmut; Klie, Wolfgang; and Weidemann, Dieter, 4,293,160, Cl. 296-188.000.

- Weinberg, Norman L., to Minrad Corporation. Radiographic image enhancement. 4,293,640, Cl. 430-421.000.
- Weingand, Kaspar, to Siemens Aktiengesellschaft. Method of producing perforated glass plate. 4,293,376, Cl. 156-644.000.
- Weis, Rudolf R.: See—
Geyer, Joseph E.; Rehr, Henry W.; Schutz, Rudolph W.; and Weis, Rudolf R., 4,293,365, Cl. 156-364.000.
- Weisenburger, Lawrence P., to AMP Incorporated. Flat cable connector. 4,293,177, Cl. 339-99.00R.
- Weiss, Martin J.: See—
Bernady, Karel F.; Floyd, Middleton B., Jr.; Poletto, John F.; Schaub, Robert E.; and Weiss, Martin J., 4,293,704, Cl. 556-442.000.
- Weissel, Oskar; Serini, Volker; and Buysch, Hans-Josef, to Bayer Aktiengesellschaft. Tetraalkylated bicyclohexylamine derivatives. 4,293,687, Cl. 528-346.000.
- Weissappel, Helmut: See—
Lutze, Hans; Weissappel, Helmut; Klie, Wolfgang; and Weidemann, Dieter, 4,293,160, Cl. 296-188.000.
- Weithman, John A.: See—
Royer, George R., 4,293,733, Cl. 174-67.000.
- Welch, John A.: See—
Bible, Dennis E.; Crano, Richard N.; and Welch, John A., 4,293,016, Cl. 152-158.000.
- Wells, Alton R.; Wells, Robert M.; and Heir, James L. Fountain pump for electric coffee percolators. 4,292,888, Cl. 99-312.000.
- Wells, Robert M.: See—
Wells, Alton R.; Wells, Robert M.; and Heir, James L., 4,292,888, Cl. 99-312.000.
- Welsh, David M.: See—
Morrey, William B.; and Welsh, David M., 4,292,896, Cl. 102-275.800.
- Weman, Per O., to Allied Chemical Corporation. Bi-level web sensitive retractor. 4,293,105, Cl. 242-107.40B.
- Werffeli, Hermann, to Maschinenfabrik Schweizer AG. Textile spooling machine, an apparatus and method to prevent the formation of loose cut thread pieces. 4,292,868, Cl. 83-13.000.
- Werneke, Michael F.; and Jones, James A., to American Cyanamid Company. Synergistic promoter combination for zinc sulfide ores. 4,293,406, Cl. 209-166.000.
- Werner, Nils H.: See—
Millgard, Ulf J.; Lindberg, Ulf W.; Anneslod, Weimar A.; Werner, Nils H.; and Wemelius, Bjorn, 4,293,607, Cl. 428-212.000.
- Werst, Lyman L., to Parks-Cramer Company. Textile machine data link apparatus. 4,292,800, Cl. 57-264.000.
- Weselo, Roger J.; Kanjo, Wajih; and Karim, Syed, to American Standard Inc. Crimping device for use in assembling an overtravel spring assembly for slack adjuster. 4,292,721, Cl. 29-243.520.
- Wesley, William M., to Creative Tool Company. Compression rate analyzer. 4,292,841, Cl. 73-119.00A.
- Wesselman, Bernard W.: See—
Tepe, James R.; Sandor, Robert P.; Wesselman, Bernard W.; and Woeste, David R., 4,293,027, Cl. 165-12.000.
- West, Jerry B.; Kretzschmar, John L.; and Fung, Bing, to Century Geophysical Corporation. Fluxgate magnetometer circuit with earth's field elimination. 4,293,815, Cl. 324-254.000.
- West Point Pepperell, Inc.: See—
Davis, Gayron N.; Sellers, Larry S.; and Hagborg, Winston E., 4,292,918, Cl. 118-33.000.
- Westinghouse Electric Corp.: See—
Church, Larry L.; Smith, David R.; and Sun, Shan C., 4,293,886, Cl. 361-71.000.
- Glenn, Robert G., 4,292,810, Cl. 60-757.000.
- Perulfi, John R., 4,293,747, Cl. 200-145.000.
- Yoldas, Bulent E., 4,293,593, Cl. 427-106.000.
- Yoldas, Bulent E.; and Mattox, Douglas M., 4,293,594, Cl. 427-107.000.
- Wetterlin, Kjell I. L.: See—
Mono, Rune G.; Moren, Nils F. E.; and Wetterlin, Kjell I. L., 4,292,966, Cl. 128-200.230.
- Weyand, Harley P., Jr.: See—
Loeffler, Earl F.; and Weyand, Harley P., Jr., 4,293,358, Cl. 156-131.000.
- Weyerhaeuser Company: See—
Gerard, Thomas J., 4,293,091, Cl. 229-27.000.
- Grant, Peter S., 4,293,155, Cl. 294-75.000.
- Whaley, Howard A.; and Coats, John H., to Upjohn Company, The. Process for producing antibiotic using saccharopolyspora. 4,293,651, Cl. 435-169.000.
- Wheaton, John E. G.; Griffiths, David; and Learner, Richard C. M., to Chelsea Instruments Limited. Underwater fluorometer measuring system. 4,293,225, Cl. 356-417.000.
- Wheless, Leon L., Jr.: See—
Kay, David B.; Wheless, Leon L., Jr.; and Cambier, James L., 4,293,221, Cl. 356-318.000.
- Whelan, Paul L., to Texas Instruments Incorporated. Material handling system and method for manufacturing line. 4,293,249, Cl. 406-72.000.
- Whirlpool Corporation: See—
Paddock, Stephen W., 4,292,813, Cl. 62-158.000.
- White, Charles A.: See—
Kennedy, Jerome J.; Wayne, Harold S.; and White, Charles A., 4,293,066, Cl. 198-813.000.
- White, John E., to AEL Mirrotel, Ltd. Transformerless fast current limiter with symmetry correction for a switched-mode power supply. 4,293,902, Cl. 363-26.000.
- White, Preston S.: See—
Darlington, William B.; DuBois, Donald W.; and White, Preston S., 4,293,394, Cl. 204-98.000.
- White, Thomas M.; Barton, Edwin A.; and Ware, Jesse P., to Vermont Log Buildings, Inc. Rafter cutting machine. 4,293,011, Cl. 144-3.00R.
- Whitehurst, Darrell D.: See—
Farcasiu, Malvina; and Whitehurst, Darrell D., 4,293,404, Cl. 208-214.000.
- White's Electronics, Inc.: See—
Johnson, Douglas L., 4,293,816, Cl. 324-329.000.
- Whitney, Thomas A.: See—
Klemann, Lawrence P.; Newman, Gerald H.; Stogryn, Eugene L.; Whitney, Thomas A.; and Farcasiu, Dan, 4,293,623, Cl. 429-194.000.
- Wickers, Francis A.: See—
Gilbride, Andrew J.; and Wickers, Francis A., 4,292,907, Cl. 112-236.000.
- Widmer, Hans, to Fritz Gegauf AG, Bernina-Nachmaschinenfabrik Steckborn. Data display device for sewing machine adjustment and set-up. 4,292,905, Cl. 112-121.110.
- Wiget, Fridolin, to Ebauches S.A. Apparatus for measuring the rate of an analog-display electronic timepiece. 4,292,836, Cl. 73-6.000.
- Wikel, James W.: See—
Paget, Charles J.; Chamberlin, James W.; and Wikel, James W., 4,293,558, Cl. 424-270.000.
- Wilhelm, Rudolf: See—
Heitmann, Jurgen; Maly, Hans-Peter; and Wilhelm, Rudolf, 4,293,879, Cl. 360-10.000.
- Wilhoite, Murray O., to Martin Industries, Inc. Wood burning heater. 4,292,954, Cl. 126-290.000.
- Wilkes, Colin; and Hilt, Milton B., to General Electric Company. Dual stage-dual mode low nox combustor. 4,292,801, Cl. 60-39.060.
- Willard, Alvin K., to Merck & Co., Inc. 6(R)-[2-(8-Hydroxy-2,6-dimethylpolyhydronaphthyl-1-ethyl)]-4(R)-hydroxy-3,4,5,6-tetrahydro-2H-pyran-2-ones. 4,293,496, Cl. 260-343.500.
- William R. Selwood Limited: See—
Burton, John D., 4,293,285, Cl. 417-240.000.
- Williams, Clarence E. Frictional retainer for holding a door open. 4,292,707, Cl. 16-48.500.
- Williams, David L.: See—
Brogdon, Vas H.; and Williams, David L., 4,293,276, Cl. 416-134.00A.
- Williams, Garnet M. E.; Hutton, Stanley P.; and Bushman, John A., to Ferraris Development and Engineering Co., Ltd. Fluid flow measuring apparatus. 4,292,853, Cl. 73-861.790.
- Williams, Jarvis L. Television monitoring system. 4,293,876, Cl. 358-211.000.
- Williams, Thomas W.: See—
Dasgupta, Sumit; Goel, Prabhakar; and Williams, Thomas W., 4,293,919, Cl. 364-716.000.
- Williams, William H., to Sandstone, Inc. Anti-theft screen construction. 4,293,778, Cl. 307-147.000.
- Willis, John K.: See—
Rose, Bernard R.; and Willis, John K., 4,293,338, Cl. 75-253.000.
- Wilson, Robert B., to Northwestern Laboratories, Inc. Diester composition and textile processing compositions therefrom. 4,293,305, Cl. 8-115.600.
- Wilson Trailer Company: See—
Lewis, Mack A.; and Spencer, Mike R., 4,293,158, Cl. 296-24.00C.
- Wimelius, Bjorn: See—
Millgard, Ulf J.; Lindberg, Ulf W.; Anneslod, Weimar A.; Werner, Nils H.; and Wemelius, Bjorn, 4,293,607, Cl. 428-212.000.
- Windsor, David L.: See—
Denton, Medona B.; and Windsor, David L., 4,293,220, Cl. 356-316.000.
- Winegard Company: See—
Winegard, John R.; Shelledy, Carey W.; and Cowan, Keith B., 4,293,861, Cl. 343-766.000.
- Winegard, John R.; Shelledy, Carey W.; and Cowan, Keith B., to Winegard Company. Compact television antenna system. 4,293,861, Cl. 343-766.000.
- Wing, Paul, to Masonell International, Inc. Erosion resistant valve. 4,292,991, Cl. 137-329.050.
- Winiasz, Michael E., to Clark-Reliance Corp., The. Pressure reducing valve. 4,292,998, Cl. 137-489.500.
- Winiasz, Michael E., to A-T-O Inc. Adjustable volumetric filler head. 4,293,010, Cl. 141-392.000.
- Winkler, H. Eugene, to United States of America, National Aeronautics and Space Administration. Electrophotolysis oxidation system for measurement of organic concentration in water. 4,293,522, Cl. 422-80.000.
- Winter, George R., III, to UOP Inc. Apparatus for the solvent extraction of aromatic hydrocarbons from a hydrocarbon mixture. 4,293,387, Cl. 196-14.520.
- Wirostko, Emil; and Johnson, Lewis A. Method for treatment of human eye disease. 4,293,568, Cl. 424-330.000.
- Wisconsin Alumni Research Foundation: See—
Bradley, Robert L., Jr.; and Hekmati, Majid, 4,293,573, Cl. 426-43.000.
- Wiseman, Robert L.: See—
Long, Lennart E.; and Wiseman, Robert L., 4,293,766, Cl. 235-462.000.
- Woeste, David R.: See—
Tepe, James R.; Sandor, Robert P.; Wesselman, Bernard W.; and Woeste, David R., 4,293,027, Cl. 165-12.000.

- Wolcott, Judith: See—
Champion, Carolyn; Wolcott, Judith; Hart, Barbara; and Garcia, Zulma C., 4,292,975, Cl. 128-498.000.
- Wolf, Hans J.: See—
Maag, Willi; Baumgartner, Hans U.; Vollenweider, Max; and Wolf, Hans J., 4,292,769, Cl. 51-169.000.
- Wong, Chung-Chee, to Kong, San P. Battery-operated lantern. 4,293,896, Cl. 362-200.000.
- Wong, Dennis W. Novel chemical method of labeling proteins with ^{99m}Tc-Technetium at physiological condition. 4,293,537, Cl. 424-1.000.
- Wong, Jason S.: See—
Levine, David W.; Thilly, William G.; Wang, Daniel I. C.; and Wong, Jason S., 4,293,654, Cl. 435-241.000.
- Wong, Tai W.: See—
Merrifield, Robert B.; and Wong, Tai W., 4,293,455, Cl. 260-8.000.
- Wood, John F.: See—
Leeper, Charles G.; and Wood, John F., 4,293,020, Cl. 157-1.280.
- Wood, Robert: See—
Olofsson, Mats; Buhler, Marcel; and Wood, Robert, 4,293,571, Cl. 426-7.000.
- Wooderson, Charles R. Vehicular pet anchor. 4,292,932, Cl. 119-109.000.
- Woodward, Robert B.; and Bickel, Hans, to Ciba-Geigy Corporation. Process for the manufacture of enol derivatives, and intermediates. 4,293,462, Cl. 260-239.00A.
- Wool Development International Limited: See—
Gore, Colin E.; and Coulter, John P., 4,292,798, Cl. 57-86.000.
- World Carpets, Inc.: See—
Toland, James, 4,292,822, Cl. 68-5.00D.
- Worsham, Daniel A., to Pacific Western Systems, Inc. Renewable nut for a lead screw drive and method of making same. 4,292,722, Cl. 29-402.210.
- Wovcha, Merle G.; and Biggs, Candice B., to Upjohn Company, The. Process for preparing androst-4-ene-3,17-dione. 4,293,644, Cl. 435-55.000.
- Wovcha, Merle G.; Biggs, Candice B.; and Pyke, Thomas R., to Upjohn Company, The. Process for preparing androsta-1,4-diene-3,17-dione and androst-4-ene-3,17-dione. 4,293,645, Cl. 435-55.000.
- Wovcha, Merle G.; and Brooks, Kevin E., to Upjohn Company, The. Composition of matter and process. 4,293,646, Cl. 435-55.000.
- Woychick, John, to Land-O-Nod. Water bed construction with enclosure. 4,292,701, Cl. 5-422.000.
- Wrede, Hans: See—
Nestler, Johannes; and Wrede, Hans, 4,293,779, Cl. 307-252.00C.
- Wright, Luther M., deceased: See—
Roshborough, Robert S., Jr.; and Wright, Luther M., deceased, 4,293,215, Cl. 355-40.000.
- Wright, Michael J., to Newage Engineers Limited. Control systems for electric generators. 4,293,810, Cl. 322-28.000.
- Wright, Ralph W.: See—
Flusche, Frederick O.; Tan, Kwang G.; and Wright, Ralph W., 4,293,910, Cl. 364-200.000.
- Wright, Wade S.: See—
Fellman, Marc M.; and Wright, Wade S., 4,293,131, Cl. 273-121.00A.
- Wu, George: See—
Szanto, Elmer G.; Wu, George; and Ulrich, Charles J., 4,293,366, Cl. 156-477.00B.
- Wynn Oil Company: See—
Babish, John A.; Arnot, Larry K.; and Appel, Douglas C., 4,293,031, Cl. 165-95.000.
- Xerox Corporation: See—
Dickerson, Charles G.; and Erhardt, Peter F., 4,293,632, Cl. 430-137.000.
- George, Clifford L.; and Olson, Jon S., 4,293,214, Cl. 355-14.00R.
- Huggins, Raymond W., 4,292,923, Cl. 118-658.000.
- Lindblad, Nero R.; Rezanka, Ivan; and Cassidy, John V., 4,292,924, Cl. 118-658.000.
- Lu, Chin H., 4,293,631, Cl. 430-106.000.
- Murphy, Cornelius B.; and Sypula, Donald S., 4,293,627, Cl. 430-39.000.
- Scifres, Donald R.; Burnham, Robert D.; and Streifer, William, 4,293,826, Cl. 331-94.50H.
- Yabuuchi, Takahiro: See—
Fujimura, Hajime; Hiramatsu, Yasuzo; Yabuuchi, Takahiro; Hisaki, Masakatu; Takikawa, Katsuo; Honna, Takaji; Miyake, Hidekazu; and Kajitani, Makoto, 4,293,713, Cl. 564-38.000.
- Yamada, Tsuneo; and Miyamoto, Yukihiko. Monostable multivibrator. 4,293,781, Cl. 307-273.000.
- Yamaguchi, Hisao; and Fujisawa, Kazuo, to Sumitomo Metal Industries, Ltd. Method for correcting the sensitivity of an electromagnetic ultrasonic probe. 4,292,849, Cl. 73-643.000.
- Yamaguchi, Shigehiro: See—
Ichiyama, Tadashi; Yamaguchi, Shigehiro; Iuchi, Tohru; and Kuroki, Katsuro, 4,293,350, Cl. 148-111.000.
- Yamaha Hatsukoki Kabushiki Kaisha: See—
Matsumoto, Hiromitsu; Sugiyama, Keiichi; and Uchiyama, Kazuo, 4,292,944, Cl. 123-432.000.
- Yamakoshi, Nobuaki: See—
Shibata, Kenyu; Itaya, Toshihisa; Yamakoshi, Nobuaki; Kurata, Shigeru; Koizumi, Naoyuki; Tarutani, Masaaki; Sakuma, Hideki; and Konishi, Kunihiro, 4,293,557, Cl. 424-267.000.
- Yamauchi, Toshima; Nogami, Sadao; Sawada, Kengi; Moriya, Jyunchiro; Sawada, Hiroomi; and Kobayashi, Keizou, to Kabushiki Kai-
- sha Kurio-Medikaru. Apparatus for refrigeration treatment. 4,292,973, Cl. 128-303.100.
- Yamauchi, Yukio: See—
Sawa, Hiroshi; and Yamauchi, Yukio, 4,292,844, Cl. 73-359.00A.
- Yamazaki, Yasuo; and Egawa, Takeshi, to Minolta Camera Kabushiki Kaisha. Optical conversion assembly for objective camera lenses. 4,293,185, Cl. 350-18.000.
- Yamazaki, Yoshio; Kamogawa, Nin-ichi; and Iwai, Yasuyuki, to Konishiroku Photo Industry Co., Ltd. Developing device for an electro-photographic copying machine. 4,292,922, Cl. 118-657.000.
- Yanagisawa, Hifumi: See—
Sakuma, Shinzo; and Yanagisawa, Hifumi, 4,293,748, Cl. 200-144.00B.
- Yano, Teruo: See—
Higuchi, Noboru; Yano, Teruo; and Ohnishi, Masahiro, 4,293,357, Cl. 156-89.000.
- Yates, George, Jr., to Growth International Industries Corp. Container with collar. 4,293,073, Cl. 206-519.000.
- Yazu, Shuji: See—
Hara, Akio; and Yazu, Shuji, 4,293,618, Cl. 428-551.000.
- Yello, Joseph F., to Zenith Radio Corporation. Raster-centering circuit. 4,293,804, Cl. 315-398.000.
- Yeo, Norman H.: See—
Swanson, Douglas L.; and Yeo, Norman H., 4,292,734, Cl. 29-791.000.
- Yesuratnam, Richard J. Fish landing net. 4,292,753, Cl. 43-5.000.
- Yim, Bohyun, to United States of America, Navy. Transcavitating propeller. 4,293,280, Cl. 416-237.000.
- Yokozawa, Norio: See—
Shibayama, Akinori; Maio, Kenji; and Yokozawa, Norio, 4,293,819, Cl. 330-9.000.
- Yoldas, Bulent E., to Westinghouse Electric Corp. Method of fabricating heat mirror for incandescent lamp envelope. 4,293,593, Cl. 427-106.000.
- Yoldas, Bulent E.; and Mattox, Douglas M., to Westinghouse Electric Corp. Method for forming conductive, transparent coating on a substrate. 4,293,594, Cl. 427-107.000.
- Yonan, Edward E.: See—
Gorman, Susan B.; Thompson, Ralph B.; and Yonan, Edward E., 4,293,706, Cl. 560-163.000.
- Yoneda, Takao: See—
Nishimura, Hideo; Yoneda, Takao; and Enomoto, Minoru, 4,293,913, Cl. 364-474.000.
- Yonkers, Edward H.; and LeDoux, Gilbert A., to Data Packaging Corporation. Ribbon cartridge for band printer. 4,293,234, Cl. 400-196.100.
- Yoo, Jin S.: See—
Burk, Emmett H., Jr.; Yoo, Jin S.; Karch, John A.; and Sun, Jui-Yuan, 4,293,403, Cl. 208-120.000.
- Yoshida Kogyo, K.K.: See—
Iimura, Yoshitaka, 4,292,733, Cl. 29-766.000.
- Yoshino Kogyosho Co., Ltd.: See—
Akutsu, Masao, 4,293,520, Cl. 264-513.000.
- Yost, Gerald H.: See—
Chirino, Agustin M.; and Yost, Gerald H., 4,293,325, Cl. 65-43.000.
- Young, David E., to Smith International, Inc. Drilling head. 4,293,047, Cl. 175-195.000.
- Young, Elgin E., to PPG Industries, Inc. Synthesis of polyol bis(allyl carbonate) utilizing reagent recovery and recycle. 4,293,503, Cl. 260-463.000.
- Yukinaga, Hisajiro; Sumimoto, Shinzaburo; Ishizuka, Ichiro; and Sugita, Jitsuo, to Shionogi & Co., Ltd. N-(5-t-Butyl-3-isoxazolyl)alkanamide derivatives and herbicidal compositions containing them. 4,293,328, Cl. 71-88.000.
- Yukitake, Tugihito: See—
Isahaya, Fumio; and Yukitake, Tugihito, 4,293,521, Cl. 422-62.000.
- Zalucha, Denis J.; Sexsmith, Frederick H.; Hornaman, Ernest C.; and Dawdy, Terrance H., to Lord Corporation. Structural adhesive formulations. 4,293,665, Cl. 525-255.000.
- Zankl, Robert H. Screw lock rivet. 4,293,263, Cl. 411-500.000.
- Zapara, Boris M.: See—
Dunaevsky, Vladimir I.; Boidenko, Nikolai G.; Samarin, Alexei P.; Levit, Viktor M.; Zapara, Boris M.; Ivanov, Boris N.; Frolov, Sergei A.; Voronin, Rostislav A.; Belozero, Nikolai P.; Momot, Valery I.; Stusenko, Jury A.; and Samoilov, Vladimir A., 4,293,101, Cl. 242-56.400.
- Zdaniewski, Joseph J.; Penn, William B.; and Balke, Roy L., to General Electric Co. Insulated pole and coil assembly and method of making same. 4,293,784, Cl. 310-45.000.
- Zecher, Wilfried: See—
Rottmaier, Ludwig; Merten, Rudolf; Lewalter, Jurgen; Zecher, Wilfried; and Dunwald, Willi, 4,293,669, Cl. 525-452.000.
- Zeidman, Zvi; Goldenberg, Carol; and Grinbaum, Zvi. Impacting device. 4,293,045, Cl. 173-121.000.
- Zeilstra, Jacobus J.; de Klein, Willem J.; and Bik, Joannes D., to Akzona Incorporated. Wax composition for entirely or partly replacing carnauba wax or montan wax. 4,293,345, Cl. 106-270.000.
- Zenith Radio Corporation: See—
Reneau, Daniel L., 4,293,874, Cl. 358-172.000.
- Yello, Joseph F., 4,293,804, Cl. 315-398.000.
- Zerennner, Ernest H.: See—
Bente, Paul F., III; Zerennner, Ernest H.; and Dandeneau, Raymond D., 4,293,415, Cl. 210-198.200.

- Zidermane, Aina A.: See—
Uldrikis, Yan R.; Preisa, Ieva E.; Dubur, Gunar Y.; Zidermane, Aina A.; Biseniex, Egils A.; and Tirzit, Gunar D., 4,293,700, Cl. 546-321.000.
- Zilog, Inc.: See—
Trueblood, Richard K., 4,293,587, Cl. 427-90.000.
- Zimmermann & Jansen GmbH: See—
Felthuis, Jacob; and Rumphorst, Jacobus A., 4,292,993, Cl. 137-340.000.
- Hoppe, Walter, 4,292,747, Cl. 37-58.000.
- Zinchenko, Yakov A.: See—
Kopylov, Alexei A.; Kuzmenko, Valentin T.; Stepanov, Alexandr N.; Gaschenko, Viktor P.; Kaznacheevsky, Nikolai A.; Nosovitsky, Alexandr Y.; Misikov, Ivan I.; Shapiro, Alexandr I.; Skakunov, Ivan G.; Markin, Valentin G.; Konstantinov, Alexei K.; Abramian, Eduard S.; Soroka, Arseny M.; and Zinchenko, Yakov A., 4,292,928, Cl. 119-17.000.
- Ziv, Avraham, to American Safety Equipment Corporation. Tension relieving selective engagement mechanism with memory. 4,293,107, Cl. 242-107.700.
- Zoerb, Alan E., deceased: See—
Carpenter, Edward J.; Korff, William W.; Zoerb, Alan E., deceased; Barelo, Lawrence J.; Hall, Donald R.; and Becker, Orlin N., 4,293,915, Cl. 364-493.000.
- Zoerb, Delores E.: See—
Carpenter, Edward J.; Korff, William W.; Zoerb, Alan E., deceased; Barelo, Lawrence J.; Hall, Donald R.; and Becker, Orlin N., 4,293,915, Cl. 364-493.000.
- Zollinger, J. Lamar; and Lien, Larry A., to Minnesota Mining and Manufacturing Company. Low friction, abrasion resistant coating for transparent film. 4,293,606, Cl. 428-203.000.
- Zook, Grant W. Conversion or extension beam. 4,293,269, Cl. 414-686.000.
- Zovitsky, Gert J.: See—
Retief, Andries; and Zovitsky, Gert J., 4,293,134, Cl. 273-428.000.
- Zuffellato, Giuseppe. Writing instrument with holder or grip portion incorporating a partially visible movable ribbon. 4,292,750, Cl. 40-334.000.

LIST OF REISSUE PATENTEES

TO WHOM

PATENTS WERE ISSUED ON THE 6TH DAY OF OCTOBER, 1981

NOTE—Arranged in accordance with the first significant character or word of the name (in accordance with city and telephone directory practice).

- Arvin Industries, Inc.: See—
 Maxey, Alexander R., Re. 30,762, Cl. 360-85.000.
 Ban, Itsuki; and Shiraki, Manabu. Three-phase DC motor having non-superimposed armature coils. Re. 30,761, Cl. 318-439.000.
 Bayer Aktiengesellschaft: See—
 Kubens, Rolf; and Heine, Heinrich, Re. 30,760, Cl. 528-67.000.
 Burkner, Wolfgang, to Carl Schenck AG. Method and apparatus for producing and transporting single and multilayer chipboards. Re. 30,759, Cl. 264-118.000.
 Carl Schenck AG: See—
 Burkner, Wolfgang, Re. 30,759, Cl. 264-118.000.
 Cook, Robert D.: See—
 Hirzel, Edgar A.; and Cook, Robert D., Re. 30,763, Cl. 364-426.000.
 Crane Co., Hydro-Aire Division: See—
 Hirzel, Edgar A.; and Cook, Robert D., Re. 30,763, Cl. 364-426.000.
 Gerber Garment Technology, Inc.: See—
 Gerber, Heinz J., Re. 30,757, Cl. 83-74.000.
 Gerber, Heinz J., to Gerber Garment Technology, Inc. Closed loop apparatus for cutting sheet material. Re. 30,757, Cl. 83-74.000.
 Heine, Heinrich: See—
 Kubens, Rolf; and Heine, Heinrich, Re. 30,760, Cl. 528-67.000.
 Hirzel, Edgar A.; and Cook, Robert D., to Crane Co., Hydro-Aire Division. Selective deceleration brake control system. Re. 30,763, Cl. 364-426.000.
 Kubens, Rolf; and Heine, Heinrich, to Bayer Aktiengesellschaft. Process for the production of synthetic resins containing isocyanurate groups. Re. 30,760, Cl. 528-67.000.
 Lang, Richard A. Pedal-actuated bicycle gear shift means. Re. 30,758, Cl. 474-80.000.
 Maxey, Alexander R., to Arvin Industries, Inc. Method and apparatus for video signal recording. Re. 30,762, Cl. 360-85.000.
 Muir, Andrew R.; and Vergato, Joseph A., to Perkin-Elmer Corporation. The Electrical output peak detecting apparatus. Re. 30,764, Cl. 364-487.000.
 Perkin-Elmer Corporation, The: See—
 Muir, Andrew R.; and Vergato, Joseph A., Re. 30,764, Cl. 364-487.000.
 Shiraki, Manabu: See—
 Ban, Itsuki; and Shiraki, Manabu, Re. 30,761, Cl. 318-439.000.
 Vergato, Joseph A.: See—
 Muir, Andrew R.; and Vergato, Joseph A., Re. 30,764, Cl. 364-487.000.

LIST OF DESIGN PATENTEES

- Abeta Pet Supply, Inc.: See—
 Michalski, Robert J., 261,186, Cl. D30-42.000.
 Adkins, James C.: See—
 Rosenblatt, Aaron A.; Mann, Walter J.; and Adkins, James C., 261,109, Cl. D9-384.000.
 Akimov, Boris M.; Morozov, Viktor I.; Shalae, Vitaly I.; Telegin, Viktor V.; Vasiltsov, Alexandr M.; Tsoglin, Georgy S.; and Vasiliev, Vladimir I. Vacuum vessel for comestibles or the like. 261,088, 10-6-81, Cl. D7-77.000.
 Aktiebolaget Volvo: See—
 Lindfors, Olof H., 261,126, Cl. D34-34.000.
 Allen, Donald B.: See—
 Rice, Kenneth, Jr., 261,168, Cl. D21-225.000.
 Alley, John P., Sr. Candle sconce. 261,179, 10-6-81, Cl. D26-9.000.
 Allibert Exploitation Societe Anonyme: See—
 Cornou, Jean, 261,193, Cl. D34-45.000.
 Alternative Pioneering Systems, Inc.: See—
 Erickson, Chad S.; and Worrell, W. Robert, 261,142, Cl. D15-110.000.
 Amarger, Guy, to Compagnie Generale des Etablissements Michelin. Tire. 261,130, 10-6-81, Cl. D12-147.000.
 American Hospital Supply Corporation: See—
 O'Day, David L., 261,175, Cl. D24-99.000.
 American Optical Corporation: See—
 Armbruster, John T., 261,173, Cl. D24-21.000.
 AMP Incorporated: See—
 Sotolongo, Thomas J., 261,101, Cl. D8-353.000.
 Armbruster, John T., to American Optical Corporation. Bilirubinometer. 261,173, 10-6-81, Cl. D24-21.000.
 Barbour, William P., to Security Imprinter Corporation. Handle and cap assembly for the print head of imprinting machines. 261,151, 10-6-81, Cl. D18-14.000.
 Barbour, William P., to Security Imprinter Corporation. Printing bed assembly for imprinting machines. 261,152, 10-6-81, Cl. D18-14.000.
 Barich, Pamela. Pleated nurse cap. 261,072, 10-6-81, Cl. D2-230.000.
 Barr, Josef J. Necklace or similar article. 261,119, 10-6-81, Cl. D11-7.000.
 Barr, Josef J. Necklace or similar article. 261,120, 10-6-81, Cl. D11-15.000.
 Barr, Josef J. Necklace or similar article. 261,121, 10-6-81, Cl. D11-15.000.
 Barr, Josef J. Finger ring. 261,122, 10-6-81, Cl. D11-34.000.
 Baxter Travenol Laboratories, Inc.: See—
 Winchell, David A.; and Evans, William M., 261,106, Cl. D9-369.000.
 Berliner, Emanuel, to Bristol Inc. Bottom plate for a sphygmomanometer. 261,174, 10-6-81, Cl. D24-29.000.
 Bogert, Frances P.: See—
 Bogert, Theodore L.; and Bogert, Frances P., 261,083, Cl. D6-161.000.
 Bogert, Theodore L.; and Bogert, Frances P. Computer terminal desk. 261,083, 10-6-81, Cl. D6-161.000.
 Box, Theodor M., to Cities Service Company. Beverage case. 261,194, 10-6-81, Cl. D34-46.000.
 Bristol Inc.: See—
 Berliner, Emanuel, 261,174, Cl. D24-29.000.
 Brooksby, Brian T.; Murray, Harold J.; Simpson, Anthony; and Peterkin, Stuart M. Moving target projector console. 261,144, 10-6-81, Cl. D16-11.000.
 Brooksby, Brian T.; Murray, Harold J.; Simpson, Anthony; and Peterkin, Stuart M. Screen unit. 261,149, 10-6-81, Cl. D16-43.000.
 Bunker, Richard E. Flume platform for animal confinement pens. 261,183, 10-6-81, Cl. D30-2.000.
 Bunker, Richard E. Flume platform for animal confinement pens. 261,184, 10-6-81, Cl. D30-2.000.
 Bunker, Richard E. Flume platform for animal confinement pens. 261,185, 10-6-81, Cl. D30-2.000.
 Cathey, Wayne C., to Xerox Corporation. Acoustical hood assembly for a printer apparatus. 261,153, 10-6-81, Cl. D18-22.000.
 Charles of the Ritz Group Ltd.: See—
 Harris, Ned, 261,107, Cl. D9-370.000.
 Harris, Ned, 261,108, Cl. D9-370.000.
 Chernin, Samuel. Building. 261,176, 10-6-81, Cl. D25-11.000.
 Chernoff, Maxwell B., to Dart Industries Inc. Tote bag. 261,076, 10-6-81, Cl. D3-42.000.
 Chicago Pneumatic Tool Company: See—
 Wallace, William K.; and Giardino, David A., 261,097, Cl. D8-61.000.
 Chikaishi, Koichi: See—
 Yamada, Nobuo; Kamikubo, Masayoshi; Chikaishi, Koichi; and Terahata, Junichi, 261,136, Cl. D14-5.000.

LIST OF DESIGN PATENTEES

PI 47

- Chromcraft Corporation: See—
 Wilson, Robert L., 261,078, Cl. D6-35.000.
 Wilson, Robert L., 261,080, Cl. D6-70.000.
 Cities Service Company: See—
 Box, Theodor M., 261,194, Cl. D34-46.000.
 Citizen Watch Co. Ltd.: See—
 Fukumura, Yutaka, 261,111, Cl. D10-38.000.
 Fukumura, Yutaka, 261,112, Cl. D10-38.000.
 Fukumura, Yutaka, 261,113, Cl. D10-39.000.
 Cohen Skalli, Robert A. Bottle. 261,104, 10-6-81, Cl. D9-329.000.
 Collins, Samuel T., to Trend Line Furniture Corporation. Seat. 261,079, 10-6-81, Cl. D6-63.000.
 Compagnie Generale des Etablissements Michelin: See—
 Amarger, Guy, 261,130, Cl. D12-147.000.
 Cornou, Jean, to Allibert Exploitation Societe Anonyme. Tote tray. 261,193, 10-6-81, Cl. D34-45.000.
 Crawford, Emmet. Belt elevator type educational toy. 261,156, 10-6-81, Cl. D19-59.000.
 Cullity, Richard E.: See—
 Rallis, Rallie P.; Cullity, Richard E.; and Tamplin, Lyle R., 261,127, Cl. D34-34.000.
 Cullom, Keith D.: See—
 Spruill, Mark C.; Hipes, Michael D.; Durtche, Carl J.; and Cullom, Keith D., 261,073, Cl. D2-232.000.
 Cummings, Kenneth W.: See—
 Vetter, Craig W.; Perethian, Charles M.; and Cummings, Kenneth W., 261,132, Cl. D12-182.000.
 Cuttriss, Richard J., to Gruber Systems, Inc. Water closet. 261,171, 10-6-81, Cl. D23-65.000.
 Dart Industries Inc.: See—
 Chernoff, Maxwell B., 261,076, Cl. D3-42.000.
 Trombly, Edgar F., 261,086, Cl. D7-15.000.
 Davis, Myron F., Jr., to International Business Machines Corporation. Magnetic tape unit. 261,138, 10-6-81, Cl. D14-108.000.
 De Lillo, Peter G. Automotive audio system speaker enclosure. 261,137, 10-6-81, Cl. D14-33.000.
 Dolas, Michael. Money pouch. 261,075, 10-6-81, Cl. D3-41.000.
 Dunham, Scott. Test tube baby figurine. 261,124, 10-6-81, Cl. D11-160.000.
 Durtche, Carl J.: See—
 Spruill, Mark C.; Hipes, Michael D.; Durtche, Carl J.; and Cullom, Keith D., 261,073, Cl. D2-232.000.
 Emhart Industries, Inc.: See—
 Russell, Richard H., 261,099, Cl. D8-330.000.
 Erickson, Chad S.; and Worrell, W. Robert, to Alternative Pioneering Systems, Inc. Food dehydrator. 261,142, 10-6-81, Cl. D15-110.000.
 Ettoh, Taro; and Ishihara, Sadao, to Minolta Camera Kabushiki Kaisha. Copier or similar article. 261,145, 10-6-81, Cl. D16-30.000.
 Evans, William M.: See—
 Winchell, David A.; and Evans, William M., 261,106, Cl. D9-369.000.
 Fears, Lowell T. Combined fluids container and applicator. 261,103, 10-6-81, Cl. D9-300.000.
 First Campaign Corporation: See—
 Vetter, Craig W.; Perethian, Charles M.; and Cummings, Kenneth W., 261,132, Cl. D12-182.000.
 Ford, Harry R.; and Yoshihashi, Yasuo, to Formica Corporation. Laminate sheet. 261,189, 10-6-81, Cl. D92-1.00R.
 Ford, Harry R.; and Yoshihashi, Yasuo, to Formica Corporation. Laminate sheet. 261,190, 10-6-81, Cl. D92-1.00R.
 Ford, Harry R.; and Yoshihashi, Yasuo, to Formica Corporation. Laminate sheet. 261,191, 10-6-81, Cl. D92-1.00Y.
 Formica Corporation: See—
 Ford, Harry R.; and Yoshihashi, Yasuo, 261,189, Cl. D92-1.00R.
 Ford, Harry R.; and Yoshihashi, Yasuo, 261,190, Cl. D92-1.00R.
 Ford, Harry R.; and Yoshihashi, Yasuo, 261,191, Cl. D92-1.00Y.
 Four Star Corporation: See—
 Mareydt, Ray G.; and Kowalski, Daniel J., 261,131, Cl. D12-157.000.
 Fowler, George D., to Supreme Industries, Inc. Boat. 261,128, 10-6-81, Cl. D12-300.000.
 Fox Valley Instrument Company: See—
 Greenlee, Hugh T.; Hess, Roy P.; and McKinnon, Donald C., 261,115, Cl. D10-112.000.
 Fukumura, Yutaka, to Citizen Watch Co. Ltd. Wrist watch. 261,111, 10-6-81, Cl. D10-38.000.
 Fukumura, Yutaka, to Citizen Watch Co., Ltd. Wrist watch. 261,112, 10-6-81, Cl. D10-38.000.
 Fukumura, Yutaka, to Citizen Watch Co., Ltd. Wrist watch. 261,113, 10-6-81, Cl. D10-39.000.
 Gakken Co., Ltd.: See—
 Kurosawa, Kenzo; and Hachimura, Fukuji, 261,165, Cl. D21-160.000.
 Gardisette International AG: See—
 Stocker, Hans, 261,187, Cl. D47-6.00E.
 Stocker, Hans, 261,188, Cl. D47-6.00E.
 Stocker, Hans, 261,192, Cl. D92-1.00A.
 Giardino, David A.: See—
 Wallace, William K.; and Giardino, David A., 261,097, Cl. D8-61.000.
 Gordon, Donald J.; Johnson, Frank H.; Schick, George L.; and Smart, J. David, to Slater Steel Industries Limited. Hand cart. 261,125, 10-6-81, Cl. D34-24.000.
 Graco/Dendoki, Inc.: See—
 Lawrence, Frederick J., 261,147, Cl. D16-32.000.
 Lawrence, Frederick J., 261,148, Cl. D16-32.000.
 Green, Robert H. Wood splitter. 261,143, 10-6-81, Cl. D15-127.000.
 Greenlee, Hugh T.; Hess, Roy P.; and McKinnon, Donald C., to Fox Valley Instrument Company. Timing light. 261,115, 10-6-81, Cl. D10-112.000.
 Gronborg, Jan L. Visor for attachment to helmet or the like. 261,074, 10-6-81, Cl. D2-233.000.
 Gruber Systems, Inc.: See—
 Cuttriss, Richard J., 261,171, Cl. D23-65.000.
 Gschwandtnr, Eric. Building structure or the like. 261,177, 10-6-81, Cl. D25-17.000.
 Guilfoyle, John L. Bee frame end bar. 261,182, 10-6-81, Cl. D30-2.000.
 Hachimura, Fukuji: See—
 Kurosawa, Kenzo; and Hachimura, Fukuji, 261,165, Cl. D21-160.000.
 Harris, Ned, to Charles of the Ritz Group Ltd. Combined bottle and cap. 261,107, 10-6-81, Cl. D9-370.000.
 Harris, Ned, to Charles of the Ritz Group Ltd. Combined bottle and cap. 261,108, 10-6-81, Cl. D9-370.000.
 Hendon, Benny J.; and Malinowski, Julius, Jr. Fence post setting chuck. 261,098, 10-6-81, Cl. D8-70.000.
 Heritage, Robert, to Rotaflex (Great Britain) Limited. Electrical current supply track. 261,134, 10-6-81, Cl. D13-13.000.
 Hess, Roy P.: See—
 Greenlee, Hugh T.; Hess, Roy P.; and McKinnon, Donald C., 261,115, Cl. D10-112.000.
 Hipes, Michael D.: See—
 Spruill, Mark C.; Hipes, Michael D.; Durtche, Carl J.; and Cullom, Keith D., 261,073, Cl. D2-232.000.
 Hoover, Charles J. Choker line coupler. 261,102, 10-6-81, Cl. D8-383.000.
 Horne, James. Safety cover for electrical outlets. 261,135, 10-6-81, Cl. D13-30.000.
 Hospital Medical Corp.: See—
 Lissack, Tsvi, 261,172, Cl. D24-17.000.
 Ikeda, Tameaki, to Sony Corporation. Television camera. 261,140, 10-6-81, Cl. D14-78.000.
 International Business Machines Corporation: See—
 Davis, Myron F., Jr., 261,138, Cl. D14-108.000.
 International Standard Electric Corporation: See—
 Jakobsen, Knud, 261,139, Cl. D14-53.000.
 Ishihara, Sadao: See—
 Ettoh, Taro; and Ishihara, Sadao, 261,145, Cl. D16-30.000.
 J-Mark, Inc.: See—
 Makela, Martin A., 261,133, Cl. D12-203.000.
 Jakobsen, Knud, to International Standard Electric Corporation. Telephone apparatus. 261,139, 10-6-81, Cl. D14-53.000.
 Johnson, Frank H.: See—
 Gordon, Donald J.; Johnson, Frank H.; Schick, George L.; and Smart, J. David, 261,125, Cl. D34-24.000.
 Kamikubo, Masayoshi: See—
 Yamada, Nobuo; Kamikubo, Masayoshi; Chikaishi, Koichi; and Terahata, Junichi, 261,136, Cl. D14-5.000.
 Kapolis, Melodee A. Pan insert. 261,090, 10-6-81, Cl. D7-102.000.
 Kask, Eugene, to Rogers Corporation. Level indicating float. 261,114, 10-6-81, Cl. D10-103.000.
 Kowalski, Daniel J.: See—
 Mareydt, Ray G.; and Kowalski, Daniel J., 261,131, Cl. D12-157.000.
 Kubota, Ltd.: See—
 Takahashi, Teizo; and Toyokuni, Kazuo, 261,141, Cl. D15-23.000.
 Kudo, Kazuo, to Tomy Kogyo Co., Inc. Animated frog figurine. 261,164, 10-6-81, Cl. D21-158.000.
 Kudo, Kazuo, to Tomy Kogyo Co., Inc. Animated penguin figurine. 261,166, 10-6-81, Cl. D21-160.000.
 Kurosawa, Kenzo; and Hachimura, Fukuji, to Gakken Co., Ltd. Toy animal figure. 261,165, 10-6-81, Cl. D21-160.000.
 Lagin, Herbert. Track light system. 261,180, 10-6-81, Cl. D26-66.000.
 Lawrence, Frederick J., to Graco/Dendoki, Inc. Combined copying and sorting apparatus. 261,147, 10-6-81, Cl. D16-32.000.
 Lawrence, Frederick J., to Graco/Dendoki, Inc. Combined copying and sorting apparatus. 261,148, 10-6-81, Cl. D16-32.000.
 Lewis, Kenneth T. Door-annunciator housing. 261,117, 10-6-81, Cl. D10-118.000.
 Lindfors, Olof H., to Aktiebolaget Volvo. Remote controlled fork truck. 261,126, 10-6-81, Cl. D34-34.000.
 Lissack, Tsvi, to Hospital Medical Corp. Pulmonary function measurement apparatus or the like. 261,172, 10-6-81, Cl. D24-17.000.
 Loomis, Judith J. Neckwear purse. 261,077, 10-6-81, Cl. D3-52.000.
 Lordahl, Var E., to T.S.G. Mfg. Co. Display stand. 261,082, 10-6-81, Cl. D6-114.000.
 Maglificio Biellese Fratelli S.p.A.: See—
 Rolando, Pierluigi, 261,071, Cl. D12-187.000.
 Makela, Martin A., to J-Mark, Inc. Combined running board and splash guard. 261,133, 10-6-81, Cl. D12-203.000.
 Malinowski, Julius, Jr.: See—
 Hendon, Benny J.; and Malinowski, Julius, Jr., 261,098, Cl. D8-70.000.
 Manmouhong Manufacturing Co.: See—
 Tsang, Ng-Fai A., 261,095, Cl. D7-157.000.
 Mann, Walter J.: See—
 Rosenblatt, Aaron A.; Mann, Walter J.; and Adkins, James C., 261,109, Cl. D9-384.000.
 Mareydt, Ray G.; and Kowalski, Daniel J., to Four Star Corporation. Article carrier stanchion. 261,131, 10-6-81, Cl. D12-157.000.

- Mark Industries: See—
Rallis, Rallie P.; Cullity, Richard E.; and Tamplin, Lyle R., 261,127, Cl. D34-34.000.
- Matsui, Hidetoshi. Kinetic sculpture. 261,158, 10-6-81, Cl. D21-102.000.
- Maxwell-Muir, Rodney: See—
McDonnell, Jessop I.; and Maxwell-Muir, Rodney, 261,089, Cl. D7-101.000.
- McDonnell, Jessop I.; and Maxwell-Muir, Rodney. Tenderizer. 261,089, 10-6-81, Cl. D7-101.000.
- McFarlane, James S. Shampoo sink. 261,170, 10-6-81, Cl. D23-64.000.
- McKinnon, Donald C.: See—
Greenlee, Hugh T.; Hess, Roy P.; and McKinnon, Donald C., 261,115, Cl. D10-112.000.
- Menard, Gerald J. Rotating multiple skewer assembly. 261,092, 10-6-81, Cl. D7-129.000.
- Michalski, Robert J., to Abeta Pet Supply, Inc. Combined cat play-ground and exerciser. 261,186, 10-6-81, Cl. D30-42.000.
- Minolta Camera Kabushiki Kaisha: See—
Etoh, Taro; and Ishihara, Sadao, 261,145, Cl. D16-30.000.
- Sakai, Masaaki; and Sakow, Toshihiko, 261,146, Cl. D16-31.000.
- Morishita Jintan Co., Ltd.: See—
Yoshimoto, Noboru, 261,110, Cl. D9-432.000.
- Morozov, Viktor I.: See—
Akimov, Boris M.; Morozov, Viktor I.; Shalaev, Vitaly I.; Telegin, Viktor V.; Vasiltsov, Alexandr M.; Tsoglin, Georgy S.; and Vasiliev, Vladimir I., 261,088, Cl. D7-77.000.
- Murray, Harold J.: See—
Brooksby, Brian T.; Murray, Harold J.; Simpson, Anthony; and Peterkin, Stuart M., 261,144, Cl. D16-11.000.
- Brooksby, Brian T.; Murray, Harold J.; Simpson, Anthony; and Peterkin, Stuart M., 261,149, Cl. D16-43.000.
- Myodo, Kenichi, to Shinko Kinzoku Kabushiki Kaisha. Kettle. 261,087, 10-6-81, Cl. D7-66.000.
- Nagel, Anita. Soap-dish. 261,081, 10-6-81, Cl. D6-89.000.
- Nast, Richard. Transparent storage envelope for a flexible magnetic computer disc. 261,155, 10-6-81, Cl. D19-33.000.
- O'Day, David L., to American Hospital Supply Corporation. Medical container hanger. 261,175, 10-6-81, Cl. D24-99.000.
- Ohkawa, Hiroshi, to Tomy Kogyo Co., Inc. Toy bear figurine. 261,161, 10-6-81, Cl. D21-150.000.
- Ohkawa, Hiroshi, to Tomy Kogyo Co., Inc. Toy dog figurine. 261,162, 10-6-81, Cl. D21-150.000.
- Perego, Giuseppe. Foldable baby stroller. 261,129, 10-6-81, Cl. D12-129.000.
- Perethian, Charles M.: See—
Vetter, Craig W.; Perethian, Charles M.; and Cummings, Kenneth W., 261,132, Cl. D12-182.000.
- Perhacs, Leslie, Jr., to Proctor & Associates Company. Sonic signal generator. 261,118, 10-6-81, Cl. D10-121.000.
- Peterkin, Stuart M.: See—
Brooksby, Brian T.; Murray, Harold J.; Simpson, Anthony; and Peterkin, Stuart M., 261,144, Cl. D16-11.000.
- Brooksby, Brian T.; Murray, Harold J.; Simpson, Anthony; and Peterkin, Stuart M., 261,149, Cl. D16-43.000.
- Petersen, Christian, to Petersen Manufacturing Co., Inc. Hand tool. 261,096, 10-6-81, Cl. D8-22.000.
- Petersen Manufacturing Co., Inc.: See—
Petersen, Christian, 261,096, Cl. D8-22.000.
- Pettibone, Robert E. Field and winter sports jacket. 261,070, 10-6-81, Cl. D2-185.000.
- Proctor & Associates Company: See—
Perhacs, Leslie, Jr., 261,118, Cl. D10-121.000.
- QED: See—
Rosenblatt, Aaron A.; Mann, Walter J.; and Adkins, James C., 261,109, Cl. D9-384.000.
- Rallis, Rallie P.; Cullity, Richard E.; and Tamplin, Lyle R., to Mark Industries. Mobile self-powered hydraulic lift. 261,127, 10-6-81, Cl. D34-34.000.
- Rapaport, Gerald M. Toy kitchen sink. 261,159, 10-6-81, Cl. D21-122.000.
- Rapaport, Gerald M. Toy stove. 261,160, 10-6-81, Cl. D21-122.000.
- Reiner, Ralph E. Casing for food grinder. 261,094, 10-6-81, Cl. D7-155.000.
- Reinhard, Cheyenne A. Fire escape platform. 261,178, 10-6-81, Cl. D25-62.000.
- Repak, Wayne R., to Safe-T-Signal, Inc. Warning flasher or similar article. 261,116, 10-6-81, Cl. D10-114.000.
- Revlon, Inc.: See—
Schwartz, Ira, 261,105, Cl. D9-353.000.
- Rexham Corporation: See—
Thresher, Glenn A., 261,154, Cl. D19-4.000.
- Rice, Kenneth, Jr., to Allen, Donald B. Skateboard ice blade. 261,168, 10-6-81, Cl. D21-225.000.
- Rogers Corporation: See—
Kask, Eugene, 261,114, Cl. D10-103.000.
- Rolando, Pierluigi, to Maglificio Biellese Fratelli S.p.A. Jacket. 261,071, 10-6-81, Cl. D2-187.000.
- Rosenblatt, Aaron A.; Mann, Walter J.; and Adkins, James C., to QED. Bottle. 261,109, 10-6-81, Cl. D9-384.000.
- Rotaflex (Great Britain) Limited: See—
Heritage, Robert, 261,134, Cl. D13-13.000.
- Rujitsu Ten Limited: See—
Yamada, Nobuo; Kamikubo, Masayoshi; Chikaishi, Koichi; and Terahata, Junichi, 261,136, Cl. D14-5.000.
- Russell, Richard H., to Emhart Industries, Inc. Door closer. 261,099, 10-6-81, Cl. D8-330.000.
- Safe-T-Signal, Inc.: See—
Repak, Wayne R., 261,116, Cl. D10-114.000.
- Saffran, Mortimer; and Turcek, Emil. Bracelet support. 261,123, 10-6-81, Cl. D11-86.000.
- Sakai, Masaaki; and Sakow, Toshihiko, to Minolta Camera Kabushiki Kaisha. Electrostatic copier or similar article. 261,146, 10-6-81, Cl. D16-31.000.
- Sakow, Toshihiko: See—
Sakai, Masaaki; and Sakow, Toshihiko, 261,146, Cl. D16-31.000.
- Sands, Gloria J. Comb with artificial flowers and seashells. 261,181, 10-6-81, Cl. D28-32.000.
- Schick, George L.: See—
Gordon, Donald J.; Johnson, Frank H.; Schick, George L.; and Smart, J. David, 261,125, Cl. D34-24.000.
- Schwartz, Ira, to Revlon, Inc. Dispensing container. 261,105, 10-6-81, Cl. D9-353.000.
- Scott, Janet. Portable back rest. 261,084, 10-6-81, Cl. D6-200.000.
- Security Imprinter Corporation: See—
Barbour, William P., 261,151, Cl. D18-14.000.
- Barbour, William P., 261,152, Cl. D18-14.000.
- Segal, William J. Eating utensil. 261,093, 10-6-81, Cl. D7-151.000.
- Shalaev, Vitaly I.: See—
Akimov, Boris M.; Morozov, Viktor I.; Shalaev, Vitaly I.; Telegin, Viktor V.; Vasiltsov, Alexandr M.; Tsoglin, Georgy S.; and Vasiliev, Vladimir I., 261,088, Cl. D7-77.000.
- Shinko Kinzoku Kabushiki Kaisha: See—
Myodo, Kenichi, 261,087, Cl. D7-66.000.
- Simpson, Anthony: See—
Brooksby, Brian T.; Murray, Harold J.; Simpson, Anthony; and Peterkin, Stuart M., 261,144, Cl. D16-11.000.
- Brooksby, Brian T.; Murray, Harold J.; Simpson, Anthony; and Peterkin, Stuart M., 261,149, Cl. D16-43.000.
- Slater Steel Industries Limited: See—
Gordon, Donald J.; Johnson, Frank H.; Schick, George L.; and Smart, J. David, 261,125, Cl. D34-24.000.
- Smart, J. David: See—
Gordon, Donald J.; Johnson, Frank H.; Schick, George L.; and Smart, J. David, 261,125, Cl. D34-24.000.
- Snyder, Larry R. Fishing lure. 261,169, 10-6-81, Cl. D22-27.000.
- Sony Corporation: See—
Ikeda, Tameaki, 261,140, Cl. D14-78.000.
- Sotolongo, Thomas J., to AMP Incorporated. Floor outlet housing. 261,101, 10-6-81, Cl. D8-353.000.
- Spruill, Mark C.; Hipes, Michael D.; Durtche, Carl J.; and Cullom, Keith D. Combined fireman's hood and face mask. 261,073, 10-6-81, Cl. D2-232.000.
- Stiggers, Weldon W. Shell-fish utensil. 261,091, 10-6-81, Cl. D7-106.000.
- Stocker, Hans, to Gardisette International AG. Curtain material. 261,187, 10-6-81, Cl. D47-6.00E.
- Stocker, Hans, to Gardisette International AG. Design for curtain material. 261,188, 10-6-81, Cl. D47-6.00E.
- Stocker, Hans, to Gardisette International AG. Curtain material. 261,192, 10-6-81, Cl. D92-1.00A.
- Supreme Industries, Inc.: See—
Fowler, George D., 261,128, Cl. D12-300.000.
- Swanson, Arthur P. Golf club head. 261,167, 10-6-81, Cl. D21-220.000.
- T.S.G. Mfg. Co.: See—
Lordahl, Var E., 261,082, Cl. D6-114.000.
- Takahashi, Teizo; and Toyokuni, Kazuo, to Kubota, Ltd. Agricultural tractor. 261,141, 10-6-81, Cl. D15-23.000.
- Takizawa, Toshiaki, to Tomy Kogyo Co., Inc. Animated seal figurine. 261,163, 10-6-81, Cl. D21-150.000.
- Tamplin, Lyle R.: See—
Rallis, Rallie P.; Cullity, Richard E.; and Tamplin, Lyle R., 261,127, Cl. D34-34.000.
- Telegin, Viktor V.: See—
Akimov, Boris M.; Morozov, Viktor I.; Shalaev, Vitaly I.; Telegin, Viktor V.; Vasiltsov, Alexandr M.; Tsoglin, Georgy S.; and Vasiliev, Vladimir I., 261,088, Cl. D7-77.000.
- Terahata, Junichi: See—
Yamada, Nobuo; Kamikubo, Masayoshi; Chikaishi, Koichi; and Terahata, Junichi, 261,136, Cl. D14-5.000.
- Terry, Forest L., Jr. Combined guitar and synthesizer sound box, or similar article. 261,150, 10-6-81, Cl. D17-2.000.
- Thresher, Glenn A., to Rexham Corporation. Envelope. 261,154, 10-6-81, Cl. D19-4.000.
- Tomy Kogyo Co., Inc.: See—
Kudo, Kazuo, 261,164, Cl. D21-158.000.
- Kudo, Kazuo, 261,166, Cl. D21-160.000.
- Ohkawa, Hiroshi, 261,161, Cl. D21-150.000.
- Ohkawa, Hiroshi, 261,162, Cl. D21-150.000.
- Takizawa, Toshiaki, 261,163, Cl. D21-150.000.
- Toyokuni, Kazuo: See—
Takahashi, Teizo; and Toyokuni, Kazuo, 261,141, Cl. D15-23.000.
- Trend Line Furniture Corporation: See—
Collins, Samuel T., 261,079, Cl. D6-63.000.
- Trombly, Edgar F., to Dart Industries Inc. Tumbler. 261,086, 10-6-81, Cl. D7-15.000.
- Tsang, Ng-Fai A., to Manmouhong Manufacturing Co. All purpose beater. 261,095, 10-6-81, Cl. D7-157.000.

- Tsoglin, Georgy S.: See—
Akimov, Boris M.; Morozov, Viktor I.; Shalaev, Vitaly I.; Telegin, Viktor V.; Vasiltsov, Alexandr M.; Tsoglin, Georgy S.; and Vasiliev, Vladimir I., 261,088, Cl. D7-77.000.
- Turcek, Emil: See—
Saffran, Mortimer; and Turcek, Emil, 261,123, Cl. D11-86.000.
- Vasiliev, Vladimir I.: See—
Akimov, Boris M.; Morozov, Viktor I.; Shalaev, Vitaly I.; Telegin, Viktor V.; Vasiltsov, Alexandr M.; Tsoglin, Georgy S.; and Vasiliev, Vladimir I., 261,088, Cl. D7-77.000.
- Vasiltsov, Alexandr M.: See—
Akimov, Boris M.; Morozov, Viktor I.; Shalaev, Vitaly I.; Telegin, Viktor V.; Vasiltsov, Alexandr M.; Tsoglin, Georgy S.; and Vasiliev, Vladimir I., 261,088, Cl. D7-77.000.
- Ventura, Frank. Drinking cup. 261,085, 10-6-81, Cl. D7-6.000.
- Vetter, Craig W.; Perethian, Charles M.; and Cummings, Kenneth W., to First Champaign Corporation. Motorcycle fairing. 261,132, 10-6-81, Cl. D12-182.000.
- Wallace, Dan F.: See—
Wallace, Robert S., 261,100, Cl. D8-336.000.
- Wallace, Robert S., to Wallace, Dan F. Latch. 261,100, 10-6-81, Cl. D8-336.000.
- Wallace, William K.; and Giardino, David A., to Chicago Pneumatic Tool Company. Pneumatic nut runner with torque indicator. 261,097, 10-6-81, Cl. D8-61.000.
- Wilson, Robert L., to Chromcraft Corporation. Bar stool. 261,078, 10-6-81, Cl. D6-35.000.
- Wilson, Robert L., to Chromcraft Corporation. Chair. 261,080, 10-6-81, Cl. D6-70.000.
- Winchell, David A.; and Evans, William M., to Baxter Travenol Laboratories, Inc. Bottle. 261,106, 10-6-81, Cl. D9-369.000.
- Wolf, Tobin. Combined kaleidoscope and toy mail box. 261,157, 10-6-81, Cl. D21-60.000.
- Worrell, W. Robert: See—
Erickson, Chad S.; and Worrell, W. Robert, 261,142, Cl. D15-110.000.
- Xerox Corporation: See—
Cathey, Wayne C., 261,153, Cl. D18-22.000.
- Yamada, Nobuo; Kamikubo, Masayoshi; Chikaishi, Koichi; and Terahata, Junichi, to Rujitsu Ten Limited. Combined automobile cartridge player and radio receiver or the like. 261,136, 10-6-81, Cl. D14-5.000.
- Yoshihashi, Yasuo: See—
Ford, Harry R.; and Yoshihashi, Yasuo, 261,189, Cl. D92-1.00R.
- Ford, Harry R.; and Yoshihashi, Yasuo, 261,190, Cl. D92-1.00R.
- Ford, Harry R.; and Yoshihashi, Yasuo, 261,191, Cl. D92-1.00Y.
- Yoshimoto, Noboru, to Morishita Jintan Co., Ltd. Pillbox. 261,110, 10-6-81, Cl. D9-432.000.

LIST OF PLANT PATENTEEES

Fry, Byard O. Muscadine grape. 4,772, 10-6-81, Cl. 47.000.

Holtkamp, Reinhold. African violet plant. 4,773, 10-6-81, Cl. 69.000.

Holtkamp, Reinhold. African violet plant. 4,774, 10-6-81, Cl. 69.000.

LIST OF DEFENSIVE PUBLICATIONS

APPLICANTS TO WHOM

DEFENSIVE PUBLICATIONS WERE ISSUED ON THE 6TH DAY OF OCTOBER, 1981

Published at the request of the applicant or owner in accordance with the Notice of Dec. 16, 1969, 869 O. G. 687.

- Kogon, Irving C. Process for preparing a small particle size dispersion of a complex of 4,4'-methylenedianiline with a salt. T101,101, 10-6-81, Cl. 564-334.000.
- Mijovic, Miroslav V.: See—
Sidhu, Jasbir; Simons, Michael J.; and Mijovic, Miroslav V., T101,103, Cl. 430-598.000.
- Sidhu, Jasbir; Simons, Michael J.; and Mijovic, Miroslav V. Absorbed hydrazide nucleating agents and photographic elements containing such agents. T101,103, 10-6-81, Cl. 430-598.000.
- Simons, Michael J.: See—
Sidhu, Jasbir; Simons, Michael J.; and Mijovic, Miroslav V., T101,103, Cl. 430-598.000.
- Turner, John J. P. Pigmented coating of polyester/cotton spun yarns. T101,102, 10-6-81, Cl. 8-495.000.

CLASSIFICATION OF PATENTS

ISSUED OCTOBER 6, 1981

NOTE.—First number, class; second number, subclass; third number, patent number

CLASS 2	73	4,292,744	24	4,292,797	466	4,292,857	55.1	4,292,901	296	4,292,972
2	156	4,292,745	86	4,292,798	501 R	4,292,858	146	4,292,902	303.1	4,292,973
6	CLASS 36		246	4,292,799		4,292,859		4,292,903	344	4,292,974
12	83	4,292,746	264	4,292,800	665 GA	4,292,860		CLASS 110	498	4,292,975
65	CLASS 37			CLASS 60	813 R	4,292,861	198	4,292,904	656	4,292,976
418	58	4,292,747	39.06	4,292,801		CLASS 75		CLASS 112	712	4,292,977
CLASS 3	CLASS 38		204	4,292,802	99	4,293,332		121.11	730	4,292,978
1.9	102	4,292,748	230	4,292,803	101 BE	4,293,333		184	743	4,292,979
1.91	CLASS 40		407	4,292,804		4,293,334		236	783	4,292,980
	308	4,292,749	450	4,292,805	124	4,293,335		306	CLASS 130	
CLASS 4	334	4,292,750	600	4,292,806	232	4,293,336		74 R	27 F	4,292,981
505	517	4,292,751	601	4,292,807	253	4,293,337		102	30 R	4,292,982
CLASS 5	576	4,292,752	673	4,292,808		4,293,338		218	187	4,292,983
18 R	CLASS 43		757	4,292,810	4	4,292,862		219	345	4,292,984
45	5	4,292,753		CLASS 62		CLASS 81		222	CLASS 132	
413	CLASS 44		17	4,293,322	184	4,292,863		260	9	4,292,985
422	1 R	4,293,312	56	4,292,811		CLASS 82		205	11 R	4,292,986
451	7 A	4,293,313	157	4,292,812	2.7	4,292,864		205	73	4,292,987
468	CLASS 8		158	4,292,813	36 R	4,292,865		16	CLASS 134	
115.6	471	4,293,305	238.6	4,292,814	47	4,292,866		33	11	4,293,347
CLASS 13	CLASS 46		262	4,292,815		4,292,867		212	22 R	4,293,348
6	6	4,292,754	345	4,292,816		CLASS 83		425	245	4,293,731
CLASS 15	44	4,292,755	457	4,292,817	13	4,292,868		648	257	4,293,732
104.3 SN	72	4,292,756		CLASS 63	74	Re.30,757		657	68 R	4,292,988
110	80	4,292,757	28	4,292,818	137	4,292,869		658	72	4,292,989
341	93	4,292,758	28 R	4,292,819	471.2	4,292,870		690	115	4,292,990
CLASS 16	205	4,292,759		CLASS 64	661	4,292,871		14.02	340	4,292,991
48.5	14	4,292,760	27	4,293,324	866	4,292,872		16	351	4,292,992
140	17	4,292,762	43	4,293,325		CLASS 84		17	384.2	4,292,993
CLASS 17	94	4,293,315	60 D	4,293,326	1.14	4,292,875		27	393	4,292,994
11.1 R	CLASS 48		64	4,293,327		CLASS 86		51.11	454.6	4,292,995
21	64	4,292,763	8	4,292,820	31	4,292,877		103	489.5	4,292,996
49	237	4,292,764	75.2	4,292,821	48	4,292,878		109	560	4,292,997
CLASS 19	CLASS 51			CLASS 68	57	4,292,879		114	596.13	4,292,998
159 A	94 R	4,292,699	5 D	4,292,822		CLASS 89		145 A	596.2	4,293,000
CLASS 23	103 TF	4,292,765		CLASS 70	1.815	4,292,880		193 P	625.64	4,293,002
230 B	105 SP	4,292,766	364 R	4,292,823	33 CA	4,292,881		285	637.4	4,293,003
230 EP	168	4,292,768	373	4,292,824	36 A	4,292,882		335	884	4,293,004
230 PC	169	4,292,769		CLASS 71		CLASS 91		387	149	4,293,005
301	170 PT	4,292,770	88	4,293,328		4,292,883		416	102	4,293,006
CLASS 24	CLASS 52		94	4,293,329		4,292,884		418	358	4,293,007
24	98	4,292,771	118	4,293,330		CLASS 92		427	95	4,293,008
30.5 R	118	4,292,772	118	4,293,331		4,292,885		432	311 R	4,293,009
155 C	171	4,292,773		CLASS 72		4,292,886		440	392	4,293,010
CLASS 29	208	4,292,774	8	4,292,825		4,292,887		445	CLASS 144	
116 AD	394	4,292,775	45	4,292,826		CLASS 99		490	3 R	4,293,011
148.4 A	407	4,292,776	46	4,292,827		4,292,888		556	193 A	4,293,012
149.5 DP	486	4,292,777	54	4,292,828		4,292,889			208 B	4,293,014
156.4 R	541	4,292,778	76	4,292,829		4,292,890			CLASS 148	
157.1 R	547	4,292,779	197	4,292,830		CLASS 100			6.15 R	4,293,349
243.52	696	4,292,780	260	4,292,831		4,292,891			111	4,293,350
402.01	741	4,292,781	365	4,292,832		4,292,892			19.2	4,293,351
402.21	CLASS 53		416	4,292,833		CLASS 101			19.4	4,293,352
418	391	4,292,784	482	4,292,834		4,292,893			CLASS 150	
419 R	399	4,292,785		CLASS 73		4,292,894			52 R	4,293,015
527.6	434	4,292,786		1 B		4,292,895			CLASS 152	
566.3	456	4,292,787		6		4,292,896			158	4,293,016
571	500	4,292,788		17 R		4,292,897			339	4,293,017
CLASS 30	CLASS 55			37.7		4,292,898			347	4,293,018
43.92	16	4,293,316		49.2		4,292,899			361 R	4,293,019
162	71	4,293,317		115		4,292,900			69	4,293,353
CLASS 33	85	4,293,318		119 A		4,292,901			73.2	4,293,354
126.4 R	122	4,293,319		155		4,292,902			89	4,293,355
172 E	273	4,293,320		171		4,292,903			214 R	4,293,356
379	357	4,293,321		359 A		4,292,904			214.4	4,293,357
CLASS 34	CLASS 56			362.1		4,292,905			256	4,293,358
35	12.7	4,292,789		427		4,292,906			260	4,293,359
65	13.6	4,292,790		587		4,292,907				4,293,360
	255	4,292,791		602		4,292,908				
	330	4,292,792		643		4,292,909				
	378	4,292,793		702		4,292,910				
	400.16	4,292,794		762		4,292,911				
	503	4,292,795		827		4,292,912				
	CLASS 57			861.79		4,292,913				
	22	4,292,796				4,292,914				
						4,292,915				
						4,292,916				
						4,292,917				
						4,292,918				
						4,292,919				
						4,292,920				
						4,292,921				
						4,292,922				
						4,292,923				
						4,292,924				
						4,292,925				
						4,292,926				
						4,292,927				
						4,292,928				
						4,292,929				
						4,292,930				
						4,292,931				
						4,292,932				
						4,292,933				
						4,292,934				
						4,292,935				
						4,292,936				
						4,292,937				
						4,292,938				
						4,292,939				
						4,292,940				
						4,292,941				
						4,292,942				
						4,292,943				
						4,292,944				
						4,292,945				
						4,292,946				
						4,292,947				
						4,292,948				
						4,292,949				
						4,292,950				
						4,292,951				
						4,292,952				
						4,292,953				
						4,292,954				
						4,292,955				
						4,292,956				
						4,292,957				
						4,292,958				
						4,292,959				
						4,292,960				
						4,292,961				
						4,292,962				
						4,292,963				
						4,292,964				
						4,292,965				
						4,292,966				
						4,292,967				
						4,292,968				
						4,292,969				
						4,292,970				
						4,292,971				
						4,292,972				
						4,292,973				
						4,292,974				
						4,292,975				
						4,292,976				
						4,292,977				
						4,292,978				
						4,292,979				
						4,292,980				

357	4,293,194	124	4,293,905	593	4,293,236	356	4,293,532	212	4,293,607	196	4,293,664	
358	4,293,195	135	4,293,906			449	4,293,533	220	4,293,608	255	4,293,665	
452	4,293,196			CLASS 364	39	4,293,237	593	4,293,534	246	4,293,609	284	4,293,666
454	4,293,197	200	4,293,907			175	4,293,238		4,293,610		4,293,667	
			4,293,908			195	4,293,239	CLASS 424	266	4,293,611	369	4,293,668
13	4,293,198		4,293,909				4,293,240		281	4,293,612	436	4,293,670
	4,293,199		4,293,910			213	4,293,241		364	4,293,613	452	4,293,669
36	4,293,200		4,293,941			239	4,293,242		370	4,293,614	478	4,293,671
178	4,293,201	405	4,293,911			259	4,293,243		412	4,293,615	507	4,293,672
		414	4,293,912			272	4,293,244	19	4,293,539			
		426	Re.30,763			291	4,293,245	26	4,293,540			
5	4,293,202	474	4,293,913			296	4,293,246	45	4,293,541			
17	4,293,203	478	4,293,914			300	4,293,247	47	4,293,542			
21	4,293,204	487	Re.30,764					59	4,293,543			
23 D	4,293,205	493	4,293,915			CLASS 406		60	4,293,544			
25	4,293,206	571	4,293,916					92	4,293,545			
	4,293,207	591	4,293,917			72	4,293,249	119	4,293,546	CLASS 429		
29	4,293,208	701	4,293,918			109	4,293,250	180	4,293,547	50	4,293,622	
269	4,293,209	702	4,293,919					242	4,293,548	194	4,293,623	
298	4,293,210	716	4,293,920			CLASS 408		245	4,293,549			
299	4,293,211	725	4,293,921			59	4,293,251	246	4,293,550	CLASS 430		
	4,293,212	726	4,293,922			224	4,293,252	249	4,293,551	5	4,293,624	
		757	4,293,923			226	4,293,253	250	4,293,552	9	4,293,625	
CLASS 355		800	4,293,924			229	4,293,254		4,293,553	17	4,293,626	
		902	4,293,925			CLASS 410			4,293,554	39	4,293,627	
14 R	4,293,213		4,293,926			104	4,293,255	263	4,293,555	58	4,293,628	
	4,293,214		4,293,927					267	4,293,556	39	4,293,630	
40	4,293,215		4,293,928			CLASS 411			4,293,557	64	4,293,629	
77	4,293,216							270	4,293,558	106	4,293,631	
		CLASS 356				11	4,293,256		4,293,559	132	4,293,632	
37	4,293,217		CLASS 365			30	4,293,257	271	4,293,560	157	4,293,633	
138	4,293,218	2	4,293,929			30	4,293,258	273 R	4,293,561	269	4,293,634	
240	4,293,219	8	4,293,930			32	4,293,930		4,293,562	281	4,293,635	
316	4,293,220	222	4,293,931			44	4,293,931		4,293,563	281	4,293,636	
318	4,293,221		4,293,932			85	4,293,932		4,293,564	314	4,293,637	
319	4,293,222					311	4,293,933	285	4,293,565	373	4,293,638	
352	4,293,223		CLASS 366			500	4,293,934	300	4,293,569	393	4,293,639	
357	4,293,224	11	4,293,227			542	4,292,876	304	4,293,566	402	4,293,640	
417	4,293,225	25	4,293,228			CLASS 414		312	4,293,567	521	4,293,641	
443	4,293,226	78	4,293,229					330	4,293,568	534	4,293,642	
		101	4,293,230			38	4,293,264	CLASS 425		286	4,293,292	
CLASS 357		120	4,293,231			140	4,293,265		4,293,292		4,293,297	
46	4,293,868					411	4,293,266	9	4,293,293		4,293,298	
		CLASS 358				462	4,293,267	23	4,293,294	CLASS 432		
8	4,293,869	25	4,293,933			591	4,293,268	112	4,293,295	58	4,293,299	
10	4,293,870	27	4,293,934			686	4,293,269	331	4,293,296	234	4,293,299	
44	4,293,871	43	4,293,935			690	4,293,270	547				
75	4,293,872	82	4,293,936			737	4,293,271		CLASS 426		CLASS 433	
	4,293,873		4,293,937			744 B	4,293,272			92	4,293,300	
172	4,293,874		CLASS 368					3	4,293,570	136	4,293,301	
184	4,293,875	72	4,293,938			78	4,293,273	7	4,293,571	173	4,293,302	
211	4,293,876	74	4,293,939					19	4,293,572	177	4,293,303	
213	4,293,877	75	4,293,940			51	4,293,274	43	4,293,573			
231	4,293,878	280	4,293,942			97 R	4,293,275	46	4,293,574			
		316	4,293,943			134 A	4,293,276	104	4,293,575	39	4,293,643	
CLASS 360							4,293,277		4,293,576	55	4,293,644	
10	4,293,879		CLASS 369				4,293,278	244	4,293,577		4,293,645	
	4,293,880	45	4,293,944			186 R	4,293,279	332	4,293,578		4,293,646	
60	4,293,881					227 A	4,293,280	535	4,293,579	69	4,293,647	
85	Re.30,762		CLASS 370			237	4,293,280	560	4,293,580	70	4,293,648	
93	4,293,882	17	4,293,945					630	4,293,581	118	4,293,649	
104	4,293,883	62	4,293,946			CLASS 417		637	4,293,582	119	4,293,650	
121	4,293,884	89	4,293,947					657	4,293,583	169	4,293,651	
130.33	4,293,885	90	4,293,948			53	4,293,282	CLASS 427		172	4,293,652	
						172	4,293,283			237	4,293,653	
CLASS 361		CLASS 371				218	4,293,284	11	4,293,584	241	4,293,654	
71	4,293,886	6	4,293,949			240	4,293,285	40	4,293,585	316	4,293,655	
120	4,293,887	21	4,293,950			253	4,293,286	68	4,293,586			
152	4,293,888	43	4,293,951			393	4,293,287	90	4,293,587			
212	4,293,889					434	4,293,288	93	4,293,588			
310	4,293,890		CLASS 375						4,293,589	83	4,293,304	
383	4,293,891	14	4,293,952			CLASS 418			4,293,590			
		25	4,293,953					97	4,293,591	54	4,293,954	
CLASS 362						84	4,293,289	98	4,293,592		4,293,955	
17	4,293,892		CLASS 376			104	4,293,291	106	4,293,593	327	4,293,956	
38	4,293,893	159	4,293,979					107	4,293,594			
100	4,293,894	209	4,293,980			CLASS 422		121	4,293,595			
147	4,293,895	230	4,293,981			62	4,293,521	160	4,293,596	CLASS 474		
200	4,293,896	283	4,293,985			80	4,293,522	186	4,293,597	80	Re.30,758	
284	4,293,897	290	4,293,983			139	4,293,523	203	4,293,598	CLASS 521		
291	4,293,898	308	4,293,982			169	4,293,524	274	4,293,599	88	4,293,656	
294	4,293,899	391	4,293,984			176	4,293,525	385.5	4,293,600	121	4,293,657	
342	4,293,900	461	4,293,986			205	4,293,526			129	4,293,658	
346	4,293,901							CLASS 428				
		CLASS 400				6	4,293,527	24	4,293,601	CLASS 525		
CLASS 363						7	4,293,528	28	4,293,602	28	4,293,659	
26	4,293,902	124	4,293,232			10	4,293,233	86	4,293,603	68	4,293,660	
68	4,293,903	144.2	4,293,233			32	4,293,234	90	4,293,604	127	4,293,661	
86	4,293,904	196.1	4,293,234			18	4,293,235	126	4,293,605	184	4,293,662	
		322	4,293,235			232	4,293,531	203	4,293,606	187	4,293,663	

CLASSIFICATION OF DESIGNS

D2—	185	261,070	106	261,091		261,112	D14—	5	261,136	D21—	60	261,157		62	261,178
	187	261,071	129	261,092	39	261,113		33	261,137		102	261,158	D26—	9	261,179
	230	261,072	151	261,093	103	261,114		53	261,139		122	261,159		66	261,180
	232	261,073	155	261,094	112	261,115		78	261,140			261,160	D28—	32	261,181
	233	261,074	157	261,095	114	261,116		108	261,138	150	261,161		D30—	2	261,182
D3—	41	261,075	22	261,096	118	261,117	D15—	23	261,141			261,162			261,183
	42	261,076	61	261,097	121	261,118		110	261,142			261,163			261,184
	52	261,077	70	261,098		261,119	D11—	127	261,143	158	261,164				261,185
D6—	35	261,078	330	261,099	15	261,120	D16—	11	261,144	160	261,165				261,186
	63	261,079	336	261,100		261,121		30	261,145			261,166		42	261,187
	70	261,080	353	261,101	34	261,122		31	261,146	220	261,167	D34—	24		261,188
	89	261,081	383	261,102	86	261,123		32	261,147	225	261,168		34		261,189
	114	261,082	300	261,103	160	261,124			261,148	D22—	27	261,169			261,190
	161	261,083	329	261,104	129	261,125	D12—	43	261,149	D23—	64	261,170		45	261,191
	200	261,084	353	261,105	147	261,130		2	261,150	65	261,171			46	261,192
D7—	6	261,085	369	261,106	157	261,131	D18—	14	261,151	D24—	17	261,172	D47—	6 E	261,193
	15	261,086	370	261,107	182	261,132			261,152	21	261,173				261,194
	66	261,087		261,108	203	261,133		22	261,153	29	261,174				261,195
	77	261,088	384	261,109	300	261,128		4	261,154	99	261,175				261,196
	101	261,089	432	261,110	13	261,134	D13—	33	261,155	D25—	11	261,176	D92—	1 A	261,197
	102	261,090	D10—	38	261,111	30	261,135		59	261,156	17	261,177		1 R	261,198
														1 Y	261,199

CLASSIFICATION OF PLANTS

P—	47	4,772	69	4,773	4,774			
----	----	-------	----	-------	-------	--	--	--

DEFENSIVE PUBLICATIONS APPLICATIONS

[Notice of Dec. 16, 1969, 869 O.G. 6877]

8—	495	T101,102	430—	598	T101,103	564—	334	T101,101			
----	-----	----------	------	-----	----------	------	-----	----------	--	--	--

GEOGRAPHICAL INDEX
OF RESIDENCE OF INVENTORS

(U.S. States, Territories and Armed Forces, the Commonwealth of Puerto Rico, and the Canal Zone)

Alabama	1	Kentucky	21	Oregon	41
Alaska	2	Louisiana	22	Pennsylvania	42
American Samoa	3	Maine	23	Puerto Rico	43
Arizona	4	Maryland	24	Rhode Island	44
Arkansas	5	Massachusetts	25	South Carolina	45
California	6	Michigan	26	South Dakota	46
Canal Zone	7	Minnesota	27	Tennessee	47
Colorado	8	Mississippi	28	Texas	48
Connecticut	9	Missouri	29	Utah	49
Delaware	10	Montana	30	Vermont	50
District of Columbia	11	Nebraska	31	Virginia	51
Florida	12	Nevada	32	Virgin Islands	52
Georgia	13	New Hampshire	33	Washington	53
Guam	14	New Jersey	34	West Virginia	54
Hawaii	15	New Mexico	35	Wisconsin	55
Idaho	16	New York	36	Wyoming	56
Illinois	17	North Carolina	37	U.S. Air Force	57
Indiana	18	North Dakota	38	U.S. Army	58
Iowa	19	Ohio	39	U.S. Navy	59
Kansas	20	Oklahoma	40		

(First number in listing denotes location according to above key. Refer to patent number in body of the Official Gazette to obtain details as to inventor name, location, etc.)

PATENTS

2 :	4,293,578	4,293,107	4,293,917	4,293,323	4,293,403	4,292,994
6 :	4,292,840	4,293,113	4,293,928	4,293,405	4,293,413	4,293,158
	4,293,089	4,293,127	4,293,956	4,293,497	4,293,442	4,293,850
	4,293,894	4,293,130	4,293,126	4,293,529	4,293,510	4,292,783
9 :	4,293,109	4,293,132	4,293,231	4,293,613	4,293,536	4,292,913
	4,293,572	4,293,133	4,293,861	4,293,614	4,293,648	4,293,120
01 :	4,292,748	4,293,135	4,293,862	4,293,817	4,293,658	4,293,729
	4,292,880	4,293,162	4,293,925	4,293,878	4,293,664	4,293,859
	4,292,918	4,293,165	Re. 30,757	4,293,921	4,293,689	4,293,118
	4,292,954	4,293,178	Re. 30,764	4,292,739	4,293,706	4,293,153
	4,293,216	4,293,181	4,292,717	4,292,822	4,293,722	4,293,170
	4,293,217	4,293,182	4,292,765	4,292,902	4,293,738	4,293,244
	4,293,233	4,293,192	4,292,807	4,293,008	4,293,757	4,293,851
04 :	4,292,729	4,293,196	4,292,834	4,293,062	4,293,804	4,292,915
	4,292,870	4,293,223	4,292,835	4,293,066	4,293,835	4,292,970
	4,293,175	4,293,267	4,292,995	4,293,069	4,293,874	4,293,239
	4,293,220	4,293,281	4,293,053	4,293,097	4,293,887	4,293,241
	4,293,519	4,293,296	4,293,079	4,293,145	4,293,895	4,293,319
	4,293,562	4,293,314	4,293,154	4,293,293	4,292,698	4,293,360
05 :	4,292,952	4,293,316	4,293,157	4,293,881	4,292,707	4,293,360
06 :	Re. 30,762	4,293,352	4,293,174	15 :	4,293,119	4,292,753
	Re. 30,763	4,293,365	4,293,186	16 :	4,292,797	4,292,951
	4,292,689	4,293,366	4,293,315		4,293,015	4,293,128
	4,292,692	4,293,371	4,293,406		4,293,400	4,293,222
	4,292,699	4,293,372	4,293,624		4,293,582	4,293,280
	4,292,702	4,293,401	4,292,692	17 :	4,292,708	4,293,339
	4,292,704	4,293,425	4,293,746		4,292,719	4,293,380
	4,292,706	4,293,451	4,292,721		4,292,721	4,293,390
	4,292,714	4,293,537	4,293,933		4,292,751	4,293,567
	4,292,722	4,293,561	4,292,756		4,292,756	4,293,136
	4,292,752	4,293,587	4,292,761		4,292,758	4,293,139
	4,292,784	4,293,619	4,292,789	10 :	4,292,789	4,293,355
	4,292,787	4,293,652	4,293,330		4,292,790	4,293,482
	4,292,803	4,293,701	4,292,808		4,292,808	4,293,483
	4,292,806	4,293,732	4,293,473		4,292,833	4,293,484
	4,292,838	4,293,763	4,293,615		4,292,841	4,293,485
	4,292,843	4,293,778	4,293,674		4,292,841	4,293,486
	4,292,865	4,293,795	4,293,452	11 :	4,292,940	4,293,487
	4,292,876	4,293,796	4,292,730	12 :	4,292,969	4,293,488
	4,292,882	4,293,797	4,292,780		4,292,971	4,293,489
	4,292,891	4,293,798	4,292,804		4,293,025	4,293,490
	4,292,898	4,293,826	4,292,852		4,293,050	4,293,491
	4,292,901	4,293,833	4,292,888		4,293,070	4,293,493
	4,292,935	4,293,841	4,293,013		4,293,141	4,293,495
	4,292,957	4,293,847	4,293,026		4,293,151	4,293,539
	4,292,974	4,293,848	4,293,083		4,293,179	4,293,552
	4,292,983	4,293,857	4,293,091		4,293,254	4,293,558
	4,293,031	4,293,858	4,293,104		4,293,257	4,293,569
	4,293,046	4,293,871	4,293,122		4,293,261	4,293,571
	4,293,052	4,293,884	4,293,124		4,293,320	4,293,584
	4,293,073	4,293,904	4,293,263		4,293,346	4,293,585
	4,293,075	4,293,909	4,293,266		4,293,367	4,293,589
	4,293,086	4,293,914	4,293,311		4,293,387	4,293,592

GEOGRAPHICAL INDEX OF RESIDENCE OF INVENTORS

4,293,137	4,293,169	4,293,704	4,293,043	4,293,172	4,293,163
4,293,188	4,293,211	4,293,805	4,292,726	4,293,191	4,293,167
4,293,208	4,293,441	4,293,806	4,292,781	4,293,193	4,293,249
4,293,234	4,293,604	4,293,818	4,292,802	4,293,253	4,293,276
4,293,322	4,293,606	4,293,837	4,292,817	4,293,269	4,293,283
4,293,338	4,293,625	4,293,864	4,292,827	4,293,292	4,293,309
4,293,341	4,293,663	4,293,870	4,292,848	4,293,310	4,293,347
4,293,396	4,293,675	4,293,875	4,292,862	4,293,398	4,293,394
4,293,436	4,293,741	4,293,898	4,292,866	4,293,415	4,293,402
4,293,461	4,293,882	4,293,907	4,292,874	4,293,454	4,293,427
4,293,462	4,292,963	4,293,953	4,292,893	4,293,457	4,293,428
4,293,524	4,292,713	4,293,279	4,292,998	4,293,471	4,293,470
4,293,527	4,292,858	4,292,690	4,293,000	4,293,496	4,293,522
4,293,595	4,292,932	4,292,691	4,293,001	4,293,502	4,293,528
4,293,610	4,293,164	4,292,724	4,293,010	4,293,531	4,293,672
4,293,622	4,293,274	4,292,754	4,293,016	4,293,538	4,293,723
4,293,654	4,293,288	4,292,759	4,293,027	4,293,546	4,293,758
4,293,693	4,293,353	4,292,762	4,293,044	4,293,593	4,293,802
4,293,766	4,293,392	4,292,792	4,293,095	4,293,594	4,293,823
4,293,769	4,293,393	4,292,801	4,293,099	4,293,665	4,293,863
4,293,892	4,293,429	4,292,815	4,293,114	4,293,666	4,293,888
4,293,908	4,293,432	4,292,921	4,293,140	4,293,667	4,293,901
4,292,740	4,293,668	4,292,923	4,293,140	4,293,696	4,293,906
4,292,746	4,293,756	4,292,924	4,293,264	4,293,703	4,293,932
4,292,749	4,293,759	4,292,933	4,293,302	4,293,716	4,293,934
4,292,831	4,293,131	4,292,956	4,293,317	4,293,724	4,293,936
4,292,851	4,293,545	4,292,968	4,293,327	4,293,725	4,293,937
4,292,869	4,293,955	4,293,021	4,293,329	4,293,726	4,293,937
4,292,892	4,293,845	4,293,057	4,293,340	4,293,727	4,293,937
4,292,916	4,292,775	4,293,060	4,293,343	4,293,747	4,293,917
4,292,919	4,292,776	4,293,063	4,293,358	4,293,784	4,293,783
4,292,930	4,293,203	4,293,064	4,293,391	4,293,791	4,292,878
4,292,945	4,292,818	4,293,088	4,293,433	4,293,792	4,293,011
4,292,948	4,292,856	4,293,093	4,293,443	4,293,838	Re. 30,758
4,292,958	4,292,867	4,293,214	4,293,449	4,293,856	4,292,720
4,293,017	4,292,906	4,293,215	4,293,480	4,293,886	4,292,757
4,293,080	4,292,909	4,293,221	4,293,498	4,293,900	4,292,872
4,293,159	4,292,953	4,293,224	4,293,503	4,293,905	4,292,979
4,293,173	4,292,959	4,293,230	4,293,517	4,293,930	4,293,098
4,293,218	4,292,960	4,293,242	4,293,548	4,292,910	4,293,129
4,293,258	4,292,965	4,293,325	4,293,617	4,292,715	4,293,460
4,293,262	4,292,972	4,293,361	4,293,707	4,292,712	4,293,951
4,293,268	4,293,067	4,293,374	4,293,714	4,292,723	4,292,777
4,293,284	4,293,078	4,293,416	4,293,719	4,292,839	4,292,863
4,293,291	4,293,108	4,293,422	4,293,730	4,293,286	4,292,886
4,293,299	4,293,150	4,293,439	4,293,733	4,293,305	4,293,110
4,293,354	4,293,212	4,293,469	4,293,789	4,293,518	4,293,112
4,293,379	4,293,333	4,293,534	4,293,821	4,293,682	4,293,142
4,293,408	4,293,334	4,293,535	4,293,912	4,293,351	4,293,155
4,293,476	4,293,348	4,293,568	4,293,924	4,292,687	4,293,421
4,293,477	4,293,378	4,293,597	4,292,846	4,292,693	4,293,027
4,293,505	4,293,404	4,293,598	4,293,036	4,292,763	4,293,855
4,293,547	4,293,414	4,293,601	4,293,146	4,293,020	4,293,915
4,293,609	4,293,444	4,293,602	4,293,228	4,293,071	4,292,786
4,293,611	4,293,446	4,293,603	4,293,287	4,293,324	4,292,982
4,293,629	4,293,450	4,293,616	4,293,440	4,293,559	4,293,243
4,293,644	4,293,453	4,293,626	4,293,688	4,293,721	4,293,678
4,293,646	4,293,455	4,293,627	4,293,728	4,292,772	4,292,805
4,293,651	4,293,464	4,293,631	4,293,815	4,292,842	4,292,816
4,293,676	4,293,465	4,293,632	4,293,849	4,292,895	4,292,877
4,293,708	4,293,467	4,293,640	4,292,771	4,292,908	4,292,992
4,293,709	4,293,475	4,293,642	4,293,042	4,292,912	4,293,040
4,293,710	4,293,481	4,293,681	4,293,785	4,292,920	4,293,059
4,293,711	4,293,499	4,293,683	4,293,816	4,292,987	4,293,125
4,293,712	4,293,513	4,293,684	4,292,694	4,292,988	4,293,282
4,293,744	4,293,544	4,293,752	4,292,695	4,293,034	4,293,290
4,293,777	4,293,554	4,293,755	4,292,705	4,293,035	4,293,337
4,293,814	4,293,555	4,293,822	4,292,731	4,293,037	4,293,342
4,293,876	4,293,569	4,293,846	4,292,734	4,293,038	4,293,459
4,292,701	4,293,570	4,293,910	4,292,736	4,293,039	4,293,573
4,292,814	4,293,579	4,293,919	4,292,767	4,293,047	4,293,659
4,292,929	4,293,591	4,293,943	4,292,782	4,293,048	4,293,770
4,292,950	4,293,591	4,293,943	4,292,810	4,293,100	4,293,771
4,292,990	4,293,623	4,292,770	4,292,976	4,293,115	4,293,807
4,293,032	4,293,635	4,292,788	4,292,978	4,293,116	4,293,834
4,293,041	4,293,670	4,293,177	4,293,005	4,293,117	4,293,920
4,293,102	4,293,686	4,292,700	4,293,090	4,293,148	

U.S. GOVERNMENT PRINTING OFFICE : O-1981

DESIGN PATENTS

4 : 261,183	261,169	261,121	29 : 261,142	261,137	47 : 261,077
261,184	261,171	261,122	261,098	261,173	261,078
261,185	261,175	261,138	31 : 261,096	261,174	261,080
6 : 261,181	261,178	261,082	261,156	261,176	261,128
9 : 261,114	261,092	261,090	34 : 261,124	261,180	261,155
06 : 261,073	261,132	261,116	261,157	261,157	261,103
261,075	261,172	261,151	261,186	261,177	261,117
261,084	261,099	261,152	261,194	261,115	261,153
261,085	261,123	261,159	261,081	261,143	261,076
261,093	261,135	261,160	261,094	261,189	261,079
261,100	261,072	261,167	261,097	261,190	261,070
261,127	261,083	261,150	261,105	261,191	261,089
261,147	261,101	261,086	261,107	261,091	261,118
261,148	261,119	261,131	261,108	261,102	261,170
261,168	261,120	261,133	261,109	261,179	261,106

PLANT PATENTS

13 : 4,772				
------------	--	--	--	--

DEFENSIVE PUBLICATIONS APPLICATIONS
[Notice of Dec. 16, 1969, 869 O.G. 6877]

10 : T101,101	T101,102			
---------------	----------	--	--	--

U.S. GOVERNMENT PRINTING OFFICE : O-1981

CHANGE OF ADDRESS FORM

NAME—FIRST, LAST	
COMPANY NAME OR ADDITIONAL ADDRESS LINE	
STREET ADDRESS	
CITY	STATE ZIP CODE

PLEASE PRINT OR TYPE

(or) COUNTRY

Mail this form to: NEW ADDRESS

Superintendent of Documents
Government Printing Office SSOM
Washington, D.C. 20402

Attach last subscription
label here.

SUBSCRIPTION ORDER FORM

SUBSCRIPTION ORDER FORM

ENTER MY SUBSCRIPTION TO:

@ \$ Domestic; @ \$ Foreign.


NAME—FIRST, LAST	
COMPANY NAME OR ADDITIONAL ADDRESS LINE	
STREET ADDRESS	
CITY	STATE ZIP CODE

PLEASE PRINT OR TYPE

(or) COUNTRY

- ☐ Remittance Enclosed (Make checks payable to Superintendent of Documents)
- ☐ Charge to my Deposit Account No.

MAIL ORDER FORM TO:
Superintendent of Documents
Government Printing Office
Washington, D.C. 20402



Vol. 1011 Number 2

OFFICIAL GAZETTE

of the
UNITED STATES PATENT AND TRADEMARK OFFICE



October 13, 1981

U.S.
DEPARTMENT
OF COMMERCE

Patent
and
Trademark
Office

OFFICIAL GAZETTE of the
UNITED STATES PATENT and TRADEMARK OFFICE

October 13, 1981

Volume 1011

Number 2

CONTENTS

	Page
Patent and Trademark Office Notices	
Patent Cooperation Treaty (PCT) Information	1011 OG 10
Reissue Applications Filed	1011 OG 10
Requests for Reexamination Filed	1011 OG 10
Errata	1011 OG 10
Patent Certificates of Correction	1011 OG 11
Disclaimers	1011 OG 11
Dedications	1011 OG 11
Patents Available for License or Sale	1011 OG 11
Reference Collections of U.S. Patents Available for Public Use in Patent Depository Libraries	1011 OG 16
Condition of Patent Applications	1011 OG 17
Reissue Patents Granted (30,765)	451
Plant Patents Granted (4,775)	455
Patents Granted	
General and Mechanical (4,293,957)	457
Chemical (4,294,575)	665
Electrical (4,295,000)	789
Design Patents Granted (261,195)	871
Index of Patentees	PI 1
Indices of Reissue, Design and Plant Patentees	PI 46
Classification of	
Patents (Including Reissues)	PI 51
Designs and Plants	PI 54
Geographical Index of Residence of Inventors	
Patents (Including Reissues)	PI 55
Designs and Plants	PI 56
Change of Address Form and Subscription Order Form	Back Page

The following are mailed under direction of the Superintendent of Documents, Government Printing Office, Washington, D.C., 20402, to whom all subscriptions should be made payable and all communications addressed:

THE OFFICIAL GAZETTE (PATENT SECTION), issued weekly, subscription \$325.00 per annum for first-class mailing, also available as fourth-class mail at \$225.00 domestic; \$281.25 foreign; foreign first-class mailing rates will be furnished upon request; single copies each, \$5.50 domestic, \$6.90 foreign.

THE OFFICIAL GAZETTE (TRADEMARK SECTION), issued weekly, subscription \$105.00 per annum, foreign mailing \$131.25 per annum; single copies \$2.75 each domestic, \$3.45 foreign.

GENERAL INFORMATION concerning PATENTS, price \$2.25 each.

GENERAL INFORMATION concerning TRADEMARKS, price \$1.70 each.

PRINTED COPIES OF PATENTS are furnished by the Patent and Trademark Office at 50 cents each; PLANT PATENTS in color, \$1.00 each; copies of TRADEMARKS AND DESIGN PATENTS at 20 cents each. Address orders to the Commissioner of Patents and Trademarks, Washington, D.C., 20231.

PATENT AND TRADEMARK OFFICE NOTICES

Patent Cooperation Treaty Information

For information concerning the PCT, consult Chapter 1800 of the Manual of Patent Examining Procedure and notices 90-95 in the consolidated listing of notices appearing in the Official Gazette of Jan. 6, 1981.

The PCT fees in effect after May 19, 1981 are as follows:

Transmittal fee	\$ 35.00
Search fee	300.00
International Basic Fee (for the first 30 sheets of an international application)	215.00
Basic Supplemental Fee (for each sheet over 30)	4.00
International Designation Fee (for each State for which a national patent is sought, or group of States for which the same regional patent is sought)	50.00

RENE D. TEGTMEYER,
Assistant Commissioner
for Patents.

REISSUE APPLICATIONS FILED

Notice under 37 CFR 1.11(b). The reissue applications listed below are open to inspection by the general public in the indicated Examining Groups and copies may be obtained by paying the fee therefor (37 CFR 1.21(b)).

3,693,629, Re. S.N. 272,615; Filed June 11, 1981, Cl. 131/5, LIGHTLY PRIZED TOBACCO, James A. Broughton, Owner of Record: *Brown & Williamson Tobacco Corp., Louisville, Ky.*, Attorney or Agent: Charles G. Lamb, Ex. Gp.: 335

4,109,750, Re. S.N. 266,715, Filed May 26, 1981, Cl. 181/224, ZENO DUCT SOUND ATTENUATING MEANS, Leslie S. Wirt, Owner of Record: *Lockhead Aircraft Corp., Burbank, Calif.*, Attorney or Agent: Frederic P. Smith, Ex. Gp.: 211

4,155,878, Re. S.N. 270,371, Filed June 4, 1981, Cl. 252/423, PROCESS FOR MAKING ACTIVATED CARBON WITH CONTROL OF METAL ION CONCENTRATION IN PHOSPHORIC ACID, Edward D. Tolles, et al., Owner of Record: *Westvaco Corp., New York, N.Y.*, Attorney or Agent: Richard L. Schmalz, et al., Ex. Gp.: 117

4,181,457, Re. S.N. 271,322, Filed June 8, 1981, Cl. 408/217, TAPPING TOOL FOR MAKING VIBRATION RESISTANT PREVAILING TORQUE FASTENER, Horace D. Holmes, Owner of Record: *Inventor*, Attorney or Agent: Allen M. Krass, et al., Ex. Gp.: 324

4,237,165, Re. S.N. 272,513, Filed June 11, 1981, Cl. 424/308, TREATMENT OF CARBOHYDRATE METABOLISM DISORDERS, Jacques Duhault, Owner of Record: *Science Union et cie Societe Francaise de*

Recherche Medicale, Suresnes, France, Attorney or Agent: Gordon W. Hueschen, Ex. Gp.: 125

REQUESTS FOR REEXAMINATION FILED

Notice under 37 CFR 1.11(c). The requests for reexamination listed below are open to inspection by the general public in the indicated Examining Groups. Copies of the requests and related papers may be obtained by paying the fee therefor established in the Rules (37 CFR 1.21(b)).

In the event correspondence to the patent owner is not received, this notice will be considered to be constructive notice to the patent owner and reexamination will proceed (37 CFR 1.248(a)(5) and 1.525(b)).

3,091,912, Reexam. No. 90/000,068, Requested: Sept. 9, 1981, Cl. 57/247, METHOD OF PROCESSING STRETCH YARN AND YARNS PRODUCED THEREBY, Nicholas J. Stoddard, et al., Owner of Record: *Lex Tex Ltd., Inc.*, Attorney or Agent: Howson & Howson, Ex. Gp.: 244, Requester: Glen Raven Mills, Inc., et al., c/o Cushman, Darby & Cushman, Washington, D.C.

3,449,567, Reexam. No. 90/000,065, Requested: Sept. 8, 1981, Cl. 250/362, APPARATUS AND PROCESS FOR DETERMINING PARTICLE SIZE BY X-RAY ABSORPTION ANALYSIS, James Peter Olivier, et al., Owner of Record: *Freeport Minerals Co.*, Attorney or Agent: Paul J. Luckern, Ex. Gp.: 252, Requester: Micromeritics Instrument Corp., Norcross, Ga.

Errata

The following registration numbers, listed in the "Trademark Registrations Issued" section of the Official Gazettes of Feb. 24, 1981, May 26, 1981, Aug. 18, 1981, and Aug. 25, 1981, were assigned, prematurely, to published marks for which the opposition period had not yet run:

TMOG Feb. 24, 1981	TMOG May 26, 1981	TMOG Aug. 18, 1981	TMOG Aug. 25, 1981
1,147,842	1,155,713	1,165,412	1,166,062
		1,165,465	1,166,299
		1,165,588	1,166,392
		1,165,620	1,166,414
		1,165,738	1,166,454
			1,166,541
			1,166,687

Consequently, certificates of registration bearing the above-identified numbers were not issued on the dates indicated, and these registration numbers have been vacated.

Sept. 15, 1981. Margaret Lawrence,
Assistant Commissioner
for Trademarks.

PATENT NOTICES

Certificates of Correction for the Week of Oct. 13, 1981

Re. 30,476	4,243,091	4,265,658	4,275,458
D. 259,815	4,243,584	4,265,817	4,275,688
D. 260,031	4,243,673	4,266,481	4,275,953
3,605,892	4,244,033	4,266,608	4,276,002
4,011,191	4,244,990	4,266,642	4,276,278
4,019,015	4,245,405	4,266,765	4,276,325
4,026,835	4,248,039	4,266,865	4,276,756
4,043,391	4,248,529	4,266,878	4,276,996
4,071,959	4,248,750	4,267,082	4,277,216
4,075,709	4,248,980	4,267,258	4,277,258
4,100,136	4,250,408	4,267,334	4,277,611
4,104,732	4,251,448	4,267,340	4,277,826
4,123,604	4,252,786	4,267,354	4,278,032
4,124,056	4,252,909	4,267,385	4,278,171
4,124,679	4,253,794	4,267,835	4,278,176
4,156,964	4,254,037	4,267,875	4,278,465
4,164,617	4,254,401	4,268,451	4,278,805
4,181,168	4,254,443	4,268,539	4,279,902
4,182,751	4,254,612	4,268,598	4,279,941
4,196,282	4,255,671	4,268,686	4,280,038
4,200,849	4,255,864	4,268,756	4,280,990
4,203,893	4,255,876	4,269,440	4,281,150
4,210,614	4,256,615	4,269,707	4,281,159
4,212,118	4,257,111	4,269,713	4,281,164
4,212,205	4,260,062	4,269,733	4,281,196
4,218,344	4,260,766	4,269,917	4,281,302
4,218,609	4,261,002	4,270,190	4,281,429
4,219,192	4,261,185	4,270,277	4,281,554
4,226,547	4,261,848	4,271,426	4,281,760
4,230,430	4,261,866	4,271,466	4,281,971
4,230,611	4,262,232	4,272,209	4,282,393
4,230,696	4,262,282	4,272,698	4,282,566
4,231,676	4,262,341	4,273,435	4,282,601
4,232,034	4,264,344	4,273,586	4,282,618
4,235,709	4,264,439	4,274,071	4,282,658
4,237,068	4,264,610	4,274,297	4,283,146
4,237,443	4,264,921	4,274,852	4,283,311
4,239,298	4,264,933	4,275,376	4,283,453
4,242,150	4,265,633	4,275,438	4,284,942

Disclaimers

Re. 28,682.—*Charles E. Hoey*, Marlton, N.J. DECORATIVE LAMINATE. Patent dated Jan. 13, 1976. Disclaimer filed May 29, 1981, by the assignee, *Rohm & Haas Co.*

Hereby enters this disclaimer to all claims of said patent.

3,163,645.—*George de Stevens and Lincoln Harvey Werner*, Summit, N. J. DERIVATIVES OF 3,4-DIHYDRO-2-H-[1,2,4]-BENZOTHIADIAZINE-1, 1-DI-OXIDES. Patent dated Dec. 29, 1964. Disclaimer filed June 29, 1981, by the assignee, *Ciba-Geigy Corp.*

Hereby enters this disclaimer to all claims of said patent.

4,068,488.—*D. Graham Ball*, North Vancouver, Canada. METHOD OF BACKFILLING PIPELINE TRENCHES. Patent dated Jan. 17, 1978. Disclaimer filed July 31, 1981, by the assignee, *Rader Companies, Inc.*

Hereby enters this disclaimer to claims 3 and 6 of said patent.

4,166,415.—*Edwin A. Spanke*, Oak Forest and *Louis F. Carrieri*, La Grange Park, Ill. PRESS HAVING OVERLOAD RESPONSIVE SLIDE SHUT

HEIGHT ADJUSTING MECHANISM. Patent dated Sept. 4, 1979. Disclaimer filed July 6, 1981, by the assignee, *Gulf & Western Manufacturing Co.*

Hereby enters this disclaimer to claims 1 and 5 of said patent.

4,204,212.—*Arthur R. Sindoris*, Cary, N.C., *Frederick G. Farrar*, Kensington, and *Daniel H. Schaubert*, Silver Spring, Md. CONFORMAL SPIRAL ANTENNA. Patent dated May 20, 1980. Disclaimer filed Aug. 11, 1981, by the assignee, *The United States of America as represented by the Secretary of the Army.*

Hereby enters this disclaimer to claims 1-2 and 4-5 of said patent.

4,272,980.—*Louis F. Carrieri*, La Grange Park, IL. LOAD EQUALIZER FOR PRESS TOOLING. Patent dated June 16, 1981. Disclaimer filed July 6, 1981, by the assignee, *Gulf & Western Manufacturing Co.*

Hereby enters this disclaimer to claims 1, 3, 8 and 17 of said patent.

Dedications

3,291,947.—*Roswell C. Van Sickle*, Wilkesburg, Pa. INTERRUPTING STRUCTURES FOR COMPRESSED-GAS CIRCUIT INTERRUPTERS HAVING DOUBLE-BREAK HOLLOW ROTATIVE MOVING CONTACT-ARM ASSEMBLY. Patent dated Dec. 13, 1966. Dedication filed July 20, 1981, by the assignee, *Westinghouse Electric Corp.*

Hereby dedicates to the Public the remaining term of said patent.

4,270,640.—*David A. Davies*, Leamington SPA, United Kingdom. FRICTION CLUTCH DRIVEN PLATES. Patent dated June 2, 1981. Dedication filed Aug. 31, 1981, by the assignee, *Automotive Products Ltd.*

Hereby dedicates to the public the remaining portion of the term of said patent.

Patents Available for License or Sale

3,748,898. METHOD AND APPARATUS RELATED TO THE TESTING OF HYDRAULIC CIRCUITS. *Neil F. Greenblum, Esq. Sandler & Greenblum*, 1717 K St., N. W., Suite 1101, Washington, D.C. 20006 202-659-0035.

3,961,865. CONVERSION BRACKET FOR WELL PUMP. *Vernon E. Spaulding*, 7021 Grade La., Louisville, Ky. 40213.

4,031,862. ECONOMIZER. *Richard D. Weber, Synnestvedt & Lechner*, 3131 PSFS Bldg. 12, South 12th St., Philadelphia, Pa. 19107.

4,136,764. MOTHER ALICE'S BREAD VENDING MACHINE. *Alice Johnson*, 8650 Belford Ave. #11, Los Angeles, Calif. 90045 or Attorney Bernard Kleinke, (312) 332-6930.

4,209,539. DETOXIFICATION OF BOTANICAL FOODSTUFFS. *Thomas F. Banigan and Anthony J. Verbiscar*, Anver Bioscience Design, Inc., 160 E. Montecito Ave., Sierra Madre, Calif. 91024.

4,222,371. SOLAR ENERGY COLLECTOR. *George F. Heath*, 1655 Richard Ave. Sanger, Calif. 92657.

4,225,052. INSULATED FOOD CONTAINER. *Nancie Tector*. Correspondence to: Wagner & Aubel, 135 S. La Salle St., Chicago, Ill., 60603.

4,275,536. WALL ELEMENT FOR A CONSTRUCTION WALL. *Karl H. Vahlbrauk*, Kriegerweg 1, D-3353 Bad Gandersheim, Federal Republic of Germany. Correspondence to: Michael J. Striker, 360 Lexington Ave., New York, N.Y. 10017.

4,275,975. MINE ROOF ANCHOR SYSTEM. *Bennie E. Morgan*, Roof Control, Inc., 411 E. Main St., Morganfield, Ky. 42437.

4,270,123. DETECTOR FOR INDICATING A FIRE OR DETECTOR MALFUNCTION. *Neil F. Greenblum, Esq. Sandler & Greenblum*, 1717 K St., N. W. Suite 1101, Washington, D.C. 20006 202-659-0035.

4,231,061. INSTANT COLOR SLIDE RECORDER OF CRT IMAGE. *Samuel Freeman*, 13 Birchwood Ct. East, Syosset, N.Y. 11791.

Otis Engineering Corp. is prepared to grant licenses under the following patents upon reasonable terms. Address inquiries to: Patent Attorney, Otis Engineering Corp., P.O. Box 34380, Dallas, Tex. 75234, Telephone (214) 323-3882.

4,117,563. THREAD CHASER TOOL FOR CONTIGUOUS STRAIGHT AND TAPERED THREAD RUNS.

4,234,167. AUTOMATIC INHAUL WINCH SYSTEM.

General Electric Co. is prepared to grant non-exclusive licenses under the following patents upon reasonable terms to domestic manufacturers.

Applications for license may be addressed to: Patent Counsel, Industrial and Marine Steam Turbine Division, General Electric Co., 1100 Western Ave., Lynn, Ma. 01910.

3,651,662. GEAR TYPE FLEXIBLE COUPLING.

Application for license may be addressed to: Patent Counsel, Mobile Radio Products Department, Mobile Communications Business Division, General Electric Co., Mountain View, Lynchburg, Va. 24502.

4,259,596. CHARGE TRANSFER SIGNAL PROCESSING APPARATUS FILTER.

4,259,597. CHARGE TRANSFER SIGNAL PROCESSING APPARATUS FILTER.

4,259,598. CHARGE TRANSFER SIGNAL PROCESSING APPARATUS TRANSVERSAL FILTER.

Application for license may be addressed to the General Electric Co., Division Patent Counsel, Housewares and Audio Business Division, 1285 Boston Ave., Bridgeport, Conn. 06602.

4,229,811. INTRUSION DETECTION METHOD AND APPARATUS.

Applications for license may be addressed to: Patent Counsel, Mobile Radio Products Department, Mobile Communications Business Division, General Electric Co., Mountain View Rd., Lynchburg, Va. 24502.

4,281,413. MULTICHANNEL RADIO TELEPHONE SYSTEM.

Applications for license under the following patent should be addressed to: Mr. Arnold E. Renner, Division Patent Counsel, Industrial Electronics Systems Division General Electric Co., 1501 Roanoke Blvd., Salem, Va. 24153.

4,257,000. APPARATUS FOR CONTROLLING THE LENGTH OF MOVEMENT OF A

CONTROLLED MEMBER ALONG A PATH OF REPEATED OPERATING POSITIONS.

Applications for license may be addressed to Patent Counsel, Gas Turbine Division, General Electric Co., 1 River Rd., Bldg. 500, Room 218, Schenectady, N.Y. 12345.

4,275,559. RETRACTABLE IGNITER DEVICE FOR GAS TURBINES.

4,277,832. FLUID FLOW CONTROL SYSTEM.

Applicants for license may be addressed to: Patent Counsel, Transportation Systems, Business Division, General Electric Co., 2901 E. Lake Rd., Erie, Pa. 16531.

4,207,778. REINFORCED CROSS PLY COMPOSITE FLYWHEEL AND METHOD FOR MAKING SAME.

4,244,017. THIRD HARMONIC AUXILIARY COMMUTATED INVERTER HAVING SELECTABLE COMMUTATION CAPACITANCE AS A FUNCTION OF LOAD CURRENT.

4,258,302. APPARATUS FOR MAINTAINING SYNCHRONOUS MACHINE DRIVE SYSTEM AT LIGHT OF ZERO MACHINE LOADS.

Application for license may be addressed to the General Electric Co., Division Patent Counsel, Housewares and Audio Business Division, 1285 Boston Ave., Bridgeport, Conn. 06602.

D-210,895. DESIGN FOR CLOCK OR SIMILAR ARTICLE.

D-217,928. DESIGN FOR FLOOR POLISHER DISPENSER.

D-255,571. DESIGN FOR CITIZEN'S BAND RADIO OR SIMILAR ARTICLE.

D-255,572. DESIGN FOR A CLOCK RADIO OR SIMILAR ARTICLE.

D-248,468. DESIGN FOR CASSETTE TAPE RECORDER.

D-248,754. DESIGN FOR COMBINED CASSETTE TAPE RECORDER AND RADIO.

D-249,865. DESIGN FOR PORTABLE RADIO.

D-250,191. DESIGN FOR PORTABLE RADIO.

D-251,555. DESIGN FOR RADIO AND TAPE PLAYER OR SIMILAR ARTICLE.

D-251,782. DESIGN FOR TAPE RECORDER AND PLAYER OR SIMILAR ARTICLE.

D-251,841. DESIGN FOR CARTRIDGE TAPE PLAYER OR SIMILAR ARTICLE.

D-253,107. DESIGN FOR TAPE PLAYER OR SIMILAR ARTICLE.

D-255,444. DESIGN FOR COMBINED TAPE RECORDER AND PLAYER OR SIMILAR ARTICLE.

4,065,658. ELECTRIC TOASTER CONTROL.

4,166,994. THERMOSTAT WITH POSITIVE OFF POSITION.

4,220,134. TOASTER/OVEN ACCESSORY CONTAINER.

4,278,873. TEMPERATURE-RESPONSIVE CONTROL MEANS.

D-256,013. DESIGN FOR COMBINED CASSETTE TAPE PLAYER AND RADIO.

D-256,122. DESIGN FOR COMBINED RADIO AND WALKIE TALKIE OR SIMILAR ARTICLE.

D-256,123. DESIGN FOR CLOCK RADIO OR SIMILAR ARTICLE.

3,805,375. COMPOSITE INTEGRATED CIRCUITS INCLUDING SEMICONDUCTOR

3,654,563. TOR CHIPS MOUNTED ON A COMMON SUBSTRATE WITH CONNECTIONS MADE THROUGH A DIELECTRIC ENCAPSULATOR.

3,816,196. PASSIVATION OF PHOTORESIST MATERIALS USED IN SELECTIVE PLASMA ETCHING.

3,816,198. SELECTIVE PLASMA ETCHING OF ORGANIC MATERIALS EMPLOYING PHOTOLITHOGRAPHIC TECHNIQUES.

3,835,397. DIGITALLY CONTROLLED PHASE SHIFT NETWORK.

3,840,293. ELECTRONICALLY DRIVEN SPIRAL SCAN SYNCHRONOUS TRANSMIT-RECEIVER LASER SYSTEM.

3,840,827. DIODE PHASE SHIFTING NETWORK.

3,853,496. METHOD OF MAKING A METAL INSULATOR SILICON FIELD EFFECT TRANSISTOR (MIS-FET) MEMORY DEVICE AND THE PRODUCT.

3,856,406. HETERODYNE LASER ABSORPTION SPECTROMETER.

3,860,399. LIQUID BLOCKING TECHNIQUE FOR WORKING A MEMBER TO PRECISE OPTICAL TOLERANCES.

3,870,414. METHOD OF SENSING SURFACE DISPLACEMENT ORTHOGONAL TO THE DIRECTION OF OBSERVATION.

3,874,796. METHOD OF SURFACE CONTOURING.

3,879,988. OPTICAL COMPARATOR FOR MEASURING VIBRATION ON A ROTATING OBJECT.

3,904,925. POWER SUPPLY FOR A THERMIONIC EMISSION GAS DISCHARGE LAMP.

3,914,590. SERIAL TWO'S COMPLEMENTER.

3,919,558. HOT SUB-STAGE FOR A SCANNING ELECTRON MICROSCOPE.

3,920,951. LASER ETCHING APPARATUS FOR FORMING PHOTOGRAPHIC IMAGES ON METALLIC SURFACES.

Applications for licenses may be addressed to the Patent Counsel, Electronics Laboratory, General Electric Co., Electronics Park, Bldg. 2, Room 205, Syracuse, N.Y. 13221.

3,493,073. ACOUSTIC HOLOGRAPHIC APPARATUS WITH VISUAL DISPLAY.

3,558,974. LIGHT EMITTING DIODE ARRAY STRUCTURE.

3,559,091. BROADBAND INTERSTAGE COUPLING CIRCUIT.

3,594,795. RADAR SYSTEM.

3,599,104. LOGARITHMIC AMPLIFIER OF EXTENDED DYNAMIC RANGE.

3,614,404. ELECTRONIC CALCULATOR.

3,614,748. HIGH-SPEED MEMORY AND MULTIPLE LEVEL LOGIC NETWORK WITH PULSE SHAPING.

3,615,946. METHOD OF EMBEDDING SEMICONDUCTOR CHIP WITHIN A DIELECTRIC LAYER FLUSH WITH SURFACE.

3,621,354. DC MOTOR CURRENT ACTUATED DIGITAL CONTROL SYSTEM.

3,652,162. COMPLEX DATA PROCESSING SYS-

TEM EMPLOYING INCOHERENT OPTICS.

3,654,563. ACTIVE FILTER CIRCUIT HAVING NONLINEAR PROPERTIES.

3,655,371. METHOD AND APPARATUS FOR REPRODUCING OPTICAL INFORMATION.

3,679,941. COMPOSITE INTEGRATED CIRCUITS INCLUDING SEMICONDUCTOR CHIPS MOUNTED ON A COMMON SUBSTRATE WITH CONNECTIONS MADE THROUGH A DIELECTRIC ENCAPSULATOR.

3,691,628. METHOD OF FABRICATING COMPOSITE INTEGRATED CIRCUITS.

3,710,267. ENVELOPE RATE DEMODULATOR.

3,737,743. HIGH POWER MICROWAVE FIELD EFFECT TRANSISTOR.

3,757,175. COMPOSITE INTEGRATED CIRCUITS WITH COPLANAR CONNECTIONS TO SEMICONDUCTOR CHIPS MOUNTED ON A SINGLE SUBSTRATE.

3,767,308. METHOD AND APPARATUS FOR SENSING SURFACE DISPLACEMENT ORTHOGONAL TO THE LINE OF SIGHT.

3,782,176. APPARATUS FOR MEASURING VIBRATION IN A MOVING OBJECT.

Application for license may be addressed to: General Electric Co., Component Motor Division, 1635 Broadway, P.O. Box 2204, Fort Wayne, Ind. 46801, Attention: Patent Counsel.

3,261,992. ELECTRICAL LOAD BALANCING CONTROL SYSTEM.

3,881,238. APPARATUS FOR WINDING MAGNETIC CORES AND TREATING LEADS.

3,887,677. PROCESS OF MAKING A DYNAMOELECTRIC MACHINE STRUCTURE BY PRESSURE MOLDING.

4,107,583. DYNAMOELECTRIC MACHINE WINDING ARRANGEMENTS, DYNAMOELECTRIC MACHINES INCORPORATING SAME AND METHODS OF OPERATING SUCH DYNAMOELECTRIC MACHINES.

4,116,410. ADAPTABLE RESILIENT MOTOR MOUNTING.

4,243,967. THERMOSTAT AND METHOD OF OPERATING.

Applications for license may be addressed to: Group Patent Counsel, Major Appliance Business Group, General Electric Co., Appliance Park, Louisville, Ky. 40225.

3,640,264. COMBUSTOR MEANS FOR PRESSURIZED GAS-FIRED SPACE HEATER.

3,667,451. GAS-FIRED HEATER MEANS.

3,667,892. CONTROL MEANS FOR PRESSURIZED GAS-FIRED SPACE HEATER.

3,670,713. GAS-FIRED HEATER MEANS.

3,850,496. CONNECTOR BLOCK FOR HERMETIC MOTOR COMPRESSOR.

3,995,349. DOOR HANDLE OF A HOUSEHOLD REFRIGERATOR.

4,009,589. SINGLE EVAPORATOR, SINGLE FAN COMBINATION REFRIGERATOR WITH INDEPENDENT TEMPERATURE CONTROLS AND METHOD OF ADJUSTMENT.

- 4,009,590. SINGLE EVAPORATOR, SINGLE FAN COMBINATION REFRIGERATOR WITH INDEPENDENT TEMPERATURE CONTROLS.
- 4,009,591. SINGLE EVAPORATOR, SINGLE FAN COMBINATION REFRIGERATOR WITH INDEPENDENT TEMPERATURE CONTROLS.
- 4,031,715. FLEXIBLE COUPLING ASSEMBLY.
- 4,084,291. CENTER HINGE FOR TOP-MOUNT TWO DOOR REFRIGERATOR.
- 4,096,430. METAL-OXIDE-SEMICONDUCTOR VOLTAGE REFERENCE.
- 4,121,204. BAR GRAPH TYPE TOUCH SWITCH AND DISPLAY DEVICE.
- 4,138,859. SPLIT HEAT PUMP OUTDOOR FAN ARRANGEMENT.
- 4,156,350. REFRIGERATION APPARATUS DEMAND DEFROST CONTROL SYSTEM AND METHOD.
- 4,156,352. COOLING ARRANGEMENT FOR A REFRIGERATOR MACHINERY.
- 4,157,042. PULLEY DRIVE SYSTEM.
- 4,256,951. REPETITION RATE POWER CONTROL FOR APPLIANCE USING HIGH CURRENT INRUSH ELEMENTS.
- 4,261,182. AUTOMATIC ICEMAKER INCLUDING MEANS FOR MINIMIZING THE SUPERCOOLING EFFECT.
- 4,262,183. COMBINATION MICROWAVE/FORCED CONVECTION OVEN.
- 4,263,646. MISSED COMMUTATION DETECTOR AND SAFEGUARD ARRANGEMENT.
- 4,265,089. ICE MAKING APPARATUS AND METHOD.
- 4,269,035. DEFROST CONTROL.
- 4,271,861. DISHWASHER FILL LEVEL CONTROL ARRANGEMENT.
- 4,271,899. HEAT PUMP CONTROL SYSTEM.
- 4,207,778. REINFORCED CROSS PLY COMPOSITE FLYWHEEL AND METHOD FOR MAKING SAME.
- 4,244,017. THIRD HARMONIC AUXILIARY COMMUTATED INVERTER HAVING SELECTABLE COMMUTATION CAPACITANCE AS A FUNCTION OF LOAD CURRENT.
- 4,258,302. APPARATUS FOR MAINTAINING SYNCHRONOUS MACHINE DRIVE SYSTEM AT LIGHT OF ZERO MACHINE LOADS.
- 4,275,388. PIEZOELECTRIC AUDIBLE ALARM FREQUENCY SELF-CALIBRATION SYSTEM.
- D-236,902. DESIGN FOR PORTABLE CASSETTE TAPE RECORDER WITH AM/FM RECEIVER.
- D-254,489. CASSETTE TAPE RECORDER OR SIMILAR ARTICLE.
- The RCA Corp. offers to grant non-exclusive licenses on reasonable terms and conditions under the patents listed below. Inquiries respecting licenses under RCA patents should be addressed to RCA Corp., Sr. Vice President, Licensing 30 Rockefeller Plz., New York, N.Y. 10020.
- 4,271,129. HEAT RADIATION DEFLECTORS WITHIN AN EFG CRUCIBLE.
- 4,271,247. COLOR PICTURE TUBE WITH SCREEN HAVING LIGHT ABSORBING AREAS.
- 4,271,377. SYSTEM FOR COMPENSATING FOR CATHODE VARIATIONS IN DISPLAY DEVICES UTILIZING LINE CATHODES.
- 4,271,394. AMPLIFIER CIRCUIT.
- 4,271,422. CMOS SOS WITH NARROW RING SHAPED P SILICON GATE COMMON TO BOTH DEVICES.
- 4,271,433. SAW FILTER PREAMPLIFIER.
- 4,271,489. OPTICAL DISC PLAYER SYSTEM.
- 4,271,532. RECEIVER WITH A CHANNEL SWAPPING APPARATUS.
- 4,272,045. NUTATION DAMPING IN A DUAL-SPIN SPACECRAFT.
- 4,272,083. VIDEO DISC PLAYER HAVING RECORD EXTRACTING MECHANISM.
- 4,272,197. APPARATUS AND METHOD FOR MEASURING THE RATIO OF TWO SIGNALS.
- 4,272,641. TANDEM JUNCTION AMORPHOUS SILICON SOLAR CELLS.
- 4,272,726. DIFFERENTIAL FM DETECTOR WITH SERIES TUNED FILTER.
- 4,272,728. DIFFERENTIAL-INPUT AMPLIFIER CIRCUIT.
- 4,272,743. METHOD FOR TUNING A FILTER CIRCUIT.
- 4,272,777. SERVICE SWITCH APPARATUS.
- 4,272,778. COLOR-DIFFERENCE SIGNAL PROCESSING CIRCUITS.
- 4,272,785. DEFECT COMPENSATION FOR COLOR TELEVISION.
- 4,272,786. VIDEO DISC PLAYBACK APPARATUS WITH NON-LINEAR APERTURE CORRECTION.
- 4,272,881. METHOD FOR MAKING A CLOSED GATE MOS TRANSISTOR WITH SELF-ALIGNED CONTACTS WITH DUAL PASSIVATION LAYER.
- 4,272,882. METHOD OF LAYING OUT AN INTEGRATED CIRCUIT WITH SPECIFIC ALIGNMENT OF THE COLLECTOR CONTACT WITH THE EMITTER REGION.
- 4,273,342. PROTECTIVE CARTRIDGE FOR OPTICAL DISCS.
- 4,273,805. PASSIVATING COMPOSITE FOR A SEMICONDUCTOR DEVICE COMPRISING A SILICON NITRIDE (Si₃N₄) LAYER AND PHOSPHOSILICATE GLASS (PSG) LAYER.
- 4,273,822. GLAZING PASTE FOR BONDING A METAL LAYER TO A CERAMIC SUBSTRATE.

Application for license may be addressed to the General Electric Co., Division Patent Counsel, Housewares and Audio Business Division, 1285 Boston Ave., Bridgeport, Conn. 06602.

- 4,273,828. BULK GLASS HAVING IMPROVED PROPERTIES.
- 4,274,014. SWITCHED CURRENT SOURCE FOR CURRENT LIMITING COMPLEMENTARY SYMMETRY INVERTER.
- 4,276,688. METHOD FOR FORMING BURIED CONTACT COMPLEMENTARY MOS DEVICES.
- 4,277,695. AMPLIFIER HAVING DEAD ZONE OF CONTROLLABLE WIDTH AND POSITION.
- 4,277,729. SIMPLIFIED VERTICAL DEFLECTION CIRCUIT.
- 4,277,793. PHOTODIODE HAVING ENHANCED LONG WAVELENGTH RESPONSE.
- 4,277,796. SLOW DOWN COLOR PROCESSOR FOR VIDEO DISC MASTERING USING A SPECIAL MODE VIR.
- 4,277,798. AUTOMATIC KINESCOPE BIASING SYSTEM WITH INCREASED INTERFERENCE IMMUNITY.
- 4,277,801. COLOR FILTER HAVING VERTICAL COLOR STRIPES WITH A NONINTEGRAL RELATIONSHIP TO CCD PHOTODIODES.
- 4,277,884. METHOD FOR FORMING AN IMPROVED GATE MEMBER UTILIZING SPECIAL MASKING AND OXIDATION TO ELIMINATE PROJECTING POINTS ON SILICON ISLANDS.
- 4,278,508. METHOD OF DETECTING A CATHODIC CORROSION SITE ON A METALLIZED SUBSTRATE.
- 4,278,704. METHOD FOR FORMING AN ELECTRICAL CONTACT TO A SOLAR CELL.
- 4,278,846. VIDEO DISC LOCKED GROOVE CLEARANCE SYSTEM.
- 4,278,946. CURRENT SCALING CIRCUITRY.
- 4,278,977. RANGE DETERMINING SYSTEM.
- 4,278,992. PCM DETECTOR FOR VIDEO REPRODUCER APPARATUS.
- 4,279,073. METHOD FOR RELEASING PRINTED WIRING BOARDS FROM PRINTED WIRING BOARD RACKS.
- 4,279,688. METHOD OF IMPROVING SILICON CRYSTAL PERFECTION IN SILICON ON SAPPHIRE DEVICES.
- 4,280,023. STYLUS POSITION SENSING APPARATUS FOR VIDEO DISC PLAYER.
- 4,280,024. SELECTIVELY DAMPED VIDEO DISC STYLUS ASSEMBLY.
- 4,280,077. CATHODE-RAY TUBE HAVING CORRUGATED SHADOW MASK WITH VARYING WAVEFORM.
- 4,280,191. QUANTIZING CIRCUITS.
- 4,280,674. BALLOON WITH DEFLATION PORT.
- 4,280,941. VIDEO DISCS AND MOLDING COMPOSITIONS THEREFOR.
- 4,281,270. PRECOATED RESISTIVE LENS STRUCTURE FOR ELECTRON GUN AND METHOD OF FABRICATION.
- 4,281,278. REDUNDANT BATTERY PROTECTION SYSTEM.
- 4,281,349. POWER SUPPLY ARRANGEMENT FOR A TUNING SYSTEM.
- 4,281,349. POWER SUPPLY ARRANGEMENT FIELD-EFFECT TRANSISTOR (IGFET) ON A SIGNAL SOURCE.
- 4,281,407. SURFACE ACOUSTIC WAVE PICKUP AND RECORDING DEVICE.
- 4,274,193. METHOD FOR MAKING A CLOSED GATE MOS TRANSISTOR WITH SELF-ALIGNED CONTACTS.
- 4,274,294. APPARATUS FOR CONVERTING ROTARY MOTION TO LINEAR MOTION.
- 4,275,100. VIDEO DISC PROCESSING.
- 4,275,101. VIDEO DISC LUBRICANTS.
- 4,275,282. CENTERING SUPPORT FOR A ROTABLE WAFER SUPPORT SUSCEPTOR.
- 4,275,316. RESETTABLE BISTABLE CIRCUIT.
- 4,275,347. PRECISION CATHODE CURRENT REGULATOR.
- 4,275,362. GAIN CONTROLLED AMPLIFIER USING A PIN DIODE.
- 4,275,366. PHASE SHIFTER.
- 4,275,416. PCM DETECTOR.
- 4,275,861. ORIENTATION OF MOMENTUM STABILIZED VEHICLES.
- 4,276,566. CIRCUIT FOR INHIBITING RADIO FREQUENCY INTERFERENCE IN A TELEVISION RECEIVER.
- 4,276,592. A-C RECTIFIER CIRCUIT FOR POWERING MONOLITHIC INTEGRATED CIRCUITS.

Reference Collections of U.S. Patents Available for Public Use in Patent Depository Libraries

The libraries listed herein, designated as patent depository libraries, receive current issues of U.S. Patents and maintain collections of earlier issued patents. The scope of these collections varies from library to library, ranging from patents of only recent months or years in some libraries to all or most of the patents issued since 1870, or earlier, in other libraries.

These patent collections are open to public use and each of the patent depository libraries, in addition, offers the publications of the patent classification system (e.g. The Manual of Classification, Index to the U.S. Patent Classification, Classification Definitions, etc.) and provides technical staff assistance in their use to aid the public in gaining effective access to information contained in patents. With one exception, as noted in the

table following, the collections are organized in patent number sequence.

Depending upon the library, the patents may be available in microfilm, in bound volumes of paper copies, or in some combination of both. Facilities for making paper copies from either microfilm in reader-printers or from the bound volumes in paper-to-paper copies are generally provided for a fee.

Owing to variations in the scope of patent collections among the patent depository libraries and in their hours of service to the public, anyone contemplating use of the patents at a particular library is advised to contact that library, in advance, about its collection and hours, so as to avert possible inconvenience.

State	Name of Library	Telephone Contact
Alabama	Birmingham Public Library	(205) 254-2555
Arizona	Tempe: Science Library, Arizona State University	(602) 965-7607
California	Los Angeles Public Library	(213) 626-7555 Ext. 273
	Sacramento: California State Library	(916) 322-4572
	Sunnyvale: Patent Information Clearinghouse*	(408) 738-5580
Colorado	Denver Public Library	(303) 573-5152 Ext. 222
Delaware	Newark: University of Delaware	(302) 738-2238
Georgia	Atlanta: Price Gilbert Memorial Library, Georgia Institute of Technology	(404) 894-4519
Illinois	Chicago Public Library	(312) 269-2814
Louisiana	Baton Rouge: Troy H. Middleton Library, Louisiana State University	(504) 388-2570
Massachusetts	Boston Public Library	(617) 536-5400 Ext. 265
Michigan	Detroit Public Library	(313) 833-1450
Minnesota	Minneapolis Public Library & Information Center	(612) 372-6552
Missouri	Kansas City: Linda Hall Library	(816) 363-4600
	St. Louis Public Library	(314) 241-2288 Ext. 214, 215
Nebraska	Lincoln: University of Nebraska-Lincoln, Engineering Library	(402) 472-3411
New Hampshire	Durham: University of New Hampshire Library	(603) 862-1777
New Jersey	Newark Public Library	(201) 733-7814
New York	Albany: New York State Library	(518) 474-5125
	Buffalo and Erie County Public Library	(716) 856-7525 Ext. 267
	New York Public Library (The Research Libraries)	(212) 790-6291
North Carolina	Raleigh: D. H. Hill Library, N.C. State University	(919) 737-3280
Ohio	Cincinnati & Hamilton County, Public Library of	(513) 369-6936
	Cleveland Public Library	(216) 623-2870
	Columbus: Ohio State University Libraries	(614) 422-6286
	Toledo/Lucas County Public Library	(419) 255-7055 Ext. 212
Oklahoma	Stillwater: Oklahoma State University Library	(405) 624-6546
Pennsylvania	Philadelphia: Franklin Institute Library	(215) 448-1321**
	Pittsburgh: Carnegie Library of Pittsburgh	(412) 622-3138
	University Park: Pattee Library, Pennsylvania State University	(814) 865-4861
Rhode Island	Providence Public Library	(401) 521-7722 Ext. 226
Tennessee	Memphis & Shelby County Public Library and Information Center	(901) 528-2957
Texas	Dallas Public Library	(214) 748-9071
	Houston: The Fondren Library, Rice University	(713) 527-8101 Ext. 2587
Washington	Seattle: Engineering Library, University of Washington	(206) 543-0740
Wisconsin	Madison: Kurt F. Wendt Engineering Library, University of Wisconsin	(608) 262-6845
	Milwaukee Public Library	(414) 278-3043

*Collection organized by subject matter.

**Call only between the hours of 10:00 a.m. and 5:00 p.m.

1011 OG 16

PATENT EXAMINING CORPS RENE D. TEGMEYER, Assistant Commissioner WILLIAM FELDMAN, Deputy Assistant Commissioner CONDITION OF PATENT APPLICATIONS AS OF September 5, 1981

PATENT EXAMINING GROUPS	Actual Filing Date of Oldest New Case Awaiting Action
CHEMICAL EXAMINING GROUPS	
GENERAL CHEMISTRY AND PETROLEUM CHEMISTRY, GROUP 110—D. E. TALBERT, Director	5-12-80
Inorganic Compounds; Inorganic Compositions; Organo-Metal and Organo-Metalloid Chemistry; Metallurgy; Metallurgical Apparatus; Metal Stock; Electro Chemistry; Batteries; Hydrocarbons; Mineral Oil Technology; Lubricating Compositions; Gaseous Compositions; Fuel and Igniting Devices.	
GENERAL ORGANIC CHEMISTRY, GROUP 120—C. E. VAN HORN, Director	10-11-79
Heterocyclic Amides; Alkaloids; Azo; Sulfur; Misc. Esters; Carbohydrates; Herbicides; Poisons; Medicines; Cosmetics; Steroids; Oxo and Oxy; Quinones; Acids; Carboxylic Acid Esters; Acid Anhydrides; Acid Halides.	
HIGH POLYMER CHEMISTRY, PLASTICS AND MOLDING, GROUP 140—J. O. THOMAS, JR., Director	7-09-80
Synthetic Resins; Rubber; Proteins; Macromolecular Carbohydrates; Mixed Synthetic Resin Compositions; Synthetic Resins With Natural Polymers and Resins; Reclaiming; Pore-Forming; Compositions (Part) e.g., Coating; Molding; Ink; Prosthetics; Adhesive and Abrading Compositions; Molding, Shaping, Treating Process, and Apparatus Therefor; Irradiation (Part); Bleaching; Dyeing; Leather, Fur and Textile Treating Compositions.	
COATING, LAMINATING AND PHOTOGRAPHY, GROUP 160—S. N. ZAHARNA, Director	1-12-80
Coating; Processes, Apparatus and Misc. Products; Laminating Methods and Apparatus; Stock Materials; Adhesive Bonding; Special Chemical Manufactures; Special Utility Compositions; and Photography.	
SPECIALIZED CHEMICAL INDUSTRIES AND CHEMICAL ENGINEERING, GROUP 170—R. F. WHITE, Director	5-06-80
Fertilizers; Foods; Fermentation; Analytical Chemistry; Reactors; Sugar and Starch; Paper Making; Glass Manufacture; Gas; Heating and Illuminating; Cleaning Processes; Liquid Purification; Distillation; Preserving; Liquid, Gas, and Solid Separation; Gas and Liquid Contact Apparatus; Refrigeration; Concentrative Evaporators; Mineral Oils Apparatus; Misc. Physical Processes.	
ELECTRICAL EXAMINING GROUPS	
INDUSTRIAL ELECTRONICS, PHYSICS AND RELATED ELEMENTS, GROUP 210—S. W. ENGLE, Director	1-07-80
Generation and Utilization; General Applications; Conversion and Distribution; Heating and Related Art Conductors; Switches; Photography; Motion Pictures; Horology; Acoustics; Recorders; Weighing Scales.	
SPECIAL LAWS ADMINISTRATION, GROUP 220—KENNETH L. CAGE, Director	1-18-80
Ordnance, Firearms and Ammunition; Lubrication; Illumination; Nuclear Reactors; Acoustics, Communications, Optics; Radar; Directional Radio; Torpedoes; Seismic Exploring; Cathode Ray Tube Circuitry; Cryptography; Laser Devices; Radioactive Materials; Powder Metallurgy, Rocket Fuels; Special, Fuel, Explosive and Thermic Compositions; Thermal and Photoelectric Batteries.	
INFORMATION TRANSMISSION, STORAGE, AND RETRIEVAL, GROUP 230—VACANT	1-23-80
Communications; Multiplexing Techniques; Television; Facsimile; Data Processing, Computation and Conversion; Storage Devices and Related Arts.	
RECEPTACLES, SANITATION AND CLEANING, WINDING, AND MEASURING, GROUP 240—A. L. SMITH, Director	12-07-79
Receptacles; Bearings; Joint Packing; Conduits; Switches; Presses; Plumbing Fixtures; Textile Spinning; Cleaning; Food Treating; Agitating; Centrifugal Separating; Geometrical Instruments; Sound Recording; Image Projectors; Web Feeding; Winding and Reeling; Cable Hoists; Measuring and Testing; Indicating; Fluent Material Handling.	
ELECTRONIC COMPONENT SYSTEMS AND DEVICES, GROUP 250—S. S. MATTHEWS, Director	4-20-79
Semi-Conductor and Space Discharge Systems and Devices; Electronic Component Circuits; Wave Transmission Lines and Networks; Optics; Radiant Energy; Measuring.	
DESIGN, GROUP 290—KENNETH L. CAGE, Director	2-08-80
Industrial Arts; Household, Personal and Fine Arts.	
MECHANICAL EXAMINING GROUPS	
HANDLING AND TRANSPORTING MEDIA, GROUP 310—B. R. GRAY, Director	1-09-80
Conveyors; Hoists; Elevators; Article Handling Implements; Store Service; Sheet Feeding; Dispensing; Fluid Sprinkling; Fire Extinguishers; Coin Handling; Check Controlled Apparatus; Classifying and Assorting Solids; Boats; Ships; Aeronautics; Motor and Land Vehicles and Appurtenances; Brakes; Railways and Railway Equipment.	
MATERIAL SHAPING, ARTICLE MANUFACTURING, TOOLS, GROUP 320—M. M. NEWMAN, Director	6-12-79
Manufacturing Processes, Assembling, Combined Machines, Special Article Making; Metal Deforming; Sheet Metal and Wire Working; Metal Fusion-Bonding; Metal Founding; Machine Tools for Shaping or Dividing; Work and Tool Holders, Woodworking; Tools; Cutlery; Jacks; Fishing, Etc.; Butchering; and Books and Printed Matter.	
AMUSEMENT, HUSBANDRY, PERSONAL TREATMENT, INFORMATION, GROUP 330—R. E. AEGERTER, Director	1-30-80
Amusement and Exercising Devices; Projectors; Animal and Plant Husbandry; Plants; Harvesting; Earth Working and Excavating; Tobacco; Artificial Body Members; Dentistry; Jewelry; Surgery; Toiletry; Printing; Typewriters; Information Dissemination.	
HEAT, POWER, AND FLUID ENGINEERING, GROUP 340—D. J. STOCKING, Director	10-22-79
Power Plants; Combustion Engines; Fluid Motors; Reaction Motors; Pumps; Rotary Engines and Pumps; Heat Generation and Exchange; Refrigeration; Ventilation; Drying; Temperature and Humidity Regulation; Couplings; Gearing; Fluid Handling and Control; Lubrication.	
GENERAL CONSTRUCTIONS, TEXTILES, MINING AND GEARING, GROUP 350—G. M. FORLENZA, Director	2-19-80
Building Structures; Racks; Cabinets; Closures; Supports; Furniture; Fasteners; Locks; Pipe Couplings; Joints; Miscellaneous Hardware; Textiles; Sewing Machines; Apparel; Footwear; Earth Engineering; Earth Drilling; Mining; Wells; Roads; Bridges; Tool Driving; Gearing; Machine Elements; Clutches.	

Expiration of patents: The patents within the range of numbers indicated below expire during September 1981, except those which may have expired earlier due to shortened terms under the provisions of Public Law 690, 79th Congress, approved August 8, 1946 (60 Stat. 940) and Public Law 619, 83rd Congress, approved August 23, 1954 (68 Stat. 764), or which may have had their terms curtailed by disclaimer under the provisions of 35 U.S.C. 253. Other patents, issued after the dates of the range of numbers indicated below, may have expired before the full term of 17 years for the same reasons, or have lapsed under the provisions of 35 U.S.C. 151.

Patents Numbers 3,146,459 to 3,151,328, inclusive
Plant Patents Numbers 2,444 to 2,448, inclusive

1011 OG 17

REISSUES

OCTOBER 13, 1981

Matter enclosed in heavy brackets [] appears in the original patent but forms no part of this reissue specification; matter printed in italics indicates additions made by reissue.

Re. 30,765

HEAT PUMP SYSTEM


Rudy C. Bussjager, Syracuse, N.Y., assignor to Carrier Corporation, Syracuse, N.Y.

Original No. 4,057,975, dated Nov. 15, 1977, Ser. No. 720,721, Sep. 7, 1976. Application for reissue Nov. 15, 1978, Ser. No. 960,997

Int. Cl.³ F25B 1/00, 13/00; F28F 27/02

U.S. Cl. 62—115

9 Claims



1. In a heat pump system having a compressor, a pair of heat exchangers and means for selectively reversing the flow of refrigerant through the system so that the function of the exchangers is also reversed, the improvement comprising means for separating each exchanger into a plurality of heat transfer zones, each zone containing a number of flow circuits,

flow control means for routing refrigerant discharged from the compressor through each of the zones of one exchanger in a series flow progression and routing the refrigerant discharged from said one exchanger into the other exchanger simultaneously through each of the zones of said other exchanger whereby flow is parallel through the zones, and

switching means operatively associated with said flow control means for automatically reversing the flow geometry through the exchangers in response to reversing the flow of refrigerant through the system whereby refrigerant flow is parallel through said one exchanger and in series through said other exchanger.

3. A heat pump system having a compressor, an indoor coil, an outdoor coil, a reversing valve for delivering refrigerant discharged from the compressor to the indoor coil during heating operations and to the outdoor coil during cooling operations, the method of processing refrigerant through the system including the steps:

separating the indoor and outdoor coils into a plurality of heat transfer zones, each zone having a number of flow circuits passing through the coil associated therewith, routing the refrigerant delivered from the compressor to the outdoor coil during the cooling operation so that refrigerant flows through each of the heat transfer zones in a series progression,

delivering the refrigerant discharged from the outdoor coil to each of the heat transfer zones of the indoor coil simultaneously so that the refrigerant flows through the zones in a parallel flow,

returning the refrigerant from the indoor coil to the compressor to complete the cycle, and reversing the flow geometry through the indoor and outdoor coils in response to a change in the systems operation

whereby refrigerant flow in series through the zones of the indoor coil and in parallel through the zones of the outdoor coil.

Re. 30,766

MODULAR HEAT EXCHANGER WITH PIVOTAL CORES


Erwin J. H. Bentz, Washington, Ill., assignor to Caterpillar Tractor Co., Peoria, Ill.

Original No. 4,076,072, dated Feb. 28, 1978, Ser. No. 620,999, Oct. 9, 1975. Application for reissue May 21, 1980, Ser. No. 152,014

Int. Cl.³ F28G 13/00

U.S. Cl. 165—41

19 Claims



9. An internal combustion engine having a heat exchanger with a top tank and a bottom tank, said top tank being connected to said engine for receiving heated coolant, said bottom tank being connected to said engine for returning cooled coolant to said engine, a plurality of cooling cores extending between said top tank and said bottom tank, means for pivotally mounting each said cooling core at an angle with respect to each other and at an angle to the plane lying perpendicular to the axis of the engine whereby increased cooling core surface is exposed to oncoming air passing through said heat exchanger.

Re. 30,767

METHOD USING LIGNOSULFONATES FOR HIGH-TEMPERATURE PLUGGING

Betty J. Felber; Dwight L. Dauben, and Richard E. Marrs, all of Tulsa, Okla., assignors to Standard Oil Company (Indiana), Chicago, Ill.

Original No. 4,074,757, dated Feb. 21, 1978, Ser. No. 795,341, May 9, 1977. Continuation of Ser. No. 710,963, Aug. 2, 1977, abandoned, which is a continuation-in-part of Ser. No. 592,849, Jul. 3, 1975, abandoned. Application for reissue Oct. 15, 1979, Ser. No. 85,071


Int. Cl.³ E21B 33/138, 43/24

U.S. Cl. 166—261

25 Claims

13. A method for treating an underground zone having a temperature in excess of about 250° F. which comprises: introducing into said zone an aqueous gel-forming solution of a water-soluble lignosulfonate, wherein said solution comprises

at least about 2.5 weight percent reducing sugars based on the weight of said water-soluble lignosulfonate and



maintaining said gel-forming solution in said zone until said gel-forming solution is converted to a gel.

Re. 30,768

VACUUM INSULATED BOTTLE


Carl Bramming, deceased, late of Nashville, Tenn.; by Clara B. Bramming, heir, Plainfield, Ind.; by Kenneth R. Bramming, heir, Nashville, Tenn., and by Beverley B. Wheeler, heir, Plainfield, Ind., assignors to Aladdin Industries, Incorporated, Chicago, Ill.

Original No. 3,910,441, dated Oct. 7, 1975, Ser. No. 446,695, Feb. 28, 1974. Application for reissue Nov. 16, 1976, Ser. No. 742,224

Int. Cl.³ A47J 41/02

U.S. Cl. 215—13 R

14 Claims



12. An insulated bottle for containing foodstuffs or the like comprising an outer case, a liner received within said outer case and spaced therefrom for a major portion of the depth of said liner, said liner having an outer configuration of substantially cylindrical shape and terminating at one end thereof in a constricted neck and defining a cavity adapted to receive foodstuffs or the like, a vacuum filler having a generally cylindrical configuration and an opening at one end thereof interposed between said outer case and the cylindrical portion of said liner, the upper end of said vacuum filler terminating contiguous to the juncture between said liner cylindrical portion and its neck, a body of insulating material received between a portion of said outer case and said neck, said body of insulating material having a configuration conforming generally in shape to said neck and terminating contiguous to the juncture of said neck and said liner cylindrical portion, said body of insulating material being formed with a recess therein for receiving and supporting the upper end of said vacuum filler.

Re. 30,769 MOUNTING ARRANGEMENT FOR IMPACT ROCK-BREAKER


Delwin E. Cobb, Peoria; Jerry D. Fidler, East Peoria, both of Ill.; Nathan Gutman, Simsbury, Conn.; Richard E. Livesay, Peoria, Ill.; Gerald P. Simmons, Washington, Ill., and Orrin A. Stemler, East Peoria, Ill., assignors to Caterpillar Tractor Co., Peoria, Ill.

Original No. 3,915,501, dated Oct. 28, 1975, Ser. No. 526,280, Nov. 22, 1974. Application for reissue Aug. 29, 1979, Ser. No. 70,934

Int. Cl.³ E02F 3/96

U.S. Cl. 299—67

29 Claims



1. Material-fracturing apparatus for mounting adjacent the bucket of an excavator having a boom and a stick, said apparatus comprising:
a housing having a fracturing shank supported by and extending therefrom and means for applying impact blows to said shank for breaking hardened materials;
bracket means extending from and pivotally mounted to said housing for pivotal connection to the stick of [an] the excavator adjacent the bucket of said excavator;
an actuable hydraulic cylinder pivotally connected to said housing and to said bracket means at locations sufficient for controllably, pivotally moving said housing relative to said bracket means for relative angular adjustment about an axis extending at substantially a right angle to the pivotal connection of said housing to said stick;
first latch means for latching said housing means to said bucket for manipulation of said fracturing device into operative position by manipulation of said bucket; and
second latch means for latching said housing to said stick to permit free operation of said bucket.

Re. 30,770

METHOD FOR FABRICATING IMPROVED FIBER REINFORCED PLASTIC RODS HAVING A SMOOTH SURFACE


Samuel M. Shobert, Mishawaka, and Elson B. Fish, Lakeville, both of Ind., assignors to Plas/Steel Products, Inc., Walkerton, Ind.

Original No. 4,154,634, dated May 15, 1979, Ser. No. 835,825, Sep. 22, 1977. Application for reissue Apr. 21, 1980, Ser. No. 142,456

Int. Cl.³ B32B 31/04

U.S. Cl. 156—180

17 Claims



14. The method of fabricating a solidified bundle of fibrous strands in a body of resinous material comprising the steps of:
(a) impregnating all of a plurality of fibrous strands with a liquid heat-hardenable resin,
(b) collecting all of said impregnated strands into a resin wetted bundle and unidirectionally intermittently pulling said bundle

dle through an elongated closed hollow die device thereby providing alternate pulling and dwell, said die device being filled with said bundle during pulling and said bundle being fully impregnated prior to entry into said die device, said intermittent pulling being in substantially equal length increments, said dwell being for substantially equal time increments.

(c) heating said bundle while within said die device to solidify said resin, said pulling, heating and dwell of said bundle being so controlled that
(i) resin in the bundle which emerges from the die device is fully solidified and the resin in the bundle at the point of entry into the die device is not solidified,
(ii) the surface of the emerging bundle corresponds to the polish of the surface of said die device,
(iii) is substantially devoid of imperfections due to resin build-up within said die device, and
(iv) the emerging bundle is devoid of internal fractures.

Re. 30,771

METHOD OF PROTECTING THE HULLS OF MARINE VESSELS FROM FOULING

Klaus Zondek, Cinco de Abril 4534, Santiago, Chile
Reissued No. Re. 29,072, dated Dec. 14, 1976, Ser. No. 611,633, Sep. 9, 1975.

Original No. 3,761,334, dated Sep. 25, 1973, Ser. No. 191,233, Oct. 21, 1971. Application for reissue Jul. 9, 1979, Ser. No. 55,607

Int. Cl.³ E04B 2/00; B31F 1/00; B21D 35/00; B63B 3/00

U.S. Cl. 156—196

13 Claims



1. A method of protecting from marine growth the contoured hull of a marine vessel [from marine growth] having a clean, non-conductive, smooth, hard surface, which comprises providing a metal foil of anti-fouling metal in strip form, coating one face of said foil with a layer of pressure-sensitive adhesive and progressively rolling said coated foil strip into conforming pressure contact directly with said hull surface with successive strips of said foil overlapping and with [a] said layer of pressure sensitive adhesive between said foil strip and the hull surface and between overlapping portions of said foil strips, to adhesively bond said foil throughout its area to the exterior surface of said contoured hull below the water line and to bond adjacent strips of foil to one another, said foil being sufficiently thin to be easily applied and sufficiently thick to provide protection against fouling for a period of from two to five years.

Re. 30,772

AMIDE-MODIFIED URETHANE ACRYLATE RADIATION CURABLE COMPOUNDS AND COATING COMPOSITIONS AND METHODS OF MAKING SAME

Charles B. Friedlander, Glenshaw; Gerald W. Gruber, Wexford, and Rostyslaw Dowbenko, Gibsonia, all of Pa., assignors to PPG Industries, Inc., Pittsburgh, Pa.

Original No. 4,153,776, dated May 8, 1979, Ser. No. 890,895, Mar. 28, 1978. Application for reissue Jun. 2, 1980, Ser. No. 155,711

Int. Cl.³ C08G 18/38

U.S. Cl. 525—421

40 Claims

1. Addition polymerizable compound having [at least] one or two amide [group] groups, at least [one] three urethane [group] groups and at least one [ethylenically unsaturated functional] acrylate or methacrylate group comprising the reaction product of [the] components [of] comprising:
(a) an amide-containing compound [having] which contains

one or two amide groups and at least one NCO-reactive hydroxy functional group;

(b) a polyisocyanate which is a diisocyanate or a triisocyanate; [and]

(c) a polyfunctional compound [containing at least one functional group reactive with an isocyanato group of said polyisocyanate and] which [polyfunctional compound] provides at least one [ethylenically unsaturated functional] acrylate or methacrylate group in said reaction product, said polyfunctional compound being a hydroxy-containing ester of acrylic acid or a hydroxy-containing ester of methacrylic acid; and

(d) polyol selected from the group consisting of polyester polyol and polyether polyol.

Re. 30,773

TRANSACTION TERMINAL


Paul F. Glaser, Culver City, and Richard J. Orford, Hermosa Beach, both of Calif., assignors to Transaction Technology, Inc., Los Angeles, Calif.

Original No. 4,134,537, dated Jan. 16, 1979, Ser. No. 790,764, Apr. 25, 1977. Application for reissue Nov. 5, 1979, Ser. No. 91,509

Int. Cl.³ G06F 15/30; G07F 7/08

U.S. Cl. 235—379

74 Claims



1. A terminal for providing for the performance of transactions by a user on a step by step basis, including, a visual display formed by an electronic display for displaying to the user at specific steps in a transaction instructional text to the user for the performance by the user to advance the transaction on a step by step basis and with this electronic display electronically programmable for modifying the instructional text.

a plurality of function selectors located adjacent the visual display at a position corresponding to the location of particular instructional text on the visual display for selection in the successive steps of individual ones of the function selectors in the plurality to advance the transaction sequentially through the successive steps, the visual display including at particular ones of the steps in transaction instructional text providing for a selection between individual ones of the function selectors in the plurality to advance the transaction to the next steps, means coupled to the function selectors for enabling, at the particular ones of the steps, only the individual ones of the function selectors capable of being selected at such steps, and

means responsive to the selection, from the individual ones of the function selectors at each of the particular steps, of a particular one of such function selectors for providing for the performance of individual transaction in accordance with such selection.

PLANT PATENTS

GRANTED OCTOBER 13, 1981

Illustrations for plant patents are usually in color and therefore it is not practicable to reproduce the drawing.

4,775

GAZANIA PLANT

Paul C. Enright, 11615 Riverside Dr., Lakeside, Calif. 92040

Filed Jul. 28, 1980, Ser. No. 173,183

Int. Cl.³ A01H 5/00

U.S. Cl. Plt.—68

1 Claim

1. A new and distinct variety of Gazania plant substantially as herein described, characterized particularly as to novelty by its unique flower and varying leaf form.

growth habit, dark green, shiny leaves, upright stems each of which carries 7-12 flowers, and by its large blue frilled flowers which are long lasting and non-dropping.

4,776

AFRICAN VIOLET PLANT

Reinhold Holtkamp, Werther Strasse 112, D-4294 Isselburg,

Fed. Rep. of Germany

Filed Jul. 25, 1980, Ser. No. 172,395

Int. Cl.³ A01H 5/00

U.S. Cl. Plt.—69

1 Claim

1. A new and distinct cultivar of African violet known by the cultivar name Texas, as described and illustrated, and particularly characterized by its vigorous and very uniform

4,777

AFRICAN VIOLET PLANT

Reinhold Holtkamp, Werther Strasse 112, D-4294 Isselburg,

Fed. Rep. of Germany

Filed Jul. 25, 1980, Ser. No. 172,396

Int. Cl.³ A01H 5/00

U.S. Cl. Plt.—69

1 Claim

1. A new and distinct cultivar of African violet known by the cultivar name South Carolina, as described and illustrated, and particularly characterized by its vigorous growth habit; intensive green leaves; strong upright flower stems; large star-shaped white flowers, with wavy petal edges, and by its floriferous corolla, which is positioned well above the leaves.

PATENTS

GRANTED OCT. 13, 1981

ERRATA

For CLASS	See PATENT NO.
411-345	4,294,156
411-185	4,294,300
501-129	4,294,618
376-404	4,294,658
376-442	4,294,660
376-363	4,294,661
219-061	4,294,662
361-318	4,294,715
424-049	4,294,894

PATENTS

GRANTED OCTOBER 13, 1981

GENERAL AND MECHANICAL

4,293,957

WET SUIT


Joel D. Melarvie, Box 1977, 304 E. Rosser, Bismarck, N. Dak.
58501

Filed Jan. 25, 1980, Ser. No. 115,355

Int. Cl.³ A62B 17/00

U.S. Cl. 2—2.1 R

12 Claims



1. A wet suit for use under water, or the like, comprising a tight form fitting garment of waterproof material having a slit in at least one portion thereof, said slit being closed by a piece of elastic fabric secured to both edges of the slit and a flap of watertight material secured to one edge of the slit and overlapping the other edge of the slit by a substantial amount, whereby said garment is stretchable in the area of the slit while said flap seals against entry of water.

4,293,958

HEAD GEAR

Christian W. Zauner, 4139 SW. Archer Rd., Gainesville, Fla.
32608

Filed May 27, 1980, Ser. No. 153,048

Int. Cl.³ A61F 9/04

U.S. Cl. 2—12

8 Claims



1. An article of apparel of the type to be worn on the head, said article comprising: support means including at least in part a band means, said band means having a substantially circular configuration and disposable in surrounding relation to a portion of the head of the wearer; visor means attached to said support means and including a pouch means, a substantially flat visor support means mountable on the interior of said pouch means, said pouch means disposed relative to said band means to extend outwardly therefrom when said visor support means is mounted on the interior of said pouch means, whereby said visor means is positioned to offer shade to a predetermined portion of the wearer's head, said pouch means and said band means are formed from a substantially flexible moisture absorbent material, said pouch means being disposed in a folded over relation to itself and in at least partially surrounding relation to a predetermined length of said band means, upon

absence of said visor support means from the interior of said pouch means, said predetermined length substantially equal to the transverse dimension of said visor means, whereby said band means is disposed so as to substantially function as perspiration absorbing band when mounted on the head of a wearer.

4,293,959


STRETCH KNIT BODY SUIT WITH PADDED AREAS
Debbie A. Gioello, 237 Van Cortlandt Park Ave., Yonkers, N.Y.
10705

Filed Dec. 26, 1979, Ser. No. 106,496

Int. Cl.³ A41B 17/02; D06C 14/00; A41H 1/00

U.S. Cl. 2—243 B

2 Claims



1. As a new article of manufacture, a stretch body suit used for the forming of a precision garment pattern corresponding to the figure of a wearer, said suit consisting substantially of knitted material and having a plurality of elongated padded areas on the outer surface thereof, said padded areas being stretchable along the principal axis thereof with said body suit, said padded areas being adapted to receive pins for retaining panels in position upon the suit while worn, while shielding the wearer from penetration of said pins; said padded areas defining a plurality of horizontally disposed lines encircling the wearer at the neck, shoulders, bust, waist, hips, knees, ankles, biceps, elbows and wrists; said padded areas defining a plurality of vertical lines at the armscyes, center front, center back, and sides of the torso, and the inner and outer sides of the arms and legs of said bodysuit.

4,293,960

HEADGEAR

Tore G. Palmaer, S-330, 30 Gnosjö, Sweden

Filed May 22, 1979, Ser. No. 41,540

Claims priority, application Sweden, May 30, 1978, 7806254


Int. Cl.³ A42B 3/02

U.S. Cl. 2—416

7 Claims

1. Protective headgear for mounting within a helmet, comprising an impact-absorbing crash element having means thereon for releasable attachment to cooperable means carried by a helmet shell whereby said crash element is mountable to extend within the helmet shell in spaced relation thereto, said crash element also having means thereon for adjustably and releasably attaching same in spaced superposed relation to a helmet lining; and a helmet lining which comprises a first

curved section adapted to cover the nape of the neck and a second curved section adapted to cover the forehead, said first curved section including a first transverse strip arranged to form side pieces in the lining when assembled and three flaps arranged in sequence along the length of said transverse strip, the two outer ones of the flaps being arranged to be secured to the middle one of the flaps to form a domed configuration



conforming generally to the skull; the helmet lining further comprises a connection piece into which the middle flap continues; and said second curved section including a second transverse strip with three flaps arranged along the length of the strip, the middle one of the flaps being connected with the connection piece, there being attachment element to secure the two other flaps of the second part to its middle flap.

4,293,961

PULSATILE FLOW CARDIOPULMONARY BYPASS PUMP


Thomas M. Runge, 2501 Galewood Pl., Austin, Tex. 78703

Filed Mar. 26, 1980, Ser. No. 134,089

Int. Cl.³ A61F 1/00; A61B 19/00; F04B 43/00

U.S. Cl. 3—1.7

6 Claims



1. A pulsatile flow pumping mechanism particularly adapted to operate a cardiopulmonary bypass device comprising a rotary spinner having a spiral groove including a partial retainer wall and entrance and exit groove portions of increased width and progressively decreasing depth beyond the terminals of the partial retainer wall, power drive means connected with the spinner to rotate it in one direction, a ring follower housing surrounding the spinner and operatively coupled with said bypass device and adapted to traverse the spinner axially of the spinner and being held against rotation with the spinner, a holding magnet on the ring follower housing radially outwardly of the spinner, a magnetically attractable groove rider mounted for movement radially of the spinner within a passage of the ring follower housing which is in alignment with said magnet, camming surface means on the spinner near one end thereof including the exit groove portion of the spinner engageable with said rider to displace the rider radially outwardly into held engagement with said magnet with the rider

radially beyond the periphery of the spinner, and stationary cam means near the opposite end of the spinner and radially outwardly of the periphery of the spinner to strip said rider from the holding magnet and move it into said entrance groove portion.

4,293,962

BONE PLUG INSERTING SYSTEM


Robert L. Fuson, Warsaw, Ind., assignor to Zimmer USA, Inc., Warsaw, Ind.

Filed Feb. 14, 1980, Ser. No. 121,560

Int. Cl.³ A61F 1/00, 1/24

U.S. Cl. 3—1.9

9 Claims



1. A device for plugging the medullary canal comprising the combination of:

- (a) a means for plugging the medullary canal made of a biologically compatible material, and wherein said plugging means has a proximal and a distal end and is round in cross-section and tapered from a larger diameter at the proximal end of the plug to a smaller diameter at the distal end of the plug, and wherein the proximal portion of the plugging means has tooth-like steps in which the diameter decreases in a series of steps, each perpendicular to the length of the plugging means and then tapering back out toward the distal end and approaching the original diameter, but with the outer diameter of each successive step being slightly less in diameter than the previous step as the steps progress from the proximal end toward the distal end of the plugging means, and wherein each step is a continuous ring about the plug, and;
- (b) a means for inserting the plugging means into the canal; and
- (c) a means associated with said plugging means and inserting means for engaging and disengaging the plugging means from the inserting means.

4,293,963

UNRESTRAINED ELBOW PROSTHESIS

Barry L. Gold, and Richard C. Bolesky, both of Warsaw, Ind., assignors to Zimmer USA, Inc., Warsaw, Ind.

Filed Feb. 14, 1980, Ser. No. 121,559

Int. Cl.³ A61F 1/03

U.S. Cl. 3—1.91


4 Claims

1. An unrestrained elbow prosthesis comprised of the combination of:

- (a) a humeral component formed of a bio-compatible metal alloy having an elongated stem with a substantially cylin-

dricul articulating surface on the distal end of said stem and a supporting collar outwardly extending from the stem and located toward the distal end of the stem, but proximal to the substantially cylindrical articulating surface and separated from the cylindrical surface by a neck portion, said substantially cylindrical surface being convex such that the diameter of the midportion of the cylindrical shape is greater than the flat circular ends of the cylindrical shape; and

- (b) an ulnar component consisting of a bio-compatible metal alloy retainer, and a bio-compatible non-metal bearing and an engaging means for attaching said non-metal bearing to the metal retainer and wherein the retainer has an elongated stem and an enlarged metal base portion attached to the proximal end of said elongated stem by a widened base support portion, said stem having a side which spreads into a first rectangular shaped flat plane with a second substantially rectangular plane projecting upward at a 90 degree angle from the first rectangular plane, each of said planes having some thickness so as to create said metal base portion with two parallel retaining walls separated by a retaining platform wherein each retaining wall, as well as the retaining platform, has an L-shaped outer configuration and a C-shaped inner configuration for supporting the non-metal bearing attached by the engaging means to the metal base, said non-metal bearing having a cylindrical



outer bearing surface for mating with the C-shaped retaining platform, an inner concave substantially cylindrical articulating bearing surface, for mating with or receiving the said substantially convex articulating surface of the humeral component, and two parallel side walls between which both of said inner and outer bearing surfaces are disposed, and wherein the engaging means for attaching said non-metal bearing to the metal retainer of the ulnar component includes a first pair of circular ribs and a first pair of circular grooves on the metal base with one circular rib and one circular groove being disposed on the inner side of each of said parallel retaining walls, and wherein the retaining platform is cylindrical and contains a longitudinal protuberance and wherein the engaging means also includes a second pair of circular ribs and a second pair of circular grooves on the non-metal bearing with one circular rib and one circular groove being disposed on the outer surface of each of said parallel side walls, and wherein the outer cylindrical surface of the non-metal bearing contains a longitudinal indentation, and said engaging means is adapted such that the first pair of circular grooves slidably receives the second pair of circular ribs and the second pair of circular grooves slidably receives the first pair of circular ribs whereby engagement of the non-metal bearing into the metal retainer is achieved by circular rotation of the bearing while the pairs of grooves and ribs are engaged, and whereby further forced circular

rotation allows the longitudinal protuberance on the metal retaining platform to engage the corresponding longitudinal indentation on the outer cylindrical surface of the non-metal bearing to engage and subsequently lock the bearing into place on the metal retainer.

4,293,964

DESIGN FOR FLUSH TANK CONTROL USING NON-BUOYANT FLAPPER VALVE



Rudolph T. Riedel, 7198 Sugarbush St., Orlando, Fla. 32807

Filed Sep. 2, 1980, Ser. No. 183,287

Int. Cl.³ E03D 1/34

U.S. Cl. 4—378

1 Claim



1. A flush arrangement for preventing the utilization of an unnecessary amount of water in the flushing of a toilet of the type having a water storage tank and a handle movable to bring about a lifting of a water release device from its seat to accomplish a controlled flushing of the toilet, and water release device being a pivotally mounted non-buoyant, one piece solid rubber flapper valve, said flapper valve including a generally flat member having a sealing portion, an integral generally ball-shaped portion disposed centrally on said seating portion and surrounded thereby, said ball shaped portion being of solid construction utilizing no air pocket to render it buoyant, with a greater proportion of said ball shaped portion being above said flat member than below it, means connecting a portion of said flapper valve to said handle so that handle manipulation brings about a pivotal upward movement of said non-buoyant flapper valve away from its seat, thus permitting a controlled flow of water from said tank, said flapper valve, because of its non-buoyance and weight of said ball-shaped portion returns to its seat the moment said handle is released, such that the flow of water from the tank will be instantly shut off by the substantially flat sealing portion of said flapper valve.

4,293,965

UNITARY FURNITURE ELEMENT

Margaret C. Hrubec, 220 E. 27th St., Apt. 17, New York, N.Y. 10016

Filed Jun. 2, 1980, Ser. No. 155,437


Int. Cl.³ A47C 27/14, 17/04

U.S. Cl. 5—465

6 Claims

1. A unitary furniture element comprising a segmented cushion member of uniform thickness having in plan view a rectangular shape with a length of twice its width, with a center line of the cushion member dividing same into two square portions in plan view, the cushion member being segmented into four isosceles right triangular sections arranged such that the two sections bounding the center line coextensively abut along their corresponding legs and the two sections in each square portion coextensively abut one another along their hypotenuses such that the respective lines of abutment of the sections in the square portions intersect at right angles, the sections

being hingedly joined such that on one rectangular face of the cushion member the two sections bounding the center line are hingedly joined in the plane of the one rectangular face and on the other rectangular face, the two sections in each square



portion are hingedly joined in the plane of the other rectangular face, whereby the segmented cushion member may be pivotally folded at its hinged joints to assume multiple furniture configurations.

4,293,966

LEAFCUTTER BEE LARVAE EXTRACTING METHOD AND DEVICE


LeRoy J. Weiderrich, North Havre, Mont., assignor to Pollination Technics, Inc., Havre, Mont.

Filed Oct. 9, 1979, Ser. No. 82,991

Int. Cl.³ A01K 51/00

U.S. Cl. 6—12 R

19 Claims



1. Apparatus for cleaning a bee hive which includes a spirally wound strip, the surface thereof having bee larvae adhered thereto comprising in combination:
means to unwind said strip,
extractor means operatively associated with said unwinding means for scraping the surface of said strip in a direction transverse to the direction of unwinding of said strip to remove the larvae therefrom, and
control means for operating said extractor means to scrape the surface of an unwound portion of said strip.

4,293,967

PIVOTAL DECK RAMP

Thomas M. Ord, Rte. 1, Box 174 D, Vaughn, Wash. 98394

Filed Apr. 30, 1979, Ser. No. 34,635

Int. Cl.³ B63B 17/00


U.S. Cl. 9—1.6

10 Claims

1. A deck ramp for the disembarking of passengers from boats comprising:
a first ramp section;
a means of attaching the ramp to a boat whereby the first ramp may be pivoted about the means of attachment;
a second ramp section;
a hinge which attaches the second ramp section to the first ramp section wherein when the first ramp section is placed in the closed position, the second ramp section is capable of positioning itself beneath the first ramp section, and when the first ramp section is in the open position, the

second ramp is capable of pivoting as an extension of the first ramp section.

a first rail affixed to the first ramp section;
a hinge affixed to the inner hull of the boat;
a second rail affixed to the hinge; and



a line affixed to the first rail and affixed to the second rail such that when the deck ramp is placed in the open position the line pivots the second rail about the hinge affixed to the boat to an approximate vertical position.

4,293,968

INTERCONNECTED WATER SKIS

Elliott M. Levine, 393 Kingston Crescent, Winnipeg, Manitoba, Canada


Filed Nov. 6, 1978, Ser. No. 958,157

Claims priority, application United Kingdom, Nov. 11, 1977, 47063/77

Int. Cl.³ A63C 5/00, 9/00, 11/00, 15/00

U.S. Cl. 9—310 A

6 Claims



1. A pair of buoyant water ski components or the like and means incorporated thereto connect said components in spaced and parallel relationship with one another to form a platform, and foot engaging means on the upper surface of each of said components, said connecting means including a connector member and means detachably securing said connector member by one end thereof to one of said skis and by the other end thereof to the other of said skis intermediate the ends of said skis, and approximately midway along the length of said skis, said connector member being in the form of a torsion bar whereby said skis are each movable independently in a fore and aft vertical pitching movement, within limits, around the axis of said connector member, due to the torsional characteristics of said connector, the connector means at the ends of said connector member including further means for maintaining the parallelism of said skis and facilitating horizontal plane rigidity of said skis.

4,293,969

INFLATABLE SEAL

Sylvan J. Frommelt, Peosta, Iowa, assignor to Frommelt Industries, Inc., Dubuque, Iowa

Filed Dec. 26, 1979, Ser. No. 107,034


Int. Cl.³ E01D 1/00

U.S. Cl. 14—71.1

12 Claims

10. In an adjustable dockboard for spanning the gap between a loading dock and the bed of a carrier in loading or unloading

position in front of the dock, the dockboard embodying a stationary mounting structure, a ramp having front and rear portions, with the rear portion hingedly connected to said mounting structure so that the ramp can swing up and down around a horizontal axis between a raised position wherein it is disposed at a forwardly opening acute angle to the horizontal above the floor of the loading dock and a lowered position wherein it is disposed in horizontally extending position wherein it is substantially flush with said floor of said loading dock, and said mounting structure including a depression in said loading dock, said depression embodying two oppositely disposed side walls, between which said ramp is disposed when it is disposed in said lowered position, a rear wall and an open front, and wherein the bottom of said ramp comprises a plurality of elongated beams extending between the front and rear edges thereof in substantially parallel spaced relation to each other, the combination of



a. means disposed between said beams at said front portion of said ramp for closing the spaces therebetween,
b. an inflatable member,
c. means securing the top of said inflatable member to the bottom of said beams across substantially the full width of said front portion of said ramp,
d. means securing the bottom of said inflatable member to the bottom of said depression across substantially the full width of said depression between said side walls thereof,
e. said inflatable member being movable upwardly and downwardly by said ramp between said raised and lowered positions of the latter, and
f. means for inflating said inflatable member, when said ramp is disposed in said raised position, to thereby yieldingly urge said inflatable member into sealing engagement with said side walls substantially throughout the height of the latter.

4,293,970

BELT CLEANING APPARATUS

Robert C. Bencene, Rte. 4, Jonesboro, Tenn. 37650, and Charles

A. Granger, #3 Matson Ct., Johnson City, Tenn. 37601


Filed Jun. 28, 1979, Ser. No. 52,852

Int. Cl.³ A46B 13/02

U.S. Cl. 15—21 D

10 Claims

1. A cleaning apparatus for a continuous belt, comprising a base having elongated belt supporting mandrel means rotatably mounted thereon, said mandrel means having a plurality of belt engaging peripheral portions spaced from the rotational axis thereof, drive roll means for said continuous belt rotatably mounted on said base and having its rotational axis substantially parallel to the rotational axis of said mandrel means, belt cleaning means adjacent the periphery of said mandrel means and adapted to engage said belt, and a first one of said periph-



eral portions of said mandrel means being movable substantially parallelly into close juxtaposition to the periphery of said drive roll means upon rotative movement of said mandrel means.

4,293,971

FLOOR TREATING MACHINE WITH SQUEEGEE


Thomas S. Block, Muskegon, Mich., assignor to Clarke-Gravely Corporation, Muskegon, Mich.

Filed Jun. 19, 1979, Ser. No. 49,884

Int. Cl.³ A47L 9/02

U.S. Cl. 15—98

30 Claims



1. A floor treating machine, with a squeegee operably connected thereto for selective engagement or disengagement with the surface being treated, in which the improvement comprises: spring means, capable of flexing spring action in at least a side to side direction laterally of the direction of travel of the machine, secured at one end to said machine and at the other end to said squeegee, said squeegee being free of connection to said machine through a rigid linkage whereby it is free to shift laterally side to side not only relative to said machine but also relative to the normal longitudinal axis of said spring means through said flexing action of said spring means thereby allowing said squeegee to deflect out of the way of obstacles and not get hung up on corners or the like.

4,293,972

HANDLE ATTACHING MEANS FOR BROOMS AND THE LIKE

Francis Pomares, 124 Russell St., White Plains, N.Y. 10606

Filed Oct. 26, 1979, Ser. No. 88,649


Int. Cl.³ A46B 15/00; F16B 35/06

U.S. Cl. 15—145

6 Claims

1. A handle attachment for push brooms and the like having an elongated head with at least two angularly disposed openings positioned transversely of the head comprising tubular handle attaching means having an enlarged handle receiving and holding portion and a shank portion of smaller cross sectional area than and extending from said enlarged portion, the

end of said shank portion having a pair of diametrically disposed and aligned openings, and an elongated bolt extending through said pair of openings, said bolt having a head portion engaging said shank portion to prevent rotation of said bolt and



a cooperating nut, whereby insertion of said shank portion in one of said angularly disposed openings with said bolt extending through said aligned shank openings and the other angularly disposed opening and held in position by said nut secures said handle attaching means in position.

4,293,973

FLOOR CLEANING DEVICE


Ernst Schär, Stallikonstrasse 73, 8903 Birmensdorf, Switzerland

Filed Oct. 22, 1979, Ser. No. 87,105

Int. Cl.³ A47L 11/14

U.S. Cl. 15—230.17

12 Claims



1. A floor cleaning device of the kind having a holding plate from the lower face of which there projects a multiplicity of bristles distributed over the lower face, at least some of which have beaded ends for carrying along a cleaning pad, having the improvement which consists in that:

said holding plate has a number of bores, open at the bottom, in each of which at least one bristle is held which is bent over to provide legs of different length and is secured by means of a loop passing through the bend of each bristle in said bore, said legs diverging outwardly from the bore in which the bristle is secured;

the longer leg of at least one bristle in each bore is beaded at its end, and

a multiplicity of said bristle-equipped bores is distributed over the lower face of the holding plate and both the shorter leg and longer leg of each bristle of said bores projects on the lower face of the holding plate.

4,293,974

ARM TO BLADE CONNECTOR

Neil A. Gowans, Buffalo, and William C. Riester, Williamsville, both of N.Y., assignors to Trico Products Corporation, Buffalo, N.Y.

Filed May 19, 1980, Ser. No. 151,127


Int. Cl.³ B60S 1/40

U.S. Cl. 15—250.32

7 Claims

1. A connector assembly for connecting a windshield wiper

arm and a windshield wiper blade, said arm having a free end U-shaped in cross section, forming depending ears, a slot in each of said depending ears, said slot being open at the free end of said arm tip, said wiper blade having a channel-shaped central portion with depending side walls connected by a web at the upper edge of said side walls, elongate longitudinally extending aperture means extending over a central portion of



said web for receiving said depending ears and a cross pin exposed to said aperture means for receiving said slots; characterized in that a strike is disposed intermediate the side walls exposed to said aperture means, detent means are positioned on said ears disposed for engagement with said strike, said ears include shoulder means positioned to engage an abutting part of said blade for limiting longitudinal movement of the blade relative to the arm when in operative position.

4,293,975

ATTACHMENT FOR WINDSHIELD WIPER BLADES


Bobby J. Ainsworth, P.O. Box 182, Achille, Okla. 74720

Filed Jan. 14, 1980, Ser. No. 111,534

Int. Cl.³ B60S 1/04

U.S. Cl. 15—250.41

4 Claims



1. An attachment for vehicle windshield wiper blades and comprising an elongated body having a slot extending longitudinally along one side thereof for receiving a wiper blade therein, scraper means provided on the opposite side edges of the body and extending longitudinally therealong to provide a scraping of the windshield during operation of the wiper blades, and transversely extending scraper means provided on one end of the body for manual scraping of the windshield for facilitating the scraping action of the longitudinal scraper means, wherein the transverse scraping edge comprises an angularly and outwardly extending flange, and a scraping edge provided at the outer end of the flange extending transversely with respect to the longitudinal axis of the body.

4,293,976

CABINET HINGE

Willi Pittasch, and Johannes Dalbert, both of Herford, Fed. Rep. of Germany, assignors to Firma Richard Heinze, Fed. Rep. of Germany

Division of Ser. No. 844,118, Oct. 20, 1977, Pat. No. 4,159,557.

This application Mar. 8, 1979, Ser. No. 18,456

Claims priority, application Fed. Rep. of Germany, Oct. 22, 1976, 2647776; Oct. 23, 1976, 2648095


Int. Cl.³ E05D 5/02, 7/04

U.S. Cl. 16—129

14 Claims

1. A hinge for articulated connection of two surfaced components, said hinge comprising first and second hinge parts, said first hinge part comprising an outer anchoring sleeve

operable to secure said first hinge part in a recess in a first of said components and an inner body disposed in said sleeve, and said second hinge part comprising means operable to secure said second hinge part to a second of said components and a pivotally mounted hinge arm, one edge of said hinge arm defining a rack, said outer sleeve of said first hinge part having a first opening operable to receive said inner body for selective positioning along a first axis which axis is perpendicular to the



surface of said first components and a second opening operable to permit communication of said hinge arm and said inner body along a second axis which axis is parallel to the surface of said first component, said first hinge part having means operable to position said inner body along said first axis and said inner body having pinion operable to receive and engage said hinge arm for selective positioning along said second axis and means operable to position said hinge arm in said inner body along said second axis.

4,293,977

POULTRY TRUSSING DEVICE


Anthony J. Volk, 173 E. Syracuse St., and Henry J. Volk, P.O. Box 1484, both of Turlock, Calif. 95380

Filed Dec. 3, 1979, Ser. No. 99,470

Int. Cl.³ A22B 5/00; A22C 21/00

U.S. Cl. 17—11

8 Claims



1. An improved poultry trussing device formed of a thin elongated strip of rigid but resilient material having a central U-shaped section having a substantially straight bottom portion with substantially parallel extensions of the ends thereof with aligned shoulders extending therefrom substantially perpendicularly thereto and legs depending from said shoulders with hooked ends.

4,293,978

POULTRY HEAD PULLING APPARATUS

David M. McDonald, Kansas City, Kans., and Donald J. Scheler, Kansas City, Mo., assignors to Simon-Johnson, Inc., Kansas City, Mo.

Filed Oct. 1, 1979, Ser. No. 81,008

Int. Cl.³ A22C 21/00

U.S. Cl. 17—12

2 Claims

1. For use with an arcuate section of an overhead conveyor having means for uninterrupted horizontal advancement of a continuous train of birds pendulously suspended by their legs

in a head down position, apparatus for processing said birds as they are advanced, said apparatus including:


a rotor beneath the conveyor at said section mounted for rotation about an upright axis in timed relationship to said conveyor;

stationary guide means for maintaining the bodies of the birds confined to an arcuate path of travel spaced radially outwardly from said axis;

means attached to said rotor and rotatable therewith for separately capturing the head of each suspended bird as the birds are advanced;

means attached to said rotor and rotatable therewith for separately capturing the necks of each suspended bird as the birds are advanced, and having means for holding the bodies of the birds against descent as the birds are advanced,

each of said head capturing means having means for holding the neck skin of the captured head in a taut condition as the birds are advanced; and



means for progressively and separately lowering said head capturing means with respect to the rotor as the latter rotates until the heads are separated from neck skins adjacent their heads and until the heads pull the trachea, esophagus and crop from within the birds through their necks,

each head capturing means being provided with means for holding the heads oriented to point their beaks inwardly toward said axis,

with means for tilting the heads upwardly and inwardly toward said axis as the head capturing means is lowered during rotation thereof,

with means about which the head is tilted across a line extending transversely of the throat adjacent the larynx for pinching the esophagus against the roof of the mouth and

with an essentially V-shaped loop having a bight, a pair of legs diverging downwardly and outwardly from said bight and a horizontal arm extending outwardly from one of the legs.

4,293,979

FORMING PRESS FOR SAUSAGE AND THE LIKE

Gabriel A. Colosimo, and Ernest Colosimo, both of 9009 W. 2700 South, Magna, Utah 84044

Division of Ser. No. 830,838, Sep. 6, 1977, Pat. No. 4,148,598.

This application Oct. 13, 1978, Ser. No. 951,028


Int. Cl.³ A22C 11/00, 7/00

U.S. Cl. 17—32

2 Claims

1. A food forming press comprising a press body having upper and lower body halves;

means for clamping said body halves together in mating relationship to form a cavity open at each end;
 an inlet opening to the cavity of the press body;
 means for coupling the inlet opening of the press body to a discharge outlet of a meat grinder;
 walls at the inlet opening of the press body angularly interconnecting the inlet opening and the cavity of the press;
 an extrusion die formed to fit within the cavity of the two body halves of the press and containing a plurality of die passages therethrough, each said die passage being open to opposite ends of said cavity, said extrusion die comprising a housing containing a plurality of elongated extrusion passages;



an inwardly converging V-shaped common inlet to the extrusion passages at the inlet opening of the press whereby said inlets of the extrusion passages have sharp, angled edges therearound, the ends of the passages at the opposite end of the extrusion die being formed flush with one another, said housing having a lower surface extending beyond the flush ends, and sidewalls; and
 gradually converging inner surfaces of the said sidewalls of the die extending beyond the flush ends of the extrusion passages to slightly compress foodstuffs ejected from the passages.

4,293,980

METHOD FOR WASHING ANIMAL CASINGS


Roderick O. Ward, Havelock North, New Zealand, assignor to W & R Fletcher (N.Z.) Limited, Wellington, New Zealand
 Filed Jun. 18, 1979, Ser. No. 49,804

Claims priority, application New Zealand, Jun. 30, 1978, 187739

Int. Cl.³ A22B 5/18

U.S. Cl. 17—51

11 Claims



1. A method of mechanically washing an animal casing such as a bung, said method comprising the steps of
 (a) placing the casing on an elongate support element so that said element extends through the interior of the casing, said element including means defining duct means for washing liquid and outlet means for the discharge of such liquid in the interior of the casing,

(b) causing washing liquid to issue under pressure from said outlet means thereby to wash the interior of the casing, and
 (c) directing said washing liquid in the form of jets at an angle to the interior surface of the casing to rotate the casing around said element.

4,293,981

CRAB BUTCHERING MACHINE


Charles M. Smith, Cordova, Ak.

Filed Sep. 24, 1979, Ser. No. 78,036

Int. Cl.³ A22C 29/02

U.S. Cl. 17—71

32 Claims



1. A cleaning machine for crabs having a body, gills, viscera in a body cavity, legs, tail, carapace, and pincers, comprising:
 first endless conveyor means having a plurality of crab body engaging abutments spaced along its length for positively driving crabs along a conveying path in a conveying direction with their eyes facing in the conveying direction and their carapaces facing away from said conveyor means;
 second endless conveyor means having a plurality of rigid projections;
 means for mounting said second conveyor means for movement in a projection path substantially co-planar with said first conveying means so that said projection path intersects the conveying path of said first conveyor means;
 means for driving said second conveyor means so that said abutments and said projections respectively in said conveying path and projection path have their movement timed with respect to each other so that a crab engaged by said abutments and being driven along said conveying path will have its carapace's leading edge struck by one of said projections of said second conveyor means to break said carapace away from the crab body, drive the carapace in a pivoting relationship with respect to the tail end of the carapace backward and away from said conveying path as the crab body moves in the conveying direction.

4,293,982

TOOL FOR OPENING UP FIBER BALE

Herr J. Marx, Monchen-Gladbach, Fed. Rep. of Germany, assignor to Trutzschler GmbH & Co. KG, Monchen-Gladbach, Fed. Rep. of Germany


Filed Mar. 24, 1980, Ser. No. 133,398

Claims priority, application Fed. Rep. of Germany, Apr. 27, 1979, 2917122

Int. Cl.³ D01G 7/06

U.S. Cl. 19—80 A

10 Claims



1. A tool for opening up fiber bales, comprising a shaft adapted to be driven in rotation about an axis; and a plurality

of axially spaced blades coaxially mounted on said shaft for rotation therewith and each having a periphery provided with projecting sawteeth adapted to engage the fiber of a fiber bale, each of said sawteeth being bounded by two flanks which include between themselves an angle of 20°-70° and the circumferential spacing between the tips of successive fronts of said sawteeth being between 60-180 mm.

4,293,983

HIGH SPEED GILL BOX


George S. Van Deusen, and Joseph F. Ogrinc, both of Gastonia, N.C., assignors to The Warner & Swasey Company, Cleveland, Ohio

Filed Sep. 19, 1979, Ser. No. 77,079

Int. Cl.³ D01G 19/10

U.S. Cl. 19—127

11 Claims



1. A high speed gill box having a drafting zone through which textile sliver is drawn comprising:
 a plurality of faller bars each having a plurality of pins extending therefrom and an integral crank arm formed on one end thereof;
 path means for constraining movement of said plurality of faller bars to a defined path along which the faller bars can move;
 a drive sprocket disposed at one end of the drafting zone for engaging some of said plurality of faller bars and pushing others of said plurality of faller bars along the defined path;
 an idler sprocket disposed at the opposite end of the drafting zone for assisting in guiding movement of the faller bars from the drafting zone;
 cam track means for receiving the crank arm of said plurality of faller bars to control orientation of the faller bars as they are pushed along the path;
 a crowder roll disposed to contact said faller bars moving along the defined path to urge them into engagement with said drive sprocket; and, wherein,
 the integral crank arm extends from one end only of each faller bar; and,
 the integral crank arm extends from opposite ends of adjacent faller bars constrained by said path means.

4,293,984

SPRING TENSION FASTENER

John Kaufmann, Jr., 3716 Woodrow Ave., Pittsburgh, Pa. 15227, assignor to John Kaufmann, Jr., Pittsburgh, Pa.

Continuation of Ser. No. 885,512, Mar. 13, 1978, abandoned.

This application Oct. 30, 1979, Ser. No. 89,756


Int. Cl.³ A44B 17/00

U.S. Cl. 24—221 R

1 Claim

1. A spring tension fastener for tightly securing together in face-to-face relationship at least a pair of plate members substantial thickness fixed relative to each other, one of said plate members being formed of spring material and being arched to

form a gap between it and the opposing plate member when the arched plate member of spring material is in a relaxed state, the opposing plate member being substantially flat, both of said plate members being provided with through openings which are elongated and which are in registration with each other, the face of the arched plate member formed of spring material away from the opposing flat plate member being provided with ramp surfaces at diametrically opposed locations and being further provided at diametrically opposed locations between the ramp surfaces with locking recesses, the common axis longitudinally across the locking recesses being at right angles to the major axis of said elongated openings, and a rigid pin fastener element including a straight shank adapted to pass through said registering openings of the plate members and having a turnable head with a rounded interior end face and



wrench flats on one end of the shank of a size unable to pass through said openings and bearing against the face of the flat plate member distant from the arched plate member and also having an elongated fastener head at the other end of the shank extending transversely and equidistantly beyond opposite sides of said shank, the fastener head having a side profile and an end profile approximating the configuration of the elongated openings and being sized to pass therethrough axially of the registering openings, said fastener head having diametrically oppositely disposed flat cam faces on its interior side adapted to rotationally pass over said ramp surfaces and drop into said locking recesses with the fastener head then being arranged across the major axis of said elongated openings, the arched plate member of spring material then exerting tension on said rigid pin fastener element.

4,293,985

METHOD AND APPARATUS FOR MAKING BOUNCE CRIMPED YARN


Philip C. Feffer, Silver Springs, Md., assignor to Chevron Research Company, San Francisco, Calif.

Filed Jan. 7, 1980, Ser. No. 110,050

Int. Cl.³ D02G 1/16

U.S. Cl. 28—254

9 Claims



1. A process for manufacturing a bounce crimped multifilament thermoplastic yarn having improved fiber-fiber coherency which comprises the steps of:

- (a) supplying a drawn multi-filament thermoplastic yarn to an enclosed texturizer chambered bounce crimper comprising a texturizing chamber, a yarn entrance passage, a lateral yarn exit passage, a fluid inlet passage, a fluid exhaust passage axially aligned with said yarn entrance passage and a foraminous surface covering said fluid exhaust passage, and supplying a compressible heated fluid to said texturizing chamber with sufficient force to draw said yarn into said texturizing chamber and hurl it against said foraminous surface with sufficient force to axially compress said yarn and rebound and discharge said yarn from said bounce crimper through said yarn exit and whereby the bulk of said fluid passes through said foraminous surface and said fluid exhaust passage;
- (b) obstructing a portion of said fluid exhaust passage to substantially prevent the occurrence of filament loops and filament entanglement in said discharged crimped yarn; and
- (c) supplying the discharged crimp yarn to a fluid vortex interlacer, without substantially increasing the tension on said crimped yarn, wherein said crimped yarn is fluid interlaced to yield a bounced crimped yarn having improved fiber-fiber coherency.

4,293,986

METHOD OF MAKING A QUARTZ CRYSTAL OSCILLATOR


Masatoshi Kobayashi; George Shimakawa; Yukio Hara, all of Nagano; Hiroyuki Fujii, Suwa, all of Japan, and Kabushiki Kaisha Seikosha, 03, Suwa, both of Japan, assignors to Matsushita Kogyo Kabushiki Kaisha, Toyko

Filed Dec. 5, 1978, Ser. No. 966,688

Claims priority, application Japan, Dec. 5, 1977, 52-145863; Dec. 5, 1977, 52-145864

Int. Cl.³ H01L 41/22

U.S. Cl. 29—25.35



1. A method for manufacturing a quartz crystal oscillator package having a high internal vacuum, said package comprising a quartz crystal vibrator with a frame, a pair of housing elements having peripheral surfaces, said peripheral surfaces being shaped to register one to the other, a hermetic seal at the periphery of said oscillator package, comprising the steps of:

- coating said peripheral surfaces with a metal film;
- coating at least one of said metal films with a gas free material capable of forming an alloy with said metal film, said alloy forming coating being produced on said at least one said metal film at an ambient pressure less than 10^{-2} torr, whereby gas is eliminated from said alloy forming coating during step (b);
- positioning said coated housing elements in an opposed position, said coatings being opposed one to the other, said crystal vibrator with a frame being enclosed within said opposed housing elements;
- drawing a high vacuum over the elements of said quartz crystal oscillator package and within said housing elements;
- applying heat under said high vacuum to fuse said alloy forming coating with said metal film to form an alloy whereby said housing elements are rigidly and hermetically joined together and said package has said high internal vacuum within said joined housing elements.

4,293,987

METHOD OF FABRICATING CAPACITIVE TOUCH SWITCH PANEL


Tom L. Gottbrecht, Plano, and Glen C. Shepherd, Garland, both of Tex., assignors to Texas Instruments Incorporated, Dallas, Tex.

Division of Ser. No. 105,802, Dec. 20, 1979, which is a continuation of Ser. No. 887,387, Mar. 16, 1978. This application Dec. 21, 1979, Ser. No. 106,294

Int. Cl.³ H01G 4/30; H01H 9/26

U.S. Cl. 29—25.42

32 Claims



1. A method of fabricating a capacitive touch switch panel comprising the steps of:

- forming conductive touch pads on one major surface of a rigid dielectric panel;
- forming pairs of spaced-apart conductive pads and conductive leads extending to said conductive pads on one of two opposite major surfaces of a flexible synthetic resin sheet; and
- bonding the second of the said two opposite surfaces of said flexible synthetic resin sheet to the opposite major surface of said rigid dielectric panel with each of said pairs of conductive pads in registered alignment with a respective one of said conductive touch pads.

4,293,988

CONTROLLED DEFLECTION ROLL

Mario Biondetti, Schio, Italy, assignor to Escher Wyss Limited, Zurich, Switzerland

Filed Apr. 28, 1980, Ser. No. 144,772

Claims priority, application Switzerland, May 15, 1979, 4499/79

Int. Cl.³ B21B 13/02


U.S. Cl. 29—116 AD

6 Claims

1. A controlled deflection roll comprising:
- a stationary roll support;
 - a rotatable roll shell;
 - means for mounting said rotatable roll shell for rotation about said stationary roll support;
 - at least one pressure element for supporting the rotatable roll shell upon said stationary roll support;
 - said pressure element being provided with bearing surface means upon which there bears said roll shell, during operation of said controlled deflection roll, with the aid of a liquid film;
 - said roll shell having opposed ends;
 - said means for rotatably mounting said roll shell comprising bearing means arranged at the opposed ends of said roll shell;

seal means for sealing the opposed ends of said roll shell towards the outside;

said roll shell and said stationary roll support forming therebetween an intermediate chamber;



a throttle disk provided with throttle openings arranged at the side of each related one of said bearing means confronting said intermediate chamber between said roll support and said roll shell; and

outflow means for the withdrawal of the liquid arranged between the bearing means and said seal means.

4,293,989

GLUE ROLLER FOR LABELLING MACHINE

Egon Schneider, Neutraubling, Fed. Rep. of Germany, assignor to Hermann Kronseder, Worth, Donau, Fed. Rep. of Germany


Filed Jun. 11, 1979, Ser. No. 47,501

Claims priority, application Fed. Rep. of Germany, Jun. 10, 1978, 282561

Int. Cl.³ B21B 31/08

U.S. Cl. 29—130

9 Claims



1. Glue roller for labeling machines, with a metal hub for rotationally fixed mounting on a drive shaft, a tubelike support body fixed on the hub and with an elastic sleeve, having a cylindrical outer surface, seated on the support body, the hub and the support body being provided with interengaging recesses and projections, characterized in that the support body (6) is formed by a first moulded part of foam material having sealed boundary zones, which is foamed directly onto the hub (1), that the elastic sleeve (11) is formed by a second moulded part of elastic foam material with sealed boundary zones (13), which is foamed directly on the support body (6), that the foam material of the sleeve (11), and that the support body (6) and the elastic sleeve (11) are provided with interengaging projections (10) and recesses (12) which extend parallel to the axis of the roller.

4,293,990

METHOD OF MAKING EMBOSSED ROLL FOR PRODUCING PAPER TOWELS

Stephen F. Pollock, Palatka, Fla., assignor to Hudson Pulp & Paper Corp., New York, N.Y.


Division of Ser. No. 842,161, Oct. 14, 1977, Pat. No. 4,181,068.

This application Oct. 18, 1979, Ser. No. 86,079

Int. Cl.³ B21M 1/14

U.S. Cl. 29—148.4 D

2 Claims



1. The method of producing an embossed roll which includes, the steps of, producing an embossing tool which has a cylindrical surface bearing a continuous spiral pattern of identical embossing designs, rotating an unembossed roll about a first axis at a predetermined peripheral rate, rotating said engraving tool about a second axis which is parallel with said first axis and with said axes being so spaced that said engraving tool mates with the surface of said unembossed roll, and moving said engraving tool axially at a rate relative to said peripheral rate so that it moves the axial dimension of said design patterns during each complete rotation of said unembossed roll whereby a continuous spiral embossing design is produced on said unembossed roll.

4,293,991

APPARATUS FOR ASSEMBLING LADDER-TYPE FRAMES


William Bailey, P.O. Box 73, Acacia Ridge 4110, Qld., Australia

Filed Sep. 17, 1979, Ser. No. 76,086

Int. Cl.³ B23P 11/00

U.S. Cl. 29—243.52

19 Claims



1. Apparatus for assembling frames of the-type having transverse members extending between side members and connected thereto at each end by a compression joint, said apparatus including a main support frame for supporting a pair of connection-forming assemblies, each adapted to co-operate with an end of said transverse member adjacent a respective said side member, each said connection-forming assembly including compressing means located on the outside of said side member and adapted to co-operate with an anvil assembly located on the inside of said side member, said anvil assembly having two co-operating parts provided with complimentary recesses to receive said transverse members, one said part being fixed to a base plate slidably mounted on said support frame for movement in the direction parallel to said transverse members and wherein said compressing means is mounted on

said base plate and movable with respect thereto whereby said anvil assembly and compressing means are movable towards one another and across said support frame to co-operate with the respective said end to form said compression joint.

4,293,992

DIESEL FUEL INJECTOR TOOL


James E. Webb, 13809 Hershe, Houston, Tex. 77015

Filed Sep. 17, 1979, Ser. No. 76,149

Int. Cl.³ B23P 19/04

U.S. Cl. 29—267

1 Claim



1. A tool for removing fuel injectors from diesel engines comprising:

- an elongated member having a first end and a second end;
- an injector engaging member fixedly mounted to a tube adapted for receiving the elongated member, said elongated member being movably mounted inside of the tube;
- said injector engaging member engageable with the injector between a collar formed on the injector and the diesel engine for prying the injector from the diesel engine;
- said first end of the elongated member being engageable with the diesel engine and having a locating means mounted thereon for holding said elongated member in a fixed relationship to the injector;
- a pawl on said tube which engages a recess on said elongated member to move said elongated member relative to the injector engaging member for maintaining contact of the injector engaging member with the fuel injector as the fuel injector is pried loose from the diesel engine.

4,293,993

TOOL FOR REMOVING CASEMENT WINDOW FROM BUILDING

James A. Baker, P.O. Box 71, Dunkirk, Md. 20754

Filed May 16, 1979, Ser. No. 39,379

Int. Cl.³ B26B 27/14

U.S. Cl. 29—278

4 Claims


1. A tool for removing a casement window from the wall of a building, said casement window comprising a first frame containing the glass of said casement window, said first frame being contained in said wall by a second frame embedded in said wall, said tool comprising:

- a first bar for bearing on the exterior vertical portion of the wall and on the vertical portion of the sill of the window adjacent to a selected corner of the window;
- a second bar for bearing on interior portions of said first frame of said selected corner of said casement window, said second bar being shorter than said first bar, and said second bar having bevelled ends for bearing on vertical and horizontal

portions of said first frame adjacent to said selected corner of said window;

a threaded rod connecting said first and second bars for controllably applying a force to pull said first and second bars together to move the corner of said first frame corresponding to said selected corner of said casement window past said embedded second frame towards the exterior of said building;

said first and second bars and said threaded rod comprising means for advancing said threaded rod within a selected one of said first and second bars upon rotation of said threaded



rod, and for preventing the advancement while allowing the rotation of the threaded rod within the other of said first and second bars upon said rotation of said threaded rod, and for allowing at least one of said bars to rotate in a direction towards said threaded rod during said removal of said casement window; and

no-mar means mounted at each said end of said second bar for protecting the interior portions of said wall and sill adjacent to said selected corner of said casement window while said tool operates to move said second frame through said first frame.

4,293,994

SLIDING METHOD AND APPARATUS


George B. Moertel, Conneautville, Pa., assignor to Textron, Inc., Providence, R.I.

Filed Aug. 30, 1979, Ser. No. 70,940

Int. Cl.³ B23P 19/04; B21D 53/50

U.S. Cl. 29—409

11 Claims



1. A method of installing a slider on a pair of slide fastener stringers having respective end sections which are separated, the method comprising the steps of

- positioning a slider on a support having a slider holding mechanism,
- raising a stringer guiding means which has an upper surface and a pair of converging flanges in front of the slider so that the inner surfaces of said converging flanges are aligned with and adjacent to respective inner surfaces of diverging ends of slider flanges;
- placing inner portions of the end slide fastener stringer sec-

tions, including sections of coupling element trains with respective slider flange engaging means of the slide fastener stringers, on the upper surface of the stringer guiding means;

engaging the slider flange engaging means of the end slide fastener stringer sections with the inner surfaces of the respective guiding means flanges;

simultaneously advancing the end slide fastener stringer sections along the guiding means flanges while maintaining engagement of the slider flange engaging means with the respective guiding means flanges to simultaneously insert the end slide fastener stringer sections into the slider and to interlock the trains of coupling elements on such end slide fastener stringer sections by means of the slider, lowering the stringer guiding means, and removing the slider and stringers from the support.

4,293,995

METHOD OF MAKING CAMSHAFT FOR RECIPROCABLE PISTON ENGINES

Friedrich Jordan, Kürten, Fed. Rep. of Germany, assignor to Klöckner-Humboldt-Deutz Aktiengesellschaft, Cologne, Fed. Rep. of Germany


Continuation of Ser. No. 898,818, Apr. 21, 1978, abandoned, which is a continuation of Ser. No. 733,071, Oct. 18, 1975, abandoned. This application Oct. 5, 1979, Ser. No. 82,017

Claims priority, application Fed. Rep. of Germany, Oct. 18, 1975, 2546802

Int. Cl.³ B23P 17/00

U.S. Cl. 29—421 R

2 Claims



1. A method of making a camshaft having cam and bearing ring members on a hollow shaft with the cam ring members laterally offset relative to the axis of the shaft, which includes placing cam and bearing ring members on the tubular shaft, mounting said members on said tubular shaft in dies to preserve their shape, each of said ring members having in the inner wall thereof at least one recess means extending substantially the length of the member, and expanding said tubular member into said ring members and into said recess means to secure said ring members to said shaft with the cam ring members laterally offset relative to the axis of the shaft.

4,293,996

METHOD FOR SECURING A WHEEL TO A ROTATABLE SHAFT

Carl H. Geary, Jr., Greensburg, Pa., assignor to Carrier Corporation, Syracuse, N.Y.

Filed Oct. 27, 1978, Ser. No. 955,428

Int. Cl.³ B23P 11/02


U.S. Cl. 29—446

3 Claims

1. A method of securing a wheel member to a rotatable shaft comprising the steps of:

- positioning the wheel member between a piston member and one end of the shaft, with the piston member extending into a chamber defined by the wheel member;
- passing a plurality of bolts through aligned apertures defined by the piston member and wheel member and into holes defined by the shaft;
- securing a first end of each bolt to the shaft;

attaching a second end of each bolt to the piston member; delivering a pressurized fluid into the chamber defined by the wheel member to move the piston member relative to the wheel member and form a space therebetween; stretching the bolts as a result of the movement of the piston member attached thereto; and



placing a spacing member in the space formed between the wheel member and the piston member to place a compressive force on the wheel member for positively securing the wheel member to the shaft.

4,293,997

METHOD FOR MANUFACTURE OF ARTIFICIAL FLOWERS



Bobby L. Lee, 5, Mok Cheong St., ground floor, block C, Kowloon, Hong Kong

Division of Ser. No. 925,705, Jul. 18, 1978, which is a continuation-in-part of Ser. No. 790,016, Apr. 22, 1977, abandoned. This application Nov. 14, 1979, Ser. No. 94,174

Int. Cl.³ B23P 11/02

U.S. Cl. 29—450

11 Claims



7. A method for making artificial flowers, comprising: molding around a reinforcing wire core, as one single inte-

gral plastic unit, a stem with side petioles and flower calyx and attachment means surrounded by said calyx, securing pre-cut artificial leaves to said petioles, and attaching a preassembled artificial flower to said attachment means.

4,293,998

AUTOMATIC APPARATUS FOR INSERTING ELECTRIC COMPONENTS


Hidetoshi Kawa, Ibaraki; Kazuhiro Mori, Katano; Yoshihiko Misawa, Katano, and Hiroshi Nakagawa, Katano, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Kadoma, Japan

Filed Aug. 30, 1979, Ser. No. 71,378

Claims priority, application Japan, Aug. 31, 1978, 53-107130
Int. Cl.³ H05K 13/04

U.S. Cl. 29—564.1

6 Claims



1. In an automatic apparatus for inserting electric components into a circuit board, the electric components having a plurality of lead wires which are arranged in two rows in approximately the same direction, the improvement comprising a taking-out chuck unit provided with a pair of forming levers for spreading apart the tip ends of said lead wires in two rows and retaining said lead wires, a driving source for moving the taking-out chuck unit from a component taking-out position, an insertion chuck unit for receiving and retaining the electric components from said taking-out chuck unit delivered by the driving source thereby to insert the electric components into said circuit board, and a component feed portion for sequentially feeding said electric components to the components taking-out position of said taking-out chuck unit.

4,293,999

RADIAL LEAD INSERTING MACHINE


Daniel W. Woodman, Jr., Beverly, Mass., assignor to USM Corporation, Farmington, Conn.

Filed Oct. 31, 1978, Ser. No. 956,436

Int. Cl.³ H05K 3/32

U.S. Cl. 29—564.6

19 Claims



1. In a machine for inserting the leads of radial-lead type components into a circuit board, a driver cyclically reciprocable toward and from the board, means for feeding successive

tape-mounted components into registration with the path of the driver, a pusher operable by the driver yieldingly to accommodate different body shapes and sizes of the components and to urge the leads of each component endwise into the board, cooperative fingers movable to grip and guide the leads of each component while it is acted on by the pusher, and cooperative knives for separating each component from the tape and shearing the leads to be inserted by the pusher while they are under the control of the fingers, means for shifting that portion of the tape holding the excess lead portions out of the path of the component to be inserted and the closed fingers guiding its leads; and means to actuate the fingers and knives in sequence in response to movement of the driver.

4,294,000

MACHINE FOR INSERTING ELECTRONIC COMPONENTS

Tetsuo Takahashi; Yoshinobu Taguchi; Kotaro Harigane; Tetsuro Ito, and Akihiro Kato, all of Tokyo, Japan, assignors to Tokyo Denki Kogaku Kogyo Kabushiki Kaisha, Japan


Filed Apr. 27, 1979, Ser. No. 34,014

Claims priority, application Japan, May 2, 1978, 53-53161

Int. Cl.³ H05K 3/32, 13/02

U.S. Cl. 29—564.6

15 Claims



1. In a machine for processing and inserting parallel lead electronic components from an electronic component web carrier into lead receiving openings in a printed circuit board, insert means for receiving an electronic component at a predetermined position and inserting the electronic component into the printed circuit board, said insert means including an insert sub-assembly having

a frame;

first slider means slidably mounted on the frame;

driving means mounted on said frame for driving the first slider means;

second slider means slidably mounted on said frame and cooperating with movement of said first slider means, said second slider means including lead inserting and guiding means for holding and guiding the electronic component and push bar means for displacing the electronic component from the predetermined position to an inserted position under the control of the lead inserting and guiding means;

intermittent drive means;

feed means mounted on said frame and driven by the intermittent drive means for feeding the electronic component web carrier intermittently, pitch by pitch, said feed means including a feed member for receiving and feeding said electronic component web carrier while maintaining electronic components of said electronic component web carrier substantially vertically and a holding member for holding the electronic components in an oblique orientation to the vertical direction;

cutting means for separating one electronic component from

said electronic component web carrier fed by the feed means while the electronic component is being held by said holding member in an oblique orientation; and transfer means including reciprocating means for producing reciprocative movements between the cutting means and said lead inserting and guiding means, and electronic component holding means for holding a lead of the electronic component to be separated by said cutting means while the electronic component is being held by said holding member in an oblique orientation and transferring said electronic component to said lead inserting and guiding means after said electronic component has been separated by said cutting means whereupon the transferred electronic component is situated in a substantially vertical orientation.

4,294,001

METHOD OF MAKING IMPLANT PROGRAMMABLE METAL GATE MOS READ ONLY MEMORY


Chang-Kiang Kuo, Houston, Tex., assignor to Texas Instruments Incorporated, Dallas, Tex.

Filed Jan. 8, 1979, Ser. No. 1,571

Int. Cl.³ H01L 21/425

U.S. Cl. 29—571

10 Claims



1. A method of making a read-only-memory comprising the steps of: forming a plurality of insulated gate field effect transistors in a face of a semiconductor body, each of the transistors having a source, a drain and a polysilicon gate, the transistors being in a regular pattern to provide an array of memory cells; applying a plurality of parallel polysilicon strips each including a plurality of said gates extending along said face with a metal layer over each strip except over the gates so the polysilicon of each gate is not covered by metal; and thereafter programming the array of memory cells by masked ion implant penetrating through the gates of selected ones but not all of the field effect transistors.

4,294,002

MAKING A SHORT-CHANNEL FET

Chakrapani G. Jambotkar, Hopewell Junction, and Paul P. Wang, Kingston, both of N.Y., assignors to International Business Machines Corp., Armonk, N.Y.

Filed May 21, 1979, Ser. No. 41,023

Int. Cl.³ H01L 21/26

U.S. Cl. 29—571

8 Claims


1. A method for forming a field effect transistor which comprises:

(a) ion-implanting an impurity of one conductivity type into two areas on a major face of a second conductivity type substrate of substantially low conductivity to a first depth to form two closed, spaced regions of one conductivity type to function as the source and drain of the field effect transistor;

(b) ion implanting an impurity of the second conductivity type into a third area including at least a portion of the first of said two areas and a portion of the area between the two regions to a second depth which is only a small fraction of the first depth to form a third region of the said second conductivity type adjacent to the first of the said

two regions but spaced from the second of the two said regions to function as the effective channel of the field effect transistor;

(c) forming a gate for the field effect transistor insulated



from the said low conductivity substrate over the third region; and
(d) forming electrical contacts to the said two closed spaced regions and the said gate to provide connections to the field effect transistor.

4,294,003

INSULATED RADIANT HEATING PANEL


Don A. Coverstone, Larwill, Ind., assignor to Lyall Electric, Inc., Albion, Ind.

Filed Dec. 13, 1979, Ser. No. 103,190

Int. Cl.³ H05B 3/00

U.S. Cl. 29—611

9 Claims



1. The method of forming a radiant heating panel comprising the steps of:

selecting a relatively flat metal heat-radiating plate having a first generally planar surface for forming a front surface of the panel;

adhering an electrically insulated sheet heating element to a second generally planar surface of the metal plate opposite the first surface;

embedding the metal plate and adhering heating element in a flowable material to cover the heating element and the plate edges about substantially the entire periphery of the plate while leaving the plate front surface substantially material free; and

solidifying the flowable material to form an electrically and thermally insulating frame for supporting the plate and heating element.

4,294,004

METHOD OF ASSEMBLING A SWITCH AND TERMINAL ASSEMBLY

James P. Frank, Rock Falls, Ill., assignor to General Electric Company, Fort Wayne, Ind.

Division of Ser. No. 671,965, Mar. 30, 1976, Pat. No. 4,095,073.

This application Mar. 6, 1978, Ser. No. 884,097

Int. Cl.³ H01H 11/00; 11/04, 9/12


U.S. Cl. 29—622

31 Claims

1. A method of assembling a switch and terminal assembly having a casing including a pair of casing members, a switch means accommodating chamber within the casing, a plurality of terminals respectively having electrical connector sections, and a ground device having a ground connection section and another section, the method comprising the steps of:

disposing the terminals in one of the casing members with the electrical connection sections of the terminals exposed

beyond the casing and arranged generally in row formation therealong; positioning the other of the casing members with respect to the one casing member and the terminals so as to generally enclose the chamber within the casing and retain the terminals against displacement therefrom; and thereafter disposing the ground connection section of the grounding



device generally in the row formation with the electrical connection sections of the terminals and inserting the another section of the grounding device from exteriorly of the enclosed casing through one of the one and other casing members into releasable gripping engagement with the other of the one and other casing members so as to at least in part oppose the separation thereof and the displacement of the grounding device from the casing.

4,294,005

METHOD OF FORMING CATHODIC ELECTRODE STRUCTURE FOR A SODIUM SULFUR CELL

Michael P. J. Brennan, Helsby, England, assignor to Chloride Silent Power Limited, London, England



Continuation-in-part of Ser. No. 861,924, Dec. 19, 1977, Pat. No. 4,176,447. This application May 23, 1979, Ser. No. 41,380

Claims priority, application United Kingdom, Dec. 20, 1976, 53197/76; Australia, Feb. 6, 1979, 43990/79; India, Feb. 6, 1979, 87/DEL/79; South Africa, Feb. 6, 1979, 79/0504; European Pat. Off., Feb. 13, 1979, 7930214.8; Japan, Feb. 13, 1979, 54-15371; United Kingdom, Feb. 13, 1979, 04968/79

Int. Cl.³ H01M 4/04

U.S. Cl. 29—623.5

5 Claims



1. In the manufacture of a sodium sulphur cell, a method of forming a cathodic electrode structure comprising the steps of forming a compressible block of electronically conductive fibrous material which is chemically resistant to a hot cathodic reactant containing sulphur/polysulphides, the fibres in the block predominantly extending parallel to a given plane in the

block and being randomly oriented in said plane, cutting the block in a plurality of planes normal to said one plane to form at least one sheet in which substantially all of the fibres have a component of direction normal to the plane of the sheet, compressing the sheet in a direction normal to the plane of the sheet in a series of regions defined by parallel strips of the sheet surface to form a series of parallel grooves with sloping sides defining segments of trapezoidal section between the compressed regions with fibres lying normal to the parallel surfaces of the trapezoids between the compressed regions, impregnating the fibrous sheet, either before compression or during compression, with the cathodic reactant at a temperature such that the cathodic reactant is liquid, and cooling the impregnated shape to solidify the reactant.

4,294,006

AUTOMATIC CONTROL FOR WIRE CRIMPING MACHINE


Eugene C. Bair, and Willard C. Hopkins, both of Holland, Mich., assignors to General Electric Company, Fort Wayne, Ind.

Filed Oct. 18, 1979, Ser. No. 86,000

Int. Cl.³ H01R 43/04; B23P 21/00

U.S. Cl. 29—701

17 Claims



1. Automatic control apparatus for wire crimping equipment adapted to make, during a crimp cycle having one or more crimp steps, electrical interconnections with one or more magnet wire segments extending from windings supported on the core of a dynamoelectric machine, the equipment having a crimp height setting mechanism which is substantially infinitely variable over a predetermined range of maximum and minimum height limits, the control apparatus comprising:

first input means for establishing the number of crimp steps to be performed and for generating a signal representative of each step;

second input means for establishing any desired crimp height setting, within said range of maximum and minimum limits, for each crimp step to be performed and for generating a signal representative thereof;

means operative in response to the first and second input means during each crimp step for actuating the crimp height setting mechanism to the setting established for that step;

and crimp actuating means for initiating a crimp operation at each crimp step after the crimp height mechanism has been properly positioned to the corresponding crimp height setting.

4,294,007

METHOD OF MOUNTING THICK FILM HYBRID CIRCUITS IN PRINTED CIRCUIT BOARDS


Paul R. Ellis, Jr., Albuquerque, N. Mex., assignor to GTE Automatic Electric Laboratories, Inc., Northlake, Ill.

Division of Ser. No. 417, Jan. 2, 1979, Pat. No. 4,257,668. This application Dec. 31, 1979, Ser. No. 108,624

Int. Cl.³ H05K 3/36

U.S. Cl. 29—830

7 Claims



1. In a method of fabricating an electrical circuit assembly including a hybrid circuit having flexible terminal leads that depend from a substrate and extend through holes in a mother board and are soldered to conductive traces on the board, the improvement comprising the steps of:

inserting at least a pair of leads into apertures extending through associated fracturable beads that are relatively non-porous for spacing the substrate and portions of the leads above the board during soldering of leads to traces, fracturing the beads following soldering of the board, and removing bead parts from leads so that the leaded substrate may be tilted generally about the line intersection of planes containing surfaces of the substrate and the board.

4,294,008

METHODS OF MANUFACTURING AND SECURING TUBULAR WIRE-RETAINING ANCHORS TO CIRCUIT BOARDS


Frank J. Pollack, Naperville, Ill., assignor to Western Electric Company, Inc., New York, N.Y.

Filed Jun. 27, 1979, Ser. No. 52,655

Int. Cl.³ H05K 3/20

U.S. Cl. 29—831

7 Claims



1. A method of forming discrete circuit wiring on a circuit board including securing a tubular-shaped anchor having an outer wall surface of continuously arcuate profile in the circumferential direction, and adapted to retain an elongated element therewithin, on a circuit board, comprising the steps of:

applying a viscous portion of adhesive on the surface of said circuit board at a desired anchor location, said viscous portion comprising the second part of a two-part adhesive, with the first part being initially applied at least to a portion of the outer arcuate wall surface of said anchor, and being of a type that readily dries as a non-tacky coating at ambient temperature, and which requires no protective covering prior to said anchor being brought into contact with the second part adhesive portion;

positioning said tubular anchor in said second part adhesive portion such that a solidified adhesive bond is formed on opposite sides of the contact juncture between a portion of the arcuate wall surface of said anchor and said circuit board, at which time the second part adhesive portion

rapidly solidifies to form a fillet-shaped bond between said anchor and circuit board; threading a section of at least one elongated element, in the form of a wire, through said anchor so as to secure the threaded section of wire to said circuit board, and connecting opposite ends of said wire to spaced conductive sites on said board.

4,294,009

METHOD OF MANUFACTURING A HYBRID INTEGRATED CIRCUIT

Rene Quintin, Houdan, and Claude M. Villemant, Paris, both of France, assignors to Le Material Telephonique, Boulogne-Billancourt, France


Filed Jun. 28, 1979, Ser. No. 52,932

Claims priority, application France, Jun. 29, 1978, 78 19509

Int. Cl.³ H05K 3/32

U.S. Cl. 29—832

8 Claims



1. A method of manufacturing a hybrid integrated circuit having on a substrate passive components, such as resistors and capacitors deposited in the form of thin or thick films, and active components, such as diodes, transistors and monolithic integrated circuits, connected together by means of an interconnection network, comprising the steps of:

(a) selecting a steel plate of a size corresponding to the circuit to be manufactured;

(b) preparing the surfaces of the steel plate to receive a coat of enamel which can be bonded to and vitrified on steel;

(c) masking selected areas of the plate by the local application of a coat of thermally decomposable or volatilizable material;

(d) coating the surfaces of the plate and mask with an even layer of an enamel composition which can be vitrified on steel;

(e) drying the enamel coating while leaving the masking intact;

(f) removing the dried enamel deposited over the masking;

(g) thermally treating the plate in order to bond the dried enamel coating on the steel, and for volatilizing or burning the masking material on the masked areas, thus forming a dielectric enamel layer, and baring of the masked areas;

(h) forming on selected portions of the bared areas of the plate a solderable and electrically conducting metallic film;

(i) forming passive components and an interconnection network on the continuous layer of dielectric enamel using techniques of depositing inks or pastes followed by baking;

(j) fixing monolithic integrated circuits to the previously metallized areas of the plate, and;

(k) electrically connecting the monolithic circuits to the interconnection network by means of metallic conductors.

4,294,010

ROTATABLE SAFETY RAZOR AND BLADE CARTRIDGE THEREFOR


Evan N. Chen, Fairfield, and Frank A. Ferraro, Trumbull, both of Conn., assignors to Warner-Lambert Company, Morris Plains, N.J.

Filed May 23, 1980, Ser. No. 152,901

Int. Cl.³ B26B 19/14

U.S. Cl. 30—42

19 Claims



1. A rotatable safety razor cartridge comprising: a circular blade supporting member; a plurality of arcuate grooves concentrically formed in said supporting member about a central axis, said grooves forming a plurality of concentric skin-engaging lands; at least one razor blade connected to said supporting member and extending through said plurality of grooves and lands with a cutting edge positioned for engaging the skin of a user; and means for engaging said supporting member with a rotary drive mechanism.

4,294,011

TUBE CUTTER


Wendell J. Kemme, Redlands, Calif., assignor to T/Drill, Inc., Ann Arbor, Mich.

Filed Jun. 18, 1979, Ser. No. 49,398

Int. Cl.³ B23D 21/06; B26B 27/00

U.S. Cl. 30—106

4 Claims



1. A cutter apparatus for cutting tubes a fixed distance outward from a support wall, said cutter apparatus comprising: a cylindrical housing having an open end, an interior cam surface, and a closed end; connecting means located on said closed end of said housing for receipt of drive means for rotating said housing; a hollow tubular coupling having one end slidably mounted within said open end of said housing and the other end having a central bore to closely receive one of said tubes, said coupling being slidably movable between a first position and a second position relative to said housing; an elongated arm pivotally mounted on said coupling within said coupling and said housing; a cutter wheel attached to one end of said arm; a cam follower on said arm engageable with said cam surface such that relative sliding movement between said housing and said coupling pivots said arm; and a removable bushing connected to said coupling to provide the selective attachment of variable length bushings for positioning said cutter wheel a predetermined fixed distance from said support wall.

4,294,012

CHAIN SAW ANTI-PINCH GUARD ARM


Donald D. Lanz, 15702 S. Neibur Rd., Oregon City, Oreg. 97045

Filed Mar. 25, 1980, Ser. No. 133,915

Int. Cl.³ B27B 17/00

U.S. Cl. 30—378

20 Claims



1. In combination with a chain saw having an outwardly projecting blade mounting a saw chain having a working stretch, an antipinch guard attachment comprising: (a) a stiff arm of substantial strength; (b) pivotal mounting means mounting on one end of the arm on the saw adjacent to the base of the blade in a plane substantially parallel to the plane of the blade, the arm thereby being pivotal between an initial angular position wherein it extends divergently to the working stretch of the saw chain and a second angular position wherein it is adjacent and substantially aligned with the working stretch of the saw chain; and (c) elongated handle means attached to the arm for adjustment angularly relative thereto and for pivotal movement therewith.

4,294,013

PORTABLE HACKSAW


Adrian H. Krieg, Woodbridge, Conn., assignor to Widder Corporation, Naugatuck, Conn.

Filed Feb. 25, 1980, Ser. No. 124,448

Int. Cl.³ B27B 11/00

U.S. Cl. 30—392

15 Claims



3. In a hacksaw having a body, a motor and a shaft connected to the motor for reciprocating motion, the combination of a blade connected to the shaft, said blade having a haft with a rear surface, said rear surface being cut away, the cut away portion being defined by a line continuing in the long direction of said blade which line at the terminal end of its travel defines a female recess and a wall generally parallel to and spaced inwardly from the rear surface of said haft, cooperating means on said shaft for abutting said recess and said wall in supporting relationship, and means for securing said blade and shaft together.

4,294,014

APPARATUS FOR DETERMINING THE SHOE SIZE CORRESPONDING TO A FOOT

Dieter Baumann, Leun-Stockhausen, Fed. Rep. of Germany, and Pierre Bidegain, Pau, France, assignors to Bidegain S.A., Pau, France


Filed Mar. 27, 1980, Ser. No. 134,633

Claims priority, application Fed. Rep. of Germany, Mar. 27, 1979, 2912038

Int. Cl.³ A43D 1/02

U.S. Cl. 33—3 C

38 Claims



1. In an apparatus for determining the shoe size corresponding to a foot, said apparatus being of the type having a foot holding device, at least one transmitting unit which radiates spatially bunched signals to a receiving unit opposite the foot holding device, the transmitting unit being subdivided into radiating basic elements and the receiving unit into basic elements responding to the signals, pairs of respective radiating and responding basic elements being in opposed, spaced relationship with basic elements of the same type being arranged side by side in the direction of successive, spaced measuring raster points, the improvement comprising: the extension of said basic elements in the direction of successive measuring raster points being no greater than the spacing of adjacent measuring raster points; and at least within adjacent pairs of basic elements, the two basic elements defining each of said pairs being in one to one correlation with each other regarding the signals to be transmitted.

4,294,015

EXTENSOMETER


Gilbert Drouin, L'Acadie, and Jacques Sibille, Beloeil, both of Canada, assignors to Ecole Polytechnique, Quebec, Canada

Filed Dec. 27, 1979, Ser. No. 107,574

Int. Cl.³ G01B 7/16

U.S. Cl. 33—174 D

9 Claims



1. An extensometer for detecting deformation of a biological elongatable member to be stretched, said extensometer comprising: a support base; a pair of spaced-apart flexible plates; a strain gauge secured to each of said flexible plates for measuring deflection of said flexible plates, from the normal plane of said flexible plates; said flexible plates each further comprising a free end and an

opposed end, said opposed end secured to said support base; said free end further comprising gripping means for engagement in a surface portion of said elongatable member; and clamping means for applying a force perpendicular to said elongatable member positioned opposite said gripping means of said pair of flexible plates to cause said gripping means to positively engage in said surface portion of said elongatable member, said clamping means being secured to said support base for maintaining said support base substantially stationary with respect to said elongatable member such that elongation of said elongatable member is detected by flexion of said flexible plates.

4,294,016

AUTOMOBILE HEIGHT GAUGE


Edward D. Wilkerson, P.O. Box 755 South Ct., Normandy Beach, N.J. 08739

Continuation of Ser. No. 731,061, Oct. 8, 1976, abandoned, which is a continuation of Ser. No. 573,816, May 2, 1975, abandoned. This application Aug. 16, 1977, Ser. No. 825,023

Int. Cl.³ G01B 3/02

U.S. Cl. 33—180 AT

2 Claims



1. In a height gauge for measuring the vertical distance between a vehicle tire support tread and certain selectable parts of a vehicle, and in which the vehicle may be either ground supported or it may be lift supported by a lift which has a pair of separated tire tread engaging supports with each support formed with an upwardly projecting tire guide element, and in which the gauge has an elongated horizontal bar member, a measuring tape cartridge frame mounted for movement along said bar member, coiled tape means in said frame, a magnet carried by the end of said tape means and window means in said frame positioned so that the numerical calibration reads directly the distance from the end of the magnet to the vehicle tire support tread, the improvement comprising a fitting fixed to each end of said bar member and each individually adapted to fit over a guide element or to rest on any vehicle ground support surface, each of said fittings being U-shaped in configuration with at least one leg of the U-shaped fitting being engageable with a vehicle ground support surface or with the tire tread engaging support surface of the lift so that the height gauge measures height from the vehicle tire support tread as a reference and in which the fittings are formed with sufficient clearance so that the bight portion of each does not engage an associated lift tire guide element, and in which both legs of each fitting extend below the elongated horizontal bar member.


4,294,017

ARCHERY SIGHTING DEVICE AND METHODS OF CONSTRUCTING AND UTILIZING SAME

Robert J. Byrnes, 4366 Genesee Rd., and Bruce R. Byrnes, 937 N. Monroe St., Apt. 4, both of Lapeer, Mich. 48446
Continuation-in-part of Ser. No. 935,667, Sep. 19, 1978. This application Mar. 31, 1980, Ser. No. 135,654
Int. Cl.³ F41G 1/46

U.S. Cl. 33—265

5 Claims



1. An archery sighting device comprising:
 - a mounting bracket;
 - first means for affixing said mounting bracket to the midsection of an archery bow;
 - a curved elongated support member directly rigidly affixed along a portion of the length thereof to said mounting bracket such that the curve thereof is concave relative to the archer when said mounting bracket is affixed to said archery bow;
 - said curved support member having a radius of curvature which is substantially proportional to the draw length of the archer;
 - said curved support member being affixed to said mounting bracket such that the lower end of said curved support member extends freely;
 - an optical sight housing member slidably mounted on said curved support member and slidably movable along the length of said curved support member;
 - an optical sight mounted within said optical sight housing member such that the longitudinal axis of said optical sight extends substantially transversely to the longitudinal axis of said curved support member;
 - second means for selectively securing said optical sight housing member at any desired position along the length of said curved support member;
 - third means operatively cooperating with said second means, said curved support member, and said optical sight housing member for defining detent positions of said optical sight housing member at selectively-predetermined locations along the length of said curved support member;
 - said curved support member being provided with a dovetail portion along the length thereof;
 - said optical sight housing member being provided with a dovetail mating portion received by said dovetail portion of said curved support member to permit said housing member to be slidably moved along the length of said curved support member;
 - said second means comprising a locking screw member extending through said optical sight housing member and adapted to secure said optical sight housing at a predetermined position along the length of said curved support member when said locking screw member is rotated to a locked position; and
 - wherein said third means comprises:
 - at least one detent positioning block provided with a detent tooth and adapted to be slidably received within said dovetail portion of said curved support member;
 - fastening means for selectively securing said detent positioning block at any desired fixed position within said dovetail portion of said curved support member;
 - a spring-biased lever operatively disposed within said optical

sight housing member, said lever including a detent projection portion; and
said lever being selectively movable between a first position wherein said detent projection is in locking engagement with said detent tooth of said detent positioning block, and a second position wherein said detent projection is disengaged from said detent tooth of said detent positioning block.


4,294,018

MATERIAL FEED PIPE FOR USE IN BELT-SYSTEM CONTINUOUS VACUUM DRIER

Eitaro Kumazawa, Sayama; Yukihiro Saiki, Oaza-Hidaka, and Yozo Ishioka, Higashi-Kurume, all of Japan, assignors to Snow Brand Milk Products Co., Ltd., Sapporo, Japan
Filed Apr. 9, 1980, Ser. No. 138,812
Claims priority, application Japan, Jul. 25, 1979, 54-94731
Int. Cl.³ F26B 15/10

U.S. Cl. 34—56

2 Claims



1. A material feed pipe for use in a belt-system continuous vacuum drier and oriented above a belt movably mounted within a vacuum drying chamber, comprising: an inner tube member having one end thereof provided with an inlet for material and the other end closed; an outer tube member coaxial with said inner tube and having its two ends closed and encircling said inner tube member and being radially spaced therefrom; a plurality of first nozzle openings provided in an upper part of said inner tube member and oriented at a fixed pitch along the axial length thereof, said first nozzle openings being so devised as to have a larger diameter in regular succession from the inlet end to the opposite end of said inner tube member; and a plurality of second nozzle openings provided in a lower part of said outer tube member and at a fixed pitch along the axial length thereof and having a fixed diameter.


4,294,019

GRAIN DRYING APPARATUS

Vernon H. Seimann, Laurel, Iowa 50141
Filed May 7, 1979, Ser. No. 36,382
Int. Cl.³ F26B 9/02

U.S. Cl. 34—65

16 Claims



1. An apparatus for drying grain comprising,
 - a grain bin having a bottom surface, sidewall and top wall,
 - a perforated cooling floor supported in said bin in spaced relation from said bottom surface to define an ambient air supply chamber between said bottom surface and cooling floor,
 - a perforated drying floor supported in said bin and spaced substantially above said cooling floor to define a cooling

chamber between said cooling floor and drying floor and a drying chamber between said drying floor and top wall, said top wall having an opening for the introduction of grain into said drying chamber and said drying floor having an opening therethrough,
a grain hopper supported below said drying floor in communication with said drying floor opening,
a grain discharge conveyor having one end in communication with said hopper and the other end extended outwardly through said sidewall,
said hopper including a gate means adapted to confine grain within said hopper when closed and adapted to permit grain to fall from the hopper into the cooling chamber when opened,
a sweep auger positioned on said drying floor and operative to traverse said drying floor for conveying grain to said hopper through said drying floor opening,
a grain spreader means positioned below said gate means for distributing grain generally uniformly about said cooling chamber, and
a single power means for operating said sweep auger and said grain spreader means.

with the granular material flowing through the plenum chamber;
a separator barrier positioned between the gas inlet and the diffuser cone;
a plurality of gas passages extending through the separator barrier;
a plurality of heaters, one in each gas passage, for heating gas flowing from the gas inlet through such passages toward the diffuser cone; and
deflection shield means, mounted in the lower portion of the housing, between the heaters and the diffuser cone, for deflecting heated gas along a labyrinthine path from the heaters into the plenum chamber through the diffuser cone, shielding the diffuser cone from the heaters to prevent radiant heat from reaching the diffuser cone and deflecting any fine particles of the granular material that pass through the diffuser cone into the material outlet.

4,294,020


PLENUM DRYING HOPPER WITH INTEGRAL HEATERS

Arthur J. Evans, Northville, Mich., assignor to Whitlock, Inc., Farmington, Mich.

Filed May 9, 1980, Ser. No. 148,517
Int. Cl.³ F26B 17/14

U.S. Cl. 34—168

4 Claims



1. A plenum drying hopper for reducing the moisture content of granular material, comprising:
 - a housing enclosing a plenum chamber and including an upper material inlet for introducing a flow of granular material into the plenum chamber and a lower material outlet for discharging the granular material from the plenum chamber;
 - a perforate diffuser cone, at the bottom of the plenum chamber, for directing the flow of granular material from the plenum chamber into the material outlet, the perforations in the diffuser cone being large enough to permit ready passage of gas therethrough and small enough to preclude passage of all but the finest particles of the granular material;
 - a gas inlet, extending into the housing below the diffuser cone, for introducing dry gas into the plenum chamber through the diffuser cone;
 - a gas outlet, extending from the upper portion of the housing, for discharging gas from the housing after contact


4,294,021

METHOD AND APPARATUS FOR CURING OF ARTICLES

James O. Turnbull; John C. Barker, both of Cowansville, and Arthur J. Knight, Bromont, all of Canada, assignors to J. J. Barker Company Limited, Cowansville, Canada
Filed Apr. 5, 1979, Ser. No. 27,914
Int. Cl.³ F26B 15/12

U.S. Cl. 34—224

6 Claims



1. An apparatus for curing wet resin coated articles comprising:
 - a curing chamber, said chamber having a longitudinal direction between inlet and exit openings, said chamber substantially horizontal and hermetically sealed with the exception of said openings;
 - conveyor means for transporting said articles through said chamber, said conveyor means passing into the inlet opening and out of the exit opening;
 - at least one supply duct extending parallel to the direction of travel of articles on said conveyor;
 - a plurality of distribution members, said distribution members extending transversely with respect to the direction of travel of articles on said conveyor means, said distribution members in fluid communication with said supply ducts, said distribution members including a plurality of jet forming nozzles thereon;
 - vaporous curing agent withdrawal means, associated with said chamber and located between a midpoint of said chamber and said exit opening, for withdrawing a vaporous curing agent from said chamber;
 - said jet forming nozzles when said supply duct is supplied with a vaporous curing agent, providing a jet of vaporous curing agent forming an acute angle to the vertical, said jet having a component towards said withdrawal means, said nozzles in combination with said vaporous curing agent withdrawal means comprising the sole means for inducing a dynamic flow over the articles to be cured towards said withdrawal means and away from said openings; and
 - means for recirculating the vaporous curing agent passing into said withdrawal means through said supply duct.


4,294,022

BOOTS FOR AQUATIC ACTIVITIES

Andre Stockli, 2086 Prieur St., Fernando Castaneda, 7838 Casgrain St., both of Montreal, Quebec, and Jean-Louis Stockli, 3112 Gerard St., Fabreville, Quebec, all of Canada
Continuation of Ser. No. 922,070, Jul. 5, 1978, abandoned. This application Dec. 7, 1979, Ser. No. 101,214
Int. Cl.³ A43B 1/02, 1/10

U.S. Cl. 36—4

9 Claims



1. A boot useful in aquatic activities, particularly in under-water diving, comprising a sock made of a cellular elastomeric material and including an insole and an upper; an outsole assembly consisting substantially of a non-cellular rubber composition covering the insole and the adjacent part of the upper all around the insole, said outsole assembly being vulcanized in situ and adhering to the sock.


4,294,023

ATHLETIC FOOTWEAR FOR NON-CONTACT OR LIGHT CONTACT SPORTS

Samuel E. Banford, 5226 Akron St., Philadelphia, Pa. 19124
Filed Aug. 16, 1979, Ser. No. 67,198
Int. Cl.³ A43B 3/12, 11/00

U.S. Cl. 36—11.5

4 Claims



1. An athletic shoe characterized by members which are in contact with and which reinforce the wearer's foot at points of maximum flexibility only and which athletic shoe is otherwise unrestricting as to the wearer's foot, comprising first means to protect the sole of the wearer's foot from direct contact with a playing surface, said first means comprising a readily yieldable elastic sole portion member extending essentially the entire length and width of the wearer's foot and conforming to the natural configuration of the sole of said foot; second and third means independently attached to said first means, said second means further comprising two generally tabular shaped members configured to restrainedly encompass the wearer around the ankle and remain in close restraining relationship therewith to thereby reinforce and protect the maximum stress points of the wearer's ankle whereby said first and second means acting in conjunction with one another to minimize any shifting of the heel of the wearer relative to said first means while permitting the wearer to move the ankle in a manner which is independent of and unconstrained by said third means, and said third means

further comprising two generally tabular shaped members configured to restrainedly encompass the wearer only above the ball of the foot and remain in close restraining relationship therewith so as to thereby reinforce and protect said ball of the foot whereby said first and third means acting in conjunction with one another permit the wearer's foot to flex across the ball portion thereof in a manner which is independent of and unconstrained by said second means while precluding the foot from shifting forward relative to said first means.


4,294,024

SOLE FOR LOGGING BOOT

Joseph J. Nab, 265 Orange St., Ashland, Oreg. 97520
Filed Sep. 27, 1978, Ser. No. 946,342
Int. Cl.³ A43B 3/00; A43C 15/00

U.S. Cl. 36—113

17 Claims



1. A work boot suitable for use on uneven surfaces comprising:
a boot upper having a lasting margin and including ball-receiving, arch-receiving and heel-receiving portions;
a rigid heel wedge secured beneath the heel-receiving portion of the upper;
an outsole of resilient sheet material, the outsole including:
a. a heel portion secured beneath the heel wedge,
b. a ball portion secured beneath the ball-receiving portion of the upper, and
c. an arch portion secured beneath the arch-receiving portion of the upper; and
a plurality of metal calk means located in each portion of the outsole, a part of each calk means being imbedded in the resilient sheet material;
a number of the calk means located in the ball portion of the outsole being in lateral rows consecutively including:
a. a first row, near the wearer's toes, containing at least one calk means, and
b. multiple, additional rows each containing at least three calk means, the rows being spaced apart a sufficient distance that an uninterrupted, substantially straight, flexible band of the resilient sheet material extends transversely across the entire width of the outsole, substantially parallel to a line through the metatarsal phalangeal joints of the wearer's foot, between the imbedded parts of the calk means of adjacent rows so that the outsole is longitudinally flexible along an axis which is normal to the bands in a region defined by the rows to urge the wearer's foot to move orthopedically correctly.

4,294,025

SOLE ATTACHMENT FOR FACILITATING WALKING

Andre Keller, Virs, Switzerland, assignor to Roll & Go AG, Stansstad, Switzerland

Filed Feb. 19, 1980, Ser. No. 121,993

Int. Cl.³ A43B 5/00


U.S. Cl. 36—132

14 Claims

1. A sole attachment for footwear having a footwear sole

and serving for facilitating walking, especially for use with ski boots, comprising:

a plate member having an upper surface intended to be applied to the sole of the footwear;
means provided for said plate member for forming a lower tread surface domed in the direction of the sole of the footwear;
attachment devices for securing the plate member at the footwear;
said plate member having opposed ends;
said attachment devices comprising a respective holder element provided at each end of the plate member;



each said holder element engaging over the sole of the footwear;

at least one of the holder elements being formed of one-piece with the plate member;
at least one of the holder elements being structured to be elastically movable between an effectual position for securing the plate member to the footwear and out of such effectual position into an ineffectual position; and
said plate member having an upper surface provided with at least one fixation means intended to be introduced into related recess means provided at the sole of the footwear.

4,294,026

ELEVATING EARTH SCRAPER


James A. Welch, Black Canyon City, Ariz., assignor to Sanner Contracting Co., Phoenix, Ariz.

Filed May 15, 1980, Ser. No. 150,153

Int. Cl.³ E02F 1/00, 9/24

U.S. Cl. 37—8

3 Claims



1. In an earth moving machine for removing topsoil and transporting said soil to another location for unloading and distribution, said earth moving machine including,
a frame,
a primary mover for said earth moving machine mounted in said frame,
a bowl pivotally carried by said frame and having two generally vertical parallel side walls and a scraping edge at the mouth of said bowl for removing topsoil from the ground,
elevator means positioned at said mouth of said bowl to

carry said soil from said scraping edge upwardly into said bowl,
ejector floor means movably secured in the bottom of said bowl to upwardly open and release topsoil carried therein,
a pair of ejector floor group members for supporting said ejector floor means, each fixed to and pivotally carried by a respective said bowl wall,
a pair of elevator linkage group members, each adjacent to a respective said bowl wall and interconnecting said elevator means and a respective said ejector floor group member,
the improved elevator linkage group members, said elevator linkage group members being shaped, contoured and dimensioned to generally prevent particles of said soil from lodging between said elevator linkage group members and said respective bowl walls.

4,294,027

LIGHT WEIGHT SNOW THROWER


Merle L. Edwards, Port Washington, Wis., assignor to FMC Corporation, San Jose, Calif.

Filed Feb. 26, 1980, Ser. No. 125,000

Int. Cl.³ E01H 5/00

U.S. Cl. 37—43 R

9 Claims




1. A light weight compact snow thrower having an engine; a transversely extending chute; and a transverse impeller driven by the engine; the improvement which comprises means defining a light weight metal frame for supporting the engine and chute; a lower transversely extending handle bar included in said metal frame; an upper handle bar support included in said frame means and extending upwardly and rearwardly relative to the engine; an upper handle bar having a transverse gripping portion; adjustment means releasably securing said upper handle bar to said handle bar support for height adjustment and also for folding the upper handle bar between an operative position extending rearwardly of said engine and a storage position wherein said transverse gripping portion extends forwardly of said engine; a non-metallic engine housing; said engine housing including a lower cover secured to said frame, an upper cover removably secured to said frame and said lower cover, said lower handle bar having an exposed intermediate gripping portion and having end portions projecting within said upper cover, means defining two access openings in said upper cover adjacent said end portions, connector means for removably connecting said end portions to portions of said metal frame enclosed within said housing, and plug means for closing said two access openings after said lower handle bar has been connected to said frame means for minimizing vandalism to said engine.

4,294,028

SUSPENSION-TYPE FILE FOLDER

Jean R. A. Reymond, Grenoble, France, assignor to Etablissements F. Nicolle & Cie Societe Anonyme, Echirrolle, France
Filed Jan. 9, 1980, Ser. No. 110,800

Claims priority, application France, Jan. 11, 1979, 79 01181
Int. Cl.³ B42F 21/00; A47B 63/00; B42F 15/00
U.S. Cl. 40—359 5 Claims



1. A suspension-file folder comprising:
a pair of leaves hingedly interconnected at their bottoms and formed with a pair of horizontal edges and a pair of vertical edges;
suspension rods formed along the upper edges of said leaves and having laterally projecting formations adapted to suspend the folder from a pair of rails; and
an indicating tab fixed to one of said leaves along one of said edges, said indicating tab being molded in a single piece from a transparent synthetic resin material and comprising:
an elongated tubular portion extending along said one of said edges and adapted to receive an identifying label for said folder,
a plate formed unitarily with said tubular portion and overlying a face of one of said leaves, said plate being provided with at least one opening, and
a pair of arms disposed in said opening and molded unitarily with said plate at one end of each arm while having free ends disposed in said opening and deflectable in planes parallel to said plate, said free ends of said arms being formed with mutually confronting recesses forming a seat for a male member carried by an adjacent folder whereby said arms form a pincer defining a female member for connecting folders together.

4,294,029


PIVOTALLY MOUNTED PHOTO ALBUM PAGE

Sheldon Holson, Wilton, Conn., assignor to The Holson Company, Wilton, Conn.

Filed Jun. 19, 1980, Ser. No. 161,213
Int. Cl.³ B42F 17/00

U.S. Cl. 40—388

2 Claims



1. In a pivotally mounted photo album page of a type including a planar page element having a rectilinear edge, and means for engaging said edge forming a hinged interconnection with a binder, said means including a wire segment lying in the plane of said page element having free ends projecting laterally of said page element, the improvement in said last-mentioned means comprising: a generally planar channel forming element including a body of extruded synthetic resinous material having first and second opposed surfaces and a rectilinear hollow beaded edge defining a cylindrical channel therein, said wire being disposed in said channel to be frictionally retained thereby; and first and second adhesive tape strips, each strip interconnecting a surface of said page element with a surface of the body.


4,294,030

ICE HOLE HEATER

James W. Stewart, 1104 Norton, St. Paul, Minn. 55117
Filed May 1, 1980, Ser. No. 145,427
Int. Cl.³ F23B 3/00

U.S. Cl. 43—4

1 Claim



1. An ice fishing device operable for fishing therethrough comprising:
a cylindrical sleeve having a top and a bottom, said cylindrical sleeve having a pair of ends that overlap each other to define a cylindrical shape having an interior surface and an exterior surface, said cylindrical sleeve made from a resilient material so that radial compression of said cylindrical sleeve produces a force to restore said cylindrical sleeve to its original shape, said cylindrical sleeve having an unobstructed passage therethrough to permit one to pull a fish therethrough without displacing said cylindrical sleeve;
ice gripping members located adjacent but spaced from the bottom of said cylindrical sleeve, said ice gripping members coacting with said cylindrical sleeve to permit a user to position the bottom of said ice fishing device in a hole in the ice; and
a heat chamber attached to exterior surface of said cylindrical sleeve so that when said cylindrical device is positioned in the ice said heat chamber is remotely located from a fishing line to permit heat transfer from said heat chamber to said cylindrical sleeve to prevent freezing of water located in the hole in the ice, said heat chamber also acting as a source of heat for warming a user's hands, said heat chamber being disposed above the ice gripping members and intermediate the ends of the cylindrical sleeve.

4,294,031

HOOK-STRAND CONNECTING

Joseph T. Manno, Star Rte., Kane, Pa. 16735
Continuation-in-part of Ser. No. 933,503, Aug. 14, 1978, Pat. No. 4,209,933. This application Jan. 18, 1980, Ser. No. 113,379
Int. Cl.³ A01K 83/00

U.S. Cl. 43—43.16

10 Claims

1. An integral structure for ready attachment to a strand, said structure consisting essentially of:
a first end forming a hook;
a second end forming a strand receiving portion;
a middle portion between said first and second ends; and
a generally T-shaped projection means formed from said middle portion for friction wrapping of a strand to said structure, said projection means consisting of a cross portion of the T spaced from and generally parallel to said middle portion, and a leg portion of the T interconnecting said cross portion to said middle portion, said leg portion being relatively short compared to the thickness of a

strand to be received thereby so that a strand may be wrapped around said leg portion one or more times and be



tightly frictionally engaged by both said middle portion and said cross portion.

4,294,032


TOY SIMULATED ROCKET PROPELLED AIRCRAFT SYSTEM

Jack L. Breneman, Orchard Park, N.Y., assignor to The Quaker Oats Company, Chicago, Ill.

Filed Jan. 22, 1980, Ser. No. 114,279
Int. Cl.³ A63H 33/00

U.S. Cl. 46—1 R

10 Claims



1. A toy simulated rocket propelled aircraft system comprising in combination:
a mother aircraft having a fuselage and an opening leading therein;
a rocket mounted on the rear end of said mother aircraft for propelling it;
cover means for said fuselage opening movable between open and closed positions;
first mounting means in said fuselage;
second mounting means on said cover means when said cover means are in said closed position; and
a miniature rocket propelled aircraft selectively releasably mountable on said first and second mounting means.

4,294,033

ANIMATED TALKING DOLL

Rouben T. Terzian, Chicago, Ill., assignor to Marvin Glass & Associates, Chicago, Ill.


Filed Feb. 9, 1979, Ser. No. 10,936
Int. Cl.³ A63H 5/00, 11/00, 2/28

U.S. Cl. 46—118

2 Claims

1. An animated talking doll, comprising:
a doll body having a head and a movable mouth defined thereon;
sounding means within the doll body including means responsive to the passage of air for generating an audible sound;
a manually operable air pump within said body communicating with said sounding means;
manually operable means within said body for manipulating

said mouth including a pivotal member and a reducing gear train, said pivotal member operatively connected to said reducing gear train, said gear train including means for converting a single pivotal movement of said member into at least two opening and two closing movements of said mouth; and



- a scissors mechanism operatively connected to open and close said mouth, said scissors mechanism connected to said gear train and including an extension arranged to control the air flow through said sounding means.

4,294,034


ARTICULATED FIGURE TOY

Jorge Magria-Deulofeu, and Jose Magria-Deulofeu, both of 157, Carretera del Medio, Hospitalet Barcelona, Spain
Filed Oct. 11, 1979, Ser. No. 83,962

Claims priority, application Spain, Nov. 21, 1978, 239583
Int. Cl.³ A63H 3/46, 3/20; E05D 1/04

U.S. Cl. 46—161

5 Claims



1. A figure toy comprising:
a body portion having a chamber therein adjacent a wall of said body;
at least one opening through said wall into said chamber, one edge of said opening defining a cylindrical bead a portion of which extends into said chamber;
a simulated limb having an end portion extending through said opening and having a cylindrical recess in one side thereof pivotally embracing said bead; and
the cross sectional size and shape of said end portion of said limb in the region of said recess being substantially the same as the size and shape of said opening, stop means on said limb, in said chamber and on the same side of said limb as said recess arranged to abut the inner surface of said wall and thereby limit pivotal movement of said limb about said bead in one direction in a position substantially perpendicular to said wall.

4,294,035

DEVICE WITH VISUAL AND AUDIO OUTPUT


David I. Klein, Columbia, Md., assignor to George Eng, Rockville, Md., a part interest

Filed Mar. 21, 1980, Ser. No. 131,945

Int. Cl.³ A63H 33/26

U.S. Cl. 46—227

13 Claims



1. An amusement device comprising:
 - (a) integrated circuit means having first and second oscillator circuits contained therein for producing output signals at predetermined first and second frequencies respectively;
 - (b) power means coupled to said integrated circuit means for activating said first and second oscillator circuits;
 - (c) visual output means coupled to an output terminal of said first oscillator circuit for producing visual output responsive to said first frequency;
 - (d) first frequency control means coupled to said first oscillator circuit for modulating said first frequency output of said first oscillator circuit;
 - (e) audio output means coupled to an output terminal of said second oscillator circuit for producing an audio output responsive to said second frequency;
 - (f) second frequency control means coupled to said second oscillator circuit for modulating said second frequency output of said second oscillator circuit;
 - (g) coupling means between said first frequency control means and a reset terminal of said second oscillator circuit for providing a synchronous visual output and audio output; and,
 - (h) an enclosed housing within which said integrated circuit means, said power means, said visual output means, said first and second frequency control means, said audio output means and said coupling means are contained and secured thereto.

4,294,036

FIGURE FOR ARRANGEMENT ON MAGNETICALLY ATTRACTIVE SURFACE

David W. Wion, Glen Waverley, Australia, assignor to Magmate Australia Proprietary Limited, Glen Waverley, Australia

Filed Aug. 20, 1979, Ser. No. 68,001

Claims priority, application Australia, Aug. 24, 1978, PD5647


Int. Cl.³ A63H 33/26

U.S. Cl. 46—242

7 Claims

1. An articulated figure comprising a body component and a plurality of limb components pivotally attached to the body component, characterized in that at least said limb components are formed from flexible magnetic material, the flexibility of said magnetic material being such that the maximum possible surface to surface contact can be achieved between at least said limb components and a flat magnetically attractive surface by virtue of the magnetic attraction between said limb components and said magnetically attractive surface, said limb components therefore being held in any articulated position by said

magnetic attraction, said limb components being attached to freely pivot relative to said body component by means of rivets



passing with clearance through holes in said body component and said limb components.

4,294,037

PRODUCTION OF MYCORRHIZAL FUNGI


Barbara Mosse, Harpenden, England, and John P. Thompson, Toowoomba, Australia, assignors to National Research Development Corporation, England

Filed Feb. 13, 1980, Ser. No. 121,171

Int. Cl.³ A01G 31/00

U.S. Cl. 47—59

23 Claims



1. A process for the production of vesicular-arbuscular (VA) mycorrhizal fungi by growing a VA mycorrhizal fungus on plant roots wherein the invention comprises effecting said growth in nutrient film culture.

4,294,038

SOLAR PANEL WINDOW UNIT

James D. Davidson, 67 Grantour Ct., Pontiac, Mich. 48055

Continuation of Ser. No. 828,437, Aug. 29, 1977, abandoned.

This application May 16, 1979, Ser. No. 39,448


Int. Cl.³ E05C 7/02

U.S. Cl. 49—63

8 Claims

1. For use in combination with a window unit in a wall of a building including a window frame and glass panel means mounted in said window frame, a shutter unit, comprising:
 - first and second parallel extending track means having a spacing therebetween at least equal to the height dimension of said window unit, said track means being located on the inside of said building relative to said window unit and extending parallel to the plane of said glass panel means;
 - laminar insulative shield means mounted in said track means for movement between positions at the side of said win-

dow unit and in front thereof, to block off the entirety of said glass panel means to the inside of said building, said laminar insulative shield means including a frame movably supported on said track means and having an outside facing impermeable heat absorptive surface layer facing said glass panel and an insulation material layer mounted on the inside facing portion of said heat absorptive surface layer remote from said glass panel in said frame, said insulative material having little resistance against breakage when forces are applied in directions perpendicular to the plane thereof, said impermeable surface providing a protective barrier from the outside and a rigidification of



said insulative material against the effects caused by forces applied from the outside in directions perpendicular to the plane thereof;

seal means for effecting a seal around the periphery of said glass panel means and between said window unit and said insulative shield means to define a sealed chamber therebetween when said insulative shield means is in the blocking position; and

openable and closeable passageway means into and out of said sealed chamber defined between said glass panel means and said laminar insulative shield means when in the blocking position to facilitate the flow of fluid through said chamber.

4,294,039

PIVOTAL CONNECTION FOR HOODS AND COVERS IN MOTOR VEHICLES

Walter Dalheimer, and Olaf Kuus, both of Sindelfingen, Fed. Rep. of Germany, assignors to Daimler-Benz Aktiengesellschaft, Stuttgart, Fed. Rep. of Germany


Filed Sep. 6, 1979, Ser. No. 72,912

Claims priority, application Fed. Rep. of Germany, Sep. 21, 1978, 2841092

Int. Cl.³ E05D 15/40

U.S. Cl. 49—248

8 Claims



1. A pivotal connection for hoods or covers of motor vehicles which includes a lever means arranged between a bracket

formed on the vehicle and the hood or cover, and a control means for controlling a positioning of an edge of the hood or cover which is nearest the pivot axis of the pivotal connection, characterized in that a track means is provided for supporting the hood or cover, the lever means includes a support arm having a first end rotatably mounted on the bracket and a second end connected with the track means, a two-armed guide lever means is pivotally mounted on the support arm and has a first arm a free end thereof which is pivotally connected to the track means, and a link means having a first end pivotally connected to the support arm and a second end pivotally connected to the track means at a position spaced from the pivotal connection of the first arm with the track means, the first arm, the track means, the link means, and a section of the support arm located between the first arm and the link means forming a four-bar linkage, and in that the control means includes a lever having a first end pivotally mounted at a free end of a second arm of the guide lever means and a second end pivotally connected to the bracket whereby, upon an opening of the hood or cover, the four-bar linkage undergoes a reversal such that an edge of the hood or cover nearest the pivot axis of the pivotal connection is first raised upwardly.

4,294,040

SAFETY DOOR FOR BUILDINGS AND ROOMS

Bianca M. Crotti, Via Archirola, 125, Modena, Italy


Filed Oct. 1, 1979, Ser. No. 80,921

Claims priority, application Italy, Sep. 29, 1978, 40125 A/78

Int. Cl.³ E05D 15/58

U.S. Cl. 49—254

13 Claims



1. A safety door assembly for buildings and rooms in general, the assembly comprising fixed works (1); a door including two main transversely sliding parts (3, 4), one of said parts being a supporting column (3) of given width and the other of said parts being a door body (4) which is much wider than said given width of said column; hinge means (5) between a first edge of said column and a first edge of said door body for supporting said door body for movement about an axis defined by said hinge means; a first recess (17) in said fixed works along a side thereof into which said supporting column substantially disappears during opening, said hinge means remaining outside said first recess during opening; a second recess (37) in said fixed works opposite said first recess; lock means including operating means installed in said door body in vicinity of an edge thereof opposite said hinge means, said lock means substantially disappearing into said second recess during closing; respective openings (11, 12) on opposite side of said fixed works opening into said second recess for allowing access to said operating means of said lock means from inside and outside when said door body is in said second recess while preventing access to said lock means; respective grooves (9) along

upper and lower edges of said supporting column (3); respective fixed guide (6, 7) adjacent said grooves (9); and rolling, or sliding means (8) received in said grooves and movable therein.


4,294,041

MOBILE MACHINES FOR REMOVING SURFACE IRREGULARITIES FROM RAIL HEADS

Josef Theurer, and Klaus Riessberger, both of Vienna, Austria, assignors to Franz Plasser Bahnbaumaschinen-Industriegesellschaft m.b.H., Vienna, Austria
Division of Ser. No. 968,264, Dec. 11, 1978. This application Jun. 2, 1980, Ser. No. 155,559
Claims priority, application Austria, Dec. 30, 1977, 9451/77
Int. Cl.³ E01B 31/12

U.S. Cl. 51-5 C

4 Claims



1. A mobile machine mounted on a track for advancement therealong, the track having two rails including heads, for removing irregularities from the surfaces of the rail heads to a predetermined depth, which comprises

- (a) a machine frame,
- (b) a tool carrier rigidly resistant to bending and vertically adjustably mounted on the machine frame and arranged thereon for vertical and lateral guidance without play along a respective one of the track rails,
- (c) a cutter head on the tool carrier, the cutter head having
 - (1) a cutting tool capable of machining the surface of the head of the respective track rail continuously upon advance of the tool carrier along the track rail,
- (d) a hydraulic jack unit linking the tool carrier to the machine frame for vertically adjusting the tool carrier and subjecting the tool carrier to a vertically directed loading force sufficient to obtain the predetermined machining depth,
- (e) an additional tool carrier and a rail grinding tool on the additional tool carrier, and
- (f) drive means for imparting to the additional tool carrier a working movement in the direction of the track additional to that simultaneously imparted to it by the advancement of the machine.

4,294,042

APPARATUS AND METHOD FOR GRINDING A HELICAL SURFACE ON A FLAT BLADE


Robert W. Davenport, Golden; Eugene L. Moore, Lakewood, and Ronald L. Goodman, Woodland Park, all of Colo., assignors to Johns-Manville Corporation, Denver, Colo.
Filed Sep. 5, 1979, Ser. No. 72,740
Int. Cl.³ B24B 3/40, 3/42

U.S. Cl. 51-54

22 Claims

1. Apparatus for grinding a helical cutting surface on a flat cutting blade, comprising:
- a stationary support,
 - an arbor for mounting said blade, said arbor being rotatably mounted on said support about an axis of rotation, said arbor having at least two mutually perpendicular planar surfaces which are disposed oblique to said axis of rotation;
 - means for mounting said blade on one of said planar surfaces, an adjustable cam plate mounted on the other of said planar surfaces,
 - means for adjusting all points along the lower surface of said cam plate such that said lower surface is equidistant from said axis of rotation,
 - a carriage mounted on said support for reciprocation along a plane parallel to said axis of rotation,
 - a cam follower for contacting said lower surface,

means for mounting said cam follower on said carriage, means for grinding said blade, and means for mounting said grinding means on said carriage such that said grinding means may be reciprocated along a plane parallel to said axis of rotation,



whereby when said carriage and said grinding means are reciprocated, said cam follower contacts the lower surface of said cam plate, said arbor is oscillated about its axis of rotation and a helical cutting surface is ground into said blade.

4,294,043


ICE SKATE SHARPENER

Glenn Sakcriska, 1714 Abbott, Ann Arbor, Mich. 48103
Division of Ser. No. 869,696, Jan. 16, 1978, Pat. No. 4,172,343, which is a continuation-in-part of Ser. No. 745,362, Nov. 26, 1976, Pat. No. 4,069,620. This application Aug. 27, 1979, Ser. No. 70,408

Int. Cl.³ B24B 9/04

U.S. Cl. 51-100 R

11 Claims



1. In a scale for use in conjunction with ice skate blade sharpening and contouring, there being an equivalent center location on the ice skate blade to be sharpened and contoured, the improvement characterized by,
- a generally oblong scale for determining the equivalent center location on the ice skate blade comprising,
 - a zero mark on the scale to be placed adjacent the front of the blade, a first set of separately identifiable marks on the scale for identifying the length of a particular blade, a second set of separately identifiable marks on the scale indicating said equivalent center locations, each mark of the second set paired to a mark in the first set and located from the mark in the first set a specified percentage of the distance between the mark in the first set and the zero mark.


4,294,044

TRACKING MECHANISM FOR A BELT TYPE SANDER

John M. Hansen, Dover Township, Racine County, Wis., assignor to Emerson Electric Co., St. Louis, Mo.
Filed Jun. 2, 1980, Ser. No. 155,284
Int. Cl.³ B24B 21/18

U.S. Cl. 51-135 BT

5 Claims



1. In a belt sanding machine having a frame, drive and idler pulleys mounted for rotation in spaced relationship on said frame and an endless sanding belt extending over said pulleys, an arm having one end pivotally mounted on said frame and carrying an idler drum mounted for rotation on the other end thereof, said arm being tiltable about a longitudinal center line extending through its axis of rotation and the axis of rotation of said idler drum and having a normal position in which the axis of rotation of said idler drum is parallel with the axis of said pulleys, said idler drum being arranged to engage and tension said sanding belt at points between said pulleys when said arm is swung to either of two angularly spaced positions, belt tracking means for adjustably tilting the axis of rotation of said idler drum from its normal position comprising spring means acting to tilt said arm in one direction from its normal position and separate screw threaded means on said frame positioned so as to engage said arm and to adjustably oppose the tilting of said arm in said one direction when said arm is in either of its said two positions.


4,294,045

GRINDING MACHINE WITH A SIZING DEVICE
Minoru Enomoto, Ohbu; Takao Yoneda, Toyoake, and Yoshiyuki Takeuchi, Gamagouri, all of Japan, assignors to Toyoda Koki Kabushiki Kaisha, Kariya, Japan
Filed Jan. 23, 1980, Ser. No. 114,646

Claims priority, application Japan, Jan. 30, 1979, 54-9502
Int. Cl.³ B24B 49/02

U.S. Cl. 51-165.71

6 Claims



1. A grinding machine for simultaneously grinding with a grinding wheel a cylindrical surface and a shoulder side surface perpendicular thereto of a workpiece, comprising:

a bed;
work support means slidable on said bed, for carrying said workpiece for rotation about an axis extending in the sliding direction of said work support means;
a wheel support carrying said grinding wheel and slidable on said bed for movement along a straight path extending at an acute angle to the rotational axis of said workpiece;
first and second feed means connected to said work support means and said wheel support for moving the same on said bed, respectively;
a sizing device having feeler means engageable with said cylindrical surface of said workpiece for measuring the diameter of said cylindrical surface;
guide means for slidably guiding said sizing device in a direction parallel to the rotational axis of said workpiece;
third feed means connected to said sizing device for moving the same along said guide means; and
a positioning controller connected to said third feed means for controlling the same and including
first calculation circuit means responsive to first input data indicative of a desired finish diameter of said cylindrical surface for calculating a cotangent component at said acute angle of said desired finish diameter,
second calculation circuit means responsive to said first calculation circuit means and second input data indicative of a first distance spaced from said shoulder side surface for adding said cotangent component and said second input data to thereby obtain command data indicative of a second distance from an intersection at which the rotational axis of said workpiece intersects a line extending through the juncture between first and second surfaces of said grinding wheel in parallel relation with said straight path, said first and second surfaces of said grinding wheel corresponding, respectively, to said cylindrical and shoulder side surfaces of said workpiece, and
control means responsive to said second calculation circuit means for controlling said third feed means to position said feeler means at a position which is spaced said second distance from said intersection.


4,294,046

TRAVELING TOOL CARRIER FOR SEVERING RAILWAY SPIKES

Luigi Damiano, 135 Farm St., Providence, R.I. 02908
Filed Mar. 26, 1980, Ser. No. 133,976
Int. Cl.³ B24B 23/00

U.S. Cl. 51-170 R

10 Claims



1. A traveling tool carrier for severing heads of railway spikes prior to removal or replacement of railway rails, comprising a platform having front and rear wheels mounted on the underside thereof for rolling engagement with said rails, a support mounted on said platform, a vertical adjustment assembly mounted on said support, a horizontal adjustment assembly secured to said vertical adjustment assembly for vertical movement thereof, a saw support assembly mounted on said horizontal adjustment assembly for movement thereof, a rotating saw suspended from said saw support assembly and disposed such that the plane thereof is inclined to the vertical,

wherein said saw is angularly engageable with said spike heads upon traveling movement of said platform, means mounted on said vertical and horizontal assemblies for vertically and horizontally adjusting said saw support assembly and the saw suspended therefrom in the angular operative position thereof, and means mounted on said platform for rotating said saw for severing the heads of said spikes as said platform is moved over said rails.

4,294,047


METHOD OF SHARPENING LATERAL EDGES AND END EDGES OF A BLADE DURING RECIPROCATATION THEREOF

David R. Pearl, West Hartford, Conn., assignor to Gerber Garment Technology, Inc., South Windsor, Conn.

Filed Jan. 14, 1980, Ser. No. 111,527

Int. Cl.³ B24B 1/00, 3/36

U.S. Cl. 51—327



1. A method for sharpening the cutting edges of a reciprocating blade on a sheet material cutting apparatus, the blade being supported for generally vertical reciprocating movement relative to a generally horizontal sheet material supporting surface and having a generally vertically extending leading cutting edge and a lower cutting edge intersecting the leading cutting edge and extending downwardly therefrom and in the direction of the blade trailing edge, the apparatus having a cutting region proximate the sheet material supporting surface and a blade sharpening region above the cutting region, and at least one blade sharpening wheel supported within the cutting region, said method comprising the steps of elevating the blade from the cutting region to the blade sharpening region, reciprocating the blade within the sharpening region, biasing the one sharpening wheel toward the blade and into sharpening engagement with the leading cutting edge of the blade and maintaining the one sharpening wheel in sharpening engagement with the leading cutting edge as the blade moves upwardly from a lower limit toward an upper limit within the sharpening region, and moving the one sharpening wheel under the leading edge of the blade and in sharpening engagement with the lower cutting edge of the blade as the blade approaches and moves to the upper limit of its travel within the sharpening region.

4,294,048 APPARATUS FOR SUPPORTING PIVOTALLY MOUNTED SEATS


David L. Sutter, Kennebunkport, Me., assignor to Hussey Manufacturing Co., Inc., North Berwick, Me.

Filed Feb. 4, 1980, Ser. No. 118,393

Int. Cl.³ E04H 3/12; A47C 1/12

U.S. Cl. 52—9

12 Claims



1. Apparatus for supporting an extended row of adjoining seats to pivot on a base in unison between an upright and a collapsed position comprising:

- (a) means for applying pivotal force to each seat which is substantially equal and opposite to the pivotal force on the seat of the weight of the seat in any position between and including the upright and collapsed positions, and
- (b) releasable means for locking the row of seats respectively in the upright and collapsed positions.

4,294,049

QUICK OPENING INTERNAL MANWAY FOR TOWERS


Dick K. Young, and Kenneth E. Sumner, both of Littleton, Colo., assignors to Marathon Oil Company, Findlay, Ohio

Continuation of Ser. No. 6,604, Jan. 16, 1979, abandoned. This application Jan. 31, 1980, Ser. No. 117,159

Int. Cl.³ E02D 29/14

U.S. Cl. 52—20

2 Claims



1. An improved quick opening internal manway cover for selectively opening and closing a manway, said manway having an edge disposed therearound, said improved manway cover comprising:

- opposing identical panels for selectively opening and closing one-half of said manway, said panels being opposing and non-connected to each other when closed in said manway, each of said panels comprising:

- (a) a cover piece for covering approximately one-half of said manway, said cover having means extending therefrom for overlying a portion of the top of said manway edge,
- (b) means extending downward from said cover piece for

positioning said panel in said manway against said manway edge,

- (c) means connected to said positioning means on said cover piece opposite the side where said panel abuts the opposing panel for extending under said manway edge,
- (d) means connected to the top surface of said cover piece for overlying a portion of the top surface of the top of the cover piece of said opposing panel when said panels are in said closed position, and
- (e) means operatively connected through said cover piece near where the aforesaid overlying means is connected to said cover piece for releasably locking said panel to said manway edge when said panel is in said closed position, said locking means being capable of being operated from either side of said panel,

and

said improved cover being capable of being opened and closed on either side of said cover in said manway by operation of said locking means to fully release either one of said panels for removal and then by removing the remaining panel from said manway.

4,294,050

TRUSS-FRAMED BUILDING STRUCTURES


Arnold Kandel, P.O. Box 416, Fairfax, Va. 22030

Filed Jan. 24, 1980, Ser. No. 114,747

Int. Cl.³ E04B 7/02

U.S. Cl. 52—93

4 Claims



1. A roof truss made of unitized wooden frame elements comprising a pair of centrally interconnected upper chords which provide the upper sloped surfaces of a roof, said upper chords being joined near their outer ends by a horizontal lower chord which is discontinuous near each end thereof, and vertical risers interconnecting said lower chord on both sides of each discontinuity with said upper chord to form post-receiving pockets near each end of said lower chord, said post-receiving pockets being backed up by a prenailed gusset on one side of said truss.

4,294,051

MODULAR BUILDING SYSTEM

William J. Hughes, Jr., 2100 College Dr., Baton Rouge, La. 70808

Filed May 21, 1979, Ser. No. 40,878

Int. Cl.³ E04C 1/08, 1/28

U.S. Cl. 52—98

5 Claims


1. A building having an exterior wall structure which comprises:

- (a) a series of like panels and sub-divisions thereof, each of which has a plurality of defined internal horizontal passages with said passages of adjacent panels being in alignment; said panels capable of being subdivided along any line normal to said passages to provide a subdivided panel having an edge configuration identical to the edge of the uncut panel;
- (b) fins positioned between adjacent panels, said fins being constructed of material having greater shear strength than

said panels and having openings therein in alignment with said passages;

- (c) load transferring members positioned in a plurality of said openings in said fins, each of said members extending partially into said aligned passages of said panels on each side of a fin; and
- (d) integrating means positioned in and extending through a plurality of said aligned passages and openings of said panels and fins respectively, each of said integrating means extending continuously through a plurality of said panels and fins and being anchored at each end thereof and maintained in state of tension so as to maintain said panels and fins under compression in the horizontal direction;

said building also having a ceiling and roof each of which



comprises at least one row of panels with fins positioned between adjacent panels, said panels and fins being alike and interchangeable with said panels and fins of said wall structure and being held in assembled relation by a plurality of integrating means passing through aligned passages and openings in said panels and fins respectively, each of said integrating means being maintained in a state of tension and secured at opposite ends of said ceiling and roof respectively so as to maintain said panels and fins under compression, load transferring members positioned in a plurality of the openings in said fins and extending partially into said passages of the adjacent panels each of said fins having a width in excess of the thickness of said panels such that a portion of each of said fins extends beyond the surface of the panels, and auxiliary strengthening members secured to said portions of a plurality of said fins so as to augment the strength of the fins.

4,294,052

PREFABRICATED LOAD BEARING STRUCTURE


Aaron Blauer, 386 Strathcona Dr., Town of Mount Royal, Quebec, Canada

Filed Nov. 19, 1979, Ser. No. 95,400

Int. Cl.³ E04H 1/00

U.S. Cl. 52—236.5

11 Claims



1. A multi-storey building having a foundation and a roof, the building comprising a plurality of poured concrete floors,

the poured concrete floors being separated by parallel walls, each wall comprising a row of a plurality of prefabricated panels made up of structural tubular members, the panels extending from one floor to a next adjacent floor, each panel having parallel upper and lower chords, each wall being in vertical alignment with corresponding wall situated on vertically adjacent floors, each vertically adjacent wall being interconnected by high-tensile strength fasteners rigidly interconnecting the upper chord of each panel to an adjacent lower chord of a vertically adjacent panel, each fastener having a length at least greater than the combined thickness of the upper and lower chords of vertically adjacent panels and the floor therebetween, the rows of vertically interconnected prefabricated panels providing effective continuous lightweight bearing walls extending from the foundation of the building to the roof thereof, the bearing walls supporting loads imposed on the building and providing stiffness to the building.

4,294,053

MOBILE HOME ANCHOR


Rosario Lopes, 19266 Berden, Harper Woods, Mich. 48225

Filed Jun. 5, 1978, Ser. No. 912,321

Int. Cl.³ E02D 27/00

U.S. Cl. 52—295

7 Claims



1. In combination with a mobile home having an underframe with an I-beam and said mobile home being mounted above a base, an anchor for detachably securing said I-beam to said base comprising:

a pair of spaced clamping elements, each clamping element having an upper flange engaging portion and a downwardly depending portion, each downwardly depending portion having an aperture formed therethrough;

elongated connecting means extending from between the downwardly depending portions of the clamping elements and to said base, said connecting means having an aperture at its upper end;

means for securing the lower end of the connecting means to the base;

means for attaching the upper end of the connecting means to the clamping elements, said attaching means comprising a clevis having a central leg and two end legs, the central leg of said clevis being positioned through the apertures in said clamping elements and in the upper end of the connecting means so that the clevis and legs face downwardly and extend along the outside faces of the clamping element downwardly depending portions below said apertures; and

means for tensioning said elongated connecting means to thereby hold said clevis to said clamping elements and so that said clevis prevents separation of said downwardly depending portions and thus separation of said clamping elements.


4,294,054
SOFFIT SYSTEM FOR SUSPENDED CEILING
Albert F. Kuhr, Elk Grove Village, Ill., assignor to United States Gypsum Company, Chicago, Ill.

Filed Aug. 9, 1979, Ser. No. 65,398

Int. Cl.³ E04B 5/52

U.S. Cl. 52—484

1 Claim



1. A suspended ceiling boxed around a projection depending from ceiling joists, said suspended ceiling comprising in combination:

a plurality of suspension brackets depending from the ceiling and terminating at the bottom thereof in inverted-T runners;

a plurality of ceiling tiles resting on the inverted-T runners; at least one U-shaped channel resting on an inverted-T runner adjacent to the projection depending from the ceiling and having a vertically disposed ceiling tile resting therein, and means for holding the ceiling tile against the side of the U-shaped channel member.

4,294,055

HONEYCOMB OVERHEAD DOOR

Donald D. Andresen, 10380 W. Whitesbridge Ave., Fresno, Calif. 93706


Continuation of Ser. No. 479,643, Jun. 17, 1974, abandoned.

This application Feb. 14, 1977, Ser. No. 768,325

Int. Cl.³ E05C 2/32

U.S. Cl. 52—795

5 Claims



1. A panel construction useful for doors which are supported at side bearing points and are supported thereby in an overhead, horizontal position which comprises:

a plurality of cores formed of a honeycomb structure defined by a plurality of parallel strips of sheet material, each formed into a sinuous path and bonded to immediately adjacent strips at its outwardly bowed extremities, said core being aligned with said strips extending across the width of said door;

said cores being interspaced by internal spline members, each spline member being formed of a core of said honeycomb structure;

upper and lower cross frame members;

covering sheets extending over the opposite sides of said honeycomb core; and,

foamed adhesive material on the interior surfaces of said covering sheets and drawn up on said strips of sheet material, forming a continuous fillet at the juncture of the edges of said strips and said covering sheets, thereby bonding said sheets to the edges of said strips of said core of honeycomb structure.

4,294,056

VACUUM PACKAGING MACHINE

Ralf Paulsen, Kapellenweg 1, Buchenberg; Max Sontheim, An der Steig 17, Wiggensbach, and Christoph Ullmann, Falkenberg 17, Kempten, all of Fed. Rep. of Germany


Filed Oct. 1, 1979, Ser. No. 80,924

Claims priority, application Fed. Rep. of Germany, Oct. 4, 1978, 2843166; Aug. 8, 1979, 2932098

Int. Cl.³ B65B 31/02, 43/08, 47/10

U.S. Cl. 53—86

6 Claims



1. A vacuum packaging machine comprising chambers for forming a packaging foil from at least two foils and means for evacuating and sealing the packages, each chamber comprising an upper and a lower part, which parts are movable relative to one another and, in an operative position in which they are pressed together, clamp marginal portions of the foils therebetween, each chamber part having a hollow recess in its central region formed by a plate portion and four walls arranged in a rectangle, said walls depending from said plate portion of said upper part and upstanding from said plate portion of said lower part to form a single chamber when pressed together, wherein at least one of said chamber parts is made from a preformed length of material having an appropriate cross-sectional profile to provide two opposite walls integral with said plate, and the other two walls are formed by covers attached to said integral walls and plate.

4,294,057

CASE PACKER APPARATUS INCLUDING VELOCITY COMPENSATOR ASSEMBLY

Michael E. Winiasz, and James M. Long, both of Lorain, Ohio, assignors to A-T-O, Inc., Willoughby, Ohio

Continuation-in-part of Ser. No. 895,815, Apr. 12, 1978, Pat. No. 4,199,291. This application Apr. 21, 1980, Ser. No. 141,774

Int. Cl.³ B65B 21/12


U.S. Cl. 53—244

7 Claims

1. In a case packer apparatus including a frame, a driven conveyor for moving empty cases through a fixed course having a horizontal section, said cases being moved at a fixed speed in said horizontal section, and a driven conveyor means having a fixed, closed orbit positioned in a vertical plane above said conveyor horizontal section, said conveyor means being driven at a greater speed than said fixed speed, a drive sprocket and a guide sprocket for said driven conveyor means, article gripper means, and carrier bars for said article gripper means operatively connected to and movable with said conveyor means, a driven article supply conveyor positioned below said driven sprocket, a pair of control arms for each said carrier bar individually fixedly secured to different ends of said carrier bar, to form carrier bar units,

said driven conveyor means having a course extending downwardly towards said horizontal section at an acute

angle thereto and then upwardly from an inflection area or zone at an acute angle thereto, said inflection area being the area of transfer of an article in relation to said driven conveyor and said conveyor means, and characterized by pairs of longitudinally spaced first guide means and second guide means on said frame to engage one of said control arms and control the angular relationship of said carrier bars and gripper fingers to the axis of said conveyor means



as the carrier bar units are descending towards and into said inflection area and to engage the other of said control arms as its carrier bar moves away from said inflection area, said guide means each having an entrance end and an exit end, and said guide means operatively extending around the orbit of said driven conveyor means and being varied in spaced from such orbit to vary the positions of said gripper means in relation to a vertical axis.

4,294,058

CONTAINER PACKAGE AND ITS MANUFACTURE


Jürgen G. Rensner, Philadelphia, Pa., assignor to Pepsico, Inc., Purchase, N.Y.

Continuation of Ser. No. 812,327, Jul. 1, 1977, abandoned, which is a division of Ser. No. 697,578, Jun. 18, 1976, Pat. No. 4,078,659. This application Apr. 3, 1979, Ser. No. 26,772

Int. Cl.³ B65B 61/14

U.S. Cl. 53—413

26 Claims



1. A method of attaching thermoplastic film handles to adjacent packages of articles tightly wrapped in thermoplastic film, said packages having an upper surface, said method comprising the steps of:

(a) providing a weakened portion in the upper surfaces of said thermoplastic film for opening said packages;

(b) contacting thermoplastic handle film tacked to said thermoplastic wrapping at a first side at a location below the level of said weakened portion of a first said package, with a second location on said thermoplastic wrapping on an opposite side of said first package;

(c) heating said handle film in contact with said opposite side of said first package to tack said handle film to said first package thermoplastic wrapping at the location of said contact, while leaving an area of the handle film adjacent the tack at least partially untacked;

(d) contacting another portion of said thermoplastic handle film with a first location on said thermoplastic wrapping on a first side at a location below the level of said weakened portion of a second said package;

- (e) heating said handle film in contact with the thermoplastic wrapping on said first side of said second package to tack said handle film to said second package thermoplastic wrapping at the location of said contact, while leaving an area of the handle film adjacent the tack at least partially untacked;
- (f) severing said handle film between said tacks on said opposite side of said first package and said first side of said second package;
- (g) repeating steps (b) through (f) with respect to a location on said second package opposite to said first side thereof, and with respect to subsequent said packages to which said handle film is attached; and
- (h) heating said adjacent areas of the tacked portions of said thermoplastic handle film to increase the attachment of said handle film to said packages.

4,294,059


BIN FILLING APPARATUS AND METHOD
Robert E. Stilwell, and David E. Westerling, both of Riverside, Calif., assignors to FMC Corporation, San Jose, Calif.

Filed Feb. 22, 1980, Ser. No. 123,606

Int. Cl.³ B65B 35/38, 35/52, 1/16

U.S. Cl. 53—448

26 Claims



19. Apparatus for receiving generally rounded articles from an article supply source and for spreading the articles laterally in a close-packed array over a predetermined width wherein the outlet from the supply source is substantially narrower than the predetermined width, said apparatus comprising an inclined spreading conveyor with means mounting an elevated end adjacent to the narrow supply source outlet, means for intermittently driving said spreading conveyor to advance toward said elevated end whereby articles collecting thereon while said spreading conveyor is stationary, tend to spread transversely at the lower end thereof while said spreading conveyor is being driven.

22. A method of filling loose articles of produce of generally rounded configuration and of random sizes and shapes, such as apples, into a bin, said method comprising the steps of assembling a layer of said articles on a generally flat surface in a closely packed and randomly oriented array where said articles are in abutting engagement with each other throughout the layer, moving a vacuum head with a plurality of depending vacuum pickup cups over and onto said layer to cause the cups to grip substantially all of the articles in the layer within the confines of the vacuum head, there being substantially more vacuum cups on said vacuum head than articles to be gripped, moving the vacuum head over and into said bin, removing the vacuum from the cups to release the layer of articles in the bin directly adjacent to the previously loaded layer of articles or to the bottom of the bin, and repeating the aforesaid steps until the bin is filled to the desired level, wherein the step of assembling the layer of articles comprises randomly receiving the articles from a supply conveyor having a width substantially narrower than said layer, and causing the articles to gravitate over an intermediate conveyor between said supply conveyor and the assembling area, which intermediate conveyor is driven in a direction opposite to the direction of movement of

the articles to cause the articles to uniformly spread to the width of the layer to be picked up in the assembling area.

4,294,060

SWEET FORMING AND WRAPPING MACHINE


Arthur V. Naylor, Seacroft, and John K. Spencer, Gainsborough, both of England, assignors to Baker Perkins Holdings Limited, Peterborough, England

Continuation-in-part of Ser. No. 877,290, Feb. 13, 1978, abandoned. This application Apr. 17, 1979, Ser. No. 30,837
Claims priority, application United Kingdom, Feb. 18, 1977, 6822/77

Int. Cl.³ B65B 57/02

U.S. Cl. 53—506

3 Claims



1. In a sweet-forming and wrapping machine comprising a wrapping mechanism, a feed channel for feeding a rope of candy in a normal path of travel towards the wrapping mechanism, feed rollers for advancing the rope along said feed channel, cutting means for severing sweets in succession from the leading end of the rope, means for transferring the sweets in succession into the wrapping mechanism, means for feeding wrappers in succession into the path of travel of the sweets so that each sweet enters the wrapping mechanism with a wrapper partially folded about it drive means for driving said machine, a detector for sensing the feed of the wrappers and a machine stopping switch operable instantaneously by said detector to stop said machine drive in response to detection of a failure in the wrapper feed, the improvement which consists in the provision, in a machine capable of running at such a high speed that the wrapping mechanism overruns an amount sufficient to complete wrapping of partially wrapped sweets following the stopping of said machine drive by said stopping switch, of means responsive instantaneously to operation of said machine stopping switch by said detector to immediately divert said rope out of its normal path of travel and away from said cutting means, notwithstanding the overrun of said wrapping mechanism following the stopping of said machine drive.

4,294,061

COMESTIBLE PACKAGING APPARATUS

John P. Lekas, 5316 E. Exeter Blvd., Phoenix, Ariz. 85019

Filed Sep. 13, 1978, Ser. No. 942,126


Int. Cl.³ B65B 35/50

U.S. Cl. 53—536

5 Claims

1. Apparatus for automatically packing trays of comestibles having conveyance means for incrementally supplying a plurality of trays shelf means for receiving the trays, said shelf means including a plurality of individually extendable shelves, said shelves having retraction means, feed comb means for transferring the trays from the conveyance means to said shelves of said shelf means alignment means for incrementally moving said shelf means to sequentially align at least some of said plurality of shelves with said conveyance means to receive a tray reset arm means for individually extending at least some of said plurality of shelves to receive a tray, said retraction means on said shelves causing at least some of said shelves

to retract as soon as said reset arm means stops causing each of said plurality of shelves to be individually extended, thereby causing the trays to stack, and



cycloidal cam means for causing said conveyance means, said feed comb means, said alignment means and said reset arm means to cooperate in synchronism.

4,294,062

SENSING BAR


Shaun A. Seymour, New Holland, Pa., assignor to Sperry Corporation, New Holland, Pa.

Filed Mar. 27, 1980, Ser. No. 134,721

Int. Cl.³ A01F 12/10

U.S. Cl. 56—102

12 Claims



1. In an infeed housing for a harvesting and threshing machine attachable on a first end to a harvesting attachment and on a second end to the harvesting and threshing machine effective to receive from the harvesting attachment crop material collected from a field and convey it into the harvesting and threshing machine for processing having:

- a frame with a bottom surface, an upper surface and two opposing sides thereby defining a flow passage for crop material as it is conveyed to the machine;
- conveying means moveably mounted to the infeed housing to convey crop material from the harvesting attachment to the machine and cooperative with the bottom surface to thereby define a predetermined path of travel within the flow path, said conveying means including a front guide drum mounted above said path of travel of said crop material adjacent said first end of said infeed housing for deflecting material entering said first end downwardly toward said bottom surface;
- object removal means moveably connected to the infeed housing intermediate the first end and the second end effective to remove non-frangible objects from the predetermined path of travel;
- non-frangible object detecting means connectable to the

object removal means and mountable to the infeed housing; and

- sensing means for sensing non-frangible objects fastened to the bottom surface adjacent the first end between the two opposing sides positioned along the predetermined path of travel and connectable to the object detecting means, the sensing means having a first portion adapted to contact a non-frangible object within said crop material flow path and direct the non-frangible object upwardly toward said guide drum and a second portion adapted to contact non-frangible objects deflected downwardly by said guide drum and to guide the non-frangible object toward the object removal means, the contact with the sensing means by the object further being effective to permit the object detecting means to selectively actuate the object removal means to eject the object from the infeed housing.

4,294,063

HARVESTER AND METHOD FOR HARVESTING GREEN TOMATOES


George Bianchi, P.O. Box 190, Merced, Calif. 95341

Filed Feb. 7, 1980, Ser. No. 119,308

Int. Cl.³ A01D 17/08

U.S. Cl. 56—16.4

10 Claims



1. A harvester for green tomatoes growing on vines in a row comprising:

- a frame;
- means supporting the frame for travel along such a row;
- means on the frame for severing vines in the row from the ground as the frame travels along the row;
- an aqueous bath mounted on the frame;
- means mounted on the frame above the bath adapted to receive vines with tomatoes thereon from the severing means and to shake tomatoes from the severed vines into the bath while excluding the vines from the bath and discarding the same;
- means on the frame for removing tomatoes from the bath; and
- means on the frame for drying surface moisture from the tomatoes removed from the bath, in which the bath comprises a tank having a dividing wall separating the tank into a tomato washing compartment and a water cleaning compartment interconnected in a closed circuit, a pump for circulating water in the closed circuit from the tomato washing compartment to the water cleaning compartment and return in a predetermined direction of flow in each compartment, a straining conveyor mounted in the tomato washing compartment and upwardly inclined from the tank at a position in the predetermined direction of flow therein to strain tomatoes from the bath and to elevate them from the tank and a sieving conveyor mounted in the water cleaning compartment and upwardly inclined from the tank at a position in the predetermined direction of flow therein to sieve debris from the bath and to elevate it from the tank.

4,294,064

METHOD OF AND A DEVICE FOR BALANCING A CHANGING LOAD OF A STRIP ROLL ORBITING ABOUT AN AXIS IN A STRIP WINDING MACHINE
Günther Schmitz, Odenthal, and Hans Kierdorf, Cologne, both of Fed. Rep. of Germany, assignors to Felten & Guillaume Carlswerk, Cologne, Fed. Rep. of Germany


Filed Jan. 25, 1980, Ser. No. 115,288

Claims priority, application Fed. Rep. of Germany, Jan. 1, 1979, 2903807

Int. Cl.³ B65H 81/06

U.S. Cl. 57-3

14 Claims



6. A strip winding machine, including a stationary frame, a winding head rotating about a first axis, at least one head disk supported in said winding head for rotation about a second axis which is perpendicular to said first axis and being adapted for carrying a strip roll, comprising a device for balancing the changing load of said strip roll, the device including a counterbalancing weight displaceable about a third axis extending perpendicularly to said first axis opposite said second axis; means for measuring the change of the diameter of the strip roll during the winding operation and for producing control signals corresponding to the measured change; and drive means for said counterbalancing weight controlled by said control signals.

4,294,065

METHOD AND APPARATUS FOR FACILITATING MAINTENANCE OF SPINNING MACHINE INFORMATION SYSTEM


John E. Lane, Littleton, Mass., assignor to Parks-Cramer Company, Fitchburg, Mass.

Continuation-in-part of Ser. No. 900,267, Apr. 26, 1978, Pat. No. 4,194,349. This application Sep. 24, 1979, Ser. No. 77,929

Int. Cl.³ D01H 13/32; G06F 11/32; H04Q 9/00

U.S. Cl. 57-265

10 Claims



1. In apparatus for displaying information regarding the operating conditions of a group of ring spinning machines in a textile mill wherein each machine has instrumentalities from which strand material issues and by which strand material is formed into packages during winding thereof, and detectors on each machine for signalling occurrences of events characteristic of certain operating conditions of the machines, and wherein the apparatus has at least one traveling unit supported for travel along a predetermined path for traversing one or more of the machines, and detectors mounted on the traveling unit for monitoring ends of strand material normally being formed by a traversed machine, and further wherein the apparatus has a data system responsive to the detectors on each machine and on the traveling unit for determining said operating conditions of each machine of the traversed group of machines, the improvement in the data system which comprises: input means for entering a request for display of information characteristic of a selected individual operating condition of a selected individual spinning machine, and output means for displaying requested information in response to entry of a request through said input means.

tic of certain operating conditions of the machines, and wherein the apparatus has a data system with distributed processors responsive to the detectors on each machine for determining said certain operating conditions of each machine of the group of machines, and display means responsive to the processors for visually displaying such certain operating conditions, the improvement in the data system which facilitates maintenance thereof and comprises: malfunction detection circuit means operatively connected with the distributed processors for identifying malfunctions of defined portions of the data system, and output means operatively connected with said malfunction detection circuit means and responsive thereto for effecting display of information characteristic of the nature and location of malfunctions.

4,294,066

METHOD AND APPARATUS FOR DISPLAYING SPECIFIC SPINNING MACHINE OPERATING CONDITIONS


John E. Lane, Littleton, Mass., assignor to Parks-Cramer Company, Fitchburg, Mass.

Continuation-in-part of Ser. No. 900,267, Apr. 26, 1978, Pat. No. 4,194,349. This application Sep. 24, 1979, Ser. No. 77,931

Int. Cl.³ D01H 13/32; G06F 11/32; H04Q 9/00

U.S. Cl. 57-265

16 Claims



1. In apparatus for displaying information regarding the operating conditions of a group of ring spinning machines in a textile mill wherein each machine has instrumentalities from which strand material issues and by which strand material is formed into packages during winding thereof, and detectors on each machine for signalling occurrences of events characteristic of certain operating conditions of the machines, and wherein the apparatus has at least one traveling unit supported for travel along a predetermined path for traversing one or more of the machines, and detectors mounted on the traveling unit for monitoring ends of strand material normally being formed by a traversed machine, and further wherein the apparatus has a data system responsive to the detectors on each machine and on the traveling unit for determining said operating conditions of each machine of the traversed group of machines, the improvement in the data system which comprises: input means for entering a request for display of information characteristic of a selected individual operating condition of a selected individual spinning machine, and output means for displaying requested information in response to entry of a request through said input means.

4,294,067

METHOD AND APPARATUS FOR DOFFING AND DONNING BOBBINS IN A SPINNING MACHINE
Shuji Takahisa, Toyota; Osamu Suzuki, Ohbu, and Michio Shibano, Kariya, all of Japan, assignors to Kabushiki Kaisha Toyoda Jidoshokki Seisakusho, Aichi, Japan


Filed Jan. 22, 1980, Ser. No. 114,361

Claims priority, application Japan, Jan. 25, 1979, 54-8023

Int. Cl.³ D01H 9/08, 9/02

U.S. Cl. 57-274

7 Claims



1. An apparatus for removing full bobbins from a succession of spindles of a spinning machine and applying empty bobbins to the spindles from which the full bobbins have been removed, said apparatus comprising:

bobbin conveying means extending along the side of the spinning machine;

means disposed between the succession of spindles and said bobbin conveying means and along the side of the spinning machine for temporarily receiving the bobbins;

a tiltable and vertically movable doffing bar extending along the side of the spinning machine;

a succession of bobbin holders supported by said doffing bar so as to be arranged at the same intervals as the spindles;

means for tilting and means for vertically moving said doffing bar so that said bobbin holders supported by said doffing bar can operate on the spindles, said bobbin temporary receiving means and said bobbin conveying means;

said tilting means including a first piston and cylinder assembly with a reciprocating piston rod, and a mechanism connected between said piston rod and said doffing bar for converting reciprocating movement of said piston rod to tilting movement of said doffing bar between opposite end positions and an intermediate position;

means for maintaining said doffing bar at said intermediate position whereat said bobbin holders can operate on the bobbins on said bobbin temporary receiving means, said maintaining means including an engaging member mounted on a portion of said converting mechanism, and a second piston and cylinder assembly having a stop selectively movable into a path, along which said engaging member is moved by said first piston and cylinder assembly, to allow said engaging member to pressure contact with said stop, thereby stopping said doffing bar at said intermediate position; and

means for supplying fluid into said first piston and cylinder assembly so as to cause said engaging member to be disengaged from said stop in the path of said engaging member before said stop is moved out of the path of said engaging member in order to release said doffing bar from said intermediate position.

4. A method for removing full bobbins from a succession of spindles of a spinning machine and applying empty bobbins to the spindles from which the full bobbins have been removed, the spinning machine including a bobbin doffing and donning apparatus, said method comprising:

projecting a stop into a path along which an engaging member, mounted on a portion of a power transmission mechanism structurally associating a doffing bar with a piston and cylinder assembly for tilting said doffing bar, is moved by said piston and cylinder assembly to allow said engaging member to pressure contact against said stop, thereby stopping said doffing bar at an intermediate inclined position

in which said doffing bar operates on a refuge support; releasing said doffing bar from said intermediate inclined position by temporarily supplying fluid into said piston and cylinder assembly so as to move said engaging member in a direction in which it disengages from said stop; and thereafter moving said stop out of the path of said engaging member.

1. A supersonic jet engine adapted to cruise at supersonic speeds at a relatively high efficiency, to operate with turbine inlet temperatures of at least 2500° F. for high power operation, and to cruise subsonically with a relatively low specific fuel consumption, said engine comprising:

a. a housing structure having an upstream inlet end to receive intake air, and a downstream exhaust end to discharge jet exhaust;

b. an air inlet arranged to receive intake air at subsonic velocity and also to receive intake air at supersonic velocities and reduce said air to subsonic velocity;

c. a compressor mounted in said housing rearwardly of said inlet and arranged to compress air flowing into said inlet, said compressor having an inlet end and an outlet end arranged to operate between a maximum compression ratio and a minimum compression ratio;

d. means defining a combustion chamber mounted in said housing downstream of said compressor to receive compressed air therefrom;

e. fuel injection and ignition means in said combustion chamber arranged to burn fuel in air flow from the compressor and provide a gaseous flow from said combustion chamber;

f. a turbine mounted in said housing rearwardly of said combustion chamber and arranged to receive said gaseous flow from the combustion chamber at temperatures at least as high as 2500° F. and also at lower temperatures, said turbine being operatively connected to said compressor to drive said compressor, said turbine having a predetermined cross-sectional nozzle area through which said gaseous flow passes to pass rearwardly through a primary exhaust passageway;

g. a variable area exhaust nozzle to receive gaseous flow from said turbine and exhaust said flow to produce a thrust;

h. turbine bypass means to receive flow from a location downstream of said compressor as bypass flow, and to direct said bypass flow along a path bypassing said turbine, and exhaust said bypass flow from said engine to produce a thrust;

i. bypass valve means to control the amount of flow bypassed into said turbine bypass means;

j. engine control means operatively connected to said fuel injection and ignition means, to said bypass valve means

4,294,068

SUPERSONIC JET ENGINE AND METHOD OF OPERATING THE SAME


Garry W. Klees, Mercer Island, Wash., assignor to The Boeing Company, Seattle, Wash.

Filed Mar. 27, 1978, Ser. No. 890,364

Int. Cl.³ F02K 3/02

U.S. Cl. 60-204

30 Claims



1. A supersonic jet engine adapted to cruise at supersonic speeds at a relatively high efficiency, to operate with turbine inlet temperatures of at least 2500° F. for high power operation, and to cruise subsonically with a relatively low specific fuel consumption, said engine comprising:

a. a housing structure having an upstream inlet end to receive intake air, and a downstream exhaust end to discharge jet exhaust;

b. an air inlet arranged to receive intake air at subsonic velocity and also to receive intake air at supersonic velocities and reduce said air to subsonic velocity;

c. a compressor mounted in said housing rearwardly of said inlet and arranged to compress air flowing into said inlet, said compressor having an inlet end and an outlet end arranged to operate between a maximum compression ratio and a minimum compression ratio;

d. means defining a combustion chamber mounted in said housing downstream of said compressor to receive compressed air therefrom;

e. fuel injection and ignition means in said combustion chamber arranged to burn fuel in air flow from the compressor and provide a gaseous flow from said combustion chamber;

f. a turbine mounted in said housing rearwardly of said combustion chamber and arranged to receive said gaseous flow from the combustion chamber at temperatures at least as high as 2500° F. and also at lower temperatures, said turbine being operatively connected to said compressor to drive said compressor, said turbine having a predetermined cross-sectional nozzle area through which said gaseous flow passes to pass rearwardly through a primary exhaust passageway;

g. a variable area exhaust nozzle to receive gaseous flow from said turbine and exhaust said flow to produce a thrust;

h. turbine bypass means to receive flow from a location downstream of said compressor as bypass flow, and to direct said bypass flow along a path bypassing said turbine, and exhaust said bypass flow from said engine to produce a thrust;

i. bypass valve means to control the amount of flow bypassed into said turbine bypass means;

j. engine control means operatively connected to said fuel injection and ignition means, to said bypass valve means

and to said exhaust nozzle, in a manner to control the amount of fuel directed to said fuel injection and ignition means, to control said bypass valve means in a manner to control the amount of bypass flow through said turbine bypass means, and to control the discharge area through said exhaust nozzle,

- k. said turbine being matched to said compressor in a manner that with said engine operating at subsonic cruise velocity, with said compressor operating at maximum compression ratio, with said bypass valve means positioned so that there is substantially no flow through said turbine bypass means, and with fuel flow being adequate to create thrust to match airplane drag at said subsonic cruise velocity, the turbine has a flow area sized to allow gaseous flow there-through at the speed of sound in said gaseous flow,
- l. said engine control means being arranged to set said bypass valve means at a more open position at higher engine thrust settings where higher temperatures are created in said combustion chamber, and to set said bypass valve means at a more closed position at lower engine thrust settings where lower temperatures are created in said combustion chamber, in a manner that there is substantially constant corrected gaseous flow into said turbine, said corrected flow being measured according to the formula:

$$(W\sqrt{\theta + \delta +}) = \text{corrected flow}$$

where:

W = Total mass flow rate in lbs. per second

$\theta +$ = Observed temperature (absolute) divider by standard temperature (518.67° R)

$\delta +$ = Observed pressure divided by standard pressure (2116.22 lbs./sq. ft.)

whereby during subsonic cruise said engine can operate at a relatively low specific fuel consumption with high compression ratio and low combustion exit temperature, in a condition where said valve bypass means is at a substantially closed position, during high power acceleration mode said engine can operate at high combustion exit temperatures in a condition where said valve bypass means is in a more open position to maintain constant corrected flow through said turbine to satisfy the turbine requirements, and during supersonic cruise mode the engine can operate efficiently at relatively high combustion exit temperatures.

4,294,069

EXHAUST NOZZLE CONTROL AND CORE ENGINE FUEL CONTROL FOR TURBOFAN ENGINE


Vann T. Camp, Jupiter, Fla., assignor to United Technologies Corporation, Hartford, Conn.

Filed Apr. 26, 1978, Ser. No. 900,384

Int. Cl.² F02K 11/00; F02C 9/04

U.S. Cl. 60—238

2 Claims



1. A system for optimizing thrust of a gas turbine engine for powering aircraft having a variable area exhaust nozzle while maintaining airflow through the engine within its stable limits,

and having independent fuel control means and independent nozzle area control means comprising:

- means responsive to rotational speed of said engine for generating a signal for a desired engine pressure ratio,
- means responsive to actual pressure ratio for producing a signal indicative of the error between the actual pressure ratio and desired pressure ratio signal,
- nozzle area actuator means controlled by said independent nozzle area control responding to said error to further adjust the area of the exhaust nozzle,
- means for maintaining the proper amount of airflow in the engine and its inlet to achieve stable engine operations including,
- means for selecting the maximum value of a desired airflow signal generated as a function of Mach No. and engine inlet temperature and a minimum inlet airflow schedule generated as a function of Mach No. for producing a first output signal,
- means for selecting the minimum value of said first output signal and a maximum inlet airflow schedule generated as a function of Mach No. for producing a second output signal,
- means for measuring the airflow in said engine for producing an airflow signal,
- means summing said second output signal and said airflow signal for producing an error for further adjusting said exhaust nozzle area,
- a maximum selector for selecting the higher value of said error of said pressure ratio signal and said error of said airflow signal,
- and means for trimming the independent fuel control means as a function of the difference between a scheduled engine rotational speed and the actual engine rotational speed.

4,294,070

MASTER CYLINDER ASSEMBLIES

Glyn P. R. Farr, Leek Wootton, England, assignor to Lucas Industries Limited, Birmingham, England


Filed Oct. 29, 1979, Ser. No. 89,103

Claims priority, application United Kingdom, Nov. 2, 1978, 42910/78

Int. Cl.³ B60T 17/22

U.S. Cl. 60—534

10 Claims



1. A master cylinder assembly for a vehicle braking system having two pressure circuits, comprising a master cylinder, two pistons working in said cylinder and defining two separate pressure chambers, one chamber being arranged for connection to one of said pressure circuits, and a control valve means fast with the master cylinder, said control valve means having an inlet for connection to the other of said chambers and an outlet for connection to the other of said pressure circuits, a normally-open valve for controlling communication between said inlet and said outlet, and an auxiliary piston assembly movable to open and close said valve, wherein the auxiliary piston assembly has two portions, one portion being subjected to the pressure at said outlet of said valve arrangement and the other portion being subjected to the pressure of said one chamber of said master cylinder and being engageable by an adjacent one of said pistons of the master cylinder, in the event of failure of pressure in said one pressure circuit, whereby said piston assembly is moved to a position in which said valve is held open.

4,294,071

HYDRAULIC BOOSTER TRAVEL RATIO CHECK VALVE


Kenneth D. Jensen, Owosso, Mich., assignor to Midland-Ross Corporation, Cleveland, Ohio

Filed Dec. 12, 1979, Ser. No. 102,883

Int. Cl.³ B60T 13/00, 11/20

U.S. Cl. 60—547 A

16 Claims



1. A hydraulic booster comprising:
- a housing having an input end and an output end, the housing having a housing inlet, a housing outlet and a low pressure outlet;
- a control valve means, within the housing, having an inlet valve and an exhaust valve;
- an input means through the input end, the input means being operatively connected to the control valve means;
- a gain valve means in communication with a passage from the housing inlet to the housing outlet, at a gain valve gap;
- a power piston chamber on the output end side of the inlet valve of the control valve means, the power piston chamber connected through the inlet valve to the passage from the housing inlet to the gain valve gap;
- power piston slidingly located with a power piston bore in the housing between the power piston chamber and the output end;
- a slave piston slidingly located within a slave piston bore in the housing between the power piston and the output end;
- an output means from the output end operatively connected to the slave piston;
- a ratio chamber within the housing between the slave piston and power piston, there being a passage between the ratio chamber and the low pressure outlet;
- a check valve means disposed in the passage between the ratio chamber and the low pressure outlet and designed to allow fluid, under pressure, to flow through the passage in only one direction towards the ratio chamber, the check valve being designed to prevent the loss of fluid from the ratio chamber when the power piston moves in the direction of the output means.

4,294,072

MASTER CYLINDER AND RESERVOIR ASSEMBLIES

Derek J. Flynn, Solihull, England, assignor to Lucas Industries Limited, Birmingham, England

Filed Sep. 28, 1979, Ser. No. 80,065

Claims priority, application United Kingdom, Oct. 4, 1978, 39336/78


Int. Cl.³ B60T 11/26

U.S. Cl. 60—585

4 Claims

1. A master cylinder and reservoir assembly comprising an elongate master cylinder having a longitudinal axis and longitudinally extending recesses thereon, a reservoir having cooperating projections complementary to said recesses, said projections and recesses being so arranged as to permit interconnection of said reservoir and master cylinder by relative sliding movement in a direction generally parallel to said longitudinal axis of said master cylinder, said projections being formed on a foot portion of the reservoir, said foot portion having an aperture therethrough which cooperates with an aperture in the master cylinder wall to create a flow path between the reservoir and master cylinder, said foot portion having an extension

and a downwardly extending lug on said extension engageable with a complementary hole in said master cylinder to locate



and retain said reservoir in a desired predetermined position on said master cylinder.

4,294,073

INTEGRAL TURBINE HOUSING AND EXHAUST COLLECTOR SECTION


Joseph J. Neff, Zionsville, Ind., assignor to Cummins Engine Company, Inc., Columbus, Ind.

Filed Oct. 5, 1979, Ser. No. 82,284

Int. Cl.³ F02B 37/00

U.S. Cl. 60—597

20 Claims



1. A turbine housing for use on a multi-cylinder internal combustion engine having plural exhaust ports formed in the engine head/block assembly generally aligned from front to rear and a multi-branch exhaust manifold having a forward branch connected with at least one forward exhaust port for directing exhaust gases generally rearwardly and a rearward branch connected with at least one rearward exhaust port for directing exhaust gases generally forwardly, the rearward and forward branches terminating short of at least a pair of centrally located exhaust ports, wherein said turbine housing comprises:

(a) a volute section containing a central opening for receiving a rotatable turbine wheel having a rotational axis coincident with the central axis of the central opening and parallel to the first and second axis of the forward and rearward branches when the turbine housing is operatively mounted on the internal combustion engine and containing a pair of substantially isolated, side-by-side volute passages communicating with said central opening for receiving exhaust gases supplied by the forward and rearward branches, respectively, and for delivering exhaust gases to the turbine wheel substantially 360° around the periphery thereof, each said volute passage having an outermost wall which intersects a plane perpendicular to the central axis of the central opening to define a curved line beginning at the commencement point of each said volute passage and continuing around said central axis at

lating liquid simultaneously throughout the phase change material during melting.

36. The method for freezing ice solid in a vertical cylindrical plastic tank without creating lateral expansion forces in the tank for cooling storage for use in air conditioning a building using electrical energy at "off peak" rates including the steps of:

- uniformly spacing a grid of small diameter spaced flexible plastic tubes within and substantially throughout the tank in the main lower portion of said tank;
- arranging said tubes to give multiple parallel circuits with opposite direction of liquid flow in adjoining tubes;
- connecting said tubes to supply and return headers;
- filling said tank with water in the main lower portion of said tank while leaving the top portion of the tank free of water to accommodate expansion as the water is frozen into solid ice in the tank;
- connecting said headers through electrically energized pumping and refrigeration means located outside of said tank and arranged for refrigerating anti-freeze liquid;
- electrically energizing said pumping and heat exchange means during "off peak" hours of a 24 hour day for recirculating the anti-freeze liquid through said tubes at a temperature below the freezing point of water for causing the water in said plastic tank to freeze to solid ice around all of said adjoining tubes uniformly throughout the whole volume of water in said tank during said "off peak" hours;
- said freezing of the water to solid ice around all of said adjoining tubes throughout the whole volume of water in said tank squeezing the extra water volume upwardly due to expansion of the freezing ice and thereby preventing rupture of the plastic tank as the whole volume of water freezes to solid ice;
- during daylight hours when air conditioning is desired in the building recirculating the anti-freeze liquid through said tubes embedded in said solid ice and through second heat exchange means;
- blowing building air past said second heat exchange means for cooling the building air by transferring heat energy from the building air into said recirculating liquid and for transferring heat energy from said recirculating liquid into the ice in said tank;
- thereby providing air conditioning in the building while avoiding the use of electrical energy during hours of "peak" rates, and
- thereby advantageously avoiding rupture of the tank even though the water is frozen solid therein.

4,294,079

INSULATED CONTAINER AND PROCESS FOR SHIPPING PERISHABLES


Ernest J. Benson, Berkeley Heights, N.J., assignor to Better Agricultural Goals Corporation, Dallas, Tex.

Filed Mar. 12, 1980, Ser. No. 129,565

Int. Cl.³ B65B 63/08; F25D 3/08

U.S. Cl. 62—60

20 Claims



1. A process for packing perishables for shipment, comprising the steps of:

- (a) chilling the perishables to a desired predetermined unfrozen temperature;

- (b) placing the prechilled perishables on an absorbent pad within an insulated box;
- (c) covering the prechilled perishables with a layer of ice;
- (d) placing a wet pad on the layer of ice;
- (e) closing the top end of said box with a lid positioned in spaced relationship with said wet pad in order to define a head space therebetween; and
- (f) connecting a compartment containing subliming expendable refrigerant in fluid communication with the head space of said box so that sublimated refrigerant can refrigerate said box and substantially freeze said wet pad, thereby maintaining the perishables in chilled but unfrozen condition during shipment.

4,294,080

DESORPTION STEP IN ABSORPTION HEAT PUMPS AND REFRIGERATORS

Georges Cohen, Le Pecq, and Alexandre Rojey, Garches, both of France, assignors to Institut Français du Pétrole, Rueil-Malmaison, France


Filed Dec. 11, 1979, Ser. No. 102,489

Claims priority, application France, Dec. 11, 1978, 78 35010

Int. Cl.³ F25B 15/00

U.S. Cl. 62—101

18 Claims



1. An improved process for operating an absorption heat pump or an absorption refrigerator, the improvement comprising the steps of:

- (a) directly contacting a solute vapor phase (V'') with a liquid phase (L') and a liquid phase (L'') in an absorption zone, the liquid phases (L') and (L'') being solvents for the solute vapor phase (V''), thereby recovering a solution (S);
- (b) dividing the recovered solution (S) into a first portion (S₁) and a second portion (S₂), supplying said first portion (S₁) of the solution (S) to an indirect contact heat exchange zone and indirectly contacting said portion (S₁) with an external heating fluid in said indirect contact heat exchange zone, thereby recovering a vapor phase (V'), and a residual liquid phase (L'), separating said vapor phase (V') from said residual liquid phase (L') and feeding back said liquid phase (L') to step (a);
- (c) directly contacting, in counter-current contact, the vapor phase (V') from step (b) with said second portion (S₂) of the solution (S) in a desorption zone, thereby recovering separately a vapor phase (V) and a liquid phase (L'') and feeding back said liquid phase (L'') to step (a);
- (d) passing the vapor phase (V) from step (c) through a condensation zone, externally cooling the vapor phase (V) in said condensation zone with an external cooling fluid and recovering a condensed phase (C); and
- (e) passing said condensed phase (C) through an evaporation zone, externally heating said evaporation zone with an external heating fluid to vaporize at least a portion of said condensed phase (C), recovering a vapor phase (V'') therefrom, and feeding back said vapor phase (V'') to step (a).

4,294,081

FREEZING REFRIGERATOR



Akio Mitani; Moriyoshi Sakamoto, both of Yokohama, and Hiroaki Murasaki, Ibaraki, all of Japan, assignors to Tokyo Shibaura Denki Kabushiki Kaisha, Kawasaki, Japan

Filed Apr. 27, 1979, Ser. No. 33,978

Int. Cl.³ F25D 21/02; F25B 5/00

U.S. Cl. 62—140

8 Claims



1. A freezing refrigerator comprising:
 - a freezing chamber for storing an object to be frozen, said freezing chamber defined by contiguous top, bottom, side and rear walls and including an opening for taking the object in or out of said chamber;
 - a freezing chamber door member provided at the opening which is opened or closed when the object is taken in or out of said freezing chamber and for intimately closing said freezing chamber when said door member is closed;
 - a first cooling means which is provided at the periphery around the top, bottom and side walls of said freezing chamber to cool said freezing chamber;
 - a second cooling means which is disposed close to the rear wall of said freezing chamber;
 - a shield which is disposed between said second cooling means and said door and close to said second cooling means and is made of a heat insulative material, said shield substantially open around its periphery;
 - a heating means for melting frost attached to said second cooling means; and
 - coolant supply means for supplying a coolant to said first and second cooling means to produce a temperature differential therebetween such that the surface temperature of said second cooling means is lower than that of said first cooling means;
- wherein said shield defines a defrost region between said shield and said rear wall, said defrost region communicating with the rest of said freezing chamber around the periphery of said shield, whereby frost deposited on the first cooling means is migrated by air convection past said shield towards said second cooling means in said defrost region.

4,294,082

HYDRAULIC BLOWER SYSTEM FOR VEHICLES

Patrick L. Gerboth, Concord Township, Lake County, and Charles W. Thompson, Willoughby, both of Ohio, assignors to SGM Co., Inc., Mentor, Ohio

Filed Mar. 13, 1979, Ser. No. 20,075

Int. Cl.³ B60H 3/04

U.S. Cl. 62—244

6 Claims

1. For a vehicle including a hydraulic system for operating hydraulic equipment associated with the vehicle, and a prime mover for driving the hydraulic system to provide work thereto, the improvement comprising hydraulic blower means for blowing air in the vehicle to circulate air therein, and means for coupling hydraulic fluid of the hydraulic system to said hydraulic blower means to operate said hydraulic blower

means to blow air in the vehicle; said hydraulic blower means including a hydraulic motor having an output shaft on one side of said hydraulic motor and another output shaft on an opposite side of said hydraulic motor and blower means for blowing air, said output shafts being commonly rotated, said blower means including a separate squirrel cage blower mounted on each of said output shafts, and blower housing means about said squirrel cage blowers for at least partly covering said

squirrel cage blowers; the vehicle including an air conditioning system having a condenser with a condenser coil, said hydraulic blower means being mounted with respect to the condenser to circulate air over the condenser coil; said output shafts providing the sole support for said squirrel cage blowers; said blower housing means having inlet means and outlet means for air flow with respect thereto; and further comprising blower system housing means for supporting said hydraulic motor and said blower housing means in the vehicle.

4,294,083

AIR CONDITIONING SYSTEM


Barton King, 19415 W. Indies La., Tequesta, Fla. 33458

Filed Apr. 7, 1980, Ser. No. 137,870

Int. Cl.³ F25D 17/02

U.S. Cl. 62—434

9 Claims




1. An air conditioning system having a freeze tank, a first coolant tank positioned within said freeze tank, means for freezing a liquid in said freeze tank around said first coolant tank and cooling a liquid in the first coolant tank to a desired temperature, a second coolant tank, heat absorber plates being positioned within said second coolant tank, means connecting said first coolant tank to said heat absorber plates for pumping a cooled liquid in the first coolant tank through said heat absorber plates and back into said first coolant tank, an evaporator coil, means connecting said second coolant tank to said evaporator coil for pumping a cooled liquid in the second coolant tank through said evaporator coil and back into said second coolant tank.

4,294,084

ARTICLE OF JEWELRY WITH RECIPROCALLY MOVABLE GEM
 Lester M. Lampert, 2304 Greenview Rd., Northbrook, Ill. 60048
 Filed Aug. 19, 1976, Ser. No. 715,987
 Int. Cl.³ A44C 9/00, 17/02
 U.S. Cl. 63—15

9 Claims



9. An article of jewelry comprising a setting and at least one stone carried in said setting wherein the setting comprises guide means slidably holding said stone, said stone having a top side and a bottom side and being adapted to move in said guide means upon random tilting of said setting while being constrained by said guide means to movement in a linear path with said top side maintained uppermost in said setting.


4,294,085

FLAT BED KNITTING MACHINES
 Johann G. Trautner, Creussen, Fed. Rep. of Germany, assignor to Bentley Alemannia Limited, Great Britain
 Filed Oct. 2, 1979, Ser. No. 81,113
 Claims priority, application United Kingdom, Oct. 3, 1978, 39031/78

Int. Cl.³ D04B 7/00

U.S. Cl. 66—75.1

25 Claims



1. Flat bed knitting machines having a pair of needle beds, tricks in said needle beds, needles and jacks in the respective tricks and having associated operating butts extending outwards of the tricks, said needle operating butts being non-rotatable, a cam carriage, means for sliding said cam carriage across said needle beds, cam means including clearing cam means and stitch cam means on said cam carriage defining for said needle operating butts in each direction of carriage movement a collecting track, a knitting track and a tucking track, a first bank of actuators for selectively engaging said jacks to

cause selected needle operating butts to be raised lengthwise of the tricks from the collecting track for passing through the knitting track by means of said clearing cam means and said stitch cam means, a second bank of actuators spaced in trackwise alignment with said clearing cam means and housing on either side thereof cam means for raising the needle operating butts from the collecting track lengthwise of the tricks on the trailing side of said clearing cam means for passing through the tucking track by means of said stitch cam means in each direction of carriage movement.

4,294,086

LATCH NEEDLE FOR KNITTING MACHINES
 Harald Mayer, and Harido Berentzen, both of Albstadt, Fed. Rep. of Germany, assignors to Theodor Groz & Sohne & Ernst Beckert Nadelfabrik Commandit-Gesellschaft, Albstadt, Fed. Rep. of Germany


Filed Mar. 17, 1978, Ser. No. 887,587

Claims priority, application Fed. Rep. of Germany, Apr. 1, 1977, 2714607

Int. Cl.³ D04B 35/04

U.S. Cl. 66—121

1 Claim



1. A latch needle for knitting or like machines comprising: an elongated needle shank having an upper edge and a lower edge, and a hook at at least one end thereof and a longitudinally-extending slot formed therein flanked by a pair of opposed faces, and a latch pivotably mounted in said slot and having a spine with a widened wedge-like, rounded portion, said needle shank having a supporting portion for the widened, rounded portion of the spine of the latch at the faces of said shank flanking said longitudinal slot and said supporting portion being recessed relative to the upper edge of said needle shank, said longitudinal slot having a short recessed portion defined by a curved base wall containing an aperture leading to the lower edge of said needle shank and a further portion adjacent to said short portion which defines a channel characterized by an initial substantially rectilinear base wall and a further curved base wall which merges with said upper edge of the needle shank, said supporting portion of said needle shank for said widened, rounded portion of the spine of the latch being located over the substantially rectilinear base wall region of said further portion and said channel of said further portion being deeper than half the height of said needle shank in said substantially rectilinear base wall region and projecting in length beyond the end of said latch when in its rearward open position displaced away from its associated hook.

4,294,087

ENZYMATIC METHOD FOR HAIR RECOVERY WITH CONCURRENT OPENING OF HIDE STRUCTURE
 Rolf Monsheimer, Darmstadt-Eberstadt, and Ernst Pfeleiderer, Darmstadt-Arheilgen, both of Fed. Rep. of Germany, assignors to Röhm GmbH, Darmstadt, Fed. Rep. of Germany
 Filed Apr. 2, 1980, Ser. No. 136,678
 Claims priority, application Fed. Rep. of Germany, Apr. 28, 1979, 2917376


Int. Cl.³ C14C 1/06

U.S. Cl. 69—21

13 Claims

1. A method for the recovery of hair from an animal hide and for a concurrent opening of the hide structure using a proteolytic enzyme, which method comprises first pretreating the hide, free of preservative salt, in the acid pH region with a material cleaving disulfide bridges and then, without a previous softening, concurrently loosening hair and opening the hide structure by treating said hide with a protease, effective in the alkaline region, at a pH value of about 11 to about 13.

crank rotatably mounted in the front wall between the positions of the spaced springs, and having a forwardly




offset crank pin engaged in said cam opening and movable against the cam surface to move the bolt to retracted position.

4,294,088

SECURITY DEVICE FOR SPARE TIRES
 Rolla W. Barr, 16300 Fontaine Dr., Chesterfield, Mo. 63017
 Filed Oct. 16, 1978, Ser. No. 951,757
 Int. Cl.³ B60R 43/00, 43/02; E05B 67/38, 73/00
 U.S. Cl. 70—56

4 Claims



1. A security device for spare tires comprising: a housing having first means for receiving a shackle portion of an associated padlock, and second means for receiving a first portion of an associated member to be secured by the padlock, said first means being a relief adjacent one end of the housing and said second means being a relief opposite the first relief and adjacent the one end; shackle-securing means connected to the housing adjacent the one end; third means for receiving a second portion of the associated member, said third means being a relief adjacent another end of the housing opposite the one end; and means for manual access to the shackle, said means being an opening formed in the housing between the opposite ends.

4,294,089

LATCHBOLT RIM LOCK
 Walter E. Best, and William R. Foshee, both of Indianapolis, Ind., assignors to Best Lock Corporation, Indianapolis, Ind.
 Filed Nov. 30, 1978, Ser. No. 965,185
 Int. Cl.³ E05B 55/00


U.S. Cl. 70—150

16 Claims

1. A rim lock, comprising a case having a front wall and side and end walls, a latchbolt including a head and a draw plate, slidably mounted in the case for movement between a projected locking position and a retracted unlocked position, said draw plate having laterally spaced spring seats at its rear end, said case having two laterally spaced spring seats formed in its rear end wall, a spring mounted between each spring seat and the rear end of the draw plate and biasing the bolt forward to projected position, said draw plate having a cam opening therein ahead of said spring seats defining a forwardly presented cam surface, a

CYCLE LOCK ARRANGEMENT
 Romain Metzger, 1310 Roscoe, Chicago, Ill. 60657
 Filed Aug. 17, 1979, Ser. No. 67,350
 Int. Cl.³ B62H 5/08, 5/18; E05B 67/06, 71/00
 U.S. Cl. 70—226

9 Claims



1. In a locking device for a cycle having a fork, a wheel mounted in the fork, and a brake disc, with opening means extending therethrough, secured to said wheel outboardly thereof, the combination of:

- (a) a housing member including a body having a cavity therein, open at only one side thereof, and adapted to have said one side mounted against an outboard surface of said disc adjacent said opening means;
- (b) a retaining member including:
 - (i) an inboard portion adapted to be mounted against an inboard surface of said disc adjacent said opening means;
 - (ii) an integral outboard portion adapted to extend from said inboard portion, through said opening means and into said housing member cavity;
- (c) said housing member also including a lock element mounted for movement within said cavity into and out of engagement with the outboard portion of said retaining member to keep said disc snugly positioned between opposed surfaces of said retaining member inboard portion and said housing member body;
- (d) means for moving said lock element into and out of engagement with said retaining member outboard portion.

4,294,091

CONTROL DEVICE FOR CYLINDER LOCKS

Kurt Prunbauer, Herzogenburg, Austria, assignor to Evva Werk Spezialerzeugung von Zylinder- und Sicherheitsschlossern Gesellschaft m.b.H. & Co. Kommanditgesellschaft, Vienna, Austria


Filed Feb. 16, 1979, Ser. No. 12,895

Claims priority, application Austria, Feb. 20, 1978, 1222/78

Int. Cl.³ E05B 9/04, 47/00

U.S. Cl. 70—276

5 Claims



1. A control device, particularly for use in a magnetic cylinder lock, comprising, a housing defining a cylindrical passage, a cylindrical plug disposed in said passage for a rotational and axial movement relative to said housing; arresting means operable between said plug and said housing for blocking the rotational movement in one axial position of said plug and for unblocking the rotational movement in another axial position thereof; said plug having a radial extension and said housing defining an axial groove in engagement with said extension and an annular groove communicating with said axial groove to guide said extension in said other axial position; said plug including at least one longitudinal boring, a plurality of rotary members arranged respectively for rotation about an axis transverse to said longitudinal boring and each defining a diametrical boring which at one angular position of the rotary member is in alignment with said longitudinal boring, a plurality of arresting elements arranged in said longitudinal and diametrical borings over the entire length of said passage in the housing, and biasing means normally urging said plug into said one axial position.

4,294,092

CYLINDER LOCK HAVING SPRING-ACTUATED PINS

Ake T. L. Häggström, Lycksele, Sweden, assignor to GKN-Stenman AB, Eskilstuna, Sweden


Filed Feb. 13, 1980, Ser. No. 120,961

Claims priority, application Sweden, Feb. 13, 1979, 7901266

Int. Cl.³ E05B 27/04

U.S. Cl. 70—364 A

4 Claims



1. A cylinder lock, comprising: a cylinder housing (2), a cylindrical body (3) mounted in said housing for rotation through at least 180° when a correct key is inserted into said lock, said housing and said cylindrical body individually defining a first parallel set and a second parallel set of communicating bores, and a plurality of spring-actuated pins individually

accommodated within said first and second sets of bores, each pin comprising at least two parts and inner ends of said pins cooperating with a bit of the key, at least one of said sets of bores being inclined relative to a normal to the axis of the cylinder housing to partially axially offset the first and second sets of bores subsequent to rotating the cylindrical body through 180° and prevent the pin parts within the cylindrical body from falling out.

4,294,093

PIN TUMBLER LOCK WITH PULL-RESISTANT KEY PLUG


Walter E. Best; William R. Foshee, and Max L. Flack, all of Indianapolis, Ind., assignors to Best Lock Corporation, Indianapolis, Ind.

Filed Jun. 14, 1979, Ser. No. 48,531

Int. Cl.³ E05B 27/00

U.S. Cl. 70—369

14 Claims



1. A pin tumbler lock, comprising lock body means forming a key plug bore extending between front and rear faces and forming pin tumbler bores intersecting therewith, a key plug having a cylindrical portion received in said plug bore and containing an axial key slot and pin tumbler bores alignable with those of the body means, a peripheral flange on said plug integral with said cylindrical portion and disposed in thrust transmitting overlapping relation with the rear of the lock body means so as to oppose forward movement of the key plug, a circumferential groove in the key plug adjacent its front end and a retainer ring engaged in said groove and disposed in axially engaging relation with the front of the lock body so as to oppose rearward movement of the plug, said ring having a key-pass opening therein and interengaging the plug so as to be held with its said opening in alignment with the key slot of the key plug.

4,294,094

METHOD FOR AUTOMATICALLY CONTROLLING WIDTH OF SLAB DURING HOT ROUGH-ROLLING THEREOF

Masaru Okado, Tokyo, and Takashi Ariizumi, Yokohama, both of Japan, assignors to Nippon Kokan Kabushiki Kaisha, Tokyo, Japan

Filed Jan. 31, 1980, Ser. No. 117,272

Claims priority, application Japan, Feb. 24, 1979, 54-20213


Int. Cl.³ B21B 1/04, 27/02, 37/00

U.S. Cl. 72—16

10 Claims

1. A method for automatically controlling the width of a slab during hot rough-rolling thereof, which comprises: arranging a pair of horizontal broadening rolls each having at least one annular projection in a hot roughing mill train comprising a plurality of roll stands each having a pair of vertical rolls and a pair of horizontal rolls; calculating an amount of roll gap correction of said pair of broadening rolls on the basis of variations in the width of said slab during hot rough-rolling by said hot roughing mill, at the entry of said pair of broadening rolls; and,

controlling the roll gap of said gap of broadening rolls in response to said amount of roll gap correction; thereby automatically controlling the width of said slab



during hot rough-rolling thereof to a prescribed value in accordance with the finishing width of a steel strip, and at the same time, automatically correcting variations in the width of said slab during hot rough-rolling thereof.

4,294,095

PROCESS FOR FABRICATING HEAVY WALL TO PIPE

Tsuyoshi Kawano; Matsuo Usuda, and Toshio Hirokawa, all of Kisarazu, Japan, assignors to Nippon Steel Corporation, Tokyo, Japan


Filed Nov. 23, 1979, Ser. No. 97,043

Claims priority, application Japan, Nov. 22, 1978, 53-143325; Feb. 23, 1979, 54-19750

Int. Cl.³ B21D 5/00

U.S. Cl. 72—51

10 Claims



1. A process of fabricating flat steel plate into heavy wall UO pipe by crimping, U-ing and O-ing, wherein the U-ing operation comprises:

using a collapsible U-ing punch comprising a center block carrying paired side punches on both sides and a bottom punch at the bottom thereof; and obtaining the desired butt edge gap in the O-shaped work-piece by decreasing the ratio of the U-ing punch height to the U-ing punch width when the gap is smaller than the desired butt edge gap, and increasing said ratio when the gap is larger than the desired butt edge gap.

4,294,096

METHOD AND APPARATUS FOR MAKING A SECONDARY KEY FOR A LOCK MECHANISM

Joseph B. Heimann, 502 Marlbrook La., Lansdale, Pa. 19446 Division of Ser. No. 790,824, Apr. 25, 1977, Pat. No. 4,143,582. This application Dec. 11, 1978, Ser. No. 968,198

Int. Cl.³ B21D 33/00


U.S. Cl. 72—60

9 Claims

1. Apparatus for recording information relating to a primary key in order to be able to make a secondary key comprising: (a) a frame of essentially rectangular shape to accommodate the largest key to be recorded; (b) a support member for supporting said frame in a fixed position, said support member including a rectangular slot of dimensions sized to fit said frame, said slot being of a depth equal to or greater than the height of said frame whereby a key may be placed on the portion of said support member within the area enclosed by said rectangular

slot, said portion being coplanar with the rest of said support member;

(c) a piece of metallic foil secured between at least two sides of said frame, said frame with said foil placed over the rectangular portion of said support member enclosed by said rectangular slot, whereby the primary key may be placed under said foil for recording the impression of said primary key in said foil;



(d) an elastic roller mounted on a shaft for applying pressure between said metallic foil and key to press said key and metallic foil together such that the metallic foil is forced into and around indentations on said key, thereby making a recording in said foil; (e) means to support said shaft for rolling motion over said metallic foil; and (f) means in said support member for guiding said roller over said foil.

4,294,097

BOTTOM ROLL-FORMING METHOD AND APPARATUS AND RESULTANT CAN END CONFIGURATION


Laszlo A. Gombas, Rte. 7, Box 555Q, Evergreen, Colo. 80439 Division of Ser. No. 931,124, Aug. 4, 1978, Pat. No. 4,199,073.

This application Apr. 8, 1980, Ser. No. 138,855

Int. Cl.³ B21D 17/04

U.S. Cl. 72—94

23 Claims



1. The method of roll forming the end wall of a generally cylindrical receptacle composed of a ductile material which is open at one end and is provided with an end wall at the opposite end, the method comprising the steps of retaining each receptacle in succession in a fixed position with the exterior of the unitary end wall in facing relation to the end of a yieldable support and advancing at least one bearing surface axially through the interior of the receptacle into engagement with the end wall and rotating the bearing surface while continuously advancing same in an axial direction whereby to force the end wall into engagement with the yieldable support to roll-form an axially directed, annular rib in the end wall while forcing

the end wall to assume a generally dome-shaped configuration as it is forced against the yieldable member.

4,294,098

APPARATUS FOR MANUFACTURING STEEL SPRING LEAVES

Viktor P. Egorov, Vostryakovsky proezd, 11, korpus 1, kv. 226; Viktor A. Ognevsky, Sumskoi proezd, 15, korpus 2, kv. 279; Anatoly G. Orlovsky, Avtozavodskaya ulitsa, 7, kv. 81; Grigory A. Ostrovsky, Raketny bulvar, 10, kv. 47; Alexandr M. Ryskind, Kirovogradskaya ulitsa, 24, korpus 1, kv. 161; Anatoly L. Stepin, Birjulevskaya ulitsa, 5, korpus 2, kv. 347; Oleg F. Trofimov, Chusovskaya ulitsa, 11, korpus 8, kv. 92, and Isaak N. Shklyarov, Velozavodskaya ulitsa, 9, kv. 24, all of Moscow, U.S.S.R.

Division of Ser. No. 824,211, Aug. 9, 1977, Pat. No. 4,193,824.


This application Apr. 26, 1979, Ser. No. 33,520

Claims priority, application U.S.S.R., Aug. 18, 1976, 2385501; Aug. 18, 1976, 2385502

Int. Cl.³ B21D 5/14

U.S. Cl. 72-128

1 Claim



1. An apparatus for manufacturing spring leaves comprising: a support adapted to mount, live entry guide rollers; an induction heating coil, said coil being arranged intermediate said live entry guide rollers and connected to a power source; bending rollers set in pairs for accommodating therebetween a spring leaf; stops disposed between said live entry guide rollers and said bending rollers, as well as between the neighboring pairs of said bending rollers and spaced from the surface of each spring leaf passing in between said rollers, at a distance of from 0.0001 to 0.00005 of a specified radius of curvature of each spring leaf; a first cooler connected to a fluid source; exit guide rollers; an additional induction heating coil and cooler, both being arranged between said exit guide rollers and intended for surface hardening of spring leaves; an induction heating coil of said additional induction heating coil and cooler, being connected to a power source; a cooler of said additional induction heating coil and cooler, being connected to a fluid source; said first cooler, said additional induction heating coil and cooler and said exit guide rollers all being arranged along a circular arc having a radius equal to a specified radius of curvature of a spring leaf; a fluid source; and a means for actuating said live entry guide rollers.

4,294,099

ROLLING MILL TRAIN

Alfons Spaude, Dusseldorf, Fed. Rep. of Germany, assignor to Schloemann-Siemag Aktiengesellschaft, Dusseldorf, Fed. Rep. of Germany

Filed Oct. 10, 1979, Ser. No. 83,264

Claims priority, application Fed. Rep. of Germany, Oct. 12, 1978, 2844433


Int. Cl.³ B21B 1/12

U.S. Cl. 72-234

8 Claims

1. A method of rolling, comprising the sequential steps of: (a) passing material through a reversing pre-rolling stand;

- (b) passing the material through an edging stand a first time; (c) passing the material through a reversing universal rolling stand; (d) passing the material back through the reversing universal rolling stand; (e) passing the material through the edging stand a second time;



time with the reduction caliber roll of the edging stand adjusted from their position in step (b);

- (f) passing the material back through the edging stand a third time with the reduction caliber roll of the edging stand adjusted from their position in step (e); and (g) passing the material once again through the reversing universal rolling stand.

4,294,100

METHOD OF MANUFACTURING A SEAMLESS OUTER SLEEVE FOR A BALL BEARING

Armin Olschewski, Schweinfurt; Manfred Brandenstein, Eusenheim; Lothar Walter, Schweinfurt; Horst M. Ernst, Eltinghausen, and Toni Schulz, Dittelbrunn, all of Fed. Rep. of Germany, assignors to SKF Kugellagerfabriken GmbH, Schweinfurt, Fed. Rep. of Germany


Filed Jul. 11, 1979, Ser. No. 56,738

Claims priority, application Fed. Rep. of Germany, Jul. 15, 1978, 2831148

Int. Cl.³ B21D 53/10

U.S. Cl. 72-340

8 Claims



1. In a method of manufacturing a seamless outer sleeve for a ball bearing from a hollow cylindrical tube of predetermined outer diameter and uniform wall thickness to have radially inwardly projecting race sections parallel to the tube's central axis for the load-carrying balls of the ball bearing with inclined race transition sections at each end of each load-bearing section, the method steps comprising (a) forming only said axial race sections by deformation to a depth d radially inward of said outer diameter, and (b) cutting away the outer circumference of the sleeve by the amount of the forming depth d of the race sections thereby forming at each end of each load-bearing section a ramp having thickness less than that of said load-bearing sections.

4,294,101

METHOD OF MAKING SINGLE OR DOUBLE FLANGED TRACK TRACTOR ROLLER FOR OFF-HIGHWAY EQUIPMENT


Donald J. Diemer, 4355 Brendan La., North Olmsted, Ohio 44070, and Ralph D. Delio, R.D. #1 Susan Trace, New Wilmington, Pa. 16142

Filed Jan. 12, 1979, Ser. No. 2,851

Int. Cl.³ B21D 22/00; B21K 1/28

U.S. Cl. 72-356

29 Claims



1. A method of closed die forging to form a flanged cylindrical metal part having at least two exterior cylindrical flanges and a cylindrical cavity, which comprises the steps of:

- A. busting and preforming a heated billet to a cylindrical shape having one end and an axially opposite other end; B. thereafter inserting the billet and a split ring outwardly thereof into a set of dies, said ring having an interior conformation with at least one interior cylindrical groove to form a first flange; C. mating and supporting said ring within a first one of said dies to effectively close one end of said ring; D. closing the other end of said ring with the other die to forge said billet; and E. thereafter removing the split ring and billet together from said first-mentioned dies and placing the split ring and billet into a set of finishing dies, which finish forms the flanges and the cylindrical cavity, thereby displacing metal from the center of the billet into the flanges while forming the cylindrical cavity.

4,294,102

DEVICE FOR BENDING AND HARDENING BAR MATERIAL

Lothar Lückert, Hagen-Ems; Christoph Pohl, Witten; Carl-Erich Proll, Hagen, and Paul Steffes, Gevelsberg, all of Fed. Rep. of Germany, assignors to Proll & Lohmann Betriebs GmbH, Hagen, Fed. Rep. of Germany

Filed Mar. 27, 1980, Ser. No. 134,611

Claims priority, application Fed. Rep. of Germany, Mar. 29, 1979, 2912364


Int. Cl.³ B21D 37/04

U.S. Cl. 72-413

5 Claims

1. In a device for the bending and/or distortion-free hardening of bar material, particularly leaf springs, having a plurality of frame-shaped tools each of which comprises an upper part and a lower part, the tools, upon closing, bending a heated workpiece and lowering the workpiece in clamped condition into a treatment tank, the tools being moved vertically in a portal for the bending and lowering and being discharged from the portal in a lowest position thereof and being transported by means of guide rails of a transport device through the treatment tank before the tools are grasped by a lift portal and raised into a position above the treatment tank, in which latter position the tools are opened, the workpiece is removed and the opened tools are transferred into a ready position, the improvement comprising upper guide rail means for returning opened tools including a movable part of the length of said upper guide rail means, said movable part corresponds at least to the axial depth of

a tool, said movable part defining a normal position relative to the remainder of said upper guide rail means, said movable part being movable out of said normal position, changing means for being moved with said tool,



means comprising rail sections arranged on said changing means and for replacing said movable part of said upper guide rail means.

4,294,103

OVERLOAD SAFETY DEVICE IN HYDRAULIC FORMING PRESSES, IN PARTICULAR SHEET METAL FORM DRAWING PRESSES

Willi Funck, Meerbusch; Roland Verheyen, Krefeld, and Heinz Schedler, Heidesheim, all of Fed. Rep. of Germany, assignors to Schloemann-Siemag Aktiengesellschaft, Dusseldorf, Fed. Rep. of Germany


Filed May 1, 1980, Ser. No. 145,495

Claims priority, application Fed. Rep. of Germany, May 11, 1979, 2919012

Int. Cl.³ B21J 9/20

U.S. Cl. 72-453.14

9 Claims



1. A safety device against overload in a hydraulic forming press in particular for shaping sheet metal, said press comprising:

- (A) A table beam with a press table attached thereto, an opposing beam spaced therefrom, and end supports spacing said beams each provided with tension members; (B) A travelling beam guided at said opposing beam provided with at least one pressure cylinder to exert at said table a pressing force opposed by said tension members, (C) at least one parallel linkage comprising (a) a connecting rod pivoted at one end to one end of the travelling beam (b) an angle lever pivoted at the end of an upper arm thereof to the other end of said connecting rod (c) a like connecting rod pivoted at one end to the other end of the travelling beam (d) a like angle lever, with its included angle facing the

same direction as the first, and similarly pivoted at the end of an upper arm thereof to the other end of the like connecting rod

(e) a transverse connecting rod pivoted at both ends one to each lower arm of said angle levers;

said safety device comprising an operating rod fixed to lie along at least one of said connecting rods in such a way as to move with the small changes in longitudinal dimension of said one connecting rod due to tensile or compressive strain arising from unsymmetrical press loading, and switch means operable by said movements of said one rod to actuate an overload indication.

4,294,104

FRICTION DRIVE FORCE MEASUREMENT FIXTURE


Robert M. Pepper, Penfield, and Charles H. Braun, Webster, both of N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.

Filed Oct. 30, 1979, Ser. No. 89,687

Int. Cl.³ G01N 19/02

U.S. Cl. 73—9

7 Claims



1. Fixture for measuring the driving force of a friction drive apparatus, said fixture comprising:

- a first member having a first surface including means for locating said first member in juxtaposition with said friction drive apparatus;
- a reaction member movably supported on said first member such that when said first member is in juxtaposition with the friction drive apparatus said reaction member is in engagement with the friction drive apparatus and movable relative to said first surface in response to the driving force of the friction drive apparatus, said reaction member including reference means for indicating the relative position of said reaction member and said first surface; and
- means mounted on said first member for urging said reaction member toward a rest position on said first surface, the magnitude of force applied by said urging means being proportional to the displacement of said reaction member from said rest position by the driving force, whereby the position of said reference means relative to said first surface indicates the magnitude of the driving force on said reaction member.

4,294,105

MASS SENSING ELEMENT

Arnold J. Kelly, Princeton Junction, N.J., assignor to Exxon Research & Engineering Co., Florham Park, N.J.

Filed Apr. 8, 1980, Ser. No. 138,412


Int. Cl.³ G01N 22/00

U.S. Cl. 73—28

26 Claims

1. An apparatus used for sensing the mass of incident particles impinging thereupon, comprising a piezoelectric crystal coated over at least a surface portion thereof with a plurality of substantially rigid whiskers having a generally perpendicular

attitude with respect to said crystal surface and forming a mat-like mass upon said crystal so as to entrap or otherwise



retain said incident particles while said piezoelectric crystal is caused to vibrate.

4,294,106

LEAK DETECTOR

Roland Gevaud, Argonay, and Jacques Tallon, Annecy, both of France, assignors to Compagnie Industrielle des Telecommunications Cit-Alcatel, Paris, France


Filed Mar. 17, 1980, Ser. No. 131,121

Claims priority, application France, Mar. 28, 1979, 79 07788

Int. Cl.³ G01M 3/20

U.S. Cl. 73—40.7

5 Claims



1. A leak detector of the type that detects helium, the detector comprising a sniffer connected via a flexible hose to an inlet duct which is itself connected via a nitrogen trap and a molecular diffusion pump to a main vacuum pump whose inlet is connected to the molecular diffusion pump and whose outlet exhausts into the atmosphere, the nitrogen trap being further connected to helium measuring means; the improvement comprising:

- firstly providing the main vacuum pump in the form of a two stage pump having a low pressure stage connected to pump from the molecular diffusion pump and to exhaust, via a link duct, into a high pressure stage which itself exhausts to the atmosphere; and
- secondly providing a bleeder arrangement connecting the flexible hose both to the inlet duct and to an auxiliary duct which leads to said link duct between the pump stages to pump air and any leaking helium along the flexible hose at a speed greater than that which is attainable when the hose is directly connected only to the inlet duct, the bleeder arrangement ensuring that a proportion of the gas pumped in through the sniffer is fed via the inlet duct and the nitrogen trap to the helium measuring means.

4,294,107

SELF-PURGING PROBE FOR LOW PRESSURE LEAK DETECTION

L. Irwin Walle, 1537 Greenlea Dr., Clearwater, Fla. 33515

Filed May 19, 1980, Ser. No. 150,933

Int. Cl.³ G01M 3/32


U.S. Cl. 73—49.2

7 Claims

1. A fluid pressure purging adapter connected between a fluid test pressure source, a fluid pressure gauge and a fluid container undergoing a pressure test, for rapidly purging fluid

pressure from said pressure gauge when said container is disconnected from the adapter, comprising:

- a fluid pressure inlet chamber connected to said fluid test pressure source;
- a fluid pressure outlet chamber selectively connected to either said container under test or to an ambient fluid pressure;
- a high velocity fluid chamber connected between said fluid pressure inlet chamber and said fluid pressure outlet chamber, for conducting the testing fluid from said inlet chamber to said outlet chamber at a minimum velocity when said container is connected to said outlet chamber and for conducting the testing fluid from said inlet cham-



ber to said outlet chamber at a maximum velocity when said container is disconnected from said outlet chamber;

a pressure gauge channel connected to said fluid pressure gauge, having an orifice opening into said high velocity fluid chamber;

said high velocity fluid chamber having a fluid pressure substantially equal to the fluid pressure in said pressure gauge channel when said testing fluid therein has said minimum velocity and said high velocity fluid chamber having a fluid pressure substantially lower than the fluid pressure in said pressure gauge channel when said testing fluid therein has said maximum velocity;

whereby said fluid pressure is rapidly purged from said pressure gauge when said container is disconnected.

4,294,108

DEVICE FOR MEASURING THE FUEL CONSUMPTION OF A VEHICLE

Wolfgang Sauershell, and Karl-Heinz Werkmann, both of Frankfurt am Main, Fed. Rep. of Germany, assignors to VDO Adolf Schindling AG, Schwalbach, Fed. Rep. of Germany


Filed Dec. 21, 1979, Ser. No. 105,932

Claims priority, application Fed. Rep. of Germany, Feb. 12, 1979, 2905304

Int. Cl.³ G01F 9/02

U.S. Cl. 73—119 A

3 Claims



1. A device for measuring the fuel consumption of a vehicle, with means for measuring the fuel flow in a forward flow line, and means for measuring the fuel return flow in a return flow line, having means for detecting the difference between these

flows and for the calculation of the fuel consumption, characterized in that, for the measurement of the fuel forward flow and of the fuel return flow, respectively, a turbine flowmeter is connected in each of the forward flow line and the return flow line and photoelectric means is positioned to scan the rotation of each for the generation of an electrical value corresponding to the forward flow or return flow, and that means for gauging are provided in one of said means for measuring the fuel flow in said forward flow line and in said means for measuring the fuel return flow in said return flow line to adjust the measurement in said one means to correspond with the measurement in said other means, for obtaining identical electrical values at operative fuel consumption and at the same forward fuel flow and return fuel flow.

4,294,109

TEST APPARATUS FOR HYDRAULIC VALVE


Lester L. Peters, and John W. Black, both of Columbus, Ind., assignors to Cummins Engine Company, Inc., Columbus, Ind.

Filed Dec. 19, 1979, Ser. No. 105,290

Int. Cl.³ G01M 15/00, 19/00

U.S. Cl. 73—119 A

7 Claims



1. Apparatus for use in testing a hydraulic assembly, the assembly including a cup-shaped part having a bottom wall, a generally cylindrical wall, and an orifice formed in the bottom wall thereof, a valve member within said cylindrical wall on one side of the orifice, a spring urging the valve member toward the bottom wall to close the orifice, and a spider positioned within the cylindrical wall and supporting the spring, the spider further being connected to the part, said apparatus comprising a housing having a bore formed therein that is adapted to receive the assembly, said housing including seal means adapted to engage the outer surface of said assembly and form a sealed chamber on the outer side of the bottom wall around the orifice, means on said housing for connecting said chamber to receive a fluid under pressure from a variable fluid pressure supply, and link means connected to said housing and adapted to engage the spider for supporting the assembly against said pressure in a manner that simulates actual operating conditions, said cup-shaped part being supported against said pressure only by said connection with said spider.

4,294,110

TORQUE MEASURING SYSTEM FOR AN AIR TOOL

Hugh L. Whitehouse, Lyndhurst, Ohio, assignor to The Stanley Works, New Britain, Conn.

Filed Nov. 13, 1979, Ser. No. 93,111


Int. Cl.³ G01L 3/00

U.S. Cl. 73—862.23

4 Claims


1. In an air tool for setting threaded fasteners to a desired torque and having a rotary air motor adapted to be energized to accelerate a rotary output of the motor to a predetermined free-running no-load speed and which decelerates in response to increased fastener resistance at a rate proportional to the rate of rise in motor air pressure caused by an increase in

torque applied by the rotary output of the tool in setting a fastener, a torque measuring system comprising a torque indicator located in external remote relation to the air tool, tubing having one end serving as a probe located within the air tool for sensing motor air pressure, an air supply hose connected to the air tool, the tubing extending through an air supply passageway in the air tool and into the air supply hose to the torque indicator for delivering a motor air pressure signal to the torque indicator for sensing and indicating torque applied to a fastener by the rotary output of the tool, the torque indicator including a junction box having a pressure transducer mounted therein and air signal tubing connected thereto, the junction box including conduit therein connected to a supply of compressed air, a first quick-disconnect coupling between the air supply hose and the air tool for supplying air under pressure to said air supply passageway, the first coupling including a socket attached to one of the hose and air tool members and a complementary plug attached to the other of said members, the socket and plug having complementary internal connectors coupled to the tubing in the hose and air tool members of their respective socket and plug components, the internal connectors of the socket and plug being engageable in registered relation with one another for communicating the




tubing in the air tool with the tubing in the air supply hose simultaneously upon connecting the socket and plug for establishing the supply air connection between the supply air hose and the air tool, the socket and plug and their internal connectors serving to simultaneously disconnect the supply air and the motor pressure signal air between the air supply hose and the air tool upon disconnecting said first coupling, and a second quick-disconnect coupling between the air supply hose and the junction box, the second coupling including a socket attached to one of the hose and box members and a complementary plug attached to the other of the said members, the socket and plug having complementary internal connectors coupled to the tubing in the hose and box members of their respective socket and plug components, the internal connectors of the socket and plug being engageable in registered relation with one another for communicating the tubing in the hose with the tubing in the junction box simultaneously upon connecting the socket and plug for establishing the supply air connection between the supply conduit of the junction box and the air hose, the socket and plug and their internal connectors serving to simultaneously disconnect the supply air and the motor pressure signal air to the pressure transducer upon disconnecting said second coupling between the air hose and junction box.

4,294,111
PORTABLE FLUID INK TACK TESTER
 Wyman C. Rutledge; J. Robert Graves, both of Chillicothe, and William G. Cassill, McArthur, all of Ohio, assignors to The Mead Corporation, Dayton, Ohio
 Filed Feb. 6, 1980, Ser. No. 119,052
 Int. Cl.³ G01N 19/04
 U.S. Cl. 73—150 R 4 Claims



1. A portable fluid ink tack tester comprising:
 - (a) a manually portable frame having a longitudinal axis,
 - (b) first and second rolls,
 - (c) mounting means rotatably mounting said rolls on parallel axes of rotation on said frame and in rolling contact, with a predetermined pressure therebetween, and positioned with at least one of said rolls supported and extending outwardly from said frame to expose the surface thereof for contacting an ink coated surface and receiving an ink sample therefrom,
 - (d) rotating means including a drive shaft for controllably rotating said first roll at a predetermined speed,
 - (e) a rotating strain gauge mounted on said drive shaft for measuring the force supplied to said first roll by said rotating means, and
 - (f) means for displaying said measured force.


4,294,112
CLOSED TORQUE TEST MACHINE
 Ronald D. Moore, Lexington Park, and John W. Hall, Lusby, both of Md., assignors to The United States of America as represented by the Secretary of the Navy, Washington, D.C.
 Filed May 16, 1980, Ser. No. 150,381
 Int. Cl.³ G01M 13/02
 U.S. Cl. 73—162 14 Claims



1. Apparatus for testing mating splined parts under rotational torque load and axial misalignments comprising:
 - a first pair of rotatably connected shafts;
 - a second pair of rotatably connected shafts;
 - means generally coextensive with and interconnecting the shaft pairs to define a four-square arrangement;
 - means for inducing a locked-in static torque in the arrangement;

at least one of the shafts carrying one splined part to be tested;
 said interconnecting means carrying another splined part to be tested in mating torque load engagement with the first mentioned splined part;
 means driving the arrangement and;
 means for selectively positioning the splined part carried by the shaft out of concentricity with respect to the axis of shaft rotation;
 whereby upon rotation of the arrangement the mating splined parts are torque tested under load and selected axial misalignment.

4,294,113
ANTI-SURGE SYSTEM FOR GASES AND OTHER MEDIA
 Kenneth J. Sprott, Whitinsville, and George M. Herterick, Westborough, both of Mass., assignors to Dresser Industries, Inc., Dallas, Tex.
 Filed Feb. 4, 1980, Ser. No. 118,263
 Int. Cl.³ G01F 15/10
 U.S. Cl. 73—199 7 Claims




1. A device for preventing high pressure surges in fluidic material delivery systems to metering and measuring instruments comprising means for flowing the fluidic material to a normally closed pilot operated valve, means for diverting flow therefrom through a restrictor directly to said instruments, means for diverting flow therefrom through a restrictor to the pilot of the pilot valve to produce a time delay in total delivery of the fluidic material to the instruments.

5. A method for preventing high pressure surges in fluidic material delivery systems to metering and measuring instruments comprising flowing the fluidic material to a normally closed pilot operated valve, diverting flow therefrom through a restrictor directly to said instruments, further diverting flow therefrom through a restrictor to the pilot of the pilot valve to produce a time delay in total delivery of the fluidic material to the instruments.

4,294,114
APPARATUS FOR THE MEASUREMENT OF THE MASS OF A FLOWING MEDIUM
 Heinz Lauterbach, Esslingen, Fed. Rep. of Germany, assignor to Robert Bosch GmbH, Stuttgart, Fed. Rep. of Germany
 Filed Nov. 20, 1979, Ser. No. 96,113
 Claims priority, application Fed. Rep. of Germany, Apr. 1, 1979, 2900210
 Int. Cl.³ G01F 1/68 3 Claims

1. In an apparatus for measuring the mass of an air induced mass into an internal combustion engine, having at least one temperature-dependent resistor disposed in the flow of the medium, the temperature-dependent resistor including: a carrier; and a resistor film disposed on the carrier and in the flow of the medium, the temperature and/or resistance of the resistor film being governed by the mass of the flowing medium, and serving as the basis for the generation of a manipulated variable which is a standard for the mass of the flowing medium, the improvement comprising:


a preceding body having approximately the same cross-section as that of the carrier,
 said carrier extending longitudinally in the direction of the flow of the medium at least a portion of said resistor film disposed along said longitudinal direction, and
 said preceding body being aligned with the carrier directly



upstream thereof in the direction of the flow of the medium, and having a length in the direction of the flow of the medium such that a particular boundary layer state prevails about the temperature-dependent resistor and the heat-transfer coefficient of the resistor film is influenced by the preceding body in accordance with the mass of the flowing medium.

4,294,115
MEASURING DEVICE FOR PRACTICALLY SIMULTANEOUS ΔT AND T MEASUREMENT
 Herwig Labus, Jülich, Fed. Rep. of Germany, assignor to Kernforschungsanlage Jülich Gesellschaft mit beschränkter Haftung, Jülich, Fed. Rep. of Germany
 Filed Mar. 17, 1980, Ser. No. 130,849
 Claims priority, application Fed. Rep. of Germany, Mar. 17, 1979, 2910608
 Int. Cl.³ G01K 7/16 3 Claims

U.S. Cl. 73—342



1. A measuring device, for the practically simultaneous measurement of a temperature difference and an absolute temperature, comprising:

two temperature precision resistors for the two temperatures, and a reference resistor, one of said precision resistors being associated with said absolute temperature, and said resistors being connected in parallel;
 a common constant power source;
 current supply lines respectively connected with said resistors and said power source;
 time switches respectively provided in said current supply lines and with the aid of which power can be successively applied to said resistors from said power source with equal current pulses during specified time intervals;
 three capacitors respectively provided in parallel to said resistors;
 sense lines and differential switches respectively connected with said resistors and capacitors, said capacitors being sequentially chargeable, with the aid of a time window switching during time intervals lying within said current

pulse time intervals, over said sense lines and said differential switches, to the pulse voltages which fall at said resistors; and
switches for the transfer, within a subsequent time interval, to a fourth capacitor, of the voltage difference between the other precision resistor and said precision resistor associated with said absolute temperature, and to a fifth capacitor, of the voltage difference between said precision resistor associated with said absolute temperature and said reference resistor, said fourth and fifth capacitors being grounded on one side, and said voltage values being a measure for said temperature difference and said absolute temperature.

4,294,116

TEMPERATURE DETECTING CIRCUIT


Keizo Yamamura, Nagaokakyo, and Yasuo Ohashi, Kyoto, both of Japan, assignors to Omron Tateisi Electronics Co., Kyoto, Japan

Filed Mar. 14, 1980, Ser. No. 130,435

Int. Cl.³ G01K 7/20

U.S. Cl. 73—362 AR

6 Claims



1. A temperature detecting circuit comprising a three-wire temperature sensor module including a first, a second and a third terminal, a temperature responsive resistance, a first cable lead connected across said first terminal and one end of said temperature responsive resistance, a second cable lead connected across said second terminal and said one terminal of the temperature responsive resistance, and a third cable lead connected across said third terminal and the other end of said temperature responsive resistance, a first and a second power terminal across which a reference voltage is supplied, said first terminal being connected to said first power terminal, a first resistance connected across said third terminal and said second power terminal, a second and a third resistance connected in series across said second terminal and said second power terminal, the respective resistance values of said first, second and third resistances being such that a current flowing through said second cable lead is substantially equal to that of said third cable lead, a potential divider being connected across said first and second power terminals and having a movable contact, and a summing amplifying means for summing a first voltage appearing at a junction between said third terminal and said first resistance, a second voltage appearing at a junction between said second and third resistances and a third voltage appearing on said movable contact of the potential divider and for generating an output signal, said potential divider being designed so that a variation of said third voltage can be rendered equal to a variation of said first voltage corresponding to the resistance value of said temperature responsive resistance sensing a temperature.

4,294,117
SAMPLE CHARGER FOR A GAS CHROMATOGRAPH
Hansueli Buser, Arlesheim, and Peter E. Jordi, Basel, both of Switzerland, assignors to Ciba-Geigy Corporation, Ardsley, N.Y.


Filed Jan. 28, 1980, Ser. No. 116,139

Claims priority, application Switzerland, Feb. 8, 1979, 1243/79

Int. Cl.³ G01N 31/08

U.S. Cl. 73—864.85

12 Claims



1. A sample charger for introducing a test sample into a separating column of a gas chromatograph, comprising in combination: a tubular charging chamber for receiving a tubular container for the test sample; connection means at one end of said charging chamber for placing the interior thereof into communication with the separating column of a gas chromatograph; at least one inlet adjacent said one end of said charging chamber for the admission of a carrier gas thereinto; a lock disposed adjacent the end of said charging chamber remote from said connection means, said lock including a lock gate operable to open or close said chamber to atmosphere; a sample holder for introducing the tubular sample container from outside through said open lock gate and into said charging chamber, said sample holder including an open-ended insertion tube for lengthwise insertion into said charging chamber; receiving means disposed at said one end of said charging chamber for receiving the leading end of said insertion tube in sealing engagement therewith and for placing the interior of said insertion tube in communication with the separating column of the gas chromatograph through said connection means; holding means disposed at said leading end of said insertion tube for releasably holding the forward end of said tubular sample container within said insertion tube, said leading end of said insertion tube being sealed by the sample container held therein; a passage between the inner wall of said insertion tube and the outer wall of said sample container held in said insertion tube for flow of carrier gas into the open end of said sample container remote from said holding means; at least one inlet adjacent said leading end of said sample holder for the admission of carrier gas from said charging chamber into said passage; and releasable means for holding said insertion tube in sealing engagement with said one end of said charging chamber.

4,294,118

FULLY AUTOMATIC ULTRASONIC FLAW DETECTION APPARATUS


Toshio Shiraiwa; Hisao Yamaguchi, and Shigeaki Matsumoto, all of Amagasaki, Japan, assignors to Sumitomo Kinzoku Kogyo Kabushiki Kaisha, Osaka, Japan

Filed Oct. 29, 1979, Ser. No. 89,277

Int. Cl.³ G01N 29/04

U.S. Cl. 73—620

8 Claims



1. A fully automatic ultrasonic flaw detection apparatus comprising: a probe for transmitting and receiving ultrasonic waves in a testpiece; a probe holder having said probe mounted thereon; a probe scanner connected to said probe holder having a first motor for moving said probe holder back and forth on a first line parallel to the surface of the testpiece and parallel to the area which is to be tested for flaws, and a second motor for moving said probe holder back and forth on a second line perpendicular to said first line and parallel to the surface of the testpiece; an information processing unit connected to said probe scanner and said ultrasonic transmitting and receiving apparatus having a memory means and a display means (a) for generating drive signals for application to said motors of said probe scanner for moving said probe holder according to a predetermined repeating rough scanning pattern in one direction along a first line, then along a second line for a short distance and then along another first line in the opposite direction, (b) for storing in said memory means flaw detection data indicative of the position of said probe when said probe receives ultrasonic waves from the testpiece and the amplitude of said received ultrasonic waves is indicative of a flaw, (c) for determining the position and characteristics of flaws in the testpiece from said stored flaw detection data, (d) for generating drive signals for application to said motors of said probe scanner for moving said probe holder according to a predetermined repeating fine scanning pattern in the vicinity of the position of each flaw if any flaw position is determined, said pattern being in one direction along a second line, then along a first line for a short distance and then along another second line in the opposite direction; and (e) for displaying the position and characteristics of each such determined flaw on said display means.

4,294,119

ULTRASONIC APPLICATOR FOR ULTRASONIC SCANNING OF BODIES

Richard E. Soldner, Erlangen, Fed. Rep. of Germany, assignor to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany

Division of Ser. No. 694,608, Jun. 10, 1976, Pat. No. 4,163,394.

This application May 17, 1979, Ser. No. 39,951


Claims priority, application Fed. Rep. of Germany, Jun. 30, 1975, 2529112

The portion of the term of this patent subsequent to Aug. 7, 1996, has been disclaimed.

Int. Cl.³ A61B 10/00

U.S. Cl. 73—625

12 Claims



7. Apparatus for scanning internal body regions accessible through narrow acoustic apertures, which comprises: ultrasonic scanning means for sequentially directing converging ultrasonic beams along beam paths converging toward substantially a common point of convergence at a narrow acoustic aperture within the body such that the beams extend through the acoustic aperture and then diverge along successive scan lines forming a sector scanning configuration within an internal body region beyond the acoustic aperture, and means for predominantly utilizing ultrasonic echo signals produced in the sector scanning configuration beyond the point of convergence so as to predominantly provide an ultrasonic echo sectional view of the internal body region beyond such acoustic aperture, said ultrasonic scanning means comprising a housing having window means for transmitting the converging ultrasonic beams, each beam path within the housing having a length which is large in comparison to the distance of the point of convergence from the window means.

4,294,120

TORSIONAL VIBRATION MONITORING APPARATUS FOR ROTATING SHAFT SYSTEM

Ichiji Shima; Tatsuo Yamamoto; Shigeru Yoshibayashi; Hiroshi Teshima, all c/o The Kansai Electric Power Co., Inc., Technical Research Center of 2, Ichinotsubo 1-chome, Waka-cho, Amagasaki City, Osaka; Akio Hizume, 8-11, Naka-machi, 1-chome, Setagaya-ku, Tokyo; Tetsuo Iki, 1998-5, Yokoo-machi, Nagasaki City, Nagasaki Pref.; Takashi Yamamoto, 347, Motomurago, Tokitsu-cho, Nishisonogi-gun, Nagasaki Pref.; Kyojo Kanamori, 16-10, Shiraiwa-cho, Isahaya City, Nagasaki Pref., and Shigeo Tanaka, 39-27, Hokuyo-machi, Nagasaki City, Nagasaki Pref., all of Japan

Filed Jun. 8, 1979, Ser. No. 46,913

Claims priority, application Japan, Jun. 8, 1978, 53-69048


Int. Cl.³ G01N 29/04; G01H 1/10

U.S. Cl. 73—650

3 Claims

1. A torsional vibration monitoring apparatus for a rotating shaft system in which the torsional vibration of the rotating shaft system is monitored by estimating torsional vibration at arbitrary positions x_j of the rotating shaft system from torsional vibration detected at a certain position x_p of the rotating shaft system on the basis of the facts that a torsional vibration $Y(x,t)$ produced in a rotating shaft system is an accumulation of modal vibrations $Y_j(x,t)$ and that each modal vibration is a product of a vibration mode type $g_j(x)$ and a vibration mode

component $h(t)$, comprising a detector for detecting the torsional vibration at the certain position x_p of the rotating shaft system and an operator having a transfer characteristic for



converting the torsional vibration detected at the certain position x_p into the torsional vibration at the arbitrary position x_j of the rotating shaft system.

4,294,121

POSITION MEASURING SYSTEM

Kiyoshi Inoue, Tokyo, Japan, assignor to Inoue-Japax Research Incorporated, Yokohama, Japan


Filed May 11, 1979, Ser. No. 38,174

Claims priority, application Japan, Jun. 6, 1978, 53-77591[U]; Aug. 5, 1978, 53-95976; Aug. 5, 1978, 53-108225[U]; Dec. 22, 1978, 53-162352

Int. Cl.³ G01M 7/00

U.S. Cl. 73-662

29 Claims



28. A device for detecting a contact of a solid surface with a contact sensing probe on an elongated stylus assembly having a stylus in a position measuring system, said device comprising: support means for carrying said stylus assembly to advance said probe towards said solid surface; vibration means for imparting a small vibration to said stylus in the axial direction thereof to reciprocate repetitively said probe toward and away from said solid surface with an amplitude of 0.1 and 10 micrometers; and response means responsive to a modification in the mode of vibration of said stylus upon said probe establishing a predetermined contact or proximity relationship with said solid surface for producing an output signal.

4,294,122

FASTENER INCORPORATING ULTRASONIC TRANSDUCER

James C. Couchman, Fort Worth, Tex., assignor to General Dynamics Corporation, Fort Worth, Tex.

Filed Jul. 12, 1979, Ser. No. 57,059


Int. Cl.³ F16B 31/02; G01N 24/00

U.S. Cl. 73-761

29 Claims

27. A fastener, comprising: a shank having a head at one end and threads formed at the other end, a shallow opening formed in one end only of said fastener, an acoustic transducer located in said opening and perma-

nently secured therein with said transducer being acoustically coupled to said fastener, said transducer being located in said opening such that it may be used for pulse-echo measurements wherein said transducer is pulsed, a transducer signal is generated which travels from said transducer through said fastener to the end of said fastener opposite said opening and back to said transducer at least once, the distance between said transducer and said end of said



fastener opposite said opening being equal to a major portion of the length of said fastener such that when said signal is generated, it will travel through the entire gripping length of said fastener, including the portion of said shank next to said head, when traveling between said transducer and said end of said fastener opposite said opening,

said fastener being formed of metal with the portion of said fastener between said opening and said end of said fastener opposite said opening being of solid metal throughout.

4,294,123

TURBINE METER

Hiroiyuki Amemori, and Masao Yamada, both of Kawasaki, Japan, assignors to Tokico Ltd., Kawasaki, Japan


Filed Nov. 20, 1979, Ser. No. 96,186

Claims priority, application Japan, Nov. 22, 1978, 53-144885

Int. Cl.³ G01F 1/115

U.S. Cl. 73-861.92

5 Claims



1. A turbine meter comprising: an axle member supported by a support member within a conduit through which a fluid to be measured is passed and having a small-diameter axle part and an annular recess formed around said small diameter axle part between a pair of opposed faces; a longitudinal flow passage formed in said axle member; a plurality of discharge holes formed in said axle member to communicatively connect the annular recess and the flow passage, said discharge holes comprising a first discharge hole formed in said small-diameter part, and a second discharge hole having one end thereof open into said passage and the other end thereof open into one of said opposed faces; a supply pipe inserted into said conduit

through the wall thereof, functioning to supply a pressurized fluid from a pressurized fluid source disposed outside of said conduit to said flow passage in said axle member; a vane wheel comprising, a hub disposed around said axle member and within said annular recess with minute gaps therebetween, being adapted to rotate in a substantially noncontacting state relative to said small-diameter axle part, a plurality of vanes implantedly fixed at their respective root parts to said hub, said vane wheel being rotated by a portion of said fluid to be measured and flowing through said conduit; and at least one discharge passage opening at one end thereof at one of said pair of opposed faces for communication with said annular recess and at the other end thereof, into said conduit through which said fluid to be measured is passed at a position separate from said vanes of said vane wheel, one end of at least one discharge passage opening in the inner periphery of said opposed faces, and the pressurized fluid which has been discharged from said discharge holes into said annular recess being discharged by way of said discharge passage to said conduit through which said fluid to be measured is passed at a position separated from said vanes.

4,294,124

APPARATUS FOR EXTRACTION OF MATERIALS FROM OPERATING PRESSURIZED VESSELS


George V. Kalwaitis, Gulf Breeze, Fla., assignor to Air Products and Chemicals, Inc., Allentown, Pa.

Filed Apr. 10, 1980, Ser. No. 139,073

Int. Cl.³ G01N 1/10

U.S. Cl. 73-863.85

8 Claims



1. A sampling apparatus for withdrawing and collecting samples from an operating pressure vessel without disturbing a reaction in said pressure vessel and while maintaining physical conditions of said sample, which apparatus comprises:

- a pressure vessel having an aperture;
- a first valve attached to said vessel and aligned with said aperture;
- a first tube having a sealed end and an open end;
- a second valve attached to said open end of said first tube and removably attached to said first valve;
- a second tube coaxially oriented within said first tube, said second tube having a perforated end for receiving a sample from said vessel; and
- means for sliding said perforated end of said second tube in and out of said second valve, said first valve, and said pressure vessel.

4,294,125

PIPETTE CONTROLLER WITH GRADUATE READING PLUNGER AND LEVER ASSEMBLY FOR GRAVITY DRAINAGE

Tsao-Piao Lee, No. 89-1, Chang Chun Rd. 2nd Floor, Taipei, Taiwan

Filed Apr. 24, 1980, Ser. No. 143,270


Int. Cl.³ B01L 3/02

U.S. Cl. 73-864.15

6 Claims

1. A pipette controller comprising: a cylinder; a piston disposed in said cylinder;

a threaded rod operatively coupled to said piston; a spring arranged in said cylinder between the bottom thereof and said piston for biasing said piston to a predetermined position; a cylinder cap having a hole therein, said cap being coupled to said cylinder; a graduate reading plunger in thread engagement with said threaded rod and disposed through said hold in said cylinder cap; sealing means including a port for receiving the end of a pipette, the sealing means being disposed at the bottom of the cylinder for sealing the end of the pipette to the con-



troller and placing the interior of the pipette in communication with a chamber defined by the piston and cylinder, said cylinder having a port for communicating with the atmosphere via a channel;

an operable lever assembly adapted to selectively close the port of said channel, said operable lever assembly including a lever arm including a pair of lugs and a seal pad for selectively sealing said channel, a member having a pair of claws for engaging the lugs of said lever arm and projection means for providing a fulcrum for said lever arm, said controller providing natural drainage when the end of the lever arm remote from said pair of lugs is biased toward said cylinder.

4,294,126

SAMPLE FEEDING DEVICE

Toma Tomoff; Wolfgang Chlosta, both of Überlingen; Heinz Henninger, Owingen; Rolf Tamm, Salem, and Klaus Grossmann, Owingen, all of Fed. Rep. of Germany, assignors to Bodenseewerk Perkin-Elmer & Co., GmbH, Fed. Rep. of Germany


Filed Dec. 12, 1979, Ser. No. 102,704

Claims priority, application Fed. Rep. of Germany, Jan. 2, 1979, 2900066

Int. Cl.³ G01N 35/04, 35/06

U.S. Cl. 73-864.21

9 Claims



1. Sample feeding device for automatically feeding samples into a graphite tube atomizer provided with a sample inlet opening, comprising: a turntable adapted to accommodate a circular array of liquid vessels, said turntable including a turntable position

sensor connected to said turntable, which sensor supplies a turntable position signal to a control device;

a turntable servomotor for driving said turntable, said turntable being arranged to be rotated by said turntable servomotor into positions determined by the program of said control device only and monitored by said turntable position signal;

a carrier, pivotably movable relative to an instrument base plate, is arranged to carry said turntable and said turntable servomotor, said carrier being arranged to be displaced by a separate carrier servomotor, said carrier having a carrier position sensor affixed thereto for applying a carrier position signal to said control device;

an intake tube movable between a first position and a second position by means of an intake tube servomotor, said intake tube, in its first position, dipping with one end into a respective liquid vessel located in an operative position, and, in its second position, extending with said one end into said sample inlet opening of said graphite tube atomizer;

a control device, adapted to control said intake tube servomotor, said turntable servomotor and said carrier servomotor in accordance with a certain program such that liquids from different liquid vessels are sucked into said intake tube and are discharged into said graphite tube atomizer and that in one position of said carrier said further liquid vessel is located below said intake tube when said intake tube is in its first position.

4,294,127

AUTOMATIC SAMPLE FEEDER FOR FLAMELESS ATOMIC ABSORPTION SPECTROMETER

Toma Tomoff, Überlingen, Fed. Rep. of Germany, assignor to Bodenseewerk Perkin-Elmer & Co., GmbH, Fed. Rep. of Germany


Filed May 29, 1980, Ser. No. 154,208

Claims priority, application Fed. Rep. of Germany, Jun. 15, 1979, 2924124

Int. Cl.³ G01N 35/06

U.S. Cl. 73—864.21

4 Claims



1. In combination with an atomic absorption spectrometer having a heatable sample atomizer with an aperture for receiving an injected liquid sample, an automatic sample feeding apparatus comprising:

- a rotatable turntable having therein a plurality of fluid containing vessels;
- an intake tube having a first end movable between a first position at said turntable and a second position at the aperture of the sample atomizer;
- pumping means connected with the second end of said intake tube, said pumping means for drawing in and injecting fluids from said first end of said intake tube; and
- control means coupled to said turntable, said first end of said intake tube, and to said pumping means for respectively positioning a selected one of said vessels on said turntable under said first intake tube end, dipping said first end into said selected vessel, drawing a fluid sample therefrom, transferring said first end to said second position at said sample aperture, and injecting said fluid sample therein;

the improvement comprising:

said fluid containing vessels are overflow vessels having at least one fluid overflow aperture in the wall thereof;

an input conduit couples each of said overflow vessels with a source of fluid; and

an annular drain channel is positioned under said turntable, said drain channel forming a housing for said turntable and providing a waste fluid outlet for fluids from said overflow vessels.

4,294,128

DEVICE FOR ERECTING AND STABILIZING A GYRO VERTICAL

Peter Giesenberger, Uhldingen-Mühlhofen, Fed. Rep. of Germany, assignor to Bodenseewerk Gerätetechnik GmbH, Überlingen, Fed. Rep. of Germany


Filed Jan. 23, 1979, Ser. No. 6,079

Claims priority, application Fed. Rep. of Germany, Sep. 6, 1978, 2838740

Int. Cl.³ G01C 19/50

U.S. Cl. 74—5.44

16 Claims



1. Device for erecting and stabilizing of a gyro vertical, comprising a disc arranged on the gyro housing and perpendicular to the gyro axis, said disc being driven in the same sense as the gyro rotor but at a reduced rate as compared thereto, and having at least one guideway, in which a mass is movably guided, the guideway being arranged such that the disc with the mass is balanced with respect to the gyro axis, when the mass abuts the rear end, with respect to the rotary movement, of the guideway, and that the movement of the mass in the guideway causes an erecting torque, when the gyro spin axis deviates from the vertical direction observed,

characterized in that the guideway (40,42;90,92;130,132) is generally S-shaped and extends from one end (82,84;106,108) located near the edge of the disc (14,88;128) around the gyro spin axis (16) to an end (60,62;110,112) located near the gyro spin axis (16).

4,294,129

CONTROL LEVER OF ELECTRICAL STARTER

Alfred B. Mazzorana, Venissieux, France, assignor to Societe de Paris et du Rhone, Lyons, France

Filed Mar. 19, 1979, Ser. No. 24,212

Claims priority, application France, Jul. 29, 1977, 77 24135

Int. Cl.³ F02N 11/00


U.S. Cl. 74—7 A

4 Claims

1. A control lever assembly for a starter for an internal combustion engine, the assembly being supported in a starter casing and the lever having one end cooperating with the core of a starter solenoid and having a second end actuating a starter gear, the assembly comprising:

- (a) an elongated lever arm extending between said two ends and comprising two flat arm portions disposed normal to said pivot means and joined together by a web portion extending transversely therebetween;
- (b) the casing having internal depressions disposed transversely of the lever intermediate its ends;
- (c) pivot means located in and extending across said depressions and pivotally supporting the lever in the casing; and

said pivot means comprising two rivet members each having a head shaped to fit into a depression in the casing and each having a cylindrical body portion extending through a pivot hole in an arm portion;



- (d) said one end of said lever having an arcuate member located thereat; and
- (e) rod means pivotally connected to the lever at said arcuate member and extending toward and coupled to said core to pivot the lever when the solenoid is actuated.

4,294,130

TRANSMISSION FOR TRACTOR

Hiroyuki Kisaka, Sennan; Makoto Sagata, Kaizuka; Masayoshi Miyahara, and Morimitsu Katayama, both of Sakai, all of Japan, assignors to Kubota Ltd., Japan


Filed Apr. 5, 1978, Ser. No. 893,757

Claims priority, application Japan, Apr. 27, 1977, 52-51031

Int. Cl.³ F16H 37/00

U.S. Cl. 74—15.4

9 Claims



- 1. A transmission for a tractor, comprising:
- a main shaft to receive engine power;
- a travelling speed change shaft disposed in parallel with said main shaft;
- a PTO speed change shaft disposed in parallel with said two shafts;
- a first travelling speed change means of a hydraulic clutch type mounted on said travelling speed change shaft and having travelling speed change input gears;
- a PTO speed change means of a mechanical clutch type mounted on said PTO speed change shaft and having plural PTO speed change gears;
- a plurality of power transmission gears fixed on said main shaft for transmitting power to said travelling speed change input gears and said PTO speed change gears with at least one of said power transmission gears serving as a dual-purpose transmission gear to transmit power not only to one of said travelling speed change input gears but also to one of said PTO speed change gears;
- a second travelling speed change means of a hydraulic clutch type connected to a rear end of said main shaft and having travelling speed change output gears, said second travelling speed change means being so constructed that, in response to power input from said main shaft, a clutch

function thereof is performed prior to a speed change function thereof; and

a plurality of travelling speed change gears fixed on said travelling speed change shaft and engaged with said travelling speed change output gears of said second travelling speed change means.

4,294,131

TRACTOR TRAVELLING SYSTEM TRANSMISSION MECHANISM

Yoshinobu Murayama, Sakai, Japan, assignor to Kubota, Ltd., Osaka, Japan


Filed May 26, 1978, Ser. No. 909,790

Claims priority, application Japan, Nov. 10, 1977, 52-135811

Int. Cl.³ F16H 37/00, 37/06

U.S. Cl. 74—15.4

4 Claims



- 1. A tractor transmission comprising a transmission case (3) extending longitudinally of a tractor body,
- a main shaft (11) extending longitudinally in the transmission case (3) and operatively connected to an engine (1),
- friction type stepless transmission means (12) disposed above said main shaft (11) and in a front position within the transmission case (3) and interlocked with the main shaft (11),
- a planet reduction gearing (13) mounted on the main shaft (11) and rearwardly of the friction type stepless transmission means (12) and including a first component element (28) interlocked with the main shaft (11), a second component element (27) interlocked with the stepless transmission means (12) and a third component element (29) in engagement with the first and second component elements (28, 27), a forward/reverse changeover gearing (14) disposed beneath the main shaft (11) and rearwardly of the planet reduction gearing (13) and operatively connected to the third component element (29),
- a differential gearing (16) disposed in a rear and lower position within the transmission case (3) and interlocked with the forward/reverse changeover gearing (14),
- hydraulic means (21) disposed in a rear and upper position within the transmission case (3), and
- a power-take-off shaft (8) disposed in a rear end position of the transmission case (3) and operatively connected to the main shaft (11), whereby a space is defined beneath said main shaft (11) and in a front position within said transmission case (3), said space housing a hydraulic pump (19) connected to said main shaft (11) for actuating said hydraulic means (21).

4,294,132

CYLINDRICAL GEAR WITH HELICAL TEETH

Zbigniew Matusz, Warsaw, Poland, assignor to Fabryka Obrabiarek Precyzyjnych "Ponar-Bruszkow", Pruszkow, Poland

Filed Sep. 25, 1978, Ser. No. 946,208

Claims priority, application Poland, Sep. 29, 1977, 201127


Int. Cl.³ F16H 55/08

U.S. Cl. 74—462

3 Claims

- 1. A cylindrical gear wheel comprising helical teeth having

left and right hand sides with different pitch diameters (d_L and d_R), different angles of helix inclination (β_{OL} and β_{OR}), different nominal diameters (d_Z) and different profile face angles



(xm_n) within at least a range of normal tooth module (m_n) varying from 2 up to 6 mm as the angular difference of inclination ($2\Delta\beta$) between the left hand (β_{OL}) and right hand (β_{OR}) sides varies within the range of 30° and 3° .

4,294,133

BOWDEN CABLE RETAINER AND ADJUSTER


John J. Hurley, Livonia, Mich., assignor to Ford Motor Company, Dearborn, Mich.

Filed Sep. 24, 1979, Ser. No. 78,130

Int. Cl.³ F16C 1/06

U.S. Cl. 74—501 P

9 Claims



1. A Bowden cable and an adjustable connector assembly for securing and positioning a Bowden cable with respect to a support member, said adjustable connector assembly including:

a grooved sleeve means attached to said Bowden cable, said grooved sleeve means being generally elongated along the axis of said Bowden cable and having circumferential grooves spaced along the Bowden cable axis;

a mounting assembly means for attaching said grooved sleeve means to the support member, said mounting assembly means including a clip means and an adjuster means for securing therebetween said grooved sleeve means;

said clip means and said adjuster means being adapted to mate laterally to said sleeve means and including a first connector means and a second connector means, respectively, for releasably attaching said clip means to said adjuster means sufficiently snugly so as to securely, longitudinally position said mounting assembly means with respect to said grooved fitting;

said first connector means having an inclined, ratchet like protrusion and said second connector means having a slotted, flexible finger for receiving said protrusion;

said clip means including ridges for mating with said grooves thereby providing a means to secure the longitudinal position of said mounting assembly means and said sleeve means;

said adjuster means including an opening for passing a securing member, such as a screw, for attaching said adjuster means to the support member; and

said first connector means including a concave arc portion

with said ridges positioned thereon to mate with the grooved exterior surface of said sleeve means, and a first leg extending down from an end of said concave portion, an interior surface of said first leg including said ridges and an exterior surface of said first leg including said protrusion.

4,294,134

ACTUATING HANDLE MEANS

Keiji Mori, and Kyoichi Kurimoto, both of Toyota, Japan, assignors to Aisin Seiki Kabushiki Kaisha, Kariya and Toyota Jidosha Kogyo Kabushiki Kaisha, Toyota, both of, Japan


Filed Jun. 22, 1979, Ser. No. 51,233

Claims priority, application Japan, Jun. 23, 1978, 53/76074

Int. Cl.³ G05G 1/00

U.S. Cl. 74—547

7 Claims



1. Foldable actuating handle means for vehicles which comprises base plate means adapted to be engaged with actuating shaft means to rotate therewith, actuating handle lever means provided with an actuating knob and having one end pivotally connected with said base plate means at a position remote from said actuating knob for movement between extended and folded positions, resilient spring means mounted on said base plate means and having one end constrained by said base plate means at a position diametrically opposite to the position where the actuating handle lever means is pivotally mounted on the base plate means, the resilient spring means having its other end adapted to resiliently bias the one end of the actuating handle lever means, said actuating handle lever means being formed at said one end with a pair of spaced seat surfaces which are adapted to be operatively engaged with said other end of the resilient spring means in the extended and folded positions, respectively, said spring means being deflected from its free position when its other end is operatively engaged with either of said spring seat surfaces, said actuating handle lever means being further formed with an intermediate projection between said spring seat surfaces so that the spring means is overridden when the actuating handle means is moved between the extended and folded positions.

4,294,135

TURBOMACHINE BALANCE CORRECTION SYSTEM

Robert P. Tameo, Peabody, Mass., assignor to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Jan. 12, 1979, Ser. No. 4,248

Int. Cl.³ F16F 15/22

U.S. Cl. 74—573 R


12 Claims

1. A balancing system comprising in combination:

a rotor rotatable about an axis;

at least a pair of balancing rings mounted for rotation with said rotor, each of said balancing rings is provided with a radially extending tab; and

a plurality of axial retention locations positioned on said rotor in the form of axial slots parallel the axis, said tabs of said crank shaft, and said rotatable member being in the form of a truncated cone-shaped clamping disc conforming in shape to said truncated cone-shaped recess.



said balancing rings are oriented in selected axial retention locations for providing balance correction.

4,294,136

CRANK GEAR WITH ADJUSTABLE CRANK RADIUS FOR MOTOR DRIVEN WORKING IMPLEMENTS

Martin Greppmair, München-Lerchenau, and Wittloff Grünwald, Pielenhofen, both of Fed. Rep. of Germany, assignors to Wacker Werke GmbH & Co. KG, Munich, Fed. Rep. of Germany


Filed Jan. 2, 1979, Ser. No. 485

Claims priority, application Fed. Rep. of Germany, Dec. 30, 1977, 2758989

Int. Cl.³ F16C 3/04

U.S. Cl. 74—600

9 Claims



1. A crank gear with adjustable crank radius for motor driven beating, working implements, especially tamping implements, jack hammers and hammer drills which includes: a housing, a crank shaft rotatably journaled in said housing, said crank shaft having a first end section and an axially oppositely located second end section, a crank disc connected to said first end section for rotation therewith and having an outer periphery provided with teeth, driving gear means meshing with said teeth and drivingly connectable to a prime mover for rotating said crank disc, a rotatable member associated with said crank disc and operable to move into a first position for engagement with said crank disc and also operable to move into a second position for disengagement from said crank disc, a crank pin mounted on said rotatable member for connection to a connecting rod, said rotatable member having an axis of rotation eccentrically arranged with regard to the axis of rotation of said crank disc, and control means associated with said second end section and operatively connected to said rotatable member for selectively moving the same into said first position or into said second position, said control means including spring means urging said rotatable member into said first position, that end face of said crank disc which faces away from said second end section being provided with a truncated cone-shaped recess the extension of which has the longitudinal axis

4,294,137

TRANSMISSION WITH VARIATOR

Jean Piret, Bougival, and Michel Jallas, Garches, both of France, assignors to Regie Nationale Des Usines Renault, Boulogne-Billancourt, France


Filed Mar. 16, 1979, Ser. No. 21,171

Claims priority, application France, Mar. 16, 1978, 78 07643

Int. Cl.³ F16H 37/06

U.S. Cl. 74—665 G

7 Claims



1. An automotive vehicle transmission having both variable transmission ratios and constant transmission ratios, said transmission being coupled to an automobile engine and comprising: a variator providing a predetermined range of variable transmission ratios and including a primary shaft driven by said engine, a plurality of driving sheaves carried by said primary shaft, a plurality of driven sheaves, and a secondary shaft supporting said driven sheaves; and a constant ratio direct drive located between said engine and said variator and providing a constant transmission ratio different from said predetermined range of variable transmission ratios; wherein the engagement of said constant ratio direct drive releases said variator and the engagement of said variator releases said constant ratio direct drive, whereby said transmission provides an increased range of ratios for a given size variator.

4,294,138

TWO STAGE TRANSMISSION HUB FOR A BICYCLE

Seiji Fukui, Sakai, Japan, assignor to Shimano Industrial Company, Limited, Osaka, Japan

Filed Jul. 19, 1979, Ser. No. 58,735

Claims priority, application Japan, Jul. 21, 1978, 53-101296[U]; Jan. 30, 1979, 54-1125[U]

Int. Cl.³ F16H 3/44; F16D 41/02

U.S. Cl. 74—750 B

4 Claims

1. A two stage transmission hub for a bicycle, comprising:


(a) a hub shaft;

(b) a hub body rotatably supported to said hub shaft, said hub body being provided at both axial ends thereof with hub end portions having flanges respectively, one of said hub end portions having a cylindrical extension extending axially outwardly of one of said flanges, said cylindrical extension supporting at a substantially intermediate portion thereof freely rising and falling transmitting pawls;

(c) a sun gear provided at the outer periphery of said hub shaft at a position axially outwardly of said cylindrical extension;

(d) a gear frame having planetary pinions in mesh with said sun gear, said gear frame being supported rotatably to said hub shaft and being positioned axially outwardly of said cylindrical extension and arranged axially in series thereto;

- (e) a unidirectional rotary transmission mechanism for transmitting one-directional rotation of said gear frame to said cylindrical extension;
- (f) a cylindrical driving member covering the outer peripheries of said cylindrical extension and gear frame, said driving member being provided at the inner periphery of an axially inside portion thereof with ratchet teeth in mesh with said transmitting pawls, at the inner periphery of an axially outside portion thereof with inner teeth in mesh



with said planetary pinions, and at the outer periphery thereof with at least one sprocket;

- (g) a pair of first and second bearing means for rotatably supporting said driving member, said first bearing means being provided on said cylindrical extension, said second bearing means being provided on said hub shaft; and
- (h) a control member for controlling said transmitting pawls to cause their engagement with and disengagement from said ratchet teeth, said control member being supported to said hub shaft so as to be axially movable.

4,294,139

DRIVE FOR A MACHINE COMPRISING VARIABLE-STROKE RECIPROCATING PISTONS

Peter T. J. Bex, and George A. A. Asselman, both of Eindhoven, Netherlands, assignors to U.S. Philips Corporation, New York, N.Y.

Filed Nov. 30, 1979, Ser. No. 99,182

Claims priority, application Netherlands, Jan. 5, 1979, 7900076

Int. Cl.³ F16H 35/08; F01B 13/04

U.S. Cl. 74—839

6 Claims

6. A drive for a machine having variable-stroke reciprocating pistons, comprising:

- a shaft having an axis, said shaft being rotatably journaled in the machine;
- a plate, mounted on the shaft so that the plate cannot rotate with respect to the shaft around the shaft axis, said plate being mounted on the shaft so that the angle between the plate and the shaft axis can be varied, by pivoting the plate around a plate axis, and so that the plate is movable along the direction of the shaft axis;
- at least one piston comprising a piston rod having a piston rod head, said piston rod head having a side which faces the plate comprising a spherical surface; and
- means for slideably coupling the spherical surface of the piston rod head to the plate;


CHARACTERIZED IN THAT

the plate has a side which is remote from the piston rod, said side comprising a cam having a cam surface;

the drive further comprises a structural member, rigidly coupled to the shaft, for supporting the cam via the cam surface;

said cam has a cross section which passes through said cam surface and which is substantially at least a portion of a

circle having an axis which is parallel to the plate axis, the axis of said circle passing through the center of curvature



of said spherical surface of the piston rod head when the piston rod is situated opposite the cam.

4,294,140

HYDRAULIC TORQUE CONVERTER CONTROL SYSTEM

Kazuyoshi Iwanaga, Yokohama; Kazuhiko Sugano, Tokyo, and Kunio Ohtsuka, Yokohama, all of Japan, assignors to Nissan Motor Company, Limited, Yokohama, Japan

Filed Jan. 23, 1979, Ser. No. 5,892

Claims priority, application Japan, Sep. 4, 1978, 53-107529

Int. Cl.³ B60K 41/10; F16H 47/00; F16D 33/00

U.S. Cl. 74—868

4 Claims



1. A hydraulic control system for a vehicular automatic transmission including fluid operable units and a torque converter with a lock-up clutch, comprising:

- a source of first pressurized fluid adapted to be used for operating the fluid operable units;
- a source of second pressurized fluid that is indicative of the vehicle speed;
- a lock-up control valve communicating with the torque converter and including a single control chamber and a valve member exclusively movable in response to pressure within said control chamber, said valve member being movable between a lock-up position in which the lock-up clutch is engaged and a release position in which the lock-up clutch is disengaged;

and

a shift valve communicating with said source of first pressurized fluid and with at least one of the fluid operable units, said shift valve including a chamber having a first port communicating with said source of second pressurized fluid, a second port communicating with said control chamber of said lock-up control valve and a port for drainage, said shift valve including a valve member mov-

able between a low speed position in which said second port communicates only with said port for drainage and a



high speed position in which said second port communicates only with said first port.

4,294,141

TOOL AND METHOD FOR HOLDING AUTOMOTIVE VALVES CLOSED DURING SERVICING


Ronald J. Miller, 4681 Lake Ave., Blasdell, N.Y. 14219

Filed Oct. 30, 1979, Ser. No. 89,406

Int. Cl.³ B25B 11/00; B23P 19/00

U.S. Cl. 81—3 R

7 Claims



1. An automotive tool for engagement with overhead valves to retain them in seated positions while working on the valve associated structure which is external of the automotive combustion chamber to prevent valves from falling into said chamber when released from such structure, said tool comprising an elongate tubular member having an inflatable balloon at one end thereof adapted to be projected through a spark plug opening into the combustion chamber, said balloon being of such form as to substantially fully occupy said chamber upon inflation thereof, means at the other end of said tubular member for supplying air pressure to said balloon through said tubular member and control valve means for selectively con-

necting said air pressure means to said balloon for inflating the latter to bear upwardly against the valves and for subsequently venting the tool to deflate the same and withdraw the balloon, and means for connecting the tool to the spark plug opening.

4,294,142

AUTOMATIC SCREWDRIVER

Syunji Sugahara, Osaka, and Takao Morimoto, Kadoma, both of Japan, assignors to Matsushita Electric Industrial Company, Limited, Osaka, Japan


Filed Jan. 10, 1980, Ser. No. 111,073

Claims priority, application Japan, Jan. 20, 1979, 54-5005

Int. Cl.³ B25B 23/06

U.S. Cl. 81—57.37

3 Claims



1. An automatic screwdriver having a power unit, comprising: a first cylindrical member having a bore extending therethrough, a hand grip portion, a guide portion and a contacting surface portion between said hand grip and guide portions, a hand-operated lever pivotally mounted on said hand grip portion; a screw driving bit adapted to be rotatably driven by said power unit under the control of said hand-operated lever; a second cylindrical member mounted to telescope over said guide portion; means for biasing said second cylindrical member away from said first cylindrical member; a feeder tube connected at one end to a front end of said second cylindrical member at an angle thereto for feeding a bolt or the like to the front end of said second cylindrical member; a third cylindrical member extending over said guide portion and movably mounted on said second member and having a contacting surface engageable with the contacting surface of said contacting surface portion; manually operable means for providing pressure contact between said contacting surfaces to couple said first and second cylindrical members together, said manually operable means being operable to decouple said contacting surfaces to allow said second cylindrical member to rotate manually to a desired angular position with respect to said first cylindrical member; and means for coupling said second and third cylindrical members to provide unitary rotation about their axes when said first and second cylindrical members are decoupled from one another and to allow said second cylindrical member to telescope with respect to said third cylindrical member.

4,294,143

METHOD AND APPARATUS FOR CUTTING INTO SEGMENTS A CONTINUOUSLY MOVING WEB OF RIGID INSULATION

Abraham Lieberman, 4555 Bonavista Ave., Apt. 31, Montreal, Quebec, Canada (H3W 2C7)

Filed Oct. 23, 1979, Ser. No. 87,499

Int. Cl.³ B26D 1/18, 1/24, 1/56


U.S. Cl. 83—37

28 Claims

8. Apparatus for transversely cutting into predetermined lengths, a continuous strip-like web, the web being conveyed along its longitudinal axis, the apparatus comprising:

- (a) means for simultaneously engaging and cutting into the moving web at both major web surfaces, said means including at least one pair of cooperating first and second blades;
- (b) means for simultaneously transporting said blade pair transversely across the web and longitudinally in the direction of conveyance of the web, said transporting means including

- (1) first travelling carriage means positioned adjacent one major surface of the web and oriented to traverse the web along a first carriage path disposed at a first angle to the longitudinal axis of the web, said first travelling carriage means carrying said first blade;
- (2) second travelling carriage means positioned adjacent the other major surface of the web and oriented to traverse the web along a second carriage path disposed at a second angle to the longitudinal axis of the web, said second travelling carriage means carrying said second blade;
- (3) means for synchronizing the speed of said first travelling carriage means with the speed of said second travelling carriage means wherein said first blade cooperates with second blade to provide mutually opposing forces biasing the web against the cutting action of each



- of said cooperating blades for completely severing the web through its thickness; and
- (c) means associated with said transporting means for aligning each blade of said blade pair such that the plane of the respective blade is perpendicular to the longitudinal axis of the web, wherein said transporting means includes first and second stationary frame means positioned adjacent the opposite major web surfaces, and wherein said first and second travelling carriage means include, respectively, first and second endless belt means supported in said respective frame means to span the web along respective ones of said first and second carriage paths, and wherein said aligning means includes a plurality of assemblies for holding the individual blades of said blade pair, said blade-holder assemblies being attached to the respective ones of said first and second endless belt means.

4,294,144

APPARATUS FOR CUTTING SHEET MOLDING COMPOUND


Richard H. Hayes, Tallmadge, Ohio, assignor to Eagle-Picher Industries, Inc., Cincinnati, Ohio

Filed Nov. 7, 1979, Ser. No. 91,968

Int. Cl.³ B26D 5/02, 9/00

U.S. Cl. 83—71

4 Claims



1. Apparatus for cutting sheet molding compound carried on a liner comprising,
 - a conveyor for carrying compound and liner,
 - a plurality of transversely adjustable slitting knives engage-

able with said compound to form longitudinal slits in said compound to form strips of selectively variable width, a transversely movable knife engageable with said compound to cut said strips into preselected lengths, means for separating said liner from said compound upstream of said transverse knife and returning it to said compound downstream of said knife, anvil means against which said knife presses said compound to cut the same, said anvil means being located between said liner and compound, means for detecting the longitudinal distance of movement of said compound, and means for automatically operating said knife after a preselected length of compound passes under it.

4,294,145

MACHINE FOR THE CROSSCUTTING OF A WEB CONVEYED AS A MULTI-PLY WEB

Jakob Bodewein, Monchen-Gladbach, Fed. Rep. of Germany, assignor to Jagenberg Werke AG, Dusseldorf, Fed. Rep. of Germany


Filed Apr. 10, 1980, Ser. No. 138,775

Claims priority, application Fed. Rep. of Germany, Apr. 30, 1979, 2917582

Int. Cl.³ B26D 1/62

U.S. Cl. 83—302

5 Claims



1. A machine for the crosscutting of a multi-ply web, comprising: a crosscutter; means preceding the crosscutter in the direction of web travel for guiding the plies of the web; means disposed between the web guiding means and the crosscutter for feeding the multi-ply web to the crosscutter comprising a pair of rolls; and means for compensating for the differences in sheet lengths of the various plies cut by the crosscutter comprising means mounting the web guiding means for pivotable movement as a unit about the axis of one of the two rolls of the feeding means and means for fixing the web guiding means in a selected position in the path of motion thereof.

4,294,146

OSCILLATION TYPE FLYING SHEAR

Yukio Ohtake, Hitachi, Japan, assignor to Hitachi, Ltd., Tokyo, Japan


Filed Apr. 1, 1980, Ser. No. 136,248

Claims priority, application Japan, Dec. 3, 1979, 54-155670

Int. Cl.³ B26D 1/56

U.S. Cl. 83—316

5 Claims



1. An oscillation type flying shear comprising: a main crank shaft driven by drive means;

a frame pivotally supported by a first eccentric portion of said main crank shaft;

an upper cutting blade secured to said frame;

a lower cutting blade holder pivotally secured to a second eccentric portion of said main crank shaft and slidably attached to said frame;

a lower cutting blade secured to said lower cutting blade holder;

gearing for transmitting the rotational force of said drive means to an oscillating crank; and

a link for transmitting the eccentric movement of said oscillating crank to said frame as a pivotal movement; the improvement comprising means for adjusting the gear meshing position of gears of said gearing.

4,294,147

TUBE CUTTING APPARATUS


John J. Borzym, 4820 Schoolbell La., Birmingham, Mich. 48010

Filed Feb. 7, 1980, Ser. No. 119,241

Int. Cl.³ B23D 21/00

U.S. Cl. 83—382

24 Claims



1. Apparatus for clamping a workpiece, comprising: a pair of opposed, complementary die jaws; first and second slide means respectively mounting said die jaws for sliding movement toward and away from each other between an open release position and a closed clamping position; first and second cam followers; and means for respectively mounting said first and second cam followers on said first and second slide means, including means for allowing selective adjustment of the distance between said die jaws, said adjustment means including
 - (1) selectively rotatable eccentric shaft means on said first slide means for rotatably mounting said first cam follower on said first slide means, said eccentric shaft means being operative upon rotation thereof to shift the position of said first cam follower whereby to adjust the distance between said die jaws, and
 - (2) means coupled with said eccentric shaft means for locking said eccentric shaft means in a selected rotational position thereof corresponding to a desired adjustment of said distance between said die jaws.

4,294,148

GUARDS FOR CIRCULAR SAW BLADES OF CIRCULAR SAWING MACHINES

Karl Drixler, Nürtingen-Neckarhausen, Fed. Rep. of Germany, assignor to Chr. Eisele Maschinenfabrik GmbH. & Co. KG, Fed. Rep. of Germany

Filed Dec. 10, 1979, Ser. No. 102,122

Claims priority, application Fed. Rep. of Germany, Dec. 16, 1978, 7837368[U]


Int. Cl.³ B27B 5/29

U.S. Cl. 83—397

9 Claims

1. A guard for the circular saw blade of a circular sawing machine whose sawing unit has a horizontally supported saw spindle and is disposed on a frame of the machine so as to be vertically movable, the guard being arranged to cover the circular saw blade from above and at least partially on an

accessible end face thereof and on the circumferential portion of an operating side, the guard forming a housing arranged to be mounted on the machine frame so as to be fixed relative to the circular saw blade with the latter in an upper starting position, said housing being open at its bottom only and, with said saw blade in its upper starting position, said housing completely accommodating the circular saw blade, a downwardly extended elongate opening being disposed in a side wall of the housing to accommodate the saw spindle and being associated with a covering element arranged to move between a covering



position, in which the covering element covers at least one region having disposed therein the circumference of the circular saw blade and being associated with the part of the elongate opening disposed beneath the saw spindle when the circular saw blade is in the upper starting position, and a released position, the covering element operating toward said released position and progressively exposing the said part of the elongate opening when feed motion of the circular saw blade is performed, the saw spindle traveling within the elongate opening during such feed motion.

4,294,149

APPARATUS FOR MEASURING AND ORIENTING LOGS FOR SAWING


Lars J. Olsson, Linköping, Sweden, assignor to Saab-Scania AB, Jonköping, Sweden

Continuation-in-part of Ser. No. 856,130, Dec. 1, 1977, abandoned. This application Aug. 23, 1979, Ser. No. 68,904

Int. Cl.³ B27B 15/04, 29/04, 1/00; B56G 47/90

U.S. Cl. 83—435.1

12 Claims



1. Apparatus comprising a feed mechanism by which a log is fed to a cutting machine in horizontal substantially lengthwise translatable motion parallel to a vertical cutting plane through the cutting machine, said feed mechanism comprising carriage means constrained to move horizontally in opposite directions parallel to the cutting plane and two pairs of jaws on the carriage means, projecting downwardly to a level beneath the carriage means, for gripping opposite sides of a log to constrain the log to move with the carriage means, said apparatus being characterized by:

A. measuring station means defining a reference plane that is

cylinder, a piston slidably mounted within the cylinder; a slot formed in at least one of said piston or cylinder at the sliding interface and open only at said interface, and means to feed pressurized hydraulic fluid adjacent the ends of said cylinder to actuate said piston and to said slot to balance and cushion the piston, said slot having a depth of approximately between 0.001 and 0.0025 inch thereby being sufficiently shallow to set up high capillary attraction of the fluid molecules within the slot, whereby the fluid is trapped within the slot and leakage is prevented.

4,294,162

FORCE FEEL ACTUATOR FAULT DETECTION WITH DIRECTIONAL THRESHOLD


Donald W. Fowler, West Haven, and Douglas H. Cleford, Trumbull, both of Conn., assignors to United Technologies Corporation, Hartford, Conn.

Filed Jul. 23, 1979, Ser. No. 60,093

Int. Cl.³ F15B 13/14, 13/16

U.S. Cl. 91-434

4 Claims



1. An improved fault detector for a force feel system having an hydraulic actuator responsive to the difference in pressure of hydraulic fluid applied to opposite ends thereof through a turn-on valve to apply force in either of two directions to the control stick of an aircraft, the fault detector including:

means for providing a desired force signal indicative of the force desired to be applied to the control stick by the actuator;

means for providing an actual force signal indicative of the force applied by the actuator to the control stick;

error means responsive to said desired force signal and said actual force signal for providing force error signals indicative of the magnitude and direction of the difference between the desired force and the actual force applied by said actuator;

position means for providing control stick position signals indicative of the position of said control stick; and

signal processing means connected to said position means and said error means, and responsive to the amount and direction of control stick motion, which occurs directly subsequent to said error means generating a signal indicative of an excessive force in either of said directions, for providing a fault signal to close said turn-on valve in response to excessive stick motion in the same direction as the direction of excessive force;

in which the improvement in said signal processing means comprises means continually responsive to current ones of said control stick position signals for registering the control stick position indicated by said signals in response to said error means providing signals indicative of excessive force in either direction, to provide base position signals, for comparing said control stick position signals with said base position signals, for providing a first signal in response to said base position signals exceeding said current position signals by a threshold magnitude, for providing a second signal in response to said current position signals exceeding said base position signals by a threshold magnitude, and for generating said fault signal in response to said error means providing signals indicative of excessive

force in a first direction concurrently with said first signal or in response to said error means providing signals indicative of excessive force in a second direction concurrently with said second signal.

4,294,163

NON ADJUSTABLE HYDRAULIC CYLINDER


Wilfred E. Boehringer, Fullerton, Calif., assignor to McDonnell Douglas Corporation, Long Beach, Calif.

Filed Oct. 29, 1979, Ser. No. 88,943

Int. Cl.³ F01B 7/20; F16J 1/10

U.S. Cl. 92-52

4 Claims



1. A dual acting hydraulic actuator primarily for the actuation of aircraft landing gear including:

a hydraulic cylinder having first and second ports for flowing fluid in and out thereof, a first end having a gland therein, and a second end having an attachment fitting;

a rod having first and second end portions and a central cylindrical portion of predetermined diameter therebetween, said first end portion having a rod end thereon and said central cylindrical portion being positioned to slide through said gland; and

a piston mounted to said second end portion of said rod for limited sliding movement a predetermined distance with respect thereto and sliding movement in said hydraulic cylinder in response to fluid pressure applied through said first and second ports, said piston including first and second abutment surfaces, said rod second end portion having first and second abutment surfaces positioned to engage said first and second abutment surfaces of said piston, said first and second abutment surfaces of said piston being closer together than said first and second abutment surfaces of said rod second end portion so that said predetermined distance of relative movement between said piston and said rod is defined by the difference therebetween, said rod second end portion also including an end cylindrical portion between said first and second abutment surfaces thereof, said end cylindrical portion having a diameter which is less than the diameter of said central cylindrical portion, and said piston further including first and second interior cylindrical surfaces which slide on said central cylindrical portion and said end cylindrical portion of said rod respectively, said piston and said rod defining a damping chamber between said first and second interior cylindrical surfaces, and at least one damping orifice establishing a flow path between said damping chamber and one of said ports.

4,294,164

PISTON FOR USE IN PNEUMATICALLY OPERATED PISTON-CYLINDER APPARATUS

Kurt Stoll, Lenzhalde 72, 7300 Esslingen, N., Fed. Rep. of Germany

Filed Dec. 4, 1979, Ser. No. 100,068

Claims priority, application Fed. Rep. of Germany, Dec. 14, 1978, 7836994[U]

Int. Cl.³ F16J 9/08

U.S. Cl. 92-243

4 Claims


1. A piston for operating cylinders which are to be operated utilizing compressed air, comprising:

a rigid cylindrical core member adapted to be connected to a piston rod;

an annular sealing ring of elastic material mounted around

and completely enclosing the peripheral edge of said core, said sealing ring having a pair of radially inwardly and axially spaced flange parts tightly engaging opposite axially facing sides of said core, said sealing ring further having a central web member integrally connecting the radially outer extremity of said flange parts and tightly engaging the radial periphery of said core, said sealing ring further having a pair of annular sealing lips integrally connected at the juncture between each flange part and said central web member and at a location spaced radially inwardly from the radially outermost extremity of said central web member to thereby define first and second

through said aperture between said two chambers, means for detecting a predetermined level of smoke or temperature, means for responding to said detecting means for filling and closing said drain trap-like conduit portion with a noncombustible fluid thereby closing communication between said two chambers through said aperture, means defining a door aperture in said partition, a hollow door movable between a first position at which said door aperture is open and a second position at which said door aperture is closed, means for conducting a noncombustible fluid through said door aperture defining means and into said hollow door when the latter is in its second position, second means for detecting a predetermined level of smoke or temperature, and means responsive to said second detecting means for effecting the conducting of fluid through said conducting means.



radially outwardly opening, axially spaced recesses, each of said sealing lips being outwardly inclined relative to the axially facing sides of said core and terminating at a location whereat the diameter is of greater dimension than the diameter of said central web member; and

a resilient annular guide ring having a generally channel-shaped cross section having a central bight portion and a pair of axially spaced legs, each of said axially spaced legs being received in a respective one of said first and second recesses to thereby prevent said guide ring from moving axially relative to said sealing ring, said guide ring being slotted to facilitate an installation of said guide ring on said sealing ring.

4,294,165

ARRANGEMENT TO COUNTERACT OR PREVENT SPREADING OF FIRE OR SMOKE

Knut Bergdahl, Kvartsgård 4, S-852 52 Sundsvall, Sweden


Filed May 4, 1979, Ser. No. 35,824

Claims priority, application Sweden, May 8, 1978, 0519/78

Int. Cl.³ F16K 9/00

U.S. Cl. 98-1

5 Claims



3. An arrangement to counteract or prevent the spreading of fire or smoke comprising means for defining a partition between two chambers of a static structure, means for defining an aperture in said partition for normally placing said two chambers in fluid communication with each other, means for normally maintaining said aperture open while being operative to close said aperture in response to the detection of fire or smoke, said last-mentioned means including a drain trap-like conduit portion through which air can normally flow to pass

1. An apparatus for making bread which comprises a casing frame, an oven accommodated in said casing frame, a combined trough and baking-pan unit removably mounted in said oven, a water tank accommodated in said oven, oven heater means effective to heat water as held in said water tank to the same temperature as that of the oven interior, means for directing the water heated in said water tank into said combined trough and baking-pan unit, an agitating device in said oven having an agitator element, and lift means operable to move said combined trough and baking-pan unit and said agitating device vertically relative to each other thereby to place the agitator element of said agitating device into and out of said combined trough and baking-pan unit.

4,294,167

METHOD OF APPARATUS FOR CANNING FOOD PRODUCTS

Max P. Beauvais, 46 Southridge West, Tiburon, Calif. 94920, and Raymond E. Camezon, 623 Tunbridge Rd., Danville, Calif. 94526

Filed Dec. 26, 1979, Ser. No. 107,425

Int. Cl.³ A47J 27/08

U.S. Cl. 99-369


6 Claims

1. Apparatus for canning food products, comprising a container having a removable lid capable of forming an air-tight seal against the open upper extremity of said container under the influence of a lower than ambient pressure within said container;

a pressure cover for covering the upper portions of said container and including pressure sealing means for forming a pressure-tight engagement with portions of the sides of said container, whereby the combination of the pressure cover and the container so covered forms a completely enclosed pressure vessel;

means for resiliently urging said container lid downwardly against said upper extremity of said container; pressure control means for limiting the maximum pressure differential between ambient and the pressure within said combined pressure cover and container to a predetermined level;

a base member; and



means for releasably connecting and restraining movement of said pressure cover relative to said base member, whereby a container and lid enclosing a food product, positioned and held by the base, may be engaged by the pressure cover and its sealing means when heat is applied from a heating unit to the containers, with the cover connected to the base assembly, for limiting pressure within the combined container and cover to the predetermined level to sterilize the food product, with subsequent cooling of the container causing the pressure within the container to be less than ambient to effect an air-tight seal between the lid and the container upper extremity.

4,294,168

INSERTABLE ARTICLE FOR ALTERING THE CURE RATE AND CHEMICAL COMPOSITION OF AN OBJECT
Walden K. Redhead, 3831 E. McGilvra St., Seattle, Wash. 98112
Filed Jul. 10, 1980, Ser. No. 167,773
Int. Cl.³ A23B 4/02; A23L 1/22
U.S. Cl. 99—494

7 Claims



1. An insertable article for altering the cure rate and chemical composition of an object comprising in combination: an elongate shaft,


recess means along the length of said shaft provided with support areas for carrying chemicals therein, said shaft having one pointed terminus for facile insertion into the object,

said support areas and recess means communicating without said shaft whereby chemicals disposed therein gradually leach out into the object wherein said recess means comprise a spiral groove (5) running the length of said shaft around said shaft and wherein said support areas comprise pockets (4) along side edges of said groove, above and below, and having openings (6) facing said groove and wherein said pockets have a circular configuration in section with an open arc area facing said groove and a shoulder extending to edge portion of said groove, and linear with an outer periphery of said shaft to protect against displacement of the chemicals upon insertion, removal, or rotation of said shaft, and wherein said support area are coextensive with said groove and similarly follow a spiral path.

4,294,169

COTTON MODULE COMPACTER
Charles D. Baird, P.O. Box 976, Coleman, Tex. 76834
Filed Feb. 4, 1980, Ser. No. 117,826
Int. Cl.³ B30B 15/30
U.S. Cl. 100—48

41 Claims



1. A seed cotton compacter for field use comprising in combination;

a frame;

a vertical compaction chamber mounted to said frame and including door means pivotal about a vertical axis between open and closed positions;

tamper means mounted to said frame above said compaction chamber and vertically reciprocal for tamping seed cotton in said compaction chamber into a compact module with said door means in said closed position, said door means in said open position permitting horizontal discharge of said compact module; and

said door means comprising a pair of L-shaped doors forming in said closed position left, and right and rear generally vertical walls of said compaction chamber, said doors forming said left, right and rear walls of said compaction chamber being tapered outwardly and rearwardly from top to bottom, each door being pivotally mounted to said frame at its forward vertical edge and extending rearwardly to define a respective right or left sidewall, and then inwardly to define part of the rear wall and meet the facing edge of the other door.

4,294,170

ROLL FEED DEVICE FOR FEEDING MATERIAL TO A PRESS


Yuu Takahashi, Hachioji, Japan, assignor to Aida Engineering, Ltd., Sagami-hara, Japan

Filed Jan. 24, 1980, Ser. No. 116,602

Claims priority, application Japan, Feb. 1, 1979, 54-10778[U]
Int. Cl.³ B30B 15/30

U.S. Cl. 100—216

2 Claims



1. A roll feed device for feeding a material to a press in a predetermined timed relationship to the operation of the press, said device comprising a pair of feed rolls between which the material is fed, one being an idle roll and the other being a driven roll, a drive shaft on said driven roll, an intermittent rotating mechanism operably associated with the drive of the press and having an output shaft, friction disk means easily removably mounted on said shafts and having the peripheral edges in frictional engagement with each other for driving said drive shaft from said output shaft and pressure means for urging the peripheral edges of said disk means into contact with each other, whereby an infinite number of feeding pitches can be provided by replacing the disks with other size disks.

4,294,171

EXPLOSIVES PACKAGE FOR COUPLED CAST PRIMER COMPOSITIONS

Gilles H. Ducharme, North Bay, Canada, assignor to E. I. Du Pont de Nemours and Company, Wilmington, Del.

Filed Sep. 21, 1979, Ser. No. 77,543

Claims priority, application Canada, Sep. 21, 1978, 311787
Int. Cl.³ C06B 11/00

U.S. Cl. 102—317

12 Claims



1. A container for explosives adapted for interconnection

with like containers to form a column, comprising a thin-walled elongated substantially cylindrical plastic tube open at both ends, said tube being provided with

- a male coupling at one end of the tube;
- a female coupling at the other end of the tube adapted to couple and retain a male coupling at the end of a like container;
- a circumferential groove inside the tube adapted to retain a closure disc within the tube adjacent the female coupling, between the male and female coupling;
- a circumferential ring seat extending into the tube and adapted to form a liquid-tight joint with a piston during casting of a high explosive into the tube, said ring seat being positioned between the circumferential groove and the male coupling; and
- a hole in the wall of the tube, adapted to receive and retain a thin-walled capwell thimble entirely between the ring seat and the end of the container having the male coupling.

4,294,172

PROJECTILE WITH RECOVERABLE DETONATOR

Willi Rauschert, Altensittenbach; Gerald Rieger; Erich Bock, both of Nuremberg, and Alfred Eckel, Treuchtlingen, all of Fed. Rep. of Germany, assignors to Diehl GmbH & Co., Fed. Rep. of Germany

Filed May 29, 1979, Ser. No. 43,133

Claims priority, application Fed. Rep. of Germany, Jun. 2, 1978, 2824203

Int. Cl.³ F42B 11/22

U.S. Cl. 102—473

6 Claims



1. Projectile including a detonator (2) recoverable to provide function control, wherein an aerodynamic brake arrangement (5) located interiorly of the projectile body (3) is mounted on a projectile upper portion (1) supporting the detonator (2) and which is fastened to the projectile body (3), and a piston (11) is supported within the projectile body (3) which propels the projectile upper portion (1) out of the projectile body (3) at the ignition of a propellant charge (13), characterized in that the projectile body is formed by a projectile shell (3), the propellant charge (13) is arranged in the projectile shell (3) at the side of the piston (11) facing away from the projectile upper portion (1), and the piston (11) impacts against the projectile upper portion (1) through half-shells (8) which extend about the brake arrangement (5), ram means being arranged in said projectile upper portion said ram means having a limited path of movement, and said brake means being fastened thereto; a further ejector charge in said upper portion being located against the side of said ram means opposite the projectile shell (3), and said ejector charge being detonated by said detonator (2).

4,294,173

AMMUNITION FOR A TOY WEAPON


Giampiero Ferri, Via Stoppani 38, Florence, Italy

Filed Jun. 4, 1979, Ser. No. 44,904

Claims priority, application Italy, Jun. 7, 1978, 9492 A/78

Int. Cl.³ F42B 4/02

U.S. Cl. 102—281



1. A process for the production of ammunition for toy-weapons, said process comprising the steps of forming a support having a plurality of seats for explosive charges, by injection moulding a plastics material, depositing explosive charges in said seats, arranging the support with the explosive charges in a second injection mould, and forming, in said second mould, a separate cover for each said seat using a plastics material which is fused to the seat, said covers being injected simultaneously, but separately.

4,294,174

VEHICLE SYSTEM WITH SPEED-RESPONSIVE STOP


Gerhard H. Todt, Ailing-Biburg, Fed. Rep. of Germany, assignor to Buro Patent A.G., Glarus, Switzerland

Filed Mar. 24, 1980, Ser. No. 132,767

Claims priority, application Switzerland, Mar. 23, 1979, 2753/79

Int. Cl.³ B61B 7/8, 7/00

U.S. Cl. 104—250



1. A mechanical stop mechanism for a vehicle system having a track defining a vehicle path and at least one vehicle displaceable along said path, said mechanism comprising:

- an arm pivotally mounted alongside said path at an axis transverse thereto and adapted to extend into said path for engagement by said vehicle whereby said arm is swung by said vehicle about said axis at an angular velocity determined by the speed of said vehicle;
- a centrifugal clutch having an output element, said clutch being connected to said arm and having a threshold velocity for clutch engagement whereby said output element of said clutch is rotatably entrained by said arm upon the angular velocity thereof exceeding said threshold velocity;
- a restoring spring connected to said arm for biasing same into a position wherein said arm extends into said path; and
- a stop member triggered upon movement of said output element into a position wherein said stop member engages said vehicle and holds the same along said path.

4,294,175

SWIVEL-TRUCK SPRING SYSTEM FOR RAILROAD USE

Gabor Harsy, Neuhausen, Switzerland, assignor to Sig

Schweizerische Industrie-Gesellschaft, Switzerland

Filed Apr. 2, 1979, Ser. No. 26,405


Claims priority, application Switzerland, Apr. 10, 1978,

1 Claim 3819/78

Int. Cl.³ B61F 3/08, 5/30

U.S. Cl. 105—199 R

25 Claims



1. A swivel truck spring system for a railroad car, or the like, comprising:

- a truck, including a frame and rotatable wheels supported on said frame;
- first and second spring means arranged in series between said truck frame and the body of the railroad car, with said first spring means being adapted for absorbing vertical load forces and with said second spring means being adapted for absorbing lateral load forces;
- said first and said second spring means being laterally spaced apart and being near each other, thereby to take up both vertical and lateral forces, while minimizing the height of the combined structure of said first and said second spring means;
- a pair of normally spaced apart spring washers for each set of said first and said second spring means; said spring washers extending laterally between said truck frame and the body of the railroad car, or the like; said first spring means being between said spring washers and said second spring means comprising one second spring between the uppermost said washer and the car body and another second spring between the lowermost said washer and said truck frame.

4,294,176

PORTABLE HOIST FRAME


Albert C. Brooks, 2023 W. Lexington St., Baltimore, Md. 21223

Filed Apr. 4, 1979, Ser. No. 26,815

Int. Cl.³ B61D 17/00

U.S. Cl. 105—363

10 Claims



1. An easily assembled and dis-assembled portable hoist frame comprising:

- a first end frame means, said first end frame means having a top and bottom and side members;
- a second end frame means, said second end frame means being similar to said first end frame means and spaced therefrom;
- a first horizontal frame means, said first horizontal frame

means having a vertically inclined strut member, said first horizontal frame means being connected to said first and second end frame means at both the top and at the bottom of said first and second end frame means;

a second horizontal frame means, said second horizontal frame means having a vertically inclined strut member connected to said first horizontal frame means, said second horizontal frame means being connected to said first and second end frame means at the bottom of said first and second end frame means;

a plurality of wheel-like means, said plurality of wheel-like means being attached to said first and second horizontal frame means to provide positioning flexibility to said portable hoist frame in a first direction of movement; and a plurality of clip means, said plurality of clip means being attached to said first and second end frame means to secure said portable hoist frame against a movement in a second direction of movement perpendicular to said first direction of movement when being positioned on said wheel-like means.

4,294,177

SUPPORT BRACKET AND OPEN SHELVING ASSEMBLY


James A. Nicholson, 10600 Van Stralen Way, Rancho Cordova, Calif. 95670

Filed Nov. 14, 1977, Ser. No. 851,299

Int. Cl.³ A47B 37/00

U.S. Cl. 108—42

5 Claims



1. In combination with a wall cabinet, a back wall and a ceiling, a ventilator hood and a standing exhaust pipe; a support bracket and open shelving assembly wherein said assembly consist of an elongated first bracket and a second bracket with both said bracket having upper and lower base extensions and with said extensions oppositely spaced apart on said first and second brackets and, with said brackets in attachment with said upper and lower base extensions of both said brackets facing inwardly of each other to form a right angle facing primary bracket with said bracket having attachment means at each end of said primary bracket and on the lower base extension, also alternate attaching means; two elongated vertical posts in attachment with the said first bracket with said posts substantially square in cross section and in attachment with said first bracket by one corner of said vertical posts in a spaced apart relationship and with each said post having ceiling attaching means at their top ends also, alternate attaching means of said vertical posts to said first bracket; a plurality of shelving support brackets having upper and lower spaced apart extensions comprising two basic sets of brackets, a first set is attachable to the said vertical posts and, a second set which has attachable means to a back wall, two alternate shelf support means; a plurality of dampener devices affixed inwardly of the aforesaid shelf support brackets to include, one alternate mode of shelf support also, a plurality of chatter pads for association with the said dampener devices and said shelf

support brackets; a plurality of preferably transparent rectangular shelving in association with said brackets and components within said brackets and, two stabilizer anchorage means.

4,294,178

TANGENTIAL FIRING SYSTEM


Richard W. Borio, Somers, and Arun K. Mehta, Windsor Locks, both of Conn., assignors to Combustion Engineering, Inc., Windsor, Conn.

Filed Jul. 12, 1979, Ser. No. 57,049

Int. Cl.³ F23D 1/00

U.S. Cl. 110—347

2 Claims



1. The method of operating a furnace having four walls, a first set and second set of nozzle means, with each set having nozzle means located in each of the four corners of the furnace, the method of operation comprising introducing pulverized coal and primary air into the furnace through the first set of nozzle means in such a manner that the streams of coal and primary air are directed tangentially to a first imaginary, substantially horizontal, circle in the center of the furnace, introducing secondary air into the furnace through the second set of nozzle means in such a manner that the stream of secondary air are directed tangentially to a second imaginary circle spaced from, concentric with, and surrounding the first imaginary circle, in order to reduce NO_x in the exhaust gases, and also maintain an oxidizing atmosphere adjacent the furnace walls, thus reducing slagging and corrosion of the furnace walls.

4,294,179

DIBBLE TUBE SOIL PLUG PLANTER


David W. Cayton, Errol C. Armstrong, and Angus B. MacKenzie, all of Salinas, Calif., assignors to Bud Antle, Inc., Salinas, Calif.

Filed Aug. 1, 1979, Ser. No. 62,667

Int. Cl.³ A01C 11/02, 5/04

U.S. Cl. 111—3

3 Claims



1. Apparatus for the transplant of plant containing plugs from trays into a field having elevated seed beds contained between paired furrows, said apparatus comprising: a transport frame having first and second ground support members for passage within said furrows, said furrows having at least one plant bed defined between said furrows; at least one planting chassis suspended from said transport frame; a plug extractor

supported on said transport frame; said plug extractor including means for registering columns of plant containing plugs from a vertically supported and adjustable rigid carrying tray mounted on a horizontally adjustable support frame, said tray having rows and columns of plant containing plugs for extraction from said tray; said rigid carrying tray forming the sole support for said plugs; plug extractors, including ejectors, for contacting a group of plugs in a column of plugs from one side of said tray to cause the horizontal discharge of plugs to a plurality of plug receiving stations on the opposite side of said tray; a member defining said plurality of plug receiving stations, each station registered to said tray at a position of extraction of said plugs; said member juxtaposed to said tray to receive said plugs upon extraction; means for moving said member to register said plug receiving stations to plug receiving tubes; dibble planters for said tubes; a plug receiving tube extending from each plug receiving station to and towards one dibble planter mechanism at least two of said dibble planters being aligned with the direction of travel of said apparatus; air supply means for each said plug receiving tube; said chassis including a registry means for each tube; a dibble planter at each said registry means, each said dibble planter including a first solid sectioned cylinder for penetration into the ground to define within said ground a ground aperture the size and volume of said plug; a second hollow sectioned cylinder reciprocal about the first cylinder for receiving interiorly said first cylinder to hold the ground adjacent to said first cylinder; said registry means including horizontal sliding means for vertical registry of said tube to said second hollow sectioned cylinder when said first cylinder is withdrawn to permit air assisted gravity discharge of plugs within said tubes into the ground aperture in said ground whereby when said second cylinders are retracted, said plug resides in said ground.

4,294,180

GRAIN DRILL WITH DEVICE FOR PREVENTING UNDESIRABLE BACKFILLING OF FRONT FURROW BY REAR FURROW OPENERS


Waldo H. Pust, Savage, Mont. 59262

Filed Oct. 31, 1979, Ser. No. 89,911

Int. Cl.³ A01C 5/00

U.S. Cl. 111—52

12 Claims



1. A method of planting seed comprising the steps of forming a front furrow, depositing seed in said front furrow, concurrently forming a rear furrow offset to one side of said front furrow, said step of forming said rear furrow displacing or shifting soil from said rear furrow in the direction of said front furrow, depositing seed in said rear furrow, preventing the soil displaced or shifted from said rear furrow as it is formed from entering said front furrow by employing disc means for deflecting soil displaced or shifted from said rear furrow, thereby preventing undesired backfilling of said front furrow, and covering the seed in said front furrow with some of the soil forming said front furrow.

4,294,181 SUBSOIL AGRICULTURAL IMPLEMENT WITH ROTATABLE DISC


Franklin Smith, Potlatch, Id.

Continuation-in-part of Ser. No. 950,124, Oct. 10, 1978, abandoned. This application Jun. 9, 1980, Ser. No. 157,805

Int. Cl.³ A01C 7/20; A01B 33/06

U.S. Cl. 111—87

8 Claims



1. A subsurface agricultural implement comprising:
a framework;
a circular cultivator disc having oppositely facing upper and lower surfaces joined at a peripheral edge formed about a central disc axis;
an elongated rigid disc support having an upright forward edge and an upright rearward edge, and an upper end mounted to the framework;
an upright delivery tube fixed to the cultivator disc at a lower tube end and extending upwardly therefrom centered and preceding the forward edge of the disc support to an upper tube end, said delivery tube being centered along the disc axis as a coaxial extension thereof;
bearing means on said disc support mounting the delivery tube to the disc support for rotation of the delivery tube about the central disc axis, said bearing means comprising first and second coaxial rotational bearings mounted to the disc support at two axial spaced locations with an exposed section of the tube between said bearings, one of which is located on said disc support elevationally adjacent said disc at said lower tube end;
an open bore extending through the delivery tube from its upper end to its lower tube end;
said disc including a central opening formed therein in alignment with the open bore;
means on said framework for lowering the disc to an elevation below the soil surface;
means for causing rotation of the disc and delivery tube about the central disc axis in response to forward movement of the framework while the disc is elevationally below the ground surface;
means on said framework for directing a flowable material to the open bore at the upper tube end; and
trash clearing means on the delivery tube for preventing buildup of trash against the disc support as it is moved along the ground;
a pivot bracket and pin joining an upper end of the disc support to the framework for transverse pivotal movement about a longitudinal axis; and
spring means interconnecting the disc support and said framework for normally urging the disc support toward an upright position.

4,294,182 DEVICE FOR APPLYING THREAD STAPLES TO FOLDED SHEETS

Winfried Böttcher, and Kurt Germer, both of Leipzig, German Democratic Rep., assignors to Veb Kombinat Polygraph "Werner Lamberz" Leipzig, Leipzig, German Democratic Rep.


Continuation-in-part of Ser. No. 72,294, Sep. 4, 1979. This application Sep. 13, 1979, Ser. No. 75,000

Claims priority, application German Democratic Rep., Sep. 4, 1978, 207622

Int. Cl.³ B42B 1/02

U.S. Cl. 112—21

6 Claims



1. A device for applying thread staples to folded sheets, comprising means for feeding said sheets in a plane; an endless chain having a section travelling in said plane in the feeding direction of the sheets; a plurality of thread feeding plates attached to said chain and each carrying a length of the thread corresponding to a staple to be formed; a pair of needles supported on each plate and guided for a reciprocating movement relative to said threads and said sheet; and stationary cam means operable to impart said reciprocating movement to said needles during the travel of said chain.

4,294,183

CUTTER CONFIGURATION FOR EFFICIENT ICE DISAGGREGATION AND CLEARING


George W. Morgan, San Jose, Calif., assignor to Suncor Inc., Toronto, Canada

Filed Apr. 14, 1980, Ser. No. 139,960

Int. Cl.³ B63B 35/12

U.S. Cl. 114—42

4 Claims



4. An ice engaging tooth structure adapted to be affixed to and carried by a rotatable ice disaggregating drum, said tooth structure including:

- (A) a base portion extending outwardly from the peripheral surface of said drum;
- (B) an intermediate portion effecting a continuation of said tooth structure from said base portion, said intermediate portion being angled rearwardly with respect to the direction of drum rotation during ice disaggregating operations;
- (C) a forwardly sweeping arcuate portion effecting a continuation of said tooth structure from said intermediate portion; and
- (D) an ice engaging portion effecting a continuation of said tooth structure from said arcuate portion, said ice engaging portion comprising:
 - (i) an inverted skate element oriented along the centerline of said ice engaging portion, said inverted skate element

having an edge generally facing the peripheral surface of said drum;

- (ii) wing-like projections extending outwardly, respectively, on first and second sides of said inverted skate element and oriented generally parallel to the axis of said drum, said wing-like projections terminating at their forward ends in ice engaging chisel-like leading edges; and
- (iii) a centrally disposed pick element generally aligned with said inverted skate element and extending forwardly beyond said chisel-like leading edges of said wing-like projections.

4,294,184

MULTI-HULL STEERING SYSTEM

Bernd Heinrich, Flat 27, 40 Spofforth St., Cremorne, N.S.W., Australia (2090)


Filed Apr. 6, 1979, Ser. No. 27,821

Claims priority, application Australia, Apr. 11, 1978, PD3976

Int. Cl.³ B63B 1/00

U.S. Cl. 114—61

6 Claims



1. A multi-hull craft steering system comprising:
a frame member;
a plurality of hulls each constructed from flexible envelopes pneumatically inflated to obtain buoyancy, said hulls being supported by a trunion mounted to said frame member, each of said trunions having a hollow body enveloping one of said flexible envelopes near a mid-region of said envelopes, the upper surface of each of said hollow bodies extending longitudinally to a greater extent than the remainder of said bodies, wherein one of said hulls is a middle steering hull pivotally mounted for controlled angular variation in azimuth, said middle hull located ahead of the remaining hulls to at least an extent sufficient to permit rotation of said middle hull to avoid interference with the bows of the remaining hulls during such angular variation whereby said craft is steered;
said outer hulls having a variable track therebetween, whereby said hulls are selectively locatable in a discrete number of locations;
a locking means for maintaining said hulls at one of said locations; and
means for angularly rotating the outer hulls away from the longitudinal axis of said craft about a hinge means connected to said frame from a first working position to a second stowed position, said stowed position permitting transportation and storage of said craft.


4,294,185

SYSTEM FOR SECURING CONTAINERS IN A SHIP'S HOLD

Immo R. Nordstrom, P.O. Box 305, Fair Haven, N.J. 07701, and Johannes A. Bak, Prunuslaan 41, Dordrecht, Netherlands
Continuation-in-part of Ser. No. 830,500, Sep. 6, 1977, abandoned. This application Sep. 8, 1978, Ser. No. 940,767
Int. Cl.³ B63B 25/08

U.S. Cl. 114—75

20 Claims



1. An apparatus for securing containers in a storage or cargo cell in a ship's hold wherein the containers are of substantially equal length and the storage cell is greater in length than the combined lengths of two such containers, the storage cell having a bottom wall and vertical side and end walls, and wherein each of the containers is of a type having corner pieces as a structural part of the container, each said corner piece having an elongated side opening therein, the apparatus comprising

guide means structurally attached to a vertical side wall of the storage cell for guiding the containers
said guide means having elongated flange portions extending vertically upwardly from a location adjacent the bottom wall thereof;

first and second guide hooks;

and means for detachably mounting each of said guide hooks in an opening in a corner piece of each of the containers on the same side as, and at the end closest to, the other container,

each of said guide hooks having a recess portion directed toward the other guide hook,

whereby said hooks lie on opposite sides of, and partially enclose, said flange portions of said guide means.

4,294,186


RETRACTABLE BOW THRUSTER

Gerald S. Wardell, 2249 SW. 68th Ter., Miramar, Fla. 33023
Filed Jan. 25, 1980, Ser. No. 117,219

Int. Cl.³ B63H 25/42

U.S. Cl. 114—151

14 Claims



1. A retractable thruster for use in providing lateral thrust for steering a vessel, comprising:

a main housing;

a first gear housing disposed within said main housing;

a drive gear mounted for rotation within said first gear

housing, said first gear housing having mounting means for providing a pivotal connection to said main housing, said pivotal connection allowing said first gear housing to pivot about the axis of rotation of said drive gear;

a propeller;

drive means connected between said drive gear and said propeller for causing rotation of said propeller upon rotation of said drive gear; and

connection means operatively connecting said propeller to said first gear housing for causing said propeller to move up and down within said housing upon pivotal movement of said first gear housing.

4,294,187

APPLICATOR FOR DIRECT ROLL COATING

Ozzie Fogle, Orangeburg, S.C., assignor to Champion International Corporation, Stamford, Conn.


Continuation of Ser. No. 900,819, Apr. 27, 1978, abandoned.

This application Jun. 5, 1980, Ser. No. 156,818

Int. Cl.³ B05C 1/00

U.S. Cl. 118—244

7 Claims



1. An apparatus for continuous direct roll coating of textured panels or sheet-like members comprising in combination: a roll applicator; means for continuously applying coating material to said applicator, and means for continuously bringing the panels into contact with said applicator, said applicator including a central core; a relatively thick layer of soft, fibrous, compressible and pliable material having a web construction held together by a binding adhesive, said fibrous layer being disposed over said core enabling said applicator to follow contoured surfaces; a very thin protective tube member disposed around said layer of fibrous web material to prevent coating material from penetrating said fibrous web material, said tube member being of an impervious material; and a very thin layer of woven fabric material disposed over said protective tube member, said layer of woven fabric material absorbing a coating for application by said applicator, said means for continuously applying coating material to said applicator including a reservoir for containing the coating material, a first roller partially immersed in said reservoir, a second roller immediately adjacent said first roller and engaged therewith, said second roller also being immediately adjacent to and engaged with said applicator, and means for rotating said first and second rollers and said applicator such that said first roller and said applicator rotate in the same direction, and said second roller rotates in the opposite direction to that of said first roller and applicator.

4,294,188

HYDRAULICALLY OPERATED ACCESS EQUIPMENT

Denis H. Ashworth, Dudley, England, assignor to Simon Engineering Dudley Limited, West Midlands, England

Continuation of Ser. No. 824,822, Aug. 15, 1977, abandoned.

This application Sep. 24, 1979, Ser. No. 78,183

Claims priority, application United Kingdom, Aug. 21, 1976, 34923/76

Int. Cl.³ B05C 5/00

U.S. Cl. 118—305

8 Claims

1. Hydraulically operated access equipment comprising a supporting structure such as a vehicle, a boom structure, a turntable rotatable about a vertical axis on said supporting

structure and on which at least a part of said boom structure is pivotally mounted for movement about a horizontal axis, hydraulic actuating means for said boom structure whereby the boom structure may be moved about its horizontal pivot between a generally horizontal stowed position on said supporting structure and an elevated position wherein its outermost end is raised above said supporting structure, a frame or housing mounted on said boom structure at the outermost end thereof, treatment means carried by said frame or housing for cleaning or applying a coating to an adjacent surface, means in said hydraulic actuating means effective to swing said boom structure to cause said treatment means to traverse said surface in substantially vertical arc paths, surface-engaging means on

ber; paint pool holding means for receiving discharged paint from said aperture of each said chamber, said paint pool holding means being provided externally of, and laterally displaced from said chambers and below said paint dies, and said paint pool being in fluid communication with a lower portion of each said chamber, and wherein the cross-sectional area of each said chamber is sufficiently small such that the temperature gradient of the paint within each chamber is minimized.

4,294,190

METHOD OF COATING OPTICAL WAVEGUIDE FILAMENTS AND COATING DIE

James W. Ohls, Horseheads, N.Y., assignor to Corning Glass Works, Corning, N.Y.


Division of Ser. No. 46,232, Jun. 7, 1979, Pat. No. 4,246,299.

This application Mar. 20, 1980, Ser. No. 132,259

Int. Cl.³ B05C 3/12

U.S. Cl. 118—620

11 Claims



said frame or housing adapted to maintain said frame or housing at a fixed distance from said surface when the equipment is in use and as said boom structure is moved to cause said treatment means to traverse said surface, and means for imparting a continuous rotational drive to said vertical axis turntable during movement of said treatment means in said paths whereby to continuously bias said boom structure and frame or housing means toward said surface to thereby positively cause said surface-engaging means to be maintained in contact with said surface during all operational movement of said treatment means in said paths, said means for imparting a continuous rotational drive to said vertical axis turntable further comprising means to permit the means for imparting the rotational drive to slip during operation.

1. An apparatus for coating an optical waveguide filament comprising

a reservoir for containing a quantity of coating material, the bottom thereof defining an aperture,

a die body disposed within said aperture in said reservoir, said die body defining an at least partly tapered central longitudinal aperture extending from the top surface thereof to the bottom surface thereof,

means intermediate said top surface and said bottom surface of said die body communicating between said central longitudinal aperture and the interior of said reservoir for flowing said coating material into said central longitudinal aperture and for maintaining the level of said coating material in said central longitudinal aperture at a point intermediate said top and bottom surfaces of said die body but not above said top surface when said filament is passed through said central longitudinal aperture and said coating material contained therein, and

means extending past said top surface of said die body for shielding said top surface from the interior of said reservoir.

4,294,189

APPARATUS FOR COATING WIRES WITH PAINT

Hiroshi Ashida, and Fumitake Takahashi, both of Nagoya, Japan, assignors to Sumitomo Electric Industries, Ltd., Osaka, Japan


Filed Feb. 27, 1980, Ser. No. 125,053

Claims priority, application Japan, Mar. 19, 1979, 54-31999

Int. Cl.³ B05C 3/12

U.S. Cl. 118—603

5 Claims



1. An apparatus for coating wires with paint comprising: at least one chamber for holding paint to be applied to said wires and adapted for said wires to pass therethrough, a discharge outlet being provided in each said chamber for allowing said paint to be discharged from an upper portion of each chamber; a coating die disposed in said upper portion of each said cham-

4,294,191

SPRAY BOOTH

Ingemar Lööf, Fabrikgatan 6, S-560 10 Skillingaryd, Sweden

Filed Dec. 6, 1979, Ser. No. 100,750

Claims priority, application Sweden, Dec. 6, 1978, 7812532

Int. Cl.³ B05C 15/00

U.S. Cl. 118—634


11 Claims

1. A spray booth comprising:

a housing having an internal surface and at least one opening for introducing an object to be spray-covered by a spray material,

said housing having opposed first and second ends and first and second guide means disposed at such ends,

an inlet device movable within said housing and having an inlet opening facing said internal surface of said housing for receiving spray material which has not adhered to said object, said inlet device including first and second end portions



which are guided by said first and second guide means, and drive means operably connected to said first and second end portions for moving said inlet device along said internal surface.

4,294,192



LIQUID ELECTROSTATIC IMAGE DEVELOPING SYSTEM EMPLOYS MESH DEVELOPMENT ELECTRODE

Syunzi Nakai, Moriguchi, and Motokazu Nakao, Sakurai, both of Japan, assignors to Sharp Kabushiki Kaisha, Osaka, Japan
Filed May 28, 1980, Ser. No. 154,016

Claims priority, application Japan, May 30, 1979, 54-67632
Int. Cl.³ G03G 15/10

U.S. Cl. 118—650

7 Claims



1. A liquid development system for developing an electrostatic latent image formed on a copy paper through the use of a developer liquid, said liquid development system comprising in combination:

- a mesh shaped development electrode disposed in the traveling path of a copy paper above a developer liquid reservoir;
- a liquid developer supplying means for supplying the devel-

oper liquid from said reservoir to said mesh shaped development electrode; and
a copy paper feed means for transferring said copy paper above said mesh shaped development electrode in a manner that the front surface of said copy paper, on which said electrostatic latent image is formed, makes contact with or is positioned in close proximity to said mesh shaped development electrode.

4,294,193


APPARATUS FOR VAPOR COATING A MOVING GLASS SUBSTRATE

Roy G. Gordon, 22 Highland St., Cambridge, Mass. 02138
Division of Ser. No. 884,432, Mar. 8, 1978, Pat. No. 4,206,252, which is a continuation-in-part of Ser. No. 784,542, Apr. 4, 1977, Pat. No. 4,187,336. This application Dec. 14, 1979, Ser. No. 103,519

Int. Cl.³ B05C 5/02

U.S. Cl. 118—718

6 Claims



1. In an apparatus for forming a continuous coating of progressively changing composition on heated glass over the length of a processing path through which said glass passes said apparatus comprising, in addition to means to support said glass and means to move it continuously along said processing path,

the improvement wherein there is provided a reaction zone the interior surfaces of which are formed primarily by said moving glass and a heat-transfer-medium moderated, temperature-controlled wall opposed to said glass said zone having, at one end thereof, a part means at a first station to introduce and distribute a gaseous reaction mixture comprising reactants which form reaction products that deposit on said glass at different rates, a gas flow path within said reaction zone wherein said gaseous reaction mixture flows along said glass surface, and said temperature controlled wall to port means at a second station at the opposite end of said zone to remove residual gaseous reaction mixture, wherein

said second station being relatively positioned along said reaction zone with respect to said first station that said heated glass wall of said reaction zone forms means to provide sufficient energy to said gaseous reaction mixture to achieve a substantial difference in composition deposited on said glass between the reaction gas mixture composition, as it passes between said first station and second station and wherein said temperature-controlled wall is maintained at a temperature low enough to avoid deposits of reaction products thereon.

4,294,194

DEVICE FOR COATING OBJECTS

Reinhard Behn; Hermann Heywang, both of Munich, and Horst Pachonik, Unterhaching, all of Fed. Rep. of Germany, assignors to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany

Filed Oct. 31, 1979, Ser. No. 89,857

Claims priority, application Fed. Rep. of Germany, Nov. 8, 1978, 2849480


Int. Cl.³ C23C 13/00

U.S. Cl. 118—719

8 Claims

1. A device for coating carriers with alternating different coatings in a different vacuum, comprising: at least first and

second vacuum chambers separated from one another by first and second vacuum air locks; transport means for transporting the carriers to be coated in only one moving direction from the first air lock through the first vacuum chamber to the second air lock and back towards the first air lock through the second vacuum chamber; means for coating the carriers arranged on the transport means in each of the vacuum chambers; each of



the air locks having jaws arranged directly adjacent the transport means and which form a relatively narrow gap therewith; suction means for drawing off residual gas between jaws of each of the air locks; and the first air lock, located in front of the first vacuum chamber in the direction of movement, having a lower residual gas pressure and having longer diffusion paths than the second air lock following the first vacuum chamber in the direction of movement.

4,294,195

HOG FARROWING MODULE

Joseph H. Rodenberg, 8290 N. Kenwood, Indianapolis, Ind. 46260, and Richard K. Gilcrest, 5613 Skyridge Dr., Indianapolis, Ind. 46250


Continuation of Ser. No. 801,625, May 31, 1977, abandoned.

This application Jun. 4, 1979, Ser. No. 45,507

Int. Cl.³ A01K 1/00

U.S. Cl. 119—20

1 Claim



1. A modular base comprising:

- a floor serving as a top for said base;
- said floor having an opening toward one end thereof extending completely across the width thereof;
- manure passing grate means retained by said base for covering said opening;
- trough means connected to said base and disposed under said grate means for receiving waste disposed therethrough;
- drinking water drain means attached to said base at the end thereof away from said opening, said drain means being connected to a tube running under said floor, with said tube emptying into said trough means;

heating means embedded in said floor and maintaining a desired floor temperature; said floor having a crown profile formed therein as viewed in side elevation, with said crown formed between said trough means and said drain means, said crown extending laterally throughout the entire width of said floor; and a plurality of screw jacks attached to said base for tilting said base at a desired slope of said trough means, and wherein said modular base is moveable as a unit and locateable on any flat surface by means of said screw jacks.

4,294,196

GATE ASSEMBLY

Owen M. Larsen, Box 68, Mitta Roadside, Tallangatta, Victoria 3700, Australia


Filed Feb. 14, 1980, Ser. No. 121,556

Claims priority, application Australia, Feb. 15, 1979, PD7702

Int. Cl.³ A01K 1/00

U.S. Cl. 119—27

5 Claims



1. A gate assembly for a milking parlor or like animal enclosure including,

- a barrier pivotally mounted about a substantially horizontal elevated axis from a support for movement between an open position in which it allows exit of an animal from the enclosure, and a closed position in which it prevents such exit,
- operating means for said barrier and a lever arrangement connecting said operating means to the barrier providing locking means tending to hold the barrier open against the action of gravity,
- said locking means providing a past dead centre locking action,
- said lever arrangement including an extension arm on said barrier,
- an angled arm pivotally attached to the extension arm,
- a bell crank arm pivotally connected to the angled arm and to a rotatable shaft attached to said support, and
- said operating means connected to said rotatable shaft for rotating the shaft and said crank arm for opening and closing said barrier.

4,294,197

HAYBOX

Cornelis Snel, Atlasdreef 53, 3561 Ac Utrecht, and Albert Kuus, Korhoenlaan 41, 3721 Eb Bilthoven, both of Netherlands

Filed Jul. 9, 1979, Ser. No. 55,959


Int. Cl.³ A01K 5/00

U.S. Cl. 119—60

13 Claims

1. Haybox for the feeding of horses comprising interconnected walls defining a box, a rack positioned on an upper part of the box, and a movable plate forming a bottom of the box and being movable between lowered and raised positions within said box for supporting hay, guide bars extending within said box parallel to said wall, said movable plate being provided with at least two spaced apart perforations through which said guide bars extend, pressure springs fitted on said guide bars on the underside of the movable plate for exerting

upwards pressure, spherical type means positioned at least in part between said springs and said movable plate for transferring spring force to said movable plate, said spherical type means having a larger diameter than that of the perforations,



the diameter of the guide bars extending through the movable plate being smaller than the diameter of the perforations in the movable plate to allow the latter to carry out a tilting movement with respect to walls of the box.

4,294,198

HEATING BOILER FOR LIQUID OR GASEOUS FUELS
Hans Viessmann, Im Hain, 3559 Battenberg, Eder, Fed. Rep. of Germany


Filed Jan. 31, 1979, Ser. No. 7,886

Claims priority, application Fed. Rep. of Germany, Feb. 4, 1978, 2804780; Dec. 27, 1978, 2856061

Int. Cl.³ F22B 7/00

U.S. Cl. 122—136 R

3 Claims



1. A heating boiler comprising a water jacket including front and rear walls, fuel flues, tube and sleeve means, said tube means extending through said walls and enclosing said flues and defining a combustion chamber and a collecting chamber, one of said means, in the vicinity of said collecting chamber, encircling the other of said means and defining an annular gap therewith, at least one of said means having a bulge adjacent said gap to increase the size of the gap between said means, and closure means on one of the first said means to obturate said collecting chamber, said rear wall having a thermally conductive connection with said one means which encircles said other means.

4,294,199

STEAM GENERATING MAGNETOHYDRODYNAMIC DIFFUSER

Scott L. Darling, Tariffville, and Carl R. Bozzuto, Enfield, both of Conn., assignors to Combustion Engineering, Inc., Windsor, Conn.

Filed Oct. 26, 1979, Ser. No. 88,731


Int. Cl.³ F22B 21/30

U.S. Cl. 122—276

1 Claim

1. A steam generating diffuser comprising:

- a horizontally orientated, longitudinally elongated upper collection header;
- a horizontally orientated, longitudinally elongated lower distribution header positioned beneath said upper header;
- a plurality of heat exchange tube pairs disposed side by side in vertical planes to form an open-ended divergent duct disposed about a vertical axis, the tubes of each pair extending vertically upward from said lower header, thence diverging by extending outwardly and upwardly at an acute angle with the horizontal to form the floor of said duct, thence extending substantially vertically upward to form the side walls of said duct, thence converging by extending upwardly and inwardly at an acute angle with the horizontal to form the roof of said duct, and thence extending substan-



- tially vertically upward to said upper header, each tube thereby providing a continuously upwardly directed fluid flowpath between said lower and said upper headers;
- a refractory lining laid up around the inner surface of said divergent duct so as to protect the heat exchange tubes forming said divergent duct from hot gases passing there-through;
- means for circulating water from said lower header through the heat exchange tubes forming said duct to said upper header whereby a portion of the water is vaporized to steam when passing through said heat exchange tubes; and
- said upper collection header further comprises a water and steam drum having internal means for separating the steam from the water collecting therein.

4,294,200

VARIABLE PRESSURE VAPOR GENERATOR UTILIZING CROSSOVER CIRCUITRY FOR THE FURNACE BOUNDARY WALL FLUID FLOW TUBES
Walter P. Gorzegno, Morristown, N.J., assignor to Foster Wheeler Energy Corporation, Livingston, N.J.

Filed Dec. 6, 1979, Ser. No. 100,770


Int. Cl.³ F22B 27/04

U.S. Cl. 122—406 S

6 Claims

1. A vapor generator comprising an enclosure defined in part by a front wall, a rear wall and two sidewalls, each of said walls comprising a plurality of interconnected tubes; burner means associated with either said front wall, said rear wall or both; each of said sidewalls having a plurality of sections; means for passing fluid initially through the entire length of at least one of said sidewall sections and then through said front wall, said rear wall and the other sidewall sections; and cross-

over means associated with said front wall, said rear wall and said other sidewall sections for transferring said fluid from one



area of said front wall, said rear wall and said other sidewall sections to another area thereof.

4,294,201

INTERNAL COMBUSTION ENGINES


Robert V. Swartz, 2528 Westford Way, Mountain View, Calif. 94040

Filed Feb. 5, 1979, Ser. No. 9,490

Int. Cl.³ F02B 33/04; F01L 11/00; F02B 25/12

U.S. Cl. 123—73 R

3 Claims



1. An internal combustion engine of the character described comprising in combination a cylinder having adjoined at opposite ends a cylinder-head and a crankcase, a piston reciprocable in said cylinder, a scavenging-pump formed by cooperation of said piston and said crankcase, an annular recess in the head of said piston, the portion of the piston-head surrounded by said recess being referred to as a plunger, a stationary concentric sleeve suspended from said cylinder-head with transverse gas-passage-means interposed between said sleeve and said cylinder-head, a plain working-chamber formed by cooperation of said plunger with the internal cylindrical surface of said sleeve, said sleeve having a sliding fit in said recess, an annular working-chamber formed by cooperation of said piston with said cylinder and the external cylindrical surface of said sleeve, exhaust-porting in said cylinder adapted to be uncovered by

said piston completing its power-stroke toward said crankcase, transfer-porting in outer wall of said recess adapted to be uncovered by the outer surface of said sleeve as said piston completes its power-stroke, whereby said recess is placed in communication with said crankcase, transfer-porting in said sleeve adapted to be uncovered by said plunger as said piston completes its power-stroke, whereby said recess communicates with said plain working-chamber, the arrangement being such that when said piston ends its power-stroke a scavenging-path is established from said crankcase into said recess, thence through said plain working-chamber, thence in various radially-outward directions through said transverse gas-passage-means, thence through said annular working-chamber to said exhaust-porting.

4,294,202

FUEL PORTING FOR TWO CYCLE INTERNAL COMBUSTION ENGINE


Eyvind Boyesen, Kempton, Pa., assignor to Performance Industries, Inc., Kempton, Pa.

Continuation-in-part of Ser. No. 941,596, Sep. 12, 1978, Pat. No. 4,202,298, which is a continuation-in-part of Ser. No. 859,476, Dec. 12, 1977, Pat. No. 4,143,626, and a continuation-in-part of Ser. No. 839,180, Oct. 4, 1977, Pat. No. 4,161,163, which is a continuation-in-part of Ser. No. 674,102, Apr. 6, 1976, Pat. No. 4,062,331, which is a continuation-in-part of Ser. No. 586,138, Jun. 11, 1975, Pat. No. 4,051,820, which is a continuation-in-part of Ser. No. 375,065, Jun. 29, 1973, Pat. No. 3,905,340, which is a continuation-in-part of Ser. No. 282,734, Aug. 22, 1972, abandoned, and a continuation-in-part of Ser. No. 361,407, May 18, 1973, abandoned. This application Mar. 24, 1980, Ser. No. 133,098

Int. Cl.³ F02B 33/04

U.S. Cl. 123—73 PP

7 Claims



5. A variable speed, two-cycle, internal combustion engine comprising a crankcase and a cylinder having a combustion chamber, a piston working in the cylinder, a fuel chamber below the piston, port means providing communication with said fuel chamber, an intake tract in fluid communication with said port means, reed valve means disposed in the intake tract for controlling the flow of fluid through the intake tract, at least two transfer ports communicating with the combustion chamber above the piston when the piston is in bottom dead center position, transfer passages formed in the cylinder and respectively communicating with the transfer ports and with said fuel chamber for conveying fluid from the fuel chamber to the transfer ports, and fuel flow passage means interconnecting the transfer passages in a region above the piston when the piston is in bottom dead center position.

7. A variable speed, two-cycle crankcase compression, internal combustion engine, comprising: engine housing structure including a cylinder and a crankcase, a piston mounted for reciprocation in the cylinder between top and bottom dead center positions, a fuel intake chamber for receiving fuel from a supply source, reed valve means for controlling the flow of fluid through the intake chamber in a path directed substantially radially toward the bottom dead center position of the piston, and passage means formed in the engine housing struc-

ture and communicating with the intake chamber downstream of the reed valve means, the passage means including porting in the engine housing structure at least a part of which is in the cylinder wall in the bottom dead center position of the piston and provides for substantially direct flow of fuel substantially radially of the cylinder from the reed valve means into the space below the level of the lower edge of the piston at the side presented toward the porting when the piston rises substantially above the bottom dead center position, said porting being dimensioned and positioned axially of the cylinder so that a substantial part thereof extends below the level of the lower edge of the piston at the side presented toward the porting when the piston is in bottom dead center position and so that a substantial part of said porting is open to the crankcase throughout the stroke of the piston, and the passage means further including at least one portion communicating with the fuel intake chamber throughout the piston stroke and having porting through the cylinder wall above the piston in bottom dead center position and being extended through the housing structure and opening into the crankcase below the piston throughout the piston stroke.

4,294,203

INTERNAL COMBUSTION ENGINE WITH INTEGRAL UPPER CYLINDER SECTION AND HEAD


Philip E. Jones, Columbus, Ind., assignor to Cummins Engine Company, Inc., Columbus, Ind.

Filed Sep. 10, 1979, Ser. No. 74,065

Int. Cl.³ F02F 7/00, 1/10; F02B 75/18

U.S. Cl. 123—195 R

21 Claims



14. In an internal combustion engine having a crankshaft, at least one reciprocating piston connected with the crankshaft and a cylinder cavity within which the reciprocating piston moves between upper and lower limits of travel, the combination comprising

- (a) an integral head and upper cylinder section assembly containing a recess shaped to form a first portion of the cylinder cavity, said upper assembly being formed of cast iron;
- (b) an integral crankcase and lower cylinder section assembly containing the remaining portion of the cylinder cavity, said lower assembly being formed of metallic material distinct from cast iron;
- (c) connection means for connecting said upper and lower assemblies along a joiner zone;
- (d) liner means disposed within said cylinder cavity portions for guiding the reciprocating movement of the piston within the cylinder cavity, said liner means including an exterior surface spaced from the interior surface of said upper assembly recess to form a coolant cavity shaped to bring coolant into direct contact with no more than 40 percent of the total axial length of said liner means;
- (e) combustion gas seal means for sealing the upper end

portion of said liner means to form a combustion chamber; and

- (f) coolant seal means disposed adjacent said joiner zone for forming a coolant cavity seal between said liner means and at least one of said upper and lower cylinder section assemblies to cause coolant to contact directly said liner means substantially only along the portion of the liner received within said upper cylinder section assembly.

4,294,204

VEHICLE SPEED LIMITING DEVICE


Erwin E. Hurner, 2605 S. Rivershore Dr., Moorhead, Minn. 56560

Filed Jun. 18, 1979, Ser. No. 49,307

Int. Cl.³ F02B 77/00

U.S. Cl. 123—198 DB

5 Claims



1. A Vehicle Speed Limiting Device for use with diesel vehicles having fuel injection systems, said speed limiting device comprising:

- means for measuring the speed of said vehicle;
- means for comparing the output of said vehicle speed measuring means to a predetermined speed; and
- means responsive to said comparing means for interrupting of fuel flow through said injection system when said vehicle speed exceeds said predetermined speed, said interrupting means comprising a valve having an inlet and selectable first and second outlets, said injection system having a fuel pump and injector nozzles, said fuel pump having an inlet and an outlet, said valve inlet being connected to said pump outlet, said valve first outlet being connected to said injector nozzles and said valve second outlet being connected to said pump inlet and said injector nozzles, said second outlet directing a minimal amount of fuel to said nozzles and a great majority of the fuel to said pump inlet, said minimal amount having a pressure of at least 18 p.s.i.

4,294,205

INTERNAL COMBUSTION ENGINE

Masahiko Iiyama, Tokyo; Tsugio Sanka, Wako, and Kenji Naito, Kamifukuoka, all of Japan, assignors to Honda Giken Kogyo Kabushiki Kaisha, Tokyo, Japan


Division of Ser. No. 48,468, Jun. 14, 1979, abandoned. This application Nov. 20, 1980, Ser. No. 208,841

Claims priority, application Japan, Jun. 15, 1978, 53-72421; Jun. 15, 1978, 53-72422; Jun. 15, 1978, 53-72424

Int. Cl.³ F02B 19/10

U.S. Cl. 123—274

7 Claims



1. In a multi-cylinder internal combustion engine having, for each cylinder provided with a reciprocal piston therein, a main combustion chamber defined above the piston and a sub-com-

bustion chamber defined above said main combustion chamber and communicating with the latter through a torch nozzle, a carburetor having a main intake passage and a sub-intake passage for supplying a comparatively lean mixture and a comparatively rich mixture to said main and sub-combustion chambers, respectively, said carburetor comprising a single throttle valve shaft extending across said main and sub-intake passages, a main throttle valve and a sub-throttle valve disposed in said main and sub-intake passages, respectively, said main and sub-throttle valves being attached to said single throttle valve shaft, one of said main and sub-throttle valves having an outside diameter smaller than the inside diameter of the associated intake passage so that the ratio of the open areas of said main and sub-intake passages is not constant as said throttle valve shaft is operated.

4,294,207

EXTERNALLY IGNITED, FOUR-CYCLE, PISTON-TYPE INTERNAL COMBUSTION ENGINE

Michael G. May, Bel Air, Ch-1180 Rolle, Switzerland


Filed Apr. 25, 1980, Ser. No. 143,586

Claims priority, application Fed. Rep. of Germany, Aug. 28, 1979, 2934644

Int. Cl.³ F02B 3/00, 23/00

U.S. Cl. 123—279

34 Claims



1. An externally ignited, four-cycle internal combustion engine comprising a gas supply channel having an inlet valve, at least one cylinder having a head, a piston in said cylinder having a top defining with said cylinder a combustion chamber, overhead gas exchange valves having plates provided with end faces, said piston top being provided with a depression having a guide groove provided with a mouth communicating therewith, vortex producing means including a circumferential wall with said mouth in which a vortex flow of gas and air mixture to be combusted is generated rotating in a path approximately parallel to said piston top, the volume of said combustion chamber available in the top dead center position of said piston is primarily embodied by said depression in said piston top, the central longitudinal axis of said depression being provided at a distance from the longitudinal axis of said piston approximately parallel to it, the central longitudinally axis of said depression being disposed at a location between the vicinity of a connecting line of the centers of the end faces on the combustion chamber side of said valve plates within a distance from this connecting line of less than 10% of the diameter of said piston and said longitudinal axis of said depression being at a smaller or no distance from the center of one valve front face than from the center of the other valve front face, one valve front face being located at least substantially above and respectively opposite said depressions, an indentation being provided in said piston top opposite said other valve plate, said indentation having at least the diameter of said valve plate and into which the valve plate protrudes in the top dead center position of said piston, and said indentation in the top of the piston and in the cylinder head including said other valve plate being extended toward a broad and flat guide groove leading approximately tangentially into said depression of said piston, so that the vortex flow rotating in a path approximately parallel to said piston top about the central longitudinal axis of said depression is effected by means of the gas and air mixture flowing out of said guide groove into said depression toward the end of the compression stroke, and that the average depth of said guide groove at its discharge point is substantially smaller than the depth of said depression.

4,294,208

ATOMIZING SHOCK WAVE PRECOMBUSTOR

William R. Wagner, Los Angeles, Calif., assignor to Rockwell International Corporation, El Segundo, Calif.


Filed Mar. 31, 1980, Ser. No. 135,389

Int. Cl.³ F02B 19/14

U.S. Cl. 123—285


14 Claims

1. A precombustor for use in diesel engines, comprising:
a precombustion chamber;
a fuel spray nozzle port through which a fuel spray nozzle may be incorporated into said precombustion chamber;



1. An air compressing internal combustion engine having ignition means which includes in combination: a cylinder, a cylinder head sealingly connected to said cylinder, a piston reciprocally arranged in said cylinder and provided with a combustion chamber open toward said cylinder head with the inner contour of said combustion chamber being that of a body of revolution, injection nozzle means arranged in said cylinder head and having a nozzle opening directed toward said combustion chamber so that the major portion of the fuel jet injected by said injection nozzle hits the wall of said combustion chamber, and ignition means so arranged in the region of said injection nozzle that at the top dead center position of said piston said ignition means extend into said combustion chamber near said injection nozzle opening both between the pass of the fuel jet ignited already when injected through said nozzle into said combustion chamber on one hand and then said combustion chamber wall on the other hand, the area of impingement of the fuel jet on the combustion chamber wall being located in the lower section of said combustion chamber, the combustion chamber being formed as a spherical combustion chamber having a flattened bottom and a constricted throat.

a port for an ignition means adjacent to said spray nozzle port; and



a supersonic DeLaval nozzle integrally incorporated into said precombustion chamber opposite said spray nozzle, for enhancing the injection of air into said precombustion chamber.

4,294,209

INTERNAL COMBUSTION ENGINE


Erwin Eisele, Stuttgart; Hans-Peter Charzinski, Waiblingen, and Klaus Binder, Deizisau, all of Fed. Rep. of Germany, assignors to Daimler-Benz Aktiengesellschaft, Fed. Rep. of Germany

Continuation of Ser. No. 901,772, Aug. 18, 1976, abandoned, which is a continuation of Ser. No. 715,540, Aug. 18, 1976, abandoned. This application Apr. 16, 1979, Ser. No. 30,545

Int. Cl.³ F02B 3/00

U.S. Cl. 123—293

10 Claims



1. An internal combustion engine comprising a plurality of pistons disposed in cylinders, a cylinder head, a main combustion space means, recess means provided in the respective pistons for forming at least a part of the main combustion space means, an auxiliary chamber means eccentrically provided in the cylinder head, and an injection nozzle means operatively associated with the auxiliary chamber means, several discharge openings provided in said auxiliary chamber means for discharging into the main combustion space means, the direction and cross section of the discharge openings being matched to a main combustion space-air volume component of a main combustion space-air volume to be impinged upon by a jet passing through the respective discharge openings, characterized in that the discharge openings have a cross section which is substantially proportional to the main combustion space-air volume component of the main combustion space-air volume disposed in front of and impinged upon by a jet passing through the respective discharge openings when the piston is

at a position having a crankshaft angle corresponding to a center point of an area under a full-load heat-release curve for the combustion process, and in that the discharge openings are substantially directed toward a center of gravity of the respective main combustion space-air volume component of the main combustion space-air volume.

4,294,210

DISTRIBUTOR-TYPE INJECTOR PUMP, FOR MULTI-CYLINDER COMPRESSION-IGNITION INTERNAL COMBUSTION ENGINES

Cesare Bassoli; Giorgio Cornetti, and Francesco Lovisolo, all of Turin, Italy, assignors to Centro Ricerche Fiat S.p.A., Orbassano, Italy


Filed Feb. 6, 1979, Ser. No. 9,619

Claims priority, application Italy, Feb. 15, 1978, 67315 A/78

Int. Cl.³ F02M 45/02

U.S. Cl. 123—300

1 Claim



1. A fuel injection pump for a multi-cylinder compression-ignition internal combustion engine of the direct-injection type, said pump comprising:

a pump body having an internal cylindrical cavity and a compression chamber, means for the introduction of fuel in the said compression chamber,

piston means slidable within the body for compressing fuel in the said compression chamber, means defining a number of delivery apertures in the wall of the cylindrical cavity of the body for communication with each of the cylinders of the engine,

a rotary distributor member located in the said cylindrical cavity, said distributor member being rotatable by drive transmitted from the engine in use of the pump to effect one complete revolution in said cavity in each cycle of the engine,

two distinct fuel passage means, formed in said rotary distributor member and each having an inlet end permanently communicating with the compression chamber and an outlet end in the external surface of the distributor member, the outlet ends of the said passage means being situated in two areas angularly separated from each other such that they come intermittently into communication, upon rotation of the distributor member, with successive said apertures to effect, in correspondence with each fuel delivery stroke of the said piston means, two injections of fuel into two different cylinders of the engine, so that the pump delivers to each cylinder of the engine in each cycle thereof a principal injection of fuel substantially at the end of the compression stroke in said cylinder, preceded by a pre-injection of fuel,

means sensitive to the engine rotational speed for advancing the start of the delivery stroke of the piston means upon increase in the engine rotational speed, wherein the angle between the outlet ends of the said two fuel passage means is such that when the engine rotational speed is lower than a threshold value substantially equal to half the maximum speed of rotation of the engine, only one of said two fuel passage means communicates with one of said delivery

apertures during each fuel delivery stroke of said piston means, whereby only the principal injection is delivered to each cylinder of the engine in each cycle thereof when the rotational speed of the engine is lower than said threshold value.

4,294,211

METHOD AND APPARATUS FOR CORRECTING THE FUEL QUANTITY IN AN INTERNAL COMBUSTION ENGINE

Gerhard Stumpp, Stuttgart, and Wolf Wessel, Oberriexingen, both of Fed. Rep. of Germany, assignors to Robert Bosch GmbH, Stuttgart, Fed. Rep. of Germany


Filed Feb. 22, 1979, Ser. No. 14,197

Claims priority, application Fed. Rep. of Germany, Feb. 24, 1978, 2807924

Int. Cl.³ F02M 59/20

U.S. Cl. 123—379

22 Claims



1. A method for the correction of a fuel quantity apportioned to an internal combustion engine in accordance with the deviation of the same from a desired value having a fuel injection apparatus which has a control device having an apparatus for the arbitrary and/or regulatable adjustment of the fuel injection quantity per injection step characterized by the steps of measuring the fuel quantity delivered per unit of time to the fuel injection apparatus as a first control value, converting said first control value with consideration of the rpm into a second control value in accordance with the quantity of fuel injected per injection step, comparing said second control value with a desired value which is variable in accordance with at least one operational parameter, and generating a correction value in accordance with the deviation of said second control value from the desired value for the purpose of adjusting the control device of the injection apparatus.

4,294,212

AIR-FUEL RATIO CONTROL METHOD AND APPARATUS OF AN INTERNAL COMBUSTION ENGINE

Kenji Aoki, Susono, Japan, assignor to Toyota Jidosha Kogyo Kabushiki Kaisha, Toyota, Japan

Filed Apr. 11, 1978, Ser. No. 895,524

Claims priority, application Japan, Sep. 12, 1977, 52-108889

Int. Cl.³ F01N 3/15


U.S. Cl. 123—440

9 Claims

1. An air-fuel ratio control method for adjusting the amount of fuel permitted to flow into an internal combustion engine in accordance with engine condition signals comprising the steps of:

detecting engine operating conditions; generating said engine condition signals from said detected engine operating conditions, said engine condition signals being related to said detected engine operating conditions in accordance with predetermined functional relationships;

adjusting the amount of fuel permitted to flow into said engine in accordance with said engine condition signals; sensing the concentration of a predetermined exhaust gas component in the exhaust gas of said engine and generating a detected component concentration signal; producing an air-fuel ratio correction signal by integrating said detected component concentration signal with respect to time; compensating the adjusted amount of fuel permitted to flow into said engine by said engine condition signals in accordance with said air-fuel correction signal;



generating a signal corresponding to a mean value of said air-fuel ratio correction signal; adjusting at least one of said functional relationships in accordance with said generated mean value signal; and, repeating the above sequence of steps so that the said means value signal continuously approaches a predetermined value equivalent to the value of the air-fuel ratio correction signal when the compensated amount of fuel supplied in accordance with the air-fuel ratio correction signal becomes zero.

4,294,213

FUEL SUPPLYING DEVICE FOR USE IN FUEL INJECTION TYPE INTERNAL COMBUSTION ENGINE

Masaharu Sumiyoshi; Setsuro Sekiya; Katsuhiko Motosugi, all of Toyota; Junzo Uozumi, Nagoya; Tsuneo Ando, Chiryu; Yuzo Takeuchi, and Mikio Minoura, both of Nagoya, all of Japan, assignors to Aisan Industry Co., Ltd., Ohbu and Toyota Jidosha Kogyo Kabushiki Kaisha, Toyota, both of, Japan


Filed Jul. 10, 1979, Ser. No. 56,310

Claims priority, application Japan, Nov. 30, 1978, 53-147148

Int. Cl.³ F02M 39/00

U.S. Cl. 123—454

8 Claims




1. In a fuel supplying device for a fuel injection type internal combustion engine, comprising:

(a) an air horn, (b) a throttle valve disposed in said air horn, (c) an air valve disposed in said air horn upstream of said throttle valve,

- (d) a fuel metering device operatively connected to said air valve,
- (e) fuel supplying means adapted to supply fuel at a predetermined fuel pressure to said fuel metering device,
- (f) a fuel tank,
- (g) an injector arranged to discharge the fuel metered by said fuel metering device into said air horn in the vicinity of said throttle valve, and
- (h) a constant differential pressure valve arranged to maintain a predetermined differential pressure across said fuel metering device, and including a diaphragm type valve arranged to sense and amplify differential pressure across said fuel metering device, and a variable orifice type flow control device provided in said injector and arranged to operate in response to the differential pressure sensed and amplified by said diaphragm type valve,

the improvement wherein said diaphragm type valve comprises a first chamber into which the metered fuel downstream of said fuel metering device is introduced, a second chamber into which the supplied fuel upstream of said fuel metering device is introduced, a diaphragm by which said first and second chambers are separated from each other, a first spring disposed in said first chamber and arranged to bias said diaphragm toward said second chamber, and a nozzle disposed in said second chamber and provided at its end confronting said diaphragm with an introduction port and at its other end with a fuel relief port through which fuel returns to said fuel tank through a fixed orifice, while said variable orifice type flow control device comprises a metered fuel chamber into which the metered fuel is introduced, a pilot chamber into which the relieved fuel through said relief port upstream of said fixed orifice is introduced, a movable piston by which said chambers are separated from each other, a piston rod unitary with said movable piston, a second spring disposed in said metered fuel chamber and arranged to bias said movable piston toward said pilot chamber, a third spring disposed in said pilot chamber and arranged to bias said movable piston toward said metered fuel chamber, and a variable orifice actuated by said piston rod.

for regulating fuel conduct through said fuel inlet line; wherein the improvement comprises:



transducer means comprised by said fuel regulating means for transforming said unitary, electrical signals into analogous fluid pressures.

4,294,215

FUEL INJECTION SYSTEM


Waldmar Hans, Bamberg; Rudolf Sauer, Renningen; Otto Glöckler, Benningen; Ulrich Steinbrenner, Stuttgart; Dieter Günther, Murr, and Manfred Lembke, Gerlingen, all of Fed. Rep. of Germany, assignors to Robert Bosch GmbH, Stuttgart, Fed. Rep. of Germany

Filed Jul. 31, 1979, Ser. No. 62,598

Claims priority, application Fed. Rep. of Germany, Mar. 2, 1979, 2908095

Int. Cl.³ F02M 55/02; B05B 1/14
U.S. Cl. 123—470

10 Claims



1. A fuel injection system for internal combustion engines including a common fuel distributor line in which: said common distributor line includes a plurality of apertures therein; a plurality of sockets one each inserted in each of said apertures in said distributor line;

4,294,214

ENGINE COMBUSTION CONTROL SYSTEM

Edwin S. Treible, Ringoes; Joseph A. Dopkin, Hopewell, both of N.J., and Raymond N. Alford, Coopers Plains, N.Y., assignors to Ingersoll-Rand Co., Princeton, N.J.

Division of Ser. No. 96,426, Nov. 21, 1979, Pat. No. 4,263,883.

This application Oct. 20, 1980, Ser. No. 198,531

Int. Cl.³ F02B 75/10, 3/02; F02D 1/00; F16K 17/34

U.S. Cl. 123—458

7 Claims

1. An improved combustion control system for an engine having an exhaust conduit and fuel and air inlet lines, comprising temperature and oxygen sensor means, for interpositioning in the engine exhaust conduit, for: (a) admitting engine exhaust gases thereto, and (b) for emitting electrical signals representative of or analogous to both engine exhaust temperatures and engine exhaust oxygen content; signal comparator/controller means, coupled to said sensor means, for emitting discrete, unitary electrical signals derivative of said temperature and oxygen-content signals; and fuel-regulating means, for interpositioning in said fuel inlet line, coupled to said comparator/controller means and responsive to said discrete, unitary signals

a plurality of injection valves each including a body portion, an input end and an output end; said inlet end of each valve inserted into one each of said sockets; means between said injection input end of each of said valves and said sockets for sealing against leakage of fuel; said output end of each of said injection valves forming a nozzle element which can be sealably inserted into an appropriate opening correlated with an opening in an intake pipe of an internal combustion engine; separate support means, each separate support means supported by said body of one each of said injection valves; a support bracket member supported by each of said support means including a portion extending from said support means to said fuel distributor line, and each of said bracket portions extending to said distributor line includes grasping means for grasping said distributor line; whereby each of said injection valves are secured to said fuel distributor line in a tight leak-free condition.

4,294,216

AIR FUEL RATIO CONTROLLING DEVICE

Toshimi Abo, and Akio Hosaka, both of Yokohama, Japan, assignors to Nissan Motor Company, Limited, Yokohama, Japan


Filed Dec. 7, 1979, Ser. No. 101,551

Claims priority, application Japan, Dec. 8, 1978, 53-151011

Int. Cl.³ F02B 3/08; F02M 7/12

U.S. Cl. 123—489

3 Claims



1. An air fuel ratio controlling device comprising an exhaust gas sensor for detecting composition and concentration of exhaust gas of an engine, and a means for delivering a deviation signal based on a deviation between an output of said exhaust gas sensor and a reference value, the air fuel ratio of mixed gas to be supplied to the engine is feedback controlled by a control signal based on said deviation signal and the reference value is varied to match with condition of the output of the exhaust gas sensor, an improvement lies in that the device comprising a means for switching outer supply current to the exhaust gas sensor when an output voltage of the exhaust gas sensor during supply of a current of a first predetermined value becomes less than a certain predetermined value to a second predetermined value smaller than said first predetermined value and for starting feedback control from such time, and a means for previously setting an intermediate value lying between an expected value V''_x of the output voltage of the exhaust gas sensor when the mixed gas is too rich and an expected value V''_y of the same is too lean at a time of switching from said first predetermined value to said second predetermined value under the situation of too rich or too lean mixed gas and applying said intermediate value as an initial value of said reference value.

4,294,217

ELECTRICALLY CONTROLLED FUEL INJECTION APPARATUS

Otto Glöckler, Renningen, Fed. Rep. of Germany, assignor to Robert Bosch GmbH, Stuttgart, Fed. Rep. of Germany


Continuation of Ser. No. 966,232, Dec. 4, 1978, abandoned. This application Sep. 21, 1980, Ser. No. 196,501

Claims priority, application Fed. Rep. of Germany, Jan. 26, 1978, 2803266

Int. Cl.³ F02M 23/10

U.S. Cl. 123—491

9 Claims



1. An electrically controlled fuel injection apparatus for internal combustion engines comprising at least one electromagnetic injection valve which is controlled by an electronic control apparatus, a throttle valve in an intake manifold, one supplementary air valve disposed laterally within a housing and arranged to supply supplemental air so that the supplemental air bypasses said throttle valve in the intake manifold, said supplementary air valve having a movable valve member actuatable against a return force, an actuating means operating in dependence on temperature for actuating said movable valve member, an electrical heating device attached to at least a portion of said actuating means operating in dependence on temperature and capable of being switched ON in the presence of ignition impulses, a temperature-sensitive element secured on said actuating means within the supplementary air valve housing responsive to prevailing temperature within said supplementary air valve housing and the temperature of said actuating means and connected electrically with the electronic control apparatus to influence the fuel injection quantity.

4,294,218

DIFFERENTIAL TIMING ALTERING MECHANISM FOR FUEL INJECTORS

Dennis M. King, Peoria Heights, and Ronald D. Richardson, Pekin, both of Ill., assignors to Caterpillar Tractor Co., Peoria, Ill.

Filed Oct. 26, 1978, Ser. No. 955,082


Int. Cl.³ F02M 59/20

U.S. Cl. 123—502

2 Claims

1. A power plant comprising: an internal combustion engine having a rotary output; a fuel injection pump having a rotary input adapted to be driven by said rotary output in timed relation thereto; means interconnecting said input and output comprising first and second bevel gears mounted, in spaced relation, for rotation about a common axis, the facing sides of said bevel gears having facing teeth in aligned relationship, one of said bevel gears being connected to said input and the other of said bevel gears being connected to said output, at least one pinion gear disposed in the space between said bevel gears and having teeth in engagement with the teeth of both said bevel gears, a carrier disposed between said bevel gears and mounted for rotation about said common axis, said carrier further journalling said pinion gear for rotation about an axis between said bevel gears and extending generally radially of said common axis, and selectively operable means connected to said carrier for bidirectionally moving the same to shift said third gear to selectively alter the phasing between said engine and said fuel pump; and

said selectively operable means including a shaft mounted for rotation about a fixed axis spaced from, but generally parallel to said common axis, an eccentric mounted on said



shaft, a pair of spaced surfaces on said carrier partially surrounding said eccentric, and a motor affixed to said shaft to rotate the same.

4,294,219


FUEL HEATING SYSTEM FOR AN ENGINE

Bryant T. Rowe, P.O. Box 605, Louisburg, N.C. 27549
Filed Aug. 27, 1979, Ser. No. 70,017

Int. Cl.³ F02M 31/00

U.S. Cl. 123-557

1 Claim



1. A device and system for improving the performance and fuel economy of an engine of the type having a radiator cooling system and a fuel pump for directing fuel to the carburetor, said device and system comprising: a generally elongated fuel chamber having a longitudinal axis and a pair of end walls and a connecting surrounding wall structure extending between said end walls that define a closed fuel chamber therein; fuel inlet port means formed off center in one end wall of said fuel chamber and communicatively connected to receive fuel being pumped by said fuel pump; fuel outlet port means formed off center in said other end wall of said fuel chamber and communicatively connected to a line leading to said carburetor for delivering fuel thereto and wherein said fuel inlet and outlet port means are disposed on opposite sides of said longitudinal axis of said fuel chamber; a heating line operatively connected to said radiator cooling system and extending generally centrally through said fuel chamber for heating fuel contained therein, said heating line including inlet and outlet ends formed

generally centrally within opposite end walls of said fuel chamber in general parallel alignment with said fuel inlet and outlet means; said fuel inlet port means being formed in the same end wall of said fuel chamber as said outlet end of said heating line while said fuel outlet port means is formed in the opposite end wall of said fuel chamber generally adjacent said inlet end of said heating line; said inlet end of said heating line being operatively connected within said radiator cooling system to a hot water line leaving said engine such that fuel entering said fuel chamber enters the side thereof where hot water enters; and means for varying the resulting heated liquid-vapor state of fuel passing through said chamber and wherein said means for varying the resulting state of the fuel is provided for by the relative disposition of said heating line and said fuel inlet and outlet port means formed about the end walls of said fuel chamber in that by rotating said fuel chamber about said longitudinal axis of said fuel chamber and the axis of said heating line, said fuel outlet port means may be elevated with respect to said fuel inlet means and accordingly the liquid-vapor state of the existing fuel may be varied and adjusted accordingly.

4,294,220


INTAKE PORT MEANS FOR EXTRACTING ENGINE EXHAUST GAS FOR RECIRCULATION

Seishi Yasuhara, Yokosuka, and Eiichi Ohnishi, Tokyo, both of Japan, assignors to Nissan Motor Co., Ltd., Yokohama, Japan
Filed Jan. 14, 1980, Ser. No. 111,555

Claims priority, application Japan, Jan. 17, 1979, 54/4411[U]
Int. Cl.³ F02M 25/06

U.S. Cl. 123-568

10 Claims



1. An intake port means for extracting engine exhaust gas for recirculation in an internal combustion engine having an exhaust gas recirculation (EGR) system, comprising an intake port means formed of an EGR pipe and having an extracting aperture placed in a stream of the engine exhaust gas, and a cover having a closed end lying on the upstream side of said aperture while having an open end facing the downstream side of said aperture in such a manner that the engine exhaust gas is extracted through trailing portion of the open end of the cover.

4,294,221

DEVICE FOR RETAINING A COMPOUND BOW IN A PARTIALLY DRAWN CONDITION

LeRoy J. Bryant, 2704 SE. 170th Ave., Portland, Oreg. 97236
Filed May 3, 1979, Ser. No. 15,062


Int. Cl.³ F41B 5/00

U.S. Cl. 124-23 R

11 Claims

1. In a compound bow having a pair of flexible limbs and a pair of eccentric wheels, one of said pair of eccentric wheels being associated with each of said limbs, and the axes of rotation of the eccentric wheels being parallel to one another and extending transversely of the direction of flexure of said limbs, a pair of cables, each of said cables having an end and being wrapped around one of said eccentric wheels, attachment means connecting said end of each said cable to a respective end of a bowstring, and means for preventing slippage of each cable relative to the respective eccentric wheel around which it is wrapped, the improvement comprising:

(a) unidirectional motion-limiting and retention means interconnected with one of said eccentric wheels for allowing said one of said eccentric wheels to rotate substantially only in a first direction until it has rotated a predetermined angular distance in said first direction; and



(b) release means for deactivating said retention means and allowing free rotation of said one of said eccentric wheels after it has rotated through said predetermined angular distance in said first direction.

4,294,222


PISTON TYPE CROSSBOW

Henry F. Pelsue, 8421 Foothill Blvd., Sunland, Calif. 91040
Filed Dec. 31, 1979, Ser. No. 108,636

Int. Cl.³ F41B 5/00

U.S. Cl. 124-25

8 Claims



1. A crossbow comprising:
an elongated stock having a pistol grip integrally formed on one end thereof;
a flexible bow carried on the opposite end of said stock from its end having said pistol grip;
hinge means interconnecting said bow at its mid-section to said stock so that said bow has a storage position lying parallel to the longitudinal axis of said stock and an operable position lying laterally across the longitudinal axis of said stock;
latch means releasably connecting said bow to said stock adapted to secure said bow to said stock in said operable position;
said bow having a string extending between the opposite ends of said bow;
a cocking mechanism carried on said stock operable to draw said string into a taut condition;
a trigger means operably carried on said stock for releasing said bow string;
said cocking mechanism includes a rotatable rod with re-

spect to said stock having a catch selectively engagable with said bow string for drawing said bow string taut; said cocking mechanism further includes said stock having a longitudinal slot rotatably carrying said rod;
a finger grip carried on the rear end of said rod with said catch carried on the opposite end thereof; and
a recess formed in said stock coextensive with said slot adapted to receive said catch when said rod is rotated so as to not interfere with said bow string during release of said bow string by said trigger mechanism.

4,294,223



BI-LOOP HEAT RECOVERY SYSTEM FOR AN OIL FIRED FURNACE

Albert Montague, 1689 Blue Jay Lane, Cherry Hill, N.J. 08003
Continuation-in-part of Ser. No. 7,412, Jan. 29, 1979, which is a continuation-in-part of Ser. No. 838,749, Oct. 3, 1977, abandoned. This application Sep. 4, 1979, Ser. No. 72,086

Int. Cl.³ F24H 3/00; F23L 3/00; F24B 7/00

U.S. Cl. 126-112

5 Claims



1. In a furnace located in an enclosure, the furnace having a burner, a blower coupled to the burner, an exhaust duct to convey products of combustion from the furnace to a stack, said exhaust duct having a barometric draft regulator, an improved system comprising:

(a) heat exchange means which can be quickly and easily coupled to the exhaust duct to provide a first zone to carry the products of combustion, and a second zone in heat flow communication with the first zone to carry a stream of air;
(b) first conduit means which can be quickly and easily coupled to provide gas flow communication between a point outside the enclosure and the second zone of said heat exchange means;
(c) second conduit means which can be quickly and easily coupled to provide gas flow communication between said point outside the enclosure and the barometric draft regulator; and
(d) third conduit means which can be quickly and easily coupled to provide gas flow communication between the second zone of said heat exchange means and the blower whereby air for combustion in the burner is supplied from said point outside the enclosure, and air is supplied to the barometric draft regulator from the same point outside the enclosure.

4,294,224

FIREPLACE SCREEN AND SHIELD ASSEMBLY


Walter C. Luther, Sr., Rte. 8, Box 267, Lake City, Fla. 32055

Filed Sep. 4, 1979, Ser. No. 72,123

Int. Cl.³ F23L 5/02

U.S. Cl. 126—135

5 Claims



1. A fire screen and shield apparatus for use with a fireplace including a hearth, a generally vertical wall having an opening having a top, a bottom, and connecting side edges, said apparatus comprising in combination:

a generally rectangular frame including a pair of side members and top and bottom cross members interconnecting said side members defining an opening at least as large as said fireplace opening, said frame being adapted to lean against said vertical wall with the base of said side members resting on said hearth at a position removed from said wall and the upper ends of said side members resting against said wall at a position at or above said top of said opening,

a curtain formed of a fireproof fabric of a height and width at least as great as said opening for completely shielding said fireplace opening, said curtain including a transverse rod at the upper end thereof, a transverse rod at the lower end thereof, and a plurality of stiffening rods extending transversely of the curtain at spaced intervals therebetween, the opposite ends of said rods projecting laterally beyond the vertical side edges of said curtain,

a metal screen of a height and width at least as great as said fireplace opening for preventing sparks from being projected from said fireplace beyond said screen, said screen including a transverse support rod at the upper end thereof,

said frame including support means at the upper ends of said side members, said support means being adapted to receive the projecting ends of the top rod of said curtain to mount and support said curtain and to receive the projecting ends of said stiffening rods and said bottom rod such that said rods may be selectively disposed therein for selectively positioning the bottom rod and thereby the lower end of said curtain between a closed position wherein the bottom rod rests on the hearth, an open position wherein the bottom rod and stiffening rods are received in said support means, and a draft position wherein said bottom rod is raised off said hearth for permitting draft along the fireplace floor and for preventing smoke from entering the room through the fireplace opening, and to receive said screen support rod to mount and support said screen at least when said curtain is in its open position.

4,294,225

DIVER HEATER SYSTEM


Kenneth E. Mayo, Nashua, N.H., assignor to Energy Systems Corporation, Nashua, N.H.

Filed May 22, 1979, Ser. No. 41,537

Int. Cl.³ A61F 7/06

U.S. Cl. 126—204

6 Claims



1. A heater for warming the body of a diver while under water comprising a housing, having a fluid inlet, a combustion chamber, means for supplying air and means for supplying fuel to said chamber of combustion therein, and means for exhausting the products of combustion, a fluid heat exchanger arranged in association with said combustion chamber, a pump for circulating fluid through said heat exchanger to be heated, electric motor means for operating said pump, and thermoelectric means mounted in association with said combustion chamber for converting a portion of said heat to electrical energy and means for passing said electrical energy to said motor to operate said pump, said pump having means for passing the heated fluid to the diver said means for supplying said fuel comprises a fuel storage canister removably securable to said housing in combination with the exhaust means from said combustion chamber to cause said fuel storage canister to be heated by said exhaust.

4,294,226

AUTOMATIC FURNACE VENT DAMPER CONTROL


Emanuel Feinberg, 24316 Martha Washington, Southfield, Mich. 48075

Filed Jan. 21, 1980, Ser. No. 113,992

Int. Cl.³ F23L 3/00

U.S. Cl. 126—286

9 Claims



1. A temperature responsive damper system for use with a burner having a vent for combustion gases, comprising: a rotatable damper shaft supported in the vent to extend transversely across the vent; a planar damper fixed to the shaft so as to extend in a closed position transversely to the vent and block passage of air through the vent when the shaft is in a first rotational position and to extend in an open position parallel to the longitudinal axis of the vent to allow gas passage through the vent when the shaft is in a second rotational position; a fluid reservoir supported in the vent between the damper and the burner so that the reservoir experiences a temperature

which depends upon the state of operation of the burner; a fluid contained in the reservoir having a liquid state when the reservoir temperature is that obtained when the burner is not in operation and a gaseous state when the reservoir temperature is that obtained when the burner is in operation; a linear actuator supported for movement between a first position and a second position; a cam mechanism fixed to the damper shaft and connected to the linear actuator so that the damper is in an open position when said actuator is in a first position and the damper is in a closed position when the actuator is in the second position; and means for moving the actuator from its first position to the second position upon transition of the fluid within the reservoir from a liquid to a gas as a result of an increase in temperature in the reservoir resulting from the burner going into operation, and from its second position to its first position upon transition of the fluid from a gas to a liquid as a result of a decrease in the temperature of the reservoir resulting from the burner going out of operation; whereby said damper assumes its open position when the burner is in operation and its closed position when the burner is not in operation.

4,294,227

APPARATUS FOR HEATING WATER BY SOLAR HEAT

Ursula Kreibich, Riehen, and Rolf Schmid, Gelterkinden, both of Switzerland, assignors to CIBA-GEIGY Corporation, Ardsley, N.Y.


Filed Jun. 11, 1979, Ser. No. 47,548

Claims priority, application Switzerland, Jun. 16, 1978, 6581/78; Aug. 29, 1978, 9114/78

Int. Cl.³ F24J 3/02

U.S. Cl. 126—400

18 Claims



1. Apparatus for heating water by solar energy, comprising a solar collector, a latent-heat storage means, first and second heat exchangers, and a service-water outlet side, the first exchanger operating at a lower temperature than the second, each of said heat exchangers comprising a container having a first heat exchange material therein, a first conduit passing through said container for conveying a second heat exchange material in indirect heat exchange with said first heat exchange material and a second conduit passing through said container conveying a third heat exchange material in indirect-heat exchange with said first heat exchange material, storage means the second conduit of each heat exchanger being connected in series on the service water outlet side, means coupling the heat exchangers to the collector to form three circuits, the first containing the collector and the first heat exchanger, the second containing the collector, the storage means and the second heat exchanger, and the third containing the storage means and the second heat exchanger, a circulating means in each circuit, and

a plurality of sensors to sense the temperature of the circulating medium in the collector, the operating temperatures of the two heat exchangers and the temperature of the storage means, and a control circuit responsive to said sensors to, activate the first circuit if the collector temperature is

higher than the operating temperature of the first heat exchanger and lower than that of the second heat exchanger,

activate the second circuit if the collector temperature is higher than the operating temperature of the second heat exchanger, and

activate the third circuit if the collector temperature is lower than the operating temperature of the first heat exchanger and if the temperature of the storage means is simultaneously higher than the operating temperature of the second heat exchanger.

4,294,228

SOLAR HEATING AND SUBTERRANEAN COOLING


Robert Kruger, 412 N. Burnt Mill Rd., Ashland, N.J. 08003, and William J. Miller, Chalet Apartments, Tusc.-A, Pine Hill, N.J. 08021

Filed Nov. 9, 1978, Ser. No. 959,123

Int. Cl.³ F24J 3/02; F24H 9/08; E04B 1/74

U.S. Cl. 126—430

24 Claims



1. A solar heating system for a structure comprising: at least one transparent portion; at least one heat conducting chamber for heating a fluid medium contained within said chamber by means of solar energy admitted to said chamber through said transparent portion, said heat conducting chamber further comprising a plurality of heat conducting elements disposed within said chamber; and a fluid medium distribution means associated with said chamber for receiving the heated fluid from said chamber and distributing it to utilization areas, said structure and said transparent portion are both pyramidal in shape, said transparent portion comprising at least one corner of said structure, said transparent portion comprises the apex portion of said structure, said plurality of heat conducting elements comprises a plurality of different size heat conducting boxes disposed in a nesting array, each box having at least three side walls.

4,294,229

THERMOSIPHONING MODULE FOR ENVIRONMENTALLY DRIVEN HEATING AND COOLING SYSTEM

Timothy Maloney, Mountain Falls, Va., assignor to One Design, Inc., Mountain Falls, Va.

Continuation-in-part of Ser. No. 941,735, Sep. 12, 1978. This application Sep. 13, 1978, Ser. No. 942,133

Int. Cl.³ F24J 3/02; F16K 31/18

U.S. Cl. 126—434

19 Claims



1. A thermosiphoning module for an environmentally driven heating and cooling system utilizing a heat-transfer liquid, said module comprising:

a hollow body defining a liquid-tight interior space; a partition arranged within the hollow body for dividing the interior of the hollow body into an outer compartment and an inner compartment;

a first upper opening adjacent the top of the hollow body defining a liquid flow passageway past the partition intercommunicating the inner and outer compartments;

a second lower opening adjacent the bottom of the hollow

body defining a liquid flow passageway past the partition intercommunicating the inner and outer compartments; a check valve disposed in one said openings for restricting liquid flow to one direction in a loop defined by the inner and outer compartments and the upper and lower openings, said check valve including a generally tubular shaped housing having an internal chamber, two generally opposed series of slots extending through said tubular housing, each series including a plurality of slots, said series defining inlet and outlet ports to said internal chamber, respectively, and a buoyant rod-like member disposed within said chamber for controlling the flow of liquid through said valve by selectively blocking one of said inlet and said outlet ports; and



port means into said hollow body, for filling the body with said heat-transfer liquid for flow along said loop.

19. A reversible check valve for a liquid flow system comprising:

a generally tubular shaped housing having an internal chamber; two generally opposed series of slots extending through said housing, each series including a plurality of slots, said series defining inlet and outlet ports to said internal chamber and a rod-like member buoyant in said liquid, disposed within said chamber for controlling the flow of liquid through said valve by selectively blocking one of said inlet and outlet ports.

4,294,230

SOLAR ENERGY COLLECTION PANEL AND METHOD
Jerome H. Lemelson, 85 Rector St., Metuchen, N.J. 08840

Filed Jun. 25, 1979, Ser. No. 51,869
Int. Cl.³ F24J 3/02

U.S. Cl. 126-438


11 Claims

1. A solar energy unit comprising an integral unitary metal panel structure having a front face adapted to receive solar energy, said unitary panel structure containing a plurality of closely spaced parallel cavities formed therein and extending inwardly of said front face of said panel structure, said cavities having side wall portions which converge inwardly toward each other, each of said cavities having a bottom wall portion joining said side wall portions together,

said side wall portions of said cavities of said unitary panel structure being highly reflective of sunlight directed against the face of said panel structure containing said cavities and being angled to reflect such sunlight between

said converging wall portions toward the bottom of each cavity,

the bottom wall portion of each of said cavities having a sunlight absorbing material to permit sunlight which is directed into the cavities and reflected off the side wall portions of the cavities to be absorbed by said bottom wall portions, whereby concentrated heat of the absorbed sunlight will be conducted from the locations where the energy is absorbed through bottom portions of the panel structure,



a plurality of parallel fluid conduits underlying said bottom portions and coextensive with said cavities and formed integral within and extending through said unitary panel structure and containing heat transfer fluid in closely spaced heat transfer relationship with respective bottom portions of said panel structure which are directly aligned with said cavities therein,

said conduits containing heat transfer fluid adapted to receive heat transferred thereto through said bottom wall portions of said cavities of said panel structure and being aligned with respective of said cavities.

4,294,231

HEAT INSULATOR

Marcel J. E. Golay, 1095 Lutry, Vd, Switzerland
Continuation of Ser. No. 833,253, Sep. 14, 1977, abandoned,


which is a continuation of Ser. No. 591,694, Jun. 30, 1975, Pat. No. 4,084,574. This application Jun. 22, 1979, Ser. No. 51,162

The portion of the term of this patent subsequent to Apr. 18, 1995, has been disclaimed.

Int. Cl.³ F24J 3/02

U.S. Cl. 126-441

6 Claims



1. Radiant heat absorbing apparatus comprising a housing having at least one clear side, radiation absorbing means in said housing comprising a radiation absorbing surface facing said clear side, a radiation transparent plate closing said clear side of the housing and a plurality of ribbon-like elements of relatively low thermal conductivity insulating material spaced apart a distance not exceeding about 1 centimeter and positioned substantially normal to, between and spaced from said radiation absorbing surface and said transparent plate to restrict circulation of gas between said surface and said plate and

minimize loss of heat through convection while introducing negligible heat bypass between said surface and said plate.

4,294,232

SOLAR COLLECTOR

Jean-Louis Boy-Marcotte, Orsay; Henri D. M. Junot, Paris; Richard J. A. M. Grossin, Rueil-Malmaison, and Philippe J. M. R. Chevalier, Garancieres, all of France, assignors to Bertin & Cie, Plaisir, France


Filed Dec. 10, 1979, Ser. No. 101,575

Claims priority, application France, Dec. 8, 1978, 78 34553

Int. Cl.³ F24J 3/02

U.S. Cl. 126-443

8 Claims



1. A solar energy absorber unit of the evacuated flat-plate collector type, comprising the combination of:

a gastight enclosure designed for long-duration maintenance inside thereof of a high-order vacuum, said enclosure being made up of two opposite half-shells of glass which are glass-welded to each other all along their mating peripheries to form together an integral all-glass, airtight envelope having a generally flattened front-side window designed for exposure to the sun and a corresponding rear-side closure opposite said front-side window,

a solar-radiation flat-plate collector suspended inside said enclosure by a light-weight low-conduction suspension secured to the wall of said envelope, to thereby stretch out behind said front-side window in non-conductive thermal relationship with said wall, at least the sun-exposed front-side face of said flat-plate collector bearing a selective coating adapted to increase solar radiation absorption and reduce infrared emission, and

a radiant screen formed of sheet material having low infrared emissivity, and in spaced relationship between said flat-plate collector and said rear-side closure, adjacent and generally parallel to the non sun-exposed rear-side face of said flat-plate collector to minimize radiation losses thereof and said solar screen being supported from said flat plate collector and out of physical contact with said rear side closure.

4,294,233

SLACK ABSORBING DEVICE FOR AN ENDOSCOPE

Nagashige Takahashi, Tokyo, Japan, assignor to Kabushiki Kaisha Medos Kenkyusho, Tokyo, Japan


Filed Apr. 5, 1979, Ser. No. 27,418

Claims priority, application Japan, Apr. 12, 1978, 53/47865[U]

Int. Cl.³ A61B 1/00

U.S. Cl. 128-4

7 Claims



1. An endoscope having a distal and a proximal end, a man-

ual operating section adjacent the proximal end and a bending section adjacent the distal end, a plurality of elongated passageways in said manual operating section extending lengthwise of said endoscope, a plurality of slack absorbing members, one said member being mounted for slidable movement in each said passageway, said slack absorbing members being connected to said operating section such that they are movable along the length of said endoscope within said passageways as said operating section is operated, each of said slack absorbing members being elongated in the direction of said movement and having a centrally located elongated groove extending in the direction of said movement, said groove having a threaded portion, at least two twisted wires each having two ends, one end of each wire being connected to said bending section and the other ends of said wires being connected to different ones of said slack absorbing members such that when said manual operating section is operated said wires are moved in such a way that said bending section bends, said wires having threaded rods connected to said other ends whereby said threaded rods are moved together with said wires at least when said wires are pulled towards said manual operating section, said passageways being partially defined by a removable cover member, said threaded rods being provided with an end piece, each threaded groove having an open portion extending for at least the length of said threaded portion such that when said cover member is removed each of said threaded rods are engageable with a respective threaded groove by positioning said threaded rods above said threaded grooves and lowering said rods into said grooves, said cover member and said end pieces being positioned and sized such that they prevent removal of said rods from said grooves.

4,294,234

ENDOSCOPE


Kazumasa Matsuo, Hachioji, Japan, assignor to Olympus Optical Co., Ltd., Tokyo, Japan

Filed Jun. 22, 1979, Ser. No. 51,034

Int. Cl.³ A61B 1/00

U.S. Cl. 128-6

5 Claims



1. An endoscope comprising:
an elongated rigid sheath to be inserted into a body cavity, said sheath having a base end and a distal end;
a control section housing having a side wall and an end wall connected to the base end of the sheath;
a rigid channel tube inserted within the sheath along the length of the sheath to permit an instrument such as catheter to be inserted therein, said channel tube having a base end extended into the housing and a distal end opened at the distal end of the sheath;
an insertion hole formed in the side wall of said control section housing;
an extension guide having an outer free end and an inserted end slantwise inserted into the housing through the insertion hole;
an eyepiece fitted over the outer free end of the extension guide;
an optical fiber bundle having a straight portion disposed in the sheath, a distal end extended in the distal end of the sheath, a base end portion bent relative to the straight portion, and a base end, said bundle being made rigidly in

the glass rodlike form over substantially the whole length; and opening means mounted on the inserted end of the extension guide for introducing the base end portion of the fiber bundle into the insertion guide, so that said base end of the fiber bundle is optically coupled to the eyepiece, said opening means comprising an elongated cut out formed in said extension guide along the axial direction thereof and opened at the inserted end of the extension guide.

4,294,235

LARYNGOSCOPE

Karl Storz, Auf dem Schildrain 39, 7200 Tuttlingen, Fed. Rep. of Germany


Filed Nov. 13, 1978, Ser. No. 959,703

Claims priority, application Fed. Rep. of Germany, Nov. 27, 1977, 2751990

Int. Cl.³ A61B 1/06, 1/26

U.S. Cl. 128—11

3 Claims



1. An injection breathing laryngoscope comprising: a laryngoscope tube having a proximal and a distal end, an axis, and an inner wall defining an axial passage from end to end, an insert tube having a proximal and a distal end, an axis, an inner wall defining an axial passage from end to end, and an outer wall so proportioned and arranged as rotatably to fit in said inner wall of said laryngoscope tube entering the proximal end of said laryngoscope tube, and having an axial length substantially shorter than that of the laryngoscope tube so that its distal end lies within said laryngoscope tube and substantially spaced from the distal end of said laryngoscope tube; fiber optics means and a breathing gas tube inside the insert tube passage and attached to said insert tube and terminating at said distal end of said insert tube, said inner wall of said laryngoscope tube and said outer wall of said insert tube having matching conical axially extending locking tapers, whereby said tubes can be rotated relative to one another with said tubes axially spaced apart, and locked in an adjusted position by pressing them axially together, and in which said laryngoscope tube flares outwardly from a medial location to its distal end.

4,294,236

FOOT EXERCISER

Steven R. Hofstein, North Brunswick, N.J., assignor to World Medical Marketing Corporation, New York, N.Y.

Division of Ser. No. 85,330, Oct. 29, 1979, This application Jan. 14, 1980, Ser. No. 111,876

The portion of the term of this patent subsequent to Jul. 28, 1998, has been disclaimed.


Int. Cl.³ A61H 1/02

U.S. Cl. 128—25 B

2 Claims

1. A foot exercising device, comprising: a pair of foot pedals; motor means for reciprocating said foot pedals; blood flow detector means for detecting the flow of blood through a leg of a patient using said foot exercising device;

control means for controlling the operation of said motor means as a function of the blood flow through said patient as detected by said blood flow detector means, said control means causing the said motor means to vary the recip-



rocation frequency of said pedals as a function of said blood flow signal; and display means responsive to said blood flow signal for providing a visual indication of said blood flow.

4,294,237

SPLINT FOR REDUCING FRACTURES OF THE METACARPALS


Calvin H. Frazier, 1808 Verdugo Blvd., Glendale, Calif. 91208

Filed Dec. 26, 1979, Ser. No. 107,025

Int. Cl.³ A61F 5/10

U.S. Cl. 128—77

9 Claims



1. An apparatus for reducing a fracture of the metacarpal comprising:

a generally rigid foundation having a reducing portion overlying the dorsum of the hand adjacent at least one metacarpal of said hand, said reducing portion being generally coplanar to said dorsum, and a support portion whose longitudinal cross section has a curved shape that is shaped complementary to the ulnar side of said hand, said support portion extending from said dorsum around said ulnar side of said hand and terminating in a support end, said support end being generally coplanar to the palm of said hand and having a width that exceeds the width of said reducing portion;

means for securing said foundation to said hand, said means being adjustable to compensate for variations in sizes of hands; and

means for reducing the apex of said fracture, said means comprising a threaded shaft mounting at an upper end an adjusting knob and an aperture in said reducing portion of said foundation adapted to receive said shaft connected to said reducing portion and mounting at a lower end adjacent said hand a pressure distributing plate, said means adapted for adjustable advancement of said plate from a first position adjacent said reducing portion to at least one other position further below said reducing end.

4,294,238

LOWER LIMB MUSCLE AID DEVICE


Thomas J. Woodford, Benton Harbor, Mich., assignor to Stephen C. Small, Benton Harbor, Mich., a part interest

Filed Sep. 21, 1979, Ser. No. 77,600

Int. Cl.³ A61F 3/00

U.S. Cl. 128—80 G

10 Claims



1. A device for assisting and relaxing a user's leg muscles in and after physical activities such as jogging, said device comprising:

a strap member having a top end, a bottom end, and an elastic midportion having a width substantially the width of a user's heel;

a first securing means extending from said top end and defining means for releasably encircling the user's leg adjacent the knee for securing said top end of the strap member thereto; and

a second securing means extending from said bottom end and defining means for releasably encircling the user's foot for securing said bottom end of the strap member thereto with said midportion stretchably retained against the calf of the user's leg and said bottom end extending around the user's heel and underlying the arch of the user's foot for providing a supportive force on the user's leg during a physical activity such as jogging.

4,294,239

STEADY SUPPORT ABDOMINAL SPLINT


W. Wayne Oram, 2108 Chambwood Dr., Charlotte, N.C. 28205; Nora L. Oram, 525 Manhasset Rd., Charlotte, N.C. 28209, and Robert W. Boris, 405 Bluegrass Dr., Morristown, Tenn. 37814

Filed Apr. 6, 1979, Ser. No. 27,766

Int. Cl.³ A61F 5/24, 5/28, 5/30

U.S. Cl. 128—96

2 Claims



1. A splint supporting the front abdomen of a human body and directing pressure to localized regions of the abdomen of a human body, comprising a molded pad of resilient material formed in an approximate U-shape with a front portion of substantially uniform thickness and height and including top edge, bottom edge, convex outer surface, concave body facing surface, and opposite end portions, said end portions being curved with respect to said front portion to extend partially about the sides of the abdomen of the human body, said front portion merging into said end portions and each end portion

symmetrically diminished in height and the outer surface of each end portion tapered toward its body facing surface whereby the thickness of each end portion is diminished, said body facing surface being of a width sufficient to span the width of the human body across the abdomen and said pad being of a height sufficient to approximately cover the abdominal area of the body without extending over the thorax and formed in a size and shape along said body facing surface for conforming to the shape of the front abdominal area of the human body, the material of said pad having a density of between 2.5 and 3.5 pounds per cubic foot and a load bearing (ILD) of a twenty-five percent load deflection value at between 25 and 35 pounds, strap means for extending from said end portions and about the abdomen to urge said pad in constant contact with the abdomen to apply approximately uniform support pressure to the abdomen, said end portions being of a height at least as wide as said strap means, said pad being fabricated of material sufficiently flexible to permit a force applied externally to the pad to transmit localized pressure through the pad to the abdomen, whereby the pad is held by the strap against the abdomen and the wearer can press inwardly with his hand against the outside surface of the pad when coughing to apply additional pressure to a localized area of the abdomen.

4,294,240

PERFORATED CLOSED CELL PADDING MATERIAL


Gary A. Thill, Saint Paul, Minn., assignor to Minnesota Mining and Manufacturing Company, Saint Paul, Minn.

Continuation of Ser. No. 815,857, Jul. 14, 1977, abandoned. This application Aug. 17, 1979, Ser. No. 67,394

Int. Cl.³ A61L 15/00

U.S. Cl. 128—156

8 Claims



1. A combination for rendering a portion of the body relatively immobile, said combination comprising an orthopedic device which renders the portion of the body relatively immobile and a padding material, said padding material consisting essentially of a closed cell polymeric foam, said foam being water repellent at least to the extent that water penetrates the foam with difficulty, said padding material being conformable, being resiliently compressible, containing perforations capable of passing perspiration from human skin therethrough and being elastic in the longitudinal direction.

4,294,241

COLLAGEN SKIN DRESSING

Teruo Miyata, No. 314, 3-6-29, Shimochiai, Shinjuku-ku, Tokyo, Japan

Continuation-in-part of Ser. No. 805,003, Jun. 9, 1977, abandoned. This application Oct. 19, 1979, Ser. No. 86,547

Int. Cl.³ A61L 15/00

U.S. Cl. 128—156

8 Claims

5. A method for the preparation of a collagen skin dressing in sheet from whose upper and lower surfaces possess differing porosity characteristics which comprises the steps of:

(a) treating a source of collagen with a proteolytic enzyme to form a telopeptide-poor, monomolecularly dispersed atelocollagen extract,

- (b) precipitating atelocollagen from the extract,
- (c) purifying the precipitated atelocollagen by redissolving and reprecipitation,
- (d) converting the extracted, purified atelocollagen to a gel,
- (e) extruding the atelocollagen gel through a circular extrusion nozzle in a coagulation bath,
- (f) recovering atelocollagen in tubular form from the coagulation bath,
- (g) slitting the tubular collagen longitudinally to form a collagen sheet therefrom,
- (h) cross-linking the longitudinal sheet,
- (i) partially air-drying the cross-linked sheet, and
- (j) freeze-drying the partially air-dried sheet whereby the upper surface of said sheet becomes more concentrated in atelocollagen content with the lower surface thereof.

4,294,242

SURVIVAL SYSTEM


Kenneth W. Cowans, Encino, Calif., assignor to Kinergetics, Inc., Tarzana, Calif.

Filed Mar. 31, 1980, Ser. No. 135,979

Int. Cl.³ A62B 7/10

U.S. Cl. 128—201.13

13 Claims



1. A passive system for reducing the thermal energy losses of a person in a confined cold hyperbaric environment, comprising:

insulative means for encompassing the person at all but the face region, the insulative means having at least four inches of conductive path length and comprising interior fibrous insulation providing minimal interior convection currents;

carbon dioxide scrubber means disposed within the insulative means and coupled to receive expiratory flows from the person, such that the heat and moisture in the expiratory flows together with the encompassing insulative means establish an efficient exothermic reaction contributing heat to the person; and

regenerator means coupled to receive expiratory flow from the scrubber means and communicating with the environment to provide inspiratory flows from said scrubber means therethrough to the person, the regenerator means being configured to couple expiratory flows to the environment while storing heat and moisture contained therein, and to give up the heat and moisture to inspiratory flows.

4,294,243

RESPIRATORS

John Ernsting, Fleet; Thomas R. Morgan, Farnborough; Leonard F. W. Palmer, Aldershot; Alfred J. Rivers, Church Crookham, all of England, and Stephen M. Robson, RAF St. Athan, Wales, assignors to The United States of America as represented by the Secretary of the Air Force, Washington, D.C.

Filed Dec. 8, 1978, Ser. No. 967,122

Int. Cl.³ A62B 7/00


U.S. Cl. 128—201.18

8 Claims

1. An oro-nasal respirator, comprising:

- a. a visor;
- b. a mask carried by said visor, said mask having a shape adapted to cover the nose and mouth of the wearer;

- c. means for providing respiratory gas to the wearer through said mask;
- d. means attached to said mask for selectively occluding the wearer's nose; said last mentioned means including a pair of spaced apart pivots penetrating through said mask in



the nasal region thereof; yoke arms extending radially from said pivots on the inside of said mask; a handle secured to said pivots on the outside of said mask; said handle operable to rotate said pivots and cause said yoke arms to turn into the sides of the wearer's nose.

4,294,244

RESPIRATOR WITH A COOLING DEVICE

Adalbert Pasternack, Bad Schwartau, Fed. Rep. of Germany, assignor to Drägerwerk Aktiengesellschaft, Fed. Rep. of Germany


Filed Jan. 28, 1980, Ser. No. 115,877

Claims priority, application Fed. Rep. of Germany, Feb. 2, 1979, 2903920

Int. Cl.³ A62B 7/08

U.S. Cl. 128—202.26

1 Claim



1. In combination with a respirator of the type having a carrying frame, a chemical cartridge mounted to the carrying frame for binding carbon dioxide or forming oxygen or both, a breathing bag mounted to the frame and an oxygen supply container mounted to the frame, means for communicating said cartridge, breathing bag and supply container such that exhaled gas from a user is recirculated therethrough for rebreathing, wherein the frame includes ducting means for passing a cooling gas flow over the oxygen container, the breathing bag and the cartridge, a vest adapted to be worn by a person comprising an outer wall of flexible material, an inner wall of flexible material spaced from the outer wall to define a spacing therebetween, a coolant medium comprising dry ice which sublimates to create carbon dioxide coolant gas mounted in

said spacing, means for mounting the respirator adjacent of said vest, and further comprising means for discharging said carbon dioxide coolant gas from said spacing to said ducting means for passing the coolant gas to effect a coolant flow over the oxygen container, the breathing bag and the chemical cartridge.

4,294,245

PERIOPERATIVE APPLICATION OF ELECTRONIC PAIN CONTROL IN COMBINATION WITH ANESTHETIC AGENTS

Joseph G. Bussey, Austell, Ga., assignor to Stimtech, Inc., Minneapolis, Minn.

Filed Mar. 24, 1980, Ser. No. 133,211

Int. Cl.³ A61N 1/30

U.S. Cl. 128—207.21

7 Claims

1. An improved method of preparing a patient for surgery, and for alleviating sensation of a patient during surgery, wherein the improvement comprises applying transcutaneous electrical nerve stimulation at least one point proximal to the site of incision, administering an anesthetic agent, and proceeding with surgery with the patient under the combined synergistic influence of said simulator and said agent.

4,294,246

FLOW CONTROL DEVICE FOR ADMINISTRATION OF INTRAVENOUS FLUIDS


Jerry L. Aslanian, Phoenix, and Jody L. Numbers, Scottsdale, both of Ariz., assignors to Master Medical Corporation, Phoenix, Ariz.

Filed Jan. 22, 1979, Ser. No. 5,313

Int. Cl.³ A61M 5/00

U.S. Cl. 128—214 E

4 Claims



1. A metering device for accurately setting flow rates in an IV system including a source of IV or parenteral fluid, said valve comprising:

- (a) a housing;
- (b) a fluid passageway within said housing;
- (c) a valve seat in said passageway having a valving surface;
- (d) a cylindrical metering member axially moveable relative to said valve seat, said metering member including a cam follower and said member further defining a flow passage in the wall surface having a cross-sectional area which varies axially along at least a section of said flow passage;
- (e) actuating cam means having a generally spiral cam surface cooperable with said cam follower;
- (f) biasing means urging said metering member into engagement with said cam surface in a direction to reduce flow; and
- (g) dial means moveable relative to said housing for imparting rotational movement to said actuating cam means whereby said cam surface axially displaces said member relative to said valving seat surface to progressively regulate flow from a closed to a purge position with flow metering occurring along said portion of said flow passage which varies in cross-sectional area.

4,294,247


FRANGIBLE, RESEALABLE CLOSURE FOR A FLEXIBLE TUBE

Garry L. Carter, Palatine; Daniel B. Granzow, Arlington Heights, and Edward L. Bayham, Mundelein, all of Ill., assignors to Baxter Travenol Laboratories, Inc., Deerfield, Ill. Continuation of Ser. No. 818,357, Jul. 25, 1977, abandoned. This application Feb. 26, 1979, Ser. No. 15,395

Int. Cl.³ A61M 5/00

U.S. Cl. 128—214 D

11 Claims



1. In a flexible tube, valve means which comprises: a tubular portion having a closed end; an elongated, generally rigid member carried on the exterior of said closed end and positioned within said flexible tube; and frangible means to permit the opening of said closed end by manual manipulation of said elongated member from outside of the flexible tube, to separate said elongated member from the tubular portion and to open said closed end, said elongated rigid member being adapted to fit in sealing relation within said tubular portion after said opening to permit resealing of the valve.

4,294,248

DEVICE FOR AUTOMATICALLY CONTROLLING THE INFUSION LIQUID FLOW IN AN INFUSION APPARATUS

Nuno R. M. de Figueiredo, Högstigen 5, 182 74 Stocksund, Sweden


Filed Oct. 16, 1979, Ser. No. 85,281

Claims priority, application Sweden, Oct. 19, 1978, 7810917

Int. Cl.³ A61M 5/06

U.S. Cl. 128—214 E

7 Claims



1. A device for automatically controlling infusion liquid flow in an infusion apparatus comprising first means for successively adjusting the actual value of said flow towards a desired value of said flow, second means for successively adjusting said desired value of the flow, and third means for successively calculating the value of the instantaneously remaining portion of a preselected total infusion liquid volume intended for infusion during a given total time, said second means being responsive to said third means.

4,294,249


SWAGE-MOLDED INJECTION SITE

Neil J. Sheehan, Berkeley, and Melvin H. Norman, Oakland, both of Calif., assignors to Cutter Laboratories, Inc., Berkeley, Calif.

Filed Oct. 18, 1979, Ser. No. 85,841
Int. Cl.³ A61M 5/00

U.S. Cl. 128—214 G

7 Claims



1. An injection site, comprising in combination:
 - a self-sealing, puncturable member of resilient material, said puncturable member being a generally cylindrical body having a top surface on which is centrally located a flat, smooth surfaced raised projection, and
 - a generally tubular, plastic housing wherein said puncturable member is compressibly confined, said housing having a top receptor portion whose inside diameter is greater than the inside diameter of the remaining portion of the housing so as to provide a ledge on which said puncturable member rests, the top receptor portion having a swage-molded top edge which extends over at least a portion of the top surface of said puncturable member, said swagemolded top edge being below the flat surface of said raised projection.

4,294,250


LUER LOCK CONNECTION DEVICE

T. Michael Dennehey, Arlington Heights, Ill., assignor to Baxter Travenol Laboratories, Inc., Deerfield, Ill.

Filed Dec. 7, 1979, Ser. No. 101,246
Int. Cl.³ A61M 3/00

U.S. Cl. 128—247

12 Claims



1. A luer lock connection device which comprises: a cooperating male luer lock connector and a female luer lock connector;
 - said male luer lock connector having a central tubular portion defining an axial bore with at least a portion of said central tubular portion being enclosed by an outer sheath having a generally circular cross-sectional configuration; said outer sheath having internal connecting means for cooperating with external connecting means of said female luer lock connector;
 - said female luer lock connector comprising a main tubular member for receiving said central tubular portion and having said external connecting means for cooperating with the internal connecting means of said male luer connector's outer sheath; and
 - said main tubular member of said female luer connector

having visual indicating means which is positioned to indicate that the male and female connectors are assembled properly for use when said outer sheath and said visual indicating means are in a predetermined relationship.

4,294,251

METHOD OF SUCTION LAVAGE

A. Seth Greenwald, 2235 Tudor Dr.; Jack M. Geiger, 2713 Hampshire Rd., both of Cleveland Heights, Ohio 44106; Nathaniel C. Narten, 3732 Northampton Rd., Cleveland Heights, Ohio 44121; Derek S. Porritt, 3263 Granger Rd., Medina, Ohio 44256; Steven P. Combs, 404 DuPont Way, Dayton, Ohio 45433, and John J. Brems, 1591 Grace Ave., Lakewood, Ohio 44107


Continuation of Ser. No. 952,195, Oct. 17, 1978, abandoned.

This application Jul. 21, 1980, Ser. No. 170,596

Int. Cl.³ A61M 1/00

U.S. Cl. 128—276

3 Claims



1. A suction lavage method to improve the bond strength of a prosthetic fixation, such as an implant, with reamed cancellous bone, comprising:
 - A. applying a pulsatile water jet operating in an air environment to reamed cancellous bone;
 - B. applying suction contiguously with the water jet at a greater suction capacity than the water jet flow;
 - C. pulsing said water jet at about 2100 pulses per minute;
 - D. pressure cementing an implant into the cancellous bone which results in a 20 percent greater penetration of cement into the trabecular interstices of the cancellous bone and greatly improves the bond strength between the implant and the bone.

4,294,252

OSTOMY DEVICE

Eystein Einset, 1916 Sunset Dr., St. Joseph, Mich. 49085

Filed Nov. 5, 1979, Ser. No. 91,338

Int. Cl.³ A61F 5/44


U.S. Cl. 128—283

11 Claims

1. In an ostomy device having a drainage sleeve provided with a flexible connecting neck defining an inlet opening, improved retaining means for use in retaining the sleeve neck to a user's body in alignment with a stoma therein for collecting material draining outwardly through the stoma, said retaining means comprising:
 - a one-piece gasket having a first inner clamp half provided with a first drain opening, a second outer clamp half provided with a second drain opening, a hinge comprising portions of said clamp halves connecting the clamp halves for selective spaced disposition and facially overlying clamping disposition with said drain openings aligned, cooperating means on said clamp halves for sealingly securing said sleeve neck between said clamp halves in said clamping disposition with said neck passed through said second drain opening of the outer clamp half and outturned between said clamp halves with said inlet opening aligned with said first drain opening of the inner clamp

half, and at least two different types of releasable interlock means for releasably interlocking said clamp halves in said clamping disposition; and

and the liquid permeable cover at the area of the cushion underlying the withdrawal cord.



means for preventing disengagement of said interlock means when the device is being retained to the user's body.

4,294,253

TAMPON WITH A NON-WOVEN WRAP

Axel Friese, Wuppertal, Fed. Rep. of Germany, assignor to Carl Hahn, G.m.b.H., Dusseldorf, Fed. Rep. of Germany


Filed Dec. 3, 1979, Ser. No. 99,771

Claims priority, application Fed. Rep. of Germany, Dec. 20, 1978, 2855179

Int. Cl.³ A61F 13/20

U.S. Cl. 128—285

1 Claim



1. An absorbent body suitable for compressing into a catamerial tampon comprising:
 - a flat cushion of absorbent material enveloped by a liquid permeable cover and having a top face, said cushion extending in a longitudinal direction and consisting of three longitudinally successive sections; namely, a front section defined by a front edge and a front fold line, a central section defined by said front fold line and a rear fold line, and a rear section defined by said rear fold line and a rear edge;
 - said front and rear sections being folded onto the top face of said central section about said front and rear fold lines, respectively, with said front and rear edges facing one another;
 - a withdrawal cord fastened longitudinally around said folded cushion and dividing said cushion therewith into two lateral sections;
 - the two lateral sections being folded toward each other about said withdrawal cord with the folded front and rear sections facing each other;
 - said absorbent body further provided with a reinforcing strip of material sandwiched between the absorbent material

4,294,254

SURGICAL APPARATUS


Dale L. Chamness, 621 Pleasant Ridge Rd., Bloomington, Ind. 47401

Continuation-in-part of Ser. No. 858,712, Dec. 8, 1977, Pat. No. 4,256,113. This application Oct. 19, 1979, Ser. No. 86,588

Int. Cl.³ A61B 17/00

U.S. Cl. 128—303.14

14 Claims



1. An apparatus including a sheath having proximal and distal ends, a member disposed within the sheath and movable longitudinally therein, the movable member having proximal and distal ends, and a surgical instrument operable by movement of the distal end of the movable member with respect to the distal end of the sheath, an operating assembly comprising first means for moving the movable member longitudinally with respect to the sheath, second means for rotating the movable member within the sheath, and a body for supporting the first and second means, the body including a portion for fixed attachment of the proximal end of the sheath thereto, said portion of the body further defining an aperture through which the proximal end of the movable member movably extends, the proximal end of the movable member being coupled to the first and second means for movement thereby, the first means including a slide supported in the body for movement longitudinally thereof, the body including means defining an interior and the slide including means shaped to slide in the interior and a driven portion, the first means further including a first thumbwheel rotatably mounted in the body, the first thumbwheel providing a driving portion to engage the driven portion, the first means further including means for providing a braking force on the first thumbwheel, manipulation of the first thumbwheel overcoming the braking force on the first thumbwheel to cause movement of the slide.

4,294,255

INTRALUMINAL ANASTOMOSIS

Andre Geroc, 1823 Lee Rd., Cleveland Heights, Ohio 44118

Continuation of Ser. No. 890,914, Apr. 17, 1978, abandoned. This application Feb. 19, 1980, Ser. No. 106,926


Int. Cl.³ A61B 17/04

U.S. Cl. 128—334 C

7 Claims

1. Anastomosis devices for intraluminal, end-to-end connection of the severed ends of an intestine or other tubular organ, the devices including a pair of mating, ring-shaped, clamping members, each of the members comprising:
 - (a) a circumferential, laterally extending, sharpened rim, the rim being located adjacent a radially innermost portion of the member;
 - (b) a second, laterally extending rim, the second rim extending outwardly of the member on the same side as the sharpened rim but to a lesser extent than the sharpened rim, the second rim being located adjacent a radially outermost portion of the member;

(c) a groove located intermediate the sharpened rim and the second rim; and



(d) means for connecting the members together, the connecting means being in the region of the groove.

4,294,256

RATE CONTROLLED DIGITAL PACEMAKER


Wilson Greatbatch, 5220 Donnington Rd., Clarence, N.Y. 14031

Filed Jul. 16, 1979, Ser. No. 57,745

Int. Cl.³ A61N 1/36

U.S. Cl. 128-419 PT

11 Claims



1. In combination with a cardiac pacer comprising electrode means adapted to be operatively connected to a patient's heart for applying stimulating pulses thereto, a source providing an output train of electrical pulses having a constant frequency and including oscillator means providing a train of output pulses at a relatively high frequency and means for converting said high frequency pulses to pulses having a lower frequency suitable for heart stimulation comprising a first component including a plurality of frequency divider stages having an output and having an input connected to said oscillator output and a second component including a plurality of frequency divider stages having an input and an output, and coupling means connected to the output of said second component of said frequency converting means for coupling said lower frequency pulses to said electrode means;

(a) pulse rate control means connected in series between said output of said first component of said frequency converting means and said input of said second component of said frequency converting means, said pulse rate control means comprising means for providing a path for said train of pulses from the output of said first component to the input of said second component of said frequency converting means, blanking pulse generating means having an input and an output and connected in synchronized relation to said output of said first frequency converting means for

generating blanking pulses of a number determined by signal conditions at said input of said generating means during each time interval of said train of pulses and in synchronism with said train of pulses, and means for connecting the output of said blanking pulse generating means in controlling relation to said path providing means for preventing transmission of those pulses in the train which coincide in time with said number of blanking pulses to change the rate of stimulating pulses coupled to said electrode means for application to the heart by an amount determined by the number of blanking pulses;

(b) command signal responsive control means connected to said pulse rate control means for controlling the number of blanking pulses to be applied to said train of pulses in said path, said command signal responsive control means including means connected to said input of said blanking pulse generating means and responsive only to a first command signal for causing said blanking pulse generating means to increase the number of blanking pulses generated during each time interval of said train of pulses by an amount determined by said first command signal to decrease the rate of stimulating pulses applied to the heart and means connected to said input of said blanking pulse generating means and responsive only to a second command signal for causing said blanking pulse generating means to decrease the number of blanking pulses generated during each time interval of said train of pulses by an amount determined by said second command signal to increase the rate of stimulating pulses applied to the heart; and

(c) auxiliary control means adapted to receive at least two instruction inputs at a location physically separate from said cardiac pacer and operatively coupled to said command signal responsive means for generating said first and second command signals to change the rate of stimulating pulses applied by said electrode means to the heart, said auxiliary control means including means responsive to one of said instruction inputs for generating said first command signal having a given characteristic and means responsive to the other of said instruction inputs for generating said second command signal having a different characteristic.

4,294,257

HALTER TOP FOR SPORTS SUIT

Linda Rennhofer, c/o Ronald M. Lieberman, Suite 201, 2 Gloucester St., Toronto, Ontario, Canada (M4Y 1L5)


Filed May 15, 1979, Ser. No. 39,298

Claims priority, application Canada, Apr. 24, 1979, 326248

Int. Cl.³ A41C 3/00; A41D 5/00; A47K 13/00

U.S. Cl. 128-495

12 Claims



1. A halter top formed of substantially non-stretchable material for a sports outfit for females comprising the combination of:

(a) a body encircling portion constituted by a discontinuous panel having a pair of free lateral edges and cooperating means at said free lateral edges to hold said free lateral edges together, said body encircling portion being provided with

(i) a pair of discrete, separated breast-receiving and supporting cups, each said cup including a vertical seam therein bisecting said cup, the preselected variable but permanent location of said vertical seam thereby providing preselected different cup sizes, the top edge of said breast-receiving and supporting cup being so curved as to follow the natural incline of said breasts, the lower edge of said breast-receiving and supporting cups being so curved as to fit below the breasts, and

(ii) means constituted mainly by said cooperating means for adjustably interconnecting said free lateral edges with a predetermined spacing therebetween while thus simultaneously separating one said breast cup from its adjacent said breast cup;

(b) means for adjustably securing said halter top to the upper chest portion of a female body;

whereby, in use, the breasts are held firmly yet comfortably against the body, with the breast being urged towards each other and inwardly towards the body.

4,294,258

MEASURING HEAD ENABLING THE PRODUCTION OF PHYSIOLOGICAL MEASUREMENT SIGNALS DESIGNED TO BE POSITIONED ON OR IN CORPOREAL PARTS

Claude Bernard, Le Plessis-Robinson, France, assignor to Agence Nationale de Valorisation de la Recherche (Anvar), Neuilly-sur-Seine, France


Filed Mar. 19, 1979, Ser. No. 21,779

Claims priority, application France, Mar. 23, 1978, 78 08428

Int. Cl.³ A61B 5/00, 5/04

U.S. Cl. 128-635

32 Claims



1. A measuring head adapted to be positioned on or in corporeal parts of a living body, said head comprising:

an insulating body, said insulating body having a first electrode means which is sensitive to electrical activity of said corporeal parts, an electrical lead operatively connected to and extending from said first electrode means,

said insulating body also having a second electrode means which is sensitive to an ionic or physical activity of said corporeal parts, an electrical lead operatively connected to and extending from said second electrode means,

an elongated sheath means being connected to and extending from said insulating body, said electrical leads extending from the insulating body along said sheath means, said insulating body having a claw means movable between a retracted position within said insulating body and an extended position out of said insulating body whereat it is positioned to enter the corporeal parts, to thereby secure the measuring head to the corporeal parts,

control means for moving the claw means between said retracted and extended positions such that in the said extended position the claw means has entered the corporeal parts while said first and second electrode means simultaneously engage the corporeal parts.

4,294,259

METHOD AND APPARATUS FOR CHARACTERIZING BLOOD FLOW THROUGH THE HEART


Thomas Picunko, Bronxville, N.Y.; Henry H. Kramer, Mahwah, N.J.; Naim G. Dam, Bayside, and Robert I. Gray, Irvington, both of N.Y., assignors to Bios Inc., Valhalla, N.Y.

Filed Nov. 25, 1977, Ser. No. 854,537

Int. Cl.³ A61B 5/02

U.S. Cl. 128-653

18 Claims



1. Apparatus for characterizing blood flow through a heart for analysis of individual cardiac cycles comprising:

a nuclear detector probe responsive to the radioactive output of a radioactive trace introduced into a patient's blood stream to provide an output indicating the amount of radioactivity at a selected location of the heart blood pool, a time base generator to provide a time base that is divided into successive time intervals,

a counter of said detector output, a memory to store counts from said counter over each of said time intervals,

a programmable computer responding to said counts of certain of said time intervals to compute the value of a predetermined parameter of the patient's blood flow simultaneous with each cardiac cycle being detected, a display of said value of said predetermined parameter substantially simultaneous with the computation thereof, said computer calculations and said display being substantially simultaneous with the production of said detector output signal and changing in response to changes of said detector output signal.

4,294,260

CYSTOURETHROGRAPHIC EXAMINATION CHAIN

William M. Veatch, Olympia, Wash., assignor to Olympia Radiological Associates, Olympia, Wash.

Filed Jun. 18, 1979, Ser. No. 49,503

Int. Cl.³ A61B 6/00

U.S. Cl. 128-654

2 Claims



1. A flexible insert for cystourethrographic examination, comprising:

an elongated continuous radio opaque flexible tensioning member having a plurality of interconnected rigid chain links,

a forward stop fastened to an end of the tensioning member and having a smoothly contoured continuous forward end,

a rearward stop fastened to the tensioning member, and a plurality of radio opaque bead members having axially opposite flat ends slidably mounted on the chain links between said forward and rearward stops whereby press-

tobacco an organoleptic property augmenting or enhancing quantity of a cyclic chemical compound having the structure:



wherein Z is benzo or cyclohexano.


4,294,267 POCKET PIPE

Ronald C. Glymph, 11914 Wilmington Ave., Los Angeles, Calif. 90059

Filed Jun. 27, 1977, Ser. No. 810,636
Int. Cl.³ A24F 3/02, 7/00, 5/10, 5/12

U.S. Cl. 131-330

4 Claims



1. A smoking pipe comprising:

a unitary body;

first and second chambers in said body each communicating with an exterior surface of said body with an intervening portion of said body between said first and second chambers, said first chamber adapted to receive burning materials for smoking and said second chamber adapted to receive smoke and resin from said first chamber;

at least one aperture in said intervening portion communicating with each of said first and second chambers;

a channel in said body communicating with said second chamber and the exterior of said body to form a mouthpiece for said pipe;

a third chamber in said body communicating with an exterior surface of said body and separated from said first and second chambers, said third chamber providing means for storage of smoking materials;

removable caps for each of said chambers, at least one of said caps having a time dependent therefrom for cleaning said aperture in said intervening portion;

said caps having a portion which engages the outer edge of its respective chamber to form a snug fit and a main body which extends from said snugly fitted portion into its chamber when its outer portion is in a snugly fitted relationship; and

at least one of said main bodies of said caps having a hollow portion therein for transferring smoking materials.

4,294,268

PEDICURE EASEL

John V. Kitrell, 4639 Holdrege, Lincoln, Nebr. 68503

Filed May 13, 1980, Ser. No. 149,320

Int. Cl.³ A45D 29/00

U.S. Cl. 132-73

9 Claims



1. A pedicure easel, comprising, a supporting means comprising first and second support means, said first support means having a pair of ends, one end of said first support means being adapted to be placed on a horizontal supporting surface, said second support means having a pair of ends, said second support means being secured, adjacent one end thereof, to said first support means adjacent the said other end thereof, the other end of said second support means being adapted to be removably secured to a toilet bowl, and a foot supporting plate mounted on said supporting means.

4,294,269

COMPACT TOOTHBRUSH KIT


Albert D. Kyte, P.O. Box 2523, Pensacola, Fla. 32503

Filed Jan. 31, 1977, Ser. No. 764,354

Int. Cl.³ A45D 44/18

U.S. Cl. 132-84 B

3 Claims



1. A toothbrush assembly which may be disassembled to fit into a container, comprising a shank unit fitted at a first end with bristles and shaped at a second end to detachably engage a first cap, a tubular housing threadably attachable at a first end to said first cap and fitted with an internal chamber open at one end of the housing of a size to contain a tube of dentifrice, and a second cap threadably attachable to a second end of said housing, said second cap fitted with a chamber of a size to contain a reel of dental floss, said second cap formed with a through hole to permit a length of dental floss to extend through said second cap, in which a member formed with a projecting cutting edge section, for cutting of dental floss, is externally mounted to the assembled housing, said member and cutting edge section being located within the confines of an open external recess in said assembled housing.

4,294,270

HAIR TREATING FLUID APPLICATOR


Loretta L. Cochran, 807 Corvallis Dr., Sunnyvale, Calif. 94087

Filed Sep. 19, 1977, Ser. No. 834,188

Int. Cl.³ A45D 24/22


U.S. Cl. 132-112

6 Claims



1. An applicator for depositing and distributing a fluid onto the hair of a human being comprising:
 - (a) a fluid supply reservoir having an open end;
 - (b) a cap portion attached to said open end of said supply reservoir, said cap portion having a passage formed there-through for communication with the interior of said supply reservoir;
 - (c) a fountain comb including a backbone secured to said cap portion and having a manifold passage in communication with the passage formed through said cap portion;
 - (d) A plurality of comb teeth extending in parallel relation to one another from the backbone of said comb and each having a passage formed lengthwise therethrough for communication with the manifold passage in said backbone;
 - (e) a bumper sponge on said backbone of said comb for absorbing and mopping excess fluid from the scalp and hair under treatment, said bumper sponge being disposed on one side of said backbone of said comb displaced in the vicinity of 90° degrees from the side of said backbone of said comb from which said comb teeth project and having an outer surface opposite the surface thereof on said backbone of said comb; and
 - (f) a brush on said outer surface of said sponge for spreading the fluid relative to strands and curls of hair under treatment, said brush having bristles extending laterally outward from the outer surface of said sponge for combined action with said sponge in spreading and distributing the fluid over hair under treatment.

means from forming channels in said deposited matter, said means to prevent including spray nozzles for spraying



the reagent circumferentially and longitudinally along the inside surface of said tube at said opening.

4,294,272

APPARATUS FOR WASHING, RINSING AND SPIN DRYING PAINT ROLLERS


William C. Klaiber, 601 York Rd., Fayetteville, N.C. 28303

Filed Oct. 11, 1979, Ser. No. 83,613

Int. Cl.³ B08B 3/02

U.S. Cl. 134-138

12 Claims



1. A paint roller cleaner including a receptacle for receiving a paint roller therein, elongated horizontal roller support means journaled within said receptacle for rotation about an axis extending longitudinally of said roller support means, said roller support means being adapted to have a paint roller sleeve lengthwise telescoped thereover for support therefrom and rotation therewith, an elongated horizontal water discharge manifold supported within said housing in horizontally laterally spaced relation relative to said roller support means, said manifold including water outlet jet discharge means spaced therealong and opening outwardly along one side of said manifold toward said roller support means, means operative to selectively supply water under pressure to the interior of said manifold, drive means, independent of said manifold water jet discharge means, operative to drive said roller support means, said receptacle including water outlet means operative to drain collected water in said receptacle from within the latter on one side of said roller support means down to a predetermined level spaced slightly below said axis of rotation of said roller support means, said drive means being operative to drive said roller support means in a direction of rotation of said roller

4,294,271

APPARATUS FOR REMOVING DEPOSITED MATTER FROM A DIFFUSION TUBE

Josef Intrater, Englewood Cliffs, N.J.; Gene Bertholdo, New York, N.Y., and Janet Intrater, Englewood Cliffs, N.J., assignors to Dexon, Inc., Minneapolis, Minn.

Filed Nov. 30, 1979, Ser. No. 98,756

Int. Cl.³ B08B 3/02, 9/02

U.S. Cl. 134-113

28 Claims

18. A spray head device for use in cleaning a diffusion tube of matter deposited therewithin comprising:

- a body portion;
- sealing means for sealably contacting an opening at one end of said tube;
- spraying means for spraying a reagent against the inside surface of said tube;
- means for providing a flow of said reagent to said spraying means; and
- means to prevent said reagent sprayed by said spraying

with the lower periphery of said roller support means being advanced toward the other side of said roller support means.


4,294,273

FLUID PROPORTIONING DEVICE

Gary J. Isberg, P.O. Box 491, Trail, British Columbia, Canada
Filed Jun. 18, 1979, Ser. No. 50,024
Int. Cl.³ B65D 87/00

U.S. Cl. 137-1

2 Claims



1. A method of proportioning oil and gasoline in a fuel tank comprising the steps of inserting into the partially filled fuel tank a tube having a volumetric capacity related to the volumetric capacity of the fuel tank by a ratio directly proportional to a prescribed ratio for mixing the gasoline and oil, admitting into and retaining within the tube a level of fuel equal to the level remaining in the fuel tank, removing the tube from the tank, adding oil to the tube to fill said tube to a predetermined level, and pouring the contents of the tube into the fuel tank before filling said tank with gasoline.

4,294,274

HYDROGEN INJECTION INTO GAS PIPELINES AND OTHER PRESSURIZED CONTAINERS

Rodney L. LeRoy, Pointe Claire, Canada, assignor to Noranda Mines Limited and The Electrolyser Corporation Ltd., both of Toronto, Canada


Filed Jul. 17, 1979, Ser. No. 58,306

Claims priority, application United Kingdom, Jul. 17, 1978, 30090/78

Int. Cl.³ F17D 1/02

U.S. Cl. 137-7

8 Claims



1. A method of introducing a proportion of hydrogen into a gas pipeline or other pressurized gas container, said method comprising feeding hydrogen into the container from a pressure source lower than the pressure of the gas in the container through a barrier freely permeable to hydrogen but impermeable to the gas in the container until the hydrogen partial pressure in the container becomes equal to the hydrogen pressure which is applied to the barrier.

4,294,275

FLANGED JOINT SEALING NUT


Mirrel L. Totman, McPherson, Kans., assignor to Totman Seal Nut, Inc., McPherson, Kans.

Filed Apr. 13, 1979, Ser. No. 29,679

Int. Cl.³ F16L 55/18; F17D 3/00

U.S. Cl. 137-15

4 Claims



4. An improved method of sealing a leaking flanged pipe joint comprising the steps of:
sealing the outer circumferential gap between the two adjacent flanges of the joint;
replacing the original bolts and nuts, one at a time, with a bolt and two closed-end nuts, the nuts having a means for sealing between the nuts and the flanges; and
threading the sealing nuts onto the bolt until both nuts contact the flanges, then tightening each nut until fully tightened, thus lastingly and positively sealing each nut to its adjacent flange;
in which the improvement comprises:
using full size sealing nuts and bolts equal in diameter to the original nuts and bolts, and locating the sealing area on the face of the flange near perimeter of the nut and away from rim of bolt hole.

4,294,276

WATER SENSITIVE PROBE VALVE FOR USE WITH A GAS LEAK DETECTOR


Loren C. Harrison, 8607 Danby Ave., Whittier, Calif. 90606

Filed Dec. 26, 1979, Ser. No. 107,151

Int. Cl.³ F16K 13/04

U.S. Cl. 137-67

13 Claims



1. An improved water sensitive probe valve comprising:
(a) a body defining an interior gas passage for the passage of gas through the probe valve;
(b) a coupling of the body and detachable from the balance thereof;
(c) a valve mounted on the coupling for closing the gas passage in a closed position of the valve, the valve being capable of translation along a path with respect to the coupling, the valve having a first finger extending radially of its path of translation;
(d) an anchor mounted on the coupling and defining a second finger extending radially of the path of translation of the valve;
(e) the first and second fingers defining mounting means for a water soluble link that keeps the valve in an open position;
(f) biasing means for urging the valve into the closed position and applying tension to the water soluble link;
(g) a gas probe mounted on the body; and
(h) means for coupling the interior gas passage to a gas detector downstream of the valve.

4,294,277

FLOW CONTROL APPARATUS


Philip C. Szeliga, Utica, N.Y., assignor to Foam Controls, Inc., New Hartford, N.Y.

Filed Jul. 9, 1980, Ser. No. 167,127

Int. Cl.³ G05D 7/06, 11/13

U.S. Cl. 137-101.19

11 Claims



1. A fluid control apparatus of the type wherein a plurality of fluids are delivered by means of a like number of lines to a mixing device, said apparatus including
a sensing means positioned in each line for developing a rate signal that is indicative of the flow passing through said line,
a comparator means operatively connected to each of the sensing means for comparing the rate signal of said sensing means with a selected rate and producing an upper control signal when the sensed rate is above the selected rate and a lower control signal when the sensed rate is below the selected rate,
a control valve means contained in each of said lines that is responsive to said comparator means for increasing the flow rate in the line when a lower control signal is generated by said comparator means and for decreasing the flow rate when the upper control signal is generated by said comparator means, and
circuit means for monitoring the rate signals developed by each sensing means and for inhibiting the comparator means in the event all the rate signals fall simultaneously below a predetermined rate.

4,294,278

PRESSURE MODULATING VALVE

William W. Blake, Kewanee, Ill., assignor to Caterpillar Tractor Co., Peoria, Ill.

PCT No. PCT/US79/01129, § 371 Date Dec. 14, 1979, § 102(e)

Date Dec. 14, 1979, PCT Pub. No. WO81/01733, PCT Pub.


Date Jun. 25, 1981

PCT Filed Dec. 14, 1979, Ser. No. 110,712

Int. Cl.³ F16K 11/10

U.S. Cl. 137-115

15 Claims



1. In a modulating valve (28) having an axial passage (76), with a first end portion (96) and a second end portion (92), the improvement comprising:
a relief valve spool (128) mounted in said axial passage (76) adjacent the first end portion (96);
a load piston (114) mounted in said axial passage (76) adjacent the second end portion (92);
resilient means (144) for interconnecting said spool (128) and said load piston (114);
a pressure operated check valve means (106) for selectively

relieving the pressure in said second end portion (92), which check valve means (106) is slidably mounted about said load piston (114);
means (124) for communicating the first end piston (96) with the second end portion (92); and
means (118) for communicating the pressure operated check valve means (106) with the first end portion (92).

4,294,279

FUEL TANKS

Harold W. G. Wyeth, Fleet, England, assignor to The Secretary of State for Defence in Her Britannic Majesty's Government of the United Kingdom of Great Britain and Northern Ireland, London, England


Filed May 31, 1979, Ser. No. 44,160

Claims priority, application United Kingdom, May 31, 1978, 24761/78

Int. Cl.³ B64D 37/08

U.S. Cl. 137-264

27 Claims



1. A tank for liquid fuel and containing
a plurality of cells for containing fuel and each extending substantially from the floor of the tank to the ceiling thereof,
collection means, in the bottom of said tank, for collecting fuel from said cells and supplying it to at least one common tank outlet,
plug and socket means for mounting and detaining said cells in said tank and connecting said cells to said collection means, and
non-return valves preventing fluid flow from said collection means into said cells,
each of said cells being distinct and individually detachable from said tank and comprising an envelope of impermeable flexible material surrounding a resilient fire protective reticulated structure, said envelope being open at a top end thereof and having an outlet at the bottom thereof, and there being an ullage between the top of said cells and the roof of said tank, said ullage being substantially filled with at least one fire protective reticulated structure.

4,294,280

APPARATUS FOR PRODUCING AND DISPENSING DETERGENT SOLUTIONS

Milton D. Tom, R-1, Norwich, Ohio 43767

Filed Jul. 10, 1979, Ser. No. 56,309


Int. Cl.³ B05B 7/00

U.S. Cl. 137-268

7 Claims

1. A device for selectively supplying a cleansing solution to a liquid conduit comprising:
a body having an interior chamber, inlet means for passing a liquid into said chamber, outlet means for discharging the liquid from said chamber, first aperture means in said body, and second aperture means in said body spaced from said first aperture means, housing means for a cleansing material, said housing means having an open end removably mounted on said body so as to completely surround said first and second aperture means.
said chamber having valve support means therein, a flap

valve movably carried by said valve support means so as to be movable between a first position, wherein liquid from said inlet means passes through said chamber to said outlet means, and a second position wherein liquid passes from said inlet means into a portion of said chamber and then through said first aperture means into said housing means, through said second aperture means back into said chamber and then to said outlet means, said second aperture means being disposed downstream of said valve support means and said flap valve so as to be in flow communication with said outlet means through said chamber when said flap valve is in either said first or second position.



tions so that any liquid in said housing means will drain from said housing when said housing is located vertically above said chamber and said outlet means.

said valve support means including first wall means defining a first flow path and a portion of said chamber adjacent said first aperture means for directing liquid through said first aperture means into said housing means, and said valve support means including second wall means defining a second flow path in a portion of said chamber remote from said first aperture means and first flow path for directing liquid through said chamber to said outlet means.

4,294,281

RELIEF VALVE

Theodor Gerdes, Langenfeld, Fed. Rep. of Germany, assignor to Blau KG Fabrik fur Kraftfahrzeugteile, Langenfeld, Fed. Rep. of Germany


Filed Dec. 10, 1979, Ser. No. 101,543

Claims priority, application Fed. Rep. of Germany, Dec. 21, 1978, 2855290

Int. Cl.³ F16K 15/02

U.S. Cl. 137-541

6 Claims



1. A relief valve having a wall with a valve aperture there-through, a valve disc disposed on one side of the wall and adapted to cover the valve aperture, a sealing washer disposed on the valve disc for cooperation with a valve seat surrounding

the valve aperture, a holding element moveably connected with the valve disc on the opposite side of said wall therefrom and extending into said valve aperture, a compression spring connected between the wall and a ring about the outer end of the holding element, said holding element having a hub extending into the valve aperture with radially projecting and axially extending parallel ribs circumferentially spaced about the exterior of said hub and formed integrally with said ring, said holding element at said ribs having a smaller diameter than the inside diameter of the valve aperture, and said valve disc and holding element being connected by a head, characterized by said hub having a central axial opening therethrough of circular cross-section enlarging conically toward the valve disc,

said valve disc being comprised of an inelastic material having a valve stem extending from the disc into the opening of said hub with a diameter of the stem being equal to the smallest diameter of said hub opening and having a head on the stem with a greater diameter than the smallest diameter of said head opening for extension therethrough to bear upon the outer end of the hub.

4,294,282

APPARATUS AND SYSTEM FOR CONTROLLING THE AIR-FUEL RATIO SUPPLIED TO A COMBUSTION ENGINE


Ralph P. McCabe, Troy, and Keith D. Marsh, St. Clair Shores, both of Mich., assignors to Colt Industries Operating Corp., New York, N.Y.

Filed Jul. 27, 1979, Ser. No. 61,428

Int. Cl.³ F16K 31/06, 11/14

U.S. Cl. 137-595

17 Claims



1. A valving assembly for variably restricting fluid flow through first and second spaced flow orifice means, comprising housing means, said housing means comprising a first end member, a second end member, said first end member having a first portion for operative connection to associated structure, said second end member having a first portion for operative connection to associated structure, solenoid motor means, said solenoid motor means comprising axially extending spool means, said spool means comprising a generally centrally disposed tubular portion, a solenoid field winding carried by said spool means, axially extending armature means reciprocally situated in said tubular portion, a first opening formed through said first end member for permitting the free axial movement of said armature means therethrough, a second opening formed through said second end member for permitting the free axial movement of said armature means therethrough, a first valve member operatively connected to a first axial end of said armature means as to be effective to be juxtaposed to said first flow

orifice means, a second valve member operatively connected to a second axial end of said armature means opposite to said first axial end as to be effective to be juxtaposed to said second flow orifice means, said first and second valve members moving in unison with said armature means, resilient means effective for applying to said armature means only that resilient force tending to move said first valve member toward said first flow orifice means and said second valve member away from said second flow orifice means, and sleeve-like bushing means, said bushing means being carried within said first opening of said first end member and effective for slidably receiving said armature means.

4,294,283

WEDGE SEALED DAMPER

Harry J. Scharres, 10 Gilbert Ave., Clarendon Hills, Ill. 60514

Continuation-in-part of Ser. No. 854,591, Nov. 25, 1977,

abandoned. This application Nov. 19, 1979, Ser. No. 95,295

Int. Cl.³ F16K 11/14

U.S. Cl. 137-601

6 Claims



1. A damper assembly comprising, in combination, a generally rectangular frame member including side, top and bottom members, a plurality of damper blades supported at opposite ends in the side member of the frame for limited rotative movement about axes extending longitudinally and substantially along the center line of the blades, a resilient sealing strip supported in each side frame member, the outer surfaces of said sealing strips being convex and extending beyond the interior surfaces of said side frame members, portions of each end of said blades being individually angled to be generally tangential to said convex surface of said sealing strip as said blade approaches the closed position, each of said angled blade end portions wedging against said sealing strip to create a seal when said blades move into the closed position, and said assembly further comprising two washers at each blade end to reduce friction between the ends of said blades and said resilient strips at the rotative axes of said blades.

4,294,284

FAIL-SAFE, NON-PRESSURE LOCKING GATE VALVE

David P. Herd, Kingwood, Tex., assignor to Smith International, Inc., Newport Beach, Calif.

Filed Nov. 13, 1979, Ser. No. 93,612

Int. Cl.³ F16K 31/122, 3/00

U.S. Cl. 137-613

2 Claims

1. A gate valve for operation on a submerged flowline comprising:

- a valve housing having a valve chamber, a flow way intersecting said valve chamber, and a stem bore extending from said valve chamber;
- a bonnet disposed on said valve housing having an actuator chamber and a bore extending from said actuator chamber into said valve chamber;
- a closure member disposed on said valve housing having a bore extension coaxial with said stem bore;
- a gate disposed in said valve chamber movable between an

open position and a closed position, said gate having gate segments connected to first and second attached stems, said first stem extending through said bonnet bore and into said actuator chamber and said second attached stem extending into said stem bore;

a piston connected to said first attached stem and disposed in said actuator chamber for urging said gate between said open and closed positions;


biasing means disposed in said actuator chamber engaging said piston for urging said gate from said open position to said closed position;

a detached stem disposed in said stem bore and extending into said bore extension and movable into engagement with said second attached stem;

seals around said first attached stem, around said second attached stem, and around said detached stem;

spring means disposed in said bore extension and engaging said detached stem;

port means extending from said flow way to said stem bore between said second attached stem and one end of said detached stem;



first means for supplying hydraulic fluid pressure and ambient sea pressure to one side of said piston, said first means applying a force on said piston to move said gate from said closed position to said open position where upon internal valve fluid is displaced from said stem bore through said port means as said second attached stem decreases the fluid volume in said stem bore and said second attached stem engages said detached stem to compress said spring means; and

second means for supplying ambient sea pressure to the other end of said detached stem in said bore extension and to the other side of said piston for applying an equivalent opposing force to the ambient sea pressure on said piston, said biasing means applying force to said piston to urge said gate from said open position to said closed position where upon the upstream line pressure assists said biasing means when the upstream line pressure is greater than ambient sea pressure and said detached stem engages said second attached stem when ambient sea pressure is greater than the upstream line pressure, said spring means urging said detached stem toward said second attached stem to overcome the frictional forces of said seals around said detached stem.

4,294,285

MULTI-PORT VALVE


Larry J. Joslyn, 720 Wilkinson Rd., Macedon, N.Y. 14502

Filed Dec. 14, 1978, Ser. No. 969,534

Int. Cl.³ F17D 3/01

U.S. Cl. 137—625.11

5 Claims



1. A multi-port valve comprising:

- (a) a valve housing having an end wall containing at least three fluid outlets and a fluid inlet and said fluid outlets all being spaced apart from each other and being located equi-distant from said fluid inlet;
- (b) a cylindrical, rotatably movable valve body positioned in said valve housing, said valve body containing a fluid inlet and a fluid outlet located in one end face thereof and being spaced apart from each other and being in fluid communication with each other, said fluid inlet of said valve body being located on the rotational axis of said valve body; and said fluid inlet of said valve housing also being located on rotational axis of said valve body;
- (c) a rotatably movable flow control disc positioned in said housing and located intermediate said one end face of said valve body and said end wall of said valve housing and being in fluid tight contact with said end face and end wall, respectively, and being axially aligned with said cylindrical rotatably movable valve body, said flow control disc including an inlet fluid passage and an outlet fluid passage extending therethrough, said fluid passages being spaced apart from each other the same distance said fluid inlet of said valve housing is spaced apart from each of said fluid outlets of said valve housing, said fluid inlet passage being located on the rotational axis of said valve body and of said flow control disc and being in-line with and in fluid communication with both said fluid inlet of said valve housing and said fluid inlet of said valve body at all relative rotational positions of said valve body and said flow control disc;
- (d) means connected to said rotatably movable valve body for rotating said valve body relative to said valve housing and relative to said flow control disc, said valve body and said flow control disc cooperating with each other such that said body can move relative to said disc between a first position wherein said body fluid outlet is in fluid communication with said disc outlet passage, and a second position wherein said body fluid outlet is sealed from said disc outlet passage; and
- (e) drive means cooperatively interengageable between said valve body and said flow control disc, after said valve body has moved to said second position, for rotatably moving said flow control disc together as a unit with said valve body and relative to said housing, as rotation of said valve body is continued, whereby said fluid outlet passage of said flow control disc can be placed in registry with a selected one of said housing fluid outlets, and the flow of fluid therefrom is accomplished only after said valve body is moved, relative to said disc, back to said first position to place said valve body fluid outlet, said disc outlet and said selected housing outlet into registry.

4,294,286

ELECTROMAGNETICALLY OPERABLE FLUID FLOW CONTROL VALVE MECHANISM

Takeharu Ohumi, Toyota, Japan, assignor to Aisin Seiki Kabushiki Kaisha, Kariya and Toyota Jidosha Kogyo Kabushiki Kaisha, Toyota, both of, Japan


Filed May 16, 1979, Ser. No. 39,592

Claims priority, application Japan, May 16, 1978, 53-58108

Int. Cl.³ F16K 11/07, 31/08

U.S. Cl. 137—625.48

4 Claims



1. A control valve mechanism comprising a casing having therewithin a valve means, said valve means comprising a linearly movable valve member, an electric motor means comprising a field and an armature to move linearly and operatively connected to the valve member, the electric motor means having a coil of electrically insulated wire surrounding the armature, and the field comprising a pair of arcuate permanent magnets disposed to form a circle surrounding the armature with a magnetic field across the coil, one inlet port, a first outlet port, a second outlet port, a first fluid path connecting the inlet port and the first outlet port, a second fluid path connecting the inlet port and the second outlet port, said valve means being commonly located on both of said fluid paths to control fluid communication therethrough, and spring means normally urging the valve member to a position in which the first fluid path is closed while the second fluid path is opened, the spring means comprising a pair of diametrically different coiled springs in concentric and electrically insulated relation with each other, said springs being respectively connected to both ends of said coil of wire of the armature to provide electric conductive means, wherein said valve means further comprises a tubular guide member, the valve member having a sliding fit on the tubular guide member, and the armature of the electric motor means being of tubular form and firmly surrounding the valve member to move together as a unit.

4,294,287

SHIFTING VALVE

William C. Boswell, 420 E. 2nd, Tulsa, Okla. 74120

Continuation of Ser. No. 945,398, Sep. 25, 1978, abandoned. This application Jan. 14, 1980, Ser. No. 111,902


Int. Cl.³ F15B 13/06

U.S. Cl. 137—625.69

7 Claims

2. A shifting valve for a multiple position transmission having multiple modes of operation and comprising valve body means having a pressure fluid inlet and a pressure fluid outlet provided therein, both said fluid inlet and fluid outlet being in communication with a pressure fluid source to provide for circulation of pressure fluid to and from the pressure fluid source through the valve, a bore provided in the valve body means and in communication with the fluid inlet and fluid outlet, a unitary shifting element slidably disposed within said bore and movable between definite preselected positions therein, a first multi-passageway array provided in said valve body means providing said communication between the fluid inlet and the bore for directing the pressure fluid into the bore, second and third multi-passageway arrays provided in said valve body means providing said communication between the

bore and the fluid outlet for discharging pressure fluid from the bore, a plurality of independently isolated actuator outlets provided in the valve body means, each of said actuator outlets being in operable communication with the transmission for actuation thereof upon pressurization of the actuator outlets, a plurality of multi-passageway arrays provided in the valve body means interconnecting each actuator outlet with the bore whereby the pressure fluid may be selectively directed to and withdrawn from each actuator outlet upon the selective positioning of the shifting element within the bore, said shifting element being provided with a plurality of spaced lands and recesses on the outer periphery thereof cooperating with the



bore and the multi-passageway arrays for opening and closing the arrays whereby pressure fluid is directed to the actuator outlets in a manner providing a single operational mode for the transmission at a time and for withdrawing the pressure fluid from the actuator outlets which are not pressurized, said shifting element being movable to said definite preselected positions therefor for connecting each actuator outlet with the fluid inlet for pressurization of each actuator outlet in two separate preselected positions of the shifting element, each different pressurization of each independent actuator outlet providing pressure fluid to the transmission to produce differing modes of operation therefor.

4,294,288

ACCUMULATOR WITH FLOAT ORIENTING MEANS


Rajam R. Murthy, Houston, Tex., assignor to Koomey, Inc., Houston, Tex.

Filed Feb. 25, 1980, Ser. No. 124,136

Int. Cl.³ F16L 55/04

U.S. Cl. 138—30

5 Claims



1. In a guided-float accumulator comprising a vessel in the

shape of a sphere or cylinder adapted to contain high fluid pressures, a mouth at the bottom of the vessel, fluid outlet means associated with the mouth for connection of the vessel and its content to a hydraulic system such as used in an oil well blowout preventer, a normally open shut-off valve associated with the mouth in series with the fluid outlet means, and a vented float movable in the vessel along transversely centered normally vertically extending guide means according to the level of the liquid fill within the vessel to thereby close off the shut-off valve and prevent the escape of pressurized gas from the ullage space of the vessel into the hydraulic system proper as the liquid fill within the vessel approaches exhaustion, the improvement which comprises provision of a vent outlet for the float and a ballast weight for the float with the vent outlet and ballast weight on opposite sides of the center of said normally vertically extending guide means, said float being mounted for free turning around said center whereby whatever the degree of liquid fill of the vessel, sidewise tilting of the vessel so as to move the normally vertically extending guide means toward a horizontal position will be accompanied by rotation of the vent outlet to the then-high side of said center of said normally vertically extending guide means to keep the vent outlet above the liquid fill and maintain the float directly vented to the ullage space of the vessel.

4,294,289

FLOW CONTROL DEVICE


Armin O. Fischer, Louisville, Ky., assignor to American Standard Inc., New York, N.Y.

Filed Jan. 24, 1980, Ser. No. 114,818

Int. Cl.³ F15D 1/02

U.S. Cl. 138—44

2 Claims



1. A flow restrictor comprising a disc having a recessed downstream side and a boss formed on the upstream side thereof to form a rim, the upstream surface of said boss being flat, said boss having at least one slot formed therein, the upstream opening of said slot having a respective width that is substantially smaller than the length of said opening, said width being very narrow to prevent foreign matter from entering said slot, said slot having sides within the device, said slot having an aperture formed therein to permit fluid communication between said upstream and downstream disc sides, said aperture at said downstream side being at no point narrower than the narrowest portion of said upstream slot width, and the upstream side of the slot having leading edges that are substantially longer than those of said aperture due to a portion of the slot being obstructed by said rim.

4,294,290

PROCESS AND LOOM FOR THE PRODUCTION OF PILE FABRICS

Erhard Freisler, Bubikon, Switzerland, assignor to Ruti Machinery Works Ltd., Ruti, Switzerland

Filed Jun. 20, 1979, Ser. No. 50,167

Claims priority, application Switzerland, Jun. 30, 1978, 7153/78


Int. Cl.³ D03D 39/22, 49/06

U.S. Cl. 139—26

21 Claims

1. A process of producing pile fabric with pile or terry loops

of constant height, on a loom having a pile-warp beam, a ground-warp beam and a batten the stroke of which in operation is shortened periodically from the value corresponding to a full beating-up of the batten by a value for partial beatings



referred to as the pre-beating distance, characterized by the fact that during the weaving process the pre-beating distance is decreased or increased upon variations in the tension of the pile warp.

4,294,291

SHUTTLE RETAINING APPARATUS


Philip A. Nims, Charlotte, and Roger K. Bollinger, Gastonia, both of N.C., assignors to Crompton & Knowles Corporation, New York, N.Y.

Filed May 15, 1980, Ser. No. 150,273

Int. Cl.³ D03D 47/24

U.S. Cl. 139-438

9 Claims



1. Shuttle control apparatus for looms having a shuttle box rotatable 180° from a first position for allowing the shuttle to be picked out of the shuttle box, means for checking the shuttle when it enters the shuttle box, means for positioning the shuttle within the shuttle box to a predetermined picking position when the shuttle box is in its first position and means for picking the shuttle when the shuttle box is in its second position, said shuttle control apparatus comprising:

- means for guiding the shuttle as it moves from the first position to the second position to maintain the shuttle in said predetermined picking position within the shuttle box;
- a shuttle brake normally disposed in a non-braking mode and operable to a braking mode for engaging the shuttle and maintaining the shuttle in the predetermined picking position; and
- brake actuating means for operating the shuttle brake to the braking mode when the shuttle box is in its second position, said actuating means being effective to cause the shuttle brake to apply a braking force to the shuttle which is sufficient to maintain the shuttle in said predetermined

picking position and insufficient to prevent the shuttle from being picked.

4,294,292

TUMBLE DUMPER


William J. Eberle, Reading, Pa., assignor to General Battery Corporation, Reading, Pa.

Filed Nov. 1, 1979, Ser. No. 90,477

Int. Cl.³ B65B 21/08

U.S. Cl. 141-1

22 Claims



9. The method of actively removing electrolyte from lead-acid storage batteries having filling holes defined in a top surface thereof comprising:

- carrying the batteries into an automatic apparatus;
- inverting said batteries over a receiver tank;
- jostling the batteries so that all of the electrolyte therein is actively removed; and
- righting the batteries so that they may be carried out of the machine for further processing.

4,294,293

METHOD OF MIXING COSMETIC MULTI-COMPONENT PREPARATIONS AND SET OF APPARATUS FOR THE PRACTICE OF THE METHOD
Heribert Lorenz, Gross-Bieberau, and Jürgen Tennigkeit, Seeheim, both of Fed. Rep. of Germany, assignors to Goldwell GmbH, Darmstadt-Eberstadt, Fed. Rep. of Germany

Filed Jun. 22, 1979, Ser. No. 51,035

Claims priority, application Fed. Rep. of Germany, Jun. 23, 1978, 2827610

Int. Cl.³ B01F 15/02; B65B 3/10

U.S. Cl. 141-100


21 Claims

1. A set of apparatus comprising:

- a first supply container for a liquid first preparation component and having a dispensing orifice, a piston pump adapted to be inserted into said dispensing orifice and having a piston, and a plunger connected to said piston, a spring biasing said piston to an outer position of maximum stroke volume in which said plunger protrudes from said first supply container by the length of the piston stroke and adapted to be displaced by pressure on said plunger against the action of said spring towards the interior of said first container by the length of the piston stroke, said piston pump also having a suction connection adapted to be immersed in the preparation component when contained in the supply container and also having a discharge connection, a mixing container for receiving and mixing of a multi-component preparation and having a self-closing bottom valve and a pedestal, said discharge connection adapted to be sealingly connected to said self-closing bottom valve, a guiding housing open at the top, annularly surrounding the plunger and adapted to be disposed on said first supply container, the free cross-section of said guide housing conforming to the outer cross-sectional dimensions of said pedestal and guiding the pedestal upon

the depression of the plunger, such that the discharge connection of the pump is adapted to be aligned with the bottom valve of the mixing container, a pressure container, a second supply container being disposed in said pressure container and being volume-variable and adapted to be filled with an additional paste or liquid preparation component, an external dispensing valve in communica-

tion with said second supply container, the capacity of said second supply container being smaller than the capacity of the pressure container, the space remaining between the second supply container and the inside walls of the pressure container being filled with a propellant under pressure, said dispensing valve being adapted to be sealingly connected to the bottom valve of said mixing container.




4,294,294
CONTROL SYSTEM FOR FILLING MACHINE
Richard N. Bennett, Arbutus, Md., assignor to National Instrument Company, Inc., Baltimore, Md.

Filed Feb. 7, 1980, Ser. No. 119,317

Int. Cl.³ B65B 43/56

U.S. Cl. 141-179

9 Claims



1. A control system for a filling machine having filling means operatively connected with nozzle means for simultaneously filling a number of containers corresponding to the number of nozzle means at the filling station, support means for the nozzle means operable to lower and raise the nozzle means into and out of the containers in timed relationship to the filling operation during a given cycle, and control means for controlling the operation of the filling machine including means for actuating the filling means to cause discharge of the product to be filled while the nozzle means are in the containers, means for selectively lowering and raising the nozzle support means in

4,294,295
APPARATUS FOR CUTTING AND SPLITTING FIREWOOD


C. Howard Olin, Tigard, Oreg., assignor to Bloomfield Farms, Inc., Los Altos, Calif.

Filed Sep. 25, 1978, Ser. No. 945,464

Int. Cl.³ B27L 7/00

U.S. Cl. 144-3 K

14 Claims



1. Firewood splitting apparatus, comprising:

- a frame,
- block splitter means on the frame,
- ram means on the frame arranged for axial movement toward and away from the splitter means for moving a block toward the splitter means, and
- block centering means on the frame comprising upper and lower centering pans arranged to receive a block between them and movable vertically to position the block between the splitter means and the ram means.

4,294,296
CARPENTER PLANER
Hirotugu Onda, Seki, Japan, assignor to Onda Ironworks Company, Limited, Gifu, Japan

Filed Sep. 21, 1979, Ser. No. 78,312


Int. Cl.³ B27C 1/12

U.S. Cl. 144-120

6 Claims

1. A carpenter planer comprising a planer base, a stock feeding table provided on the planer base, a stock feeding unit connected to and situated above the stock feeding table and spaced therefrom, said stock feeding unit having an endless belt and a reversible motor for rotating the endless belt back and forth, a planer blade situated in the stock feeding table and slightly projecting therefrom, detecting means for detecting passage of stock moved on the stock feeding table by the endless belt of the stock feeding unit, and timing means actu-

ated by said detecting means, said timing means controlling the motor so that after the stock is completely passed over the



planer blade, the motor is stopped and then the motor is reversely actuated to return the stock to a first position.

4,294,297

ROUTER GUIDE APPARATUS AND METHOD


Vincent C. Kieffer, 411 Highland Dr., Gretna, Nebr. 68028

Filed Apr. 11, 1979, Ser. No. 28,985

Int. Cl.³ B27C 5/10

U.S. Cl. 144—134 D

18 Claims



1. An apparatus for guiding a router relative to a guide surface on a workpiece, said router having a rotatable bit protruding from the underside thereof, comprising, a pair of guide pins, means for securing the guide pins to the underside of said router at positions spaced apart from one another and radially spaced from the bit, said guide pins protruding from the underside of said router for continuous engagement with said guide surface as the router is advanced along the workpiece, said means for securing the guide pins comprising a subbase plate having a tool opening and a plurality of guide pin openings adapted to receive said guide pins and means for securing said subbase plate to the underside of the router with said tool opening positioned for protrusion of said bit through the center thereof, said guide pin openings including a plurality of pairs of guide pin holes aligned along a line disposed in nonintersecting relation to the center of said tool opening, the holes of each pair being equidistant from the point of intersection of said line and another line perpendicular thereto and passing through the center of said tool opening.

4,294,298

IMPACT CUTTING TOOL

Otto M. Otte, Jr., 719 Avenue "A", Apt. 705 ID, Springfield, Mich. 49017

Filed Mar. 1, 1979, Ser. No. 16,392


Int. Cl.³ B27L 7/00

U.S. Cl. 144—193 C

12 Claims

1. An impact tool for splitting logs comprising: an elongated guide member, a primary anvil formed at one end of said guide member, a hammer element mounted on said guide member for

sliding movement on said guide member and having an impact surface engageable with said anvil, a tool supported from said anvil and extending generally axially of said guide member, said tool including a curved cutting edge in spaced relation of said anvil, wedge means formed by said tool between said anvil



and said cutting edge to engage wood and widen the split initiated by said cutting edge, said wedge means being formed by a tool portion disposed to one side of the axis of said guide member and having a guide surface conforming to the shape of said curved cutting edge and operable to engage and be guided by the wood path cut by said cutting edge.

4,294,299

HANDBAG CONSTRUCTION


Mac Dorsen, Scarsdale, and Philip A. Saltzman, Brooklyn, both of N.Y., assignors to Stupell Industries, Ltd., Johnston, R.I.

Filed Feb. 12, 1980, Ser. No. 120,936

Int. Cl.³ A45C 3/06

U.S. Cl. 150—28 R

9 Claims



1. A case adapted for movement between open and closed positions, such as a handbag and the like, comprising a pair of identically configured shells, each said shell including an open inwardly concave body having first and second opposed parallel upright end walls inwardly extending therefrom and further terminating in upper and lower edges extending between said end walls, each of said end walls having a face essentially corresponding in planar configuration to that of the end configuration of the case when disposed in its closed position, said lower edges including inwardly extending hinge means defining a longitudinal hinge line, said shells adapted for connection with each other along said hinge line with said concave shell bodies opposed and pivotable away from and towards each other about said hinge line between said open and closed case positions, respectively, with the first end wall of one shell and the second end wall of the other shell overlapped in slidable, generally face to face contacting relationship with the first end wall of said one shell disposed inwardly of the second end wall of the other shell at one end of the case and the second end wall of said one shell disposed outwardly of the first end wall of the other shell at the other case end.

4,294,300

SELF-LOCKING FASTENER

Johannes E. Bouwman, Helmond, Netherlands, assignor to Nedschroef Octrooi Maatschappij N.V., Helmond, Netherlands


Filed Jan. 9, 1979, Ser. No. 2,229

Claims priority, application Netherlands, Jan. 13, 1978, 7800432

Int. Cl.³ F16B 39/282

U.S. Cl. 411—185

5 Claims



1. A self-locking threaded fastener having a planar rigid bearing surface with a plurality of elongated teeth thereon, characterized in that the teeth are located in a plurality of groups, in that the teeth in each group extend parallel with each other and to a tangent to the threads of the fastener, in that the height of the teeth are the same over the entire length of the teeth and in that the teeth extend above said bearing surface with the roots of the teeth being disposed below said surface.

4,294,301

VALVE CONSTRUCTION FOR TUBELESS TIRE

Sepp Lutz, Giengen, Fed. Rep. of Germany, assignor to Alligator Ventilfabrik GmbH, Fed. Rep. of Germany


Continuation of Ser. No. 819,991, Jul. 28, 1977, abandoned. This application Jan. 2, 1980, Ser. No. 109,073

Claims priority, application Fed. Rep. of Germany, Jul. 29, 1976, 2634153

Int. Cl.³ B60C 29/00

U.S. Cl. 152—427

5 Claims



1. A valve for the bore in a tire rim of a tubeless tire comprising: a tubular metal valve body having a passage communicating with the interior of the tubeless tire; a valve core movable in the passage to block a flow of air therethrough out of the interior of the tubeless tire; said valve body having, a rim surface engagement flange extending radially outwardly of the rim bore and bearing on one side of the rim adjacent the rim bore for fixing said valve body in one direction in the rim bore, a deformable tubular portion permanently deformed from an axial position to a radially outwardly extending position and bearing on an opposite side of the rim adjacent the bore to fix the valve body in an opposite direction, and a sleeve extending through the bore and connecting said deformed tubular portion and said engagement flange, the spacing

between said flange and said deformed tubular portion being approximately equal to the length of the rim bore; said deformed tubular portion comprising an initially annular tubular portion extending axially with a remainder of said valve body which is deformed downwardly against an outer surface of the rim adjacent the rim bore; and a soft material lining the outer diameter of which is initially approximately equal in diameter to the diameter of the rim bore, disposed and compressed between the rim bore and said valve body sleeve for establishing an air-tight seal between said valve body and the rim, ends of said soft material lining at opposite ends of the rim bore being bent over by said flange and said deformed tubular portion and pressed into engagement with the one and the opposite side of the rim adjacent the rim bore.

4,294,302

SHUTTER AND AWNING DEVICE


Cyril T. Ricke, Sr., Itasca, Ill., assignor to Security Shutter Corp., Venice, Fla.

Continuation of Ser. No. 528,482, Nov. 29, 1974, abandoned, which is a continuation of Ser. No. 313,563, Dec. 13, 1972, abandoned. This application Aug. 14, 1980, Ser. No. 178,038 The portion of the term of this patent subsequent to Aug. 13, 1993, has been disclaimed.

Int. Cl.³ E06B 9/08


U.S. Cl. 160—133

10 Claims



1. A protective shutter device for an opening in a wall or the like comprising an articulated curtain made of a plurality of identical interlocked elongated rigid slats each assembled hingedly relative to an adjoining slat and each having a rod-like integral projection extending along an edge thereof and a socket-like integral portion extending along the other edge thereof whereby said plurality of slats are assembled together by sliding the rod-like projection along an edge of a slat through the socket-like edge portion of another slat, a pair of guide frame members each mounted on one side of said articulated curtain and having a groove slidably receiving an end of each of said slats, and a drive mechanism for raising and lowering said articulated curtain, said drive mechanism comprising a shaft having an axis of rotation disposed substantially parallel to the longitudinal axis of said slats, means rotatably supporting said shaft at the top of said opening, at least a pair of lugs mounted on said shaft and extending radially from said shaft, means attaching one of said slats disposed at an end of said articulated curtain to one of said lugs whereby rotation of said shaft in one direction causes said articulated curtain to be raised and said slats to be wound around said shaft in spaced apart relationship from said shaft, gear drive means driving said shaft in said one direction for raising said articulated curtain and in an opposite direction for lowering said articulated curtain, and gear drive locking means for controllably locking said gear drive means against rotation when not in operation for raising and lowering said articulated curtain.

through the heat storage chamber, when t_A is less than $t_B + Dt$, where Dt is a temperature offset having a value



which varies inversely with the value of the difference $t_B - t_C$.

4,294,310

METHOD FOR CHARGING AND DISCHARGING A LATENT-HEAT STORAGE MEDIUM AND HEAT STORAGE


Heinz Reusch, Höxter, and Robert Kreikenbohm, Stadtoldendorf, both of Fed. Rep. of Germany, assignors to Stiebel Eltron GmbH & Co. KG, Holzmindel, Fed. Rep. of Germany
Filed Oct. 6, 1978, Ser. No. 949,026

Claims priority, application Fed. Rep. of Germany, Oct. 10, 1977, 2745492; Jul. 17, 1978, 2831325

Int. Cl.³ F28D 21/00

U.S. Cl. 165—104.13

7 Claims



1. Heat storage unit for charging and discharging a latent-heat storage medium by a heat carrier liquid not miscible with it and flowing through the storage medium from the bottom upwardly and collecting on top, comprising: a latent-heat storage medium accommodated in a container, conduit means carrying heat carrier liquid and discharging at the bottom into the container, said container comprising a cylinder with a vertical axis, said conduit means having an exit nozzle located outside the axial center of said container and with an exit direction substantially in a horizontal direction and substantially perpendicular to the radius of the container, said conduit means conducting said heat carrier liquid and charging and discharging said container, the heat carrier liquid being introduced in such a direction and through such an entry cross section into said storage medium that in the melt of the storage medium a flow with a horizontal flow component is built up and the melt is set into a rotary motion by the horizontal flow component, rotary motion of the melt being set by the flowing motion of said heat carrier liquid, at least two conduits being provided with exit nozzles, and a sheet metal deflector arranged ahead of said exit nozzles.

4,294,311 METHOD OF AND ARRANGEMENT FOR THE SEASONAL STORAGE AND USE OF HOT WATER PRODUCED IN PARTICULAR BY ELECTRICAL POWER-GENERATING THERMAL AND NUCLEAR STATIONS

Louis H. D. Denis, Puteaux-Bellini; Abel J. H. Bedue, Versailles, and Jacques Malherbaud, Chatou, all of France, assignors to Compagnie Francaise d'Etudes et de Construction Technip, Rueil-Malmaison, France

Division of Ser. No. 668,000, Mar. 18, 1976, Pat. No. 4,159,736.


This application Oct. 20, 1978, Ser. No. 952,944

Claims priority, application France, Mar. 20, 1975, 75 08747; Jun. 19, 1975, 75 19253; Aug. 27, 1975, 75 26419

Int. Cl.³ F28D 13/00; F24H 7/00

U.S. Cl. 165—104.14

32 Claims



1. A large-capacity tank for seasonal storage of hot water, produced for example by electric power generating thermal and nuclear stations, and for their seasonal use, for example for the heating of buildings, comprising:

a basin of large surface area;
partition walls provided in said basin dividing said basin into a plurality of distinct elongated storage zones, each elongated storage zone having two separated ends;
first means coupled to one end of each of said elongated storage zones for supplying and recovering hot water stored in said elongated storage zones;
second means coupled to the other end of each of said elongated storage zones for supplying and recovering cold water stored in said elongated storage zones; and
means coupled to said first and second means for controlling the flows of water such that an instantaneous supply of hot water at one end of one of said elongated storage zones is balanced by a corresponding drawing off of cold water at the other end of another of said elongated storage zones, and such that an instantaneous drawing off of hot water at one end of said one elongated storage zone is balanced by a corresponding supply of cold water at the other end of said another elongated storage zone, said one and another elongated storage zones providing together a substantially constant body of storage water.

4,294,312

TUBE-BUNDLE HEAT EXCHANGER FOR COOLING A MEDIUM HAVING A HIGH INLET TEMPERATURE

Wolfgang Kehr, and Helmut Lachmann, both of Berlin, Fed. Rep. of Germany, assignors to Borsig GmbH, Berlin, Fed. Rep. of Germany

Filed Apr. 18, 1980, Ser. No. 141,327

Claims priority, application Fed. Rep. of Germany, Nov. 9, 1979, 2945844

Int. Cl.³ F28F 9/22


U.S. Cl. 165—134 R

4 Claims

1. A tube-bundle heat exchanger, for cooling a medium having a high inlet temperature, which comprises:

a shell having an inlet, inlet chamber, and outlet for said medium to be cooled, an inlet and outlet for cooling medium, and a reversing chamber, for medium to be cooled, at that end of said shell remote from said inlet chamber;

an inlet tube bottom and an outlet tube bottom supported at least in part by said shell;
a plurality of tubes, the ends of which are respectively fastened to and connect said inlet and outlet tube bottoms, said medium to be cooled flowing through said tubes;
an intermediate tube bottom supported at least in part by said shell and located in said inlet chamber in such a way as to form an intermediate chamber between said inlet tube bottom and said intermediate tube bottom; and
insert tubes respectively connected to said intermediate tube bottom and located concentrically in at least some of said tubes and projecting out on both sides from respective tubes, those ends of said insert tubes remote from said inlet chamber being sealingly covered by said reversing chamber, said insert tubes being spaced from respective tubes to



form annular spaces therebetween, said annular spaces, toward said inlet chamber, opening into said intermediate chamber, and, in the opposite direction, opening into said reversing chamber;

only those tubes located in a concentric circle with respect to the cross section of said shell including insert tubes, and said shell including an outlet chamber, for cooled-off medium, which concentrically surrounds said reversing chamber in such a way that an annular chamber of circular cross section is formed around said reversing chamber between it and said shell, those tubes present in said annular chamber externally of said reversing chamber not including insert tubes and having a direct connection between said intermediate chamber and said outlet chamber with said outlet for cooled-off medium.

4,294,313

KICKOVER TOOL

Harry E. Schwegman, deceased, late of Dallas County, Tex. (by M. J. Whitfield for First National Bank in Dallas, executor), assignor to Otis Engineering Corporation, Dallas, Tex.

Continuation-in-part of Ser. No. 384,520, Aug. 1, 1973, abandoned. This application Jul. 24, 1974, Ser. No. 490,557

Int. Cl.³ E21B 43/12

U.S. Cl. 166—117.5

74 Claims

1. A kickover tool for installing a device in the side pocket of a side pocket mandrel in a well tubing having a shoulder therein, comprising:

an elongated body;
actuator means arranged in telescopic relationship with said body and movable longitudinally relative thereto;
pivot arm means carried by one and positively connected to the other of said body and said actuator means and movable from a retracted position of longitudinal alignment with said body to an extended position laterally outwardly of said body upon relative longitudinal movement between said body and said actuator means;
releasable latching means initially engageable with said actuator means and said body means for preventing relative longitudinal movement between said body and said actuator means; and
means on said body operatively associated with said releas-

able latching means and engageable with a shoulder in said tubing for moving said releasable latching means to a



position permitting longitudinal movement of said actuator means relative to said body upon relative upward movement of said kickover tool in said tubing.

4,294,314

INSIDE BLOWOUT PREVENTER WELL TOOL


Tosh Miyagishima; Joseph Puntar, and Raymond Wieg, all of Los Angeles, Calif., assignors to Hydriil Company, Los Angeles, Calif.

Filed Dec. 31, 1979, Ser. No. 108,384

Int. Cl.³ E21B 43/00; F16K 31/63

U.S. Cl. 166—318

4 Claims



1. An inside blowout preventer well tool, comprising:
an elongated body threaded at both ends for securing in a conduit when desired and including an axial opening extending through said body;
a flapper pivotally mounted on a side of said axial opening movable between a lower-open position and an upper-closed position;
a downwardly-facing valve seat around the opening, the flapper engaging the seat in a flow sealing relationship in the upper-closed position for blocking fluid flow;
spring means for urging the flapper toward the seat, a piston movably disposed in said opening between an upper position where the lower end of the piston is above the valve

seat and a lower position where the piston operably engages the flapper and holds it in the lower-open position; urging means for normally urging the piston toward its upper position;

said piston being arranged pressure responsive in order that when the internal pressure of drilling mud normally circulating through the opening is greater by a predetermined amount than pressure outside the body the pressure differential will overcome the force of the urging means and move the piston to the lower position, said piston responsive to fluid pressure outside said body for moving said piston to its upper position when the pressure differential is reduced by a predetermined amount;

a hollow cage rigidly mounted in said axial opening, said flapper being pivotally mounted on said cage and the valve seat being formed around the inner surface of the cage.

an outer surface of the cage includes an upwardly-facing shoulder and the inner wall of the body includes a groove coextensive with the shoulder, and a retaining ring in the groove engaging the upper side of the groove and the shoulder for restraining upward movement of the cage, relative to the body; and

the ring is split and the groove is at least as deep as the width of the ring so that at least a portion of the cage can be inserted below the groove without contacting the ring, a plurality of set screws moving the ring inwardly against the cage to engage the shoulder.

4,294,315

LANDING NIPPLE


John H. Yonker; Ernest P. Fisher, Jr., both of Carrollton, Tex., and David Bills, Baldrack, England, assignors to Otis Engineering Corporation, Dallas, Tex.

Filed Nov. 13, 1978, Ser. No. 960,169

Int. Cl.³ E21B 43/12; F16K 3/00

U.S. Cl. 166—322

12 Claims



1. A landing nipple adapted to be made up in a tubing string comprising:

a tubular member having a bore extending axially there-through adapted for receiving a flow control device in said bore,

said tubular member having exterior means for receiving balance and control pressure fluids and means for communicating said fluids from the said exterior to the interior thereof,

said means for communicating control pressure fluid being separated from well fluid pressure conducted through said tubing string by said means for communicating balance pressure fluid and seals therebetween, and

additional seal means between said balance pressure fluid communicating means and said well fluid pressure con-

ducted through said tubing string, whereby failure of said additional seal means causes said well fluid pressure to invade said balance pressure fluid communicating means rather than said control pressure communicating means.

4,294,316

SOD CUTTING AND STACKING MACHINE


Victor H. Hedley, 5050 SW. 70th Ave., Ft. Lauderdale, Fla. 33314, and Walter A. Olson, 510 Grapefruit St., (Apt. 4B), Sebring, Fla. 33870

Filed Apr. 25, 1980, Ser. No. 143,788

Int. Cl.³ A01B 45/04

U.S. Cl. 172—20

21 Claims



1. In a sod cutting machine having; means for peeling parallel strips of sod from the ground simultaneously; means providing a horizontal support in the machine; means for conveying the strips of sod upward from the ground to said horizontal support means; means for cutting the strips of sod transversely into pieces which are deposited on said horizontal support means; transfer means for picking the pieces of sod off said horizontal support means and carrying said pieces to a stacking location at one side of said support means; and means for actuating said transfer means to release the sod pieces to drop by gravity into respective stacks when said transfer means is at said stacking location;

the improvement which comprises:

means for controlling said transfer means to maintain the same orientation of the sod pieces during successive operations of said transfer means;

and means for periodically varying the timing of the release of sod pieces during different operations of said transfer means to thereby produce a lateral overlap between neighboring stacks of sod pieces.

21. In a sod cutting machine having; means for peeling parallel strips of sod from the ground simultaneously;

means providing a horizontal support in the machine; conveyor belt means extending upward and rearward from said peeling means, and driving means for moving said conveyor belt means to convey the strips of sod upward and rearward from the ground;

cutting means located between the rear end of said conveyor belt means and said horizontal support means for cutting the strips of sod transversely into pieces which are deposited on said support means;

transfer means for picking the pieces of sod off said horizontal support means and carrying said pieces to a stacking location at one side of said support means;

and means for actuating said transfer means to release the sod pieces to drop by gravity into respective stacks when said transfer means is at said stacking location;

the improvement which comprises:

means for holding said strips of sod on said conveyor belt means at the latter's rear end and preventing said strips of

sod from continuing to move onto said horizontal support means while said cutting means cuts the sod into pieces; and wherein:

said horizontal support means comprises a plurality of horizontal rollers extending transversely of the machine and spaced apart longitudinally of the machine;

and said transfer means includes a vertically reciprocable horizontal platform below said rollers and vertical fingers extending up from said platform between the rollers to engage the sod pieces from below and lift them off the rollers when said platform is raised, said platform being operatively coupled to said cutting means to cause the latter to cut the strips of sod when the platform is raised.

4,294,317

DRILLHEAD UNIT


Michael J. Amoroso, Marion, Ill., assignor to M.A.T. Industries, Inc., West Frankford, Ill.

Filed Oct. 16, 1978, Ser. No. 951,747

Int. Cl.³ E21C 7/02

U.S. Cl. 173—57

7 Claims



1. A drillhead unit for transmitting power from a motor to a hollow drill bit, the unit comprising:

(a) a housing including an inner passage portion, (b) a gear assembly received by the housing and having a longitudinal axis of rotation, said assembly including:

(1) a shaft having an outer bit-receiving end, and an inner end disposed within the housing remote from said outer end and including an annular transverse bearing face disposed inwardly of the shaft outside diameter, and an axial passage extending between said outer and inner ends and connected to the inner passage portion of the housing, and

(2) a gear disposed between said inner and outer ends of the shaft and connected to said shaft for rotation therewith,

(c) means for mounting the gear assembly to the housing including:

(1) bearing means operatively disposed in coaxial relation between the gear assembly and the housing, and

(2) pressure sealing means disposed between the gear assembly and the housing for separating at least the bearing means from the inner passage portion of the housing, said sealing means including:

(1) a coaxial element non-rotatively attached to the housing and including a transverse bearing face spaced from the transverse bearing face of the shaft, and

(2) a longitudinal resilient seal mounted between said spaced transverse bearing surfaces within the housing,

(d) a pinion assembly received by the housing and having an axis of rotation disposed transversely of the axis of rotation of the gear assembly, said pinion assembly including:

(1) a shaft having an outer end connected to the motor and an inner end remote from said outer end, and

(2) a pinion disposed at the inner end of said shaft and connected to said shaft for rotation therewith said pinion being engageable with the gear of said gear assembly in drive relation thereto,

(e) means for mounting the pinion assembly to the housing including:

(1) bearing means operatively disposed in coaxial relation between the pinion assembly and the housing.

4,294,318

DEVICE FOR MEASURING THE STRESSES APPLIED IN USE TO THE DOWNHOLE ASSEMBLY OF A DRILL PIPE

Robert Desbrandes, Sevres, and Pierre Grolet, Orgerus, both of France, assignors to Institut Francais du Pétrole, Rueil-Malmaison, France


Filed Oct. 19, 1979, Ser. No. 86,607

Claims priority, application France, Oct. 19, 1978, 78 30026

Int. Cl.³ E21B 47/00

U.S. Cl. 175—321

3 Claims



1. A new device for measuring the stresses applied to the downhole assembly of a drill pipe, said device comprising measuring means operatively associated with at least one resilient member interconnecting two adjacent conduits which can respectively be coupled to an upper and to a lower part of said downhole assembly, a sleeve integral with one of said conduits and for protecting said resilient member against external radial pressure, wherein said conduits have substantially the same diameter at their adjacent ends, and wherein said sleeve and one of said conduits form the lateral walls of an annular space which houses at least one intermediate annular piston, said annular space limited by two annular elements forming the end walls thereof, said annular elements being integral with a first of said lateral walls, and slidable along the second of said walls, while said annular piston is integral with the second lateral wall and is slidable along said first wall, said piston separating two annular chambers, one of which communicates with the space outside the downhole assembly of the drill string, and the other communicating with the inner space of said downhole assembly, the operative annular cross-sections of said chambers on both sides of said piston being selected, in dependence on the values of the internal diameter of said annular space at the respective levels of the end walls thereof, so as to substantially nullify any axial load resulting from a pressure difference between the inner and the outer space of the downhole assembly of the drill pipe.

4,294,319

CUTTER HEAD FOR ROTARY PERCUSSION DRILLS
Karlheinz Guergen, Elsterkamp 3, 2110 Buchholz, Nordheide,
Fed. Rep. of Germany


Filed Apr. 25, 1979, Ser. No. 33,305

Claims priority, application Fed. Rep. of Germany, May 16,
1978, 2821248; Sep. 25, 1978, 2841679

Int. Cl.³ E21B 9/02

U.S. Cl. 175—389

5 Claims



1. A rotary percussion drill bit comprising a drill stem having a pilot cutter at one end thereof, and a detachable main cutter head surrounding said drill stem shank and set back from the leading edge of said pilot cutter, said cutter head comprising a plurality of main cutter elements having their cutting edges arranged along outwardly extending main radial cutter lines, characterized in that said main cutter head is provided with both milling and hammering/chipping cutters along each of said main radial cutter lines, said cutter elements are spaced along said radial cutter lines with small gaps between adjacent cutters the gaps between the cutters of one radial cutter line are bridged by cutters arranged along another radial cutter line following said one radial cutter line in the direction of rotation of the cutter head.

4,294,320

METHOD AND APPARATUS FOR WEIGHING MATERIAL BEING COLLECTED


Arnold C. Bilstad, Deerfield, and John T. Foley, Wheeling, both of Ill., assignors to Baxter Travenol Laboratories, Inc., Deerfield, Ill.

Filed Mar. 6, 1980, Ser. No. 127,734

Int. Cl.³ G01G 13/00, 23/14

U.S. Cl. 177—1

23 Claims



1. A process for weighing material being collected, which comprises the steps of:
sensing the tare weight of the weight and collection apparatus;
sensing the weight of the material being collected;
providing pulses in frequency proportion to the weight sensed;
counting the tare weight pulses;
storing the tare weight count;
setting a net weight counter with a predetermined count corresponding to the maximum weight to be collected;

providing a measure weight signal to reverse the tare weight count;
inhibiting the net weight counter until the tare weight count reversal has been completed;
thereafter operating the net weight counter to count the sensed weight pulses; and
providing a completion signal when the predetermined count has been removed from the net weight counter.

4,294,321


POSITION SENSING AND DISPLAY MEANS
Harold A. Wittlinger, Pennington, and Carmine P. Salerno, Avenel, both of N.J., assignors to RCA Corporation, New York, N.Y.

Filed Feb. 27, 1980, Ser. No. 125,118

Int. Cl.³ G01G 3/14; G01R 27/26; H01G 7/00

U.S. Cl. 177—210 FP

11 Claims



1. The combination comprising:
two stationary spaced conductive members;
an electronic oscillator supplying an oscillation of one phase to one of said two members and an oscillation of the opposite phase to the other of the two members;
a movable conductive member having a position between said two stationary members dependent on the magnitude of a physical characteristic being measured; and
an amplitude detector means having an input directly connected to said movable conductive member and producing an output in accordance with the difference in the amplitudes of the oscillations of opposite phases coupled from the two stationary members to the one movable member.

4,294,322

ELECTRONIC WEIGHT MEASURING DEVICE
Yoshihisa Nishiyama, Shizuoka, Japan, assignor to Tokyo Electric Co., Ltd., Tokyo, Japan


Filed May 9, 1980, Ser. No. 148,499

Claims priority, application Japan, May 15, 1979, 59-489

Int. Cl.³ G01G 3/14

U.S. Cl. 177—210 R

11 Claims



1. An electronic weight measuring device comprising:

a power source (E) having first and second power source terminals;
a reference power source terminal;
a load cell (2) coupled between said first and second power source terminals for producing between first and second output terminals an output voltage signal corresponding to a weight of load within a given weight measuring range;
a voltage generating circuit (12) coupled between said first and second power source terminals for generating an output voltage between the output terminal thereof and said reference power source terminal, the output voltage of said voltage generating circuit (12) being varied according to a voltage applied between said first and second power source terminals;
first bias means including a first potentiometer (52) having a movable terminal and two terminals respectively coupled to said reference power source terminal and to an output terminal of said voltage generating circuit;
second bias means including a second potentiometer (64) having two terminals respectively coupled to the movable terminal of said first potentiometer and said reference power source terminal, and a movable terminal coupled to the first output terminal of said load cell;
a signal processor circuit coupled to the second output terminal of said load cell and to the movable terminal of said first potentiometer and producing in response to an output signal from said first bias means an output signal corresponding to the output signal from said load cell within a range corresponding to said given weight measuring range and defined by positive and negative values;
analog-digital converter means coupled to said signal processor circuit to convert the output signal from said signal processor circuit into a digital signal; and
a digital processor unit coupled to said analog-digital converter means to produce an output signal representing a weight to be measured in response to an output signal from said analog-digital converter means.

4,294,323


CRYOGENIC POWERED VEHICLE
Harold L. Boese, Galveston, Tex., assignor to Cryogenics Unlimited, Galveston, Tex.

Filed Sep. 13, 1979, Ser. No. 75,235

Int. Cl.³ B60K 3/02

U.S. Cl. 180—54 B

2 Claims



1. A cryogenic powered vehicle comprising insulated supply tank means for cryogenic liquid, a supply manifold communicated with the supply tank means, a one-way valve between the manifold and supply tank means, a plurality of heat absorbing expansion assemblies each having an inlet communicated directly with the supply manifold, a discharge manifold, each heat absorbing expansion assembly having an outlet communicating directly with the discharge manifold, a master expansion assembly communicating with the discharge manifold, a pres-

surized gas driven motor communicated with the master expansion assembly for imparting driving force to an output shaft, means communicating with the motor to discharge expanded gas to atmosphere and means directly and mechanically connecting the output shaft of the motor to the drive train of a vehicle, each of the heat absorbing expansion assemblies including a serpentine tube through which cryogenic fluid passes, heat exchange fins secured to the tube and baffle means in the tube to provide a spiral flow path to the fluid material to assure heat exchange contact between the material and the tube for absorbing heat from ambient air, said supply tank means including a pair of tanks for liquid nitrogen having a filler line extending to the lower portion thereof, an exhaust line communicated with each of the gaseous upper portions of the tanks, an exhaust expansion assembly connected with the exhaust lines from the tanks and an opened exhaust pipe connected to the exhaust expansion assembly for bleeding gaseous portions of the cryogenic fluid from upper portions of the tanks during refill thereby enabling the tanks to be completely refilled with liquid nitrogen.

4,294,324


CAB SUSPENSION AND RESTRAINING DEVICE
Charles A. Kimball, and Marc L. Sullivan, both of Salt Lake County, Utah, assignors to Time Commercial Financing Corporation, Salt Lake City, Utah

Filed Dec. 3, 1979, Ser. No. 99,467

Int. Cl.³ B62D 23/00

U.S. Cl. 180—89,14

10 Claims



1. A cab suspension and restraining device for securing a tiltable automotive truck cab to the truck chassis, comprising a housing shell adapted to be secured to either the cab or the chassis; an air spring secured within said shell and having a bearing block extending beyond the shell; a second housing shell of larger diameter than the first and adapted to be secured to either the cab or the chassis in opposition to the first housing shell and to receive the said bearing block of the air spring as well as a portion of the first shell in the telescoped relationship; hydraulically operated restraining means for holding the two housing shells in their said telescoped relationship so as to substantially prevent relative lateral movement but to allow limited relative axial movement of the two during travel of the vehicle and to allow complete separation of the two when in unrestraining position; means for operating the restraining means; and means for operatively connecting the air spring to a source of pressurized air.

4,294,325

POWER ASSISTED STEERING SYSTEM FOR VEHICLES
Yoshihiko Nomura, Nagoya, Japan, assignor to Aisin Seiki Kabushiki Kaisha, Kariya, Japan

Filed Jun. 6, 1979, Ser. No. 45,887

Claims priority, application Japan, Jun. 12, 1978, 53-80291[U]


Int. Cl.³ B62D 5/08

U.S. Cl. 180—148

2 Claims

1. A power assisted steering system for vehicles comprising

a steering shaft adapted to be rotated by a steering wheel, rack means adapted to be connected to steering link means, pinion means engaged with said rack means, a torsion rod operatively connected to said pinion means and said steering shaft means at opposite ends thereof, said torsion rod and said pinion means being of integral one-piece construction with the diameter of said rod being substantially smaller than that of said pinion



means, a valve body separate from said pinion means, means connecting said valve body to the end of said torsion rod operatively connected to said pinion means, hydraulic servomotor means operatively connected to said rack means and control valve means operatively connected to said steering shaft means and associated with said valve body for controlling the actuation of said hydraulic servomotor in accordance with the rotation of said steering shaft means.

4,294,326

WHEEL SUPPORT ASSEMBLY

Timothy S. Fry, Dunchurch, England, assignor to GKN Group Services Limited, England


Filed Nov. 14, 1979, Ser. No. 94,023

Claims priority, application Denmark, Nov. 15, 1978, 5073/78

Int. Cl.³ F16H 3/44

U.S. Cl. 180—255

5 Claims



1. A motor vehicle support assembly, comprising a casing connected to a suspension component of the vehicle, a stub axle connected to a road wheel of the vehicle; at least one thin walled bearing liner within the casing receiving the stub axle with a bearing clearance; a thrust plate carried by the axle; thrust washer means carried by the casing and engaging the thrust plate for constraining relative axial movement between the axle and casing; a reservoir for lubricant above said bearing liners; means for delivering lubricant from said reservoir to said bearing liners; and means for returning lubricant to said reservoir upon rotation of said axle;

said means for returning lubricant to said reservoir comprising said thrust plate; means defining an annular groove in which said thrust plate is received, said groove having a radial clearance from said thrust plate over a lower part of the periphery thereof; means defining a sump in said cas-

ing and means for supplying lubricant from said sump to said clearance part of said groove; and means defining a passage from an upper part of said groove to said reservoir, whereby rotation of said thrust plate impels lubricant from said groove to said reservoir by way of said passage.

4,294,327

SAFETY INTERLOCK FOR MACHINE AND ENGINE WITH MAGNETO IGNITION


William A. Howard, Troy Township, Geauga County, Ohio, assignor to Delta Systems, Inc., Twinsburg, Ohio

Filed Dec. 15, 1978, Ser. No. 969,871

Int. Cl.³ B60K 23/00

U.S. Cl. 180—273

7 Claims



1. In a vehicle driven through a transmission to a traction drive by an internal combustion engine that has a magneto ignition system and that has a seat occupied by a driver, a seat-operated switch that is closed when the seat is occupied and a transmission-operated switch that is open when the transmission is engaged, an electrical circuit connected between said switches and across a primary winding of the magneto ignition, said circuit including means for selectively shorting the primary winding when the engine is not running and the transmission-operated switch is open, and means for shorting the primary winding when the engine is running and both the seat-operated switch and the transmission-operated switch are open.

4,294,328

DEVICE FOR EMITTING ACOUSTIC WAVES IN A LIQUID MEDIUM BY IMPLSION

Jacques Cholet, L'Etang la Ville; Pierre Magneville, Vernouillet, and Jean Cassand, Royan, all of France, assignors to Institut Francais du Petrole, Rueil-Malmaison, France

Filed Sep. 18, 1979, Ser. No. 76,646

Claims priority, application France, Sep. 18, 1978, 78 26882


Int. Cl.³ G01V 1/38

U.S. Cl. 181—120

8 Claims

1. A device for emitting acoustic waves in a water medium by implosion, comprising first and second members movable with respect to each other from a spaced apart position to a position of closeness, said first and second movable members being interconnected at their periphery by at least one flexible membrane which defines therewith a tight enclosure of variable volume, moving means for moving said first and second movable members apart from each other and intermittently maintaining them in a spaced apart relationship, said moving means comprising a first cylinder secured to one of said first and second movable members, a piston slidable in said first cylinder and provided with a rod adapted for coming in contact with a wall which is integral with the other of said first and second members, and a system for distributing pressurized fluid in order to exert on said piston an intermittent pushing force, said system comprising a second cylinder of fixed position with respect to said first cylinder and a source of pressurized fluid, said second cylinder including a first component, and a second compartment which is in communication intermittently with said first compartment through a first aperture, with said first cylinder through a second aperture, and perma-

nently in communication with an external medium through at least one third aperture, and said distribution system comprising a valve having a valve rod of smaller section than that of the valve head and movable from a first position wherein the valve head and the end of said valve rod respectively close substantially tightly said first and said second apertures of said second compartment and a second position where said first and



second apertures are opened, a channel being provided throughout said valve and in a direction parallel to its longitudinal axis, for feeding with pressurized fluid said first cylinder, intermittent feeding means for intermittently feeding with pressurized fluid the interior of said first compartment of said second cylinder and maintaining means for maintaining intermittently the pressurized fluid in said first cylinder.

4,294,329

DOUBLE LAYER ATTENUATION PANEL WITH TWO LAYERS OF LINEAR TYPE MATERIAL


Philip M. Rose, Chula Vista, and Frank J. Riel, San Diego, both of Calif., assignors to Rohr Industries, Inc., Chula Vista, Calif.

Filed Dec. 17, 1979, Ser. No. 103,913

Int. Cl.³ E04B 1/82; F01N 1/24

U.S. Cl. 181—222

8 Claims



1. A double layer acoustical honeycomb sandwich panel having structural strength for use in the severe environment in and around high velocity fluid flow paths associated with aircraft gas turbine engines comprising:

first and second honeycomb cores having a multiplicity of endwise directed cells with walls of thin sheet material disposed transversely to the panel;

an impervious facing of thin sheet material;

first, second and third facings of perforated thin sheet material; and

first and second thin sheets of porous fibrous material;

said impervious facing of this sheet material is adhesively bonded to one end wise cell face of said first honeycomb core;

said first perforated facing of thin sheet material is adhe-

sively bonded to said first honeycomb core on the surface opposite said impervious facing of this sheet material; said first thin sheet of porous fibrous material is adhesively bonded to the other surface of said first perforated facing of thin sheet material; said third facing of perforated thin sheet material is adhesively bonded between one end wise cell surface of said second honeycomb core and to the other surface of said first thin sheet of porous fibrous material; said second perforated facing of thin sheet material is adhesively bonded to the opposite surface of said second honeycomb core; said second thin sheet of porous fibrous material is adhesively bonded to the opposite surface of said second perforated facing of this sheet material whereby a smooth outer surface is presented to a high velocity fluid flow.

4,294,330

MUFFLERS FOR PERCUSSIVE PNEUMATIC MACHINES

Stanley L. Baldwin, Winnipeg; Vernon Hampton, Thompson, and Tony F. W. Embleton, Ottawa, all of Canada, assignors to Inco Limited, Toronto, Canada


Filed Jan. 21, 1980, Ser. No. 113,742

Claims priority, application Canada, Feb. 13, 1979, 321357

Int. Cl.³ F01N 1/08, 1/02

U.S. Cl. 181—230

8 Claims



1. A muffler for a pneumatic impact device operating at a frequency below about 60 Hertz comprising a housing adapted to receive and discharge exhaust gas from said impact device and made of an elastic, high damping, hydrophobic material, a gas entrance chamber in said housing communicating with a Helmholtz resonator tuned to a frequency in the range of about 500 to 2,500 Hertz, a gas transport conduit exiting from said gas entrance chamber at an abrupt angle from the direction of gas entrance into said chamber, a plurality of first ports in the walls of said gas transport conduit, said first ports having a total cross-sectional area at least equal to the cross-sectional area of said gas transport conduit, a gas discharge conduit closed at its inner end and having a plurality of second ports in the walls thereof, a plurality of mutually isolated gas transport chambers each in communication with at least one of said first ports and at least one of said second ports, each of said gas transport chambers having a cross-sectional area substantially greater than the cross-sectional area of said first and second ports in communication therewith, the gas path in said transport chamber being at an abrupt angle from both the direction of flow in said gas transport conduit and in said gas discharge conduit.

4,294,331

METHOD AND SYSTEM FOR ESCAPING FROM AN OFFSHORE DRILLING PLATFORM


Ronald H. Reynoir, Robert A. Flautt, both of New Orleans, La., and Clyde M. Leavitt, Ocean Springs, Miss., assignors to The Reynoir Company, New Orleans, La.

Filed Dec. 12, 1979, Ser. No. 102,934

Int. Cl.³ A62B 1/02; B63C 9/02

U.S. Cl. 182—10

17 Claims



1. In a system for escaping from an offshore drilling or production platform, or the like, in emergency situations which includes an offshore platform in operative position substantially fixed relative to the marine bottom at an offshore location for engaging in hazardous operations involving combustible and explosive fluids entrapped in the marine bottom, a floating haven fixedly anchored near but at a safe distance from the platform, at least one cableway unsupported between its ends attached to and extending above water between the platform and the haven with the cableway inclining downwardly from the platform to the haven, and a personnel carrier suspended from and movable along the cableway for transferring personnel from the platform to the haven, the improvement wherein the haven comprises:

- at least one upright buoyant cylinder;
- means for ballasting and deballasting said cylinder;
- means defining an enlarged watertight compartment mounted to the upper end of said cylinder with the top of said compartment forming a weather deck, said cylinder and said compartment-defining means together forming a structure ballastable to float with said compartment partly submerged for increased stability.

4,294,332

SCAFFOLD WITH GEAR DRIVE

Delbert L. Ready, P.O. Box 19462, Houston, Tex. 77024

Filed Apr. 13, 1979, Ser. No. 29,601


Int. Cl.³ E04G 1/20

U.S. Cl. 182—141

16 Claims

1. A scaffolding unit comprising:
- at least two towers each having a front and a back and each tower having a pair of rails, each rail having a linear gear rack facing the front of each tower;
 - bracing means for rigidly interconnecting said two rails;
 - cross-bracing members coupled to the rails of opposite towers for maintaining said towers in back-to-back and spaced relationship;
 - a platform-supporting carriage having a frame outwardly extending from the front of each tower, a pair of laterally-spaced upright shoes on said frame, each shoe having a U-shaped cross section adapted to movably embrace a rail, each shoe defining an opening facing the front of each tower, said shoes having open sides which face each other; and

bi-directional drive means on said frame for moving said carriage up and down on said towers, said drive



means having pinion gears meshable with the racks of said rails through said openings in said shoes.

4,294,333

OIL PAN ADAPTOR FOR INTERNAL COMBUSTION ENGINES


Barry S. Little, Mission Viejo, Calif.

Filed Jul. 20, 1978, Ser. No. 926,285

Int. Cl.³ F02F 7/00; F16N 31/00

U.S. Cl. 184—106

9 Claims



1. Lubricating apparatus comprising:
- pan means for containing a lubricant;
 - adaptor means having a first surface for attachment to a device to be lubricated;
 - flange means fastened to said pan means and positioned to connect said adaptor means to said pan means;
 - quick release clamp means for securing said flange means to a second surface of said adaptor means; and
 - said flange means comprising a collar-like device having a lip which is engaged by said clamp means, said collar-like device including shoulders for securing means thereto, and embossments for establishing securing means relative to said adaptor means.

4,294,334

AXLE HOUSING SUB-ASSEMBLY

Akibumi Shinoda, and Masao Nakane, both of Handa, Japan, assignors to Kabushiki Kaisha Toyoda Jidoshokki Seisakusho, Kariya, Japan

Filed Jun. 5, 1979, Ser. No. 45,814


Claims priority, application Japan, Jun. 15, 1978, 53-83144[U]
Int. Cl.³ B60T 1/06; F16D 55/36

U.S. Cl. 188—18 A

7 Claims

1. A disc brake system sub-assembly for use in a heavy load vehicle comprising: an axle shaft having a spline portion on one end thereof, a differential gear attached to said axle shaft at said spline portion, an axle housing having a through-hole, bearing

means fixed at one end of said through-hole, for rotatably supporting said axle shaft, a plurality of rotary disc plates engaging said axle shaft for rotation therewith, said rotary disc plates axially movable within said through-hole of said axle housing, a plurality of stationary disc plates disposed in said axle housing for axial movement within said through-hole, said stationary disc plates being arranged alternately with said



rotary disc plates, piston means adapted to close the other end of said through-hole, said piston means urging said stationary disc plates against said rotary disc plates when actuated and, means for joining said axle housing and said piston means as a unit, said sub-assembly further comprising further bearing means fixed in said piston means for rotatably supporting said axle shaft at the other end of said through-hole.

4,294,335

DEVICE FOR AUTOMATICALLY ADJUSTING A BRAKING CLEARANCE FOR A DISC BRAKE

Toshifumi Maehara, Chichibu, Japan, assignor to Akebono Brake Industry Co., Ltd., Japan


Filed Oct. 5, 1979, Ser. No. 82,292

Claims priority, application Japan, Oct. 13, 1978, 53-139606[U]

Int. Cl.³ F16D 65/56

U.S. Cl. 188—71.9

6 Claims



1. A device for automatically adjusting a braking clearance for a disc brake in which a friction pad is placed in frictional engagement with a disc rotor by a hydraulically-operated main piston, said device comprising:

an adjusting bolt slidable relative to an end wall of a cylinder in which said main piston is fitted, said adjusting bolt having one end which extends into a liquid chamber of the cylinder;

stop means for controlling movement of said adjusting bolt in a direction apart from the disc rotor;

an adjusting nut threaded on said adjusting bolt with a predetermined thread clearance;

first spring means retained between said main piston and said adjusting nut for transmitting to said adjusting nut the

movement of said main piston in a direction toward the disc rotor;

a stepped piston slidably mounted within an inner periphery of said main piston, said stepped piston being subjected to a force in a direction away from the disc rotor by fluid pressure in said liquid chamber;

limit means for preventing rotation of said stepped piston in said main piston;

a frictional surface defined by each of said stepped piston and said adjusting nut and adapted for engagement with each other; and

second spring means disposed between said main piston and said stepped piston and adapted for biasing said stepped piston in a direction releasing engagement between said frictional surfaces, whereby in response to a given fluid pressure in said liquid chamber said stepped piston moves against said second spring means to engage said frictional surfaces and impede rotation of said adjusting nut.

4,294,336

DISC BRAKE


Kazuaki Shimizu, Fujisawa, Japan, assignor to Nissan Motor Company, Limited, Yokohama, Japan

Filed Mar. 15, 1979, Ser. No. 20,624

Claims priority, application Japan, Mar. 30, 1978, 53-37122
Int. Cl.³ F16D 65/20

U.S. Cl. 188—72.4

7 Claims



1. A disc brake comprising a cylinder means with opposed ends one of which is open and the other of which is closed, said cylinder means being formed at an inner surface of the closed end thereof with an annular groove which is located at the periphery of a circular bottom of said cylinder, cylindrical piston means slidably and sealingly disposed in said cylinder means to define in said cylinder means between said piston means and said closed end of said cylinder means an operating chamber into which an operating fluid is fed through a fluid inlet port formed in said closed end of said cylinder means, a first braking pad directly actuated by said piston means, a second braking pad actuated by said cylinder means through a calliper which is integral with said cylinder means, and a braking disc disposed between said first and second braking pads at the peripheral portion thereof, so that when a predetermined amount of operating fluid is introduced into said operating chamber to cause said piston means and said closed ends to be moved in opposite directions, said first and second braking pads are moved toward the opposed faces of said braking disc and finally brought into contact with the faces to grip said braking disc, wherein one of said cylinder means and said cylindrical piston means is integrally formed at its one end adjacent said closed end of said cylinder means with a groove which is arranged to communicate with both said annular groove and said fluid inlet port when said piston means is in contact with said closed end of said cylinder means.

4,294,337

BRAKING SYSTEM FOR A TRANSPORT CAR FOR TRANSPORTING FILES


Edelbert Wiechert, Berlin, Fed. Rep. of Germany, assignor to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany

Filed Sep. 13, 1979, Ser. No. 74,990

Claims priority, application Fed. Rep. of Germany, Sep. 27, 1978, 2842558

Int. Cl.³ B61H 5/00

U.S. Cl. 188—171



1. A braking system for a transport car for transporting files or goods of similar weight running on profile rails with traveling rollers, equipped with a drive motor fed via wiper contacts of current paths designed on the profile rails, said braking system comprising a brake disc secured to the motor shaft for rotation therewith, and a counter disc aligned for engagement with the brake disc, a spring device for urging the counter disc toward the braking disc to establish a braking condition, an electromagnet coupled with said counter disc and energizable for withdrawing the counter disc from the brake disc against the force of the spring device to release the braking condition, characterized in that the spring device (7, 8, 9) is of unsymmetrical force configuration such that, upon initiation of energization of the electromagnet in a first phase of the withdrawal of the counter disc (4), the counter disc (4) is more strongly withdrawn in the area of lower spring forces.

4,294,338

TRANSMISSION SHIFT CONTROL APPARATUS WITH COUNTERSHAFT BRAKE


John P. Simmons, Muncie, Ind., assignor to Borg-Warner Corporation, Chicago, Ill.

Filed Nov. 9, 1979, Ser. No. 92,886

Int. Cl.³ B60K 41/28, 41/24; F16H 3/38

U.S. Cl. 192—4 A

16 Claims



1. Apparatus comprising a ground member, a shaft rotatable relative to said member, a sleeve rotatable with and slidable relative to said shaft, said sleeve defining a spline, at least one thrust-transmitting strut in break-away connection with said sleeve for rotational and sliding movement therewith, and a blocker ring in rotational lost-motion connection with said strut adjacent said member, said blocker ring defining blocker teeth rotatable into and out of alignment with said spline, said sleeve being slidable for sliding said strut into thrust-transmitting engagement with said blocker ring such that said blocker

ring establishes frictional braking contact with said member and said blocker teeth rotate out of alignment with said spline, said blocker teeth being rotatable into alignment with said spline upon braking of said shaft such that said sleeve is further slidable to release said break-away connection and thereby release said shaft for further rotation.

4,294,339

CLUTCH ASSEMBLY


Bruce A. Granger, Prior Lake, and David S. Klis, Minneapolis, both of Minn., assignors to The Toro Company, Minneapolis, Minn.

Filed Dec. 21, 1979, Ser. No. 106,234

Int. Cl.³ F16D 67/02, 13/08, 13/12

U.S. Cl. 192—12 BA

3 Claims



1. An improved clutch assembly of the type having a driven hub, a rotatable member, clutch means for selectively driving the rotatable member from the driven hub, wherein the clutch means comprises a coiled spring secured to the rotatable member and surrounding the hub and having a first configuration in which the spring engages the hub to drive the rotatable member and a second configuration in which the spring disengages the hub to stop driving the rotatable member, and movable means secured by a first connecting means to the spring for placing the spring into its second configuration, wherein the improvement comprises:

safety means for connecting the spring to the movable means for continued operation of the clutch means in the event the first connecting means fails.

4,294,340

OVERLOAD CLUTCH

Dieter Kunze, Siegburg, Fed. Rep. of Germany, assignor to Jean Walterscheid GmbH, Siegburg, Fed. Rep. of Germany


Filed Nov. 21, 1979, Ser. No. 96,425

Claims priority, application Fed. Rep. of Germany, Dec. 9, 1978, 2853293

Int. Cl.³ F16D 7/02, 43/20

U.S. Cl. 192—56 R

11 Claims



between a first position where said engagement members are out of angular alignment with said second recess means, and a second position where said second recess means are brought into angular alignment with said engagement members; said engagement members being located between said control ring means and said other of said driving and driven members; axial spring means urging said control ring means against said engagement members, and urging said engagement members against said other of said driving and driven members; and circumferential spring means urging said control ring means toward said first position; said engagement members being held in torque transmitting engagement within said first recess means where said clutch is operated to transmit torque below a predetermined nominal value; said control ring means being moved against said circumferential spring means from said first position to said second position when said clutch is operated above said predetermined nominal value thereby to effect disengagement of said engagement members with said first recess means to bring said clutch into an overrunning condition.

4,294,341

GEAR RATIO SELECTION APPARATUS

Petrus H. Swart, Bank Colliery, House No. 1A, Middelburg District, Transvaal, South Africa


Filed Feb. 9, 1979, Ser. No. 10,794

Claims priority, application South Africa, Feb. 15, 1978, 78/0885; Jun. 13, 1978, 78/3385

Int. Cl.³ B60K 41/28

U.S. Cl. 192—0.073

14 Claims



1. Gear ratio selector apparatus for use on a vehicle which has a manual shift gearbox with a gear changing mechanism and a manually operable clutch, the apparatus comprising: means for generating a first signal which is dependent on the vehicle speed, means for generating a second signal which is dependent on the vehicle's throttle position, means responsive to the first and second signals for generating gear ratio selection signals, means responsive to the gear ratio selection signals for disengaging the vehicle's clutch and acting directly on said gear changing mechanism to select a desired gear, means for deactivating the apparatus so that the manual shift gearbox can be operated manually, and means responsive to at least the first signal for controlling the engine speed during gear changes.

4,294,342

CENTRIFUGAL CLUTCH CONSTRUCTION

Richard C. St. John, North Canton, Ohio, assignor to Dyneer Corporation, Canton, Ohio

Continuation-in-part of Ser. No. 928,850, Jul. 28, 1978, abandoned. This application Feb. 4, 1980, Ser. No. 118,502

Int. Cl.³ F16D 23/10


U.S. Cl. 192—105 CD

14 Claims

1. An improved centrifugal clutch construction including: (a) a driven clutch member; (b) pivot collar means adapted to be mounted on a drive shaft for rotation with said drive shaft, the collar means having a cylindrical-shaped sleeve formed with a bore and a pair of diametrically opposed cylindrical-shaped projection means mounted externally on the sleeve and extend-

ing along the parallel with the axis of said sleeve, with the imaginary outer circumferences of the projection means lying in abutting or overlapping relationship with respect to the imaginary outer circumference of the sleeve at the mounting location therebetween when viewed in transverse cross section;

(c) a pair of clutch shoe means, each shoe means being pivotally mounted on a respective one of the pair of projection means for pivotal movement outwardly toward



and against the driven clutch member under the influence of centrifugal force from retracted to extended positions; and

(d) discontinuous opening means formed in an end of each of the clutch shoe means for receiving the projection means therein to pivotally mount the shoe means on said projection means, said opening means having a partial circular cross-sectional configuration of greater than 180° and less than 360° complementary to the cross-sectional configuration of the projection means.

4,294,343

FRICTION CLUTCH FOR MOTOR VEHICLES

Walter Reh, Munich, Fed. Rep. of Germany, assignor to Bayerische Motoren Werke Aktiengesellschaft, Munich, Fed. Rep. of Germany


Filed Feb. 26, 1979, Ser. No. 15,152

Claims priority, application Fed. Rep. of Germany, Feb. 24, 1978, 2808019

Int. Cl.³ F16D 13/72

U.S. Cl. 192—113 A

6 Claims



1. A friction clutch for a motor vehicle, comprising a flywheel disk means having an end face acting predominantly as a friction surface, said end face being provided with a steel

insert, a clutch cover means rigidly connected with the flywheel disk means, said clutch cover means having a plurality of openings and surrounding a pressure ring means and at least one spring, said spring being supported, on the one hand, at the clutch cover means and, on the other, forcing the pressure ring means against the steel insert of the friction surface of said flywheel disk means in the engaged condition of the clutch by way of a friction disk, said flywheel disk means being provided with a plurality of substantially uniformly distributed and outwardly extending aperture means each having a through-opening on the side of the engine and a through-opening on the side of the friction surface of said flywheel disk means, said engine side through-opening extending outwardly from the engine side toward the friction surface side and said friction surface side through-opening being in the form of a substantially longitudinal slot whereby air may be drawn in from the engine side and conducted to the friction surface side of said flywheel disk means in the manner of a radial blower, said substantially longitudinal slot partially accepting said steel insert and being so designed that the steel insert can be subjected to the flow of cooling air on all sides at least when said clutch disengaged.

4,294,344

APPARATUS FOR POSITIONING ARTICLES BETWEEN THE CARRIERS OF A DRAG CONVEYOR, SAID ARTICLES BEING FED IN A CONTINUOUS CLOSED ROW

Johannes D. van Maanen, Berkel en Rodenrijs, Netherlands, assignor to Tevopharm-Schiedam B.V., Netherlands


Filed Sep. 20, 1979, Ser. No. 77,375

Claims priority, application Netherlands, Sep. 21, 1978, 7809612

Int. Cl.³ B65G 47/31

U.S. Cl. 198—461

3 Claims



1. Apparatus for positioning articles between the carriers of a drag conveyor, said articles being fed in a continuous closed row, comprising a first conveyor belt or conveyor-belt system, capable of receiving the articles at one end and a second conveyor belt or conveyor-belt system disposed in line with the first conveyor belt, said second belt being arranged to move at a speed which is greater than the speed of the first conveyor belt and to transfer the articles to the drag conveyor, characterized in that at the transition point between the first conveyor belt and the second conveyor belt a stop means is provided, said stop means being provided on an arm, said arm being mounted for a pivotal movement about a pivot point and a sliding movement along said point, said arm being connected to a crank means through a link means, said link means at one end being pivotally connected to the arm and at its other end being connected to said crank means and intermediate said ends being pivotally connected to a rocker element mounted for a pivotal movement about a fixed point, the movement of said stop means being synchronized with respect to the movement of the drag conveyor, said stop means being movable in an endless path, said path comprising a first portion extending essentially parallel to the first conveyor belt in the direction of travel, a second portion directed backwards and away from the conveyor belt and a third portion directed again towards the conveyor belt, such that during operation, in the first path

portion the stop means moves along with and at a distance in front of an article which is advanced by said first conveyor belt, then in the second path portion said stop means moves away from said article and past said article to the rear and subsequently, in the third path portion, said stop means returns to its starting point behind the article then being moved along faster by the second conveyor belt and in front of the next article still lying on the first conveyor belt.

4,294,345

UNIVERSAL JOINT-LINK CHAIN

Hans-Ulrich Stauber, Grüt, and Jürg Eberle, Hinwil, both of Switzerland, assignors to Ferag AG, Hinwil, Switzerland


Continuation of Ser. No. 703,834, Jul. 9, 1976, abandoned. This application Jan. 5, 1978, Ser. No. 867,027

Claims priority, application Switzerland, Jul. 28, 1975, 9810/75

Int. Cl.³ B65G 17/32

U.S. Cl. 198—683

4 Claims



1. A universal joint-link chain comprising a plurality of chain links, each chain link having opposed ends, one end of each chain link being provided with a hinge body and the opposite end with a hinge socket, the hinge socket of one chain link receiving the hinge body of the neighboring chain link, each hinge socket and each hinge body being formed as an equatorial spherical segment, each chain link including a connection element engaging with the hinge bodies, said hinge body being wider than the hinge sockets, a shaft for mounting each hinge body, said shaft having opposed ends, travelling wheels provided at the opposed ends of the shaft, a substantially C-shaped guide channel which is downwardly open, said guide channel having spaced apart confronting flanges and a rear channel wall oppositely spaced from said flanges, a guide wheel arranged at the region of the travelling wheels, said guide wheel having an axis extending essentially perpendicular to its related connection element and through the center of the associated spherical segment, said confronting flanges serving as tracks for the travelling wheels and for guiding therebetween the guide wheels, said rear channel wall serving as a track for one of the travelling wheels when the chain carries a load, support means carried by each chain link, said support means including means for the attachment of a conveyed material, said attachment means of the support means comprising a lateral offloading attachment element, said offloading attachment element extending substantially parallel to and in vertically spaced relationship from the axis of the shaft and further extending laterally from the underside of the guide channel and transversely to the direction of movement of the chain, said lateral

offloading attachment element, when loaded by said conveyed material, exerting a moment upon the travelling wheels such that one travelling wheel at an end of the shaft bears against its related flange while the other travelling wheel at the other end of the shaft bears against the rear channel wall to provide a stable position for the universal joint-link chain.

4,294,346

BALER FEEDER MECHANISM

Frans J. G. C. Decoene, Zedelgem; Etienne R. O. C. Hommez, Oostende, and Adrianus Naaktgeboren, Zedelgem, all of Belgium, assignors to Sperry Corporation, New Holland, Pa.


Filed Sep. 19, 1979, Ser. No. 77,253

Claims priority, application United Kingdom, Sep. 30, 1978, 38836/78

Int. Cl.³ B65G 25/02

U.S. Cl. 198—740

8 Claims



1. A baler having a drive shaft and a plurality of housing walls adjacent a feed mechanism comprising: a feed bar carrying a plurality of tines; and means for driving the feed bar in an elliptical path, said means including a first shaft having a first crank connected at one end thereof, said first crank rotatably supporting first and second gears, said first gear being a reversing gear intermeshing with a stationary gear and said second gear, said stationary gear supported by one of said walls, a second shaft supporting said second gear at one end thereof and a second crank at another end thereof, said second crank connected to said feed bar.

4,294,347

AUTOMATIC ACCUMULATING LIFT AND CARRY TRANSFER MECHANISM

James L. Furllette, and Donald A. Stadler, both of 1101 Copper Ave., Fenton, Mich. 48430


Filed Feb. 21, 1979, Ser. No. 13,458

Int. Cl.³ B65G 23/02, 43/08

U.S. Cl. 198—751

13 Claims

U.S. Cl. 206—1.7



1. A mechanical automatic accumulating transfer mechanism comprising: an elongated frame, said frame comprising a plurality of work support members secured to and spaced longitudinally along said frame and on each lateral side thereof, said support members on opposite lateral sides of the frame being in alignment with each other and forming a

work station along the frame adapted to receive and support a workpiece; a carriage assembly and means for longitudinally slidably mounting said carriage assembly to said frame between a forward and a retracted position and means for vertically slidably mounting said carriage assembly to said frame between an upper and a lower position; means for moving said carriage assembly between said upper and said lower position; means for longitudinally reciprocally moving said carriage assembly in a forward direction with said carriage assembly in said upper position, and for moving said carriage in the reverse direction with said carriage assembly in its lower position; a plurality of lifting members pivotally secured to said carriage assembly at longitudinally spaced intervals therealong so that at least one lifting member is associated with each work station, said lifting members being pivotal between an upper workpiece engaging position and a lower workpiece clearing position whereby with said lifting members in their work engaging position, said lifting members lift and carry a workpiece from the support members at their associated work station and to the next forward work station; knockdown means for pivoting said lifting members to their workpiece clearing position prior to the rearward longitudinal travel of said carriage assembly; means for detecting the absence of a workpiece at a work station; means responsive to said detecting means for actuating the lifting member associated with the vacant work station from the workpiece clearing position and to the workpiece engaging position during rearward longitudinal travel of the carriage assembly; means for pivoting all lifting members rearwardly of a lifting member actuated by said actuating means from their workpiece clearing position and to their workpiece engaging position; and said carriage assembly further comprising an upper part and a lower part, said upper part being vertically slidably mounted to said frame, means for longitudinally slidably mounting said upper part to said lower part and said lifting members being pivotally mounted to said upper part.

4,294,348


CARRYING CASE FOR ARTIST'S MATERIALS

Jeanne D. Hastings, Old Stone School House, Middle Rd., Lake George, N.Y. 12845

Filed Mar. 24, 1980, Ser. No. 133,529

Int. Cl.³ B65D 71/00; A45C 13/18

10 Claims



1. A paint box for storing and transporting artist's materials, said paint box comprising a base storage section having an upper flat surface and having a plurality of drawers slidably arranged to open at one end, a main body storage section mounted on said base and comprising a front end located on the same side as said one

end, a back end opposite said front end, a top connected between said front end and said back end, a first dropping side attached by a hinging means to said base on one side of said body and spaced inwardly from one side of said base to permit said first side to rest flat upon said base or to stand substantially upright enclosing a first opening bounded by said front end, said top and said back end, and a second dropping side attached by a hinging means to said base on the side opposite to said one side and spaced inwardly from the side opposite said one side of said base to permit said second side to rest flat upon said base or to stand substantially upright enclosing a second opening, opposite said first opening, bounded by said front end, said top and said back end.


4,294,349

KIT FOR REPAIR OF PORCELAIN DENTAL PROSTHESES

Robert L. Ibsen, and William R. Glace, both of Santa Maria, Calif., assignors to Den-Mat, Inc., Santa Maria, Calif. Division of Ser. No. 926,943, Jul. 21, 1978, Pat. No. 4,256,603, which is a division of Ser. No. 787,754, Apr. 15, 1977, Pat. No. 4,117,595. This application Jun. 11, 1980, Ser. No. 158,487 Int. Cl.³ B65D 81/32

U.S. Cl. 206—63.5

13 Claims



1. A kit for the repair of damaged or fractured porcelain dental prosthesis comprising
a box,
a priming agent,
a bonding agent to adhere a restorative agent to porcelain and metal,
a pigmented masking restorative agent for said metal base,
a white powder restorative agent,
a resin for mixture with each said restorative agent to bond said masking agent and said white powder in turn, to said bonding agent,
each of said agents and said resin being disposed in separate containers within said box.

4,294,350

SHOWER PARTY NAME PLATE AND FAVOR

Margaret J. Haase; Meredith Hasse, both of 140-25 Donizetti Pl., Apt. 25E, and Joan Halle, 140-25 Donizetti Pl., Apt. 25F, all of Bronx, N.Y. 10475

Filed Feb. 28, 1980, Ser. No. 125,327

Int. Cl.³ B65D 77/00

U.S. Cl. 206—216

1 Claim

1. A party nameplate and favor comprising, a bag made of a flexible mesh fabric that is easily collapsible, said bag designed to hold candy and the like; a nameplate of cardboard affixed to said bag, said nameplate comprising a shape having a handle portion and a decorative portion affixed to said handle portion, said handle portion having a spur for engagement with said mesh bag; said handle portion and said decorative portion being arranged in an overlap formation such that the overlapping portions of each are attached to each other and a portion of the overlapped portion of said handle portion having said spur thereon, that portion of said handle portion comprising said spur being free from permanent bonding with said decora-

tive portion; means for tying said handle portion to said bag at that portion of said handle portion remote from the overlapping portion thereof, said means for tying also serving to close off said bag after the candy and the like have been inserted



4,294,351

CONTAINERS


Jeffery J. Cheetham, 5 Brunson St., Bayswater, Victoria, Australia (3153)

Continuation of Ser. No. 774,950, Mar. 7, 1977, Pat. No. 4,167,228. This application Jul. 17, 1979, Ser. No. 58,260 Claims priority, application Australia, May 5, 1976, PCS817; Oct. 18, 1976, PC7760

The portion of the term of this patent subsequent to Sep. 11, 1996, has been disclaimed.
Int. Cl.³ B65D 25/08

U.S. Cl. 206—222

7 Claims



1. A container comprising means defining a chamber separated into first and second compartments, the first compartment being arranged to contain a first component of a composition and the second compartment being arranged to contain a second component of the composition, said means defining the chamber comprising a wall means having a closed end and an open end, a partition extending across the wall means, and a plunger slidably and sealingly located in the open end of the wall means, said plunger having an inner end surface spaced from the partition, the inner surface of the plunger being inclined at an acute angle to the partition and having a leading edge and a trailing edge movable along said wall means during a depression stroke of the plunger, at least the major portion of the interior surface of said wall means over which the leading and trailing edges of said inner surface of said plunger move during its depression stroke defining a chamber portion of substantially uniform lateral dimensions on both sides of said partition, said first compartment being defined by part of the wall means, said partition and the inner surface of said plunger, and the second compartment being defined by the closed end of the wall means and the partition, whereby upon the plunger being depressed the leading edge of the inner surface first

separates a corresponding portion of the margin of the partition from the wall means, and then the partition is hinged toward the second compartment by progressive contact with the inner surface and corresponding progressive separation of the margin of the partition from the wall means, the stroke of the plunger being limited so as to leave an unseparated portion of the margin of the partition.

4,294,352

CATASTROPHIC-EXPOSURE EMERGENCY KIT

Rudolf Fitzke, Mariannenplatz 2, 1000 Berlin 36, Fed. Rep. of Germany


Filed May 28, 1980, Ser. No. 154,090

Claims priority, application Fed. Rep. of Germany, May 31, 1979, 2922507

Int. Cl.³ B65D 85/18, 85/56, 81/00

U.S. Cl. 206—223

2 Claims



1. A conveniently transportable emergency kit for use in adverse environmental conditions, comprising:
a pouch dimensioned to receive the head of a user and composed of a synthetic resin foil having a gold metallic outer surface and a silver metallic inner surface;
folded rectangular sheet of synthetic resin foil received in said pouch and dimensioned to wrap around the body of a user, said foil being composed of synthetic resin and having a silver metallized surface adapted to reflect body heat back to the user and a gold metallized surface adapted to be readily detected by the rescuer; and
a supply of vitamins capable of sustaining life in the absence of other sustenance for an extended period received in said pouch.

4,294,353

SIDE CONNECTED CIGARETTE HALF-PACKS

Heinz H. Focke, and Kurt Liedtke, both of Verden, Fed. Rep. of Germany, assignors to Focke & Co., Verden, Fed. Rep. of Germany


Filed Jan. 16, 1980, Ser. No. 112,491

Claims priority, application Fed. Rep. of Germany, Jan. 24, 1979, 7901873[U]

Int. Cl.³ B65D 85/10

U.S. Cl. 206—273

8 Claims



1. A pack for enclosing a pair of cigarette groups, comprising two partial packs connected together via a fold line and made from a one-piece blank, each said partial pack being provided with a rear wall having a closing flap attached thereto by means of an intermediate cover wall, and a front wall having a cut-out portion adapted for the insertion of said

closing flap therebehind, wherein said rear wall and said frontal wall of each partial package are connected to one another by a bottom wall, said frontal walls facing one another when said pack is folded so as to be closed, and wherein said fold line defines a center line of a center bridge extending between said partial packs, said center bridge, when folded along said fold line, extending between the planes of said rear walls and said frontal walls.

4,294,354

PACKAGING CASE

Shoji Ariga, Toda, Japan, assignor to Clarion Co., Ltd., Tokyo, Japan


Filed Dec. 10, 1979, Ser. No. 102,078

Claims priority, application Japan, Dec. 15, 1978, 53-172497[U]

Int. Cl.³ B65D 85/00; H01R 43/00

U.S. Cl. 206—335

3 Claims



1. A packaging case, comprising: a plurality of walls defining a container for containing an article which is adapted to be flush-mounted on a mounting structure by fastening means, said article having a centrally located, projecting, back portion; at least one of said walls having depicted thereon the outlines of (1) an outer, first pattern having the shape of the perimeter of the zone within which the article is to be flush-mounted on the mounting structure, (2) a second pattern of holes disposed inside said first pattern and substantially corresponding to the locations of the fastening means for fastening the article on the mounting structure and (3) a third pattern of an opening centrally disposed inside said first pattern, spaced from said second pattern and substantially corresponding to the shape of the perimeter of the hole to be cut in the mounting structure for receiving the projecting back portion of the article, said third pattern having marked thereon instructions for mounting the article on the mounting structure, said first pattern being detachable from the remainder of said container so as to be useable as a template for marking the location at which the article is to be mounted on the mounting structure, said second and third patterns being detachable from said first pattern so as to be useable for marking the locations of said holes and said opening, respectively, on the mounting structure.

4,294,355

CARTRIDGE FOR HEMOSTATIC CLIPS

Stephen J. Jewusiak, Denville; Howard Beroff, Bridgewater, and Michael Schuler, Edison, all of N.J., assignors to Ethicon, Inc., Somerville, N.J.

Filed Dec. 6, 1979, Ser. No. 100,778


Int. Cl.³ B65D 85/24

U.S. Cl. 206—339

22 Claims

1. A cartridge for holding a plurality of plastic ligating clips, each clip having one leg terminating in a hook-like head member adapted to engage and retain the free end of the other leg of the clip when the clip is closed by pivoting about an integral hinge section, comprising a body member having a base and two side walls forming an elongated channel

a central rail extending from the base of said channel along the length thereof parallel to and spaced from said side walls said rail having a step on one side thereof forming a ledge extending along the length of said rail



a plurality of uniformly spaced notches along the top of said rail angled toward said ledge and means for holding one leg of a clip in position on said rail with the head of the clip on said ledge and the leg of said clip resting on the angled surface of said notch.

4,294,356

DENTAL MIRROR PROTECTOR CASE


Herbert Abramowitz, 143-19 25th Ave., Whitestone, N.Y. 11357

Filed Apr. 21, 1980, Ser. No. 141,994

Int. Cl.³ A45C 11/00; B65D 85/38

U.S. Cl. 206-368

12 Claims



1. A mirror protector case comprising in combination: a mirror cover means for protecting a mirror reflective surface against contact with exterior objects and against contact with an interior surface of the mirror cover means, said mirror cover means including a cover structure having an interior-space surface of concave shape formed as a centrally positioned recess positioned between spaced-apart mirror-contact surfaces, and said mirror cover means further including spring structure mounted on said cover structure and positioned to exert biasing pressure against a rearward wall of a mirror such that mirror bezel structure on each of opposite sides of and adjacent to reflective mirror structure, is pressed against said spaced-apart mirror-contact surfaces, said recess being sufficiently concave that exposed mirror reflective surface is devoid of contact with and is spaced from said interior surface when mirror bezel structure is pressed against the spaced-apart mirror-contact surfaces.

4,294,357

POP UP ABRASIVE DISC DISPENSER

John H. Stevens, Germantown, Tenn., and Bruce A. Reidel, East Amherst, N.Y., assignors to Kennecott Corporation, Stamford, Conn.

Filed Jan. 10, 1980, Ser. No. 110,878

Int. Cl.³ B65D 85/67, 85/672


U.S. Cl. 206-409

21 Claims

1. A device for shipping, storage, protection and dispensing of abrasive discs comprising,

a rectangular box having a bottom, a front wall, a back wall, two side walls and a top closure member connected with each other to define a container, said top closure means hingedly connected to the back wall of said container, a flap hingedly connected to the portion of said top closure

adjacent said front wall and extending into said container adjacent to the front wall of said container, a roll, comprising abrasive discs, said discs having an abrasive surface and an adhesive surface releasably adhered on



said adhesive surface to a continuous flexible backing, said roll being rolled such that the abrasive surface of said discs faces toward the center of said roll, arranged such that the outer end of said roll extends between said flap and said front wall.

4,294,358

PACKAGE FOR VIDEO TUBES


James F. Naubeimer, Chicago, and Steven J. Benzschawel, Carol Stream, both of Ill., assignors to Container Corporation of America, Chicago, Ill.

Filed Apr. 14, 1980, Ser. No. 140,301

Int. Cl.³ B65D 85/42

U.S. Cl. 206-419

3 Claims



1. In a package for a plurality of necked articles of commerce, such as video tube envelopes having a viewing screen at one end and a neck at the other end:

- a walled tube of rectangular cross-section having intumed flanges along the bottoms of the walls of said tube;
- a platform of rectangular cross-section nesting within said walled tube and including a platform panel having flaps extending downward against said flanges to maintain said platform in spaced relationship to said flanges;
- protective and support means formed in said platform panel for said tube envelopes comprising at least one cutout panel in said platform panel, one portion of which is foldable with respect to said platform panel and downward against an intumed flange to brace against said intumed flange and form a support for a tube envelope.

4,294,359

RESHIPPER CARTON FOR FINISHED OR UNFINISHED TV BULBS


Michael R. Berkel, Circleville, Ohio, assignor to Owens-Illinois, Inc., Toledo, Ohio

Filed Jan. 28, 1980, Ser. No. 116,332

Int. Cl.³ B65D 85/42

U.S. Cl. 206-422

15 Claims



1. A carton for a pair of TV bulbs or funnels having a large rectangular end tapering down to an integral neck tubulation, comprising:

- a corrugated box having a bottom and four vertical side walls disposed in rectangular relationship;
- a vertical corrugated partition extending diagonally between two corners of said side walls, thereby dividing the box space into two equal compartments of triangular configuration;
- a pair of integral flaps respectively formed in said partition and swung horizontally outwardly from opposite sides of said partition to respectively traverse said compartments and contact opposed side walls of said box; and
- means on each said flap for engaging the neck tubulation portion of a TV bulb or funnel inserted in the respective compartment to secure same for shipment.

4,294,360

STERILE ARTICLE CONTAINER WITH STERILE OPENING EDGE PORTIONS


Harry H. LeVeen, 321 Confederate Cir., Charleston, S.C. 29407

Filed Aug. 13, 1979, Ser. No. 65,924

Int. Cl.³ B65D 75/58, 77/38

U.S. Cl. 206-438

9 Claims



1. A container for a sterile article, said container comprising a tube of material impenetrable to contaminants, a pair of adjacent portions of said tube extending into the interior of said tube, a seal joining the outermost ends of said portions about the periphery of each thereof, said seal being impenetrable to contaminants forming a contamination barrier whereby both surfaces of each said portion lie within said tube inside such barrier, and said seal being separable upon manual forces applied to said container at the ends thereof in a direction which

moves said ends apart, the innermost ends of said portions being separable without tearing said tube at other than said innermost ends by continued application of said forces whereby said container is opened providing edges about the openings formed by said innermost ends of said portions with the surfaces of said portions on both sides of said edges being those surfaces retained inside of said contamination barrier prior to opening said container.

4,294,361

PUSH AND PEEL BLISTER STRIP PACKAGES

Herman Margulies, South Orange, and Richard H. Kaufman, Ridgewood, both of N.J., assignors to Sterling Drug, Inc., New York, N.Y.

Continuation-in-part of Ser. No. 28,399, Apr. 9, 1979, abandoned. This application Dec. 26, 1979, Ser. No. 106,850

Int. Cl.³ B65D 83/04, 85/56, 75/36, 75/58

U.S. Cl. 206-532

17 Claims



1. A blister strip package comprising a pair of heat sealable co-extensive sheets one of which is provided with a first cavity or row of spaced first cavities for containing a product to be dispensed, and a second cavity or row of second cavities each of which is laterally aligned with a corresponding first cavity and spaced therefrom, said sheets being heat sealed to one another except in the areas defined by the first and second cavities;

the other of said sheets overlying both said first and second cavities and covering the same; said second cavities being adapted to being pushed inwards to an inverted state in order to disrupt the sheet covering said second cavities thereby providing a pull tab formed by the sheet covering said second cavities and enabling said sheet to be peeled back towards a respective first cavity to provide access thereto; said second cavities having edges defining the area for peeling back the sheet covering the cavities.

4,294,362

PARALLELEPIPEDIC PACKING CONTAINER

Kjell H. Martensson, Malmö, Sweden, assignor to Tetra Pak International AB, Lund, Sweden

Filed Apr. 29, 1980, Ser. No. 144,862

Claims priority, application Sweden, May 10, 1979, 7904103

Int. Cl.³ B43M 7/00; B65D 5/70, 5/54


U.S. Cl. 206-622

12 Claims

1. A packing container of the type having an end wall and adjacent side walls and being substantially in the shape of a parallelepiped, said container comprising:

- a sealing fin integral with said end wall, said sealing fin having a free edge, and when said container is sealed said fin overlies said end wall and a portion of an adjacent side wall;
- said sealing fin including a triangular lug extending from said end wall and overlying said side wall;
- a tear line in said sealing fin extending from a point adjacent said triangular lug along a portion of said sealing fin;

said free edge of said sealing fin being oblique with respect to said end wall and having a greater width adjacent said



triangular lug than adjacent the opposite end of said sealing fin.

4,294,363

MERCHANDISE SHELVING DISPLAY


Muammer A. Oztekin, and Vincent J. Albano, both of Birmingham, Ala., assignors to The Kent Corporation, Birmingham, Ala.

Filed Dec. 17, 1979, Ser. No. 104,192

Int. Cl.³ A47F 1/00

U.S. Cl. 211—49 D

3 Claims



1. In a merchandise shelving display having at least one downwardly inclined shelf panel supported from a supporting frame,

(a) at least one downwardly inclined track unit integrally formed and having a pair of upstanding outer rails extending in spaced parallel relation to each other and a pair of upstanding inner rails between said outer rails and extending in spaced parallel relation to each other and said outer rails with the upper surfaces of said outer rails being at an elevation below the elevation of the upper surfaces of said inner rails, and

(b) means securing said track unit to the upper surface of said shelf panel.

4,294,364

LOG CRADLE

Donald L. Bilbrey, 3481 Mills Acres, Flint, Mich. 48503

Filed Feb. 16, 1979, Ser. No. 12,642

Int. Cl.³ A47F 7/00


U.S. Cl. 211—60 R

6 Claims

1. A storage device for storing kindling materials comprising:

a base;
means for receiving kindling materials mounted on the base

and having a bottom and sides provided with air access means, the means for receiving kindling material defined by a frame, the frame comprising at least two opposed frame members mounted to the base and a plurality of



material supporting elements extending between and supported from the frame members; and
a debris receiving receptacle adapted to be slidingly and removably inserted into and nest snugly within the base, beneath the receiving means.

4,294,365

COMBINED DART RACK AND SAFETY DEPOSITORY


Ellsworth S. Henderson, 9532 Lamar St., Spring Valley, Calif. 92077

Filed Nov. 6, 1979, Ser. No. 91,705

Int. Cl.³ A47F 7/00

U.S. Cl. 211—60 R

1 Claim



1. A combined rack and safety depository for game darts having a spike tip and weighted boss at the base of the spike tip, said rack and safety depository comprising:

(a) an elongated, one-piece, generally rectangular simple parallelepiped hollow box-like body having a horizontal flat closed top, an open bottom and substantially vertical side walls when the rack is oriented as in use;

(b) adhesive, no-mar attachment means on one of said side walls enabling said body to be readily removably mounted on a wall surface with said top extending horizontally along and normal to said wall surface;

(c) said body having separate free standing cylindrical sockets extending normal to said top from said top substantially to the plane of the bottom of said body for substantially completely sheathing and protecting the spikes of said darts and said sockets having countersunk annular portions at said top functioning as guides to direct dart spikes into said sockets and also to serve as seats to receive terminals of said bosses, said sockets being offset horizontally from a longitudinal vertical center plane of said body toward the other of said vertical side walls to space darts well away from said wall surface so that the flights of said darts are not damaged by wall contact and finger access to said darts is assured, the lower ends of said sockets being open.

4,294,366

FREE-STANDING PLASTIC BOTTLE


Long F. Chang, Sylvania, Ohio, assignor to Owens-Illinois, Inc., Toledo, Ohio

Filed Mar. 17, 1980, Ser. No. 130,777

Int. Cl.³ B65D 23/00, 1/02

U.S. Cl. 215—1 C

4 Claims



1. A plastic container comprising
a side wall having an oriented generally cylindrical lower portion, and
a bottom joined to said side wall and closing the lower end of said container,
said bottom including a generally elliptical bottom wall and a plurality of oriented circumferentially spaced outwardly convex legs extending from the elliptical wall,
said elliptical wall having a first portion extending downwardly from the lower cylindrical side wall portion and having a radius less than the diameter of the container,
said elliptical wall having a central portion,
each said leg having a first oriented portion extending downwardly from the cylindrical portion of the side wall and having a radius greater than the diameter of the cylindrical portion of the side wall,
a second oriented portion extending downwardly from said first portion of said leg and having a radius substantially less than the radius of said cylindrical portion,
a third oriented portion extending from said second portion defining a flat contacting portion,
a fourth oriented portion extending upwardly and inwardly from said flat portion and being convex outwardly,
a fifth oriented portion blending with said fourth portion and the central portion of the bottom wall,
the radius of said fourth portion being greater than the radius of said second portion,
the first and second portions of each said leg defining an outwardly extending convex surface,
each said leg having diverging oriented side wall portions merging radially inwardly with the elliptical wall portion of the bottom wall.

4,294,367

CONTAINER HAVING RIMMED SHRINK CAP

Chikao Otsuka; Reinosuke Hara, both of Kashiwa, and Yoshito Shigenaka, Tokyo, all of Japan, assignors to Asahi Breweries Ltd., Tokyo, Japan

Continuation-in-part of Ser. No. 833,682, Sep. 15, 1977,

abandoned. This application May 17, 1979, Ser. No. 39,888

Claims priority, application Japan, Sep. 21, 1976, 51-113317


Int. Cl.³ B65D 41/54, 41/62; B67B 5/00

U.S. Cl. 215—246

8 Claims

1. In combination with a container having a tubular neck and a mouth at the upper end of said neck, a rimmed shrink cap comprising a disc-shaped cover having a diameter which is from 10 to 40% larger than the outer diameter of the mouth of the container, said cover being made of a nonshrinkable material, a tubular skirt overlying the top surface of said cover and extending downwardly from the perimeter of said cover, said

skirt being made of a heat-shrinkable material, said cap being positioned so that said cover is substantially concentric with and overlies and closes the mouth of the container, and the lower portion of said skirt surrounds the tubular neck of the container and is heat-shrunk into tight sealing contact with the exterior wall of the tubular neck of the container below the



mouth, the outer edge portion of said disc-shaped cover projecting radially outwardly beyond the outer edge of the mouth and forming an annular rim above said mouth, the upper portion of said skirt being exposed to but spaced outwardly from the outer edge of said tubular mouth and the outer surface of the portion of said neck adjacent to said mouth, said rim allows said cap to be readily torn off with ones fingers.

4,294,368

METAL SEALING CAP

Manfred Bodenbender, Kirchheim; Willy Reinhardt, Burgeln, and Hermann Ritzenhoff, Marburg, all of Fed. Rep. of Germany, assignors to Firma Hermann Ritzenhoff, Marburg an der Lahn, Fed. Rep. of Germany


Filed Feb. 11, 1980, Ser. No. 120,466

Claims priority, application Fed. Rep. of Germany, Feb. 16, 1979, 2906065

Int. Cl.³ B65D 41/32

U.S. Cl. 215—256

12 Claims



1. A metal sealing cap consisting of a cap upper part and a cap lower part removable from said cap upper part with aid of a tear-off band and by means of which cap lower part the sealing cap is securely sealed with the container by flanging in, the cap upper part of said sealing cap being removable from the container by rupturing a line of weakened strength connecting the cap upper part with the cap lower part, wherein the skirt of the cap upper part bordering on the line of weakened strength has been constructed as a folded area of at least three overlapping thicknesses of material, a first and second outer layer of material in the folded area forming a closed fold downwards and the second layer forming together with an inner third layer a closed fold upwards, the third inner layer of material being bounded at its lower perimeter by the line of weakened strength, characterized in that the line of weakened strength is axially overlapped by the lower edge formed by the downwardly closed fold of the two outerlayers of material, whereby upon rupture along the line of weakened strength, the downwardly closed fold circumferentially encloses the edge along which the line was ruptured.

4,294,369

LIQUID DISPENSING RECEPTACLE

Pierre Racine, 4801, rue Rachel, Pierrefonds, P. Q., Canada (H8Y 2C6)


Filed Jan. 21, 1980, Ser. No. 115,247

Claims priority, application Canada, Dec. 20, 1979, 342373

Int. Cl.³ E03D 9/03

U.S. Cl. 215—311

5 Claims



1. A fluid-tight receptacle for ultimate use in the automatic and periodic dispensing of a liquid into a flush tank or the like, comprising:

- a container having a body with a neck portion, said neck portion having a mouth with an upper edge;
- a cup-shaped member tightly engaged in said neck portion, said member having a side wall with an annular rim extending at said upper edge of said neck portion of said container, said cup-shaped member including a bottom end wall with an axial opening therethrough;
- a cap threadedly engaged exteriorly with said neck portion, said cap having a flat circular inner top wall;
- a resilient liner tightly received in said cap on said top wall thereof; and
- a float member slidably mounted relative to said cup member, said float member including a cup portion concentrically mounted within said cup-shaped member and a lower stem portion slidable through said opening of said bottom end wall; said stem portion including an enlarged end portion adapted to abut against said bottom end wall whereby movement of said float member in said cup-shaped member and of the stem portion in the opening is limited by said enlarged portion and said cup portion; said cup portion having an upper edge extending at a level which is at or below the level of said rim of said cup-shaped member, whereby tight engagement of said cap with said container results in sunken engagement of said rim in said resilient liner to thereby prevent fluid leakage from said cup-shaped member.

4,294,370

THREADED CLOSURE AND CONTAINER


Thurston H. Toeppen, Lois La. R.D. 3, Poughkeepsie, N.Y. 12603

Filed Mar. 24, 1980, Ser. No. 133,536

Int. Cl.³ B65D 41/04

U.S. Cl. 215—329

5 Claims



1. A closure device of resilient material, in combination with a container having an external screw thread of less resilient material, comprising: a circular crown disc, a cylindrical side-wall or skirt depending from said disc and perpendicular to it,

an internal screw thread within said sidewall to mate with said external screw thread, and sealing means integral with the inside surface of said crown disc for mating contact with the upper rim of the opening of said container; said internal thread having an initial axial pitch shorter than the initial axial pitch of said external thread by an amount proportional to the difference in the effective elasticities of said materials and to the axial pitch of said external thread.

4,294,371

SUNDAE DISH


Paul Davis, Swampscott, Mass., assignor to Sweetheart Plastics, Inc., Wilmington, Mass.

Filed Jan. 10, 1980, Ser. No. 111,102

Int. Cl.³ B65D 1/22

U.S. Cl. 220—4 E

7 Claims



1. A thin-walled plastic sundae dish adapted to mate with a second identical dish so that one may serve as a cover for the other comprising:

- a bottom wall and an upstanding continuous side wall, an outwardly extending substantially horizontal flange attached to the top of the side wall about its periphery, upstanding first and second beads formed on the flange and each extending about approximately one half the periphery of the flange, said first and second beads being substantially a continuation of one another so that the two together extend about the full periphery of the flange, said second bead being positioned on the flange so that its inner side is disposed outwardly from the center of the dish beyond the outer side of the first bead, and a male latching member formed at one end of the flange as an extension of the first bead and a female latching member formed at the other end of the flange and interrupting the second bead whereby when two identical dishes are placed flange to flange with the male and female latching members of the two dishes registering with one another, the second bead of each dish lies outside the first bead of the other dish to form a skirt about the closed container formed by the two dishes and the male and female latching members are positioned to engage one another and hold the two dishes together.

4,294,372

SMALL-SIZED CONTAINER CAPABLE OF MIXING MORE THAN TWO COMPONENTS AT A PREDETERMINED MIXING RATIO

Shigeru Onishi, Kanazawa, Japan, assignor to Nippon Clean Engine Laboratory Co., Japan

Filed Oct. 29, 1979, Ser. No. 89,041

Claims priority, application Japan, Nov. 3, 1978, 53-135949

Int. Cl.³ B65D 1/24, 88/56


U.S. Cl. 220—20

1 Claim

1. Container apparatus for storing at least two components and for mixing the same according to a predetermined ratio, comprising:

- means for defining at least two chambers, each chamber having a hollow interior space defined therewithin, and

wherein the ratio of the cross-sectional areas of the interior spaces of said at least two chambers is substantially constant at any level of the apparatus when the latter is oriented in a storage position, said chamber defining means including a container having bottom, side and upper walls and a partition wall located within said container, said partition wall having connected to said container bottom and side walls along its bottom and side edges respectively to define said at least two chambers, said partition wall having a top edge which is spaced below the upper wall of said container, the space defined between said partition wall top edge and said upper wall



of said container forming a passage interconnecting said hollow interior spaces of said at least two chambers with each other;

- at least two opening means formed in said container, each opening means communicating with only a respective one of said at least two chambers when the apparatus is oriented in the storage position, whereby each respective component can be charged into the hollow interior space defined by a respective chamber through the respective openings means communicating therewith; and
- at least two lid members, each of said lid members being adapted to close a respective one of said openings means.

4,294,373


LIGHTWEIGHT METAL CONTAINER

Edward C. Miller, Broomfield, and David A. Straw, Lakewood, both of Colo., assignors to Ball Corporation, Muncie, Ind. Continuation of Ser. No. 962,493, Nov. 20, 1978, abandoned, which is a continuation-in-part of Ser. No. 900,411, Apr. 26, 1978, abandoned. This application Jun. 16, 1980, Ser. No. 159,733

Int. Cl.³ B23K 9/00

U.S. Cl. 220—70

10 Claims



1. A lightweight aluminum-base alloy container capable of withstanding a substantial internal pressure without eversion comprising a unitary structure having a seamless cylindrical side wall and a bottom wall integrally formed with the side wall at the lower extremity thereof, the ratio of the thickness of said bottom wall to the thickness of said side wall being 3.0 or less, said bottom wall comprising a tapering surface extending downwardly from the side wall, said tapering surface forming a taper angle of between 1.3° and about 2.2° and a wall taper thickness of between about 0.006 inch and about 0.010 inch in excess of the side wall, an outer frustoconical surface extending downwardly and inwardly from said side wall toward the axis of said container, said outer frustoconical surface forming a bottom angle of between about 35° and about 45° with respect

to the axis of the container, a bottom radius integrally connected with and extending downwardly from said outer frustoconical surface providing an annular supporting surface of the container, said annular supporting surface having a diameter in the range of about 2.05 inches to about 2.2 inches, an inner frustoconical surface integrally connected with said bottom radius and extending upwardly and inwardly from said annular supporting surface toward the axis of the container, said inner frustoconical surface forming an angle in the range of about 12°±4° with respect to the axis of the container, the height of said inner frustoconical surface being less than half the height of said outer frustoconical surface, and a downwardly concaved center panel integrally connected with said inner frustoconical surface and extending upwardly and inwardly from said inner frustoconical surface to the axis of said container, the radius of curvature of said downwardly concaved center panel being between about 2.250 inches and about 3.000 inches, said center panel extending at its uppermost portion slightly above said height of said outer frustoconical surface.

4,294,374

PLASTIC DRUM ASSEMBLY

Geoffrey C. Ames, Toledo, Ohio, assignor to Owens-Illinois, Inc., Toledo, Ohio


Continuation of Ser. No. 636,272, Nov. 28, 1975, abandoned.

This application Feb. 8, 1978, Ser. No. 876,081

Int. Cl.³ B65D 1/46, 6/34, 25/22

U.S. Cl. 220—71

17 Claims



1. A plastic drum assembly comprising a single piece blow molded plastic drum having a top end panel, a bottom end panel, and a circumferential sidewall joining said top and bottom end panels, said top end panel defining at least one opening therethrough, said sidewall including a horizontal circumferential recess adjacent said top end having a substantially semi-circular cross section and at least one arcuate substantially vertical drain channel formed in the surface of said recess and a split metal collar mounted on said drum having a vertically disposed wall portion including a substantially circumferential inwardly extending projection adjacent the lower margin of said vertically disposed wall portion, said inwardly extending projection having a substantially semi-circular cross section positioned within and in snug contact with said recess, said metal collar further including a substantially circumferential rolled annular bead disposed adjacent the upper margin of said vertically disposed wall portion, said annular bead located above said top end, whereby said metal collar and drum are movable by chime-gripping drum handling devices.

4,294,375

VEHICLE FUEL TANK SEALING CAP

Theodor Gerdes, Langenfeld, Fed. Rep. of Germany, assignor to Blau KG Fabrik Fur Kraftfahrzeuge, Fed. Rep. of Germany


Filed Dec. 4, 1979, Ser. No. 100,159

Claims priority, application Fed. Rep. of Germany, Dec. 4, 1978, 2852454

Int. Cl.³ B65D 41/06, 51/18

U.S. Cl. 220—293

6 Claims



1. In a sealing cap, for the fuel tank pipe of a motor vehicle, comprising:

(i) an outer cap 10

(ii) an inner cover portion 12, said inner cover portion 12 being cup-shaped and having a peripheral flange 18 at its side facing the outer cap 10, said cover portion 12 carrying packing means to form a seal with the fuel tank pipe, said cover portion 12 further comprising fastening means 22 for engagement with the fuel tank pipe, said outer cap 10 at its side facing the inner cover portion 12 including an integrally molded rib 36 of synthetic material having at its free end at least one inwardly-directed radial lug 38 engaging said inner cover portion 12, said outer cap 10 being adapted to snap off from said inner cover portion 12 under the influence of forces exerted on it as a result of a motor vehicle accident,

the improvement which comprises:

(a) the strength of the lug 38 is selected such that it is adapted to break under the influence of said forces,

(b) positive anti-rotational coupling means 56, 58, 70, 72 to prevent relative rotation between said inner cover portion 12 and said outer cap 10 and provided respectively on said inner cover portion 12 and on said outer cap 10.

4,294,376

FUEL TANK CAP


Russell D. Keller, 1750 SE. Risley, Milwaukie, Oreg. 97222

Filed Jan. 3, 1980, Ser. No. 108,448

Int. Cl.³ B65D 45/00

U.S. Cl. 220—318

8 Claims



1. A fuel tank cap comprising:

a cap body adapted to form a closure on the outer end of a fuel tank neck,

a housing member depending from underneath said cap body and provided with movable means comprising a

plurality of balls for selectively engaging the underside of an inner lip of the fuel tank neck when said cap body is positioned on said fuel tank neck,

an actuating member for operating said movable means for moving the same between first and second positions into and out of engagement with the inner lip of the fuel tank neck,

and a manually operable control element on the outer side of said cap body for causing said actuating member to operate said movable means between said first and second positions.

4,294,377

CONSTANT PRESSURE COOKER AND FASTENER


Shin-I. Chen, No. 5, 102 La., Ho-Chiang St., Taipei, Taiwan

Filed Mar. 14, 1980, Ser. No. 130,341

Int. Cl.³ B65D 45/34

U.S. Cl. 220—321

12 Claims



1. A constant pressure cooker, comprising:

a cooker body having a protruding edge portion;

a cover having an exterior margin curved inward and under the cover to form a cover groove, the exterior margin being shaped so as to mate with the protruding edge portion of the cooker body when the cover is placed on the cooker body;

a thermal resistant rubber material placed within the cover groove; and

a coupling ring having a gap therein and having a cross sectional shape for clamping the protruding edge portion of the cooker body to the exterior margin of the cover and fabricated from a flexible metal material such that for pressures within the cooker below a predetermined threshold, the edge portion of the body is held tightly to the exterior margin of the cover, but for pressures within the cooker at or above the predetermined threshold, the cross-section of the ring deforms and allows the exterior margin of the cover to separate from the edge portion of the cooker body so that pressurized gases can escape from the cooker; and

means for adjusting the size of the gap to clamp and unclamp the coupling ring.

4,294,378

SAFETY HATCH COVER APPARATUS

Evsey Rabinovich, Erie, Pa., assignor to Emco Wheaton Inc., Conneaut, Ohio

Filed Feb. 4, 1980, Ser. No. 118,647

Int. Cl.³ B65D 45/28

U.S. Cl. 220—323

14 Claims

1. Hatch cover apparatus for a tank comprising a base member fixed to the tank having an opening providing access to the tank; a pair of keeper members mounted on the base member at opposite sides of said opening, each keeper member providing lateral access for an end portion of a latch bar; a cover associated with the base member and adapted to be put in closed position to engage the base member and close the opening and to be put in opened position to open the opening; an elongated latch bar adapted to have its ends engage with the keeper members when the cover is in closed position and be disengaged from the keeper members when the cover is in opened

4,294,380

TELLER MACHINES AND METHODS OF OPERATION THEREOF


Kenneth F. Rankin, St. Albans, England, assignor to Chubb Integrated Systems Limited, Brighton, England

Filed May 21, 1979, Ser. No. 40,786


Int. Cl.³ E05G 7/00

U.S. Cl. 221—195

2 Claims



position; means on the cover for mounting a latch bar on the cover so that it is capable of limited movement to engage and disengage from said keeper members and of rotation about its longitudinal axis, said latch bar being thus movable between a position in which its ends are engaged with the keeper members and another position in which its ends are not so engaged; a cam affixed to the latch bar and adapted to be rotated about the longitudinal axis of the latch bar, said cam having a projecting external surface portion that is located a maximum distance from the latch bar axis and toward the cover when the cover is in its closed position and retracted external surface portion



located at lesser distance from the latch bar axis and away from the cover when the cover is not in the closed position; resilient biasing means operating by cooperation with the cover, the cam, the latch bar, and the keeper members to urge the cover toward the base member when the cover is closed and the latch bar ends are engaged with the keeper members, yet when gas pressure above a predetermined amount exists within the receptacle and generates a force on said cover against the biasing force of said biasing means, said biasing means will permit at least a portion of the cover to lift from the base member and permit escape of such gas from the tank.

4,294,379

UPWARD VENTED TRASH RECEPTACLE FOR FLEXIBLE COLLAPSIBLE TRASH LINER


Robert A. Bard, 70 Hopatcong Dr., Lawrenceville, N.J. 08648

Filed Aug. 27, 1979, Ser. No. 70,179

Int. Cl.³ B65D 25/16

U.S. Cl. 220—404

4 Claims



1. An apparatus for receiving a flexible and collapsible trash liner comprising:

a rigid upward vented trash receptacle having a main body with a closed bottom; a collapsible trash liner; and an open top with a rim containing circumferentially positioned notches for assisting the escape of air trapped between the walls of said main body and said trash liner; said main body including along its side walls a plurality of axially aligned hollow open ended conduits positioned in the corners of said main body and spaced sufficiently from said bottom and top of said receptacle to permit trapped air to flow out of said trash receptacle during the filling of said liner and to permit ambient air to flow into said trash receptacle as the liner is removed from said receptacle so as to reduce the vacuum created in the void between the exterior of said liner and the interior of said receptacle.

4,294,381

DISPENSER FOR AND METHOD OF DISPENSING A MATERIAL FROM A NON-PRESSURIZED MATERIAL RESERVOIR

Kenneth L. Miller, 7345 N. Meridian St., Indianapolis, Ind. 46260

Continuation-in-part of Ser. No. 668,417, Mar. 18, 1976, Pat. No. 4,095,722. This application Jun. 15, 1978, Ser. No. 915,874

The portion of the term of this patent subsequent to Jun. 20, 1995, has been disclaimed.


Int. Cl.³ B65D 37/00

U.S. Cl. 222—1

21 Claims

1. A material dispenser for dispensing a material from a non-pressurized material reservoir comprising a resilient pinch-off tube having opposite ends, one end of said pinch-off tube being removably coupled to said reservoir, a nozzle removably coupled to other end of said pinch-off tube, said nozzle being in communication with said reservoir through said tube, and squeezing means, operative with said tube, for selectively forcing a selected amount of said material out of said tube and nozzle and drawing said material from said nozzle.

zle into said tube, said squeezing means including an upper ram and an intermediate ram and a lower ram, each of said rams being selectively movable from a first position in which said ram is disengaged from said tube to a second position in which said ram engages and compresses said tube and back from said second position to said first position, said squeezing means further including means for positioning said rams and means, operative with said ram positioning means, for sequencing the movement of said rams to, firstly isolate said material in said tube by positioning said upper and lower rams in said second position thereof, secondly dispense a portion of said material in




said tube by positioning said upper ram in said second position thereof, and said lower ram in said first position thereof, and squeezing said tube by moving said intermediate ram from said first position thereof toward said second position thereof, thirdly withdraw said material from said nozzle into said tube by positioning said lower ram in said first position thereof and positioning said upper ram in said second position thereof, and positioning said intermediate ram in said first position thereof, and fourthly fill said tube from said reservoir by positioning said intermediate and upper rams in said first position thereof and said lower ram in said second position thereof.

4,294,382 CONTAINER CLOSURE DEVICE

Kenneth L. Summers, Angola, and Mahlon E. Rieke, Auburn, both of Ind., assignors to Riche Corporation, Auburn, Ind.
Filed Jul. 26, 1979, Ser. No. 60,971
Int. Cl.³ B67D 3/00

U.S. Cl. 222—529

1 Claim



1. A cap-like closure device for a container of the type including a flexible spout member having a substantially cylindrical top rim portion and an outer edge portion and extendable from a nested orientation to a pouring orientation, an anchor ring for securing the outer edge portion of the flexible spout member to the container, a first cap for engaging the top

rim portion and closing said spout member, and a tamper-proof cap disposed over and removable from the top of said first cap, wherein the improvement comprises:


an interior annular groove disposed in a top lip portion of said first cap and including a base surface at the uppermost end, said interior annular groove opening downwardly toward said top rim portion of said flexible member, wherein said interior annular groove narrows as it extends upwardly away from the top rim portion of said flexible spout member, and wherein said top rim portion has an upwardly and outwardly inclined top surface which tapers to an edge at the outermost and uppermost location of said top rim portion, the width of the interior annular groove at said base surface is narrower than the maximum thickness of said top rim portion thereby forcing the thinner parts of said top rim portion corresponding to the inclined top surface to curl into said interior annular groove when said first cap is fitted onto said flexible spout member.

4,294,383 MORTAR APPLYING DEVICE

Rodney J. Hession, and Brent M. Hession, both of New Orleans, La., assignors to Hession Industries, Inc., New Orleans, La.
Filed Jan. 18, 1980, Ser. No. 113,325
Int. Cl.³ B05D 1/26, 1/30; F04G 21/16

U.S. Cl. 222—611

5 Claims



1. A device for applying mortar to a course of masonry units having side faces and a top surface, comprising a hopper formed with side members and end plate members and having an open top and bottom, plate members defining a divider mounted within said hopper and defining a pair of mortar receiving and delivering compartments communicating with the open top and bottom, the portion of said end plate members of said hopper lying between said plate members of said divider are formed to define an elongated recess extending through the bottom of said hopper, a wheeled undercarriage chassis extending through said recess and fastening means on said hopper for securing same to said chassis for moving said hopper over the top surface of a course of masonry units and semi-cylindrical guide members secured to said hopper in trailing relation for depositing uniform beads of mortar upon said surface, contemporaneous with the moving of said hopper.

4,294,384 LIQUID DISPENSER HOLDER

Terrence D. Howell, Apt. 214, 3395 Yankee Doodle Rd., Eagan, Minn. 55121

Filed Oct. 25, 1977, Ser. No. 844,632

Int. Cl.³ B60N 3/10, 3/18


U.S. Cl. 224—42.2

1 Claim

1. A liquid dispenser holder, comprising:
(A) a cradle for receiving and holding a liquid dispenser such as an Air Pot, which cradle includes a cradle base having a planar member for setting thereon of a dispenser and a collar supported vertically above the base for at least partially encircling the upper portion of a said dispenser to prevent the dispenser from tipping;
(B) cradle attachment means adapted to hold the cradle stationary when the cradle is on a vehicle seat, transmis-

sion shroud, or floor, which attachment means includes a pair of planar leg members rigidly attached to and depending from said cradle base and diverging from each other in two directions, which leg members are longitudinally elongate, closer together at one end than the other and closer together at their juncture with said cradle base than at their bottoms to form a saddle for securely engaging a transmission shroud graduating dimensionally either longitudinally or vertically;

(C) a ballast compartment supported by said base for accepting ballast or utilitarian articles of sufficient weight to stabilize said cradle; and



(D) receptacle holding means for supporting a receptacle in position under and to receive a fluid from an Air Pot dispensing spout, which holding means includes a platform which in turn is an extension of said collar and has at least one receptacle filling station having means for releasably engaging a receptacle such as a coffee mug and which receptacle holding means is supported vertically above said cradle base, whereby all the steps for filling a receptacle from a dispenser such as an Air Pot can be accurately and safely performed with only one hand.

4,294,385 RAPIDLY SEPARABLE HOLSTER AND HOLSTER-CARRYING BELT


William H. Rogers, Jacksonville, Fla., assignor to Alpha Plastics, Inc., Jacksonville, Fla.

Filed Feb. 25, 1980, Ser. No. 124,658

Int. Cl.³ F41C 33/02; F41B 13/04

U.S. Cl. 224—240

13 Claims



1. A rapidly separable holster and holster-carrying belt comprising a holster with two spaced upstanding pins on the side of the holster next to the body of the person wearing the holster, said pins comprising a shank and a generally flat head of substantially larger diameter than the diameter of said shank; and a belt having on the inside surface thereof two rigid slotted plates spaced apart substantially the same distance as the distance between said pins, each of said plates and the contiguous portion of the belt being perforated with a slot, one end of which is slightly larger than the diameter of said head and the other end of which has a diameter larger than the diameter of said shank and smaller than the diameter of said head, said slots being oriented with the lengthwise axis of the slot substantially


parallel to the lengthwise axis of the belt and with the distance between the smaller ends of the slots being less than the distance between the larger ends of the slots.

4,294,386 TENNIS BALL HOLDER

Arlen E. Ingram, 32606 Barkley, Livonia, Mich. 48154
Continuation of Ser. No. 912,446, Jun. 5, 1978, abandoned. This application Jan. 25, 1980, Ser. No. 115,386
Int. Cl.³ A45F 5/00

U.S. Cl. 224—252

5 Claims



1. A tennis ball holder attachable to the garment of a player and constructed and arranged to receive and hold only one tennis ball at a time, comprising a homogeneously integral one-piece body of a plastic material having a retainer ring which is flexible, resilient, form-retaining, and can be disposed in a generally horizontal plane with its central axis extending generally vertically, a plurality of discreet and generally circumferentially spaced apart fingers each at its proximal and homogeneously integral with said ring and depending normally generally downwardly from said ring and having its distal end curved generally inwardly of said ring toward its center axis and terminating at a point spaced from said center axis and the distal end of the other of said fingers, each said finger being flexible, resilient, form-retaining, and constructed and arranged so that its distal end, in the unflexed position of such finger, underlies and supports a single tennis ball inserted through said ring and can be yieldably moved away from said center axis to allow the tennis ball to be manually pushed generally downwardly beyond the distal end, out of the holder and into the fingers and hand of a user by pressure manually applied to the top of the tennis ball by the thumb of the same hand of the user extending through said ring, said ring being constructed, arranged, and dimensioned to yieldably permit the tennis ball to pass therethrough and into engagement with said flexible fingers and in its normal unflexed state to retain the tennis ball between said ring and said fingers, and a tab homogeneously integral with said ring and being constructed and arranged for attaching the holder to the garment of a tennis player.

4,294,387
CONVERTIBLE SKI CARRYING APPARATUS
Kenneth A. Wnek, 282 Valley Park South, Bethlehem, Pa. 18018
Continuation-in-part of Ser. No. 921,969, Jul. 5, 1978, Pat. No. 4,171,759. This application Jun. 25, 1979, Ser. No. 51,516
Int. Cl.³ B60R 9/12


U.S. Cl. 224—315

10 Claims

1. A convertible carrier for skis comprising:
(a) a generally L-shaped housing including a floor portion and a side portion, said floor portion having sufficient length and width to receive at least one pair of skis resting in parallel juxtaposition, and where said skis are supported on their longitudinal edge by said floor portion, said side portion being of sufficient height to provide lateral support for said skis, said floor portion also including a transverse opening, said opening being of a shape and size to permit the insertion therein of a bracket plate which is separate from said housing;
(b) retainer means for said skis of the same proximate size

and shape as said side portion, hingeably connected at its proximal end to said floor portion and at its distal end adapted to interface with a handle means whereby said carrier may be opened or closed;

(c) handle means to provide hand carrying of said carrier said handle means adapted to mate with said retainer means so that said handle means together with said floor portion, side portion and retainer means define a total closure for said skis and said poles, said handle means also including at least one shank portion containing at least one recess positioned intermittent its length to receive an extension bar section of a locking mechanism;



(d) bracket means, including at least one bracket plate, adapted to be affixed to a vehicle, said bracket plate adapted to slidably mate within said housing transverse opening, said bracket plate including at least one opening to receive and permit passage therethrough of said shank whereby when an end of a shank extends into an opening, sliding of said carrier from said bracket plate is prevented; and,

(e) locking means interconnected with said handle means and said shank so that when said shank is slidably mounted in said housing, said extension bar section operably connects with said locking mechanism so that unlocking of said locking mechanism operates to release said extension bar section from a recess of said shank.

4,294,388

CAR TOP CARRIER SUPPORT


Franz Wünnel, Morellstr. 1, D-8900 Augsburg, Fed. Rep. of Germany

Filed Aug. 11, 1980, Ser. No. 177,445

Int. Cl.³ B60M 9/04

U.S. Cl. 224—315

10 Claims



1. A car top carrier support comprising a substantially H-shaped frame, the frame consisting of a pair of parallel hollow tubes and at least one hollow tube cross-wise extending therebetween, at least four legs arranged at the frame and extending downwardly, the legs standing on the car top edge or the gutter of which, a claw associated with each leg and connected with a slide, the slide being movably guided in the leg for a reciprocating motion; a central hand operating means arranged at the frame and a set of at least four driving means, each one of the driving means being connected at its one end with one of the claws and at its other end with the central operating means.

4,294,389

DISPENSER FOR ROLLS OF PAPER

Filip Falk, Hammarbacken 22, S-182 35 Danderyd, and Lennart Falk, Visborgsgatan 16, S-621 00 Visby, both of Sweden


Filed Sep. 7, 1979, Ser. No. 73,270

Claims priority, application Sweden, Sep. 13, 1978, 782101

Int. Cl.³ B26D 1/02; B26F 3/02

U.S. Cl. 225—34

5 Claims



1. A dispenser for a plurality of rolls of paper or the like comprising:

(a) a longitudinally extending hollow housing having a rear wall, a front wall and confronting side walls;

(b) means at an upper section of said housing for depositing in said housing a column of rolls of paper, said column of rolls of paper extending in the longitudinal direction of said housing with the axes of said rolls of paper extending in parallel relation between said side walls and transversely of said housing;

(c) said front wall and said side walls at a lower section of said housing forming a paper exit opening for said housing;

(d) said housing being formed with a wall at the lower section thereof on which a dispensable roll of paper is seated for rotation, said dispensable roll of paper being a lower roll of said column of rolls of paper, said dispensable roll of paper having the free end thereof projecting through said paper exit opening;

(e) a cutting edge extending transversely across said paper exit opening for severing the free end of the dispensable roll of paper from the remainder of the roll of paper; and

(f) a gate supported in said housing by said rear wall between said dispensable roll of paper and a succeeding roll of paper, said gate being arranged to retain said succeeding roll of paper out of contact with said dispensable roll of paper, said gate being displaceable in response to said succeeding roll of paper being moved into the position occupied by said dispensable roll of paper after the supply of paper of said dispensable roll of paper has been expended, said gate being returned to its initial position to retain the next succeeding roll of paper out of contact with the roll of paper now occupying the position of a dispensable roll of paper, said gate being adjustably supported in said housing by said rear wall in the longitudinal direction for accommodating rolls of paper of various diameters in maintaining the succeeding roll of paper out of contact with the dispensable roll of paper.

4,294,390

PINCH ROLLER MECHANISM

Takeshi Toriumi, Sagami-hara, and Tamotsu Tominaga, Aki-shima, both of Japan, assignors to Hitachi Denshi Kabushiki Kaisha, Tokyo, Japan

Filed Oct. 16, 1979, Ser. No. 85,377

Claims priority, application Japan, Oct. 23, 1978, 53-146353

Int. Cl.³ B65H 17/22



U.S. Cl. 226—181

3 Claims

1. A pinch roller mechanism comprising a source of rotary

motion, an eccentric cam coupled to said source of rotary motion and adapted to be rotated by said source, a capstan shaft, a pinch roller, an arm normally urged against the side surface of said eccentric cam and supporting said pinch roller,

(c) the joining surfaces of the parts are urged into interengagement and are simultaneously caused to undergo rela-



spring means of different spring forces for urging said pinch roller against said capstan shaft when said eccentric cam is rotated by said source of rotary motion, and control means for controlling energization of said source.

4,294,391

FASTENER DRIVING TOOL


Allen R. Obergfell, Park Ridge, Ill., assignor to Duo-Fast Corporation, Franklin Park, Ill.

Filed Oct. 31, 1979, Ser. No. 89,878

Int. Cl.³ B25C 1/04

U.S. Cl. 227—130

13 Claims



1. In a fastener driving tool including a housing defining a reservoir for pressurized fluid, a nose portion and a handle portion, a driver mounted in said nose portion, means for driving said driver through a driving stroke, the improvement comprising

means for returning said driver to a static position, said returning means comprises a chamber, first and second inlets in said chamber, said first and second inlets in fluid communication with said reservoir, a diaphragm mounted in said chamber and sealing said first inlet, and a first outlet in said chamber in fluid communication with said nose portion below said driver, said diaphragm separates said first inlet and said outlet from said second inlet and controls fluid flow therethrough.

4,294,392

METHOD OF JOINING A PAIR OF METAL PARTS

Nicholas J. Colloff, Sutton Coldfield, England, assignor to Lucas Industries Limited, Birmingham, England

Filed Dec. 28, 1979, Ser. No. 108,129

Claims priority, application United Kingdom, Jan. 16, 1979, 1598/79


Int. Cl.³ B23K 21/00

U.S. Cl. 228—111

4 Claims

1. A method of joining a pair of metal parts wherein: (a) at least one of the parts is provided with an insulative coating at its surface to be joined to the other part, (b) at least one of the parts defines a plurality of substantially parallel, longitudinally extending splines at its surface to be joined to the other part, and

tive vibrational movement in a direction substantially parallel with said splines.



1. A method of manufacturing a vehicular wheel rim comprising the steps of:

- providing a wire spoke vehicular wheel rim;
- providing a felly for said wheel rim and having walls defining spaced bores extending circumferentially therearound;
- providing solid spokes having radially outer ends;
- securing said spoke outer ends within said felly bores by:
 - inserting a spoke outer end partially within a felly bore, thereby leaving a cavity defined by said felly bore atop said spoke outer end with said spoke outer end providing a substantially closed bottom wall of said cavity;
 - feeding a welding wire into said cavity under wire melting conditions;
 - substantially filling said cavity with melted welding wire but not overfilling said cavity;
 - producing a weld formation extending transversely across said spoke outer end;
 - fusing said spoke outer end to said melted welding wire which is fused to the felly bore wall; and
- assembling the wheel rim and felly-spoke assembly.

4,294,394

METHOD OF AND APPARATUS FOR CONTINUOUSLY ROLLING STEEL SLABS

Yoshihiko Iida, and Toshiyuki Kajiura, both of Hitachi, Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed Aug. 6, 1979, Ser. No. 63,776

Claims priority, application Japan, Aug. 7, 1978, 53-95479

Int. Cl.³ B23K 37/04; B21B 1/04

U.S. Cl. 228—158

13 Claims



1. In a process for producing strip by a continuous hot rolling of slab steel including the steps of welding a piece of slab at its leading end to the trailing end of a steel slab while transferring said steel slab by making said piece of slab follow said steel slab, moving said steel slab including successive steel slab pieces welded together in series through a heating furnace to heat said steel slab, and effecting hot rolling of a steel slab by passing said steel slab through a rolling mill to produce a strip; wherein the improvement resides in that said step of welding is made at the boundary surface between the trailing end of said steel slab and said piece of slab which is positioned in abutment at its leading end with said trailing end of said steel slab, over an area which amounts to 1/20 to 1/4 of the whole area of said boundary surface, and in the further step of shearing said roller strip at said areas of welding after said step of hot rolling.

4,294,395

BRAZING PROCESS


Harbhajan S. Nayar, Murray Hill, N.J., assignor to Airco, Inc., Montvale, N.J.

Filed Mar. 23, 1979, Ser. No. 23,377

Int. Cl.³ B23K 1/04

U.S. Cl. 228—220

15 Claims



1. A process for copper brazing ferrous parts in a continuous furnace comprising the steps of: heating said furnace to establish a region therein at a temperature of at least 600° C.; establishing an atmosphere in said region under equilibrium conditions in the absence of parts comprised of at least 90% nitrogen, at total of about 1.0 to 7.0% hydrogen and carbon monoxide, wherein the concentration of hydrogen is greater than the concentration of carbon monoxide, and moisture sufficient to provide a dew point of about -40° C. to +10° C.; and passing through said furnace said ferrous parts having thereon a brazing paste comprised of a copper paste and 25-75% of a copper oxide paste whereby said parts are brazed.

4,294,396

METHOD FOR MANUFACTURING BRAZED PARTS

Toshiharu Obata; Toshimasa Hagyu, and Hisao Kojima, all of Kawasaki, Japan, assignors to Fuji Electric Co., Ltd., Kawasaki, Japan


Filed Jul. 23, 1979, Ser. No. 59,840

Claims priority, application Japan, Jul. 21, 1978, 53-89257

Int. Cl.³ B23K 1/12

U.S. Cl. 228—245

5 Claims



1. In a method for manufacturing brazed parts made by brazing a metal part with a base material made of a plate metal, the improvement comprising the steps of: stamping out said base material to form a through-hole in said base material, stamping out said filler material and urging said filler material into said through-hole formed in said base material and held protruding outwardly therefrom, placing said metal part on said filler material and, brazing said metal part to said base material through said filler material.

4,294,397

CARTON WITH SELF ERECTING PARTITIONS


Karl A. Kohler, Roselle, Ill., assignor to Container Corporation of America, Chicago, Ill.

Filed Jul. 15, 1980, Ser. No. 169,192

Int. Cl.³ B65D 5/48

U.S. Cl. 229—27

2 Claims



1. In a folding carton, formed from a unitary blank of foldable paperboard, including automatically self-erecting internal longitudinal and transverse partition structures, the combination of:

- opposed pairs of major and minor side wall panels foldably joined to each other along parallel fold lines to form a tubular structure open at the ends;
- opposed pairs of major and minor end closure panels foldably joined to opposite ends of respective major and minor side wall panels, respectively, and adapted to be secured to each other in overlapped relation to close the ends of said carton;
- an internal longitudinal partition member including:
 - a first element secured to and extending between and normal to opposed major side wall panels and disposed parallel to but spaced inwardly from one of said minor side wall panels;
 - a second element, having a width greater than that of

said first element, secured at one side to one of said major side wall panels in alignment with said first element, and having its other side extending diagonally toward the junction of said other major side wall panel and said one minor side wall panel and being free from attachment to any of said panels;

- an internal transverse partition member being:
 - foldably joined at one end to an edge of said longitudinal element member first element at a location between the ends of said carton and extending transversely from said first element toward said one minor side wall panel between said longitudinal partition member first and second elements;
 - supported by an end edge of said longitudinal member second element.

4,294,398

PARTITION FOR CARRIER CARTON


Francis A. Chidsey, Jr., Devon, Pa., assignor to Container Corporation of America, Chicago, Ill.

Filed Jan. 22, 1981, Ser. No. 227,542

Int. Cl.³ B65D 5/48; 71/00, 25/04

U.S. Cl. 229—15

1 Claim



1. In a partition arrangement for separating corresponding areas of adjacent packaged articles, such as bottles, arranged in three side-by-side rows, a pair of partitions, each being formed of a unitary blank of paperboard or the like which is cut and scored to provide:

- a plurality of alternately disposed longitudinal members, for interposition between adjacent articles of separate rows, and transverse members, for interposition between adjacent articles of the same row;
- each of said members having a relatively narrow main section, extending the entire height thereof, and separator elements projecting laterally outward from opposite sides thereof;
- said transverse member each having a pair of separator elements extending from one side of said main section toward upper end, center, and lower end areas of the articles and another pair of separator elements extending from the other side of said main section toward center and one of the end areas of the articles, so that when said partition is used with a similar partition, disposed in an inverted position, the elements extending from said other side of said partition main sections cooperate to prevent contact between corresponding areas of adjacent articles of the center row, at the center and both the upper and lower end areas of said partitions.

4,294,399

FOLDING BOX

Oskar Wilfer, Grünbach, Fed. Rep. of Germany, assignor to H. F. & Ph. F. Reemtsma, Hamburg, Fed. Rep. of Germany

Filed Sep. 21, 1979, Ser. No. 78,585

Claims priority, application Fed. Rep. of Germany, Sep. 22, 1978, 2841257; Apr. 6, 1979, 2913891


Int. Cl.³ B65D 5/66

U.S. Cl. 229—44 CB

2 Claims

1. A unitary folding box for cigarettes and smoking articles comprising a single blank having a front wall, a rear wall, a pair of side walls, an upper wall, a bottom wall, and a cap

formed from a portion of said front, side and upper walls which pivots about an axis in the plane of a wall in opening and closing; complementary locking means formed from a portion of said walls, said locking means having rotating locking means



and stationary locking means, one of which is associated with said cap and the other of which is associated with said box, both said rotating locking means and said stationary locking means lying in the same plane as said wall portions from which they are formed.

4,294,400

NON-GUSSETED EXPANSIBLE ENVELOPE


Wilfred H. Gendron, Wilbraham, Mass., assignor to Westvaco Corporation, New York, N.Y.

Filed Apr. 17, 1980, Ser. No. 141,052

Int. Cl.³ B65D 27/00, 30/20; B31B 1/48, 1/62

U.S. Cl. 229—68 R

6 Claims



1. A non-gusseted expansible envelope comprising a one piece blank including a substantially rectangular rear panel, a front panel foldably attached thereto along a transverse fold line, a closure flap foldably attached to the front panel along another transverse fold line and two pairs of equally sized and shaped side seam flaps foldably attached respectively to the side edges of the front and rear panels along a pair of longitudinal fold lines, the improvement wherein the side seam flaps attached to the side edges of the front panels are each applied with longitudinal perforated lines which substantially bisect the flaps to form outer portions for the application of adhesive and to provide hinge connections which enable the side seam flaps to be folded inwardly upon themselves when the envelope is expanded.

4,294,401

DRAFT CONTROL ARRANGEMENT



Werner Diermayer, 1275 Panorama Dr., Lafayette, Calif. 94549;
Luitpold Kutzner, Marschnerstrasse 78, D-8000 Munich, and
Erwin Postenreider, Postfach 240, D-8031 Grobenzell, both
of Fed. Rep. of Germany

Continuation of Ser. No. 831,547, Sep. 8, 1977, abandoned. This
application Apr. 9, 1979, Ser. No. 28,718

Int. Cl.³ G05D 23/08

U.S. Cl. 236-1 G

4 Claims



1. In a gas-fired heating apparatus having a draft hood for directing a flow of waste gas to a vent, a throttling device comprising the combination of main flow control means for sensing temperature of the gas within the hood and responding to said temperature for reducing or enlarging the cross-sectional throttle area for directing gas to the vent, said main flow control means including bimetal element means shaped to project across said throttle area and changing shape at a first rate responsive to temperature change for reducing or enlarging the throttle area, and secondary bimetal element means which changes shape, at a rate which differs from the first rate, responsive to gas temperature for causing the rate of throttle area change for unit change in temperature during one phase of operation to vary from the rate of throttle area change for unit change in temperature during another phase.

4. In a gas-fired heating apparatus having a draft hood for directing a flow of waste gas to a vent, a throttling device comprising the combination of main flow control means for sensing temperature of the gas within the hood and responding to said temperature for reducing or enlarging the cross-sectional throttle area for directing gas to the vent, said main flow control means including bimetal element means shaped to project across said throttle area and changing shape responsive to temperature change for reducing or enlarging the throttle area, and secondary control means for causing the rate of throttle area change for unit change in temperature during one phase of operation to vary from the rate of throttle area change for unit change in temperature during another phase, said secondary control means including means forming an opening in the first-mentioned bimetal element means, together with secondary bimetal element means carried by the first element and extending across the opening for reducing or enlarging the flow area therethrough responsive to gas temperature for causing a high rate of throttle area change for unit change in gas temperature during said one phase.

4,294,402

CONTROL DEVICES FOR HEATERS

Rudolf Vollmer, Mosbach, Fed. Rep. of Germany, assignor to
Honeywell Inc., Minneapolis, Minn.


Filed Oct. 23, 1978, Ser. No. 953,453

Claims priority, application Fed. Rep. of Germany, Oct. 26,
1977, 2747969

Int. Cl.³ G09D 23/13

U.S. Cl. 236-12 R

13 Claims



1. A control device for a heating installation including one individually temperature controlled radiator means, first means for passing a heating medium to the heating installation and second means for returning the heating medium from the heating installation to mix with said heating medium passing into said heating installation, moveable means in said first and second means and control means actuable in response to the temperature of said heating medium and returning heating medium, said control means operating on said moveable means to vary inversely the flow of said heating medium as compared to the returning heating medium to maintain a pre-determined temperature drop between the heating medium passing to said radiator means and returning therefrom, said control means including a first thermostatic working element having a sensor for determining the temperature of the heating medium being passed to the heating installation and a second thermostatic working element having a sensor for determining the temperature of the heating medium being returned from said heating installation.

4,294,403

SYSTEM AND METHOD FOR CONTROLLING THE CONDITIONING AND DELIVERY OF AIR TO A CONDITIONED SPACE

Staron E. Ammons, P.O. Box 17128, Dallas, Tex. 75217; Edwin
L. Paschall, P.O. Box 35226, Dallas, Tex. 75235, and Morris
G. Carter, P.O. Box 17128, Dallas, Tex. 75217

Continuation-in-part of Ser. No. 958,961, Nov. 9, 1978,
abandoned. This application Jul. 21, 1980, Ser. No. 170,996

Int. Cl.³ G05D 23/13


U.S. Cl. 236-13

19 Claims

1. A system for controlling the conditioning and delivery of air to a conditioned space comprising
a cool air duct for connection to a cool air supply duct;
a warm air duct for communication with a return plenum;
a delivery duct connected to both said cool air and warm air ducts for delivering air to the conditioned space;
a thermostat control device for providing a varying control signal related to the varying temperature of the air in the conditioned space;
coupled discharge damper means for said cool air duct and said warm air duct, shiftable between a first condition wherein said cool air duct is open and said warm air duct

is closed, and a second condition wherein said cool air duct is closed and said warm air duct is open;
a fan disposed in said warm air duct for effecting air flow from the return plenum to said delivery duct;
a variable flow control device disposed in said cool air duct for varying the air flow therein between maximum and minimum flow conditions;
first actuator means responsive to said thermostat signal for controlling said variable flow control device;
second actuator means responsive to said thermostat signal for controlling said discharge damper means and said fan;
said second actuator means being operative in one condition to start said fan simultaneously with the opening of said warm air duct discharge damper means; and being operative in another condition to stop said fan simultaneously with the closing of said warm air duct discharge damper means.

10. A system for controlling the conditioning and delivery of air to a conditioned space comprising
a cool air duct for connection to a cool air supply duct;
a warm air duct for communication with a return plenum;



a delivery duct connected to both said cool air and warm air ducts for delivering air to the conditioned space;
a thermostat control device for providing a varying control signal related to the varying temperature of the air in the conditioned space;
damper means for said warm air duct for allowing air flow from the return plenum to said delivery duct and for preventing reverse flow therein;
a fan disposed in said warm air duct for effecting air flow from the return plenum to said delivery duct;
variable flow control damper means disposed in said cool air duct for varying the air flow therein between maximum flow and no flow conditions;
first actuator means responsive to said thermostat signal for controlling said variable flow control damper means;
second actuator means responsive to said thermostat signal for controlling said damper means and said fan;
said second actuator means being operative in one condition to start said fan simultaneously with the closing of said cold air duct damper means; and being operative in another condition to stop said fan simultaneously with the opening of said cold air duct damper means.

4,294,404

ENVIRONMENTAL CONTROL SYSTEM

Jagdishchandra T. Gajjar, Clifton Park, N.Y., assignor to Integrated Energy Systems, Schenectady, N.Y.

Filed Feb. 14, 1978, Ser. No. 877,682


Int. Cl.³ F24F 7/00

U.S. Cl. 236-49

18 Claims

1. An environmental control system for a structure having a plurality of rooms and means for modifying an environmental parameter within said structure comprising:
an occupancy sensor in each room of at least two rooms of said plurality of rooms providing exclusively a first output

signal when said room is occupied and a second output signal when said room is unoccupied;
a second sensor in each room of at least two rooms of said plurality of rooms for providing an output signal responsive to the level of said environmental parameter in said room;
control means for receiving the output signals of each and every of said occupancy sensors and said second sensors and for controlling said means for modifying responsively to a composite function of said output signals of said occupancy sensors and said sensors; and



wherein said control means more particularly includes means for receiving the output signals of said occupancy sensors and said second sensors and for providing a control output signal, said control output signal being a composite function of said output signals of said occupancy sensor and said second sensor; and
means for receiving said control output signal and controlling said means for modifying responsively to said control output signal; and
wherein further said environmental parameter is temperature, and said means for modifying comprises an energy conversion unit and means for conveying a fluid from said energy conversion unit to said rooms.

4,294,405

TRACTION BAG


Lawrence M. Ross, 5840 Highway V, Racine County, Caledonia,
Wis. 53108

Filed Mar. 3, 1980, Ser. No. 126,335

Int. Cl.³ E01B 23/00

U.S. Cl. 238-14

1 Claim




1. A reusable traction device for automobile tires comprising a bag made of flexible material, filled with fine aggregate, said filled bag being sufficiently flexible so that it will tend to conform to a tread pattern when in use, the bag having a plurality of rows of fingerlike compartments on one end, the number of compartments per row decreasing with distance from the end of the bag so that the filled bag has a wedge shaped cross section, the wedge shape of the bag tending to prevent the bag from sliding under the tire without moving the automobile.

4,294,406

PROGRAM CONTROLLABLE FREE FALLING WATER DROP FOUNTAIN

Stephen H. Pevnick, 2314 E. Wyoming, Milwaukee, Wis. 53202
 Filed Nov. 14, 1978, Ser. No. 960,621
 Int. Cl.³ B05B 17/08; F21P 7/00
 U.S. Cl. 239—20

13 Claims



1. A free falling water droplet fountain comprising a manifold having a series of openings, means for independently controlling the size and rate of release of water droplets from said openings, said controlling means including a plurality of valve assemblies for defining the form and size of said water droplets, said controlling means including timing means connected to said valve assemblies to selectively control the length of time of opening to form the water droplets and the time of initiation of each of the valve assemblies to release the droplets at programmed intervals whereby a constant or asymmetrical frequency can be provided for the initialization of release of water droplets from the openings and a constant or asymmetrical size of water droplet can be provided within said frequency.

4,294,407


ATOMIZER FOR FLUIDS, PREFERABLY AN INHALATION DEVICE

Ernst Reichl, Munich, and Herbert Marloth, Siegersbrunn, both of Fed. Rep. of Germany, assignors to Bosch-Siemens Hausgeräte GmbH, Stuttgart, Fed. Rep. of Germany
 Filed Dec. 17, 1979, Ser. No. 104,581
 Claims priority, application Fed. Rep. of Germany, Dec. 19, 1978, 2854841

Int. Cl.³ A61M 11/00

U.S. Cl. 239—102

9 Claims



1. Atomizer for fluid, comprising an atomizer housing, a unitary fluid container removably inserted in said housing, an

atomizing element activatable by ultrasonic flexural vibrations being disposed in said housing, manually operable means integral with said fluid container for transporting the fluid from said fluid container to said atomizing element, and manually activatable means for operating said transporting means and atomizing element.


4,294,408

IN CENTRIFUGAL SPRAY GUNS

Irving F. Snyder, and Duane A. Luebeck, both of Blaine, Minn., assignors to Graco Inc., Minneapolis, Minn.
 Filed May 8, 1980, Ser. No. 148,135
 Int. Cl.³ B05B 3/08

U.S. Cl. 239—218.5

11 Claims



1. An apparatus for spraying liquid by centrifugal atomization of liquid pumped from a container to the surface of a high speed spinning disk, comprising

- (a) a drive motor mounted on a vertical axis and having a downwardly projecting motor shaft;
- (b) a circular disk and helical screw pump attached to said motor shaft in axial alignment, the upper end of said screw pump forming a frusto conical valve member;
- (c) a hollow tube surrounding said screw pump and extending into said container, said tube having a telescoping upper portion and a lower portion which is seatable against said valve member;
- (d) means for axially fixing said tube upper portion relative to said disk; and
- (e) means for axially varying said disk, said tube upper portion and said valve member relative to said tube lower portion.


4,294,409

SHOWER HEAD AND VALVE ASSEMBLY FOR CAMPING SHOWER

Charles H. Larsen, 901 Date St., Rawlins, Wyo. 82301
 Continuation of Ser. No. 713,714, Aug. 12, 1976, Pat. No. 4,151,616. This application Apr. 25, 1979, Ser. No. 33,035
 Int. Cl.³ B05B 1/30

U.S. Cl. 239—577

18 Claims



1. In a portable shower, a shower head and valve apparatus, comprising:

- a housing with an upper body portion and a lower body portion enclosing a chamber in the space between said upper and lower body portions, said upper and lower body portions each having a hole from the exterior to the

interior of said chamber, the hole in said upper body portion being axially aligned with the hole in said lower body portion, and a portion of the hole in said upper body portion having a progressively decreasing diameter defining a hole portion with upwardly converging sidewalls, a valve stem member slidably extending through the hole in said lower body member and extending upwardly through said chamber and into said hole portion of said upper body portion, said valve stem including sealing means at its upper end, closing means normally urging said sealing means into sealing contact with said converging hole portion, and limit stop means on said valve stem operative to retain said valve in an open position and resist the urging of said closing means, and said lower body portion including ports extending from the internal surface of said lower body portion to the external surface such that when said valve stem is moved downwardly allowing water to flow into said chamber through the opening between said converging sidewalls and said sealing means, said ports conduct the water in droplet form from said chamber to the underside of said shower head and valve apparatus for release in the form of a shower.

4,294,411


ELECTROSTATIC SPRAY GUN

Donald R. Hastings, Elyria, and Martin J. Harjar, Vermilion, both of Ohio, assignors to Nordson Corporation, Amherst, Ohio

Filed Jul. 5, 1979, Ser. No. 55,020
 Int. Cl.³ B05B 5/02

U.S. Cl. 239—707

20 Claims



1. An electrostatic spray gun comprising:
 a substantially electrically non-conductive barrel having a fluid conduit therein adapted to be connected to a source of fluid coating material under pressure, and an air conduit,
 a nozzle made from a substantially non-conductive material on the forward end of said barrel, said nozzle having a fluid discharge opening effective to project coating material therefrom, fluid valve means for controlling the flow of coating material through said discharge opening, and an air opening communicating with said air conduit for dispensing air effective to atomize said coating material issuing from said discharge opening,
 charging means for imparting an electrical charge to said coating material,
 a removable air valve module mounted to and externally of the rear end of said barrel including an air valve and movable valve closure means for selectively opening and closing said air valve to selectively supply said air conduit with atomizing air,
 a relatively thin-walled handle shell attached to the rear end of said barrel, said handle shell surrounding said rear end of said barrel and said air valve module without said air valve module being physically supported by said handle shell permitting ready access to said air valve module by removing said handle shell, and
 means for moving said movable valve closure means for selectively opening and closing said air valve and for opening said fluid valve means on opening of said air valve and closing said fluid valve means before closing of said air valve.

4,294,410

CLOSING DEVICE, WITH A TILTABLE NOZZLE, FOR A PRESSURIZED CONTAINER


Jean-Louis Gueret, Paris, France, assignor to L'Oreal, Paris, France

Filed Jan. 22, 1980, Ser. No. 114,260

Claims priority, application France, Feb. 28, 1979, 79 05192
 Int. Cl.³ B65D 83/14

U.S. Cl. 239—577

13 Claims



1. A closing device intended to be fixed to a container neck, such closing device consisting of a dispensing cap made of an elastically deformable material; said dispensing cap comprising:

- (a) a fixed part;
- (b) a movable part;
- (c) means on said fixed part effective to fasten said fixed part to a said container neck;
- (d) deformable wall means connecting said movable part swingably to said fixed part;
- (e) means on said movable part defining a discharge orifice whereby said movable part constitutes a dispensing nozzle projecting outside the container;
- (f) two ends to said dispensing cap;
- (g) means defining an axial channel connecting that end of the dispensing cap which is intended to face the internal volume of the container with said discharge orifice means;
- (h) obturator means consisting of an elongate body of an elastically deformable material;
- (i) means fixing one of the ends of said obturator body to at least one of said fixed part of the dispensing cap and said neck of the container; and
- (j) means defining an externally concave intermediate zone of said obturator body between the ends thereof; wherein said deformable wall means joining the dispensing

4,294,412


METHOD AND APPARATUS FOR CONTROLLING WOOD PULP GRINDING MACHINES

Karl G. Bohlin, Sundsvall; Borje I. Fredriksson, Matfors; Kent A. B. Karlsson, and Lars T. Nelvig, both of Sundsvall, all of Sweden, assignors to SCA Development Aktiebolag, Sweden
Continuation-in-part of Ser. No. 864,231, Dec. 27, 1977, abandoned. This application Sep. 27, 1979, Ser. No. 79,486
Claims priority, application Sweden, Dec. 27, 1976, 7614558; Dec. 27, 1976, 7614559

Int. Cl.³ B02C 25/00

U.S. Cl. 241—30

28 Claims



1. A method of controlling the operation of a wood pulp grinding machine of the type which has at least two pockets per grindstone and two grindstones coupled by way of a common shaft to a single drive motor, comprising the steps of:

- (i) simultaneously measuring the power of the motor and the feed rates of the pockets;
- (ii) repeating step (i) after a predetermined time interval during which the operating conditions of the machine change as a result of the operation thereof;
- (iii) calculating the degrees of sharpness of the grindstones using the power and feed rate values measured in steps (i) and (ii); and
- (iv) dressing each grindstone when its calculated degree of sharpness reaches a determined value.

4,294,413


APPARATUS FOR THE BREAKING OF HETEROGENEOUS MATERIALS, AS CITY SOLID WASTES

Manlio Cerroni, Via Bruxelles 53, Roma, Italy
Filed Jul. 25, 1979, Ser. No. 60,322

Int. Cl.³ B02C 1/00

U.S. Cl. 241—36

7 Claims



1. An apparatus for the breaking of heterogeneous materials, in particular city solid wastes in which the waste material (26)

to the treated is conveyed by an endless belt conveyor (27) travelling at a constant speed, characterized by the fact that the apparatus comprises a first primary working system forming a working unit, including a rigid system of blades (15) and counterblades (8) respectively alternately juxtaposed to each other and mounted so as to rotate about a common axis and controlled in both their opening and closure directions by a guiding rod system forming an articulated quadrilateral system (13, 14, 18), pivotally connected to driving means (10), adapted to cause the articulated rod system to perform each operative stroke at a speed higher than that of the travel of the material (26) on the belt carried by the belt conveyor (27), while a return or closing stroke of the blades (15) and counterblades (8) is performed out of the contact of the waste material (26), owing to a displacement movement transmitted to the first primary system by an auxiliary system, including hydraulic driving means (4), further including means for performing the return stroke immediately, as the counterblades and blades (8 and 15) encounter a resistance higher than a predetermined value.

4,294,414


FEED ROLL DEVICE FOR SHEET GRANULATOR

Roy W. Gerstenberg, Norfolk, Mass., assignor to Leesona Corporation, Warwick, R.I.
Filed Jan. 14, 1980, Ser. No. 112,075

Int. Cl.³ B02C 18/22, 18/44

U.S. Cl. 241—222

6 Claims



1. In combination with a granulator for size reduction of plastic sheet material, a feeding device for feeding such sheet material thereto, said granulator including walls defining a generally enclosed chamber, a rotor mounted for rotation about an axis within said chamber, cutting means affixed on said rotor, bed knife means mounted for projection into said chamber for cooperative cutting relationship with said rotor cutting means as said rotor is driven, said feeding device comprising first and second longitudinally oriented, generally cylindrical feed rolls coaxially mounted with respect to each other so as to form a longitudinally directed nip for receipt of a minimum thickness of at least a single material sheet therebetween and a maximum thickness of a plurality of said sheets, means for continuously rotating said rolls in opposite rotational directions, means for positioning said rolls in spaced relation with each other and means for directing said sheet material to said nip whereby said rolls feed said material to said chamber for granulation therein, the outer surface of both said rolls having a plurality of radial grooves inwardly extending a distance slightly greater than said maximum material thickness, said grooves longitudinally spaced from each other along each said rolls so as to form a plurality of spaced ridges adjacent said grooves, said rolls longitudinally positioned with respect to each other so that the ridges of said first roll and the grooves of said second roll and vice versa are aligned for respective interdigitation with each other such that said sheet material passing through said nip is forced into a sinuous cross-sectional configuration by said interdigitation of said rolls and whereby opposite surfaces portion of said sheet material are contacted by respective roll surfaces at different surface velocities.

4,294,415

CUTTER KNIFE

Manfred Wetter, Biedenkopf-Breidenstein, and Karl H. Schmidt, Steffenberg-Quotshausen, both of Fed. Rep. of Germany, assignors to Kraemer & Grebe GmbH & Co. KG Maschinen- und Modellfabrik, Biedenkopf-Wallau, Fed. Rep. of Germany


Filed Aug. 9, 1979, Ser. No. 65,038

Claims priority, application Fed. Rep. of Germany, Aug. 22, 1978, 2836630

Int. Cl.³ B02C 18/18

U.S. Cl. 241—292

12 Claims



1. In a cutter knife having a knife blade and an opening for receiving a cutter spindle therein, which opening is constructed in the shape of a polygon and having a stop key means for said cutter spindle in a side of said opening which is opposite said knife blade, the improvement comprising at least one balancing disk having an opening therein for receiving said cutter spindle therein and being secured on said cutter knife in the region of said opening for said cutter spindle, the shape, weight and mounting of which are chosen such that the center of gravity of the totality of said cutter knife and balancing disk lies on the axis of said cutter spindle to thereby statically balance said cutter knife, said cutter knife further including dynamic balancing means for facilitating a dynamic balancing of said cutter knife.

4,294,416

CONTROLLED MULTIPACKAGE WINDING

John T. Beckman, Granville, Ohio, assignor to Owens-Corning Fibreglas Corporation, Toledo, Ohio

Filed Mar. 19, 1980, Ser. No. 132,473

Int. Cl.³ B65H 54/08, 54/30


U.S. Cl. 242—18 G

18 Claims

1. A method of controlling the simultaneous winding of linear elements into more than one package, said method comprising:

- (a) supplying at least two linear elements;
- (b) engaging said elements in a guide means;
- (c) forming said elements into at least a first and second package;
- (d) sensing when said first package is a predetermined size;
- (e) sensing when said second package is a predetermined size;
- (f) determining when a predetermined period of time has elapsed after one of said packages has been sensed; and

(g) increasing the distance between said packages and said guide means when either said first and second packages



have been sensed or said predetermined period of time has elapsed.

4,294,417

STATIC WIRE TENSIONER FOR COIL WINDING MACHINES


Giuseppe Camardella, Saronno, Italy, assignor to Tekma Kinomat S.p.A., Caronno Pertusella, Italy

Filed Nov. 20, 1979, Ser. No. 95,940

Claims priority, application Italy, Nov. 24, 1978, 30141 A/78
Int. Cl.³ B65H 59/22

U.S. Cl. 242—149

9 Claims



1. In a winding machine for winding coils of metallic wire for electrical or electronic use, a static wire tensioning device comprising a first friction shoe mounted fixedly on a first bearing arm, a second friction shoe, a second bearing arm, means mounting said second friction shoe on said second bearing arm for freely oscillating around an axis perpendicular to the sliding direction of the wire, means for mounting said two bearing arms rotatable one with respect to the other about an axis parallel to the sliding direction of the wire and for finely adjusting the mutual distance of said bearing arms at a distance from the friction shoe, and spring means acting on said arms for pushing said friction shoes one toward the other with finely adjusted force.

4,294,418

TAPE CARTRIDGE

Peter L. Gell, Redfern, Australia, assignor to Tuscan Industries Pty. Limited, Redfern, Australia


Filed Mar. 22, 1979, Ser. No. 22,946

Claims priority, application Australia, Mar. 29, 1978, PD3805
Int. Cl.³ G03B 1/04; G11B 15/32

U.S. Cl. 242—197

5 Claims

U.S. Cl. 244—117 R



1. A cartridge to house a rotatable tape spool, said cartridge comprising a first part and a second part, each part including a rectangular panel of resilient material with upstanding flanges at the first and fourth edges of the respective panels, releasable coupling means on said first and second parts, alignment means to align corresponding flanges of the first and second parts and align said releasable coupling means to couple the first and second parts together to form a closed cartridge with an interior spool chamber to house a spool, a primary access opening comprising aligned gaps in corresponding first flanges at the first edges of the panels, a secondary access opening comprising aligned further gaps in said first flanges which further gaps provide extensions of aligned gaps in second flanges at second edges of said panels, arcuate upstanding walls on each panel to define said spool chamber and position said spool for rotation in the chamber, the upstanding arcuate walls and the flanges on the corresponding first, second, third and fourth edges of the panels substantially preventing flexure of the panel at those edges except in the panels adjacent the gaps of the primary access opening in the first flanges so as to permit flexure of the panels adjacent the gaps of the primary access opening, said releasable coupling means comprising complementarily toothed upstanding lug means and surface means respectively at the third edges of the first and second panels which third edges lie opposite the first edges thereof, and a rigid upstanding first leg at the first edge of the panel having said lug means, the first leg at the first edge being disposed between the primary access opening and the secondary access opening in the second flange, and a rigid upstanding second leg at the fourth edge of the panel having said lug means, the second leg lying adjacent the first panel edge, shoulder means on the second leg, a rigid upstanding tongue at the fourth edge of the panel not having the lug means, the tongue engaging in a notch in the corresponding flange of the panel having the lug means so as to align the first and second parts, an aperture in the tongue engageable by the shoulder means of the second leg to releasably secure the parts together, said shoulder means being engageable in said aperture as a result of flexure of the first edges of the panels adjacent the primary access opening to convex and concave configuration to make the second leg lie inwardly of the flange of the fourth edge of the panel having the lugs and to make the tongue lie outwardly of the second leg, and an opening in one panel to permit driving engagement of driving means with a spool when housed in said chamber.

4,294,419

AIRFRAME ASSEMBLY AND PROCESS


Jack A. Fouse, Dallas, and Sherwood W. McClaren, III, Grand Prairie, both of Tex., assignors to Vought Corporation, Dallas, Tex.

Filed Jan. 22, 1979, Ser. No. 4,965

Int. Cl.³ B64C 1/00; B23K 20/22

U.S. Cl. 244—117 R

9 Claims



1. The method of assembling a portion of an airframe having a minimum radar cross section comprising the steps of:
 - (a) diffusion bonding the periphery of a preform capable of being superplastically formed and diffusion bonded onto the outer surface of a substantially cylindrical casing,
 - (b) placing said cylindrical casing in a mold having a cavity therein substantially conforming to the external dimension of a structural air duct, said cavity enclosing said preform and said mold supporting a wing structure with the wing root face forming a portion of said cavity, and
 - (c) heating said preform to a superplastic forming and diffusion bonding temperature and applying sufficient pressure across said preform to superplastically deform said preform to conform to the dimensions of said mold and diffusion bond said deformed preform to said wing root face.
2. The product made by the method of claim 1.

4,294,420


ATTITUDE CONTROL SYSTEMS FOR SPACE VEHICLES
Jean B. Broquet, Saint Cyr l'Ecole, France, assignor to Matra, Paris, France

Filed Jan. 30, 1978, Ser. No. 873,684

Int. Cl.³ B64G 1/20

U.S. Cl. 244—165

14 Claims



1. An attitude control system for a body-stabilized space vehicle designed for travelling in an orbit and having roll, pitch and yaw axes, comprising: a plurality of sensors carried by the vehicle for sensing angular deviations about at least two of said axes, an actuator including only two wheels rotatable about respective non-aligned spin axes fixed with respect to said vehicle, electronic control means connected to receive input signals from the sensors and to control the rotation speeds of said two wheels for attitude correction about two orthogonal axes of said vehicle, said actuator permanently having, in operation, a momentum providing a gyroscopic stiffness providing short term stabilization about a third axis orthogonal to said two orthogonal axes, wherein each wheel is operatively associated with a tachometer generator and the electronic control means has means each associated with one of said tachometer generators to compute the angular position

of the momentum of the actuator relative to said axes of the vehicle.

4,294,421

KNIFE HOLDER

Erich Künstlicher, Johan Baners Gata 6, 252 33 Helsingborg, and Harry V. Thomasson, Box 29, 260 33 Paarp, both of Sweden

PCT No. PCT/SE78/00093, § 371 Date Aug. 7, 1979, § 102(e)
Date Aug. 7, 1979, PCT Pub. No. WO79/00376, PCT Pub. Date Jun. 28, 1979


PCT Filed Dec. 11, 1978, Ser. No. 140,387

Claims priority, application Sweden, Dec. 12, 1977, 7714058

Int. Cl.³ A47G 21/14; A47F 7/00

U.S. Cl. 248—37.6

11 Claims



1. A holder for knives and similar flatware, the holder having an elongate base which may be mounted on a surface for example a wall or the like and supports one or more gripping members with which the knives may individually be moved with their blades into and out of retentive engagement, characterized in that each gripping member comprises two rollers in side by side relationship and cooperating with each other, the rollers being at least partially made of an elastomer material and each being mounted on a journal located on the base, the rollers having facing circumferential surfaces which form a nip into and out of which the knife blade may be moved, with the rollers rolling on the two sides of the blade under elastic blade-retentive deformation of the rollers.

4,294,422

GUTTER HANGER


William H. Odekirk, 7446 Gatewood Rd., SW., Seattle, Wash. 98136

Filed Sep. 24, 1979, Ser. No. 78,295

Int. Cl.³ E04D 13/06

U.S. Cl. 248—48.2

8 Claims



1. A hanger for mounting a gutter to a structure with a fastener, comprising:
 - a hanger member extending across the width of said gutter comprising a substantially horizontally disposed bracket arm and a raised fastener guide portion;
 - first means attached to one end of said bracket arm for engaging the outside wall of said gutter; and
 - second means attached to one end of said fastener guide portion for engaging the inside wall of said gutter and for

receiving said fastener to mount said gutter to said structure;
said raised fastener guide portion comprising a first upright section extending upwardly from said bracket arm, a second upright section extending upwardly from said hanger member, a connecting crosspiece between said first upright section and said second connecting crosspiece including a downwardly bent mid-section for engaging and retaining a fastener extending through said fastener guide portion, said upright sections having apertures formed therein for receiving said fastener.

4,294,423

SEALING MEANS FOR GUTTER HANGER FASTENING MEANS


Lacy A. Rowe, 1851 Skycoe Dr., Salem, Va. 24153

Filed Mar. 10, 1980, Ser. No. 128,727

Int. Cl.³ E04D 13/06

U.S. Cl. 248—48.2

3 Claims



1. Gutter wall fastener nail hole sealing means for use with a rain gutter having a rear wall portion adapted to be secured to a fascia board or wall of a building, fastening means for securing the gutter to the building wall, including a headed nail or like headed and sharpened fastening means adapted to be driven through a hole in the rear wall of the gutter and into the fascia board; said sealing means comprising compressible elastomeric material adapted to be compressed about the rear gutter wall nail hole, when the nail is driven through the rear gutter wall into the fascia board whereby the fascia board is protected against deterioration due to leakage of water about the rear gutter wall nail hole, said gutter including a front wall spaced from the rear gutter wall, said front and rear walls having apertures through which said sharpened fastening means is adapted to be driven to secure the gutter to a fascia board; a fastener receiving tube or ferrule interposed between the apertures in said front and rear walls of the gutter, said sealing means comprising a compressible grommet of elastomeric material having a body portion adapted to fit within one end of said fastener receiving tube or ferrule, said grommet body portion having a passage there through coaxial with the outer tube or ferrule when the body of the grommet is inserted therein, through which passage in the body of the grommet said sharpened fastening means is adapted to be driven, compressible means at one end of the grommet projecting beyond the ferrule and extending between the end of the ferrule and the gutter rear wall, said compressible means being adapted to be compressed when the fastener is driven into the fascia board.

4,294,424

SUCTION GRIPPING DEVICE

Jacques Teissier, 18, rue Gustave Flaubert, Rueil-Malmaison, France (92500)

Filed Jul. 16, 1979, Ser. No. 57,634

Claims priority, application France, Jul. 20, 1978, 78 21554

Int. Cl.³ A45D 42/14; F16B 47/00


U.S. Cl. 248—362

6 Claims

1. A gripping device adapted when under reduced pressure

to be brought into close gripping conformity with the surface of an object to be gripped, comprising,

- (a) a ring-shaped body deformable in any direction and having a head portion and a skirt portion, the skirt portion having walls of deformable material defining a hollow interior within the skirt, and defining an open space outside the skirt and within the ring;
- (b) at least one means in the head portion communicating the hollow interior of the skirt with means for withdrawing fluid from the interior and reducing pressure within the interior to below the pressure outside the skirt;
- (c) at least one means in the head portion communicating the open space with means for withdrawing fluid from the



open space and reducing pressure within the space to below the pressure outside the ring when the skirt is in contact with an object to be gripped;

- (d) a plurality of freely movable particles confined within the hollow interior of the skirt portion, and compelled to conform to any deformed configuration thereof adopted under reduced pressure within the interior of the skirt, and within the ring; and
- (e) the body walls of the skirt portion under such reduced pressure and higher external pressure conforming closely to the surface of an object to be gripped, and retaining and fixing the particles in such conformity, thereby firmly gripping the object while such reduced pressure continues.

4,294,425

OVERHEAD BOOKHOLDER


Paul J. Weber, 22 Seneca Rd., Fort Lauderdale, Fla. 33308

Filed Oct. 9, 1979, Ser. No. 82,862

Int. Cl.³ A47B 23/00

U.S. Cl. 248—445

13 Claims



1. In an apparatus for holding a book open above a reader, said apparatus comprising:

- a suspension bar shaped and dimensioned to extend laterally across the cover of an open book and beyond the opposite side edges of said cover;
- means for attaching said suspension bar to an open book to position the suspension bar extending across the cover of the book transverse to the spine of the book and project-

ing laterally past the opposite side edges of the book cover;

- manually yieldable page retainer means operatively coupled to said suspension bar for engagement with the open pages of the book from below to hold the book open;
 - and suspension means operatively coupled to said suspension bar to suspend it from above;
- the improvement wherein said suspension means comprises:
- a flexible hang line having interconnected opposite segments attachable respectively at spaced points to an overhead support to position the middle of the hang line closely above said suspension bar;
 - means for operatively connecting said suspension bar to the middle of the hang line to be suspended from the latter;
 - a pitch bar extending transversely between and operatively connected to said opposite segments of the hang line above said last-mentioned means;
 - a pitch line attached at its upper end to said pitch bar between said opposite segments of the hang line and extending down and laterally outward therefrom;
 - and means attaching the lower end of said pitch line to said suspension bar laterally outward past one side edge of the book cover.

4,294,426

UNIQUE JOINT ESPECIALLY USEFUL WITH JUVENILE FURNITURE AND PLAYTHINGS

Henry Fleischer, 18 Notch Park Rd., Little Falls, N.J. 07424


Division of Ser. No. 758,799, Jan. 12, 1977, Pat. No. 4,160,553.

This application Apr. 2, 1979, Ser. No. 26,419

Int. Cl.³ F16M 13/00

U.S. Cl. 248—561

15 Claims



1. A joint adapted to be used in a child holding, carrying and amusement system, said joint comprising, in combination, an outer sleeve, said outer sleeve including at least two sections an upper section of which includes an upper end having a flared end portion, resilient means disposed within the outer sleeve, and a shock absorbing member employed in conjunction with the resilient means and spaced from the internal walls of said outer sleeve, said shock absorbing member including a lower portion and an upper portion, whereby said upper portion of said shock absorbing member is free to move up and down and from side to side within said outer sleeve, said flared end portion of said outer sleeve permitting increased side-to-side movement of said shock absorbing member, said joint being adapted to be removably connected to and between a child holding device and a support base for said holding device, said resilient means in conjunction with said shock absorbing member providing up and down motion and side-to-side motion with respect to said outer sleeve, further including connecting means for connecting said joint to a child holding device and a support base therefor, said connecting means comprising upper connecting means connected to said upper portion of said resilient means and shock absorbing member for connecting said shock absorbing member to a child holding device, and further including control means for controlling and locking said joint to limit movement, said control means comprising a lift member disposed between the two sections of said outer

sleeve and pivotally connected to said sections, said lift member including handle means disposed externally to said outer sleeve and extending through a slot in one of said sections of said outer sleeve, whereby downwardly applied force on said handle means causes said lift member to separate said two sections of said outer sleeve.

4,294,427

MONO-SEAT GATE VALVE


Eugene J. Cilny, 13418 Lindsay, Cypress, Tex. 77429

Filed Jul. 19, 1979, Ser. No. 59,251

Int. Cl.³ F16K 25/00

U.S. Cl. 251—86

3 Claims



1. A gate valve comprising:

- (a) a valve body formed to define inlet and outlet passages having a common axis, said valve body further defining a transverse axis being substantially normal to said common axis, said valve body defining an annular seat about at least one of said inlet and outlet passages, said seat lying in a plane that is inclined at a first angle with respect to said transverse axis, said seat being formed to define a frusto conical annular sealing surface, said sealing surface being generated about an axis disposed in normal relation to said inclined plane, said body defining first and second cam action surfaces inclined at a second angle with respect to said transverse axis in a direction opposite that of the plane of said valve seat, said cam action surfaces being positioned outside of the flow passage defined by said inlet and outlet passages and respectively above and below said flow passage, and a second body section defining a valve chamber communicating with said inlet and outlet passages;
- (b) a bonnet cooperating with said second body section to further define said valve chamber;
- (c) a closure member, comprising:
 - (1) a hanger forming a front surface defining a plane, said plane inclined at said first angle with respect to a central axis of said hanger, and having a mounting hole there-through normal to said front surface plane, and having a vertically oriented arcuate member positioned on each side of said mounting hole adjacent thereto, said hanger further defining first and second cam action surfaces for engaging respective body first and second cam action surfaces, each of said hanger cam action surfaces inclined at said second angle with respect to said central axis;
 - (2) a valve disc defining a plane and having a mounting shaft formed at the geometric center thereof normal to said valve disc plane, said valve disc being carried and retained solely by said hanger in a spaced relation to

said valve body in a manner to permit limited universal movement of said disc with respect to said hanger about an axis passing through said mounting hole normal to said hanger front surface plane, and positioned so that said disc plane is essentially parallel to said valve seat plane, said valve disc permitted to pivot about said mounting hole axis sufficiently to engage said valve seat and effect a uniform seal therebetween to preclude fluid flow through said passage; and

- (3) a valve stem having an axis coincident with said valve body transverse axis, said stem extending through said bonnet and valve chamber and carrying said hanger by a means permitting limited movement of said hanger with respect to said stem in a plane normal to said stem axis, said stem threadedly engaging said bonnet for raising and lowering said hanger and said valve disc with respect to said body flow passage;
 - (d) an annular seal positioned within said bonnet and about said stem for precluding the escape of medium fluid therebetween; and
 - (e) a back seal formed by said stem and said bonnet when said stem is in its uppermost position for sealing said valve chamber to permit said annular seal to be removed and replaced while said valve remains in service,
- whereby lowering said stem and said hanger causes said hanger respective first and second cam action surfaces to engage respective first and second valve body cam action surfaces, thereby causing an axial force along said valve stem to be transmitted through said vertically oriented arcuate members to the geometric center of said valve disc in a direction essentially normal to said valve seat plane for urging said valve disc into sealing engagement with said valve seat to preclude fluid flow through said body flow passage.

4,294,428

BUTTERFLY VALVE

Yoshitsugu Okada, and Osamu Nakai, both of Hirakata, Japan,

assignors to Kubota, Ltd., Osaka, Japan

Continuation of Ser. No. 892,342, Mar. 31, 1978, abandoned.

This application Dec. 3, 1980, Ser. No. 212,465

Claims priority, application Japan, Apr. 1, 1977, 52-37985;

Apr. 1, 1977, 52-41104; Apr. 6, 1977, 52-40205



Int. Cl.³ F16K 31/44, 1/22, 41/02

U.S. Cl. 251—214

7 Claims

1. A butterfly valve comprising a valve housing having spaced bearing portions,
 - a valve stem rotatably supported by said bearing portions said valve stem being axially adjustable in said bearing portions,
 - a tubular bearing member disposed between at least one of said bearing portions and said valve stem,
 - a valve body mounted on said valve stem,
 - a tubular holder member including an elastic seal member having respective upper and lower ring portions retainable in respective annular recesses of the tubular holder member, said elastic seal member including at least one web portion interconnecting said upper and lower ring portions,
 - said upper ring portion contacting the bearing portion and said lower ring portion contacting said valve body, said tubular holder member further contacting one of a plurality of valve seat portions of said valve body,
 - said plurality of valve seat portions attached to said valve housing to contact a periphery of said valve body in a closed position,
 - said elastic seal member fitted exteriorly on said tubular holder member contacting said bearing portions and being rotatable relative to said valve stem,
 - said elastic seal member upper and lower ring portions being

responsive to line fluid pressure for pressing the elastic seal member upper and lower ring portions against a side



wall of said annular recesses when in a closed valve position.

4,294,429

PULLEY ASSEMBLY FOR IMPROVING THE COOPERATION BETWEEN A WINCH AND A CABLE ACTUATED THEREBY


André Desplats, Boulogne Billancourt, France, assignor to Tractel S.A., France

Filed Aug. 13, 1979, Ser. No. 66,276

Claims priority, application France, Aug. 22, 1978, 78 24359
Int. Cl.³ B66D 1/74

U.S. Cl. 254-272

4 Claims



1. A cable hoist apparatus comprising:

- (i) a first pulley for driving in rotation in one direction, said pulley having a peripheral groove of which the cross-sectional shape is without cable-wedging action,
- (ii) a second pulley for driving in rotation at the same velocity in the other direction, said second pulley having a peripheral groove of which the cross-sectional shape provides cable-wedging action.

- (iii) a presser means movable in the same plane towards and away from the peripheral groove of said second pulley,
- (iv) a third pulley having its axis of rotation movable in a common plane of rotation of the three pulleys, said third pulley being coupled to said presser means, and
- (v) a cable which, starting from a load-bearing portion thereof, is passed in said other direction about said third pulley and then in said one direction about said first pulley and then in said other direction about said second pulley, between said second pulley and said presser means, whereby force is exerted by said presser means to urge said cable into the peripheral groove of said second pulley in proportion to tension in the load-bearing portion of the cable tending to move the axis of the third pulley in said common plane.

4,294,430

SUPPORTS


Christiaan L. de Jager, Flat 1, 322 Kingsway, Amanzimtoti, Natal Province, South Africa

Filed Feb. 27, 1980, Ser. No. 125,403

Int. Cl.³ E04H 17/02

U.S. Cl. 256-58

3 Claims



1. A fence wire support, comprising:

- (a) an elongated, substantially planar strap (7) of malleable metal,
- (b) a plurality of closed, elongated slots (6) defined in the strap at spaced locations along its length,
- (c) each slot lying just inwardly of one edge of the strap and oriented substantially parallel thereto to define an integral continuous strip (10) of the support between an outer side (8) of the slot and said one edge of the strap, said strip being frangible and deformable by manually operable tools pursuant to the installation of a fence wire in the slot; and a web of metal (9,11) displaced during the formation of each slot spanning and connected between the opposite ends thereof, each web (11) being bent away from said one edge of the strap to leave its associated slot substantially laterally unobstructed.

4,294,431

METHOD OF PROVIDING AND MAINTAINING A WEAR-LINING OF A STEEL CONVERTER AND A STEEL CONVERTER HAVING SUCH A LINING

Adam Steen, Heemskerk, and Hendrik M. Verhoog, Heemstede, both of Netherlands, assignors to Hoogovens IJmuiden B.V., IJmuiden, Netherlands

Filed Jul. 6, 1979, Ser. No. 55,388

Claims priority, application Netherlands, Jul. 14, 1978, 7807580

Int. Cl.³ C21B 13/00, 15/00

U.S. Cl. 266-44

9 Claims

- 1. In a method of operating a steel converter which has a basic wear-lining formed of refractory material at least partly composed of burnt magnesite, including the step of performing maintenance on the said lining by intermittently spraying refractory material onto the wear-lining and/or slagging-in while the wear-lining is hot, the improvement that the particles of the magnesite component of the wear-lining contain on average more than 6% monticellite.

4,294,432

METHOD AND APPARATUS FOR COOLING BOF HOOD PANELING


Matthew J. Blair, Niles, and Thomas A. Wiktorowski, Parma Heights, both of Ohio, assignors to Republic Steel Corporation, Cleveland, Ohio

Filed Jun. 2, 1980, Ser. No. 155,311

Int. Cl.³ C21B 7/10

U.S. Cl. 266-46

11 Claims



4,294,433

PYROMETALLURGICAL METHOD AND FURNACE FOR PROCESSING HEAVY NONFERROUS METAL RAW MATERIALS


Andrei V. Vanjukov, ulitsa Miklukho-Maklaya, 65, kv. 4, Moscow; Valery V. Mechev, prospekt Lenina, 44a, kv. 49, Norilsk; Valentin P. Bystrov, Schelkovsky proezd, 3, korpus 3, kv. 43, Moscow; Evgeny I. Ezhov, Grazhdansky prospekt, 11, Leningrad; Mikhail G. Vasiliev, prospekt Lenina, 31, kv. 89, Norilsk; Vladimir Y. Zaitsev, ulitsa Lobachevskogo, 6, kv. 34; Vladimir A. Romenets, Lomonosovsky prospekt, 33, korpus 2, kv. 87, both of Moscow; Vladimir V. Ivanov, ulitsa Leningradskaya, 22, kv. 26; Sergei Y. Golik, prospekt Lenina, 13, kv. 87, both of Norilsk; Evgeny S. Grin-Gnatovsky, 2 Schukinsky proezd, 5, kv. 1, Moscow; Alexandr V. Grechko, Vesennaya ulitsa, 4, kv. 42; Ivan V. Savin, ulitsa Vesennaya, 4, kv. 56, both of Ryazan; Sultanbek M. Kozhakhmetov, ulitsa Shevchenko, 32, kv. 16; Veniamin B. Meierovich, ulitsa Auezova, 175b, kv. 29, both of Alma-Ata; Vladimir D. Nagibin, ulitsa Pushkinskaya, 7/5, kv. 6, Moscow; Nariman A. Ramazanov, ulitsa Seifullina, 452/3, kv. 25; Almas B. Umarov, Mikroraiion Koktem - 1, dom 37, kv. 51, both of Alma-Ata; Valentin E. Ziberov, ulitsa Voronezhskaya, 38/43, kv. 309, Moscow; Askar M. Kunaev, ulitsa Vinogradova, 49/130, kv. 23; Saik T. Takezhanov, ulitsa Shevchenko, 44, kv. 3, both of Alma-Ata; Petr A. Alexandrov, ulitsa, Pushkinskaya, 2, Balkhash Dzhetskazganskoi oblasti; Boris I. Kolesnikov, prospekt Lenina, 11, kv. 24, and Dzhonson T. Khagazheev, ulitsa Entuziastov, 53, kv. 93, both of Norilsk, all of U.S.S.R.

Division of Ser. No. 962,603, Nov. 21, 1978, Pat. No. 4,252,560.
This application Jul. 30, 1980, Ser. No. 173,807

Int. Cl.³ F27B 1/20

U.S. Cl. 266-161

13 Claims



1. A furnace for carrying out the pyrometallurgical method for processing heavy nonferrous metal raw materials comprising:

- a shaft, where a charge is fed into a prepared heterogeneous melt composed of slag and matte, charge components being caused to interact with said melt and an oxygen-bearing gas to yield smelting products, said shaft having: having a jacket section in the middle part of said shaft; cooled side tuyeres intended to supply said oxygen-bearing gas into said molten bath and placed at a level dividing said shaft into two vertical parts, or a top and a bottom parts, the ratio of the height of said top part to that of said bottom part ranging from about 2-to-1 to about 10-to-1; a hole for feeding said charge and/or said fuel provided in said top part of the shaft;
- a flue for exhausting said gaseous smelting products placed in said top part of said shaft;
- ducts intended for discharging said slag, said matte and/or said crude metal and arranged in said bottom part of the shaft; and
- a device for discharging said slag from said bottom part of said shaft formed with a separate recipient adjoining said shaft and communicating therewith by means of a duct placed below the level of said tuyeres, but above the level of the matte inside said shaft with the effect that the level of the slag in said recipient determines that of the melt inside said shaft.

- 1. In a method of making steel in a basic oxygen furnace having an oxygen lance and an exhaust hood over the furnace, the steps comprising: providing a plurality of fluid outlet spray nozzles about the oxygen lance at a location adjacent the bottom edge of the exhaust hood when the lance is in an operative position in the furnace, supplying water under pressure to the nozzles, and directing the water outwardly from the lance toward the hood, with spray streams from adjacent nozzles intersecting between the lance and the hood.

4,294,434

HEAVY METAL REMOVAL APPARATUS


Richard G. Durkee, 3616 W. Pendleton, Santa Ana, Calif. 92704

Filed Jan. 24, 1980, Ser. No. 115,039

Int. Cl.³ C22B 15/12

U.S. Cl. 266—170

15 Claims



1. An apparatus for reclaiming heavy metal from heavy metal salts in an aqueous solution, comprising:
 - a. A reaction chamber defining a path for receiving and for conducting said solution therethrough;
 - b. A source of concentrated acid sufficient to impart a pH less than 2 to said aqueous solution wherein said acid in solution has anions;
 - c. First valve means connecting said concentrated acid to said reaction chamber, said valve means operable in response to the pH of said aqueous solution for admitting amounts of said acid into said reaction chamber to maintain the pH of said solution at a predetermined level at least less than 2; and
 - d. Means for retaining, substantially pure aluminum stable in an acid aqueous solution, capable of forming a salt compound with said anions and having a relative electrode potential greater than that of the heavy metal to be reclaimed from the heavy metal salt in solution for precipitating said heavy metal from said heavy metal salt in said solution, said retaining means being positioned in said path in the reaction chamber at a plurality of points along said defined path.

4,294,435

METHOD FOR AGITATION OF MOLTEN METAL AND FURNACE FOR AGITATION OF MOLTEN METAL

Ryohei Matsuno, Tokyo, Japan, assignor to Daido Giken Industries, Co., Ltd. and Amino Aluminium Industries, Co., Ltd., both of Tokyo, Japan


Filed Dec. 19, 1978, Ser. No. 971,044

Claims priority, application Japan, Dec. 26, 1977, 52-155651

Int. Cl.³ H05B 5/12

U.S. Cl. 266—234

1 Claim



1. An agitation melting furnace for molten metal, which comprises a furnace proper made of a refractory material and two sets of electromagnetic-wave devices each formed of a coil and an iron core, one set of electromagnetic-wave devices being disposed to define magnetic fields forming a circle on the

outer surface of the bottom of said furnace, the magnetic fields of said one set of electromagnetic-wave devices being all in one same direction, the other set of electromagnetic-wave devices being disposed within said circle in at least one row, the magnetic fields of said other set of electromagnetic-wave devices in at least one row being all in one same direction.

4,294,436

FURNACE WITH PROTECTIVE ATMOSPHERE FOR HEATING METALS

Susumu Takahashi, Yokohama, Japan, assignor to Kanto Yakin Kogyo Kabushiki Kaisha, Japan


Filed Aug. 29, 1980, Ser. No. 182,774

Claims priority, application Japan, Sep. 5, 1979, 54-112996

Int. Cl.³ C21D 1/06

U.S. Cl. 266—257

3 Claims



1. A furnace having a protective atmosphere therein for heat-treating metallic articles, comprising a heating enclosure having between the sidewalls thereof a space for accommodating said articles to be treated within the furnace, piping means having its discharge communicating with said space for supplying into said enclosure a raw material gas for forming said protective atmosphere, heating elements provided in the said enclosure, and catalytic means extending into the enclosure adjacent to said heating means and operative to react with said raw material gas to convert it into said protective atmosphere, said catalytic means comprising a plurality of spaced, metallic, catalytic elements secured in said enclosure adjacent opposite sides thereof, and with at least certain of said catalyst elements being disposed in spaced relation to said sidewalls of said enclosure.

4,294,437

SLIDE CLOSURE FOR THE POURING NOZZLE OF A MOLTEN METAL VESSEL

Hajimu Sawada, Kawasaki, and Hisao Inubushi, Yokohama, both of Japan, assignors to Nippon Kokan Kabushiki Kaisha, Tokyo; Nippon Rotary Nozzle Co., Ltd., Kawasaki; Kokan Kikai Kogyo Kabushiki Kaisha and Tokyo Yogyo Kabushiki Kaisha, both of Tokyo, all of Japan

Filed Oct. 11, 1979, Ser. No. 83,970

Claims priority, application Japan, Oct. 12, 1978, 53-124654


Int. Cl.³ C21C 5/48

U.S. Cl. 266—272

2 Claims

1. In a slide closure for a molten metal vessel having a pouring nozzle comprising:
 - a fixed plate brick attached to a bottom portion of said vessel and having at least one pouring opening;
 - a sliding plate brick having at least one opening and rotatably pressed against a lower surface of said fixed plate brick whereby rotation of said sliding plate brick brings said opening into or out of alignment with said pouring opening to open or close said pouring nozzle;

a rotor for receiving said sliding plate brick so as to be rotated therewith by a driving source; and supporting means for slidably supporting said rotor and for urging said rotor in a direction to press said sliding plate brick against said fixed plate brick with a bed plate of said vessel serving as a fulcrum; a slide closure for a molten metal vessel having a pouring nozzle characterized in that said supporting means com-



prises a first supporter arranged to surround and slidably support said rotor and including an outwardly projected annular portion, and a second supporter fastened to said vessel bed plate with pins so as to urge said first supporter upwardly or in a direction to press said sliding plate brick against said fixed plate brick with dish spring means being placed between said second supporter and a lower side of the annular projection of said first supporter so as to surround said first supporter.

4,294,438

REPLACEABLE LINER FOR A CRUCIBLE

William A. Nystrom; Leo C. Lanzel, and William A. Bauer, all of St. Marys, Pa., assignors to The Stackpole Corporation, St. Marys, Pa.

Filed Jul. 30, 1980, Ser. No. 173,735

Int. Cl.³ B28B 7/08

U.S. Cl. 266—280

6 Claims

1. A replaceable liner for a crucible for molten metal, the liner consisting of an open-top receptacle having at least its side wall made of graphite foil preformed from compressed expanded graphite.

4,294,439

SPRING SHACKLE


Lester A. McIntosh, deceased, late of Grosse Pointe Shores, Mich. (by Detroit Bank & Trust Co., executor), assignor to McIntosh Corporation, Detroit, Mich.

Filed Apr. 9, 1979, Ser. No. 28,561

Int. Cl.³ F16F 1/26

U.S. Cl. 267—54 A

10 Claims



1. A spring shackle for mounting one end of a suspension spring to a vehicle frame, comprising:
 - a body member;
 - first mounting means integral with one end of said body

member for connecting said shackle to one of said frame or spring; second mounting means integral with the opposite end portion of said body member for connecting said shackle to the other of said frame or spring, said second mounting means comprising an integral extension of said body member curving in helical-like fashion and defining a generally cylindrical bore, said integral extension having an offset portion defining a recess disposed radially outwardly from said bore and a free end portion, said recess terminating axially at points spaced axially inwardly from the ends of said bore, said integral extension tapering to a reduced circumferential thickness at said free end portion thereof, said free end portion being nestingly disposed in said recess whereby the internal wall of said bore is substantially continuous; and an elastomeric bushing press fit into and directly frictionally engaging said bore.

4,294,440

HOLDING DEVICE


Wilhelm Severt, Venn Diek 21, 4426 Vreden, Fed. Rep. of Germany

Filed Oct. 10, 1979, Ser. No. 83,445

Int. Cl.³ B23Q 1/04

U.S. Cl. 269—71

3 Claims



1. A holding device for enabling heavy workpieces of the order of several tons to be oriented without reclamping into any position so that welding seams in the workpiece may be favorably welded horizontally from above, comprising a frame, a first rotary support means mounted on said frame for rotation about a fixed horizontal axis, said first rotary support means comprising a first vertically disposed flange which is rotated about said fixed horizontal axis, a second vertically disposed flange mounted face-to-face on said first flange, mounting means on said first and second flanges for adjusting their relative mounting positions such that said second flange is displaceable relative to said first flange in a direction perpendicular to said fixed horizontal axis such that said second flange is mountable on said first flange at different positions relative to said first flange, a third rotary support means having an axis of rotation coincident with said fixed horizontal axis of said first rotary support means, said third rotary support means comprising a third vertically disposed flange rotatable about said fixed horizontal axis, a fourth vertically disposed flange mounted face-to-face on said third flange, additional mounting means for adjusting their relative mounting positions such that said fourth flange is displaceable relative to said third flange in a direction perpendicular to said fixed horizontal axis such that said fourth flange is mountable on said third flange at different positions relative to said third flange and in a direction perpendicular to said fixed horizontal axis, a support arm having one end mounted on said second vertical flange and extending generally horizontally from said second vertical flange, said


support arm having its other end mounted on said fourth flange, and a second rotary support means mounted on said support arm, said second rotary support means comprising a clamping plate on which said workpiece is clamped and a drive means for rotating said clamping plate about a rotary axis which is perpendicular to said fixed horizontal axis, whereby said clamping plate has unlimited rotational mobility and hence also the workpiece clamped thereto so that each welding seam on the workpiece may be disposed in a horizontal position and the seams in the workpiece may be favorably welded from above while such seams are horizontally disposed.

4,294,441

APPARATUS FOR SUPPORTING A WORK PIECE
Michael L. O'Banion, 15 Poppy Ln., East Lyne, Conn. 06333,
and Jack R. Veara, 5408 Emerald Dr., Eldersburg, Md. 21784
Filed May 15, 1979, Ser. No. 39,244
Int. Cl.³ B23Q 3/02

U.S. Cl. 269—97

26 Claims



1. A worktable for use with an auxiliary support structure comprising:

- (a) first and second elongated table members each having a work piece support surface for supporting and for gripping a work piece therebetween;
- (b) an annular rectangular shaped base support body formed of a polymer plastic defining an enclosed aperture;
- (c) means including first and second parallel aligned support bodies formed of metal for supporting said first and second table members on said support base body in a work plane parallel to and juxtaposed with said support base body;
- (d) means including first and second screws supported by said first and second parallel aligned support bodies for varying the relative position between the first and second table members in said work plane to provide a spacing therebetween for receiving and gripping work pieces of different sizes between said table members;
- (e) said support base body positioned relative to said table members for enabling a gripped work piece to extend through said aperture and to contact a surface of the auxiliary support structure; and,
- (f) adjustable, demountable means for clamping said support base body to an auxiliary support structure at a plurality of different locations on said auxiliary support structure.

4,294,442

WORKPIECE PALLET WITH DISTORTION FREE CLAMPING MEANS


Kenneth O. Kolnes, and Wynsel J. Johnson, both of Rockford, Ill., assignors to Greenlee Bros. & Co., Rockford, Ill.
Division of Ser. No. 934,751, Aug. 21, 1978, abandoned, which is a division of Ser. No. 832,764, Sep. 12, 1977, Pat. No. 4,148,470, which is a division of Ser. No. 652,257, Jan. 26, 1976, abandoned.
This application Jan. 18, 1980, Ser. No. 113,012
Int. Cl.³ B25B 1/04

U.S. Cl. 269—101

2 Claims

1. In a clamping means for clamping workpieces on a pallet for use in a transfer machine, the combination comprising:

- (a) an elongated support bar;
- (b) means for attaching said support bar to a pallet;
- (c) an elongated clamp bar having a clamp nose on one end thereof for engagement with a workpiece on the pallet to clamp the workpiece to the pallet;
- (d) fulcrum means supported by said support bar and engaged with the other end of said elongated clamp bar;
- (e) clamp screw means interconnecting said elongated clamp bar with said support bar at a point between said clamp nose and fulcrum means;
- (f) said elongated clamp bar is provided with a longitudinally extended recess on the lower side thereof and toward said other end thereof;



- (g) said fulcrum means comprises a fulcrum clamp screw having a central body portion slidably mounted in a bore formed through the support bar, a head portion on the upper end thereof slidably mounted in said longitudinal recess in the lower side of said elongated clamp bar, and a lower end adjustably mounted in the outer end of the elongated support bar;
- (h) the outer end of said support bar is bifurcated and includes means for forcing the parts of said bifurcated end together to retain said fulcrum clamp screw in fixed position in said support bar; and
- (i) means for retaining said clamp screw means in said support bar against longitudinal movement relative to said support bar.


4,294,443

WORKPIECE RETAINER

Alex W. Sova, 19951 Houghton, Detroit, Mich. 48219
Filed Sep. 19, 1980, Ser. No. 188,892
Int. Cl.³ B25B 1/24

U.S. Cl. 269—108

7 Claims



1. A device for holding irregular stones for the purpose of performing mechanical operations thereon which comprises:

- (a) spaced support members,
- (b) means mechanically associating said members operable to move said members toward and away from each other,
- (c) a length of flexible member mechanically associated with a portion of each of said members to form a closed loop, said flexible member lying essentially in a single plane, said flexible member having two ends secured to one of

said support members and a portion passing around a portion of the other support member, and
(d) a plurality of means on said flexible member in opposed positions to engage a stone positioned in the loop of said flexible member, whereby when said members are moved away from each other the loop is tightened to secure a stone to said chain.

4,294,444

PIPE GRIPPING VISE


Herbert D. Horton, Mayhill, N. Mex., assignor to World Wide Oil Tools, Inc., Houston, Tex.

Filed Apr. 29, 1980, Ser. No. 145,367

Int. Cl.³ B25B 1/08

U.S. Cl. 269—156

2 Claims



1. An apparatus for gripping pipe, said apparatus comprising:

- a frame for supporting a pipe to be gripped;
- a housing for supporting said frame;
- at least two vise jaws pivotally mounted on said frame with a first vise jaw disposed on a first side of said pipe when said pipe is supported on said frame and with a second vise jaw disposed on a second side of said pipe when said pipe is supported on said frame;
- a yoke having a first arm for slidably moving along a surface of said first vise jaw to cause said first vise jaw to pivot into gripping contact with said pipe and having a second arm for slidably moving along a surface of said second vise jaw to cause said second vise jaw to pivot into gripping contact with said pipe, said first and second arms of said yoke being slidably mounted within said housing so that the ends of said first and second arms of said yoke slidably communicate with said first and second vise jaws, respectively;
- means for biasing said yoke with respect to said housing to cause the ends of the first and second arms of said yoke to press against said first and second vise jaws, respectively; and
- means, mounted on said frame, for translating a rotational force acting on said pipe into a gripping force exerted on said pipe by said vise jaws.

4,294,445

SIGHTING DEVICE WITH MEANS FOR REFLECTING AND SUPERIMPOSING LIGHT FLASHES ON A VIEWED OBJECT

Scott C. Crosbie, 4349 Brookside Ave., St. Louis Park, Minn. 55436

Filed Feb. 15, 1980, Ser. No. 121,807


Int. Cl.³ A63J 5/02

U.S. Cl. 272—8 M

9 Claims

9. In an amusement device, the combination, comprising: viewing means for observing an object, said viewing means including an aperture for directing the viewing attention of an observer to said object and means for superimposing a pattern of indicia on the field of view through said aperture,

said means including opposed reflective surfaces and a light source, said pattern of indicia being comprised of individual



indicia of progressively increasing size with increasing distance from the view of said object observed through said aperture.

4,294,446

FRICTION TYPE EXERCISING DEVICE WITH IMPROVED FRICTION SETTING INDICATOR


Gerald L. Moore, San Jose, Calif., assignor to Ronald E. Useldinger, San Jose, Calif.

Filed Jul. 23, 1979, Ser. No. 59,899

Int. Cl.³ A63B 21/00

U.S. Cl. 272—133

11 Claims



- 1. An exercise device, comprising in combination: a housing having an outer wall forming a hollow cavity, said housing having a central axis;
- a shaft positioned within the cavity and held to allow axial and rotative movement relative to said housing when moved in one axial direction and preventing axial rotative movement relative to said housing when moved in the other axial direction;
- a hub positioned in said cavity and fixed to said shaft to move axially therewith while allowing rotation of the shaft relative to said hub, said hub being nonrotatable with respect to said housing;
- first and second openings in said hub;
- a rope-like member extending through said first opening in the hub, around said shaft and out the second opening in said hub whereby when the rope-like member is pulled frictional resistance is exerted on said rope-like member in proportion to the number of turns around said shaft;
- means attaching said rope-like member to the shaft whereby with relative rotation of the shaft and the hub, the number of turns of the rope-like member about the shaft is changed;

releasable means for holding the shaft against rotation relative to said housing which when released allows rotation of said shaft within said cavity thereby to change the number of turns said rope-like member is wound around said shaft;

a slide positioned with said cavity;

means connecting said slide, shaft and housing to cause movement of said slide in the direction parallel of the central axis with relative rotation between said shaft and housing; and

an opening in said housing in a position to allow viewing of the position of said slide thereby to indicate the number of turns said rope-like member is wound around said shaft.

4,294,447

AERIAL AMUSEMENT PROJECTILE AND METHOD OF MANUFACTURE

Merlin W. Clark, Rte. 1, Box 171, Spanish Fork, Utah 84660




Continuation-in-part of Ser. No. 19,050, Mar. 9, 1979,

abandoned. This application Sep. 10, 1979, Ser. No. 74,222

Int. Cl.³ A63B 43/00

U.S. Cl. 273—58 R

15 Claims



9. An aerial amusement projectile comprising: an aerodynamic body fabricated as a solid shape from a penetrable, resilient, sponge material; a streamer comprising a plurality of ribbons, the ribbons being fabricated from a flexible material; and a fastener for securing the streamer to the aerodynamic body, the fastener being fabricated as a harpoon member having a penetrating means and a streamer engaging means to accommodate being inserted inside the aerodynamic body to thereby secure an end of the streamer inside the aerodynamic body, the harpoon member comprising a body having a base at one end and an apex at the other end, the fastener comprising an angular face on the base and a leading edge defined by the perimeter of the angular face, the angular face being positioned at the end of the fastener nearest the point of insertion on the aerodynamic body after the fastener has been inserted into the aerodynamic body, the angular face comprising a planar element forming an angle of less than 90° with the axis of the harpoon member so that pulling forces against said har-

poon member cause the leading edge of said planar element to cut into said sponge material thereby accommodating the base causing the leading edge of the fastener to cut into the sponge material and thereby twist the harpoon member longitudinally under pulling forces exerted on the streamer, the apex allowing the body to be forcibly inserted inside the aerodynamic body while the base inhibits dislodgment of the harpoon member from the aerodynamic body.

14. A method for manufacturing an aerial amusement projectile comprising:

preparing an aerodynamic body from a solid mass of synthetic sponge material, the synthetic sponge material being resilient and penetrable, the body having a suitable aerodynamic profile;

obtaining a plurality of ribbons by cutting a flexible sheet material into a plurality of strips and bundling the strips into a streamer;

fabricating a fastener for the streamer by forming the fastener as a harpoon member having a base and a penetrating means extending from the end opposite the base and having a streamer engaging means, the base having a counterbore formed therein to serve as an insertion rod receiving means;

forming a slanted face on the base of the harpoon member, the slanted face being formed as a planar element angularly offset from an axis of insertion of said harpoon member into said sponge material so that pulling forces against said streamer tend to cause a leading edge of said planar element to cut into said sponge material thereby accommodating the harpoon member being longitudinally offset upon rearward movement of the harpoon member in the aerodynamic body;

mounting the streamer to the aerodynamic body by securing the streamer with the streamer engaging means of the fastener and by placing an insertion rod into the counterbore and inserting the insertion rod and fastener into the aerodynamic body so that the fastener is completely inside the aerodynamic body with the streamer extending from the aerodynamic body, the resilient material of the aerodynamic body resisting dislodgment of the fastener and the streamer from the body; and

rotating the fastener inside the aerodynamic body by pulling on the streamer and causing the base to cut into the resilient material of the aerodynamic body so as to provide better securement of the fastener thereto.

4,294,448

GAME APPARATUS


Newell B. Oler, 4323 Brown, Apt. 149, Dallas, Tex. 75219

Filed Jan. 21, 1980, Ser. No. 113,492

Int. Cl.³ A63F 7/06, 7/10

U.S. Cl. 273—94

12 Claims



1. A game apparatus for use with a ball, which comprises: an outer frame supported for pivotal movement about a first axis;

a first handle secured to said outer frame; an inner frame supported within said outer frame for pivotal movement about a second axis perpendicular to said first axis; a second handle secured to said inner frame; a planar game board defining a playing field mounted on said inner frame, said board including a plurality of apertures therein sized to receive the ball, certain ones of the apertures being designated penalty apertures; spring means for normally biasing said inner and outer frames to urge said game board toward a horizontal orientation; a plurality of fences attached to said game board so as to define, together with the apertures therein, an obstacle course for the ball; and spinner means for defining one of a plurality of predetermined rule infractions and penalties therefor to be applied when the ball enters a penalty aperture on said game board.

4,294,449

AMUSEMENT DEVICE


James K. Shaw, 4916 Erie St., Annandale, Va. 22003

Filed Oct. 13, 1978, Ser. No. 950,966

Int. Cl.³ A63F 3/00

U.S. Cl. 273—126 R

7 Claims



1. A game apparatus comprising: a substantially planar playing surface mounted atop a game table; vertical walls attached to the perimeter of said playing surface; indicia located substantially at the center of said playing surface; said surface having a plurality of corners; some of said corners having indicia and others of said corners having receptacles; the number of said corners being greater than the number of said receptacles, and said receptacles being dimensioned for receiving playing pieces used in conjunction with said game apparatus; a plurality of playing pieces; said playing pieces including separate sets of playing pieces for use by separate players, each of said separate sets of playing pieces having means for distinguishing it from the other sets; each separate set being divided into at least one pair of subsets whereby players using said subsets from the same separate set may play as partners; side indicia on said gameboard between a receptacle and one of said corner indicia; each of said side indicia being located adjacent said side walls to define a position at which at least one subset of said playing pieces is placed; each receptacle being placed a distance from said walls to define an area between said wall and said receptacle for receiving a playing piece therein; at least one cue piece, each receptacle having means adjacent thereto for defining an area whereby said at least one cue piece may be positioned.

4,294,450

GOLF TRAINING AID AND GAME


John Gallic, 151 Lenape La., Berkeley Heights, N.J. 07922

Filed May 2, 1980, Ser. No. 146,336

Int. Cl.³ A63B 69/36

U.S. Cl. 273—176 F

12 Claims



1. A practice putting game comprising a flexible base layer of predetermined length, a plurality of smooth monofilament fibers locked into said base from the back and protruding through the front surface thereof to form a simulated golf green surface, said fibers having a predetermined essentially uniform first height above said base, a continuous wear layer comprising a material having a high coefficient of friction covering the back of said base, a group of upright fibers anchored in said wear layer and protruding from said base through said monofilament fibers to a substantially uniform second height above said first height, said group of upright fibers being arrayed in a circle to define a raised ring, said ring having a predetermined interior diameter on the surface of said green, and said upright fibers being substantially less resilient than said monofilament fibers to permit a ball rolling on said monofilament fibers to pass through the circle of said upright fibers and into the interior of said ring.

4,294,451

SLOT MACHINE CARD GAME


Robert A. Wollner, 5547 Yarmouth Ave., Apt. #9, Encino, Calif. 91316

Filed Aug. 27, 1979, Ser. No. 70,244

Int. Cl.³ A63F 1/00

U.S. Cl. 273—308

1 Claim



1. A card game comprising: a plurality of cards, said cards being divided into several different groups with there being ten in number of said groups, there also being an equal number of said cards within each of said groups, the basic format of the different card groups being similar, each said card having a first indicia with there being several different first indicia, each said first indicia comprising symbols from the group consisting of fruits, bar representations, enlarged single numerals, and a slot machine with only a single said object represented on a single card, each said group of cards having identical first indicia; second indicia located on each card of said cards, said second indicia comprising monetary numerical values, there being different said monetary numerical values within each said group with each said card having only a single monetary value of said second indicia; and

third indicia located on each of said cards within certain said groups of cards, said third indicia comprising different monetary numerical values with there being the identical monetary numerical value used entirely throughout each of said certain groups.

4,294,452

TARGET BACKSTOP


Harold J. Schlotter, Springfield, and Leroy Young, Sedalia, both of Mo., assignors to Champion International Corporation, Stamford, Conn.

Filed Nov. 29, 1979, Ser. No. 98,657

Int. Cl.³ F41J 1/00

U.S. Cl. 273—403

13 Claims



1. A target backstop for supporting a target in which projectiles may be embedded comprising:
 - a plug;
 - a wall member formed of corrugated material having a front face, a rear face, and at least one cavity formed therein opening on said front face, said cavity comprising a front portion adjacent said front face for receiving said plug and a rear portion remote from said front face;
 - a resilient member formed of a heavy rubberized material mounted in said rear portion to abut said plug when said plug is mounted in said front portion, said rear portion having a rear chamber on the side of said resilient member remote from said front face;
 - said plug being formed of corrugated material and adapted to be coupled releasably within said cavity.

4,294,453

MECHANICAL SEAL

Hiroshi Inouye, and Eiichi Sato, both of Ibaraki, Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed Apr. 1, 1980, Ser. No. 136,368

Claims priority, application Japan, Apr. 4, 1979, 54-39827

Int. Cl.³ F16J 15/34

U.S. Cl. 277—22

8 Claims



1. A mechanical seal comprising:
 - a rotary sealing element rotatable with a shaft; and
 - a stationary sealing element secured to a casing through resil-

ient means and recoil preventing means to cooperate with said rotary sealing element to form a sealed surface; wherein the improvement comprises: a stationary retainer located opposite said sealed surface with respect to said stationary sealing element for holding said stationary sealing element, said resilient means and said recoil preventing means; a seal housing provided to said stationary retainer for enclosing said stationary sealing element; and an inwardly projecting portion formed in said seal housing in a portion thereof near said sealed surface for preventing axial movement of said stationary sealing element which might otherwise be caused by the biasing force of said resilient means when the seal is disassembled, whereby the stationary retainer including said stationary sealing element, said resilient means and said recoil preventing means as well as said seal housing can be attached to and detached from the casing as a unit.

4,294,454

ROTARY SEAL UNIT

John A. Cannings, Midway, Crowe Hill, Limpley Stoke, Bath, Avon, England


Filed Jan. 30, 1980, Ser. No. 117,836

Claims priority, application United Kingdom, Feb. 5, 1979, 03907/79

Int. Cl.³ F16J 15/34

U.S. Cl. 277—65

4 Claims



1. A rotary seal for establishing a seal between a shaft and a surrounding member with which the shaft is relatively rotatable, comprising:
 - an annular outer component adapted to be rotatable relative to the shaft;
 - an annular runner component adapted to be secured around the shaft;
 - a first sealing member carried by the outer component;
 - a second sealing member carried by the runner component;
 - one of said first and second sealing members being axially located on said component which carries it, the other of said first and second sealing members being axially slidable on said component which carries it;
 - spring means acting between said other sealing member and the component carrying said other sealing member to urge said other sealing member into sealing engagement with said one sealing member, thereby establishing an annular seal separating spaces on either side; and
 - a setting ring engaging axially between said components and rotatable relative to at least one of them so as to locate axially the two said components relative to each other while allowing them to rotate relative to each other, the setting ring being of a material of substantially different hardness from the material of a said component with which it is in rotatable axial engagement, so that after the seal has been running for some time the softer material

wears away to provide a clearance between the setting ring and at least one of said components.

4,294,455

ROLLER SKATE CONSTRUCTION


Arnold F. Krueger, Buffalo, N.Y., assignor to M & K Industries, Inc., Buffalo, N.Y.

Filed May 2, 1979, Ser. No. 35,242

Int. Cl.³ A63C 17/02, 17/14

U.S. Cl. 280—11.2

15 Claims



1. A roller skate construction comprising an elongated cast plastic body member including front and rear axle supporting portions, first and second bores in said front and rear axle supporting portions, respectively, first and second axles extending through said first and second bores, respectively, first and second axle supporting bolts extending perpendicularly through said first and second axles, respectively, in said front and rear axle supporting portions, respectively, first and second wear plates in said first and second bores, respectively, interposed between said first and second axles, respectively, and said front and rear axle supporting portions, respectively, said first and second axles including a rectangular solid central portion through which said first and second axle supporting bolts, respectively, extend, and flat planar portions defining the sides of said first and second bores and diverging away from said rectangular solid central portions on opposite sides of a plane extending perpendicularly thereto and passing through the axis of said first and second bolts, said flat planar portions providing limit stops for limiting pivotal movement of said first and second axles, respectively.

4,294,456

PIVOTABLE BALL SKATE


James L. Tuell, and Paul Wahnschaff, both of Atlanta, Ga., assignors to Tuell Industries, Inc., Atlanta, Ga.

Filed Nov. 13, 1979, Ser. No. 93,746

Int. Cl.³ A63C 17/02, 17/24

U.S. Cl. 280—11.28

5 Claims



1. A roller skate comprising an elongated foot support platform having a front end and a rear end for mounting against the bottom surface of a shoe or the like with its front end adjacent the toe of the shoe and the rear end adjacent the heel of the shoe, a front roller assembly mounted to said foot support platform adjacent the front end of said foot support platform, a rear roller assembly mounted to said foot support platform adjacent the rear end of said foot support platform, at least said front roller assembly comprising a roller support

bracket including a support plate portion in abutment with the foot support platform and an axle support projection extending from said support plate, an axle extending outwardly to opposite sides of said axle support projection and rollers mounted on said axle with one roller on each end of said axle, said rollers each being approximately of similar size and hemispherical in shape with their larger diameters positioned in juxtaposition with respect to said support projection, a pivot connector pivotally connecting said support plate portion of said roller support bracket to said foot support platform at a position of said support plate which is longitudinally offset from said axle so that when a lateral force is applied to said rollers the rollers tend to pivot about said pivot connector out of alignment with said foot support platform, and restraining means comprising a resilient pad positioned on each side of said roller support bracket and attached to said foot support platform, said resilient pads being offset longitudinally along the length of said foot support platform with respect to said pivot connector for resiliently maintaining said rollers in alignment with said foot support platform, and means for connecting said resilient pads to said foot support platform at a multiple number of positions along the length of said foot support platform.

4,294,457

COLLAPSIBLE SUPPORT DEVICE FOR A FOLDING SLED

Robert Thiboutot, Lac St. Charles, Canada, assignor to Les Entreprises Rotot Ltee, Comte de Bellechasse, Canada


Division of Ser. No. 960,444, Nov. 13, 1978, Pat. No. 4,245,849.

This application Apr. 11, 1980, Ser. No. 139,206

Int. Cl.³ B62B 13/16

U.S. Cl. 280—20

2 Claims



1. A sled which is collapsible in height and in width, the sled having a pair of spaced apart foldable runners and a collapsible support structure pivotally connected to the runners for pivotal movement about axes extending transversely to the longitudinal axes of the runners, said collapsible support structures comprising:
 - a. a first collapsible support structure forming the back of said sled;
 - b. a second collapsible structure forming the front of said sled;
 wherein each of said collapsible support structures has
 - (1) a first and a second support member pivotally connected to a respective runner and positionable in an upright position;
 - (2) a collapsible support mechanism interconnecting said support members and movable between a collapsed position in which the support members are adjacent to each other and an erected position in which the support members are spaced apart from each other;
 - (3) side members, generally parallel to said runners, interconnecting the support members forming the said front and back of said sled; and

(4) diagonal members interconnecting each of said runners with the support members not pivotally connected thereto so that pivotal movement of said support members towards said runners moves said runners towards each other, said diagonal members being adapted to support said support members in upright positions.

4,294,458 SKI STOP


Gerhard Sedlmayr, Farchant, Fed. Rep. of Germany, assignor to Hannes Marker, Garmisch-Partenkirchen, Fed. Rep. of Germany

Filed Nov. 16, 1978, Ser. No. 961,458
Claims priority, application Fed. Rep. of Germany, Nov. 18, 1977, 2751602

Int. Cl.³ A63C 7/10

U.S. Cl. 280—605

10 Claims



1. A ski stop in the form of a two-armed lever having a extending transversely to the length of a ski on an upper surface thereof, one arm of said lever being divided to form two brake prongs disposed at both sides of the ski, the other arm being spring-loaded into a first position in which said prongs are in braking positions and being engageable by a ski boot for movement into a second position in which said prongs are in non-braking positions, a coupling (9, 10) having a first end mounted at a position fixed with respect to the ski at a spacing from the pivot shaft (2), and a second end connected to the other lever arm (5), yoke means (12, 23) for intercoupling the second end of the coupling and the other lever arm, the yoke means extending parallel to the pivot shaft and being displaceable lengthwise of the shorter of the other lever arm and the coupling (5; 9, 20), and spring biasing means for spring loading said other arm and for biasing the yoke means (12, 23) towards a limiting position remote from the pivot shaft.

4,294,459 SKI BRAKE

Josef Svoboda, Schwechat; Erwin Krob, Vienna, and Erwin Weigl, Brunn am Gebirge, all of Austria, assignors to TMC Corporation, Baar, Switzerland

Division of Ser. No. 896,216, Apr. 13, 1978, Pat. No. 4,272,099.

This application Nov. 7, 1979, Ser. No. 92,139

Claims priority, application Austria, Apr. 18, 1977, 2678/77

Int. Cl.³ A63C 17/10


U.S. Cl. 280—605

1 Claim

1. A support structure for mounting a ski brake on a ski adjacent to a safety ski binding means also mounted on said ski, comprising:

- a mounting plate mounted on said ski and having means defining first and second axle receiving openings thereon spaced along the longitudinal axis of said ski;
- a U-shaped, spring wire ski brake means having a pair of brake arms located along opposite side edges of said ski interconnected by a first bight portion, each of said brake arms having a first axle segment therein received in said first axle receiving opening, said first bight portion including an integral U-shaped central segment opening outwardly in a direction opposite to the opening of said U-shaped, brake means to thereby define two laterally

spaced second bight portions located on opposite lateral sides of said U-shaped central segment, said U-shaped central segment having a third bight portion defining a second axle segment received in said second axle receiving opening, said first and second axle segments supporting said ski brake means for pivotal movement between a braking position wherein said brake arms extend at a transverse angle to the bottom surface of said ski and a retracted position wherein said brake arms extend generally parallel to the upper surface of said ski, said first and second axle segments extending perpendicular to the longitudinal axis of said ski, one of said first and second axle openings fixedly locating one of said first and second axle segments, the other of said first and second axle openings being elongated in the direction of said longitudinal axis of said ski to facilitate a sliding movement of said one of said first and second axle segments; and



stepping plate means pivotally mounted for movement about a pivot axle on said mounting plate by a pivot axle support, said stepping plate means including guide means for slidably supporting thereon said second bight portions, said second bight portions sliding along said guide means toward said pivot axle support during a movement of said ski brake means from said braking position toward said retracted position to thereby reduce the force required to hold said stepping plate in a position parallel with the upper surface of said ski,

said second bight portions' contact location being located on said stepping plate and divides the length of said stepping plate into two segments, a first segment extending between the pivot axle support and said location and a second segment extending between said location and an end of said stepping plate remote from said pivot axle whereat an external force is to be applied, whereby as said stepping plate is urged to said parallel position with said upper surface of said ski, the value of a ratio

$$\frac{\text{length of first segment}}{\text{length of second segment}}$$

is reduced; and

said guide means includes an intermediate lever engaging said second bight portions, one end of said lever being pivotally secured to said mounting plate adjacent said other of said first and second axle openings, the other end being slidably engaged with said stepping plate at said contact location thereon, wherein a further location of said second bight portions' contact location on said lever divides the length of said lever into third and fourth segments, said third segment extending between the pivotal support for said lever and said further location, said fourth segment extending between said further location and an end of said lever engaging said stepping plate at said contact location thereon whereby as said stepping plate is urged to said parallel position with said upper surface of said ski, the value of said ratio is further reduced.

4,294,460

FOOT-PLATES FOR SKI-BINDINGS

Bernhard Kirsch, Im Litzelholz 23, 5500 Trier-Biewer, Fed. Rep. of Germany


Filed Nov. 14, 1978, Ser. No. 960,662

Claims priority, application Fed. Rep. of Germany, Nov. 23, 1977, 2752206

Int. Cl.³ A63C 9/00

U.S. Cl. 280—607

17 Claims



1. In a ski assembly, a foot-plate member for carrying a ski-binding, a substantially rigid member including a ski and rigid pin means including at least one rigid pin rigidly connected to said ski, said rigid pin having a portion projecting upward from the ski, said foot-plate member having an upright recess receiving said rigid pin projecting portion which recess is of a cross-sectional size substantially larger than the cross-sectional size of said rigid pin projecting portion in said recess for enabling movement during skiing of said foot-plate member relative to said ski a substantial distance in all directions laterally of the direction of projection of said rigid pin projecting portion, the upright sides of said recess limiting the maximum range of lateral movement of said foot-plate member relative to said substantially rigid member, and resilient means including at least one pad of resilient material interposed between said substantially rigid member and said foot-plate member for cushioning lateral movement of said foot-plate member relative to said substantially rigid member throughout the full range of relative lateral movement of said two members permitted by said rigid pin projecting portion in combination with the upright sides of said foot-plate member recess for cushioning the transmission of lateral forces exerted on said ski from being directly transmitted to said foot-plate member.

4,294,461

SAFETY SKI BINDING COMPRISING A SOLE PLATE

Erich G. Eckart, Angererstr. 36, 8000 München 40, Fed. Rep. of Germany


Filed Nov. 19, 1979, Ser. No. 95,441

Claims priority, application Fed. Rep. of Germany, Nov. 29, 1978, 2851634

Int. Cl.³ A63C 9/081

U.S. Cl. 280—618

8 Claims



1. A safety ski binding comprising:
a sole plate pivotally connected to a ski by a trunnion approximately below the heel position of a skier;
a heel assembly on said sole plate adapted to pivot about a first axis transverse to said ski, said assembly being connected to a holder member having means for engaging the heel of a user for maintaining that heel of the sole plate;
spring means urging said assembly to pivot about said axis in a direction to maintain a heel on the sole plate; said spring

means including a carriage biased by spring force to a normal position;
a curved cam member rigidly attached to the ski;
a double-armed rocker pivotally mounted on said assembly about an axis extending laterally perpendicular to the ski, one arm of said rocker being rearwardly directed and being formed to define a cam follower engaging said curved cam member, the other arm of said rocker being pivotally connected to said carriage whereby said spring means biases said carriage to pivot said rocker and hold said cam follower against said curved cam member in a region thereof wherein said holder members holds the heel on the sole plate and said sole plate is held against free rotation on said ski.

4,294,462

SPRING LOCKING DEVICE

Josef Svoboda, Schwechat; Herbert Wuerthner, Hainburg, and Karl Stritzl, Vienna, all of Austria, assignors to TMC Corporation, Baar, Switzerland

Division of Ser. No. 900,302, Apr. 26, 1978, Pat. No. 4,213,630.


This application Dec. 21, 1979, Ser. No. 106,054

Claims priority, application Austria, Apr. 27, 1977, 2929/77

Int. Cl.³ A63C 9/08

U.S. Cl. 280—634

4 Claims



1. The combination of a release ski binding having a housing and an adjustable spring abutment thereon for changing the effective force of a spring in said ski binding housing, said adjustable spring abutment being initially exposed through an opening in said ski binding housing, and a seal member of brittle material for indicating that an adjustment of said adjustable spring abutment has taken place subsequent to an authorized adjustment thereof, said seal member being received in said opening in said ski binding housing directly in the pathway to said adjustable spring abutment, said seal member having destructible means thereon for securely holding said seal means in said pathway to prevent ready access to said adjustable spring abutment, said adjustable spring abutment means being adjustable only through a destruction of said destructible means, said adjustable spring abutment being threadedly coupled to said ski binding housing and having means thereon for receiving an adjustment tool therein, said destructible means on said seal member being positioned between said adjustable spring abutment and said ski binding housing whereby an axial movement of said adjustable spring abutment in response to a rotary movement thereof in said threaded coupling beyond a predetermined limit will cause a destruction of said destructible means.

4,294,463

COLLAPSIBLE LUGGAGE CARRIER

Hiroto Kotani, No.2-4, Ayameike-cho Minami-6-chome, Nara-shi, Nara-ken, 631, Japan

Filed Oct. 10, 1979, Ser. No. 83,368

Int. Cl.³ B62B 1/00

U.S. Cl. 280—646

11 Claims


1. A portable luggage carrier collapsible into the form of a bundle comprising:

- a base platform frame including a pair of first links each pivotally connected to the other at one end and angularly expandable and collapsible and a pair of second links each


pivoted to the midportion of one of the first links approximately at one end portion of each second link intersecting said first link, the second links being pivotally connected to each other at the other ends thereof and being angularly expandable and collapsible, the base platform frame being adapted to receive luggage thereon for transport;

a back frame including a collapsible handle bar pivotally connected at its lower portion to said other ends of the pair of second links and having the handle member at its upper portion and a pair of third links each pivotally connected approximately at one end portion thereof to a portion of one of the first links close to its free end and having the other ends pivotally connected to each other and also connected to the handle bar, the third links being angularly expandable and collapsible, the back frame being unfoldable to a position at least at a right angle with the base platform frame and foldable over the base platform frame, the back frame being laterally expandable and collapsible in operative relation with the base platform frame when folded over the base platform frame;

first hinge means pivotally connecting the handle bar to the second links as pivotal movement for pivotally connecting the base platform frame to the back frame and provided with movement compensating means for compensating



frame and also to a first arm of the pantograph linkage, a second arm of the pantograph linkage connected to a first wheel frame having wheels, a second wheel frame having wheels and link means extending between and interconnecting



said wheel frames, so that on collapsing said stroller said handle folds onto the upper frame and said upper frame moves in parallel manner to be adjacent said seat frame, said link means moving said first wheel frame wheels towards the second wheel frame wheels.

4,294,465

OPERATOR'S STATION AND MOUNTING

Gerald P. Simmons, Washington, Ill., assignor to Caterpillar Tractor Co., Peoria, Ill.


Continuation of Ser. No. 859,361, Dec. 13, 1977, abandoned.

This application Jun. 9, 1980, Ser. No. 157,332

Int. Cl.³ B62D 33/06

U.S. Cl. 280—756

7 Claims



1. In an earthworking machine having frame means defining opposite side portions, a pair of front wheels carried by a front portion of said frame means, a pair of rear wheels carried by a rear portion of said frame means, said wheels being disposed outwardly of said frame means side portions, and mechanism for operating the machine, the improvement comprising:

wall means defining an upwardly open operator's station; means for securing said wall means to one of said frame side portions to dispose said operator's station outwardly thereof between a front wheel and rear wheel;

a protective canopy mounted to said frame inwardly of said operator's station and including a cantilevered portion overlying and being unsupported by the operator's station outwardly of the frame for protecting the operator in said station from injury by falling objects and permitting substantially unobstructed viewing forwardly, rearwardly and outwardly from said station, said frame being pro-

4,294,464

CHILD'S STROLLER

John P. Ettridge, 235 Diagonal Rd., Warradale, Australia (5046)

Filed Feb. 14, 1979, Ser. No. 11,794

Claims priority, application Australia, Feb. 17, 1978, PD3427

Int. Cl.³ B62B 7/06

U.S. Cl. 280—649

6 Claims

1. A child's stroller comprising an upper horizontal frame, a lower horizontal seat frame, a pantograph linkage connecting the said frames, an articulated handle connected to the upper

vided with connector portions on the opposite side portions thereof, said canopy being provided with depending leg portions arranged to be connected to said connecting portions; and

bolt means for removably securing said leg portions to said connector portions to removably support the canopy at each of the opposite sides of the frame, the canopy being supported to the frame side portion opposite that to which the operator's station wall means is secured by only one of said leg portions.

4,294,466

WEIGHT REDISTRIBUTION APPARATUS


Dennis C. Hyman, Olympia, Wash., assignor to Molly Presley, Olympia, Wash.

Filed Oct. 4, 1979, Ser. No. 81,858

Int. Cl.³ B62D 9/02

U.S. Cl. 280—772

9 Claims



1. An apparatus for redistributing the weight of a vehicle as said vehicle negotiates a turn, said vehicle including a frame, two front wheels, and two rear wheels, comprising:

a pair of relatively telescoping elements, a first of said elements being affixed to said frame, the second of said elements being operatively coupled to said two front wheels to mount said front wheels for fore and aft longitudinal movement relative to said frame,

means associated with said elements for axially rotating said second element in a predetermined direction relative to said first element as said elements telescope, said second element being operatively coupled to said front wheels to alter the relative elevation of said wheels as said second element rotates relative to said first element,

biasing means operatively coupled between said telescoping elements to bias the telescoping movement of said second element in a forward direction, said biasing means being resiliently collapsible in reaction to exertion of a turning force on said front wheels to allow said second element to telescope relative to said first element, to thereby effect an elevation differential in said front wheels relative to said frame in reaction to said turning force.

4,294,467

SEAT BELT COMFORT DEVICE

Richard L. Frantom, Richmond, Mich., assignor to Allied Chemical Corporation, Morris Township, Morris County, N.J.

Filed Oct. 5, 1979, Ser. No. 82,397

Int. Cl.³ B60R 21/10



U.S. Cl. 280—801

17 Claims

1. A vehicle seat belt system comprising: seat belt webbing adapted to at least extend over the torso of an occupant seated in a seat in said vehicle; rewind means exerting a biasing force and biasing said webbing in a rewind direction and permitting extension of said webbing against said biasing force, said biasing force

causing said webbing to exert pressure against the torso of said occupant;

a tongue and buckle assembly associated with said seat belt webbing to provide a releasable interconnection for fastening said webbing about said occupant; and comfort means associated with said tongue and buckle assembly and actuable to at least reduce the pressure exerted by said webbing against the torso of said occupant;



said comfort means comprising a contact means for contacting said webbing, said contact means normally being located at a first position at which said webbing is not contacted by said contact means, said contact means being manually movable to a second position at which said webbing is contacted, said contact means including means responsive to release of said tongue from said buckle to automatically move said contact means from said second position to said first position to thereby automatically disengage said comfort means.

4,294,468

SEATBELT SYSTEM

Eiichi Kinaga, Toyota, and Mamoru Mori, Okazaki, both of Japan, assignors to Toyota Jidosha Kogyo Kabushiki Kaisha, Toyota, Japan


Filed Jun. 8, 1979, Ser. No. 47,140

Claims priority, application Japan, Aug. 24, 1978, 53-116464[U]

Int. Cl.³ B60R 21/02

U.S. Cl. 280—807

2 Claims



1. In a vehicle seatbelt system having a retractor fixedly mounted to said vehicle, a lap slip anchor rotatably mounted to

said vehicle subjacent said retractor and a seatbelt wound into and out of said retractor, and slideably received by said slip anchor, the improvement comprising means for preventing said slip anchor from rotating beyond a predetermined range wherein smooth extension and retraction of said seatbelt is assured, said preventing means including a slot in said slip anchor and a pawl fixed relative to said vehicle and extending into said slot, the dimension of said slot relative to said pawl enabling said anchor to rotate relative to said pawl within said range.

4,294,469


BOOK BINDERS AND BOOKS MADE WITH SAID BINDERS

Dominic R. Errichiello, 389 Meadowlark Rd., Bloomington, Ill. 60108

Filed Aug. 6, 1979, Ser. No. 63,859
Int. Cl.³ B42F 15/04

U.S. Cl. 281—29

4 Claims



1. A book comprising an integrally molded binder of a thermoplastic polymer having a spine with a substantially planar, longitudinal panel portion and a front cover panel and rear cover panel respectively hinged mounted on opposite, longitudinal sides of said spine by means of a living hinge formed between each of said cover panels and respective longitudinal sides of said spine; and paper pages positioned in said binder between said cover panels, one edge of said pages being fastened to said planar panel portion of said spine by means of stitching or stapling extending through said pages and said planar panel portion.

4,294,470

IN-LINE TUBE JOCTIONS

Alfred D. Tucker, Kersbrook, Australia, assignor to Reed Irrigation Systems Pty Ltd., Australia

Filed Dec. 7, 1979, Ser. No. 101,275

Claims priority, application Australia, Dec. 11, 1978, PD7073; Jun. 1, 1979, PD9044


Int. Cl.³ F16L 41/00

U.S. Cl. 285—5

2 Claims

1. An in-line tube junction for joining a first flexible tube to a lateral tube, said in-line tube junction comprising:
an open-ended, tubular socket member having a socket passage extending longitudinally therethrough, said socket member being formed of resilient material and having a longitudinal slit, the width of the slit being sized so that the first flexible tube when flattened can be inserted into the socket passage of the tubular socket member through the slit at least when the slit is increased in width by flexing the tubular socket member;
a hollow spike joined to the tubular socket member and projecting inwardly thereof, said spike being arranged to pierce the first flexible tube or to engage in an aperture in the first flexible tube to thereby place the hollow of the spike into communication with the interior of the first flexible tube;
a hollow take-off projecting outwardly from the tubular

socket member adjacent said spike, the hollow of said take-off communicating with the hollow of the spike; means for coupling the lateral tube to the take-off whereby fluid can flow from the first tube to the lateral tube through the spike and the take-off;



a removable keeper; and
means on the socket member adjacent said slit for cooperating with said removable keeper to prevent removal of the first tube from the socket member through the slit.

4,294,471

SUBSEA FLOWLINE CONNECTOR


Bernard H. van Bilderbeek, Monymusk, Scotland, assignor to Vetco Inc., Ventura, Calif.

Filed Nov. 30, 1979, Ser. No. 99,183

Int. Cl.³ F16L 55/00

U.S. Cl. 285—24

3 Claims



1. An apparatus for connecting a horizontal subsea flowline having a first sealing surface at one end thereof, to a generally vertical production riser comprising: means for holding an end of said flowline at a predetermined location; a rigid tubular spool piece having, a generally horizontally extending portion, a generally vertically extending portion, and a second sealing surface at the end of said horizontal portion and adapted to mate with said first sealing surface; guide means for guiding movement of the end of the horizontal portion of said spool piece substantially perpendicular to said second sealing surface, and for guiding movement of the end of the vertical portion of said spool piece in a manner to maintain it a fixed distance from the end of the horizontal portion of said spool piece; means for stroking said entire spool piece in a manner producing the guided movement of said spool piece; and stab means for stabbing and sealing the vertical riser on the upper end of said vertically extending portion of said spool piece.

4,294,472

PIPE COUPLING ASSEMBLY ESPECIALLY SUITABLE FOR USE IN THE NUCLEAR REACTOR


William E. Stolecki, East Longmeadow, Mass., assignor to Electric Power Research Institute, Palo Alto, Calif.

Filed Jun. 25, 1979, Ser. No. 51,805

Int. Cl.³ F16L 27/04

U.S. Cl. 285—27

12 Claims



1. A pipe coupling assembly especially suitable for fluid connecting together certain components submerged within a pool of liquid metal in a nuclear reactor, said assembly comprising a first tubular section having one end adapted for connection with one of said reactor components, a second tubular section having one end adapted for connection with another of said reactor components; a third intermediate tubular section and first and second joint arrangements for respectively connecting one end of said intermediate section with the otherwise free end of said first second and the opposite end of said intermediate section with the otherwise free end of said second section, said first joint arrangement forming the connecting ends of said first and intermediate sections and including a male portion having an outer partially spherical contour, an associated female portion including means interconnected with said male portion for providing limited axial and pivotal movement between said first and intermediate tubular sections and means for interlocking said male and female portions together, said interconnecting means including an outer cylindrical housing and a concentric inner cylindrical sleeve shorter in length than said outer housing and slidable within and against the inner surface of said housing along a longitudinal section of the latter, said housing and sleeve being positioned around their associated male portion for pivotal movement about the latter, said second joint arrangement forming the connecting ends of said second and intermediate sections and including a male portion having an outer partially spherical contour and an associated female portion including means supporting said last-mentioned male portion for pivotal movement.

4,294,473

DEVICE AT MUTUALLY LOCKABLE FIRST AND SECOND PARTS

Kjell R. Ekman, Zug, Switzerland, assignor to Ekman Engineering AG, Switzerland

Filed Mar. 12, 1980, Ser. No. 129,804

Claims priority, application Switzerland, Mar. 20, 1979, 02488/79


Int. Cl.³ F16L 55/00

U.S. Cl. 285—50

10 Claims

1. An improved coupling device for providing a fluid-tight connection between a source of fluid and a hollow conduit unit having an enlarged cavity for receiving said coupling device, and comprising:

a first coupling member having a fluid passageway extending therethrough;
a second coupling member having a fluid passageway extending therethrough;
said first and second coupling members each having on a respective first end portion thereof means for permitting insertion of said second coupling member into said first coupling member, thereby aligning said flow passageways extending therethrough;
at least one sealing ring means compressed between confronting surface portions of said first and second coupling members for preventing the flow of fluid between said coupling members while simultaneously suppressing the transmission of vibrations through said coupling device;
said first coupling member further having on a second end portion thereof means for permitting free insertion of said first coupling member into an enlarged cavity in a hollow conduit unit until said second end portion abuts a portion of an end wall of said enlarged cavity and an exterior surface portion of said first coupling member is radially spaced from a surface portion of said enlarged cavity a distance sufficient to create a substantially cylindrically-shaped slot therebetween;
at least one additional sealing ring means contacting said abutting portions of said first coupling member and said enlarged cavity for preventing fluid from leaking therebetween;



a hollow nut assembly including on a first portion thereof means for permitting insertion of said nut assembly into said cylindrically-shaped slot a sufficient distance such that an end surface of said hollow nut assembly abuts a radially extending wall portion of said first coupling member and a second end portion of said hollow nut assembly overlaps and faces a substantially radially extending end wall of said first coupling member, defining a circumferentially extending locking slot therebetween;
said hollow nut assembly including attachment means engaging complimentary attachment means formed on said hollow conduit unit for fixedly positioning said hollow nut assembly within said substantially cylindrically-shaped slot;
a substantially ring-shaped locking member formed of resilient material extending partially into said circumferentially extending locking slot and confronting a circumferentially extending stop assembly formed on an exterior surface of said second coupling member; and
said second end portion of said hollow nut assembly including wall means for engaging and biasing said substantially ring-shaped locking member into tight frictional contact with said stop assembly, thereby preventing inadvertent withdrawal of said second coupling member from said first coupling member.

4,294,474


PREFABRICATED CHIMNEY-SHAFT

Josephus J. D. Harm, Vijzelgracht 29-31, Amsterdam, Netherlands

Filed Sep. 25, 1978, Ser. No. 945,234
Int. Cl.³ F16L 39/00

U.S. Cl. 285—133 R

5 Claims



1. A prefabricated chimney-shaft comprising an inner sheath and an outer sheath surrounding said inner sheath, in which the inner sheath and the outer sheath are interconnected near their two ends with the aid of tie-members and at least the outer sheath has a multi-angled cross section, and near each said end of the outer sheath is positioned a tie-member comprising a plate extending substantially perpendicular to the longitudinal axis of the chimney, the shape of said plate being adapted to the inner cross-section of the outer sheath, and at its periphery said plate is provided with first bent-over rims for joining the outer sheath, and the tie-member further has a passage bounded by a second bent-over rim for engaging the inner sheath, such that said first and second bent-over rims of each said tie-member are arranged to face one another, and at one end of the outer sheath both of said rims project a longitudinal distance out of the outer sheath over a portion of their height and near the other end of the outer sheath the tie-member and both of its rims are recessed a longitudinal distance from said other end.

4,294,475

FLEXIBLE PIPE CONNECTOR

Isamu Kanai, Sayama; Shigeki Okubo, Yokosuka; Kazuo Tsuchiya, Ebina, and Toshio Takasaki, Yokohama, all of Japan, assignors to Bridgestone Tire Company Limited, Tokyo, Japan


Filed Nov. 8, 1979, Ser. No. 92,262

Claims priority, application Japan, Nov. 10, 1978, 53-154012[U]

Int. Cl.³ F16L 15/02

U.S. Cl. 285—165

5 Claims



1. A flexible pipe connector comprising; a pair of connection pipes arranged on the same axial line and spaced apart from

each other, a pair of intermediate sleeves each having one end portion overlapped with each of said connection pipes and coaxially arranged therewith, each of said intermediate sleeves being provided at its opposed end portion with projections defining abutments limiting axial movement of said intermediate sleeves away from each other, a rubber-like elastic body filling up a gap formed between each of said intermediate sleeves and each of said connection pipes and bonding the former with the latter, and connection fitting means to fluid-tightly seal and connect both said intermediate sleeves with each other and permitting said intermediate sleeves to slidably move in the axial direction and limit in cooperation with said projections said movement away from each other.

4,294,476

CONNECTING DEVICE


Patrick L. Nash, 7 E. Mill St., Shelburn, Ind. 47879

Filed Nov. 8, 1979, Ser. No. 92,929

Int. Cl.³ F16L 41/00

U.S. Cl. 285—189

13 Claims



1. A connecting device for anchoring a duct segment to an opening in a wall, the duct segment having a peripheral edge portion closely receivable into the opening, the connecting device being formable of integral construction from a metal sheet of substantially uniform thickness and comprising a plurality of strips defined by bending said sheet along crease lines, the strips including first and second gripping strips and first and second flange strips, said first and second gripping strips being adapted for grippingly fitting over said peripheral edge portion of the duct, said first and second gripping strips being connected to said first and second flange strips along a joint and being substantially orthogonally aligned to said second flange strip and in parallel alignment with said first flange strip, said first and second flange strips being positioned to abut against said wall in close proximity to the opening, said first flange strip including a plurality of tabs substantially orthogonally aligned to said second flange strip and being manually bendable around said opening to a position parallel to said second flange strip with the portion of the wall immediately adjacent said opening included therebetween, whereby secure anchoring of the duct to the wall around said opening is effected.

4,294,477

FLEXIBLE RING GASKET RETAINER FOR FLANGED CONNECTORS

Arthur G. Ahlstone, Ventura, Calif., assignor to Vetco Inc., Ventura, Calif.

Continuation of Ser. No. 804,584, Jun. 8, 1977, abandoned. This application May 29, 1979, Ser. No. 42,461

Int. Cl.³ F16L 17/06

U.S. Cl. 285—336

18 Claims

1. In a connector: a pair of connector bodies having a fluid passage therein when said bodies are connected together, said

4,294,479

SAFETY LIFTING HOOKS

Jean-Francois Archer, Villennes, France, assignor to Stas Societe Technique d'Accessoires Specialises S.A., Sartrouville, France


Filed Jan. 17, 1980, Ser. No. 112,822

Claims priority, application France, Jan. 25, 1979, 79 02691

Int. Cl.³ B66C 1/36

U.S. Cl. 294—82 R

10 Claims



with respect to the groove in one of said bodies to be clamped between said bodies in said grooves with at least said outer side walls loaded against said gasket ring, and means independent of said retainer means clamping said bodies together, said means connecting said retainer means to said gasket ring being flexible to enable movement of said gasket ring during loading thereof, said radial surfaces engaging said retainer means to limit the loading of said gasket ring by said side walls.

4,294,478

DETACHABLE PROTECTOR FOR STEEL OBJECTS


Russell C. Marquette, 2415 E. 15 St., Tulsa, Okla. 74104

Continuation of Ser. No. 867,239, Jan. 6, 1978, abandoned. This application Mar. 19, 1979, Ser. No. 22,215

Int. Cl.³ B60R 19/08

U.S. Cl. 293—128

2 Claims



1. An improved detachable protector for steel objects comprising:

an elongated body formed of magnetic plastic material which adheres to metal, such as steel, the body in cross-section being defined by a thin flat part having an upper and a lower surface and an arcuate part extending from the flat part upper surface, the width of the arcuate part being less than the width of the flat part, said flat part has side portions along each side of said arcuate part and a mediate portion substantially equal to the internal width of the arcuate part, said portions of said flat part extending along each side of said arcuate part are integral with said arcuate part and wherein the intermediate portion of said flat part is a separate element bonded to said arcuate part, the lower surface being planar; and

a thin elongated flat paramagnetic metal member of length substantially equal to the length of the detachable protector, positioned within said arcuate part and in close engagement with the upper surface of the intermediate portion of said flat part, said metal member having width substantially equal to the internal width of the arcuate part at point adjacent the intermediate flat part upper surface.

4,294,480

SAFETY GUARDS AND METHODS FOR MANUALLY FEEDING WORKPIECES TO ASSEMBLY MACHINES

William S. Burns, Jr., and William M. Sankey, both of Shreveport, La., assignors to Western Electric Company, Incorporated, New York, N.Y.

Filed Feb. 1, 1980, Ser. No. 117,687

Int. Cl.³ B25D 17/10; F16P 1/00


U.S. Cl. 294—131

6 Claims

1. A safety guard that permits manual gripping of an end portion of a workpiece to be fed to an assembly machine, which comprises:

a hollow shield having an opening at one end thereof into which an operator's hand can be inserted, the shield having a slot at the opposite end arranged for receiving the end portion of the workpiece within the shield, the shield further having means for supporting the end portion of the

workpiece within the shield and for permitting manual gripping of the end portion by the operator within the



shield, while the shield precludes injury to the operator's hand when the workpiece is fed to the assembly machine.

4,294,481

GAS CYLINDER CARRIER


Douglas B. Pearl, Pompano Beach, Fla., assignor to Uniweld Products, Incorporated, Ft. Lauderdale, Fla.

Filed Jun. 26, 1980, Ser. No. 163,176

Int. Cl.³ B62B 1/14

U.S. Cl. 294—146

3 Claims



1. In a gas cylinder stand or truck including cylinder support or base means, handle means and cylinder retaining means, improvements in said cylinder retaining means comprising: first and second pairs of spaced, opposed arcuate sections; said first pair of said sections being spaced and having a radius to accommodate and retain a gas cylinder of a given size therebetween; said second pair of said sections being joined to said first pair at four junction points to form a unitary, cylinder-retaining structure; said second pair of said sections having radii and an included angle or length to accommodate two adjacent gas cylinders of smaller size than said given size therebetween; the radii of said second pair of said sections being smaller than the radius of said first pair of said sections.

4,294,482
RAILWAY WHEEL TREAD PROFILE

Herbert Scheffel, Rowlen E. von Gericke, and Joseph A. Viviers, all of Transvaal, South Africa, assignors to South African Inventions Development Corporation, Transvaal, South Africa
Filed Aug. 23, 1979, Ser. No. 69,515

Claims priority, application South Africa, Aug. 23, 1978, 78/4791

Int. Cl.³ B60B 17/00

U.S. Cl. 295—34

19 Claims



1. A profiled wheel-tread for a railway wheel having a circumferential running surface and a circumferential wheel flange with the running surface having a tapering line and a running zone between the tapering line and a radiused fillet portion at the base of the wheel flange with the improvement that the effective conicity across the running zone, the effective conicity being dependent on the rate of change of rolling diameter, decreases progressively while remaining positive from a zone adjacent the tapering line towards the wheel flange.

4,294,483

INFLATABLE VEHICLE COVER


Sean D. Ferris, 96 Spruce St., Natrona, Pa. 15065

Filed Mar. 14, 1980, Ser. No. 130,249

Int. Cl.³ B62D 25/00

U.S. Cl. 296—136

6 Claims



1. A cover for protecting the body of a vehicle during transit against damage from the force of foreign objects directed at said vehicle body comprising: a body member defining at least one cell adapted for inflation by the introduction of a fluid into said cell; a surface of said cell being shaped to conform to the contours of the outer surface of said vehicle body when said cell is inflated; means for allowing introduction of said fluid into said cell to inflate said cell and for permitting release of said fluid from said cell to deflate said cell; and means for securing said cell to said vehicle body to completely cover the exterior surface thereof.

4,294,484

VEHICLE CAMPER


Robert H. Robertson, Dallas, Tex., assignor to Ronbil Industries, Inc., Dallas, Tex.

Filed Mar. 9, 1979, Ser. No. 18,888

Int. Cl.³ B60P 3/32

U.S. Cl. 296—156

23 Claims



10. A camper mounted on a vehicle having a vehicle bed, two sidewalls and a front wall, said camper comprising: a top covering the vehicle bed and movable between a lowered position adjacent the upper edge of the two sidewalls and the front wall and a raised position elevated above the vehicle bed; main frame means pivotally attached adjacent said sidewalls for supporting the rigid top in the raised position and for pivotally moving between a lowered frame position and a raised frame position; lever means extending from said main frame means for applying a rotational force to said main frame means and comprising: triangular plates extending from the lower end of said main frame means; and catch means on said triangular plates disposed remotely from said main frame means for attaching said tension means to said triangular plates, whereby said tension means will impart a tension force to said triangular plates for applying a torque to said main frame means causing said main frame means to rotate toward the raised frame position; and force means for applying a force to said lever means to apply a rotational force to said main frame means for urging said main frame means to rotate from the lowered frame position towards the raised frame position.

4,294,485

WINDOW BOOT

Thomas E. Engelhard, 4325 Colfax Ave. South, Minneapolis, Minn. 55409

Continuation-in-part of Ser. No. 921,276, Jul. 3, 1978, Pat. No. 4,222,605, which is a continuation-in-part of Ser. No. 738,313, Nov. 2, 1976, Pat. No. 4,114,943. This application Feb. 2, 1979, Ser. No. 8,539


Int. Cl.³ B60P 3/32

U.S. Cl. 296—166

7 Claims

1. A combination including a boot and frame windows of a cab/camper assembly of the type having a rear frame window in the cab and a corresponding front frame window in the forward wall of the camper, said boot comprising a boot frame including a continuous resiliently deformable sidewall, said sidewall defining an aperture corresponding respectively to said windows in said cab and said camper, said sidewall terminating in respective opposite ends, one of said opposite ends including a thickened resilient continuous lip, said lip being adapted to be snap-fit into a corresponding window frame for thereby mounting said boot between said cab and camper, said window frame including an exteriorly extending substantially

U-shaped channel in which the lip of said boot is grippingly receivable, the other of said ends including magnetic means for



securement of said boot to said cab, whereby said boot may be easily mounted and dismounted from said cab and camper.

4,294,486

CAMPER AND TENT UNIT


Eusebio H. Espejo, 1429 Alma St., San Pedro, Calif. 90731

Filed Dec. 21, 1978, Ser. No. 971,871

Int. Cl.³ B60P 3/34

U.S. Cl. 296—167

21 Claims



1. A camper tent unit comprising a housing structure having a vertical section and a horizontal hollow shell section; means for supporting said housing structure on a passenger vehicle with said vertical section supported on the rear and said horizontal section extending forwardly on top of the vehicle; said horizontal shell section having a roof and front and side walls extending downwardly from said roof to form a storage space; flexible fabric tent components having means connecting the components to said front and side walls for folding storage in said shell and erectable to form with said housing structure, when removed from the vehicle, a laterally extended tent roof and side, front and rear tent walls connected with one another and with said housing structure to form an enclosure; and means providing frame structures connected with said roof and said front wall tent components to form rigid support therefore, when deployed from said housing structure.

4,294,487

CAR BODY

Yoshiharu Nakamura, Koganei, Japan, assignor to Nissan Motor Company, Limited, Kanagawa, Japan

Filed Aug. 20, 1979, Ser. No. 68,002

Claims priority, application Japan, Sep. 12, 1978, 53-125960[U]


Int. Cl.³ B62D 25/04

U.S. Cl. 296—188

3 Claims

1. A car body of two-door type comprising: a center pillar provided on each side portion of the car body; a rear fender integrated with the bottom of said center pillar; a rear side glass elevatably provided along said center pillar; and a stiffener having a front wall, a side wall and a rear wall which are formed of a channel shape in cross section so as to fit on the inside of said center pillar, said stiffener being

arranged within said center pillar, said stiffener extending downwards beyond the waist line of said rear fender, the



rear wall of said stiffener being fixed through a flange formed at an edge of said stiffener to an inner panel of said car body.

4,294,488

RECLINER AND INERTIA LATCH


Joseph Pickles, Birmingham, Mich., assignor to Ferro Manufacturing Corporation, Southfield, Mich.

Filed Nov. 23, 1979, Ser. No. 96,883

Int. Cl.³ A47C 1/026

U.S. Cl. 297—367

13 Claims



1. A vehicle seat construction comprising a vehicle seat having seat brackets fixed to opposite lateral ends thereof, a reclining seat back having recliner brackets fixed to opposite sides at the lower end thereof, pivot means interconnecting the seat brackets and the adjacent recliner brackets, lock means for positively locking both recliner brackets simultaneously in selected positions relative to said seat brackets, said lock means comprising a movable lock member at each side of the seat construction, a rotatably mounted actuator cooperating with each of said lock members, a manually movable lever fixed to one of said actuators, and a drive connection between said actuators to insure identical simultaneous movement of said actuators at opposite sides of said seat construction, said drive connection comprising an elongated straight, rigid torsion bar extending between and mounted for rotation about its longitudinal axis relative to a first pair of like brackets at opposite sides of the seat construction, and means providing for movement of said bar relative to the other pair of like brackets in an arcuate path concentric with but displaced substantially from the transverse pivot axis determined by the location of the pivot means interconnecting the brackets at opposite side of said seat construction.

4,294,489 UPHOLSTERED FURNITURE HAVING IMPROVED FLAME RESISTANCE

Colin Anolick; Vivian M. Robinson, both of Wilmington, and Charles W. Stewart, Sr., Newark, all of Del., assignors to E. I. Du Pont de Nemours and Company, Wilmington, Del.

Continuation of Ser. No. 572,709, Apr. 29, 1975, Pat. No.

4,174,420. This application Mar. 13, 1978, Ser. No. 886,260

The portion of the term of this patent subsequent to Nov. 13, 1996, has been disclaimed.

Int. Cl.³ A47C 5/12; B32B 3/26

U.S. Cl. 297—452

3 Claims

1. A flame resistant cushion comprising a metal frame assembly, an inner padding of foamed urethane material, an exterior layer of foamed neoprene material covering the entire exterior surface of said inner padding, and means for uniting said padding and said exterior layer together integrally.

4,294,490

FIBER-REINFORCED COMPOSITE WHEEL CONSTRUCTION


James A. Woelfel, Lansing, Mich., assignor to Motor Wheel Corporation, Lansing, Mich.

Filed Feb. 6, 1980, Ser. No. 119,141

Int. Cl.³ B60B 21/00, 1/06

U.S. Cl. 301—63 PW

26 Claims



1. A composite wheel of fiber-reinforced resin comprising a disc wherein reinforcing fibers comprise fibers oriented randomly of the wheel axis and a rim wherein reinforcing fibers include first fibers oriented substantially randomly of the wheel axis and directional second fibers all extending in a direction essentially parallel to the wheel axis with the random and directional reinforcing fibers in said rim being disposed in essentially distinct layers radially of said wheel axis and with the fiber to resin weight ratio being in the range of 30% to 80%.

4,294,491

METAL DISK WHEEL WITH RESILIENT TREAD AND BEARING SUPPORT

John W. Black, Hickory Corners, Mich., assignor to Pemco-Kalamazoo, Inc., Kalamazoo, Mich.

Continuation of Ser. No. 964,133, Nov. 27, 1978, abandoned.

This application Apr. 30, 1980, Ser. No. 145,279


Int. Cl.³ B60B 1/06; F16C 33/00

U.S. Cl. 301—63 DD

5 Claims

1. A wheel construction, comprising: bearing means defining an axis of rotation, said bearing means being housed in an elastically deformable elastomeric sleeve; a pair of identically shaped metallic stampings, each having a central cylindrical shell part axially aligned with the other and means defining a hole therethrough in approximately the center thereof, said stampings each having a surface portion intermediate said central cylindrical shell part and a first peripheral surface which is coextensive with a central plane through said wheel construction and perpendicular to said axis of rotation, said axially aligned cylindrical shell parts of each stamping housing said bear-

ing means therein with at least a portion of the inner surface of said cylindrical shell part engaging a portion of the external surface of said elastomeric sleeve adjacent the axial ends thereof and said surface portions slidably engaging one another; and an elastically deformable annulus of moldable synthetic resin material and means for fixedly securing said annulus to said first peripheral surface of said pair of metallic stampings to effect, along with said elastomeric sleeve engaging said inner surface of said cylindrical shell parts, a holding of said cylindrical shell parts and said surface portions in axial alignment, the material of said annulus and said sleeve having an elastically deformable characteristic to thereby permit said pair of stampings to temporarily shift radially relative to one another against the elastic resistance of said annulus and said sleeve arising due to an



elastic deformation of said annulus and said sleeve while maintaining said surface portions in sliding engagement with one another and to temporarily facilitate an orientation of said central plane inclined to said axis of rotation in response to shock loads having a component of force applied to said wheel construction in a direction parallel to said axis of rotation, said material further having a sufficient resistance to elastic deformation to thereby hold said metallic stamping in axial alignment during normal use thereof, said sleeve and said annulus thereby facilitating an absorption of said shock loads applied to said bearing means, said material further effecting a return of said pair of stampings to said axially aligned position thereof with said central plane oriented perpendicular to said axis of rotation following the termination of a shock load applied thereto.

4,294,492

CALIPER SEAL ASSEMBLY


Robert F. Evans, 631 Honeywood La., La Habra, Calif. 90631

Continuation-in-part of Ser. No. 95,532, Nov. 19, 1979, Pat. No. 4,240,674. This application May 27, 1980, Ser. No. 153,540

Int. Cl.³ F16C 33/74

U.S. Cl. 308—8.2

20 Claims



1. In combination with a drill bit, which includes a cutter

wheel rotatably connected by a bearing assembly to a body element of the drill bit, a caliper seal assembly operatively extending between the cutter wheel and the bit body to seal the bearing assembly from the ambient environment of the bit, said caliper seal assembly comprising:

a first structure having a bifurcated end defined by a pair of flexible flank members separated by an intermediate channel, each flank member including a contact pad formed thereon facing into the intermediate channel; and means defining a flange-like projection extending into the intermediate channel of said first structure, said flange-like projection including a pair of sealing surfaces, each sealing surface being positioned in contacting and movable sealing relation with a different contact pad.

4,294,493

MAGNETIC BEARING ASSEMBLY

Rainer Sindlinger, Hirschberg, and Josef Hammer, Rotenberg, both of Fed. Rep. of Germany, assignors to Teldix GmbH, Heidelberg, Fed. Rep. of Germany


Filed Nov. 2, 1979, Ser. No. 90,588

Claims priority, application Fed. Rep. of Germany, Nov. 4, 1978, 2847930

Int. Cl.³ F16C 39/06

U.S. Cl. 308—10

16 Claims



1. In a magnetic bearing assembly for a rotor having an axis of rotation; the assembly including at least two actively regulated magnetic bearings for stabilizing the rotor in radial directions oriented substantially perpendicularly to one another and to said axis; said magnetic bearings defining a bearing plane oriented perpendicularly to said axis; means for sensing radial motions of said rotor and emitting first signals in response to said radial motions; and force generating means for applying to said rotor radial return forces as a function of said first signals; the improvement wherein said rotor has a center of gravity situated at an axial distance from said bearing plane whereby tilting motions of said rotor about tilt-axes perpendicular to said axis of rotation can be sensed; further comprising sensors for sensing said tilting motions of said rotor and emitting second signals in response to said tilting motions; said sensors being situated at an axial distance from said bearing plane; said force generating means applying to said rotor, as a function of said second signals, return forces opposing said tilting motions of said rotor.

4,294,494

SLIDING-TYPE BEARING

Masahiro Yoshioka; Toshifumi Koike, both of Ibaraki, and Hideki Izumi, Tsuchiura, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Filed Nov. 27, 1979, Ser. No. 97,698

Claims priority, application Japan, Dec. 4, 1978, 53-149117

Int. Cl.³ F16C 1/24


U.S. Cl. 308—76

6 Claims

1. In a sliding-type bearing having a bearing surface provided with a lubricating oil groove at each of two portions thereof substantially 90° apart from the point to which the load of a rotary shaft is applied,

an improvement which comprises: a chamfer formed in at least the portion of the bearing surface near one of the

lubricating oil groove remoter from the point of the minimum bearing clearance determined by the direction of rotation of the shaft and by the direction of application of the load, said chamfer being communicated with said one



of said lubricating oil groove and opening at the side of said bearing, said chamfer being adapted to permit the discharge of the heated lubrication oil to the outside of said bearing together with the cooled lubricating oil supplied to said one of said lubricating oil grooves.

4,294,495

BOOM SOCKETS


Morris L. Whaley, Chula Vista, Calif., assignor to Morris Whaley, Inc., Chula Vista, Calif.

Filed Oct. 15, 1979, Ser. No. 84,852

Int. Cl.³ F16C 19/36

U.S. Cl. 308—174

14 Claims



1. A boom socket or the like, comprising: a housing; a gooseneck assembly comprising a vertical pin and a gooseneck at the upper end thereof; means comprising vertically spaced, upper and lower tapered roller bearings rotatably supporting said vertical pin in said housing for rotation about a vertical axis; a boom end; and means for rotatably supporting said boom end for rotation about a horizontal axis from said gooseneck comprising a cross pin extending through said gooseneck, boom end brackets embracing said gooseneck, and tapered roller bearings surrounding the respective end of said cross pin for rotatably supporting said boom end brackets from the respective ends of said cross pin.

4,294,496

PORTABLE COMPUTER ENCLOSURE


James D. Murez, Santa Monica, Calif., assignor to GM Research, Carson, Calif.

Filed Aug. 3, 1979, Ser. No. 63,418

Int. Cl.³ A47B 21/00; A47R 81/00; H05K 5/00

U.S. Cl. 312—208

4 Claims



1. A portable computer including: first and second enclosures hinged together at ends which are closeable upon each other to define a single suitcase-type cabinet having a general rectangular parallelepiped configuration; said first enclosure comprising a main frame with a display at its closeable end, and a rear panel backing said main frame; said second enclosure having a keyboard at its closeable end, a front panel backing said keyboard, and a handle extending from said front panel; said enclosures further having top and bottom panels respectively segmented into first and second portions respectively on said first and second enclosures; hinges connecting said first and second portions of said segmented bottom panel; cooperating latches respectively on said first and second portions of said segmented top panel for securing said enclosures together when closed; and foot pads extending from said rear panel, said first portion and said front panel.

4,294,497

COMBINED CARRYING CASE, DISPLAY DEVICE AND LECTERN

Robert A. Daniel, 455 Center St., Bridgewater, Mass. 02324

Filed Aug. 14, 1980, Ser. No. 178,085

Int. Cl.³ A47B 27/00

U.S. Cl. 312—231

5 Claims



1. A multi-use carrying case, display and lectern device comprising: a bottom wall; an upwardly extending rear wall; a relatively short front wall; a pair of side walls, the side walls being tapered upwardly so as to present a narrowing and reduced width at their upper ends; said walls being secured together to define a case configuration which, in cross section, tapers upwardly;

a rectangular cover extending downwardly along the front edge of each of the side walls and being arranged to cover fully the case, the cover being hinged at its upper end to the upper end of the rear wall; a transversely extending slot formed in the short front wall; a shelf defining a false bottom within the case, the shelf being extendable through the slot to provide a forwardly extending shelf on which materials may be supported; guide means for guiding and supporting the shelf for movement between its retracted configuration in which it defines the false bottom for the case and its extended configuration in which it projects outwardly through the slot; and a carrying handle secured to the upper region of the device.

4,294,498

WALL CABINET AND METHOD OF MAKING


Richard D. Van Luit, 189 Manning Dr., Berea, Ohio 44017

Filed Oct. 17, 1979, Ser. No. 85,691

Int. Cl.³ A47B 67/02; A47F 5/08; E05D 7/00

U.S. Cl. 312—245

7 Claims



1. A plastic wall cabinet comprising a body portion of plastic sheet material and having a back wall and top, bottom and side walls integral with and extending forwardly of said back wall to provide said body portion with an open front, mounting flange means including upper and lower planar mounting flanges integral with and extending upwardly and downwardly respectively from said top and bottom walls, said upper and lower mounting flanges having upwardly and downwardly facing terminal edges, respectively, extending laterally between said side walls, said planar mounting flanges having corresponding first ends adjacent one of said side walls, upper and lower hinge leaf means each integral with the corresponding one of said upper and lower terminal edges of said first ends of said mounting flanges, each said hinge leaf means including a laterally narrow planar hinge leaf vertically spaced from the corresponding one of said top and bottom walls and extending horizontally forwardly of the corresponding mounting flange, a hollow door for closing said open front, said hollow door comprising front and back panels of plastic sheet material bonded together to provide a central portion bounded by a peripherally continuous hollow portion including a seam between said panel sheets extending about said hollow portion and rearwardly from said front panel toward said back panel, said panel sheets in the area of said seam having rearwardly facing terminal end edges transverse to said seam, and a hinge pin extending through each said hinge leaf and into said hollow portion of said door to pivotally mount said door on said body portion.

4,294,499

PULL-OUT GUIDE ASSEMBLY

Erich Röck, Höchst, and Bernhard Mages, Dornbirn, both of Austria, assignors to Julius Blum Gesellschaft m.b.H., Höchst, Austria


Filed Jun. 4, 1979, Ser. No. 45,264

Claims priority, application Austria, Jun. 6, 1978, 4097/78

Int. Cl.³ A47B 88/04, 88/14, 88/16

U.S. Cl. 312—334

9 Claims



1. A pull-out guide assembly for use on each of opposite sides of a drawer in an article of furniture of the type wherein a drawer is slidably insertable into and removable from a furniture body, said pull-out guide assembly comprising: separate plural first rail supports adapted to be fixed to a side of a drawer in spaced relationship with respect to each other along a direction of sliding movement of the drawer; separate plural second rail supports adapted to be fixed to a side of a furniture body in spaced relationship with respect to each other along said direction; a single rail directly supported by said plural first rail supports and by said plural second rail supports for relative sliding movement therebetween in said direction; an endless belt mounted on said rail for movement in said direction; and connecting means for fixing said endless belt to the drawer and to the furniture body, such that movement of the drawer in said direction will pull said endless belt in said direction and cause said rail to slide with respect to said plural first and second rail supports.

4,294,500

ROTARY ELECTRICAL JUNCTION ASSEMBLY


Jack A. Wilson, 502 N. Santa Fe, Salina, Kans. 67401

Filed Aug. 30, 1979, Ser. No. 71,191

Int. Cl.³ H01R 39/08, 39/14

U.S. Cl. 339—5 M

13 Claims



1. A rotary electrical junction device comprising: (a) stator means formed in at least two stator sections;

- (b) means-securing said stator sections around a stationary support member for selective mutual separation of said stator sections laterally outward from said stationary support member;
- (c) stator contact means on said stator means and electrically connected to stationary electrical means;
- (d) rotor means formed in at least two rotor sections;
- (e) means securing said rotor sections around a rotary support member for selective mutual separation of said rotor sections laterally outward from said rotary support member, said rotary support member being rotatably connected to said stationary support member;
- (f) rotor contact means on said rotor means and electrically connected to revolving electrical means associated with said rotary support member, said rotor contact means being in contact with said stator contact means when said junction device is assembled to thereby provide continuous electrical communication between said stationary electrical means and said revolving electrical means, and whereby the laterally outward separability of said stator and rotor sections facilitates the installation and removal of said rotary electrical junction device on and from said stationary and rotary support members;
- (g) said rotary support means being rotatable about an axis of rotation and wherein:
- (1) said stator means is separable along a stator split plane including said axis of rotation into a pair of stator halves; and
 - (2) said rotor means is separable along a rotor split plane including said axis of rotation into a pair of rotor halves;
- (h) said stator contact means being a plurality of slip rings, each of said slip rings being separable into a pair of slip ring halves;
- (i) said rotor contact means being a plurality of brushes, each brush being associated with a respective slip ring;
- (j) said brushes mounted in side-by-side relation on at least one brush rack;
- (k) annular guide means provided on each of said stator halves to receive said brush rack thereon with said brushes conductively engaging respective slip rings such that said brush rack may be revolved about said stator means; and
- (l) said rotor means including a split construction housing enclosing said stator means and said brush rack, said housing being mounted on said rotary support member and including brush rack engaging means whereby said brush rack is revolved about said stator means upon rotation of said housing.

4,294,501

PLUG MEMBER FOR THE ELECTRICAL CONNECTION OF AN APPLIANCE TO A BASE

Edouard Jouret, Bresso-Milano, Italy, assignor to Crouzet, Paris, France


Filed Nov. 26, 1979, Ser. No. 97,428

Claims priority, application France, Dec. 1, 1978, 78 34162

Int. Cl.³ H01R 13/639

U.S. Cl. 339—66 M

4 Claims



1. In an electrical connector including a plug member and a

base having conducting pins extending from the plug to be introduced into metal-sheathed holes in the base for electrically connecting the plug to the base, a centering stud adapted to be introduced in a centering hole in the base, and locking means for locking the plug member on the base, the improvement wherein the locking means comprises a hollow recess in said stud, at least two lateral openings through said stud between said recess and the outer surface of said stud, a U-shaped locking member mounted within said recess for sliding movement with respect to said stud between a locking and a release position, means in said recess for spreading apart the arms of the U-shaped locking member as it moves from said release to said locking position so that said arms project from the centering stud through said lateral openings to engage the wall of the centering hole in the base, and means on said plug to move said locking member between said release and locking positions.

4,294,502

BUSHING TERMINAL AND BUSS BAR


Walter L. Martin, Jr., Lexington, N.C., assignor to PPG Industries, Inc., Pittsburgh, Pa.

Filed Sep. 4, 1979, Ser. No. 72,702

Int. Cl.³ H01R 13/00

U.S. Cl. 339—112 L

6 Claims



1. An electrically conductive supply connector suitable for use in connecting a power transformer to a fiber glass forming bushing comprising a bushing terminal connector having an electrically conductive body provided with a slot adapted to receive the electrical supply terminal of a fiber glass bushing, means to circulate cooling fluid through said body, means to connect at least two tubular bus bars to said body, a metal block on the opposite ends of said bus bars provided internally with a cooling fluid passage and in communication with the bus bars so that fluid can be circulated from said body through one of said bus bars and said block and back to said body, a transformer terminal connector having a solid electrically conductive core provided with two arm like extensions forming a recess therein and adapted to receive said body, means to clamp said body in said recess and form an electrical connection between said extension and said body and means in said core to connect said core to the secondary of a power transformer.

4,294,503

LOCKING MEANS FOR A LAMP HOLDER

Gilbert R. Lieberman, Hampstead, Canada, assignor to Gilbert Products, Pointe-aux-Trembles, Canada

Filed Jan. 11, 1980, Ser. No. 111,372

Claims priority, application Canada, Dec. 7, 1979, 341477


Int. Cl.³ H01R 13/629

U.S. Cl. 339—119 L

13 Claims

1. A locking arrangement for a lamp holder which has a threaded opening to receive a threaded component and having an axis, the locking device comprising:
 - a locking member captively carried by the lamp holder and

which is mounted for limited movement in a direction normal to the axis of the threaded opening, the locking member having opposed inwardly facing edges for contact with a threaded component into the lamp holder,



the lamp holder comprising a body portion and a cap portion, the locking member being positioned in a cavity provided in the cap portion and held captively therein by a retaining cap, and the locking member permitting threaded insertion of the threaded component and preventing inadvertent threaded removal.

4,294,504

HIGH VOLTAGE CABLE

Lothar Siewerdt, Eggenstein-Leopoldshafen, Fed. Rep. of Germany, assignor to Kernforschungszentrum Karlsruhe GmbH, Karlsruhe, Fed. Rep. of Germany


Filed Jul. 13, 1979, Ser. No. 57,373

Claims priority, application Fed. Rep. of Germany, Jul. 13, 1978, 2830736

Int. Cl.³ H01R 15/12; H01B 11/18

U.S. Cl. 339—132 R

7 Claims



2. A high voltage cable and support therefor for transmitting current pulses up to 10 kiloamperes at temperatures in the range from 4° K. to 300° K.,

said cable comprising at least one conductive element including:

- a flexible inner conductor;
- an insulating sheath surrounding said inner conductor, said inner conductor moving freely within said insulating sheath;
- a flexible outer conductor encasing said insulating sheath, the cross-sectional area of said outer conductor being relatively small compared to that of said inner conductor, said inner and outer conductors being electrically conductively connected together; and
- an insulating jacket encasing said outer conductor and insulating sheath without the formation of gas bubbles within said insulating jacket; and

said support structure comprising a plug-in coupling including:

- a cast resin block having a plurality of said conductive elements encased therein;
- a soldering sleeve having a threaded opening therein positioned within the bore in said block, said inner conductor being soldered within the opening of said soldering sleeve and said insulating jacket surrounding said sleeve;
- an annular flange enclosing said block; and
- a contact pin threaded into the opening of said soldering sleeve.

4,294,505

TERMINAL CONNECTOR FOR AN ELECTRIC STORAGE BATTERY

Edward N. Gaffney, Sutton Coldfield, England, assignor to Lucas Industries Limited, Birmingham, England


Filed May 3, 1979, Ser. No. 35,766

Claims priority, application United Kingdom, May 12, 1978, 19141/78

Int. Cl.³ H01R 11/26

U.S. Cl. 339—231

7 Claims



1. A terminal connector for an electric storage battery comprising a body having a bore therein arranged to receive a terminal post, an electric cable, a conductive element to which the electric cable is secured with the cable being presented to said bore, and an operating member movable relative to the body and said conductive element and carrying said conductive element, the operating member being movable relative to the body, while the body remains stationary, to move the conductive element and the electrical cable relative to said bore whereby the electrical cable can be moved into and out of electrical contact with a terminal post received in said bore in use.

4,294,506

OPTICAL SCANNER WITH ANAMORPHIC OPTICAL SYSTEM

Nobuoto Hattori, Hachioji, Japan, assignor to Olympus Optical Company Ltd., Tokyo, Japan


Filed Dec. 15, 1978, Ser. No. 969,849

Claims priority, application Japan, Dec. 26, 1977, 52/156954

Int. Cl.³ G02B 27/17

U.S. Cl. 350—6.8

8 Claims



1. An optical scanner comprising a laser unit for producing a collimated light beam, a multi-faceted rotating mirror for

receiving said collimated light beam and reflecting it to a scanning surface, an anamorphic optical system disposed between said rotating mirror and said scanning surface for focussing said beam on the latter surface in a scan direction and for focussing said beam on a plane located short of said scanning surface in a direction perpendicular to said scan direction, said anamorphic optical system comprising a first lens which has a focussing power only in a direction perpendicular to said scan direction and a second lens, said first and second lenses disposed between said rotating mirror and said plane for focussing said beam on said plane at a location short of said scanning surface, and an optical element disposed between said plane and said scanning surface and having a focussing power only in a direction perpendicular to said scan direction and having a magnification of projection which is equal to or less than unity, said optical element projecting said beam which is focussed on said plane onto said scanning surface to focus said beam thereon.

4,294,507

CONTROLLABLY DEFORMED ELASTIC WAVEGUIDE ELEMENTS


Mark Johnson, Ossining, N.Y., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Jan. 25, 1980, Ser. No. 115,477

Int. Cl.³ G02B 5/14

U.S. Cl. 350—96.13

41 Claims



1. An active waveguide element, comprising: an elastic two dimensionally guiding waveguide for propagating wave energy therethrough along a first path, said wave energy having immediately adjacent rays each experiencing the same effective propagation path lengths; and means for stretchably deforming said waveguide to a different configuration such that said adjacent rays would experience effective propagation path lengths different from each other if said wave energy were to still propagate along said first path, said wave energy propagating instead along a second different path through said waveguide when said waveguide is stretchably deformed to said different configuration such that said adjacent rays each experience the same effective propagation path length also when said wave propagates along said second path.

4,294,508

OPTICAL MULTIPLEXER/DEMULTIPLEXER

Charles R. Husbands, Acton, Mass., assignor to The United States of America as represented by the Secretary of the Air Force, Washington, D.C.

Filed Aug. 22, 1979, Ser. No. 68,822


Int. Cl.³ G02B 5/14

U.S. Cl. 350—96.15

17 Claims

1. An optical multiplexer/demultiplexer comprising a body having a preselected index of refraction, said body having a pair of reflective sides and a pair of non-reflective sides, means associated with one of said non-reflective sides for directing a single beam of radiant energy at a predetermined angle with respect to said one non-reflective side into or out of said body, said single beam of radiant energy containing at least two preselected wavelengths, means associated with the other of said non-reflective sides for directing at least two beams of

radiant energy, each at predetermined angles with respect to said other non-reflective side into or out of said body, each of said two beams of radiant energy containing only one of said preselected wavelengths, respectively, said two beams of radiant energy being spaced apart a preselected distance along said other non-reflective side, and each of said predetermined angles lying between angles of complete refraction and complete reflection, whereby when said single beam of radiant energy is directed into said body through said one non-reflective side, said multiplexer/demultiplexer operates as a demultiplexer with said single beam of radiant energy being separated within



said body into said two beams of radiant energy, each of said two beams containing only one of said preselected wavelengths, respectively, said two beams reflecting off at least one of said reflective sides of said body before being output from said other non-reflective side, and when said two beams of radiant energy are directed into said body through said other non-reflective side, said multiplexer/demultiplexer operates as a multiplexer with said two beams of radiant energy being reflected off at least one of said reflective sides of said body and combining into said single beam of radiant energy at said one non-reflective side of said body before being output therefrom.

4,294,509

OPTICAL CIRCULATORS

Tsukasa Nagao, 4-75, Mabari, Yokosuka-shi, Kanagawa-ken, Japan


Filed Dec. 6, 1979, Ser. No. 100,893

Claims priority, application Japan, Dec. 8, 1978, 53-152308

Int. Cl.³ G02F 1/00; G02B 5/30

U.S. Cl. 350—96.15


27 Claims



1. An optical circulator comprising: a plurality of optical fiber transmission lines for guiding a signal light, a magneto-optic structure made of magneto-optic material displaying optical anisotropy under a biasing magnetic field to produce a given Faraday rotation of said signal light on passage through said magneto-optic structure,

a signal coupler having a plurality of openings which define polarized Brewster windows formed on a common region in rotational symmetry around a symmetric axis, said transmission lines being coupled to the windows of the common region in rotational symmetry around the symmetric axis to transmit said signal light through said windows with respectively given angles of polarization, a first reflecting mirror formed on said common region except said openings of said signal coupler, said first mirror being positioned on said symmetric axis facing said magneto-optic structure, a second reflecting mirror being positioned facing the rear surface of said magneto-optic structure, thereby said reflecting mirrors forming a reflection-type resonator, and means for magnetically biasing said magneto-optic structure in the direction parallel to said symmetric axis.

said second light guides for illuminating an object, and a lens system arranged between said first and second light guides; the emerging end surface of said first light guide being arranged in the vicinity of the front focal point of said lens system, the incidence end surface of said second light guide being arranged



4,294,510

SEMICONDUCTOR FIBER OPTICAL DETECTION


Terry I. Chappell, Amawalk, N.Y., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Dec. 10, 1979, Ser. No. 101,960

Int. Cl.³ G02B 5/172

U.S. Cl. 350—96.17

8 Claims



in the vicinity of the rear focal point of said lens system with the diameter of the end surface of said first light guide being larger than that of the incidence end surface of said second light guide; and said optical system being so designed as to satisfy the following condition:

$$\frac{2r_1}{f} \geq 1$$

wherein the reference symbol r_1 represents radius of the emerging end surface of said first light guide and the reference symbol f designates focal length of said lens system.

1. A coupler for converting light signals transmitted by an optical fiber to electrical signals wherein the optical path in said coupler is longer than the length dimension of said coupler comprising in combination:

a coupler body of semiconductor material having a length dimension governed by the optical absorption coefficient of said semiconductor material and the wave length of said light signals and having width and height dimensions less than said length dimension; a region of p conductivity type along a first side of said body essentially parallel to said length dimension and having an external electrical connection; a region of n conductivity type along a second side of said body opposite to said first side and having an external electrical connection; internal reflection means on each of the remaining sides of said body that are essentially parallel to said length dimension; and alignment means positioning the end of an optical fiber adjacent one end of said body with the axis of said optical fiber parallel with said length dimension of said body.

4,294,512

OPTOELECTRONIC INTERFACE APPARATUS


Maurus C. Logan, Elizabeth, N.J., assignor to Thomas & Betts Corporation, Raritan, N.J.

Filed Jan. 14, 1980, Ser. No. 111,943

Int. Cl.³ G02B 5/14

U.S. Cl. 350—96.20

11 Claims



1. Optoelectronic apparatus comprising a housing having an upstanding wall defining an entry aperture, said housing supporting a first disconnect electrical contact distal from said wall and interiorly of said entry aperture, and a fiber optic assembly including a fiber optic cable, transducer means for conversion between light and electrical energy in registry with said cable, a second disconnect electrical contact coupled to said transducer means and configured to couple to said first disconnect electrical contact, and ferrule means for securing said cable and said transducer means to one another, said fiber optic assembly being of cross-section less than the cross-section of said entry aperture, whereby said fiber optic assembly is insertable through said entry aperture and said second disconnect contact may be coupled to said first disconnect contact within said housing remotely from said entry aperture.

4,294,511

CONNECTING OPTICAL SYSTEM FOR LIGHT GUIDES

Nobuo Yamashita, Tama, and Miwako Maeda, Hino, both of Japan, assignors to Olympus Optical Co., Ltd., Tokyo, Japan

Filed Jul. 5, 1979, Ser. No. 55,035

Claims priority, application Japan, Jul. 10, 1978, 53-83825

Int. Cl.³ G02B 5/16

U.S. Cl. 350—96.18

1 Claim

1. An optical system for connecting light guides for endoscopes comprising a first light guide which is arranged on the side of the light source and functions to transmit rays from said light source, a second light guide which receives the rays transmitted through said first light guide and which emerge from the emerging end surface thereof, transmits said rays and allows said rays to emerge from the emerging end surface of


4,294,513

OPTICAL SENSOR SYSTEM

David E. Nelson, and John V. Bouyoucos, both of Rochester, N.Y., assignors to Hydroacoustics Inc., Rochester, N.Y.
Filed Sep. 11, 1979, Ser. No. 74,270
Int. Cl.³ G02B 5/172

U.S. Cl. 350—96.29

29 Claims



1. An optical sensor system which comprises an optical waveguide, first and second means each for detecting light which is propagated along different paths in said waveguide to reach said detection means, means for deforming said waveguide to provide a bias deformation which, on the average, approximately equally partitions the light energy which propagates to said detecting means along said different paths, and to modulate the partitioning of light energy between said paths in response to the parameter to be sensed, and means for providing an electrical output corresponding to the difference between light energies detected by said first and second detection means.

4,294,514

LIGHT-WAVE GUIDES AND METHOD OF PRODUCING SAME

Hartmut Schneider, Munich, Fed. Rep. of Germany, assignor to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany


Filed Sep. 10, 1979, Ser. No. 73,724

Claims priority, application Fed. Rep. of Germany, Oct. 4, 1978, 2843276

Int. Cl.³ G02B 5/14; C03B 37/00

U.S. Cl. 350—96.31

5 Claims



5. A low loss light-wave guide comprising a fiber composed of a substantially chemically homogeneous material having a given density along the center axis thereof and a density lower than said given density at peripheral surface areas thereof whereby such fiber exhibits a radially outwardly decreasing refractive index.

4,294,515

VIRTUAL IMAGE DISPLAY APPARATUS


Arthur Kaufman, 19 Covlee Dr., Westport, Conn. 06880
Filed Mar. 23, 1979, Ser. No. 23,160
Int. Cl.³ G02B 27/14, 5/10

U.S. Cl. 350—174

18 Claims

1. A virtual image display apparatus comprising a mirror in the shape of a substantially concave segment of a hemisphere

said spherical mirror having an optical axis and a focus, an image source means for said mirror segment, and an image display face on said image source disposed substantially per-



pendicular to said optical axis but located off said axis and substantially on the same side of the axis as the line of sight of an observer and between said focus and said mirror segment.

4,294,516

MOVING PICTURE APPARATUS


Philip A. Brooks, 436 NW. 46th Terrace, Oklahoma City, Okla. 73118

Filed Sep. 11, 1978, Ser. No. 941,146

Int. Cl.³ G02F 1/133

U.S. Cl. 350—335

1 Claim



1. An apparatus for creating the effect upon a viewer of a three-dimensional moving image, comprising:

a display structure including a stacked array of a plurality of transparent members and liquid crystal members alternately positioned so that said stacked array has a first end thereof defined by a respective one of the transparent members and a second end thereof defined by another respective one of the transparent members and said stacked array also has a liquid crystal member disposed between consecutive transparent members whereby there are a plurality of sets of facing surfaces of consecutively stacked transparent members, each set being disposed adjacent the two major surfaces of a respective one of the liquid crystal members;

a plurality of pairs of image producers associated with said display structure, each pair of said image producers comprising solely:

a first transparent electrode having a predetermined shape in the configuration of a total pictorial image to be displayed, said first transparent electrode being disposed on a respective one of the facing surfaces of a respective one of the sets of facing surfaces; and

a second transparent electrode having a predetermined shape which is the mirror image of the predetermined shape of said first transparent electrode, said second transparent electrode being disposed in alignment with said first transparent electrode on the other facing surface of the respective set of facing surfaces with which said first transparent electrode is associated; and

a scanning controller means, electrically connected to said plurality of pairs of image producers, for sequentially activating at a selectable rate said image producers so that each set of first and second transparent electrodes be-

comes periodically visible to the viewer so that the effect of motion is imparted thereto.

4,294,517

ELECTROOPTICAL DEVICE WITH ENCAPSULATED SELF-LUMINOUS BACKLIGHT ASSEMBLY



John Jakubek, Watertown, Conn., assignor to Timex Corporation, Waterbury, Conn.

Filed May 14, 1979, Ser. No. 39,095

Int. Cl.³ G02F 1/133

U.S. Cl. 350—345

10 Claims



1. An illuminated electrooptical device, comprising:

(a) an electrooptic display;
(b) a unitary pod member-backlight assembly comprising,
(1) a pod member located behind and supporting the display, said pod member including a receptacle in a surface facing the display, and
(2) a backlight comprising at least one self-luminous light source encapsulated in situ within a substantially transparent carrier medium in the receptacle with the receptacle acting as a mold during encapsulation.

4,294,518

DUAL MODE LIGHT VALVE DISPLAY

James M. O'Connor, Farmington, and George W. Goodrich, Bloomfield Hills, both of Mich., assignors to The Bendix Corporation, Southfield, Mich.

Filed Nov. 30, 1978, Ser. No. 965,117

Int. Cl.³ G02F 1/17

U.S. Cl. 350—357


18 Claims

1. A dual mode display comprising:
a front transparent window having a front and a rear surface, said rear surface having a first set of transparent electrically conductive electrodes arranged in a predetermined pattern disposed thereon;
a rear transparent window disposed parallel to said, front window said rear window having a front surface and a rear surface, the front surface of said rear window further

having deposited thereon a second set of electrically conductive transparent electrodes corresponding to said first set of electrically conductive transparent electrodes and in registration therewith;

a semi-transparent reflective substrate disposed intermediate said front and rear windows and parallel thereto, said semi-transparent reflective substrate having an electrically conductive front surface facing said front window, and a rear surface facing said rear window, the rear surface of said semi-transparent substrate having disposed thereon a third set of transparent electrodes corresponding to said first set of transparent electrodes and in registration therewith;

a first layer of electro-responsive material filling the space between said front window and said semi-transparent substrate, said first layer of electro-responsive material



having a first optical density in the absence of an electrostatic field, and a second optical density in response to an electrostatic field applied thereacross;

a second layer of electro-responsive material filling the space between said semi-transparent substrate and said rear window, said second layer of electro-responsive material having a third optical density in the absence of an electrostatic field and a fourth optical density in response to an electrostatic field applied thereacross;

means for sealing said front window, said semi-transparent substrate and said rear window in said parallel relationship; and

means for individually conducting electrical potentials to said first, second and third sets of electrically conductive transparent electrodes and the electrically conductive front surface of said semi-transparent reflective substrate.

4,294,519

COLOR DENSITY STABILIZER FOR ELECTROCHROMIC DISPLAY

Sadakatsu Hashimoto, Nara, Japan, assignor to Sharp Kabushiki Kaisha, Osaka, Japan


Filed May 23, 1979, Ser. No. 41,637

Claims priority, application Japan, May 26, 1978, 53-64173

Int. Cl.³ G02F 1/17; 350 357

U.S. Cl. 350—357

9 Claims



1. A driving circuit for developing driving signals to drive an electro-optical device, said device including an optical

element, said element being colored in response to said driving signals, the coloration of said element depending on the surrounding temperature, said driving circuit comprising: monitoring means for monitoring variations in the surrounding temperature; and controlling means responsive to the monitoring means for controlling the time interval of application of the driving signals being applied to the electro-optical device in accordance with the variations in the surrounding temperature monitored by the monitoring means; whereby a single, uniform depth of color of the optical element is maintained regardless of the variations in the surrounding temperature monitored by the monitoring means.

4,294,520

ELECTROCHROMIC DISPLAY DEVICE

Eiichi Inoue, Tokyo; Isamu Shimizu, Yokohama, and Makoto Shizukuishi, Kamakura, all of Japan, assignors to Fuji Photo Film Co., Ltd., Minami-ashigarah, Japan

Filed Sep. 6, 1979, Ser. No. 73,032

Claims priority, application Japan, Sep. 6, 1978, 53-110171

Int. Cl.³ G02F 1/17

U.S. Cl. 350—357

12 Claims



1. An electrochromic display device comprising a transparent electrode, a laminate structure provided on said electrode comprising a vapor deposited layer of an electrochromic substance and a second vapor deposited mixed layer of chromium (III) oxide and an oxide selected from the group consisting of a transition metal oxide and silicon oxide and a counter electrode provided on said laminated structure wherein said oxide is present in an amount of 5 to 80% of said second vapor deposited mixed layer.

4,294,521

REAR STOP TYPE ZOOM LENS

Yoshikazu Doi, Yutaka Sakai, and Kazunori Ohno, all of Omiya, Japan, assignors to Fuji Photo Optical Co., Ltd., Japan


Filed Aug. 30, 1979, Ser. No. 71,042

Claims priority, application Japan, Sep. 1, 1978, 53-107735

Int. Cl.³ G02B 15/16

U.S. Cl. 350—426

2 Claims



1. A rear stop type zoom lens, comprising a front lens group possessing negative refracting power and a rear lens group possessing positive refracting power relative to the object side which two lens groups effect variation in magnification by being moved in opposite directions on the optical axis of the entire lens, a diaphragm fixed externally and to the rear of the rear lens group, the front lens group consisting of two biconcave lenses and one convex lens and the rear lens group consisting of five lenses, the first three in order being convex

meniscus lenses each having its convex surface on the object side, and satisfying the following conditions:

- (1) $-2.4 < F_A < -2.0$
- (2) $0.13 < d_{11} + d_{12} + d_{13} < 0.19$
- (3) $vd_3 < 30.0$, $vd_8 < 30.0$
- (4) $0.35 < 1/r_4 < 0.55$
- (5) $1.7 < 1/r_9 < 1.9$

wherein, r_i ($i=1, 2, \dots$) stands for the radius of curvature of the lens surface of the respective lenses beginning from the foremost surface of the front lens group, d_i for the center thickness of the lenses or the air gaps between the adjacent lenses, vd_i for the Abbe number of the lenses, and F_A for the focal length of the front lens group as a whole.

4,294,522

VISION THERAPEUTIC APPARATUS


John T. Jacobs, 1318 Rimrock Dr., San Jose, Calif. 95120

Filed Aug. 16, 1978, Ser. No. 934,381

Int. Cl.³ A61B 3/00; A61H 1/02

U.S. Cl. 351—2

6 Claims



1. Vision therapeutic apparatus comprising means for automatically generating sequences of different images at different spaced apart locations, different ones of the images displayed at one of the locations providing preselected information when matched with preselected ones of the images displayed at another of said locations, the images at each of said locations being selected for display on a non-predictable basis among various other images not providing said preselected information, whereby said matching occurs on a non-predictable basis, and means for detecting responses from the user indicative of his observations of said images.

4,294,523

THREE-DIMENSIONAL DISPLAY APPARATUS

Edward A. Woloshuk; Gregory J. Walz, both of New York, and Robert O. Kretschmar, Brooklyn, all of N.Y., assignors to The Zyntrax Corporation, New York, N.Y.

Filed Oct. 19, 1979, Ser. No. 86,393

Int. Cl.³ G03B 21/32


U.S. Cl. 352—86

20 Claims

1. Apparatus for forming and displaying a three-dimensional image of a selectable portion of a three-dimensional object, comprising:

- a. a series of two-dimensional photographs of successive sections of said object, said photographs being arranged in a predetermined order corresponding to the relationship that said successive sections bear to each other;
- b. illuminating means;
- c. an optical system defining an optical path extending from said illuminating means;
- d. means supporting said series of photographs and operable to move said series of photographs repeatedly through said optical path in said predetermined order and at a rate such that the series moves through the path within the period of persistence of vision, whereby said photographs are successively positioned for projection along said path;

- e. stroboscopic means for flashing said illuminating means as a photograph is aligned with said path;
- f. a projection screen disposed in said optical path and adapted to move along the optical path toward and away from the photographs moving through the optical path, said projection screen having its surface formed with a curved cross-section and being rotatable about an axis displaced from the center of curvature of the cross-section, which axis is disposed substantially at right angles to the optical path, said rotation being in synchronization



with the motion of said photographs so that said photographs are projected onto the screen at successive positions thereof, and form a series of images which appear to an observer having persistence of vision to be a composite three-dimensional image;

wherein the improvement comprises:

- g. means, including selection means manually settable at any time, for controlling said illuminating means to illuminate only selected photographs of said series during each movement of the series through said optical path.

4,294,524

IMAGE OR PICTURE PROJECTING SYSTEM USING ELECTRONICALLY CONTROLLED SLIDES

Michael Stolov, 25 Hapoel St., Nof-Yam, Herzlia, Israel Division of Ser. No. 943,982, Sep. 20, 1978, Pat. No. 4,222,641.


This application May 16, 1980, Ser. No. 150,520

Claims priority, application Israel, Jun. 29, 1978, 55032

Int. Cl.³ G03B 21/00, 21/14; H04N 9/31

U.S. Cl. 353—84

17 Claims



1. A changeable image or picture system for producing complex, colored, images or pictures, the system comprising a light source; liquid crystal display means for displaying images or pictures spaced from said light source; at least one electronically controlled liquid crystal multiple color filter positioned between said light source and said liquid crystal display means; a light scattering means positioned between said at least one electronically controlled multiple color filter and said liquid crystal display means for diffusing light which has passed through said at least one electronically controlled multiple color filter into light of substantially uniform intensity at any given time; a plurality of electrodes operatively associated

with said liquid crystal display means; means for supplying selectively to individual ones of said electrodes associated with said liquid crystal display means voltages to make selected portions or said liquid crystal display means transparent thereby selectively passing area portions of light from said means for diffusing; a screen; and lens means for projecting the area portions of light passing through said liquid crystal display means onto said screen; whereby colored, complex images or pictures appear on the screen.

4,294,525

CAMERA HAVING A DIGITAL EXPOSURE VALUE DISPLAY DEVICE

Osamu Maida, Tokyo, Japan, assignor to Nippon Kogaku K.K., Tokyo, Japan


Filed Oct. 14, 1980, Ser. No. 196,358

Claims priority, application Japan, Oct. 20, 1979, 54-135507

Int. Cl.³ G03B 7/091, 9/62, 17/18

U.S. Cl. 354—23 D

9 Claims



1. A camera having a digital exposure display device (C_1-C_n , 14, 15) for comparing a voltage associated with an exposure value such as a shutter time value or an aperture value obtained from exposure operating means (P, 1, 2, 3, 4, 5, 6, A1) with a plurality of reference voltages produced by a reference voltage generating circuit (F1) and thereby converting the exposure value into a digital signal and digitally displaying said exposure value on the basis of said digital signal, said camera further having a digital fixed point match type exposure display device comprising:

- an exposure value setting circuit (T) for generating a voltage associated with a manually set exposure value;
- differential amplifier circuit means (D) for generating a voltage including a voltage corresponding to the difference between the voltage of said exposure value setting circuit (T) and the voltage obtained from said exposure operating means;
- forming means (11-14) for forming a first comparison voltage and a second comparison voltage greater than said first comparison voltage by using the output voltage of said reference voltage generating circuit;
- comparing means (C) for comparing the comparison voltage of said forming means (11-14) with the output of said differential circuit means (D) and producing a first signal variable in condition depending on whether said output is smaller or greater than said first comparison voltage and a second signal variable in condition depending on whether said output is greater or smaller than said second comparison voltage; and
- display means (14, 15) operative to effect a display based on said first and second signals of said comparing means.

4,294,526

AUTOMATIC FOCUSING CAMERA COMBINED WITH MANUAL FOCUSING SYSTEM

Tadashi Nakagawa, Yotsukaido, Japan, assignor to Seiko Koki Kabushiki Kaisha, Tokyo, Japan


Filed Sep. 17, 1980, Ser. No. 188,115

Claims priority, application Japan, Oct. 27, 1979, 54-148913[U]

Int. Cl.³ G03B 3/10, 7/08

U.S. Cl. 354—25

1 Claim



1. An automatic focusing camera comprising an automatic focus detecting electronic circuit capable of detecting the distance between the camera and an object and automatically focus the taking lens, an electromagnet controlled by said electronic circuit, a release member actuated in interlocking relation with the shutter release operation and operative to actuate the shutter at the end of the operation of the same, an armature lever controlled by said electromagnet to operate between a resting position and a taking lens focusing position in interlocking relation with said release operation, a locking means which locks the shutter actuating operation of said release member with said armature lever at said resting position and allows the actuation of the shutter at the taking lens focusing position, and a selecting means for selecting between automatic focusing mode and manual focusing mode and operative to retract said locking means to a position where said locking means will not lock said release member when said manual focusing mode is selected.

4,294,527

MOTOR DRIVEN CAMERA

Akihiko Hashimoto; Yukio Nakajima, both of Hachioji; Tamotsu Koiwai, Shimosuwa, and Toyohiko Kimura, Hachioji, all of Japan, assignors to Olympus Optical Company, Ltd., Japan

Filed Jan. 7, 1980, Ser. No. 109,764

Claims priority, application Japan, Feb. 2, 1979, 54-11260


Int. Cl.³ G03B 1/12, 3/00

U.S. Cl. 354—25

14 Claims

1. A motor driven camera, comprising:
a camera body;
a film winding shaft disposed in said camera body;
a film rewind shaft disposed in said camera body parallel to said film winding shaft;
a single reversible drive motor disposed in said camera body, said motor having an output shaft;
a first connection shaft disposed in a direction perpendicular to the direction of extension of said film winding shaft and said film rewind shaft; said first connection shaft having two ends;
a motor drive transmission mechanism for transmitting drive from said motor to said first connection shaft;
a film winding mechanism adjacent one said end of said first

connection shaft for selectively transmitting drive from said first connection shaft to said film winding shaft; and



a film rewind mechanism adjacent the other said end of said first connection shaft for selectively transmitting drive from said first connection shaft to said film rewind shaft.

4,294,528

AUTOMATICALLY CONTROLLED ELECTRONIC FLASH DEVICE

Yoshiharu Ohta, and Mikio Naya, both of Izumi, Japan, assignors to Minolta Camera Kabushiki Kaisha, Osaka, Japan


Filed Aug. 20, 1979, Ser. No. 67,968

Claims priority, application Japan, Aug. 23, 1978, 53-103054

Int. Cl.³ G03B 15/05; H05B 41/32

U.S. Cl. 354—33

8 Claims



1. An automatic electronic flash device for use with a camera, comprising:

a housing;
an electronic flash tube provided in said housing;
a battery provided in said housing as a source of electric supply;
a DC-DC converter circuit connected to said battery for generating a high DC voltage;
a capacitor connected to said DC-DC converter circuit to be charged up to the DC voltage and connected to said flash tube to energize said tube when discharged;
a manual switching member provided on said housing, said switching member having a plurality of settable positions; calculator means carried on said housing for calculation of a plurality of combinations of aperture settings and distance settings in response to a film speed setting;
a plurality of illuminators each of which is associated with said calculator means for indication of one of said combinations calculated by said calculator means;
a control circuit having a light receiving element, said control circuit adapted for adjusting the amount of light emitted from said flash tube in accordance with a film speed setting and the intensity of light which is reflected

by an object to be photographed and received by said light receiving element during the firing of said flash tube; means connected to said control circuit for adjusting the amount of light emitted from said tube in accordance with the setting of said manual switching member; and means interlocked with said manual switching member for selectively and directly connecting one of said illuminators to said battery for energization thereof in accordance with the setting of said manual switching member.

4,294,529

CAMERA

Yasuhisa Sato, Kawasaki; Sadahiko Tsuji, and Kazuo Ishikawa, both of Yokohama, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan


Filed Aug. 28, 1979, Ser. No. 70,659

Claims priority, application Japan, Sep. 7, 1978, 53-122915[U]; Sep. 7, 1978, 53-122916[U]

Int. Cl.³ G03B 17/20

U.S. Cl. 354—53

8 Claims



1. A camera apparatus, comprising:
a photo-taking optical system;
a finder optical system including a focusing screen;
a diffraction device arranged near one of a plurality of predetermined planes including a focal plane of said photo-taking optical system and an optically conjugate plane thereto and having recorded therein on indicium to be displayed;
a pair of optical members,
said diffraction device being supported and sealed between the two optical members;
a light source for illuminating said diffraction device from an oblique direction; and
an electrical power circuit for energizing said light source.

4,294,530

MOTORIZED PHOTOGRAPHIC SYSTEM AND CAMERA AND POWER DRIVE UNIT THEREFOR

Tomonori Iwashita, Fuchu; Hidehiko Fukahori, Kawasaki, and Yukio Mashimo, Tokyo, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan

Filed Jul. 19, 1979, Ser. No. 59,233

Claims priority, application Japan, Jul. 28, 1978, 53-92318


Int. Cl.³ G03B 1/18, 1/60

U.S. Cl. 354—173

15 Claims

1. A motor drive unit for a camera comprising:
an electric motor,
a control circuit connected to said electric motor to control the electrical power supply to said motor, said control circuit having a control input and responsive to at least an electrical control signal applied to said input for controlling the electrical power to said motor,
terminal means connected to the input of said control circuit to receive from the camera a combination signal including a first electrical signal indicating completion of a winding operation for advancing film one frame and a second electrical signal indicating completion of a rewinding operation for rewinding film in the camera, the combination signal representing winding completion signal when the first and second signals assume one set of states, and

rewind completion signal when the first and second signals assume another set of states, and



a motion transmitting mechanism for transmitting the driving force of said electric motor to the camera to perform a winding or rewinding operation.

4,294,531

AUTO-FOCUS MOVIE CAMERA


Edwin K. Shenk, Westford, Mass., assignor to Polaroid Corporation, Cambridge, Mass.

Continuation of Ser. No. 899,785, Apr. 25, 1978, abandoned, which is a continuation-in-part of Ser. No. 729,289, Oct. 4, 1976, abandoned. This application Sep. 26, 1979, Ser. No. 79,052

Int. Cl.³ G03B 3/10

U.S. Cl. 354—195

13 Claims



1. In a camera having an adjustable lens for directing scene light onto a focal plane of a recording station when a shutter mechanism is operated, the lens having a predetermined lens/-subject function that relates the desired focus position of the lens to the subject distance, and also having range finding means operable for generating a range parameter related to subject distance, the improvement comprising:

a programmer periodically operating the range finding means for generating a range parameter to track changes in subject distance;
first means responsive to the generation of a range parameter for generating a first number representative of the desired focus position of the lens;
a first register for storing said first numbers generated by said first means whereby the contents of this register varies in response to changes in subject distance at a rate dependent on the repetition rate of generation of said range parameters;
second means responsive to the position of the lens for generating a second number representative of the actual position of the lens;
a second register for storing said second number representative of lens position whereby the contents of the second

register varies in response to changes in the position of the lens at a rate determined by the rate of change of lens position;

a comparator for comparing the contents of the first and second register, the comparator having first and second terminals, a signal appearing on the first terminal only when the contents of the first register exceeds the contents of the second register, and a signal appearing on the second terminal only when the reverse relationship between the contents occurs;

sample-and-hold means associated with each terminal for sampling and storing the state thereof as determined by the presence or absence of a signal thereon, logic means associated with each sample-and-hold means for producing a control signal when either sample-and-hold means has a majority of a predetermined number of samples in a state indicated by the presence of a signal; and

drive means responsive to the output of the comparator for causing the lens to track changes in subject distance, the drive means including a reversible motor operatively associated with the lens, a forward motor control for operating the motor in one direction to thereby move the lens in one direction, and a reverse motor control responsive to a signal on the second terminal for operating the motor in the opposite direction so as to move the lens in its opposite direction, the two motor controls being respectively responsive to the control signals of the sample-and-hold means for operating the motor in a direction that moves the lens mount toward a focus position at which the signals on the terminals are nulled.

4,294,532

SHUTTER BLADE DEVICE FOR FOCAL PLANE SHUTTER

Tadashi Nakagawa, Shikawatashi, Japan, assignor to Seiko Koki Kabushiki Kaisha, Tokyo, Japan


Filed Apr. 23, 1980, Ser. No. 143,008

Claims priority, application Japan, Apr. 24, 1979, 54/51085

Int. Cl.³ G03B 9/40

U.S. Cl. 354-246

8 Claims



1. In a focal plane shutter for a single lens reflex camera having on the side of the shutter aperture two blade groups each consisting of a plurality of separate blades adapted to operate sequentially in exposure operation and located adjacent to the focal plane, a shutter blade device for the focal plane shutter including said two blade groups having at least some of blades formed of thin synthetic resin plates, and a reflex mirror, and characterized by a shielding member provided between the reflex mirror and said blade groups and adapted to retract from an aperture shielding position during the exposure operation of said two blade groups and return to an aperture shielding position before and after the exposure operation.

4,294,533

APPARATUS FOR PRE-CONDITIONING FILM


Martin D. Bratt, Old Bridge, and John F. Oakley, Parlin, both of N.J., assignors to E. I. Du Pont de Nemours and Company, Wilmington, Del.

Division of Ser. No. 889,420, Mar. 23, 1978, abandoned. This application Aug. 3, 1979, Ser. No. 63,471

Int. Cl.³ G03D 5/06

U.S. Cl. 354-318

6 Claims



1. In an apparatus for developing film, a pre-conditioner comprising: a scrub roll; a second roll in engagement with the scrub roll for transporting a film to be developed therebetween; a conduit positioned above and provided with perforations directed at said scrub roll; a source of flushing liquid connected to said conduit; and drive means coupled to said rolls for their co-current rotation at different surface speeds.

4,294,534

MULTIPLE FUNCTION REPRODUCTION APPARATUS


Christopher Snelling, Penfield, N.Y., assignor to Xerox Corporation, Stamford, Conn.

Filed Jan. 14, 1980, Ser. No. 111,519

Int. Cl.³ G03G 15/00

U.S. Cl. 355-3 R

23 Claims



12. In a copying apparatus having a photoreceptor, means to charge said photoreceptor in preparation for imaging, exposure means for exposing said charged photoreceptor to produce latent electrostatic images, developing means for developing said latent electrostatic images, and transfer means for transferring said developed images to copy substrate material, the improvement comprising:

a high intensity light beam; means to focus said light beam onto said photoreceptor; scanning means astride the path of said light beam for line scanning said light beam across said photoreceptor; radiation detection means for converting scattered radiation resulting from scanning developed images on said photoreceptor with said beam to image signals representative of the image scanned; and lens means for focusing said scattered radiation onto said radiation detection means.

4,294,535

ELECTROSTATIC COPYING APPARATUS

Kenzo Ariyama, Syozo Miyawaki, and Takashi Murakami, all of Tokyo, Japan, assignors to Ricoh Company, Ltd., Tokyo, Japan


Filed Jan. 21, 1980, Ser. No. 114,016

Claims priority, application Japan, Jan. 30, 1979, 54-9412

Int. Cl.³ G03G 15/00

U.S. Cl. 355-14 SH

7 Claims



1. An electrostatic copying apparatus including a transparent document support platen, document feed means for feeding an original document along a document feed path onto the platen in a first direction, a photoconductive member, imaging means for radiating a light image of the document onto the photoconductive member to form an electrostatic image, developing means for developing the electrostatic image to produce a toner image and transfer means for feeding a copy sheet into engagement with the photoconductive member in a second direction which is perpendicular to the first direction to transfer the toner image to the copy sheet, characterized by comprising:

document support means for supporting the document prior to feeding by the document feed means such that a center of the document is aligned with a center line of the document feed path;

sensor means for sensing a width of the document perpendicular to the document feed path;

sheet feed timing means for controlling the transfer means to begin feeding the copy sheet to the photoconductive member at a timing corresponding to a predetermined function of the width of the document such that a leading edge of the copy sheet aligns with a leading edge of the toner image on the photoconductive member.

4,294,536

AUTOMATIC CONTROL OF COPIER COPY CONTRAST AND DENSITY FOR PRODUCTION RUNS

Kenneth B. Paxton, Webster, N.Y., assignor to Eastman Kodak Company, Rochester, N.Y.

Filed May 30, 1980, Ser. No. 154,747

Int. Cl.³ G03G 15/00


U.S. Cl. 355-14 C

12 Claims

1. In apparatus for producing copies of a multi-sheet document which includes at least one sheet having a copy characteristic that is substantially different from the other sheets, said copier including adjustable control means for varying at least one copy process parameter to change copy contrast and density, and means for feeding serially the sheets of a multi-sheet document to a copying position to produce copies of the document, the improvement comprising:

(a) memory means for storing production run signals corresponding to (i) the number of copies to be made of a multi-sheet document, (ii) the copy process parameters for said multi-sheet document including the variation in said one copy process parameter for said one sheet, and (iii) the position of said one sheet in the multi-sheet document; and (b) logic and control means responsive to said signals for operating said feeding means to sequentially feed the sheets of said multi-sheet document to said copying position

tion and for setting said adjustable control means prior to copying said one sheet to produce copies of the document,



with each copy of a document sheet having a desired contrast and density.

4,294,537

PHOTOGRAPHIC REPRINT SYSTEM WITH INFORMATION DISPLAY


Ronald C. Laska, Minnetonka, and Janis Pone, Minneapolis, both of Minn., assignors to Pako Corporation, Minneapolis, Minn.

Continuation-in-part of Ser. No. 23,521, Mar. 23, 1979, abandoned. This application Jan. 7, 1980, Ser. No. 109,825

Int. Cl.³ G03B 27/72, 27/76

U.S. Cl. 355-35

12 Claims



1. In a photographic reprint system in which photographic prints are produced from film frames of short previously-severed film strips which are connected together, the improvement comprising:

storage means for storing information for each film frame to be printed, the information including the number of prints to be made from each film frame; a print gate at which light is directed through a film frame to expose a photosensitive medium and produce a print; means for sequentially advancing the film frames to the print gate; means for sequentially retrieving the stored information from the storage medium; and means for displaying in human readable form information retrieved from the storage means in a predetermined time relationship with respect to the sequential advancing of the film frames to the print gate and printing of the film frames; and means for displaying a human readable indication of the film frame for which information has been retrieved.


4,294,538

IMAGE FORMING OPTICAL SYSTEM

Mikichi Ban, Yokohama, Japan, assignor to Canon Kabushiki Kaisha, Tokyo, Japan

Continuation of Ser. No. 18,910, Mar. 9, 1979, abandoned. This application Jan. 30, 1980, Ser. No. 116,752

Claims priority, application Japan, Mar. 18, 1978, 53-31578; Mar. 18, 1978, 53-31579

Int. Cl.³ G03B 27/48, 27/50, 27/70; G02B 21/18
U.S. Cl. 355—51 7 Claims

1. An image forming optical system using a concave spherical mirror, said system comprising a band-like spherical mirror obtained by optically sectioning the concave spherical mirror, said band-like spherical mirror enabling the meridional light beam from a spot object on the rotational symmetry axis other than the center of curvature of the spherical surface of said band-like spherical mirror to be imaged on a predetermined surface perpendicular to said rotational symmetry axis, causing a sagittal light beam not to be imaged and enabling an arcuate image centered at said rotational symmetry axis to be obtained on said predetermined surface.

4,294,539


DOCUMENT VACUUM WEIR SYSTEM

Charles W. Spehrley, Jr., Lebanon, N.H., assignor to Xerox Corporation, Stamford, Conn.

Filed Jan. 10, 1980, Ser. No. 111,059

Int. Cl.³ G03B 27/62, 27/64

U.S. Cl. 355—76 9 Claims



1. In a document handling system in which documents are moved with a vacuum belt to an imaging station of a copier where the documents are imaged against a light reflective document imaging surface on the first side of said belt, and in which the documents are attracted to said first side of said belt by an air flow applied from a vacuum manifold at the second side of said belt through multiple vacuum apertures extending through the belt and opening on said first side of said belt, the improvement wherein:

said apertures open on said first side of said belt only within minor, spaced, discrete limited first surface areas of said

belt which first belt surface areas have a first convoluted surface configuration which holds the documents substantially spaced from said vacuum apertures and provides substantially unrestricted (low impedance) communication of said vacuum air flow under the documents from said apertures throughout said first surface areas, said first surface areas of said belt surface being substantially enclosed by narrow border areas comprising unapertured pneumatic weirs

said weir areas having a second and much more finely convoluted surface configuration than said first surface areas, said weir areas providing an air flow therethrough under a document, but with a substantially higher air flow impedance than said first surface areas to provide a substantial restriction in the air flow under the document to said vacuum apertures in said first areas, and

said weir areas being located on said belt surface at positions corresponding to the edges of a conventional size of documents, and configured to provide light reflective characteristics generally corresponding to the remainder of said light reflective document imaging surface of said belt to improve said imaging of documents against said belt.

4,294,540


DOCUMENT BELT VACUUM MANIFOLD

Raghulinga R. Thettu, Webster, N.Y., assignor to Xerox Corporation, Stamford, Conn.

Filed Jan. 10, 1980, Ser. No. 111,061

Int. Cl.³ G03B 27/62, 27/64

U.S. Cl. 355—76 7 Claims



1. In a document handling system in which documents are moved with a vacuum belt to an imaging station of a copier where the document are illuminated for imaging against a light reflective document imaging surface on a first side of said belt with a width greater than that of the document, and in which document handling system the documents are vacuum attracted toward said first side of said belt by an air flow applied from vacuum apertures in a light reflective vacuum manifold surface at the backside of said belt, which vacuum air flow is communicated from said manifold apertures through further apertures in said vacuum belt which open on said first side of said belt, the improvement wherein:

said vacuum manifold surface at said backside of said belt has elongated grooves slightly recessed in said manifold surface,

said manifold surface grooves extend in the direction of movement of said belt spaced apart transverse the direction of movement of said belt, and relatively narrow in comparison to the overall width of said vacuum belt, said vacuum apertures in said vacuum manifold surface open

recessed within said grooves in said vacuum manifold surface;

said vacuum belt apertures are in narrow bands of apertures similarly transversely spaced apart and similarly extending in the direction of movement of said belt to generally overlie said grooves in said vacuum manifold surface, said manifold surface grooves have a sufficiently large cross-sectional area to provide relatively unrestricted air flow from said manifold surface apertures along said grooves under said belt to said vacuum belt apertures.

4,294,541


BI-PERISCOPIC INSTRUMENT FOR USE IN DETERMINING TERRESTRIAL POSITIONS THROUGH CELESTIAL OBSERVATION

William L. Abler, 3350 S. Michigan, Chicago, Ill. 60616

Filed Jun. 18, 1979, Ser. No. 49,567

Int. Cl.³ G01C 1/00, 1/14; G02B 23/04

U.S. Cl. 356—145 9 Claims



1. An instrument for use in establishing terrestrial positions through celestial observation, comprising in operative combination:

- (a) an annular body having a central axis;
- (b) a first periscope having a tubular axial portion coaxial with said body and a tubular arm portion with an axis extending radially from said central axis, said arm portion having a proximal end secured to said axial portion and having said radial axis thereof perpendicular to said central axis;
- (c) a second periscope having a tubular axial portion coaxial with said body and a tubular arm portion with an axis extending radially from said central axis, said arm portion having a proximal end secured to said axial portion and having said radial axis thereof perpendicular to said central axis;
- (d) said tubular axial portions of said periscopes being adjustably mounted upon opposite ends of said annular body for independent relative rotation about said central axis;
- (e) each of said periscopes having rotatably mounted on a distal end thereof a turret having a sight opening;
- (f) each of said turrets having reflecting means fixed therewithin for transmitting images from said sight openings to said central axis;
- (g) one of said periscopes having a viewing opening for viewing along said central axis;
- (h) said annular body having a single 360° scale extending circumferentially thereabout;
- (i) indicator means disposed on each of said periscopes for indicating the angular position thereof along said scale and to indicate Local Hour Angle of Aries along said scale when said instrument is positioned for the viewing, in superimposed relation, a pair of celestial reference objects through said turret sight openings via said viewing opening; and
- (j) direct-line-of-sight horizon viewing means for indicating the angle of said central axis from horizontal disposed

connected to said viewing opening of said periscope, which viewing means provides for a central superimposed image of said celestial reference objects sighted through said turrets and a view of said horizon alignable with said central superimposed image, said horizon view being disposed located in an annular zone around said central image of said celestial objects.

4,294,542


METHOD AND APPARATUS FOR COUNTING SMALL OBJECTS SUSPENDED IN A LIQUID STREAM

Gary M. Strauss, Kent, Wash., assignor to Weyerhaeuser Company, Tacoma, Wash.

Filed Dec. 17, 1979, Ser. No. 104,596

Int. Cl.³ B65G 51/36; G06M 7/00

U.S. Cl. 356—339 17 Claims



1. A method for counting suspended discrete small objects carried in a liquid stream which comprises:

- a. splitting a liquid stream into primary and secondary streams;
- b. introducing the objects into the moving secondary liquid stream, said stream having sufficient velocity to prevent settling or back movement;
- c. recombining the primary and secondary streams;
- d. maintaining the moving stream at a steady flow rate;
- e. measuring turbidity of the stream containing the objects;
- f. establishing a calibration algorithm of turbidity measurement versus number count of the objects for a given increment of time;
- g. integrating the turbidity measurement over time and comparing the integrated value with the calibration algorithm;
- h. providing an output signal responsive to the integrated value that indicates the number of individual objects that have passed the turbidity counter within a given time period.

4,294,543

OPTICAL SYSTEM FOR DEVELOPING POINT COORDINATE INFORMATION

Joseph Apple, Canoga Park, Calif., and Eric L. Upton, Mesa, Ariz., assignors to Command Control & Communications Corporation, Lomita, Calif.

Filed Nov. 13, 1979, Ser. No. 93,524


Int. Cl.³ G08C 21/00

U.S. Cl. 356—375 15 Claims

1. A means for defining coordinates of an object intersecting a predefined plane, comprising:

- a first rotatable means for sweeping a first light beam over a plane substantially coincident with said predefined plane;
- a second rotatable means for sweeping a second light beam over a plane substantially coincident with said predefined plane;
- an elongated light detection means positioned to be continuously irradiated by said first and second light beams while being swept over said predefined plane, said light detection means providing a first intersection pulse when said first light beam intersects and is blocked by said object and a second intersection pulse when said second light beam intersects and is blocked by said object;
- first timing means for generating a first timing signal when

said first light beam is at a first predetermined reference angle;
 second timing means for generating a second timing signal when said second light beam is at a second predetermined reference angle;
 processor means responsive to the time duration between said first timing signal and said first intersection pulse and between said second timing signal and said second intersection pulse for producing X-Y coordinate signals defining the coordinates of said object;
 said first rotatable means including a first motor;
 a first tachometer providing an output signal indicative of the rotational velocity of said first motor;



a reference oscillator;
 means for controlling said first motor rotational velocity in accordance with a phase difference between said first tachometer output signal and a signal produced by said reference oscillator;
 a first voltage controlled oscillator; and
 means for controlling the frequency of said first voltage controlled oscillator in accordance with a phase difference between a signal related to the output of said first voltage controlled oscillator and said first tachometer output signal.

4,294,544


TOPOGRAPHIC COMPARATOR

Bruce R. Altschuler, 123 Thornell, San Antonio, Tex. 78235;
 John Taboada, 12530 Elm Country La., San Antonio, Tex. 78230, and Martin D. Altschuler, 228 Ranch Trail, Amherst, N.Y. 14221

Filed Aug. 3, 1979, Ser. No. 63,500
 Int. Cl.³ G01B 11/00

U.S. Cl. 356—376

21 Claims



1. Apparatus for providing three dimensional location information relative to a coordinate system for selected points on a remote surface, said apparatus comprising
 a source of illumination for providing light beam illumination of said surface, said source of illumination comprising means for providing an array of light beams,
 a scene recording device for providing surface scene images from an aspect angle other than parallel or normal to said light beam, each said surface scene image having an x,y

coordinate system correlated with the surface x,y coordinate system, the elevation dimension of the surface at any selected illuminated x,y coordinate position being a function of (a) the displacement of the corresponding imaged spot from its x,y coordinates, (b) the scene recording device aspect angle and (c) surface to image coordinate system conversion factors, and
 space coding means for correlating spots illuminated by said array of light beams with spots imaged by said scene recording device.

4,294,545

DEVICE FOR CONTINUOUSLY MEASURING A TRANSVERSE DIMENSION OF A THREAD-LIKE STRUCTURE

Hansruedi Stutz, Dietlikon, Switzerland, assignor to Gebrüder Loepfe AG, Zurich, Switzerland


Filed Dec. 10, 1979, Ser. No. 101,879

Claims priority, application Switzerland, Dec. 18, 1978, 12824/78

Int. Cl.³ G01B 11/10, 11/02

U.S. Cl. 356—386

5 Claims



1. A device for continuously measuring a transverse dimension of a traveling yarn-like structure, comprising:
 an array of optoelectrical sensors extending in a direction transverse to the traveling yarn-like structure;
 means for scanning sensors of the array in consecutive cycles for producing a digital scanning signal in serial form;
 means for delaying the digital scanning signal by an integer number $n \geq 1$ of cycles;
 logic means for producing a serial signal representative of the difference of the delayed and undelayed scanning signals;
 means for storing consecutive serial signals, for producing a signal representative of an instantaneous transverse dimension of the yarn-like structure; and
 the storing means being arranged as a counting device comprising a bidirectional counter, and an AND-gate having a first input connected to the output of the delaying means and a second input connected to the output of the logic means, the AND-gate having an output controlling the counting direction of the bidirectional counter.

4,294,546

APPARATUS FOR WORKING ALIGNED BORES

Irolt Killmann, St. Augustin-Müllendorf, and Georg W. Bonifer, Cologne, both of Fed. Rep. of Germany, assignors to Klöckner-Humboldt-Deutz Aktiengesellschaft, Cologne, Fed. Rep. of Germany

Filed Apr. 2, 1979, Ser. No. 26,076

Claims priority, application Fed. Rep. of Germany, Dec. 29, 1977, 2758742


Int. Cl.³ G01B 11/26

U.S. Cl. 356—399

8 Claims

1. An apparatus for working with a tool at least one of a plurality of bores aligned on an axis wherein the bores are associated with the crankshaft bearings of internal combustion engines, said apparatus comprising in combination:
 means for generating a laser beam to be passed through said bores and for aligning the laser beam with a longitudinal axis aligning said bores;
 a driven hollow shaft for supporting said tool in one of said bores, said hollow shaft being positioned within said bore

and surrounding the longitudinal axis thereof and said hollow shaft being adjustable with respect to said laser beam to align with the laser beam and said longitudinal axis;
 centering discs positioned in those bores not being worked on by said tool, said centering discs including means for indicating misalignment between said discs and said laser beam, said centering discs further including movable measuring devices and chucking means for adjusting and subsequently fixing, respectively, said centering discs within said bores wherein the centering discs are centered with respect to the bores;



a cylindrical prism centrally mounted within said hollow shaft for alignment with the laser beam, the prism having a cylindrical reflecting mantle surface and conical end surfaces having aligned axes which are aligned with the laser beam for initially splitting the laser beam into components which components reflect from said reflecting mantle surface and converge back to a single beam when the aligned axes are aligned with the laser beam and converge back into a plurality of beams when the aligned axes are out of alignment with the laser beam, whereby misalignment can be detected.

4,294,547

MORTAR/CONCRETE HAND-MIXING TUB


James F. Harkleroad, 9032 - 49th Ave., College Park, Md. 20740

Filed Jul. 20, 1979, Ser. No. 59,359

Int. Cl.³ B01F 13/00, 15/02

U.S. Cl. 366—1

14 Claims



1. In a concrete or mortar mixing tub or box of the type having a flat bottom wall integrally joined with peripheral side walls upstanding therefrom and terminating in an upper edge forming an open top, the improvement comprising a selectively openable planar panel constituting a mortar discharge door formed in conjunction with a door opening provided in one of said peripheral side walls, said door panel being of lesser length than said side wall panel with which it is associated, and support and retaining means operatively connected with said side wall and said door to facilitate its selective opening and closing.

4,294,548

DRIVE ARRANGEMENT FOR CONCRETE MIXERS


Arthur Watson, Sellicks Beach, Australia, assignor to Lightburn & Co. Limited, Novar Gardens, Australia

Filed Mar. 21, 1980, Ser. No. 132,404

Int. Cl.³ B28C 5/18

U.S. Cl. 366—60

3 Claims



1. A concrete mixer drive arrangement, said mixer including a bowl having a base and an axis of rotation extending through the base, said bowl being supported by a shaft extending from the base of the mixer, a ring gear on said base about the shaft, a drive shaft having a pinion arranged to operably engage said ring gear, an electric motor having a motor shaft, a multiple stage speed reduction operably connected between said motor shaft and drive shaft, said motor shaft extending at a right angle to said axis of rotation, said drive shaft extending parallel to said motor shaft, characterized in that said multiple stage speed reduction comprises a three-stage V-belt drive including pulleys and driving belts, said first stage comprising a pulley fast to said motor shaft driving a pulley loose on said drive shaft, said second stage comprising a pulley loose on said drive shaft and drivingly connected to said first mentioned pulley on said drive shaft driving a pulley loose on said motor shaft, and said third stage comprises a further pulley loose on said motor shaft and drivingly connected to said first mentioned loose pulley on said motor shaft driving a drive pulley fast on said drive shaft.

4,294,549

MIXING APPARATUS

Raymond V. Thompson, Stocksfield; Alan Todd, Chester-le-Street, and Albert B. Constantine, Great Lumley, all of England, assignors to Dynatrol Consultants (U.K.) Limited, Newcastle-upon-Tyne, England

Division of Ser. No. 749,369, Dec. 10, 1976, Pat. No. 4,172,668.


This application Jun. 14, 1979, Ser. No. 48,383

Claims priority, application United Kingdom, Dec. 12, 1975, 51027/75; Aug. 26, 1976, 35600/76

Int. Cl.³ B01F 5/06, 5/12

U.S. Cl. 366—164

3 Claims



1. Apparatus for mixing fluids comprising a housing affording a substantially annular mixing chamber, an annular rotor

distance between the first gear paths, the motion converting means converting the rotational movement of the pinion to a reciprocating movement of the print head along the data carrier, the driving device further including guiding means in engagement with each other, with the motion converting means and with the printing carriage, the guiding means moving the printing carriage in the printing direction when the pinion is in engagement with any of the first gear paths of the motion converting means and permitting the displacement of the motion converting means essentially perpendicularly to the printing direction when the pinion is in engagement with any of the second gear paths of the motion transmitting means, characterized in that the guiding means consist of two gear segments each one provided with two gear paths, that the gear paths turned towards each other on the gear segments are in engagement with each other and the gear paths turned away from each other on the gear segments are in engagement with gear paths on one of the motion converting means and the printing carriage, and that the gear segments are pivotally supported on one of the printing carriage and the motion converting means.

4,294,555

MULTI-ROW KEYBOARD FOR TYPEWRITERS OR SIMILAR MACHINES

Folker Galaske, and Oswald Hack, both of Pforzheim, Fed. Rep. of Germany, assignors to International Standard Electric Corporation, New York, N.Y.


Filed Jan. 28, 1980, Ser. No. 116,228

Claims priority, application Fed. Rep. of Germany, Feb. 1, 1980, 2903780

Int. Cl.³ B41J 5/10, 5/16

U.S. Cl. 400—488

4 Claims



1. A multi-row keyboard for typewriters or similar machines comprising a set of keys arranged in an inclined position (α) and comprising a plurality of individual keys arranged in parallel, longitudinally extending rows, each said key comprising a key element having a plunger and a keyhead connected to said plunger, the center points of the upper surfaces of said keyheads lying in a plane dished transversely in relation to the longitudinal direction of said rows of keys, wherein the improvement comprises:

- said keyheads of all rows of said set of keys all having the same shape;
- an adapter being located between each said plunger and its associated keyhead;
- the heights of said adapters differing from row to row of said keys; and
- said adapters having supporting surfaces for their respective keyheads having a slope (angle β) differing from row to row of said keys, said slope angles of said supporting surfaces being selected to cause said upper surfaces of said keyheads to lie in said dished plane.

4,294,556

GUIDE FOR RECORD CARRIER IN PRINTERS


Albert Rix, Wilhelmshaven, Fed. Rep. of Germany, assignor to Olympia Werke AG, Wilhelmshaven, Fed. Rep. of Germany
Filed Jul. 9, 1979, Ser. No. 56,001

Claims priority, application Fed. Rep. of Germany, Jul. 7, 1978, 2829827

Int. Cl.³ B41J 3/04, 13/18

U.S. Cl. 400—643

14 Claims



1. A device for guiding a record medium sheet which is to be printed upon in a printing machine having a platen, said device being arranged to guide the sheet around the platen and comprising: an apron member formed and positioned to hold the sheet in contact with said platen and to guide the sheet at a point closely below the line being printed, said member being constructed to conform to the curvature of the lower portion of said platen and presenting a press and guide edge at each end of said member in the direction of the circumference of said platen; and spring biasing means disposed for pressing said member resiliently against said platen to cause said edges to bear against said platen; wherein said member is of a material selected so that the coefficient of friction between the record medium sheet and said press and guide edges is less than the coefficient of friction between said platen and the record medium sheet, said apron member is provided with at least one bearing portion presenting a guide slot, said portion being mounted to be slidable and pivotal relative to a pivot axis fixed relative to the machine and extending parallel to the axis of said platen, said spring biasing means act on said member via said bearing means, and said spring biasing means are constructed and mounted for pressing said apron member against said platen in a manner to establish a self-centering action between said press and guide edges and said platen.

4,294,557

SHIELD FOR TYPEWRITER KEYBOARD AND CYLINDER

Carroll H. Blanchard, 26 S. Royal Dr., Albany, N.Y. 12205, and Robert P. Marcelonis, 170 Ottawa St., Lake George, N.Y. 12845

Filed Dec. 27, 1979, Ser. No. 107,543

Int. Cl.³ B41J 29/12


U.S. Cl. 400—714

4 Claims

1. A portable and compact shield for use with a typewriter supported by legs and having a keyboard, a cylinder and a casing comprised of:

- a keyboard screen;
- a cylinder screen hingedly connected to the keyboard screen;
- vertical extension member hingedly connected to the keyboard screen on one side thereof and adapted to extend vertically downwardly from the keyboard screen along the side of the typewriter;
- a lateral extension member hingedly connected to the vertical extension member, said lateral extension member being of sufficient length to extend under at least one of the legs of the typewriter; and
- means for flexibly and releasably fastening the keyboard screen to the casing of the typewriter,

once the keyboard screen is released from the casing, the hinge between the keyboard screen and the vertical extension and the hinge between the vertical and lateral extension



sions being such as to permit the screens to be lifted away and folded off to the side of the typewriter for unobstructed access to the keyboard and cylinder.

4,294,558

WEATHERPROOF PORTFOLIOS


Dominic R. Errichiello, 389 Meadowlark Rd., Bloomington, Ill. 60108

Filed Aug. 6, 1979, Ser. No. 63,865

Int. Cl.³ A45C 3/02; B65D 43/14

U.S. Cl. 402—75

4 Claims



1. An integrally molded weatherproof portfolio of a thermoplastic polymer comprising an elongated spine having a first side panel and a second side panel hingedly mounted on respective, opposite, longitudinal edges of said spine, each said panel having two integrally molded side flanges connected by an integrally molded top flange to form two opposite, three-sided, substantially identical enclosures on respective panels, the longitudinal edges of said two side flanges and said top flange of the respective enclosures being aligned when said side panels are swung about their hinges from an open position toward each other and into abutting contact by said flanges in the closed position, and sealing means comprising longitudinal tongues and mating longitudinal grooves on respective longitudinal edges of said flanges providing a substantially watertight seal when the edges of respective enclosures are in abutting contact;

and a substantially triangular wall near each end of said spine and aligned with respective side flanges on the respective panels, said side flanges each having a diagonal edge adjacent said spine, which edge abuts against one of the diagonal walls of said triangular wall when said portfolio is in the closed position, and sealing means on the respective edges of said diagonal walls to provide a substantially watertight seal between said edges when they are in abutting contact.

4,294,559

PRE-STRESSED STRUCTURAL JOINT


Jerome C. Schutzler, El Toro, Calif., assignor to PDA Engineering, Santa Ana, Calif.

Filed Aug. 27, 1979, Ser. No. 70,167

Int. Cl.³ F16B 4/00; F16D 1/00; F16L 25/00

U.S. Cl. 403—28

6 Claims



1. A structural joint wherein two portions of a structure are joined together by a connection means at a parting line which joint comprises:

- a first member;
- a second member;
- a connection means;
- a third member interposed within said connection means which has been formed from a nickel-titanium alloy containing up to 5% by weight of cobalt and which has been compressively deformed below its transformation temperature to provide an expansive stress against said connection means and said first and second members when at ambient temperature.

4,294,560

LOCKING MEANS


Miles K. Larkin, 13 Roadley Ave., Pakuranga, Auckland, New Zealand

Filed Mar. 12, 1980, Ser. No. 129,665

Int. Cl.³ F16B 7/10

U.S. Cl. 403—104

8 Claims



1. Locking means for inner and outer telescopically engageable tubes, including at least one primary locking member and at least one secondary locking member in the form of a substantially resilient bushing mounted within a section of the inner tube which is within the outer tube, so as to be engageable with the inner surface of the outer tube, the primary locking member and resilient bushing being mounted relative to the inner

tube and to each other so that relative rotational movement between said inner and outer tubes causes said primary locking member to lockingly engage the inner surface of said outer tube and a further relative axial movement between said inner and outer tubes causes said resilient bushing to be compressed longitudinally and thereby to expand substantially radially into engagement with the inner surface of said outer tube.

4,294,561

JOINTING MEMBER FOR FRAME SYSTEMS


Arthur J. Chapman, Reading, and Geoffrey M. G. Hayes, Weybridge, both of England, assignors to Pentabloc, Ltd., London, England

Filed Jan. 14, 1980, Ser. No. 111,675

Int. Cl.³ F16B 7/04

U.S. Cl. 403—219

10 Claims



1. A jointing member for a frame system comprising: a member having three bores therein with the axes of said bores mutually perpendicular and with two of said bores lying in the same plane, and securing means for securing an elongate member engaged in one of said bores against longitudinal movement with respect to said member, said bores being so interconnected within said member that tightening said securing means to secure an elongate member in one of said bores, said one of said bores being other than one of said two bores lying in said plane, will secure respective elongate members engaged in the others of said bores against longitudinal movement with respect to said member; wherein said securing means is a set screw engaged in a screw-threaded hole in said member and engageable, by screwing it inwardly, with the elongated member engaged in said one of said bores, to press that elongate member against the elongate members engaged in said others of said bores to bind them therein, and wherein one of said two bores lying in the same plane is a blind bore.

4,294,562

POLYGON CONNECTION OF A HUB WITH A SHAFT

Ralph Müllenberg, Im Wiesengrund 6, 4048 Grevenbroich 12, Fed. Rep. of Germany


Filed Jul. 23, 1980, Ser. No. 171,484

Claims priority, application Fed. Rep. of Germany, Jul. 24, 1979, 2929908

Int. Cl.³ F16D 1/06

U.S. Cl. 403—383

1 Claim



1. A polygonal connection for joining a hub with a shaft,

said hub and shaft each having an axis, the connection comprising:

- a bore of non-circular cross section in the hub;
- a joining portion of non-circular cross section in the shaft, said joining portion of said shaft fitting within said bore, said non-circular cross sections of said bore and of said joining portion approximately corresponding with each other in size and shape, said non-circular cross sections being taken in planes normal to the axes of the hub and shaft, said joining portion of said shaft having a perimeter defining said non-circular cross section of said joining portion, said joining portion of the shaft being so configured as to define a plurality of corners at said perimeter of said joining portion;
- a plurality of fasteners disposed in vicinities of said corners of said joining portion of said shaft, said fasteners extending in directions parallel to the axis of the shaft; each fastener including means for effecting radial expansion thereof, said fasteners having longitudinal axes located within said perimeter of said joining portion of said shaft; said fasteners being disposed entirely within said perimeter of said joining portion of said shaft.

4,294,563

THERMALLY INSULATED BULKHEAD FOR IN SITU OIL SHALE RETORT


James S. Kilburn, Grand Junction, Colo., assignor to Occidental Oil Shale, Inc., Grand Junction, Colo.

Filed Apr. 9, 1979, Ser. No. 28,226

Int. Cl.³ E21F 17/00

U.S. Cl. 405—132

37 Claims



1. An insulated heat seal in an access drift adjacent a portion of in situ oil shale retort comprising:
 - a bulkhead placed across an access drift excavated in formation containing oil shale, the drift being in communication with a fragmented permeable mass of formation particles containing oil shale in an in situ oil shale retort, the bulkhead having an inside surface facing toward the fragmented mass, the access drift having an inside wall between the inside surface of the bulkhead and the fragmented mass;
 - a first layer of heat insulating material on the inside surface of the bulkhead for reducing heat transfer to the bulkhead from a hot portion of the fragmented mass in communication with said access drift; and
 - a second elongated layer of heat insulating material on the inside wall of the access drift on the same side of the bulkhead as the first layer of heat insulating material, the second layer of heat insulating material extending along the length of the inside wall of the drift away from the first layer of heat insulating material for reducing heat transfer from said hot portion of the fragmented mass to formation

forming the drift wall adjacent the inside surface of the bulkhead.

4,294,564

METHOD OF DEPLOYMENT, RELEASE AND RECOVERY OF OCEAN RISER PIPES



Abraham Person, Los Alamitos; Sherman B. Wetmore, Westminster, and James F. McNary, Santa Ana, all of Calif., assignors to Global Marine Inc., Los Angeles, Calif.

Division of Ser. No. 935,672, Aug. 21, 1978, Pat. No. 4,234,269. This application Jan. 14, 1980, Ser. No. 111,812

Int. Cl.³ E02D 21/00, 29/06

U.S. Cl. 405—195

9 Claims



1. A method for connecting to a structure adjacent the surface of an ocean an elongate pipe assembly having overall negative buoyancy and which, when connected to the structure, depends downwardly from the structure and is supported thereby, the method comprising the operations of

- (a) fabricating the pipe assembly to an essentially finished state at a location away from the structure, the upper end of the pipe assembly being sufficiently positively buoyant that the normal stable position of the assembly when submerged and released from support from above is substantially vertical,
- (b) moving the pipe assembly in a horizontal attitude to the location of the structure,
- (c) controllably lowering the pipe assembly toward the ocean floor and concurrently both maintaining a connection to the upper end of the assembly and causing the assembly to assume a vertical attitude in a fully submerged state thereof, the lowering operation including a further operations of (1) connecting a line from the structure to the lower end of the assembly while the assembly is horizontal at the location of the structure, and (2) paying out the line from the structure to lower the lower end of the assembly,
- (d) moving the submerged vertically disposed pipe assembly to below the structure, and
- (e) raising the pipe assembly into engagement with the structure and connecting the same to the structure for support thereafter by the structure.

4,294,565

INDEXABLE FINISHING INSERT FOR A MILLING CUTTER


Donald S. Erkfritz, Clarkston, Mich., assignor to General Electric Company, Columbus, Ohio

Filed Mar. 6, 1980, Ser. No. 127,598

Int. Cl.³ B26D 1/12

U.S. Cl. 407—113

14 Claims



1. A finishing insert for use with an indexable cutting tool, said insert comprising:

a flat wafer of cutting material having parallel, spaced front and rear planar rake surfaces and a plurality of edge faces disposed therebetween, said rake faces being of equilateral, polygonal configuration with the side edges of said polygonal front rake surface corresponding to the cutting edges of said insert, said cutting edges being arcuate having a radius of curvature several times greater than the width of said front rake surface and with the intermediate portion of each said edge face being substantially planar and defining a locating land, with at least a portion of the opposed ends of said edge faces being curved and sloped away from said front rake surface in order to provide clearance along said edge faces when said insert is mounted on a cutting tool at a rake angle between said front rake surface and the workpiece.

4,294,566

EIGHT EDGE POSITIVE CHIP CONTROL INSERT


Gary A. Boone, Farmington, Mich., assignor to Carmet Company, Pittsburgh, Pa.

Filed Jun. 16, 1980, Ser. No. 159,580

Int. Cl.³ B26D 1/00, 1/12

U.S. Cl. 407—114

10 Claims



1. An eight-edge cutter insert adapted for use with a tool holder having an insert-receiving square pocket formed therein, said insert comprising:

a generally rectangular prismatic element of cutting material, said element having a pair of parallel, laterally offset primary faces, and four rectangular side faces each outwardly bounded by a respective side reference plane extending perpendicularly of said primary faces and the adjacent side reference planes, each of said side faces having an opposed pair of recessed, beveled facets formed therein, said facets each intersecting a respective primary face to form a cutting edge ex-

tending parallel to the side reference plane of the side face containing the said facet, each facet being inwardly inclined away from its respective cutting edge to define a shear angle measured from said side reference plane, said side faces each having a diametrically opposed pair of flat lands substantially coplanar with a respective side reference plane whereby to define a planar base on each side face for permitting said cutter to be accurately located, and securely clamped, in said square pocket.

4,294,567

DOWELING JIG TEMPLATE


Garfield Wiggins, 162 Burnett Ave., Maplewood, N.J. 07040

Filed Jan. 11, 1979, Ser. No. 2,506

Int. Cl.³ B23B 47/28

U.S. Cl. 408—72 R

5 Claims



1. In combination a template to support a doweling jig in a position above and parallel to a flat surface for drilling longitudinally spaced series of vertical dowel holes for mating with similarly positioned holes in an edge or end of another workpiece to be joined in a right angle relationship to a flat surface, said doweling jig characterized by a horizontally elongated channel having a flat top member and two parallel side members extending transversely to said top member, said top member having parallel ends extending transversely to said side members and having an undersurface parallel with its upper surface and having longitudinally spaced vertical guide bushings through which a drill bit can pass for making spaced holes in a piece of stock beneath said undersurface, one of said side members having attached means for clamping a template against the other side member in a position for such drilling, said template characterized by a horizontally elongated body having at least one vertical cavity to allow passage of the drill bit through the guide bushing into the flat piece of stock held in contact with the undersurface of said elongated body, a channel portion containing said cavity recessed into the upper surface of said elongated body and extending across the entire width of said upper surface and forming spaced abutments to allow precise positioning and support against movement in one horizontal direction by abutment of either end of the flat top of the dowel jig in the channel portion, and vertical guide holes at each end of said elongated body for allowing the passage of securing means for holding the elongated body in contact with the flat workpiece.

4,294,568

PROCESS FOR BROACHING OF GROOVES

Dieter Lipowsky, Grobenzell, and Karl Meyle, Munich, both of Fed. Rep. of Germany, assignors to Motoren- und Turbinen-Union München GmbH, Munich, Fed. Rep. of Germany

Continuation of Ser. No. 875,403, Feb. 6, 1977, abandoned. This application Nov. 29, 1979, Ser. No. 98,659

Claims priority, application Fed. Rep. of Germany, Feb. 5, 1977, 2704812


Int. Cl.³ B23D 37/04, 41/04

U.S. Cl. 409—244

12 Claims

1. A process for production of a series of circumferentially adjacent retaining grooves for turbine blades in the peripheral

surface of a rotor plate for a turbine engine by broaching, said retaining grooves being inclined with a predetermined pitch relative to the longitudinal axis of the rotor plate and being spaced from each other at a predetermined distance comprised



by the simultaneous broaching of two adjacent retaining grooves in one broaching stroke by means of two broaching tools positioned relative to each other at the distance and in the angular position of the pitch of the grooves that are to be produced.

4,294,569

SINGLE COLUMN LOAD DIVIDING GATE


Alfred E. Lewis, Tustin, and Robert E. Salisbury, Whittier, both of Calif., assignors to Preco Inc., Los Angeles, Calif.

Filed Jun. 14, 1979, Ser. No. 48,454

Int. Cl.³ B60P 17/14; B61D 17/10

U.S. Cl. 410—133

23 Claims



10. In a load dividing gate movable along a track and lockable by locking pin means projectable to engage the track, said gate having a vertical edge structure comprising spaced flanges with a web recessed between the flanges and forming therewith a channel; control mechanism for the locking pin means comprising

a crank shaft journaled on said web and terminating outward of the web in a coupling formation, crank means mounted on the shaft and coupled to the locking pin means for operating the same in response to shaft rotation,

a handle rigidly carrying at one end coupling means for engaging and disengaging said coupling formation in response to respective movements of said one handle end along the shaft axis to and from said one end of the shaft,

a support member mounted for rotation about the shaft axis, and linkage means for interconnecting the handle and the support member with freedom of relative movement sufficient to permit said axial handle movement and to permit handle movement to and from a stowed position radially spaced from the shaft and substantially within the channel.

4,294,570

LOCKABLE CAP SCREW

Albin Meschnig, Müllern 72 (Kärnten), A-9585 Gödersdorf, Austria


Filed Feb. 21, 1979, Ser. No. 13,659

Claims priority, application Austria, Mar. 7, 1978, 1638/78; Sweden, Oct. 30, 1978, 7811221

Int. Cl.³ F16B 39/00

U.S. Cl. 411—103

13 Claims



1. A lockable cap screw having a head formed with a bore opening in an outside peripheral surface of the head, and a pin slidable in said bore between a position of rest and an operative position in which an outer end of the pin protrudes over the outside peripheral surface of the head of the screw, comprising means, comprising an actuating member engaging an inner end of the pin and being adjustable relative to the head of the screw, for shifting the pin to said operative position, said actuating member is formed with an opening, and the inner end of said pin is angled and enters said opening of the actuating member, the bore in the head of the screw is oblique to a radial plane of the actuating member.

4,294,571

VAN PLATFORM WITH LOCKABLE RAMP


Joseph R. Tordella, 128 B Elm Dr., Medford, N.J. 08055

Filed Nov. 30, 1979, Ser. No. 99,069

Int. Cl.³ B60P 1/00

U.S. Cl. 414—537

12 Claims



1. A van platform comprising a housing including first floor means terminating outwardly in an outer edge and defining a space thereunder, movable ramp means located in said space and having roller means to enable said ramp means to be extended from a retracted position within said space to an extended, ramp-functioning position outside said space, a pair of inclined guides positioned in said space adjacent the outer edge of said first floor, each of said guides being inclined upwardly

and outwardly and including an indentation at the top thereof, said rollers being arranged to engage said inclined guides to facilitate movement of said ramp means to and from the extended position, at least one of said rollers being received in said indentation when said ramp means is brought to the extended position, and first releasable locking means for preventing said roller from moving inwardly out of said indentation when said ramp means is in said extended ramp functioning position, said releasable locking means comprising at least one stop member located adjacent said indentation and a movable to a position immediately inward of said indentation to engage the roller disposed therein.

4,294,572

INTERNAL FLUID COMMUNICATION SYSTEM FOR POWER CYLINDERS

Jack E. Pattison, 115 S. Ridgeway Dr., Battle Creek, Mich. 49015

Filed Apr. 10, 1978, Ser. No. 894,691

Int. Cl.³ B66F 9/22

U.S. Cl. 414—641

6 Claims



1. In a lift truck having an upright with two sections, each with spaced vertical side members, and a fluid operated attachment on said upright: a fluid operated ram disposed vertically between said side members and in spaced relation thereto and consisting of two ram sections with directly interconnecting chambers containing the operating fluid therefor, for operating said upright sections between raised and lowered positions, a conduit having a first pair of tubular sections comprising upper and lower tubular sections disposed in telescopic relationship lengthwise within the chambers containing the operating fluid of said ram and forming a first fluid passageway for transmitting fluid through said ram separate from the operating fluid therein, a bottom end member connecting the lower end of said lower tubular section with the lower end of said lower ram section, means forming a passage in said bottom end member for receiving fluid from a source to be transmitted through the first passageway in said telescopic sections, a top end member connecting the upper end of said upper tubular section with the upper end of said upper ram section, and means forming a passage in said top end member for transmitting the fluid in said first passageway to said attachment.

4,294,573


SUBMERSIBLE ELECTRICALLY POWERED CENTRIFUGAL AND JET PUMP ASSEMBLY
John W. Erickson, Huntington Beach, and Harold L. Petrie, Sierra Madre, both of Calif., assignors to Kobe, Inc., Huntington Park, Calif.

Filed May 17, 1979, Ser. No. 39,775

Int. Cl.³ F04B 23/14

U.S. Cl. 417—83

19 Claims U.S. Cl. 493—213



1. A downhole petroleum pump comprising:
 - (a) a housing adapted for residence in a downhole location within a well;
 - (b) an electric motor within the housing;
 - (c) a plurality of centrifugal pump stages within the housing and driven by the motor, the centrifugal pump stages being serially coupled and having at least one low pressure stage and at least one high pressure stage to progressively increase the pressure of well fluid from a low value at the low pressure stage to a high value at the high pressure stage;
 - (d) means for providing the well fluid as the fluid to be pumped to the centrifugal pump stages;
 - (e) a jet pump within the housing having means for receiving an aspirated fluid and means for receiving a power fluid;
 - (f) means for providing high pressure well fluid to the jet pump from the high pressure centrifugal pump stage as the power fluid for the jet pump;
 - (g) means for providing well fluid to the jet pump at a pressure lower than the power fluid as the aspirated fluid to the jet pump;
 - (h) means for recirculating well fluid from the output of the jet pump, including the power fluid, to the high pressure centrifugal pump stage including the power fluid;
 - (i) means for drawing off well fluid from the high pressure centrifugal pump stage as the production fluid from the well; and
 - (j) centrifugal cleaner means upstream of the jet pump for cleaning the power fluid of particulate matter, the cleaner means being powered by the electrical motor.

4,294,574

METHOD OF MAKING SEAL FOR FLEXIBLE CONTAINER


Edward L. Bayham, Mundelein, Ill., assignor to Baxter Travenol Laboratories, Inc., Deerfield, Ill.

Division of Ser. No. 17,529, Mar. 5, 1979, Pat. No. 4,234,026.

This application Oct. 29, 1979, Ser. No. 89,815

Int. Cl.³ B31B 1/84

13 Claims



1. The method of sealing a flexible container with an openable seal member which comprises:
 - inserting a thermoplastic tube between thermoplastic members with a portion of the tube communicating outwardly beyond said members;
 - enclosing the outer end of said tube with a thermoplastic pocket member having an open outer end;
 - inserting a mandrel through the outer end of said pocket member and said tube;
 - sealing said thermoplastic members, tube, and inner end of the pocket member together in a smooth, continuous seal such that the inner and outer ends of the tube communicate through said seal;
 - withdrawing said mandrel through the outer end of said pocket member; and
 - sealing the outer end of the pocket member.

CHEMICAL

4,294,575

PEROXIDE STABILIZATION

Xavier Kowalski, St. Louis, Mo., assignor to Monsanto Company, St. Louis, Mo.

Division of Ser. No. 403, Jan. 2, 1979, Pat. No. 4,239,643. This application Jul. 18, 1980, Ser. No. 170,201

Int. Cl.³ D06C 3/02; D21C 9/16

U.S. Cl. 8—111

5 Claims

1. In a process for bleaching cellulose fiber with an aqueous peroxide-containing solution having a pH from about 7 to about 12.5, the improvement which comprises including in said solution from about 0.2 to about 20 grams per liter of alkali metal polyphosphate and from about 0.1 to about 10 grams per liter of alkali metal diethylene triamine penta(methylene phosphonate).

4,294,576

REMOVAL OF OLIGOMER DEPOSITS FROM TEXTILE MATERIALS

Herbert Helfert, Frankenthal; Friedrich Reinert, Wachenheim; Paul Richter, Friedelsheim; Michele Vescia, Limburgerhof, and Dieter Wegerle, Mannheim, all of Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Ludwigshafen, Fed. Rep. of Germany

Filed May 22, 1980, Ser. No. 152,178

Claims priority, application Fed. Rep. of Germany, Jun. 23, 1979, 2925477

Int. Cl.³ D06L 1/12; D06P 5/02; C11D 1/62

U.S. Cl. 8—137.5

10 Claims

1. A process for removing oligomer deposits from textile materials which consist of polyester fibers or of blends of polyester fibers with other fibers, and from dyeing machinery, comprising:

treating said fibers or machinery with an aqueous alkaline liquor at a temperature from 30° to 100° C., containing as the active ingredient of the liquor, at least one quaternary ammonium compound whose quaternary nitrogen atom bears not less than two C₆-C₂₂-alkyl or -alkenyl groups with the remaining groups being selected from the group consisting of alkyl, aryl, alkylphenyl, aralkyl, alkylene oxide and RCO—X—(CH₂)_n—, wherein R is C₁-C₁₈ alkyl, X is —NH— or —O— and n is a value from 1 to 6.

4,294,577

DYED FLOCKED FABRIC AND METHOD OF MAKING THE SAME


Leo N. Bernard, Plainfield, Conn., assignor to Pervel Industries, Inc., Plainfield, Conn.

Filed Mar. 25, 1980, Ser. No. 133,864

Int. Cl.³ D06P 5/00, 7/00

U.S. Cl. 8—488

40 Claims



1. The method of producing a dyed flocked fabric, which comprises selecting a suitable substrate fabric, coating the substrate fabric with a wet layer of flock adhesive, said adhesive having as an essential component thereof a selected heat-sublimable dye, selecting flock of a material capable of being dyed with a heat-sublimable dye, applying the selected flock to the wet coating of flock adhesive, drying the adhesive at a temperature less than that at which said dye sublimates, and then curing the adhesive by exposing the dried flocked substrate for a predetermined period of time to an elevated curing temperature at which said dye substantially fully sublimates.

4,294,578

COLORANTS

Friedrich W. Kröck, Cologne, and Rütger Neeff, Leverkusen, both of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Mar. 15, 1979, Ser. No. 20,867


Claims priority, application Fed. Rep. of Germany, Mar. 17, 1978, 2811718

Int. Cl.³ D06P 3/04, 1/24

U.S. Cl. 8—516

4 Claims

1. A polymeric material containing amide groups dyed with a dye which, in the form of the free acid, corresponds to the formula



in which

Z represents halogen or alkylcarbonylamino with 1-4 C atoms in the alkyl radical,
m is 0, 1 or 2 and n, r and s represent the numbers 0 or 1, with the proviso that the sum of n, r and s has a value of 1 or 2 and s can be 1 only if r at the same time is 0.

4,294,579

PROCESS FOR THE ONE-BATH, SINGLE-STAGE DYEING OR PRINTING OF CELLULOSE FIBRES WITH FIBRE-REACTIVE DISPERSE DYE STUFFS

Udo-Winifred Hendricks; Dietrich Hildebrand, both of Oden-
thal, and Robert Kuth, Cologne, all of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Aug. 27, 1979, Ser. No. 69,690

Claims priority, application Fed. Rep. of Germany, Apr. 7, 1979, 2914142


The portion of the term of this patent subsequent to May 19, 1998, has been disclaimed.

Int. Cl.³ D06P 3/66, 3/84

U.S. Cl. 8—549

3 Claims

1. In the dyeing and printing of fibres and textile materials containing cellulose wherein the fibres or textile materials are contacted with a padding liquor or printing paste containing a water-insoluble reactive disperse dyestuff in the absence of alkali or alkaline compounds, the improvement which comprises incorporating in the padding liquor or printing paste at least one compound of the formula



wherein

Z₁ is a monovalent to tetravalent aliphatic hydrocarbon radical with 1-5 carbon atoms,
n is 0-10, and
p is 1-4.

4,294,580

REACTIVE DYESTUFFS, THEIR PREPARATION AND THEIR USE FOR DYEING MATERIALS CONTAINING OH OR N

Hermann Henk, Cologne; Klaus Wunderlich, Leverkusen, and Peter Wild, Alten Buseck, all of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Dec. 31, 1979, Ser. No. 108,307


Claims priority, application Fed. Rep. of Germany, Jan. 16, 1979, 2901546

Int. Cl.³ C09B 62/06

U.S. Cl. 8—549

9 Claims

1. Reactive dyestuffs of the formula



wherein

Fb denotes the radical of an organic dyestuff, W denotes a direct bond or a bridge member, W being bonded to a C atom of an aromatic-carbocyclic ring of the chromophore Fb,

R1 denotes hydrogen, optionally substituted C1-C4-alkyl or aralkyl,

R2 denotes C2H4—OH,

R3 denotes hydrogen, C1-C4-alkyl, C1-C4-alkoxy, halogen, carboxyl, C1-C4-alkoxycarbonyl, C1-C4-alkyl- or -dialkyl-aminocarbonyl, optionally substituted arylaminocarbonyl, sulpho, C1-C4-alkyl- or -dialkyl-aminosulphonyl, hydroxyl, optionally substituted C1-C4-alkyl- or aryl-carbonylamino, formylamino, oxalylamino, optionally substituted ureido or sulphomethylene,

n is 0, 1, 2 or 3 and

m is 1 or 2.

4,294,581

UNIFORMLY DYED WATER-SWELLABLE CELLULOSIC FIBERS

Siegfried Mensch; Gerhard Epple, Weisenheim, and Wolfgang Elser, Wachenheim, all of Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Ludwigshafen, Fed. Rep. of Germany


Filed Nov. 16, 1979, Ser. No. 94,893

Int. Cl.³ C09B 1/00, 1/56

U.S. Cl. 8—611


6 Claims

1. Uniformly dyed water-swellaable cellulosic fibers prepared by a process comprising: contacting water-swellaable cellulosic fibers successively or simultaneously with water, with ethylene glycol, propylene glycol or a derivative thereof and, while the fibers are still swollen, with an essentially water-insoluble dye of the formula



where Y is phenyl which is unsubstituted, or is monosubstituted or disubstituted by C1-C4-alkyl, chlorine, bromine, nitro,

cyano, C1-C4-alkoxy, C1-C4-alkoxy-C2-C3-alkyl, C1-C4-alkylsulfonyl, C1-C4-alkanoylamino or phenoxy, the substituents, in the case of disubstitution, being identical or different, or is α - or β -naphthyl, thiazol-2-yl, 4-(C1-C4-alkyl)-thiazol-2-yl, 4-phenylthiazol-2-yl, 4-(C1-C4-alkyl)-thiazolin-2-yl, 4-phenylthiazolin-2-yl, 5-amino-thiazol-2-yl, pyrazol-5-yl, imidazol-2-yl, 3-(C1-C4-alkyl)-imidazol-2-yl, 3-(C1-C4-alkyl)-1,2,4-triazol-5-yl, 2-phenyl-1,3,4-thiadiazol-5-yl, 2- or 5-thio-1,3,4-thiadiazol-5- or -2-yl, 3-phenyl-1,2,4-thiadiazol-5-yl, 2-(C1-C4-alkyl)-1,3,4-oxadiazol-5-yl, 2-phenyl-1,3,4-oxadiazol-5-yl, pyrid-2-yl, quinol-2-yl, quinazol-2-yl, quinazol-4-yl, benzimidazol-2-yl, 3-(C1-C4-alkyl)-benzimidazol-2-yl, benzoxazol-2-yl or benzthiazol-2-yl, two of the three radicals X being hydroxyl and the remaining radical being



where A is (a) saturated, linear or branched, C1-C18-alkyl; (b) C2-C8-alkyl substituted by cyano, chlorine, bromine, carbonyl-C1-C5-alkoxy, N-C1-C8-alkylcarbonyl, N,N-di-C1-C8-alkylcarbonyl, C1-C4-alkylsulfonyl, amino, di-C1-C4-alkylamino or phenoxy, the number of substituents being 1 or 2; (c) C1-C10-alkoxy, alkoxyalkoxy and alkoxyalkyl of a total of 3 to 11 carbon atoms; (d) hydroxyalkoxyalkyl of a total of 4 to 10 carbon atoms, and alkoxyalkoxyalkyl of a total of 5 to 11 carbon atoms; (e) phenoxyalkoxyalkyl, where the alkoxyalkyl radical is of a total of 4 to 6 carbon atoms; (f) saturated 5-, 6-, 7- or 8-membered cycloalkyl or polycycloalkyl of a total of 5 to 15 carbon atoms; (g) C5-C8-cycloalkyl which is unsubstituted or mono-, di- or tri-substituted by C1-C8-alkyl, cycloalkyl or hydroxyl; (h) phenyl-C1-C4-alkyl, where alkyl is unsubstituted or substituted by hydroxyl and phenyl is unsubstituted or substituted by C1-C15-alkyl; (i) phenyl which is unsubstituted or in which from 1 to 3 hydrogen atoms are replaced by C1-C18-alkyl, hydroxyl, chlorine, bromine, trifluoromethyl, nitro, cyano, C1-C5-alkoxy, C1-C4-alkylthio, C1-C5-alkanoylamino, sulfamyl, N-C1-C8-alkylsulfamyl, N,N-di-C1-C8-alkylsulfamyl, N-phenylsulfamyl, carbamyl, N-C1-C8-alkylcarbonyl, N,N-di-C1-C8-alkylcarbonyl, N-phenylcarbonyl, where phenyl is unsubstituted or substituted by methoxy, ethoxy or methyl, carbalkoxy of a total of 2 to 6 carbon atoms, C1-C4-alkylsulfonyl, phenylsulfonyl, where phenyl is unsubstituted or substituted by C1-C4-alkyl, C1-C4-alkylcarbonyl, phenalkoxy of 7 to 10 carbon atoms or phenoxy, and, if more than one substituent is present, these may be identical or different and, if more than one alkyl, alkoxy or alkyl and alkoxy is present, the sum of the carbon atoms in these substituents is at most 12; (j) cyano; (k) carbalkoxy of a total of 2 to 12 carbon atoms; (l) nitro; (m) N-C1-C8-alkylamino or N,N-di-C1-C8-alkyl-amino; (n) carbamyl, N-C1-C8-alkylcarbonyl or N,N-di-C1-C8-alkylcarbonyl; (o) alkanoylamino of 2 to 12 carbon atoms; (p) C1-C6-alkylsulfonyl; (q) sulfamyl, N-C1-C8-alkyl-sulfamyl or N,N-di-C1-C8-alkylsulfamyl; (r) azophenyl; (s) phenoxy which is unsubstituted or in which 1 or 2 hydrogens are replaced by chlorine or bromine, or (t) α - or β -naphthyl, and n is 0, 1 or 2.

4,294,582

METHOD FOR PROCESSING A BODY LIQUID SPECIMEN

Jan I. Naslund, Vassvagen 21, Huddinge, Sweden


Continuation-in-part of Ser. No. 62,617, Aug. 1, 1979, abandoned, which is a continuation-in-part of Ser. No. 903,259, May 5, 1978, abandoned. This application Jul. 9, 1980, Ser. No. 167,199

Claims priority, application Sweden, May 17, 1977, 7705788

Int. Cl.³ A61B 10/00; G01N 1/10

U.S. Cl. 23—230 B

2 Claims



1. A method of processing a urine specimen for diagnostic examination, comprising the steps of: introducing a fixative into the lower, closed end of an elongated tube formed of flexible material; closing the tube with a first removable clip just above the portion containing the fixative; introducing the urine specimen into the tube through a collapsible hopper which forms an open upper end of the tube and which funnels the urine down into said tube just above said removable clip; permitting the urine specimen to separate, by settlement, to form a concentrate having a higher concentration of settled body cells than the rest of the urine specimen, and such that said concentrate is located adjacent the said removable clip; applying a further removable clip across the first chamber of said tube to separate some or all of said concentrate from the remainder of the urine specimen therein; removing said first removable clip to place said concentrate and said fixative into communication with each other to mix said concentrate with said fixative; and removing the remainder of the urine specimen from said tube.

4,294,583

HIGHLY SENSITIVE GAS MEASURING METHOD FOR THE ANALYSIS OF BREATH ALCOHOL CONCENTRATIONS, USING TEST TUBES

Kurt Lechnitz, Grosse Grönu, Fed. Rep. of Germany, assignor to Drägerwerk Aktiengesellschaft, Fed. Rep. of Germany

Filed Feb. 29, 1980, Ser. No. 125,978

Claims priority, application Fed. Rep. of Germany, Mar. 31, 1979, 2912967


Int. Cl.³ G01N 31/12, 31/22

U.S. Cl. 23—232 R

3 Claims

1. A method of testing a person's breath for the purpose of determining its alcohol content as an indication of the ethyl alcohol in the person's blood of the type using a colorimetric carbon monoxide gas detector tube, comprising obtaining a sample of expiratory breathing air of the person, conducting the sample through a pyrolysis oven and operating the pyroly-

sis oven to decompose the alcohol and form carbon monoxide, collecting a predetermined quantity of the pyrolyzed sample,



and passing the collected quantity through the detector tube to determine the quantity of carbon monoxide as an indication of the alcohol content.

4,294,584

DEWATERING OF COAL SLURRIES

Eke Verschuur, Amsterdam, Netherlands, assignor to Shell Oil Company, Houston, Tex.

Filed Nov. 10, 1980, Ser. No. 205,394

Claims priority, application Netherlands, Feb. 7, 1980, 8000750

Int. Cl.³ C10L 5/14, 5/22

U.S. Cl. 44—23

10 Claims

1. A process for dewatering a slurry of coal particles and for producing strong pellets therefrom comprising agglomerating the coal particles with a hydrocarbon binder at an elevated temperature to obtain coal pellets, subjecting the pellets to heat treatment at a temperature of between 200° and 300° C., contacting gases released by the coal pellets during the heat treatment with the slurry to remove condensable components from the gases and to transfer heat to the slurry, and burning at least a part of the non-condensable gases to produce heat for the heat treatment.

6. Apparatus for dewatering a slurry of coal particles and for producing strong pellets therefrom by agglomeration of the coal particles with a hydrocarbon binder at an elevated temperature comprising a slurry feed line, a pelletizer downstream of the slurry feed line, means for supplying binder to the pelletizer, mechanical dewatering means downstream of the pelletizer, heat treatment means downstream of the dewatering means, a recycle passageway for condensable and non-condensable gases from the heat treatment means to a scrubber situated in the slurry feed line upstream of the pelletizer, and means in the slurry feed line between the scrubber and the pelletizer for separating non-condensable gases from the slurry feed.

4,294,585

NOVEL FUEL COMPOSITION FOR INTERNAL COMBUSTION ENGINE

Rodney L. Sung, Fishkill, N.Y., assignor to Texaco Inc., White Plains, N.Y.

Filed Sep. 22, 1980, Ser. No. 189,530

Int. Cl.³ C10L 1/18, 1/22

U.S. Cl. 44—53

46 Claims

1. A fuel composition for internal combustion engines comprising

(a) a major portion of a fuel containing (i) at least one alcohol selected from the group consisting of ethanol and methanol and (ii) gasoline in amount of 0-50 volumes per volume of alcohol; and

(b) a minor corrosion inhibiting amount of, as a corrosion inhibiting agent, a reaction product of (i) an aminotetrazole, (ii) a ketone or an aldehyde, and (iii) a C3-C12 poly-primary amine bearing at least one free —NH2 group and at least one —NHR' group wherein R' is a C12-C18 hydrocarbon group.

4,294,586

GASOLINE AND DIESEL FUEL ADDITIVE

Charles P. Cox, Jr., 208 S. Sunnyside Rd., Decatur, Ill. 62522
Filed Jun. 5, 1980, Ser. No. 156,843
Int. Cl.³ C10L 1/18

U.S. Cl. 44—56

* 18 Claims

1. The process of making a fuel additive comprising the steps of:

- placing a predetermined quantity of alcohol in a mixing vessel;
- adding a predetermined quantity of toluene to said predetermined quantity of alcohol;
- blending thoroughly the aforesaid quantities of substances by vigorous agitation of the mixing vessel;
- adding a predetermined quantity of hydrogen peroxide; and then blending all together by further vigorous agitation of the mixing vessel.

4,294,587

MOTOR FUEL

Lyle D. Burns, Bartlesville, Okla., assignor to Phillips Petroleum Company, Bartlesville, Okla.

Filed Oct. 24, 1980, Ser. No. 200,366

Int. Cl.³ C10L 1/22

U.S. Cl. 44—74

9 Claims

1. An internal combustion fuel composition comprising a major proportion of a motor fuel containing a small but effective amount, sufficient to impart reduced knocking tendencies to said motor fuel, of an ashless antiknock additive selected from the group consisting of N-methyl-aniline (I), N-allyl-o-toluidine (II), and N-crotyl-p-toluidine.

4,294,588

ELECTROSTATIC PRECIPITATOR EFFICIENCY ENHANCEMENT

David M. Polizzotti, Yardley, and Joe C. Steelhammer, Lansdale, both of Pa., assignors to Betz Laboratories, Inc., Trevo, Pa.

Continuation-in-part of Ser. No. 140,287, Apr. 14, 1980, Pat. No. 4,239,504, which is a continuation-in-part of Ser. No. 29,414, Apr. 12, 1979, abandoned. This application Nov. 17, 1980, Ser. No. 207,173

Int. Cl.³ B03C 3/00

U.S. Cl. 55—5

37 Claims

1. In an electrostatic precipitator, a method for removing particles from a particle-laden gas stream, which method comprises electrically charging the particles by passing the gas stream through an ionization field and attracting the thus-charged particles to a grounded collecting electrode for collection, the improvement comprising: prior to collection of the particles distributing across the gas stream within the ionization field from about 1 to 200 parts of an additive selected from the group of morpholine, morpholine compounds, and mixtures thereof per million parts of gas to enhance the efficiency of particle removal.

4,294,589

METHOD FOR REMOVING TRAPPED GAS UNDER POND LINERS

Richard E. Zachary, Clinton, La., assignor to The Dow Chemical Company, Midland, Mich.

Filed Dec. 22, 1977, Ser. No. 863,633

Int. Cl.³ B01D 53/00

U.S. Cl. 55—36

5 Claims

1. A method for removing trapped gases under a liner in a lined pond adapted for storing liquids comprising:

- (a) partially filling the pond excavation under the liner with a liquid thereby floating the liner on the liquid and collecting the trapped gases between the surface of the liquid and liner;
- (b) Progressively filling the pond of top of the liner with another liquid thereby forcing the trapped gases beneath

the liner to the sides of the pond and venting the gases up the sides of the pond to the atmosphere; and
(c) draining away the liquid under the liner thereby settling the liner onto the bottom of the pond excavation.

4,294,590

REMOVAL OF UNDESIRE GASEOUS COMPONENTS FROM HOT WASTE GASES

Gerhard Linde, Gruenwald; Peter Haeussinger, Munich, and Claus Schliebener, Strasslach, all of Fed. Rep. of Germany, assignors to Linde Aktiengesellschaft, Wiesbaden, Fed. Rep. of Germany


Filed Nov. 9, 1979, Ser. No. 93,089

Claims priority, application Fed. Rep. of Germany, Nov. 11, 1978, 2848721; Oct. 25, 1979, 2943130

Int. Cl.³ B01D 53/14

U.S. Cl. 55—48

28 Claims



1. In a process for removing undesired gaseous components from hot combustion gases by scrubbing with a regenerable absorbent,

the improvement which comprises:

conducting the scrubbing with a liquid physical absorbent at a temperature less than 0° C. and supplying cooling requirements of the scrubbing process by means of an absorption-type refrigeration unit, cooling the combustion gases prior to scrubbing, in indirect heat exchange with gas streams to be heated, the indirect heat exchange being performed in an upper temperature range and a subsequent lower temperature range and using air as said gas stream to be heated in the upper temperature range of the indirect heat exchange, resultant heated air being used in part as (a) preheated air of combustion and in part as (b) an energy source for the operation of the absorption-type refrigeration unit.

4,294,591

MOUNTING FOR HIGH-VOLTAGE ELECTRODE SUPPORT FRAME IN AN ELECTROSTATIC PRECIPITATOR

Melvin R. Kahl, Richland, Pa., assignor to Envirotech Corporation, Menlo Park, Calif.

Filed May 12, 1980, Ser. No. 148,845


Int. Cl.³ B03C 3/70, 3/41; H01B 17/54, 17/52

U.S. Cl. 55—120

9 Claims

1. In an electrostatic precipitator having a housing with an opening formed therein and a mounting assembly suspending an electrically conductive support frame for a high-voltage electrode in the electrostatic precipitator, said mounting assembly comprising:

- (a) an electrical insulator having a bore therethrough, said insulator being secured to said housing of the precipitator circumjacent the opening therein;
- (b) a substantially gas-tight housing portion, stationed on said housing over said opening, said housing portion enclosing said insulator;
- (c) fastening means for securing said support frame to said insulator, said fastening means including:
 - (i) an elongate portion affixed to said support frame and extending upward through said opening and through said insulator bore, and
 - (ii) a connecting portion extending outward from said



elongate portion and bearing against said insulator, said connecting portion having inlet ports for permitting gas flow from said housing portion into said bore;

(d) means for introducing heated gas into said housing portion; and

(e) a porous fabric skirt positioned in said insulator bore so that heated gas flowing from said housing portion into said insulator bore passes through said porous fabric skirt as it enters into said precipitator, said skirt being mechanically fastened to said connecting portion and to a bottom portion of said insulator to prevent direct exposure of the bore of the insulator to particulate-laden gas within the precipitator housing.

4,294,592

APPARATUS FOR THE HYDRAULIC TRANSPORT OF PRECIPITATOR DUST

Horst Buchmüller, Hünxe, and Bernhard Michelbrink, Wesel, both of Fed. Rep. of Germany, assignors to Deutsche Babcock Aktiengesellschaft, Oberhausen, Fed. Rep. of Germany


Filed Jun. 20, 1980, Ser. No. 161,653

Claims priority, application Fed. Rep. of Germany, Jun. 29, 1979, 2926330

Int. Cl.³ B03C 3/00

U.S. Cl. 55—120

5 Claims



1. Apparatus for precipitating dust and the hydraulic transport of precipitator dust from a precipitator plant, comprising precipitator cells; a plurality of hoppers consecutively arranged in flow direction of gas to be cleaned by said precipitator cells; discharge means connected to said hoppers; a sluice chamber for each hopper and connected to said discharge

means underneath said hoppers, said sluice chamber having an inlet for rinse water and an outlet for a mixture of rinse water and precipitator dust; the outlet of the sluice chamber of the rear hopper in gas flow direction being connected with the inlet of the sluice chamber of the preceding hopper by one sluiceway each, only the sluice chamber of the last hopper being supplied with fresh rinse water; each chamber having only a single source of rinse water, the sluice chamber of the last hopper having an outlet connected to an inlet of its immediately preceding sluice chamber so that said latter chamber is rinsed with water already containing filtered dust; said latter chamber having an outlet connected to the input of its own immediately preceding chamber so that the rinse water flows thereby in sequence through all sluice chambers located below the individual hoppers, the rinse water becoming increasingly laden with dust in its flow direction, the flow direction of the rinse water being opposite to the flow direction of the gas to be cleaned.

4,294,593


DRILLING MUD DEGASSER APPARATUS AND SYSTEM

William A. Rehm, 1726 Augusta, Suite 113, Houston, Tex. 77057
Filed May 2, 1980, Ser. No. 145,895

Int. Cl.³ B01D 19/00

U.S. Cl. 55—166

15 Claims



1. A drilling mud degasser system comprising a tank having an inlet for drilling mud and an overhead outlet for removal of gas and a bottom outlet for removal of degassed mud, a plurality of blowers operatively connected to said overhead outlet for evacuating the same to remove gas from drilling mud therein, pressure operated switch means operable to energize said blowers successively upon occurrence of a predetermined pressure on the inlet side of said blowers, and thermostatic switch means responsive to gas temperature on the outlet sides of said blowers and operable upon occurrence of a predetermined temperature to deenergize at least one of said blowers.

15. A drilling mud degasser tank comprising a hollow enclosed tank having a side inlet for receiving drilling mud, a top outlet for removal of gas, and a bottom outlet for removal of degassed drilling mud, a helical shelf supported inside the wall of said tank having the bottom end thereof adjacent to said side inlet to receive drilling mud thereon and spiralling upward along the tank wall so that mud moving along said shelf may fall as a thin sheet or film into the interior of the tank, thus facilitating removal of gas therefrom, and said helical shelf narrower at its bottom end than at its top end and tapering outward from bottom to top along its helical length.

4,294,594

SELF-CONTAINED FILTER ASSEMBLY FOR REMOVING AIR, PARTICLES AND BACTERIA FROM A SOLUTION


Thomas E. Sloane, Jr., West Redding; Clair Melius, Southport, both of Conn., and Erich Kling, Carmel, N.Y., assignors to United States Surgical Corporation, Norwalk, Conn.

Filed Oct. 2, 1979, Ser. No. 81,185

Int. Cl.³ B01D 25/00, 53/22

U.S. Cl. 55—186

15 Claims



1. A filter assembly for removing particulate matter, bacteria, and air from a liquid, said filter assembly comprising: a housing having first, second, and third chambers; inlet means for receiving said liquid containing air in said first chamber; first venting means for venting said air in said first chamber to the atmosphere; passage means providing a fluid passage from said first chamber to said second chamber; prefilter means for preventing particulate matter in said liquid from entering said second chamber; second venting means for venting to the atmosphere the air entering said second chamber; means providing a fluid passage from said second chamber to said third chamber; bacteria filtering means for preventing air and bacteria in said second chamber from entering said third chamber; and outlet means for providing an exit for the liquid in said third chamber.

4,294,595

VACUUM CLEANER INCLUDING AUTOMATIC SHUTOFF DEVICE

Leonard E. Bowerman, Fairfield, Conn., assignor to Electrolux Corporation, Old Greenwich, Conn.

Filed Jul. 18, 1980, Ser. No. 170,244

Int. Cl.³ B01D 46/46; A47L 9/12


U.S. Cl. 55—213

7 Claims

1. In a vacuum cleaner having a motor, a nozzle intake, dirty air passageways extending from the nozzle intake to a filter, a housing for the filter, and a door in the housing for access to the filter, a fan operably connected to the motor to draw air through the dirty air passageways and the filter, and a clean air passageway extending between the filter and the fan, the improvement comprising:

means for sensing the differential pressure between the dirty air passageways at a first point adjacent the nozzle intake and at a second point along the clean air passageway, and a first switch means responsive to a predetermined change in

the differential pressure due to clogging of the dirty air passageways or a full filter, relay means normally electrically connecting said first switch means and the motor, said relay means being activated in response to said first switch means to interrupt power to the motor until said relay is reset,



- a second switch means operatively connected through said relay means to interrupt power to the motor in response to the absence of the filter in the filter housing, and a bypass valve means selectively connecting said sensing means to atmosphere for defeating the operation of said pressure differential sensing means to thereby permit an auxiliary cleaning tool to be operatively connected along the dirty air passageway.

4,294,596

AIR-FILTER APPARATUS IN COMBINATION WITH A TURBINE ENGINE


Dan Taveraz, 17375 Brookhurst, No. 46, Fountain Valley, Calif. 92644

Filed Apr. 25, 1980, Ser. No. 143,880

Int. Cl.³ B01D 45/10, 46/04, 46/22

U.S. Cl. 55—242

3 Claims



1. An air-filter apparatus in combination with a turbine engine having an air intake, wherein said air-filter apparatus comprises:

an air filter formed as a continuous movable loop positioned transversely over the air intake of said turbine engine, said air filter being defined by a continuously formed belt-like blanket of fibrous material to filter foreign matter, and having a first outer layer and a second inner layer which continuously move in opposite directions from each other longitudinally; means for movably supporting said looped air filter, whereby said air filter moves longitudinally about said support means, said support means including rotatable support spindle guides and tension spindles; a first drive means positioned and arranged to drive said air filter;

4,294,598

APPARATUS FOR THE SEPARATION OF GAS MIXTURES, PARTICULARLY THE ENRICHMENT OF A GAS MIXTURE IN A COMPONENT CONTAINING URANIUM 235

Hans O. E. Gazda, Anton-Krieger-Gasse 155, A-1238 Wien, Austria

Division of Ser. No. 889,395, Mar. 23, 1978, Pat. No. 4,225,324.

This application Jul. 19, 1979, Ser. No. 59,055

Claims priority, application Austria, Mar. 24, 1977, 2076/77

Int. Cl.³ B01D 45/14

U.S. Cl. 55—403

5 Claims

- a pair of rotating brushes, each brush being positioned within respective looped ends of said air filter to engage said first and second layers thereof;
- brush-drive means attached to said brushes to rotate said brushes at a speed less or greater than the longitudinal movement of said air filter;
- means for applying a cleaning fluid to said air filter, which comprises a plurality of holes formed in said support spindle guides, to supply the cleaning fluid directly to said air filter and a reservoir having a pump interconnected to said support spindle guides, to provide cleaning fluid to said support rollers as said air filter moves thereon;
- a pair of vacuum systems, each being positioned on opposite sides of said turbine engine and having vacuum means for removing said foreign matter from said air filter, and said vacuum systems being connected to said air intake such that said air intake provides a vacuum source.

4,294,597

LINT COLLECTING SYSTEM AND APPARATUS


Ronald J. Archer, 3414 Brookglen, Garland, Tex. 75042, and Richard V. Fetterly, 12801 Champion Forest Dr., Houston, Tex. 77066

Filed Mar. 17, 1980, Ser. No. 131,280


Int. Cl.³ B01D 46/04

U.S. Cl. 55—283

9 Claims



1. In an air cleaning system having a rotary filter means and bin structure: said bin structure comprising, a bin with a plenum chamber; said filter means comprising roller filter means mounted in the top of said bin plenum chamber; doffer roller means for removing bat deposited on said roller filter means; air flow system means for delivery of particle laden air to said bin plenum chamber, and developing a pressure differential across from a first side to a second side of said roller filter means and for exhausting air from the second side of said roller filter means and from said bin; barrier wall means within said bin extending down from said doffer roller means through a substantial vertical distance within said bin to provide a still chamber generally separate from said plenum chamber, with bat removed from said roller filter means falling through said still chamber to the bottom of said bin and air lock means for removing deposited material from bottom of said bin.



1. An apparatus for separating a light component from a heavy component in a gas mixture, said apparatus comprising: a housing; a shaft rotatable about an upright axis; and extending into said housing; a motor operatively connected to said shaft for rotating same; a plurality of axially spaced centrifugal disks positioned in said housing and mounted on said shaft and rotatable therewith, each of said disks being formed with a radial passage extending from a central portion of the respective disk outwardly and opening into a peripheral compartment of greater axial width than the passage at the outer periphery of the respective disk; means for feeding said gas mixture centrally to a first of said disks for acceleration outwardly through its radial passage whereby a turbulent flow is formed along the peripheral compartment of said first of said disks; means in said housing for recovering a light component from said mixture through the passage of said first of said disks and including a duct reaching into said boundary layer from said housing at a location thereon radially outwardly of said one of said disks; means for feeding the light component collected from the boundary layer of said first of said disks and supplying it centrally to a second of said disks for acceleration through the passage of said second of said disks whereby another boundary layer is maintained adjacent the periphery of said second of said disks by the interaction of the accelerated light component in said second of said disks and the surrounding body of gas retained by the respective compartment of said housing; and a further duct reaching radially from said housing into said boundary layer of said second of said disks to collect a light component therefrom whereby said disks are connected in cascade for multistage recovery of said light component from said mixture.

4,294,599

AEROSOL FILTER CARTRIDGE


William R. Grovesteen, Southbridge, and John A. Jones, Wilbraham, both of Mass., assignors to American Optical Corporation, Southbridge, Mass.

Filed Feb. 19, 1980, Ser. No. 122,206

Int. Cl.³ B01D 50/00, 46/12

U.S. Cl. 55—485

6 Claims



1. In an aerosol filter cartridge having a shell containing an air filtering system including final filtering components, the improvement of a prefiltering component comprising:

an elongated mat of glass fibers, said mat being closely spiraled with opposite edges thereof providing opposite air-receiving and air-emitting faces of said component, one of said faces being adjacent to said final filtering components and a side of said spiraled mat being closely fitted against said shell.

4,294,600

VALVES FOR CRYOGENIC REFRIGERATORS


Domenico S. Sarcia, Carlisle, Mass., and Calvin K. Lam, Bedford, N.H., assignors to Oerlikon-Bührle U.S.A. Inc., New York, N.Y.

Filed Oct. 29, 1979, Ser. No. 89,272

Int. Cl.³ F25B 9/00

U.S. Cl. 62—6

29 Claims



19. A cryogenic refrigerator comprising:

cylinder means;
displacer means movable within the cylinder means according to a four step sequence wherein it (a) dwells in an uppermost position, (b) moves downwardly, (c) dwells in a lowermost position and (d) moves upwardly again; first and second chambers the volumes of which are defined by movement of the displacer means,
conduit means connecting said first and second chambers, thermal storage means associated with said conduit means, supply reservoir means for supplying high pressure fluid;

exhaust reservoir means for receiving low pressure fluid; and refrigerator regulating valve means associated with the supply and exhaust reservoir means for causing high pressure fluid to enter the first chamber and the conduit means during the first-mentioned and second-mentioned steps of the displacer means motion and to exhaust low-pressure fluid during the third and fourth steps of the displacer means motion, said valve means comprising a valve casing fixed with respect to the cylinder means and a valve member slidable relative to the casing, the casing having one or more pairs of diametrically opposed inlet ports communicating with said supply reservoir means and one or more pairs of diametrically opposed outlet ports communicating with said exhaust reservoir means, said valve casing and valve member also having cooperating means for alternately connecting said first chamber to said inlet or outlet ports according to the movement of the valve member between two limit positions, and cooperating means on the displacer means and valve member for (a) causing the valve member to be in one of its limit positions and the displacer means to be in its uppermost position concurrently, and (b) causing the valve member to be in its other limit position and the displacer means to be in its lowermost position concurrently.

4,294,601

APPARATUS AND PROCESS FOR AUTOMATIC CONTROL OF THE PRODUCTION OF OPTICAL FIBER


Franklin W. Dabby, Woodbridge, and Ronald B. Chesler, Cheshire, both of Conn., assignors to Times Fiber Communications, Inc., Wallingford, Conn.

Filed Jul. 13, 1979, Ser. No. 57,501

Int. Cl.³ C03B 37/025, 37/07, 37/075

U.S. Cl. 65—3.12

19 Claims



16. In a process for the production of optical fiber comprising preparing a preform by depositing and sintering glass particles on a cylindrical glass rod, heating said preform to the drawing temperature, and drawing said preform into optical fiber, the improvement comprising continuously monitoring the diameter of the glass rod during deposition of the glass particles and adjusting the composition of said particles in response to the diameter measurement such that the particles are uniformly distributed across the length of the rod at the appropriate composition for a given radial distance from the rod axis.

4,294,602

ELECTRO-OPTICALLY ASSISTED BONDING

William E. Horne, Bellevue, Wash., assignor to The Boeing Company, Seattle, Wash.

Filed Aug. 9, 1979, Ser. No. 64,994


Int. Cl.³ C03C 27/00

U.S. Cl. 65—40

12 Claims

1. A method of integrally bonding a cover glass to a surface of a semiconductor cell having conductors thereon, comprising the steps of:

providing a semiconductor cell and a cover glass having a desired ratio of energy absorptions at a certain wavelength;
juxtaposing the cover glass and the semiconductor cell, the conductors spacing apart the cover glass and the semiconductor cell;
applying a predetermined electrostatically-bonding high voltage between the outer surfaces of the juxtaposed cover glass and the semiconductor cell;
pre-heating the juxtaposed cover glass and the semiconductor cell to a first temperature sufficient to promote ion drift in the cover glass and to establish an electrostatic field between the cover glass and the cell; and



irradiating the juxtaposed cover glass and the semiconductor cell with a pulsed beam of electromagnetic energy at the certain wavelength on a path substantially normal to said cover glass to heat the juxtaposed cover glass and the silicon cell to a second temperature higher than the first temperature except in those regions above the conductors which are heated to a third temperature higher than the second temperature due to reflection back into said cover glass of the pulsed beam by the conductors, the third temperature sufficient to enable the cover glass to soften and flow around the conductors so that the cover glass is electrostatically drawn toward the adjacent surface of the semiconductor cell to bond the surfaces thereof along substantially all of the interface therebetween.

4,294,603

GLASS FOREHEARTH CONSTRUCTION


Frederick W. Winzer, East Granby, and James R. Ault, New Britain, both of Conn., assignors to Emhart Industries, Inc., Farmington, Conn.

Filed Sep. 4, 1979, Ser. No. 71,923

Int. Cl.³ C03B 5/16

U.S. Cl. 65—346

1 Claim



1. A molten glass forehearth comprising an elongated channel for constraining the flow of molten glass, a roof structure for said channel and including side blocks of heat conductive refractory material supported on the channel sides, said roof structure including arch blocks also of heat conductive refractory material supported on said side blocks, said roof structure defining top openings at longitudinally spaced locations in the forehearth, closure blocks supported in spaced relationship above said top openings, roof superstructure means supported by said side blocks and said arch blocks, said roof superstructure means including a plurality of longitudinally spaced

blocks defining transverse muffled cooling air passageways therebetween, a source of cooling air communicating with the outer ends of said muffled cooling air passageways, inner ends of said muffled cooling air passageways communicating with said top openings, said roof superstructure further including insulating bricks supported by said longitudinally spaced blocks to provide for substantial heat transfer from said refractory brick roof structure to the cooling air flowing in said muffled cooling air passageways, said refractory blocks of said roof structure defining direct cooling air passages having inner ends communicating with the interior of said forehearth channel to direct air along the interior of the arch blocks toward said top openings, and outer ends of said direct cooling air passageways communicating with a plenum defined by said roof superstructure insulating bricks, said plenum also communicating with said transverse muffled cooling air passageways and with said source of cooling air, and means for selectively closing said direct cooling air passageways.

4,294,604

USE OF SELECTED

N-(2,6-DIMETHYLPHENYL)-ALANINE METHYL ESTER COMPOUNDS AS AMMONIUM NITRIFICATION COMPOUNDS

Thomas O. Evrard, Little Rock, Ark., assignor to Olin Corporation, New Haven, Conn.


Filed Feb. 25, 1980, Ser. No. 124,185

Int. Cl.³ C05C 11/00


U.S. Cl. 71—27

12 Claims

1. A method for inhibiting the nitrification of ammonium-nitrogen in soil which comprises treating the soil with an effective nitrification-inhibiting amount of at least one of the nitrification-inhibiting compounds having the formula:



wherein R is selected from the group consisting of:



4,294,605

AGENTS FOR THE DEFOLIATION OF PLANTS

Friedrich Arndt, Reinhard Rusch, and Heinz Schulz, all of Berlin, Fed. Rep. of Germany, assignors to Schering Aktiengesellschaft, Berlin and Bergkamen, Fed. Rep. of Germany

Continuation of Ser. No. 651,522, Jan. 22, 1976, abandoned. This application Nov. 21, 1979, Ser. No. 96,577

Claims priority, application Fed. Rep. of Germany, Feb. 14, 1975, 2506690

Int. Cl.³ A01N 43/82

U.S. Cl. 71—73

3 Claims

1. Method for defoliating cotton plants, comprising applying to the plants N-phenyl-N¹-1,2,3-thiadiazol-5-yl urea of the formula

weight) of Ca and at least 0.001 (by weight) of B or Ce or their mixture.

4,294,614

AUSTENITIC IRON-BASE CRYOGENIC ALLOY AND ARC WELDING ELECTRODE FOR DEPOSITING THE SAME

Damian J. Kotecki, Spring Garden Township, York County, Pa., assignor to Teledyne Industries, Inc., Los Angeles, Calif.

Filed Oct. 17, 1979, Ser. No. 85,471

Int. Cl.³ C22C 39/54, 38/04, 38/44

U.S. Cl. 75—128 A

4 Claims

1. An austenitic iron-base cryogenic alloy consisting essentially of, in weight percent,

Carbon	0.05 min. to 0.20 max.
Manganese	3.5 to 7.0
Silicon	0.75 max.
Chromium	13.0 to 17.0
Nickel	14.0 min.
Molybdenum	1 to 3
Iron plus unavoidable impurities	Balance,

and containing no more than 2FN delta ferrite, said alloy displaying at least 15 mils lateral expansion when impact tested by the Charpy V-notch test at -320°F .

4,294,615

TITANIUM ALLOYS OF THE TIAL TYPE



Martin J. Blackburn, Kensington, and Michael P. Smith, Glasstonbury, both of Conn., assignors to United Technologies Corporation, Hartford, Conn.

Filed Jul. 25, 1979, Ser. No. 60,265

Int. Cl.³ C22C 14/00; C21D 1/00

U.S. Cl. 75—175.5

6 Claims



1. A cast and forged titanium alloy with ductility at room temperature and good high temperature strength, consisting essentially of by weight percent 31-36 aluminum, 0.1-4 vanadium, balance titanium (in atomic percent, about: 45-50Al, 0.1V, bal Ti).

4,294,616

ELECTRICAL CONTACTS


Han J. Kim, Greensburg, Pa.; Thomas E. Peters, Chelmsford, and John Gustafson, Harvard, both of Mass., assignors to GTE Products Corporation, Stamford, Conn.

Filed Jan. 2, 1979, Ser. No. 628

Int. Cl.³ H01H 1/02

U.S. Cl. 75—234

5 Claims



1. An electrical contact having a working surface consisting essentially of from about 50 to about 95 percent by weight silver or silver alloy, from about 5 to about 50 percent by weight of cadmium oxide, and an additional oxide selected from the oxides of germanium, tantalum, and mixtures thereof, said additional oxide being present in an effective amount sufficient to reduce the surface energy between said working surface and the liquid phase of said silver and being substantially homogeneously distributed on said surface in a silver matrix.

4,294,617

COMPOSITIONS AND METHODS FOR THE DENATURATION OF WATER-BASE PAINTS

Philippe Schlicklin, Nancy; Anne-Marie Mertzweiler nee Mailard, Maidieres, and Jacques Ploussard, Pont a Mousson, all of France, assignors to Air Industrie, France

Continuation of Ser. No. 938,909, Sep. 1, 1978, abandoned. This application Apr. 21, 1980, Ser. No. 141,796


Claims priority, application France, Sep. 6, 1977, 77 26948

Int. Cl.³ C09D 5/08

U.S. Cl. 106—14.37

9 Claims

1. Method for the denaturation of water-base paints, characterized in that the paint is contacted with and dispersed in a solution containing between 1.5 to 10 g/l of at least one sulphate of iron (II), of magnesium or of manganese and at least one non-ionic surface active agent corresponding to general formula



in which R is an alkyl, aryl, aryl-alkyl or alkyl-aryl group, containing at least 10 carbon atoms, and n and p are whole numbers of which one may be zero, and n+p being comprised between 12 and 100, said solution having a pH during use of between 6.5 and 8.0.

4,294,618

SILICA-DOPED, CHROME-ALUMINA MONOLITHIC REFRACTORY COMPOSITIONS

Henry E. Anthonis, Annapolis, Md., assignor to General Refractories Company, Bala Cynwyd, Pa.

Filed May 27, 1980, Ser. No. 152,992

Int. Cl.³ C04B 35/10, 35/12

U.S. Cl. 501—129

8 Claims

1. A monolithic refractory composition comprising: from about 63% to 90% by weight high purity Al₂O₃;

from about -2-8% by weight free crystalline silica having a particle size of -200 mesh; from about 2-6% by weight high purity of Cr₂O₃; from about 1-8% by weight high purity kaolin clay having a particle size of -10μ (micron); and from about 5-15% by weight phosphate binder.

4,294,619

METHOD OF PRODUCING PIGMENTED SILICATE COATINGS

Donald C. Dulaney, Gurnee, and John A. Bowman, Wheeling, both of Ill., assignors to Rust-Oleum Corporation, Vernon Hills, Ill.

Filed Apr. 1, 1980, Ser. No. 136,322

Int. Cl.³ C09D 5/04, 5/08, 5/10

U.S. Cl. 106—188

4 Claims

1. A method of manufacturing pigmented hydrolyzed ethyl silicate binders suitable for use in zinc-rich primers wherein an extender pigment suitable for use in zinc-rich primers is added to an organic solvent containing ethyl hydroxy ethyl cellulose, ground in a paint manufacturing grinder to the proper size, and added to a solution containing partially hydrolyzed ethyl silicate.

4,294,620

PHTHALOCYANINE FORMULATIONS

Reinhard Sappok, Heidelberg, and Joachim Kranz, Ludwigshafen, both of Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Ludwigshafen, Fed. Rep. of Germany

Filed Jan. 29, 1980, Ser. No. 116,582

Int. Cl.³ C09B 47/08

U.S. Cl. 106—288 Q

10 Claims

1. A pigmentary phthalocyanine formulation, prepared by a process comprising: dry milling (a) a crude phthalocyanine with (b) from 2 to 20% by weight, based on (a), of at least one urea derivative of the formula:



where K is 1,5-naphthylene or 4,4'-diphenylenemethane; R is alkyl of 12 to 18 carbon atoms, alkenyl of 12 to 18 carbon atoms, 3-(alkoxy of 8 to 18 carbon atoms)-propyl, 2-(alkylthio of 8 to 18 carbon atoms)-ethyl, 2-(alkylamino of 8 to 18 carbon atoms)-ethyl or $-(\text{CH}_2)_3-\text{O}-(\text{CH}_2\text{CH}_2\text{O})_n-\text{R}^1$, wherein R¹ is alkyl of 2 to 8 carbon atoms or phenyl; and n is a integer of 1 to 4, in the absence of a grinding medium.

4,294,621

PRODUCTION OF AN ANTICORROSIVE PIGMENT ON PHOSPHATE BASIS

Alexander Maurer; Renate Adrian, both of Hürth; Klaus Hestermann, and Gero Heymer, both of Erfstadt, all of Fed. Rep. of Germany, assignors to Hoechst Aktiengesellschaft, Fed. Rep. of Germany

Filed Apr. 16, 1980, Ser. No. 141,135

Claims priority, application Fed. Rep. of Germany, Apr. 20, 1979, 2916029

Int. Cl.³ C08K 3/10; C09D 5/08

U.S. Cl. 106—306

8 Claims

1. A process for making phosphorus-containing anticorrosive pigments with a particle size of at most 20 microns which comprises: converting, with agitation, fine pulverulent calcium and magnesium compounds selected from the group consisting of oxides, hydroxides, carbonates, basic carbonates or carboxylates together with water to a homogeneous suspension; intimately mixing said suspension inside a dispersing means rotating at a speed of 3000 to 10,000 rpm at 0° to 40° C. and in an approximately stoichiometric ratio with phosphoric acid or a solution of acid alkali metal or ammonium phosphates; separating resulting and precipitated pigment and drying it while maintaining its content of water of crystallization, the anticorrosive pigment being comprised of a homogeneous mixture or

mixed crystals of which 10 to 95 mol% is calcium hydrogen phosphate dihydrate, the balance being magnesium hydrogen phosphate trihydrate, and of which an at least 55 weight% proportion consists of particles with a size of up to 5 microns with a BET-surface area of at least 1 m²/g.

4,294,622

DRY WALL JOINT AND FINISHING COMPOUNDS

William F. Brown, Wausau, Wis., assignor to Weston Research Corporation, Wausau, Wis.

Division of Ser. No. 954,445, Oct. 25, 1978, Pat. No. 4,238,239. This application Jun. 9, 1980, Ser. No. 157,306

Int. Cl.³ C04B 11/14

U.S. Cl. 106—314

2 Claims

1. A liquid additive composition for admixing with a wall board joint compound to provide a joint cement, said liquid additive composition comprising an aqueous mixture containing about 0.35 to about 8 weight % zinc oxide, about 0.35 to about 1.5 weight % sodium acetate, about 0.35 to about 3 weight % ammonium alum, and about 0.35 to about 8 weight % of an acrylic resin, based on the total weight of the aqueous mixture.

4,294,623

METHOD OF PRODUCING HIGH PURITY MALTOSE

Hidemasa Hidaka, Urawa; Toshiaki Kohno, Yokohama, and Toshiaki Eida, Chigasaki, all of Japan, assignors to Meiji Seika Kaisha, Ltd., Tokyo, Japan

Filed Dec. 5, 1979, Ser. No. 100,435

Claims priority, application Japan, Dec. 7, 1978, 53-150547

Int. Cl.³ C13D 3/12; C13K 7/00; C12P 19/22

U.S. Cl. 127—55

3 Claims

1. Method of producing high purity maltose having more than 97% of maltose content from a saccharified liquor containing less than 0.5% of glucose, 60-85% of maltose and less than 5% of maltotriose, the remainder oligosaccharide and/or dextrin, comprising passing said saccharified liquor through a column filled with granular activated carbon having a peak micropore diameter above 25 Å, thereby removing mainly dextrin, and then passing the liquor through a column filled with granular activated carbon having a main peak of micropore diameter distribution below 25 Å, thereby removing mainly oligosaccharide, and eluting without using any organic solvent.

4,294,624

DRYING CO-MINGLED CARBOHYDRATE SOLUTION AND RECYCLED PRODUCT BY DIELECTRIC HEATING

Preston L. Veltman, 212 Old County Rd., Severna Park, Md. 21146

Filed Mar. 14, 1980, Ser. No. 130,531

Int. Cl.³ C13F 1/00, 5/00; C13K 11/00


U.S. Cl. 127—62

13 Claims

1. A process for drying a carbohydrate solution to form a stable, solid, substantially anhydrous particulate product therefrom comprising:

- co-mingling said carbohydrate solution with recycled dry product solid to form a particulate admixture dryable in a dielectrically heated drying zone;
- drying said particulate admixture in said dielectrically heated drying zone at a particle temperature below the melting point of said particulate admixture to form said stable, solid, substantially anhydrous product;
- removing said stable, solid, substantially anhydrous prod-

uct from the drying zone and dividing it into a first portion and a second portion;



- (d) recycling said first portion; and
(e) recovering said second portion.


4,294,625

ALUMINUM ALLOY PRODUCTS AND METHODS
Michael V. Hyatt, Bellevue, and William E. Quist, Redmond, Wash., assignors to The Boeing Company, Seattle, Wash.

Continuation-in-part of Ser. No. 974,484, Dec. 29, 1978, abandoned. This application Apr. 18, 1980, Ser. No. 141,272
Int. Cl.³ C22F 1/04; C22C 21/16

U.S. Cl. 148—2

33 Claims



11. A method for producing a plate product from an aluminum alloy, said product having high strength, high toughness and improved fatigue properties comprising the steps of providing an alloy consisting essentially of

weight percent	element
3.8 to 4.4	Cu
1.2 to 1.8	Mg
0.3 to 0.9	Mn
0.12 maximum	Si
0.15 maximum	Fe
0.25 maximum	Zn
0.15 maximum	Ti
0.10 maximum	Cr
0.05 maximum	each trace element
0.15 maximum	total of trace elements
balance	Al

casting said alloy into a body,
hot working said body to form a plate product,
solution heat treating the alloy in said product such that the maximum amount of Cu is taken into solid solution during the solution heat treating step;
quenching said product,

preaging said alloy at room temperature,
thereafter cold rolling said product to reduce the thickness of said product,
and
thereafter stretching said product to relieve residual stresses in said product.

4,294,626

METHOD FOR THE TREATMENT OF SURFACES AND APPARATUS EMPLOYED IN SAID METHOD

Atsushi Kirisawa, Maehara, Japan, assignor to Japan Envirotic Industry Co., Ltd., Nagoya, Japan


Filed Nov. 2, 1979, Ser. No. 90,578

Claims priority, application Japan, Nov. 9, 1978, 53-138487

Int. Cl.³ C23F 7/26

U.S. Cl. 148—6.2

2 Claims



1. A method of the chromate treatment which comprises: filling materials to be treated into holed container rotatably equipped in a vessel, charging water into said vessel with or without rotation of said holed container, exhausting said water with rotation of said holed container, charging nitric acid solution into said vessel with or without rotation of said holed container, exhausting said nitric acid solution with rotation of said holed container, charging water into said vessel with or without rotation of said holed container, exhausting said water with rotation of said holed container, charging chromate solution into said vessel with or without rotation of said holed container, exhausting said chromate solution with rotation of said holed container, charging water into said vessel with or without rotation of said holed container, exhausting said water with rotation of said holed container, and dehydrating and drying said material treated.

4,294,627

TREATMENT OF TINPLATE SURFACES

Peter J. Heyes, Swindon, England, assignor to Metal Box Limited, Reading, England

Filed May 28, 1980, Ser. No. 153,910

Claims priority, application United Kingdom, Jun. 7, 1979, 19793/79; Apr. 25, 1980, 13748/80

Int. Cl.³ C23F 7/02

U.S. Cl. 148—6.14 R

8 Claims

1. A method of treating a tinplate surface comprising the steps: wetting said tinplate surface with a solution-free of organic polymeric materials and consisting essentially of a solvent, and a zirconium compound selected from the group consisting of ammonium zirconium carbonate and zirconium acetate at a concentration, calculated as ZrO_2 , in the range between 0.1 and 10% w/w; and thereafter heating said tinplate surface to a temperature in the range between 20° and 300° C. until said surface is dry.

4,294,628

METHOD FOR THE PRODUCTION OF CATHODE FOR USE IN ELECTROLYSIS

Kazuki Kasuya, Ichihara, Japan, assignor to Chlorine Engineers Corp., Ltd., Tokyo, Japan

Division of Ser. No. 008,813, Feb. 2, 1979, Pat. No. 4,238,311.

This application Jun. 17, 1980, Ser. No. 160,333

Claims priority, application Japan, Feb. 20, 1978, 53/17690

Int. Cl.³ C25B 11/06, 11/02; B01J 25/02

U.S. Cl. 148—6.35

4 Claims

1. A method for producing a cathode for use in electrolysis which comprises:

- (a) forming a compact layer of Fe_3O_4 on a substrate of iron or an alloy of iron; and
(b) coating activating nickel comprising mainly nickel or an alloy of nickel on the Fe_3O_4 layer.

4,294,630

METHOD AND APPARATUS FOR THE CONTINUOUS FURNACE BRAZING AND SOFT-NITRIDING TREATMENTS OF IRON ARTICLES

Teruoki Watanabe; Tadao Kanno; Akio Hidaka, all of Kawagoe, and Shunji Kobayashi, Sayama, all of Japan, assignors to Honda Giken Kogyo Kabushiki Kaisha, Tokyo, Japan


Filed Jul. 12, 1979, Ser. No. 56,922

Claims priority, application Japan, Jul. 12, 1978, 53-84680; Jul. 13, 1978, 53-85384

Int. Cl.³ C21D 1/48

U.S. Cl. 148—16.6

12 Claims



1. A method for the continuous furnace brazing and gas soft-nitriding treatments of an iron member, comprising the steps of:

subjecting the iron member to a furnace brazing treatment in a controlled gas for brazing;
furnace-cooling the brazed member only sufficiently to attain a temperature suitable for a subsequent gas soft-nitriding treatment, such that sufficient heat energy is retained from said brazing treatment without re-heating said member for said gas soft-nitriding treatment; and
adding a predetermined amount of ammonia gas to said controlled gas to conduct said gas soft-nitriding treatment of said member in the resulting atmosphere.

4,294,631

SURFACE CORROSION INHIBITION OF ZIRCONIUM ALLOYS BY LASER SURFACE β -QUENCHING


Thomas R. Anthony, Schenectady, N.Y., and Harvey E. Cline, Stanford, Calif., assignors to General Electric Company, Schenectady, N.Y.

Filed Dec. 22, 1978, Ser. No. 972,389

Int. Cl.³ C22F 1/18; B23K 26/00

U.S. Cl. 148—133

9 Claims



1. In a process for the thermal treatment of drawn copper-zinc-lead brass alloy stock to improve the machinability by ensuring fine short shavings, the improvement which comprises:

providing a billet consisting essentially on the basis of weight percentage

zinc	30 to 42
lead	1.5 to 4.5
arsenic	≤ 0.1
aluminum	≤ 2.5
tin	≤ 1.3
iron	≤ 0.1
silicon	≤ 0.01
copper	balance;

- extruding said stock to obtain a blank;
subjecting the blank to a drawing pass to provide stock of a desired final dimension;
subjecting the drawn stock to a rapid annealing comprising heating said drawn stock to a temperature between about 425° C. and about 10° C. below the solidus temperature of the alloy for a period of between about 1/100 of a second and about 10 minutes.

1. A method for improving the corrosion resistance of a body of a zirconium alloy to high pressure and high temperature steam including the process steps of

- (a) heating substantially isothermally, without melting, by means of a scanning laser beam a surface region of said body to a temperature range for a sufficient period of time to assure nucleation and growth of the body centered cubic β grains of said zirconium alloy material; and
(b) quenching said heated surface region at a rate effective to form thereby a metallurgical microstructure in said sur-

face region consisting of β -quenched zirconium alloy material, said surface region encompassing thereby a core of zirconium alloy material, said core having a metallurgical structure selected to maximize the physical and mechanical properties of the body.

4,294,632

METHOD FOR OVERAGING OF HOT DIP METAL COATED STEEL MATERIAL


Michio Kubota; Kazuhiro Takagi, both of Amagasaki, and Yorimasa Mitani, Osaka, all of Japan, assignors to Nisshin Steel Co., Ltd., Tokyo, Japan

Filed Sep. 24, 1979, Ser. No. 78,407

Int. Cl.³ C21D 6/02, 9/48

U.S. Cl. 148—142

5 Claims



1. A continuous method for the overaging of a hot dip metal coated steel sheet material to improve the formability of the material, which is hard due to the presence of C and N in the form of supersaturated solid solution, said method comprising the steps of continuously passing the material through a heating zone so as to rapidly heat the material at a rate of heating of at least 50° C./sec. to a temperature above 300° C. but below that at which alloying of the coating with the base steel or formation of additional alloys not already present in the coated material will substantially take place, and continuously passing the heated material through a cooling zone so as to cool the material at a controlled rate of cooling of not more than 20° C./sec. until the supersaturation of C and N in the base steel substantially disappears.

4,294,633

BLASTING COMPOSITION


Robert B. Clay, 728 West 3800 South, Bountiful, Utah 84010

Filed Jun. 7, 1979, Ser. No. 46,360

Int. Cl.³ C06B 45/00

U.S. Cl. 149—2

14 Claims



1. A blasting agent having a bulk density above 1.0 grams per cc. of generally solid or plastic solid consistency, based

largely on particulate ammonium nitrate, which comprises, in combination:

- 60 to 90% by weight, based on the total, of solid particulate oxidizer sale which includes ammonium nitrate, and
- 10 to 40% by weight of a thickened liquid component comprising a nitrate oxidizer salt dissolved in a polar organic solvent selected from the group which consists of methanol, ethylene glycol and, said solution being substantially fully saturated by said salt and only partially filling the interstices in component (a) to provide for sensitizing the overall composition to detonation by standard detonating devices.

4,294,634

METHOD FOR MANUFACTURING A SOLID STATUE

Byun Mookil, 190, Simkoc-dong, Buchyun-shi, Kyungki-do, Rep. of Korea

Filed Apr. 1, 1980, Ser. No. 136,267

Int. Cl.³ B32B 31/22; B44C 3/02; G09B 25/00

U.S. Cl. 156—59

7 Claims



1. A method of producing a three-dimensional solid art object comprising:
forming a solid basic body and component parts from a shapeable art medium in initial shapes corresponding approximately to those of said solid basic body and said component parts when said three-dimensional solid art object is assembled and finished,
adhesively attaching said component parts on said solid basic body to form an assembled object with a three-dimensional surface;
adhesively and conformationally attaching a covering sheet to the three-dimensional surface of said assembled object to form said three-dimensional solid art object.

4,294,635

PROCESS FOR MAKING GLAZED CERAMIC WARE

Donald C. Hurley, Jr., 183 St. Joseph Ave., Long Beach, Calif. 90803

Continuation-in-part of Ser. No. 718,344, Aug. 27, 1976, Pat. No. 4,200,468. This application Jan. 28, 1980, Ser. No. 116,229

Int. Cl.³ C03C 5/02

U.S. Cl. 156—89

8 Claims

1. A process for making a glazed ceramic ware comprising the steps of:

- mixing sufficient clay, feldspar, flux and water containing a deflocculant to form a slurry glaze-forming composition, said slurry composition consisting essentially of at least 30%, by weight, of clay, and where the molecular ratio of flux to alumina to silica in said slurry is from 1-0.1-1.15 to 1-1.05-9.2 and wherein said deflocculant is included with said water to minimize the amount of said water necessary to form said slurry;
- applying the slurry onto the surface of an unfired clay body to form a decorative pattern;
- firing the combined clay body and decorative pattern so that they are matured in one firing operation.

4,294,636

METHOD AND APPARATUS FOR MAKING WIRE REINFORCED HOSE


Frank A. Vitellaro, Trenton, N.J., assignor to Dayco Corporation, Dayton, Ohio

Filed Jul. 10, 1980, Ser. No. 167,293

Int. Cl.³ B65H 81/00

U.S. Cl. 156—143

12 Claims



1. A method for producing a reinforced flexible polymeric hose which comprises the steps of extruding a continuous flat strip of polymeric material, forming said flat strip to define a profiled strip having a flat side portion and a convoluted portion by continuously passing said flat strip between two profiled rollers to thereby define the desired strip profile with the convoluted side portion, and thereafter helically winding said profiled strip with adjoining turns in overlapping relation, disposing a reinforcing wire in said convoluted side portion in sandwiched relation between the overlapping portions during said helical winding step, and bonding together the overlapping portions.

8. A flexible hose forming apparatus comprising:

- extruder means for forming an elongated flat strip of polymeric material;
- means for shaping said flat strip to define a profiled strip having a flat side portion and a convoluted side portion, said strip shaping means comprising at least two spaced profiled rollers having parallel axes of rotation, a first of said rollers having a circumferential ridge and a second of said rollers having a corresponding circumferential groove, said ridge and said groove cooperating to form a convolution in said polymeric strip passing therebetween;
- means for helically winding said profiled strip with adjoining turns having portions in overlapping relation;
- means for disposing a reinforcing wire in said convoluted side portion in sandwiched relation between said overlapped strip portions; and
- means for bonding said overlapping portions.

4,294,637

PROCESS FOR MANUFACTURE OF A WIDE PATTERNED BAND SUCH AS A TRANSFER-CARRYING SHEET AND FOR PRINTING ON A SUBSTRATE THEREWITH

Björn S. Rump, Le Rossignol, Vandoeuvres, Switzerland (1253), assignor to Björn Sigurd Rump, Switzerland

Division of Ser. No. 598,545, Jul. 23, 1975, abandoned, which is a continuation of Ser. No. 893,289, Apr. 5, 1978, abandoned, which is a continuation of Ser. No. 961,231, Nov. 16, 1978. This application Dec. 21, 1977, Ser. No. 862,834

Claims priority, application Switzerland, Jul. 31, 1974,

10568/74; Jul. 31, 1974, 10570/74


Int. Cl.³ B44C 1/16; B41M 5/26; B31F 5/00; B65H 69/02

U.S. Cl. 156—157

16 Claims

1. A process for the transfer printing of a substrate from opaque transfer webs of lesser width than said substrate, said transfer webs each having a straight edge and carrying transferable designs or patterns, said process comprising the steps

of: aligning, at least two transfer webs with their respective straight edges near and parallel to each other; feeding the thus aligned transfer webs, together with the substrate onto which the designs or patterns are to be transferred, into transfer means; and transferring the designs or patterns onto the substrate in the transfer means after previously adjusting the rela-



tive position of the webs in a direction parallel to said straight edges, utilizing registration means which are formed on said transfer webs but are separate from and non-transferable with said designs or patterns, in such a manner that the designs or patterns on each of said transfer webs are in register with each other during said transferring step.

4,294,638

CIRCULAR EXTRUSION METHOD PROVIDING FOR ROTATION AROUND THE EXTRUSION OPENING

Ole-Bendt Rasmussen, 7, Topstykke, 3460 Birkerød, Denmark


Continuation of Ser. No. 841,481, Oct. 12, 1977, abandoned, which is a continuation of Ser. No. 657,649, Feb. 12, 1976, abandoned. This application Dec. 11, 1979, Ser. No. 102,561

Claims priority, application United Kingdom, Feb. 12, 1975, 5971/75

Int. Cl.³ B29F 3/10

U.S. Cl. 156—176

35 Claims



1. An improved method of extruding elongated structures in annular form, by feeding an inhomogeneous extrudable material in a generally fluid state through a circular die which has a hollow center and an annular die part defining at least one extrusion exit orifice extending annularly around the die part and rotating bodily around its axis to extrude with substantial helical drawing or stretching a material structure in generally annular form which has a generally uniaxial grain therein extending in a substantially helical direction making a significant angle with respect to the extrusion die axis, the method being characterized by the following steps:

- supplying said extrudable material to said circular die while rotating said annular die part;
- discharging the extrudable material from the rotating exit orifice defined by said die part in at least one stream extending in generally annular form;
- collecting the thus discharged generally annular-form stream of extrudable material in a collecting zone downstream of such exit orifice by collecting means comprising a generally rigid support and a conveying surface which receives said stream and at least said conveying surface extending axially through said hollow interior and being moved forwardly along the extrusion die axis to convey

the extrudable material stream collected thereon from said die orifice while said annular die part is rotating bodily around its axis about said conveying surface, whereby the material stream is drawn or stretched at an angle to the extrusion axis by virtue of said rotation between said exit orifice and said conveying surface; solidifying the collected material stream while being conveyed; and removing said solidified material stream from at least the support of said collecting means.

4,294,639


FIBER-REINFORCED COMPOSITE WHEEL CONSTRUCTION

James A. Woelfel, and Richard W. Smith, both of Lansing, Mich., assignors to Motor Wheel Corporation, Lansing, Mich. Continuation-in-part of Ser. No. 14,265, Feb. 22, 1979, abandoned. This application Feb. 6, 1980, Ser. No. 119,128

Int. Cl.³ B65H 81/00

U.S. Cl. 156—185

44 Claims



1. A method of constructing a vehicle wheel of the type which includes a rim portion for mounting of a tire thereon and a disc portion for mounting the wheel to a vehicle, said method comprising the steps of:

- coiling a first sheet section of fiber-reinforced plastic resin construction having laterally spaced parallel side edges to form a rim charge hoop consisting of at least one coil ply having said laterally spaced side edges disposed in respective axially spaced planes;
- placing said rim charge hoop in a mold;
- placing a separate disc charge into said mold within said rim charge hoop, said disc charge comprising at least one second sheet section of fiber-reinforced plastic resin construction;
- compression molding said rim and disc charge to form an integral fiber-reinforced composite wheel; and
- removing said wheel from said mold.

4,294,640

FORMING PROCESS FOR LIGHT GAUGE POLYMER SHEET MATERIAL

Lawrence G. Martinelli, San Jose, and Mark R. Garrison, Santa Clara, both of Calif., assignors to Verbatim Corporation, Sunnyvale, Calif.

Filed Dec. 12, 1979, Ser. No. 102,777

Int. Cl.³ B29C 17/04; B29F 1/10; B29C 3/00; B65D 85/30

U.S. Cl. 156—213

5 Claims

1. A method for forming a substantially flat, warp-free flexible magnetic disk jacket assembly from a pre-cut sheet of light

gauge polymeric material having wipe material pre-attached to one planar side thereof, comprising the steps of:

- clamping a rear panel region of a pre-cut sheet of light gauge polymeric material having wipe material pre-attached to one planar side thereof between a first substantially rigid base and a second substantially rigid square-shaped folding member so that said wipe material is contacted by said substantially rigid folding member, said pre-cut sheet being essentially at room temperature;
- folding a front panel region of said sheet over said substantially rigid folding member by means of a first substantially rigid folding bar into a substantially 180° flat fold whereby a first folded edge is formed in said sheet;
- retaining said front panel region of said sheet in said folded condition without slippage by means of said first substantially rigid folding bar;
- folding a first and a second tab region of said sheet over said front panel region by means of a second and a third substantially rigid folding bar into substantially 180° flat folds whereby a second and a third folded edge are formed in said sheet, said second and third folded edges being formed essentially perpendicularly to and extending from opposite terminal ends of said first folded edge along opposite edges of said rear panel region whereby a pocket is formed between said front panel region and said rear panel region, said pocket being enclosed around its edges by said first, second and third folded edges, said pocket having an open end along an edge of said front panel

- region opposite to said first folded edge, said open end extending between said terminal ends of said second and said third folded edge furthest from said first folded edge;
- retaining said first and second tab regions of said sheet in said folded condition without slippage by means of said second and third substantially rigid folding bar;
- applying heat uniformly along said first, second and third folded edges of said sheet by contacting said outer surface of said sheet with a first, a second and a third heated bar having a U-shaped trough adapted to mate with said outer surface of said sheet along said folded edges;
- inserting a flexible magnetic disk into said pocket;
- folding a third tab region of said sheet over said front panel region by means of a fourth substantially rigid folding bar into a substantially 180° flat fold whereby a fourth folded edge is formed in said sheet, said fourth folded edge being formed essentially perpendicular to said second and third folded edge, extending between said terminal ends of said second and third folded edge furthest from said first folded edge;
- retaining said third tab region of said sheet in said folded condition without slippage by means of said fourth substantially rigid folding bar; and
- applying heat uniformly along said fourth folded edge of said sheet by contacting said outer surface of said sheet with a fourth heated bar having a U-shaped trough adapted to mate with said outer surface of said sheet along said folded edge.

4,294,641

HEAT TRANSFER SHEETS

Kenneth J. Reed, Deer Park Rd., Wimbledon, London, S.W. 19, and Alan L. Lythgoe, 25 Sene Park, Hythe, Kent, both of England

Continuation of Ser. No. 817,707, Jul. 21, 1977, abandoned. This application Jul. 6, 1979, Ser. No. 55,929

Claims priority, application United Kingdom; Jul. 23, 1976, 30925/76

Int. Cl.³ B32B 3/18; B41M 5/26; B44C 1/16

U.S. Cl. 156—234

34 Claims

1. A method of marking or decorating a textile or other absorbent surface with a design, said method comprising the steps of:

- providing a heat transfer including a flexible support substrate coated with a solid printing ink layer embodying the design to be transferred;
- contacting the printing ink layer face to face with the textile under conditions of temperature and pressure which do not damage the textile and which cause the solid printing ink layer to melt to a liquid ink composition having a viscosity less than 100 poise and to penetrate the textile and transfer the ink layer to the textile as a nonlabel like design;
- separating the support substrate from the textile with the transferred design being retained in the form of solid ink within the textile;
- said solid printing ink layer being substantially non-tacky and non-blocking at room temperature and including at least one polymer having solid particles of a tack reducing agent present as a separate phase in at least a surface portion of the layer;
- said tack reducing agent being sublimable at said elevated temperature or having a melting point of at least 60° C. and melting at said elevated temperature to a liquid which reduces the viscosity of the polymer composition.

4,294,642

PROCESS FOR THE PRODUCTION OF PACKAGE FOR CIGARETTES OR THE LIKE

Heinz Focke, and Kurt Liedtke, both of Verden, Fed. Rep. of Germany, assignors to Focke & Pfuhl, Verden, Fed. Rep. of Germany

Division of Ser. No. 886,700, Mar. 15, 1978, Pat. No. 4,225,040.


This application Dec. 5, 1979, Ser. No. 100,784

Claims priority, application Fed. Rep. of Germany, Mar. 22, 1977, 2712482

Int. Cl.³ B65D 85/10

U.S. Cl. 156—250

3 Claims



1. A method for the production of cigarette pack blanks from a web of relatively thick, stiff cardboard, paste board or the like, said blanks being subsequently folded in a U-shape around the front, bottom and rear surfaces of a rectangular block of cigarettes, and wherein the lateral edges of said web coincide with the upper edges of the blanks laid out thereon, after folding, characterized by the steps of:

- coating one entire surface of said web (34) with a moisture and aroma-proof metal coating (17), said one surface being the outer surface of the folded cigarette pack;
- applying by gluing or the like a pair of relatively thin and

pliable, continuous strips of metal foil (11a, 11b) to the respective lateral edges of said web on the other side thereof opposite said metal coating such that the outer edges of said metal foil strips extend outwardly beyond the lateral edges of said web;

- applying a relatively thin and pliable sealing layer (30, 33) of metal foil to said other side of said web at least in the areas which form the four bottom corners of the folded pack; and
- separating said blanks from said web by cross stamping.

4,294,643

HEATER ASSEMBLY AND METHOD OF FORMING SAME

Thomas D. Tadewald, La Crosse, Wis., assignor to UOP Inc., Des Plaines, Ill.

Filed Sep. 5, 1978, Ser. No. 939,764

Int. Cl.³ B29C 19/00; B32B 31/00

U.S. Cl. 156—293

7 Claims



1. A method of forming a heater plate assembly comprising the steps of: forming a C-stage laminate assembly from layers of glass cloth and epoxy resin with at least one cut-out opening therein for receiving at least one complementary shaped heater member; laying up a stack of B-stage layers of epoxy resin coated glass; positioning at least one heater member within said at least one cut-out opening in said C-stage assembly so that its flat outer surface is exposed and its inner surface is in surface contact with said stack of B-stage layers; applying heat and pressure to the top and bottom of said final laminate assembly to cure said B-stage layers and bond them to each other and to said C-stage laminate and to the inner surface of said at least one heater member; said at least one heater member being of a more thermally conductive material than the adjacent portions of C-stage laminate so that when said heat is applied, the resin in the B-stage layers in the regions immediately laterally adjacent the said at least one heater member will become liquid sooner than in areas further laterally spaced from said at least one heater member and will tend to flow toward said heater member and seal the open area between the edges of the heater member and the internal edges of the C-stage laminate which define said at least one opening.

4,294,644

SERVO MOTOR CONTROL LABELLER

Dale L. Anderson, Mound, Minn., assignor to Datafile Limited, Toronto, Ontario, Canada

Filed Jan. 30, 1980, Ser. No. 112,341


Int. Cl.³ B32B 31/00

U.S. Cl. 156—361

48 Claims

1. In a labeller actuated to advance and dispense labels by a rotary drive onto a surface fed therepast, a servo motor for actuating said labeller drive and a control system for said servo motor, said system having means adapted to respond to the rate of feed of a surface to be labelled to accelerate the servo motor from zero to the desired labelling speed corresponding to the rate of feed of the surface to be labelled while the surface to be labelled is advanced towards the labeller a predetermined distance, and means to decelerate the servo motor from labelling speed to zero while label feed is advanced a predetermined distance, the system being adapted so that upon a label instructing signal being fed to the control system at a preselected point of advance of the surface towards the labeller, the labeller will accelerate a label from a predetermined start position and

deliver same to touch down on the surface to be labelled at the precise desired point with the label moving at the same speed as the surface and upon a label feed sensing signal generated by



label feed being fed to the control system the labeller will decelerate to bring the next label to be delivered to said predetermined start position in preparation for the next label instructing signal.

4,294,645

LABEL APPLICATORS

Anthony V. J. Figg, Spalding, and Harry Cunningham, Boston, both of England, assignors to Norprint Limited, Boston, England

PCT No. PCT/GB79/00005, § 371 Date Sep. 12, 1979, § 102(e) Date Sep. 12, 1979, PCT Pub. No. WO79/00499, PCT Pub. Date Aug. 9, 1979


PCT Filed Jan. 11, 1979, Ser. No. 74,724

Claims priority, application United Kingdom, Jan. 12, 1978, 1160/78; Jul. 20, 1978, 30511/78

Int. Cl.³ B32B 31/00

U.S. Cl. 156—384

19 Claims



1. Apparatus for dispensing individual labels from a web of labels including a backing strip and a series of labels mounted on the backing strip, said apparatus comprising in succession along a web path through the apparatus, reel mounting means for carrying a reel of the said web, continuously-operative brake means for applying a continuous braking force to the web, a rotary registration device co-operating with the web, dispensing means at which individual labels can be peeled from the backing strip of the web, a take-up reel for taking up spent backing strip, and means for synchronously actuating the registration device and the take-up reel to index the web through the apparatus and dispense a label at the dispensing means.

4,294,646
APPARATUS FOR MANUFACTURING FLAT PLASTIC NET

Thomas Urquhart, Cobourg, Canada, assignor to E. I. Du Pont de Nemours and Company, Wilmington, Del.

Division of Ser. No. 26,206, Apr. 2, 1979, Pat. No. 4,242,295.


This application Jun. 3, 1980, Ser. No. 155,980

Claims priority, application Canada, Oct. 4, 1978, 312717

Int. Cl.³ B29C 17/14

U.S. Cl. 156—500

5 Claims



1. An apparatus comprising in combination (a) an extruder adapted to extrude, about an axis of extrusion, plastic net in tubular form through two coaxial circular counter-rotating die members, said plastic net comprising a plurality of crossing plastic strands; (b) a detector adapted to detect the angular displacement of substantially successive longitudinally-aligned junctions of the crossing strands about the axis of extrusion and relative to a fixed plane through the axis of extrusion; (c) a controller adapted to regulate the relative rotation of the die members to minimize said angular displacement; (d) guide means, adapted to align successive longitudinally aligned junctions of the strands of the tubular net with a cutting means, said cutting means being adapted to cut each junction longitudinally and within each junction; and (e) advancing means adapted to move the tubular net from the extruder past said cutting means, and to tension the tubular net during extrusion of the plastic net.

4,294,647

WOOD FINGER JOINTING APPARATUS


Melvin D. Strickler, 192 Larch La., Columbia Falls, Mont. 59912

Filed May 20, 1980, Ser. No. 151,714

Int. Cl.³ B27F 1/16; B32B 31/20


U.S. Cl. 156—558

7 Claims



1. Apparatus for end joining straight elongated boards having a preselected maximum length and a common transverse cross section, the boards having complementary configurations of elongated parallel fingers formed between opposed side edges of the boards across opposed first and second transverse end faces thereof, comprising: an elongated frame; guide means on the frame for engaging the opposed side

edges of the boards and directing the boards along a straight path parallel to the board lengths; ram means movably mounted on said frame at a location adjacent the guide means at one end of the path for reciprocating movement along the path in a first direction for engaging successive boards across their first end faces and for imparting movement to the boards along the path their second end faces into mating engagement with the first end faces of preceeding boards and in an opposite second direction for providing clearance for engagement of incoming boards by said guide means; said ram means having a ram face for engaging the first end faces of the boards, said ram face having a configuration matching the finger configuration of the first board ends; channel means on said frame positioned transversely adjacent to the path for receiving successive boards moved along the path by the ram means and for transversely engaging the opposed edges of the board to align the first end of each board with the second end of a preceding board at the instant of mating the joint between them; and thrusting means on the frame for clamping opposed side edges of the boards and forcibly resisting movement of the mated first and second ends of successive boards as imparted by said ram means.



ured the same as the lines of said master image are formed on each die plate, and thereafter selectively removing material from at least one side of the raised portions on each plate until the lands of each plate are formed.

4,294,650

METHOD OF AND APPARATUS FOR PRODUCING EMBOSSED TOOLS

Wilfried Werthmann, Krefeld, Fed. Rep. of Germany, assignor to Firma Standex International GmbH, Krefeld, Fed. Rep. of Germany

Continuation of Ser. No. 878,432, Feb. 16, 1978, Pat. No. 4,213,819. This application Jan. 7, 1980, Ser. No. 110,252

Claims priority, application Fed. Rep. of Germany, Feb. 18, 1977, 2706947

The portion of the term of this patent subsequent to Jul. 22, 1997, has been disclaimed.

Int. Cl.³ C23F 1/02

9 Claims

7 Claims

4,294,648
METHOD FOR INCREASING THE RESISTANCE OF IGNITER ELEMENTS OF GIVEN GEOMETRY


Uwe Brede, Fürth, and Heinz Kern, Fürth-Burgfarnbach, both of Fed. Rep. of Germany, assignors to Dynamit Nobel Aktiengesellschaft, Postfach, Fed. Rep. of Germany

Filed Feb. 26, 1980, Ser. No. 124,894

Claims priority, application Fed. Rep. of Germany, Mar. 3, 1979, 2908361

Int. Cl.³ C23F 1/02

U.S. Cl. 156—627



1. A method for increasing the resistance of an igniter element of given geometry in an electrical circuit to a predetermined, specific value by the removal of resistance material, which comprises heating the resistance material situated between two acid-resistance electrodes simultaneously etching the resistance material with acid until the desired resistance value has been established.

4,294,649

METHOD OF MAKING DIE PLATES

Albert J. Sarka, 18828 Canyon Dr., Fairview Park, Ohio 44126

Filed Nov. 5, 1979, Ser. No. 91,361


Int. Cl.³ C23F 1/02

U.S. Cl. 156—645

7 Claims

1. A method of forming accurately located lands on an opposing pair of die plates, the lands cooperating to cut material pressed between the die plates in regions where the lands on one die plate are positioned in a predetermined relationship with the lands on the opposite die plate, said method comprising the steps of forming a master image having lines representing the lands to be formed on both die plates, the lines in said master image having a width exceeding by a predetermined amount a desired width of the cooperating lands on the die

1. A method of making a large-format surface-texture embossing tool free from pattern-separating lines for the embossing plates, sheets, or foils, said method comprising the steps of: (a) juxtaposing a large-format press plate having a width in excess of 160 centimeters with a synthetic elastic-surfaced transfer roll of a length substantially corresponding to said width; (b) applying a layer of an etching resist to a patterned roll having a surface texture corresponding to the pattern to be applied to said plate to impart a corresponding pattern to said layer; (c) rotating said rolls into close proximity to each other to deposit said layer onto said transfer roll substantially over a length thereof corresponding to said width; (d) rolling said transfer roll over a surface of said press plate and relatively displacing said transfer roll and said press plate to deposit the layer of said resist from the synthetic elastic surface of said transfer roll onto said surface of said plate while leaving exposed locations of said surface of said plate within the pattern of the resist layer deposited thereon;



(e) etching said locations of said surface of said plate; and
(f) repeating steps (a) through (e) in succession with application of a second layer of resist to said surface of said plate in a pattern out of perfect registry with the previously applied pattern.

4,294,651

METHOD OF SURFACE-TREATING SEMICONDUCTOR SUBSTRATE

Sohshi Ohmura, Kawasaki, Japan, assignor to Fujitsu Limited, Kawasaki, Japan


Filed May 16, 1980, Ser. No. 150,686

Claims priority, application Japan, May 18, 1979, 54-61228

Int. Cl.³ C09K 13/02, 13/08; H01L 21/306

U.S. Cl. 156-662

10 Claims



1. A method of roughening at least one surface of a silicon semiconductor substrate comprising the step of bringing each surface of the semiconductor substrate that is to be roughened into contact with an etchant comprising (i) at least one fluorine-containing compound selected from the group consisting of hydrofluoric acid (HF), ammonium fluoride (NH₄F) and acid ammonium fluoride (NH₄HF₂), (ii) at least one oxidizing agent selectively containing manganese and chromium, and (iii) an alkali.

2. The method of claim 1, wherein the etchant contains, based on the weight of the etchant, (i) 7% to 38% by weight of the fluorine-containing compound, (ii) 2.5% to 7% by weight of the manganese- or chromium-containing oxidizing agent and (iii) 1% to 10% by weight of the alkali.

3. The method of claim 1, wherein the etchant comprises, based on the weight of the etchant, (i) 13% to 35% by weight of the fluorine-containing compound and (ii) 3% to 7% by weight of the oxidizing agent.

7. A method according to claim 1, 2 or 3, wherein prior to the step of bringing each surface of the semiconductor substrate to be etched into contact with the etchant, each said surface is subjected to a pre-etching by using an etchant comprising (i) at least one fluorine-containing compound selected from the group consisting of hydrofluoric acid (HF), ammonium fluoride (NH₄F) and acid ammonium fluoride (NH₄HF₂) and (ii) at least one manganese-containing oxidizing agent selected from the group consisting of potassium permanganate (KMnO₄) and potassium manganate (K₂MnO₄).

4,294,652

FALLING STRAND DEVOLATILIZER

Randolph E. Newman, Belchertown, Mass., assignor to Monsanto Company, St. Louis, Mo.

Filed Jun. 30, 1980, Ser. No. 164,414


Int. Cl.³ B01D 1/00

U.S. Cl. 159-2 R

5 Claims

1. An improved staged falling strand devolatilizing apparatus for a polymer-monomer melt, comprising a heating means for said melt mounted integrally above first and second flash vaporization tanks positioned respectively in contiguous descending vertical relationship and communicating with one another, means for producing a different vacuum within each of said flash vaporization tanks and means for maintaining an elevated temperature in said tanks, the improvement comprising: said second tank having a baffle means to pass the falling strand melt to a first bottom side compartment of said second tank, a recycle transfer means for the melt from said first side compartment to a second bottom side compartment in said second tank such that the melt is devolatilized again by the

vacuum applied to said second tank and a means to withdraw the melt from said second side compartment, said first and second bottom side compartments are formed by a generally vertical partition dividing said second tank into substantially



4,294,653

PROCESS FOR MANUFACTURING CHEMIMECHANICAL CELLULOSE PULP IN A HIGH YIELD WITHIN THE RANGE FROM 65 TO 95%

Jonas A. I. Lindahl, Domsjoverken, and Lars G. Rudstrom, Husum, both of Sweden, assignors to Mo och Domsjo Aktiebolag, Ornskoldsvik, Sweden


Continuation-in-part of Ser. No. 615,625, Sep. 22, 1975, abandoned. This application Apr. 11, 1978, Ser. No. 895,163

Claims priority, application Sweden, Sep. 23, 1974, 7411949

Int. Cl.² D21B 1/16; D21D 1/20

U.S. Cl. 162-25

33 Claims



1. In the process for the manufacture of chemimechanical cellulose pulp in high yields within the range from about 65 to about 95% from particulate lignocellulosic material which comprises subjecting particulate lignocellulosic material to a mild partial digestion in the presence of a delignifying agent, and then mechanically defibrating the partially digested material, the improvement which comprises blending the partially digested lignocellulosic material after it has been defibrated to

within the range from about 27 to about 44% of completion with waste bleaching liquor from a lignin-preserving bleaching process cooled to a temperature not exceeding 40° C.; and then completing the defibration to obtain a pulp of improved brightness and strength.

4,294,654

DELIGNIFICATION AND BLEACHING OF LIGNOCELLULOSIC PULP VIA PHOTO-OXYGENATION

Rex H. Turner, Mobile, Ala., assignor to International Paper Company, New York, N.Y.

Filed Mar. 21, 1980, Ser. No. 132,604

Int. Cl.³ D21C 5/00, 9/10

U.S. Cl. 162-50

12 Claims

1. A process for delignification and bleaching of lignocellulosic pulp employing electronically excited oxygen generated in situ, which comprises:

subjecting an aqueous slurry of said lignocellulosic pulp having a consistency of from about 0.01% to about 10.0%, by weight of oven-dried pulp, and whose slurry pH is between about 8 and about 13 to irradiation with ultraviolet light while admitting oxygen into said slurry, whereby the ultraviolet light excites the oxygen to produce electronically excited oxygen in situ which bleaches and delignifies the pulp.

4,294,655

METHOD AND APPARATUS FOR FORMING FIBERGLASS MATS

John R. Pfeffer, Bakersfield, Calif., assignor to Consolidated Fiberglass Products Company, Bakersfield, Calif.


Continuation of Ser. No. 886,881, Mar. 15, 1978, abandoned.

This application Nov. 27, 1979, Ser. No. 97,776

Int. Cl.³ D21H 3/82

U.S. Cl. 162-107

14 Claims



1. The method of making a wet process fiber mat comprising the steps of:

- forming an aqueous body of chopped fiber slurry;
- moving an endless screen upwardly through said slurry from an entrance position spaced substantially below said slurry surface and at a predetermined rate of movement to an exit position at the surface of said slurry;
- applying suction to the lower surface of said screen, in a zone through which said screen moves in order to draw water of said slurry through said screen thereby;
- collecting a first layer of chopped fibers on the surface of the screen with increasing thickness as the distance traveled by the screen through the slurry increases;
- positioning a first reinforcement strand projecting means beneath the surface of the slurry;
- projecting a plurality of first continuous reinforcement strands through said first strand projecting means below the slurry surface by propelling said first strands at approximately the same velocity as said screen onto said first chopped fiber layer at a first predetermined location inter-

mediate the ends of the screen thereby depositing said first reinforcement strands in a longitudinally oriented configuration and in a first substantially horizontal plane within the resultant mat;

- collecting a second layer of chopped fibers on top of said first layer and said first reinforcement strands with increasing thickness as the distance traveled by the screen through the slurry increases;
- positioning a second reinforcement strand projecting means above the surface of said slurry at a location between the first projecting means and the exit position;
- projecting a plurality of second continuous reinforcement strands onto the surface of said slurry by projecting said second strands from said second strand projecting means from above the slurry surface onto that slurry surface near said exit position at a velocity greater than the velocity of said screen such that the second strands assume a randomly oriented interengaged configuration upon entering said slurry;
- allowing said random interengaged strands to migrate in an unconstrained manner from the slurry surface through the slurry and onto said second chopped fiber layer captured by the screen at a second predetermined location intermediate the ends of said screen thereby depositing said second reinforcement strands in a substantially horizontal plane within the resultant mat so that both random and longitudinal reinforcement strands will be present in the resultant mat;
- continuing the movement of the screen past the point of randomly oriented strand installation to cover said strands with a third uniform layer of chopped fibers; and
- moving the screen out of the slurry, thus withdrawing the wet mat from the slurry.

4,294,656

PROCESS FOR MEASURING THE STATE OF CHARGE OF SUSPENSIONS AND FOR CONTROLLING THE ADDITION OF AUXILIARY AGENTS TO THE SUSPENSIONS

Ulrich Beck, Bornheim-Merten, and Ekhard Rohloff, Düsseldorf, both of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany


Continuation of Ser. No. 949,357, Oct. 6, 1978, abandoned. This application Apr. 1, 1980, Ser. No. 136,188

Claims priority, application Fed. Rep. of Germany, Oct. 14, 1977, 2746179

Int. Cl.³ D21F 11/00

U.S. Cl. 162-192

6 Claims



1. A process for controlling the addition of retention agents to a fibrous suspensions, comprising the steps of: exposing a portion of the suspension of an ultrasonic field in a measuring cell having two electrodes which extend into the suspension and are spaced from each other by an odd multiple of half ultrasonic wavelengths of the ultrasonic field in the suspension; measuring the ultrasonic vibration potential generated by the ultrasonic field; and adding retention agents to the suspension in response to the magnitude of the measured ultrasonic vibration potential.

4,294,657

APPARATUS FOR MAKING FIBERBOARD


Tsutomu Saito, Tokyo, and Masaaki Shida, Fuji, both of Japan, assignors to Kabushiki Kaisha Fuji Seisakusho, Fuji, Japan
Continuation of Ser. No. 7,641, Jan. 29, 1979, abandoned. This application Aug. 5, 1980, Ser. No. 175,826

Claims priority, application Japan, Nov. 15, 1976, 51-136268; Jan. 31, 1978, 53-8850

Int. Cl.³ D21F 11/02

U.S. Cl. 162-303

2 Claims



1. An apparatus for manufacturing fiberboard, comprising: a first endless belt conveyor having a slanted portion constituting a first fiber layer forming section; a first suction box provided on the inner surface of said first fiber layer forming section; a second endless belt conveyor having a slanted portion constituting a second fiber layer forming section disposed above said first fiber layer forming section; a second suction box provided on the inner surface of said second fiber layer forming section; a passage means disposed between said first and second fiber layer forming sections for directing a slurry flow of fibers and so arranged whereby the speed of the slurry flow through the passage and onto the surfaces of said first and second fiber layer forming sections is differentiated from the running speed of said conveyors; a supply duct for the slurry of fibers, said duct being disposed in the center of said passage and having an outlet positioned near the upper ends of said first and second fiber layer forming sections whereby the slurry flow of fibers from said outlet diverges upwards and downwards and flows down the respective first and second fiber layer forming sections so that two separate fiber layers may be formed simultaneously and subsequently placed one upon another to form a single sheet of fiberboard.

4,294,658

NUCLEAR REACTORS

Peter Humphreys, Warrington; Daniel F. Davidson, Altrincham, and Gordon Thatcher, Lymm, all of England, assignors to United Kingdom Atomic Energy Authority, London, England
Filed Sep. 19, 1979, Ser. No. 76,943

Claims priority, application United Kingdom, Oct. 9, 1978, 39814/78


Int. Cl.³ G21C 9/00, 15/18

U.S. Cl. 376-404

3 Claims

1. A liquid metal cooled nuclear reactor comprising: a primary vessel; a fuel assembly submerged in a pool of primary liquid metal coolant within the primary vessel; a concrete vault housing said primary vessel; at least one heat exchange module carried by a roof of the vault and immersed in the pool of coolant, and a pump for circulating primary coolant from the pool through the fuel assembly to the heat exchange module, the heat exchange module comprising a tube-in-shell heat exchanger and an electromagnetic flow coupler disposed in the base region of the module for driving primary

coolant through the heat exchanger, the electromagnetic flow coupler being associated with a secondary coolant



circuit from which the driving effort for the primary coolant is derived.

4,294,659

APPARATUS FOR USE IN A LIQUID ALKALI METAL ENVIRONMENT


Charles S. Campbell, Hale, England, assignor to United Kingdom Atomic Energy Authority, London, England
Filed Jan. 16, 1978, Ser. No. 869,443

Claims priority, application United Kingdom, Feb. 4, 1977, 11924/77

Int. Cl.³ G21C 19/28

U.S. Cl. 165-133

3 Claims



1. Heat exchange apparatus for use in a liquid alkali metal environment comprising, a bundle of spaced heat exchange tubes of stainless steel, a tubular shell housing the tubes and adapted by inlet and outlet ports for conducting liquid alkali metal there-through in heat exchange with the tubes, and a plurality of cellular grids laterally supporting the tubes in the shell, each tube slidably occupying a discrete cell of each grid and wherein the complementary bearing surfaces of the grids for the tubes are aluminised.

4,294,660

SPACER ASSEMBLY RETAINER ARRANGEMENT


David W. Christiansen, Lynchburg, Va., assignor to The Babcock & Wilcox Company, New Orleans, La.

Filed Oct. 7, 1977, Ser. No. 840,207

Int. Cl.³ G21C 3/30

U.S. Cl. 376-442

4 Claims



1. In combination with a nuclear fuel assembly of the type having a plurality of vertically extending fuel elements and guide tubes maintained in a laterally spaced array by at least one spacer assembly with a multiplicity of intersecting slotted grid plates that form first cells through which the fuel elements are inserted and second cells through which the guide tubes are inserted, an improved arrangement for restraining spacer assembly movement comprising: guide tube sleeves circumscribing and fixedly connected to the guide tubes, each guide tube sleeve positioned so as to completely circumscribe the guide tube within each guide tube cell and partly beyond each guide tube cell, said guide tube sleeve portion extending beyond said guide tube cell completely connected to the circumference of said guide tube by welding, each sleeve having at least one aperture in the portion thereof extending beyond the guide tube cell; a plurality of collars; said collars having at least one longitudinal slot therein for mechanically interlocking each collar with a portion of the grid plates defining a respective guide tube cell by passing a grid plate within said slot; each of the collars circumscribing completely part of a guide tube sleeve, and each of said collars being crimped in part to extend into at least one aperture of said sleeves.

4,294,661

LIQUID METAL COOLED FAST BREEDER NUCLEAR REACTOR CONSTRUCTIONS

Geoffrey Seed, St. Helens; Graham Chesworth, Lymm; John R. Hind, Warrington, and Donald Hodgson, Ormskirk, all of England, assignors to Nuclear Power Company Limited, England

Filed Apr. 4, 1979, Ser. No. 26,819


Int. Cl.³ G21C 13/00

U.S. Cl. 376-363

6 Claims

1. A liquid metal cooled fast breeder nuclear reactor construction comprising: a concrete containment vault, a primary vessel containing a pool of liquid alkali metal coolant housed within the vault, a nuclear fuel assembly support strongback within the primary vessel, and a nuclear fuel assembly submerged in the pool of coolant and supported by the strongback, the primary vessel incorporating a yoke comprised of a plurality of arcuate segments welded end-to-end to form an annular support member, the yoke being suspended from the roof structure of the vault by a first annular series of tie straps disposed outside the primary vessel whilst the

strongback is supported from the yoke by a second annular series of tie straps, the yoke having upwardly and



downwardly extending legs which are extended by upper and lower strakes respectively of the primary vessel.

4,294,662

PROCESS FOR THE FINAL ASSEMBLY OF A NUCLEAR REACTOR VESSEL


Paul Guignard, Le Creusot, and Alain Commeau, Montchanin, both of France, assignors to Framatome, Courbevoie, France
Filed May 12, 1980, Ser. No. 150,224

Claims priority, application France, May 16, 1979, 79 12399

Int. Cl.³ B23K 31/06

U.S. Cl. 219-61

5 Claims



1. A process for the final assembly of a nuclear reactor vessel comprising two sub-assemblies possessing symmetry of revolution, which sub-assemblies have been assembled and machined to provide elements for positioning the internal fittings of the vessel and which have been provided with annular mating surfaces in planes perpendicular to said axes of symmetry of said sub-assemblies and with assembly ridges projecting from each said mating surface at a median part of said surface and extending over the complete perimeter of said surface, said process comprising arranging said sub-assemblies with said axes thereof horizontal and with said mating surfaces thereof facing, bringing said ridges into contact and coincidence thereby defining two annular spaces between said mating surfaces, one said space opening into the interior of said vessel and the other said space opening into the exterior over the whole periphery of said vessel, said spaces being separated by a wall formed by said contacting ridges, initially welding said sub-assemblies by deposition of a filler metal in one of said spaces, removing by machining said ridges and part of said deposited metal, and finally welding said sub-assemblies by

deposition of filler metal in said annular spaces between said mating surfaces, said process additionally comprising providing at the level of one of said annular spaces at least three female centering stubs projecting from said mating surface of one of said sub-assemblies, each said female stub having an associated seat recessed relative to the outer surface of said stub, said female stubs extending over a fraction of said perimeter of said vessel, providing at least three male centering stubs on said mating surface of the other said sub-assembly, the shape, size and position thereof corresponding to the shape, size and position of said seats of said female stubs, said male stubs and female stubs being in positions matched in a precise manner relative to said positioning elements for internal fittings of said vessel, and at least one of said male stubs and at least one of said female stubs together providing a radially directed key socket, introducing said male stubs into said seats of said corresponding female stubs when bringing said ridges into contact to simultaneously achieve centering, axial alignment and orientation of said sub-assemblies relative to one another, checking alignment thereof preferably by an optical method, inserting a key into said socket provided by said pair of stubs, which socket has been obtained by bringing said sub-assemblies into contact and orientation, to maintain the relative positioning of said sub-assemblies, joining said stubs together by point-welds before effecting initial welding, and, after initial welding, removing said male and female stubs by machining when removing said ridges and before completely filling said annular spaces with filler metal.

4,294,663

METHOD FOR OPERATING A COKE QUENCH TOWER SCRUBBER SYSTEM


Richard P. Tennyson, Fort Myers, Fla., assignor to Munters Corporation, Fort Myers, Fla.

Filed Jun. 18, 1980, Ser. No. 160,744

Int. Cl.³ C10B 39/08; B01D 47/00

U.S. Cl. 201-39

8 Claims



1. The method of quenching coke and scrubbing the resulting gases comprising the steps of placing a supply of hot coke in an enclosed natural draft tower having an open top, passing water from above to said coke through at least one layer of a liquid gas contact body formed of corrugated sheets of materials arranged with the corrugations in each adjacent sheet crossing each other, passing gases from the quenched coke through said contact body countercurrent to said water to remove particulate matter, liquid drops and water soluble vapors from said gases in said contact body, the pressure drop across the contact body being on the order of 0.15 inches w.g., and thereafter passing said gases through a mist eliminator structure to remove water droplets therefrom, the pressure drop across the mist eliminator being on the order of 0.10 inches w.g.

4,294,664 LATENT HEAT RECIRCULATING SYSTEM


Myron L. Anthony, Grand Junction, Colo., assignor to Sax Zzyzx, Ltd., Clifton, Colo.

Filed Jul. 16, 1980, Ser. No. 169,441

Int. Cl.³ B01D 3/02, 3/22

U.S. Cl. 203-19

11 Claims



1. A method of conserving energy while processing a process liquid in a process stream to recover its latent heat of condensation for return to the process stream and comprising the following steps:

- (1) providing an open process stream having a first heat accepting means and a first heat rejecting means;
 - (2) providing a closed refrigerator loop having second heat accepting means and second heat rejecting means;
 - (3) providing a closed chiller loop having third heat accepting means and third heat rejecting means;
 - (4) indirectly exchanging heat between said second heat accepting means and said third heat rejecting means;
 - (5) indirectly exchanging heat between said first heat rejecting means and said third heat accepting means; and
 - (6) indirectly exchanging heat between said second heat rejecting means and said first heat accepting means,
- thereby enabling said latent heat to be passed to the chiller loop and from there to the refrigerator loop for exchange back to the process stream, and allowing adjustments to be made in the refrigerator loop for efficiency and performance without necessarily effecting the chiller loop.

4,294,665 SEPARATION OF ACETONITRILE FROM CRUDE OLEFINICALLY UNSATURATED NITRILE

Katsuta Issei, and Tanaka Tetsuo, both of Kurashiki, Japan, assignors to Asahi Kasei Kogyo Kabushiki Kaisha, Osaka, Japan


Filed Jan. 28, 1980, Ser. No. 115,865

Claims priority, application Japan, Feb. 2, 1979, 54/11109

Int. Cl.³ B01D 3/00; C07C 121/32

U.S. Cl. 203-50

11 Claims



1. A process for separating acetonitrile from a crude olefinically unsaturated nitrile which comprises passing a reaction gas obtained in the ammoxidation of propylene or isobutylene through a quenching column, an absorption column with water, an extractive distillation column for the olefinically unsaturated nitrile and a stripping column for acetonitrile successively, condensing the acetonitrile-containing vapor from the top of the stripping column, evaporating the condensed acetonitrile-containing liquid into the waste gas discharged from

the top of the absorption column, subjecting the waste gas containing a gas and a liquid obtained by the evaporation to a vapor-liquid separation subjecting the gas separated thereby to incineration and recycling the liquid thereby separated to a preselected point selected from the group consisting of the bottom of the quenching column, the stripping column and the bottom of the extractive distillation column.

4,294,666

PROCESS FOR THE MANUFACTURE OF 4,4'-DIPHENYL-METHANE DIISOCYANATE AND A MIXTURE OF DIPHENYL-METHANE DIISOCYANATE ISOMERS CONTAINING A SMALL AMOUNT OF URETDIONES AND HYDROLYZABLE CHLORINE

Hans J. Astheimer, Neuhofen; Horst Brandtstaedter, Ludwigshafen; Rainer Ohlinger, Heidelberg, all of Fed. Rep. of Germany; Willy Van Pee, Ekeren; Jaak Van Steen, Wuustwezel, both of Belgium; Friedrich Sauer, Obersulzen, Fed. Rep. of Germany; Rudolf Schmidt, Frankenthal, Fed. Rep. of Germany, and Siegfried Krueger, Speyer, Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Ludwigshafen, Fed. Rep. of Germany

Filed Aug. 15, 1980, Ser. No. 178,673

Claims priority, application Fed. Rep. of Germany, Aug. 18, 1979, 2933601

Int. Cl.³ B01D 3/10; C07C 119/048

U.S. Cl. 203-72

6 Claims

1. A process for the manufacture of a mixture of diphenylmethane diisocyanate isomers and particularly 4,4'-diphenylmethane diisocyanate containing a small amount of uretdiones and hydrolyzable chlorine by the distillation of a mixture of crude MDI, diphenylmethane diisocyanate isomers and polyphenylene polymethylene polyisocyanates, which comprises:

- A. feeding crude MDI into an evaporator at temperatures of 175° C. to 210° C. under reduced pressure,
- B. discharging a non-distilled bottom fraction of from 97 weight percent to 50 weight percent based on the feed amount of crude MDI,
- C. evaporating a head fraction of from 3 weight percent to 50 weight percent based on the feed amount of crude MDI,
- D. condensing from the head fraction a fraction I of from 90 weight percent to 99 weight percent based on the feed amount of the head fraction, in a condensation stage I, at a temperature of from 130° C. to 170° C., the fraction I containing at least 96 weight percent, based on the weight of fraction I, of diphenylmethane diisocyanate isomers, less than one weight percent, based on the weight of fraction I, of uretdiones and less than 50 ppm based on the weight of fraction I of hydrolyzable chlorine, and
- E. condensing the remaining 10 weight percent to one weight percent, based on the feed amount of head fraction, in a condensation stage II at a temperature of from 45° C. to 60° C.

4,294,667

CORROSION EVALUATION TESTING METHOD OF COATED METALLIC MATERIAL AND APPARATUS EMPLOYED THEREFOR

Takashi Yamamoto, Kyoto, and Hiroshi Amako, Hirakata, both of Japan, assignors to Nippon Paint Co., Ltd., Osaka, Japan

Filed Mar. 14, 1980, Ser. No. 130,443

Claims priority, application Japan, May 10, 1979, 54-57868

Int. Cl.³ G01N 27/30, 27/46

U.S. Cl. 204-1 T


28 Claims

1. A method of testing coated metallic material for corrosion, comprising the steps of:

- (a) providing a metallic specimen plate having a film face coated by a film of paint and bringing the film face in contact with a corrosive test medium;
- (b) detecting the plate's spontaneous electrode potential with respect to the corrosive medium and potentiostatically

electrolyzing said film face at said spontaneous electrode potential;

- (c) selectively pulse polarizing said film face by cathodic-anodic voltage and computing the existence or non-existence of a film defect from the polarizing voltage and detected induced polarization current;
- (d) selectively sweep polarizing said film face by a linear positive and negative potential sweep to induce a sweep polarization current;
- (e) responding to the computation of non-existence of a film defect in step (c) by
- (i) selectively pulse polarizing said film face by small



voltage cathodic-anodic pulses and computing the film face's film resistance from the polarizing pulses and detected induced pulse polarization current; said

- (ii) selectively subtracting a current correction portion, computed as caused by the film resistance, from said sweep polarization current to detect a comparatively very small current-potential variation and from this very small current-potential variation computing the specimen's corrosion current; and
- (f) responding to the computation of existence of a film defect in step (c) by detecting said sweep polarization current to selectively form cathodic polarization curves and anodic polarization curves.

4,294,668

METHOD OF MEASURING OXYGEN AND PROCESS FOR PRETREATING A SOLID ELECTROLYTE OXYGEN GAS SENSING ELEMENT

Ching T. Young, Troy, Mich., assignor to Bendix Autolite Corporation, Fostoria, Ohio

Division of Ser. No. 942,102, Sep. 13, 1978, abandoned. This

application Jun. 12, 1980, Ser. No. 158,843

Int. Cl.³ G01N 27/58

U.S. Cl. 204-1 T

13 Claims

1. A process for pretreating a solid electrolyte oxygen gas sensor element so as to increase the voltage output under rich gas conditions, shorten the switching response time, and reduce the internal resistance thereof, the sensor element comprising a solid electrolyte body having an inner conductive catalyst electrode on the inner surface, that is to be in contact with a reference gas during operation of the sensor, an outer conductive catalyst electrode coating on the outer surface thereof, that is to be in contact with a gas, the oxygen content of which is to be measured during operation of the sensor, and a porous protective coating over at least a portion of said outer electrode, comprising:

- (a) heating the sensor element to an elevated temperature in excess of 450° C. and subjecting the outer surface thereof, with said outer conductive catalyst coating, to a nonoxidizing atmosphere; and
- (b) applying a direct current to the sensor element, with said outer electrode as an anode, while said outer surface is at

said elevated temperature and subjected to said nonoxidizing atmosphere, the current density thereof being at least 5 milliamperes per square centimeter of the planar surface of said outer conductive catalyst electrode.

10. The solid electrolyte oxygen gas sensor element pre-treated according to the process of claim 1.

13. A method for measuring the oxygen content of a gas with a solid electrolyte oxygen gas sensor element comprising a solid electrolyte body, an inner electrode on the inner surface, that is to be in contact with a reference gas during operation of the sensor, and an outer electrode on the outer surface, that is to be in contact with a gas, the oxygen content of which is to be measured during operation of the sensor, said method comprising:

heating the sensor element to an elevated temperature in excess of 450 degrees C. and subjecting the outer surface thereof to a non-oxidizing atmosphere;

applying a direct current to the sensor element, with said outer electrode as an anode, while said outer surface is at said elevated temperature and subjected to said non-oxidizing atmosphere, the current density thereof being at least 5 milliamperes per square centimeter of the planar surface of said outer electrode;

removing the current from the sensor;

exposing the outer electrode of said sensor to a gas the oxygen content of which is to be measured, with the inner electrode in contact with a reference gas; and measuring an electrical output from said sensor electrodes as a measure of the oxygen content of in said gas.


4,294,669

PROCESS FOR PLATING SELECTED METAL AREAS
Howard P. Lincoln, North Warren, and Donald M. Reddinger, Russell, both of Pa., assignors to GTE Products Corporation, Stamford, Conn.

Filed Sep. 8, 1980, Ser. No. 185,091
Int. Cl.³ C25D 5/02

U.S. Cl. 204—15

3 Claims




1. In a process for plating selected areas of a metal wherein a rigid plate covered with a resilient material is placed in contact with one surface of the metal and a plating solution is energized and applied to the selected areas of the opposite surface of the metal, the improvement comprising the steps of contacting the opposite surface of the metal with an apertured mask comprising a mask blank having a plurality of apertures and having a layer of polyurethane on one surface for forming a seal with said metal, a layer of polyurethane affixed to the inner periphery of the apertures of said apertured mask, and a layer of polyurethane in a recessed portion of an opposite surface of said apertured mask blank surrounding each one of said apertures and applying said plating solution to said selected areas of said metal through said apertures of said apertured mask.

PRECISION ELECTROPLATING OF METAL OBJECTS
Louis W. Raymond, 2500 Post Rd., Fairfield, Conn. 06430
Filed Oct. 29, 1979, Ser. No. 89,589
Int. Cl.³ C25D 7/04, 17/10

U.S. Cl. 204—26

5 Claims



1. In the process for the precision electroplating of a layer of metal of predetermined uniform thickness on the surface of a metal object in which an anode comprising the source of the metal being electroplated on the surface of the metal object is positioned in close proximity to said surface with the facing surfaces of the anode and the metal object spaced a predetermined uniform distance apart, in which the space between said facing surfaces of the anode and the metal object being electroplated is filled with an aqueous electrolyte containing a cation of the electroplating metal and in which an electrolyzing current is passed through said aqueous electrolyte between the facing surfaces of the anode and the object being electroplated to cause the electroplating metal of the anode to be electrolytically dissolved in the aqueous electrolyte and to cause an exactly equal amount of said metal to be electrolytically deposited on said facing surface of the metal object being electroplated, the improvement which comprises:

employing a composite anode having an under body of generally electrically conductive but anodically non-conductive material on the surface of which under body is disposed an outer layer of the metal being electroplated on the surface of the metal object, said outer layer of electroplating metal of the anode initially being of predetermined uniform thickness and completely covering the surface of the under body of the anode that immediately faces the surface of the metal object being electroplated, and continuing the electroplating operation to effect the complete electrolytic dissolution of the outer layer of electroplating metal of the anode, the complete removal of said outer layer of electroplating metal from any given area of the anode under body automatically terminating the flow of electrolyzing current from that area of the anode with the concomitant termination of the electrodeposition of said metal onto the corresponding area of the metal object being electroplated, whereby a layer of metal of predetermined uniform thickness is electroplated onto the surface of said metal object.

4,294,671

HIGH TEMPERATURE AND LOW FEED ACID CONCENTRATION OPERATION OF HCL ELECTROLYZER HAVING UNITARY MEMBRANE ELECTRODE STRUCTURE

Edward N. Balko, Wilmington, Mass., assignor to General Electric Company, Wilmington, Mass.


Filed May 14, 1980, Ser. No. 149,619
Int. Cl.³ C25B 1/26, 9/00

U.S. Cl. 204—128

13 Claims

1. A process of generating halogens which comprises, (a) electrolyzing an aqueous halide between an anode and a cathode electrode separated by a permselective, liquid and gas impervious ion exchanging membrane, said anode being bonded to the membrane to provide a gas and liquid permeable electrode which forms part of a unitary electrode-membrane structure,

(b) applying potential to the anode through a separate electron current conducting structure to introduce electron current flow to the bonded anode at a plurality of discrete areas on the surface of the anode,



(c) establishing turbulent anolyte flow conditions over the surface of the anode to maintain the chloride ion concentration at the discrete areas of the anode at a level to minimize chloride ion starvation and oxygen evolution at the operating current density to maintain the oxygen content of the evolved halogen below 1%.


4,294,672

METHOD FOR PREPARING A SUPPORT FOR A LITHOGRAPHIC PRINTING PLATE
Hisao Ohba; Kazutaka Oda; Yukio Yabuta, and Azusa Ohashi, all of Shizuoka, Japan, assignors to Fuji Photo Film Co., Ltd., Kanagawa, Japan

Filed May 30, 1980, Ser. No. 154,665
Claims priority, application Japan, May 30, 1979, 54-67210
Int. Cl.³ C25F 3/04

U.S. Cl. 204—129.4

15 Claims



1. A method for preparing a support for a lithographic printing plate comprising electrolytically graining an aluminum plate in an acidic electrolyzing bath, wherein an alternating charge voltage having a wave form which includes at least one intermission period of zero voltage in at least one of the anode or the cathode phases is applied to said plate, and is such that the electric quantity for the anode phase Q_a is larger than the electric quantity for the cathode phase Q_c .

4,294,673

METHOD OF MIRROR-FINISHING A CYLINDRICAL WORKPIECE

Yasuo Kimoto, Fujiidera; Katsunori Tamiya, Kobe; Shoichi Honda, Osaka; Hidehiko Maehata, Toyonaka, and Hiroshi Kamada, Takatsuki, all of Japan, assignors to Hitachi Shipbuilding & Engineering Co., Ltd., Osaka, Japan


Filed Feb. 22, 1980, Ser. No. 123,648

Claims priority, application Japan, Feb. 24, 1979, 54-20919; Mar. 27, 1979, 54-36618; May 2, 1979, 54-55086; May 2, 1979, 54-55087; Aug. 15, 1979, 54-104313; Aug. 15, 1979, 54-104314; Aug. 15, 1979, 54-104315

Int. Cl.³ C25F 3/16

U.S. Cl. 204—129.46

2 Claims



1. A method of mirror-finishing a cylindrical workpiece comprising the steps of:

disposing a plurality of working electrodes oppositely to one surface of said cylindrical workpiece defining a plurality of gaps between said working electrodes and said cylindrical workpiece;

introducing an electrolyte and an abrasive matter into said plurality of gaps, said electrolyte being in a passive state, said abrasive matter being water permeable;

connecting said cylindrical workpiece to the anode of a power supply and said working electrodes to the cathode of said power supply, said power supply providing an electrolytic voltage in a range from 2 volts to 15 volts and an electrolytic current less than or equal to 10 amperes/cm²;

performing an anodic liquation operation by electrolysis onto a metallic surface of the cylindrical workpiece being treated;

assisting said anodic liquation operation by simultaneously performing an abrasive operation to the metallic surface of the workpiece being treated resulting in the abrasion of an anodic passive film formed on said metallic surface; the steps of performing an anodic liquation operation and performing an abrasive operation further including the steps of:

swivelling each of said plurality of working electrodes and the cylindrical workpiece relative to one another in a circumferential direction of the cylindrical workpiece, and

simultaneously pressing said working electrodes and the abrasive matter toward the metallic surface of the cylindrical workpiece, the pressing force of said abrasive matter on the surface of the cylindrical workpiece being greater than or equal to 0.5 kgf/cm²,

the steps of swivelling one of said plurality of working electrodes and said cylindrical workpiece relative to one another and simultaneously pressing said one of said working electrodes and the abrasive matter toward the surface of the cylindrical workpiece providing a speed of abrasion of said abrasive matter across a portion of the metallic surface of the cylindrical workpiece of greater than or equal to 2 meters/second,

a period of time between the steps of swivelling and simultaneously pressing said one of said working electrodes relative to said portion of the metallic surface of the cylindrical workpiece and swivelling and simultaneously pressing an adjacent one of said working elec-

trodes relative to said portion of the surface of the cylindrical workpiece being in a range from 20 milliseconds to 200 milliseconds.

4,294,674

METHOD OF TREATING WASTE GAS BY IRRADIATION

Shinji Aoki, Tokyo; Keita Kawamura; Hitoshi Kimura, both of Fujisawa; Tsutomu Katayama; Chikara Kaido, both of Kitakyushu, and Hiroshi Yoshida, Koganei, all of Japan, assignors to Ebara Corporation, Tokyo, Japan


Filed Dec. 26, 1979, Ser. No. 107,500

Claims priority, application Japan, Dec. 29, 1978, 53-162153

Int. Cl.³ B01J 19/08

U.S. Cl. 204—157.1 H

4 Claims



1. An improved method of treating waste gas containing sulfur oxides and nitrogen oxides and having ammonia added, the waste gases being subjected to ionizing radiation characterized in that the reaction temperature is held between 50° C. and 80° C. during the treatment.

4,294,675

PROCESS FOR PRODUCTION OF FLUORINE-CONTAINING MULTI-COMPONENT COPOLYMERS

Osamu Matsuda; Terutaka Watanabe, both of Takasaki; Yoneho Tabata, Tokyo, and Sueo Machi, Takasaki, all of Japan, assignors to Japan Atomic Energy Research Institute, Tokyo, Japan

Filed Oct. 16, 1979, Ser. No. 85,328

Claims priority, application Japan, Oct. 18, 1978, 53-128206; Mar. 20, 1979, 54-32962; Mar. 20, 1979, 54-32963; Apr. 27, 1979, 54-52278

Int. Cl.³ C08F 8/00, 214/18, 214/26

U.S. Cl. 204—159.14

29 Claims

1. A process for the cross-linking of fluorine-containing multi-component interpolymer of regular repeating sequential alternating structure of $-A_1-B_1-A_2-B_2-A_3-B_3-$, wherein A_1 , A_2 and A_3 represent α -olefin units and B_1 , B_2 and B_3 represent α,β,β -trifluoroacrylate or tetrafluoroethylene formed by copolymerizing by irradiating with ionizing radiation a mixture of tetrafluoroethylene; at least one α,β,β -trifluoroacrylate selected from the group consisting of methyl α,β,β -trifluoroacrylate, ethyl α,β,β -trifluoroacrylate, and butyl α,β,β -trifluoroacrylate; and at least one α -olefin selected from the group consisting of ethylene, propylene, 1-butene, 1-pentene, 1-hexene, 1-heptene, 1-octene, 1-nonene, 1-decene, 1-undecene, 1-dodecene, 1-tridecene, 1-isobutylene, 2-methyl-1-butene, 2-methyl-1-pentene, 2-methyl-1-hexene, 2-methyl-1-heptene and 2-methyl-1-octene; comprising subjecting said interpolymer to electron beam irradiation in air or in an inert gas.

4,294,676

AQUEOUS MONOMER SOLUTIONS ADAPTED FOR DIRECT PHOTOPOLYMERIZATION

Jean Boutin, Mions; Bernard Guenot, Paris, and Bruno Jamet, Lyons, all of France, assignors to Rhone-Poulenc Industries, Paris, France


Filed Jul. 10, 1979, Ser. No. 56,337

Claims priority, application France, Jul. 24, 1978, 78 22883

Int. Cl.³ C08F 2/10, 2/46

U.S. Cl. 204—159.23

19 Claims



1. A process for the preparation of an aqueous monomer solution adapted for direct photopolymerization into water soluble polymers, comprising deoxygenating and counter-currently scrubbing an aqueous solution of olefinically unsaturated hydrophilic monomer with an inert gas in a packed column, and concurrently adding a photopolymerization inducing amount of photoinitiator to said aqueous solution.

4,294,677

METHOD FOR ELECTRODEPOSITING A PROTEIN ONTO AN ION-EXCHANGE MEMBRANE

Teruo Sakagami, Iwaki; Tadaaki Kato, Tokyo; Toru Hirai, and Naohiro Murayama, both of Iwaki, all of Japan, assignors to Kureha Kagaku Kogyo Kabushiki Kaisha, Tokyo, Japan


Filed Sep. 12, 1979, Ser. No. 74,826

Claims priority, application Japan, Nov. 17, 1978, 53-141863

Int. Cl.³ C25D 1/18, 1/20

U.S. Cl. 204—181 F

11 Claims



1. A process for recovering protein from an aqueous solution or suspension containing the protein by electrically depositing the protein on at least one diaphragmatic membrane comprising introducing an aqueous solution of an electrolyte into at least one electrode-chamber formed by an electrode and an ion-exchange membrane as said diaphragmatic membrane, and

electrophoretically moving said protein contained in said aqueous solution or suspension in a chamber adjacent to said electrode-chamber while controlling the pH of the surface of said ion-exchange membrane by creating a difference between the pH of said aqueous solution or electrolyte and the pH of said aqueous solution or suspension whereby said protein is recovered as a film or cylindrical film without bubbling.

4,294,678

APPARATUS AND METHOD FOR PREVENTING CONTAMINATION OF SPUTTERING TARGETS


Manfred R. Kuehnle, New London, N.H., assignor to Coulter Systems Corporation, Bedford, Mass.

Filed Nov. 28, 1979, Ser. No. 98,223

Int. Cl.³ C23C 15/00

U.S. Cl. 204—192 R

10 Claims



1. In a sputtering apparatus which comprises a vessel including means for establishing low pressure gas conditions within the vessel and maintaining the interior of the vessel in sealed condition relative to the exterior ambient atmosphere, anode and cathode means within the vessel and the cathode means including at least one target material surface exposed to the interior of the vessel, the anode and cathode means being disposed in such a manner that said target material surface is in face to face relationship with the anode means and spaced therefrom whereby to enable a substrate member to be interposed in said space, means for extending electrical connections from said anode and cathode means to an exterior source of electrical energy, means for establishing and maintaining sputtering conditions within the vessel and means for maintaining a substrate member adjacent to the anode means in said space during the period of time that the sputtering conditions are being maintained within said vessel, the invention herein which comprises:

means for preventing contamination of the target material surface when the vessel is opened to the exterior ambient atmosphere comprising remotely controlled shutter means for selectively sealing off said target material surface from the interior of the vessel and exposing said target material surface to said interior of the vessel.

4,294,679

FLAT ELECTROCHEMICAL SENSOR, AND METHOD OF ITS MANUFACTURE

Helmut Maurer, Schwieberdingen; Klaus Müller, Tamm; Ernst Linder, Mühlacker; Franz Rieger, Aalen-Wasserralfingen, and Günther Stecher, Ludwigsburg, all of Fed. Rep. of Germany, assignors to Robert Bosch GmbH, Stuttgart, Fed. Rep. of Germany

Filed May 1, 1980, Ser. No. 145,738

Claims priority, application Fed. Rep. of Germany, Jul. 14, 1979, 2928496

Int. Cl.³ G01N 27/58

U.S. Cl. 204—195 S

34 Claims

1. Electrochemical sensor unit for determination of oxygen content in gases, particularly exhaust gases from a combustion process, especially exhaust gases from an internal combustion engine, adapted for support by and in a metallic housing, said sensor unit being of essentially elongated plate-like form

having a sensing end portion adapted for exposure to the gases and a holding end portion adapted for attachment into the housing, and an intermediate portion intermediate said end portions,


said sensor units having a plate carrier element (11, 14, 31, 32, 46, 59, 71, 89, 108, 112);

a plate-like solid electrolyte body (11, 31, 46, 59, 71, 89, 108, 112) forming at least in part said carrier element;

a measuring electrode and a reference electrode forming an electrode pair (12, 13, 29, 30, 45, 50, 60, 61, 69, 70, 92, 93, 108, 113, 114), said electrodes being porous metallic layers located on said electrolyte body, spaced from each other, at least the measuring electrode being adapted to be exposed to the gases to be tested; wherein, in accordance with the invention, at least one of the electrodes is covered with a cover plate (17, 36, 63, 77, 83, 103, 103', 120), and

to conduct a gas to at least one of the electrodes, depressions, grooves, ducts or flutes (22, 94, 94', 115) are formed between the respective electrode and at least one of said cover plates said depressions, grooves, ducts or flutes being open to the gas to be admitted and dimensioned to control the quantity of gas being admitted to the respective electrode.

22. Method to make an electrochemical sensor unit, for the determination of oxygen content in gases, particularly exhaust gases from a combustion process and especially exhaust gases from an internal combustion engine, adapted for support in a metallic housing, said sensor unit being essentially of elongated



- (d) applying a cover (103, 103') of a gas-imperious material capable of being sintered on the surface formed by the projecting elements and the filler material; then
- (e) sintering said sensor unit to unite the components thereof to sinter together the projecting elements and the cover and evaporate or dissolve and filler to leave the grooves or flutes free.


4,294,680

APPARATUS FOR SELECTIVE METAL PLATING
Howard P. Lincoln, North Warren, and Donald M. Reddinger, Russell, both of Pa., assignors to GTE Products Corporation, Stamford, Conn.

Filed Sep. 8, 1980, Ser. No. 185,092
Int. Cl.³ C25D 17/00

U.S. Cl. 204—224 R

4 Claims



1. In apparatus for plating selected areas of a metal wherein a rubber-covered rigid plate is placed in contact with one surface of the metal, an apertured mask is placed in contact with an opposite surface of the metal, and a plating solution is applied to selected areas of the opposite surface of the metal through said mask and energized for a given period of time, the improvement wherein said apertured mask comprises a mask blank having a top surface, at least one aperture having an inner perimeter, and a bottom surface with a recessed portion surrounding said aperture and a layer of polyurethane covering said top surface for forming a seal with said metal, said inner perimeter of said aperture and said recessed portion of said bottom surface whereby said polyurethane forms a seal surrounding said selected areas of the metal.

4,294,681


MOLDED SELECTIVE PLATING MASK

Howard P. Lincoln, North Warren, and Donald M. Reddinger, Russell, both of Pa., assignors to GTE Products Corporation, Stamford, Conn.

Filed Sep. 8, 1980, Ser. No. 185,094
Int. Cl.³ C25D 17/00

U.S. Cl. 204—224 R

10 Claims



1. A mask for selectively plating specific areas of a metal comprising:
a mask blank having a plurality of apertures therein for alignment with said specific areas for selective plating of said metal with each of said apertures surrounded by a recessed portion of said mask blank on one surface thereof; and a layer of polyurethane covering a surface opposite said one surface of said mask blank for forming a seal with said metal, said recessed portion of said one

surface of said mask blank, and the inner perimeter of each aperture in said mask blank.

4,294,682

DATA ACQUISITION SYSTEMS


Andrew E. Deczky, Ottawa, Canada, assignor to Alcan Research and Development Limited, Montreal, Canada

Filed Jan. 31, 1977, Ser. No. 764,167

Claims priority, application Canada, Jan. 29, 1976, 244504
Int. Cl.³ H04B 9/00; G06K 15/20

U.S. Cl. 204—244

14 Claims



1. A system for a hot metal handling operation comprising:
a plurality of operating stations each including an electrolytic aluminum reducing pot;
a mobile crane for servicing said pots at each operating station by adding raw materials and removing molten metal;
a data acquisition system comprising:
means associated with the crane for providing identification information of a particular pot and pot row being serviced;
means associated with the crane for measuring process variables at each operating station; and means on the crane for optically transmitting said identification information and said information concerning the measurements over a cableless path from said crane to a receiver and computer located remotely of said operating stations.

4,294,683

ELECTROLYSIS UNIT


Gerard Pere, Le Breuil, France, assignor to Creusot-Loire, Paris, France

Filed Mar. 31, 1980, Ser. No. 136,099

Claims priority, application France, Apr. 2, 1979, 79 08694
Int. Cl.³ C25B 9/00, 15/08

U.S. Cl. 204—258

10 Claims



1. Electrolysis unit comprising at least one electrolyzer provided with at least one anolyte outlet and at least one catholyte outlet, a degasser for each of said outlets, a circuit connecting each degasser to its respective outlet, means for controlling the flow of electrolyte in each connecting circuit means, each for controlling the flow of anolyte being coupled

to the corresponding means for controlling the flow of catholyte, and vice versa, by a coupling connection producing concomitant variations in these two flow-control means and an electrolyte return circuit leading from each degasser, said return circuits being connected together at a point upstream of the electrolyzer.


4,294,684

TEMPLATE FOR FORMING MULTIPLE GEL TRACKS WITHIN A SINGLE ELECTROPHORETIC GEL FRAME
Philip Serwer, San Antonio, Tex., assignor to Board of Regents, University of Texas, Austin, Tex.

Filed Jun. 30, 1980, Ser. No. 164,274
Int. Cl.³ G01N 27/28

U.S. Cl. 204—299 R

9 Claims



1. A template for forming multiple gel tracks in a gel bed, which comprises:
a support frame;
a plurality of rigid elongate bars, each bar spaced a sufficient distance from an adjacent bar effective to form gel tracks in a gel bed, each bar of which is securely attached to the support frame in a parallel alignment with respect to the other bars; and
a sample-well forming comb having a plurality of teeth projecting linearly from a base, said comb adapted to be detachably disposed with respect to the support frame, the teeth of the comb aligned in a manner to form a flush contact with one set of ends presented by the elongate bars.

4,294,685

PROCESS FOR COAL LIQUEFACTION AND CATALYST
Dae K. Kim, Naperville; Ralph J. Bertolacini, Chesterton; L. Charles Gutberlet, Wheaton, and Ken K. Robinson, St. Charles, all of Ill., assignors to Electric Power Research Institute, Inc., Palo Alto, Calif.

Division of Ser. No. 20,209, Mar. 13, 1979, Pat. No. 4,257,922.
This application Jul. 7, 1980, Ser. No. 166,552

Int. Cl.³ C10G 1/06

U.S. Cl. 208—10

8 Claims

1. An improved process for hydroconversion of coal solids to liquid and gaseous products comprising contacting the coal solids, a gas containing molecular hydrogen and catalyst solids in a coal reaction zone at elevated temperatures and pressures at which a major portion of said coal solids undergo hydroconversion to gaseous and liquid products, the improvement comprising using, as catalyst solids, a supported catalyst comprising a catalytically active substance on support particles, said particles having essentially bimodal pore distribution with peak concentrations of smaller pores below about 600 angstroms and larger pores above about 600 angstroms, with the average diameter of the smaller pores ranging from about 100-200 angstroms, and the average diameter of the larger pores being in excess of 1000 angstroms said catalyst including at least 5.0% of the total pore volume of the larger pores and at least 70.0% of the total pore volume of the smaller pores.

4,294,686

PROCESS FOR UPGRADING HEAVY HYDROCARBONACEOUS OILS


Ian P. Fisher, Oakville; H. John Woods, Campbellville, and Frank Souhrada, Weston, all of Canada, assignors to Gulf Canada Limited, Toronto, Canada

Filed Mar. 11, 1980, Ser. No. 129,288

Int. Cl.³ C10G 45/28, 47/34

U.S. Cl. 208—56

13 Claims



1. A process for the upgrading of viscous hydrocarbonaceous oils comprising:

- fractionally distilling said hydrocarbonaceous oil to produce at least one fraction boiling below a temperature from substantially 300° C. to substantially 570° C. and a residuum boiling above said temperature, without significantly cracking said hydrocarbonaceous oil;
- contacting said residuum with a liquid hydrogen donor material stream at hydrocracking conditions to produce a hydrocracked stream;
- separating said hydrocracked stream into a gaseous stream and a liquid hydrocracked stream;
- fractionally distilling said liquid hydrocracked stream to separate, from lower and higher boiling fractions, a hydrogen donor precursor stream boiling above a temperature from substantially 180° C. to substantially 200° C. and below a temperature from substantially 330° C. to substantially 350° C.;
- catalytically reacting said hydrogen donor precursor stream with a hydrogen-rich gaseous stream to produce a hydrogenated donor material; and
- recycling at least part of said hydrogenated hydrogen donor material as the material which constitutes the entire liquid hydrogen donor material stream to contact said residuum in step (b) noted above.

4,294,687

LUBRICATING OIL PROCESS

Ronald Pinaire, Park Forest, and Gary L. Everett, Chicago Heights, both of Ill., assignors to Atlantic Richfield Company, Philadelphia, Pa.

Filed Dec. 26, 1979, Ser. No. 106,973

Int. Cl.³ C10G 45/00, 47/02, 65/12

U.S. Cl. 208—58

29 Claims

1. A process for preparing a mineral hydrocarbon lubricating oil base stock comprising:

- contacting a mineral hydrocarbon oil feedstock of lubricating oil viscosity with molecular hydrogen in the presence of a hydrotreating catalyst under hydrotreating conditions to avoid undue cracking of said feedstock such that less than about 5% by volume of said feedstock is cracked to produce materials boiling below about 600° F.;
- contacting the effluent oil from step (a) with molecular hydrogen in the presence of a hydrocracking catalyst under hydrocracking conditions; and

(c) contacting the effluent oil from step (b) with molecular hydrogen in the presence of a hydrogenation catalyst under hydrogenation conditions such that less than about 5% by volume of said effluent oil from step (b) which boils above 600° F. is cracked to produce material boiling below about 600° F.

4,294,688


HEAT TRANSFER IN MAGNETICALLY STABILIZED, FLUIDIZED BEDS

Francis X. Mayer, Baton Rouge, La., assignor to Exxon Research & Engineering Co., Florham Park, N.J.
Continuation of Ser. No. 737,227, Nov. 1, 1976, abandoned. This application Mar. 19, 1980, Ser. No. 131,855

Int. Cl.³ C10G 11/00, 15/00

U.S. Cl. 208—164

10 Claims



1. A hydrocarbon conversion process which comprises (a) contacting a hydrocarbon feedstock in a conversion zone having a magnetic field applied thereto with a fluidizable particulate solids mixture containing a plurality of separate discrete substantially inert heat carrier particles and magnetizable catalyst particles, said substantially inert heat carrier particles having settling rates higher than the settling rates of said catalyst particles; (b) permitting said heat carrier particles to settle in preference to the catalyst particles in a settling zone communicating with said conversion zone; (c) circulating said catalyst particles from the settling zone to said regeneration zone, said circulation of heat carrier particles being independent of the circulation of catalyst particles; (d) circulating said heat carrier particles from the settling zone to said regeneration zone, said circulation of heat carrier particles being independent of the circulation of catalyst particles; (e) contacting said catalyst particles in the presence of said heat carrier particles with oxygen at elevated temperatures to burn coke deposited upon said catalyst particles; (f) permitting said heat carrier particles to settle in preference to the catalyst particles in a settling zone communicating with said regeneration zone; (g) circulating said catalyst particles from the regeneration zone to a conversion zone having a magnetic field applied thereto; and (h) circulating said heat carrier particles from the settling zone to said reaction zone, said circulation of heat carrier particles being independent of the circulation of catalyst particles.

4,294,689

SOLVENT REFINING PROCESS

Avilino Sequeira, Jr., Port Arthur; Benjamin F. Smith, Jr., Groves, and Theodore C. Mead, Port Neches, all of Tex., assignors to Texaco, Inc., White Plains, N.Y.

Filed Feb. 14, 1980, Ser. No. 121,571


Int. Cl.³ C10G 21/20

U.S. Cl. 208—326

4 Claims

1. In a process for solvent refining a lubricating oil feedstock wherein said lubricating oil feedstock is contacted with N-methyl-2-pyrrolidone as selective solvent for aromatic constituents of said feedstock in an extraction zone thereby forming an extract phase rich in said aromatic constituents and comprising

a major portion of said solvent and a non-aromatic raffinate phase comprising a minor portion of said solvent, said raffinate phase is separated from said extract phase, and solvent is removed from each of said phases by flash vaporization, distillation, rectification, or a combination thereof, the improvement which comprises stripping residual solvent from said extract and from said raffinate with gaseous ammonia thereby forming a mixture of gaseous ammonia and solvent vapor, passing said



mixture of gaseous ammonia and solvent vapor to a solvent recovery zone wherein said mixture is cooled to a temperature sufficient to condense at least a portion of said solvent therefrom, separating gaseous ammonia from liquid condensate solvent, returning said condensate solvent to said extraction zone, and passing gaseous ammonia from which solvent has been removed into contact with said extract and said raffinate as said stripping gas for the removal of solvent therefrom.

4,294,690

PROCESS FOR SEPARATING WEAKLY MAGNETIC ACCOMPANYING MINERALS FROM NONMAGNETIC USEFUL MINERALS

Erich Kollenz, Leoben, Austria, assignor to Voest-Alpine Aktiengesellschaft, Vienna, Austria


Filed Apr. 2, 1980, Ser. No. 136,708

Claims priority, application Austria, May 31, 1979, A3984/79

Int. Cl.³ B03C 1/00

U.S. Cl. 209—3

6 Claims



1. A process for separating minerals having a mass susceptibility of below $200 \times 10^{-6} \text{ cm}^3/\text{g}$ from useful minerals or ores which are nonmagnetic or less magnetic than the minerals to be separated therefrom comprising the steps of:
crushing said minerals or ores to a grain size no greater than 0.2 mm; and
separating said minerals in a magnetic separator having a strong magnetic field.

4,294,691

HYDRODYNAMIC BLUEBERRY SORTING


Albert W. Patzlaff, South Haven, Mich., assignor to Blueberry Equipment, Inc., South Haven, Mich.
Continuation of Ser. No. 962,381, Nov. 20, 1978, Pat. No. 4,225,424. This application Jan. 7, 1980, Ser. No. 110,259

The portion of the term of this patent subsequent to Sep. 30, 1997, has been disclaimed.

Int. Cl.³ B07C 5/02

U.S. Cl. 209—3.1

4 Claims



1. Blueberry sorting apparatus comprising:
a water bath vessel having a receiving and immersion zone for receiving a harvested mixture of green, partially ripe, and ripe blueberries in the water bath; means for causing a downward current of water at said receiving and immersion zone for entraining and immersing the mixture of berries into the water bath whereby air bubbles are separated from berries to decrease their buoyancy, while green berries rise and float; a perforate conveyor in the path of said downward current to allow water flow therethrough while retaining ripe and partially ripe berries thereon; and means forming a quiescent zone in said water bath vessel, and said conveyor extending through said quiescent zone to allow partially ripe berries to rise to the bath surface and separate from the ripe berries remaining on said conveyor; said current causing means being at one upper side of said vessel, including water outlet means for propelling water into the bath, and oriented to cause said current to be directed smoothly and continuously downwardly toward the opposite lower side of said vessel; water inlet means beneath said conveyor for receiving water after flow through said conveyor; and conduit means for returning water from said water inlet means to said water outlet means.

4,294,692

DRUM-TYPE SCREENING MACHINE AND METHOD OF OPERATION

Alois Keller, Uzwil, Switzerland, assignor to Gebrueder Buehler AG, St. Gallen, Switzerland

Continuation of Ser. No. 934,022, Aug. 16, 1978, abandoned, which is a division of Ser. No. 873,896, Jan. 31, 1978, Pat. No. 4,222,864. This application May 1, 1980, Ser. No. 145,834

Claims priority, application Switzerland, Feb. 3, 1977, 1349/77

Int. Cl.³ B07B 1/20, 1/48

U.S. Cl. 209—300


16 Claims

1. A method of operating a drum type separator of the type having a stationary tubular screen, opposed support means for supporting the screen at opposite ends thereof and a rotor for causing movement of ground stock to be filtered, comprising the steps of:

supplying ground stock to be sieved through an inlet opening to the interior of the tubular screen while operating the rotor to cause movement of the ground stock such that the finer product passes through the stationary tubular screen and through a first outlet while the coarser product passes out a second outlet without having passed through the tubular screen,

and, while the rotor is rotating and while product is being

delivered to and through the separator, operating an adjusting means accessible exteriorly of the separator to vary the distance between the opposed support means to vary the tension of the tubular screen, one of the opposed support means being fixed axially and the other being



axially moveable in either direction, and wherein the step of operating the adjusting means includes turning a turning means at one end of the drum to move the axially moveable support means axially in one direction or the other relative to the fixed support means.

4,294,693

AIR FLOTATION ORE ENRICHING APPARATUS


Ray A. Brennan, Rte. 1, Box 575, Lake Geneva, Wis. 53147

Filed Dec. 8, 1980, Ser. No. 214,085

Int. Cl.³ B03B 4/00

U.S. Cl. 209—466

10 Claims



1. In a flotation ore enriching apparatus including a classification trough having an air-diffusing floor composed of interstitially cellular ceramic material having spaced riffle traps in the top surface thereof, a plenum chamber subjacent and opening to said floor to supply flotation air thereto, means for continuously supplying air under pressure to said plenum chamber, means for continuously supplying pulverized gangue and value ore mixture to be enriched to the inlet end of said classification trough, and means for controlling the flow of flotation air to said classification trough, the improvement wherein said means for continuously supplying air consists of a positive blower, said plenum chamber contains a partition defining within said chamber an inlet plenum located subjacent the inlet end of said trough and a classification plenum subjacent the remainder of said trough downstream from said inlet end thereof, said blower being connected to discharge only into said inlet plenum, said means for controlling the flow of air consisting essentially of an adjustable bleeder valve in a wall of said classification plenum to control the total volume of air forced through said air-diffusing floor and adjustable valve means in said partition to impede the flow of air from said inlet plenum to said classification plenum to maintain a high pressure in said inlet plenum sufficient to force sufficient air through said inlet end of said trough to impregnate and suspend the ore as it is being fed to said trough while maintaining by means of said bleeder valve a relatively low pressure in said classification plenum.

4,294,694

ANAEROBIC FILTER

John L. Coulthard, 16 Newry St., Richmond, Victoria, Australia



Filed Mar. 26, 1979, Ser. No. 24,083

Claims priority, application Australia, Mar. 28, 1978, PD3787

Int. Cl.³ C02C 1/04

U.S. Cl. 210—150

6 Claims



1. A biological filter for the treatment of a liquid medium comprising: a tank having an inlet and an outlet, the inlet of the tank being arranged to be connected to a source of polluted liquid medium, whereby said medium can flow through the tank; means for sealing said tank sufficiently to effect anaerobic conditions in said tank; an array of a plurality of vertically elongated strips of plastics material disposed in the tank and randomly floating in the liquid medium present in the tank, said strips having surfaces along essentially their entire lengths which are provided with a plurality of indentations and which are suitable for the attachment thereto of anaerobic biologically-active organisms, at least said surfaces being sufficiently flexible to move randomly so as to cause the flow path of the liquid medium to vary and so as to cause dead clusters of anaerobic organisms to break away from the surfaces thereby permitting renewed growth on the surfaces.

4,294,695

MULTI-PHASE SEPARATION METHODS AND APPARATUS

Clay D. Smith, and Douglas V. Keller, Jr., both of Lafayette, N.Y., assignors to Standard Oil Company, Chicago, Ill.
Division of Ser. No. 662,888, Mar. 1, 1976, Pat. No. 4,055,480, which is a continuation-in-part of Ser. No. 460,558, Apr. 12, 1974, Pat. No. 3,941,679, and Ser. No. 561,168, Mar. 24, 1975, Pat. No. 4,173,530, which is a continuation-in-part of Ser. No. 423,577, Jan. 14, 1974, abandoned. This application Jul. 8, 1977, Ser. No. 814,040


Int. Cl.³ B01D 17/02, 11/02, 45/02

U.S. Cl. 210—173

11 Claims

1. Apparatus for resolving a composite composed of a first, soluble phase and second and third phases of insoluble solids into the phases of which it is composed, said apparatus comprising: an extractor in which a solvent extraction of said first phase from said composite and a gravity separation of the second insoluble phase of said composite from the third insoluble phase thereof can concurrently be effected; means for introducing the composite into the extractor; means in said extractor for effecting said solvent extraction and said gravity separation which includes a body of a liquid which is comprised of a solvent for said first phase of the composite and which has a specific gravity intermediate those of the solids respectively making up the insoluble second and third phases of said composite, whereby: said first phase of the composite introduced into the extractor will dissolve in said body of

liquid isolating said first phase and freeing the solids making up the insoluble second and third phases; the solids making up one of said insoluble phases will then migrate toward the top of said body of liquid; and the solids making up the other of the insoluble phases will sink to the bottom thereof, thereby effecting a separation in said extractor of said three phases, each from the other; means for introducing into said extractor a solvent as aforesaid; offtake means for removing from said extractor solvent as aforesaid and that material making up the



first phase of the composite which is dissolved therein; a first solids transfer means for removing from said extractor independently of said first phase solids which have a specific gravity lower than that of the liquid in the extractor and therefore tend to collect in the upper part of the body of liquid therein; and a second solids transfer means for removing from said extractor solids which have a specific gravity higher than the specific gravity of said liquid and therefore tend to collect in the lower part of said body of liquid.

4,294,696

SWING DIFFUSER


Paul M. Thayer, Shorewood, Wis., assignor to Water Pollution Control Corporation, Milwaukee, Wis.

Filed Jan. 25, 1980, Ser. No. 115,470

Int. Cl.³ C02F 3/20; B01F 3/04

U.S. Cl. 210—220

12 Claims



1. A swing diffuser apparatus for gas diffuser systems of the type in which diffusers are submerged in a tank of liquids to be treated, said apparatus comprising:

- a rigid upper hanger arm;
- means for pivoting said upper hanger arm to or adjacent to said tank for movement in a generally upright plane;
- a rigid lower hanger arm;
- means for pivoting said lower arm to said upper arm for

movement in said generally upright plane or a parallel plane;
an array of gas diffusers pivotably connected to the lower portion of said lower hanger arm, said array having a substantially horizontal operating position when submerged in said liquids; and
means cooperating with said upper hanger arm and said diffuser array for rotating said diffuser array from said substantially horizontal position to an upwardly extending servicing position above the surface of said liquids at the side of said tank, said rotating occurring as said upper hanger arm is pivoted to a servicing position extending upwardly from said means for pivoting said upper hanger arm.

4,294,697

APPARATUS FOR TREATMENT OF SEWAGE

Toshio Sawa; Masayoshi Kubota; Sankichi Takahashi, and Toyohiko Kaneko, all of Ibaraki, Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed Jul. 25, 1979, Ser. No. 60,475

Claims priority, application Japan, Mar. 22, 1979, 54/34592

Int. Cl.³ C02F 1/24; B03D 1/00

U.S. Cl. 210—221.1

12 Claims



1. An apparatus for the treatment of sewage comprising: a processing tank having a floating-separation zone formed at the upper portion therein and an electrolysis zone formed therein below the floating-separation zone; inlet means to introduce sewage into said tank in the floating-separation zone; means regulating flow of the sewage into the tank comprising a cylinder mounted in the processing tank and said inlet means opening inwardly into the cylinder, said cylinder having a lower portion in the form of a skirt that opens downwardly so as to collect bubbles; means dividing the floating-separation zone into two portions; a fixed bed of electrically conductive porous adsorbent particles disposed in the electrolysis zone for adsorbing organic matter, nitrogen compounds and metal ions in the sewage; a plurality of anode and cathode electrodes disposed among the adsorbent particles; means supplying electric current to said electrodes thereby polarizing the individual adsorbent particles and electrolyzing water to produce hydrogen and oxygen bubbles on the surface of each individual adsorbent particle, the rising flow of the bubbles floating suspended matter and organic matter upward into the floating-separation zone; means to discharge the suspended matter and organic matter attached to the bubbles out of the processing tank; and means to take out the sewage so that the sewage will pass from said inlet means to be treated through the floating-separation zone and the electrolysis zone out of the processing tank.

4,294,698

DEVICE FOR CLEANING LIQUID SURFACES

Jean A. L. Bronnec, Brest, France, assignor to Etablissements Generaux de Mecanique de l'Ouest, Brest, France


Filed Nov. 26, 1979, Ser. No. 97,724

Claims priority, application France, Apr. 12, 1981, 78 34077

Int. Cl.³ E02B 15/04

U.S. Cl. 210—242.3

16 Claims



1. A device for cleaning a liquid surface to remove a polluted material therefrom, said device comprising:
(a) a barrier adapted to float on the surface of said liquid, said barrier comprising two diverging wing portions and a tow portion positioned between said wing portions;
(b) inlet means adapted to receive said polluted material prior to passing said polluted material to a recovery apparatus; and
(c) hitching means adapted to maintain each of said wing portions spaced from one another at one of their ends while said barrier is being towed;
each of said wing portions of said barrier comprising only a wing rope adapted to at least partially float on said liquid surface, and wherein said central portion comprises only a flexible tow rope arranged between said wing ropes, said tow rope being adapted to pull said recovery apparatus to thereby exert tension on each of said wing ropes in an amount adapted to maintain each of said wing ropes such that they do not substantially curve in a horizontal plane relative to said surface and to allow for movement of said wing ropes in a vertical plane with respect to said surface.

4,294,699

APPARATUS FOR PURIFYING A LIQUID BY ION-EXCHANGE

Willy Herrmann, Strombergstrasse 21, 7140 Ludwigsburg, Fed. Rep. of Germany

Continuation of Ser. No. 952,635, Oct. 19, 1978, abandoned.


This application Apr. 29, 1980, Ser. No. 144,926

Claims priority, application Fed. Rep. of Germany, May 29, 1978, 2823432

Int. Cl.³ B01D 15/00

U.S. Cl. 210—287

4 Claims



1. Filtering apparatus for treating a liquid such as softening and/or purifying water, comprising an axially elongated hol-

low tubular body, a bed of particulate ion-exchange material confined in said tubular body, at least a portion of the axial length of said tubular body being compressible for varying the volume within said tubular body, said tubular body having an inlet opening and an outlet opening for flowing a liquid through said bed therein, biasing means for applying compressive force for adjusting the volume within said tubular body when said bed of particulate ion-exchange material shrinks, wherein the improvement comprises a supporting bracket for mounting said tubular body and said bracket being arranged to be secured on a wall, the compressible portion of said tubular body comprises an axially extending tubular bellows portion so that the axial length of said tubular body can be decreased as the volume of said bed of particulate ion-exchange material shrinks, said bracket being elongated in the same direction as said tubular body and having an integral stationary abutment at each of the ends thereof spaced apart in the elongated direction, said tubular body being supported between said support abutments with said biasing means securing said tubular body between said support abutments and said tubular body being removably mounted between said abutments, and said biasing means comprising an axially extending compression spring extending in the elongated direction of said tubular body and support bracket and bearing at one end against one of said abutments and at the other end against said tubular body for applying a compressive force against the bed of ion-exchange material within said tubular body and against said tubular body so that as the volume of the bed of ion-exchange material shrinks said spring maintains the compressive force on the bed and deforms the tubular bellows part in the axial direction relative to the shrinkage of the bed, said compression spring being located exteriorly of said tubular body and said tubular body being displaceable in the elongated direction within said bracket against said compressive spring for removing said tubular body from said bracket.

4,294,700

SUBMERGED LARGE DIAMETER SEAL


Thomas J. Casper, Waukesha, Wis., assignor to Envirex Inc., Waukesha, Wis.

Filed Jun. 8, 1979, Ser. No. 47,191

Int. Cl.³ B01D 33/10

U.S. Cl. 210-403

4 Claims



2. A drum screen comprising a rotatable drum having one end provided with a central opening to receive the raw flow, a drum well surrounding the lower part of the drum to receive the screened flow through the drum periphery, one wall of the drum well being provided with an opening which adjoins the opening of said one end of the drum, said one end of the drum having an inwardly extending circular flange, said flange having an end face which is normal to the axis of rotation of the drum, said one wall having a circular rim which is concentric with said flange and extends into the drum through the opening of said one end thereof, and a seal to function between said end of the drum and said wall of the drum well, said seal

comprising (1) a seamed tubing of a flexible, low friction material fitted over said flange, said tubing being of one of two forms, one form being a circular element of integral construction, the second form being a linear element with aligned and abutted ends, said tubing being opened at the seam and assembled on said flange with its inner side opposite the seam pressed against the end face of the flange, and (2) a stationary element of a molded wear resistant material and including a flat base which is drawn around the outside of said rim and clamped thereto, said stationary element further including a radially projecting flange which is pivotally movable relative to and pressed by the raw water within the drum against the tubing.

4,294,701

PAINT STRAINER


James P. Whelan, North Marshfield, Mass., assignor to Ad-Tec Products, Inc., Plymouth, Mass.

Filed Jan. 24, 1977, Ser. No. 761,895

Int. Cl.³ B01D 23/28

U.S. Cl. 210-497.2

3 Claims



1. A paint strainer comprising a hollow truncated conical structure having an imperforate side wall of stiff paperboard and open ends, one of which is smaller than the other, a web of flexible screening material stretched taut across the smaller end constituting a perforate bottom for the structure, said screening material being folded upwardly from the bottom onto the outer surface of the side wall and a layer of solvent-resistant adhesive securing the entire surface area of the upwardly-folded portion of the web of flexible screening material to the entire outer surface area of the side wall covered by said upwardly-folded portion of the web of flexible screening material.

4,294,702

APPARATUS FOR THE CONTROLLABLE REMOVAL OF ONE OR MORE PHASES FROM A LIQUID-LIQUID EXTRACTOR

Lorenz Finsterwalder, Karlsruhe, Fed. Rep. of Germany, assignor to Gesellschaft zur Wiederaufarbeitung von Kernbrennstoffen mbH, Eggenstein-Leopoldshafen, Fed. Rep. of Germany

Filed Jun. 3, 1977, Ser. No. 803,317

Claims priority, application Fed. Rep. of Germany, Jun. 3, 1976, 2624936


Int. Cl.³ B01D 11/04

U.S. Cl. 210-513

12 Claims

1. In a liquid-liquid extractor, including a settler for separation of light and heavy liquid phases, an arrangement for controllable removal of one or more liquid phases said arrangement comprising: a tapering member connected to an opening in a wall of the settler for removing a heavy phase from the settler; a first tube having a first end connected to an opening in said tapering member and a second end extending to the level of a light phase; and a second tube and means for intro-

ducing a gas into said second tube, said second tube being connected to said first tube for introducing gas into said first



tube to move liquid present in the first tube in an upwardly direction.

4,294,703

HYDROGEN PEROXIDE TREATMENT OF EFFLUENT

Klaus G. Wilms, Dormagen, and Helmut Waldmann, Leverkusen, both of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Jul. 2, 1980, Ser. No. 165,422

Claims priority, application Fed. Rep. of Germany, Jul. 11, 1979, 2927912

Int. Cl.³ C02F 3/00

U.S. Cl. 210-631

6 Claims

1. In the process for decreasing the COD-content of effluent by treating with hydrogen peroxide in the presence of a transition metal compound, the improvement which comprises adding to the effluent about 5 to 40% of the calculated quantity of H_2O_2 required for the total oxidation of the total COD-content of the effluent, the transition metal compound being dissolved in the effluent in an amount such that the molar ratio of H_2O_2 to transition metal is from about 30:1 to 3:1, bringing the pH initially to about 2 to 9, maintaining the effluent at about 5° to 100° C., separating from the effluent whatever material has flocculated, and after the removal of the flocculated material the effluent is subjected to biological degradation.

4,294,704

PROCESS FOR THE MANUFACTURE OF PRINTING PAPER AND BOARD

Jean-Claude Daniel, Fontenay-Sous-Bois; Jacques Grossolleil, Pairs, and Robert Roulet, Lyon, all of France, assignors to Rhone-Poulenc Industries, Paris, France

Continuation of Ser. No. 898,953, Apr. 21, 1978, abandoned.


This application Mar. 31, 1980, Ser. No. 135,239

Claims priority, application France, Apr. 22, 1977, 77 12159

Int. Cl.³ B01D 13/00; C02F 1/44

U.S. Cl. 210-651

5 Claims



1. Process for the manufacture of printing paper and board having increased wet tear strength and dry tear strength comprising coating the paper or board on one surface with a coat-

ing composition containing as a binder an aqueous latex of a synthetic polymer characterized by the fact that the content in the latex of hydrosoluble compounds dissolved in the aqueous phase is less than 0.5% by weight in relation to the polymer, said synthetic polymer being selected from the group consisting of styrene-butadiene copolymers, carboxyl styrene-butadiene copolymers, vinyl polyacetates, carboxyl vinyl polyacetates, alkyl acrylate-vinyl acetate copolymers, and carboxyl alkyl acrylate-vinyl acetate copolymers.

2. Process as claimed in claim 1, in which hydrosoluble compounds are removed from a latex obtained of a synthetic polymer prepared by emulsion polymerization.

4,294,705

METHOD AND AN AGENT FOR CHEMICAL PURIFICATION OF WATER BY MEANS OF CHEMICAL PRECIPITATION AND MAGNETIC SLUDGE SEPARATION

Carl-Johan S. Hellestam, Helsingborg, Sweden, assignor to Boliden Aktiebolag, Stockholm, Sweden

PCT No. PCT/SE78/00063, § 371 Date Jun. 25, 1979, § 102(e)

Date May 31, 1979, PCT Pub. No. WO79/00230, PCT Pub.


Date May 3, 1979

PCT Filed Oct. 23, 1978, Ser. No. 117,492

Int. Cl.³ B01D 35/06

U.S. Cl. 210-695

1 Claim



1. A method of chemically purifying water with a subsequent magnetic sludge separation comprising introducing into water a solid crystalline precipitant comprising as major components $Al_2(SO_4)_3$ and/or $FeSO_4$ together with a magnetic material, said precipitant consisting of a solid, crystalline composition having a uniform distribution of the magnetic material therein.

4,294,706

PROCESS FOR TREATING WASTE WATER

Naomichi Kakiyama; Yoshiaki Harada, and Norio Uedono, all of Osaka, Japan, assignors to Osaka Gas Company, Limited, Osaka, Japan

Filed Apr. 28, 1980, Ser. No. 144,696

Claims priority, application Japan, May 16, 1979, 54-60886


Int. Cl.³ C02F 1/74

U.S. Cl. 210-762

12 Claims

1. A process for treating ammonia-containing waste water which comprises introducing at a pH of about 8.5 to about 11.5 the waste water to a reactor to subject the same to wet oxidation with an oxygen-containing gas in the presence of a catalyst while maintaining the waste water at a temperature of about 100° to about 370° C. and at pressure permitting the waste water to remain in the liquid phase, the oxygen-containing gas containing oxygen in an amount of about 1 to about 1.5 times

the theoretical amount required for decomposing the ammonia, organic substances and inorganic substances contained in the waste water, the catalyst being supported by at least one of zirconia and titania and comprising at least one of iron, cobalt, nickel, ruthenium, rhodium, palladium, iridium, platinum, copper, gold, tungsten and compounds thereof insoluble or



sparingly soluble in water, and supplying an alkali substance to the reactor at a rate required to maintain at least about 80% of the waste water introduced to the reactor and positioned toward the water inlet of the reactor at a pH of at least about 8 at all times and to permit the water resulting from the wet oxidation to retain a pH of about 5 to about 8.

4,294,707

METHOD FOR SEPARATING BLOOD AND A BARRIER DEVICE THEREFOR

Tatsuhiko Ikeda, Kawasaki, and Soichiro Terada, Tama, both of Japan, assignors to Terumo Corporation, Tokyo, Japan

Filed Mar. 19, 1980, Ser. No. 131,874

Claims priority, application Japan, Mar. 23, 1979, 54-33943

Int. Cl.³ B01D 21/26

U.S. Cl. 210—782

16 Claims



1. A method for separating blood collected in a blood-collecting tube into a serum part and a solid component part by centrifugation, comprising:

introducing a barrier formed of an elastic foamed plastic member into said blood-collecting tube, said elastic foamed plastic member having a porosity of 97 to 98%, a continuous-pore size of 50 to 400 μ , the pores of said elastic foamed plastic member being thermally treated for dissolving a filmy material formed around the pores in the foaming step, an overall true specific gravity greater than that of said serum part, and a frusto-conical upper portion, the upper cross section of which is larger than the cross section of said blood-collecting tube;

moving said elastic foamed plastic member to the interface between a serum part layer and a solid component layer in the blood by centrifugal force produced in centrifuging the blood; and

separating serum in the blood.

4,294,708 PROCESS FOR AUGMENTING OR ENHANCING THE AROMA OF PERFUMED ARTICLE USING ALKYL CYCLOALKENYL CARBINOL






Mark A. Sprecker, Sea Bright; Frederick L. Schmitt, Holmdel; Manfred H. Vock, Locust; Joaquin F. Vinals, Red Bank, all of N.J., and Jacob Kiwala, Brooklyn, N.Y., assignors to International Flavors & Fragrances Inc., New York, N.Y.

Division of Ser. No. 52,335, Jun. 27, 1979, Pat. No. 4,235,729, which is a division of Ser. No. 8,924, Feb. 2, 1979, Pat. No. 4,197,328, which is a continuation-in-part of Ser. No. 953,128, Oct. 20, 1978, Pat. No. 4,195,099. This application Feb. 8, 1980, Ser. No. 119,889

Int. Cl.³ D06M 13/16

U.S. Cl. 252—8.6



1 Claim




1. A process for augmenting or enhancing the aroma of a perfumed article selected from the group consisting of fabric

softener compositions, fabric softener articles and optical brightener compositions comprising the step of intimately

relationship and further provided that at least one propylene oxide unit is always present; and X is an anion.



admixing with a fabric softener article coating, or a fabric softener composition, or an optical brightener composition, from 0.01% up to 0.5% of a compound having the structure:



4,294,709

SPIN FINISH WITH ANTI-STATIC AGENT

Norman Anderson, Matthews, N.C.; Richard Peak, and James A. Moyse, both of Manchester, England, assignors to Imperial Chemical Industries Limited, London, England

Filed Jan. 10, 1980, Ser. No. 110,994

Claims priority, application United Kingdom, Jan. 26, 1979, 02933/79; Jun. 4, 1979, 19385/79


Int. Cl.³ D06M 15/42, 13/46, 15/00

U.S. Cl. 252—8.8

4 Claims

1. A spin finish composition comprising

- (1) a lubricant selected from the group consisting of mineral oils, esters and copolymers of ethylene oxide, propylene oxide and mixtures thereof for spin finishes, and
- (2) an antistatic agent of the formula



where:

R¹ and R², which may be same or different, are alkyl groups containing up to six carbon atoms;
R³ is an alkyl group containing up to twelve carbon atoms;
R⁴ is an alkylene group containing up to ten carbon atoms;
R⁵ and R⁶ are hydrogen or methyl;
m and n are integers from 0 to 60, provided that either m or n is at least 1 and where R⁵ and R⁶ are different, the polyalkylene oxide units are in block or random copolymer

4,294,710

DETERGENT SOFTENER WITH AMINE INGREDIENT

Frederick E. Hardy, Gosforth, and Colin A. Dewar, Tweedmouth, both of England, assignors to The Procter & Gamble Company, Cincinnati, Ohio

Filed Jun. 30, 1980, Ser. No. 164,446

Claims priority, application United Kingdom, Jul. 5, 1979, 23527/79


Int. Cl.³ D06M 11/04, 13/36, 13/46

U.S. Cl. 252—8.8


6 Claims

1. A method of preparing a detergent composition adapted to provide fabric softening benefits when used to wash textiles, said method constituting the steps of

- (a) forming a slurry containing (i) an anionic surfactant selected from the group consisting of sodium and potassium C₉-C₁₅ alkyl benzene sulphonates, C₁₂-C₁₈ alkyl sulphates and C₁₂-C₁₈ alkyl polyethoxy ether sulphates containing from about 1 to about 12 ethoxy groups per mole and mixtures thereof, said anionic surfactant being present in an amount to provide from about 3% to about 30% of the composition, (ii) a water soluble alkaline detergency builder salt selected from the group consisting of alkaline sodium and potassium carbonates, borates, phosphates, polyphosphates, silicates, polycarboxylates, polyphosphonates, amino polycarboxylates, amino polymethylene phosphonates and mixtures thereof, said detergency builder salt being present in an amount to provide from about 10% to about 80% of the composition,
- (b) spray during said slurry so as to form free-flowing spray dried granules and
- (c) spraying said spray dried granules with a tertiary amine in liquid form in an amount of from about 1% to about 25% by weight of the composition, said amine being selected from the group consisting of (i) alkylamines of formula




wherein R₁ and R₂ are each radicals independently selected from C₁₀-C₂₆ alkyl and alkenyl groups and R₃ represents a radical selected from the group consisting of



wherein R₄ is a C₁-C₄ alkyl group, each R₅ is independently selected from H and C₁-C₄ alkyl groups and each R₆ is independently selected from H and C₁-C₂₀ alkyl groups and

(ii) imidazoline derivatives of formula



wherein R₁ and R₂ are as defined above and (iii) mixtures of any of (i) and (ii).

(d) dry mixing oxygen bleaching agent or enzyme or silica-silicone suds suppressor or mixtures thereof with the product of step (c).

4,294,711

WASHING AND SOFTENING COMPOSITIONS AND METHODS FOR THEIR MANUFACTURE

Frederick E. Hardy, Gosforth, and Barry Stoddart, Gateshead, both of England, assignors to The Procter & Gamble Company, Cincinnati, Ohio

Filed Sep. 15, 1980, Ser. No. 187,371

Claims priority, application United Kingdom, Sep. 21, 1979, 32918/79


Int. Cl.³ C11D 3/42, 11/00, 11/02; D06M 13/44

U.S. Cl. 252—8.75

9 Claims

1. A granular detergent composition adapted to impart a soft feel to fabrics washed therewith, consisting essentially of:

- (a) from about 3% to about 30% by weight of a polyethoxy nonionic detergent having a hydrophilic-lipophilic balance in the range from about 8 to about 15 and having not more than an average of 16 ethoxy units per molecule;
- (b) from about 1% to about 15% by weight of a cationic surfactant material;
- (c) from about 10% to about 80% by weight of a detergency builder; and
- (d) from about 0.001% to about 3% by weight of an acid optical brightener of the following structure



wherein R is selected from the group consisting of methylamino- and morpholino- groups.

4,294,712

SELF-LUBRICATING BEARING

Toshihiko Ueno, and Teruhisa Tomogane, both of Kobe, Japan, assignors to Bando Chemical Industries, Ltd., Kobe, Japan
Filed Aug. 21, 1980, Ser. No. 180,166

Claims priority, application Japan, Aug. 29, 1979, 54-110944; Sep. 26, 1979, 54-124401; Mar. 17, 1980, 55-34339; Mar. 17, 1980, 55-34340; Mar. 17, 1980, 55-34341

Int. Cl.³ C10M 5/10, 5/02, 7/14, 7/04

U.S. Cl. 252—12

11 Claims

1. A self-lubricating bearing comprising 1 to 40 volume

percent lubricating oil; 0.1 to 20 volume percent carrier for said lubricating oil, said carrier being selected from the group consisting of polynorbornene resin, expanded graphite and mixtures thereof; and remainder main bearing material comprising another synthetic resin having properties of slidability and abrasion resistance.

11. The bearing of claim 1, wherein said synthetic resin is selected from the group consisting of polyamides, polyacetals, polybutylenephthalates, polycarbonates, and polytetrafluoroethylenes.

4,294,713

GREASE COMPOSITIONS CONTAINING SELECTED SHIELDED POLYSILICATE COMPOUNDS

Karl O. Knollmueller, Hamden; Robert J. Fairbrother, and David F. Gavin, both of Cheshire, all of Conn., assignors to Olin Corporation, New Haven, Conn.

Filed Mar. 31, 1980, Ser. No. 135,744

Int. Cl.³ C10M 5/26, 7/48, 7/50

U.S. Cl. 252—28

28 Claims

1. A grease composition comprising:

- (a) a major amount of a shielded polysilicate compound selected from the group consisting of alkoxysilane cluster compounds, alkoxysilanol cluster compounds, alkoxysilane ester compounds, alkoxysilane multiple cluster compounds, silicone-bridged alkoxysilane double cluster compounds, distillation residues containing these compounds, and mixtures thereof; and
- (b) an amount of at least one grease thickener sufficient to thicken said shielded polysilicate compound to a grease consistency.

4,294,714

CARBOXYLIC ACID SALT CONTAINING DEPOSIT CONTROL ADDITIVES AND FUEL AND LUBE OIL COMPOSITIONS CONTAINING THEM

Robert A. Lewis, Berkeley, and Lewis R. Honnen, Petaluma, both of Calif., assignors to Chevron Research Company, San Francisco, Calif.


Filed Jul. 25, 1979, Ser. No. 60,306

Int. Cl.³ C10M 1/32, 3/26; C10L 1/22

U.S. Cl. 252—34

13 Claims


2. An additive composition effective as a minor component in a fuel or lubricating oil composition for reducing the deposition of solids in the intake system and crankcase of an internal combustion engine, said additive composition comprising at least one salt of the formula




wherein:

- (1) R¹ is a hydrocarbyl group having a carbon atom content in the range 3 to 30 selected from the group consisting of alkyl, phenyl, cyclohexyl, alkenyl, cyclohexenyl, combinations thereof and of said groups having a single hydrogen atom thereof substituted by a hydroxyl or alkoxyl group, provided that said substituent is attached to a carbon atom at least 4 carbon atoms distant from the carboxyl group of said anion;

- (2) R² is a hydrocarbyl group having a carbon atom content in the range from 1 to 30 selected from the group consisting of phenyl, mono-, di- and trialkylphenyl, alkyl, alkenyl, cyclohexyl, cyclohexenyl and combinations thereof;
- (3) A is an alkylene group having a carbon atom content in the range of from 2 to 4 and x is an integer sufficient to provide said cation in unprotonated form with a molecular weight in the range of from about 500 to 10,000;
- (4) L is monovalent and selected from the group consisting of radicals of the formula



wherein J is an alkylene group having a carbon atom content in the range 2 to 6 and y is an integer in the range 1 to 11,



wherein n is an integer in the range 2-6, and

(iii) NHCH₂C(OH)HCH₂NH₂;

- (5) R³, R⁴ and R⁵ are the same or different groups having a carbon atom content in the range 0 to 16 selected from the group consisting of hydrogen, hydrocarbyl, acyl, alkoxy, ketoalkyl, hydroxyalkyl and cyanoalkyl groups; and
- (6) a is an integer in the range 1 to 3.

4,294,715

IMPREGNATING AGENT AND ITS USE

Alfons Klein, Duesseldorf; Rudolf Kron, Leverkusen; Karlfried Wedemeyer, Cologne; Ernst Knust, and Lothar Havenith, both of Leverkusen, all of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany
Filed Oct. 11, 1979, Ser. No. 83,876

Claims priority, application Fed. Rep. of Germany, Jul. 2, 1979, 2926609

Int. Cl.³ H01B 3/18, 3/40

U.S. Cl. 361—318

5 Claims

1. A dielectric composition comprising a mixture of isopropylated diphenyls, said mixture containing 30 to 60 parts by weight of mono-isopropylated diphenyls and 70 to 40 parts by weight of poly-isopropylated diphenyls, said poly-isopropylated diphenyls comprising di-, tri- and tetra-isopropylated diphenyls, said poly-isopropylated diphenyls comprising 60 to 85 parts by weight of di-isopropylated diphenyls, 10 to 35 parts by weight of tri-isopropylated diphenyls and 0.5 to 5 parts by weight of tetra-isopropylated diphenyls, the amount of di-, tri- and tetra-isopropylated diphenyls being based upon the total amount of poly-isopropylated diphenyls said mixture containing an epoxide and a hydroquinone derivative.

4,294,716

HALOCARBON AND AZEOTROPE REFRIGERANT COMPOSITIONS CONTAINING OFFENSIVE WARNING COMPONENT

Joseph F. Saccavino, W. Branch Rd., Mahopac, N.Y. 10541, and Edward A. Vanek, 964 Cedarhurst St., North Woodmere, N.Y. 11581

Filed May 14, 1980, Ser. No. 149,163

Int. Cl.³ C09K 5/00; C10M 01/30

U.S. Cl. 252—68

1 Claim

1. A refrigerant composition comprising: a substantially odorless chlorofluorocarbon; an odorant component, said component being not more than

2% by weight of the composition, said component being inert, volatile and soluble in said chlorofluorocarbon, said component being an organic ketone selected from the group consisting of 3-Methyl-Cyclohexanone and Methyl Isobutyl Ketone, said refrigerant composition adapted for use in a refrigeration system whereby any leaks which develop in said system can be readily detected due to the noticeable and pervasive odor resulting from the vaporization of said odorant component such that said leak may be rapidly repaired preventing continued operation of said refrigeration system at reduced efficiency.

4,294,717

COMPOSITIONS CONTAINING AN ALKALI METAL MONO- OR POLYALKYLARYLSULFONATE AND THE CORRESPONDING HYDROPEROXIDE, PROCESS FOR THEIR PREPARATION AND DETERGENT COMPOSITIONS CONTAINING THEM

Pierre Couderc; Jean-Luc Grardel, both of Bethune, and Gerard Caux, Bully les Mines, all of France, assignors to Societe Chimique des Charbonnages SA, Paris, France

Filed Apr. 16, 1979, Ser. No. 30,666


Claims priority, application France, Apr. 14, 1978, 78 11082; Oct. 10, 1978, 78 28907

Int. Cl.³ C11D 7/54, 7/56, 9/42

U.S. Cl. 252—97

36 Claims

11. A dry detergent composition containing up to 30% of a solid, dry bleaching agent comprising (a) at least one alkali metal alkylarylsulfonate having the formula:




wherein

M is an alkali metal;

R' is lower alkyl; and

n is 0, 1, 2, 3, or 4; and

(b) the hydroperoxide obtained by hydroperoxidation of said at least one alkali metal alkylarylsulfonate and having the formula



wherein M, R' and n are as defined above;

wherein the amount of said hydroperoxide contained in said detergent composition is from 0.1 to 21% by weight of said detergent composition.

14. The detergent composition of claim 11, further comprising at least one anionic detergent, at least one soap, at least one non ionic detergent, sodium triphosphosphate, sodium silicate and at least one of sodium sulfate or sodium carbonate.

4,294,718

NON-GELLING INORGANIC SALT CRUTCHER SLURRIES

James A. Kaeser, Somerset, N.J., assignor to Colgate-Palmolive Company, New York, N.Y.

Filed Mar. 10, 1980, Ser. No. 128,574

Int. Cl.³ C11D 3/04, 7/14

U.S. Cl. 252—135

22 Claims

1. A method of retarding or preventing the gelation of a miscible and pumpable crutcher slurry containing from about 40 to 70% of solids and 60 to 30% of water, of which solids content, on a 100% solids basis, about 55 to 85% is sodium bicarbonate, about 5 to 25% is sodium carbonate, and about 5 to 25% is sodium silicate of Na₂O:SiO₂ ratio within the range of 1:1.4 to 1:3, with the ratio of sodium bicarbonate:sodium carbonate being within the range of about 2:1 to 8:1, the ratio of sodium carbonate:sodium silicate being within the range of about 1:3 to 3:1, and the ratio of sodium bicarbonate:sodium silicate being within the range of about 2:1 to 10:1, which comprises preparing a crutcher slurry of the described composition containing from 0.1 to 2% of a citric material selected from the group consisting of citric acid, water soluble citrate and mixtures thereof, and from 0.1 to 1.4% of magnesium sulfate, with the total of such citric material and magnesium sulfate, in combination, being gelation retarding and at least 0.4% of the slurry, and mixing such composition in the crutcher during preparation thereof.

4,294,719

POLYISOCYANATES WHICH CONTAIN CARBODIIMIDE GROUPS AND WHICH ARE STABLE IN STORAGE

Kuno Wagner, Leverkusen; Hans-Dieter Block, and Walter Schäfer, both of Cologne, all of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany


Continuation of Ser. No. 653,689, Jan. 30, 1976, abandoned. This application Aug. 8, 1977, Ser. No. 822,489

Claims priority, application Fed. Rep. of Germany, Feb. 1, 1975, 2504400

Int. Cl.³ C08G 18/18, 73/10

U.S. Cl. 252—182

19 Claims



1. A composition of matter comprising a storage-stable, catalyst-free, equilibrium mixture of an organic carbodiimide, an organic uretone imine, and an organic isocyanate produced by the process comprising:

- contacting an organic mono- and/or polyisocyanate, optionally dissolved in an inert solvent, with a high molecular weight, insoluble catalyst, said catalyst comprising a high molecular weight, insoluble inorganic or organic matrix and a low molecular weight carbodiimidization catalyst linked to said matrix via ionic bonds, and
- removing said insoluble catalyst when the desired degree of carbodiimidization has been reached.

4,294,720

PROCESS FOR THE PREPARATION OF GAS MIXTURES

Pieter Visser, Amsterdam, and Johan P. van de Water, The Hague, both of Netherlands, assignors to Shell Oil Company, Houston, Tex.

Filed Dec. 7, 1979, Ser. No. 101,340

Claims priority, application Netherlands, Dec. 22, 1978, 7812466

Int. Cl.³ C01B 2/06

U.S. Cl. 252—373

5 Claims

1. A process for preparing a gas mixture containing hydrogen and carbon monoxide comprising partially oxidizing a hydrocarbon feedstock with oxygen or an oxygen-containing gas in a partial oxidation reactor at elevated pressure to produce a raw product gas, contacting the raw product gas in a quench zone with water to remove soot and other contaminating material from the gas and producing a gas mixture and a soot-containing liquor, removing soot-containing liquor from the quench zone, and contacting the liquor removed with oxygen or an oxygen-containing gas in a soot oxidation reactor at a temperature between 240° C. and 375° C., and at a pressure at least equal to the vapor pressure of water at the temperature used to oxidize the soot in the liquor and producing CO₂ and a substantially soot-free water effluent.

4,294,721

PROCESS FOR PREPARING COMPONENTS OF CATALYSTS FOR POLYMERIZING ALPHA-OLEFINS AND MIXTURES THEREOF WITH ETHYLENE

Giuliano Cecchin, Ferrara, and Enrico Albizzati, Arona, both of Italy, assignors to Montedison S.p.A., Milan, Italy

Continuation of Ser. No. 921,717, Jul. 3, 1978, abandoned. This application Mar. 28, 1980, Ser. No. 134,773

Claims priority, application Italy, Jul. 4, 1977, 25345 A/77

Int. Cl.³ C08F 4/64

U.S. Cl. 252—429 B

7 Claims

1. Process for preparing solid catalyst components for the polymerization of alpha-olefins and mixtures thereof with ethylene, which comprises reacting a Ti compound containing at least one Ti-halogen linkage with at least one of the following substances:

- a hydrocarbyl electron-donor compound ED which does not contain active hydrogen atoms and an adduct (a) of a Mg dihalide with at least one hydrocarbyl electron-donor compound AH containing active hydrogen atoms and present in the adduct in an amount of at least 0.5 moles/mole of Mg dihalide, electron-donor compound ED being reacted in an amount of not less than 0.05 moles/mole of compound AH of the adduct;
- an adduct (b) of at least a Mg dihalide with a compound AH and ED, as defined in (1), compound ED being present in an amount ranging from 0.05 to 1 mole/mole of compound AH, and adducts (a) and (b) being prepared without co-grinding of the Mg dihalide with compounds AH and ED; the amount of compound ED that remains in the solid after extraction thereof with TiCl₄ at 80° C. for 2 hours being comprised between 0.3 and 3 moles/gram atom of Ti, and the amount of Ti compounds extractable with TiCl₄ at 80° C. being lower than 50%.

4,294,722

PREPARATION OF VANADIUM PHOSPHORUS CATALYSTS

Noel J. Bremer, Kent, and Dennis E. Dria, Spencer, both of Ohio, assignors to Standard Oil Company, Cleveland, Ohio

Division of Ser. No. 106,786, Dec. 26, 1979, Pat. No. 4,244,879.

This application May 19, 1980, Ser. No. 150,783

Int. Cl.³ B01J 27/14

U.S. Cl. 252—435

18 Claims

1. A process for the preparation of oxidation catalysts containing the mixed oxides of vanadium and phosphorus which comprises

- introducing a pentavalent vanadium-compound into an organic liquid capable of at least partially solubilizing and capable of reducing vanadium to a valence state less than +5 to form a reaction medium in which at least a portion of said vanadium compound remains unsolubilized;
- effecting reduction of at least a portion of said vanadium to a valence state of +4;
- removing unsolubilized vanadium-containing compounds having a particle size greater than about 0.1 mm diameter;
- adding a pentavalent phosphorus-containing compound to the reaction medium resulting from step (c) to form a catalyst precursor precipitate;
- recovering said catalyst precursor precipitate;
- drying said catalyst precursor precipitate;
- calcining said precipitate to form the active oxidation catalyst.

4,294,723

HEAT RESISTANT CATALYST FOR THE PRODUCTION OF SULFURIC ACID FOR USING A GAS CONTAINING SULFUR DIOXIDE IN A HIGH CONCENTRATION

Haruichi Hara, Toyonaka; Toshihide Kanzaki, Takatsuki; Hisanao Motomuro, and Akiyoshi Adachi, both of Suita, all of Japan, assignors to Nippon Shokubai Kagaku Kogyo Co. Ltd., Osaka, Japan

Continuation of Ser. No. 689,807, May 25, 1976, abandoned.

This application Sep. 27, 1977, Ser. No. 837,226

Claims priority, application Japan, May 29, 1975, 50-63492

Int. Cl.³ B01J 27/02

U.S. Cl. 252—440

5 Claims

1. A heat resistant catalyst suitable for the production of sulfuric acid by using a gas containing sulfur dioxide in a high concentration at a reaction temperature of 420° to 800° C. which consists essentially of vanadium pentoxide as the main catalytic component, potassium sulfate as a promoter and a carrier consisting essentially of diatomaceous earth wherein the ratio of K₂O(mol)/V₂O₅(mol) is 4 to 5, V₂O₅ content is 5.5 to 7% by weight and the sum of the value of said ratio and the V₂O₅ content (% by weight) is 9.5 to 11.

4,294,724

TITANIUM IMPREGNATED SILICA-CHROMIUM CATALYSTS

Max P. McDaniel, Bartlesville, Okla., assignor to Phillips Petroleum Company, Bartlesville, Okla.

Filed Feb. 6, 1980, Ser. No. 118,893

Int. Cl.³ B01J 21/08, 23/26, 21/00


U.S. Cl. 252—451

28 Claims

1. A process for producing a chromium-containing catalyst comprising forming a silica hydrogel containing a pore preserving agent selected from (1) organic silicon compounds having the structure R_nSiA_{4-n} wherein n is an integer of 2 or 3, and wherein each R is a saturated or unsaturated hydrocarbon group wherein each R can be the same or different and wherein A is selected from the group consisting of hydroxy radicals, halides and alkoxy radicals in which the alkyl group therein contains from 1 to about 10 carbon atoms, (2) water soluble inorganic acids which are sufficiently ionized to produce a pH of 0 to 3.5, (3) organic acids having an acid strength equal to or greater than that of acetic acid, and (4) anionic, cationic or non-ionic surfactants; drying said hydrogel by means of air oven drying, spray drying, tray drying, vacuum oven drying or drying under a heat lamp to form a xerogel; and anhydrously incorporating a titanium compound into said xerogel, and wherein said chromium is introduced by either coprecipitating same with said silica hydrogel, by combining an aqueous solution of a water-soluble chromium compound with said hydrogel, or adding anhydrous solution of a chromium compound soluble in non-aqueous solvents to said xerogel.

17. A process for producing a chromium-containing catalyst comprising forming a silica hydrogel and thereafter removing

water to form a xerogel, said silica in either the hydrogel stage or the xerogel stage being impregnated with an aqueous titanium-containing composition formed by mixing an essentially water-free organic acid and a titanium compound of the formula



wherein the R and R' groups are the same or different and are selected from 1-7 carbon atom alkyl radicals to give a titanium-containing composition and thereafter diluting said titanium-containing composition with water to give said aqueous titanium-containing composition, and wherein said chromium is introduced by either coprecipitating same with said silica hydrogel, by combining an aqueous solution of a water-soluble chromium compound with said hydrogel, or adding an anhydrous solution of a chromium compound soluble in a non-aqueous solvent to said xerogel.

4,294,725

CATALYST, METHOD FOR CATALYST MANUFACTURE AND USE

Dan Fraenkel, and Bruce C. Gates, both of Newark, Del., assignors to University of Delaware, Newark, Del.

Filed Nov. 20, 1979, Ser. No. 95,989

Int. Cl.³ B01J 29/14

U.S. Cl. 252—455 Z

3 Claims

1. A Fischer-Tropsch type catalyst comprising a particulate synthetic zeolite catalyst support having a pore size in the range of 2-10 Å, which has ion exchange properties, within which there is incorporated, by ion exchange, at least one reducible transition metal having catalytic properties effective in the conversion of CO and H₂ to hydrocarbon products consisting essentially of cobalt, said transition metal being reduced by the vapor of at least one preselected reductant metal consisting essentially of cadmium having a reduction potential greater than the reduction potential of said transition metal at a temperature below about 800° C.

2. The method of preparing a Fischer-Tropsch catalyst comprising in sequence: (a) contacting a particulate synthetic zeolite catalyst support having a pore size in the range of 2-10 Å with a solution of a salt of a reducible transition metal having catalytic properties effective in the conversion of CO and H₂ to hydrocarbon products consisting essentially of cobalt; (b) drying to eliminate substantially all water from the zeolite pores; (c) reducing a substantial proportion of the transition metal within the dried reducible transition metal solution-treated zeolite prepared per step (b) by exposure to the vapor of a reductant metal consisting essentially of cadmium, having a reduction potential greater than the reduction potential of said transition metal at a temperature below about 800° C.; (d) heating the product of step (c) to remove superfluous reductant metal from said product of step (c); and (e) cooling under vacuum or in an inert atmosphere to a temperature below about 200° C.

4,294,726

CATALYST FOR THE PURIFICATION OF EXHAUST GASES OF INTERNAL COMBUSTION ENGINES

Alfred Bozon, Erlensee; Edgar Koberstein, Alzenau; Hans-Dieter Pletka, Freigericht; Herbert Völker, Hanau, and Edward Lakatos, Rheinfelden-Eichsel, all of Fed. Rep. of Germany, assignors to Deutsche Gold-und Silber-Scheideanstalt vormals Roessler, Frankfurt, Fed. Rep. of Germany

Filed Feb. 11, 1980, Ser. No. 120,172

Claims priority, application Fed. Rep. of Germany, Feb. 23, 1979, 2907106

Int. Cl.³ B01J 21/06, 23/10, 23/89

U.S. Cl. 252-462

27 Claims

1. A catalyst for simultaneous oxidation of carbon monoxide and hydrocarbons and reduction of nitric oxides in exhaust gases of internal combustion engines, comprising

(a) 0.03-3% by weight of a platinum and rhodium containing active phase with a weight ratio between platinum and rhodium of 2:1-20:1;

(b) 5-15% by weight of a mixture of CeO₂ and ZrO₂, whereby these oxides are at weight ratios of 20-80:80-20;

(c) 1-10% by weight of Fe₂O₃ as well as

(d) a residual quantity up to 100% by weight of aluminum oxide of the transition series

and obtained by impregnating a carrier material of Al₂O₃ of the transition series, with an aqueous solution containing cerium, zirconium and iron salts or, mixing the carrier material with the respective oxides of cerium, zirconium and iron, tempering for 30-180 minutes in air at 500°-700° C. thereupon impregnating the carrier with an aqueous solution of a salt of platinum and a salt of rhodium, drying and subsequently treating in a gas current containing hydrogen at temperatures 250°-650° C.

4,294,727

PERFUME COMPOSITION CONTAINING 4,5-DIOXA-5-ALKYL-TRICYCLO[7.2.1.0^{2,8}

[DODEC-10-ENES AND ITS USE AS AN ODORANT
Jens Conrad, Hilden; Horst Upadek, Erkrath, and Klaus Bruns, Krefeld-Traar, all of Fed. Rep. of Germany, assignors to Henkel Kommanditgesellschaft auf Aktien, Düsseldorf-Holthausen, Fed. Rep. of Germany

Filed Apr. 21, 1980, Ser. No. 142,607


Claims priority, application Fed. Rep. of Germany, May 5, 1979, 2918168

Int. Cl.³ C11B 9/00

U.S. Cl. 252-522 R

5 Claims

1. A perfumery composition comprising from about 1 to 50 percent by weight of at least one tricyclododecene of the formula:



wherein R is a member selected from the group consisting of alkyl having from 1 to 8 carbon atoms, alkenyl having from 2 to 8 carbon atoms and alkynyl having from 2 to 8 carbon atoms, and the remainder customary constituents of perfumery compositions.

4,294,728

SHAMPOO AND/OR BUBBLE BATH COMPOSITION CONTAINING SURFACTANT AND 1,2-ALKANE DIOL

Guy Vanlerberghe, Montjay-La-Tour; Henri Sebag, Paris, and Claire Fiquet, Paris, all of France, assignors to Societe Anonyme dite: L'Oreal, Paris, France

Continuation of Ser. No. 565,130, Apr. 4, 1975, abandoned, which is a continuation of Ser. No. 227,299, Feb. 17, 1972, abandoned. This application Nov. 26, 1979, Ser. No. 97,492

Claims priority, application Luxembourg, Feb. 17, 1971, 62616; Feb. 17, 1971, 62617



Int. Cl.³ C11D 1/835; A61K 7/06

U.S. Cl. 252-542


8 Claims

1. A shampoo composition consisting essentially of an aqueous solution of




(a) 0.5-30 percent by weight based on the total weight of the composition of a surfactant selected from the group consisting of



wherein R is the hydrocarbon chain from the fatty acids of copra and n=2.5,






wherein R is the hydrocarbon radical of oleic acid and n=1,





wherein R is the alkyl from the fatty acids of tallow,




wherein R is a mixture of dodecyl to hexadecyl,









wherein R is isobutyl,








wherein R is a mixture of doecyl and tetradecyl, and n=1.5,




wherein R is the alkyl from the fatty acids of copra,



wherein R is a mixture of dodecyl and tetradecyl,



wherein R is the alkyl of the fatty acids of copra and



wherein R is the hydrocarbon chain from the fatty acids of copra and mixtures thereof; and

(b) 0.4 to 4.5 percent by weight based on the total weight of the composition of a straight chain 1,2-alkane diol selected from the group consisting of 1,2-alkane diols having 10-14 carbon atoms, and mixtures thereof.

4,294,729

COMPOSITION CONTAINING ALCOHOL AND USE THEREOF FOR EPOXY REMOVAL

Peter Bakos, Endicott; Russell E. Darrow, Newark Valley; Joseph Funari, Vestal, and Richard M. Poliak, Endwell, all of N.Y., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Dec. 17, 1979, Ser. No. 104,623

Int. Cl.³ C09D 9/00, 9/04; C11D 3/43, 3/44

U.S. Cl. 252-545

42 Claims

1. A removal composition capable of removing a cured epoxy polymer from a substrate consisting essentially of at least about 75% by weight based upon the weight of the composition of an organic cyclohydrocarbyl alcohol boiling above about 110° C., wherein said hydrocarbyl is selected from the group of aromatic ring, cycloaliphatic ring or terpene ring, and a minor amount of an ionic fluorocarbon surface agent.

11. The composition of claim 1 wherein the surface-active agent is present in an amount of at least about 0.05% by weight of the composition.

4,294,730

GELLED LUBRICANT COMPOSITION FOR RUN-FLAT TIRES COMPRISING POLYBUTENE ACRYLIC OR POLYOLEFIN GELLING AGENT AND PARTICULATE SOLID PUNCTURE SEALING MATERIAL

Michael J. Kenney, Sutton Coldfield, England, assignor to Dunlop Limited, England


Division of Ser. No. 766,679, Feb. 8, 1977. This application Oct. 2, 1979, Ser. No. 81,158

Claims priority, application United Kingdom, Feb. 13, 1976, 5674/76; Oct. 15, 1976, 42864/76

Int. Cl.³ C08L 1/02

U.S. Cl. 260—17.4 BB

14 Claims



1. A composition for application to the interior surface of the tread of a pneumatic tire to facilitate relative movement between contacting portions of the interior surface of the tire when the tire is driven deflated, said composition comprising a polybutene, an acrylic polymer or a polyolefin as gelling agent for the polybutene, and a particulate solid puncture sealing material, the particles of said puncture sealing material being of sizes distributed in a range extending from particles passing through a 7 mesh B.S. screen and retained on a 10 mesh B.S. screen to particles which will pass through a 150 micron aperture sieve, the volume of particulate solid material being at least 8% and no more than 66% of the total volume of said composition.

4,294,731

METHOD FOR DRYING ABSORBENT MODIFIED CELLULOSIC POLYMERS AND THE LIKE

Thomas C. Allen, Asheville, N.C., assignor to Akzona Incorporated, Asheville, N.C.

Continuation of Ser. No. 39,725, May 17, 1979, abandoned. This application Aug. 13, 1980, Ser. No. 177,678

Int. Cl.³ C08L 1/00

U.S. Cl. 260—17.4 CL

18 Claims

1. A method for drying chemically modified cellulose or starch materials which comprises mixing the materials with an aqueous solution of at least one amphiphilic compound, which is miscible with water nonvolatile and substantially non-reactive with said modified cellulose and thereafter evaporating the water from the materials at an elevated temperature whereby said amphiphilic compound is retained by said materials and prevents the substantial collapse of the cellulosic structure, thereby avoiding significant reduction in water absorbency or loss of aesthetics of the material.

4,294,732

RUBBER MOUNTING COMPOSITIONS

Tomio Ohyaichi, Akiyawa, and Koichi Irako, Higashimurayama, both of Japan, assignors to Bridgestone Tire Company Limited, Tokyo, Japan

Filed Aug. 14, 1980, Ser. No. 177,962

Claims priority, application Japan, Aug. 16, 1979, 54/103535; Feb. 15, 1980, 55/16541


Int. Cl.³ C08L 93/04; F16M 13/00

U.S. Cl. 260—27 BB

6 Claims

1. Rubber mounting compositions having excellent vibration isolating properties at a relatively high hardness obtained by

compounding 100 parts by weight of at least one of natural rubber, diene rubbers and diene copolymeric rubbers or a rubber blend of these rubbers and a halogenated butyl rubber, 0.5–35 parts by weight of an oil modified phenol resin selected



from the group consisting of tall oil modified phenol resin and cashew oil modified phenol resin, a modified ratio of said tall oil being 30% or more, and 2–30 parts by weight based on said resin, of a hardening agent for the phenol resin and hardening the resulting mixture.

4,294,733

ADHESIVE FOR DOUBLE GLAZING UNITS

Taieb Marzouki, and Bernd Schwisser, both of Taunus, Fed. Rep. of Germany, assignors to USM Corporation, Farmington, Conn.

Filed Apr. 2, 1979, Ser. No. 26,064

Claims priority, application United Kingdom, May 5, 1978, 13236/78

Int. Cl.³ C08L 53/00, 63/00, 91/06

U.S. Cl. 260—28.5 B

26 Claims

1. A sealant system comprising an adhesive composition and a primer composition which on combination provide a cured adhesive; said adhesive composition being a composition which is extrudable as a hot melt from about 140° C. to about 190° C. and is hardenable to yield a non-tacky, cohesive elastic mass having a moisture vapor transmission rate of not more than about 0.5 g/m²/day measured at 38° C. and comprising per hundred parts by weight of the adhesive composition, from about 5 to about 50 parts by weight of a block copolymer having two polystyrene end blocks linked to a substantially saturated polyolefin rubber midblock, from about 5 to about 50 parts by weight of an aliphatic hydrocarbon resin having a melting point not less than 60° C., from about 2 to about 40 parts by weight of a curable epoxy resin and a finely divided inorganic filler;

said primer composition comprising a heat softenable polymeric composition and an amine curing agent for the epoxy resin in the adhesive composition.

4,294,734

LOW VISCOSITY UNSATURATED POLYESTER RESINS

Giovanni Corrado, 190, Via Gentile da Mogliano, Roma; Elvio Bertotti, 45, Corso Garibaldi, Colleferro, Roma, and Bruno Sopino, 21, Via Belvedere, Colleferro, all of Italy

Filed Dec. 27, 1979, Ser. No. 107,709

Claims priority, application Italy, Dec. 29, 1978, 31405 A/78; Jun. 29, 1979, 23991 A/79

Int. Cl.³ C08L 91/00; C08G 63/52

U.S. Cl. 260—22 CB

5 Claims

1. Low viscosity unsaturated polyester resins for making glass fiber reinforced products by the injection between coupled moulds, vacuum moulding, vacuum injection moulding, low pressure pressure moulding, filament winding, application by hand and by spraying, essentially comprising:

(A) an alkyd prepared by esterification of
(a) a compound selected from the group consisting of maleic anhydride, maleic acid, fumaric acid, and mixtures thereof alone or in association with phthalic anhydride or phthalic acid, with

(b) one or more glycols essentially comprising dipropylene glycol, and at least

(B) one ethylenically unsaturated monomer copolymerizable with (A), selected from the group consisting of styrene and vinyltoluene, in an amount of 27–34% by weight of the total (A)+(B), said unsaturated polyester resins being characterized by the fact that said alkyd (A) has a molecular weight/double bond factor between 200 and 360 and has an amount of free functional groups constituted by hydroxyl groups+carboxyl groups, between 80 and 100, inclusive expressed as mg of KOH per g of alkyd (A).

4,294,735

COATING COMPOSITIONS

John Bentley, and Morice Thompson, both of Maidenhead, England, assignors to Imperial Chemical Industries Limited, London, England

Continuation-in-part of Ser. No. 896,597, Apr. 14, 1978, abandoned. This application Jan. 22, 1980, Ser. No. 114,316

Claims priority, application United Kingdom, Apr. 25, 1977, 17124/77

Int. Cl.³ C09D 3/48, 3/66, 5/02

U.S. Cl. 260—22 CB

12 Claims

1. A coating composition in which the film-forming material consists of:

(a) from 30% to 85% by volume of a disperse phase consisting of particles having a size or size distribution in the range 0.01 to 20 microns, not less than 50% by volume of those particles consisting of non-crosslinked polyester microparticles, and the disperse phase being in a state of stable dispersion maintained by means of an amphipathic dispersing agent in a substantially deflocculated, sterically stabilized state of dispersion in

(b) from 70% to 15% by volume of a liquid continuous phase in which said polyester is insoluble, the continuous phase having a viscosity of from 0.1 to 20 poise at room temperature, being capable of curing to a film-forming polymer by an autoxidative polymerisation reaction and consisting of a homogeneous mixture of:

(i) an autoxidisable derivative of a polyhydric alcohol such that in each molecule of the derivative there are present from 4 to 12 autoxidisable groupings bound by ester or ether linkages to a polyhydric alcohol residue, the said derivative having a boiling point in excess of 150° C., and

(ii) a liquid compound of viscosity less than 2 poise at room temperature which contains in the molecule at least one unsaturated grouping correlative with the autoxidisable groupings in (i) but which is not itself capable of undergoing autoxidative polymerisation, the said compound having a boiling point in excess of 150° C.; the total volume of (a) and (b) being 100% and the autoxidisable groupings constituting at least 30% of the total number of autoxidisable and coreactive groupings in the continuous phase.

4,294,736

ACCELERATED PROCESS FOR MAKING NONLINEAR POLYESTERS

William H. Burgess, III, Newark, Del., and Philip Heiberger, Broomall, Pa., assignors to E. I. Du Pont de Nemours and Company, Wilmington, Del.

Filed Mar. 24, 1980, Ser. No. 132,839

Int. Cl.³ C08G 63/48; C09D 3/64

U.S. Cl. 260—22 M

14 Claims

1. In a process for the manufacture of an alkyd resin by reaction between a polybasic acid, a polyhydric alcohol and a fatty acid under reaction temperature conditions with removal of water formed in the process, the improvement which comprises carrying out this reaction in 15–50% by weight, based on the weight of the reaction ingredients, of an inert volatile organic solvent.

4,294,737

WATER SOLUBLE EPOXY ESTER COPOLYMERS FOR INTERIOR CAN USE

Kazys Sekmakas, Palatine, and Raj Shah, Schaumburg, both of Ill., assignors to DeSoto, Inc., Des Plaines, Ill.

Continuation-in-part of Ser. No. 108,283, Dec. 28, 1979. This application May 27, 1980, Ser. No. 153,429

Int. Cl.³ C08L 35/02

U.S. Cl. 260—29.2 EP

11 Claims

1. An aqueous dispersion comprising water having dispersed therein in the form of a salt with an amine an epoxy ester copolymer comprising a polyepoxide having a 1,2-epoxy equivalency in excess of 1.0 and a molecular weight of from 350 to 8000 esterified with at least about 0.5% of the copolymer of a monoester of a saturated monohydric alcohol with a monoethylenically unsaturated dicarboxylic acid which resists homopolymerization, said polyepoxide ester being copolymerized with from 15% to 70% of monoethylenic monomers, based on the weight of the copolymer, and said monoethylenic monomers including carboxy functional monomer providing an acid number of from 20–150 in the copolymer.

4,294,738

WATER-EXTENDIBLE OLIGOMER SOLUTIONS AND COATINGS THEREFROM


Aleksander Beresiewicz, Wilmington, Del., assignor to E. I. Du Pont de Nemours and Company, Wilmington, Del.

Filed Oct. 28, 1980, Ser. No. 201,468

Int. Cl.³ C08L 61/20

U.S. Cl. 260—29.4 UA

5 Claims



1. Coating solution consisting essentially of:
(a) about 30 to 75 wt % of the following non-volatile ingredients which are present in amounts, relative to each other:
(i) 30 to 80 wt % of an oligomer having a degree of polymerization (DP) of about 10 to about 50 and a polyalkylene ether glycol having a molecular weight of about 400 to about 1300, the amount of glycol being 0 to 60 wt % of the amount of oligomer;
(ii) 2 to 12 wt % of a non-volatile, water-miscible compound selected from p-toluenesulfonic acid, trifluoromethanesulfonic acid, 5-sulfosalicylic acid, 1-naphthalene-sulfonic acid, 2,5-dimethylbenzene-sulfonic acid, the sodium salts of the above acids, the sodium salts of aliphatic monocarboxylic acids having 6 to 12 carbon atoms, ammonium benzoate, and sodium di-2-ethylhexylsulfosuccinate;
(iii) 5 to 65 wt % of an amine-aldehyde cross-linking resin; and
(iv) 0 to 10 wt % of an acidic curing catalyst;
and
(b) 25 to about 70 wt % of the following volatile ingredients which are present in amounts, relative to each other:
(i) 5 to 70 wt % of water-miscible organic solvent; and

(2) an amount of 1 to 20 percent by weight, relative to the total amount of components (1) to (2), of needle-shaped to rod-shaped crystals which are insoluble in epoxide resin, and which have a length of 0.1 to 600 μm , a thickness of 0.01 to 60 μm , a length/thickness ratio of 3 to 200, and a density of 1.3 to 3.0.

4,294,746

STABILIZERS FOR CYCLOALIPHATIC EPOXIDE CONTAINING COMPOSITIONS

Eskel B. Blair, St. Albans, and Joseph V. Koleske, Charleston, both of W. Va., assignors to Union Carbide Corporation, New York, N.Y.

Filed Jun. 17, 1980, Ser. No. 160,287

Int. Cl.³ C08G 59/68, 59/72

U.S. Cl. 260—37 EP

26 Claims

1. A stabilized curable composition comprising a cycloaliphatic epoxide, a Bronsted or Lewis acid catalyst and a stabilizing amount of a compound containing at least one nitrile and/or isocyanate group.

4,294,747

SHAPEABLE THERMOPLASTIC RESIN COMPOSITION CONTAINING CYCLIC ACETAL

Tien-Kuei Su, Spartanburg, S.C., assignor to Milliken Research Corporation, Spartanburg, S.C.

Continuation-in-part of Ser. No. 78,315, Sep. 24, 1979, abandoned. This application Aug. 18, 1980, Ser. No. 178,753

Int. Cl.³ C08K 5/06

U.S. Cl. 260—37 R

12 Claims

1. A shapeable resin composition which consists essentially of a thermoplastic, condensation polymer substantially free of olefinic unsaturation having an intrinsic viscosity of from about 0.1 to 5 measured at 25° C. in a mixture of equal parts by volume of sym-tetrachloroethane and phenol and an effective minor amount sufficient to improve crystallization properties of a cyclic acetal as a nucleating agent, said cyclic acetal being at least one member selected from the polyhydric alcohol acetals of benzaldehyde or derivatives thereof wherein the benzene ring of said benzaldehyde moiety is substituted with at least one substituent selected from the group consisting of halogen substituents, alkyl groups having one to eight carbon atoms, and alkoxy groups having one to eight carbon atoms, said polyhydric alcohols having 5 to 7 hydroxyl groups.

4,294,748

LOW VISCOSITY UNSATURATED POLYESTER RESINS

Giovanni Corrado, 190, Via Gentile da Mogliano, Roma; Elvio Bertotti, 45, Corso Garibaldi, Colferro, Roma, and Bruno Sopino, 21, Via Belvedere, Colferro, all of Italy

Filed Dec. 27, 1979, Ser. No. 107,708

Claims priority, application Italy, Dec. 29, 1978, 31404 A/78

Int. Cl.³ C08L 91/00; C08G 63/52

U.S. Cl. 260—22 CB

4 Claims

1. Low viscosity unsaturated polyester resins for making products, optionally reinforced with glass fibers, by conventional polyester resin processing techniques, essentially comprising:

- (A) an alkyl prepared by esterification of (a) a compound selected from the group consisting of maleic anhydride, maleic acid, fumaric acid, and mixtures thereof in association with isophthalic acid, with (b) one or more glycols, essentially comprising dipropylene glycol, and at least
- (B) one monomer copolymerizable with (A), selected from the group consisting of styrene, toluene, and mixtures thereof, in an amount of 25–40% by weight of the total (A)+(B), said unsaturated polyester resins being characterized in that said alkyl A has a molecular weight/double bond factor between 300 and 390 and an amount of free functional groups constituted by hydroxyl groups + carboxyl groups, of between 50 and 85, inclusive expressed as mg of KOH per g of alkyl.

4,294,749

PROCESS FOR THE COLORATION OF THERMOPLASTIC POLYMERS AND POLYCONDENSATES IN THE MASS WITH WATER-INSOLUBLE DISAZO-METHINE COMPOUNDS

Theodor Papenfuhs, Frankfurt am Main, and Wolfgang Teige, Kelkheim, both of Fed. Rep. of Germany, assignors to Hoechst Aktiengesellschaft, Fed. Rep. of Germany

Continuation of Ser. No. 2,250, Jan. 10, 1979, abandoned. This application Dec. 28, 1979, Ser. No. 107,936


Claims priority, application Fed. Rep. of Germany, Jan. 13, 1978, 2801288

Int. Cl.³ C08L 67/00; C09B 55/00

U.S. Cl. 260—40 P

5 Claims

1. In a process for spin-dyeing a water-insoluble thermoplastic polyester with a nickel-complex disazomethine coloring compound, the improvement consisting of spinning a melt of said polyester containing dissolved therein, as the coloring compound, a disazomethine compound of the formula (1)



in which

X and Y each is hydrogen, alkyl of from 1 to 4 carbon atoms, alkoxy of from 1 to 4 carbon atoms, carboxy or carbalkoxy of from 1 to 4 carbon atoms in the alkyl moiety, and Z is hydrogen, carboxy or carbalkoxy of from 1 to 4 carbon atoms in the alkyl moiety, X, Y and Z being identical or different to each other, with the proviso that either X or Y or both are not hydrogen if Z is hydrogen.

4,294,750

PYROPLASTOID PARTICLES, COMPOSITION AND METHOD OF PRODUCTION

Richard M. Klingaman, Philadelphia, Pa., and Leo C. Ehrenreich, Amherst, N.Y., assignors to Penn Virginia Corporation, Philadelphia, Pa.

Division of Ser. No. 921,523, Jul. 3, 1978, abandoned, which is a continuation of Ser. No. 786,513, Apr. 11, 1977, abandoned. This application Feb. 25, 1980, Ser. No. 124,043

Int. Cl.³ C08L 67/00

U.S. Cl. 260—40 R

28 Claims

1. A composite comprising from about 15 to 99% by volume of one or more polymeric media and about one to about 85% of particulate material composed of particles: at least about 85% of which (number basis) have a well-defined, regular, ellipsoidal shape; having a size less than about 25 μm , with at least about 90% by weight of the particles having a size less than about 15 μm ; and at least about 50% being less than about 10 μm ; the specific surface of the particles being in the range of about 0.75 to about 2.5 square meters per gram; said particles having a specific gravity of about two to three, and being composed substantially of aluminosilicate glass.

4,294,751

POLYESTER RESIN COMPOSITIONS

Hugh C. Gardner, Somerville, N.J., assignor to Union Carbide Corporation, New York, N.Y.


Continuation-in-part of Ser. No. 34,997, May 1, 1979, abandoned. This application Apr. 14, 1980, Ser. No. 135,905

Int. Cl.³ C08L 67/02

U.S. Cl. 260—400 R

7 Claims

1. A curable molding composition comprising a mixture of: (a) a polyester of the following formula



wherein n has an average value between 1.5 and 2, m is 2-n, R is the hydroxyl-free residue of a predominantly hydroxyl terminated polyester having a molecular weight not exceeding about 1500 and obtained by the condensation of a diol selected from the class consisting of 1,2-propylene glycol, 1,3-butanediol, 2,2-dimethyl-1,3-propanediol, dipropylene glycol, diethylene glycol, 2,2-dimethyl-3-hydroxypropyl 2,2-dimethyl-3-hydroxypropionate, the ethylene and propylene oxide derivatives of 2,2-bis(4-hydroxyphenyl)propane, and mixtures thereof, and mixtures of ethylene glycol and said diols, with a dicarboxylic acid or anhydride selected from the class consisting of maleic acid and anhydride, fumaric acid, ortho-phthalic acid and anhydride, isophthalic acid, terephthalic acid, carbic acid and anhydride, and mixtures thereof, (b) maleic anhydride, (c) an ethylenically unsaturated monomer which forms a homogeneous mixture with and is copolymerizable with (a) and (b) and (d) one or more reinforcing fibers having a melting point or a glass transition temperature above about 130° C. 5. A composition as in claim 1 wherein the reinforcing fiber is selected from fiberglass, carbon fibers, or polyamide fibers. 6. A composition as in claim 1 wherein the composition contains from about 15 to about 80 weight percent of the reinforcing fiber.

4,294,752

FILLED VINYL CHLORIDE POLYMER COMPOSITION

Joseph Silberberg, Brooklyn, N.Y., assignor to Stauffer Chemical Company, Westport, Conn.


Filed Jan. 14, 1980, Ser. No. 111,626

Int. Cl.³ C08K 9/04, 5/52

U.S. Cl. 260—42.14

7 Claims

1. A filled vinyl chloride polymer composition having improved processing characteristics and impact resistance comprising a vinyl chloride polymer, a filler, and an effective amount for said improved processing and impact resistance of a composition comprising a lower alkoxyalkyl acid phosphate ester having the formula



where x is an integer of from 1 to 5, m and n are either 1 or 2, with the sum of m and n being 3, R is a C₁-C₂₀ alkyl group, and R' is a C₂-C₅ alkyl group.

4,294,753

BONE MORPHOGENETIC PROTEIN PROCESS

Marshall R. Urist, Pacific Palisade, Calif., assignor to The Regents of the University of California, Calif.

Filed Aug. 4, 1980, Ser. No. 174,906

Int. Cl.³ C07G 7/00

U.S. Cl. 260—112 R

17 Claims

1. The process of separating bone morphogenetic protein (BMP) from bone tissue comprising the steps of: (a) demineralizing bone tissue; (b) treating said demineralized bone tissue under aqueous conditions with a water soluble neutral salt and a solubilizing agent for said BMP, said agent being selected from the group consisting of urea and guanidine, and thereby transforming the bone collagen to gelatin and extracting BMP into said solution of solubilizing agent; and (c) separating said solubilizing agent and neutral salt from said solution, thereby precipitating BMP in the aqueous medium.

4,294,754

RING PEPTIDE ANTIBIOTICS, PERMETIN A AND A PROCESS FOR PRODUCING THE SAME

Yoshiyuki Takahara, Tokyo; Yoshiteru Hirose, Kamakura; Yoko Takeuchi; Asao Murai, both of Tokyo; Masatsune Kainosho, Kawasaki, and Sawao Murao, Sakai, all of Japan, assignors to Ajinomoto Company, Incorporated, Tokyo, Japan

Filed Apr. 4, 1979, Ser. No. 27,029


Claims priority, application Japan, Apr. 7, 1978, 53-40999

Int. Cl.³ C07C 103/52; C12P 21/04

U.S. Cl. 260—112.5 R

1 Claim

1. A purified ring peptide antibiotic having the following empirical formula: $\text{N}\alpha\text{-(3-hydroxy-4-methyl-1-oxohexyl)-L-}\alpha\text{,}\gamma\text{-diaminobutyl-L-isoecyl-L-}\alpha\text{,}\gamma\text{-diaminobutyl-D-phenylalanyl-L-leucyl-L-}\alpha\text{,}\gamma\text{-diaminobutyl-D-valyl-L-leucyl-L-serine(9-1)-lactone;}$ and which has the following structural formula:



and wherein Dab represents 2,4-diamino butyric acid.

C₁₋₄ alkoxy, phenoxy, benzyloxy, halogen or cyano, and said cyclic moiety being unsubstituted or substituted by C₁₋₄ alkyl.

4,294,758

7-ISOCYANATO-1,4-BENZODIAZEPIN-2-ONES

Albert E. Fischli, and Andre Szente, both of Riehen, Switzerland, assignors to Hoffmann-La Roche Inc., Nutley, N.J.

Division of Ser. No. 63,288, Aug. 2, 1979, Pat. No. 4,251,443.

This application Sep. 11, 1980, Ser. No. 186,094


Claims priority, application Switzerland, Aug. 11, 1978, 8563/78; Jun. 6, 1979, 5270/79; Jul. 5, 1979, 6296/79

Int. Cl.³ C07D 243/24

U.S. Cl. 260—239.3 D

2 Claims

1. A compound of the formula



wherein R¹ represents lower alkyl, R² represents a hydrogen atom or lower alkyl, R³ represents a halogen atom and R⁴ represents a hydrogen or halogen atom.

4,294,759

STRUCTURAL ANALOGUES OF 5,6-DIHYDRO PG₁

Herman W. Smith, Kalamazoo, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.


Continuation-in-part of Ser. No. 94,572, Nov. 15, 1979, abandoned. This application Jun. 16, 1980, Ser. No. 159,738

Int. Cl.³ C07D 209/12

U.S. Cl. 260—326.27

9 Claims

1. A compound of the formula



wherein P is H, OH, or CH₂OH;

X is (CH₂)_n wherein n is 2 or 4;

Y is CH₂-CH₂, -CH=CH- (trans), or CH₂CF₂;

Z is

a. CO₂R₈ wherein R₈ is hydrogen, alkyl of one to six carbon atoms, inclusive, phenyl or a pharmacologically

acceptable metal or amine cation, phenyl, phenyl substituted with one, two or three chloro or alkyl of one to three carbon atoms, inclusive, phenyl substituted in the para position by

(i) NHCOR₁₀

(ii) COR₁₁

(iii) OCOR₁₂


(iv) CH=NNHCONH₂

wherein R₁₀ is methyl, phenyl, acetamidophenyl, benzamidophenyl or NH₂, R₁₁ is methyl, phenyl, NH₂ or methoxy; and R₁₂ is phenyl or acetamidophenyl;

b. CONR₁₃R₁₄ wherein R₁₃ and R₁₄ are the same or different and are hydrogen, alkyl of one to six carbon atoms, inclusive, phenyl or benzyl, or

c. CH₂OR₅ wherein R₅ is hydrogen, alkyl of one to six carbon atoms, inclusive, COC₆H₅ or COCH₃;

R₁ is hydrogen, alkyl of one to four carbon atoms, inclusive, cycloalkyl three to seven carbon atoms, inclusive,



wherein K_m is as defined above, the K_m of E being the same or different as the K_m of R₁.

4,294,760

PREPARATION OF

5-(ARYLCYANOHYDROXYMETHYL)-1-LOWERALKYL-PYRROLE-2-ACETIC ACID DERIVATIVES

John R. Carson, Norristown, Pa., assignor to McNeilab, Inc., Fort Washington, Pa.


Filed Apr. 17, 1980, Ser. No. 141,438

Int. Cl.³ C07D 207/337

U.S. Cl. 260—326.47

6 Claims

1. A 5-(arylcyanohydroxymethyl)-1-loweralkylpyrrole-2-acetic acid derivative having the formula:



Formula I

wherein:


R is loweralkyl;

R₁ is hydrogen or loweralkyl;

Z is CN or COO(loweralkyl); and

Ar is phenyl or phenyl substituted with a substituent selected from the group consisting of loweralkyl, halo, nitro, methylthio, trifluoromethyl, and loweralkoxy.


6. The process of preparing 5-(arylcyanohydroxymethyl)-1-loweralkylpyrrole-2-acetic acid derivatives of formula:



which comprises reacting an aroylcyanide of formula:



with a 1-loweralkylpyrrole-2-acetic acid derivative of formula:




in the presence of an acid of pK below about 2, in an inert aprotic solvent at a temperature between 0° and 40° C., wherein in the foregoing formulae:

R is loweralkyl;

R₁ is hydrogen or loweralkyl;


Z is CN OR COO(loweralkyl);

Ar is phenyl or phenyl substituted with a substituent selected from the group consisting of loweralkyl, halo, nitro, methylthio, trifluoromethyl and loweralkoxy.



in which

R⁵ represents hydrogen, methyl, chlorine, or bromine and R⁶ represents methyl, chlorine, bromine or optionally halogen-substituted phenyl, or R represents the radical



in which


R⁷ represents phenyl which is optionally substituted by halogen, C₁-C₄-alkyl, C₁-C₄-alkoxy, C₁-C₄-alkylthio, halogenomethyl, C₁-C₂-halogenoalkoxy, C₁-C₂-halogenoalkylthio, C₁-C₂-alkylenedioxy or C₁-C₂-halogenoalkylenedioxy and

R⁸ represents isopropyl or cyclopropyl,

R¹ represents hydrogen, halogen or an optionally halogen-substituted alkyl, alkenyl, alkynyl, alkoxy, alkenoxy, alkynoxy, aralkyl or aryloxy radical and

R² represents hydrogen or halogen,

comprising reacting a phosphoric acid α-cyano-benzyl ester of the formula



4,294,761

PREPARATION OF

7,12-DIOXASPIRO[5,6]DODECANE-3-ONE

John A. Hyatt, Kingsport, Tenn., assignor to Eastman Kodak Company, Rochester, N.Y.

Filed Feb. 14, 1980, Ser. No. 121,549

Int. Cl.³ C07D 321/10

U.S. Cl. 260—338

1 Claim

1. Process for the preparation of 7,12-dioxaspiro[5,6]-dodecane-3-one which comprises reacting under dehydrating conditions 1,4-cyclohexanedione and 1,4-butanediol in an inert hydrocarbon solvent in the presence of an effective amount of a ketal-forming, acid catalyst.

in which

R³ each independently is alkyl or phenyl or both together are alkanediyl,

with a carboxylic acid salt of the formula



in which

M represents one equivalent of an alkali metal or alkaline earth metal,

at a temperature of about 20° to 250° C.

4,294,762

PREPARATION OF α-CYANO-BENZYL ESTERS

Hellmut Hoffmann, Wuppertal, Fed. Rep. of Germany, assignor to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed May 1, 1980, Ser. No. 145,636


Claims priority, application Fed. Rep. of Germany, May 26, 1979, 2916224

Int. Cl.³ C07C 121/66, 121/75; C07D 317/60, 319/20

U.S. Cl. 260—340.3

9 Claims

1. A process for the preparation of an α-cyano-benzyl ester of the formula



in which

R represents a radical of the formula

4,294,763

INTERMEDIATES FOR THE PRODUCTION OF PICROPODOPHYLLIN AND RELATED COMPOUNDS AND PROCESSES FOR THE PREPARATION AND USE THEREOF

Andrew S. Kende, Pittsford, N.Y.; Dennis P. Curran, Madison, Wis.; Margaret L. King, Rochester, and Neil A. Feldstein, Westbury, both of N.Y., assignors to University of Rochester, Rochester, N.Y.


Filed Mar. 5, 1980, Ser. No. 127,436

Int. Cl.³ C07D 317/70; C07C 69/76, 49/337

U.S. Cl. 260—340.5 DP

8 Claims

1. A compound of the formula:



wherein;

- R¹ represents alkoxy or aralkoxy,
 R² represents hydrogen, alkoxy or aralkoxy,
 or R¹ and R² taken together represent the group —O—CH₂—O—,
 R³ represents hydrogen, alkyl, aralkyl, or a conventional protecting group,
 Z¹ represents a non-reacting electron withdrawing group which can be readily converted to a carboxyl group,
 Z² represents a non-reacting electron withdrawing group which can be readily converted to a carboxyl group, or hydrogen,
 R⁷ represents hydrogen, alkyl, aralkyl or acyl, and
 R⁸ and R⁹ are the same or different and represent hydrogen, alkoxy or aralkoxy.

4,294,764

N-(OPTIONALLY SUBSTITUTED 1,3-DIOXOLAN- OR DIOXAN-2-YLMETHYL)-N-ALKYL, ALKENYL, OR ALKYNYL-2,2-DICHLOROACETAMIDES

Jay K. Rinehart, Akron, Ohio, assignor to PPG Industries, Inc., Pittsburgh, Pa.


Filed Dec. 26, 1979, Ser. No. 106,434

Int. Cl.³ C07D 317/10, 317/12, 319/04

U.S. Cl. 260—340.9 R

2 Claims

1. A compound represented by the formula:



wherein:

- R is ethyl, propyl, 1-methylethyl, 2-propenyl, 2-butenyl, 2-methyl-2-propenyl, 2-propynyl, or 1,1-dimethyl-2-propynyl;
 R¹, R², R³, and R⁴ are independently hydrogen or methyl; and
 n is 0 or 1.

4,294,765

CIS-LACTONE PYRETHROID INTERMEDIATES

Petrus A. Kramer, and Pieter A. Verbrugge, both of Amsterdam, Netherlands, assignors to Shell Oil Company, Houston, Tex.

Filed Oct. 23, 1980, Ser. No. 200,227


Claims priority, application United Kingdom, Nov. 1, 1979, 37858/79

Int. Cl.³ C07D 307/93

U.S. Cl. 260—343.3 R

3 Claims

1. A cis-lactone of formula III



III

wherein X¹ and X² each represents an alkyl group containing fewer than five carbon atoms, phenyl, benzyl or phenethyl, substantially free of other stereoisomers.

4,294,766

PREPARATION OF PURE POTASSIUM RIBONATE AND RIBONOLACTONE

Wolfram Schmidt, Friedelsheim, and Joachim Paust, Neuhausen, both of Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Ludwigshafen, Fed. Rep. of Germany

Filed Dec. 6, 1979, Ser. No. 100,724

Claims priority, application Fed. Rep. of Germany, Dec. 6, 1978, 2852721

Int. Cl.³ C07D 307/32; C07C 59/105

U.S. Cl. 260—343.6

5 Claims

1. A process for the preparation of pure ribonolactone from a mixture of ribonolactone and arabinolactone, which contains 70% by weight or more of the ribonolactone, wherein the mixture is subjected to fractional crystallization from a concentrated solution in dioxane or ethylene glycol monomethyl ether at a low temperature.

2. A process for the preparation of pure potassium ribonate, comprising:

- (a) epimerizing potassium arabinonate in an aqueous solution at 130°–140° C. thereby forming a mixture of potassium ribonate and potassium arabinonate in solution;
 (b) mixing the product solution from step (a) with from 40 to 900% by wt., based on the amount of water present, of an organic solvent selected from the group consisting of C₁–C₄ alkanols, cycloaliphatic ethers, alkanediols of 2 or 3 carbon atoms which are partially etherified with methanol or ethanol and mixtures thereof and allowing most of the potassium arabinonate present to crystallize from solution;
 (c) removing the solvent from said aqueous potassium ribonate containing solution;
 (d) concentrating the aqueous solution to a salt strength from about 40 to 60% by weight;
 (e) crystallizing the potassium ribonate from the solvent free, concentrated aqueous solution at from about –2° to 10° C.

4,294,767

PROCESS FOR THE PREPARATION OF 2,5-DIMETHYL-4-HYDROXY-3(2H)-FURANONE AND ITS 2,5-DIALKYL HOMOLOGUES

Emile H. Eschinasi, Haifa, Israel, and Enrico Castelli, Leumann, Italy, assignors to Istituto per la Ricerca Scientifica e Applicata di Technologie Alimentari S.p.A., Turin, Italy


Filed Aug. 21, 1980, Ser. No. 180,179

Int. Cl.³ C07D 307/32

U.S. Cl. 260—347.8

8 Claims


1. A process comprising the steps of:
 effecting an aldol condensation reaction between a 2,5-dialkyl-dihydro-3(2H)-furanone having the formula:



I

wherein R and R' are each selected from the lower alkyl groups having from 1–3 carbon atoms, and an aldehyde having the formula R''CHO, wherein R'' is chosen from alkyl and isoalkyl groups having from 1 to 6 carbon atoms and aryl groups, under basic conditions at a temperature of from –10° C. to 100° C. to obtain the corresponding aldol compound;

dehydrating said aldol compound to form the corresponding exocyclic alkene having the formula:




wherein R, R' and R'' have the significations indicated above;

treating said exocyclic alkene (II) with ozone in the presence of a participating solvent selected from the group consisting of aliphatic alcohols and acyl compounds having from 1 to 4 carbon atoms, water, acetone and mixtures thereof, at a temperature of from –70° C. to 30° C. to obtain the corresponding hydroperoxyhemiacetal;

reducing said hydroperoxy-hemiacetal to the corresponding hemiacetal;

converting said hemiacetal to its corresponding 2,5-dialkyl-4-hydroxy-3(2H)-furanone having the formula:



III

wherein R and R' have the significations indicated above, by refluxing under acidic conditions in an inert atmosphere; and
 recovering said 2,5-dialkyl-4-hydroxy-3(2H)-furanone (III).

4,294,768

WATER-SOLUBLE ANTHRAQUINONE DYES

Jean-Marie Adam, Saint-Louis, France, assignor to Ciba-Geigy Corporation, Ardsley, N.Y.

Continuation of Ser. No. 908,495, May 23, 1978, abandoned.

This application May 9, 1980, Ser. No. 148,443


Claims priority, application Luxembourg, May 26, 1977, 77419

Int. Cl.³ C07C 143/675

U.S. Cl. 260—372

10 Claims

1. A new water-soluble anthraquinone dye which, in the form of the free acid, corresponds to the formula I



I

wherein

- R₁ represents a straight-chain or branched chain alkyl group having 4 to 8 carbon atoms,
 R₂ and R₃ independently of one another represent a straight-

chain or branched-chain alkyl group having 1 to 4 carbon atoms,

R₄ represents hydrogen, an optionally acylated amino group, or a fibre-reactive radical bonded by way of an amino group,

R₅ represents hydrogen or a straight-chain or branched-chain alkyl group having 1 to 4 carbon atoms, and the phenylene rings

A and/or B can be further substituted, with the proviso that one X of the symbols X₁ and X₂ represents the —SO₃H— group, and the other X represents hydrogen.

4,294,769

PROCESS FOR THE PREPARATION OF 1,4-DIAMINO-2,3-DICYANO-ANTHRAQUINONES

Friedrich W. Kröck, Cologne; Rütger Neeff, and Heinz Scheiter, both of Leverkusen, all of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Jul. 24, 1980, Ser. No. 171,870


Claims priority, application Fed. Rep. of Germany, Aug. 7, 1979, 2931981; Feb. 1, 1980, 3003657

Int. Cl.³ C07C 97/12

U.S. Cl. 260—378


10 Claims

1. Process for the preparation of 2,3-dicyanoanthraquinones of the formula



wherein

R denotes hydrogen, optionally substituted alkyl or optionally substituted cycloalkyl,
 by reacting sulphonic acids of the formula



or salts thereof,

wherein

R has the abovementioned meaning and
 X denotes hydrogen or the sulphonic acid group, with compounds which donate cyanide ions, characterised in that the reaction is carried out in formamide or N-methyl-formamide.

4,294,770

PROCESS FOR PREPARING A NORMAL LONG CHAIN ALKANOIC ACID

Hitoshi Takita; Yutaka Mukaida, both of Tokyo, and Satoru Enomoto, Fujisawa, all of Japan, assignors to Kureha Kagaku Kogyo Kabushiki Kaisha, Tokyo, Japan

Filed Feb. 15, 1980, Ser. No. 121,875

Claims priority, application Japan, Feb. 22, 1979, 54-19998

Int. Cl.³ C11C 1/00

U.S. Cl. 260—413

4 Claims

1. A process for preparing a normal alkanolic acid of 26 to 36 carbon atoms comprising the steps of heating a mixture of 1,1,1-trihalogeno-normalalkane of 26 to 36 carbon atoms dissolved in an organic solvent which is not completely miscible with water and an aqueous alkali solution to a temperature of 40° to 100° C. while stirring said mixture, thereby hydrolyzing

said 1,1,1-trihalogeno-normalalkane into an alkali normalalkanoate, and neutralizing said alkali normalalkanoate, thereby obtaining said normal alkanic acid of 26 to 36 carbon atoms.

4,294,771

METHOD FOR THE PRODUCTION OF METAL SOAPS
Norbert Pietralla, Weidenstrasse 33, 8034 Unterpfeffenhofen;
Valentin Ausserbauer, Zugspitzweg 29, 8015 Markt
Schwaben, and Christian Rosenthal, Bäckergasse 15, 8131
Berg, all of Fed. Rep. of Germany

Filed Mar. 27, 1980, Ser. No. 134,194

Claims priority, application Fed. Rep. of Germany, Apr. 4,
1979, 2913592

Int. Cl.³ C08H 17/36

U.S. Cl. 260—413

7 Claims

1. In a process for producing granulate metal soap or metal soap mixture in which at least one aliphatic carboxylic acid having about 8 to 22 carbon atoms is reacted with at least one soap-forming metal compound selected from the group consisting of metal oxide, metal hydroxide and metal carbonate in the presence of water at elevated temperature to provide soap, and water is subsequently removed, the improvement which comprises:

- heating a reaction mixture containing carboxylic acid and soap-forming metal compound in the presence of from 1 to 5 weight percent water based on the total weight of carboxylic acid(s) to a temperature at which the soap-forming reaction is initiated;
- permitting the soap-forming reaction to proceed under built-up overpressure without further supply of external heat;
- reducing the built-up overpressure; and,
- removing water from the reaction mixture under reduced pressure to provide granulate metal soap or metal soap mixture.

4,294,772

OXIME DERIVATIVES FOR PROTECTING PLANT CROPS

Henry Martin, Allschwil, Switzerland, assignor to Ciba-Geigy Corporation, Ardsley, N.Y.

Filed Aug. 20, 1979, Ser. No. 68,262


Claims priority, application Switzerland, Aug. 31, 1978,
9200/78

Int. Cl.³ C07F 7/22

U.S. Cl. 260—429.7

5 Claims

1. An oxime derivative of the formula



wherein

n is 0, 1 or 2,
m is 0 or 1,

Ar is alkylphenyl in which the alkyl group has from 1 to 4 carbon atoms, alkoxyphenyl in which the alkyl group has from 1 to 4 carbon atoms, halo-phenyl or naphthyl, and R₈, R₉ and R₁₀ are the same and are C₁-C₄ alkyl, benzyl or phenyl.

4,294,773

PREPARATION OF 1-HALOALKYL ISOCYANATES AND 1-ALKENYL ISOCYANATES

Karl-Heinz Koenig, Frankenthal; Karl-Heinz Feuerherd, and Heinz-Guenter Oeser, both of Ludwigshafen, all of Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Fed. Rep. of Germany

Filed Aug. 5, 1980, Ser. No. 175,591


Claims priority, application Fed. Rep. of Germany, Sep. 13,
1979, 2937006

Int. Cl.³ C07C 118/00, 119/042

U.S. Cl. 260—453 P


10 Claims

1. A process for the preparation of 1-haloalkyl isocyanates of the formula




Ia

and 1-alkenyl isocyanates of the formula




Ib

where R¹, R² and R³ may be identical or different and each is hydrogen or methyl, and X is halogen, wherein a 1-haloalkyl-carbamic acid halide of the formula



II

or a 1-haloalkyl isocyanate of the formula



III

where R¹, R², R³ and X have the above meanings, is reacted with α-pinene.

4,294,774

PREPARATION OF ORGANIC ISOCYANATES
Thomas R. Henson, and John F. Timberlake, both of Baton Rouge, La., assignors to The Dow Chemical Company, Midland, Mich.

Filed Nov. 14, 1980, Ser. No. 206,747

Int. Cl.³ C07C 118/00

U.S. Cl. 260—453 P

5 Claims

1. A process for the preparation of an organic isocyanate product comprising the step of preparing a heated solution of an alkyl carbamate in a solvent whereby the carbamate is catalytically decomposed into the corresponding organic isocyanate product and alkyl alcohol, said solvent being an N,N-dialkyl aniline compound which is characterized as being catalytic with respect to the decomposition rate of the carbamate but unreactive with respect to the organic isocyanate product.

4,294,775

RESOLUTION OF ACYLATED D,L-ALKYL SUBSTITUTED ALKANOIC ACIDS

Bonnie G. McKinnie, Baton Rouge, La., assignor to Ethyl Corporation, Richmond, Va.

Filed Mar. 3, 1980, Ser. No. 126,678

Int. Cl.³ C07C 153/07, 153/09

U.S. Cl. 260—455 R

12 Claims

1. A process for resolving a racemic mixture of 3-benzoylthio- or 3-acetylthio-2-D,L-methylpropanoic acid comprising the steps of reacting said racemic mixture with an organoamine resolving agent in a solvent having an active oxygen selected from alcohols, ketones, esters and aldehydes suitable for the particular acid at a temperature sufficient to form the 3-benzoylthio- or 3-acetylthio-2-D,L-methylpropanoic acid organoamine salt, cooling the resultant salt-containing solution at a rate sufficient to preferentially form crystalline solids containing a substantially enriched proportion of the 3-benzoylthio- or 3-acetylthio-2-D-methylpropanoic acid organoamine salt and separating said crystalline solids from the remaining salt-containing solution and recovering from the resultant crystalline solids said 3-benzoylthio- or 3-acetylthio-2-D-methylpropanoic acid.

4,294,776

PROCESS FOR THE PURIFICATION OF ORGANIC SOLUTIONS OF PERCARBOXYLIC ACIDS

Nicolas Hardy, and Georges Dancot, both of Jemeppe-sur-Sambre, Belgium, assignors to Propylox (Societe Anonyme), Brussels, Belgium



Filed May 1, 1980, Ser. No. 145,836

Claims priority, application France, May 4, 1979, 79 11234

Int. Cl.³ C07C 179/10

U.S. Cl. 260—502 R

10 Claims



1. In a process for the purification of an organic solution of a percarboxylic acid in an inert organic solvent, the solution originating from the manufacture of a percarboxylic acid by reaction of the corresponding carboxylic acid or carboxylic anhydride with hydrogen peroxide in the presence of a catalyst, under conditions sufficient to produce said percarboxylic acid, the improvement comprising subjecting the solution to be purified to a wash at a temperature of 263° to 303° K., by means

of a dilute aqueous solution containing from 35 to 60% by weight of sulphuric acid.

4,294,777

COLOR-STABILIZED AROMATIC CARBOXYLIC ACID CHLORIDES AND A PROCESS FOR THEIR PREPARATION

Walter Böckmann; Karl-August Lipper, and Friedrich Brühne, all of Krefeld, Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Oct. 17, 1979, Ser. No. 85,553


Claims priority, application Fed. Rep. of Germany, Nov. 8,
1978, 2848356

Int. Cl.³ C07C 51/64

U.S. Cl. 260—544 D

15 Claims


1. A process for color stabilizing an aromatic carboxylic acid chloride of the formula



wherein

R₁ and R₂ independently represent hydrogen and halogen, alkyl or alkoxy which comprises introducing into a composition containing said aromatic carboxylic acid chloride 0.001 to 2% by weight of a color stabilizer, based upon the amount of said carboxylic acid chloride, said color stabilizer being selected from the group consisting of


A. A stabilizer of the formula



wherein

R₃ and R₄ can be identical or different and represent hydrogen, halogen, hydroxy, alkoxy, aryloxy, aralkoxy, alkyl, aralkyl, aryl, alkenyl or mono- or di-alkylamino radicals; R₃ and R₄ together with the carbonyl group can further form a ring;


B. A stabilizer of the formula



wherein

R₅ to R₈ are identical or different and represent hydrogen, nitrile, halogen, carboxyl, carbaryloxy, carbalkoxy, alkoxy, aryloxy, acyloxy, alkyl, aralkyl or alkenyl and R₅ and R₆ and/or R₇ and R₈, or R₅ and R₇, and/or R₆ and R₈ together with the atoms to which they are linked, can further form a ring; and

C. A stabilizer of the formula



wherein

R₉ to R₁₁ can be identical or different and represent alkyl, aryl, alkoxy, or aralkoxy and X denotes phosphorus or arsenic.

4,294,778

EVAPORATIVE DISPENSER


Raymond F. DeLuca, Stamford, Conn., assignor to Georgia-Pacific Corporation, Portland, Oreg.

Filed Oct. 18, 1978, Ser. No. 952,386

Int. Cl.³ A61L 9/04

U.S. Cl. 261—30

14 Claims



1. A dispenser for emitting a vaporized material into the ambient comprising:

- a housing;
- a reservoir disposed within said housing for containing a quantity of material to be vaporized;
- inlet means for admitting air into said housing;
- outlet means for exhausting air mixed with vaporized material from said housing;
- air circulation means for effecting a flow of air through said housing from said inlet means to said outlet means;
- a supply container for replenishing material evaporated from said reservoir and replaceable when empty with a full supply container;
- means for removably supporting said supply container within said housing; and
- air channelling means carried by said supply container for channelling the air flowing through said housing across said reservoir, whereby said material is vaporized from said reservoir, entrained in said air flow and exhausted from said housing through said outlet means, said air channelling means comprising a protrusion formed on the exterior of said supply container which cooperates with said housing to define an airway for directing said air flow toward said reservoir.

4,294,779

CARBURETOR DEVICE

William J. Alape, Springfield, N.J., assignor to Aquascooter Inc., Springfield, N.J.

Filed Aug. 14, 1980, Ser. No. 178,061


Int. Cl.³ F02M 17/04

U.S. Cl. 261—35

8 Claims

1. In a compensating membrane carburetor having a fuel accumulating chamber connected through idling and high-speed jets to a Venturi, the improvement which comprises: compensating chamber means maintained naturally or artificially at atmospheric pressure; second chamber means for sealing the external face of the compensating membrane from the environment of the carburetor; first relief means partially disposed in the carburetor providing fluid communication between the compensating chamber means and the second chamber means to maintain the second chamber means at

atmospheric pressure; and second relief means disposed substantially outside of the carburetor for providing a second fluid



communication between the compensating chamber means and the second chamber means.

4,294,780

TEMPERATURE COMPENSATOR FOR A CARBURETOR CHOKE VALVE


Chester G. DuBois, Zion, and Richard P. Hulsebus, Waukegan, both of Ill., assignors to Outboard Marine Corporation

Filed Mar. 26, 1980, Ser. No. 134,065

Int. Cl.³ F02M 1/10

U.S. Cl. 261—39 B

4 Claims



4,294,791

PROCESS FOR PRODUCING THERMOPLASTIC RESIN FILM OF MARKEDLY REDUCED THICKNESS UNEVENNESS

Hiroshi Nouda, Sagamihara; Yoshiaki Tanihara, Machida; Takashi Ikeda, and Ituo Ogiuchi, both of Sagamihara, all of Japan, assignors to Teijin Limited, Osaka, Japan

Filed Dec. 26, 1979, Ser. No. 107,280

Claims priority, application Japan, Jan. 5, 1979, 54/22; Jan. 5, 1979, 54/23; Jan. 5, 1979, 54/24

Int. Cl.³ B29D 7/24

U.S. Cl. 264—210.2

4 Claims

1. In a process for producing a film of a thermoplastic resin which comprises extruding a molten thermoplastic resin in film form onto a rotating cooling drum through a die slit, cooling the film-like extrudate on the cooling drum, withdrawing the cooled film-like extrudate from the cooling drum, and then stretching it, the improvement wherein the rotation of the cooling drum is controlled such that the variation rate (%) of instantaneous rotation under no load defined by the following

$$\frac{(\text{Maximum instantaneous rotating speed}) - (\text{Minimum instantaneous rotating speed})}{\text{Average rotating speed}} \times 100$$

is less than about 1%, and wherein said withdrawal of the cooled film-like extrudate is carried out so that substantially no tension in the subsequent stretching step is exerted on the film-like extrudate on the cooling drum.

4,294,792

MOLDED PLASTIC PARTS, PARTICULARLY SPIN-CAST PLASTIC PARTS FOR EYEGLASS FRAMES


Irving J. Arons, Peabody; Richard E. Merrill, Wakefield, and Arthur P. Drennan, Brighton, all of Mass., assignors to Universal Optical Company, Inc., Providence, R.I.

Filed Oct. 27, 1978, Ser. No. 955,149

Int. Cl.³ B29C 5/04

U.S. Cl. 264—311

13 Claims



1. A spin casting process for producing a solid, substantially clear, low color thermoset plastic part which has a cross-linked structure when cured, particularly an eyeglass part, in a flexible mold from a curable liquid resin system, the flexible mold including separable mold portions at least one of which is flexible and which define at least one mold cavity when the mold portions are assembled to form the flexible mold, means being provided for rigidly holding the mold portions together as a rigid, transportable mold assembly, said process comprising the steps of:

assembling the mold portions to form the flexible mold; introducing the liquid resin system comprising an epoxy resin and a curing agent therefor which are substantially clear and of low color into the flexible mold; rotating the flexible mold in the rigid mold assembly in or on

spinning apparatus until the liquid resin system is distributed in the mold cavity but is still soft and uncured and is yet not self-supporting;

removing the rigid mold assembly including the flexible mold as a rigid unit from the spinning apparatus while the liquid resin system therein is still soft and uncured and is yet not self-supporting;

hardening the liquid resin system while in the rigid mold assembly after removal of the rigid mold assembly from the spinning apparatus to form the part; and

thereafter disassembling the rigid mold assembly and removing the part.

4,294,793

METHOD AND APPARATUS FOR MANUFACTURING A SPHERICAL HOLLOW BODY

Kazuyasu Takazawa, Tokyo, Japan, assignor to Tachikara Kabushiki Kaisha, Tokyo, Japan


Continuation of Ser. No. 894,007, Apr. 6, 1978, abandoned. This application Feb. 27, 1980, Ser. No. 125,389

Claims priority, application Japan, Nov. 15, 1977, 52-136813; Nov. 30, 1977, 52-143379

Int. Cl.³ B29C 5/04

U.S. Cl. 264—311

8 Claims



1. A method for manufacturing a spherical hollow body, comprising the steps of:

providing a plurality of individual openable spherical hollow molds each defining therein a single spherical mold cavity disposed so that its center is located substantially at the intersection of first and second orthogonal rotational axes;

mounting said molds in horizontally angularly spaced relationship on a supporting turntable rotatable about a vertical axis positioned at the center of a circular locus defined by the centers of said plurality of molds;

loading liquid thermoplastic material into each said hollow mold at an operator position;

circulating said hollow molds along a horizontal circular path by movement of said supporting turntable about said vertical axis so that the centers of said molds are maintained in a horizontal plane defined by said circular locus;

rotating each said spherical hollow mold with respect to said turntable about said first axis by clutching a rotating drive member to said spherical hollow mold through a clutch having driving and driven clutch members to effect said rotating;

simultaneously rotating each said spherical hollow mold with respect to said turntable about said second axis whenever the respective mold is rotated about said first axis by rotatably driving the mold through a clutch-free driving mechanism which is continuously driven whenever said driven clutch member is rotatably driven;

forcibly effecting said circulating of the turntable during said rotation of the molds;

discharging cooling water over the molds for effecting hardening of the thermoplastic material to provide a hardened

spherical body while continuing to rotate said molds simultaneously about said first and second orthogonal axes;

circulating a declutching member with said turntable for each said hollow spherical mold and connecting said declutching member to said clutch of the respective hollow spherical mold;

locating an elongated guide plate in fixed relation to said operator position adjacent said turntable;

riding the follower along the guide plate contoured to move the following transversely thereof to effect declutching and clutching of each said mold from the corresponding said drive member by contact of said guide plate and follower moving said declutching member with respect to said turntable as said turntable circulates each said mold respectively into and out of said operator position.

4,294,794

ETHYLENE POLYMERS OF HIGH MELT INDEX

Peter J. Lovell, Kingston, and Ian C. B. Saunders, Sarnia, both of Canada, assignors to E. I. Du Pont de Nemours and Company, Wilmington, Del.

Continuation-in-part of Ser. No. 77,717, Sep. 21, 1979, abandoned, which is a division of Ser. No. 170, Jan. 2, 1979, Pat. No. 4,192,935. This application Aug. 20, 1980, Ser. No. 179,811

Claims priority, application United Kingdom, Jan. 6, 1978, 000517/78; Mar. 21, 1978, 011206/78

Int. Cl.³ B29F 1/00

U.S. Cl. 264—328.1

7 Claims

1. In a process for the manufacture of containers having a wall thickness of less than 0.7 mm, said containers being manufactured from thermoplastic polymer by injection-moulding said polymer, the improvement comprising using as the thermoplastic polymer an ethylene polymer having a density in the range of about 0.940–0.960, a melt index in the range 100–200 and a ratio of weight-average molecular weight to number-average molecular weight of less than 5, said polymer being a copolymer of ethylene and at least one α -olefin having 4–10 carbon atoms, the α -olefin being an aliphatic hydrocarbon.

4,294,795

STABILIZED ELECTROCAST ZIRCONIA REFRACTORIES

Toshikatsu Haga; Hiroyuki Fukuda, both of Iwaki; Hiroshi Shinoda, Gifu, and Hideharu Hayakawa, Nagoya, all of Japan, assignors to Kureha Kagaku Kogyo Kabushiki Kaisha, Tokyo and NGK Insulators, Ltd., Aichi, both of Japan


Continuation-in-part of Ser. No. 45,687, Jun. 5, 1979, abandoned. This application Jan. 29, 1980, Ser. No. 116,409

Claims priority, application Japan, Jun. 12, 1978, 53-70529; Jun. 27, 1978, 53-77837

Int. Cl.³ C04B 35/48

U.S. Cl. 264—332

12 Claims



1. A method for producing a stabilized electrocast zirconia refractory having a bending strength of over 500 kg/cm² at room temperature and containing less than 1% each of TiO₂, Al₂O₃ and SiO₂, which comprises the steps of:

blending a zirconia base material and a stabilizing agent selected from the group consisting of alkaline earth metal compounds and rare earth compounds,

electrofusing the thus formed mixture thereby obtaining a stabilized molten zirconia blend, pouring said stabilized molten zirconia blend into a mold, letting said melt solidify from its lower portion by cooling forcibly the bottom of the mold, and cutting out the portion of the solidified mass where voids were formed,

thus obtaining said stabilized electrocast zirconia refractory.

4,294,796

EXTRUSION PROCESSES AND APPARATUS FOR QUENCHING TUBES

James Jack, Mistley, and Derek C. Gray, Colchester, both of England, assignors to BXL Plastics Limited, London, England

Continuation of Ser. No. 903,914, May 8, 1978, abandoned, which is a continuation of Ser. No. 514,801, Oct. 15, 1974, abandoned. This application Jan. 22, 1979, Ser. No. 5,231


The portion of the term of this patent subsequent to Aug. 24, 1993, has been disclaimed.

Claims priority, application United Kingdom, Oct. 15, 1973, 48047/73

Int. Cl.³ B29D 7/20

U.S. Cl. 264—559

13 Claims



1. In an apparatus for use in the production of a quenched tube of organic thermoplastic polymeric material comprising a downwardly operating extrusion die, a quenching bath, an assembly of calibrating discs which are disposed perpendicularly to the axis of the tube and which are mutually coaxial with each other as well as with the axis of the tube and which assembly is supported by a tubular structure attached to and passing through the mandrel of the extrusion die, means for passing quenching liquid continuously through the tubular structure into contact with the inner surface of the tube at a level below that of the lowermost of the calibrating discs, suction means for continuously drawing the same liquid upwardly as a continuous column within said tube to a selected level above the uppermost level of the assembly of calibrating discs and for removing said liquid upwardly from said selected level, means for controlling a gas pressure in the space enclosed by the die, the thermoplastic tube and the surface of the quenching liquid, a pair of nip rollers which flatten the tube across only part of its width and which enable the direction of travel of the tube to be changed from a vertically downward direction to an upward direction of travel in the quenching bath and means for taking the tube from the quenching bath to a point where it is batched or is subjected to additional treatment, the improvement whereby at least the peripheral portions of all of the calibrating discs that in operation contact the wall of the tube comprise a soft, liquid absorbent material.

8. In a process for quenching a continuously extruded tube of organic thermoplastic polymeric material which comprises the steps of leading the tube from the die of an extrusion machine vertically downward around an assembly of a plurality of calibrating discs which are positioned coaxially of said tube and perpendicular to the axis thereof into a quenching bath, while bathing the inner surface of said tube with a quenching liquid which is circulated through said tube by first forming a body of liquid in contact with said inner surface beneath said

assembly, causing the liquid in said body to rise in a continuous column within said tube to a selected level lying above the top of said assembly while remaining in contact with said inner surface between the discs of said assembly and at said selected level above said assembly, and withdrawing said liquid upwardly from a point above said assembly by suction means which maintains said liquid at said selected level, causing said tube to change its direction of travel from a vertically downward direction to an upward direction of travel in the quenching bath after it has passed through a pair of nip-rollers which flatten the tube across only part of its width, and withdrawing the tube from the quenching bath, the improvement which comprises the step of forming a lubricating layer of quenching liquid between the periphery of each disc and the wall of the tube by causing said liquid to saturate at least peripheral portions of the calibrating discs that contact the wall of the tube, which portions are made of a soft, liquid absorbent material so that a lubricating layer of quenching liquid is continuously in contact with the inner surface of said tube from a point below to a point above said discs.

4,294,797

SERVICING COMPOSITION FOR SPRAYING ON MEDICAL INSTRUMENTS

Eugen Eibofner, Biberach, Fed. Rep. of Germany, assignor to Kaltenbach & Voigt GmbH & Co., Fed. Rep. of Germany
Filed Apr. 18, 1980, Ser. No. 141,363

Claims priority, application Fed. Rep. of Germany, Apr. 24, 1979, 2916552

Int. Cl.³ A01N 31/00

U.S. Cl. 422—36

1 Claim

1. A method of lubricating and sterilizing a medical instrument comprising: spraying a servicing composition on said instrument so that the latter is wetted internally and externally with the servicing composition, said composition comprising a mixture of a lubricating oil and a propellant, and a sterilizing agent added to said mixture and comprising an isopropanol-aldehyde active substance combination in a proportion of 5 to 15% by weight of the servicing composition wherein the aldehyde is selected from the group consisting of formaldehyde and a succinic acid dialdehyde complex;

and heating the medical instrument, so as to increase the sterilizing effect of said active substance combination, until the active substance combination has vaporized.

4,294,798

SODIUM AMALGAM MONITOR

Italo A. Capuano; Patricia A. Turley, both of Orange, and Edward W. DuBord, Hamden, all of Conn., assignors to Olin Corporation, New Haven, Conn.

Filed May 31, 1979, Ser. No. 44,295

Int. Cl.³ G01N 21/00, 31/12

U.S. Cl. 422—62


10 Claims

1. An apparatus for automatically monitoring sodium concentration in a sodium-mercury amalgam, which comprises:

- a reactor;
- sample supply means positioned above said reactor, fluidly connecting said reactor with said sodium amalgam for automatically supplying a selected sample of said sodium-mercury amalgam to said reactor;
- acid supply means containing acid connected to the lower end of said reactor for automatically supplying a sufficient quantity of acid to said reactor to completely react with and remove any metallic sodium from said sample and producing a quantity of hydrogen gas proportional to the amount of sodium in said sample;
- a liquid-gas separator located at the upper end of said reactor in fluid communication with said reaction chamber, for separating liquid and gaseous reaction products produced by said reaction of said mineral acid with said sample;
- inert gas supply means containing inert gas connected to the lower end of said reactor in selective communication

with said reaction chamber, for automatically forcing said gaseous reaction products out of said reactor and into said liquid-gas separator;

- a reactor outlet for mercury removal located at the bottom of said reactor;
- detector means for determining the amount of hydrogen in the gas fraction from said liquid-gas separator and



producing a signal which is indicative of said amount of hydrogen;

- a programmer means for controlling the order of operation of said sample supply means, mineral acid supply means and inert gas supply means; and
- display means, for providing a visual indication of the amount of said quantity of hydrogen in terms of percent sodium concentration in said sample.

4,294,799

TEMPERATURE REGULATING APPARATUS


Donald E. Stephens, Palo Alto, and John T. Taylor, Santa Clara, both of Calif., assignors to Beckman Instruments, Inc., Fullerton, Calif.

Filed Apr. 24, 1980, Ser. No. 143,212

Int. Cl.³ G01N 31/22, 31/08; G01J 3/46

U.S. Cl. 422—62

13 Claims



1. An apparatus for preventing boiling of a liquid flowing through a heated reaction chamber of a liquid chromatograph instrument due to a change in the boiling point of said liquid, said apparatus comprising:

- said heated reaction chamber;
means, adjacent said reaction chamber, for exchanging heat to and from said reaction chamber;
means, associated with said flowing liquid, for monitoring a change in the ratio of reactants in said flowing liquid, said

change in the ratio of reactants resulting in a change in the boiling point of said flowing liquid;
means, defining a substantially enclosed space containing said reaction chamber and said heat exchanging means, for retaining heat;
means, responsive to said monitoring means, for introducing a coolant into said substantially enclosed space in response to a change in said boiling point; and
means defining an exit for said coolant from said enclosed space.

4,294,800

LIQUID JET RECYCLE REACTOR


Lawrence L. Tavlirides, 940 Sheridan Rd., Wilmette, Ill. 60091; Robert W. Freeman, 1539 S. Wolf Rd., Wheeling, Ill. 60090, and Alexander M. Hsia, c/o Illinois Institute of Technology, 71 E. 32nd St. - Room 110, Chicago, Ill. 60616

Filed Oct. 30, 1978, Ser. No. 955,581

Int. Cl.³ G01N 21/00; B01J 14/00

U.S. Cl. 422—68

7 Claims



1. A liquid-liquid jet reactor apparatus in which, for the investigation of interphase phenomena two immiscible or partially miscible liquids, one being represented by an aqueous phase and the other by an organic phase, are brought into mutual contact, said reactor apparatus comprising:

- a nozzle means for producing a vertical jet of the first liquid, a receiver means longitudinally spaced from and axially aligned with said nozzle means for collecting said jet, said receiver means having an inner surface and an outer surface, a tubular vessel coaxial with said nozzle means and said receiver means, the inner wall of said tubular vessel being radially spaced from said nozzle means and said receiver means so that said tubular vessel closely surrounds said nozzle means and said receiver means in sleeve-like fashion, and said tubular vessel extending both upstream of the inner end of said nozzle means and downstream of the inner end of said receiver means so as to define a narrow annular gap between said nozzle means, said liquid jet and said receiver means on the one hand and said tubular vessel on the other hand,

feed means opening into said narrow annular gap upstream of the inner end of said nozzle means for admitting the second liquid into said annular gap so as to produce, in operation, a separate steady stream of the second liquid which is confined to said annular gap and flows coaxially and cocurrently about, and in contiguity with, said jet throughout the length thereof,

outlet means located downstream of the inner end of said receiver means for removing the second liquid from the corresponding portion of the annular gap, and baffle means between said nozzle means and said vessel for directing the stream of said second liquid, one of said surfaces of said receiver means, which serves to conduct said organic phase, having a coating of hydrophobic material deposited thereon so as to be less readily wetted by said aqueous phase than by said organic phase thereby to facilitate separation of said two streams.

4,294,801

GAS COMPONENT DETECTOR

Yoshihiro Segawa, Okazaki; Minoru Ohta, Anjo, and Eturo Yasuda, Okazaki, all of Japan, assignors to Nippon Soken, Inc., Nishio, Japan


Continuation of Ser. No. 20,927, Mar. 15, 1979, abandoned. This application Jul. 15, 1980, Ser. No. 169,162

Claims priority, application Japan, Mar. 24, 1978, 53/38196

Int. Cl.³ G01N 27/04

U.S. Cl. 422—98

4 Claims



1. A gas component detector comprising:
a detector element of a metal oxide, said metal oxide exhibiting an electrical resistance value change depending upon a gas component in detected gases,
a pair of electrodes connected to said detector element for picking up an electrical signal indicative of said electrical resistance value change,
a holding body of an electrically insulating and heat-resistant metal oxide having a pair of through holes for supporting said pair of electrodes inserted therein,
a cup-shaped catalyst carrier body of a heat-resistant metal oxide having a well, said catalyst carrier body being fixed to one end of said holding body to enclose said detector element within said well, said catalyst carrier body being so porous as to allow the exhaust gases to be detected to pass therethrough,
a catalyst material carried by said catalyst carrier body for effecting oxidizing reaction of said gas component in the detected gases,
said cup-shaped catalyst carrier body having an internal surface of the well being spaced from the metal oxide of said detector element by an air gap with the catalyst thereon, which catalyst is not contacting the metal oxide,
a cover of heat resistant metal enclosing said cup shaped catalyst carrier body, said cover having opening means provided therethrough for exposing the cup shaped catalyst carrier body to the exhaust gas.

4,294,802

APPARATUS FOR PARALLEL FEEDING OF SMALL VOLUMES OF FLUIDS IN SEVERAL ESSENTIALLY PARALLEL FLEXIBLE HOSES

Henry Johansson, Törevägen 28, S-741 00 Knivsta, Sweden

Filed Feb. 14, 1980, Ser. No. 121,534

Claims priority, application Sweden, Feb. 27, 1979, 7901775


Int. Cl.³ G01N 1/14

U.S. Cl. 422—103

12 Claims

1. Apparatus for parallel feeding of small volumes of liquids in essentially parallel flexible hoses comprising a surface over which said hoses extend during operation of said apparatus, a pumping bar extending substantially perpendicular to said surface, at least one hose clamp extending substantially perpendicular to said surface, an eccentric coupled to said pumping bar, a shaft coupled to said hose clamp, a support coupled to said eccentric and said shaft for causing said eccentric and shaft to synchronously rotate causing said pumping bar to reciprocate in a pendulum motion towards and away from said surface for

subjecting said hoses to a pumping action and said hose clamp to reciprocate towards and away from said surface for clamp-



ing said hoses together at predetermined times during the pumping cycle.

4,294,803

APPARATUS FOR PREVENTING COKING IN FLUIDIZED BED REACTOR FOR CRACKING HEAVY HYDROCARBON OIL

Seiichi Uchida, Urawa; Yoshihito Satomi, Kurashiki; Norihiro Kiuchi, Hachioji; Takeo Yamagata, Takahagi; Susumu Yoshiooka, Hitachi; Tomohiko Miyamoto, Takahagi, and Jinichi Tomuro, Hitachi, all of Japan, assignors to Hitachi, Ltd. and Nippon Mining Co., Ltd., both of Tokyo, Japan


Division of Ser. No. 946,426, Sep. 27, 1978, Pat. No. 4,220,518. This application Aug. 21, 1979, Ser. No. 68,452

Claims priority, application Japan, Sep. 28, 1977, 52-115538; Sep. 28, 1977, 52-115539; Nov. 7, 1977, 52-132478

Int. Cl.³ G05D 16/00, 7/00; F27B 15/08

U.S. Cl. 422-111

10 Claims



1. In an apparatus, for cracking heavy hydrocarbon oil through a fluidized bed, comprising a reactor column of fluidized bed type for cracking heavy hydrocarbon oil through contact with fluidization particles, provided with a means for supplying a fluidization gas at its lower part and an outlet port for discharging a cracked effluent gas at its top, and a regenerator column of fluidized bed type for regenerating the fluidization particles, the reactor column provided with a means for supplying a fluidized gas at its lower part and an outlet port for gas at its top, and the reactor column and the regenerator column communicating with each other,

an apparatus which comprises: a fluidization particle vessel having an inlet for fluidization particles at its top, and a lower part throttled to a smaller cross-sectional area than the top; a lift gas supply line means moving a stream of lift gas through said lift gas supply line and communicating with the bottom of the particle vessel to receive fluidization particles at a controlled rate determined by the throttled part into said lift gas supply line and entrain them in the lift gas moving in said lift gas supply line; said lift gas supply line having one end open towards one of the outlet ports for discharging the entrained fluidization particles and lift gas above the associated fluidized bed; a control gas supply line means conducting control gas into the

throttled lower part of the particle vessel; and means selectively controlling the control gas conducted through said control gas supply line into said throttled lower part to correspondingly control the movement of the fluidization particles from the particle vessel to the lift gas supply line.

4,294,804

PRESSURE RESPONSIVE CONDITIONING CONTROL GAS STERILIZATION


Walter J. Baran, Erie, Pa., assignor to American Sterilizer Company, Erie, Pa.

Division of Ser. No. 9,818, Feb. 6, 1979, Pat. No. 4,241,010. This application Jun. 25, 1980, Ser. No. 162,812

Int. Cl.³ A61L 2/20, 2/24

U.S. Cl. 422-112

3 Claims



1. Apparatus for conditioning goods for sterilization and sterilizing goods with a chemically biocidal gas, the conditioning including heating the goods to a selected temperature related to the desired sterilization temperature and moistening the goods to a desired level for such biocidal gas sterilization, with conditioning steps being free of temperature and moisture measurement requirement levels in the goods and chamber, comprising in combination

a sealable chamber capable of operating at pressures other than atmospheric,

means providing access for loading goods to be sterilized into the chamber and closing the chamber to permit operation at other than atmospheric pressure,

means for evacuating the chamber,

means for sensing pressure levels in the chamber,

means for injecting a conditioning vapor comprising steam into the chamber,

valve means for controlling injection of conditioning vapor into the chamber, said valve means being free of flow rate control adjustment capabilities,

means for introducing a chemically biocidal gas, and

control means electrically interconnected to activate and deactivate the means for evacuating the chamber, the valve means for controlling injection of conditioning vapor, and the means for introducing a biocidal gas,

such control means being electrically connected to the means for sensing pressure level within the chamber and including timer means and sequencing means to evacuate the chamber to a preselected subatmospheric level responsive to such pressure level sensing means, then

inject conditioning vapor to raise chamber pressure to a higher preselected subatmospheric pressure level responsive to such pressure level sensing means, then

hold the chamber in sealed condition with evacuation and vapor injection interrupted for a predetermined time responsive to the timer means, then

repeat such sequence of evacuating the chamber, injecting

conditioning vapor, and holding the chamber in sealed condition, then
add biocidal gas to raise chamber pressure to a desired pressure above atmospheric pressure responsive to such pressure sensing means, and
hold such biocidal gas and conditioning vapor in the chamber a predetermined time responsive to the timer means to complete desired sterilization.

4,294,805

METHOD OF LEACHING THE CONTENTS OF A CAN

Thomas D. Hodgson, and Tony W. J. Jordan, both of Abingdon, England, assignors to United Kingdom Atomic Energy Authority, London, England


Filed Aug. 8, 1979, Ser. No. 64,911

Claims priority, application United Kingdom, Aug. 9, 1978, 32747/78

Int. Cl.³ C01G 43/00

U.S. Cl. 423-4

7 Claims



1. A method of leaching material from a composite body with a liquid dissolvent which evolves a gas on contacting the material, the composite body comprising the material to be leached located in a tubular can, said can being insoluble in the dissolvent and open at one end thereof to expose said material, the method comprising placing the body in a vessel containing a said liquid dissolvent for the material and heating the vessel to a temperature near to the boiling point of the dissolvent, and then subjecting the vessel to a plurality of pressure cycles, each pressure cycle comprising, firstly, reducing the pressure inside the vessel using a vacuum source connected to the vessel so as to cause boiling of the dissolvent, and subsequently, introducing a gas into the vessel through a vent means of the vessel so as to increase the pressure inside the vessel from the reduced pressure therein to inhibit the boiling of the dissolvent, thereby to displace from partially enclosed cavities in said body during the reduced pressure portions of the cycles evolved gas entrapped in said cavities.

7. A method of leaching irradiated nuclear material and fission products from at least one length cut from an irradiated nuclear fuel element said fuel element comprising said nuclear material clad with a metal can, the method comprising placing the cut length of the fuel element into a vessel containing nitric acid and heating the vessel near to the boiling point of the nitric acid, and subjecting the vessel to a plurality of pressure cycles, each pressure cycle comprising, firstly, reducing the pressure inside the vessel using a vacuum source connected to the vessel so as to cause boiling of the nitric acid, and subsequently, introducing a gas into the vessel through a vent means of the vessel so as to increase the pressure inside the vessel from the reduced pressure therein to inhibit the boiling of the nitric acid, thereby to displace from partially enclosed cavities in the cut length during the reduced pressure portions of the cycles gas evolved from contact of the nitric acid with the nuclear material.

4,294,806

METHOD FOR PREVENTING THE WEAR OF A MONOLITHIC CATALYST BY DUSTS


Kazunobu Abe, Izumi; Shoichi Tamura, Sakai, and Tadao Nakatsuji, Matsubara, all of Japan, assignors to Sakai Chemical Industry Co., Ltd., Osaka, Japan

Continuation-in-part of Ser. No. 12,196, Feb. 14, 1979, abandoned, which is a continuation-in-part of Ser. No. 974,519, Dec. 29, 1978, abandoned. This application Nov. 21, 1979, Ser. No. 96,561

Int. Cl.³ B01D 53/36

U.S. Cl. 423-239

12 Claims



1. In a method for the catalytic reduction of nitrogen oxides contained in waste gases together with dusts therein in the presence of ammonia as a reducing agent so as to convert said nitrogen oxides to nitrogen and water by use of a monolithic ceramic honeycomb catalyst having at least one passage therethrough parallel to the direction of flow of gas for allowing the gas to pass therethrough and comprising a support of at least one member selected from the group consisting of alumina and titanium dioxide and a catalytically active ingredient uniformly dispersed in the support, the ingredient being of at least one oxide of a base metal selected from the group consisting of Cu, Ni, Co, V and W, the improvement in which the support and the active ingredient are not sintered but calcined throughout the structure so as to be substantially porous throughout the structure but wherein the honeycomb catalyst is sintered only at its front inlet so as to render it substantially non-porous, thereby making the honeycomb catalyst more wear-resistant as a whole.

4,294,807

SYSTEM FOR REMOVING SOLIDS FROM A USED LIME OR LIMESTONE SLURRY SCRUBBING LIQUOR IN FLUE GAS DESULFURIZATION

Alan D. Randolph, Tucson, Ariz., assignor to Electric Power Research Institute, Inc., Palo Alto, Calif. and The Arizona Board of Regents, The University of Arizona, Tucson, Ariz.

Filed Nov. 10, 1980, Ser. No. 205,702

Int. Cl.³ B01D 9/02

U.S. Cl. 423-242

11 Claims

1. In a flue gas desulfurization process using a lime or limestone slurry scrubbing liquor in which used liquor including crystallizable solids comprising calcium sulfite or sulfate, in hydrated or unhydrated form, is produced, wherein precipitated particles are removed from the used scrubbing liquor, the steps of

- (a) feeding the used scrubbing liquor to an agitated crystallization zone and agitating the liquor therein, thereby growing crystals from said crystallizable solids,
- (b) directing part of the used scrubbing liquor from the agitated crystallization zone to an inlet in the lower portion of a quiescent crystallization zone, and settling said crystals therein back into the agitated crystallization zone,
- (c) removing an underflow stream of crystal-containing liquor from the agitated crystallization zone and separate overflow stream of crystal-containing liquor from an upper part of the quiescent crystallization zone, the ratio

of said underflow stream to said overflow stream being adjusted to cause crystals above a predetermined size to settle from the quiescent zone back into said agitated zone, rather than being carried out in the overflow stream, to promote secondary crystal nucleation.

4,294,808

PRODUCTION OF ANTICORROSIVE PIGMENTS CONTAINING PHOSPHORUS

Horst-Dieter Wasel-Nielsen; Renate Adrian; Herbert Panter, all of Hürth; Gero Heymer, Erfstadt; Alexander Maurer, and Raban von Schenck, both of Hürth, all of Fed. Rep. of Germany, assignors to Hoechst Aktiengesellschaft, Fed. Rep. of Germany

Filed Sep. 17, 1979, Ser. No. 76,307

Claims priority, application Fed. Rep. of Germany, Sep. 20, 1978, 2840820

Int. Cl.³ C01B 25/26, 25/32, 25/36, 25/37

U.S. Cl. 423—305

8 Claims

1. In a process for making phosphorus-containing anticorrosive pigments having a size of at most 20 microns by reacting at least one compound of the metals selected from the group consisting of magnesium, calcium, strontium, barium, zinc, aluminum, iron, chromium and manganese with an oxygen acid of phosphorus or an alkali metal or ammonium salt of said acid at temperatures within the range 10° to 100° C., the improvement which comprises: intimately mixing and thereby reacting an aqueous suspension or solution of the reactants inside a dispersing means rotating at a speed of 3000 to 10,000 rpm, separating and drying precipitated pigment, the pigment consisting to an extent of at least 90% of particles with a size between 0.05 and 8 microns.

4,294,809

AERATION OF PHOSPHORIC ACID

Richard N. Hill, Lakeland, Fla., assignor to W. R. Grace & Co., New York, N.Y.

Continuation-in-part of Ser. No. 54,449, Jul. 3, 1979, which is a continuation-in-part of Ser. No. 951,804, Oct. 16, 1978, abandoned, which is a continuation of Ser. No. 767,175, Feb. 9, 1977, abandoned, which is a division of Ser. No. 683,756, May 6, 1976, abandoned, said Ser. No. 54,449, is a continuation-in-part of Ser. No. 883,381, Mar. 6, 1978, Pat. No. 4,164,550, said Ser. No. 883,381, and Ser. No. 951,804, each is a continuation-in-part of Ser. No. 812,319, Jul. 1, 1977, Pat. No. 4,110,422, which is a continuation-in-part of Ser. No. 683,756. This application Sep. 29, 1980, Ser. No. 191,940

Int. Cl.³ C01B 25/16

U.S. Cl. 423—321 R

4 Claims

1. In the method of making wet process phosphoric acid analyzing about 56–63% P₂O₅ prepared by steps including (a) clarifying crude feed acid in a clarifier, said feed acid analyzing about 26–36% P₂O₅, and containing Fe⁺⁺ and Fe⁺⁺⁺, the weight ratio of Fe as Fe₂O₃:P₂O₅ being 0.04–0.065:1; (b) treating the clarified acid with aluminum silicate; (c) concentrating the treated acid to about 46–52% P₂O₅; (d) settling solids in the concentrated acid in a crystallizer-settler providing an overflow and an underflow; (e) further concentrating the overflow in (d) to about 56–63% P₂O₅;

the improvement comprising aerating with strong agitation the clarified acid resulting from step (a) to oxidize at least some Fe⁺⁺ to Fe⁺⁺⁺, whereby post-precipitation characteristics of the acid are improved.

4,294,810

ALKALI CALCIUM SILICATES AND PROCESS FOR PREPARATION THEREOF

Genji Taga, Shinnanyo; Teruo Oikawa, Kudamatsu, and Yoshiaki Watanabe, Hikari, all of Japan, assignors to Tokuyama Soda Kabushiki Kaisha, Yamaguchi, Japan


Division of Ser. No. 54,810, Jul. 5, 1979. This application Feb. 27, 1980, Ser. No. 125,186

Claims priority, application Japan, Jul. 7, 1978, 53-81935; Jul. 11, 1978, 53-83565; Aug. 7, 1978, 53-95397; Sep. 21, 1978, 53-115131; Dec. 5, 1978, 53-158639

Int. Cl.³ C01B 33/24

U.S. Cl. 423—331

23 Claims



1. An alkali calcium silicate having an X-ray diffraction pattern having diffraction peaks at spacings (d) of 13.0–13.4 Å, 6.7 Å and 3.1 Å said silicate having a composition represented by the following formula:



wherein a is zero or a number larger than 0, b is zero or a number larger than 0, c is a number of from 7 to 9, d is a number of from 30 to 34 and e is a number of from 0 to 30, with the proviso that the sum of a and b is larger than 0 but smaller than or equal to 8.

8. A process for the preparation of alkali calcium silicates, which comprises subjecting an aqueous suspension of an alkali component, a calcium component and a silicon dioxide component to hydrothermal reaction under pressure at a temperature of 150° to 250° C., wherein the silicon dioxide component is a soluble silicon dioxide component and the hydrothermal reaction is carried out under conditions satisfying the requirement defined by the following formula combination (H):

$$0.00533t + 0.4 \leq T \leq 0.008t + 0.8 \quad (H)$$

$$0.0002t - 0.025 < U \leq 0.04$$

wherein T stands for the starting material charge coefficient, said coefficient T being represented by the following formula (A):

$$T = \frac{9Y - 32Z}{9X - 12Z} \quad (A)$$

wherein X stands for the amount (moles) of the alkali component as R₂O contained in the aqueous suspension, in which R is an alkali metal selected from the group consisting of sodium and potassium, Y stands for the amount (moles) of the silicon dioxide component as SiO₂ contained in the aqueous suspension and Z stands for the amount (moles) of the calcium component as CaO contained in the aqueous suspension, when an alkali metal salt is formed as a by-product by the reaction, or the following formula (B):

$$T = \frac{9Y - 32Z}{9X - 3Z} \quad (B)$$

wherein X, Y and Z are as defined above, when an alkali metal salt is not formed as a by-product by the reaction, U stands for the alkalinity coefficient, said coefficient U represented by the following formula (C):

$$U = \frac{3X - 4Z}{3S} \quad (C)$$

wherein X and Z are as defined above and S stands for the amount (moles) of H₂O contained in the aqueous suspension, when an alkali metal salt is formed as a by-product by the reaction, or the following formula (D):

$$U = \frac{3X - Z}{3S} \quad (D)$$

wherein X, Z and S are as defined above, when an alkali metal salt is not formed as a by-product by the reaction, and t stands for the hydrothermal reaction temperature (°C.), whereby an alkali calcium silicate of the type 13 A is formed.

4,294,811

PROCESS FOR MANUFACTURING SI USEFUL FOR SEMICONDUCTOR COMPONENTS FROM QUARTZ SAND

Hubert Aulich, Munich, and Josef Grabmaier, Berg, both of Fed. Rep. of Germany, assignors to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany

Filed Oct. 6, 1980, Ser. No. 194,336

Claims priority, application Fed. Rep. of Germany, Nov. 8, 1979, 2945141

Int. Cl.³ C01B 33/02

U.S. Cl. 423—350

18 Claims

1. In a method of producing silicon which is useful for fabrication of semiconductor components, such as solar cells, wherein quartz sand is utilized as a starting material and silicon is obtained through reduction of silicon dioxide in an electrical arc process, the improvement comprising:

- admixing select amounts of quartz sand with suitable amounts of glass-forming materials and melting such admixture and converting it into glass;
- annealing the so-obtained glass at an elevated temperature below the temperature utilized to form such glass to that a phase-separation occurs comprised of a silicon dioxide-rich phase and an impurity-rich phase;
- subjecting the so-annealed glass to a leaching-out process with an acid and/or lye so that the impurity-rich phase is extracted; and
- admixing the remaining silicon dioxide-rich glass with a carbon-containing compound and reducing such glass to silicon in an electrical arc.

4,294,812

RECOVERY OF AMMONIA FROM AQUEOUS STREAMS


Robert A. Oler, Wilmington, N.C., assignor to General Electric Company, San Jose, Calif.

Continuation of Ser. No. 909,674, May 25, 1978, abandoned. This application Sep. 7, 1979, Ser. No. 73,316

Int. Cl.³ C01C 1/02

U.S. Cl. 423—357

21 Claims



8. A method of recovering ammonia from a continuously circulating aqueous stream containing an ammonium com-

pound capable of reacting with lime to form free ammonia in solution, which consists essentially of the steps of:

- contacting the continuously circulating aqueous stream with a lime slurry to form a mixture containing free ammonia in solution and continuing the circulating of the mixture to maintain solids thereof in suspension;
- contacting the mixture of step (a) while continuously circulating with the vapor stream from step (c) and steam to form a heated liquid mixture and an ammonia-rich product vapor;
- contacting a portion of the continuously circulating heated liquid mixture from step (b) with steam in a stripping zone to form a liquid waste stream and a vapor stream containing free ammonia and steam; and
- recovering ammonia-rich product vapor.

4,294,813

PROCESS FOR FORMING CALCIUM NITRITE


James M. Gaidis, Ellicott City, and Arnold M. Rosenberg, Potomac, both of Md., assignors to W. R. Grace & Co., New York, N.Y.

Filed Sep. 23, 1980, Ser. No. 189,993

Int. Cl.³ C01B 21/20; C01D 9/00

U.S. Cl. 423—385

13 Claims



12. A method for preparing aqueous solutions of calcium nitrite comprising the successive steps of:

- forming an aqueous solution of sodium nitrite and calcium nitrate;
- cooling said solution to insolubilize sodium nitrate and form an aqueous solution of calcium nitrite; and
- separating the aqueous calcium nitrite solution from the insoluble sodium nitrate.

4,294,814

CARBON BLACK PROCESS AND REACTOR

Paul J. Cheng, Bartlesville, Okla., assignor to Phillips Petroleum Company, Bartlesville, Okla.

Continuation-in-part of Ser. No. 895,430, Apr. 12, 1978, Pat. No. 4,224,284, which is a continuation-in-part of Ser. No. 498,776, Aug. 19, 1974, abandoned. This application Mar. 28, 1980, Ser. No. 134,856

Int. Cl.³ C09C 1/50


U.S. Cl. 423—457

9 Claims

1. In a process for the production of carbon black by the pyrolytical decomposition of hydrocarbons comprising the steps

- introducing hydrocarbons along the axis of a tubularly shaped longitudinal reactor having an upstream confining wall,
- introducing hot combustion gases of nonstoichiometric composition tangentially into said reactor at a location close to said upstream confining wall to form a vortex of hot combustion gases spinning around the axial hydrocarbon stream,

- (c) withdrawing carbon black containing smoke from the downward end of said reactor, the improvement comprising
- (d) introducing hot combustion gases of nonstoichiometric composition opposite to the nonstoichiometric composition of the tangentially introduced hot combustion gases radially inwardly toward its longitudinal axis into the reactor from orifices located radially at a distance from the axially introduced hydrocarbon stream and located axially at a distance from said upstream confining wall and located within said vortex, the nonstoichiometric compositions of said tangentially introduced hot combustion gases as well as of said radially inwardly introduced hot combustion gases being such that said radially inwardly introduced hot combustion gases mixed with a portion of the tangentially introduced hot combustion gases form a stoichiometric hot combustion gas mixture, and
- (e) contacting said stoichiometric hot combustion gas mixture with said axially introduced hydrocarbon stream to effect pyrolytical decomposition thereof.
4. A carbon black reactor comprising:
- (a) a housing with tubular-shaped interior from heat resistant




- material having an upstream confining wall arranged essentially orthogonally to the longitudinal axis of the reactor,
- (b) first conduit means for axial introduction of hydrocarbon feed into said housing, said first conduit means being arranged extending axially through said upstream confining wall,
- (c) a cylindrical portion of said housing attached to said upstream confining wall,
- (d) second conduit means for tangential introduction of combustion gases into said housing, said second conduit means being arranged extending tangentially through said cylindrical portion of the housing close to said confining wall,
- (e) third conduit means for radially inward introduction of a gas into said housing, said third conduit means comprising a plurality of conduits extending into the interior of the reactor and ending in openings facing the stream of axially introduced hydrocarbon feed, said conduits extending axially through said confining wall and end turned 90° from the axial direction toward the radial direction,
- (f) means to withdraw the carbon black smoke from the downstream end of the reactor.

4,294,815
PROCESS OF PRODUCING CHLORINE DIOXIDE AND, IF DESIRED, CHLORINE
 Karl Lohrberg, Heusenstamm; Siegfried Bielz, Frankfurt am Main, and Paul Janisch, Steinau, all of Fed. Rep. of Germany, assignors to Metallgesellschaft Aktiengesellschaft, Frankfurt, Fed. Rep. of Germany

Filed Nov. 13, 1979, Ser. No. 93,708
 Claims priority, application Fed. Rep. of Germany, Nov. 14, 1978, 2849250

Int. Cl.³ C01B 11/02
 U.S. Cl. 423—478 13 Claims



1. A process for producing ClO₂ which comprises
- (A) feeding aqueous NaCl into an electrolyte membrane cell and therein electrolyzing the same to obtain H₂ Cl₂, NACH
- (B) reacting the H₂ and Cl₂ formed in step A to form HCl;
- (C) feeding HCl from step B into a chlorate reaction zone;
- (D) feeding NaClO₃ into said chlorate reaction zone, with NaClO₃ being obtained as a product of an electrolysis of NaCl;
- (E) reacting sodium chlorate with hydrochloric acid in said chlorate reaction zone to form chlorine dioxide chlorine and sodium chloride;
- (F) separating said ClO₂ and Cl₂ from NaCl and electrolyzing said NaCl in an electrolysis cell to obtain NaClO₃ and recycling the same to step D.


4,294,816
PROCESS FOR PRODUCING HYDROGEN FLUORIDE FROM FLUORINE CONTAINING MATERIALS BY CONTINUOUS PYROHYDROLYSIS
 Jorg Kruger, Schwandorf; Roland Thome, Bonn; Dieter Moritz, Lunen; Hubert Bings, Lunen, and Herbert Losert, Lunen, all of Fed. Rep. of Germany, assignors to Vereinigte Aluminium-Werke Aktiengesellschaft, Bonn, Fed. Rep. of Germany

Filed Oct. 17, 1980, Ser. No. 198,217
 Claims priority, application Fed. Rep. of Germany, Oct. 20, 1979, 2942439

Int. Cl.³ C01B 7/19
 U.S. Cl. 423—484 9 Claims

1. A process for producing hydrogen fluoride from fluorine containing materials which comprises introducing a quantity of a solid material containing a mixture of fluorine and carbon into a first zone of a rotating kiln,
- heating said material in said first zone with a countercurrent atmosphere containing oxygen and steam,
- conducting said material from said first zone to a second zone in said kiln,
- injecting oxygen into said second zone, heating said material to a temperature of between 1200° and 1800° C. in said second zone,
- conducting said material from said second zone to a third zone in said kiln,
- said third zone having an atmosphere comprising steam,

injecting said steam into said kiln to create a turbulent flow of steam and oxygen in said kiln,



and continuously recovering said hydrogen fluoride from said third zone.

4,294,817
METHOD OF FLUORO IMMUNOASSAY
 Michael W. Burgett, El Granada, and Richard A. Harte, Redwood City, both of Calif., assignors to International Diagnostic Technology, Inc., Santa Clara, Calif.

Continuation-in-part of Ser. No. 854,613, Nov. 25, 1977, abandoned. This application Sep. 18, 1978, Ser. No. 943,314
 Int. Cl.³ G01N 33/58, 33/54, 21/25, 1/28

U.S. Cl. 424—8 14 Claims

1. An immunofluorescence method of testing for the presence of an analyte where a test sample may contain an unknown amount of an interfering material which comprises preparing a first surface having bound thereto an antigen for the analyte with which the interfering material may interfere, preparing a second surface which is adapted to bind a broad spectrum of protein materials including said interfering materials but which does not bind any substantial amount of said analyte, performing an immunoassay of an unknown serum sample with said first and second surfaces by (a) immersing said first surface in an aliquot of said unknown serum, (b) immersing said first surface in an aliquot of a fluorescent labeled material adapted to bind to antibodies in the serum sample, (c) immersing the second surface in an aliquot of said unknown serum, (d) immersing said second surface in an aliquot of a fluorescent labeled material adapted to bind to antibodies in the serum sample, and thereafter measuring the difference in the amount of labeled material on the first and second surfaces.

2. An immunoassay method for the detection of an analyte in serum in the presence of interfering sera constituents comprising:

- (a) providing two test surfaces each nonreactive with the analyte but capable of binding a broad spectrum of serum components;
- (b) binding an antigen for the analyte on only one of the surfaces;
- (c) moving the test surfaces through an aliquot of serum to be tested and a fluorescent labeled material;
- (d) measuring quantitatively the fluorescence of each surface and subtracting the measurement of one of the surfaces from the other surface measurement to provide an analyte specific fluorescent measurement.

14. The method of claim 2 in which the test surfaces are mounted on a single sampler.

4,294,818
METHODS AND MATERIALS FOR DETECTION OF MULTIPLE SCLEROSIS
 John McMichael, Cambridge Springs, Pa.; Ellis L. Kline, Pendleton, S.C.; and James G. Spaulding, Saegertown, Pa., assignors to University Patents, Inc., Norwalk, Conn.

Filed Jul. 30, 1979, Ser. No. 61,759
 Int. Cl.³ G01N 33/48, 33/50, 33/54

U.S. Cl. 424—12 6 Claims

1. A diagnostic reagent for use in serological determination of the presence of a multiple sclerosis disease state in a human patient, said reagent comprising heterologous species antibodies obtained by means of a heterologous species immune response to exposure to components of a homogenate of lymphocytes of a human patient suffering from multiple sclerosis.

4,294,819
ALKALINE ANALGESIC CAPSULE
 Thomas M. Tencza, Wallington, N.J., assignor to Bristol-Myers Company, New York, N.Y.

Filed Aug. 18, 1980, Ser. No. 179,191
 Int. Cl.³ A61K 9/48, 31/60, 33/10, 33/12

U.S. Cl. 424—14 13 Claims

1. As a unit dosage form a capsule having incorporated therein an alkaline tablet having a fast disintegration rate and an aspirin mixture; said aspirin mixture being present in said capsule as a powder or granulated material; said aspirin being present in said capsule at a level in the range of from about 160 mg. to about 500 mg. per capsule; and the quantity of alkaline material contained in said capsule being between about 30% to about 100% by weight based on the total weight of aspirin contained in the capsule.

4,294,820
POLYMERIC DIFFUSION MATRIX CONTAINING PHENYLEPHRINE
 Alec D. Keith, Miami, Fla., and Wallace Snipes, State College, Pa., assignors to Key Pharmaceuticals, Inc., Miami, Fla.

Continuation-in-part of Ser. No. 109,242, Jan. 3, 1980, which is a continuation-in-part of Ser. No. 2,565, Jan. 11, 1979, abandoned, and Ser. No. 47,084, Jun. 11, 1979, abandoned. This application Jul. 9, 1980, Ser. No. 167,101

Claims priority, application Japan, Aug. 14, 1979, 54-103459
 Int. Cl.³ A61L 15/03; A61K 31/79

U.S. Cl. 424—28 10 Claims

1. A self-supporting polymeric diffusion matrix for the sustained release of phenylephrine in order to transdermally deliver said phenylephrine to a patient and provide said patient with a decongestant effect, said matrix comprising from about 2 to about 60% of a polar plasticizer, from about 6 to about 20% by weight polyvinylalcohol, from about 2 to 10% by weight polyvinylpyrrolidone, and a pharmaceutically effective amount of phenylephrine to provide a sustained release of said phenylephrine over a prolonged period.

4,294,821
ODOR ABSORBING COMPOSITIONS
 Phillip J. Neumiller, Racine County, Wis., assignor to S. C. Johnson & Son, Inc., Racine, Wis.

Filed Dec. 15, 1980, Ser. No. 216,411
 Int. Cl.³ A61L 13/00, 9/01

U.S. Cl. 424—45 10 Claims

1. An odor absorbing composition comprising:
- (a) from about 0.5 to 45% by weight of diethylene glycol;
- (b) from about 0.5 to 45% by weight of propylene glycol;
- (c) from about 0.5 to 30% by weight triethylene glycol;
- (d) from about 1 to 50% by weight of glycerine;
- (e) from about 0.1 to 20% by weight of a diethanol amide of a C₁₆ to C₁₈ unsaturated fatty acid, and
- (f) from about 0.05 to 5% by weight of an unsaturated fatty acid.

10. A solid air treating composition which comprises an

absorbent substrate containing from 10 to 200% by weight based on the weight of the substrate of the composition of claim 1.

4,294,822

5-AMINOALKYL-4,4,8-TRIALKYLPSORALENS

Kurt D. Kaufman, Kalamazoo, Mich. (by Marilee Kaufman, conservator), assignor to Thomas C. Elder, Inc., Hamilton, Ind.

Filed Jul. 29, 1980, Ser. No. 173,437

Int. Cl.³ C07D 493/02; A61K 31/365

U.S. Cl. 424—59

6 Claims

1. 5'-primaryaminoloweralkyl-4',4,8-triloweralkylpsoralen.
3. The method of effecting photochemical sensitivity on the skin of a mammal comprising the step of orally administering to the said mammal an effective photosensitizing dose of a compound of claim 1.

4,294,823

ASTRINGENT OR DEGREASING LOTION

Thomas J. Elliott, London, and David Ford, Isleworth, both of England, assignors to Beecham Group Limited, England
Continuation of Ser. No. 965,790, Dec. 4, 1978, abandoned. This application Dec. 26, 1979, Ser. No. 107,275

Claims priority, application United Kingdom, Nov. 26, 1977, 49304/77

Int. Cl.³ A61K 7/00, 7/035, 7/48, 31/74

U.S. Cl. 424—78

1 Claim

1. A cosmetic ethanol:water based astringent or degreasing lotion which provides a long lasting smoothing and matting effect comprising in suspension in said lotion base from 3 to 10% by weight of spherical or substantially spherical particles of polystyrene, polymethylmethacrylate or polyethylene, said particles having an average particle size of 5 to 7 microns, together with a skin emollient and a cosmetically acceptable suspending agent, said ethanol: water being present relative to one another in a ratio of from 1:19 to 19:1.

4,294,824

EXTRACTS OF THE HEMOPOIETIC SYSTEM

William A. Jones, Staines; Tse Lin Sin Tse Hing Yuen, Harpenden, both of England; Tapio Rytomaa, Helsinki, Finland; Norman J. Harper, Pyrford, and Henry F. Frost, Hemel Hempstead, both of England, assignors to The Union International Company, Ltd., England

Continuation-in-part of Ser. No. 667,217, Mar. 15, 1976, abandoned. This application Jun. 19, 1978, Ser. No. 917,076

Claims priority, application United Kingdom, Aug. 5, 1975, 32659/75

Int. Cl.³ A61K 35/14

U.S. Cl. 424—101

5 Claims

1. A pharmaceutical composition for producing temporary remissions with minimal serious side effects in the treatment of myeloid leukaemia in human patients in intravenous injectable form which comprises an antimyeloid leukaemic effective amount of granulocytic chalone having an elemental analysis of carbon 43.6%, hydrogen 5.8% and nitrogen 6.0%, a molecular weight less than 1,500 daltons when determined by gel techniques and having an infrared spectrum as shown in FIG. 10, sufficient to produce such remissions without impairing the immune defense system of the patient as the active therapeutic agent in combination with a pharmaceutically acceptable carrier suitable for intravenous injection to human patients.

4,294,825

PROCESS FOR THE PRODUCTION OF AN ANDREXOGENIC SUBSTANCE HAVING SPECIFIC EFFECT ON THE CENTRAL REGULATION OF FOOD INTAKE

Jozsef Knoll; Huba Kalasz; Berta Knoll, all of Budapest, and Janos Nagy, Szentendre, all of Hungary, assignors to Richter Gedeon Vegyészeti Gyár RT, Budapest, Hungary

Filed Aug. 23, 1979, Ser. No. 68,766

Claims priority, application Hungary, Aug. 29, 1978, RI 683
Int. Cl.³ A23J 1/06; A23K 1/04; C07G 7/00

U.S. Cl. 424—101

5 Claims

1. A process for the preparation of an endogenous anorexogenic substance having a satiety effect on the central regulation of food intake which comprises the steps of:

- (a) membrane filtering mammalian serum or plasma to separate out materials having a molecular weight of up to 50,000 as a filtrate;
- (b) drying the filtrate;
- (c) dissolving the filtrate dried during step (b) in water;
- (d) chromatographically fractionating on a gel with a void volume under 50,000 the filtrate dissolved during step (c) with a 'neutral', aqueous, eluting salt solution containing at least 0.1% of the salt to obtain a fraction with high anorexogenic activity;
- (e) drying the fraction with high anorexogenic activity;
- (f) dissolving the fraction with high anorexogenic activity in water;
- (g) subjecting the fraction with high anorexogenic activity to a second chromatographic fractionation on a gel with a void volume under 50,000 with distilled water to obtain a second fraction of higher anorexogenic activity; and
- (h) lyophilizing the second fraction of higher anorexogenic activity.

4,294,826

PROCESS FOR THE PREPARATION OF HIGHLY PURIFIED ANTIHEMOPHILIC FACTOR

Fred Feldman, Park Forest, Ill., assignor to Armour Pharmaceutical Company, Tuckahoe, N.Y.

Filed May 7, 1980, Ser. No. 147,441

Int. Cl.³ A61K 35/14, 37/00

U.S. Cl. 424—101

4 Claims

1. A process for the preparation of an aqueous composition of antihemophilic factor having a concentration of about 20 to 45 units of antihemophilic factor per ml, a specific antihemophilic factor activity of at least 1 unit per mg protein, and being obtained from an aqueous solution of antihemophilic factor derived from human blood plasma, said aqueous solution having a concentration of about 5 to 15 units of antihemophilic factor per ml, and a specific antihemophilic factor activity of about 0.3 to 1.0 unit per mg protein, which comprises:

- (a) effecting about a 2- to 10-fold concentration of the low concentrate solution,
- (b) adjusting the pH of said concentrated solution to about 5.0 to 6.0,
- (c) cooling the resultant solution to about 0° to 14° C.,
- (d) removing the precipitate which forms at said pH and temperature,
- (e) further clarifying the solution from step (d), and
- (f) adjusting the pH to about 7.0.

3. A freeze-dried composition of antihemophilic factor derived from human blood plasma, having about 1 to 10 units antihemophilic factor activity per mg protein with a ratio of antigenic Factor VIII to Factor VIII procoagulant activity of approximately one and being substantially free of denatured antihemophilic factor.

4,294,827

ANTIBACTERIAL AND GROWTH PROMOTING β -LACTAM ANTIBIOTICS CARRYING AN -YLIDENE-2-PYRROLIDINON-1-YL RADICAL

Michael Preiss, and Karl G. Metzger, both of Wuppertal, Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Dec. 20, 1977, Ser. No. 862,452


Claims priority, application Fed. Rep. of Germany, Dec. 24, 1976, 2658905

Int. Cl.³ A61K 31/655; C07D 499/68, 501/22, 501/34

U.S. Cl. 424—226

17 Claims

1. A β -lactam antibiotic of the formula (I)



in which


A and A' represent hydrogen; alkyl of up to 5 carbon atoms optionally substituted by halogen, cyano or nitro; a phenyl, naphthyl or furyl radical; or a group of the formula R_1-X'

in which


X' denotes a $-CO-$ or $-SO_2-$ group and R_1 denotes hydrogen; alkyl of up to 5 carbon atoms optionally substituted by halogen, cyano or nitro; a phenyl, naphthyl, thienyl, furyl, pyrrolidyl or piperidyl radical; amino; monoalkylamino or dialkylamino of up to 4 carbon atoms per alkyl group, it being furthermore possible for R_1 to denote alkoxy of up to 4 carbon atoms if X' represents the $-CO-$ group;
R represents H or OCH_3 ,
B represents phenyl, methylphenyl, chlorophenyl, hydroxyphenyl, furyl or the radical



X represents S, SO or SO_2 ; and
Y represents the group



in which
the carbon atom which carries the carboxyl group is bonded to the nitrogen atom of the β -lactam ring and T denotes hydrogen, C_{1-4} alkyl-CO-O, pyridinium, aminopyridinium, carbamoyloxy, azido, cyano, hydroxyl, the group $-S$ -phenyl, which can be substituted by halogen, amino, lower alkylamino, di-lower alkylamino, lower alkyl, cycloalkyl of 3-7 ring carbon atoms, lower alkoxy, trifluoromethyl, phenyl, benzyl or acylamino with 2 to 5 carbon atoms, or the group $-S$ -Het,
in which
Het represents



optionally substituted by halogen, amino, lower alkyl-amino, di-lower alkylamino, lower alkyl, cycloalkyl of 3-7 ring carbon atoms, lower alkoxy, trifluoromethyl, phenyl, benzyl or acylamino with 2 to 5 carbon atoms; or a pharmaceutically acceptable salt thereof.

13. An antibacterial and growth promoting composition containing as an active ingredient an effective amount of a compound according to claim 1 in admixture with a diluent.

4,294,828

NEW DERIVATIVES OF 4-AMINO-5-ALKYL SULPHONYL ORTHOANISAMIDES, METHODS OF PREPARING THEM AND THEIR APPLICATION AS PSYCHOTROPIC AGENTS

Michel Thominet, Paris; Jacques Acher, Itteville, and Jean-Claude Monier, Lardy, all of France, assignors to Societe d'Etudes Scientifiques et Industrielles de l'Ile de France, Paris, France

Filed Jan. 18, 1979, Ser. No. 4,397


Claims priority, application France, Jan. 20, 1978, 78-01632

Int. Cl.³ A61K 31/40, 31/62; C07D 207/08

U.S. Cl. 424—232

3 Claims

1. A pharmaceutical composition having antiemetic or antiserotonin activity comprising an effective amount of a compound selected from the group consisting of 4-amino-5-alkylsulphonylorthoanisamides having the formula:



wherein:

R_1 is lower alkyl of 1 to 5 carbon atoms or lower alkenyl of 2 to 5 carbon atoms and R_2 and R_3 are lower alkyl of 1 to 5 carbon atoms,
the N-oxides of said anisamides, the addition salts of said derivatives with pharmacologically acceptable acids, the quaternary ammonium salts of said derivatives and the

levorotatory and dextrorotatory optical isomers of all of the foregoing compounds, and a pharmaceutically acceptable carrier.

4,294,829

POWDERY PHARMACEUTICAL COMPOSITION AND POWDERY PREPARATION FOR APPLICATION TO THE NASAL MUCOSA, AND METHOD FOR ADMINISTRATION THEREOF

Yoshiki Suzuki; Hiroshi Ikura, both of Hino; Gentaro Yamashita, Koganei, and Tsuneji Nagai, Tokyo, all of Japan, assignors to Teijin Limited, Osaka, Japan

Filed Jul. 30, 1980, Ser. No. 173,906

Claims priority, application Japan, Jul. 31, 1979, 54-96666

Int. Cl.³ A61K 31/58, 31/56; A01N 43/36

U.S. Cl. 424-241

19 Claims



1. A powdery pharmaceutical composition for application to the mucosa of the nasal cavity, at least about 90% of which consists of particles having an effective particle diameter of about 20 to about 250 microns, said composition comprising a lower alkyl ether of cellulose selected from the group consisting of methyl cellulose, hydroxy-lower alkyl cellulose and carboxylate formed between alkali metals and carboxy-lower alkyl cellulose wherein said lower alkyls have 2 or 3 carbon atoms, said lower alkyl ether of cellulose having a viscosity, determined at about 37° C. for a 2% aqueous solution thereof, of at least about 5 centipoises and a pharmaceutically effective amount of a drug selected from the group consisting of a steroidal anti-inflammatory agent, a nonsteroidal anti-inflammatory agent, an anti-histaminic agent, an anti-allergic agent and a vasoconstrictor.

8. The composition of claim 1 wherein said steroidal anti-inflammatory agent is triamcinolone acetonide or beclomethasone dipropionate.

4,294,830

[[[4-AZIDO-5-(ETHOXYETHYL)-6-PHENYL-2-PYRIMIDINYL]AMINO]CARBONYL]GLYCINE AND ESTERS THEREOF

Hans A. Wagner, Skokie, Ill., assignor to G. D. Searle & Co., Skokie, Ill.


Filed Jun. 16, 1980, Ser. No. 159,703

Int. Cl.³ A61K 31/505; C07D 239/48

U.S. Cl. 424-251

5 Claims

1. A compound of the formula



wherein R₁ is phenyl or substituted phenyl wherein the substituents are from one to three selected from lower alkyl, chloro, bromo, or fluoro; R₂ is hydrogen or C₁-C₄ alkyl; and when R₂ is hydrogen, a pharmaceutically acceptable salt thereof.

5. A pharmaceutical composition comprising a therapeuti-

cally effective amount of a compound of claim 1 and a pharmaceutically acceptable carrier or diluent.

4,294,831

PURINE DERIVATIVES

Howard J. Schaeffer, Raleigh, N.C., assignor to Burroughs Wellcome Co., Research Triangle Park, N.C.

Division of Ser. No. 718,105, Aug. 27, 1976, abandoned, which is a continuation-in-part of Ser. No. 662,900, Mar. 1, 1976, Pat. No. 4,199,574, and Ser. No. 608,263, Aug. 27, 1975, abandoned.

This application Feb. 1, 1978, Ser. No. 874,060

Claims priority, application United Kingdom, Sep. 2, 1974, 38278/74

The portion of the term of this patent subsequent to Apr. 22, 1997, has been disclaimed.

Int. Cl.³ C07D 473/18

U.S. Cl. 424-253

14 Claims

1. 9-(2-propionyloxyethoxymethyl)guanine.

4,294,832

TETRAHYDROISOQUINOLINE COMPOUNDS AND A PHARMACEUTICAL COMPOSITION THEREOF

Naoto Yoneda, Suita; Jyoji Kato, Yawata, and Keizo Kinashi, Yao, all of Japan, assignors to Tanabe Seiyaku Co., Ltd., Osaka, Japan

Filed Apr. 10, 1980, Ser. No. 138,933


Claims priority, application Japan, Apr. 28, 1979, 54/52796; Jul. 17, 1979, 54/91123; Aug. 2, 1979, 54/98832

Int. Cl.³ A61K 31/47; C07D 217/16, 217/24

U.S. Cl. 424-258

17 Claims

1. A tetrahydroisoquinoline compound of the formula:



wherein R¹ is alkyl of one to six carbon atoms, cycloalkyl of three to six carbon atoms, allyl or propargyl, R² is hydrogen or alkyl of one to six carbon atoms, and R³ is hydrogen, alkyl of one to six carbon atoms or benzyl, or a pharmaceutically acceptable salt thereof.

17. An inhibitory composition for the treatment of angiotensin-related hypertension comprising an amount of the compound of claim 1 such that, when said composition is administered to a warm blooded animal, it will provide an effective amount in said animal, and a pharmaceutically acceptable carrier therefor.

4,294,833

SUBSTITUTED 4-HYDROXY-ISOPHTHALIC ACID PICOLYLAMIDES HAVING A PHARMACEUTICAL ACTIVITY IN THROMBOEMBOLIC DISORDERS

Franco Innocenti; Giovanni Orzalesi, and Ivo Volpato, all of Florence, Italy, assignors to Societa Italo-Britannica, Florence, Italy

Filed Aug. 29, 1978, Ser. No. 937,732

Claims priority, application Italy, Sep. 6, 1977, 50896 A/77


Int. Cl.³ A61K 31/44; C07D 213/40

U.S. Cl. 424-263

24 Claims

1. 4-hydroxy-isophthalic acid bis(3-or 4-picolylamides) of the formula I:

and R₃ are as defined in claim 2 and R₄ is hydroxy, alkoxy of from 1 to 6 carbon atoms or benzyloxy.



wherein R' is H or an aliphatic or alicyclic hydrocarbon group with 1 to 6 carbon atoms, R''' is 3-pyridyl or 4-pyridyl, R'' is H, Cl, NO₂, or -OCH₃, R'' is an aliphatic or alicyclic hydrocarbon group with 1 to 8 carbon atoms, with the exception that when R''' is 3-pyridyl and R' and R'' are both H, then R'' is an aliphatic or alicyclic hydrocarbon group with 3 to 8 carbon atoms.

4,294,834

AZOCINE ANALGESICS AND METHOD FOR THEIR PREPARATION

Johannes Hartenstein, Stegen-Wittental; Gerhard Satzinger, Denzlingen; Heinrich Bahrmann, Kirchzarten, and Volker Ganser, Freiburg, all of Fed. Rep. of Germany, assignors to Godecke Aktiengesellschaft, Freiburg, Fed. Rep. of Germany

Filed Nov. 13, 1979, Ser. No. 93,314


Claims priority, application Fed. Rep. of Germany, Nov. 15, 1978, 2849472; Jul. 7, 1979, 2927501

Int. Cl.³ C07D 221/22; A61K 31/435

U.S. Cl. 424-260

22 Claims


1. A compound having the structural formula:



wherein R is hydrogen, branched or straight chain alkyl of from 1 to 3 carbon atoms, branched or straight chain alkenyl of 2 to 5 carbon atoms, cycloalkylalkyl of from 4 to 8 carbon atoms, or benzyl or phenethyl the aromatic rings of which may be optionally substituted by from 1 to 3 alkoxy groups of 1 to 3 carbon atoms or methylenedioxy; R₁ is hydroxy or alkoxy of from 1 to 3 carbon atoms; R₂ is hydrogen or alkoxy of from 1 to 3 carbon atoms; R₁ and R₂ when taken together may form a methylenedioxy group; R₃ is alkoxy of 1 to 3 carbon atoms; and the pharmacologically acceptable salts thereof.

2. A pharmaceutical composition for treating pain consisting essentially of an analgesic-effective amount of a compound as defined in claim 1 in combination with a pharmaceutically acceptable carrier.

16. A process for preparing a compound as defined in claim 1 which comprises treating a compound having the structural formula II



with an oxidizing agent in the presence of a strong acid at a temperature of from -15° C. to +30° C.; wherein R, R₁, R₂

2-HYDROXY BENZAMIDE DERIVATIVES AND USE THEREOF AS A FUNGICIDE

Taizo Nakagawa; Hiroshi Matsumoto, both of Ageo; Kaoru Ohmori, Okegawa; Shizuo Shimano, and Kengo Koike, both of Ageo, all of Japan, assignors to Nippon Kayaku Kabushiki Kaisha, Tokyo, Japan

Filed Feb. 20, 1980, Ser. No. 123,766


Claims priority, application Japan, Feb. 27, 1979, 54-21350

Int. Cl.³ C07C 103/26; C07D 213/75; A01N 43/40, 37/24

U.S. Cl. 424-263


7 Claims

1. A compound represented by the formula:



wherein R is alkyl having 1-12 carbon atoms.

6. A fungicidal composition for agriculture and horticulture comprising 0.5 to 95% by weight of a compound of the formula:



wherein

R is alkyl having 1-12 carbon atoms, and 99.5 to 5% by weight of inert adjuvants.

4,294,836

1,3-DIHYDRO-6-(PYRIDINYL)-2H-IMIDAZO[4,5-B]PYRIDIN-2-ONES AND -IMIDAZO[4,5-B]-PYRIDINE-2-THIONES AND THEIR CARDIOTONIC USE

George Y. Leshner, Schodack, and Ruth P. Brundage, East Greenbush, both of N.Y., assignors to Sterling Drug Inc., New York, N.Y.


Filed Mar. 24, 1980, Ser. No. 132,907

Int. Cl.³ C07D 471/04; A61K 31/415

U.S. Cl. 424-263

14 Claims

1. A 1,3-dihydro-3-R-5-PY-2H-imidazo[4,5-b]pyridin-2-one or -2-thione having the formula



II where Z is O, or S, R is hydrogen, lower-alkyl, lower-hydroxyalkyl, 2,3-dihydroxypropyl, lower-alkoxyalkyl or Y-NB where Y is lower-alkylene having at least two carbon atoms between its connecting linkages and NB is di-(lower-alkyl)amino or 4-morpholinyl, and PY is 4- or 3-pyridinyl or 4- or 3-pyridinyl having one or two lower-alkyl substituents, or pharmaceutically-acceptable acid-addition salt thereof.

11. The method for increasing cardiac contractility in a patient requiring such treatment which comprises administering orally or parenterally in a solid or liquid dosage form to

such patient an effective amount of the cardiotonic 1,3-dihydro-3-R-5-PY-2H-imidazo[4,5-b]pyridin-2-one or -2-thione or pharmaceutically-acceptable acid-addition salt thereof, where Z is O or S, R is hydrogen, lower-alkyl, lower-hydroxyalkyl, 2,3-dihydroxypropyl, lower-alkoxyalkyl or Y-NB where Y is lower-alkylene having at least two carbon atoms between its connecting linkages and NB is di-(lower-alkyl)amino or 4-morpholinyl, and PY is 4- or 3-pyridinyl or 4- or 3-pyridinyl having one or two lower-alkyl substituents.

4,294,837

1,3-DIHYDRO-6-(PYRIDINYL)-2H-IMIDAZO[4,5-B]PYRIDIN-2-ONES AND -IMIDAZO[4,5-B]PYRIDINE-2-THIONES AND THEIR CARDIOTONIC USE

George Y. Lesh; Chester J. Opalka, Jr., both of Schodack, and Donald F. Page, East Greenbush, all of N.Y., assignors to Sterling Drug Inc., New York, N.Y.


Filed Mar. 28, 1980, Ser. No. 135,105

Int. Cl.³ C07D 471/04; A61K 31/415

U.S. Cl. 424-263

12 Claims

1. A 1,3-dihydro-1-R₁-3-R₃-6-PY-5-Q-2H-imidazo[4,5-b]pyridin-2-one or -2-thione having the formula



where Z is O or S, Q is hydrogen or lower-alkyl, R₁ and R₃ each are hydrogen, lower-alkyl, lower-hydroxyalkyl, 2,3-dihydroxypropyl, lower-alkoxyalkyl or Y-NB where Y is lower-alkylene having at least two carbon atoms between its connecting linkages and NB is di-(lower-alkyl)amino or 4-morpholinyl, at least one of R₁ or R₃ being hydrogen, and PY is 4- or 3-pyridinyl or 4- or 3-pyridinyl having one or two lower-alkyl substituents, or pharmaceutically-acceptable acid-addition salt thereof.

11. The method for increasing cardiac contractility in a patient requiring such treatment which comprises administering orally or parenterally in a solid or liquid dosage form to such patient an effective amount of the cardiotonic 1,3-dihydro-1-R₁-3-R₃-6-PY-5-Q-2H-imidazo[4,5-b]pyridin-2-one or -2-thione or pharmaceutically-acceptable acid-addition salt thereof, where Z is O or S, Q is hydrogen or lower-alkyl, R₁ and R₃ each are hydrogen, lower-alkyl, lower-hydroxyalkyl, 2,3-dihydroxypropyl, lower-alkoxyalkyl or Y-NB where Y is lower-alkylene having at least two carbon atoms between its connecting linkages and NB is di-(lower-alkyl)amino or 4-morpholinyl, at least one of R₁ or R₃ being hydrogen, and PY or 4- or 3-pyridinyl or 4- or 3-pyridinyl having one or two lower-alkyl substituents.

4,294,838

CERTAIN HETEROCYCLIC SULFOXIMIDE DERIVATIVES

Peter Stoss, Mooswaldstr. 11., 7801 Vorstetten; Gerhard Satzinger, Im Mattenbühl 7, 7809 Denzlingen; Manfred Herrmann, Wolfweg 25, 7811 St. Peter, and Wolfgang Heldt, Weidenmattenstr. 4, 7803 Emmendingen 16, all of Fed. Rep. of Germany


Continuation-in-part of Ser. No. 971,139, Dec. 19, 1978, abandoned. This application May 15, 1980, Ser. No. 150,119. Claims priority, application Fed. Rep. of Germany, Dec. 29, 1977, 2758613

Int. Cl.³ A61K 31/44; C07D 213/62, 407/12, 409/12

U.S. Cl. 424-263

11 Claims

1. Sulphoximide derivatives of the general formula:



wherein R₁ is a phenyl, thienyl, furyl or pyridyl ring; R₂ is a thienyl, furyl or pyridyl ring; R₃ and R₄, which can be the same or different, are alkyl groups containing up to 6 carbon atoms and n is a whole number of from 1 to 5; and the pharmaceutically acceptable salts thereof with organic and inorganic acids, as well as the pharmaceutically acceptable quaternary ammonium salts thereof.

11. An anti-spasmodic composition, comprising a sulphoximide derivative according to claim 1, in admixture with an inert solid or liquid pharmaceutical diluent or carrier.

4,294,839

BENZOTHIADIAZOLE DERIVATIVES AND PHARMACEUTICAL FORMULATIONS CONTAINING THEM

Thomas Doll, Mainz; Erich Schacht, Seeheim-Jugenheim; Hans-Eckart Radunz, Mühlthal, and Ernst Schulze, Darmstadt, all of Fed. Rep. of Germany, assignors to Merck Patent Gesellschaft mit beschränkter Haftung, Darmstadt, Fed. Rep. of Germany

Filed Dec. 12, 1980, Ser. No. 215,987


Claims priority, application Fed. Rep. of Germany, Dec. 13, 1979, 2950095

Int. Cl.³ A61K 31/425, 31/44; C07D 277/74, 417/12

U.S. Cl. 424-263

8 Claims

1. A benzothiazole derivative of the formula



wherein R¹ is H or CH₃; R² is phenyl, tolyl, xylyl or pyridyl; R³ is OH, alkoxy of 1-4 C atoms or -NHCH₂CH₂OH; and R⁴ is H, Cl, Br, OH or alkoxy of 1-4 C atoms, or a physiologically acceptable salt thereof.

8. A method of lowering the lipid level in a patient in need of such lowering, comprising administering to the patient an amount of a compound of claim 1 effective for such lowering.

4,294,840

KETAZOCINE ANESTHETIC METHOD OF USE

Alfred E. Farah, Shodack, N.Y., assignor to Sterling Drug Inc., New York, N.Y.

Division of Ser. No. 11,107, Feb. 12, 1979, Pat. No. 4,217,354.

This application Aug. 31, 1979, Ser. No. 71,774

Int. Cl.³ A61K 31/445

U.S. Cl. 424-267

3 Claims

1. The method of producing general anesthesia in a mammal in need of general anesthesia which comprises administering diazepam intramuscularly to the mammal and subsequently administering intravenously to the mammal an amount effective for producing general anesthesia of a pharmaceutically acceptable salt of racemic or levo 1,2,3,4,5,6-hexahydro-1-oxo-3-cyclopropylmethyl-8-hydroxy-6(eq),11(ax)-dimethyl-2,6-methano-3-benzazocine.

4,294,841

DERIVATIVES OF 1-PHENYL 3-(4-PIPERIDYL) 1-PROPANONE USABLE AS DRUGS

Alain A. Champseix, Forges les Bains, and Gerard R. Le Fur, Plessis Robinson, both of France, assignors to Pharmindus-trie, Gennevilliers, France

Filed Nov. 27, 1979, Ser. No. 97,772


Claims priority, application France, Dec. 5, 1978, 78 34185

Int. Cl.³ A61K 31/445; C07D 211/32


U.S. Cl. 424-267

8 Claims

1. A pharmaceutical composition, particularly useful as an antiarrhythmic and for the treatment of states of depression and anxiety, which contains as an active agent a pharmaceutically effective amount of a compound corresponding to the formula:



wherein X and Y are the same or different and represent hydrogen, halogen, alkyl containing 1 to 4 carbon atoms, alkoxy containing 1 to 4 carbon atoms, alkylthio containing 1 to 4 carbon atoms, trifluoromethyl, hydroxy, amino, monoalkylamino containing 1 to 4 carbon atoms or amino substituted by alkylsulfonyl containing 1 to 4 carbon atoms, by alkylcarbonyl containing 1 to 5 carbon atoms or by benzoyl, and A represents



or a salt of said compound with a pharmaceutically acceptable acid, in a pharmaceutically acceptable carrier.

4. A chemical compound corresponding to formula (I) of claim 1, wherein A is CH₂, Y is hydrogen or halogen or alkyl containing 1 to 4 carbon atoms, alkoxy containing 1 to 4 carbon atoms, alkylthio containing 1 to 4 carbon atoms, trifluoromethyl, hydroxy, amino, monoalkylamino containing 1 to 4 carbon atoms, or amino substituted by alkylsulfonyl containing 1 to 4 carbon atoms, by alkylcarbonyl containing 1 to 5 carbon atoms or by benzoyl and X is halogen or alkylthio containing 1 to 4 carbon atoms, alkoxy containing 2 to 4 carbon atoms, trifluoromethyl, hydroxy, amino or monoalkylamino containing 1 to 4 carbon atoms or amino substituted by alkylsulfonyl containing 1 to 4 carbon atoms, by alkylcarbonyl containing 1 to 5 carbon atoms or by benzoyl.

4,294,842

ANTI-PROTOZOAL OXADIAZOLE DERIVATIVES

John B. Weston, Tring, England, assignor to Burroughs Wellcome Co., Research Triangle Park, N.C.

Filed Jul. 12, 1979, Ser. No. 56,997


Claims priority, application United Kingdom, Jul. 13, 1978, 29818/78

Int. Cl.³ A61K 31/42; C07D 271/06

U.S. Cl. 424-272

7 Claims

1. A compound of the formula (I)



wherein

R¹ is selected from the group consisting of hydrogen, lower alkyl, halogen, hydroxy, alkoxy or nitro; each R² is the same or different and is selected from the group consisting of hydrogen, lower alkyl, halogen, hydroxy, alkoxy, aryloxy, alkylthio, arylthio, amino, substituted amino, cyano, nitro or together with an adjacent group R² a residue -CH=CH-CH=CH-; or R¹ and one R² together form a residue -CH=CH-CH=CH-;

X and Y together represent a bond or are both hydrogen; R³ is selected from the group consisting of hydrogen, lower alkyl, aryl, and a group Ar-S-CH₂-; and

Ar is phenyl optionally substituted with one, two or three substituents which may be the same or different, and acid addition salts thereof.

7. A method for the treatment of a protozoal infection in animal, including man, comprising administration of a non-toxic antiprotozoal-effective amount of a compound as defined in any one of claims 1 to 4.

4,294,843

ANTI-PROTOZOAL OXADIAZOLE DERIVATIVES

John B. Weston, Tring, England, assignor to Burroughs Wellcome Co., Research Triangle Park, N.C.

Filed Jul. 12, 1979, Ser. No. 56,998


Claims priority, application United Kingdom, Jul. 13, 1978, 29817/78

Int. Cl.³ A61K 31/42; C07D 271/06

U.S. Cl. 424-272

17 Claims

1. A compound of the formula (I):



wherein R¹ is selected from the group consisting of amino or substituted amino;

each R² is the same or different, in one or more of the 3, 4, 5 or 6 positions and is selected from the group consisting of hydrogen, lower alkyl, halogen, hydroxy, alkoxy, alkylthio, arylthio, amino, substituted amino, cyano or nitro; X and Y together represent a bond or X and Y are both hydrogen;

R³ is selected from the group consisting of hydrogen, lower alkyl, aryl, and a group -SCH₂Ar; and

Ar is phenyl, optionally substituted with one, two or three substituents which may be the same or different; and acid addition salts thereof.

8. A method for the treatment of a protozoal infection in an animal including man, comprising administration of a non-toxic, anti-protozoal effective amount of a compound as defined in any one of claims 1 to 5.

4,294,844

USE OF 4,5-DIHYDRO-2-LOWER ALKOXYCARBONYLAMINO-4-PHENYL IMIDAZOLES AND SUBSTITUTED PHENYL DERIVATIVES THEREOF AS ANTI-HYPERTENSIVE AGENTS

George S. Harris, Palo Alto, Calif., assignor to Syntex (U.S.A.) Inc., Palo Alto, Calif.


Filed Jun. 4, 1979, Ser. No. 44,900

Int. Cl.³ A61K 31/415

U.S. Cl. 424-273 R

5 Claims

1. A method for lowering the blood pressure in a hypertensive human being which comprises administering to said human being a therapeutically effective hypotensive amount of a compound chosen from those represented by the formula



wherein

R is lower alkyl;
R¹ is hydrogen, lower alkyl, hydroxy, lower alkoxy, fluoro, chloro, bromo, iodo or trifluoro methyl; and
R² is hydrogen or is a substituent which is identical to the R¹ substituent, and wherein R¹ and R² can be at any position on the phenyl ring or R¹ and R² together form methylenedioxy and are at adjacent carbon atoms on the phenyl ring, and the pharmaceutical salts thereof.

4,294,845

1,3-BENZODIOXIN DERIVATIVES

Daniel Humbert, Fontenay-sous-Bois; Francois Clemence, Paris, and Michele Dagnaux, Fontenay-sous-Bois, all of France


Continuation-in-part of Ser. No. 847,776, Nov. 2, 1977, abandoned. This application Apr. 30, 1979, Ser. No. 34,431 Claims priority, application France, May 3, 1978, 78 13094

Int. Cl.³ A61K 31/335; C07D 319/08

U.S. Cl. 424-278 Q


30 Claims

1. A compound selected from the group consisting of racemic mixtures or optically active isomers of 1,3-benzodioxins of the formula



wherein R₁' is selected from the group consisting of hydrogen, alkali metal, alkaline earth metal, —NH₄, aluminum, non-toxic, pharmaceutically acceptable amines, alkyl of 1 to 5 carbon atoms, 2,3-dihydroxypropyl, (2,2-dimethyl-1,3-dioxolan-4-yl)-methyl and dialkylaminolalkyl with alkyls of 1 to 4 carbon atoms, R₂ is selected from the group consisting of hydrogen and alkyl of 1 to 5 carbon atoms, R₃ is selected from the group consisting of hydrogen, alkyl of 1 to 5 carbon atoms and phenyl and R₄ and R₅ are individually selected from the group consisting of hydrogen and halogen and the non-toxic, pharmaceutically acceptable acid addition salts where R₁' is dialkylaminoalkyl with the proviso that R₂ and R₃ are not simultaneously hydrogen.


11. An hypolipemiant composition comprising an hypolipemiantly effective amount of at least one compound selected from the group consisting of racemic mixtures or optically active isomers of 1,3-benzodioxins of the formula



wherein R₁' is selected from the group consisting of hydrogen, alkali metal, alkaline earth metal, —NH₄, aluminum, non-toxic, pharmaceutically acceptable amines, alkyl of 1 to 5 carbon

atoms, 2,3-dihydroxypropyl, (2,2-dimethyl-1,3-dioxolan-4-yl)-methyl and dialkylaminoalkyl with alkyls of 1 to 4 carbon atoms, R₂ is selected from the group consisting of hydrogen and alkyl of 1 to 5 carbon atoms, R₃ is selected from the group consisting of hydrogen, alkyl of 1 to 5 carbon atoms and phenyl and R₄ and R₅ are individually selected from the group consisting of hydrogen and halogen and the non-toxic, pharmaceutically acceptable acid addition salts when R₁' is dialkylaminoalkyl and an inert pharmaceutical carrier.

21. A method of inducing hypolipemiant activity in warm-blooded animals comprising administering a warm-blooded animals an hypolipemiantly effective amount of at least one compound selected from the group consisting of racemic mixtures or optically active isomers of 1,3-benzodioxins of the formula



wherein R₁' is selected from the group consisting of hydrogen, alkali metal, alkaline earth metal, —NH₄, aluminum, non-toxic, pharmaceutically acceptable amines, alkyl of 1 to 5 carbon atoms, 2,3-dihydroxypropyl, (2,2-dimethyl-1,3-dioxolan-4-yl)-methyl and dialkylaminoalkyl with alkyls of 1 to 4 carbon atoms, R₂ is selected from the group consisting of hydrogen and alkyl of 1 to 5 carbon atoms, R₃ is selected from the group consisting of hydrogen, alkyl of 1 to 5 carbon atoms and phenyl and R₄ and R₅ are individually selected from the group consisting of hydrogen and halogen and the non-toxic, pharmaceutically acceptable acid addition salts where R₁' is dialkylaminoalkyl.

4,294,846

HYPOCHOLESTEREMIC FERMENTATION PRODUCTS AND PRODUCTS OF PREPARATION

George Albers-Schonberg, Princeton, N.J.; Henry Joshua, Staten Island, N.Y., and Maria B. Lopez, Elizabeth, N.J., assignors to Merck & Co., Inc., Rahway, N.J.


Continuation-in-part of Ser. No. 77,807, Sep. 21, 1979, abandoned. This application May 28, 1980, Ser. No. 154,157

Int. Cl.³ C07D 309/30; A61K 31/365

U.S. Cl. 424-279

2 Claims

1. A compound, in substantially pure form, with structural formula:



4,294,847

8-AMINOALKYL-4-ALKYLISOPSORALENS

Kurt D. Kaufman, Kalamazoo, Mich., assignor to Thomas C. Elder, Inc., Hamilton, Ind.

Filed Jul. 29, 1980, Ser. No. 173,384

Int. Cl.³ C07D 493/04; A61K 31/365

U.S. Cl. 424-279

10 Claims

1. 4-loweralkyl-8-primarilyaminoloweralkylisoporsalen or a non-toxic and pharmacologically-acceptable salt thereof.

5. The method of effecting photochemical sensitivity on the skin of a mammal comprising the step of orally or topically administering to the said mammal an effective photosensitizing dose of a compound of claim 1.

4,294,848

THIOCYANO-CONTAINING POLYOXYALKYLENES

David J. Tracy, Lincoln Park; Lindley S. Wood, Montclair, and Paritosh M. Chakrabarti, Wayne, all of N.J., assignors to GAF Corporation, New York, N.Y.


Filed Jul. 31, 1980, Ser. No. 174,291

Int. Cl.³ A01N 47/48; C07C 161/02

U.S. Cl. 424-302

11 Claims

1. A thiocyno-containing polyoxyalkylene product having the formula:



wherein E is halogen or —SCN, A, C and D represent lower alkylene of 2 to 4 carbon atoms; B is alkylene of 2 to 8 carbon atoms; y and z are each integers having a value of from 0 to 50 and x is an integer having a value of from 2 to 50; and intermixtures of said thiocyno-containing polyoxyalkylene compounds.

10. The process of contacting a site of infestation of bacteria, fungi or a nematode with between about 0.05 and about 20 weight % of the product of claim 1 to arrest said infestation.

4,294,849

PROSTAGLANDIN ANALOGUES

Masaki Hayashi, Takatsuki; Sadahiko Iguchi, Otsu; Takanori Okada, Ibaraki, and Akiyoshi Kawasaki, Osaka, all of Japan, assignors to Warner-Lambert Company, Morris Plains, N.J.

Filed Jan. 24, 1980, Ser. No. 114,804


Claims priority, application Japan, Jan. 29, 1979, 54-8904

Int. Cl.³ C07C 177/00; A61K 31/557

U.S. Cl. 424-305

11 Claims

1. A prostaglandin analogue of the general formula:



(wherein R represents a hydrogen atom or a straight- or branched-chain alkyl group containing from 1 to 4 carbon atoms, the wavy line indicates attachment of α- or β-configuration or a mixture thereof, and the double bonds between C₂-C₃ and C₁₃-C₁₄ are trans), and cyclodextrin clathrates of such acids and esters, and when R represents a hydrogen atom, non-toxic salts of such acids.

4,294,850

FUNGICIDAL ACYLANILIDES

Adolf Hubele, Magden, Switzerland, assignor to Ciba-Geigy Corporation, Ardsley, N.Y.


Division of Ser. No. 923,604, Jul. 11, 1978, Pat. No. 4,206,228, which is a division of Ser. No. 723,826, Sep. 16, 1976, Pat. No. 4,151,299, which is a continuation of Ser. No. 565,037, Apr. 4, 1975, abandoned. This application Dec. 7, 1979, Ser. No. 101,355 Claims priority, application Switzerland, Apr. 9, 1974, 4995/74; Mar. 14, 1975, 3259/75

Int. Cl.³ A01N 37/10; C07C 149/43

U.S. Cl. 424-309


12 Claims

1. A fungicidal composition which contains as active substance a fungicidally effective amount of a compound of the formula



wherein

R₁ represents alkyl of 1 to 4 carbon atoms, alkoxy of 1 to 4 carbon atoms or halogen,
R₂ represents hydrogen, alkyl of 1 to 3 carbon atoms, alkoxy of 1 to 4 carbon atoms or halogen,
R₇ represents hydrogen, alkyl of 1 to 3 carbon atoms, alkoxy of 1 to 4 carbon atoms or halogen,
R₈ represents hydrogen or methyl,
the total number of carbon atoms of the substituents R₁, R₂, R₇ and R₈ in the phenyl ring not exceeding 8,
X represents —CH₂— or



R₃ represents —COOR' or



wherein each of R', R'' and R''' independently represents hydrogen, methyl or ethyl, and
Hal represents a halogen anion,
together with suitable carriers and optionally other agents which promote the application thereof.

7. A compound according to claim 1.

4,294,851

AMINO BENZOIC ACID DERIVATIVES

Gunter Metz, Auf dem Rucken 29, and Manfred Specker, Weilerhalde 32, both of Blaubeuren, Fed. Rep. of Germany

Filed Jun. 27, 1978, Ser. No. 919,747

Claims priority, application Fed. Rep. of Germany, Jul. 4, 1977, 2730174


VI The portion of the term of this patent subsequent to Mar. 27, 1996, has been disclaimed.

Int. Cl.³ A61K 31/17, 31/165; C07C 101/00, 103/78


U.S. Cl. 424-311

2 Claims

1. Aminobenzoic acid compounds of the formula:



wherein R₁ is hydrogen, chlorine, hydroxy, acetoxy or C₁—C₃—alkoxy; Y is the group:



wherein R_3 and R_4 are hydrogen or methyl and their acid addition salts.

4,294,852

SKIN TREATING COMPOSITIONS

Richard H. Wildnauer, East Brunswick, and William T. Humphries, Pennington, both of N.J., assignors to Johnson & Johnson, New Brunswick, N.J.

Continuation-in-part of Ser. No. 411,939, Nov. 1, 1973, abandoned. This application Aug. 21, 1975, Ser. No. 607,171 Int. Cl.³ A61K 31/19

U.S. Cl. 424—317

13 Claims

1. A skin treating composition comprising (a) a major amount of an aqueous phase comprising water having dissolved therein from about 0.1 to about 35% by weight of said composition of an alcohol selected from the group consisting of n-propanol and the monohydric aliphatic alcohols having from 4 to 6 carbon atoms, and an effective amount, sufficient to adjust the pH of said composition to a pH within the range of about 2 to about 6.5, of an organic acid having from 2 to about 10 carbon atoms selected from the group consisting of the aliphatic mono-, di- and tri-carboxylic acids and the derivatives of said acids which are substituted at one or both of the alpha and beta carbons with a hydroxyl or keto group; and (b) no more than about 15% by weight of the total composition of a lipid phase.

5. The composition of claim 1, further comprising an effective amount of a topically active pharmaceutical compound.

8. The composition of claim 5, wherein said pharmaceutical compound is retinoic acid.

4,294,853

BIOCIDAL ADDITIVE FOR CUTTING FLUIDS


John W. Williams, Vallejo, Calif.; Robert A. Smith, Lindenhurst, and Francis W. Arbir, Itasca, both of Ill., assignors to Abbott Laboratories, North Chicago, Ill.

Continuation-in-part of Ser. No. 48,202, Jun. 13, 1979, abandoned. This application Jun. 3, 1980, Ser. No. 156,141 Int. Cl.³ A01N 37/12

U.S. Cl. 424—319

12 Claims

1. A mixture for use as a biocidal additive to industrial cutting fluids consisting essentially of 1 part by weight of 1,1-diiododimethyl sulfone and between 0.5 and 250 parts by weight of a chelating agent



wherein R is hydrogen, an alkali metal cation or ammonium, and n is 0 or 1.

4,294,854

PHARMACEUTICAL COMPOSITIONS

Graham J. Durant; Charon R. Ganellin, and Margaret R. Vickers, all of Welwyn Garden City, England, assignors to Smith Kline & French Laboratories Limited, Welwyn Garden City, England

Division of Ser. No. 853,773, Nov. 21, 1977, Pat. No. 4,205,071, which is a continuation-in-part of Ser. No. 795,983, May 11, 1977, abandoned. This application Oct. 9, 1979, Ser. No. 82,836 Claims priority, application United Kingdom, May 14, 1976, 19994/76


Int. Cl.³ A61K 31/33, 31/155, 31/495

U.S. Cl. 424—326

4 Claims

1. A method of producing immunosuppressant activity by

administering to an animal in need thereof an effective amount of an isothiourea of the formula:



wherein

n is 2, 3 or 4;

R^1 and R^2 , which may be the same or different, are lower alkyl; and

R^3 and R^4 , which may be the same or different, are lower alkyl,

or a pharmaceutically acceptable acid addition salt thereof.

4,294,855

EMOLLIENT AND/OR DYED PRILLED UREA BEAD COMPOSITION

Donald C. Wood, Des Plaines, and Robert L. McLaughlin, Wilmette, both of Ill., assignors to DeSoto, Inc., Des Plaines, Ill.

Filed Nov. 26, 1975, Ser. No. 635,282

The portion of the term of this patent subsequent to Jun. 6, 1995, has been disclaimed.

Int. Cl.³ A61K 7/50

U.S. Cl. 424—358

9 Claims

1. A bath bead composition comprising at least 50% by weight of beads of prilled urea, said beads having absorbed therein from 0.5–10% by weight of an oily emollient, and said beads being dyed with water soluble dye.

5. A bath bead composition comprising at least 50% by weight of beads of prilled urea, said beads having absorbed therein from 0.5–10% by weight of an oily emollient, and from 2–15% by weight of a foaming anionic surfactant being present in said composition.

9. A method of producing a dyed bath bead composition comprising mixing urea beads with water soluble dye in the form of a dry powder, said urea beads containing absorbed or adsorbed water to pick up said water soluble dye.

4,294,856

PROCESS FOR MANUFACTURE OF ARTIFICIAL MILK REPLACER FOR RAISING INFANT PIGS AND OTHER INFANT ANIMALS

Toyosuke Kinumaki; Takehiko Watanabe, both of Yokohamashi; Kisaburo Sugii, Hasudashi, and Shigeo Iseki, Tokyo, all of Japan, assignors to Tokai Regional Fisheries Research Laboratory, Tokyo, Japan

Filed Jan. 4, 1977, Ser. No. 759,491

Int. Cl.³ A23L 1/33

U.S. Cl. 426—7

5 Claims

1. A process for manufacturing artificial milk replacer for raising infant pigs and other infant animals comprising the steps of:

crushing meat and viscera of fish and shell fish to form a pulp;

digesting said pulp with protease;

heating the digested pulp to inactivate the protease,

removing the solid matter and suspended particles successively by screening, centrifuging, and filtering the digested pulp to obtain a liquid;

defatting the liquid with solvent;

condensing the defatted liquid; and

reducing the condensed liquid to a powder by spray-drying.

4,294,857

DOG FOOD COMPOSITIONS OF IMPROVED PALATABILITY TO DOGS

Mary L. Fuller, Pacific, Mo., assignor to Ralston Purina Company, St. Louis, Mo.

Filed Dec. 5, 1979, Ser. No. 100,600

Int. Cl.³ A23K 1/00

U.S. Cl. 426—99

43 Claims

1. A dog food composition having greater palatability to dogs than the same composition without the palatability enhancer, comprising a nutritionally balanced mixture of proteinaceous and farinaceous ingredients, and an added palatability enhancing 0.0001 to 0.01% by weight amount of linalool.

4,294,858

SELF-SURFACED MEAT PRODUCT MANUFACTURING METHOD AND APPARATUS


Rex E. Moule, 370 Grant Ave., Satellite Beach, Fla. 32937

Filed Mar. 27, 1980, Ser. No. 134,605

Int. Cl.³ A23B 4/00

U.S. Cl. 426—241

19 Claims



1. The method for preparing a self-surfaced congealed meat product comprising storing emulsified product in a container, forcing the emulsified product from the container, forcing the emulsified product through a tube at a predetermined rate against a back pressure, wherein back pressure is created by laterally constraining the product as it moves through the tube, passing microwave energy through the tube and into the product, continuing forcing of the product through the tube and continuing passage of microwave energy through the tube and into the product, thereby congealing the product while the product remains under pressure, heating the tube to temperature sufficient to melt materials on the outer surfaces of the product, conducting heat through the tube to outer surfaces of the product thereby forming a self-skin on the product while the product remains under pressure, subsequently cooling the tube and cooling the outer surfaces of the product while the product continually passes through the tube, thereby solidifying materials in the outer surfaces of the product and completing the forming of a self-skin, and releasing the product from the tube.

4,294,859

PROCESS FOR PACKAGING FOOD

Burton R. Lundquist, Highland Park, Ill., and Thomas Macherione, Mesa, Ariz., assignors to Armour and Company, Phoenix, Ariz.

Continuation of Ser. No. 568,016, Apr. 14, 1975, abandoned.

This application Nov. 15, 1979, Ser. No. 94,380


Int. Cl.³ B65B 31/04

U.S. Cl. 426—410

12 Claims

1. A process for packaging foods comprising passing a unit of food between a top film and a bottom film into an open first chamber, said bottom film having an opening therein to one side of said unit, withdrawing air from said first chamber through a passage which is open at a position below said opening, whereby pressure within said chamber is reduced, sealing said top and bottom films along a line which extends about said unit and encloses said opening, introducing a gas which is substantially free of oxygen through a passage which opens at a position under said opening whereby to pass said gas upwardly through said opening and into the enclosure between said films until the pressure within said chamber is approximately that of the atmosphere surrounding said chamber,

opening said chamber, passing said unit with said enclosure out of said chamber to a position in which a nozzle engages said opening, passing gas which is substantially free of oxygen through said nozzle and into said enclosure to flush said enclosure, passing said unit which has been flushed within said enclosure into an open second chamber, closing said second



chamber, withdrawing gas from said second chamber through an outlet passage which is open at a position under said opening to draw gas through said opening and out of said second chamber through said outlet passage, and sealing said top and bottom films along a line extending about said unit and excluding said opening.

4,294,860

REFRIGERATING MEAT PASTE

Eldon N. Roth, 99 Madera Ct., San Ramon, Calif. 94583


Continuation-in-part of Ser. No. 970,579, Dec. 18, 1978, abandoned, which is a continuation of Ser. No. 849,166, Nov. 7, 1977, abandoned. This application Dec. 14, 1979, Ser. No. 103,498

The portion of the term of this patent subsequent to Jul. 4, 1995, has been disclaimed.

Int. Cl.³ A23B 4/06; A23L 1/31

U.S. Cl. 426—417

19 Claims



17. In a process for treating a protein-containing meat product having a high fat content in order to first recover a substantial portion of the fat and then refrigerate remaining protein-containing solids in order to limit bacterial growth, the steps comprising,

heating the meat product in order to render and separate a substantial portion of the fat from the remaining protein-containing solid material,

forming the remaining solid material into a viscous paste, refrigerating a cylindrical heat transfer surface of a rotating drum to a preselected temperature,

applying the viscous paste onto the heat transfer surface to form a sheet of the viscous paste on the heat transfer surface, the relatively high temperature of the viscous paste and the relatively low temperature of the heat transfer surface being selected so that, upon application of the viscous paste to the heat transfer surface, the relatively high temperature of the viscous paste is capable of causing congealed or frozen liquid at an interface between the heat transfer surface and the viscous paste to initially melt, the relatively low temperature of the heat transfer surface

immediately thereafter causing liquid components at the interface to form a congealed or frozen solid in order to cause adhesion of the viscous paste to the heat transfer surface, compressing the viscous paste sheet in order to improve heat transfer characteristics throughout its thickness, cooling the viscous paste upon the heat transfer surface of the rotating drum, and subsequently removing the viscous paste from the heat transfer surface in a frozen condition.

4,294,861

METHOD OF SEPARATING AND TAKING OUT PULP FROM CITRUS FRUITS


Yasushi Ifuku; Hirofumi Uchiyama, both of Wakayama, and Masayuki Hayashi, Komaki, all of Japan, assignors to Mitsubishi Jukogyo Kabushiki Kaisha, Tokyo and Prefectural Economic Federation of Agricultural Co-operatives, Wakayama, both of, Japan

Continuation of Ser. No. 17,853, Mar. 6, 1979, This application Jun. 27, 1980, Ser. No. 163,554

Int. Cl.³ A23L 2/26

U.S. Cl. 426—475

7 Claims



1. A method of continuously processing citrus fruits to separate the pulp and juice from said fruit which comprises the steps of:

1. dividing the fruit into pieces;
2. Supporting said fruit pieces between an endless chain and a perforated net wherein said net is between said fruit pieces and a plurality of fluid injection nozzles which are directed toward the fruit's exposed pulp;
3. Continuously moving the fruit pieces in a linear path along the net with the endless chain; and
4. injecting fluid from said fluid injection nozzles into said fruit pieces while, said fruit pieces are moving along the net, to separate said pulp and juice from said fruit, said pulp and juice passing through said net.

4,294,862

PROCESS FOR THE PRODUCTION OF PASTRY AND FLAKY PASTRY-LIKE PRODUCTS

Gerhard Wilke, Holderlinweg 1, 6900 Heidelberg, Fed. Rep. of Germany

Continuation-in-part of Ser. No. 76,994, Sep. 19, 1979, which is a continuation of Ser. No. 873,889, Jan. 31, 1978, abandoned.

This application Apr. 10, 1980, Ser. No. 138,849


Int. Cl.³ A21C 9/08; A21D 13/08

U.S. Cl. 426—502

9 Claims

1. A process for producing pastry and flaky pastry-like products from a starting mixture, comprising subjecting said mixture to rollers arranged in series, each succeeding roller moving faster than the preceding roller, while precisely controlling within a range of 1° C. the temperature of said rollers at a low temperature of 3° C. to 20° C., producing a fleece-like film on the last of said rollers, thereafter conducting said

fleece-like film to a belt, including adjusting the ratio of the linear speed of said belt to the rotational speed of said last roller



for imparting a mechanical undulating effect to said fleece-like film, and drying said film.

4,294,863

FLAVORING WITH MIXTURE OF NOR-METHYL JASMONATE AND DIHYDRO-NOR-METHYL JASMONATE

Braja D. Mookherjee, Holmdel; Richard A. Wilson, Westfield; Frederick L. Schmitt, Holmdel, and Manfred H. Vock, Locust, all of N.J., assignors to International Flavors & Fragrances Inc., New York, N.Y.

Division of Ser. No. 106,158, Dec. 21, 1979, abandoned. This application Jun. 5, 1980, Ser. No. 156,688

Int. Cl.³ A23L 1/235

U.S. Cl. 426—538

1 Claim

1. A process for augmenting or enhancing the aroma or taste of a guava flavored foodstuff comprising the step of adding to said foodstuff, from 0.1 up to 0.5 ppm of a mixture of nor-methyl jasmonate and dihydro-nor-methyl jasmonate, the weight ratio of said nor-methyl jasmonate: dihydro-nor-methyl jasmonate being 50:50, produced by the process of hydrogenation of nor-methyl jasmonate in the presence of a hydrogenation catalyst selected from the group of Raney Nickel, Palladium-on-Carbon and Palladium-on-Calcium Carbonate at a temperature in the range of from about 10° C. up to about 100° C.; a hydrogen pressure in the range of from about 5 psig up to about 80 psig, the concentration of catalyst based on the weight of starting material being from about 0.1% up to about 10%.

4,294,864

PREPARATION OF HIGH-RATIO CAKES USING UNTREATED WHEAT FLOUR

Karel Kulp, and William J. Hoover, both of Manhattan, Kans., assignors to The American Institute of Baking, Manhattan, Kans.

Filed Jun. 4, 1979, Ser. No. 45,347

Int. Cl.³ A21D 10/04

U.S. Cl. 426—549

12 Claims

1. A high-ratio cake batter composition, comprising: a quantity of wheat flour, said flour being free of treatment, including chlorination and heat treatment, for rendering the flour usable in high-ratio cake batter; at least about 110% of a sweetening agent; from about 4 to 35% of protein taken from the group consisting of proteins found in rye, soy, cottonseed, peanut, pea, egg whites, milk, whey, wheat protein concentrate and mixtures thereof; and from about 5 to 15% of unmodified starch, said percentage ranges being stated in terms of flour weight basis wherein the quantity of said wheat flour is taken as 100% by weight.

4,294,865

PROCESS FOR PREPARING BEEF FOR USE ON A VERTICAL ROTISSERIE


James H. Coroncos, 11335 Frederick Rd., West Friendship, Md. 21794

Continuation of Ser. No. 53,580, Jun. 28, 1979, abandoned, which is a division of Ser. No. 917,077, Jun. 19, 1978, Pat. No. 4,245,373. This application Oct. 29, 1980, Ser. No. 203,576

Int. Cl.³ A23L 1/31

U.S. Cl. 426—646

10 Claims



1. A process for preparing beef for use on a vertical rotisserie, comprising:

- selecting a quantity of beef to be processed from a beef carcass in a blend between very lean beef and partially fat beef;
- removing a portion of the fat from those partially fat parts of selected beef;
- cutting said beef into small pieces for grinding in a mechanical grinder;
- grinding said small pieces of beef in said mechanical grinder and then reground the ground meat a second time in said mechanical grinder;
- preparing a mixture of additive ingredients;
- spreading out the ground beef on a wide working surface, and then spreading said additive ingredients evenly over the spread out beef;
- kneading the combination of ground beef and additive ingredients until said additive ingredients are thoroughly and evenly mixed throughout the ground beef;
- lubricating interior surfaces of beef unit mold and thereafter successively place lifting disc, sheet of beef unit wrapping material, and beef unit mold on base of beef compressing device centered on mold centering section of beef compressing device, said mold interfacing in locating groove in base of beef compressing device, place measured portion of said combination of ground beef and additive ingredients into said mold;
- operating beef compressing device to move compressor plate of beef compressing device into said beef unit mold to compress said combination of ground beef and additive ingredients mass into said mold and to compress until substantially all entrapped air is squeezed out of said combination of ground beef and additive ingredients, said compressor plate forming a concave spherically accurate depression across the uppermost surface of the compressed mass;
- placing skewer sleeve on mandrel and insert skewer sleeve and mandrel through guide collar and compressor plate aperture and force combined skewer sleeve and mandrel into compressed meat unit;
- removing said mandrel, thereby leaving said skewer sleeve embedded within said compressed meat unit;
- operating said compressing device to remove said compressor plate of said compressing device from said mold, thereby permitting said concave spherically accurate depression across the uppermost surface of the compressed mass to expand to an essentially level configuration;
- removing said mold from compressed meat unit;
- wrapping meat unit and said skewer sleeve with said wrapping material; and

lifting wrapped said meat unit on said lifting disc and place in freezer.

4,294,866

METHOD FOR PRODUCING MONOCELLULAR LAYERS OF CELL-CONTAINING BIOLOGICAL FLUID


Leighton C. Johnson, Edwardsburg, Mich., assignor to Miles Laboratories, Inc., Elkhart, Ind.

Filed Nov. 6, 1980, Ser. No. 204,564

Int. Cl.³ B44D 1/02

U.S. Cl. 427—2

13 Claims



1. A method of producing a monolayer of cell-containing biological fluid on a microscope slide or the like, which method comprises the steps of depositing a sample of the fluid on a surface of a microscope slide or the like, inverting said slide so that the sample-bearing surface thereof faces downwardly, and then spinning said slide about a vertical axis normal to said surface.

4,294,867

METHOD FOR DEVELOPING A PATTERN ON A CERAMIC SUBSTRATE

Premakaran T. Boaz, Livonia, Mich., assignor to Ford Motor Company, Dearborn, Mich.

Filed Aug. 15, 1980, Ser. No. 178,416

Int. Cl.³ B05D 5/12

U.S. Cl. 427—96

6 Claims



1. A method for developing a pattern on a ceramic substrate, the pattern being formed of a material which is electrically conductive, which method comprises the steps of: depositing on the ceramic substrate in a desired pattern a thin layer of a heat fusible material which contains a current conducting base metal in granular form; depositing as an encasing layer over said pattern formed of heat fusible material an oxygen barrier material containing an oxygen getting material, said oxygen barrier material being non-heat fusible and nonreactive with said heat fusible material; heating in an oxygen containing ambient the ceramic substrate along with said heat fusible material and said oxygen barrier material supported on the ceramic substrate, the heating being to a temperature sufficient to permit said heat fusible material to fuse to the ceramic substrate, said oxygen barrier material protecting said granular, current conducting base metal of said fusible material from oxidation.

tion by physically blocking out oxygen and by chemically providing an oxygen getting material which will react with any oxygen which does manage to penetrate into said oxygen barrier material;
cooling the ceramic substrate along with the now fused heat fusible material and any remaining oxygen barrier material supported on the ceramic substrate to room temperature; and
removing any of said remaining oxygen barrier material from the ceramic substrate.

4,294,868

PROCESS FOR CONTINUOUSLY DEPOSITING A LAYER OF A SOLID MATERIAL ON THE SURFACE OF A SUBSTRATE HEATED TO A HIGH TEMPERATURE
Reinhard Kalbskopf, Onex, and Otto Baumberger, Carouge, both of Switzerland, assignors to Società Italiana Vetro-Siv-S.p.A., San Salvo, Italy


Filed Jan. 31, 1980, Ser. No. 117,086

Claims priority, application Switzerland, Feb. 14, 1979, 1412/79

Int. Cl.³ B05D 1/34; C03C 17/245

U.S. Cl. 427—109

11 Claims



1. A process for continuously depositing on the surface of a substrate heated to high temperature a layer of a solid material resulting from the reaction of at least two reactants selected from gaseous reactants and reactants diluted in a gas, which process comprises forming discrete laminar streams of each reactant and projecting these streams on said substrate by bringing the streams together in reciprocal tangential contact, while effecting relative displacement of said streams and the substrate in such a manner that said streams are applied successively to different regions of the substrate, characterised in that each said stream has the form of rectilinear gas curtains, the transverse profile of each said stream converging towards an imaginary edge common to all the said streams, that these curtains and the substrate are disposed in such a manner that said edge is substantially in the plane of the said surface of the substrate, that the said substrate and said curtains are displaced relative to each other in a direction substantially perpendicular to the said common edge in such a manner that the said edge remains substantially in the plane of the said surface of the substrate, that the gases evolving from the reaction which results from the impact of said stream on the substrate are compelled to flow above a predetermined portion of this substrate extending on each side of said edge, and that these gases are evacuated at the extremity of said substrate portion located opposite the said imaginary common edge of said curtains.

4,294,869

METHOD FOR COATING PIPELINE

Christian C. Bassompierre-Sewrin, Embrun, France, assignor to Martech International, Inc., Houston, Tex.

Filed Sep. 26, 1979, Ser. No. 79,181

Int. Cl.³ B05D 3/12


U.S. Cl. 427—177

17 Claims

1. In a method for coating an elongate pipeline prior to the

laying for inhibiting corrosion wear on the interior thereof comprising the steps of:

reeling the pipeline onto a spool,
installing a pig into the pipeline adjacent a first end thereof and closing that end and also the second end,
introducing coating material into the pipeline between the pig and the second end in sufficient quantity to coat the interior of the pipeline to a predetermined thickness,
rotating the pipeline on its reel in a first direction, and



introducing a sufficient air pressure into the pipeline between the pig and said first end to cause the pig to move through the pipeline in a direction opposite to the direction of rotation, thus causing the interior of the pipeline to be coated with the coating material that is caused to move therethroughout by gravitational force as the pipeline rotates, the pig moving to smooth the coated pipeline surface as it traverses the walls thereof.

4,294,870

METHODS AND DEVICE FOR CLADDING ELONGATED OBJECTS SUCH AS WIRES AND THE LIKE WITH POWDERED MATERIAL

Walter Hufnagl, Loininetstr. 9, 8 Munich, Fed. Rep. of Germany, and Peter Kotaucaek, We. Spertlitz 58, 7030 Wien, Austria


Division of Ser. No. 958,882, Nov. 8, 1978. This application Mar. 31, 1980, Ser. No. 135,623

Claims priority, application Fed. Rep. of Germany, Nov. 10, 1977, 2750369

Int. Cl.³ B05D 3/12

U.S. Cl. 427—189

3 Claims



1. A method of cladding elongated objects such as wires and the like with a powdered material, comprising the steps of sprinkling the object to be clad with the powdered material by passing the object through a storage container; continuously feeding the object in its axial direction through a rotary internal worm conveyor having an outlet provided with a nozzle for continuously applying a layer of powdered material onto the surface of the advancing object during the feeding operation; and roll pressing said applied layer to the surface of the object in its path through a set of pressing rollers, the roll pressing being applied to said layer in a direction forming with said axial direction an acute angle to thereby obtain said elongated object the compacted powdered layer with bonded portions having spiral-like form and overlapping each other.

4,294,871

METHOD FOR DEPOSITING A LAYER ON THE INSIDE OF CAVITIES OF A WORK PIECE

Konrad Hieber, and Manfred Stolz, both of Munich, Fed. Rep. of Germany, assignors to Siemens Aktiengesellschaft, Munich, Fed. Rep. of Germany

Continuation of Ser. No. 897,349, Apr. 18, 1978, abandoned.


This application Aug. 29, 1979, Ser. No. 71,685

Claims priority, application Fed. Rep. of Germany, Apr. 26, 1977, 2718518

Int. Cl.³ C23C 11/00

U.S. Cl. 427—237

8 Claims



1. A method for depositing a layer of material of substantially uniform thickness on the inside of cavities of a workpiece having at least two internal cavities of differing inside diameter by chemical deposition from the gaseous phase, comprising heating the parts of said workpiece to be provided with said layer; conducting a gas stream containing the components of the material to be deposited along the surface of said parts in a substantially laminar flow by provision of a flow profiler at least approximately fitted to the shape of the workpiece and precipitation of said material from the gaseous phase at a pressure of less than 10^4 N/m², whereby said flow profiler is designed and fitted to said workpiece so as to cause said gas stream to flow uniformly past the parts of said workpiece and to cause the resistance to flow of said gas stream from each of said individual internal cavities to be of approximately the same magnitude.

4,294,872

METHOD AND AN APPARATUS FOR COATING A WEB WITH A COATING COMPOSITION

Mats O. Kullander, Sjöfle, Sweden, assignor to Billerud Udeholm AB, Sjöfle, Sweden


Filed Mar. 21, 1980, Ser. No. 132,792

Claims priority, application Sweden, Sep. 22, 1978, 7809998

Int. Cl.³ B05D 3/12; B05C 3/02, 3/12

U.S. Cl. 427—358

13 Claims



1. A method of coating a continuously conveyed web with a coating composition, comprising the steps of:
applying a coating composition in excess to a first zone of the continuously conveyed web;
providing a backing support for one of the first zone and a second, uncoated zone of the web; and
deflecting the other of the first and second zones of the web into contact with said one zone without providing a backing support for said other zone, to thereby form a contact

zone such that the uncoated second zone of the web wipes excess coating composition from the coated first zone of the web.

4,294,873

MANUFACTURE OF PAPER HAVING A HIGH DRY STRENGTH AND A LOW WET STRENGTH

Juergen Hartmann, Ludwigshafen; Joachim Stedefeder, Lampertheim; Walter Denzinger, and Sigberg Pfohl, both of Speyer, all of Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Ludwigshafen, Fed. Rep. of Germany

Filed Jan. 3, 1980, Ser. No. 109,315

Claims priority, application Fed. Rep. of Germany, Jan. 27, 1979, 2903218

Int. Cl.³ B05D 3/02; B32B 23/08, 27/10

U.S. Cl. 427—391

5 Claims

1. A process for the manufacture of paper having a high dry strength and a low wet strength which comprises treating the surface of paper with an aqueous solution of a water-soluble alkaline earth metal salt or a mixture of a water-soluble alkaline earth metal salt and an alkali metal salt, the ratio of alkaline earth metal salts to alkali metal salts being 30-50:70-50, of a polymer selected from the group consisting of homopolymer of acrylic acid, homopolymer of methacrylic acid, acrylic acid/acrylamide copolymer, acrylic acid/acrylonitrile copolymer, acrylic acid/methacrylic acid/acrylamide copolymer and acrylic acid/acrylamide/methacrylamide copolymer; which has a viscosity of from 5 to 100 mPas (measured in a Brookfield viscometer at 20 revolutions per minute) in 2% by wt. strength aqueous solution at 20° C., and drying the paper.

4,294,874

SILICATE-CONTAINING LATEX COATING COMPOSITIONS

Mark J. Howe, Pittsburgh, Pa., assignor to PPG Industries, Inc., Pittsburgh, Pa.

Filed Jul. 23, 1979, Ser. No. 59,825

Int. Cl.³ B05D 1/18, 3/02

U.S. Cl. 427—393

9 Claims

1. A method of filling wood or a wood-like product, comprising the steps of:

(a) applying a latex composition to the wood or wood-like product wherein the composition has a film-forming solids content of at least about 2.5 percent and consists essentially of:
(1) an alkali metal silicate, and
(2) a synthetic polymeric latex selected from the group consisting of styrene-butadiene copolymers, vinyl chloride-alkylene copolymers and mixtures thereof,
wherein, as film-forming solids, the silicate is present in an amount of from about 15 percent to about 40 percent and the latex is present in an amount of from about 60 percent to about 85 percent; and
(b) drying the coated product of step (a) so as to remove water and cure the composition to produce the filled wood or wood-like product.

4,294,875

INSULATION PANEL

Arthur G. Schramm, 8780 E. McKellips Rd., Space 125, Scottsdale, Ariz. 85257

Continuation-in-part of Ser. No. 937,266, Aug. 31, 1978, abandoned. This application Apr. 3, 1979, Ser. No. 26,668


Int. Cl.³ B32B 3/12

U.S. Cl. 428—72

4 Claims

1. The thermal insulation structure comprising:
a front sheet, a back sheet, a pair of side sheets, a top sheet and a bottom sheet forming an envelope defining a space which is substantially a rectangular parallelepiped, said front, back and side sheets having a length and a width, the length of said front, back and side sheets being substan-

tially equal, the width of the front and back sheets being substantially greater than the width of the side sheets; substantially rigid panel means having edges mounted in said space for dividing said space into a plurality of substantially regular equilateral triangular prismatic closed compartments having lateral edges defined by said rigid panel



means, edges of said rigid panel means defining lateral edges of said compartments and being secured to the front and back sheets of said envelope, said lateral edges of the compartments being substantially perpendicular to the side sheets; and a plurality of individual granules of a cellulose material substantially filling said compartments.

4,294,876


TUFTED MATERIAL HAVING A LAMINATED FILM PRIMARY TUFTING SUBSTRATE

James B. Camden, Newcastle Upon Tyne, England, and Kenneth D. Vinson, Bartlett, Tenn., assignors to The Buckeye Cellulose Corporation, Cincinnati, Ohio

Continuation-in-part of Ser. No. 34,059, Apr. 27, 1979, abandoned. This application May 1, 1980, Ser. No. 145,414
Int. Cl.³ B32B 27/16

U.S. Cl. 428—95

7 Claims



1. A tufted material comprising:

- (a) tuft strand elements arranged in substantially orthogonally related sets of rows, and
- (b) a primary tufting substrate having needle holes there-through and through which said tuft strand elements extend, said substrate comprising a bonded laminate having a plurality of layers of nonwoven materials, including two oppositely disposed surface layers, said substrate comprising first and second layers of uniaxially molecularly oriented polymeric material of substantially uniform thickness, each of said first and second layers having been drawn sufficiently to induce splitting parallel to its direction of molecular orientation upon penetration, said layers being split on both sides of each of the needle holes whereby each pair of adjacent rows of tuft portions in a direction which is parallel to the molecular orientation of one of said layers defines an elongate segment of primary tufting substrate in the layer, said segment being substan-

tially uninterrupted between the adjacent pair of rows of tuft portions,

- (1) said first layer located intermediate said surface layers and having the direction of molecular orientation thereof parallel to the tufting machine direction,
- (2) said second layer having the direction of molecular orientation substantially at right angles to that of said first layer,
- (3) said surface layers of said bonded laminate being made of materials other than uniaxially molecularly oriented polymeric material having a direction of molecular orientation which is parallel to the tufting machine direction.

4,294,877

EPOXY IMIDE COMPOSITIONS

William F. Graham, Wilmington, Del., assignor to E. I. Du Pont de Nemours and Company, Wilmington, Del.


Division of Ser. No. 27,444, Apr. 5, 1979, which is a continuation-in-part of Ser. No. 848,638, Nov. 4, 1977, abandoned. This application Jun. 6, 1980, Ser. No. 157,454
Int. Cl.³ C08L 63/00; B32B 15/14, 27/04

U.S. Cl. 428—209

18 Claims


1. A product comprising a fibrous substrate impregnated with a composition comprising 20–80% by weight of a reaction product and 20–80% of a nonamide solvent for the reaction product having a dispersion solubility parameter of 7.2–10.5, a polar solubility parameter of 3–9.5 and a hydrogen bonding solubility parameter of 0–5.5; wherein the reaction product consists essentially of

- (a) an epoxy resin of the formula




wherein R is an alkylene group of 1–4 carbon atoms, n is a positive integer; and the resin having an epoxide equivalent of about 150–1000; and

- (b) a bismaleimide of the formula



wherein (a) and (b) are reacted at 115°–135° C. for about 0.5–2 hours and subsequently contacting the product of (a) and (b) with

- (c) a diamine of the formula



reaction product; wherein the molar ratio of bismaleimide to diamine is about 0.6–0.8.

4,294,878

PROCESS FOR RAPID ANNEALING OF REFRACTORY FIBER BODIES AND LAMINATED BODY PRODUCED BY PROCESS



Richard N. Cunningham, Littleton, Colo., and Romain E. Loeffler, deceased, late of Littleton, Colo. (by Carolyn R. Loeffler, personal representative), assignors to Johns-Manville Corporation, Denver, Colo.

Filed Sep. 7, 1979, Ser. No. 73,412

Int. Cl.³ B32B 7/02

U.S. Cl. 428—212

15 Claims



1. A process for annealing of a body of refractory fiber which comprises passing air at a temperature in the range of from about 750° F. to about 1400° F. through said body for a period of from about 5 to about 200 seconds while maintaining said body with a predetermined dimension in the direction of air flow.

4,294,879

FIBROUS INSULATION MAT WITH ANTI-PUNKING BINDER SYSTEM

Patricia A. McHenry, Denver, Colo., assignor to Johns-Manville Corporation, Denver, Colo.

Filed Dec. 4, 1980, Ser. No. 212,928

Int. Cl.³ D04H 1/58

U.S. Cl. 428—288

5 Claims

1. Fibrous insulation comprising a mass of glass fibers bonded with a binder system in an amount which lies between about 1 to 20% loss-on-ignition, said binder comprising a water soluble phenolicformaldehyde resin mixed with a water soluble urea-formaldehyde resin, the urea-formaldehyde resin content in said binder system comprising an amount of about 5 to 50% by weight of the binder solids content, said urea-formaldehyde resin comprising about 59% urea, about 19% formaldehyde and about 22% water by weight.

4,294,880

FOAMED POLYURETHANE ARTICLES WITH SKIN AND A METHOD FOR PRODUCING THE SAME

Masazo Nishida, Toyota, Japan, assignor to The Toyo Rubber Industry Co., Ltd., Osaka, Japan

Filed Aug. 10, 1979, Ser. No. 65,748

Claims priority, application Japan, Aug. 11, 1978, 53/98446

Int. Cl.³ B29D 27/04

U.S. Cl. 428—315

7 Claims

1. A method of producing a molded polyurethane article having a foamed polyurethane core member and a polyurethane surface skin layer formed as an integral unit, consisting essentially of the steps of spraying the inner surface of a foam-

ing mold with a polyurethane composition to prepare a surface skin layer in the mold, pouring a foamable polyurethane solution into said mold and causing the polyurethane to foam and cure, thereby forming said integral unit, wherein the polyurethane composition used for the polyurethane surface skin layer is a two-part system consisting of (1) an organic polyisocyanate, and (2) polyols mixed with an aliphatic or equivalent aliphatic aromatic primary diamine in which the amino groups are attached to an aliphatic side chain, whereby in advance of the formation of the surface skin layer, an initial reaction product of said organic polyisocyanate and said aliphatic or equivalent aliphatic aromatic primary diamine having thixotropic properties is caused to be formed on the inner surface of the foaming mold; said reaction product being formed during the spray operation in which said two component polyurethane system is sprayed from a spray-coating apparatus used for two-component spraying and whereby the reaction product is formed in the mixing chamber.

7. A molded polyurethane article having an inner foamed polyurethane core member and a polyurethane surface skin layer of a uniform thickness produced by the method of claims 1 or 2.

4,294,881

COATED GLASS ARTICLE

John H. Meyer, Milford, and Salvatore Guerra, Detroit, both of Mich., assignors to Ford Motor Company, Dearborn, Mich.

Filed Jul. 2, 1980, Ser. No. 165,427

Int. Cl.³ B32B 17/06, 27/20, 27/30

U.S. Cl. 428—334

12 Claims

1. As an article of manufacture having transmission capabilities above 70%;
- a glass substrate having at least first and second surfaces;
- a coating on at least a portion of one surface of said glass substrate, said coating having a thickness in a range from about 70 angstroms to about 120 angstroms, said coating consisting, on a mixed metal oxide weight basis, of about 60 to 70% cobalt, 12 to 18% chromium, and 16 to 24% iron; and
- a protective layer over said coating.
5. As an article of manufacture having transmission capabilities above 70%;
- a glass substrate having at least first and second surfaces
- a coating on at least a portion of one surface of said glass substrate, said coating having a thickness in a range from about 75 angstroms to about 110 angstroms, said coating consisting, on a mixed metal oxide weight basis, of about 63 to 68% cobalt, 14 to 16% chromium, and 17 to 20% iron; and
- a protective layer over said coating.
9. As an article of manufacture having transmission capabilities above 70%;
- a glass substrate having at least first and second surfaces;
- a coating on at least a portion of one surface of said glass substrate, said coating having a thickness in a range from about 80 angstroms to about 100 angstroms, said coating consisting, on a mixed metal oxide weight basis, of about 65 to 66% cobalt, 14.5 to 15.5% chromium, and 18.5 to 19.5% iron; and
- a protective layer over said coating.

4,294,882

HEAT-SEALABLE ANTISTATIC POLYPROPYLENE FILMS

William J. Andrews, Taunton; David J. C. Espley, and William J. M. Philpott, both of Bridgewater, all of England, assignors to British Cellophane Limited, Somerset, England
Filed Aug. 23, 1979, Ser. No. 69,089

Claims priority, application United Kingdom, Sep. 19, 1978, 37295/78

Int. Cl.³ B32B 27/08; B29C 19/00; B32B 27/00

U.S. Cl. 428—349 17 Claims

1. A method for the manufacture of an oriented heat-sealable antistatic polypropylene film comprising applying to one or both sides of a base polypropylene film a layer of a heat-sealable olefinic polymer capable of forming a heat-seal below 140° C., the olefinic polymer layer containing between 0.2 and 10% by weight of an antistatic agent comprising an anionic hydrocarbyl sulphonate, and stretching the combination in one or more directions under stretch orientatable conditions.

12. An oriented heat-sealable antistatic polypropylene film comprising a base polypropylene film having on one or both surfaces a layer of an olefinic polymer capable of forming a heat-seal below 140° C., the olefinic polymer layer containing between 0.2 and 10% by weight of an antistatic agent comprising an anionic hydrocarbyl sulphonate.

4,294,883

STAPLE FIBER, FINISH THEREFOR AND PROCESS FOR USE OF SAME

Roland L. Hawkins, Spartanburg, S.C., assignor to Hoechst Fibers Industries, Div. of American Hoechst Corporation, Spartanburg, S.C.

Continuation-in-part of Ser. No. 715,719, Aug. 19, 1976, Pat. No. 4,179,543. This application Aug. 17, 1979, Ser. No. 67,294. The portion of the term of this patent subsequent to Dec. 18, 1996, has been disclaimed.

Int. Cl.³ D02G 3/00

U.S. Cl. 428—361 7 Claims

1. A synthetic polymeric staple fiber, said fiber having a length in a range of from about ¼ to about 3 inches and having a finish thereon comprising:

- (a) an ethoxylated primary emulsifier containing at least five moles of ethylene oxide and having a surface tension of at least 30 dynes per centimeter in a 0.10 weight percent aqueous solution of same at about 25 degrees Centigrade; p0 (b) a lubricant for said fiber;
- (c) a secondary emulsifier for said lubricant, said secondary emulsifier being compatible with said primary emulsifier; and
- (d) an anionic constituent, said finish being present on the fiber in an amount of at least 0.1 percent based on fiber weight and exhibiting a low foaming propensity and being conducive to good fiber bondability in the presence of a chemical binder.

4,294,884

ACRYLIC FIBER HAVING IMPROVED BASIC DYEABILITY AND METHOD FOR MAKING THE SAME

Hartwig C. Bach, and Helmuth E. Hinderer, both of Pensacola, Fla., assignors to Monsanto Company, St. Louis, Mo.

Filed Jun. 6, 1980, Ser. No. 157,128

Int. Cl.³ D02G 3/00

U.S. Cl. 428—364 3 Claims

1. A wet spun fiber composed of an acrylic polymer formed from monomers at least one of which is a sulfonated vinyl monomer, wherein said polymer contains 0.5 to 25 weight percent of an additive polymer dispersed therein, said additive polymer being selected from the group consisting of cellulose triacetate, polymethyl methacrylate, polyvinyl chloride, a polyamide of hexamethylenediamine with 1,1,3-trimethyl-5-carboxy-3-(p-carboxyphenyl) indane and a polyamide of hexamethylenediamine with isophthalic acid.

4,294,885

SURFACE-MODIFIED PIGMENT OF NATURAL KAOLIN MATERIAL AND A PROCESS OF PRODUCING SAME

Olof Sundén, Lidingö, Sweden, assignor to EKA AB, Surte, Sweden

Filed May 14, 1980, Ser. No. 149,769

Claims priority, application Sweden, Jun. 1, 1979, 7904814 Int. Cl.³ B32B 5/16, 9/00

U.S. Cl. 428—404 5 Claims

1. A surface-modified pigment of natural kaolin material intended for use as a pigment in paper and coats of paint, characterised in that it has on its pigment particles precipitated primary and secondary layers bonded to one another by hydrogen or ion bonding, the primary layer consisting of anionic $Al_2O_3-SiO_2$ hydrate gel having a molar ratio of $SiO_2:Al_2O_3$ of from 3 to 30, preferably from 8 to 15, and being present in an amount corresponding to from 2 to 15% by weight of SiO_2 , based upon the original quantity of kaolin material, and the secondary layer consisting of a polymeric binder which is included in a quantity of at least 2% by weight, based upon the original quantity of kaolin material.

4,294,886

TRANSPARENCIES PRODUCED FROM EPOXY RESINS CURED WITH ADDUCTS OF TRIMETHOXYBOROXINE AND BENZYL ALCOHOL

John R. Uram, Jr., Glendale, Ariz., assignor to Goodyear Aerospace Corporation, Akron, Ohio

Filed Aug. 28, 1979, Ser. No. 70,390

Int. Cl.³ C08G 59/40

U.S. Cl. 428—412 11 Claims

1. A transparent composition having resistance to intense heat, comprising:

- a transparent blend having (a) from 80 parts to about 100 parts of an epoxy resin;
- (b) from 7.5 parts to about 30 parts of trimethoxyboroxine; and
- (c) from 1 part to about 10 parts of a phenyl substituted alkyl alcohol.

4,294,887

PRODUCTION OF COATING FILMS FROM AUTOXIDIZABLE MATERIALS AND COATING COMPOSITIONS CAPABLE OF PRODUCING SUCH FILMS

Peter F. Nicks, Maidenhead, England, assignor to Imperial Chemical Industries Limited, London, England

Filed Sep. 18, 1979, Ser. No. 76,726

Claims priority, application United Kingdom, Sep. 27, 1978, 38332/78

Int. Cl.³ B32B 27/40

U.S. Cl. 428—423.1 11 Claims

1. A method of preparing a cured coating film by applying to a substrate a liquid coating which is free from metal catalyst and which comprises

- (a) a film-forming material comprising moieties of an ethylenically unsaturated fatty acid containing at least two ethylenically unsaturated groups, said film-forming material being selected from the group consisting of oil-modified alkyd resins, oil-modified addition polymers of ethylenically unsaturated monomers, epoxy esters of ethylenically unsaturated fatty acids, oil-modified polyurethane oils and oil-modified polyurethane alkyds, and
 - (b) an acid which is fully dissociated when in the presence of water, said acid being selected from the group consisting of a sulphonic acid, hydrochloric acid and sulphuric acid, and thereafter exposing the coating to oxygen until fully cured, the acid functioning to catalyze autoxidation of component (a).
10. A cured coating film prepared by the method of claim 1, said film being supported on a substrate.

4,294,888

RELEASE MEDIUM HAVING TRANSFERRABLE GLUE LINES


Christo Antonio, Princeton, and Wyman F. Uhl, Sterling, both of Mass., assignors to Litton Business Systems, Inc., New York, N.Y.

Continuation of Ser. No. 922,191, Jul. 5, 1978, abandoned, which is a continuation of Ser. No. 780,850, Mar. 24, 1977, abandoned, which is a division of Ser. No. 521,054, Nov. 5, 1974, Pat. No. 4,030,955. This application Apr. 24, 1979, Ser. No. 32,759

Int. Cl.³ B32B 27/08, 27/30

U.S. Cl. 428—451

4 Claims



1. A release medium adapted to separate laminates during heat and pressure consolidation comprising a self-sustaining film material which will not soften or become tacky during said heat and pressure consolidation, said film material having its opposite surfaces coated with a glue adherable layer containing at least 40% polyvinyl alcohol on a dry solid basis and positionable between the backmost surfaces of the laminates, said polyvinyl alcohol being water insolubilized, said glue adherable layers being transferable to the backmost surfaces of said laminates during consolidation of said laminates.

4,294,889

RESIN COMPOSITIONS AND HEAT-SEALABLE COMPOSITE BIAXIALLY-STRETCHED FILMS


Fukashi Hashimoto, Yokkaichi, Japan, assignor to Mitsubishi Petrochemical Co., Ltd., Tokyo, Japan

Filed Mar. 28, 1979, Ser. No. 24,673

Int. Cl.³ B32B 27/08

U.S. Cl. 428—515

9 Claims



1. A biaxially-stretched polypropylene composite film comprising a biaxially-stretched film of a crystalline polypropylene and a monoaxially-stretched or biaxially-stretched film of a resin composition bonded in laminated state to at least one surface of the crystalline polypropylene film, the resin composition comprising:

- from 96 to 50 percent of a propylene copolymer (a), which is a member selected from the group consisting of (a₁) ethylene-propylene random copolymers each of an ethylene component content of 1.5 to 10 percent, (a₂) ethylene-propylene-butene-1 random copolymers each of an ethylene component content of 0 to 5 percent, a butene-1 component content of 8 to 30 percent, and a propylene component content of 92 to 65 percent, and
- from 3 to 30 percent of a polybutene-1 (b); and
- from 1 to 20 percent of an ethylene-propylene-butene-1 random copolymer (c) of a propylene component content of 0.5 to 3 percent and a butene-1 component

content of 2 to 10 percent, of a density of 0.915 to 0.935 g./cm.³, and of a melting point of 115° to 125° C., all quantities expressed in percent being by weight, and in which the melt flow rate of said propylene copolymer (a) is about 1 to 30 g./10 min., the melt flow rate of said polybutene-1 (b) is about 5 to 50 g./10 min. and the melt flow rate of said ethylene-propylene-butene-1 copolymer (c) is about 2 to 50 g./10 min., with the proviso that at 180°–300° C. the melt flow rate of propylene copolymer (a) is equal to or less than those of polybutene-1 (b) and ethylene copolymer (c).

4,294,890


METHOD FOR PREVENTING REFLECTION

Susumu Ito, Tokyo; Noboru Sugawara, Sagami, and Sayoko Amano, Kawasaki, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan

Continuation of Ser. No. 15,655, Feb. 27, 1979, abandoned, which is a continuation of Ser. No. 856,734, Dec. 1, 1977, abandoned, which is a continuation of Ser. No. 641,265, Dec. 16, 1975, abandoned. This application Dec. 10, 1979, Ser. No. 102,312

Claims priority, application Japan, Dec. 23, 1974, 49/147843 Int. Cl.³ B32B 15/20, 15/04; C23C 13/02, 13/04

U.S. Cl. 428—641 7 Claims



1. A coating having anti-reflection characteristics within a visible range, comprising: an aluminum layer vapor-deposited on a substrate to a film thickness preventing the transmission of light there-through under a pressure of 2×10^{-5} Torr. or below, and a silicon layer having a film thickness of the order of 300 Å vapor-deposited on said aluminum layer under a pressure of 2×10^{-5} Torr. or below.

4,294,891

INTERMITTENTLY REFUELABLE IMPLANTABLE BIO-OXIDANT FUEL CELL


Shang J. Yao; Hui Y. Sun Yao, both of Upper St. Clair, and Sidney K. Wolfson, Jr., Fox Chapel, all of Pa., assignors to The Montefiore Hospital Association of Western Pennsylvania, Pittsburgh, Pa.

Filed Mar. 12, 1980, Ser. No. 129,709

Int. Cl.³ H01M 8/16

U.S. Cl. 429—2

14 Claims



1. A biologically acceptable, implantable, bio-oxidant fuel cell comprising in operative combination: (a) at least one anode assembly;

- (b) at least one cathode assembly;
- (c) a fuel/electrolyte chamber defined between said anode and said cathode assemblies for receiving an externally supplied fuel;
- (d) an electrical lead attached to each of said anode and cathode assembly to provide electrical output to a prothesis;
- (e) a biologically acceptable, oxygen permeable membrane disposed substantially in contact with said cathode assembly so that said membrane lies between said cathode and body tissue, said membrane being adapted to permit endogenous tissue O_2 as a biological oxidant to diffuse into said cell from said body tissue;
- (f) a fuel/electrolyte composition disposed in said fuel/electrolyte chamber; and
- (g) said fuel/electrolyte composition having a high concentration ratio of fuel to endogenous tissue O_2 diffusing through said membrane into said cell.


4,294,892

METHOD FOR THE OPERATION OF A FUEL CELL
 Marinus Alfenaar, Schinnen, Netherlands, assignor to Electrochemische Energieconversie, N.V., Mol, Belgium
 Filed May 1, 1980, Ser. No. 145,843
 Claims priority, application Netherlands, May 2, 1979, 7903426

Int. Cl.³ H01M 8/04

U.S. Cl. 429—13

12 Claims



1. A method for operating a fuel cell with a porous gas diffusion electrode to which an oxidizing or reducing gas is fed, wherein the concentration level of the oxidizing or reducing gas, calculated as molecular oxygen or hydrogen respectively, in the gas phase in situ of the electrode in question is temporarily brought to a reduced level the terminal voltage being reduced to below 10% of its original value, the overall pressure of the gas phase in situ of this electrode being substantially maintained and the power output is continued for at least the period during which the concentration level is reduced.

4,294,893


GRAPHITE-RESIN COMPOSITE ELECTRODE STRUCTURE, AND A PROCESS FOR ITS MANUFACTURE

Giuliano Iemmi, Turin, and Diego Macerata, Pinerolo, both of Italy, assignors to Centro Ricerche Fiat S.p.A., Orbassano, Italy

Filed May 21, 1979, Ser. No. 41,050
 Int. Cl.³ H01M 4/96, 4/62; C25B 11/12

U.S. Cl. 429—42

2 Claims



1. A press-formed fuel cell electrode comprising an electrically conductive porous plate portion contoured by an electrically

cally conductive compact carrier frame portion integral with said plate portion, the structure of each of said portions being formed by resin-bonded particles of a conductive carbon, the bonding resin being a cross-linked polyimide resin in an amount of 15–50% while the carbon particles are correspondingly in an amount of 85–50% on the joint weight of the carbon particles and resin, and wherein the porous plate portion has been obtained by a process comprising pressing at cross-linking temperature a particulate mixture of (a) particles of a prepolymer of said polyimide resin filled with said carbon particles and (ii) particles of a pore-forming agent removable by volatilization or leaching, one face of the porous plate portion being coated with sintered particles of polytetrafluoroethylene rendering said face hydrophobic.

4,294,894

TRANSPARENT TOOTHPASTE HAVING A MEDICINAL ACTION AND PROCESS FOR ITS PRODUCTION
 Enzo Vellucci, Rome, Italy, assignor to E. R. Squibb & Sons, Inc., Princeton, N.J.

Continuation of Ser. No. 3,565, Jan. 15, 1979, abandoned. This application Feb. 15, 1980, Ser. No. 121,933
 Int. Cl.³ A61K 9/16, 9/18, 7/22; B65D 81/24

U.S. Cl. 424—49

14 Claims

1. A process for the preparation of a toothpaste which comprises:

- (a) preparing under heat a gelled basic mass comprising a gel, and a polyglycolic vehicle;
- (b) adding to said gelled mass, while heating, de-ionized water containing buffer and then sodium chloride as a saline electrolyte in amounts ranging from 0.5 to 20% by weight of the entire toothpaste composition;
- (c) cooling said mixture from (b) and adding thereto de-ionized water, silica thickening compound and amorphous silica gel, which is in finely divided form and has an average particle size ranging from about 2 to about 20 microns and a surficial development of within the range of from 600 to 800 m²/g, in amounts ranging from 5 to 50% by weight with respect to the entire toothpaste composition, and stirring until a uniform single phase is attained, and
- (d) cooling to room temperature, deaerating until a uniform transparent paste is free from clouds and bubbles to obtain said toothpaste and packaging it in unlined aluminum tubes.

4,294,895

BATTERY VENT CAP FOR PREVENTING ELECTROLYTE FOAM ESCAPE


Larry P. Atkins, Daleville, Ind., assignor to General Motors Corporation, Detroit, Mich.

Filed Jul. 10, 1980, Ser. No. 168,276

Int. Cl.³ H01M 2/12

U.S. Cl. 429—84

5 Claims



1. A vent device for releasing gases formed in a battery container while preventing the escape of electrolyte that may be carried with the gas in the form of foam, said vent device comprising:

a housing comprising a cylindrical side wall and transverse

walls defining a compartment, said housing being adapted to be vertically mounted in the container such that the then lower transverse wall lies inside the container, a gas passage adapted for venting the compartment to outside the container, at least one opening in the housing side wall spaced apart from the lower transverse wall and adapted to connect the compartment to inside the container for admitting gases and foam, and a reservoir within the compartment between the opening and the lower end wall and containing an antifoam agent, said reservoir, gas passage and opening defining a gas-foam flow path through the compartment such that foam entering the compartment through the opening spills into the reservoir whereupon the agent dissipates the foam and foam-free gas flows to the gas passage unimpeded by the agent.

4,294,896

BATTERY WITH FLAME INTERCEPTING FILTER AND GROUNDING LEAD

Masahiro Ueda, Toyota, Japan, assignor to Toyota Jidosha Kogyo Kabushiki Kaisha, Toyota, Japan


Filed Aug. 8, 1980, Ser. No. 176,349

Claims priority, application Japan, Aug. 29, 1979, 54-119576[U]

Int. Cl.³ H01M 2/12

U.S. Cl. 429—86

9 Claims



- 1. An electrical storage battery, comprising: a battery casing formed with a gas venting exhaust passage which communicates the interior of the battery casing to the exterior thereof;
- a flame intercepting filter located at an intermediate portion of the gas venting exhaust passage and extending thereacross so as to define a passage portion on the exterior side of the flame intercepting filter;
- and a means for substantially electrically grounding in the vicinity of a part of said exterior side passage portion.

4,294,897

SEALING OF CERAMIC ELECTROLYTE TUBES IN ELECTROCHEMICAL CELLS

Peter J. Bindin, Runcorn, England, assignor to Chloride Silent Power Limited, London, England

Division of Ser. No. 902,528, May 3, 1978, Pat. No. 4,215,466.

This application Mar. 25, 1980, Ser. No. 133,723

Claims priority, application United Kingdom, May 5, 1977, 18870/77


Int. Cl.³ H01M 2/08

U.S. Cl. 429—104

12 Claims

1. An electrochemical cell having a ceramic electrolyte tube closed at one end and separating anodic and cathodic reactants, wherein an annular element of ceramic material is sealed with glass to the open end of the electrolyte tube, said annular element having shaped external surfaces such that, over these surfaces, the diameter of the element decreases from a maximum diameter intermediate the ends of the element to minimum diameters at or near the respective ends of the element, soft metal over said shaped surfaces and outer metal elements around said shaped surfaces and secured thereto by the soft

metal, one of said metal elements forming part of a housing enclosing the electrolyte tube and the other of the metal ele-



ments forming a top closure extending at least partly across the top of said annular ceramic element.

4,294,898

SOLID STATE BATTERY


Allan M. Hartstein, Chappaqua, N.Y., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed May 5, 1980, Ser. No. 146,965

Int. Cl.³ H01M 6/18

U.S. Cl. 429—104

8 Claims



1. A solid state rechargeable battery comprising at least three layers including a first layer consisting essentially of an alkali metal-containing electrode in the solid state, a second solid electrolyte layer adjacent said first layer, and a third layer adjacent said second solid electrolyte layer consisting essentially of intercalation graphite adapted to accept ions of the alkali metal from the first layer, wherein said third layer is free from materials which interface to an undesirable extent with the ability of the graphite to intercalate the ions of said alkali metal therein, and wherein the C-axis of the solid electrolyte and at least a portion of the C-axis of said graphite layer are perpendicular to the flow of the alkali metal ions in the battery.

4,294,899

PTFE-BOUND TALC SEPARATORS FOR SECONDARY ZINC ALKALINE BATTERIES

Romeo R. Witherspoon, Utica, Mich., assignor to General Motors Corporation, Detroit, Mich.

Filed May 1, 1980, Ser. No. 145,595


Int. Cl.³ H01M 2/16

U.S. Cl. 429—206

5 Claims

1. A secondary zinc alkaline battery comprising a zinc electrode, a counterelectrode and a microporous separator between said electrodes for preventing zinc dendrite bridging between said electrodes, said separator having a first face adjacent said zinc electrode and a second face adjacent said counterelectrode and comprising a multiplicity of overlapping talc platelets randomly distributed throughout a fibrillated polytetrafluoroethylene binder, said platelets being oriented

such that the face of the platelets substantially parallel the faces of the separator and being microspaced one from the other



such as to define a tortuously-pathed network of interconnected pores extending between the faces of said separator.

4,294,900

PROCESS OF PRODUCING MULTICOLOR OPTICAL FILTERS

Toshiaki Aono, Minami-ashigara, Japan, assignor to Fuji Photo Film Co., Ltd., Minami-ashigara, Japan

Filed Feb. 22, 1980, Ser. No. 123,610

Claims priority, application Japan, Feb. 23, 1979, 54-20265

Int. Cl.³ G03C 7/00; G03F 5/00

U.S. Cl. 430-7

8 Claims

Cp(C)-M	EMULSION LAYER (2)
Cp(M)-Y	EMULSION LAYER (1)
SUPPORT	

1. A process of producing a multicolor optical filter which comprises:

exposing a multilayer color photographic material comprising: (1) a silver halide emulsion layer containing a colored coupler (1b) colored cyan, magenta or yellow and forming a dye having one of the other two principal colors by coupling reaction with the oxidation product of an aromatic primary amine color developing agent, and (2) a silver halide emulsion layer (2) containing a silver halide emulsion (2a) having a sufficiently high sensitivity that upon exposure that does not produce an image in emulsion layer (1) upon development, an image is produced in emulsion layer (2) and containing a colored coupler (2b) having the same color as that of the dye formed by the coupling reaction of the colored coupler (1b) in emulsion layer (1) and forming a cyan, magenta or yellow dye other than the color of the colored coupler (1b) or the color of the dye formed by coupling reaction of the colored coupler (1b);

said exposure being such that a portion of the material is unexposed and no image-wise development occurs in the silver halide emulsion layer (1) or (2), a portion is exposed in an amount sufficient to increase the coupling color density of the silver halide emulsion layer (2) and no image-wise development occurs in silver halide emulsion layer (1), and the remaining portion is exposed in an amount sufficient to produce image-wise development of the silver halide emulsion layer (1); and

processing the color photographic material in color developer containing an aromatic primary amine color developing agent.

4,294,901 THERMOREMANENT MAGNETIC IMAGING MEMBER AND SYSTEM


Frank C. Genovese, Fairport, N.Y., assignor to Xerox Corporation, Stamford, Conn.

Filed Nov. 3, 1980, Ser. No. 203,207

Int. Cl.³ G03G 19/00

U.S. Cl. 430-39

10 Claims



1. A magnetic imaging process comprising:
 - (a) providing a thermoremanent magnetic imaging member comprising a substrate, an electrically conductive layer over said substrate, and an electrically resistive layer over said conductive layer wherein said resistive layer comprises aligned magnetic particles and electrically conductive particles dispersed in a polymer binder;
 - (b) forming a latent magnetic image on said imaging member by heating selected portions of said imaging member to about the Curie temperature of said magnetic particles and allowing the heated portions of said imaging member to cool in the presence of an externally applied magnetic field;
 - (c) developing said latent magnetic image by contacting said imaging member with a magnetic toner composition comprising a fusible resinous component and a magnetically attractable component;
 - (d) transferring the developed image to a receiving member; and
 - (e) fixing the transferred image to said receiving member.

4,294,902

IMAGE FORMATION METHOD HAVING TRANSLUCENT PARTICLES CONTAINING A COLORING AGENT AND A COLORLESS DYE FORMER

Yuji Takashima, Osaka; Eisuke Ishida, Nara; Hisanori Nishiguchi, Neyagawa, and Kimiaki Yoshino, Hirakata, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan

Continuation of Ser. No. 741,022, Nov. 11, 1976, abandoned.

This application Aug. 17, 1978, Ser. No. 934,503

Claims priority, application Japan, Nov. 12, 1975, 50-136505; Nov. 12, 1975, 50-136506; Nov. 12, 1975, 50-136507

Int. Cl.³ G03G 13/08, 13/16

U.S. Cl. 430-45

10 Claims

1. Image formation method comprising steps of:
 - a. imparting a charge to a photoconductive member combined with an electrically conductive support member;
 - b. spreading on the surface of the charged photoconductive member a mixture of particles comprising at least one type of non-photoconductive, translucent particles containing a coloring agent and a colorless dye which is capable of developing a color different from that transmitted by said translucent particles;
 - c. causing said translucent particles to electrostatically adhere to said surface through electrostatic attraction;
 - d. subjecting the charged photoconductive member bearing said translucent particles to light image exposure through said translucent particles, thereby selectively weakening and attenuating the charge on a portion of said photocon-

ductive member below said translucent particles through which the light of said light image has passed, whereby the electrostatic attraction of said particles to said photoconductive member is selectively weakened in relation to the degree of said light exposure;

- e. exerting a force on said translucent particles to remove those translucent particles with selectively weakened attraction for said photoconductive member and to thereby obtain a particle image; and
- f. bringing said particle image into close contact with a color developing agent which develops said colorless dye into a color different from that transmitted by said translucent particles.

4,294,903

PROCESS FOR ELECTROSTATICALLY DEVELOPING AND PRESSURE-FIXING A REVERSED IMAGE INCLUDING CHARGE DISSIPATION PRIOR TO FIXING

Donald Kings, Saint Nicolas d'Almermont, and Pham K. Quang, Dieppe, both of France, assignors to Rhone Poulenc Systemes, Creteil, France


Filed Jun. 31, 1980, Ser. No. 174,130

Claims priority, application France, Aug. 8, 1979, 79 20264

Int. Cl.³ G03G 13/22

U.S. Cl. 430-98

5 Claims



1. In an electrophotographic copying process for obtaining a reversed image of an original negative transparency by uniformly electrostatically charging a copying paper, dissipating the electrostatic charges in selected areas corresponding to the transparent areas of the original negative, developing the copying paper by depositing toner on the selected areas and fixing the toner by passing the copying paper between metal pressure rollers,

the improvement comprising, dissipating the remaining uniform electrostatic charge on the copying paper after the development step but before the fixing step.

2. The process of claim 1 in which the copying paper comprises a support and a photoconductive layer on said support, wherein the dissipation of the remaining uniform electrostatic charge is obtained by illuminating the support.

4,294,904

INDUCTIVE DEVELOPMENT MATERIALS FOR A MAGNETIC DEVELOPMENT PROCESS

Joseph Mammino, Penfield, N.Y., assignor to Xerox Corporation, Stamford, Conn.

Filed Nov. 21, 1979, Ser. No. 96,593

Int. Cl.³ G03G 13/09

U.S. Cl. 430-122

8 Claims

1. A magnetic brush inductive development process comprising the steps of providing an electrostatic imaging member having a recording surface, forming an electrostatic latent image on said recording surface, and contacting the recording surface with an electrostatic developer mixture comprising electrically conductive carrier particles and a finely-divided toner composition, said toner composition com-

prising a colorant, a thermoplastic resin, a magnetic or magnetically attractable material, present in an amount of from about 10% to about 80% by weight, and being selected from the group consisting of magnetite, ferrites, iron, and nickel, and a triboelectric charging-enhancing material dispersed in the toner composition, present in an amount of between about 0.25% to about 15% by weight, and selected from the group consisting of alkyl pyridinium compounds, long chain hydrazinium compounds, quaternary ammonium compounds, and fluorosurfactants comprising ionic solubilizing groups linked to highly branched perfluoro groups, said toner composition being characterized as possessing triboelectric charging properties such that it is charged to a level of from about 15 microcoulombs per gram to about 30 microcoulombs per gram of toner composition, a resistivity of at least 10¹⁴ ohm-cm, and promotes homogeneous mixing of said toner composition with said carrier particles thereby improving transport of the toner particles and avoiding clumping of the toner particles, whereby at least a portion of said finely-divided toner composition is attracted to and deposited on said recording surface in conformance with said electrostatic image.

4,294,905

LIGHT-SENSITIVE LITHOGRAPHIC PRINTING PLATE AND COMPOSITIONS THEREFORE WITH MULTIPLE RESINS

Yoshio Okishi; Akinobu Koike, and Shizuo Miyano, all of Shizuoka, Japan, assignors to Fuji Photo Film Co., Ltd., Minami-ashigara, Japan

Filed Jun. 18, 1979, Ser. No. 49,246

Claims priority, application Japan, Jun. 16, 1978, 53-72787


Int. Cl.³ G03C 1/60, 1/52; G03F 7/08

U.S. Cl. 430-175

27 Claims

1. A light-sensitive lithographic printing plate comprising a support having provided on at least one surface thereof a light-sensitive layer comprising a light-sensitive component, a first resin and a second resin having poor compatibility with said first resin, said first resin including side chains which are compatible with said second resin and said first resin selectively accumulating at the outermost surface of said light-sensitive layer to impart higher oleophilicity thereto whereby the outermost surface of said light-sensitive layer exhibits higher oleophilicity than the balance of the light-sensitive layer, wherein said light-sensitive layer comprises:

(a) as said first resin, a copolymer having repeating units of the formulae (I) and (II):




wherein R₁ represents a hydrogen atom or a methyl group, R₂ represents a hydrogen atom, a methyl group, an ethyl group or a chloromethyl group, and n represents an integer of 1 to 10;




wherein R₃ represents a hydrogen atom or a methyl group and having an acid value of about 10 to 100;

(b) as said second resin, a copolymer having repeating units of the formulae (III) and (IV):



wherein R_4 represents a hydrogen atom, a methyl group, an ethyl group, a methoxy group, an ethoxy group or an aryl group;



wherein R_5 represents a hydrogen atom, a methyl group or an ethyl group, and R_6 represents an alkyl group or an aryl group; and

(c) a diazo compound, as said light-sensitive component.

4,294,906

INSTANT PROCESSING SLEEVE


Philip D. Bechle, Rochester, and Joseph A. Roth, Webster, both of N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.

Filed Apr. 14, 1980, Ser. No. 140,072

Int. Cl.³ G03C 1/48

U.S. Cl. 430—207

6 Claims



1. A processing sleeve for receiving photographic film processable by a fluid to form an imagewise distribution of material for transfer by diffusion from the film to an image-receiving sheet; said sleeve comprising:

an image-receiving sheet including means for accepting and immobilizing the diffusion material from the film to form a visible image in the receiving sheet;

sheet means, superposed with said receiving sheet, including a generally flat section and doubled over portions, said portions and said flat section forming channels for slidably receiving the film into juxtaposition with said receiving sheet with the film between the portions and the flat section whereby the film is spaced from the receiving sheet; and

means for supplying the processing fluid between the received film and said receiving sheet to process the film and bring about the transfer of the diffusion material to said receiving sheet with the doubled over portions assisting in establishing a predetermined depth of the processing fluid between the received film and said receiving sheet.

4,294,907

IMAGE-RECEIVING ELEMENTS

Irena Y. Bronstein-Bonte, Newton; Edward P. Lindholm, Boston, and Lloyd D. Taylor, Lexington, all of Mass., assignors to Polaroid Corporation, Cambridge, Mass.

Filed Apr. 24, 1980, Ser. No. 143,281

Int. Cl.³ G03C 5/54, 1/40


U.S. Cl. 430—213

11 Claims

1. An image-receiving element for use in a diffusion transfer process, said image-receiving element comprising, in sequence, a transparent support, an image-receiving layer for a diffusible image-providing material, and a layer adapted to decolorize a pH-sensitive phthaline dye in aqueous alkaline solution, said decolorizing layer comprising a polyoxyalkylene decolorizing agent hydrogen bonded with at least one other polymer.

2. An image-receiving element as defined in claim 1 wherein

said diffusible image-providing material is a dye and said image-receiving layer contains a mordant.



3. An image-receiving element as defined in claim 2 wherein said mordant contains quaternary ammonium moieties.

4,294,908

PHOTORESIST COMPOSITION CONTAINING MODIFIED CYCLIZED DIENE POLYMERS

Yoshiyuki Harita, Kawasaki; Yoichi Kamoshida, Yokohama, and Kunihiro Harada, Machida, all of Japan, assignors to Japan Synthetic Rubber Co., Ltd., Tokyo, Japan

Filed Apr. 2, 1980, Ser. No. 136,477

Claims priority, application Japan, Apr. 24, 1979, 54-50694

Int. Cl.³ G03C 1/68

U.S. Cl. 430—286

15 Claims

1. A photoresist composition comprising a cyclized product obtained by contacting a conjugated diene polymer or copolymer having sites of unsaturation in the main chain or side chains with a fluorine-containing substituted sulfonic acid compound of the formula:



wherein R is hydrogen, alkyl or $\text{CF}_n\text{H}_{3-n}\text{SO}_2$, X is halogen, and n is 1, 2 or 3, in an inert solvent, and a photosensitive crosslinking agent soluble in an organic solvent.

4,294,909

PHOTOSENSITIVE NEGATIVE-WORKING TONING PROCESS

Ross A. Lee, Webster, N.Y., assignor to E. I. Du Pont de Nemours and Company, Wilmington, Del.

Filed Dec. 26, 1979, Ser. No. 106,401

Int. Cl.³ G03C 5/04


U.S. Cl. 430—291

10 Claims


1. A process for preparing negative tonable images which comprises exposing imagewise a photosensitive element comprising a support bearing a layer of a negative-working tonable photoimaging composition which comprises

(a) at least one organic polymeric binder taken from the group consisting of polyvinylformal, polyvinylpyrrolidone, polyacrylate, cellulose acetate, polymethacrylate, and polyvinyl acetate;

(b) a photosensitizer which upon absorption of actinic radiation is capable of generating an acid; and at least one acetal compound taken from the group of



wherein R is hydrogen, alkyl of 1 to 18 carbon atoms, phenyl and substituted phenyl, and R_1 is taken from the group of alkylene of 2 to 12 carbon atoms and heteroalkylene of 2 to 12 carbon atoms, and



wherein R_2 is alkyl of 1 to 18 carbon atoms, furyl, substituted furyl, phenyl, substituted phenyl, naphthyl, and substituted naphthyl, R_3 is alkyl of 1 to 18 carbon atoms, and OR_3 when taken together form a 5, 6 or 7 membered ring, the polymeric binder (a) being plasticized by the decomposition product of one of compound (c) (1), compound (c) (2) or the combination of compounds (c) (1) and (2), and toning the exposed image areas of said element.

4,294,910

PRINTING PLATES

Hans Wielinga, Hilversum, Netherlands, assignor to Vickers Limited, London, England
Continuation of Ser. No. 781,102, Mar. 25, 1977, abandoned, which is a continuation of Ser. No. 593,697, Jul. 7, 1975, abandoned. This application Aug. 11, 1980, Ser. No. 177,283
Claims priority, application United Kingdom, Jul. 8, 1974, 30264/74

Int. Cl.³ G03F 7/02; G03C 5/00

U.S. Cl. 430—302

11 Claims

1. A method of processing a pre-sensitized radiation sensitive plate which method comprises

(i) image-wise exposing to radiation a pre-sensitized radiation sensitive plate, said plate being adapted for the manufacture of a lithographic printing plate or a printed circuit or an integrated circuit, and said plate comprising a metallic substrate and a radiation sensitive layer comprising an organic photosensitive compound, so that said radiation sensitive layer includes areas exposed to radiation and areas not exposed to radiation, said areas being of differing solubility and comprising a more-soluble area,

(ii) thereafter developing the image-wise exposed radiation sensitive layer by selectively removing said layer from said more-soluble area and revealing the substrate underlying said more-soluble area,

(iii) thereafter treating the plate with an aqueous solution to provide a water-soluble layer overlying the revealed substrate and the previously-exposed radiation sensitive layer not removed during said developing step, said water-soluble layer being formed by applying to said plate an aqueous solution of at least one water-soluble salt selected from the group consisting of a sodium dodecyl phenoxy benzene disulphonate, a sodium salt of an alkylated naphthalene sulphonic acid, a disodium salt of methylene dinaphthalene sulphonic acid, a sodium salt of a sulphonated alkylphenyl oxide, a sodium dodecyl benzene sulphinate, lithium nitrate, and mixtures thereof,

(iv) thereafter burning-in said plate to adapt said plate for lithographic printing, or printed circuit or integrated circuit said burning-in being conducted in the presence of scum-forming contaminants, and

(v) removing said water-soluble layer from said plate with water, thereby removing scum-forming contaminants from the area of the revealed substrate of said plate.

(c) (1)

4,294,911
DEVELOPMENT OF LIGHT-SENSITIVE QUINONE DIAZIDE COMPOSITIONS USING SULFITE STABILIZER

John R. Guild, Rochester, N.Y., assignor to Eastman Kodak Company, Rochester, N.Y.

Filed Jun. 18, 1979, Ser. No. 49,765

Int. Cl.³ G03C 5/34; G03F 7/08; B05D 3/06

U.S. Cl. 430—326

23 Claims

1. A method of developing an image-wise-exposed layer of a light-sensitive quinone diazide composition comprising contacting said layer with an alkaline developing composition to remove exposed areas of said layer, said developing composition comprising an aqueous solution containing a quaternary alkanol ammonium hydroxide developing agent, in a sufficient concentration to remove exposed areas of said layer, and a stabilizing concentration of a sulfite.

4,294,912

THERMALLY RESPONSIVE COBALT(III) COMPLEX IMAGING COMPOSITIONS HAVING LOWERED ACTIVATION TEMPERATURES


Anthony Adin, Rochester; John W. Boettcher, Ontario, and James C. Fleming, Webster, all of N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.

Filed Jul. 17, 1980, Ser. No. 169,703

Int. Cl.³ G03C 1/02

U.S. Cl. 430—341

32 Claims



1. In a dye-forming composition including a thermally-activatable precursor composition including a cobalt(III) complex containing releasable ligands; an amplifier that reacts with either cobalt(II) or released ligands to form an agent for conversion of cobalt(III) to cobalt(II) and the release of ligands; a first destabilizer compound which when heated with said amplifier for a specified time causes conversion of said cobalt(III) complex to cobalt(II) and released ligands; and a dye-former capable of generating a dye in response to said conversion of the cobalt complex; the improvement wherein said composition further includes a second destabilizer compound different from said first destabilizer compound which, when heated with said amplifier for said time without said first compound, converts said cobalt(III) complex to cobalt(II) and released ligands, said first and second destabilizer compounds together being present in admixture in respective individual amounts that provide an initiation temperature for the conversion of said complex at said specified heating time that is lower than the initiation temperatures that result when either of said destabilizer compounds is used alone in said respective individual amount.

4,294,913




INFORMATION CARRIERS, METHOD OF FORMING AND COPYING SAID CARRIERS

Roland Moraw, and Renate Schädlich, both of Naurod, Fed. Rep. of Germany, assignors to Hoechst Aktiengesellschaft, Frankfurt am Main, Fed. Rep. of Germany
Division of Ser. No. 861,491, Dec. 16, 1977. This application Aug. 7, 1979, Ser. No. 64,645

Claims priority, application Fed. Rep. of Germany, Dec. 17, 1976, 2657246

Int. Cl.³ G03C 7/00

U.S. Cl. 430—396



1. A process for producing an original of an information carrier for use in zero order diffraction color projection which comprises the steps of:

- exposing a recording layer, mounted on a carrier, through separate color separation originals to form relief part-images, each relief part-image corresponding to a different projection color, said originals being transparent in the areas of the particular projection colors of the individual color separation originals each of said relief part-images of the projection color adjoining one another without overlap and having a depth corresponding to one of the particular projection colors;
- exposing the entire portion of said recording layer to be utilized in carrying information to a grating pattern without intervening development to provide a structure in which the recording layer is exposed through to said carrier;
- said image-wise exposure through each individual color separation original provided with an energy density equal to that required to obtain the individual projection color; and
- developing said exposed recording layer.

4,294,914

PHOTOGRAPHIC BLEACH COMPOSITIONS AND METHODS OF PHOTOGRAPHIC PROCESSING

John R. Fyson, London, England, assignor to Eastman Kodak Company, Rochester, N.Y.

PCT No. PCT/GB79/00152, § 371 Date May 14, 1980, § 102(e) Date May 2, 1980, PCT Pub. No. WO80/00624, PCT Pub. Date Apr. 3, 1980

PCT Filed Sep. 14, 1979, Ser. No. 192,952

Claims priority, application United Kingdom, Sep. 14, 1978, 36816/78

Int. Cl.³ G03C 5/32, 5/38, 5/44, 5/52

U.S. Cl. 430—418

15 Claims

1. A method of processing a photographic color material comprising the step of bleaching or bleach-fixing said material with a composition comprising, as the bleaching agent, a ferric complex of an alkyliminodiacetic acid, the alkyl group of which contains from 1 to 6 carbon atoms.

10. An aqueous photographic bleaching solution containing

a water-soluble halide and, as the bleaching agent, a ferric complex of an alkyliminodiacetic acid, the alkyl group of which contains from 1 to 6 carbon atoms.

4,294,915

SILVER HALIDE DEVELOPING AGENTS

Elbert M. Idelson, West Newton, Mass., assignor to Polaroid Corporation, Cambridge, Mass.


Continuation-in-part of Ser. No. 89,555, Oct. 29, 1979, abandoned, which is a continuation-in-part of Ser. No. 1,447, Jan. 8, 1979, abandoned. This application Jul. 11, 1980, Ser. No. 168,642

Int. Cl.³ G03C 5/30

U.S. Cl. 430—441

6 Claims

1. A photographic method which comprises treating an exposed silver halide emulsion with an aqueous alkaline processing composition containing a silver halide developing agent which is represented by a formula selected from the group consisting of



wherein R₁ and R₂ are each H or when taken together represent the carbon atoms necessary to complete a five or six member heterocyclic moiety; X and X' are each radicals containing an onium group; Y is a hydroquinonyl group; A and B are each alkylene having from 1 to 6 carbon atoms with the proviso that the sum of the carbon atoms of A and B is not greater than 8; D is a saturated aliphatic radical having up to 6 carbon atoms; and Z is an anion.

4,294,916

PHOTOGRAPHIC SILVER HALIDE MATERIAL CONTAINING A DYE FILTER OR A DYE ANTI-HALATION LAYER

Stephen R. Postle, Brentwood, and Alexander Psaila, Chelmsford, both of England, assignors to Ciba-Geigy AG, Basel, Switzerland

Filed Apr. 30, 1980, Ser. No. 145,174

Claims priority, application United Kingdom, May 22, 1979, 17692/79

Int. Cl.³ G03C 1/84

U.S. Cl. 430—522

8 Claims

1. Photographic silver halide material which comprises in at least one layer a solid dispersion of at least one water-insoluble dye of the general formula

4,294,918

COLOR PHOTOGRAPHIC SILVER HALIDE LIGHT-SENSITIVE MATERIAL

Morio Yagihara, and Yukio Yokota, both of Minami-ashigara, Japan, assignors to Fuji Photo Film Co., Ltd., Minami-ashigara, Japan

Filed Jul. 14, 1980, Ser. No. 168,917

Claims priority, application Japan, Jul. 12, 1979, 54-88440 Int. Cl.³ G03C 1/40

U.S. Cl. 430—553

16 Claims

1. A color photographic silver halide light-sensitive material containing a colorless photographic cyan color-forming coupler having, in a position for coupling with the oxidation product of an aromatic primary amine developing agent, as a coupling-off group, at least one alkoxy group substituted with a sulfinyl group represented by the formula (I)



(I)

wherein R represents a saturated or unsaturated divalent aliphatic group containing from 1 to 10 carbon atoms which may be straight or branched chain and may be substituted; and R₁ represents a substituted or unsubstituted straight or branched chain alkyl group, an alkenyl group, an aralkyl group, an aralkenyl group, a cycloalkyl group, an aryl group or a heterocyclic group; and said heterocyclic group being connected with a sulfinyl group on the position of a carbon atom of the heterocyclic group.

4,294,917

PHOTOGRAPHIC SILVER HALIDE MATERIAL CONTAINING A DYE FILTER OR A DYE ANTI-HALATION LAYER

Stephen R. Postle, Brentwood, and Alexander Psaila, Chelmsford, both of England, assignors to Ciba-Geigy AG, Basel, Switzerland

Filed Apr. 30, 1980, Ser. No. 145,175


Claims priority, application United Kingdom, May 22, 1979, 17693/79

Int. Cl.³ G03C 1/84

U.S. Cl. 430—522

6 Claims

1. Photographic silver halide material which comprises in at least one layer a solid dispersion of a water-insoluble dye of the formula



wherein each of L, L' and L'' are an optionally substituted methine group, n is 0 or 1, Q is phenyl or phenyl substituted by halogen, hydroxy or di-lower-alkylamino, or benzimidazole, benzoxazole, benzthiazole, benziselenazole, lepidinole, quinole or indole which are unsubstituted or substituted by halogen, cyano, nitro or lower alkyl, R₁ represents a hydrogen atom or an optionally substituted alkyl, benzyl, β-phenylethyl, cycloalkyl, phenyl, tolyl, chlorophenyl, methoxyphenyl, ethoxyphenyl or heterocyclic radical or an optionally substituted amino group, R₂ represents a hydrogen atom or a hydroxy, amino, —CN, —COOR¹, —CONR¹R² or —COR¹ group or an optionally substituted alkyl, benzyl, β-phenylethyl, cycloalkyl, phenyl, tolyl, chlorophenyl, methoxyphenyl, ethoxyphenyl or heterocyclic radical, and R₃ represents hydrogen, a —CN, —COOR³, —CONR³R⁴, —SO₃H, —SO₃⊖ or —COR³ group, where R¹, R², R³ and R⁴ each independently represent a hydrogen atom or an optionally substituted alkyl, benzyl, β-phenylethyl, cycloalkyl, phenyl, tolyl, chlorophenyl, methoxyphenyl, ethoxyphenyl or heterocyclic radical, in a binder.

4,294,919

DIRECT POSITIVE SILVER HALIDE LIGHT-SENSITIVE MATERIAL

Nobuyuki Tsujino, and Shigeo Hirano, both of Minami-ashigara, Japan, assignors to Fuji Photo Film Co., Ltd., Minami-ashigara, Japan


Filed Jun. 6, 1980, Ser. No. 156,949

Claims priority, application Japan, Jun. 6, 1979, 54-70854 Int. Cl.³ G03C 1/36

U.S. Cl. 430—559

20 Claims

1. A direct positive silver halide photographic light-sensitive material comprising a support having coated thereon an internal latent image emulsion layer which contains a light-sensitive silver halide of the type that is not previously fogged and a hydrophilic colloid layer, at least one of said layers containing a compound represented by the formula (I) in an amount which gives a suitable maximum density when the light-sensitive material is developed by a surface developing solution



(I)

wherein R¹ represents R⁶ or R⁶CO—; and R⁶ represents an aliphatic group, an aromatic group, a heterocyclic aromatic group or hydrogen; R² and R⁴, which may be the same or different, each represents an aliphatic group, an aromatic group, a heterocyclic aromatic group or hydrogen; or R¹ and R² together can form a ring; R³ represents hydrogen or an aliphatic group; R⁵ represents Y or X—A—Y wherein X and Y, which may be the same or different, each represents a divalent aromatic group, and A represents a divalent connecting group selected from —CONH—, NHCONH—, —SO₂NH—, —B—CONH— and —B—SO₂NH— wherein B represents —E—, —O—E— or —S—E— wherein the O and S is bonded to X; and E represents a divalent aliphatic group.

4,294,927

GENETIC PROCESS FOR THE PREPARATION OF ANTIBIOTIC-PRODUCER MICROMONOSPORA STRAINS

Lajos Alföldi; Katalin Balint nee Fodor; Csaba Kari; Istvan Török, all of Szeged; György Szvoboda, Budapest; Tibor Lang, Budapest; Istvan Gado, Budapest, and Gabor Ambrus, Budapest, all of Hungary, assignors to Gyógyszerkutató Intézet, Budapest, Hungary

Filed Nov. 8, 1979, Ser. No. 92,554

Claims priority, application Hungary, Nov. 13, 1978, G0 1430 Int. Cl.³ C12N 15/00

U.S. Cl. 435—172

9 Claims

1. A process for preparing an antibiotic-producing Micromonospora strain having modified genetic material, which comprises preparing, following cultivation in a glycine medium, a protoplast suspension of each of two genetically different mutants of antibiotic-producing Micromonospora with lysozyme, under osmotically buffered conditions ensured by sucrose, combining the two suspensions thus obtained in the presence of polyethylene glycol, incubating at room temperature, suspending the resulting fused protoplasts in soft agar, then plating the suspended protoplasts on an agar plate containing sucrose, proline and inorganic salts, incubating the plated protoplasts for 20 to 30 days, selecting all colonies from the regenerated colonies which are sure to have genetic material different from that of said two mutants, and, prior to fusion, heat-inactivating the protoplasts of one of said mutants by heating them at 55° C. for three hours, thereby to permit the genetic material of the non-heated protoplasts to be transferred into the cytoplasm of the heat-inactivated protoplasts.

4,294,928

DENITRIFICATION OF A GAS STREAM

Andree E. Tamony, Antioch, and Charles R. Youngson, Jr., Concord, both of Calif., assignors to The Dow Chemical Company, Midland, Mich.

Filed Aug. 8, 1980, Ser. No. 176,439

Int. Cl.³ B01D 53/34

U.S. Cl. 423—235

1 Claim

1. A process for removing NO_x from a gas stream wherein at least part of the NO_x is present as nitric oxide which comprises (a) mixing more than one molecular proportion of chlorine per molecular proportion of said nitric oxide with the gas stream, (b) subsequently contacting the resulting mixture of gases with aqueous hydrochloric acid at a temperature of from about 10° C. to about 50° C. for a time sufficient to oxidize a substantial proportion of the nitric oxide present, and (c) scrubbing the gas stream exiting from step (b) with a mixture of aqueous sodium hydroxide and sodium hypochlorite at a temperature of from about 30° C. to about 50° C.

4,294,929

PRODUCTION OF EDIBLE PROTEIN SUBSTANCES

Gerald L. Solomons, High Wycombe, and Gerald W. Scammell, Chinnor, both of England, assignors to Ranks Hovis McDougall Limited, London, England

Continuation of Ser. No. 711,964, Aug. 5, 1976, Pat. No. 4,061,781, which is a continuation of Ser. No. 414,102, Nov. 8, 1973, abandoned, which is a continuation of Ser. No. 140,303, May 4, 1971, abandoned. This application Dec. 5, 1977, Ser. No. 857,591

Claims priority, application United Kingdom, May 14, 1970, 23452/70; Jun. 24, 1970, 30584/70

The portion of the term of this patent subsequent to Feb. 10, 1993, has been disclaimed.

Int. Cl.³ C12N 1/14; C12R 1/27

U.S. Cl. 435—254

9 Claims

1. Biologically pure fungal culture containing a strain of *Fusarium graminearum* Schwabe I.M.I. 145425 or a mutant or variant thereof in a culture medium in which this strain is present in a culture medium containing or being supplied with nutrients or additives necessary for the sustenance and multi-

plication of the strain, the medium having a pH between 3.5 and 7 and the temperature of the medium being maintained at a precise value within the range of between 25° and 34° C.

4. A biologically pure culture of the microorganism *Fusarium graminearum* Schwabe, having the identifying characteristics of IMI 145425, said culture being capable of producing proliferation of said microorganism in a recoverable quantity upon fermentation in a culture medium containing essentially growth-promoting nutrient substances, wherein said proliferated organism comprises an edible protein-containing substance possessing a high net protein utilization value of at least 65 based on the α-amino nitrogen.

4,294,930

PROCESS FOR IMPROVING THE RECOVERY OF MICROBIAL CELL BIOMASS

Jeffrey T. Barach, and Leslie Blum, both of Elkhart, Ind., assignors to Miles Laboratories, Inc., Elkhart, Ind.

Filed Aug. 22, 1979, Ser. No. 68,876

Int. Cl.³ C12N 1/02

U.S. Cl. 435—261

4 Claims

1. A process for recovering chain-forming microorganisms from a culture broth with improved yield, consisting essentially of subjecting a culture broth containing chain-forming microorganisms to shearing conditions in apparatus selected from the class consisting of high speed dispersers, homogenizers and sonic oscillators sufficient to shorten the chain length of said microorganisms and thereby substantially reduce the packed cell volume thereof, and then recovering said microorganisms from said culture broth by centrifugation.

4,294,931

DEVICE FOR CONDUCTING MICROBIOLOGICAL RADIORESPIROMETRIC ASSAYS


Gilbert V. Levin, Annapolis, and Patricia A. Straat, Baltimore, both of Md., assignors to Biospherics Incorporated, Rockville, Md.

Filed Dec. 26, 1979, Ser. No. 107,383

Int. Cl.³ C12M 1/20

U.S. Cl. 435—301

8 Claims



1. A device for conducting a microbiological radiorespirometric assay under aerobic or anaerobic conditions which device comprises a support member which includes a plurality of pairs of chambers, one chamber in each said pair containing a radioactive labeled substrate which is capable of being metabolized by at least some microorganisms to yield a radioactive gas, the other chamber in each said pair containing a means for collecting radioactive gas, the two chambers in each pair being in communication with each other by means of a passageway, said passageway opening into each of said chambers at the upper portion thereof, and closure means for closing said chambers and said passageway, said passageway being situated in said support member or in said closure means.

4,294,932

METHANATION PROCESS


Reiner Lohmüller, Munich; Helmut Schneider, Grünwald, and Allan Watson, Ottobrunn, all of Fed. Rep. of Germany, assignors to Linde AG, Wiesbaden, Fed. Rep. of Germany Continuation of Ser. No. 875,903, Feb. 7, 1978, abandoned. This application Aug. 8, 1979, Ser. No. 64,831

Claims priority, application Fed. Rep. of Germany, Feb. 8, 1977, 2705151

Int. Cl.³ C10K 3/04

U.S. Cl. 518—706

1 Claim



1. A process for carrying out a strongly exothermic catalytically promoted chemical reaction to form methane, comprising the steps of:

forming reactant-gas mixture of at least two components capable of undergoing catalytically promoted exothermic reaction, said components consisting essentially of hydrogen and carbon oxide;

subdividing said reactant-gas mixture into two streams;

passing a first of said streams of said reactant-gas mixture into contact with a catalyst in an adiabatic exothermic methanization reaction stage without heating the latter or abstracting heat from the latter to produce a first product mixture;

passing the second of said streams of said reactant-gas mixture through an isothermal exothermic methanization reaction stage into contact with a catalyst capable of promoting said reaction to produce a second product mixture while abstracting heat from said isothermal reaction stage to maintain a substantially constant temperature therein; and controlling the distribution of said reactant-gas mixture between said streams in response to the temperature of said first product mixture to prevent excessive temperatures from developing in said adiabatic reaction stage, portion of said second product mixture being passed through said adiabatic reaction stage.

4,294,933

PROCESS FOR THE PRODUCTION OF AN ION EXCHANGE MEMBRANE

Kunio Kihara; Hideo Toda, both of Ami; Elki Yasukawa, Tsuchiura; Toshiaki Ishibashi, Ami, and Taketoshi Tokita, Tsuchiura, all of Japan, assignors to Mitsubishi Petrochemical Company Limited, Tokyo, Japan

Filed Jul. 5, 1979, Ser. No. 54,883

Claims priority, application Japan, Jul. 13, 1978, 53-84590



Int. Cl.³ C25B 13/00

U.S. Cl. 521—27

26 Claims

1. A process for the production of a heterogeneous ion exchange membrane in which an ion exchange resin fine powder is dispersed in a thermoplastic resin, which process comprises kneading a silane-modified polyolefin resin selected from the group consisting of silane-grafted polyolefin resins and

vinylsilane-copolymerized polyolefin resins, and an ion exchange resin fine powder, extruding the mixture to form a



membrane and then subjecting the resulting membrane to a treatment with hot water.

4,294,934

PROCESS FOR THE PRODUCTION OF ELASTIC, OPTIONALLY CELLULAR, POLYURETHANE UREAS

Gerhard Grögl; Jürgen Schwindt; Otto Ganster; Hans-Joachim Meiners, all of Leverkusen, and Hans-Dieter Rupprecht, Cologne, all of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Jun. 30, 1980, Ser. No. 164,752

Claims priority, application Fed. Rep. of Germany, Jul. 12, 1979, 2928182

Int. Cl.³ C08G 18/76, 18/22, 18/18

U.S. Cl. 521—160

4 Claims

1. In a process for the production of polyurethane urea elastomers having a gross density of more than 200 kg/m³ comprising: casting a reaction mixture of

(A) an isocyanate prepolymer produced from

(a) 1 mole of a compound containing at least 2 Zerewitinoff-active hydrogen atoms and having a molecular weight of from 400 to 10,000 and

(b) 2 to 10 moles of diisocyanatodiphenylmethane, and

(B) an aromatic diamine, and (C) 0 to 50 mole percent, based on component (B), of a polyol having a molecular weight of from 62 to 6000, the equivalent ratio between component (A) and components (B)+(C) amounting to between 0.9:1 and 1.3:1,

into a mold, hardening the reaction mixture in the mold and subsequently removing it from the mold, the improvement wherein said isocyanate prepolymer (A) has been produced using an isomer mixture comprising:

from 15 to 80 mole percent of 2,4'-diisocyanatodiphenylmethane, and

from 20 to 85 mole percent of 4,4'-diisocyanatodiphenylmethane, and

from 0 to 20 mole percent of 2,2'-diisocyanatodiphenylmethane.

4,294,935

METHOD OF PRODUCING ETHYLENE-VINYL ALCOHOL COPOLYMER FILM

Yuji Kodera; Kyoichiro Ikari, and Shunji Miyake, all of Kurashiki, Japan, assignors to Kuraray Company, Limited, Kurashiki, Japan

Filed Dec. 19, 1979, Ser. No. 105,412

Claims priority, application Japan, Dec. 29, 1978, 53-161912; Aug. 22, 1979, 54-107569

Int. Cl.³ B29C 17/02, 25/00; C08F 16/06; C08L 29/04

U.S. Cl. 525—60

14 Claims

11. A method of producing an ethylene-vinyl alcohol copolymer film, which comprises: biaxially or multiaxially stretching a nonstretched ethylene-vinylalcohol copolymer film having a moisture content of not more than 3.5%, said ethylene-vinyl alcohol copolymer having an ethylene content of 20 to 55 mole % and a saponification degree of not less than 96 mole %, and said stretching being conducted within a temperature range of 50° to 150° C. to such an extent that the film is expanded to an area 4 to 20 times the original area; and heat treating said stretched film at a temperature in the range between 100° C. and a temperature lower than the melting point of said copolymer by 10° C.

14. The ethylene-vinylalcohol copolymer film produced by the process of claim 11.

4,294,936

ADHESIVE COMPOSITIONS

Ralf Korpman, Bridgewater, N.J., assignor to Permacel, New Brunswick, N.J.

Continuation-in-part of Ser. No. 54,541, Jul. 5, 1979, abandoned. This application May 5, 1980, Ser. No. 142,691

Int. Cl.³ C08L 9/06

U.S. Cl. 525—93

10 Claims

1. A pressure-sensitive adhesive composition comprising a synthetic thermoplastic rubbery block copolymer, a non-rubbery polymer and a tackifier resin, wherein said rubbery block polymer is a copolymer of an alkenylarene A block and an aliphatic diene B block in which the alkenylarene is a polymer of styrene, a ring lower alkyl substituted styrene, a ring phenyl lower-alkyl substituted styrene, a ring (lower alkyl substituted) phenyl lower alkyl substituted styrene or a ring cyclohexyl substituted styrene and the aliphatic diene is a conjugated lower aliphatic diene of from 4 to 6 carbon atoms inclusive and said non-rubbery polymer is a copolyester, said copolyester being a polymer of at least two different ester units, each ester unit being a condensation product of a dicarboxylic acid and an alkylene diol of from 2 to 6 carbon atoms; and wherein for every 100 parts of rubbery block copolymer there is employed from about 5 to about 50 parts of the non-rubbery polymer and from about 20 to about 150 parts of tackifier resin.

4,294,937

IMPACT POLYMERS

Richard O. Whitehead, Houston, Tex., assignor to Shell Oil Company, Houston, Tex.

Filed Jun. 18, 1979, Ser. No. 49,840

Int. Cl.³ C08L 9/06, 53/02

U.S. Cl. 525—99

6 Claims

1. A graft copolymer composition having improved toughness consisting essentially of:

- from about 4 to about 12 parts by weight of a mixture of a polybutadiene elastomer and a styrene-butadiene two-block copolymer in a weight ratio of styrene-butadiene two-block copolymer to polybutadiene elastomer of about 2:80 to about 4:80, where the average molecular weight of the styrene block of the block copolymer is between about 100,000 and about 150,000, and the average molecular

weight of the butadiene block of the block copolymer is between about 30,000 and about 60,000; and
(b) from about 96 to about 88 parts by weight of a polymerized styrene.

4,294,938

THERMAL STABILIZATION OF POLYALKYLENE TEREPHTHALATE RESIN COMPOSITIONS

Charles E. Berr, Wilmington, Del., and Edward J. Deyrup, Northeast, Md., assignors to E. I. Du Pont de Nemours and Company, Wilmington, Del.


Filed Feb. 15, 1980, Ser. No. 122,063

Int. Cl.³ C08L 67/02, 23/26

U.S. Cl. 525—101

9 Claims

1. A molding composition comprising (a) polyalkylene terephthalate having an inherent viscosity of at least 0.4 wherein the alkylene moiety contains 2-4 carbon atoms, (b) 0-50% by weight of reinforcing material, said weight based on polyalkylene terephthalate and reinforcing material, (c) 1-25% by weight of an ionic hydrocarbon copolymer of an α -olefin of 2-5 carbon atoms and an α,β -ethylenically unsaturated carboxylic acid of 3-5 carbon atoms in which the carboxyl groups have been partially neutralized with metal cations, said weight based on polyalkylene terephthalate and copolymer, and (d) 0.1-5% by weight of a silicone resin of the general formula



wherein R is lower alkyl or phenyl, R' and R'' are each independently a hydrocarbyl group of 1-20 atoms and one of R' and R'' can be hydrogen, and n is an integer of between about 5 and 500, said weight based on polyalkylene terephthalate and silicone resin.

4,294,939

COATING COMPOSITION

Eiji Taniguchi; Susumu Akagi, both of Ichihara, and Seiichi Torimitsu, Chiba, all of Japan, assignors to Toray Industries, Inc., Tokyo, Japan

Continuation of Ser. No. 930,407, Aug. 2, 1978, abandoned. This application Sep. 11, 1980, Ser. No. 186,158

Int. Cl.³ C08L 63/00

U.S. Cl. 525—118

4 Claims

1. An organic solvent-based coating composition comprising:

- a water-insoluble polymeric cross-linkable basic nitrogen atom-containing acrylic component comprising at least one film-forming acrylic copolymer containing basic nitrogen atoms, in which component there are present, based on the weight of said component:
 - 2 to 10% by weight of polymerized units derived from at least one basic nitrogen atom-containing acrylate selected from the group consisting of di(C₁₋₂-alkyl)-amino C₁₋₃-alkyl acrylates and methacrylates,
 - 0.5 to 5% (B%) by weight of polymerized units derived from at least one acrylic amide selected from the group consisting of acrylamide and methacrylamide,
 - 0.5 to 20% (C%) by weight of polymerized units derived from at least one hydroxyl-containing acrylic monomer selected from the group consisting of hydroxy C₂₋₄-alkyl acrylates and methacrylates,
 - 35 to 95% by weight of polymerized units derived from at least one alkyl acrylate selected from the group consisting of C₁₋₄-alkyl acrylates and methacrylates, and
 - 0 to 50% by weight of polymerized units derived from one or more other copolymerizable ethylenically unsaturated monomers, said percentages A, B and C satisfying the relation:

$$\frac{14-A}{4} \leq B+C \leq 28-2A, \text{ and;}$$

(II) a cross-linking component comprising at least one polyepoxide compound having an epoxy equivalent of not more than 400 and containing at least two epoxy groups per molecule, said cross-linkable component (I) and cross-linking component (II) being present in said composition so that the ratio by gram atom of the basic nitrogen atom in said component (I) to the epoxy oxygen atom in said component (II) falls within the range of between 0.3 and 3.0.

4,294,940

RESIN COMPOSITION FOR ELECTROCOATING

Minoru Hino; Takao Oshima, both of Takatsuki; Kazuo Hayatsu, Ibaraki; Michio Yamamoto, Takatsuki, and Seimei Yasui, Takarazuka, all of Japan, assignors to Sumitomo Chemical Company, Limited, Osaka, Japan

Filed Jan. 9, 1980, Ser. No. 110,688

Claims priority, application Japan, Jan. 12, 1979, 54-2525; Jul. 19, 1979, 54-92202; Aug. 23, 1979, 54-108016

Int. Cl.³ C08G 18/80, 18/62; C25D 13/06

U.S. Cl. 525—124

10 Claims

1. A resin composition for electrocoating, which comprises (I) a reaction product (G) of 100 parts by weight of an epoxy compound (E) and 5 to 200 parts by weight of a partially esterified and/or partially amidated product (D) which is obtained by partially esterifying and/or partially amidating an adduct (A) of a conjugated diene polymer having a number average molecular weight of 150 to 50,000 with an α,β -unsaturated dicarboxylic acid or its anhydride, wherein said α,β -unsaturated dicarboxylic acid or its anhydride is used in an amount such that the content of the dicarboxylic acid in the adduct (A) becomes 5 to 25% by weight based on the total weight of the adduct (A), with an alcoholic hydroxy group-containing compound (B) and/or a primary or secondary monoamine (C), respectively, said compound (B) and monoamine (C) being used in an amount such that the sum of the molar number of the compound (B) and that of the monoamine (C) becomes 0.7 to 1.2 mol per 1 mol of the α,β -unsaturated dicarboxylic acid or its anhydride, and (II) a completely blocked organic polyisocyanate in an amount of 5 to 200 parts by weight to 100 parts by weight of the reaction product (G), said mixture of the reaction product (G) and the completely blocked organic polyisocyanate being neutralized.

4,294,941

COMPATIBLE LOW SHRINK RESIN SYSTEMS

Gwilym E. Owen, Jr., Granville, Ohio, assignor to Owens-Corning Fiberglass Corporation, Toledo, Ohio

Filed Dec. 14, 1979, Ser. No. 103,751

Int. Cl.³ C08L 67/06

U.S. Cl. 525—170

8 Claims

1. A compatible, moldable composition comprising a thermoplastic resin, a thermosetting resin and a monomer, a. said thermoplastic resin comprising the terpolymer of vinyl acetate, methylmethacrylate and acrylic acid; b. said thermosetting resin comprising an unsaturated polyester produced by the interreaction of propylene glycol, dipropylene glycol, maleic anhydride and adipic acid, the sum of the weight of said dipropylene glycol and said adipic acid comprising not less than about 31.6 percent by weight of the weight of the theoretical yield of the polyester product; and, c. said thermoplastic resin comprising from about 7 to about 18 weight percent of said composition, said thermosetting resin comprising from about 31 to about 55 weight percent of said composition and said monomer comprising from about 27 to about 61 weight percent of said composition.

4,294,942 RUBBERY COPOLYMERS OF 2,3-DIMETHYL-1,3-BUTADIENE

James N. Henderson, Hudson, Ohio, assignor to The Goodyear Tire & Rubber Company, Akron, Ohio

Continuation of Ser. No. 3,835, Jan. 16, 1979, abandoned, which is a continuation of Ser. No. 915,682, Jun. 14, 1978, abandoned, which is a continuation of Ser. No. 825,318, Aug. 17, 1977, abandoned, which is a continuation of Ser. No. 775,125, Mar. 7, 1977, abandoned. This application Feb. 14, 1980, Ser. No. 121,626

Int. Cl.³ C08F 297/02

U.S. Cl. 525—314

5 Claims

1. Stress crystallizable tapered block copolymers of 2,3-dimethyl-1,3-butadiene and butadiene or isoprene in which the 2,3-dimethyl-1,3-butadiene content ranges from about 20 to about 80 mole percent, characterized in that the said tapered block copolymers have one terminal segment of the block made up almost entirely of 2,3-dimethyl-1,3-butadiene units and the other terminal segment made up almost entirely of units of the other diene, either butadiene or isoprene, between these relatively pure terminal blocks is a central segment of gradually changing composition made up of both 2,3-dimethyl-1,3-butadiene units and units of the other diene, 1,3-butadiene or isoprene, said copolymers being further characterized in that the microstructure of the 2,3-dimethyl-1,3-butadiene segments range from about 55 to about 65 percent trans-1,4 and does not exceed about 20 percent 1,2-microstructure.

4,294,943

PROCESS FOR PREPARING FLUORINE-CONTAINING POLYMERS HAVING CARBOXYL GROUPS

Yasuharu Onoue, Tokyo; Toshikatsu Sata, Tokuyama; Akihiko Nakahara, Tokuyama, and Junichi Itoh, Tokuyama, all of Japan, assignors to Tokuyama Soda Kabushiki Kaisha, Yamaguchi, Japan


Division of Ser. No. 898,950, Apr. 21, 1978, Pat. No. 4,200,711. This application Nov. 28, 1979, Ser. No. 92,339

Claims priority, application Japan, Apr. 25, 1977, 52-46861; Dec. 19, 1977, 52-152694

Int. Cl.³ C08F 8/06

U.S. Cl. 525—358

14 Claims



1. A process for preparing a fluorine-containing polymer having carboxyl groups, which comprises subjecting a solid fluorine-containing polymer having sulfonyl halide groups bonded thereto as pendant groups to an oxidation reaction at a temperature of 50° to 250° C. in the presence of a vapor of an organic compound at least having a carbon-hydrogen bond and an oxidizing agent in vapor form.

4,294,944

FLAME RETARDANT ANTISTATIC ADDITIVES AND ANTISTATIC FIBERS

David D. Newkirk, Beaverton, Oreg.; Robert B. Login, Middletown, Pa., and Basil Thir, Grosse Ile, Mich., assignors to BASF Wyandotte Corporation, Wyandotte, Mich.

Division of Ser. No. 746,723, Dec. 2, 1976, Pat. No. 4,229,554.

This application Nov. 13, 1979, Ser. No. 94,032

Int. Cl.³ C08L 63/00

U.S. Cl. 525—423

7 Claims

1. A flame-retardant, antistatic synthetic polymeric fiber which is the product of the process of dispersing in said fiber about 1 percent to about 12 percent by weight of a polymer composition which is the reaction product of a polyoxyalkylene compound with a halogenated aliphatic or aromatic diacid, anhydride or acid halide thereof or a diol.

2. The flame-retardant antistatic fiber of claim 1 wherein said fiber is a polyamide fiber.

4,294,945

REDUCTION OF SCALE FORMATION DURING VINYL CHLORIDE POLYMERIZATION WITH TIN MERCAPTIDES

Chung H. Wei, Bolton, Mass., assignor to Stauffer Chemical Company, Westport, Conn.

Filed Apr. 21, 1980, Ser. No. 142,294

Int. Cl.³ C08F 2/44, 2/38, 2/18

U.S. Cl. 526—74

10 Claims

1. A process for the suspension polymerization of vinyl chloride which comprises polymerizing vinyl chloride monomer in an aqueous suspension polymerization medium in the presence of an effective amount of a composition consisting essentially of an organotin mercaptide having the formula $R_mSn(SR')_4-m$, where m is an integer from 1 to 3, R_m is a hydrocarbon group, and R' is selected from the group consisting of R_m and $-C(O)R_m$, and an epoxidized vegetable oil, during a substantial portion of the reaction, to lessen the amount of polymer scale formation from the polymerization reaction.

4,294,946

LOW RESIDUAL MONOMER

 α -METHYLSTYRENE-ACRYLONITRILE COPOLYMERS AND ABS BLENDS THEREFROM

Hiroyuki Minematsu, Niihama; Kojiro Matsumoto, Takarazuka; Tadashi Saeki, and Akira Kishi, both of Niihama, all of Japan, assignors to Sumitomo Naugatuck Co., Ltd., Japan

Continuation-in-part of Ser. No. 100,763, Dec. 6, 1979, abandoned. This application Jul. 21, 1980, Ser. No. 170,203


Claims priority, application Japan, Dec. 6, 1978, 53-151807; Dec. 6, 1978, 53-151808; Rep. of Korea, Dec. 6, 1979, 79-4310[U]

Int. Cl.³ C08F 2/22, 2/26

U.S. Cl. 526—80

6 Claims

1. A process for preparing a thermoplastic resin having high heat resistance by emulsion polymerization of a monomer mixture consisting essentially of α -alkylstyrene compound of the formula:



wherein R_1 is C_1 - C_3 alkyl and R_2 is hydrogen, C_1 - C_3 alkyl or halo(C_1 - C_3)alkyl and an unsaturated nitrile in a weight proportion of 65:35 to 80:20 in the presence of a radical initiator, characterized in that the whole amount of the α -alkylstyrene compound and 10 to 99% by weight of the unsaturated nitrile on the basis of its total amount are first subjected to polymeri-

zation and, after the polymerization, the remaining portion of the unsaturated nitrile is added to the reaction mixture and the resultant mixture is subjected to further polymerization until the polymerization is substantially completed.

4,294,947

PROCESS FOR THE PRODUCTION OF POWDERY, THERMOPLASTIC COPOLYMERS FROM ETHYLENE AND BUTENE-(1)

Klaus Doerk, Gladbeck; Klaus Koch, Kirchhellen; Horst Banke, Dorsten, and Bernhard Toben, Schermbeck, all of Fed. Rep. of Germany, assignors to Chemische Werke Huls Aktiengesellschaft, Herne, Fed. Rep. of Germany

Filed Nov. 1, 1979, Ser. No. 90,408

Claims priority, application Fed. Rep. of Germany, Nov. 4, 1978, 2847986

Int. Cl.³ C08F 2/14, 4/76

U.S. Cl. 526—119

17 Claims

1. A process for the production of a copolymer of ethylene and butene-(1) which comprises:

copolymerizing a mixture of ethylene and butene-(1) at 50°-95° C. and 10-100 bar in the presence of a catalyst which comprises (1) the reaction product of a chlorine and/or alkoxy-containing vanadyl (V) compound and an organic aluminum compound selected from the group consisting of ethylaluminum dichloride, diethylaluminum chloride, isobutylaluminum dichloride, diisobutylaluminum chloride and mixtures thereof, and (2) an aluminum alkyl activating compound therefor selected from the group consisting of aluminum trialkyls, alkyl aluminum sesquichloride, alkyl aluminum dichloride, and mixtures thereof;

wherein the polymerization reaction is carried out in a solvent which comprises liquid butene-(1); thereby obtaining a fluid powdery copolymer having a density up to about 0.930 g/cm³.

4,294,948

PROCESS FOR PREPARING OLEFIN POLYMERS OR COPOLYMERS, AND CATALYST FOR USE IN SAID PROCESS

Akinori Toyota, Iwakuni; Ken Yoshitugu, Ohtake, and Norio Kashiwa, Iwakuni, all of Japan, assignors to Mitsui Petrochemical Industries Ltd., Tokyo, Japan

Continuation of Ser. No. 880,584, Feb. 23, 1978, abandoned.

This application Oct. 12, 1979, Ser. No. 84,317

Claims priority, application Japan, Mar. 4, 1977, 52-22754

Int. Cl.³ C08F 4/02, 10/06

U.S. Cl. 526—125

7 Claims

1. A process for preparing an olefin polymer or copolymer by polymerizing or copolymerizing an olefin containing at least 3 carbon atoms which may contain at most 10 mole% of ethylene and/or a diene, at a temperature of about 0° to about 300° C., and a pressure of about 1 to about 7 kg/cm², in the presence of a catalyst composed of (A) a solid titanium catalyst component obtained by reacting a solid magnesium compound derived from (i) a halogen-containing magnesium compound, (ii) an active hydrogen-containing organic compound, (iii) an organic acid ester and (iv) an organometallic compound of metal of Groups II to III of periodic table, with a titanium compound, and (B) an organoaluminum compound; characterized in that the solid titanium catalyst component (A) is prepared by

(1) reacting a mechanically pulverized product of an aromatic carboxylic acid ester containing up to 20 carbon atoms, and a halogen-containing magnesium compound selected from the group consisting of magnesium dihalides, magnesium alkyl halides, magnesium alkoxy halides and magnesium phenoxy halides, said mechanically pulverized product being obtained by milling at a temperature of about 0° to about 100° C. during the period of about 1 hour to about 10 days, with an active hydrogen-

containing organic compound selected from the group consisting of aliphatic alcohols containing 1 to 8 carbon atoms, alicyclic alcohols containing 5 to 12 carbon atoms, aromatic alcohols containing 7 to 8 carbon atoms, and phenols containing 6 to 18 carbon atoms, in the absence of mechanical pulverization,

(2) reacting the resulting reaction product with an organometallic compound of a metal of Groups II to III of the periodic table selected from the group consisting of:

(a) organoaluminum compounds of the formula



wherein R^1 and R^2 are identical to, or different from, each other and represent an alkyl group containing 1 to 8 carbon atoms, X represents a halogen atom, m is more than 0 but not more than 3 ($0 < m \leq 3$), n is at least 0 but less than 3 ($0 \leq n < 3$), p is at least 0 but less than 3 ($0 \leq p < 3$), q is at least 0 but less than 3 ($0 \leq q < 3$), and $m + n + p + q = 3$, and

(b) compounds of the formula



wherein R^1 is as defined above, R^3 is the same as R^1 or represents a halogen atom, and M^2 represents magnesium, in the absence of mechanical pulverization, and

(3) washing the resulting solid reaction product with an inert organic solvent, reacting the washed solid reaction product with a titanium compound of the formula



wherein R represents a hydrocarbon group, X represents a halogen atom, and r is a number of 0 to 4 ($0 \leq r \leq 4$), in the absence of mechanical pulverization, and separating the solid from the reaction system, wherein the molar ratio of the organic acid ester and halogen-containing magnesium compound is from about 0.01 to 1 less than 1 to 1; the ratio of the mechanically pulverized product to the active hydrogen-containing organic compound is from about 0.01 to about 10 moles of organic compound per magnesium atom in the pulverized product; and the amount of the organometallic compound of a metal of Groups II to III of the periodic table is from about 0.01 moles to about 10 moles per mole of the active hydrogen-containing compound.

4,294,949

NOVEL POLYMERIC COMPOUNDS

Friedrich Karrer, Zofingen, Switzerland, assignor to Ciba-Geigy Corporation, Ardsley, N.Y.

Continuation-in-part of Ser. No. 924,417, Jul. 13, 1978, Pat. No. 4,210,612. This application Jan. 25, 1980, Ser. No. 115,277


Claims priority, application Switzerland, Jul. 19, 1977, 8915/77

Int. Cl.³ C08F 226/06


U.S. Cl. 526—262

12 Claims


1. A copolymer of a compound which carries N-heterocyclic rings in a side position and has the recurring structural unit of the formula I




in which R_1 is a group, containing an N-heterocyclic ring, of the formulae II, III, IV and V



in which R_5 is hydrogen, oxyl, C_1 - C_{18} alkyl, 2-hydroxyethyl, 2-hydroxypropyl, C_3 - C_8 alkenyl, C_3 - C_6 alkynyl, C_7 - C_{12} aralkyl, C_2 - C_{21} alkoxyalkyl, an aliphatic acyl group having 1-4 C atoms or one of the groups $-CH_2COOR_7$ or $-COOR_8$, in which R_7 is C_1 - C_{12} alkyl, C_3 - C_8 alkenyl, phenyl, C_7 - C_8 aralkyl or cyclohexyl and R_8 is C_1 - C_{12} alkyl, phenyl, benzyl or cyclohexyl, and R_6 is hydrogen or C_1 - C_4 alkyl and Y is $-O-$ or



in which R_9 is hydrogen, C_1 - C_{12} alkyl, C_7 - C_{12} aralkyl or cyclohexyl, and X_1 is a group of the formula $-O-CH(R_{10})-CH_2-$ (VI) or denotes $-O-CH_2-CH_2-CH_2-$, in which R_{10} is hydrogen, methyl, ethyl, phenoxyethyl or phenyl, and n is 0 or 1, and X_2 is a group of the formula VI, in which R_{10} is as defined above, or a group of the formula $-O-CH_2-CH(OH)-CH_2-$ (VII), and m is 0 or 1, and R_{11} is C_1 - C_{18} alkyl or is cyclohexyl, phenyl or benzyl which are unsubstituted or substituted by C_1 - C_4 alkyl or C_1 - C_4 alkoxy, and R_2 is hydrogen or C_1 - C_4 alkyl, and, if R_2 and R_4 are hydrogen, R_1 and R_3 together form a group of the formula VIII



in which R_5 and R_6 are as defined above and R_3 is hydrogen or C_1 - C_2 alkyl and R_4 is hydrogen or methyl, with a compound containing at least one polymerisable double bond, the molar ratio of the component of the formula I to the co-component being up to 1:10.

4,294,950

COATING COMPOSITION COMPRISING
HYDROLYZATES FROM SILANE COMPOUNDS
Hirohisa Kato, Aichi, Japan, assignor to Ito Optical Industrial
Co., Ltd., Gamagori, Japan


Filed Jan. 30, 1980, Ser. No. 116,946

Claims priority, application Japan, Feb. 16, 1979, 54-17716
Int. Cl.³ C08G 77/06


U.S. Cl. 528—14

7 Claims

1. A coating composition comprising:
(A) at least one hydrolyzate selected from the group consisting of a hydrolyzate of a silicon compound of the general formula



wherein R¹ is hydrogen or CH₃, R² is alkylene of 1-4 carbon atoms, and R³ is alkyl of 1-4 carbon atoms, and a hydrolyzate of a silicon compound of the general formula



wherein R¹ is alkylene of 1-4 carbon atoms and R² is alkyl of 1-4 carbon atoms;

(B) a compound selected from the group consisting of unsaturated and saturated polyvalent carboxylic acids and anhydrides thereof; and
(C) a curing agent.

4,294,951

RAPID CURING POLYURETHANE ELASTOMER
PREPARED FROM A
DIPHENYLMETHANEDIISOCYANATE BASED LIQUID
PREPOLYMER AND A CURING AGENT CONTAINING A
POLYTETRAMETHYLENE ETHER GLYCOL, A DIOL
AND AN ORGANOMETALLIC CATALYST

Toshio Sugita, Yokohama; Hiroaki Sakaguchi, Ashiya;
Hisanobu Tsuda, Kamakura, and Tsuyoshi Suzuki, Kawasaki,
all of Japan, assignors to Mitsui-Nisso Corporation, Tokyo,
Japan

Filed Jul. 14, 1980, Ser. No. 168,482

Int. Cl.³ C08G 18/72

U.S. Cl. 528—55

13 Claims

1. A rapid curing polyurethane elastomer, said elastomer being prepared by a process comprising mixing:

A. a prepolymer which is liquid at room temperature and which is prepared by reacting:

1. about 4 to about 6 equivalents of a mixture of diphenylmethanediisocyanate and a carbodiimide modified material of said diisocyanate, said modified material being liquid at room temperature, with

2. about one equivalent of polytetramethylene ether glycol having a mean molecular weight of from about 650 to about 2000, or with about one equivalent of a mixture of said polytetramethylene ether glycol and an aliphatic diol having a molecular weight less than about 250, and

B. a curing agent consisting essentially of a mixture of about one equivalent of said polytetramethylene ether glycol, about one to about four equivalents of a diol having a molecular weight less than about 250 as a chain-elongating agent, and an organometallic catalyst,

the weight ratio of the prepolymer to the curing agent being such that the NCO/OH equivalent ratio is about 1.00 to about 1.10.

4,294,952

POLYAMIDE-IMIDE RESIN AND ITS PRODUCTION
Yoshiyuki Mukoyama, Hitachi, and Tonichi Sakata, Katsuta,
both of Japan, assignors to Hitachi Chemical Company, Ltd.,
Tokyo, Japan

Filed Nov. 16, 1979, Ser. No. 94,938

Claims priority, application Japan, Nov. 30, 1978, 53-148820;
Dec. 28, 1978, 53-164753; Mar. 22, 1979, 54-33921

Int. Cl.³ C08G 18/73, 18/74, 18/75, 18/76

U.S. Cl. 528—67

16 Claims

1. A polyamide-imide resin obtained by reacting in a cresol type solvent a polyisocyanate containing isocyanurate rings, an aromatic diisocyanate, a lactam and a polycarboxylic acid containing at least one acid anhydride group at a temperature of 160° to 230° C., said polyisocyanate being used in an amount of 1 to 30 equivalent % based on the total isocyanate equivalent and said lactam being used in an amount of 20 to 80 equivalent % based on the total isocyanate equivalent; with the amounts of the isocyanate and the acid being 1.5 to 0.71/1 in terms of a ratio of the carboxyl group and the acid anhydride group to the isocyanate group.

4,294,953

PROCESS FOR PREPARING A BRANCHED
POLYCARBONATE

Clayton B. Quinn, and William Hilakos, both of Mt. Vernon,
Ind., assignors to General Electric Company, Mt. Vernon,
Ind.

Filed May 31, 1979, Ser. No. 44,040

Int. Cl.³ C08G 63/62

U.S. Cl. 528—128

7 Claims

1. A process for producing a thermoplastic, randomly branched polycarbonate substantially free of cross-linking which consists essentially of reacting, at a pH of about 9 to 12, a carbonate precursor, a dihydric phenol, and a dianhydride branching agent, to thereby produce a thermoplastic randomly branched polycarbonate.

4,294,954

POLYCARBONATE COPOLYMERS

Charles M. Orlando, Schenectady, and George R. Loucks, Scotia, both of N.Y., assignors to General Electric Company, Schenectady, N.Y.


Filed Dec. 13, 1979, Ser. No. 103,215

Int. Cl.³ C08G 63/62

U.S. Cl. 528—174


2 Claims

1. Polycarbonates consisting essentially of about (a) 5 to 70 mole percent of carbonate units of the formula,




chemically combined with about

(b) 95 to 30 mole percent of carbonate units of the formula,



where R is a C₍₆₋₁₃₎ divalent aromatic organic radical, Z is a member selected from —S—, —O—,



and a C₍₄₋₈₎ cycloaliphatic radical and a is equal to 0 or 1.

4,294,955

POLYMERS FROM PHENYLTEREPHTHALIC ACID
John F. Harris, Jr., Wilmington, Del., assignor to E. I. Du Pont
de Nemours and Company, Wilmington, Del.


Filed Dec. 10, 1979, Ser. No. 102,040

Int. Cl.³ C08G 63/18


U.S. Cl. 528—176

7 Claims

1. A fiber forming melt-spinnable (co)polyester consisting essentially of units having the structural formulas




or a combination of (1) and up to 50 mol % of



wherein R¹ is 1,4-phenylene, 2,6-naphthalene, 4,4'-biphenylene or mixtures thereof, and

(3) —O—R²—O— wherein R² is 1,4-phenylene, 2,6-naphthalene, 1,4-naphthalene, 4,4'-biphenylene or mixtures thereof or a combination of (3) with up to 20 mol % of



based on the total mols of dioxy units present.

4,294,956

PROCESS FOR PREPARING POLYARYLATES IN THE
PRESENCE OF A DIPHENYL ETHER

Mitchell H. Berger, Somerville; Peter J. Gill, North Brunswick,
and Louis M. Maresca, Belle Mead, all of N.J., assignors to
Union Carbide Corporation, New York, N.Y.

Filed Aug. 27, 1979, Ser. No. 69,818


Int. Cl.³ C08G 63/18, 63/28, 63/66

U.S. Cl. 528—179

17 Claims

1. A process for preparing a polyarylate having a reduced viscosity of from about 0.5 to greater than 1.0 gl/gm, which process comprises reacting:

(a) at least one diester derivative of a dihydric phenol having the following formula:



wherein R is independently selected from an alkyl radical having from 1 to about 6 carbon atoms, or cycloalkyl

having from 4 to about 7 carbon atoms, y is independently selected from alkyl groups of 1 to 4 carbon atoms, chlorine, or bromine, z independently has a value of from 0 to 4, inclusive, and R' is independently selected from a divalent saturated aliphatic hydrocarbon radical having 1 to 8 carbon atoms, a cycloalkylene or cycloalkylidene radical having up to and including 9 carbon atoms, O, S, SO, SO₂, CO, x is 0 or 1; with

(b) at least one aromatic dicarboxylic acid, in the presence of from about 10 to about 60 weight percent, based on the polyarylate produced, of a diphenyl ether compound, at a temperature of from about 260° to about 350° C., said reaction being conducted in the absence of catalyst.

4,294,957

PROCESS FOR PREPARING POLYARYLATES

Mitchell H. Berger, Somerville; Louis M. Maresca, Belle Mead,
and Markus Matzner, Edison, all of N.J., assignors to Union
Carbide Corporation, New York, N.Y.

Filed Aug. 27, 1979, Ser. No. 69,819


Int. Cl.³ C08G 63/46, 63/18

U.S. Cl. 528—179

15 Claims

1. A process for preparing polyarylate having a reduced viscosity of from about 0.5 to greater than 1.0 dl/gm and improved color which process comprises reacting, at a temperature of from about 260° to about 350° C.:

(a) at least one diester derivative of a dihydric phenol having the following formula:



wherein R is independently selected from an alkyl radical having from 1 to about 6 carbon atoms or cycloalkyl having from 4 to about 7 carbon atoms, y is independently selected from alkyl groups of 1 to 4 carbon atoms, chlorine, or bromine, z independently has a value of from 0 to 4, inclusive, and R' is independently selected from a divalent saturated aliphatic hydrocarbon radical having 1 to 8 carbon atoms, a cycloalkylene, or cycloalkylidene radical having up to and including 9 carbon atoms, O, S, SO, SO₂, CO, x is 0 or 1; with

(b) at least one aromatic dicarboxylic acid, in the presence of from about 10 to about 60 weight percent, based on the polyarylate produced, of at least one cycloaliphatic, substituted aromatic or heteroaromatic compound, which compounds contain at least one benzylic and/or tertiary hydrogen atom, and have a boiling point of about 150° to about 350° C. at atmospheric pressure.

4,294,958

WATER-SOLUBLE SALTS OF TRIMETHYLAMMONIUM
DERIVATIVES OF POLYENE MACROLIDE
ANTIBIOTICS AND THE PREPARATION THEREOF

Leonard Falkowski, Gdansk; Barbara Stefanska, Gdansk-Oliwa;
Jan Zielinski, Gdansk-Oliwa; Elzbieta Troka, Gdansk-Oliwa;
Jerzy Golik, Sopot; Pawel Kolodziejczyk, Gdansk-Wrzeszcz;
Andrzej Jarzebski, Gdansk; Emilia Cybulska, Gdansk-Oliwa,
and Edward Borowski, Gdansk-Wrzeszcz all of Poland, as-
signors to Politechnika Gdanska, Gdansk, Poland

Filed Jul. 25, 1979, Ser. No. 60,427

Claims priority, application Poland, Jul. 19, 1978, 208519

Int. Cl.³ C07H 17/08

U.S. Cl. 536—17 R

4 Claims

1. An antibiotically-active water-soluble salt of a trimethylammonium derivative of a polyene macrolide having the general formula:

4,294,967

N-ACYL-PIPERIDONE COMPOUNDS

Hans-Jochem Riebel, Wuppertal; Ludwig Eue, Leverkusen, and Wilfried Faust, Odenthal, all of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Sep. 8, 1980, Ser. No. 184,728


Claims priority, application Fed. Rep. of Germany, Sep. 21, 1979, 2938155

Int. Cl.³ C07D 217/74; A01N 43/40

U.S. Cl. 546—242

3 Claims

1. An N-Acyl-piperidone of the formula



wherein R is methyl or chloro.

4,294,968

METHOD FOR PREPARING α -PICOLINE FROM 5-OXOHAXANENITRILE

Frederick C. Stone, and Gary G. Schupka, both of Midland, Mich., assignors to The Dow Chemical Company, Midland, Mich.

Continuation of Ser. No. 53,635, Jun. 29, 1979, abandoned. This application Jul. 7, 1980, Ser. No. 166,512

Int. Cl.³ C07D 213/08, 213/09

U.S. Cl. 546—251

4 Claims

1. In a method of preparing α -picoline comprising contacting under dehydrogenation conditions 5-oxohexanenitrile with a palladium dehydrogenation catalyst, the improvement wherein the catalyst is palladium on a carbon support.

4,294,969

PROCESS FOR PRODUCING 2-BROMO-3,5-DISUBSTITUTED PYRIDINES

John J. Baldwin, and Gerald S. Ponticello, both of Lansdale, Pa., assignors to Merck & Co., Inc., Rahway, N.J.


Division of Ser. No. 7,092, Jan. 29, 1979, which is a continuation-in-part of Ser. No. 866,961, Jan. 4, 1978, abandoned. This application Jul. 11, 1980, Ser. No. 167,577

Int. Cl.³ C07D 213/55, 213/57


U.S. Cl. 546—286

2 Claims


1. A process for preparing compounds of the formula



wherein R₃ is COOC₂H₅ or CN and R₅ is CHO or —COOC₂H₅ which comprises (1) reacting a compound of the formula



with N-Bromosuccinimide in the presence of a peroxide and U.V. light and (2) hydrolyzing the resultant compound of the formula



where R₅ is —CH₂Br, —CHBr₂ or CBr₃ using AgNO₃.

4,294,970

OXIDATION OF ALPHA-ALKYLATED, BENZYL-SUBSTITUTED 2-THIOPYRIDINE 1-OXIDES

Howard L. Plant, Milford, and Glenn S. Peterson, Watertown, both of Conn., assignors to Uniroyal, Inc., New York, N.Y.


Filed Feb. 4, 1980, Ser. No. 118,175

Int. Cl.³ C07D 213/62

U.S. Cl. 546—294

10 Claims

1. A method of oxidizing alphaalkylated, benzyl-substituted 2-thio pyridine 1-oxides having the general formula



where R is alkyl having from 1 to 8 carbon atoms and n is 1 or 2, said method comprising reacting the compound to be oxidized with acetonitrile and hydrogen peroxide in a solvent for said compound selected from the group consisting of methanol, propanol and butanol, the pH of the reaction mixture being maintained at about 9.0 to about 9.5 with a metal hydroxide.

4,294,971

PREPARATION OF N-ARYLOXAZOLIDINE-2,4-DIONES


Franz Merger, Frankenthal, and Friedrich Towae, Ludwigshafen, both of Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Fed. Rep. of Germany

Filed Mar. 6, 1980, Ser. No. 127,759


U.S. Cl. 548—226

10 Claims


1. A process for the preparation of an N-aryloxazolidine-2,4-dione of the formula



where the individual radicals R¹ and R² may be identical or different and each is hydrogen or an aliphatic, cycloaliphatic, araliphatic or aromatic radical, the two radicals R² may also together be a methylene radical and R¹ may also be halogen or —X—R³, where R³ is an aliphatic radical and X is oxygen or sulfur, wherein a nitrobenzene of the formula



where R¹ has the above meaning, is reacted with a 2-hydroxycarboxylic acid ester of the formula



where R² and R³ have the above meanings, and with carbon monoxide in the presence of selenium and a basic compound under superatmospheric pressure at an elevated temperature.

4,294,972

1,2-DISUBSTITUTED OXO TRIAZOLIDINE

Frederick Cassidy, and Alexander C. Goudie, both of Harlow, England, assignors to Beecham Group Limited, England

Filed Jun. 14, 1979, Ser. No. 48,390


Claims priority, application United Kingdom, Jun. 15, 1978, 27060/78

Int. Cl.³ A61K 31/41; C07D 249/12

U.S. Cl. 548—264

14 Claims

1. A compound of the formula:



and salts thereof wherein

n is 4;

Y is —CH₂CH₂—;

L is O or S;

R₁ is alkyl of from 1 to 4 carbon atoms;R₂ is hydrogen or alkyl of 1 to 4 carbon atoms;R₃ is hydroxy;R₄ is alkyl of 1 to 9 carbon atoms; andR₅ is alkyl of 1 to 6 carbon atoms.

4,294,973

PROCESS FOR THE PREPARATION OF DIACYLATED 4-IMIDAZOLIN-2-ONES

Karl-Heinz Scholz; Willy Hartmann, and Hans-Georg Heine, all of Krefeld, Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Division of Ser. No. 884,520, Mar. 8, 1978, Pat. No. 4,238,618. This application Dec. 10, 1979, Ser. No. 101,610

Claims priority, application Fed. Rep. of Germany, Mar. 26, 1977, 2713431


Int. Cl.³ C07D 233/70

U.S. Cl. 548—320

6 Claims

1. A process for the preparation of a diacylated 4-imidazolin-2-one of the formula


II



wherein

R¹ and R² independently represent hydrogen, alkyl, which can be substituted by a C₁₋₂ alkoxy radical or a halogen, cycloalkyl which can be C₁₋₄ alkyl substituted, aryl which can be C₁₋₄ alkyl or C₁₋₂ alkoxy or halogen substituted or alkoxy, the alkyl, cycloalkyl, aryl or alkoxy groups representing

R¹ and R² having up to 10 carbon atoms, which comprises contact a compound of the formula



wherein

R¹ and R² have the previously assigned significance with an equimolar amount of chlorine or sulphuryl chloride at a temperature from 20° to 150° C. in the presence of a peroxide, peracid ester or azoalkane radical forming agent or under ultra-violet light to monohalogenate the same and thereafter dehydrohalogenating the resultant monohalogenated product by:

A. Subjecting the monochlorinated product to a temperature of 100° to 250° C. at reduced pressure; or

B. contacting the same with a tertiary amine.

4,294,974

HYDROPHILIC SILICONE COMPOUNDS AND CONTACT LENSES CONTAINING POLYMERS THEREOF

Albert R. LeBoeuf, Framingham, Mass., assignor to American Optical Corporation, Southbridge, Mass.

Division of Ser. No. 8,301, Jan. 31, 1979, Pat. No. 4,261,875.


This application Dec. 17, 1979, Ser. No. 104,259

Int. Cl.³ C07F 7/08, 7/18

U.S. Cl. 556—440

11 Claims

1. A hydrophilic siloxane having the formula:



wherein R is an alkyl having 1 to 3 carbons, a+b+c+d=e, b=0 to e, c=0 to e, b+c>1, d=1 to 5, e=1 to 100, and Y is an organic group containing at least one >C=C<.

4,294,975

HYDROALKENYLOXYSILANES

Toshio Takago; Masatoshi Arai, and Koji Futatsumori, all of Annaka, Japan, assignors to Shin-Etsu Chemical Co. Ltd., Tokyo, Japan


Filed May 20, 1980, Ser. No. 151,696

Claims priority, application Japan, May 31, 1979, 54/67706
Int. Cl.³ C07F 7/04, 7/18

U.S. Cl. 556—482

5 Claims

1. A hydrogenalkenyloxysilane represented by the general formula



in which R¹ is a monovalent hydrocarbon group having from 1 to 8 carbon atoms, R², R³ and R⁴ are each independently a hydrogen atom or a monovalent hydrocarbon group having from 1 to 8 carbon atoms and n is a number of zero, 1 or 2.

4,294,976

PROCESS FOR PRODUCING BIPHENYL COMPOUNDS
Hiroshi Itatani, Chiba; Hataaki Yoshimoto, Ichihara; Akinori Shiotani, Ichihara; Akiyoshi Yokota, Ichihara, and Motozoh Yoshikiyo, Ichihara, all of Japan, assignors to UBE Industries, Ltd., Ube, Japan

Filed Aug. 31, 1979, Ser. No. 71,089

Claims priority, application Japan, Sep. 5, 1978, 53/108097
Int. Cl.³ C07C 69/76, 179/02, 15/14

U.S. Cl. 560—76

11 Claims

1. A process for producing a biphenyl compound, comprising dehydrogenatively dimerizing an aromatic monocyclic compound selected from the group consisting of benzene and substituted benzene compounds having 1 to 4 substituents attached to the benzene ring thereof, with molecular oxygen in the presence of oxalic acid together with a catalyst comprising at least one organic palladium salt, under a pressurized condition, and, isolating the resulting biphenyl compound from the reaction mixture.

4,294,977

PROCESS FOR PRODUCING AROMATIC CARBOXYLIC ACIDS

Raymond A. Schep, Newport Beach, Calif., assignor to Occidental Research Corporation, Irvine, Calif.

Continuation of Ser. No. 883,933, Mar. 6, 1978, abandoned. This application Sep. 24, 1979, Ser. No. 78,401

Int. Cl.³ C07C 51/21


U.S. Cl. 562—407

27 Claims

8. A process for producing benzene carboxylic acid from coal comprising:

a. treating in an oxidation zone a mixture of coal, water, and calcined oil shale with oxygen, at a temperature of from about 200° to about 350° C., a pressure of from about 250 to about 2000 psig, and a reaction time of from about 10 minutes to about 3 hours, wherein the amount of said calcined oil shale is about 1 to about 10 parts by weight of said calcined oil shale per part by weight of said coal, to convert said coal to a benzene carboxylic acid salt thereby producing a second mixture containing dissolved therein said benzene carboxylic acid salt;

b. removing solids comprising said calcined oil shale from said second mixture thereby producing a solution;



c. treating said solution with an acid to convert said benzene carboxylic acid salt dissolved therein to a benzene carboxylic acid; and

d. recovering said benzene carboxylic acid thusly formed.

4,294,978

13,14-DIDEHYDRO-19-OXO-PGF₂ COMPOUNDS

John C. Sih, Kalamazoo, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.


Division of Ser. No. 25,879, Apr. 2, 1979. This application Mar. 20, 1980, Ser. No. 132,000

Int. Cl.³ C07C 177/00

U.S. Cl. 562—503

4 Claims

1. A compound of the formula



wherein D is

- (1) cis-CH=CH-CH₂-(CH₂)_g-CH₂—,
- (2) cis-CH=CH-CH₂-(CH₂)_g-CF₂—,
- (3) cis-CH₂-CH=CH-CH₂-CH₂—, or
- (4) trans-(CH₂)₃-CH=CH—;

wherein g is zero, one, two, or three;

wherein Q is α-OH:β-R₅ or α-R₅:β-OH, wherein R₅ is hydrogen or methyl;

wherein R₆ is

- (a) hydrogen,
- (b) alkyl of one to 12 carbon atoms, inclusive,
- (c) cycloalkyl of 3 to 10 carbon atoms, inclusive,
- (d) aralkyl of 7 to 12 carbon atoms, inclusive,
- (e) phenyl,
- (f) phenyl substituted with one, 2, or 3 chloro or alkyl groups of one to 3 carbon atoms, inclusive,
- (g) —(p-Ph)—CO—CH₃,
- (h) —(p-Ph)—NH—CO—(p-Ph)—NH—CO—CH₃,
- (i) —(p-Ph)—NH—CO—(p-Ph),
- (j) —(p-Ph)—NH—CO—CH₃,
- (k) —(p-Ph)—NH—CO—NH₂,
- (l) —(p-Ph)—CH=N—NH—CO—NH₂,
- (m) β-naphthyl,

(n) —CH₂—CO—R₂₈,

wherein (p-Ph) is para-phenyl or inter-para-phenylene, wherein R₂₈ is phenyl, p-bromophenyl, p-biphenyl, p-nitrophenyl, p-benzamidophenyl, or 2-naphthyl, or

(o) a pharmacologically acceptable cation;

wherein R₃ and R₄ are hydrogen, methyl, or fluoro, being the same or different, with the proviso that one of R₃ and R₄ is fluoro only when the other is hydrogen or fluoro; and wherein X is —C≡C—.

4,294,980

13,14-DIHYDRO-11-DEOXY-11-HYDROXYMETHYL-19-OXO-PGF₁ COMPOUNDS

John C. Sih, Kalamazoo, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.


Division of Ser. No. 25,879, Apr. 2, 1979. This application Mar. 20, 1980, Ser. No. 132,010

Int. Cl.³ C07C 177/00

U.S. Cl. 562—503

4 Claims

1. A compound of the formula



wherein D is

- (1) (CH₂)₃—(CH₂)_g—CH₂—, or
- (2) (CH₂)₃—(CH₂)_g—CF₂—;

wherein g is zero, one, two, or three;

wherein Q is α-OH:β-R₅ or α-R₅:β-OH, wherein R₅ is hydrogen or methyl;

wherein R₆ is

- (a) hydrogen,
- (b) alkyl of one to 12 carbon atoms, inclusive,
- (c) cycloalkyl of 3 to 10 carbon atoms, inclusive,
- (d) aralkyl of 7 to 12 carbon atoms, inclusive,
- (e) phenyl,
- (f) phenyl substituted with one, 2, or 3 chloro or alkyl groups of one to 3 carbon atoms, inclusive,
- (g) —(p-Ph)—CO—CH₃,
- (h) —(p-Ph)—NH—CO—(p-Ph)—NH—CO—CH₃,
- (i) —(p-Ph)—NH—CO—(p-Ph),
- (j) —(p-Ph)—NH—CO—CH₃,
- (k) —(p-Ph)—NH—CO—NH₂,
- (l) —(p-Ph)—CH=N—NH—CO—NH₂,
- (m) β-naphthyl,
- (n) —CH₂—CO—R₂₈,

wherein (p-Ph) is para-phenyl or inter-para-phenylene

wherein R₂₈ is phenyl, p-bromophenyl, p-biphenyl, p-nitrophenyl, p-benzamidophenyl, or 2-naphthyl, or

(o) a pharmacologically acceptable cation;

wherein R₃ and R₄ are hydrogen, methyl, or fluoro, being the same or different, with the proviso that one of R₃ and R₄ is fluoro only when the other is hydrogen or fluoro; and

wherein X is —CH₂CH₂—.

4,294,981

13,14-DIDEHYDRO-11-DEOXY-9-DEOXY-9-METHYLENE-19-OXO-PGF₁ COMPOUNDS

John C. Sih, Kalamazoo, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.


Division of Ser. No. 25,879, Apr. 2, 1979. This application Mar. 20, 1980, Ser. No. 132,035

Int. Cl.³ C07C 177/00

U.S. Cl. 562—503

4 Claims

1. A compound of the formula



wherein D is

4,294,979

13,14-DIHYDRO-11-DEOXY-11-HYDROXYMETHYL-19-OXO-PGE₂ COMPOUNDS

John C. Sih, Kalamazoo, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.


Division of Ser. No. 25,879, Apr. 2, 1979. This application Mar. 20, 1980, Ser. No. 132,005

Int. Cl.³ C07C 177/00

U.S. Cl. 562—503

4 Claims

1. A compound of the formula



wherein D is

- (1) cis-CH=CH-CH₂-(CH₂)_g-CH₂—,
- (2) cis-CH=CH-CH₂-(CH₂)_g-CF₂—,
- (3) cis-CH₂-CH=CH-CH₂-CH₂—, or
- (4) trans-(CH₂)₃-CH=CH—;

wherein g is zero, one, two, or three;

wherein Q is α-OH:β-R₅ or α-R₅:β-OH, wherein R₅ is hydrogen or methyl;

wherein R₆ is

- (a) hydrogen,
- (b) alkyl of one to 12 carbon atoms, inclusive,
- (c) cycloalkyl of 3 to 10 carbon atoms, inclusive,
- (d) aralkyl of 7 to 12 carbon atoms, inclusive, (e) phenyl,
- (f) phenyl substituted with one, 2, or 3 chloro or alkyl groups of one to 3 carbon atoms, inclusive,
- (g) —(p-Ph)—CO—CH₃,
- (h) —(p-Ph)—NH—CO—(p-Ph)—NH—CO—CH₃,
- (i) —(p-Ph)—NH—CO—(p-Ph),
- (j) —(p-Ph)—NH—CO—CH₃,
- (k) —(p-Ph)—NH—CO—NH₂,
- (l) —(p-Ph)—CH=N—NH—CO—NH₂,
- (m) β-naphthyl,
- (n) —CH₂—CO—R₂₈,

wherein (p-Ph) is para-phenyl or inter-para-phenylene,

wherein R₂₈ is phenyl, p-bromophenyl, p-biphenyl, p-nitrophenyl, p-benzamidophenyl, or 2-naphthyl, or

(o) a pharmacologically acceptable cation;

wherein R₃ and R₄ are hydrogen, methyl, or fluoro, being the same or different, with the proviso that one of R₃ and R₄ is fluoro only when the other is hydrogen or fluoro; and

wherein X is —CH₂CH₂—.

(1) $(\text{CH}_2)_3-(\text{CH}_2)_g-\text{CH}_2-$, or
 (2) $(\text{CH}_2)_3-(\text{CH}_2)_g-\text{CF}_2-$;
 wherein g is zero, one, two, or three;
 wherein Q is $\alpha\text{-OH}:\beta\text{-R}_5$ or $\alpha\text{-R}_5:\beta\text{-OH}$, wherein R_5 is hydrogen or methyl;
 wherein R_6 is
 (a) hydrogen,
 (b) alkyl of one to 12 carbon atoms, inclusive,
 (c) cycloalkyl of 3 to 10 carbon atoms, inclusive,
 (d) aralkyl of 7 to 12 carbon atoms, inclusive,
 (e) phenyl,
 (f) phenyl substituted with one, 2, or 3 chloro or alkyl groups of one to 3 carbon atoms, inclusive,
 (g) $-(\text{p-Ph})-\text{CO}-\text{CH}_3$,
 (h) $-(\text{p-Ph})-\text{NH}-\text{CO}-(\text{p-Ph})-\text{NH}-\text{CO}-\text{CH}_3$,
 (i) $-(\text{p-Ph})-\text{NH}-\text{CO}-(\text{p-Ph})$,
 (j) $-(\text{p-Ph})-\text{NH}-\text{CO}-\text{CH}_3$,
 (k) $-(\text{p-Ph})-\text{NH}-\text{CO}-\text{NH}_2$,
 (l) $-(\text{p-Ph})-\text{CH}=\text{N}-\text{NH}-\text{CO}-\text{NH}_2$,
 (m) β -naphthyl,
 (n) $-\text{CH}_2-\text{CO}-\text{R}_{28}$,
 wherein (p-Ph) is para-phenyl or inter-para-phenylene,
 wherein R_{28} is phenyl, p-bromophenyl, p-biphenyl, p-nitrophenyl, p-benzamidophenyl, or 2-naphthyl, or
 (o) a pharmacologically acceptable cation;
 wherein R_3 and R_4 are hydrogen, methyl, or fluoro, being the same or different, with the proviso that one of R_3 and R_4 is fluoro only when the other is hydrogen or fluoro;
 and
 wherein X is $-\text{C}\equiv\text{C}-$.


4,294,982

13,14-DIDEHYDRO-11-DEOXY-19-OXO-PGE₁ COMPOUNDS

John C. Sih, Kalamazoo, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.
 Division of Ser. No. 25,879, Apr. 2, 1979. This application Mar. 20, 1980, Ser. No. 132,036
 Int. Cl.³ C07C 177/00

U.S. Cl. 562-503

1. A compound of the formula



wherein D is

(1) $(\text{CH}_2)_3-(\text{CH}_2)_g-\text{CH}_2-$, or
 (2) $(\text{CH}_2)_3-(\text{CH}_2)_g-\text{CF}_2-$;
 wherein g is zero, one, two, or three; wherein Q is $\alpha\text{-OH}:\beta\text{-R}_5$ or $\alpha\text{-R}_5:\beta\text{-OH}$, wherein R_5 is hydrogen or methyl;
 wherein R_6 is
 (a) hydrogen,
 (b) alkyl of one to 12 carbon atoms, inclusive,
 (c) cycloalkyl of 3 to 10 carbon atoms, inclusive,
 (d) aralkyl of 7 to 12 carbon atoms, inclusive,
 (e) phenyl,
 (f) phenyl substituted with one, 2, or 3 chloro or alkyl groups of one to 3 carbon atoms, inclusive,
 (g) $-(\text{p-Ph})-\text{CO}-\text{CH}_3$,
 (h) $-(\text{p-Ph})-\text{NH}-\text{CO}-(\text{p-Ph})-\text{NH}-\text{CO}-\text{CH}_3$,
 (i) $-(\text{p-Ph})-\text{NH}-\text{CO}-(\text{p-Ph})$,
 (j) $-(\text{p-Ph})-\text{NH}-\text{CO}-\text{CH}_3$,
 (k) $-(\text{p-Ph})-\text{NH}-\text{CO}-\text{NH}_2$,
 (l) $-(\text{p-Ph})-\text{CH}=\text{N}-\text{NH}-\text{CO}-\text{NH}_2$,
 (m) β -naphthyl,
 (n) $-\text{CH}_2-\text{CO}-\text{R}_{28}$,
 wherein (p-Ph) is para-phenyl or inter-para-phenylene,

wherein R_{28} is phenyl, p-bromophenyl, p-biphenyl, p-nitrophenyl, p-benzamidophenyl, or 2-naphthyl, or
 (o) a pharmacologically acceptable cation;
 wherein R_3 and R_4 are hydrogen, methyl, or fluoro, being the same or different, with the proviso that one of R_3 and R_4 is fluoro only when the other is hydrogen or fluoro; and wherein X is $-\text{C}\equiv\text{C}-$.

4,294,983

13,14-DIDEHYDRO-11-DEOXY-19-OXO-PGF₁ COMPOUNDS


John C. Sih, Kalamazoo, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.

Filed Mar. 20, 1980, Ser. No. 132,037

Int. Cl.³ C07C 177/00

U.S. Cl. 562-503

1. A compound of the formula



wherein D is

(1) $(\text{CH}_2)_3-(\text{CH}_2)_g-\text{CH}_2-$, or
 (2) $(\text{CH}_2)_3-(\text{CH}_2)_g-\text{CF}_2-$;
 wherein g is zero, one, two, or three; wherein Q is $\alpha\text{-OH}:\beta\text{-R}_5$ or $\alpha\text{-R}_5:\beta\text{-OH}$, wherein R_5 is hydrogen or methyl;
 wherein R_6 is
 (a) hydrogen,
 (b) alkyl of one to 12 carbon atoms, inclusive,
 (c) cycloalkyl of 3 to 10 carbon atoms, inclusive,
 (d) aralkyl of 7 to 12 carbon atoms, inclusive,
 (e) phenyl,
 (f) phenyl substituted with one, 2, or 3 chloro or alkyl groups of one to 3 carbon atoms, inclusive,
 (g) $-(\text{p-Ph})-\text{CO}-\text{CH}_3$,
 (h) $-(\text{p-Ph})-\text{NH}-\text{CO}-(\text{p-Ph})-\text{NH}-\text{CO}-\text{CH}_3$,
 (i) $-(\text{p-Ph})-\text{NH}-\text{CO}-(\text{p-Ph})$,
 (j) $-(\text{p-Ph})-\text{NH}-\text{CO}-\text{CH}_3$,
 (k) $-(\text{p-Ph})-\text{NH}-\text{CO}-\text{NH}_2$,
 (l) $-(\text{p-Ph})-\text{CH}=\text{N}-\text{NH}-\text{CO}-\text{NH}_2$,
 (m) β -naphthyl,
 (n) $-\text{CH}_2-\text{CO}-\text{R}_{28}$,
 wherein (p-Ph) is para-phenyl or inter-para-phenylene,
 wherein R_{28} is phenyl, p-bromophenyl, p-biphenyl, p-nitrophenyl, p-benzamidophenyl, or 2-naphthyl, or
 (o) a pharmacologically acceptable cation;
 wherein R_3 and R_4 are hydrogen, methyl, or fluoro, being the same or different, with the proviso that one of R_3 and R_4 is fluoro only when the other is hydrogen or fluoro; and wherein X is $-\text{C}\equiv\text{C}-$.

4,294,984

13,14-DIDEHYDRO-11-DEOXY-11-HYDROXYMETHYL-9-DEOXY-9-METHYLENE-19-OXO-PGF₁ COMPOUNDS

John C. Sih, Kalamazoo, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.

Division of Ser. No. 25,879, Apr. 2, 1979. This application Mar. 20, 1980, Ser. No. 132,038

Int. Cl.³ C07C 177/00

U.S. Cl. 562-503

1. A compound of the formula

4 Claims

4,294,986

NOVEL PARA-PHENYLALKOXY PHENYLUREA AND THIOUREA COMPOUNDS AND HERBICIDAL USE THEREOF

David M. Spatz, San Francisco, Calif., and Barrington Cross, Rocky Hill, N.J., assignors to American Cyanamid Co., Stamford, Conn.


Division of Ser. No. 51,584, Jun. 25, 1979. This application Apr. 24, 1980, Ser. No. 143,223

Int. Cl.³ C07C 127/19; A01N 9/20

U.S. Cl. 564-52

7 Claims

1. A compound of the formula:



wherein R_2 and R_3 each represent alkyl $\text{C}_1\text{-C}_4$ or alkoxy $\text{C}_1\text{-C}_4$; X is oxygen; A is a straight or branched, unsaturated, alkyl $\text{C}_2\text{-C}_8$ group; W is hydrogen or chlorine; and Y is hydrogen, halogen, alkyl $\text{C}_1\text{-C}_4$ or alkoxy $\text{C}_1\text{-C}_4$.

4,294,987

PROCESS FOR PREPARING METHYLENE DIANILINES Richard A. Prather, and Nirad N. Shah, both of Houston, Tex., assignors to The Upjohn Company, Kalamazoo, Mich.

Filed Dec. 31, 1979, Ser. No. 108,522

Int. Cl.³ C07C 85/145

U.S. Cl. 564-331

8 Claims

1. In a process for the preparation of a mixture of di(aminophenyl)methane and oligomeric polymethylene polyphenyl polyamines the steps comprising:
 reacting aniline and formaldehyde in a proportion of about 1.6 moles to about 8 moles of aniline per mole of formaldehyde in the presence of an acid catalyst at a temperature in the range of about 0°C . to about 55°C . until the formation of aminobenzylamines is substantially complete;
 adjusting, if necessary, the proportions of aniline and water in the resulting reaction mixture so that the molar proportion of aniline to formaldehyde originally present in the reaction mixture is at least 4:1 and the amount of water is such that the concentration of acid catalyst is in the range of about 1 to about 8 percent by weight based on the total weight of the reaction mixture;
 subjecting the resulting aqueous solution to extraction with an inert organic solvent;
 separating the solvent and aqueous layers;
 removing the solvent from said solvent extract by distillation under reduced pressure;
 subjecting the residual mixture of amines to rearrangement to the corresponding mixture of di(aminophenyl)methane and oligomeric polymethylene polyphenyl polyamines by heating at a temperature in the range of about 60°C . to about 115°C . in the presence of a catalyst selected from the class consisting of strong acids, diatomaceous earth, clay and zeolite, provided that, when a strong acid is employed as catalyst, it is present in an amount substantially less than that employed in the initial condensation of the aniline and formaldehyde.

4,294,988

METHOD OF PREPARING 2,4-DIFLUOROANILINE

Roger J. Tull, Metuchen; Leonard M. Weinstock, Bellemead, and Ichiro Shinkai, Westfield, all of N.J., assignors to Merck & Co., Inc., Rahway, N.J.


Filed Oct. 31, 1977, Ser. No. 847,187

Int. Cl.³ C07C 85/11

U.S. Cl. 564-417

8 Claims

1. A method of preparing 2,4-difluoroaniline comprising the steps of



wherein D is

(1) $(\text{CH}_2)_3-(\text{CH}_2)_g-\text{CH}_2-$, or
 (2) $(\text{CH}_2)_3-(\text{CH}_2)_g-\text{CF}_2-$;
 wherein g is zero, one, two, or three;
 wherein Q is $\alpha\text{-OH}:\beta\text{-R}_5$ or $\alpha\text{-R}_5:\beta\text{-OH}$, wherein R_5 is hydrogen or methyl;
 wherein R_6 is
 (a) hydrogen,
 (b) alkyl of one to 12 carbon atoms, inclusive,
 (c) cycloalkyl of 3 to 10 carbon atoms, inclusive,
 (d) aralkyl of 7 to 12 carbon atoms, inclusive,
 (e) phenyl,
 (f) phenyl substituted with one, 2, or 3 chloro or alkyl groups of one to 3 carbon atoms, inclusive,
 (g) $-(\text{p-Ph})-\text{CO}-\text{CH}_3$,
 (h) $-(\text{p-Ph})-\text{NH}-\text{CO}-(\text{p-Ph})-\text{NH}-\text{CO}-\text{CH}_3$,
 (i) $-(\text{p-Ph})-\text{NH}-\text{CO}-(\text{p-Ph})$,
 (j) $-(\text{p-Ph})-\text{NH}-\text{CO}-\text{CH}_3$,
 (k) $-(\text{p-Ph})-\text{NH}-\text{CO}-\text{NH}_2$,
 (l) $-(\text{p-Ph})-\text{CH}=\text{N}-\text{NH}-\text{CO}-\text{NH}_2$,
 (m) β -naphthyl,
 (n) $-\text{CH}_2-\text{CO}-\text{R}_{28}$,
 wherein (p-Ph) is para-phenyl or inter-para-phenylene,
 wherein R_{28} is phenyl, p-bromophenyl, p-biphenyl, p-nitrophenyl, p-benzamidophenyl, or 2-naphthyl, or
 (o) a pharmacologically acceptable cation;
 wherein R_3 and R_4 are hydrogen, methyl, or fluoro, being the same or different, with the proviso that one of R_3 and R_4 is fluoro only when the other is hydrogen or fluoro;
 and
 wherein X is $-\text{C}\equiv\text{C}-$.

4,294,985

PRODUCTION OF THIOCARBOHYDRAZIDE ON A COMMERCIAL SCALE

Günther Cramm, Cologne, and Karl H. Blöcher, Leverkusen, both of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany
 Continuation of Ser. No. 856,455, Nov. 30, 1977, abandoned.

This application Jun. 15, 1979, Ser. No. 48,856

Claims priority, application Fed. Rep. of Germany, Dec. 23, 1976, 2658557

Int. Cl.³ C07C 159/00

U.S. Cl. 564-18

3 Claims

1. In the production of thiocarbonylhydrazide by reacting hydrazine hydrate with carbon disulphide in the presence of water to form in a first stage hydrazinium dithiocarbazinate, subsequently thermally decomposing the hydrazinium dithiocarbazinate in a second stage to form thiocarbonylhydrazide, and recovering the thiocarbonylhydrazide from the reaction medium, the improvement which comprises effecting the entire reaction in the mother liquor of a preceding batch, carrying out the first reaction stage at a temperature between about 25°C . and 45°C ., with injection of carbon disulphide below the surface of the reaction mixture carrying out the second stage at about 62° to 65°C . without prior isolation of the intermediate product; subsequently cooling the reaction mixture to about 20° to 25°C . and filtering off the thiocarbonylhydrazide formed, separating the amount of mother liquor in excess of that required for the next batch, and feeding the balance of the mother liquor to the next batch.

- (a) reacting 2,4,5-trichloronitrobenzene under anhydrous conditions with a fluorinating agent selected from NaF, KF, CsF, C₁₋₄ alkyl quaternary ammonium fluoride, and mixtures thereof, to form 2,4-difluoro-5-chloronitrobenzene; and
- (b) hydrogenating the 2,4-difluoro-5-chloronitrobenzene with hydrogen in the presence of a catalyst to form 2,4-difluoroaniline.

4,294,989

METHYLCYCLOHEXYL-O-ANISYLPHOSPHINE
William S. Knowles, St. Louis, and Milton J. Sabacky, Ballwin, both of Mo., assignors to Monsanto Company, St. Louis, Mo. Division of Ser. No. 122,116, Mar. 8, 1971, abandoned, which is a continuation-in-part of Ser. No. 36,471, May 11, 1970, abandoned, which is a continuation-in-part of Ser. No. 758,603, Sep. 9, 1968, abandoned. This application Sep. 5, 1978, Ser. No. 939,568

Int. Cl.³ C07F 9/50

U.S. Cl. 568—13

1 Claim

1. Methylcyclohexyl-o-anisylphosphine.

4,294,990

ALKYL-POLYGLYCOL MIXED FORMALS AS FIBER PREPARATION AGENTS
Rolf Kleber, Neu-Isenburg, and Siegfried Billenstein, Burgkirchen, both of Fed. Rep. of Germany, assignors to Hoechst Aktiengesellschaft, Fed. Rep. of Germany
Filed Mar. 19, 1979, Ser. No. 21,978

Claims priority, application Fed. Rep. of Germany, Mar. 22, 1978, 2812443

Int. Cl.³ D06M 13/18

U.S. Cl. 568—601

2 Claims

1. A polyglycol ether mixed formal of the formula



in which R₁ is a linear or branched alkyl or alkenyl radical of from 8 to 22 carbon atoms, R₂ is a linear alkyl radical of from 1 to 4 carbon atoms and n is an integer of from 3 to 30.

4,294,991

PROCESS FOR MONOALKYLATION OF DIHYDRIC PHENOLS

Michael Bellas, Wigan, and Robert Cahill, Kirkby, both of England, assignors to Eastman Kodak Company, Rochester, N.Y.


Continuation of Ser. No. 904,683, May 10, 1978, abandoned, which is a continuation-in-part of Ser. No. 748,036, Dec. 6, 1976, abandoned. This application Sep. 24, 1979, Ser. No. 78,123

Int. Cl.³ C07C 43/178, 43/00


U.S. Cl. 568—650

16 Claims

1. A process for the preparation of a monoalkyl ether having the formula




wherein R is an alkyl radical having 1 to 18 carbon atoms or C₂H₅—O—CH₂CH₂— and R¹ is hydrogen or an alkyl radical having 1 to 4 carbon atoms, which comprises reacting a compound having the formula R-OH with a mixture of a compound having the formula



II

and a compound having the formula



III

in the presence of an acid dehydration catalyst, wherein the weight ratio of II:III is from 5:1 to 20:1.

4,294,992

PROCESS FOR THE PRODUCTION OF ALKYL ARYL ETHERS

Graham K. Hughes, Hackettstown, N.J., assignor to The Southland Corporation, Dallas, Tex.

Filed Jan. 23, 1980, Ser. No. 114,601

Int. Cl.³ C07C 43/205

U.S. Cl. 568—632

8 Claims

1. A process for the production of an alkyl aryl ether comprising incrementally reacting an acid and an alkanol with a phenol at a rate of about 0.907–0.133 weight percent per minute of the acid and alcohol based on the weight of the phenol and continuously removing water formed as a by-product of said reaction, said reaction being carried out at an elevated temperature.

4,294,993

PURIFICATION OF BISPHENOL-A

Ming K. Li, Schenectady, N.Y., assignor to General Electric Company, Schenectady, N.Y.

Filed Apr. 14, 1980, Ser. No. 139,969

Int. Cl.³ C07C 37/70

U.S. Cl. 568—724

5 Claims

1. The method of recovering 2,2-bis(4-hydroxyphenyl) propane in a purified state from a mixture of the latter and impurities therein derived from the acid condensation of phenol and acetone, which process comprises (1) combining a mixture of (a) a preformed isolated adduct of phenol and the above-identified dihydroxydiphenyl propane and (b) impurities associated with (a), with sufficient toluene alone or with a mixture of toluene and water to form a homogeneous solution with the toluene, or a liquid-liquid mixture when water and toluene are used, the toluene being employed, on a weight basis, from 0.5 to 10 parts toluene per part adduct, (2) heating the mixture at a temperature of from 45°–125° C., (3) cooling the solution or liquid-liquid mixture to a temperature where the aforesaid dihydroxydiphenyl propane precipitates in a highly purified state, and (4) isolating the purified 2,2-bis(4-hydroxyphenyl) propane.

4,294,994

PURIFICATION OF BISPHENOL-A


Ming K. Li, Schenectady, N.Y., assignor to General Electric Company, Schenectady, N.Y.

Filed Apr. 21, 1980, Ser. No. 141,778

Int. Cl.³ C07C 37/70

U.S. Cl. 568—724

4 Claims



1. The method of recovering 2,2-bis(4-hydroxyphenyl) propane in a highly purified state which comprises subjecting a preformed isolated adduct of the aforesaid dihydroxydiphenyl propane and phenol containing at least 0.05%, by weight, of said adduct of acetone, to spray drying conditions at a temperature of from 50°–150° C. whereby the adduct is converted to the purified dihydroxydiphenyl propane and is recovered in a highly purified state and the acetone and phenol thereby produced are separately recovered.

4,294,995

METHOD AND CATALYST FOR MAKING BISPHENOL
Gary R. Faler, and George R. Loucks, both of Scotia, N.Y., assignors to General Electric Company, Schenectady, N.Y.

Filed Dec. 13, 1979, Ser. No. 103,095

Int. Cl.³ C07C 37/00; C08F 112/08

U.S. Cl. 568—728

2 Claims

1. In a method of making bisphenol, based on the reaction between a ketone and a phenol in the presence of an effective amount of a sulfonated polystyrene cation-exchange resin in acid form modified by the neutralization of 5–25% of a cation-exchange capacity with a promoter in the form of a C₂–C₄ alkyl mercapto amine whereby the promoter is incorporated onto the cation-exchange resin backbone by an acid-amine salt ionic bond which is susceptible to excessive loss from the cation-exchange resin due to leaching as the result of the degradation of the acid-amine salt ionic bond during the use of the ion-exchange resin in phenol-ketone condensation reaction, the improvement which comprises utilizing as the cation-exchange resin, a sulfonated polystyrene having 5–25% of its cation-exchange capacity occupied by an organo mercapto amine covalently bonded to the cation-exchange backbone by nitrogen sulfur linkages.
2. A method in accordance with claim 1, where the bisphenol is bisphenol-A.

4,294,996

METHOD OF REDUCING FORMATION OF CHLORINATED DIOXINS IN MANUFACTURE OF CHLORINATED PHENOLS

William H. Wetzel, Federal Way; Hsi-Lung Pan, Seattle; Robert J. Goodwin, Puyallup, and John E. Wilkinson, Gig Harbor, all of Wash., assignors to Reichhold Chemicals, Incorporated, White Plains, N.Y.

Filed Jun. 9, 1980, Ser. No. 157,447

Int. Cl.³ C07C 39/36, 39/27

U.S. Cl. 568—776

15 Claims

1. A process for producing polychlorinated phenols having

reduced amount of chlorinated dioxin formed therein during processing comprising reacting at a temperature of from 10° C. to 190° C. (A) a phenol, which is at least one member selected from a group consisting of phenol and lower chlorophenols and mixtures thereof, (B) chlorine to form a reaction mixture in the presence of from about 0.005 to about 0.016 moles per mole of (A) used of an acid catalyst, said catalyst consisting essentially of aluminum chloride, ferric chloride, aluminum tri-butoxide, antimony chloride, stannous chloride, cuprous chloride, metallic aluminum powder, metallic antimony, metallic copper or mixtures thereof; the improvement consisting of adding to the reaction mixture from about 0.0001 to 0.5 moles per mole of (A) used of a dioxin inhibitor selected from the group consisting of:

Antimony pentachloride
Chromium dichloride
Chromium powder
Chromium sulfide
Cobalt metal
Gadolinium trichloride
Germanium tetrachloride
Hafnium tetrachloride
Indium chloride
Magnesium turnings
Manganese dichloride
Niobium chloride
Zirconium tetrachloride
Antimony powder
Bismuth trichloride
Chromium metal
Cobalt fluoride
Iridium chloride
Niobium pentachloride
Rhenium pentachloride
Rhodium trichloride
Samarium trichloride
Tantalum chloride
Tin powder
Tungsten hexachloride
Zinc fluoride
Rubidium trichloride
and mixtures thereof.

4,294,997

PROCESS FOR THE CONTROL OF PH IN THE ETHYNYLATION OF FORMALDEHYDE

Albert M. Stock, LaPorte, and James D. Verbsky, Seabrook, both of Tex., assignors to E. I. Du Pont de Nemours and Company, Wilmington, Del.

Filed Jul. 10, 1978, Ser. No. 923,371

Int. Cl.³ C07C 33/046

U.S. Cl. 568—855

14 Claims

1. In the process for the production of butynediol by contacting acetylene and formaldehyde in the presence of a particulate copper acetylide catalyst in an agitated aqueous medium in a continuous reaction at 60°–120° C., the improvement wherein the pH of the reaction mixture is maintained at from 5–8 by the incremental or continuous addition of an aqueous solution of an alkali metal hydroxide and an alkali metal carbonate at equivalent ratios of alkali metal hydroxide to alkali metal carbonate of 1:1–4:1.

4,294,998

PREPARATION OF HIGH PURITY 1,4-BUTANEDIOL
 Harry B. Copelin, Wilmington, Del., assignor to E. I. Du Pont de Nemours and Company, Wilmington, Del.
 Continuation-in-part of Ser. No. 920,123, Jun. 28, 1978. This application Jul. 31, 1980, Ser. No. 174,258
 Int. Cl.³ C07C 29/78

U.S. Cl. 568-868

13 Claims

1. A process for purifying 1,4-butanediol, the process comprising
- crystallizing 1,4-butanediol from a crude liquid comprising
 - 35-85%, by weight, of 1,4-butanediol and
 - 2-15%, by weight, of impurities dissolved in tetrahydrofuran, by holding the liquid at a temperature of -10°C . to $+10^{\circ}\text{C}$., to form a slurry of 1,4-butanediol crystals; and then
 - separating the crystals from the crude liquid.

4,294,999


PREPARING OXYGEN-CONTAINING FUEL WHEREIN TERTIARY BUTYL ALCOHOL IS THE MAJOR PRODUCT OF THE PROCESS

Henry R. Grane, Springfield; John C. Jubin, Jr., Wallingford, and G. Richard Worrell, Media, all of Pa., assignors to Atlantic Richfield Company, Los Angeles, Calif.

Continuation-in-part of Ser. No. 45,454, Jun. 4, 1979, abandoned. This application Feb. 25, 1980, Ser. No. 124,035
 Int. Cl.³ C07C 29/50

U.S. Cl. 568-910

2 Claims



1. The method of preparing a motor fuel blending component which consists of:
- maintaining in an oxidation zone a liquid consisting of dissolved isobutane and oxidate, said oxidate comprising dissolved byproducts, tertiary butyl hydroperoxide, and tertiary butyl alcohol, solubilized molybdenum catalyst in a concentration corresponding to from about 1 to about

1,000 parts per million of isobutane, while injecting into the liquid a gas comprising oxygen and while injecting into the liquid a mixture of recycled and fresh isobutane; maintaining the liquid in said oxidation zone at a temperature within the range from 240°F . to 310°F . at a pressure adapted to maintain much of the isobutane in the liquid phase, said pressure being within the range from 200 to 1000 psig;

controlling product withdrawal rate and isobutane injection rate to provide a residence time within the range from about 3 to about 10 hours;

transferring from said oxidation zone a liquid stream, and directing said liquid stream through a debutanizing zone, to provide a debutanized liquid stream, and to provide a stream of isobutane recycled from the liquid, and to provide a withdrawn vapor stream comprising nitrogen, oxygen, carbon monoxide, and carbon dioxide;

transferring from said oxidation zone a vapor stream comprising nitrogen, oxygen, carbon monoxide, carbon dioxide, and isobutane, said vapor stream being subjected to partial condensation to provide a stream of isobutane recycled from a vapor zone of the oxidation zone, and to provide a withdrawn vapor stream comprising nitrogen, oxygen, carbon monoxide and carbon dioxide;

directing said debutanized liquid stream to a thermal decomposition zone maintained at a temperature within the range from about 260°F . to about 320°F . for from about 2 to about 8 hours to decompose a significant portion of the tertiary butyl hydroperoxide to form tertiary butyl alcohol and oxygen, and withdrawing a stream of oxygen from said decomposition zone;

transferring liquid from said decomposition zone for transfer to a distillation zone in which there is a distillate stream comprising acetone, methanol, and tertiary butyl alcohol which is taken overhead, and in which there is a residual liquid stream containing measurable amounts of tertiary butyl hydroperoxide, sufficient tertiary butyl alcohol to provide a unit weight ratio of tertiary butyl alcohol to tertiary butyl hydroperoxide greater than one, byproducts which are not completely codistilled with tertiary butyl alcohol, and molybdenum catalyst;

withdrawing said residual liquid stream; subjecting said distillate stream to treatment in a peroxide clean-up zone, said treatment consisting of heating the liquid at from 375°F . to 475°F . for a time of from 1 minute to 10 minutes to provide a motor fuel blending component; and

withdrawing from the peroxide clean-up zone a motor fuel blending component product stream containing tertiary butyl alcohol as the major product of the process, said stream also containing methanol.

ELECTRICAL


4,295,000

ELECTRODE-POSITION CONTROL IN ARC FURNACES
 Edgar Mark, Lohr, Fed. Rep. of Germany, assignor to G. L. Rexroth GmbH, Lohr, Fed. Rep. of Germany
 Filed Jan. 10, 1980, Ser. No. 110,855
 Claims priority, application Fed. Rep. of Germany, Jan. 13, 1979, 2901198

Int. Cl.³ H05B 7/156

U.S. Cl. 13-13

5 Claims



1. An electrode position control for arc furnaces comprising a hydraulically operated cylinder and piston unit having a cylinder chamber and a plunger piston extending into said cylinder chamber and connected to an electrode to be moved; a three-position control valve; a first pressure conduit connecting said control valve with a source of pressure fluid; a working conduit connecting said control valve with said cylinder chamber, said control valve being movable from a neutral position to a first operating position connecting said working chamber with a reservoir so that pressure fluid will flow out from said cylinder chamber to lower said electrode and a second operating position connecting said working conduit with a pressure source so that pressure fluid will flow into said cylinder chamber to raise said electrode; a first preselectable two-way valve movable between a closed and an open position in said first pressure conduit; a second preselectable two-way valve movable between an open and a closed position in said working conduit; a second pressure conduit connecting said chamber directly with said pressure source; a third preselectable two-way valve movable between an open and a closed position in said pressure conduit, and means cooperating with said two-way valves for moving said first and second two-way valves to said closed position while moving said third two-way valve to said open position and vice versa.

4,295,001


ELECTRODE SEAL
 Kenneth L. Britton, Claypool, Ariz., assignor to Inspiration Consolidated Copper Company, Inspiration, Ariz.
 Filed Dec. 3, 1979, Ser. No. 99,632
 Int. Cl.³ H05B 7/12

U.S. Cl. 13-17

10 Claims

1. An electrode seal for an electric furnace having at least one electrode movable into and out of said furnace through an opening in the furnace roof wherein said seal comprises a first ring including a plurality of radially slidable first refractory bricks partially overlying said opening and adapted to contact and seal with the periphery of said electrode, and contractions means for periodically exerting a contraction force on said first ring to slide said first refractory bricks radially inwardly towards said electrode until said first refractory bricks contact and seal with the periphery of said electrode and wherein said

first refractory bricks are free to slide radially outwardly of said opening under force of engagement with the periphery of



said electrode during periods of time when said contraction means does not exert a contraction force on said first ring.

4,295,002

HETEROJUNCTION V-GROOVE MULTIJUNCTION SOLAR CELL


Terry I. Chappell, Amawalk, and Jerry M. Woodall, Bedford Hills, both of N.Y., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Jun. 23, 1980, Ser. No. 161,820

Int. Cl.³ H01L 31/06

U.S. Cl. 136-244

17 Claims




1. A solar energy converter comprising:
- a first solar cell comprising first multiple p-n heterojunctions in association with a first type of optically active semiconductor material on one side of an insulating substrate; and
 - a second solar cell comprising second multiple p-n heterojunctions in association with a second type of optically active semiconductor material on the opposite side of the insulating substrate;
- said first type of semiconductor material is GaAlAs, said second type of semiconductor material is Si, and said insulating substrate is semi-insulating GaP.

4,295,003

THREADED SCREW MOUNTING MEANS
 Jesus Borja, Glenview, and Jack R. Halvorsen, Mt. Prospect, both of Ill., assignors to Illinois Tool Works Inc., Chicago, Ill.
 Filed Jan. 7, 1980, Ser. No. 110,055
 Int. Cl.³ H02G 3/08

U.S. Cl. 174-53

14 Claims



1. A threaded screw mounting means including:

a screw mounting member;
a generally D-shaped bore hole open along its flat side formed in said mounting member;
an axially extending slot substantially parallel to and communicating with said D-shaped bore hole along said open flat side and extending laterally therefrom;
a substantially flat clip member complementary to and slidably received within said slot, said clip member including: substantially planar head means at one end extending perpendicularly to the plane of the flat clip,
at least two yieldable arms struck from said clip member and extending angularly into said bore hole along said open flat side in a direction away from said head,
a pair of spaced yieldable leg members struck from adjacent the opposite edges of said clip and providing shoulder means in spaced opposition to said head, said leg members extending outwardly from the same side of the plane of said clip member as said at least two yieldable arms extend,

said slot and bore having a coterminous predetermined axial extent whereby when said clip member has been fully inserted said head bears against the outer one end of said mounting member and said leg members which flex during insertion into said slot snap outwardly after passage through said slot and bear against said mounting member adjacent said bore hole at its end opposite said outer end in locking engagement,
said at least two yieldable arms being deflectable when a screw threaded member is axially pushed into said bore hole from the outer end and engages said thread against retrograde axial movement while permitting adjustment of the screw, as well as removal, by appropriate rotation, said mounting member being counterbored adjacent said opposite end of said bore hole and slot to form abrupt shoulder means at said opposite end at least adjacent said slot and on opposite sides of said bore hole, said slot being tapered from said outer end toward said opposite end and terminating in parallel walls spaced apart a distance substantially equal to the effective thickness of said clip member for a limited axial distance adjacent the point where said slot communicates with said counterbore, said limited axial distance of said parallel walls gripping said clip member only in the region axially intermediate said yieldable arms and legs.

4,295,004


WIRE CONNECTOR

William C. Dauser, Jr., North Muskegon, Mich., assignor to Lloyd A., Trustee Heneveld, Grand Rapids, Mich.

Filed Dec. 3, 1979, Ser. No. 99,624
Int. Cl.³ H01R 11/00

U.S. Cl. 174-87

17 Claims



1. A self-stripping solderless electrical connector comprising:
an elongated body of insulating material having wire receiving channels formed along at least a portion of its length;
a cap member having a conductive member fixed thereto, said cap member and said conductive member being adapted for positioning over and movable along a portion of said elongated body and said channels, said conductive

member adapted to engage a plurality of insulated wire conductors positioned in said channels, cut through the insulation thereof, and engage wire conductors to provide an electrical connection therebetween upon movement of said cap member and conductive member along said elongated body.

4,295,005


CABLE SPLICE CLOSURE

Edgar E. Daugherty; Kenneth W. Jackson; Wesley W. Jones, and Nalf T. Subh, all of Gwinnett, Ga., assignors to Western Electric Company, Inc., New York, N.Y.

Filed Oct. 17, 1979, Ser. No. 85,850
Int. Cl.³ H02G 15/113

U.S. Cl. 174-92

7 Claims



1. A telecommunications cable splice closure comprising a pair of elongated covers each having a generally semi-cylindrical interior wall extending radially about a closure axis from opposed ends of which wall two flat end walls extend approximately normally to said closure axis with each end wall defining an opening from which a closure end port extends; a pair of cable clamp supports having generally annular rims sized to be positioned about a cable within said cover interior walls in flush contact or in point contact with said end walls; and means for securing said pair of covers together about said pair of cable clamp supports; whereby during a splicing operation a cable clamp support may temporarily be positioned within the covers in point contact with a cover end wall clamped about a cable entering the closure through an end port at a skewed angle with respect to the closure axis and later be pulled into flush contact with the end wall as the cable is straightened into a position along the closure axis.

4,295,006

SPEAKER SYSTEM


Mitsuaki Tanaka, and Hidesugu Suzuki, both of Yokohama, Japan, assignors to Victor Company of Japan, Limited, Yokohama, Japan

Filed Apr. 23, 1979, Ser. No. 32,229
Claims priority, application Japan, Apr. 24, 1978, 53-54248[U]; Jul. 6, 1978, 53-93181[U]

Int. Cl.³ H04R 1/28

U.S. Cl. 179-1 E

19 Claims



1. A speaker system comprising:

(a) a speaker enclosure having a diffraction characteristic;
(b) at least one speaker installed in said enclosure;
(c) a diffraction compensation circuit responsive to an input electrical audio signal for relatively elevating the level of the electrical signal at low frequencies so as to compensate for said diffraction characteristic of said speaker enclosure, said speaker being responsive to the output signal of said diffraction compensation circuit, said diffraction compensation circuit including a lowpass filter and an amplifier to exhibit a frequency characteristic opposite to said diffraction characteristic.

4,295,007


LINE IDENTIFIER FOR SWITCHBOARDS

Luciano Astegiano, and Wouter M. D. van Veen, both of Turin, Italy, assignors to CSELT-Centro Studi e Laboratori Telecomunicazioni S.p.A., Turin, Italy

Continuation-in-part of Ser. No. 953,163, Oct. 20, 1978, Pat. No. 4,252,998. This application Feb. 11, 1980, Ser. No. 120,545
Claims priority, application Italy, Oct. 21, 1977, 69356 A/77
Int. Cl.³ H04M 5/04, 15/00

U.S. Cl. 179-7 R

17 Claims



1. In a telecommunications system including a switchboard with multiplicity of incoming lines and a multiplicity of outgoing lines,

the combination therewith of a line identifier for monitoring switchboard activity and for establishing a communication link between a selected incoming line and a selected outgoing line in response to manual operations at said switchboard, said line identifier comprising:

first detector means connected to said switchboard for generating a signal coding the identity of a selected incoming line and for requesting the identification of a concomitantly selected outgoing line;

second detector means connected to said switchboard for generating a signal coding the identity of a selected outgoing line;

switching means coupled to said lines for connecting a selected incoming line to a concomitantly selected outgoing line upon the successful recognition thereof by said line identifier; and

control means operationally linked to said first detector means for decoding identification-request signals therefrom, to said second detector means for enabling same to emit a trunk-identifying signal upon the reception by said control means of a request signal from said first detector means, and to said switching means for activating same to connect a selected incoming line to a concomitantly selected outgoing line upon the decoding by said control means of a signal from said second detector means indicating such outgoing line.

4,295,008

TELEPHONE-CONFERENCING APPARATUS AND METHOD HAVING RESPONSE TALLYING


Avery R. Johnson, Milford, N.H.; Richard G. McGurk, Hull, Mass., and John M. Harrison, Epsom, N.H., assignors to Small World Exchange, Inc., Nashua, N.H.

Filed Mar. 23, 1979, Ser. No. 23,387

Int. Cl.³ H04M 3/22, 3/56

U.S. Cl. 179-18 BC

8 Claims



1. Telephone conferencing apparatus comprising input means for concurrently receiving a plurality of incoming calls over an associated plurality of incoming telephone lines and responding to a caller-initiated signaling condition on any incoming line for conditioning that line for conference communication,

control means responsive to said input means for connecting said lines associated with said incoming calls to at least one conference grouping wherein any associated incoming line in the grouping provides communication with other lines in said grouping and wherein said grouping has the capacity of at least three incoming calls, said control means providing said connecting of each line, to such a conference grouping, independently of the connecting of other of said lines to a conference grouping,

monitor means operatively responsive to the incoming signal energy on each incoming line for generating electrical report signals distinct from incoming communication and indicating at least which of said lines carries incoming communication,

means for initiating a tally condition, and tally means responsive to said monitor means and to said tally condition-initiating means for providing a summation of the number of lines having associated therewith reports signals during a selected time interval.

4,295,009

PIEZOELECTRIC AUDIO TRANSDUCER MOUNTING AND ELECTRICAL CONNECTOR

Charles H. Weidler, Lancaster, Pa., assignor to AMP Incorporated, Harrisburg, Pa.

Filed Mar. 7, 1980, Ser. No. 128,331

Int. Cl.³ H04R 17/00

U.S. Cl. 179-110 A

10 Claims


1. Supporting and contacting means for a piezoelectric audio transducer comprising:

transducer housing means having a transducer-receiving recess therein which is dimensioned to receive said transducer, said recess having an inner end surface and having transducer-supporting surface portions for supporting peripheral portions of said transducer, said transducer supporting surface portions being spaced from said inner end surface,

first and second terminal-receiving wells in said inner end surface, each of said wells having a terminal-supporting floor and having sidewalls extending from said inner end surface to said terminal-supporting floor,

first and second contact terminal in said wells, each of said

terminals having an elongated generally channel-shaped frame section comprising a web and terminal sidewalls extending from said web, said web being on said floor and said terminal sidewalls being against said well sidewalls, an elongated spring struck from said web along the length thereof, said spring extending obliquely from said web at an acute angle and having a contact portion which is normally elevated above said inner end surface and above said transducer supporting surface portions,



conductor means extending from said web at each end thereof and externally of said housing means and clamping means for clamping said transducer in said recess with peripheral portions thereof on said transducer supporting surfaces whereby, upon placement of said transducer in said recess, and clamping said transducer against said transducer supporting surface portions, said contact springs are flexed towards said webs of said terminals and are thereby placed in preloaded resilient contact with said transducer.

4,295,010

PLURAL PIEZOELECTRIC POLYMER FILM ACOUSTIC TRANSDUCER


Preston V. Murphy, Geneva, Switzerland, assignor to Lectret S.A., Geneva, Switzerland

Filed Feb. 22, 1980, Ser. No. 123,719

Int. Cl.³ H04R 17/00

U.S. Cl. 179—110 A

15 Claims



1. An acoustic transducer comprising: a hollow support member, and a plurality of metal-coated piezoelectric polymer films to act as an oscillator, said films being spaced apart at their peripheries, mounted at said peripheries to said support member, and physically connected to at least one adjacent film near their centers.

4,295,011 LINEAR EXCURSION-CONSTANT INDUCTANCE LOUDSPEAKER


Dana B. Hathaway, Amesbury, Mass., assignor to Epicure Products Inc., Newburyport, Mass.

Filed Sep. 11, 1979, Ser. No. 74,507

Int. Cl.³ H04R 9/06

U.S. Cl. 179—115.5 VC

19 Claims



1. A loudspeaker, comprising: a frame, a speaker cone attached at its widest portion to the frame, a hollow cylindrical voice coil attached to the narrow portion of the cone and having a winding formed on the end of the voice coil distal said cone, said winding having no more than two layers and forming a coil, and means attached to said frame for generating a focused magnetic field, said field being formed to surround said voice coil and being focused onto said coil winding, said focused magnetic field being formed as a cylinder having a height less than the height of said winding; said means for generating said focused magnetic field comprising a center pole extending upwards inside of said hollow voice coil, and a bottom plate affixed to said center pole at an end thereof distal from said hollow voice coil, said center pole having a midsection and a portion of gradually increasing diameter, said diameter gradually increasing from said midsection through said portion of gradually increasing diameter to said end of said center pole distal said hollow voice coil, whereby to add increased magnetizable mass to said center pole.

4,295,012

SECRETARIAL SHIFT MECHANISM FOR AN ELECTRIC KEYBOARD

Robert J. Keeler, Elmhurst, and Stanley E. Filipiak, Chicago, both of Ill., assignors to Illinois Tool Works Inc., Chicago, Ill.

Filed Feb. 4, 1980, Ser. No. 118,038


Int. Cl.³ H01H 9/20

U.S. Cl. 200—5 B

8 Claims

1. A keyboard mechanism comprising a shift keyswitch and a shift lock keyswitch positioned adjacent said shift keyswitch wherein each of said keyswitches comprises a switching means, a housing with a base for said switching means, an actuating member in the form of a plunger within said housing mounted for movement relative to said housing base from an initial undepressed position to a depressed position for actuating said switching means when said actuating member is in said depressed position, resilient means for returning said actuating member to its undepressed position and wherein said mechanism further comprises a ledge formed on said actuating member of said shift lock keyswitch, locking means which is resiliently biased toward said ledge and which engages said ledge so as to hold said actuating member of said shift lock keyswitch in its depressed position when said actuating member of said

shift keyswitch is in its undepressed position, but which does not engage said ledge when said actuating member of said shift lock keyswitch is in its undepressed position and said actuating member of said shift keyswitch is depressed, rotatable release means connected to said locking means and an actuator bar operable exteriorly of said housing and including an arm connected to said actuating member of said shift keyswitch which is constructed to engage said rotatable release means when said



actuating member of said shift keyswitch is depressed and said actuating member of said shift lock keyswitch is held in its depressed position in a manner which causes said rotatable release means to rotate sufficiently far to allow said locking means to be withdrawn clear of said ledge which in turn allows said actuating member of said shift lock keyswitch to be returned to its initial undepressed position by said resilient means of said shift lock keyswitch.

4,295,013

IGNITION SWITCH


Millard E. Gage, Otego, and Derek J. Landers, Sidney Center, both of N.Y., assignors to The Bendix Corporation, Southfield, Mich.

Filed May 12, 1980, Ser. No. 149,108

Int. Cl.³ H01H 21/62

U.S. Cl. 200—11 C

2 Claims



1. In combination with a switch of the type having: a housing which includes an internal shoulder; a rotor which includes a central passage and an annular recess located at one end and spaced from said central passage, said recess including an inner wall and an outer wall; means for mounting said rotor for radial movement within said housing, said means including a shaft disposed in said rotor central passage and connected to said rotor; at least one electrical contact mounted on the other opposite end of said rotor; a coil spring mounted in the annular recess of said rotor; means for attaching one end of said spring to said rotor; and a plate connected to the other opposite end of said spring, said plate having an extended portion adapted to

engage said housing shoulder when said rotor is rotated a predetermined distance, the improvement wherein:

the retainer plate includes a tab projecting from the surface of said plate in the direction of said spring and located adjacent the inner diameter of the first winding of said spring, whereby when said rotor is rotated a predetermined distance the extended portion of said plate engages said housing shoulder and further rotation of said rotor causes said rotor to wind said spring which compresses inwardly, further causing the tab on said plate to engage the first winding of said spring as it compresses to prevent the first winding of said spring from engaging the inner wall of said recess.

4,295,014

IGNITION DISTRIBUTOR WITH INTEGRAL COMMON ELECTRODE, SHAFT BEARING AND HIGH VOLTAGE TERMINAL CONNECTOR


David H. Fox, Ann Arbor, and Charles C. Kostan, Canton, both of Mich., assignors to Ford Motor Company, Dearborn, Mich.

Filed Dec. 14, 1979, Ser. No. 103,675

Int. Cl.³ H01H 19/00

U.S. Cl. 200—19 R

4 Claims



1. A high voltage commutation distributor for an internal combustion engine comprising:

a distributor base for mounting on said engine, defining a shaft housing and a portion of an electrical commutation cavity; a distributor cap for mounting on said base and defining the remaining portion of said commutation cavity; means defining a plurality of spark plug terminal connectors mounted within said commutation cavity; a rotor driveshaft formed of electrically insulative material mounted within said shaft housing and being rotationally driven by said engine; unitary structure means mounted on said base within said cavity and formed entirely of an electrically conductive material for providing both a common high voltage conductor means and means for mounting said driveshaft in said base for rotation about a central axis therein; and means defining a rotor element mounted on said rotor driveshaft for providing electrical commutation between said common high voltage conductor means and respective ones of said spark plug terminal connectors.

4,295,015

REPEAT TYPE TIME SWITCH

Ichiroh Fujiwara; Yoshiaki Motoki; Toshinori Inoue, and Kazuma Fukuoka, all of Fukuyama, Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan


Filed Sep. 6, 1979, Ser. No. 73,133

Claims priority, application Japan, Sep. 14, 1978, 53-112930

Int. Cl.³ H01H 7/00

U.S. Cl. 200—38 R

3 Claims



1. A time switch comprising:
 - a cradle substantially in the form of a disk and rotatable about an axis;
 - a plurality of circumferentially spaced axial depressions on one axial surface of said cradle, said depressions being separated by partitions and including radially outwardly located depression walls including two detent means;
 - an annular element fixable adjacent said surface and concentric with said disk, said annular element being radially inward relative to said depressions;
 - a radially extending change over pawl for each of said depressions and each said pawl having substantially the same circumferential width as one of said depressions, each of said pawls having a radially inward end fixed to said annular element by an elastically deformable connecting means, a radially outward end adapted to selectively engage a switch element and an intermediate portion inserted in one of said depressions and having a surface including means selectively engageable with one of said detent means;
 - whereby said depression substantially encloses all of said pawl except for said radially outward end and said partitions prevent distortion of said pawls in the circumferential direction.

4,295,016

GARAGE DOOR LOCK


John H. Cantlin, Lincoln, Mass., assignor to Hudson Lock, Inc., Hudson, Mass.

Filed Dec. 14, 1979, Ser. No. 103,532

Int. Cl.³ H01H 27/06

U.S. Cl. 200—44

9 Claims



1. A lockable electrical switch comprising:
 - a lock shell;
 - a cylindrical plug mounted within said shell for rotary movement between locked and unlocked positions and for

axial movement between active and inactive positions, said plug defining a keyway and a plurality of tumblerways intersecting therewith;

tumbler means movably mounted in said tumblerways, said tumbler means operatively engaging said shell and said plug so as to prevent relative rotation therebetween in the absence of a proper key in said keyway;

a movable contact means mounted for movement with said plug; and

stationary assembly means comprising stationary contact means shaped and arranged so as to be engaged by said movable contact means with said plug in both said unlocked and active positions and to be disengaged therefrom with said plug in either of said locked or inactive positions, said stationary assembly means further comprising an insulator body defining both an internal cavity retaining said stationary contact means and an opening communicating with said cavity, said opening having a periphery with dimensions that permit entry into said cavity of said movable contact with said plug in said unlocked position and obstruct entry thereof with said plug in said locked position.

4,295,017

LIMIT SWITCH

Isoo Kashima; Masami Mishina, both of Watarai; Yosio Takase, Matsuzaka, and Katsumi Maruchi, Tsu, all of Japan, assignors to Matsushita Electric Works, Ltd., Osaka, Japan


Filed Mar. 6, 1980, Ser. No. 127,885

Claims priority, application Japan, Mar. 6, 1979, 54-285131[U]

Int. Cl.³ H01H 3/16

U.S. Cl. 200—47

20 Claims



1. In a limit switch comprising a switching means having a push-button for actuating said means, a housing having an interior space for housing said switching means, means provided to communicate said interior space with the exterior of said housing for operating said push-button to actuate the switching means by transmitting an externally given operating force to the push-button, means cooperating with said operating means for absorbing said operating force applied sequentially after an actuation of the switching means, the combination comprising a first spring means fixed at one end within said interior space of the housing and extended at the other end to be engageable with the push-button, said the other end of said first spring means providing a first biasing force acting substantially in the same direction as said operating force, and a second spring means fixed at one end within said interior space of the housing and extended at the other end to a position adjacent said the other end of said first spring means to provide thereto a second biasing force in a direction opposite to the operating force for normally restraining the other end of the first spring means from engaging the push-button against said first biasing force, said second spring means engaging said operating means to act as said absorbing means and releasing said restraint to the other end of the first spring means in response to the operating force applied through the operating

means to allow the first spring means to engage and operate the push-button with the first biasing force.

4,295,018

ELECTRICAL HOUSING AND SWITCH BOX


Dominick Borrelli, 2243 Cropsey Ave., Brooklyn, N.Y. 11214

Filed Apr. 28, 1980, Ser. No. 144,386

Int. Cl.³ H01R 33/30

U.S. Cl. 200—51.09

5 Claims



1. An electrical switch assembly comprising a housing having first and second openings therein, and adapted to receive a plurality of electrical wires internally thereof through said first opening, a plurality of electrically conductive contacts mounted on said housing adjacent said second opening, said contacts having means for receiving the said wires, each contact receiving a different one of said wires; a switch box for electrically connecting and disconnecting said wires, said switch box having a plurality of electrical connector means thereon, each of said contacts having a connector receiving opening therein for receiving and partially enclosing one of said connector means when the switch box is pushed into said housing, each connector being shaped to engage said opening.

4,295,019

WATER LEVEL CONTROL DEVICE AND METHOD OF MAKING THE SAME


Thomas M. Buckshaw, Indiana, Pa., assignor to Robertshaw Controls Company, Richmond, Va.

Filed Oct. 24, 1979, Ser. No. 87,753

Int. Cl.³ H01H 35/34

U.S. Cl. 200—61.2

12 Claims



1. In a water level control device having a cam follower for setting the desired water level setting for said control device and a movable cam means having a cam surface engaging said cam follower to set the same in desired positions, said cam surface having a reset portion for resetting said control device

when said reset portion is disposed against said cam follower, said control device having a spring means that cooperates with said cam means to tend to move said cam means from its resetting position when said reset portion is disposed against said cam follower, the improvement wherein said spring means is integral and homogeneous with said cam means whereby said cam means and said spring means comprises a one-piece homogeneous structure.

4,295,020

ELECTRICAL SWITCH MECHANISM


James Heydweiller, Rochester, N.Y., assignor to General Signal Corporation, Rochester, N.Y.

Filed Dec. 26, 1979, Ser. No. 106,568

Int. Cl.³ H01H 35/14

U.S. Cl. 200—61.45 R

11 Claims



1. A switch mechanism which comprises at least a first set of switch contacts which are moveable with respect to each other between make and break positions where said contacts are in contact and apart respectively, an axle, a pendulum pivotally moveable about said axle with respect to the vertical in first and second opposite directions in response to deceleration and acceleration events in said opposite directions, an arm mounted on said pendulum for actuating said contacts when said pendulum moves a predetermined distance in one of said opposite directions in response to the occurrence of a predetermined level of one of said acceleration and deceleration events which is applied to said mechanism, means pivotally supporting said arm on said pendulum and for adjusting the position of said arm on said pendulum to selected different inclinations with respect to the vertical for selecting said predetermined level of said one event upon occurrence of which said first set of contacts is actuated to said other position thereof.

4,295,021

ELECTROMAGNETIC ARC EXTINCTION APPARATUS FOR SWITCHGEAR

Erik I. Asinovsky, 16 Parkovaya ulitsa, 49, korpus 1, kv. 78; Anatoly A. Afanasiev, Ljubertsy, ulitsa Shosseynaya, 10, kv. 137; Evgeny P. Pakhomov, Yakhromskaya ulitsa, 3, korpus 2, kv. 30; Vladimir A. Zelgarnik, Bolshoi Tishinsky pereulok, 41, kv. 9, all of Moscow, and Ivan M. Yartsev, ulitsa Teatralnaya, 27, korpus 3, kv. 28, Dolgoprudny, Moskovskaya oblast, all of U.S.S.R.

Filed Jan. 19, 1979, Ser. No. 4,669

Int. Cl.³ H01H 33/06


U.S. Cl. 200—147 R

9 Claims

1. An electromagnetic arc extinction apparatus for switchgear, comprising:

an arc chamber defined by an electrically insulating material and having a cavity extending along a helix so as to allow a quenching arc in the form of a helix to be moved in a radial direction, said cavity having a pitch which is at least 10 times smaller than the diameter of the arc chamber measured over the cross-section thereof;

an axial channel extending axially through said arc chamber; and



two electrodes at least in part situated in said axial channel and arranged in alignment with the axis of said arc chamber and adapted to form said quenching arc.

4,295,022

TRIFURCATED ARC RUNNER


Charles T. Robins, Swarthmore, Pa., assignor to Gould Inc., Rolling Meadows, Ill.

Filed Mar. 15, 1979, Ser. No. 20,767

Int. Cl.³ H01H 33/20

U.S. Cl. 200—147 R

10 Claims



1. A circuit breaker including an elongated conducting strap having first and second ends; stationary contact means mounted on said strap and positioned in front of a first face thereof at said first end; said stationary contact means including a stationary arcing contact section and a stationary main contact section positioned closer to said first end than said stationary arcing contact section; movable contact means including movable arcing and main contact sections operable into and out of engagement with the respective stationary arcing and main contact sections; arc chute means to receive and extinguish electric current arcs drawn between said movable and stationary contact means upon separation thereof; said arc chute means being positioned in front of said first face and interposed between said stationary contact means and said second end; arc runner means in front of said first face and in electrical contact with said stationary arcing contact section and extending therefrom toward said second end; said arc runner means including at its end remote from said stationary main contact section a plurality of transversely spaced sections for dispersing various arc sections into different regions of said arc chute means.

4,295,023

GAS-BLAST CIRCUIT-BREAKER


Edmond Thuries, Pusignan; Pierre Vernat, and Roger Sauvat, both of Villeurbanne, France, assignors to Delle-Alsthom, Villeurbanne, France

Filed Jun. 13, 1979, Ser. No. 48,120

Int. Cl.³ H01H 33/14, 33/82

U.S. Cl. 200—148 R

5 Claims



1. A gas-blast circuit-breaker, said circuit-breaker including for each pole, a horizontal base, a control box, an actuator chamber secured to said base, a plurality of groups of arc-extinguishing chambers, each group including at least two arc-extinguishing chambers, each arc-extinguishing chamber including an opening unit and a closing unit, arc-extinguishing chambers being electrically connected in series, each group including a support assembly, said support assembly comprising a plate, said control chamber fixed to said plate, said arc-extinguishing chambers being fixed to said control chamber and opening thereto, two insulating pillars extending between said plate and said base and being secured to said base, said column being fixed at one end to said plate and communicating through said plate with the interior of said arc-extinguishing chamber via said control box, said column being abutting at its other end to said actuator chamber and being secured thereto and communicating with the inside of said actuator chamber, said hollow column including rod means extending longitudinally interiorly thereof and controlling said opening and closing units, a compressed gas source connected to said actuator chamber for supplying compressed air via said actuator chamber and said hollow insulated column to said arc-extinguishing chambers and said actuator chamber including means for imparting simultaneous axial movement of said rod means so as to simultaneously open and close all of said opening and closing units of said plurality of groups of arc-extinguishing chambers.

4,295,024

SPRING BIASED ENERGY ABSORBER FOR VACUUM SWITCH CONTACT SHAFTS

Eugene L. Kamp, Fulton, Mo., assignor to A. B. Chance Company, Centralia, Mo.

Filed Sep. 24, 1979, Ser. No. 78,094


Int. Cl.³ H01H 3/60

U.S. Cl. 200—288

4 Claims

1. In an electrical switch including a pair of electrical contacts, soft metal, deformable shafts respectively supporting said contacts, and spring-loaded means for selective opening and closing of the contacts as desired and for creating a predetermined static closing force between said contacts when the contacts are in a closed condition, including opening and closing apparatus operatively coupled to at least one of the shafts, the improvement comprising structure for slowing the relative closing speed of said contacts prior to the instant of impact between said contacts for absorbing a part of the impact force developed during closing of said contacts, and without substantially lessening said static closing force between the contacts when the contacts are closed, said structure including an elongated arm presenting an engagement surface;

means supporting said arm for pivoting movement thereof and in a location proximal to said closing apparatus; and means associated with said arm for biasing the arm to a disposition where said surface is in the path of said closing apparatus during closing of said contacts for causing said



apparatus to engage and pivot said arm immediately prior to closing of said contacts, the distance between the pivot axis of said arm and said engagement surface being substantially less than the overall length of said arm.

4,295,025

CIRCUIT BREAKER WITH ELECTROMECHANICAL TRIP MEANS


William E. Beatty, Jr., Beaver Falls, and James P. Ellsworth, Beaver, both of Pa., assignors to Westinghouse Electric Corp., Pittsburgh, Pa.

Filed Jun. 6, 1980, Ser. No. 156,961

Int. Cl.³ H01N 3/60; N01N 9/20

U.S. Cl. 200—288

1 Claim



1. A circuit interrupter, comprising:

- (a) housing means;
- (b) contact means disposed within said housing means for being actuated to an opened state;
- (c) manual actuating means disposed in said housing means to be moved to actuate said contact means;
- (d) electromechanical trip means disposed in said housing means to be electromechanically moved to actuate said contact means and to provide an associated trip indication; and
- (e) shock absorbing means generally comprised of a leaf spring connected to said electromechanical trip means so it is disposed to absorb the shock and vibration when said manual actuating means is manually operable to open and close said contacts.

4,295,026

SWITCH ADAPTER MECHANISM


Allen C. Williams, and Barbara J. Williams, both of 322 W. Jefferson Ct., Vernon Hills, Ill. 60061

Filed Nov. 5, 1979, Ser. No. 91,378

Int. Cl.³ H01H 3/04

U.S. Cl. 200—331

5 Claims



1. Apparatus for use with a wall mounted switch of the type having an outlet box including at least one fastening aperture adapted for receiving a cover plate mounting screw and a vertically moveable operating level for turning the switch on and off, said apparatus comprising:

an elongate cover plate having an upper portion disposed overlying said outlet box and a lower portion depending therefrom, said upper portion including at least one mounting aperture adapted for receiving said cover plate to said outlet box and an opening receiving said operating level for allowing local manual operation of said switch, said lower portion including a plurality of vertically spaced longitudinal slots;

an elongate slide plate interposed between the wall and said cover plate, said slide plate including at least one longitudinal guide slot receiving said mounting screw for allowing limited vertical displacement of said slide plate relative to said cover plate, an opening receiving said lever for operating said switch in response to vertical movement of said slide plate, and a plurality of apertures each displaceable in a locus underlying a respective one of said cover plate longitudinal slots in response to vertical movement of said slide plate; and

a single horizontally disposed operating member passing through a selected one of said cover plate longitudinal slots and snugly engaging the associated one of said slide plate apertures, said slide plate being moveable for operating said switch in response to vertical displacement of said operating member from an adjustable height above the floor corresponding to said selected cover plate longitudinal slot while said cover plate is maintained in a stationary orientation.

4,295,027

MICROWAVE OVENS WITH PROGRAMMABLE CONTROL

Sadao Zushi, Fuji, and Yoshio Oida, Funabashi, both of Japan, assignors to Tokyo Shibaura Electric Co., Ltd., Kawasaki, Japan

Continuation of Ser. No. 887,221, Mar. 16, 1978, abandoned.


This application Jan. 17, 1980, Ser. No. 113,050

Claims priority, application Japan, Mar. 18, 1977, 52-30106; Mar. 18, 1977, 52-30107; Mar. 18, 1977, 52-30108

Int. Cl.³ H05B 9/06

U.S. Cl. 219—10.55 B

15 Claims



1. A microwave oven comprising:

a casing;
a heating chamber provided in the casing;
a door provided at an opening of the heating chamber;
a magnetron for supplying a microwave energy to the heating chamber;

a source circuit for energizing the magnetron;
key means provided at the front panel of the casing and including numeral keys, function keys including a time key for setting or changing at least a selected cooking time, a temperature key for setting or changing selected temperature in a cooking operation, a power level key for setting or changing power levels which control cooking speed, a "heat & hold" key for setting a temperature level to be held for a selected time period, a memory key for selecting more than one stage of cooking operations prior to starting the oven so that cooking automatically progresses from one stage to the next, a start key for starting a selected cooking operation and a clear key for stopping oven operation and clearing a prior selected cooking operation;

digital control logic means for encoding an operation condition determined in response to the operation of the function keys and numeral keys in said key means selectively operated by users, which comprise a key circuit and an input control unit including a key encoder for encoding an output signal of said key circuit and a key ROM supplied with the output of said key encoder;

memory means having at least three memory areas for memorizing the encoded operation condition regarding the time, temperature and power level encoded by the digital control logic means, respectively;

display means for displaying digitally the operation condition encoded by said digital control logic means;

operation means for initiating an operation in response to the operation of said start key to energize said magnetron based on the operation condition memorized in said memory means, which includes an oscillator, a timing signal generator supplied with the output of said oscillator, and a main ROM connected to memorize a predetermined program, a status register connected to said key ROM and said main ROM, a first display control unit connected to receive the output of said status register, a second display control unit connected to said memory means, a display

circuit for supplying the outputs of said first and second display control units to said display means;
said second display control circuit comprising a control gate with controls interchange of data between said key ROM and said main ROM, a display register and a half adder which are supplied with the output of said control gate, a latch circuit supplied with the output of said display register, and a segment decoder for decoding the output of said latch circuit; and
control means for controlling said source circuit in response to an output signal of said operation means.

4,295,028

COMBINATION OF GAS SENSOR CONTROLLED COOKING UTENSIL AND GAS LEAK ALARM

Takeshi Tanabe, Higashiosaka, Japan, assignor to Sharp Kabushiki Kaisha, Osaka, Japan


Filed Feb. 21, 1980, Ser. No. 123,278

Claims priority, application Japan, Feb. 23, 1979, 54-21061

Int. Cl.³ H05B 6/68

U.S. Cl. 219—10.55 B

4 Claims



1. A combined cooking utensil and gas leak alarm comprising:

an oven cavity;
a cooking energy source for conducting the cooking operation of a foodstuff disposed in said oven cavity;
a blower fan system for introducing a fresh air into the oven cavity and exhausting gas from said oven cavity;
a gas sensor disposed in a path of the gas developed from said oven cavity for detecting the gas concentration;
a control circuit for controlling the operation of said cooking energy source in response to an output signal derived from said gas sensor when said combined cooking utensil and gas leak alarm is placed in a cooking operation mode;
a monitor circuit for detecting an ambient gas concentration through the use of said gas sensor when said combined cooking utensil and gas leak alarm is placed in a gas leak alarm operation mode, said monitor circuit developing an alarm instruction output when the ambient gas concentration exceeds a preselected value; and
an alarm system responding to said alarm instruction output derived from said monitor circuit.

4,295,029

BATTERY STRAP CONNECTION WELDING METHOD

Toshio Uba, Denver, Colo., assignor to The Gates Rubber Company, Denver, Colo.

Division of Ser. No. 43,203, May 29, 1979, Pat. No. 4,241,151.

This application May 27, 1980, Ser. No. 153,346

Int. Cl.³ B23K 9/225, 9/16

U.S. Cl. 219—75

4 Claims

1. A method for forming a unitary welded connection between collector tabs of electrode plates and a strap having at least one projecting leg, in a lead electrochemical cell, normally subject to variations in collector tab height relative to the leg contributing to the problem of forming an unsatisfactorily high percentage of "bridge welds", comprising the steps of:

4,295,031

ARC WELDING APPARATUS WITH OSCILLATING ELECTRODE

Richard A. Roen, Edmonton, Canada, assignor to The Research Council of Alberta, Edmonton, Canada

Continuation of Ser. No. 895,266, Apr. 10, 1978, Pat. No. 4,177,373. This application Jul. 10, 1979, Ser. No. 56,294


Claims priority, application United Kingdom, Aug. 3, 1977, 32626/77

The portion of the term of this patent subsequent to Dec. 4, 1996, has been disclaimed.

Int. Cl.³ B23K 9/12

U.S. Cl. 219—125.12

4 Claims



supplying an electrode arc employing an inert-gas-shielded, non-consumable electrode to the weldable surface (comprising collector tabs, leg and included boss) to cause upwardly extending portions of the collector tabs, and at least a portion of the boss, to melt and flow together into a fused mass without the use of lead filler rods, the flow being contained by the mold means.

4,295,030

PLASMA-ARC CUTTING METHOD

Naoyoshi Hosoda, 2-20-18, Denenchofu, Ota-ku, Tokyo, and Takeshi Hosoda, 2-22-7, Wakabayashi, Setagaya-ku, Tokyo, both of Japan


Continuation of Ser. No. 884,682, Mar. 8, 1978, abandoned. This application Sep. 19, 1979, Ser. No. 76,821

Claims priority, application Japan, Mar. 8, 1978, 53-34732

Int. Cl.³ B23K 9/16

U.S. Cl. 219—121 PH

3 Claims



1. A plasma-arc cutting method comprising:

contacting the end of an electrically conductive nozzle having a downwardly tapering lower end portion having a reduced inside nozzle diameter, with a base metal; after said contacting, bringing a central electrode surrounded in spaced concentric relation by said nozzle towards the surface of said base metal in a flow of a first inert gas resulting in striking an arc on a first anode point on said base metal while said electrode is away from said base metal;

adding a second inert gas to the flow of said first inert gas; changing the distance between the electrode and said base metal from a first distance employed while striking an arc between said electrode and said base metal to a second distance employed while cutting said base metal with said arc, said first distance being less than said second distance; whereby said nozzle and said base metal are at the same electric potential while said base metal is being cut and an opening approximately equal in diameter to said reduced inside nozzle diameter is cut through said base metal.

4,295,032

PROCESS FOR BALANCING A CRANKSHAFT

Takeshi Sasaki, Tokorozawa, Japan, assignor to Honda Giken Kogyo Kabushiki Kaisha, Tokyo, Japan

Filed Dec. 6, 1979, Ser. No. 100,876

Claims priority, application Japan, Dec. 11, 1978, 53/151933

Int. Cl.³ B23K 9/04; G01M 1/16


U.S. Cl. 219—137 R

1 Claim

1. In a process for balancing a crankshaft having pin portions and associated balancing weight parts counterbalancing said pin portions, and which includes the step of welding masses of welding wire to the balancing weight parts to compensate for imbalance of the crankshaft, the improvement comprising the steps of:

electronically sensing and obtaining an analog signal of the extent of imbalance in said crankshaft, converting said analog signal to digital form, feeding said digital signal to an electronic counter to count-up said counter, employing said counter when other than in null condition to

activate a welding current supply and to activate a feed for welding wire, obtaining a digital signal representative of the length and thus of the weight of the welding wire fed by said feed, and



supplying said signal representative of the length of the welding wire to said counter to progressively count-down said counter to a null condition and to deactivate said welding current supply and said feed.

4,295,033

ANNEALING OVEN

Hakan O. Lindgren, and Bengt Magnusson, both of Hallstahammar, Sweden, assignors to Bulten-Kanthall Aktiebolag, Hallstahammar, Sweden



Filed Jul. 12, 1978, Ser. No. 923,968

Claims priority, application Sweden, Jun. 20, 1977, 7707127

Int. Cl.³ H05B 3/40

U.S. Cl. 219—388

4 Claims



1. An annealing oven for wire and the like, comprising:
 - (a) a tubular elongated heater, open at both of its ends, there being a wire-receptive passage extending between said ends, said heater being made of an electrical resistance alloy, said alloy being essentially molybdenumdisilicide;
 - (b) a pair of electrical terminals connected to said heater at longitudinally spaced points;
 - (c) guide structure at each end of said heater and disposed to keep moving wire in said passage out of contact with said heater; and
 - (d) at least one pair of sections of heat insulating material surrounding said heater, said sections being selectively movable, without disassembly, with respect to each other for regulating oven temperature.



4,295,034
HOT AIR GRILL
Jurgen Assmann, Michelbach, Fed. Rep. of Germany, assignor to Grossag GmbH, Fed. Rep. of Germany
Filed Dec. 5, 1978, Ser. No. 966,571

Claims priority, application Fed. Rep. of Germany, Dec. 6, 1977, 2754208

Int. Cl.³ A37J 37/00; A21B 1/22

U.S. Cl. 219—400

25 Claims



1. A portable hot air grill comprising a two-part base comprising a horizontal base portion and a vertical base portion foldably interconnected with one another, an electric motor mounted on said vertical base portion and having a horizontal shaft, a heating assembly projecting from said vertical base portion over said horizontal base portion and comprising a heater fan mounted on said motor shaft and an electric heating element in position to heat air blown by said fan, and a removable casing for receiving food stuff to be cooked, said horizontal base portion including means for removably supporting said casing thereon, and said casing being supported by removably resting by gravity on said horizontal base portion and having front, back, side, top and bottom walls of which at least said top wall is at least in part transparent, said back wall being unitary with said front and side walls and having an opening of a size and shape to receive said heating assembly when said casing rests on said horizontal base portion, said casing comprising at least two complementary, separable superposed parts which meet in a horizontal plane and have interfitting rim portions positioning said parts relative to one another when assembled one over another, said horizontal base portion and said casing having interfitting portions for positioning said casing in predetermined position on said horizontal base portion to receive said heating assembly through said opening said base being of a size to be received in said casing when in a folded-up condition.

4,295,035

DOUBLE-GRIP MOUNTING MEANS FOR SHEATHED HEATING ELEMENTS


Lester D. Drugmand, Arnold, Md., assignor to Electro-Therm, Inc., Laurel, Md.

Filed Sep. 10, 1980, Ser. No. 185,994

Int. Cl.³ H05B 3/06

U.S. Cl. 219—536

6 Claims



1. A double-grip mounting assembly for securing a sheathed metallic electric heating element to a metallic bracket having an aperture thereon, comprising in combination, a sheathed metallic electric heating element including a linear portion disposed within the aperture of said bracket, a tubular metallic insert of relatively thin material disposed within the aperture of said bracket and in surrounding relation to said heating element linear portion, said insert including integrally therewith; two radially outwardly extending flange-like portions, each one being disposed in snug axial relation and in direct contact with both sides of the said bracket adjacent to said aperture thereby to axially grip the bracket therebetween, an axially extending tubular portion in surrounding concentric relation to said heating element connecting the radially inner extremity of said flange-like portions, said flange-like portions respectively merging into axially adjacent reversely extending radially inwardly directed terminal flanges, with said terminal flanges in snug axial relation and in partial direct contact with the respective flange-like portions, and slightly flared at the bottom, said terminal flanges at their radially inner extremities defining openings of lesser effective diameter than said insert tubular portion, thereby to mechanically engage the periphery of said sheathed metallic heating element and secure the bracket thereto in double-gripped relation.

4,295,036

TOY CASH REGISTER


Kwok W. Tsui, Wanchai, Hong Kong, assignor to Arco Industries Ltd., Hong Kong

Filed Apr. 25, 1980, Ser. No. 143,850

Int. Cl.³ G07G 1/00

U.S. Cl. 235—1 E

10 Claims



1. A toy cash register comprising in combination, a shell-like housing provided with an upstanding rear hollow portion and a forwardly and downwardly sloping upper surface section extending forwardly therefrom and positioned over a lower compartment, said sloping surface having a relatively large

opening therein, a cash drawer slidable into and from a front opening in said lower compartment, latch means normally engaging complementary retaining means on said drawer within said compartment and spring means in said housing engaging said drawer to project it forwardly from said compartment when said latch is released, a rotatable register drum having money indicating indicia thereon enclosed within said upstanding rear hollow portion of said housing and operable about a horizontal axis therein, viewing means in a forward face of said upstanding rear portion of said housing within which indicia on said drum are viewable, a unitary cash key-simulating member having an area similar in size to said opening in said sloping surface and comprising a plurality of simulated cash keys upstanding thereon in fixed relation to each other in a bank arrangement and actuating means thereon extending from one end of said member into said upstanding portion of said housing and engageable with said rotatable register drum to rotate it, means pivotally connecting the opposite end of said key-simulating member to said housing for actuation thereof by depressing said member downwardly to effect rotation of said register drum, a release key pivotally supported by said housing and including means engageable with said latch means to disengage the same from said drawer and permit said spring means to project it to open position, and receipt-simulating member slidable forwardly through an opening in said housing upon actuation of said release key.

4,295,037

PRODUCTION COUNTER APPARATUS


Gary L. Miller, 16497 Terra Bella, Mt. Clemens, Mich. 48044

Filed Apr. 23, 1979, Ser. No. 32,124

Int. Cl.³ G06M 3/08; G07C 3/10

U.S. Cl. 235—92 PD

6 Claims



1. Counting apparatus for a production machine producing parts having a plurality of distinct states, said counting apparatus comprising:
 - means for detecting the production of a part;
 - first switch means, responsive to operator selection, for selecting between each of said plurality of distinct states of said produced part;
 - a plurality of electronic counter means, each responsive to said detecting means and said first switch means, for respectively counting the number of occurrences of one of said distinct states of said produced parts; and
 - a plurality of display means, each responsive to one of said counter means, for displaying the current number of occurrences of one of said distinct states of said produced part;
 second switch means switchable between first and second positions; and wherein
 - each counter means is responsive to said second switch means to hold the output signals transferred from said counter means to said display means at the state present when said second switch means is switched to said first position;
 - each of said counter means continuing to count the number of parts produced of a particular distinct state after said second switch means is switched to said first position so as to provide to the display means the total number of parts produced of a particular distinct state when said second switch means is switched to said second position.

4,295,038


MARKING AND COUNTING PROBE ASSEMBLY
Paul H. Kreinbrink, Temperance, Mich., and David C. Neiman, Waterville, Ohio, assignors to Libbey-Owens-Ford Company, Toledo, Ohio

Filed Oct. 10, 1979, Ser. No. 83,407

Int. Cl.³ G06M 11/00

U.S. Cl. 235—92 PK

11 Claims



1. A probe assembly for initiating electrical signals in serial for use in a counting apparatus comprising:
 - a. an elongated tubular housing having a transverse wall separating it into top and bottom sections, said sections being axially aligned;
 - b. a switch disposed in said top section for initiating electrical signals and including an axially extending plunger pin;
 - c. means disposed in said bottom section for operating said switch, said operating means including an axially reciprocal piston coaxially aligned with said plunger pin and engageable therewith for movement as a unit, said piston including an axial bore; and
 - d. a marking stylus detachably mounted within said bore to move with said piston, said stylus extending beyond the end of said elongated housing.

4,295,039


METHOD AND APPARATUS FOR ACHIEVING SECURE PASSWORD VERIFICATION
Paul E. Stuckert, Katonah, N.Y., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Dec. 3, 1979, Ser. No. 99,797

Int. Cl.³ G06K 5/00, 19/06; H04Q 9/00; G06F 7/00

U.S. Cl. 235—380

18 Claims



1. A personal identification system including the combination of a credit card-like device (CARD) to be presented by the holder of the CARD (Person), a Utilization Terminal (U/I

Terminal) to which the CARD is presented for identification purposes, and a data interface for the exchange of predetermined data between the CARD and the U/I Terminal, said CARD including means for permanently storing a secret key, K_7 , unique to said person, said combination further including, encryption means comprising at least one key-controlled block-cipher encryption device located in said CARD, a keyboard at which the person may enter a secret key, K_A , at least one random word generator for supplying a data input word for encryption by said encryption means, said encryption means being operable to encrypt a random word supplied by the random word generator under the stored key, K_7 , and also being operable to encrypt the same random word under said secret key, K_A , entered by the person at said keyboard, said encryption means utilizing identical encryption algorithms for each encryption operation, first comparison means in said Terminal for comparing the results of said first and second encryption operations and means for indicating a successful comparison.

4,295,040

DETECTOR ARRANGEMENT FOR DATA-CARD READERS


Daniel Berthier, Eybens, France, assignor to Hewlett-Packard Company, Palo Alto, Calif.

Filed Feb. 1, 1979, Ser. No. 8,306

Int. Cl.³ G06K 7/10, 7/14

U.S. Cl. 235—458

1 Claim



1. A card reader for reading cards marked either by holes or by writing and providing an output indicative not only of the presence or absence of a mark but of the type of mark as well, the card reader comprising:
 - a. a light source emitting light toward a principal surface of a card to be read;
 - b. a reflective surface having a reflective power greater than that of the unmarked surface of the card and located parallel to an opposite surface of the card, for reflecting light reaching the reflective surface via a hole in the card back through the hole;
 - c. an optical detector for receiving light of a first intensity reflected from marks indicated by writing on the card, light of a second intensity greater than the first reflected from the unmarked surface of the card, and light of a third intensity greater than the second reflected from the reflective surface through marks indicated by holes in the card, and for producing a sense signal whose amplitude is indicative of the amount of light reaching the optical detector; and
 - d. level detection means coupled to the sense signal for producing an output signal having three distinct values respectively indicative of the presence of a mark produced by a hole, the presence of a mark produced by writing, and the absence of a mark.

4,295,041

DEVICE FOR THE PROTECTION OF ACCESS TO A PERMANENT MEMORY OF A PORTABLE DATA CARRIER

Michel Ugon, Saint-Ouen, France, assignor to Compagnie Internationale pour l'Informatique CII-Honeywell Bull (Société Anonyme), France


Continuation-in-part of Ser. No. 936,694, Aug. 25, 1978, Pat. No. 4,211,919. This application Apr. 7, 1980, Ser. No. 137,973

Claims priority, application France, Aug. 26, 1977, 77 26107; Jul. 2, 1979, 79 17171

Int. Cl.³ G06K 19/06



U.S. Cl. 234—487

4 Claims



1. A portable data carrier for storing and processing data, comprising:
 - a. a microprocessor;
 - b. a protected memory to which access is to be protected;
 - c. an access memory element of the electrically alterable read only memory type and an error memory element of the electrically alterable read only memory type;
 - d. said microprocessor including internal first elements for reading and writing in said protected memory, second elements for receiving external data to be written in said protected memory, and third elements for externally transmitting data read from said protected memory; and
 - e. said internal first elements including means for checking an enabling key received from a device external to said carrier, means for storing an error bit in said error memory element when the enabling key is incorrect, and means for storing an access bit in said access memory element when the enabling key is correct.

tained in the leaf, and measuring the amount of both the components at the same time to determine the amount of chloro-



1. A portable data carrier for storing and processing data, comprising:
 - a. a microprocessor;
 - b. a protected memory to which access is to be protected;
 - c. an access memory element of the electrically alterable read only memory type and an error memory element of the electrically alterable read only memory type;
 - d. said microprocessor including internal first elements for reading and writing in said protected memory, second elements for receiving external data to be written in said protected memory, and third elements for externally transmitting data read from said protected memory; and
 - e. said internal first elements including means for checking an enabling key received from a device external to said carrier, means for storing an error bit in said error memory element when the enabling key is incorrect, and means for storing an access bit in said access memory element when the enabling key is correct.

4,295,043

FIBER OPTIC CABLE CONNECTOR


Jules A. Eibner, Dresher, and Franz X. Kanamuller, Glenside, both of Pa., assignors to Sperry Corporation, New York, N.Y.

Filed Dec. 13, 1979, Ser. No. 103,270

Int. Cl.³ G02B 5/14

U.S. Cl. 250—227

7 Claims



1. A connector which connects an optical cable to an electrical circuit, comprising:
 - a. a cable holder body;
 - b. a connector housing means formed to accept said cable holder body within and formed to locate a first end of said cable holder body in close proximity to a portion of said electrical circuit, said connector housing means being further formed to have access means;
 - c. a length indication means for selecting a value of a predetermined parameter of said electrical circuit when said length indication means is connected to said electrical circuit, said value being related to the length of said optical cable, said length indication means disposed between a section of said cable holder body and said connector housing means and accessible from without through said access means; and
 - d. electrically conducting contact means attached to said connector housing means and formed to electrically connect said length indication means to said electrical circuit.

4,295,042

METHOD OF AND DEVICE FOR MEASURING CHLOROPHYLL OF LIVING LEAVES
Shigeru Watanabe, Tokyo, and Tatsuo Kusunuki, Minamiashigara, both of Japan, assignors to Fuji Photo Film Co. Ltd., Minamiashigara, Japan

Filed Sep. 17, 1979, Ser. No. 76,475

Claims priority, application Japan, Sep. 18, 1978, 53/114364

Int. Cl.³ G01J 3/34

U.S. Cl. 250—226

6 Claims

1. A method for measuring the amount of chlorophyll contained in a leaf of a plant comprising the steps of causing light from a light source to pass through a leaf of a plant, dividing the light which has passed through the leaf into the first component of a shorter wavelength the amount of which changes with the amount of chlorophyll contained in the leaf and the second component of a longer wavelength the amount of which does not change with the amount of chlorophyll con-


4,295,044

BEVERAGE FLOW SWITCH

Kenneth W. Anderson, Fremont, Calif.; Brent Summerhays, Logan, Utah, and Verl O. Cazier, Lander, Wyo., assignors to Electronic Systems Engineering, Inc., Logan, Utah
Continuation of Ser. No. 927,200, Jul. 24, 1978, abandoned. This application Jul. 9, 1980, Ser. No. 167,273
Int. Cl.³ G01D 5/34

U.S. Cl. 250—229

9 Claims U.S. Cl. 250—255



1. A flow switch comprising
 - vertical conduit means having a lower, inlet means and an upper, outlet means;
 - a light path transecting the conduit means;
 - an open chamber extending outwardly from a side of the vertical conduit means and having an open end and a closed end with the open end providing an unobstructed opening into the vertical conduit means;
 - a stop means in the lower side of the open end of the open chamber;
 - pivotal mounting means in the open chamber adjacent the closed end of the open chamber;
 - an actuator arm pivotally mounted on the pivotal mounting means and extending into the vertical conduit means and resting against the stop, the actuator arm thereby extending horizontally into the vertical conduit means in obstruction of the light path, the actuator arm thereby being adapted to be moved upwardly from obstruction of the light path by flow of a liquid upwardly through the vertical conduit means between the lower, inlet means to the upper, outlet means, the actuator arm being adapted to be urged downwardly against the stop and across the light path by gravitational forces;
 - a light source on a first side of the vertical conduit means for transmitting light into the light path;
 - light detector means on a second side of the vertical conduit means for detecting light transmitted through the light path as the actuator arm is moved upwardly from obstruction of the light path as a result of upward light flow through the vertical conduit means; and
 - circuit means for electronically amplifying an electronic signal generated by the light detector means as a function of liquid flow through the vertical conduit means.


4,295,045

BACKGROUND COMPENSATION TYPE PLUTONIUM AIR MONITOR

Kentaro Minami, Oaraimachi, Japan, assignor to Japan Atomic Energy Research Institute, Tokyo, Japan
Filed Apr. 8, 1980, Ser. No. 138,406
Claims priority, application Japan, Apr. 28, 1979, 54-52030
Int. Cl.³ G01V 5/00; G01T 1/18

U.S. Cl. 250—255

2 Claims



1. A background compensating plutonium air monitor comprising:
 - a detector for producing electrical signals in response to the incidence of radiation;
 - an upper level discriminator and a lower level discriminator, each responsive to said electrical signals and each having an output, wherein the output of the upper level discriminator has a higher rate than the output of the lower level discriminator;
 - an anti-coincidence gate connected to the output of both the upper level discriminator and the lower level discriminator and having an output;
 - an arbitrary frequency divider for frequency dividing signals from the upper level discriminator and having an output; and
 - an automatic erasing circuit connected to the output of said anti-coincidence gate and the output of said arbitrary frequency divider wherein the signals from the output of the arbitrary frequency divider are combined with the signals from the output of the anti-coincident circuit so as to erase background signals from the output of the anti-coincidence gate.


4,295,046

MASS SPECTROMETER

Karl Gräter, Brauweiler, and Jürgen Leineweber, Cologne, both of Fed. Rep. of Germany, assignors to Leybold Heraeus GmbH, Cologne, Fed. Rep. of Germany
Continuation of Ser. No. 722,415, Sep. 13, 1976, abandoned. This application Sep. 8, 1978, Ser. No. 940,829
Claims priority, application Fed. Rep. of Germany, Sep. 11, 1975, 2540505
Int. Cl.³ B01D 59/44; H01J 49/00

U.S. Cl. 250—287

6 Claims



1. A transit time mass spectrometer for analyzing ions produced by pulsed laser radiation and having different energies, comprising, in combination:
 - (a) means forming a drift path to be traversed by the ions in a predetermined direction, said drift path comprising a cylindrical section having an input end and an output end;

- (b) an ion detector arranged downstream of said output end and having an entrance opening;
- (c) an electrostatic lens system for focussing as well as for accelerating the ions and including a plurality of electrodes, including three which are in the form of cylindrical sections, one of said three electrodes being constituted by said cylindrical section serving as said drift path and the other two of said sections being arranged upstream of said input end, said lens system being a means for focussing onto said entrance opening only those ions which have a predetermined energy interval lying in the region of the maximum energy distribution;
- (d) means for holding an ion-emitting test specimen which is to be subjected to the laser radiation, said holding means being constituted by that electrode of said lens system which is the furthest upstream of the input end of the drift path; and
- (e) means forming an aperture diaphragm arranged between an ion-emitting test specimen which is held by said holding means and the next downstream cylindrical section, said diaphragm having an aperture which is as small as possible without impairing the ion flow, said diaphragm being at the same potential as said next downstream cylindrical section.


4,295,047

EMISSION COMPUTED TOMOGRAPH

Kenichiro Koga; Yoshiharu Hirose, both of Kyoto; Iwao Kanno, Akita; Kazuo Uemura, Akita, and Shuichi Miura, Akita, all of Japan, assignors to Shimadzu Corporation, Japan
Filed Jan. 16, 1980, Ser. No. 112,787
Claims priority, application Japan, Jan. 23, 1979, 54-7390
Int. Cl.³ G01T 1/20; G21K 1/04

U.S. Cl. 250—363 S

9 Claims



1. An emission computed tomograph comprising: means for supporting an object to be examined at a predetermined position, said object having taken therein a radionuclide that emits penetrating radiation such as X- or gamma radiation; a plurality of radiation detectors; means for supporting said detectors side by side along a circle about said predetermined position so that the radiation incident planes of said detectors face said object so as to receive radiation from said objects the position of each of said detectors being stationary relative to said object; a plurality of collimators; means for supporting said collimators between said predetermined position and said detectors so that each of said collimators is disposed in front of one of said detectors; each of said collimators comprising a pair of thin main plates made of a material capable of blocking penetration of said radiation therethrough, said main plates extending radially inwardly of said circle so as to define the direction in which said radiation from said object is incident on said radiation incident plane of said detector, and said main plates having an axis of rotation at a border between said radiation incident planes of each adjacent two of said detectors so that said main plates are swingable about said respective axes over

4,295,048

METHOD AND SYSTEM FOR SCANNING A BEAM OF CHARGED PARTICLES TO CONTROL IRRADIATION DOSAGE


Marshall R. Cleland, 9 Mohegan Pl., Huntington Station, N.Y. 11746, and Howard F. Malone, Sr., 35 Third Ave., Massapequa Park, N.Y. 11762

Filed Apr. 28, 1980, Ser. No. 145,061

Int. Cl.³ G01K 1/08; G01N 23/00

U.S. Cl. 250—398

29 Claims



1. A system for controlling the scanning of a beam of charged particles across a conveyor path to produce selective radiation dose at various locations comprising
 - particle accelerator means for producing a beam of charged particles;
 - deflecting means controllably operable to deflect said beam to a plurality of discrete positions across the conveyor path; and
 - control means coupled with said deflecting means to maintain said beam at each said discrete position for a preselected time in accordance with the radiation dose required at each said discrete position.

4,295,049

X-RAY DIAGNOSTIC GENERATOR WITH AN INVERTER SUPPLYING THE HIGH-TENSION TRANSFORMER

Otto Ebersberger, Erlangen, and Werner Kuehnle, Uttenreuth, both of Fed. Rep. of Germany, assignors to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany
Filed Feb. 1, 1980, Ser. No. 117,549

Claims priority, application Fed. Rep. of Germany, Mar. 6, 1979, 2908767


Int. Cl.³ H05G 1/32

U.S. Cl. 250—409

10 Claims


1. An x-ray diagnostic generator comprising
 - an inverter having an input and an output and having a controllable frequency of operation,
 - a high tension transformer having an input connected with the output of the inverter, and having an output,
 - a high tension rectifier having an input connected with the output of the high tension transformer, and having an output,
 - high tension capacitors connected at the output of the high tension rectifier,
 - control loop means for receiving respective pairs of set point value signals in accordance with respective settings of x-ray tube voltage and current, and operable for sensing actual value signals in accordance with actual values of x-ray tube voltage and current and for controlling x-ray tube voltage and current to minimize errors between the settings of x-ray tube voltage and current, and the actual values thereof,
 - said control loop means comprising x-ray tube voltage con-

trol means (7, 20, 21, 21a, 30) connected with said inverter and operable to control inverter frequency to minimize the error between an x-ray tube voltage set point value signal and an x-ray tube voltage actual value signal, and direct current supply means (16-19) connected with the input of said inverter (7) and operable for controlling the voltage supplied to said inverter, program storage means (23) for supplying an optimum value signal in accordance with an optimum value of inverter



input voltage for each pair of settings of x-ray tube voltage and current to be received by said control loop means, and inverter input voltage control means (24-29) connected with said direct current supply means (16-19) for setting the voltage supplied to said inverter (7) and connected with said storage means (23) and responsive to the optimum value signal therefrom to set the inverter input voltage at an optimum value during an operation of said generator with corresponding settings of x-ray tube voltage and current.


4,295,050
INSTRUMENT FOR POSITIONING AN X-RAY CAMERA
IN DENTAL X-RAY PHOTOGRAPHY
Sigurd Linden, Teatergatan 4, Linköping, Sweden
Filed Feb. 15, 1980, Ser. No. 121,880
Claims priority, application Sweden, Feb. 27, 1979, 7901788
Int. Cl.³ A61B 6/14
U.S. Cl. 250—479 6 Claims



1. An instrument for positioning the X-ray camera relatively the object and the X-ray film when taking X-ray photographs of teeth or adjacent tissues, comprising a plate-like member which at its one end, during the exposure of the film located inside the object as related to the camera, has a support for holding the film in a plane perpendicular to the longitudinal axis of said plate-like member, the outer end portion of the plate-like member being arranged, during exposure of the film, to be located outside the row of teeth of the patient and having a laterally extending arm-like portion located perpendicularly to the plate-like member and coplanar therewith, means being arranged to receive a guide pin in a position where its longitudi-

dinal axis is parallel to that of said plate-like member and said guide pin protrudes outside the oral cavity of the patient, whereby the optical axis of the X-ray camera objective can be positioned relatively said pin and, thence, relatively the film.

4,295,051
OPTICAL CARD READER
Fredy E. Graf, William M. Mahler, and Howard J. Malan, all of San Diego, Calif., assignors to General Atomic Company, San Diego, Calif.
Filed May 21, 1979, Ser. No. 40,571
Int. Cl.³ G06K 7/10
U.S. Cl. 250—569 11 Claims




1. An on-the-fly optical card reader for use with processing means for decoding multibit data words from a card as it is inserted therein and providing digital output signals corresponding to the data words encoded on the card, comprising: frame means for supporting components of the reader and for mounting said reader; guide means associated with the frame means for slidably receiving and positioning the card to be decoded; means for optically reading one row having at least two of said multibit digital encoded data words from said cards, said reading means being adapted to sequentially read each row of said data words as said card is inserted in said reader, said reading means being adapted to read at least two data words per row with the bits of each data word being adjacent one another and said words being separate from one another at specific locations along said row, said reading means generating digital signals corresponding to said data words and providing the digital signals of a complete one of the two or more data words at the output of said card reader in response to a control signal identifying a single data word location being selectively applied thereto.

4,295,052
CIRCUIT FOR MOTOR VEHICLES
Franz Jochmann, Munich, and Helmar Jedeck, Oberschleissheim, both of Fed. Rep. of Germany, assignors to Bayerische Motoren Werke Aktiengesellschaft, Munich, Fed. Rep. of Germany
Filed Mar. 21, 1979, Ser. No. 22,632
Claims priority, application Fed. Rep. of Germany, Mar. 23, 1978, 2812721
Int. Cl.³ B60R 27/00
U.S. Cl. 307—10 R 18 Claims


1. A circuit arrangement for motor vehicles comprising circuit means responsive to operation of an actuating means of the motor vehicle for being energized, the actuating means including an actuating device of at least one of a door and flap lock of the motor vehicle, timer means responsive to the operation of the actuating device for providing a predetermined switching period, the circuit means being responsive to the elapse of the predetermined switching period of the timer means for being automatically de-energized, the circuit means

including at least one of a door and flap lock heater and at least one additional load means, the at least one additional load




means being energized in response to the actuating means enabling opening of the motor vehicle.

4,295,053
ELECTRIC CONTROL SYSTEM WITH MECHANICAL INTERLOCK
George N. Kovatch, Monroeville, and James B. Wallace, Beaver, both of Pa., assignors to Westinghouse Electric Corp., Pittsburgh, Pa.
Filed Oct. 23, 1979, Ser. No. 87,365
Int. Cl.³ H02J 9/06
U.S. Cl. 307—64 7 Claims




1. An electric control system for switching between supply lines extending to a load, comprising an isolation switching structure, a transfer switching structure, and a bypass switching structure; the isolation switching structure including first and second control devices, the transfer switching structure including third and fourth control devices, the bypass switching structure including fifth, sixth and seventh control devices, all of the control devices having contact carriers operable between open and closed circuit conditions; an emergency supply line including a first of two parallel paths extending to a load with one path including the first, third, and sixth control devices in series and with the other path including the fifth control device; a normal supply line including a second of two parallel paths extending to the load with one path including the second, fourth, and sixth control devices in series and with the other path including the seventh control device; and the bypass switching structure including interlock means including levers between the fifth, sixth, and seventh control devices for preventing closing of two control devices when one is previously closed.

4,295,054
ELECTRIC CONTROL SYSTEM WITH ROTARY MECHANICAL INTERLOCK AND TIMING MECHANISM
George N. Kovatch, Monroeville; George S. Bettencourt, Murrysville, and Otto H. Soles, North Huntingdon, all of Pa., assignors to Westinghouse Electric Corp., Pittsburgh, Pa.
Filed Oct. 23, 1979, Ser. No. 87,366
Int. Cl.³ H02J 9/00
U.S. Cl. 307—80 6 Claims



1. An electric control system for switching between two current supply lines extending to a load, comprising an isolation switching structure, a transfer switching structure, and a bypass switching structure; the isolation switching structure including first and second control devices, the transfer switching structure including third and fourth control devices, the bypass switching structure including fifth, sixth, and seventh control devices, all of the control devices being operable between open and closed circuit conditions; one of the current supply lines including a first of two parallel paths extending to the load with one path including the first, third, and sixth control devices in series and with the other path including the fifth control device; the other of the current supply lines including a second of two parallel paths extending to the load with one path including the second, fourth, and sixth control devices in series and with the other path including the seventh control device; the bypass switching structure including interlock timing means between the fifth, sixth, and seventh control devices for preventing simultaneous closing of one control device when another of the control devices is closed.

4,295,055
CIRCUIT FOR GENERATING SCANNING PULSES
Iwao Takemoto, Kodaira; Norio Koike, Tokyo; Shinya Ohba; Haruhisa Ando, both of Kokubunji; Masaaki Nakai, Hachioji; Syoji Hanamura; Ryuichi Izawa, both of Kokubunji; Masaharu Kubo; Masakazu Aoki, both of Hachioji, and Shuhei Tanaka, Higashiyamato, all of Japan, assignors to Hitachi, Ltd. and Hitachi Denshi Kabushiki Kaisha, both of Tokyo, Japan
Filed Jun. 6, 1979, Ser. No. 46,028
Claims priority, application Japan, Jun. 12, 1978, 53/69793
Int. Cl.³ H03K 27/00
U.S. Cl. 307—221 C 29 Claims



1. A circuit for generating scanning pulses comprising a plurality of stages of basic circuits connected in series, said each basic circuit comprising first, second and third insulated gate field-effect transistors (MISTs) each of which has first and

second terminals each being either of source and drain terminals and a gate terminal, said first terminal of said first MIST being used as a clock pulse-applying terminal, said gate terminal of said first MIST being used as an input terminal, said second terminal of said first MIST and said first terminal of said second MIST being connected and used as a scanning pulse output terminal, said second terminal of said second MIST and said first terminal of said third MIST being connected and used as an output terminal, said second terminal of said third MIST being used as a ground terminal, said gate terminal of said third MIST being used as a feedback input terminal.

4,295,056

INTEGRATED FREQUENCY DIVIDER


Jacob Luscher, Venthorne, Switzerland, assignor to Ebauches S.A., Switzerland

Filed Jul. 2, 1979, Ser. No. 54,230

Int. Cl.³ H03K 21/00, 5/13

U.S. Cl. 307—221 C

10 Claims



1. A frequency divider circuit for two periodic signals in phase opposition comprising, integrated in a semi-conductor substrate, a first shift register comprising a plurality of transistors and capacitors which form a plurality of cells connected one after the other, each cell being constituted by two identical stages which are connected in series and are supplied, in use, by the two periodic signals respectively, first detection means for detecting a particular state of the register, and first production means, responsive to the detecting of the said state to produce a first signal with a frequency which is a sub-multiple of that of the said periodic signals, and wherein each stage of the shift register comprises an MOS transistor structure which has two principal electrodes respectively forming the input and output of the stage and two control electrodes, one of which is, in operation, connected to a bias source and the other of which is connected to the output principal electrode, and a capacitor, one plate of which is connected to the said output electrode and the other plate of which receives one of the said periodic signals.

4,295,057

DUAL SIGNAL CONTROL SYSTEM

Thomas E. Hendrickson, Wayzata, Minn., assignor to Honeywell Inc., Minneapolis, Minn.

Filed Nov. 8, 1979, Ser. No. 92,785

Int. Cl.³ H03K 5/22, 5/00


U.S. Cl. 307—231

16 Claims

1. An electronic switching circuit receiving first and second control signals, said electronic switching circuit being capable of providing a logic output signal having a phasing of value changes therein similar to that phasing of changes in value of a selected one of said first and said second control signals for those changes of said selected signal which are sufficient in magnitude and rate of change, but only for each such change in said selected signal which is accompanied by a change of value in an opposite direction in that remaining one of said first

and second control signals occurring sufficiently concurrently therewith, said electronic control circuit comprising:

- a first rising signal detector having an input region for receiving said first control signal, and having an output region, said first rising signal detector being capable of providing an output indication at said output region if said first control signal has an increase in value which exceeds a selected magnitude and also exceeds a selected rate of increase;
- a second rising signal detector having an input region for receiving said second control signal, and having an output region, said second rising signal detector being capable of providing an output indication at said output region if said second control signal has an increase in value which exceeds a selected magnitude and also exceeds a selected rate of increase;
- a first falling signal detector having an input terminal for receiving said first control signal, and having an output region, said first falling signal detector being capable of providing an indication at said output region if said first control signal has a decrease in value which exceeds a selected magnitude and also exceeds a selected rate of decrease;
- a second falling signal detector having an input region for



receiving said second control signal, and having an output region, said second falling signal detector being capable of providing an indication at said output region if said second control signal has a decrease in value which exceeds a selected magnitude and also exceeds a selected rate of decrease; and

- a logical sorting means having a first input connected to said first rising signal detector output region, a second input electrically connected to said second rising signal detector output region, a third input electrically connected to said first falling signal detector output region, and a fourth input electrically connected to said second falling signal detector output region, and with said logic sorting means having an output region, said logic sorting means being capable of providing said electronic switching circuit logic output signal at said logical sorting means output region in a first state when output indications occur substantially concurrently at said first rising signal detector output region and said second falling signal detector output region, and of providing said electronic switching circuit logic output signal at said logical sorting means output region in a second state when output indications occur substantially concurrently at said first falling signal detector output region and said second rising signal detector output region.

4,295,058

RADIANT ENERGY ACTIVATED SEMICONDUCTOR SWITCH


Robert W. Lade, Charlotte Amalie, V.I.; Gordon B. Spellman, Mequon, Wis.; Stanley V. Jaskolski, Sussex, Wis.; Herman P. Schutten, Elm Grove, Wis., and James R. Jaeschke, Wauke-sha, Wis., assignors to Eaton Corporation, Cleveland, Ohio

Filed Jun. 7, 1979, Ser. No. 46,568

Int. Cl.³ H03K 17/72, 17/94, 17/687

U.S. Cl. 307—252 A

29 Claims



- 1. A radiant energy activated semiconductor switching device comprising in combination:

a semiconductor switch having a plurality of alternating conductivity type regions, including a pair of end regions and a middle control region, and switchable from a low current OFF state to a high current ON state between said end regions by a triggering signal applied to said control region;

normally conductive variable conductance means connected between said control region and one of said end regions of said switch, said variable conductance means having a control terminal for varying the conduction value thereof between a conductive state and a state having greater conductivity, said normally conductive variable conductance means being conductive when no potential is applied to said control terminal and being less conductive when potential is applied to said control terminal, the requisite magnitude of said triggering signal decreasing as the conduction of said variable conductance means decreases; and

transducer means connected to said control terminal of said variable conductance means and responsive to impinging radiant energy to develop an electrical bias potential which biases said variable conductance means and decreases the conduction value thereof.

4,295,059

HIGH GAIN LATCHING DARLINGTON TRANSISTOR


Robert L. Steigerwald, Scotia, N.Y., assignor to General Electric Company, Schenectady, N.Y.

Filed Mar. 30, 1979, Ser. No. 25,383

Int. Cl.³ H03K 17/12, 17/60, 17/72

U.S. Cl. 307—253

2 Claims



- 1. A high gain latching Darlington transistor having increased dv/dt capability comprising:

(a) a four-layer PNP semiconductor switching device

having a gate, a cathode, and an anode electrode, said four-layer PNP semiconductor switching device conducting current through the anode-cathode portion thereof in accordance with the polarity of the gating pulse signals applied to said gate electrode;

(b) a load transistor having a base, a collector, and an emitter electrode, said load transistor coupled in Darlington configuration to said four-layer PNP semiconductor switching device, said load transistor conducting substantial load current through the collector-emitter portion thereof in response to current conduction through said four-layer PNP semiconductor switching device; and

(c) first and second diodes coupled in inverse series aiding fashion between the gate electrode of said 4-layer PNP semiconductor and the junction of said 4-layer PNP semiconductor and said load transistor base electrode.

4,295,060

SOLID STATE TRIGGERING CIRCUIT


Richard S. McGehee, 1509 Crawford La., Hanover Park, Ill. 60103

Filed Sep. 20, 1979, Ser. No. 77,347

Int. Cl.³ H03K 3/284, 3/42

U.S. Cl. 307—273

10 Claims



1. An electronic triggering circuit comprising: light sensing circuit means for providing a first electrical signal responsive to a predetermined interruption of light exposure, RC time delay circuit means having discharging capacitor means and providing an electrical output signal following a predetermined time delay from the receipt of an electrical input signal, said predetermined time delay provided by the electrical discharge of said discharging capacitor means, first monostable electronic circuit means connected to receive the first electrical signal of the light sensing circuit means and being activated thereby for providing a predetermined ON time period and further providing a first electrical output signal during the ON time period comprising the electrical input signal to the RC time delay circuit means, said first monostable circuit means including RC time constant means with charging capacitor means biasing the first monostable circuit means after a first predetermined charging time period to switch to an OFF electrical state whereby the first electrical output signal is discontinued, the first predetermined charging time period of the first monostable circuit means exceeding the discharging time period for the RC time delay circuit means, second monostable electronic circuit means connected to receive as an input signal thereto the electrical output signal from the RC time delay circuit means, said second monostable circuit means having a predetermined ON time period and providing a second electrical output signal during the ON time period, and including RC time constant means with charging capacitor means biasing the second monostable circuit means after a second predetermined charging time period to switch to an OFF electrical state whereby the second electrical output signal is discontinued, and third monostable electrical circuit means connected to receive as an input signal thereto the second electrical output signal from the second monostable circuit means, said third monostable circuit means having a predetermined ON time period and providing a third electrical output signal during the ON time period, and including RC

time constant means with charging capacitor means biasing the third monostable circuit means after a third predetermined charging time period to switch to an OFF electrical state whereby the third electrical output signal is discontinued, and the second predetermined charging time period exceeding the third predetermined charging time period whereby the third monostable circuit means is disabled to provide said third electrical output signal during the continued charging time period for the second monostable circuit means, and the third electrical output signal comprising the electrical output triggering signal of the electronic triggering circuit.

4,295,061

LATCH CIRCUIT

Saburo Tokoda, Koichiro Okumura, and Eiji Sugimoto, all of Tokyo, Japan, assignors to Nippon Electric Co., Ltd., Tokyo, Japan


Filed Mar. 16, 1979, Ser. No. 21,281

Claims priority, application Japan, Mar. 16, 1978, 53/30773

Int. Cl.³ H03K 5/26

U.S. Cl. 307-279

6 Claims



1. A circuit comprising a first inverter circuit having input and output terminals, means for applying an input signal to the input terminal of said first inverter circuit, a second inverter circuit having an input terminal coupled to the output terminal of said first inverter circuit and having an output terminal, and feed-back means coupled between said input terminal of the first inverter circuit and said output terminal of the second inverter circuit, said feed-back means including a first insulated-gate field-effect transistor having a drain, a gate and a source, the drain and gate of said first transistor being commonly coupled to the output of said second inverter circuit, and a second insulated-gate field-effect transistor having a gate, a drain and a source, the source of said second transistor being coupled to the source of said first transistor, the gate and drain of said second transistor being commonly coupled to the input terminal of said first inverter circuit.

4,295,062

CMOS SCHMITT TRIGGER AND OSCILLATOR


Stephen K. Mihalich, Santa Clara, and Thomas S. W. Wong, Sunnyvale, both of Calif., assignors to National Semiconductor Corporation, Santa Clara, Calif.

Filed Apr. 2, 1979, Ser. No. 26,277

Int. Cl.³ H03K 3/295, 3/354, 4/48

U.S. Cl. 307-279

9 Claims



1. A complementary metal oxide semiconductor trigger

circuit having a non-inverting signal transfer characteristic that displays hysteresis, said circuit having first and second power supply rails connectable to a source of operating voltage and comprising:

- a resistor having a value that is large with respect to the on resistance of an active transistor and having first and second terminals;
- a first P channel transistor having a source coupled to said first supply rail, a drain coupled to said first resistor terminal, and a gate;
- a second N channel transistor having a source coupled to said second supply rail, a drain coupled to said second resistor terminal, and a gate;
- means for coupling said gates of said first and second transistors together to comprise an input terminal to said circuit;
- a third P channel transistor having a source coupled to said first supply rail, a gate coupled to said drain of said first transistor, and a drain;
- a fourth N channel transistor having a source coupled to said second supply rail, a gate coupled to said drain of said second transistor, and a drain; and

means for coupling said drains of said second and third transistors together to comprise an output terminal to said circuit whereby the output signal is responsive to the potential difference developed between said first and second resistor terminals to provide first and second logic state output signals, said first logic state being produced when said input terminal is operated at a potential that lies between the potential of said first supply rail and the threshold potential of said first transistor and said second logic state being produced when said input terminal is operated at a potential that lies between the potential of said second supply rail and the threshold potential of said second transistor.

4,295,063

FAST SETTLING DIGITAL TO ANALOG CONVERTER BIT SWITCH


John J. Price, Jr., Mesa, Ariz., assignor to Motorola Inc., Schaumburg, Ill.

Filed Jun. 28, 1979, Ser. No. 53,131

Int. Cl.³ H03K 5/153, 17/02

U.S. Cl. 307-362

2 Claims



1. A current bit switch for use in a digital to analog converter for directing a bit current generated by a first current source to an output bus, comprising:

- a first differential pair of switching devices for receiving a reference voltage and a digital input signal, said digital input signal capable of assuming first and second states;
- a second differential pair of switching devices for directing said bit current onto said output bus when said input signal is in said first state;
- a third differential pair of switching devices having an input coupled to said first pair and having an output coupled to said second pair for reducing overshoot caused by fast transitions of said input signals between said first and second states,
- a second current source for supplying current to said first

pair of switching devices; and a third current source coupled to said third pair of switching devices,

said first differential pair of switching devices comprising first and second emitter coupled transistors, said first transistor having a base coupled to said input signal and having a collector coupled to said third differential pair and said second transistor having a base coupled to a reference voltage and a collector coupled to said third differential pair,

said third differential pair comprising third and fourth emitter coupled transistors, the base of said third transistor coupled to the collector of said first transistor and to a first source of supply voltage and the collector of said third transistor coupled to a second source of supply voltage, the base of said fourth transistor coupled to the collector of said second transistor and to said first source of supply voltage and the collector of said fourth transistor coupled to said second source of supply voltage, the common emitters of said third and fourth transistors coupled to said third current source, and

said second differential pair comprising fifth and sixth emitter coupled transistors, said fifth transistor having a base coupled to the collector of said third transistor and to said second source of supply voltage and having a collector coupled to said output bus, and said sixth transistor having a base coupled to the collector of said fourth transistor and to said second source of supply and having a collector coupled to ground, the emitters of said fifth and sixth transistors coupled to said first current source, and said first and second transistors being PNP transistors and said third, fourth, fifth and sixth transistors being NPN transistors.

4,295,064

LOGIC AND ARRAY LOGIC DRIVING CIRCUITS


Stanley E. Schuster, Granite Springs, N.Y., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Jun. 30, 1978, Ser. No. 920,943

Int. Cl.³ H03K 19/173, 19/20, 19/094

U.S. Cl. 307-468

3 Claims



1. A prearray logic section of a programmed logic array having a partitioning logic circuit wherein each logical input variable is combined and duplicated to provide a separate output for each of all possible logical combinations of all logical input variables and wherein each said output having a driver circuit comprising:

- a first FET transistor having its source connected to the reference potential of said logic circuit and having its drain connected through a load device to a drive voltage;

means connecting the input to the gate of said first FET transistor;

a second and a third FET transistor of the type exhibiting no conduction in the "off" condition connected in series source-to-drain with said second FET transistor adjacent to the reference potential of said logic circuit and said third FET transistor adjacent to a drive voltage;

means connecting the output to the junction between said second and third series connected FET transistors;

means connecting the input to the gate of said third series connected FET transistor; and

means connecting the output of said first FET transistor to the gate of said second FET transistor.

4,295,065

LEVEL SHIFT CIRCUIT


Peter K. Hsieh, Parsippany, and Richard M. Vaccarella, Raritan, both of N.J., assignors to RCA Corporation, New York, N.Y.

Filed Aug. 13, 1979, Ser. No. 65,841

Int. Cl.³ H03K 19/092, 19/094, 19/20

U.S. Cl. 307-475

18 Claims



1. The combination comprising:

first and second power terminals for the application therebetween of an operating potential;

an input terminal adapted to receive input signals having either a first value approximately equal to the potential applied to said first power terminal or a second value equal to a voltage intermediate the voltages applied to said first and second power terminals;

a level shift control node, and an output node;

a first input signal responsive means including means connected between one of said first and second power terminals and said output node and between said output node and said level shift control node for clamping said one of said first and second terminals to said output node and said output node to said level shift control node for one value of input signal and decoupling said one of said first and second terminals from said output node and said output node from said level shift control node for the other value of input signal;

a second, normally non-conductive, input signal responsive means for clamping said level shift control node to said other one of said first and second power terminals for the other value of input signal; and

regenerative feedback means responsive to the voltage at said level shift control node for clamping said input terminal to said second power terminal in response to input signals of said second value.

4,295,066


ELECTROMAGNETIC ACTUATOR

C. F. Lloyd, Rexdale; Z. Leo Zalewski, Brampton, and Paul C. Brendle, Mississauga, all of Canada, assignors to CTS Corporation, Elkart, Ind.

Filed Jan. 11, 1980, Ser. No. 111,398
Int. Cl.³ H02K 33/12

U.S. Cl. 310—30

10 Claims



1. In an electromagnetic actuator, the combination comprising a housing of magnetizable material, a bobbin supported by the housing and provided with an interior bore, an armature supported in the interior bore for movement relative to the housing, the armature being provided with a magnet and a pair of spaced magnetic poles, the bobbin comprising a pair of bobbin sections, an inner rim and an outer rim secured to each of the bobbin sections, and means connecting the bobbin sections, the interior bore extending through the sections and the means connecting the sections, a radial bore being provided in the means connecting the sections and communicating with the interior bore to reduce resistance retarding movement of the armature, a coil carried by each of the bobbin sections and circumposing the armature, the coils being associated with the magnet poles, a first and a second wire end portion extending from each of the coils and disposed between the inner rims, the first wire end portion of each of the coils being electrically interconnected, and means securing the wire end portions to the bobbin.

4,295,067

COOLING APPARATUS FOR ELECTRICAL MACHINERY

Georg Binder, Bechhofen, and Günter Wössner, Esslingen, both of Fed. Rep. of Germany, assignors to Robert Bosch GmbH, Stuttgart, Fed. Rep. of Germany


Filed Feb. 7, 1979, Ser. No. 10,049

Claims priority, application Fed. Rep. of Germany, Mar. 9, 1978, 2810222

Int. Cl.³ H02K 9/00

U.S. Cl. 310—52

12 Claims



1. In a d-c generator, particularly automotive alternator having a housing (1);

a stator structure (2) having stator windings thereon located in the housing;
a rotor structure (3) including a rotor shaft (4) rotatably positioned within the housing to rotate with respect to the stator;
a heat pipe structure including heat pipe cooling means (11, 14, 15, 18, 21, 21b, 24, 24', 30, 34, 36) to cool the stator windings on the stator structure including means (11a, 14a, 15a, 18a, 21a, 24a, 24a', 30a, 34a, 36a) 36a', 41, 42, 41', 42') for forming an evaporation chamber and means (11b, 14b, 15b, 18b, 21d, 21f, 24b, 27, 30b, 33, 36b, 39, 39') for forming a condensation chamber in fluid communication with said evaporation chamber, and an evaporatable fluid contained in said chambers and wherein, in accordance with the invention, the evaporation chamber forming means (11a, 14a, 15a, 18a, 21a, 24a, 24a', 30a, 34a, 36a, 36a', 41, 42, 41', 42') are positioned adjacent the stator structure (2) and in heat transfer relation thereto;
the condensation chamber forming means are secured externally of the housing and in a location at which the temperature is low with respect to that of the stator windings;
a sequence of multiple and mutually communicating heat pipes is provided in communication with, and interconnecting said chambers;
and said shaft (4) consists of a fan-less or ventilator wheel-less construction.

4,295,068

CANTILEVERED FIELD WINDING SUPPORT FOR A SUPERCONDUCTING AC MACHINE


Bruce B. Gamble, Clifton Park, N.Y., assignor to General Electric Company, Schenectady, N.Y.

Filed May 18, 1979, Ser. No. 40,172

Int. Cl.³ H02K 9/00

U.S. Cl. 310—52

12 Claims



1. In a superconducting electrical machine including a rotor comprising a shaft adapted to be driven in rotation about a longitudinal axis of the rotor, a hollow undriven shaft disposed concentrically with said driven shaft and a hollow axially central portion disposed concentrically with and attached to each of said shafts, and a torque tube and at least one superconducting winding disposed within said hollow central portion; a support means for said torque tube and said field winding comprising:
means for supporting said torque tube and said superconducting winding within said central portion and substantially concentrically with said rotor shafts in cantilever fashion from one of said shafts.

4,295,069

ARMATURE SHAFT FOR A VEHICLE STARTER MOTOR


David E. Givan, Anderson, and Charles R. Ashton, Middletown, both of Ind., assignors to General Motors Corporation, Detroit, Mich.

Filed Apr. 17, 1978, Ser. No. 897,109

Int. Cl.² H02K 7/00

U.S. Cl. 310—67 R

3 Claims



1. An armature shaft for a motor vehicle engine starter motor assembly of the type having an axially movable clutch and pinion drive assembly splined to the armature shaft for rotation therewith, the armature shaft comprising, in combination:

a tubular member having an open end and another end and being adapted to receive armature core laminations thereon; and

a solid cylindrical member having one end provided with at least one spiral spline groove adapted for engagement with the clutch and pinion drive assembly and another end, the other ends of the tubular and solid cylindrical members comprising the opposite ends of the armature shaft, the one end of the cylindrical member being received coaxially in the open end of the tubular member, the open end of the tubular member having at least one portion thereof radially staked into the spline groove, whereby the tubular and cylindrical members are joined to each other, the portions of the open end of the tubular member which are not radially staked into the spline groove being effective to provide an axial stop for the clutch and pinion drive assembly.

4,295,070

MEANS FOR PROVIDING A MECHANICALLY DEFINABLE SELECTED TRIGGER INTERVAL IN A FLYWHEEL MAGNETO

Sven H. Johansson, Amal, Sweden, assignor to Aktiebolaget Svenska Elektromagneter, Amal, Sweden

Filed Jun. 14, 1979, Ser. No. 48,685

Claims priority, application Sweden, Jun. 16, 1978, 7806971

Int. Cl.³ H02K 21/22


U.S. Cl. 310—70 R

1 Claim

1. A flywheel magneto in an electronic ignition circuit, including:

- (a) a flywheel;
- (b) a ferromagnetic core having in succession a first leg, a second leg, and a third leg, each leg terminating at the periphery of said flywheel;
- (c) a trigger coil in said circuit and carried on said first leg, and a charging coil carried on said third leg;
- (d) a pair of magnetic pole shoes and a permanent magnet disposed between said shoes and jointly molded into said flywheel, said pole shoes being disposed at the periphery of said flywheel in magnetic circuit with said permanent magnet, a first of said shoes, situated first in the direction of rotation of said flywheel, having such extent that its flux can coact with said first and second legs in one position, said first pole shoe having a notch underlying its leading edge for limiting initial flux transfer to said second leg, the leading edge of said one shoe being sharply de-

fined, the leading edge of a second of said shoes, thereafter, coming to the first encountered edge of said first leg where the magnetic flux of said second shoe begins to coact with magnetic flux in said second leg;
(e) a first-encountered edge of each of said first and second legs being sharply defined and registering with the path of movement of said pole shoes; and



(f) the distance between said leading edges defining the duration of a triggering signal induced in said trigger coil, said signal beginning in response to said leading edge of said first shoe encountering the first-encountered edge of said second leg, and said signal ending in response to said leading edge of said second shoe encountering the first-encountered edge of said second leg.

4,295,071

LATTICE BAR FOR ELECTRICAL MACHINERY

Ernst Kaspar, Birr, Switzerland, assignor to BBC Brown, Boveri & Company Limited, Baden, Switzerland


Filed Apr. 5, 1979, Ser. No. 27,408

Claims priority, application Switzerland, Apr. 6, 1978, 3691/78

Int. Cl.³ H02K 3/14

U.S. Cl. 310—213

7 Claims



1. In a lattice bar for electrical machinery comprised of a plurality of transposed flat copper conductors insulated from each other and having bending portions along their length, the improvement wherein a notch is provided in only one flat side of each transposed conductor, each notch extending approximately longitudinally of an extended edge of its respective transposed conductor over the entirety of the bending portion of the conductor.

4,295,072

FIELD EMISSION ELECTRON GUN WITH ANODE HEATER AND PLURAL EXHAUSTS

Hideo Todokoro, Hinodemachi, and Yoshio Sakitani, Ohimachi, both of Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Filed Feb. 1, 1979, Ser. No. 8,259

Claims priority, application Japan, Feb. 8, 1978, 53-13722[U]


Int. Cl.³ H01J 7/16

U.S. Cl. 313—7

7 Claims

1. A field emission electron gun comprising:
a field emission cathode;
an anode having an aperture through which an electron beam emitted by said cathode can pass;

heating means for heating said anode;
a first chamber in which said cathode is disposed;
first exhaust means for evacuating said first chamber;



a second chamber adjoining said first chamber through said anode and in which said heating means is disposed, and second exhaust means for evacuating said second chamber independently from said first chamber.

4,295,073


MICROCHANNEL PLATE-IN-WALL STRUCTURE

Charles F. Freeman, Springfield, and Kurt Villhauer, Annandale, both of Va., assignors to The United States of America as represented by the Secretary of the Army, Washington, D.C.
Filed Mar. 28, 1978, Ser. No. 890,899

Int. Cl.³ H01J 43/22, 43/28

U.S. Cl. 313-105 CM

9 Claims



1. A microchannel plate-in-wall structure comprising:
a microchannel plate consisting of semiconducting glass, having anode and cathode surfaces and a plurality of electron multiplier channels therebetween;
at least one continuous thin planar electrode deposited on each of said surfaces, said electrode extending substantially to the edge of said plate as well as adjacent to and surrounding one end of at least one of said channels; and
a first hollow generally cylindrical glass wall section axially positioned normal to one of said surfaces and sealed with glass directly to said electrode and plate, said wall section at said surface having a minimum cross-section which encloses all of the ends of said channels at said one surface, and a maximum cross-section smaller than said one surface, whereby said one plate surface and each said one thin planar electrode it supports is divided into a pair of exposed portions which lie on opposite sides of said wall interconnected by a third portion sealed between said wall and said plate.

4,295,074 MERCURY ARC LAMP HAVING COMMUNICATING MERCURY RESERVOIR


Frank R. Ragland, Jr., Lancaster, Pa., assignor to RCA Corporation, New York, N.Y.

Filed Mar. 21, 1979, Ser. No. 22,617

Int. Cl.³ H01J 61/28, 61/30

U.S. Cl. 313-174

5 Claims



1. In a high pressure mercury discharge device including an envelope having a first internal bore including a pair of spaced apart regions, said envelope having lead-in conductors terminating in electrodes, said conductors being sealed in said envelope and extending through said regions, and having pools of mercury retained within said regions around said electrodes, the improvement comprising

at least one chamber having a reservoir of mercury therein, and a second integral bore communicating between said chamber and one of said regions, said chamber being substantially larger than second integral bore, said chamber being remote from said regions whereby said chamber can be selectively heated or cooled independently of said regions to vary the impedance of said device.

4,295,075


ARC DISCHARGE LAMP HAVING CERAMIC ARC TUBE
Edward A. Webb, Reading; John F. McKenna, Newburyport, both of Mass., and Frank B. Makar, Jr., Plaistow, N.H., assignors to GTE Products Corporation, Stamford, Conn.

Filed Dec. 14, 1979, Ser. No. 103,659

Int. Cl.³ H01J 17/16

U.S. Cl. 313-220

5 Claims



1. An arc discharge lamp comprising: a ceramic arc tube having an electrode at each end, each electrode being mounted on a support member; a ceramic cylinder at each end of the arc tube, the arc tube fitting inside one end of the ceramic cylinder and being sealed thereto; a ceramic adapter fitting into the other end of the ceramic cylinder and being sealed thereto; a lead-in wire extending into, and externally of, the ceramic adapter and being sealed thereto; the support member extending through the ceramic cylinder into the ceramic adapter and being sealed to the ceramic cylinder; and a spiral refractory-metal conductor disposed within the ceramic adapter and electrically connecting the support member to the lead-in wire.

5. The method of making an arc discharge lamp comprising the steps of: preparing an arc tube assembly including an arc tube, a ceramic cylinder sealed to the arc tube, a ceramic adapter sealed to the ceramic cylinder, and an electrode within the arc tube mounted on a support member extending into the adapter where it is connected to a lead-in wire extending externally of the adapter through a small clearance hole in a disc which is sealed to the adapter a short distance from the end thereof; disposing a glass bead around the lead-in wire at the end of the adapter; placing the arc tube assembly into a chamber and filling the chamber with a nonoxidizing gas to a predetermined pressure; heating the glass bead to its softening temperature; raising the pressure within the chamber; and heating

the glass bead to its sealing temperature to effect a hermetic seal between the lead-in wire and the disc.

4,295,076

ELECTRIC LAMP WITH CEMENTLESS ATTACHED BASE

Fritz Eckhardt, Bolheim, and Walter Schönherr, Giengen, both of Fed. Rep. of Germany, assignors to Patent-Treuhand-Gesellschaft für elektrische Glühlampen m.b.H., Munich, Fed. Rep. of Germany


Filed Mar. 20, 1979, Ser. No. 22,371

Claims priority, application Fed. Rep. of Germany, Apr. 4, 1978, 2814461

Int. Cl.³ H01K 1/46

U.S. Cl. 313-223

12 Claims



1. Electric lamp having a bulb (2), a glass press stem (4) projecting from the bulb, and lead wires (5) projecting from the stem in combination with a cylindrical lamp base shell (11) open at one end for insertion of the press stem and having internally projecting locating means (12) and a generally smooth interior surface in the region between the open end and said locating means; and means securing the bulb (2) to the lamp base shell (11) comprising:
a resilient disk-shaped element (7) formed with an upwardly bent notched or serrated edge (8) having serration points (8'), the points (8') of the notched or serrated edge being engaged against the generally smooth interior surface of the lamp base shell;
the disk-shaped element mechanically engaging the press stem essentially centrally of the disk-shaped element, said lead wires being soldered to base contacts (14, 214) on the base shell.

4,295,077

CIRCUMFERENTIALLY APERTURED CYLINDRICAL GRID FOR ELECTRON TUBE

Don R. Carter, Lancaster; Claude E. Doner, New Providence; Fred G. Hammersand, East Petersburg, and Joseph R. Tomcavage, Lancaster, all of Pa., assignors to RCA Corporation, New York, N.Y.

Filed Feb. 14, 1980, Ser. No. 121,530

Int. Cl.³ H01J 1/46, 21/10

U.S. Cl. 313-293


7 Claims

1. In a high power electron tube having a cathode, a cylindrical anode circumscribing said cathode and at least one tubular electrode disposed between said cathode and said anode, said electrode being formed from a cylindrical member closed at one end, said member having an outside diameter D, said member further having a plurality of first apertures extending therethrough, each of said first apertures having a length x and a width y, the improvement wherein said electrode comprises:

spurious oscillation control means including said first apertures, wherein said first apertures are circumferentially elongated, the length x, of said first apertures being greater than the width y, and wherein the length x of said

first apertures is not greater than 0.55 times the diameter D, of said one electrode.

6. In a high power electron tube having a cathode, an anode and at least one tubular electrode disposed between said cathode and said anode, said tubular electrode being closed at one



4,295,078 COLOR TELEVISION RECEIVER DEGAUSSING CIRCUIT


Paul C. Wilmarth, Noblesville, Ind., assignor to RCA Corporation, New York, N.Y.

Filed May 12, 1980, Ser. No. 148,088

Int. Cl.³ H04N 9/29

U.S. Cl. 315-8

13 Claims



1. A degaussing arrangement, comprising:
a source of alternating polarity voltage;
a power supply coupled to said source for developing a supply voltage from said alternating polarity voltage;
a deflection generator coupled to said power supply and being energized by said supply voltage to develop a deflection rate voltage;
a transformer including first and second windings, said deflection rate voltage being applied to said first winding;
a degaussing winding; and
a relay including a coil coupled to said transformer second winding and subject to energization in response to application of said deflection rate voltage to said first winding and including switching means actuated by said coil energization for coupling said degaussing winding to said source of alternating polarity voltage to permit the flow of degaussing current.

4,295,079


LAMP CIRCUIT WITH DISCONNECTED LAMP
DETECTING DEVICEKenichi Otsuka, Kodaira, and Yorio Hosokawa, Kawasaki, both
of Japan, assignors to Tokyo Shibaura Denki Kabushiki Kai-
sha, Kawasaki, Japan

Filed Mar. 25, 1980, Ser. No. 133,935

Claims priority, application Japan, Apr. 19, 1979, 54/47194
Int. Cl.³ H05B 37/03

U.S. Cl. 315-130

14 Claims



1. A lamp circuit comprising:
a constant-current type AC power source;
a plurality of isolation transformers connected in series with
the AC power source, each isolation transformer being
coupled to an electric lamp;
means for detecting the rise of the output voltage waveform
of the AC power source which exceeds a positive prede-
termined value which is sufficiently small with respect to
the maximum level of the voltage signal and which is
larger than a possible circuit induced noise level;
means for detecting the rise of the output current waveform
of the AC power source which exceeds a positive prede-
termined value which is sufficiently small with respect to
the maximum value of the current signal and which is
larger than a possible circuit induced noise level;
means for performing a calculation utilizing as an input the
output of said voltage detecting means and the output of
said current detecting means;
means for comparing the output of said calculating means
with a predetermined calculated value;
whereby the failure of at least one of said electric lamps
coupled to said plurality of isolation transformers is de-
tected.

4,295,080

SYSTEM FOR CONTROLLING ROTATIONAL
DIRECTION SWITCHOVER AND FOR VARIABLY
CONTROLLING ROTATIONAL SPEED OF MOTORMitsuo Fujita, and Koji Matsumura, both of Yokohama, Japan,
assignors to Victor Company of Japan, Ltd., Yokohama,
Japan

Filed Nov. 15, 1979, Ser. No. 94,437


Claims priority, application Japan, Nov. 15, 1978, 53-139850
Int. Cl.³ H02P 5/06

U.S. Cl. 318-257

5 Claims

1. A system for controlling a switchover of rotational direc-
tions and for variably controlling the rotational speed of a
motor, said system comprising:
a motor capable of rotating in both a normal direction and a
reverse direction;

means for switching over the rotational direction of said
motor;
means for supplying a driving voltage to said motor, said
motor rotating at a speed which depends upon the driving
voltage;
a single voltage varying means for continuously varying a
voltage; and
control signal generating means responsive to a variable
voltage from said voltage varying means for generating a
rotational control signal and a motor rotation stop signal
for controlling said driving voltage supplying means and
further for generating a rotational direction switchover



control signal for controlling said switchover means, the
voltage of said rotation control signal produced by said
control signal generating means decreasing as the variable
voltage approaches a predetermined value, said rotation
control signal reaching a minimum when the variable
voltage coincides with the predetermined value, and in-
creasing as the variable voltage goes beyond the predeter-
mined value, the motor rotation stop signal being gener-
ated when the variable voltage decreases and reaches
substantially the predetermined voltage, and the rotational
direction switchover control signal being produced by
said control signal generating means when the variable
voltage is substantially at said predetermined voltage.

4,295,081


LOAD ACTUATING SERVOMECHANISM WITH
RESONANCE EQUALIZATIONWilliam J. Bigley, Jr., Scotch Plains, and Vincent J. Rizzo,
Basking Ridge, both of N.J., assignors to Lockheed Electron-
ics Co., Inc., Plainfield, N.J.

Filed Jan. 6, 1978, Ser. No. 866,394

Int. Cl.³ H02P 5/00

U.S. Cl. 318-327

6 Claims



1. In combination in servomechanism apparatus for driving a
load via coupling means characterized by a mechanical reso-
nance at rates exceeding said resonance, summing means hav-
ing first and second additive input ports, a subtractive input
port and an output, a motor, a load, coupling means charac-
terized by a mechanical resonance connecting said motor and said
load, first network means connecting said output of said sum-
ming means and said motor, first negative feedback means

having an output connected to said subtractive input port of
said summing means and an input responsive to said motor,
monitoring means for monitoring the current consumed by
said motor, and positive feedback network means having an
input connected to said current monitoring means and an
output connected to said first additive input port of said sum-
ming means for increasing the energization applied to said
motor when said monitoring means senses an increasing cur-
rent consumed by said motor to thereby overcome said me-
chanical resonance of said coupling means.

4,295,082

PULSE WIDTH MODULATED SERVO CIRCUIT



Masato Moto, and Seigo Ito, both of Mobara, Japan, assignors
to Futaba Denshi Kogyo K.K., Mobara, Japan

Filed Mar. 6, 1980, Ser. No. 127,744

Claims priority, application Japan, Mar. 9, 1979, 54-26767
Int. Cl.³ G05B 11/28

U.S. Cl. 318-599

3 Claims



1. A motor servo circuit comprising:
a first pulse generator for generating pulses having a pulse
width adjusted by external signals and synchronized with
input pulses;
a pulse width comparator for comparing output pulses from
the first generator with the pulse width of the input pulses
and generating pulses having a pulse width corresponding
to a difference in the pulse width of both of these pulses
when the pulse widths are different;
a pulse width stretcher for stretching an output of the pulse
width comparator;
a second pulse generator for generating pulses having a
predetermined pulse width at intervals of the generation
of predetermined number of the output pulses of the pulse
width comparator;
an adder for performing an OR of the output pulses of the
pulse width stretcher and the second pulse generator; and
a motor driven by the output of the adder for adjusting the
output pulse width of the first pulse generator in accor-
dance with the rotation angle of the motor.

4,295,083

PULSED ENERGY STEPPING MOTOR POWER
CONTROL UNITAlbert C. Leenhouts, Harwinton, Conn., assignor to The Supe-
rior Electric Company, Bristol, Conn.

Filed Jul. 2, 1979, Ser. No. 54,311

Int. Cl.³ G05B 19/40

U.S. Cl. 318-696

26 Claims

1. A power control unit for supplying power to a winding of
a stepping motor, comprising a source of D.C. power, a capaci-
tor, step-switching means for connecting the motor winding
intermittently across the capacitor at a variable frequency that
determines the motor's speed, thereby causing the capacitor to
energize said winding as determined by the capacitor's charge
and voltage and the impedance of said winding at the step-
switching frequency, and means operable at a frequency inde-
pendent of the frequency of said step-switching means for
receiving pulses of energy up to a maximum amount of energy
in each pulse from said D.C. source and for supplying pulses to

said capacitor, said receiving and supplying means being re-
sponsive to the voltage of the capacitor to deliver to the capac-

4,295,084


CONTROL APPARATUS OF SYNCHRONOUS MOTOR
HAVING THYRISTOR CONVERTERHiroshi Nagase, Hitachi; Toshiaki Okuyama, Tokaimura;
Yuzuru Kubota, Hitachi, and Katsunori Suzuki, Takahagi, all
of Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Filed Jun. 5, 1979, Ser. No. 45,849

Claims priority, application Japan, Jun. 5, 1978, 53-66701
Int. Cl.³ H02P 5/40

U.S. Cl. 318-719

8 Claims



1. A control apparatus of a synchronous motor having arma-
ture windings and perpendicular field windings, and a rotating
shaft comprising: a frequency converter composed of thy-
ristors to convert the frequency of an alternating current to
supply the converted current to the armature windings of the
synchronous motor; means for detecting the actual speed of the
synchronous motor; means for detecting a position of the
armature relative to the field; means for generating a speed
instruction signal; means for rotationally exciting the field
windings with alternating current; means for controlling the
direction of the rotating magnetic field generated by the field
windings which are excited with the alternating current,
wherein the direction of the rotating magnetic field is con-
trolled in accordance with the rotating direction of the rotary
shaft of the synchronous motor as determined from the output
of said actual speed detecting means; and means for controlling
said frequency converter to regulate the amplitude of the
converted current fed to the armature windings in accordance
with a value proportional to a deviation between the speed
instruction signal and the output of said speed detecting means
and to regulate the frequency of the converted current in
accordance with a sum of the output frequency of said position

detecting means and the frequency of the alternating current to the field windings.

4,295,085

PHASE LOCK LOOP COMMUTATION POSITION CONTROL AND METHOD


David L. Lafuze, Endicott, N.Y., assignor to General Electric Company, Binghamton, N.Y.

Filed May 25, 1979, Ser. No. 42,432

Int. Cl.³ H02P 5/28, 7/36

U.S. Cl. 318—721

43 Claims



1. A drive system for a multiphase DC field motor having a rotor and a stator windings for each machine phase, said drive system comprising:

- means for sequentially supplying electric power to said stator windings in response to gating signals generated in accordance with the position of the rotor with respect to such stator windings;
- means for generating gating signals for sequentially supplying electric power to said stator windings in accordance with a plurality of timing signals equal to the number of machine phases;
- means for generating said timing signals as a function of the position of said rotor comprising;
- means for furnishing a plurality of position signals as a function of the position of said rotor with respect to a plurality of preselected stator positions, said position signals being lesser in number than the number of stator windings;
- means for generating error signals proportional to phase difference between preselected ones of said timing signals and said positions signals;
- means for producing clocking signals as a function of said error signals;
- means for supplying said clocking signal to said means for generating timing signals;
- means for deriving additional timing signals representative of intermediate rotor positions from said clocking signals.

4,295,086

METHOD AND APPARATUS FOR DYNAMIC BRAKING IN A MOTOR CONTROL SYSTEM

John H. Cutler, Roanoke; Paul M. Espelage, and Loren H. Walker, both of Salem, all of Va., assignors to General Electric Company, Salem, Va.

Filed Apr. 22, 1980, Ser. No. 142,696


Int. Cl.³ H02P 3/22

U.S. Cl. 318—759

24 Claims

1. In a control for an alternating current electric motor having a stator and a rotor spaced from the stator by a gap across which motor flux is produced in response to an electrical current of variable magnitude and frequency through windings associated with said stator, said control comprising:

- a d.c. source for providing a direct current of variable magnitude;
- a power converter for supplying a variable frequency electrical current to said motor;
- a d.c. link for connecting said d.c. source to said power converter whereby said direct current of variable magnitude is supplied from said source to said converter, said d.c. link including a resistive element and switch means for selectively including and excluding said resistive element into and from said d.c. link;
- means to sense prescribed motor operating parameters and provide signals proportional thereto;
- control means for controlling said power converter to thereby control the frequency of said electrical current



supplied to said motor as a function of motor operating parameters;

- means to provide a braking signal designating a dynamic braking action of said motor; and,
- means responsive to said braking signal to:
 - short circuit said d.c. source,
 - render ineffective normal control of said control means,
 - effect a braking control signal to said control means to thereby control the frequency of the electrical current supplied to said motor at a value determined by the value of a designated operating parameter, and
 - subsequently, operating said switch means to thereby include said resistive element in said d.c. link.

4,295,087

CHARGE INDICATOR CIRCUIT FOR A BATTERY CHARGING SYSTEM

Mitsuharu Morishita, and Yoshiyuki Iwaki, both of Himeji, Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan


Filed May 20, 1980, Ser. No. 151,734

Claims priority, application Japan, Jun. 12, 1979, 54/80275[U]

Int. Cl.³ H02J 7/14, 7/24

U.S. Cl. 322—99

1 Claim



1. In a battery charging system comprising an alternating current generator having a field winding and an output winding, full-wave rectifier means rectifying an alternating current output of said output winding and having first and second rectified output terminals and a grounded terminal, a battery

connected to said first rectified output terminal of said rectifier means to be charged therefrom, a resistor connected between said second rectified output terminal and said grounded terminal of said rectifier means, and voltage regulator means connected serially with said field winding for regulating an output voltage of said generator to a first predetermined level by conducting and cutting off a current flowing through said field winding of said generator, said field winding of said generator being supplied from an output from the second rectified output terminal of said rectifier means through said voltage regulator; a charge indicator circuit comprising a serial connection of a diode and a charge indicator lamp connected between said second rectified output terminal and said battery through a key switch, said diode having an anode and a cathode connected to said indicator lamp and said second rectified output terminal respectively, a detector and switching network including detecting means for detecting the output voltage of said second output terminal, and switching means which is connected between said anode of said diode and a ground terminal and is turned on by said detecting means to become conductive to energize said indicator lamp when said detecting means detects that the output voltage of said second output terminal becomes less than a second predetermined level which is lower than said predetermined level by a predetermined amount.

4,295,088

TEMPERATURE-SENSITIVE VOLTAGE DIVIDER

Max E. Malchow, Raritan Township, Somerset County, N.J., assignor to RCA Corporation, New York, N.Y.


Continuation-in-part of Ser. No. 968,443, Dec. 11, 1978. This

application Jan. 18, 1980, Ser. No. 113,372

Int. Cl.³ G05F 3/20

U.S. Cl. 323—313

6 Claims



1. A voltage divider comprising: a first terminal for receiving a reference voltage; a second terminal for receiving a voltage to be divided; a third terminal, between which and each of said first and second terminals respective divided voltages are available; a fourth terminal for receiving an operating voltage; a first transistor with a collector region, with a base region formed by a first diffusion into its collector region, followed by a second diffusion thereinto, with an emitter region formed by said second diffusion with a collector electrode contacting its collector region ohmically and connecting to said fourth terminal, with a base electrode contacting its base region ohmically, and with an emitter electrode contacting its emitter ohmically, one of its base and emitter electrodes connecting to said third terminal; a first resistor with a body formed by said first diffusion process in a body of semiconductive material formed by the same process as the collector region of said first transistor, with a first electrode contacting its body ohmically and connecting to said first terminal, and with a second electrode contacting its body ohmically at a different point than its first electrode does and connecting to the emitter electrode of said first transistor; and

a second resistor with a body formed by said first diffusion process in a body of semiconductor material formed by the same process as the collector region of said first transistor, and its body further formed by said second diffusion

process, with a first electrode contacting its body ohmically and connecting to said second terminal, and with a second electrode contacting its body ohmically at a different point than its first electrode does and connecting to the base electrode of said first transistor.

4,295,089

METHODS OF AND APPARATUS FOR GENERATING REFERENCE VOLTAGES


Michael Cooperman, Framingham, Mass., assignor to GTE Laboratories Incorporated, Waltham, Mass.

Filed Jun. 12, 1980, Ser. No. 158,672

Int. Cl.³ H02J 1/00; H03K 13/02

U.S. Cl. 323—351

32 Claims



1. In a system utilizing a reference voltage V, a method for providing a precise reference voltage xV comprising the steps of

- applying said reference voltage V to one side of a first capacitor while the opposite side of said first capacitor is coupled to a point of reference potential;
- with said opposite side of said first capacitor coupled to an input terminal of a comparator, decoupling said opposite side of said first capacitor from said point of reference potential, permitting said opposite side to "float";
- applying said point of reference potential to said one side of said first capacitor while said opposite side of said first capacitor remains coupled to said input terminal of said comparator; converting an output of said comparator to a nominal reference voltage xV; applying said nominal reference voltage xV to one side of a second capacitor while the opposite side of said second capacitor is coupled to said input terminal of said comparator; and
- coupling all sides of said capacitors to said point of reference potential; and cyclically repeating the foregoing steps, wherein the ratio of the value of said first capacitor to the value of said second capacitor is x.

4,295,090

ELECTRONIC SELECTOR SWITCH PARTICULARLY FOR USE IN RADIOSCONDES

Jorma Pankala, Helsinki, Finland, assignor to Vaisala Oy, Finland

Continuation of Ser. No. 950,546, Oct. 12, 1978. This application Dec. 4, 1979, Ser. No. 100,199

Claims priority, application Finland, Oct. 14, 1977, 773064


Int. Cl.³ G01R 27/26, 19/26

U.S. Cl. 324—60 CD

7 Claims

1. An electronic selector switch for telemetrical use in measuring a plurality of impedances to be measured, said selector switch comprising

an impedance measuring circuit;
a plurality of CMOS inverting amplifiers each having an input and an output, the output of each of said amplifiers being connected to a corresponding one of the impedances to be measured; and
a stepping circuit connected to the inputs of said amplifiers for connecting a selected one of said inverting amplifiers and the corresponding one of said impedances to be mea-



sured in said impedance measuring circuit and connecting the remaining inverting amplifiers and impedances to be measured to a point at ground potential whereby said impedance measuring circuit measures said one of said impedances to be measured free from the influence of said remaining impedances to be measured, said impedance measuring circuit producing an output frequency proportional to the impedance measured.

4,295,091

CIRCUIT FOR MEASURING LOW CAPACITANCES


Jorma Pankala, Helsinki, Finland, assignor to Vaisala Oy, Finland

Continuation of Ser. No. 950,547, Oct. 12, 1978. This application Dec. 4, 1979, Ser. No. 100,200

Int. Cl.³ G01R 27/26, 19/26

U.S. Cl. 324—60 CD

6 Claims



1. A circuit for measuring low capacitances with the elimination of the influence of stray capacitances, said circuit comprising

- an inverting amplifier having an input and an output;
- a capacitance to be measured connected between the input and the output of the inverting amplifier;
- a bistable circuit having an input connected to the output of said inverting amplifier, an output and an output frequency inversely proportional to the capacitance to be measured; and
- a resistive feedback connected from the output of the bistable circuit to the input of the inverting amplifier.

4,295,092

APPARATUS FOR AND METHOD OF DETECTING AND MEASURING CORROSION DAMAGE IN PIPE

Okiyoshi Okamura, Mitaka, Japan, assignor to Koa Oil Company, Limited, Ohte, Japan


Filed Nov. 3, 1978, Ser. No. 957,315

Claims priority, application Japan, Feb. 9, 1978, 53-13935; Feb. 9, 1978, 53-13936; Feb. 9, 1978, 53-13938

Int. Cl.³ G01R 27/26; G01B 5/28

U.S. Cl. 324—61 R

25 Claims



1. Apparatus for detecting corrosion damage to electrically conductive pipe, comprising:

- (a) a movable conductive ring within said pipe; and
- (b) means for moving said conductive ring longitudinally of said pipe;

said conductive ring and the wall of said pipe forming the electrodes of a varying electrical capacitance means such that the capacitance of said varying capacitance means changes whenever said movable conductive ring passes a corrosion portion of the inner pipe wall; and

(c) means electrically connected to said varying capacitance means for detecting the variations in its electrical capacitance.

4,295,093

SPECTRUM ANALYSERS

John D. Middleton, Welwyn, England, assignor to Marconi Instruments Limited, Chelmsford, England


Filed Nov. 16, 1979, Ser. No. 95,098

Claims priority, application United Kingdom, Nov. 17, 1978, 44927/78

Int. Cl.³ G01R 23/16

U.S. Cl. 324—77 B

4 Claims



1. A spectrum analyser including a monochrome cathode ray tube utilising a raster scanning pattern in which the lines of the raster are representative of different frequency components; a liquid crystal colour switch positioned immediately in front of the screen of the cathode ray tube and containing a thin film of liquid crystal material and two coloured polarised sheets, and selection means to selectively controlling the optical properties of the film so as to produce a display consisting of at least the two colours of said polarised sheets, and means for synchronising the operation of said selection means with the raster scanning pattern of the cathode ray tube.

4,295,094

HIGH VOLTAGE HIGH FREQUENCY ANALOG SIGNAL MEASURING SYSTEM


Victor F. Wilreker, and William H. Smith, both of Greensburg, Pa., assignors to Westinghouse Electric Corp., Pittsburgh, Pa.

Filed Apr. 30, 1979, Ser. No. 34,308

Int. Cl.³ G01R 19/26, 15/04

U.S. Cl. 324—96

11 Claims



1. In a system for deriving a representation as a function of time of high frequency high voltage transients appearing on a high voltage power line, the combination of:

- voltage divider means coupled to said power line at a point of measurement for deriving at low voltage at a first location a first analog signal representing said transients;
- a first metallic enclosure surrounding said first location and connected to ground potential;
- frequency modulation means disposed at a second location in close proximity to said first location and responsive to said first analog signal for frequency modulating said first analog signal and for converting the resulting frequency-encoded electrical signal into a frequency-encoded optical signal;
- a second metallic enclosure at ground potential surrounding said frequency modulating means;
- fiber optic means for transmitting said frequency-encoded optical signal out of said second enclosure onto a remote location; and
- means at said remote location for converting said frequency-encoded optical signal into a second analog signal representative of said first analog signal.

4,295,095

APPARATUS AND METHOD FOR DETECTING THE LOCATION OF METALLIC OBJECTS HAVING ALTERNATING CURRENT PASSING THERE THROUGH

Richard C. Thomas, Cramlington; Stewart M. Pegler, Wideopen, and Paul B. Cordes, North Shields, all of England, assignors to British Gas Corporation, London, England


Filed Mar. 20, 1979, Ser. No. 22,100

Claims priority, application United Kingdom, Jan. 29, 1979, 03083/79

Int. Cl.³ G01V 3/11, 3/165

U.S. Cl. 324—326

16 Claims



1. Detector means for locating an elongated metallic object through which an alternating electrical current is passing,

thereby producing an alternating magnetic field therearound, said detector means including

first, second and third magnetic field strength measuring means, said first and second magnetic field strength measuring means being positioned in a common plane which is perpendicular to a plane passing through the third magnetic field strength measuring means and said first and second magnetic field strength measuring means being equidistant from said plane passing through said third magnetic field strength measuring means and on opposite sides thereof,

first comparator means electrically connected to said first and second magnetic field strength measuring means to determine when the magnitudes of the field strengths measured thereby are equal,

second comparator means electrically connected to said first and second magnetic field strength measuring means to determine the larger field strength measurement therebetween,

third comparator means electrically connected to said third magnetic field strength measuring means and said second comparator means to determine when the field strength measurement from said third magnetic field measuring means is greater than the larger of the field strength measurements between the first and second magnetic field strength measuring means, and

indicator means electrically connected to said first comparator means and said third comparator means to indicate when the field strengths measured by the first and second magnetic field strength measuring means are equal and when the field strength of the third magnetic field strength measuring means is greater than the larger of the field strengths measured by either of said first and second magnetic field strength measuring means, said indicator means thus indicating when the detector means has been positioned such that the plane passing through said third magnetic field strength measuring means is coincident with a plane in which the elongated metallic object is located.

4,295,096

ELECTRODE PROSPECTING METHOD PROVIDING CALCULABLE ELECTROMAGNETIC COUPLING FOR THE INDIRECT DETECTION OF HYDROCARBON RESERVOIRS


Ben K. Sternberg; Dale E. Miller, and Dhari S. Bahjat, all of Ponca City, Okla., assignors to Conoco, Inc., Ponca City, Okla.

Filed Dec. 20, 1978, Ser. No. 971,177

Int. Cl.³ G01V 3/06

U.S. Cl. 324—357

11 Claims



9. A method of electrical hydrocarbon prospecting to investigate a subsurface polarizable stratum which is indicative of the presence of a hydrocarbon deposit lower than the stratum wherein a first set of spaced electrode means is placed in the surface of the ground in electrical communication with said stratum, a second set of spaced electrode means is placed in the

surface of the ground in electrical communication with said stratum, with generating means coupled through second conductor means to said second set of electrode means, and a voltage measuring means coupled through a first conductor means to said first set of spaced electrode means, an improvement comprising:

- maintaining a calculable electromagnetic coupling between said first and second conductor means;
- measuring the current through said second conductor means to said second set of spaced electrical means; and
- recording in time synchronism voltage that is measured through said first conductor means from said first set of spaced electrical means by said voltage measuring means, and said measured current, whereby an anomaly indication of a hydrocarbon deposit can be ascertained by processing from the measured current and voltage and said calculable electro-magnetic coupling.

4,295,097

BATTERY CAPACITY MEASURING METHOD AND APPARATUS


Arthur H. Thompson, 14 Princeton Dr., New Providence, N.J. 07974, and Ricardo H. Ballester, Jamaica Estates, N.Y., assignors to Arthur H. Thompson, New Providence, N.J.

Filed May 7, 1979, Ser. No. 36,412

Int. Cl.³ H02J 7/00

U.S. Cl. 324-429

16 Claims




1. A device for automatically testing an electrochemical cell, comprising:

- means for selectively charging and discharging current to and from said cell in predetermined discrete steps responsive to control circuitry means;
- means responsive to the current flowing from said cell, the output of which is capable of being interfaced with control circuitry means;
- means responsive to the voltage across said cell, the output of which is capable of interfacing with control circuitry means;
- means for measuring the current flowing through said means of paragraph (b) responsive to the current flowing from said cell, which is also capable of integrating said current and is further capable of being interfaced with control circuitry means;
- control circuitry means coupled to said means of paragraph (a), whereby said control circuitry means selectively controls the state of charge or discharge of current to and from said cell in response to said means of paragraph (c).

4,295,098 DIGITALLY ADJUSTABLE PHASE SHIFTING CIRCUIT

Albert T. Crowley, Gloucester Township, Camden County, N.J., assignor to RCA Corporation, New York, N.Y.
Filed Dec. 19, 1979, Ser. No. 105,122
Int. Cl.³ H03L 7/18; H03K 13/02, 4/02, 3/017
U.S. Cl. 328-24 6 Claims



- Apparatus for producing an alternating signal with a controllable phase shift, comprising in combination: means producing a periodic signal having a given period; divider means responsive to said periodic signal for producing a first digital signal changing as a function of said given period and manifested as a plurality of M bits; means for storing a value indicative of the phase of said alternating signal and for producing, in accordance with said value, a second digital signal manifested as a plurality of N bits comprising M higher order bits and N-M lower order bits and having a control terminal receptive of a control signal for changing said value, where, $N \geq M$; means responsive to said first digital signal and second digital signal for adding ones of said M bits of said first digital signal with corresponding ones of said higher order bits of said N bits to produce a most significant bit (MSB) and lower order bits; means responsive to said added bits and lower order ones of said N bits for producing an analog alternating signal corresponding to the value of said added and lower order bits; and means coupled to said means for storing a value for producing a control signal to change said stored value to thereby change the phase of said alternating signal.

4,295,099

PEAK DETECTOR


Thomas E. Evans, Parker, Colo., assignor to Honeywell Inc., Minneapolis, Minn.

Filed Sep. 5, 1979, Ser. No. 72,572

Int. Cl.³ H03K 5/153

U.S. Cl. 328-151

8 Claims



1. A peak detector circuit comprising:

input signal terminal means for confection to a source of analog signals, a first and second sample holding means, means connected to said input terminal means for applying successive samples of said analog signals to said first and second holding means alternately, comparator means connected to compare the magnitude of said signals stored in said holding means to produce a phase change signal on the occurrence of a peak value of said analog signal, and means connected to be responsive to said phase change signal from said comparator means to produce an output signal indicative of the occurrence of said peak value.

4,295,100

MICROPHONE AMPLIFIER, IN PARTICULAR FOR TELEPHONE SYSTEMS

Horst Kraemer, Munich, Fed. Rep. of Germany, assignor to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany


Filed Nov. 1, 1979, Ser. No. 90,468

Claims priority, application Fed. Rep. of Germany, Nov. 23, 1978, 2850792

Int. Cl.³ H03F 3/45, 3/68

U.S. Cl. 330-257

8 Claims



- In a microphone amplifier of the type providing common terminals on which an output signal is superimposed on its feed current, in which an input stage comprises an emitter resistance stabilized differential amplifier, an output stage comprising a two-transistor Darlington amplifier operating as a controlled voltage source, a negative feedback circuit connects the output and input stages, and a reference voltage source is connected to stabilize the operating point of the differential amplifier, the improvement therein comprising: coupling means connecting the differential amplifier to the Darlington amplifier, including a symmetrically connected transistor coupling stage and a two-stage intermediate amplifier; and current mirror circuits connected to said coupling stage and to the input stage for providing current symmetry therein.

4,295,101

CLASS AB PUSH-PULL QUASI-LINEAR AMPLIFIERS

Arthur J. Leidich, Raritan Township, Hunterdon County, N.J., assignor to RCA Corporation, New York, N.Y.

Filed Dec. 10, 1979, Ser. No. 102,131

Int. Cl.³ H03F 3/26


U.S. Cl. 330-262

13 Claims

- A Class AB push-pull quasi-linear amplifier comprising: input and output signal terminals; first and second supply terminals for receiving an energizing potential therebetween; a first plurality, N in number, of transistors of a first conductivity type in a first sequential arrangement, each transistor having a respective base electrode, each having respective emitter and collector electrodes defining the ends of a respective principal current conduction path the

conductivity of which is controlled by current applied to the base electrode of that transistor, and each exhibiting a current gain between its base electrode and one of its emitter and collector electrodes appreciably greater than unity;

- a second plurality, N in number, of transistors of said first conductivity type in a second sequential arrangement, each transistor having a respective base electrode, each having respective emitter and collector electrodes defining the ends of a respective principal current conduction path the conductivity of which is controlled by current applied to the base electrode of that transistor, and each exhibiting a current gain between its base electrode and one of its emitter and collector electrodes substantially corresponding to said current gain exhibited by a respective one of the transistors in said first plurality, with which it is paired;
- means for connecting said first plurality of transistors, in order of said first sequential arrangement, in a first direct-coupled cascade amplifier with a current gain that is substantially equal to the product of the current gains of said first plurality of transistors, including means connecting said input signal terminal to the base electrode of the first transistor in said first sequential arrangement including means connecting the principal conduction path of each transistor except the last in said first sequential arrangement to control the current flowing to the base electrode of the following transistor in said first sequential arrangement, and including



- a connection of the emitter electrode of the last transistor in said first sequential arrangement to said first supply terminal and
- a connection of its collector electrode to said output signal terminal;
- means for connecting said second plurality of transistors, in order of said second sequential arrangement, in a second direct-coupled cascade amplifier with a current gain that is substantially equal to the product of the current gains of said second plurality of transistors and that is opposite in sense to that of said first direct-coupled cascade amplifier, including means connecting said input signal terminal to the base electrode of the first transistor in said second sequential arrangement, including means connecting the principal conduction path of each transistor except the last in said second sequential arrangement to control the current flowing to the base electrode of the following transistor in said second sequential arrangement, and including
- a connection of the emitter electrode of the last transistor in said second sequential arrangement to said output signal terminal and

a connection of its collector electrode to said second supply terminal; and
 respective constant current generator means connected to the base electrode of each transistor in said first and second sequential arrangements which has connected to it the collector electrode of a preceding current-inverting transistor.

4,295,102

SURFACE ACOUSTIC WAVE SENSOR SENSING CIRCUITS



Gary D. Schmidt; Jerry L. Norris, and Donald F. Weirauch, all of Dallas, Tex., assignors to Texas Instruments Incorporated, Dallas, Tex.

Filed Sep. 28, 1979, Ser. No. 80,366

Int. Cl.³ G01B 7/16; H03B 5/18; H03H 9/25

U.S. Cl. 331—65

8 Claims




5. A strain sensing system comprising:
 a first substrate having a surface acoustic wave array located thereon, and an amplifier coupled to said array to form a first oscillator circuit;
 second substrate having a surface acoustic wave array located thereon, and an amplifier coupled to said array to form a second oscillator circuit;
 means for physically locating said first substrate and said second substrate in proximity to each other such that a capacitive coupling is created between said SAW arrays for mixing the frequencies generated by said oscillator circuits, and for changing said capacitive coupling when either of said substrates is recipient of strain which alters the proximity of said SAW arrays;
 circuit means for development of frequency difference of said oscillator circuits, in at least one of said oscillator circuits;
 filter means for passage of said frequency difference only, coupled to said circuit means for development of frequency difference.

4,295,103
METAL VAPOR LASER
 Ariold Ljudmirsky, 81/26 Ramot, Jerusalem, Israel
 Filed Mar. 23, 1978, Ser. No. 889,396
 Int. Cl.³ H01S 3/097

U.S. Cl. 331—94.5 PE

33 Claims



1. A method of stimulating the emission of light in a laser, comprising the steps of:
 disposing a plurality of solid electrically conductive bodies, each consisting at least in part of a vaporizable substance whose vapors are excitable to a radiation-emissive level, at spaced-apart sites in a substantially closed vessel of dielectric material;
 simultaneously generating an electric current pulse by electromagnetic induction through the wall of said vessel in each of said bodies for vaporizing at least part of said substance; and
 exciting the resulting vapors to the radiation-emissive level by subjecting said vapors to a high-intensity electric field.


4,295,104
LASER HAVING SIMULTANEOUS ULTRAVIOLET AND VISIBLE WAVELENGTHS
 Ralph L. Burnham, Oxon Hill, Md., assignor to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Nov. 14, 1979, Ser. No. 94,125

Int. Cl.³ H01S 3/05

U.S. Cl. 331—94.5 C

14 Claims



1. A laser system operative in the visible region of the spectrum which comprises:
 a first and second laser having a common optical cavity;
 said first laser including a medium which possesses a high-gain UV transition and a low-gain visible transition disposed within a resonant second optical cavity;
 said second laser including a high gain medium which is stimulated by UV radiation; and
 said first laser further including means for extracting and directing the ultraviolet radiation from said second optical cavity into the high gain medium of said second laser;
 whereby the stimulated emission of said second laser is amplified by the low-gain visible transition of said first laser to produce laser emission in the visible region of the spectrum in the common optical cavity.

4,295,105
SWITCHED-CAPACITOR MODULATOR
 John A. C. Bingham, Palo Alto, Calif., assignor to Racal-Vadic, Inc., Sunnyvale, Calif.

Filed Feb. 7, 1980, Ser. No. 119,374


Int. Cl.³ H03C 1/02; H03K 7/00

U.S. Cl. 332—9 R

8 Claims

1. A switched-capacitor modulator for modulating a carrier signal with a modulating signal to develop a modulated signal, said modulator comprising:
 switching means including, a first input terminal for applica-

tion of the modulating signal, a second input terminal for application of a plurality of switching signals, an output terminal for providing a sampled modulating signal, a primary capacitive means having first and second plates, and a plurality of binary switches responsive to the switching signals for connecting said first and second plates to said input and output terminals;



logic means responsive to the carrier signal and a clock signal having a frequency of at least four times the frequency of said carrier signal and operative to generate said switching signals; and
 integrator means responsive to said sampled modulating signal and operative to provide the modulated signal.


4,295,106
METHOD AND MEANS FOR INTRODUCING ADDITIONAL ASYMMETRY INTO AUDIO WAVES
 Leonard Kahn, 137 E. 36 St., New York, N.Y. 10016

Filed Oct. 4, 1979, Ser. No. 81,631

Int. Cl.³ H03C 1/00; H03G 11/00; H03K 5/153

U.S. Cl. 332—37 R

16 Claims



1. Audio signal modulation equipment comprising an audio signal source, carrier wave generation means, and means for modulating carrier waves with the audio signal, the improvement which comprises:
 means for converting an audio signal, having little or no asymmetry, to a wave having substantial asymmetry through which an audio signal from said audio signal source is passed and fed to the carrier wave modulating means,
 said converting means, comprising a peak detector which detects the signal having the proper polarity to cause positive going envelope modulation, and,
 means controlled by the peak detector for providing greater transmission for portions of the audio wave that produce positive going envelope modulation than portions of the audio wave that produce negative going modulation during periods when the peak detector provides an output above a predetermined level.
 9. A detector for detecting the peak voltage of a wave comprising:
 (a) a first rectification means with its input terminal coupled to the signal having the proper polarity to cause positive going envelope modulation,
 (b) one or more additional rectification means,
 (c) one or more time delay means through which at least a sample of said proper polarity signal is passed and if a plural-


ity of delay means are provided said delay means connected so as to provide a total delay equal to the sum of the delays of the individual delay means,
 (d) means for connecting the input terminals of the one or more rectification means (b) to the one or more output terminals of delay means (c),
 (e) combining means connected to the output terminals of the rectification means (a) and rectification means (b), said combining means incorporating storage means having a capacity sufficient to maintain the level of the detected wave within a predetermined droop tolerance for a period of time equal to approximately T/D+T where T is the period of one complete alternation of the lowest frequency component of substantial level expected in the wave being detected and D is the number of time delay means (c).
 11. A device for converting a substantially symmetrical wave into one substantially asymmetrical comprising:
 means for splitting said wave into its positive and negative polarity segments,
 two separate paths at least for some portion of the path to an associated transmitter's modulator for passing the two segments, said separate paths having different transmission characteristics both of which are essentially linear, but the path for the segment that causes positive going modulation being of higher transmission gain.

4,295,107
IMPEDANCE TRANSFORMATION NETWORK
 Stewart M. Perlow, Marlboro, N.J., assignor to RCA Corporation, New York, N.Y.

Filed Jan. 31, 1980, Ser. No. 117,238

Int. Cl.³ H03H 7/38, 7/42

12 Claims



1. Apparatus comprising:
 first circuit for processing RF signals in a predetermined frequency range having a signal connection point and a signal reference point for signals developed at said signal connection point of said first circuit;
 a second circuit for processing RF signals in said predetermined frequency range having first and second signal connection points and a signal reference point for signals developed at said first and second signal connection points of said second circuit;
 a trifilar wire configuration having three conductors substantially equally spaced with respect to one another throughout a predetermined length of said wire configuration between first and second ends, said predetermined length being substantially shorter than the wavelength of the highest frequency signal in said predetermined range, each of said conductors having first and second ends respectively connected to points respectively located at said first and second ends of said predetermined length, said first and second ends of said first conductor being connected to said signal connection and signal reference points, respectively, of said first circuit, said first end of said third conductor being connected to said first signal connection point of said second circuit, said second end of said second conductor being connected to said second signal connection point of said second circuit, and said

first end of said second conductor and said second end of said third conductor being connected to said signal reference point of said second circuit, there being no DC signal paths connected directly between said signal connection point of said first circuit and each of said first and second signal connection points of said second circuit; and a ferrite member having a generally cylindrical shape with two apertures formed through it through which said trifilar wire configuration is wound, said apertures having lengths such that the substantial portion of said predetermined length is surrounded by ferrite material.

4,295,108

FILTER CIRCUIT EMPLOYING SURFACE ACOUSTIC WAVE DEVICE

Hideharu Ieki, Nagaokakyo, Japan, assignor to Murata Manufacturing Co., Ltd., Japan


Filed Sep. 17, 1980, Ser. No. 188,226

Claims priority, application Japan, Sep. 25, 1979, 54/123343

Int. Cl.³ H03H 9/64, 9/60

U.S. Cl. 333—193

8 Claims



1. A filter circuit located between an input and an output terminal, comprising:
 - a surface acoustic wave device having an input transducer and an output transducer acoustically coupled to each other and electrically connected to said input and output terminals, respectively;
 - a tuning coil connected in series between one said transducer and said terminal which is electrically connected thereto; and
 - a piezoelectric resonator connected in parallel with said tuning coil.

4,295,109

RECTANGULAR WAVE GUIDE ELBOW BENT ACROSS THE NARROW SIDE WITH CAPACITIVE LOADING

Eberhard Schuegraf, Munich, Fed. Rep. of Germany, assignor to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany


Filed Dec. 10, 1979, Ser. No. 101,577

Claims priority, application Fed. Rep. of Germany, Dec. 29, 1978, 2856733

Int. Cl.³ H01P 1/02

U.S. Cl. 333—249

3 Claims



1. A rectangular wave guide H-elbow bent across the narrow side of the wave guide and having an external corner symmetrically flattened with a conductive flattening plane, characterized in that the value x_H/a of the corner flattening is selected so as to be greater than 0.73, whereby x_H is the distance from the junction of the flattening plane with the narrow side (k) to the apex of the outer bend edge of a non-flattened

elbow and "a" is the length of the broad side of the wave guide; and electrically conductive means (3) functioning as a capacitive load are provided in the wave guide elbow in the area of the geometrical median (w) of the bend, in that a conductive cross-bar (3) which extends between the flattening plane (2) to the inner bend edge (K) is provided as the capacitive load electrically conductive means.

4,295,110

ADJUSTING DEVICE FOR COLOR CATHODE RAY TUBE

Tatsuo Uesaka; Hiroshi Sugahara, both of Amagasaki, and Takeo Fujimura, Nagaokakyo, all of Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan


Filed Jun. 13, 1979, Ser. No. 47,993

Claims priority, application Japan, Jun. 24, 1978, 53/76644

Int. Cl.³ H01F 1/00

U.S. Cl. 335—212

3 Claims



1. An adjusting device for a color cathode ray tube comprising:
 - a neck portion of a color cathode ray tube;
 - electron gun means disposed within said neck portion;
 - a magnetic member fixedly secured to an external surface of said neck portion and magnetized into a predetermined magnetization pattern;
 - wherein said predetermined magnetization pattern is effective for correcting the static convergence and color purity of electron beams emitted from said electron gun means; wherein said magnetic member is magnetized after being fixedly secured to said external surface of said neck portion; and wherein said magnetic member is formed of a magnetically anisotropic sheet-shaped magnet material having a magnetic easy axis perpendicular to said external surface of said neck portion.

4,295,111

LOW TEMPERATURE LATCHING SOLENOID


Robert A. Frosch, Administrator of the National Aeronautics and Space Administration, with respect to an invention of, and William S. Wang, Marina del Rey, Calif.

Filed Nov. 29, 1979, Ser. No. 98,568

Int. Cl.³ H01F 3/00, 7/08

U.S. Cl. 335—256

12 Claims



1. Magnetically operable apparatus capable of operating in cryogenic environment comprising:
 - (a) plunger means, including magnetically responsive mate-

- rial, movable generally along a path between a first position and a second position;
- (b) coil means generally circumscribing at least a portion of said path and positioned so that the center of said magnetically responsive material of said plunger means moves generally toward the center of said coil means as said plunger means moves toward said second position;
- (c) a first coil segment, as part of said coil means, constructed of electrically conducting material; and
- (d) a second coil segment, as part of said coil means, electrically connected in sequence with said first coil segment, and constructed of electrically conducting material with a temperature coefficient of resistivity lower than that of said first coil segment and
- (e) the total resistance of the coil means remaining nonzero for all values of the temperature of the environment within which the apparatus is to be operated.

4,295,112

RESIDUAL CURRENT TRANSFORMER

Yoshito Yamada; Hiroshi Okumura, and Shoji Murakami, all of Sagami, Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan


Filed Aug. 30, 1979, Ser. No. 71,360

Claims priority, application Japan, Aug. 30, 1978, 53-105930; Dec. 15, 1978, 53-155454

Int. Cl.³ H01F 15/04, 40/06

U.S. Cl. 336—84 M

8 Claims



1. A residual current transformer, comprising:
 - an annular core of magnetic material, said core including a continuous magnetic path within said core, said core including at least one portion wherein the longitudinal cross-section of said core is reduced with respect to the longitudinal cross-section of the remainder of said core;
 - a first annular shield of magnetic material positioned concentric with respect to said core and located in parallel with a first side thereof;
 - a second annular shield of magnetic material positioned concentric with respect to said core and located in parallel with a second side thereof; and
 - a secondary coil wound about the exterior of said annular core, said secondary coil being located between said annular core and said first and second annular shields.

4,295,113

SHEET-WOUND TRANSFORMER OR REACTOR

Anders Björklund; Erik Persson, and Lars-Göran Virsberg, all of Vesteras, Sweden, assignors to Asea Aktiebolag, Vesteras, Sweden

Filed Aug. 11, 1980, Ser. No. 176,911

Claims priority, application Sweden, Aug. 14, 1979, 7906765


Int. Cl.³ H01F 15/04

U.S. Cl. 336—84 M

10 Claims

1. A transformer or reactor comprising:
 - a core consisting of magnetic material and having at least one leg (1) and one yoke (2);
 - at least one winding (3) arranged substantially concentrically around said core leg, said winding being built up from a foil (4), spirally-wound in several turns, of a mate-

rial having a high electrical conductivity and an insulating film (5) arranged between said turns; a magnetic flux-controlling spirally-wound tape (6) of a highly permeable ferro-magnetic material being arranged axially outside each end of the winding and coaxially



therewith, the magnetic material in the tape being divided in such a manner that the ability of the tape to carry electric current in the longitudinal direction of the tape is considerably reduced; and connections (7) being arranged between the tape and the winding at the beginning and end of the tape.

4,295,114

THERMO-SWITCH

Walter Pohl, Milan, Italy, assignor to Eaton Corporation, Cleveland, Ohio


Filed Jan. 28, 1980, Ser. No. 115,977

Claims priority, application Italy, Jan. 29, 1979, 19684 A/79

Int. Cl.³ H01H 61/01

U.S. Cl. 337—3

6 Claims



1. An overload protective thermostat comprising:
 - (a) housing means;
 - (b) switch means disposed within said housing means, said switch means including a switch blade member mounted on a support for movement between positions making and breaking first and second spaced sets of circuit contacts;
 - (c) heat responsive service actuator means disposed within said housing means, said actuator means being operative in response to experiencing a predetermined service temperature to cause movement of said switch member for breaking said first set of electrical contacts;
 - (d) collapsible support means maintaining said switch member in a position such that said first and second sets of contacts are normally closed; and,
 - (e) means biasing said switch member against said support means in a direction tending to open said second set of contacts wherein upon said thermostat experiencing temperatures above a second predetermined level greater than said service temperature, said support means collapses permitting said bias means to open said second set of contacts irrespective of the condition of said first set of contacts;
 - (f) a first electrical terminal, operatively connected in series circuit arrangement with said first set of contacts and adapted for connection thereto externally of said housing means; and
 - (g) a second electrical terminal operatively connected in

series circuit arrangement with said second set of contacts and adapted for connections thereto externally of said housing means.

4,295,115

SEMICONDUCTOR ABSOLUTE PRESSURE TRANSDUCER ASSEMBLY AND METHOD


Minoru Takahashi, Katsuta; Takahiko Tanigami, Mito; Kaoru Uchiyama, Katsuta; Hitoshi Minorikawa, Mito; Motohisa Nishihara; Kanji Kawakami, both of Katsuta; Seiko Suzuki, Hitachi; Hiroaki Hachino, Hitachi, and Yutaka Misawa, Katsuta, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan
Filed Apr. 4, 1979, Ser. No. 27,157

Claims priority, application Japan, Apr. 5, 1978, 53-39191

Int. Cl.³ G01L 1/22

U.S. Cl. 338—4

13 Claims



1. A semiconductor pressure transducer assembly comprising:
 - a silicon diaphragm assembly, on which a pressure sensitive diaphragm is formed;
 - piezoresistive elements diffused on the pressure sensitive diaphragm of said silicon diaphragm assembly, the resistance value of the piezoresistive elements varying depending on the strain appearing in the diaphragm;
 - conducting paths diffused on said silicon diaphragm assembly for electrical connection of said piezoresistive elements;
 - passivating layer covering the surface of said silicon diaphragm assembly, on which surface said piezoresistive elements and said conducting paths are diffused; and
 - a covering member of insulating material mounted on the surface of said silicon diaphragm assembly, characterized in that a layer of conductor is disposed between said passivating layer and said covering member, and said conductor layer and said covering member are bonded by Anodic Bonding method.

4,295,116

PRESSURE TRANSDUCER


Vance D. Studlien, Stow, Mass., assignor to Bofors America, Inc., Edison, N.J.

Filed Dec. 5, 1979, Ser. No. 100,384

Int. Cl.³ G01L 1/22

U.S. Cl. 338—4

16 Claims



1. A fluid-pressure transducer comprising a substantially rigid single-piece body having a recess therein from an open end thereof which is closed at its bottom by a substantially flat uniform-thickness integral diaphragm, the outer side of said

diaphragm being substantially coplanar with the end of a relatively thick and substantially rigid annular rim of said body about said diaphragm, said recess having pressure-fitting means near said open end for coupling said recess and the inner side of said diaphragm with a site of fluid pressures which are to be sensed, and said coplanar outer side of said diaphragm and end of said annular rim being substantially unobstructed by any portions of said body extending beyond the plane thereof, and a substantially flat foil electrical network including strain gages and relatively broad-area contact tabs and conductive paths bonded in insulated overlying relation to said coplanar outer side of said diaphragm and said end of said annular rim, said gages being disposed in overlying relation to said diaphragm and said contact tabs being disposed in overlying relation to said end of said annular rim, and means making external electrical circuit connections with said gages through said contact tabs.

4,295,117

PRESSURE SENSOR ASSEMBLY


Donald E. Lake, and John M. Hart, Jr., both of Kokomo, Ind., assignors to General Motors Corporation, Detroit, Mich.

Filed Sep. 11, 1980, Ser. No. 186,238

Int. Cl.³ G01L 1/22

U.S. Cl. 338—4

3 Claims



1. In a pressure sensor assembly, means for mounting a pressure sensor element in a housing to isolate the sensor element from stresses occurring in the housing, comprising
 - a hollow molded resin housing having an external opening, a flat surface surrounding the opening,
 - a glass base secured to the flat surface and covering the opening, the glass base and the housing having different thermal coefficients of expansion and being joined by a layer of soft resilient adhesive which inhibits stress transfer from the housing to the base, the glass base comprising a plate having an integral raised pedestal extending into the said opening whereby any stresses in the base are minimized in the pedestal due to the added rigidity in the region of the pedestal,
 - a glass support in the housing secured to the pedestal by a soft epoxy adhesive which inhibits the transfer of stress from the pedestal to the support, and
 - a silicon pressure sensor chip rigidly bonded to the glass support at a region spaced from the pedestal, the glass base and the glass support each having approximately the same thermal coefficient of expansion as the silicon chip,
 whereby the cumulative effect of the several stress minimizing features is to isolate the silicon chip from thermal and other stresses induced in the housing or other parts of the assembly.

4,295,118

LATCHING RELAY USING HALL EFFECT DEVICE


John A. Herr, Garwood, and Bruce R. Rogan, Somerville, both of N.J., assignors to The Singer Company, Stamford, Conn.

Filed May 21, 1980, Ser. No. 152,210

Int. Cl.³ H01L 43/04

U.S. Cl. 338—32 H

6 Claims



1. A latching switch comprising:
 - a Hall effect digital switching device including a Hall sensor for generating an output voltage proportional to magnet field strength and means responsive to the output voltage generated by said Hall sensor for providing a switching function;
 - a reversible bias magnet supported with a pole thereof contiguous said Hall sensor for generating at one polarity, a first output voltage providing a switching function and at a reverse polarity a second output voltage providing a converse switching function; and,
 - means for reversing the polarity of said reversible bias magnet.

4,295,119

ROTARY VARIABLE RESISTOR

Masao Kasashima, and Yoshizo Kubo, both of Miyagi, Japan, assignors to Alps Electric Co., Ltd., Tokyo, Japan


Filed Mar. 10, 1980, Ser. No. 128,941

Claims priority, application Japan, Mar. 12, 1979, 54-31478[U]

Int. Cl.³ H01C 10/32

U.S. Cl. 338—162

3 Claims



1. A rotary variable resistor having a substrate carrying a resistance element connected to terminal portions; a cover member fitting over said substrate and having an upper wall extending generally parallel thereto; and a rotor formed of a synthetic resin and carrying a conductive wiper adapted to slide across said resistance element during rotation of said rotor; said rotor having an upper shoulder adapted to bear against the inner surface of the upper wall of said cover, an elastic flange extending outwardly from the lower portion of said rotor and means including a plurality of legs extending downwardly from said flange and riding on said substrate for elastically deforming said flange upwardly to urge said upper shoulder into continuous engagement with the inner surface of the upper wall of said cover.

4,295,120

PATTERN DATA PROCESSING METHOD AND APPARATUS TO PRACTICE SUCH METHOD


Hajime Yoshida, Tokyo, Japan, assignor to Hajime Industries Ltd., Tokyo, Japan

Filed Aug. 27, 1979, Ser. No. 69,911

Claims priority, application Japan, Aug. 28, 1978, 53/104554 Int. Cl.³ G06K 9/46

U.S. Cl. 340—146.3 MA

2 Claims



1. Apparatus for processing patent data comprising:
 - a photo-electric conversion sensor including a screen on which a pattern to be recognized is applied said screen comprising a plurality of picture elements, said picture elements being divided into a plurality of picture element groups, each of said picture element groups comprising at least two adjacent horizontal and vertical picture elements;
 - comparator means for receiving an output signal from said photo-electric conversion sensor and producing white and black two value data signals;
 - means for delaying said white and black two value data signals; a clock signal generator means for producing a clock signal and applying said clock signal to said delay means so that said delay means delays said white and black two value signal at a speed equal to the scanning speed of said photoelectric conversion sensor to produce a delayed signal corresponding to each of said plurality of picture element groups;
 - a decoder means for decoding said delayed signal from said delay means; and,
 - means for counting a signal from said decoder means to produce data corresponding to said picture element groups.

4,295,121

DEVICE FOR OPTICAL CHARACTER READING

Mats A. Enser, Vändstigen; Lars O. Hallberg, Stalvägen, and Nils G. Stalberg, Jaktstigen, all of Sweden, assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Nov. 19, 1979, Ser. No. 95,832


Claims priority, application Sweden, Jan. 16, 1979, 7900362 Int. Cl.³ G06K 9/34

U.S. Cl. 340—146.3 MA

11 Claims

1. Device for optical character reading comprising an optical reading unit, a video detector, a segmenting unit, a video buffer, a recognition unit, a user unit and a control computer, characterized in that said control computer 1 is adapted to receive horizontal and vertical information for detecting video patterns 20, 21, 22, and 28 from the segmenting unit 2 and that said controlling computer 1 further is adapted to calculate coordinates for a start point 41, 42 for a character to be recog-

nized, whereby the computer sends coordinate values for the start point to the recognition unit 3 and that the recognition



unit thereafter, starting from the starting point, recognizes a character and returns the recognition result to the computer.

4,295,122

BUS PRIORITY CONTROL METHOD IN LOOP BUS NETWORK SYSTEM

Minoru Hatada; Kunio Hiyama, both of Sagami-hara; Hirokazu Ihara, Machida, and Hisao Kuma, Tokyo, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed Oct. 19, 1979, Ser. No. 86,443

Claims priority, application Japan, Oct. 30, 1978, 53-132656

Int. Cl.³ H04Q 9/00

U.S. Cl. 340-147 LP

17 Claims



1. For use in a loop bus network comprising a plurality of processors and a loop bus for connecting said processors to one another and for transmitting data in the form of messages in a predetermined direction therealong among said processors in series, a loop bus priority control method for selectively assigning the bus use to one of said processors on a priority bus, comprising

- transmitting priority data to said bus from one or more of said processors when message transmission on said loop is desired by said processor or processors, said priority data including both a message level and a sub-priority level, said message level designating the kind of message to be transmitted with respect to a plurality of different kinds of messages that might be transmitted and said sub-priority level indicating the priority level of the respective processor for the designated message level, the sub-priority levels assigned to said processors being different in different message levels;
- receiving in said processors priority data from said bus; and
- enabling use of said bus by that processor whose transmitted priority data designates the highest message level without regard to sub-priority levels or designates the highest sub-priority level within the highest designated

message level where the priority data transmitted by more than one processor designates the same highest message level.

4,295,123

ANALOG-TO-DIGITAL CONVERTER


Samuel C. M. Reid, R.F.D. 2, Peppers Ferry Rd., Radford, Va. 24141

Filed Jul. 27, 1979, Ser. No. 61,509

Int. Cl.³ H03K 13/02

U.S. Cl. 340-347 AD

16 Claims



1. An analog to digital converter for converting an analog signal into a digital equivalent, comprising:

- a first stage having:
 - first positive fixed current source means for providing a first positive current;
 - first current direction controlled voltage drop means having an input for the reception of input current and an output, for producing a voltage drop between the input and the output that varies in polarity in response to the sign of the input current, the input being operably connected to said first positive fixed current source means and to the analog signal.
 - first comparator means for comparing the input signal with the output signal of said first current direction controlled voltage drop means;
 - first negative switched current source means for providing a first negative current; and
 - first current switch means operably connected to said first comparator means and further operably connected between said first negative switched current source means and the output of said first current direction controlled voltage drop means, for selectively connecting said first negative switched current source means to the output of said first current direction controlled voltage drop means; and
- a second stage having:
 - second positive fixed current source means for providing a second positive current;
 - second current direction controlled voltage drop means having an input for the reception of input current and an output for producing a voltage drop between the input and the output that varies in polarity in response to the sign of the input current, the input being operably connected to said second positive fixed current sources means and to the output of said first current direction controlled voltage drop means, the output being operably connected to a ground; and
 - second comparator means for comparing the input signal with the output signal of said second current direction controlled voltage drop means.

4,295,124

COMMUNICATION METHOD AND SYSTEM


Philip M. Roybal, San Jose, Calif., assignor to National Semiconductor Corporation, Santa Clara, Calif.

Filed Aug. 13, 1979, Ser. No. 66,221

Int. Cl.³ H03K 13/00; H04L 3/00

U.S. Cl. 340-347 DD

22 Claims



19. A system for encoding and transmitting messages comprising words which are composed of characters coded in a code, comprising:

- a register for receiving entry of a word to be encoded and transmitted, said entry being coded character by character in said code;
- a code generation means for generating from the word entered in said register an address;
- a memory having addresses and having words stored at said addresses, said memory being connected to receive the generated address and to read out the corresponding word stored at said address;
- means for comparing for identity the word read out by said memory and the word received in said register, and
- means for transmitting the memory address of said word, if, and only if, the comparing means indicates identity.

4,295,125

METHOD AND MEANS FOR PIPELINE DECODING OF THE HIGH TO LOW ORDER PAIRWISE COMBINED DIGITS OF A DECODABLE SET OF RELATIVELY SHIFTED FINITE NUMBER OF STRINGS


Glen G. Langdon, Jr., San Jose, Calif., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Apr. 28, 1980, Ser. No. 143,986

Int. Cl.³ H03K 13/24

U.S. Cl. 340-347 DD

8 Claims



7. An apparatus for recursively decoding an instantaneous

FIFO binary arithmetic number string into a series of binary source symbols comprising:

- first means (23) for generating a binary source symbol (18) by the magnitude comparison between a predetermined portion of an arithmetic code string applied thereto and an updated trial augend, said first means includes means (202, 203) responsive to a present integer-valued parameter for controlling the relative magnitude between the arithmetic code string and the updated trial augend; and means for generating a status signal (WASMP5, 31) identifying the Boolean value of the previous bit decoded;
- second means (11) responsive to the output signal for accessing K component/K candidate next intergvalued control parameters (L0, k0; L1, k1; 25) and
- third means (21) including a memory for storing vector representations of the present and K next candidate control parameters and K next trial augends for K-way selecting and updating the trial augend from said candidates and applying them to said first means in predetermined displaced time relation to the next candidate control parameters applied to said third means.

4,295,126

MOS-BINARY-TO-DECIMAL CODE CONVERTER


Dieter Holzmann, Freiburg, and Friedrich Schmidtppott, Hartheim, both of Fed. Rep. of Germany, assignors to ITT Industries, Inc., New York, N.Y.

Filed Oct. 2, 1980, Ser. No. 193,205

Int. Cl.³ G06F 5/02

U.S. Cl. 340-347 DD

1 Claim



1. An MOS switching circuit for converting the code of an n-position binary number (n > 3) into the code of the associated, at least two-place decimal number with the aid of MOS-gates which are controlled by the respective binary position signals or the complement thereof, corresponding to the binary positions of the binary number, said circuit comprising: a NOR-matrix (1-10) with s times z transistors arranged in a row- and column-wise manner (s=number of columns, z=number of rows), is provided for each of the ten digits in the units place (DE1-DE0) of the decimal numbers (D1-D32), in each NOR-matrix (1-10) the controlled current paths of the transistors of each row, hence the row transistors, are arranged in parallel with one another, and the controlled current paths of the transistors of each column, hence the column transistors, are arranged in series with one another, with the one end of each series arrangement being applied to the zero point of the circuit, and with the other end thereof, via a load transistor (LM1-LM10) which is common to all columns per NOR-matrix (1-10), being applied to the supply voltage (+U_B), the number of columns s of the respective NOR-matrix (1-10)

equals n , the number of rows z is in the utmost equal to the number (d) of the decimal decades (DK) contained in the decimal number range (DB) as represented by the n -position binary numbers (B1-B32), to each row of the ten NOR-matrices (1-10) there is assigned one of the binary numbers (B1-B32) in such a way that in each NOR-matrix the binary numbers (B1, B11, B21, B31, etc.) are combined with the same decimal units digit (DE1-DE0), i.e. in such a way that the row as applied to the zero point of the circuit belongs to the binary number (B1-B10) with this decimal units digit from the lowest decimal decade (DK1), that the row which is the next higher one in direction towards the common load transistor (LM1) belongs to the binary number (B11-B20) with the same decimal units digit from the next higher decimal decade (DK2), etc. up to the row applied to the load transistor (LM1) which belongs to the binary number (B31, B32) with the same decimal units digit from the highest decimal decade (DK4), to the gate electrodes of the row transistors in a row belonging to one individual binary number (B1-B32) there are to be applied the position signals (A, B, C, D, E) of this binary number or else the complement thereof (A, B, C, D, E) so that in this way all row transistors of this particular row are switched to the non-conducting state, moreover, there is provided a multiple-NOR-gate (11) having p columns (S1-S4), with p being equal to the number (d) of the decimal decades (DK1-DK4) as contained in the decimal number range (DB) of the binary numbers (B1-B32), to each column (S1-S4) there is equidirectionally assigned one decimal decade (DK1-DK4) (S1 DK1, etc.), and this particular column consists of transistors (TS . . .) arranged parallel in relation to one another with their controlled current paths, arranged between one common load transistor (LS1-LS4) and the zero point of the circuit, the gate electrode of respectively one transistor (TS11-TS91) of the first column (S1) is applied to the output of the rows of the first nine NOR-matrices (1-9) associated with the first nine binary numbers (B1-B9), the gate electrode of respectively one transistor (TS02-TS92) of the second column (S2) is applied to the output of the rows of the ten NOR-matrices (1-10) as associated with the following ten binary numbers (B10-B19), the gate electrode of respectively one transistor (TS03-TS93) of the third column (S3), is applied to the output of the rows of the ten NOR-matrices (1-10) associated with the ten following binary numbers (B20-B29), etc., the gate electrode of respectively one transistor (TS04-TS24) of the last column (S4) is applied to the output of the rows of the ten NOR-matrices (1-10) associated with the remaining binary numbers (B30-B32), the output of the first column (S1) is applied via a first inverter (IN1) to the first input of a first decade-NOR-gate (N1) to the second input of which there is applied the output of the second column (S2), this output is applied via a second inverter (IN2) to the first input of a second decade-NOR-gate (N2), to the second input of which there is applied the output of the third column (S3), this output is applied via a third inverter (IN3) to the first input of a third decade-NOR-gate (N3), to the second input of which there is applied the output of the fourth column (S4), etc., up to reaching the highest decimal decade, at the output of the rows of the NOR-matrices (1-10) associated with the highest decimal decade (DK4 or DK3) there is to be taken off the signal for the digits (DE0-DE9) of the decimal units position (DE), and at the output of the decade-NOR-gate (N1-N3) there is to be taken off the signal for the digits (DZ1-DZ3) of the decimal-tens position (DZ), and all of the employed transistors are of the same conductivity type (n -channel or p -channel) as well as the same control type (depletion or enhancement type).

4,295,127

INFORMATION DISPLAY DEVICE


Helmut Sautter, Ditzingen; Kurt Hurst, Stuttgart, and Rainer Schink, Leonberg, all of Fed. Rep. of Germany, assignors to Robert Bosch GmbH, Stuttgart, Fed. Rep. of Germany
Filed Oct. 25, 1978, Ser. No. 954,639

Claims priority, application Fed. Rep. of Germany, Oct. 25, 1977, 2747794

Int. Cl.³ G08B 5/00

U.S. Cl. 340-373

4 Claims



1. Information display device having a frame (1) furnishing a display surface; a plurality of movable indicating elements (3, 13) arranged on said frame in segmental patterns representative of alphanumeric characters, and formed with at least two surface regions, one surface region having a visible aspect which essentially matches the visible aspect of the display surface and another, or other surface regions which have visible aspects contrasting with the visible aspect of the display surface, said indicating elements being movable to display respective surface regions so that, when any indicating element is in a first terminal position in which the visible aspects of the display surface and of the surface element matches, no display visible, but when the indicating element is in a second terminal position in which the visible aspects of the display surface and of the element differ, the element is visually recognizable, and comprising magnetic means (3, 4, 9) biasing said movable indicating element into one, or the other of said terminal positions and establishing the first and second positions as stable terminal positions; control means (39-44, 46; 47, 57) to selectively place said elements in either of said stable first or second terminal positions to provide a selective display of alphanumeric characters; electromagnetic operating means (3, 4, 7) including at least one permanent magnet (4) and one solenoid-electromagnet (7) located, respectively, on the display element and on the frame and being connected to and controlled by said control means to control movement of the display element between said stable first and second terminal positions; said movable indicating elements are elongated, essentially rectangular plates (3); the frame (1) is formed with an essentially V-shaped elongated groove, the longitudinal edge of said plate being fitted in the V-shaped groove and located adjacent the apex thereof; said permanent magnet (4) acting on said plate to hold said plate in position in the absence of energization of said solenoid-electromagnet (7), energization of said solenoid-electromagnet causing pivoting of said plate about a pivot axis adjacent the apex of the V to move the plate from one, to the other of said stable terminal positions.

4,295,128


APPARATUS FOR MEASURING THE DEGRADATION OF A SENSOR TIME CONSTANT

Hashem M. Hashemian, Knoxville; Thomas W. Kerlin, Concord, and Belle R. Upadhyaya, Knoxville, all of Tenn., assignors to University of Tennessee Research Corp., Knoxville, Tenn.
Filed Mar. 26, 1979, Ser. No. 23,641

Int. Cl.³ G08B 27/00

U.S. Cl. 340-506

21 Claims



1. A method for monitoring changes in the response time of a sensor while said sensor monitors fluctuations in a selected parameter comprising the steps of: providing a sensor signal from said sensor being monitored, said sensor signal indicative of fluctuations of said selected parameter; receiving said sensor signal and monitoring when the value of said sensor signal crosses a selected signal level; determining the number of times said sensor signal crosses said selected level in a selected time period to obtain a crossing rate; and comparing said crossing rate with a nominal crossing rate of determine a change in the response time of said monitored sensor.

4,295,129

SYSTEM CONDITION INDICATOR


Phillip J. Cade, Winchester, Mass., assignor to Electronics Corporation of America, Cambridge, Mass.

Filed May 7, 1979, Ser. No. 36,547

Int. Cl.³ G08B 23/00

U.S. Cl. 340-520

15 Claims



1. For use with a burner control system including a plurality of interlock switches, a main fuel valve, and a pilot fuel valve, a system condition indicator comprising: a plurality of interlock monitor means, equal in number to the number of interlock switches and each associated with and connected to respective ones of the plurality of interlock switches, for determining the absence of an AC power line signal at a terminal of the associated interlock switch and for providing an output signal representative thereof; main monitor means associated with and connected to the

4,295,130

AUDIO-VISUAL DISASTER ALERT SYSTEM


Yang Tai-Her, No. 9-1, Tai-Ping St., Kung-Hua Li, Hsi-Hu Town, Chang Hua Hsien, Taiwan

Filed Jun. 18, 1979, Ser. No. 49,806

Int. Cl.³ G08B 19/00

U.S. Cl. 340-524

7 Claims



1. An audio/visual disaster alert system for a plurality of areas in a building or the like comprising, in combination, a disaster warning circuit in each of said areas, an associated source of electric power, each of said disaster warning circuits including sensing means responsive to a disaster for producing an out signal a normally inoperative tape recorder/player having an audio output for providing a taped message stating the location of the disaster and the disaster measures to be taken and a speaker connected to said tape recorder/player audio output, means responsive to said output signal from said sensing means in each of said areas for activating the associated tape recorder/player to provide an audio output, means for feeding the audio output of said activated tape recorder/player to the associated speaker in said area and means for interconnecting the audio output from said activated tape recorder/player to all of the speakers in said areas, whereby the message from said activated tape recorder/player is supplied to the speakers in all of said disaster warning circuits.

4,295,131

LOW CONSUMPTION PULSES DOPPLER EFFECT INTRUSION SENSOR



Maurizio Bonori, and Caferio Franconi, both of Rome, Italy, assignors to AD.ELE. -Advanced Electronics- S.R.L., Rome, Italy

Filed Apr. 19, 1978, Ser. No. 897,776

Claims priority, application Italy, May 10, 1977, 49333 A/77
Int. Cl.³ G01S 13/56; G08B 13/18

U.S. Cl. 340—554

7 Claims



1. An intruder alarm sensor for detecting, from the Doppler information of pulsed waves reflected from a target, the presence of a target moving at a speed within a range between a slowest target speed of interest and a fastest target speed of interest in the presence of stationary or periodic interference in a zone under surveillance defined by a maximum range, said intruder alarm sensor comprising:

- a pulse modulated oscillator means for generating a pulse modulated oscillation signal at a predetermined carrier frequency having a pulse repetition frequency at least twice the Doppler frequency of the fastest target speed of interest and having a pulse width greater than a first predetermined period of time;
- a first transducing means connected to said pulse modulated oscillator means for transmitting said pulse modulated oscillation signal for propagation as pulsed wave fields within the zone under surveillance, said first predetermined period of time being twice the period required for said pulsed wave fields to propagate a distance equal to the maximum range of the zone under surveillance;
- a second transducing means for receiving pulsed wave signals reflected by a target within the zone of surveillance and for transforming said received pulsed wave signals into pulsed oscillatory electric signals having Doppler information corresponding to the relative motion between the target and said first transducing means;
- mixing means connected to said pulse modulated oscillator means and said second transducing means for mixing said pulse modulated oscillation signal and said pulsed oscillatory electric signals for producing a detected pulse signal having said pulse repetition frequency and having amplitude modulation corresponding to said Doppler information, said detected pulse signal having a center frequency and an amplitude modulated bandwidth equal to twice the difference between the Doppler frequency of the fastest target speed of interest and the Doppler frequency of the slowest target speed of interest;
- a processing means connected to said mixing means for demodulating said Doppler information which is amplitude modulated on said detected pulse signal for generat-

ing a Doppler information signal having an amplitude proportional to the value of said Doppler information; a comparing means connected to said processing means for comparing said Doppler information signal with a predetermined threshold level for generating an alarm trigger signal when the level of said Doppler information signal exceeds said predetermined threshold level; and an alarm actuating means connected to said comparing means for actuating an alarm when said comparing means generates said alarm trigger signal.

4,295,132


CAPACITANCE INTRUSION DETECTION SYSTEM
Charles F. Burney, and Marvin D. Laymon, both of Milpitas, Calif., assignors to GTE Products Corporation, Stamford, Conn.

Filed Jul. 28, 1980, Ser. No. 172,602

Int. Cl.³ G08B 13/26

U.S. Cl. 340—562

11 Claims



1. An intrusion detection system for an object having a capacitance comprising
- a charge pump having an input and an output,
 - a voltage source connected to said input,
 - said object being connected to said output of the charge pump,
 - means to cyclically switch said charge pump between first and second states whereby alternately to connect and disconnect said voltage source and said object for successively charging the latter,
 - storage means connected to said charge pump for producing a DC voltage proportional to the charge on said object,
 - bandpass filter means having a low cutoff frequency f_1 and a high cutoff frequency f_2 ,
 - capacitor means interconnecting said storage means and said filter means whereby changes in the capacitance of said object at a rate between f_1 and f_2 produce an output from said filter means, and
 - means responsive to the output of said filter means for producing an alarm.

4,295,133

APPARATUS TO INDICATE WHEN A PATIENT HAS EVACUATED A BED OR DEMONSTRATES A RESTLESS CONDITION

Dwight A. Vance, 8709 E. 29th, Tulsa, Okla. 74129

Continuation-in-part of Ser. No. 794,041, May 5, 1977. This application Oct. 10, 1978, Ser. No. 949,969

The portion of the term of this patent subsequent to Dec. 18, 1996, has been disclaimed.

Int. Cl.³ G08B 21/00

U.S. Cl. 340—573

11 Claims

1. A monitoring system for a bed patient, comprising:
- (a) a binary signal generating means adapted to indicate one of two possible positions of a body in a bed; and producing

4,295,135

ALIGNABLE ELECTRONIC BACKGROUND GRID GENERATION SYSTEM

Josef Sukonick, 10395 Dempster Ave., Cupertino, Calif. 95014



Filed Dec. 18, 1978, Ser. No. 970,755

Int. Cl.³ G06F 3/14

U.S. Cl. 340—734

31 Claims

- a first signal when said body is in a rest position in said bed; and a second signal when said body is out of said bed;
- (b) signal processing means comprising:
 - (i) oscillator means actuated responsive to said second signal, said oscillator means comprising:
 - (i) a first and a second NAND gate;
 - (ii) one input lead from each gate connected to a selected terminal responsive to said second signal;
 - (iii) the output of said second gate connected through a capacitor and first resistor to the second input of said first NAND gates;
 - (iv) the output of said first NAND gate connected to the second input terminal of said second NAND gate;
 - (v) a series second resistor and third resistor connected between the output of said first NAND gate and the junction between said capacitor and said first resistor;
- (2) counter means responsive to said oscillator means;
- (3) latch means responsive to a selected count of said counter means;
- (4) alarm means responsive to the setting of said latch means.



1. An alignable electronic background grid generation system for use with a raster-type video graphics display unit on which graphic data is displayed, comprising:
- control means for supplying alterable grid pattern and offset data,
 - vertical grid pattern generation means, cooperating with said control means and synchronized with the display unit horizontal video scan, for providing in response to said alterable grid pattern data vertical grid pattern defining signals indicative of requisite background grid spots at horizontal picture element locations corresponding to desired vertical background grid lines specified by said grid pattern data,
 - horizontal grid pattern generation means, cooperating with said control means and synchronized with the display unit vertical line scan, for providing in response to said alterable grid pattern data horizontal grid pattern defining signals indicative of a desired horizontal grid line pattern specified by said grid pattern data, and
 - combinatorial logic means, cooperating with both said vertical and horizontal grid pattern generation means, for combining said provided vertical and horizontal grid pattern defining signals and producing as a result of said combination a set of grid intensity or color control signals, said grid intensity control signals being supplied to said video graphics display unit to be mixed with the other video signals defining said graphic data being displayed, said display unit thereby producing a composite display including both said graphic data and said background grid.

4,295,134

LIQUID FLOW DETECTING DEVICE

Anthony C. Fairlie-Clarke, Edinburgh, Scotland, assignor to Vickers Limited, London, England


Filed Jul. 11, 1979, Ser. No. 56,649

Claims priority, application United Kingdom, Jul. 12, 1978, 29638/78

Int. Cl.³ G08B 21/00; G01F 15/06

U.S. Cl. 340—610

10 Claims



1. A liquid flow detecting device incorporating a static member arranged to be fixed within a passage through which flow of an operating liquid is to take place and an active member held captive in space by the static member but physically separate from the static member and free to undergo a displacement relatively to the static member to a limited extent in one particular direction at least and having an overall specific gravity substantially the same as that of the chosen operating liquid and proximity sensing apparatus operative to detect movement of the active member relative to the static member in the particular direction and issue a corresponding signal.

4,295,136

INDICATING APPARATUS, PARTICULARLY FOR VIBRATION ANALYZING EQUIPMENT

Donn V. Stoutenburg, Westerville, Ohio, assignor to IRD Mechanical Analysis, Inc., Columbus, Ohio

Filed Sep. 17, 1979, Ser. No. 76,030


Int. Cl.³ G06F 3/14; H04N 5/50

U.S. Cl. 340—753

9 Claims

1. Apparatus for facilitating the manual selection and read-out of the center frequency of an a.c. signal which corresponds with a characteristic amplitude comprising:
- a tunable filter of a variety wherein the passband center frequency thereof is selectable as a function of a tuning input signal applied at a tuning input thereof, said filter receiving said a.c. signal and providing a filtered signal at an output;
 - error circuit means responsive to said a.c. signal and said filtered signal for deriving an error signal of magnitude and polarity corresponding to the relationship of said

tuning input and a frequency associated with said characteristic amplitude;
manually actuable means movable in first and second directions for deriving said input signal;
means for deriving first and second reference level signals including converter means responsive to said filtered signal for providing said reference level signals as d.c. voltages proportioned with said filtered signal; and display means including:
first and second indicators, each being selectively energizable in correspondence with respective first and second said ranges of magnitudes of said error signal and each being energizable in correspondence with a first said polarity;
third and fourth indicators, each being selectively energizable in correspondence with respective third and fourth ranges of said magnitudes of said error signal and each



being energizable in correspondence with a second said polarity; and
fifth indicator means energizable when said filtered signal substantially corresponds with said center frequency; electrical circuitry responsive to said error signal and said first reference level signal for energizing said first indicator in the presence of said first polarity and said first magnitude range, for energizing said second indicator in the presence of said first polarity and said second magnitude range, for energizing said third indicator in the presence of said second polarity and said third magnitude range, and for energizing said fourth indicator in the presence of said second polarity and said fourth magnitude range, and for energizing said fifth indicator substantially in the absence of said error signal, said second and fourth magnitude ranges being of lesser value than said first and second magnitude ranges.

4,295,137

ELECTROLUMINESCENT DISPLAY DRIVER SYSTEM FOR THIN-FILM ELECTROLUMINESCENT DEVICES REQUIRING ELECTRIC FIELD REVERSAL

Paul O. Haugsjaa, Acton, Mass., assignor to GTE Laboratories Incorporated, Waltham, Mass.

Filed Jan. 7, 1980, Ser. No. 110,161


Int. Cl.³ G06F 3/14

U.S. Cl. 340—781

15 Claims

1. An electroluminescent display system comprising:
a plurality of thin-film electroluminescent elements each having a digit electrode and a segment electrode and having associated therewith a characteristic electroluminescent threshold voltage;
a set of digit driver means each selectively coupled to digit electrodes of the elements of said display and having an input terminal for receiving a digit control signal including precharging portions and addressing portions; and
a set of segment driver means each selectively coupled to segment electrodes of the elements of said display and having an input terminal for receiving a segment control signal including precharging portions and energizing

portions which are simultaneous with the addressing portions of the digit control signal;
said set of digit driver means and said set of segment driver means being operative, during precharging portions of digit and segment control signals, to precharge the elements of said display by applying a first voltage to the digit electrode and a second voltage to the segment electrode of each element of said display, said first and second voltages having a difference therebetween which is greater in magnitude than said threshold voltage,
said set of digit driver means being further operative, during addressing portions of the digit control signal, to selec-



4,295,138

COMBINED CONSTANT POTENTIAL AND CONSTANT VOLTAGE DRIVING TECHNIQUE FOR ELECTROCHROMIC DISPLAYS

Hiroshi Nakauchi; Katubumi Koyanagi; Yasuhiko Inami, all of Tenri, and Hisashi Ueda, Yamatokoriyama, all of Japan, assignors to Sharp Corporation, Osaka, Japan

Continuation of Ser. No. 873,504, Jan. 30, 1978, abandoned. This application Nov. 16, 1979, Ser. No. 94,933

Claims priority, application Japan, Jan. 31, 1977, 52-10120; Feb. 4, 1977, 52-12350


Int. Cl.³ G06F 3/14; G09F 9/32

U.S. Cl. 340—785

9 Claims

1. A method for driving an electrochromic display cell to exhibit electrochromic phenomenon at said display cell, said display cell including a counter electrode, a plurality of display electrodes and a reference electrode, said method comprising the steps of:
driving said electrochromic display cell by maintaining a constant potential at respective ones of said display electrodes relative to said reference electrode when it is desired to color said respective ones of said display electrodes despite variations in the amount of energizing current supplied to said counter electrode in response to increases and decreases in the number of said display electrodes having their display states changed thereby

maintaining the degree of coloration of said respective ones of said display electrodes uniform; and
driving said electrochromic display cell by maintaining a constant voltage between said display electrodes and said



4,295,139

METHOD FOR TRANSMITTING AIRPORT WEATHER INFORMATION


Roberto Arpino, 4722 Shire Ridge Rd. West, Columbus, Ohio 43220

Filed May 7, 1979, Ser. No. 36,518

Int. Cl.³ G01W 1/10; G01C 21/00

U.S. Cl. 340—870.01

7 Claims



1. A method of transmitting a plurality of types of real-time weather information to a remotely located receiver comprising the steps of:

- generating a signal representing instantaneous weather information;
- determining a real-time weather information value from said instantaneous weather information signal over a predetermined time interval;
- performing said steps (a) and (b) for each one of said types of real-time weather information in sequence;
- generating an address signal representing said real-time weather information value;
- storing a plurality of signals representing real-time weather information messages;
- generating the one of said message signals corresponding to the real-time weather information value in response to said address signal;
- transmitting said one message signal to the receiver; and performing steps (c) through (f) for each one of said types of real-time weather information in sequence.

4,295,140

FARADAY ROTATION MEASUREMENT METHOD AND APPARATUS


Robert A. Frosch, Administrator of the National Aeronautics and Space Administration, with respect to an invention of, and Milton H. Brockman, Glendale, Calif.

Filed Dec. 21, 1979, Ser. No. 106,119

Int. Cl.³ H04B 7/00

U.S. Cl. 343—100 PE

15 Claims



1. In an rf receiver array having at least a first and second receiving system, said first receiving system having a reference signal for forming an IF signal and said second receiving system having a tracking feedback signal whose phase is related to the phase of a received signal, a measurement means for determining Faraday rotation of said received signal comprising:

- a first phase detector;
- a second phase detector;
- means for providing said reference signal to said first phase detector;
- means for providing said reference signal phase-shifted by a predetermined phase increment to said second phase detector;
- means for providing said feedback signal to said first and second phase detectors;
- first means for generating a plurality of first occurrence time signals when said first phase detector output defines a predetermined phase relationship between said reference signal and said feedback signal;
- second means for generating a plurality of second occurrence time signals when said second phase detector output defines said predetermined phase relationship between said phase-shifted reference signal and said feedback signal;
- third means for generating a plurality of cyclically occurring comparison signals having a cycle time related to an average time between a predetermined number of occurrence time signals from said first phase detector output signal; and
- means for determining the phase relationship between said cyclically occurring comparison signals and said second occurrence time signals, said phase relationship being related to Faraday rotation of said received signal.

4,295,141

DISC-ON-ROD END-FIRE MICROWAVE ANTENNA

Richard D. Bogner, 4 Hunters La., Roslyn, N.Y. 11576

Continuation-in-part of Ser. No. 938,883, Sep. 1, 1978,

abandoned. This application May 14, 1980, Ser. No. 149,664


Int. Cl.³ H01Q 13/28

U.S. Cl. 343—753

12 Claims

1. A plate-on-rod end-fire antenna comprising a launcher and end-fire radiator exhibiting close to optimum gain over a range of lengths between 3λ and 12λ where λ is the wavelength at the operating frequency, and having a principal axis adapted to be energized by the launcher at the non-radiating end of said radiator for the transmission of energy wavelength λ in the direction of the axis, the electrically active components of said radiator consisting of a plurality of substantially thin

identical electrically conductive round plates substantially uniformly spaced between 0.18λ and 0.23λ apart, along said axis, with the plane of the plates normal to said axis, to form an elongated radiator fitting within a circumscribing cylinder,



coaxial with said principal axis, the difference between the diameter of said cylinder and the diameter of an axial conductive support rod supporting said plates being greater than 0.23λ and less than 0.27λ .

4,295,142

CORRUGATED HORN RADIATOR

Helmuth Thiere, Munich, and Werner Vallentin, Groebenzell, both of Fed. Rep. of Germany, assignors to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany


Filed Jul. 22, 1980, Ser. No. 171,143

Claims priority, application Fed. Rep. of Germany, Jul. 30, 1979, 2930932

Int. Cl.³ H01Q 19/12, 13/02

U.S. Cl. 343—781 CA

7 Claims



1. A corrugated horn radiator in which a transition zone is inserted between a smooth-walled wave guide feed with a constant cross-section and a funnel radiator with a regularly periodic corrugation structure with a corrugation depth of less than a quarter wave length with reference to the lowest operating frequency, characterized in that, proceeding from the said wave guide feed (1), the transition zone consists of the following sections attached to one another in the following order:

- a uniformly expanding, smooth-walled wave guide section (2),
- a smooth-walled wave guide section (3) designed with a constant cross-section connected to wave guide section (2),
- a smooth-walled funnel section (4) connected to wave guide section (3) smoothly and bend-free and which continuously increases in diameter particularly exponentially, with respect to its cross-section dimension,
- a funnel section connected to wave guide section (4) smoothly and bend-free, continuously increasing in diameter, particularly exponentially, with respect to its cross-section dimension, said funnel section having a first matching adaptation zone (5) which consists of at least two successive corrugations (6, 7) which are dimensioned considerably narrower with respect to their widths than are the corrugations of the periodic corrugation structure (10) and are also suitably matched in width, which exceed in depth the corrugation depths in the periodic corrugation structure (10) and which are provided with ring-

shaped openings (11) which extend in the direction toward the wave guide feed (1), said openings (11) being approximately one eighth a wave length deep with respect to the lowest operating frequency to be transmitted, and (e) a uniformly increasing funnel section with respect to its cross-section dimension which has a second matching adaptation zone (8) which consists of a plurality of successive corrugations (9) with depths continuously graduated up to the depths of the regular corrugation structure (10).

4,295,143

LOW WIND LOAD MODIFIED PARABOLIC ANTENNA


John R. Winegard, Evergreen; Carey W. Shelledy, Lakewood, and Keith B. Cowan, Arvada, all of Colo., assignors to Winegard Company, Burlington, Iowa

Filed Feb. 15, 1980, Ser. No. 121,696

Int. Cl.³ H01Q 19/12, 15/20

U.S. Cl. 343—840

24 Claims



1. An improved modified and collapsible parabolic antenna for receiving incoming signals having low wind load characteristics mounted to a support, said antenna having means for sensing reflected signals in its focal area, said improved antenna comprising:

- an elongated boom having two symmetrical half sections, said boom being further formed to follow a substantially parabolic orientation along its longitudinal axis,
- a first and second series of reflector elements for reflecting said incoming signals to said sensing means, each of said series being mounted to one of said half sections of said boom, each of said first and second series of reflector elements comprising:
 - a plurality of thin substantially elongated rectangular elements of equal length being formed in the substantial shape of a parabola along its longitudinal axis, and
 - means for mounting the mid-section of each of said elements in a substantial perpendicular relationship to said boom at equal predetermined spaced distances from each other, said predetermined spaced distance being determined in a plane perpendicular to the path of said incoming signals, and
- means releasably connectable to said support for mounting to one end of each of said boom half sections in the region of the vertex of said boom parabolic shape, said boom half sections being capable of pivoting in said mounting means from an outward position wherein said boom half sections form said parabolic shape to an inward position wherein said boom half sections are in substantial opposing parallel relationship.

4,295,144

FEED SYSTEM FOR A CIRCULARLY POLARIZED TETRA-COIL ANTENNA


Joseph J. Matta, Cinnaminson, and Andrej Skalina, Cherry Hill, both of N.J., assignors to RCA Corporation, New York, N.Y.

Filed Mar. 31, 1980, Ser. No. 136,155

Int. Cl.³ H01Q 1/36

U.S. Cl. 343—895

8 Claims



1. An antenna comprising a central conductive mast, at least first and second conducting helices disposed about said mast, a conductive housing disposed proximate an end of said helices, a coaxial transmission line disposed within said mast, the inner conductor of said line extending into said housing and being coupled to said first helix, and a first belt line disposed in said housing and coupled between said helices and having a selected length to provide a selected phase shift between said helices and being folded to conserve space.

4,295,145

ACOUSTO-OPTICALLY MODULATED LASER SCANNING ARRANGEMENT FOR CORRECTING FOR INTERFERENCE APPEARING THEREIN


Milton R. Latta, San Jose, Calif., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Dec. 29, 1978, Ser. No. 974,632

Int. Cl.³ G01D 15/14

U.S. Cl. 346—108

8 Claims



1. An acousto-optically modulated light scanning system of the type wherein light from a laser beam is deflected in one direction by acousto-optical apparatus operating at a plurality of different frequencies and thereafter deflected in another direction by other optical apparatus for creating an image raster display in a multiple of scan lines spaced apart by a designated scan line spacing, which scanning normally would include undesirable effects of intermodulation products including spot overlap in said display, said system comprising

- laser apparatus for generating a beam of coherent light, acousto-optical modulating apparatus arranged for intercepting light from said laser apparatus and for deriving at least a plurality of beams that are individually modulatable, and for independently and simultaneously modulating said derived beams to form at least a plurality of sequentially modulated beams for creating a display, and
- characterized by said acousto-optically modulating apparatus being arranged

for extending the angle between said individually and simultaneously modulated light beams by at least triple the angle at which said designated scan line spacing obtains on said display, and

said system being arranged simultaneously for projecting at least two of said simultaneously and individually modulated light beams onto said display in coincidence with at least two scan lines spaced apart at an integral number greater than two of intervals of said designated scan line spacing whereby simultaneous spot overlap is prevented for obviating distortion that otherwise would result from said intermodulation products.

4,295,146

DEVICE FOR MOVING AUTOMATIC DRAWING MACHINE TOOLS

Werner Cordes, Hamburg, Fed. Rep. of Germany, assignor to Aristo Graphic Systeme GmbH & Co. KG, Hamburg, Fed. Rep. of Germany


Filed Jun. 20, 1980, Ser. No. 161,477

Claims priority, application Fed. Rep. of Germany, Aug. 24, 1979, 2934273

Int. Cl.³ G01D 15/16

U.S. Cl. 346—140 R

11 Claims



1. An improved device for translational movement of automatic drawing machine tools, comprising a frame capable of being connected to a drawing machine, and a permanent magnet system, wherein a controlling plunger is attached for free movement, with respect to said frame, and said plunger is connected to a tool carrier which accepts a writing tool, wherein further, an electromagnetic control coil (3) around said plunger, is interconnected to said tool carrier (6) by means of a mechanical linkage on said frame (1), to move said plunger and carrier in opposite directions.

4,295,147

JOSEPHSON DEVICES OF IMPROVED THERMAL CYCLABILITY AND METHOD

Charles J. Kircher, Yorktown Heights; Hung-Chang W. Huang, Hopewell Junction, and Masanori Murakami, Yorktown Heights, all of N.Y., assignors to International Business Machines Corp., Armonk, N.Y.

Filed Feb. 1, 1980, Ser. No. 117,790

Int. Cl.³ H01L 39/22


U.S. Cl. 357—5

23 Claims

1. A tunnel device exhibiting Josephson tunneling current comprising:

- a first electrode comprised of at least one superconductor, the grain size of the said superconductor being ≤ 100 nm;
- a tunnel barrier in contact with said first electrode com-

prised of an insulating layer and being sufficiently thin that Josephson current can tunnel therethrough; and



(c) a second electrode in contact with said tunnel barrier comprised of a superconductor.

4,295,148 METHOD OF FABRICATION OF ELECTROLUMINESCENT AND PHOTODETECTING DIODES

Jean Marine, and Michel Ravetto, both of Grenoble, France, assignors to Commissariat a l'Energie Atomique, Paris, France


Filed Mar. 21, 1979, Ser. No. 22,607

Claims priority, application France, Mar. 23, 1978, 78 08522

Int. Cl.³ H01L 33/00, 31/00, 31/18

U.S. Cl. 357-17

13 Claims



1. A method of fabricating electroluminescent and photodetecting diodes, comprising

- providing a wafer of p-type ZnTe semiconductor material;
- forming a compensated layer of thickness x_1 in a first surface of said wafer in such a manner as to provide insulation with high resistivity;
- implanting ions in the first surface with sufficient energy to form a trapping region of thickness x_1 and to form beneath said trapping region an insulating region of thickness x_2 , with $x_1 < x_2$; and
- forming a metallic contact layer on a second surface of the wafer.

12. An electroluminescent and/or photodetecting diode of ZnTe comprising a substrate of p-type ZnTe, a trapping region at a surface of the substrate, a resistive region below said trapping region having a resistivity of the order of 10^7 to 10^9 cm, and an electrical surface contact.

4,295,149 MASTER IMAGE CHIP ORGANIZATION TECHNIQUE OR METHOD


John Balyoz, Hopewell Junction; Chi S. Chang, Wappingers Falls; Barry C. Fox, Poughkeepsie; John A. Palmieri, Wappingers Falls; Majid Ghafghaichi, Poughkeepsie; Teh-Sen Jen, Fishkill, and Donald B. Mooney, Poughkeepsie, all of N.Y., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Dec. 29, 1978, Ser. No. 974,576

Int. Cl.³ H01L 27/10

U.S. Cl. 357-45

6 Claims



1. In an improved planar semiconductor integrated circuit chip structure, said chip structure having:

- a surface from which a plurality of regions of different conductivity type extend into the chip to provide a plurality of electrically isolated functional circuits, each of said functional circuits including the required interconnected components to provide the function thereof;
- at least one of said functional circuits being a transistor-transistor logic functional circuit, at least one of said functional circuits being an emitter coupled logic functional circuit, and at least one of said functional circuits being a Schottky-Transistor logic functional circuit;
- an X pattern of equally spaced parallel conductors overlying and electrically insulated from said chip structure surface, said X pattern of conductors being minimally spaced one from another and selectively connected to at least selected certain ones of said functional circuits;
- a Y pattern of equally spaced parallel conductors overlying and electrically insulated from said X pattern of parallel conductors, said Y pattern of conductors being selectively connected to at least selected certain ones of said functional circuits and at least certain conductors of said X pattern of conductors;
- said X pattern of conductors and said Y pattern of conductors being orthogonal one to another and thereby geometrically manifesting an X, Y coordinate system;
- said integrated circuit chip structure being characterized in that all connections between said X pattern conductors, said Y pattern conductors and said functional circuits exist in space only at X, Y intersections of said X-Y coordinate system geometrically manifested by said X and Y patterns of conductors.

4,295,150 STORAGE TRANSISTOR

Fritz G. Adam, Freiburg, Fed. Rep. of Germany, assignor to ITT Industries, Inc., New York, N.Y.

Filed Oct. 1, 1979, Ser. No. 80,869

Claims priority, application Fed. Rep. of Germany, Oct. 18, 1978, 2845328

Int. Cl.³ H01C 29/78; G11C 11/40

U.S. Cl. 357-54


14 Claims

1. A storage transistor, comprising:
 - a substrate formed of a semiconductor body having a plane surface;
 - a source region formed in said surface;

a drain region formed in said surface and spaced from the source region forming a channel region therebetween;

a gate electrode disposed over said channel region;

a storage medium comprising a layer of semiconducting material, said storage medium having a first portion disposed between the gate electrode and channel region and a second portion extending from between the channel region and gate electrode, the ratio of the surface area of the second portion of the storage medium to the first portion of the storage medium being between 2 and 3;



- a first partial gate insulator layer disposed between the storage medium and the channel region having a thickness ranging between approximately 100 and 200 A.U.; and
- a second partial gate insulator layer disposed between the storage medium and the gate electrode and having a thickness ranging between approximately 200 and 500 A.U., whereby a write or erase pulse may be applied to the gate electrode for storing or removing a charge into or from the storage medium respectively thereby displacing the threshold voltage and a read pulse may be applied to the gate electrode for scanning the magnitude of the threshold voltage.

4,295,151 METHOD OF BONDING TWO PARTS TOGETHER AND ARTICLE PRODUCED THEREBY


Paul Nyul, New Holland, and Frederick R. Hughes, Lancaster, both of Pa., assignors to RCA Corporation, New York, N.Y.

Filed Jan. 14, 1980, Ser. No. 111,814

Int. Cl.³ H01U 23/48

U.S. Cl. 357-68

4 Claims



1. An array of laser diodes comprising
 - a pair of laser diodes each being a body of semiconductor material having top and bottom surfaces and an edge surface from which light is adapted to be emitted, said diodes being arranged with the top surface of one being in spaced opposed relation to the bottom surface of the other,
 - an intermediate member between said opposed surfaces of the laser diodes and having a separate surface contacting each of said opposed surfaces of said laser diodes, said intermediate member having a plurality of openings therethrough, and
 - a bonding material in the openings in the intermediate member and adhered to the opposed surfaces of said diodes to secure the diodes together.

4,295,152 OPTICAL COUPLER WITH A HOUSING PERMITTING ADJUSTMENT OF THE DISTANCE BETWEEN THE LIGHT SOURCE AND THE LENS

Giok D. Khoe; Hendrikus G. Kock; Lambertus J. Meuleman, and Lodewijk J. Van Ruyven, all of Eindhoven, Netherlands, assignors to U.S. Philips Corporation, New York, N.Y.


Filed Jun. 1, 1979, Ser. No. 44,611

Claims priority, application Netherlands, Jun. 19, 1978, 7806569

Int. Cl.³ H01L 23/12, 23/02, 27/14

U.S. Cl. 357-74

8 Claims



1. An optical coupler comprising a support, a light source for emitting a beam of light mounted on said support, a tubular member affixed to said support, said tubular member being disposed about said source such that the longitudinal axis of said tubular member is generally coaxial with the axis of said beam so that said beam passes through said tubular member along the axis thereof, a holder having a cylindrical portion and a hole formed therethrough, said hole extending along the longitudinal axis of said cylindrical portion, a lens, means for supporting said lens on said holder adjacent one end of said cylindrical portion so that said lens is centered about the longitudinal axis of said hole, the end portion of said cylindrical portion opposite said one end being in telescoping engagement with said tubular member so that said axis of said cylindrical portion is coaxial with the axis of said tubular member and so that said holder and said lens supported thereon is displaceable relative to said tubular member and said support in a direction parallel to the longitudinal axes thereof thereby enabling the distance between said light source and said lens to be adjusted while maintaining the axis of said beam aligned with the center of said lens.

4,295,153 STEREOSCOPIC APPARATUS AND METHOD OF USING SAME


Stephen Gibson, 547 N. Beachwood Dr., Los Angeles, Calif. 90004

Filed Mar. 31, 1980, Ser. No. 135,471

Int. Cl.³ H04N 9/54, 9/60


U.S. Cl. 358-3

9 Claims



1. In combination with a camera that includes a housing on which a lens assembly is removably supported by first means on the exterior thereof to record a two-dimensional of a scene

- position between the initial and inserted positions, to the inserted position by the force of the second bias means;
- (d) locking means, movable between a lock position and an unlock position, being moved into the lock position for restraining the guiding means in the inserted position, and being moved into the unlock position for releasing the guiding means to allow the first bias means to return the guiding means from the inserted position back to the initial position;
- (e) a disabling means, operatively associated with the locking means, for disabling the intake mechanism means to disengage the second bias means from the guiding means when the locking means is moved to the lock position;



- (f) actuating means, operatively associated with the locking means, adapted for connection to the electric power source for energization thereby, said actuating means being adapted to restrain the locking means in the lock position only when both the actuating means is energized by the power source and when the locking means is shifted to the lock position, whereby if the power from the power source is cut off when the cassette is in the loaded condition, the actuating means will be de-energized and cease restraining the locking means in the lock position, allowing the locking means to move from the lock position to the unlock position, and permitting the first bias means to return the guiding means back to the initial position to guide the cassette to the unloaded position.


4,295,170

VARIABLE TAPE SPEED FOR VIDEO RECORDERS
David A. Weisbrod, Moore, Okla., assignor to Mike A. Janko, Oklahoma City, Okla.

Filed Oct. 22, 1979, Ser. No. 87,429
Int. Cl.³ G11B 15/46, 19/28

U.S. Cl. 360-73

11 Claims



1. A speed control adapted for use with a video tape recorder having a play mode, a record mode, a power supply providing a power signal, a capstan motor for driving the video tape in a forward direction, a reel stop detector which provides a command signal for causing the video tape to be

unthreaded and returned to a video cassette, and a capstan servo amplifier which provides an output signal to the capstan motor for preventing the capstan motor from being operated below normal speed, the video tape recorder providing an output signal indicating the video tape recorder is in the play mode of operation, the speed control comprising:

- a capstan drive amplifier adapted to receive the power signal and an input control signal, the capstan drive amplifier providing an output signal connectable to the capstan motor and the speed of the capstan motor being varied in response to the variations in the capstan drive amplifier output signal, the capstan drive amplifier output signal being controllably variable in response to the input control signal;
- a variable controller, having an "on" position and an "off" position, the variable controller providing the controllably variable control signal, the variable controller control signal being connected to the capstan drive amplifier for controllably varying the output signal of the capstan drive amplifier;
- an unthread inhibit receiving the output signal provided by the variable controller and providing an output shunt signal in response to receiving the output signal from the variable controller, the shunt signal being connectable to the reel stop detector in the video tape recorder for preventing the reel stop detector from providing the command signal; and
- a capstan servo inhibit receiving the output control signal provided by the variable controller and providing and output disable signal in response to receiving the control signal, the output disable signal being connectable to the capstan servo amplifier in the video tape recorder to inhibit the capstan servo amplifier from providing the output signal to the capstan motor for preventing the capstan motor from operating below normal speed.

4,295,171

SYSTEM FOR CONTROLLING ROTATION OF ROTATING STRUCTURE

Akira Hirota, Chigasaki; Yoshiteru Kosaka, Kamakura, and Kazutaka Ashida, Sagami-hara, all of Japan, assignors to Victor Company of Japan, Ltd., Yokohama, Japan


Filed Feb. 11, 1980, Ser. No. 120,287

Claims priority, application Japan, Feb. 13, 1979, 54-15226

Int. Cl.³ G11B 15/54, 19/28

U.S. Cl. 360-73

6 Claims



1. A system for controlling the rotation of a rotating structure comprising:
- means for detecting the rotation of the rotating structure;
- means for repeatedly forming address signals for every revolution of the rotating structure in response to a detection output from the rotation detection means;
- memory means in which control data responsive to deviations in the rotational peripheral speed of the rotating structure in each revolution thereof have been stored beforehand at addresses corresponding to said address signals, the address signals being supplied to the memory

means, whereupon the data stored at the corresponding addresses are read out; and

control means for obtaining a control signal from the detection output of the rotation detecting means and the data thus read out from the memory means and accordingly controlling the rotation of the rotating structure.

4,295,172

ROTARY MAGNETIC HEAD APPARATUS

Tetsuji Fukada, Nirakata, and Yukihiro Ise, Toyonaka, both of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan


Filed Nov. 8, 1979, Ser. No. 92,375

Claims priority, application Japan, Nov. 10, 1978, 53-139032; Nov. 27, 1978, 53-146928; Feb. 16, 1979, 54-17379

Int. Cl.³ G11B 21/24, 5/56, 21/10

U.S. Cl. 360-109

7 Claims



1. A rotary support apparatus for magnetic heads which record and reproduce signals on magnetic tape, comprising two vibrators each of said vibrators supporting one of said heads, said vibrators formed respectively by bonding together two piezoelectric vibrator elements having a hemi-ring shape, the polarization axes of said elements being in parallel with the direction of the element thickness, said vibrators operating in a bending mode, and a cylindrical rotator supporting said vibrators.

4,295,173

THIN FILM INDUCTIVE TRANSDUCER


Lubomyr T. Romankiw, Briarcliff Manor, and David A. Thompson, South Salem, both of N.Y., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Oct. 18, 1979, Ser. No. 83,182

Int. Cl.³ G11B 5/12, 5/20, 5/22

U.S. Cl. 360-125

6 Claims



1. A thin film inductive transducer for recording and reading magnetic transitions on a selectable one of a plurality of tracks on a magnetic recording medium, said transducer being of the

type comprising two layers of a magnetic material forming a yoke structure that is activated by a conductor coil characterized in that

said yoke structure adjacent its one end comprises a pole tip region including a portion which is of a predetermined substantially constant width and a preselected substantially constant thickness, said predetermined width not exceeding the width of a track on the medium, said pole tip region extending a relatively short distance normal to the magnetic medium, thereby to maximize resolution of transitions during recording, and

said yoke structure comprises a back region which joins said pole tip region and increases in width from said predetermined width and has a back gap adjacent its wider end, the thickness of the layers of magnetic material in said back region being greater than the thickness of those layers in said portion of said pole tip region, thereby to oppose saturation of the yoke structure with applied current and enhance efficiency of the transducer by increasing the cross-sectional area of the yoke structure.

4,295,174

MULTI-SERIES GROUP CAPACITOR BANK PROTECTION EQUIPMENT


Charles A. Peterson, Van Buren, and Louis C. Grove, Jr., Bloomington, both of Ind., assignors to Westinghouse Electric Corp., Pittsburgh, Pa.

Filed May 29, 1979, Ser. No. 43,531

Int. Cl.³ H02H 7/16

U.S. Cl. 361-16

7 Claims



1. Capacitor apparatus comprising:
- a plurality of capacitor units in a bank arranged in a plurality of series groups with a plurality of units in parallel with each other within each series group;
- a fuse means connected with each capacitor unit; bypass means connected across a plurality of said series groups, said bypass means having a predetermined protection level sufficient to protect said capacitor units against transients to which said bank is subjected; and
- voltage limiter means connected individually across each of said series groups and having a predetermined protection level higher than that of said bypass means, said voltage limiter means operable to temporarily bypass a series group upon one of said fuse means of one of said units clearing due to conditions not affecting said bypass means.

4,295,175

PILOT WIRE RELAY PROTECTION SYSTEM FOR ELECTRICAL DISTRIBUTION NETWORKS

Daniel E. Cordray, Media, Pa., assignor to General Electric Company, Philadelphia, Pa.

Filed Apr. 21, 1980, Ser. No. 142,512

Int. Cl.³ H02H 7/26

U.S. Cl. 361-69


13 Claims

1. A pilot wire relay protection system for protecting a section of a high voltage network located between first and second circuit breakers and comprising at least a first and a

second transmission line each constituting a phase of said network, said pilot wire relay protection system detecting and responding to phase-to-phase faults, phase-ground faults and phase-phase-ground faults that may occur within the protected section by detecting and responding to an excessive differential current existing between a first and a second end of said protected section, said pilot wire relay protection system comprises:

a plurality of current sensors each coupled to a transmission line and arranged into a first group located at the first end of said protected section for respectively developing coupled currents representative of the transmission-line currents flowing at said first end of said protected section and a second group located at the second end of said protected section for respectively developing coupled currents representative of currents flowing at the second end of said protected section;

said first and second groups of current sensors having at least a first, a second, and a third current sensor respectively coupled to the first, the second, and the combination of the first and second transmission lines, said third current sensor developing a coupled current representative of the sum of currents flowing within the first and the second transmission lines at said third current sensors, so that upon the occurrence of a phase to phase fault within said protected section causing a relatively high current to flow within said protected section, said coupled current from the third current sensor will be representative of the dif-



ference between the transmission-line currents at said third current sensor flowing toward and away from the location of the fault, and such that the coupled current from the third current sensor will be substantially unchanged by the relatively high current flowing within either of the transmission lines of said protected section during the phase to phase fault, whereby said third current sensors remain unaffected by said phase-phase fault and thus able to provide a coupled current representative of the currents flowing within said transmission lines upon a simultaneous or subsequent occurrence of a phase-ground fault within said protected section;

each of said first, second, and third current sensors having a first and a second terminal, said first and said second current sensors of each group further having their second terminal connected together;

a first pilot relay coupled to said first and second terminals of each of the current sensors of said first group;

a second pilot relay coupled to said first and second terminals of each of the current sensors of said second group;

each of said pilot relays being responsive to coupled current from its associated current sensors for generating a first output signal representative of the composite of the current coupled from its associated first, second, and third current sensors;

pilot wire means comprising first and second conductors for coupling said first output signals together;

each of said first and said second pilot relays having further means for generating a second output signal if the current

flowing within said first and said second conductors and the voltage difference between said first and said second conductor exceed predetermined limits; and

means adapted to couple said second output signal of said first and said second pilot relays to said first and said second circuit breakers for causing said circuit breakers to disconnect the protected section from the remainder of the power network if the differential current between said first and said second ends of said protected section exceeds a predetermined limit.

4,295,176

SEMICONDUCTOR INTEGRATED CIRCUIT PROTECTION ARRANGEMENT


Norman C. Wittwer, Oldwick, N.J., assignor to Bell Telephone Laboratories, Incorporated, Murray Hill, N.J.

Filed Sep. 4, 1979, Ser. No. 72,139

Int. Cl.³ H02H 9/04

U.S. Cl. 361-91

8 Claims



1. Semiconductor apparatus comprising an overvoltage protection arrangement for a multiplicity of MOSFET circuits (16, 26, . . . 96) integrated in a single semiconductor body at a first major surface thereof, characterized by means for connecting a node (16.5, 26.5, . . . 96.5) of each of said circuits through the high current path of an auxiliary transistor, (T₁), integrated in said semiconductor body to an electrode in wide area contact with a second opposed major surface of said body, and with a common reference voltage metalization line (101) connected (18, 28, . . . 98) to each said circuit for providing the reference voltage thereto, said means including a separate unidirectional current inhibiting device (17, 27, . . . 97) connected between each said node (16.5, 26.5, . . . 96.5) and the common line (101), the common line being connected through bidirectional current conducting means (102) to the high current path of the auxiliary transistor.

4,295,177

CONTROL CIRCUITS FOR SOLENOIDS

Richard G. Woodhouse, and Peter H. Salway, both of Birmingham, England, assignors to Lucas Industries Limited, Birmingham, England

Filed Aug. 7, 1979, Ser. No. 64,644

Claims priority, application United Kingdom, Aug. 24, 1978, 34442/78


Int. Cl.³ F02D 5/02; G05B 11/01

U.S. Cl. 361-154

7 Claims

1. A solenoid control circuit comprising semi-conductor switch means and a current sensing element in series with the solenoid between a pair of supply terminals, initiating means for turning on said switch means to initiate current flow in the solenoid, first means sensitive to said current sensing element for turning off said switch means when the solenoid current reaches a first predetermined level and second means sensitive to said current sensing element for turning the switch means on

and off to maintain the solenoid current at a second predetermined level lower than said first predetermined level, said second means sensitive to said current sensing element initially being overridden by said first means sensitive to the current



sensing element, said semi-conductor switching means including two separate first and second switching devices controlled respectively by said initiating means and by said first and second current sensitive means.

4,295,178

ELECTRODE ARRANGEMENT WITH INDIVIDUALLY CONNECTABLE AND DISCONNECTABLE ELECTRODES

Walter Spengler, Strehlgasse 23, CH-4105 Biel-Benken, Switzerland


Filed Dec. 10, 1979, Ser. No. 101,642

Claims priority, application Switzerland, Feb. 21, 1979, 1709/79

Int. Cl.³ H01T 19/04

U.S. Cl. 361-220

19 Claims



1. In an electrode arrangement for applying or removing an electrostatic charge to or from a surface and comprising a plurality of electrodes adapted to apply to or receive from the surface an electrostatic charge, and insulating body means mounting the plurality of electrodes in a predetermined arrangement for positioning in operative association with the surface to which the charge is to be applied or from which the charge is to be removed, the improvement in said arrangement in which each of said electrodes comprises

an electrode point carried by said insulating body means and projecting outwardly therefrom and adapted to be positioned adjacent said surface,

contact means carried by said insulating body means in spaced relation to said electrode point and adapted to be connected to an electrical supply source or to ground, and

connecting means carried by said insulating body means for selectively connecting and disconnecting said electrode point and said contact means, said connecting means comprising an electrically conductive bridging member electrically connected to one of said electrode point and said contact means and mounted for movement between an active position in which said bridging member is in electrical contact with the other of said electrode point and said contact means to bridge the space therebetween and to provide for the flow of an electrical current therebetween and an inactive position in which said bridging member is spaced from the other of said electrode point and said contact means, means operably associated with said bridging member for selectively moving said bridging member between said active and inactive positions, and displace-

able insulating means positioned in the path of travel of said bridging member from said inactive position to said active position for insulating said bridging member from the other of said electrode point and said contact means when said bridging member is in said inactive position while permitting movement of said bridging member to said active position.

4,295,179

ELECTRIC TEST EQUIPMENT HOUSING


Clifford D. Read, Almonte, Canada, assignor to Northern Telecom Limited, Montreal, Canada

Filed Dec. 18, 1979, Ser. No. 104,869

Int. Cl.³ H05K 5/06

U.S. Cl. 361-331

12 Claims



1. A housing for electrical or electronic test equipment made from waterproof material, having inner and outer skin layers which are relatively resiliently movable upon application of pressure, defining a chamber for containing electrical or electronic test set equipment and comprising a closed top, two sidewalls and a base, a rear defining an opening to admit the equipment into the chamber, and a front wall defining an aperture to the chamber, and a flap on said housing for closing the aperture, the flap being hinged at an upper edge for upward hinging movement away from the aperture.

4,295,180

WALL MOUNTABLE HOUSING FOR PROGRAMMABLE THERMOSTAT

Clifford W. Herron, 717 Via Bravo, Mesquite, Tex. 75150, and Robert J. Wunderlich, 961 Easton Pl., Dallas, Tex. 75218

Filed Jun. 4, 1980, Ser. No. 156,401

Int. Cl.³ H05K 7/20

U.S. Cl. 361-383

4 Claims

1. A wall mountable housing having multiple members which, together, enclose the electronic components of a programmable thermostat having switching controls, keyboard, and display elements, said housing comprising:

a generally rectangular rear panel comprising: means for attaching said rear panel to said wall;

at least one aperture whereby control wires pass through the rear panel and into said housing;


a first hinge element at an edge of said panel; and first detent dagger means whereby the rear panel is attachable to another housing member;

second detent dagger means whereby the electronic components are connectable to a housing member;

a generally rectangular face plate comprising: third detent dagger means whereby the face plate is connectable to a housing member;

an aperture whereby the switching controls and display elements are accessible;

an aperture whereby the display elements are viewable; and
 a second hinge element at an edge of said face plate;
 a door whereby switching controls and keyboard of the programmable thermostat are protected, said door comprising:
 latching means; and



a third hinge element at an edge of said door whereby, interacting with said first and second hinge elements, the door is pivotally connected to the attached face plate and rear panel;
 a window whereby the display elements are protected and viewable; and
 vents whereby air circulates through said housing.

4,295,181


MODULE FOR AN INTEGRATED CIRCUIT SYSTEM
 Richard R. Chang, Richardson; Gene A. Frantz, and William R. Hawkins, both of Lubbock, all of Tex., assignors to Texas Instruments Incorporated, Dallas, Tex.

Filed Jan. 15, 1979, Ser. No. 3,449

Int. Cl.³ H05K 7/10

U.S. Cl. 361—395

9 Claims



1. A modular electronic device comprising:
 - (a) housing means of an insulative material defining an internal chamber, said housing means including parallel planar first and second major surfaces, side walls and end walls;
 - (b) one of said side walls having an elongated slot of predetermined width extending inwardly along the entire length of the side wall and along adjacent portions of the end walls and communicating with the internal chamber defined by said housing means;
 - (c) a side wall oppositely positioned from said elongated slot including an integral projection extending therefrom with an outwardly opening recess for receiving an implement to facilitate removal of said housing means from an installed position within an electronic apparatus; and
 - (d) electronic device means mounted within the internal chamber of said housing means and completely enclosed thereby, said electronic device means including electronic circuit means and a plurality of electrical contacts connected to said electronic circuit means for coupling said electronic circuit means to an external apparatus, said contacts being disposed in substantial alignment with the

slot in said side wall of said housing means, said electronic circuit means and said plurality of electrical contacts being accessible from the exterior of said housing means only via the slot in said side wall, the width of said slot being sufficiently small so that the electronic circuit means and electrical contacts are not accessible to a human finger or other object of comparable or larger dimensions, thereby preventing wanton contact and tampering with the electronic circuit means and electrical contacts.

4,295,182

INTERCONNECTION ARRANGEMENTS FOR TESTING MICROELECTRONIC CIRCUIT CHIPS ON A WAFER
 Russell C. Aubusson, Broxbourne, and Richard J. Gledhill, London, both of England, assignors to The Secretary of State for Industry in Her Britannic Majesty's Government of the United Kingdom of Great Britain and Northern Ireland, London, England


Continuation of Ser. No. 948,195, Oct. 2, 1978, abandoned. This application Feb. 11, 1980, Ser. No. 120,035

Claims priority, application United Kingdom, Oct. 3, 1977, 40896/77

Int. Cl.³ H01L 27/00

U.S. Cl. 361—400

6 Claims



1. In a circuit configuration for use in testing microelectronic circuit chips, said circuit configuration being of the type comprising a flat wafer having non-adjacent opposite physical edges and thereon within the region bounded by said physical edges an array of microelectronic circuit chips to be tested, each of the chips on said wafer comprising a digital circuit which processes digital information and to transfer digital information and control signals from a set of input connections on the chip to one of a plurality of sets of output connections on the chip selected by a switching circuit within the digital circuit, each set of output connections being connected to input connections of an adjacent chip on said wafer in accordance with the operation of the switching circuit thereby to set up a chain of interconnected sound chips in said array or said surface on said wafer which extends from a selected sound first chip and which bypasses faulty chips on said wafer, the improvement wherein said circuit configuration includes electrical connections which directly connect an output connection of each chip immediately adjacent a first physical edge of the said flat wafer to the input connection of a different chip adjacent a second physical edge of the said flat wafer whereby all chips behave electrically as though the surface of said flat wafer were unbounded in a direction transverse to said first and second edges and whereby the said selected first chip in said chain of interconnected chips is located immediately adjacent one of the physical edges of said flat wafer.

4,295,183


THIN FILM METAL PACKAGE FOR LSI CHIPS
 Ekkehard F. Miersch, Boeblingen, Fed. Rep. of Germany, and Lubomyr T. Romankiw, Briarcliff Manor, N.Y., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Jun. 29, 1979, Ser. No. 53,497

Int. Cl.³ H05K 1/16

U.S. Cl. 361—403

7 Claims



1. In an electronic chip carrier, a substrate with pad areas thereon for connection to a thin film, integrated circuit chip, a said chip connected to said pad areas, said substrate including a plurality of conductors coupled to said pad areas for electrical connection of said pads to various points, the improvement comprising connecting means for said chip to said pad areas by means of connections on the base of said chip, said conductors comprising a plurality of parallel conductive planar metallic sheets having large parallel surfaces with a layer of high dielectric material between adjacent ones of said sheets for providing high electrical capacitance and minimal inductive coupling therebetween, and at least one of said pads extending through at least one of said planar metallic sheets, each said pad being electrically insulated from said sheets through which it passes.

4,295,184


CIRCUIT BOARD WITH SELF-LOCKING TERMINALS
 Joseph A. Roberts, Hudson, N.H., assignor to Advanced Circuit Technology, Nashua, N.H.

Division of Ser. No. 934,702, Aug. 21, 1978, Pat. No. 4,223,435, which is a continuation-in-part of Ser. No. 808,808, Jun. 22, 1977, Pat. No. 4,107,836. This application Apr. 4, 1980, Ser. No. 137,449

Int. Cl.³ H05K 1/18

U.S. Cl. 361—406

11 Claims



1. A circuit board comprising in combination:
 - (a) a rigid dielectric carrier panel, said carrier panel having at least one aperture formed between opposite surfaces thereof;
 - (b) at least one electrically conductive circuit formed of a resiliently flexible metal, secured at least in part to said dielectric carrier panel, said electrically conductive circuit having (i) at least one integral termination which essentially surrounds said at least one aperture in said panel, said termination including (ii) a pair of dissimilar size generally L-shaped fingers disposed inwardly for a distance from the edge of said aperture;
 - (c) said termination including a frame section of cross-sectional thickness greater than the cross-sectional thickness of said electrically conductive circuit and a shoulder section of reduced cross-section thickness as compared with said

frame section, said shoulder section having a plan area greater than that of said at least one aperture, said shoulder being secured to said dielectric panel at least in part; and
 a dielectric material covering said conductive circuit patterns at least in part and secured to said dielectric panel, said dielectric material having (i) at least one aperture substantially corresponding in position to said at least one termination and (ii) overlaying and secured at least in part to said termination shoulder area.

4,295,185

FILAMENT MOUNT ASSEMBLY FOR MINIATURE INCANDESCENT LAMP, AND METHOD OF MANUFACTURE


Jack Martin, Paramus, N.J., assignor to Westinghouse Electric Corp., Pittsburgh, Pa.

Filed Sep. 26, 1979, Ser. No. 79,150

Int. Cl.³ F21M 3/30

U.S. Cl. 362—211

10 Claims



1. An electric incandescent lamp comprising:
 - (a) a sealed light-transmitting envelope containing a refractory wire filament having a coiled body portion that is terminated at each end by an uncoiled leg;
 - (b) a pair of substantially rigid lead-in conductors extending into said envelope and having end segments that are disposed in abutting end-to-end relationship with the respective legs of the filament and form therewith a pair of filament-conductor junctures, and
 - (c) means electrically and mechanically coupling the filament legs to the associated abutting end segments of the lead-in conductors comprising a pair of sleeve-like members of stiff electrically-conductive material that are disposed in overlying bridging relationship with the respective filament-conductor junctures, said sleeve-like coupling members being fastened to the abutted parts of the filament legs and lead-in conductors in overlapped engagement therewith and thereby securely locking the filament and lead-in conductors in operative relationship.

4,295,186

SLIT ILLUMINATING DEVICE

Muneharu Sugiura, Tokyo, and Seiji Sagara, Kawasaki, both of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan

Continuation-in-part of Ser. No. 948,399, Oct. 4, 1978, abandoned. This application Oct. 26, 1978, Ser. No. 954,760

Claims priority, application Japan, Oct. 12, 1977, 52-122172


Int. Cl.³ F21V 7/12; G03B 27/54

U.S. Cl. 362—217

3 Claims

1. A slit illuminating device for an image reproduction apparatus, which comprises:
 - (a) an original support table having a slit portion for slit illumination of an original;
 - (b) a tubular shaped light source arranged with its longitudinal axis spaced a predetermined distance from and parallel to a reference line which extends along the length of said slit; and

(c) a multi-surfaced mirror partially surrounding said light source and comprising a plurality of planar mirrors provided on both sides of a plane defined by the longitudinal axis of said light source and the reference line, wherein the respective length of each planar mirror, when viewed in cross-section defined by a plane perpendicular to the



reference line, is such that it transmits an effective bundle of light, as if emitted from a corresponding enlarged virtual image of said light source, to said slit portion, the size of the enlarged image being determined in accordance with an acceptable deviation of said light source from a predetermined mounting position.

4,295,187

ASSEMBLABLE CONTAINER


Norman S. Shemitz, Milford, Conn., assignor to Shem Safe Incorporated, Milford, Conn.

Continuation-in-part of Ser. No. 950,592, Oct. 12, 1978, Pat. No. 4,233,656. This application Feb. 27, 1980, Ser. No. 125,168

Int. Cl.³ F21V 1/06

U.S. Cl. 362—352

13 Claims



1. A support system for a container having a plurality of panels forming at least the sides and bottom of the container and connected together by the support system in a predetermined polyhedral configuration, each of the panels defining a plurality of corners; comprising, a plurality of collars, each collar being adapted to extend around a corresponding one of the panel corners, elastic connecting members connecting at least some of the collars together such that groups of opposing, adjacent collars on juxtaposed panels are connected together at their proximate ends by a said elastic member, and at least some of the said groups of collars are connected to other groups of collars which are spaced from the first said group by tensioned elastic members stretched between the said groups of collars, such that all of the collars are capable of being releasably held in place on their respective panels, to releasably hold all of the panels under the tension of the elastic members in the predetermined polyhedral configuration.

4,295,188 CONVERTER CIRCUIT PROVIDING ISOLATION AND LOAD SENSING


James E. Brunssen, Parsippany, N.J., assignor to Bell Telephone Laboratories, Incorporated, Murray Hill, N.J.

Filed Dec. 13, 1979, Ser. No. 103,271

Int. Cl.³ H02M 3/335

U.S. Cl. 363—21

9 Claims



1. A blocking oscillator converter comprising a transformer having: a primary winding circuit for connecting a DC source to current switching means; a secondary winding circuit for supplying a load; a tertiary winding circuit for regulating the voltage delivered to said load; and a drive winding circuit for operating said switching means characterized by means in said tertiary circuit for sensing current diverted from said secondary circuit and returned to said source, and means, coupled to said means for sensing, for controlling the operation of said switching means in response to said current.

4,295,189

APPARATUS AND METHOD FOR GENERATING WAVEFORMS WHICH ARE PARTICULARLY SUITABLE FOR A PWM-DRIVEN MOTOR


John T. Boys, Auckland, New Zealand, assignor to The University of Auckland, Auckland, New Zealand

Filed Dec. 4, 1979, Ser. No. 99,998

Int. Cl.³ H02M 1/08

U.S. Cl. 363—41

32 Claims



14. Apparatus for generating an n-phase pulse width modulated (PWM) waveform particularly adapted for energizing an n-phase electrical motor, wherein n is an integer, said apparatus comprising a source of n-phase sine wave signal, each phase having a fundamental frequency f, triangle waveform generating means for generating a triangle waveform of frequency mf from said n-phase sine wave signal wherein m is an integer, said triangle waveform having substantially linearly sloped, gradually increasing and decreasing edges, said triangle waveform generating means including detecting means for detecting when a segment of any of said n phases of said sine wave signal

is within a predetermined angular amount from a reference crossing level, and selecting means for selecting successive ones of said detected segments to synthesize said triangle waveform; and n comparing means, a respective comparing means being provided for each phase for comparing said triangle waveform to an associated phase of said sine wave signal to produce a pulse transition at each intersection of said triangle waveform and said associated phase of said sine wave.

4,295,190

BANK SELECTION IN NATURALLY COMMUTATED THYRISTOR CONTROLLED STATIC POWER CONVERTERS


Eric J. Stacey, Penn Hills, Pa., and Donal E. Baker, American Township, Lima County, Ohio, assignors to Westinghouse Electric Corp., Pittsburgh, Pa.

Filed Nov. 19, 1979, Ser. No. 95,899

Int. Cl.³ H02M 5/27

U.S. Cl. 363—162

13 Claims



4. A converter for generating from a multiphase AC voltage source a desired output waveform to be applied to a load, said converter comprising:

a naturally commutated power circuit including a plurality of thyristors arranged in positive and negative banks inserted between the AC voltage source and the load, the thyristors in each thyristor bank being arranged in pulse groups interconnected by interphase transformers; control means for firing said thyristors sequentially to generate said desired output waveform which is applied to said load; means for determining which thyristor bank is carrying the load current; means for determining when the current in each pulse group of the nonload current carrying bank goes to zero; and means for inhibiting the firing of thyristors in each pulse group of the nonload current carry bank in response to zero current therethrough.

4,295,191

PROGRAMMABLE CONTROL SYSTEM

Worley C. Wilson, Ft. Lauderdale, Fla., assignor to Telemetry Controls, Inc., Miami, Fla.

Filed Feb. 14, 1980, Ser. No. 121,446

Int. Cl.³ G05B 19/04; H01H 43/00

U.S. Cl. 364—104

6 Claims

1. An electronic programmable system for controlling the operation of remotely located equipment comprising:


(a) time base generating means including means for cyclically providing a plurality of output timing signals corresponding to a predetermined number of equally spaced-apart points of a preselected time base;

(b) controllable data transfer means including first data transfer means and second data transfer means;

(c) programmable connection means including a plurality of controllable circuit paths operatively connected between said time base generating means and said first data transfer

means and a plurality of controllable circuit paths operatively connected between said time base generating means and said second data transfer means, said programmable connection means including user-accessible panel means for receiving insertable program pins which effect actuation of selected ones of said controllable circuit paths thereby coupling selected ones of said output timing signals to said first data transfer means and to said second data transfer means;

(d) data transfer control means for selectively enabling said controllable data transfer means, said data transfer control means including means for generating a first data transfer control signal, a second data transfer control signal and a strobe signal, wherein said first data transfer control signal is coupled to said first data transfer means and said second



data transfer control signal is coupled to said second data transfer means and said strobe signal is coupled to said first and second data transfer means, said first data transfer means being enabled when said first data transfer control signal, said strobe signal and one of said coupled output timing signals are coincidentally applied to said first data transfer means, said second data transfer means being enabled when said second data transfer control signal, said strobe signal and one of said coupled output signals are coincidentally applied to said second data transfer means; and

(e) programmable switching means operatively connected to said controllable data transfer means and responsive to said transferred output timing signals including means for generating a switching control signal for controlling the operation of said remotely located equipment.

4,295,192

ROW ADDRESS MEMORY MAP OVERLAP


Brewster J. Porcella, Tustin, Calif., assignor to Sperry Rand Corporation, New York, N.Y.

Filed Apr. 13, 1979, Ser. No. 29,697

Int. Cl.³ G11C 13/00

U.S. Cl. 364—200

16 Claims



1. A memory mapping apparatus comprising, a source of original address information wherein said original address information is comprised of a specified number of bits; memory map means connected to receive a first portion of said original address information directly from said source;

multiplexer means connected to receive a different portion of said original address information directly from said source; memory means connected to said memory map means to concurrently supply memory information directly to said memory map means; and means connected between said memory map means and said multiplexer means and operative to supply map information to said multiplexer means from said memory map means, said multiplexer means providing new address information representative of said map information and said different portion of said original address information wherein said new address information includes mapped information from said memory via said memory map means.

4,295,193

MACHINE FOR MULTIPLE INSTRUCTION EXECUTION



James H. Pomerene, Chappaqua, N.Y., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Jun. 29, 1979, Ser. No. 53,567

Int. Cl.³ G06F 7/00

U.S. Cl. 364—200

6 Claims



6. In apparatus for computing instructions of a given type compiled into groups of n , where n is an integer ≥ 4 , instructions, with no more than one instruction being other than said given type and said one instruction being at a fixed position from one group to the next, with two data fetches and one branch instruction fetch and one store operation being permit-

ted in a group, with any branch instruction fetch being the last instruction in the group, the combination comprising:

- an instruction cache wherein said groups of n instructions including branch instructions are stored;
- a data cache containing data necessary to perform said instructions;
- an n stage register in which a group of n instructions at a time is stored from said instruction cache, with any instruction other than said given type being stored in a predetermined one of said n stages;
- a first gating means responsive to the instruction stored in said predetermined one of said n stages for determining if the instruction is of said given type, and if so permitting same to be processed by said apparatus;
- a second gating means responsive to each of said n instructions for determining which instructions, if any, contains a branch instruction fetch;
- a third gating means responsive to each of said n instructions for determining which instruction, if any, contains a first data fetch;
- a fourth gating means responsive to each of said n instructions for determining which instruction, if any, contains a second data fetch;
- a group of general purpose registers in which addresses and data needed for executing said instructions are stored;
- an instruction address generation means operative with said general purpose registers and responsive to said second gating means for initiating a branch instruction fetch from said instruction cache;
- a first data address generation means operative with said data cache and general purpose registers and responsive to said third gating means for fetching addresses and data;
- a second data address generation means operative with said data cache and general purpose registers and responsive to said fourth gating means for fetching addresses and data; and
- n execution logic means, each operative with one of said n stages of said n stage register and said first and second data and address generators for concurrently executing the called for valid instructions of said given type including called for data fetches and store operations, if any, with the address and data called for by said store operation being provided to said data cache.

4,295,194

ADAPTER UNIT FOR USE IN A DATA PROCESSING SYSTEM FOR PROCESSING A VARIETY OF REQUESTS


Boyd E. Darden, St. Petersburg, Fla., and Henry F. Hartley, Lowell, Mass., assignors to Honeywell Information Systems Inc., Waltham, Mass.

Filed Sep. 6, 1979, Ser. No. 73,056

Int. Cl.³ G06F 9/46

U.S. Cl. 364—200

31 Claims



1. A data processing system including a central processing unit and a controller coupled in common to a bus, said controller having a number of ports connected to a corresponding number of adapter units, one of said adapter units comprising: a data bus; an address bus;

microprocessing means coupled to receive task word commands from said controller coded to specify a number of time of day operations and including time of day information signals, said microprocessing means being coupled to said data and address buses;

random access memory means coupled to said data and address buses, said memory means being organized into a plurality of sections, each section having a plurality of locations, a first section corresponding to a first buffer, a second section corresponding to a second buffer, a third section corresponding to a third buffer and a fourth section corresponding to a timer control section;

a programmable read only memory means coupled to said data and address buses, said read only memory means including a plurality of locations for storing a plurality of timer control sequences for processing different ones of said commands; free running time of day means for generating and storing time of day values, said time of day means being coupled to said data bus and operatively coupled to said address bus; and, timer module means coupled to said microprocessing means and to said data and address buses, said module means including a number of programmable cyclic timer circuits, each timer circuit including control and counter registers operatively coupled to said address and data buses;

said microprocessing means being operative in response to one of said task commands to reference a first predetermined one of said plurality of timer control sequences for generating signals to load predetermined time of day information signals received from said controller required for executing the time of day operation specified by said command into a selected one of said buffers and for generating signals on said address and data bus lines for loading said timer control and counter registers of one of said timer circuits with control signals read out from said fourth section specifying a timer mode of operation and a predetermined time interval in accordance with said one command, said timer module means being conditioned by said control signals to generate an interrupt at the end of said predetermined time interval to said microprocessing means for detecting the completion of the time of day operation specified by said one command.

4,295,195

RADIOGRAPHY

Godfrey N. Hounsfield, Newark, England, assignor to E M I Limited, Hayes, England


Filed Oct. 24, 1979, Ser. No. 87,669

Claims priority, application United Kingdom, Oct. 24, 1978, 41710/78

Int. Cl.³ G06F 15/42; G01N 23/00

U.S. Cl. 364—414

3 Claims



1. A CT scanner including a source of a substantially planar, divergent spread of penetrating radiation, the radiation propa-

gating across a patient position, detector means sensitive to the radiation and disposed to receive the radiation emergent from said patient position; the detector means including a plurality of detector devices arranged to receive radiation element from said patient position along respective, substantially linear paths and to generate respective electrical output signals indicative of the amounts of radiation so received, scanning means causing said source and said detector means to move angularly around the patient position about a common axis of rotation with the spread of radiation remaining in a plane intersected substantially orthogonally by said axis, and processing means for operating upon output signals generated by said detector means throughout the angular movement to generate a representation of the variation of attenuation of said radiation from place to place over said patient position and in the said plane; the scanning permitting said detector means to generate output signals relating to many sets of paths distributed across the patient position, each set being disposed at a respective attitude to the patient position and consisting of several sub-sets of paths, the radiation propagating along each path of any given sub-set being received by a respective detector device and that propagating along the paths of other sub-sets of the same set being received by different detectors; overlap zones existing between each pair of adjacent sub-sets wherein any two detector devices associated with the paths included in adjacent sub-sets receive radiation along several common paths, the processing means including components operating upon the respective signals generated by the two detector devices in respect of said common paths to generate a respective normalized signal, containing contributions from both detectors, in respect of each of said common paths; each of said normalized signals being generated by comparing output signals relating to different numbers of the paths in the overlap zone for common paths at different positions within the overlap zone, the number of paths involved in the comparison varying, across the overlap zone, from a minimum for common paths at one edge thereof through a maximum in the center thereof to a minimum at the other edge thereof.

4,295,196

FRACTIONAL DISTILLATION COLUMN CONTROL


Danny L. Furr, Broken Arrow, Okla., assignor to Phillips Petroleum Company, Bartlesville, Okla.

Filed Jul. 2, 1980, Ser. No. 165,463

Int. Cl.³ E01D 3/42

U.S. Cl. 364—501

3 Claims




1. Apparatus comprising:
a fractional distillation column means;
a first heat exchanger means;
means for supplying a feed stream through said first heat exchanger means to said fractional distillation column means;
means for withdrawing a pump around stream from a first upper portion of said fractional distillation column means and for passing said pump around stream through said first heat exchange means to a second upper portion of said

fractional distillation column means, wherein said second upper portion is above said first upper portion;
 a first cooling means;
 an overhead accumulator means;
 means for withdrawing an overhead vapor stream from an upper portion of said fractional distillation column means and for passing said overhead vapor stream through said first cooling means to said overhead accumulator means;
 means for withdrawing a liquid stream from said overhead accumulator means, for returning the first portion of the thus withdrawn liquid stream to a third upper portion of said fractional distillation column means as an upper external reflux, and for removing a second portion of the thus withdrawn liquid stream as a product stream, wherein said third upper portion is above said first upper portion;
 means for manipulating the flow rate of said pump around stream;
 means for manipulating the flow rate of said upper external reflux;
 means for calculating a first signal representative of the actual flow rate of the internal reflux in an upper portion of said fractional distillation column means;
 means for calculating a second signal representative of the flow rate of the internal reflux in the upper portion of said fractional distillation column means required to maintain a desired product specification for said product stream;
 means for comparing said first signal and said second signal to thereby determine if the internal reflux flow rate in the upper portion of said fractional distillation column means should be increased or decreased;
 means for determining if the flow rate of said pump around stream can be increased;
 means for determining if the flow rate of said upper external reflux can be decreased;
 means for calculating a third signal representative of the flow rate of said pump around stream required to make said first signal substantially equal to said second signal;
 means for establishing a fourth signal representative of the highest desired flow rate of said pump around stream;
 means for establishing a fifth signal representative of the flow rate of said upper external reflux required to make said first signal substantially equal to said second signal; and
 means for establishing a sixth signal representative of the lowest desired flow rate of said upper external reflux, wherein the flow rate of said pump around stream is manipulated in response to said third signal and the flow rate of said upper external reflux is manipulated in response to said sixth signal if it is desired to increase the flow rate of said internal reflux and it is determined that the flow rate of said pump around stream can be increased or if it is desired to decrease the flow rate of said internal reflux and it is determined that the flow rate of said upper external reflux cannot be decreased, and wherein the flow rate of said pump around stream is manipulated in response to said fourth signal and the flow rate of said upper external reflux is manipulated in response to said fifth signal if it is desired to increase the flow rate of said internal reflux and it is determined that the flow rate of said pump around stream cannot be increased, or if it is desired to decrease the flow rate of said internal reflux and it is determined that the flow rate of said upper external reflux can be decreased.

4,295,197
INFILTRATION-INFLOW SEWER LINE ANALYZER
 Peter D. Petroff, 4102 Piedmont Dr., Huntsville, Ala. 35802
 Division of Ser. No. 905,196, May 12, 1978, Pat. No. 4,211,111, which is a division of Ser. No. 811,557, Jun. 30, 1977, Pat. No. 4,116,061, which is a division of Ser. No. 602,974, Aug. 8, 1975, Pat. No. 4,070,563. This application Dec. 17, 1979, Ser. No. 104,540
 The portion of the term of this patent subsequent to Jan. 24, 1995, has been disclaimed.
 Int. Cl.³ G01F 23/14

U.S. Cl. 364—510


5 Claims



1. A system of measurement of flow gains between ends of a sewer line, said line extending between an upstream manhole and a downstream manhole, and having a first sewer pipe with an exit end at the downstream manhole, and there being a second sewer pipe having an exit feeding said upstream manhole, comprising:
 first and second monitoring assemblies, said first monitoring assembly being positioned in the end region of said first sewer pipe, and said second monitoring assembly being positioned in an end region of said second sewer pipe, and wherein each monitoring assembly comprises:
 liquid level sensing means for sensing liquid level and providing as an output a signal which is a function of liquid level,
 mounting means for mounting and positioning said liquid level sensing means in said end regions of said sewer pipes, and
 sampling and recording means for periodically and synchronously, as between monitoring assemblies, and responsive to said liquid level sensing means, sampling and recording time identified said signals over a selected period of time;
 conversion means responsive to selected recorded signals for converting said signals into liquid flow rates;
 computation means responsive to said conversion means and dry and rainy day samples of values from each of said monitoring assemblies supplied said conversion means for (1) determining the difference between like timed, time of day, dry and rainy day flows from said first sewer pipe, (2) determining the difference between like timed, time of day, dry and rainy day flows from said second sewer pipe, and (3) determining the differences between said difference flows obtained as per (1) and (2) of this paragraph; and
 control means for selectively fetching samples from said sampling and recording means and placing same in said conversion means, whereby readings and computations may be made at selected times, and thereby measurements may be made during rainfalls which are representative of inflow into said pipe, and measurements made following rainfalls are representative of infiltration into a said pipe.

4,295,198
AUTOMATIC PRINTED CIRCUIT DIMENSIONING, ROUTING AND INSPECTING APPARATUS
 Robert K. Copeland, Pennington, and Richard J. Dimaggio, Trenton, both of N.J., assignors to Cogit Systems, Inc., Princeton, N.J.
 Filed Apr. 2, 1979, Ser. No. 26,436
 Int. Cl.³ G05B 19/42; H04N 7/18
 U.S. Cl. 364—515

24 Claims




22. An automatic inspecting apparatus for scanning a first object and comparing certain features of said first object to certain features of a second object, said apparatus comprising:
 means for supporting said first object;
 means for scanning said first object and producing a first set of scan data representative thereof;
 processing means for processing said first set of scan data to detect said certain features of said first object, said processing means producing a first set of processed data representative of said features of said first object, said first set of processed data being smaller in volume than said first set of scan data;
 comparison means for comparing said first set of processed data against a pre-stored second set of processed data representative of said certain features of said second object and producing an electrical output representative of said comparison; and
 reporting means for producing an output representative of the output from said comparison means.

4,295,199
AUTOMATIC FLUOROMETER AND DATA PROCESSOR FOR PERFORMING FLUORESCENT IMMUNOASSAYS
 Robert E. Curry, Novato, and Michael G. Simonsen, San Rafael, both of Calif., assignors to Bio-Rad Laboratories, Inc., Richmond, Calif.

Filed Oct. 22, 1979, Ser. No. 86,917
 Int. Cl.³ G01N 33/16

U.S. Cl. 364—555

44 Claims



1. A fluorescence immunoassay apparatus for quantitating

relatively small amounts of a clinically significant composition comprising:


transparent means including a member constructed of a transparent material and defining therein a hollow cell for holding a liquid sample including fluorescent particles;
 means for flowing the sample into and out of the cell including an inlet to and an outlet from the cell;
 a sample probe;
 intake tubing fluidly communicating the probe with the inlet;
 discharge tubing fluidly communicating the outlet with a sample discharge point;
 a pump located downstream of the outlet for intermittently flowing a sample from the probe to the cell, for maintaining the sample in the cell for a period of time, and for thereafter removing the entire sample from the cell and the intake tubing and replacing the removed sample with a fresh sample;
 whereby the sample is not subjected to the flow inducing action of the pump until after it has passed the cell;
 a light source for generating a stable light beam focused on the sample;
 whereby the light beam causes fluorescent emissions by the particles in the sample, the intensity of which emissions is a function of the intensity of the light beam and the quantity of fluorescent particles in the sample; and
 means in optical communication with the transparent means for detecting photons resulting from fluorescent emissions by the particles when excited by the light beam;
 whereby the number of photons detected by the photon detecting means is a function of the number of fluorescent particles in the sample.

4,295,200
AUTOMATIC PARTICLE ANALYZING SYSTEM
 Richard F. Johnson, Vero Beach, Fla., assignor to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Nov. 2, 1979, Ser. No. 90,787
 Int. Cl.³ G01N 15/02

U.S. Cl. 364—555

14 Claims



1. An automated system for analyzing particulate matter comprising:
 a supply of said particulate matter,
 a horizontally-disposed wheel-like platen,
 means for feeding a portion of said supply particles to said platen,
 means for distributing said portion in a single-file arrangement on the peripheral edge portion of the platen,
 means for rotatably driving said platen,
 means for scanning a frame area of said peripheral edge and for generating an electrical scan output, said scanned frame area being fixed relative to platen rotation, and
 signal generating means operatively coupled to said scanned output and having an output coupled to said platen drive,

said generating means being operatively responsive to said scanned output for stopping said platen rotation when one of said particles is within said frame area whereupon a stationary particle is sequentially viewed and for resuming said rotation upon completion of said sequentially viewing whereupon another particle is carried into said frame area for viewing.

4,295,201

ELECTRONIC DISTANCE-MEASURING INSTRUMENT
Klas R. Wiklund, Täby, Sweden, assignor to AGA Aktiebolag, Lidings, Sweden


Filed Aug. 21, 1979, Ser. No. 68,440

Claims priority, application Sweden, Apr. 27, 1979, 7903749; Jun. 18, 1979, 7905325

Int. Cl.³ G01B 7/14

U.S. Cl. 364—561

7 Claims



1. An electronic distance measuring instrument comprising an electronic distance meter; vertical angle determining means for establishing at least one vertical angle; horizontal angle determining means for establishing the angle between the instrument and the horizontal plane; and calculating means for trigonometrical transformations of input signals received by the instrument, said horizontal angle determining means comprising a terrestrial magnetic field detector comprising at least two detector units which are fixedly mounted in the instrument and which are oriented in different directions so that at least two components of the magnetic flux in an instrument-based coordinate system can be established with the aid of the detector units; said calculating means including means for converting the components of the terrestrial magnetic field from the instrument-based coordinate system to an earth-based coordinate system using an input signal from the vertical angle determining unit; for calculating the direction of the terrestrial magnetic field in a horizontal plane; and for calculating the horizontal distance from fixed point to a measuring point based on the said input signals and the data obtained from said electronic distance meter.

4,295,202

HEXADECIMAL DIGIT SHIFTER OUTPUT CONTROL BY A PROGRAMMABLE READ ONLY MEMORY
Thomas J. Joyce, Burlington, and David E. Cushing, Chelmsford, both of Mass., assignors to Honeywell Information Systems Inc., Waltham, Mass.

Filed Nov. 9, 1979, Ser. No. 92,810


Int. Cl.³ G06F 7/48

U.S. Cl. 364—748

20 Claims

1. A shifter unit for performing scientific arithmetic operations comprising:
shifting means for receiving a mantissa and responsive to a plurality of shift signals for generating a plurality of shifter signals indicative of said mantissa shifted a number of positions specified by said shift signals;
multiplexer means coupled to said shifting means for receiving said shifter signals for transfer to an output;
read only memory means responsive to said plurality of shift

signals for generating a plurality of enabling signals in a first state and a plurality of enabling signals in a second state, said multiplexer means being coupled to said read only memory means and responsive to said enabling signals



nals in said first state for transferring said plurality of shifter signals, and responsive to said enabling signals in said second state for transferring characters having a value of ZERO to said output.

4,295,203

AUTOMATIC ROUNDING OF FLOATING POINT OPERANDS


Thomas F. Joyce, Burlington, Mass., assignor to Honeywell Information Systems Inc., Waltham, Mass.

Filed Nov. 9, 1979, Ser. No. 92,907

Int. Cl.³ G06F 7/48

U.S. Cl. 364—748

7 Claims



1. Apparatus for performing a scientific arithmetic rounding operation comprising:

memory means for storing a plurality of mantissas and generating a plurality of mantissa signals indicative of the binary value of said plurality of mantissas;
shifter means coupled to said memory means and responsive to a first plurality of mantissa signals for generating shifted mantissa signals;
arithmetic logic means coupled to said memory means and said shifter means and responsive to a second plurality of mantissa signals and said shifted mantissa signals for performing a predetermined arithmetic operation during a first cycle of operation for generating a plurality of result mantissa signals indicative of a binary result of said predetermined arithmetic operation and a normalization and an overflow signal, said plurality of result mantissa signals being stored in said memory means;
rounding means coupled to said arithmetic logic means for receiving a first signal and a second signal of said plurality of result mantissa signals, said rounding means being responsive to a rounding signal and a length signal in a first

state for selecting said first signal, and said length signal in a second state for selecting said second signal for generating a round request signal;

control means coupled to said rounding means and responsive to said round request signal for generating a round control signal, said rounding means being responsive to said round control signal and said rounding signal for rounding said binary result during a second cycle of operation;

said control means being further coupled to said arithmetic logic means and responsive to said normalization signal for initiating a normalization cycle during said second cycle of operation, said rounding means being responsive to said round control signal and said rounding signal for rounding said binary result during said normalization cycle,

said control means being responsive to said overflow signal for initiating an overflow mantissa correction cycle during said second cycle of operation, said rounding means being responsive to said round control signal and said rounding signal for rounding said binary result during said overflow mantissa correction cycle.

4,295,204

PROGRAMMABLE CORRELATOR


Drew E. Sunstein, 19 Parkhurst Dr., Nashua, N.H. 03060

Filed May 31, 1979, Ser. No. 44,392

Int. Cl.³ G06G 7/19

U.S. Cl. 364—824

6 Claims



1. A programmable correlator for correlating a sampled information signal with a programmable reference signal, such correlator comprising a plurality of correlator stages connected in cascade, each stage including:

- (a) an information register, having an input for receiving at a given instant in time a sample of the information signal, a first output related to the signal stored in the register, and a second output also related to the signal stored in the register;
- (b) a reference register, having an input for receiving a signal related to the programmable reference signal, and an output related to the stored signal;
- (c) a multiplier, having a first input connected to the first output of the information register, a second input connected to the output of the reference register, and an output related to the product of the signals present at the multiplier's first input and its second input;
- (d) first means, for transferring the sample of the information signal, from the second output of the information register in such stage, to the input of the information register in the next successive stage, such transfer being accomplished without undesirable amounts of changes in the signal stored in the reference register;
- (e) second means, for summing the outputs of the multipliers in each stage; and
- (f) third means, distinct from the reference register, for distributing one of a series of consecutive samples of a signal related to the reference signal to each reference

register of the device, so that collectively the reference registers have received all samples in the series.

4,295,205

SOLID STATE MASS MEMORY SYSTEM COMPATIBLE WITH ROTATING DISC MEMORY EQUIPMENT


George H. Kunstadt, 4450 La Barca, Tarzana, Calif. 91356

Filed Oct. 16, 1978, Ser. No. 951,711

Int. Cl.³ G06F 3/00; G06G 7/48

U.S. Cl. 364—900

6 Claims



1. A mass memory system, having a plurality of memory modules, other than rotating disc memories, compatible with memory equipment employing a disc memory controller designed to operate only with rotating disc memories and in conjunction with a computer, said system comprising:

means connected to a disc memory controller for providing signals simulating origin and sector signals like those which are transmitted from a rotating disc memory system and for transmitting said signals to a disc memory controller; and

memory module selecting means for selecting one of said memory module for a read or write operation, said memory module selecting means being connected to said means for providing signals simulating origin and sector signals like those which are transmitted from a rotating disc memory system and also being connected to said plurality of memory modules and being responsive to cessation of said simulated origin and sector signals to select one of said memory module, whereby said memory equipment designed to operate only with rotating disc memories is usable with solid state memories having a plurality of memory modules other than rotating disc memories.

4,295,206

DOCUMENT SORTING METHOD

John D. Cain, Kitchener, and Gary C. Lovie, Waterloo, both of Canada, assignors to NCR Canada Ltd.-NCR Canada Ltee, Mississauga, Canada

Filed Jun. 6, 1979, Ser. No. 45,820

Int. Cl.³ G06F 7/08


U.S. Cl. 364—900

8 Claims

2. In a data processing system, a method of sorting a plurality of documents into selected pockets of a sorter comprising the steps of:

building a record file of data from said documents in physical sequential order with each document containing a sort key thereon,
determining the number of different sort keys for said documents by arranging the record file of data in sort key numerical order, those document records in the record file having the same sort key being arranged in physical sequence,
assigning sort numbers to said record file of data in a manner wherein all documents with the same sort key will have the same sort number when sequentially read for ascend-

ing order and incrementing the sort number in ascending numerical order upon encountering a descending physical sequence order, and



transporting said documents to said selected pockets identified by sort numbers assigned to said record file of data.

4,295,207

DATA PROCESSING APPARATUS FOR RECEIVING AND DECODING WORDS IN WHICH DATA IS ENCODED BY PHASE REVERSALS OR NON-PHASE REVERSALS OF A SIGNAL OF A PREDETERMINED FREQUENCY

Martin L. Resnick, Chestnut Hill, Mass., assignor to GTE Laboratories Incorporated, Waltham, Mass.

Filed Nov. 14, 1979, Ser. No. 94,241

Int. Cl.³ G06F 3/05, 5/00

U.S. Cl. 364—900

21 Claims



1. A data processing apparatus for receiving and processing coded words, each word including, in succession, a reference bit, a start bit, and additional bits, said bits being encoded within a corresponding number of bit periods by a predetermined number of cycles of a signal of a predetermined frequency, said start bit being reversed in phase with respect to the phase of the reference bit to represent a first logic value and each of the additional bits being either reversed in phase or not reversed in phase with respect to the preceding bit thereby to represent a first logic value or second logic value, respectively, said apparatus comprising:

- an input arranged to receive each word;
- first sampling means arranged to take successive samples of each word received at the input;
- comparator means operative to compare samples taken by the first sampling means with frequency data representing a signal of the predetermined frequency and at least one approximation thereof;
- first means operative when samples produced by the first sampling means compare with the frequency data of the comparator means to produce a condition indicating the reception of a reference bit;
- second means operative following the aforesaid condition produced by the first means and when succeeding samples produced by the first sampling means do not compare with the frequency data of the comparator means to invert said samples;
- said comparator means being further operative to compare the inverted samples with the frequency data;
- third means operative when inverted samples compare with the frequency data of the comparator means to produce a condition indicating a phase reversal corresponding to a start bit of the sampled word;
- start means operative following the aforesaid condition

produced by the third means to establish a count representing a predetermined time period the expiration of which corresponds to a predetermined point in the next bit period following the start bit period;

second sampling means arranged to alter the count established by the start means and operative at the expiration of the predetermined time period to take successive samples of the word at the input;

fourth means operative for each successive bit period following the start bit period to establish a count representing the aforesaid predetermined time period the expiration of which corresponds to the predetermined point in the next bit period;



said second sampling means being further operative to alter the count established by the fourth means and operative at the expiration of the predetermined time period to take successive samples of the word at the input;

fifth means arranged for each bit period following the start bit period and following the establishing of each count representing the predetermined time period by the fourth means to determine the phase of the bit in the previous bit period relative to the reference phase, and operative if the phase is different from the reference phase to invert the samples taken by the second sampling means and if the

phase is the same as the reference phase to not invert the samples taken by the second sampling means;

said comparator means being further operative following each determination by the fifth means to compare the inverted or non-inverted samples of the fifth means with the frequency data;

sixth means operative if inverted or non-inverted samples of the fifth means in each bit period following the start bit period compare with the frequency data of the comparator means to produce an output of the second logic value;

seventh means operative if inverted or non-inverted samples of the fifth means in each bit period following the start bit period do not compare with the frequency data of the comparator means to invert the samples;

said comparator means being further operative to compare the inverted samples of the seventh means with the frequency data; and

eighth means operative if the inverted samples of the seventh means compare with the frequency data of the comparator means to produce an output of the first logic value.

4,295,208

SIGNALLING SYSTEM INCLUDING APPARATUS FOR GENERATING AND TESTING DATA AND COMMAND WORDS WITHIN FIRST AND SECOND MESSAGE INTERVALS

Robert A. Norbedo, North Andover, and Martin L. Resnick, Chestnut Hill, both of Mass., assignors to GTE Laboratories Incorporated, Waltham, Mass.

Filed Nov. 14, 1979, Ser. No. 94,245

Int. Cl.³ G06F 3/04, 11/30

U.S. Cl. 364—900

17 Claims

1. In a signalling system, apparatus comprising:

an input terminal;

an output terminal;

first means arranged during a first message interval to generate and apply data words in succession to the output terminal and to receive and test command words received in succession at the input terminal, each of said command words including flag data specifying the word as a command word, command data representing either a "send" command or a "retransmit" command, and other data, said first means comprising:

first test means operative to receive each command word at the input terminal and to test the command word to determine whether the word satisfies prescribed requirements of command words including whether the flag data specifies the word as a command word and the command data represents a "send" command or a "retransmit" command; and



send/retransmit means operative if a command word tested by the first test means satisfies the prescribed requirements of a command word and represents a "send" command to generate and apply a data word to the output terminal, and operative if a command word tested by the first test means satisfies the prescribed requirements of a command word and represents a "retransmit" command to reapply the data word last applied to the output terminal back to the output terminal; and

second means arranged during a second message interval to receive and test data words received in succession at the input terminal and to generate and apply command words in succession to the output terminal, each of said data words including flag data specifying the word as a data word and other data, and each of the command words including command data representing either a "send" command or a "retransmit" command, said second means comprising:

second test means operative to receive each data word at the input terminal and to test the data word to determine whether the data word satisfies prescribed requirements of a data word including whether the flag data specifies the word as a data word; and

third means operative if a data word tested by the second test means satisfies the prescribed requirements of a data

word to generate and apply a command word including command data representing a "send" command to the output terminal for requesting the next word, and operative if a data word tested by the second test means does



not satisfy the prescribed requirements of a data word to generate and apply a command word including command data representing a "retransmit" command to the output terminal for requesting the previous word.

4,295,209

PROGRAMMING AN IGFET READ-ONLY-MEMORY

William B. Donley, Kokomo, Ind., assignor to General Motors Corporation, Detroit, Mich.

Filed Nov. 28, 1979, Ser. No. 98,211

Int. Cl.³ G11C 17/00, 11/40

U.S. Cl. 365—178

2 Claims


1. A programmed read-only-memory comprising:

an array of programmable IGFETs on a semiconductor surface;

a silicon nitride coating on said surface, with apertures therein for electrically contacting all of said programmable IGFETs;

a glass coating on said silicon nitride coating, with apertures therein corresponding to said first-mentioned apertures

and additional apertures over channel regions of selected IGFETs;
said selected IGFETs having ion implanted channel regions



unaffected by gate operating voltage for said read-only-memory; and
conductors on said glass coating over said IGFETs through said first-mentioned and corresponding apertures.

4,295,210


POWER SUPPLY SYSTEM FOR MONOLITHIC CELLS
Herve Beranger, Fontainebleau; Claude Marzin, Mennecy; Dominique M. Omet, Corbeil, and Jean-Luc Peter, Ris-Orangis, all of France, assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Sep. 4, 1979, Ser. No. 71,826

Claims priority, application France, Nov. 30, 1978, 78 34434
Int. Cl.³ G11C 11/40

U.S. Cl. 365—227

3 Claims



1. In a monolithic memory having n word lines and an address decoder having n outputs, said monolithic memory being characterized by an improved bilevel powering system, said powering system including:

- n discrete current switch circuit means;
- each of said n current switch circuit means having an input and an output;
- each of said n current switch circuit means having its input connected to a predetermined one of said n outputs of said address decoder and its output connected to a discrete one of said n word lines; and
- each said current switch circuit means including, a first transistor having an emitter, base and collector and a second transistor having an emitter, base and collector, said base of said first transistor being connected to said input of said current switch circuit means, said collector of said first transistor being connected to a source of potential having a magnitude $|V_1|$, said base of said second transistor being connected to a reference potential, said collector of said second transistor being connected to a source of potential having a magnitude of $|V_2|$, where $|V_1| < |V_2|$, and said emitters of said first and second transistors being connected in common to the output of said current switch means.

4,295,211
INERTIALLY RELEASED JETTISONABLE AIRBORNE BUOY



Vito Suppa, and Daniel Viallet, both of Paris, France, assignors to Thomson-CSF, Paris, France

Filed Feb. 22, 1980, Ser. No. 123,817

Claims priority, application France, Feb. 27, 1979, 79 05002
Int. Cl.³ H04B 1/59

U.S. Cl. 367—4

7 Claims



1. A radio buoy incorporating a hydrophone which can be jettisoned into the water from an aircraft and having two separate parts, an upper part containing a transmission antenna and the electronics associated therewith for transmitting the sound waves detected in water by the hydrophone, and supporting a float balloon protected by a casing, said balloon inflating during the fall of the buoy by means of a forced air intake established by the raising of openings in the form of scoops located at the bottom of the balloon, a lower diving part containing the hydrophone and its drum of wound suspension cable, whereby the hydrophone can be submerged at depths up to 2,000 meters, wherein the upper part of the buoy includes means operated by the raising of the scoops for unlocking the two separate parts of said buoy.

4,295,212

LINEAR ACOUSTIC ARRAY

Richard C. Swenson, Carriere, Miss., assignor to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Jan. 28, 1980, Ser. No. 115,643

Int. Cl.³ G01V 1/38; H04R 1/44

U.S. Cl. 367—20

8 Claims

1. A flexible linear array for use in oceanography, said array comprising:

- a braided mesh tube formed of a plurality of flexible strands defining a central lumen;
- a plurality of instrumentation assemblies disposed within said tube at instrumentation stations spaced at predetermined distances from one another along the length thereof;
- said tube being adapted to constrict only a limited amount to a predetermined minimum diameter when under linear tension so that said instrumentation assemblies are gripped by said tube while those portions of said lumen lying between said assemblies remain open while being of reduced diameter relative to the portions of said lumen containing said assemblies; and
- conductor means of greater lengths than said distances interconnecting said assemblies and extending freely through

said open, reduced diameter portions of said lumen without being gripped by said strands defining said reduced



diameter portions, whereby said conductor means are free of said linear tension.

4,295,213

COMPOSITE SEISMIC SIGNAL


Joseph F. Mifsud, Houston, Tex., assignor to Exxon Production Research Company, Houston, Tex.

Filed Oct. 9, 1979, Ser. No. 83,059

Int. Cl.³ G01V 1/143

U.S. Cl. 367—41

8 Claims



1. A method of generating a seismic signal of selected frequency content comprising:

- generating simultaneously from substantially the same location a plurality of component swept sine wave seismic signals covering selected frequency segments within the frequency spectrum of said seismic signal of selected frequency content wherein said selected frequency segments do not substantially overlap in frequency content, said plurality of component swept sine wave seismic signals including at least two signals substantially covering two of said frequency segments which are substantially contiguous in frequency content, the swept sine wave seismic signal substantially covering one of said two frequency segments sweeping in an ascending order of frequency and the swept sine wave seismic signal substantially covering the other of said two frequency segments sweeping in a descending order of frequency; and correlating the sum of said plurality of component swept sine wave seismic signals with the sum of the reflections of said plurality of component swept sine wave seismic signals.

4,295,214

ULTRASONIC SHEAR WAVE TRANSDUCER


Robert B. Thompson, Thousands Oaks, Calif., assignor to Rockwell International Corporation, El Segundo, Calif.

Filed Aug. 23, 1979, Ser. No. 68,988

Int. Cl.³ G01N 29/04

U.S. Cl. 367—140

9 Claims



1. A unidirectional electromagnetic acoustic transducer, comprising:

- a first electrical conductor adapted to carry a first alternating current in a first current plane, said first current being conveyed by said first conductor at any instant in parallel and alternate directions spaced by a uniform amount;
- a second electrical conductor adapted to carry a second alternating current 90° out of phase with respect to said first alternating current in a second current plane substantially coplanar with said first current plane, said second current being conveyed by said second conductor at any instant in parallel and alternate directions spaced by said uniform amount, said second conductor being parallel to but staggered from said first conductor by one half said uniform amount; and
- a source of magnetic flux positioned to direct a static magnetic field parallel to said alternate directions.

4,295,215

SECOND HAND CORRECTION DEVICE FOR USE IN TIMEPIECES

Kiyoshi Kitai, Masuo Ogiwara, and Kozo Chimura, all of Shikawatah, Japan, assignors to Seiko Kokai Kabushiki Kaisha, Tokyo, Japan


Filed Feb. 27, 1979, Ser. No. 15,624

Claims priority, application Japan, Mar. 1, 1978, 53/23898

Int. Cl.³ G04B 27/02, 17/12, 27/00

U.S. Cl. 368—196


7 Claims



1. Second hand correction device in a timepiece having a second hand that regularly rotates in a particular direction, comprising, a second hand axis provided with a cam wheel fixed thereto and having a plurality of cams, a second hand correction member manually movable in a forward direction and a reverse direction and rotationally, control means for

apparatus for checking clock synchronization, said apparatus including:

- (a) logic circuit means for receiving the time-based periodic signals from the clocks and for generating an output signal indicative of proper clock synchronization in response thereto;



- (b) first circuit means connected between the clocks and said logic circuit means for applying a predetermined combination of the clock period signals to said logic circuit means; and
- (c) second circuit means connected between said first circuit means and said logic circuit means for delaying at least one of the clock period signals before it is applied to said logic circuit means.

4,295,221


METHOD AND APPARATUS AT ONE-WAY OR TWO-WAY INFORMATION LINK TO EFFECT INTERFERENCE SUPPRESSION

Bengt Henoch, Hagersten, and Eilert Berglund, Bandhagen, both of Sweden, assignors to Stiftelsen Institute for Mikrovagsteknik vid Tekniska Hogskolan i Stockholm, Stockholm, Sweden
Filed Apr. 18, 1978, Ser. No. 897,374

Claims priority, application Sweden, Apr. 28, 1977, 7704935
Int. Cl.³ H03K 5/08, 7/06

U.S. Cl. 375—23

9 Claims



1. A method providing communication between first and second stations comprising the steps of providing a first pulse train containing certain information at said first station, chopping the pulses in said first pulse train at a constant pre-selected chopping frequency at said first station to develop a second pulse train, modulating said second pulse train onto a carrier signal at said first station, said carrier signal having a frequency that is substantially higher than said chopping frequency, and said chopping frequency being individual to the communication link between said first and second stations to distinguish said link from other communication links, transmitting the thusly modulated carrier signal from said first station, receiving the transmitted carrier signal along with interference signals, if present, at said second station to provide a received signal, detecting the received signal at said second station to provide a detected signal having an intelligence signal component which contains said information and which has a pulse frequency corresponding to said pre-selected chopping frequency, filtering the detected signal at said second station to separate the intelligence signal component from other signal

components of different frequencies and to thereby provide for the recovery of said intelligence signal component, and processing the recovered intelligence signal component following filtering to retrieve said information.

4,295,222

ARRANGEMENT FOR RESTITUTING THE CLOCK FOR A RECEIVER OF DATA TRANSMITTED BY PHASE MODULATION OF A CARRIER


Jean-Pierre H. Van Uffelen, Chevilly Larue, France, assignor to Telecommunications Radioelectriques et Telephoniques, Paris, France

Filed Feb. 8, 1980, Ser. No. 120,015

Claims priority, application France, Feb. 15, 1979, 79 03833
Int. Cl.³ H04L 7/04

U.S. Cl. 375—106

6 Claims



1. An arrangement for restituting a clock included in the receiver of a system for the transmission of data by n-valent phase modulation of a carrier, and used to sample the demodulated signals formed by demodulation of the received signal with the modulating frequency by means of signals which are of the same phase and shifted 90° relative to a local carrier, this arrangement for restituting a clock comprising a circuit for controlling a local clock on the zero-passages of a signal characterized in that the circuit comprises local means to detect from the samples of said demodulated signals to which phase section, out of n possible phase sections of the transmitted signals, the phase of the received signal belongs at the sampling instants, and calculating means for forming the component which is of the same phase as, or the component which is shifted 90° relative to, the local carrier of a signal derived from the received signal by a phase shift $\Delta\theta$, so as to make its phase equal, at the sampling instants, to the centre phase of the said detected phase section, said component which is n phase with or shifted 90° relative to the local carrier constituting the signal whose zero transitions are used to control the local clock.

4,295,223

DIGITAL SIGNAL/NOISE RATIO AMPLIFIER APPARATUS FOR A COMMUNICATION SYSTEM

Harold B. Shutterly, Pittsburgh, Pa., assignor to Westinghouse Electric Corp., Pittsburgh, Pa.

Filed Apr. 25, 1979, Ser. No. 33,064


Int. Cl.³ H04B 1/64; H04N 7/16

U.S. Cl. 455—72

5 Claims

1. In a communication system including a transmitter, a receiver and a communication channel, a signal modifier apparatus associated with said transmitter comprising: sampler means responsive to an input signal to be transmitted through said communication channel for deriving a

series of samples representative of a segment of said input signal;
analog-to-digital converter means for converting each sample to a digital sample value;
first means responsive to said digital sample values for subtracting a first predetermined digital value M_1 thereof to derive digital values representative of deviations of said input signal from said first predetermined value M_1 ;
second means for determining with said digital values representative of deviations a common factor K with $K > 1$;



- third means for multiplying each of said representative digital values by said common factor K to derive corresponding amplified digital values;
fourth means for adding a second predetermined digital value M_2 to each of said amplified digital values to derive corresponding augmented digital values;
digital-to-analog converter means for converting said augmented digital values into an intermediary analog signal; said transmitter transmitting said intermediary analog signal through said communication channel.

4,295,224

TUNING INDICATOR APPARATUS FOR A FREQUENCY SYNTHESIZER TUNER


Yoshinori Nishimura, Niiza; Kaoru Umeda, Kawasaki, and Hideo Harada, Tokyo, all of Japan, assignors to Sony Corporation, Tokyo, Japan

Filed Aug. 14, 1979, Ser. No. 66,383

Claims priority, application Japan, Aug. 16, 1978, 53-99850
Int. Cl.³ H04B 1/16

U.S. Cl. 455—156

11 Claims



1. Apparatus for indicating a changing tuning condition in a frequency synthesizer tuner of the type having a phase-locked loop including a reference oscillator, a variable frequency oscillator to produce a local oscillating signal, a programmable frequency divider coupled to the variable frequency oscillator for dividing the frequency of said local oscillating signal by a variable dividing ratio to produce a frequency-divided oscillating signal, a phase comparator for comparing the frequency-divided oscillating signal to the output of the reference oscillator to produce an error signal, and means for feeding back the error signal from the phase comparator to the variable frequency oscillator to adjust the frequency of the local oscillating signal and thereby adjust the tuning condition of the tuner, said apparatus comprising a source of counter pulses; counter means for counting counter pulses supplied thereto, said counter means being coupled to said programmable frequency

divider to determine the dividing ratio thereof; manually operable slide switch means slidable in a first range to enable only a predetermined number of counter pulses to be supplied to said counter means and slidable in a second range to enable counter pulses to be supplied continually to said counter means; sensing means for sensing when the count of said counter means changes by a predetermined amount; and sound generating means for generating an audible sound indication in response to said sensed change in said count to indicate that said tuning condition has changed.

4,295,225

FIBER OPTIC REPEATER


Jing-Jong Pan, Melbourne, Fla., assignor to Harris Corporation, Cleveland, Ohio

Filed Aug. 18, 1978, Ser. No. 934,885

Int. Cl.³ H04B 9/00

U.S. Cl. 455—601

10 Claims



1. A fiber optic repeater comprising a photodetector circuit including an optic detecting MESFET coupled in said photodetector circuit to sense an optic input applied to the gate of said MESFET, an amplification and pulse sharpening circuit and a driver circuit connected in cascade with said photodetector circuit, said amplification and pulse sharpening circuit and said driver circuit each including a single MESFET.

4,295,226

HIGH SPEED DRIVER FOR OPTOELECTRONIC DEVICES


Leonard C. Dombrowski, Batavia, Ill., assignor to Bell Telephone Laboratories, Incorporated, Murray Hill, N.J.

Filed Jul. 2, 1980, Ser. No. 165,380

Int. Cl.³ H04B 9/00

U.S. Cl. 455—618

7 Claims



1. A high speed driver for a unidirectional optoelectronic device (13), characterized by means (16, 30, 31, 32) for biasing the device to draw a first prescribed steady-state current greater than zero when the

device is in a first state and a second prescribed steady-state current greater than the first prescribed current when the device is in a second state, and means (35) for controlling the biasing means to cause the current drawn by the device momentarily to be a value less than that of the first prescribed current during a tran-

sition of the device from the second to the first state, thereby to simulate a negative current overdrive through the unidirectional drive.

DESIGN PATENTS

GRANTED OCT. 13, 1981

ERRATA

For CLASS	See PATENT NO.
D32-049	261,217
D34-001	261,218
D32-073	261,219
D32-021	261,266
D32-021	261,267
D32-032	261,268
D28-035	261,316

DESIGNS

OCTOBER 13, 1981

261,195
SHOE


Howard K. Weiss, New York, N.Y., assignor to Glen Shoe Company, New York, N.Y.

Filed Feb. 23, 1979, Ser. No. 14,747

Term of patent 14 years

Int. Cl. D2—04

U.S. Cl. D2—279



261,198

CONTAINER FOR CARRYING FIRST AID DATA AND EQUIPMENT


James Altadonna, 90 E. 2nd St., Deer Park, N.J. 11729

Filed Jun. 25, 1979, Ser. No. 27,403

Term of patent 14 years

Int. Cl. D2—99

U.S. Cl. D2—400



261,196

SPORTSMAN'S BELT


Robert P. Griffin, Orient, Iowa 50858

Filed Mar. 16, 1979, Ser. No. 21,075

Term of patent 14 years

Int. Cl. D2—07

U.S. Cl. D2—383



261,199
CANE

Allen W. Dockery, 900 Sypert, Carrizo Springs, Tex. 78834

Filed May 16, 1979, Ser. No. 39,788

Term of patent 14 years

Int. Cl. D3—03

U.S. Cl. D3—7



261,197

BELT ATTACHABLE HAMMER HOLDER OR THE LIKE


Donald Rowswell, 678 Lauderdale Ave., London, Ontario, Canada

Filed Jan. 15, 1979, Ser. No. 3,182

Term of patent 14 years

Int. Cl. D2—99

U.S. Cl. D2—400




261,200

DISPLAY UNIT AND LIGHT FIXTURES THEREFOR
 Jerry Shaw, 50 West Fairlawn Blvd., and Samuel G. Solitt, 2121 Brookshire Rd., both of, Akron, Ohio 44313
 Division of Ser. No. 781,653, Mar. 28, 1977, Pat. No. Des. 253,143. This application Jan. 19, 1979, Ser. No. 4,903
 Term of patent 14 years


Int. Cl. D20-02; D25-02; D26-05

U.S. Cl. D6-85

261,201
STAND

Jack E. Blake, P.O. Box 2102, Midland, Tex. 79701
 Filed Apr. 4, 1979, Ser. No. 27,192
 Term of patent 14 years
 Int. Cl. D6-99


U.S. Cl. D6-85



261,202

SOAP DISH FOR ATTACHMENT TO A FRAME
 Sidney J. Shames, 57 Holly Pl., Briarcliff Manor, N.Y. 10510, and Harold Shames, 5 Agnes Cir., Ardsley, N.Y. 10502
 Filed Apr. 4, 1980, Ser. No. 137,353
 Term of patent 14 years
 Int. Cl. D23-02; D7-01

U.S. Cl. D6-89




261,203

WALL MOUNTED SOAP DISH

Sidney J. Shames, 57 Holly Pl., Briarcliff Manor, N.Y. 10510, and Harold Shames, 5 Agnes Cir., Ardsley, N.Y. 10502
 Filed Apr. 4, 1980, Ser. No. 137,358
 Term of patent 14 years
 Int. Cl. D23-02

U.S. Cl. D6-90




261,204

TOWEL BAR SUPPORT POST

Sidney J. Shames, 57 Holly Pl., Briarcliff Manor, N.Y. 10510, and Harold Shames, 5 Agnes Cir., Ardsley, N.Y. 10502
 Filed Apr. 4, 1980, Ser. No. 137,362
 Term of patent 14 years
 Int. Cl. D23-02; D8-08

U.S. Cl. D6-103




261,205

DOUBLE HOOK CLOTHES SUPPORT

Sidney J. Shames, 57 Holly Pl., Briarcliff Manor, N.Y. 10510, and Harold Shames, 5 Agnes Cir., Ardsley, N.Y. 10502
 Filed Apr. 4, 1980, Ser. No. 137,361
 Term of patent 14 years
 Int. Cl. D6-06; D8-08

U.S. Cl. D6-122




261,206

CHECK-OUT STATION ACCESSORY FRAME

Kenneth A. Lloyd, Jr., 10192 Orchard Park West Dr., Indianapolis, Ind. 46280
 Filed Nov. 13, 1978, Ser. No. 960,002
 Term of patent 14 years
 Int. Cl. D6-06

U.S. Cl. D6-143

261,208
MIRROR

Richard J. Whiting, 66 Bonniebrook, Chatham, Ill. 62629
 Filed Feb. 12, 1979, Ser. No. 11,450
 Term of patent 14 years
 Int. Cl. D6-07

U.S. Cl. D6-234



261,209

PANEL FOR A CHAIR BACK


David L. Lee, 1841 Port Margate Pl., Newport Beach, Calif. 92660, and Harry J. O'Connor, 26992 LaPaja, Mission Viejo, Calif. 92675

Filed Aug. 2, 1978, Ser. No. 930,585

Term of patent 14 years

Int. Cl. D6-06

U.S. Cl. D6-197




261,210

TABLECLOTH

Patricia Capanear, 102 Franklin Ave., Belleville, N.J. 07109
 Filed Aug. 1, 1978, Ser. No. 930,084
 Term of patent 14 years
 Int. Cl. D6-13

U.S. Cl. D6-286




261,207

ROLL TOP WET BAR

Robert R. Robins, 721 N. Woodland, Minneapolis, Kans. 67467
 Filed Dec. 3, 1979, Ser. No. 99,944
 Term of patent 14 years
 Int. Cl. D06-04

U.S. Cl. D6-144



261,211

GOBLET OR SIMILAR ARTICLE


Jean-Jacques Durand, LaGarenne, 62510 Arques, France

Filed Jan. 3, 1980, Ser. No. 109,354

Term of patent 14 years

Int. Cl. D07-01

U.S. Cl. D7-13



261,213

INSULATED CARRIER FOR FOOD OR THE LIKE


Charles M. Perethian, Arroyo Grande, Calif.; Marcia L. Le Compte, and Bruce W. Vetter, both of Champaign, Ill., assignors to First Champaign Corporation, Rantoul, Ill.

Filed Sep. 14, 1979, Ser. No. 75,671

Term of patent 14 years

Int. Cl. D03-02

U.S. Cl. D7-77



261,212

COMBINED FUNNEL AND POURING SPOUT

Frederick G. W. Mills, North Walsham, England, assignor to U.G. Closures & Plastics Ltd., England



Filed Jan. 25, 1979, Ser. No. 6,401

Claims priority, application United Kingdom, Jul. 28, 1978, 985662/78

Term of patent 14 years

Int. Cl. D07-99

U.S. Cl. D7-68



261,214

COMBINED BUTTER HOLDER DISH AND COVER


Alfred H. Oelzner, 1205 Leeds Ter., Baltimore, Md. 21227

Filed Jan. 2, 1979, Ser. No. 953,975

Term of patent 14 years

Int. Cl. D07-01

U.S. Cl. D7-84



261,215

COFFEE URN LID



Leo A. Groh; Douglas D. Ludwig, both of West Bend, Wis.; David L. Painter, Glenview, Ill., and John H. Free, Kalispell, Mont., assignors to Dart Industries Inc., Los Angeles, Calif.

Filed Feb. 4, 1980, Ser. No. 118,121

Term of patent 14 years

Int. Cl. D07-02

U.S. Cl. D7-131



261,217

DISH OR POT SCRAPER

Clyde E. Mutch, 5238 Mt. Alifan, San Diego, Calif. 92111

Filed Aug. 23, 1979, Ser. No. 68,974

Term of patent 14 years

Int. Cl. D07-05

U.S. Cl. D32-49



261,216

SPOON OR SIMILAR ARTICLE

Colin B. Richmond, II, Oneida, N.Y., assignor to General Mills, Inc., Minneapolis, Minn.

Filed Sep. 14, 1979, Ser. No. 75,639

Term of patent 14 years

Int. Cl. D07-03

U.S. Cl. D7-137



261,218

REFUSE CONTAINER


William A. Gilbert, Clayton, Mo., assignor to Clean City Squares, Inc., St. Louis, Mo.

Filed Mar. 6, 1978, Ser. No. 884,018

Term of patent 14 years

Int. Cl. D7-07, 99

U.S. Cl. D34-1




261,219
IRON HOLDER

Margaret D. Latimer, 1828 Ceres Way, Sacramento, Calif. 95825

Filed Jun. 20, 1979, Ser. No. 50,450
Term of patent 14 years
Int. Cl. D7—99

U.S. Cl. D32—73



261,221
UNDERSIDE WICK HAND-HELD ROPE WICK
APPLICATOR

Ricks H. Plueneke, Rte. 7, Box 441E, Ft. Worth, Tex. 76119
Continuation-in-part of Ser. No. 156,086, Jun. 3, 1980. This
application Oct. 31, 1980, Ser. No. 202,753

Term of patent 14 years
Int. Cl. D8—05

U.S. Cl. D8—02




261,222
PNEUMATIC IMPACT WRENCH

Roderick F. Bunyea, Cockeysville, Md., assignor to Black & Decker Inc., Newark, Del.

Filed Aug. 8, 1979, Ser. No. 64,964
Term of patent 14 years
Int. Cl. D8—05

U.S. Cl. D8—68




261,220
FIRE SCREEN

Ralph E. Matthews, Decatur, Ala., assignor to Matthews Machine Co., Inc., Decatur, Ala.

Filed Apr. 23, 1979, Ser. No. 32,718
Term of patent 14 years
Int. Cl. D7—08

U.S. Cl. D7—208



261,223
DOOR KNOB

Winfried Scholl, Düsseldorf, Fed. Rep. of Germany, assignor to HEWI, Heinrich Wilke GmbH, Fed. Rep. of Germany
Filed Aug. 7, 1979, Ser. No. 64,564
Claims priority, application Fed. Rep. of Germany, Feb. 8, 1979, MR89

Term of patent 14 years
Int. Cl. D8—06

U.S. Cl. D8—312




261,224
PIVOT PIN FOR MOVABLE LOUVERS OR THE LIKE

Paul H. Sanderson, Jr., Lewisville, Tex., assignor to Dowco Corporation, Dallas, Tex.

Filed Mar. 19, 1979, Ser. No. 21,616
Term of patent 14 years
Int. Cl. D8—08

U.S. Cl. D8—323




261,227
WALL PLATE FOR DOUBLE ELECTRIC SOCKET

Sidney J. Shames, 57 Holly Pl., Briarcliff Manor, N.Y. 10510, and Harold Shames, 5 Agnes Cir., Ardsley, N.Y. 10502

Filed Apr. 4, 1980, Ser. No. 137,360
Term of patent 14 years
Int. Cl. D8—09

U.S. Cl. D8—350




261,225
STRIKE PLATE

John G. Sterling, 888 Country Club Rd., Crystal Lake, Ill. 60014

Filed May 29, 1979, Ser. No. 42,860
Term of patent 14 years
Int. Cl. D8—07

U.S. Cl. D8—344




261,228
WALL PLATE

Sidney J. Shames, 57 Holly Pl., Briarcliff Manor, N.Y. 10510, and Harold Shames, 5 Agnes Cir., Ardsley, N.Y. 10502

Filed Apr. 4, 1980, Ser. No. 137,363
Term of patent 14 years
Int. Cl. D8—09

U.S. Cl. D8—350




261,226
WALL PLATE FOR DOUBLE ELECTRIC SWITCH

Sidney J. Shames, 57 Holly Pl., Briarcliff Manor, N.Y. 10510, and Harold Shames, 5 Agnes Cir., Ardsley, N.Y. 10502

Filed Apr. 4, 1980, Ser. No. 137,359
Term of patent 14 years
Int. Cl. D8—09

U.S. Cl. D8—350




261,229
QUICK RELEASE HONDA

Daniel A. Dvorsky, Rte. 2, Box 106-D, Conifer, Colo. 80433

Filed Jan. 29, 1979, Ser. No. 7,665
Term of patent 14 years
Int. Cl. D8—08

U.S. Cl. D8—396



261,230
BOTTLE

John J. Bird, 1725 Glenoaks, San Fernando, Calif. 91340
Filed Jun. 25, 1979, Ser. No. 51,418
Term of patent 14 years
Int. Cl. D9—01


U.S. Cl. D9—367



261,231
BOTTLE OR SIMILAR ARTICLE

John A. Grip, Cheesequake, N.J., assignor to American Cyanamid Company, Stamford, Conn.
Filed Feb. 21, 1979, Ser. No. 13,774
Term of patent 14 years
Int. Cl. D9—01


U.S. Cl. D9—370



261,232
BOTTLE AND CAP OR SIMILAR ARTICLE

John A. Grip, Cheesequake, N.J., assignor to American Cyanamid Company, Stamford, Conn.
Filed Feb. 21, 1979, Ser. No. 13,775
Term of patent 14 years
Int. Cl. D9—01

U.S. Cl. D9—370



261,233
CONTAINER FOR LIQUIDS OR THE LIKE
Marianne C. Green, Midland, Mich., assignor to Koehring Company, Brookfield, Wis.

Division of Ser. No. 835,418, Sep. 21, 1977, Pat. No. Des. 254,234, which is a division of Ser. No. 552,702, Feb. 24, 1975, Pat. No. Des. 246,891. This application Jun. 29, 1979, Ser. No. 53,380

Term of patent 14 years
Int. Cl. D9—01

U.S. Cl. D9—398




261,234
COMBINED BOX AND LID

Anthony S. Abraham, Stanmore, England, assignor to Lever Brothers Company, New York, N.Y.
Filed Sep. 5, 1979, Ser. No. 72,855
Claims priority, application United Kingdom, Mar. 7, 1979, 988896/79

Term of patent 14 years
Int. Cl. D9—03


U.S. Cl. D9—432



261,235
COLLAPSIBLE HANDLE

Robert G. McMullan, Oakville, Canada, assignor to SCM (Canada) Limited, Don Mills, Canada
Filed Feb. 8, 1979, Ser. No. 10,388
Term of patent 14 years
Int. Cl. D9—99


U.S. Cl. D9—434



261,237
DIGITAL CLOCK OR THE LIKE


David K. Haufe, Hinsdale, Ill., assignor to Sunbeam Corporation, Chicago, Ill.
Division of Ser. No. 794,904, May 9, 1977, Pat. No. Des. 256,676. This application Sep. 28, 1979, Ser. No. 79,688
Term of patent 14 years
Int. Cl. D10—01

U.S. Cl. D10—15



261,238
ADJUSTABLE BATTER BOARD
James K. Pitt, 1712 S. Walnut, Pittsburg, Kans. 66762
Filed May 3, 1979, Ser. No. 35,527
Term of patent 14 years
Int. Cl. D10—04

U.S. Cl. D10—61



261,236
CLOSURE ASSEMBLY FOR LIQUID CONTAINER
Robert P. Williams, Kingswood, Australia, assignor to Baxter Travenol Laboratories, Inc., Deerfield, Ill.
Filed Jan. 29, 1979, Ser. No. 7,084
Claims priority, application Australia, Oct. 13, 1978, 76355
Term of patent 7 years
Int. Cl. D9—07

U.S. Cl. D9—435



261,239
DUAL SIZE BRAKE SHOE APERTURE GAUGE
Thomas E. Morgan, 11061 Clinton River Dr., Sterling Heights, Mich. 48078
Filed Jan. 18, 1980, Ser. No. 113,408
Term of patent 14 years
Int. Cl. D10—04

U.S. Cl. D10—64



261,240

BATTERY TESTER


Gary W. Vest, and James C. Loase, both of Cleveland, Ohio, assignors to New Era Products, Inc., Cleveland, Ohio

Filed Jun. 28, 1979, Ser. No. 53,047

Term of patent 14 years

Int. Cl. D10—04

U.S. Cl. D10—77



261,241

SCALE


Edward Lawing, Columbus, Ohio, assignor to Reliance Electric Co., Cleveland, Ohio

Filed Aug. 30, 1979, Ser. No. 71,313

Term of patent 14 years

Int. Cl. D10—04

U.S. Cl. D10—91



261,242

HOUSING FOR AN EMERGENCY ALARM FOR SWIMMING POOLS AND THE LIKE


Hendrik J. G. Lorist, 791 Cornell Dr., Santa Clara, Calif. 95050

Filed May 14, 1979, Ser. No. 38,632

Term of patent 14 years

Int. Cl. D10—05

U.S. Cl. D10—106



261,243

WATER SENSING ALARM


Richard P. Mintz, Oceanside; Ronald A. Buttner, Bellmore, and Alton K. Allen, Great Neck, all of N.Y., assignors to Data-sonic, Inc., Mineola, N.Y.

Filed Dec. 3, 1979, Ser. No. 99,864

Term of patent 14 years

Int. Cl. D10—05

U.S. Cl. D10—121



261,244

INTERLOCKING WEDDING BAND


Vito A. Scola, 139 Baker St., Providence, R.I. 02905

Filed Apr. 14, 1980, Ser. No. 139,977

Term of patent 14 years

Int. Cl. D11—01

U.S. Cl. D11—27



261,245

EARRING


Elias Epstein, Flushing, N.Y., assignor to Kaspar & Esh, Inc., New York, N.Y.

Filed Jan. 4, 1980, Ser. No. 109,525

Term of patent 14 years

Int. Cl. D11—01

U.S. Cl. D11—75



261,246

EARRING


Elias Epstein, Flushing, N.Y., assignor to Kaspar & Esh, Inc., New York, N.Y.

Filed Jan. 4, 1980, Ser. No. 109,526

Term of patent 14 years

Int. Cl. D11—01

U.S. Cl. D11—75



261,247

EARRING


Elias Epstein, Flushing, N.Y., assignor to Kaspar & Esh, Inc., New York, N.Y.

Filed Jan. 4, 1980, Ser. No. 109,609

Term of patent 14 years

Int. Cl. D11—01

U.S. Cl. D11—75



261,248

ORNAMENT PREFORM


Joan T. Birmingham, 2989 N. Garden Dr., San Bernardino, Calif. 92404

Filed May 27, 1980, Ser. No. 153,533

Term of patent 14 years

Int. Cl. D11—05

U.S. Cl. D11—121



261,249

CREATURE ORNAMENT

Joan T. Birmingham, 2989 N. Garden Dr., San Bernardino, Calif. 92404

Filed May 27, 1980, Ser. No. 153,534

Term of patent 14 years

Int. Cl. D11—05

U.S. Cl. D11—128



261,250

CREATURE ORNAMENT

Joan T. Birmingham, 2989 N. Garden Dr., San Bernardino, Calif. 92404

Filed May 27, 1980, Ser. No. 153,535

Term of patent 14 years

Int. Cl. D11—05

U.S. Cl. D11—128



261,251

DESK ORNAMENT

Arthur E. Lange, 222 11th Ave. North, and Roger F. Bautch, 235 11th Ave. North, both of Waite Park, Minn. 56387

Filed Aug. 29, 1979, Ser. No. 70,917

Term of patent 14 years

Int. Cl. D11—02

U.S. Cl. D11—157



261,252

FIGURINE OF A BULLDOG

Jesus A. Carbajales Santa-Eulalia, and Javier B. Carbajales Santa-Eulalia, both of Montevideo, Uruguay, assignors to John J. Madison Company, Inc., Laguna Hills, Calif.

Filed Mar. 9, 1979, Ser. No. 19,227

Term of patent 14 years

Int. Cl. D11—02

U.S. Cl. D11—158



261,253

FIGURINE OF A LYNX

Jesus A. Carbajales Santa-Eulalia, and Javier B. Carbajales Santa-Eulalia, both of Montevideo, Uruguay, assignors to John J. Madison Company, Inc., Laguna Hills, Calif.

Filed Dec. 15, 1978, Ser. No. 970,007

Term of patent 14 years

Int. Cl. D11—02

U.S. Cl. D11—158



261,254

FIGURINE OF A POODLE

Jesus A. Carbajales Santa-Eulalia, and Javier B. Carbajales Santa-Eulalia, both of Montevideo, Uruguay, assignors to John J. Madison Company, Inc., Laguna Hills, Calif.

Filed Dec. 15, 1978, Ser. No. 970,008

Term of patent 14 years

Int. Cl. D11—02

U.S. Cl. D11—158



261,255

MODEL SHIP


William R. Ervin, 7011 Pinefield Dr., Orlando, Fla. 32809

Filed Mar. 25, 1980, Ser. No. 133,794

Term of patent 14 years

Int. Cl. D11—02

U.S. Cl. D11—163



261,256

VEHICLE TIRE

Naoki Yamazaki, Kodaira; Hiroshi Kojima, Hino, and Hideaki Nishio, Kunitachi, all of Japan, assignors to Bridgestone Tire Co., Ltd., Tokyo, Japan


Filed Dec. 19, 1978, Ser. No. 971,127

Claims priority, application Japan, Oct. 28, 1978, 53-45612

Term of patent 14 years

Int. Cl. D12—15

U.S. Cl. D12—148



261,257

TIRE


Warren L. Guidry, Rayne, La., assignor to Interco Marketing, Incorporated, Rayne, La.

Filed Mar. 30, 1979, Ser. No. 25,576

Term of patent 14 years

Int. Cl. D12—15

U.S. Cl. D12—146



261,258

ADJUSTABLE VIEWING MIRROR

Patricia S. Lavanhar, 1776 Elmwood Dr., Highland Park, Ill. 60035

Filed Feb. 5, 1979, Ser. No. 9,509

Term of patent 14 years

Int. Cl. D12—16

U.S. Cl. D12—189



261,259

UNITIZED POWER CONVERTOR


Henry A. Swartz, 436 N. Rockwell, Oklahoma City, Okla. 73127

Filed Jul. 3, 1979, Ser. No. 54,504

Term of patent 14 years

Int. Cl. D13—02

U.S. Cl. D13—11



261,260

INSULATOR FOR AN OPEN-COIL ELECTRIC HEATING ELEMENT

Wayne R. Seeley, Pulaski, Va., assignor to Emerson Electric Co., St. Louis, Mo.

Filed Oct. 22, 1979, Ser. No. 86,937

Term of patent 14 years

Int. Cl. D13—03

U.S. Cl. D13—18



261,261

FUSE HOLDER


John C. Linton, Potomac, Md., assignor to FIC Corporation, Rockville, Md.

Filed May 24, 1979, Ser. No. 42,075

Term of patent 14 years

Int. Cl. D13—03

U.S. Cl. D13—35



261,262

FUSE HOLDER


John C. Linton, Potomac, Md., assignor to FIC Corporation, Rockville, Md.

Filed May 24, 1979, Ser. No. 42,076

Term of patent 14 years

Int. Cl. D13—03

U.S. Cl. D13—35



261,263

VIDEO TAPE RECORDER DECK

Koya Kurokawa; Noriyuki Arai; Hideo Takahashi, and Taisuke Saeki, all of Saijo, Japan, assignors to Matsushita Electric Industrial Co., Ltd., Kadoma, Japan


Filed Mar. 7, 1979, Ser. No. 18,392

Claims priority, application Japan, Sep. 7, 1978, 53/38172

Term of patent 14 years

Int. Cl. D14—01

U.S. Cl. D14—2



261,266

VACUUM CLEANER

Toshihiko Yoshida, Suita; Masakazu Tatsumi; Seiichi Sakakibara, both of Hirakata; Toshiki Kubo, Kobe; Tsugio Akita, Osaka, and Yoshiaki Ueda, Toyonaka, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Kadoma, Japan


Filed Jan. 23, 1980, Ser. No. 114,528

Claims priority, application Japan, Oct. 8, 1979, 54-42524

Term of patent 14 years

Int. Cl. D15—05

U.S. Cl. D32—21



261,264

CASING FOR A MICROPHONOGRAPH


Bruce P. Carey, Saugus; Lloyd Y. Ishimaru, Agoura, and Moto Shimano, Los Angeles, all of Calif., assignors to Microsonics Corporation, Los Angeles, Calif.

Filed Aug. 10, 1977, Ser. No. 823,542

Term of patent 14 years

Int. Cl. D14—01

U.S. Cl. D14—14



261,267

VACUUM CLEANER

Niklaus Hug, Romanshorn, Switzerland, assignor to Rommag P. Wörwag & Co., Romanshorn, Switzerland



Filed Dec. 29, 1978, Ser. No. 974,530

Claims priority, application Fed. Rep. of Germany, Jul. 1, 1978, 636

Term of patent 14 years

Int. Cl. D15—05

U.S. Cl. D32—21



261,265

TELEPHONE NOTE HOLDER, OR THE LIKE


Norbert Leopoldi, 4180 Marine Dr., Chicago, Ill. 60613

Filed Feb. 19, 1980, Ser. No. 122,250

Term of patent 14 years

Int. Cl. D14—03

U.S. Cl. D14—59



261,268

MOTOR HOUSING AND RUG NOZZLE FOR A VACUUM CLEANER


Sheldon Rutter, New York, N.Y., assignor to The Scott & Fetzer Company, Lakewood, Ohio

Filed Jan. 21, 1980, Ser. No. 114,067

Term of patent 14 years

Int. Cl. D15—05

U.S. Cl. D32—32



261,270

COMBINED SWIMMING POOL COVER-ROLLER AND BRAKE

Alfred D. Jeffrey, 9 Delaware St., Epping, New South Wales 2121, Australia


Filed Aug. 30, 1978, Ser. No. 938,123

Claims priority, application Australia, Mar. 1, 1978, 74142

Term of patent 14 years

Int. Cl. D15—99

U.S. Cl. D15—199



261,271

DUPLICATING APPARATUS


Casimir S. Samczyk, Itasca, Ill., assignor to White Consolidated Industries, Inc., Cleveland, Ohio

Filed Jul. 31, 1978, Ser. No. 929,386

Term of patent 14 years

Int. Cl. D16—03

U.S. Cl. D16—31



261,269

COMBINED DISPENSER CABINET AND STAND


Donald F. Cornett, Cartersville, Ga., assignor to The Coca-Cola Company, Atlanta, Ga.

Filed Mar. 4, 1980, Ser. No. 127,055

Term of patent 14 years

Int. Cl. D15—08

U.S. Cl. D15—116



261,272

SORTING APPARATUS


Frederick J. Lawrence, Tustin, Calif., assignor to Gradco/Dendoki, Inc., Calif.

Filed Sep. 24, 1979, Ser. No. 78,398

Term of patent 14 years

Int. Cl. D16—03

U.S. Cl. D16—32




261,273

DESK TOP ELECTRONIC CALCULATOR

Masaaki Sakai, Tokyo, and Sakae Uematsu, Yokohama, both of Japan, assignors to Canon Kabushiki Kaisha, Japan
Filed Jun. 28, 1979, Ser. No. 52,986

Claims priority, application Japan, Jan. 25, 1979, 54-2564
Term of patent 14 years
Int. Cl. D18—01

U.S. Cl. D18—7



261,276

CASH REGISTER ATTACHMENT FOR SCREENING KEYS

William B. Denker, Fridley, and Jeanne C. Frank, Minneapolis, both of Minn., assignors to Red Owl Stores, Inc., Hopkins, Minn.

Filed Feb. 26, 1979, Ser. No. 15,457
Term of patent 14 years
Int. Cl. D18—99

U.S. Cl. D18—12




261,277

PRINTER RIBBON CASSETTE

Masanori Hashimoto, and Kolchi Soda, both of Tokyo, Japan, assignors to Ricoh Company Ltd., Tokyo, Japan
Filed Jan. 2, 1980, Ser. No. 109,059

Claims priority, application Japan, Jul. 13, 1979, 54-29244
Term of patent 14 years
Int. Cl. D18—01

U.S. Cl. D18—12




261,274

DIGITIZER CURSOR FOR COMPUTER DRAFTING

Gregg P. Gobeli, Plano, Tex., assignor to Camsco, Inc., Richardson, Tex.

Filed Aug. 24, 1979, Ser. No. 69,492
Term of patent 14 years
Int. Cl. D18—01

U.S. Cl. D18—7



261,278

FONT OF VEGETABLE SCRIPT

Willi Rieser, Kloten, Switzerland, assignor to Pfanni-Werk Otto Eckart KG, Munich, Fed. Rep. of Germany
Filed Jan. 22, 1979, Ser. No. 5,481

Claims priority, application Fed. Rep. of Germany, Jul. 21, 1978, MR 11421; Jul. 21, 1978, MR 11423
Term of patent 14 years
Int. Cl. D18—03

U.S. Cl. D18—27




261,275

DISK FOR A MENSTRUAL CALENDAR

Kurt Christensen, Abildgaardsparken 29, 3460 Birkerød, Denmark

Filed Jan. 24, 1979, Ser. No. 6,191
Claims priority, application Denmark, Jul. 24, 1978, 581
Term of patent 14 years
Int. Cl. D18—01

U.S. Cl. D18—10



261,279

SOLAR DEMONSTRATION UNIT

Walter H. Barrett, Woonsocket, R.I., assignor to Columbia Chase Corporation, Braintree, Mass.

Filed Dec. 21, 1978, Ser. No. 971,947
Term of patent 14 years
Int. Cl. D19—07

U.S. Cl. D19—62




261,282

GAME BOARD

Enoch E. Hicks, 3727 Pittsburgh Ave., Dayton, Ohio 45406
Filed Aug. 13, 1979, Ser. No. 66,157

Term of patent 14 years
Int. Cl. D21—01

U.S. Cl. D21—24




261,280

ROTARY CARD FILE

Albrecht Goertz, Nassau, The Bahamas, assignor to Rolodex Corporation, Secaucus, N.J.

Continuation-in-part of Ser. No. 757,514, Jan. 7, 1977, abandoned. This application Nov. 24, 1978, Ser. No. 963,218
Term of patent 14 years
Int. Cl. D19—02

U.S. Cl. D19—76




261,281

LAWN SIGN

Christopher L. McDonald, 28444 Joy Rd., Livonia, Mich. 48150
Filed Jan. 19, 1979, Ser. No. 4,723

Term of patent 14 years
Int. Cl. D20—03

U.S. Cl. D20—38




261,283

GAME BOARD

James R. Becker, New York; David D. Austin, Rochester, both of N.Y., and Ronald A. Rudat, Attleboro, Mass., assignors to Hasbro Industries, Inc., Pawtucket, R.I.

Filed Aug. 27, 1979, Ser. No. 70,306
Term of patent 14 years
Int. Cl. D21—01

U.S. Cl. D21—33



261,284

BACKGAMMON GAMEBOARD (I)


Robert M. Thomas, 2970 Mendon Rd.-15, Cumberland, R.I. 02864, and Robert E. Thomas, R.D.-3 Acorn St., Stanhope, N.J. 07874

Filed Aug. 6, 1979, Ser. No. 64,347

Term of patent 3½ years

Int. Cl. D21-01

U.S. Cl. D21-34



261,286

TOY SPACE SHUTTLE


Jack L. Breneman, Orchard Park, N.Y., assignor to The Quaker Oats Company, Chicago, Ill.

Filed Jan. 22, 1980, Ser. No. 114,277

Term of patent 14 years

Int. Cl. D21-01

U.S. Cl. D21-87



261,287

TOY SPACE ROCKET


Steven E. Hilko, East Aurora, N.Y., assignor to The Quaker Oats Company, Chicago, Ill.

Filed Jan. 22, 1980, Ser. No. 114,280

Term of patent 14 years

Int. Cl. D21-01

U.S. Cl. D21-87



261,285

GINGERBREAD MAN RATTLE

Robin Clark, Kenley, England, assignor to Hilary Page "Sensible" Toys Limited, Kenley, England


Filed Sep. 5, 1979, Ser. No. 72,605

Claims priority, application United Kingdom, Mar. 16, 1979, 989079/79

Term of patent 14 years

Int. Cl. D21-02

U.S. Cl. D21-65



261,288

TOY GLIDER


Steven E. Hilko, East Aurora, N.Y., assignor to The Quaker Oats Company, Chicago, Ill.

Filed Dec. 10, 1979, Ser. No. 101,803

Term of patent 14 years

Int. Cl. D21-01

U.S. Cl. D21-89



261,289

COMBINED CASH REGISTER AND BAR CODE READER TOY


Palmer J. Schoenfeld, Evanston, Ill., assignor to Marvin Glass & Associates, Chicago, Ill.

Filed Feb. 12, 1980, Ser. No. 120,864

Term of patent 14 years

Int. Cl. D21-01

U.S. Cl. D21-111



261,292

CLIP FOR TOY RAILWAY TRACK

Duncan Tong, Hong Kong, Hong Kong, assignor to Playart Limited, Hong Kong, Hong Kong


Filed Mar. 29, 1979, Ser. No. 25,130

Claims priority, application United Kingdom, Nov. 29, 1978, 987465/78

Term of patent 14 years

Int. Cl. D21-01

U.S. Cl. D21-143



261,293

JACK-IN-THE-BOX TOY


Donald H. Samuels, Warwick, and Brian L. Newton, Woonsocket, both of R.I., assignors to Hasbro Industries, Inc., Pawtucket, R.I.

Filed Feb. 15, 1979, Ser. No. 12,359

Term of patent 14 years

Int. Cl. D21-01

U.S. Cl. D21-151



261,290

TOY RADIO


Paul D. Snyder, East Aurora, N.Y., assignor to The Quaker Oats Company, Chicago, Ill.

Filed Oct. 17, 1979, Ser. No. 85,692

Term of patent 14 years

Int. Cl. D21-01

U.S. Cl. D21-113



261,294

ARM WRESTLING DEVICE


Sterling A. Clink, 1930 Maxwell Ave., and Jack E. Barringer, 1313 Ontario Cir., both of Ames, Iowa 50010

Filed Sep. 8, 1978, Ser. No. 940,578

Term of patent 14 years

Int. Cl. D21-02

U.S. Cl. D21-195



261,291


SIMULATIVE TOY VEHICLE

Donald C. Wilson, 18085 Birchcrest, Detroit, Mich. 48221
Continuation-in-part of Ser. No. 894,198, Apr. 5, 1978, abandoned. This application Apr. 16, 1979, Ser. No. 30,556

Term of patent 14 years

Int. Cl. D21-01


U.S. Cl. D21-128



261,295

INDOOR/OUTDOOR GOLF PRACTICE TARGET
James Todd, 24 Casey La., East Northport, N.Y. 11731
Filed Nov. 5, 1979, Ser. No. 78,009
Term of patent 14 years
Int. Cl. D21—02


U.S. Cl. D21—234



261,296

PULLEY FOR COMPOUND ARCHERY BOWS
Joseph M. Caldwell, 2259 W. Big Tujunga Canyon, Tujunga, Calif. 91042
Filed Jan. 28, 1980, Ser. No. 115,955
Term of patent 14 years
Int. Cl. D22—02


U.S. Cl. D22—5



261,297

FISHING REEL
Masakazu Sakamoto, and Takeshi Shohoji, both of Fukuyama, Japan, assignors to Ryobi, Ltd., Fuchu, Japan
Filed Dec. 4, 1979, Ser. No. 100,151
Claims priority, application Japan, Jul. 24, 1979, 54-31206
Term of patent 14 years
Int. Cl. D22—05


U.S. Cl. D22—25



261,298

FISHING LURE
Lester M. Davis, 10805 36 NW., Gig Harbor, Wash. 98335
Filed Apr. 23, 1979, Ser. No. 32,245
Term of patent 14 years
Int. Cl. D22—27


U.S. Cl. D22—27



261,299

FISHING LURE
James E. Easterday, R.R. #1, Spencer, Ind. 47460
Filed Mar. 14, 1980, Ser. No. 130,457
Term of patent 14 years
Int. Cl. D22—05


U.S. Cl. D22—27



261,300

HANDSHOWER
Odo Klose, Wuppertal, Fed. Rep. of Germany, assignor to Friedrich Grohe Armaturenfabrik GmbH & Co., Hemer, Fed. Rep. of Germany
Filed May 23, 1979, Ser. No. 41,695
Claims priority, application Fed. Rep. of Germany, Dec. 15, 1978, MR 6891
Term of patent 14 years
Int. Cl. D23—01

U.S. Cl. D23—35



261,301

DENTAL HANDPIECE
N. Dominic Marucci, Philadelphia, and David B. Wright, Wayne, both of Pa., assignors to Syntex (U.S.A.) Inc., Palo Alto, Calif.
Filed Sep. 29, 1978, Ser. No. 947,123
Term of patent 14 years
Int. Cl. D24—02


U.S. Cl. D24—12



261,303

HYDROTHERAPY POOL WITH SLIDE
John L. Haller, 7249 Carrizo Dr., La Jolla, Calif. 92037
Filed Jul. 18, 1979, Ser. No. 58,746
Term of patent 14 years
Int. Cl. D24—01


U.S. Cl. D24—38



261,304

FRAME MEMBER FOR WINDOWS OR THE LIKE
Dietrich F. Schmidt, Camp Hill, Pa., assignor to Capitol Products Corporation, Mechanicsburg, Pa.
Filed Jan. 21, 1980, Ser. No. 113,561
Term of patent 14 years
Int. Cl. D25—01

U.S. Cl. D25—74



261,302

SURGICAL CALIPER
Michael R. Wheeler, 4448 Lennington Ct., Flint, Mich. 48503
Filed Mar. 5, 1979, Ser. No. 17,399
Term of patent 14 years
Int. Cl. D24—02


U.S. Cl. D24—26



261,305

FRAME MEMBER FOR WINDOWS OR THE LIKE
Dietrich F. Schmidt, Camp Hill, Pa., assignor to Capitol Products Corporation, Mechanicsburg, Pa.
Filed Jan. 21, 1980, Ser. No. 113,562
Term of patent 14 years
Int. Cl. D25—01


U.S. Cl. D25—74



261,306

FRAME MEMBER FOR WINDOWS OR THE LIKE
Dietrich F. Schmidt, Camp Hill, Pa., assignor to Capitol Products Corporation, Mechanicsburg, Pa.
Filed Jan. 21, 1980, Ser. No. 113,563
Term of patent 14 years
Int. Cl. D25—01


U.S. Cl. D25—74



261,309

FRAME MEMBER FOR WINDOWS OR THE LIKE
Dietrich F. Schmidt, Camp Hill, Pa., assignor to Capitol Products Corporation, Mechanicsburg, Pa.
Filed Jan. 21, 1980, Ser. No. 113,566
Term of patent 14 years
Int. Cl. D25—01


U.S. Cl. D25—74



261,307

FRAME MEMBER FOR WINDOWS OR THE LIKE
Dietrich F. Schmidt, Camp Hill, Pa., assignor to Capitol Products Corporation, Mechanicsburg, Pa.
Filed Jan. 21, 1980, Ser. No. 113,564
Term of patent 14 years
Int. Cl. D25—01


U.S. Cl. D25—74



261,310

FRAME MEMBER FOR WINDOWS OR THE LIKE
Dietrich F. Schmidt, Camp Hill, Pa., assignor to Capitol Products Corporation, Mechanicsburg, Pa.
Filed Jan. 21, 1980, Ser. No. 113,567
Term of patent 14 years
Int. Cl. D25—01


U.S. Cl. D25—74



261,308

FRAME MEMBER FOR WINDOWS OR THE LIKE
Dietrich F. Schmidt, Camp Hill, Pa., assignor to Capitol Products Corporation, Mechanicsburg, Pa.
Filed Jan. 21, 1980, Ser. No. 113,565
Term of patent 14 years
Int. Cl. D25—01


U.S. Cl. D25—74



261,311

FRAME MEMBER FOR WINDOWS OR THE LIKE
Dietrich F. Schmidt, Camp Hill, Pa., assignor to Capitol Products Corporation, Mechanicsburg, Pa.
Filed Jan. 21, 1980, Ser. No. 113,568
Term of patent 14 years
Int. Cl. D25—01


U.S. Cl. D25—74



261,312

FRAME MEMBER FOR WINDOWS OR THE LIKE
Dietrich F. Schmidt, Camp Hill, Pa., assignor to Capitol Products Corporation, Mechanicsburg, Pa.
Filed Jan. 21, 1980, Ser. No. 113,641
Term of patent 14 years
Int. Cl. D25—01


U.S. Cl. D25—74



261,315

FRAME MEMBER FOR WINDOWS OR THE LIKE
Dietrich F. Schmidt, Camp Hill, Pa., assignor to Capitol Products Corporation, Mechanicsburg, Pa.
Filed Jan. 24, 1980, Ser. No. 115,085
Term of patent 14 years
Int. Cl. D25—01


U.S. Cl. D25—74



261,313

FRAME MEMBER FOR WINDOWS OR THE LIKE
Dietrich F. Schmidt, Camp Hill, Pa., assignor to Capitol Products Corporation, Mechanicsburg, Pa.
Filed Jan. 21, 1980, Ser. No. 113,794
Term of patent 14 years
Int. Cl. D25—03


U.S. Cl. D25—74



261,316

FRAME MEMBER FOR WINDOWS OR THE LIKE
Dietrich F. Schmidt, Camp Hill, Pa., assignor to Capitol Products Corporation, Mechanicsburg, Pa.
Filed Jan. 24, 1980, Ser. No. 115,086
Term of patent 14 years
Int. Cl. D25—01


U.S. Cl. D25—74



261,314

FRAME MEMBER FOR WINDOWS OR THE LIKE
Dietrich F. Schmidt, Camp Hill, Pa., assignor to Capitol Products Corporation, Mechanicsburg, Pa.
Filed Jan. 21, 1980, Ser. No. 113,795
Term of patent 14 years
Int. Cl. D25—01

U.S. Cl. D25—74



261,317

COMBINED CURLING IRON WITH COVER
Robert Oberheim, Liederbach; Jürgen Greubel, Heidenrod, and Dieter Rams, Kronberg, all of Fed. Rep. of Germany, assignors to Braun Aktiengesellschaft, Fed. Rep. of Germany
Filed Jun. 19, 1980, Ser. No. 158,837
Claims priority, application Fed. Rep. of Germany, Jan. 8, 1980, 8842

Term of patent 14 years
Int. Cl. D28—03

U.S. Cl. D28—35



261,318
CURLING IRON

Robert Oberheim, Liederbach; Jürgen Greubel, Heidenrod, and Dieter Rams, Kronberg, all of Fed. Rep. of Germany, assignors to Braun Aktiengesellschaft, Kronberg, Fed. Rep. of Germany

Filed Jun. 19, 1980, Ser. No. 158,838

Claims priority, application Fed. Rep. of Germany, Jan. 8, 1980, 8842

Term of patent 14 years
Int. Cl. D28—03

U.S. Cl. D28—35



261,319
COVER FOR A CURLING IRON


Robert Oberheim, Liederbach; Jürgen Greubel, Heidenrod, and Dieter Rams, Kronberg, all of Fed. Rep. of Germany, assignors to Braun Aktiengesellschaft, Kronberg, Fed. Rep. of Germany

Filed Jun. 19, 1980, Ser. No. 158,839

Claims priority, application Fed. Rep. of Germany, Jan. 8, 1980, 8842

Term of patent 14 years
Int. Cl. D28—03

U.S. Cl. D28—35



LIST OF PATENTEES

TO WHOM

PATENTS WERE ISSUED ON THE 13TH DAY OF OCTOBER, 1981

NOTE—Arranged in accordance with the first significant character or word of the name (in accordance with city and telephone directory practice).

- A. B. Chance Company: See—
Kamp, Eugene L., 4,295,024, Cl. 200-288.000.
- A-T-O, Inc.: See—
Winiasz, Michael E.; and Long, James M., 4,294,057, Cl. 53-244.000.
- Abbott Laboratories: See—
Williams, John W.; Smith, Robert A.; and Arbir, Francis W., 4,294,853, Cl. 424-319.000.
- Abe, Kazunobu; Tamura, Shoichi; and Nakatsuji, Tadao, to Sakai Chemical Industry Co., Ltd. Method for preventing the wear of a monolithic catalyst by dusts. 4,294,806, Cl. 423-239.000.
- Abler, William L. Bi-periscopic instrument for use in determining terrestrial positions through celestial observation. 4,294,541, Cl. 356-145.000.
- Abo, Toshimi; and Hosaka, Akio, to Nissan Motor Company, Limited. Air fuel ratio controlling device. 4,294,216, Cl. 123-489.000.
- Abramowitz, Herbert. Dental mirror protector case. 4,294,356, Cl. 206-368.000.
- Acher, Jacques: See—
Thominet, Michel; Acher, Jacques; and Monier, Jean-Claude, 4,294,828, Cl. 424-232.000.
- Achiha, Masahiko: See—
Hata, Hidetoh; Haji, Katsumi; Sako, Kazushige; Shibata, Yoji; and Achiha, Masahiko, 4,295,154, Cl. 358-4.000.
- AD.ELE. -Advanced Electronics- S.R.L.: See—
Bonori, Maurizio; and Franconi, Cafiero, 4,295,131, Cl. 340-554.000.
- Ad-Tec Products, Inc.: See—
Whelan, James P., 4,294,701, Cl. 210-497.200.
- Adachi, Akiyoshi: See—
Hara, Haruichi; Kanzaki, Toshihide; Motomuro, Hisanao; and Adachi, Akiyoshi, 4,294,723, Cl. 252-440.000.
- Adam, Fritz G., to ITT Industries, Inc. Storage transistor. 4,295,150, Cl. 357-54.000.
- Adam, Jean-Marie, to Ciba-Geigy Corporation. Water-soluble anthraquinone dyes. 4,294,768, Cl. 260-372.000.
- Adin, Anthony; Boettcher, John W.; and Fleming, James C., to Eastman Kodak Company. Thermally responsive cobalt(III) complex imaging compositions having lowered activation temperatures. 4,294,912, Cl. 430-341.000.
- Adrian, Renate: See—
Maurer, Alexander; Adrian, Renate; Hestermann, Klaus; and Heymer, Gero, 4,294,621, Cl. 106-306.000.
- Wasel-Nielsen, Horst-Dieter; Adrian, Renate; Panter, Herbert; Heymer, Gero; Maurer, Alexander; and von Schenck, Raban, 4,294,808, Cl. 423-305.000.
- Advanced Circuit Technology: See—
Roberts, Joseph A., 4,295,184, Cl. 361-406.000.
- Afanasiev, Anatoly A.: See—
Asinovsky, Erik I.; Afanasiev, Anatoly A.; Pakhomov, Evgeny P.; Zeigarnik, Vladimir A.; and Yartsev, Ivan M., 4,295,021, Cl. 200-147.00R.
- AGA Aktiebolag: See—
Wiklund, Klas R., 4,295,201, Cl. 364-561.000.
- Agence Nationale de Valorisation de la Recherche (Anvar): See—
Bernard, Claude, 4,294,258, Cl. 128-635.000.
- Agfa-Gevaert Aktiengesellschaft: See—
Helling, Gunter; Saleck, Wilhelm; and Berghaller, Peter, 4,294,920, Cl. 430-569.000.
- Ahlstone, Arthur G., to Vetco Inc. Flexible ring gasket retainer for flanged connectors. 4,294,477, Cl. 285-336.000.
- Aida Engineering, Ltd.: See—
Takahashi, Yuu, 4,294,170, Cl. 100-216.000.
- Ainsworth, Bobby J. Attachment for windshield wiper blades. 4,293,975, Cl. 15-250.410.
- Air Industrie: See—
Schlicklin, Philippe; Mertzweiler nee Maillard, Anne-Marie; and Ploussard, Jacques, 4,294,617, Cl. 106-14.370.
- Air Products and Chemicals, Inc.: See—
Kalwaitis, George V., 4,294,124, Cl. 73-863.850.
- Air Shields, Inc.: See—
Hochman, Benjamin L., 4,294,263, Cl. 128-736.000.
- Airco, Inc.: See—
Nayar, Harbhajan S., 4,294,395, Cl. 228-220.000.
- Aisan Industry Co., Ltd.: See—
Sumiyoshi, Masaharu; Sekiya, Setsuro; Motosugi, Katsuhiko; Uozumi, Junzo; Ando, Tsuneo; Takeuchi, Yuzo; and Minoura, Mikio, 4,294,213, Cl. 123-454.000.
- Aisin Seiki Kabushiki Kaisha: See—
Mori, Keiji; and Kurimoto, Kyoichi, 4,294,134, Cl. 74-547.000.
- Nomura, Yoshihiko, 4,294,325, Cl. 180-148.000.
- Ohumi, Takeharu, 4,294,286, Cl. 137-625.480.
- Ajinomoto Company, Incorporated: See—
Takahara, Yoshiyuki; Hirose, Yoshiteru; Takeuchi, Yoko; Murai, Asao; Kainosho, Masatsune; and Murao, Sawao, 4,294,754, Cl. 260-112.50R.
- Akagi, Susumu: See—
Taniguchi, Eiji; Akagi, Susumu; and Torimitsu, Seiichi, 4,294,939, Cl. 525-118.000.
- Akebono Brake Industry Co., Ltd.: See—
Machara, Toshifumi, 4,294,335, Cl. 188-71.900.
- Aktiebolaget Svenska Elektromagneter: See—
Johansson, Sven H., 4,295,070, Cl. 310-70.00R.
- Akzona Incorporated: See—
Allen, Thomas C., 4,294,731, Cl. 260-17.4CL.
- Alape, William J., to Aquascooter Inc. Carburetor device. 4,294,779, Cl. 261-35.000.
- Albano, Vincent J.: See—
Oztekin, Muammer A.; and Albano, Vincent J., 4,294,363, Cl. 211-49.00D.
- Albers-Schonberg, George; Joshua, Henry; and Lopez, Maria B., to Merck & Co., Inc. Hypocholesteremic fermentation products and products of preparation. 4,294,846, Cl. 424-279.000.
- Albers-Schonberg, George: See—
Monaghan, Richard L.; Alberts, Alfred W.; Hoffman, Carl H.; and Albers-Schonberg, George, 4,294,926, Cl. 435-125.000.
- Alberts, Alfred W.: See—
Monaghan, Richard L.; Alberts, Alfred W.; Hoffman, Carl H.; and Albers-Schonberg, George, 4,294,926, Cl. 435-125.000.
- Albizzati, Enrico: See—
Cecchin, Giuliano; and Albizzati, Enrico, 4,294,721, Cl. 252-429.00B.
- Alcan Research and Development Limited: See—
Deczky, Andrew E., 4,294,682, Cl. 204-244.000.
- Alexandrov, Petr A.: See—
Vanjukov, Andrei V.; Mechev, Valery V.; Bystrov, Valentin P.; Ezhov, Evgeny I.; Vasiliev, Mikhail G.; Zaitsev, Vladimir Y.; Romenets, Vladimir A.; Ivanov, Vladimir V.; Golik, Sergei Y.; Grin-Gnatovsky, Evgeny S.; Grechko, Alexander V.; Savin, Ivan V.; Kozhakhmetov, Sultanbek M.; Meierovich, Veniamin B.; Nagibin, Vladimir D.; Ramazanov, Nariman A.; Umarov, Almas B.; Ziberov, Valentin E.; Kunaev, Askar M.; Takezhanov, Saik T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazheev, Dzhonson T., 4,294,433, Cl. 266-161.000.
- Alfenaar, Marinus, to Electrochemische Energieconversie, N.V. Method for the operation of a fuel cell. 4,294,892, Cl. 429-13.000.
- Alfoldi, Lajos; Balint nee Fodor, Katalin; Kari, Csaba; Torok, Istvan; Szvoboda, Gyorgy; Lang, Tibor; Gado, Istvan; and Ambrus, Gabor, to Gyogyszerkutato Intezet. Genetic process for the preparation of antibiotic-producer micromonospora strains. 4,294,927, Cl. 435-172.000.
- Alford, Raymond N.: See—
Treible, Edwin S.; Dopkin, Joseph A.; and Alford, Raymond N., 4,294,214, Cl. 123-458.000.
- Allen, Thomas C., to Akzona Incorporated. Method for drying absorbent modified cellulosic polymers and the like. 4,294,731, Cl. 260-17.4CL.
- Allied Chemical Corporation: See—
Frantom, Richard L., 4,294,467, Cl. 280-801.000.
- Alligator Ventilfabrik GmbH: See—
Lutz, Sepp, 4,294,301, Cl. 152-427.000.
- Alpha Plastics, Inc.: See—
Rogers, William H., 4,294,385, Cl. 224-240.000.
- Alps Electric Co., Ltd.: See—
Kasashima, Masao; and Kubo, Yoshizo, 4,295,119, Cl. 338-162.000.
- Altschuler, Bruce R.; Taboada, John; and Altschuler, Martin D. Topographic comparator. 4,294,544, Cl. 356-376.000.
- Altschuler, Martin D.: See—
Altschuler, Bruce R.; Taboada, John; and Altschuler, Martin D., 4,294,544, Cl. 356-376.000.
- Aluminum Company of America: See—
Dawless, Robert K.; and Graziano, Robert E., 4,294,612, Cl. 75-68.00R.
- Amako, Hiroshi: See—
Yamamoto, Takashi; and Amako, Hiroshi, 4,294,667, Cl. 204-1.00T.
- Amano, Sayoko: See—
Ito, Susumu; Sugawara, Noboru; and Amano, Sayoko, 4,294,890, Cl. 428-641.000.
- Ambrus, Gabor: See—
Alfoldi, Lajos; Balint nee Fodor, Katalin; Kari, Csaba; Torok, Istvan; Szvoboda, Gyorgy; Lang, Tibor; Gado, Istvan; and Ambrus, Gabor, 4,294,927, Cl. 435-172.000.
- Amemori, Hiroyuki; and Yamada, Masao, to Tokico Ltd. Turbine meter. 4,294,123, Cl. 73-861.920.

- Amer, Myron: See—
Froehlig, Guy M., 4,294,782, Cl. 264-1.400.
- American Cyanamid Co.: See—
Spatz, David M.; and Cross, Barrington, 4,294,986, Cl. 564-52.000.
- American Institute of Baking, The: See—
Kulp, Karel; and Hoover, William J., 4,294,864, Cl. 426-549.000.
- American Optical Corporation: See—
Grovesteen, William R.; and Jones, John A., 4,294,599, Cl. 55-485.000.
- LeBoeuf, Albert R., 4,294,974, Cl. 556-440.000.
- American Standard Inc.: See—
Fischer, Armin O., 4,294,289, Cl. 138-44.000.
- American Sterilizer Company: See—
Baran, Walter J., 4,294,804, Cl. 422-112.000.
- Ames, Geoffrey C., to Owens-Illinois, Inc. Plastic drum assembly, 4,294,374, Cl. 220-71.000.
- Amino Aluminium Industries, Co., Ltd.: See—
Matsuno, Ryohel, 4,294,435, Cl. 266-234.000.
- Ammons, Sharon E.; Paschall, Edwin L.; and Carter, Morris G. System and method for controlling the conditioning and delivery of air to a conditioned space, 4,294,403, Cl. 236-13.000.
- Amoroso, Michael J., to M.A.T. Industries, Inc. Drillhead unit, 4,294,317, Cl. 173-57.000.
- AMP Incorporated: See—
Weidler, Charles H., 4,295,009, Cl. 179-110.00A.
- Anderson, Dale L., to Datafile Limited. Servo motor control labeller, 4,294,644, Cl. 156-361.000.
- Anderson, Kenneth W.; Summerhays, Brent; and Cazier, Verl O., to Electronic Systems Engineering, Inc. Beverage flow switch, 4,295,044, Cl. 250-229.000.
- Anderson, Norman; Peak, Richard; and Moyse, James A., to Imperial Chemical Industries Limited. Spin finish with anti-static agent, 4,294,709, Cl. 252-8.800.
- Ando, Haruhisa: See—
Takemoto, Iwao; Koike, Norio; Ohba, Shinya; Ando, Haruhisa; Nakai, Masaaki; Hanamura, Syoji; Izawa, Ryuichi; Kubo, Masaharu; Aoki, Masakazu; and Tanaka, Shuhei, 4,295,055, Cl. 307-221.00C.
- Ando, Tsuneo: See—
Sumiyoshi, Masaharu; Sekiya, Setsuro; Motosugi, Katsuhiko; Uozumi, Junzo; Ando, Tsuneo; Takeuchi, Yuzo; and Minoura, Mikio, 4,294,213, Cl. 123-454.000.
- Andresen, Donald D. Honeycomb overhead door, 4,294,055, Cl. 52-795.000.
- Andrews, William J.; Espley, David J. C.; and Philpott, William J. M., to British Cellophane Limited. Heat-sealable antistatic polypropylene films, 4,294,882, Cl. 428-349.000.
- Anolick, Colin; Robinson, Vivian M.; and Stewart, Charles W., Sr., to Du Pont de Nemours, E. I., and Company. Upholstered furniture having improved flame resistance, 4,294,489, Cl. 297-452.000.
- Antonhis, Henry E., to General Refractories Company. Silica-doped, chrome-alumina monolithic refractory compositions, 4,294,618, Cl. 501-129.000.
- Anthony, Myron L., to Sax Zzyzzy, Ltd. Latent heat recirculating system, 4,294,664, Cl. 203-19.000.
- Anthony, Thomas R.; and Cline, Harvey E., to General Electric Company. Surface corrosion inhibition of zirconium alloys by laser surface β -quenching, 4,294,631, Cl. 148-133.000.
- Antonio, Christo; and Uhl, Wymen F., to Litton Business Systems, Inc. Release medium having transferrable glue lines, 4,294,888, Cl. 428-451.000.
- Aoki, Kenji, to Toyota Jidosha Kogyo Kabushiki Kaisha. Air-fuel ratio control method and apparatus of an internal combustion engine, 4,294,212, Cl. 123-440.000.
- Aoki, Masakazu: See—
Takemoto, Iwao; Koike, Norio; Ohba, Shinya; Ando, Haruhisa; Nakai, Masaaki; Hanamura, Syoji; Izawa, Ryuichi; Kubo, Masaharu; Aoki, Masakazu; and Tanaka, Shuhei, 4,295,055, Cl. 307-221.00C.
- Aoki, Shinji; Kawamura, Keita; Kimura, Hitoshi; Katayama, Tsutomu; Kaido, Chikara; and Yoshida, Hiroshi, to Ebara Corporation. Method of treating waste gas by irradiation, 4,294,674, Cl. 204-157.10H.
- Aono, Toshiaki, to Fuji Photo Film Co., Ltd. Process of producing multicolor optical filters, 4,294,900, Cl. 430-7.000.
- Apple, Joseph; and Upton, Eric L., to Command Control & Communications Corporation. Optical system for developing point coordinate information, 4,294,543, Cl. 356-375.000.
- Aquascooter Inc.: See—
Alape, William J., 4,294,779, Cl. 261-35.000.
- Arai, Masatoshi: See—
Takago, Toshio; Arai, Masatoshi; and Futatsumori, Koji, 4,294,975, Cl. 556-482.000.
- Arbir, Francis W.: See—
Williams, John W.; Smith, Robert A.; and Arbir, Francis W., 4,294,853, Cl. 424-319.000.
- Archer, Jean-Francois, to Stas Societe Technique d'Accessoires Specialises S.A. Safety lifting hooks, 4,294,479, Cl. 294-82.00R.
- Archer, Ronald J.; and Fetterly, Richard V. Lint collecting system and apparatus, 4,294,597, Cl. 55-283.000.
- Arco Industries Ltd.: See—
Tsui, Kwok W., 4,295,036, Cl. 235-1.00E.
- Ariga, Shoji, to Clarion Co., Ltd. Packaging case, 4,294,354, Cl. 206-335.000.
- Ariizumi, Takashi: See—
Okado, Masaru; and Ariizumi, Takashi, 4,294,094, Cl. 72-16.000.
- Aristo Graphic Systeme GmbH & Co. KG: See—
Cordes, Werner, 4,295,146, Cl. 346-140.00R.
- Ariyama, Kenzo; Miyawaki, Syozo; and Murakami, Takashi, to Ricoh Company, Ltd. Electrostatic copying apparatus, 4,294,535, Cl. 355-14.0SH.
- Arizona Board of Regents, The University of Arizona, The: See—
Randolph, Alan D., 4,294,807, Cl. 423-242.000.
- Armour and Company: See—
Lundquist, Burton R.; and Macherione, Thomas, 4,294,859, Cl. 426-410.000.
- Armour Pharmaceutical Company: See—
Feldman, Fred, 4,294,826, Cl. 424-101.000.
- Armstrong, Errol C.: See—
Cayton, David W.; Armstrong, Errol C.; and MacKenzie, Angus B., 4,294,179, Cl. 111-3.000.
- Arndt, Friedrich; Rusch, Reinhard; and Schulz, Heinz, to Schering Aktiengesellschaft. Agents for the defoliation of plants, 4,294,605, Cl. 71-73.000.
- Arons, Irving J.; Merrill, Richard E.; and Drennan, Arthur P., to Universal Optical Company, Inc. Molded plastic parts, particularly spin-cast plastic parts for eyeglass frames, 4,294,792, Cl. 264-311.000.
- Arpino, Roberto. Method for transmitting airport weather information, 4,295,139, Cl. 340-870.010.
- Asahi Breweries Ltd.: See—
Otsuka, Chikao; Hara, Reinosuke; and Shigenaka, Yoshito, 4,294,367, Cl. 215-246.000.
- Asahi Kasei Kogyo Kabushiki Kaisha: See—
Issei, Katsuta; and Tetsuo, Tanaka, 4,294,665, Cl. 203-50.000.
- Asai, Mitsuko, to Takeda Chemical Industries, Ltd. 20-O-Acylmaitaninoids, 4,294,757, Cl. 260-239.30P.
- Asea Aktiebolag: See—
Bjorklund, Anders; Persson, Erik; and Virsberg, Lars-Goran, 4,295,113, Cl. 336-84.00M.
- Ashida, Hiroshi; and Takahashi, Fumitake, to Sumitomo Electric Industries, Ltd. Apparatus for coating wires with paint, 4,294,189, Cl. 118-603.000.
- Ashida, Kazutaka: See—
Hirota, Akira; Kosaka, Yoshiteru; and Ashida, Kazutaka, 4,295,171, Cl. 360-73.000.
- Ashton, Charles R.: See—
Givan, David E.; and Ashton, Charles R., 4,295,069, Cl. 310-67.00R.
- Ashworth, Denis H., to Simon Engineering Dudley Limited. Hydraulically operated access equipment, 4,294,188, Cl. 118-305.000.
- Asinovsky, Erik I.; Afanasiev, Anatoly A.; Pakhomov, Evgeny P.; Zeigarnik, Vladimir A.; and Yartsev, Ivan M. Electromagnetic arc extinction apparatus for switchgear, 4,295,021, Cl. 200-147.00R.
- Aslanian, Jerry L.; and Numbers, Jody L., to Master Medical Corporation. Flow control device for administration of intravenous fluids, 4,294,246, Cl. 128-214.00E.
- Asselman, George A. A.: See—
Bex, Peter T. J.; and Asselman, George A. A., 4,294,139, Cl. 74-839.000.
- Assmann, Jurgen, to Grossag GmbH. Hot air grill, 4,295,034, Cl. 219-400.000.
- Astegiano, Luciano; and van Veen, Wouter M. D., to CSELT-Centro Studi e Laboratori Telecomunicazioni S.p.A. Line identifier for switchboards, 4,295,007, Cl. 179-7.00R.
- Aszheimer, Hans J.; Brandstaedter, Horst; Ohlinger, Rainer; Van Pee, Willy; Van Steen, Jaak; Sauer, Friedrich; Schmidt, Rudolf; and Krueger, Siegfried, to BASF Aktiengesellschaft. Process for the manufacture of 4,4'-diphenyl-methane diisocyanate and a mixture of diphenyl-methane diisocyanate isomers containing a small amount of uretdiones and hydrolyzable chlorine, 4,294,666, Cl. 203-72.000.
- Atkins, Larry P., to General Motors Corporation. Battery vent cap for preventing electrolyte foam escape, 4,294,895, Cl. 429-84.000.
- Atlantic Richfield Company: See—
Grane, Henry R.; Jubin, John C., Jr.; and Worrell, G. Richard, 4,294,999, Cl. 568-910.000.
- Pinaire, Ronald; and Everett, Gary L., 4,294,687, Cl. 208-58.000.
- Aubusson, Russell C.; and Gledhill, Richard J., to United Kingdom of Great Britain and Northern Ireland, The Secretary of State for Industry in Her Britannic Majesty's Government of the Interconnection arrangements for testing microelectronic circuit chips on a wafer, 4,295,182, Cl. 361-400.000.
- Aulich, Hubert; and Graubmaier, Josef, to Siemens Aktiengesellschaft. Process for manufacturing Si useful for semiconductor components from quartz sand, 4,294,811, Cl. 423-350.000.
- Ault, James R.: See—
Winzer, Frederick W.; and Ault, James R., 4,294,603, Cl. 65-346.000.
- Ausserbauer, Valentin: See—
Pietralla, Norbert; Ausserbauer, Valentin; and Rosenthal, Christian, 4,294,771, Cl. 260-413.000.
- Autelca AG: See—
Wuthrich, Werner, 4,294,553, Cl. 400-219.100.
- Babcock & Wilcox Company, The: See—
Christiansen, David W., 4,294,660, Cl. 376-442.000.
- Bach, Hartwig C.; and Hinderer, Helmut E., to Monsanto Company. Acrylic fiber having improved basic dyeability and method for making the same, 4,294,884, Cl. 428-364.000.
- Bagnall, Elizabeth A.; Guiliano, Basil A.; and Pfeffer, Henry A., III, to FMC Corporation. Continuous process for the manufacture of cyanuric acid, 4,294,962, Cl. 544-192.000.

- Bahjat, Dhari S.: See—
Sternberg, Ben K.; Miller, Dale E.; and Bahjat, Dhari S., 4,295,096, Cl. 324-357.000.
- Bahrman, Heinrich: See—
Hartenstein, Johannes; Satzinger, Gerhard; Bahrman, Heinrich; and Ganser, Volker, 4,294,834, Cl. 424-260.000.
- Bailey, William. Apparatus for assembling ladder-type frames, 4,293,991, Cl. 29-243.520.
- Bair, Eugene C.; and Hopkins, Willard C., to General Electric Company. Automatic control for wire crimping machine, 4,294,006, Cl. 29-701.000.
- Baird, Charles D. Cotton module compacter, 4,294,169, Cl. 100-48.000.
- Bak, Johannes A.: See—
Nordstrom, Immo R.; and Bak, Johannes A., 4,294,185, Cl. 114-75.000.
- Baker, Donal E.: See—
Stacey, Eric J.; and Baker, Donal E., 4,295,190, Cl. 363-162.000.
- Baker, James A. Tool for removing casement window from building, 4,293,993, Cl. 29-278.000.
- Baker, Joseph T.; Hoffer, George W.; and Hursta, William, to United States of America, National Aeronautics and Space Administration. Logic-controlled occlusive cuff system, 4,294,261, Cl. 128-691.000.
- Baker Perkins Holdings Limited: See—
Naylor, Arthur V.; and Spencer, John K., 4,294,060, Cl. 53-506.000.
- Bakos, Peter; Darrow, Russell E.; Funari, Joseph; and Poliak, Richard M., to International Business Machines Corporation. Composition containing alcohol and use thereof for epoxy removal, 4,294,729, Cl. 252-545.000.
- Baldwin, John J.; and Ponticello, Gerald S., to Merck & Co., Inc. Process for producing 2-bromo-3,5-disubstituted pyridines, 4,294,969, Cl. 546-286.000.
- Baldwin, Stanley L.; Hampton, Vernon; and Embleton, Tony F. W., to Inco Limited. Mufflers for percussive pneumatic machines, 4,294,330, Cl. 181-230.000.
- Balint nee Fodor, Katalin: See—
Alföldi, Lajos; Balint nee Fodor, Katalin; Kari, Csaba; Torok, Istvan; Szvoboda, Gyorgy; Lang, Tibor; Gado, Istvan; and Ambrus, Gabor, 4,294,927, Cl. 435-172.000.
- Balko, Edward N., to General Electric Company. High temperature and low feed acid concentration operation of HCl electrolyzer having unitary membrane electrode structure, 4,294,671, Cl. 204-128.000.
- Ball Corporation: See—
Miller, Edward C.; and Straw, David A., 4,294,373, Cl. 220-70.000.
- Ballester, Ricardo H.: See—
Thompson, Arthur H.; and Ballester, Ricardo H., 4,295,097, Cl. 324-429.000.
- Balyoz, John; Chang, Chi S.; Fox, Barry C.; Palmieri, John A.; Ghafghaichi, Majid; Jen, Teh-Sen; and Mooney, Donald B., to International Business Machines Corporation. Master image chip organization technique or method, 4,295,149, Cl. 357-45.000.
- Ban, Mikichi, to Canon Kabushiki Kaisha. Image forming optical system, 4,294,538, Cl. 355-51.000.
- Bando Chemical Industries, Ltd.: See—
Ueno, Toshihiko; and Tomogane, Teruhisa, 4,294,712, Cl. 252-12.000.
- Banford, Samuel E. Athletic footwear for non-contact or light contact sports, 4,294,023, Cl. 36-11.500.
- Banke, Horst: See—
Doerk, Klaus; Koch, Klaus; Banke, Horst; and Toben, Bernhard, 4,294,947, Cl. 526-119.000.
- Barach, Jeffrey T.; and Bluhm, Leslie, to Miles Laboratories, Inc. Process for improving the recovery of microbial cell biomass, 4,294,930, Cl. 435-261.000.
- Baran, Walter J., to American Sterilizer Company. Pressure responsive conditioning control gas sterilization, 4,294,804, Cl. 422-112.000.
- Barbarasch, Joseph: See—
Carollo, Jerome T.; and Barbarasch, Joseph, 4,295,159, Cl. 358-22.000.
- Bard, Robert A. Upward vented trash receptacle for flexible collapsible trash liner, 4,294,379, Cl. 220-404.000.
- Barker, John C.: See—
Turnbull, James O.; Barker, John C.; and Knight, Arthur J., 4,294,021, Cl. 34-224.000.
- Barr, Rolla W. Security device for spare tires, 4,294,088, Cl. 70-56.000.
- BASF Aktiengesellschaft: See—
Aszheimer, Hans J.; Brandstaedter, Horst; Ohlinger, Rainer; Van Pee, Willy; Van Steen, Jaak; Sauer, Friedrich; Schmidt, Rudolf; and Krueger, Siegfried, 4,294,666, Cl. 203-72.000.
- Hartmann, Juergen; Stedefeder, Joachim; Denzinger, Walter; and Pfohl, Sigberg, 4,294,873, Cl. 427-391.000.
- Helfert, Herbert; Reinert, Friedrich; Richter, Paul; Vescia, Michele; and Wegerle, Dieter, 4,294,576, Cl. 8-137.500.
- Kanter, Hartmut, 4,294,755, Cl. 260-154.000.
- Koenig, Karl-Heinz; Feuerherd, Karl-Heinz; and Oeser, Heinz-Guenter, 4,294,773, Cl. 260-453.00P.
- Mensch, Siegfried; Eppe, Gerhard; and Elser, Wolfgang, 4,294,581, Cl. 8-611.000.
- Merger, Franz; and Towae, Friedrich, 4,294,971, Cl. 548-226.000.
- Sappok, Reinhard; and Kranz, Joachim, 4,294,620, Cl. 106-288.00Q.
- Schmidt, Wolfram; and Paust, Joachim, 4,294,766, Cl. 260-343.600.
- BASF Wyandotte Corporation: See—
Newkirk, David D.; Login, Robert B.; and Thir, Basil, 4,294,944, Cl. 525-423.000.
- Bassoli, Cesare; Cornetti, Giorgio; and Lovisolo, Francesco, to Centro Ricerche Fiat S.p.A. Distributor-type injector pump, for multi-cylinder compression-ignition internal combustion engines, 4,294,210, Cl. 123-300.000.
- Bassompierre-Sewrin, Christian C., to Martech International, Inc. Method for coating pipeline, 4,294,869, Cl. 427-177.000.
- Bauer, Jerome: See—
Froehlig, Guy M., 4,294,782, Cl. 264-1.400.
- Bauer, William A.: See—
Nystrom, William A.; Lanzel, Leo C.; and Bauer, William A., 4,294,438, Cl. 266-280.000.
- Baumann, Dieter; and Bidegain, Pierre, to Bidegain S.A. Apparatus for determining the shoe size corresponding to a foot, 4,294,014, Cl. 33-3.00C.
- Baumberger, Otto: See—
Kalbskopf, Reinhard; and Baumberger, Otto, 4,294,868, Cl. 427-109.000.
- Baxter Travenol Laboratories, Inc.: See—
Bayham, Edward L., 4,294,574, Cl. 493-213.000.
- Bilstad, Arnold C.; and Foley, John T., 4,294,320, Cl. 177-1.000.
- Carter, Garry L.; Granzow, Daniel B.; and Bayham, Edward L., 4,294,247, Cl. 128-214.00D.
- Dennehey, T. Michael, 4,294,250, Cl. 128-247.000.
- Bayer Aktiengesellschaft: See—
Beck, Ulrich; and Rohloff, Ekhard, 4,294,656, Cl. 162-192.000.
- Bockmann, Walter; Lipper, Karl-August; and Bruhne, Friedrich, 4,294,777, Cl. 260-544.00D.
- Cramm, Gunther; and Blocher, Karl H., 4,294,985, Cl. 564-18.000.
- Grogler, Gerhard; Schwindt, Jurgen; Ganster, Otto; Meiners, Hans-Joachim; and Ruprecht, Hans-Dieter, 4,294,934, Cl. 521-160.000.
- Hendricks, Udo-Winifred; Hildebrand, Dietrich; and Kuth, Robert, 4,294,579, Cl. 8-549.000.
- Henk, Hermann; Wunderlich, Klaus; and Wild, Peter, 4,294,580, Cl. 8-549.000.
- Hoffmann, Hellmut, 4,294,762, Cl. 260-340.300.
- Klein, Alfons; Kron, Rudolf; Wedemeyer, Karlfried; Knust, Ernst; and Havenith, Lothar, 4,294,715, Cl. 361-318.000.
- Krock, Friedrich W.; and Neef, Rutger, 4,294,578, Cl. 8-516.000.
- Krock, Friedrich W.; Neef, Rutger; and Scheiter, Heinz, 4,294,769, Cl. 260-378.000.
- Kuhlthau, Hans-Peter, 4,294,756, Cl. 260-163.000.
- Preiss, Michael; and Metzger, Karl G., 4,294,827, Cl. 424-226.000.
- Riebel, Hans-Jochem; Eue, Ludwig; and Faust, Wilfried, 4,294,967, Cl. 546-242.000.
- Schmidt, Robert K.; and Thomas, Rudolf, 4,294,607, Cl. 71-92.000.
- Scholz, Karl-Heinz; Hartmann, Willy; and Heine, Hans-Georg, 4,294,973, Cl. 548-320.000.
- Voss, Eckart; Petersen, Uwe; and Stadler, Peter, 4,294,959, Cl. 536-17.00R.
- Wagner, Kuno; Block, Hans-Dieter; and Schafer, Walter, 4,294,719, Cl. 252-182.000.
- Wilms, Klaus G.; and Waldmann, Helmut, 4,294,703, Cl. 210-631.000.
- Bayerische Motoren Werke Aktiengesellschaft: See—
Jochmann, Franz; and Jedeck, Helmar, 4,295,052, Cl. 307-10.00R.
- Reh, Walter, 4,294,343, Cl. 192-113.00A.
- Bayham, Edward L., to Baxter Travenol Laboratories, Inc. Method of making seal for flexible container, 4,294,574, Cl. 493-213.000.
- Bayham, Edward L.: See—
Carter, Garry L.; Granzow, Daniel B.; and Bayham, Edward L., 4,294,247, Cl. 128-214.00D.
- BBC Brown, Boveri & Company Limited: See—
Kasper, Ernst, 4,295,071, Cl. 310-213.000.
- Beatty, William E., Jr.; and Ellsworth, James P., to Westinghouse Electric Corp. Circuit breaker with electromechanical trip means, 4,295,025, Cl. 200-288.000.
- Beauvais, Max P.; and Camezon, Raymond E. Method of apparatus for canning food products, 4,294,167, Cl. 99-369.000.
- Bechle, Philip D.; and Roth, Joseph A., to Eastman Kodak Company. Instant processing sleeve, 4,294,906, Cl. 430-207.000.
- Beck, Ulrich; and Rohloff, Ekhard, to Bayer Aktiengesellschaft. Process for measuring the state of charge of suspensions and for controlling the addition of auxiliary agents to the suspensions, 4,294,656, Cl. 162-192.000.
- Beckman Instruments, Inc.: See—
Stephens, Donald E.; and Taylor, John T., 4,294,799, Cl. 422-62.000.
- Beckman, John T., to Owens-Corning Fiberglass Corporation. Controlled multipackaging winding, 4,294,416, Cl. 242-18.00G.
- Bedue, Abel J. H.: See—
Denis, Louis H. D.; Bedue, Abel J. H.; and Malherbaud, Jacques, 4,294,311, Cl. 165-104.00S.
- Beecham Group Limited: See—
Cassidy, Frederick; and Goudie, Alexander C., 4,294,972, Cl. 548-264.000.
- Elliott, Thomas J.; and Ford, David, 4,294,823, Cl. 424-78.000.
- Behn, Reinhard; Heywang, Hermann; and Pachonik, Horst, to Siemens Aktiengesellschaft. Device for coating objects, 4,294,194, Cl. 118-719.000.
- Bell Telephone Laboratories, Incorporated: See—
Brunssen, James E., 4,295,188, Cl. 363-21.000.
- Dombrowski, Leonard C., 4,295,226, Cl. 455-618.000.
- Draper, Don R.; and Kusulas, Peter, Jr., 4,295,219, Cl. 371-51.000.
- Wittwer, Norman C., 4,295,176, Cl. 361-91.000.
- Bellas, Michael; and Cahill, Robert, to Eastman Kodak Company. Process for monoalkylation of dihydric phenols, 4,294,991, Cl. 568-650.000.

- Bencene, Robert C.; and Granger, Charles A. Belt cleaning apparatus. 4,293,970, Cl. 15-21.00D.
- Bendix Autolite Corporation: See—
Young, Ching T., 4,294,668, Cl. 204-1.00T.
- Bendix Corporation: See—
Gage, Millard E.; and Landers, Derek J., 4,295,013, Cl. 200-11.00C.
O'Connor, James M.; and Goodrich, George W., 4,294,518, Cl. 350-357.000.
- Bennett, Richard N., to National Instrument Company, Inc. Control system for filling machine. 4,294,294, Cl. 141-179.000.
- Benson, Ernest J., to Better Agricultural Goals Corporation. Insulated container and process for shipping perishables. 4,294,079, Cl. 62-60.000.
- Bentley Alemannia Limited: See—
Trautner, Johann G., 4,294,085, Cl. 66-75.100.
- Bentley, John; and Thompson, Morice, to Imperial Chemical Industries Limited. Coating compositions. 4,294,735, Cl. 260-22.0CB.
- Benzschawel, Steven J.: See—
Nauheimer, James F.; and Benzschawel, Steven J., 4,294,358, Cl. 206-419.000.
- Beranger, Herve; Marzin, Claude; Omet, Dominique; and Peter, Jean-Luc, to International Business Machines Corporation. Power supply system for monolithic cells. 4,295,210, Cl. 365-227.000.
- Berenov, Alexandr D.; Krainev, Vladislav P.; Mansurov, Midkhat M.; Niskovskikh, Vitaly M.; and Silin, Evgeny L. Withdrawal roll unit for horizontal continuous billet casting machines. 4,294,306, Cl. 164-448.000.
- Berentzen, Harro: See—
Mayer, Harald; and Berentzen, Harro, 4,294,086, Cl. 66-121.000.
- Beresniewicz, Aleksander, to Du Pont de Nemours & Co., Inc. and Company. Water-extensible oligomer solutions and coatings therefrom. 4,294,738, Cl. 260-29.4UA.
- Bergdahl, Knut. Arrangement to counteract or prevent spreading of fire or smoke. 4,294,165, Cl. 98-1.000.
- Berger, Mitchell H.; Gill, Peter J.; and Maresca, Louis M., to Union Carbide Corporation. Process for preparing polyarylates in the presence of a diphenyl ether. 4,294,956, Cl. 528-179.000.
- Berger, Mitchell H.; Maresca, Louis M.; and Matzner, Markus, to Union Carbide Corporation. Process for preparing polyarylates. 4,294,957, Cl. 528-179.000.
- Berglund, Eilert: See—
Henoch, Bengt; and Berglund, Eilert, 4,295,221, Cl. 375-23.000.
- Bergthaller, Peter: See—
Helling, Gunter; Saleck, Wilhelm; and Bergthaller, Peter, 4,294,920, Cl. 430-569.000.
- Berkel, Michael R., to Owens-Illinois, Inc. Reshipper carton for finished or unfinished TV bulbs. 4,294,359, Cl. 206-422.000.
- Bernard, Claude, to Agence Nationale de Valorisation de la Recherche (Anvar). Measuring head enabling the production of physiological measurement signals designed to be positioned on or in corporeal parts. 4,294,258, Cl. 128-635.000.
- Bernard, Leo N., to Pervel Industries, Inc. Dyed flocked fabric and method of making the same. 4,294,577, Cl. 8-488.000.
- Beroff, Howard: See—
Jewusiak, Stephen J.; Beroff, Howard; and Schuler, Michael, 4,294,355, Cl. 206-339.000.
- Berr, Charles E.; and Deyrup, Edward J., to Du Pont de Nemours & Co., Inc. and Company. Thermal stabilization of polyalkylene terephthalate resin compositions. 4,294,938, Cl. 525-101.000.
- Berthier, Daniel, to Hewlett-Packard Company. Detector arrangement for data-card readers. 4,295,040, Cl. 235-458.000.
- Bertholdo, Gene: See—
Intrater, Josef; Bertholdo, Gene; and Intrater, Janet, 4,294,271, Cl. 134-113.000.
- Bertin & Cie: See—
Boy-Marcotte, Jean-Louis; Junot, Henri D. M.; Grossin, Richard J. A. M.; and Chevalier, Philippe J. M. R., 4,294,232, Cl. 126-443.000.
- Bertolacini, Ralph J.: See—
Kim, Dae K.; Bertolacini, Ralph J.; Gutberlet, L. Charles; and Robinson, Ken K., 4,294,685, Cl. 208-10.000.
- Bertotti, Elvio: See—
Corrado, Giovanni; Bertotti, Elvio; and Sopino, Bruno, 4,294,734, Cl. 260-22.0CB.
Corrado, Giovanni; Bertotti, Elvio; and Sopino, Bruno, 4,294,748, Cl. 260-22.0CB.
- Best Lock Corporation: See—
Best, Walter E.; and Foshee, William R., 4,294,089, Cl. 70-150.000.
Best, Walter E.; Foshee, William R.; and Flack, Max L., 4,294,093, Cl. 70-369.000.
- Best, Walter E.; and Foshee, William R., to Best Lock Corporation. Latchbolt rim lock. 4,294,089, Cl. 70-150.000.
- Best, Walter E.; Foshee, William R.; and Flack, Max L., to Best Lock Corporation. Pin tumbler lock with pull-resistant key plug. 4,294,093, Cl. 70-369.000.
- Bettencourt, George S.: See—
Kovatch, George N.; Bettencourt, George S.; and Soles, Otto H., 4,295,054, Cl. 307-80.000.
- Better Agricultural Goals Corporation: See—
Benson, Ernest J., 4,294,079, Cl. 62-60.000.
- Betz Laboratories, Inc.: See—
Polizzotti, David M.; and Steelhammer, Joe C., 4,294,588, Cl. 55-5.000.
- Bex, Peter T. J.; and Asselman, George A. A., to U.S. Philips Corporation. Drive for a machine comprising variable-stroke reciprocating pistons. 4,294,139, Cl. 74-839.000.
- Bianchi, George. Harvester and method for harvesting green tomatoes. 4,294,063, Cl. 56-16.400.
- Bidegain, Pierre: See—
Baumann, Dieter; and Bidegain, Pierre, 4,294,014, Cl. 33-3.00C.
- Bidegain S.A.: See—
Baumann, Dieter; and Bidegain, Pierre, 4,294,014, Cl. 33-3.00C.
- Bielz, Siegfried: See—
Lohrberg, Karl; Bielz, Siegfried; and Janisch, Paul, 4,294,815, Cl. 423-478.000.
- Bigley, William J., Jr.; and Rizzo, Vincent J., to Lockheed Electronics Co., Inc. Load actuating servomechanism with resonance equalization. 4,295,081, Cl. 318-327.000.
- Bilbrey, Donald L. Log cradle. 4,294,364, Cl. 211-60.00R.
- Billenstein, Siegfried: See—
Kleber, Rolf; and Billenstein, Siegfried, 4,294,990, Cl. 568-601.000.
- Billerud Uddeholm AB: See—
Kullander, Mats O., 4,294,872, Cl. 427-358.000.
- Billot, Michel: See—
Godard, Pierre; and Billot, Michel, 4,294,309, Cl. 165-18.000.
- Bills, David: See—
Yonker, John H.; Fisher, Ernest P., Jr.; and Bills, David, 4,294,315, Cl. 166-322.000.
- Bilstad, Arnold C.; and Foley, John T., to Baxter Travenol Laboratories, Inc. Method and apparatus for weighing material being collected. 4,294,320, Cl. 177-1.000.
- Binder, Georg; and Wossner, Gunter, to Robert Bosch GmbH. Cooling apparatus for electrical machinery. 4,295,067, Cl. 310-52.000.
- Binder, Klaus: See—
Eisele, Erwin; Charzinski, Hans-Peter; and Binder, Klaus, 4,294,209, Cl. 123-293.000.
- Bindin, Peter J., to Chloride Silent Power Limited. Sealing of ceramic electrolyte tubes in electrochemical cells. 4,294,897, Cl. 429-104.000.
- Bingham, John A. C., to Racal-Vadic, Inc. Switched-capacitor modulator. 4,295,105, Cl. 332-9.00R.
- Bings, Hubert: See—
Kruger, Jorg; Thome, Roland; Moritz, Dieter; Bings, Hubert; and Losert, Herbert, 4,294,816, Cl. 423-484.000.
- Bio-Rad Laboratories, Inc.: See—
Curry, Robert E.; and Simonsen, Michael G., 4,295,199, Cl. 364-555.000.
- Biondetti, Mario, to Escher Wyss Limited. Controlled deflection roll. 4,293,988, Cl. 29-116.0AD.
- Bios Inc.: See—
Picunko, Thomas; Kramer, Henry H.; Dam, Naim G.; and Gray, Robert I., 4,294,259, Cl. 128-653.000.
- Biospherics Incorporated: See—
Levin, Gilbert V.; and Straat, Patricia A., 4,294,931, Cl. 435-301.000.
- Bissell, Eugene R.: See—
Smith, Robert E.; and Bissell, Eugene R., 4,294,923, Cl. 435-23.000.
- Bjorklund, Anders; Persson, Erik; and Virsberg, Lars-Goran, to Asea Aktiebolag. Sheet-wound transformer or reactor. 4,295,113, Cl. 336-84.00M.
- Black, John W., to Pemco-Kalamazoo, Inc. Metal disk wheel with resilient tread and bearing support. 4,294,491, Cl. 301-63.0DD.
- Black, John W.: See—
Peters, Lester L.; and Black, John W., 4,294,109, Cl. 73-119.00A.
- Blackburn, Martin J.; and Smith, Michael P., to United Technologies Corporation. Titanium alloys of the TiAl type. 4,294,615, Cl. 75-175.500.
- Blair, Eskel B.; and Koleske, Joseph V., to Union Carbide Corporation. Stabilizers for cycloaliphatic epoxide containing compositions. 4,294,746, Cl. 260-37.0EP.
- Blair, Matthew J.; and Wiktorowski, Thomas A., to Republic Steel Corporation. Method and apparatus for cooling BOF hood paneling. 4,294,432, Cl. 266-46.000.
- Blake, William W., to Caterpillar Tractor Co. Pressure modulating valve. 4,294,278, Cl. 137-115.000.
- Blanchard, Carroll H.; and Marcelonis, Robert P. Shield for typewriter keyboard and cylinder. 4,294,557, Cl. 400-714.000.
- Blau KG Fabrik Fur Kraftfahrzeuge: See—
Gerdes, Theodor, 4,294,375, Cl. 220-293.000.
Gerdes, Theodor, 4,294,281, Cl. 137-541.000.
- Blauer, Aaron. Prefabricated load bearing structure. 4,294,052, Cl. 52-236.500.
- Blocher, Karl H.: See—
Cramm, Gunther; and Blocher, Karl H., 4,294,985, Cl. 564-18.000.
- Block, Hans-Dieter: See—
Wagner, Kuno; Block, Hans-Dieter; and Schafer, Walter, 4,294,719, Cl. 252-182.000.
- Block, Thomas S., to Clarke-Gravely Corporation. Flour treating machine with squeegee. 4,293,971, Cl. 15-98.000.
- Bloomfield Farms, Inc.: See—
Olin, C. Howard, 4,294,295, Cl. 144-3.00K.
- Blueberry Equipment, Inc.: See—
Patzlaff, Albert W., 4,294,691, Cl. 209-3.100.
- Bluhm, Leslie: See—
Barach, Jeffrey T.; and Bluhm, Leslie, 4,294,930, Cl. 435-261.000.
- Blum, Arnold; Geng, Hellmuth R.; Schulze-Schoelling, Hermann; and Spaeth, Bernd, to International Business Machines Corporation. Clock check circuits using delayed signals. 4,295,220, Cl. 371-61.000.
- Board of Regents, University of Texas: See—
Serwer, Philip, 4,294,684, Cl. 204-299.00R.
- Boaz, Premakaran T., to Ford Motor Company. Method for developing a pattern on a ceramic substrate. 4,294,867, Cl. 427-96.000.

- Bock, Erich: See—
Rauschert, Willi; Rieger, Gerald; Bock, Erich; and Eckel, Alfred, 4,294,172, Cl. 102-473.000.
- Bockmann, Walter; Lipper, Karl-August; and Bruhne, Friedrich, to Bayer Aktiengesellschaft. Color-stabilized aromatic carboxylic acid chlorides and a process for their preparation. 4,294,777, Cl. 260-544.00D.
- Bodenbender, Manfred; Reinhardt, Willy; and Ritzenhoff, Hermann, to Hermann Ritzenhoff, Firma. Metal sealing cap. 4,294,368, Cl. 215-256.000.
- Bodenseewerk Geratetechnik GmbH: See—
Giesenberg, Peter, 4,294,128, Cl. 74-5.440.
- Bodenseewerk Perkin-Elmer & Co., GmbH: See—
Tomoff, Toma; Chlosta, Wolfgang; Henninger, Heinz; Tamm, Rolf; and Grossmann, Klaus, 4,294,126, Cl. 73-864.210.
Tomoff, Toma, 4,294,127, Cl. 73-864.210.
- Bodewein, Jakob, to Jagenberg Werke AG. Machine for the crosscutting of a web conveyed as a multi-ply web. 4,294,145, Cl. 83-302.000.
- Boehringer, Wilfried E., to McDonnell Douglas Corporation. Non adjustable hydraulic cylinder. 4,294,163, Cl. 92-52.000.
- Boeing Company, The: See—
Horne, William E., 4,294,602, Cl. 65-40.000.
Hyatt, Michael V.; and Quist, William E., 4,294,625, Cl. 148-2.000.
Klees, Garry W., 4,294,068, Cl. 60-204.000.
- Boese, Harold L., to Cryogenics Unlimited. Cryogenic powered vehicle. 4,294,323, Cl. 180-54.00B.
- Boettcher, John W.: See—
Adin, Anthony; Boettcher, John W.; and Fleming, James C., 4,294,912, Cl. 430-341.000.
- Bofors America, Inc.: See—
Studien, Vance D., 4,295,116, Cl. 338-4.000.
- Bogner, Richard D. Disc-on-rod end-fire microwave antenna. 4,295,141, Cl. 343-753.000.
- Bohlin, Karl G.; Fredriksson, Borje I.; Karlsson, Kent A. B.; and Nelvig, Lars T., to SCA Development Aktiebolag. Method and apparatus for controlling wood pulp grinding machines. 4,294,412, Cl. 241-30.000.
- Bolesky, Richard C.: See—
Gold, Barry L.; and Bolesky, Richard C., 4,293,963, Cl. 3-1.910.
- Boliden Aktiebolag: See—
Hellestam, Carl-Johan S., 4,294,705, Cl. 210-695.000.
- Bollinger, Roger K.: See—
Nims, Philip A.; and Bollinger, Roger K., 4,294,291, Cl. 139-438.000.
- Bonifer, Georg W.: See—
Killmann, Irolt; and Bonifer, Georg W., 4,294,546, Cl. 356-399.000.
- Bonori, Maurizio; and Franconi, Cafiero, to ADELE - Advanced Electronics - S.R.L. Low consumption pulses doppler effect intrusion sensor. 4,295,131, Cl. 340-554.000.
- Boone, Gary A., to Carmet Company. Eight edge positive chip control insert. 4,294,566, Cl. 407-114.000.
- Borg-Warner Corporation: See—
Simmons, John P., 4,294,338, Cl. 192-4.00A.
- Borio, Richard W.; and Mehta, Arun K., to Combustion Engineering, Inc. Tangential firing system. 4,294,178, Cl. 110-347.000.
- Boris, Robert W.: See—
Oram, W. Wayne; Oram, Nora L.; and Boris, Robert W., 4,294,239, Cl. 128-96.000.
- Borja, Jesus; and Halvorsen, Jack R., to Illinois Tool Works Inc. Threaded screw mounting means. 4,295,003, Cl. 174-53.000.
- Borowski, Edward: See—
Falkowski, Leonard; Stefanska, Barbara; Zielinski, Jan; Troka, Elzbieta; Golik, Jerzy; Kolodziejczyk, Pawel; Jarzebski, Andrzej; Cybulska, Emilia; and Borowski, Edward, 4,294,958, Cl. 536-17.00R.
- Borrelli, Dominick. Electrical housing and switch box. 4,295,018, Cl. 200-51.090.
- Borsig GmbH: See—
Kehrer, Wolfgang; and Lachmann, Helmut, 4,294,312, Cl. 165-134.00R.
- Borzum, John J. Tube cutting apparatus. 4,294,147, Cl. 83-382.000.
- Bosch-Siemens Hausgerate GmbH: See—
Reichl, Ernst; and Marloth, Herbert, 4,294,407, Cl. 239-102.000.
- Bosso, Joseph F., to PPG Industries, Inc. Cationic polymers and their use in electrodeposition. 4,294,741, Cl. 260-29.6NR.
- Boswell, William C. Shifting valve. 4,294,287, Cl. 137-625.690.
- Botcher, Winfried; and Germer, Kurt, to Veb Kombinat Polygraph "Werner Lamberz" Leipzig. Device for applying thread staples to folded sheets. 4,294,182, Cl. 112-21.000.
- Boutin, Jean; Guenot, Bernard; and Jamet, Bruno, to Rhone-Poulenc Industries. Aqueous monomer solutions adapted for direct photopolymerization. 4,294,676, Cl. 204-159.230.
- Bouwman, Johannes E., to Nedschroef Octrooi Maatschappij N.V. Self-locking fastener. 4,294,300, Cl. 411-185.000.
- Bouyoucos, John V.: See—
Nelson, David E.; and Bouyoucos, John V., 4,294,513, Cl. 350-96.290.
- Bowerman, Leonard E., to Electrolux Corporation. Vacuum cleaner including automatic shutoff device. 4,294,595, Cl. 55-213.000.
- Bowman, John A.: See—
Dulaney, Donald C.; and Bowman, John A., 4,294,619, Cl. 106-188.000.
- Boy-Marcotte, Jean-Louis; Junot, Henri D. M.; Grossin, Richard J. A. M.; and Chevalier, Philippe J. M. R., to Bertin & Cie. Solar collector. 4,294,232, Cl. 126-443.000.
- Boyesen, Eyvind, to Performance Industries, Inc. Fuel porting for two cycle internal combustion engine. 4,294,202, Cl. 123-73.0PP.
- Boys, John T., to University of Auckland, The. Apparatus and method for generating waveforms which are particularly suitable for a PWM-driven motor. 4,295,189, Cl. 363-41.000.
- Bozon, Alfred; Koberstein, Edgar; Pletka, Hans-Dieter; Volker, Herbert; and Lakatos, Eduard, to Deutsche Gold-und Silber-Scheideanstalt vormals Roessler. Catalyst for the purification of exhaust gases of internal combustion engines. 4,294,726, Cl. 252-462.000.
- Bozzuto, Carl R.: See—
Darling, Scott L.; and Bozzuto, Carl R., 4,294,199, Cl. 122-276.000.
- Brandenstein, Manfred: See—
Olschewski, Armin; Brandenstein, Manfred; Walter, Lothar; Ernst, Horst M.; and Schulz, Toni, 4,294,100, Cl. 72-340.000.
- Brandtstaedter, Horst: See—
Astheimer, Hans J.; Brandtstaedter, Horst; Ohlinger, Rainer; Van Pee, Willy; Van Steen, Jaak; Sauer, Friedrich; Schmidt, Rudolf; and Krueger, Siegfried, 4,294,666, Cl. 203-72.000.
- Bratt, Martin D.; and Oakley, John F., to Du Pont de Nemours & Co., Inc. and Company. Apparatus for pre-conditioning film. 4,294,533, Cl. 354-318.000.
- Braun, Charles H.: See—
Peffer, Robert M.; and Braun, Charles H., 4,294,104, Cl. 73-9.000.
- Brede, Uwe; and Kern, Heinz, to Dynamit Nobel Aktiengesellschaft. Method for increasing the resistance of igniter elements of given geometry. 4,294,648, Cl. 156-627.000.
- Bremer, Noel J.; and Dria, Dennis E., to Standard Oil Company. Preparation of vanadium phosphorus catalysts. 4,294,722, Cl. 252-435.000.
- Brems, John J.: See—
Greenwald, A. Seth; Geiger, Jack M.; Narten, Nathaniel C.; Porritt, Derek S.; Combs, Steven P.; and Brems, John J., 4,294,251, Cl. 128-276.000.
- Brendle, Paul C.: See—
Lloyd, C. F.; Zalewski, Z. Leo; and Brendle, Paul C., 4,295,066, Cl. 310-30.000.
- Breneman, Jack L., to Quaker Oats Company, The. Toy simulated rocket propelled aircraft system. 4,294,032, Cl. 46-1.00R.
- Brennan, Michael P. J., to Chloride Silent Power Limited. Method of forming cathodic electrode structure for a sodium sulfur cell. 4,294,005, Cl. 29-623.500.
- Brennan, Ray A. Air flotation ore enriching apparatus. 4,294,693, Cl. 209-466.000.
- Bridgestone Tire Company Limited: See—
Kanai, Isamu; Okubo, Shigeki; Tsuchiya, Kazuo; and Takasaki, Toshio, 4,294,475, Cl. 285-165.000.
Ohyachi, Tomio; and Irako, Koichi, 4,294,732, Cl. 260-27.0BB.
- Bristol-Myers Company: See—
Tencza, Thomas M., 4,294,819, Cl. 424-14.000.
- British Cellophane Limited: See—
Andrews, William J.; Espley, David J. C.; and Philpott, William J. M., 4,294,882, Cl. 428-349.000.
- British Gas Corporation: See—
Thomas, Richard C.; Pegler, Stewart M.; and Cordes, Paul B., 4,295,095, Cl. 324-326.000.
- Britton, Kenneth L., to Inspiration Consolidated Copper Company. Electrode seal. 4,295,001, Cl. 13-17.000.
- Brockman, Milton H.: See—
United States of America, National Aeronautics and Space Administration; and Brockman, Milton H., 4,295,140, Cl. 343-100.0PE.
- Bronnec, Jean A. L., to Etablissements Genereux de Mecanique de l'Ouest. Device for cleaning liquid surfaces. 4,294,698, Cl. 210-242.300.
- Bronstein-Bonte, Irena Y.; Lindholm, Edward P.; and Taylor, Lloyd D., to Polaroid Corporation. Image-receiving elements. 4,294,907, Cl. 430-213.000.
- Brooks, Albert C. Portable hoist frame. 4,294,176, Cl. 105-363.000.
- Brooks, Philip A. Moving picture apparatus. 4,294,516, Cl. 350-335.000.
- Broquet, Jean B., to Matra. Attitude control systems for space vehicles. 4,294,420, Cl. 244-165.000.
- Brown, William F., to Weston Research Corporation. Dry wall joint and finishing compounds. 4,294,622, Cl. 106-314.000.
- Bruhne, Friedrich: See—
Bockmann, Walter; Lipper, Karl-August; and Bruhne, Friedrich, 4,294,777, Cl. 260-544.00D.
- Brundage, Ruth P.: See—
Leshner, George Y.; and Brundage, Ruth P., 4,294,836, Cl. 424-263.000.
- Bruns, Klaus: See—
Conrad, Jens; Upadek, Horst; and Bruns, Klaus, 4,294,727, Cl. 252-522.00R.
- Brunssen, James E., to Bell Telephone Laboratories, Incorporated. Converter circuit providing isolation and load sensing. 4,295,188, Cl. 363-21.000.
- Bryant, LeRoy J. Device for retaining a compound bow in a partially drawn condition. 4,294,221, Cl. 124-23.00R.
- Buchmuller, Horst; and Michelbrink, Bernhard, to Deutsche Babcock Aktiengesellschaft. Apparatus for the hydraulic transport of precipitator dust. 4,294,592, Cl. 55-120.000.
- Buckeye Cellulose Corporation, The: See—
Camden, James B.; and Vinson, Kenneth D., 4,294,876, Cl. 428-95.000.
- Buckshaw, Thomas M., to Robertshaw Controls Company. Water level control device and method of making the same. 4,295,019, Cl. 200-61.200.

- Bud Antle, Inc.: See—
Cayton, David W.; Armstrong, Errol C.; and MacKenzie, Angus B., 4,294,179, Cl. 111-3.000.
- Bullis, Stephen J.: See—
Patenade, Raymond A.; Cozzy, Thomas W.; and Bullis, Stephen J., 4,294,158, Cl. 89-12.000.
- Bulten-Kanthal Aktiebolag: See—
Lindgren, Hakan O.; and Magnusson, Bengt, 4,295,033, Cl. 219-388.000.
- Burgess, William H., III; and Heiberger, Philip, to Du Pont de Nemours, E. I., and Company. Accelerated process for making nonlinear polyesters. 4,294,736, Cl. 260-22.00M.
- Burgett, Michael W.; and Harte, Richard A., to International Diagnostic Technology, Inc. Method of fluoro immunoassay. 4,294,817, Cl. 424-8.000.
- Burney, Charles F.; and Laymon, Marvin D., to GTE Products Corporation. Capacitance intrusion detection system. 4,295,132, Cl. 340-562.000.
- Burnham, Ralph L., to United States of America, Navy. Laser having simultaneous ultraviolet and visible wavelengths. 4,295,104, Cl. 331-94.50C.
- Burns, Lyle D., to Phillips Petroleum Company. Motor fuel. 4,294,587, Cl. 44-74.000.
- Burns, William S., Jr.; and Sankey, William M., to Western Electric Company, Incorporated. Safety guards and methods for manually feeding workpieces to assembly machines. 4,294,480, Cl. 294-131.000.
- Buro Patent A.G.: See—
Todi, Gerhard H., 4,294,174, Cl. 104-250.000.
- Burroughs Wellcome Co.: See—
Schaeffer, Howard J., 4,294,831, Cl. 424-253.000.
Weston, John B., 4,294,842, Cl. 424-272.000.
Weston, John B., 4,294,843, Cl. 424-272.000.
- Burton, Edward D., to Great Lakes Carbon Corporation. Foundry coke. 4,294,610, Cl. 75-43.000.
- Buser, Hansueli; and Jordi, Peter E., to Ciba-Geigy Corporation. Sample charger for a gas chromatograph. 4,294,117, Cl. 73-864.850.
- Bussey, Joseph G., to Stimatech, Inc. Perioperative application of electronic pain control in combination with anesthetic agents. 4,294,245, Cl. 128-207.210.
- BXL Plastics Limited: See—
Jack, James; and Gray, Derek C., 4,294,796, Cl. 264-559.000.
- Byrnes, Bruce R.: See—
Byrnes, Robert J.; and Byrnes, Bruce R., 4,294,017, Cl. 33-265.000.
Byrnes, Robert J.; and Byrnes, Bruce R. Archery sighting device and methods of constructing and utilizing same. 4,294,017, Cl. 33-265.000.
- Bystrov, Valentin P.: See—
Vanjukov, Andrei V.; Mechev, Valery V.; Bystrov, Valentin P.; Ezhov, Evgeny I.; Vasiliev, Mikhail G.; Zaitsev, Vladimir Y.; Romenets, Vladimir A.; Ivanov, Vladimir V.; Golik, Sergei Y.; Grin-Gnatovsky, Evgeny S.; Grechko, Alexandr V.; Savin, Ivan V.; Kozhakhmetov, Sultanbek M.; Meierovich, Veniamin B.; Nagibin, Vladimir D.; Ramazanov, Nariman A.; Umarov, Almas B.; Ziberov, Valentin E.; Kunaev, Askar M.; Takezhanov, Saub T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazhev, Dzhonson T., 4,294,433, Cl. 266-161.000.
- Cade, Phillip J., to Electronics Corporation of America. System condition indicator. 4,295,129, Cl. 340-520.000.
- Cahill, Robert: See—
Bellas, Michael; and Cahill, Robert, 4,294,991, Cl. 568-650.000.
- Cain, John D.; and Lovie, Gary C., to NCR Canada Ltd.-NCR Canada Ltee. Document sorting method. 4,295,206, Cl. 364-900.000.
- Calmac Manufacturing Corporation: See—
MacCracken, Calvin D., 4,294,078, Cl. 62-59.000.
- Camardella, Giuseppe, to Tekma Kinomat S.p.A. Static wire tensioner for coil winding machines. 4,294,417, Cl. 242-149.000.
- Camden, James B.; and Vinson, Kenneth D., to Buckeye Cellulose Corporation, The. Tufted material having a laminated film primary tufting substrate. 4,294,876, Cl. 428-95.000.
- Camezon, Raymond E.: See—
Beauvais, Max P.; and Camezon, Raymond E., 4,294,167, Cl. 99-369.000.
- Camp, Vann T., to United Technologies Corporation. Exhaust nozzle control and core engine fuel control for turbofan engine. 4,294,069, Cl. 60-238.000.
- Campbell, Charles S., to United Kingdom Atomic Energy Authority. Apparatus for use in a liquid alkali metal environment. 4,294,659, Cl. 165-133.000.
- Campbell, Gerald A.: See—
Upson, Donald A.; Campbell, Gerald A.; and Kestner, Diane E., 4,294,739, Cl. 260-29.6RW.
- Cannings, John A. Rotary seal unit. 4,294,454, Cl. 277-65.000.
- Canon Kabushiki Kaisha: See—
Ban, Mikichi, 4,294,538, Cl. 355-51.000.
Ito, Susumu; Sugawara, Noboru; and Amano, Sayoko, 4,294,890, Cl. 428-641.000.
Iwashita, Tomonori; Fukahori, Hidehiko; and Mashimo, Yukio, 4,294,530, Cl. 354-173.000.
Sato, Yasuhisa; Tsuji, Sadahiko; and Ishikawa, Kazuo, 4,294,529, Cl. 354-53.000.
Sugiura, Muneharu; and Sagara, Seiji, 4,295,186, Cl. 362-217.000.
- Cantlin, John H., to Hudson Lock, Inc. Garage door lock. 4,295,016, Cl. 200-44.000.
- Capuano, Italo A.; Turley, Patricia A.; and DuBord, Edward W., to Olin Corporation. Sodium amalgam monitor. 4,294,798, Cl. 422-62.000.
- Carl Hahn, G.m.b.H.: See—
Frieze, Axel, 4,294,253, Cl. 128-285.000.
- Carlsen, W. John, to GTE Laboratories Incorporated. Reading one-dimensional line image holograms of a video from a disc with a guide track. 4,295,162, Cl. 358-128.600.
- Carmet Company: See—
Boone, Gary A., 4,294,566, Cl. 407-114.000.
- Carollo, Jerome T.; and Barbarasch, Joseph, to General Electric Company. Light projection system. 4,295,159, Cl. 358-22.000.
- Carrier Corporation: See—
Geary, Carl H., Jr., 4,293,996, Cl. 29-446.000.
- Carson, John R., to McNeilab, Inc. Preparation of 5-(arylcyanohydroxymethyl)-1-loweralkylpyrrole-2-acetic acid derivatives. 4,294,760, Cl. 260-326.470.
- Carter, Don R.; Doner, Claude E.; Hammersand, Fred G.; and Tomcavage, Joseph R., to RCA Corporation. Circumferentially apertured cylindrical grid for electron tube. 4,295,077, Cl. 313-293.000.
- Carter, Garry L.; Granzow, Daniel B.; and Bayham, Edward L., to Baxter Travenol Laboratories, Inc. Frangible, resealable closure for a flexible tube. 4,294,247, Cl. 128-214.00D.
- Carter, Morris G.: See—
Ammons, Sharon E.; Paschall, Edwin L.; and Carter, Morris G., 4,294,403, Cl. 236-13.000.
- Casio Computer Co., Ltd.: See—
Fujisawa, Hidetaka, 4,294,154, Cl. 84-1.010.
- Casper, Thomas J., to Envirex Inc. Submerged large diameter seal. 4,294,700, Cl. 210-403.000.
- Cassand, Jean: See—
Cholet, Jacques; Magneville, Pierre; and Cassand, Jean, 4,294,328, Cl. 181-120.000.
- Cassidy, Frederick; and Goudie, Alexander C., to Beecham Group Limited. 1,2-Disubstituted oxo triazolidine. 4,294,972, Cl. 548-264.000.
- Cassill, William G.: See—
Rutledge, Wyman C.; Graves, J. Robert; and Cassill, William G., 4,294,111, Cl. 73-150.00R.
- Castaneda, Fernando: See—
Stockli, Andre; Castaneda, Fernando; and Stockli, Jean-Louis, 4,294,022, Cl. 36-4.000.
- Castelli, Enrico: See—
Eschinas, Emile H.; and Castelli, Enrico, 4,294,767, Cl. 260-347.800.
- Caterpillar Tractor Co.: See—
Blake, William W., 4,294,278, Cl. 137-115.000.
Flesburg, Edward E., 4,294,303, Cl. 164-44.000.
King, Dennis M.; and Richardson, Ronald D., 4,294,218, Cl. 123-502.000.
- Simmons, Gerald P., 4,294,465, Cl. 280-756.000.
- Caux, Gerard: See—
Couderc, Pierre; Grardel, Jean-Luc; and Caux, Gerard, 4,294,717, Cl. 252-97.000.
- Cayton, David W.; Armstrong, Errol C.; and MacKenzie, Angus B., to Bud Antle, Inc. Dibble tube soil plug planter. 4,294,179, Cl. 111-3.000.
- Cazier, Verl O.: See—
Anderson, Kenneth W.; Summerhays, Brent; and Cazier, Verl O., 4,295,044, Cl. 250-229.000.
- CBS Inc.: See—
Turner, James, 4,294,155, Cl. 84-1.010.
- Cecchin, Giuliano; and Albizzati, Enrico, to Montedison S.p.A. Process for preparing components of catalysts for polymerizing alpha-olefins and mixtures thereof with ethylene. 4,294,721, Cl. 252-429.00B.
- CEM - Compagnie Electro-Mecanique: See—
Delassus, Jean, 4,294,304, Cl. 164-504.000.
- Centro Ricerche Fiat S.p.A.: See—
Bassoli, Cesare; Cornetti, Giorgio; and Lovisolo, Francesco, 4,294,210, Cl. 123-300.000.
Iemmi, Giuliano; and Macerata, Diego, 4,294,893, Cl. 429-42.000.
Taricco, Stefano, 4,294,609, Cl. 75-34.000.
- Cerroni, Manlio. Apparatus for the breaking of heterogeneous materials, as city solid wastes. 4,294,413, Cl. 241-36.000.
- Chakrabarti, Paritosh M.: See—
Tracy, David J.; Wood, Lindley S.; and Chakrabarti, Paritosh M., 4,294,848, Cl. 424-302.000.
- Chamness, Dale L. Surgical apparatus. 4,294,254, Cl. 128-303.140.
- Champion International Corporation: See—
Fogle, Ozzie, 4,294,187, Cl. 118-244.000.
Schlotter, Harold J.; and Young, Leroy, 4,294,452, Cl. 273-403.000.
- Champseix, Alain A.; and Le Fur, Gerard R., to Pharmindustrie. Derivatives of 1-phenyl 3-(4-piperidyl) 1-propanone usable as drugs. 4,294,841, Cl. 424-267.000.
- Chang, Chi S.: See—
Balyoz, John; Chang, Chi S.; Fox, Barry C.; Palmieri, John A.; Ghafghaichi, Majid; Jen, Teh-Sen; and Mooney, Donald B., 4,295,149, Cl. 357-45.000.
- Chang, Long F., to Owens-Illinois, Inc. Free-standing plastic bottle. 4,294,366, Cl. 215-1.00C.
- Chang, Richard R.; Frantz, Gene A.; and Hawkins, William R., to Texas Instruments Incorporated. Module for an integrated circuit system. 4,295,181, Cl. 361-395.000.
- Chapman, Arthur J.; and Hayes, Geoffrey M. G., to Pentabloc, Ltd. Joining member for frame systems. 4,294,561, Cl. 403-219.000.
- Chappell, Terry I., to International Business Machines Corporation. Semiconductor fiber optical detection. 4,294,510, Cl. 350-96.170.

- Chappell, Terry I.; and Woodall, Jerry M., to International Business Machines Corporation. Heterojunction V-groove multijunction solar cell. 4,295,002, Cl. 136-244.000.
- Charzinski, Hans-Peter: See—
Eisele, Erwin; Charzinski, Hans-Peter; and Binder, Klaus, 4,294,209, Cl. 123-293.000.
- Cheatham, Jeffery J. Containers. 4,294,351, Cl. 206-222.000.
- Chehovah, Felix, to Thomson-CSF. Series-parallel print mechanism for printer. 4,294,551, Cl. 400-119.000.
- Chemische Werke Huls Aktiengesellschaft: See—
Doerk, Klaus; Koch, Klaus; Banke, Horst; and Toben, Bernhard, 4,294,947, Cl. 526-119.000.
- Chen, Evan N.; and Ferraro, Frank A., to Warner-Lambert Company. Rotatable safety razor and blade cartridge therefor. 4,294,010, Cl. 30-42.000.
- Chen, Shin-I. Constant pressure cooker and fastener. 4,294,377, Cl. 220-321.000.
- Cheng, Paul J., to Phillips Petroleum Company. Carbon black process and reactor. 4,294,814, Cl. 423-457.000.
- Chesler, Ronald B.: See—
Dabby, Franklin W.; and Chesler, Ronald B., 4,294,601, Cl. 65-3.120.
- Chesworth, Graham: See—
Seed, Geoffrey; Chesworth, Graham; Hind, John R.; and Hodgson, Donald, 4,294,661, Cl. 376-363.000.
- Chevalier, Philippe J. M. R.: See—
Boyer-Marcotte, Jean-Louis; Junot, Henri D. M.; Grossin, Richard J. A. M.; and Chevalier, Philippe J. M. R., 4,294,232, Cl. 126-443.000.
- Chevron Research Company: See—
Feffer, Philip C., 4,293,985, Cl. 28-254.000.
Lewis, Robert A.; and Honnen, Lewis R., 4,294,714, Cl. 252-34.000.
- Chiba, Toshiyuki: See—
Takaya, Takao; Takasugi, Hisashi; Chiba, Toshiyuki; and Tsuji, Kiyoshi, 4,294,960, Cl. 544-22.000.
- Chidsey, Francis A., Jr., to Container Corporation of America. Partition for carrier carton. 4,294,398, Cl. 229-15.000.
- Chimura, Kozo: See—
Kitai, Kiyoshi; Ogihara, Masuo; and Chimura, Kozo, 4,295,215, Cl. 368-196.000.
- Chloride Silent Power Limited: See—
Bindin, Peter J., 4,294,897, Cl. 429-104.000.
Brennan, Michael P. J., 4,294,005, Cl. 29-623.500.
- Chlorine Engineers Corp., Ltd.: See—
Kasuya, Kazuki, 4,294,628, Cl. 148-6.350.
- Chlosta, Wolfgang: See—
Tomoff, Toma; Chlosta, Wolfgang; Henninger, Heinz; Tamm, Rolf; and Grossmann, Klaus, 4,294,126, Cl. 73-864.210.
- Chmela, Franz: See—
Urlaub, Alfred; and Chmela, Franz, 4,294,206, Cl. 123-276.000.
- Cholet, Jacques; Magneville, Pierre; and Cassand, Jean, to Institut Francais du Petrole. Device for emitting acoustic waves in a liquid medium by implosion. 4,294,328, Cl. 181-120.000.
- Chr. Eisele Maschinenfabrik GmbH & Co. KG: See—
Drixler, Karl, 4,294,148, Cl. 83-397.000.
- Christiansen, David W., to Babcock & Wilcox Company, The. Spacer assembly retainer arrangement. 4,294,660, Cl. 376-442.000.
- Chubb Integrated Systems Limited: See—
Rankin, Kenneth F., 4,294,380, Cl. 221-195.000.
- Ciba-Geigy AG: See—
Postle, Stephen R.; and Psaila, Alexander, 4,294,916, Cl. 430-522.000.
Postle, Stephen R.; and Psaila, Alexander, 4,294,917, Cl. 430-522.000.
- Ciba-Geigy Corporation: See—
Adam, Jean-Marie, 4,294,768, Cl. 260-372.000.
Buser, Hansueli; and Jordi, Peter E., 4,294,117, Cl. 73-864.850.
Hubele, Adolf, 4,294,850, Cl. 424-309.000.
Karrer, Friedrich, 4,294,949, Cl. 526-262.000.
Kreibich, Ursula; and Schmid, Rolf, 4,294,227, Cl. 126-400.000.
Martin, Henry, 4,294,772, Cl. 260-429.700.
Rody, Jean, 4,294,963, Cl. 544-198.000.
Schmid, Rolf; and Lohse, Friedrich, 4,294,745, Cl. 260-37.00EP.
Tobler, Hans; Forry, Werner; and Schurter, Rolf, 4,294,606, Cl. 71-88.000.
Zergenyi, Janos, 4,294,966, Cl. 544-316.000.
- Cilny, Eugene J. Mono-seat gate valve. 4,294,427, Cl. 251-86.000.
- Clarion Co., Ltd.: See—
Ariga, Shoji, 4,294,354, Cl. 206-335.000.
- Clark, Merlin W. Aerial amusement projectile and method of manufacture. 4,294,447, Cl. 273-58.00R.
- Clarke-Gravely Corporation: See—
Block, Thomas S., 4,293,971, Cl. 15-98.000.
- Clay, Robert B. Blasting composition. 4,294,633, Cl. 149-2.000.
- Clelland, Marshall R.; and Malone, Howard F., Sr. Method and system for scanning a beam of charged particles to control irradiation dosage. 4,295,048, Cl. 250-398.000.
- Cleford, Douglas H.: See—
Fowler, Donald W.; and Cleford, Douglas H., 4,294,162, Cl. 91-434.000.
- Clemence, Francois: See—
Humbert, Daniel; Clemence, Francois; and Dagnaux, Michele, 4,294,845, Cl. 424-278.00Q.
- Cline, Harvey E.: See—
Anthony, Thomas R.; and Cline, Harvey E., 4,294,631, Cl. 148-133.000.
- Closs, Joseph J. Single stage rankine and cycle power plant. 4,294,075, Cl. 60-671.000.
- Cochran, Loretta. Hair treating fluid applicator. 4,294,270, Cl. 132-112.000.
- Cogit Systems, Inc.: See—
Copeland, Robert K.; and Dimaggio, Richard J., 4,295,198, Cl. 364-515.000.
- Cohen, Georges; and Rojey, Alexandre, to Institut Francais du Petrole. Desorption step in absorption heat pumps and refrigerators. 4,294,080, Cl. 62-101.000.
- Colgate-Palmolive Company: See—
Kaesler, James A., 4,294,718, Cl. 252-135.000.
- Colloff, Nicholas J., to Lucas Industries Limited. Method of joining a pair of metal parts. 4,294,392, Cl. 228-111.000.
- Colosimo, Ernest: See—
Colosimo, Gabriel A.; and Colosimo, Ernest, 4,293,979, Cl. 17-32.000.
- Colosimo, Gabriel A.; and Colosimo, Ernest. Forming press for sausage and the like. 4,293,979, Cl. 17-32.000.
- Colt Industries Operating Corp.: See—
McCabe, Ralph P.; and Marsh, Keith D., 4,294,282, Cl. 137-595.000.
- Combs, Steven P.: See—
Greenwald, A. Seth; Geiger, Jack M.; Narten, Nathaniel C.; Porritt, Derek S.; Combs, Steven P.; and Brems, John J., 4,294,251, Cl. 128-276.000.
- Combustion Engineering, Inc.: See—
Borio, Richard W.; and Mehta, Arun K., 4,294,178, Cl. 110-347.000.
Darling, Scott L.; and Bozzuto, Carl R., 4,294,199, Cl. 122-276.000.
- Command Control & Communications Corporation: See—
Apple, Joseph; and Upton, Eric L., 4,294,543, Cl. 356-375.000.
- Commeau, Alain: See—
Guignard, Paul; and Commeau, Alain, 4,294,662, Cl. 219-61.000.
- Commissariat a l'Energie Atomique: See—
Marine, Jean; and Ravetto, Michel, 4,295,148, Cl. 357-17.000.
- Compagnie Francaise d'Etudes et de Construction Technip: See—
Denis, Louis H. D.; Bedue, Abel J. H.; and Malherbaud, Jacques, 4,294,311, Cl. 165-104.00S.
- Compagnie Industrielle des Telecommunications Cit-Alcatel: See—
Gevaud, Roland; and Tallon, Jacques, 4,294,106, Cl. 73-40.700.
- Compagnie Internationale pour l'Informatique CII-Honeywell Bull (Societe Anonyme): See—
Ugon, Michel, 4,295,041, Cl. 234-487.000.
- Congoleum Corporation: See—
Graham, Alan A.; Haemer, Laurence F.; and Miller, Charles H., 4,294,786, Cl. 264-46.400.
- Conoco, Inc.: See—
Sternberg, Ben K.; Miller, Dale E.; and Bahjat, Dhari S., 4,295,096, Cl. 324-357.000.
- Conrad, Jens; Upadek, Horst; and Bruns, Klaus, to Henkel Kommanditgesellschaft auf Aktien. Perfume composition containing 4,5-dioxo-5-alkyl-tricyclo[2.1.0.2.8] dodec-10-enes and its use as an odorant. 4,294,727, Cl. 252-522.00R.
- Consolidated Fiberglass Products Company: See—
Pfeffer, John R., 4,294,655, Cl. 162-107.000.
- Constantine, Albert B.: See—
Thompson, Raymond V.; Todd, Alan; and Constantine, Albert B., 4,294,549, Cl. 366-164.000.
- Container Corporation of America: See—
Chidsey, Francis A., Jr., 4,294,398, Cl. 229-15.000.
Kohler, Karl A., 4,294,397, Cl. 229-27.000.
Nauheimer, James F.; and Benzschawel, Steven J., 4,294,358, Cl. 206-419.000.
- Cooperman, Michael, to GTE Laboratories Incorporated. Methods of and apparatus for generating reference voltages. 4,295,089, Cl. 323-351.000.
- Copeland, Robert K.; and Dimaggio, Richard J., to Cogit Systems, Inc. Automatic printed circuit dimensioning, routing and inspecting apparatus. 4,295,198, Cl. 364-515.000.
- Copelin, Harry B., to Du Pont de Nemours, E. I., and Company. Preparation of high purity 1,4-butanediol. 4,294,998, Cl. 568-868.000.
- Cordes, Paul B.: See—
Thomas, Richard C.; Pegler, Stewart M.; and Cordes, Paul B., 4,295,095, Cl. 324-326.000.
- Cordes, Werner, to Aristo Graphic Systeme GmbH & Co. KG. Device for moving automatic drawing machine tools. 4,295,146, Cl. 346-140.00R.
- Cordray, Daniel E., to General Electric Company. Pilot wire relay protection system for electrical distribution networks. 4,295,175, Cl. 361-69.000.
- Cornetti, Giorgio: See—
Bassoli, Cesare; Cornetti, Giorgio; and Lovisolo, Francesco, 4,294,210, Cl. 123-300.000.
- Corning Glass Works: See—
Ohls, James W., 4,294,190, Cl. 118-620.000.
- Coroncos, James H. Process for preparing beef for use on a vertical rotisserie. 4,294,865, Cl. 426-646.000.
- Corrado, Giovanni; Bertotti, Elvio; and Sopino, Bruno. Low viscosity unsaturated polyester resins. 4,294,734, Cl. 260-22.00B.
- Corrado, Giovanni; Bertotti, Elvio; and Sopino, Bruno. Low viscosity unsaturated polyester resins. 4,294,748, Cl. 260-22.00B.
- Couchman, James C., to General Dynamics Corporation. Fastener incorporating ultrasonic transducer. 4,294,122, Cl. 73-761.000.
- Couderc, Pierre; Grardel, Jean-Luc; and Caux, Gerard, to Societe Chimique des Charbonnages SA. Compositions containing an alkali metal mono- or polyalkylarylsulfonate and the corresponding hydro-

- peroxide, process for their preparation and detergent compositions containing them. 4,294,717, Cl. 252-97.000.
- Coulter Systems Corporation: See—
Kuehnle, Manfred R., 4,294,678, Cl. 204-192.00R.
- Coulthard, John L. Anaerobic filter. 4,294,694, Cl. 210-150.000.
- Coverstone, Don A., to Lyall Electric, Inc. Insulated radiant heating panel. 4,294,003, Cl. 29-611.000.
- Cowan, Keith B.: See—
Winegard, John R.; Shelledy, Carey W.; and Cowan, Keith B., 4,295,143, Cl. 343-840.000.
- Cowans, Kenneth W., to Kinergetics, Inc. Survival system. 4,294,242, Cl. 128-201.130.
- Cox, Charles P., Jr. Gasoline and diesel fuel additive. 4,294,586, Cl. 44-56.000.
- Cozy, Thomas W.: See—
Patenaude, Raymond A.; Cozy, Thomas W.; and Bullis, Stephen J., 4,294,158, Cl. 89-12.000.
- Cramm, Gunther; and Blocher, Karl H., to Bayer Aktiengesellschaft. Production of thiocarbonylhydrazide on a commercial scale. 4,294,985, Cl. 564-18.000.
- Creusot-Loire: See—
Pere, Gerard, 4,294,683, Cl. 204-258.000.
- Crompton & Knowles Corporation: See—
Nims, Philip A.; and Bollinger, Roger K., 4,294,291, Cl. 139-438.000.
- Crosbie, Scott C. Sighting device with means for reflecting and superimposing light flashes on a viewed object. 4,294,445, Cl. 272-8.00M.
- Cross, Barrington: See—
Spatz, David M.; and Cross, Barrington, 4,294,986, Cl. 564-52.000.
- Crotti, Bianca M. Safety door for buildings and rooms. 4,294,040, Cl. 49-254.000.
- Crouzet: See—
Jouret, Edouard, 4,294,501, Cl. 339-66.00M.
- Crowley, Albert T., to RCA Corporation. Digitally adjustable phase shifting circuit. 4,295,098, Cl. 328-24.000.
- Cryogenics Unlimited: See—
Boese, Harold L., 4,294,323, Cl. 180-54.00B.
- CSELT-Centro Studi e Laboratori Telecomunicazioni S.p.A.: See—
Astegiano, Luciano; and van Veen, Wouter M. D., 4,295,007, Cl. 179-7.00R.
- CTS Corporation: See—
Lloyd, C. F.; Zalewski, Z. Leo; and Brendle, Paul C., 4,295,066, Cl. 310-30.000.
- Cummins Engine Company, Inc.: See—
Jones, Philip E., 4,294,203, Cl. 123-195.00R.
- Neff, Joseph J., 4,294,073, Cl. 60-597.000.
- Peters, Lester L.; and Black, John W., 4,294,109, Cl. 73-119.00A.
- Cunningham, Richard N.; and Loeffler, Romain E., deceased (by Loeffler, Carolyn R., personal representative), to Johns-Manville Corporation. Process for rapid annealing of refractory fiber bodies and laminated body produced by process. 4,294,878, Cl. 428-212.000.
- Cunnington, Harry: See—
Figg, Anthony V. J.; and Cunningham, Harry, 4,294,645, Cl. 156-384.000.
- Curran, Dennis P.: See—
Kende, Andrew S.; Curran, Dennis P.; King, Margaret L.; and Feldstein, Neil A., 4,294,763, Cl. 260-340.5DP.
- Curry, Robert E.; and Simonsen, Michael G., to Bio-Rad Laboratories, Inc. Automatic fluorometer and data processor for performing fluorescent immunoassays. 4,295,199, Cl. 364-555.000.
- Cushing, David E.: See—
Joyce, Thomas J.; and Cushing, David E., 4,295,202, Cl. 364-748.000.
- Cutler, John H.; Espelage, Paul M.; and Walker, Loren H., to General Electric Company. Method and apparatus for dynamic braking in a motor control system. 4,295,086, Cl. 318-759.000.
- Cutter Laboratories, Inc.: See—
Sheehan, Neil J.; and Norman, Melvin H., 4,294,249, Cl. 128-214.00G.
- Cybulska, Emilia: See—
Falkowski, Leonard; Stefanska, Barbara; Zielinski, Jan; Troka, Elzbieta; Golik, Jerzy; Kolodziejczyk, Pawel; Jarzebski, Andrzej; Cybulska, Emilia; and Borowski, Edward, 4,294,958, Cl. 536-17.00R.
- Dabby, Franklin W.; and Chesler, Ronald B., to Times Fiber Communications, Inc. Apparatus and process for automatic control of the production of optical fiber. 4,294,601, Cl. 65-3.120.
- Dagnaux, Michele: See—
Humbert, Daniel; Clemence, Francois; and Dagnaux, Michele, 4,294,845, Cl. 424-278.00Q.
- Daido Giken Industries, Co., Ltd.: See—
Matsumoto, Ryohei, 4,294,435, Cl. 266-234.000.
- Daimler-Benz Aktiengesellschaft: See—
Dalheimer, Walter; and Kuus, Olaf, 4,294,039, Cl. 49-248.000.
- Eisele, Erwin; Charzinski, Hans-Peter; and Binder, Klaus, 4,294,209, Cl. 123-293.000.
- Dalbert, Johannes: See—
Pittasch, Willi; and Dalbert, Johannes, 4,293,976, Cl. 16-129.000.
- Dalheimer, Walter; and Kuus, Olaf, to Daimler-Benz Aktiengesellschaft. Pivotal connection for hoods and covers in motor vehicles. 4,294,039, Cl. 49-248.000.
- Dallas, M. J. Whitfield for First National Bank in, executor: See—
Schwegman, Harry E., deceased, 4,294,313, Cl. 166-117.500.
- Dam, Naim G.: See—
Picunko, Thomas; Kramer, Henry H.; Dam, Naim G.; and Gray, Robert I., 4,294,259, Cl. 128-653.000.
- Damiano, Luigi. Traveling tool carrier for severing railway spikes. 4,294,046, Cl. 51-170.00R.
- Dancot, Georges: See—
Hardy, Nicolas; and Dancot, Georges, 4,294,776, Cl. 260-502.00R.
- Daniel, Jean-Claude; Grossoleil, Jacques; and Rouillet, Robert, to Rhone-Poulenc Industries. Process for the manufacture of printing paper and board. 4,294,704, Cl. 210-651.000.
- Daniel, Robert A. Combined carrying case, display device and lectern. 4,294,497, Cl. 312-231.000.
- Darden, Boyd E.; and Hartley, Henry F., to Honeywell Information Systems Inc. Adapter unit for use in a data processing system for processing a variety of requests. 4,295,194, Cl. 364-200.000.
- Darling, Scott L.; and Bozzuto, Carl R., to Combustion Engineering, Inc. Steam generating magnetohydrodynamic diffuser. 4,294,199, Cl. 122-276.000.
- Darrow, Russell E.: See—
Bakos, Peter; Darrow, Russell E.; Funari, Joseph; and Poliak, Richard M., 4,294,729, Cl. 252-545.000.
- Data Packaging Corporation: See—
Pepicelli, Pasquale L.; Lyman, George F.; and Mavilia, Robert A., 4,294,924, Cl. 435-30.000.
- Datafile Limited: See—
Anderson, Dale L., 4,294,644, Cl. 156-361.000.
- Daugherty, Edgar E.; Jackson, Kenneth W.; Jones, Wesley W.; and Subh, Naif T., to Western Electric Company, Inc. Cable splice closure. 4,295,005, Cl. 174-92.000.
- Dauser, William C., Jr., to Heneveld, Lloyd A., Trustee. Wire connector. 4,295,004, Cl. 174-87.000.
- Davenport, Robert W.; Moore, Eugene L.; and Goodman, Ronald L., to Johns-Manville Corporation. Apparatus and method for grinding a helical surface on a flat blade. 4,294,042, Cl. 51-54.000.
- Davidson, Daniel F.: See—
Humphreys, Peter; Davidson, Daniel F.; and Thatcher, Gordon, 4,294,658, Cl. 376-404.000.
- Davidson, James D. Solar panel window unit. 4,294,038, Cl. 49-63.000.
- Davis, Paul, to Sweetheart Plastics, Inc. Sundae dish. 4,294,371, Cl. 220-4.00E.
- Dawless, Robert K.; and Graziano, Robert E., to Aluminum Company of America. Fractional crystallization process. 4,294,612, Cl. 75-68.00R.
- Dayco Corporation: See—
Vitellaro, Frank A., 4,294,636, Cl. 156-143.000.
- Decoene, Frans J. G. C.; Hommez, Etienne R. O. C.; and Naaktgeboren, Adrianus, to Sperry Corporation. Baler feeder mechanism. 4,294,346, Cl. 198-740.000.
- Deczy, Andrew E., to Alcan Research and Development Limited. Data acquisition systems. 4,294,682, Cl. 204-244.000.
- de Figueiredo, Nuno R. M. Device for automatically controlling the infusion liquid flow in an infusion apparatus. 4,294,248, Cl. 128-214.00E.
- de Jager, Christiaan L. Supports. 4,294,430, Cl. 256-58.000.
- Delassus, Jean, to CEM - Compagnie Electro-Mecanique. Electromagnetic centrifuging inductor for rotating a molten metal about its casting axis. 4,294,304, Cl. 164-504.000.
- Delio, Ralph D.: See—
Diemer, Donald J.; and Delio, Ralph D., 4,294,101, Cl. 72-356.000.
- Delle-Althom: See—
Thurles, Edmond; Vernat, Pierre; and Sauvat, Roger, 4,295,023, Cl. 200-148.00R.
- Delta Systems, Inc.: See—
Howard, William A., 4,294,327, Cl. 180-273.000.
- DeLuca, Raymond F., to Georgia-Pacific Corporation. Evaporative dispenser. 4,294,778, Cl. 261-30.000.
- Den-Mat, Inc.: See—
Ibsen, Robert L.; and Glace, William R., 4,294,349, Cl. 206-63.500.
- Denis, Louis H. D.; Bedue, Abel J. H.; and Malherbaud, Jacques, to Compagnie Francaise d'Etudes et de Construction Technip. Method of and arrangement for the seasonal storage and use of hot water produced in particular by electrical power-generating thermal and nuclear stations. 4,294,311, Cl. 165-104.00S.
- Dennehey, T. Michael, to Baxter Travenol Laboratories, Inc. Luer lock connection device. 4,294,250, Cl. 128-247.000.
- Denzinger, Walter: See—
Hartmann, Juergen; Stedefeder, Joachim; Denzinger, Walter; and Pfohl, Sigberg, 4,294,873, Cl. 427-391.000.
- Desbrandes, Robert; and Grolet, Pierre, to Institut Francais du Petrole. Device for measuring the stresses applied in use to the downhole assembly of a drill pipe. 4,294,318, Cl. 175-321.000.
- DeSoto, Inc.: See—
Sekmakas, Kazys; and Shah, Raj, 4,294,737, Cl. 260-29.2EP.
- Wood, Donald C.; and McLaughlin, Robert L., 4,294,855, Cl. 424-358.000.
- Desplats, Andre, to Tractel S.A. Pulley assembly for improving the cooperation between a winch and a cable actuated thereby. 4,294,429, Cl. 254-272.000.
- Detroit Bank & Trust Co., executor: See—
McIntosh, Lester A., deceased, 4,294,439, Cl. 267-54.00A.
- Deutsche Babcock Aktiengesellschaft: See—
Buchmuller, Horst; and Michelbrink, Bernhard, 4,294,592, Cl. 55-120.000.
- Deutsche Gold-und Silber-Scheideanstalt vormals Roessler: See—
Bozon, Alfred; Koberstein, Edgar; Pletka, Hans-Dieter; Volker, Herbert; and Lakatos, Eduard, 4,294,726, Cl. 252-462.000.
- Dewar, Colin A.: See—
Hardy, Frederick E.; and Dewar, Colin A., 4,294,710, Cl. 252-8.800.

- Dexon, Inc.: See—
Intrater, Josef; Bertholdo, Gene; and Intrater, Janet, 4,294,271, Cl. 134-113.000.
- Deyrup, Edward J.: See—
Berr, Charles E.; and Deyrup, Edward J., 4,294,938, Cl. 525-101.000.
- Dickason, Alan F.: See—
Rugen, Donald F.; and Dickason, Alan F., 4,294,742, Cl. 260-31.80H.
- Diehl GmbH & Co.: See—
Rauschert, Willi; Rieger, Gerald; Bock, Erich; and Eckel, Alfred, 4,294,172, Cl. 102-473.000.
- Diemer, Donald J.; and Delio, Ralph D. Method of making single or double flanged track tractor roller for off-highway equipment. 4,294,101, Cl. 72-356.000.
- Diermayer, Werner; Kutzner, Luitpold; and Postenreider, Erwin. Draft control arrangement. 4,294,401, Cl. 236-1.00G.
- Dimaggio, Richard J.: See—
Copeland, Robert K.; and Dimaggio, Richard J., 4,295,198, Cl. 364-515.000.
- Dr. Ing. h.c. F. Porsche Aktiengesellschaft: See—
Striebig, Helmut, 4,294,074, Cl. 60-616.000.
- Doerk, Klaus; Koch, Klaus; Banke, Horst; and Toben, Bernhard, to Chemische Werke Huls Aktiengesellschaft. Process for the production of powdery, thermoplastic copolymers from ethylene and butene-(1). 4,294,947, Cl. 526-119.000.
- Doi, Yoshikazu; Sakai, Yutaka; and Ohno, Kazunori, to Fuji Photo Optical Co., Ltd. Rear stop type zoom lens. 4,294,521, Cl. 350-426.000.
- Doll, Thomas; Schacht, Erich; Radunz, Hans-Eckart; and Schulze, Ernst, to Merck Patent Gesellschaft mit beschränkter Haftung. Benzothiazole derivatives and pharmaceutical formulations containing them. 4,294,839, Cl. 424-263.000.
- Dombrowski, Leonard C., to Bell Telephone Laboratories, Incorporated. High speed driver for optoelectronic devices. 4,295,226, Cl. 455-618.000.
- Doner, Claude E.: See—
Carter, Don R.; Doner, Claude E.; Hammersand, Fred G.; and Tomcavage, Joseph R., 4,295,077, Cl. 313-293.000.
- Donley, William B., to General Motors Corporation. Programming an IGFET read-only-memory. 4,295,209, Cl. 365-178.000.
- Dopkin, Joseph A.: See—
Treible, Edwin S.; Dopkin, Joseph A.; and Alford, Raymond N., 4,294,214, Cl. 123-458.000.
- Dorsen, Mac; and Saltzman, Philip A., to Stupell Industries, Ltd. Handbag construction. 4,294,299, Cl. 150-28.00R.
- Dow Chemical Company, The: See—
Henson, Thomas R.; and Timberlake, John F., 4,294,774, Cl. 260-453.00P.
- Stone, Frederick C.; and Schupska, Gary G., 4,294,968, Cl. 546-251.000.
- Tamony, Andree E.; and Youngson, Charles R., Jr., 4,294,928, Cl. 423-235.000.
- Zachary, Richard E., 4,294,589, Cl. 55-36.000.
- Dragerwerk Aktiengesellschaft: See—
Leichnitz, Kurt, 4,294,583, Cl. 23-232.00R.
- Pasternack, Adalbert, 4,294,244, Cl. 128-202.260.
- Draper, Don R.; and Kusulas, Peter, Jr., to Bell Telephone Laboratories, Incorporated. Memory write error detection circuit. 4,295,219, Cl. 371-51.000.
- Drennan, Arthur P.: See—
Arons, Irving J.; Merrill, Richard E.; and Drennan, Arthur P., 4,294,792, Cl. 264-311.000.
- Dresser Industries, Inc.: See—
Sprott, Kenneth J.; and Herterick, George M., 4,294,113, Cl. 73-199.000.
- Dria, Dennis E.: See—
Bremer, Noel J.; and Dria, Dennis E., 4,294,722, Cl. 252-435.000.
- Drixler, Karl; to Chr. Eisele Maschinenfabrik GmbH & Co. KG. Guards for circular saw blades of circular sawing machines. 4,294,148, Cl. 83-397.000.
- Drouin, Gilbert; and Sibille, Jacques, to Ecole Polytechnique. Extensometer. 4,294,015, Cl. 33-174.00D.
- Drugmand, Lester D., to Electro-Therm, Inc. Double-grip mounting means for sheathed heating elements. 4,295,035, Cl. 219-536.000.
- DuBois, Chester G.; and Hulsebus, Richard P., to Outboard Marine Corporation. Temperature compensator for a carburetor choke valve. 4,294,780, Cl. 261-39.00B.
- DuBord, Edward W.: See—
Capuano, Italo A.; Turley, Patricia A.; and DuBord, Edward W., 4,294,798, Cl. 422-62.000.
- Ducharme, Gilles H., to Du Pont de Nemours, E. I., and Company. Explosives package for coupled cast primer compositions. 4,294,171, Cl. 102-317.000.
- Dulaney, Donald C.; and Bowman, John A., to Rust-Oleum Corporation. Method of producing pigmented silicate coatings. 4,294,619, Cl. 106-188.000.
- Dunlop Limited: See—
Kenney, Michael J., 4,294,730, Cl. 260-17.4BB.
- Duo-Fast Corporation: See—
Oberfell, Allen R., 4,294,391, Cl. 227-130.000.
- Du Pont de Nemours, E. I., and Company: See—
Anolick, Colin; Robinson, Vivian M.; and Stewart, Charles W., Sr., 4,294,489, Cl. 297-452.000.
- Beresniewicz, Aleksander, 4,294,738, Cl. 260-29.4UA.
- Berr, Charles E.; and Deyrup, Edward J., 4,294,938, Cl. 525-101.000.
- Bratt, Martin D.; and Oakley, John F., 4,294,533, Cl. 354-318.000.
- Burgess, William H., III; and Heiberger, Philip, 4,294,736, Cl. 260-22.00M.
- Copelin, Harry B., 4,294,998, Cl. 568-868.000.
- Ducharme, Gilles H., 4,294,171, Cl. 102-317.000.
- Graham, William F., 4,294,743, Cl. 260-32.8EP.
- Graham, William F., 4,294,877, Cl. 428-209.000.
- Harris, John F., Jr., 4,294,955, Cl. 528-176.000.
- Lee, Ross A., 4,294,909, Cl. 430-291.000.
- Lovell, Peter J.; and Saunders, Ian C. B., 4,294,794, Cl. 264-328.100.
- Stock, Albert M.; and Verbsky, James D., 4,294,997, Cl. 568-855.000.
- Urquhart, Thomas, 4,294,646, Cl. 156-500.000.
- Durant, Graham J.; Ganellin, Charon R.; and Vickers, Margaret R., to Smith Kline & French Laboratories Limited. Pharmaceutical compositions. 4,294,854, Cl. 424-326.000.
- Durkee, Richard G. Heavy metal removal apparatus. 4,294,434, Cl. 266-170.000.
- Dynamit Nobel Aktiengesellschaft: See—
Brede, Uwe; and Kern, Heinz, 4,294,648, Cl. 156-627.000.
- Dynatrol Consultants (U.K.) Limited: See—
Thompson, Raymond V.; Todd, Alan; and Constantine, Albert B., 4,294,549, Cl. 366-164.000.
- Dyneer Corporation: See—
St. John, Richard C., 4,294,342, Cl. 192-105.0CD.
- E M I Limited: See—
Hounsfield, Godfrey N., 4,295,195, Cl. 364-414.000.
- E. R. Squibb & Sons, Inc.: See—
Vellucci, Enzo, 4,294,894, Cl. 424-49.000.
- Eagle-Picher Industries, Inc.: See—
Hayes, Richard H., 4,294,144, Cl. 83-71.000.
- Eastman Kodak Company: See—
Adin, Anthony; Boettcher, John W.; and Fleming, James C., 4,294,912, Cl. 430-341.000.
- Bechle, Philip D.; and Roth, Joseph A., 4,294,906, Cl. 430-207.000.
- Bellas, Michael; and Cahill, Robert, 4,294,991, Cl. 568-650.000.
- Fyson, John R., 4,294,914, Cl. 430-418.000.
- Guild, John R., 4,294,911, Cl. 430-326.000.
- Hyatt, John A., 4,294,761, Cl. 260-338.000.
- Paxton, Kenneth B., 4,294,536, Cl. 355-14.00C.
- Pfeffer, Robert M.; and Braun, Charles H., 4,294,104, Cl. 73-9.000.
- Upson, Donald A.; Campbell, Gerald A.; and Kestner, Diane E., 4,294,739, Cl. 260-29.6RW.
- Eaton Corporation: See—
Lade, Robert W.; Spellman, Gordon B.; Jaskolski, Stanley V.; Schutten, Herman P.; and Jaeschke, James R., 4,295,058, Cl. 307-252.00A.
- Pohl, Walter, 4,295,114, Cl. 337-3.000.
- Ebara Corporation: See—
Aoki, Shinji; Kawamura, Keita; Kimura, Hitoshi; Katayama, Tsutomu; Kaido, Chikara; and Yoshida, Hiroshi, 4,294,674, Cl. 204-157.10H.
- Ebauches S.A.: See—
Luscher, Jacob, 4,295,056, Cl. 307-221.00C.
- Eberle, Jurg: See—
Stauber, Hans-Ulrich; and Eberle, Jurg, 4,294,345, Cl. 198-683.000.
- Eberle, William J., to General Battery Corporation. Tumble dumper. 4,294,292, Cl. 141-1.000.
- Ebersberger, Otto; and Kuehnle, Werner, to Siemens Aktiengesellschaft. X-Ray diagnostic generator with an inverter supplying the high-tension transformer. 4,295,049, Cl. 250-409.000.
- Eckart, Erich G. Safety ski binding comprising a sole plate. 4,294,461, Cl. 280-618.000.
- Eckel, Alfred: See—
Rauschert, Willi; Rieger, Gerald; Bock, Erich; and Eckel, Alfred, 4,294,172, Cl. 102-473.000.
- Eckhardt, Fritz; and Schonherr, Walter, to Patent-Treuhand-Gesellschaft fur elektrische Gluhlampen m.b.H. Electric lamp with cementless attached base. 4,295,076, Cl. 313-223.000.
- Ecole Polytechnique: See—
Drouin, Gilbert; and Sibille, Jacques, 4,294,015, Cl. 33-174.00D.
- Edwards, Merle L., to FMC Corporation. Light weight snow thrower. 4,294,027, Cl. 37-43.00R.
- Egorov, Viktor P.; Ognevsky, Viktor A.; Orlovsky, Anatoly G.; Ostrovsky, Grigory A.; Ryskind, Alexandr M.; Stepin, Anatoly L.; Trofimov, Oleg F.; and Shklyarov, Isaak N. Apparatus for manufacturing steel spring leaves. 4,294,098, Cl. 72-128.000.
- Ehrenreich, Leo C.: See—
Klingaman, Richard M.; and Ehrenreich, Leo C., 4,294,750, Cl. 260-40.00R.
- Eibner, Jules A.; and Kanamuller, Franz X., to Sperry Corporation. Fiber optic cable connector. 4,295,043, Cl. 250-227.000.
- Eibofner, Eugen, to Kaltenbach & Voigt GmbH & Co. Servicing composition for spraying on medical instruments. 4,294,797, Cl. 422-36.000.
- Eida, Toshiaki: See—
Hidaka, Hidemasa; Kohno, Toshiaki; and Eida, Toshiaki, 4,294,623, Cl. 127-55.000.
- Einset, Eystein. Ostomy device. 4,294,252, Cl. 128-283.000.
- Eisele, Erwin; Charzinski, Hans-Peter; and Binder, Klaus, to Daimler-Benz Aktiengesellschaft. Internal combustion engine. 4,294,209, Cl. 123-293.000.
- EKA AB: See—
Sunden, Olof, 4,294,885, Cl. 428-404.000.

Ekman Engineering AG: See—
Ekman, Kjell R., 4,294,473, Cl. 285-50.000.
Ekman, Kjell R., to Ekman Engineering AG. Device at mutually lockable first and second parts. 4,294,473, Cl. 285-50.000.
Electric Power Research Institute: See—
Stolecki, William E., 4,294,472, Cl. 285-27.000.
Electric Power Research Institute, Inc.: See—
Kim, Dae K.; Bertolacini, Ralph J.; Gutberlet, L. Charles; and Robinson, Ken K., 4,294,685, Cl. 208-10.000.
Randolph, Alan D., 4,294,807, Cl. 423-242.000.
Electro-Therm, Inc.: See—
Drugmand, Lester D., 4,295,035, Cl. 219-536.000.
Electrochemische Energieconversie, N.V.: See—
Alfenaar, Marinus, 4,294,892, Cl. 429-13.000.
Electrolux Corporation: See—
Bowerman, Leonard E., 4,294,595, Cl. 55-213.000.
Electrolyser Corporation Ltd., The: See—
LeRoy, Rodney L., 4,294,274, Cl. 137-7.000.
Electronic Systems Engineering, Inc.: See—
Anderson, Kenneth W.; Summerhays, Brent; and Cazier, Verl O., 4,295,044, Cl. 250-229.000.
Electronics Corporation of America: See—
Cade, Phillip J., 4,295,129, Cl. 340-520.000.
Eli Lilly and Company: See—
Matsumoto, Ken, 4,294,964, Cl. 544-249.000.
Elliott, Thomas J.; and Ford, David, to Beecham Group Limited. Astringent or degreasing lotion. 4,294,823, Cl. 424-78.000.
Ellis, Paul R., Jr., to GTE Automatic Electric Laboratories, Inc. Method of mounting thick film hybrid circuits in printed circuit boards. 4,294,007, Cl. 29-830.000.
Ellsworth, James P.: See—
Beatty, William E., Jr.; and Ellsworth, James P., 4,295,025, Cl. 200-288.000.
Elser, Wolfgang: See—
Mensch, Siegfried; Eppe, Gerhard; and Elser, Wolfgang, 4,294,581, Cl. 8-611.000.
Embleton, Tony F. W.: See—
Baldwin, Stanley L.; Hampton, Vernon; and Embleton, Tony F. W., 4,294,330, Cl. 181-230.000.
Emco Wheaton Inc.: See—
Rabinovich, Evsey, 4,294,378, Cl. 220-323.000.
Emerson Electric Co.: See—
Hansen, John M., 4,294,044, Cl. 51-135.0BT.
Emhart Industries, Inc.: See—
Winzer, Frederick W.; and Ault, James R., 4,294,603, Cl. 65-346.000.
Energy Systems Corporation: See—
Mayo, Kenneth E., 4,294,225, Cl. 126-204.000.
Eng, George: See—
Klein, David I., 4,294,035, Cl. 46-227.000.
Engelhard, Thomas E. Window boot. 4,294,485, Cl. 296-166.000.
Enomoto, Minoru; Yoneda, Takao; and Takeuchi, Yoshiyuki, to Toyoda Koki Kabushiki Kaisha. Grinding machine with a sizing device. 4,294,045, Cl. 51-165.710.
Enomoto, Satoru: See—
Takita, Hitoshi; Mukaida, Yutaka; and Enomoto, Satoru, 4,294,770, Cl. 260-413.000.
Enser, Mats A.; Hallberg, Lars O.; and Stalberg, Nils G., to International Business Machines Corporation. Device for optical character reading. 4,295,121, Cl. 340-146.3MA.
Envirex Inc.: See—
Casper, Thomas J., 4,294,700, Cl. 210-403.000.
Envirotech Corporation: See—
Kahl, Melvin R., 4,294,591, Cl. 55-120.000.
Epicure Products Inc.: See—
Hathaway, Dana B., 4,295,011, Cl. 179-115.5VC.
Eppe, Gerhard: See—
Mensch, Siegfried; Eppe, Gerhard; and Elser, Wolfgang, 4,294,581, Cl. 8-611.000.
Erickson, John W.; and Petrie, Harold L., to Kobe, Inc. Submersible electrically powered centrifugal and jet pump assembly. 4,294,573, Cl. 417-83.000.
Erkfriz, Donald S., to General Electric Company. Indexable finishing insert for a milling cutter. 4,294,565, Cl. 407-113.000.
Ernst, Horst M.: See—
Olschewski, Armin; Brandenstein, Manfred; Walter, Lothar; Ernst, Horst M.; and Schulz, Toni, 4,294,100, Cl. 72-340.000.
Ernsting, John; Morgan, Thomas R.; Palmer, Leonard F. W.; Rivers, Alfred J.; and Robson, Stephen M., to United States of America, Air Force. Respirators. 4,294,243, Cl. 128-201.180.
Errichiello, Dominic R. Book binders and books made with said binders. 4,294,469, Cl. 281-29.000.
Errichiello, Dominic R. Weatherproof portfolios. 4,294,558, Cl. 402-75.000.
Escher Wyss Limited: See—
Biondetti, Mario, 4,293,988, Cl. 29-116.0AD.
Eschinasi, Emile H.; and Castelli, Enrico, to Istituto per la Ricerca Scientifica e Applicata di Technologie Alimentari S.p.A. Process for the preparation of 2,5-dimethyl-4-hydroxy-3(2H)-furanone and its 2,5-dialkyl homologues. 4,294,767, Cl. 260-347.800.
Espejo, Eusebio H. Camper and tent unit. 4,294,486, Cl. 296-167.000.
Espelage, Paul M.: See—
Cutler, John H.; Espelage, Paul M.; and Walker, Loren H., 4,295,086, Cl. 318-759.000.

Espley, David J. C.: See—
Andrews, William J.; Espley, David J. C.; and Philpott, William J. M., 4,294,882, Cl. 428-349.000.
Etablissements F. Nicolle & Cie Societe Anonyme: See—
Remond, Jean R. A., 4,294,028, Cl. 40-359.000.
Etablissements Generaux de Mecanique de l'Ouest: See—
Bronnec, Jean A. L., 4,294,698, Cl. 210-242.300.
Ethicon, Inc.: See—
Jewusiak, Stephen J.; Beroff, Howard; and Schuler, Michael, 4,294,355, Cl. 206-339.000.
Ethyl Corporation: See—
McKinnie, Bonnie G., 4,294,775, Cl. 260-455.00R.
Ettridge, John P. Child's stroller. 4,294,464, Cl. 280-649.000.
Eue, Ludwig: See—
Riebel, Hans-Jochem; Eue, Ludwig; and Faust, Wilfried, 4,294,967, Cl. 546-242.000.
Evans, Arthur J., to Whitlock, Inc. Plenum drying hopper with integral heaters. 4,294,020, Cl. 34-168.000.
Evans, Robert F. Caliper seal assembly. 4,294,492, Cl. 308-8.200.
Evans, Thomas E., to Honeywell Inc. Peak detector. 4,295,099, Cl. 328-151.000.
Everett, Gary L.: See—
Pinaire, Ronald; and Everett, Gary L., 4,294,687, Cl. 208-58.000.
Evrard, Thomas O., to Olin Corporation. Use of selected N-(2,6-dimethylphenyl)-alanine methyl ester compounds as ammonium nitration compounds. 4,294,604, Cl. 71-27.000.
Evva Werk Spezialerzeugung von Zylinder- und Sicherheitsschlossern Gesellschaft m.b.H. & Co. Kommanditgesellschaft: See—
Prunbauer, Kurt, 4,294,091, Cl. 70-276.000.
Exxon Production Research Company: See—
Mifsud, Joseph F., 4,295,213, Cl. 367-41.000.
Exxon Research & Engineering Co.: See—
Kelly, Arnold J., 4,294,105, Cl. 73-28.000.
Klein, Robert R.; and Makowski, Henry S., deceased, 4,294,744, Cl. 260-33.6AQ.
Mayer, Francis X., 4,294,688, Cl. 208-164.000.
Patton, Tad L., 4,294,785, Cl. 264-41.000.
Ezhov, Evgeny I.: See—
Vanjukov, Andrei V.; Mechev, Valery V.; Bystrov, Valentin P.; Ezhov, Evgeny I.; Vasiliev, Mikhail G.; Zaitsev, Vladimir Y.; Romanets, Vladimir A.; Ivanov, Vladimir V.; Golik, Sergei Y.; Grin-Gnatovsky, Evgeny S.; Grechko, Alexandr V.; Savin, Ivan V.; Kozhakhmetov, Sultanbek M.; Meierovich, Veniamin B.; Nagibin, Vladimir D.; Ramazanov, Nariman A.; Umarov, Almas B.; Ziberov, Valentin E.; Kunaev, Askar M.; Takezhanov, Saik T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazheev, Dzhonson T., 4,294,433, Cl. 266-161.000.
Fabryka Obrabiarek Precyzyjnych "Ponar-Bruszkow": See—
Matusz, Zbigniew, 4,294,132, Cl. 74-462.000.
Fairbrother, Robert J.: See—
Knollmueller, Karl O.; Fairbrother, Robert J.; and Gavin, David F., 4,294,713, Cl. 252-28.000.
Fairlie-Clarke, Anthony C., to Vickers Limited. Liquid flow detecting device. 4,295,134, Cl. 340-610.000.
Faler, Gary R.; and Loucks, George R., to General Electric Company. Method and catalyst for making bisphenol. 4,294,995, Cl. 568-728.000.
Falk, Filip; and Falk, Lennart. Dispenser for rolls of paper. 4,294,389, Cl. 225-34.000.
Falk, Lennart: See—
Falk, Filip; and Falk, Lennart, 4,294,389, Cl. 225-34.000.
Falkowski, Leonard; Stefanska, Barbara; Zielinski, Jan; Troka, Elzbieta; Golik, Jerzy; Kolodziejczyk, Pawel; Jarzebski, Andrzej; Cybulska, Emilia; and Borowski, Edward, to Politechnika Gdanska. Water-soluble salts of trimethylammonium derivatives of polyene macrolide antibiotics and the preparation thereof. 4,294,958, Cl. 536-17.00R.
Farah, Alfred E., to Sterling Drug Inc. Ketazocine anesthetic method of use. 4,294,840, Cl. 424-267.000.
Farr, Glyn P. R., to Lucas Industries Limited. Master cylinder assemblies. 4,294,070, Cl. 60-534.000.
Faust, Wilfried: See—
Riebel, Hans-Jochem; Eue, Ludwig; and Faust, Wilfried, 4,294,967, Cl. 546-242.000.
Feffer, Philip C., to Chevron Research Company. Method and apparatus for making bounce crimped yarn. 4,293,985, Cl. 28-254.000.
Feinberg, Emanuel. Automatic furnace vent damper control. 4,294,226, Cl. 126-286.000.
Feldman, Fred, to Armour Pharmaceutical Company. Process for the preparation of highly purified antihemophilic factor. 4,294,826, Cl. 424-101.000.
Feldstein, Neil A.: See—
Kende, Andrew S.; Curran, Dennis P.; King, Margaret L.; and Feldstein, Neil A., 4,294,763, Cl. 260-340.5DP.
Felten & Guillaume Carlswerk: See—
Schmitz, Gunther; and Kierdorf, Hans, 4,294,064, Cl. 57-3.000.
Fennel, John W., Jr.; Hallett, Robert J.; Head, Stanley M.; and Meias, Constantine M., to International Business Machines Corporation. Apparatus to reduce the effect of a mid-talkspurt freeze-out. 4,295,217, Cl. 370-81.000.
Ferag AG: See—
Stauber, Hans-Ulrich; and Eberle, Jurg, 4,294,345, Cl. 198-683.000.
Ferraris Development and Engineering Company Limited: See—
Williams, Garnet M. E.; and Hollis, James E. L., 4,294,262, Cl. 128-726.000.
Ferraro, Frank A.: See—
Chen, Evan N.; and Ferraro, Frank A., 4,294,010, Cl. 30-42.000.

Ferri, Giampiero. Ammunition for a toy weapon. 4,294,173, Cl. 102-281.000.
Ferris, Sean D. Inflatable vehicle cover. 4,294,483, Cl. 296-136.000.
Ferro Manufacturing Corporation: See—
Pickles, Joseph, 4,294,488, Cl. 297-367.000.
Fetterly, Richard V.: See—
Archer, Ronald J.; and Fetterly, Richard V., 4,294,597, Cl. 55-283.000.
Feuerherd, Karl-Heinz: See—
Koenig, Karl-Heinz; Feuerherd, Karl-Heinz; and Oeser, Heinz-Guenter, 4,294,773, Cl. 260-453.00P.
Figg, Anthony V. J.; and Cunningham, Harry, to Norprint Limited. Label applicators. 4,294,645, Cl. 156-384.000.
Filipiak, Stanley E.: See—
Keeler, Robert J.; and Filipiak, Stanley E., 4,295,012, Cl. 200-5.00B.
Finsterwalder, Lorenz, to Gesellschaft zur Wiederaufarbeitung von Kernbrennstoffen mbH. Apparatus for the controllable removal of one or more phases from a liquid-liquid extractor. 4,294,702, Cl. 210-513.000.
Fiquet, Claire: See—
Vanlerberghe, Guy; Sebagn, Henri; and Fiquet, Claire, 4,294,728, Cl. 252-542.000.
Fischell, David R.; and Mazique, Jeffrey C., to United States of America, National Aeronautics and Space Administration. Cervix-to-rectum measuring device in a radiation applicator for use in the treatment of cervical cancer. 4,294,264, Cl. 128-778.000.
Fischer, Armin O., to American Standard Inc. Flow control device. 4,294,289, Cl. 138-44.000.
Fischli, Albert E.; and Szente, Andre, to Hoffmann-La Roche Inc. 7-Isocyanato-1,4-benzodiazepin-2-ones. 4,294,758, Cl. 260-239.30D.
Fisher, Ernest P., Jr.: See—
Yonker, John H.; Fisher, Ernest P., Jr.; and Bills, David, 4,294,315, Cl. 166-322.000.
Fisher, Ian P.; Woods, H. John; and Souhrada, Frank, to Gulf Canada Limited. Process for upgrading heavy hydrocarbonaceous oils. 4,294,686, Cl. 208-56.000.
Fitzke, Rudolf. Catastrophic-exposure emergency kit. 4,294,352, Cl. 206-223.000.
Flack, Max L.: See—
Best, Walter E.; Foshee, William R.; and Flack, Max L., 4,294,093, Cl. 70-369.000.
Flautt, Robert A.: See—
Reynoir, Ronald H.; Flautt, Robert A.; and Leavitt, Clyde M., 4,294,331, Cl. 182-10.000.
Fleischer, Henry. Unique joint especially useful with juvenile furniture and playthings. 4,294,426, Cl. 248-561.000.
Fleming, James C.: See—
Adin, Anthony; Boettcher, John W.; and Fleming, James C., 4,294,912, Cl. 430-341.000.
Flesburg, Edward E., to Caterpillar Tractor Co. Sand core pattern and method of forming a sand mold. 4,294,303, Cl. 164-44.000.
Flynn, Derek J., to Lucas Industries Limited. Master cylinder and reservoir assemblies. 4,294,072, Cl. 60-585.000.
FMC Corporation: See—
Bagnall, Elizabeth A.; Guiliano, Basil A.; and Pfeffer, Henry A., III, 4,294,962, Cl. 544-192.000.
Edwards, Merle L., 4,294,027, Cl. 37-43.00R.
Stilwell, Robert E.; and Westerling, David E., 4,294,059, Cl. 53-448.000.
Foam Controls, Inc.: See—
Szeliga, Philip C., 4,294,277, Cl. 137-101.190.
Focke & Co.: See—
Focke, Heinz H.; and Liedtke, Kurt, 4,294,353, Cl. 206-273.000.
Focke, Heinz; and Liedtke, Kurt, to Focke & Pfuhl. Process for the production of package for cigarettes or the like. 4,294,642, Cl. 156-250.000.
Focke, Heinz H.; and Liedtke, Kurt, to Focke & Co. Side connected cigarette half-packs. 4,294,353, Cl. 206-273.000.
Focke & Pfuhl: See—
Focke, Heinz; and Liedtke, Kurt, 4,294,642, Cl. 156-250.000.
Fogle, Ozzie, to Champion International Corporation. Applicator for direct roll coating. 4,294,187, Cl. 118-244.000.
Foley, John T.: See—
Bilstad, Arnold C.; and Foley, John T., 4,294,320, Cl. 177-1.000.
Ford, David: See—
Elliott, Thomas J.; and Ford, David, 4,294,823, Cl. 424-78.000.
Ford Motor Company: See—
Boaz, Premakaran T., 4,294,867, Cl. 427-96.000.
Fox, David H.; and Kostan, Charles C., 4,295,014, Cl. 200-19.00R.
Hurley, John J., 4,294,133, Cl. 74-501.00P.
Meyer, John H.; and Guerra, Salvatore, 4,294,881, Cl. 428-334.000.
Fory, Werner: See—
Tobler, Hans; Fory, Werner; and Schurter, Rolf, 4,294,606, Cl. 71-88.000.
Foshee, William R.: See—
Best, Walter E.; and Foshee, William R., 4,294,089, Cl. 70-150.000.
Best, Walter E.; Foshee, William R.; and Flack, Max L., 4,294,093, Cl. 70-369.000.
Foster Wheeler Energy Corporation: See—
Gorzegno, Walter P., 4,294,200, Cl. 122-406.00S.
Fouse, Jack A.; and McClaren, Sherwood W., III, to Vought Corporation. Airframe assembly and process. 4,294,419, Cl. 244-117.00R.
Fowler, Donald W.; and Clefford, Douglas H., to United Technologies Corporation. Force feel actuator fault detection with directional threshold. 4,294,162, Cl. 91-434.000.
Fox, Barry C.: See—
Balyoz, John; Chang, Chi S.; Fox, Barry C.; Palmieri, John A.; Ghafghaichi, Majid; Jen, Teh-Sen; and Mooney, Donald B., 4,295,149, Cl. 357-45.000.
Fox, David H.; and Kostan, Charles C., to Ford Motor Company. Ignition distributor with integral common electrode, shaft bearing and high voltage terminal connector. 4,295,014, Cl. 200-19.00R.
Fraenkel, Dan; and Gates, Bruce C., to University of Delaware. Catalyst method for catalyst manufacture and use. 4,294,725, Cl. 252-455.00Z.
Framatome: See—
Guignard, Paul; and Commeau, Alain, 4,294,662, Cl. 219-61.000.
Franconi, Cafiero: See—
Bonori, Maurizio; and Franconi, Cafiero, 4,295,131, Cl. 340-554.000.
Frank, James P., to General Electric Company. Method of assembling a switch and terminal assembly. 4,294,004, Cl. 29-622.000.
Frantom, Richard L., to Allied Chemical Corporation. Seat belt comfort device. 4,294,467, Cl. 280-801.000.
Frantz, Gene A.: See—
Chang, Richard R.; Frantz, Gene A.; and Hawkins, William R., 4,295,181, Cl. 361-395.000.
Franz Plasser Bahnbaumaschinen-Industriegesellschaft m.b.H.: See—
Theurer, Josef; and Riessberger, Klaus, 4,294,041, Cl. 51-5.00C.
Frazier, Calvin H. Splint for reducing fractures of the metacarpals. 4,294,237, Cl. 128-77.000.
Fredriksson, Borje I.: See—
Bohlin, Karl G.; Fredriksson, Borje I.; Karlsson, Kent A. B.; and Nelvig, Lars T., 4,294,412, Cl. 241-30.000.
Freeman, Charles F.; and Villhauer, Kurt, to United States of America, Army. Microchannel plate-in-wall structure. 4,295,073, Cl. 313-105.0CM.
Freeman, Robert W.: See—
Tavlarides, Lawrence L.; Freeman, Robert W.; and Hsia, Alexander M., 4,294,800, Cl. 422-68.000.
Freisler, Erhard, to Ruti Machinery Works Ltd. Process and loom for the production of pile fabrics. 4,294,290, Cl. 139-26.000.
Friese, Axel, to Carl Hahn, G.m.b.H. Tampon with a non-woven wrap. 4,294,253, Cl. 128-285.000.
Froehlig, Guy M., to Bauer, Jerome; and Amer, Myron. Method for substantially instantaneous liquid molding of an article. 4,294,782, Cl. 264-1.400.
Frommelt Industries, Inc.: See—
Frommelt, Sylvan J., 4,293,969, Cl. 14-71.100.
Frommelt, Sylvan J., to Frommelt Industries, Inc. Inflatable seal. 4,293,969, Cl. 14-71.100.
Frost, Henry F.: See—
Jones, William A.; Hing Yuen, Tse Lin Sin Tse; Rytomaa, Tapio; Harper, Norman J.; and Frost, Henry F., 4,294,824, Cl. 424-101.000.
Fry, Timothy S., to GKN Group Services Limited. Wheel support assembly. 4,294,326, Cl. 180-255.000.
Fuji Electric Co., Ltd.: See—
Obata, Toshiharu; Hagyu, Toshimasa; and Kojima, Hisao, 4,294,396, Cl. 228-245.000.
Fuji Photo Film Co., Ltd.: See—
Aono, Toshiaki, 4,294,900, Cl. 430-7.000.
Inoue, Eiichi; Shimizu, Isamu; and Shizukushi, Makoto, 4,294,520, Cl. 350-357.000.
Ohba, Hisao; Oda, Kazutaka; Yabuta, Yukio; and Ohashi, Azusa, 4,294,672, Cl. 204-129.400.
Okishi, Yoshio; Koike, Akinobu; and Miyano, Shizuo, 4,294,905, Cl. 430-175.000.
Tsujino, Nobuyuki; and Hirano, Shigeo, 4,294,919, Cl. 430-559.000.
Watanabe, Shigeru; and Kuzunuki, Tatsuo, 4,295,042, Cl. 250-226.000.
Yagihara, Morio; and Yokota, Yukio, 4,294,918, Cl. 430-553.000.
Yamaguchi, Jun; Naoi, Takashi; Sera, Hideo; Ishigaki, Kunio; and Ogawa, Masasi, 4,294,921, Cl. 430-621.000.
Fuji Photo Optical Co., Ltd.: See—
Doi, Yoshikazu; Sakai, Yutaka; and Ohno, Kazunori, 4,294,521, Cl. 350-426.000.
Fujii, Hiroyuki: See—
Kobayashi, Masatoshi; Shimakawa, George; Hara, Yukio; Fujii, Hiroyuki; and Kabushiki Kaisha Seikosha, 4,293,986, Cl. 29-25.350.
Fujimura, Takeo: See—
Uesaka, Tatsuo; Sugahara, Hiroshi; and Fujimura, Takeo, 4,295,110, Cl. 335-212.000.
Fujisawa, Hidetaka, to Casio Computer Co., Ltd. Music tone generating system. 4,294,154, Cl. 84-1.010.
Fujisawa Pharmaceutical Co., Ltd.: See—
Takaya, Takao; Takasugi, Hisashi; Chiba, Toshiyuki; and Tsuji, Kiyoshi, 4,294,960, Cl. 544-22.000.
Fujita, Mitsuo; and Matsumura, Koji, to Victor Company of Japan, Ltd. System for controlling rotational direction switchover and for variably controlling rotational speed of motor. 4,295,080, Cl. 318-257.000.
Fujitsu Limited: See—
Ohmura, Sohshi, 4,294,651, Cl. 156-662.000.
Fujiwara, Ichiro; Motoki, Yoshiaki; Inoue, Toshinori; and Fukuoka, Kazuma, to Mitsubishi Denki Kabushiki Kaisha. Repeat type time switch. 4,295,015, Cl. 200-38.00R.
Fukada, Tetsuji; and Ise, Yukihiko, to Matsushita Electric Industrial Co., Ltd. Rotary magnetic head apparatus. 4,295,172, Cl. 360-109.000.

- Fukahori, Hidehiko: See—
Iwashita, Tomonori; Fukahori, Hidehiko; and Mashimo, Yukio, 4,294,530, Cl. 354-173.000.
- Fukuda, Hiroyuki: See—
Haga, Toshikatsu; Fukuda, Hiroyuki; Shinoda, Hiroshi; and Hayakawa, Hideharu, 4,294,795, Cl. 264-332.000.
- Fukui, Seiji, to Shimano Industrial Company, Limited. Two stage transmission hub for a bicycle, 4,294,138, Cl. 74-750.00B.
- Fukuoka, Kazuma: See—
Fujiwara, Ichiro; Motoki, Yoshiaki; Inoue, Toshinori; and Fukuoka, Kazuma, 4,295,015, Cl. 200-38.00R.
- Fuller, Mary L., to Ralston Purina Company. Dog food compositions of improved palatability to dogs, 4,294,857, Cl. 426-99.000.
- Funari, Joseph: See—
Bakos, Peter; Darrow, Russell E.; Funari, Joseph; and Poliak, Richard M., 4,294,729, Cl. 252-545.000.
- Funck, Willi; Verheyen, Roland; and Schedler, Heinz, to Schloemann-Siemag Aktiengesellschaft. Overload safety device in hydraulic forming presses, in particular sheet metal form drawing presses, 4,294,103, Cl. 72-453.140.
- Furlet, James L.; and Stadler, Donald A. Automatic accumulating lift and carry transfer mechanism, 4,294,347, Cl. 198-751.000.
- Furr, Danny L., to Phillips Petroleum Company. Fractional distillation column control, 4,295,196, Cl. 364-501.000.
- Fuson, Robert L., to Zimmer USA, Inc. Bone plug inserting system, 4,293,962, Cl. 3-1.900.
- Futaba Denshi Kogyo K.K.: See—
Moto, Masato; and Ito, Seigo, 4,295,082, Cl. 318-599.000.
- Futsumori, Koji: See—
Takago, Toshio; Arai, Masatoshi; and Futsumori, Koji, 4,294,975, Cl. 556-482.000.
- Fyson, John R., to Eastman Kodak Company. Photographic bleach compositions and methods of photographic processing, 4,294,914, Cl. 430-418.000.
- G. D. Searle & Co.: See—
Wagner, Hans A., 4,294,830, Cl. 424-251.000.
- G. L. Rexroth GmbH: See—
Mark, Edgar, 4,295,000, Cl. 13-13.000.
- Gado, Istvan: See—
Alfoldi, Lajos; Balint nee Fodor, Katalin; Kari, Csaba; Torok, Istvan; Szvoboda, Gyorgy; Lang, Tibor; Gado, Istvan; and Ambrus, Gabor, 4,294,927, Cl. 435-172.000.
- GAFF Corporation: See—
Tracy, David J.; Wood, Lindley S.; and Chakrabarti, Paritosh M., 4,294,848, Cl. 424-302.000.
- Gaffney, Edward N., to Lucas Industries Limited. Terminal connector for an electric storage battery, 4,294,505, Cl. 339-231.000.
- Gage, Millard E.; and Landers, Derek J., to Bendix Corporation. The Ignition switch, 4,295,013, Cl. 200-11.00C.
- Gaidis, James M.; and Rosenberg, Arnold M., to W. R. Grace & Co. Process for forming calcium nitrite, 4,294,813, Cl. 423-385.000.
- Gajjar, Jagdishchandra T., to Integrated Energy Systems. Environmental control system, 4,294,404, Cl. 236-49.000.
- Galaske, Folker; and Hack, Oswald, to International Standard Electric Corporation. Multi-row keyboard for typewriters or similar machines, 4,294,555, Cl. 400-488.000.
- Gallic, John. Golf training aid and game, 4,294,450, Cl. 273-176.00F.
- Gamble, Bruce B., to General Electric Company. Cantilevered field winding support for a superconducting AC machine, 4,295,068, Cl. 310-52.000.
- Ganellin, Charon R.: See—
Durant, Graham J.; Ganellin, Charon R.; and Vickers, Margaret R., 4,294,854, Cl. 424-326.000.
- Ganser, Volker: See—
Hartenstein, Johannes; Satzinger, Gerhard; Bahrmann, Heinrich; and Ganser, Volker, 4,294,834, Cl. 424-260.000.
- Ganster, Otto: See—
Grogler, Gerhard; Schwindt, Jurgen; Ganster, Otto; Meiners, Hans-Joachim; and Ruprecht, Hans-Dieter, 4,294,934, Cl. 521-160.000.
- Gardner, Hugh C., to Union Carbide Corporation. Polyester resin compositions, 4,294,751, Cl. 260-400.00R.
- Garfield, Nathaniel H.: See—
McSherry, Thomas W.; and Garfield, Nathaniel H., 4,294,156, Cl. 411-345.000.
- Garrison, Mark R.: See—
Martinelli, Lawrence G.; and Garrison, Mark R., 4,294,640, Cl. 156-213.000.
- Gates, Bruce C.: See—
Fraenkel, Dan; and Gates, Bruce C., 4,294,725, Cl. 252-455.00Z.
- Gates Rubber Company, The: See—
Uba, Toshio, 4,295,029, Cl. 219-75.000.
- Gavin, David F.: See—
Knollmueller, Karl O.; Fairbrother, Robert J.; and Gavin, David F., 4,294,713, Cl. 252-28.000.
- Gazda, Hans O. E. Apparatus for the separation of gas mixtures, particularly the enrichment of a gas mixture in a component containing uranium 235, 4,294,598, Cl. 55-403.000.
- Geary, Carl H., Jr., to Carrier Corporation. Method for securing a wheel to a rotatable shaft, 4,293,996, Cl. 29-446.000.
- Gebruder Loepfe AG: See—
Stutz, Hansruedi, 4,294,545, Cl. 356-386.000.
- Gebrueder Buehler AG: See—
Keller, Alois, 4,294,692, Cl. 209-300.000.
- Geiger, Jack M.: See—
Greenwald, A. Seth; Geiger, Jack M.; Narten, Nathaniel C.; Porritt, Derek S.; Combs, Steven P.; and Brems, John J., 4,294,251, Cl. 128-276.000.
- Geiszler, Willard A., Jr.: See—
Kassman, Allen J.; and Geiszler, Willard A., Jr., 4,294,265, Cl. 131-366.000.
- Gell, Peter L., to Tuscan Industries Pty. Limited. Tape cartridge, 4,294,418, Cl. 242-197.000.
- Gendron, Wilfred H., to Westvaco Corporation. Non-gusseted expandable envelope, 4,294,400, Cl. 229-68.00R.
- General Atomic Company: See—
Graf, Fredy E.; Mahler, William M.; and Malan, Howard J., 4,295,051, Cl. 250-569.000.
- General Battery Corporation: See—
Eberle, William J., 4,294,292, Cl. 141-1.000.
- General Dynamics Corporation: See—
Couchman, James C., 4,294,122, Cl. 73-761.000.
- General Electric Company: See—
Anthony, Thomas R.; and Cline, Harvey E., 4,294,631, Cl. 148-133.000.
- Bair, Eugene C.; and Hopkins, Willard C., 4,294,006, Cl. 29-701.000.
- Balko, Edward N., 4,294,671, Cl. 204-128.000.
- Carollo, Jerome T.; and Barbarasch, Joseph, 4,295,159, Cl. 358-22.000.
- Cordray, Daniel E., 4,295,175, Cl. 361-69.000.
- Cutler, John H.; Espelage, Paul M.; and Walker, Loren H., 4,295,086, Cl. 318-759.000.
- Erkfriz, Donald S., 4,294,565, Cl. 407-113.000.
- Faler, Gary R.; and Loucks, George R., 4,294,995, Cl. 568-728.000.
- Frank, James P., 4,294,004, Cl. 29-622.000.
- Gamble, Bruce B., 4,295,068, Cl. 310-52.000.
- Lafuze, David L., 4,295,085, Cl. 318-721.000.
- Laskow, William; and Morelock, Charles R., 4,294,788, Cl. 264-101.000.
- Li, Ming K., 4,294,993, Cl. 568-724.000.
- Li, Ming K., 4,294,994, Cl. 568-724.000.
- Oler, Robert A., 4,294,812, Cl. 423-357.000.
- Orlando, Charles M.; and Loucks, George R., 4,294,954, Cl. 528-174.000.
- Patenaude, Raymond A.; Cozzy, Thomas W.; and Bullis, Stephen J., 4,294,158, Cl. 89-12.000.
- Quinn, Clayton B.; and Hilakos, William, 4,294,953, Cl. 528-128.000.
- Sedlak, John M.; and Lawrance, Richard J., 4,294,608, Cl. 75-0.50A.
- Steigerwald, Robert L., 4,295,059, Cl. 307-253.000.
- General Motors Corporation: See—
Atkins, Larry P., 4,294,895, Cl. 429-84.000.
- Donley, William B., 4,295,209, Cl. 365-178.000.
- Givan, David E.; and Ashton, Charles R., 4,295,069, Cl. 310-67.00R.
- Lake, Donald E.; and Hart, John M., Jr., 4,295,117, Cl. 338-4.000.
- Wendler, Paul O.; and Welsh, Clarence E., 4,294,159, Cl. 91-375.00A.
- Witherspoon, Romeo R., 4,294,899, Cl. 429-206.000.
- General Refractories Company: See—
Anthonis, Henry E., 4,294,618, Cl. 501-129.000.
- General Signal Corporation: See—
Heydweiller, James, 4,295,020, Cl. 200-61.45R.
- Geng, Hellmuth R.: See—
Blum, Arnold; Geng, Hellmuth R.; Schulze-Schoelling, Hermann; and Spaeth, Bernd, 4,295,220, Cl. 371-61.000.
- Genovese, Frank C., to Xerox Corporation. Thermoremanent magnetic imaging member and system, 4,294,901, Cl. 430-39.000.
- Georgia-Pacific Corporation: See—
DeLuca, Raymond F., 4,294,778, Cl. 261-30.000.
- Gerber Garment Technology, Inc.: See—
Pearl, David R., 4,294,047, Cl. 51-327.000.
- Gerboth, Patrick L.; and Thompson, Charles W., to SGM Co., Inc. Hydraulic blower system for vehicles, 4,294,082, Cl. 62-244.000.
- Gerdes, Theodor, to Blau KG Fabrik Fur Kraftfahrzeugteile. Vehicle fuel tank sealing cap, 4,294,375, Cl. 220-293.000.
- Gerdes, Theodor, to Blau KG Fabrik fur Kraftfahrzeugteile. Relief valve, 4,294,281, Cl. 137-541.000.
- Germer, Kurt: See—
Botcher, Winfried; and Germer, Kurt, 4,294,182, Cl. 112-21.000.
- Geroc, Andre. Intraluminal anastomosis, 4,294,255, Cl. 128-334.00C.
- Gerstenberg, Roy W., to Leeson Corporation. Feed roll device for sheet granulator, 4,294,414, Cl. 241-222.000.
- Gesellschaft zur Wiederaufarbeitung von Kernbrennstoffen mbH: See—
Finsterwalder, Lorenz, 4,294,702, Cl. 210-513.000.
- Gevaud, Roland; and Tallon, Jacques, to Compagnie Industrielle des Telecommunications Cit-Alcatel. Leak detector, 4,294,106, Cl. 73-40.700.
- Ghafghaichi, Majid: See—
Balyoz, John; Chang, Chi S.; Fox, Barry C.; Palmieri, John A.; Ghafghaichi, Majid; Jen, Teh-Sen; and Mooney, Donald B., 4,295,149, Cl. 357-45.000.
- Gibson, Stephen. Stereoscopic apparatus and method of using same, 4,295,153, Cl. 358-3.000.
- Giesenberg, Peter, to Bodenseewerk Geratetechnik GmbH. Device for erecting and stabilizing a gyro vertical, 4,294,128, Cl. 74-5.440.
- Giffo, Henrik. Acid resistant, high-strength steel suitable for polishing, 4,294,613, Cl. 75-124.000.

- Gilbert Products: See—
Lieberman, Gilbert R., 4,294,503, Cl. 339-119.00L.
- Gilcrest, Richard K.: See—
Rodenberg, Joseph H.; and Gilcrest, Richard K., 4,294,195, Cl. 119-20.000.
- Gill, Peter J.: See—
Berger, Mitchell H.; Gill, Peter J.; and Maresca, Louis M., 4,294,956, Cl. 528-179.000.
- Gioello, Debbie A. Stretch knit body suit with padded areas, 4,293,959, Cl. 2-243.00B.
- Givan, David E.; and Ashton, Charles R., to General Motors Corporation. Armature shaft for a vehicle starter motor, 4,295,069, Cl. 310-67.00R.
- GKN Group Services Limited: See—
Fry, Timothy S., 4,294,326, Cl. 180-255.000.
- GKN-Stenman AB: See—
Haggstrom, Ake T. L., 4,294,092, Cl. 70-364.00A.
- Glance, William R.: See—
Ibsen, Robert L.; and Glance, William R., 4,294,349, Cl. 206-63.500.
- Gledhill, Richard J.: See—
Aubusson, Russell C.; and Gledhill, Richard J., 4,295,182, Cl. 361-400.000.
- Global Marine Inc.: See—
Person, Abraham; Wetmore, Sherman B.; and McNary, James F., 4,294,564, Cl. 405-195.000.
- Glockler, Otto, to Robert Bosch GmbH. Electrically controlled fuel injection apparatus, 4,294,217, Cl. 123-491.000.
- Glockler, Otto: See—
Hans, Waldmar; Sauer, Rudolf; Glockler, Otto; Steinbrenner, Ulrich; Gunther, Dieter; and Lembke, Manfred, 4,294,215, Cl. 123-470.000.
- Glymph, Ronald C. Pocket pipe, 4,294,267, Cl. 131-330.000.
- GM Research: See—
Murex, James D., 4,294,496, Cl. 312-208.000.
- Godard, Pierre; and Billot, Michel, to Sait-Societe des Accumulateurs Fixes et de Traction. Method of controlling the heating of a chamber and a controlled chamber-heating installation, 4,294,309, Cl. 165-18.000.
- Godecke Aktiengesellschaft: See—
Hartenstein, Johannes; Satzinger, Gerhard; Bahrmann, Heinrich; and Ganser, Volker, 4,294,834, Cl. 424-260.000.
- Golay, Marcel J. E. Heat insulator, 4,294,231, Cl. 126-441.000.
- Gold, Barry L.; and Bolesky, Richard C., to Zimmer USA, Inc. Unrestrained elbow prosthesis, 4,293,963, Cl. 3-1.910.
- Goldwell GmbH: See—
Lorenz, Heribert; and Tennigkeit, Jurgen, 4,294,293, Cl. 141-100.000.
- Golik, Jerzy: See—
Falkowski, Leonard; Stefanska, Barbara; Zielinski, Jan; Troka, Elzbieta; Golik, Jerzy; Kolodziejczyk, Pawel; Jarzebski, Andrzej; Cybulska, Emilia; and Borowski, Edward, 4,294,958, Cl. 536-17.00R.
- Golik, Sergei Y.: See—
Vanjukov, Andrei V.; Mechev, Valery V.; Bystrov, Valentin P.; Ezhov, Evgeny I.; Vasiliev, Mikhail G.; Zaitsev, Vladimir Y.; Romanets, Vladimir A.; Ivanov, Vladimir V.; Golik, Sergei Y.; Grin-Gnatovsky, Evgeny S.; Grechko, Alexandr V.; Savin, Ivan V.; Kozhakhmetov, Sultanbek M.; Meierovich, Veniamin B.; Nagibin, Vladimir D.; Ramazanov, Nariman A.; Umarov, Almas B.; Ziberov, Valentin E.; Kunaev, Askar M.; Takezhanov, Sauk T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazheev, Dzhanon T., 4,294,433, Cl. 266-161.000.
- Gombas, Laszlo A. Bottom roll-forming method and apparatus and resultant can end configuration, 4,294,097, Cl. 72-94.000.
- Goodrich, George W.: See—
O'Connor, James M.; and Goodrich, George W., 4,294,518, Cl. 350-357.000.
- Goodwin, Robert J.: See—
Wetzel, William H.; Pan, Hsi-Lung; Goodwin, Robert J.; and Wilkinson, John E., 4,294,996, Cl. 568-776.000.
- Goodyear Aerospace Corporation: See—
Uram, John R., Jr., 4,294,886, Cl. 428-412.000.
- Goodyear Tire & Rubber Company, The: See—
Henderson, James N., 4,294,942, Cl. 525-314.000.
- Gordon, Roy G. Apparatus for vapor coating a moving glass substrate, 4,294,193, Cl. 118-718.000.
- Gorzegno, Walter P., to Foster Wheeler Energy Corporation. Variable pressure vapor generator utilizing crossover circuitry for the furnace boundary wall fluid flow tubes, 4,294,200, Cl. 122-406.00S.
- Gottbrecht, Tom L.; and Shepherd, Glen C., to Texas Instruments Incorporated. Method of fabricating capacitive touch switch panel, 4,293,987, Cl. 29-25.420.
- Goudie, Alexander C.: See—
Cassidy, Frederick; and Goudie, Alexander C., 4,294,972, Cl. 548-264.000.
- Gould Inc.: See—
Robins, Charles T., 4,295,022, Cl. 200-147.00R.
- Gowans, Neil A.; and Riester, William C., to Trico Products Corporation. Arm to blade connector, 4,293,974, Cl. 15-250.320.
- Graco Inc.: See—
Snyder, Irving F.; and Luebeck, Duane A., 4,294,408, Cl. 239-218.500.
- Graf, Fredy E.; Mahler, William M.; and Malan, Howard J., to General Atomic Company. Optical card reader, 4,295,051, Cl. 250-569.000.
- Graham, Alan A.; Haemer, Laurence F.; and Miller, Charles H., to Congoleum Corporation. Solar heat energy collecting systems and methods of making the same, 4,294,786, Cl. 264-46.400.
- Graham, William F., to Du Pont de Nemours, E. I., and Company. Epoxy imide, 4,294,743, Cl. 260-32.8EP.
- Graham, William F., to Du Pont de Nemours, E. I., and Company. Epoxy imide compositions, 4,294,877, Cl. 428-209.000.
- Grane, Henry R.; Jubin, John C., Jr.; and Worrell, G. Richard, to Atlantic Richfield Company. Preparing oxygen-containing fuel wherein tertiary butyl alcohol is the major product of the process, 4,294,999, Cl. 568-910.000.
- Granger, Bruce A.; and Klis, David S., to Toro Company. The Clutch assembly, 4,294,339, Cl. 192-12.0BA.
- Granger, Charles A.: See—
Bencene, Robert C.; and Granger, Charles A., 4,293,970, Cl. 15-21.00D.
- Granzow, Daniel B.: See—
Carter, Garry L.; Granzow, Daniel B.; and Bayham, Edward L., 4,294,247, Cl. 128-214.00D.
- Gardel, Jean-Luc: See—
Couderc, Pierre; Gardel, Jean-Luc; and Caux, Gerard, 4,294,717, Cl. 252-97.000.
- Graubmaier, Josef: See—
Aulich, Hubert; and Graubmaier, Josef, 4,294,811, Cl. 423-350.000.
- Graves, J. Robert: See—
Rutledge, Wyman C.; Graves, J. Robert; and Cassill, William G., 4,294,111, Cl. 73-150.00R.
- Gray, Derek C.: See—
Jack, James; and Gray, Derek C., 4,294,796, Cl. 264-559.000.
- Gray, Robert L.: See—
Picunko, Thomas; Kramer, Henry H.; Dam, Naim G.; and Gray, Robert L., 4,294,259, Cl. 128-653.000.
- Graziano, Robert E.: See—
Dawless, Robert K.; and Graziano, Robert E., 4,294,612, Cl. 75-68.00R.
- Great Lakes Carbon Corporation: See—
Burton, Edward D., 4,294,610, Cl. 75-43.000.
- Greatbatch, Wilson. Rate controlled digital pacemaker, 4,294,256, Cl. 128-419.0PT.
- Grechko, Alexandr V.: See—
Vanjukov, Andrei V.; Mechev, Valery V.; Bystrov, Valentin P.; Ezhov, Evgeny I.; Vasiliev, Mikhail G.; Zaitsev, Vladimir Y.; Romanets, Vladimir A.; Ivanov, Vladimir V.; Golik, Sergei Y.; Grin-Gnatovsky, Evgeny S.; Grechko, Alexandr V.; Savin, Ivan V.; Kozhakhmetov, Sultanbek M.; Meierovich, Veniamin B.; Nagibin, Vladimir D.; Ramazanov, Nariman A.; Umarov, Almas B.; Ziberov, Valentin E.; Kunaev, Askar M.; Takezhanov, Sauk T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazheev, Dzhanon T., 4,294,433, Cl. 266-161.000.
- Greenlee Bros. & Co.: See—
Kolnes, Kenneth O.; and Johnson, Wynsel J., 4,294,442, Cl. 269-101.000.
- Greenwald, A. Seth; Geiger, Jack M.; Narten, Nathaniel C.; Porritt, Derek S.; Combs, Steven P.; and Brems, John J. Method of suction lavage, 4,294,251, Cl. 128-276.000.
- Greppmair, Martin; and Grunwald, Wittloff, to Wacker Werke GmbH & Co. KG. Crank gear with adjustable crank radius for motor driven working implements, 4,294,136, Cl. 74-600.000.
- Grin-Gnatovsky, Evgeny S.: See—
Vanjukov, Andrei V.; Mechev, Valery V.; Bystrov, Valentin P.; Ezhov, Evgeny I.; Vasiliev, Mikhail G.; Zaitsev, Vladimir Y.; Romanets, Vladimir A.; Ivanov, Vladimir V.; Golik, Sergei Y.; Grin-Gnatovsky, Evgeny S.; Grechko, Alexandr V.; Savin, Ivan V.; Kozhakhmetov, Sultanbek M.; Meierovich, Veniamin B.; Nagibin, Vladimir D.; Ramazanov, Nariman A.; Umarov, Almas B.; Ziberov, Valentin E.; Kunaev, Askar M.; Takezhanov, Sauk T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazheev, Dzhanon T., 4,294,433, Cl. 266-161.000.
- Grogler, Gerhard; Schwindt, Jurgen; Ganster, Otto; Meiners, Hans-Joachim; and Ruprecht, Hans-Dieter, to Bayer Aktiengesellschaft. Process for the production of elastic, optionally cellular, polyurethane ureas, 4,294,934, Cl. 521-160.000.
- Grolet, Pierre: See—
Desbrandes, Robert; and Grolet, Pierre, 4,294,318, Cl. 175-321.000.
- Grossag GmbH: See—
Assmann, Jurgen, 4,295,034, Cl. 219-400.000.
- Grossin, Richard J. A. M.: See—
Boy-Marcotte, Jean-Louis; Junot, Henri D. M.; Grossin, Richard J. A. M.; and Chevalier, Philippe J. M. R., 4,294,232, Cl. 126-443.000.
- Grossmann, Klaus: See—
Tomoff, Toma; Chlosta, Wolfgang; Henninger, Heinz; Tamm, Rolf; and Grossmann, Klaus, 4,294,126, Cl. 73-864.210.
- Grossoleil, Jacques: See—
Daniel, Jean-Claude; Grossoleil, Jacques; and Rouillet, Robert, 4,294,704, Cl. 210-651.000.
- Grove, Louis C., Jr.: See—
Peterson, Charles A.; and Grove, Louis C., Jr., 4,295,174, Cl. 361-16.000.
- Grovesteen, William R.; and Jones, John A., to American Optical Corporation. Aerosol filter cartridge, 4,294,599, Cl. 55-485.000.
- Grunwald, Wittloff: See—
Greppmair, Martin; and Grunwald, Wittloff, 4,294,136, Cl. 74-600.000.

- Gruter, Karl; and Leineweber, Jürgen, to Leybold Heraeus GmbH. Mass spectrometer. 4,295,046, Cl. 250-287.000.
- GTE Automatic Electric Laboratories, Inc.: See—
Ellis, Paul R., Jr., 4,294,007, Cl. 29-830.000.
- GTE Laboratories Incorporated: See—
Carlsen, W. John, 4,295,162, Cl. 358-128.600.
Cooperman, Michael, 4,295,089, Cl. 323-351.000.
Haugjsjaa, Paul O., 4,295,137, Cl. 340-781.000.
Norbedo, Robert A.; and Resnick, Martin L., 4,295,208, Cl. 364-900.000.
Resnick, Martin L., 4,295,207, Cl. 364-900.000.
- GTE Products Corporation: See—
Burney, Charles F.; and Laymon, Marvin D., 4,295,132, Cl. 340-562.000.
Kim, Han J.; Peters, Thomas E.; and Gustafson, John, 4,294,616, Cl. 75-234.000.
Lincoln, Howard P.; and Reddinger, Donald M., 4,294,669, Cl. 204-15.000.
Lincoln, Howard P.; and Reddinger, Donald M., 4,294,680, Cl. 204-224.00R.
Lincoln, Howard P.; and Reddinger, Donald M., 4,294,681, Cl. 204-224.00R.
Lincoln, Howard P.; and Reddinger, Donald M., 4,294,789, Cl. 264-102.000.
Webb, Edward A.; McKenna, John F.; and Makar, Frank B., Jr., 4,295,075, Cl. 313-220.000.
- Guenot, Bernard: See—
Boutin, Jean; Guenot, Bernard; and Jamet, Bruno, 4,294,676, Cl. 204-159.230.
- Gueret, Jean-Louis, to L'Oreal. Closing device, with a tiltable nozzle, for a pressurized container. 4,294,410, Cl. 239-577.000.
- Guergen, Karlheinz. Cutter head for rotary percussion drills. 4,294,319, Cl. 175-389.000.
- Guerra, Salvatore: See—
Meyer, John H.; and Guerra, Salvatore, 4,294,881, Cl. 428-334.000.
- Guignard, Paul; and Commeau, Alain, to Framatome. Process for the final assembly of a nuclear reactor vessel. 4,294,662, Cl. 219-61.000.
- Guild, John R., to Eastman Kodak Company. Development of light-sensitive quinone diazide compositions using sulfite stabilizer. 4,294,911, Cl. 430-326.000.
- Guiliano, Basil A.: See—
Bagnall, Elizabeth A.; Guiliano, Basil A.; and Pfeffer, Henry A., III, 4,294,962, Cl. 544-192.000.
- Gulf Canada Limited: See—
Fisher, Ian P.; Woods, H. John; and Souhrada, Frank, 4,294,686, Cl. 208-56.000.
- Gunther, Dieter: See—
Hans, Waldmar; Sauer, Rudolf; Glockler, Otto; Steinbrenner, Ulrich; Gunther, Dieter; and Lembke, Manfred, 4,294,215, Cl. 123-470.000.
- Gustafson, John: See—
Kim, Han J.; Peters, Thomas E.; and Gustafson, John, 4,294,616, Cl. 75-234.000.
- Gutberlet, L. Charles: See—
Kim, Dae K.; Bertolacini, Ralph J.; Gutberlet, L. Charles; and Robinson, Ken K., 4,294,685, Cl. 208-10.000.
- Gyogyszerkutató Intézet: See—
Alfoldi, Lajos; Balint nee Fodor, Katalin; Kari, Csaba; Torok, Istvan; Szvoboda, Gyorgy; Lang, Tibor; Gado, Istvan; and Ambrus, Gabor, 4,294,927, Cl. 435-172.000.
- H. F. & Ph. F. Reemtsma: See—
Wilfer, Oskar, 4,294,399, Cl. 229-44.0CB.
- Haase, Margaret J.; Hasse, Meredith; and Halle, Joan. Shower party name plate and favor. 4,294,350, Cl. 206-216.000.
- Hachino, Hiroaki: See—
Takahashi, Minoru; Tanigami, Takahiko; Uchiyama, Kaoru; Minorikawa, Hitoshi; Nishihara, Motohisa; Kawakami, Kanji; Suzuki, Seiko; Hachino, Hiroaki; and Misawa, Yutaka, 4,295,115, Cl. 338-4.000.
- Hack, Oswald: See—
Galaske, Folker; and Hack, Oswald, 4,294,555, Cl. 400-488.000.
- Haemer, Laurence F.: See—
Graham, Alan A.; Haemer, Laurence F.; and Miller, Charles H., 4,294,786, Cl. 264-46.400.
- Haussinger, Peter: See—
Linde, Gerhard; Haussinger, Peter; and Schliebener, Claus, 4,294,590, Cl. 55-48.000.
- Haga, Toshikatsu; Fukuda, Hiroyuki; Shinoda, Hiroshi; and Hayakawa, Hideharu, to Kureha Kagaku Kogyo Kabushiki Kaisha; and NGK Insulators, Ltd. Stabilized electrocast zirconia refractories. 4,294,795, Cl. 264-332.000.
- Haggstrom, Ake T. L., to GKN-Stenman AB. Cylinder lock having spring-actuated pins. 4,294,092, Cl. 70-364.00A.
- Hagyu, Toshimasa: See—
Obata, Toshiharu; Hagyu, Toshimasa; and Kojima, Hisao, 4,294,396, Cl. 228-245.000.
- Haji, Katsumi: See—
Hata, Hidetoh; Haji, Katsumi; Sako, Kazushige; Shibata, Yoji; and Achiha, Masahiko, 4,295,154, Cl. 358-4.000.
- Hajime Industries Ltd.: See—
Yoshida, Hajime, 4,295,120, Cl. 340-146.3MA.
- Hall, John B.: See—
Sprecker, Mark A.; Hall, John B.; and Schmitt, Frederick L., 4,294,266, Cl. 131-277.000.
- Hall, John W.: See—
Moore, Ronald D.; and Hall, John W., 4,294,112, Cl. 73-162.000.
- Hallberg, Lars O.: See—
Enser, Mats A.; Hallberg, Lars O.; and Stalberg, Nils G., 4,295,121, Cl. 340-146.3MA.
- Halle, Joan: See—
Haase, Margaret J.; Hasse, Meredith; and Halle, Joan, 4,294,350, Cl. 206-216.000.
- Hallett, Robert J.: See—
Fennel, John W., Jr.; Hallett, Robert J.; Head, Stanley M.; and Melas, Constantine M., 4,295,217, Cl. 370-81.000.
- Halvorsen, Jack R.: See—
Borja, Jesus; and Halvorsen, Jack R., 4,295,003, Cl. 174-53.000.
- Hammer, Josef: See—
Sindlinger, Rainer; and Hammer, Josef, 4,294,493, Cl. 308-10.000.
- Hammersand, Fred G.: See—
Carter, Don R.; Doner, Claude E.; Hammersand, Fred G.; and Tomcavage, Joseph R., 4,295,077, Cl. 313-293.000.
- Hampton, Vernon: See—
Baldwin, Stanley L.; Hampton, Vernon; and Embleton, Tony F. W., 4,294,330, Cl. 181-230.000.
- Hanamura, Syoji: See—
Takemoto, Iwao; Koike, Norio; Ohba, Shinya; Ando, Haruhisa; Nakai, Masaaki; Hanamura, Syoji; Izawa, Ryuichi; Kubo, Masaharu; Aoki, Masakazu; and Tanaka, Shuhei, 4,295,055, Cl. 307-221.00C.
- Hannes Marker: See—
Sedlmayr, Gerhard, 4,294,458, Cl. 280-605.000.
- Hans, Waldmar; Sauer, Rudolf; Glockler, Otto; Steinbrenner, Ulrich; Gunther, Dieter; and Lembke, Manfred, to Robert Bosch GmbH. Fuel injection system. 4,294,215, Cl. 123-470.000.
- Hansen, John M., to Emerson Electric Co. Tracking mechanism for a belt type sander. 4,294,044, Cl. 51-135.0BT.
- Hara, Haruichi; Kanzaki, Toshihide; Motomuro, Hisanao; and Adachi, Akiyoshi, to Nippon Shokubai Kagaku Kogyo Co. Ltd. Heat resistant catalyst for the production of sulfuric acid for using a gas containing sulfur dioxide in a high concentration. 4,294,723, Cl. 252-440.000.
- Hara, Reinosuke: See—
Otsuka, Chikao; Hara, Reinosuke; and Shigenaka, Yoshito, 4,294,367, Cl. 215-246.000.
- Hara, Yukio: See—
Kobayashi, Masatoshi; Shimakawa, George; Hara, Yukio; Fujii, Hiroyuki; and Kabushiki Kaisha Seikosha, 4,293,986, Cl. 29-25.350.
- Harada, Hideo: See—
Nishimura, Yoshinori; Umeda, Kaoru; and Harada, Hideo, 4,295,224, Cl. 455-156.000.
- Harada, Kunihiro: See—
Harita, Yoshiyuki; Kamoshida, Yoichi; and Harada, Kunihiro, 4,294,908, Cl. 430-286.000.
- Harada, Yoshiaki: See—
Kakihara, Naomichi; Harada, Yoshiaki; and Uedono, Norio, 4,294,706, Cl. 210-762.000.
- Hardy, Frederick E.; and Dewar, Colin A., to Procter & Gamble Company. The Detergent softener with amine ingredient. 4,294,710, Cl. 252-8.800.
- Hardy, Frederick E.; and Stoddart, Barry, to Procter & Gamble Company. The Washing and softening compositions and methods for their manufacture. 4,294,711, Cl. 252-8.750.
- Hardy, Nicolas; and Dancot, Georges, to Propylor (Societe Anonyme). Process for the purification of organic solutions of percarboxylic acids. 4,294,776, Cl. 260-502.00R.
- Harigane, Kotaro: See—
Takahashi, Tetsuo; Taguchi, Yoshinobu; Harigane, Kotaro; Ito, Tetsuro; and Kato, Akihiro, 4,294,000, Cl. 29-564.600.
- Harita, Yoshiyuki; Kamoshida, Yoichi; and Harada, Kunihiro, to Japan Synthetic Rubber Co., Ltd. Photoresist composition containing modified cyclized diene polymers. 4,294,908, Cl. 430-286.000.
- Harjar, Martin J.: See—
Hastings, Donald R.; and Harjar, Martin J., 4,294,411, Cl. 239-707.000.
- Harkleroad, James F. Mortar/concrete hand-mixing tub. 4,294,547, Cl. 366-1.000.
- Harm, Josephus J. D. Prefabricated chimney-shaft. 4,294,474, Cl. 285-133.00R.
- Harper, Norman J.: See—
Jones, William A.; Hing Yuen, Tse Lin Sin Tse; Rytomaa, Tapio; Harper, Norman J.; and Frost, Henry F., 4,294,824, Cl. 424-101.000.
- Harris Corporation: See—
Pan, Jing-Jong, 4,295,225, Cl. 455-601.000.
- Harris, George S., to Syntex (U.S.A.) Inc. Use of 4,5-dihydro-2-lower alkoxycarbonylamino-4-phenyl imidazoles and substituted phenyl derivatives thereof as anti-hypertensive agents. 4,294,844, Cl. 424-273.00R.
- Harris, John F., Jr., to Du Pont de Nemours, E. I., and Company. Polymers from phenylterephthalic acid. 4,294,955, Cl. 528-176.000.
- Harrison, John M.: See—
Johnson, Avery R.; McGurk, Richard G.; and Harrison, John M., 4,295,008, Cl. 179-18.0BC.
- Harrison, Loren C. Water sensitive probe valve for use with a gas leak detector. 4,294,276, Cl. 137-67.000.
- Harsy, Gabor, to Sig Schweizerische Industrie-Gesellschaft. Swivel-truck spring system for railroad use. 4,294,175, Cl. 105-199.00R.
- Hart, John M., Jr.: See—
Lake, Donald E.; and Hart, John M., Jr., 4,295,117, Cl. 338-4.000.

- Harte, Richard A.: See—
Burgett, Michael W.; and Harte, Richard A., 4,294,817, Cl. 424-8.000.
- Hartenstein, Johannes; Satzinger, Gerhard; Bahrmann, Heinrich; and Ganser, Volker, to Godecke Aktiengesellschaft. Azocine analgesics and method for their preparation. 4,294,834, Cl. 424-260.000.
- Hartley, Henry F.: See—
Darden, Boyd E.; and Hartley, Henry F., 4,295,194, Cl. 364-200.000.
- Hartmann, Juergen; Stedefeder, Joachim; Denzinger, Walter; and Pfohl, Sigberg, to BASF Aktiengesellschaft. Manufacture of paper having a high dry strength and a low wet strength. 4,294,873, Cl. 427-391.000.
- Hartmann, Willy: See—
Scholz, Karl-Heinz; Hartmann, Willy; and Heine, Hans-Georg, 4,294,973, Cl. 548-320.000.
- Hartstein, Allan M., to International Business Machines Corporation. Solid state battery. 4,294,898, Cl. 429-104.000.
- Hashemian, Hashem M.; Kerlin, Thomas W.; and Upadhyaya, Belle R., to University of Tennessee Research Corp. Apparatus for measuring the degradation of a sensor time constant. 4,295,128, Cl. 340-506.000.
- Hashimoto, Akihiko; Nakajima, Yukio; Koiwai, Tamotsu; and Kimura, Toyohiko, to Olympus Optical Company, Ltd. Motor driven camera. 4,294,527, Cl. 354-25.000.
- Hashimoto, Fukashi, to Mitsubishi Petrochemical Co., Ltd. Resin compositions and heat-sealable composite biaxially-stretched films. 4,294,889, Cl. 428-515.000.
- Hashimoto, Sadakatsu, to Sharp Kabushiki Kaisha. Color density stabilizer for electrochromic display. 4,294,519, Cl. 350-357.000.
- Hasse, Meredith: See—
Haase, Margaret J.; Hasse, Meredith; and Halle, Joan, 4,294,350, Cl. 206-216.000.
- Hastings, Donald R.; and Harjar, Martin J., to Nordson Corporation. Electrostatic spray gun. 4,294,411, Cl. 239-707.000.
- Hastings, Jeanne D. Carrying case for artist's materials. 4,294,348, Cl. 206-1.700.
- Hata, Hidetoh; Haji, Katsumi; Sako, Kazushige; Shibata, Yoji; and Achiha, Masahiko, to Nippon Telegraph, Telephone Public Corp.; and Hitachi, Ltd. Digital video and audio file system. 4,295,154, Cl. 358-4.000.
- Hatada, Minoru; Hiyama, Kunio; Ihara, Hirokazu; and Kuma, Hisao, to Hitachi, Ltd. Bus priority control method in loop bus network system. 4,295,122, Cl. 340-147.0LP.
- Hathaway, Dana B., to Epicure Products Inc. Linear excursion-constant inductance loudspeaker. 4,295,011, Cl. 179-115.5VC.
- Hattori, Nobuo, to Olympus Optical Company Ltd. Optical scanner with anamorphic optical system. 4,294,506, Cl. 350-6.800.
- Haugjsjaa, Paul O., to GTE Laboratories Incorporated. Electroluminescent display driver system for thin-film electroluminescent devices requiring electric field reversal. 4,295,137, Cl. 340-781.000.
- Hausdorfer, Michael; and Heitmann, Jürgen, to Robert Bosch GmbH. Method for producing color television signals. 4,295,156, Cl. 358-12.000.
- Havenith, Lothar: See—
Klein, Alfons; Kron, Rudolf; Wedemeyer, Karlfried; Knust, Ernst; and Havenith, Lothar, 4,294,715, Cl. 361-318.000.
- Hawkins, Roland L., to Hoechst Fibers Industries, Div. of American Hoechst Corporation. Staple fiber, finish therefor and process for use of same. 4,294,883, Cl. 428-361.000.
- Hawkins, William R.: See—
Chang, Richard R.; Frantz, Gene A.; and Hawkins, William R., 4,295,181, Cl. 361-395.000.
- Hayakawa, Hideharu: See—
Haga, Toshikatsu; Fukuda, Hiroyuki; Shinoda, Hiroshi; and Hayakawa, Hideharu, 4,294,795, Cl. 264-332.000.
- Hayashi, Masaki; Iguchi, Sadahiko; Okada, Takanori; and Kawasaki, Akiyoshi, to Warner-Lambert Company. Prostaglandin analogues. 4,294,849, Cl. 424-305.000.
- Hayashi, Masayuki: See—
Ifuku, Yasushi; Uchiyama, Hirofumi; and Hayashi, Masayuki, 4,294,861, Cl. 426-475.000.
- Hayatsu, Kazuo: See—
Hino, Minoru; Oshima, Takao; Hayatsu, Kazuo; Yamamoto, Michio; and Yasui, Seimei, 4,294,940, Cl. 525-124.000.
- Hayes, Geoffrey M. G.: See—
Chapman, Arthur J.; and Hayes, Geoffrey M. G., 4,294,561, Cl. 403-219.000.
- Hayes, Richard H., to Eagle-Picher Industries, Inc. Apparatus for cutting sheet molding compound. 4,294,144, Cl. 83-71.000.
- Head, Stanley M.: See—
Fennel, John W., Jr.; Hallett, Robert J.; Head, Stanley M.; and Melas, Constantine M., 4,295,217, Cl. 370-81.000.
- Heap, Robert B., to National Research Development Corporation. Method for monitoring pregnancy in milk-producing domestic animals. 4,294,922, Cl. 435-7.000.
- Hedley, Victor H.; and Olson, Walter A. Sod cutting and stacking machine. 4,294,316, Cl. 172-20.000.
- Heiberger, Philip: See—
Burgess, William H., III; and Heiberger, Philip, 4,294,736, Cl. 260-22.00M.
- Heimann, Joseph B. Method and apparatus for making a secondary key for a lock mechanism. 4,294,096, Cl. 72-60.000.
- Heine, Hans-Georg: See—
Scholz, Karl-Heinz; Hartmann, Willy; and Heine, Hans-Georg, 4,294,973, Cl. 548-320.000.
- Heinrich, Bernd. Multi-hull steering system. 4,294,184, Cl. 114-61.000.
- Heitmann, Jürgen: See—
Hausdorfer, Michael; and Heitmann, Jürgen, 4,295,156, Cl. 358-12.000.
- Heldt, Wolfgang: See—
Stoss, Peter; Satzinger, Gerhard; Herrmann, Manfred; and Heldt, Wolfgang, 4,294,838, Cl. 424-263.000.
- Helfert, Herbert; Reinert, Friedrich; Richter, Paul; Vescia, Michele; and Wegerle, Dieter, to BASF Aktiengesellschaft. Removal of oligomer deposits from textile materials. 4,294,576, Cl. 8-137.500.
- Hellestam, Carl-Johan S., to Boliden Aktiebolag. Method and an agent for chemical purification of water by means of chemical precipitation and magnetic sludge separation. 4,294,705, Cl. 210-695.000.
- Helling, Gunter; Saleck, Wilhelm; and Berghaller, Peter, to Agfa-Gevaert Aktiengesellschaft. Photographic silver halide emulsion. 4,294,920, Cl. 430-569.000.
- Henderson, Ellsworth S. Combined dart rack and safety depository. 4,294,365, Cl. 211-60.00R.
- Henderson, James N., to Goodyear Tire & Rubber Company. The Rubbery copolymers of 2,3-dimethyl 1,3-butadiene. 4,294,942, Cl. 525-314.000.
- Hendricks, Udo-Winifred; Hildebrand, Dietrich; and Kuth, Robert, to Bayer Aktiengesellschaft. Process for the one-bath, single-stage dyeing or printing of cellulose fibres with fibre-reactive disperse dyestuffs. 4,294,579, Cl. 8-549.000.
- Hendrickson, Thomas E., to Honeywell Inc. Dual signal control system. 4,295,057, Cl. 307-231.000.
- Heneveld, Lloyd A., Trustee: See—
Dauser, William C., Jr., 4,295,004, Cl. 174-87.000.
- Henk, Hermann; Wunderlich, Klaus; and Wild, Peter, to Bayer Aktiengesellschaft. Reactive dyestuffs, their preparation and their use for dyeing materials containing OH or N. 4,294,580, Cl. 8-549.000.
- Henkel Corporation: See—
Spitzner, Ernest, 4,294,961, Cl. 544-49.000.
- Virnig, Michael J., 4,294,965, Cl. 544-297.000.
- Henkel Kommanditgesellschaft auf Aktien: See—
Conrad, Jens; Upadek, Horst; and Bruns, Klaus, 4,294,727, Cl. 252-522.00R.
- Henninger, Heinz: See—
Tomoff, Toma; Chlosta, Wolfgang; Henninger, Heinz; Tamm, Rolf; and Grossmann, Klaus, 4,294,126, Cl. 73-864.210.
- Henoch, Bengt; and Berglund, Eilert, to Stiftelsen Institute for Mikrovagsteknik vid Tekniska Hogskolan i Stockholm. Method and apparatus at one-way or two-way information link to effect interference suppression. 4,295,221, Cl. 375-23.000.
- Henson, Thomas R.; and Timberlake, John F., to Dow Chemical Company. The Preparation of organic isocyanates. 4,294,774, Cl. 260-453.00P.
- Herd, David P., to Smith International, Inc. Fail-safe, non-pressure locking gate valve. 4,294,284, Cl. 137-613.000.
- Hermann Ritzenhoff, Firma: See—
Bodenbender, Manfred; Reinhardt, Willy; and Ritzenhoff, Hermann, 4,294,368, Cl. 215-256.000.
- Herr, John A.; and Rogan, Bruce R., to Singer Company. The Latching relay using Hall effect device. 4,295,118, Cl. 338-32.00H.
- Herrmann, Manfred: See—
Stoss, Peter; Satzinger, Gerhard; Herrmann, Manfred; and Heldt, Wolfgang, 4,294,838, Cl. 424-263.000.
- Herrmann, Willy. Apparatus for purifying a liquid by ion-exchange. 4,294,699, Cl. 210-287.000.
- Herron, Clifford W.; and Wunderlich, Robert J. Wall mountable housing for programmable thermostat. 4,295,180, Cl. 361-383.000.
- Herterick, George M.: See—
Sprott, Kenneth J.; and Herterick, George M., 4,294,113, Cl. 73-199.000.
- Hession, Brent M.: See—
Hession, Rodney J.; and Hession, Brent M., 4,294,383, Cl. 222-611.000.
- Hession Industries, Inc.: See—
Hession, Rodney J.; and Hession, Brent M., 4,294,383, Cl. 222-611.000.
- Hession, Rodney J.; and Hession, Brent M., to Hession Industries, Inc. Mortar applying device. 4,294,383, Cl. 222-611.000.
- Hestermann, Klaus: See—
Maurer, Alexander; Adrian, Renate; Hestermann, Klaus; and Heymer, Gero, 4,294,621, Cl. 106-306.000.
- Hettiger, James, to RCA Corporation. Keyed noise filter in a television receiver. 4,295,161, Cl. 358-34.000.
- Hettiger, James, to RCA Corporation. Keying signal generator responsive to plural input signals. 4,295,163, Cl. 358-165.000.
- Hettiger, James: See—
Shanley, Robert L., II; and Hettiger, James, 4,295,166, Cl. 358-243.000.
- Hewlett-Packard Company: See—
Berthier, Daniel, 4,295,040, Cl. 235-458.000.
- Heydweiller, James, to General Signal Corporation. Electrical switch mechanism. 4,295,020, Cl. 200-61.45R.
- Heyes, Peter J., to Metal Box Limited. Treatment of tinplate surfaces. 4,294,627, Cl. 148-6.14R.
- Heymer, Gero: See—
Maurer, Alexander; Adrian, Renate; Hestermann, Klaus; and Heymer, Gero, 4,294,621, Cl. 106-306.000.
- Wasel-Nielsen, Horst-Dieter; Adrian, Renate; Panter, Herbert; Heymer, Gero; Maurer, Alexander; and von Schenck, Raban, 4,294,808, Cl. 423-305.000.

- Heywang, Hermann: See—
Behn, Reinhard; Heywang, Hermann; and Pachonik, Horst, 4,294,194, Cl. 118-719.000.
- Hidaka, Akio: See—
Watanabe, Teruoki; Kanno, Tadao; Hidaka, Akio; and Kobayashi, Shunji, 4,294,630, Cl. 148-16.600.
- Hidaka, Hidemasa; Kohno, Toshiaki; and Eida, Toshiaki, to Meiji Seika Kaisha, Ltd. Method of producing high purity maltose. 4,294,623, Cl. 127-55.000.
- Hieber, Konrad; and Stolz, Manfred, to Siemens Aktiengesellschaft. Method for depositing a layer on the inside of cavities of a work piece. 4,294,871, Cl. 427-237.000.
- Hilakos, William: See—
Quinn, Clayton B.; and Hilakos, William, 4,294,953, Cl. 528-128.000.
- Hildebrand, Dietrich: See—
Hendricks, Udo-Winfred; Hildebrand, Dietrich; and Kuth, Robert, 4,294,579, Cl. 8-549.000.
- Hill, Richard N., to W. R. Grace & Co. Aeration of phosphoric acid. 4,294,809, Cl. 423-321.00R.
- Hind, John R.: See—
Seed, Geoffrey; Chesworth, Graham; Hind, John R.; and Hodgson, Donald, 4,294,661, Cl. 376-363.000.
- Hinderer, Helmut E.: See—
Bach, Hartwig C.; and Hinderer, Helmut E., 4,294,884, Cl. 428-364.000.
- Hing Yuen, Tse Lin Sin Tse: See—
Jones, William A.; Hing Yuen, Tse Lin Sin Tse; Rytomaa, Tapio; Harper, Norman J.; and Frost, Henry F., 4,294,824, Cl. 424-101.000.
- Hino, Minoru; Oshima, Takao; Hayatsu, Kazuo; Yamamoto, Michio; and Yasui, Seimei, to Sumitomo Chemical Company, Limited. Resin composition for electrocoating. 4,294,940, Cl. 525-124.000.
- Hirai, Toru: See—
Sakagami, Teruo; Kato, Tadaaki; Hirai, Toru; and Murayama, Naohiro, 4,294,677, Cl. 204-181.00F.
- Hirano, Shigeo: See—
Tsujino, Nobuyuki; and Hirano, Shigeo, 4,294,919, Cl. 430-559.000.
- Hirokawa, Toshio: See—
Kawano, Tsuyoshi; Usuda, Matsuo; and Hirokawa, Toshio, 4,294,095, Cl. 72-51.000.
- Hirose, Yoshiharu: See—
Koga, Kenichiro; Hirose, Yoshiharu; Kanno, Iwao; Uemura, Kazuo; and Miura, Shuichi, 4,295,047, Cl. 250-363.00S.
- Hirose, Yoshiteru: See—
Takahara, Yoshiyuki; Hirose, Yoshiteru; Takeuchi, Yoko; Murai, Asao; Kainosho, Masatsune; and Muroa, Sawao, 4,294,754, Cl. 260-112.50R.
- Hirota, Akira; Kosaka, Yoshiteru; and Ashida, Kazutaka, to Victor Company of Japan, Ltd. System for controlling rotation of rotating structure. 4,295,171, Cl. 360-73.000.
- Hitachi Chemical Company, Ltd.: See—
Mukoyama, Yoshiyuki; and Sakata, Touichi, 4,294,952, Cl. 528-67.000.
- Hitachi Denshi Kabushiki Kaisha: See—
Takemoto, Iwao; Koike, Norio; Ohba, Shinya; Ando, Haruhisa; Nakai, Masaaki; Hanamura, Syoji; Izawa, Ryuichi; Kubo, Masaharu; Aoki, Masakazu; and Tanaka, Shuhei, 4,295,055, Cl. 307-221.00C.
- Toriumi, Takeshi; and Tominaga, Tamotsu, 4,294,390, Cl. 226-181.000.
- Hitachi, Ltd.: See—
Hata, Hidetoh; Haji, Katsumi; Sako, Kazushige; Shibata, Yoji; and Achiha, Masahiko, 4,295,154, Cl. 358-4.000.
- Hatada, Minoru; Hiyama, Kunio; Ihara, Hirokazu; and Kuma, Hisao, 4,295,122, Cl. 340-147.0LP.
- Iida, Yoshihiko; and Kajiwara, Toshiyuki, 4,294,394, Cl. 228-158.000.
- Inouye, Hiroshi; and Sato, Eiichi, 4,294,453, Cl. 277-22.000.
- Nagase, Hiroshi; Okuyama, Toshiaki; Kubota, Yuzuru; and Suzuki, Katsunori, 4,295,084, Cl. 318-719.000.
- Ohtake, Yukio, 4,294,146, Cl. 83-316.000.
- Sawa, Toshio; Kubota, Masayoshi; Takahashi, Sankichi; and Kaneko, Toyohiko, 4,294,697, Cl. 210-221.100.
- Takahashi, Minoru; Tanigami, Takahiko; Uchiyama, Kaoru; Minorikawa, Hitoshi; Nishihara, Motohisa; Kawakami, Kanji; Suzuki, Seiko; Hachino, Hiroaki; and Misawa, Yutaka, 4,295,115, Cl. 338-4.000.
- Takemoto, Iwao; Koike, Norio; Ohba, Shinya; Ando, Haruhisa; Nakai, Masaaki; Hanamura, Syoji; Izawa, Ryuichi; Kubo, Masaharu; Aoki, Masakazu; and Tanaka, Shuhei, 4,295,055, Cl. 307-221.00C.
- Todokoro, Hideo; and Sakitani, Yoshio, 4,295,072, Cl. 313-7.000.
- Uchida, Seiichi; Satomi, Yoshihito; Kiuchi, Norihiro; Yamagata, Takeo; Yoshioka, Susumu; Miyamoto, Tomohiko; and Tomuro, Jinichi, 4,294,803, Cl. 422-111.000.
- Yoshioka, Masahiro; Koike, Toshifumi; and Izumi, Hideki, 4,294,494, Cl. 308-76.000.
- Hitachi Shipbuilding & Engineering Co., Ltd.: See—
Kimoto, Yasuo; Tamiya, Katsunori; Honda, Shoichi; Maehata, Hidehiko; and Kamada, Hiroshi, 4,294,673, Cl. 204-129.460.
- Hiyama, Kunio: See—
Hatada, Minoru; Hiyama, Kunio; Ihara, Hirokazu; and Kuma, Hisao, 4,295,122, Cl. 340-147.0LP.
- Hizume, Akio: See—
Shima, Ichiji; Yamamoto, Tatsuo; Yoshibayashi, Shigeru; Teshima, Hiroshi; Hizume, Akio; Iki, Tetsuo; Yamamoto, Takashi;
- Kanamori, Kyoze; and Tanaka, Shigeho, 4,294,120, Cl. 73-650.000.
- Hochman, Benjamin L., to Air Shields, Inc. System for detecting probe dislodgement. 4,294,263, Cl. 128-736.000.
- Hodgson, Donald: See—
Seed, Geoffrey; Chesworth, Graham; Hind, John R.; and Hodgson, Donald, 4,294,661, Cl. 376-363.000.
- Hodgson, Thomas D.; and Jordan, Tony W. J., to United Kingdom Atomic Energy Authority. Method of leaching the contents of a can. 4,294,805, Cl. 423-4.000.
- Hoechst Aktiengesellschaft: See—
Kleber, Rolf; and Billenstein, Siegfried, 4,294,990, Cl. 568-601.000.
- Maurer, Alexander; Adrian, Renate; Hestermann, Klaus; and Heymer, Gero, 4,294,621, Cl. 106-306.000.
- Moraw, Roland; and Schädlich, Renate, 4,294,913, Cl. 430-396.000.
- Papenfuh, Theodor; and Teige, Wolfgang, 4,294,749, Cl. 260-40.00P.
- Wasel-Nielsen, Horst-Dieter; Adrian, Renate; Panter, Herbert; Heymer, Gero; Maurer, Alexander; and von Schenck, Raban, 4,294,808, Cl. 423-305.000.
- Hoechst Fibers Industries, Div. of American Hoechst Corporation: See—
Hawkins, Roland L., 4,294,883, Cl. 428-361.000.
- Hoffler, George W.: See—
Baker, Joseph T.; Hoffler, George W.; and Hursta, William, 4,294,261, Cl. 128-691.000.
- Hoffman, Carl H.: See—
Monaghan, Richard L.; Alberts, Alfred W.; Hoffman, Carl H.; and Albers-Schonberg, George, 4,294,926, Cl. 435-125.000.
- Hoffmann, Hellmut, to Bayer Aktiengesellschaft. Preparation of α -cyano-benzyl esters. 4,294,762, Cl. 260-340.300.
- Hoffmann-La Roche Inc.: See—
Fischli, Albert E.; and Szente, Andre, 4,294,758, Cl. 260-239.30D.
- Liu, Chao-Min; and Westley, John, 4,294,925, Cl. 435-84.000.
- Hofstein, Steven R., to World Medical Marketing Corporation. Foot exerciser. 4,294,236, Cl. 128-25.00B.
- Hollis, James E. L.: See—
Williams, Garnet M. E.; and Hollis, James E. L., 4,294,262, Cl. 128-726.000.
- Holmquist, Borje G. A., to Leifex Stockholms-Tvatt Aktiebolag. Apparatus for washing gases and/or recovering heat therefrom. 4,294,781, Cl. 261-89.000.
- Holson Company, The: See—
Holson, Sheldon, 4,294,029, Cl. 40-388.000.
- Holson, Sheldon, to Holson Company, The. Pivotally mounted photo album page. 4,294,029, Cl. 40-388.000.
- Holzmann, Dieter; and Schmidtpott, Friedrich, to ITT Industries, Inc. MOS-Binary-to-decimal code converter. 4,295,126, Cl. 340-347.0DD.
- Hommez, Etienne R. O. C.: See—
Decoene, Frans J. G. C.; Hommez, Etienne R. O. C.; and Naaktgeboren, Adrianus, 4,294,346, Cl. 198-740.000.
- Honda Giken Kogyo Kabushiki Kaisha: See—
Iiyama, Masahiko; Sanka, Tsugio; and Naito, Kenji, 4,294,205, Cl. 123-274.000.
- Sasaki, Takeshi, 4,295,032, Cl. 219-137.00R.
- Watanabe, Teruoki; Kanno, Tadao; Hidaka, Akio; and Kobayashi, Shunji, 4,294,630, Cl. 148-16.600.
- Honda, Shoichi: See—
Kimoto, Yasuo; Tamiya, Katsunori; Honda, Shoichi; Maehata, Hidehiko; and Kamada, Hiroshi, 4,294,673, Cl. 204-129.460.
- Honeywell Inc.: See—
Evans, Thomas E., 4,295,099, Cl. 328-151.000.
- Hendrickson, Thomas E., 4,295,057, Cl. 307-231.000.
- Vollmer, Rudolf, 4,294,402, Cl. 236-12.00R.
- Honeywell Information Systems Inc.: See—
Darden, Boyd E.; and Hartley, Henry F., 4,295,194, Cl. 364-200.000.
- Joyce, Thomas F., 4,295,203, Cl. 364-748.000.
- Joyce, Thomas J.; and Cushing, David E., 4,295,202, Cl. 364-748.000.
- Honnen, Lewis R.: See—
Lewis, Robert A.; and Honnen, Lewis R., 4,294,714, Cl. 252-34.000.
- Hoogovens Ijmuiden B.V.: See—
Steen, Adam; and Verhoog, Hendrik M., 4,294,431, Cl. 266-44.000.
- Hoover, William J.: See—
Kulp, Karel; and Hoover, William J., 4,294,864, Cl. 426-549.000.
- Hopkins, Willard C.: See—
Bair, Eugene C.; and Hopkins, Willard C., 4,294,006, Cl. 29-701.000.
- Horne, William E., to Boeing Company, The. Electro-optically assisted bonding. 4,294,602, Cl. 65-40.000.
- Horton, Herbert D., to World Wide Oil Tools, Inc. Pipe gripping vise. 4,294,444, Cl. 269-156.000.
- Hosaka, Akio: See—
Abo, Toshimi; and Hosaka, Akio, 4,294,216, Cl. 123-489.000.
- Hosoda, Naoyoshi; and Hosoda, Takeshi. Plasma-arc cutting method. 4,295,030, Cl. 219-121.0PH.
- Hosoda, Takeshi: See—
Hosoda, Naoyoshi; and Hosoda, Takeshi, 4,295,030, Cl. 219-121.0PH.
- Hosokawa, Yorio: See—
Otsuka, Kenichi; and Hosokawa, Yorio, 4,295,079, Cl. 315-130.000.
- Hounsfield, Godfrey N., to EMI Limited. Radiography. 4,295,195, Cl. 364-414.000.
- Howard, William A., to Delta Systems, Inc. Safety interlock for machine and engine with magneto ignition. 4,294,327, Cl. 180-273.000.

- Howe, Mark J., to PPG Industries, Inc. Silicate-containing latex coating compositions. 4,294,874, Cl. 427-393.000.
- Howell, Terrence D. Liquid dispenser holder. 4,294,384, Cl. 224-42.420.
- Hrubec, Margaret C. Unitary furniture element. 4,293,965, Cl. 5-465.000.
- Hsia, Alexander M.: See—
Tavlarides, Lawrence L.; Freeman, Robert W.; and Hsia, Alexander M., 4,294,800, Cl. 422-68.000.
- Hsieh, Peter K.; and Vaccarella, Richard M., to RCA Corporation. Level shift circuit. 4,295,065, Cl. 307-475.000.
- Huang, Hung-Chang W.: See—
Kircher, Charles J.; Huang, Hung-Chang W.; and Murakami, Masanori, 4,295,147, Cl. 357-5.000.
- Hubele, Adolf, to Ciba-Geigy Corporation. Fungicidal acylanilides. 4,294,850, Cl. 424-309.000.
- Hudson Lock, Inc.: See—
Cantlin, John H., 4,295,016, Cl. 200-44.000.
- Hudson Pulp & Paper Corp.: See—
Pollock, Stephen F., 4,293,990, Cl. 29-148.40D.
- Hufnagl, Walter; and Koutaack, Peter. Methods and device for cladding elongated objects such as wires and the like with powdered material. 4,294,870, Cl. 427-189.000.
- Hughes, Frederick R.: See—
Nyul, Paul; and Hughes, Frederick R., 4,295,151, Cl. 357-68.000.
- Hughes, Graham K., to Southland Corporation, The. Process for the production of alkyl aryl ethers. 4,294,992, Cl. 568-632.000.
- Hughes, William J., Jr. Modular building system. 4,294,051, Cl. 52-98.000.
- Hulsebus, Richard P.: See—
DuBois, Chester G.; and Hulsebus, Richard P., 4,294,780, Cl. 261-39.00B.
- Humbert, Daniel; Clemence, Francois; and Dagnaux, Michele. 1,3-Benzodioxin derivatives. 4,294,845, Cl. 424-278.00Q.
- Humphreys, Peter; Davidson, Daniel F.; and Thatcher, Gordon, to United Kingdom Atomic Energy Authority. Nuclear reactors. 4,294,658, Cl. 376-404.000.
- Humphries, William T.: See—
Wildnauer, Richard H.; and Humphries, William T., 4,294,852, Cl. 424-317.000.
- Hurley, Donald C., Jr. Process for making glazed ceramic ware. 4,294,635, Cl. 156-89.000.
- Hurley, John J., to Ford Motor Company. Bowden cable retainer and adjuster. 4,294,133, Cl. 74-501.00P.
- Humer, Erwin E. Vehicle speed limiting device. 4,294,204, Cl. 123-198.0DB.
- Hurst, Kurt: See—
Sautter, Helmut; Hurst, Kurt; and Schink, Rainer, 4,295,127, Cl. 340-373.000.
- Hursta, William: See—
Baker, Joseph T.; Hoffler, George W.; and Hursta, William, 4,294,261, Cl. 128-691.000.
- Husbands, Charles R., to United States of America, Air Force. Optical multiplexer/demultiplexer. 4,294,508, Cl. 350-96.150.
- Hussey Manufacturing Co., Inc.: See—
Sutter, David L., 4,294,048, Cl. 52-9.000.
- Hyatt, John A., to Eastman Kodak Company. Preparation of 7,12-dioxaspiro[5.6]dodecane-3-one. 4,294,761, Cl. 260-338.000.
- Hyatt, Michael V.; and Quist, William E., to Boeing Company, The. Aluminum alloy products and methods. 4,294,625, Cl. 148-2.000.
- Hydral Company: See—
Miyagishima, Tosh; Puntar, Joseph; and Wieveg, Raymond, 4,294,314, Cl. 166-318.000.
- Hydroacoustics Inc.: See—
Nelson, David E.; and Bouyoucos, John V., 4,294,513, Cl. 350-96.290.
- Hyman, Dennis C., to Presley, Molly. Weight redistribution apparatus. 4,294,466, Cl. 280-772.000.
- Ibsen, Robert L.; and Glace, William R., to Den-Mat, Inc. Kit for repair of porcelain dental prostheses. 4,294,349, Cl. 206-63.500.
- Idelson, Elbert M., to Polaroid Corporation. Silver halide developing agents. 4,294,915, Cl. 430-441.000.
- Ideta, Yasufumi; Takeda, George; and Watanabe, Shoji, to Nissan Motor Co., Ltd. Oil pressure booster. 4,294,160, Cl. 91-378.000.
- Ieki, Hideharu, to Murata Manufacturing Co., Ltd. Filter circuit employing surface acoustic wave device. 4,295,108, Cl. 333-193.000.
- Iemmi, Giuliano; and Macerata, Diego, to Centro Ricerche Fiat S.p.A. Graphite-resin composite electrode structure, and a process for its manufacture. 4,294,893, Cl. 429-42.000.
- Ifuku, Yasushi; Uchiyama, Hirofumi; and Hayashi, Masayuki, to Mitsubishi Jukogyo Kabushiki Kaisha; and Prefectural Economic Federation of Agricultural Co-operatives. Method of separating and taking out pulp from citrus fruits. 4,294,861, Cl. 426-475.000.
- Iguchi, Sadahiko: See—
Hayashi, Masaki; Iguchi, Sadahiko; Okada, Takanori; and Kawasaki, Akiyoshi, 4,294,849, Cl. 424-305.000.
- Ihara, Hirokazu: See—
Hatada, Minoru; Hiyama, Kunio; Ihara, Hirokazu; and Kuma, Hisao, 4,295,122, Cl. 340-147.0LP.
- Iida, Yoshihiko; and Kajiwara, Toshiyuki, to Hitachi, Ltd. Method of and apparatus for continuously rolling steel slabs. 4,294,394, Cl. 228-158.000.
- Iiyama, Masahiko; Sanka, Tsugio; and Naito, Kenji, to Honda Giken Kogyo Kabushiki Kaisha. Internal combustion engine. 4,294,205, Cl. 123-274.000.
- Ikari, Kyoichiro: See—
Kodera, Yuji; Ikari, Kyoichiro; and Miyake, Shunji, 4,294,935, Cl. 525-60.000.
- Ikeda, Takashi: See—
Nouda, Hiroshi; Tanihara, Yoshiaki; Ikeda, Takashi; and Ogiuchi, Ituo, 4,294,791, Cl. 264-210.200.
- Ikeda, Tatsuhiko; and Terada, Soichiro, to Terumo Corporation. Method for separating blood and a barrier device therefor. 4,294,707, Cl. 210-782.000.
- Ikemura, Yuichi: See—
Machida, Toyotaka; and Ikemura, Yuichi, 4,295,157, Cl. 358-17.000.
- Iki, Tetsuo: See—
Shima, Ichiji; Yamamoto, Tatsuo; Yoshibayashi, Shigeru; Teshima, Hiroshi; Hizume, Akio; Iki, Tetsuo; Yamamoto, Takashi; Kanamori, Kyoze; and Tanaka, Shigeho, 4,294,120, Cl. 73-650.000.
- Ikura, Hiroshi: See—
Suzuki, Yoshiki; Ikura, Hiroshi; Yamashita, Gentaro; and Nagai, Tsuneji, 4,294,829, Cl. 424-241.000.
- Illinois Tool Works Inc.: See—
Borja, Jesus; and Halvorsen, Jack R., 4,295,003, Cl. 174-53.000.
- Keeler, Robert J.; and Filipiak, Stanley E., 4,295,012, Cl. 200-5.00B.
- Imperial Chemical Industries, Inc.: See—
Snowden, Paul, 4,294,783, Cl. 264-8.000.
- Imperial Chemical Industries Limited: See—
Anderson, Norman; Peak, Richard; and Moyse, James A., 4,294,709, Cl. 252-8.800.
- Bentley, John; and Thompson, Morice, 4,294,735, Cl. 260-22.0CB.
- Nicks, Peter F., 4,294,887, Cl. 428-423.100.
- Inami, Yasuhiko: See—
Nakachi, Hiroshi; Koyanagi, Katubumi; Inami, Yasuhiko; and Ueda, Hisashi, 4,295,138, Cl. 340-785.000.
- Inco Limited: See—
Baldwin, Stanley L.; Hampton, Vernon; and Embleton, Tony F. W., 4,294,330, Cl. 181-230.000.
- Ingersoll-Rand Co.: See—
Treible, Edwin S.; Dopkin, Joseph A.; and Alford, Raymond N., 4,294,214, Cl. 123-458.000.
- Ingram, Arlen E. Tennis ball holder. 4,294,386, Cl. 224-252.000.
- Innocenti, Franco; Orzalesi, Giovanni; and Volpato, Ivo, to Societa Italo-Britannica. Substituted 4-hydroxy-isophthalic acid picolylamides having a pharmaceutical activity in thromboembolic disorders. 4,294,833, Cl. 424-263.000.
- Inoue, Eiichi; Shimizu, Isamu; and Shizukuishi, Makoto, to Fuji Photo Film Co., Ltd. Electrochromic display device. 4,294,520, Cl. 350-357.000.
- Inoue-Japax Research Incorporated: See—
Inoue, Kiyoshi, 4,294,121, Cl. 73-662.000.
- Inoue, Kiyoshi, to Inoue-Japax Research Incorporated. Position measuring system. 4,294,121, Cl. 73-662.000.
- Inoue, Toshinori: See—
Fujiwara, Ichiro; Motoki, Yoshiaki; Inoue, Toshinori; and Fukuoka, Kazuma, 4,295,015, Cl. 200-38.00R.
- Inouye, Hiroshi; and Sato, Eiichi, to Hitachi, Ltd. Mechanical seal. 4,294,453, Cl. 277-22.000.
- Inspiration Consolidated Copper Company: See—
Britton, Kenneth L., 4,295,001, Cl. 13-17.000.
- Institut Francais du Petrole: See—
Cholet, Jacques; Magneville, Pierre; and Cassand, Jean, 4,294,328, Cl. 181-120.000.
- Cohen, Georges; and Rojey, Alexandre, 4,294,080, Cl. 62-101.000.
- Desbrandes, Robert; and Grolet, Pierre, 4,294,318, Cl. 175-321.000.
- Instituto per la Ricerca Scientifica e Applicata di Technologie Alimentari S.p.A.: See—
Eschinasi, Emile H.; and Castelli, Enrico, 4,294,767, Cl. 260-347.800.
- Integrated Energy Systems: See—
Gajjar, Jagdishchandra T., 4,294,404, Cl. 236-49.000.
- International Business Machines Corporation: See—
Bakos, Peter; Darrow, Russell E.; Funari, Joseph; and Poliak, Richard M., 4,294,729, Cl. 252-545.000.
- Balyoz, John; Chang, Chi S.; Fox, Barry C.; Palmieri, John A.; Ghaighaichi, Majid; Jen, Teh-Sen; and Mooney, Donald B., 4,295,149, Cl. 357-45.000.
- Beranger, Herve; Marzin, Claude; Omet, Dominique; and Peter, Jean-Luc, 4,295,210, Cl. 365-227.000.
- Blum, Arnold; Geng, Hellmuth R.; Schulze-Schoelling, Hermann; and Spaeth, Bernd, 4,295,220, Cl. 371-61.000.
- Chappell, Terry I., 4,294,510, Cl. 350-96.170.
- Chappell, Terry I.; and Woodall, Jerry M., 4,295,002, Cl. 136-244.000.
- Enser, Mats A.; Hallberg, Lars O.; and Stalberg, Nils G., 4,295,121, Cl. 340-146.3MA.
- Fennel, John W., Jr.; Hallett, Robert J.; Head, Stanley M.; and Melas, Constantine M., 4,295,217, Cl. 370-81.000.
- Hartstein, Allan M., 4,294,898, Cl. 429-104.000.
- Jambotkar, Chakrapani G.; and Wang, Paul P., 4,294,002, Cl. 29-571.000.
- Johnson, Mark, 4,294,507, Cl. 350-96.130.
- Kircher, Charles J.; Huang, Hung-Chang W.; and Murakami, Masanori, 4,295,147, Cl. 357-5.000.
- Masanori, Glen G., Jr., 4,295,125, Cl. 340-347.0DD.
- Langdon, Milton R., 4,295,145, Cl. 346-108.000.
- Latta, John, 4,294,552, Cl. 400-219.100.

- Miersch, Ekkehard F.; and Romankiw, Lubomir T., 4,295,183, Cl. 361-403.000.
 Pomerene, James H., 4,295,193, Cl. 364-200.000.
 Romankiw, Lubomir T.; and Thompson, David A., 4,295,173, Cl. 360-125.000.
 Schuster, Stanley E., 4,295,064, Cl. 307-468.000.
 Stuckert, Paul E., 4,295,039, Cl. 235-380.000.
 International Diagnostic Technology, Inc.: See—
 Burgett, Michael W.; and Harte, Richard A., 4,294,817, Cl. 424-8.000.
 International Flavors & Fragrances Inc.: See—
 Mookherjee, Braja D.; Wilson, Richard A.; Schmitt, Frederick L.; and Vock, Manfred H., 4,294,863, Cl. 426-538.000.
 Sprecker, Mark A.; Hall, John B.; and Schmitt, Frederick L., 4,294,266, Cl. 131-277.000.
 Sprecker, Mark A.; Schmitt, Frederick L.; Vock, Manfred H.; Vinals, Joaquin F.; and Kiwala, Jacob, 4,294,708, Cl. 252-8.600.
 International Paper Company: See—
 Turner, Rex H., 4,294,654, Cl. 162-50.000.
 International Standard Electric Corporation: See—
 Galaske, Folker; and Hack, Oswald, 4,294,555, Cl. 400-488.000.
 International Telephone and Telegraph Corporation: See—
 Jarger, Harold F.; and Sassler, Marvin L., 4,295,155, Cl. 358-12.000.
 Intrater, Janet: See—
 Intrater, Josef; Bertholdo, Gene; and Intrater, Janet, 4,294,271, Cl. 134-113.000.
 Intrater, Josef; Bertholdo, Gene; and Intrater, Janet, to Dexon, Inc. Apparatus for removing deposited matter from a diffusion tube. 4,294,271, Cl. 134-113.000.
 Inubushi, Hisao: See—
 Sawada, Hajimu; and Inubushi, Hisao, 4,294,437, Cl. 266-272.000.
 Irako, Koichi: See—
 Ohyaichi, Tomio; and Irako, Koichi, 4,294,732, Cl. 260-27.0BB.
 IRD Mechanalysis, Inc.: See—
 Stoutenburg, Donn V., 4,295,136, Cl. 340-753.000.
 Isberg, Gary J. Fluid proportioning device. 4,294,273, Cl. 137-1.000.
 Ise, Yukihiko: See—
 Fukada, Tetsuji; and Ise, Yukihiko, 4,295,172, Cl. 360-109.000.
 Iseki, Shigeo: See—
 Kinumaki, Toyosuke; Watanabe, Takehiko; Sugii, Kisaburo; and Iseki, Shigeo, 4,294,856, Cl. 426-7.000.
 Ishibashi, Toshiaki: See—
 Kihara, Kunio; Toda, Hideo; Yasukawa, Eiki; Ishibashi, Toshiaki; and Tokita, Taketoshi, 4,294,933, Cl. 521-27.000.
 Ishida, Eisuke: See—
 Takashima, Yuji; Ishida, Eisuke; Nishiguchi, Hisanori; and Yoshino, Kimiaki, 4,294,902, Cl. 430-45.000.
 Ishigaki, Kunio: See—
 Yamaguchi, Jun; Naoi, Takashi; Sera, Hideo; Ishigaki, Kunio; and Ogawa, Masasi, 4,294,921, Cl. 430-621.000.
 Ishii, Keizou: See—
 Mizuguchi, Ryuzo; Ishikura, Sinichi; Ishii, Keizou; and Yoshioka, Tamotu, 4,294,740, Cl. 260-29.6RB.
 Ishikawa, Kazuo: See—
 Sato, Yasuhisa; Tsuji, Sadahiko; and Ishikawa, Kazuo, 4,294,529, Cl. 354-53.000.
 Ishikura, Sinichi: See—
 Mizuguchi, Ryuzo; Ishikura, Sinichi; Ishii, Keizou; and Yoshioka, Tamotu, 4,294,740, Cl. 260-29.6RB.
 Ishioka, Yoza: See—
 Kumazawa, Eitaro; Saiki, Yukihiro; and Ishioka, Yoza, 4,294,018, Cl. 34-56.000.
 Issei, Katsuta; and Tetsuo, Tanaka, to Asahi Kasei Kogyo Kabushiki Kaisha. Separation of acetonitrile from crude olefinically unsaturated nitrile. 4,294,665, Cl. 203-50.000.
 Itatani, Hiroshi; Yoshimoto, Hataaki; Shiotani, Akinori; Yokota, Akiyoshi; and Yoshikuni, Motozoh, to UBE Industries, Ltd. Process for producing biphenyl compounds. 4,294,976, Cl. 560-76.000.
 Ito Optical Industrial Co., Ltd.: See—
 Kato, Hirohisa, 4,294,950, Cl. 528-14.000.
 Ito, Seigo: See—
 Moto, Masato; and Ito, Seigo, 4,295,082, Cl. 318-599.000.
 Ito, Susumu; Sugawara, Noboru; and Amano, Sayoko, to Canon Kabushiki Kaisha. Method for preventing reflection. 4,294,890, Cl. 428-641.000.
 Ito, Tetsuro: See—
 Takahashi, Tetsuo; Taguchi, Yoshinobu; Harigane, Kotaro; Ito, Tetsuro; and Kato, Akihiro, 4,294,000, Cl. 29-564.600.
 Itoh, Junichi: See—
 Onoue, Yasuharu; Sata, Toshikatsu; Nakahara, Akihiko; and Itoh, Junichi, 4,294,943, Cl. 525-358.000.
 ITT Industries, Inc.: See—
 Adam, Fritz G., 4,295,150, Cl. 357-54.000.
 Holzmann, Dieter; and Schmidtppott, Friedrich, 4,295,126, Cl. 340-347.0DD.
 Ivanov, Vladimir V.: See—
 Vanjukov, Andrei V.; Mechev, Valery V.; Bystrov, Valentin P.; Ezhov, Evgeny I.; Vasiliev, Mikhail G.; Zaitsev, Vladimir Y.; Romenets, Vladimir A.; Ivanov, Vladimir V.; Golik, Sergei Y.; Grin-Gnatovsky, Evgeny S.; Grechko, Alexander V.; Savin, Ivan V.; Kozhakhmetov, Sultanbek M.; Meierovich, Veniamin B.; Nagibin, Vladimir D.; Ramazanov, Nariman A.; Umarov, Almas B.; Ziberov, Valentin E.; Kunaev, Askar M.; Takezhanov, Saik T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazheev, Dzhonson T., 4,294,433, Cl. 266-161.000.
 Iwaki, Yoshiyuki: See—
 Morishita, Mitsuharu; and Iwaki, Yoshiyuki, 4,295,087, Cl. 322-99.000.
 Iwanaga, Kazuyoshi; Sugano, Kazuhiko; and Ohtsuka, Kunio, to Nissan Motor Company, Limited. Hydraulic torque converter control system. 4,294,140, Cl. 74-868.000.
 Iwasa, Tomoyuki: See—
 Iwata, Mitsuo; Wada, Hajime; Iwasa, Tomoyuki; and Tsuchino, Kunio, 4,295,169, Cl. 360-71.000.
 Iwashita, Tomonori; Fukahori, Hidehiko; and Mashimo, Yukio, to Canon Kabushiki Kaisha. Motorized photographic system and camera and power drive unit therefor. 4,294,530, Cl. 354-173.000.
 Iwata, Mitsuo; Wada, Hajime; Iwasa, Tomoyuki; and Tsuchino, Kunio, to Sanyo Electric Co., Ltd.; and Tottori Sanyo Electric Co., Ltd. Cassette loading and unloading device. 4,295,169, Cl. 360-71.000.
 Izawa, Ryuichi: See—
 Takemoto, Iwao; Koike, Norio; Ohba, Shinya; Ando, Haruhisa; Nakai, Masaaki; Hanamura, Syoji; Izawa, Ryuichi; Kubo, Masaharu; Aoki, Masakazu; and Tanaka, Shuhei, 4,295,055, Cl. 307-221.00C.
 Izumi, Hideki: See—
 Yoshioka, Masahiro; Koike, Toshifumi; and Izumi, Hideki, 4,294,494, Cl. 308-76.000.
 J. J. Barker Company Limited: See—
 Turnbull, James O.; Barker, John C.; and Knight, Arthur J., 4,294,021, Cl. 34-224.000.
 Jack, James; and Gray, Derek C., to BXL Plastics Limited. Extrusion processes and apparatus for quenching tubes. 4,294,796, Cl. 264-559.000.
 Jackson, Kenneth W.: See—
 Daugherty, Edgar E.; Jackson, Kenneth W.; Jones, Wesley W.; and Subh, Naif T., 4,295,005, Cl. 174-92.000.
 Jacobs, John T. Vision therapeutic apparatus. 4,294,522, Cl. 351-2.000.
 Jaeschke, James R.: See—
 Lade, Robert W.; Spellman, Gordon B.; Jaskolski, Stanley V.; Schutten, Herman P.; and Jaeschke, James R., 4,295,058, Cl. 307-252.00A.
 Jagenberg Werke AG: See—
 Bodewein, Jakob, 4,294,145, Cl. 83-302.000.
 Jakubek, John, to Timex Corporation. Electrooptical device with encapsulated self-luminous backlight assembly. 4,294,517, Cl. 350-345.000.
 Jallas, Michel: See—
 Piret, Jean; and Jallas, Michel, 4,294,137, Cl. 74-665.00G.
 Jambotkar, Chakrapani G.; and Wang, Paul P., to International Business Machines Corp. Making a short-channel FET. 4,294,002, Cl. 29-571.000.
 Jamet, Bruno: See—
 Boutin, Jean; Guenot, Bernard; and Jamet, Bruno, 4,294,676, Cl. 204-159.230.
 Janisch, Paul: See—
 Lohrborg, Karl; Biel, Siegfried; and Janisch, Paul, 4,294,815, Cl. 423-478.000.
 Janko, Mike A.: See—
 Weiszbrod, David A., 4,295,170, Cl. 360-73.000.
 Japan Atomic Energy Research Institute: See—
 Matsuda, Osamu; Watanabe, Terutaka; Tabata, Yoneho; and Machi, Suet, 4,294,675, Cl. 204-159.140.
 Mimami, Kentaro, 4,295,045, Cl. 250-255.000.
 Japan Envirotic Industry Co., Ltd.: See—
 Kirisawa, Atsushi, 4,294,626, Cl. 148-6.200.
 Japan Synthetic Rubber Co., Ltd.: See—
 Harita, Yoshiyuki; Kamoshida, Yoichi; and Harada, Kunihiro, 4,294,908, Cl. 430-286.000.
 Jarger, Harold F.; and Sassler, Marvin L., to International Telephone and Telegraph Corporation. Gray scale sync video processing system. 4,295,155, Cl. 358-12.000.
 Jarzebski, Andrzej: See—
 Falkowski, Leonard; Stefanska, Barbara; Zielinski, Jan; Troka, Elzbieta; Golik, Jerzy; Kolodziejczyk, Pawel; Jarzebski, Andrzej; Cybulska, Emilia; and Borowski, Edward, 4,294,958, Cl. 536-17.00R.
 Jaskolski, Stanley V.: See—
 Lade, Robert W.; Spellman, Gordon B.; Jaskolski, Stanley V.; Schutten, Herman P.; and Jaeschke, James R., 4,295,058, Cl. 307-252.00A.
 Jean Walterscheid GmbH: See—
 Kunze, Dieter, 4,294,340, Cl. 192-56.00R.
 Jedeck, Helmar: See—
 Jochmann, Franz; and Jedeck, Helmar, 4,295,052, Cl. 307-10.00R.
 Jen, Teh-Sen: See—
 Balyoz, John; Chang, Chi S.; Fox, Barry C.; Palmieri, John A.; Ghafghaichi, Majid; Jen, Teh-Sen; and Mooney, Donald B., 4,295,149, Cl. 357-45.000.
 Jensen, Kenneth D., to Midland-Ross Corporation. Hydraulic booster travel ratio check valve. 4,294,071, Cl. 60-547.00A.
 Jewusiak, Stephen J.; Beroff, Howard; and Schuler, Michael, to Ethicon, Inc. Cartridge for hemostatic clips. 4,294,355, Cl. 206-339.000.
 Jochmann, Franz; and Jedeck, Helmar, to Bayerische Motoren Werke Aktiengesellschaft. Circuit for motor vehicles. 4,295,052, Cl. 307-10.00R.
 Johansson, Henry. Apparatus for parallel feeding of small volumes of fluids in several essentially parallel flexible hoses. 4,294,802, Cl. 422-103.000.

- Johansson, Sven H., to Aktiebolaget Svenska Elektromagneter. Means for providing a mechanically definable selected trigger interval in a flywheel magneto. 4,295,070, Cl. 310-70.00R.
 Johns-Manville Corporation: See—
 Cunningham, Richard N.; and Loeffler, Romain E., deceased, 4,294,878, Cl. 428-212.000.
 Davenport, Robert W.; Moore, Eugene L.; and Goodman, Ronald L., 4,294,042, Cl. 51-54.000.
 McHenry, Patricia A., 4,294,879, Cl. 428-288.000.
 Johnson, Avery R.; McGurk, Richard G.; and Harrison, John M., to Small World Exchange, Inc. Telephone-conferencing apparatus and method having response tallying. 4,295,008, Cl. 179-18.0BC.
 Johnson & Johnson: See—
 Wildnauer, Richard H.; and Humphries, William T., 4,294,852, Cl. 424-317.000.
 Johnson, Leighton C., to Miles Laboratories, Inc. Method for producing monocellular layers of cell-containing biological fluid. 4,294,866, Cl. 427-2.000.
 Johnson, Mark, to International Business Machines Corporation. Controllably deformed elastic waveguide elements. 4,294,507, Cl. 350-96.130.
 Johnson, Richard F., to United States of America, Navy. Automatic particle analyzing system. 4,295,200, Cl. 364-555.000.
 Johnson, Wynsel J.: See—
 Kolnes, Kenneth O.; and Johnson, Wynsel J., 4,294,442, Cl. 269-101.000.
 Jones, John A.: See—
 Grovesteen, William R.; and Jones, John A., 4,294,599, Cl. 55-485.000.
 Jones, Philip E., to Cummins Engine Company, Inc. Internal combustion engine with integral upper cylinder section and head. 4,294,203, Cl. 123-195.00R.
 Jones, Wesley W.: See—
 Daugherty, Edgar E.; Jackson, Kenneth W.; Jones, Wesley W.; and Subh, Naif T., 4,295,005, Cl. 174-92.000.
 Jones, William A.; Hing Yuen, Tse Lin Sin Tse; Rytomaa, Tapio; Harper, Norman J.; and Frost, Henry F., to Union International Company, Ltd., The Extracts of the hemopoietic system. 4,294,824, Cl. 424-101.000.
 Jordan, Friedrich, to Klockner-Humboldt-Deutz Aktiengesellschaft. Method of making camshaft for reciprocable piston engines. 4,293,995, Cl. 29-421.00R.
 Jordan, Tony W. J.: See—
 Hodgson, Thomas D.; and Jordan, Tony W. J., 4,294,805, Cl. 423-4.000.
 Jordi, Peter E.: See—
 Buser, Hansueli; and Jordi, Peter E., 4,294,117, Cl. 73-864.850.
 Joshua, Henry: See—
 Albers-Schönberg, George; Joshua, Henry; and Lopez, Maria B., 4,294,846, Cl. 424-279.000.
 Joslyn, Larry J. Multi-port valve. 4,294,285, Cl. 137-625.110.
 Jourret, Edouard, to Crouzet. Plug member for the electrical connection of an appliance to a base. 4,294,501, Cl. 339-66.00M.
 Joyce, Thomas F., to Honeywell Information Systems Inc. Automatic rounding of floating point operands. 4,295,203, Cl. 364-748.000.
 Joyce, Thomas J.; and Cushing, David E., to Honeywell Information Systems Inc. Hexadecimal digit shifter output control by a programmable read only memory. 4,295,202, Cl. 364-748.000.
 Jubin, John C., Jr.: See—
 Grane, Henry R.; Jubin, John C., Jr.; and Worrell, G. Richard, 4,294,999, Cl. 568-910.000.
 Julius Blum Gesellschaft m.b.H.: See—
 Rock, Erich; and Mages, Bernhard, 4,294,499, Cl. 312-334.000.
 Junot, Henri D. M.: See—
 Boy-Marcotte, Jean-Louis; Junot, Henri D. M.; Grossin, Richard J. A. M.; and Chevalier, Philippe J. M. R., 4,294,232, Cl. 126-443.000.
 Kabushiki Kaisha Fuji Seisakusho: See—
 Saito, Tsutomu; and Shida, Masaaki, 4,294,657, Cl. 162-303.000.
 Kabushiki Kaisha Medos Kenkyusho: See—
 Takahashi, Nagashige, 4,294,233, Cl. 128-4.000.
 Kabushiki Kaisha Seikoshu: See—
 Kobayashi, Masatoshi; Shimakawa, George; Hara, Yukio; Fujii, Hiroyuki; and Kabushiki Kaisha Seikoshu, 4,293,986, Cl. 29-25.350.
 Kabushiki Kaisha Toyoda Jidoshokki Seisakusho: See—
 Shinoda, Akibumi; and Nakane, Masao, 4,294,334, Cl. 188-18.00A.
 Takahisa, Shuji; Suzuki, Osamu; and Shibano, Michio, 4,294,067, Cl. 57-274.000.
 Kaeser, James A., to Colgate-Palmolive Company. Non-gelling inorganic salt crutcher slurries. 4,294,718, Cl. 252-135.000.
 Kahl, Melvin R., to Envirotech Corporation. Mounting for high-voltage electrode support frame in an electrostatic precipitator. 4,294,591, Cl. 55-120.000.
 Kahn, Leonard. Method and means for introducing additional asymmetry into audio waves. 4,295,106, Cl. 332-37.00R.
 Kaido, Chikara: See—
 Aoki, Shinji; Kawamura, Keita; Kimura, Hitoshi; Katayama, Tsutomu; Kaido, Chikara; and Yoshida, Hiroshi, 4,294,674, Cl. 204-157.10H.
 Kainosho, Masatsune: See—
 Takahara, Yoshiyuki; Hirose, Yoshiteru; Takeuchi, Yoko; Murai, Asao; Kainosho, Masatsune; and Murao, Sawao, 4,294,754, Cl. 260-112.50R.
 Kajiura, Toshiyuki: See—
 Iida, Yoshihiko; and Kajiura, Toshiyuki, 4,294,394, Cl. 228-158.000.
 Kakiara, Naomichi; Harada, Yoshiaki; and Uedono, Norio, to Osaka Gas Company, Limited. Process for treating waste water. 4,294,706, Cl. 210-762.000.
 Kalasz, Huba: See—
 Knoll, Jozsef; Kalasz, Huba; Knoll, Berta; and Nagy, Janos, 4,294,825, Cl. 424-101.000.
 Kalbskopf, Reinhard; and Baumberger, Otto, to Societa Italiana Vetro-Siv-S.p.A. Process for continuously depositing a layer of a solid material on the surface of a substrate heated to a high temperature. 4,294,868, Cl. 427-109.000.
 Kaldor, Antal: See—
 Tamas, Istvan; Tamas, Lajos; Kiss, Gyula; Kiss, Jozsef; and Kaldor, Antal, 4,294,611, Cl. 75-49.000.
 Kaltenbach & Voigt GmbH & Co.: See—
 Eibofner, Eugen, 4,294,797, Cl. 422-36.000.
 Kalwaitis, George V., to Air Products and Chemicals, Inc. Apparatus for extraction of materials from operating pressurized vessels. 4,294,124, Cl. 73-863.850.
 Kamada, Hiroshi: See—
 Kimoto, Yasuo; Tamiya, Katsunori; Honda, Shoichi; Machata, Hidehiko; and Kamada, Hiroshi, 4,294,673, Cl. 204-129.460.
 Kamoshida, Yoichi: See—
 Harita, Yoshiyuki; Kamoshida, Yoichi; and Harada, Kunihiro, 4,294,908, Cl. 430-286.000.
 Kamp, Eugene L., to A. B. Chance Company. Spring biased energy absorber for vacuum switch contact shafts. 4,295,024, Cl. 200-288.000.
 Kanai, Isamu; Okubo, Shigeki; Tsuchiya, Kazuo; and Takasaki, Toshio, to Bridgestone Tire Company Limited. Flexible pipe connector. 4,294,475, Cl. 285-165.000.
 Kanamori, Kyoza: See—
 Shima, Ichiji; Yamamoto, Tatsuo; Yoshibayashi, Shigeru; Teshima, Hiroshi; Hizume, Akio; Iki, Tetsuo; Yamamoto, Takashi; Kanamori, Kyoza; and Tanaka, Shigeho, 4,294,120, Cl. 73-650.000.
 Kanamuller, Franz X.: See—
 Eibner, Jules A.; and Kanamuller, Franz X., 4,295,043, Cl. 250-227.000.
 Kandel, Arnold. Truss-framed building structures. 4,294,050, Cl. 52-93.000.
 Kaneko, Toyohiko: See—
 Sawa, Toshio; Kubota, Masayoshi; Takahashi, Sankichi; and Kaneko, Toyohiko, 4,294,697, Cl. 210-221.100.
 Kanno, Iwao: See—
 Koga, Kenichiro; Hirose, Yoshiharu; Kanno, Iwao; Uemura, Kazuo; and Miura, Shuichi, 4,295,047, Cl. 250-363.00S.
 Kanno, Tadao: See—
 Watanabe, Teruoki; Kanno, Tadao; Hidaka, Akio; and Kobayashi, Shunji, 4,294,630, Cl. 148-16.600.
 Kanter, Hartmut, to BASF Aktiengesellschaft. Pigments containing pyrazolo quinoxaline radicals. 4,294,755, Cl. 260-154.000.
 Kanto Yakin Kogyo Kabushiki Kaisha: See—
 Takahashi, Susumu, 4,294,436, Cl. 266-257.000.
 Kanzaki, Toshihide: See—
 Hara, Haruichi; Kanzaki, Toshihide; Motomuro, Hisanao; and Adachi, Akiyoshi, 4,294,723, Cl. 252-440.000.
 Kari, Csaba: See—
 Alföldi, Lajos; Balint nee Fodor, Katalin; Kari, Csaba; Torok, Istvan; Szvoboda, Gyorgy; Lang, Tibor; Gado, Istvan; and Ambrus, Gabor, 4,294,927, Cl. 435-172.000.
 Karlsson, Kent A. B.: See—
 Bohlin, Karl G.; Fredriksson, Borje I.; Karlsson, Kent A. B.; and Nelvig, Lars T., 4,294,412, Cl. 241-30.000.
 Karrer, Friedrich, to Ciba-Geigy Corporation. Novel polymeric compounds. 4,294,949, Cl. 526-262.000.
 Kasashima, Masao; and Kubo, Yoshizo, to Alps Electric Co., Ltd. Rotary variable resistor. 4,295,119, Cl. 338-162.000.
 Kashima, Isao; Mishina, Masami; Takase, Yosio; and Maruchi, Katsumi, to Matsushita Electric Works, Ltd. Limit switch. 4,295,017, Cl. 200-47.000.
 Kashiwa, Norio: See—
 Toyota, Akinori; Yoshitugu, Ken; and Kashiwa, Norio, 4,294,948, Cl. 526-125.000.
 Kaspar, Ernst, to BBC Brown, Boveri & Company Limited. Lattice bar for electrical machinery. 4,295,071, Cl. 310-213.000.
 Kassman, Allen J.; and Geisler, Willard A., Jr., to Philip Morris Incorporated. Filter cigarette with inlet vent zones. 4,294,265, Cl. 131-366.000.
 Kasuya, Kazuki, to Chlorine Engineers Corp., Ltd. Method for the production of cathode for use in electrolysis. 4,294,628, Cl. 148-6.350.
 Katayama, Morimitsu: See—
 Kisaka, Hiroyuki; Sagata, Makoto; Miyahara, Masayoshi; and Katayama, Morimitsu, 4,294,130, Cl. 74-15.400.
 Katayama, Tsutomu: See—
 Aoki, Shinji; Kawamura, Keita; Kimura, Hitoshi; Katayama, Tsutomu; Kaido, Chikara; and Yoshida, Hiroshi, 4,294,674, Cl. 204-157.10H.
 Kato, Akihiro: See—
 Takahashi, Tetsuo; Taguchi, Yoshinobu; Harigane, Kotaro; Ito, Tetsuro; and Kato, Akihiro, 4,294,000, Cl. 29-564.600.
 Kato, Hirohisa, to Ito Optical Industrial Co., Ltd. Coating composition comprising hydrolyzates from silane compounds. 4,294,950, Cl. 528-14.000.

- Kato, Jyoji: See—
Yoneda, Naoto; Kato, Jyoji; and Kinashi, Keizo, 4,294,832, Cl. 424-258.000.
- Kato, Tadaaki: See—
Sakagami, Teruo; Kato, Tadaaki; Hirai, Toru; and Murayama, Naohiro, 4,294,677, Cl. 204-181.00F.
- Kaufman, Arthur: Virtual image display apparatus, 4,294,515, Cl. 350-174.000.
- Kaufman, Kurt D., to Thomas C. Elder, Inc.: 5-Aminoalkyl-4,4,8-trialkylsoralens, 4,294,822, Cl. 424-59.000.
- Kaufman, Kurt D., to Thomas C. Elder, Inc.: 8-Aminoalkyl-4-alkylsoralens, 4,294,847, Cl. 424-279.000.
- Kaufman, Richard H.: See—
Margulies, Herman; and Kaufman, Richard H., 4,294,361, Cl. 206-532.000.
- Kaufmann, John, Jr., to Kaufmann, John, Jr.: Spring tension fastener, 4,293,984, Cl. 24-221.00R.
- Kawa, Hidetoshi; Mori, Kazuhiro; Misawa, Yoshihiko; and Nakagawa, Hiroshi, to Matsushita Electric Industrial Co., Ltd.: Automatic apparatus for inserting electric components, 4,293,998, Cl. 29-564.100.
- Kawakami, Kanji: See—
Takahashi, Minoru; Tanigami, Takahiko; Uchiyama, Kaoru; Minorikawa, Hitoshi; Nishihara, Motohisa; Kawakami, Kanji; Suzuki, Seiko; Hachino, Hiroaki; and Misawa, Yutaka, 4,295,115, Cl. 338-4.000.
- Kawamura, Keita: See—
Aoki, Shinji; Kawamura, Keita; Kimura, Hitoshi; Katayama, Tsutomu; Kaido, Chikara; and Yoshida, Hiroshi, 4,294,674, Cl. 204-157.10H.
- Kawano, Tsuyoshi; Usuda, Matsuo; and Hirokawa, Toshio, to Nippon Steel Corporation: Process for fabricating heavy wall to pipe, 4,294,095, Cl. 72-51.000.
- Kawasaki, Akiyoshi: See—
Hayashi, Masaki; Iguchi, Sadahiko; Okada, Takanori; and Kawasaki, Akiyoshi, 4,294,849, Cl. 424-305.000.
- Kawasaki Steel Corporation: See—
Oda, Kenichi, 4,294,305, Cl. 164-150.000.
- Keeler, Robert J., and Filipiak, Stanley E., to Illinois Tool Works Inc.: Secretarial shift mechanism for an electric keyboard, 4,295,012, Cl. 200-5.00B.
- Kehrer, Wolfgang; and Lachmann, Helmut, to Borsig GmbH: Tube-bundle heat exchanger for cooling a medium having a high inlet temperature, 4,294,312, Cl. 165-134.00R.
- Keith, Alec D., and Snipes, Wallace, to Key Pharmaceuticals, Inc.: Polymeric diffusion matrix containing phenylephrine, 4,294,820, Cl. 424-28.000.
- Keller, Alois, to Gebrueder Buehler AG: Drum-type screening machine and method of operation, 4,294,692, Cl. 209-300.000.
- Keller, Andre, to Roll & Go AG: Sole attachment for facilitating walking, 4,294,025, Cl. 36-132.000.
- Keller, Douglas V., Jr.: See—
Smith, Clay D.; and Keller, Douglas V., Jr., 4,294,695, Cl. 210-173.000.
- Keller, Russell D.: Fuel tank cap, 4,294,376, Cl. 220-318.000.
- Kelly, Arnold J., to Exxon Research & Engineering Co.: Mass sensing element, 4,294,105, Cl. 73-28.000.
- Kemme, Wendell J., to T/Drill, Inc.: Tube cutter, 4,294,011, Cl. 30-106.000.
- Kende, Andrew S.; Curran, Dennis P.; King, Margaret L.; and Feldstein, Neil A., to University of Rochester: Intermediates for the production of pteropodophyllin and related compounds and processes for the preparation and use thereof, 4,294,763, Cl. 260-340.5DP.
- Kennecott Corporation: See—
Stevens, John H.; and Reidel, Bruce A., 4,294,357, Cl. 206-409.000.
- Kenney, Michael J., to Dunlop Limited: Gelled lubricant composition for run-flat tires comprising polybutene acrylic or polyolefin gelling agent and particulate solid puncture sealing material, 4,294,730, Cl. 260-17.4BB.
- Kent Corporation, The: See—
Oztekin, Muammer A.; and Albano, Vincent J., 4,294,363, Cl. 211-49.00D.
- Kerlin, Thomas W.: See—
Hashemian, Hashem M.; Kerlin, Thomas W.; and Upadhyaya, Belle R., 4,295,128, Cl. 340-506.000.
- Kern, Heinz: See—
Brede, Uwe; and Kern, Heinz, 4,294,648, Cl. 156-627.000.
- Kernforschungsanlage Julich Gesellschaft mit beschränkter Haftung: See—
Labus, Herwig, 4,294,115, Cl. 73-342.000.
- Kernforschungszentrum Karlsruhe GmbH: See—
Siewerdt, Lothar, 4,294,504, Cl. 339-132.00R.
- Kestner, Diane E.: See—
Upson, Donald A.; Campbell, Gerald A.; and Kestner, Diane E., 4,294,739, Cl. 260-29.6RW.
- Key Pharmaceuticals, Inc.: See—
Keith, Alec D.; and Snipes, Wallace, 4,294,820, Cl. 424-28.000.
- Khagazheev, Dzhanon T.: See—
Vanjukov, Andrei V.; Mechev, Valery V.; Bystrov, Valentin P.; Ezhov, Evgeny I.; Vasiliev, Mikhail G.; Zaitsev, Vladimir Y.; Romenets, Vladimir A.; Ivanov, Vladimir V.; Golik, Sergei Y.; Grin-Gnatovsky, Evgeny S.; Grechko, Alexandr V.; Savin, Ivan V.; Kozhakhmetov, Sultanbek M.; Meierovich, Veniamin B.; Nagibin, Vladimir D.; Ramazanov, Nariman A.; Umarov, Almas B.; Ziberov, Valentin E.; Kunaev, Askar M.; Takezhanov, Sauk T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazheev, Dzhanon T., 4,294,433, Cl. 266-161.000.
- T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazheev, Dzhanon T., 4,294,433, Cl. 266-161.000.
- Khoe, Giok D.; Kock, Hendrikus G.; Meuleman, Lambertus J.; and Van Ruyven, Lodewijk J., to U.S. Philips Corporation: Optical coupler with a housing permitting adjustment of the distance between the light source and the lens, 4,295,152, Cl. 357-74.000.
- Kieffer, Vincent C.: Router guide apparatus and method, 4,294,297, Cl. 144-134.00D.
- Kierdorf, Hans: See—
Schmitz, Gunther; and Kierdorf, Hans, 4,294,064, Cl. 57-3.000.
- Kihara, Kunio; Toda, Hideo; Yasukawa, Eiki; Ishibashi, Toshiaki; and Tokita, Takatoshi, to Mitsubishi Petrochemical Company Limited: Process for the production of an ion exchange membrane, 4,294,933, Cl. 521-27.000.
- Kilburn, James S., to Occidental Oil Shale, Inc.: Thermally insulated bulkhead for in situ oil shale retort, 4,294,563, Cl. 405-132.000.
- Killmann, Irolt; and Bonifer, Georg W., to Klockner-Humboldt-Deutz Aktiengesellschaft: Apparatus for working aligned bores, 4,294,546, Cl. 356-399.000.
- Kim, Dae K.; Bertolacini, Ralph J.; Gutberlet, L. Charles; and Robinson, Ken K., to Electric Power Research Institute, Inc.: Process for coal liquefaction and catalyst, 4,294,685, Cl. 208-10.000.
- Kim, Han J.; Peters, Thomas E.; and Gustafson, John, to GTE Products Corporation: Electrical contacts, 4,294,616, Cl. 75-234.000.
- Kimball, Charles A.; and Sullivan, Marc L., to Time Commercial Financing Corporation: Cab suspension and restraining device, 4,294,324, Cl. 180-89.140.
- Kimoto, Yasuo; Tamiya, Katsunori; Honda, Shoichi; Maehata, Hidehiko; and Kamada, Hiroshi, to Hitachi Shipbuilding & Engineering Co., Ltd.: Method of mirror-finishing a cylindrical workpiece, 4,294,673, Cl. 204-129.460.
- Kimura, Hitoshi: See—
Aoki, Shinji; Kawamura, Keita; Kimura, Hitoshi; Katayama, Tsutomu; Kaido, Chikara; and Yoshida, Hiroshi, 4,294,674, Cl. 204-157.10H.
- Kimura, Toyohiko: See—
Hashimoto, Akihiko; Nakajima, Yukio; Koiwai, Tamotsu; and Kimura, Toyohiko, 4,294,527, Cl. 354-25.000.
- Kinaga, Eiichi; and Mori, Mamoru, to Toyota Jidosha Kogyo Kabushiki Kaisha: Seatbelt system, 4,294,468, Cl. 280-807.000.
- Kinashi, Keizo: See—
Yoneda, Naoto; Kato, Jyoji; and Kinashi, Keizo, 4,294,832, Cl. 424-258.000.
- Kinergetics, Inc.: See—
Cowans, Kenneth W., 4,294,242, Cl. 128-201.130.
- King, Barton: Air conditioning system, 4,294,083, Cl. 62-434.000.
- King, Dennis M.; and Richardson, Ronald D., to Caterpillar Tractor Co.: Differential timing altering mechanism for fuel injectors, 4,294,218, Cl. 123-502.000.
- King, Margaret L.: See—
Kende, Andrew S.; Curran, Dennis P.; King, Margaret L.; and Feldstein, Neil A., 4,294,763, Cl. 260-340.5DP.
- Kings, Donald; and Quang, Pham K., to Rhone Poulenc Systemes: Process for electrostatically developing and pressure-fixing a reversed image including charge dissipation prior to fixing, 4,294,903, Cl. 430-98.000.
- Kinumaki, Toyosuke; Watanabe, Takehiko; Sugii, Kisaburo; and Iseki, Shigeo, to Tokai Regional Fisheries Research Laboratory: Process for manufacture of artificial milk replacer for raising infant pigs and other infant animals, 4,294,856, Cl. 426-7.000.
- Kircher, Charles J.; Huang, Hung-Chang W.; and Murakami, Masanori, to International Business Machines Corp.: Josephson devices of improved thermal cyclability and method, 4,295,147, Cl. 357-5.000.
- Kirisawa, Atsushi, to Japan Envirotic Industry Co., Ltd.: Method for the treatment of surfaces and apparatus employed in said method, 4,294,626, Cl. 148-6.200.
- Kirsch, Bernhard: Foot-plates for ski-bindings, 4,294,460, Cl. 280-607.000.
- Kisaka, Hiroyuki; Sagata, Makoto; Miyahara, Masayoshi; and Katayama, Morimitsu, to Kubota Ltd.: Transmission for tractor, 4,294,130, Cl. 74-15.400.
- Kishi, Akira: See—
Minematsu, Hiroyuki; Matsumoto, Kojiro; Saeki, Tadashi; and Kishi, Akira, 4,294,946, Cl. 526-80.000.
- Kiss, Gyula: See—
Tamas, Istvan; Tamas, Lajos; Kiss, Gyula; Kiss, Jozsef; and Kaldor, Antal, 4,294,611, Cl. 75-49.000.
- Kiss, Jozsef: See—
Tamas, Istvan; Tamas, Lajos; Kiss, Gyula; Kiss, Jozsef; and Kaldor, Antal, 4,294,611, Cl. 75-49.000.
- Kitai, Kiyoshi; Ogihara, Masuo; and Chimura, Kozo, to Seiko Koki Kabushiki Kaisha: Second hand correction device for use in timepieces, 4,295,215, Cl. 368-196.000.
- Kitrell, John V.: Pedicure easel, 4,294,268, Cl. 132-73.000.
- Kiuchi, Norihiro: See—
Uchida, Seiichi; Satomi, Yoshihito; Kiuchi, Norihiro; Yamagata, Takeo; Yoshioka, Susumu; Miyamoto, Tomohiko; and Tomuro, Jinichi, 4,294,803, Cl. 422-111.000.
- Kiwala, Jacob: See—
Sprecker, Mark A.; Schmitt, Frederick L.; Vock, Manfred H.; Vinals, Joaquin F.; and Kiwala, Jacob, 4,294,708, Cl. 252-8.600.
- Klaiber, William C.: Apparatus for washing, rinsing and spin drying paint rollers, 4,294,272, Cl. 134-138.000.
- Kleber, Rolf; and Billenstein, Siegfried, to Hoechst Aktiengesellschaft: Alkyl-polyglycol mixed formal as fiber preparation agents, 4,294,990, Cl. 568-601.000.

- Klees, Garry W., to Boeing Company: The Supersonic jet engine and method of operating the same, 4,294,068, Cl. 60-204.000.
- Klein, Alfons; Kron, Rudolf; Wedemeyer, Karlfried; Knust, Ernst; and Havenith, Lothar, to Bayer Aktiengesellschaft: Impregnating agent and its use, 4,294,715, Cl. 361-318.000.
- Klein, David I., to Eng, George, a part interest: Device with visual and audio output, 4,294,035, Cl. 46-227.000.
- Klein, Robert R.; and Makowski, Henry S., deceased (by Makowski, Patricia, executrix), to Exxon Research & Engineering Co.: Process for forming a powdered EPDM terpolymer (C-955), 4,294,744, Cl. 260-33.6AQ.
- Kline, Ellis L.: See—
McMichael, John; Kline, Ellis L.; and Spaulding, James G., 4,294,818, Cl. 424-12.000.
- Kling, Erich: See—
Sloane, Thomas E., Jr.; Melius, Clair; and Kling, Erich, 4,294,594, Cl. 55-186.000.
- Klingaman, Richard M.; and Ehrenreich, Leo C., to Penn Virginia Corporation: Pyroplastoid particles, composition and method of production, 4,294,750, Cl. 260-40.00R.
- Klis, David S.: See—
Granger, Bruce A.; and Klis, David S., 4,294,339, Cl. 192-12.0BA.
- Klockner-Humboldt-Deutz Aktiengesellschaft: See—
Jordan, Friedrich, 4,293,995, Cl. 29-421.00R.
- Killmann, Irolt; and Bonifer, Georg W., 4,294,546, Cl. 356-399.000.
- Knight, Arthur J.: See—
Turnbull, James O.; Barker, John C.; and Knight, Arthur J., 4,294,021, Cl. 34-224.000.
- Knoll, Berta: See—
Knoll, Jozsef; Kalasz, Huba; Knoll, Berta; and Nagy, Janos, 4,294,825, Cl. 424-101.000.
- Knoll, Jozsef; Kalasz, Huba; Knoll, Berta; and Nagy, Janos, to Richter Gedeon Vegyeszeti Gyar RT.: Process for the production of an androgenic substance having specific effect on the central regulation of food intake, 4,294,825, Cl. 424-101.000.
- Knollmueller, Karl O.; Fairbrother, Robert J.; and Gavin, David F., to Olin Corporation: Grease compositions containing selected shielded polysilicate compounds, 4,294,713, Cl. 252-28.000.
- Knowles, William S.; and Sabacky, Milton J., to Monsanto Company: Methylcyclohexyl-O-anisylphosphine, 4,294,989, Cl. 568-13.000.
- Knust, Ernst: See—
Klein, Alfons; Kron, Rudolf; Wedemeyer, Karlfried; Knust, Ernst; and Havenith, Lothar, 4,294,715, Cl. 361-318.000.
- Koa Oil Company, Limited: See—
Okamura, Okiyoshi, 4,295,092, Cl. 324-61.00R.
- Kobayashi, Masatoshi; Shimakawa, George; Hara, Yukio; Fujii, Hiroyuki; and Kabushiki Kaisha Seikoshu, to Matsushita Kogyo Kabushiki Kaisha: Method of making a quartz crystal oscillator, 4,293,986, Cl. 29-25.350.
- Kobayashi, Shunji: See—
Watanabe, Teruoki; Kanno, Tadao; Hidaka, Akio; and Kobayashi, Shunji, 4,294,630, Cl. 148-16.600.
- Kobe, Inc.: See—
Erickson, John W.; and Petrie, Harold L., 4,294,573, Cl. 417-83.000.
- Koberstein, Edgar: See—
Bozon, Alfred; Koberstein, Edgar; Pletka, Hans-Dieter; Volker, Herbert; and Lakatos, Eduard, 4,294,726, Cl. 252-462.000.
- Koch, Klaus: See—
Doerk, Klaus; Koch, Klaus; Banke, Horst; and Toben, Bernhard, 4,294,947, Cl. 526-119.000.
- Kock, Hendrikus G.: See—
Khoe, Giok D.; Kock, Hendrikus G.; Meuleman, Lambertus J.; and Van Ruyven, Lodewijk J., 4,295,152, Cl. 357-74.000.
- Kodera, Yuji; Ikari, Kyoichiro; and Miyake, Shunji, to Kuraray Company, Limited: Method of producing ethylene-vinyl alcohol copolymer film, 4,294,935, Cl. 525-60.000.
- Koenig, Karl-Heinz; Feuerherd, Karl-Heinz; and Oeser, Heinz-Guenter, to BASF Aktiengesellschaft: Preparation of 1-haloalkyl isocyanates and 1-alkenyl isocyanates, 4,294,773, Cl. 260-453.00P.
- Koga, Kenichiro; Hirose, Yoshiharu; Kanno, Iwao; Uemura, Kazuo; and Miura, Shuichi, to Shimadzu Corporation: Emission computed tomograph, 4,295,047, Cl. 250-363.00S.
- Kohler, Karl A., to Container Corporation of America: Carton with self erecting partitions, 4,294,397, Cl. 229-27.000.
- Kohno, Toshiaki: See—
Hidaka, Hidemasa; Kohno, Toshiaki; and Eida, Toshiaki, 4,294,623, Cl. 127-55.000.
- Koike, Akinobu: See—
Okishi, Yoshio; Koike, Akinobu; and Miyano, Shizuo, 4,294,905, Cl. 430-175.000.
- Koike, Kengo: See—
Nakagawa, Taizo; Matsumoto, Hiroshi; Ohmori, Kaoru; Shimano, Shizuo; and Koike, Kengo, 4,294,835, Cl. 424-263.000.
- Koike, Norio: See—
Takemoto, Iwao; Koike, Norio; Ohba, Shinya; Ando, Haruhisa; Nakai, Masaaki; Hanamura, Syoji; Izawa, Ryuichi; Kubo, Masaharu; Aoki, Masakazu; and Tanaka, Shuhei, 4,295,055, Cl. 307-221.00C.
- Koike, Toshifumi: See—
Yoshioka, Masahiro; Koike, Toshifumi; and Izumi, Hideki, 4,294,494, Cl. 308-76.000.
- Koiwai, Tamotsu: See—
Hashimoto, Akihiko; Nakajima, Yukio; Koiwai, Tamotsu; and Kimura, Toyohiko, 4,294,527, Cl. 354-25.000.
- Kojima, Hisao: See—
Obata, Toshiharu; Hagyu, Toshimasa; and Kojima, Hisao, 4,294,396, Cl. 228-245.000.
- Kokan Kikai Kogyo Kabushiki Kaisha: See—
Sawada, Hajimu; and Inubushi, Hisao, 4,294,437, Cl. 266-272.000.
- Koleske, Joseph V.: See—
Blair, Eskel B.; and Koleske, Joseph V., 4,294,746, Cl. 260-37.0EP.
- Kolesnikov, Boris I.: See—
Vanjukov, Andrei V.; Mechev, Valery V.; Bystrov, Valentin P.; Ezhov, Evgeny I.; Vasiliev, Mikhail G.; Zaitsev, Vladimir Y.; Romenets, Vladimir A.; Ivanov, Vladimir V.; Golik, Sergei Y.; Grin-Gnatovsky, Evgeny S.; Grechko, Alexandr V.; Savin, Ivan V.; Kozhakhmetov, Sultanbek M.; Meierovich, Veniamin B.; Nagibin, Vladimir D.; Ramazanov, Nariman A.; Umarov, Almas B.; Ziberov, Valentin E.; Kunaev, Askar M.; Takezhanov, Sauk T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazheev, Dzhanon T., 4,294,433, Cl. 266-161.000.
- Kollenz, Erich, to Voest-Alpine Aktiengesellschaft: Process for separating weakly magnetic accompanying minerals from nonmagnetic useful minerals, 4,294,690, Cl. 209-3.000.
- Kolnes, Kenneth O.; and Johnson, Wynsel J., to Greenlee Bros. & Co.: Workpiece pallet with distortion free clamping means, 4,294,442, Cl. 269-101.000.
- Kolodziejczyk, Pawel: See—
Falkowski, Leonard; Stefanska, Barbara; Zielinski, Jan; Troka, Elzbieta; Golik, Jerzy; Kolodziejczyk, Pawel; Jarzelski, Andrzej; Cybulska, Emilia; and Borowski, Edward, 4,294,958, Cl. 536-17.00R.
- Koomey, Inc.: See—
Murthy, Rajam R., 4,294,288, Cl. 138-30.000.
- Korpman, Ralf, to Permaceil: Adhesive compositions, 4,294,936, Cl. 525-93.000.
- Kosaka, Yoshiteru: See—
Hirota, Akira; Kosaka, Yoshiteru; and Ashida, Kazutaka, 4,295,171, Cl. 360-73.000.
- Kostan, Charles C.: See—
Fox, David H.; and Kostan, Charles C., 4,295,014, Cl. 200-19.00R.
- Kotani, Hirotaro: Collapsible luggage carrier, 4,294,463, Cl. 280-646.000.
- Kotaucaek, Peter: See—
Hufnagl, Walter; and Kotaucaek, Peter, 4,294,870, Cl. 427-189.000.
- Kotecki, Damian J., to Teledyne Industries, Inc.: Austenitic iron-base cryogenic alloy and arc welding electrode for depositing the same, 4,294,614, Cl. 75-128.00A.
- Kovatch, George N.; and Wallace, James B., to Westinghouse Electric Corp.: Electric control system with mechanical interlock, 4,295,053, Cl. 307-64.000.
- Kovatch, George N.; Bettencourt, George S.; and Soles, Otto H., to Westinghouse Electric Corp.: Electric control system with rotary mechanical interlock and timing mechanism, 4,295,054, Cl. 307-80.000.
- Kowalski, Xavier, to Monsanto Company: Peroxide stabilization, 4,294,575, Cl. 8-111.000.
- Koyanagi, Katubumi: See—
Nakauchi, Hiroshi; Koyanagi, Katubumi; Inami, Yasuhiko; and Ueda, Hisashi, 4,295,138, Cl. 340-785.000.
- Kozhakhmetov, Sultanbek M.: See—
Vanjukov, Andrei V.; Mechev, Valery V.; Bystrov, Valentin P.; Ezhov, Evgeny I.; Vasiliev, Mikhail G.; Zaitsev, Vladimir Y.; Romenets, Vladimir A.; Ivanov, Vladimir V.; Golik, Sergei Y.; Grin-Gnatovsky, Evgeny S.; Grechko, Alexandr V.; Savin, Ivan V.; Kozhakhmetov, Sultanbek M.; Meierovich, Veniamin B.; Nagibin, Vladimir D.; Ramazanov, Nariman A.; Umarov, Almas B.; Ziberov, Valentin E.; Kunaev, Askar M.; Takezhanov, Sauk T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazheev, Dzhanon T., 4,294,433, Cl. 266-161.000.
- Kraemer & Grebe GmbH & Co. KG Maschinen- und Modellfabrik: See—
Wetter, Manfred; and Schmidt, Karl H., 4,294,415, Cl. 241-292.000.
- Kraemer, Horst, to Siemens Aktiengesellschaft: Microphone amplifier, in particular for telephone systems, 4,295,100, Cl. 330-257.000.
- Kraev, Vladislav P.: See—
Berenov, Alexandr D.; Kraev, Vladislav P.; Mansurov, Midkhat M.; Niskovskikh, Vitaly M.; and Silin, Evgeny L., 4,294,306, Cl. 164-448.000.
- Kramer, Henry H.: See—
Picunko, Thomas; Kramer, Henry H.; Dam, Naim G.; and Gray, Robert L., 4,294,259, Cl. 128-653.000.
- Kramer, Petrus A.; and Verbrugge, Pieter A., to Shell Oil Company: Cis-lactone pyrethroid intermediates, 4,294,765, Cl. 260-343.30R.
- Kranz, Joachim: See—
Sappok, Reinhard; and Kranz, Joachim, 4,294,620, Cl. 106-288.00Q.
- Kreibich, Ursula; and Schmid, Rolf, to CIBA-GEIGY Corporation: Apparatus for heating water by solar heat, 4,294,227, Cl. 126-400.000.
- Kreikenbohm, Robert: See—
Reusch, Heinz; and Kreikenbohm, Robert, 4,294,310, Cl. 165-104.130.
- Kreinbrink, Paul H.; and Neiman, David C., to Libbey-Owens-Ford Company: Marking and counting probe assembly, 4,295,038, Cl. 235-92.0PK.
- Kretzschmar, Robert O.: See—
Woloshuk, Edward A.; Walz, Gregory J.; and Kretzschmar, Robert O., 4,294,523, Cl. 352-86.000.
- Krieg, Adrian H., to Widder Corporation: Portable hacksaw, 4,294,013, Cl. 30-392.000.

- Krob, Erwin: See—
Svoboda, Josef; Krob, Erwin; and Weigl, Erwin, 4,294,459, Cl. 280-605.000.
- Krock, Friedrich W.; and Neef, Rutger, to Bayer Aktiengesellschaft. Colorants, 4,294,578, Cl. 8-516.000.
- Krock, Friedrich W.; Neef, Rutger; and Scheiter, Heinz, to Bayer Aktiengesellschaft. Process for the preparation of 1,4-diamino-2,3-dicyano-anthraquinones, 4,294,769, Cl. 260-378.000.
- Kron, Rudolf: See—
Klein, Alfons; Kron, Rudolf; Wedemeyer, Karlfried; Knust, Ernst; and Havenith, Lothar, 4,294,715, Cl. 361-318.000.
- Kronseder, Hermann: See—
Schneider, Egon, 4,293,989, Cl. 29-130.000.
- Krueger, Arnold F., to M & K Industries, Inc. Roller skate construction, 4,294,455, Cl. 280-11.200.
- Krueger, Siegfried: See—
Astheimer, Hans J.; Brandtstaedter, Horst; Ohlinger, Rainer; Van Pee, Willy; Van Steen, Jaak; Sauer, Friedrich; Schmidt, Rudolf; and Krueger, Siegfried, 4,294,666, Cl. 203-72.000.
- Kruger, Jorg; Thome, Roland; Moritz, Dieter; Bings, Hubert; and Losert, Herbert, to Vereinigte aluminium-Werke Aktiengesellschaft. Process for producing hydrogen fluoride from fluorine containing materials by continuous pyrohydrolysis, 4,294,816, Cl. 423-484.000.
- Kruger, Robert; and Miller, William J. Solar heating and subterranean cooling, 4,294,228, Cl. 126-430.000.
- Kubo, Masaharu: See—
Takemoto, Iwao; Koike, Norio; Ohba, Shinya; Ando, Haruhisa; Nakai, Masaki; Hanamura, Syoji; Izawa, Ryuchii; Kubo, Masaharu; Aoki, Masakazu; and Tanaka, Shuhei, 4,295,055, Cl. 307-221.000.
- Kubo, Yoshizo: See—
Kasashima, Masao; and Kubo, Yoshizo, 4,295,119, Cl. 338-162.000.
- Kubota Ltd.: See—
Kisaka, Hiroyuki; Sagata, Makoto; Miyahara, Masayoshi; and Katayama, Morimitsu, 4,294,130, Cl. 74-15.400.
- Murayama, Yoshinobu, 4,294,131, Cl. 74-15.400.
- Okada, Yoshitsugu; and Nakai, Osamu, 4,294,428, Cl. 251-214.000.
- Kubota, Masayoshi: See—
Sawa, Toshio; Kubota, Masayoshi; Takahashi, Sankichi; and Kaneko, Toyohiko, 4,294,697, Cl. 210-221.100.
- Kubota, Michio; Takagi, Kazuhiro; and Mitani, Yomimasu, to Nisshin Steel Co., Ltd. Method for overaging of hot dip metal coated steel material, 4,294,632, Cl. 148-142.000.
- Kubota, Yuzuru: See—
Nagase, Hiroshi; Okuyama, Toshiaki; Kubota, Yuzuru; and Suzuki, Katsunori, 4,295,084, Cl. 318-719.000.
- Kuehnle, Werner: See—
Ebersberger, Otto; and Kuehnle, Werner, 4,295,049, Cl. 250-409.000.
- Kuehnle, Manfred R., to Coulter Systems Corporation. Apparatus and method for preventing contamination of sputtering targets, 4,294,678, Cl. 204-192.00R.
- Kuhlthau, Hans-Peter, to Bayer Aktiengesellschaft. Cationic dyestuffs, 4,294,756, Cl. 260-163.000.
- Kuhr, Albert F., to United States Gypsum Company. Soffit system for suspended ceiling, 4,294,054, Cl. 52-484.000.
- Kullander, Mats O., to Billerud Uddeholm AB. Method and an apparatus for coating a web with a coating composition, 4,294,872, Cl. 427-358.000.
- Kulp, Karel; and Hoover, William J., to American Institute of Baking, The. Preparation of high-ratio cakes using untreated wheat flour, 4,294,864, Cl. 426-549.000.
- Kuma, Hisao: See—
Hatada, Minoru; Hiyama, Kunio; Ihara, Hirokazu; and Kuma, Hisao, 4,295,122, Cl. 340-147.0LP.
- Kumazawa, Eitaro; Saiki, Yukihiko; and Ishioka, Yozo, to Snow Brand Milk Products Co., Ltd. Material feed pipe for use in belt-system continuous vacuum drier, 4,294,018, Cl. 34-56.000.
- Kunaev, Askar M.: See—
Vanjukov, Andrei V.; Mechev, Valery V.; Bystrov, Valentin P.; Ezhov, Evgeny I.; Vasiliev, Mikhail G.; Zaitsev, Vladimir Y.; Romanets, Vladimir A.; Ivanov, Vladimir V.; Golik, Sergei Y.; Grin-Gnatovsky, Evgeny S.; Grechko, Alexandr V.; Savin, Ivan V.; Kozhakhmetov, Sultanbek M.; Meierovich, Veniamin B.; Nagibin, Vladimir D.; Ramazanov, Nariman A.; Umarov, Almas B.; Ziberov, Valentin E.; Kunaev, Askar M.; Takezhanov, Saik T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazheev, Dzhonson T., 4,294,433, Cl. 266-161.000.
- Kunstadt, George H. Solid state mass memory system compatible with rotating disc memory equipment, 4,295,205, Cl. 364-900.000.
- Kunstlicher, Erich; and Thomasson, Harry V. Knife holder, 4,294,421, Cl. 248-37.600.
- Kunze, Dieter, to Jean Walterscheid GmbH. Overload clutch, 4,294,340, Cl. 192-56.00R.
- Kuo, Chang-Kiang, to Texas Instruments Incorporated. Method of making implant programmable metal gate MOS read only memory, 4,294,001, Cl. 29-571.000.
- Kuraray Company, Limited: See—
Kodera, Yuji; Ikari, Kyoichiro; and Miyake, Shunji, 4,294,935, Cl. 525-60.000.
- Kureha Kagaku Kogyo Kabushiki Kaisha: See—
Haga, Toshikatsu; Fukuda, Hiroyuki; Shinoda, Hiroshi; and Hayakawa, Hideharu, 4,294,795, Cl. 264-332.000.
- Sakagami, Teruo; Kato, Tadaaki; Hirai, Toru; and Murayama, Naohiro, 4,294,677, Cl. 204-181.00F.
- Takita, Hitoshi; Mukaida, Yutaka; and Enomoto, Satoru, 4,294,770, Cl. 260-413.000.
- Kurimoto, Kyoichi: See—
Mori, Keiji; and Kurimoto, Kyoichi, 4,294,134, Cl. 74-547.000.
- Kusulas, Peter, Jr.: See—
Draper, Don R.; and Kusulas, Peter, Jr., 4,295,219, Cl. 371-51.000.
- Kuth, Robert: See—
Hendricks, Udo-Winfred; Hildebrand, Dietrich; and Kuth, Robert, 4,294,579, Cl. 8-549.000.
- Kutzner, Luitpold: See—
Diermayer, Werner; Kutzner, Luitpold; and Postenreider, Erwin, 4,294,401, Cl. 236-1.00G.
- Kuus, Albert: See—
Snel, Cornelis; and Kuus, Albert, 4,294,197, Cl. 119-60.000.
- Kuus, Olaf: See—
Dalheimer, Walter; and Kuus, Olaf, 4,294,039, Cl. 49-248.000.
- Kuzunuki, Tatsuo: See—
Watanabe, Shigeru; and Kuzunuki, Tatsuo, 4,295,042, Cl. 250-226.000.
- Kyte, Albert D. Compact toothbrush kit, 4,294,269, Cl. 132-84.00B.
- Labus, Herwig, to Kernforschungsanlage Julich Gesellschaft mit beschränkter Haftung. Measuring device for practically simultaneous ΔT and T measurement, 4,294,115, Cl. 73-342.000.
- Lachmann, Helmut: See—
Kehrer, Wolfgang; and Lachmann, Helmut, 4,294,312, Cl. 165-134.00R.
- Lade, Robert W.; Spellman, Gordon B.; Jaskolski, Stanley V.; Schutten, Herman P.; and Jaeschke, James R., to Eaton Corporation. Radiant energy activated semiconductor switch, 4,295,058, Cl. 307-252.00A.
- Lafuze, David L., to General Electric Company. Phase lock loop commutation position control and method, 4,295,085, Cl. 318-721.000.
- Lagoni, William A., to RCA Corporation. Signal processing circuit having a non-linear transfer function, 4,295,160, Cl. 358-31.000.
- Lakatos, Eduard: See—
Bozon, Alfred; Koberstein, Edgar; Pletka, Hans-Dieter; Volker, Herbert; and Lakatos, Eduard, 4,294,726, Cl. 252-462.000.
- Lake, Donald E.; and Hart, John M., Jr., to General Motors Corporation. Pressure sensor assembly, 4,295,117, Cl. 338-4.000.
- Lam, Calvin K.: See—
Sarcia, Domenico S.; and Lam, Calvin K., 4,294,600, Cl. 62-6.000.
- Lampert, Lester M. Article of jewelry with reciprocally movable gem, 4,294,084, Cl. 63-15.000.
- Land, Donald E. Film punch, 4,294,152, Cl. 83-588.000.
- Landers, Derek J.: See—
Gage, Millard E.; and Landers, Derek J., 4,295,013, Cl. 200-11.00C.
- Lane, John E., to Parks-Cramer Company. Method and apparatus for facilitating maintenance of spinning machine information system, 4,294,065, Cl. 57-265.000.
- Lane, John E., to Parks-Cramer Company. Method and apparatus for displaying specific spinning machine operating conditions, 4,294,066, Cl. 57-265.000.
- Lang, Tibor: See—
Alfoldi, Lajos; Balint nee Fodor, Katalin; Kari, Csaba; Torok, Istvan; Szvoboda, Gyorgy; Lang, Tibor; Gado, Istvan; and Ambrus, Gabor, 4,294,927, Cl. 435-172.000.
- Langdon, Glen G., Jr., to International Business Machines Corporation. Method and means for pipeline decoding of the high to low order pairwise combined digits of a decodable set of relatively shifted finite number of strings, 4,295,125, Cl. 340-347.0DD.
- Lanz, Donald D. Chain saw anti-pinch guard arm, 4,294,012, Cl. 30-378.000.
- Lanzel, Leo C.: See—
Nystrom, William A.; Lanzel, Leo C.; and Bauer, William A., 4,294,438, Cl. 266-280.000.
- Larkin, Miles K. Locking means, 4,294,560, Cl. 403-104.000.
- Larsen, Charles H. Shower head and valve assembly for camping shower, 4,294,409, Cl. 239-577.000.
- Larsen, Owen M. Gate assembly, 4,294,196, Cl. 119-27.000.
- Laska, Ronald C.; and Pone, Janis, to Pako Corporation. Photographic reprint system with information display, 4,294,537, Cl. 355-35.000.
- Laskow, William; and Morelock, Charles R., to General Electric Company. Method of making a shaped silicon carbide-silicon matrix composite and articles made thereby, 4,294,788, Cl. 264-101.000.
- Latta, Milton R., to International Business Machines Corporation. Acousto-optically modulated laser scanning arrangement for correcting for interference appearing therein, 4,295,145, Cl. 346-108.000.
- Lauterbach, Heinz, to Robert Bosch GmbH. Apparatus for the measurement of the mass of a flowing medium, 4,294,114, Cl. 73-204.000.
- Lawrance, Richard J.: See—
Sedlak, John M.; and Lawrance, Richard J., 4,294,608, Cl. 75-0.50A.
- Laymon, Marvin D.: See—
Burney, Charles F.; and Laymon, Marvin D., 4,295,132, Cl. 340-562.000.
- Le Matériel Telephonique: See—
Quintin, Renee; and Villemant, Claude M., 4,294,009, Cl. 29-832.000.
- Leavitt, Clyde M.: See—
Reynoir, Ronald H.; Flautt, Robert A.; and Leavitt, Clyde M., 4,294,331, Cl. 182-10.000.
- LeBoeuf, Albert R., to American Optical Corporation. Hydrophilic silicone compounds and contact lenses containing polymers thereof, 4,294,974, Cl. 556-440.000.
- Lectret S.A.: See—
Murphy, Preston V., 4,295,010, Cl. 179-110.00A.

- Lee, Bobby L. Artificial flowers and method for their manufacture, unistem, 4,293,997, Cl. 29-450.000.
- Lee, Ross A., to Du Pont de Nemours, E. I., and Company. Photosensitive negative-working toning process, 4,294,909, Cl. 430-291.000.
- Lee, Tsao-Piao. Pipette controller with graduate reading plunger and lever assembly for gravity drainage, 4,294,125, Cl. 73-864.150.
- Leenhouts, Albert C., to Superior Electric Company, The. Pulsed energy stepping motor power control unit, 4,295,083, Cl. 318-696.000.
- Leesona Corporation: See—
Gerstenberg, Roy W., 4,294,414, Cl. 241-222.000.
- Le Fur, Gerard R.: See—
Champseix, Alain A.; and Le Fur, Gerard R., 4,294,841, Cl. 424-267.000.
- Leichnitz, Kurt, to Dragerwerk Aktiengesellschaft. Highly sensitive gas measuring method for the analysis of breath alcohol concentrations, using test tubes, 4,294,583, Cl. 23-232.00R.
- Leidich, Arthur J., to RCA Corporation. Class AB push-pull quasi-linear amplifiers, 4,295,101, Cl. 330-262.000.
- Leineweber, Jürgen: See—
Grueter, Karl; and Leineweber, Jürgen, 4,295,046, Cl. 250-287.000.
- Leitex Stockholms-Tvätt Aktiebolag: See—
Holmquist, Borje G. A., 4,294,781, Cl. 261-89.000.
- Lekas, John P. Comestible packaging apparatus, 4,294,061, Cl. 53-536.000.
- Lembke, Manfred: See—
Hans, Waldmar; Sauer, Rudolf; Glockler, Otto; Steinbrenner, Ulrich; Gunther, Dieter; and Lembke, Manfred, 4,294,215, Cl. 123-470.000.
- Lemelson, Jerome H. Solar energy collection panel and method, 4,294,230, Cl. 126-438.000.
- Lemus, Julian. Anti-kick back device, 4,294,151, Cl. 83-477.200.
- LeRoy, Rodney L., to Noranda Mines Limited; and Electrolyser Corporation Ltd., The. Hydrogen injection into gas pipelines and other pressurized containers, 4,294,274, Cl. 137-7.000.
- Les Entreprises Rotot Lee: See—
Thiboutot, Robert, 4,294,457, Cl. 280-20.000.
- Leshner, George Y.; and Brundage, Ruth P., to Sterling Drug Inc. 1,3-Dihydro-6-(pyridinyl)-2H-imidazo[4,5-b]pyridine-2-ones and -imidazo[4,5-b]pyridine-2-thiones and their cardiotonic use, 4,294,836, Cl. 424-263.000.
- Leshner, George Y.; Opalka, Chester J., Jr.; and Page, Donald F., to Sterling Drug Inc. 1,3-Dihydro-6-(pyridinyl)-2H-imidazo[4,5-b]pyridine-2-ones and -imidazo[4,5-b]pyridine-2-thiones and their cardiotonic use, 4,294,837, Cl. 424-263.000.
- LeVeen, Harry H. Sterile article container with sterile opening edge portions, 4,294,360, Cl. 206-438.000.
- Levin, Gilbert V.; and Straat, Patricia A., to Biospherics Incorporated. Device for conducting microbiological radiorespirometric assays, 4,294,931, Cl. 435-301.000.
- Levine, Elliott M. Interconnected water skis, 4,293,968, Cl. 9-310.00A.
- Lewis, Alfred E.; and Salisbury, Robert E., to Preco Inc. Single column load dividing gate, 4,294,569, Cl. 410-133.000.
- Lewis, Robert A.; and Honnen, Lewis R., to Chevron Research Company. Carboxylic acid salt containing deposit control additives and fuel and lube oil compositions containing them, 4,294,714, Cl. 252-34.000.
- Leybold Heraeus GmbH: See—
Grueter, Karl; and Leineweber, Jürgen, 4,295,046, Cl. 250-287.000.
- Li, Ming K., to General Electric Company. Purification of bisphenol-A, 4,294,993, Cl. 568-724.000.
- Li, Ming K., to General Electric Company. Purification of bisphenol-A, 4,294,994, Cl. 568-724.000.
- Libbey-Owens-Ford Company: See—
Kreinbrink, Paul H.; and Neiman, David C., 4,295,038, Cl. 235-92.0PK.
- Licentia Patent-Verwaltungs GmbH: See—
Rausser, Horst, 4,295,164, Cl. 358-166.000.
- Lieberman, Abraham. Method and apparatus for cutting into segments a continuously moving web of rigid insulation, 4,294,143, Cl. 83-37.000.
- Lieberman, Gilbert R., to Gilbert Products. Locking means for a lamp holder, 4,294,503, Cl. 339-119.00L.
- Liedtke, Kurt: See—
Focke, Heinz; and Liedtke, Kurt, 4,294,642, Cl. 156-250.000.
- Focke, Heinz H.; and Liedtke, Kurt, 4,294,353, Cl. 206-273.000.
- Lightburn & Co. Limited: See—
Watson, Arthur, 4,294,548, Cl. 366-60.000.
- Lincoln, Howard P.; and Reddinger, Donald M., to GTE Products Corporation. Process for plating selected metal areas, 4,294,669, Cl. 204-15.000.
- Lincoln, Howard P.; and Reddinger, Donald M., to GTE Products Corporation. Apparatus for selective metal plating, 4,294,680, Cl. 204-224.00R.
- Lincoln, Howard P.; and Reddinger, Donald M., to GTE Products Corporation. Molded selective plating mask, 4,294,681, Cl. 204-224.00R.
- Lincoln, Howard P.; and Reddinger, Donald M., to GTE Products Corporation. Plating mask fabricating process, 4,294,789, Cl. 264-102.000.
- Lindahl, Jonas A. I.; and Rudstrom, Lars G., to Mo och Domsjö Aktiebolag. Process for manufacturing chemimechanical cellulose pulp in a high yield within the range from 65 to 95%, 4,294,653, Cl. 162-25.000.
- Linde AG: See—
Lohmuller, Reiner; Schneider, Helmut; and Watson, Allan, 4,294,932, Cl. 518-706.000.
- Linde Aktiengesellschaft: See—
Linde, Gerhard; Haussinger, Peter; and Schliebener, Claus, 4,294,590, Cl. 55-48.000.
- Linde, Gerhard; Haussinger, Peter; and Schliebener, Claus, to Linde Aktiengesellschaft. Removal of undesired gaseous components from hot waste gases, 4,294,590, Cl. 55-48.000.
- Linden, Sigurd. Instrument for positioning an X-ray camera in dental X-ray photography, 4,295,050, Cl. 250-479.000.
- Linder, Ernst: See—
Maurer, Helmut; Muller, Klaus; Linder, Ernst; Rieger, Franz; and Stecher, Gunther, 4,294,679, Cl. 204-195.00S.
- Lindgren, Hakan O.; and Magnusson, Bengt, to Bulten-Kanthall Aktiebolag. Annealing oven, 4,295,033, Cl. 219-388.000.
- Lindholm, Edward P.: See—
Bronstein-Bonte, Irena Y.; Lindholm, Edward P.; and Taylor, Lloyd D., 4,294,907, Cl. 430-213.000.
- Lipowsky, Dieter; and Meyle, Karl, to Motoren- und Turbinen-Union Munchen GmbH. Process for broaching of grooves, 4,294,568, Cl. 409-244.000.
- Lipper, Karl-August: See—
Bockmann, Walter; Lipper, Karl-August; and Bruhne, Friedrich, 4,294,777, Cl. 260-544.00D.
- Little, Barry S. Oil pan adaptor for internal combustion engines, 4,294,333, Cl. 184-106.000.
- Litton Business Systems, Inc.: See—
Antonio, Christo; and Uhl, Wyman F., 4,294,888, Cl. 428-451.000.
- Liu, Chao-Min; and Westley, John, to Hoffmann-La Roche Inc. Monensin urethane derivatives produced by streptomycetes, 4,294,925, Cl. 435-84.000.
- Ljudmirsky, Ariold. Metal vapor laser, 4,295,103, Cl. 331-94.5PE.
- Lloyd, C. F.; Zalewski, Z. Leo; and Brendle, Paul C., to CTS Corporation. Electromagnetic actuator, 4,295,066, Cl. 310-30.000.
- Lo, Kun-Nan. Method of producing reinforced composite racket frame, 4,294,787, Cl. 264-46.600.
- Lockheed Electronics Co., Inc.: See—
Bigley, William J., Jr.; and Rizzo, Vincent J., 4,295,081, Cl. 318-327.000.
- Loeffler, Carolyn R., personal representative: See—
Cunningham, Richard N.; and Loeffler, Romain E., deceased, 4,294,878, Cl. 428-212.000.
- Loeffler, Romain E., deceased: See—
Cunningham, Richard N.; and Loeffler, Romain E., deceased, 4,294,878, Cl. 428-212.000.
- Logan, Maurus C., to Thomas & Betts Corporation. Optoelectronic interface apparatus, 4,294,512, Cl. 350-96.200.
- Login, Robert B.: See—
Newkirk, David D.; Login, Robert B.; and Thir, Basil, 4,294,944, Cl. 525-423.000.
- Lohmuller, Reiner; Schneider, Helmut; and Watson, Allan, to Linde AG. Methanation process, 4,294,932, Cl. 518-706.000.
- Lohrberg, Karl; Bielz, Siegfried; and Janisch, Paul, to Metallgesellschaft Aktiengesellschaft. Process of producing chlorine dioxide and, if desired, chlorine, 4,294,815, Cl. 423-478.000.
- Lohse, Friedrich: See—
Schmid, Rolf; and Lohse, Friedrich, 4,294,745, Cl. 260-37.0EP.
- Long, James M.: See—
Winiasz, Michael E.; and Long, James M., 4,294,057, Cl. 53-244.000.
- Loof, Ingemar. Spray booth, 4,294,191, Cl. 118-634.000.
- Lopes, Rosario. Mobile home anchor, 4,294,053, Cl. 52-295.000.
- Lopez, Maria B.: See—
Albers-Schonberg, George; Joshua, Henry; and Lopez, Maria B., 4,294,846, Cl. 424-279.000.
- L'Oreal: See—
Gueret, Jean-Louis, 4,294,410, Cl. 239-577.000.
- Lorenz, Heribert; and Tennigkeit, Jürgen, to Goldwell GmbH. Method of mixing cosmetic multi-component preparations and set of apparatus for the practice of the method, 4,294,293, Cl. 141-100.000.
- Losert, Herbert: See—
Kruger, Jorg; Thome, Roland; Moritz, Dieter; Bings, Hubert; and Losert, Herbert, 4,294,816, Cl. 423-484.000.
- Loucks, George R.: See—
Faler, Gary R.; and Loucks, George R., 4,294,995, Cl. 568-728.000.
- Orlando, Charles M.; and Loucks, George R., 4,294,954, Cl. 528-174.000.
- Lovell, Peter J.; and Saunders, Ian C. B., to Du Pont de Nemours, E. I., and Company. Ethylene polymers of high melt index, 4,294,794, Cl. 264-328.100.
- Lovie, Gary C.: See—
Cain, John D.; and Lovie, Gary C., 4,295,206, Cl. 364-900.000.
- Lovisolo, Francesco: See—
Bassoli, Cesare; Cornetti, Giorgio; and Lovisolo, Francesco, 4,294,210, Cl. 123-300.000.
- Lucas Industries Limited: See—
Colloff, Nicholas J., 4,294,392, Cl. 228-111.000.
- Farr, Glyn P. R., 4,294,070, Cl. 60-534.000.
- Flynn, Derek J., 4,294,072, Cl. 60-585.000.
- Gaffney, Edward N., 4,294,505, Cl. 339-231.000.
- Woodhouse, Richard G.; and Salway, Peter H., 4,295,177, Cl. 361-154.000.
- Luckert, Lothar; Pohl, Christoph; Proll, Carl-Erich; and Steffes, Paul, to Proll & Lohmann Betriebs GmbH. Device for bending and hardening bar material, 4,294,102, Cl. 72-413.000.
- Luebeck, Duane A.: See—
Snyder, Irving F.; and Luebeck, Duane A., 4,294,408, Cl. 239-218.500.

Lundquist, Burton R.; and Macherione, Thomas, to Armour and Company. Process for packaging food. 4,294,859, Cl. 426-410.000.
 Luscher, Jacob, to Ebauches S.A. Integrated frequency divider. 4,295,056, Cl. 307-221.00C.
 Luther, Walter C., Sr. Fireplace screen and shield assembly. 4,294,224, Cl. 126-135.000.
 Lutz, Sepp, to Alligator Ventilfabrik GmbH. Valve construction for tubeless tire. 4,294,301, Cl. 152-427.000.
 Lyall Electric, Inc.: See—
 Coverstone, Don A., 4,294,003, Cl. 29-611.000.
 Lyman, George F.: See—
 Pepicelli, Pasquale L.; Lyman, George F.; and Mavilia, Robert A., 4,294,924, Cl. 435-30.000.
 Lythgoe, Alan L.: See—
 Reed, Kenneth J.; and Lythgoe, Alan L., 4,294,641, Cl. 156-234.000.
 M.A.T. Industries, Inc.: See—
 Amoroso, Michael J., 4,294,317, Cl. 173-57.000.
 M & K Industries, Inc.: See—
 Krueger, Arnold F., 4,294,455, Cl. 280-11.200.
 MacCracken, Calvin D., to Calmac Manufacturing Corporation. Method and system for the compact storage of heat and coolness by phase change materials. 4,294,078, Cl. 62-59.000.
 Macerata, Diego: See—
 Lemmi, Giuliano; and Macerata, Diego, 4,294,893, Cl. 429-42.000.
 Macherione, Thomas: See—
 Lundquist, Burton R.; and Macherione, Thomas, 4,294,859, Cl. 426-410.000.
 Machi, Suet: See—
 Matsuda, Osamu; Watanabe, Terutaka; Tabata, Yoneho; and Machi, Suet, 4,294,675, Cl. 204-159.140.
 Machida, Toyotaka; and Ikemura, Yuichi, to Victor Company of Japan, Ltd. Signal generating circuit in a color television system. 4,295,157, Cl. 358-17.000.
 MacKenzie, Angus B.: See—
 Cayton, David W.; Armstrong, Errol C.; and MacKenzie, Angus B., 4,294,179, Cl. 111-3.000.
 Maeda, Miwako: See—
 Yamashita, Nobuo; and Maeda, Miwako, 4,294,511, Cl. 350-96.180.
 Maehara, Toshifumi, to Akebono Brake Industry Co., Ltd. Device for automatically adjusting a braking clearance for a disc brake. 4,294,335, Cl. 188-71.900.
 Maehata, Hidehiko: See—
 Kimoto, Yasuo; Tamiya, Katsumori; Honda, Shoichi; Maehata, Hidehiko; and Kamada, Hiroshi, 4,294,673, Cl. 204-129.460.
 Mages, Bernhard: See—
 Rock, Erich; and Mages, Bernhard, 4,294,499, Cl. 312-334.000.
 Magmate Australia Proprietary Limited: See—
 Wion, David W., 4,294,036, Cl. 46-242.000.
 Magneville, Pierre: See—
 Cholet, Jacques; Magneville, Pierre; and Cassand, Jean, 4,294,328, Cl. 181-120.000.
 Magnusson, Bengt: See—
 Lindgren, Hakan O.; and Magnusson, Bengt, 4,295,033, Cl. 219-388.000.
 Magria-Deulofeu, Jorge; and Magria-Deulofeu, Jose. Articulated figure toy. 4,294,034, Cl. 46-161.000.
 Magria-Deulofeu, Jose: See—
 Magria-Deulofeu, Jorge; and Magria-Deulofeu, Jose, 4,294,034, Cl. 46-161.000.
 Mahler, William M.: See—
 Graf, Fredy E.; Mahler, William M.; and Malan, Howard J., 4,295,051, Cl. 250-569.000.
 Maida, Osamu, to Nippon Kogaku K.K. Camera having a digital exposure value display device. 4,294,525, Cl. 354-23.00D.
 Mailund, Steinar J. Method of hauling granulates and similar material. 4,294,784, Cl. 264-14.000.
 Makar, Frank B., Jr.: See—
 Webb, Edward A.; McKenna, John F.; and Makar, Frank B., Jr., 4,295,075, Cl. 313-220.000.
 Mako, John, to International Business Machines Corporation. Bidirectional ribbon drive control for printers. 4,294,552, Cl. 400-219.100.
 Makowski, Henry S., deceased: See—
 Klein, Robert R.; and Makowski, Henry S., deceased, 4,294,744, Cl. 260-33.6AQ.
 Makowski, Patricia, executrix: See—
 Klein, Robert R.; and Makowski, Henry S., deceased, 4,294,744, Cl. 260-33.6AQ.
 Malan, Howard J.: See—
 Graf, Fredy E.; Mahler, William M.; and Malan, Howard J., 4,295,051, Cl. 250-569.000.
 Malchow, Max E., to RCA Corporation. Temperature-sensitive voltage divider. 4,295,088, Cl. 323-313.000.
 Malherbaud, Jacques: See—
 Denis, Louis H. D.; Bedue, Abel J. H.; and Malherbaud, Jacques, 4,294,311, Cl. 165-104.00S.
 Malone, Howard F., Sr.: See—
 Cleland, Marshall R.; and Malone, Howard F., Sr., 4,295,048, Cl. 250-398.000.
 Maloney, Timothy, to One Design, Inc. Thermosiphoning module for environmentally driven heating and cooling system. 4,294,229, Cl. 126-434.000.
 Mammino, Joseph, to Xerox Corporation. Inductive development materials for a magnetic development process. 4,294,904, Cl. 430-122.000.
 Manno, Joseph T. Hook-strand connecting. 4,294,031, Cl. 43-43.160.
 Mansurov, Midkhat M.: See—
 Berenov, Alexandr D.; Krainev, Vladislav P.; Mansurov, Midkhat M.; Niskovskikh, Vitaly M.; and Silin, Evgeny L., 4,294,306, Cl. 164-448.000.
 Marathon Oil Company: See—
 Young, Dick K.; and Sumner, Kenneth E., 4,294,049, Cl. 52-20.000.
 Marcelonis, Robert P.: See—
 Blanchard, Carroll H.; and Marcelonis, Robert P., 4,294,557, Cl. 400-714.000.
 Marconi Instruments Limited: See—
 Middleton, John D., 4,295,093, Cl. 324-77.00B.
 Maresca, Louis M.: See—
 Berger, Mitchell H.; Gill, Peter J.; and Maresca, Louis M., 4,294,956, Cl. 528-179.000.
 Berger, Mitchell H.; Maresca, Louis M.; and Matzner, Markus, 4,294,957, Cl. 528-179.000.
 Margulies, Herman; and Kaufman, Richard H., to Sterling Drug, Inc. Push and peel blister strip packages. 4,294,361, Cl. 206-532.000.
 Marine, Jean; and Ravetto, Michel, to Commissariat a l'Energie Atomique. Method of fabrication of electroluminescent and photodetecting diodes. 4,295,148, Cl. 357-17.000.
 Mark, Edgar, to G. L. Rexroth GmbH. Electrode-position control in arc furnaces. 4,295,000, Cl. 13-13.000.
 Marloth, Herbert: See—
 Reichl, Ernst; and Marloth, Herbert, 4,294,407, Cl. 239-102.000.
 Marquette, Russell C. Detachable protector for steel objects. 4,294,478, Cl. 293-128.000.
 Marsh, Keith D.: See—
 McCabe, Ralph P.; and Marsh, Keith D., 4,294,282, Cl. 137-595.000.
 Martech International, Inc.: See—
 Bassompierre-Sewrin, Christian C., 4,294,869, Cl. 427-177.000.
 Martenson, Kjell H., to Tetra Pak International AB. Parallelepiped packing container. 4,294,362, Cl. 206-622.000.
 Martin, Henry, to Ciba-Geigy Corporation. Oxime derivatives for protecting plant crops. 4,294,772, Cl. 260-429.700.
 Martin, Jack, to Westinghouse Electric Corp. Filament mount assembly for miniature incandescent lamp, and method of manufacture. 4,295,185, Cl. 362-211.000.
 Martin, Walter L., Jr., to PPG Industries, Inc. Bushing terminal and buss bar. 4,294,502, Cl. 339-112.00L.
 Martinelli, Lawrence G.; and Garrison, Mark R., to Verbatim Corporation. Forming process for light gauge polymer sheet material. 4,294,640, Cl. 156-213.000.
 Maruchi, Katsumi: See—
 Kashima, Isao; Mishina, Masami; Takase, Yosio; and Maruchi, Katsumi, 4,295,017, Cl. 200-47.000.
 Marvin Glass & Associates: See—
 Terzian, Rouben T., 4,294,033, Cl. 46-118.000.
 Marx, Herr J., to Trutzschler GmbH & Co. KG. Tool for opening up fiber bales. 4,293,982, Cl. 19-80.00A.
 Marzin, Claude: See—
 Beranger, Herve; Marzin, Claude; Omet, Dominique; and Peter, Jean-Luc, 4,295,210, Cl. 365-227.000.
 Marzouki, Taieb; and Schwisser, Bernd, to USM Corporation. Adhesive for double glazing units. 4,294,733, Cl. 260-28.50B.
 Maschinenfabrik Augsburg-Nurnberg Aktiengesellschaft: See—
 Urlaub, Alfred; and Chmela, Franz, 4,294,206, Cl. 123-276.000.
 Mashimo, Yukio: See—
 Iwashita, Tomonori; Fukahori, Hidehiko; and Mashimo, Yukio, 4,294,530, Cl. 354-173.000.
 Master Medical Corporation: See—
 Aslanian, Jerry L.; and Numbers, Jody L., 4,294,246, Cl. 128-214.00E.
 Matra: See—
 Broquet, Jean B., 4,294,420, Cl. 244-165.000.
 Matsuda, Osamu; Watanabe, Terutaka; Tabata, Yoneho; and Machi, Suet, to Japan Atomic Energy Research Institute. Process for production of fluorine-containing multi-component copolymers. 4,294,675, Cl. 204-159.140.
 Matsumoto, Hiroshi: See—
 Nakagawa, Taizo; Matsumoto, Hiroshi; Ohmori, Kaoru; Shimano, Shizuo; and Koike, Kengo, 4,294,835, Cl. 424-263.000.
 Matsumoto, Ken, to Eli Lilly and Company. 2-Aryl-1H-perimidines. 4,294,964, Cl. 544-249.000.
 Matsumoto, Kojiro: See—
 Minematsu, Hiroyuki; Matsumoto, Kojiro; Sacki, Tadashi; and Kishi, Akira, 4,294,946, Cl. 526-80.000.
 Matsumoto, Shigeaki: See—
 Shiraiwa, Toshio; Yamaguchi, Hisao; and Matsumoto, Shigeaki, 4,294,118, Cl. 73-620.000.
 Matsumura, Koji: See—
 Fujita, Mitsuo; and Matsumura, Koji, 4,295,080, Cl. 318-257.000.
 Matsuno, Ryohei, to Daido Giken Industries, Co., Ltd.; and Amino Aluminium Industries, Co., Ltd. Method for agitation of molten metal and furnace for agitation of molten metal. 4,294,435, Cl. 266-234.000.
 Matsuo, Kazumasa, to Olympus Optical Co., Ltd. Endoscope. 4,294,234, Cl. 128-6.000.
 Matsushima Kogo Kabushiki Kaisha: See—
 Kobayashi, Masatoshi; Shimakawa, George; Hara, Yukio; Fujii, Hiroyuki; and Kabushiki Kaisha Seikoshu, 4,293,986, Cl. 29-25.350.
 Matsushita Electric Industrial Co., Ltd.: See—
 Fukada, Tetsuji; and Ise, Yukihiko, 4,295,172, Cl. 360-109.000.
 Kawa, Hidetoshi; Mori, Kazuhiro; Misawa, Yoshihiko; and Nakagawa, Hiroshi, 4,293,998, Cl. 29-564.100.

Sugahara, Syunji; and Morimoto, Takao, 4,294,142, Cl. 81-57.370.
 Takashima, Yuji; Ishida, Eisuke; Nishiguchi, Hisanori; and Yoshino, Kimiaki, 4,294,902, Cl. 430-45.000.
 Matsushita Electric Works, Ltd.: See—
 Kashima, Isao; Mishina, Masami; Takase, Yosio; and Maruchi, Katsumi, 4,295,017, Cl. 200-47.000.
 Matta, Joseph J.; and Skalina, Andrej, to RCA Corporation. Feed system for a circularly polarized tetra-coil antenna. 4,295,144, Cl. 343-895.000.
 Mattsson, Mats E., to Svenska Kassaregister AB. Driving device for a printing carriage provided with a print head. 4,294,554, Cl. 400-320.000.
 Matusz, Zbigniew, to Fabryka Obrabiarek Precyzyjnych "Ponar-Bruszkow". Cylindrical gear with helical teeth. 4,294,132, Cl. 74-462.000.
 Matzner, Markus: See—
 Berger, Mitchell H.; Maresca, Louis M.; and Matzner, Markus, 4,294,957, Cl. 528-179.000.
 Maurer, Alexander; Adrian, Renate; Hestermann, Klaus; and Heymer, Gero, to Hoechst Aktiengesellschaft. Production of an anticorrosive pigment on phosphate basis. 4,294,621, Cl. 106-306.000.
 Maurer, Alexander: See—
 Wasel-Nielsen, Horst-Dieter; Adrian, Renate; Panter, Herbert; Heymer, Gero; Maurer, Alexander; and von Schenck, Raban, 4,294,808, Cl. 423-305.000.
 Maurer, Helmut; Muller, Klaus; Linder, Ernst; Rieger, Franz; and Stecher, Gunther, to Robert Bosch GmbH. Flat electrochemical sensor, and method of its manufacture. 4,294,679, Cl. 204-195.00S.
 Mavilia, Robert A.: See—
 Pepicelli, Pasquale L.; Lyman, George F.; and Mavilia, Robert A., 4,294,924, Cl. 435-30.000.
 May, Michael G. Externally ignited, four-cycle, piston-type internal combustion engine. 4,294,207, Cl. 123-279.000.
 Mayer, Francis X., to Exxon Research & Engineering Co. Heat transfer in magnetically stabilized, fluidized beds. 4,294,688, Cl. 208-164.000.
 Mayer, Harald; and Berentzen, Harro, to Theodor Groz & Sohne & Ernst Becker Nadelfabrik Commandit-Gesellschaft. Latch needle for knitting machines. 4,294,086, Cl. 66-121.000.
 Mayo, Kenneth E., to Energy Systems Corporation. Diver heater system. 4,294,225, Cl. 126-204.000.
 Mazique, Jeffrey C.: See—
 Fischell, David R.; and Mazique, Jeffrey C., 4,294,264, Cl. 128-778.000.
 Mazzorana, Alfred B., to Societe de Paris et du Rhone. Control lever of electrical starter. 4,294,129, Cl. 74-7.00A.
 McCabe, Ralph P.; and Marsh, Keith D., to Colt Industries Operating Corp. Apparatus and system for controlling the air-fuel ratio supplied to a combustion engine. 4,294,282, Cl. 137-595.000.
 McClaren, Sherwood W., III: See—
 Fouse, Jack A.; and McClaren, Sherwood W., III, 4,294,419, Cl. 244-117.00R.
 McDaniel, Max P., to Phillips Petroleum Company. Titanium impregnated silica-chromium catalysts. 4,294,724, Cl. 252-451.000.
 McDonald, David M.; and Scheier, Donald J., to Simon-Johnson, Inc. Poultry feed pulling apparatus. 4,293,978, Cl. 17-12.000.
 McDonnell Douglas Corporation: See—
 Boehringer, Wilfred E., 4,294,163, Cl. 92-52.000.
 McGehee, Richard S. Solid state triggering circuit. 4,295,060, Cl. 307-273.000.
 McGurk, Richard G.: See—
 Johnson, Avery R.; McGurk, Richard G.; and Harrison, John M., 4,295,008, Cl. 179-18.00C.
 McHenry, Patricia A., to Johns-Manville Corporation. Fibrous insulation mat with anti-punking binder system. 4,294,879, Cl. 428-288.000.
 McIntosh Corporation: See—
 McIntosh, Lester A., deceased, 4,294,439, Cl. 267-54.00A.
 McIntosh, Lester A., deceased (by Detroit Bank & Trust Co., executor), to McIntosh Corporation. Spring shackle. 4,294,439, Cl. 267-54.00A.
 McKenna, John F.: See—
 Webb, Edward A.; McKenna, John F.; and Makar, Frank B., Jr., 4,295,075, Cl. 313-220.000.
 McKinnie, Bonnie G., to Ethyl Corporation. Resolution of acylated D,L-alkyl substituted alkanolic acids. 4,294,775, Cl. 260-455.00R.
 McLaughlin, Robert L.: See—
 Wood, Donald C.; and McLaughlin, Robert L., 4,294,855, Cl. 424-358.000.
 McMichael, John; Kline, Ellis L.; and Spaulding, James G., to University Patents, Inc. Methods and materials for detection of multiple sclerosis. 4,294,818, Cl. 424-12.000.
 McNary, James F.: See—
 Person, Abraham; Wetmore, Sherman B.; and McNary, James F., 4,294,564, Cl. 405-195.000.
 McNeillab, Inc.: See—
 Carson, John R., 4,294,760, Cl. 260-326.470.
 McSherry, Thomas W.; and Garfield, Nathaniel H., to Mechanical Plastics Corporation. High strength anchor assembly for fastener. 4,294,156, Cl. 411-345.000.
 Mead Corporation, The: See—
 Rutledge, Wyman C.; Graves, J. Robert; and Cassill, William G., 4,294,111, Cl. 73-150.00R.
 Mead, Theodore C.: See—
 Sequeira, Avilio, Jr.; Smith, Benjamin F., Jr.; and Mead, Theodore C., 4,294,689, Cl. 208-326.000.
 Mechanical Plastics Corporation: See—
 McSherry, Thomas W.; and Garfield, Nathaniel H., 4,294,156, Cl. 411-345.000.
 Mechev, Valery V.: See—
 Vanjukov, Andrei V.; Mechev, Valery V.; Bystrov, Valentin P.; Ezhov, Evgeny I.; Vasiliev, Mikhail G.; Zaitsev, Vladimir Y.; Romenets, Vladimir A.; Ivanov, Vladimir V.; Golik, Sergei Y.; Grin-Gnatovsky, Evgeny S.; Grechko, Alexandr V.; Savin, Ivan V.; Kozhakhmetov, Sultanbek M.; Meierovich, Veniamin B.; Nagibin, Vladimir D.; Ramazanov, Nariman A.; Umarov, Almas B.; Ziberov, Valentin E.; Kunaev, Askar M.; Takezhanov, Sauk T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazheev, Dzhonson T., 4,294,433, Cl. 266-161.000.
 Mehta, Arun K.: See—
 Borio, Richard W.; and Mehta, Arun K., 4,294,178, Cl. 110-347.000.
 Meierovich, Veniamin B.: See—
 Vanjukov, Andrei V.; Mechev, Valery V.; Bystrov, Valentin P.; Ezhov, Evgeny I.; Vasiliev, Mikhail G.; Zaitsev, Vladimir Y.; Romenets, Vladimir A.; Ivanov, Vladimir V.; Golik, Sergei Y.; Grin-Gnatovsky, Evgeny S.; Grechko, Alexandr V.; Savin, Ivan V.; Kozhakhmetov, Sultanbek M.; Meierovich, Veniamin B.; Nagibin, Vladimir D.; Ramazanov, Nariman A.; Umarov, Almas B.; Ziberov, Valentin E.; Kunaev, Askar M.; Takezhanov, Sauk T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazheev, Dzhonson T., 4,294,433, Cl. 266-161.000.
 Meiji Seika Kaisha, Ltd.: See—
 Hidaka, Hidemasa; Kohno, Toshiaki; and Eida, Toshiaki, 4,294,623, Cl. 127-55.000.
 Meiners, Hans-Joachim: See—
 Grogler, Gerhard; Schwindt, Jurgen; Ganster, Otto; Meiners, Hans-Joachim; and Ruprecht, Hans-Dieter, 4,294,934, Cl. 521-160.000.
 Melarvie, Joel D. Wet suit. 4,293,957, Cl. 2-2.10R.
 Melas, Constantine M.: See—
 Fennel, John W., Jr.; Hallett, Robert J.; Head, Stanley M.; and Melas, Constantine M., 4,295,217, Cl. 370-81.000.
 Melius, Clair: See—
 Sloane, Thomas E., Jr.; Melius, Clair; and Kling, Erich, 4,294,594, Cl. 55-186.000.
 Mensch, Siegfried; Epple, Gerhard; and Elser, Wolfgang, to BASF Aktiengesellschaft. Uniformly dyed water-swellaable cellulosic fibers. 4,294,581, Cl. 8-611.000.
 Merck & Co., Inc.: See—
 Albers-Schonberg, George; Joshua, Henry; and Lopez, Maria B., 4,294,846, Cl. 424-279.000.
 Baldwin, John J.; and Ponticello, Gerald S., 4,294,969, Cl. 546-286.000.
 Monaghan, Richard L.; Alberts, Alfred W.; Hoffman, Carl H.; and Albers-Schonberg, George, 4,294,926, Cl. 435-125.000.
 Tull, Roger J.; Weinstock, Leonard M.; and Shinkai, Ichiro, 4,294,988, Cl. 564-417.000.
 Merck Patent Gesellschaft mit beschrankter Haftung: See—
 Doll, Thomas; Schacht, Erich; Radunz, Hans-Eckart; and Schulze, Ernst, 4,294,839, Cl. 424-263.000.
 Merger, Franz; and Towae, Friedrich, to BASF Aktiengesellschaft. Preparation of N-aryloxazolidine-2,4-diones. 4,294,971, Cl. 548-226.000.
 Merrill, Richard E.: See—
 Arons, Irving J.; Merrill, Richard E.; and Drennan, Arthur P., 4,294,792, Cl. 264-311.000.
 Mertzeueller nee Maillard, Anne-Marie: See—
 Schlicklin, Philippe; Mertzeueller nee Maillard, Anne-Marie; and Ploussard, Jacques, 4,294,617, Cl. 106-14.370.
 Meschnig, Albin. Lockable cap screw. 4,294,570, Cl. 411-103.000.
 Metal Box Limited: See—
 Heyes, Peter J., 4,294,627, Cl. 148-6.14R.
 Metallgesellschaft Aktiengesellschaft: See—
 Lohrberg, Karl; Bielz, Siegfried; and Janisch, Paul, 4,294,815, Cl. 423-478.000.
 Metz, Gunter; and Specker, Manfred. Aminobenzoic acid derivatives. 4,294,851, Cl. 424-311.000.
 Metzger, Karl G.: See—
 Preiss, Michael; and Metzger, Karl G., 4,294,827, Cl. 424-226.000.
 Metzger, Romain. Cycle lock arrangement. 4,294,090, Cl. 70-226.000.
 Meuleman, Lambertus J.: See—
 Khoe, Giok D.; Kock, Hendrikus G.; Meuleman, Lambertus J.; and Van Ruyven, Lodewijk J., 4,295,152, Cl. 357-74.000.
 Meyer, John H.; and Guerra, Salvatore, to Ford Motor Company. Coated glass article. 4,294,881, Cl. 428-334.000.
 Meyle, Karl: See—
 Lipowsky, Dieter; and Meyle, Karl, 4,294,568, Cl. 409-244.000.
 Michelbrink, Bernhard: See—
 Buchmuller, Horst; and Michelbrink, Bernhard, 4,294,592, Cl. 55-120.000.
 Middleton, John D., to Marconi Instruments Limited. Spectrum analyzers. 4,295,093, Cl. 324-77.00B.
 Midland-Ross Corporation: See—
 Jensen, Kenneth D., 4,294,071, Cl. 60-547.00A.
 Miersch, Ekkehard F.; and Romankiw, Lubomir T., to International Business Machines Corporation. Thin film metal package for LSI chips. 4,295,183, Cl. 361-403.000.
 Mifsud, Joseph F., to Exxon Production Research Company. Composite seismic signal. 4,295,213, Cl. 367-41.000.
 Mihalich, Stephen K.; and Wong, Thomas S. W., to National Semiconductor Corporation. CMOS Schmitt trigger and oscillator. 4,295,062, Cl. 307-279.000.
 Miles Laboratories, Inc.: See—
 Barach, Jeffrey T.; and Bluhm, Leslie, 4,294,930, Cl. 435-261.000.
 Johnson, Leighton C., 4,294,866, Cl. 427-2.000.

- Miller, Charles H.: See—
Graham, Alan A.; Haemer, Laurence F.; and Miller, Charles H., 4,294,786, Cl. 264-46.400.
- Miller, Dale E.: See—
Sternberg, Ben K.; Miller, Dale E.; and Bahjat, Dhari S., 4,295,096, Cl. 324-357.000.
- Miller, Edward C.; and Straw, David A., to Ball Corporation. Light-weight metal container. 4,294,373, Cl. 220-70.000.
- Miller, Gary L. Production counter apparatus. 4,295,037, Cl. 235-92.0PD.
- Miller, Kenneth L. Dispenser for and method of dispensing a material from a non-pressurized material reservoir. 4,294,381, Cl. 222-1.000.
- Miller, Ronald J. Tool and method for holding automotive valves closed during servicing. 4,294,141, Cl. 81-3.00R.
- Miller, William J.: See—
Kruger, Robert; and Miller, William J., 4,294,228, Cl. 126-430.000.
- Milliken Research Corporation: See—
Su, Tien-Kuei, 4,294,747, Cl. 260-37.00R.
- Minami, Kentaro, to Japan Atomic Energy Research Institute. Background compensation type plutonium air monitor. 4,295,045, Cl. 250-255.000.
- Minematsu, Hiroyuki; Matsumoto, Kojiro; Saeki, Tadashi; and Kishi, Akira, to Sumitomo Naugatuck Co., Ltd. Low residual monomer α -methylstyrene-acrylonitrile copolymers and ABS blends therefrom. 4,294,946, Cl. 526-80.000.
- Minnesota Mining and Manufacturing Company: See—
Thill, Gary A., 4,294,240, Cl. 128-156.000.
- Minolta Camera Kabushiki Kaisha: See—
Ohta, Yoshiharu; and Naya, Mikio, 4,294,528, Cl. 354-33.000.
- Minorikawa, Hitoshi: See—
Takahashi, Minoru; Tanigami, Takahiko; Uchiyama, Kaoru; Minorikawa, Hitoshi; Nishihara, Motohisa; Kawakami, Kanji; Suzuki, Seiko; Hachino, Hiroaki; and Misawa, Yutaka, 4,295,115, Cl. 338-4.000.
- Minoura, Mikio: See—
Sumiyoshi, Masaharu; Sekiya, Setsuro; Motosugi, Katsuhiko; Uozumi, Junzo; Ando, Tsuneo; Takeuchi, Yuzo; and Minoura, Mikio, 4,294,213, Cl. 123-454.000.
- Misawa, Yoshihiko: See—
Kawa, Hidetoshi; Mori, Kazuhiro; Misawa, Yoshihiko; and Nakagawa, Hiroshi, 4,293,998, Cl. 29-564.100.
- Misawa, Yutaka: See—
Takahashi, Minoru; Tanigami, Takahiko; Uchiyama, Kaoru; Minorikawa, Hitoshi; Nishihara, Motohisa; Kawakami, Kanji; Suzuki, Seiko; Hachino, Hiroaki; and Misawa, Yutaka, 4,295,115, Cl. 338-4.000.
- Mishina, Masami: See—
Kashima, Isao; Mishina, Masami; Takase, Yosio; and Maruchi, Katsumi, 4,295,017, Cl. 200-47.000.
- Mitani, Akio; Sakamoto, Moriyoichi; and Murasaki, Hiroaki, to Tokyo Shibaura Denki Kabushiki Kaisha. Freezing refrigerator. 4,294,081, Cl. 62-140.000.
- Mitani, Yoriyasu: See—
Kubota, Michio; Takagi, Kazuhiro; and Mitani, Yoriyasu, 4,294,632, Cl. 148-142.000.
- Mitsubishi Denki Kabushiki Kaisha: See—
Fujiwara, Ichiro; Motoki, Yoshiaki; Inoue, Toshinori; and Fukuoka, Kazuma, 4,295,015, Cl. 200-38.00R.
- Morishita, Mitsuharu; and Iwaki, Yoshiyuki, 4,295,087, Cl. 322-99.000.
- Uesaka, Tatsuo; Sugahara, Hiroshi; and Fujimura, Takeo, 4,295,110, Cl. 335-212.000.
- Yamada, Yoshito; Okumura, Hiroshi; and Murakami, Shoji, 4,295,112, Cl. 336-84.00M.
- Mitsubishi Jukogyo Kabushiki Kaisha: See—
Ifuku, Yasushi; Uchiyama, Hirofumi; and Hayashi, Masayuki, 4,294,561, Cl. 426-475.000.
- Mitsubishi Petrochemical Co., Ltd.: See—
Hashimoto, Fukashi, 4,294,889, Cl. 428-515.000.
- Kihara, Kunio; Toda, Hideo; Yasukawa, Eiki; Ishibashi, Toshiaki; and Tokita, Taketoshi, 4,294,933, Cl. 521-27.000.
- Mitsuhashi, Yasuhiro, to Nippon Gakki Seizo Kabushiki Kaisha. Method of synthesizing musical tones. 4,294,153, Cl. 84-1.010.
- Mitsui-Nisso Corporation: See—
Sugita, Toshio; Sakaguchi, Hiroaki; Tsuda, Hisanobu; and Suzuki, Tsuyoshi, 4,294,951, Cl. 528-55.000.
- Mitsui Petrochemical Industries Ltd.: See—
Toyota, Akinori; Yoshitugu, Ken; and Kashiwa, Norio, 4,294,948, Cl. 526-125.000.
- Miura, Shuichi: See—
Koga, Kenichiro; Hirose, Yoshiharu; Kanno, Iwao; Uemura, Kazuo; and Miura, Shuichi, 4,295,047, Cl. 250-363.00S.
- Miyagishima, Tosh; Puntar, Joseph; and Wiegand, Raymond, to Hydriil Company. Inside blowout preventer well tool. 4,294,314, Cl. 166-318.000.
- Miyahara, Masayoshi: See—
Kisaka, Hiroyuki; Sagata, Makoto; Miyahara, Masayoshi; and Katayama, Morimitsu, 4,294,130, Cl. 74-15.400.
- Miyake, Shunji: See—
Kodera, Yuji; Ikari, Kyoichiro; and Miyake, Shunji, 4,294,935, Cl. 525-60.000.
- Miyamoto, Tomohiko: See—
Uchida, Seiichi; Satomi, Yoshihito; Kiuchi, Norihiro; Yamagata, Takeo; Yoshioka, Susumu; Miyamoto, Tomohiko; and Tomuro, Jinichi, 4,294,803, Cl. 422-111.000.
- Miyano, Shizuo: See—
Okishi, Yoshio; Koike, Akinobu; and Miyano, Shizuo, 4,294,905, Cl. 430-175.000.
- Miyata, Teruo. Collagen skin dressing. 4,294,241, Cl. 128-156.000.
- Miyawaki, Syozo: See—
Ariyama, Kenzo; Miyawaki, Syozo; and Murakami, Takashi, 4,294,535, Cl. 355-14.0SH.
- Mizuguchi, Ryuzo; Ishikura, Sinichi; Ishii, Keizou; and Yoshioka, Tamotu, to Nippon Paint Co., Ltd. Process for preparing acrylic resin emulsions. 4,294,740, Cl. 260-29.6RB.
- Mo och Domsjo Aktiebolag: See—
Lindahl, Jonas A. I.; and Rudstrom, Lars G., 4,294,653, Cl. 162-25.000.
- Moertel, George B., to Textron, Inc. Sliding method and apparatus. 4,293,994, Cl. 29-409.000.
- Monaghan, Richard L.; Alberts, Alfred W.; Hoffman, Carl H.; and Albers-Schonberg, George, to Merck & Co., Inc. Hypocholesteremic fermentation products and process of preparation. 4,294,926, Cl. 435-125.000.
- Monier, Jean-Claude: See—
Thominet, Michel; Acher, Jacques; and Monier, Jean-Claude, 4,294,828, Cl. 424-232.000.
- Monsanto Company: See—
Bach, Hartwig C.; and Hinderer, Helmut E., 4,294,884, Cl. 428-364.000.
- Knowles, William S.; and Sabacky, Milton J., 4,294,989, Cl. 568-13.000.
- Kowalski, Xavier, 4,294,575, Cl. 8-111.000.
- Newman, Randolph E., 4,294,652, Cl. 159-2.00R.
- Monzheimer, Rolf; and Pfeleiderer, Ernst, to Rohm GmbH. Enzymatic method for hair recovery with concurrent opening of hide structure. 4,294,087, Cl. 69-21.000.
- Montague, Albert. Bi-loop heat recovery system for an oil fired furnace. 4,294,223, Cl. 126-112.000.
- Montedison S.p.A.: See—
Cecchin, Giuliano; and Albizzati, Enrico, 4,294,721, Cl. 252-429.00B.
- Montefiore Hospital Association of Western Pennsylvania, The: See—
Yao, Shang J.; Sun Yao, Hui Y.; and Wolfson, Sidney K., Jr., 4,294,891, Cl. 429-2.000.
- Mookherjee, Braja D.; Wilson, Richard A.; Schmitt, Frederick L.; and Vock, Manfred H., to International Flavors & Fragrances Inc. Flavoring with mixture of nor-methyl jasmonate and dihydro-nor-methyl jasmonate. 4,294,863, Cl. 426-538.000.
- Mookil, Byun. Method for manufacturing a solid statue. 4,294,634, Cl. 156-59.000.
- Mooney, Donald B.: See—
Balyoz, John; Chang, Chi S.; Fox, Barry C.; Palmieri, John A.; Ghafghaichi, Majid; Jen, Teh-Sen; and Mooney, Donald B., 4,295,149, Cl. 357-45.000.
- Moore, Eugene L.: See—
Davenport, Robert W.; Moore, Eugene L.; and Goodman, Ronald L., 4,294,042, Cl. 51-54.000.
- Moore, Gerald L., to Useldinger, Ronald E. Friction type exercising device with improved friction setting indicator. 4,294,446, Cl. 272-133.000.
- Moore, Ronald D.; and Hall, John W., to United States of America, Navy. Closed torque test machine. 4,294,112, Cl. 73-162.000.
- Moraw, Roland; and Schädlich, Renate, to Hoechst Aktiengesellschaft. Information carriers, method of forming and copying said carriers. 4,294,913, Cl. 430-396.000.
- Moreau, Marc: See—
Szyszkowski, Adam; Moreau, Marc; and Priester, Pierre, 4,294,629, Cl. 148-11.50C.
- Morelock, Charles R.: See—
Laskow, William; and Morelock, Charles R., 4,294,788, Cl. 264-101.000.
- Morgan, George W., to Suncor Inc. Cutter configuration for efficient ice disaggregation and clearing. 4,294,183, Cl. 114-42.000.
- Morgan, Thomas R.: See—
Ernsting, John; Morgan, Thomas R.; Palmer, Leonard F. W.; Rivers, Alfred J.; and Robson, Stephen M., 4,294,243, Cl. 128-201.180.
- Mori, Kazuhiro: See—
Kawa, Hidetoshi; Mori, Kazuhiro; Misawa, Yoshihiko; and Nakagawa, Hiroshi, 4,293,998, Cl. 29-564.100.
- Mori, Keiji; and Kurimoto, Kyoichi, to Aisin Seiki Kabushiki Kaisha; and Toyota Jidosha Kogyo Kabushiki Kaisha. Actuating handle means. 4,294,134, Cl. 74-547.000.
- Mori, Mamoru: See—
Kinaga, Eiichi; and Mori, Mamoru, 4,294,468, Cl. 280-807.000.
- Morimoto, Takao: See—
Sugahara, Syunji; and Morimoto, Takao, 4,294,142, Cl. 81-57.370.
- Morishita, Mitsuharu; and Iwaki, Yoshiyuki, to Mitsubishi Denki Kabushiki Kaisha. Charge indicator circuit for a battery charging system. 4,295,087, Cl. 322-99.000.
- Moritz, Dieter: See—
Kruger, Jorg; Thome, Roland; Moritz, Dieter; Bings, Hubert; and Losert, Herbert, 4,294,816, Cl. 423-484.000.
- Morris Whaley, Inc.: See—
Whaley, Morris L., 4,294,495, Cl. 308-174.000.
- Mosse, Barbara; and Thompson, John P., to National Research Development Corporation. Production of mycorrhizal fungi. 4,294,037, Cl. 47-59.000.
- Moto, Masato; and Ito, Seigo, to Futaba Denshi Kogyo K.K. Pulse width modulated servo circuit. 4,295,082, Cl. 318-599.000.

- Motoki, Yoshiaki: See—
Fujiwara, Ichiro; Motoki, Yoshiaki; Inoue, Toshinori; and Fukuoka, Kazuma, 4,295,015, Cl. 200-38.00R.
- Motomuro, Hisanao: See—
Hara, Haruichi; Kanzaki, Toshihide; Motomuro, Hisanao; and Adachi, Akiyoshi, 4,294,723, Cl. 252-440.000.
- Motor Wheel Corporation: See—
Woelfel, James A., 4,294,490, Cl. 301-63.0PW.
- Woelfel, James A.; and Smith, Richard W., 4,294,639, Cl. 156-185.000.
- Motoren- und Turbinen-Union Munchen GmbH: See—
Lipowsky, Dieter; and Meyle, Karl, 4,294,568, Cl. 409-244.000.
- Motorola Inc.: See—
Price, John J., Jr., 4,295,063, Cl. 307-362.000.
- Motosugi, Katsuhiko: See—
Sumiyoshi, Masaharu; Sekiya, Setsuro; Motosugi, Katsuhiko; Uozumi, Junzo; Ando, Tsuneo; Takeuchi, Yuzo; and Minoura, Mikio, 4,294,213, Cl. 123-454.000.
- Moule, Rex E. Self-surfaced meat product manufacturing method and apparatus. 4,294,858, Cl. 426-241.000.
- Moyse, James A.: See—
Anderson, Norman; Peak, Richard; and Moyse, James A., 4,294,709, Cl. 252-8.800.
- Mukaida, Yutaka: See—
Takita, Hitoshi; Mukaida, Yutaka; and Enomoto, Satoru, 4,294,770, Cl. 260-413.000.
- Mukoyama, Yoshiyuki; and Sakata, Touichi, to Hitachi Chemical Company, Ltd. Polyamide-imide resin and its production. 4,294,952, Cl. 528-67.000.
- Mullenberg, Ralph. Polygon connection of a hub with a shaft. 4,294,562, Cl. 403-383.000.
- Muller, Klaus: See—
Maurer, Helmut; Muller, Klaus; Linder, Ernst; Rieger, Franz; and Stecher, Gunther, 4,294,679, Cl. 204-195.00S.
- Muller, Rolf, to Robert Bosch GmbH. Method and system to optimize recording conditions in magnetic recording systems. 4,295,168, Cl. 360-66.000.
- Munters Corporation: See—
Tennyson, Richard P., 4,294,663, Cl. 201-39.000.
- Murai, Asao: See—
Takahara, Yoshiyuki; Hirose, Yoshiteru; Takeuchi, Yoko; Murai, Asao; Kainosho, Masatsune; and Murao, Sawao, 4,294,754, Cl. 260-112.50R.
- Murakami, Masanori: See—
Kircher, Charles J.; Huang, Hung-Chang W.; and Murakami, Masanori, 4,295,147, Cl. 357-5.000.
- Murakami, Shoji: See—
Yamada, Yoshito; Okumura, Hiroshi; and Murakami, Shoji, 4,295,112, Cl. 336-84.00M.
- Murakami, Takashi: See—
Ariyama, Kenzo; Miyawaki, Syozo; and Murakami, Takashi, 4,294,535, Cl. 355-14.0SH.
- Murao, Sawao: See—
Takahara, Yoshiyuki; Hirose, Yoshiteru; Takeuchi, Yoko; Murai, Asao; Kainosho, Masatsune; and Murao, Sawao, 4,294,754, Cl. 260-112.50R.
- Murasaki, Hiroaki: See—
Mitani, Akio; Sakamoto, Moriyoichi; and Murasaki, Hiroaki, 4,294,081, Cl. 62-140.000.
- Murata Manufacturing Co., Ltd.: See—
Ieki, Hideharu, 4,295,108, Cl. 333-193.000.
- Murayama, Naohiro: See—
Sakagami, Teruo; Kato, Tadaaki; Hirai, Toru; and Murayama, Naohiro, 4,294,677, Cl. 204-181.00F.
- Murayama, Yoshinobu, to Kubota, Ltd. Tractor travelling system transmission mechanism. 4,294,131, Cl. 74-15.400.
- Murez, James D., to GM Research. Portable computer enclosure. 4,294,496, Cl. 312-208.000.
- Murphy, Preston V., to Lectret S.A. Plural piezoelectric polymer film acoustic transducer. 4,295,010, Cl. 179-110.00A.
- Murthy, Rajam R., to Koomey, Inc. Accumulator with float orienting means. 4,294,288, Cl. 138-30.000.
- Naaktgeboren, Adrianus: See—
Decoene, Frans J. G. C.; Hommez, Etienne R. O. C.; and Naaktgeboren, Adrianus, 4,294,346, Cl. 198-740.000.
- Nab, Joseph J. Sole for logging boot. 4,294,024, Cl. 36-113.000.
- Nagai, Tsuneji: See—
Suzuki, Yoshiki; Ikura, Hiroshi; Yamashita, Gentaro; and Nagai, Tsuneji, 4,294,829, Cl. 424-241.000.
- Nagao, Tsukasa. Optical circulators. 4,294,509, Cl. 350-96.150.
- Nagase, Hiroshi; Okuyama, Toshiaki; Kubota, Yuzuru; and Suzuki, Katsunori, to Hitachi, Ltd. Control apparatus of synchronous motor having thyristor converter. 4,295,084, Cl. 318-719.000.
- Nagibin, Vladimir D.: See—
Vanjukov, Andrei V.; Mechev, Valery V.; Bystrov, Valentin P.; Ezhov, Evgeny I.; Vasiliev, Mikhail G.; Zaitsev, Vladimir Y.; Romanets, Vladimir A.; Ivanov, Vladimir V.; Golik, Sergei Y.; Grin-Gnatovsky, Evgeny S.; Grechko, Alexandr V.; Savin, Ivan V.; Kozhakhmetov, Sultanbek M.; Meierovich, Veniamin B.; Nagibin, Vladimir D.; Ramazanov, Nariman A.; Umarov, Almas B.; Ziberov, Valentin E.; Kunaev, Askar M.; Takezhanov, Saik T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazheev, Dzhonson T., 4,294,433, Cl. 266-161.000.
- Nagy, Janos: See—
Knoll, Jozsef; Kalasz, Huba; Knoll, Berta; and Nagy, Janos, 4,294,825, Cl. 424-101.000.
- Naito, Kenji: See—
Iiyama, Masahiko; Sanka, Tsugio; and Naito, Kenji, 4,294,205, Cl. 123-274.000.
- Nakagawa, Hiroshi: See—
Kawa, Hidetoshi; Mori, Kazuhiro; Misawa, Yoshihiko; and Nakagawa, Hiroshi, 4,293,998, Cl. 29-564.100.
- Nakagawa, Tadashi, to Seiko Koki Kabushiki Kaisha. Automatic focusing camera combined with manual focusing system. 4,294,526, Cl. 354-25.000.
- Nakagawa, Tadashi, to Seiko Koki Kabushiki Kaisha. Shutter blade device for focal plane shutter. 4,294,532, Cl. 354-246.000.
- Nakagawa, Taizo; Matsumoto, Hiroshi; Ohmori, Kaoru; Shimano, Shizuo; and Koike, Kengo, to Nippon Kayaku Kabushiki Kaisha. 2-Hydroxy benzamide derivatives and use thereof as a fungicide. 4,294,835, Cl. 424-263.000.
- Nakahara, Akihiko: See—
Onoue, Yasuharu; Sata, Toshikatsu; Nakahara, Akihiko; and Itoh, Junichi, 4,294,943, Cl. 525-358.000.
- Nakai, Masaaki: See—
Takemoto, Iwao; Koike, Norio; Ohba, Shinya; Ando, Haruhisa; Nakai, Masaaki; Hanamura, Syoji; Izawa, Ryuichi; Kubo, Masaharu; Aoki, Masakazu; and Tanaka, Shuhei, 4,295,055, Cl. 307-221.00C.
- Nakai, Osamu: See—
Okada, Yoshitsugu; and Nakai, Osamu, 4,294,428, Cl. 251-214.000.
- Nakai, Syunji; and Nakao, Motokazu, to Sharp Kabushiki Kaisha. Liquid electrostatic image developing system employs mesh development electrode. 4,294,192, Cl. 118-650.000.
- Nakajima, Yukio: See—
Hashimoto, Akihiko; Nakajima, Yukio; Koiwai, Tamotsu; and Kimura, Toyohiko, 4,294,527, Cl. 354-25.000.
- Nakamura, Yoshiharu, to Nissan Motor Company, Limited. Car body. 4,294,487, Cl. 296-188.000.
- Nakane, Masao: See—
Shinoda, Akibumi; and Nakane, Masao, 4,294,334, Cl. 188-18.00A.
- Nakao, Motokazu: See—
Nakai, Syunji; and Nakao, Motokazu, 4,294,192, Cl. 118-650.000.
- Nakatsuji, Tadao: See—
Abe, Kazunobu; Tamura, Shoichi; and Nakatsuji, Tadao, 4,294,806, Cl. 423-239.000.
- Nakauchi, Hiroshi; Koyanagi, Katubumi; Inami, Yasuhiko; and Ueda, Hisashi, to Sharp Corporation. Combined constant potential and constant voltage driving technique for electrochromic displays. 4,295,138, Cl. 340-785.000.
- Naoki, Takashi: See—
Yamaguchi, Jun; Naoki, Takashi; Sera, Hidefumi; Ishigaki, Kunio; and Ogawa, Masasi, 4,294,921, Cl. 430-621.000.
- Narten, Nathaniel C.: See—
Greenwald, A. Seth; Geiger, Jack M.; Narten, Nathaniel C.; Porritt, Derek S.; Combs, Steven P.; and Brems, John J., 4,294,251, Cl. 128-276.000.
- Nash, Patrick L. Connecting device. 4,294,476, Cl. 285-189.000.
- Naslund, Jan I. Method for processing a body liquid specimen. 4,294,582, Cl. 23-230.00B.
- National Instrument Company, Inc.: See—
Bennett, Richard N., 4,294,294, Cl. 141-179.000.
- National Research Development Corporation: See—
Heap, Robert B., 4,294,922, Cl. 435-7.000.
- Mosse, Barbara; and Thompson, John P., 4,294,037, Cl. 47-59.000.
- National Semiconductor Corporation: See—
Mihalich, Stephen K.; and Wong, Thomas S. W., 4,295,062, Cl. 307-279.000.
- Roybal, Philip M., 4,295,124, Cl. 340-347.0DD.
- Nauheimer, James F.; and Benzschawel, Steven J., to Container Corporation of America. Package for video tubes. 4,294,358, Cl. 206-419.000.
- Naya, Mikio: See—
Ohta, Yoshiharu; and Naya, Mikio, 4,294,528, Cl. 354-33.000.
- Nayar, Harbhajan S., to Airco, Inc. Brazing process. 4,294,395, Cl. 228-220.000.
- Naylor, Arthur V.; and Spencer, John K., to Baker Perkins Holdings Limited. Sweet forming and wrapping machine. 4,294,060, Cl. 53-506.000.
- NCR Canada Ltd.-NCR Canada Ltee: See—
Cain, John D.; and Lovie, Gary C., 4,295,206, Cl. 364-900.000.
- Nedschroef Octrooi Maatschappij N.V.: See—
Bouwman, Johannes E., 4,294,300, Cl. 411-185.000.
- Neeff, Rutger: See—
Krock, Friedrich W.; and Neeff, Rutger, 4,294,578, Cl. 8-516.000.
- Krock, Friedrich W.; Neeff, Rutger; and Scheiter, Heinz, 4,294,769, Cl. 260-378.000.
- Neff, Joseph J., to Cummins Engine Company, Inc. Integral turbine housing and exhaust collector section. 4,294,073, Cl. 60-597.000.
- Neiman, David C.: See—
Kreinbrink, Paul H.; and Neiman, David C., 4,295,038, Cl. 235-92.0PK.
- Nelson, David E.; and Bouyoucos, John V., to Hydroacoustics Inc. Optical sensor system. 4,294,513, Cl. 350-96.290.
- Nelvig, Lars T.: See—
Bohlin, Karl G.; Fredriksson, Borje I.; Karlsson, Kent A. B.; and Nelvig, Lars T., 4,294,412, Cl. 241-30.000.
- Neumiller, Phillip J., to S. C. Johnson & Son, Inc. Odor absorbing compositions. 4,294,821, Cl. 424-45.000.
- Newkirk, David D.; Login, Robert B.; and Thir, Basil, to BASF Wyandotte Corporation. Flame retardant antistatic additives and antistatic fibers. 4,294,944, Cl. 525-423.000.

Newman, Randolph E., to Monsanto Company. Falling strand devolatilizer. 4,294,652, Cl. 159-2.00R.

NGK Insulators, Ltd.: See—
Haga, Toshikatsu; Fukuda, Hiroyuki; Shinoda, Hiroshi; and Hayakawa, Hideharu, 4,294,795, Cl. 264-332.000.

Nicholson, James A. Support bracket and open shelving assembly. 4,294,177, Cl. 108-42.000.

Nicks, Peter F., to Imperial Chemical Industries Limited. Production of coating films from autoxidizable materials and coating compositions capable of producing such films. 4,294,887, Cl. 428-423.100.

Nims, Philip A.; and Bollinger, Roger K., to Crompton & Knowles Corporation. Shuttle retaining apparatus. 4,294,291, Cl. 139-438.000.

Nippon Clean Engine Laboratory Co.: See—
Onishi, Shigeru, 4,294,372, Cl. 220-20.000.

Nippon Electric Co., Ltd.: See—
Tokoda, Saburo; Okumura, Koichiro; and Sugimoto, Eiji, 4,295,061, Cl. 307-279.000.

Nippon Gakki Seizo Kabushiki Kaisha: See—
Mitsunashi, Yasuhiro, 4,294,153, Cl. 84-1.010.

Nippon Kayaku Kabushiki Kaisha: See—
Nakagawa, Taizo; Matsumoto, Hiroshi; Ohmori, Kaoru; Shimano, Shizuo; and Koike, Kengo, 4,294,835, Cl. 424-263.000.

Nippon Kogaku K.K.: See—
Maida, Osamu, 4,294,525, Cl. 354-23.00D.

Nippon Kokan Kabushiki Kaisha: See—
Okado, Masaru; and Ariizumi, Takashi, 4,294,094, Cl. 72-16.000.

Sawada, Hajimu; and Inubushi, Hisao, 4,294,437, Cl. 266-272.000.

Nippon Mining Co., Ltd.: See—
Uchida, Seiichi; Satomi, Yoshihito; Kiuchi, Norihiro; Yamagata, Takeo; Yoshioka, Susumu; Miyamoto, Tomohiko; and Tomuro, Jinichi, 4,294,803, Cl. 422-111.000.

Nippon Paint Co., Ltd.: See—
Mizuguchi, Ryuzo; Ishikura, Sinichi; Ishii, Keizou; and Yoshioka, Tamoto, 4,294,740, Cl. 260-29.6RB.

Yamamoto, Takashi; and Amako, Hiroshi, 4,294,667, Cl. 204-1.00T.

Nippon Rotary Nozzle Co., Ltd.: See—
Sawada, Hajimu; and Inubushi, Hisao, 4,294,437, Cl. 266-272.000.

Nippon Shokubai Kagaku Kogyo Co. Ltd.: See—
Hara, Haruichi; Kanzaki, Toshihide; Motomuro, Hisanao; and Adachi, Akiyoshi, 4,294,723, Cl. 252-440.000.

Nippon Soken, Inc.: See—
Segawa, Yoshihiro; Ohta, Minoru; and Yasuda, Eturo, 4,294,801, Cl. 422-98.000.

Nippon Steel Corporation: See—
Kawano, Tsuyoshi; Usuda, Matsuo; and Hirokawa, Toshio, 4,294,095, Cl. 72-51.000.

Nippon Telegraph, Telephone Public Corp.: See—
Hata, Hidetoh; Haji, Katsumi; Sako, Kazushige; Shibata, Yoji; and Achiha, Masahiko, 4,295,154, Cl. 358-4.000.

Nishida, Masazo, to Toyo Rubber Industry Co., Ltd., The. Foamed polyurethane articles with skin and a method for producing the same. 4,294,880, Cl. 428-315.000.

Nishiguchi, Hisanori: See—
Takashima, Yuji; Ishida, Eisuke; Nishiguchi, Hisanori; and Yoshino, Kimiaki, 4,294,902, Cl. 430-45.000.

Nishihara, Motohisa: See—
Takahashi, Minoru; Tanigami, Takahiko; Uchiyama, Kaoru; Minorikawa, Hitoshi; Nishihara, Motohisa; Kawakami, Kanji; Suzuki, Seiko; Hachino, Hiroaki; and Misawa, Yutaka, 4,295,115, Cl. 338-4.000.

Nishimura, Yoshinori; Umeda, Kaoru; and Harada, Hideo, to Sony Corporation. Tuning indicator apparatus for a frequency synthesizer tuner. 4,295,224, Cl. 455-156.000.

Nishiyama, Yoshihisa, to Tokyo Electric Co., Ltd. Electronic weight measuring device. 4,294,322, Cl. 177-210.00R.

Niskovskikh, Vitaly M.: See—
Berenov, Alexandr D.; Krainev, Vladislav P.; Mansurov, Midkhat M.; Niskovskikh, Vitaly M.; and Silin, Evgeny L., 4,294,306, Cl. 164-448.000.

Nissan Motor Company, Limited: See—
Abo, Toshimi; and Hosaka, Akio, 4,294,216, Cl. 123-489.000.

Ideta, Yasufumi; Takeda, George; and Watanabe, Shoei, 4,294,160, Cl. 91-378.000.

Iwanaga, Kazuyoshi; Sugano, Kazuhiko; and Ohtsuka, Kunio, 4,294,140, Cl. 74-868.000.

Nakamura, Yoshiharu, 4,294,487, Cl. 296-188.000.

Shimizu, Kazuaki, 4,294,336, Cl. 188-72.400.

Yasuhara, Seishi; and Ohnishi, Eiichi, 4,294,220, Cl. 123-568.000.

Nissen, Nico; Op Het Veld, Sebastianus J.; and Schneider, Henri W., to U.S. Philips Corporation. Digital frequency divider. 4,295,158, Cl. 358-17.000.

Nisshin Steel Co., Ltd.: See—
Kubota, Michio; Takagi, Kazuhiro; and Mitani, Yorimasa, 4,294,632, Cl. 148-142.000.

Noda, Teruaki: See—
Watanabe, Yasuaki; and Noda, Teruaki, 4,295,165, Cl. 358-193.100.

Nomura, Yoshihiko, to Aisin Seiki Kabushiki Kaisha. Power assisted steering system for vehicles. 4,294,325, Cl. 180-148.000.

Noranda Mines Limited: See—
LeRoy, Rodney L., 4,294,274, Cl. 137-7.000.

Norbedo, Robert A.; and Resnick, Martin L., to GTE Laboratories Incorporated. Signalling system including apparatus for generating and testing data and command words within first and second message intervals. 4,295,208, Cl. 364-900.000.

Nordson Corporation: See—
Hastings, Donald R.; and Harjar, Martin J., 4,294,411, Cl. 239-707.000.

Nordstrom, Immo R.; and Bak, Johannes A. System for securing containers in a ship's hold. 4,294,185, Cl. 114-75.000.

Norman, Melvin H.: See—
Sheehan, Neil J.; and Norman, Melvin H., 4,294,249, Cl. 128-214.00G.

Norprint Limited: See—
Figg, Anthony V. J.; and Cunningham, Harry, 4,294,645, Cl. 156-384.000.

Norris, Jerry L.: See—
Schmidt, Gary D.; Norris, Jerry L.; and Weirauch, Donald F., 4,295,102, Cl. 331-65.000.

Northern Telecom Limited: See—
Read, Clifford D., 4,295,179, Cl. 361-331.000.

Nouda, Hiroshi; Tanihara, Yoshiaki; Ikeda, Takashi; and Ogiuchi, Ituo, to Teijin Limited. Process for producing thermoplastic resin film of markedly reduced thickness unevenness. 4,294,791, Cl. 264-210.200.

Nuclear Power Company Limited: See—
Seed, Geoffrey; Chesworth, Graham; Hind, John R.; and Hodgson, Donald, 4,294,661, Cl. 376-363.000.

Numbers, Jody L.: See—
Aslanian, Jerry L.; and Numbers, Jody L., 4,294,246, Cl. 128-214.00E.

Nystrom, William A.; Lanzel, Leo C.; and Bauer, William A., to Stackpole Corporation. The. Replaceable liner for a crucible. 4,294,438, Cl. 266-280.000.

Nyul, Paul; and Hughes, Frederick R., to RCA Corporation. Method of bonding two parts together and article produced thereby. 4,295,151, Cl. 357-68.000.

Oakley, John F.: See—
Bratt, Martin D.; and Oakley, John F., 4,294,533, Cl. 354-318.000.

O'Banion, Michael L.; and Veara, Jack R. Apparatus for supporting a work piece. 4,294,441, Cl. 269-97.000.

Obata, Toshiharu; Hagyu, Toshimasa; and Kojima, Hisao, to Fuji Electric Co., Ltd. Method for manufacturing brazed parts. 4,294,396, Cl. 228-245.000.

Obergfell, Allen R., to Duo-Fast Corporation. Fastener driving tool. 4,294,391, Cl. 227-130.000.

Occidental Oil Shale, Inc.: See—
Kilburn, James S., 4,294,563, Cl. 405-132.000.

Occidental Research Corporation: See—
Schep, Raymond A., 4,294,977, Cl. 562-407.000.

O'Connor, James M.; and Goodrich, George W., to Bendix Corporation. The. Dual mode light valve display. 4,294,518, Cl. 350-357.000.

Oda, Kazutaka: See—
Ohba, Hisao; Oda, Kazutaka; Yabuta, Yukio; and Ohashi, Azusa, 4,294,672, Cl. 204-129.400.

Oda, Kenichi, to Kawasaki Steel Corporation. Roll gap measuring device for continuous casting machine. 4,294,305, Cl. 164-150.000.

Odekirk, William H. Gutter hanger. 4,294,422, Cl. 248-48.200.

Oerlikon-Buhrle U.S.A. Inc.: See—
Sarcia, Domenico S., 4,294,077, Cl. 62-6.000.

Sarcia, Domenico S.; and Lam, Calvin K., 4,294,600, Cl. 62-6.000.

Oeser, Heinz-Guenter: See—
Koenig, Karl-Heinz; Feuerherd, Karl-Heinz; and Oeser, Heinz-Guenter, 4,294,773, Cl. 260-453.00P.

Ogawa, Masasi: See—
Yamaguchi, Jun; Naoi, Takashi; Sera, Hidefumi; Ishigaki, Kunio; and Ogawa, Masasi, 4,294,921, Cl. 430-621.000.

Ogihara, Masuo: See—
Kitai, Kiyoshi; Ogihara, Masuo; and Chimura, Kozo, 4,295,215, Cl. 368-196.000.

Ogiuchi, Ituo: See—
Nouda, Hiroshi; Tanihara, Yoshiaki; Ikeda, Takashi; and Ogiuchi, Ituo, 4,294,791, Cl. 264-210.200.

Ognevsky, Viktor A.: See—
Egorov, Viktor P.; Ognevsky, Viktor A.; Orlovsky, Anatoly G.; Ostrovsky, Grigory A.; Ryskind, Alexandr M.; Stepin, Anatoly L.; Trofimov, Oleg F.; and Shklyarov, Isaak N., 4,294,098, Cl. 72-128.000.

Ogrinc, Joseph F.: See—
Van Deusen, George S.; and Ogrinc, Joseph F., 4,293,983, Cl. 19-127.000.

Ohashi, Azusa: See—
Ohba, Hisao; Oda, Kazutaka; Yabuta, Yukio; and Ohashi, Azusa, 4,294,672, Cl. 204-129.400.

Ohashi, Yasuo: See—
Yamamura, Keizo; and Ohashi, Yasuo, 4,294,116, Cl. 73-362.0AR.

Ohba, Hisao; Oda, Kazutaka; Yabuta, Yukio; and Ohashi, Azusa, to Fuji Photo Film Co., Ltd. Method for preparing a support for a lithographic printing plate. 4,294,672, Cl. 204-129.400.

Ohba, Shinya: See—
Takemoto, Iwao; Koike, Norio; Ohba, Shinya; Ando, Haruhisa; Nakai, Masaaki; Hanamura, Syoji; Izawa, Ryuichi; Kubo, Masaharu; Aoki, Masakazu; and Tanaka, Shuhei, 4,295,055, Cl. 307-221.00C.

Ohlinger, Rainer: See—
Astheimer, Hans J.; Brandstaedter, Horst; Ohlinger, Rainer; Van Pee, Willy; Van Steen, Jaak; Sauer, Friedrich; Schmidt, Rudolf; and Krueger, Siegfried, 4,294,666, Cl. 203-72.000.

Ohls, James W., to Corning Glass Works. Method of coating optical waveguide filaments and coating die. 4,294,190, Cl. 118-620.000.

Ohmori, Kaoru: See—
Nakagawa, Taizo; Matsumoto, Hiroshi; Ohmori, Kaoru; Shimano, Shizuo; and Koike, Kengo, 4,294,835, Cl. 424-263.000.

Ohmura, Sohshi, to Fujitsu Limited. Method of surface-treating semiconductor substrate. 4,294,651, Cl. 156-662.000.

Ohnishi, Eiichi: See—
Yasuhara, Seishi; and Ohnishi, Eiichi, 4,294,220, Cl. 123-568.000.

Ohno, Kazunori: See—
Doi, Yoshikazu; Sakai, Yutaka; and Ohno, Kazunori, 4,294,521, Cl. 350-426.000.

Ohta, Minoru: See—
Segawa, Yoshihiro; Ohta, Minoru; and Yasuda, Eturo, 4,294,801, Cl. 422-98.000.

Ohta, Yoshiharu; and Naya, Mikio, to Minolta Camera Kabushiki Kaisha. Automatically controlled electronic flash device. 4,294,528, Cl. 354-33.000.

Ohtake, Yukio, to Hitachi, Ltd. Oscillation type flying shear. 4,294,146, Cl. 83-316.000.

Ohtsuka, Kunio: See—
Iwanaga, Kazuyoshi; Sugano, Kazuhiko; and Ohtsuka, Kunio, 4,294,140, Cl. 74-868.000.

Ohumi, Takeharu, to Aisin Seiki Kabushiki Kaisha; and Toyota Jidosha Kogyo Kabushiki Kaisha. Electromagnetically operable fluid flow control valve mechanism. 4,294,286, Cl. 137-625.480.

Ohyachi, Tomio; and Irako, Koichi, to Bridgestone Tire Company Limited. Rubber mounting compositions. 4,294,732, Cl. 260-27.0BB.

Oida, Yoshio: See—
Zushi, Sadao; and Oida, Yoshio, 4,295,027, Cl. 219-10.55B.

Oikawa, Teruo: See—
Taga, Genji; Oikawa, Teruo; and Watanabe, Yoshiaki, 4,294,810, Cl. 423-331.000.

Okada, Takanori: See—
Hayashi, Masaki; Iguchi, Sadahiko; Okada, Takanori; and Kawasaki, Akiyoshi, 4,294,849, Cl. 424-305.000.

Okada, Yoshitsugu; and Nakai, Osamu, to Kubota, Ltd. Butterfly valve. 4,294,428, Cl. 251-214.000.

Okado, Masaru; and Ariizumi, Takashi, to Nippon Kokan Kabushiki Kaisha. Method for automatically controlling width of slab during hot rough-rolling thereof. 4,294,094, Cl. 72-16.000.

Okamura, Okiyoshi, to Koa Oil Company, Limited. Apparatus for and method of detecting and measuring corrosion damage in pipe. 4,295,092, Cl. 324-61.00R.

Okishi, Yoshio; Koike, Akinobu; and Miyano, Shizuo, to Fuji Photo Film Co., Ltd. Light-sensitive lithographic printing plate and compositions therefore with multiple resins. 4,294,905, Cl. 430-175.000.

Okubo, Shigeki: See—
Kanai, Isamu; Okubo, Shigeki; Tsuchiya, Kazuo; and Takasaki, Toshio, 4,294,475, Cl. 285-165.000.

Okumura, Hiroshi: See—
Yamada, Yoshito; Okumura, Hiroshi; and Murakami, Shoji, 4,295,112, Cl. 336-84.00M.

Okumura, Koichiro: See—
Tokoda, Saburo; Okumura, Koichiro; and Sugimoto, Eiji, 4,295,061, Cl. 307-279.000.

Okuyama, Toshiaki: See—
Nagase, Hiroshi; Okuyama, Toshiaki; Kubota, Yuzuru; and Suzuki, Katsunori, 4,295,084, Cl. 318-719.000.

Oler, Newell B. Game apparatus. 4,294,448, Cl. 273-94.000.

Oler, Robert A., to General Electric Company. Recovery of ammonia from aqueous streams. 4,294,812, Cl. 423-357.000.

Olin, C. Howard, to Bloomfield Farms, Inc. Apparatus for cutting and splitting firewood. 4,294,295, Cl. 144-3.00K.

Olin Corporation: See—
Capuano, Italo A.; Turley, Patricia A.; and DuBord, Edward W., 4,294,798, Cl. 422-62.000.

Evvard, Thomas O., 4,294,604, Cl. 71-27.000.

Knollmueller, Karl O.; Fairbrother, Robert J.; and Gavin, David F., 4,294,713, Cl. 252-28.000.

Olschewski, Armin; Brandenstein, Manfred; Walter, Lothar; Ernst, Horst M.; and Schulz, Toni, to SKF Kugellagerfabriken GmbH. Method of manufacturing a seamless outer sleeve for a ball bearing. 4,294,100, Cl. 72-340.000.

Olson, Walter A.: See—
Hedley, Victor H.; and Olson, Walter A., 4,294,316, Cl. 172-20.000.

Olsson, Lars J., to Saab-Scania AB. Apparatus for measuring and orienting logs for sawing. 4,294,149, Cl. 83-435.100.

Olympia Radiological Associates: See—
Veatch, William M., 4,294,260, Cl. 128-654.000.

Olympia Werke AG: See—
Rix, Albert, 4,294,556, Cl. 400-643.000.

Olympus Optical Company, Ltd.: See—
Hashimoto, Akihiko; Nakajima, Yukio; Koiwai, Tamotsu; and Kimura, Toyohiko, 4,294,527, Cl. 354-25.000.

Hattori, Nobuo, 4,294,506, Cl. 350-6.800.

Matsuo, Kazumasa, 4,294,234, Cl. 128-6.000.

Yamashita, Nobuo; and Maeda, Miwako, 4,294,511, Cl. 350-96.180.

Omet, Dominique: See—
Beranger, Herve; Marzin, Claude; Omet, Dominique; and Peter, Jean-Luc, 4,295,210, Cl. 365-227.000.

Omron Tateisi Electronics Co.: See—
Yamamura, Keizo; and Ohashi, Yasuo, 4,294,116, Cl. 73-362.0AR.

Onda, Hirotosuga, to Onda Ironworks Company, Limited. Carpenter planer. 4,294,296, Cl. 144-120.000.

Onda Ironworks Company, Limited: See—
Onda, Hirotosuga, 4,294,296, Cl. 144-120.000.

One Design, Inc.: See—
Maloney, Timothy, 4,294,229, Cl. 126-434.000.

Onishi, Shigeru, to Nippon Clean Engine Laboratory Co. Small-sized container capable of mixing more than two components at a predetermined mixing ratio. 4,294,372, Cl. 220-20.000.

Onoue, Yasuharu; Sata, Toshikatsu; Nakahara, Akihiko; and Itoh, Junichi, to Tokuyama Soda Kabushiki Kaisha. Process for preparing fluorine-containing polymers having carboxyl groups. 4,294,943, Cl. 525-358.000.

Op Het Veld, Sebastianus J.: See—
Nissen, Nico; Op Het Veld, Sebastianus J.; and Schneider, Henri W., 4,295,158, Cl. 358-17.000.

Opalka, Chester J., Jr.: See—
Leshner, George Y.; Opalka, Chester J., Jr.; and Page, Donald F., 4,294,837, Cl. 424-263.000.

Oram, Nora L.: See—
Oram, W. Wayne; Oram, Nora L.; and Boris, Robert W., 4,294,239, Cl. 128-96.000.

Oram, W. Wayne; Oram, Nora L.; and Boris, Robert W. Steady support abdominal splint. 4,294,239, Cl. 128-96.000.

Ord, Thomas M. Pivotal deck ramp. 4,293,967, Cl. 9-1.600.

Orlando, Charles M.; and Loucks, George R., to General Electric Company. Polycarbonate copolymers. 4,294,954, Cl. 528-174.000.

Orlovsky, Anatoly G.: See—
Egorov, Viktor P.; Ognevsky, Viktor A.; Orlovsky, Anatoly G.; Ostrovsky, Grigory A.; Ryskind, Alexandr M.; Stepin, Anatoly L.; Trofimov, Oleg F.; and Shklyarov, Isaak N., 4,294,098, Cl. 72-128.000.

Orzalesi, Giovanni: See—
Innocenti, Franco; Orzalesi, Giovanni; and Volpato, Ivo, 4,294,833, Cl. 424-263.000.

Osaka Gas Company, Limited: See—
Kakihara, Naomichi; Harada, Yoshiaki; and Uedono, Norio, 4,294,706, Cl. 210-762.000.

Oshima, Takao: See—
Hino, Minoru; Oshima, Takao; Hayatsu, Kazuo; Yamamoto, Michio; and Yasui, Seimei, 4,294,940, Cl. 525-124.000.

Ostrovsky, Grigory A.: See—
Egorov, Viktor P.; Ognevsky, Viktor A.; Orlovsky, Anatoly G.; Ostrovsky, Grigory A.; Ryskind, Alexandr M.; Stepin, Anatoly L.; Trofimov, Oleg F.; and Shklyarov, Isaak N., 4,294,098, Cl. 72-128.000.

Otis Engineering Corporation: See—
Schwegman, Harry E., deceased, 4,294,313, Cl. 166-117.500.

Yonker, John H.; Fisher, Ernest P., Jr.; and Bills, David, 4,294,315, Cl. 166-322.000.

Otsuka, Chikao; Hara, Reinosuke; and Shigenaka, Yoshito, to Asahi Breweries Ltd. Container having rimmed shrink cap. 4,294,367, Cl. 215-246.000.

Otsuka, Kenichi; and Hosokawa, Yorio, to Tokyo Shibaura Denki Kabushiki Kaisha. Lamp circuit with disconnected lamp detecting device. 4,295,079, Cl. 315-130.000.

Otte, Otto M., Jr. Impact cutting tool. 4,294,298, Cl. 144-193.00C.

Outboard Marine Corporation: See—
DuBois, Chester G.; and Hulsebus, Richard P., 4,294,780, Cl. 261-39.00B.

Owen, Gwilym E., Jr., to Owens-Corning Fiberglass Corporation. Compatible low shrink resin systems. 4,294,941, Cl. 525-170.000.

Owens-Corning Fiberglass Corporation: See—
Beckman, John T., 4,294,416, Cl. 242-18.00G.

Owen, Gwilym E., Jr., 4,294,941, Cl. 525-170.000.

Owens-Illinois, Inc.: See—
Ames, Geoffrey C., 4,294,374, Cl. 220-71.000.

Berkel, Michael R., 4,294,359, Cl. 206-422.000.

Chang, Long F., 4,294,366, Cl. 215-1.00C.

Oztekin, Muammer A.; and Albano, Vincent J., to Kent Corporation. The. Merchandise shelving display. 4,294,363, Cl. 211-49.00D.

Pachonik, Horst: See—
Behn, Reinhard; Heywang, Hermann; and Pachonik, Horst, 4,294,194, Cl. 118-719.000.

Page, Donald F.: See—
Leshner, George Y.; Opalka, Chester J., Jr.; and Page, Donald F., 4,294,837, Cl. 424-263.000.

Pakhomov, Evgeny P.: See—
Asinovskiy, Erik I.; Afanasiev, Anatoly A.; Pakhomov, Evgeny P.; Zeigarnik, Vladimir A.; and Yartsev, Ivan M., 4,295,021, Cl. 200-147.00R.

Pako Corporation: See—
Laska, Ronald C.; and Pone, Janis, 4,294,537, Cl. 355-35.000.

Palmaer, Tore G. Headgear. 4,293,960, Cl. 2-416.000.

Palmer, Leonard F. W.: See—
Ernsting, John; Morgan, Thomas R.; Palmer, Leonard F. W.; Rivers, Alfred J.; and Robson, Stephen M., 4,294,243, Cl. 128-201.180.

Palmieri, John A.: See—
Balyoz, John; Chang, Chi S.; Fox, Barry C.; Palmieri, John A.; Ghafghaichi, Majid; Jen, Teh-Sen; and Mooney, Donald B., 4,295,149, Cl. 357-45.000.

Pan, Hsi-Lung: See—
Wetzel, William H.; Pan, Hsi-Lung; Goodwin, Robert J.; and Wilkinson, John E., 4,294,996, Cl. 568-776.000.

Pan, Jing-Jong, to Harris Corporation. Fiber optic repeater. 4,295,225, Cl. 455-601.000.

- Panter, Herbert: See—
Wasel-Nielsen, Horst-Dieter; Adrian, Renate; Panter, Herbert; Heymer, Gero; Maurer, Alexander; and von Schenck, Raban, 4,294,808, Cl. 423-305.000.
- Papenfuchs, Theodor; and Teige, Wolfgang, to Hoechst Aktiengesellschaft. Process for the coloration of thermoplastic polymers and polycondensates in the mass with water-insoluble disazo-methine compounds. 4,294,749, Cl. 260-40.00P.
- Parks-Cramer Company: See—
Lane, John E., 4,294,065, Cl. 57-265.000.
Lane, John E., 4,294,066, Cl. 57-265.000.
- Paschall, Edwin L.: See—
Ammons, Sharon E.; Paschall, Edwin L.; and Carter, Morris G., 4,294,403, Cl. 236-13.000.
- Pasternack, Adalbert, to Dragerwerk Aktiengesellschaft. Respirator with a cooling device. 4,294,244, Cl. 128-202.260.
- Patenaude, Raymond A.; Cozzy, Thomas W.; and Bullis, Stephen J., to General Electric Company. Gun bolt control mechanism. 4,294,158, Cl. 89-12.000.
- Patent-Treuhand-Gesellschaft für elektrische Glühlampen m.b.H.: See—
Eckhardt, Fritz; and Schönherr, Walter, 4,295,076, Cl. 313-223.000.
- Pattison, Jack E. Internal fluid communication system for power cylinders. 4,294,572, Cl. 414-641.000.
- Patton, Tad L., to Exxon Research & Engineering Co. Process of casting polyparabanic acid films from stabilized organic amide solvents. 4,294,785, Cl. 264-41.000.
- Patzlaff, Albert W., to Blueberry Equipment, Inc. Hydrodynamic blueberry sorting. 4,294,691, Cl. 209-3.100.
- Paulsen, Ralf; Sontheim, Max; and Ullmann, Christoph. Vacuum packaging machine. 4,294,056, Cl. 53-86.000.
- Paust, Joachim: See—
Schmidt, Wolfram; and Paust, Joachim, 4,294,766, Cl. 260-343.600.
- Paxton, Kenneth B., to Eastman Kodak Company. Automatic control of copier copy contrast and density for production runs. 4,294,536, Cl. 355-14.00C.
- PDA Engineering: See—
Schutzler, Jerome C., 4,294,559, Cl. 403-28.000.
- Peak, Richard: See—
Anderson, Norman; Peak, Richard; and Moyse, James A., 4,294,709, Cl. 252-8.800.
- Pearl, David R., to Gerber Garment Technology, Inc. Method of sharpening lateral edges and end edges of a blade during reciprocation thereof. 4,294,047, Cl. 51-327.000.
- Pearl, Douglas B., to Uniweld Products, Incorporated. Gas cylinder carrier. 4,294,481, Cl. 294-146.000.
- Peffer, Robert M.; and Braun, Charles H., to Eastman Kodak Company. Friction drive force measurement fixture. 4,294,104, Cl. 73-9.000.
- Pegler, Stewart M.: See—
Thomas, Richard C.; Pegler, Stewart M.; and Cordes, Paul B., 4,295,095, Cl. 324-326.000.
- Pelsue, Henry F. Piston type crossbow. 4,294,222, Cl. 124-25.000.
- Pemco-Kalamazoo, Inc.: See—
Black, John W., 4,294,491, Cl. 301-63.0DD.
- Penn Virginia Corporation: See—
Klingaman, Richard M.; and Ehrenreich, Leo C., 4,294,750, Cl. 260-40.00R.
- Pentabloc, Ltd.: See—
Chapman, Arthur J.; and Hayes, Geoffrey M. G., 4,294,561, Cl. 403-219.000.
- Pepicelli, Pasquale L.; Lyman, George F.; and Mavilia, Robert A., to Data Packaging Corporation. Method and container for growth of anaerobic microorganisms. 4,294,924, Cl. 435-30.000.
- Pepsico, Inc.: See—
Rensner, Jürgen G., 4,294,058, Cl. 53-413.000.
- Pere, Gerard, to Creusot-Loire. Electrolysis unit. 4,294,683, Cl. 204-258.000.
- Performance Industries, Inc.: See—
Boyesen, Eyvind, 4,294,202, Cl. 123-73.0PP.
- Perlow, Stewart M., to RCA Corporation. Impedance transformation network. 4,295,107, Cl. 333-25.000.
- Permacel: See—
Korpmann, Ralf, 4,294,936, Cl. 525-93.000.
- Person, Abraham; Wetmore, Sherman B.; and McNary, James F., to Global Marine Inc. Method of deployment, release and recovery of ocean riser pipes. 4,294,564, Cl. 405-195.000.
- Persson, Erik: See—
Bjorklund, Anders; Persson, Erik; and Virsberg, Lars-Goran, 4,295,113, Cl. 336-84.00M.
- Pervel Industries, Inc.: See—
Bernard, Leo N., 4,294,577, Cl. 8-488.000.
- Peter, Jean-Luc: See—
Beranger, Herve; Marzin, Claude; Omet, Dominique; and Peter, Jean-Luc, 4,295,210, Cl. 365-227.000.
- Peters, Lester L.; and Black, John W., to Cummins Engine Company, Inc. Test apparatus for hydraulic valve. 4,294,109, Cl. 73-119.00A.
- Peters, Thomas E.: See—
Kim, Han J.; Peters, Thomas E.; and Gustafson, John, 4,294,616, Cl. 75-234.000.
- Petersen, Uwe: See—
Voss, Eckart; Petersen, Uwe; and Stadler, Peter, 4,294,959, Cl. 536-17.00R.
- Peterson, Charles A.; and Grove, Louis C., Jr., to Westinghouse Electric Corp. Multi-series group capacitor bank protection equipment. 4,295,174, Cl. 361-16.000.
- Peterson, Glenn S.: See—
Plant, Howard L.; and Peterson, Glenn S., 4,294,970, Cl. 546-294.000.
- Petrie, Harold L.: See—
Erickson, John W.; and Petrie, Harold L., 4,294,573, Cl. 417-83.000.
- Petroff, Peter D. Infiltration-inflow sewer line analyzer. 4,295,197, Cl. 364-510.000.
- Pevnick, Stephen H. Program controllable free falling water drop fountain. 4,294,406, Cl. 239-20.000.
- Pfeffer, Henry A., III: See—
Bagnall, Elizabeth A.; Guiliano, Basil A.; and Pfeffer, Henry A., III, 4,294,962, Cl. 544-192.000.
- Pfeffer, John R., to Consolidated Fiberglass Products Company. Method and apparatus for forming fiberglass mats. 4,294,655, Cl. 162-107.000.
- Pfleiderer, Ernst: See—
Monsheimer, Rolf; and Pfeiderer, Ernst, 4,294,087, Cl. 69-21.000.
- Pfohl, Sigberg: See—
Hartmann, Jürgen; Stedefeder, Joachim; Denzinger, Walter; and Pfohl, Sigberg, 4,294,873, Cl. 427-391.000.
- Pharmindustrie: See—
Champseix, Alain A.; and Le Fur, Gerard R., 4,294,841, Cl. 424-267.000.
- Philip Morris Incorporated: See—
Kassman, Allen J.; and Geiszler, Willard A., Jr., 4,294,265, Cl. 131-366.000.
- Phillips Petroleum Company: See—
Burns, Lyle D., 4,294,587, Cl. 44-74.000.
Cheng, Paul J., 4,294,814, Cl. 423-457.000.
Furr, Danny L., 4,295,196, Cl. 364-501.000.
McDaniel, Max P., 4,294,724, Cl. 252-451.000.
- Philpott, William J. M.: See—
Andrews, William J.; Espley, David J. C.; and Philpott, William J. M., 4,294,882, Cl. 428-349.000.
- Pickles, Joseph, to Ferro Manufacturing Corporation. Recliner and inertia latch. 4,294,488, Cl. 297-367.000.
- Picunko, Thomas; Kramer, Henry H.; Dam, Naim G.; and Gray, Robert I., to Bios Inc. Method and apparatus for characterizing blood flow through the heart. 4,294,259, Cl. 128-653.000.
- Pietralla, Norbert; Ausserbauer, Valentin; and Rosenthal, Christian. Method for the production of metal soaps. 4,294,771, Cl. 260-413.000.
- Pinaire, Ronald; and Everett, Gary L., to Atlantic Richfield Company. Lubricating oil process. 4,294,687, Cl. 208-58.000.
- Piret, Jean; and Jallas, Michel, to Regie Nationale Des Usines Renault. Transmission with variator. 4,294,137, Cl. 74-665.00G.
- Pittasch, Willi; and Dalbert, Johannes, to Richard Heinze, Firma. Cabinet hinge. 4,293,976, Cl. 16-129.000.
- Plant, Howard L.; and Peterson, Glenn S., to Uniroyal, Inc. Oxidation of alpha-alkylated, benzyl-substituted 2-thiopyridine 1-oxides. 4,294,970, Cl. 546-294.000.
- Pletka, Hans-Dieter: See—
Bozon, Alfred; Koberstein, Edgar; Pletka, Hans-Dieter; Volker, Herbert; and Lakatos, Eduard, 4,294,726, Cl. 252-462.000.
- Ploussard, Jacques: See—
Schlicklin, Philippe; Mertzweiler nee Maillard, Anne-Marie; and Ploussard, Jacques, 4,294,617, Cl. 106-14.370.
- Pohl, Christoph: See—
Luckert, Lothar; Pohl, Christoph; Proll, Carl-Erich; and Steffes, Paul, 4,294,102, Cl. 72-413.000.
- Pohl, Walter, to Eaton Corporation. Thermo-switch. 4,295,114, Cl. 337-3.000.
- Polaroid Corporation: See—
Bronstein-Bonte, Irena Y.; Lindholm, Edward P.; and Taylor, Lloyd D., 4,294,907, Cl. 430-213.000.
Idelson, Elbert M., 4,294,915, Cl. 430-441.000.
Shenk, Edwin K., 4,294,531, Cl. 354-195.000.
- Poliak, Richard M.: See—
Bakos, Peter; Darrow, Russell E.; Funari, Joseph; and Poliak, Richard M., 4,294,729, Cl. 252-545.000.
- Politechnika Gdanska: See—
Falkowski, Leonard; Stefanska, Barbara; Zielinski, Jan; Troka, Elzbieta; Golik, Jerzy; Kolodziejczyk, Pawel; Jarzebski, Andrzej; Cybulska, Emilia; and Borowski, Edward, 4,294,958, Cl. 536-17.00R.
- Polizzotti, David M.; and Steelhammer, Joe C., to Betz Laboratories, Inc. Electrostatic precipitator efficiency enhancement. 4,294,588, Cl. 55-5.000.
- Pollack, Frank J., to Western Electric Company, Inc. Methods of manufacturing and securing tubular wire-retaining anchors to circuit boards. 4,294,008, Cl. 29-831.000.
- Pollination Technics, Inc.: See—
Weiderrich, LeRoy J., 4,293,966, Cl. 6-12.00R.
- Pollock, Stephen F., to Hudson Pulp & Paper Corp. Method of making embossing roll for producing paper towels. 4,293,990, Cl. 29-148.40D.
- Pomares, Francis. Handle attaching means for brooms and the like. 4,293,972, Cl. 15-145.000.
- Pomerene, James H., to International Business Machines Corporation. Machine for multiple instruction execution. 4,295,193, Cl. 364-200.000.
- Pone, Janis: See—
Laska, Ronald C.; and Pone, Janis, 4,294,537, Cl. 355-35.000.
- Ponkala, Jorma, to Vaisala Oy. Electronic selector switch particularly for use in radiosondes. 4,295,090, Cl. 324-60.0CD.
- Ponkala, Jorma, to Vaisala Oy. Circuit for measuring low capacitances. 4,295,091, Cl. 324-60.0CD.

- Ponticello, Gerald S.: See—
Baldwin, John J.; and Ponticello, Gerald S., 4,294,969, Cl. 546-286.000.
- Porcella, Brewster J., to Sperry Rand Corporation. Row address memory map overlap. 4,295,192, Cl. 364-200.000.
- Porritt, Derek S.: See—
Greenwald, A. Seth; Geiger, Jack M.; Narten, Nathaniel C.; Porritt, Derek S.; Combs, Steven P.; and Brems, John J., 4,294,251, Cl. 128-276.000.
- Postenreider, Erwin: See—
Diermayer, Werner; Kutzner, Luitpold; and Postenreider, Erwin, 4,294,401, Cl. 236-1.00G.
- Postle, Stephen R.; and Psaila, Alexander, to Ciba-Geigy AG. Photographic silver halide material containing a dye filter or a dye antihalation layer. 4,294,916, Cl. 430-522.000.
- Postle, Stephen R.; and Psaila, Alexander, to Ciba-Geigy AG. Photographic silver halide material containing a dye filter or a dye antihalation layer. 4,294,917, Cl. 430-522.000.
- PPG Industries, Inc.: See—
Bosso, Joseph F., 4,294,741, Cl. 260-29.6NR.
Howe, Mark J., 4,294,874, Cl. 427-393.000.
Martin, Walter L., Jr., 4,294,502, Cl. 339-112.00L.
Rinehart, Jay K., 4,294,764, Cl. 260-340.90R.
- Prather, Richard A.; and Shah, Nirad N., to Upjohn Company, The. Process for preparing methylene dianilines. 4,294,987, Cl. 564-331.000.
- Preco Inc.: See—
Lewis, Alfred E.; and Salisbury, Robert E., 4,294,569, Cl. 410-133.000.
- Prefectural Economic Federation of Agricultural Co-operatives: See—
Ifuku, Yasushi; Uchiyama, Hirofumi; and Hayashi, Masayuki, 4,294,861, Cl. 426-475.000.
- Preiss, Michael; and Metzger, Karl G., to Bayer Aktiengesellschaft. Antibacterial and growth promoting β -lactam antibiotics carrying an γ -lactone-2-pyrrolidinone-1-yl radical. 4,294,827, Cl. 424-226.000.
- Presley, Molly: See—
Hyman, Dennis C., 4,294,466, Cl. 280-772.000.
- Price, John J., Jr., to Motorola Inc. Fast settling digital to analog converter bit switch. 4,295,063, Cl. 307-362.000.
- Priester, Pierre: See—
Szyzkowski, Adam; Moreau, Marc; and Priester, Pierre, 4,294,629, Cl. 148-11.50C.
- Procter & Gamble Company, The: See—
Hardy, Frederick E.; and Dewar, Colin A., 4,294,710, Cl. 252-8.800.
- Hardy, Frederick E.; and Stoddart, Barry, 4,294,711, Cl. 252-8.750.
- Proll, Carl-Erich: See—
Luckert, Lothar; Pohl, Christoph; Proll, Carl-Erich; and Steffes, Paul, 4,294,102, Cl. 72-413.000.
- Proll & Lohmann Betriebs GmbH: See—
Luckert, Lothar; Pohl, Christoph; Proll, Carl-Erich; and Steffes, Paul, 4,294,102, Cl. 72-413.000.
- Propyllox (Societe Anonyme): See—
Hardy, Nicolas; and Dancot, Georges, 4,294,776, Cl. 260-502.00R.
- Prunbauer, Kurt, to Evva Werk Spezialerzeugung von Zylinder- und Sicherheitsschloßern Gesellschaft m.b.H. & Co. Kommanditgesellschaft. Control device for cylinder locks. 4,294,091, Cl. 70-276.000.
- Psaila, Alexander: See—
Postle, Stephen R.; and Psaila, Alexander, 4,294,916, Cl. 430-522.000.
Postle, Stephen R.; and Psaila, Alexander, 4,294,917, Cl. 430-522.000.
- Puntar, Joseph: See—
Miyagishima, Tosh; Puntar, Joseph; and Wieveg, Raymond, 4,294,314, Cl. 166-318.000.
- Pust, Waldo H. Grain drill with device for preventing undesired back-filling of front furrow by rear furrow openers. 4,294,180, Cl. 111-52.000.
- Quaker Oats Company, The: See—
Breneman, Jack L., 4,294,032, Cl. 46-1.00R.
- Quang, Pham K.: See—
Kings, Donald; and Quang, Pham K., 4,294,903, Cl. 430-98.000.
- Quinn, Clayton B.; and Hilakos, William, to General Electric Company. Process for preparing a branched polycarbonate. 4,294,953, Cl. 528-128.000.
- Quintin, Rene; and Villemant, Claude M., to Le Material Telephonique. Method of manufacturing a hybrid integrated circuit. 4,294,009, Cl. 29-832.000.
- Quist, William E.: See—
Hyatt, Michael V.; and Quist, William E., 4,294,625, Cl. 148-2.000.
- Rabinovich, Evsey, to Emco Wheaton Inc. Safety hatch cover apparatus. 4,294,378, Cl. 220-323.000.
- Racal-Vadic, Inc.: See—
Bingham, John A. C., 4,295,105, Cl. 332-9.00R.
- Racine, Pierre. Liquid dispensing receptacle. 4,294,369, Cl. 215-311.000.
- Radunz, Hans-Eckart: See—
Doll, Thomas; Schacht, Erich; Radunz, Hans-Eckart; and Schulze, Ernst, 4,294,839, Cl. 424-263.000.
- Ragland, Frank R., Jr., to RCA Corporation. Mercury arc lamp having communicating mercury reservoir. 4,295,074, Cl. 313-174.000.
- Ralston Purina Company: See—
Fuller, Mary L., 4,294,857, Cl. 426-99.000.
- Ramazanov, Nariman A.: See—
Vanjukov, Andrei V.; Mechev, Valery V.; Bystrov, Valentin P.; Ezhov, Evgeny I.; Vasilev, Mikhail G.; Zaitsev, Vladimir Y.; Romenets, Vladimir A.; Ivanov, Vladimir V.; Golik, Sergei Y.; Grin-Gnatovsky, Evgeny S.; Grechko, Alexandr V.; Savin, Ivan V.; Kozhakhmetov, Sultanbek M.; Meierovich, Veniamin B.; Nagibin, Vladimir D.; Ramazanov, Nariman A.; Umarov, Almas B.; Ziberov, Valentin E.; Kunaev, Askar M.; Takezhanov, Saik T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazhev, Dzhonson T., 4,294,433, Cl. 266-161.000.
- Randolph, Alan D., to Electric Power Research Institute, Inc.; and Arizona Board of Regents, The University of Arizona, The. System for removing solids from a used lime or limestone slurry scrubbing liquor in flue gas desulfurization. 4,294,807, Cl. 423-242.000.
- Rankin, Kenneth F., to Chubb Integrated Systems Limited. Teller machines and methods of operation thereof. 4,294,380, Cl. 221-195.000.
- Ranks Hovis McDougall Limited: See—
Solomons, Gerald L.; and Scammell, Gerald W., 4,294,929, Cl. 435-254.000.
- Rasmussen, Ole-Bendt. Circular extrusion method providing for rotation around the extrusion opening. 4,294,638, Cl. 156-176.000.
- Rauschert, Willi; Rieger, Gerald; Bock, Erich; and Eckel, Alfred, to Diehl GmbH & Co. Projectile with recoverable detonator. 4,294,172, Cl. 102-473.000.
- Rausser, Horst, to Licentia Patent-Verwaltungs GmbH. Circuit for improving picture quality in a television receiver. 4,295,164, Cl. 358-166.000.
- Ravetto, Michel: See—
Marine, Jean; and Ravetto, Michel, 4,295,148, Cl. 357-17.000.
- Raymond, Louis W. Precision electroplating of metal objects. 4,294,670, Cl. 204-26.000.
- RCA Corporation: See—
Carter, Don R.; Doner, Claude E.; Hammersand, Fred G.; and Tomcavage, Joseph R., 4,295,077, Cl. 313-293.000.
Crowley, Albert T., 4,295,098, Cl. 328-24.000.
Hettiger, James, 4,295,161, Cl. 358-34.000.
Hettiger, James, 4,295,163, Cl. 358-165.000.
Hsieh, Peter K.; and Vaccarella, Richard M., 4,295,065, Cl. 307-475.000.
Lagoni, William A., 4,295,160, Cl. 358-31.000.
Leidich, Arthur J., 4,295,101, Cl. 330-262.000.
Malchow, Max E., 4,295,088, Cl. 323-313.000.
Matta, Joseph J.; and Skalina, Andrej, 4,295,144, Cl. 343-895.000.
Nyul, Paul; and Hughes, Frederick R., 4,295,151, Cl. 357-68.000.
Perlow, Stewart M., 4,295,107, Cl. 333-25.000.
Ragland, Frank R., Jr., 4,295,074, Cl. 313-174.000.
Shanley, Robert L., II; and Hettiger, James, 4,295,166, Cl. 358-243.000.
- Truesdell, Raymond L.; and Ross, Michael D., 4,295,216, Cl. 369-55.000.
- Wilmarth, Paul C., 4,295,078, Cl. 315-8.000.
- Wittlinger, Harold A.; and Salerno, Carmine P., 4,294,321, Cl. 177-210.0FP.
- Read, Clifford D., to Northern Telecom Limited. Electric test equipment housing. 4,295,179, Cl. 361-331.000.
- Ready, Delbert L. Scaffold with gear drive. 4,294,332, Cl. 182-141.000.
- Reddinger, Donald M.: See—
Lincoln, Howard P.; and Reddinger, Donald M., 4,294,669, Cl. 204-15.000.
Lincoln, Howard P.; and Reddinger, Donald M., 4,294,680, Cl. 204-224.00R.
Lincoln, Howard P.; and Reddinger, Donald M., 4,294,681, Cl. 204-224.00R.
Lincoln, Howard P.; and Reddinger, Donald M., 4,294,789, Cl. 264-102.000.
- Redhead, Walden K. Insertable article for altering the cure rate and chemical composition of an object. 4,294,168, Cl. 99-494.000.
- Reed Irrigation Systems Pty Ltd.: See—
Tucker, Alfred D., 4,294,470, Cl. 285-5.000.
- Reed, Kenneth J.; and Lythgoe, Alan L. Heat transfer sheets. 4,294,641, Cl. 156-234.000.
- Regie Nationale Des Usines Renault: See—
Piret, Jean; and Jallas, Michel, 4,294,137, Cl. 74-665.00G.
- Reh, Walter, to Bayerische Motoren Werke Aktiengesellschaft. Friction clutch for motor vehicles. 4,294,343, Cl. 192-113.00A.
- Rehm, William A. Drilling mud degasser apparatus and system. 4,294,593, Cl. 55-166.000.
- Reichhold Chemicals, Incorporated: See—
Wetzel, William H.; Pan, Hsi-Lung; Goodwin, Robert J.; and Wilkinson, John E., 4,294,996, Cl. 568-776.000.
- Reichl, Ernst; and Marloth, Herbert, to Bosch-Siemens Hausgerate GmbH. Atomizer for fluids, preferably an inhalation device. 4,294,407, Cl. 239-102.000.
- Reid, Samuel C. M. Analog-to-digital converter. 4,295,123, Cl. 340-347.0AD.
- Reidel, Bruce A.: See—
Stevens, John H.; and Reidel, Bruce A., 4,294,357, Cl. 206-409.000.
- Reinert, Friedrich: See—
Helfert, Herbert; Reinert, Friedrich; Richter, Paul; Vescia, Michele; and Wegerle, Dieter, 4,294,576, Cl. 8-137.500.
- Reinhardt, Willy: See—
Bodenbender, Manfred; Reinhardt, Willy; and Ritzenhoff, Hermann, 4,294,368, Cl. 215-256.000.
- Remond, Jean R. A., to Etablissements F. Nicolle & Cie Societe Anonyme. Suspension-type file folder. 4,294,028, Cl. 40-359.000.
- Rennhofer, Linda. Halter top for sports suit. 4,294,257, Cl. 128-495.000.
- Rensner, Jürgen G., to Pepsico, Inc. Container package and its manufacture. 4,294,058, Cl. 53-413.000.

- Republic Steel Corporation: See—
Blair, Matthew J.; and Wiktorowski, Thomas A., 4,294,432, Cl. 266-46.000.
- Research Council of Alberta, The: See—
Roen, Richard A., 4,295,031, Cl. 219-125.120.
- Resnick, Martin L., to GTE Laboratories Incorporated. Data processing apparatus for receiving and decoding words in which data is encoded by phase reversals or non-phase reversals of a signal of a predetermined frequency. 4,295,207, Cl. 364-900.000.
- Resnick, Martin L.: See—
Norbedo, Robert A.; and Resnick, Martin L., 4,295,208, Cl. 364-900.000.
- Reusch, Heinz; and Kreikenbohm, Robert, to Stiebel Eltron GmbH & Co. KG. Method for charging and discharging a latent-heat storage medium and heat storage. 4,294,310, Cl. 165-104.130.
- Reynoir Company, The: See—
Reynoir, Ronald H.; Flaunt, Robert A.; and Leavitt, Clyde M., 4,294,331, Cl. 182-10.000.
- Reynoir, Ronald H.; Flaunt, Robert A.; and Leavitt, Clyde M., to Reynoir Company, The. Method and system for escaping from an offshore drilling platform. 4,294,331, Cl. 182-10.000.
- Rhone-Poulenc Industries: See—
Boutin, Jean; Guenot, Bernard; and Jamet, Bruno, 4,294,676, Cl. 204-159.230.
- Daniel, Jean-Claude; Grossoleil, Jacques; and Roulet, Robert, 4,294,704, Cl. 210-651.000.
- Rhone Poulenc Systems: See—
Kings, Donald; and Quang, Pham K., 4,294,903, Cl. 430-98.000.
- Richard Heinze, Firma: See—
Pittasch, Willi; and Dalbert, Johannes, 4,293,976, Cl. 16-129.000.
- Richardson, Ronald D.: See—
King, Dennis M.; and Richardson, Ronald D., 4,294,218, Cl. 123-502.000.
- Riche Corporation: See—
Summers, Kenneth L.; and Rieke, Mahlon E., 4,294,382, Cl. 222-529.000.
- Richter Gedeon Vegyeszeti Gyar RT: See—
Knoll, Jozsef; Kalasz, Huba; Knoll, Berta; and Nagy, Janos, 4,294,825, Cl. 424-101.000.
- Richter, Paul: See—
Helfert, Herbert; Reinert, Friedrich; Richter, Paul; Vescia, Michele; and Wegerle, Dieter, 4,294,576, Cl. 8-137.500.
- Ricke, Cyril T., Sr., to Security Shutter Corp. Shutter and awning device. 4,294,302, Cl. 160-133.000.
- Ricoh Company, Ltd.: See—
Ariyama, Kenzo; Miyawaki, Syozo; and Murakami, Takashi, 4,294,535, Cl. 355-14.0SH.
- Riebel, Hans-Jochem; Eue, Ludwig; and Faust, Wilfried, to Bayer Aktiengesellschaft. N-Acyl-piperidone compounds. 4,294,967, Cl. 546-242.000.
- Riedel, Rudolph T. Design for flush tank control using non-buoyant flapper valve. 4,293,964, Cl. 4-378.000.
- Rieger, Franz: See—
Maurer, Helmut; Muller, Klaus; Linder, Ernst; Rieger, Franz; and Stecher, Gunther, 4,294,679, Cl. 204-195.005.
- Rieger, Gerald: See—
Rauschert, Willi; Rieger, Gerald; Bock, Erich; and Eckel, Alfred, 4,294,172, Cl. 102-473.000.
- Rieke, Mahlon E.: See—
Summers, Kenneth L.; and Rieke, Mahlon E., 4,294,382, Cl. 222-529.000.
- Riel, Frank J.: See—
Rose, Philip M.; and Riel, Frank J., 4,294,329, Cl. 181-222.000.
- Riessberger, Klaus: See—
Theurer, Josef; and Riessberger, Klaus, 4,294,041, Cl. 51-5.00C.
- Riester, William C.: See—
Gowans, Neil A.; and Riester, William C., 4,293,974, Cl. 15-250.320.
- Rinehart, Jay K., to PPG Industries, Inc. N-(Optionally substituted 1,3-dioxolan- or dioxan-2-ylmethyl)-N-alkyl, alkenyl, or alkynyl-2,2-dichloroacetamides. 4,294,764, Cl. 260-340.90R.
- Ritzenhoff, Hermann: See—
Bodenbender, Manfred; Reinhardt, Willy; and Ritzenhoff, Hermann, 4,294,368, Cl. 215-256.000.
- Rivers, Alfred J.: See—
Ernsting, John; Morgan, Thomas R.; Palmer, Leonard F. W.; Rivers, Alfred J.; and Robson, Stephen M., 4,294,243, Cl. 128-201.180.
- Rix, Albert, to Olympia Werke AG. Guide for record carrier in printers. 4,294,556, Cl. 400-643.000.
- Rizzo, Vincent J.: See—
Bigley, William J., Jr.; and Rizzo, Vincent J., 4,295,081, Cl. 318-327.000.
- Robert Bosch GmbH: See—
Binder, Georg; and Wossner, Gunter, 4,295,067, Cl. 310-52.000.
- Glockler, Otto, 4,294,217, Cl. 123-491.000.
- Hans, Waldmar; Sauer, Rudolf; Glockler, Otto; Steinbrenner, Ulrich; Gunther, Dieter; and Lembke, Manfred, 4,294,215, Cl. 123-470.000.
- Hausdorfer, Michael; and Heitmann, Jurgen, 4,295,156, Cl. 358-12.000.
- Lauterbach, Heinz, 4,294,114, Cl. 73-204.000.
- Maurer, Helmut; Muller, Klaus; Linder, Ernst; Rieger, Franz; and Stecher, Gunther, 4,294,679, Cl. 204-195.005.
- Muller, Rolf, 4,295,168, Cl. 360-66.000.
- Sautter, Helmut; Hurst, Kurt; and Schink, Rainer, 4,295,127, Cl. 340-373.000.
- Stumpp, Gerhard; and Wessel, Wolf, 4,294,211, Cl. 123-379.000.
- Roberts, Joseph A., to Advanced Circuit Technology. Circuit board with self-locking terminals. 4,295,184, Cl. 361-406.000.
- Robertshaw Controls Company: See—
Buckshaw, Thomas M., 4,295,019, Cl. 200-61.200.
- Robertson, Robert H., to Ronbil Industries, Inc. Vehicle camper. 4,294,484, Cl. 296-156.000.
- Robins, Charles T., to Gould Inc. Trifurcated arc runner. 4,295,022, Cl. 200-147.00R.
- Robinson, Ken K.: See—
Kim, Dae K.; Bertolacini, Ralph J.; Gutberlet, L. Charles; and Robinson, Ken K., 4,294,685, Cl. 208-10.000.
- Robinson, Vivian M.: See—
Anolick, Colin; Robinson, Vivian M.; and Stewart, Charles W., Sr., 4,294,489, Cl. 297-452.000.
- Robson, Stephen M.: See—
Ernsting, John; Morgan, Thomas R.; Palmer, Leonard F. W.; Rivers, Alfred J.; and Robson, Stephen M., 4,294,243, Cl. 128-201.180.
- Rock, Erich; and Mages, Bernhard, to Julius Blum Gesellschaft m.b.H. Pull-out guide assembly. 4,294,499, Cl. 312-334.000.
- Rockwell International Corporation: See—
Thompson, Robert B., 4,295,214, Cl. 367-140.000.
- Wagner, William R., 4,294,208, Cl. 123-285.000.
- Rodenberg, Joseph H.; and Gilcrest, Richard K. Hog farrowing module. 4,294,195, Cl. 119-20.000.
- Rody, Jean, to Ciba-Geigy Corporation. Polyalkylpiperidine derivatives of s-triazine. 4,294,963, Cl. 544-198.000.
- Roen, Richard A., to Research Council of Alberta, The. Arc welding apparatus with oscillating electrode. 4,295,031, Cl. 219-125.120.
- Rogan, Bruce R.: See—
Herr, John A.; and Rogan, Bruce R., 4,295,118, Cl. 338-32.00H.
- Rogers, William H., to Alpha Plastics, Inc. Rapidly separable holster and holster-carrying belt. 4,294,385, Cl. 224-240.000.
- Rohloff, Ekhard: See—
Beck, Ulrich; and Rohloff, Ekhard, 4,294,656, Cl. 162-192.000.
- Rohm GmbH: See—
Monsheimer, Rolf; and Pfeleiderer, Ernst, 4,294,087, Cl. 69-21.000.
- Rohr Industries, Inc.: See—
Rose, Philip M.; and Riel, Frank J., 4,294,329, Cl. 181-222.000.
- Rojey, Alexandre: See—
Cohen, Georges; and Rojey, Alexandre, 4,294,080, Cl. 62-101.000.
- Roll & Go AG: See—
Keller, Andre, 4,294,025, Cl. 36-132.000.
- Romankiw, Lubomyr T.; and Thompson, David A., to International Business Machines Corporation. Thin film inductive transducer. 4,295,173, Cl. 360-125.000.
- Romankiw, Lubomyr T.: See—
Miersch, Ekkehard F.; and Romankiw, Lubomyr T., 4,295,183, Cl. 361-403.000.
- Romenets, Vladimir A.: See—
Vanjukov, Andrei V.; Mechev, Valery V.; Bystrov, Valentin P.; Ezhov, Evgeny I.; Vasiliev, Mikhail G.; Zaitsev, Vladimir Y.; Romenets, Vladimir A.; Ivanov, Vladimir V.; Golik, Sergei Y.; Grin-Gnatovsky, Evgeny S.; Grechko, Alexander V.; Savin, Ivan V.; Kozhakhmetov, Sultanbek M.; Meierovich, Veniamin B.; Nagibin, Vladimir D.; Ramazanov, Nariman A.; Umarov, Almas B.; Ziberov, Valentin E.; Kunaev, Askar M.; Takezhanov, Sauk T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazheev, Dzhonson T., 4,294,433, Cl. 266-161.000.
- Ronbil Industries, Inc.: See—
Robertson, Robert H., 4,294,484, Cl. 296-156.000.
- Rose, Philip M.; and Riel, Frank J., to Rohr Industries, Inc. Double layer attenuation panel with two layers of linear type material. 4,294,329, Cl. 181-222.000.
- Rosenberg, Arnold M.: See—
Gaidis, James M.; and Rosenberg, Arnold M., 4,294,813, Cl. 423-385.000.
- Rosenthal, Christian: See—
Pietrala, Norbert; Ausserbauer, Valentin; and Rosenthal, Christian, 4,294,771, Cl. 260-413.000.
- Ross, Lawrence M. Traction bag. 4,294,405, Cl. 238-14.000.
- Ross, Michael D.: See—
Truesdell, Raymond L.; and Ross, Michael D., 4,295,216, Cl. 369-55.000.
- Roth, Eldon N. Refrigerating meat paste. 4,294,860, Cl. 426-417.000.
- Roth, Joseph A.: See—
Bechle, Philip D.; and Roth, Joseph A., 4,294,906, Cl. 430-207.000.
- Roulet, Robert: See—
Daniel, Jean-Claude; Grossoleil, Jacques; and Roulet, Robert, 4,294,704, Cl. 210-651.000.
- Rowe, Bryant T. Fuel heating system for an engine. 4,294,219, Cl. 123-557.000.
- Rowe, Lacy A. Sealing means for gutter hanger fastening means. 4,294,423, Cl. 248-48.200.
- Roybal, Philip M., to National Semiconductor Corporation. Communication method and system. 4,295,124, Cl. 340-347.00D.
- Rudstrom, Lars G.: See—
Lindahl, Jonas A. I.; and Rudstrom, Lars G., 4,294,653, Cl. 162-25.000.
- Rugen, Donald F.; and Dickason, Alan F., to Sun Oil Company of Pennsylvania. Plasticized vinyl resins containing a linear mono C₁₂-alkyl diphenyl compound. 4,294,742, Cl. 260-31.80H.

- Rump, Bjorn S., to Rump, Bjorn Sigurd. Process for manufacture of a wide patterned band such as a transfer-carrying sheet and for printing on a substrate therewith. 4,294,637, Cl. 156-157.000.
- Rump, Bjorn Sigurd: See—
Rump, Bjorn S., 4,294,637, Cl. 156-157.000.
- Runge, Thomas M. Pulsatile flow cardiopulmonary bypass pump. 4,293,961, Cl. 3-1.700.
- Ruprecht, Hans-Dieter: See—
Grogler, Gerhard; Schwindt, Jurgen; Ganster, Otto; Meiners, Hans-Joachim; and Ruprecht, Hans-Dieter, 4,294,934, Cl. 521-160.000.
- Rusch, Reinhard: See—
Arndt, Friedrich; Rusch, Reinhard; and Schulz, Heinz, 4,294,605, Cl. 71-73.000.
- Rust-Oleum Corporation: See—
Dulaney, Donald C.; and Bowman, John A., 4,294,619, Cl. 106-188.000.
- Ruti Machinery Works Ltd.: See—
Freisler, Erhard, 4,294,290, Cl. 139-26.000.
- Rutledge, Wyman C.; Graves, J. Robert; and Cassill, William G., to Mead Corporation, The. Portable fluid ink tack tester. 4,294,111, Cl. 73-150.00R.
- Ryskind, Alexandr M.: See—
Egorov, Viktor P.; Ognevsky, Viktor A.; Orlovsky, Anatoly G.; Ostrovsky, Grigory A.; Ryskind, Alexandr M.; Stepin, Anatoly L.; Trofimov, Oleg F.; and Shklyarov, Isaak N., 4,294,098, Cl. 72-128.000.
- Rytomaa, Tapio: See—
Jones, William A.; Hing Yuen, Tse Lin Sin Tse; Rytomaa, Tapio; Harper, Norman J.; and Frost, Henry F., 4,294,824, Cl. 424-101.000.
- S. C. Johnson & Son, Inc.: See—
Neumiller, Phillip J., 4,294,821, Cl. 424-45.000.
- Saab-Scania AB: See—
Olsson, Lars J., 4,294,149, Cl. 83-435.100.
- Sabacky, Milton J.: See—
Knowles, William S.; and Sabacky, Milton J., 4,294,989, Cl. 568-13.000.
- Saccavino, Joseph F.; and Vanek, Edward A. Halocarbon and azeotropic refrigerant compositions containing offensive warning component. 4,294,716, Cl. 252-68.000.
- Sacki, Tadashi: See—
Minematsu, Hiroyuki; Matsumoto, Kojiro; Sacki, Tadashi; and Kishi, Akira, 4,294,946, Cl. 526-80.000.
- Saft-Societe des Accumulateurs Fixes et de Traction: See—
Godard, Pierre; and Billot, Michel, 4,294,309, Cl. 165-18.000.
- Sagara, Seiji: See—
Sugiura, Muneharu; and Sagara, Seiji, 4,295,186, Cl. 362-217.000.
- Sagata, Makoto: See—
Kisaka, Hiroyuki; Sagata, Makoto; Miyahara, Masayoshi; and Katayama, Morimitsu, 4,294,130, Cl. 74-15.400.
- Saiki, Yukihiro: See—
Kumazawa, Eitaro; Saiki, Yukihiro; and Ishioka, Yozo, 4,294,018, Cl. 34-56.000.
- St. John, Richard C., to Dyneer Corporation. Centrifugal clutch construction. 4,294,342, Cl. 192-105.00D.
- Saito, Tsutomu; and Shida, Masaaki, to Kabushiki Kaisha Fuji Seisakusho. Apparatus for making fiberboard. 4,294,657, Cl. 162-303.000.
- Sakagami, Teruo; Kato, Tadaaki; Hirai, Toru; and Murayama, Naohiro, to Kureha Kagaku Kogyo Kabushiki Kaisha. Method for electrodeposition of a protein onto an ion-exchange membrane. 4,294,677, Cl. 204-181.00F.
- Sakaguchi, Hiroaki: See—
Sugita, Toshio; Sakaguchi, Hiroaki; Tsuda, Hisanobu; and Suzuki, Tsuyoshi, 4,294,951, Cl. 528-55.000.
- Sakai Chemical Industry Co., Ltd.: See—
Abe, Kazunobu; Tamura, Shoichi; and Nakatsuji, Tadao, 4,294,806, Cl. 423-239.000.
- Sakai, Yutaka: See—
Doi, Yoshikazu; Sakai, Yutaka; and Ohno, Kazunori, 4,294,521, Cl. 350-426.000.
- Sakamoto, Moriyoshi: See—
Mitani, Akio; Sakamoto, Moriyoshi; and Murasaki, Hiroaki, 4,294,081, Cl. 62-140.000.
- Sakata, Touichi: See—
Mukoyama, Yoshiyuki; and Sakata, Touichi, 4,294,952, Cl. 528-67.000.
- Sakcriska, Glenn. Ice skate sharpener. 4,294,043, Cl. 51-100.00R.
- Sakitani, Yoshio: See—
Todokoro, Hideo; and Sakitani, Yoshio, 4,295,072, Cl. 313-7.000.
- Sako, Kazushige: See—
Hata, Hidetoh; Haji, Katsumi; Sako, Kazushige; Shibata, Yoji; and Achiha, Masahiko, 4,295,154, Cl. 358-4.000.
- Saleck, Wilhelm: See—
Helling, Gunter; Saleck, Wilhelm; and Berghaller, Peter, 4,294,920, Cl. 430-569.000.
- Salerno, Carmine P.: See—
Wittlinger, Harold A.; and Salerno, Carmine P., 4,294,321, Cl. 177-210.00P.
- Salisbury, Robert E.: See—
Lewis, Alfred E.; and Salisbury, Robert E., 4,294,569, Cl. 410-133.000.
- Saltzman, Philip A.: See—
Dorsen, Mac; and Saltzman, Philip A., 4,294,299, Cl. 150-28.00R.
- Salway, Peter H.: See—
Woodhouse, Richard G.; and Salway, Peter H., 4,295,177, Cl. 361-154.000.
- Sanka, Tsugio: See—
Iiyama, Masahiko; Sanka, Tsugio; and Naito, Kenji, 4,294,205, Cl. 123-274.000.
- Sankey, William M.: See—
Burns, William S., Jr.; and Sankey, William M., 4,294,480, Cl. 294-131.000.
- Sanner Contracting Co.: See—
Welch, James A., 4,294,026, Cl. 37-8.000.
- Sanyo Electric Co., Ltd.: See—
Iwata, Mitsuo; Wada, Hajime; Iwasa, Tomoyuki; and Tsuchino, Kunio, 4,295,169, Cl. 360-71.000.
- Yoshii, Kazuhiro, 4,294,076, Cl. 62-235.100.
- Sappok, Reinhard; and Kranz, Joachim, to BASF Aktiengesellschaft. Phthalocyanine formulations. 4,294,620, Cl. 106-288.00Q.
- Sarcia, Domenico S., to Oerlikon-Buhrle U.S.A. Inc. Cryogenic refrigerator with dual control valves. 4,294,077, Cl. 62-6.000.
- Sarcia, Domenico S.; and Lam, Calvin K., to Oerlikon-Buhrle U.S.A. Inc. Valves for cryogenic refrigerators. 4,294,600, Cl. 62-6.000.
- Sarka, Albert J. Method of making die plates. 4,294,649, Cl. 156-645.000.
- Sasaki, Takeshi, to Honda Giken Kogyo Kabushiki Kaisha. Process for balancing a crankshaft. 4,295,032, Cl. 219-137.00R.
- Sassler, Marvin L.: See—
Jarger, Harold F.; and Sassler, Marvin L., 4,295,155, Cl. 358-12.000.
- Sata, Toshikatsu: See—
Onoue, Yasuharu; Sata, Toshikatsu; Nakahara, Akihiko; and Itoh, Junichi, 4,294,943, Cl. 525-358.000.
- Sato, Eiichi: See—
Inouye, Hiroshi; and Sato, Eiichi, 4,294,453, Cl. 277-22.000.
- Sato, Yasuhisa; Tsuji, Sadahiko; and Ishikawa, Kazuo, to Canon Kabushiki Kaisha. Camera. 4,294,529, Cl. 354-53.000.
- Satomi, Yoshihito: See—
Uchida, Seichi; Satomi, Yoshihito; Kiuchi, Norihiro; Yamagata, Takeo; Yoshioka, Susumu; Miyamoto, Tomohiko; and Tomuro, Jinichi, 4,294,803, Cl. 422-111.000.
- Satzinger, Gerhard: See—
Hartenstein, Johannes; Satzinger, Gerhard; Bahrmann, Heinrich; and Ganser, Volker, 4,294,834, Cl. 424-260.000.
- Stoss, Peter; Satzinger, Gerhard; Herrmann, Manfred; and Heldt, Wolfgang, 4,294,838, Cl. 424-263.000.
- Sauer, Friedrich: See—
Astheimer, Hans J.; Brandstaedter, Horst; Ohlinger, Rainer; Van Pee, Willy; Van Steen, Jaak; Sauer, Friedrich; Schmidt, Rudolf; and Krueger, Siegfried, 4,294,666, Cl. 203-72.000.
- Sauer, Rudolf: See—
Hans, Waldmar; Sauer, Rudolf; Glockler, Otto; Steinbrenner, Ulrich; Gunther, Dieter; and Lembke, Manfred, 4,294,215, Cl. 123-470.000.
- Sauerscheil, Wolfgang; and Werkmann, Karl-Heinz, to VDO Adolf Schindling AG. Device for measuring the fuel consumption of a vehicle. 4,294,108, Cl. 73-119.00A.
- Saunders, Ian C. B.: See—
Lovell, Peter J.; and Saunders, Ian C. B., 4,294,794, Cl. 264-328.100.
- Sautter, Helmut; Hurst, Kurt; and Schink, Rainer, to Robert Bosch GmbH. Information display device. 4,295,127, Cl. 340-373.000.
- Sauvat, Roger: See—
Thuries, Edmond; Vernet, Pierre; and Sauvat, Roger, 4,295,023, Cl. 200-148.00R.
- Savin, Ivan V.: See—
Vanjukov, Andrei V.; Mechev, Valery V.; Bystrov, Valentin P.; Ezhov, Evgeny I.; Vasiliev, Mikhail G.; Zaitsev, Vladimir Y.; Romenets, Vladimir A.; Ivanov, Vladimir V.; Golik, Sergei Y.; Grin-Gnatovsky, Evgeny S.; Grechko, Alexander V.; Savin, Ivan V.; Kozhakhmetov, Sultanbek M.; Meierovich, Veniamin B.; Nagibin, Vladimir D.; Ramazanov, Nariman A.; Umarov, Almas B.; Ziberov, Valentin E.; Kunaev, Askar M.; Takezhanov, Sauk T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazheev, Dzhonson T., 4,294,433, Cl. 266-161.000.
- Sawa, Toshio; Kubota, Masayoshi; Takahashi, Sankichi; and Kaneko, Toyohiko, to Hitachi, Ltd. Apparatus for treatment of sewage. 4,294,697, Cl. 210-221.100.
- Sawada, Hajimu; and Inubushi, Hisao, to Nippon Kokan Kabushiki Kaisha; Nippon Rotary Nozzle Co., Ltd.; Kokan Kikai Kogyo Kabushiki Kaisha; and Tokyo Yogyo Kabushiki Kaisha. Slide closure for the pouring nozzle of a molten metal vessel. 4,294,437, Cl. 266-272.000.
- Sax Zzyx, Ltd.: See—
Anthony, Myron L., 4,294,664, Cl. 203-19.000.
- SCA Development Aktiebolag: See—
Bohlin, Karl G.; Fredriksson, Borje I.; Karlsson, Kent A. B.; and Nelvig, Lars T., 4,294,412, Cl. 241-30.000.
- Scammell, Gerald W.: See—
Solomons, Gerald L.; and Scammell, Gerald W., 4,294,929, Cl. 435-254.000.
- Schacht, Erich: See—
Doll, Thomas; Schacht, Erich; Radunz, Hans-Eckart; and Schulze, Ernst, 4,294,839, Cl. 424-263.000.
- Schadlich, Renate: See—
Moraw, Roland; and Schadlich, Renate, 4,294,913, Cl. 430-396.000.
- Schaeffer, Howard J., to Burroughs Wellcome Co. Purine derivatives. 4,294,831, Cl. 424-253.000.

- Schafer, Walter: See—
Wagner, Kuno; Block, Hans-Dieter; and Schafer, Walter, 4,294,719, Cl. 252-182.000.
- Schar, Ernst. Floor cleaning device. 4,293,973, Cl. 15-230.170.
- Scharres, Harry J. Wedge sealed damper. 4,294,283, Cl. 137-601.000.
- Schedler, Heinz: See—
Funk, Willi; Verheyen, Roland; and Schedler, Heinz, 4,294,103, Cl. 72-453.140.
- Scheffel, Herbert; von Gericke, Rowlen E.; and Viviers, Joseph A., to South African Inventions Development Corporation. Railway wheel tread profile. 4,294,482, Cl. 295-34.000.
- Scheier, Donald J.: See—
McDonald, David M.; and Scheier, Donald J., 4,293,978, Cl. 17-12.000.
- Scheiter, Heinz: See—
Krock, Friedrich W.; Neeff, Rutger; and Scheiter, Heinz, 4,294,769, Cl. 260-378.000.
- Schep, Raymond A., to Occidental Research Corporation. Process for producing aromatic carboxylic acids. 4,294,977, Cl. 562-407.000.
- Schering Aktiengesellschaft: See—
Arndt, Friedrich; Rusch, Reinhard; and Schulz, Heinz, 4,294,605, Cl. 71-73.000.
- Schreuer, Werner: See—
Wiesinger, Horst; and Schreuer, Werner, 4,294,307, Cl. 164-448.000.
- Schink, Rainer: See—
Sautter, Helmut; Hurst, Kurt; and Schink, Rainer, 4,295,127, Cl. 340-373.000.
- Schlicklin, Philippe; Mertzweiler nee Maillard, Anne-Marie; and Ploussard, Jacques, to Air Industrie. Compositions and methods for the denaturation of water-base paints. 4,294,617, Cl. 106-14.370.
- Schliebener, Claus: See—
Linde, Gerhard; Haeussinger, Peter; and Schliebener, Claus, 4,294,590, Cl. 55-48.000.
- Schloemann-Siemag Aktiengesellschaft: See—
Funk, Willi; Verheyen, Roland; and Schedler, Heinz, 4,294,103, Cl. 72-453.140.
- Spaude, Alfons, 4,294,099, Cl. 72-234.000.
- Schlottter, Harold J.; and Young, Leroy, to Champion International Corporation. Target backstop. 4,294,452, Cl. 273-403.000.
- Schmid, Rolf; and Lohse, Friedrich, to Ciba-Geigy Corporation. Curable mixture for producing reinforced elastomeric plastics based on epoxide resin. 4,294,745, Cl. 260-37.0EP.
- Schmid, Rolf: See—
Kreibich, Ursula; and Schmid, Rolf, 4,294,227, Cl. 126-400.000.
- Schmidt, Gary D.; Norris, Jerry L.; and Weirauch, Donald F., to Texas Instruments Incorporated. Surface acoustic wave sensor sensing circuits. 4,295,102, Cl. 331-65.000.
- Schmidt, Karl H.: See—
Wetter, Manfred; and Schmidt, Karl H., 4,294,415, Cl. 241-292.000.
- Schmidt, Robert R.; and Thomas, Rudolf, to Bayer Aktiengesellschaft. Herbicidal compositions. 4,294,607, Cl. 71-92.000.
- Schmidt, Rudolf: See—
Astheimer, Hans J.; Brandstaedter, Horst; Ohlinger, Rainer; Van Pee, Willy; Van Steen, Jaak; Sauer, Friedrich; Schmidt, Rudolf; and Krueger, Siegfried, 4,294,666, Cl. 203-72.000.
- Schmidt, Wolfram; and Paut, Joachim, to BASF Aktiengesellschaft. Preparation of pure potassium ribonate and ribonolactone. 4,294,766, Cl. 260-343.600.
- Schmidtpott, Friedrich: See—
Holzmann, Dieter; and Schmidtpott, Friedrich, 4,295,126, Cl. 340-347.0DD.
- Schmitt, Frederick L.: See—
Mookherjee, Braja D.; Wilson, Richard A.; Schmitt, Frederick L.; and Vock, Manfred H., 4,294,863, Cl. 426-538.000.
- Sprecker, Mark A.; Hall, John B.; and Schmitt, Frederick L., 4,294,266, Cl. 131-277.000.
- Sprecker, Mark A.; Schmitt, Frederick L.; Vock, Manfred H.; Vinals, Joaquin F.; and Kiwala, Jacob, 4,294,708, Cl. 252-8.600.
- Schmitz, Gunther; and Kierdorf, Hans, to Felten & Guillaume Carlswerk. Method of and a device for balancing a changing load of a strip roll orbiting about an axis in a strip winding machine. 4,294,064, Cl. 57-3.000.
- Schneider, Egon, to Kronseder, Hermann. Glue roller for labelling machine. 4,293,989, Cl. 29-130.000.
- Schneider, Hartmut, to Siemens Aktiengesellschaft. Light-wave guides and method of producing same. 4,294,514, Cl. 350-96.310.
- Schneider, Helmut: See—
Lohmuller, Reiner; Schneider, Helmut; and Watson, Allan, 4,294,932, Cl. 518-706.000.
- Schneider, Henri W.: See—
Nissen, Nico; Op Het Veld, Sebastianus J.; and Schneider, Henri W., 4,295,158, Cl. 358-17.000.
- Scholz, Karl-Heinz; Hartmann, Willy; and Heine, Hans-Georg, to Bayer Aktiengesellschaft. Process for the preparation of diacylated 4-imidazolin-2-ones. 4,294,973, Cl. 548-320.000.
- Schonherr, Walter: See—
Eckhardt, Fritz; and Schonherr, Walter, 4,295,076, Cl. 313-223.000.
- Schramm, Arthur G. Insulation panel. 4,294,875, Cl. 428-72.000.
- Schuegraf, Eberhard, to Siemens Aktiengesellschaft. Rectangular wave guide elbow bent across the narrow side with capacitive loading. 4,295,109, Cl. 333-249.000.
- Schuler, Michael: See—
Jewusiak, Stephen J.; Beroff, Howard; and Schuler, Michael, 4,294,355, Cl. 206-339.000.
- Schulz, Heinz: See—
Arndt, Friedrich; Rusch, Reinhard; and Schulz, Heinz, 4,294,605, Cl. 71-73.000.
- Schulz, Toni: See—
Olschewski, Armin; Brandenstein, Manfred; Walter, Lothar; Ernst, Horst M.; and Schulz, Toni, 4,294,100, Cl. 72-340.000.
- Schulze, Ernst: See—
Doll, Thomas; Schacht, Erich; Radunz, Hans-Eckart; and Schulze, Ernst, 4,294,839, Cl. 424-263.000.
- Schulze-Schoelling, Hermann: See—
Blum, Arnold; Geng, Hellmuth R.; Schulze-Schoelling, Hermann; and Spaeth, Bernd, 4,295,220, Cl. 371-61.000.
- Schupska, Gary G.: See—
Stone, Frederick C.; and Schupska, Gary G., 4,294,968, Cl. 546-251.000.
- Schurter, Rolf: See—
Tobler, Hans; Fory, Werner; and Schurter, Rolf, 4,294,606, Cl. 71-88.000.
- Schuster, Stanley E., to International Business Machines Corporation. Logic and array logic driving circuits. 4,295,064, Cl. 307-468.000.
- Schutten, Herman P.: See—
Lade, Robert W.; Spellman, Gordon B.; Jaskolski, Stanley V.; Schutten, Herman P.; and Jaeschke, James R., 4,295,058, Cl. 307-252.00A.
- Schutzler, Jerome C., to PDA Engineering. Pre-stressed structural joint. 4,294,559, Cl. 403-28.000.
- Schwegman, Harry E., deceased (by Dallas, M. J. Whitfield for First National Bank in, executor), to Otis Engineering Corporation. Kick-over tool. 4,294,313, Cl. 166-117.500.
- Schwindt, Jürgen: See—
Grogler, Gerhard; Schwindt, Jürgen; Ganster, Otto; Meiners, Hans-Joachim; and Ruprecht, Hans-Dieter, 4,294,934, Cl. 521-160.000.
- Schwisser, Bernd: See—
Marzouki, Taieb; and Schwisser, Bernd, 4,294,733, Cl. 260-28.50B.
- Sebag, Henri: See—
Vanlerberghe, Guy; Sebag, Henri; and Fiquet, Claire, 4,294,728, Cl. 252-542.000.
- Security Shutter Corp.: See—
Ricke, Cyril T., Sr., 4,294,302, Cl. 160-133.000.
- Sedlak, John M.; and Lawrance, Richard J., to General Electric Company. Catalytic alloys. 4,294,608, Cl. 75-0.50A.
- Sedlmayr, Gerhard, to Hannes Marker. Ski stop. 4,294,458, Cl. 280-605.000.
- Seed, Geoffrey; Chesworth, Graham; Hind, John R.; and Hodgson, Donald, to Nuclear Power Company Limited. Liquid metal cooled fast breeder nuclear reactor constructions. 4,294,661, Cl. 376-363.000.
- Segawa, Yoshihiro; Ohta, Minoru; and Yasuda, Eturo, to Nippon Soken, Inc. Gas component detector. 4,294,801, Cl. 422-98.000.
- Seiko Koki Kabushiki Kaisha: See—
Kitai, Kiyoshi; Ogihara, Masuo; and Chimura, Kozo, 4,295,215, Cl. 368-196.000.
- Nakagawa, Tadashi, 4,294,526, Cl. 354-25.000.
- Nakagawa, Tadashi, 4,294,532, Cl. 354-246.000.
- Seitmann, Vernon H. Grain drying apparatus. 4,294,019, Cl. 34-65.000.
- Sekiya, Setsuro: See—
Sumiyoshi, Masaharu; Sekiya, Setsuro; Motosugi, Katsuhiko; Uozumi, Junzo; Ando, Tsuneo; Takeuchi, Yuzo; and Minoura, Mikio, 4,294,213, Cl. 123-454.000.
- Sekmakas, Kazys; and Shah, Raj, to DeSoto, Inc. Water soluble epoxy ester copolymers for interior can use. 4,294,737, Cl. 260-29.2EP.
- Sequeira, Avilino, Jr.; Smith, Benjamin F., Jr.; and Mead, Theodore C., to Texaco, Inc. Solvent refining process. 4,294,689, Cl. 208-326.000.
- Sera, Hidefumi: See—
Yamaguchi, Jun; Naoi, Takashi; Sera, Hidefumi; Ishigaki, Kunio; and Ogawa, Masasi, 4,294,921, Cl. 430-621.000.
- Serwer, Philip, to Board of Regents, University of Texas. Template for forming multiple gel tracks within a single electrophoretic gel frame. 4,294,684, Cl. 204-299.00R.
- Severt, Wilhelm. Holding device. 4,294,440, Cl. 269-71.000.
- Seymour, Shaun A., to Sperry Corporation. Sensing bar. 4,294,062, Cl. 56-102.000.
- SGM Co., Inc.: See—
Gerboth, Patrick L.; and Thompson, Charles W., 4,294,082, Cl. 62-244.000.
- Shah, Nirad N.: See—
Prather, Richard A.; and Shah, Nirad N., 4,294,987, Cl. 564-331.000.
- Shah, Raj: See—
Sekmakas, Kazys; and Shah, Raj, 4,294,737, Cl. 260-29.2EP.
- Shanley, Robert L., II; and Hettiger, James, to RCA Corporation. Failure compensated automatic kinescope beam current limiter. 4,295,166, Cl. 358-243.000.
- Sharp Corporation: See—
Nakauchi, Hiroshi; Koyanagi, Katubumi; Inami, Yasuhiko; and Uede, Hisashi, 4,295,138, Cl. 340-785.000.
- Sharp Kabushiki Kaisha: See—
Hashimoto, Sadakatsu, 4,294,519, Cl. 350-357.000.
- Nakai, Syunji; and Nakao, Motokazu, 4,294,192, Cl. 118-650.000.
- Tanabe, Takeshi, 4,295,028, Cl. 219-10.55B.
- Shaw, James K. Amusement device. 4,294,449, Cl. 273-126.00R.
- Sheehan, Neil J.; and Norman, Melvin H., to Cutter Laboratories, Inc. Swage-molded injection site. 4,294,249, Cl. 128-214.00G.
- Shell Oil Company: See—
Kramer, Petrus A.; and Verbrugge, Pieter A., 4,294,765, Cl. 260-343.30R.

- Verschuur, Eke, 4,294,584, Cl. 44-23.000.
- Visser, Pieter; and van de Water, Johan P., 4,294,720, Cl. 252-373.000.
- Whitehead, Richard O., 4,294,937, Cl. 525-99.000.
- Shelley, Carey W.: See—
Winegard, John R.; Shelley, Carey W.; and Cowan, Keith B., 4,295,143, Cl. 343-840.000.
- Shem Safe Incorporated: See—
Shemitz, Norman S., 4,295,187, Cl. 362-352.000.
- Shemitz, Norman S., to Shem Safe Incorporated. Assemblable container. 4,295,187, Cl. 362-352.000.
- Shenk, Edwin K., to Polaroid Corporation. Auto-focus movie camera. 4,294,531, Cl. 354-195.000.
- Shepherd, Glen C.: See—
Gottbrecht, Tom L.; and Shepherd, Glen C., 4,293,987, Cl. 29-25.420.
- Sheppard, Peter H. Power steering gear with oil filled capillary balancing slots. 4,294,161, Cl. 91-422.000.
- Shibano, Michio: See—
Takahisa, Shuji; Suzuki, Osamu; and Shibano, Michio, 4,294,067, Cl. 57-274.000.
- Shibata, Yoji: See—
Hata, Hidetoh; Haji, Katsumi; Sako, Kazushige; Shibata, Yoji; and Achiha, Masahiko, 4,295,154, Cl. 358-4.000.
- Shida, Masaaki: See—
Saito, Tsutomu; and Shida, Masaaki, 4,294,657, Cl. 162-303.000.
- Shigenaka, Yoshito: See—
Otsuka, Chikao; Hara, Reinosuke; and Shigenaka, Yoshito, 4,294,367, Cl. 215-246.000.
- Shima, Ichiji; Yamamoto, Tatsuo; Yoshibayashi, Shigeru; Teshima, Hiroshi; Hizume, Akio; Iki, Tetsuo; Yamamoto, Takashi; Kanamori, Kyojo; and Tanaka, Shigehito. Torsional vibration monitoring apparatus for rotating shaft system. 4,294,120, Cl. 73-650.000.
- Shimadzu Corporation: See—
Koga, Kenichiro; Hirose, Yoshiharu; Kanno, Iwao; Uemura, Kazuo; and Miura, Shuichi, 4,295,047, Cl. 250-363.00S.
- Shimakawa, George: See—
Kobayashi, Masatoshi; Shimakawa, George; Hara, Yukio; Fujii, Hiroyuki; and Kabushiki Kaisha Seikoshu, 4,293,986, Cl. 29-25.350.
- Shimano Industrial Company, Limited: See—
Fukui, Seiji, 4,294,138, Cl. 74-750.00B.
- Shimano, Shizuo: See—
Nakagawa, Taizo; Matsumoto, Hiroshi; Ohmori, Kaoru; Shimano, Shizuo; and Koike, Kengo, 4,294,835, Cl. 424-263.000.
- Shimizu, Isamu: See—
Inoue, Eiichi; Shimizu, Isamu; and Shizukuishi, Makoto, 4,294,520, Cl. 350-357.000.
- Shimizu, Kazuaki, to Nissan Motor Company, Limited. Disc brake. 4,294,336, Cl. 188-72.400.
- Shin-Etsu Chemical Co. Ltd.: See—
Takago, Toshio; Arai, Masatoshi; and Futatsumori, Koji, 4,294,975, Cl. 556-482.000.
- Shinkai, Ichiro: See—
Tull, Roger J.; Weinstock, Leonard M.; and Shinkai, Ichiro, 4,294,988, Cl. 564-417.000.
- Shinoda, Akiyoshi; and Nakane, Masao, to Kabushiki Kaisha Toyoda Jidoshokki Seisakusho. Axle housing sub-assembly. 4,294,334, Cl. 188-18.00A.
- Shinoda, Hiroshi: See—
Haga, Toshikatsu; Fukuda, Hiroyuki; Shinoda, Hiroshi; and Hayakawa, Hideharu, 4,294,795, Cl. 264-332.000.
- Shiotani, Akinori: See—
Itatani, Hiroshi; Yoshimoto, Hataaki; Shiotani, Akinori; Yokota, Akiyoshi; and Yoshikiyo, Motozoh, 4,294,976, Cl. 560-76.000.
- Shiraiwa, Toshio; Yamaguchi, Hisao; and Matsumoto, Shigeaki, to Sumitomo Kinzoku Kogyo Kabushiki Kaisha. Fully automatic ultrasonic flaw detection apparatus. 4,294,118, Cl. 73-620.000.
- Shizukuishi, Makoto: See—
Inoue, Eiichi; Shimizu, Isamu; and Shizukuishi, Makoto, 4,294,520, Cl. 350-357.000.
- Shklyarov, Isaak N.: See—
Egorov, Viktor P.; Ognevsky, Viktor A.; Orlovsky, Anatoly G.; Ostrovsky, Grigory A.; Ryskind, Alexandr M.; Stepin, Anatoly L.; Trofimov, Oleg F.; and Shklyarov, Isaak N., 4,294,098, Cl. 72-128.000.
- Shutterly, Harold B., to Westinghouse Electric Corp. Digital signal/noise ratio amplifier apparatus for a communication system. 4,295,223, Cl. 455-72.000.
- Sibille, Jacques: See—
Drouin, Gilbert; and Sibille, Jacques, 4,294,015, Cl. 33-174.00D.
- Siemens Aktiengesellschaft: See—
Aulich, Hubert; and Graubmaier, Josef, 4,294,811, Cl. 423-350.000.
- Behn, Reinhard; Heywang, Hermann; and Pachonik, Horst, 4,294,194, Cl. 118-719.000.
- Ebersberger, Otto; and Kuehnell, Werner, 4,295,049, Cl. 250-409.000.
- Hieber, Konrad; and Stolz, Manfred, 4,294,871, Cl. 427-237.000.
- Kraemer, Horst, 4,295,100, Cl. 330-257.000.
- Schneider, Hartmut, 4,294,514, Cl. 350-96.310.
- Schuegraf, Eberhard, 4,295,109, Cl. 333-249.000.
- Soldner, Richard E., 4,294,119, Cl. 73-625.000.
- Thiere, Hellmuth; and Vallentin, Werner, 4,295,142, Cl. 343-781.0CA.
- Wiechert, Edelbert, 4,294,337, Cl. 188-171.000.
- Siewerdt, Lothar, to Kernforschungszentrum Karlsruhe GmbH. High voltage cable. 4,294,504, Cl. 339-132.00R.
- Sig Schweizerische Industrie-Gesellschaft: See—
Harsy, Gabor, 4,294,175, Cl. 105-199.00R.
- Sih, John C., to Upjohn Company, The. 13,14-Didehydro-19-oxo-PGF₂ compounds. 4,294,978, Cl. 562-503.000.
- Sih, John C., to Upjohn Company, The. 13,14-Dihydro-11-deoxy-11-hydroxymethyl-19-oxo-PGE₂ compounds. 4,294,979, Cl. 562-503.000.
- Sih, John C., to Upjohn Company, The. 13,14-Dihydro-11-deoxy-11-hydroxymethyl-19-oxo-PGF₁ compounds. 4,294,980, Cl. 562-503.000.
- Sih, John C., to Upjohn Company, The. 13,14-Didehydro-11-deoxy-9-deoxy-9-methylene-19-oxo-PGF₁ compounds. 4,294,981, Cl. 562-503.000.
- Sih, John C., to Upjohn Company, The. 13,14-Didehydro-11-deoxy-19-oxo-PGE₁ compounds. 4,294,982, Cl. 562-503.000.
- Sih, John C., to Upjohn Company, The. 13,14-Didehydro-11-deoxy-19-oxo-PGF₁ compounds. 4,294,983, Cl. 562-503.000.
- Sih, John C., to Upjohn Company, The. 13,14-Didehydro-11-deoxy-11-hydroxymethyl-9-deoxy-9-methylene-19-oxo-PGF₁ compounds. 4,294,984, Cl. 562-503.000.
- Silberberg, Joseph, to Stauffer Chemical Company. Filled vinyl chloride polymer composition. 4,294,752, Cl. 260-42.140.
- Silin, Evgeny L.: See—
Berenov, Alexandr D.; Krainev, Vladislav P.; Mansurov, Midkhat M.; Niskovskikh, Vitaly M.; and Silin, Evgeny L., 4,294,306, Cl. 164-448.000.
- Simmons, Gerald P., to Caterpillar Tractor Co. Operator's station and mounting. 4,294,465, Cl. 280-756.000.
- Simmons, John P., to Borg-Warner Corporation. Transmission shift control apparatus with countershaft brake. 4,294,338, Cl. 192-4.00A.
- Simon Engineering Dudley Limited: See—
Ashworth, Denis H., 4,294,188, Cl. 118-305.000.
- Simon-Johnson, Inc.: See—
McDonald, David M.; and Scheier, Donald J., 4,293,978, Cl. 17-12.000.
- Simonsen, Michael G.: See—
Curry, Robert E.; and Simonsen, Michael G., 4,295,199, Cl. 364-555.000.
- Sindlinger, Rainer; and Hammer, Josef, to Teldix GmbH. Magnetic bearing assembly. 4,294,493, Cl. 308-10.000.
- Singer Company, The: See—
Herr, John A.; and Rogan, Bruce R., 4,295,118, Cl. 338-32.00H.
- Skalina, Andrej: See—
Matta, Joseph J.; and Skalina, Andrej, 4,295,144, Cl. 343-895.000.
- SKF Kugellagerfabriken GmbH: See—
Olschewski, Armin; Brandenstein, Manfred; Walter, Lothar; Ernst, Horst M.; and Schulz, Toni, 4,294,100, Cl. 72-340.000.
- Sloane, Thomas E., Jr.; Melius, Clair; and Kling, Erich, to United States Surgical Corporation. Self-contained filter assembly for removing air, particles and bacteria from a solution. 4,294,594, Cl. 55-186.000.
- Small World Exchange, Inc.: See—
Johnson, Avery R.; McGurk, Richard G.; and Harrison, John M., 4,295,008, Cl. 179-18.0BC.
- Smith, Benjamin F., Jr.: See—
Sequeira, Avilino, Jr.; Smith, Benjamin F., Jr.; and Mead, Theodore C., 4,294,689, Cl. 208-326.000.
- Smith, Charles M. Crab butchering machine. 4,293,981, Cl. 17-71.000.
- Smith, Clay D.; and Keller, Douglas V., Jr., to Standard Oil Company. Multi-phase separation methods and apparatus. 4,294,695, Cl. 210-173.000.
- Smith, Franklin. Subsoil agricultural implement with rotatable disc. 4,294,181, Cl. 111-87.000.
- Smith, Herman W., to Upjohn Company, The. Structural analogues of 5,6-dihydro PG₁. 4,294,759, Cl. 260-326.270.
- Smith International, Inc.: See—
Herd, David P., 4,294,284, Cl. 137-613.000.
- Smith Kline & French Laboratories Limited: See—
Durant, Graham J.; Ganellin, Charon R.; and Vickers, Margaret R., 4,294,854, Cl. 424-326.000.
- Smith, Michael P.: See—
Blackburn, Martin J.; and Smith, Michael P., 4,294,615, Cl. 75-175.500.
- Smith, Richard W.: See—
Woelfel, James A.; and Smith, Richard W., 4,294,639, Cl. 156-185.000.
- Smith, Robert A.: See—
Williams, John W.; Smith, Robert A.; and Arbir, Francis W., 4,294,853, Cl. 424-319.000.
- Smith, Robert E.; and Bissell, Eugene R. Substrates and method for determining enzymes. 4,294,923, Cl. 435-23.000.
- Smith, William H.: See—
Wilreker, Victor F.; and Smith, William H., 4,295,094, Cl. 324-96.000.
- Snel, Cornelis; and Kuus, Albert. Haybox. 4,294,197, Cl. 119-60.000.
- Snelling, Christopher, to Xerox Corporation. Multiple function reproduction apparatus. 4,294,534, Cl. 355-3.00R.
- Snipes, Wallace: See—
Keith, Alec D.; and Snipes, Wallace, 4,294,820, Cl. 424-28.000.
- Snow Brand Milk Products Co., Ltd.: See—
Kumazawa, Eitaro; Saiki, Yukihiko; and Ishioka, Yozo, 4,294,018, Cl. 34-56.000.
- Snowden, Paul, to Imperial Chemical Industries, Inc. Spinning process and apparatus. 4,294,783, Cl. 264-8.000.

- Snyder, Irving F.; and Luebeck, Duane A., to Graco Inc. In centrifugal spray guns. 4,294,408, Cl. 239-218.500.
- Societa Italiana Vetro-Siv-S.p.A.: See—
Kalbskopf, Reinhard; and Baumberger, Otto, 4,294,868, Cl. 427-109.000.
- Societa Italo-Britannica: See—
Innocenti, Franco; Orzalesi, Giovanni; and Volpato, Ivo, 4,294,833, Cl. 424-263.000.
- Societe Anonyme dite: L'Oreal: See—
Vanlerberghe, Guy; Sebag, Henri; and Fiquet, Claire, 4,294,728, Cl. 252-542.000.
- Societe Chimique des Charbonnages SA: See—
Couderc, Pierre; Grardel, Jean-Luc; and Caux, Gerard, 4,294,717, Cl. 252-97.000.
- Societe de Paris et du Rhone: See—
Mazzorana, Alfred B., 4,294,129, Cl. 74-7.00A.
- Societe d'Etudes Scientifiques et Industrielles de l'ile de France: See—
Thominet, Michel; Acher, Jacques; and Monier, Jean-Claude, 4,294,828, Cl. 424-232.000.
- Soldner, Richard E., to Siemens Aktiengesellschaft. Ultrasonic applicator for ultrasonic scanning of bodies. 4,294,119, Cl. 73-625.000.
- Soles, Otto H.: See—
Kovatch, George N.; Bettencourt, George S.; and Soles, Otto H., 4,295,054, Cl. 307-80.000.
- Solomons, Gerald L.; and Scammell, Gerald W., to Ranks Hovis McDougall Limited. Production of edible protein substances. 4,294,929, Cl. 435-254.000.
- Sontheim, Max: See—
Paulsen, Ralf; Sontheim, Max; and Ullmann, Christoph, 4,294,056, Cl. 53-86.000.
- Sony Corporation: See—
Nishimura, Yoshinori; Umeda, Kaoru; and Harada, Hideo, 4,295,224, Cl. 455-156.000.
- Sopino, Bruno: See—
Corrado, Giovanni; Bertotti, Elvio; and Sopino, Bruno, 4,294,734, Cl. 260-22.0CB.
Corrado, Giovanni; Bertotti, Elvio; and Sopino, Bruno, 4,294,748, Cl. 260-22.0CB.
- Souhrada, Frank: See—
Fisher, Ian P.; Woods, H. John; and Souhrada, Frank, 4,294,686, Cl. 208-56.000.
- South African Inventions Development Corporation: See—
Scheffel, Herbert; von Gericke, Rowlen E.; and Viviers, Joseph A., 4,294,482, Cl. 295-34.000.
- Southland Corporation, The: See—
Hughes, Graham K., 4,294,992, Cl. 568-632.000.
- Sova, Alex W. Workpiece retainer. 4,294,443, Cl. 269-108.000.
- Spaeth, Bernd: See—
Blum, Arnold; Geng, Hellmuth R.; Schulze-Schoelling, Hermann; and Spaeth, Bernd, 4,295,220, Cl. 371-61.000.
- Spanier, Florence: See—
Spanier, Joseph; and Spanier, Florence, 4,294,308, Cl. 165-1.000.
- Spanier, Joseph; and Spanier, Florence. Method and assembly for camouflaging at least one building. 4,294,308, Cl. 165-1.000.
- Spatz, David M.; and Cross, Barrington, to American Cyanamid Co. Novel para-phenylalkoxy phenylurea and thiourea compounds and herbicidal use thereof. 4,294,986, Cl. 564-52.000.
- Spaude, Alfons, to Schloemann-Siemag Aktiengesellschaft. Rolling mill train. 4,294,099, Cl. 72-234.000.
- Spaulding, James G.: See—
McMichael, John; Kline, Ellis L.; and Spaulding, James G., 4,294,818, Cl. 424-12.000.
- Specker, Manfred: See—
Metz, Gunter; and Specker, Manfred, 4,294,851, Cl. 424-311.000.
- Spehrley, Charles W., Jr., to Xerox Corporation. Document vacuum weir system. 4,294,539, Cl. 355-76.000.
- Spellman, Gordon B.: See—
Lade, Robert W.; Spellman, Gordon B.; Jaskolski, Stanley V.; Schutten, Herman P.; and Jaeschke, James R., 4,295,058, Cl. 307-252.00A.
- Spencer, John K.: See—
Naylor, Arthur V.; and Spencer, John K., 4,294,060, Cl. 53-506.000.
- Spengler, Walter. Electrode arrangement with individually connectable and disconnectable electrodes. 4,295,178, Cl. 361-220.000.
- Sperry Corporation: See—
Decoene, Frans J. G. C.; Hommez, Etienne R. O. C.; and Naaktgeboren, Adrianus, 4,294,346, Cl. 198-740.000.
- Eibner, Jules A.; and Kanamuller, Franz X., 4,295,043, Cl. 250-227.000.
- Seymour, Shaun A., 4,294,062, Cl. 56-102.000.
- Sperry Rand Corporation: See—
Porcella, Brewster J., 4,295,192, Cl. 364-200.000.
- Spitzner, Ernest, to Henkel Corporation. Benzothiazine 1,1-dioxides. 4,294,961, Cl. 544-49.000.
- Specker, Mark A.; Hall, John B.; and Schmitt, Frederick L., to International Flavors & Fragrances Inc. Benzodioxanones and organoleptic uses thereof. 4,294,266, Cl. 131-277.000.
- Specker, Mark A.; Schmitt, Frederick L.; Vock, Manfred H.; Vinals, Joaquin F.; and Kiwala, Jacob, to International Flavors & Fragrances Inc. Process for augmenting or enhancing the aroma of perfumed article using alkyl cycloalkenyl carbinol. 4,294,708, Cl. 252-8.600.
- Sprott, Kenneth J.; and Westrick, George M., to Dresser Industries, Inc. Anti-surge system for gases and other media. 4,294,113, Cl. 73-199.000.
- Stacey, Eric J.; and Baker, Donal E., to Westinghouse Electric Corp. Bank selection in naturally commutated thyristor controlled static power converters. 4,295,190, Cl. 363-162.000.
- Stackpole Corporation, The: See—
Nystrom, William A.; Lanzel, Leo C.; and Bauer, William A., 4,294,438, Cl. 266-280.000.
- Stadler, Donald A.: See—
Furlet, James L.; and Stadler, Donald A., 4,294,347, Cl. 198-751.000.
- Stadler, Peter: See—
Voss, Eckart; Petersen, Uwe; and Stadler, Peter, 4,294,959, Cl. 536-17.00R.
- Stahan Corporation: See—
Stancil, Charles M., 4,294,157, Cl. 89-1.00G.
- Stalberg, Nils G.: See—
Enser, Mats A.; Hallberg, Lars O.; and Stalberg, Nils G., 4,295,121, Cl. 340-146.3MA.
- Stancil, Charles M., to Stahan Corporation. Projectile deployed cable weapons system. 4,294,157, Cl. 89-1.00G.
- Standard Oil Company: See—
Bremer, Noel J.; and Dria, Dennis E., 4,294,722, Cl. 252-435.000.
- Smith, Clay D.; and Keller, Douglas V., Jr., 4,294,695, Cl. 210-173.000.
- Standex International GmbH, Firma: See—
Werthmann, Wilfried, 4,294,650, Cl. 156-660.000.
- Stanley Works, The: See—
Whitehouse, Hugh L., 4,294,110, Cl. 73-862.230.
- Stas Societe Technique d'Accessoires Specialises S.A.: See—
Archer, Jean-Francois, 4,294,479, Cl. 294-82.00R.
- Stauber, Hans-Ulrich; and Eberle, Jurg, to Ferag AG. Universal joint-link chain. 4,294,345, Cl. 198-683.000.
- Stauffer Chemical Company: See—
Silberberg, Joseph, 4,294,752, Cl. 260-42.140.
- Wei, Chung H., 4,294,945, Cl. 526-74.000.
- Stecher, Gunther: See—
Maurer, Helmut; Muller, Klaus; Linder, Ernst; Rieger, Franz; and Stecher, Gunther, 4,294,679, Cl. 204-195.00S.
- Stedefeder, Joachim: See—
Hartmann, Juergen; Stedefeder, Joachim; Denzinger, Walter; and Pfohl, Sigberg, 4,294,873, Cl. 427-391.000.
- Steelhammer, Joe C.: See—
Polizzotti, David M.; and Steelhammer, Joe C., 4,294,588, Cl. 55-5.000.
- Steen, Adam; and Verhoog, Hendrik M., to Hoogovens Ijmuiden B.V. Method of providing and maintaining a wear-lining of a steel converter and a steel converter having such a lining. 4,294,431, Cl. 266-44.000.
- Stefanska, Barbara: See—
Falkowski, Leonard; Stefanska, Barbara; Zielinski, Jan; Troka, Elzbieta; Golik, Jerzy; Kolodziejczyk, Pawel; Jarzebski, Andrzej; Cybulska, Emilia; and Borowski, Edward, 4,294,958, Cl. 536-17.00R.
- Steffes, Paul: See—
Luckert, Lothar; Pohl, Christoph; Prohl, Carl-Erich; and Steffes, Paul, 4,294,102, Cl. 72-413.000.
- Steigerwald, Robert L., to General Electric Company. High gain latching Darlington transistor. 4,295,059, Cl. 307-253.000.
- Steinbrenner, Ulrich: See—
Hans, Waldmar; Sauer, Rudolf; Glockler, Otto; Steinbrenner, Ulrich; Gunther, Dieter; and Lembke, Manfred, 4,294,215, Cl. 123-470.000.
- Stephen C. Small: See—
Woodford, Thomas J., 4,294,238, Cl. 128-80.00G.
- Stephens, Donald E.; and Taylor, John T., to Beckman Instruments, Inc. Temperature regulating apparatus. 4,294,799, Cl. 422-62.000.
- Stepin, Anatoly L.: See—
Egorov, Viktor P.; Ognevsky, Viktor A.; Orlovsky, Anatoly G.; Ostrovsky, Grigory A.; Ryskind, Alexandr M.; Stepin, Anatoly L.; Trofimov, Oleg F.; and Shklyarov, Isaak N., 4,294,098, Cl. 72-128.000.
- Sterling Drug Inc.: See—
Farah, Alfred E., 4,294,840, Cl. 424-267.000.
- Leshner, George Y.; and Brundage, Ruth P., 4,294,836, Cl. 424-263.000.
- Leshner, George Y.; Opalka, Chester J., Jr.; and Page, Donald F., 4,294,837, Cl. 424-263.000.
- Margulies, Herman; and Kaufman, Richard H., 4,294,361, Cl. 206-532.000.
- Sternberg, Ben K.; Miller, Dale E.; and Bahjat, Dhari S., to Conoco, Inc. Electrode prospecting method providing calculable electromagnetic coupling for the indirect detection of hydrocarbon reservoirs. 4,295,096, Cl. 324-357.000.
- Stevens, John H.; and Reidel, Bruce A., to Kennecott Corporation. Pop up abrasive disc dispenser. 4,294,357, Cl. 206-409.000.
- Stewart, Charles W., Sr.: See—
Anolick, Colin; Robinson, Vivian M.; and Stewart, Charles W., Sr., 4,294,489, Cl. 297-452.000.
- Stewart, James W. Ice hole heater. 4,294,030, Cl. 43-4.000.
- Stiebel Eltron GmbH & Co. KG: See—
Reusch, Heinz; and Kreikenbohm, Robert, 4,294,310, Cl. 165-104.130.
- Stiftelsen Institute for Mikrovagsteknik vid Tekniska Hogskolan i Stockholm: See—
Henoch, Bengt; and Berglund, Eilert, 4,295,221, Cl. 375-23.000.
- Stilwell, Robert E.; and Westerling, David E., to FMC Corporation. Bin filling apparatus and method. 4,294,059, Cl. 53-448.000.

- Stimtech, Inc.: See—
Bussey, Joseph G., 4,294,245, Cl. 128-207.210.
- Stock, Albert M.; and Verbsky, James D., to Du Pont de Nemours, E. I., and Company. Process for the control of pH in the ethynylation of formaldehyde. 4,294,997, Cl. 568-855.000.
- Stockli, Andre; Castaneda, Fernando; and Stockli, Jean-Louis. Boots for aquatic activities. 4,294,022, Cl. 36-4.000.
- Stockli, Jean-Louis: See—
Stockli, Andre; Castaneda, Fernando; and Stockli, Jean-Louis, 4,294,022, Cl. 36-4.000.
- Stoddart, Barry: See—
Hardy, Frederick E.; and Stoddart, Barry, 4,294,711, Cl. 252-8.750.
- Stolecki, William E., to Electric Power Research Institute. Pipe coupling assembly especially suitable for use in the nuclear reactor. 4,294,472, Cl. 285-27.000.
- Stoll, Kurt. Piston for use in pneumatically operated piston-cylinder apparatus. 4,294,164, Cl. 92-243.000.
- Stolov, Michael. Image or picture projecting system using electronically controlled slides. 4,294,524, Cl. 353-84.000.
- Stolz, Manfred: See—
Hieber, Konrad; and Stolz, Manfred, 4,294,871, Cl. 427-237.000.
- Stone, Frederick C.; and Schupsky, Gary G., to Dow Chemical Company. The Method for preparing α -picoline from 5-oxohexanenitrile. 4,294,968, Cl. 546-251.000.
- Storz, Karl. Laryngoscope. 4,294,235, Cl. 128-11.000.
- Stoss, Peter; Satzinger, Gerhard; Herrmann, Manfred; and Heldt, Wolfgang. Certain heterocyclic sulfoximide derivatives. 4,294,838, Cl. 424-263.000.
- Stoutenburg, Donn V., to IRD Mechanalysis, Inc. Indicating apparatus, particularly for vibration analyzing equipment. 4,295,136, Cl. 340-753.000.
- Straat, Patricia A.: See—
Levin, Gilbert V.; and Straat, Patricia A., 4,294,931, Cl. 435-301.000.
- Strauss, Gary M., to Weyerhaeuser Company. Method and apparatus for counting small objects suspended in a liquid stream. 4,294,542, Cl. 356-339.000.
- Straw, David A.: See—
Miller, Edward C.; and Straw, David A., 4,294,373, Cl. 220-70.000.
- Strickler, Melvin D. Wood finger jointing apparatus. 4,294,647, Cl. 156-558.000.
- Striebach, Helmut, to Dr. Ing. h.c. F. Porsche Aktiengesellschaft. Drive assembly, especially for motor vehicles. 4,294,074, Cl. 60-616.000.
- Stritzl, Karl: See—
Svoboda, Josef; Wuerthner, Herbert; and Stritzl, Karl, 4,294,462, Cl. 280-634.000.
- Stuckert, Paul E., to International Business Machines Corporation. Method and apparatus for achieving secure password verification. 4,295,039, Cl. 235-380.000.
- Studien, Vance D., to Bofors America, Inc. Pressure transducer. 4,295,116, Cl. 338-4.000.
- Stumpp, Gerhard; and Wessel, Wolf, to Robert Bosch GmbH. Method and apparatus for correcting the fuel quantity in an internal combustion engine. 4,294,211, Cl. 123-379.000.
- Stupel Industries, Ltd.: See—
Dorsen, Mac; and Saltzman, Philip A., 4,294,299, Cl. 150-28.00R.
- Stutz, Hansruedi, to Gebruder Loepfe AG. Device for continuously measuring a transverse dimension of a thread-like structure. 4,294,545, Cl. 356-386.000.
- Su, Tien-Kuei, to Milliken Research Corporation. Shapeable thermoplastic resin composition containing cyclic acetal. 4,294,747, Cl. 260-37.00R.
- Subh, Naif T.: See—
Daugherty, Edgar E.; Jackson, Kenneth W.; Jones, Wesley W.; and Subh, Naif T., 4,295,005, Cl. 174-92.000.
- Sugahara, Hiroshi: See—
Uesaka, Tatsuo; Sugahara, Hiroshi; and Fujimura, Takeo, 4,295,110, Cl. 335-212.000.
- Sugahara, Syunji; and Morimoto, Takao, to Matsushita Electric Industrial Company, Limited. Automatic screwdriver. 4,294,142, Cl. 81-57.370.
- Sugano, Kazuhiko: See—
Iwanaga, Kazuyoshi; Sugano, Kazuhiko; and Ohtsuka, Kunio, 4,294,140, Cl. 74-868.000.
- Sugawara, Noboru: See—
Ito, Susumu; Sugawara, Noboru; and Amano, Sayoko, 4,294,890, Cl. 428-641.000.
- Sugii, Kisaburo: See—
Kinumaki, Toyosuke; Watanabe, Takehiko; Sugii, Kisaburo; and Iseki, Shigeo, 4,294,856, Cl. 426-7.000.
- Sugimoto, Eiji: See—
Tokoda, Saburo; Okumura, Koichiro; and Sugimoto, Eiji, 4,295,061, Cl. 307-279.000.
- Sugita, Toshio; Sakaguchi, Hiroaki; Tsuda, Hisanobu; and Suzuki, Tsuyoshi, to Mitsui-Nisso Corporation. Rapid curing polyurethane elastomer prepared from a diphenylmethanediisocyanate based liquid prepolymer and a curing agent containing a polytetramethylene ether glycol, a diol and an organometallic catalyst. 4,294,951, Cl. 528-55.000.
- Sugiura, Muneharu; and Sagara, Seiji, to Canon Kabushiki Kaisha. Slit illuminating device. 4,295,186, Cl. 362-217.000.
- Sukonick, Josef. Alignable electronic background grid generation system. 4,295,135, Cl. 340-734.000.
- Sullivan, Marc L.: See—
Kimball, Charles A.; and Sullivan, Marc L., 4,294,324, Cl. 180-89.140.
- Sumitomo Chemical Company, Limited: See—
Hino, Minoru; Oshima, Takao; Hayatsu, Kazuo; Yamamoto, Michio; and Yasui, Seimei, 4,294,940, Cl. 525-124.000.
- Sumitomo Electric Industries, Ltd.: See—
Ashida, Hiroshi; and Takahashi, Fumitake, 4,294,189, Cl. 118-603.000.
- Sumitomo Kinzoku Kogyo Kabushiki Kaisha: See—
Shiraiwa, Toshio; Yamaguchi, Hisao; and Matsumoto, Shigeaki, 4,294,118, Cl. 73-620.000.
- Sumitomo Naugatuck Co., Ltd.: See—
Minematsu, Hiroyuki; Matsumoto, Kojiro; Saeki, Tadashi; and Kishi, Akira, 4,294,946, Cl. 526-80.000.
- Sumiyoshi, Masaharu; Sekiya, Setsuro; Motosugi, Katsuhiko; Uozumi, Junzo; Ando, Tsuneo; Takeuchi, Yuzo; and Minoura, Mikio, to Aisan Industry Co., Ltd.; and Toyota Jidosha Kogyo Kabushiki Kaisha. Fuel supplying device for use in fuel injection type internal combustion engine. 4,294,213, Cl. 123-454.000.
- Summerhays, Brent: See—
Anderson, Kenneth W.; Summerhays, Brent; and Cazier, Verl O., 4,295,044, Cl. 250-229.000.
- Summers, Kenneth L.; and Rieke, Mahlon E., to Riche Corporation. Container closure device. 4,294,382, Cl. 222-529.000.
- Sumner, Kenneth E.: See—
Young, Dick K.; and Sumner, Kenneth E., 4,294,049, Cl. 52-20.000.
- Sun Oil Company of Pennsylvania: See—
Rugen, Donald F.; and Dickason, Alan F., 4,294,742, Cl. 260-31.80H.
- Sun Yao, Hwei Y.: See—
Yao, Shang J.; Sun Yao, Hwei Y.; and Wolfson, Sidney K., Jr., 4,294,891, Cl. 429-2.000.
- Suncor Inc.: See—
Morgan, George W., 4,294,183, Cl. 114-42.000.
- Sunden, Olof, to EKA AB. Surface-modified pigment of natural kaolin material and a process of producing same. 4,294,885, Cl. 428-404.000.
- Sung, Rodney L., to Texaco Inc. Novel fuel composition for internal combustion engine. 4,294,585, Cl. 44-53.000.
- Sunstein, Drew E. Programmable correlator. 4,295,204, Cl. 364-824.000.
- Superior Electric Company, The: See—
Leenhouts, Albert C., 4,295,083, Cl. 318-696.000.
- Suppa, Vito; and Viallet, Daniel, to Thomson-CSF. Inertially released jettisonable airborne buoy. 4,295,211, Cl. 367-4.000.
- Sutter, David L., to Hussey Manufacturing Co., Inc. Apparatus for supporting pivotally mounted seats. 4,294,048, Cl. 52-9.000.
- Suzuki, Hidetsugu: See—
Tanaka, Mitsuaki; and Suzuki, Hidetsugu, 4,295,006, Cl. 179-1.00E.
- Suzuki, Katsunori: See—
Nagase, Hiroshi; Okuyama, Toshiaki; Kubota, Yuzuru; and Suzuki, Katsunori, 4,295,084, Cl. 318-719.000.
- Suzuki, Osamu: See—
Takahisa, Shuji; Suzuki, Osamu; and Shibano, Michio, 4,294,067, Cl. 57-274.000.
- Suzuki, Seiko: See—
Takahashi, Minoru; Tanigami, Takahiko; Uchiyama, Kaoru; Minorikawa, Hitoshi; Nishihara, Motohisa; Kawakami, Kanji; Suzuki, Seiko; Hachino, Hiroaki; and Misawa, Yutaka, 4,295,115, Cl. 338-4.000.
- Suzuki, Tsuyoshi: See—
Sugita, Toshio; Sakaguchi, Hiroaki; Tsuda, Hisanobu; and Suzuki, Tsuyoshi, 4,294,951, Cl. 528-55.000.
- Suzuki, Yoshiki; Ikura, Hiroshi; Yamashita, Gentaro; and Nagai, Tsuneji, to Teijin Limited. Powder pharmaceutical composition and powder preparation for application to the nasal mucosa, and method for administration thereof. 4,294,829, Cl. 424-241.000.
- Svenska Kassaregister AB: See—
Mattsson, Mats E., 4,294,554, Cl. 400-320.000.
- Svoboda, Josef; Krob, Erwin; and Weigl, Erwin, to TMC Corporation. Ski brake. 4,294,459, Cl. 280-605.000.
- Svoboda, Josef; Wuerthner, Herbert; and Stritzl, Karl, to TMC Corporation. Spring locking device. 4,294,462, Cl. 280-634.000.
- Swart, Petrus H. Gear ratio selection apparatus. 4,294,341, Cl. 192-0.073.
- Swartz, Robert V. Internal combustion engines. 4,294,201, Cl. 123-73.00R.
- Sweetheart Plastics, Inc.: See—
Davis, Paul, 4,294,371, Cl. 220-4.00E.
- Swenson, Richard C., to United States of America, Navy. Linear acoustic array. 4,295,212, Cl. 367-20.000.
- Syntex (U.S.A.) Inc.: See—
Harris, George S., 4,294,844, Cl. 424-273.00R.
- Szeliga, Philip C., to Foam Controls, Inc. Flow control apparatus. 4,294,277, Cl. 137-101.190.
- Szente, Andre: See—
Fischli, Albert E.; and Szente, Andre, 4,294,758, Cl. 260-239.30D.
- Szvoboda, Gyorgy: See—
Alfoldi, Lajos; Balint nee Fodor, Katalin; Kari, Csaba; Torok, Istvan; Svoboda, Gyorgy; Lang, Tibor; Gado, Istvan; and Ambrus, Gabor, 4,294,927, Cl. 435-172.000.
- Szyszkowski, Adam; Moreau, Marc; and Priester, Pierre, to Trefime-taux. Drawn rods made of lead brass and a process for the thermal treatment thereof. 4,294,629, Cl. 148-11.50C.
- T/Drill, Inc.: See—
Kemme, Wendell J., 4,294,011, Cl. 30-106.000.
- Tabata, Yoneho: See—
Matsuda, Osamu; Watanabe, Terutaka; Tabata, Yoneho; and Machi, Suet, 4,294,675, Cl. 204-159.140.

- Taboada, John: See—
Altschuler, Bruce R.; Taboada, John; and Altschuler, Martin D., 4,294,544, Cl. 356-376.000.
- Tachikara Kabushiki Kaisha: See—
Takazawa, Kazuyasu, 4,294,793, Cl. 264-311.000.
- Tadewald, Thomas D., to UOP Inc. Heater assembly and method of forming same. 4,294,643, Cl. 156-293.000.
- Taga, Genji; Oikawa, Teruo; and Watanabe, Yoshiaki, to Tokuyama Soda Kabushiki Kaisha. Alkali calcium silicates and process for preparation thereof. 4,294,810, Cl. 423-331.000.
- Taguchi, Yoshinobu: See—
Takahashi, Tetsuo; Taguchi, Yoshinobu; Harigane, Kotaro; Ito, Tetsuro; and Kato, Akihiro, 4,294,000, Cl. 29-564.600.
- Tai-Her, Yang. Audio-visual disaster alert system. 4,295,130, Cl. 340-524.000.
- Takagi, Kazuhiro: See—
Kubota, Michio; Takagi, Kazuhiro; and Mitani, Yorisama, 4,294,632, Cl. 148-142.000.
- Takago, Toshio; Arai, Masatoshi; and Futatsumori, Koji, to Shin-Etsu Chemical Co. Ltd. Hydroalkenylsiloxanes. 4,294,975, Cl. 556-482.000.
- Takahara, Yoshiyuki; Hirose, Yoshiteru; Takeuchi, Yoko; Murai, Asao; Kainosho, Masatsune; and Murao, Sawao, to Ajinomoto Company, Incorporated. Ring peptide antibiotics, Permetin A and a process for producing the same. 4,294,754, Cl. 260-112.50R.
- Takahashi, Fumitake: See—
Ashida, Hiroshi; and Takahashi, Fumitake, 4,294,189, Cl. 118-603.000.
- Takahashi, Minoru; Tanigami, Takahiko; Uchiyama, Kaoru; Minorikawa, Hitoshi; Nishihara, Motohisa; Kawakami, Kanji; Suzuki, Seiko; Hachino, Hiroaki; and Misawa, Yutaka, to Hitachi, Ltd. Semiconductor absolute pressure transducer assembly and method. 4,295,115, Cl. 338-4.000.
- Takahashi, Nagashige, to Kabushiki Kaisha Medos Kenkyusho. Slack absorbing device for an endoscope. 4,294,233, Cl. 128-4.000.
- Takahashi, Sankichi: See—
Sawa, Toshio; Kubota, Masayoshi; Takahashi, Sankichi; and Kaneko, Toyohiko, 4,294,697, Cl. 210-221.100.
- Takahashi, Susumu, to Kanto Yakin Kogyo Kabushiki Kaisha. Furnace with protective atmosphere for heating metals. 4,294,436, Cl. 266-257.000.
- Takahashi, Tetsuo; Taguchi, Yoshinobu; Harigane, Kotaro; Ito, Tetsuro; and Kato, Akihiro, to Tokyo Denki Kogaku Kogyo Kabushiki Kaisha. Machine for inserting electronic components. 4,294,000, Cl. 29-564.600.
- Takahashi, Yuu, to Aida Engineering, Ltd. Roll feed device for feeding material to a press. 4,294,170, Cl. 100-216.000.
- Takahisa, Shuji; Suzuki, Osamu; and Shibano, Michio, to Kabushiki Kaisha Toyoda Jidoshokki Seisakusho. Method and apparatus for doffing and donning bobbins in a spinning machine. 4,294,067, Cl. 57-274.000.
- Takasaki, Toshio: See—
Kanai, Isamu; Okubo, Shigeki; Tsuchiya, Kazuo; and Takasaki, Toshio, 4,294,475, Cl. 285-165.000.
- Takase, Yosio: See—
Kashima, Isao; Mishina, Masami; Takase, Yosio; and Maruchi, Katsumi, 4,295,017, Cl. 200-47.000.
- Takashima, Yuji; Ishida, Eisuke; Nishiguchi, Hisanori; and Yoshino, Kimiaki, to Matsushita Electric Industrial Co., Ltd. Image formation method having translucent particles containing a coloring agent and a colorless dye former. 4,294,902, Cl. 430-45.000.
- Takasugi, Hisashi: See—
Takaya, Takao; Takasugi, Hisashi; Chiba, Toshiyuki; and Tsuji, Kiyoshi, 4,294,960, Cl. 544-22.000.
- Takaya, Takao; Takasugi, Hisashi; Chiba, Toshiyuki; and Tsuji, Kiyoshi, to Fujisawa Pharmaceutical Co., Ltd. 7-[2-(2-Aminothiazol-4-yl)-2-cyclopentyl-oxyminoacetamido]-3-cephem-4-carboxylic acid (synisomer). 4,294,960, Cl. 544-22.000.
- Takazawa, Kazuyasu, to Tachikara Kabushiki Kaisha. Method and apparatus for manufacturing a spherical hollow body. 4,294,793, Cl. 264-311.000.
- Takeda Chemical Industries, Ltd.: See—
Asai, Mitsuko, 4,294,757, Cl. 260-239.30P.
- Takeda, George: See—
Ideta, Yasufumi; Takeda, George; and Watanabe, Shoji, 4,294,160, Cl. 91-378.000.
- Takemoto, Iwao; Koike, Norio; Ohba, Shinya; Ando, Haruhisa; Nakai, Masaaki; Hanamura, Syoji; Izawa, Ryuichi; Kubo, Masaharu; Aoki, Masakazu; and Tanaka, Shuhei, to Hitachi, Ltd.; and Hitachi Denshi Kabushiki Kaisha. Circuit for generating scanning pulses. 4,295,055, Cl. 307-221.00C.
- Takeuchi, Shigeo. Apparatus for mixing and baking of bread. 4,294,166, Cl. 99-348.000.
- Takeuchi, Yoko: See—
Takahara, Yoshiyuki; Hirose, Yoshiteru; Takeuchi, Yoko; Murai, Asao; Kainosho, Masatsune; and Murao, Sawao, 4,294,754, Cl. 260-112.50R.
- Takeuchi, Yoshiyuki: See—
Enomoto, Minoru; Yoneda, Takao; and Takeuchi, Yoshiyuki, 4,294,045, Cl. 51-165.710.
- Takeuchi, Yuzo: See—
Sumiyoshi, Masaharu; Sekiya, Setsuro; Motosugi, Katsuhiko; Uozumi, Junzo; Ando, Tsuneco; Takeuchi, Yuzo; and Minoura, Mikio, 4,294,213, Cl. 123-454.000.
- Takezhanov, Sauk T.: See—
Vanjukov, Andrei V.; Mechev, Valery V.; Bystrov, Valentin P.; Ezhov, Evgeny I.; Vasiliev, Mikhail G.; Zaitsev, Vladimir Y.; Romenets, Vladimir A.; Ivanov, Vladimir V.; Golik, Sergei Y.; Grin-Gnatovsky, Evgeny S.; Grechko, Alexandr V.; Savin, Ivan V.; Kozhakhmetov, Sultanbek M.; Meierovich, Veniamin B.; Nagibin, Vladimir D.; Ramazanov, Nariman A.; Umarov, Almas B.; Ziberov, Valentin E.; Kunaev, Askar M.; Takezhanov, Sauk T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazheev, Dzhonson T., 4,294,433, Cl. 266-161.000.
- Takita, Hitoshi; Mukaida, Yutaka; and Enomoto, Satoru, to Kureha Kagaku Kogyo Kabushiki Kaisha. Process for preparing a normal long chain alkanolic acid. 4,294,770, Cl. 260-413.000.
- Tallon, Jacques: See—
Gevaud, Roland; and Tallon, Jacques, 4,294,106, Cl. 73-40.700.
- Tamas, Istvan; Tamas, Lajos; Kiss, Gyula; Kiss, Jozsef; and Kaldor, Antal, to Vasipari Kutato Intezet. Process and apparatus for reducing the inclusion content of steels and for refining their structure. 4,294,611, Cl. 75-49.000.
- Tamas, Lajos: See—
Tamas, Istvan; Tamas, Lajos; Kiss, Gyula; Kiss, Jozsef; and Kaldor, Antal, 4,294,611, Cl. 75-49.000.
- Tameo, Robert P., to United States of America, Navy. Turbomachine balance correction system. 4,294,135, Cl. 74-573.00R.
- Tamiya, Katsunori: See—
Kimoto, Yasuo; Tamiya, Katsunori; Honda, Shoichi; Maehata, Hidehiko; and Kamada, Hiroshi, 4,294,673, Cl. 204-129.460.
- Tamm, Rolf: See—
Tomoff, Toma; Chlosta, Wolfgang; Henninger, Heinz; Tamm, Rolf; and Grossmann, Klaus, 4,294,126, Cl. 73-864.210.
- Tamony, Andree E.; and Youngson, Charles R., Jr., to Dow Chemical Company, The. Denitrification of a gas stream. 4,294,928, Cl. 423-235.000.
- Tamura, Shoichi: See—
Abe, Kazunobu; Tamura, Shoichi; and Nakatsuji, Tadao, 4,294,806, Cl. 423-239.000.
- Tanabe Seiyaku Co., Ltd.: See—
Yoneda, Naoto; Kato, Jyoji; and Kinashi, Keizo, 4,294,832, Cl. 424-258.000.
- Tanabe, Takeshi, to Sharp Kabushiki Kaisha. Combination of gas sensor controlled cooking utensil and gas leak alarm. 4,295,028, Cl. 219-10.55B.
- Tanaka, Mitsuaki; and Suzuki, Hidetsugu, to Victor Company of Japan, Limited. Speaker system. 4,295,006, Cl. 179-1.00E.
- Tanaka, Shigeo: See—
Shima, Ichiji; Yamamoto, Tatsuo; Yoshibayashi, Shigeru; Teshima, Hiroshi; Hizume, Akio; Iki, Tetsuo; Yamamoto, Takashi; Kanamori, Kyozo; and Tanaka, Shigeo, 4,294,120, Cl. 73-650.000.
- Tanaka, Shuhei: See—
Takemoto, Iwao; Koike, Norio; Ohba, Shinya; Ando, Haruhisa; Nakai, Masaaki; Hanamura, Syoji; Izawa, Ryuichi; Kubo, Masaharu; Aoki, Masakazu; and Tanaka, Shuhei, 4,295,055, Cl. 307-221.00C.
- Tanigami, Takahiko: See—
Takahashi, Minoru; Tanigami, Takahiko; Uchiyama, Kaoru; Minorikawa, Hitoshi; Nishihara, Motohisa; Kawakami, Kanji; Suzuki, Seiko; Hachino, Hiroaki; and Misawa, Yutaka, 4,295,115, Cl. 338-4.000.
- Taniguchi, Eiji; Akagi, Susumu; and Torimitsu, Seiichi, to Toray Industries, Inc. Coating composition. 4,294,939, Cl. 525-118.000.
- Tanihara, Yoshiaki: See—
Nouda, Hiroshi; Tanihara, Yoshiaki; Ikeda, Takashi; and Ogiuchi, Ituo, 4,294,791, Cl. 264-210.200.
- Tanner, Robert M., to University of California, Regents of the. Error-correcting coding system. 4,295,218, Cl. 371-40.000.
- Taricco, Stefano, to Centro Ricerche Fiat S.p.A. Process for the reduction of iron oxide. 4,294,609, Cl. 75-34.000.
- Taverez, Dan. Air-filter apparatus in combination with a turbine engine. 4,294,596, Cl. 55-242.000.
- Tavlarides, Lawrence L.; Freeman, Robert W.; and Hsia, Alexander M. Liquid jet recycle reactor. 4,294,800, Cl. 422-68.000.
- Taylor, John T.: See—
Stephens, Donald E.; and Taylor, John T., 4,294,799, Cl. 422-62.000.
- Taylor, Lloyd D.: See—
Bronstein-Bonte, Irena Y.; Lindholm, Edward P.; and Taylor, Lloyd D., 4,294,907, Cl. 430-213.000.
- TBA Industrial Products Limited: See—
Thornley, Harry, 4,294,790, Cl. 264-171.000.
- Teige, Wolfgang: See—
Papenfus, Theodor; and Teige, Wolfgang, 4,294,749, Cl. 260-40.00P.
- Teijin Limited: See—
Nouda, Hiroshi; Tanihara, Yoshiaki; Ikeda, Takashi; and Ogiuchi, Ituo, 4,294,791, Cl. 264-210.200.
- Tekma Kinomat S.p.A.: See—
Camardella, Giuseppe, 4,294,417, Cl. 242-149.000.
- Teldix GmbH: See—
Sindlinger, Rainer; and Hammer, Josef, 4,294,493, Cl. 308-10.000.
- Telecommunications Radioelectriques et Telephoniques: See—
Van Uffelen, Jean-Pierre H., 4,295,222, Cl. 375-106.000.
- Teledyne Industries, Inc.: See—
Kotecki, Damian J., 4,294,614, Cl. 75-128.00A.
- Telemetry Controls, Inc.: See—
Wilson, Worley C., 4,295,191, Cl. 364-104.000.

- Tencza, Thomas M., to Bristol-Myers Company. Alkaline analgesic capsule. 4,294,819, Cl. 424-14.000.
- Tennigkeit, Jurgen: See—
Lorenz, Heribert; and Tennigkeit, Jurgen, 4,294,293, Cl. 141-100.000.
- Tennyson, Richard P., to Munters Corporation. Method for operating a coke quench tower scrubber system. 4,294,663, Cl. 201-39.000.
- Terada, Soichiro: See—
Ikeda, Tatsuhiko; and Terada, Soichiro, 4,294,707, Cl. 210-782.000.
- Terumo Corporation: See—
Ikeda, Tatsuhiko; and Terada, Soichiro, 4,294,707, Cl. 210-782.000.
- Terzian, Rouben T., to Marvin Glass & Associates. Animated talking doll. 4,294,033, Cl. 46-118.000.
- Teshima, Hiroshi: See—
Shima, Ichiji; Yamamoto, Tatsuo; Yoshibayashi, Shigeru; Teshima, Hiroshi; Hizume, Akio; Iki, Tetsuo; Yamamoto, Takashi; Kanamori, Kyozo; and Tanaka, Shigeo, 4,294,120, Cl. 73-650.000.
- Tetra Pak International AB: See—
Martensson, Kjell H., 4,294,362, Cl. 206-622.000.
- Tetsuo, Tanaka: See—
Issei, Katsuta; and Tetsuo, Tanaka, 4,294,665, Cl. 203-50.000.
- Tevopharm-Schiedam B.V.: See—
van Maanen, Johannes D., 4,294,344, Cl. 198-461.000.
- Texaco, Inc.: See—
Sequeira, Avilino, Jr.; Smith, Benjamin F., Jr.; and Mead, Theodore C., 4,294,689, Cl. 208-326.000.
- Sung, Rodney L., 4,294,585, Cl. 44-53.000.
- Texas Instruments Incorporated: See—
Chang, Richard R.; Frantz, Gene A.; and Hawkins, William R., 4,295,181, Cl. 361-395.000.
- Gottbrecht, Tom L.; and Shepherd, Glen C., 4,293,987, Cl. 29-25.420.
- Kuo, Chang-Kiang, 4,294,001, Cl. 29-571.000.
- Schmidt, Gary D.; Norris, Jerry L.; and Weirauch, Donald F., 4,295,102, Cl. 331-65.000.
- Textron, Inc.: See—
Moertel, George B., 4,293,994, Cl. 29-409.000.
- Thatcher, Gordon: See—
Humphreys, Peter; Davidson, Daniel F.; and Thatcher, Gordon, 4,294,658, Cl. 376-404.000.
- Thayer, Paul M., to Water Pollution Control Corporation. Swing diffuser. 4,294,696, Cl. 210-220.000.
- Theodor Groz & Sohne & Ernst Beckert Nadelfabrik Commandit-Gesellschaft: See—
Mayer, Harald; and Berentzen, Harde, 4,294,086, Cl. 66-121.000.
- Thettu, Raghulinga R., to Xerox Corporation. Document belt vacuum manifold. 4,294,540, Cl. 355-76.000.
- Theurer, Josef; and Riessberger, Klaus, to Franz Plasser Bahnbaumaschinen-Industriegesellschaft m.b.H. Mobile machines for removing surface irregularities from rail heads. 4,294,041, Cl. 51-5.00C.
- Thiboutot, Robert, to Les Entreprises Rotot Ltee. Collapsible support device for a folding sled. 4,294,457, Cl. 280-20.000.
- Thiere, Helmut; and Vallentin, Werner, to Siemens Aktiengesellschaft. Corrugated horn radiator. 4,295,142, Cl. 343-781.00A.
- Thill, Gary A., to Minnesota Mining and Manufacturing Company. Perforated closed cell padding material. 4,294,240, Cl. 128-156.000.
- Thir, Basil: See—
Newkirk, David D.; Login, Robert B.; and Thir, Basil, 4,294,944, Cl. 525-423.000.
- Thomas & Betts Corporation: See—
Logan, Maurus C., 4,294,512, Cl. 350-96.200.
- Thomas C. Elder, Inc.: See—
Kaufman, Kurt D., 4,294,822, Cl. 424-59.000.
- Kaufman, Kurt D., 4,294,847, Cl. 424-279.000.
- Thomas, Richard C.; Pegler, Stewart M.; and Cordes, Paul B., to British Gas Corporation. Apparatus and method for detecting the location of metallic objects having alternating current passing therethrough. 4,295,095, Cl. 324-326.000.
- Thomas, Rudolf: See—
Schmidt, Robert R.; and Thomas, Rudolf, 4,294,607, Cl. 71-92.000.
- Thomasson, Harry V.: See—
Kunstlicher, Erich; and Thomasson, Harry V., 4,294,421, Cl. 248-37.600.
- Thome, Roland: See—
Krugler, Jorg; Thome, Roland; Moritz, Dieter; Bings, Hubert; and Losert, Herbert, 4,294,816, Cl. 423-484.000.
- Thominet, Michel; Acher, Jacques; and Monier, Jean-Claude, to Societe d'Etudes Scientifiques et Industrielles de l'Ile de France. New derivatives of 4-amino-5-alkyl sulphonyl orthoanisamides, methods of preparing them and their application as psychotropic agents. 4,294,828, Cl. 424-232.000.
- Thompson, Arthur H.; and Ballester, Ricardo H., to Thompson, Arthur H. Battery capacity measuring method and apparatus. 4,295,097, Cl. 324-429.000.
- Thompson, Charles W.: See—
Gerboth, Patrick L.; and Thompson, Charles W., 4,294,082, Cl. 62-244.000.
- Thompson, David A.: See—
Romankiw, Lubomir T.; and Thompson, David A., 4,295,173, Cl. 360-125.000.
- Thompson, John P.: See—
Mosse, Barbara; and Thompson, John P., 4,294,037, Cl. 47-59.000.
- Thompson, Morice: See—
Bentley, John; and Thompson, Morice, 4,294,735, Cl. 260-22.00CB.
- Thompson, Raymond V.; Todd, Alan; and Constantine, Albert B., to Dynatrol Consultants (U.K.) Limited. Mixing apparatus. 4,294,549, Cl. 366-164.000.
- Thomson; Robert B., to Rockwell International Corporation. Ultrasonic shear wave transducer. 4,295,214, Cl. 367-140.000.
- Thomson-CSF: See—
Chehovah, Felix, 4,294,551, Cl. 400-119.000.
- Suppa, Vito; and Viallet, Daniel, 4,295,211, Cl. 367-4.000.
- Thornley, Harry, to TBA Industrial Products Limited. Manufacture of sheet material. 4,294,790, Cl. 264-171.000.
- Thurles, Edmond; Vernat, Pierre; and Sauvat, Roger, to Delle-Alstom. Gas-blast circuit-breaker. 4,295,023, Cl. 200-148.00R.
- Timberlake, John F.: See—
Henson, Thomas R.; and Timberlake, John F., 4,294,774, Cl. 260-453.00P.
- Time Commercial Financing Corporation: See—
Kimball, Charles A.; and Sullivan, Marc L., 4,294,324, Cl. 180-89.140.
- Times Fiber Communications, Inc.: See—
Dabby, Franklin W.; and Chesler, Ronald B., 4,294,601, Cl. 65-3.120.
- Timex Corporation: See—
Jakubek, John, 4,294,517, Cl. 350-345.000.
- TMC Corporation: See—
Svoboda, Josef; Krob, Erwin; and Weigl, Erwin, 4,294,459, Cl. 280-605.000.
- Svoboda, Josef; Wuerthner, Herbert; and Stritzl, Karl, 4,294,462, Cl. 280-634.000.
- Toben, Bernhard: See—
Doerk, Klaus; Koch, Klaus; Banke, Horst; and Toben, Bernhard, 4,294,947, Cl. 526-119.000.
- Tobler, Hans; Fory, Werner; and Schurter, Rolf, to Ciba-Geigy Corporation. Novel N-phenyl-substituted N-heterocyclic compounds, their preparation and use in agents for regulating plant growth. 4,294,606, Cl. 71-88.000.
- Toda, Hideo: See—
Kihara, Kunio; Toda, Hideo; Yasukawa, Eiki; Ishibashi, Toshiaki; and Tokita, Taketoshi, 4,294,933, Cl. 521-27.000.
- Todd, Alan: See—
Thompson, Raymond V.; Todd, Alan; and Constantine, Albert B., 4,294,549, Cl. 366-164.000.
- Todokoro, Hideo; and Sakitani, Yoshio, to Hitachi, Ltd. Field emission electron gun with anode heater and plural exhausts. 4,295,072, Cl. 313-7.000.
- Todt, Gerhard H., to Buro Patent A.G. Vehicle system with speed-responsive stop. 4,294,174, Cl. 104-250.000.
- Toeppen, Thurston H. Threaded closure and container. 4,294,370, Cl. 215-329.000.
- Tokai Regional Fisheries Research Laboratory: See—
Kinumaki, Toyosuke; Watanabe, Takehiko; Sugii, Kisaburo; and Iseki, Shigeo, 4,294,856, Cl. 426-7.000.
- Tokico Ltd.: See—
Amemori, Hiroyuki; and Yamada, Masao, 4,294,123, Cl. 73-861.920.
- Tokita, Taketoshi: See—
Kihara, Kunio; Toda, Hideo; Yasukawa, Eiki; Ishibashi, Toshiaki; and Tokita, Taketoshi, 4,294,933, Cl. 521-27.000.
- Tokoda, Saburo; Okumura, Koichiro; and Sugimoto, Eiji, to Nippon Electric Co., Ltd. Latch circuit. 4,295,061, Cl. 307-279.000.
- Tokuyama Soda Kabushiki Kaisha: See—
Onoue, Yasuharu; Sata, Toshikatsu; Nakahara, Akihiko; and Itoh, Junichi, 4,294,943, Cl. 525-358.000.
- Taga, Genji; Oikawa, Teruo; and Watanabe, Yoshiaki, 4,294,810, Cl. 423-331.000.
- Tokyo Denki Kogaku Kogyo Kabushiki Kaisha: See—
Takahashi, Tetsuo; Taguchi, Yoshinobu; Harigane, Kotaro; Ito, Tetsuro; and Kato, Akihiro, 4,294,000, Cl. 29-564.600.
- Tokyo Electric Co., Ltd.: See—
Nishiyama, Yoshihisa, 4,294,322, Cl. 177-210.00R.
- Tokyo Sanyo Electric: See—
Yoshii, Kazuhiro, 4,294,076, Cl. 62-235.100.
- Tokyo Shibaura Denki Kabushiki Kaisha: See—
Mitani, Akio; Sakamoto, Moriyoichi; and Murasaki, Hiroaki, 4,294,081, Cl. 62-140.000.
- Otsuka, Kenichi; and Hosokawa, Yorio, 4,295,079, Cl. 315-130.000.
- Tokyo Shibaura Electric Co., Ltd.: See—
Zushi, Sadao; and Oida, Yoshio, 4,295,027, Cl. 219-10.55B.
- Tokyo Yogyo Kabushiki Kaisha: See—
Sawada, Hajimu; and Inubushi, Hisao, 4,294,437, Cl. 266-272.000.
- Tom, Milton D. Apparatus for producing and dispensing detergent solutions. 4,294,280, Cl. 137-268.000.
- Tomcavage, Joseph R.: See—
Carter, Don R.; Doner, Claude E.; Hammersand, Fred G.; and Tomcavage, Joseph R., 4,295,077, Cl. 313-293.000.
- Tominaga, Tamotsu: See—
Toriumi, Takeshi; and Tominaga, Tamotsu, 4,294,390, Cl. 226-181.000.
- Tomoff, Toma; Chlosta, Wolfgang; Henninger, Heinz; Tamm, Rolf; and Grossmann, Klaus, to Bodenseewerk Perkin-Elmer & Co., GmbH. Sample feeding device. 4,294,126, Cl. 73-864.210.
- Tomoff, Toma, to Bodenseewerk Perkin-Elmer & Co., GmbH. Automatic sample feeder for flameless atomic absorption spectrometer. 4,294,127, Cl. 73-864.210.
- Tomogane, Teruhisa: See—
Ueno, Toshihiko; and Tomogane, Teruhisa, 4,294,712, Cl. 252-12.000.

- Tomuro, Jinichi: See—
Uchida, Seiichi; Satomi, Yoshihito; Kiuchi, Norihiro; Yamagata, Takeo; Yoshioka, Susumu; Miyamoto, Tomohiko; and Tomuro, Jinichi, 4,294,803, Cl. 422-111.000.
- Toray Industries, Inc.: See—
Taniguchi, Eiji; Akagi, Susumu; and Torimitsu, Seiichi, 4,294,939, Cl. 525-118.000.
- Tordella, Joseph R.: Van platform with lockable ramp, 4,294,571, Cl. 414-537.000.
- Torimitsu, Seiichi: See—
Taniguchi, Eiji; Akagi, Susumu; and Torimitsu, Seiichi, 4,294,939, Cl. 525-118.000.
- Toriumi, Takeshi; and Tominaga, Tamotsu, to Hitachi Denshi Kabushiki Kaisha. Pinch roller mechanism, 4,294,390, Cl. 226-181.000.
- Toro Company, The: See—
Granger, Bruce A.; and Klis, David S., 4,294,339, Cl. 192-12.0BA.
- Torok, Istvan: See—
Alfoldi, Lajos; Balint nee Fodor, Katalin; Kari, Csaba; Torok, Istvan; Szvoboda, Gyorgy; Lang, Tibor; Gado, Istvan; and Ambrus, Gabor, 4,294,927, Cl. 435-172.000.
- Totman, Mirrel L., to Totman Seal Nut, Inc. Flanged joint sealing nut, 4,294,275, Cl. 137-15.000.
- Totman, Mirrel L.: See—
Totman, Mirrel L., 4,294,275, Cl. 137-15.000.
- Tottori Sanyo Electric Co., Ltd.: See—
Iwata, Mitsuo; Wada, Hajime; Iwasa, Tomoyuki; and Tsuchino, Kunio, 4,295,169, Cl. 360-71.000.
- Towae, Friedrich: See—
Merger, Franz; and Towae, Friedrich, 4,294,971, Cl. 548-226.000.
- Toyo Rubber Industry Co., Ltd., The: See—
Nishida, Masazo, 4,294,880, Cl. 428-315.000.
- Toyoda Koki Kabushiki Kaisha: See—
Enomoto, Minoru; Yoneda, Takao; and Takeuchi, Yoshiyuki, 4,294,045, Cl. 51-165.710.
- Toyota, Akinori; Yoshitugu, Ken; and Kashiwa, Norio, to Mitsui Petrochemical Industries Ltd. Process for preparing olefin polymers or copolymers, and catalyst for use in said process, 4,294,948, Cl. 526-125.000.
- Toyota Jidosha Kogyo Kabushiki Kaisha: See—
Aoki, Kenji, 4,294,212, Cl. 123-440.000.
- Kinaga, Eiichi; and Mori, Mamoru, 4,294,468, Cl. 280-807.000.
- Mori, Keiji; and Kurimoto, Kyoichi, 4,294,134, Cl. 74-547.000.
- Ohumi, Takeharu, 4,294,286, Cl. 137-625.480.
- Sumiyoshi, Masaharu; Sekiya, Setsuro; Motosugi, Katsuhiko; Uozumi, Junzo; Ando, Tsuneo; Takeuchi, Yuzo; and Minoura, Mikio, 4,294,213, Cl. 123-454.000.
- Ueda, Masahiro, 4,294,896, Cl. 429-86.000.
- Tractel S.A.: See—
Desplats, Andre, 4,294,429, Cl. 254-272.000.
- Tracy, David J.; Wood, Lindley S.; and Chakrabarti, Paritosh M., to GAF Corporation. Thiocyanate-containing polyoxyalkylenes, 4,294,848, Cl. 424-302.000.
- Trautner, Johann G., to Bentley Alemannia Limited. Flat bed knitting machines, 4,294,085, Cl. 66-75.100.
- Trefimetaux: See—
Szyzkowski, Adam; Moreau, Marc; and Priester, Pierre, 4,294,629, Cl. 148-11.50C.
- Treible, Edwin S.; Dopkin, Joseph A.; and Alford, Raymond N., to Ingersoll-Rand Co. Engine combustion control system, 4,294,214, Cl. 123-458.000.
- Trico Products Corporation: See—
Gowans, Neil A.; and Riester, William C., 4,293,974, Cl. 15-250.320.
- Trofimov, Oleg F.: See—
Egorov, Viktor P.; Ognevsky, Viktor A.; Orlovsky, Anatoly G.; Ostrovsky, Grigory A.; Ryskind, Alexandr M.; Stepin, Anatoly L.; Trofimov, Oleg F.; and Shklyarov, Isaak N., 4,294,098, Cl. 72-128.000.
- Troka, Elzbieta: See—
Falkowski, Leonard; Stefanska, Barbara; Zielinski, Jan; Troka, Elzbieta; Golik, Jerzy; Kolodziejczyk, Pawel; Jarzebski, Andrzej; Cybulska, Emilia; and Borowski, Edward, 4,294,958, Cl. 536-17.00R.
- Truesdell, Raymond L., and Ross, Michael D., to RCA Corporation. Apparatus for measuring the characteristics of a wideband electromechanical recording system having a transformer, 4,295,216, Cl. 369-55.000.
- Trutzschler GmbH & Co. KG: See—
Marx, Herr J., 4,293,982, Cl. 19-80.00A.
- Tsuchino, Kunio: See—
Iwata, Mitsuo; Wada, Hajime; Iwasa, Tomoyuki; and Tsuchino, Kunio, 4,295,169, Cl. 360-71.000.
- Tsuchiya, Kazuo: See—
Kanai, Isamu; Okubo, Shigeki; Tsuchiya, Kazuo; and Takasaki, Toshio, 4,294,475, Cl. 285-165.000.
- Tsuda, Hisanobu: See—
Sugita, Toshio; Sakaguchi, Hiroaki; Tsuda, Hisanobu; and Suzuki, Tsuyoshi, 4,294,951, Cl. 528-55.000.
- Tsui, Kwok W., to Arco Industries Ltd. Toy cash register, 4,295,036, Cl. 235-1.00E.
- Tsuji, Kiyoshi: See—
Takaya, Takao; Takasugi, Hisashi; Chiba, Toshiyuki; and Tsuji, Kiyoshi, 4,294,960, Cl. 544-22.000.
- Tsujii, Sadahiko: See—
Sato, Yasuhisa; Tsujii, Sadahiko; and Ishikawa, Kazuo, 4,294,529, Cl. 354-53.000.
- Tsujino, Nobuyuki; and Hirano, Shigeo, to Fuji Photo Film Co., Ltd. Direct positive silver halide light-sensitive material, 4,294,919, Cl. 430-559.000.
- Tucker, Alfred D., to Reed Irrigation Systems Pty Ltd. In-line tube junctions, 4,294,470, Cl. 285-5.000.
- Tuell Industries, Inc.: See—
Tuell, James L.; and Wahnschaff, Paul, 4,294,456, Cl. 280-11.280.
- Tuell, James L.; and Wahnschaff, Paul, to Tuell Industries, Inc. Pivotal ball skate, 4,294,456, Cl. 280-11.280.
- Tull, Roger J.; Weinstock, Leonard M.; and Shinkai, Ichiro, to Merck & Co., Inc. Method of preparing 2,4-difluoroaniline, 4,294,988, Cl. 564-417.000.
- Turley, Patricia A.: See—
Capuano, Italo A.; Turley, Patricia A.; and DuBord, Edward W., 4,294,798, Cl. 422-62.000.
- Turnbull, James O.; Barker, John C.; and Knight, Arthur J., to J. J. Barker Company Limited. Method and apparatus for curing of articles, 4,294,021, Cl. 34-224.000.
- Turner, James, to CBS Inc. Electronic musical instrument, 4,294,155, Cl. 84-1.010.
- Turner, Rex H., to International Paper Company. Delignification and bleaching of lignocellulosic pulp via photo-oxygenation, 4,294,654, Cl. 162-50.000.
- Tuscan Industries Pty. Limited: See—
Gell, Peter L., 4,294,418, Cl. 242-197.000.
- Uba, Toshio, to Gates Rubber Company, The. Battery strap connection welding method, 4,295,029, Cl. 219-75.000.
- UBE Industries, Ltd.: See—
Itatani, Hiroshi; Yoshimoto, Hataaki; Shiotani, Akinori; Yokota, Akiyoshi; and Yoshiaki, Motozoh, 4,294,976, Cl. 560-76.000.
- Uchida, Seiichi; Satomi, Yoshihito; Kiuchi, Norihiro; Yamagata, Takeo; Yoshioka, Susumu; Miyamoto, Tomohiko; and Tomuro, Jinichi, to Hitachi, Ltd.; and Nippon Mining Co., Ltd. Apparatus for preventing coking in fluidized bed reactor for cracking heavy hydrocarbon oil, 4,294,803, Cl. 422-111.000.
- Uchiyama, Hirofumi: See—
Ifuku, Yasushi; Uchiyama, Hirofumi; and Hayashi, Masayuki, 4,294,861, Cl. 426-475.000.
- Uchiyama, Kaoru: See—
Takahashi, Minoru; Tanigami, Takahiko; Uchiyama, Kaoru; Minorikawa, Hitoshi; Nishihara, Motohisa; Kawakami, Kanji; Suzuki, Seiko; Hachino, Hiroaki; and Misawa, Yutaka, 4,295,115, Cl. 338-4.000.
- Ueda, Masahiro, to Toyota Jidosha Kogyo Kabushiki Kaisha. Battery with flame intercepting filter and grounding lead, 4,294,896, Cl. 429-86.000.
- Uede, Hisashi: See—
Nakauchi, Hiroshi; Koyanagi, Katubumi; Inami, Yasuhiko; and Uede, Hisashi, 4,295,138, Cl. 340-785.000.
- Uedono, Norio: See—
Kakihara, Naomichi; Harada, Yoshiaki; and Uedono, Norio, 4,294,706, Cl. 210-762.000.
- Uemura, Kazuo: See—
Koga, Kenichiro; Hirose, Yoshiharu; Kanno, Iwao; Uemura, Kazuo; and Miura, Shuichi, 4,295,047, Cl. 250-363.00S.
- Ueno, Toshihiko; and Tomogane, Teruhisa, to Bando Chemical Industries, Ltd. Self-lubricating bearing, 4,294,712, Cl. 252-12.000.
- Uesaka, Tatsuo; Sugahara, Hiroshi; and Fujimura, Takeo, to Mitsubishi Denki Kabushiki Kaisha. Adjusting device for color cathode ray tube, 4,295,110, Cl. 335-212.000.
- Ugon, Michel, to Compagnie Internationale pour l'Informatique CII-Honeywell Bull (Societe Anonyme). Device for the protection of access to a permanent memory of a portable data carrier, 4,295,041, Cl. 234-487.000.
- Uhl, Wyman F.: See—
Antonio, Christo; and Uhl, Wyman F., 4,294,888, Cl. 428-451.000.
- Ullmann, Christoph: See—
Paulsen, Ralf; Sontheim, Max; and Ullmann, Christoph, 4,294,056, Cl. 53-86.000.
- Umarov, Almas B.: See—
Vanjukov, Andrei V.; Mechev, Valery V.; Bystrov, Valentin P.; Ezhov, Evgeny I.; Vasiliev, Mikhail G.; Zaitsev, Vladimir Y.; Romenets, Vladimir A.; Ivanov, Vladimir V.; Golik, Sergei Y.; Grin-Gnatovsky, Evgeny S.; Grechko, Alexandr V.; Savin, Ivan V.; Kozhakhmetov, Sultanbek M.; Meierovich, Veniamin B.; Nagibin, Vladimir D.; Ramazanov, Nariman A.; Umarov, Almas B.; Ziberov, Valentin E.; Kunaev, Askar M.; Takezhanov, Sauk T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazhev, Dzhonson T., 4,294,433, Cl. 266-161.000.
- Umeda, Kaoru: See—
Nishimura, Yoshinori; Umeda, Kaoru; and Harada, Hideo, 4,295,224, Cl. 455-156.000.
- Union Carbide Corporation: See—
Berger, Mitchell H.; Gill, Peter J.; and Maresca, Louis M., 4,294,956, Cl. 528-179.000.
- Berger, Mitchell H.; Maresca, Louis M.; and Matzner, Markus, 4,294,957, Cl. 528-179.000.
- Blair, Eskel B.; and Koleske, Joseph V., 4,294,746, Cl. 260-37.0EP.
- Gardner, Hugh C., 4,294,751, Cl. 260-400.00R.
- Union International Company, Ltd., The: See—
Jones, William A.; Hing Yuen, Tse Lin Sin Tse; Rytomaa, Tapio; Harper, Norman J.; and Frost, Henry F., 4,294,824, Cl. 424-101.000.
- Uniroyal, Inc.: See—
Plant, Howard L.; and Peterson, Glenn S., 4,294,970, Cl. 546-294.000.

- United Kingdom Atomic Energy Authority: See—
Campbell, Charles S., 4,294,659, Cl. 165-133.000.
- Hodgson, Thomas D.; and Jordan, Tony W. J., 4,294,805, Cl. 423-4.000.
- Humphreys, Peter; Davidson, Daniel F.; and Thatcher, Gordon, 4,294,658, Cl. 376-404.000.
- United Kingdom of Great Britain and Northern Ireland, The Secretary of State for Defence in Her Britannic Majesty's Government of the: See—
Wyeth, Harold W. G., 4,294,279, Cl. 137-264.000.
- United Kingdom of Great Britain and Northern Ireland, The Secretary of State for Industry in Her Britannic Majesty's Government of the: See—
Aubusson, Russell C.; and Gledhill, Richard J., 4,295,182, Cl. 361-400.000.
- United States Gypsum Company: See—
Kuh, Albert F., 4,294,054, Cl. 52-484.000.
- United States of America
Air Force: See—
Ernsting, John; Morgan, Thomas R.; Palmer, Leonard F. W.; Rivers, Alfred J.; and Robson, Stephen M., 4,294,243, Cl. 128-201.180.
- Husbands, Charles R., 4,294,508, Cl. 350-96.150.
- Army: See—
Freeman, Charles F.; and Villhauer, Kurt, 4,295,073, Cl. 313-105.0CM.
- National Aeronautics and Space Administration; administrator; with respect to an invention of:
Brockman, Milton H. Faraday rotation measurement method and apparatus, 4,295,140, Cl. 343-100.0PE.
- Wang, William S. Low temperature latching solenoid, 4,295,111, Cl. 335-256.000.
- National Aeronautics and Space Administration: See—
Baker, Joseph T.; Hoffer, George W.; and Hursta, William, 4,294,261, Cl. 128-691.000.
- Fischell, David R.; and Mazique, Jeffrey C., 4,294,264, Cl. 128-778.000.
- Navy: See—
Burnham, Ralph L., 4,295,104, Cl. 331-94.50C.
- Johnson, Richard F., 4,295,200, Cl. 364-555.000.
- Moore, Ronald D.; and Hall, John W., 4,294,112, Cl. 73-162.000.
- Swenson, Richard C., 4,295,212, Cl. 367-20.000.
- Tameo, Robert P., 4,294,135, Cl. 74-573.00R.
- U.S. Phillips Corporation: See—
Bex, Peter T. J.; and Asselman, George A. A., 4,294,139, Cl. 74-839.000.
- Khoe, Giok D.; Kock, Hendrikus G.; Meuleman, Lambertus J.; and Van Ruyven, Lodewijk J., 4,295,152, Cl. 357-74.000.
- Nissen, Nico; Op Het Veld, Sebastianus J.; and Schneider, Henri W., 4,295,158, Cl. 358-17.000.
- United States Surgical Corporation: See—
Sloane, Thomas E., Jr.; Melius, Clair; and Kling, Erich, 4,294,594, Cl. 55-186.000.
- United Technologies Corporation: See—
Blackburn, Martin J.; and Smith, Michael P., 4,294,615, Cl. 75-175.500.
- Camp, Vann T., 4,294,069, Cl. 60-238.000.
- Fowler, Donald W.; and Cleford, Douglas H., 4,294,162, Cl. 91-434.000.
- Universal Optical Company, Inc.: See—
Arons, Irving J.; Merrill, Richard E.; and Drennan, Arthur P., 4,294,792, Cl. 264-311.000.
- University of Auckland, The: See—
Boys, John T., 4,295,189, Cl. 363-41.000.
- University of California, Regents of the: See—
Tanner, Robert M., 4,295,218, Cl. 371-40.000.
- Urist, Marshall R., 4,294,753, Cl. 260-112.00R.
- University of Delaware: See—
Fraenkel, Dan; and Gates, Bruce C., 4,294,725, Cl. 252-455.00Z.
- University of Rochester: See—
Kende, Andrew S.; Curran, Dennis P.; King, Margaret L.; and Feldstein, Neil A., 4,294,763, Cl. 260-340.5DP.
- University of Tennessee Research Corp.: See—
Hashemian, Hashem M.; Kerlin, Thomas W.; and Upadhyaya, Belle R., 4,295,128, Cl. 340-506.000.
- University Patents, Inc.: See—
McMichael, John; Kline, Ellis L.; and Spaulding, James G., 4,294,818, Cl. 424-12.000.
- Uniweld Products, Incorporated: See—
Pearl, Douglas B., 4,294,481, Cl. 294-146.000.
- UOP Inc.: See—
Tadewald, Thomas D., 4,294,643, Cl. 156-293.000.
- Uozumi, Junzo: See—
Sumiyoshi, Masaharu; Sekiya, Setsuro; Motosugi, Katsuhiko; Uozumi, Junzo; Ando, Tsuneo; Takeuchi, Yuzo; and Minoura, Mikio, 4,294,213, Cl. 123-454.000.
- Upadek, Horst: See—
Conrad, Jens; Upadek, Horst; and Bruns, Klaus, 4,294,727, Cl. 252-522.00R.
- Upadhyaya, Belle R.: See—
Hashemian, Hashem M.; Kerlin, Thomas W.; and Upadhyaya, Belle R., 4,295,128, Cl. 340-506.000.
- Upjohn Company, The: See—
Prather, Richard A.; and Shah, Nirad N., 4,294,987, Cl. 564-331.000.
- Sih, John C., 4,294,978, Cl. 562-503.000.
- Sih, John C., 4,294,979, Cl. 562-503.000.
- Sih, John C., 4,294,980, Cl. 562-503.000.
- Sih, John C., 4,294,981, Cl. 562-503.000.
- Sih, John C., 4,294,982, Cl. 562-503.000.
- Sih, John C., 4,294,983, Cl. 562-503.000.
- Sih, John C., 4,294,984, Cl. 562-503.000.
- Smith, Herman W., 4,294,759, Cl. 260-326.270.
- Upson, Donald A.; Campbell, Gerald A.; and Kestner, Diane E., to Eastman Kodak Company. Antistatic compositions comprising cross-linkable latex binders, 4,294,739, Cl. 260-29.6RW.
- Upton, Eric L.: See—
Apple, Joseph; and Upton, Eric L., 4,294,543, Cl. 356-375.000.
- Uram, John R., Jr., to Goodyear Aerospace Corporation. Transparencies produced from epoxy resins cured with adducts of trimethoxyboroxine and benzyl alcohol, 4,294,886, Cl. 428-412.000.
- Urist, Marshall R., to University of California, The Regents of the. Bone morphogenetic protein process, 4,294,753, Cl. 260-112.00R.
- Urlaub, Alfred; and Chmela, Franz, to Maschinenfabrik Augsburg-Nürnberg Aktiengesellschaft. Combustion method and device for practicing same, 4,294,206, Cl. 123-276.000.
- Urquhart, Thomas, to Du Pont de Nemours, E. I., and Company. Apparatus for manufacturing flat plastic net, 4,294,646, Cl. 156-500.000.
- Useldinger, Ronald E.: See—
Moore, Gerald L., 4,294,446, Cl. 272-133.000.
- USM Corporation: See—
Marzouki, Taieb; and Schwisser, Bernd, 4,294,733, Cl. 260-28.50B.
- Woodman, Daniel W., Jr., 4,293,999, Cl. 29-564.600.
- Usuda, Matsuo: See—
Kawano, Tsuyoshi; Usuda, Matsuo; and Hirokawa, Toshio, 4,294,095, Cl. 72-51.000.
- Vaccarella, Richard M.: See—
Hsieh, Peter K.; and Vaccarella, Richard M., 4,295,065, Cl. 307-475.000.
- Vaisala Oy: See—
Ponkala, Jorma, 4,295,090, Cl. 324-60.0CD.
- Ponkala, Jorma, 4,295,091, Cl. 324-60.0CD.
- Vallentin, Werner: See—
Thiere, Helmut; and Vallentin, Werner, 4,295,142, Cl. 343-781.0CA.
- van Bilderbeek, Bernard H., to Vetco Inc. Subsea flowline connector, 4,294,471, Cl. 285-24.000.
- Vance, Dwight A. Apparatus to indicate when a patient has evacuated a bed or demonstrates a restless condition, 4,295,133, Cl. 340-573.000.
- Van Deusen, George S.; and Ogrinc, Joseph F., to Warner & Swasey Company, The. High speed gill box, 4,293,983, Cl. 19-127.000.
- van de Water, Johan P.: See—
Visser, Pieter; and van de Water, Johan P., 4,294,720, Cl. 252-373.000.
- Vanek, Edward A.: See—
Saccavino, Joseph F.; and Vanek, Edward A., 4,294,716, Cl. 252-68.000.
- Vanjukov, Andrei V.; Mechev, Valery V.; Bystrov, Valentin P.; Ezhov, Evgeny I.; Vasiliev, Mikhail G.; Zaitsev, Vladimir Y.; Romenets, Vladimir A.; Ivanov, Vladimir V.; Golik, Sergei Y.; Grin-Gnatovsky, Evgeny S.; Grechko, Alexandr V.; Savin, Ivan V.; Kozhakhmetov, Sultanbek M.; Meierovich, Veniamin B.; Nagibin, Vladimir D.; Ramazanov, Nariman A.; Umarov, Almas B.; Ziberov, Valentin E.; Kunaev, Askar M.; Takezhanov, Sauk T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazhev, Dzhonson T., 4,294,433, Cl. 266-161.000.
- Vanlerberghe, Guy; Sebag, Henri; and Fiquet, Claire, to Societe Anonyme dite: L'Oreal. Shampoo and/or bubble bath composition containing surfactant and 1,2 alkane diol, 4,294,728, Cl. 252-542.000.
- Van Luit, Richard D. Wall cabinet and method of making, 4,294,498, Cl. 312-245.000.
- van Maanen, Johannes D., to Tevopharm-Schiedam B.V. Apparatus for positioning articles between the carriers of a drag conveyor, said articles being fed in a continuous closed row, 4,294,344, Cl. 198-461.000.
- Van Pee, Willy: See—
Astheimer, Hans J.; Brandtstaedter, Horst; Ohlinger, Rainer; Van Pee, Willy; Van Steen, Jaak; Sauer, Friedrich; Schmidt, Rudolf; and Krueger, Siegfried, 4,294,666, Cl. 203-72.000.
- Van Ruyven, Lodewijk J.: See—
Khoe, Giok D.; Kock, Hendrikus G.; Meuleman, Lambertus J.; and Van Ruyven, Lodewijk J., 4,295,152, Cl. 357-74.000.
- Van Steen, Jaak: See—
Astheimer, Hans J.; Brandtstaedter, Horst; Ohlinger, Rainer; Van Pee, Willy; Van Steen, Jaak; Sauer, Friedrich; Schmidt, Rudolf; and Krueger, Siegfried, 4,294,666, Cl. 203-72.000.
- Van Uffelen, Jean-Pierre H., to Telecommunications Radioelectriques et Telephoniques. Arrangement for restituting the clock for a receiver of data transmitted by phase modulation of a carrier, 4,295,222, Cl. 375-106.000.
- van Veen, Wouter M. D.: See—
Astegiano, Luciano; and van Veen, Wouter M. D., 4,295,007, Cl. 179-7.00R.
- Vasiliev, Mikhail G.: See—
Vanjukov, Andrei V.; Mechev, Valery V.; Bystrov, Valentin P.; Ezhov, Evgeny I.; Vasiliev, Mikhail G.; Zaitsev, Vladimir Y.; Romenets, Vladimir A.; Ivanov, Vladimir V.; Golik, Sergei Y.; Grin-Gnatovsky, Evgeny S.; Grechko, Alexandr V.; Savin, Ivan V.; Kozhakhmetov, Sultanbek M.; Meierovich, Veniamin B.; Nagibin, Vladimir D.; Ramazanov, Nariman A.; Umarov, Almas

- B.; Ziberov, Valentin E.; Kunaev, Askar M.; Takezhanov, Sauk T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazheev, Dzhonson T., 4,294,433, Cl. 266-161.000.
- Vasipari Kutato Intezet: See—
Tamas, Istvan; Tamas, Lajos; Kiss, Gyula; Kiss, Jozsef; and Kaldor, Antal, 4,294,611, Cl. 75-49.000.
- VDO Adolf Schindling AG: See—
Sauersschell, Wolfgang; and Werkmann, Karl-Heinz, 4,294,108, Cl. 73-119.00A.
- Veara, Jack R.: See—
O'Banion, Michael L.; and Veara, Jack R., 4,294,441, Cl. 269-97.000.
- Veatch, William M., to Olympia Radiological Associates. Cystourethrographic examination chain, 4,294,260, Cl. 128-654.000.
- Veb Kombinat Polygraph "Werner Lamberz" Leipzig: See—
Bottcher, Winfried; and Germer, Kurt, 4,294,182, Cl. 112-21.000.
- Vellucci, Enzo, to E. R. Squibb & Sons, Inc. Transparent toothpaste having a medicinal action and process for its production, 4,294,894, Cl. 424-49.000.
- Veltman, Preston L. Drying co-mingled carbohydrate solution and recycled product by dielectric heating, 4,294,624, Cl. 127-62.000.
- Verbatim Corporation: See—
Martinelli, Lawrence G.; and Garrison, Mark R., 4,294,640, Cl. 156-213.000.
- Verbrugge, Pieter A.: See—
Kramer, Petrus A.; and Verbrugge, Pieter A., 4,294,765, Cl. 260-343.30R.
- Verbsky, James D.: See—
Stock, Albert M.; and Verbsky, James D., 4,294,997, Cl. 568-855.000.
- Vereinigte aluminium-Werke Aktiengesellschaft: See—
Krugler, Jorg; Thome, Roland; Moritz, Dieter; Bings, Hubert; and Losert, Herbert, 4,294,816, Cl. 423-484.000.
- Verheyen, Roland: See—
Funk, Willi; Verheyen, Roland; and Schedler, Heinz, 4,294,103, Cl. 72-453.140.
- Verhoog, Hendrik M.: See—
Steen, Adam; and Verhoog, Hendrik M., 4,294,431, Cl. 266-44.000.
- Vernat, Pierre: See—
Thurles, Edmond; Vernat, Pierre; and Sauvat, Roger, 4,295,023, Cl. 200-148.00R.
- Verschuur, Eke, to Shell Oil Company. Dewatering of coal slurries, 4,294,584, Cl. 44-23.000.
- Vescia, Michele: See—
Helfert, Herbert; Reinert, Friedrich; Richter, Paul; Vescia, Michele; and Wegerle, Dieter, 4,294,576, Cl. 8-137.500.
- Vetco Inc.: See—
Ahlstone, Arthur G., 4,294,477, Cl. 285-336.000.
- van Bilderbeek, Bernard H., 4,294,471, Cl. 285-24.000.
- Viallet, Daniel: See—
Suppa, Vito; and Viallet, Daniel, 4,295,211, Cl. 367-4.000.
- Vickers Limited: See—
Fairlie-Clarke, Anthony C., 4,295,134, Cl. 340-610.000.
- Wielinga, Hans, 4,294,910, Cl. 430-302.000.
- Vickers, Margaret R.: See—
Durant, Graham J.; Ganellin, Charon R.; and Vickers, Margaret R., 4,294,854, Cl. 424-326.000.
- Victor Company of Japan, Ltd.: See—
Fujita, Mitsuo; and Matsumura, Koji, 4,295,080, Cl. 318-257.000.
- Hirota, Akira; Kosaka, Yoshiteru; and Ashida, Kazutaka, 4,295,171, Cl. 360-73.000.
- Machida, Toyotaka; and Ikemura, Yuichi, 4,295,157, Cl. 358-17.000.
- Tanaka, Mitsuki; and Suzuki, Hidetsugu, 4,295,006, Cl. 179-1.00E.
- Watanabe, Yasuaki; and Noda, Teruaki, 4,295,165, Cl. 358-193.100.
- Vierstraete, Jean. Sawing or cutting machine, 4,294,150, Cl. 83-453.000.
- Viessmann, Hans. Heating boiler for liquid or gaseous fuels, 4,294,198, Cl. 122-136.00R.
- Villemant, Claude M.: See—
Quintin, Renee; and Villemant, Claude M., 4,294,009, Cl. 29-832.000.
- Villhauer, Kurt: See—
Freeman, Charles F.; and Villhauer, Kurt, 4,295,073, Cl. 313-105.00C.
- Vinals, Joaquin F.: See—
Sprecker, Mark A.; Schmitt, Frederick L.; Vock, Manfred H.; Vinals, Joaquin F.; and Kiwala, Jacob, 4,294,708, Cl. 252-8.600.
- Vinson, Kenneth D.: See—
Camden, James B.; and Vinson, Kenneth D., 4,294,876, Cl. 428-95.000.
- Virnig, Michael J., to Henkel Corporation. Benzene sulfonamido pyrimidine derivatives, 4,294,965, Cl. 544-297.000.
- Virsberg, Lars-Goran: See—
Bjorklund, Anders; Persson, Erik; and Virsberg, Lars-Goran, 4,295,113, Cl. 336-84.00M.
- Visser, Pieter; and van de Water, Johan P., to Shell Oil Company. Process for the preparation of gas mixtures, 4,294,720, Cl. 252-373.000.
- Vitellaro, Frank A., to Dayco Corporation. Method and apparatus for making wire reinforced hose, 4,294,636, Cl. 156-143.000.
- Viviers, Joseph A.: See—
Scheffel, Herbert; von Gericke, Rowlen E.; and Viviers, Joseph A., 4,294,482, Cl. 295-34.000.
- Vock, Manfred H.: See—
Mookherjee, Braja D.; Wilson, Richard A.; Schmitt, Frederick L.; and Vock, Manfred H., 4,294,863, Cl. 426-538.000.
- Sprecker, Mark A.; Schmitt, Frederick L.; Vock, Manfred H.; Vinals, Joaquin F.; and Kiwala, Jacob, 4,294,708, Cl. 252-8.600.
- Voeest-Alpine Aktiengesellschaft: See—
Kollenz, Erich, 4,294,690, Cl. 209-3.000.
- Wiesinger, Horst; and Scheurecker, Werner, 4,294,307, Cl. 164-448.000.
- Volk, Anthony J.; and Volk, Henry J. Poultry trussing device, 4,293,977, Cl. 17-11.000.
- Volk, Henry J.: See—
Volk, Anthony J.; and Volk, Henry J., 4,293,977, Cl. 17-11.000.
- Volker, Herbert: See—
Bozon, Alfred; Koberstein, Edgar; Pletka, Hans-Dieter; Volker, Herbert; and Lakatos, Eduard, 4,294,726, Cl. 252-462.000.
- Vollmer, Rudolf, to Honeywell Inc. Control devices for heaters, 4,294,402, Cl. 236-12.00R.
- Volpato, Ivo: See—
Innocenti, Franco; Orzalesi, Giovanni; and Volpato, Ivo, 4,294,833, Cl. 424-263.000.
- von Gericke, Rowlen E.: See—
Scheffel, Herbert; von Gericke, Rowlen E.; and Viviers, Joseph A., 4,294,482, Cl. 295-34.000.
- von Schenck, Raban: See—
Wassel-Nielsen, Horst-Dieter; Adrian, Renate; Panter, Herbert; Heymer, Gero; Maurer, Alexander; and von Schenck, Raban, 4,294,808, Cl. 423-305.000.
- Voss, Eckart; Petersen, Uwe; and Stadler, Peter, to Bayer Aktiengesellschaft. Selectively protected 4,6-di-O-(aminoglycosyl)-1,3-diaminocyclitols and their production, 4,294,959, Cl. 536-17.00R.
- Vought Corporation: See—
Fouse, Jack A.; and McClaren, Sherwood W., III, 4,294,419, Cl. 244-117.00R.
- W & R Fletcher (N.Z.) Limited: See—
Ward, Roderick O., 4,293,980, Cl. 17-51.000.
- W. R. Grace & Co.: See—
Gaidis, James M.; and Rosenberg, Arnold M., 4,294,813, Cl. 423-385.000.
- Hill, Richard N., 4,294,809, Cl. 423-321.00R.
- Wacker Werke GmbH & Co. KG: See—
Grepplmaier, Martin; and Grunwald, Wittloff, 4,294,136, Cl. 74-600.000.
- Wada, Hajime: See—
Iwata, Mitsuo; Wada, Hajime; Iwasa, Tomoyuki; and Tsuchino, Kunio, 4,295,169, Cl. 360-71.000.
- Wagner, Hans A., to G. D. Searle & Co. {[4-Azido-5-(ethoxyethyl)-6-phenyl-2-pyrimidinyl]amino}carbonyl glycine and esters thereof, 4,294,830, Cl. 424-251.000.
- Wagner, Kuno; Block, Hans-Dieter; and Schafer, Walter, to Bayer Aktiengesellschaft. Polysocyanates which contain carbodiimide groups and which are stable in storage, 4,294,719, Cl. 252-182.000.
- Wagner, William R., to Rockwell International Corporation. Atomizing shock wave precombustor, 4,294,208, Cl. 123-285.000.
- Wahnschaff, Paul: See—
Tuell, James L.; and Wahnschaff, Paul, 4,294,456, Cl. 280-11.280.
- Waldmann, Helmut: See—
Wilms, Klaus G.; and Waldmann, Helmut, 4,294,703, Cl. 210-631.000.
- Walker, Loren H.: See—
Cutler, John H.; Espelage, Paul M.; and Walker, Loren H., 4,295,086, Cl. 318-759.000.
- Wallace, James B.: See—
Kovatch, George N.; and Wallace, James B., 4,295,053, Cl. 307-64.000.
- Walle, L. Irwin. Self-purging probe for low pressure leak detection, 4,294,107, Cl. 73-49.200.
- Walter, Lothar: See—
Olschewski, Armin; Brandenstein, Manfred; Walter, Lothar; Ernst, Horst M.; and Schulz, Toni, 4,294,100, Cl. 72-340.000.
- Walz, Gregory J.: See—
Woloshuk, Edward A.; Walz, Gregory J.; and Kretschmar, Robert O., 4,294,523, Cl. 352-86.000.
- Wang, An, to Wang Laboratories, Inc. Ideographic typewriter, 4,294,550, Cl. 400-110.000.
- Wang Laboratories, Inc.: See—
Wang, An, 4,294,550, Cl. 400-110.000.
- Wang, Paul P.: See—
Jambotkar, Chakrapani G.; and Wang, Paul P., 4,294,002, Cl. 29-571.000.
- Wang, William S.: See—
United States of America, National Aeronautics and Space Administration; and Wang, William S., 4,295,111, Cl. 335-256.000.
- Ward, Roderick O., to W & R Fletcher (N.Z.) Limited. Method for washing animal casings, 4,293,980, Cl. 17-51.000.
- Wardell, Gerald S. Retractable bow thruster, 4,294,186, Cl. 114-151.000.
- Warner-Lambert Company: See—
Chen, Evan N.; and Ferraro, Frank A., 4,294,010, Cl. 30-42.000.
- Hayashi, Masaki; Iguchi, Sadahiko; Okada, Takanori; and Kawasaki, Akiyoshi, 4,294,849, Cl. 424-305.000.
- Warner & Swasey Company, The: See—
Van Deusen, George S.; and Ogrinc, Joseph F., 4,293,983, Cl. 19-127.000.
- Wassel-Nielsen, Horst-Dieter; Adrian, Renate; Panter, Herbert; Heymer, Gero; Maurer, Alexander; and von Schenck, Raban, to Hoechst Aktiengesellschaft. Production of anticorrosive pigments containing phosphorus, 4,294,808, Cl. 423-305.000.

- Watanabe, Shigeru; and Kusunuki, Tatsuo, to Fuji Photo Film Co. Ltd. Method of and device for measuring chlorophyll of living leaves, 4,295,042, Cl. 250-226.000.
- Watanabe, Shoei: See—
Ideta, Yasufumi; Takeda, George; and Watanabe, Shoei, 4,294,160, Cl. 91-378.000.
- Watanabe, Takehiko: See—
Kinumaki, Toyosuke; Watanabe, Takehiko; Sugii, Kisaburo; and Iseki, Shigeo, 4,294,856, Cl. 426-7.000.
- Watanabe, Teruoki; Kanno, Tadao; Hidaka, Akio; and Kobayashi, Shunji, to Honda Giken Kogyo Kabushiki Kaisha. Method and apparatus for the continuous furnace brazing and soft-nitriding treatments of iron articles, 4,294,630, Cl. 148-16.600.
- Watanabe, Terutaka: See—
Matsuda, Osamu; Watanabe, Terutaka; Tabata, Yoneho; and Machi, Sueo, 4,294,675, Cl. 204-159.140.
- Watanabe, Yasuaki; and Noda, Teruaki, to Victor Company of Japan, Ltd. Television signal discrimination system in a television receiver, 4,295,165, Cl. 358-193.100.
- Watanabe, Yoshiaki: See—
Taga, Genji; Oikawa, Teruo; and Watanabe, Yoshiaki, 4,294,810, Cl. 423-331.000.
- Water Pollution Control Corporation: See—
Thayer, Paul M., 4,294,696, Cl. 210-220.000.
- Watson, Allan: See—
Lohmuller, Reiner; Schneider, Helmut; and Watson, Allan, 4,294,932, Cl. 518-706.000.
- Watson, Arthur, to Lightburn & Co. Limited. Drive arrangement for concrete mixers, 4,294,548, Cl. 366-60.000.
- Webb, Edward A.; McKenna, John F.; and Makar, Frank B., Jr., to GTE Products Corporation. Arc discharge lamp having ceramic arc tube, 4,295,075, Cl. 313-220.000.
- Webb, James E. Diesel fuel injector tool, 4,293,992, Cl. 29-267.000.
- Weber, Paul J. Overhead bookholder, 4,294,425, Cl. 248-445.000.
- Wedemeyer, Karlfried: See—
Klein, Alfons; Kron, Rudolf; Wedemeyer, Karlfried; Knust, Ernst; and Havenith, Lothar, 4,294,715, Cl. 361-318.000.
- Wegerle, Dieter: See—
Helfert, Herbert; Reinert, Friedrich; Richter, Paul; Vescia, Michele; and Wegerle, Dieter, 4,294,576, Cl. 8-137.500.
- Wei, Chung H., to Stauffer Chemical Company. Reduction of scale formation during vinyl chloride polymerization with tin mercaptides, 4,294,945, Cl. 526-74.000.
- Weiderrich, LeRoy J., to Pollination Technics, Inc. Leafcutter bee larvae extracting method and device, 4,293,966, Cl. 6-12.00R.
- Weidler, Charles H., to AMP Incorporated. Piezoelectric audio transducer mounting and electrical connector, 4,295,009, Cl. 179-110.00A.
- Weigl, Erwin: See—
Svoboda, Josef; Krob, Erwin; and Weigl, Erwin, 4,294,459, Cl. 280-605.000.
- Weinstock, Leonard M.: See—
Tull, Roger J.; Weinstock, Leonard M.; and Shinkai, Ichiro, 4,294,988, Cl. 564-417.000.
- Weirauch, Donald F.: See—
Schmidt, Gary D.; Norris, Jerry L.; and Weirauch, Donald F., 4,295,102, Cl. 331-65.000.
- Weiszbrod, David A., to Janko, Mike A. Variable tape speed for video recorders, 4,295,170, Cl. 360-73.000.
- Welch, James A., to Sanner Contracting Co. Elevating earth scraper, 4,294,026, Cl. 37-8.000.
- Weld, Richard G., to Weldwheels, Inc. Method of manufacturing a wire spoke automotive wheel, 4,294,393, Cl. 228-134.000.
- Weldwheels, Inc.: See—
Weld, Richard G., 4,294,393, Cl. 228-134.000.
- Welsh, Clarence E.: See—
Wendler, Paul O.; and Welsh, Clarence E., 4,294,159, Cl. 91-375.00A.
- Wendler, Paul O.; and Welsh, Clarence E., to General Motors Corporation. Thread delasher in vehicle steering gear, 4,294,159, Cl. 91-375.00A.
- Werkmann, Karl-Heinz: See—
Sauersschell, Wolfgang; and Werkmann, Karl-Heinz, 4,294,108, Cl. 73-119.00A.
- Werthmann, Wilfried, to Standex International GmbH, Firma. Method of and apparatus for producing embossing tools, 4,294,650, Cl. 156-660.000.
- Wessel, Wolf: See—
Stumpp, Gerhard; and Wessel, Wolf, 4,294,211, Cl. 123-379.000.
- Westerling, David E.: See—
Stilwell, Robert E.; and Westerling, David E., 4,294,059, Cl. 53-448.000.
- Western Electric Company, Incorporated: See—
Burns, William S., Jr.; and Sankey, William M., 4,294,480, Cl. 294-131.000.
- Daugherty, Edgar E.; Jackson, Kenneth W.; Jones, Wesley W.; and Subh, Naif T., 4,295,005, Cl. 174-92.000.
- Pollack, Frank J., 4,294,008, Cl. 29-831.000.
- Westinghouse Electric Corp.: See—
Beatty, William E., Jr.; and Ellsworth, James P., 4,295,025, Cl. 200-288.000.
- Kovatch, George N.; and Wallace, James B., 4,295,053, Cl. 307-64.000.
- Kovatch, George N.; Bettencourt, George S.; and Soles, Otto H., 4,295,054, Cl. 307-80.000.
- Martin, Jack, 4,295,185, Cl. 362-211.000.
- Peterson, Charles A.; and Grove, Louis C., Jr., 4,295,174, Cl. 361-16.000.
- Shutterly, Harold B., 4,295,223, Cl. 455-72.000.
- Stacey, Eric J.; and Baker, Donal E., 4,295,190, Cl. 363-162.000.
- Wilreker, Victor F.; and Smith, William H., 4,295,094, Cl. 324-96.000.
- Westley, John: See—
Liu, Chao-Min; and Westley, John, 4,294,925, Cl. 435-84.000.
- Weston, John B., to Burroughs Wellcome Co. Anti-protozoal oxadiazole derivatives, 4,294,842, Cl. 424-272.000.
- Weston, John B., to Burroughs Wellcome Co. Anti-protozoal oxadiazole derivatives, 4,294,843, Cl. 424-272.000.
- Weston Research Corporation: See—
Brown, William F., 4,294,622, Cl. 106-314.000.
- Westvaco Corporation: See—
Gendron, Wilfred H., 4,294,400, Cl. 229-68.00R.
- Wetmore, Sherman B.: See—
Person, Abraham; Wetmore, Sherman B.; and McNary, James F., 4,294,564, Cl. 405-195.000.
- Wetter, Manfred; and Schmidt, Karl H., to Kraemer & Grebe GmbH & Co. KG Maschinen- und Modellfabrik. Cutter knife, 4,294,415, Cl. 241-292.000.
- Wetzel, William H.; Pan, Hsi-Lung; Goodwin, Robert J.; and Wilkinson, John E., to Reichhold Chemicals, Incorporated. Method of reducing formation of chlorinated dioxins in manufacture of chlorinated phenols, 4,294,996, Cl. 568-776.000.
- Weyerhaeuser Company: See—
Strauss, Gary M., 4,294,542, Cl. 356-339.000.
- Whaley, Morris L., to Morris Whaley, Inc. Boom sockets, 4,294,495, Cl. 308-174.000.
- Whelan, James P., to Ad-Tec Products, Inc. Paint strainer, 4,294,701, Cl. 210-497.200.
- Whitehead, Richard O., to Shell Oil Company. Impact polymers, 4,294,937, Cl. 525-99.000.
- Whitehouse, Hugh L., to Stanley Works, The. Torque measuring system for an air tool, 4,294,110, Cl. 73-862.230.
- Whitlock, Inc.: See—
Evans, Arthur J., 4,294,020, Cl. 34-168.000.
- Widder Corporation: See—
Krieg, Adrian H., 4,294,013, Cl. 30-392.000.
- Wichert, Edelbert, to Siemens Aktiengesellschaft. Braking system for a transport car for transporting files, 4,294,337, Cl. 188-171.000.
- Wielinga, Hans, to Vickers Limited. Printing plates, 4,294,910, Cl. 430-302.000.
- Wiesinger, Horst; and Scheurecker, Werner, to Voest-Alpine Aktiengesellschaft. Supporting and guiding stand arrangement to be used in a bow-type continuous casting plant, 4,294,307, Cl. 164-448.000.
- Wieveg, Raymond: See—
Miyagishima, Tosh; Puntar, Joseph; and Wieveg, Raymond, 4,294,314, Cl. 166-318.000.
- Wiggins, Douglas G., to Xerox Corporation. Carriage speed control for a raster scanner, 4,295,167, Cl. 358-285.000.
- Wiggins, Garfield. Doweling jig template, 4,294,567, Cl. 408-72.00R.
- Wiklund, Klas R., to AGA Aktiebolag. Electronic distance-measuring instrument, 4,295,201, Cl. 364-561.000.
- Wiktorowski, Thomas A.: See—
Blair, Matthew J.; and Wiktorowski, Thomas A., 4,294,432, Cl. 266-46.000.
- Wild, Peter: See—
Henk, Hermann; Wunderlich, Klaus; and Wild, Peter, 4,294,580, Cl. 8-549.000.
- Wildnauer, Richard H.; and Humphries, William T., to Johnson & Johnson. Skin treating compositions, 4,294,852, Cl. 424-317.000.
- Wilfer, Oskar, to H. F. & Ph. F. Reemtsma. Folding box, 4,294,399, Cl. 229-44.00B.
- Wilke, Gerhard. Process for the production of pastry and flaky pastry-like products, 4,294,862, Cl. 426-502.000.
- Wilkerson, Edward D. Automobile height gauge, 4,294,016, Cl. 33-180.00A.
- Wilkinson, John E.: See—
Wetzel, William H.; Pan, Hsi-Lung; Goodwin, Robert J.; and Wilkinson, John E., 4,294,996, Cl. 568-776.000.
- Williams, Allen C.; and Williams, Barbara J. Switch adapter mechanism, 4,295,026, Cl. 200-331.000.
- Williams, Barbara J.: See—
Williams, Allen C.; and Williams, Barbara J., 4,295,026, Cl. 200-331.000.
- Williams, Garnet M. E.; and Hollis, James E. L., to Ferraris Development and Engineering Company Limited. Apparatus for monitoring respiratory performance, 4,294,262, Cl. 128-726.000.
- Williams, John W.; Smith, Robert A.; and Arbir, Francis W., to Abbott Laboratories. Biocidal additive for cutting fluids, 4,294,853, Cl. 424-319.000.
- Wilmarth, Paul C., to RCA Corporation. Color television receiver degaussing circuit, 4,295,078, Cl. 315-8.000.
- Wilms, Klaus G.; and Waldmann, Helmut, to Bayer Aktiengesellschaft. Hydrogen peroxide treatment of effluent, 4,294,703, Cl. 210-631.000.
- Wilreker, Victor F.; and Smith, William H., to Westinghouse Electric Corp. High voltage high frequency analog signal measuring system, 4,295,094, Cl. 324-96.000.
- Wilson, Jack A. Rotary electrical junction assembly, 4,294,500, Cl. 339-5.00M.
- Wilson, Richard A.: See—
Mookherjee, Braja D.; Wilson, Richard A.; Schmitt, Frederick L.; and Vock, Manfred H., 4,294,863, Cl. 426-538.000.

- Wilson, Worley C., to Telemetry Controls, Inc. Programmable control system. 4,295,191, Cl. 364-104.000.
- Winegard Company: See—
Winegard, John R.; Shelledy, Carey W.; and Cowan, Keith B., 4,295,143, Cl. 343-840.000.
- Winegard, John R.; Shelledy, Carey W.; and Cowan, Keith B., to Winegard Company. Low wind load modified farabolic antenna. 4,295,143, Cl. 343-840.000.
- Winiasz, Michael E.; and Long, James M., to A-T-O, Inc. Case packer apparatus including velocity compensator assembly. 4,294,057, Cl. 53-244.000.
- Winzer, Frederick W.; and Ault, James R., to Emhart Industries, Inc. Glass forehead construction. 4,294,603, Cl. 65-346.000.
- Wion, David W., to Magmate Australia Proprietary Limited. Figure for arrangement on magnetically attractive surface. 4,294,036, Cl. 46-242.000.
- Witherspoon, Romeo R., to General Motors Corporation. PTFE-Bound talc separators for secondary zinc alkaline batteries. 4,294,899, Cl. 429-206.000.
- Wittlinger, Harold A.; and Salerno, Carmine P., to RCA Corporation. Position sensing and display means. 4,294,321, Cl. 177-210.0FP.
- Wittwer, Norman C., to Bell Telephone Laboratories, Incorporated. Semiconductor integrated circuit protection arrangement. 4,295,176, Cl. 361-91.000.
- Wnek, Kenneth A. Convertible ski carrying apparatus. 4,294,387, Cl. 224-315.000.
- Woelfel, James A., to Motor Wheel Corporation. Fiber-reinforced composite wheel construction. 4,294,490, Cl. 301-63.0PW.
- Woelfel, James A.; and Smith, Richard W., to Motor Wheel Corporation. Fiber-reinforced composite wheel construction. 4,294,639, Cl. 156-185.000.
- Wolfson, Sidney K., Jr.: See—
Yao, Shang J.; Sun Yao, Huei Y.; and Wolfson, Sidney K., Jr., 4,294,891, Cl. 429-2.000.
- Wollner, Robert A. Slot machine card game. 4,294,451, Cl. 273-308.000.
- Woloshek, Edward A.; Walz, Gregory J.; and Kretschmar, Robert O., to Zyntrax Corporation. The Three-dimensional display apparatus. 4,294,523, Cl. 352-86.000.
- Wong, Thomas S. W.: See—
Mihalich, Stephen K.; and Wong, Thomas S. W., 4,295,062, Cl. 307-279.000.
- Wood, Donald C.; and McLaughlin, Robert L., to DeSoto, Inc. Emollient and/or dyed prilled urea bath bead composition. 4,294,855, Cl. 424-358.000.
- Wood, Lindley S.: See—
Tracy, David J.; Wood, Lindley S.; and Chakrabarti, Paritosh M., 4,294,848, Cl. 424-302.000.
- Woodall, Jerry M.: See—
Chappell, Terry I.; and Woodall, Jerry M., 4,295,002, Cl. 136-244.000.
- Woodford, Thomas J., to Stephen C. Small, a part interest. Lower limb muscle aid device. 4,294,238, Cl. 128-80.00G.
- Woodhouse, Richard G.; and Salway, Peter H., to Lucas Industries Limited. Control circuits for solenoids. 4,295,177, Cl. 361-154.000.
- Woodman, Daniel W., Jr., to USM Corporation. Radial lead inserting machine. 4,293,999, Cl. 29-564.600.
- Woods, H. John: See—
Fisher, Ian P.; Woods, H. John; and Souhrada, Frank, 4,294,686, Cl. 208-56.000.
- World Medical Marketing Corporation: See—
Hofstein, Steven R., 4,294,236, Cl. 128-25.00B.
- World Wide Oil Tools, Inc.: See—
Horton, Herbert D., 4,294,444, Cl. 269-156.000.
- Worrell, G. Richard: See—
Grane, Henry R.; Jubin, John C., Jr.; and Worrell, G. Richard, 4,294,999, Cl. 568-910.000.
- Wossner, Gunter: See—
Binder, Georg; and Wossner, Gunter, 4,295,067, Cl. 310-52.000.
- Wuerthner, Herbert: See—
Svoboda, Josef; Wuerthner, Herbert; and Stritzl, Karl, 4,294,462, Cl. 280-634.000.
- Wunderlich, Klaus: See—
Henk, Hermann; Wunderlich, Klaus; and Wild, Peter, 4,294,580, Cl. 8-549.000.
- Wunderlich, Robert J.: See—
Herron, Clifford W.; and Wunderlich, Robert J., 4,295,180, Cl. 361-383.000.
- Wunstel, Franz. Car top carrier support. 4,294,388, Cl. 224-315.000.
- Wuthrich, Werner, to Autelca AG. Ribbon feed mechanism. 4,294,553, Cl. 400-219.100.
- Wyeth, Harold W. G., to United Kingdom of Great Britain and Northern Ireland, The Secretary of State for Defence in Her Britannic Majesty's Government of the. Fuel tanks. 4,294,279, Cl. 137-264.000.
- Xerox Corporation: See—
Genovese, Frank C., 4,294,901, Cl. 430-39.000.
- Mammino, Joseph, 4,294,904, Cl. 430-122.000.
- Snelling, Christopher, 4,294,534, Cl. 355-3.00R.
- Spehrley, Charles W., Jr., 4,294,539, Cl. 355-76.000.
- Thettu, Raghulinga R., 4,294,540, Cl. 355-76.000.
- Wiggins, Douglas G., 4,295,167, Cl. 358-285.000.
- Yabuta, Yukio: See—
Ohba, Hisao; Oda, Kazutaka; Yabuta, Yukio; and Ohashi, Azusa, 4,294,672, Cl. 204-129.400.
- Yagihara, Morio; and Yokota, Yukio, to Fuji Photo Film Co., Ltd. Color photographic silver halide light-sensitive material. 4,294,918, Cl. 430-553.000.
- Yamada, Masao: See—
Amemori, Hiroyuki; and Yamada, Masao, 4,294,123, Cl. 73-861.920.
- Yamada, Yoshito; Okumura, Hiroshi; and Murakami, Shoji, to Mitsubishi Denki Kabushiki Kaisha. Residual current transformer. 4,295,112, Cl. 336-84.00M.
- Yamagata, Takeo: See—
Uchida, Seiichi; Satomi, Yoshihito; Kiuchi, Norihiro; Yamagata, Takeo; Yoshioka, Susumu; Miyamoto, Tomohiko; and Tomuro, Jinichi, 4,294,803, Cl. 422-111.000.
- Yamaguchi, Hisao: See—
Shiraiwa, Toshio; Yamaguchi, Hisao; and Matsumoto, Shigeaki, 4,294,118, Cl. 73-620.000.
- Yamaguchi, Jun; Naoi, Takashi; Sera, Hidefumi; Ishigaki, Kunio; and Ogawa, Masasi, to Fuji Photo Film Co., Ltd. Method of hardening gelatin. 4,294,921, Cl. 430-621.000.
- Yamamoto, Michio: See—
Hino, Minoru; Oshima, Takao; Hayatsu, Kazuo; Yamamoto, Michio; and Yasui, Seimei, 4,294,940, Cl. 525-124.000.
- Yamamoto, Takashi; and Amako, Hiroshi, to Nippon Paint Co., Ltd. Corrosion evaluation testing method of coated metallic material and apparatus employed therefor. 4,294,667, Cl. 204-1.00T.
- Yamamoto, Takashi: See—
Shima, Ichiji; Yamamoto, Tatsuo; Yoshibayashi, Shigeru; Teshima, Hiroshi; Hizume, Akio; Iki, Tetsuo; Yamamoto, Takashi; Kanamori, Kyozo; and Tanaka, Shigeo, 4,294,120, Cl. 73-650.000.
- Yamamoto, Tatsuo: See—
Shima, Ichiji; Yamamoto, Tatsuo; Yoshibayashi, Shigeru; Teshima, Hiroshi; Hizume, Akio; Iki, Tetsuo; Yamamoto, Takashi; Kanamori, Kyozo; and Tanaka, Shigeo, 4,294,120, Cl. 73-650.000.
- Yamamura, Keizo; and Ohashi, Yasuo, to Omron Tateisi Electronics Co. Temperature detecting circuit. 4,294,116, Cl. 73-362.0AR.
- Yamashita, Gentaro: See—
Suzuki, Yoshiki; Ikura, Hiroshi; Yamashita, Gentaro; and Nagai, Tsuneji, 4,294,829, Cl. 424-241.000.
- Yamashita, Nobuo; and Maeda, Miwako, to Olympus Optical Co., Ltd. Connecting optical system for light guides. 4,294,511, Cl. 350-96.180.
- Yao, Shang J.; Sun Yao, Huei Y.; and Wolfson, Sidney K., Jr., to Montefiore Hospital Association of Western Pennsylvania, The. Intermittently refuelable implantable bio-oxidant fuel cell. 4,294,891, Cl. 429-2.000.
- Yartsev, Ivan M.: See—
Asinovsky, Erik I.; Afanasiev, Anatoly A.; Pakhomov, Evgeny P.; Zeigarnik, Vladimir A.; and Yartsev, Ivan M., 4,295,021, Cl. 200-147.00R.
- Yasuda, Etsuro: See—
Segawa, Yoshihiro; Ohta, Minoru; and Yasuda, Etsuro, 4,294,801, Cl. 422-98.000.
- Yasuhara, Seishi; and Ohnishi, Eiichi, to Nissan Motor Co., Ltd. Intake port means for extracting engine exhaust gas for recirculation. 4,294,220, Cl. 123-568.000.
- Yasui, Seimei: See—
Hino, Minoru; Oshima, Takao; Hayatsu, Kazuo; Yamamoto, Michio; and Yasui, Seimei, 4,294,940, Cl. 525-124.000.
- Yasukawa, Eiki: See—
Kihara, Kunio; Toda, Hideo; Yasukawa, Eiki; Ishibashi, Toshiaki; and Tokita, Taketoshi, 4,294,933, Cl. 521-27.000.
- Yokota, Akiyoshi: See—
Itatani, Hiroshi; Yoshimoto, Hataaki; Shiotani, Akinori; Yokota, Akiyoshi; and Yoshikiyo, Motozoh, 4,294,976, Cl. 560-76.000.
- Yokota, Yukio: See—
Yagihara, Morio; and Yokota, Yukio, 4,294,918, Cl. 430-553.000.
- Yoneda, Naoto; Kato, Jyoji; and Kinashi, Keizo, to Tanabe Seiyaku Co., Ltd. Tetrahydroisoquinoline compounds and a pharmaceutical composition thereof. 4,294,832, Cl. 424-258.000.
- Yoneda, Takao: See—
Enomoto, Minoru; Yoneda, Takao; and Takeuchi, Yoshiyuki, 4,294,045, Cl. 51-165.710.
- Yonker, John H.; Fisher, Ernest P., Jr.; and Bills, David, to Otis Engineering Corporation. Landing nipple. 4,294,315, Cl. 166-322.000.
- Yoshibayashi, Shigeru: See—
Shima, Ichiji; Yamamoto, Tatsuo; Yoshibayashi, Shigeru; Teshima, Hiroshi; Hizume, Akio; Iki, Tetsuo; Yamamoto, Takashi; Kanamori, Kyozo; and Tanaka, Shigeo, 4,294,120, Cl. 73-650.000.
- Yoshida, Hajime, to Hajime Industries Ltd. Pattern data processing method and apparatus to practice such method. 4,295,120, Cl. 340-146.3MA.
- Yoshida, Hiroshi: See—
Aoki, Shinji; Kawamura, Keita; Kimura, Hitoshi; Katayama, Tsutomu; Kaido, Chikara; and Yoshida, Hiroshi, 4,294,674, Cl. 204-157.10H.
- Yoshii, Kazuhiro, to Sanyo Electric Co. Ltd.; and Tokyo Sanyo Electric. Absorption refrigerating system. 4,294,076, Cl. 62-235.100.
- Yoshikiyo, Motozoh: See—
Itatani, Hiroshi; Yoshimoto, Hataaki; Shiotani, Akinori; Yokota, Akiyoshi; and Yoshikiyo, Motozoh, 4,294,976, Cl. 560-76.000.
- Yoshimoto, Hataaki: See—
Itatani, Hiroshi; Yoshimoto, Hataaki; Shiotani, Akinori; Yokota, Akiyoshi; and Yoshikiyo, Motozoh, 4,294,976, Cl. 560-76.000.
- Yoshino, Kimiaki: See—
Takashima, Yuji; Ishida, Eisuke; Nishiguchi, Hisanori; and Yoshino, Kimiaki, 4,294,902, Cl. 430-45.000.

- Yoshioka, Masahiro; Koike, Toshifumi; and Izumi, Hideki, to Hitachi, Ltd. Sliding-type bearing. 4,294,494, Cl. 308-76.000.
- Yoshioka, Susumu: See—
Uchida, Seiichi; Satomi, Yoshihito; Kiuchi, Norihiro; Yamagata, Takeo; Yoshioka, Susumu; Miyamoto, Tomohiko; and Tomuro, Jinichi, 4,294,803, Cl. 422-111.000.
- Yoshioka, Tamotu: See—
Mizuguchi, Ryuzo; Ishikura, Sinichi; Ishii, Keizou; and Yoshioka, Tamotu, 4,294,740, Cl. 260-29.6RB.
- Yoshitugu, Ken: See—
Toyota, Akinori; Yoshitugu, Ken; and Kashiwa, Norio, 4,294,948, Cl. 526-125.000.
- Young, Ching T., to Bendix Autolite Corporation. Method of measuring oxygen and process for pretreating a solid electrolyte oxygen gas sensing element. 4,294,668, Cl. 204-1.00T.
- Young, Dick K.; and Sumner, Kenneth E., to Marathon Oil Company. Quick opening internal manway for towers. 4,294,049, Cl. 52-20.000.
- Young, Leroy: See—
Schlotter, Harold J.; and Young, Leroy, 4,294,452, Cl. 273-403.000.
- Youngson, Charles R., Jr.: See—
Tamony, Andree E.; and Youngson, Charles R., Jr., 4,294,928, Cl. 423-235.000.
- Zachary, Richard E., to Dow Chemical Company, The. Method for removing trapped gas under pond liners. 4,294,589, Cl. 55-36.000.
- Zaitsev, Vladimir Y.: See—
Vanjukov, Andrei V.; Mechev, Valery V.; Bystrov, Valentin P.; Ezhov, Evgeny I.; Vasiliev, Mikhail G.; Zaitsev, Vladimir Y.; Romenets, Vladimir A.; Ivanov, Vladimir V.; Golik, Sergei Y.; Grin-Gnatovsky, Evgeny S.; Grechko, Alexandr V.; Savin, Ivan V.; Kozhakhmetov, Sultanbek M.; Meierovich, Veniamin B.; Nagibin, Vladimir D.; Ramazanov, Nariman A.; Umarov, Almas B.; Ziberov, Valentin E.; Kunaev, Askar M.; Takezhanov, Sauk T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazheev, Dzhonson T., 4,294,433, Cl. 266-161.000.
- Zalewski, Z. Leo: See—
Lloyd, C. F.; Zalewski, Z. Leo; and Brendle, Paul C., 4,295,066, Cl. 310-30.000.
- Zauner, Christian W. Head gear. 4,293,958, Cl. 2-12.000.
- Zeigarnik, Vladimir A.: See—
Asinovsky, Erik I.; Afanasiev, Anatoly A.; Pakhomov, Evgeny P.; Zeigarnik, Vladimir A.; and Yartsev, Ivan M., 4,295,021, Cl. 200-147.00R.
- Zergenyi, Janos, to Ciba-Geigy Corporation. Process for inverting the configuration in optically active compounds. 4,294,966, Cl. 544-316.000.
- Ziberov, Valentin E.: See—
Vanjukov, Andrei V.; Mechev, Valery V.; Bystrov, Valentin P.; Ezhov, Evgeny I.; Vasiliev, Mikhail G.; Zaitsev, Vladimir Y.; Romenets, Vladimir A.; Ivanov, Vladimir V.; Golik, Sergei Y.; Grin-Gnatovsky, Evgeny S.; Grechko, Alexandr V.; Savin, Ivan V.; Kozhakhmetov, Sultanbek M.; Meierovich, Veniamin B.; Nagibin, Vladimir D.; Ramazanov, Nariman A.; Umarov, Almas B.; Ziberov, Valentin E.; Kunaev, Askar M.; Takezhanov, Sauk T.; Alexandrov, Petr A.; Kolesnikov, Boris I.; and Khagazheev, Dzhonson T., 4,294,433, Cl. 266-161.000.
- Zielinski, Jan: See—
Falkowski, Leonard; Stefanska, Barbara; Zielinski, Jan; Troka, Elzbieta; Golik, Jerzy; Kolodziejczyk, Pawel; Jarzebski, Andrzej; Cybulska, Emilia; and Borowski, Edward, 4,294,958, Cl. 536-17.00R.
- Zimmer USA, Inc.: See—
Fuson, Robert L., 4,293,962, Cl. 3-1.900.
- Gold, Barry L.; and Bolesky, Richard C., 4,293,963, Cl. 3-1.910.
- Zushi, Sadao; and Oida, Yoshio, to Tokyo Shibaura Electric Co., Ltd. Microwave ovens with programmable control. 4,295,027, Cl. 219-10.55B.
- Zyntrax Corporation, The: See—
Woloshek, Edward A.; Walz, Gregory J.; and Kretschmar, Robert O., 4,294,523, Cl. 352-86.000.

LIST OF REISSUE PATENTEEES

TO WHOM

PATENTS WERE ISSUED ON THE 13TH DAY OF OCTOBER, 1981

NOTE—Arranged in accordance with the first significant character or word of the name (in accordance with city and telephone directory practice).

Aladdin Industries, Incorporated: See—
Bramming, Carl, deceased; Bramming, Clara B., heir; Bramming, Kenneth R., heir; and Wheeler, Beverley B., heir, Re. 30,768, Cl. 215-13.00R.

Bentz, Erwin J. H., to Caterpillar Tractor Co. Modular heat exchanger with pivotal cores. Re. 30,766, Cl. 165-41.000.

Bramming, Carl, deceased; by Bramming, Clara B., heir; by Bramming, Kenneth R., heir; and by Wheeler, Beverley B., heir, to Aladdin Industries, Incorporated. Vacuum insulated bottle. Re. 30,768, Cl. 215-13.00R.

Bramming, Clara B., heir: See—
Bramming, Carl, deceased; Bramming, Clara B., heir; Bramming, Kenneth R., heir; and Wheeler, Beverley B., heir, Re. 30,768, Cl. 215-13.00R.

Bramming, Kenneth R., heir: See—
Bramming, Carl, deceased; Bramming, Clara B., heir; Bramming, Kenneth R., heir; and Wheeler, Beverley B., heir, Re. 30,768, Cl. 215-13.00R.

Bussjager, Rudy C., to Carrier Corporation. Heat pump system. Re. 30,765, Cl. 62-115.000.

Carrier Corporation: See—
Bussjager, Rudy C., Re. 30,765, Cl. 62-115.000.

Caterpillar Tractor Co.: See—
Bentz, Erwin J. H., Re. 30,766, Cl. 165-41.000.

Cobb, Delwin E.; Fidler, Jerry D.; Gutman, Nathan; Livesay, Richard E.; Simmons, Gerald P.; and Stemler, Orrin A., Re. 30,769, Cl. 299-67.000.

Cobb, Delwin E.; Fidler, Jerry D.; Gutman, Nathan; Livesay, Richard E.; Simmons, Gerald P.; and Stemler, Orrin A., to Caterpillar Tractor Co. Mounting arrangement for impact rock-breaker. Re. 30,769, Cl. 299-67.000.

Dauben, Dwight L.: See—
Felber, Betty J.; Dauben, Dwight L.; and Marrs, Richard E., Re. 30,767, Cl. 166-261.000.

Dowbenko, Rostyslaw: See—
Friedlander, Charles B.; Gruber, Gerald W.; and Dowbenko, Rostyslaw, Re. 30,772, Cl. 525-421.000.

Felber, Betty J.; Dauben, Dwight L.; and Marrs, Richard E., to Standard Oil Company (Indiana). Method using lignosulfonates for high-temperature plugging. Re. 30,767, Cl. 166-261.000.

Fidler, Jerry D.: See—
Cobb, Delwin E.; Fidler, Jerry D.; Gutman, Nathan; Livesay, Richard E.; Simmons, Gerald P.; and Stemler, Orrin A., Re. 30,769, Cl. 299-67.000.

Fish, Elson B.: See—
Shobert, Samuel M.; and Fish, Elson B., Re. 30,770, Cl. 156-180.000.

Friedlander, Charles B.; Gruber, Gerald W.; and Dowbenko, Rostyslaw, to PPG Industries, Inc. Amide-modified urethane acrylate radiation curable compounds and coating compositions and methods of making same. Re. 30,772, Cl. 525-421.000.

Glaser, Paul F.; and Orford, Richard J., to Transaction Technology, Inc. Transaction terminal. Re. 30,773, Cl. 235-379.000.

Gruber, Gerald W.: See—
Friedlander, Charles B.; Gruber, Gerald W.; and Dowbenko, Rostyslaw, Re. 30,772, Cl. 525-421.000.

Gutman, Nathan: See—
Cobb, Delwin E.; Fidler, Jerry D.; Gutman, Nathan; Livesay, Richard E.; Simmons, Gerald P.; and Stemler, Orrin A., Re. 30,769, Cl. 299-67.000.

Livesay, Richard E.: See—
Cobb, Delwin E.; Fidler, Jerry D.; Gutman, Nathan; Livesay, Richard E.; Simmons, Gerald P.; and Stemler, Orrin A., Re. 30,769, Cl. 299-67.000.

Marrs, Richard E.: See—
Felber, Betty J.; Dauben, Dwight L.; and Marrs, Richard E., Re. 30,767, Cl. 166-261.000.

Orford, Richard J.: See—
Glaser, Paul F.; and Orford, Richard J., Re. 30,773, Cl. 235-379.000.

Plas/Steel Products, Inc.: See—
Shobert, Samuel M.; and Fish, Elson B., Re. 30,770, Cl. 156-180.000.

PPG Industries, Inc.: See—
Friedlander, Charles B.; Gruber, Gerald W.; and Dowbenko, Rostyslaw, Re. 30,772, Cl. 525-421.000.

Shobert, Samuel M.; and Fish, Elson B., to Plas/Steel Products, Inc. Method for fabricating improved fiber reinforced plastic rods having a smooth surface. Re. 30,770, Cl. 156-180.000.

Simmons, Gerald P.: See—
Cobb, Delwin E.; Fidler, Jerry D.; Gutman, Nathan; Livesay, Richard E.; Simmons, Gerald P.; and Stemler, Orrin A., Re. 30,769, Cl. 299-67.000.

Standard Oil Company (Indiana): See—
Felber, Betty J.; Dauben, Dwight L.; and Marrs, Richard E., Re. 30,767, Cl. 166-261.000.

Stemler, Orrin A.: See—
Cobb, Delwin E.; Fidler, Jerry D.; Gutman, Nathan; Livesay, Richard E.; Simmons, Gerald P.; and Stemler, Orrin A., Re. 30,769, Cl. 299-67.000.

Transaction Technology, Inc.: See—
Glaser, Paul F.; and Orford, Richard J., Re. 30,773, Cl. 235-379.000.

Wheeler, Beverley B., heir: See—
Bramming, Carl, deceased; Bramming, Clara B., heir; Bramming, Kenneth R., heir; and Wheeler, Beverley B., heir, Re. 30,768, Cl. 215-13.00R.

Zondek, Klaus. Method of protecting the hulls of marine vessels from fouling. Re. 30,771, Cl. 156-196.000.

LIST OF DESIGN PATENTEEES

Abraham, Anthony S., to Lever Brothers Company. Combined box and lid. 261,234, 10-13-81, Cl. D9-432.000.

Akita, Tsugio: See—
Yoshida, Toshihiko; Tatsumi, Masakazu; Sakakibara, Seichi; Kubo, Toshiaki; Akita, Tsugio; and Ueda, Yoshiaki, 261,266, Cl. D32-21.000.

Allen, Alton K.: See—
Mintz, Richard P.; Buttner, Ronald A.; and Allen, Alton K., 261,243, Cl. D10-121.000.

Altadonna, James. Container for carrying first aid data and equipment. 261,198, 10-13-81, Cl. D2-400.000.

American Cyanamid Company: See—
Grip, John A., 261,231, Cl. D9-370.000.

Grip, John A., 261,232, Cl. D9-370.000.

Arai, Noriyuki: See—
Kurokawa, Koya; Arai, Noriyuki; Takahashi, Hideo; and Saeiki, Taisuke, 261,263, Cl. D14-2.000.

Austin, David D.: See—
Becker, James R.; Austin, David D.; and Rudat, Ronald A., 261,283, Cl. D21-33.000.

Barrett, Walter H., to Columbia Chase Corporation. Solar demonstration unit. 261,279, 10-13-81, Cl. D19-62.000.

Barringer, Jack E.: See—
Clink, Sterling A.; and Barringer, Jack E., 261,294, Cl. D21-195.000.

Bautch, Roger F.: See—
Lange, Arthur E.; and Bautch, Roger F., 261,251, Cl. D11-157.000.

Baxter Travenol Laboratories, Inc.: See—
Williams, Robert P., 261,236, Cl. D9-435.000.

Becker, James R.; Austin, David D.; and Rudat, Ronald A., to Hasbro Industries, Inc. Game board. 261,283, 10-13-81, Cl. D21-33.000.

Bird, John J. Bottle. 261,230, 10-13-81, Cl. D9-367.000.

Birmingham, Joan T. Ornament preform. 261,248, 10-13-81, Cl. D11-121.000.

Birmingham, Joan T. Creature ornament. 261,249, 10-13-81, Cl. D11-128.000.

Birmingham, Joan T. Creature ornament. 261,250, 10-13-81, Cl. D11-128.000.

Black & Decker Inc.: See—
Bunyea, Roderick F., 261,222, Cl. D8-68.000.

Blake, Jack E. Stand. 261,201, 10-13-81, Cl. D6-85.000.

PI 46

LIST OF DESIGN PATENTEEES

PI 47

Braun Aktiengesellschaft: See—
Oberheim, Robert; Greubel, Jurgen; and Rams, Dieter, 261,317, Cl. D28-35.000.

Oberheim, Robert; Greubel, Jurgen; and Rams, Dieter, 261,318, Cl. D28-35.000.

Oberheim, Robert; Greubel, Jurgen; and Rams, Dieter, 261,319, Cl. D28-35.000.

Breneman, Jack L., to Quaker Oats Company. The. Toy space shuttle. 261,286, 10-13-81, Cl. D21-87.000.

Bridgestone Tire Co., Ltd.: See—
Yamazaki, Naoki; Kojima, Hiroshi; and Nishio, Hideaki, 261,256, Cl. D12-148.000.

Bunyea, Roderick F., to Black & Decker Inc. Pneumatic impact wrench. 261,222, 10-13-81, Cl. D8-68.000.

Buttner, Ronald A.: See—
Mintz, Richard P.; Buttner, Ronald A.; and Allen, Alton K., 261,243, Cl. D10-121.000.

Caldwell, Joseph M. Pulley for compound archery bows. 261,296, 10-13-81, Cl. D22-5.000.

Camsco, Inc.: See—
Gobeli, Gregg P., 261,274, Cl. D18-7.000.

Canon Kabushiki Kaisha: See—
Sakai, Masaaki; and Uematsu, Sakae, 261,273, Cl. D18-7.000.

Capanear, Patricia. Tablecloth. 261,210, 10-13-81, Cl. D6-286.000.

Capitol Products Corporation: See—
Schmidt, Dietrich F., 261,304, Cl. D25-74.000.

Schmidt, Dietrich F., 261,305, Cl. D25-74.000.

Schmidt, Dietrich F., 261,306, Cl. D25-74.000.

Schmidt, Dietrich F., 261,307, Cl. D25-74.000.

Schmidt, Dietrich F., 261,308, Cl. D25-74.000.

Schmidt, Dietrich F., 261,309, Cl. D25-74.000.

Schmidt, Dietrich F., 261,310, Cl. D25-74.000.

Schmidt, Dietrich F., 261,311, Cl. D25-74.000.

Schmidt, Dietrich F., 261,312, Cl. D25-74.000.

Schmidt, Dietrich F., 261,313, Cl. D25-74.000.

Schmidt, Dietrich F., 261,314, Cl. D25-74.000.

Schmidt, Dietrich F., 261,315, Cl. D25-74.000.

Schmidt, Dietrich F., 261,316, Cl. D25-74.000.

Carbajales Santa-Eulalia, Javier B.: See—
Carbajales Santa-Eulalia, Jesus A.; and Carbajales Santa-Eulalia, Javier B., 261,252, Cl. D11-158.000.

Carbajales Santa-Eulalia, Jesus A.; and Carbajales Santa-Eulalia, Javier B., 261,253, Cl. D11-158.000.

Carbajales Santa-Eulalia, Jesus A.; and Carbajales Santa-Eulalia, Javier B., 261,254, Cl. D11-158.000.

Carbajales Santa-Eulalia, Jesus A.; and Carbajales Santa-Eulalia, Javier B., to John J. Madison Company, Inc. Figurine of a bulldog. 261,252, 10-13-81, Cl. D11-158.000.

Carbajales Santa-Eulalia, Jesus A.; and Carbajales Santa-Eulalia, Javier B., to John J. Madison Company, Inc. Figurine of a lynx. 261,253, 10-13-81, Cl. D11-158.000.

Carbajales Santa-Eulalia, Jesus A.; and Carbajales Santa-Eulalia, Javier B., to John J. Madison Company, Inc. Figurine of a poodle. 261,254, 10-13-81, Cl. D11-158.000.

Carey, Bruce P.; Ishimaru, Lloyd Y.; and Shimano, Moto, to Microsonics Corporation. Casing for a microphonograph. 261,264, 10-13-81, Cl. D14-14.000.

Christensen, Kurt. Disk for a menstrual calendar. 261,275, 10-13-81, Cl. D18-10.000.

Clark, Robin, to Hilary Page "Sensible" Toys Limited. Gingerbread man rattle. 261,285, 10-13-81, Cl. D21-65.000.

Clean City Squares, Inc.: See—
Gilbert, William A., 261,218, Cl. D34-1.000.

Clink, Sterling A.; and Barringer, Jack E. Arm wrestling device. 261,294, 10-13-81, Cl. D21-195.000.

Coca-Cola Company, The: See—
Cornett, Donald F., 261,269, Cl. D15-116.000.

Columbia Chase Corporation: See—
Barrett, Walter H., 261,279, Cl. D19-62.000.

Cornett, Donald F., to Coca-Cola Company, The. Combined dispenser cabinet and stand. 261,269, 10-13-81, Cl. D15-116.000.

Dart Industries Inc.: See—
Groh, Leo A.; Ludwig, Douglas D.; Painter, David L.; and Free, John H., 261,215, Cl. D7-131.000.

Datasonic, Inc.: See—
Mintz, Richard P.; Buttner, Ronald A.; and Allen, Alton K., 261,243, Cl. D10-121.000.

Davis, Lester M. Fishing lure. 261,298, 10-13-81, Cl. D22-27.000.

Denker, William B.; and Frank, Jeanne C., to Red Owl Stores, Inc. Cash register attachment for screening keys. 261,276, 10-13-81, Cl. D18-12.000.

Dockery, Allen W. Cane. 261,199, 10-13-81, Cl. D3-7.000.

Dowco Corporation: See—
Sanderson, Paul H., Jr., 261,224, Cl. D8-323.000.

Durand, Jean-Jacques. Goblet or similar article. 261,211, 10-13-81, Cl. D7-13.000.

Dvorsky, Daniel A. Quick release honda. 261,229, 10-13-81, Cl. D8-396.000.

Easterday, James E. Fishing lure. 261,299, 10-13-81, Cl. D22-27.000.

Emerson Electric Co.: See—
Seeley, Wayne R., 261,260, Cl. D13-18.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,245, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,246, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,247, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,248, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,249, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,250, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,251, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,252, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,253, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,254, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,255, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,256, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,257, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,258, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,259, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,260, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,261, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,262, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,263, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,264, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,265, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,266, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,267, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,268, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,269, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,270, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,271, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,272, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,273, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,274, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,275, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,276, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,277, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,278, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,279, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,280, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,281, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,282, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,283, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,284, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,285, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,286, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,287, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,288, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,289, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,290, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,291, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,292, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,293, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,294, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,295, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,296, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,297, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,298, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,299, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,300, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,301, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,302, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,303, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,304, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,305, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,306, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,307, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,308, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,309, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,310, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,311, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,312, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,313, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,314, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,315, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,316, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,317, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,318, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,319, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,320, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,321, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,322, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,323, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,324, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,325, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,326, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,327, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,328, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,329, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,330, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,331, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,332, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,333, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,334, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,335, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,336, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,337, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,338, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,339, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,340, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,341, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,342, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,343, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,344, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,345, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,346, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,347, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,348, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,349, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,350, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,351, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,352, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,353, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,354, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,355, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,356, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,357, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,358, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,359, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,360, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc. Earring. 261,361, 10-13-81, Cl. D11-75.000.

Epstein, Elias, to Kaspar & Esh, Inc

LIST OF DESIGN PATENTEEES

- Kubo, Toshiaki: See—
Yoshida, Toshihiko; Tatsumi, Masakazu; Sakakibara, Seiichi; Kubo, Toshiaki; Akita, Tsugio; and Ueda, Yoshiaki, 261,266, Cl. D32-21.000.
- Kurokawa, Koya; Arai, Noriyuki; Takahashi, Hideo; and Saeki, Taisuke, to Matsushita Electric Industrial Co., Ltd. Video tape recorder deck. 261,263, 10-13-81, Cl. D14-2.000.
- Lange, Arthur E.; and Baugh, Roger F. Desk ornament. 261,251, 10-13-81, Cl. D11-157.000.
- Latimer, Margaret D. Iron holder. 261,219, 10-13-81, Cl. D32-73.000.
- Lavanhar, Patricia S. Adjustable viewing mirror. 261,258, 10-13-81, Cl. D12-189.000.
- Lawing, Edward, to Reliance Electric Co. Scale. 261,241, 10-13-81, Cl. D10-91.000.
- Lawrence, Frederick J., to Gradco/Dendoki, Inc. Sorting apparatus. 261,272, 10-13-81, Cl. D16-32.000.
- Le Compte, Marcia L.: See—
Perethian, Charles M.; Le Compte, Marcia L.; and Vetter, Bruce W., 261,213, Cl. D7-77.000.
- Lee, David L.; and O'Connor, Harry J. Panel for a chair back. 261,209, 10-13-81, Cl. D6-197.000.
- Leopoldi, Norbert. Telephone note holder, or the like. 261,265, 10-13-81, Cl. D14-59.000.
- Lever Brothers Company: See—
Abraham, Anthony S., 261,234, Cl. D9-432.000.
- Linton, John C., to FIC Corporation. Fuse holder. 261,261, 10-13-81, Cl. D13-35.000.
- Linton, John C., to FIC Corporation. Fuse holder. 261,262, 10-13-81, Cl. D13-35.000.
- Lloyd, Kenneth A., Jr. Check-out station accessory frame. 261,206, 10-13-81, Cl. D6-143.000.
- Loase, James C.: See—
Vest, Gary W.; and Loase, James C., 261,240, Cl. D10-77.000.
- Lorist, Hendrik J. G. Housing for an emergency alarm for swimming pools and the like. 261,242, 10-13-81, Cl. D10-106.000.
- Ludwig, Douglas D.: See—
Groh, Leo A.; Ludwig, Douglas D.; Painter, David L.; and Free, John H., 261,215, Cl. D7-131.000.
- Marucci, N. Dominic; and Wright, David B., to Syntex (U.S.A.) Inc. Dental handpiece. 261,301, 10-13-81, Cl. D24-12.000.
- Marvin Glass & Associates: See—
Schoenfeld, Palmer J., 261,289, Cl. D21-111.000.
- Matsushita Electric Industrial Co., Ltd.: See—
Kurokawa, Koya; Arai, Noriyuki; Takahashi, Hideo; and Saeki, Taisuke, 261,263, Cl. D14-2.000.
- Yoshida, Toshihiko; Tatsumi, Masakazu; Sakakibara, Seiichi; Kubo, Toshiaki; Akita, Tsugio; and Ueda, Yoshiaki, 261,266, Cl. D32-21.000.
- Matthews Machine Co., Inc.: See—
Matthews, Ralph E., 261,220, Cl. D7-208.000.
- Matthews, Ralph E., to Matthews Machine Co., Inc. Fire screen. 261,220, 10-13-81, Cl. D7-208.000.
- McDonald, Christopher L. Lawn sign. 261,281, 10-13-81, Cl. D20-38.000.
- McMullan, Robert G., to SCM (Canada) Limited. Collapsible handle. 261,235, 10-13-81, Cl. D9-434.000.
- Microsonics Corporation: See—
Carey, Bruce P.; Ishimaru, Lloyd Y.; and Shimano, Moto, 261,264, Cl. D14-14.000.
- Mills, Frederick G. W., to U.G. Closures & Plastics Ltd. Combined funnel and pouring spout. 261,212, 10-13-81, Cl. D7-68.000.
- Mintz, Richard P.; Buttner, Ronald A.; and Allen, Alton K., to Data-sonic, Inc. Water sensing alarm. 261,243, 10-13-81, Cl. D10-121.000.
- Morgan, Thomas E. Dual size brake shoe aperture gauge. 261,239, 10-13-81, Cl. D10-64.000.
- Mutch, Clyde E. Dish or pot scraper. 261,217, 10-13-81, Cl. D32-49.000.
- New Era Products, Inc.: See—
Vest, Gary W.; and Loase, James C., 261,240, Cl. D10-77.000.
- Newton, Brian L.: See—
Samuels, Donald H.; and Newton, Brian L., 261,293, Cl. D21-151.000.
- Nishio, Hideaki: See—
Yamazaki, Naoki; Kojima, Hiroshi; and Nishio, Hideaki, 261,256, Cl. D12-148.000.
- Oberheim, Robert; Greubel, Jurgen; and Rams, Dieter, to Braun Aktiengesellschaft. Combined curling iron with cover. 261,317, 10-13-81, Cl. D28-35.000.
- Oberheim, Robert; Greubel, Jurgen; and Rams, Dieter, to Braun Aktiengesellschaft. Curling iron. 261,318, 10-13-81, Cl. D28-35.000.
- Oberheim, Robert; Greubel, Jurgen; and Rams, Dieter, to Braun Aktiengesellschaft. Cover for a curling iron. 261,319, 10-13-81, Cl. D28-35.000.
- O'Connor, Harry J.: See—
Lee, David L.; and O'Connor, Harry J., 261,209, Cl. D6-197.000.
- Oelzner, Alfred H. Combined butter holder dish and cover. 261,214, 10-13-81, Cl. D7-84.000.
- Painter, David L.: See—
Groh, Leo A.; Ludwig, Douglas D.; Painter, David L.; and Free, John H., 261,215, Cl. D7-131.000.
- Perethian, Charles M.; Le Compte, Marcia L.; and Vetter, Bruce W., to First Champaign Corporation. Insulated carrier for food or the like. 261,213, 10-13-81, Cl. D7-77.000.
- Pfanni-Werk Otto Eckart KG: See—
Rieser, Willi, 261,278, Cl. D18-27.000.
- Pitt, James K. Adjustable batter board. 261,238, 10-13-81, Cl. D10-61.000.
- Playart Limited: See—
Tong, Duncan, 261,292, Cl. D21-143.000.
- Pluenneke, Ricks H. Underside wick hand-held rope wick applicator. 261,221, 10-13-81, Cl. D8-02.000.
- Quaker Oats Company, The: See—
Breneman, Jack L., 261,286, Cl. D21-87.000.
- Hilko, Steven E., 261,287, Cl. D21-87.000.
- Hilko, Steven E., 261,288, Cl. D21-89.000.
- Snyder, Paul D., 261,290, Cl. D21-113.000.
- Rams, Dieter: See—
Oberheim, Robert; Greubel, Jurgen; and Rams, Dieter, 261,317, Cl. D28-35.000.
- Oberheim, Robert; Greubel, Jurgen; and Rams, Dieter, 261,318, Cl. D28-35.000.
- Oberheim, Robert; Greubel, Jurgen; and Rams, Dieter, 261,319, Cl. D28-35.000.
- Red Owl Stores, Inc.: See—
Denker, William B.; and Frank, Jeanne C., 261,276, Cl. D18-12.000.
- Reliance Electric Co.: See—
Lawing, Edward, 261,241, Cl. D10-91.000.
- Richmond, Colin B., II, to General Mills, Inc. Spoon or similar article. 261,216, 10-13-81, Cl. D7-137.000.
- Ricoh Company Ltd.: See—
Hashimoto, Masanori; and Soda, Koichi, 261,277, Cl. D18-12.000.
- Rieser, Willi, to Pfanni-Werk Otto Eckart KG. Font of vegetable script. 261,278, 10-13-81, Cl. D18-27.000.
- Robins, Robert R. Roll top wet bar. 261,207, 10-13-81, Cl. D6-144.000.
- Rolodex Corporation: See—
Goertz, Albrecht, 261,280, Cl. D19-76.000.
- Rommag P. Worwag & Co.: See—
Hug, Niklaus, 261,267, Cl. D32-21.000.
- Rowswell, Donald. Belt attachable hammer holder or the like. 261,197, 10-13-81, Cl. D2-400.000.
- Rudat, Ronald A.: See—
Becker, James R.; Austin, David D.; and Rudat, Ronald A., 261,283, Cl. D21-33.000.
- Rutter, Sheldon, to Scott & Fetzer Company, The. Motor housing and rug nozzle for a vacuum cleaner. 261,268, 10-13-81, Cl. D32-32.000.
- Ryobi, Ltd.: See—
Sakamoto, Masakazu; and Shohoji, Takeshi, 261,297, Cl. D22-25.000.
- Saeki, Taisuke: See—
Kurokawa, Koya; Arai, Noriyuki; Takahashi, Hideo; and Saeki, Taisuke, 261,263, Cl. D14-2.000.
- Sakai, Masaaki; and Uematsu, Sakae, to Canon Kabushiki Kaisha. Desk top electronic calculator. 261,273, 10-13-81, Cl. D18-7.000.
- Sakakibara, Seiichi: See—
Yoshida, Toshihiko; Tatsumi, Masakazu; Sakakibara, Seiichi; Kubo, Toshiaki; Akita, Tsugio; and Ueda, Yoshiaki, 261,266, Cl. D32-21.000.
- Sakamoto, Masakazu; and Shohoji, Takeshi, to Ryobi, Ltd. Fishing reel. 261,297, 10-13-81, Cl. D22-25.000.
- Samczyk, Casimir S., to White Consolidated Industries, Inc. Duplicating apparatus. 261,271, 10-13-81, Cl. D16-31.000.
- Samuels, Donald H.; and Newton, Brian L., to Hasbro Industries, Inc. Jack-in-the-box toy. 261,293, 10-13-81, Cl. D21-151.000.
- Sanderson, Paul H., Jr., to Dowco Corporation. Pivot pin for movable louvers or the like. 261,224, 10-13-81, Cl. D8-323.000.
- Schmidt, Dietrich F., to Capitol Products Corporation. Frame member for windows or the like. 261,304, 10-13-81, Cl. D25-74.000.
- Schmidt, Dietrich F., to Capitol Products Corporation. Frame member for windows or the like. 261,305, 10-13-81, Cl. D25-74.000.
- Schmidt, Dietrich F., to Capitol Products Corporation. Frame member for windows or the like. 261,306, 10-13-81, Cl. D25-74.000.
- Schmidt, Dietrich F., to Capitol Products Corporation. Frame member for windows or the like. 261,307, 10-13-81, Cl. D25-74.000.
- Schmidt, Dietrich F., to Capitol Products Corporation. Frame member for windows or the like. 261,308, 10-13-81, Cl. D25-74.000.
- Schmidt, Dietrich F., to Capitol Products Corporation. Frame member for windows or the like. 261,309, 10-13-81, Cl. D25-74.000.
- Schmidt, Dietrich F., to Capitol Products Corporation. Frame member for windows or the like. 261,310, 10-13-81, Cl. D25-74.000.
- Schmidt, Dietrich F., to Capitol Products Corporation. Frame member for windows or the like. 261,311, 10-13-81, Cl. D25-74.000.
- Schmidt, Dietrich F., to Capitol Products Corporation. Frame member for windows or the like. 261,312, 10-13-81, Cl. D25-74.000.
- Schmidt, Dietrich F., to Capitol Products Corporation. Frame member for windows or the like. 261,313, 10-13-81, Cl. D25-74.000.
- Schmidt, Dietrich F., to Capitol Products Corporation. Frame member for windows or the like. 261,314, 10-13-81, Cl. D25-74.000.
- Schmidt, Dietrich F., to Capitol Products Corporation. Frame member for windows or the like. 261,315, 10-13-81, Cl. D25-74.000.
- Schmidt, Dietrich F., to Capitol Products Corporation. Frame member for windows or the like. 261,316, 10-13-81, Cl. D25-74.000.
- Schoenfeld, Palmer J., to Marvin Glass & Associates. Combined cash register and bar code reader toy. 261,289, 10-13-81, Cl. D21-111.000.
- Scholl, Winfried, to HEWI, Heinrich Wilke GmbH. Door knob. 261,223, 10-13-81, Cl. D8-312.000.
- SCM (Canada) Limited: See—
McMullan, Robert G., 261,235, Cl. D9-434.000.
- Scola, Vito A. Interlocking wedding band. 261,244, 10-13-81, Cl. D11-27.000.

LIST OF DESIGN PATENTEEES

- Scott & Fetzer Company, The: See—
Rutter, Sheldon, 261,268, Cl. D32-32.000.
- Seeley, Wayne R., to Emerson Electric Co. Insulator for an open-coil electric heating element. 261,260, 10-13-81, Cl. D13-18.000.
- Shames, Harold: See—
Shames, Sidney J.; and Shames, Harold, 261,202, Cl. D6-89.000.
- Shames, Sidney J.; and Shames, Harold, 261,203, Cl. D6-90.000.
- Shames, Sidney J.; and Shames, Harold, 261,204, Cl. D6-103.000.
- Shames, Sidney J.; and Shames, Harold, 261,205, Cl. D6-122.000.
- Shames, Sidney J.; and Shames, Harold, 261,226, Cl. D8-350.000.
- Shames, Sidney J.; and Shames, Harold, 261,227, Cl. D8-350.000.
- Shames, Sidney J.; and Shames, Harold, 261,228, Cl. D8-350.000.
- Shames, Sidney J.; and Shames, Harold. Soap dish for attachment to a frame. 261,202, 10-13-81, Cl. D6-89.000.
- Shames, Sidney J.; and Shames, Harold. Wall mounted soap dish. 261,203, 10-13-81, Cl. D6-90.000.
- Shames, Sidney J.; and Shames, Harold. Towel bar support post. 261,204, 10-13-81, Cl. D6-103.000.
- Shames, Sidney J.; and Shames, Harold. Double hook clothes support. 261,205, 10-13-81, Cl. D6-122.000.
- Shames, Sidney J.; and Shames, Harold. Wall plate for double electric switch. 261,226, 10-13-81, Cl. D8-350.000.
- Shames, Sidney J.; and Shames, Harold. Wall plate for double electric socket. 261,227, 10-13-81, Cl. D8-350.000.
- Shames, Sidney J.; and Shames, Harold. Wall plate. 261,228, 10-13-81, Cl. D8-350.000.
- Shaw, Jerry; and Solitt, Samuel G. Display unit and light fixtures therefor. 261,200, 10-13-81, Cl. D6-85.000.
- Shimano, Moto: See—
Carey, Bruce P.; Ishimaru, Lloyd Y.; and Shimano, Moto, 261,264, Cl. D14-14.000.
- Shohoji, Takeshi: See—
Sakamoto, Masakazu; and Shohoji, Takeshi, 261,297, Cl. D22-25.000.
- Snyder, Paul D., to Quaker Oats Company, The. Toy radio. 261,290, 10-13-81, Cl. D21-113.000.
- Soda, Koichi: See—
Hashimoto, Masanori; and Soda, Koichi, 261,277, Cl. D18-12.000.
- Solitt, Samuel G.: See—
Shaw, Jerry; and Solitt, Samuel G., 261,200, Cl. D6-85.000.
- Sterling, John G. Strike plate. 261,225, 10-13-81, Cl. D8-344.000.
- Sunbeam Corporation: See—
Haufe, David K., 261,237, Cl. D10-15.000.
- Swartz, Henry A. Unitized power convertor. 261,259, 10-13-81, Cl. D13-11.000.
- Syntex (U.S.A.) Inc.: See—
Marucci, N. Dominic; and Wright, David B., 261,301, Cl. D24-12.000.
- Takahashi, Hideo: See—
Kurokawa, Koya; Arai, Noriyuki; Takahashi, Hideo; and Saeki, Taisuke, 261,263, Cl. D14-2.000.
- Tatsumi, Masakazu: See—
Yoshida, Toshihiko; Tatsumi, Masakazu; Sakakibara, Seiichi; Kubo, Toshiaki; Akita, Tsugio; and Ueda, Yoshiaki, 261,266, Cl. D32-21.000.
- Thomas, Robert E.: See—
Thomas, Robert M.; and Thomas, Robert E., 261,284, Cl. D21-34.000.
- Thomas, Robert M.; and Thomas, Robert E. Backgammon gameboard. 261,284, 10-13-81, Cl. D21-34.000.
- Todd, James. Indoor/outdoor golf practice target. 261,295, 10-13-81, Cl. D21-234.000.
- Tong, Duncan, to Playart Limited. Clip for toy railway track. 261,292, 10-13-81, Cl. D21-143.000.
- U.G. Closures & Plastics Ltd.: See—
Mills, Frederick G. W., 261,212, Cl. D7-68.000.
- Ueda, Yoshiaki: See—
Yoshida, Toshihiko; Tatsumi, Masakazu; Sakakibara, Seiichi; Kubo, Toshiaki; Akita, Tsugio; and Ueda, Yoshiaki, 261,266, Cl. D32-21.000.
- Uematsu, Sakae: See—
Sakai, Masaaki; and Uematsu, Sakae, 261,273, Cl. D18-7.000.
- Vest, Gary W.; and Loase, James C., to New Era Products, Inc. Battery tester. 261,240, 10-13-81, Cl. D10-77.000.
- Vetter, Bruce W.: See—
Perethian, Charles M.; Le Compte, Marcia L.; and Vetter, Bruce W., 261,213, Cl. D7-77.000.
- Weiss, Howard K., to Glen Shoe Company. Shoe. 261,195, 10-13-81, Cl. D2-279.000.
- Wheeler, Michael R. Surgical caliper. 261,302, 10-13-81, Cl. D24-26.000.
- White Consolidated Industries, Inc.: See—
Samczyk, Casimir S., 261,271, Cl. D16-31.000.
- Whiting, Richard J. Mirror. 261,208, 10-13-81, Cl. D6-234.000.
- Williams, Robert P., to Baxter Travenol Laboratories, Inc. Closure assembly for liquid container. 261,236, 10-13-81, Cl. D9-435.000.
- Wilson, Donald C. Simulative toy vehicle. 261,291, 10-13-81, Cl. D21-128.000.
- Wright, David B.: See—
Marucci, N. Dominic; and Wright, David B., 261,301, Cl. D24-12.000.
- Yamazaki, Naoki; Kojima, Hiroshi; and Nishio, Hideaki, to Bridgestone Tire Co., Ltd. Vehicle tire. 261,256, 10-13-81, Cl. D12-148.000.
- Yoshida, Toshihiko; Tatsumi, Masakazu; Sakakibara, Seiichi; Kubo, Toshiaki; Akita, Tsugio; and Ueda, Yoshiaki, to Matsushita Electric Industrial Co., Ltd. Vacuum cleaner. 261,266, 10-13-81, Cl. D32-21.000.

LIST OF PLANT PATENTEEES

- Enright, Paul C. Gazania plant. 4,775, 10-13-81, Cl. 68.000.
- Holtkamp, Reinhold. African violet plant. 4,776, 10-13-81, Cl. 69.000.
- Holtkamp, Reinhold. African violet plant. 4,777, 10-13-81, Cl. 69.000.

CLASSIFICATION OF PATENTS

ISSUED OCTOBER 13, 1981

NOTE.—First number, class; second number, subclass; third number, patent number

CLASS 2	831	4,294,008	213	4,294,595	662	4,294,121	CLASS 106	77	4,294,237
2.1 R	4,293,957	832	4,294,009	242	4,294,596	761	4,294,122	80 G	4,294,238
12	4,293,958	CLASS 30		283	4,294,597	861.92	4,294,123	96	4,294,239
243 B	4,293,959	42	4,294,010	403	4,294,598	862.23	4,294,110	156	4,294,240
416	4,293,960	106	4,294,011	485	4,294,599	863.85	4,294,124	288 Q	4,294,241
CLASS 3		378	4,294,012	CLASS 56		864.15	4,294,125	306	4,294,242
1.7	4,293,961	392	4,294,013	16.4	4,294,063	864.21	4,294,126	314	4,294,243
1.9	4,293,962	CLASS 33		102	4,294,062	864.85	4,294,127	CLASS 108	201.13
1.91	4,293,963	3 C	4,294,014	CLASS 57		CLASS 74		202.26	4,294,244
CLASS 4		174 D	4,294,015	3	4,294,064	5.44	4,294,128	42	4,294,245
378	4,293,964	180 AT	4,294,016	265	4,294,065	7 A	4,294,129	CLASS 110	207.21
CLASS 5		265	4,294,017	274	4,294,066	15.4	4,294,130	214 D	4,294,247
465	4,293,965	CLASS 34		CLASS 60		462	4,294,131	214 E	4,294,246
CLASS 6		56	4,294,018	204	4,294,068	501 P	4,294,132	214 G	4,294,248
12 R	4,293,966	65	4,294,019	238	4,294,069	547	4,294,133	214 H	4,294,249
CLASS 8		168	4,294,020	534	4,294,070	573 R	4,294,135	214 I	4,294,250
111	4,294,575	224	4,294,021	547 A	4,294,071	600	4,294,136	214 J	4,294,251
137.5	4,294,576	CLASS 36		585	4,294,072	665 G	4,294,137	214 K	4,294,252
488	4,294,577	4	4,294,022	597	4,294,073	750 B	4,294,138	214 L	4,294,253
516	4,294,578	11.5	4,294,023	616	4,294,074	839	4,294,139	214 M	4,294,254
549	4,294,579	113	4,294,024	671	4,294,075	868	4,294,140	214 N	4,294,255
611	4,294,580	132	4,294,025	CLASS 62		CLASS 75		214 O	4,294,256
CLASS 9		8	4,294,026	6	4,294,077	0.5 A	4,294,608	214 P	4,294,257
1.6	4,293,967	43 R	4,294,027	59	4,294,600	34	4,294,609	214 Q	4,294,258
310 A	4,293,968	CLASS 40		60	4,294,078	43	4,294,610	214 R	4,294,259
CLASS 13		359	4,294,028	101	4,294,079	49	4,294,611	214 S	4,294,260
13	4,295,000	388	4,294,029	115	4,294,080	68 R	4,294,612	214 T	4,294,261
17	4,295,001	CLASS 43		140	4,294,081	128 A	4,294,613	214 U	4,294,262
CLASS 14		4	4,294,030	235.1	4,294,076	175.5	4,294,615	214 V	4,294,263
71.1	4,293,969	43.16	4,294,031	244	4,294,077	234	4,294,616	214 W	4,294,264
CLASS 15		23	4,294,584	434	4,294,083	CLASS 81		214 X	4,294,265
21 D	4,293,970	53	4,294,585	CLASS 63		3 R	4,294,141	214 Y	4,294,266
98	4,293,971	56	4,294,586	15	4,294,084	57.37	4,294,142	214 Z	4,294,267
145	4,293,972	74	4,294,587	CLASS 65		CLASS 83		214 AA	4,294,268
230.17	4,293,973	CLASS 46		3.12	4,294,601	37	4,294,143	214 AB	4,294,269
250.32	4,293,974	118	4,294,032	40	4,294,602	71	4,294,144	214 AC	4,294,270
250.41	4,293,975	145	4,294,033	346	4,294,603	302	4,294,145	214 AD	4,294,271
CLASS 16		118	4,294,034	CLASS 66		316	4,294,146	214 AE	4,294,272
129	4,293,976	161	4,294,035	75.1	4,294,085	382	4,294,147	214 AF	4,294,273
CLASS 17		242	4,294,036	121	4,294,086	397	4,294,148	214 AG	4,294,274
11	4,293,977	CLASS 47		CLASS 69		435.1	4,294,149	214 AH	4,294,275
12	4,293,978	59	4,294,037	21	4,294,087	453	4,294,150	214 AI	4,294,276
32	4,293,979	CLASS 49		56	4,294,088	477.2	4,294,151	214 AJ	4,294,277
51	4,293,980	63	4,294,038	150	4,294,089	588	4,294,152	214 AK	4,294,278
71	4,293,981	226	4,294,039	226	4,294,090	CLASS 84		214 AL	4,294,279
CLASS 19		276	4,294,040	364 A	4,294,091	1.01	4,294,153	214 AM	4,294,280
80 A	4,293,982	254	4,294,041	369	4,294,092	CLASS 89		214 AN	4,294,281
127	4,293,983	CLASS 51		CLASS 71		1 G	4,294,157	214 AO	4,294,282
230 B	4,294,582	5 C	4,294,042	27	4,294,604	12	4,294,158	214 AP	4,294,283
232 R	4,294,583	100 R	4,294,043	73	4,294,605	CLASS 91		214 AQ	4,294,284
CLASS 24		135 BT	4,294,044	88	4,294,606	375 A	4,294,159	214 AR	4,294,285
221 R	4,293,984	165.71	4,294,045	92	4,294,607	378	4,294,160	214 AS	4,294,286
CLASS 28		170 R	4,294,046	CLASS 72		422	4,294,161	214 AT	4,294,287
254	4,293,985	327	4,294,047	16	4,294,094	434	4,294,162	214 AU	4,294,288
CLASS 29		CLASS 52		51	4,294,095	CLASS 92		214 AV	4,294,289
25.35	4,293,986	9	4,294,048	60	4,294,096	52	4,294,163	214 AW	4,294,290
25.42	4,293,987	20	4,294,049	94	4,294,097	243	4,294,164	214 AX	4,294,291
116 AD	4,293,988	93	4,294,050	128	4,294,098	CLASS 98		214 AY	4,294,292
130	4,293,989	98	4,294,051	234	4,294,099	1	4,294,165	214 AZ	4,294,293
148.4 D	4,293,990	236.5	4,294,052	340	4,294,100	CLASS 99		214 BA	4,294,294
243.52	4,293,991	295	4,294,053	356	4,294,101	348	4,294,166	214 BB	4,294,295
267	4,293,992	484	4,294,054	413	4,294,102	369	4,294,167	214 BC	4,294,296
278	4,293,993	795	4,294,055	453.14	4,294,103	494	4,294,168	214 BD	4,294,297
409	4,293,994	CLASS 53		CLASS 73		494	4,294,168	214 BE	4,294,298
421 R	4,293,995	86	4,294,056	9	4,294,104	CLASS 100		214 BF	4,294,299
446	4,293,996	244	4,294,057	28	4,294,105	48	4,294,169	214 BG	4,294,300
450	4,293,997	413	4,294,058	40.7	4,294,106	216	4,294,170	214 BH	4,294,301
564.1	4,293,998	448	4,294,059	49.2	4,294,107	CLASS 102		214 BI	4,294,302
564.6	4,293,999	506	4,294,060	119 A	4,294,108	281	4,294,173	214 BJ	4,294,303
571	4,294,000	536	4,294,061	150 R	4,294,109	317	4,294,171	214 BK	4,294,304
611	4,294,001	CLASS 55		162	4,294,111	473	4,294,172	214 BL	4,294,305
622	4,294,002	5	4,294,588	199	4,294,113	CLASS 104		214 BM	4,294,306
623.5	4,294,003	36	4,294,589	204	4,294,114	250	4,294,174	214 BN	4,294,307
701	4,294,004	48	4,294,590	342	4,294,115	CLASS 105		214 BO	4,294,308
830	4,294,005	120	4,294,591	362 AR	4,294,116	199 R	4,294,175	214 BP	4,294,309
	4,294,006	166	4,294,592	620	4,294,118	363	4,294,176	214 BQ	4,294,310
	4,294,007	186	4,294,594	650	4,294,120			214 BR	4,294,311

CLASSIFICATION OF PATENTS

CLASS 150	CLASS 184	513	4,294,702	36	4,294,413	413	4,294,770
28 R	4,294,299	106	4,294,333	631	4,294,703	136	4,294,771
CLASS 152	CLASS 188	651	4,294,704	222	4,294,414	156	4,294,772
427	4,294,301	695	4,294,705	292	4,294,415	166	4,294,773
CLASS 156	18 A	762	4,294,706	18 G	4,294,416	167	4,294,774
59	4,294,634	782	4,294,707	149	4,294,417	188	4,294,775
89	4,294,635	49 D	4,294,363	197	4,294,418	367	4,294,776
143	4,294,636	60 R	4,294,364	117 R	4,294,419	452	4,294,777
157	4,294,637	171	4,294,365	165	4,294,420	67	Re.30,769
176	4,294,638	0.073	4,294,341	CLASS 244	4,294,421	CLASS 299	CLASS 301
180	Re.30,770	4 A	4,294,338	37.6	4,294,422	63 DD	4,294,491
185	4,294,639	12 BA	4,294,339	48.2	4,294,423	63 PW	4,294,490
196	Re.30,771	56 R	4,294,340	246	4,294,424	CLASS 307	CLASS 308
213	4,294,640	105 CD	4,294,342	256	4,294,425	10 R	4,295,052
234	4,294,641	113 A	4,294,343	311	4,294,426	64	4,295,053
250	4,294,642	CLASS 198	4,294,344	329	4,294,427	80	4,295,054
293	4,294,643	461	4,294,345	561	4,294,428	221 C	4,295,055
361	4,294,644	683	4,294,346	226	4,295,042	231	4,295,056
384	4,294,645	740	4,294,347	227	4,295,043	252 A	4,295,057
500	4,294,646	751	4,294,348	229	4,295,044	279	4,295,058
558	4,294,647	CLASS 200	4,295,012	255	4,295,045	362	4,295,063
627	4,294,648	5 B	4,295,013	287	4,295,046	468	4,295,064
645	4,294,649	11 C	4,295,014	363 S	4,295,047	475	4,295,065
660	4,294,650	19 R	4,295,015	398	4,295,048	CLASS 308	CLASS 309
662	4,294,651	38 R	4,295,016	409	4,295,049	8.2	4,294,492
2 R	4,294,652	44	4,295,017	479	4,295,050	10	4,294,493
CLASS 159	CLASS 160	47	4,295,018	569	4,295,051	76	4,294,494
133	4,294,302	51.09	4,295,019	CLASS 220	4,295,052	174	4,294,495
CLASS 162	4,294,303	61.2	4,295,020	4 E	4,294,371	CLASS 310	CLASS 311
25	4,294,653	61.45 R	4,295,021	20	4,294,372	30	4,295,066
50	4,294,654	147 R	4,295,022	70	4,294,373	52	4,295,067
107	4,294,655	148 R	4,295,023	71	4,294,374	67 R	4,295,068
192	4,294,656	288	4,295,024	293	4,294,375	70 R	4,295,069
303	4,294,657	331	4,295,025	318	4,294,376	213	4,295,071
CLASS 164	CLASS 165	39	4,294,663	321	4,294,377	CLASS 312	CLASS 313
44	4,294,303	323	4,295,026	404	4,294,378	30	4,295,072
150	4,294,305	CLASS 201	4,294,663	404	4,294,379	52	4,295,073
448	4,294,306	CLASS 203	4,294,664	12	4,294,712	105 CM	4,295,074
504	4,294,307	19	4,294,665	28	4,294,713	174	4,295,075
CLASS 166	4,294,308	50	4,294,666	34	4,294,714	220	4,295,076
1	4,294,309	72	4,294,667	68	4,294,715	293	4,295,077
18	Re.30,766	CLASS 204	4,294,667	97	4,294,716	CLASS 315	CLASS 316
41	4,294,311	1 T	4,294,668	135	4,294,717	8	4,295,078
104 S	4,294,312	15	4,294,669	182	4,294,718	130	4,295,079
104.13	4,294,313	26	4,294,670	373	4,294,719	CLASS 318	CLASS 319
133	4,294,659	129.4	4,294,671	429 B	4,294,720	257	4,295,080
134 R	4,294,312	129.46	4,294,672	435	4,294,721	327	4,295,081
CLASS 166	4,294,313	157.1 H	4,294,673	440	4,294,722	599	4,295,082
117.5	4,294,313	159.14	4,294,674	451	4,294,723	696	4,295,083
261	Re.30,767	159.23	4,294,675	455 Z	4,294,724	719	4,295,084
318	4,294,314	181 F	4,294,676	462	4,294,725	721	4,295,085
322	4,294,315	192 R	4,294,677	462	4,294,726	759	4,295,086
CLASS 172	4,294,316	195 S	4,294,678	522 R	4,294,727	CLASS 322	CLASS 323
20	4,294,317	224 R	4,294,680	542	4,294,728	99	4,295,087
CLASS 173	4,294,317	244	4,294,682	545	4,294,729	CLASS 324	CLASS 325
57	4,294,317	258	4,294,684	272	4,294,429	60 CD	4,295,090
CLASS 174	4,294,317	299 R	4,294,684	58	4,294,430	61 R	4,295,091
53	4,295,003	CLASS 206	4,294,348	111	4,294,392	77 B	4,295,093
87	4,295,004	1.7	4,294,349	134	4,294,393	96	4,295,094
92	4,295,005	63.5	4,294,350	158	4,294,394	326	4,295,095
CLASS 175	4,295,005	216	4,294,351	220	4,294,395	429	4,295,097
321	4,294,318	222	4,294,352	245	4,294,396	CLASS 328	CLASS 329
389	4,294,319	223	4,294,353	CLASS 229	4,294,396	24	4,295,098
CLASS 177	4,294,320	227	4,294,354	15	4,294,398	151	4,295,099
1	4,294,321	273	4,294,355	27	4,294,399	65	4,295,102
210 FP	4,294,322	335	4,294,356	44 CB	4,294,400	94.5 C	4,295,104
210 R	4,294,322	339	4,294,357	68 R	4,294,400	94.5 PE	4,295,103
CLASS 179	4,294,322	368	4,294,358	CLASS 234	4,295,041	CLASS 332	CLASS 333
1 E	4,295,006	409	4,294,359	487	4,295,041	9 R	4,295,105
7 R	4,295,007	419	4,294,358	CLASS 235	4,295,036	37 R	4,295,106
18 BC	4,295,008	422	4,294,359	92 PD	4,295,037	CLASS 281	CLASS 282
110 A	4,295,009	438	4,294,360	92 PK	4,295,038	29	4,294,469
115.5 VC	4,295,011	622	4,294,362	379	Re.30,773	CLASS 285	CLASS 286
CLASS 180	4,294,323	379	4,294,362	380	4,294,747	5	4,294,470
54 B	4,294,324	458	4,294,363	458	4,294,749	24	4,294,471
89.14	4,294,325	CLASS 208	4,294,685	CLASS 236	4,294,750	133 R	4,294,474
148	4,294,326	10	4,294,686	12 R	4,294,751	165	4,294,475
255	4,294,327	56	4,294,687	13	4,294,752	189	4,294,476
273	4,294,327	58	4,294,688	49	4,294,753	336	4,294,477
CLASS 181	4,294,328	164	4,294,689	112 R	4,294,754	CLASS 293	CLASS 294
120	4,294,329	326	4,294,690	112.5 R	4,294,755	82 R	4,294,479
222	4,294,330	3	4,294,691	154	4,294,756	131	4,294,480
230	4,294,331	3.1	4,294,692	239.3 D	4,294,757	146	4,294,481
CLASS 182	4,294,332	300	4,294,693	239.3 P	4,294,758	CLASS 295	CLASS 296
10	4,294,333	466	4,294,694	326.27	4,294,759	34	4,294,482
141	4,294,333	273	4,294,695	326.47	4,294,760	CLASS 330	CLASS 331
CLASS 183	4,294,333	150	4,294,696	338	4,294,761	257	4,295,100
120	4,294,334	173	4,294,697	340.3	4,294,762	262	4,295,101
222	4,294,335	220	4,294,698	340.5 DP	4,294,763	CLASS 332	CLASS 333
230	4,294,336	221.1	4,294,699	340.9 R	4,294,764	65	4,295,102
CLASS 184	4,294,337	242.3	4,294,700	343.3 R	4,294,765	94.5 C	4,295,104
10	4,294,338	287	4,294,701	343.6	4,294,766	94.5 PE	4,295,103
141	4,294,339	497.2	4,294,702	347.8	4,294,767	CLASS 334	CLASS 335
CLASS 185	4,294,340	497.2	4,294,703	372	4,294,768	9 R	4,295,105
141	4,294,341	497.2	4,294,704	400 R	4,294,769	37 R	4,295,106

CLASSIFICATION OF PATENTS

CLASS 333	CLASS 353	200	4,295,192	CLASS 411	646	4,294,865	CLASS 521		
25	4,295,107	84	4,295,193	103	4,294,570	2	4,294,933		
193	4,295,108	414	4,295,194	185	4,294,300	2	4,294,934		
249	4,295,109	501	4,295,195	345	4,294,156	96	CLASS 525		
CLASS 335	CLASS 354	510	4,295,196	CLASS 414	109	4,294,868	60	4,294,935	
212	4,295,110	515	4,295,197	537	4,294,571	177	4,294,869	60	4,294,936
256	4,295,111	555	4,295,198	641	4,294,572	189	4,294,870	99	4,294,937
CLASS 336	CLASS 355	561	4,295,201	83	4,294,573	237	4,294,871	101	4,294,938
84 M	4,295,112	748	4,295,202	CLASS 417	358	4,294,872	118	4,294,939	
CLASS 337	CLASS 356	824	4,295,203	391	4,294,873	124	4,294,874	124	4,294,940
3	4,295,114	900	4,295,204	393	4,294,874	170	4,294,875	170	4,294,941
CLASS 338	CLASS 357	36	4,294,797	CLASS 422	72	4,294,875	314	4,294,942	
4	4,295,115	62	4,294,798	62	4,294,798	358	4,294,943		
32 H	4,295,116	68	4,294,799	68	4,294,800	421	4,294,944		
162	4,295,117	98	4,294,801	103	4,294,802	423	4,294,945		
CLASS 339	CLASS 358	178	4,294,803	111	4,294,804	74	4,294,946		
5 M	4,295,120	227	4,294,804	CLASS 423	361	4,294,883	119	4,294,947	
66 M	4,295,121	1	4,294,547	361	4,294,883	262	4,294,948		
112 L	4,295,122	60	4,294,548	364	4,294,884	314	4,294,949		
119 L	4,295,123	164	4,294,549	404	4,294,885	358	4,294,950		
132 R	4,295,124	CLASS 367	4,295,211	412	4,294,886	421	4,294,951		
231	4,295,125	242	4,295,212	423.1	4,294,887	14	4,294,952		
CLASS 340	CLASS 359	305	4,295,213	451	4,294,888	55	4,294,953		
146.3 MA	4,295,126	321 R	4,295,214	515	4,294,889	67	4,294,954		
147 LP	4,295,127	350	4,295,215	641	4,294,890	128	4,294,955		
347 AD	4,295,128	357	4,295,216	CLASS 429	2	4,294,891	179	4,294,956	
347 DD	4,295,129	385	4,295,217	13	4,294,892	179	4,294,957		
CLASS 341	CLASS 360	478	4,295,218	42	4,294,893	CLASS 536	17 R	4,294,958	
30	4,295,126	484	4,295,219	84	4,294,894	4,294,959	CLASS 544	22	4,294,960
52	4,295,127	CLASS 370	4,295,220	104	4,294,895	49	4,294,961		
67 R	4,295,128	8	4,295,221	206	4,294,896	192	4,294,962		
70 R	4,295,129	12	4,295,222	22	4,294,897	198	4,294,963		
213	4,295,130	14	4,294,817	49	4,294,898	249	4,294,964		
CLASS 342	CLASS 361	28	4,294,818	7	4,294,899	297	4,294,965		
7	4,295,131	45	4,294,819	39	4,294,901	316	4,294,966		
CLASS 343	CLASS 362	49	4,294,820	45	4,294,902	CLASS 546	242	4,294,967	
100 PE	4,295,140	51	4,294,821	78	4,294,903	251	4,294,968		
753	4,295,141	61	4,294,822	98	4,294,904	286	4,294,969		
781 CA	4,295,142	101	4,294,823	122	4,294,905	294	4,294,970		
840	4,295,143	226	4,294,824	175	4,294,906	CLASS 548	226	4,294,971	
895	4,295,144	232	4,294,825	207	4,294,907	264	4,294,972		
CLASS 346	CLASS 363	241	4,294,826	213	4,294,908	320	4,294,973		
108	4,295,145	258	4,294,827	286	4,294,909	CLASS 556	440	4,294,974	
140 R	4,295,146	260	4,294,828	291	4,294,910	482	4,294,975		
CLASS 350	CLASS 364	263	4,294,829	302	4,294,911	CLASS 560	76	4,294,976	
6.8	4,294,506	263	4,294,830	326	4,294,912	CLASS 562	407	4,294,977	
96.13	4,294,507	278	4,294,831	341	4,294,913	503	4,294,978		
96.15	4,294,508	279 Q	4,294,832	396	4,294,914	4,294,979	4,294,980		
96.17	4,294,509	278	4,294,833	418	4,294,915	4,294,981	4,294,982		
96.18	4,294,510	278	4,294,834	522	4,294,916	4,294,983	4,294,984		
96.20	4,294,511	302	4,294,835	553	4,294,917	CLASS 564	18	4,294,985	
96.29	4,294,512	305	4,294,836	559	4,294,918	32	4,294,986		
96.31	4,294,513	309	4,294,837	569	4,294,919	331	4,294,987		
174	4,294,514	267	4,294,838	621	4,294,920	417	4,294,988		
335	4,294,515	272	4,294,839	72	4,295,223	CLASS 568	13	4,294,989	
345	4,294,516	273 R	4,294,840	156	4,295,224	601	4,294,990		
357	4,294,517	278 Q	4,294,841	601	4,295,225	632	4,294,991		
426	4,294,521	279	4,294,842	618	4,295,226	650	4,294,992		
CLASS 351	CLASS 365	291	4,294,843	213	4,294,924	724	4,294,993		
2	4,294,522	99	4,294,844	CLASS 426	4,294,856	728	4,294,994		
86	4,294,523	410	4,294,845	475	4,294,857	855	4,294,995		
CLASS 352	CLASS 366	502	4,294,846	538	4,294,858	868	4,294,996		
CLASS 353	CLASS 367	549	4,294,847	549	4,294,859	910	4,294,997		
CLASS 354	CLASS 368	72 R	4,294,848	559	4,294,860	918	4,294,998		
CLASS 355	CLASS 369	244	4,294,849	569	4,294,861	924	4,294,999		
CLASS 356	CLASS 370	133	4,294,850	579	4,294,862	930	4,294,999		
CLASS 357	CLASS 371	113	4,294,851	589	4,294,863	936	4,294,999		
CLASS 358	CLASS 372	114	4,294,852	599	4,294,864	942	4,294,999		
CLASS 359	CLASS 373	114	4,294,853	609	4,294,865	948	4,294,999		
CLASS 360	CLASS 374	114	4,294,854	619	4,294,866	954	4,294,999		
CLASS 361	CLASS 375	114	4,294,855	629	4,294,867	960	4,294,999		
CLASS 362	CLASS 376	114	4,294,856	639	4,294,868	966	4,294,999		
CLASS 363	CLASS 377	114	4,294,857	649	4,294,869	972	4,294,999		
CLASS 364	CLASS 378	114	4,294,858	659	4,294,870	978	4,294,999		
CLASS 365	CLASS 379	114	4,294,859	669	4,294,871	984	4,294,999		
CLASS 366	CLASS 380	114	4,294,860	679	4,294,872	990	4,294,999		
CLASS 367	CLASS 381	114	4,294,861	689	4,294,873	996	4,294,999		
CLASS 368	CLASS 382	114	4,294,862	699	4,294,874	1002	4,294,999		
CLASS 369	CLASS 383	114	4,294,863	709	4,294,875	1008	4,294,999		
CLASS 370	CLASS 384	114	4,294,864	719	4,294,876	1014	4,294,999		
CLASS 371	CLASS 385	114	4,294,865	729	4,294,877	1020	4,294,999		
CLASS 372	CLASS 386	114	4,294,866	739	4,294,878	1026	4,294,999		
CLASS 373	CLASS 387	114	4,294,867	749	4,294,879	1032	4,294,999		
CLASS 374	CLASS 388	114	4,294,868	759	4,294,880	1038	4,294,999		
CLASS 375	CLASS 389	114	4,294,869	769	4,294,881	1044	4,294,999		
CLASS 376	CLASS 390	114	4,294,870	779	4,294,882	1050	4,294,999		
CLASS 377	CLASS 391	114	4,294,871	789	4,294,883	1056	4,294,999		
CLASS 378	CLASS 392	114	4,294,872	799	4,294,884	1062	4,294,999		
CLASS 379	CLASS 393	114	4,294,873	809	4,294,885	1068	4,294,999		
CLASS 380	CLASS 394	114	4,294,874	819	4,294,886	1074	4,294,999		
CLASS 381	CLASS 395	114	4,294,875	829	4,294,887	1080	4,294,999		
CLASS 382	CLASS 396	114	4,294,876	839	4,294,888	1086	4,294,999		
CLASS 383	CLASS 397	114	4,294,877	849	4,294,889	1092	4,294,999		
CLASS 384	CLASS 398	114	4,294,878	859	4,294,890	1098	4,294,999		
CLASS 385	CLASS 399	114	4,294,879	869	4,294,891	1104	4,294,999		
CLASS 386	CLASS 400	114	4,294,880	879	4,294,892	1110	4,294,999		
CLASS 387	CLASS 401	114	4,294,881	889	4,294,893	1116	4,294,999		
CLASS 388	CLASS 402	114	4,294,882	899	4,294,894	1122	4,294,999		
CLASS 389	CLASS 403	114	4,294,883	909	4,294,895	1128	4,294,999		
CLASS 390	CLASS 404	114	4,294,884	919	4,294,896	1134	4,294,999		
CLASS 391	CLASS 405	114	4,294,885	929	4,294,897	1140	4,294,999		
CLASS 392	CLASS 406	114	4,294,886	939	4,294,898	1146	4,294,999		
CLASS 393	CLASS 407	114	4,294,887	949	4,294,899	1152	4,294,999		
CLASS 394	CLASS 408	114	4,294,888	959	4,294,900	1158	4,294,999		
CLASS 395	CLASS 409	114	4,294,889	969	4,294,901	1164	4,294,999		
CLASS 396	CLASS 410	114	4,294,890	979	4,294,902	1170	4,294,999		
CLASS 397	CLASS 411	114	4,294,891	989	4,294,903	1176	4,294,999		
CLASS 398	CLASS 412	114	4,294,892	999	4,294,904	1182	4,294,999		
CLASS 399	CLASS 413	114	4,294,893	1009	4,294,905	1188	4,294,999		
CLASS 400	CLASS 414	114	4,294,894	1019	4,294,906	1194	4,294,999		
CLASS 401	CLASS 415	114	4,294,895	1029	4,294,907	1200	4,294,999		
CLASS 402	CLASS 416	114	4,294,896	1039	4,294,908	1206	4,294,999		
CLASS 403	CLASS 417	114	4,294,897	1049	4,294,909	1212	4,294,999		
CLASS 404	CLASS 418	114	4,294,898	1059	4,294,910	1218	4,294,999		
CLASS 405	CLASS 419	114	4,294,899	1069	4,294,911	1224	4,294,999		
CLASS 406	CLASS 420	114	4,294,900	1079	4,294,912	1230	4,294,999		
CLASS 407	CLASS 421	114	4,294,901	1089	4,294,913	1236	4,294,999		
CLASS 408	CLASS 422	114	4,294,902	1099	4,294,914	1242	4,294,999		
CLASS 409	CLASS 423	114	4,294,903	1109	4,294,915	1248	4,294,999		
CLASS 410	CLASS 424	114	4,294,904	1119	4,294,916	1254	4,294,999		
CLASS 411	CLASS 425	114	4,294,905	1129	4,294,917	1260	4,294,999		
CLASS 412	CLASS 426	114	4,294,906	1139	4,294,918	1266	4,294,999		
CLASS 413	CLASS 427	114	4,294,907	1149	4,294,919	1272	4,294,999		
CLASS 414	CLASS 428	114	4,294,908	1159	4,294,920	1278	4,294,999		
CLASS 415	CLASS 429	114	4,294,909	1169	4,294,921	1284	4,294,999		
CLASS 416	CLASS 430	114	4,294,910	1179	4,294,922	1290	4,294,999		
CLASS 417	CLASS 431	114	4,294,911	1189	4,294,923	1296	4,294,999		
CLASS 418	CLASS 432	114	4,294,912	1199	4,294,924	1302	4,294,999		
CLASS 419	CLASS 433	114	4,294,913	1209	4,294,925	1308	4,294,999		
CLASS 420	CLASS 434	114	4,294,914	1219	4,294,926	1314	4,294,999		
CLASS 421	CLASS 435	114	4,294,915	1229	4,294,927	1320	4,294,999		
CLASS 422	CLASS 436	114	4,294,916	1239	4,294,928	1326	4,294,999		
CLASS 423	CLASS 437	114	4,294,917	1249	4,294,929	1332	4,		

CLASSIFICATION OF DESIGNS

D2—	279	261,195		137	261,216		77	261,240		35	261,261		65	261,285			261,306	
	383	261,196			208	261,220		91	261,241			261,262		87	261,286		261,307	
	400	261,197	D8—	02	261,221		106	261,242	D14—	2	261,263				261,287		261,308	
		261,198		68	261,222		121	261,243		14	261,264		89		261,288		261,309	
D3—	7	261,199		312	261,223		27	261,244		59	261,265		111		261,289		261,310	
D6—	85	261,200		323	261,224		75	261,245	D15—	116	261,269		113		261,290		261,311	
		261,201		344	261,225			261,246		199	261,270				261,291		261,312	
	89	261,202		350	261,226			261,247	D16—	31	261,271		143		261,292		261,313	
	90	261,203			261,227		121	261,248		32	261,272		151		261,293		261,314	
	103	261,204			261,228		128	261,249	D18—	7	261,273		195		261,294		261,315	
	122	261,205			261,229			261,250			261,274		234		261,295		261,316	
	143	261,206	D9—	367	261,230		157	261,251		10	261,275	D22—	5		261,296	D28—	35	261,317
	144	261,207		370	261,231		158	261,252		12	261,276		25		261,297		261,318	
	197	261,209			261,232			261,253			261,277		27		261,298		261,319	
	234	261,208		398	261,233			261,254		27	261,278				261,299		261,320	
	286	261,210		432	261,234		163	261,255	D19—	62	261,279	D23—	35		261,300	D32—	21	261,266
D7—	13	261,211		434	261,235	D12—	146	261,257		76	261,280	D24—	12		261,301		261,267	
	68	261,212		435	261,236		148	261,256	D20—	38	261,281		26		261,302		32	261,268
	77	261,213	D10—	15	261,237		189	261,258	D21—	24	261,282		38		261,303		49	261,217
	84	261,214		61	261,238	D13—	11	261,259		33	261,283	D25—	74		261,304		73	261,219
	131	261,215		64	261,239		18	261,260		34	261,284				261,305	D34—	1	261,218

CLASSIFICATION OF PLANTS

P.—	68	4,775	69	4,776	4,777			
-----	----	-------	----	-------	-------	--	--	--

GEOGRAPHICAL INDEX
OF RESIDENCE OF INVENTORS

(U.S. States, Territories and Armed Forces, the Commonwealth of Puerto Rico, and the Canal Zone)

Alabama	1	Kentucky	21	Oregon	41
Alaska	2	Louisiana	22	Pennsylvania	42
American Samoa	3	Maine	23	Puerto Rico	43
Arizona	4	Maryland	24	Rhode Island	44
Arkansas	5	Massachusetts	25	South Carolina	45
California	6	Michigan	26	South Dakota	46
Canal Zone	7	Minnesota	27	Tennessee	47
Colorado	8	Mississippi	28	Texas	48
Connecticut	9	Missouri	29	Utah	49
Delaware	10	Montana	30	Vermont	50
District of Columbia	11	Nebraska	31	Virginia	51
Florida	12	Nevada	32	Virgin Islands	52
Georgia	13	New Hampshire	33	Washington	53
Guam	14	New Jersey	34	West Virginia	54
Hawaii	15	New Mexico	35	Wisconsin	55
Idaho	16	New York	36	Wyoming	56
Illinois	17	North Carolina	37	U.S. Air Force	57
Indiana	18	North Dakota	38	U.S. Army	58
Iowa	19	Ohio	39	U.S. Navy	59
Kansas	20	Oklahoma	40		

(First number in listing denotes location according to above key. Refer to patent number in body of the Official Gazette to obtain details as to inventor name, location, etc.)

PATENTS

9 :	4,294,029	4,294,569	4,294,515	16 :	4,294,181	4,294,203	4,294,077
01 :	4,294,363	4,294,573	4,294,517	17 :	Re.30,766	4,294,254	4,294,113
	4,294,654	4,294,596	4,294,577		Re.30,769	4,294,338	4,294,135
	4,295,197	4,294,635	4,294,594		4,294,004	4,294,381	4,294,193
04 :	4,294,026	4,294,640	4,294,595		4,294,008	4,294,382	4,294,371
	4,294,061	4,294,655	4,294,601		4,294,033	4,294,476	4,294,400
	4,294,246	4,294,714	4,294,603		4,294,054	4,294,495	4,294,414
	4,294,807	4,294,753	4,294,615		4,294,084	4,294,930	4,294,472
	4,294,875	4,294,799	4,294,670		4,294,090	4,294,953	4,294,497
	4,294,886	4,294,817	4,294,713		4,294,218	4,294,964	4,294,508
	4,295,001	4,294,844	4,294,778		4,294,247	4,295,069	4,294,531
	4,295,063	4,294,853	4,294,798		4,294,250	4,295,078	4,294,550
05 :	4,293,981	4,294,860	4,294,970		4,294,278	4,295,117	4,294,599
	4,294,604	4,294,923	4,295,083		4,294,283	4,295,160	4,294,600
06 :	Re.30,773	4,294,928	4,295,187		4,294,302	4,295,161	4,294,608
	4,293,977	4,294,977	4,294,489		4,294,303	4,295,163	4,294,652
	4,294,011	4,294,986	4,294,489	10 :	4,294,317	4,295,166	4,294,671
	4,294,055	4,295,044	4,294,736		4,294,320	4,295,174	4,294,701
	4,294,059	4,295,051	4,294,738		4,294,358	4,295,209	4,294,792
	4,294,163	4,295,062	4,294,742		4,294,391	4,295,299	4,294,888
	4,294,177	4,295,105	4,294,743		4,294,397	4,295,019	4,294,907
	4,294,179	4,295,111	4,294,877		4,294,442	4,295,078	4,294,915
	4,294,183	4,295,124	4,294,938		4,294,465	4,294,275	4,294,924
	4,294,201	4,295,125	4,294,955		4,294,469	4,294,500	4,294,945
	4,294,208	4,295,132	4,294,998		4,294,541	4,294,864	4,294,974
	4,294,222	4,295,135	4,294,558	12 :	4,294,558	4,294,289	4,295,011
	4,294,237	4,295,140	4,293,964		4,294,574	4,294,051	4,295,016
	4,294,242	4,295,145	4,293,990		4,294,586	4,294,331	4,295,075
	4,294,249	4,295,153	4,294,069		4,294,619	4,294,383	4,295,089
	4,294,267	4,295,192	4,294,083		4,294,685	4,294,480	4,295,116
	4,294,270	4,295,199	4,294,107		4,294,687	4,294,589	4,295,129
	4,294,276	4,295,205	4,294,124		4,294,737	4,294,688	4,295,137
	4,294,308	4,295,214	4,294,151		4,294,780	4,294,774	4,295,162
	4,294,314	4,295,218	4,294,186		4,294,800	4,294,775	4,295,202
	4,294,329	4,294,042	4,294,224		4,294,826	4,294,048	4,295,203
	4,294,333	4,294,049	4,294,269		4,294,830	4,293,985	4,295,207
	4,294,349	4,294,097	4,294,316		4,294,855	4,293,993	4,295,208
	4,294,365	4,294,373	4,294,385		4,294,859	4,294,035	4,293,971
	4,294,401	4,294,563	4,294,425		4,295,003	4,294,112	4,294,006
	4,294,434	4,294,664	4,294,481		4,295,012	4,294,176	4,294,017
	4,294,446	4,294,878	4,294,663		4,295,026	4,294,294	4,294,020
	4,294,451	4,294,879	4,294,809		4,295,060	4,294,547	4,294,038
	4,294,477	4,295,029	4,294,820		4,295,219	4,294,618	4,294,043
	4,294,486	4,295,099	4,294,858		4,295,226	4,294,624	4,294,053
	4,294,492	4,295,143	4,294,884	18 :	Re.30,770	4,294,813	4,294,071
	4,294,495	4,294,010	4,295,159		4,293,962	4,294,865	4,294,133
	4,294,496	4,294,013	4,295,191		4,293,963	4,294,931	4,294,147
	4,294,522	4,294,047	4,295,194		4,294,003	4,295,035	4,294,159
	4,294,543	4,294,155	4,295,200		4,294,073	4,295,104	4,294,226
	4,294,559	4,294,162	4,295,225		4,294,089	4,295,217	4,294,238
	4,294,564	4,294,178	4,294,245	13 :	4,294,093	4,293,999	4,294,252
		4,294,199	4,294,456		4,294,109	4,294,065	4,294,282
		4,294,441	4,295,005		4,294,195	4,294,066	4,294,298

PI 56 GEOGRAPHICAL INDEX OF RESIDENCE OF INVENTORS

4,294,347	4,294,678	4,293,959	4,295,106	4,293,996	4,294,169
4,294,364	4,295,008	4,293,965	4,295,141	4,294,023	4,294,261
4,294,386	4,295,184	4,293,972	4,295,147	4,294,031	4,294,284
4,294,439	4,295,204	4,293,974	4,295,149	4,294,058	4,294,288
4,294,443	4,294,016	4,294,002	4,295,167	4,294,062	4,294,313
4,294,467	4,294,078	4,294,032	4,295,173	4,294,096	4,294,315
4,294,488	4,294,079	4,294,104	4,295,193	4,294,161	4,294,323
4,294,490	4,294,105	4,294,141	4,293,983	4,294,202	4,294,332
4,294,491	4,294,185	4,294,156	4,294,219	4,294,263	4,294,403
4,294,518	4,294,200	4,294,190	4,294,239	4,294,292	4,294,419
4,294,565	4,294,214	4,294,256	4,294,272	4,294,378	4,294,427
4,294,566	4,294,223	4,294,259	4,294,291	4,294,387	4,294,448
4,294,572	4,294,228	4,294,264	4,294,502	4,294,398	4,294,484
4,294,639	4,294,230	4,294,277	4,294,709	4,294,438	4,294,544
4,294,668	4,294,236	4,294,285	4,294,731	4,294,483	4,294,593
4,294,691	4,294,266	4,294,299	4,294,812	4,294,588	4,294,597
4,294,759	4,294,271	4,294,348	4,294,831	4,294,591	4,294,684
4,294,822	4,294,321	4,294,350	4,293,957	4,294,612	4,294,689
4,294,847	4,294,355	4,294,356	4,294,057	4,294,614	4,294,785
4,294,866	4,294,361	4,294,370	4,294,082	4,294,616	4,294,937
4,294,867	4,294,379	4,294,404	4,294,101	4,294,669	4,294,987
4,294,881	4,294,395	4,294,455	4,294,110	4,294,680	4,294,997
4,294,899	4,294,426	4,294,507	4,294,111	4,294,681	4,295,102
4,294,968	4,294,450	4,294,510	4,294,144	4,294,741	4,295,180
4,294,978	4,294,512	4,294,513	4,294,251	4,294,750	4,295,181
4,294,979	4,294,533	4,294,523	4,294,255	4,294,760	4,295,213
4,294,980	4,294,567	4,294,534	4,294,280	4,294,788	4,293,979
4,294,981	4,294,571	4,294,536	4,294,327	4,294,789	4,294,324
4,294,982	4,294,636	4,294,540	4,294,342	4,294,804	4,294,447
4,294,983	4,294,708	4,294,552	4,294,359	4,294,818	4,294,633
4,294,984	4,294,718	4,294,557	4,294,366	4,294,874	4,294,158
4,295,004	4,294,744	4,294,585	4,294,374	4,294,891	4,294,050
4,295,014	4,294,751	4,294,631	4,294,411	4,294,962	4,294,157
4,295,037	4,294,779	4,294,695	4,294,416	4,294,969	4,294,229
4,295,038	4,294,786	4,294,716	4,294,432	4,294,999	4,294,265
4,294,030	4,294,819	4,294,729	4,294,498	4,295,009	4,294,423
4,294,204	4,294,846	4,294,739	4,294,649	4,295,019	4,294,449
4,294,240	4,294,848	4,294,752	4,294,722	4,295,022	4,294,660
4,294,339	4,294,852	4,294,763	4,294,764	4,295,025	4,295,073
4,294,384	4,294,863	4,294,782	4,294,941	4,295,043	4,295,086
4,294,408	4,294,925	4,294,836	4,294,942	4,295,053	4,295,123
4,294,445	4,294,926	4,294,837	4,295,136	4,295,054	4,295,058
4,294,485	4,294,936	4,294,840	4,295,139	4,295,074	4,293,967
4,294,537	4,294,956	4,294,898	Re.30,767	4,295,077	4,294,068
4,294,644	4,294,957	4,294,901	4,293,975	4,295,094	4,294,168
4,294,961	4,294,988	4,294,904	4,294,287	4,295,151	4,294,260
4,294,965	4,294,992	4,294,906	4,294,478	4,295,175	4,294,422
4,295,057	4,295,065	4,294,909	4,294,516	4,295,190	4,294,466
4,295,212	4,295,081	4,294,911	4,294,587	4,295,223	4,294,542
4,294,088	4,295,088	4,294,912	4,294,724	4,294,046	4,294,602
4,294,152	4,295,097	4,294,954	4,294,814	4,294,187	4,294,625
4,294,393	4,295,098	4,294,993	4,295,096	4,294,360	4,294,996
4,294,452	4,295,101	4,294,994	4,295,133	4,294,747	4,294,746
4,294,575	4,295,107	4,294,995	4,295,170	4,294,883	4,294,027
4,294,610	4,295,118	4,295,002	4,295,196	Re.30,768	4,294,044
4,294,857	4,295,144	4,295,013	4,294,012	4,293,970	4,294,405
4,294,989	4,295,155	4,295,018	4,294,024	4,294,357	4,294,406
4,295,024	4,295,176	4,295,020	4,294,221	4,294,761	4,294,622
4,293,966	4,295,185	4,295,039	4,294,295	4,295,128	4,294,643
4,294,180	4,295,198	4,295,048	4,294,376	4,293,961	4,294,693
4,294,647	4,295,198	4,295,059	4,294,944	4,293,987	4,294,696
4,294,268	4,295,216	4,295,064	Re.30,772	4,293,992	4,294,700
4,294,297	4,294,007	4,295,068	4,293,984	4,294,001	4,294,821
4,294,225	4,294,444	4,295,085	4,293,994	4,294,122	4,294,409
4,294,539	Re.30,765				

DESIGN PATENTS

6 : 261,296	17 : 261,208	26 : 261,262	261,204	39 : 261,295	261,313
01 : 261,220	261,225	261,233	261,205	261,200	261,314
06 : 261,209	261,237	261,239	261,216	261,240	261,315
261,213	261,258	261,281	261,226	261,241	261,316
261,217	261,265	261,291	261,227	261,282	261,244
261,219	261,271	261,302	261,228	261,259	261,279
261,230	261,289	261,251	261,243	261,301	261,284
261,242	261,206	261,276	261,245	261,304	261,293
261,248	261,299	261,218	261,246	261,305	261,199
261,249	261,196	261,210	261,247	261,306	261,201
261,250	261,294	261,231	261,268	261,307	261,221
261,264	261,207	261,232	261,283	261,308	261,224
261,272	261,238	261,195	261,286	261,309	261,274
08 : 261,303	261,257	261,198	261,287	261,310	261,260
12 : 261,229	261,214	261,202	261,288	261,311	261,298
13 : 261,255	261,222	261,203	261,290	261,312	261,215
261,269	261,261				

PLANT PATENTS

06 : 4,775					
------------	--	--	--	--	--

U.S. GOVERNMENT PRINTING OFFICE : O-1981

CHANGE OF ADDRESS FORM

NAME—FIRST, LAST									
COMPANY NAME OR ADDITIONAL ADDRESS LINE									
STREET ADDRESS									
CITY					STATE		ZIP CODE		

PLEASE PRINT OR TYPE

Mail this form to: NEW ADDRESS

Superintendent of Documents
Government Printing Office SSOM
Washington, D.C. 20402

(or) COUNTRY

Attach last subscription
label here.

SUBSCRIPTION ORDER FORM

SUBSCRIPTION ORDER FORM

ENTER MY SUBSCRIPTION TO:

@ \$ Domestic; @ \$ Foreign.

NAME—FIRST, LAST									
COMPANY NAME OR ADDITIONAL ADDRESS LINE									
STREET ADDRESS									
CITY					STATE		ZIP CODE		


PLEASE PRINT OR TYPE

(or) COUNTRY

☐ Remittance Enclosed (Make
checks payable to Superin-
tendent of Documents)

☐ Charge to my Deposit
Account No.

MAIL ORDER FORM TO:
Superintendent of Documents
Government Printing Office
Washington, D.C. 20402



Vol. 1011 Number 3

OFFICIAL GAZETTE

of the
UNITED STATES PATENT AND TRADEMARK OFFICE

October 20, 1987



U.S.
DEPARTMENT
OF COMMERCE

Patent
and
Trademark
Office

OFFICIAL GAZETTE of the
UNITED STATES PATENT and TRADEMARK OFFICE

October 20, 1981

Volume 1011

Number 3

CONTENTS

	Page
Patent and Trademark Office Notices	
Patent Cooperation Treaty (PCT) Information	1011 OG 20
Reissue Applications Filed	1011 OG 20
Requests for Reexamination Filed	1011 OG 20
Patent Certificates of Correction	1011 OG 21
Disclaimers	1011 OG 21
Dedication	1011 OG 21
Reference Collections of U.S. Patents Available for Public Use in Patent Depository Libraries	1011 OG 22
Condition of Patent Applications	1011 OG 23
Reissue Patents Granted (30,774)	895
Plant Patents Granted (4,778)	899
Patents Granted	
General and Mechanical (4,295,227)	901
Chemical (4,295,844)	1111
Electrical (4,296,269)	1233
Design Patents Granted (261,320)	1309
Index of Patentees	PI 1
Indices of Reissue, Design and Plant Patentees	PI 43
Classification of	
Patents (Including Reissues)	PI 47
Designs and Plants	PI 50
Geographical Index of Residence of Inventors	
Patents (Including Reissues)	PI 51
Designs and Plants	PI 52
Change of Address Form and Subscription Order Form	Back Page

The following are mailed under direction of the Superintendent of Documents, Government Printing Office, Washington, D.C., 20402, to whom all subscriptions should be made payable and all communications addressed:

THE OFFICIAL GAZETTE (PATENT SECTION), issued weekly, subscription \$325.00 per annum for first-class mailing, also available as fourth-class mail at \$225.00 domestic; \$281.25 foreign; foreign first-class mailing rates will be furnished upon request; single copies each, \$5.50 domestic, \$6.90 foreign.

THE OFFICIAL GAZETTE (TRADEMARK SECTION), issued weekly, subscription \$105.00 per annum, foreign mailing \$131.25 per annum; single copies \$2.75 each domestic, \$3.45 foreign.

GENERAL INFORMATION concerning PATENTS, price \$2.25 each.

GENERAL INFORMATION concerning TRADEMARKS, price \$1.70 each.

PRINTED COPIES OF PATENTS are furnished by the Patent and Trademark Office at 50 cents each; PLANT PATENTS in color, \$1.00 each; copies of TRADEMARKS AND DESIGN PATENTS at 20 cents each. Address orders to the Commissioner of Patents and Trademarks, Washington, D.C., 20231.

Printing authorized by Section 11(a)3 of Title 35, U.S. Code P.T.O.

PATENT AND TRADEMARK OFFICE NOTICES

Patent Cooperation Treaty Information

For information concerning the PCT, consult Chapter 1800 of the Manual of Patent Examining Procedure and notices 90-95 in the consolidated listing of notices appearing in the Official Gazette of Jan. 6, 1981.

The PCT fees in effect after May 19, 1981 are as follows:

Transmittal fee	\$ 35.00
Search fee	300.00
International Basic Fee (for the first 30 sheets of an international application)	215.00
Basic Supplemental Fee (for each sheet over 30)	4.00
International Designation Fee (for each State for which a national patent is sought, or group of States for which the same regional patent is sought)	50.00

RENE D. TEGTMEYER,
Assistant Commissioner
for Patents.

REISSUE APPLICATIONS FILED

Notice under 37 CFR 1.11(b). The reissue applications listed below are open to inspection by the general public in the indicated Examining Groups and copies may be obtained by paying the fee therefor (37 CFR 1.21(b)).

3,729,680, Re. S.N. 273,371, Filed June 15, 1981, Cl. 455/36, RADIO PAGER WITH VOICE MESSAGE AND SUBSTITUTE PAGING NUMBERS, Ramsey H. McDonald, Owner of Record: *Inventor*, Attorney or Agent: Harold R. Woodard, et al., Ex. Gp.: 233

4,153,174, Re. S.N. 261,623, Filed May 7, 1981, Cl. 215/252, TAMPER-PROOF CLOSURE, Frederick D. Keeler, Owner of Record: *The KLM Co., Stratford, Conn.*, Attorney or Agent: Morris Relson, et al., Ex. Gp.: 241

4,157,724, Re. S.N. 273,040, Filed June 12, 1981, Cl. 141/1, METHOD AND AN APPARATUS FOR DISTRIBUTING A DISINTEGRATED MATERIAL ONTO A LAYER FORMING SURFACE, Torsten B. Persson, Owner of Record: *Inventor*, Attorney or Agent: Paul M. Craig, Jr., et al., Ex. Gp.: 243

4,188,103, Re. S.N. 268,781, Filed June 1, 1981, Cl. 354/27, RANGE SYNCHRONIZED FLASH PHOTOGRAPHIC APPARATUS AND METHOD FOR ACHIEVING OPTIMUM FLASH EXPOSURE, Conrad H. Biber, et al., Owner of Record: *Polaroid Corp., Cambridge, Mass.*, Attorney or Agent: David R. Thornton, Ex. Gp.: 211

4,195,953, Re. S.N. 270,721, Filed June 5, 1981, Cl. 405/300, ADVANCE MECHANISM FOR A MINE ROOF SUPPORT ASSEMBLY, Kunibert Becker, et al., Owner of Record: *Gewerkschaft Eisenhütte Westfalen, Lunen, Germany*, Attorney or Agent: Richard C. Sughrue, et al., Ex. Gp.: 354

4,207,206, Re. S.N. 271,564, Filed June 8, 1981, Cl. 252/429B, CATALYST SYSTEM, Nikolaous K. Balint,

Owner of Record: *Standard Oil Co., Chicago, Ill.*, Attorney or Agent: William T. McClain, et al., Ex. Gp.: 117

4,221,751, Re. S.N. 273,266, Filed June 12, 1981, Cl. 264/119, ARTICLES MOLDED FROM PAPER MILL SLUDGE, Bruce A. Haataja, et al., Owner of Record: *Board of Control of Michigan Technological University, Houghton, Mich.*, Attorney or Agent: Gerrit D. Foster, et al., Ex. Gp.: 147

4,249,044, Re. S.N. 271,771, Filed June 8, 1981, Cl. 200/5A, MEMBRANE SWITCH WITH MEANS FOR PREVENTING CONTAMINATION OF THE INTERIOR THEREOF, Willis A. Larson, Owner of Record: *Oak Industries, Inc., Crystal Lake, Ill.*, Attorney or Agent: James B. Kinzer, et al., Ex. Gp.: 217

4,257,204, Re. S.N. 263,442, Re. S.N. June 2, 1981, Cl. 52/395, PREFABRICATED INSULATED PANEL AND WALL STRUCTURE PRODUCED THEREFROM, Martin C. Rieger, Owner of Record: *Childers Products Co., Inc., Cleveland, Ohio*, Attorney or Agent: David A. Burge, et al., Ex. Gp.: 354

4,262,138, Re. S.N. 272,519, Filed June 11, 1981, Cl. 560/233, PREPARATION OF CARBOXYLIC ACID ESTERS WITH BF₃ COMPLEX CATALYST, Abraham P. Gelbein, Owner of Record: *Chem Systems, Inc., New York, N.Y.*, Attorney or Agent: Bert J. Lewen, Ex. Gp.: 126

REQUESTS FOR REEXAMINATION FILED

Notice under 37 CFR 1.11(c). The requests for reexamination listed below are open to inspection by the general public in the indicated Examining Groups. Copies of the requests and related papers may be obtained by paying the fee therefor established in the Rules (37 CFR 1.21(b)).

In the event correspondence to the patent owner is not received, this notice will be considered to be constructive notice to the patent owner and reexamination will proceed (37 CFR 1.248(a)(5) and 1.525(b)).

3,828,610, Reexam. No. 90/000,073, Requested: Sept. 18, 1981, Cl. 73/862.49, THRUST MEASUREMENT, Judson S. Swearingen, Owner of Record: *Rotoflow Corp., Los Angeles, Calif.*, Attorney or Agent: Browning & Bushman, Ex. Gp.: 244, Requester: Alfred B. Levine, Washington, D.C.

4,031,289, Reexam. No. 90/000,070, Requested: Sept. 18, 1981, Cl. 428/451, STAIN RESISTANT POLYESTER-COATED BLOCK, John A. Sergovic, Owner of Record: *The Burns & Russell Co., Baltimore Md.*, Attorney or Agent: John W. Malley, et al., Ex. Gp.: 160, Requester: Trenwyth Ind., Inc., Emigsville, Pa.

4,246,240, Reexam. No. 90/000,071, Requested: Sept. 17, 1981, Cl. 423/139, PROCESS FOR SEPARATING COBALT AND NICKEL FROM A SOLUTION CONTAINING COBALT AND NICKEL, Takashi Ogata, et al., Owner of Record: *Nippon Mining Co. Ltd., Tokyo, Japan*, Attorney or Agent: Wegner & Bretschneider, Ex. Gp.: 110, Requester: John W. Schneller, Washington, D.C.

PATENT NOTICES

Certificates of Correction for the Week of Oct 20, 1981

Re. 30,520	4,256,014	4,270,183	4,278,590
Re. 30,568	4,257,731	4,270,424	4,278,826
Re. 30,585	4,258,479	4,270,824	4,278,866
D. 257,600	4,258,864	4,270,858	4,279,523
4,089,491	4,260,373	4,271,153	4,279,593
4,135,808	4,260,851	4,271,197	4,280,477
4,157,357	4,261,860	4,271,328	4,280,541
4,159,331	4,262,236	4,271,546	4,280,753
4,166,465	4,262,497	4,271,705	4,280,826
4,167,567	4,263,027	4,271,847	4,280,835
4,186,119	4,263,218	4,272,457	4,281,094
4,204,702	4,263,273	4,272,530	4,281,154
4,204,717	4,263,274	4,272,604	4,281,163
4,205,178	4,263,287	4,272,711	4,281,205
4,208,328	4,263,290	4,272,994	4,281,597
4,212,076	4,263,601	4,274,118	4,281,617
4,215,480	4,263,777	4,274,146	4,281,664
4,216,541	4,263,997	4,274,232	4,281,871
4,220,925	4,264,075	4,274,427	4,282,016
4,221,328	4,264,435	4,274,494	4,282,405
4,224,434	4,264,466	4,274,686	4,282,517
4,236,218	4,264,932	4,275,051	4,282,540
4,238,325	4,265,022	4,275,664	4,283,070
4,239,656	4,265,197	4,275,793	4,283,301
4,240,633	4,265,524	4,276,089	4,283,343
4,241,078	4,265,922	4,276,205	4,283,611
4,241,815	4,266,054	4,276,266	4,283,796
4,242,009	4,266,523	4,276,619	4,283,823
4,242,098	4,267,186	4,276,771	4,283,895
4,243,543	4,267,532	4,276,812	4,284,208
4,245,804	4,267,915	4,277,293	4,284,249
4,246,844	4,268,267	4,277,322	4,284,571
4,248,729	4,268,578	4,277,485	4,284,596
4,249,104	4,268,782	4,277,583	4,284,734
4,250,526	4,268,871	4,278,031	4,284,833
4,252,707	4,269,053	4,278,126	4,284,839
4,252,973	4,269,410	4,278,206	4,284,879
4,253,037	4,270,096	4,278,255	
4,255,346	4,270,131	4,278,479	

Disclaimers

4,023,105.—*Kenneth Rau Wooling, Jr.*, Indianapolis, Ind. COUNTER TYPE REMOTE CONTROL RECEIVER PRODUCING BINARY OUTPUTS CORRELATED WITH NUMERICAL COMMANDS OF A COMPANION REMOTE CONTROL TRANSMITTER. Patent dated May 10, 1977. Disclaimer filed Aug. 17, 1981, by the assignee, *RCA Corp.*

Hereby enters this disclaimer to claims 1, 2 and 3 of said patent.

4,074,896.—*Larry G. Eftefield*, Joliet, Ill. CUSHION COMPRESSION STRUTS FOR BULLDOZER BLADES. Patent dated Feb. 21, 1978. Disclaimer filed Aug. 17, 1981, by the assignee, *Caterpillar Tractor Co.*

Hereby enters this disclaimer to claims 1, 2, 3 and 4 of said patent.

4,183,921.—*W. David Weir*, Levittown and *Edward E. Kilbourn*, Chalfont, Pa. PHOSPHONOUREIDE AND PHOSPHONOTHIOUREIDE ANTHELMINTICS. Patent dated Jan. 15, 1980. Disclaimer filed Mar. 31, 1981, by the assignee, *Beecham, Inc.*

Hereby enters this disclaimer to all claims of said patent.

4,203,652.—*Hiroshi Hanada*, Yokohama, Japan BEAM SHAPING OPTICAL SYSTEM. Patent dated May 20, 1980. Disclaimer filed Aug. 28, 1981, by the assignee, *Canon Kabushiki Kaisha*.

Hereby enters this disclaimer to claims 1, 2, 17 and 18 of said patent.

4,235,158.—*A. David Johnson, Jr.*, Radnor, Pa. METHOD OF MAKING HIGH STRENGTH SHIPPING CARTON. Patent dated Nov. 25, 1980. Disclaimer filed Aug. 27, 1981, by the assignee, *Wayne Automation Corp.*

Hereby enters this disclaimer to claims 1, 2, 3 and 4 of said patent.

4,239,861.—*Hans-Eberhard Braese*, Winfried Fischer, Dietrich Hardt, Cologne, Richard Prinz, Leverkusen; and *Volker Serini*, Krefeld, Germany. POLYVINYL CHLORIDE-POLYCARBONATE ALLOYS. Patent dated Dec. 16, 1980. Disclaimer filed Aug. 28, 1981, by the assignee, *Bayer Aktiengesellschaft*.

Hereby enters this disclaimer to claims 1-9, all claims of said patent.

4,264,429.—*Joel W. Rosenthal*, El Cerrito; *Arthur J. Dahlberg*, Pinole; and *Christopher W. Kuehler*, Larkspur, Calif. TWO-STAGE COAL LIQUEFACTION PROCESS WITH PROCESS-DERIVED SOLVENT. Patent dated Apr. 28, 1981. Disclaimer filed July 27, 1981, by the assignee, *Chevron Research Co.*

The term of this patent subsequent to Mar. 10, 1998, has been disclaimed.

4,278,756.—*Eric W. Bouldin*, Woodside, and *Jerome Drexler*, Los Altos Hills, Calif. REFLECTIVE DATA STORAGE MEDIUM MADE BY SILVER DIFFUSION TRANSFER. Patent dated July 14, 1981. Disclaimer filed Aug. 17, 1981, by the assignee, *Drexler Technology Corp.*

Hereby enters this disclaimer to claims 2, 4, 5, 7, 8 and 9 of said patent.

Dedication

3,414,928.—*Jerome H. Lemelson*, Metuchen, N.J. COMBINATION SPONGE AND SCANNER. Patent dated Dec. 10, 1968. Dedication filed June 11, 1981, by the assignee, *Minnesota Mining and Manufacturing Co.*

Hereby dedicates the remaining term of said patent to the Public.

Reference Collections of U.S. Patents Available for Public Use in Patent Depository Libraries

The libraries listed herein, designated as patent depository libraries, receive current issues of U.S. Patents and maintain collections of earlier issued patents. The scope of these collections varies from library to library, ranging from patents of only recent months or years in some libraries to all or most of the patents issued since 1870, or earlier, in other libraries.

These patent collections are open to public use and each of the patent depository libraries, in addition, offers the publications of the patent classification system (e.g. The Manual of Classification, Index to the U.S. Patent Classification, Classification Definitions, etc.) and provides technical staff assistance in their use to aid the public in gaining effective access to information contained in patents. With one exception, as noted in the

table following, the collections are organized in patent number sequence.

Depending upon the library, the patents may be available in microfilm, in bound volumes of paper copies, or in some combination of both. Facilities for making paper copies from either microfilm in reader-printers or from the bound volumes in paper-to-paper copies are generally provided for a fee.

Owing to variations in the scope of patent collections among the patent depository libraries and in their hours of service to the public, anyone contemplating use of the patents at a particular library is advised to contact that library, in advance, about its collection and hours, so as to avert possible inconvenience.

State	Name of Library	Telephone Contact
Alabama	Birmingham Public Library	(205) 254-2555
Arizona	Tempe: Science Library, Arizona State University	(602) 965-7607
California	Los Angeles Public Library	(213) 626-7555 Ext. 273
	Sacramento: California State Library	(916) 322-4572
	Sunnyvale: Patent Information Clearinghouse*	(408) 738-5580
Colorado	Denver Public Library	(303) 573-5152 Ext. 222
Delaware	Newark: University of Delaware	(302) 738-2238
Georgia	Atlanta: Price Gilbert Memorial Library, Georgia Institute of Technology	(404) 894-4519
Illinois	Chicago Public Library	(312) 269-2814
Louisiana	Baton Rouge: Troy H. Middleton Library, Louisiana State University	(504) 388-2570
Massachusetts	Boston Public Library	(617) 536-5400 Ext. 265
Michigan	Detroit Public Library	(313) 833-1450
Minnesota	Minneapolis Public Library & Information Center	(612) 372-6552
Missouri	Kansas City: Linda Hall Library	(816) 363-4600
	St. Louis Public Library	(314) 241-2288 Ext. 214, 215
Nebraska	Lincoln: University of Nebraska-Lincoln, Engineering Library	(402) 472-3411
New Hampshire	Durham: University of New Hampshire Library	(603) 862-1777
New Jersey	Newark Public Library	(201) 733-7814
New York	Albany: New York State Library	(518) 474-5125
	Buffalo and Erie County Public Library	(716) 856-7525 Ext. 267
	New York Public Library (The Research Libraries)	(212) 790-6291
North Carolina	Raleigh: D. H. Hill Library, N.C. State University	(919) 737-3280
Ohio	Cincinnati & Hamilton County, Public Library of	(513) 369-6936
	Cleveland Public Library	(216) 623-2870
	Columbus: Ohio State University Libraries	(614) 422-6286
	Toledo/Lucas County Public Library	(419) 255-7055 Ext. 212
Oklahoma	Stillwater: Oklahoma State University Library	(405) 624-6546
Pennsylvania	Philadelphia: Franklin Institute Library	(215) 448-1321**
	Pittsburgh: Carnegie Library of Pittsburgh	(412) 622-3138
	University Park: Pattee Library, Pennsylvania State University	(814) 865-4861
Rhode Island	Providence Public Library	(401) 521-7722 Ext. 226
Tennessee	Memphis & Shelby County Public Library and Information Center	(901) 528-2957
Texas	Dallas Public Library	(214) 748-9071
	Houston: The Fondren Library, Rice University	(713) 527-8101 Ext. 2587
Washington	Seattle: Engineering Library, University of Washington	(206) 543-0740
Wisconsin	Madison: Kurt F. Wendt Engineering Library, University of Wisconsin	(608) 262-6845
	Milwaukee Public Library	(414) 278-3043

*Collection organized by subject matter.

**Call only between the hours of 10:00 a.m. and 5:00 p.m.

1011 OG-22

PATENT EXAMINING CORPS

RENE D. TEGMEYER, Assistant Commissioner

WILLIAM FELDMAN, Deputy Assistant Commissioner

CONDITION OF PATENT APPLICATIONS AS OF September 5, 1981

PATENT EXAMINING GROUPS

CHEMICAL EXAMINING GROUPS

	Actual Filing Date of Oldest New Case Awaiting Action
GENERAL CHEMISTRY AND PETROLEUM CHEMISTRY, GROUP 110—D. E. TALBERT, Director	5-12-80
Inorganic Compounds; Inorganic Compositions; Organo-Metal and Organo-Metalloid Chemistry; Metallurgy; Metallurgical Apparatus; Metal Stock; Electro Chemistry; Batteries; Hydrocarbons; Mineral Oil Technology; Lubricating Compositions; Gaseous Compositions; Fuel and Igniting Devices.	
GENERAL ORGANIC CHEMISTRY, GROUP 120—C. E. VAN HORN, Director	10-11-79
Heterocyclic Amides; Alkaloids; Azo; Sulfur; Misc. Esters; Carbohydrates; Herbicides; Poisons; Medicines; Cosmetics; Steroids; Oxo and Oxy; Quinones; Acids; Carboxylic Acid Esters; Acid Anhydrides; Acid Halides.	
HIGH POLYMER CHEMISTRY, PLASTICS AND MOLDING, GROUP 140—J. O. THOMAS, JR., Director	7-09-80
Synthetic Resins; Rubber; Proteins; Macromolecular Carbohydrates; Mixed Synthetic Resin Compositions; Synthetic Resins With Natural Polymers and Resins; Reclaiming; Pore-Forming; Compositions (Part) e.g., Coating; Molding; Ink; Prosthetics; Adhesive and Abrading Compositions; Molding, Shaping, Treating Process, and Apparatus Therefor; Irradiation (Part); Bleaching; Dyeing; Leather, Fur and Textile Treating Compositions.	
COATING, LAMINATING AND PHOTOGRAPHY, GROUP 160—S. N. ZAHARNA, Director	1-12-80
Coating; Processes, Apparatus and Misc. Products; Laminating Methods and Apparatus; Stock Materials; Adhesive Bonding; Special Chemical Manufactures; Special Utility Compositions; and Photography.	
SPECIALIZED CHEMICAL INDUSTRIES AND CHEMICAL ENGINEERING, GROUP 170—	
R. F. WHITE, Director	5-06-80
Fertilizers; Foods; Fermentation; Analytical Chemistry; Reactors; Sugar and Starch; Paper Making; Glass Manufacture; Gas; Heating and Illuminating; Cleaning Processes; Liquid Purification; Distillation; Preserving; Liquid, Gas, and Solid Separation; Gas and Liquid Contact Apparatus; Refrigeration; Concentrative Evaporators; Mineral Oils Apparatus; Misc. Physical Processes.	

ELECTRICAL EXAMINING GROUPS

INDUSTRIAL ELECTRONICS, PHYSICS AND RELATED ELEMENTS, GROUP 210—S. W. ENGLE, Director	1-07-80
Generation and Utilization; General Applications; Conversion and Distribution; Heating and Related Art Conductors; Switches; Photography; Motion Pictures; Horology; Acoustics; Recorders; Weighing Scales.	
SPECIAL LAWS ADMINISTRATION, GROUP 220—KENNETH L. CAGE, Director	1-18-80
Ordnance, Firearms and Ammunition; Lubrication; Illumination; Nuclear Reactors; Acoustics, Communications, Optics; Radar; Directional Radio; Torpedoes; Seismic Exploring; Cathode Ray Tube Circuitry; Cryptography; Laser Devices; Radioactive Materials; Powder Metallurgy; Rocket Fuels; Special, Fuel, Explosive and Thermic Compositions; Thermal and Photoelectric Batteries.	
INFORMATION TRANSMISSION, STORAGE, AND RETRIEVAL, GROUP 230—VACANT	1-23-80
Communications; Multiplexing Techniques; Television; Facsimile; Data Processing, Computation and Conversion; Storage Devices and Related Arts.	
RECEPTACLES, SANITATION AND CLEANING, WINDING, AND MEASURING, GROUP 240—	
A. L. SMITH, Director	12-07-79
Receptacles; Bearings; Joint Packing; Conduits; Switches; Presses; Plumbing Fixtures; Textile Spinning; Cleaning; Food Treating; Agitating; Centrifugal Separating; Geometrical Instruments; Sound Recording; Image Projectors; Web Feeding; Winding and Reeling; Cable Hoists; Measuring and Testing; Indicating; Fluent Material Handling.	
ELECTRONIC COMPONENT SYSTEMS AND DEVICES, GROUP 250—S. S. MATTHEWS, Director	4-20-79
Semi-Conductor and Space Discharge Systems and Devices; Electronic Component Circuits; Wave Transmission Lines and Networks; Optics; Radiant Energy; Measuring.	
DESIGN, GROUP 290—KENNETH L. CAGE, Director	2-08-80
Industrial Arts; Household, Personal and Fine Arts.	

MECHANICAL EXAMINING GROUPS

HANDLING AND TRANSPORTING MEDIA, GROUP 310—B. R. GRAY, Director	1-09-80
Conveyors; Hoists; Elevators; Article Handling Implements; Store Service; Sheet Feeding; Dispensing; Fluid Sprinkling; Fire Extinguishers; Coin Handling; Check Controlled Apparatus; Classifying and Assorting Solids; Boats; Ships; Aeronautics; Motor and Land Vehicles and Appurtenances; Brakes; Railways and Railway Equipment.	
MATERIAL SHAPING, ARTICLE MANUFACTURING, TOOLS, GROUP 320—M. M. NEWMAN, Director	6-12-79
Manufacturing Processes, Assembling, Combined Machines, Special Article Making; Metal Deforming; Sheet Metal and Wire Working; Metal Fusion-Bonding; Metal Founding; Machine Tools for Shaping or Dividing; Work and Tool Holders, Woodworking; Tools; Cutlery; Jacks; Fishing, Etc.; Butchering; and Books and Printed Matter.	
AMUSEMENT, HUSBANDRY, PERSONAL TREATMENT, INFORMATION, GROUP 330—	
R. E. AEGERTER, Director	1-30-80
Amusement and Exercising Devices; Projectors; Animal and Plant Husbandry; Plants; Harvesting; Earth Working and Excavating; Tobacco; Artificial Body Members; Dentistry; Jewelry; Surgery; Toiletry; Printing; Typewriters; Information Dissemination.	
HEAT, POWER, AND FLUID ENGINEERING, GROUP 340—D. J. STOCKING, Director	10-22-79
Power Plants; Combustion Engines; Fluid Motors; Reaction Motors; Pumps; Rotary Engines and Pumps; Heat Generation and Exchange; Refrigeration; Ventilation; Drying; Temperature and Humidity Regulation; Couplings; Gearing; Fluid Handling and Control; Lubrication.	
GENERAL CONSTRUCTIONS, TEXTILES, MINING AND GEARING, GROUP 350—	
G. M. FORLENZA, Director	2-19-80
Building Structures; Racks; Cabinets; Closures; Supports; Furniture; Fasteners; Locks; Pipe Couplings; Joints; Miscellaneous Hardware; Textiles; Sewing Machines; Apparel; Footwear; Earth Engineering; Earth Drilling; Mining; Wells; Roads; Bridges; Tool Driving; Gearing; Machine Elements; Clutches.	

Expiration of patents: The patents within the range of numbers indicated below expire during September 1981, except those which may have expired earlier due to shortened terms under the provisions of Public Law 690, 79th Congress, approved August 8, 1946 (60 Stat. 940) and Public Law 619, 83rd Congress, approved August 23, 1954 (68 Stat. 764), or which may have had their terms curtailed by disclaimer under the provisions of 35 U.S.C. 253. Other patents, issued after the dates of the range of numbers indicated below, may have expired before the full term of 17 years for the same reasons, or have lapsed under the provisions of 35 U.S.C. 151.

Patents Numbers 3,146,459 to 3,151,328, inclusive

Plant Patents Numbers 2,444 to 2,448, inclusive

1011 OG-23

Patent and Trademark Office

Taking Effect in the United States of the International Convention for the Protection of New Varieties of Plants

The International Convention for the Protection of New Varieties of Plants (the UPOV Convention) will take effect in the United States on November 8, 1981. It will apply to all applications for the patenting of plants under the provisions of Title 35, United States Code, which are filed on or after November 8, 1981. The actual filing date will govern in determining whether the Convention will apply to an application, even though the application may be entitled to an earlier effective date under section 119 or 120 of Title 35, United States Code.

In addition to the United States, the UPOV Convention will be in effect as of November 8, 1981, in the following fourteen States: Belgium, Denmark, Federal Republic of Germany, France, Ireland, Israel, Italy, Netherlands, New Zealand, Republic of South Africa, Spain, Sweden, Switzerland, and the United Kingdom.

No changes in the patent law are needed to implement the UPOV Convention in the United States. An applicant for a plant patent will be required, however, to submit for registration a variety name for the plant to be patented. Registration is required by Article 13 of the UPOV Convention.

Registrability shall be determined in accordance with the International Code of Nomenclature for Cultivated Plants (1980). As an interim procedure pending the promulgation of an appropriate rule, inclusion of the variety name in the application will be accepted as a submission of the name for registration. No plant patent as a result of an application filed on or after November 8, 1981, shall be issued without the registration of a variety name. Questions concerning this variety naming requirement or the UPOV Convention may be addressed to:

Mr. Michael K. Kirk, Director
Office of Legislation and International Affairs
Box 4
U.S. Patent and Trademark Office
Washington, D.C. 20231

Mr. Kirk's telephone number is (703) 557-3065.

GERALD J. MOSSINGHOFF,
Date: Oct. 15, 1981. *Commissioner of Patents
and Trademarks.*


REISSUES

OCTOBER 20, 1981

Matter enclosed in heavy brackets [] appears in the original patent but forms no part of this reissue specification; matter printed in italics indicates additions made by reissue.

Re. 30,774
LIGHTWEIGHT REMOVABLE COVER FOR A POOL, GREENHOUSE OR THE LIKE
 Edwin L. Dahlbeck, and Verna H. Dahlbeck, both of 739 N. 198th, Seattle, Wash. 98133
 Original No. 4,136,408, dated Jan. 30, 1979, Ser. No. 744,729, Nov. 24, 1976. Application for reissue Feb. 26, 1980, Ser. No. 124,121


Int. Cl.³ E04H 3/16, 3/18
 U.S. Cl. 4—498 22 Claims



12. Apparatus for supporting a flexible cover over an enclosure such as a swimming pool, greenhouse or the like, comprising:
 a peripheral lower frame,
 a plurality of curved, interconnected tubular supports coupled to the lower frame overlying the enclosure and spaced along the lower frame,
 rigid elongated stabilizer members located above the peripheral lower frame and interconnecting said tubular supports, said stabilizer members being attached to the tubular supports on a side remote from the flexible cover so as not to contact the cover,
 a flexible cover overlying said supports and stabilizer members for covering the space above the enclosure, and
 means for securing the cover to the lower frame.

Re. 30,775
AUTOMATIC CAPACITOR WINDING MACHINE AND METHOD
 Fredric S. Miller; Armando A. De Mauro, both of Wayne, N.J., and Robert J. Delvy, Bridgeport, Conn., assignors to Universal Manufacturing Corporation, Paterson, N.J.
 Original No. 4,003,112, dated Jan. 18, 1977, Ser. No. 562,012, Mar. 25, 1975. Application for reissue Jan. 17, 1979, Ser. No. 4,018

Int. Cl.³ H01G 4/16
 U.S. Cl. 29—25.42 30 Claims




1. A method for winding capacitors including:
 moving a bifurcated arbor having a slot to a retracted position;
 clamping portions of dielectric layers into a substantially

planar configuration above said arbor; [retracting said arbor;]
 rotating said arbor so that its slot is substantially in alignment with the plane of said dielectric layers;
 carrying the planar portion of said dielectric layers into alignment with the axis of said arbor;
 maintaining said alignment while extending said arbor axially to an advanced position to grasp said dielectric layers;
 rotating said arbor to wind the capacitor;
 feeding electrodes from continuous supplies to said rotating arbor;
 supplying a relatively thick structural insert while said capacitor is being wound to reinforce the capacitor;
 moving said arbor to a retracted position while stripping said capacitor off said arbor.

Re. 30,776
BREAK-OUT APPARATUS FOR FAULT PREVENTION IN THE PRODUCTION OF MULTI-STRAND YARNS
 Dieter E. A. Plate, Torquay, and John D. Feehan, Belmont, both of Australia, assignors to Commonwealth Scientific and Industrial Research Organization, Campbell, Australia
 Original No. 4,110,963, dated Sep. 5, 1978, Ser. No. 796,790, May 13, 1977. Application for reissue May 6, 1980, Ser. No. 147,016

Claims priority, application Australia, May 13, 1976, 5921/76
 Int. Cl.³ D01H 13/16
 U.S. Cl. 57—86 10 Claims



20. Apparatus for spinning a two-ply yarn in a single operation from two separate running strands, said apparatus having a drafting unit for drawing said strands in spaced relation to one another from separate rovings and having a rotatable spindle for twisting the drawn strands together and for winding thereon the two-ply yarn so formed, the twisting action being such as to form a distinctive convergence point between the two component strands, wherein twist blocking means are provided in the vicinity of the said convergence point so that, when one strand breaks the other is allowed to adopt a modified line of travel in which it is acted upon by said twist blocking means to substantially block the travel of twist to that portion of said other strand between said means and the drafting unit so as to thereby cause said other strand to also break.

Re. 30,777

PORTABLE DISPLAY SYSTEM


Willy Ytter, Stockholm, Sweden, assignor to Extraversion, Inc., Dover, Del.

Original No. 4,147,198, dated Apr. 3, 1979, Ser. No. 838,667, Oct. 3, 1977. Application for reissue Oct. 25, 1979, Ser. No. 87,992

Int. Cl.³ A47G 5/00

U.S. Cl. 160—135

30 Claims



1. A portable display system comprising:

a plurality of panels each having a detachable front wallboard and detachable rear wallboard;

a first and second peripheral support means to support and position said detachable front and rear wallboard in a substantially parallel and confronting relationship so as to form a panel assembly; said first peripheral support means removably positioned along at least one outer edge of said detachable front and rear wallboard, said second peripheral support means positioned along the remaining edges of said detachable front and rear wallboard so that said detachable front and rear wallboard is removable from said first and second peripheral support means in a direction perpendicular to the edge along which said first peripheral support means is positioned;

hinging means for connecting a plurality of said panel assemblies to each other so that said panel assemblies are divided into a first and second group;

said hinging means comprising a plurality of corner hinges greater than two and a plurality of double hinges greater than two so that said corner hinges are connected to a plurality of said panel assemblies movable in a vertical direction and said double hinges connected to a plurality of said panel assemblies movable in a horizontal direction, said first and second group comprising a number of connected panel assemblies such that said number of connected panel assemblies are hinged in the said two directions so that in the extended position the number of panel assemblies extending in the vertical direction equals the number of panel assemblies extending in the horizontal direction,

said first group being extended to said position independent of said second group.

Re. 30,778

CRUSHER-DRYER AND METHOD OF CRUSHING


William F. Hahn, Devon; Joseph P. Nigro, Villanova, and Frank Wallitsch, Jr., Center Valley, all of Pa., assignors to Pennsylvania Crusher Corporation, Broomall, Pa.

Original No. 4,085,897, dated Apr. 25, 1978, Ser. No. 816,828, Jul. 18, 1977. Continuation of Ser. No. 746,379, Dec. 1, 1976, abandoned. Application for reissue Apr. 23, 1980, Ser. No. 142,957

Int. Cl.³ B02C 23/24

U.S. Cl. 241—18

48 Claims



1. An improved apparatus for crushing and drying materials, such as moist coal, comprising:

a housing having an inlet opening located [;] in the upper portion thereof and an outlet opening located in the lower portion thereof;

a rotor mounted for rotation in said housing, said rotor having impact members thereon for striking and crushing material falling through said inlet opening and passing through the impact circle defined by the outer extremities of said impact members;

a first inlet duct means entering said inlet opening and terminating a short distance above said [hammer] impact circle, for causing said material to drop through said inlet opening above said impact circle to be struck by said impact members;

a second inlet duct means entering said inlet opening for conveying hot air into said housing without substantially [interfering] interfering with said material until just prior to entry of said material into said impact circle;

at least one breaker plate mounted within said housing in position to be impacted by material thrown off by said impact members; and

means located within said second inlet duct for selectively directing the flow of hot air through said second inlet duct to pass between said breaker plate and said rotor; behind said breaker plate; or both.

Re. 30,779

FILTER ASSEMBLY WITH REPLACEABLE FILTER ELEMENT

Roydon B. Cooper, Locust Valley, N.Y., assignor to Pall Corporation, Glen Cove, N.Y.

Original No. 4,133,763, dated Jan. 9, 1979, Ser. No. 856,959, Dec. 5, 1977. Application for reissue Apr. 24, 1980, Ser. No. 143,227


Int. Cl.³ B01D 27/04

U.S. Cl. 210—232

28 Claims

1. A filter assembly having a filter chamber and a filter element therein that is replaceable without contamination of filtered fluid with unfiltered fluid in the filter chamber even though the filter chamber is not emptied of unfiltered fluid when a filter element is removed and installed, comprising, in combination, a filter housing; a filter chamber in the housing;

an inlet for unfiltered fluid and an outlet for filtered fluid in the housing; a filter element removably disposed in the filter chamber across the line of fluid flow from the inlet to the outlet so that fluid flow from the inlet to the outlet normally proceeds through the filter; a weir spaced from and downstream of the filter element, compelling filtered fluid from the filter flowing towards the outlet to proceed upwardly through the space between the weir and the filter and then by overflow across the weir; and a weir follower operatively associated with the base of the filter element [and] removably attached to one end of the



filter element and mounted on the weir in a manner to be retained thereon while a used filter element is being removed, and while a clean filter element is being installed, and slidably movable along the weir in fluid-tight relation to the base and the weir, to carry filtered fluid in the space between the weir and the filter element on the downstream side of the filter element to the top of the weir while a used filter element is being removed, and to displace unfiltered fluid in the filter chamber from contact with the downstream side of a clean filter element while the clean filter element is being installed.

Re. 30,780

HEAT TREATMENT OF HEAT-SENSITIVE PRODUCTS

Lennart A. Stenstrom, Huddinge, Sweden, assignor to Alfa-Laval AB, Tumba, Sweden

Original No. 3,814,889, dated Jun. 4, 1974, Ser. No. 176,966, Sep. 1, 1971. Application for reissue Jul. 31, 1978, Ser. No. 929,668

Claims priority, application Sweden, Sep. 8, 1970, 12153/70

The portion of the term of this patent subsequent to May 7, 1991, has been disclaimed.


Int. Cl.³ H05B 6/78

U.S. Cl. 219—10.55 M

11 Claims

1. In the processing of a heat-sensitive product by subjecting it to a sterilizing or pasteurizing treatment temperature, the method which comprises pre-treating units of the product by heating at least the main part of each said unit to a pre-heating temperature of at least 50° C. interrupting said pretreatment heating, and subjecting each unit to the influence of a cooling

medium to prevent the surface layer of said unit from acquiring a substantially higher pre-heating temperature than the inner



parts of said unit, and then heating each product unit to substantially said treatment temperature by subjecting the unit to electromagnetic energy of at least microwave frequency.

Re. 30,781

LOGARITHMIC AMPLIFIER

Yukihiko Miyamoto, Tokyo, Japan, assignor to Trio Kabushiki Kaisha, Tokyo, Japan


Original No. 4,209,714, dated Jun. 24, 1980, Ser. No. 806,098, Jun. 13, 1977. Application for reissue Aug. 15, 1980, Ser. No. 178,457

Claims priority, application Japan, Jun. 14, 1976, 51-69605

Int. Cl.³ H03K 5/08; G06G 7/12

U.S. Cl. 307—490

5 Claims



1. A logarithmic amplifier circuit comprising at least one transistor connected in a common-emitter amplifier arrangement, said transistor having base, collector and emitter electrodes, said emitter electrode being connected to ground through a resistor, said collector electrode being connected to a power source through a load and providing an output signal, said base electrode being connected to a bias voltage source through a diode and to an input signal source, said diode and the base-emitter junction of the transistor cooperating to rectify the input signal from said signal source and comprising means to impart a logarithmic input-amplitude-level-to-output-amplitude-level transfer characteristic to the amplifier circuit for a predetermined amplitude range of input signals.

PLANT PATENTS

GRANTED OCTOBER 20, 1981

Illustrations for plant patents are usually in color and therefore it is not practicable to reproduce the drawing.

4,778

GERANIUM PLANT

Walter H. Jessel, Jr., Fremont, and William E. Duffett, Salinas, both of Calif., assignors to Yoder Brothers, Inc., Barberton, Ohio

Filed Aug. 5, 1980, Ser. No. 175,751

Int. Cl.³ A01H 5/00

U.S. Cl. Plt.—68

1 Claim

1. A new and distinct geranium plant, a hybrid of the genus *Pelargonium*, L'Her., to be known by the cultivar name Songster, as described and illustrated, and particularly characterized by the combination of characteristics of orange-red flower color; medium plant height; medium internode length; semi-double flower form; semi-spreading branching pattern; mid-season spring-pot flowering response; prolific outdoor summer flowering traits; good foliage durability; good flower durability; and dark green foliage color with pronounced dark zonation.

4,779

IMPATIENS PLANT NAMED CHINOOK

John J. Ryan, 39877 Sundale Dr., Fremont, Calif. 94538

Filed May 16, 1980, Ser. No. 150,699

Int. Cl.³ A01H 5/00

U.S. Cl. Plt.—68

1 Claim

1. A new and distinct form of *Impatiens* plant as described and illustrated, known by the cultivar name Chinook.

4,780

DWARF PEACH W-114

Fedor Wassiliew, deceased, late of Orange, Calif.; by Nicolaus Wassiliew, heir, Costa Mesa, Calif.; by Alexander Wassiliew, heir; by Marsha W. Hartman, heir, both of Orange, Calif., and by Valentina Wassiliew, heir, Costa Mesa, Calif., assignors to Jackson & Perkins Co., Medford, Oreg.

Filed May 1, 1980, Ser. No. 145,510

Int. Cl.³ A01H 5/00

U.S. Cl. Plt.—43

1 Claim

1. A new and distinct variety of peach tree of the genetically dwarf type, substantially as herein shown and described, characterized particularly as to novelty by its unique combination of vigorous, dwarf plant, semi-double pink flowers, late July ripening date, nearly spherical, red flushed yellow fruit skin, and sweet yellow flesh.

PATENTS

GRANTED OCT. 20, 1981

ERRATA

For CLASS	See PATENT NO.
474-083	4,295,383
501-090	4,295,890
501-099	4,295,891
501-120	4,295,892
376-203	4,295,934
376-285	4,295,935
073-864	4,296,071

PATENTS

GRANTED OCTOBER 20, 1981

GENERAL AND MECHANICAL

4,295,227

SHOULDER PAD


Hal D. Mitchell, Rolla, Mo., assignor to A-T-O Inc., Wil-
loughby, Ohio

Filed Apr. 25, 1980, Ser. No. 143,899

Int. Cl.³ A41D 13/00

U.S. Cl. 2—2

7 Claims



1. A shoulder pad for football players comprising a left-hand member adapted to fit over the left shoulder and a right-hand member adapted to fit over the right shoulder, each of said members being a relatively rigid member of generally inverted U-shape as viewed from the side and having a chestplate portion, a backplate portion and an arch integrally connecting said plate portions, said arches being laterally spaced to provide an opening for the neck of the wearer with the spacing such that said arches lie adjacent and relatively close to the neck, each of said members having padding on the inside thereof with the padding at the top of the arch comprising an inner portion generally beneath the arch adapted to overlie the inner part of a respective shoulder and an outer portion extending laterally outwardly beyond the arch adapted to overlie the outer part of said shoulder, said outer portion comprising a front section adjacent the chestplate portion and a back section adjacent the backplate portion, said front and back sections being separate toward their outer ends for allowing the sections to spread apart upon upward movement of the arm at the shoulder, each member further comprising a cover pad extending laterally outwardly from said inner portion of the arch padding over the separate outer ends of said front and back sections of the arch padding at the top of the shoulder, said cover pad being hinged to the inner portion of the arch padding for permitting the cover pad to swing upwardly on upward movement of the arm at the shoulder, and a cap with padding on the inside thereof overlying said cover pad and adapted to fit over the outer part of the shoulder.

4,295,228

BOXING GLOVES WITHOUT A SEAM ON THE FRONTAL STRIKE PORTION THEREOF

Stojicic Dragomir, Jurija Gagarina 211/9, 11070 Novi Beograd,
Yugoslavia

Filed Dec. 28, 1979, Ser. No. 107,973

Claims priority, application Yugoslavia, Jan. 17, 1979, 18/79


Int. Cl.³ A41D 13/10

U.S. Cl. 2—18

3 Claims

1. A boxing glove comprising a frontal strike portion, a palm portion and a thumb portion, wherein said frontal strike portion and thumb portion represent a unitary piece and are slanted inwardly in a convex manner towards said palm portion and wherein said frontal portion and said thumb portion are mutually joined in said palm portion by fabric seams inwardly tucked at the point where (1) the interior of said thumb section interconnects with said palm portion; (2) said frontal

strike portion at the opposite extreme from said thumb side interconnects with said palm portion and (3) said convexly situated frontal strike portion interconnects with the top portion of said palm portion, said interconnections comprising the



attachment of at least two separate ply fabrics and wherein said attachment provides an open interconnection of stuffing between the interiors of said frontal strike portion and said thumb portion.

4,295,229

FOOTBALL GLOVES


Eugene A. Clark, 27 Blen Cathia Hill, R.R. 2, Gormley, Ontario,
Canada (L04 1G0), and Morris Zubkewych, 2184 D Bloor St.
W., Toronto, Ontario, Canada

Filed Feb. 19, 1980, Ser. No. 122,418

Int. Cl.³ A41D 13/08

U.S. Cl. 2—20

8 Claims



1. A football glove including an upper pad arrangement comprising a wrist protecting portion and a hand protecting portion integrated with one another with said hand protecting portion being partially open from beneath for palm, finger and thumb exposure below said pad arrangement, said hand protecting portion being provided with finger and thumb pads of a length such that there is at least first phalange finger and thumb coverage from above by said finger and thumb pads, inelastic web means connecting the thumb pad to the finger pads to limit movement of said thumb pad away from said finger pads, individual finger and thumb receptacles beneath said finger and thumb pads, said receptacles being adapted for limited stretching thereof to enable ready finger and thumb manipulation and being provided with restraining means for restraining excessive stretching of said receptacles to reduce finger and thumb injuries, said pad arrangement being provided with a plurality of transverse flexible joints along its length to permit flexing of the glove in said hand protecting portion and between said hand protecting portion and said wrist protecting portion and separate securing means at both said hand protecting portion and said wrist protecting portion to secure said glove in position from beneath said pad arrangement.

4,295,230

CHILDREN'S SLEEPING GARMENTS


Camille C. Blodgett, P.O. Box 202, West Stockbridge, Mass. 01266

Filed Apr. 14, 1980, Ser. No. 139,871

Int. Cl.³ A41D 11/00

U.S. Cl. 2—69,5

2 Claims



1. A sleeping garment comprising front and rear unitary panels connected by a single seam extending around bottom and side edges of the panels, each panel terminating at its upper end in a pair of unitary shoulder straps, one shoulder strap from each panel being detachably connectible to the strap from the other panel, the upper ends of the panels being contoured together to form a pair of arm holes closed only by the shoulder straps and adapted to leave the upper body of the occupant free of restraint said pair of straps from one of the panels being connected to the pair of straps from the other panel by button and buttonhole connections, the margins of the panels being turned outwardly and the seam being inserted through two thicknesses of each panel.

4,295,231

FILIGREED BELT WITH SOLID CENTER PORTION

Earl R. Wright, Comanche, Tex., assignor to Wright Leather Goods Manufacturing Co., Comanche, Tex.

Filed Apr. 14, 1980, Ser. No. 140,314

Int. Cl.³ A41F 9/00

U.S. Cl. 2—338

8 Claims



1. A belt to be worn by a person comprising: an outer layer attached to second layer means, said outer layer facing outward when the belt is worn by a person, design openings formed through said outer layer forming part of a design, said design openings being spaced inward from the opposite edges of said outer layer whereby said opposite edges comprise strips extending along the length of said belt free from said design openings, said design openings being spaced outward on opposite sides of a central portion of said outer layer extending along at

least a part of the length of said belt whereby said central portion is free from said design openings, the remainder of said design being formed on said central portion by lines or markings, said belt having a buckle at one end, said design openings and said central portion extending at least to said one end of said belt and to an end opposite said one end, and spaced apertures formed through said belt and hence through said central portion of said outer layer at said end opposite said one end of said belt for receiving the tongue of the buckle when the belt is worn by a person.

4,295,232

DEVICE FOR HUMAN BODY WASTE ELIMINATION DURING INCAPACITATION


Jeweral E. Marshall, Box 57, Oldtown, Md. 21555

Filed Jun. 9, 1980, Ser. No. 157,328

Int. Cl.³ A47K 11/06

U.S. Cl. 4—480

4 Claims



1. A device for human body waste elimination, during incapacitation, comprising: a chair-like structure; a back rest structure, said back rest structure consisting of a pair of support members, said support members being movably affixed to said chair-like structure, said support members having a plurality of slots therein; a leg support member for a user, said leg support member having a pair of crescent-like depressed areas therein, each said depressed area providing a holding means for one of the legs of a user, said leg support member being removably and adjustably affixed to said pair of support members in a matching pair of said plurality of slots in said pair of support members; a pair of pivot means, said pivot means movably affixing said pair of support members to said chair-like structure; a pair of locking means, said locking means being affixed to said pair of support members and removably affixed to said chair-like structure, said locking means being capable of locking said pair of support member means with said leg support member in a plurality of adjustable positions; a pair of latching means, said latching means being movably affixed to said chair-like structure to latch said back rest structure into a back-rest position for said chair-like structure; a bed pan holding means, chair-like structure having a plurality of slots therein, said plurality of slots providing a means for said bed pan holding means being adjustably and removably located within said chair-like structure; a toilet seat, said toilet seat being affixed to said bed pan holding means; and a bed pan, said bed pan being used in association with said chair-like structure.

4,295,233

AUTOMATIC HAND WASHER AND DRIER

Lester H. Hinkel, Benton Harbor, and Lawrence E. Wolske, St. Joseph, both of Mich., assignors to Whirlpool Corporation, Benton Harbor, Mich.


Continuation of Ser. No. 866,175, Dec. 30, 1977, abandoned.

This application Nov. 13, 1979, Ser. No. 93,906

Int. Cl.³ A47K 1/04, 5/06, 10/48; E03C 1/14

U.S. Cl. 4—619

15 Claims



1. A hand washing and drying device comprising: a bowl defining an upwardly and forwardly opening hand washing and drying space, said bowl including a rear wall having a downwardly facing portion and having an upper substantially planar narrow rim extending at a substantial angle to the horizontal for deterring persons from sitting on said rim, said bowl further having a bottom drain underlying said rear wall portion; water supply means including a water heating tank mounted closely adjacent said rear wall of the bowl and having an outlet opening substantially vertically downwardly generally toward said drain through said rear wall portion inwardly adjacent said rim for supplying wash water into said space in a first direction away from said rim, said outlet being spaced above the lowermost level of the rim; and air moving means including a blower mounted closely adjacent said rear wall of the bowl and having a horizontally elongated outlet opening across said space through said rear wall portion adjacent said rim and at the level of said water supply means outlet for supplying hand drying air across said space in a second direction generally parallel to said rim.

4,295,234

BED FRAME


Larry W. Whitehead, Lexington, N.C., assignor to Leggett & Platt, Incorporated, Carthage, Mo.

Filed Jan. 28, 1980, Ser. No. 116,220

Int. Cl.³ A47C 19/04

U.S. Cl. 5—184

6 Claims



1. A bed frame including a pair of side rails interconnected by a pair of adjustable elongated cross rail assemblies, said cross rail assemblies being fastened transversely between said pair of side rails so as to hold said side rails in spaced parallel

relationship, each of said adjustable cross rail assemblies comprising,

a pair of cross rails connected at one end to one of said side rails, each of said cross rails being L-shaped in cross section and having mutually perpendicular flat legs, one of said cross rails having a first shouldered protrusion extending from one leg thereof, the other of said cross rails having a plurality of longitudinally spaced slots adapted to receive said shouldered protrusion when said cross rails are located in any one of a plurality of overlapping face abutting positions of adjustment, said slots being configured so as to permit relative longitudinal movement of said first protrusion within said slots, one of said cross rails having a second protrusion extending from a leg thereof, the other of said cross rails having a plurality of longitudinally spaced apertures adapted to receive said second protrusion when said cross rails are located in any one of the plurality of overlapping positions of adjustment, said apertures being sized and configured so as to prevent relative longitudinal movement of said rails when said second protrusion is located within one of said apertures, said first and second protrusions extending from mutually perpendicular legs of said cross rails, and clamping means for locking said cross rails in one of said plurality of positions of adjustment.

4,295,235

WATERPROOF CUSHION FOR OUTDOOR USE AND METHOD FOR MANUFACTURING THE SAME


Bernard Deitz, West Orange, N.J., assignor to Deltz Plastic Formers, Prospect Park, N.J.

Filed Jan. 28, 1980, Ser. No. 115,871

Int. Cl.³ A47C 27/14; A47G 9/00

U.S. Cl. 5—473

7 Claims



1. In a furniture cushion for outdoor use of the type including a pair of opposed side layers, each formed of woven fabric material, and attached to each other along their respective peripherally extending regions to define an interior space therebetween and a filler material located substantially throughout said interior space, the improvement comprising: said fabric material is formed of filaments at least the outer surfaces of which comprise thermoplastic material, a thin interlayer formed of water impervious plastic material having a peripherally extending edge region interposed between peripherally extending edge regions of said pair of opposed side layers, said peripherally extending edge regions of said side layers and interlayer being heat sealed to each other to form a continuous seal band extending around the entire periphery of the cushion, said interlayer extending entirely through said interior space to divide the latter into a pair of adjacent isolated chambers separated by said interlayer and wherein said filler material is located entirely in one of said chambers such that said interlayer is contiguous with the inner surface of one of said side layers and spaced from the inner surface of the other of said side layers by said filler material.


4,295,236 PONTON BOAT

Lonnie W. Upchurch, Irving, Tex., assignor to Advanced Marine Concepts, Inc., Arlington, Tex.

Filed Jan. 12, 1979, Ser. No. 2,878
Int. Cl.³ B63B 7/04

U.S. Cl. 9—2 S

9 Claims



1. A relatively small watercraft for one or more persons, comprising:

- a pair of spaced and generally parallel pontoons, each of which consists of an elongated body of closed-cell foamed plastic, with the body having a longitudinal axis and a length of at least 2 meters and having a generally square cross-section as viewed in a transverse direction;
- a load-distribution truss provided on top of each of the foamed cell bodies for transferring vertical loads, and said trusses having a length and width so as to distribute loads across the top of the foamed cell bodies in an approximately uniform manner;
- a personnel station adapted to carry at least one person above and generally between the two spaced pontoons, and said station having a width which is sufficiently narrow so as to restrict the center of gravity of personnel on said station to a space which lies internally of the longitudinal axes of the pair of pontoons;
- a structural frame for transferring loads from the personnel station to the load-distribution trusses, with at least some of said loads being transferred through a plurality of bolts; and
- a waterproof and generally puncture-resistant skin for each of the pair of pontoons, with a given skin being installed between the structural frame and the load-distribution truss of a respective pontoon in such a way that the structural frame is external and the load-distribution truss is internal of said given skin.

4,295,237


HOSE ARM COUPLING FOR UNDERWATER FLUID SWIVEL

George M. Pomoni, Van Nuys, Calif., assignor to Amtel, Inc., Providence, R.I.

Filed Nov. 20, 1978, Ser. No. 961,991
Int. Cl.³ B65B 3/04

U.S. Cl. 9—8 P

4 Claims



1. In a mooring and cargo transfer installation which includes a product distribution unit having a stationary portion

coupled to the sea floor and a rotatable portion rotatable without limit about a vertical axis for coupling through a hose to a vessel that may drift thereabout, the improvement comprising: a pair of horizontally-spaced flanges fixed to the outside of said rotatable portion of the product distribution unit; a fluid joint having a member pivotally coupled to said flanges to pivot about a substantially horizontal axis extending through said flanges and lying outside said rotatable portion of said product distribution unit; and an elongated rigid structure which includes a fluid conduit extending along its length, said structure having an inner end connected to said fluid joint member and an outer end coupled to said hose.

4,295,238 FOOTWEAR

Lancelot P. Clark, Street, England, assignor to Clarks Limited, Street, England

Filed Nov. 16, 1979, Ser. No. 94,921
Claims priority, application United Kingdom, Nov. 17, 1978, 45098/78

Int. Cl.³ A43D 9/00; A43C 13/08; A43B 23/00
U.S. Cl. 12—142 RS

3 Claims



1. A method of making an article of footwear comprising pre-forming from flexible sheet material a component which provides a sock for underlying the foot and one part of an upper, which part comprises two side panels to extend respectively along opposite sides of the foot, the sock and side panels being formed either integrally with each other or in separate pieces which are connected together to form said component, placing said component on a last which defines the internal shape of the finished article, then enclosing the last and said component in a cavity mould having within it sealing knife edges which serve to nip said part of the upper to the last at locations adjacent but spaced from the edges of said part of the upper and to close the cavity of the mould, said cavity mould being shaped in relation to the last and said component to define therewith a sole unit and, integrally with the sole unit, the remaining part or parts of the upper, and injecting into the mould cavity a plastics material in a settable liquid form thereby in a single moulding operation to form the sole unit of the article and the remaining part or parts of the upper, the plastics material also overlying edge portions of said one part of the upper on the outer face thereof.

4,295,239

APPARATUS FOR REMOVING RESIDUAL TONER

Hisashi Myochin, Toyokawa, Japan, assignor to Minolta Camera Kabushiki Kaisha, Osaka, Japan


Filed Mar. 27, 1980, Ser. No. 134,578
Claims priority, application Japan, Mar. 30, 1979, 54-38662
Int. Cl.³ G03G 21/00

U.S. Cl. 15—1.5 R

5 Claims

1. In an apparatus for removing residual toner from a surface to be cleaned which comprises a rotatable cleaning brush in frictional engagement with the surface for removing residual toner therefrom, a dusting bar disposed in abutting relation to brush bristles of said cleaning brush for dusting toner off said brush bristles, both said dusting bar and said brush bristles

being made of electrically conductive material with at least one covered with an insulating material, and means for forming



an alternating electric field between said brush bristles and said dusting bar.

4,295,240


CLEANING DEVICE

Franz Lex, Annenstrasse 6, A 8020 Graz, Austria

Filed Aug. 27, 1979, Ser. No. 70,317
Claims priority, application Austria, Apr. 9, 1978, 6365/78
Int. Cl.³ A46B 13/04

U.S. Cl. 15—22 R

5 Claims



1. A cleaning device comprising a housing having an axis and guide means at one end of the housing, a cleaning body to be pressed against an object to be cleaned in a working direction, a drive part glidingly arranged in the guide means, the cleaning body being mounted on the drive part and being driven thereby, and a driving system for driving the drive part and the cleaning body mounted thereon in an oscillatory manner, the driving system including a drive motor having an axis and two ends, a shaft axially extending from one of the motor ends, a flywheel mass mounted on the motor shaft for generating an oscillatory motion, means for transmitting the oscillatory motion to the drive part, means mounting the drive motor in the housing for oscillation, the mounting means being arranged at one of the motor ends adjacent the drive part, and means for pivotally mounting the other end of the motor in the housing.

4,295,241

PAINT ROLLER

Kenneth W. Woolcock, Rouse Hill, Australia, assignor to Rota Cota Pty. Ltd., New South Wales, Australia


Filed Apr. 15, 1980, Ser. No. 140,491
Int. Cl.³ B05C 17/02

U.S. Cl. 15—230.11

4 Claims

1. A paint roller comprising a handle, an axle attached to said handle extending at right angles to the axis of the handle and approximately symmetrically on either side thereof, rotatable plastic end caps mounted on the axle ends having outer cylindrical sections to receive and support the base tube of a paint

roller cover in the inner surface thereof, a plurality of circumferentially spaced external longitudinal ribs on said cylindrical sections, said ribs functioning when a base tube is pushed over said end caps to distort said outer cylindrical sections of said end caps so that said ribs are deflected inwardly and the mid areas of said cylindrical sections between each pair of ribs are deflected outwardly to contact the inner surface of said base tube, thereby increasing the rigidity of said ribs already in



contact with the said inner surface and enabling a base tube having manufacturing tolerance variations of its inner diameter to have a frictional fit on a major part of each outer cylindrical section of said end caps while being held firmly and ensuring that the base tube and end caps rotate together and at the same time permitting easy installation and removal of the base tube, and means at each end of the axle to retain said end caps on said axle, said end caps constituting the only connection between the base tube and the axle.

4,295,242


CORNER BEADING CLEANER

William Dixon, Rte. #2, Box 2009, Circle Dr., Browns Mills, N.J. 08015

Filed May 5, 1980, Ser. No. 146,712
Int. Cl.³ B05C 17/10

U.S. Cl. 15—235.7

10 Claims



10. A corner beading cleaner, being particularly adapted to shape hardened joint compound adjacent convex corner beadings, said corner beading cleaner comprising:

- a body section further including:
 - a handle means adapted to be grasped by the user; and
 - a lip means extending outwardly from said handle means and being integral therewith, said lip means extending outwardly from said handle at an angle of approximately 135 degrees with respect thereto; and
- a tool means detachably secured to said lip means of said body section, said tool means including two first blade edges extending outwardly therefrom at an angle of 80 to 90 degrees with respect to one another to form a cutting surface of 80 to 90 degrees, said tool means further including two second blade edges extending outwardly therefrom at an angle of 80 to 90 degrees with respect to one another to form a cutting surface of 80 to 90 degrees, said tool means defining a first arcuate concave edge at the intersection between said first blade edges and a second arcuate concave edge at the intersection between said second blade edges; and

(c) a securement means adapted to detachably secure said tool means with respect to said lip means of said body section, said securement means further including;

- (1) a clamping plate extending laterally across said lip means of said body section and adapted to receive said tool means between said clamping plate and said lip means to fixedly hold said tool means in place with respect to said body section when said clamping plate is secured to said lip means, said clamping means further including a first ear means and a second ear means extending downwardly from the opposite lateral sides of said clamping plate to prevent lateral dislodgement of said tool means from between said clamping plate and said lip means; and
- (2) a threaded member extending through said clamping plate to detachably secure said clamping plate and said tool means to said lip means, said lip means defining a threaded aperture mated to said threaded member and adapted to receive said threaded member therein to fixedly secure said clamping plate, said tool means and said lip means with respect to one another.

4,295,243

FLOOR TREATING APPARATUS


Virginia B. King, P.O. Box 5274, 7528 Popen Dr., Knoxville, Tenn. 37918

Filed Oct. 15, 1979, Ser. No. 84,888

Int. Cl.³ A47L 7/00, 11/205

U.S. Cl. 15—320

6 Claims



1. Apparatus for cleaning and treating the surface of a floor comprising:

- a carriage means having a handle for guiding and maneuvering said apparatus;
- a plurality of dispensing chambers attached to said carriage means for holding a selection of floor cleaning and treating fluids;
- reciprocating scrubbing means moveably attached to said carriage means and suitable for use with said selection of fluids for cleaning and treating said floor surfaces;
- first transporting means connected to said dispensing chambers and a front portion of said scrubbing means for transporting a selected fluid from said dispensing chambers to said scrubbing means, said first transporting means including a first cut off valve cooperating with said transporting means for selectively interrupting the flow of said selected fluid to said scrubbing means;
- a receiving chamber attached to said carriage means suitable for receiving any excess of said selected fluids used for treating said floor surfaces;
- vacuum means for creating a vacuum at said receiving chamber;
- second transporting means connected between a rear portion of said scrubbing means and said receiving chamber such that said vacuum at said receiving chamber is applied to said second transporting means for transporting excess cleaning or treating fluid from said rear portion of said scrubbing means to said receiving chamber;
- a third transporting means having a first end and a further end and a second cut off valve between said first end and

said further end, said third transporting means connected to said receiving chamber at said first end and to said first transporting means at said further end such that said first cut off valve may be closed to interrupt the flow of a selected fluid from said dispensing chambers and said second cut off valve opened to create a vacuum at said first transporting means such that excess cleaning or treating fluid may be transported from said front part of said scrubbing means to said receiving chamber; and power means for driving said vacuum means and for imparting said reciprocating motion to said scrubbing means.

4,295,244

SCRUBBING MACHINE WITH WATER REGENERATION

Ferdinand J. Herpers, Minnetonka; Harley E. Kroll, Chaska; Alfred D. Carlson, Minneapolis, and Paul D. Dodge, Apple Valley, all of Minn., assignors to Tennant Company, Minneapolis, Minn.


Division of Ser. No. 916,929, Jun. 19, 1978, Pat. No. 4,194,263.

This application Nov. 19, 1979, Ser. No. 95,343

Int. Cl.³ A47L 11/20

U.S. Cl. 15—320

8 Claims



1. A scrubbing device including a body portion suitable for movement along a surface to be scrubbed;

- a tank including a pair of tank chambers and separator means providing communication between said chambers, said separator means comprising a basket-like filter member, said separator means being capable of separating a dirty scrubbing solution into a clean solution portion and a solid matter portion, said clean portion being fed into one of said tank chambers, said basket-like filter member comprising a mesh basket and a box-like filter member being spaced from the bottom of said tank, thereby providing a first tank chamber outside said basket-like filter member and a second tank chamber within said basket-like filter, said tank including means cooperating with said basket-like filter member to prevent downward movement of said basket-like filter member, and to concurrently preclude any resistance against upward movement of said basket-like filter member to thereby allow said basket-like filter member to be readily removable at all times for dumping the used box-like filter.

4,295,245

COMBINATION HINGE AND OVERCENTER CLOSURE FOR A DOOR

George E. Malcom, 55356 County Rd. 15 South, Elkhart, Ind. 46514

Continuation of Ser. No. 929,857, Jul. 31, 1978, abandoned. This application Dec. 12, 1979, Ser. No. 102,985


Int. Cl.³ G05F 1/12, 1/14

U.S. Cl. 16—80

2 Claims

1. In a combination hinge and overcenter retainer connecting a door having front and rear faces separated by a side edge to a frame having a front face and an adjoining side face wherein said hinge includes first and second legs mutually

connected for pivotal movement and first and second connector plates, said first connector plate joined to said first leg, said second connector plate joined to said second leg, said first connector plate secured to the rear face of said door with said first leg extending along said door edge, said second connector plate secured to the side face of said frame with said second leg extending forwardly of said frame front face whereby said door is pivotal about said legs pivot connection for movement between open and closed positions, said overcenter retainer including a flange connected to each hinge connector plate, a first said flange projecting outwardly from said first connector plate at said frame side face, a second said flange projecting outwardly from said second connector plate at said door rear face, a first link pivotally connected at one end to said first flange and a second link pivotally connected at one end to said second flange, said links pivotally connected together at their respective opposite ends, expansion means pivotally connected between one of said flanges spaced from the pivot connection of the link thereto and such link next to its pivot connection to the other link, said expansion means for applying a yieldable



biasing pull between said one flange and its connected link to urge said door into its closed and open positions upon manual movement of the door between said positions, the improvement wherein said expansion means includes a retainer and an adjustment member having a shank and a head, one end of said retainer pivotally connected to said one flange at a location spaced from the pivot connection of its connected link, the opposite end of said retainer receiving in sliding cooperation the shank of said adjustment member with the adjustment member head located exteriorly of the retainer, spring means extending between said retainer and said adjustment member shank in compression for causing said adjustment member head to be yieldably drawn toward said retainer, said adjustment member secured at its head to said one flange connected link adjacent its pivot connection to said other link, said adjustment member shank including means associated with said spring means for varying the compression of the spring means upon rotation of said adjustment member shank whereby the force exerted by said expansion means upon said door in its open and closed positions can be varied.

4,295,246

KNOB

Robert K. Howie, Jr., Decatur, Ill., assignor to The Grigoleit Company, Decatur, Ill.

Filed Apr. 18, 1980, Ser. No. 141,575


Int. Cl.³ F16D 1/06

U.S. Cl. 16—121

2 Claims

1. A molded knob of the type which frictionally engages and slips over the end of a shaft of generally circular cross section and having at least one longitudinally extending flat surface, a hub formed as part of said knob, a shaft receiving walled socket formed in said hub, said socket having a flat wall adapted to engage a flat surface on said shaft, and a resilient finger formed as part of said hub and extending into the socket from said flat wall, said resilient finger being positioned to engage an arcuate side of said shaft at a location adjacent said flat wall when said shaft is inserted into said socket to slightly deform

said resilient finger and thereby apply force to said shaft, and the wall of the socket located opposite the flat wall is a rigid part of a semi-hexagonal walled socket, the circular por-



tion of said shaft engages said semi-hexagonal rigid wall part and said resilient finger extends towards but terminates short of said semi-hexagonal rigid wall part and constitutes a flexible part of said walled socket.

4,295,247

GRIPPER-SEPARATOR DEVICE FOR CONTINUOUSLY SHIRRED CASINGS


Roy L. Trimble, Theodosia, Mo.; Alfred D. Story, and Harold H. Martinek, both of Danville, Ill., assignors to Teepak, Inc., Chicago, Ill.

Filed May 8, 1980, Ser. No. 147,768

Int. Cl.³ A22C 13/02

U.S. Cl. 17—1 R

24 Claims



1. In a machine for continuously shirring casings of the type having a fixed mandrel along which the shirred casing is continuously advanced, a segregator for segregating a continuously shirred casing into separate strands, said segregator comprising a gripper unit and a separator unit, means mounting said gripper unit and said separator unit for selected individual movement longitudinally along said mandrel, each of said units including gripper means for engaging an intermediate portion of a shirred casing, control means for separately actuating said gripper means of said units, and drive means for separately moving said units longitudinally along said mandrel with said separator unit being movable away from said gripper unit while said gripper means of said units are engaged with an intermediate portion of a shirred casing to separate a leading portion of said shirred casing from the remainder thereof.

4,295,248

CARDING WIRE BRUSH ARRANGEMENT


Wolfgang Beneke, and Paul Teichmann, both of Monchen-Gladbach, Fed. Rep. of Germany, assignors to Trutzschler GmbH & Co. KG, Monchen-Gladbach, Fed. Rep. of Germany
Filed Jun. 8, 1979, Ser. No. 46,789

Claims priority, application Fed. Rep. of Germany, Jun. 10, 1978, 2825506

Int. Cl.³ D01G 15/24

U.S. Cl. 19—113

10 Claims



1. A carding wire brush, particularly for revolving flats, comprising: a carrying layer, hooklike brush elements inserted into said carrying layer and protruding from said carrying layer to form carding teeth, said carding teeth having tooth faces forming an angle larger than 90° with said carrying layer, said carding teeth having tooth flanks chamfered and curved concavely in relation to said carrying layer; said carding teeth having tip regions substantially parallel to said carrying layer.

4,295,249

COMBING MACHINE


Bernhard Siemon, Hanover, Fed. Rep. of Germany, assignor to Schubert & Salzer, Ingolstadt, Fed. Rep. of Germany
Filed Oct. 16, 1979, Ser. No. 85,415

Claims priority, application Fed. Rep. of Germany, Oct. 18, 1978, 2845245

Int. Cl.³ D01G 19/16

U.S. Cl. 19—225

4 Claims



1. A combing machine having stationary detaching rollers (8, 9), a rotating circular comb (6) and reciprocating gripper, said gripper having a lower gripper plate (11) with a gripper opening provided adjacent thereto, said rotating circular comb combing a fiber beard held by said gripper, comprising:
a driven gripper oscillation shaft (E);
crank means mounted on said gripper oscillation shaft pivotally connected to said lower gripper plate (11);
a second driven crank means (4), and
a guide link (5) pivotally connecting said second driven crank means (4) to said lower gripper plate (11) adjacent said gripper opening whereby effective combing is produced between said gripper and said circular comb.

4,295,250

CABLE DEAD ENDING

James A. Dupuy, 135 McAuley Dr., Vicksburg, Miss. 39180
Filed Sep. 28, 1979, Ser. No. 79,702
Int. Cl.³ F16G 11/02, 11/04

U.S. Cl. 24—122.6

5 Claims



1. A cable dead end of steel multistrand cable including a core strand, comprising:
a ferrule having an elliptical interior cross section;
an insert disposed around the cable core strand with the other cable strands disposed around the insert in a bird-cage configuration, and with the insert substantially centered in the ferrule interior, said ferrule being generally elliptical in cross section and having barbs on the exterior surface thereof; and
steel wool packing the ferrule interior between it, the strands, and said insert.

4,295,251

METHOD FOR CONTROLLING EDGE UNIFORMITY IN NONWOVEN FABRICS


Jack R. Tatham, Fair Play, and Jerry L. Shelor, Waltham, both of S.C., assignors to Phillips Petroleum Company, Bartlesville, Okla.

Filed Mar. 14, 1980, Ser. No. 130,631

Int. Cl.³ D04H 1/46

U.S. Cl. 28—112

12 Claims



1. A method of producing a nonwoven fabric comprising:
passing a nonwoven fabric web through a needle punching zone, said fabric web being produced from staple fibers and having two edge portions and a medial portion intermediate the edge portions, wherein the weight per unit area of the edge portions is greater than the weight per unit area of the medial portion;
needle punching the medial portion and the edge portions in the needle punching zone in such a manner that the needle punching density per unit area of said fabric web is less in the two edge portions than the needle punching density per unit area of said fabric web in the medial portion so as to reduce the bonding among the staple fibers of the edge portions relative to the bonding among the staple fibers of the medial portion;
passing the thus needle punched fabric web to a tentering zone; and

tentering the thus needle punched fabric web so as to stretch said fabric web transversely relative to its direction of movement and thereby reduce the weight of said fabric web per unit area in the edge portions approximately to the weight of said fabric web per unit area in the medial portion so that a nonwoven fabric web of substantially uniform thickness is produced.

8. A method of producing a nonwoven fabric comprising:
moving a nonwoven fabric web along a direction of movement through a needle punching zone, said fabric web comprising nonwoven fibers and having two edge portions and a medial portion intermediate the edge portions, wherein the weight per unit area of the edge portions is greater than the weight per unit area of the medial portion;

needle punching the medial portion and edge portions of said nonwoven fabric web to produce bonding among said nonwoven fibers in the needle punching zone in such a manner that the needle punching density per unit area of said nonwoven fabric web is less in the two edge portions than the needle punching density per unit area of said nonwoven fabric web in the medial portion so as to reduce the bonding among said nonwoven fibers of the edge portions relative to the bonding among said nonwoven fibers of the medial portion;

moving said thus needle punched nonwoven fabric web from said needle punching zone along its direction of movement; and

stretching said thus needled nonwoven fabric web transversely relative to its direction of movement so as to thereby reduce the weight of said nonwoven fabric web per unit area in the edge portions approximately to the weight of said nonwoven fabric web per unit area in the medial portion so that a nonwoven fabric web of substantially uniform weight per unit area is produced.

4,295,252

METHOD FOR MEASURING YARN SHRINKAGE AND CRIMP DEVELOPMENT


Bruce A. Robinson, Gananogue, and John R. Thompson, Yarker, both of Canada, assignors to E. I. Du Pont de Nemours & Co., Wilmington, Del.

Continuation-in-part of Ser. No. 56,947, Jul. 12, 1979, abandoned. This application Jun. 11, 1980, Ser. No. 158,609

Int. Cl.³ D02G 1/20; D02J 1/12

U.S. Cl. 28—248

1 Claim



1. In a method for measuring continuously shrinkage and crimp development in yarns which develop crimp upon heating under low tension and wherein the yarn is advanced by driven rolls from a yarn source to a first tension zone, through a heating zone to a second tension zone and then through an elongation zone, whereby shrinkage and crimp development are determined in a measuring system from ratios of driven roll speeds; the improvement comprising: advancing said yarn downwardly in a free-hanging loop as it passes from said source to said first tension zone while maintaining zero tension in the yarn of said loop by noncontacting means sensing the

length of the free-hanging loop and in turn controlling the speed of the driven rolls near the yarn source whereby tension differences in the yarn due to removing the yarn from the source are isolated from the measuring system, passing the yarn downward through said heating zone into a second free-hanging loop while maintaining zero tension in the yarn in said second loop by a second noncontacting means sensing the length of the second free-hanging loop and in turn controlling the speed of driven rolls in the second tension zone whereby the yarn is able to retract completely prior to entering the elongation zone, and cooling the yarn while passing upward to the second tension zone.

4,295,253

PROCESS AND APPARATUS FOR TEXTURIZING FILAMENT BUNDLES

Hans Knopp, Ludwigshafen; Dieter Herion, Frankenthal; Gerhard Conzelmann, Otterstadt, and Heinz Gehrig, Kaiserslautern, all of Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Ludwigshafen, Fed. Rep. of Germany


Filed Sep. 27, 1979, Ser. No. 79,327

Claims priority, application Fed. Rep. of Germany, Oct. 12, 1978, 2844391

Int. Cl.³ D02G 1/12, 1/16

U.S. Cl. 28—255

7 Claims



1. A process for texturizing bundles of filaments of synthetic high molecular weight materials, comprising
passing the filament bundle through a feed nozzle and then a filament guide tube which is coaxial to said nozzle and is spaced therefrom by a gap,

passing a hot fluid medium from a fluid medium inlet through a space surrounding said filament guide tube, in the direction opposite to the passage of the filaments through said guide tube, toward said gap so as to heat said filaments countercurrent-wise,

imparting to said fluid medium incident to its passage through said space at a location in the immediate vicinity of said gap and over a lengthwise extent short compared with the overall length of said space between the fluid medium inlet and said gap, a vortical motion at a vortex angle of 10° to 70°, said space having an unobstructed cross section between said fluid medium inlet and said vortex imparting location so that the countercurrent-wise fluid flow completely surrounds said tube in transit to said location,

causing the direction of flow of said medium to be reversed at said gap so as to entrain said filaments in their passage through said guide tube, and
feeding the filaments subsequent to their passage through said guide tube, to an expansion stage to produce the crimp.

5. An apparatus for texturizing bundles of filaments of synthetic high molecular weight materials, comprising:

a jacket and, in this order,
a feed nozzle for the filament bundle,
a filament guide tube and
an expansion stage,
said feed nozzle and said filament guide tube being disposed, axially spaced from each other by a gap, coaxially within said jacket,
an inlet for a hot fluid medium provided in said jacket downstream from said gap as viewed in the direction of travel of said filaments through said guide tube, for causing said fluid to flow in the space between said jacket and said guide tube, towards said gap to meet said filaments,


said space being closed past said gap so that said fluid medium reverses its direction of flow at said gap, thereby to entrain said filaments in their travel through said guide tube, and
means provided in said space at a point between said fluid medium inlet and said gap and inclined relatively to the axis of said space, for imparting a vortical motion to said fluid medium at a vortex angle of from 10° to 70°, said vortex imparting means being located in the immediate vicinity of said gap and having a length short compared with the overall length of said space between the fluid medium inlet and said gap, and
said space having an unobstructed cross section between said fluid medium inlet and said vortex imparting means so that the countercurrent-wise fluid flow completely surrounds said guide tube in transit to said vortex imparting means.

4,295,254

TRANSMISSION LINE CABLE APPLICATOR MACHINE
John E. Adams, Mechanicsburg; Robert F. Evans, New Cumberland, and John H. Gavin, Lancaster, all of Pa., assignors to E. I. Du Pont de Nemours and Company, Wilmington, Del.
Filed Sep. 8, 1978, Ser. No. 940,620
Int. Cl.³ H01R 43/00

U.S. Cl. 29—33 M

3 Claims



1. In a machine for terminating to a connector a stripped multi-conductor flat transmission line cable having signal and ground wires, said machine having a base for supporting said connector, a slide movably attached to said base and punch guides supported by said base, the improvement comprising a punch assembly including a signal wire stuffer and buss bar hold down, said punch assembly movable on said punch guides, means for moving said punch assembly toward and away from said connector, said slide having a wire locator for separating exposed signal and ground wires, said punch assembly having plural relatively movable plates for terminating the signal and ground wires respectively in successive strokes toward said connector.

4,295,255


EXPANDED COOLING JACKET ASSEMBLY
Charles M. Weber, Alliance, Ohio, assignor to The Babcock & Wilcox Company, New Orleans, La.
Filed May 7, 1979, Ser. No. 36,720
Int. Cl.³ B23P 15/26; B21D 26/02; B23K 15/00

U.S. Cl. 29—157.3 V

4 Claims

1. A method of manufacturing a cooling jacket comprising the steps of:
providing a cylindrical inner casing having a fluid inlet and a fluid outlet formed at opposite ends therein extending through a cylindrical portion of said inner casing a;
force-fitting a cylindrical outer sleeve over said cylindrical

inner casing to longitudinally align said outer sleeve over said inner casing to cover said inlet and outlet holes extending through said cylindrical portion of said inner casing;
rotating the assembly formed by fitting said outer sleeve over said inner casing at a predetermined rotational speed; providing an electron-beam welder having a movable welding head;
maintaining the welding head of the electron-beam welder stationary at one end of said outer sleeve to form a sealing weld at the end thereof longitudinally beyond the first hole of said fluid inlet extending through said cylindrical portion of said inner casing;



traversing the welding head of the electron-beam welder along the length of said outer sleeve to form a series of parallel weld lines on said outer sleeve;
maintaining the weld head of the electron-beam welder stationary at the other end of said outer sleeve to thereby form a sealing weld thereat longitudinally beyond the second hole of said fluid outlet extending through said cylindrical portion of said inner casing; and
pressurizing said inner casing by applying a pressure in excess of the normal operating pressure of said cooling jacket to either the inlet or the outlet formed therein while sealing the other to thereby expand said outer sleeve between said parallel weld lines to thereby form a fluid passageway between said inner casing and said outer sleeve.

4,295,256

MOLDED HEAVY DUTY WHEEL
Robert A. Pascal, 1350 Forest, Highland Park, Ill. 60035
Division of Ser. No. 845,074, Oct. 25, 1977, Pat. No. 4,217,944.
This application Oct. 5, 1979, Ser. No. 82,232
Int. Cl.³ B21K 1/32

U.S. Cl. 29—159.01

10 Claims



1. The method of forming a wheel comprising the steps of:
forming a metallic core having a central open portion and a circumferential flange,
positioning and securing said metallic core inside an injection mold,
injecting a moldable material to cover essentially the entire inner portion of said metallic core and interior to said


circumferential flange while forming an aperture at the center portion,
removing the same from the mold,
coating the exterior of said circumferential flange with a bonding agent,
and applying a tread to said bonding agent on said exterior of said circumferential flange, whereby a substantially totally molded wheel is formed utilizing an interfacial metallic member for purposes of bonding two plastic or rubber materials or combination thereof which otherwise will not bond to each other.

4,295,257

WORK STAND FOR VERTICAL TURBINE PUMPS
Robert F. Strohs, 8736 Buffalo Dr., Union Lake, Mich. 48085
Filed Feb. 20, 1980, Ser. No. 122,990
Int. Cl.³ B23P 19/04

U.S. Cl. 29—240

8 Claims



1. A workstand for supporting and aligning components of a vertical turbine pump during assembly or disassembly comprising an elongate horizontally extending bed frame, a plurality of support cradles mounted at longitudinally spaced positions on said bed frame, each of said cradles comprising a cradle frame and at least a pair of support rollers mounted for free rotation on said cradle frame about spaced parallel horizontal axes extending longitudinally of said bed frame and symmetrically disposed on opposite sides of a common vertical plane extending longitudinally of said bed frame, said rollers being operable to supportingly engage cylindrical positions of components of a vertical turbine pump to maintain said components in alignment with each other with the axis of said components lying in said vertical plane, means for independently vertically positioning each of said cradle frames relative to said bed frame, means for independently longitudinally positioning each of said cradle frames relative to said bed frame, and a shaft support assembly for supporting a shaft projecting coaxially from a pump component supported on at least one of said cradles, said shaft support assembly comprising lower frame means adapted to be seated upon the support rollers of one of said cradles, and upper frame means having a longitudinally extending shaft receiving notch of V shaped transverse cross section.

4,295,258


PIN PULLER AND INSERTER
Eric J. Penn, San Jose, and Derylle L. Teegarden, Sunnyvale, both of Calif., assignors to National Semiconductor Corporation, Santa Clara, Calif.
Filed Feb. 21, 1980, Ser. No. 123,195
Int. Cl.³ B25B 27/00

U.S. Cl. 29—283

5 Claims

1. A pin puller and inserter for pulling pins from an integrated circuit package shipping rail and inserting pins thereinto, comprising:
an elongated body member having a top and a bottom;
an elongated channel formed in said body member said channel having an outwardly flared opening at one end of said body member and being dimensioned to admit the head of a pin from an integrated circuit package shipping rail through said opening;
a tapered ramp in said channel which progressively narrows the depth of the channel from a dimension which is larger

than the depth of the head of a pin to a dimension that will snugly hold the pinhead in place;
a slot in said body member extending from said channel opening along said channel and communicating into said channel, said slot being dimensioned to admit the shank of said pin when the head thereof is admitted into said channel;



a rounded fulcrum surface on said body member on the end thereof opposing said channel opening, said rounded surface serving as a fulcrum for engagement by a package, for pulling a pin whose head is in said channel; and
mounting means on the bottom of said body member for mounting said body member in a fixed position at a convenient height and angle for use in removing pins from a package.


4,295,259

METHOD OF FILLING SPIKE HOLES IN RAILWAY TIES

Curtis A. Rhodes, Tim A. Jur, and Donald A. Keating, all of Columbia, S.C., assignors to Canron Corp., Columbia, S.C.
Filed Oct. 13, 1978, Ser. No. 951,132
Int. Cl.³ B23P 7/00

U.S. Cl. 29—402.18

8 Claims



1. An in situ method of plugging spike holes in a succession of wooden railroad ties and then securing a rail to the ties, comprising: mixing components of a polyurethane foam which is foamable and curable at an outdoor ambient temperature and ambient pressure and which when foamed and cured has a sufficiently high rigidity and density to retain a spike when subsequently driven into foamed polyurethane and the polyurethane is cured, and then immediately injecting the mixed components into the spike holes to a depth sufficient for causing the polyurethane when it is foamed to at least partially fill the holes; causing the holes and the ties to remain at ambient conditions of outdoor temperature and pressure while the foaming and curing of the polyurethane is completed; and

before the polyurethane has cured, placing rail-holding tie plates on the ties over the thus filled spike holes and driving spikes through the tie plates and into thus plugged holes aligned therewith before the polyurethane has cured, for securing a rail to the ties.

4,295,260

TOOL FOR REMOVING SLEEVES FROM CYLINDERS


Robert M. Divers, 9119 Clydesdale Dr., St. Louis, Mo. 63126

Filed Oct. 15, 1979, Ser. No. 84,617

Int. Cl.³ B23P 19/00

U.S. Cl. 29—426.5

13 Claims



7. A method for removing a sleeve from a cylinder having a restricted opening at one end and an unrestricted opening at the other end which comprises inserting a tool provided with guide means into said sleeve from said unrestricted opening of the cylinder, inserting a plurality of radial collar segments from said restricted opening of the cylinder and forming a disc-shaped circular collar fitting over a shoulder of the sleeve, inserting a pusher rod means through said restricted opening, connecting the pusher rod means to said guide means and clamping the collar segments thereto, forcefully moving the pusher rod means toward said unrestricted opening of the cylinder with the clamped collar segments bearing against the sleeve to force it out of the cylinder housing.

4,295,261

METHOD OF MOUNTING A THERMAL INSULATING DOOR GASKET

Richard M. Scherer, Oxford, Miss., assignor to Chambers Corporation, Oxford, Miss.

Division of Ser. No. 869,765, Jan. 16, 1978, Pat. No. 4,214,571.

This application Dec. 26, 1979, Ser. No. 107,090

Int. Cl.³ B23P 11/02

U.S. Cl. 29—451

1 Claim

1. A method of mounting a thermal insulating door gasket adjacent an oven liner comprising:
aligning the gasket with a panel opening in an oven panel having an opening perimeter slightly smaller than a perimeter of the gasket;
forcing the gasket into the panel opening to frictionally mount the gasket on the oven panel;
aligning the panel opening with an open end of an oven liner mounted within an oven body;
forcing the panel opening over the liner open end pressing the oven gasket between the liner and the oven panel and

exposing a portion of the gasket for engaging an oven door; and



securing the oven panel to the oven body to secure the gasket on the open end of the liner.

4,295,262

METHOD OF MAKING TRUCK BED COVER ASSEMBLY


Daniel Grote, Mt. Clemens; Duane Raymond, Warren, and Joseph C. Mosher, Rochester, all of Mich., assignors to Thermoplastics, Inc., Prairie View, Tex.

Filed Mar. 21, 1980, Ser. No. 132,509

Int. Cl.³ B23P 19/00, 25/00

U.S. Cl. 29—462

3 Claims



1. A method of making a cover for a truck bed, comprising forming a shell having the general configuration of a truck bed cover and having a top wall, and sidewalls joined to the longitudinal margins of the top wall, said shell being of a length which is greater than the length of the cover to be made therefrom; positioning the shell in an inverted condition on a support member having adjustable guide means; positioning the guide means at a predetermined distance inwardly of the leading edge of the shell; trimming the shell along the guide means to provide a body portion for the truck bed cover having the length desired; and completing the assembly of the cover by securing a front panel and rear door thereto while the body portion is maintained in a fixed position on the support member.

4,295,263

CIRCULAR INSULATION SAW SYSTEM

Harry C. Davis, 8993 Airline Hwy., Baton Rouge, La. 70815

Filed Aug. 6, 1979, Ser. No. 63,743

Int. Cl.³ B23D 57/00, 3/02


U.S. Cl. 29—561

13 Claims

1. A circular insulation saw apparatus for cutting blocks of insulation material into pipe insulation members comprising:
a. a frame with a material feed surface having first and sec-

ond end portions and being supported by the frame, there being further provided a saw mount opening in said feed surface;

- b. a powered circular cutting blade movably mounted with respect to said feed surface at the said opening;
- c. a shaft spanning said opening and attaching at the end portions thereof to said material feed surface of said frame;
- d. at least one strut member attaching said blade to said shaft, said shaft occupying a position at the center of said circular cutting blade;



e. router means on said feed surface between said first end portion and said cutting blade for pre-cutting a generally semi-circular groove in a block of insulation material to be cut responsive to movement of the block of insulation material from said first to said second end portion with the semi-circular groove cut by said router means thereafter registering with said shaft during the subsequent cutting of the insulation block by said blade.

4,295,264

METHOD OF MAKING INTEGRATED CIRCUIT MOS CAPACITOR USING IMPLANTED REGION TO CHANGE THRESHOLD


Gerald D. Rogers, Houston, Tex., assignor to Texas Instruments Incorporated, Dallas, Tex.

Division of Ser. No. 645,171, Dec. 29, 1975, abandoned. This application Nov. 15, 1976, Ser. No. 741,815

Int. Cl.³ H01L 7/44; B01J 17/00

U.S. Cl. 29—571

4 Claims



1. A method of making an MOS integrated circuit device having a capacitor comprising the steps of:

- a. providing a body of silicon having an area on a major face thereof for a capacitor device;
- b. implanting a shallow surface-adjacent part of said area with conductivity-determining impurity to create a capacitor region in the surface of the silicon to function as the lower plate of the capacitor, the capacitor region being implanted to an impurity concentration selected to exhibit a threshold of the capacitor substantially different from

that of the silicon not implanted whereby such region has a threshold less than zero volts;

- c. providing a coating of silicon oxide on said area as the capacitor dielectric;
- d. applying a layer of polycrystalline silicon over said coating of silicon oxide to provide the upper plate of the capacitor;
- e. and diffusing impurity material into the major face near and on one side of said area to a depth much greater than that of said shallow surface-adjacent implanted part to provide electrical connections to the capacitor region, using said coating of silicon oxide as a mask.

4,295,265

METHOD FOR PRODUCING A NONVOLATILE SEMICONDUCTOR MEMORY

Masatada Horiuchi, Koganei, and Hisao Katto, Tokyo, both of Japan, assignors to Hitachi, Ltd., Tokyo, Japan



Filed Jul. 18, 1979, Ser. No. 58,501

Claims priority, application Japan, Jul. 31, 1978, 53-92634

Int. Cl.³ H01L 21/28

U.S. Cl. 29—571

11 Claims



1. Method for producing a nonvolatile semiconductor memory comprising:

- a step of forming a source region and a drain region in a surface portion of a semiconductor substrate having a first conductivity type, said source region and said drain region having a second conductivity type which is opposite to said first conductivity type;
- a step of forming a thin insulating film on a channel region between said source region and said drain region;
- a step of depositing a silicon layer on at least a portion of said thin insulating film;
- a step of doping said silicon layer and at the same time at least one surface portion of said substrate, which is adjacent to said channel region, with impurity having the same conductivity type as that of said substrate for forming a floating gate and at least one high impurity concentration region, doping of said at least one high impurity concentration region being effected by self-alignment with said floating gate using said floating gate as part of a mask;
- a step of forming a second insulating film on the surface of said floating gate; and
- a step of forming a control gate electrode on said second insulating film.

4,295,266

METHOD OF MANUFACTURING BULK CMOS INTEGRATED CIRCUITS

Sheng T. Hsu, West Windsor, N.J., assignor to RCA Corporation, New York, N.Y.

Filed Jun. 30, 1980, Ser. No. 164,681


Int. Cl.³ H01L 21/26

U.S. Cl. 29—571

7 Claims

1. An improved method for manufacturing a complementary symmetry metal oxide semiconductor integrated circuit comprising the steps of:

- (a) forming an oxide layer on the surface of a semiconductor substrate of a first conductivity type;
- (b) forming a silicon nitride layer on the surface of said oxide layer;
- (c) defining said silicon nitride layer to cover areas where transistors will be formed in said substrate; and
- (d) applying a photoresist layer over said defined silicon nitride layer; wherein the improvement comprises the steps of:
- (a) defining openings in said photoresist layer over areas where well regions of opposite conductivity type to said substrate will be formed;



- (b) implanting ions through said defined silicon nitride layer, through the underlying portions of said oxide layer and into said substrate;
- (c) removing said photoresist layer;
- (d) simultaneously driving said implanted ions into said substrate while growing a thermal oxide by heating said substrate in a dry oxygen ambient;
- (e) removing the silicon nitride layer and any underlying silicon dioxide portions; and
- (f) growing a gate oxide layer.


4,295,267

TWO-MASK VJ-FET TRANSISTOR STRUCTURE
 Alan L. Harrington, Glendale; Vladimir Rodov, Hollywood, and Richard Allison, Los Angeles, all of Calif., assignors to TRW Inc., Los Angeles, Calif.

Filed Jul. 18, 1980, Ser. No. 170,144
 Int. Cl.³ H01L 21/20

U.S. Cl. 29—571

5 Claims



1. A method of making field effect transistor devices comprising:

- (a) forming a wafer consisting of an epitaxial layer of semiconductor material of a first conductivity type on a substrate of semiconductor material of a second conductivity type;
- (b) forming an ohmic layer of semiconductor material of a third conductivity type in the epitaxial layer;
- (c) forming an ohmic refractory metal layer on the surface of the ohmic layer;
- (d) creating a central and two outer openings in the metal layer, wherein the outer openings are wider than the central opening;
- (e) forming, through the central opening, a device definition V-groove by anisotropically etching the semiconductor wafer, said device definition V-groove extending through the ohmic layer, dividing it into separate regions, and into the epitaxial layer, thereby defining a conduction channel

between the separate regions around the device definition V-groove;

- (f) forming, through the outer openings, isolation V-grooves by anisotropically etching the semiconductor wafer, said isolation V-grooves extending through the ohmic layer and the epitaxial layer into the substrate, thereby defining the outer edges of the separate regions;
- (g) forming a passivating layer on the front surface of the wafer;
- (h) creating openings in the passivating layer over the separate regions;
- (i) forming metal contacts to the separate regions, thereby defining source and drain electrodes; and
- (j) forming an ohmic contact to the back surface of the wafer beneath the device definition V-groove, thereby defining the gate electrode.

4,295,268

METHOD OF ASSEMBLING AN ELECTRIC MOTOR
 William D. Punshon, Bridgeton, and C. Theodore Peachee, Maryland Heights, both of Mo., assignors to Emerson Electric Co., St. Louis, Mo.


Division of Ser. No. 27,728, Apr. 6, 1979, Pat. No. 4,245,870.

This application Aug. 28, 1980, Ser. No. 182,084

Int. Cl.³ H02K 15/02

U.S. Cl. 29—596

1 Claim



1. The method of assembling an electric motor having a stator assembly including a core having a bore therethrough, a rotor, a shaft extending axially from said rotor in opposite directions, and a pair of bearing support members secured to said core for journaling said shaft for rotation about its axis with the rotor being rotatable within said bore, said method comprising the steps of:

- inserting said rotor in said bore with said shaft extending outwardly therefrom;
- installing a pair of said bearing support members on said core, each of said bearing support members having an opening therethrough for reception of a respective portion of said shaft and having an outwardly opening tapered race surrounding said shaft;
- fixing a first ball member in axial position on said shaft, said first ball member having a surface thereon adapted to be journaled in its respective race for the transfer of both radially loads and axial thrust loads in one axial direction from said shaft to said stator assembly;
- installing a second ball member on said shaft, said second ball member having a surface thereon adapted to be journaled in its respective race for the transfer of both radial loads and axial thrust loads in the opposite direction from said first ball member;
- seating said first ball member in its race;
- seating said second ball member in its race; and
- axially securing said second ball member relative to said shaft thereby to substantially prevent axial movement of said shaft and said rotor relative to said stator assembly.

4,295,269


TRUSS ASSEMBLY APPARATUS
 Ronald F. Wright, 6901 Glen Hills Rd., Fort Worth, Tex. 76118

Filed May 31, 1979, Ser. No. 44,060

Int. Cl.³ B23P 19/00

U.S. Cl. 29—798

12 Claims



1. Apparatus for assembling trusses from precut truss members and fastener plates, said apparatus comprising: an elongate table having a work surface thereon; a rigid support means supporting the table from a support surface such as the floor with the work surface in an elevated position above the support surface; a pair of elongate side members secured to said table, said side members positioned to protrude above the work surface on the table and to extend in a spaced apart relationship, each side member having a support surface thereon which is positioned above the work surface, said side members and work surface defining a recess of sufficient size to receive therein said precut truss members and fastener plates for assembly into trusses by said apparatus; carriage means supported above the work surface of said table and mounted for movement therealong; press roller means mounted for pressing said fastener plates into said truss members and for rolling movement along said side members, said press roller means spanning the recess between said side members and engaging said support surface on each of said side members, said roller means being supported in a position spaced above said work surface, means rotatably connecting said press roller means to said carriage for effecting both carriage movement and said rolling movement of said press roller means along the support surfaces on said side members for contacting and pressing said fastener plates into truss members located in said recess; and means for selectively effecting movement of said carriage and press roller means along said table.

4,295,270

ELECTRODE POSITIONING SYSTEM
 Jacob J. Cammarata, Crystal, Minn., assignor to Medtronic, Inc., Minneapolis, Minn.

Filed Oct. 15, 1979, Ser. No. 84,802

Int. Cl.³ H01B 13/20

U.S. Cl. 29—828

6 Claims



1. A method of positioning a ring electrode at a desired location on, and in electrical communication with, the outer braided conductor of a coaxial electrical lead comprising the steps of:

- stripping the outer insulation from the desired electrode location to one end of said lead to expose said braided conductor;

- pushing the exposed braided conductor back from said one lead to expose said one lead end;
- severing at least a portion of said exposed lead end;
- extending said braided conductor past said exposed lead end; forming the extending braided conductor into a twist; and
- threading said twist and exposed braided conductor through a ring electrode having an inside diameter generally identical to the outside diameter of said braided conductor until said ring electrode overlies said desired location.

4,295,271

METHOD OF SOLDERING A LEAD TO A SINTERED LEAD PAD

Donald Neuhoft, Arthur H. Mones, and Man K. Lam, all of Phoenix, Ariz., assignors to Honeywell Information Systems Inc., Phoenix, Ariz.

Division of Ser. No. 942,728, Sep. 15, 1978, abandoned, which is a continuation-in-part of Ser. No. 861,226, Dec. 16, 1977, abandoned. This application Apr. 3, 1980, Ser. No. 137,043

Int. Cl.³ H05K 3/34

U.S. Cl. 29—840

3 Claims

1. The method of soldering a lead to a lead pad on a substrate comprising the steps of: printing a conductor pattern including at least one lead pad on the substrate using a gold composition, said gold composition being composed of finely divided gold particles and finely divided inorganic binder particles dispersed in an inert liquid vehicle, by weight 98 to 99 percent gold particles and complementarily 2.0 to 1.0 percent inorganic binder particles, the binder consisting essentially by total weight of gold and binder of: 0.6 to 0.2 percent copper 0.2 percent lead 0.2 percent cadmium and the balance glass; firing the substrate to sinter the inorganic materials of the gold composition; presoldering the lead pad with a lead indium solder using a noncorrosive solder flux; presoldering a lead with a lead indium solder using a noncorrosive solder flux; and soldering the presoldered lead to the presoldered lead pad using a noncorrosive solder.

4,295,272

VIBRATION CONTROL FOR MOWING MACHINE
 Toshifumi Kubota, Katsuta, Japan, assignor to Hitachi Koki Company, Limited, Tokyo, Japan


Filed Apr. 25, 1980, Ser. No. 143,862

Claims priority, application Japan, Apr. 28, 1979, 54-52844

Int. Cl.³ A01D 35/00

U.S. Cl. 30—276

10 Claims



1. A mowing machine having a prime mover, a centrifugal clutch connected to said prime mover at one end thereof, a shaft connected to the other end of said centrifugal clutch at one end thereof, a gear means connected to the other end of said shaft, a rotary blade connected via said gear means to said shaft, and a pipe for covering said shaft, said centrifugal clutch starting transmission of the rotational torque of said prime mover to said shaft when the rotational frequency of said prime mover exceeds a predetermined value, rotary portions of said prime mover, centrifugal clutch, shaft, gear means and

rotary blade constituting a rotational system, wherein the improvement comprises:

the outer diameter of said shaft is selected such that the torsional natural vibration frequency of said rotational system is below one third of said predetermined value.

4,295,273

COMBINATION CARPET RAZOR KNIFE AND GUIDE


James Matthews, 11373 121st Ter. N., Largo, Fla. 33540

Filed Jan. 17, 1980, Ser. No. 113,070

Int. Cl.³ B26B 29/00

U.S. Cl. 30—293

1 Claim



1. A device for cutting carpets, comprising, in combination, a blade having a cutting edge and an elongated longitudinally extending central slot formed in said blade, said slot formed in parallelism with said cutting edge, an elongate handle member, a blade-retaining member, said blade-retaining member integrally formed with said elongate handle member, said elongate handle member and said blade-retaining member disposed in co-planar relation to one another, said blade-retaining member disposed in angular relation to said elongate handle member, an internally threaded bore formed in said blade-retaining member, said bore orthogonally disposed relative to the plane of said elongate handle member and said blade-retaining member, said blade-retaining member adapted to slidably receive said blade member so that said blade member is disposed in sandwiched relation to said blade-retaining member and so that the slot formed in said blade member is aligned with said bore throughout a plurality of functional positions of adjustment of said blade member, a first L-shaped member having a truncate leg portion and an elongate leg portion, said truncate leg portion having an aperture means formed therein, said truncate leg portion disposed so that said aperture means formed therein is in aligned relation with said internally threaded bore formed in said blade-retaining member, a first bolt member aligned with and extending through said truncate leg portion aperture means, said internally threaded bore and said slot formed in said blade member so that said first bolt member, when in secure screw-threaded engagement with said internally threaded bore, secures the truncate leg portion of said first L-shaped member to said blade-retaining member, in abutting relation thereto, and maintain the sandwiched relation between said blade member and said blade-retaining member, said elongate leg portion disposed at right angles to the plane of said blade-retaining member when said truncate leg portion is secured to said blade-retaining member, said elongate leg portion being substantially flat and being generally disposed in a horizontal plane, said elongate leg portion having a longitudinally extending central slot, a second L-shaped member having a truncate leg portion

and an elongate leg portion substantially orthogonally disposed relative to said truncate portion, an aperture formed substantially centrally of said truncate leg portion,

said truncate leg portion being flat and disposed in abutting relation to the underside of said elongate leg portion of said first L-shaped member so that the aperture formed in said truncate leg portion of said second L-shaped member is in registration with the longitudinally extending slot formed in the elongate leg portion of said first L-shaped member throughout a plurality of functional positions of adjustment of said second L-shaped member relative to said first L-shaped member,

a bolt member aligned with and extending through said aperture means in said truncate leg portion of said second L-shaped member and said slot formed in the elongate leg portion of said first L-shaped member,

said elongate leg portion of said second L-shaped member disposed in spaced apart, substantially parallel relation to the common plane of said handle member and said blade-retaining member when the truncate leg portion of said second L-shaped member is disposed in abutting relation to the elongate leg portion of said first L-shaped member, said elongate leg portion of said second L-shaped member having a distal end portion that extends beyond the distal end of said blade member so that at least a portion of said distal end of such elongate leg portion slidably engages a carpet edge when said blade member is disposed in cutting relation to a carpet,

said distal end portion of said elongate leg portion thereby serving as a cam follower means that effectively communicates the contour of a carpet edge to said blade member,

a wing head engaged in screw threaded relation to said second bolt so that the apertured truncate leg portion of said second L-shaped member and the slotted elongate leg portion of said first L-shaped member are releasably secured to one another, said truncate leg portions of said second L-shaped member and hence said elongate leg portion of said second L-shaped member being positionable in a plurality of functional positions of adjustment attendant loosening and tightening of said wing head, so that the spaced apart relation of said elongate leg portion of said second L-shaped member and said blade member is variable,

whereby a substantially perfect seam between two abutting carpets is at least in part provided by loosening said wing head, positioning said blade member and the elongate leg portion of said second L-shaped member in a preselected spaced apart relation such that said elongate leg portion of second L-shaped member is substantially parallel to said blade member, tightening said wing head to fix the spaced apart relation of said blade member and said elongate leg portion of said second L-shaped member, positioning the abutting edges of said abutting carpets so that one edge overlies the other, cutting both of said carpets with a conventional top cutter tool so that the cut made in the backing of the overlying carpet is in substantial vertical alignment with the cut made in the backing of the underlying carpet through the length of said cut, cutting a first salvage edge from the overlying carpet by placing the overturned edge of said carpet in sliding abutting relation to the elongate leg portion of said second L-shaped member and cutting the backing of said carpet with said blade while maintaining the sliding abutting relation of said carpet edge and said elongate leg portion of said second L-shaped member so that the cut so made in said backing is substantially parallel to the cut made in said backing by said top cutter tool, said distal end portion of such elongate leg portion of said second L-shaped member thereby serving as a cam follower means that effectively communicates the contour of a carpet edge to said blade member, and cutting a salvage edge from said underlying carpet in a like manner,

whereby the respective cuts made in the backing of said

abutting carpets by said blade follow the contour of the respective cuts made in the backings of said carpets by said conventional top cutter means, which cuts made in said overlying and underlying carpets by said conventional top cutter means define a mating profile, so that the backings of the carpets will mate when said carpets are placed in upturned, side-by-side relation to one another, such that a substantially perfect seam is formed between said abutting carpets.

4,295,274

SCARIFYING MACHINE


Charles W. Bricher, St. Paul, and Ferdinand J. Herpers, Minnetonka, both of Minn., assignors to Tennant Company, Minneapolis, Minn.

Filed Jul. 27, 1978, Ser. No. 928,685

Int. Cl.³ B26B 27/00, 25/00

U.S. Cl. 30—347

23 Claims



1. A tool suitable for removing built-up layers of soilage or coatings from surfaces, said tool comprising: first support means adapted for attachment to a rotary power machine; second support means mounted on said first support means, said second support means comprising a multiplicity of radially-extending elongated resilient spring members; and removable cutter means mounted on said second support means; said first support means, second support means and cutter means in combination serving to at least partially support said rotary power machine on said surface, said cutter means being resiliently supported with respect to said first support means by said second support means.

4,295,275

METHOD AND APPARATUS FOR MAKING RAISED AND FLAT LETTER SIGNS

Larry Cugini, Sr., and John J. Cugini, both of 23 Holley St. Extension, Danbury, Conn. 06810

Division of Ser. No. 23,599, Mar. 26, 1979, Pat. No. 4,230,513.

This application May 8, 1980, Ser. No. 147,919

Int. Cl.³ B43L 5/00; G01B 3/14; G09F 7/04

U.S. Cl. 33—1 G

1 Claim


1. A layout table for making signmakers' line level indicating layout master guide strips comprising a paramagnetic layout panel having height and width at least equal to those of a signblank to be laid out,

a blank layout master strip of sheet material positionable along one side of the layout panel, an upper curtain sheet having a magnetized strip along its lower edge positionable across the upper portion of the layout panel to denote the upper edge of a signblank,

a lower curtain sheet having a magnetized strip along its upper edge positionable across the lower portion of the layout panel to denote the lower edge of a signblank, leaving a central transverse portion of the blank layout master strip and the layout panel exposed between the curtains representing the signblank,

and a selectable plurality of magnetized layout strips of different widths corresponding to heights of letters to be employed by the signmaker, each individually position-

able extending across the exposed panel portion and the blank layout master and independently manually adjustable to positions representing individual lines of sign letters



4,295,276

TEMPLATE FOR ALIGNING A SHAFT


Rayburn P. Ellington, III, Peoria, Ill., assignor to Caterpillar Tractor Co., Peoria, Ill.

Filed Nov. 3, 1978, Ser. No. 957,507

Int. Cl.³ G01B 7/31

U.S. Cl. 33—181 R

5 Claims



1. A shaft alignment template (26) comprising: a disc (27) having a diameter larger than the thickness thereof, a piloting slot means (32) formed through said disc (27) for engaging a shaft member therein, said piloting slot means (32) including a semi-circular opening (33) disposed centrally of said disc and a slot portion (34) extending radially outwardly from said opening (33) in tangential relationship therewith and terminating in open relationship at the periphery of said disc (27), and an annular flange (28) having an annular hub means (29) secured on only one side thereof for engaging another member, said hub means (29) having an outside diameter which is less than the outside diameter of said flange (28).

4,295,277


STYLUS POSITIONER

Francis G. Dennesen, Beverly; Richard S. Wilson, Swampscott; Roy D. Toulan, Jr., Beverly, and Peter Madnick, Andover, all of Mass., assignors to Dennesen Electronics Inc., Beverly, Mass.

Filed Sep. 26, 1979, Ser. No. 79,041
Int. Cl.³ G11B 3/10

U.S. Cl. 33—181 R

29 Claims



1. A stylus positioner for a turntable assembly, which assembly has a turntable mounted to rotate about a spindle and a stylus arm pivotably mounted proximate said turntable, which stylus arm moves on a pivot axis relative to said turntable, which positioner comprises: a locator plate having an aperture which fits over said spindle and pivots thereon; said plate having a stylus positioning indicator therein at a distance from said spindle; a pivot arm fixably connectable to said locator plate; means for rotating said pivot arm and thus said locator plate around said spindle toward the pivot axis of said stylus arm to locate said indicator on said turntable so that the stylus can be positioned on said stylus arm in registration with said indicator.

4,295,278

METHOD AND APPARATUS FOR MEASURING OUT A STRAND GUIDE ARRANGEMENT

Hans Gloor, Umiken, Switzerland, assignor to Concast AG, Zürich, Switzerland


Filed Jan. 14, 1980, Ser. No. 111,768

Claims priority, application Switzerland, Jan. 30, 1979, 883/79

Int. Cl.³ G01B 5/14

U.S. Cl. 33—182

4 Claims



1. An apparatus for measuring out a strand guide arrangement of a continuous casting installation, comprising: means providing a strand guide arrangement defining guide tracks arranged at a mutual spacing from one another; a measuring device provided with measuring feeler means capable of moving along the guide tracks of the strand guide arrangement; and said measuring device comprising: analogue-digital converter means operatively connected with said measuring feeler means; microprocessor means containing program means and data storage means connected with said analogue-digital converter means, said storage means being displaced with the measuring means through the guide arrangements; and

interface means operatively connected with said microprocessor means.

4,295,279


HAND TOOL LEVELING APPARATUS

Walter F. Sienknecht, 3839 Temple City Blvd., Rosemead, Calif. 91770

U.S. Cl. 33—334

Filed Mar. 10, 1980, Ser. No. 128,723
Int. Cl.³ G01C 9/28

9 Claims



1. Apparatus for leveling a tool having a working axis comprising: a receptacle of a predetermined configuration attached to the tool; an elongated, sealed, transparent cylindrical tube containing a liquid and a bubble formed by the liquid, said tube being mounted in the receptacle with its horizontal axis parallel to the working axis of the tool to level the tool in a horizontal plane, the receptacle being configured so as to enable viewing the bubble in the cylindrical level from at least the top and both sides thereof. a circular bubble level mounted in the receptacle having an axis passing perpendicular through the center of the circular level, said axis being disposed parallel to the working axis of the tool for leveling the tool in a vertical plane, said circular level containing a transparent liquid and a bubble formed by the liquid, said circular level being biconvex in cross-section and positioned in the receptacle whereby the bubble can be properly positioned in the level to level the tool in either the vertical upward or vertical downward positions and the circular level retains the cylindrical level in the receptacle; and resilient means for removably locking the circular bubble level within the receptacle.

4,295,280

METHOD OF OBTAINING A LYOPHILIZED PRODUCT

John Krupcey, Montreal, Canada, assignor to American Home Products Corporation, New York, N.Y.

Filed Mar. 17, 1980, Ser. No. 130,927

Int. Cl.³ F26B 5/06

U.S. Cl. 34—5

6 Claims

1. A process for obtaining a package containing a mass of dry material comprising at least two immunologic reagent materials incompatible with each other in the presence of moisture comprising the steps of:

- preparing separate aqueous liquid compositions of each of the materials;
- cooling each of the liquid compositions to a temperature slightly above its freezing point;
- mixing the cooled liquid compositions to obtain a mixture thereof;
- charging the mixture of liquid compositions at a temperature slightly above the freezing point of the mixture into a container maintained at a temperature substantially below the freezing point of the mixture so that the mixture freezes in the container; and
- lyophilizing the frozen mixture.

4,295,281

DRYING SOLID MATERIALS


Owen E. Potter, Camberwell, Australia, assignor to Monash University, Victoria, Australia

Filed Dec. 29, 1978, Ser. No. 974,245

Claims priority, application Australia, Feb. 10, 1978, PD3341
Int. Cl.³ F26B 3/08, 3/10, 3/00, 5/00

U.S. Cl. 34—10

13 Claims



3. In a method of drying a solid material containing less than 95% by weight of a vapourisable material which comprises establishing a fluidized bed containing the solid material, introducing fluidizing medium, heating the fluidized bed indirectly, feeding the material to be dried to the fluidized bed, removing dried solid material therefrom, and removing vapour product from the fluidized bed; the improvement wherein the fluidizing medium is the vapourisable material in vapour form, wherein dried solid material is removed from the bottom of the fluidized bed, and wherein vapour product comprising the vapourisable material substantially uncontaminated by other gases is removed from the fluidized bed for further use.

4,295,282

HEAT AND LIQUID RECOVERY USING OPEN CYCLE HEAT PUMP SYSTEM


Bryce J. Fox, Shoreview, Minn., assignor to Minnesota Mining and Manufacturing Company, St. Paul, Minn.

Filed Nov. 15, 1978, Ser. No. 960,774

Int. Cl.³ F26B 21/08

U.S. Cl. 34—27

29 Claims



1. A drying oven system for removing vaporizable liquid from materials laden with said liquid, said system comprising a circulating gas drying oven having in combination therewith liquid removal apparatus for removing condensable vapor from said circulating gas, said apparatus comprising, in sequence means for compressing said gas, means for cooling said

compressed gas and means for expanding said compressed gas to effect further cooling of said gas, said cooling causing condensation of at least a portion of the vapor contained therein, said apparatus further including means for separating the condensed liquid from said circulating gas.

4,295,283

AIR DIFFUSER FOR A HAIR DRYER


Patrick M. Tomaro, deceased, late of Maplewood, N.J. (by Rita Tomaro, executrix), assignor to Conair Corporation, Edison, N.J.

Continuation of Ser. No. 40,886, May 21, 1979, abandoned. This application Jun. 19, 1980, Ser. No. 161,073

Int. Cl.³ A45D 20/12

U.S. Cl. 34—97

5 Claims



1. A diffuser attachment for a hand-held hair dryer for dissipating and reducing the force of an air stream of a hair dryer, said diffuser including:

a housing having an air inlet opening at a first end and an air outlet opening at a second end in alignment with said air inlet opening such that air introduced into said air inlet opening flows through said housing and is discharged therefrom through said air outlet opening, said air outlet opening being larger than said air inlet opening, said first end of said housing being adapted to be removably interconnectable with an air discharge outlet of a hair dryer, a freely rotatable fan rotatably mounted within said housing between said air inlet opening and said air outlet opening having a plurality of fan blades arranged symmetrically about a central hub, said fan blades extending substantially throughout the entire cross sectional area of said housing, said blades of said fan being so positioned such that substantially all the air discharged from said hair dryer into said air inlet opening strikes said fan and causes it to rotate, whereby said rotatable fan disperses and deflects substantially all air discharged from said hair dryer into a plurality of diversely directed, less powerful eddy air currents, which are discharged from said housing through said air outlet opening.

4,295,284

DRYER RANGE


Philip M. Witkin, Greenville, S.C., assignor to Marshall and Williams Company, Greenville, S.C.

Filed Jul. 5, 1979, Ser. No. 54,861

Int. Cl.³ F26B 13/02; D06C 3/02

U.S. Cl. 34—155

2 Claims



1. A dryer range having spaced means supplying heated air to upper and lower longitudinal manifold means for treating a web moving longitudinally through the range comprising: spaced transverse plenums carried above said lower manifold means receiving heated air therefrom; spaced transverse plenum carried below said upper manifold means receiving heated air therefrom; said plenums each having a closure member opposite said web carrying a plurality of spaced nozzles therealong directing heated air against said web, and opposed sides extending marginally of said closure member; said spaced transverse plenums being carried both above and below said cloth communicating with respective upper and lower manifold means; air flow retaining baffle means carried by each of said plenums extending laterally outwardly adjacent said closure member defining an air passage adjacent an edge thereof; said air retaining baffle means providing a wide face confronting opposing sides of said fabric for holding heated air against said fabric while allowing sufficient spacing relative to the width of said air passage between said opposed sides of adjacent plenums to facilitate a smooth uniform flow and removal of spent air such that moisture is evenly removed from said web, and the area of entrance of said air passage being greater than the area of said nozzles.

4,295,285

SNOWTHROWER


Eric Stevens, El Cajon, Calif., assignor to The Toro Company, Minneapolis, Minn.

Filed Dec. 17, 1979, Ser. No. 104,264

Int. Cl.³ E01H 5/00

U.S. Cl. 37—43 D

8 Claims



1. An improved snowthrower of the type having a snow throwing impeller mounted in an impeller housing, wherein

the impeller housing has end walls and an outlet through which the snow is thrown by the impeller, wherein the impeller is mounted between the end walls of the impeller housing for rotation about a substantially horizontal axis, wherein the impeller includes a plurality of impeller blades which are spaced apart from one another to establish an open volume therebetween, and wherein the improvement relates to the impeller and comprises:

an impeller having spaced apart side walls between which the blades extend, wherein the blades are sufficiently rigid to transmit a drive torque from one side wall to the other side wall, and wherein the open volume is radially inwardly of the blades and is completely open in that no mounting shaft extends through the impeller in a direction substantially parallel to the blades, whereby the blades themselves, rather than a mounting shaft, transmit a drive torque applied to one of the side walls through the impeller, wherein one of the end walls of the housing includes a stub shaft and the other end wall of the housing includes a means for driving the impeller, wherein the impeller driving means includes a drive member, and wherein the impeller includes a bore on one side wall for being loosely received on the stub shaft and a drive aperture on the other side wall which is configured to receive the drive member in a driving engagement, and wherein the stub shaft is removably contained in the end wall and the impeller has a length less than the distance between the drive member and the end wall which holds the stub shaft such that the impeller can be slid laterally off the drive member when the stub shaft is removed to allow removal of the impeller without disassembly of the impeller or the end walls of the housing.

4,295,286

SUPPORT FRAME FOR MOTOR, PUMP AND SUCTION TUBE OF A SUCTION DREDGER


Willem Brandwijk, Nieuw-Lekkerland, and Herman Dam, Alblasserdam, both of Netherlands, assignors to IHC Holland N.V., Papendrecht, Netherlands

Filed Apr. 8, 1980, Ser. No. 138,402

Int. Cl.³ E02F 3/88

U.S. Cl. 37—58

9 Claims



1. A suction dredger having a dredging tube with suction head, said dredging tube being pivotably connected to the side wall of the hull about a horizontal axis extending transversely to the side wall, said dredging tube between its connection to the hull and its suction head having a pump unit with a motor which in operation with the suction head at the bottom of the water operates below water level, said dredging tube between the pump and its connection to the hull having a pivot frame with one pivot axis in a vertical plane, through which frame extends a hose interconnecting the pressure conduit parts of the dredging tube while between said pump and its suction head a cardan joint frame has been provided through which extends a further hose interconnecting the suction tube parts of the dredging conduit, said cardan joint frame and said vertical pivot frame forming integral parts of a support frame, carrying

the motor and the pump as well as the adjacent part of the suction tube and the part of the pressure conduit tube between cardan joint and vertical pivot frame respectively, said support frame at the side turned towards the hull having one or more fenders extending outside the longitudinal profile of the support frame and the motor and the pump and the tube parts supported by it.

4,295,287

BACKHOE BUCKET QUICK COUPLER


Ronald C. Natzke, Burlington, and Thomas R. Brown, Yarmouth, both of Iowa, assignors to J. I. Case Company, Racine, Wis.

Filed Apr. 10, 1980, Ser. No. 139,037

Int. Cl.³ E02F 3/70

U.S. Cl. 37—103

2 Claims



1. A quick attachment and release mechanism for attaching a bucket to a loader scoop arm, said mechanism comprising: a quick coupler pivotally mounted to an end of said scoop arm for receiving various types and sizes of buckets, said quick coupler having a three-leg configuration including a pair of bucket mounting legs pivotally mounted to opposite sides of said scoop arm end, each bucket mounting leg including a hook portion engaging a lateral projection of a mounting pin on said bucket; a releasable latch mechanism rotatably mounted on a third leg of said quick coupler for engagement with a latch pin mounted on said bucket, said latch mechanism including a main body having a slot along its longitudinal extent, said main body rotatably mounted between spaced apart side members which form said third leg of said quick coupler; each side member including a bearing for rotatably holding one end of said main body, each bearing including a slot, said bearing slots forming an opening through said side members which is substantially the same size as the opening formed by the slot in said main body; a latch arm mounted to said main body, said latch arm being movable in the space between said side members for rotating said main body, said latch arm having an opening therein; and said side members having spaced apart first and second latching openings, said opening in said latch arm being aligned with and secured to said first opening through said side members by pin means thereby axially aligning said slot in said main body with said bearing slots so that said main body slot may be seated on said bucket latch pin, and said opening in said latch arm being aligned with and secured to said second opening through said side members by said pin means thereby providing a mounting for said bucket latch pin in said main body for coupling said bucket to said quick coupler.

4,295,288

HOLDER FOR INFORMATION CARRIERS IN STRIP FORM


Ake G. Westberg, Sundsvall, Sweden, assignor to H. L. Plast H. Lundvall AB, Sundsvall, Sweden

Continuation-in-part of Ser. No. 841,764, Oct. 13, 1977, abandoned. This application Nov. 22, 1978, Ser. No. 962,849

Claims priority, application Sweden, Oct. 15, 1976, 7611481 Int. Cl.³ G09F 3/18

U.S. Cl. 40—16.4

10 Claims



1. A holder for information strips, such as price strips for supermarket shelves, goods containers and the like, comprising:

- (a) an attachment portion for removably mounting the holder to a shelf, container edge or the like,
- (b) a display portion for receiving an information strip, said display portion defining a pocket having an upwardly directed opening and a portion extending below said attachment portion, said pocket having a prestressed transparent front wall forming a front-facing surface of said holder, said display portion flexible to deflect said front wall under a force applied to said pocket portion extending below said attachment portion thereby opening said upwardly directed opening and
- (c) means connecting a rear wall of said display portion to said attachment portion at a point spaced from the bottom of said pocket.

4,295,289


LASER AIMING DEVICE WITH LATERAL SHOCK ABSORBER

Wesley L. Snyder, 1103 Forest Home Dr., Houston, Tex. 77077
Continuation-in-part of Ser. No. 949,997, Oct. 10, 1978, Pat. No. 4,168,588, which is a continuation-in-part of Ser. No. 846,691, Oct. 31, 1977, Pat. No. 4,161,076. This application Feb. 12, 1979, Ser. No. 11,085

Int. Cl.³ F41G 1/34

U.S. Cl. 42—1 A

18 Claims



1. An aiming device for attachment to a barrelled weapon comprising:

- a light source for projecting a coherent beam of light onto a target;
- a member securable to the weapon for carrying said light source such that the beam is directed along the barrel of the weapon, said member defining an internal surface;
- a longitudinal buffer supported by said member and interposed between said light source and said internal surface for cushioning said light source from shock upon recoil of said weapon; and
- shock absorbing materials disposed laterally of said light source for preventing damage to said light source due to lateral impact.

4,295,290

TOY PROJECTILE


George T. Boswell, Springfield, Va., assignor to Frontier Industries, Inc., Springfield, Va.

Filed Jul. 1, 1980, Ser. No. 164,909

Int. Cl.³ A63H 27/00

U.S. Cl. 46—74 C

10 Claims



1. A toy projectile having an upper stage and a lower stage, said upper stage comprising a plurality of vanes movably mounted thereon for movement between a closed, substantially longitudinally extending position and an open, substantially radially outwardly extending position, means for biasing said vanes to said open position, and an adaptor portion disposed on the lower end of said upper stage and comprising a downwardly opening tubular section; and said lower stage comprising a first tubular portion having an upper end adapted to be received within said tubular section of said adaptor portion to removably secure said lower stage to said upper stage, means mounted on said first tubular portion for engaging the lower portions of said vanes to retain them in said closed position when said upper and lower stages are removably connected, and means mounted in the lower end of said first tubular portion for propelling said projectile and for separating said upper and lower stages to enable the lower portions of said vanes to move away from said retaining means, whereby said biasing means moves said vanes to said open position.

4,295,291

TOY FIGURE HAVING REPOSITIONABLE HEAD AND LIMBS

Osamu Fukui, Tokyo, Japan, assignor to Takara Co., Ltd., Tokyo, Japan


Filed Nov. 1, 1979, Ser. No. 90,414

Claims priority, application Japan, May 1, 1979, 54-58486[U]

Int. Cl.³ A63H 3/20

U.S. Cl. 46—161

4 Claims



1. A toy doll figure comprising:
a plurality of limb members configured to simulate limb members such as arms and legs of a humanoid;
a head member configured to simulate a humanoid head;
an approximately triangularly-shaped hollow body member having a front portion and a rear portion, each portion

having a substantially flat panel respectively corresponding to the front and the back of the toy doll figure and a peripheral rim disposed substantially at a right angle to the flat panels, the body member being assembled from the front and rear portions so that the rims are in contact with one another, the rims having apertures approximately aligned with the respective positions of the limb members and head members and one or more of the front portions and rear portions having an aligned aperture with a rim aperture extending across its flat panel to form a continuous slot that extends across the right angled interface of the flat panels and the rim, each limb member having a substantially flat mating surface with a substantially circular periphery to permit a juxtapositional mounting of the respective limb members flush against the body member; the rim aperture for the arm limb members positioned to enable the arms to extend vertically upward relative to a horizontal support surface;

resilient connectors are fixedly attached to each limb member and head member and are attached within the hollow body member to permit limited relative movement between the body member and each limb member and the head member;

at least a pair of rib members are mounted respectively on the front portion and the rear portion within the hollow body member to secure at least one resilient connector, the respective rib members extend upward from the interior of the flat panel members respectively and are spaced apart from the peripheral rim, one of the respective rib members is configured with a groove to receive a portion of the resilient connector while the other rib member is configured with a flat surface to hold the resilient connector within the groove whereby the head member and the limb member may be selectively placed in at least two positions at the option of a player.

4,295,292

DEMOLITION DERBY TOY


Stella Fitzgerald, Las Vegas, Nev., and Bryan Beaver, 3660 Boulder Hwy. - Space 129, Las Vegas, Nev. 89121, assignors to Bryan Beaver, Las Vegas, Nev.

Filed Dec. 11, 1979, Ser. No. 102,436

Int. Cl.³ A63H 11/10

U.S. Cl. 46—201

8 Claims



1. A demolition derby toy which comprises, in combination,
(a) a vehicle,
(b) shaft means slidably positioned in said vehicle along a vehicle axis and greater in length than said vehicle axis in said vehicle along which it lies,
(c) removable vehicle component means spanning a vehicle axis and removable from said vehicle in response to movement of said shaft means against said removable vehicle component, and
(d) ram means on said vehicle extending outwardly from said vehicle beyond a removable component means, wherein each said shaft means includes a shaft, a spring on each end of said shaft and a disc on each said spring, the distance between said discs being greater than the length of the vehicle along the shaft axis, said movable component means spanning said discs, said vehicle having grooves on opposite sides of said discs, said removable component means being

removably positioned in said grooves and capable of both inward and outward movement in said grooves.

4,295,293

NURSING BOTTLE HOLDER


Paul S. Baclit, 2167 College View Dr., Monterey Park, Calif. 91754

Filed Apr. 4, 1980, Ser. No. 137,289

Int. Cl.³ A63H 17/26; A47D 15/00

U.S. Cl. 46—202

2 Claims



1. A nursing bottle holder in conjunction with a pull toy, forming a combination toy, wherein,
the bottle holder includes a main support member adapted to be placed in an active position over an infant in lying position, and having its longitudinal dimension in the head-to-body direction of the infant, and having a top wall element and depending side elements with bottom surfaces engageable with the surface the infant is lying on, said bottom surfaces being shaped to contact said surface and support said main member stably thereon,
a bottle support demountably supported on the main support member, and a bottle carriage supported in the bottle support for positioning a bottle carried thereby for feeding by the infant,
the depending side elements having vertical slots opening from said bottom surfaces in longitudinally spaced positions therealong, and
the pull toy having axles and wheels supporting a body, and the main support member being fitted over the body of the pull toy, with the slots receiving the axles, and the pull toy supporting the nursing bottle holder, thereby constituting the combination toy.

4,295,294

TOY LAWN MOWER


Donald A. Rosenwinkel, Tinley Park; Burton C. Meyer, Downers Grove, and Harry Disko, South Barrington, all of Ill., assignors to Marvin Glass & Associates, Chicago, Ill.

Filed Apr. 11, 1980, Ser. No. 139,467

Int. Cl.³ A63H 11/10

U.S. Cl. 46—205

12 Claims



1. A toy power tool comprising:
a housing in the shape of a power tool;
wheel means mounted on said housing for rotation when said housing is pushed over a surface; and,
enclosure means extending away from said housing for holding particulate matter, said enclosure means including a

bed of particulate matter and agitating means mounted within said enclosure means for creating a cloud-like particulate suspension of said matter in air, said agitating means including a rotatable brush mounted adjacent one end of said enclosure means, a lower end of said enclosure means conforming to the path of movement of said agitating means so that said particulate matter is contacted by said agitating means and dispersed within the interior of said enclosure means when said toy is pushed over a surface, said agitating means being operably connected to said wheel means and said enclosure means including a transparent region to make said cloud-like suspension visible from outside said enclosure means.

4,295,295

PICK-UP SHOE AND MOTOR CONTACT ASSEMBLY FOR TOY VEHICLE


Derek A. Brand, Camarillo, and Derek R. Brand, Carpinteria, both of Calif., assignors to Tyco Industries, Inc., Moorestown, N.J.

Filed Mar. 17, 1980, Ser. No. 130,757

Int. Cl.³ A63H 18/12; F42B 13/34; H02K 21/26

U.S. Cl. 46—259

26 Claims



1. A pick-up shoe and motor contact assembly for a toy vehicle having a chassis and a motor for powering the vehicle, the motor having commutator segments, comprising:
a least one conductive brush arm for contacting the commutator segments of the motor,
said brush arm being moveable with respect to the motor commutator segments,
at least one conductive pick-up shoe depending from the vehicle chassis,
resilient means disposed in contact relation with said pick-up shoe and said brush arm for resiliently urging said pick-up shoe downwardly while resiliently urging said brush arm against the motor commutator segments,
said resilient means being adapted to conduct electrical current between said pick-up shoe and brush arm.

4,295,296

VERTICAL GARDEN

Michael H. Kinghorn, 178 Bible St., Cos Cob, Conn. 06807

Filed Jan. 14, 1980, Ser. No. 111,863


Int. Cl.³ A01G 25/00

U.S. Cl. 47—82

14 Claims

1. An upright garden assembly for culture of vertical garden displays comprising a plurality of elongated open top growing troughs, said troughs having front and rear sides and drain apertures, support frame means for separately removably supporting said troughs horizontally one above the other to form a substantially vertically extending row of trays with the drain apertures of each trough positioned and directed toward said rear side to cause drainage to be directed to the rear of the rear sides of the troughs thereunder, a water container mounted above said row, a separate horizontal distribution conduit mounted above each trough and having irrigation aperture means for directing water to the respective trough, and plural

separate tubes extending substantially directly downwardly from the lower portion of said water container, each tube being



releasably terminated in a respective distribution conduit in a removable connection.

4,295,297

REVOLVING SECURITY DOOR

Noel Carroll, Poet's La., Sherbrooke, Victoria, and William F. Carroll, 5 Garden Ct., Wheelers Hill, Victoria, both of Australia


Filed Sep. 24, 1979, Ser. No. 78,491

Claims priority, application Australia, Oct. 6, 1978, PD6263; Aug. 2, 1979, PD9865

Int. Cl.³ E05D 15/02

U.S. Cl. 49-42

3 Claims



1. The security door comprising:

- (a) a revolving door assembly having an upright shaft and a plurality of outwardly extending upright door panels secured thereto, said door assembly being arranged for rotation about the axis of said shaft,
- (b) an enclosure extending around said revolving door assembly and presenting two opposed portions one to either lateral side of the revolving door assembly and each extending from an entrance to the security door to an exit thereof, the said opposed portions being so arranged that, as the said revolving door assembly revolves about said axis, there are always at least two said panels in position adjacent the upright inner surface of each respective said opposed portion to define a separate closed space between each respective opposed portion and the two adjacent said panels, whereby a person passing through the security door must move around said axis between an adjacent pair

- of said panels under rotation of the revolving door assembly, and through a said substantially closed space,
- (c) an electric motor,
- (d) a reduction gear drive coupled to said motor and to said shaft for driving of said shaft by operation of said motor through said reduction gear drive,
- (e) rotation controlling means permitting revolving of said revolving door assembly about said axis in one direction but precluding operation in the other direction,
- (f) a control circuit controlling operation of said motor for effecting revolving of the revolving door assembly in said one direction, said control circuit having a detector for detecting the presence of a person at said entrance and operating, pursuant to said detecting, to then cause said operation of said motor to revolve said revolving door assembly in said one direction and to brake the motor at the end of one revolution to stop revolving of the revolving door assembly,
- (g) an electric clutch mechanism coupled to said shaft,
- (h) a mat switch positioned in said enclosure adjacent to one of said opposed portions, being that of said opposed portion which must be passed by a person attempting passing through the security door from said exit to said entrance when said revolving door assembly revolves in said one direction, said mat switch being located such that it must be stepped on by such person attempting passing; said clutch mechanism and said mat switch being interconnected with said control circuit whereby said clutch mechanism is energized under control of the control circuit to lock said shaft against rotation thereof when a person steps on said mat switch whereby in use a person so stepping on the mat switch is trapped in the said substantially closed space then defined adjacent to the said one opposed portion.

4,295,298

WINDOW REGULATOR


Richard A. Pundt, 4118 Hickory Hill La. SE., Cedar Rapids, Iowa 52403

Filed Aug. 27, 1979, Ser. No. 70,178

Int. Cl.³ E05F 11/14

U.S. Cl. 49-353

3 Claims



1. A window regulator for vehicles comprising,
 - a vehicle door having a window opening, an interior side and exterior side,
 - a window pane recessed in said door, adapted to move through said window opening, and including two substantially vertically disposed edges,
 - a guide bar on said window pane within said door,
 - a single eccentric arm pivotally mounted away from its ends within said door with one end thereof being movably secured to said guide bar, and said pivot point being offset below a line extending between the opposite ends of said arm whereby the opposite ends of said arm move in substantially opposite directions,
 - an arcuate slot in said door being substantially vertically disposed and positioned forward from and concentrically about said pivot point,
 - a handle on the other end of said eccentric arm and being recessed within said arcuate slot and extending interior-

ally through said slot no further than the interior of said door, and means connected to said door between the sides thereof and adapted to slidably receive the edges of said window pane.

4,295,299

STEEL CLAD WOOD DOOR FRAME


David M. Nelson, Kewanee, Ill., assignor to United States Gypsum Company, Chicago, Ill.

Filed Oct. 9, 1979, Ser. No. 83,133

Int. Cl.³ E06B 1/04

U.S. Cl. 49-504

6 Claims



1. A door frame comprising wood frame members including a strike jamb, a hinge jamb, and a header, said frame members each being recessed longitudinally to provide a rabbet having a major surface and a minor surface perpendicular to said major surface, a slot substantially coplanar with a major surface of said rabbet extending into a non-recessed portion of said member and along substantially the entire length of said member, and a substantially J-shaped metal frame reinforcing member extending along substantially the entire length of said member and having a major flange, a minor flange substantially parallel to said major flange, and a connecting web substantially perpendicular to said major and minor flanges, said minor flange engaging the major surface of said rabbet and extending into said slot, and the major flange of said reinforcing member extending in engagement with the outer surface of said member.

4,295,300

FLAP ARRANGED ON DISCHARGE AND SEPARATING DEVICES OF VIBRATORY ABRASIVE CONTAINERS

Carl K. Walther, Wuppertal-Vohwinkel, and Karl Temme, Wuppertal-Elberfeld, both of Fed. Rep. of Germany, assignors to Carl Kurt Walther GmbH & Co. KG, Wuppertal, Fed. Rep. of Germany


Filed May 27, 1980, Ser. No. 153,807

Claims priority, application Fed. Rep. of Germany, Jun. 9, 1979, 2923414

Int. Cl.³ B24B 31/00

U.S. Cl. 51-163.2

13 Claims



1. In discharge and separating devices of vibratory abrasive containers forming a trough and having a flap for the placing into operation a separating path which is coordinated behind

the flap, the flap being swingable around an axis of the flap shaft which is transverse to the container trough and being able to be moved upwardly by means of an actuating device into a maximum upper position, the improvement comprising a control lever operatively connected to the actuating device being pivotally mounted under a portion of flap parallel to the flap shaft, the control lever having a free end formed with a pin, the flap being formed with an elongated slot having an end region, the pin engaging into the slot in the flap and constituting means for limiting the upward movement of the flap by abutting against the end region of the slot.

4,295,301

DRESSING APPARATUS WITH MEANS FOR DETECTING GRINDING WHEEL WEAR


Charles F. Barth, Parma; Thomas S. Stelson, Richmond Heights, and David E. Blake, Cleveland Heights, all of Ohio, assignors to TRW Inc., Cleveland, Ohio

Filed Nov. 8, 1979, Ser. No. 92,623

Int. Cl.³ B24B 53/00

U.S. Cl. 51-165.88

8 Claims



1. An apparatus comprising a grinding wheel having a circular side surface for use in grinding a workpiece, a member, motor means for moving said member toward the circular side surface of said grinding wheel from a retracted position in which said member is spaced from the circular side surface of said grinding wheel, drive means for rotating said grinding wheel as said member moves toward the circular side surface of said grinding wheel, detector means for detecting when said member initially engages the circular side surface of said grinding wheel, and control means for effecting operation of said motor means to move said member toward the side surface of said grinding wheel in incremental steps and for interrupting movement of said member between steps for a time period sufficient to enable said drive means to rotate said grinding wheel through at least one complete revolution.

4,295,302

INFLATABLE TENT

Morris Liu, 5, Alley 21, Lane 172, Sec. 1 Keelung Rd., Taipei, Taiwan

Filed Oct. 9, 1979, Ser. No. 82,941

Claims priority, application Taiwan, Aug. 21, 1979, 6823010


Int. Cl.³ E04B 1/345

U.S. Cl. 52-2

4 Claims

1. An inflatable tent substantially comprising a plurality of inflatable frames for supporting the tent; an air passage tube for

interconnecting the frames and permitting air to flow therein; a plurality of blockage studs installed on the air passage tube for partitioning the air system inside the tent into several isolated parts; a waterproof layer of plastic film integrally formed with the frames and the air passage tube for filling the gaps between the frames and between the frames and the air passage



tube; the frames, the air passage tube, and the plastic film are multi-layer structured and all comprise an inner layer of soft plastic film and an outer layer of reinforcing netted plastic material; and inlet and an outlet for receiving or releasing air respectively; and a plurality of handles for easy set up of the tent.

4,295,303

GEODETIC DOME


Wilmer A. Klebe, 35 Park Ave., Petaluma, Calif. 94952

Filed Oct. 1, 1979, Ser. No. 80,743

Int. Cl.³ E04B 1/32;

U.S. Cl. 52—81

25 Claims



1. A joint for a geodesic dome structure comprising: a spool having an outer surface including a radially projecting circumferential spline;
- a plurality of beams having ends abutting the outer surface of the spool and engaging the spline to prevent movement of the beams axially with respect to the spool, each said beam having engaging means spaced from the end of the beam in abutment with the spool; and
- a tension member passing through the engaging means in the beams and coplanar with the spool to retain the beams against the spool and prevent movement of the beams radially with respect to the spool.

4,295,304

PREFABRICATED PANEL CONSTRUCTION SYSTEM

Kwon S. Kim, Oklahoma City, Okla., assignor to Star Manufacturing Company of Oklahoma, Oklahoma City, Okla.

Filed Apr. 4, 1978, Ser. No. 893,435

Int. Cl.³ E04B 7/02; E04C 1/10

U.S. Cl. 52—90


10 Claims

1. A prefabricated building system having an arrangement of

support members disposed on a foundation for supporting the walls and roof of a building, comprising:

a plurality of panels of generally rectangular shape adapted to be joined edge to edge to form walls and a roof; each panel having a foamed insulating core disposed between the interior and exterior metal sheets, the metal sheets having strengthening corrugations running generally parallel to side edges and transversely to end edges of the panels;

trim disposed at the juncture of the walls and the roof to form a weather-tight enclosure,



first closure strips disposed along the upper ends of the walls, the first closure strips having flat outer surfaces for attaching the trim and inner surfaces conforming to the corrugated exterior of the wall panels;

second closure strips disposed on an upper surface of the trim along a side of the building running transversely to the corrugations in the roof panels adjacent thereto, the second closure strips having flat lower surfaces for mounting on the trim and upper surfaces conforming to corrugated exterior of the roof panels;

the roof panels having an end flap portion of the exterior metal sheet extending beyond the foamed core to overlie and make a seal with the second closure strips.

4,295,305

THERMAL GLASS STRUCTURE AND METHOD FOR FORMING SAME


Lyle N. Shelver, 5020 Ambrose Dr., Reno, Nev. 89502

Continuation-in-part of Ser. No. 585,299, Jun. 9, 1975, Pat. No. 4,033,087, which is a division of Ser. No. 460,277, Apr. 12, 1974, Pat. No. 3,889,434. This application Dec. 23, 1976, Ser. No. 754,033

Int. Cl.³ E06B 7/12

U.S. Cl. 52—172

2 Claims



1. The method of forming a double-walled thermally insulated window including: (1) Placing two rectangular panes of glass of the same size and shape upon a spacer containing desiccant material adjacent the edges of said panes of glass; (2) providing a coating of waterproof mastic about the edges of the panes of glass and the desiccant and spacing material so as

to form one unit; (3) cutting a length of pliable material to the length which equals the length of all four edges of the rectangular unit as formed, and cutting three slits into said pliable material at those positions which will allow three corners of the said glass unit to protrude through said slits and wherein the slits are cut at such a distance that the fourth corner extends through the pliable material where the two cut ends of the pliable material are brought together, and placing said pliable material about the edges of said unit as formed; (4) placing adaptive elements of rigid material about said pliable material on each side of the unit; and (5) fastening the corners of the adaptive elements together.

4,295,306

WINDOW CLIP RETAINER

Ronald H. Garman, Pekin, Ill., assignor to Caterpillar Tractor Co., Peoria, Ill.

PCT No. PCT/US79/00365, § 371 Date May 29, 1979, § 102(e)

Date May 29, 1979, PCT Pub. No. WO80/02676, PCT Pub.


Date Dec. 11, 1980

PCT Filed May 29, 1979, Ser. No. 89,118

Int. Cl.³ B60J 1/02, 1/08

U.S. Cl. 52—208

24 Claims



1. In a window assembly (10,110,210, 310,410,510) having a pane (15,115,215,315,415,515) provided with a peripheral frame (16,116,216,316,416,516), and resilient mounting means (20,120,220,320,420,520) extending about the periphery of the frame for resiliently sealingly mounting the frame to a wall portion (14,114,214,314,414,514) defining an opening (13,113,213,313,413,513) for receiving the window assembly, said resilient mounting means providing the normal sole mounting of the frame to said wall portion, the improvement comprising a motion limiting means comprising:

a substantially rigid retainer (21,121,221,321,421,521) having a mounting portion (22,122,222,322,422,522), and a retaining portion (25,125,225,325,425,525); and

securing means (23,123,223,323,423,523) for fixedly securing said mounting portion to one of said wall portion and said frame, said retaining portion being disposed adjacent the other of said wall portion and frame with a preselected spacing therebetween in the normal position of the frame as supported by said resilient mounting means to prevent dislodging of the window assembly from the wall portion in the event of relative movement between the wall portion and frame permitted by said resilient mounting means reaching a preselected maximum movement as determined by said spacing of said retaining portion.

4,295,307

MODULAR BUILDING STRUCTURE

David C. Jensen, 2357 Riverside Dr., North Vancouver, British Columbia, Canada (V6B 1C8)

Continuation of Ser. No. 796,974, May 16, 1977, Pat. No. 4,186,533. This application Aug. 6, 1979, Ser. No. 63,761


Int. Cl.³ E04B 1/343, 2/28

U.S. Cl. 52—236.1

22 Claims

1. A freestanding, post-free modular building structure comprising an array of upright modular panels; panel-connecting means connecting adjacent edges of adjacent panels in said array; three overhead beam members, said beam members

being horizontal and assembled in coplanar triangular relationship; and beam-and-panel connecting means connecting each end of said beam members with one adjacent beam member end with said beam members in such triangular relationship



4,295,308

POLE BASE ASSEMBLY, BOLT CIRCLE ADAPTOR


Carl Korfanta, Denver, Colo., assignor to K S L Corporation, Denver, Colo.

Filed Oct. 26, 1979, Ser. No. 88,530

Int. Cl.³ E04H 12/00

U.S. Cl. 52—296

4 Claims



1. An adapter for pole bases having a bolt hole configuration different than the bolts formed in a concrete foundation, comprising:

- (a) a generally square bottom plate having elongated bolt holes set on radials from the center of said plate for mating over the bolts in a concrete foundation, and having a large central circular bore;
- (b) a generally square top plate having elongate bolt holes set on radials from the center of said plate for mating with bolt holes on a pole base which are of a different configuration than the bolts on the concrete foundation, and having a central circular bore;
- (c) a short length of pipe welded into the bores of said bottom and top plates to rigidly hold said plates parallel and provide space for manipulating attaching nuts and bolts, and
- (d) at least four spacers welded to the top and bottom plates securing the plates rigidly and strongly together and spaced a predetermined distance apart, said spacers being spaced uniformly around said short length of pipe.

4,295,309

LOAD SUPPORT STRUCTURE

Clarence J. Hornbeck, Allentown, Pa., assignor to Follett Corporation, Easton, Pa.

Filed Oct. 1, 1979, Ser. No. 80,885


Int. Cl.³ E04C 1/26

U.S. Cl. 52—309.7

20 Claims

1. Apparatus comprising a housing having at least one wall

for resisting forces within the housing, said wall comprising a tension member on an outer surface thereof and at least one arched compression member inwardly thereof, said compression member being juxtaposed to the tension member and spaced therefrom except for the end portions thereof, said members having curved end portions adjacent each free end thereof, the curved end portions of said members being welded together, each free end of said compression member being spaced from the adjacent free end of said tension member, a low modulus filler between said members and bonded to the



juxtaposed surface of each of said members so that force supplied to one of said members will be resisted in part by the shear and tension strength of the filler, and means for supporting said members on said housing at or adjacent the focal points for minimizing residual bending moments including at least one hanger on opposite sides of the end portions of said tension member, each hanger having one end fixedly anchored to a support on said housing and which is stationary with respect to said wall, each hanger having its other end fixedly secured to the tension member at a location spaced from the ends of the tension member.

4,295,310

PRECAST CONCRETE JOIST COMPOSITE SYSTEM


Ira J. McManus, 39 Lincoln Ave., Florham Park, N.J. 07940

Filed Aug. 22, 1979, Ser. No. 68,830

Int. Cl.³ E04B 1/16

U.S. Cl. 52—334

41 Claims



1. A precast concrete joist composite system, comprising:
 - (a) support means;
 - (b) at least first and second space apart precast concrete joist members supported at their respective ends by said support means, each of said joist members having a concrete portion, said concrete portions comprising respective end faces, said joist members comprising at their said end portions respective projecting structures that have first parts anchored in said concrete portions of their respective joist members and second parts extending from said concrete portions, said joist members including end faces, said end faces having respective portions thereof that slope downward and away from said concrete portions, said concrete portions comprising respective top surfaces; said projecting structure second part being at least partly disposed on said support means;
 - (c) at least a first pan element that is disposed at said end face, a first part of said pan element being disposed over said top surfaces of said concrete portions and a second part thereof disposed over said sloping portions of said end faces;
 - (d) a decking element disposed over the respective said top

surface of said first and second joist members and spanning the space between said joist members and part of said first pan element.

4,295,311

EXPANSION JOINT ELEMENT

Anders Dahlberg, Täby, Sweden, assignor to Tätis Plasttätning AB, Täby, Sweden


Filed Nov. 28, 1979, Ser. No. 98,047

Claims priority, application Sweden, Dec. 1, 1978, 7812402

Int. Cl.³ E01C 11/04; E04B 1/68

U.S. Cl. 52—396

6 Claims



1. A pre-fabricated expansion joint element for forming an elongated surface joint between two concrete construction parts, comprising an intermediate resilient member, substantially consisting of an elastic material, and side elements adjoining at each side thereto, and respectively adapted to be secured to one of the concrete construction parts, said side elements being constituted by profile elements of an epoxy plastic having reinforcing means, said profile elements being securable by adhesion directly onto the edge portions of the concrete construction parts, the intermediate resilient member having a thickened central portion, at least one of said reinforcing means being integrally cast into both of the profile elements as well as into the intermediate resilient member, and the external surface of the intermediate resilient member being connected to and substantially in alignment with the external surfaces of the profile elements.

4,295,312

BUILDING CONSTRUCTION


Henry F. Campbell, Belleville, Mich., assignor to Campbell Research Corporation, Detroit, Mich.

Filed Jan. 22, 1979, Ser. No. 5,473

Int. Cl.³ E04B 1/40, 7/00

U.S. Cl. 52—408

7 Claims



1. A building construction comprising a panel comprising spaced sheets and a plurality of spaced longitudinally extending prefabricated truss members, each said truss member comprising a pair of channels and an undulating member comprising alternating first and second apices connected by legs, the apices being bonded to said channels, at least one of said sheets having a plurality of transversely spaced longitudinally extending grooves receiving the truss members, said grooves having a cross sectional configuration conform-

ing to the cross sectional configuration of the channel of said truss member, and means for fastening said last-mentioned channel to said sheet, said sheet having said grooves therein including a partially extending groove along each longitudinal edge in which a truss member is positioned, the corresponding channel of the truss member including a base wall and side walls, the free edge of the sheet terminating along the base wall of the channel, adjacent panels being positioned such that they extend parallel with one another in side-by-side relation, a plurality of said panels, means defining a joint between adjacent panels comprising a member which has a generally T-shaped section including a web extending between the flanges of adjacent truss members of panels and engaging the free edges of said flanges of the adjacent channels of said truss members and arms extending laterally outwardly and including portions extending inwardly against the sides of the partial groove in the sheet member.

4,295,314

SHOULDERED SHAKE AND FILLER ROOF STRUCTURE


Stewart Ferguson, P.O. Box 12, Aloha, Wash. 98525

Filed Jul. 23, 1979, Ser. No. 59,998

Int. Cl.³ E04D 1/00

U.S. Cl. 52—553

16 Claims



1. In a roof including generally rectangular individual covering elements having respective butt and tip ends and applied in generally coplanar, side adjacent relationship in each of several overlapping courses, the improvement comprising the adjacent sides of adjacent covering elements in a course having respective shoulders extending transversely of such sides, each shoulder dividing its covering element into respective tip and butt portions of unequal width, and a filler fitted between such adjacent sides and abutting said shoulders.

4,295,313

BUILDING BLOCKS, WALL STRUCTURES MADE THEREFROM AND METHODS OF MAKING THE SAME


John N. Rassias, c/o Intralock Systems International Corporation, 565 Park Ave., New York, N.Y. 10021

Filed Dec. 10, 1979, Ser. No. 102,251

Int. Cl.³ E04B 2/68

U.S. Cl. 52—438

10 Claims



1. A substantially rectangular masonry building block having a pair of spaced opposite generally parallel side walls, spaced top and bottom faces and a pair of spaced end faces, a pair of spaced apart ribs on said top face, one adjacent and spaced from each side wall, a pair of mating recesses on said bottom face, an intermediate generally centrally extending horizontal groove in each of the top and bottom faces, a pair of narrower grooves, one on either side of said centrally extending groove on each of said top and bottom faces and spaced from said ribs and mating recesses and from said intermediate groove, a pair of spaced ribs on one end face, a pair of mating grooves on the other end face, said ribs and grooves being aligned with the ribs and recesses on the top and bottom faces, an intermediate vertical passage in said block corresponding in width to the widest portion of the central grooves on said top and bottom faces, a pair of vertical passages on each side of said intermediate vertical passage connecting the pair of top and bottom narrower grooves, and a vertical recess in each end face intermediate the side walls and having a cross section substantially equal to one half of said intermediate vertical passage.

4,295,315

EXPANSION JOINT COVER


David M. Lynn-Jones, Muncy, Pa., and R. Gordon Stewart, Georgetown, Canada, assignors to Construction Specialties, Inc., Cranford, N.J.

Filed Oct. 23, 1978, Ser. No. 953,775

Int. Cl.³ E04B 1/68

U.S. Cl. 52—573

3 Claims



ing of end portions of the tongues of each of the frame members between end portions of the tongues of the other along the expansion gap, and wherein each frame member includes a longitudinally continuous flange extending generally inwardly from the vertical wall portion toward the expansion gap and spaced apart from and located above the tongues, the flange defining with the tongues a longitudinal inwardly open cavity, and a resiliently compressible sealing element composed of interconnected walls defining hollow longitudinally elongated cells engaging the vertical wall portions of the respective frame members and supported by the tongues, wherein portions along the edges of the sealing element are received and retained in the respective cavities of the frame members, wherein said sealing element includes a multiplicity of longitudinally continuous side by side, generally rectilinear hollow cells defined in cross section by transversally spaced apart generally vertical walls and vertically spaced apart generally transverse walls interconnecting the respective top and bottom edges of adjacent vertical walls, at least one of the transverse walls of each cell having angularly related segments adapted to fold into the space within the cell upon movement of the building sections toward each other tending to close the gap, said transverse walls having angularly related segments being the top walls on every other cell along the width of the element and the bottom walls of the remaining cells, the number of side by side cells of the sealing element being an uneven number not less than five, and the top wall of the center cell having angularly related segments, and wherein the vertical walls defining the center cell extend higher above the tongues than the vertical walls of the remaining cells, the top of the walls of the center cell being generally flush with the upper surface of the flanges of the frame members.

4,295,316

NESTABLE BUILDING WALL PANEL


Lawrence E. Carlson, Lower Burrell, Pa., assignor to Aluminum Company of America, Pittsburgh, Pa.

Filed May 2, 1977, Ser. No. 792,782

Int. Cl.³ E04C 1/10

U.S. Cl. 52—588

1 Claim



1. A contoured building panel adapted to be secured to a building structure by concealed fasteners, said panel having faces for exposed and concealed disposition on a building structure and having improved nestability with other like panels in a vertical stack for storage and shipment with a relatively short stack height, comprising:

- (a) a body portion including at least one longitudinally extending channel therein having opposed sidewalls substantially continuously diverging from the bottom of the channel to the mouth of the channel to permit nesting of the channels of stacked panels, each of said diverging sidewalls defining an angle of 5° to 80° measured between said sidewall and a plane passing through the sidewall near the mouth of the channel and normal to the general plane of said panel;
 - (b) lateral edge structures along opposite sides of said body portion for engagement with an opposite edge structure of an adjacent panel;
- each of said edge structures projecting outwardly substantially laterally from the mouth of the channel in said body portion, having leg portions substantially lying in a plane parallel to the general plane of said panel with no portion of each of said edge structures projecting inwardly beyond the periphery of its respective side of said body portion, and having a maximum extent mea-

sured perpendicular to the general plane of said panel no more than 25% of the extent of the channel measured in the same direction, the perpendicular extent being determinative of the nesting height of stacked panels;

- at least one of said edge structures having a reverse bend therein forming a groove open laterally inward of said panel for receiving at least a portion of the opposite edge structure of an adjacent panel for engaging said panels in a tension joint;
- (c) a fastening edge portion on the edge structure which has said reverse bend therein and disposed laterally outwardly of the open mouth of said groove and adapted to receive fastening means to secure said panel to a building structure with the fastening means underlying said body portion of the adjacent panel for concealing the fastening means; and
- (d) the angle of the diverging sidewalls of the channel being a function of the maximum perpendicular extent of said edge structures so that said like panels when vertically stacked contact adjacent panels along the leg portions of said edge structures and along said diverging sidewalls of said channel for increasing support surfaces of nested panels.

4,295,317

MODULAR TOWER AND METHOD OF CONSTRUCTING SAME


Willem R. VanTiel, Rte. No. 3, Box 17, East Jordan, Mich. 49727

Filed Jun. 14, 1979, Ser. No. 48,482

Int. Cl.³ E04H 12/00

U.S. Cl. 52—637

6 Claims



1. A modular tower comprising, in combination, substantially identical first and second tower sections, each tower section including at least two substantially identical parallel vertical columns, each of said columns having a hollow first end defined by an inside and outside diameter and a second end defined both by an outside diameter that is slightly smaller than said first end inside diameter and also by a shoulder, said second column ends in said first section being inserted in said first column ends in said second section until each of said first column ends abuts said shoulder on one of said second column ends; a brace assembly for connecting said sections, said brace assembly including a plurality of tubes and a plurality of support members rigidly connecting said tubes, each of said tubes being defined by a vertical axis and an inside diameter slightly larger than the outside diameter of said first column end, said brace assembly being positioned so that each of said tubes substantially surrounds one of said first column ends in said

first section at a point where one of said second column ends is inserted in said one first column end; and connecting means for rigidly securing said brace assembly to each of said first and second column ends at a point where said first and second column ends are surrounded by tubes in said brace assembly so as to fasten each of said tubes to first and second column ends in said tubes whereby one of said sections is supported on the other of said sections.

4,295,318

CONNECTOR FOR WOODEN TRUSS


Milton Perlman, Miami Beach, Fla., assignor to Monex Corporation, North Miami Beach, Fla.

Filed Jul. 26, 1979, Ser. No. 60,912

Int. Cl.³ E04C 3/02

U.S. Cl. 52—693

2 Claims



1. A unitary metal connector for interconnecting spaced-apart chord members of a wooden truss structure, wherein said truss structure includes a plurality of wooden studs extending between the parallel spaced-apart chord members, said connector comprising an elongated generally rectangular support member having a central stiffening rib extending longitudinally thereof and side flanges formed thereon and extending therefrom substantially normal thereto along the side edges of said rectangular support member, said connector further including two end plates respectively integrally formed with said support member at the opposite ends thereof, each of said end plates being generally rectangular in shape and coplanar with said support member and being oriented with respect to said support member so that the longitudinal axis of said support member extends generally diagonally of said end plates; each of said end plates having fastening means integrally formed therewith consisting of a plurality of rows of aligned barbs struck from the associated end plate and extending therefrom substantially normal thereto and in the same direction, said barbs being configured and arranged such that said fastening members are adapted to be respectively embedded in the two associated spaced-apart wooden truss members and into opposite ends of spaced wooden studs extending therebetween, for attachment thereto and to provide a strengthening interconnection therebetween.

4,295,319

FLOOR PANEL

Kary A. Griffin, Dallas, Tex., assignor to G. H. Products, Inc., Dallas, Tex.

Filed Oct. 31, 1979, Ser. No. 90,018


Int. Cl.³ E04B 2/28

U.S. Cl. 52—785

4 Claims

1. A floor panel for use in elevated floor assemblies, the panel comprising:
- a noncompressible solid core having a side;
 - a bottom metal sheet having an upwardly deflected edge formed about a periphery of the bottom, the edge forming a first shoulder;
 - a top metal sheet having a downwardly deflected edge, said edge spaced from the side of said core and inwardly of said first shoulder, said edge further forming a second shoulder, and said top metal sheet and bottom metal sheet being positioned on opposed sides of said core; and
 - a flexible edge member having an outer shoulder engaging

said first shoulder on said bottom metal sheet and an inner channel formed in said flexible edge member having an upper inner shoulder engaging the upper surface of said top metal sheet and a lower inner shoulder engaging said second shoulder of said top metal sheet, the channel receiving said deflected edge of said top metal sheet to prevent rotation of the flexible edge member, said flexible



4,295,320

CLOSURE CONVERSION APPARATUS FOR EXISTING CLOSURE APPLYING MACHINES


Wendell D. Willingham, Toledo, Ohio, assignor to Owens-Illinois, Inc., Toledo, Ohio

Filed Jan. 9, 1980, Ser. No. 94,514

Int. Cl.³ B67B 3/20; B65B 7/28

U.S. Cl. 53—201

5 Claims



1. In a capping machine of the type having a rotating turret arranged to successively move the plurality of bottles around its perimeter and including means for loosely positioning a threaded cap on the threaded neck of each bottle, a continuously rotating cap applicator shaft located above each bottle and movable therewith around the turret, and means for moving each applicator shaft downwardly towards the respective bottle for a portion of the peripheral path of the bottle around the turret, the improvement comprising a capping head carried by each applicator shaft including the following elements:

- (1) an annular housing assembly adapted to be rigidly secured to the lower end portions of the cap applicator shaft;
- (2) an annular cap actuator assembly mounted for rotation relative to said annular housing assembly, said annular cap actuator assembly having means on its inner wall for engaging a cap positioned on a bottle in the turret to rotate the cap;
- (3) a pair of annular radial surfaces respectively provided on said housing and said cap actuator assembly and disposed in axially spaced alignment;
- (4) a washer of frictional material mounted between said radial surfaces;
- (5) resilient means urging said radial surfaces towards each other, thereby controlling the amount of friction exerted on said friction washer, and
- (6) means for shielding said friction washer from ambient air, thereby maintaining the friction characteristics of said washer substantially independent of ambient humidity conditions.

4,295,321

ENVELOPE PROCESSING MACHINE


John R. DeHart, Coral Gables, and Robert A. Majewski, Homestead, both of Fla., assignors to Docutronics, Inc., Homestead, Fla.

Filed Jul. 9, 1979, Ser. No. 56,275

Int. Cl.³ B65B 43/30

U.S. Cl. 53—381 R

17 Claims



1. In a machine for advancing a pre-opened envelope and separating the envelope from its contents, the envelope having two panels defining an opening therebetween along a leading edge of the envelope and connected together along the remaining edges of the envelope, the machine having feeding means for receiving and advancing an envelope along a generally predetermined path, severing means disposed along the path for engaging the advancing envelope and cutting it inwardly of its opposite side edges to sever connections between the panels along opposite side edges thereof leaving one panel connected to the other panel along a trailing edge opposite the one edge and the contents in juxtaposition between the two panels, and separating means disposed to receive the severed envelope and its contents from the severing means and including a cylindrical vacuum drum having vacuum ports opening through its peripheral surface for engaging and holding the one panel in engagement with an associated portion of the peripheral surface of the drum, drive means for rotating the drum about its axis to advance the severed envelope and move it in a direction away from its contents, and a follower roller journaled for rotation about an axis parallel to the axis of said drum, said follower roller and said drum defining a nip therebetween through which said advancing severed envelope and its contents are constrained to pass, the improvement wherein said separating means includes an extraction roller journaled for rotation about an axis parallel to said drum axis and angularly spaced about said drum axis from said follower roller axis and in the direction of drum rotation for engaging the contents as the contents advances through said nip and along a path generally tangent to the peripheral surface of said drum, means for rotating the extraction roller about its axis, and abutment means in the path of the leading edge of the other panel for

engaging the other panel as it advances through said nip and along a path generally tangent to the peripheral surface of said drum and biasing the other panel toward the contents and the extraction roller to urge the contents toward engagement with the extraction roller.

4,295,322

TUBE FORMING SHOE AND METHODS OF FORMING A FLEXIBLE WEB INTO A TUBE


Peter Kuipers, Taylors, S.C., assignor to Nordson Corporation, Amherst, Ohio

Filed Oct. 15, 1979, Ser. No. 85,044

Int. Cl.³ B65B 9/00

U.S. Cl. 53—450

36 Claims



1. Apparatus for forming a flexible web into a tube, said apparatus including a tube forming shoe comprising: a tubular shoe having an entry end and an exit end, said entry end being defined by a web brake edge, said brake edge including a plurality of fluid ports directed outwardly for blowing fluid onto said web near said brake edge and for holding said web away from said brake edge where said web bends around said brake edge and when it is pulled through said shoe, and said brake edge having a forward curved portion which, when developed in a flat plane, has a radius approximately equal to the interior diameter of said shoe, and said brake edge further including straight portions extending from each side of said curved portion.

29. A method of forming a flat flexible film web into a tube-shaped film having a longitudinal seam, said method including the steps of:

introducing said web to one end of a tube forming shoe at an angle with respect to a longitudinal axis of said shoe, bending said film around a curved brake edge of said shoe, said brake edge having a formed curved portion which, when developed in a flat plane, has a radius approximately equal to the interior diameter of said shoe, and said brake edge further including straight portions extending from each side of said curved portion, drawing said film across said brake edge of said shoe and guiding said film into a tubular shape while pulling said film through said shoe, blowing fluid from said edge against said film to hold said film away from said brake edge as said film is bent around said brake edge and pulled through said shoe, and including the further step of sensing changes of position of an edge of said film prior to said bending and rotating said shoe in response to the change of position of said edge to adjust film position in said shoe.

4,295,323

TOWED CROP HARVESTER

Martin Maier; Josef Pürer, both of Gottmadingen, and Ronald Clemens, Allensbach, all of Fed. Rep. of Germany, assignors to Klöckner-Humboldt-Deutz AG (Zweigniederlassung Fahr), Gottmadingen, Fed. Rep. of Germany


Filed Mar. 28, 1980, Ser. No. 135,080

Claims priority, application Fed. Rep. of Germany, Mar. 30, 1979, 2912715

Int. Cl.³ A01D 75/28

U.S. Cl. 56—10.2

3 Claims



1. A harvesting machine comprising: a chassis adapted to be drawn along the ground; a harvesting mechanism on said chassis having a crop engaging mouth and adapted to harvest stalk crop guided into said mouth upon the movement of the chassis along the ground along a row of crop to be harvested; a tow bar pivotally connected to said chassis and adapted to be attached to a tractor to enable the chassis to be towed thereby; a hydraulic cylinder pivotally connected to said chassis and to said tow bar at respective locations spaced from the pivot between said tow bar and said chassis whereby hydraulic pressurization of said cylinder varies the angular orientation of said tow bar and said chassis about said pivot; two lateral guide feelers swingable on said chassis on opposite sides of said mouth responsive to the said position of said row; and control means connected between said feeler and said cylinder for pressurizing said cylinder in response to said feeler to align said mouth with said row, said control means including a hydraulic pump, a multiposition valve connected between said pump and said cylinder and having a valve-actuating solenoid, respective double-pole switches operatively connected with said feelers and actuated thereby each of said switches including a normally closed fixed contact opened by the pivoting of the respective feeler upon engagement with a stalk of said crop and a normally open fixed contact closed by said pivoting of the respective feeler and respective movable contacts assigned to said fixed contacts and connected to the respective feeler, first circuit means electrically connecting the normally closed fixed contact of one of said switches to the normally open fixed contact of the other switch and the normally open fixed contact of said one of said switches to the normally closed fixed contact of said other switch, second circuit means connecting the movable contacts, associated with said normally closed switches together and to an electric current source, and third circuit means connecting the movable contacts associated with said normally open switches to terminals of said solenoid.

4,295,324

BALANCED MOWER HEAD FOR CARRYING A PLURALITY OF MONOFILAMENT LINES


Alfred A. Frantello, Satellite Beach, Fla., and Lester R. Kefauver, Knoxville, Tenn., assignors to Corinco, Inc., Knoxville, Tenn.

Filed Jun. 30, 1980, Ser. No. 164,093

Int. Cl.³ A01D 55/18

U.S. Cl. 56—12.7

10 Claims



1. A head for carrying a plurality of monofilament lines suitable for being mounted on the shaft which secures the blade of a conventional rotary mower said head comprising: a head body defining an upper surface and a lower surface, and a centrally positioned bore extending through said head body, one end portion of said bore opening on said upper surface and the further end portion of said bore opening on said lower surface, said bore being proportioned for receiving said shaft, a plurality of line holders extending outwardly from said body, each of said line holders including a first end portion joined with said body at annularly spaced locations, and an outboard end portion, said outboard end portion defining an opening therethrough having an axis substantially perpendicular to the axis of said bore in said body, each of said line holders defining a leading surface, and a grass lifting blade carried by the leading surface of each line holder, said blade serving to generate air currents in a vertical direction during operation of said mower to stand the vegetation up during the cutting operation.

4,295,325

SUGAR CANE HARVESTER

Christopher J. Cannavan, Iona Rd., Home Hill, Queensland, Australia (4806)


Filed Sep. 10, 1979, Ser. No. 74,051

Claims priority, application Australia, Sep. 15, 1978, PD5981

Int. Cl.³ A01D 45/10

U.S. Cl. 56—13.9

5 Claims



1. A sugar cane harvester of the type having a mobile frame, a base cutter on the frame for cutting cane stalks at or near to ground level as the harvester advances, a chopping cutter on the frame, means for feeding cut cane stalks to the chopping cutter which cuts them into billets, and means for elevating and

discharging the billets, wherein the chopping cutter and elevating means include:

- a rotary cutter having a knife blade on a rotatable shaft,
- a vane thrower, rotatable about an axis parallel to that of the rotary cutter shaft,
- means for counter-rotating the rotary cutter and the rotary thrower,
- the rotary cutter knife blade coacting with a vane of the thrower to sever cane fed thereto into billets,
- the thrower thereafter throwing the severed billets upwardly, and
- a cane guard chute extending essentially upright from the thrower and receiving such severed billets, the upper part of said chute curving downwardly to an outlet for the billets,
- the speed of rotation of said thrower being such that said thrower propels the severed billets upwardly into and through said cane guard chute, without separate assistance, into a collecting bin.

4,295,326


SELF-PROPELLED FLAIL BLADE LAWN MOWER
Douglas F. Green, Brisbane, Australia, assignor to Royer Mowers (Aust.) Pty. Ltd., Brisbane, Australia

Filed Mar. 10, 1980, Ser. No. 129,092

Claims priority, application Australia, Nov. 4, 1977, PD2313
Int. Cl.³ A01D 50/02

U.S. Cl. 56—11.3

6 Claims



1. A self-propelled flail blade lawn mower comprising a support frame having forward and rearward ends, a handle assembly extending upwardly and rearwardly from said rearward end and a cutter housing extending forwardly of said forward end, said support frame and said cutter housing being affixed to a common cross member extending transversely across the support frame whereby the cross member supports the forward end of the support frame and the rearward end of the cutter housing, a rear axle and wheel assembly rotatably supported substantially in the vicinity of the rearward end of said support frame and a pair of front wheels rotatably mounted substantially in the vicinity of the forward end of said cutter housing, a cutter shaft bearing a plurality of pivotally mounted flail blades horizontally and rotatably supported within said cutter housing, said flail blades being adapted for rotation in a vertical plane, a motor and a transmission box mounted on said support frame, said motor having a downwardly extending output shaft and said transmission box having input and output shafts, first drive means operatively connected between said transmission box output shaft and said rear axle and wheel assembly, second drive means connectable between said motor output shaft and said transmission box input shaft in response to the movement of a first lever mounted on said handle assembly, third drive means connectable between said motor output shaft and said cutter shaft in response to the movement in one direction of a second lever mounted on said cutter housing, and brake means operable to prevent rotation of said cutter shaft in response to the move-

ment of said second lever in a direction opposite to said one direction.

4,295,327

MAGNETIC SAFETY CLUTCH FOR ROTARY LAWNMOWER


Everest J. Bortolussi, 3148 Louisiana Ave. N., Minneapolis, Minn. 55427

Filed Jun. 5, 1980, Ser. No. 156,692

Int. Cl.³ A01D 75/20

U.S. Cl. 56—11.3

4 Claims



1. A magnetic safety clutch apparatus for use with a rotary lawnmower having a main frame, a prime mover mounted on said frame, a prime mover drive shaft extending downwardly of said main frame, a rotary lawnmower blade adapted to be rotated by said drive shaft on a vertical axis, and a lawnmower operating handle mounted to a said main frame, said apparatus including:

- A. a source of electromotive force on said frame;
- B. a magnetic flux-producing coil fixedly mounted to said main frame in concentric, surrounding relation to said drive shaft;
- C. a housing of electromagnetic material encompassing said coil;
- D. a first magnetic clutch plate fixed to said drive shaft to rotate therewith and situated in close relationship to said coil housing to provide a low reluctance path between said first clutch plate and said housing;
- E. a second magnetic clutch plate mounted to rotate with said blade and freely rotatably mounted with respect to said drive shaft and movable axially of said drive shaft between an engaged, drive transmitting, position and an unengaged position with respect to said first clutch plate;
- F. means to limit axial movement of said second clutch plate to retain it within the effective magnetic field of said coil when energized;
- G. a lever action hand switch mounted to said operating handle to be readily accessible to an operator of said lawnmower, said hand switch being biased to be normally situated in an inoperative condition and being manually movable to and maintainable in an operative condition; and
- H. circuit means including said hand switch, said circuit means being operative to electrically connect said magnetic coil to said source of electromotive force when said hand switch is in its operative condition and to disconnect said coil from said source when said hand switch is in its inoperative condition.

4,295,328

HOLDING MEANS FOR GRAIN LIFTERS, SUPPORT SKIDS AND THE LIKE

Gustav Schumacher, II, Gartenstrasse 8, and Günter Schumacher, Raiffeisenstrasse 10, both of 5231 Eichelhardt, Fed. Rep. of Germany


Filed Aug. 3, 1979, Ser. No. 63,478

Claims priority, application Fed. Rep. of Germany, Aug. 12, 1978, 2835505; Jul. 17, 1979, 2928871

Int. Cl.³ A01D 55/10

U.S. Cl. 56—313

19 Claims



1. Holding apparatus for coupling a resilient, substantially flat support leg of a grain lifter, support skid or the like, to a cutter finger of the cutter mechanism of a harvester, comprising:

- clamping means for clamping one end of said support leg with respect to said cutter finger;
- a retention bracket fixed to said support leg at a location spaced from said clamping means, said retention bracket including a pair of upstanding legs, each of which extends from said support leg on a respective side of said cutter finger upwardly beyond the same; and
- locking means located vertically above said cutter finger and extending between said upstanding legs of said retention bracket so that said cutter finger is received in the space defined between said support leg, said locking means and said pair of upstanding legs of said retention bracket; whereby said support leg can be resiliently biased in a manner such that said locking means engage said cutter finger and said pair of upstanding legs of said retention bracket prevent the latter from unhooking from said cutter finger during up-and-down movement of said resilient support leg when engaging ground irregularities.

4,295,329

COBULKED CONTINUOUS FILAMENT HEATHER YARN METHOD AND PRODUCT


William T. Windley, Seaford, Del., assignor to E. I. Du Pont de Nemours and Company, Wilmington, Del.

Filed Jun. 10, 1980, Ser. No. 158,120

Int. Cl.³ D02G 1/16, 1/18, 3/24

U.S. Cl. 57—245

23 Claims



1. An improved composite cobulked continuous filament yarn containing a first oriented continuous multifilament yarn which has been bulked in a hot fluid jet process simultaneously with a second oriented continuous multifilament yarn, the

filaments of both yarns being randomly intermingled throughout the length of the composite yarn and having random three-dimensional curvilinear filament crimp with frequently alternating regions of S and Z filament twist, the filaments of said second yarn being from about 4% to about 20% longer in said composite yarn than the filaments of said first yarn, wherein the improvement comprises: the filaments of said first and second yarns being of polymers containing the same type of chemical dye site with the filaments of said second yarn having a substantially greater concentration of said dye site in equivalents per unit weight of polymer than the filaments of said first yarn, thus providing differential dyeability, and the filaments of said first yarn and of said second yarn each comprise from about 25% to about 75% of the total denier of said composite yarn.

13. In a method of producing a composite cobulked continuous filament yarn containing filaments of a first oriented continuous filament yarn and of a second oriented continuous filament yarn in which the filaments of said second yarn are longer than the filaments of said first yarn said method including the steps of (1) feeding said first yarn in an undrawn state at a controlled speed to a pair of heated draw rolls, (2) wrapping said first yarn around said draw rolls a sufficient number of times to avoid slippage thereon and said rolls being driven at surface speed at least twice the feeding speed of said first yarn thereby applying tension to and drawing to molecularly orient said first yarn, (3) also feeding to said pair of draw rolls from a yarn package at a tension of less than 1.0 grams per denier said second yarn having a lower shrinkage potential in a hot gas bulking jet than said first yarn, (4) wrapping said second yarn around said draw rolls to prevent slippage thereon, (5) bringing said first and second yarns together and forwarding the combined yarns in a high velocity stream of hot turbulent fluid in a confined space which randomly crimps and entangles the filaments thereof and thereby forms a composite cobulked yarn in which the filaments of said second yarn are from about 4% to about 20% longer than the filaments of said first yarn, (6) removing the cobulked yarn from the stream of hot fluid and cooling it at low tension while the filaments are in a crimped condition to set crimp in the filaments and (7) winding the cobulked yarn into a package under tension, the improvement for making a heather dyeable yarn comprising: feeding to said draw rolls as said second yarn a heat-relaxed yarn containing crimped filaments which filaments are differentially dyeable with respect to the filaments of said first yarn and which filaments constitute from about 25% to about 75% of the total denier of the cobulked yarn.

4,295,330

RE-ATTACHMENT DEVICE FOR AN OPEN-END TYPE SPINNING FRAME

Hermann Pfeifer, Geneva, Switzerland, assignor to Officine Savio, S.p.A., Pordenone, Italy

Filed Jun. 24, 1980, Ser. No. 162,502

Claims priority, application Switzerland, Jun. 26, 1979, 5936/79

Int. Cl.³ D01H 15/02; B65H 54/26, 67/08


U.S. Cl. 57—263

10 Claims

1. Re-attachment device for an open-end type spinning frame, comprising:

- means to lift a cop from its drive shaft, means to drive the movement of said cop in the direction in which it is unwound, a suction conduit having an inlet to remove and aspirate the end of the yarn from the periphery of said cop, a first perforated roller next to said conduit installed coaxially with an axis crosswise to the inlet end of said conduit, an outlet pipe for the yarn coming from a spinning unit, means to transfer the yarn between said cop and said outlet pipe, an organ to shear the yarn, a drive organ, said first perforated roller and a second roller connected to said drive organ, said drive organ having a reversible direction so as to introduce the yarn into a rotor through

said outlet pipe for the yarn and then to pull it back again as soon as it is re-attached;
 a third roller fitted so as to rotate near to the outlet of the aforesaid pipe;
 said second roller cooperating with said first roller positioned next to said suction conduit and associated with said drive organ;
 a portion of said suction conduit next to said first roller being installed so as to rotate around the lengthwise axis of said conduit;



a positioning organ connected to said portion of the suction conduit serving to position it between two angular positions located 180° from each other;
 said organ to shear the yarn being installed within said suction conduit; and
 a part of the suction conduit next to its rotating portion solidly fixed to said transfer means enabling movement of said first perforated roller from a first position next to the cop in one angular position of said rotating portion to a second position next to said third roller installed near the outlet of the outlet pipe of the yarn in the other angular position of said rotating portion.

4,295,331

PROCESS FOR THE PRODUCTION OF ENERGY FROM SOLID HYDROCARBON FUELS

Uriel Rekant, Kovlosky St. 22/5, Kiryat Herzog, Bnei Brak, Israel


Filed Jan. 31, 1979, Ser. No. 8,199

Claims priority, application Israel, Mar. 7, 1978, 54214

Int. Cl.³ F02B 43/08

U.S. Cl. 60—39.02

6 Claims



1. A process for the production of energy from solid hydrocarbon fuels selected from the group consisting of ground coal, shale, and peat comprising:

(a) conveying solid hydrocarbon fuel by means of a continuous conveyor through a reactor substantially filled with CO₂ and raising the temperature within said reactor to at least about 400° C. whereby in the substantial absence of air said solid hydrocarbon fuel reacts endothermically with said CO₂ to form CO;
 (b) conveying the relatively light CO and other accompany-

ing gases from the top of said reactor to a combustion chamber for exothermic reaction of the CO gas with O₂ to form CO₂ and to generate both heat and gas pressure energy;

(c) recycling at least a portion of the gases exiting from said combustion chamber to a reactor for reaction with solid hydrocarbon fuel; and

(d) collecting for further industrial processing and use the waste product of said hydrocarbon fuel reaction with CO₂ by discharging the waste product from said continuous conveyor.

4,295,332

INFRARED SUPPRESSOR SYSTEM


William Steyer, Ipswich, and Robert J. Duffy, Boxford, both of Mass., assignors to General Electric Company, Lynn, Mass.

Filed Nov. 13, 1978, Ser. No. 960,351

Int. Cl.³ F02K 3/00, 7/00

U.S. Cl. 60—264

11 Claims



1. In an apparatus for suppressing infrared radiation emitted from hot metal parts at the aft end of a gas turbine engine and from the stream of hot exhaust gases flowing therefrom during operation of the engine, the invention comprising:

duct means for receiving the stream of hot exhaust gases from said engine, said duct means adapted to generally confine said exhaust gases to flow through said duct;

first splitter means disposed within said duct means for splitting said gas stream into first and second flowing gas streams; and

second splitter means disposed within said duct means downstream of said first splitter means for splitting each of said first and second gas streams, said first and second splitter means cooperating to obstruct the line of sight viewing of said hot metal parts when said engine is viewed from the aft direction.

4,295,333

MELTING ICEBERGS TO PRODUCE FRESH WATER AND MECHANICAL ENERGY


Wayne M. Camirand, Albany; John M. Randall, El Cerrito, and Earl Hautala, Martinez, all of Calif., assignors to The United States of America as represented by the Secretary of Agriculture, Washington, D.C.

Filed Jul. 11, 1979, Ser. No. 56,652

Int. Cl.³ F03G 7/04

U.S. Cl. 60—641.6

24 Claims



1. A method of melting an iceberg to produce fresh water in

an amount greater than that available from the melting of the iceberg and mechanical energy, which comprises—

(a) evaporating warm surface seawater to produce water vapor;

(b) generating mechanical energy from said vapor;

(c) condensing said vapor by contacting it directly and intimately with cold melt water from the iceberg to produce a mixture of condensed vapor and melt water from the iceberg, said mixture having a temperature and a volume greater than the cold melt water alone;

(d) contacting the so-produced mixture with the body of the iceberg to melt the iceberg and produce cold melt water, said contact being made in such a manner as to produce turbulent flow of the cold melt water;

(e) separating a portion of the so-produced mixture and cold melt water as fresh water produce; and

(f) cycling the remainder of the so-produced mixture and cold melt water for direct and intimate contact with said vapor;

the amount of said fresh water produced being greater than the amount of cold water obtained from melting of the iceberg.

4,295,335

REGENATIVE ABSORPTION ENGINE APPARATUS AND METHOD


VerDon C. Brinkerhoff, 917 Park Row, Salt Lake City, Utah 84105

Continuation-in-part of Ser. No. 868,117, Jan. 9, 1978, abandoned. This application May 14, 1979, Ser. No. 39,035

Int. Cl.³ F01K 25/06

U.S. Cl. 60—673

11 Claims



1. A regenerative absorption engine comprising: a closed cycle system comprising a first fluid having a first, lower boiling point and a second fluid having a second, higher boiling point, said second fluid having a relatively high degree of absorptivity for the first fluid;

distillation means for separating the first fluid from the second fluid by selectively vaporizing the first fluid, the distillation means comprising a first column having a coaxial first flue in spaced relationship inside the first column and a plurality of perforated, inverted, frustoconical distributor rings mounted to the first flue, the distributor rings directing incoming third fluid into thermal contact with the first flue for more efficient heat transfer into the third fluid, the third fluid including the first fluid and the second fluid, the trays being spaced from the internal wall of the first column for the upward passage of vaporized first fluid inside the first column, the first flue directing heated combustion products upwardly through the first column;

superheater means for superheating the vaporized first fluid; mechanical expansion engine means downstream of the superheater means, the mechanical expansion engine means converting thermal energy of the first fluid into mechanical energy; and

absorption means downstream of the mechanical expansion engine means, the absorption means providing absorption of the first fluid from the mechanical expansion engine means with the second fluid while reducing backpressure in the first fluid, the absorbed first fluid in the second fluid comprising a third fluid.

4,295,336

MASTER CYLINDER ASSEMBLY WITH DETACHABLE RESERVOIR

Edward J. Falk, St. Louis, Mo., assignor to Wagner Electric Corporation, St. Louis, Mo.

Filed Feb. 5, 1980, Ser. No. 118,781

Int. Cl.³ B60T 11/20

U.S. Cl. 60—562

2 Claims

1. A master cylinder assembly comprising:

(a) a body having a bore therein and having first and second sides;

(b) primary and secondary pistons movably disposed in said bore defining primary and secondary fluid chambers, respectively, in said bore;

4,295,334

PARAMETRIC ENERGY CONVERTER


Richard N. Johnson, 14411 Quince Orchard Rd., Gaithersburg, Md. 20760

Filed Dec. 3, 1979, Ser. No. 99,368

Int. Cl.³ F01K 11/02

U.S. Cl. 60—669

10 Claims



1. A parametric energy converter, which comprises:

a housing comprising a rotary boiler having a substantially cylindrical inner and outer wall, a top wall and a bottom wall which substantially enclose the ends of said boiler, and an intermediate wall which defines and separates an upper portion and a lower portion of said boiler;


a fluid mass positioned within said housing;

means for rotating said housing about a center of rotation thereby compressing said fluid mass against said substantially cylindrical inner wall of said boiler;

means for heating said fluid mass for causing said fluid mass to move toward said center of rotation; and

means positioned at said center of rotation for extracting the resultant kinetic energy of said fluid mass.

- (c) a fluid reservoir having depending reservoir portions on one side and a depending bracket on the other side;
 (d) first and second means detachably attaching said fluid reservoir to the first and second sides, respectively, of said body so that said depending reservoir portions and said depending bracket straddle said body;



- (e) said first means comprising bosses on said depending reservoir portions, holes in said body first side, said bosses engaged in said holes; and
 (f) said second means comprising a threaded member connecting said fluid reservoir depending bracket to said body second side, said threaded member extending into said bore and acting as a stop for rearward movement of said secondary piston.

4,295,337

COOLING APPARATUS AND METHOD IN A LIQUID CRYOGEN TREATMENT PROCESS


Harry D. Johnson, Glen Allen; Christopher J. Campbell, Richmond, both of Va.; Thomas O. Turner, Midland; Carl W. Poole, Concord, both of N.C.; James E. Gilmore, and James R. Thomas, both of Mauldin, S.C., assignors to Philip Morris Incorporated, New York, N.Y.

Filed Dec. 26, 1979, Ser. No. 106,671

Int. Cl.³ F17C 13/00

U.S. Cl. 62—54

11 Claims



1. In an apparatus for processing a product by treatment with a liquid cryogen, said apparatus including a processing chamber having means for introducing and withdrawing product, a source for supplying cryogen vapor to said chamber at superatmospheric pressure, means for supplying liquid cryogen to said chamber and removing liquid cryogen therefrom and compressing means interconnected to said processing chamber for effecting withdrawal of cryogen vapor therefrom upon removal of liquid cryogen from said processing chamber and compression of such vapor, the improvement comprising: selectively operable means interconnected between said vapor source and said compressing means for supplying vapor to said compressing means; and means responsive to a predetermined pressure at said compressing means for actuating said selectively operable vapor supply means, said predetermined pressure being lower than the pressure at said vapor source.

4,295,338

CRYOGENIC PUMPING APPARATUS WITH REPLACEABLE PUMPING SURFACE ELEMENTS


Kimo M. Welch, Mountain View, Calif., assignor to Varian Associates, Inc., Palo Alto, Calif.

Filed Oct. 18, 1979, Ser. No. 86,107

Int. Cl.³ B01D 8/00

U.S. Cl. 62—55.5

11 Claims



1. In a cryogenic pumping apparatus having pumping surfaces maintained at a predetermined temperature for condensation and adsorption of gaseous species: a frame having an axially extending core portion and a plurality of fins extending radially from the core portion, a group of axially spaced generally parallel plate members extending outwardly from the core portion between adjacent ones of the fins and inclined at a predetermined angle to the axis of the core portion, a coating of cryosorbent material on one surface of each of the plate members, and removable fasteners securing the plate members to the fins.

4,295,339

CRYOSTAT SYSTEM UTILIZING A LIQUEFIED GAS

Yasuo Kuraoka, and Yasuhiro Tsuchida, both of Sapporo, Japan, assignors to Hoxan Co. Ltd., Sapporo, Japan


Filed Mar. 11, 1980, Ser. No. 129,485

Claims priority, application Japan, Mar. 14, 1979, 54-29515; May 21, 1979, 54-68174[U]; Nov. 26, 1979, 54-152604

Int. Cl.³ F25D 17/02

U.S. Cl. 62—64

1 Claim



1. A cryostat process using a liquefied gas, in which a coolant is fed from a liquefied gas source through a heat exchanger to be sprayed out from at least one spray nozzle provided in a thermostatic zone onto a material therein, comprising the steps of:
 (a) spraying said coolant in the liquid phase as a first cooling step directly onto said material so as to localize the cooling treatment of said material to a limited space, and cooling said material towards an intended cryogenic temperature;
 (b) detecting the temperature of said material as it reaches the proximity of said temperature; and
 (c) causing a temperature controller to respond to said detected temperature so as to gasify said coolant for thermostatically controlling the temperature of said material to said intended temperature.

4,295,340

REFRIGERATED DISPLAY CASE HAVING AMBIENT AIR DEFROST

Fayez F. Abraham, Niles, Mich., assignor to Tyler Refrigeration Corporation, Niles, Mich.

Continuation-in-part of Ser. No. 11,804, Feb. 14, 1979. This application Jul. 25, 1979, Ser. No. 60,459

Int. Cl.³ A47F 3/04; F25D 21/12

U.S. Cl. 62—82

22 Claims

4,295,341

WATER CHILLING PLANT

John A. Gale, Pulborough, England, assignor to A.P.V. Spiro-Gills Limited, West Sussex, England


Filed Sep. 4, 1979, Ser. No. 71,840

Claims priority, application United Kingdom, Sep. 5, 1978, 35666/78

Int. Cl.³ F25B 19/00


U.S. Cl. 62—100

9 Claims



1. An open top refrigerated display case being selectively operative in a refrigeration cycle and a defrost cycle, said case comprising: a bottom wall and four side walls; a single air conduit extending along a first of said side walls, along said bottom wall and a second of said side walls, said first and second side walls being opposing side walls, said air conduit having first and second openings at its opposite ends and each of said openings being located near the top portion of the respective said side wall; means for refrigerating air moving through said conduit during a refrigeration cycle, said means for refrigerating being arranged within said air conduit, air circulating means arranged within said air conduit, said air circulating means circulating within said air conduit in a forward direction during a refrigeration cycle and circulating air in a reverse direction during a defrost cycle, and said air circulating means drawing in ambient air from outside of said display case through said first opening when said air circulating means circulates air within said air conduit in the reverse direction; means for switching operation of said display case between a refrigeration cycle and a defrost cycle and correspondingly causing said air circulating means to change the direction of circulation of air within said air conduit; and means for directing air leaving said air conduit upwardly and over the outside of the adjacent said side wall so as to flow away from said case when such air is flowing in said reverse direction so that such air is prevented from reentering said air conduit.

14. A method for selectively operating an open top refrigerated display case in a refrigeration cycle and a defrost cycle, where the case includes: a bottom wall and side walls, an air conduit extending along a first of the side walls, along the bottom wall and a second of the side walls, the air conduit having first and second openings at its opposite ends and each of the openings being located near the top portion of the respective side wall; the method comprising the steps of: refrigerated air moving through the air conduit during a refrigeration cycle; circulating air within the air conduit in a forward direction during a refrigeration cycle; circulating air in a reverse direction during a defrost cycle; drawing in ambient air from outside of said display case through the first opening when air is circulated within the air conduit in the reverse direction; switching the operation of the display case between a refrigeration cycle and a defrost cycle; and directing air leaving the air conduit upwardly and over the outside of the adjacent side wall so as to flow away from the case when such air is flowing in the reverse direction.



1. In a method of chilling water in a vacuum chilling plant having at least two chilling states wherein the vapour from each chilling state is condensed in a multi stage air-cooled heat exchanger, having an air inlet and an air outlet the improvement comprising:

- feeding the vapour to the heat exchanger in at least two separate flows at different states of compression and temperature whereby the cooler air near the air inlet condenses vapour at a lower temperature and the warmer air nearer the air outlet condenses vapour at a higher temperature.

4,295,342

HEAT EXCHANGE METHOD USING NATURAL FLOW OF HEAT EXCHANGE MEDIUM


James Parro, R.D. 2, Sadler Rd., Skaneateles, N.Y. 13152

Continuation-in-part of Ser. No. 845,896, Oct. 27, 1977, abandoned. This application Jul. 10, 1979, Ser. No. 56,419

Int. Cl.³ F25D 15/00; F28D 15/00

U.S. Cl. 62—119

9 Claims



1. A method of reducing energy losses in heating and cooling an enclosed room while ventilating said room with outside air at a temperature below that of said room during heating cycles and above that of said room during cooling cycles by reversible heat exchange between room air and outside air, comprising:

- (a) providing a pair of continuous heat exchange coils each having an upper and a lower end and a plurality of substantially horizontal portions therebetween;
 (b) placing the upper ends of said coils at a vertical level substantially higher than the lower ends of each coil;
 (c) connecting said upper ends for direct communication

therebetween and connecting said lower ends for direct communication therebetween;

(d) charging said coils with a heat exchange liquid to a level substantially above the lower ends and below the upper ends of both of said coils; and

(e) contacting one of said coils with room air and the other with outside air, whereby refrigerant is evaporated from said one coil when room air is warmer than outside air, and vice versa, thereby increasing the pressure in the coil from which refrigerant is evaporated and causing refrigerant to flow to the other coil giving up heat to the air at the lowest temperature.

4,295,343

MICROBE-REMOVING AND AIR-CONDITIONING APPARATUS


Masahiko Izumi, 8-26-ban, 5-chome, Hiikawa, Nishi-ku, Fukuoka-shi, Fukuoka-ken, Japan

Filed Jul. 20, 1979, Ser. No. 59,184

Int. Cl.³ F25D 17/04

U.S. Cl. 62—309

2 Claims



1. A microbe-removing and air-conditioning apparatus comprising
 - a room;
 - a water-spraying cyclone, in which a return pipe is surrounded with a water pipe which has a plurality of spraying nozzles, said water-spraying cyclone comprising means through which the air in said room is circulated and in which water is sprayed and odor, fine dust and microbes are caused to adhere to the wall of the cyclone and removed, and the air is caused to become saturated with moisture;
 - a temperature-regulating cyclone in which a temperature-regulating medium conduit is spirally arranged within said cyclone, said temperature-regulating cyclone comprising means to remove water droplets from the humid air pressing from said water-spraying cyclone and means to regulate the temperature of the air; and
 - a circulation pipe for feeding the air leaving the room to the water-spraying cyclone and from the water-spraying cyclone to the temperature-regulating cyclone and then back to the room therefrom; wherein upstream the water-spraying cyclone there is provided a sterilization cyclone where a high temperature vapour is introduced and mixed with the air coming from the room to effect sterilization.

4,295,344

REFRIGERATION UNIT WITH WATER

William J. Hannett, Jamesville; Thomas E. Brendel, and David S. Wilson, both of Fayetteville, all of N.Y., assignors to Carrier Corporation, Syracuse, N.Y.

Filed Nov. 8, 1979, Ser. No. 92,297

Int. Cl.³ F25B 13/00, 27/02

U.S. Cl. 62—324.5

4 Claims


1. An engine-driven refrigeration unit including a first heat exchanger functioning as a condenser in a first operating mode

and as an evaporator in a second operating mode of said refrigeration unit comprising:

means for delivering water from a source thereof to said first heat exchanger for condensing refrigerant vapor delivered thereto when said heat exchanger is functioning as a condenser, and for vaporizing refrigerant when the heat exchanger is functioning as an evaporator;

a second heat exchanger connected to a source of relatively warm fluid;

a conduit connected to said first heat exchanger for deliver-



ing said water to said second heat exchanger to pass in heat transfer relation with said relatively warm fluid to increase the temperature of said water;

discharge means connected to said second heat exchanger including valve means having a first position for directing the water from said second heat exchanger to the source thereof and a second position for directing the water to the inlet of said first heat exchanger; and

means for placing said valve means in said second position when said first heat exchanger is functioning as a refrigerant evaporator.

4,295,345

COOLING CONTAINER FOR CANNED BEVERAGES


Lyle H. Atkinson, 3828 Pavant Dr., Salt Lake City, Utah 84120

Filed Apr. 21, 1980, Ser. No. 142,384

Int. Cl.³ F25D 3/08

U.S. Cl. 62—371

7 Claims



1. A portable cooling container for transporting and cooling canned beverages, comprising in combination:
 - a curved bottom housing having a plurality of vertically oriented compartments for holding canned beverages, said housing having walls of insulating material which entirely surround each of said compartments;
 - a correspondingly curved top housing having walls of insulating material and having a plurality of recessed cavities therein corresponding to said vertically oriented compartments in said bottom housing;
 - a slow-thawing cooling gel disposed in the upper ends of each respective recessed cavity;
 - sealing means for sealing the interface between said top housing and said bottom housing; and

means for attaching said bottom housing to said top housing.

4,295,346

RECIRCULATING VAPOR SYSTEM FOR GELLING CRYOGENIC LIQUIDS


Lawrence C. Hoffman, Fair Oaks, Calif., assignor to Aerojet-General Corporation, La Jolla, Calif.

Filed Sep. 8, 1980, Ser. No. 185,349

Int. Cl.³ F25B 1/06

U.S. Cl. 62—500

3 Claims



1. A system for gelling cryogenic liquid comprising:
 - means for providing a spray of cryogenic liquid droplets;
 - a vessel for receiving said cryogenic spray;
 - a jet pump for introducing a gelant into said cryogenic spray disposed to also educt cryogenic vapor from said vessel; and
 - means for providing a flow of gelant fluid to said jet pump to thereby drive said pump.

4,295,347

SIMULATED GEM

James Visconti, 55 W. 28th St., New York, N.Y. 10001

Filed May 25, 1978, Ser. No. 909,347

Int. Cl.³ A44C 17/00

U.S. Cl. 63—32

3 Claims



1. A simulated gem of lacquer and plastic comprising a plastic core and a lacquer coating, said lacquer covering at least the entire outer surface of said core, said lacquer coating including a plurality of hues, said lacquer of said coating when in liquid state having a solvent adapted to superficially interfuse with the surface of said plastic core, said plastic core having a least the periphery of its underside on a single plane and substantially no upper surface concavities, and in the shape of a cabochon said lacquer coating marbled and interfused with the surface of said plastic core when in solid state, whereby the illusion of a solid unitary gem is created.

4,295,348

PROGRESSIVE TORQUE TRANSMISSION IN LEAF-SPRING COUPLING

Friedrich Helfer, Königsbrunn-Zang; Ernst Elsner, Herbrechtingen, and Wolfgang Zaiser, Steinheim, all of Fed. Rep. of Germany, assignors to Voith Getriebe KG., Fed. Rep. of Germany


Filed Aug. 24, 1979, Ser. No. 69,373

Claims priority, application Fed. Rep. of Germany, Jan. 19, 1979, 2901933

Int. Cl.³ F16D 3/56

U.S. Cl. 64—27 L

29 Claims



1. A leaf-spring coupling comprising:
 - a first coupling part and a second coupling part spaced from said first coupling part;
 - a plurality of leaf-spring assemblies extending between and coupling said first and said second coupling parts in an elastic manner; each said leaf-spring assembly comprising a plurality of leaf-springs oriented to extend between said first and said second coupling parts, and said leaf-springs of each said assembly being of different lengths, including a longer principal spring and a plurality of flank springs arrayed next to at least one side of said principal spring, wherein the lengths of said flank springs decrease stepwise from spring to spring away from said one side of said principal spring;
 - said leaf-spring assemblies being clamped to said first clamping part;
 - said second coupling part including respective stop means for each said assembly which are spaced from said flank springs of that said assembly and are so located with respect to said flank springs that upon relative motion of said first and said second coupling parts in a direction laterally of said leaf-springs, said principal spring engaging said second coupling part and being stressed and flexed by such engagement in a direction away from said flank springs at said one side of said principal springs and said stop means also engaging at least a part of at least some of said flank springs also at said one side, thereby increasing the number of said leaf-springs in a said assembly which are stressed.

4,295,349

DOOR LOCK

Georg Wasserfaller, Gratschach, A 9523 Post Landskron, Austria

Filed Jan. 15, 1979, Ser. No. 3,465


Int. Cl.³ E05B 59/00

U.S. Cl. 70—111

3 Claims

1. A door lock comprising
 - (a) a latch reciprocal between an open and a locking position, the latch being biased into the locking position,
 - (b) a pivotal element having at least one arm engageable with the latch to withdraw it to the open position,
 - (c) a locking bolt depressable to move into a blocking position to prevent swivelling of the pivotal element to withdraw said latch,
 - (d) a key-operable unlocking lever for moving the locking

bolt out of the blocking position to permit swivelling of said pivotal element, the unlocking lever having a catch operable by the key, and



(e) a key-bolt key-operable for reciprocation between an open and locked position, the unlocking lever being pivotally mounted on the key-bolt.

4,295,350


KEYHOLE SIGHTER

Kim D. Grinage, 636 Eire St., South Haven, Mich. 49090
Filed Jan. 18, 1980, Ser. No. 113,013

Int. Cl.³ E05B 15/08

U.S. Cl. 70—454

8 Claims



1. A keyhole sighting device for mounting on a key receiving member at a keyhole in said member, comprising:

a shell having a rearwardly facing base surface for opposing the front surface of said key receiving member, said shell projecting forwardly from said base surface, said shell having a substantially funnel-like interior cavity, said cavity being wide open at the front of said shell and converging rearwardly to a key receiving opening of substantially less diameter through said base surface, said shell having a night visible material along the surface of said funnel-like cavity;

an annular skirt of elastomeric material extending rearward from said base surface for snug telescoping over the key receiving member, said annular skirt having a generally radially inwardly offset annular edge portion at the rear end thereof and circumferentially stretchable to fit over and grip the rear portion of the key receiving member for holding the device on the key receiving member with said key receiving member snugly closed within said skirt, the entire device being an annular one-piece member of said elastomeric material defining said shell and skirt, said member having a substantially cylindrical peripheral surface continuing from the front end of said shell substantially to the rear end of said skirt.

4,295,351 SELF-TAPPING STAINLESS STEEL SCREW AND METHOD FOR PRODUCING SAME


Lowell L. Bjorklund, Elgin, Ill.; Ramon A. Berg, Hales Corners, Wis., and Henry A. Sygnator, Arlington Heights, Ill., assignors to Illinois Tool Works Inc., Chicago, Ill.

Filed Jan. 8, 1979, Ser. No. 1,975

Int. Cl.³ B21H 3/06; B21K 1/56

U.S. Cl. 72—38

5 Claims



1. A process for producing a threaded, self-tapping screw with a thread hardness in the range of RC 45-50 while its core retains a hardness in the area of RC 30, said screw being made from an austenitic 300 series nickel-chromium stainless steel material said method including the steps of forming a headed blank with a shank portion from said 300 series material, chilling at least the shank portion of the thus formed austenitic blank to a temperature substantially below 0° F., rolling the blank between thread-rolling dies forming threads on said shank portion while the blanks are in the chilled condition, said thread-rolling step causing sufficient localized transformation of the material in the region of the threads to martensite to produce the RC 45-50 hardness without substantial effect on a central core portion of said threaded shank.

4,295,352

DIE FOR THE FORMATION OF SEMI-CLOSED CHANNELS OR OTHER COMPLEX CONFIGURATIONS

Richard P. Stokes, and William Stokes, both of Carteret, N.J., assignors to Unlimited Steel Fabricators, Inc., Middlesex, N.J.

Filed Oct. 12, 1979, Ser. No. 84,179

Int. Cl.³ B21D 22/10


U.S. Cl. 72—57

8 Claims

1. In a die for the formation of semi-closed channels or other complex configurations in workpieces which includes relatively movable male and female die members and wherein said male die member includes a mandrel, the improvements comprising, an elastically deformable matrix included in said female die member, said matrix having a surface comprising a generally open forming groove formed therein and configured to receive said mandrel whereby, a workpiece may be disposed between said male and female die members and the same relatively moved to drive said mandrel and the relevant portion of said workpiece into said forming groove to deform said matrix and substantially close said forming groove around said mandrel to essential wrap said workpiece portion around said mandrel and form said configuration therein, whereupon said male and female die members may be relatively moved to remove said mandrel from said forming groove with attendant return of the matrix to its undeformed condition and re-opening of said forming groove to enable removal of said work-

piece portion therefrom, said matrix being generally wedge-shaped, and said forming groove being formed in the wider

longitudinal deformations on said sheet metal of generally any length without the need to change said forming rolls.



4,295,353 MILL STAND FOR FORMING DISCONTINUOUS LONGITUDINAL DEFORMATIONS IN SHEET METAL


Vyacheslav I. Anisimov, ulitsa Metallurgov, 11, kv. 16, Magnitogorsk; Evgeny G. Bulgakov, ulitsa Vrachbnaya, 23, kv. 37; Vasily N. Gurin, ulitsa Lyapidevskogo, 16, both of Kramatorsk; Leonid V. Radjuevich, ulitsa 23 Avgusta, 47, kv. 42; Igor S. Trishevsky, ulitsa Dzerzhinskogo, 34, kv. 7, both of Kharkov; Oleg I. Trishevsky, ulitsa Lunacharskogo 8, kv. 20, Kramatorsk; Grigory R. Kheifets, ulitsa Bairona, 154a, kv. 114, Kharkov, and Anatoly B. Jurchenko, ulitsa Tukhachevskogo, 22, korpus 2, kv. 253, Moscow, all of U.S.S.R.

Filed Sep. 24, 1979, Ser. No. 78,238

Int. Cl.³ B21D 13/04

U.S. Cl. 72—180

5 Claims



1. A mill stand for forming discontinuous longitudinal deformations on continuous sheet metal uninterruptedly fed to said mill stand, comprising:

a frame member;
forming rolls, having congruent circumferential forming elements, mounted on said frame member in such a way that one of the forming rolls is adapted for movement toward and away from said other forming rolls;
a power cylinder being connected with said forming roll adapted for movement;
a system for feeding a working medium to said power cylinder including means for controlling said power cylinder; and
a master device operatively connected with one of said forming rolls and interacting with said means for controlling said power cylinder for periodically bringing together said forming rolls, thereby discontinuously forming

4,295,354

METHOD FOR PRODUCING BEAM BLANK FOR LARGE SIZE H-BEAM FROM FLAT SLAB

Koichi Itoh, Ichikawa; Osamu Koshida, and Katsuichi Nakayama, both of Ibaraki, all of Japan, assignors to Sumitomo Metal Industries, Ltd., Osaka, Japan


Filed Aug. 29, 1979, Ser. No. 70,831

Claims priority, application Japan, May 8, 1979, 54/56073

Int. Cl.³ B21B 1/12

U.S. Cl. 72—225

3 Claims



1. A method for producing a beam blank for a large size H-beam from a flat slab, comprising the steps of:

positioning a large size flat slab with the width dimension vertical and rolling the vertically spaced edges a plurality of times in a two-high rolling mill to form a preformed beam blank, the shaping rolls of the two-high rolling mill having a roll profile with a groove-shaped recess therein having a depth b a width c at the bottom thereof and width d at the opening thereof, with dimensions of:

$$t \leq c \leq 1.2t$$

$$d = M + M'$$

$$b = f + f'$$

t is the thickness of the flat slab

M is the width of the flange of the beam blank to be formed

M' is a dimension of from 15 to 35 mm

f is the thickness of the flange of the beam blank to be formed; and

f' is a dimension from 20 to 40 mm; and

positioning said preformed beam blank with the width dimension thereof horizontal and further rolling the preformed blank by plurality of passes through a universal roughing mill into a beam blank of the desired shape, the rolling in the earlier passes through the universal roughing mill being with the rolls of the roughing mill positioned for making the reduction of the preformed beam blank by the horizontal rolls greater than the reduction by the vertical rolls thereof and the rolling in the later passes being with the rolls of said roughing mill positioned for making the reduction of the preformed beam blank by the horizontal rolls less than the reduction by the vertical rolls thereof.

4,295,355

BEAM-BACKED STRIP MILL WITH ATTACHED INSERTS

Tadeusz Sendzimir, P.O. Box 1350, Waterbury, Conn. 06720
Filed Aug. 13, 1979, Ser. No. 66,019


Int. Cl.³ B21B 13/14

U.S. Cl. 72—242

13 Claims

1. In a multi-roll mill for rolling wide strips, a one-piece mill housing having a rigid beam facing each side of the strip, each beam having on its pressure side an arcuate section machined around the roll bite as an axis, an insert snugly seated in each of said arcuate sections, each of said inserts having arcuate channels machined on its inner surface parallel to said axis, roll-backing elements seated in said channels, each of said inserts being interchangeable in order to change the roll configuration

of the mill, each of said inserts being axially divided into segments, each segment having at least one of said channels



therein, each segment being individually fastened to its respective one of said arcuate beam sections by means operable from the front side of said mill for withdrawal and replacement.

4,295,356


ROLLER ENTRY GUIDES FOR ROD MILLS

Mario Fabris, 8 Roberts Rd., Grimsby, Ontario, Canada (L3M 3X2)

Filed Oct. 1, 1979, Ser. No. 80,820
Int. Cl.³ B21B 39/16

U.S. Cl. 72—250

4 Claims



1. A roller entry guide for a rod mill comprising:
 - a body providing a rod passage therein through which the rod passes;
 - a pair of longitudinally extending rocker arm members mounted by the body on opposite sides of the rod passage for pivoting rocking movement about respective parallel pivot axes;
 - a pair of guide roller members each mounted by the respective rocker arm member for rotation about a respective rotation axis, the pivoting rocking movement of the arm members permitting movement of the guide roller members toward and away from one another;
 - each guide roller member having, in a peripheral portion, a ring of fluid reaction members coaxial with its axis of rotation;
 - nozzle means carried by each arm member external thereto and communicating with the passage means and disposed to direct a stream of fluid at the said ring of fluid reaction members substantially tangentially thereto to rotate the respective guide roller member about its axis of rotation; and
 - means for feeding fluid to the said nozzle means through said passage means whereby the guide roller members can be rotated at about their operative speeds prior to engagement by a rod passing through the device.

4,295,357

APPARATUS FOR MAKING METAL OUTERS AND INNERS


Ralph E. Roper, Indianapolis, Ind., assignor to General Tire & Rubber Co.

Continuation of Ser. No. 937,278, Aug. 28, 1978, Pat. No. 4,238,949, and a continuation-in-part of Ser. No. 691,720, Jun. 1, 1976, abandoned, which is a continuation-in-part of Ser. No. 622,269, Oct. 14, 1975. This application May 19, 1980, Ser. No. 150,776

Int. Cl.³ B21D 45/00

U.S. Cl. 72—344

13 Claims



1. Apparatus for forming an annular sheet metal blank into an annular member of precise tolerances which comprises:
 - (a) an external die having a continuous die surface of the configuration desired for the external surface of said annular member, at least one portion of said continuous die surface being of smaller diameter than said annular metal blank so as to be capable of shrinking said blank to said smaller diameter when said blank is forced through said die, and said die having an annular ridge surrounding the inside of the die for seating one end of said annular metal blank,
 - (b) a first punch mounted with relation to said external die for the reciprocal travel through a path into and out of an endmost position within said external die, said first punch having a reduced diameter portion shaped and proportioned to fit inside said annular metal blank and having an enlarged diameter portion that engages said blank so as to force said blank through said external die when said punch travels toward said endmost position, said reduced diameter portion being spaced away from the portion of said annular metal blank that is reduced to a smaller diameter by the continuous die surface of said external die so as to allow the free inward movement of the internal surface of said annular metal blank when said external die reduces the diameter of the blank, said reduced diameter portion also having means for holding said blank on said punch when said reduced diameter portion and blank are located outside of said external die, and
 - (c) means for reciprocating said first punch axially through said path into and out of said endmost position in said external die.

4,295,358

HYDRAULIC PRESS

J. Stewart Bulmer, 755 Fernhill Blvd., Oshawa, Ontario, Canada (L1J 5K2)


Filed Oct. 16, 1979, Ser. No. 85,241
Int. Cl.³ B21J 9/12

U.S. Cl. 72—453.06

7 Claims

1. A hydraulic trim press comprising a horizontal rectangular bed; four tie rods extending vertically upwardly from each corner of said bed; a movable rectangular platen parallel to said bed and slidably mounted on said tie rods to move towards

and away from said bed; a stationary rectangular platen parallel to said bed and connected to the end of said tie rods distal from said bed; two spaced apart hydraulic cylinders secured to said stationary platen and extending vertically downward, said cylinders located between the end tie rods with piston rods



extending outwardly from each of said cylinders and connected to said movable platen, a hydraulic tank for storage of hydraulic fluid attached to the underside of said stationary platen, a means for driving said cylinders, a manifold secured on top of said stationary platen to direct hydraulic fluid to the control valves and cylinders.

4,295,359


CALIBRATION APPARATUS FOR CML CIRCUIT TEST UNIT

Dennis C. Hilker, Cave Creek, Ariz., assignor to Honeywell Information Systems Inc., Phoenix, Ariz.

Filed Mar. 17, 1980, Ser. No. 131,294
Int. Cl.³ G04F 7/00; G01R 31/02

U.S. Cl. 73—5

8 Claims



1. Apparatus for calibrating CML integrated circuit test unit comprising:
 - a. fixture capable of receiving a CML integrated circuit therein and including a plurality of pins, each pin capable of contact with one pad of said circuit when said circuit is mounted on said fixture;
 - b. a pulse generator producing a shaped pulse upon actuation;
 - c. a power splitter connected to receive said shaped pulse for transferring said shaped pulse to outputs thereof;
 - d. a matrix of electrically actuated relays connected to one output of said power splitter and to each pin of said fixture, said matrix adapted to connect said shaped pulse to a

- e. a controller connected to said relays for providing a switching signal to each relay of said matrix, said test unit connected to another output of said power splitter and waveforms from said waveform output; and
- f. a shorting device selectively connectable between said predetermined pin and said preselected pin.

4,295,360


TENSION MEASURING APPARATUS

Frank S. Fountain, Wilmington, Del., assignor to E. I. Du Pont de Nemours and Company, Wilmington, Del.

Filed Jan. 14, 1980, Ser. No. 111,665
Int. Cl.³ G01N 25/00, 33/36

U.S. Cl. 73—15.6

2 Claims



1. In an apparatus for measuring yarn tension while the yarn is being drawn that includes means for feeding the yarn from a source through a heater to a drawing means, a yarn direction-changing tension-measuring device located between the feed means and the heater comprising: a shaft having a plug attached to one end and a direction-changing guide mounted at its other end around which yarn passes, said shaft being of rectangular cross section with wide flat surfaces several times greater than its narrower surfaces to allow for flexure in response to forces generated during change of yarn direction about said guide, a strain transducer connected to opposite wide flat surfaces of said shaft and means for mounting said plug for limited rotation to detect only forces perpendicular to said wide flat surfaces.

4,295,361

DRILL PIPE TESTER WITH AUTOMATIC FILL-UP

Michael E. McMahan, Duncan, Okla., assignor to Halliburton Company, Duncan, Okla.


Filed Apr. 3, 1980, Ser. No. 136,830
Int. Cl.³ G01M 3/08

U.S. Cl. 73—40.5 R

19 Claims

1. A pipe tester valve, comprising:
 - spherical closure valve means having a valve bore there-through and being rotatable between an open and a closed position for opening and closing an interior of a string of pipe; and
 - automatic means for automatically closing said spherical closure valve means when said string of pipe is statically positioned within a well so that said string of pipe may be pressure tested, and for automatically opening said spherical closure valve means and allowing well fluid within said well to fill said string of pipe above said closure valve

means as said string of pipe and closure valve means are lowered into said well, said spherical closure valve means



being rotatable to its said open position when said string of pipe is finally positioned within said well.

4,295,362

PENTAERYTHRITOL IN DRY DEVELOPERS

Michael L. White, Lake in the Hills, Ill., assignor to Magnaflux Corporation, Chicago, Ill.

Filed Feb. 22, 1980, Ser. No. 123,683

Int. Cl.³ C09K 3/00; G01N 19/08, 33/00

U.S. Cl. 73—104

14 Claims

1. In the method of non-destructive testing for surface flaws in which a liquid penetrant is applied to the test surface, excess penetrant is removed while leaving penetrant entrapped in surface flaws and a dry developer powder is applied over the test surface to aid in drawing the entrapped penetrant to the surface and thereby render the location of said flaws visible, the improvement which comprises:

employing as said developer powder a dry composition including at least 35% by weight pentaerythritol powder at least 90% of said powder being less than 20 microns in diameter.

9. A dry developer composition for use in the penetrant inspection method for locating surface flaws in a workpiece, said developer consisting essentially of a mixture of at least 35% by weight pentaerythritol having a particle size such that at least 90% of the particles are less than 20 microns in dimension and a finely divided inert powder with a bulk density lower than pentaerythritol.

4,295,363

APPARATUS FOR DIAGNOSING FAULTS IN INDIVIDUAL CYLINDERS IN AN INTERNAL COMBUSTION ENGINE

Gordon K. Buck, Greenlawn, and Cynthia H. Kozin, Huntington, both of N.Y., assignors to Harris Corporation, Cleveland, Ohio

Filed Mar. 25, 1977, Ser. No. 781,313

Int. Cl.³ G01M 15/00

U.S. Cl. 73—117.3


19 Claims

1. Apparatus for determining malfunctions of individual cylinders of an internal combustion engine, comprising:

means for measuring the values of the time intervals between successive crankshaft positions as the crankshaft of a said engine rotates through at least one engine cycle, wherein one engine cycle includes a number of power periods corresponding with the number of cylinders of the engine being tested and wherein each power period includes a plurality of said crankshaft positions;

first means for comparing for each power period the values of selected said time intervals associated with selected said

crankshaft positions in the associated power period and providing for each cylinder a first indication having a value in accordance therewith; and,



second means for comparing each said first indication with said other first indications and providing for each cylinder a second indication having a value in accordance with the ratio of the value of said first indication for that cylinder to the average value of at least two of said first indications.

4,295,364

TRANSDUCER DEVICE FOR MONITORING OF FUEL INJECTION


Joseph L. Dooley, Chicago, and Daniel J. Dooley, Burr Ridge, both of Ill., assignors to Creative Tool Company, Burr Ridge, Ill.

Filed Sep. 7, 1979, Ser. No. 73,251

Int. Cl.³ G01M 19/00

U.S. Cl. 73—119 A

7 Claims



7. A method for monitoring the injection of fuel into a fuel line of a fuel injection system from an injection pump assembly including a delivery valve assembly of the type wherein the fuel is forced past a spring-valve element into a delivery chamber which has a cross-sectional area substantially larger than that of an outlet passage therefrom, said delivery valve assembly including a thick-walled section having a polygonal shape with a plurality of flat surfaces for facilitating installation of said delivery valve assembly, said method comprising: providing a transducer including a piezoelectric plate element and clamping said plate element against one of said flat surfaces to produce a short-duration electrical output pulse in response to each injection operation of said pump assembly, and monitoring electrical output pulses developed by said transducer means.

4,295,365

NMR ANALYSIS OF SUBTERRANEAN RESERVOIR SAMPLES IMMERSSED IN LIQUID HALOCARBONS

Indurani D. Meshri, Tulsa, Okla., assignor to Standard Oil Company (Indiana), Chicago, Ill.

Filed Feb. 26, 1979, Ser. No. 15,267

Int. Cl.³ E21B 49/02

U.S. Cl. 73—153

5 Claims

1. In a method of analyzing a sample of a subterranean reservoir with a nuclear magnetic resonance means, wherein said sample is saturated with an aqueous liquid and thereafter analyzed with said nuclear magnetic resonance means, wherein the improvement comprises:

immediately after saturating said sample, immersing it in a liquid halocarbon having no hydrogen atoms bound thereto and analyzing said sample immersed in said liquid halocarbon.

4,295,366

DRILLING FLUID CIRCULATING AND MONITORING SYSTEM AND METHOD


Joseph T. Gibson, and Gerald L. Duhon, both of New Iberia, La., assignors to A. C. Company, New Iberia, La.

Filed May 29, 1979, Ser. No. 42,969

Int. Cl.³ E21B 47/04

U.S. Cl. 73—155

15 Claims



1. A drilling fluid circulating system, comprising: tank means for storing a quantity of drilling fluid used in a well; means mounted in fluid communication with said tank means for pumping the stored drilling fluid into the well; a drilling fluid return line mounted in fluid communication with the well for transporting drilling fluid from said well to said tank means, said drilling fluid return line including a section thereof having an interior of parallelogram cross-section; flow sensing means mounted with said drilling fluid return line for providing an electrical output proportionate to the level of the drilling fluid flowing through the parallelogram cross-section; and means mounted with said flow sensing means for receiving the electrical output therefrom to indicate the volume of drilling fluid flowing into said tank.

4,295,367

SPEED INDICATING DEVICE

Wayne B. Leslie, 12347 E. Bates Cir., Aurora, Colo. 80014

Filed Jan. 21, 1980, Ser. No. 113,622

Int. Cl.³ G01C 21/10

U.S. Cl. 73—184

20 Claims


1. A speed indicating device for a boat and like craft moving in a body of water comprising:

a plate with speed indicia for indicating the speed of the boat and having a first pivot joint portion at the front of said plate;

a mounting arm that extends laterally out from a side of the boat having a second pivot joint portion operatively associated with said first pivot joint portion for supporting

said plate for pivotal movement about a generally vertical pivot to permit the plate to aline with the course of travel of the boat; and

a combination pointing arm, flexible line, and weight supported at a rear bottom portion of said plate, said pointing arm being pivotally mounted intermediate its ends to pivot relative to said plate about a generally horizontal pivot at the rear of the plate with a pointing end moving along said speed indicia to indicate speed,



said line being connected to the lower end of said pointing arm and said weight being connected to the lower end of said line, said weight being adapted to move through a body of water while suspended from said pointing arm whereby to pivot said pointing arm about said generally horizontal pivot in relation to the speed of the boat, said plate also being moved about said generally vertical pivot to seek out a direction to aline the plate with the course of travel of the boat as said weight is dragged via the body of water.

4,295,368

METHOD FOR MEASURING THE FULL RANGE IN QUALITY OF A VAPOR


Joseph Jannone, 133-48 84th St., Ozone Park, New York, N.Y. 11417

Filed Aug. 22, 1979, Ser. No. 68,686

Int. Cl.³ G01K 17/00

U.S. Cl. 73—192

1 Claim



1. A method for determining the quality of a fluid vapor comprising the steps of (1) providing a source of fluid vapor, (2) directing a portion of said fluid vapor through an open insulated sampling chamber at substantially the same pressure and temperature as the fluid vapor in said source, (3) sealing said chamber to seal a representative portion of fluid vapor therein, (4) applying heat to said representative portion of fluid vapor to change the state of said representative portion of fluid

vapor to a superheated or liquid condition, (5) cooling said representative portion of fluid vapor to establish a cooling mode for said superheated vapor or liquid wherein the temperatures and pressures during said cooling mode are recorded, (6) utilizing the temperature and pressure readings during said cooling mode while in the superheated state to determine the specific volume of the fluid vapor source; and (7) thereafter determining the quality of said fluid vapor source by the following equation:

$$V_a = V_b = V_f + X(V_g - V_f)$$

wherein

V_a and V_b individually is the specific volume of the representative portion;

V_g is the dry saturated specific volume of the fluid vapor source;

V_f is the wet saturated specific volume of the fluid vapor source; and

X is the quality of the fluid vapor source.

4,295,369

DUAL MAGNETIC DRIVE FOR GEAR METERS


Fred E. Wendelboe, Erie, Pa., assignor to Geosource Inc., Houston, Tex.

Filed Apr. 10, 1980, Ser. No. 138,985

Int. Cl.³ G01F 3/08

U.S. Cl. 73-261

23 Claims



1. A gear meter, comprising:

a casing having a chamber, the casing having a fluid inlet and a fluid outlet communicating with the chamber;
a pair of fixed hollow shafts extending through the chamber;
a measuring gear rotatably mounted on each of the fixed shafts within the chamber so as to continuously engage one another and so as each measuring gear is in continuous dynamic sealing arrangement with the chamber walls;
a driver magnet arranged in each measuring gear; and
a drive transmission for operably connecting the measuring gears to a meter accessory wherein the drive transmission comprises:
rotatable shafts arranged inside the fixed, hollow shafts and extending beyond the measuring chamber;
driven magnets fixed to the rotatable shafts such that the rotation of the measuring gears and driver magnets urges the rotation of the driven magnets and rotatable shafts; and
a coupling gear mounted to each of the rotatable shafts outside the measuring chamber, said coupling gears being adapted for connection to a meter accessory.

4,295,370

CAPACITIVE SCHEME FOR MEASURING THE LEVEL OF A LIQUID


Robert G. Bristol, Everett, Mass., assignor to Emhart Industries, Inc., Indianapolis, Ind.

Continuation of Ser. No. 19,653, Mar. 12, 1979, abandoned. This application Jul. 17, 1980, Ser. No. 169,819

Int. Cl.³ G01F 23/26

U.S. Cl. 73-304 C

1 Claim



1. Apparatus for measuring the level of a liquid comprising:
a generally cylindrical receptacle for receiving said liquid, said receptacle having a generally concentric cylindrical portion extending substantially therethrough and being made of dielectric material;
a plurality of electrodes located within said cylindrical portion and against said dielectric material, each of said electrodes being situated at a different vertical level for said liquid in said receptacle;
a drive electrode means located within said cylindrical portion for capacitively coupling an electrical signal to said plurality of electrodes;
a layer of insulation mounted between said drive electrode means and each of said electrodes of said plurality of electrodes for forming signal transmitting capacitance therebetween;
an electrical supply means connected to said drive electrode means for supplying said electrical signal thereto;
means for capacitively shunting said electrical signal through said dielectric portion of said receptacle and any liquid in said receptacle and away from said plurality of electrodes, the amount of signal shunted being dependent upon the amount of said liquid in said receptacle;
detection electrode means mounted adjacent said plurality of electrodes and separated therefrom by said layer of insulation for capacitively receiving said electrical signal from said plurality of electrodes; and
a single measuring circuit means connected to said detection electrode means for measuring the amount of signal transmitted to said circuit means from all of said plurality of electrodes, said amount of signal transmitted to said circuit means being responsive to said amount of signal shunted by said means for capacitively shunting and thereby being responsive to the amount of said liquid in said receptacle, said measuring circuit means thereby being adapted for measuring the amount of said liquid in said receptacle.

4,295,371

TEMPERATURE DETECTING DEVICE

Hiroshi Sawa, Yokohama, Japan, assignor to Hochiki Corporation, Tokyo, Japan


Filed Apr. 11, 1980, Ser. No. 139,524

Claims priority, application Japan, Jun. 22, 1979, 54-85583[U]

Int. Cl.³ G01K 7/00

U.S. Cl. 73-359 A

9 Claims



1. A temperature detecting device comprising: casing means, said casing means being provided with a plurality of rib portions each having a receiving shoulder formed on an inside portion thereof; a protective tube formed of a material having a high thermal conductivity and being mounted upon said casing means centrally of said rib portions; heat detecting means disposed within said protective tube and in thermal contact with an end portion thereof; heat collecting means being received in said shoulder portions of said rib portions; and a protective member having portions thereof adapted to engage with said rib portions, said heat collecting means being fixedly supported on said casing means by engagement of said rib portions and said protective member.

4,295,372

GRAVITY MEASUREMENT APPARATUS FOR SHIPS


John De Matteo, Whitestone, and Frank Villani, Brooklyn, both of N.Y., assignors to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Dec. 5, 1968, Ser. No. 781,488

Int. Cl.² G01M 1/12

U.S. Cl. 73-382 G

4 Claims



1. An apparatus for continually measuring the free-air gravity anomaly from a moving vehicle which comprises:
vertical acceleration measuring means carried by said vehicle and having a digital rate pulse output proportional to the instantaneous total vertical acceleration sensed by said measuring means;
a scaler/counter having an input and output terminal and providing an output which is scaled to a selected factor and which output is a count of the input pulses;
first electrical means connecting the output of said measuring means to the said input terminal of said scaler/counter means;
a correction circuit having a pair of inputs and an output, one of its inputs connected to receive the output of said

scaler/counter means, the output of said correction being the sum of the input signals;
a Mardan navigational computer including a vertical velocity routine for providing an output which is the negative of the theoretical gravity and the Coriolis error;
second electrical means connecting the output of said computer to said other input of said correction circuit, a time averaging means having negligible weighting at the beginning and end of the period relative to the center time, said averaging means connected to receive the output of said correction means, and
readout means connected to the output of said averaging means, thereby providing an indication of the free-air gravity anomaly.

4,295,373

FLUIDIC ANGULAR RATE SENSOR WITH INTEGRATED IMPULSE JET PUMP ASSEMBLY


E. Marston Moffatt, Glastonbury, Conn., assignor to United Technologies Corporation, Hartford, Conn.

Filed Apr. 3, 1980, Ser. No. 137,109

Int. Cl.³ G01P 3/26

U.S. Cl. 73-505

7 Claims



1. An angular rate sensor, having:
a sealed, fluid filled casing for housing a nozzle block assembly having a jet chamber disposed therein, and for housing a jet pump assembly in registration with said jet chamber and connected for response to an external source of AC signals, said jet chamber including a nozzle and sensing elements disposed at opposite ends thereof, said sensing elements being cooled differentially in dependence on the angular rotation of the sensor, by a fluid jet formed by fluid forced under pressure through said nozzle by said pump assembly at a constant rate of flow provided by the improvement, comprising:
a unitary jet pump structure having a hollow cylindrical supporting flexure element cohesively joined with a metallurgical bond at one end to the periphery of a deformable piezoelectric diaphragm and cohesively joined with a metallurgical bond at the other end to a major surface of an anvil support means, said anvil means major surface providing the end wall of a pump chamber defined otherwise by the internal diameter of the cylindrical flexure and the diaphragm bonded to the other end thereof, said anvil support means being adapted to rigidly engage the casing internally for supporting said pump unitary structure in registration with said jet chamber within said casing.

4,295,374

SPECIMEN GRIPS FOR DYNAMIC MECHANICAL ANALYZER

Robert P. Kusy, Chapel Hill, N.C., assignor to E. I. Du Pont de Nemours and Company, Wilmington, Del.

Filed Sep. 10, 1979, Ser. No. 74,092


Int. Cl.³ G01N 3/32

U.S. Cl. 73-579

4 Claims

1. In a dynamic mechanical analyzer to support a specimen for testing, said analyzer having a pair of spaced sample arms

displaceable relative to each other and having terminal freely extending spaced-apart ends, one of said sample arms being driven and the other counterbalanced, said driven arm having an electromechanical transducer, and means to determine the frequency and amplitude of oscillation of said driven arm, the improvement comprising: a pair of clamps for releasably supporting a specimen to be tested and said clamps and specimen being retained by said sample arms adjacent to the terminal spaced-apart ends thereof, each clamp having a body member, said body member having a base section, said base section having a pair of laterally spaced-apart projecting and cooperat-



ing guide lugs, said guide lugs having a specimen stop means for prepositioning a specimen to be tested, said specimen stop means being removable and positionable at selected spaced increments to accommodate a specimen to be centralized relative to said guide lugs and specimen positioning means for testing, means on said base section for mounting said body member to an arm terminal end, a specimen means cooperatively and slidably retained by said guide lugs, means on one of said guide lugs for displacing said specimen positioning means laterally between said guide lugs to releasably clamp a specimen to be tested.


4,295,375

ULTRASONIC METHOD OF TESTING WELDED JOINTS
Otto Ganglbauer; Felix Wallner, both of Linz; Helmut Scheidl, Ried; Hermann Reindl, Linz, all of Austria, and Rainer Frielinghaus, Bornheim-Merten, Fed. Rep. of Germany, assignors to Voest-Alpine Aktiengesellschaft, Linz, Austria and Krautkraemer GmbH, Cologne, Fed. Rep. of Germany

Filed Dec. 26, 1979, Ser. No. 106,865
Claims priority, application Austria, Jan. 8, 1979, 115/79
Int. Cl.³ G01N 29/04

U.S. Cl. 73—582

6 Claims



1. A method of testing a welded joint comprising base metal and a weld bonded to said base metal at an interface, said method comprising the steps of causing an ultrasonic sound beam to be incident on said interface at an oblique angle to said joint, receiving echoes generated by reflectors in said joint in response to said beam, and deriving information regarding the size and nature of such reflectors from the amplitude of said echoes,

the improvement residing in that the frequency of said sound beam is below an upper frequency limit at which sound has in said base material a wavelength which equals the largest peak-to-valley distance of said interface in any area thereof on which said sound beam is incident at a time.

4,295,376


FORCE RESPONSIVE TRANSDUCER

Robert L. Bell, Chatsworth, Calif., assignor to Besco Industries, Inc., Chatsworth, Calif.

Filed Dec. 1, 1978, Ser. No. 965,604
Int. Cl.³ G01L 9/12

U.S. Cl. 73—724

42 Claims



1. A force responsive capacitive transducer comprising: a flexible diaphragm having a face region deflectable in response to a deflecting force acting thereon and including first electrode means comprising electrically separate electrodes in at least two different regions on the deflectable face region thereof that are deflected differently in response to a deflecting force; and movable plate means coupled to the deflectable face region of said diaphragm between the separate electrodes of said first electrode means and including second electrode means facing the first electrode means.

4,295,377


FASTENER INCORPORATING REMOVABLE ULTRASONIC TRANSDUCER

James C. Couchman, Fort Worth, Tex., assignor to General Dynamics Corporation, Fort Worth, Tex.

Filed Jul. 12, 1979, Ser. No. 57,057
Int. Cl.³ F16B 31/02; G01N 29/00

U.S. Cl. 73—761

21 Claims



1. A fastener, comprising: a shank having a head at one end and threads formed at the other end, an acoustic transducer located in a container means and affixed therein such that said transducer and said container means are an integral unit, and attaching means for removably attaching said container means to one end of said fastener with said acoustic transducer being acoustically coupled to said fastener to allow pulse-echo measurements to be obtained while said fastener is torqued in place with a wrench means, said attaching means being separate from the wrench means whereby when the wrench means is removed from said fastener, said container means remains attached to said fastener, the entire portion of said fastener between said container means and the head being removed.

means and the end of said fastener opposite said container means being of solid metal throughout.

4,295,378


METHOD AND APPARATUS FOR FLOW MEASUREMENT USING DOPPLER FREQUENCY SHIFT

Tom L. Erb, and Wendell D. Miller, both of Austin, Tex., assignors to Ramsey Engineering Company, St. Paul, Minn.

Filed Feb. 11, 1980, Ser. No. 120,189
Int. Cl.³ G01F 1/66

U.S. Cl. 73—861.25

12 Claims



1. The method of measurement of the average velocity of media flowing in a conduit by the use of Doppler frequency shift comprising the steps of:

- determining the locus of points within said conduit where the incremental media flow rate is equal to the average flow rate of the media in said conduit;
- directing a transmitting transducer beam central axis to an intersecting point on said locus of points;
- directing a receiving transducer beam central axis at said intersecting point on said locus of points;
- measuring the incremental rate of flow at said intersecting point on said locus by the use of Doppler frequency shift flow measurement.

4,295,379


GAGE TO MEASURE TRACK TENSION

Boris Zura, Sterling Heights, Mich., assignor to The United States of America as represented by the Secretary of the Army, Washington, D.C.

Filed Feb. 4, 1980, Ser. No. 118,136
Int. Cl.³ G01L 1/04

U.S. Cl. 73—862.62

8 Claims



1. A gage to measure the tension in the track of a track laying vehicle comprising:

- a compressible spring,
- a housing for said spring having telescoping inside and outside housing covers and a central axis,
- the covers having aligned cavities along said axis,
- means, including cam and cam follower elements, in the cavities to convert relative translatory movement of one element along said axis into angular movement of the remaining element about said axis,
- a radially disposed indicator arm secured to the angularly movable element,
- means to secure the two covers against relative angular movement while permitting relative telescoping of the covers along said axis, and
- additional spring means to oppose said angular movement.

4,295,380

GEARING FOR A MOTOR DRIVEN TIMING RELAY

Alois Mühling, Pleinfeld; Frank Reissner, and Helmut Schmidt, both of Nuremberg all of Fed. Rep. of Germany, assignors to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany


Filed Aug. 25, 1978, Ser. No. 936,946

Claims priority, application Fed. Rep. of Germany, Sep. 9, 1977, 2740743

Int. Cl.³ F16H 5/74, 3/34

U.S. Cl. 74—3.5

5 Claims



5. Gearing for a motor driven, multiple range timing relay including:

- a turntable having a motor driven shaft mounted coaxially therewith,
- a coupling pinion adjacent to the turntable;
- a chain of cascaded gear pairs having a first gear pair and at least one more driven gear pair rotatably carried on posts which are fastened by one end to the turntable, being parallel to the motor driven shaft, only every second gear pair positioned on the turntable for engagement with the coupling pinion,
- a pinion on the drive shaft engaging the first of the gear pairs, and
- a drive for indexing the turntable so as to engage any one of the driven second gear pairs with the coupling pinion, whereby the timing range of the relay is set.

4,295,381


CRANKLESS RECIPROCATING ENGINE AND GYROSCOPIC POWER TRANSMISSION SYSTEMVirgil A. Hinds, 1950 Miller Ave., Ann Arbor, Mich. 48103
Continuation-in-part of Ser. No. 785,943, Apr. 8, 1977, Pat. No.4,161,889. This application Feb. 16, 1979, Ser. No. 12,841
The portion of the term of this patent subsequent to Jul. 24,

1996, has been disclaimed.

Int. Cl.³ F16H 29/02, 33/10; G01C 19/00

U.S. Cl. 74-5 R

7 Claims



1. A crankless reciprocating engine and power transmission system comprising means for supporting and substantially linearly guiding an oscillating member of said engine, a mass rotating about a first axis, said rotating mass being in a frame pivotably supported by a gimbal about a second axis at right angle to said first axis, pivot means pivotably supporting said gimbal about a third axis at right angle to said second axis and at variable angle relative to said first axis, means coupling said engine oscillating member to a point of said gimbal for oscillating said gimbal and said rotating mass frame about said third axis, power output means reciprocable by said rotating mass frame when precessionally oscillating about said second axis and biasing means urging said first axis to a position wherein said first axis is orthogonal to said third axis.

4,295,382

IRREGULAR-MOTION MECHANISM

Bernd Lollert, and Heinrich Risse, both of Düsseldorf, Fed. Rep. of Germany, assignors to Jagenberg-Werke AG, Düsseldorf, Fed. Rep. of Germany


Filed Aug. 23, 1979, Ser. No. 69,150

Claims priority, application Fed. Rep. of Germany, Aug. 21, 1978, 2836451

Int. Cl.³ F16H 21/48, 21/18

U.S. Cl. 74-68

1 Claim



1. In an irregular-motion mechanism comprising two series-connected double cranks each comprising a driving link and a driven link connected thereto by a connecting rod, the driving link of the first double crank and the driven link of the second double crank being mounted for independent rotation about a common axis, the driven link of the first double crank being rigidly joined to the driving link of the second double crank, the improvement wherein the driven link of the first double

crank forms an obtuse angle of between 120° and 160° with the driving link of the second double crank and the ratio of their lengths is about 2:3, the length-ratio range for the driving link of the first double crank to the driven link of the second double crank is about 3:2 to 5:4, and the length ratio for the connecting rods of the first and second double cranks is about 1:1.

4,295,383

VARIABLE SPEED DRIVE


John W. Frost, De Pere, Wis., assignor to W. R. Grace & Co., New York, N.Y.

Filed Nov. 11, 1977, Ser. No. 850,607

Int. Cl.³ F16H 7/08; F16G 5/16

U.S. Cl. 474-83

5 Claims



1. A variable speed transmission having a pair of tapered rollers arranged in parallelism and each having a smaller end, the smaller end of said roller as being oppositely disposed from one another, said rollers having a central shaft extending from either end thereof, anti-friction bearing assemblies mounted on each of said shafts and adjacent the rollers thereon, a casing for enclosing said rollers and including a lower half having a pair of generally vertical side walls, one on either end of said rollers, said side walls having semi-circular openings therein for the reception of the said bearing assemblies mounted on said shaft, an endless belt trained around said rollers for providing driving connection therebetween, the spacing of the semi-circular openings in each side wall being such that when the bearing assemblies are mounted in said openings, said belt is tensioned to a predetermined magnitude, said belt including a chrome leather driving face which is bonded to a combination nylon and polyester plastic.

4,295,384

BALL NUT AND SCREW ASSEMBLY WITH TRAVEL LIMIT STOP


Howard C. Brandt, Saginaw, and Leonard R. Grabowski, Bay City, both of Mich., assignors to General Motors Corporation, Detroit, Mich.

Filed Sep. 13, 1979, Ser. No. 74,960

Int. Cl.³ F16H 1/08, 27/02, 29/20

U.S. Cl. 74-424.8 NA

6 Claims



1. In a ball screw assembly, the combination of an elongated screw having helical ball groove means therein, a ball nut member operatively mounted for movement relative to said screw having helical ball groove means therein which matches the groove means of said screw and cooperates therewith to form a helical ball track, a train of balls operatively mounted in said track to drivingly interconnect said nut member and said

screw, ball return means supported by said ball nut member for circulating said balls between opposite end turns of said track, and fixed radially extending stop means disposed in a predetermined position on said screw to provide outwardly inclined ramp means for acting on said balls of said train to progressively force said balls outwardly and radially against the inner surface of said ball nut member forming a portion of said ball groove means therein as said ball nut member progressively moves onto said ramp means to thereby place said ball nut member in hoop stress to prevent said ball nut from traveling past said stop means and thereby provide a limit stop for said assembly.

4,295,385

PIVOTED LEVER ACTUATOR


George H. Huttenhower, 4630 Fillmore St., Denver, Colo. 80216

Filed Jan. 21, 1980, Ser. No. 114,056

Int. Cl.³ G05G 9/02, 1/14; F16C 1/12

U.S. Cl. 74-478

5 Claims



1. Pivotal control means for a cable actuator comprising:
 - (a) circular base plate means for resting on a surface without attachment;
 - (b) circular rotatable top plate means with a planar top surface mounted for free rotation on and in close proximity said base plate means;
 - (c) circular cable support ring means depending from and rotatable with said top plate means positioned between said bottom and top plate means, and said ring means being slightly smaller than said top plate means including a cable support groove;
 - (d) cable guide means mounted on said base plate means for passing a cable onto and from said cable support ring means, providing two free cable ends beyond said unit; and
 - (e) guide roller means mounted adjacent said cable guide means for simultaneously guiding two stretches of a cable through said cable guide means and onto said support ring means.

4,295,386

APPARATUS FOR BALANCING BODIES OF REVOLUTION


Jury G. Zhivotov, ulitsa Svobody, 4, kv. 148, Dnepropetrovsk, U.S.S.R.

Filed Mar. 12, 1979, Ser. No. 19,935

Int. Cl.³ F16F 15/22

U.S. Cl. 74-573 F

2 Claims



1. An apparatus for balancing a body of revolution with a

vertical axis of rotation, comprising: a plurality of balancing tanks located peripherally within said body of revolution; a distributing chamber, having an annular shoulder, mounted coaxially with said body of revolution, and hydraulically connected with said balancing tanks; conduits of said distributing chamber, made in the annular shoulder of said distributing chamber and hydraulically connecting said distributing chamber with said balancing tanks; one of the ends of said conduits being located inside said distributing chamber and equidistant from said axis of rotation of said body of revolution; and the other of said ends of said conduits being located inside said balancing tanks; resilient diaphragms fixed on walls of said balancing tanks at the other ends or outlets of said conduits; a balancing liquid supply source hydraulically associated with said distributing chamber; a chamber of said liquid supply source, having a diameter smaller than the diameter of said distributing chamber and located centrally within said body of revolution; and said chamber of the liquid supply source, the distributing chamber and part of said balancing tanks defined by said resilient diaphragm, and forming a fluid tight cavity.

4,295,387

APPARATUS FOR BALANCING BODIES OF REVOLUTION


Jury G. Zhivotov, ulitsa Svobody, 4, kv. 148; Igor I. Kupchinsky, ulitsa Kuibysheva, 4, kv. 3; Vyacheslav D. Plokhuta, ulitsa Dzerzhinskogo, 33-a, kv. 7; Alexandr M. Bezverkhnny, ulitsa Titova, 30, kv. 76, all of Dnepropetrovsk, U.S.S.R.; Samoil I. Nabutovsky, deceased, late of Dnepropetrovsk, U.S.S.R., and by Elena D. Eroshevskaya, administrator, ulitsa Lenina, 1a, kv. 51, Dnepropetrovsk, U.S.S.R.

Filed Jul. 12, 1979, Ser. No. 56,925

Int. Cl.³ F16F 15/22

U.S. Cl. 74-573 F

3 Claims



1. An apparatus for balancing bodies of revolution secured on a shaft, said bodies of revolution having an axis of rotation, a geometric axis and a center of mass, comprising:
 - a liquid supply source;
 - distributing units mounted coaxially with the body of revolution in measurement planes on both sides of a plane passing through said center of mass of said body of revolution perpendicular to the geometric axis of said body of revolution, a first chamber of each of the distributing units being installed in a first measurement plane and being hydraulically connected with said liquid supply source, conduits of said first chamber of each of the distributing units being provided in a side surface of said first chamber, and ends of said conduits being located inside said first chamber and equidistant from the geometric axis of said body of revolution;
 - balancing tanks mounted peripherally within said body of revolution in correction planes on both sides of the plane

passing through said center of mass of said body of revolution perpendicular to said geometric axis of said body of revolution, and hydraulically associated with said distributing units,

each conduit of said first chamber of each of said distributing units being hydraulically associated with respective balancing tanks which are located in the correction plane to the other side of the respective measurement plane containing said distributing unit relative to the plane passing through said center of mass of said body of revolution perpendicular to said geometric axis of said body of revolution,

each of said balancing tanks and said conduit, hydraulically associated therewith, of each of said distributing units being arranged in planes passing through said geometric axis of said body of revolution to form an angle within the range of 0° to 90°, defined by the plane containing said conduit hydraulically associated with said balancing tank, and said angle coinciding in direction with the sense of rotation of said body of revolution; and

pipelines connecting said liquid supply source with said conduits of the first chamber of said distributing units, and connecting said first chambers of said distributing units with said balancing tanks.

4,295,388

CONTROL ROD AND A PROCESS FOR FITTING A CONNECTING MEMBER AT ONE END OF A CONTROL ROD

Jacques Mialon, Vitrolles, and Bernard Lamarche, Velaux, both of France, assignors to Societe Nationale Industrielle Aerospatiale, Paris, France


Filed Nov. 26, 1979, Ser. No. 97,338

Claims priority, application France, Dec. 4, 1978, 78 34111

Int. Cl.³ G05G 1/00

U.S. Cl. 74—579 R

7 Claims



1. A process for fitting a connecting member at a tubular deformable end of a light weight metal shaft, comprising the steps of:

- inserting into said tubular end a sleeve formed of resistant fibers impregnated with polymerizable resin, the outer surface of said sleeve being in substantial contact with the inner wall of said end;
- flattening a portion of said end sufficiently to bring opposite inner walls of said sleeve into substantial contact with each other; and
- polymerizing said resin to seal the interior of said rod against entry of air or other gas.

4,295,389

ADJUSTABLE LENGTH UPPER GUIDE MEMBER
Hubert Geisthoff, Lohmar, and Wilhelm von Allwörden, Erbach, both of Fed. Rep. of Germany, assignors to Jean Walter-scheid GmbH, Lohmar, Fed. Rep. of Germany
Continuation-in-part of Ser. No. 779,615, Mar. 21, 1977, Pat. No. 4,126,057. This application Nov. 20, 1978, Ser. No. 962,476


Int. Cl.³ B60D 7/00

U.S. Cl. 74—586

4 Claims

1. An adjustable length upper guide member for a hitch attachment of a tractor comprising an outer tubular guide element and an inner relatively displaceable guide element

telescopingly positioned therein, said inner guide element having annular grooves on its outer surface, a housing on said outer guide element, a pair of jaws pivotally mounted within said housing to define first and second arms on each jaw, the first arms of said jaw being engageable with the annular grooves on said inner guide element, said second arms defining actuating cams facing each other, and a first lever having a longer end extending outwardly of said housing and one end extending into said housing and an eccentric portion of said one end with two sides within said housing, one of said sides engageable against the inner surface of said housing and the other of said sides engageable with the actuating cams of said jaws such that when the longer end of the first lever is pivoted



said one side of said eccentric portion will apply a force urging the other of said sides against said actuating cams of the jaws to disengage the jaws from the annular grooves on said inner guide element, and a support lever pivotally mounted on said first lever and pivotable with respect to said outer tubular member into a first position wherein a portion of said support lever is engageable with said outer tubular guide member for supporting said first lever in a position in which said jaws are disengaged from said inner guide element grooves and into a second position in which said jaws are engaged with said inner guide element, and means connected to said support lever for pivoting said support lever between said first and second positions.

4,295,390

MANUAL OVERRIDE CONTROL FOR DOUBLE-ACTING ACTUATOR


Ervin A. Buchta, Houston, Tex., assignor to FMC Corporation, Chicago, Ill.

Filed Oct. 19, 1979, Ser. No. 86,966

Int. Cl.³ F16H 1/18; F16K 31/00

U.S. Cl. 74—625

8 Claims



5. A manual override control for selectively operating a double-acting actuator, said actuator having an actuator housing and an actuator rod with a distal end projecting from said actuator housing comprising:

- laterally directed connector means on said rod distal end;
- a control housing having an internal passage and a laterally directed aperture;
- means for detachably connecting said control housing to said actuator housing to dispose said passage in axially aligned and surrounding relation to said rod distal end;
- a threaded member having a socket portion at one end thereof for receiving said rod distal end therewithin;
- means for mounting said threaded member to said control housing for axial movement in said passage;
- said socket portion having means for releasably engaging said rod distal end connector means;
- operating means for said engaging means including a handle member carried by said socket portion and extending laterally through said control housing aperture;
- means for mounting said threaded member and said socket

portion in said control housing to facilitate removing said override control from said actuator as a single unit, said actuator being operable with said override control removed; and,

means for moving said threaded member in said passage to selectively move said actuator rod relative to said actuator housing when said socket portion has said rod distal end received therein and engaged therewith upon operation of said laterally directed handle member.

4,295,391

TRANSMISSION ASSEMBLY

Arthur Philpott, Little Eaton, and Reginald S. Fuher, Alvaston, both of England, assignors to Ready Pen Limited, Derby, England


Filed May 29, 1979, Ser. No. 43,234

Claims priority, application United Kingdom, May 30, 1978, 24160/78

Int. Cl.³ F16H 3/00, 57/10

U.S. Cl. 74—782

11 Claims



1. A transmission assembly comprising an input shaft, an output shaft in co-axial alignment with the input shaft, a drive sprocket wheel carrying member secured to the input shaft and extending generally radially therefrom, a first sprocket wheel co-axially mounted on the output shaft, a second sprocket wheel rotatably mounted on the output shaft, at least one drive sprocket wheel assembly rotatably mounted on the sprocket wheel carrying member, each drive sprocket wheel assembly including at least a primary and secondary sprocket wheel, and for each drive sprocket wheel assembly, a chain extending about the primary sprocket wheel and the first sprocket wheel and a further chain extending about the secondary sprocket wheel and the second sprocket wheel, and control means for controlling the speed of the rotation of the second sprocket wheel to control the speed of rotation of the output shaft, and reversal drive means providing a step up driving connection between the input shaft and said second sprocket wheel via a clutch, so that when said clutch is activated the second sprocket wheel is rotated faster than the input shaft to effect reversal of the output shaft.

4,295,392

CORKED BOTTLE OPENER

Wallace C. Peck, 227 Grove St., Norwell, Mass. 02061

Filed Jun. 22, 1979, Ser. No. 50,991

Int. Cl.³ B67B 7/04, 7/36


U.S. Cl. 81—3.32

4 Claims

1. A corked bottle opener (according to claim 1 wherein said cork removing means comprises) comprising

- a base section,
- a bracket support means, said bracket support means being in a substantially 90° relationship with said base section,
- retaining means contiguous with said bracket support means and positioned above said base section so that a bottle is positioned and retained onto said base section,
- a first bracket portion having a key portion configured to engage said bracket support means, said first bracket portion having means to pivotally engage a second and a third bracket portion, said second bracket portion is inte-

gral with said third bracket portion and are in an angular relationship to one another, said third bracket portion confronts said retaining means and further comprises a corkscrew mechanism means pivotally and longitudinally movably mounted to the third bracket portion at a posi-



tion confronting a slotted cylindrical opening in said retaining means and adapted to engage said cork in the bottle whereby upward movement of said second and third bracket portions pivotally about said first bracket causes the corkscrew mechanism means inserted in said cork to lift the cork out of the bottle.

4,295,393

STUD HANDLING TOOL


Marty E. Adcock, Logan, Ohio, assignor to The Babcock & Wilcox Company, New Orleans, La.

Filed Jan. 25, 1980, Ser. No. 115,519

Int. Cl.³ B25B 29/00

U.S. Cl. 81—57.4

9 Claims



1. An apparatus for threadingly engaging a first threaded member with a second threaded receiving member and disengaging it therefrom, comprising a frame, means extending from said frame for suspending said first threaded member above said second threaded receiving member, a rotary air motor attached to said frame, engagement means attached to the output of said rotary air motor for engaging said first threaded member for rotation by said rotary air motor, and means attached to said frame operable to apply a lifting force to said first threaded member while said first threaded member is rotated by said air motor and in threaded engagement with said second threaded receiving member, said lifting force applying means comprising a linear air motor operably attached to said frame, and said means extending from said frame being defined by an extensible output member of said linear air motor.

4,295,394

INSTALLATION TOOL BARREL ASSEMBLY


Charles J. DeCaro, Pittsburgh, Pa., assignor to Textron Inc., Providence, R.I.

Filed Feb. 25, 1980, Ser. No. 124,524

Int. Cl.³ B25B 23/02

U.S. Cl. 81—57.37

8 Claims



1. A barrel assembly suitable for connection to a fastener driver tool having a tool body and a driver comprising:
 - A. an outer sleeve adapted for attachment at one end to the tool body;
 - B. an inner sleeve mounted to the outer sleeve so as to be retractable therein, said inner sleeve including an annular wall, a bore and an elongated slot in the wall, said slot increasing in depth from a starting point and terminating in an enlarged clear through opening in registry with the bore to accommodate a fastener head;
 - C. a barrel retractably connected at a first end to the inner sleeve and including a clear through notch in alignment with said slot to receive the fastener in a bore of the barrel; and
 - D. biasing means associated with the inner sleeve and barrel to urge them into an extended position, the driver being positioned at the tool body end of the clear through notch in said extended position so that the barrel assembly can receive said fastener.

4,295,395

TOOL ATTACHMENT HAVING SPRING EJECT RELEASE


Vincent A. Stifano, Jr., Wethersfield, Conn., assignor to Veeder Industries Inc., Hartford, Conn.

Filed May 7, 1979, Ser. No. 36,797

Int. Cl.³ B25B 13/06

U.S. Cl. 81—121 R

10 Claims



1. A tool comprising a body having a drive member with a non-circular opening therein, and a releasable tool attachment having a fastener driving element and connected shank, the shank being dimensioned and configured to be inserted into the opening into an operating position in driving engagement with

the drive member, one of the drive and shank members having a camming surface, the other of the drive and shank members having resiliently biased ejection means engageable with the camming surface upon discrete movement of the shank from its operating position relative to the drive member in a tool attachment release direction, the ejection means and the camming surface cooperating upon engagement to apply an axial driving force to the attachment for positively ejecting the attachment from the tool body.

4,295,396

BAR FEEDING MECHANISM FOR MACHINES FOR WORKING ROTATING BAR STOCK

Heinz Hasslauer, Uhingen, Fed. Rep. of Germany, assignor to Hermann Traub GmbH & Co., Fed. Rep. of Germany

Continuation of Ser. No. 933,954, Aug. 15, 1978, abandoned.


This application Apr. 22, 1980, Ser. No. 142,669

Claims priority, application Fed. Rep. of Germany, Aug. 23, 1977, 2737957

Int. Cl.³ B23B 3/00, 13/00, 25/00

U.S. Cl. 82—1 C

7 Claims



1. A method of guiding a rotating bar stock in a machine for working said bar stock, said bar stock having a middle portion and a tail portion, comprising the steps of:
 - (a) contacting said rotating bar stock with pressure engagement by rollers in a plurality of roller assemblies, said roller assemblies being adapted to support and center said bar stock for feeding to said machine;
 - (b) feeding said rotating bar stock for working by said machine;
 - (c) limiting the contact of said rollers of at least one roller assembly engaging said middle portion of said rotating bar stock to allow sufficient play for a radial antinode of rotation; and
 - (d) readjusting the contact of said rollers of at least one roller assembly after the middle portion has passed to allow pressure engagement of said tail portion of said rotating bar stock.

4,295,397

APPARATUS FOR PEELING PIPES

Wilhelm Schweer, Leichlingen, Fed. Rep. of Germany, assignor to Th. Kieserling & Albrecht, Solingen, Fed. Rep. of Germany

Filed Feb. 7, 1979, Ser. No. 10,177

Claims priority, application Fed. Rep. of Germany, Feb. 13, 1978, 2805947


Int. Cl.³ B23B 5/12

U.S. Cl. 82—20

7 Claims

1. Apparatus for peeling pipes comprising: internal and external independent rotatably driven cutter heads for peeling a pipe, said cutter heads being positioned sufficiently close together for simultaneous peeling of a pipe over at least a portion of the pipe length, feed means for non-rotatably longitudinally feeding a pipe past said cutter heads, and said internal cutter head being in the form of a drill head secured to one end

of an elongated drill rod which extends through the pipe and along which the pipe is fed by said feed means including inde-



pendent variable speed drive means for each said cutter head for independently driving each said cutter head at a desired speed.

4,295,398

WORKPIECE SUPPORTING DEVICE

Yoshiaki Sugata, and Kiyoshi Miyagawa, both of Kariya, Japan, assignors to Toyoda Koki Kabushiki Kaisha, Kariya, Japan


Filed Mar. 21, 1980, Ser. No. 132,426

Claims priority, application Japan, Mar. 22, 1979, 54-37377

Int. Cl.³ B23B 23/00

U.S. Cl. 82—31

5 Claims



1. A workpiece supporting device comprising:
 - a housing;
 - a holding shaft slidably received in said housing;
 - a center member carried on one end of said holding shaft and adapted to support one end of said workpiece;
 - a hydraulic cylinder formed in said housing and including a piston slidably received in said housing and a piston rod integrally formed with said piston and extending from said housing in parallel relationship with the axis of said holding shaft;
 - a sleeve member rotatably but non-slidably mounted on said piston rod and formed with a threaded portion at the periphery thereof;
 - means for rotating said sleeve member;
 - a connecting member threadedly engaged with said threaded portion of said sleeve member;
 - an adjusting member threadedly engaged with said connecting member in coaxial relationship with said holding shaft;
 - spring means interposed between said holding shaft and said adjusting member for applying a holding force to said workpiece being supported on said center member; and
 - means arranged between said holding shaft and said connecting member for limiting relative axial movement therebetween within a predetermined distance.

4,295,399

APPARATUS FOR INTERMITTENT FEEDING OF WEB-TYPE OR STRIP-TYPE MATERIAL

Kurt Finsterwalder, Karl-Heinz Philipp, both of Göppingen; Günter Riedisser, Eisingen, and Wilfried Voss, Göppingen, all of Fed. Rep. of Germany, assignors to L. Schuler GmbH, Göppingen, Fed. Rep. of Germany


Filed Oct. 6, 1978, Ser. No. 949,232

Claims priority, application Fed. Rep. of Germany, Oct. 6, 1977, 2744960

Int. Cl.³ B26D 5/22

U.S. Cl. 83—251

6 Claims



1. An apparatus for intermittently feeding a web-type or strip-type material to an operating chamber of a press having a main press drive means and a scrap cutter means driven in correspondence with an operating cycle of the press, the apparatus including feed roller means, feed gear means operatively connected with the feed roller means, and means for connecting the feed gear means with the main press drive means so that the feed roller means may be driven by said main press drive means, characterized in that means are provided for selectively interrupting the driving of said feed roller means by said main press drive, an auxiliary drive means is operatively connected with the feed gear means so as to drive the same when the drive is interrupted by said interrupting means, and in that a further drive means is operatively connected with the scrap cutter for driving the scrap cutter independently of the main press drive in correspondence with a cycle of the feed gear means.

4,295,400

WEB SEVERING DEVICE


Clifford L. Larson, Marco Island, Fla., assignor to Baldwin-Korthe Web Controls, Inc., Addison, Ill.

Filed Mar. 31, 1980, Ser. No. 135,772

Int. Cl.³ B26D 7/22

U.S. Cl. 83—545

11 Claims



1. A web severing device for a printing press or the like comprising, in combination, a pair of generally parallel spaced-apart elongated carriages positioned transverse to the direction of travel of the web and straddling the path of the web so that

the web passes between said pair of carriages, a severing blade attached to a first carriage of said pair of carriages, a first means for moving the second carriage of said pair of carriages in a direction toward said first carriage to narrow the spaced-apart distance between said carriages, a second means responsive to further movement of said second carriage toward said first carriage for moving said first carriage in the opposite direction toward said second carriage to bring said blade into severing contact with said web, and means for preventing effective activation of said responsive means during any period of time in which a relatively non-flexible, rigid object is disposed between said carriages.

4,295,401

APPARATUS FOR DISPOSING OF RADIOACTIVE FUEL CHANNELS


William L. Mullett, Dunedin, Fla., assignor to NUS Corporation, Rockville, Md.

Filed Jul. 29, 1976, Ser. No. 709,745

Int. Cl.³ G21C 19/32; B26D 11/00

U.S. Cl. 83-864

5 Claims



1. Apparatus for disposing of a radioactive rectangular tubular fuel channel comprising elongated housing means for containing therein the tubular channel, and cutter means, mounted on said housing means, for cutting the channel along each longitudinal corner thereof until the channel is severed into four side plates; wherein said cutter means comprises four roller cutter blades respectively engaging the four longitudinal corners of the tubular channel, and motive means on said housing for simultaneously longitudinally moving said cutter blades in a reciprocating motion along the four longitudinal corners of the tubular channel, whereby severance is achieved by material displacement, as opposed to material removal, so that no material chips are produced; said apparatus further comprising guide roller means associated with each cutter blade to maintain alignment of the cutter blade on the corresponding longitudinal corner during the cutting operation, and to maintain the rectangular configuration of the channel after one or more plates are severed.

4,295,402

AUTOMATIC CHORD ACCOMPANIMENT FOR A GUITAR

Ralph Deutsch, and Leslie J. Deutsch, both of Sherman Oaks, Calif., assignors to Kawai Musical Instrument Mfg. Co., Ltd., Hamamatsu, Japan

Filed Oct. 29, 1979, Ser. No. 88,978

Int. Cl.³ G10F 1/00

U.S. Cl. 84-1.03

22 Claims


1. In combination with a fretted musical instrument having a plurality of electrically conducting strings, apparatus for providing automatic accompaniment comprising;

a means for generating fret signals corresponding to members of said plurality of electrically conducting strings pressed into contact with frets on said fretted musical instrument,

a string selection means for selecting said fret signals corre-

sponding to a preselected subset of said plurality of electrically conducting strings,

a chord detect means responsive to said selected fret signals comprising a matched filter processor wherein a musical chord type is selected from a preselected set of musical chord types irrespectively of whether or not said fret signals comprise a musical chord type,



a root note detect means responsive to said selected fret signals for selecting a chord root note corresponding to said selected musical chord type,

a note data generator means responsive to said selected musical chord type and said selected chord root note wherein input note data is generated, and

a tone generator for creating musical tones at pitches responsive to said input note data.

4,295,403

ADJUSTABLE NECK ATTACHMENT FOR STRINGED INSTRUMENTS


Jeff B. Harris, 10275 SW. Century Oak Dr., Tigard, Ore. 97223

Filed Dec. 24, 1980, Ser. No. 220,080

Int. Cl.³ G10D 3/00

U.S. Cl. 84-293

9 Claims



1. In a stringed musical instrument having a body, an elongate neck extending therefrom, and at least one string extending along said body and said neck, an adjustable neck attachment device for connecting said neck to said body, comprising:

(a) a neck adapter plate and means for attaching said neck adapter plate to said neck;

(b) a body adapter plate and means for attaching said body adapter plate to said body;

(c) single point pivot means associated with said neck adapter plate and said body adapter plate for permitting angular adjustment of the position of said neck adapter plate with respect to said body adapter plate about said single point pivot means;

(d) angle adjustment means extending between said body adapter plate and said neck adapter plate for adjusting the angular position of said neck with respect to said body by rotating said body and neck adapter plates with respect to one another about an axis extending through said pivot means and generally perpendicular to the length of said neck; and

(e) rotational adjustment means associated with said angle

adjustment means, for adjustably holding said neck in a selected position of rotation with respect to said body, about an axis extending generally along the length of said neck and through said pivot means.

4,295,404

COMPENSATED NUT FOR A LUTE-TYPE INSTRUMENT


Paul R. Smith, Annapolis, Md., assignor to DiMarzio Musical Instrument Pickups, Inc., N.Y.

Filed Mar. 14, 1980, Ser. No. 130,574

Int. Cl.³ G10D 3/04

U.S. Cl. 84-314 N

7 Claims



1. A nut for a lute-type instrument said nut comprising an elongated body, said body normally having a length to straddle the neck of said instrument, said body normally adapted to abut the fingerboard of said instrument, and said body including an extending portion, said extending portion adapted to extend over said fingerboard, said extended portion regularly graduated in extent increasing from the treble side to the bass side of said neck, said extent of a selected distance adapted to compensate for sharpness of notes played near said neck.

4,295,405

MUSICIAN'S DRUM

Donald E. Sleishman, 56A Bignell St., Illawong, New South Wales, 2234, Australia


Filed Oct. 9, 1979, Ser. No. 82,462

Claims priority, application Australia, Oct. 18, 1978, PD6446

Int. Cl.³ G10D 13/02

U.S. Cl. 84-413

8 Claims



1. A musician's drum of the kind comprising a cylindrical shell, a diaphragm, and loading means to stretch the diaphragm across one end of the shell, wherein said loading means comprise: engaging means gripping the periphery of the diaphragm; a stabilizer ring co-axial with the shell intermediate the ends of the shell and spaced from the shell; at least three abutment means spaced apart around, secured to and extending from said ring into abutment with said shell to prevent movement of said ring towards at least said one end of the shell; and a plurality of tensioning means extending from said engaging means to said ring.

4,295,406

NOTE TRANSLATION DEVICE

Larry C. Smith, 22916 Juniper Ave., Torrance, Calif. 90505

Filed Aug. 20, 1979, Ser. No. 68,063

Int. Cl.³ G09B 15/02

U.S. Cl. 84-470 R

25 Claims


1. A note translation device for translating selected note symbols shown in printed music to string and fingerboard

location information to use for playing the notes on a stringed fingerboard instrument, comprising:

a support structure;

a keyboard switch array supported by said support structure and including a plurality of musical note switch means corresponding to a plurality of printed music note symbols and selectively operable to enable the operator to input selected note symbols shown in the printed music;

electronic processing circuitry means responsive to said musical note switch means for storing said selected note symbols that correspond to note symbols shown in the printed music,



said electronic processing circuit means further adapted for choosing string and fingerboard location information for playing said selected note symbols thereby translating the note symbols shown in the printed music into string and fingerboard locations to use for playing the notes of a stringed fingerboard instrument, and

means for communicating to the operator said string and fingerboard location information selected by said electronic processing circuit means whereby the string number and fingerboard location is identified for playing each selected note symbol on said stringed fingerboard instrument.

4,295,407

KEYBOARD SIMULATION WITH VERTICAL INVERSION INDEXES


Verna M. Leonard, 3848 E. Swift, Fresno, Calif. 93726

Filed Apr. 18, 1980, Ser. No. 141,577

Int. Cl.³ G10G 1/02

U.S. Cl. 84-471 R

6 Claims



1. A musical teaching aid comprising:

(a) a base member having a backing panel and a front panel, side panels being seamed together across the top and bottom and said front panel defining a horizontal slit;

(b) a simulated keyboard displayed on said front panel beneath said slit;

(c) an insert card for insertion in said slit and having a plural-

- ity of vertical rows of tone-naming indicia indexed above the keys in said keyboard;
- (d) the tones in said tone-naming indicia beginning at the bottom tone thereof with the tone of the underlying key and progressing upwardly naming sequential tones in a particular chord; and
- (e) indicia displayed on the front of said front panel naming the inversions of said particular chord and indexing with the tones on said insert card initiating the respective inversion.

4,295,408

MUSIC TEACHING APPARATUS AND METHOD


John W. Pasker, 472 Tonawanda St., Buffalo, N.Y. 14207, assignor to John W. Pasker, Buffalo, N.Y.

Filed Apr. 20, 1978, Ser. No. 898,071

Int. Cl.³ G04F 5/02; G09B 15/04

U.S. Cl. 84-484

17 Claims



1. A music teaching apparatus comprising means to hold music in position for viewing by a player of a musical instrument, a continuous transparent web having a plurality of indicia thereon for indicating notes of the music to be played when the web is in position with respect to the music and the player, said indicia being so positioned as to permit continuous reading and playing of the music by the player ahead of one thereof when the web and the indicia are moving with respect to the music, means for continuously moving the web with respect to the music, and J-shaped or U-shaped spring members, one each at the top and bottom respectively of the apparatus at an end thereof and at a side of the continuous web, for applying a spring force to the web to hold it in tension, which spring members each have horizontal extensions directed away from the main portion of the apparatus and longitudinally with respect thereto and have mounted on such extensions a non-driving cylinder which applies tension to the web.

2. A music teaching apparatus comprising means to hold music in stationary position for viewing by a player of a musical instrument, a continuous transparent web having a plurality of readily removable and repositionable opaque covers thereon for covering parts of the music when the web is in position with a face thereof between the music and the player, which opaque covers are each of size and shape so as each to cover the height of a staff of the music and which are so positioned as to permit continuous reading and playing of the music by the player ahead of such covers when the web is being moved with respect to the stationary music; and means for continuously moving the web with respect to said music.

4,295,409

SHOT AND POWDER DISPENSER ATTACHMENT

Frank H. Simpson, Rte. 2 Box 276, Cornelius, Oreg. 97113

Filed Apr. 20, 1979, Ser. No. 31,764

Int. Cl.³ F42B 33/02

U.S. Cl. 86-31

2 Claims


1. A shot and powder dispenser in combination with a cartridge reloading machine comprising:

a body defining a channel;

metering means movable within the channel;

lip means on the body, the lip means including a hollow chute;

a powder carrier on the body, the carrier optionally pivotable;



from a first position above the metering means to either a second position on the lip means, so that the flow of powder to the metering means is blocked, or to a third position on the lip means above the chute;

and a dispensing tube on the body operatively connected to the metering means and to the reloading machine.

4,295,410

GUN BOLT LOCKING SYSTEM


Raymond A. Patenaude, Burlington; Steven R. Duke, Williston, and Edward A. Proulx, Burlington, all of Vt., assignors to General Electric Company, Burlington, Vt.

Filed Nov. 28, 1979, Ser. No. 97,993

Int. Cl.³ F41D 7/04

U.S. Cl. 89-12

12 Claims



1. A gun including:
- a receiver [18];
- a gun bolt assembly journaled for reciprocation along a longitudinal axis in said receiver;
- a first transverse cam track [36];
- a second transverse cam track [42];
- means for providing relative transverse motion between said gun bolt assembly and said first and second cam tracks;
- a locking lug [22] pivotally mounted to said receiver [18] and having a first cam following surface [51] and a second cam following surface [68];
- said gun bolt assembly including:
- a gun bolt body [10] having
- a cam surface [50];
- a face [56] for transmitting force along a longitudinal component;
- a first cam follower [34] engaged with said first cam track [36], having a mode of operation such that relative transverse motion between said first cam track and said first cam follower provides reciprocation of said gun bolt body [10] relative to said receiver [18];
- a slide [12] carried by and journaled for relative longitudinal reciprocation with respect to said gun bolt body [10] and having:
- a cam surface [66];
- a second cam follower [40] engaged with said second cam track [42], having a mode of operation such that relative motion between said second cam track and said second cam follower provides reciprocation of said slide [12] relative to said gun bolt body [10];

an actuator lug [44] pivotally mounted to said slide [12], having a mode of operation such that reciprocation of said slide progressively in a first direction [aft] relative to said body causes said actuator lug to be cammed progressively outwardly by such cam surface [50] of said gun bolt body and to engage said first cam following surface [51] of said locking lug [22] to pivot said locking lug progressively in a first direction to engage said gun bolt body to lock said gun bolt body against reciprocation in a first direction [aft], and that reciprocation of said slide in a second direction [forward] relative to said body causes said cam surface [66] of said slider to engage said second cam following surface [68] of said locking lug [22] to pivot said locking lug progressively in a second direction to disengage from said gun bolt body to unlock said gun bolt body to permit reciprocation in said first direction.

4,295,411

IMPACTOR


Innes Grantmyre, and Brent Miedema, both of Cambridge, Canada, assignors to Joy Manufacturing Company, Pittsburgh, Pa.

Filed Oct. 3, 1979, Ser. No. 81,519

Int. Cl.³ F01L 17/00, 25/04; F01B 7/18

U.S. Cl. 91-165

14 Claims



1. In an impactor assembly in which a hammer piston is reciprocally movable through alternate work strokes and return strokes within an elongated bore with the work strokes being effected by a closed drive system which continuously urges said hammer piston in one axial direction toward a rest position thereof by applying to said hammer piston a variable driving impetus of a magnitude dependent upon the displacement of said hammer piston from said rest position and the return strokes being effected by the selective supplying of hydraulic fluid flow from a fluid flow supply means into said bore to apply to said hammer piston a return impetus which displaces said hammer piston from said rest position by overcoming said variable driving impetus, and wherein a valve means includes a valve member which is selectively movable to a supply position to permit the supplying of hydraulic fluid flow into said bore to effect such a return stroke and subsequently is movable to an exhaust position to permit expulsion of hydraulic fluid from said bore thereby permitting said drive system to effect such a work stroke, the improvement comprising:

actuator means integral with said valve means and including surface means upon which said drive system and said hydraulic fluid flow from said fluid flow supply means continuously exert a bias to cycle said valve member between said supply and exhaust positions by providing variable valve actuating impetus to act on said valve member wherein said valve actuating impetus includes a first component resulting from the bias of said drive system on said surface means to urge said valve member toward said supply position, a second component resulting from the bias of said hydraulic fluid flow on said surface means to urge said valve member toward said supply position and a third component resulting from the

bias of said drive system on said surface means to urge said valve member toward said exhaust position.

4,295,412

HOSE WITH A ONE-WAY VALVE FOR A VACUUM OPERATED SERVOMOTOR

Nobuaki Hachiro, Ueda, Japan, assignor to Nissin Kogyo Kabushiki Kaisha, Ueda, Japan


Filed Dec. 12, 1979, Ser. No. 103,512

Claims priority, application Japan, Dec. 19, 1978, 53-158996

Int. Cl.³ F15B 13/04; F16K 15/00

U.S. Cl. 91-468

1 Claim



1. In a connection device for use with a vacuum operated servomotor comprising a flexible hose connected between a booster shell of said servomotor and an intake manifold of an internal combustion engine; a housing having a valve seat, a cylindrical guide portion, and an annular seal projection of a diameter larger than that of said cylindrical guide portion all disposed in an axial direction; a valve member disposed in said housing; and a valve spring in said housing for urging said valve member into seating engagement with said valve seat, said housing being urged into said hose and said cylindrical guide portion being closely fitted in the inner surface of said hose while said seal projection acts to expand said hose radially outwardly to form a tight seal therebetween; the improvement comprises said seal projection having a caulked portion formed at one end of said housing for holding therein an outer peripheral portion of a retainer for supporting a fixed end of said valve spring.

4,295,413

HYDRAULIC ACTUATOR

Toshio Kamimura, Gifu, Japan, assignor to Teijin Seiki Company, Limited, Osaka, Japan


Continuation of Ser. No. 4,534, Jan. 18, 1979, abandoned, which is a continuation-in-part of Ser. No. 807,233, Jun. 16, 1977, abandoned. This application Jun. 2, 1980, Ser. No. 155,743

Claims priority, application Japan, Jun. 18, 1976, 51-71966

Int. Cl.³ F01B 25/26

U.S. Cl. 92-5 L

2 Claims



1. A hydraulic actuator for aircrafts, comprising:

a cylinder;

a main piston axially slidably received in said cylinder and having a hollow bore axially extending therein;
 a liquid source system for supplying a liquid to said cylinder to relatively slidably move said cylinder and piston;
 at least one locking member radially movably retained in said main piston;
 a ram axially slidably received in said hollow bore of said main piston and having a lower engaging portion slidably engageable with the radially inner face of said locking member, an upper engaging portion axially spaced apart from said lower engaging portion with a circumferential length longer than that of said lower engaging portion and slidably engageable with the radially inner face of said locking member, a stepped portion positioned between said lower and upper engaging portions with a circumferential length longer than that of said upper engaging portion but shorter than that of said lower engaging portion and slidably engageable with the radially inner face of said locking member, a first inclined portion connected at one end with said lower engaging portion and at the other end connected with one end of said stepped portion to be slidably engageable with the radially inner face of said locking member for radial movement thereof, and a second inclined portion connected at one end with the other end of said stepped portion and at the other end connected with said upper engaging portion to be slidably engageable with the radially inner face of said locking member for radial movement thereof;
 a compression coil spring accommodated in said bore of said main piston to urge said ram toward said lower engaging portion from said upper engaging portion;
 a switch piston radially slidably mounted on said cylinder to have a radially inner face engageable with the radially outer face of said locking member;
 an indicator for indicating lock and unlock engagement conditions of said cylinder and said main piston; and
 a detecting electric switch for detecting the radially moved position of said locking member through said switch piston to detect said main piston which is locked and unlocked and for transmitting lock and unlock signals to said indicator, whereby the radially inner face of said locking member is in engagement with said lower engaging portion of said ram to assume an unlock engagement position wherein said main piston is in unlocked relation with said cylinder, the radially inner face of said locking member is in engagement with said stepped portion of said ram to assume a first lock engagement position wherein said indicator indicates said unlock signal even though said cylinder and said main piston are in said first lock engagement condition, and the radially inner face of said locking member is in engagement with said upper engaging portion of said ram to assume a second lock engagement position wherein said indicator remains indicating said lock signal.

4,295,414

DIAPHRAGM-TYPE FUEL PUMP


Hiroshi Mochizuki, and Tokio Seki, both of Sowamachi, Japan, assignors to Kyosan Denki Kabushiki Kaisha, Tokyo, Japan
 Filed Aug. 9, 1979, Ser. No. 85,037
 Int. Cl.³ F15B 21/04; F04B 45/10

U.S. Cl. 92—98

2 Claims

1. In a diaphragm-type fuel pump, including a body having an opening therein, a pumping diaphragm extending across and closing said opening, a cup-shaped outer casing positioned over said diaphragm and connected to said body, said outer casing having an end wall spaced a substantial distance from said diaphragm, said outer casing having three axially-spaced sections with a first said section being disposed directly adjacent said end wall and a second said section being cylindrical and disposed axially between said first section and a third said section, said third section being cylindrical and defined at the mouth of said outer casing and connected to said body, said third section having a diameter greater than said second section,

said second section having a cross-sectional area greater than said first section, a separator positioned within and extending diametrically across said outer casing, said separator being positioned axially between said end wall and said diaphragm and being spaced from said diaphragm to define a pumping chamber therebetween, said separator and said diaphragm having the peripheral edges thereof fixedly interposed between said body and said outer casing within said third cylindrical section, said separator having cylindrically projecting inlet and outlet valve holding sections formed thereon and projecting axially of said separator toward said end wall, inlet and outlet valve means respectively mounted within said inlet and outlet valve holding sections, and divider means disposed within the compartment defined within said outer casing between said end wall and said separator for dividing said compartment into inlet and outlet chambers which respectively communicate with the inlet and outlet valve means, a fuel inlet pipe projecting through the outer casing for communication



with the inlet chamber, and a fuel outlet pipe connected to the outer casing for communication with the outlet chamber, comprising the improvement wherein the fuel outlet pipe is connected to the second section of said outer casing and has an inlet opening associated with the end thereof which is disposed in direct communication with said outlet chamber, said inlet opening in its entirety being disposed at an elevation below the elevation of said outlet valve means so that the inlet opening is continuously immersed in its entirety within a reservoir of fuel which collects within said outlet chamber below the elevation of said outlet valve means, and a return pipe connected to said casing for direct communication with said outlet chamber for removing vapors from the upper portion of said outlet chamber, said return pipe having an inlet opening formed at the end thereof in direct communication with said outlet chamber at an elevation which is substantially higher than the elevation of said outlet valve means so that said last-mentioned inlet opening is not immersed in the fuel reservoir to permit continuous removal of vapors from said outlet chamber.

4,295,415

ENVIRONMENTALLY HEATED AND COOLED PRE-FABRICATED INSULATED CONCRETE BUILDING


Peter J. Schneider, Jr., R.D. #4, Boyertown, Pa. 19512
 Filed Aug. 16, 1979, Ser. No. 67,090
 Int. Cl.³ F24F 7/00

U.S. Cl. 98—31

14 Claims

1. A building wall construction comprising exterior wall units constructed of an inner and an outer wall forming a space therebetween with said inner and outer walls being joined by a connecting member along their lower ends, said inner and outer walls being composed of reinforced concrete, said inner and outer walls being provided with an interlocking shape along their lateral edges for interlocking with an adjacent wall unit; said wall unit being assemblable to form a wall having a continuous and substantially uniform space between said inner and outer walls for receiving and forming a continuous and substantially uniform layer of insulation; said outer walls being provided with air ducts therein providing an air passage path between a lower point and a higher point of said outer wall,

said air ducts being provided with a pair of controlled openings at its lower end for selectively communicating with the environment and the inside of the building formed by the building wall, control means for selectively placing the upper portion of



said ducts in communication with the environment and the inside of the building, said controlled openings and said control means being selectively openable to provide heating or cooling of the building.


4,295,416

AIR DISTRIBUTION SYSTEM

Dimitar Gorchev, Boston, Mass.; Karl U. Ingard, Kittery Point, Me., and Herbert L. Willke, Jr., Cambridge, Mass., assignors to Mitco Corporation, Somerville, Mass.
 Filed Sep. 20, 1978, Ser. No. 944,134
 Int. Cl.³ F24F 13/00

U.S. Cl. 98—33 R

19 Claims



1. An air distribution system comprising, in combination:
 A. a mixing plenum including means for receiving outside and return air,
 B. input flow concentrator and integral silencer disposed within said plenum, said concentrator and silencer including a concentrator input port coupled to said plenum and sidewalls establishing an airflow path from said concentrator input port to an output port, said airflow path being substantially symmetrical about an output axis, said side-

walls including inner and outer path defining surfaces lined with acoustically absorbent material, said inner and outer path defining surfaces defining a substantially radial airflow path adjacent to said plenum and a substantially axial airflow path at said output port, said inner path defining surface being substantially symmetrical about said output axis and extending along said output axis substantially across said concentrator input port, wherein said concentrator and silencer include inner and outer sections coaxial with said airflow axis, said outer section being hollow and having an inner surface and said inner section having an outer surface, said inner section having an outer surface, said inner and outer surface being mutually separated to form said path defining surfaces.


C. a fan having a fan input port coupled to said output port.

4,295,417
WINDOW UNIT

Raymond H. Isley, Decatur, Ga., assignor to Isley Window Manufacturing Co., Inc., Decatur, Ga.
 Filed Apr. 30, 1980, Ser. No. 133,916
 Int. Cl.³ E06B 7/02

U.S. Cl. 98—88 R

3 Claims



1. A window unit for a building comprising a peripheral frame, said window unit having a first facade in communication with exterior ambient air and a second facade in communication with interior ambient air, means within said frame defining multiple compartments stacked vertically one above the other, said multiple compartments comprising an upper compartment, a middle compartment and a lower compartment, said middle compartment comprising an exterior window pane and an interior window pane, said panes being spaced apart defining an air space therebetween, the upper and lower compartments being in communication with one another through the middle compartment, the upper and lower compartments having means for communication with the interior and exterior ambient air comprising a closure means in communication with the interior ambient air and a closure means in communication with the exterior ambient air, each of said closure means comprises a pair of horizontally sliding panels positioned for movement in track means and each panel being independently movable, means for preventing inclement weather from entering said upper and lower compartments comprising an awning structure mounted on the exterior facade above each of said upper and lower compartments, the interior window pane of the middle compartment being selectively removable from said frame.

4,295,418

CHAIN BROILER DOCTOR BLADE


Nils Lang-Ree, Los Altos, Calif., assignor to NPI Corporation, Burlingame, Calif.

Filed May 19, 1980, Ser. No. 151,325

Int. Cl.³ A47J 37/06

U.S. Cl. 99—355

2 Claims



1. A chain broiler doctor blade construction comprising a frame, a chain conveyor mounted on said frame to extend in a path having upper and lower portions connected by a semi-circular arcuate rear portion, means engaging said frame and defining supporting sockets on said frame at opposite sides of said chain conveyor, a doctor blade extending transversely of said chain conveyor near said arcuate rear portion thereof, means forming shoulders on said doctor blade near the central side portions of said blade and tiltably disposed in said sockets, and rods extending from said doctor blade and adapted to abut said arcuate rear portion of said chain conveyor.

4,295,419

CONFINED AIR FOOD HEATING APPARATUS


Jerome Langhammer, Rexdale, Canada, assignor to Larry Poulson, Mission, Canada

Filed May 12, 1980, Ser. No. 148,966

Int. Cl.³ A47J 43/18

U.S. Cl. 99—427

6 Claims



1. Means for cooking foodstuffs comprising: a walled housing defining forward and rearward walls, and an opening in said forward wall; means on said rearward wall for rotatably and removably mounting the rearward end of a food container; means projecting into said opening adjacent the forward side

of said housing for rotatably supporting the forward end of such container; a container for foodstuffs designed to be removably rotatably mounted on said inward and outward mounting means; means for rotating said container when so mounted; said means for mounting the forward end of said container being designed: to be removable to allow said container from said housing through said opening and to expose at least a portion of said container below said forward mounting means; said container when so mounted, and said forward and rearward mounting means being within said housing a door designed to substantially close said opening when said container is so mounted, said container being provided with side openings to allow passage of air through foodstuffs therein, said container being provided with means allowing removal of foodstuffs therefrom and the supply of foodstuffs thereto; means for heating and circulating air in said housing.

4,295,420

AUTOMATIC CONTROL SYSTEM FOR HULLING MACHINE

Toshihiko Satake; Akira Kono; Takashi Horie, and Yasuharu Mitoma, all of Higashihiroshima, Japan, assignors to Satake Engineering Co., Ltd., Tokyo, Japan


Filed Jan. 4, 1980, Ser. No. 109,634

Claims priority, application Japan, Feb. 23, 1979, 54-6820; Mar. 13, 1979, 54-28298

Int. Cl.³ B02B 3/04

U.S. Cl. 99—486

14 Claims



1. In a hulling machine comprising a hulling roll supported on a fixed main rotary shaft, another hulling roll supported on a movable auxiliary rotary shaft disposed parallel to said fixed main rotary shaft, a main electric motor for driving said two hulling rolls, means for supplying unhulled rice to the gap between said two hulling rolls and means for controlling the movement of the movable auxiliary rotary shaft, an automatic control system comprising:

- (a) load detecting means for detecting the load applied to said main electric motor; and
- (b) control means for connecting said load detecting means to said means for controlling the movement of the auxiliary rotary shaft.

4,295,421

SAFETY DEVICE FOR GUARDING NIPS IN A SHEET-FED ROTARY PRINTING PRESS

Paul Abendroth, Offenbach am Main, and Dietrich Dettinger, Dietzenbach, both of Fed. Rep. of Germany, assignors to M.A.N.-Roland Druckmaschinen Aktiengesellschaft, Fed. Rep. of Germany


Filed Apr. 7, 1980, Ser. No. 137,915

Claims priority, application Fed. Rep. of Germany, Apr. 7, 1979, 2914152

Int. Cl.³ B41F 5/00

U.S. Cl. 101—216

14 Claims



1. In a sheet-fed rotary printing press the combination comprising a pair of side frames, lower and upper blanket cylinders in running engagement with an impression cylinder, the cylinders being so arranged as to define between them lower and upper nips having a horizontally accessible access space, driving means for the cylinders including an inching circuit and a drive enabling circuit, an interlock switch stationarily mounted adjacent the access space and connected in the drive enabling circuit, a safety subassembly mounted in the access space between the side frames, the subassembly having a horizontal shaft, a guard plate thereon, the guard plate being swingable between (a) a downwardly extending normal position in which the plate closes off the access space and serves as a sheet guide and (b) a horizontally extending alternate position in which it opens up the access space for manual cleaning, and a linkage coupling the guard plate to the interlock switch so arranged that when the guard plate is in its normal closing position the enabling circuit is enabled for normal driving of the press and so that when the guard plate departs from its normal position such circuit is disabled with operation of the press being thereby limiting to inching movement, the subassembly being bodily removable from the access space.

4,295,422

CAMLESS DRIVE OF A SWINGING PRE-GRIPPER FEEDER

Norbert Thünker, Grossachsen, Fed. Rep. of Germany, assignor to Heidelberger Druckmaschinen Aktiengesellschaft, Heidelberg, Fed. Rep. of Germany

Filed Jun. 26, 1979, Ser. No. 52,257

Claims priority, application European Pat. Off., Jun. 26, 1978, 78/00234.0


Int. Cl.³ B41F 21/05; B65H 5/10, 5/14

U.S. Cl. 101—232

3 Claims

1. Camless drive of an oscillating pregripper feeder for a sheet-fed rotary printing machine having a fixed frame and a feed table, an impression cylinder rotatably mounted on said fixed frame and an oscillating pregripper feeder disposed between the feed table and the impression cylinder, the camless drive comprising a multi-bar linkage transmission system having bars mutually connected serially to one another and having pivot joints located at each of the mutual connections of said bars, two cranks articulately connected, on the one hand to

the fixed frame and, on the other hand, to said transmission system and revolvable at the same angular velocity for driving said transmission system, one of said bars forming at least part of a pregripper of said oscillating pregripper feeder, said one bar being disposed directly behind and articulately connected to one of said cranks, said one bar being rigidly connected to a second bar, in turn, articulately connected by a



coupler to a swing lever articulately connected to the fixed frame, said swing lever being drivingly swingable by a crank lever mechanism including the other of said two cranks, said oscillating pregripper feeder having means for gripping a sheet to be printed which lies on the feed table, and said multi-bar linkage transmission system being actuable by said cranks for transporting the gripped sheet along a given path directly to the impression cylinder.

4,295,423

LIQUID DISTRIBUTING ROLLER ASSEMBLY FOR PRINTING MACHINES


Hans John, Radebeul; Wolfgang Müller; Arndt Jentzsch, both of Coswig, and Günter Schumann, Radebeul, all of German Democratic Rep., assignors to VEB Kombinat Polygraph "Werner Lamberz", Leipzig, German Democratic Rep.

Continuation-in-part of Ser. No. 87,296, Oct. 22, 1979, abandoned. This application Nov. 16, 1979, Ser. No. 95,089. Claims priority, application German Democratic Rep., Oct. 28, 1978, 208737

Int. Cl.³ B41F 31/14, 27/16

U.S. Cl. 101—349

6 Claims



1. A distributing roller assembly for distributing printing ink or a dampening liquid on a driven roller of a printing machine, said assembly comprising two stationary guiding tracks arranged opposite each other; a transmission gear unit formed of a housing supported for sliding movement on one of said tracks, a main shaft having one end thereof journaled in said housing and the other end thereof being supported for sliding movement and for rotation on the other track, a drive output gear rigidly connected to one end portion of said main shaft, a transmission gear journaled in said housing and being in mesh

with said drive output gear, and a drive input gear supported for rotation and for axial movement on said one end portion of the main shaft and being in mesh with said transmission gear; a distributing roller supported for rotation and for axial movement on an intermediate portion of said main shaft, one end face of said distributing roller being connected to said input gear to impart rotary movement thereto when said driven roller of the machine is being operated; and an axial cam mechanism arranged between the other end portion of said main shaft and the other end face of said distributing roller to impart thereto via said transmission gear unit a reciprocating axial movement.

4,295,424

EXPLOSIVE CONTAINER FOR CAST PRIMER


Don H. Smith, Dallas, Tex.; Arthur F. Bowman, Tamaqua, and Norman M. Junk, New Ringgold, both of Pa., assignors to Atlas Powder Company, Dallas, Tex.

Filed Apr. 24, 1979, Ser. No. 32,777

Int. Cl.³ C06C 11/00

U.S. Cl. 102—322

16 Claims



1. An explosive container for use with a detonator delay unit of the type having an initiating means and a delay detonator means and for containing a cast explosive charge comprising: a hollow body having closed sides and two open ends with a tubular conduit disposed longitudinally on the exterior of said body, said tubular conduit being dimensioned to receive a detonating cord; partition means contained within and attached to said hollow body, said partition means extending over a cross-section of said hollow body and dividing the interior of said hollow body into an open-ended first volume and an open-ended second volume, said first volume for containing the cast explosive charge, said partition means having an aperture therein to allow the detonator delay unit to be positioned wherein the delay detonator means is positionable adjacent the explosive charge and the initiating means is located in said second volume; means located in said second volume for aligning the initiating means adjacent said tubular conduit; means for retaining the cast explosive charge within said open-ended first volume.

4,295,425

ROCKET ASSISTED PROJECTILE AND CARTRIDGE ARRANGEMENT WITH PRESSURE RELIEF SKIRT

William O. Davis, Baltimore, Md., assignor to AAI Corporation, Cockeysville, Md.

Filed Dec. 6, 1977, Ser. No. 857,957

Int. Cl.³ F42B 5/02, 11/14, 5/10

U.S. Cl. 102—326


12 Claims

1. In a cartridge arrangement having a cartridge case containing ignitable propellant for propelling a rocket-assisted projectile and having an open forward mouth end for receiving and holding a projectile,

the improvement comprising:

a rocket-assisted projectile having a casing containing a

rocket propellant grain and a nozzle block rearward of said rocket grain and having a discharge nozzle therein, said projectile casing having an external rifling-engaging rotating band about a portion of the zone of said nozzle block, and an annular securing skirt extending rearwardly of said rifling band and said nozzle block and grippingly secured within and by said open forward mouth end of said cartridge case,



said projectile securing skirt being of smaller diameter than said rotating band and having at least one vent hole formed therein rearward of and closely adjacent said nozzle block for pressure equalization between the interior and exterior of said skirt during exit of said projectile from said cartridge case by the ignition of said propellant mix, to thereby minimize likelihood of hoop tension cracking of said securing skirt.

4,295,426

PLASTIC WADS AND WAD ASSEMBLIES FOR SHOT CARTRIDGES

Vito Genco, Rome, and Vincenzo L. Turco, Colferro, both of Italy, assignors to Snia Viscosa Societa Nazionale Industria Applicazioni Viscosa S.p.A., Milan, Italy


Filed Mar. 20, 1979, Ser. No. 22,361

Claims priority, application Italy, Mar. 22, 1978, 21258/78[U]

Int. Cl.³ F42B 7/08

U.S. Cl. 102—451

4 Claims



1. A deformable plastic wad assembly for shot cartridges for hunting and shooting, said wad assembly comprising:

a first substantially rigid disc-like member extending perpendicular to a longitudinal axis of the wad assembly and forming a bottom of a shot container;

a second substantially rigid disc-like member extending perpendicular to said axis and forming a top of a seal adapted to be adjacent a powder charge; and

a reticular cushioning structure symmetric with respect to said axis and positioned between said first and second disc-like members, said cushioning structure comprising: at least first and second discs axially spaced from each other and extending perpendicular to said axis, said discs being capable of bending in two opposite directions;

first and second ribs extending parallel to each other and to said axis on opposite lateral sides of said axis, said first and second ribs extending between and being connected to said first and second discs;

a first set of ribs extending between and being connected to said first disc-like member and said first disc, said first set

of ribs comprising a first diametral rib extending in a plane containing said axis and first and second lateral ribs located symmetrically on opposite sides of said first diametral rib and extending parallel to each other and to said first diametral rib, said first and second lateral ribs being disposed along and forming chords of the periphery of said first disc, which chords have lengths, in directions parallel to the plane of said first disc, which are less than the radius of said first disc;

a second set of ribs extending between and being connected to said second disc-like member and said second disc, said second set of ribs comprising a second diametral rib extending in a plane containing said axis and third and fourth lateral ribs located symmetrically on opposite sides of said second diametral rib and extending parallel to each other and to said second diametral rib, said third and fourth lateral ribs being disposed along and forming chords of the periphery of said second disc, which chords have lengths, in directions parallel to the plane of said second disc, which are less than the radius of said second disc; all of said ribs being of a construction to resist axial loading; and

said first and second ribs being spaced from each other by a distance approximately equal to the distances spacing said first diametral rib from said first and second lateral ribs and to the distances spacing said second diametral rib from said third and fourth lateral ribs.

4,295,427

CAR REPAIR APPARATUS

Fred W. Waterman, Daly City; Jerry E. McCleery, San Francisco, both of Calif., and Robert T. McKie, Boise, Id., assignors to Morrison-Knudsen Co., Inc., Boise, Id. and Railcar Maint. Co., San Francisco, Calif.


Continuation of Ser. No. 895,685, Apr. 12, 1978, abandoned.

This application Jan. 9, 1980, Ser. No. 110,568

Int. Cl.³ B61K 5/00

U.S. Cl. 104—32 R

3 Claims



1. A railroad car repair station to lift and rotate a railroad car located at said car repair station comprising in combination: a track passing longitudinally of said car repair station; first and second gantries located at each end of said car repair station, at least one of said gantries including means for mounting said gantry for ground supported rolling movement substantially parallel to said track from a position removed from the ends of said car to a position confronted to the ends of said car; each gantry further including a substantially horizontal beam member attached at least one end to said gantry, said beam having an upward and downward movement on said gantries, said upward movement defining an unobstructed interval between said track and said beam member sufficient to permit the unobstructed passage of said car under said beam on said track, each said horizontal beam including means for grasping said car at an end of a car and means for rotating said car when said car is lifted between said grasping means and beam; whereby when said car is fastened to said beam and lifted by said beam, said car can be rotated, said means for grasping a car for rotating includes a bell crank mounted for rotation to said horizontal

beam and having a male eccentric member for being received by the female coupler concavity of said car.

4,295,428

STEERABLE TRUCK FOR A RAILWAY VEHICLE


William W. Dickhart, III, Ft. Washington, and Richard H. Marvin, Philadelphia, both of Pa., assignors to The Budd Company, Troy, Mich.

Filed Apr. 13, 1979, Ser. No. 29,720

Int. Cl.³ B61F 3/08, 5/20, 5/30

U.S. Cl. 105—168

9 Claims



1. In a railway vehicle having a car body for use on rectilinear and curvilinear pairs of tracks, the combination comprising:

- a truck for supporting said car body,
- said truck including a pair of axles each having a pair of wheels mounted thereto,
- a forced steering mechanism attached to said truck connected to steer at least one of said axles and a pair of wheels, said forced steering mechanism comprises a steering frame including at least two pivotable arms attached thereto to steer one of said pair of axles and two additional arms attached to steer the other of said pair of axles when forced steering becomes effective on curved tracks exceeding predetermined curvatures, and
- means for loosely connecting said car body to said truck and said forced steering mechanism to permit limited relative lateral movement and self steering between said car body and said truck with said forced steering mechanism being maintained ineffective to cause forced steering when said vehicle is moving over rectilinear tracks, and to restrict said lateral movement and self steering and render said steering mechanism effective to cause forced steering when said vehicle is moving over curvilinear tracks exceeding predetermined curvatures.

4,295,429

RAILWAY TRUCK BOLSTER FRICTION ASSEMBLY

Donald Wiebe, Sewickley, Pa., assignor to A. Stucki Company, Pittsburgh, Pa.

Filed Mar. 24, 1980, Ser. No. 133,268


Int. Cl.³ B60F 3/00

U.S. Cl. 105—197 DB

10 Claims

1. A railway truck bolster friction assembly adapted to be captively retained within a pocket of an elongated truck bolster member which extends between spaced elongated side frame members of a railway truck vehicle comprising: elastomeric friction means adapted to have a first portion thereof in communication with adjacent surfaces of such a pocket and a second portion thereof in frictional engagement with adjacent portions of wearing surface means of a column guide of a respective one of said side frames, said second portion being spaced longitudinally outwardly, with respect to the longitudinal axis of such a bolster member, from such a pocket and said first portion being spaced longitudinally inwardly from said second portion; said elastomeric friction means being operative

to deform and maintain said frictional engagement, without slipping between adjacent engaging surfaces, during at least initial vertical and transverse movements of such a bolster member with respect to such a respective one of said side frame members; during a subsequent transverse movement of such a bolster member with respect to such a side frame member, at least a section of said section portion slips transversely



with respect to the adjacent portion of said wearing surface means; and during such transverse slipping, said adjacent portion of said wearing surface means cooperates with such a pocket to continuously increase the friction between said section of said second portion and said adjacent portion of said wearing surface means in direct proportion to the amount of said subsequent transverse movement.

4,295,430

RAILWAY HOPPER CAR LATCH MECHANISM


Willis H. Knippel, Palos Park, and Ray Ferris, Thornton, both of Ill., assignors to Pullman Incorporated, Chicago, Ill.

Filed Feb. 25, 1980, Ser. No. 124,506

Int. Cl.³ B61D 7/18, 7/22, 7/26

U.S. Cl. 105—308 E

10 Claims



1. A closure locking mechanism for a railway hopper car including a discharge opening, closure means mounted for movement adjacent said opening and selectively closing the same and having a keeper rod disposed thereon, latching means positioned adjacent said closure means and adapted to engage and lock the same in its closed position, said latching means including bracket means attached to a hopper, a self-supporting latch member pivotally mounted by a pivot pin on said bracket means and having a keeper gathering opening adapted to move to one position to be aligned with said keeper rod to receive and hold the keeper rod and further to move to another position to latch the keeper rod, said latch member including a cam portion, and having a recessed abutment means, lever means pivotally mounted on said bracket means, and means biasing said lever means into engagement with said abutment means and said cam portion respectively whereby the latch member is positioned to initially engage the keeper rod and maintain it in said closed position.

4,295,431

PALLET FOR PRESSURIZED GAS CYLINDERS


Lars G. Stavlo, Sigtuna, Sweden, assignor to AGA AB, Sweden

Filed Nov. 23, 1979, Ser. No. 96,689

Int. Cl.³ B65D 19/00

U.S. Cl. 108—55.1

13 Claims



1. A pallet, comprising:

- first structure defining a floor having an elevated top surface;
- second structure defining a substantially continuous side wall extending upwardly above the top surface of the floor structure and having opposite end formations leaving an open side wall portion therebetween, one of the end formations including a hollow upstanding post structure;
- first and second gate means, each being connected to at least one of the first and second structures and each being movable between a retaining position and a loading position providing substantially no obstruction to loading and unloading of the pallet through the open side wall portion;
- the first gate means including a bar-like member being non-removably connected to the hollow upstanding post structure, being operable when in its retaining position to bridge the open side wall portion so as to provide a continuation of upper portions of the continuous side wall, and being nested within the hollow upstanding post structure when in its loading position; and,
- the second gate means being operable when in its retaining position to bridge the open side wall portion so as to provide a continuation of lower portions of the continuous side wall, and being operable when in its loading position to facilitate loading and unloading onto and off of the elevated top surface of the floor structure.

4,295,432

HANGING SHELVES


Donald B. Hulke, 14254 Ash Cir. Northeast, Prior Lake, Minn. 55372

Filed Dec. 20, 1979, Ser. No. 105,512

Int. Cl.³ A47B 47/06

U.S. Cl. 108—149

13 Claims



1. A hanging shelf apparatus comprising:

webbing means;

a shelf having a pair of opposing sides and an upper and a lower surface, each side having a recess proximate both ends with a depth equal to at least the width of the webbing means and a slot with a length approximately equal to the width of the webbing means communicating with and along each recess and communicating with the upper and the lower surface of the shelf, the slot and the recess being positioned to receive and hold the webbing means such that the webbing means extends through the upper and lower surfaces; and

recess engaging plug means having a width sufficient for frictionally engaging the webbing means against a surface of the recess to connect the webbing means and the shelf.

4,295,433

TAKE-UP DRIVE FOR A MULTI-HEAD EMBROIDERY MACHINE

Alfred Desprez, Wachtendonk; Heinz Sauerland, Neukirchen-Vluyn, and Wolfgang Teetz, Kerken, all of Fed. Rep. of Germany, assignors to Maschinenfabrik Carl Zangs Aktiengesellschaft, Krefeld, Fed. Rep. of Germany


Filed Aug. 6, 1979, Ser. No. 64,273

Claims priority, application Fed. Rep. of Germany, Aug. 11, 1978, 2835185

Int. Cl.³ D05C 11/00, 7/00

U.S. Cl. 112—241

7 Claims



1. In an apparatus for the drive of the thread take-up on a multi-head embroidery machine having a machine frame, with a plurality of embroidery heads arranged in a row, with at least one embroidery needle in each head, the oscillating thread take-up comprising a thread take-up lever for each embroidery head respectively, which thread take-up lever is mounted on the respective embroidery head pivotable back and forth about a horizontal axis and is operatively driveable by a machine main shaft, the improvement comprising one common thread take-up shaft extending to and passing through all of the embroidery heads, said thread take-up levers of all of the embroidery heads are secured on said common thread take-up shaft, means comprising a single crankdrive mechanism for driving said common thread take-up shaft by the machine main shaft.

4,295,434

FEED MECHANISM FOR SEWING MACHINES

James C. Hsiao, Morton Grove, Ill., assignor to Union Special Corporation, Chicago, Ill.

Filed Oct. 24, 1979, Ser. No. 87,906

Int. Cl.³ D05B 27/02


U.S. Cl. 112—314

20 Claims

1. A sewing machine having a frame, work support means, revoluble shaft means arranged in said frame beneath said work support means, eccentric means carried by said shaft means and a feed mechanism comprising:

feed bar means;
feed dog means carried thereby; drive mechanism means

including a series of connected link means operatively associated with said eccentric means for imparting motion to said feed bar means in mutually perpendicular directions, one direction being transversely across said frame to provide work advancing and return movements, the other direction being toward or away from said work support means so as to lift said feed dog means to a position above



said work support means during the work advancing movement and to lower said feed dog means below said work support means during the return movement; and means associated with said drive mechanism means for allowing rising and falling movements to be translated from said eccentric means to said feed bar means including means for modulating the amplitude of lift being imparted to said feed dog means.

4,295,435

CLOTH FEED APPARATUS

Tamio Uemura, Kawasaki; Yoshimasa Ito, and Takahiro Itakura, both of Yokohama, all of Japan, assignors to Tokyo Juki Industrial Co., Ltd., Chofu, Japan


Filed Aug. 30, 1979, Ser. No. 71,289

Claims priority, application Japan, Sep. 12, 1978, 53-11876

Int. Cl.³ D05B 27/14

U.S. Cl. 112—322

12 Claims



1. A cloth feed apparatus for a sewing machine comprising a needle and a feed dog which is coupled to a main driving shaft, rotor means coupled to said main shaft for rotation in synchronism therewith, detector means for detecting the rotation of said rotor means to generate directly a plurality of pulses in cooperation with said rotor means, stepping motor means actuated in accordance with the pulses generated by said detecting means, and rotary mechanism means driven by said stepping motor means and feeding the cloth fed by the feed dog.

4,295,436

CAP LINING MACHINE


Dominic V. Zangari, 6 Drew La., Hightstown, N.J. 08529, and Douglas R. Cranston, East Brunswick, N.J., assignors to Dominic V. Zangari, Hightstown, N.J.

Filed May 15, 1979, Ser. No. 39,220

Int. Cl.³ B21D 51/46

U.S. Cl. 113—80 D

11 Claims



1. A cap lining apparatus for cutting a cap liner from a web of lining material and placing said cap liner in a cap, said apparatus comprising:

- a hollow anvil means;
- a hollow score cutting means for cutting said web, said anvil means and said score cutting means being lined up coaxially so that the hollow portions of said anvil means and said score cutting means form a cavity;
- web feed means for transporting said web between said anvil means and said score cutting means;
- anvil drive means for driving said anvil means against said score cutting means;
- pusher means for pushing said cap liner into said cap, said pusher means being located in the cavity formed by said anvil means and said score cutting means, said cavity being large enough to allow said pusher means to reciprocate therein;
- a rotatable means for holding said caps, said rotatable means including a plurality of cap receiving pockets therein;
- indexing means for indexing said rotatable means; and,
- feed means for presenting at least two caps to a first and second receiving pocket respectively between successive indexing rotations of said rotatable means, said feed means further including a first feed means for gravity feeding a first cap to a first receiving pocket and a second feed means for positively and directly feeding a second cap to a second receiving pocket.

4,295,437

AUTOMATIC FLARE SIGNAL APPARATUS

George W. Mock, Jr., 5315 Carinleigh, Houston, Tex. 77084, and George W. Mock, Sr., 13206 Boca Raton, Houston, Tex. 77069

Continuation-in-part of Ser. No. 937,473, Aug. 28, 1978, Pat. No. 4,205,619. This application Sep. 26, 1979, Ser. No. 78,914

Int. Cl.³ G08B 21/00

U.S. Cl. 116—202

4 Claims



1. An apparatus for signalling separation between a first structure and a second structure, comprising:

- attachment means for connecting the first structure and the

second structure, said attachment means including an elongated member of a predetermined length;

signalling means responsive to the disconnection of said attachment means for indicating said disconnection, said signalling means including a lanyard cable running parallel to said attachment means, said lanyard cable being substantially the same length as said elongated member, said length of said lanyard cable being such that said lanyard cable is subjected to tension stresses after said disconnection of said attachment means;

an alarm box attached to the second structure, including alarm means for alerting operators of said disconnection of said attachment means substantially immediately upon the happening of said disconnection; and

triggering means comprising a trigger bar, said lanyard cable being removably attached to said trigger bar;

said trigger bar extends into the interior of said alarm box thereupon depressing and opening a pneumatic safety valve when said trigger bar is pulled out of said alarm box by said lanyard cable; and

said triggering means includes a compressed air tank supplying pressure to a regulator valve and said pneumatic safety valve, both controlling a pneumatic piston which drives a firing pin into a signal flare when said safety valve is opened to compressed air flow from said air tank.

4,295,438

RESCUE LOCATOR SIGNAL PACKAGE


Howard L. Porter, Rte. 5, Box 83, Lake Placid, Fla. 33852

Filed Feb. 25, 1980, Ser. No. 124,097

Int. Cl.³ G09F 9/00

U.S. Cl. 116—210

5 Claims



1. A rescue locator package comprising,

- a casing,
- a deflated and collapsed balloon in the casing, and having a fillable end with a self-closing valve therein,
- a cartridge of compressed gas in the casing and movable between an inactive position and an active position, means normally holding the cartridge in its inactive position and so holding it in normal handling of the package,
- a needle tube fixedly mounted in the casing having one end extending through the self-closing valve in the balloon and communicating with the interior of the balloon and the other end having a puncturing point positioned and operable for puncturing the cartridge when the cartridge is moved to active position, and the needle tube, in response to so puncturing the cartridge, extending into the cartridge and thereby establishing communication between the cartridge and the balloon, filling the balloon with the gas,
- the fillable end of the balloon being friction-held on the needle tube, and the remainder and body portion of the balloon being loosely contained in the casing and expella-

4,295,440

APPARATUS FOR CONTINUOUSLY COATING A SHEET MATERIAL CONCURRENTLY WITH A PLURALITY OF STRIPES

Shinzo Nakai, Tokyo, and Chitomi Shimizu, Matsudo, both of Japan, assignors to Hiraoka & Co., Ltd., Tokyo, Japan

Filed Feb. 26, 1980, Ser. No. 124,948

Claims priority, application Japan, Feb. 28, 1979, 54-23101

Int. Cl.³ B05C 3/18

U.S. Cl. 118—412

11 Claims

ble therefrom in response to being filled, and pursuant to being so expelled being normally friction-held on the needle tube and the latter holding the balloon until it is manually released therefrom,

a tether line interconnecting the fillable end of the balloon and the casing, and

manually manipulable means for moving the cartridge to active position and thereby puncturing it,

the manually manipulable means having at least a portion extending into the interior of the casing, and all of the remaining elements being entirely contained in the casing.

4,295,439

HAND OPERATED APPARATUS FOR APPLYING A GASKETING COMPOSITION


Edward G. Kruszona, Schenectady, N.Y., assignor to General Electric Company, Waterford, N.Y.

Filed Sep. 25, 1979, Ser. No. 78,754

Int. Cl.³ B05B 13/04


U.S. Cl. 118—317

12 Claims



1. A hand operated machine for applying a gasketing composition on a part comprising,

- a frame;
- a base on said frame in which is placed said part on which said gasketing composition is applied;
- template means corresponding to a said part and having track means therewith corresponding to said template;
- a vertical support mounted on said frame;
- a horizontally movable arm connected at one end to said support and a horizontally movable joint means pivotally mounted at the other end;
- first forearm means extending from said joint means and pivotally mounted thereon for movement in a vertical plane;
- second forearm means extending from said joint means and supporting roller means operatively associated with said track;
- means for dispensing said composition mounted on said first forearm such that it travels in fixed relationship to said roller means;
- trigger means for activating said dispensing means; and
- means for imparting motion to said assemblage of arms and joint means whereby movement of said roller means about said track is associated with movement of the dispenser in a path to effect application of the gasketing composition to said part.



1. An apparatus for continuously coating a sheet material concurrently with a plurality of coating liquids in the pattern of a plurality of stripes, which apparatus comprises:

- (1) means for feeding a sheet material and means for delivering said sheet material;
 - (2) a substantially vertical coating doctor knife having a blade formed in the lower end portion thereof and arranged between the sheet material-feeding means and the sheet material-delivering means, and;
 - (3) a coating liquid-feeding device attached to a front surface of said doctor knife, which front surface faces said sheet material-feeding means, and having a plurality of compartments, each of which compartments is defined by:
- (A) a pair of substantially vertical partitioning plates which are parallel to each other, spaced from each other and connected to the front surface of said doctor knife in such a manner that a side edge surface of each partitioning plate is in close contact with the front surface of the doctor knife, and a lowermost end of the side edge surface is at substantially the same level as that of a lowermost end of the blade of said doctor knife, and each of which partitioning plates has a bottom edge thereof having a profile in the shape of an arc bulged downwardly from an imaginary straight line drawn between the lowermost end of the side edge of said partitioning plate adjacent the doctor knife, and a lowermost end of another side edge of said partitioning plate, and;
- (B) an inclined guide plate interposed between said pair of partitioning plates and having an inclined upper surface thereof obliquely, downwardly approaching the blade of said doctor knife, and a lower end thereof located close to the blade of said doctor knife, said guide plate also having a lower surface located inside the bottom edges of said pair of partitioning plates.

4,295,441

APPARATUS FOR APPLYING SOLDER TO THE CONNECTIONS OF INTEGRATED CIRCUIT COMPONENTS

Anton Forstner, and Kurt Schatzmann, both of Dietikon, Switzerland, assignors to Siemens-Albis Aktiengesellschaft, Zürich, Switzerland


Filed Nov. 24, 1980, Ser. No. 209,665

Claims priority, application Switzerland, Jan. 30, 1980, 738/80

Int. Cl.³ B05C 3/09

U.S. Cl. 118—425

6 Claims



1. An apparatus for applying to the connections of integrated components arranged in dual-in-line housings solder located in a solder bath, comprising:

at least one support for carrying at least one of the components;

means for displacing said support relative to the solder bath such that the component is placed in a position in which its connections are located at a predetermined distance above the surface of the solder bath;

means for tilting the support in such position about an axis extending essentially parallel to the connections of the component carried by the support and into a position which is inclined with respect to the surface of the solder bath; and

the connections of a connection row of the component, following tilting of the support to one or the other side, simultaneously immersing into the solder bath.

4,295,442

MAGNETIC TONER APPARATUS

James B. Thaxter, Townsend, Mass., assignor to Sperry Corporation, New York, N.Y.

Filed Aug. 4, 1978, Ser. No. 931,214

Int. Cl.³ G03G 15/09

U.S. Cl. 118—657

8 Claims

1. An improved electrophoretic printer of the type having a recipient sheet, a printhead, a supply of toner, and a transfer surface having first and second sides, for conveying the toner to the printhead for transferring the toner to the recipient sheet to form an image thereon, wherein the improvement comprises:

a magnetic roller disposed in magnetic relationship to the supply of toner and opposite the first side of the transfer surface, having an inner magnetic surface and outer cylindrical shell, for generating magnetic field gradients and magnetically attracting the toner to the outer cylindrical shell; and

a high permeability backing plate disposed opposite the second side of the transfer surface and aligned with the magnetic roller cooperating therewith for modifying the magnetic field gradients by magnetization induced in the high permeability backing plate having a selectively profiled surface to produce selectively profiled gradients and for transferring the toner from the roller to the transfer surface in a controlled, uniform thickness.

4,295,443

DEVELOPING APPARATUS FOR ELECTROSTATIC COPYING MACHINE

Mitsuaki Kohyama, Higashikurume, Japan, assignor to Toshiba Corporation, Kawasaki, Japan


Filed Mar. 25, 1980, Ser. No. 133,664

Claims priority, application Japan, Apr. 18, 1979, 54-47524

Int. Cl.³ G03G 15/09

U.S. Cl. 118—657

9 Claims



1. A developer apparatus for developing an electrostatic image on an electrostatic image bearing member, comprising: a single component developer;

a stationary developing roller adjacent said electrostatic image bearing member, said developing roller comprising an electrically conductive sleeve having a plurality of spaced apart channels on the surface of said conductive sleeve, an electrically conductive segment in each of said channels and an insulator in each of said channels between said conductive sleeve and said electrically conductive segment;

voltage means connected to said conductive sleeve and said conductive segments for applying voltage between said conductive sleeve and said conductive segments to charge the developer; and

developer moving means for moving the developer across said developing roller to said electrostatic image bearing member.

4,295,444

AUTOMATIC COATING SYSTEM FOR LOST WAX PROCESS

Masami Hatta, Matsue; Katsumi Iwata, Saihakugun, and Masao Sasaki, Fujisawa, all of Japan, assignors to Hitachi Metals Precision, Ltd., Tokyo, Japan

Filed Dec. 18, 1979, Ser. No. 104,854

Claims priority, application Japan, Dec. 22, 1978, 53-157613; Dec. 22, 1978, 53-174971[U]; Dec. 22, 1978, 53-174972[U]

Int. Cl.³ B05C 3/02, 3/09

U.S. Cl. 118—668

18 Claims

1. An automatic coating system for making a set-up by coating a wax pattern with a refractory material in lost wax process, comprising a set-up pickup device adapted for picking set-ups one by one from a set-up storage section, whereby said set-ups enter said system; a slurry dipping device adapted for receiving said set-ups and for dipping said set-ups in a slurry of a coating refractory material; a sanding device adapted for receiving said set-ups and for depositing sand on the surface of said set-ups; and a set-up taking-out device for removing said set-ups out of said system; said devices being disposed on a common circle; said automatic coating system further comprising a set-up transportation device, wherein said set-up transportation device is disposed at the center of said circle and includes a vertical column, cylinder means attached to said vertical column, a guide member attached to said vertical

column, a main shaft movable up and down by the operation of said cylinder means along said guide member attached to said vertical column, a rotational driving means attached to said vertical column and adapted to cause a rotation of said main shaft around its own axis, a plurality of beams attached to the upper end of said main shaft and extending radially outwardly in a plane perpendicular to the axis of said main shaft, each beam having attached to an end thereof farthest from said main shaft an arm, a cylinder mounted on each beam, slide shafts

granules over a length different than said given length of shingle, whereby varying portions of said series of bands will be present on each of said given length of shingle.

4,295,446

COLLAPSIBLE SHELTER


Clifford C. Voss, 406 Donald Ave., Clawson, Mich. 48017

Filed Feb. 13, 1980, Ser. No. 121,265

Int. Cl.³ A01K 1/03

U.S. Cl. 119—19

5 Claims



1. A collapsible shelter, comprising:

a wrap-around roof and side wall forming part having the relatively opposite wrap-around ends thereof adapted to form and provide a floor area therefor,

said wrap-around part being formed and dimensioned to have a roof area equivalent to that of the side walls and floor area together for allowing said roof, side wall and floor areas to be collapsed and folded flatly together,

and end wall parts formed to fit and close the open ends of said first mentioned part, as erected, and to otherwise lie flatly thereon and therewith,

said end wall parts being interconnected together and relatively spaced to be folded and fitted into the open ends of said first mentioned part, as erected, and to be folded flatly together, one over the other.

4,295,447

HEATING BOILER AND TEMPERATURE CONTROL THEREFOR

Adolf Heeb, Vaduz, Liechtenstein, assignor to Interliz Anstalt, Vaduz-Neugut, Liechtenstein


Filed Sep. 5, 1979, Ser. No. 72,755

Claims priority, application Fed. Rep. of Germany, Sep. 23, 1978, 2841476

Int. Cl.³ F22B 7/00

U.S. Cl. 122—136 R

2 Claims



1. In a heating boiler having a substantially horizontally extending combustion chamber for combustion of liquid or gaseous fuel, said combustion chamber having a cylindrical cross sectional configuration and having a front end and a closed rear end, said combustion chamber having at said front end thereof a flue exhaust outlet, a boiler water chamber surrounding said combustion chamber, said boiler water chamber being defined by a boiler body of oval-shaped cross sectional configuration, said combustion chamber being disposed within

4,295,445

APPARATUS FOR MANUFACTURING ROOFING SHINGLES HAVING MULTIPLE PLY-APPEARANCE


Robert Kopenhaver, Berwyn, Pa., assignor to Certain-teed Corporation, Valley Forge, Pa.

Filed Jun. 20, 1977, Ser. No. 808,171

Int. Cl.³ B05C 1/08, 1/16, 19/00

U.S. Cl. 118—695

16 Claims




1. An improved apparatus for manufacturing roofing shingles from dry roofing material comprising, means for continuously feeding dry roofing material into said apparatus, an asphalt saturation tank for receiving, saturating and coating said dry material with asphalt, means for applying a first continuous coating of granules to said saturated and coated material, means for cutting said material into roofing shingles of a given length and a given width, wherein the improvement comprises, means disposed between said means for applying a first coating of granules and said cutting means for automatically applying a repeated series of spaced apart bands of granules to said first continuous coating of granules, said series of bands having various widths and periodically applied along said first continuous coating at a predetermined periodicity, such that said series of bands are applied to said first coating of

the lower region of said boiler body, a thermostat probe having a sensor section extending into said boiler water chamber, an auxiliary heating channel positioned above said combustion chamber within the boiler water chamber to extend longitudinally of the combustion chamber, said auxiliary heating channel comprising a box-shaped hollow body disposed within the upper region of said boiler body, a return pipe extending into the boiler water chamber for the discharge of return water thereinto, an outflow chamber surmounting said flue exhaust outlet, said outflow chamber comprising a separator wall which separates said outflow chamber from said boiler water chamber, said outflow chamber being in communication with said flue exhaust outlet, said auxiliary heating channel having an inlet joined to said separator wall such that said inlet of said auxiliary heating channel communicates through said separator wall with said outflow chamber and via the outflow chamber with said flue exhaust outlet at the front end of said combustion chamber, said box-shaped hollow body having an upper horizontal side and at least one vertical side, said thermostat probe extending through said boiler body and transversely of said auxiliary heating channel into said boiler water chamber to terminate in said sensor section above said upper horizontal side of said auxiliary heating channel and adjacent to said separator wall, said return pipe extending within said boiler water chamber from the rear end of said boiler body and along side said vertical side wall of said auxiliary heating channel, the discharge end of said return pipe being disposed below said thermostat probe, said sensor section of the thermostat probe being disposed above said inlet of said auxiliary heating channel and adjacent to said separator wall, the discharge end of the return pipe being located within said boiler water chamber in the vicinity of said sensor section such that said sensor section of the thermostat probe is directly washed by the discharged return water.

4,295,448
GAS GENERATOR FOR FINE-GRAINED COAL FUELS
Reinhard Waldhofer, Essen, Fed. Rep. of Germany, assignor to Krupp-Koppers GmbH, Essen, Fed. Rep. of Germany
Filed May 1, 1980, Ser. No. 145,791
Claims priority, application Fed. Rep. of Germany, May 19, 1979, 2920372

Int. Cl.³ F22B 7/18; C10J 3/48
U.S. Cl. 122—164

7 Claims



1. A gas generator for operation on a fuel of fine grained coal, the said generator comprising:
a steam boiler,
a combustion chamber,
a stack leading from the combustion chamber to the steam boiler,


a slanting bottom portion forming the lower part of the steam boiler for the discharge of flue ash and slag,
a gas outlet pipe attached to the combustion chamber and forming the lower part of said stack,
a gas inlet pipe leading to the boiler and forming the upper part of said stack,
connecting means attaching the gas inlet pipe to the said gas outlet pipe, the said gas inlet pipe having a double wall of which the inner wall with its top extends freely into said slanting bottom portion of the boiler and thus is adapted for axial movement due to heat expansion, and the outer wall being provided with a heat expansion compensator and being connected with its top end to the said slanting bottom portion of the boiler and being attached with its bottom end to the said connecting means between said gas inlet and gas outlet pipes.

4,295,449
ROTARY FUEL INJECTION WITH SEQUENCING
Richard A. Cemenska, Edelstein, and George B. Grim, Washington, both of Ill., assignors to Caterpillar Tractor Co., Peoria, Ill.
PCT No. PCT/US79/00762, § 371 Date Sep. 24, 1979, § 102(e) Date Sep. 24, 1979, PCT Pub. No. WO81/00884, PCT Pub. Date Apr. 2, 1981

PCT Filed Sep. 24, 1979, Ser. No. 99,137
Int. Cl.³ F02M 41/06

U.S. Cl. 123—300

22 Claims




1. A fuel injection apparatus comprising:
a plunger (12) reciprocally mounted in a plunger bore (14) to define a pumping cavity (38) therein;
means (20,22,24) for starting and stopping pilot injection and main injection of said fuel by alternately permitting pressurization and venting of said pumping cavity (38), said means for starting and stopping including a plurality of continuously rotating valves (46,48), said valves being fluidly connected to the pumping cavity (38) defined in said plunger bore (14);
a first nozzle (28);
a second nozzle (30); and
(means (26) for sequentially directing said fuel from the pumping cavity (38) of said plunger bore to said first and second nozzles (28,30) for controlling said pilot injection through said first nozzle (28) and main injection through said second nozzle (30).

4,295,450
THERMAL AND VACUUM TRACKING CARBURETOR JET
Ralph Muscatell, 200 N.E. 20th Ave., Fort Lauderdale, Fla. 33305

Filed Dec. 19, 1978, Ser. No. 970,994
Int. Cl.³ F02M 7/00, 1/04
U.S. Cl. 123—435

2 Claims



1. In a carburetor system for an internal combustion engine, said system having:
means defining a fuel chamber;
a fuel mixing conduit having an air inlet at one end and a fuel/air outlet at the opposite end, a venturi throat between said inlet and said outlet, and a throttle valve between said throat and said outlet;
a fuel nozzle operatively arranged to discharge fuel into said throat;
means defining a metering orifice operatively connected between said fuel chamber and said nozzle to supply fuel to said nozzle;
a valve member adjustably positioned at said metering orifice to control the flow of fuel therethrough;
and means responsive to the engine vacuum to adjust said valve member in a direction to increase the flow of fuel to said nozzle when the engine vacuum diminishes and in the opposite direction to decrease the flow of fuel to said nozzle when the engine vacuum increases;
the improvement which comprises:
a temperature sensor operatively arranged to sense the temperature of the engine exhaust;
and means acting between said temperature sensor and said valve member to adjust the latter in a direction to increase the flow of fuel to said nozzle in response to an increased temperature of the engine exhaust and in the opposite direction to decrease the flow of fuel to said nozzle in response to a decreased temperature of the engine exhaust, whereby the richness of the fuel/air mixture is controlled jointly by the engine vacuum and the engine exhaust temperature.

4,295,451
CLOSED LOOP FUEL CONTROL FOR INTERNAL COMBUSTION ENGINE
E. David Long, Elmira, N.Y., assignor to Allied Chemical Corporation, Morris Township, Morris County, N.J.
Continuation of Ser. No. 929,156, Jul. 31, 1978, abandoned. This application Mar. 31, 1980, Ser. No. 135,820
Int. Cl.³ F02M 7/00

U.S. Cl. 123—438

4 Claims


1. A closed loop fuel injection system for proportioning a mixture of air and fuel delivered to an internal combustion engine comprising:

- (a) sensor means for producing an electrical signal having a magnitude that varies in proportion to the concentration of exhaust gas from said engine;
(b) first electrical circuit mean responsive to said electrical

signal to compensate for small amplitude, short term disturbances in said electrical signal, said first circuit means having high gain, low stability and restrictive modification capability over said electrical signal, for providing a first circuit signal with an amplitude limited to a small value;

(c) second electrical circuit means responsive to said electrical signal to compensate for large amplitude, long term disturbances in said electrical signal, said second circuit means having low gain, high stability, and large modification capability over said electrical signal for providing a second circuit signal with a large amplitude;

(d) said first circuit means having a response time that varies directly with and is substantially the same as the time between formation and detection of said air fuel mixture, and being adapted to correct any part of said large amplitude disturbances that is not corrected by said second circuit means;



(e) said second circuit means having a response time longer than the response time of said first circuit means, and being adapted to at least partially correct said large amplitude disturbances;
(f) means for combining the first and second circuit signals to produce a composite pulse of variable width to fix the proportion of air-fuel in said mixture;
(g) means for applying said composite pulse to an injector of said internal combustion engine;
(h) wherein said means for combining includes a timing means connected to receive said circuit signals, means for enabling said timing means, said timing means being enabled in response to said enabling means and producing a timing signal having a time period responsive to said first and second circuit signals, said composite pulse of variable width produced by said means for combining, having a variable width responsive to said time period.

4,295,452
FUEL INJECTION SYSTEM
Manfred Lembke, Gerlingen, and Heinrich Knapp, Leonberg, both of Fed. Rep. of Germany, assignors to Robert Bosch GmbH, Stuttgart, Fed. Rep. of Germany
Filed Jun. 6, 1979, Ser. No. 45,894
Claims priority, application Fed. Rep. of Germany, Jul. 1, 1978, 2829057


U.S. Cl. 123—470

Int. Cl.³ F02M 53/04

6 Claims

1. A fuel injection system for internal combustion engines comprising a metallic fuel distributor tube which is in communication with a pressure regulator and a fuel supply pump, at least one fuel injection valve, at least one fuel branch line made of bendable metal connected at one end to said metallic fuel

distributor tube and at its opposite end to at least one fuel injection valve, a threaded assembly for connecting said bend-



able metal branch line to said fuel injection valve and a thin-walled bellows interposed between said threaded assembly and said fuel injection valve.

4,295,453

FUEL SYSTEM FOR AN INTERNAL COMBUSTION ENGINE

Alec H. Seilly, North Wembley; Dorian F. Mowbray, Burnham; John E. Mardell, Uxbridge, and Michael J. Davison, London, all of England, assignors to Lucas Industries Limited, Birmingham, England


Filed Nov. 16, 1979, Ser. No. 94,719

Claims priority, application United Kingdom, Feb. 9, 1979, 4724/79; Mar. 3, 1979, 7556/79

Int. Cl.³ F02M 37/04

U.S. Cl. 123—499

7 Claims



1. A fuel system for an internal combustion engine of the type in which fuel is injected into a combustion space of the engine, the system being of the kind comprising an injection nozzle positioned on the engine so that fuel delivered to the nozzle will be injected into the combustion space and an injection pump for delivering fuel to the nozzle in timed relationship with the engine, the pump comprising a piston movable in a bore to vary the size of a pumping chamber, resilient means biasing the piston in a direction to increase the size of the pumping chamber, electromagnetic means operable to move the piston against the action of the resilient means to displace fuel from the pumping chamber through the associated nozzle, a valve controlled fuel inlet to said pumping chamber and through which fuel can flow into the bore from a source of fuel when the piston is moved by the action of the resilient means, the system including first electronic means for supplying power to the electromagnetic means for a period of time during which the piston is moved to deliver fuel from the pump, the electromagnetic means at the end of said period of time being de-energised to allow return movement of the piston under the action of the resilient means and second electronic

means operable to supply a holding current to said electromagnetic means to halt the return movement of said piston after the required amount of fuel has been drawn into the pumping chamber.

4,295,454

HEATED FUEL INTAKE SYSTEM IN AUTOMOBILE ENGINE

Yoshihiko Iida, Hiroshima, Japan, assignor to Toyo Kogyo Co., Ltd., Hiroshima, Japan


Filed Feb. 25, 1980, Ser. No. 124,239

Claims priority, application Japan, Feb. 24, 1979, 54/21175

Int. Cl.³ F02M 31/00

U.S. Cl. 123—556

13 Claims



1. In an automobile internal combustion engine comprising an air cleaner, an intake passage leading from the air cleaner to the engine for the passage of air therethrough to the engine from the atmosphere by way of the air cleaner, a fuel supplying means for introducing a controlled amount of fuel into the intake passage, a heated fuel intake system which comprises:

a heating means for heating the air to a predetermined temperature when the temperature of the atmosphere is lower than the predetermined temperature, and heating the air to another predetermined temperature when the temperature of the atmosphere is higher than the predetermined temperature and lower than the another predetermined temperature; and

means for compensating for the increased richness of the air-fuel mixture to be fed to the engine when the temperature of the atmosphere is higher than the predetermined temperature.

4,295,455

EXHAUST GAS RECIRCULATION CONTROL SYSTEM FOR A COMPRESSION-IGNITION INTERNAL COMBUSTION ENGINE

Seishi Yasuhara; Jun Teranuma, both of Yokosuka; Motohiro Shinzawa, Zushi, and Hiroshi Fujii, Yokohama, all of Japan, assignors to Nissan Motor Co. Ltd, Yokohama, Japan

Filed Oct. 2, 1979, Ser. No. 81,144

Claims priority, application Japan, Oct. 9, 1978, 53-124421

Int. Cl.³ F02M 25/06

U.S. Cl. 123—569


9 Claims

1. An exhaust gas recirculation control system for a compression-ignition internal combustion engine having an intake throttle valve in an intake passage and an exhaust gas recirculation passage opening located downstream of the intake throttle valve, comprising

(a) a shutoff valve in the exhaust gas recirculation passage; (b) control means of a fuel injection pump, said control

means interconnected with the shutoff valve, said shutoff valve being closed in proximity to a full load region of the engine; and

(c) a link mechanism interconnecting the intake throttle valve and control means, said link mechanism including



delay means for initiating opening of the intake throttle valve at a time following commencement of operation of the control means of the fuel injection pump and means for completely opening said intake throttle valve before said control means reaches a full operating position.

4,295,456

EXHAUST-GAS-RECIRCULATION SYSTEM FOR USE IN DIESEL ENGINES

Etsuji Nomura, Okazaki; Kazuma Matsui, Toyohashi; Toshikuni Miyazaki, Okazaki; Hiroshi Sami, Numazu, and Tatehito Ueda, Susono, all of Japan, assignors to Nippon Soken, Inc., Nishio and Toyota Jidosha Kogyo Kabushiki Kaisha, Toyota, both of, Japan


Filed Nov. 8, 1979, Ser. No. 92,516

Claims priority, application Japan, Nov. 13, 1978, 53-140184

Int. Cl.³ F02M 25/06

U.S. Cl. 123—569

4 Claims



1. In an exhaust-gas-recirculation system for use in a diesel engine having an intake pipe connected to the engine to introduce fluid thereto and an exhaust pipe connected to the engine to discharge exhaust gas therefrom, said system including an exhaust-gas-recirculation passage having one end thereof connected to said intake pipe and the other end connected to said exhaust pipe, and valve means associated with said exhaust-gas-recirculation passage to control the flow rate of the exhaust gas to be recirculated from said exhaust pipe to said intake pipe through said exhaust-gas-recirculation passage, the improvement which comprises:

a shaft rotatable in synchronization with the engine; a fly-weight mounted on said shaft to produce a centrifugal force upon the rotation of said shaft; a governor member movable in response to a thrust acting thereon due to the centrifugal force produced by said fly-weight;

at least one control spring acting against the thrust on said governor member and having a spring load variable in response to the change in amount of depression of an accelerator pedal; and

actuating means operative in response to the movement of said governor member to actuate said valve means.

4,295,457 CRANKCASE VENTILATING DEVICE FOR RECIPROCATING PISTON INTERNAL COMBUSTION ENGINE

Herbert Schleiermacher, Brühl, Fed. Rep. of Germany, assignor to Klöckner-Humboldt-Deutz Aktiengesellschaft, Cologne, Fed. Rep. of Germany

Continuation of Ser. No. 845,350, Oct. 25, 1977, abandoned.


This application Sep. 11, 1979, Ser. No. 74,413

Claims priority, application Fed. Rep. of Germany, Oct. 23, 1976, 2648112

Int. Cl.³ F02B 25/06

U.S. Cl. 123—574

1 Claim



1. A device for ventilating a crankcase of a reciprocating piston, internal combustion engine by connecting the crankcase to the air intake of the engine, the device comprising:

a housing having a first opening in one wall thereof connected to the crankcase, a downwardly extending second opening communicating with ambient air, and a third opening in a first end wall of the housing connected to the air intake and disposed substantially normal to the first opening;

a piston mounted in the housing, the piston having a cavity therein which faces and surrounds the third opening and which extends normally with respect to the first opening; whereby when the piston reciprocates in a direction normal to the first opening, the third opening is uncovered allowing vapor to flow from the first opening through the housing and out of the third opening;

a projection mounted on a second end wall of the housing opposite the third opening and extending into the cavity of the piston, the projection having a diameter substantially less than the inner diameter of the cavity;

a coil spring surrounding the projection and abutting the piston at one end and the second end wall at the other end for urging the piston to close the third opening;

a first diaphragm disposed between the piston and said one wall of the housing at a location between the first and second openings to seal the first opening from the second opening;

a second diaphragm disposed between the surface of the cavity in the piston and the projection to effect a seal between the second opening and third opening, wherein the first and second diaphragms cooperate with the second end wall to form an ambient air chamber isolated from the first and third openings, the ambient air chamber communicating with the atmosphere via the second opening, whereby when pressure in the housing between the first and third openings exceeds ambient air pressure the piston compresses the coil spring and opens communication between the first and second openings;

a relatively narrow inlet communicating directly with the ambient air chamber and the second opening for throttling ambient air entering the ambient air chamber, and

a separating chamber communicating with the narrow inlet and being relatively wide with respect to the narrow inlet, said separating chamber including a downwardly facing screen extending thereacross for filtering out dirt in the ambient air and a downwardly facing outlet through which the ambient air enters and the filtered dirt drops.

4,295,458


DEVICE FOR INCREASING THE UNIFORMITY OF THE AIR-FUEL MIXTURE IN INTERNAL COMBUSTION ENGINES

Albert Pellerin, 35 rue Lambrechts, 92400 Courbevoie, France
Division of Ser. No. 851,971, Nov. 16, 1977, Pat. No. 4,177,780.
This application Jun. 14, 1979, Ser. No. 48,372

Claims priority, application France, Nov. 16, 1976, 76 34414
Int. Cl.³ F02M 29/00

U.S. Cl. 123—590

4 Claims



1. In a device for internal combustion engines for increasing the uniformity of the air-fuel mixture, comprising a frusto-conical element formed by a perforated lateral wall having a collar at its major opening, the collar being adapted to fit between the carburetor flange and the manifold flange of an internal combustion engine whereas the apex of the truncated cone extends into the manifold inlet of said engine; the improvement comprising a perforated truncated cone disposed inside said element and having its large base secured to the small base of said element and its small base extending in the direction of the large base of said element but terminating a substantial distance short of said large base of said element, both ends of said truncated cone being open.

4,295,459

STOVE


Charles B. Reedy, Morelia, Mexico, assignor to Benedictine Monks Inc., Benet Lake, Wis.

Filed May 23, 1979, Ser. No. 41,739

Int. Cl.³ F24C 1/00

U.S. Cl. 126—60

2 Claims



1. A stove consisting essentially of:

1. an elongated shallow, open trough-shaped fuel chamber adapted to be filled from its bottom almost to its top with fuel,
2. a door closing one end of said chamber, said door being openable to permit introduction of fuel,
3. a flat generally rectangular surface member closing the top of the trough-shaped fuel chamber,
4. said flat surface member having a first opening at the door end of the fuel chamber and a second opening at the opposite end of the chamber, said second opening serving as the sole air inlet to the fuel chamber when the stove is in operation,
5. a chimney communicating with said first opening,
6. an adjustable closure member for said second opening to regulate admission of air into said fuel chamber,

7. said stove during operation being completely closed except for the two openings in said flat surface member.

4,295,460

COMBINATION HEAT TRANSFER PANEL AND WALL SHIELD FOR USE WITH STOVES AND OTHER RADIANT HEATERS


Thomas T. Wilson, San Carlos, Calif., assignor to Epoxon Products, Inc., San Carlos, Calif.

Filed Feb. 2, 1979, Ser. No. 9,222

Int. Cl.³ F24B 7/00

U.S. Cl. 126—121

3 Claims



1. A combination heat transfer panel and wall shield for use between a stove type radiant heater and a combustible wall surface, comprising:

- (a) a hollow case having a top wall and laterally spaced side walls, the case being arranged for support independently of and spaced from a radiant heater,
- (b) a front curtain comprising a plurality of spaced louvers mounted in the case adjacent the open front thereof and spanning the space between the lateral sides thereof, the front louver curtain terminating at its upper end below the top wall of the case and at its lower end above the bottom side of the case,
- (c) a rear curtain mounted in the case spaced rearwardly of the front louver curtain and forwardly of the rear side of the case and terminating at its upper end below the top wall of the case and at its lower end above the bottom side of the case,
- (d) the space between the front louver curtain and rear curtain defining a first vertical convection chamber and the space between the rear curtain and the rear side of the case defining a second vertical convection chamber,
- (e) the space between the bottom side of the case and the lower ends of the first and second curtains defining a cold air inlet communicating the bottom portion of the open front of the case with the bottom ends of the first and second vertical convection chambers,
- (f) the space between the top wall of the case and the upper ends of the first and second curtains defining a hot air outlet communicating the top portion of the open front of the case with the top ends of the first and second vertical convection chambers.

4,295,461

FRICITION HEAT GENERATOR APPARATUS


J. Francis Cummings, 35155 Chardon Rd., Willoughby Hills, Ohio 44094, and Alfred O. Werner, 194 Hawthorn Dr., Painesville, Ohio 44077

Filed Dec. 19, 1979, Ser. No. 105,131

Int. Cl.³ F24C 9/00

U.S. Cl. 126—247

10 Claims



1. A friction heat generator apparatus comprising,
 - a. an outer housing having a fluid inlet and outlet means,
 - b. a drive shaft journaled for rotative movement within said housing,
 - c. a heat exchange means mounted on said drive shaft,
 - d. said heat exchange means including a heat exchange chamber containing a heat transfer medium communicating with said inlet and outlet means,
 - e. a non-rotatable conductor plate member attached to said heat exchange means,
 - f. fly-force-friction drive means mounted for rotation with said drive shaft,
 - g. said friction drive means including a drive hub member connected to said drive shaft,
 - h. a friction drive shoe assembly operably mounted for axial movement relative to said drive hub member,
 - i. a fly-weight mechanism mounted for resilient pivotal movement on said drive hub member, and
 - j. said fly-weight mechanism including cam means operably connected to said friction drive shoe assembly for frictionally engaging said conductor plate member upon rotation of said drive shaft.

10. A friction heat generator apparatus comprising,
 - a. an outer hollow housing having fluid inlet and outlet means,
 - b. a drive shaft journaled for rotative movement within said housing,
 - c. a heat exchange means mounted on said drive shaft interiorly of said housing,
 - d. said heat exchange means including a heat exchange chamber containing a heat transfer medium communicating with said inlet and outlet means,
 - e. a conductor plate member attached to said heat exchange means and said housing for non-rotation relative to said drive shaft,
 - f. fly-force-friction drive means mounted for rotation with said drive shaft,
 - g. said friction drive means including a drive hub member connected to said drive shaft,
 - h. a friction drive shoe member operably mounted for axial movement on said drive hub member,
 - i. a fly-weight unit mounted for resilient pivotal movement on said drive hub member, and
 - j. said fly-weight member including cam means operably connected to said friction drive shoe member for frictionally engaging said conductor plate member upon rotation of said drive shaft in response to centrifugal force imparted to said fly-weight unit.

4,295,462


ENERGY CONCENTRATOR SYSTEM

Jesse C. Bunch, 816 Easley St., Silver Spring, Md. 20910
Continuation of Ser. No. 805,867, Jun. 13, 1977, Pat. No. 4,137,902. This application Feb. 5, 1979, Ser. No. 9,358

Int. Cl.³ F24J 3/02

U.S. Cl. 126—424

11 Claims



1. A radiant energy concentrator system, comprising:
 - (a) reflector means fixedly secured to a base surface, said reflector means for reflecting incident radiation impinging thereon from an energy source, said reflector means having a geodesic dome type configuration including a plurality of reflective elements of predetermined perimetrical contour, said reflector means having a primary focus;
 - (b) receiver means having an extended length in a predetermined direction, said extended length being maintained in a direction substantially parallel with said incident radiation; and,
 - (c) receiver displacement means secured to said receiver means for maintaining said extended length of said receiver means in said parallel direction responsive to directional variations of said incident radiation, said receiver displacement means including means for rotating said receiver means about a pair of substantially mutually perpendicular axes, said mutually perpendicular axes intersecting each other within said extended length of said receiver means, said receiver means extending from at least said axes intersection to said primary focus of said reflector means.

4,295,463

FLEXIBLE V-SHAPED SOLAR TRACKING CONCENTRATING SOLAR ENERGY COLLECTOR

Jeffrey M. Citron, 6111 E. 15th St., Tucson, Ariz. 85711
Continuation-in-part of Ser. No. 680,389, Apr. 26, 1976, abandoned. This application Nov. 13, 1978, Ser. No. 960,121


Int. Cl.³ F24J 3/02

U.S. Cl. 126—425

3 Claims

1. A tracking solar energy concentrator comprising: a plurality of parallel adjacent solar tracking ridges of inverted V-shape in cross-section, said ridges being spaced to form V-shaped troughs, each of said ridges having an apex axis edge and two base axis edges joined by two sides, support means for supporting each of said ridges at said apex and base axis edges, said sides formed of material having a highly light-reflective

surface facing said troughs, said reflective material being of a flexible nature to provide for slippage around said support means during tracking orientation, said support means also providing for slippage and pivoting of said reflective material around said support means during tracking orientation, means to provide tension upon said reflective material whereby the shape of said ridges is maintained throughout thermal fluctuations and tracking orientation, driving and guiding means for the simultaneous relative lateral and vertical displacement of each of said apex axis support means with respect to said base axes support means, said driving means and said pivotally mounting means such that the operative axis of the control means shifts with and remains substantially in parallel with the operative axis of the V-shaped troughs throughout tracking orientation.



4,295,464

URETERIC STONE EXTRACTOR WITH TWO BALLOONED CATHETERS


Alfred A. Shihata, 3584 Fairlans Ave., SW., Grandville, Mich. 49418

Filed Mar. 21, 1980, Ser. No. 131,937

Int. Cl.³ A61B 19/00, 17/00; A61M 25/00, 29/02

U.S. Cl. 128—1 R

17 Claims



1. A stone extractor for extracting a ureteral stone arrested within any of various sections of a ureter of a patient wherein said various sections include ureteral sections above the lower third sectional area of said ureter; said stone extractor comprising:

first inflatable means for gradually applying an increasing outward radial force to inner walls of said ureter wherein said inner walls are distended in response to said radial force in a manner such that a stress relaxation state is induced therein;

first catheter means connected to said first inflatable means and adapted to position said first inflatable means below the position of arrestment of said ureteral stone;

second inflatable means for applying a downward force to

said ureteral stone to achieve dislodgment of said stone from said inner walls of said ureter;

second catheter means connected to said second inflatable means for positioning said second inflatable means above the position of arrestment of said ureteral stone; and

said second catheter means is adapted to adjust the position of said second inflatable means relative to said first inflatable means and is manually manipulable to move said ureteral stone into a spacial area of said ureter distended by said first inflatable means.

4,295,465

LARYNGOSCOPE BLADE


Gabor Racz, Lubbock, Tex., and Forrest Allen, Fayetteville, N.Y., assignors to N.A.D., Inc., Telford, Pa.

Filed Apr. 3, 1980, Ser. No. 137,057

Int. Cl.³ A61B 1/06

U.S. Cl. 128—11

10 Claims



1. A blade for a laryngoscope having a handle, said blade comprising a base member and a projecting flange member, and bias means, said base member being an elongated member having a rear portion, a midportion and a tip portion, said blade being secured to said handle at said rear portion said midportion being generally linear, said flange projecting upward from said base member along said rear and midportion and being pivotally mounted on said base member, said bias means providing a bias force to said blade, whereupon when said blade is inserted into a patient's mouth with flange in contact with the patient's teeth, said flange is enabled to pivot with respect to said blade against the force provided by said bias means to prevent the application of excess pressure to the teeth.

4,295,466

LIMB ENGAGING BAND FOR ORTHOTIC DEVICE

Wesley C. Prout, Los Gastos, Calif., assignor to Hosmer/Dorrance Corporation, Campbell, Calif.

Filed May 16, 1980, Ser. No. 150,646


Int. Cl.³ A61F 3/00

U.S. Cl. 128—80 R

8 Claims

1. A strap assembly for an orthotic device, comprising a form retaining first member including an arcuate configuration to encircle a portion of a limb; a second, flexible, resilient member having a longitudinally extending channel portion, said channel portion engaging and securing said first member;

said first and second members being longitudinally offset to define a free end of each, and strap and buckle means secured



to said free ends to join said free ends together in confronting relationship.

4,295,467

ELECTROLYSIS APPARATUS WITH RETRACTABLE PROBE


Samuel J. Mann, Englewood, and Michael Hrehovcik, Little Falls, both of N.J., assignors to Inverness International Corp., River Edge, N.J.

Filed May 24, 1979, Ser. No. 42,277

Int. Cl.³ A61B 17/38

U.S. Cl. 128—303.18

9 Claims



1. An electrolysis apparatus comprising a housing including a probe end, said housing including a conductor means supported on said exterior thereof for defining a current path, an electrically conductive probe adapted to be coordinately displaced between an operative position wherein said probe extends from said probe end of said housing and an inoperative position wherein said probe is retracted into the probe end of said housing, positioning means associated with said housing and said probe for selectively displacing said probe between said operative position and said inoperative position, said positioning means including spring biasing means for biasing said probe against the papilla with a force normally sufficient for entry into a pore but normally insufficient to cause penetration of the skin when said probe is displaced in an operative position, first conductive means electrically connected with said conductor means and second conductive means electrically connected with said probe, said first and second conductive means being electrically connectable with a voltage source.

4,295,468

CARDIAC PACER TESTING SYSTEM


James T. Bartelt, Shoreview, Minn., assignor to Cardiac Pacer-makers, Inc., St. Paul, Minn.

Filed Oct. 24, 1979, Ser. No. 87,867

Int. Cl.³ A61N 1/36

U.S. Cl. 128—419 PT

6 Claims



1. Apparatus for measuring the R-wave sensitivity of a demand cardiac pacer comprising:

(a) means for receiving pacer pulses from said cardiac pacer;

(b) means responsive to successive ones of received pacer pulses for producing pseudo R-waves of incrementally increasing amplitude;

(c) means for applying said pseudo R-wave signals to the R-wave sensing circuit of said cardiac pacer; and

(d) means for displaying the voltage amplitude of the pseudo R-wave just sufficient to cause resetting of the pulse generator of said demand cardiac pacer.

4,295,469

BRASSIERE CONSTRUCTION


Hazelle C. Lindgren, Rte. 4, Box 283A, Buffalo, Minn. 55313

Filed Oct. 20, 1978, Ser. No. 953,273

Int. Cl.³ A41C 3/10, 3/00

U.S. Cl. 128—480

3 Claims



1. A brassiere construction for a brassiere having a latchable, elongated vest member encircling the wearer's body, a pair of breast covering cups with upper and lower edge portions and a pair of shoulder straps, said brassiere construction comprising:

a pair of fabric material elements having upper and lower edges, each said fabric material element being flexibly secured at its lower edge to said brassiere near the lower edge portion of a cup, said material extending upwardly at least to a location for contacting the lower junction of the breast and the lower rib cage,

whereby said fabric material element may pivot about the lower edge inwardly away from the cup to form a pouch within which a breast may be contained, said material

thereby laying between the underside of a breast and the wearer's lower rib cage.

4,295,470

OPTICAL CATHETERS AND METHOD FOR MAKING SAME


Robert F. Shaw, Portola Valley, and John Sperinde, San Jose, both of Calif., assignors to Oximetrix, Inc., Mountain View, Calif.

Continuation of Ser. No. 733,279, Oct. 18, 1976, abandoned. This application Nov. 29, 1978, Ser. No. 964,612

Int. Cl.³ A61B 5/02

U.S. Cl. 128—634

18 Claims



1. A catheter for photometric analysis of a fluid, said catheter comprising a plurality of transmitting and a plurality of receiving optical fibers; each said optical fiber for conducting radiant energy therethrough from an aperture at one end thereof to an aperture at the other end thereof; each aperture of each transmitting and each receiving optical fiber at the distal end thereof having a centroid of area; the centroid of the aperture of the distal end of each and every transmitting optical fiber being equidistant from the centroid of the aperture of the distal end of each and every receiving optical fiber.

4,295,471

NON-INVASIVE VASCULAR WAVEFORM TRANSDUCER AND APPARATUS


William J. Kaspari, 342 Willowbrook Dr., Portola Valley, Calif. 94025

Filed May 25, 1979, Ser. No. 42,415

Int. Cl.³ A61B 5/02

U.S. Cl. 128—675

11 Claims



1. A transducer for noninvasively monitoring a vascular waveform comprising
a housing forming two independent cavities therein,
a pair of support members, one disposed in each of said cavities,
a pair of sensing elements, one resting on each of said first support members in said cavities,
a pair of retaining members, one disposed on top of each said sensing element in said cavities,
a pair of retaining caps, each cap having an orifice therethrough, said retaining caps being affixed to said housing to cause each of said sensing elements to be positioned between said support member and said retaining members, pressure-transmitting means within each of said orifices for causing pressure waves impinging thereupon to be transmitted to the associated sensing element, each sensing

element being responsive only to pressure waves entering its associated orifice.

4,295,472

HEART RATE MONITOR


John M. Adams, Mesa, Ariz., assignor to Medtronic, Inc., Minneapolis, Minn.

Continuation of Ser. No. 851,030, Nov. 14, 1977, abandoned, which is a continuation of Ser. No. 714,873, Aug. 16, 1976, abandoned. This application Oct. 1, 1979, Ser. No. 80,597

Int. Cl.³ A61N 5/04

U.S. Cl. 128—690

4 Claims



1. A cardiac signal detector comprising:

a housing containing circuitry for detecting and counting individual heartbeats of a person as said heartbeats are manifested by a pair of electric signals, each one of which signals manifests the electrocardiac potential at a different limb of said person, said circuitry including means for selecting the time during which said detected beats are counted to be six or sixty seconds;

a band member of an electrically conductive material selected to be capable of detecting electric signals on the skin of such person, said band being affixed to said housing and said housing and band combination being capable of firmly contacting one of said limbs, said band and housing combination further being in electric communication with said circuitry to provide the signal at said one limb as one of said pair of signals;

receiving means electrically isolated from said housing and band combination, said receiving means being adapted for physical contact with said other limb and being in electrical communication with said circuitry to provide the other one of said pair of signals;

display means for providing a signal representative of the heart rate of said person;

timing means responsive to the state of said means for selecting for providing timing signals to cause said detecting beats to be counted for said selected time;

means responsive to said timing signals and the counted beats for providing signals representative of the heart rate of said person to said display means;

means responsive to said means for selecting whereby in the event a sixty second timing signal is selected, said display means displays the number of detected and counted heartbeats;

and

decade means responsive to said means for selecting whereby in the event a six second timing signal is selected, said display means displays ten times the number of detected and counted heartbeats.

4,295,473

APPARATUS AND METHOD FOR ANALYSIS OF MOTION OF A DYNAMIC STRUCTURE


George Diamond, 2408 Wild Oak Dr., Los Angeles, Calif. 90068; James Forrester, 3226 Serra Rd., Malibu, Calif. 90265; Michael Hirsch, 756 Amalfi Dr., Pacific Palisades, Calif. 91272, and Ran Vas, 17130 Clemons Dr., Encino, Calif. 91436

Filed May 24, 1979, Ser. No. 42,247

Int. Cl.³ D61N 5/00

U.S. Cl. 178—695

58 Claims



1. A system for detecting and measuring the linear motion in at least one dimension of a portion of either a dynamically movable structure or visual image representations of that structure and providing an analog signal representative of the movement, said system comprising:

(a) sensing means for detecting and measuring the light change pursuant to a moving boundary on the structure or a series of sequential image representations of that structure moving between dark and light regions on said dynamically movable structure or on said series of sequential visual image representations of said dynamically movable structure, and which sequential visual image representations are displayed in sequence at a rate to represent the movable structure during movement thereof, said sensing means generating a current signal representative of the boundary movement,

(b) conversion means for receiving the current signal from said sensing means for generating an analog voltage signal as a fairly exact analog of the current signal and being representative of and directly related to the amount of movement of said boundary on the dynamically movable structure or on the series of sequential visual image representations,

(c) selection means operatively connected to said conversion means for selecting a sample of predetermined instantaneous amplitude and at least temporarily holding such sample,

(d) detection means operatively connected to said selection means for aiding in and determining a sample of predetermined instantaneous amplitude to thereby determine a maximum limit of movement of the boundary at least in one region, and

(e) means operatively connected to at least said selection means for providing a representation of the amount of movement of said boundary.

4,295,474

RECORDER WITH PATIENT ALARM AND SERVICE REQUEST SYSTEMS SUITABLE FOR USE WITH AUTOMATIC IMPLANTABLE DEFIBRILLATOR

Robert E. Fischell, Silver Spring, Md., assignor to The Johns Hopkins University, Baltimore, Md.

Filed Oct. 2, 1979, Ser. No. 81,167

Int. Cl.³ A61B 5/04

U.S. Cl. 128—697

34 Claims

1. A recorder system, adapted for use with an automatic defibrillator system responsive to a patient's electrocardiogram (ECG) data and capable of detecting the occurrence of abnormal cardiac activity and render effective automatically in response thereto to generate and apply one or more defibrillation electrical impulses to the patient's heart intended to return the heart to normal functioning, said recorder system being

responsive to the patient's ECG data and comprising, in combination,


means for sampling and converting said ECG data from analog to digital form,

first and second ECG data digital storage means,

means for registering the occurrence of said abnormal cardiac activity as detected by said automatic defibrillator system,

storage control means controlled by said occurrence registering means responsive to the occurrence of said abnormal cardiac activity for selectively rendering effective said first and second ECG data storage means to store ECG digital data occurring respectively for a first time period just prior to the occurrence of said abnormal cardiac activity or for a second time period encompassing the application of said defibrillation impulse(s) by said automatic defibrillator system,

time registration means controlled by said occurrence registering means responsive to the occurrence of said abnormal



mal cardiac activity for registering as a digital code the time of occurrence of said abnormal cardiac activity, first counting means responsive to the generation of each defibrillation impulse by said automatic defibrillation system for registering as a digital code a count of the number of said defibrillation electrical impulses generated by said automatic defibrillator system,

second counting means responsive to said occurrence registering means for registering as a digital code a count of the number of occurrences of said abnormal cardiac activity, and

readout control means operable upon command for reading out

(a) the ECG digital data stored in each of said first and second storage means,
(b) the digital code time registration of said time registration means, and
(c) the digital code counts of each of said first and second counting means.

4,295,475

PROBE AND SYSTEM FOR DETECTING PROBE DISLODGE

Terence A. Torzala, Warminster, Pa., assignor to Air Shields, Inc., Hatboro, Pa.

Filed Oct. 26, 1979, Ser. No. 88,474


Int. Cl.³ A61B 5/00

U.S. Cl. 128—736

13 Claims

1. A probe comprising:
a probe housing having a contact surface adapted for contact with a body and a second surface adapted to be spaced from said body and upon which radiation reflected from

said body impinges when said contact surface is in contact with said body;
first radiation receiving means located in said contact surface for sensing an increased radiation level impinging on said contact surface when said probe housing is dislodged from said body and said contact surface is exposed to said increased radiation level and for developing an output representative of said increased radiation level;




second radiation receiving means located in said second surface for sensing (1) radiation reflected from said body, and (2) a decreased radiation level impinging on said second surface when said probe housing is covered and said second surface is exposed to said decreased radiation level and for developing an output representative of said decreased radiation level;
and means emanating from said housing for transmitting said outputs of said first and said second radiation receiving means to a remote location.

4,295,476
BLOOD COLLECTION ASSEMBLY FOR PREVENTING OUTWARD MOVEMENT OF THE BLOOD CONTAINER
Gary F. Quas, Rutherford, N.J., assignor to Becton, Dickinson and Company, Paramus, N.J.

Filed Dec. 19, 1979, Ser. No. 105,346
Int. Cl.³ A61B 5/14

U.S. Cl. 128-764

7 Claims



1. A holder assembly for use with a closed blood collection container one end of which includes a cannula-penetrable closure with a lip element associated therewith, said assembly comprising:

- a receptacle having a closed end, side walls and an open end for the receipt of said blood collection container;
- an interior cannula extending from said closed end into said receptacle;
- an exterior cannula extending outwardly from said closed end, said interior and said exterior cannulae being in fluid communication with each other;
- a spring-resilient, cannula-penetrable valve sheath covering said interior cannula adapted to expose said interior cannula to fluid flow therethrough when said blood collection container is inserted into said receptacle thereby causing said interior cannula to penetrate said closure and said sheath to become compressed against said closed end, said sheath serving as a loaded spring when compressed; and

said receptacle including a spring-depressible tongue located in a side wall thereof and being normally flush with the side wall and having a distal end depressible downwardly

into the interior of said receptacle and a proximal end hingedly connected to said side wall, said distal end of said tongue being spaced a pre-determined distance from the closed end of said receptacle so that it, upon being downwardly depressed, is adapted to engage said lip element on said blood collection container after being inserted into said receptacle to thereby prevent said container from being pushed out of said receptacle under the influence of the spring force of said compressed valve sheath.

4,295,477
MULTIPLE SAMPLING DEVICE HAVING MOLDED VALVE AND HUB
Werner Christinger, Franklin Lakes, N.J., assignor to Becton, Dickinson and Company, Paramus, N.J.

Filed Aug. 15, 1979, Ser. No. 66,818
Int. Cl.³ A61B 5/14

U.S. Cl. 128-766

5 Claims



1. A multiple blood sampling device adapted to be coupled with an evacuated container to obtain blood samples from a patient, said device comprising a housing having a first hub, a second hub and chamber therein, a first cannula attached to said first hub and adapted for penetrating a blood vessel, a second cannula attached to said second hub and adapted for piercing a stopper of an evacuated collection container, and a one-way valve provided within said housing, said cannulas and said chamber being in fluid communication when said valve is in an open position, characterized in that a first portion of said valve is connected in fixed position to said first hub, and a second portion of said valve freely extends into the chamber, said second portion capable of assuming an open position to allow the passage of blood therethrough when suction is applied within the chamber by means of the second cannula, and assuming a closed position when pressures within each cannula are equal, said valve positioned inside said first hub and said chamber to be free of contact with said second hub in both open and closed conditions.

4,295,478
COMPOSITE TIPPING STRUCTURE FOR USE ON AN AIR-VENTILATED CIGARETTE AND METHOD OF MANUFACTURING SAME

Roy E. Yeatts, Winston-Salem, N.C., assignor to RJR Archer, Inc., Winston-Salem, N.C.


Filed Apr. 11, 1979, Ser. No. 29,163
Int. Cl.³ A24C 5/56; A24D 3/00, 3/18

U.S. Cl. 131-336

9 Claims

1. A composite structure for use as a tipping material for an air-ventilated smoking product comprising a non-porous paper

web, a heat activatable adhesive coating on said non-porous paper web in a pattern including a zone having a width corresponding to a fraction of the length of said non-porous paper



web and intermediate two marginal areas, said zone having a plurality of intermingled discrete coated and void areas, and microscopic perforations interspersed only within the void areas in said zone.

4,295,479
METHOD AND DEVICE FOR MANUFACTURING CIGARS

Wilhelmus P. L. Boogers, Eindhoven, Netherlands, assignor to B.V. Areco P.M.B., Best, Netherlands


Filed Nov. 29, 1978, Ser. No. 964,455

Claims priority, application Netherlands, Dec. 29, 1977, 7714544

Int. Cl.³ A24D 1/02; A24C 1/26, 1/30

U.S. Cl. 131-60

12 Claims



2. A device for wrapping cigar filler material with a tobacco wrapper portion comprising at least two filler holders for receiving each one filler, and at least one wrapper portion carrier means for applying each tobacco wrapper portion in the stretched state to a filler characterized by a feeding conveyor (13) for feeding fillers from a stock to an adjoining transfer station (10), by a delivery station (15) arranged at a distance from the latter and by an advancing mechanism for carrying the filler holders (1) from the transfer station (10) to the delivery station (15) and conversely as well as by a guide path with a driving mechanism for advancing at least one wrapper portion carrier means in synchronism with the holders (1).

4,295,480
COMB AND THE METHOD OF MAKING SAME
John A. Biela, Niles, Ill., assignor to Jerome D. Schiffman, deceased, late of Wilmette, Ill.

Filed Jan. 27, 1977, Ser. No. 763,280
Int. Cl.³ A45D 24/00

U.S. Cl. 132-151

4 Claims

1. A comb, comprising:
an elongated hollow frame having front and rear walls and fixed end members for defining a hollow interior in said frame, said hollow interior having an elongated opening at the bottom thereof;
elongated means being disposed at least partially within said hollow interior in overlying engagement with the inside surface of said front and rear walls for closing the bottom


opening in said frame and having a series of spaced-apart transversely extending openings;
a series of axially rotatable rod-like teeth having enlarged head and cylindrical body portions and disposed individually with their body portions within said openings and extending from said elongated means out of said hollow interior through the bottom opening thereof, said teeth receiving openings in said elongated means being larger in cross-sectional area than the cross-sectional area of said



4,295,481
CONVERTIBLE SUN SHADE
Charles E. Gee, 1481 Russell Dr. N., St. Petersburg, Fla. 33710
Filed Jul. 18, 1977, Ser. No. 816,339
Int. Cl.³ E04F 10/10

U.S. Cl. 135-5 R

11 Claims



1. A self-supporting sun shade, comprising:
a U-shaped support member having the bottom portion of the U as a rearward support for the shade and the legs of the U being forwardly positioned;
a pair of upright support members, one pivotally mounted on each of said legs of said U-shaped member, proximate to said bottom portion of the U;
a canopy pivotally mounted between said upright support members, on the upper ends thereof, for shielding sunlight from the region between said legs of said U-shaped member;
said pivotal mounting for said canopy to said upright support member, further comprising:
said upright support member being a hollow tubular structure;
a shaft rigidly mounted to said canopy and passing through a hole in the side of said upright support member;
a substantially U-shaped, resilient clamping member within

said hollow tubular structure at the upper end of, having two legs, one on each side of said shaft; a screw passing through the side of said upright support member and through a first one of said legs of said clamp and threadably engaging a second one of said legs of said clamp, for tightening said clamp about said shaft; a cap sealably engaging said upper end of said hollow tubular structure for protecting said clamping member from environmental elements; whereby said canopy can be locked into a fixed position with respect to said upright support member.

4,295,482


VALANCE SUPPORT

Harold F. McMullen, 5009 E. Colonial Dr., Apt. 14, Tampa, Fla. 33611

Filed Mar. 31, 1980, Ser. No. 135,773
Int. Cl.³ A45F 3/52; A47C 29/00

U.S. Cl. 135—8

11 Claims



1. A valance support for supporting a corner drapery from a ceiling, comprising in combination:
a first side portion;
a second side portion disposed at substantially right angles to said first side portion;
a first arm connected to said first side portion;
a second arm connected to said second side portion;
a valance gusset disposed in the upper corner formed by said first side portion and said second side portion;
means for hanging the corner drapery from said first and second side portions and said first and second arms; and
means for securing said valance support to the ceiling.

4,295,483

CRUTCH-MOUNTED ACCESSORY POUCH

Samuel W. Smith, P.O. Box 317, Anthony, Fla. 32617


Filed Dec. 26, 1979, Ser. No. 106,007
Int. Cl.³ A61H 3/02

U.S. Cl. 135—66

2 Claims

1. In combination a pouch means and a Y-type crutch having two separate upright side members, with said pouch means comprising a fabric envelope body means fitting around a central portion of said crutch means, and with said pouch means comprising a fitted bottom closure means extending the width of the lower portion of said pouch means and the distance between the said upright side members of the said crutch

means, and said pouch means comprising a central cavity within said side member means of said crutch means and said



fabric envelope body means whereby small articles may be transported therewithin without loss.

4,295,484


FRANGIBLE CONNECTOR FOR SELF-CLOSING BREAKAWAY VALVE ASSEMBLIES OR SIMILAR STRUCTURES

Daniel T. Meisenheimer, Jr., 404 Longmeadow Rd., Orange, Conn. 06477

Filed Aug. 22, 1980, Ser. No. 181,386
Int. Cl.³ F16K 17/40

U.S. Cl. 137—68 R

11 Claims



1. A frangible connector for frangibly connecting the first and second housings of a self-closing breakaway valve assembly or the like, the frangible connector comprising:

(A) a first clamping ring and a second clamping ring secured together by frangible means, the first and second clamping rings together defining a radially outwardly opening peripheral channel;

(B) A first attachment sleeve received over the first clamping ring and having an intumed flange received in the radially outwardly opening peripheral channel, the first attachment sleeve being adapted for attachment to the first housing of the self-closing breakaway valve assembly; and

(C) a second flanged attachment sleeve received over the second clamping ring and having an intumed flange received in the radially outwardly opening peripheral channel and a radially outwardly protruding flange, whereby the flanged attachment sleeve is free for rotation relative to the clamping rings and the first attachment sleeve, the flanged attachment sleeve being threaded for attachment to the second housing of the self-closing breakaway assembly;

whereby the clamping rings capture and clamp the attachment sleeves together and the flanged attachment sleeve may be

rotated by means of its radially protruding flange to thread it into the second housing of the self-closing breakaway valve assembly, thereby drawing the second housing into assembled relationship with the first housing without rotating the first housing so that a desired angular orientation between the first and second housings may be established.

4,295,485

LOW COST, DIFFUSER CONCEALABLE, VOLUME CONTROL, HEAT RESPONSIVE, RESETTABLE, BUTTERFLY DAMPER OPERATOR

Francis J. McCabe, Doylestown, Pa., assignor to Prefco Products, Inc., Buckingham, Pa.


Continuation-in-part of Ser. No. 900,620, Apr. 27, 1978, Pat. No. 4,263,930, which is a continuation-in-part of Ser. No. 896,299, Apr. 14, 1978, Pat. No. 4,195,384, Ser. No. 896,237, Apr. 14, 1978, Pat. No. 4,219,041, Ser. No. 792,525, May 2, 1977, Pat. No. 4,146,048, and Ser. No. 764,774, Feb. 2, 1977, Pat. No. 4,113,230, which is a continuation of Ser. No. 689,994, May 26, 1976, Pat. No. 4,081,173, said Ser. No. 896,299, is a continuation-in-part of Ser. No. 779,044, Mar. 18, 1977, Pat. No. 4,099,292, which is a continuation-in-part of Ser. No. 676,483, Apr. 13, 1976, Pat. No. 4,041,570, and Ser. No. 676,413, Apr. 13, 1976, Pat. No. 4,040,304. This application Sep. 21, 1979, Ser. No. 77,583

The portion of the term of this patent subsequent to Apr. 28, 1998, has been disclaimed.

Int. Cl.³ F16K 17/38

U.S. Cl. 137—80

30 Claims



4,295,485


DIAPHRAGM VALVE

Timothy O. W. Waterfield, Chandler's Ford, England, assignor to Waterfield Engineering Limited, Hampshire, England
Division of Ser. No. 900,393, Apr. 26, 1978, abandoned. This application Dec. 12, 1979, Ser. No. 102,791

Int. Cl.³ F16K 7/16

U.S. Cl. 137—74

a cleanout member mounted on the body and extending into a portion of said annular orifice; and,



means for rotating the orifice means whereby said cleanout member can traverse the full length of said annular orifice to dislodge any debris collected in said annular orifice.

4,295,488

DIAPHRAGM AND BALL VALVE



Harold M. Book, P.O. Box 323, 15876 Beechwood Rd., Findlay, Ohio 45840

Filed Feb. 9, 1979, Ser. No. 10,692

Int. Cl.³ F16K 31/18, 33/00

U.S. Cl. 137—414

28 Claims



1. A liquid flow valve comprising:

- (A) an adjacent inlet and outlet,
- (B) a diaphragm for simultaneously opening and closing said adjacent inlet and outlet on one side of said diaphragm,
- (C) a substantially conical chamber on the other side of said diaphragm having an inlet duct continuously open at all times to said adjacent inlet regardless of the opening and closing of said adjacent inlet and outlet of said diaphragm, said open inlet duct normally pressurizing said chamber

- for causing said diaphragm to close said adjacent inlet and outlet, said chamber having a valved outlet at its apex,
 - (D) a freely movable ball in said chamber movable by the flow of the liquid through said conical chamber for directing and maintaining said freely movable ball adjacent said apex of said conical chamber at all times and for normally closing said valved outlet from said chamber when not obstructed by external means, and
 - (E) external means for moving said ball from said valved outlet to reduce the pressure in said conical chamber from said inlet duct to permit said diaphragm to be moved by said adjacent inlet pressure to open said valve by opening said adjacent inlet and outlet.
6. A valve according to claim 1 wherein said external means comprises a float and lever mechanism.

4,295,489

PILOT-OPERATED BACK PRESSURE REGULATOR


Roger R. Arends; Wayne B. Bailey, both of Marshalltown; John W. Duffy, Tama, and Brice D. Springer, Marshalltown, all of Iowa, assignors to Fisher Controls Company, Inc., Marshalltown, Iowa

Filed Oct. 3, 1979, Ser. No. 81,587

Int. Cl.³ F16K 31/365

U.S. Cl. 137—488

2 Claims



1. A pilot-operated back pressure regulator comprising:

- (a) A regulator body having an inlet and an outlet, a valve seat located between said inlet and outlet and a valve plug guide above said valve seat;
- (b) a pressure balanced valve plug within said valve plug guide adjacent to said valve seat and movable reciprocally toward and away from said valve seat, said valve plug being ported at the end thereof remote from the end which seats on said valve seat;
- (c) an actuator having a flexible diaphragm forming a spring cavity and a lower cavity within said actuator, said spring cavity containing a spring for closing said valve plug against said valve seat and said lower cavity accepting said ported portion of said valve plug;
- (d) said valve plug being directly attached to said diaphragm such that flexure of said diaphragm operates said valve plug to open or close said back pressure regulator by moving said valve plug away from or toward, respectively, said valve seat;
- (e) a plurality of bolts securing said actuator to said regulator body whereby removal of said plurality of bolts allows simultaneous removal of said actuator and said valve plug from said regulator body; and
- (f) a pilot valve in communication with the inlet pressure, with said spring cavity, and with an exhaust whereby said pilot valve operates said actuator.

4,295,490

MILKING APPARATUS


Archie E. Boudreau, P.O. Box 1125, Modesto, Calif. 95353
Division of Ser. No. 906,425, May 16, 1978, Pat. No. 4,198,999.

This application Aug. 9, 1979, Ser. No. 65,172

Int. Cl.³ F16K 11/10

U.S. Cl. 137—595

14 Claims



1. A vacuum control valve system including:

- a valve system body which defines a first vacuum conduit communicating with a source of vacuum, and a first atmospheric conduit communicating with the atmosphere;
- said valve system body further defining a second vacuum conduit and a second atmospheric conduit;
- said first and second vacuum conduits defined by said body being out of fluid communication with said first and second atmospheric conduits defined by said body;
- a first valve means for selectively providing communication between the first and second vacuum conduits;
- a second valve means for selectively providing communication between the first and second atmospheric conduits;
- a third valve means;
- said valve system body defining a third vacuum conduit provided in communication with the third valve means and communicating with the source of vacuum and a third atmospheric conduit provided in communication with the third valve means and communicating with the atmosphere;
- a fourth conduit for providing communication between the third valve means and the first valve means and a fifth conduit for providing communication between the third valve means and the second valve means;
- wherein the third valve means has a first mode for providing communication between the fourth conduit and the third atmospheric conduit and between the fifth conduit and the third vacuum conduit; and
- wherein the third valve means has a second mode for providing communication between the fourth conduit and the third vacuum conduit, and between the fifth conduit and the third atmospheric conduit.

4,295,491

DOUBLE ANGLED-DISC DIVERter VALVE OR THE LIKE

Tod R. Galloway, Menasha, Wis., assignor to Fox Valley Process Systems & Supply, Inc., Menasha, Wis.

Filed May 15, 1980, Ser. No. 150,085

Int. Cl.³ F16K 11/02


U.S. Cl. 137—625.46

5 Claims

1. A double angled-disc valve comprising:

- a valve body defining a substantially straight through

passage and a substantially straight branch passage substantially perpendicular to the through passage; a single valve stem at least partially within the valve body, said valve stem having a longitudinal axis at substantially a 45° angle relative to both passages and being reciprocally rotatable about its longitudinal axis;



and a pair of valve discs fixed to the valve stem at angles of substantially 45° relative to the longitudinal axis of the stem, each disc being disposed in a respective one of the passages and being actuable between parallel open and perpendicular closed positions with respect thereto, rotation of the valve stem about its longitudinal axis causing simultaneous actuation of the discs.

4,295,492

LOW COST ACCUMULATOR DEVICE


Abdus Zahid, Los Angeles, Calif., assignor to Greer Hydraulics, Incorporated, Chatsworth, Calif.

Filed Nov. 13, 1979, Ser. No. 93,624

Int. Cl.³ F16L 55/04

U.S. Cl. 138—30

4 Claims



- 1. An accumulator device including a pressure vessel having an oil port at one end, and a gas charging port at the other end, and a resilient elastomeric bladder therein and dividing the same into two chambers in communication, respectively, with said oil and said gas ports, said pressure vessel being of a two part construction and comprising a generally cylindrical shell having a closed end carrying said oil port and having an open mouth portion, an upwardly directed annular trough member surrounding said mouth portion, said trough including a floor, a cylindrical skirt surrounding said trough, a circular cap member carrying said gas charging port mounted in said open mouth portion of said shell, said cap member including a downwardly facing surrounding annular trough member having a depending peripheral annular lip, said cylindrical skirt being spun inwardly over the trough defining portions of said cap member whereby said annular lip of said cap is biased into engagement with said floor of said upwardly directed trough member, said trough members together defining an annular chamber having an annular opening directed toward the inte-

rior of said vessel, said bladder assembly including a thickened rim portion maintained in compressed condition within said annular chamber and providing a seal between said cap and the open mouth portion of said shell, said bladder having side wall portions extending through said annular opening into the interior of said shell.

4,295,493

DRAG BALL VALVE INCLUDING VARIABLE PRESSURE REDUCING MEANS


Roger Bey, Illzach, France, assignor to The Babcock & Wilcox Company, New Orleans, La.

Division of Ser. No. 26,625, Apr. 2, 1979, Pat. No. 4,271,866. This application Jan. 18, 1980, Ser. No. 113,148

Int. Cl.³ F16K 5/06; F15D 1/02

U.S. Cl. 138—43

1 Claim



1. A variable fluid pressure reducing device comprising a plurality of fixed disks having apertures therein and a plurality of rotatable disks having apertures therein with means for diverting fluid passing therethrough, each of said rotatable disks being interposed between adjacent fixed disks, said diverting means in one or more of said rotatable disks being aligned with said apertures in said fixed disks adjacent said one or more of said rotatable disks causing a pressure reduction in said fluid passing therethrough when said one or more of said rotatable disks is rotated through a predetermined angle.

4,295,494

METHOD AND APPARATUS FOR PLUGGING AND CUTTING A GAS LINE OR THE LIKE WITHOUT EXCAVATION


John B. McGowan, and John Trimble, both of Malvern, Pa., assignors to UMAC, Inc., Paoli, Pa. and Brooklyn Union Gas Company, Brooklyn, N.Y., a part interest to each

Filed Jul. 16, 1979, Ser. No. 57,626

Int. Cl.³ B22D 19/10

U.S. Cl. 138—89

13 Claims



1. A method of sealing an underground pipeline or the like at or near the point where it connects to a main without excavation to obtain access to the pipe, comprising the steps of:

obtaining access to the underground pipe at a point beyond where it exits the earth;

mounting a thermally stabilized cross-linked preshrunk plug on a heater element, said heater element being mounted on a flexible elongate shaft having a diameter less than the diameter of the pipe, said shaft having sufficient rigidity to push said heating element through said line and sufficient flexibility to bend with curves in the line, said shaft being provided with electrical conductors passing longitudinally therethrough;

inserting said plug into said underground pipeline by feeding said flexible elongate shaft with said heater element mounted thereon into said underground pipeline;

positioning said plug into said line at or near said main by feeding said elongate flexible shaft into said line;

energizing said heating element by applying electrical energy to said electrical conductors causing said preshrunk cross-linked plug to expand to its cross-linked condition sealing said pipe; and

withdrawing said heater element and said shaft.

4,295,495

CONNECTION NIPPLE

Friedrich Rosemeier, Hechingen, and Horst Killmaier, Hechingen-Boll, both of Fed. Rep. of Germany, assignors to Gambio Dialysatoren GmbH & Co. KG., Fed. Rep. of Germany


Filed Sep. 11, 1979, Ser. No. 74,499

Claims priority, application Sweden, Sep. 13, 1978, 7809625

Int. Cl.³ F16L 55/10

U.S. Cl. 138—89

29 Claims



1. A connection nipple for providing fluid communication with the interior of a container, the connection nipple comprising:

a hollow member having a first open end and a second open end, the first open end being adapted to be sealingly disposed in fluid communication with the interior of the container, and the second open end being disposed exteriorly of the container;

a circumferential rib member internally disposed about the circumference of said hollow member, said rib member having a cross-sectional shape which tapers to substantially a point to define a connection line about the circumference of said hollow member, said connection line being axially spaced from said second open end of said hollow member;

a releasable sealing member integrally connected to said rib member in proximity to said connection line and sealingly surrounding said second open end of said hollow member to completely enclose and seal said second open end;

said releasable sealing member being disconnectable from said hollow member to provide access to said second open end by breaking said releasable sealing member substantially along said connection line; and

said circumferential rib member extending laterally outward from the surface of said hollow member a distance sufficient so as to provide a support surface for a finger grip when said releasable sealing member is to be disconnected from said hollow member and thereafter.

4,295,496

HOSE WITH INTERNAL INSERT MEMBER


Guy T. Bixby, Longmont, Colo., assignor to The Gates Rubber Company, Denver, Colo.

Filed Feb. 19, 1980, Ser. No. 122,784

Int. Cl.³ F16L 11/00, 9/00

U.S. Cl. 138—122

25 Claims U.S. Cl. 139—196.2



1. In a hose having an elongated polymeric body and a coiled insert member formed of a plurality of turns and positioned in the internal passageway of the hose body, said hose body having a tendency to swell during use under conditions of elevated temperature or pressure, the improvement comprising:

a filamentary annular band integral with the polymeric body and which extends generally circumferentially of the body, having filaments resistant to expansion at elevated temperature or pressure, the band having a width substantially less than that of the hose body and being positioned between at least two adjacent turns of the coiled insert member.

4,295,497

VARIEGATED STIRRUP MAT


Wilbur E. Tolliver, 364 Hamilton Dr., Holland, Mich. 49423

Filed May 4, 1979, Ser. No. 36,170

Int. Cl.³ F16L 55/00; B21F 27/20

U.S. Cl. 138—175

13 Claims



1. A concrete pipe comprising at least one cylindrical steel wire reinforcing cage, and concrete surrounding said cage, said cage including an additional reinforcing stirrup mat located in the area of the crown thereof and another located in the area of the invert thereof, each of said mats having lateral edges and a lateral center area and wherein stirrup projections project from each mat, said mats being defined by a network of interconnected wires, the improvement in said concrete pipe comprising: said cylindrical reinforcing cage being elliptical in lateral cross section and said stirrup projections being formed from steel and being taller in the lateral center area of said mat than towards the lateral edges thereof so as to concentrate more steel in the lateral center area of the mat than towards the lateral edges of the mat.

4,295,498



GRIPPER SHUTTLES

Charles D. Davis, Charlotte, N.C., assignor to Armstrong World Industries, Inc., Lancaster, Pa.

Filed Apr. 28, 1980, Ser. No. 144,418

Int. Cl.³ D03J 5/06

3 Claims



1. In a gripper shuttle for picking weft threads in a weaving machine, said shuttle comprising a tubular housing substantially oblong in transverse cross-section and having a closed front end and an open trailing end, a gripper clamp mounted within said housing and having means positioned even with or in close proximity to the opening in the trailing end of said housing for gripping a weft thread, the improvement comprising a nose on said housing having an arcuate front end edge surface with a centrally located recess therein, said recess being so dimensioned as to preclude contact between the front end edge surface of said shuttle and the weft thread gripping means of a similar shuttle when the front and rear ends of the shuttles contact each other in the same plane.

4,295,499

DETECTION OF WFT IN SHUTTLELESS LOOM

Hajime Suzuki, Anjo, and Yoshimi Iwano, Ohbu, both of Japan, assignors to Kabushiki Kaisha Toyoda Jidoshokki Seisakusho, Kariya, Japan


Filed Dec. 5, 1979, Ser. No. 100,408

Claims priority, application Japan, Dec. 12, 1978, 53-152671; Dec. 12, 1978, 53-169878; Dec. 12, 1978, 53-169879

Int. Cl.³ D03D 51/34

U.S. Cl. 139—370.2

8 Claims



1. A shuttleless loom comprising:
a reed;
a plurality of guide plates arranged in spaced relationship

along said reed, said guide plates having aligned apertures forming a weft guide passage through which a weft thread is passed, said apertures of said guide plates including upper wall surfaces aligned in a plane;

slay means supporting said reed and said guide plates and mounted for pivotal movement for moving said guide plates from an operative position, whereat said guide plates are within a shed of warp threads and a weft thread is inserted through said guide passage, to an inoperative position outside of the shed, for thereby causing the weft thread to slide in a path relative to said guide plates along said upper wall surfaces until the weft thread leaves said guide passage and remains in the shed when said guide plates are moved to said inoperative position, and for allowing beating by said reed; and

means for detecting whether or not the weft thread has been inserted properly through said guide passage when said guide plates are in said operative position thereof, said detecting means comprising a detecting unit including a mounting member mounted on said slay means for movement therewith and with said guide plates, light transmitter means, mounted on said mounting member on a first side of said guide plates, for emitting a single light beam along a path in or above said plane of said aligned upper wall surfaces of said apertures in said guide plates, such that during movement of said guide plates from said operative position to said inoperative position said light beam intersects said path of the weft thread when the weft thread leaves said guide passage and when the weft thread is properly inserted through said guide passage, and light receiver means, mounted on said mounting member on a second side, opposite said first side, of said guide plates, for receiving said single light beam from said light transmitter means.

4,295,500


METHOD OF AND A DEVICE FOR FORMING AN ADDITIONAL STREAM OF AIR IN A GUIDE COMB OF AN AIR JET LOOM

Vladimir Svaty, Liberec, Czechoslovakia, assignor to Zbrojovka Vsetin, Vsetin, Czechoslovakia

Filed Dec. 17, 1979, Ser. No. 104,393
Int. Cl.³ D03D 47/30

U.S. Cl. 139—435

2 Claims



1. In the method of operating an air jet loom having a guide comb, a reed, and means for forming a weft inserting supporting air stream which supplements a main weft supporting air stream in the guide comb, the improvement comprising directing a stream of air via at least one nozzle through said reed; and deflecting said stream of air to thereby direct it into the weft inserting direction in said guide comb.

4,295,501

SPACER BAR AND RELATED METHOD FOR CONCRETE PIPE MANUFACTURE


Wilbur E. Tolliver, 364 Hamilton Dr., Holland, Mich. 49423

Filed Jul. 11, 1979, Ser. No. 56,602

Int. Cl.³ B21F 3/00

U.S. Cl. 140—92.1

25 Claims



1. A method for spacing a generally cylindrical reinforcing wire cage from a concrete pipe form, said cage including generally circumferentially oriented wire reinforcement and generally longitudinally oriented wire reinforcement, said method comprising the steps of:

providing a plurality of spacer bars, each spacer bar having a tie rod and a plurality of links joined to and spaced along the length of said tie rod generally parallel to one another; positioning said links along said tie rod; securing said spacer bars to said cage at spaced points around the circumference thereof with said links projecting generally radially therefrom; locating said cage within said pipe form with said links of said spacer bars engaging said form to hold said cage in properly spaced relationship with respect to said pipe form.

4,295,502

METHOD AND APPARATUS FOR THE ELIMINATION OF FOAM ABOVE THE LEVEL OF A LIQUID, AND PARTICULARLY ABOVE A PACKAGED LIQUID SUCH AS MILK

Erwin Matzner, Krefeld, Fed. Rep. of Germany, assignor to Jagenberg Werke AG, Dusseldorf, Fed. Rep. of Germany


Filed Oct. 23, 1979, Ser. No. 87,358

Claims priority, application Fed. Rep. of Germany, Jul. 4, 1979, 2926955

Int. Cl.³ B65B 3/04

U.S. Cl. 141—11

20 Claims



1. A method for the elimination of foam above the level of a liquid in a container comprising collapsing the foam by applying ultrasonic waves to the foam indirectly through the ambient atmosphere.

4,295,503

AUTOMATIC GLASS FRAGMENTATION DECONTAMINATING SYSTEM FOR GLASS CONTAINERS

Alfred J. Gilmour, Waterloo, Canada, assignor to Auto-Flush Systems Ltd., Waterloo, Canada


Filed Dec. 12, 1979, Ser. No. 102,691

Claims priority, application Canada, Mar. 22, 1979, 323993

Int. Cl.³ B65B 3/04; B08B 3/02

U.S. Cl. 141—90

16 Claims



1. In a bottle filling machine in which bottles travel a path from an infeed mechanism to an outfeed mechanism during filling under pressure by a plurality of bottle filling tube mechanisms and in which a bottle may explode due to said pressure, causing glass particles to adhere to its associated filler mechanism, apparatus for cleansing said filler tube mechanisms a plurality of times comprising a broken bottle sensor located between said infeed mechanism and said outfeed mechanism which, in the event of a broken bottle, provides a pulse to activate, for a predetermined period of time, a water spray assembly comprising a plurality of high pressure spray nozzles spaced apart along a portion of said path between said sensor and said outfeed mechanism, said pulse also feeding logic means to record a data bit to indicate each filling tube mechanism associated with a broken bottle, to track the location of said filling tube mechanisms as they move along said path, and to re-activate said spray for said predetermined period of time when each said filling tube mechanism again reaches said sensor.

4,295,504

GASOLINE VAPOR RECOVERY SYSTEM


Detlev E. M. Hasselmann, 519 S. Nardo Ave., Solana Beach, Calif. 92075

Filed Dec. 26, 1979, Ser. No. 106,676

Int. Cl.³ B65B 3/04; B67C 5/377

U.S. Cl. 141—290

5 Claims



1. Gasoline Vapor Recovery System comprising: a gasoline storage tank; a pump coupled to said storage tank; a gasoline dispenser; a first hose coupled at one end to said dispensers;

means said coupling said first hose through said dispenser to said pump; a nozzle on the other end of said first hose; a vapor sealing means on said nozzle for forming a vapor seal around an opening in a receptacle into which gasoline is being pumped through said nozzle; a vapor recovery conduit extending from said nozzle to of said storage tank, said conduit having a rigid portion which is connected to said storage tank and a hose portion which is connected to said nozzle; a valve in said vapor recovery conduit, said valve being positioned in said dispenser between the end of said first hose coupled to said dispenser and said pump; means for opening said valve in response to predetermined conditions to allow gasoline vapors to flow from said receptacle; said vapor sealing means comprises a resilient boot on said nozzle and spring means for resiliently urging the boot away from said nozzle, said spring having a force/deflection ratio in the range of 2 to 7 pounds per inch of deflection.

4,295,505

GASOLINE VAPOR RECOVERY SYSTEM


Detlev E. M. Hasselmann, 519 S. Nardo Ave., Solana Beach, Calif. 92075, and Paul D. Labonte, 9371 Fermi Ave., San Diego, Calif. 92123

Filed Dec. 26, 1979, Ser. No. 106,668

Int. Cl.³ B65B 3/04

U.S. Cl. 141—301

5 Claims



1. A gasoline vapor recovery system comprising: a gasoline storage tank; a gasoline pump coupled to said storage tank; a gasoline dispenser; a vapor recovery nozzle; a gasoline delivery conduit extending from said gasoline pump, through said gasoline dispenser, and terminating in said vapor recovery nozzle; means on the end of said vapor recovery nozzle for covering the opening in a receptacle in which gasoline is to be pumped; a vapor recovery conduit extending from said vapor recovery nozzle to said gasoline storage tank; a pressure responsive valve in said vapor recovery conduit, said valve being positioned below said dispenser; a flow sensor coupled to said gasoline delivery conduit above the lowest level of said dispenser; and conduits coupling said flow sensor to said pressure responsive valve to open said pressure responsive valve when gasoline flows through said flow sensor.

4,295,506 WEDGE


William H. Nicholson, Sutton, Mass., assignor to Norman S. Blodgett, Worcester, Mass.

Continuation of Ser. No. 947,258, Sep. 29, 1978, abandoned. This application Nov. 26, 1979, Ser. No. 97,450

Int. Cl.³ B27L 7/00

U.S. Cl. 144—193 D

10 Claims



1. Wedge for splitting a wooden log, comprising:

- (a) a main body having two plane face surfaces lying at an acute angle to one another, and terminating at a lower end of the wedge,
- (b) two plane blade surfaces extending from the lower ends of said face surfaces said blade surfaces lying at an acute secondary angle to one another and terminating in a transverse edge, said secondary angle being substantially greater than the angle between said face surfaces, and
- (c) an integral point bounded by two plane surfaces which are continuous with and lie in the respective planes of said face surfaces and extend beyond said transverse edge to assist in introducing the edge into the grain of the log.

4,295,507

LIMBING AND BARKING DEVICE

Einar Karlsson, 1208 Abyn, Burträsk, Sweden (S-937 00)


Filed Dec. 14, 1979, Ser. No. 103,943

Claims priority, application Sweden, Dec. 21, 1978, 7813195

Int. Cl.³ B27L 1/00

U.S. Cl. 144—208 B

4 Claims



1. Apparatus for delimbing and barking trees or tree parts comprising a downwardly tapering trough for receiving the trees or tree parts, said trough having a generally horizontal axis and having one side formed by upwardly and outwardly inclined endless conveyor means which includes drivers projecting therefrom for circulating the trees or tree parts in the trough and for transporting wood upwardly; at least one elongated delimbing roll arranged parallel to the axis of the trough at the bottom thereof, said roll being adjacent the lower end of said conveyor means and rotatable in a direction such that its upper surface rotates toward said conveyor means; and at least one elongated barking roll arranged in side-by-side parallel relationship to said delimbing roll on the side thereof opposite said conveyor means and rotatable in a direction such that its upper surface rotates toward said delimbing roll, said barking roll having longitudinally extending planar peripheral ribs for orienting the stems of the trees or tree parts into parallelism with the barking and delimbing rolls.

4,295,508

FLEXIBLE GARBAGE CAN LID


Harold L. Metzger, 1402 Fredericksburg Rd., San Antonio, Tex. 78201

Filed Apr. 18, 1980, Ser. No. 141,288

Int. Cl.³ B65D 65/02; B65B 11/00

U.S. Cl. 150—52 R

1 Claim



1. In a garbage can lid formed of flexible material, a peripheral flange on said lid, a strap integral with said flange and having means for releasably anchoring the lid on the can, said strap being of flexible material and said means for maintaining said strap in holding position on the lid when the lid is mounted on the can consists of integral rigid terminals on the respective ends of said strap, and a hook pivotally mounted on one terminal and an eye for receiving the free end of said hook mounted on the other terminal.

4,295,509

EMERGENCY TRACK RING FOR PNEUMATIC VEHICLE TIRES

Hermann Stein, Wuppertal-Barmen, Fed. Rep. of Germany, assignor to Vorwerk & Sohn GmbH & Co. KG., Wuppertal-Barmen, Fed. Rep. of Germany


Filed Nov. 26, 1979, Ser. No. 97,414

Claims priority, application Fed. Rep. of Germany, Nov. 27, 1978, 2851187

Int. Cl.³ B60C 17/04

U.S. Cl. 152—158

10 Claims



1. An emergency track ring for a tubeless pneumatic tire adapted to be mounted on a tire rim, comprising

- (a) a bottom reinforced flange for mounting the ring on such rim,
- (b) at least one opening in said ring to permit air to be admitted to the interior of the tire,
- (c) groove means formed in said ring adapted to be filled with a lubricating material,
- (d) sealing lips closing said groove means and sealing said lubricant therein when said tire is mounted on said rim and under pressure,

flange means integrally formed with said sealing lips and extending radially upwardly with respect to said sealing

lips for engagement by the inside of the tire cover during loss of air, said sealing lips and flange means being formed and arranged such that when said flange means are depressed, lever action causes said sealing lips to move so as to open said grooves and permit said lubricating material to be released to reduce friction between said tire cover and said track ring.

4,295,510

PROTECTIVE TIRE CHAIN ASSEMBLY

Garth Foxcroft, Wynberg, South Africa, assignor to Dirk Marinus Brink, White River, South Africa


Filed Jun. 29, 1979, Ser. No. 53,224

Claims priority, application South Africa, Jul. 7, 1978, 78/3906

Int. Cl.³ B60C 27/22, 27/20

U.S. Cl. 152—220

10 Claims



1. A tire chain assembly comprising a tire chain having an endless central belt region composed of wear accepting links with connecting links interconnecting said wear accepting links, and having sidewall protecting extensions along the edges of the central belt region and wherein the spaces between the links of the chain are, at least partly, occupied by a wear resistant elastomeric material such that the combination of the material and tire chain form said central belt region having the wear accepting links extending through substantially the entire thickness of such belt region, the tire chain being adapted to be removably located over a tire of suitable size.

4,295,511

RADIAL TIRES PROVIDED WITH A STIFFENING STRUCTURE IN THE SIDEWALLS

Mario Mezzanotte, Milan, and Gianni Turchetti, Bresso, both of Italy, assignors to Societa Pneumatici Pirelli S.p.A., Milan, Italy

Filed Apr. 1, 1980, Ser. No. 136,352


Claims priority, application Italy, Apr. 10, 1979, 21708 A79

Int. Cl.³ B60C 9/06

U.S. Cl. 152—354 R

10 Claims

1. A pneumatic tire for vehicle wheels comprising a radial carcass provided with beads for assembly with a corresponding rim, a tread, and an annular reinforcing structure inserted between the carcass and tread, said annular reinforcing structure being substantially inextensible and having a width which is at least as wide as the tread, said carcass comprising at least one ply of textile or metallic cords lying in substantially radial planes and extending from one bead to another, and turned-up from the inside towards the outside of the tire, around a bead-core contained in each bead, said tire being characterized in that it comprises in each sidewall, a mixed textile-metallic reinforcement member comprising a strip of textile cords doubled over to provide two skirts having different widths, the cords of said skirts being inclined with respect to the radial direction of the carcass cord, and by a strip of metallic cords inclined with respect to said radial direction and narrower than the longer skirt inserted between said skirts to the folded-edge



to a point disposed in the sidewall, to a height between 66% and 20% of the tire's section height, said metallic cord strip extending from the folded edge of said textile strip to a point situated at a height between 50% and 20% of the section height of the tire.

4,295,512

THICK-CORD LIGHTWEIGHT TIRE BODY HAVING AN IMPROVED FATIGUE LIFE

Yasuyosi Kawaguchi, Higashiyamato; Munetoshi Shimotake, Kodaira, and Fujio Yamamoto, Kodaira, all of Japan, assignors to Bridgestone Tire Company Limited, Tokyo, Japan

Filed Sep. 4, 1980, Ser. No. 183,900

Claims priority, application Japan, Sep. 4, 1979, 54-112366

Int. Cl.³ B60C 9/06, 15/06

U.S. Cl. 152—354 R

3 Claims



1. A thick-cord lightweight tire body having an improved fatigue life, comprising a bias-structured carcass composed of rubberized plies each including thick organic fiber cords having a cord diameter equal to or larger than Nylon 1,890 d/2 and rubber interposed between said carcass plies and having a thickness corresponding to $hm/ho \leq 0.5$ where hm is an average rubber gauge between said plies at a center position in the widthwise direction of the tire and ho is a diameter of said thick cord, said rubber being a rubber composition consisting essentially of 100 parts by weight of a rubber component and 50-70 parts by weight of carbon black, said rubber component being a mixture of 60-95 parts by weight of at least one rubber selected from the group consisting of natural rubber, synthetic polyisoprene rubber, polybutadiene rubber and styrene-butadi-

ene copolymer rubber and 5-40 parts by weight of at least one liquid polymer selected from the group consisting of liquid polybutadiene, liquid polyisoprene and liquid styrene-butadiene copolymer and having a viscosity-average molecular weight of 3×10^4 - 10×10^4 , said rubber composition having a dynamic modulus of elasticity at 100° C. under 2% elongation of not less than 6.0×10^7 dyne/cm², a dynamic loss angle $\tan \delta$ of not more than 0.095 and a tensile strength of not less than 100 kg/cm² as properties after vulcanization and, an apex rubber for stiffening a turnout portion of said carcass wherein a ratio in the dynamic modulus of elasticity of said apex rubber to said rubber interposed between the plies is within a range of 0.9-1.3.

4,295,513

TIRE AND METHOD OF REINFORCEMENT


John A. Lovell, Munroe Falls, and Kenneth W. McIntosh, Cuyahoga Falls, both of Ohio, assignors to The Goodyear Tire & Rubber Company, Akron, Ohio

Filed Apr. 11, 1980, Ser. No. 139,411

Int. Cl.³ B60C 9/02

U.S. Cl. 152-358

17 Claims



1. A tire comprising an annular body of elastomeric material having a U-shaped cross section, an annular reinforcing sheet of tubular knit material stretchable into a toroidal configuration for placement in a mold and said reinforcing sheet being under tension in a molded and cured tire.

4,295,514

BIFOLD DOOR HINGE ASSEMBLY

Larry K. Johnson, Sterling, Ill., assignor to Lawrence Brothers, Inc., Sterling, Ill.


Continuation of Ser. No. 910,106, May 30, 1978, abandoned.

This application Nov. 14, 1979, Ser. No. 94,289

Int. Cl.³ E06B 3/00; E05D 7/10

U.S. Cl. 160-206

4 Claims



1. In combination, a bifold door assembly comprising: a pivoted door and a guide door, mounted such that they will be in substantially co-planar relation in the closed condition and at least one hinge assembly interconnecting said doors along a vertical edge thereof, aperture means formed in the upper and lower horizontal edge surfaces of said pivoted door at a predetermined distance from the vertical edge of said door to be disposed adjacent a door frame, said aperture means adapted to

receive pivot means for the pivotal mounting of said door, and aperture means formed in the upper and lower horizontal edge surfaces of said guide door at a predetermined distance from the vertical edge thereof remote from said pivoted door for the receipt of guide means to be disposed in horizontal linear track means to confine said edge for linear movement upon opening and closing of said assembly, the respective predetermined distances providing for the spacing of said aperture means from the said door edges being substantially equal, and said at least one hinge assembly including first and second interconnected leaf members each leaf member including a planar portion affixed to corresponding side surfaces of the pivoted and guide doors and each leaf member further including knuckle means, which knuckle means are disposed coaxially, said leaf members being mounted with said knuckle means offset from the interface of the respective door edges in a direction toward said pivot door, such that when said doors are in the mounted, fully open condition, said guide door will be disposed at an obtuse angle with respect to the associated track means, which facilitates closing movement, said obtuse disposition being attained with the use of door panels with identically positioned aperture means.

4,295,515

AUTOMATIC CONE AND MOLD-MAKING MACHINE


William L. Tordoff, Worthington, Ohio, assignor to Ashland Oil, Inc., Ashland, Ky.

Filed Mar. 20, 1980, Ser. No. 131,915

Int. Cl.³ B22C 11/04, 13/14, 17/12

U.S. Cl. 164-158

7 Claims



1. A no-bake molding machine comprising, a base, a generally circular frame mounted for rotation on said base, a plurality of concave patterns mounted around the circumference of said frame, plate means surrounding said patterns and extending around the perimeter of said frame to form with said patterns a substantially flush, flat, continuous surface around the top of said frame surrounding said concave patterns, means for continuously rotating said frame, a mixer for filler located adjacent said frame and having a discharge spout overlying said patterns and continuous surface, said mixer and filler mixing sand with a no-bake binder and depositing sand and binder on said patterns and continuous surface, and a stationary plow adjacent the mixer and filler engaging said plate means for scraping excess sand off said surface and leveling the sand in each pattern as it passes under said plow.

4,295,516

SYMMETRICAL HORIZONTAL CONTINUOUS CASTING

Robert Wilson, Dundee, Scotland, assignor to Timex Corporation, Waterbury, Conn.

Continuation-in-part of Ser. No. 958,774, Nov. 8, 1978, Pat. No. 4,216,818. This application Dec. 7, 1979, Ser. No. 101,389

Int. Cl.³ B22D 11/124, 11/00

U.S. Cl. 164-464



16 Claims

1. In a horizontal continuous casting process wherein molten

metal is continuously passed through a mold body having a substantially horizontal solidification chamber extending interiorly along the length thereof with an inlet end for receiving molten metal from a source and an outlet end through which solidified metal exits, the steps of:

- providing a plurality of cooling bores in the mold body spaced around the periphery of the solidification chamber from the bottom to the top thereof, each cooling bore having an open end on the outlet end of the mold body and extending toward the inlet end to define a peripheral cooling section adjacent said outlet end; and
- inserting an elongated cooling probe into the open end of each cooling bore to provide cooling to said peripheral cooling section with the cooling probe insertion distance into the bores increasing from the bottom to the top of the mold body such that a liquid/solid solidification front which intersects the top and bottom of said chamber at approximately the same location along its length is established in the molten metal, whereby hot tears, fissures and other surface defects resulting from asymmetric solidification of the bottom portion of molten metal ahead of the top portion are reduced.

8. A mold assembly for horizontally continuously casting molten metal comprising:



- a mold body having a substantially horizontal solidification chamber therethrough with an inlet end for receiving molten metal from a molten metal source and an outlet end through which solidified metal exits and having a plurality of longitudinal cooling bores spaced around the solidification chamber from the bottom to the top thereof, the cooling bores each having an open end on the outlet end of the mold body and extending only partially therethrough toward the inlet end to define an insulating section adjacent said inlet end to minimize heat removal from said molten metal source and a peripheral cooling section adjacent said outlet end, and
- a plurality of elongated cooling probes each of which is inserted into the open end of a cooling bore to provide cooling to said peripheral cooling section with the cooling probe insertion distance into the bores increasing from the bottom to the top of the mold so that a liquid/solid solidification front which intersects the top and bottom of said chamber at approximately the same location along its length is established in the molten metal, whereby hot tears, fissures and other surface defects resulting from asymmetric solidification of the bottom portion of molten metal ahead of the top portion are reduced.

4,295,517

REUSABLE HEAT DEVICES CONTAINING XYLITOL AS THE HEAT-STORAGE MATERIAL

Woldemar Guex, 4 Spechtweg, Bottmingen; Heinrich Klaue, 77 Kilchgrundstrasse, Riehen; Horst Pauling, 39 Ruchholzstrasse, Bottmingen, and Felix Voirol, 26 Poolstrasse, Füllinsdorf, all of Switzerland

Division of Ser. No. 916,424, Jun. 16, 1978, abandoned. This application May 20, 1980, Ser. No. 152,056

Int. Cl.³ F28D 21/00

U.S. Cl. 165-1

6 Claims

- A method for providing a source of heat which comprises
 - adding, as a heat storage material, xylitol to a container;
 - heating the xylitol in the container to a temperature above its melting point;
 - cooling the resulting melt to a temperature below the melting point of xylitol without crystallizing the xylitol and
 - initiating crystallization of the xylitol
 whereby the release of the heat of crystallization of xylitol provides a source of heat.

4,295,518

COMBINED AIR CYCLE HEAT PUMP AND REFRIGERATION SYSTEM


George C. Rannenberg, Canton, Conn., assignor to United Technologies Corporation, Hartford, Conn.

Filed Jun. 1, 1979, Ser. No. 44,840

Int. Cl.³ F25B 13/00

U.S. Cl. 165-2

11 Claims



1. A combined air cycle heat pump and refrigeration system for a load comprising:

- a source of low pressure refrigerant air at essentially ambient pressure, said refrigerant air being ambient air when said system is operating in the heat pump mode and being air returned from said load when said system is operating in the refrigeration mode;
- a turbine driven compressor receiving said refrigerant air and increasing the temperature and pressure thereof;
- means for conducting said compressed refrigerant air to said turbine for expansion therein and discharge therefrom whereby said refrigerant air is reduced in temperature;
- means for conducting the refrigerant air discharged from said turbine directly to the ambient when said system is operating in the heat pump mode, and for conducting the refrigerant air discharged from said turbine directly to said load when said system is operating in the refrigeration mode;
- a regenerative heat exchanger connecting through heat transfer surfaces within said regenerative heat exchanger the source of low pressure refrigerant air with the compressed refrigerant air upstream of said turbine whereby said compressed refrigerant air rejects some of its heat to said low pressure refrigerant air from said source and reduces the temperature of the compressed refrigerant air fed to said turbine so as to maximize the reduction in the temperature of the refrigerant air discharged from said turbine;
- additional heat exchange means downstream of said com-

pressor and upstream of said regenerative heat exchanger on the high pressure side thereof, said compressed refrigerant air passing through said additional heat exchange means;

an additional fluid, said fluid being fluid returned from said load when said system is operating in the heat pump mode and said fluid being ambient air when said system is operating in the refrigeration mode;

means for passing said fluid through said additional heat exchange means in heat exchange relation with said compressed refrigerant air whereby said fluid absorbs heat from said compressed refrigerant air;

and means for returning said fluid to supply heat to said load when said system is operating in the heat pump mode and returning said fluid to ambient when said system is operating in the refrigeration mode.

4,295,519

HEAT RECLAIMER


Leslie Bellaff, 416 Windsor Rd., River Edge, N.J. 07661

Filed Nov. 13, 1979, Ser. No. 93,873

Int. Cl.³ F28F 19/00

U.S. Cl. 165—11 R

18 Claims



1. A heat reclaimer for the exhaust flue of a heating unit comprising: a housing having an air input space, an air output space and an exhaust space; tube means connected between and communicating said air input and output spaces, extending through said exhaust space; the exhaust flue of the heating unit connected to said housing and into said exhaust space; an exhaust output connected to said housing and into said exhaust space for venting exhaust coming from the heating unit through the exhaust flue, out of said exhaust space; and a level switch connected to said housing at a location spaced from the top of said exhaust space activated if water accumulates in said exhaust space from condensed water vapor in the exhaust; said housing having at least one hole therethrough communicating with said exhaust space in the vicinity of the level of said level switch for draining water in said exhaust space rising to the level of said hole.

4,295,520

HEAT TRANSFER SYSTEM

Helmut Wulf, Ostfildern, Fed. Rep. of Germany, assignor to Daimler-Benz Aktiengesellschaft, Stuttgart, Fed. Rep. of Germany

Filed Jul. 10, 1979, Ser. No. 56,234

Claims priority, application Fed. Rep. of Germany, Sep. 8, 1978, 2834838

Int. Cl.³ F28D 15/00; B60H 1/04

U.S. Cl. 165—41

24 Claims

23. A heat pipe arrangement comprising a bundle of elastically deformable small tubes extending essentially parallel to

one another and being operatively connected to each other so as to permit relative movement therebetween, at least one adjoining heat pipe means for accommodating one end of each of the tubes, each of said tubes is constructed as a heat pipe which is sealed toward the outside and open toward an interior



of at least one adjoining heat pipe means so as to enable vapor produced in a heat-emitting zone to flow inside of the respective tubes into a heat-consuming zone and condensate produced in the heat-consuming zone to return inside of the respective tubes to the heat-emitting zone.

4,295,521


HEAT EXCHANGER CORE MOUNTING APPARATUS
Mark F. Sommars, Sparland, Ill., assignor to Caterpillar Tractor Co., Peoria, Ill.

Continuation of Ser. No. 99,143, Sep. 27, 1979, abandoned. This application Aug. 15, 1980, Ser. No. 178,278

Int. Cl.³ F28F 9/26

U.S. Cl. 165—59

7 Claims



1. A heat exchanger comprising: first and second frame members (12, 12a) each having a bore (42) therein;

a core (16) extending between the frame members (12, 12a) and having first and second opposed end portions (38, 40), each end portion having a spout (52) extending outwardly into the bore (42) of the adjacent frame member (12, 12a);

resilient means (36) for resiliently and sealingly supporting the core (16) between the frame members (12, 12a), said resilient means including a pair of resilient pads (54, 56) each positioned between one of the end portions (38, 40) and the adjacent frame member (12, 12a); and

means (24) for locating the core (16) in a predetermined registration with the frame members (12, 12a), said means (24) including an imperforate protuberance (34) extending outwardly from one of said first end portions (38) and said first frame member (12) and spaced from the spout (52), and an imperforate recess (32) in the other of said first end portion (38) and said first frame member (12) and being in registry with the protuberance (34), said one resilient pad (54) positioned between said first end portion (38) and said

first frame member (12) having a portion (62) resiliently accommodating the protuberance (34) and the recess (32).

4,295,522

PROCESS FOR THE PRODUCTION OF A TUBULAR HEAT EXCHANGER, AND A TUBULAR HEAT EXCHANGER PRODUCED ACCORDING TO THIS PROCESS

Willi Frei, Zilstrasse 16, CH-9016, St. Gallen, Switzerland

Filed Aug. 2, 1978, Ser. No. 930,363

Claims priority, application Fed. Rep. of Germany, Aug. 3, 1977, 2734958

Int. Cl.³ F28F 9/16

U.S. Cl. 165—79

3 Claims



1. A heat exchanger comprising a housing, at least one tube bundle disposed in said housing, each tube bundle containing a plurality of substantially parallel tubes, the opposite end portions and a substantially intermediate portion of said tubes being disposed in troughs containing a plurality of holes for receiving said tube end portions, said troughs containing a solidified casting resin which extends into annular gaps between the holes and the tube end portions, a substantially horizontal flange being fixed to the inside of said housing, a lowermost trough resting on said flange and said tube bundle cooperating with the housing so that a gap is formed between the sidewalls of the troughs and the housing, said gap also containing the casting resin.

4,295,523


WELL SAFETY SYSTEM METHOD AND APPARATUS
James D. Mott, Houston, Tex., assignor to Hydril Company, Houston, Tex.

Division of Ser. No. 2,197, Jan. 9, 1979. This application Dec. 12, 1979, Ser. No. 102,913

Int. Cl.³ E21B 43/10

U.S. Cl. 166—250

1 Claim



1. A method of operably installing in a single trip a well safety system having a full opening remote controlled subsurface safety valve in the well, including the steps of: connecting a subsurface tubing hanger in a string of well tubing; connecting the full opening remote controlled subsurface safety valve in the well tubing above the subsurface tubing hanger; connecting a full-strength safety joint in the well tubing

above the full opening remote controlled subsurface safety valve;

connecting a predetermined amount of well tubing above the subsurface safety valve while moving the subsurface safety valve in the well;

mounting a wellhead hanger above the predetermined amount of well tubing;

positioning the wellhead hanger a predetermined distance above the wellhead;

determining the weight supported by the wellhead hanger when positioned the predetermined distance above the wellhead;

setting the subsurface tubing hanger in the well for supporting the string of well tubing below the subsurface tubing hanger;

lowering the wellhead hanger into the wellhead;

determining the weight supported by the wellhead hanger while lowering the wellhead hanger into the wellhead;

comparing the weight supported determinations to develop a sufficient difference to indicate the subsurface tubing hanger is supporting the portion of the well tubing suspended therefrom;

activating the safety joint to reduce the strength of the safety joint; and

operating the subsurface safety valve to enable flow through the well tubing.

4,295,524

ISOLATION GRAVEL PACKER


Eugene E. Baker, and David D. Szarka, both of Duncan, Okla., assignors to Halliburton Company, Duncan, Okla.

Filed Dec. 27, 1979, Ser. No. 107,739

Int. Cl.³ E21B 43/04

U.S. Cl. 166—278

57 Claims



1. A well treatment apparatus of a type to be disposed within a conduit in a well bore, in fluid communication with first and second tubing means, said apparatus comprising: treatment means containing first and second passage means, check valve means, and third passage means; said first passage means in fluid communication with said first tubing means above said treatment means and with the bore of said conduit below said treatment means; said second passage means in fluid communication with said second tubing means above said treatment means and with the annulus between said treatment means and said conduit; said check valve means being disposed in said first passage means; and said third passage means being longitudinally fixed and in

fluid communication with said annular and with said first passage means above said check valve means.

38. A method of gravel packing a producing zone in a well bore, comprising:

- (a) placing a conduit having a gravel screen therein in said well bore, said gravel screen being positioned across said zone;
- (b) pumping a gravel slurry down first tubing means to a location above said zone;
- (c) routing said gravel slurry outside said conduit and down to the level of said gravel screen;
- (d) arresting the flow of said gravel with said screen while allowing the slurry carrier fluid to pass therethrough;
- (e) returning said carrier fluid to the surface via second tubing means;
- (f) continuing steps (d) and (e) until a gravel pack is effected;
- (g) pumping fluid down said second tubing means to the vicinity of said zone and returning said fluid to the surface via said first tubing means without inducing fluid movement within the conduit bore area defined by the top and bottom of said gravel screen.

4,295,525

METHOD AND APPARATUS FOR QUICK REPLACEMENT OF CARTRIDGE FILTERS USED IN WELL FLUID CLEANING OPERATIONS

Edward R. Swift, Jr., Houston, and Philip W. Schmuck, Spring, both of Tex., assignors to Baker International Corporation, Orange, Calif.

Filed Feb. 6, 1980, Ser. No. 118,958

Int. Cl.³ B01D 27/00, 27/08, 29/10; E21B 43/00

U.S. Cl. 166—312

4 Claims



1. In an apparatus for treating and removing contaminate particulate matter from fluid circutable into, through and out of a subterranean well, the improvement comprising: a cylindrical housing adapted to receive and discharge said fluid; means disposed across said cylindrical housing for separating said cylindrical housing into a first fluid chamber for receiving fluid to be filtered and a second fluid chamber for receiving filtered fluid; at least one cartridge filter adapter receiving means disposed through said separating means; a cartridge filter adapter secured within each of said receiving means, said adapter having an elongated cylindrical housing, and having a fluid flow passageway therethrough communicable to each of said first and second fluid chambers, said elongated cylindrical housing having an enlarged cartridge positioning portion extending radially away from and about the axis of said elongated cylindrical housing, said cartridge positioning portion having first and second faces thereon; groove means on said adapter circumferentially extending around the exterior of said elongated cylindrical housing for sealingly securing one end of said cartridge filter thereon; cartridge filter means positionable on

said adapter and extending within said first fluid chamber; and seal means disposed at one end of said cartridge filter and having an interiorly facing circumferentially extending flexible lip for contact with the exterior of said elongated cylindrical housing upon location of said cartridge filter on said adapter, said lip being sealingly securable within said groove.

4. A method for treating and removing contaminate particulate matter from fluid circutable into, through and out of a subterranean well, comprising the steps of: (1) establishing a fluid flow path into, through and out of said well; (2) circulating fluid in said flow path; (3) introducing said circulated fluid into at least one filtering vessel, said vessel comprising: a cylindrical housing adapted to receive and discharge said fluid; means disposed across said vessel for separating said vessel into a first fluid chamber for receiving fluid to be filtered from said well and a second fluid chamber for receiving filtered fluid for subsequent circulation into said well; at least one cartridge filter adapter receiving means disposed through said separating means; a cartridge filter adapter secured within each of said receiving means, said adapter having an elongated cylindrical housing and having a fluid flow passageway therethrough communicable to each of said first and second fluid chambers, said elongated cylindrical housing having an enlarged cartridge positioning portion extending radially away from and about the axis of said elongated cylindrical housing, said cartridge positioning portion having first and second faces thereon; groove means on said adapter circumferentially extending around the exterior of said elongated cylindrical housing for sealingly securing one end of said cartridge filter thereon; cartridge filter means positionable on said adapter and extending within said first fluid chamber; and seal means disposed at one end of said cartridge filter and having an interiorly facing circumferentially extending flexible lip for contact with the exterior of said elongated cylindrical housing upon location of said cartridge filter on said adapter, said lip being sealingly securable within said groove; and (4) circulating into said well fluid discharged from said second chamber of said vessel.

4,295,526

METHOD AND APPARATUS FOR CONNECTING STEEL PIPE SECTIONS

Ernest D. Hawk, Yucca Valley, and Larry Stewart, Joshua Tree, both of Calif., assignors to Service Equipment Design Co., Inc., Signal Hill, Calif.


Filed Feb. 21, 1979, Ser. No. 13,671

Int. Cl.³ E21B 43/10; B23P 19/04; B23Q 3/00; F16L 21/04
U.S. Cl. 166—315

15 Claims

1. A method of forming a casing string in a well, comprising:
 - (a) providing a plurality of sections of casing pipe having a predetermined outer diameter,
 - (b) introducing one such section into the well hole,
 - (c) providing a joint ring formed of strong and elastic material,
 - said joint ring having an inner diameter sufficiently smaller than said predetermined outer diameter of said pipe sections that entry of opposed ends of said pipe sections into said ring will expand said ring and thus cause it to frictionally grip said ends very tightly,
 - (d) providing a clasp means adapted to hold said joint ring and also adapted to receive and align the ends of said pipe sections whereby said ends may enter properly the opposite sides of said ring,
 - (e) placing said joint ring in said clasp means, and introducing the ends of said one casing section and a second casing section into said clasp means to thus cause said ends to be in coaxial relationship with said clasp means and coaxially aligned with each other,
 - (f) applying large axial forces to said coaxially-aligned pipe sections to cause said ends thereof to be forced into said

- ring and to be frictionally gripped therein while said ring is thus held in said clasp means,
- (g) removing said clasp means, and



- (h) repeating said steps (b) through (g) with additional ones of said joint rings and casing sections until the casing string has attained the desired length.

4,295,527

PROCESS AND DEVICE FOR THE CENTERING OF CASINGS AS USED FOR UNDERGROUND DRILLING

Rolf A. Rüsse, Celle, Fed. Rep. of Germany


Filed Apr. 9, 1979, Ser. No. 28,007

Claims priority, application Fed. Rep. of Germany, Apr. 12, 1978, 2815705


Int. Cl.³ B25B 1/20; E21B 19/16

U.S. Cl. 166—315

12 Claims



to project radially beyond said housing; a camming sleeve axially slidably mounted within said housing and having a series of axially spaced, external cylindrical cam surfaces selectively engagable with the inner surfaces of said dogs, said cam surfaces increasing in diameter downwardly, whereby relative upward movement of said camming sleeve will radially shift the locking dog ends successively from a fully retracted position, to a partially projecting no-go position, and then to a fully projecting locking position, the effective maximum diameter of said locking dog ends in said no-go position being greater than



said internal shoulder diameter but less than the conduit bore diameter; resilient means urging said camming sleeve upwardly, the top portions of said camming sleeve defining a plurality of peripherally spaced, resilient fingers having enlarged end portions; said enlarged finger end portions being arranged for detachable engagement by a running tool to successively shift the vertical position of said camming sleeve relative to said locking dogs from said fully retracted position, to said partially retracted position and then to said fully projecting position upon successive relative upward movements of said running tool.

4,295,529

BLOW-OUT PREVENTOR


William N. Strickland, 210 Tudor St., Houma, La. 70360

Filed Nov. 8, 1979, Ser. No. 92,573

Int. Cl.³ E21B 21/10, 34/08

U.S. Cl. 166—325

9 Claims



1. A blow out preventor assembly for attachment to the drill stem placed within the drill casing during well drilling operations comprising:

- a. a bottom seal assembly having attachment means for slideably attaching said bottom seal assembly to a section

of drill stem, which has been placed during drilling operations within a section of drill casing, said bottom seal assembly flow opening area allowing fluids to flow thereby and providing an upper valve closure surface;

- b. a first lower seat ring having an inner opening corresponding to the sectional configuration of the drill stem and providing an attachment opening for affixing said seat ring to the drill stem, said lower seat ring disallowing downward movement to said bottom seal assembly with respect to the drill stem;
- c. port-ring means slideably attachable to the drill stem and having an outer diameter substantially equal to the inside diameter of the drill casing, for forming a flow closure between said drill stem and the drill casing with said port-ring having at least one flow opening allowing fluid to pass thereby and a valve seat at said opening; and
- d. a second uppermost seat ring having an inner opening corresponding to the sectional configuration of the drill stem and providing an attachment opening for affixing said seat ring to said drill stem, said port-ring means resting upon said second uppermost seat ring, said second ring preventing downward movement of said port-ring means with respect to the drill stem.

4,295,530

LOWER LINK DRAFT SENSING SYSTEM ON TRACTOR
Herbert E. Ashfield; Harry Horsfall, and Philip M. Wade, all of Huddersfield, England, assignors to David Brown Tractors Limited, Huddersfield, England


Filed Mar. 24, 1980, Ser. No. 133,190

Claims priority, application United Kingdom, Mar. 30, 1979, 11309/79

Int. Cl.² A01B 63/112

U.S. Cl. 172—7

6 Claims



1. A lower link draft sensing system, on an agricultural tractor having a hydraulic power lift mechanism, comprising two bowed rearwardly-extending leaf springs anchored to the tractor frame at their front ends and adapted to elongate in a rearward direction when under tension, two laterally-spaced arms pivotally connected at their upper ends to the tractor frame and universally connected at their lower ends to a cross-bar secured between the rear ends of the respective springs, two lower hitch links universally connected at their front ends to points on the cross-bar which points are laterally offset from said arms, a laterally-extending unstressed summing bar universally connected at its ends to the respective arms and disposed in parallel relationship to the cross-bar, and a draft signal transmitting member actuated by the summing bar at a point between the ends of said bar and adapted to control automatically the power lift mechanism by way of linkage.

4,295,531

AUGER-EQUIPPED PLOW


Hubert E. Strickland, 2205 Ardmore Ave., Chesapeake, Va. 23324

Filed Nov. 5, 1979, Ser. No. 91,652

Int. Cl.³ A01B 33/04; B62D 51/04

U.S. Cl. 172—42

3 Claims



1. A mechanically driven ground working implement comprising:

- (a) a horizontally disposed rigid elongated framework,
- (b) front and rear wheels rotatably mounted on said framework adjacent the opposite extremities thereof, said wheels provided with peripherally mounted projections which interact with the ground to provide traction for said implement,
- (c) a pair of control handles attached to said framework and extending upwardly and rearwardly therefrom in symmetrically opposed relationship,
- (d) a power source in the form of a fuel-powered engine mounted on said framework between said wheels,
- (e) drive means extending downwardly from said power source,
- (f) forwardly and substantially horizontally directed auger means pendantly supported by said framework said auger means being comprised of a center core and spiralled blade member having an outer edge, the rearward extremity of said auger means being engaged by said drive means,
- (g) means to adjust the elevation of said auger means, and
- (h) a truncated hollow V-shaped plowshare supported by said framework in a disposition closely above said auger means, said plowshare having an inside surface and a forward end,
- (i) the forward end of said auger protruding in front of the forward end of said plowshare,
- (j) the outer edge of said blade member being adjustably located between about 1" and 4" from the inside surface of said plowshare, and the lowermost portion of said outer edge being at a level adjacent the lowermost portion of said plowshare.

4,295,532

PLANTER WITH COOPERATING TRASH CLEARING DISCS

Donald E. Williams; Forrest E. Robertson; C. Dean Gigot, and Terry K. Gigot, all of Garden City, Kans., assignors to Acra-Plant, Inc., Garden City, Kans.

Filed Nov. 2, 1979, Ser. No. 90,790

Int. Cl.³ A01C 5/06


U.S. Cl. 172—184

9 Claims

1. In a farm implement having a furrow-opening tool thereon, an attachment for moving debris outwardly in opposite directions ahead of said tool, said attachment including:

- a pair of side-by-side convex-concavo discs having sharpened, circular peripheries adapted to penetrate the soil and disposed with their convex faces back to back, at least one of the discs being peripherally notched; a support between the discs and common thereto; and means for each disc respectively rotatably mounting the same on the support with the discs converging relatively

toward the normal path of travel of said support and with notched disc leading the other disc,



the discs being relatively overlapped at their zones of convergence and overlapping said path of travel at their zones of convergence.

4,295,533

PNEUMATICALLY OPERATED RAM BORER

Paul Schmidt, P.O.B. 20, 5940 Lennestadt/Saalhausen, Fed. Rep. of Germany


Filed Mar. 13, 1980, Ser. No. 129,835

Claims priority, application Fed. Rep. of Germany, Mar. 26, 1979 2911837

Int. Cl.³ E21B 11/02

U.S. Cl. 175—19

7 Claims



1. In a self-driven pneumatically operated ram borer, said ram borer including a tubular casing, a hose connected to said tubular casing for the supply of compressed air thereto, a percussion piston axially slidably mounted in said casing for reciprocating motion therein, means defining control ports in said piston, a control tube extending into said piston for controlling said reciprocating motion of said piston by opening and closing said control ports, means movably mounting said control tube and control means for moving said control tube between a first position in which said piston is caused to move so that it drives said borer forwards and a second position in which said piston is caused to move so that it drives said borer rearwardly, the improvement wherein said control means comprises elongate flexible actuating means extending through the inside of said hose into said casing, said flexible actuating means being coextensive with and extending within said hose to a location remote from said tubular casing, means connecting said flexible actuating means to said control tube, and said flexible actuating means being rotatable relative to said hose and having a cross-sectional area smaller than the cross-sectional area within said hose so that compressed air can flow through said hose for operating said ram borer.

4,295,534

WELL BORING RIGS AND SPOIL HANDLING CONVEYOR APPARATUS THEREFOR

Thomas R. Zachmeier, Box 131, Mandan, N. Dak. 58554

Filed Mar. 29, 1979, Ser. No. 25,026

Int. Cl.³ E21B 21/06


U.S. Cl. 175—88

8 Claims

1. In an apparatus for boring holes in the earth, the apparatus including:

- (1) rotary boring means for boring a hole;
- (2) means for introducing drilling fluid to the boring area;
- (3) fixed wall structure surrounding the boring means for receiving spoil laden drilling fluid from a hole being

- bored, the wall structure having an opening for discharging the spoil-laden fluid, and
- (4) continuous conveyor means having an inlet end located at the opening in the wall structure for receiving the discharged spoil-laden drilling fluid;



the improvement wherein the conveyor comprises



(5) a plurality of V-type conveyor belts defining a conveyor working surface, the belts being arranged in side-by-side yet spaced apart relationship for allowing drilling fluid to drain therebetween while the belts carry the spoil away.

4,295,535

IN-HOLE MOTOR DRILL WITH LOCKING BIT CLUTCH
Gary M. Crase, Cypress, and Kurt M. Trzeciak, Irvine, both of Calif., assignors to Smith International, Inc., Newport Beach, Calif.

Filed Aug. 20, 1979, Ser. No. 68,212
Int. Cl.³ E21B 3/12

U.S. Cl. 175—101



1. An in-hole motor assembly adapted for connection with a rotatable pipe string and a bit, said assembly comprising: a motor stator including a housing structure connectable at one end to a pipe string; a rotor in said stator connected at one end to a shaft for rotation therewith and extending at the other end of said shaft from said housing for connection to a drill bit;


thrust bearing between said shaft and said housing structure to transmit thrust from said housing to said shaft; a clutch engageable between said shaft and said housing to couple said housing structure and shaft for mutual rotation and a lock holding said clutch against disengagement on application of thrust between said housing and said shaft.

4,295,536 PRESSURE SEAL FOR PUMPING INSTRUMENTS THROUGH DRILL ROD

Emrys H. Jones, Jr., Westover, W. Va., and Stephen D. Lauer, Waynesburg, Pa., assignors to Conoco Inc., Ponca City, Okla.
Filed Sep. 28, 1979, Ser. No. 80,352
Int. Cl.³ E21B 47/12

U.S. Cl. 175—214

2 Claims



16 Claims

1. In a system for taking surveys of borehole conditions in a generally horizontal borehole being drilled, said system comprising a drill rod, a survey probe in the drill rod adapted to be pumped through the drill rod and retrieved by reeling in a cable attached to the probe, a pump for pumping fluid through the drill rod to force the survey probe therethrough, a rotary motor between the pump and the drill rod, and a pipe extending from the rotary motor in alignment with the drill string; the improvement wherein a sealing device positioned between said pipe and said drill rod is provided, said sealing device comprising:

- a housing having a central flow passage therethrough and an enlarged recessed opening in each end therethrough, said housing being of split construction and having two half sections;
- a first seal in one end of said housing adapted to sealingly engage said drill rod when pressed thereagainst;
- a second seal in the other end of said housing adapted to sealingly engage said pipe when pressed thereagainst;
- an instrument cable entrance opening extending from outside said housing to said flow passage, said opening being bisected by the connecting plane of said two half sections, said opening being at an acute angle with respect to said flow passage; and
- packing means in said opening allowing movement of an instrument cable therethrough and preventing leakage therefrom.


4,295,537
SPONGE MEASURING DEVICE
James D. McAvinn, Chicago; Arthur R. Meister, Park Ridge, and Samuel M. Tucker, Barrington, all of Ill., assignors to The Kendall Company, Boston, Mass.

Filed Mar. 21, 1980, Ser. No. 132,585
Int. Cl.³ G01G 19/40, 13/14, 19/52, 21/22; A47F 7/08
U.S. Cl. 177—15

18 Claims

1. A device for measuring sponges, comprising: measuring means for indicating the weight of an applied object;

means operatively applied to the measuring means for retaining a plurality of wetted sponges; and



electronic means operatively associated with the measuring means for determining the total weight of liquid in said retained sponges.


4,295,538 AUXILIARY POWER SYSTEM FOR AUTOMOTIVE VEHICLE

Alexander J. Lewus, 9844 N. 11th Ave., Phoenix, Ariz. 85021
Continuation of Ser. No. 926,373, Jul. 20, 1978, abandoned, which is a continuation of Ser. No. 812,528, Jul. 5, 1977, abandoned, which is a continuation of Ser. No. 633,825, Nov. 20, 1975, abandoned, which is a continuation-in-part of Ser. No. 453,293, Mar. 21, 1974, Pat. No. 3,921,746. This application Sep. 17, 1979, Ser. No. 76,081

The portion of the term of this patent subsequent to Nov. 25, 1992, has been disclaimed.
Int. Cl.³ B60K 25/10

U.S. Cl. 180—165

5 Claims




1. A suspension and auxiliary power system for a vehicle having a frame, a power consuming load on said frame, and at least one supporting wheel adapted to move vertically relative to said frame, said system comprising: a fluid pump including a housing adapted to be connected to one of said frame and said wheel and a reciprocal piston adapted to be connected to the other of said frame and said wheel, said housing and piston forming at least one fluid pumping chamber whose volume is expanded and contracted by vertical movement between said frame and said wheel; a uni-directional fluid motor; said motor adapted to drive said power consuming load; and fluid circuit

means connecting said chamber to said motor said circuit means including a first check valve for directing fluid only from said chamber directly to said motor and a second check valve for directing fluid only from a source of fluid to said chamber, whereby said pump acts as a fluid suspension system, supporting at least a part of the weight of said vehicle on said one wheel, and whereby the loading on said motor of said power consuming load causes said motor to act as a shock absorber to said pump.

4,295,539
AUXILIARY DRIVE SYSTEM
Richard A. Beck, West Lafayette, and Glen T. Presley, Angola, both of Ind., assignors to Parno Corporation, Brookston, Ind.
Filed Dec. 5, 1979, Ser. No. 100,426
Int. Cl.³ B60K 25/04

U.S. Cl. 180—243

11 Claims



1. A hydraulic auxiliary drive system for the normally non-driven wheels of a vehicle in assistance with the main drive wheels, comprising:

- at least one variable displacement motor having a tiltable swash plate driving at least one of said non-driven wheels;
- a variable displacement pressure compensated pump supplying the motor with a constant pressure regardless of the vehicle speed;
- spring means biasing each motor swash plate toward zero displacement;
- servo means connected to the motor swash plate for varying displacement of the motor;
- a pressure source supplying the servo means;
- a manually operated pressure control means including a solenoid-controlled variable orifice controlling the pressure level supplied to the servo means to vary the torque output of the normally non-driven wheels; and
- control valve means positioned between the pump and motor for disengaging and reversing the auxiliary drive.

5. A hydraulic auxiliary drive system for the normally non-driven wheels of a vehicle in assistance with the main drive wheels, comprising:

- at least one variable displacement motor having a tiltable swash plate, said motor driving at least one of said non-driven wheels;
- a variable displacement pressure compensated pump having a preset compensating level supplying the motor with a constant pressure regardless of the vehicle speed;
- spring means biasing each motor swash plate toward zero displacement;
- a first servo means connected to the motor swash plate for increasing the motor displacement;
- a second servo means connected to the motor swash plate for decreasing the motor displacement;
- a pressure source connected to said first servo means;
- a sensing passage connecting the pump outlet with the second servo means;
- a pressure operated valve means located in said sensing passage having a first position blocking pump pressure to

the second servo means at all pressure levels above the pressure compensating level of said pump, and a second position opening pump pressure to the second servo means at a preset pressure level below said pressure compensating level of said pump whereby when said pump reaches full stroke and is unable to maintain its pressure compensating level, the pressure operated valve means opens the second servo means to pump pressure causing the motor displacement to decrease its fluid demand; and a manually operated pressure control means controlling the pressure level supplied to the first servo means to vary the torque output of the variable displacement motor.

4,295,540


VEHICLE BRAKE AND ENGINE INTERLOCK

Harold V. Hildebrecht, Cleveland, Ohio, assignor to Towmotor Corporation, Mentor, Ohio
PCT No. PCT/US79/00725, § 371 Date Sep. 14, 1979, § 102(e) Date Sep. 14, 1979, PCT Pub. No. WO81/00696, PCT Pub. Date Mar. 19, 1981

PCT Filed Sep. 14, 1979, Ser. No. 117,581
Int. Cl.³ B60K 28/00

U.S. Cl. 180—271

14 Claims



1. In a brake protection interlock system (23, 23a) for a vehicle (11, 11a) having ground engaging means (13, 13a), a brake (19, 19a), an engine (12, 12a), and drive delivery means (14, 14a) for transmitting power from said engine (12, 12a) to said ground engaging means (13, 13a), said drive delivery means (14, 14a) having a transmission (16, 16a) with at least one nondrive transmitting condition and at least one drive transmitting condition and having a clutch (18, 18a) which may be engaged and disengaged, and including first means (29, 29a) for preventing initiation of powered travel of said vehicle (11, 11a) with said brake (19, 19a) engaged by suppressing power output from said engine (12, 12a), the improvement comprising:

second means (28, 28a) for causing said first means (29, 29a) to suppress power output from said engine (12, 12a) in response to said transmission (16, 16a) being in said drive transmitting condition while both of said brake (19, 19a) and said clutch (18, 18a) are engaged, and
third means (27, 27a) for enabling starting of said engine (12, 12a) with said transmission (16, 16a) in drive transmitting condition while said brake (19, 19a) is engaged by inactivating said second means (28, 28a) in response to said clutch (18, 18a) being in disengaged condition.

4,295,541


APPARATUS FOR SUPPORTING LOADS

Richard J. Malecha, St. Louis Park, Minn., assignor to Towmotor Corporation, Mentor, Ohio
PCT No. PCT/US79/00321, § 371 Date May 14, 1979, § 102(e) Date May 14, 1979, PCT Pub. No. WO80/02550, PCT Pub. Date Nov. 27, 1980

PCT Filed May 14, 1979, Ser. No. 89,116
Int. Cl.³ G05G 1/14; 74 512; 414 635; 636

U.S. Cl. 180—315

9 Claims



1. Apparatus (10) for mounting at least one tilt cylinder (16, 18, 30) and a brake pedal (14) for controlling a brake master cylinder (42), the apparatus (10) comprising:

a frame (12) having an inboard side (12a) and an outboard side (12b);

a bracket (20) mounted on the inboard side (12a) of the frame (12) and having a bifurcated end of first (24) and second (26) spaced apart hollow ears, the first ear (24) of the bracket (20) extending to the outboard side (12b) of the frame (12);

an elongated sleeve (52 or 60 or 62) having first (52a or 60a or 62a) and second (52b or 60b or 62b) end portions and a mid-portion (52c or 60c or 62c), the first (52a or 60a or 62a) and second (52b or 60b or 62b) end portions of the sleeve (52 or 60 or 62) being supported on the frame (12) by the bracket (20);

an elongated cross pin (32) extending within the sleeve (52 or 60 or 62) and the ears (24, 26) and having a first portion (32c), a second portion (32d) and a mid-portion (32e) intermediate the first (32c) and second (32d) portions, the sleeve (52 or 60 or 62) and the cross pin (32) being constructed to be spaced apart (58, 61, 68) at the mid-portion (52c or 60c or 62c) thereof, the tilt cylinder (16, 18, 30) being rotatably mounted on the sleeve mid-portion (52c or 60c or 62c) and the brake pedal (14) being fixedly coupled to the cross pin (32);

means (38, 40, 44, 46) for coupling the cross pin (32) to the master cylinder (42); and

means (34, 36) for coupling the brake pedal (14) to the cross pin (32).

4,295,542

SEISMIC EXPLORATION WITH DISPOSABLE SEISMIC DETECTORS

H. Neal Reeves; Roy E. Burnett; Leslie R. Denham, and George E. Shields, all of Houston, Tex., assignors to Seiscom Delta Inc., Houston, Tex.

Filed Aug. 27, 1979, Ser. No. 70,241
Int. Cl.³ G01V 1/047, 1/13


U.S. Cl. 181—108

7 Claims

1. A method of seismic exploration of subsurface formations, comprising the steps of:

(a) arranging a series of shotholes along a course to be explored in a seismic line of profile above the subsurface formations;

- (b) positioning body members, each having both a seismic source and a seismic detector mounted therewith, in the series of shotholes along the course to be explored;
(c) activating one of the seismic sources in a first of the series of shotholes to emit seismic waves;
(d) detecting seismic waves from the subsurface formations with at least some of the remaining detectors located in a plurality of series of shotholes;
(e) activating another seismic source in a shothole subsequent to said step of detecting;



- (f) detecting seismic waves from the subsurface formations with the remaining detectors located in a plurality of the shotholes subsequent to said step of activating another seismic source;
(g) activating additional seismic sources in each of a series of shotholes along the seismic line of profile in a predetermined sequence; and
(h) detecting seismic waves from the subsurface waves with the remaining detectors subsequent to each step of activating.

4,295,543

FIRE ESCAPE APPARATUS


Finlay M. Graham, The Coach House, High Rocks La., Tunbridge Wells, England

Filed Feb. 6, 1980, Ser. No. 119,086

Int. Cl.³ A62B 1/20

U.S. Cl. 182—3

5 Claims



1. In a building, a fire escape apparatus comprising a vertically extending channel member secured to a wall of the building, the channel member defining a channel into which opens a vertical slot, two vertical rows of projections within the channel, each row being disposed adjacent a respective side of the slot and the projections in each row being staggered with respect to those in the other, and at least one harness support capable of being introduced into the channel through the slot and of co-operating with the projections so as to move stepwise down the channel member under the effect of the load applied to the harness support, said harness support including

a "T"-shaped member having a cross-piece surmounting an upright, the upright having a projection to which the harness is attached.

4,295,544

PLATFORM STEPLADDER


Donald J. Peterson, 2727 E. Fifth Ave., Knoxville, Tenn. 37914

Filed May 1, 1980, Ser. No. 145,475

Int. Cl.³ E06C 7/18, 1/383

U.S. Cl. 182—106

3 Claims



1. A stepladder comprising a pair of elongated front leg members pivotally attached to a front platform, a pair of elongated rear leg members pivotally attached to a rear platform, said front platform being hingedly attached to said rear platform for movement between a coplanar position and a folded position, means for releasably locking said front leg members to said front platform in a position generally perpendicular to said front platform, means for releasably locking said rear leg members to said rear platform in a position in which said rear leg members form an angle of about 110° with said rear platform, a support member pivotally attached to said front leg member and means for securing said support member in a fixed position extending generally perpendicularly upwardly from said front platform including a cylindrical section secured to one of said front legs and a hemi-cylindrical cradle section defined on said support member, adapted to receive said cylindrical section.

4,295,545

LUBRICATOR

Shoki Hiei, Aichi, Japan, assignor to Toyooki Kogyo Kabushiki Kaisha, Okazaki, Japan


Filed Dec. 4, 1979, Ser. No. 100,242

Claims priority, application Japan, Dec. 5, 1978, 53/150723

Int. Cl.³ F16N 7/34

U.S. Cl. 184—55 A

4 Claims



1. In a lubricator for a pneumatically operated device, comprising:

a housing provided at opposite sides thereof with an inlet port for connection to a source of pneumatic pressure and an outlet port for connection to said pneumatically operated device and provided therein with an air passage for

allowing the flow of compressed air between said inlet and outlet ports, said air passage including a mixture chamber formed at the inlet side thereof with a vertical flat surface wall; an oil dropping chamber provided on said housing for dropping lubricant into said mixture chamber; and a throttle valve member of elastic material having a vertical valve port pressed into contact with the vertical flat surface wall of said mixture chamber to be displaced in accordance with the flow quantity of the compressed air through said air passage; the improvement wherein the vertical valve part of said throttle valve member is provided with an orifice for permitting the compressed air flow therethrough, and a drop tube of elastic material is arranged along the vertical valve part of said throttle valve member and opens at its upper extremity into the interior of said oil dropping chamber and at its lower extremity adjacent to said orifice.

4,295,546

TORSIONAL VIBRATION DAMPERS


Eric M. Vollett, Huddersfield, England, assignor to Holset Engineering Company Limited, Huddersfield, England

Filed Oct. 2, 1979, Ser. No. 81,192

Int. Cl.³ F16F 15/16

U.S. Cl. 188—378

9 Claims



1. A torsional vibration damper comprising: an annular hub member adapted for connection to a shaft which is subject to torsional vibrations; an annular inertia member carried by and journaled for rotation relative to said hub member, at least one surface of the inertia member being in close spaced, face to face relation with at least one opposing surface of said hub member; a viscous fluid contained between said opposing surfaces so that relative movement shears the fluid to damp torsional vibrations; variable volume chamber means formed between said hub and inertia members comprising a plurality of a pair of first and second variable volume chambers whose volumes vary inversely in response to relative movement of said inertia member and said hub, said viscous liquid being contained within said variable volume chambers during operation of said damper; a pocket connected to each of said respective first and second variable volume chambers and being defined by a blind bore, each of said pockets having a gas contained therein which is pressurized by liquid from said chambers when the volume thereof is reduced; at least one of said members defining a gas reservoir radially inward from said gas pockets; first and second vent passages connecting said gas reservoir to the pockets of said first and second variable volume chambers, respectively, through the other of said members, said vent passages having restricted cross sectional flow areas; and a first gas interconnection means connecting the pockets of only said first variable volume chambers and being positioned between said pockets of said first variable volume chambers and one of said first and second vent passages; and a second gas interconnection means connecting the pockets

of only said second variable volume chambers and being positioned between said pockets of said second variable volume chambers and the other of said first and second vent passages whereby the gas pockets for each series of variable volume chambers are all interconnected, whereby a tuning effect is provided for said damper.

4,295,547

BRAKE ASSEMBLY FOR SMALL VEHICLES


D. Patrick Dungan, 901 Sherman St., #1322, Denver, Colo. 80203

Filed Mar. 31, 1980, Ser. No. 135,869

Int. Cl.³ B60T 1/04, 1/06

U.S. Cl. 188—2 R

18 Claims



1. A brake assembly for vehicles having a resilient wheel, comprising: a housing carried by the vehicle; a friction member connected to said housing and adapted to be positioned opposite a first side wall of the wheel for displacement against the wheel side wall; brake assisting means more rigid than the wheel and carried by the vehicle opposite a second side wall of the wheel for limiting the available lateral deformation of the wheel under lateral pressure from the friction member; and means for selectively activating the friction member to be displaced from the housing.

4,295,548

BRAKE ACTUATOR

Kenneth M. Quiney, Kings Heath, England, assignor to Girling Limited, Birmingham, England


Filed Nov. 29, 1979, Ser. No. 98,595

Claims priority, application United Kingdom, Dec. 9, 1978, 47852/78

Int. Cl.³ F16D 65/18

U.S. Cl. 188—72.7

12 Claims



1. A brake actuator comprising a body; first and second cam components rotatable in said body and having thereon respective helical cam tracks via which said cam components are in axial co-operative relationship with one another, said cam tracks being complementary to one another and axially confronting one another to form a helical thrust bearing; an output member axially displaceable relative to said body; a first thrust bearing axially operative between said first cam component

and said output member; a second thrust bearing axially operative between the second cam component and said body; and means for rotating both of said cam components relative to said body, the operative relationship between said cam components, said thrust member and said body being such that turning of one of said cam components relative to said body by said rotating means yields a relatively low output force at said output member and turning of the other of said cam components relative to said body, with said one cam component not rotating, yields a relatively high output force at said output member.

4,295,549

ANTI-RUST COVER FOR A DISC ROTOR OF A VEHICLE DISC BRAKE

Juichi Shibata; Kenichi Nakamura; Wataru Izuhara, and Yui-chiro Obu, all of Toyota, Japan, assignors to Toyota Jidosha Kogyo Kabushiki Kaisha, Toyota, Japan


Filed Jun. 18, 1979, Ser. No. 49,748

Claims priority, application Japan, Dec. 26, 1978, 53-178685[U]

Int. Cl.³ F16D 65/00

U.S. Cl. 188—218 A

14 Claims



1. In an anti-rusting mechanism, for a disc rotor in a vehicle disc brake, including an anti-rust cover removably attached at the outer periphery thereof to the outer periphery of a dust cover which covers the inner surface of said disc rotor integrally rotatable with a wheel, said anti-rust cover covering the outer surface of said disc rotor to envelope said disc rotor in cooperation with said dust cover, an improvement wherein said anti-rust cover is provided with a plurality of engaging members disposed, for being engaged with the outer periphery of said dust cover, on the surface faced to said disc rotor and in the vicinity of the outer periphery of said anti-rust cover with a predetermined circumferential phase difference from each other, and a plurality of projections disposed on the surface of said anti-rust cover respectively in confrontation with each of said engaging members at a nearer position to the center of said anti-rust cover than said engaging member, and at least one of said engaging members has a recess portion large enough to allow at least a part of a human finger to be held therein when said anti-rust cover is removed, and said anti-rust cover can be removably attached to said dust cover by means of allowing the outer periphery of the latter to fit snappingly between said at least one engaging member and a corresponding one of said projections at each place.

4,295,550

VISCIOUS FLUID COUPLING DEVICE

Masaharu Hayashi, Toyota, Japan, assignor to Aisin Seiki Kabushiki Kaisha, Kariya, Japan

Filed Nov. 21, 1979, Ser. No. 96,329

Claims priority, application Japan, Nov. 28, 1978, 53/147350


Int. Cl.³ F16D 35/00, 43/25

U.S. Cl. 192—58 B

4 Claims

1. A viscous fluid coupling device for controlling the revolu-

tions per minute of a radiator cooling fan in response to the temperature of an engine, said coupling device comprising: a rotor securely fixed to a shaft driven by an engine; a casing member connected with said shaft for rotation relative thereto; a cover member connected with said casing member; a labyrinth formed between projections of said rotor and projections of said casing member; a closed chamber being formed between said casing member and said cover member and containing said rotor and a quantity of operating oil; a partition plate dividing said closed chamber into an operating chamber accommodating said rotor and a reservoir



chamber storing said operating oil; a valve plate rotatably attached on said cover member; said partition plate provided in a first band of circumference thereof with first oil returning means and first pump means, and in a second band of circumference thereof with second oil returning means and second pump means, said second band being entirely radially outside said first band; thermally responsive means connected with the valve plate to control movement thereof in response to temperature to control the oil returning means and thus control the shear force between the rotor and casing member; and dam means formed between said first and second bands of circumference.

4,295,551

AUTOMATIC CLUTCH SYSTEM

Frank Zimmermann, Brunswick; Paulus Heidemeyer, and Erhard Bigalke, both of Wolfsburg, all of Fed. Rep. of Germany, assignors to Volkswagenwerk Aktiengesellschaft, Wolfsburg, Fed. Rep. of Germany

Filed Jul. 26, 1979, Ser. No. 61,059

Claims priority, application Fed. Rep. of Germany, Aug. 3, 1978, 2833961


Int. Cl.³ B60K 41/02

U.S. Cl. 192—0.076

12 Claims

1. An automatic clutch system, for use in a motor vehicle having an accelerator lever, for selectively connecting the output shaft of a vehicle engine to the input shaft of a multi-speed transmission, comprising: a clutch mechanism, responsive to supplied signals, for selectively connecting said shafts; first means for sensing the rotational speed of said engine shaft, second means for sensing the rotational speed of said transmission shaft; third means for sensing the position of said accelerator lever; and control means, responsive to said first, second and third sensing means, for developing said control signals, said control means having a first operating mode, operative when said vehicle is accelerated from a stationary condition, and wherein said control means activates said clutch mechanism

in said first mode to maintain said engine shaft speed within a selected speed range from a selected nominal engine speed



function and wherein said nominal engine speed function is determined as a function of said accelerator lever position.

4,295,552

MEANS FOR COUPLING A HAND DRIVE WITH A ROTATABLE SHAFT

Hans Erlach, Winterthur, Switzerland, assignor to Sulzer Brothers Limited, Winterthur, Switzerland


Filed Jun. 29, 1978, Ser. No. 920,287

Claims priority, application Switzerland, Jul. 15, 1977, 8831/77

Int. Cl.³ F16D 11/06

U.S. Cl. 192—81 C

27 Claims



27. A hand drive for mounting on a rotatable shaft, said drive comprising

- a sleeve mounted concentrically about a shaft to define an annular gap therewith;
- a helical spring concentrically within said sleeve and having convolutions radially biased into engagement with said sleeve;
- a pair of entraining elements rotatably mounted on opposite ends of said sleeve, each said element being entrained with an opposite end of said spring and having external teeth thereon;
- a hand wheel having a spindle passing through said sleeve;
- a pair of pinions mounted on said spindle, each pinion being in meshing engagement with a respective entraining element; and
- means for securing said sleeve to a fixed member.

4,295,553

ELECTROMAGNETIC CLUTCH

Kosaku Sayo, Katsuta; Atsushi Suginuma; Hideo Tatsumi, both of Mito, and Hisanobu Kanamaru, Katsuta, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed Jan. 3, 1980, Ser. No. 109,259

Claims priority, application Japan, Jan. 8, 1979, 54-307

Int. Cl.³ F16D 27/10

U.S. Cl. 192—84 C

11 Claims



1. In an electromagnetic clutch comprising:
 - a cylindrical rotor for introducing motive force from a drive source into the magnetic clutch formed at one end thereof with a surface for magnetic frictional engagement;
 - a motive force transmitting member located in spaced apart juxtaposed relation to said surface for magnetic frictional engagement of said cylindrical rotor and having a surface adapted to be brought into and out of magnetic frictional engagement with said surface of said cylindrical rotor;
 - a rotary shaft mechanically connected to said motive force transmitting member for rotation about an axis aligned with the axis of rotation of said cylindrical rotor;
 - energizing means including a fixed cylindrical casing, a holding member for fixedly securing said cylindrical casing in a predetermined position and a winding housed in said cylindrical casing, said energizing means being located in spaced juxtaposed relation to a surface of said end of said cylindrical rotor opposite to said surface thereof adapted to be brought into and out of magnetic frictional engagement with said motive force transmitting member, said cylindrical casing including a cylindrical outer wall and a cylindrical inner wall disposed in spaced juxtaposed relation to cylindrical walls of said cylindrical rotor and extending toward said motive force transmitting member, said cylindrical outer wall and said cylindrical inner wall each having as seen in cross section a planar surface on the side thereof which faces one of said cylindrical walls of said cylindrical rotor and a surface inclined at an acute angle with respect to said planar surface on the side of the wall which faces the winding so that the outer and inner cylindrical walls taper in the direction toward said motive power transmitting member, said motive power transmitting member being magnetically attracted into engagement with said surface of said cylindrical rotor when a current is passed to said winding to transmit motive force from said cylindrical rotor to said rotary shaft;
 - the improvement comprising a first portion of said cylindrical casing of said energizing means forming a bottom of said cylindrical casing interconnecting said cylindrical outer wall and said cylindrical inner wall at ends thereof remote from said motive force transmitting member, and a second portion of said cylindrical casing contiguous with said first portion and extending upwardly from said first portion along the cylindrical wall and beyond a portion of said inner wall which contacts with the holding member, said first portion and said second portion being substantially equal to each other and larger than other portions of the cylindrical walls of said cylindrical casing in thickness.

4,295,554

CENTRIFUGAL FRICTIONAL CLUTCH

Walter Schlagmüller, Schwieberdingen, and Rudolf Babitzka, Kirchberg, both of Fed. Rep. of Germany, assignors to Robert Bosch GmbH, Stuttgart, Fed. Rep. of Germany


Filed Aug. 16, 1979, Ser. No. 67,163

Claims priority, application Fed. Rep. of Germany, Aug. 31, 1978, 2837922; Jul. 10, 1979, 2927730

Int. Cl.³ F16D 43/14

U.S. Cl. 192—105 CE

16 Claims



1. A centrifugal frictional clutch including a housing rotatable about a first axis; a frictional member arranged about said housing concentrically with said first axis; a weight lever rotatably supported on said housing to rotate in response to a centrifugal force about a second axis radially spaced apart from said first axis; spring means supported on said housing to act on said lever against the direction of the centrifugal force; a coupling jaw rotatably supported on said weight lever for rotation about a third axis and being engageable with said frictional member, said second and third axes defining a connection line forming with the resultant normal line of action of the force of friction between said jaw and said frictional member an angle γ which corresponds to the angle of static friction between said jaw and said frictional member.

4,295,555


LIMIT SWITCH ASSEMBLY MANUFACTURING MACHINE

Lawrence J. Kamm, 2775 Kurtz St., San Diego, Calif. 92110 Division of Ser. No. 752,107, Dec. 20, 1976, Pat. No. 4,137,432, which is a division of Ser. No. 468,260, May 10, 1974, Pat. No. 3,998,316. This application Dec. 6, 1978, Ser. No. 967,059

Int. Cl.³ F16D 71/00

U.S. Cl. 192—139

2 Claims



1. A rotary motion module for imparting controlled, rotary motion to an element comprising, in combination: a rotary cylinder including a housing and a rotor, controllable drive means which, when energized, drives the rotor of the rotary cylinder, clampable module support means secured to the housing of the rotary cylinder,

an arm secured to the rotor of the rotary cylinder, limit means secured to the housing of the rotary cylinder at a predetermined position around the rotor in the path traversed by the arm when the drive means is energized, control means responsive to the arm contacting the limit means to provide a control signal indicating that the arm has contacted the limit means, and module output clamp means secured to the rotor to support the element to be moved and adapted to receive the clampable module support means of the rotary motion module, whereby a plurality of rotary motion modules may be connected in a chain to form a compound motion machine.

4,295,556

PASSENGER CONVEYOR

Cyuichi Saito, and Katsuya Teranishi, both of Katsuta, Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed Apr. 24, 1979, Ser. No. 32,756

Claims priority, application Japan, Apr. 24, 1978, 53-47746

Int. Cl.³ B65G 15/00, 9/14

U.S. Cl. 198—325

4 Claims



1. A passenger conveyor comprising a plurality of steps each including a treadboard provided with a number of cleats and grooves defined therebetween, the cleats being adapted to mesh with teeth of a comb-like plate provided at each terminal of said conveyor, and a frame to which said treadboard is secured; handrails adapted to run in synchronism with the travel of said steps; handrail frames disposed beneath said handrails; and balustrade panels, wherein said treadboard is formed of a corrugated stainless steel sheet and is reinforced by at least one reinforcement member attached to the underside of said treadboard, comb-like end pieces are attached to the leading and trailing ends of said treadboard, each end piece including a plurality of projections extending and fitted into the vacant spaces formed under said cleats of said treadboard, cleat sections extending substantially in alignment with the cleats of said treadboard, and a frame section secured to said reinforcement member, wherein said handrail frame is formed by first and second members both made of stainless steel sheets and having U-shaped cross-sections, said first and second members being welded together in back-to-back relationship so that the open side of said first member is directed toward said handrail while the open side of said second member is directed toward said balustrade panels, and wherein said comb-like end pieces are made of a colored plastic material to mark dangerous zones of the step.

4,295,557

APPARATUS AND METHOD FOR ALIGNING ELONGATED LIGNO-CELLULOSIC STRANDS INTO PARALLELISM

Roland Etzold, Mountain View, Calif.; Julius S. Impellizzeri, New York, N.Y., and Thomas W. Vaughan, Mountain View, Calif., assignors to Elmendorf Research, Inc., Palo Alto, Calif.

Filed Mar. 17, 1977, Ser. No. 778,412


Int. Cl.³ B65G 47/14

U.S. Cl. 198—382

6 Claims

1. Apparatus for orienting wood strands into parallelism comprising: a group of elongated spaced, generally parallel guide members presenting open top spaces therebetween and

defining the side boundaries for the spaces; means coupled with the guide members for moving each pair of adjacent guide members in opposite directions relative to each other and longitudinally of the spaces, said group having spaced first and second projections thereon, each first projection having an end edge extending upwardly from and substantially perpendicular to the upper margin of a corresponding guide member, each second projection having an inclined edge extending upwardly from the upper margin of a corresponding guide



member, the end edge of each first projection being operable to engage and move a wood strand in the direction of movement of the corresponding guide member, the inclined edge of each second projection defining an inclined path permitting one part of a wood strand to be raised with respect to the corresponding guide member as a function of the movement of the latter when projections of other guide members engage other parts of the wood strand, whereby strands spanning more than two guide members can be tilted, turned and moved into alignment with adjacent spaces without damage to the wood strands.

4,295,558

DEVICE FOR CONVEYING CONTAINERS

Werner Heckmann, Dortmund, Fed. Rep. of Germany, assignor to Holstein und Kappert GmbH, Dortmund, Fed. Rep. of Germany


Filed Oct. 9, 1979, Ser. No. 82,626

Claims priority, application Fed. Rep. of Germany, Dec. 13, 1978, 2853696

Int. Cl.³ B65G 47/22

U.S. Cl. 198—440

1 Claim



1. A device for conveying containers into separate paths comprising at least two conveyor wheels mounted for rotational movement and having circular recesses in their circumferential peripheries for receiving and conveying containers when said wheels are rotated, said wheels being arranged to rotate and having a location at which said wheels are arranged tangentially of each other to define a transfer region wherein a circular recess in the circumferential periphery of each conveyor wheel registers with a corresponding circular recess in the other said conveyor wheel so that a container is held in the registering recesses whereby containers can be conveyed selectively over either a main path of movement downstream from said transfer region on one of said conveyor wheels for containers to be used or a shunt path of movement downstream from said transfer region on the other one of said conveyor wheels for containers to be removed, and a pair of tongue

members located downstream of the location of tangency of said wheels in the path of containers leaving the location of tangency and each said tongue member being mounted for individual pivotal movement from a neutral position in the vicinity of said transfer region whereat said tongue members confront said containers, said pair of tongue members being supported separately from said wheels and being spring biased into the neutral position confronting oncoming containers, said tongue members comprising an elongated first tongue member and an elongated second tongue member, each said first and second tongue member having a first end arranged to contact the containers and a second end spaced out of contact with the containers with the elongated direction of said first and second tongues in the neutral position extending tangentially of said conveyor wheels at the location of tangency, the first end of first tongue member being wedge-shaped with the wedge-shaped surfaces conforming generally with the contour of said containers to engage and confine containers moving along either one of said paths to said circular recesses, the first end of said second tongue member being arranged in the neutral position in the path of the containers positioned along one of said main path and shunt path and pivoting out of the neutral position due to the contact with a container and pivoting against the spring biasing action for confining the container within the recess over a certain path of movement of the respective conveyor wheel and when the certain path of movement has been traversed said second tongue member is spring biased back into the neutral position, and a common bearing axle pivotally mounting both of said first and second tongues thereon adjacent the second ends thereof.

4,295,559

CONVEYOR SYSTEM WITH DIVERTER


Warren D. Neal, and Robert N. Nicodemus, Jr., both of Walkersville, Md., assignors to Acco Industries Inc., Trumbull, Conn.

Filed Jan. 31, 1980, Ser. No. 117,368

Int. Cl.³ B65G 47/34, 47/82

U.S. Cl. 198—598

18 Claims



1. A conveyor system comprising a conveyor having a horizontal surface upon which articles move past a given area, diverter means adjacent said area for removing said articles from the conveyor comprising a paddle member, means for mounting said paddle member for movement in an arcuate path over said conveyor to engage articles on the conveyor and remove them from the conveyor, and means for operating said last-mentioned means in a cycle, said last-mentioned means including anti-backup ratchet means operable to hold the paddle member in a predetermined position alongside the conveyor, a drive shaft, said ratchet means being mounted on said frame and operating on said drive shaft and a linear type air motor operable on the drive shaft.

4,295,560

MATERIAL HANDLING APPARATUS


Billy J. Cross, 3316 Cedar Crest, Pasadena, Tex. 77503, assignor to Billy J. Cross, Pasadena, Tex.

Continuation-in-part of Ser. No. 949,736, Oct. 10, 1978, abandoned. This application Aug. 30, 1979, Ser. No. 69,732

Int. Cl.³ B65G 65/10

U.S. Cl. 198—517

63 Claims



1. A material handling apparatus comprising: a chassis; a material conveyance surface mounted for a predetermined rate of rotation with respect to the chassis; and a loading boom having a loading device at the end thereof, the boom being mounted to but extendable from the chassis for loading material onto the material conveyance surface, and the boom being rotatable in a horizontal plane about a vertical axis which extends from the chassis and is coincident with the axis of rotation of the material conveyance surface to dispose the loading device at any angular position in a predetermined sector of the horizontal plane measured from the vertical axis.

4,295,561

CONVEYOR WITH SCRAPERS


Masaru Yasukawa, and Soji Yasukawa, both of 122, Sanmaiden-cho, Tenri-shi, Nara, Japan

Filed Jul. 18, 1977, Ser. No. 816,756

Int. Cl.³ B65G 19/28

U.S. Cl. 198—735

4 Claims



1. A conveyor disposed adjacent a machine tool comprising a plurality of interconnected chutes for transporting machining refuse, said chutes in combination comprising a channel-like vessel having upright side walls, a concave bottom extended therebetween at the lower end and a cover extended therebetween at the upper end, said cover having a plurality of spaced openings therein through which said refuse may be introduced to said chutes, supporting bases for said vessel affixed to the exterior of said concave bottom, said supporting bases including means for connecting adjacent chutes, guide means for supporting an endless chain interconnecting all of said chutes, said guide means being secured to one of said upright walls, and said guide means being a channel bar positioned about said endless chain with its opening facing downward, a plurality of spaced scrapers affixed to said endless chain for moving said refuse in said chutes, each said scraper having a configuration substantially the same as the configuration of the bottom portion of said chutes, drive means for said endless chain to continuously move it in one direction, the end faces at the interface between adjacent interconnected chutes being slanted oppositely to the advancing direction of said scrapers, underlaid

supporting bands at each end of each chute positioned to abut the underlaid bands of each adjacent chute, the end faces at the interface between adjacent underlaid bands being slanted in the same direction as the advancing direction of said scrapers, whereby each end of each chute has a V-shaped configuration which cooperatively engages with the opposed V-shaped end of the next adjacent chute.

4,295,562

ARTICLE CARRIER AND BLANK THEREFOR


Prentice J. Wood, Hapeville, Ga., assignor to The Mead Corporation, Dayton, Ohio

Filed Jan. 7, 1980, Ser. No. 109,768

Int. Cl.³ B65D 5/16, 5/46, 5/54

U.S. Cl. 206—158

23 Claims



1. An article carrier comprising a bottom wall (1), side wall means (2,3,32,37) secured to the side edges of said bottom wall, a pair of end walls (20,53) secured respectively to the ends of said bottom wall, a top panel (30) secured to said side wall means and said end walls and disposed substantially parallel to said bottom wall, and characterized by a secondary bottom panel (6) disposed in flat face contacting relation with the upper surface of said bottom wall, and handle means (8,11) struck at least in part from said secondary bottom panel and secured thereto and disposed substantially perpendicular thereto.

4,295,563

PACKAGING SHEATH WITH CONTENTS

Reinhold Becker, Wolfgang Michel, and Gerhard Hartmann, all of Wiesbaden, Fed. Rep. of Germany, assignors to Hoechst Aktiengesellschaft, Frankfurt am Main, Fed. Rep. of Germany


Filed Mar. 26, 1980, Ser. No. 134,313

Claims priority, application Fed. Rep. of Germany, Mar. 30, 1979, 2912720

Int. Cl.³ B65D 81/18, 81/22, 81/24, 85/08

U.S. Cl. 206—205

11 Claims



1. An article of manufacture, comprising: a hollow rod comprised of a longitudinally gathered tube of cellulose hydrate-based material, said hollow rod having a latent water

content of between about 25% and 100% by weight based upon the total weight of the hollow rod and being free of chemical anti-bacteriocidal agents;

- a closed, substantially gas impermeable packaging sheath having a hollow interior chamber therein, said hollow rod being positioned in said hollow interior chamber, whereby the hollow rod is completely enveloped by said packaging sheath, said packaging sheath being comprised of a flexible film of material which is substantially impermeable to gases; and
- a protective gas essentially filling the remaining portion of said hollow interior chamber, said gas protecting said hollow rod against the formation of aerobic microorganisms on said water-containing cellulose hydrate-based material of said hollow rod.

4,295,564

HANGER ASSEMBLY FOR MERCHANDISE


Fred J. Miller, Memphis, Tenn., assignor to Arthur Fulmer of Mississippi, Inc., Memphis, Tenn.

Filed Jan. 18, 1980, Ser. No. 113,332

Int. Cl.³ B65D 85/18

U.S. Cl. 206—279

4 Claims



1. A hanger assembly for displaying merchandise, comprising:
- a label including a pair of juxtaposed flaps adapted to receive therebetween merchandise to be displayed, and a normally upstanding tab secured to at least one of said flaps and extending above said merchandise;
- structure defining an arcuate slot in said tab;
- a hook for suspending said assembly and merchandise; means pivotally mounting said hook to said tab for selective movement of the hook between an upright operative position and a lowered, recessed position below the upper margin of the tab,
- said slot being configured and arranged to accommodate pivoting of said hook between said positions,
- said hook and mounting means therefor comprising—
- an arcuate section having a base;
- a pair of spaced apart marginal legs secured to the base of said arcuate section and extending away from the same;
- a segment connecting the ends of said marginal legs remote from said arcuate section;
- a central leg disposed between said marginal legs and extending away from said section;
- a laterally extending stub secured to the end of said central leg remote from said section for defining a pivot axis for said hook,
- there being structure defining an aperture through said at least one flap receiving said stub;
- retainer means secured to said stub and adjacent the face of said one flap remote from said central leg,
- said slot being oriented for receiving a portion of said central leg during said pivoting of the hook.

4,295,565

FILM CONTAINING MAGAZINE

Kiyoyuki Takeuchi, Otawara, Japan, assignor to Tokyo Shibaura Denki Kabushiki Kaisha, Japan

Filed Aug. 24, 1979, Ser. No. 69,512

Claims priority, application Japan, Aug. 31, 1978, 53/106449

Int. Cl.³ B65D 85/30, 83/08


U.S. Cl. 206—455

10 Claims

1. A film containing magazine for containing a number of

sheet films in a stack for use in an X-ray photographing machine, comprising:

- (a) top and bottom walls and paired side walls arranged along the longitudinal axis of the magazine, and front and back walls arranged crosswise of the longitudinal axis, those components cooperatively defining a space containing a number of films;



- (b) an opening formed in the top wall near said front wall, through which sheet films are taken in and out;
- (c) a plate like resilient buffering member mounted on the inner surface of said top wall, said buffering member including a pair of spaced arm sections extending longitudinally of said magazine and to said opening.

4,295,566

AIR-EVACUATED PACKAGE WITH VACUUM INTEGRITY INDICATOR MEANS


Robert C. Vincek, Clifton, N.J., assignor to Becton, Dickinson and Company, Paramus, N.J.

Filed May 7, 1980, Ser. No. 147,698

Int. Cl.³ B65D 81/20; G01L 19/12

U.S. Cl. 206—457

9 Claims



1. An evacuated article-containing package assembly with vacuum integrity indicator means comprising:
- an air-imperious, flexible package having an access for the placement of an article therein;
- an article inside said package;
- a compressible member inside said package being compressible under the influence of pressure less than atmospheric pressure; and
- a closure seal on said package sealing said access after said article and said compressible member are within said package under air-evacuated conditions, said sealed package being air-evacuated, said compressible member adapted to expand against said flexible package to thereby outwardly expand said flexible package if the pressure inside said package should substantially equal the pressure outside said package, said expanded flexible package thereby serving as a visual indicator that there is no vacuum condition inside said package.

4,295,567

MEDICAMENT CONTAINER

Eric T. Knudsen, Cobham, England, assignor to Beecham Group Limited, England

Filed Nov. 9, 1979, Ser. No. 92,922

Claims priority, application United Kingdom, Nov. 10, 1978, 44099/78


Int. Cl.³ B65D 83/02, 85/56; G09F 3/08

U.S. Cl. 206—534

9 Claims

1. A pharmaceutical dispensing container, which contains two dosage units which are symptomatic treatments for respiratory tract disorders, the first of these dosage units being

non-sedative, and the second of these dosage units being sedative, and an indicia for distinguishing between said first and



second dosage units is provided on at least one of the container and said dosage units.

4,295,568

PRESSURE FRAME WITH BOWED SIDE MEMBERS

Kenneth S. E. Orpen, 2 Oak Lodge La., Westerham, Kent, England


Filed Aug. 8, 1979, Ser. No. 64,825

Claims priority, application United Kingdom, Aug. 15, 1978, 33352/78

Int. Cl.³ B65D 19/00

U.S. Cl. 206—597

13 Claims



1. A holding frame as hereinbefore defined, for use in securing a stack of articles together, wherein two side members at opposite sides of the frame are bowed, the flange-defining parts thereof being upwardly concave when the frame is disposed horizontally, flange uppermost, the frame being elastically deformable whereby the bowing and tilting of the said two side members is reduced when force is applied to the other side members which reduces the tilting of the latter side members.

4,295,569

APPARATUS FOR SORTING TEXTILE BOBBINS


Kurt W. Niederer, Charlotte, N.C., assignor to The Terrell Machine Company, Charlotte, N.C.

Filed Sep. 25, 1979, Ser. No. 78,700

Int. Cl.³ B07C 5/04

U.S. Cl. 209—634

32 Claims



1. An apparatus for sorting textile bobbins into groups com-

prises respectively of empty bobbins and bobbins having residual yarn wrapped thereabout, comprising:

- (a) sorting conveyor means having a yarn engaging surface and being arranged for upwardly inclined movement of said yarn engaging surface for upward conveyance and discharge therefrom of bobbins having residual yarn wrapped thereabout by engagement of the yarn by said yarn engaging surface and for downward sliding discharge therefrom of empty bobbins,
- (b) means for driving said sorting conveyor means, and
- (c) means for feeding bobbins onto said sorting conveyor means including transporting conveyor means passing closely adjacent said sorting conveyor means and being higher than said sorting conveyor means at the location of adjacency for transporting bobbins to the location of adjacency and depositing said bobbins at said location onto said sorting conveyor means, bobbins being carried on said transporting conveyor means in generally axial alignment with the longitudinal extent thereof, said bobbin feeding means including side wall means extending between said transporting conveyor means and said sorting conveyor means, said side wall means having an opening therein at the location of adjacency of said transporting conveyor means to said sorting conveyor means, and said transporting conveyor means being oriented in cross-section at the location of adjacency thereof to said sorting belt means at a downward incline toward said side wall means such that bobbins being transported along said transporting conveyor means move toward said side wall means and fall through said opening therein onto said sorting conveyor means.

4,295,570

AUTOMATIC SELECTION AND DELIVERY APPARATUS OF ASSEMBLED MECHANICAL PARTS

Tsutomu Hakoi, Kurobe, Japan, assignor to Yoshida Kogyo K.K., Tokyo, Japan


Filed Dec. 21, 1979, Ser. No. 105,939

Claims priority, application Japan, Dec. 26, 1978, 53-161534

Int. Cl.³ B07C 9/00

U.S. Cl. 209—657

6 Claims



1. An automatic selection and delivery apparatus for assembled mechanical parts which comprises:
- a base having at least one recess for receiving an assembled body the correctness of which is to be detected;
- a first delivery arm having an end which includes a portion for engaging a projection which will exist on a correctly assembled body but not on an incorrectly assembled body; said end being made to move over said base along said recess,
- said base having a disk-shaped configuration and provided about its circumference with a plurality of recesses spaced apart at a fixed angular pitch for receiving assembled bodies,
- said base being rotated step-wise by said fixed angular pitch, and
- said first delivery arm being driven radially of said disk-shaped base along one of said recesses in said base whenever said base comes to a stop.

4,295,571

FILE FOLDER SUPPORT RACK


Stephen T. Meyer, Carmel, Ind., assignor to Deflecto Corporation, Indianapolis, Ind.

Filed Apr. 27, 1979, Ser. No. 34,174

Int. Cl.³ A47B 3/02; B42F 15/00

U.S. Cl. 211—200

6 Claims



1. A support device for retaining file folders of the type having a support hook on each corner in a suspended upright orientation, said support device comprising:

- two aligned, oppositely disposed end frame members each having a configuration which provides a four-corners arrangement, the upper two corners of each end frame member having substantially the same first distance of separation and the lower two corners of each end frame member having substantially the same second distance of separation, said second distance of separation being different than said first distance of separation, each of said end frame members includes a first offset arm portion and a second offset arm portion pivotally connected to said first offset arm portion at a generally central location, said arm portions being movable with respect to each other between an unfolded offset X-shaped configuration and a folded closed configuration wherein said first distance of separation and said second distance of separation are substantially reduced to zero; and
- a plurality of side rails extending between corners of one end frame member and corresponding corners of the other end frame member, each of said side rails having an edge portion suitable to receive said support hooks.

4,295,572

CANNULA PIERCEABLE SELF-SEALING CLOSURE

Edward P. Percarpio, North Haledon, N.J., assignor to Becton, Dickinson and Company, Paramus, N.J.

Division of Ser. No. 942,113, Sep. 13, 1978, Pat. No. 4,226,333, which is a division of Ser. No. 880,474, Feb. 23, 1978, Pat. No. 4,136,794, which is a division of Ser. No. 729,643, Oct. 5, 1976, Pat. No. 4,111,326, which is a continuation-in-part of Ser. No. 663,921, Mar. 4, 1976, abandoned. This application May 8, 1980, Ser. No. 147,948

Int. Cl.³ B65D 39/04

U.S. Cl. 215—247


1 Claim

1. A cannula pierceable, self-sealing, gas proof closure for sealing an open end of an air evacuated blood collection tube, which comprises:

- (a) a tubular elastomeric body having
 - (i) flexible, elastic sidewalls;
 - (ii) an open first end; and
 - (iii) a closed second end formed by a cannula pierceable, flexible, elastic end wall integral with said sidewalls; said sidewalls bearing a plurality of grooves in the outer

surface thereof and in the direction of the vertical axis of said closure; and

- (b) a flange disposed radially about the periphery of said sidewalls adjacent to said first end;
- said end wall having a convex inner surface and a concave outer surface when pressure on inner and on outer surfaces is equal, said tubular body having a diameter which bears a ratio to the height of the body of about 0.8:1 and to thickness of the second end of from 5.4:1 to 12.1:1;



whereby when the closure is emplaced in and sealing an open end of an air evacuated tube, the higher pressure on the convex inner surface of the end wall as compared to the lower pressure (vacuum) exerting itself on the concave outer surface creates a pressure differential on the end wall, flexing and flattening the concave-convex configuration and creating a radial force directed toward the periphery of the end wall, said force effecting a restraining and sealing force between the closed second end of the elastomeric body and the air evacuated tube.

4,295,573

METHOD OF OBTAINING A SEAL UPON THE INTERIOR SURFACE OF A CONTAINER CLOSURE AND RESULTING PRODUCT


Robert R. Terry, Dunwoody, Ga., and Jacob J. Boone, Vermilion, Ohio, assignors to Nordson Corporation, Amherst, Ohio

Filed Dec. 21, 1979, Ser. No. 101,502

Int. Cl.³ B65D 53/06; B32B 5/18; B05B 7/16

U.S. Cl. 215—348

2 Claims



1. The method of obtaining a seal upon the interior surface of a closure for a container, which method comprises heating a thermoplastic adhesive material which is solid at room temperature so as to convert said adhesive material to the molten state, creating a mixture of gas and molten thermoplastic adhesive, pressurizing said mixture of gas and molten thermoplastic adhesive so as to force said gas into solution with said molten thermoplastic adhesive, dispensing the pressurized mixture of gas and molten adhesive at atmospheric pressure onto the interior surface of a container closure, whereby said gas comes out of solution with said molten thermoplastic adhesive and forms a

foamed molten adhesive bead upon said interior surface, and cooling said foamed molten adhesive bead while maintained as a foam on said interior surface of said closure so as to form a cellular seal adhered to said interior surface of said closure.

4,295,574

BANDED-TYPE IMPLOSION PROTECTION CATHODE RAY TUBES

Kooichi Nakazima, Chosei; Keizo Kazama, Mobara, and Hiroshi Oki, Chiba, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Continuation of Ser. No. 974,057, Dec. 28, 1978, abandoned.


This application May 13, 1980, Ser. No. 149,380

Claims priority, application Japan, Feb. 20, 1978, 53-17664

Int. Cl.³ H01J 31/00

U.S. Cl. 220—2.1 A

2 Claims



1. A combination of a cathode ray tube and an implosion protection tension band mounted on the periphery of the face plate of the cathode ray tube, said band comprising an annular reinforcing band which is so shaped, in advance of mounting of the same, as to be fitted to the periphery of the face plate, said annular reinforcing band being formed from an integral stamped flat metal strip, one end of which overlaps the other end substantially parallel to the adjacent periphery of said face plate and having lugs projecting from the edge of said strip; and interfitted means formed at the overlapped ends of said strip, said one end having an integral raised portion and said other end having an integral recess mating with said raised portion and adapted to be engaged for coupling together the opposite ends of said strip in fixed peripheral relation determined by said raised portion and said recess for accurately determining the inner peripheral length of said annular band, and a joint securing said overlapped ends to form said annular band with accurate said inner peripheral length which is sized to be under tension when thermally shrunk fit on said periphery of said face plate.

4,295,575

SURFACE RACEWAY BOX

Charles T. Flachbarth, Parkersburg, W. Va., assignor to Butler Manufacturing Co., Kansas City, Mo.

Continuation of Ser. No. 718,590, Aug. 30, 1976, abandoned.

This application Oct. 13, 1977, Ser. No. 841,945

Int. Cl.³ H02G 3/12


U.S. Cl. 220—3.92

1 Claim

1. In a surface raceway box of the known type having a flat base and a hollow, open-ended cover to be secured to the base, the base being for use in mounting the box on a building wall or a like surface and the cover having a top and a continuous wall extending away from the top with the outer edge of the wall forming said open-end and the top also having access opening means providing access to the cover interior, the improvement for securing the cover to the base which comprises:

a pair of spaced bosses on said base, each boss having a raised section including a hole for receiving the threads of a screw, the bosses being dimensioned so that each raised section is spaced away from the base so as to be located inside said cover when the cover is secured to the base in

a position close to said outer edge and substantially spaced away from the underside of said top; a pair of tabs respectively secured to the inside of said cover wall, each tab being located closely adjacent said outer edge and substantially spaced away from the underside of said top and each tab having a screw captured and rotatably mounted thereon, the tabs being located so that when the cover is positioned over the base to be secured thereto the tabs are respectively positioned over and closely adjacent said raised section whereby the screws are respectively aligned with said holes in condition to be turned into threaded engagement for holding the cover secure to the base;



said top access opening means and said captured screws being aligned with said holes in condition to be turned into threaded engagement providing for easy assembly of the cover to the base by that a screw driver can extend through said top access opening means and through the cover interior to contact and turn said screws into said threaded engagement; the length of each said screw being made so that when the screw is turned into said threaded engagement the screw extends into the boss less than the full depth of the boss; and said disposition of said tabs closely adjacent said outer edge providing for single length screws to be employed irrespective of the length of said wall taken between said top and said outer edge.

4,295,576

MOLDED CASE FOR RETURNABLE BEVERAGE BOTTLES

Rudolf F. Steinlein, Munich, Fed. Rep. of Germany, assignor to Alexander Schoeller & Co., A.G., Switzerland


Filed Oct. 30, 1979, Ser. No. 89,304

Claims priority, application Canada, Oct. 31, 1978, 315579; Fed. Rep. of Germany, Apr. 12, 1979, 7910849[U]

Int. Cl.³ B65D 1/24

U.S. Cl. 220—21

12 Claims



1. A molded thermoplastic resin case for transporting bottle carriers or minicases filled with beverage bottles or single beverage bottles, including:

a box structure having side walls and a floor; and at least one separator column extending upwardly from said floor within said box structure, said column being subdivided into partial pillars defining a slot therebetween for receiving therein a dividing wall of a bottle carrier or minicase with bottles contained therein to be inserted into the case;

each of said pillars being formed from a web-like, profiled, single wall having opposed inner and outer surfaces, said outer surface of each said profiled wall facing said side walls of said box structure and forming concave, vertically extending bottle contact faces for separating bottles inserted in said box structure, said inner surface of each said profiled wall defining said slot at a top portion thereof.


4,295,577

ANTI-THEFT DEVICE FOR LIQUID STORAGE TANKS
Michael G. Schmid, 5383 North St., Rte. 48, Lebanon, Ohio 45036, and Roger W. Hurt, 5604 Lesourdsville-Westchester Rd., Hamilton, Ohio 45011

Filed May 23, 1980, Ser. No. 152,672
Int. Cl.³ B65D 3/00; B67C 3/00

U.S. Cl. 220-86 AT

3 Claims



1. A device for preventing theft of liquid from a storage tank of the type having a liquid fill opening positioned on the upper surface of the tank, a hollow fill tube extending upwardly from the opening, and filling means associated with the upper end of the fill tube for introducing liquid into the tank, said theft preventing device comprising:

an elongated hollow tube-like stanchion positionable within the fill tube, the lower end of said stanchion being configured to rest upon the bottom of the liquid storage tank, said stanchion including an opening to permit flow of the liquid from the fill tube to the tank interior;

and

a grid-like baffle plate having a plurality of transversely extending web members forming adjacent openings dimensioned to prevent the introduction of a siphon tube of greater than a predetermined size, attached to the interior of said stanchion.

4,295,578

CONTRACTABLE CLOSURE MEMBER


Daniel Parent, St-Hyacinthe, Canada, assignor to Plastiques Modernes Ltée., Quebec, Canada

Filed Mar. 10, 1980, Ser. No. 128,452

Int. Cl.³ B65D 53/00

U.S. Cl. 220-234

20 Claims



1. A contractable closure member for sealing an open-ended container, said closure member comprising a top wall, a bottom wall formed from an elastic material and having an integral continuous side wall, seal means in said side wall, said side wall being securable to said top wall with said bottom wall held in spaced relationship therewith, a retracting lever pivotally secured below said top wall and having an engagement end and a pusher end, said pusher end being arcuately displaceable against a central portion of said bottom wall to distend said bottom wall whereby said side wall will be drawn inwardly to remove sealing pressure of said seal means when said closure member is positioned for sealing engagement with an open-ended container.

4,295,579

TABLET DISPENSER


Eduard Haas, Vienna, Austria, assignor to Centromint Company Establishment, Vaduz, Liechtenstein

Filed Apr. 7, 1980, Ser. No. 138,224

Claims priority, application Austria, Sep. 26, 1979, 6305/79

Int. Cl.³ B65D 83/04; B65H 1/00, 1/08; G07F 11/16
U.S. Cl. 221-229

5 Claims



1. A tablet dispenser comprising a housing part and a tablet storage receptacle part coaxially displaceably mounted in the housing part, the storage receptacle part including a spring biased to press a stack of tablets stored in the receptacle part upwards towards a dispensing end of the receptacle part, one of the parts having an end remaining in contact with the other part in an outer end position of the receptacle part in relation to the housing part, the one part providing a space defining a free play between the parts terminating short of the contacting end, and the other part having a catch arranged close to an end of said other part contacting the end of the one part in the outer end position, a tolerance remaining between the catch and the space, and the catch having a height corresponding to the

tolerance, a sloping run-up section extending between the catch and the space adjacent the contacting ends.

4,295,580

CLOSURE DISPENSER


Christopher P. Amberg, Toledo, Ohio, assignor to Owens-Illinois, Inc., Toledo, Ohio

Filed Aug. 16, 1979, Ser. No. 66,942

Int. Cl.³ B65G 59/06

U.S. Cl. 221-268

1 Claim



1. A dispenser for a flexible disk shaped closure with an attached rim, including an elongate cylindrically shaped closure storing chamber for storing a vertically oriented stack of closures, a bottom plate positioned adjacent one end of said storing chamber and attached thereto, a slide bar retaining plate positioned next to and in juxtaposed relationship with respect to said bottom plate, an elongated slot, formed with reentrant corners, positioned along a diameter of said slide bar retaining plate, a slide bar positioned and guided for movement within said slot, said movement being limited by engagement of said slide bar with said reentrant corners, a closure engagement foot attached to and positioned intermediate the ends of said slide bar, an upturned edge on said closure engagement foot cantilevered at an angle with respect to said slide bar for engaging the inside rim of a closure, a cover plate containing a slotlike aperture for surrounding a portion of said closure engagement foot, said cover plate positioned adjacent to and above said slide bar, a circumferentially positioned aperture in said storing chamber wall opposite said slot in said slide bar retaining plate, a notch formed in a bottom edge of said aperture for providing specific ingress and egress for said slide bar and its closure engagement foot, said slide bar passing through and movable within said notch so that when said slide bar is moved from an inward to an outward position a closure will be partially withdrawn from said dispenser through said aperture and when said slide bar is moved from an outward to an inward position said cantilevered upturned edge will cam beneath the rim of a closure positioned within said storing chamber and assume a position whereby the next closure can be extracted from said dispenser.

4,295,581

INSECTICIDAL AEROSOL FORMULATION HAVING A LIQUIFIED PETROLEUM GAS PROPELLANT


Takashi Yamaguchi, Nishinomiya; Yoshitoshi Okuno, Toyonaka, and Chuji Hirose, Takarazuka, all of Japan, assignors to Sumitomo Chemical Company, Limited, Osaka, Japan

Continuation of Ser. No. 857,801, Dec. 5, 1977. This application Mar. 24, 1980, Ser. No. 133,600

Claims priority, application Japan, Dec. 9, 1976, 51-148426
Int. Cl.³ B65D 83/14

U.S. Cl. 222-192

1 Claim



1. An insecticidal aerosol formulation comprising a pressure-proof container equipped with a valve having a housing orifice of 0.46-0.64 mm in diameter, button, stem and vapor tap orifices of 0.33-0.41 mm in diameter wherein the stem orifice diameter $\leq$ vapor tap orifice diameter $\leq$ button orifice diameter, filled with a base liquid consisting essentially of at least one pyrethroid type insecticide dissolved in kerosene having a boiling point of 180° to 260° C. and a propellant consisting essentially of a liquified petroleum gas wherein the volume ratio of the base liquid to the liquified petroleum gas is 50:50 to 60:40.

4,295,582

DISPENSING CONTAINER WITH IMPROVED AIR VALVE


Alexander D. Acres, 368 Glenrose Dr., London, Ontario, Canada (N6K 2A8)

Filed Aug. 9, 1979, Ser. No. 65,269

Int. Cl.³ B65D 37/00

U.S. Cl. 222-213

5 Claims



1. An improved air valve for a dispensing container, the container including a resilient housing, a bottom, and a resilient expandable membrane mounted between the housing and the bottom to internally partition the container into an ingredient dispensing chamber and an air chamber, the housing defining an ingredient dispensing orifice that communicates with the ingredient containing chamber, the improvement comprising: (a) the bottom formed to matingly seal marginal edges of the membrane with peripheral walls of the container, the bottom forming a recess and having an inclined sloped portion, an aperture formed in said inclined sloped por-

tion, the sloped portion forming an acute angle with the housing, whereby on flexing of the housing, a portion of the membrane is caused to be sealingly urged against the aperture and hence to sealingly close the same whereby air in the air chamber is urged against the membrane to urge ingredients in the ingredient chamber out of the ingredient orifice.

4,295,583

CLOSURE CAP VENT

Robert E. Schurr, Garrett, Ind., assignor to Rieke Corporation, Auburn, Ind.


Filed Aug. 9, 1979, Ser. No. 65,183

Int. Cl.³ F65D 25/44

U.S. Cl. 222—478

8 Claims

tion of the cap upon partial rotation of the cap to seal the cap in the closed position.



1. A venting device for use with and secured to a container pour spout of the style having an outer base portion and a smaller inner cylindrical portion with an invertible fold portion therebetween, said venting device arranged to allow the entry of air into the corresponding container at a location exterior to the exiting fluid flow stream, said venting device comprising:

a hollow central body portion having a top end which includes a generally cylindrical section and joined thereto in end-to-end relationship therewith a frustoconical section, each section extends above said invertible fold portion and into said smaller inner cylindrical portion and said top end of said hollow central body portion is arranged substantially concentric with said container pour spout in a uniformly spaced-apart manner, the resultant space between the outside surface of said top end and the inside surface of said smaller inner cylindrical portion providing a generally annular air flow passageway for entering venting air, said hollow central body portion further comprising a base and an interior passageway extending therethrough, said central body portion tapering inwardly as it extends from said base to said top end resulting in a progressively reduced cross-sectional area; and

a substantially flat flange portion integral with said base and including a spaced plurality of outwardly radiating ribs:

4,295,584

SIDE DISPENSING CLOSURE

Raymond P. Borowitz, Rte. 6, Box 2067, Escondido, Calif. 92026

Filed Jan. 22, 1979, Ser. No. 5,340


Int. Cl.³ B65D 47/28

U.S. Cl. 222—519

1 Claim

1. A dispensing closure and container comprising: a closure with a top and side wall portion or skirt; said skirt having an opening or openings of any size constructed or molded therein for the dispensing of container's contents; said skirt also having inward facing projections; a container with an open-end neck portion; said neck having external longitudinally extending pillars cooperating with the inward facing projections of the cap skirt to define a guidepath of axial reciprocation; there being at least two pillars forming the guidepath; each pillar having vertically positioned stop lugs to limit the extent of outward opening axial movement of the cap; and alternate

pillars having a length less than an adjacent pillar to receive the inward projections of the cap skirt in the inward closed position.



4,295,585

MULTI-PIECE HANGER


Judd F. Garrison, Grand Rapids, Mich., assignor to John Thomas Batts, Inc., Zeeland, Mich.

Filed Apr. 16, 1979, Ser. No. 30,287

Int. Cl.³ A47J 51/14

U.S. Cl. 223—96

5 Claims



1. An article hanger having a frame and an article engaging member; said frame having means by which it can be suspended, said article hanger characterized in that said article engaging member and said frame are separate components and two-part means are provided for locking said article engaging member and frame together, said means including a track opening through one end of said frame and said article engaging member having a tongue adapted to be slidably and telescopically received in said track, said track and tongue being shaped to hold said article engaging member against rotation in any direction with respect to said frame.

4,295,586

RECEPTACLE SUPPORT APPARATUS FOR BICYCLE


Norman E. Shockley, 1119 Murfreesboro Rd., H-3, Nashville, Tenn. 37217

Filed Jan. 24, 1980, Ser. No. 115,013

Int. Cl.³ B62J 9/00

U.S. Cl. 224—32 R

8 Claims



1. A receptacle support apparatus for a bicycle having a rear

wheel and a bicycle frame including a rear fork straddling and connected to the rear wheel, comprising:

- a support frame,
- means mounting said support frame on said bicycle frame over said rear wheel,
- at least one receptacle made of flexible sheet material having a bottom wall, end walls, and inboard and outboard side walls, said end walls and said side walls having upper margins defining an open top,
- rod means comprising an outboard rod portion cooperatively engaging the upper margin of said outboard side wall, and end rod portions cooperatively engaging the upper margins of said respective end walls,
- each of said end rod portions having inboard end portions and having outboard ends connectable to said outboard rod portions, and
- means for detachably mounting said inboard end portions to said support frame.

4,295,588

SLOTTED SIDE RAIL AND MOVABLE BRACKET FOR ARTICLE CARRIER


Daniel J. Kowalski, Ortonville, and Ray G. Mareydt, Warren, both of Mich., assignors to Four Star Corporation, Troy, Mich.

Filed Sep. 4, 1979, Ser. No. 71,938

Int. Cl.³ B60R 9/00

U.S. Cl. 224—321

2 Claims



1. An adjustable cross-rail assembly for a vehicle-mounted article carrier of the type including a hollow side rail supported upon a vehicle surface, said rail including transversely spaced inner and outer walls, said inner wall including a longitudinally extending slot, a bracket slidably supported within said slot and including a cross-rail supporting portion projecting transversely inwardly of the inner wall of said side rail and means for releasably locking said bracket to said side rail, the improvement comprising:

- said bracket being bifurcated to provide inner and outer portions straddling said side rail slot, a threaded bore formed through said inner and outer portions and extending transversely through said side rail slot;
- a member slidably disposed within said side rail and including a recess adapted to be transversely aligned with said bracket bore, said member being transversely spaced outwardly from the outer portion of said bracket and including an outer surface disposed proximate the outer wall of said side rail; and
- an element extending through and threadable within said bracket bore and projecting within the member recess whereby rotation of said element in one direction respectively causes the outer surface of said member to engage with the outer wall of the side rail and the outer portion of said bracket to engage with the inner wall of said side rail to adjustably fix the longitudinal position of said bracket relative to the side rail.

4,295,587

ARTICLE CARRIER FOR AUTOMOTIVE VEHICLES


John A. Bott, 931 Lake Shore Dr., Grosse Pointe Shores, Mich. 48236

Division of Ser. No. 924,072, Jul. 7, 1978, Pat. No. 4,182,471, which is a division of Ser. No. 743,602, Nov. 22, 1976, Pat. No. 4,099,658, which is a continuation of Ser. No. 486,415, Jul. 8, 1974, abandoned. This application Jul. 10, 1979, Ser. No. 56,154

Int. Cl.³ B60R 11/00

U.S. Cl. 224—321

6 Claims



1. In an article carrier for an automotive vehicle, a plurality of at least two parallel arranged slats fixedly secured on a generally horizontally extending exterior body surface of the vehicle and lying closely adjacent said surface, each of said slats having major and minor dimensions, with said major dimension being arranged substantially parallel to said body surface, each of said slats having a clamping surface extending longitudinally on the exterior surface thereof, an article supporting member mounted on at least one of said slats and having clamping means clampingly engageable with said one slat for securing said member thereto, said clamping means being operable to apply a first vertically downwardly directed force against said one slat and a second vertically upwardly directed force against said one slat and being readily loosened for the movement of said member longitudinally of said slats and for the removal and reattachment of said article supporting member solely at the longitudinal end extremes of said slat.

4,295,589

DEVICE FOR FEEDING WEB WITH TEMPERATURE COMPENSATING MEANS

Shigenori Oosaka, and Makoto Murakoshi, both of Asaka, Japan, assignors to Fuji Photo Film Co., Ltd., Minami-ashigara, Japan

Filed May 22, 1980, Ser. No. 152,190

Claims priority, application Japan, May 25, 1979, 54-64623


Int. Cl.³ B65H 17/26

U.S. Cl. 226—122

4 Claims

1. A device for feeding a web comprising a rubber roller for feeding a web, a stepping motor for driving the rubber roller by way of a power transmission means, a pulse generator connected with the stepping motor for driving the stepping motor by the pulses generated thereby, a temperature detecting means for detecting the temperature of the rubber roller directly or indirectly, and a temperature compensating means for controlling the number of pulses generated by the pulse generator according to the temperature detected by said temperature detecting means in such a manner that the speed of

rotation of said rubber roller is controlled to effect the constant speed of web feeding irrespective of the temperature detected, second press plates including means for removably supporting first and second nail plates, said first and second press plates



whereby the web is fed at a constant speed irrespective of the temperature of the rubber roller.

4,295,590

APPARATUS FOR PROCESSING PHOTOGRAPHIC MATERIALS


Henry F. Hope, and Stephen F. Hope, both of 2421 Wyandotte Rd., Willow Grove, Pa. 19090

Filed Jun. 10, 1980, Ser. No. 158,248

Int. Cl.³ B65H 17/22; G03B 1/56

U.S. Cl. 226—183

6 Claims



1. In apparatus for processing photographic material by conveying an elongated web for turnaround in a confined space comprising spaced frame members, means carried by said spaced frame members for directing the web in an arcuate path, said means comprising an endless web guiding belt for engagement by the leading edge of the web and by the web.

4,295,591

NAIL PRESS

Sten Lundström, Borås, Sweden, assignor to Aktiebolaget SKF, Gothenburg, Sweden

Filed Jan. 22, 1980, Ser. No. 114,251


Claims priority, application Sweden, Jan. 30, 1979, 7900785

Int. Cl.³ B27F 7/15

U.S. Cl. 227—142

5 Claims

1. A nail press assembly comprising a yoke of generally C-shaped configuration, a hydraulic actuated piston mounted at one end of the said yoke, a shaft member aligned with said piston at the opposite end of said yoke, the confronting ends of said piston and shaft member mounting confronting first and



being mounted for limited universal pivotal movement on said piston and shaft member respectively.

4,295,592

APPARATUS FOR JOINING AND CLADDING PIPE SECTIONS

August W. Schäfer, Wilsdorf-Wilden, Fed. Rep. of Germany, assignor to Wilhelm Schäfer Maschinenbau, Wilsdorf-Wilden, Fed. Rep. of Germany


Filed Oct. 9, 1979, Ser. No. 82,624

Claims priority, application Fed. Rep. of Germany, Nov. 4, 1978, 2847966

Int. Cl.³ B23K 37/02, 37/04

U.S. Cl. 228—17

6 Claims



1. An apparatus for joining pipe sections and for forming around the joined pipe sections a helical passage, said apparatus comprising:

means including a cradle for holding two cylindrical pipe sections with their ends abutting axially and their axes coaxial;
means including a roller in said cradle for jointly rotating said sections about said axes with said ends abutting;
a track extending parallel to said axes;
a carriage displaceable axially on said track adjacent said cradle and including an upright post and a horizontal outrigger carried on said post;
means including a primary welding tool on said carriage for welding together the ends of said pipe sections as same rotate;
a supply of flat metal strip on said carriage;
means on said carriage for withdrawing said strip from said supply, bending said strip into a U-section, arcing said

strip to a radius of curvature substantially equal to that of said sections, and helically applying the arced strip to said pipe sections as same rotate with the concave side of said strip turned toward said sections, whereby said strip forms with said sections a helical passage;
means including a secondary welding tool on said carriage for welding the arced strip helically to said pipe sections as same rotate;
means for vertically displacing said outrigger on said post for displacing said tools radially of said axes and for retaining said tools in any of a multiplicity of radially offset positions on said carriage, said tools being downwardly directed and effective, whereby welding is effected at the highest parts of said sections; and
control means connected to all of said means for synchronously axially displacing said carriage on said track and rotating said pipe sections during welding of the arced and U-section strip to said sections.

4,295,593

WELDING SEAM BACK-UP MEANS


Milo M. Kensrue, 601 Lido Park Dr., 8B, Newport Beach, Calif. 92663

Filed Sep. 24, 1979, Ser. No. 78,339

Int. Cl.³ B23K 37/06

U.S. Cl. 228—50

12 Claims



1. A welding seam back-up means for mounting on the back side of the adjacently positioned edge margins of members to be joined by a weld seam, comprising:

a. an elongated tape of flexible material adapted to be positioned in straddling relation over said adjacent edge margins and extending longitudinally therealong;
b. tape holding means adapted to be positioned over said tape; and
c. means for releasably securing said tape holding means and applying pressure in a direction to force the tape against the adjacent edge margins comprising a plurality of attaching brackets for mounting at spaced intervals longitudinally of the tape holding means and adapted to transversely straddle the tape holding means, each of said brackets including:
an elongate longitudinally bowed strap-like spring; and
a magnet connected to each end of said spring;
whereby with the bowed spring engaged between its ends with the tape holding means, the magnets will be initially respectively in spaced relation to the members to be joined by the weld, and upon movement of the magnets into engagement with said members, will deform and activate the bowed spring so as to apply a holding pressure against said tape holding means.

10. A welding seam back-up means for mounting on the back side of the adjacently positioned edge margins of members to be joined by a weld seam, comprising:

a. an elongate tape of flexible material adapted to be positioned in straddling relation over the adjacent edge margins and extending longitudinally therealong;
b. tape holding means comprising an elongate channel member having a low heat sink capability adapted to be positioned over and to receive said tape therewithin and extending therealong;
c. an elongate separate bar of a material having a high heat conducting characteristic positioned in the channel in

underlying relation to said tape to provide a high heat sink capability;
d. means for releasably retaining said bar within said channel including a screw rotatably supported in said channel and having threaded engagement with said bar; and
e. means for releasably securing said tape holding means and applying pressure in a direction to force the tape against the adjacent edge margins.

4,295,594

LAMINATED JET PIPE RECEIVER PLUG ASSEMBLY METHOD AND STRUCTURE


Robert D. Nicholson, Birmingham, and Alger T. Daniel, Clawson, both of Mich., assignors to Koehring Company, Brookfield, Wis.

Filed May 22, 1979, Ser. No. 41,494

Int. Cl.³ B23K 1/20; B23P 13/00

U.S. Cl. 228—160

8 Claims



2. The method of manufacturing a receiver plug assembly structure comprising preparing a plurality of plates with openings extending therethrough which are positioned to provide passages through the receiver plug assembly when the plates are positioned adjacent to each other in surface to surface contact, said plurality of plates including at least one centrally located divider plate having spaced apart transverse openings therethrough and at least one port plate positioned on each side of the divider plate having transverse openings therethrough, which openings are aligned with the openings through the divider plate and a transverse opening extending through the end of each of the port plates in communication with separate ones of the aligned openings through the divider plate, placing a brazing compound on selected surfaces of the plates, assembling the plates in surface to surface contact to provide the passages through the receiver plug assembly, subjecting the assembled plates to brazing temperature and pressure to braze them together, and machining the brazed-together plates into the desired exterior form of the receiver plug assembly.

4,295,595

METHOD OF PRODUCING MAGNETRON ANODE

Kuninori Imai, Shiroyamamachi, and Soji Takahashi, Hachioji, both of Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed Jan. 25, 1979, Ser. No. 6,484

Claims priority, application Japan, Jan. 25, 1978, 53-6198; Jan. 27, 1978, 53-7251

Int. Cl.³ B23K 28/02

U.S. Cl. 228—161

14 Claims



1. A method of producing a magnetron anode having a plurality of copper vanes which extend radially inward from the inner peripheral surface of said copper anode toward the center of said copper anode comprising:

a first step of cleaning the outer peripheral surface of a

copper blank and the inner peripheral surface of a straight steel cylinder blank material;

a second step of fitting said copper blank to the inside of said straight steel cylinder blank material so that the cleaned outer peripheral surface of said copper blank and the cleaned inner peripheral surface of said straight steel cylinder blank material contact each other, and then compacting said copper blank to said steel cylinder blank material;

a third step of preheating said copper blank compacted to said steel cylinder blank material and press working said copper blank by penetrating said copper blank with a shaping punch so that said steel cylinder blank material is raised in a direction opposite to the penetration of the shaping punch within a time region between the instant at which the shaping punch contacts said copper blank and the instant at which the shaping flow of said copper blank becomes steady, so as to maintain a constant length between the upper end of said steel cylinder blank material and the upper end of the peripheral portion of said copper blank after the compaction without causing relative sliding between said steel cylinder blank material and said copper blank; and

a fourth step of effecting a post-treatment on the press-shaped copper blank and steel cylinder blank material so as to obtain a tight bonding and desired shape of said anode;

wherein said third step is carried out such that said steel cylinder blank material is made to move upward during said press working, the amount of rise of said steel cylinder blank material in said pressworking of said third step being $((\text{extrusion ratio}) - 1) \times 0.7$ times as large as the penetration of said shaping punch.

4,295,596

METHODS AND APPARATUS FOR BONDING AN ARTICLE TO A METALLIZED SUBSTRATE


Bradford O. Doten, Hopewell Township, Mercer County, N.J., and John J. Svitak, Lower Makefield Township, Bucks County, Pa., assignors to Western Electric Company, Inc., New York, N.Y.

Filed Dec. 19, 1979, Ser. No. 105,463

Int. Cl.³ B23K 1/12; H01S 21/60

U.S. Cl. 228—180 A

9 Claims



1. A method of bonding an article to a metallized substrate, at least one of which has a predeposited reflowable bonding material thereon, the method comprising the steps of: positioning the article on the metallized surface of the substrate; directing at least one stream of hot gas towards the substrate; redirecting the gas stream laterally, substantially parallel to the surface of the substrate, towards the article to reflow the material; and resolidifying the material to form a bond between the article and the metallized surface of the substrate.

4,295,597

TRAY BLANK FOR EGGS

Jorgen N. Petersen, Lyngby, Denmark, assignor to Aktieselskabet Brodrene Hartmann, Lyngby, Denmark
Continuation of Ser. No. 624,965, Oct. 22, 1975, abandoned.


This application Sep. 28, 1977, Ser. No. 837,533

Claims priority, application Denmark, Jan. 27, 1975, 25219/75

Int. Cl.³ B65D 1/24, 85/32

U.S. Cl. 229—2.5 EC

5 Claims



1. A tray blank especially for eggs comprising an egg carrier section and a cover, said carrier section having a plurality of egg-receiving compartments, each of said compartments being in part defined by a projection extending upwardly from the bottom of said carrier section, each projection having an open top, each projection having lateral wall portions, each lateral wall portion having an upper free edge at said open top, at least two slits in each projection, said slits extending downwardly from said upper free edge, said slits defining the lateral extent of said wall portions at and adjacent said upper free edge, each wall portion extending downwardly beyond said slits into a compartment, said wall portion being resilient due to the presence of said slits, said slits being free of engagement with said cover when said cover is in its closed position, said slits also being free when said cover is in its closed position to become reduced in size due to flexing of said wall portions, said wall portions in part defining an egg-receiving compartment only on one side of said wall portions, and the opposite side of said wall portions in part defining a space at all times free of eggs, whereby said wall portions may at all times give to support eggs of different sizes.

4,295,598

CARTON WITH CARRYING STRAP


Rodney K. Calvert, Dunwoody, Ga., assignor to The Mead Corporation, Dayton, Ohio

Filed Jun. 20, 1980, Ser. No. 161,408

Int. Cl.³ B65D 5/46, 25/28

U.S. Cl. 229—52 AL

15 Claims



1. An article carton having top, bottom, side and end walls interconnected to form an enclosure which is generally cubical in configuration, means defining an aperture in one of said

walls, and a carrying strap having an anchoring part disposed entirely within the carton and arranged in enveloping relation to at least a part of an article disposed within the carton, said strap having a handle part normally disposed within the carton and adjacent said aperture and said handle part being accessible for grasping to facilitate carrying the carton.

4,295,599

FILE BOX


John D. Locatelli, 3340 59th Ave. SW., Seattle, Wash. 98116, and Gary M. Gunderson, Seattle, Wash., assignors to John D. Locatelli, Seattle, Wash.

Filed May 16, 1980, Ser. No. 150,343

Int. Cl.³ B65D 5/22

U.S. Cl. 229—34 R

2 Claims



1. In a file box having a flat, rectangular bottom panel; a pair of hollow side walls extending upwardly from each side edge portion of the bottom panel, the side walls having front and rear entrance openings; an upright front panel pivotally connected along its bottom edge portion to a front edge portion of the bottom panel to enable the front panel to pivot between a closed, substantially vertical position and an open, forward tilted position; an upright rear panel pivotally connected along its bottom edge portion to a rear edge portion of the bottom panel to enable the rear panel to pivot between a closed, substantially vertical position and an open, rearwardly tilted position; and the improvement comprising:

unitary, substantially rigid and flat front sliding panels extending rearwardly from each side edge portion of the front panel to slidably extend through a corresponding side wall front opening a substantial distance into the hollow interior of the side wall;

unitary, substantially rigid and flat rear sliding panels extending forwardly from each side edge portion of the rear panel to slidably extend through a corresponding side wall rear opening a substantial distance into the hollow interior of the side wall to overlap said front sliding panels;

wherein said front and rear sliding panels slide relative to each other within the hollow side walls and said front and rear sliding panels pivot with their corresponding front and rear panels between a closed position wherein said front and rear sliding panels are disposed in maximum overlapping relationship and substantially entirely within a corresponding side wall, and an open position wherein said sliding panels are disposed in substantially overlapping relationship and extend outwardly from the side walls to form, respectively, front and rear extensions of the side walls; and

a unitary, substantially rigid, flat top panel having front, rear and side edge portions, said top panel being pivotally connected along its rear edge portion to the top portion of the rear panel to pivot between a first, closed position closely overlying the side walls to substantially close off the top of the file box and second, open position extending upwardly from the rear panel to provide unhindered access to the file box.

4,295,600

APPARATUS FOR THE CENTRIFUGAL SEPARATION OF AT LEAST TWO LIQUID PHASES AND ONE SEDIMENTARY PHASE OF A MIXTURE

Pierre L. Saget, 36, avenue de la Grande Armee, Paris, France (75017)


Filed Feb. 19, 1980, Ser. No. 122,472

Claims priority, application France, Feb. 23, 1979, 79 04748

Int. Cl.³ B04B 1/04, 1/20

U.S. Cl. 233—7

11 Claims



1. An improved apparatus for the centrifugal separation of at least two liquid phases and one solid sedimentary phase from a mixture, the said apparatus comprising: a rotating enclosure, first rotational means for rotating said enclosure, said rotating enclosure disposed around a nozzle supplying the mixture to be treated, said rotating enclosure being closed by a coronal base and coupled to said first rotation means for driving it in rotation, the said enclosure being integral with an angular partition therein which plunges into the mixture beyond the interface of the phases thereof, said partition separating a first chamber in said enclosure containing only the heavy phase from a second chamber in said enclosure containing the light phase "floating" on the heavy phase, said partition providing a peripheral annular passage for the transfer of the said heavy phase from the second chamber towards the first chamber, said first chamber being defined by a peripheral wall, said coronal base and said partition wall, the enclosure further presenting separate thresholds for the draining of the phases, a helical sediment conveyor within said enclosure, a second rotation means coupled to said conveyor via a plate which plunges into the mixture beyond the said interface, said plate separating the second chamber from a cavity in said enclosure with which said second chamber communicates on the periphery via a space near the conveyor for transferring the sediments through the heavy phase,

a first centrifuge device housed in the first chamber and integral with said peripheral wall, said partition wall and said base thereof provided with surfaces extending inside the entire treated volume, across their circular movement, in order to transmit the rotation of the first driving means to the heavy phase according to an angular speed which is scrupulously constant throughout its whole mass and in every one of its points;

through the entire treated volume, across their circular movement, in order to transmit the rotation of the second driving means to at least the light phase, according to an angular speed which is scrupulously constant throughout its whole mass and in every one of its points, thus opposing the natural tendency of this type of flow with constant angular speed to degenerate into an irrotational vortex flow with tangential speed inversely proportional to the radius, which would destroy the stability of the interface and would lead to a re-mixing of the phases, a device for controlling the two means for driving the centrifuge devices for stabilizing and regulating the ratio of their respective rotation speeds.

4,295,601

CENTRIFUGE TUBE HOLDER


Mark J. Cowell, Mountain View, Calif., assignor to Beckman Instruments, Inc., Fullerton, Calif.

Filed Nov. 13, 1979, Ser. No. 93,725

Int. Cl.³ B04B 15/00

U.S. Cl. 233-26

12 Claims



1. A centrifuge tube holder comprising:
a first section for holding at least one centrifuge tube;
a second section for holding at least one centrifuge tube, each of said first and second sections having a support leg;
a central support post; and
means for pivotally connecting said first and second sections to allow respective movement between said first and second sections, the bottom edges of said central post, said first section support leg and said second section support leg being positionable in the same general horizontal plane, so that said support legs of said first and second sections with said central support post will support said tubes vertically on a workbench, said bottom edges of said central post, said first section support leg and said second section support leg being positionable in general alignment with a concave cylindrical surface so that said support legs and said central post will hold said tubes horizontally in a rotor with said tubes having different radial orientations with respect to the spin axis of said rotor.

4,295,602

CONTROL VALVE

Charles H. Priesmeyer, Park Ridge, Ill., assignor to Mark Controls Corporation, Evanston, Ill.

Filed Nov. 13, 1979, Ser. No. 93,063

Int. Cl.³ G05D 23/10


U.S. Cl. 236-93 B

16 Claims

13. In a shower of the type including an inlet pipe carrying water and a shower head secured to and communicating with said pipe, the improvement comprising:

- a valve for restricting the flow of water with said shower head said valve comprising:
- a housing;
- a chamber in said housing;
- an inlet port communicating with said chamber;

at least one outlet port communicating with said chamber; and
a bimetallic concave-convex circular plate having an aperture therethrough and having a surface, said plate subdividing said chamber into an inlet section containing said inlet port and an outlet section containing said outlet port, said inlet section and said outlet section communicating



substantially only through said aperture, said aperture being offset with respect to at least one outlet port, said plate deflecting when its temperature substantially reaches a first predetermined value to a restricting position in which the surface thereof restricts the flow of water into said outlet port and deflecting into open position when its temperature substantially reaches a second predetermined value to permit the flow of said water into said outlet port.

4,295,603

MEANS CONTROLLING A FLUE DAMPER


Michael T. Clouser, Indianapolis, Ind., assignor to Emhart Industries, Inc., Indianapolis, Ind.

Filed Nov. 13, 1979, Ser. No. 93,785

Int. Cl.³ G05D 23/00

U.S. Cl. 236-1 G

13 Claims



1. In a heating system wherein a flue damper regulates gas flow through a conduit from a heat source in accordance with temperature demand actuating a heat source, an improved means controlling said flue damper comprising: a control means connected to said flue damper to rotate same to selectively open and close same at about 90° increments, including alternating current motor drive means; timing means driven by said motor drive means; and electrical circuit means including switch means responsive to said timing means and controlling electrical power in said control system and solid state switching means having a gate means connected to said heat source and selectively energizing and deenergizing said motor drive means wherein said gate means de-energizes said solid state switching means when said heat source is actuated.

4,295,604

AUTOMATIC TEMPERATURE CONTROL SYSTEM FOR DIVER HEATING SYSTEM


Sergius S. Sergev, Ventura, and Theodore J. Roster, Oxnard, both of Calif., assignors to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Apr. 24, 1980, Ser. No. 143,079

Int. Cl.³ F23N 5/06

U.S. Cl. 236-21 R

7 Claims



1. A thermally controlled gas flow valve in which the gas flow through said valve is a function of the temperature of a first fluid comprising:

- seat means having an orifice therethrough, a gas being fed under pressure into one end of said orifice;
- means for transferring heat between the first fluid and a second fluid having a high coefficient of thermal expansion, including:
- a reservoir filled with said second fluid; and
- a plurality of tubes disposed within said reservoir, said plurality of tubes being coupled to receive said first fluid so that said first fluid passes through said tubes, said first and second fluid being in thermal contact with each other through said tubes so that heat may be transferred between said fluids;
- means for varying the cross-sectional area of said orifice through which gas may flow as a function of the volume of the second fluid, including
- expansion bellows means communicating with said reservoir to receive said second fluid so that an increase or decrease in the volume of said second fluid produces an expansion or contraction, respectively, of said bellows means along its longitudinal axis; and
- a needle coupled to said bellows means so that expansion and contraction of said bellows means moves said needle into and out of said orifice to vary the cross-sectional area of the passage therethrough, thereby varying the gas flow through said orifice;
- a carrier member having an elongated cavity, said bellows means being fixed to said carrier member with the expandable portion of said bellows means being disposed in said cavity, said cavity communicating with said orifice so that the gas passing through said orifice may flow to surround said bellows means within said cavity; and
- a valve body having an elongated chamber in which said carrier is disposed, said chamber having inlet means and outlet means so that the first fluid may be circulated through said chamber, the first fluid surrounding said carrier within said chamber.

4,295,605

STEAM TRAPS

Edward R. C. Clayton, Martock, and Alan F. Bennett, Cheltenham, both of England, assignors to Spirax Sarco Limited, Gloucestershire, England

Filed Jan. 22, 1980, Ser. No. 114,408

Claims priority, application United Kingdom, Jan. 26, 1979, 02777/79


Int. Cl.³ F16T 1/10

U.S. Cl. 236-56

6 Claims

1. A thermostatic steam trap comprising a base; a cover mounted on the base, the base and cover defining a hollow interior of the trap; a casing within said interior fast with the base and cover; a housing movably mounted in the casing;

resilient means urging the housing to seat in the casing; a balanced pressure thermostatic element mounted in the housing; a valve member carried by the thermostatic element; an inlet port to said interior; an outlet port from said interior; and a valve seat in the outlet port; the casing locating the housing and the thermostatic element with respect to the outlet port so that the valve member carried by the thermostatic element co-operates with the valve seat in the outlet port for opening and closing the trap; the element defining an internal void that is open to steam/condensate within the trap and that is sealed from the interior of the housing in which the element is



mounted; the housing having its interior sealed from said interior of the trap and containing volatile fluid which entirely fills the housing outside the element when the trap is fully open thereby to support the element; the element being moved by the pressure exerted by the volatile fluid upon heating of the fluid to urge the valve member carried by the element on to the valve seat to close the trap with the element, in the trap fully-closed condition, being in a nearly nesting condition; the housing moving away from its seating condition in the casing, against the action of said resilient means; to permit the element to adopt a fully nesting condition if further heating of the volatile fluid occurs.

4,295,606

HEATING SYSTEM


Paul F. Swenson, 25525 Edgecliffe, Euclid, Ohio 44132

Filed Aug. 14, 1978, Ser. No. 933,500

Int. Cl.³ F24D 5/00

U.S. Cl. 237-12.1

12 Claims



1. A self-contained, self-starting, heat powered air heating system for residential use comprising:
a vapor generator for converting a liquid to a vapor;
a rotary vapor turbine mounted in a container and connected for receiving all of the vapor coming from said vapor

generator and producing work during the expansion of the vapor passing therethrough;
 a heat exchanger mounted at an elevation above said vapor generator for receiving all of the vapor exhausting from said turbine and operating at subatmospheric pressure for condensing said vapor;
 feed pump means directly driven by said turbine and mounted at an elevation below the heat exchanger and between the heat exchanger and the vapor generator in a fluid flow relationship and connected to return said condensed vapor from said heat exchanger to said vapor generator;
 fa means located exteriorly of said turbine container for conducting air over said heat exchanger to extract heat therefrom;
 hermetically sealed drive means connecting said turbine to drive said fan means without shaft penetration of said container;
 said vapor generator, said turbine, and said heat exchanger being connected in a hermetically sealed closed-loop cycle;
 a gas burner for heating said vapor generator; and,
 control means for controlling the flow of fuel to said burner including a thermostat responsive to the demand for heat at the point of use.

4,295,607

LAND IRRIGATING SYSTEM AND METHOD


Allen T. Noble, P.O. Box 1201, Boise, Id. 82701

Continuation-in-part of Ser. No. 923,291, Jul. 10, 1978, abandoned, which is a continuation-in-part of Ser. No. 887,792, Mar. 17, 1978, abandoned. This application Jun. 15, 1979, Ser. No. 48,886

Int. Cl.³ A01G 25/09

U.S. Cl. 239—1

14 Claims



1. In connection with land irrigation wherein a moving sprinkler means having a water inlet means at one point moves along the length of a stationary water supply means having a plurality of water outlet valve means at spaced intervals along the length thereof, the method of successively connecting water outlet valve means of the stationary water supply means with water inlet means of the water sprinkler means to obtain substantially continuous water supply to the water sprinkler means comprising

providing a conveyance means for movement along the length dimension of the stationary water supply means at the same overall rate of movement as the moving water sprinkler means, the conveyance means carrying a support means supporting an elongated water conduit means for rotation of the elongated water conduit means around one end portion of the elongated water conduit means, the elongated water conduit means including water flow control valve means for closing the elongated water conduit means to water flow and having connecting means at the other end portion of the elongated water conduit means for rotatable water flow connection of the elongated water conduit means with any water outlet valve means, the elongated water conduit means being rigid from one end portion to the other end portion and having water outlet means connecting said one end portion of the elongated water conduit means for continuous water flow from the elongated water conduit means to the water inlet means of the water sprinkler means during water flow connection of the other end portion of the elongated water conduit means with a water outlet means, the steps including closing the elongated water conduit means water flow control valve means, rotating the elongated water conduit means around the one end portion of the elongated water conduit means to bring the other end portion of the elongated water conduit means into contiguity with a water outlet valve means, rotatably connecting the connecting means at the other end portion of the elongated water conduit means to the contiguous water outlet valve means for water flow through the elongated conduit means to the sprinkler means, opening the elongated water conduit means water flow control valve means, subsequently rotating the so-connected elongated conduit means around the connected water outlet valve means while moving the conveyance means along the length dimension of the stationary water supply means, and accommodating the rigidity of the elongated water conduit means during movement of the conveyance means by supporting the support means for movement toward and away from the stationary water supply means on a movable support means carried by the conveyance means, the movement being between a position of the support means closest to the water supply means when the conveyance means is far from any one of the water outlet valve means and a position of the support means farthest from the water supply means when the conveyance means is close to any one of the plurality of water outlet valve means.

gated water conduit means with any water outlet valve means, the elongated water conduit means being rigid from one end portion to the other end portion and having water outlet means connecting said one end portion of the elongated water conduit means for continuous water flow from the elongated water conduit means to the water inlet means of the water sprinkler means during water flow connection of the other end portion of the elongated water conduit means with a water outlet means, the steps including closing the elongated water conduit means water flow control valve means, rotating the elongated water conduit means around the one end portion of the elongated water conduit means to bring the other end portion of the elongated water conduit means into contiguity with a water outlet valve means, rotatably connecting the connecting means at the other end portion of the elongated water conduit means to the contiguous water outlet valve means for water flow through the elongated conduit means to the sprinkler means, opening the elongated water conduit means water flow control valve means, subsequently rotating the so-connected elongated conduit means around the connected water outlet valve means while moving the conveyance means along the length dimension of the stationary water supply means, and accommodating the rigidity of the elongated water conduit means during movement of the conveyance means by supporting the support means for movement toward and away from the stationary water supply means on a movable support means carried by the conveyance means, the movement being between a position of the support means closest to the water supply means when the conveyance means is far from any one of the water outlet valve means and a position of the support means farthest from the water supply means when the conveyance means is close to any one of the plurality of water outlet valve means.

4,295,608

SNOWMAKING NOZZLE

Jeffrey A. White, 1 Westmorland Rd., London, Ontario, Canada (N6J 3N2)



Filed Feb. 1, 1980, Ser. No. 117,468

Claims priority, application Canada, Nov. 8, 1979, 339450

Int. Cl.³ F25C 3/04; B05B 7/10

U.S. Cl. 239—14

6 Claims



1. A snowmaking nozzle for use in the production of artificial snow and adapted to be connected to a pressurized supply

of air and water for the concurrent flow of air and water therethrough, said snowmaking nozzle comprising a nozzle housing (1, 101) having a nozzle axis;
 an elongate tubular passageway in said nozzle housing coaxial with said nozzle axis and which, relative to the flow direction of air and water therethrough, has an upstream conically convergent section (3, 103), a central throat section (5, 105) and a downstream conically divergent section (4, 104);
 an elongate restrictor (6, 106) which is a body of revolution positioned in said passageway coaxial with said nozzle axis and which along said nozzle axis is radially spaced apart from said nozzle housing, and having a conically convergent portion (7, 107);
 said elongate restrictor being positioned in said passageway, relative to said flow direction, with the conically convergent portion (7, 107) located in said downstream conically divergent section of said passageway, and a portion of said elongate restrictor also being positioned in said upstream conically convergent section of the passageway, said elongate restrictor being positioned in the passageway such that the widest part of the conically convergent portion is positioned no further downstream than the narrowest part of the central throat section; and
 attachment means (9, 109) between said nozzle housing and said elongate restrictor (6, 106) for fixedly positioning said elongate restrictor in said passageway.

4,295,609

WALL MOUNTED DRINKING FOUNTAIN WITH PUSH BAR ACTUATOR


Frank Brown, Jr., Wilmington, Del., assignor to Sunroc Corporation, Glen Riddle, Pa.

Filed Nov. 6, 1978, Ser. No. 958,146

Int. Cl.³ E03B 9/20

U.S. Cl. 239—29

2 Claims



2. A control for a drinking fountain having a generally horizontally disposed basin with a waste water drain and a bubbler for discharging water in a vertical arcuate path, said control comprising a horizontally elongated push bar, means supporting said push bar enabling inward movement by a small force applied thereto at any point along the length thereof and in a position below the level of the basin and bubbler at a height generally equal to the heights of the arms of a wheelchair whereby the push bar is readily accessible to a handicapped occupant of a wheelchair when the wheelchair is rolled to a position adjacent the drinking fountain, and means associated with the push bar and bubbler to control flow of water from the bubbler, said basin being disposed atop a wall mounted cabinet structure terminating above the floor surface a distance to enable a wheelchair to move partially under the cabinet with the arms of the wheelchair adjacent the lower edge thereof, said push bar being movably disposed in a slot-like opening adjacent the bottom of the cabinet in a position adjacent the hands of a handicapped occupant of a wheelchair whose arms are positioned on the arms of a wheelchair to enable the wheelchair occupant to control water flow, said

control including a valve controlling flow of water to the bubbler, said valve including a generally horizontally disposed actuator rod oriented generally perpendicular to the push bar and inwardly thereof and above the plane of the push bar, said means supporting the push bar including a pivot plate, means supporting the pivot plate for swinging movement about a horizontal axis parallel to the push bar, generally perpendicular to the actuator rod and located above the actuator rod, said pivot plate including means engaging the actuator rod for operating the valve upon inward movement of the push bar, said means supporting said push bar including light force spring means connected with the pivot plate to return the pivot plate and push bar to a position to stop flow of water to the bubbler, said pivot plate being generally vertically disposed and horizontally elongated for supporting engagement with the push bar over a substantial portion of the length thereof with the pivot plate stabilizing the push bar to retain it in parallel relation to its "at rest" position regardless of where forces are exerted on the push bar along its length.

4,295,610

IRRIGATION SPRINKLERS



Lloyd W. Clements, 49 W. Lincoln Ave., Woodland, Calif. 95695

Continuation-in-part of Ser. No. 786,987, Apr. 13, 1977, abandoned. This application Oct. 24, 1978, Ser. No. 954,222

Int. Cl.³ B05B 3/02

U.S. Cl. 239—230

6 Claims



1. In a swiveled irrigation sprinkler, a vertical bearing housing having an upwardly facing annular shoulder, a swivel tube rotatable in the bearing housing, seal means at the lower end of the housing between the swivel tube and the housing, a sprinkler body secured to the upper end of the swivel tube and having an annular shoulder facing the first-mentioned annular shoulder, a thin walled cylindrical tube loosely surrounding the housing and forming a spring sleeve of low friction material, an upper wedge ring having a tapered portion extending into the upper end portion of the sleeve and engaging the annular shoulder of the body, and a lower wedge ring engaging the shoulder of the housing and having a tapered portion extending into the lower end portion of the sleeve.

3. In an improved sprinkler nozzle structure, a tubular nozzle having a discharge portion having segments defining a generally cylindrical orifice at its discharge end, and adjustment means for pressing the segments inwardly to conical form to constrict the orifice, the segments being spaced circumferentially from each other to define wedge-shaped auxiliary orifice slots and having cam surfaces, the adjustment means comprising a nut screwed onto the nozzle and having a ring-like actuator portion engaging the cam surfaces, the nozzle comprising a tube having the discharge end portion thereof longitudinally slotted to define the segments and having an externally threaded portion to receive the nut, the slots extending from a point within the nut outward beyond the nut, the nozzle having an unslotted cylindrical entrance portion of a predetermined internal diameter, the discharge portion being of a substantially lesser internal diameter than said predetermined diameter, the nozzle having a tapered transition portion connecting the entrance portion and the discharge portion, the nut covering the major portion of the length of the segments.

4,295,611


TWO-DIMENSIONAL NOZZLE

Thomas A. Wynosky, Madison, Conn., and Charles A. Campbell, Palm Beach Gardens, Fla., assignors to United Technologies Corporation, Hartford, Conn.

Filed Dec. 11, 1978, Ser. No. 968,598
Int. Cl.³ F02K 1/10

U.S. Cl. 239—265.37

3 Claims



1. A two-dimensional exhaust nozzle construction for aircraft powered by a turbine type power plant receiving the fluid working medium exhausting in the ambient, a collapsible plug centrally mounted in said two-dimensional nozzle, at least one flap adjacent said nozzle and in spaced relationship defining a wall of said two-dimensional nozzle, said flap being a rigid member and said flap and said plug defining a passageway for conducting the fluid in said two-dimensional nozzle exhausting to ambient, said flap and said plug defining a throat angle and (throat are in the passageway, said flap movable in concomitant radial and axial directions to define a first geometry for optimizing the exhaust stream in a subsonic condition by making the throat angle substantially perpendicular at the exit of said flap relative to the plug surface and a second geometry for optimizing the exhaust stream in a supersonic condition by moving the throat within the flap and having its angle greater than the perpendicular relative to the plug surface, and means for scheduling the throat angle and throat area independent of each other.


4,295,612
SHOWER APPARATUS

James D. Betsinger, 19585 Rolling Acres Dr., South Bend, Ind. 46614, and James P. Bailey, 552 Apache Dr., Batavia, Ill. 60510

Filed Oct. 17, 1979, Ser. No. 85,722
Int. Cl.³ B05B 7/32

U.S. Cl. 239—310

24 Claims



1. A shower apparatus comprising a shower head which is to be adapted to be connected to a source of water, means in said head operable by the flow of water to produce a vacuum, a housing having a plurality of reservoirs for containing diverse liquids, a line extending from said vacuum producing means to said housing, first valve means in said housing for selectively connecting one of said reservoirs to said line, second valve means in said housing operable to isolate a portion of the liquid from the selected reservoir and thereafter provide communication to said line so that said predetermined quantity may be drawn by suction to said shower head.

4,295,613


APPARATUS FOR BREAKING BACTERIAL CELLS

W. Edward C. Moore, Blacksburg, and James A. Blanks, Norfolk, both of Va., assignors to VPI Educational Foundation, Blacksburg, Va.

Filed Oct. 3, 1979, Ser. No. 81,415
Int. Cl.³ B02C 17/14

U.S. Cl. 241—2

9 Claims



1. A method of breaking bacterial cells within upright tubes having a tapered closed end comprising harvesting a culture containing bacterial cells in tubes, placing beads in the tubes containing bacterial cells to be broken, oscillating the tubes about a horizontal axis adjacent their upper ends at a rate of approximately 1725 to 1800 cycles per minute, and preventing destruction of proteins and enzymes released during cell breakage by immersing the closed ends of the tubes in a bath of cool liquid during said oscillating step.


4,295,614
PNEUMATICALLY OPERATED GRAIN HANDLING APPARATUS

Ned J. Bond, III, P.O. Box 40246, Houston, Tex. 77040

Filed Oct. 15, 1979, Ser. No. 84,831
Int. Cl.³ B02C 25/00

U.S. Cl. 241—34

9 Claims



1. An apparatus for controlling the delivery of grain which comprises:
(a) a grain hopper having a restricted grain flow outlet;
(b) movable gate means operatively positioned relative to said grain hopper for selectively controlling the flow of grain from the grain flow outlet thereof, said gate having open and closed positions;
(c) grain processing equipment connected to receive grain from said grain flow outlet and which is operated by axial movement of a piston rod where extension thereof operates the equipment and retraction thereof modifies the operation of the grain processing equipment;
(d) grain flow sensor means adapted to be installed in a path of flow for the grain through said hopper and which sensor means forms a pneumatic binary output indicative of the presence or absence of grain flow and further wherein said sensor means is installed in the flow path of grain flowing through said hopper; and
(e) pneumatically powered control means connected to said sensor means and responsive to the signal provided thereby to form a control signal for operation of said gate means, said gate means being opened in the presence of grain flow and being closed in the absence of grain flow by said control means.

4,295,615


SHELL LINER ASSEMBLY FOR ORE COMMINUTING MACHINE

James E. Mishek, Arden Hills, Minn., assignor to Minneapolis Electric Steel Castings Company, Minneapolis, Minn.

Filed Sep. 27, 1979, Ser. No. 79,385
Int. Cl.³ B02C 17/22

U.S. Cl. 241—182

24 Claims



1. A liner assembly for the shell of an ore grinding machine having a predetermined axis of rotation, the liner assembly comprising:
a plurality of longitudinal holder segments having first and second ends and each defining a mounting surface con-

structed for mounting engagement with the inner surface of said shell, and a grinding surface;
each holder segment further defining a longitudinal channel extending from one end to the other, said longitudinal channel having a closed bottom and opening at the grinding surface, and being further defined by longitudinal sides that converge at least in part toward the grinding surface; and a plurality of longitudinal wear inserts for the holder segments, each insert sized for lengthwise insertion into one of said longitudinal channels and being one piece with a cross section that substantially fills the channel, and each insert further comprises longitudinal sides that converge at least in part in conformance with the channel sides so that the insert is retained within the channel;
and means for securing the holder segments to the shell of the ore grinding machine, the holder segments being arranged in the assembly with the longitudinal channels and wear inserts extending axially of the shell.

4,295,616


CHOPPING MECHANISM WITH REMOTE SHEARBAR ADJUSTER

Amos G. Hill, Hesston, Kans., assignor to Hesston Corporation, Hesston, Kans.

Filed Oct. 4, 1979, Ser. No. 81,839
Int. Cl.³ B02C 18/16

U.S. Cl. 241—241

8 Claims



1. In combination with a rotary chopper and a cooperating shearbar assembly that includes a shearbar and a shoulder movable with said shearbar during adjustment of the latter, an adjuster for controlling the position of said shearbar with respect to said chopper comprising:
a support mounting said shearbar for shifting thereof along a first path of travel extending toward and away from the chopper;
a stationary shoulder disposed in spaced opposition to said movable shoulder and held against said shifting with the shearbar; and
a cam wedge operably drivable between said shoulders in engagement therewith along a second, rectilinear path of travel in a direction to effect said shifting of the shearbar, said assembly including means for maintaining said movable shoulder engaged with said wedge.

4,295,617


SELECTABLE DRAG BRAKES FOR ROCKET RANGE CONTROL

Herman R. Oswell, Huntsville, Ala., assignor to The United States of America as represented by the Secretary of the Army, Washington, D.C.

Filed Oct. 2, 1979, Ser. No. 81,302
Int. Cl.³ F42B 13/32

U.S. Cl. 244-3.29

3 Claims



1. Apparatus for controlling the range of a free-flight artillery rocket comprising:

- (a) a plurality of drag brakes disposed around the periphery of the motor of said rocket;
- (b) means for retaining said drag brakes in unextended position said means including a pin for engagement with each of said drag brakes for secured relation thereof;
- (c) actuating means for selectively releasing predetermined pairs of said drag brakes; and,
- (d) means for releasing said drag brakes to an extended position responsive to energization of said actuating means said means for releasing said drag brakes to said extended position being a spring secured to one end of each said drag brake and said rocket.

4,295,618

DEVICE FOR FIXING PIPES, RODS AND OTHER ELONGATED BODIES

Kazutoshi Morota, Fujisawa, and Takuo Yuda, Yokohama, both of Japan, assignors to Nissan Motor Co., Ltd. and Nifco, Inc., both of Yokohama, Japan


Filed Nov. 13, 1979, Ser. No. 93,389

Claims priority, application Japan, Nov. 15, 1978, 53-156074[U]

Int. Cl.³ F16L 3/08

U.S. Cl. 248-73

3 Claims



1. In a device for fixing a tube, rod or other elongated object comprising a base plate, an anchor provided on the bottom surface of said base plate, at least two vertical walls provided on the top surface of said base plate and standing thereon parallel to each other to define at least one upward diverging "U"-shaped housing portion, a pair of opposite engaging projections provided on the upper parts of the inner surfaces of each pair of adjacent vertical walls defining each said housing portion, a foldable fitting portion which is adapted to embrace the object to be fixed, a flexible supporting portion extending from one of said two adjacent vertical walls and connected to said foldable fitting portion for thereby supporting said foldable fitting portion above said housing portion, and a pair of engaging pawls provided on the outer sides of the opposite

ends of said fitting portion, thus permitting said device to positively hold said object through engagement of said engaging pawls with said engaging projections when said fitting portion embracing said object is pushed into said housing portion, the improved device having the members of at least one pair selected from said pair of engaging projections and said pair of engaging pawls provided at different levels thereby making it possible to bring said device to a provisionally fixing position in which one of said engaging pawls is caught by the counter engaging projection when said fitting portion embracing said object is partly pushed in said housing portion, and making it possible to bring said device to a final and completely fixing position when the other engaging pawl is caught by the counter projection when said fitting portion embracing said object is completely pushed in said housing portion.

4,295,619

SOLUTION CONTAINER HANGER


Ralph Kulin, Marengo, and Ronald C. Stauber, Hawthorn Woods, both of Ill., assignors to Baxter Travenol Laboratories, Inc., Deerfield, Ill.

Filed Nov. 13, 1979, Ser. No. 93,356

Int. Cl.³ B65B 67/12

U.S. Cl. 248-95

6 Claims



1. A solution container hanger comprising:

- (a) a first member;
- (b) a second member rotationally affixed to the first member to enable the solution container hanger to be placed in an infusion, drain, or storage position;
- (c) support means attached to the first member to suspend and support a solution container in an infusion position in which the first and second members are substantially parallel;
- (d) support means attached to the second member to suspend and support a solution container in a drain or infusion position in which the first and second members are substantially perpendicular in a drain position and substantially parallel in an infusion position; and
- (e) hanger means attached to the second member to enable the solution container hanger to be hung in an infusion position from a door or other elevated structure.

4,295,620

DEVICE FOR ANCHORING A VESSEL IN A HORIZONTAL FOUNDATION RAFT

Andre LeClou, Saint Remy les Chevreuse, France, assignor to Commissariat a l'Energie Atomique, Paris, France

Filed Feb. 16, 1979, Ser. No. 12,730

Claims priority, application France, Feb. 17, 1978, 78 04577


Int. Cl.³ A47G 23/02

U.S. Cl. 248-154

3 Claims

1. A device anchoring a cylindrical vessel having a vertical axis in a foundation raft, wherein said device comprises a

orifices formed at the lower end of a lateral wall of said vessel and uniformly spaced along its periphery and n mounting elements, each mounting element being constituted by a horizontal cross-pin extending through one of said orifices so that one end of said element is located inside said vessel and the



other end is located outside said vessel and by two identical assemblies for anchoring said vessel in said raft, each anchoring assembly being a rocker-arm system of two tie-bolts anchored in said foundation raft and by a cross-member in which one end of said horizontal cross-pin is rotatably mounted.

4,295,621

SOLAR TRACKING APPARATUS


Bohdan W. Siryj, Cinnaminson, N.J., assignor to RCA Corporation, New York, N.Y.

Filed Mar. 18, 1980, Ser. No. 131,517

Int. Cl.³ F16M 11/12; G02B 21/24

U.S. Cl. 248-183

1 Claim



1. In a solar tracking apparatus the combination comprising: a base; a support member, rotatably secured to the base for rotation about a first vertical axis; means for rotating said support member about said first vertical axis, said means including a first horizontal pulley secured to the support member, and pulley drive means secured to the base and pulley for rotating the pulley with respect to the base; a pivot member rotatably secured to said support member for rotation about a horizontal axis; elevation drive means for rotating said pivot member about said horizontal axis, said elevation drive means including a

second horizontal pulley rotatably secured to the first pulley for rotation about a second vertical axis, and means secured to the support member for rotatably driving said second pulley about said second axis; and a link member pivotally secured to said second pulley at a point spaced from the second vertical axis and to said pivot member at a point spaced from said horizontal axis.

4,295,622


FRAMEWORK HOLDER FOR ATTACHING CONTAINER TO FLOOR MACHINE

Barry L. Cutler, 7 Stanford Ct., East Windsor, N.J. 08520
Filed May 23, 1980, Ser. No. 152,617

Int. Cl.³ A47K 1/08

U.S. Cl. 248-313

4 Claims



1. A holder of framework structure for removably attaching a fluid container to floor and carpet cleaning and polishing machines which comprises at least three parallel elongated upright standards spaced from each other around a circle, an adjustable, encircling strap at the lower ends of the standards for drawing the standards closer together to press them frictionally against a machine for detachably securing them to such a machine, retaining means carried by the standards and forming recesses for receiving and holding said lower encircling strap in place on the standards, an adjustable top encircling strap at the upper ends of said standards to draw them into frictional engagement with a fluid container, and retaining means at said upper ends of the standards and forming recesses for receiving and for holding said top encircling strap in place.

4,295,623

VARIABLE POSITION ARTICLE HOLDER

Eduard H. Schweizer, Dusseldorf, Fed. Rep. of Germany, assignor to Investment Rarities, Inc., Bloomington, Minn.

Filed Feb. 12, 1979, Ser. No. 11,280

Int. Cl.³ A47F 5/12; A47G 1/24


U.S. Cl. 248-456

45 Claims

1. A variable position tape holder for holding cassette, 8-track, or video tape boxes comprising, in combination: a first L-shaped member for holding at least one tape box and including first and second legs, a second L-shaped member including first and second legs, with the first L-shaped member including an L-shaped aperture of a shape and size corresponding to and for receiving the second L-shaped member such that the first leg of the first L-shaped member is U-shaped and includes a central portion and first and second leg portions and the second leg of the first L-shaped member is also U-shaped and includes a central portion and first and second leg portions, with the ends of the leg portions of the first and second legs of the first L-shaped member being joined together forming a corner, with the inside surfaces of the first and second leg portions of the first leg of the first L-shaped member including longitudinal slots, with the second leg of the second L-shaped member including a series of angular support positions comprising a washboard series of angular peaks, with the first

L-shaped member including means for engaging with the angular support positions comprising ratchet levers extending from the ends of the first and second leg portions of the second leg of the first L-shaped member into the aperture along the corner, thus giving the second leg of the first L-shaped member a C-shape, and means for slidably and pivotally mounting the first leg of the first L-shaped member to the first leg of the second L-shaped member comprising detents extending along the end of the first leg of the second L-shaped member which extend into the slots of the first L-shaped member for slidable and pivotal movement therein allowing the first L-shaped member to be slid and pivoted with respect to the second L-shaped member allowing the ratchet levers to engage with one of the angular support positions to thereby hold the first L-shaped member in any one of several angular positions.

38. In an article holder characterized by a member having at least one surface to support at least one article thereon, the improvement comprising a variable position article holder consisting only of: a first member of an unchanging shape; a second member of an unchanging shape substantially the same as the unchanging shape of the first member; with the first member and the second member having an interfitting relation such that in a first position the first member and the second member interfit to form an article holder of a single outline and in a second position the first member and the second member interfit to have an angular relationship with respect to each




other such that one of the first member and the second member forms a base and the other of the first member and the second member forms an article holder and holds articles at any of various angular relationships with respect to the base, and wherein the interfitting relationship between the first member and the second member includes a pivotal and slidable relation.

39. In an article holder characterized by a member having at least one surface to support at least one article thereon, the improvement comprising a variable position article holder consisting only of: a first member of an unchanging shape; a second member of an unchanging shape substantially the same as the unchanging shape of the first member; with the first member and the second member having an interfitting relation such that in a first position the first member and the second member interfit to form an article holder of a single outline and in a second position the first member and the second member interfit to have an angular relationship with respect to each other such that one of the first member and the second member forms a base and the other of the first member and the second member forms an article holder and holds articles at any of various angular relationships with respect to the base, wherein the interfitting relationship includes a plurality of angular support positions formed on the second member and means immovably attached on the first member for engaging with the angular support positions of the second member to thereby position the first member at any one of various angular relationships with respect to the second member.

4,295,624
READING STAND
Wilfredo A. Granada, 2600 Elisha, Zion, Ill. 60099
Filed Sep. 22, 1980, Ser. No. 189,892
Int. Cl.³ A47G 1/24

U.S. Cl. 248—456

4 Claims



1. A collapsible stand for retaining books and similar materials in an inclined position for reading and the like comprising:
 - a plate-like planar member having a supporting surface and an opposed rearward surface;
 - a planar strip member hinged to a lower portion of said supporting surface and extending generally horizontally to form a ledge for retaining a book or similar material, said strip being hinged so that in the open position the ledge extends to form a surface generally perpendicular to the support surface and in the closed position folds against the support surface so that it abuts and is generally parallel thereto;
 - a first arcuate strip section hinged to the rearward surface of said support plate, said strip section being hinged so that in an open position, the arcuate strip extends generally perpendicular from the rearward surface, and in the closed position, the strip folds against the rearward surface so that it abuts and is generally parallel thereto;
 - a retaining member attached to said hinged end of said arcuate strip having a surface which abuts the rearward surface when the strip is in the open position;
 - a catch pivotally mounted on said rearward surface to move along an arc allowing engagement of the catch with said retaining member to retain the arcuate strip in said open position;
 - an arcuate slot extending between opposite ends in said arcuate strip;
 - a plurality of saw-like teeth formed along one edge of the arcuate strip and extending the length thereof;
 - an arcuate female member constructed to receive said arcuate strip in sliding engagement therewith;
 - a pin extending through opposite sides of said female member and through said slot for sliding engagement therewith;
 - a plurality of roller members positioned in spaced apart relation along one edge of said female member and positioned for sliding engagement with an edge of said arcuate strip;
 - a ratchet arm pivotally mounted to an opposite edge of said female member;
 - a spring biasing the ratchet arm so that one end is pivoted to engage the saw teeth on the edge of the arcuate strip; and
 - a resilient restraining member attached to the opposite end of said female member to form a foot, said arcuate strip and arcuate female member cooperating to form a telescoping leg which is adjusted by sliding said female member over said strip and adjusting their relative positions with said ratchet arm, said telescoping leg adjustably varying the angle of inclination of said support surface relative to a horizontal surface.


4,295,625
PRECISION ADJUSTING DEVICE
Wolter W. J. Degger, and Adrianus C. Van Kasteren, both of Eindhoven, Netherlands, assignors to U.S. Philips Corporation, New York, N.Y.

Filed Jul. 18, 1979, Ser. No. 58,413
Claims priority, application Netherlands, Jul. 31, 1978, 7808045

U.S. Cl. 248—466

Int. Cl.³ A47F 7/14

4 Claims




1. A precision adjusting device, comprising a screw body, a holder body and a connecting, elongated torsion member which can be deformed by rotation of the screw body, the torsion member being made of a plastically deformable material, the ends of said member being connected to the screw body on the one side and to the holder body on the other side, the part of the torsion member situated between the two ends being twistable.

4,295,626
RESILIENT MOUNTING FOR A RECLINING SEAT
Eddie A. J. Large, Bayton Rd, Exhall, Coventry, West Midlands, England (CV7 9DT)

Filed Mar. 30, 1979, Ser. No. 25,368
Int. Cl.³ A47B 1/02
U.S. Cl. 248—575

10 Claims



1. A resilient mounting for a reclining seat, said mounting comprising a first member to be secured to a supporting base for the seat, a second member to be secured to the seat and a torsion bar pivotally connecting the second member to the first member, said torsion bar forming a pivot for the two members and providing a return bias when one of the members is tilted relative to the other, said torsion bar having a first bent over free end section which reacts against the first member, a second bent over free end section which reacts against the second member and an elongate rectilinear portion intermediate said free end sections which forms the pivot for the two members, aligned cradles on said first and second members which locate a portion of said elongate rectilinear portion of said torsion bar which forms the pivot, and retainers on said first and second members for rotatably retaining said elongate portion of the torsion bar in said cradles.


4,295,627
SPRING SUSPENSIONS FOR VEHICLE SEATS
Kevin Graves, Cogenhoe, England, assignor to UOP Inc., Des Plaines, Ill.

Filed Oct. 15, 1979, Ser. No. 84,925
Claims priority, application United Kingdom, Oct. 19, 1978, 41225/78

U.S. Cl. 248—588

Int. Cl.³ B60N 1/02; A47C 3/22

5 Claims



1. A spring suspension for a vehicle seat, the suspension comprising a seat frame, a base frame, a scissor-action linkage arm system interconnecting said seat frame and base frame, the system including two pairs of scissor-action linkage arms spaced apart on a common pivot axis, pivotal connections interconnecting the ends of said arms and said frames to permit the frames to move towards and away from one another, each pivotal connection on one pair of arms being coaxial with a corresponding pivotal connection on the other pair of arms, and a biasing spring connected between parts of the suspension which pivot relatively to one another during relative movement of the frames towards or away from each other to bias the two frames away from one another, all of the pivotal connections between one of said seat and base frames and the adjacent ends of the linkage arms connected to said one frame being displaceable connections extending in a common direction to permit both relative pivotal movement between the linkage arms of each pair and relative translational movement between all the linkage arms and said one frame and a motion limiting resilient coupling, including an anchoring spring of limited expansion and contraction connected between said one frame and one of said displaceable connections to the linkage arm system to permit relatively free fore and aft translational movement along said common direction between the whole linkage arm system and said one frame within the limits of expansion and contraction of the spring thereby reducing the transmission of vibration in said common direction between the base frame and the seat frame.

4,295,628
MOLD FOR THE INJECTION MOLDING OF OBJECTS OF LARGE DIMENSION AND COMPLICATED SURFACES FROM PLASTIC MATERIAL

Lubomir Kupf, Prague; Jiri Travnicek, Celakovice; Radomil Adamek, Pardubice, and Josef Kyzlink, Brno, all of Czechoslovakia, assignors to Statni vyzkumny ustav materialu, Prague, Czechoslovakia


Filed Nov. 9, 1979, Ser. No. 93,130
Int. Cl.² B29C 5/00

U.S. Cl. 249—80

13 Claims

1. A mold for forming injection moldings of large dimensions and complicated surfaces from plastic material, comprising a pair of opposed metal base plates, spaced circumferential strips defining a mold cavity, cooling grids composed of tubes embedded in said base plates, shaped forming plates and forming strips removably fixed by fixing means to the internal surface of the base plates forming a part of the active surface of the mold, said active surface of the forming plates and forming

strips, together with the surface of said fixing means which is flush with said forming plates, and the forming strips being



provided with the required surface pattern, and mobile cores for the mold provided on parts of the mold.

4,295,629

MOULD ASSEMBLY FOR USE IN THE MANUFACTURE OF SPHERICAL OR SUBSTANTIALLY SPHERICAL ARTICLES

William Williams, Queniborough, England, assignor to Delta Mouldings (Leicester) Limited, Leicester, England


Filed Aug. 11, 1980, Ser. No. 176,791

Claims priority, application United Kingdom, Aug. 17, 1979, 28822/79

Int. Cl.³ B29C 1/00

U.S. Cl. 249-160

4 Claims



1. A moulding assembly comprising two mould members having mutually confronting surfaces each surrounding a part cavity, a generally spherical mould cavity being defined when confronting surfaces are in contact with one another, lip portions of said surface defining a continuous parting line around a diametral zone of the cavity, said parting line having four portions, comprising two substantially S-shaped portions with two at least substantially straight-line portions, said portions being arranged alternately around the diametral cavity zone, each portion of the line meeting its adjacent portion to include an angle of not substantially less than a right-angle.

4,295,630

FAIL-SAFE ACTUATOR AND HYDRAULIC SYSTEM INCORPORATING THE SAME

Lorin P. Card, Sepulveda, and Otto W. Borsting, Long Beach, both of Calif., assignors to Greer Hydraulics, Incorporated, Chatsworth, Calif.

Filed Aug. 9, 1979, Ser. No. 65,368


Int. Cl.³ F16K 31/143; F15B 13/044

U.S. Cl. 251-14

2 Claims

1. A fail-safe rotary actuator member for imparting rotary movement to the shaft of a rotary valve responsive to a failure condition and for enabling unimpeded conventional operation of said valve during normal operating conditions comprising, in combination, a casing having a cylindrical bore formed therein and having a port at one end thereof, a piston mounted for reciprocal movement within said bore between extended and contracted positions and defining with said bore a variable volume fluid pressure chamber, spring means in said casing biased between said piston and the other end of said casing for urging said piston to said extended position whereat said piston lies adjacent said port end of said chamber, pilot valve means

connected with said port for selectively introducing and bleeding fluid from said chamber, thereby to control the position of said piston in said chamber, a housing on said casing, a drive shaft journaled in said housing and connected to said valve shaft for rotation between first and second positions about an axis of rotation perpendicular to the axis of said bore, a quadrant-shaped yoke member mounted on said drive shaft and including an outwardly open peripheral guide track coaxially arranged with respect to said drive shaft, a flexible cable having one end operatively connected to said piston, said cable being disposed in said guide track of said yoke member, the other end of said cable being operatively connected to said yoke member at a position to induce rotation of said drive shaft



from said first to said second position responsive to movement of said piston from said retracted to said extended position, said cable, when said drive shaft is in said second position, being in a slack condition when said piston is in said retracted position and in a tautened condition when said piston is in said extended position, drive handle means operatively associated with said drive shaft for imparting rotary movement thereto whereby said drive shaft may be rotated by said handle means between said positions without interference from said cable when said piston is in said retracted position, and said cable is effective to rotate said drive shaft to said second position when said piston is shifted by said spring means to said extended condition as a result of outward flow of fluid from said chamber through said port.

4,295,631

SOLENOID OPERATED VALVE

Walter E. Allen, 9 Barry La., Prospect, Conn. 06511

Filed Mar. 21, 1980, Ser. No. 131,950


Int. Cl.³ F16K 31/02

U.S. Cl. 251-30

13 Claims

1. In a valve assembly having a primary valve and a solenoid operated pilot valve with respective linear primary and pilot valve members, each shiftable linearly between open and closed alternate operating positions thereof, the solenoid operated pilot valve being connected to the primary valve for operating the primary valve member to its said alternate operating positions upon operation of the pilot valve member to its said alternate operating positions respectively, the improvement wherein the primary valve member has an axial opening, and wherein the pilot valve comprises a fixed linear pilot valve tube mounted coaxially with and extending through the axial opening of the primary valve member and has an inner fluid passageway through the primary valve member to provide fluid communication between opposite axial sides of the pri-

mary valve member, the primary valve member having fluid sealing means around its said axial opening which remains in sealing engagement with the fixed linear pilot valve tube as the primary valve member shifts linearly between its open and closed operating positions, and the pilot valve member in its



alternate operating positions being operable for selectively opening and closing the said inner fluid passageway of the pilot valve tube for selectively connecting the opposite axial sides of the primary valve member through the primary valve member for controlling the pressure drop across the primary valve member.

4,295,632

METHOD AND APPARATUS FOR REDUCING TORQUE ON AN AIR DAMPER


Roger P. Engelke, Roscoe, Ill., assignor to Barber-Colman Company, Rockford, Ill.

Filed Sep. 28, 1978, Ser. No. 946,478

Int. Cl.³ F16K 1/22, 47/08

U.S. Cl. 251-127

8 Claims



1. A volume air flow controller comprising a duct, a butterfly damper mounted in the duct, said damper movable about a pivot and having leading and trailing portions, and control means adapted to position said damper to control air flow through the duct, and a fixed air flow impedance located in said duct upstream from said damper and extending across said duct generally in the direction of the damper axis, said air flow impedance medially positioned within said duct offset to the leading portion-side of the axis of said damper and displaced from substantially opposite duct wall portions so as to permit portions of the air flow to pass between said opposite duct wall portions and respective sides of said air flow impedance in the directions of said leading and trailing portions respectively, said impedance changing the air velocity profile within the duct so that the velocity of air acting upon at least a portion of the leading portion of said damper is reduced whereby the damper-closing torque resulting from the aerodynamic forces produced by air flow past said damper is reduced.

4,295,633

EXPANSIBLE DEVICE


James W. Sigmon, 2415 Knollwood Rd., Charlotte, N.C. 28211

Filed Jan. 26, 1979, Ser. No. 6,892

Int. Cl.³ F16K 25/00

U.S. Cl. 251-172

24 Claims



1. A force transmitting device capable of sealing against fluid flow while accommodating a limited range of movement and comprising an annular thin wall member having stepped diameter cylindrical portions joined by a force transmitting surface portion which portions cooperate to impart a generally "S" shaped cross-section to said thin wall member, restraining means engaging said thin wall member for supporting inner and outer axial and circumferential terminal end portions thereof against movement, a movable member having a surface contoured to engage one side of said thin wall member for supporting said portions thereof against tensile stress, and means for exerting force against the other side of said thin wall member for transmission therethrough to said movable member, said thin wall and movable members cooperating for accommodating movement by displacement of the material of said thin wall member from one to another of the portions thereof.

4,295,634

STRUT COMPRESSOR

Phillip A. Spainhour, Waukegan; Leonard A. Morrison, Chicago, and Robert S. Hampton, Jr., Wadsworth, all of Ill., assignors to Amco Tools, Inc., North Chicago, Ill.

Filed Jun. 30, 1980, Ser. No. 164,801


Int. Cl.³ B23P 19/04

U.S. Cl. 254-10.5

5 Claims

1. Apparatus for use in assembling and disassembling a strut assembly of the type having a shock absorber axially disposed within a coil spring, comprising in combination a plurality of upright support rails, a first platen fixedly mounted to said support rails, a second platen slidably disposed on said support rails, a plurality of stand-off members depending from said second platen toward said first platen for engagement with said strut, an opening centrally disposed with respect to said stand-off members through which a tool may be inserted for disassembly of said strut, said first and second platens including means for holding said coil spring in a compressed condition therebetween, a third platen slidably disposed on said support rails, a fluid operated piston-cylinder assembly mounted between said second and third platens for moving said platens apart, and

means for fixedly connecting said second and third platens to said support rails at adjustable positions thereon to restrain



said second and third platens against movement relative to said first platen.

4,295,635

UNIVERSAL PNEUMATIC BELLOWS JACK LIFTER
Zdenek Pustka, and Oldrich Krejcir, both of Liberec, Czechoslovakia, assignors to Vysoka skola strojni a textilni, Liberec, Czechoslovakia


Filed Aug. 28, 1980, Ser. No. 182,302

Claims priority, application Czechoslovakia, Aug. 30, 1979, 5907-79

Int. Cl.³ B66F 3/24

U.S. Cl. 254—93 HP

5 Claims



1. Universal pneumatic bellows jack lifter comprising two coaxial elastic bellows of different diameter, one end of each of said bellows being provided with a common closing cover adapted to be fixed to a suitable base, said common closing cover having a central opening, the remaining ends of both bellows being closed by further covers mutually connected by a bar, said bar being provided with at least one termination for the manipulation of a load and means for selectively introducing fluid under pressure into both of the bellows and exhausting it therefrom.


4,295,636
SYSTEM FOR INHAULING AND OUTHAULING LINES
Frederic E. Langford, Redmond, Wash., assignor to Washington Logging Equipment, Inc., Auburn, Wash.

Filed Nov. 16, 1978, Ser. No. 961,224

Int. Cl.³ B66D 1/26

U.S. Cl. 254—304

2 Claims



1. In a system for inhauling and outhauling lines including a drive shaft, a prime mover operably coupled to rotatively drive said drive shaft, and a reversible transmission means operably interposed between said prime mover and said drive shaft for selectively reversing the rotational direction of said drive shaft,
a haulback drum mounted in a haulback shaft and a line wrapped on said haulback drum, and
a main drum mounted on a main shaft and a line wrapped on said main drum, the improvement comprising:
a first gear mounted on and arranged in driven relationship with said drive shaft and a second gear arranged in driven relationship with said first gear mounted on one of said main shaft and said haulback shaft, and clutch means operatively associated with said first and second gears for selectively coupling said drive shaft to said one shaft in driving relationship to rotate the corresponding one of the main drum and the haulback drum mounted on said one shaft to take in a pay out line at a first line speed,
a third gear mounted on and arranged in driven relationship with said drive shaft and a fourth gear arranged in driven relationship with said third gear and mounted on the other of said main shaft and haulback shaft to rotate the corresponding one of the main drum and the haulback drum mounted on said other shaft to take in and pay out line at an effective line speed less than said first line speed,
a fifth gear mounted on and arranged in driven relationship with said drive shaft and a sixth gear arranged in driven relationship with said fifth gear and mounted on the other of said main shaft and said haulback shaft, to rotate the corresponding one of said main drum and said haulback drum mounted on said other shaft to take in and pay out line at an effective line speed greater than said first line speed, said third and fifth gears forming a first gear set and said fourth and sixth gears forming a second gear set, one of said first and second gear sets being affixed to the shaft on which they are mounted, the other of said first and second gear sets being mounted for rotation relative to the shaft on which they are mounted, and
an energy-absorbing clutch means affixed to the shaft on which said other of said first and second gear sets is mounted for selectively and alternately coupling one of the gears of said other set in driving relationship to the shaft on which it is mounted and for selectively allowing restrained, relative movement between said one of the gears of said other set and the shaft on which it is mounted so that the line speed to and from the haulback drum can

be substantially equalized with the line speed respectively from and to the main drum.

4,295,637

GUARD RAIL

Anton Hulek, Goglerfeldgasse 15, A-4020 Linz, Austria

Filed May 15, 1980, Ser. No. 150,075

Claims priority, application Austria, May 23, 1979, 3775/79

Int. Cl.³ A01K 3/00

U.S. Cl. 256—13.1

5 Claims



1. In a guard rail for use alongside a road, which comprises a sheet material profiled to form two substantially U-shaped side portions extending longitudinally of the guard rail and a web interconnecting the side portions, the two side portions and the web defining a substantially U-shaped recess therebetween and the side portions projecting substantially perpendicularly from a plane defined by the web, the U-shaped side portions having the base of the U radially spaced from and substantially parallel to said plane, the improvement of the web being a grid.

4,295,638

NEWAL POST ASSEMBLY


Gene H. Eldeen, 521 Oak St., Farmington, Minn. 55024

Filed Feb. 22, 1980, Ser. No. 123,841

Int. Cl.³ E04H 17/14

U.S. Cl. 256—59

9 Claims



1. A newal post assembly for installation with respect to a floor type surface comprising:
an elongate wooden newal post for intended use in a generally upright orientation and having a transverse bottom surface;
a newal post base comprised as a metal plate member generally rectangular in shape defined by first, second, third and fourth edges respectively and having top and bottom sides with transverse dimensions greater than the bottom surface of the newal post;
a first set of mounting holes in said plate member, said bottom surface of the newal post being positioned over said first set of mounting holes in surface contact with the upper side of the plate member, and a first set of linear fastening members extended from the bottom side of the plate member upwardly through the first holes into the bottom surface of the newal post to secure the newal post with respect to the base, said first set of mounting holes being positioned near the first of said edges centrally

between adjacent edges and positioned to orientate a side of the newal post in flush relationship with said edge;
a second set of mounting holes located in said plate member and located proximate the second, third and fourth edges of said plate member in surrounding relationship to said newal post, and second linear fastening means extending from the upper surface of said plate member through the second set of mounting holes with respect to the floor type surface.
said holes of the first and second sets of holes being generally arranged in three rows on said plate member, a first row being disposed adjacent the first edge of said plate member and having two outer holes from said second set of holes and two intermediate holes from said first set of holes disposed centrally between the outer holes, a second row disposed intermediate between the first and third edges of said plate member and having two outer holes from said second set of holes and two intermediate holes from said first set of holes disposed centrally between the two outer holes, and a third row of holes disposed adjacent the third edge of said plate member comprised of four spaced apart holes from said second set of holes.

4,295,639

COIL SPRING ASSEMBLY AND FORMING METHOD
Thomas J. Wells, Carthage, Mo., assignor to Leggett & Platt, Incorporated, Carthage, Mo.

Filed Oct. 4, 1979, Ser. No. 81,818

Int. Cl.³ F16F 3/04

U.S. Cl. 267—91

36 Claims



20. A coil spring assembly comprising a spring matrix, a border wire, and lacing wire,
said matrix comprising a plurality of rows of coil springs having end loops located in a common plane, said matrix having corner and edge coil springs located around the peripheral edge of the matrix,
said border wire having sides and corners located in close adjacency to border segments of the end loops of said edge and corner coil springs, and
said lacing wire being generally helical in configuration and being wrapped around said border wire and said border segments of said corner and edge coil springs to connect said border wire to said corner and edge coil springs, said lacing wire being operative to maintain the border segment of said corner coil springs in a deflected arcuate configuration contiguous to an arcuate corner section of said border wire, said deflected arcuate border segment of said corner coil springs being of different radius from the remainder of said end loop of said corner coil springs, said spring assembly being manufactured by the method of locating said border wire in close adjacency to the outer peripheral border segments of said end loops of said corner and edge coil springs,
deflecting said border segments of said corner coil springs out of an initial configuration into a different configuration in which said border segments of said corner coil

springs are contiguous to and of approximately the same radius as an adjacent corner segment of said border wire, wrapping said helical lacing wire around said border wire and around said border segments of said edge coils and around said deflected segments of said corner coil springs while maintaining the border segments of said corner coil springs deflected into said different configurations, and releasing said corner coil springs end loop segments from said deflected configurations after lacing the end loops of said sides and corner coil springs to said border wire.

4,295,640


JEWELER'S TOOL

Charles E. Merrell, 6318 SE. Aldercrest, Milwaukie, Oreg. 97222

Filed Jan. 7, 1980, Ser. No. 109,843
Int. Cl.³ B23Q 1/00

U.S. Cl. 269—47

4 Claims



1. A jeweler's kit comprising:

- a base;
- a mandrel holder rigidly securable to the base, the holder including walls defining an opening for receiving a mandrel, one wall of the holder including a threaded hole extending therethrough into the opening;
- an elongated ring mandrel provided with a plurality of working positions having circular cross-sections of differing diameters, the ring mandrel being insertable into the opening in the holder and selectively positional therein to permit each working position to be disposed in close proximity to the holder with the mandrel secured therein;
- a bracelet mandrel provided with an oval-shaped working surface and having a shank extending outward from the working surface, the shank being insertable into the opening of the holder to secure the mandrel to holder, the shank including a threaded hole in an end thereof;
- a fastener having a head and a threaded stud affixed to the head, the stud of the fastener cooperating at one time with the threaded hole in the holder to permit the ring mandrel to be rigidly secured in selected positions by selectively clamping the mandrel within the opening by adjusting the extension of the stud into the opening, the stud of the fastener cooperating at another time with the threaded hole in the shank of the bracelet mandrel to permit the bracelet mandrel to be rigidly secured in the holder by turning the stud until the head of the fastener and a wall of the bracelet mandrel are clamped tightly against opposite sides of the holder.

4,295,641

DEVICE FOR HOLDING A WORKPIECE TO BE MACHINED IN A SPECIFIC POSITION IN RELATION TO A MACHINE-TOOL ON WHICH IT MAY BE FIXED


Pierre Boucher, Objat, France, assignor to Etablissements Boucher Frères, France

Filed Feb. 20, 1980, Ser. No. 122,867

Claims priority, application France, Feb. 20, 1979, 79 04613
Int. Cl.³ B23Q 3/00

U.S. Cl. 269—136

11 Claims



1. A device for holding a workpiece to be machined in a specific position in relation to a machine-tool on which this device may be fixed, even when it is subjected to a substantial clamping force, comprising a fixed jaw having two orthogonal reference surfaces, a jaw movable perpendicularly to one of these surfaces, and a clamping screw, also perpendicular to this surface, for clamping the machined workpiece between the fixed jaw and the movable jaw, and comprising furthermore a structure for receiving the reactions of the stresses exerted on the fixed and movable jaws, this structure having for this purpose a front part against which the fixed jaw bears and a rear part having therethrough a tapped orifice, through which the threaded portion of the clamping screw is meshingly engaged, the improvement consisting in the front and rear parts of this structure being each formed by a flange, and these two flanges being connected to one another, in the central part thereof, by at least one stay-rod parallel to the clamping screw and, in the lower part thereof opposite that where the clamping screw is to be found, by means of at least one compression bar.

4,295,642

ROLL FED SHINGLING MACHINE WITH
PREDETERMINED NUMBERING


Robert J. Kelly, Dayton, Ohio, assignor to The Reynolds and Reynolds Company, Dayton, Ohio

Filed Oct. 15, 1979, Ser. No. 84,492

Int. Cl.³ B65H 39/02; B42B 2/00

U.S. Cl. 270—53

11 Claims



1. A unitary apparatus for processing a roll of a continuous web of forms into controlled sets of shingled forms, comprising:

- (a) unwinding and advancing means for holding a roll of the web and unwinding and advancing the web from the roll,
- (b) numbering means for receiving the web as it is advanced, numbering the forms in groups of predetermined count of at least two forms each, giving the forms in each group related numbers, and numbering the forms in consecutive groups consecutively,

- (c) cutting means receiving the web and separating the numbered forms individually from the web,
- (d) fastening means for securing together the separated individual forms of each group into separate, shingled, overlapped sets,
- (e) said fastening means including a predetermined indexing position in said apparatus,
- (f) conveyor means for receiving the separated forms from the cutting means and transporting them to a predetermined shifting location,
- (g) means for transferring the separated forms individually from the shifting location to the indexing position, and
- (h) shifting means for removing the forms from said conveyor and depositing them on said transferring means.

4,295,643

APPARATUS AND METHOD FOR HANDLING JACKETS
OF PRINTED MATTER


Alejandro J. de la Vega, 629 Ote. Washington St., Monterrey, Nuevo Leon, Mexico

Continuation of Ser. No. 48,064, Jun. 13, 1979, abandoned,
which is a continuation of Ser. No. 897,022, Apr. 17, 1978,
abandoned. This application Jun. 2, 1980, Ser. No. 155,591

Int. Cl.³ B65H 5/30

U.S. Cl. 270—57

16 Claims



1. A method for feeding jackets of printed matter into an inserting machine which is synchronously driven directly by a rotary printing press, comprising the steps of:
diverting alternate jackets from a single press stream into multiple streams of slower throughput;
directing each of said multiple streams to a respective conveyor;
delivering the jackets on each conveyor to an inserting line of an inserting machine; and
prior to entering the inserting line, driving said conveyors at such speed so as to cause said jackets to be spaced apart at such distance so as to be compatible with the operation of the inserter.

4,295,644

DEVICE FOR STACKING THIN-WALLED BAGS

Leonard van der Meulen, Immeuble Saadi, Apt. 22A, Ariana, Tunisia

Filed Jul. 5, 1979, Ser. No. 54,937

Claims priority, application Netherlands, Dec. 9, 1978,
7807513


Int. Cl.³ B65H 39/08

U.S. Cl. 270—60

14 Claims

1. In a device for assembling bags made of thin-walled material comprising
(a) a rotatable stacking drum which cooperates with a sup-

- ply means and a discharge means, and which has one or more locations on the periphery of the drum for stacking material;
- (b) primary clenching means for retaining stacked material against the periphery, the primary clenching means traveling in the rotational direction of the drum; and
- (c) secondary clenching means which travel in a closed path outside the drum, part of the path following a portion of the periphery of the drum; the improvement comprising
(i) first primary clenching movement means for moving the primary clenching means tangentially relative to the stacking drum periphery between a first position adja-



- cent a location for stacking material and a second position tangentially separated from said location; and
- (ii) second primary clenching movement means for moving the primary clenching means radially relative to the stacking drum periphery between a first position pressing against the drum periphery or stacked material and a second position radially separated from the drum or stacked material; such that the movement of the primary clenching means in each of the radial and tangential directions is separately controllable and occurs sequentially, whereby the primary clenching means moves, in sequence, tangentially of the drum periphery, and then radially outwardly from the drum periphery.

4,295,645

DOCUMENT HOPPER WITH ECCENTRIC FLOOR
CYLINDERS AND A FRONT AUGER

Rathindra Nahar, Wayne, and Robert H. Dietze, Bloomfield Hills, both of Mich., assignors to Burroughs Corporation, Detroit, Mich.

Filed Feb. 19, 1980, Ser. No. 122,508


Int. Cl.³ B65H 3/04

U.S. Cl. 271—34

5 Claims


1. A feeder hopper for feeding documents into the feeder nudge belts of a document sorter, comprising:
a base including an open-topped box having a bottom and walls for receiving stacks of documents;
a plurality of openings forming slots through the bottom of said box;
a plurality of rollers extending through the slots in the bottom of the box to serve as low friction supports for the edges of documents placed in the box;
means causing said rollers to rotate and contact edges of documents placed on edge in the box, thereby driving the documents in a first direction to force first ends of the documents against one wall of the box;
an opening forming a slot through said one wall of said box; an additional roller extending through the slot in the one wall of the box in a position enabling it to engage said first ends of the documents;

means causing said additional roller to rotate in a manner to enable it to contact the first ends of the documents; each of the plurality of rollers having an eccentric axis about which it rotates; each eccentric axis enabling a roller, as it rotates, alternately to lift up and drop documents in contact with said roller, thereby lessening the effects of friction on and between the documents to prepare them for ready movement in a second direction substantially orthogonal to the first;



said additional roller having an eccentric axis about which it rotates; said eccentric axis enabling the additional roller, as it rotates, to push against the ends of documents causing them to move between positions determined by motion of the plurality of rollers and positions determined by the eccentricity of the additional roller; and flag means aligned to engage the stack of documents and biased to force the documents in the second direction, thereby driving the documents in the second direction.


4,295,646
KARATE BOARD HOLDING AND STORAGE DEVICE
Derek Squire, 265 Grove St., Apt. C-30, Elizabeth, N.J. 07202
Filed Nov. 5, 1979, Ser. No. 91,236
Int. Cl.³ A63B 69/00
U.S. Cl. 272-76 8 Claims



1. A board holding and storage device comprising a first shelf and a second shelf, a frame, said frame including four posts, said first shelf and said second shelf disposed in parallel spaced apart relationship and secured to said frame, said four posts including a first pair of posts and a second pair of posts, said first pair of posts joined to said second pair by a pair of angle members, said first shelf extending transverse to the longitudinal axis of said four posts, said second shelf being juxtaposed to said first shelf, means to mount said frame to a vertical supporting surface, means to removeably secure the marginal edges of a board to said frame disposing said board parallel and spaced apart from said supporting surface, whereby said first shelf is disposed located in a horizontal plane


extending below said board when said board is positioned having said marginal edges thereof secured to said frame and whereby said second shelf is configured to provide vertical support to said board when said board is disposed having a lateral surface thereof resting on an uppermost lateral surface of said second shelf.

4,295,647
GAME AND ARTICLE FOR USE THEREWITH
James E. Daly, 321 A. Howell Rd., Malvern, Pa. 19355
Filed Mar. 17, 1980, Ser. No. 131,231
Int. Cl.³ A63B 67/00
U.S. Cl. 273-1 G 1 Claim



1. An amusement article comprising:
(a) an open top sock having an ankle encasing portion, and a toe encasing portion; and
(b) a padded enlargement at the toe encasing portion of said sock, said padded enlargement including,
I. a tubular structure of textile material having its opposite ends closed, said tubular structure disposed transversely of said open top sock and disposed so as to protrude beyond the toe encasing portion thereof, and
II. a soft padding material in said tubular structure.


4,295,648
BASEBALL PITCHER'S TARGET
Theodore D. Stromback, 20000 Delaware Ave., Detroit, Mich. 48240
Filed Nov. 22, 1978, Ser. No. 962,925
Int. Cl.³ A63B 61/00
U.S. Cl. 273-26 A 5 Claims



1. A portable baseball pitcher's target for use as a game or practice device whereby said device may be readily assembled and adjusted comprising: a pair of vertical members spaced apart in fixed relationship to each other so that the distance between said members corresponds to the width of a baseball batter's strike zone; a pair of crossmembers spaced apart and extending across the vertical members with the end portions of at least one of the crossmembers in slideable engagement with

the vertical members so that the vertical distance between the crossmembers corresponds to the height of said strike zone and may be adjusted for a range of batter sizes; a means for locking the ends of said crossmembers to said vertical members; a target suspended within the strike zone bounded by said vertical members and said crossmembers whereby a particular area of said zone may be designated, a means for suspending the target within the strike zone comprising a cord having one end portion thereof attached to the target and the other end portion attached to one of the crossmembers whereby the target may be repositioned within the strike zone by varying the length of said cord and the point of attachment to said crossmember; and a means for supporting said vertical members to which the lower end portions of vertical members thereof are attached.

4,295,649
TOY MINIATURE VEHICLE RACING GAME
Julius Cooper, New Hyde Park, N.Y., assignor to Ideal Toy Corporation, Hollis, N.Y.
Filed May 23, 1980, Ser. No. 152,904
Int. Cl.³ A63F 9/14
U.S. Cl. 273-86 B 16 Claims



11. A toy vehicle race game comprising a relatively flat slotless track having at least two track portions each having separate inner and outer lanes defining separate paths of travel, said track sections including unobstructed cross-over sections located adjacent each other defining a cross-over being at least four lanes wide through which toy vehicles may pass from one track section to another, a pair of controllable toy vehicles, means for selectively and independently controlling the controllable toy vehicles to cause them to switch lanes within a track portion and at said cross-over thereby to pass one another and cross from one path of travel to another; a drone vehicle and means for restraining the drone vehicle for movement in one of the lanes of one track portion thereby to provide an obstacle to vehicles crossing into said one track portion.

4,295,650
SURFACE PROJECTILE GAME WITH MALLETS AND THREE-SIDED TARGETS
Joseph D. Keeble, 17829 Lazy Dog Rd., Nevada City, Calif. 95959
Filed Apr. 7, 1980, Ser. No. 137,719
Int. Cl.³ A63B 71/02, 59/10
U.S. Cl. 273-118 R 1 Claim


1. An amusement system for a plurality of player-contestants comprising:
A. a ball of a dimension suitable to permit the ball to be struck by a mallet, when positioned on a playing surface and propelled in rolling motion along segments of a course defined on said surface;
B. a plurality of portable, unitary three-sided targets adapted to be positioned on said playing surface in mutually spaced relation for dividing said surface into mutually spaced

course segments, each of said targets being characterized by three legs of a substantially common length arranged in mutually spaced parallelism defining a pair of adjacent portals arranged in a pair of horizontally converging planes for accommodating passage of the ball, said legs being interconnected by three arms horizontally extended between adjacent ends of the legs and welded thereto;
C. a plurality of course markers, each marker being adapted to be positioned in spaced relation with one target of said plurality for indicating a segment of said course; and
D. a plurality of mallets for use by said player-contestants,



each mallet being characterized by an elongated head and a handle projected perpendicularly from the head, having defined at each of its opposite ends a planar striking surface of an area less than the cross-sectional area of the head and having a resilient covering affixed thereto, said head being tapered at its ends along three sides and said cross-sectional area being substantially of a half-round shape, with the curvature thereof being oppositely related to the handle, and said handle being of a length sufficient to permit a contestant to grasp the end portion of the handle opposite head and swing the head through an area having a length of at least 90°.

4,295,651
PINBALL ACTUATOR AND FEED MECHANISM
Yukio Konta, Gardena, Calif., assignor to Tomy Kogyo Co., Inc., Tokyo, Japan
Filed Jan. 21, 1980, Ser. No. 114,019
Claims priority, application Japan, Aug. 28, 1978, 53-117472
Int. Cl.³ A63F 7/24
U.S. Cl. 273-121 D 14 Claims



1. In a game having a playing surface an object feed and propulsion apparatus for propelling an object across said playing surface which comprises:
a housing associated with said playing surface;
an actuator means movably mounted on said housing and capable of moving from a rest position to an activated position, said actuator means including an actuator-object

contact surface, said actuator means capable of propelling said object across said playing surface when said actuator means moves from said activated position to said rest position and said object is located in an abutting relationship with said actuator-object contact surface;

an object feed means movably mounted on said housing and capable of contacting an object when said object is in a first position wherein said object is located adjacent to said object feed means and moving said object from said first position to a second position wherein said object is located in said abutting relationship with said actuator-object surface;

connecting means operatively associated with said actuator means and said object feed means and capable of translating motion of said actuator means into motion of said object feed means as said actuator means moves from said rest position to said activated position to cause said object feed means to move moving said object from said first position to said second position;

movable means mounted on said housing in association with said object feed means and capable of moving independent of movement of said object feed means;

engagement means located on said movable means and capable of moving said movable means in respect to a force applied to said engagement means;

said object capable of simultaneously cooperatively engaging both said engagement means and said object feed means transferring force from the movement of said object feed means to said engagement means and to said movable means to move said movable means simultaneously as said object is transferred from said first position to said second position.

4,295,652 GOLF BALL

Tasuku Saito, Tokorozawa; Tutomu Noma, Higashimurayama; Tsutomu Matsunaga, Iruma; Nagayoshi Naito, Nagoya; Chiaki Tanaka, Chita, and Motoki Hiratsuka, Nagoya, all of Japan, assignors to Bridgestone Tire Co., Ltd. and Toray Industries, Inc., both of Tokyo, Japan
Filed Feb. 8, 1980, Ser. No. 119,640
Claims priority, application Japan, Feb. 15, 1979, 54-16339
Int. Cl.³ A63B 37/12

U.S. Cl. 273-235 R 7 Claims

1. A golf ball comprising a thread-wound central core and an outer cover for the core, said cover being formed of, as a main ingredient, a block copolyetherester comprising (A) a terephthalic acid unit, (B) a 1,4-butanediol unit, (C) a unit of a dicarboxylic acid, other than terephthalic acid, or a short-chain diol, other than 1,4-butanediol, having a number-average molecular weight of not more than 300 and (D) a poly(alkylene oxide) glycol unit having a number-average molecular weight of from 500 to 3000, the amount of the component (C), being 25/75 through 60/40 in terms of mol ratio to either component (A) or (B), and the amount of the component (D) being 35 through 70% by weight based on the total weight of the copolymer.

4,295,653
PRESSURE-COMPENSATED DIAPHRAGM SEALS FOR ACTUATORS, WITH SELF-EQUALIZATION
Carl R. Coles, Michigan City, Ind., assignor to Zero-Seal, Inc., Arlington Heights, Ill.

Filed Apr. 7, 1980, Ser. No. 138,199
Int. Cl.³ F04B 21/00; F16J 15/30

U.S. Cl. 277-2 12 Claims

1. A sealed transmission device for use in conjunction with apparatus having a working environment therein to be sealed reliably from the external environment and expected to exhibit substantial pressure and within which a function is to be performed by the transmission device; said transmission device including:


a. a seal housing for sealed communication with the working

environment and having an opening exposed to the external environment;

b. a movement transmission means extending movably through said opening;

c. a pressure-withstanding seepage-prone seal normally preventing substantial leakage through said opening while permitting movement of the transmission means, and subject to possible leakage-causing impairment by such movement;

d. an impervious flexible membrane, cooperating with said housing and said transmission means to allow said transmission means to perform a function in the working environment, and to form a hermetic seal between the working environment and said opening and to form a confined space for a sealing liquid between said opening and said membrane; the housing characteristics being such that the



volume of the confined space is substantially constant except for movement of the membrane;

said membrane having a portion free to move, extensively and independently of movement of the transmission means, under influence of pressure of the working environment to accommodate itself to the volume of the confined sealing liquid to maintain that liquid at a pressure on the outer face of the membrane substantially equal to the pressure exerted on the inner face by the working environment;

said device including means effective, in the event of failure of said pressure-withstanding seal, to limit the yielding of the membrane to a safe amount and maintaining a protective pressure on the outer face of the membrane, and at the same time to form a temporary seal between the confined space and the opening permitting the servicing of said pressure-withstanding seal.

4,295,654 SEAL ASSEMBLY FOR A LINKAGE

Toshio Kawamura, Isehara; Noboru Harashima; Hideo Ueda, both of Hiratsuka, and Seiji Sano, Ninomiya, all of Japan, assignors to Kabushiki Kaisha Komatsu Seisakusho, Tokyo, Japan

Filed May 12, 1980, Ser. No. 148,585
Claims priority, application Japan, May 11, 1979, 54-61766[U]; Oct. 5, 1979, 54-137432[U]; Oct. 5, 1979, 54-137433[U]


Int. Cl.³ F16J 15/34, 15/32

U.S. Cl. 277-92 6 Claims

1. A seal assembly in an annular cavity formed by first and second members which are subject to relative rotation, the first member forming an axially facing end wall and a radially facing side wall of the cavity, the second member having an end face forming another axially facing end wall of the cavity opposite the one axially facing end wall, said seal assembly comprising:

a load ring of resilient elastomeric material disposed in said cavity adjacent the end wall of said first member;

a seal ring of wear-resistant elastomeric material bonded to said load ring, said seal ring having a lip formed thereon; and



a wear-resistant annular plate bonded to the end face of said second member whereby said load ring is axially compressed between said first and second members thereby urging said lip into sealing contact with said wear-resistant annular plate.


4,295,655 ROLLER SKATING SHOE

David L. Landay, Brookline, and Alvan H. Wolf, Worcester, both of Mass., assignors to Brookfield Athletic Shoe Company, Inc., East Brookfield, Mass.

Filed Jul. 18, 1979, Ser. No. 40,093
Int. Cl.³ A63C 17/02

U.S. Cl. 280-11.2

10 Claims




1. A roller skating shoe comprising an integral sole-chassis unit injection molded from semi-rigid plastic material, an upper which is in-situ bonded to said sole-chassis unit during molding thereof, front and rear threaded connecting means, each said threaded connecting means being permanently embedded within the interior of said injection-molded sole-chassis unit during molding thereof, each said connecting means including one or more transversely extending portions embedded within said sole-chassis unit for resisting pull out and other forces on said connector means, front and rear skate wheel hangers connected to and retained by said threaded connector means, each of said hangers also including a strut element forming a second connection between said hanger and said sole-chassis unit, and roller skate wheels rotatably mounted on said hangers, said sole-chassis unit providing a substantial mass of semi-rigid plastic material in the region of said front and rear hangers for structurally supporting said hangers.

4,295,656
SKATEBOARD HAVING FLEXIBLE SIDES
Arlan G. Moore, Vail, Colo., assignor to C. Robert von Hellens, Phoenix, Ariz.

Filed Jul. 2, 1979, Ser. No. 53,688
Int. Cl.³ A63C 17/02
U.S. Cl. 280-87.04 A

4 Claims



1. A road skateboard, said skateboard having a wheel truck vertically dependently mounted at the nose and at the tail of said skateboard, said skateboard comprising in combination:


- a board;
- a flexible upwardly convexly curved spine extending along the longitudinal axis of said board for providing structural support intermediate the wheel trucks;
- a pair of flexible wing sections for modifying the resilient resistance to flexing of said board and for establishing a supporting surface for a skater's feet and for providing a shock absorber to smooth the ride and for providing a lateral moment arm to encourage tilting of said board about the longitudinal axis in response to a lateral weight shift by the skater, each wing section of said flexible pair of wing sections extending laterally and upwardly from one side of said spine intermediate the nose and tail of said board in the quiescent state and being flexibly deflectable downwardly relative to the spine of said board and with respect to its configuration in the quiescent state in response to any force applied by the skater and thereby proportionally modifying the resilient resistance of said board; and
- means incorporated within the wheel trucks for reorienting the wheel axles of the wheel trucks in opposed angular deviations in response to tilting of said board and flexing of said board when tilted;

4,295,657
STEERING APPARATUS FOR VEHICLES
Shoichi Sano, Tokorozawa, and Yoshimi Furukawa, Tokyo, both of Japan, assignors to Honda Giken Kogyo Kabushiki Kaisha, Tokyo, Japan

Filed Dec. 28, 1979, Ser. No. 107,718
Claims priority, application Japan, Dec. 29, 1978, 53-163681
Int. Cl.³ B62D 7/00

U.S. Cl. 280-91

8 Claims



1. A steering apparatus for a four-wheeled vehicle wherein a rotational movement of a steering wheel of the vehicle is

converted into a straight-line motion through a steering gear for turning the front wheels of the vehicle, wherein:

the rear wheels of the vehicle are also dirigible; and means are provided for changing a turning direction of said rear wheels with respect to the front wheels of the vehicle, in response to the amount of rotation of said steering wheel, such that said rear wheels are concurrently turned in the same direction as said front wheels when said steering wheel is rotated through a relatively small angle, and in the opposite direction of said front wheels when said steering wheel is rotated through a relatively large angle.

4,295,658

FRONT END SHOCK ABSORBING APPARATUS FOR WHEELED VEHICLE

Mitsubishi Kashima, Gifu, Japan, assignor to Kayaba Kogyo Kabushiki Kaisha, Tokyo, Japan


Filed Apr. 16, 1979, Ser. No. 29,999

Claims priority, application Japan, Apr. 17, 1978, 53-45021

Int. Cl.³ B62K 25/08

U.S. Cl. 280—276

9 Claims



1. A shock absorbing suspension apparatus for a front end of a wheeled vehicle having brake means, the apparatus including a telescopic shock absorber having a first fluid chamber and a second fluid chamber containing a fluid which is urged to flow from the first chamber to the second chamber upon compression of the shock absorber for shock absorption, wherein the improvement comprises:

valve means disposed between the first and second chambers;

actuator means responsive to the brake means for controlling the valve means to progressively restrict fluid flow therethrough as a degree of braking force applied by the brake means to the vehicle increases;

the valve means comprising a check valve which is normally closed and urged to open by fluid pressure in the first chamber, the actuator means being constructed to progressively increase a pressure required to open the check valve as the degree of braking force increases;

the brake means comprising a fluid pressure actuated brake and a high pressure line for supplying high pressure actuating fluid to the brake, the actuator means being connected to the high pressure line and constructed so as to increase the pressure required to open the check valve as the actuating fluid pressure increases;

the valve means comprising a valve element and a compression spring urging the valve element toward a closed position, the actuator means comprising an actuator rod, the actuator rod being urged by the high pressure actuating fluid to compress the compression spring;

the actuator means further comprising a stop, the compression spring urging the actuator rod toward engagement with the stop; and

an adjustment spring urging the actuator rod toward the

stop and adjustment means for adjusting a force exerted by the adjustment spring on the actuator rod.

4,295,659

STEERABLE SELF-SUPPORTING TRAILER


Joseph Mergen, Goshen, Ind., assignor to Bangor Punta Corporation, Greenwich, Conn.

Filed Nov. 15, 1979, Ser. No. 94,526

Int. Cl.³ B62D 13/00

U.S. Cl. 280—405 R

18 Claims



1. A self-supporting trailer system for coupling at its forward end to a towing vehicle comprising:

an elongated frame,

at least a pair of wheels carried by said frame,

a yoke connected to said frame at its forward end and having

a pair of arms,

a front wheel,

means connecting said front wheel and said yoke one to the other for pivotal movement of said front wheel about a substantially vertical axis extending substantially medially between the outer ends of said yoke arms,

means for steering said front wheel in accordance with the turning movement of the towing vehicle including a steering link having pivotal connections at its opposite ends for pivotally connecting said connecting means and said steering link on the one hand and said steering link and the towing vehicle on the other hand,

a hitch assembly including a bifurcated drawbar having a tongue at its forward end and a pair of laterally spaced arms extending rearwardly from said tongue, means carried by said tongue adjacent its forward end for releasably coupling said trailer to the towing vehicle, and means for pivotally coupling each of the drawbar arms and a corresponding yoke arm one to the other for relative pivotal movement about a generally horizontal axis,

the pivotal connections carried by said tongue and the coupling means between said drawbar arms and said yoke arms defining a plane, the pivotal connections carried by said steering link constituting universal joints lying in said plane whereby the steering link connections are maintained in said plane throughout the range of relative pivotal movement between said drawbar and said yoke.

4,295,660

ACTIVE SUSPENSIONS ASSEMBLY FOR A MOTOR CAR
Gabriele Toti, Milan; Giuliano Lenzi, Arese, and Paolo Monti, Lazzate, all of Italy, assignors to Alfa Romeo S.p.A., Milan, Italy

Filed May 30, 1979, Ser. No. 43,793

Claims priority, application Italy, Jun. 8, 1978, 24338 A/78; Mar. 29, 1979, 21421 A/79


Int. Cl.³ B60G 11/26

U.S. Cl. 280—714

10 Claims

1. Active suspensions for a motor vehicle equipped with a car body which is the suspended mass and wheels which are the non-suspended mass, said suspensions comprising usual resilient means and shock-absorbing means inserted between the car body and the wheel hubs, telescopic stay tubes filled

with liquid and inserted, each, between the car body and the hub of a car wheel, level-adjusters operatively connected to said telescopic stay tubes, said level-adjusters being composed by valve means for establishing communication between said telescopic stay tubes alternately with a source of pressurized liquid and with a sump, said valve means comprising means responsive to the variations of the mutual distance between the car body and every wheel, said responsive means being connected to the car body itself and to the hub of every wheel through means for filtering off the signals indicative of said variations of such mutual distance so that the signals originated by shocks due to road unevenness are not detected, said responsive means being operatively connected to said valve means to command them to establish a communication



between said stay tubes and the source of pressurized liquid when a depression of the car body relative to the respective wheel is detected and for commanding them to establish a communication between said stay tubes and the sump when a lift of the car body relative to the respective wheel is detected, said suspensions being characterized in that each of said telescopic stay tubes is operatively connected to a level-adjuster of its own and is also operatively connected to a load-shift adjuster, said load-shift adjuster being means for controlling the distribution ratio of the load shifts between heavily loaded wheels and lightly loaded wheels in the front and the rear wheel assemblies under combined conditions of vehicle pitching and of vehicle rolling by properly interconnecting the stay tube relative to the respective wheel of at least on wheel assembly.

4,295,661

LATCHING MECHANISM FOR MACHINE STABILIZER ARMS USING HYDRAULIC CYLINDERS


Herman J. Maurer, Burlington, Iowa, assignor to J. I. Case Company, Racine, Wis.

Filed Jan. 10, 1980, Ser. No. 111,099

Int. Cl.³ B66C 5/10

U.S. Cl. 280—765

6 Claims



1. In a mobile machine having at least one outrigger arm system.

pivotaly mounted thereon and movable between a lower ground-engaging position and a raised and inactive position powered by a hydraulic cylinder including a cylinder housing and a cylinder rod, said outrigger arm being adapted to provide lateral stabilization for the machine; a latching mechanism for the hydraulic cylinder releasably latching the cylinder rod in a retracted position, the latching mechanism comprising:

a generally flat spring having a generally V-shaped raised portion at one end and mounted at its other end to the cylinder housing so that the raised portion end of the spring extends beyond the end of the cylinder housing with the raised portion extending generally toward the cylinder rod without contacting the rod; and

a radial protrusion at the end of the cylinder rod extending beyond the diameter of the rod such that the radial protrusion contacts and coacts with the raised portion of the spring as the cylinder rod is retracted,

whereby movement of the cylinder rod from an extended position end of the spring, which is otherwise free from contacting the cylinder rod, to contact and slide completely over the protrusion at the end of the cylinder rod when the cylinder rod reaches a preselected retracted position relative to the cylinder housing, and whereby the cylinder rod is held from extension by a spring retention force, less than the hydraulic actuation force of the cylinder, until an unlatching extension force larger than the spring retention force is exerted upon the cylinder rod to overcome the spring retention force and allow extension of the rod beyond the preselected retracted position.

4,295,662

IMAGE WISE DEVELOPABLE SYSTEM

Geoffrey C. Tutty, Christchurch, New Zealand, assignor to INCA Limited, Christchurch, New Zealand

Division of Ser. No. 79,258, Sep. 27, 1979, which is a continuation-in-part of Ser. No. 930,013, Aug. 1, 1978, abandoned. This application Jul. 9, 1980, Ser. No. 167,435

Claims priority, application New Zealand, Aug. 2, 1977, 184811; Feb. 8, 1978, 186415

Int. Cl.³ B41M 5/16, 5/18, 5/20, 5/22

U.S. Cl. 282—27.5

6 Claims



1. An imagewise developable system comprising (I) a substrate supported mixture of (1) a free base of a cationic solvent dye in OH⁻ form, said dye being capable of developing a color or a more intense color upon reaction with an organic acid developing agent, and (2) a binder which (i) is non-polar and non-acid, (ii) does not develop said free base and (iii) is soluble in ASTM class 1 solvents; and (II) a substrate supported organic acid developing agent which is substantially non-crystalline and melts, sublimates or decomposes at a temperature between 50° C. and 400° C., said organic acid developing agent not being in the reactive presence of said free base of a cationic solvent dye in OH⁻ form, but being selectively migratable to imagewise develop the said free base under an action selected from the group consisting of (a) applying selective imagewise pressure to the system, (b) applying selective imagewise heat to the system and (c) applying selective electrical discharge to the system.

4,295,663

3-INDOLYL-3-BIS-AMINO-PHENYL-PHTHALIDE COMPOUNDS

Jean C. Petitpierre, Kaiseraugst, Switzerland, and Robert Garner, Bury, England, assignors to Ciba-Geigy Corporation, Ardsley, N.Y.

Division of Ser. No. 971,768, Dec. 21, 1978, Pat. No. 4,252,975, which is a division of Ser. No. 758,259, Jan. 10, 1977, Pat. No. 4,153,609. This application Aug. 25, 1980, Ser. No. 181,016


Claims priority, application Switzerland, Jan. 16, 1976, 516/76

Int. Cl.³ B41M 5/16, 5/18, 5/22

U.S. Cl. 282—27.5

9 Claims

1. A pressure- and/or heat-sensitive recording material comprising a support which contains, or has coated thereon as colour former at least one 3-indolyl-3-bis-aminophenyl-phthalide colour former of the formula



wherein

R₁ represents alkyl which has at most 12 carbon atoms and is unsubstituted or substituted by halogen, hydroxyl, cyano or lower alkoxy, cycloalkyl, or unsubstituted or substituted phenyl or benzyl wherein the substituents are halogen, nitro, lower alkyl or lower alkoxy,

R₂ represents hydrogen, alkyl which has at most 12 carbon atoms and is unsubstituted or substituted by halogen, hydroxyl, cyano or lower alkoxy, cycloalkyl, or benzyl which is unsubstituted or substituted by halogen, nitro, lower alkyl or lower alkoxy, or

R₁ and R₂ together with the nitrogen atom linking them represent a 5- or 6-membered heterocyclic radical,

X₁ and X₂ independently of one another represent hydrogen, lower alkyl, cycloalkyl, benzyl which is unsubstituted or substituted by halogen, nitro, lower alkyl or lower alkoxy, or acyl having 1 to 8 carbon atoms, and X₁ also represents phenyl which is unsubstituted or substituted by halogen, nitro, lower alkyl or lower alkoxy,

Y represents hydrogen, alkyl which has at most 12 carbon atoms and is unsubstituted or substituted by halogen, hydroxyl or cyano, or benzyl which is unsubstituted or substituted by halogen, nitro, lower alkyl or lower alkoxy,

Z represents hydrogen, lower alkyl or phenyl, and the rings A and B independently of one another are unsubstituted or substituted by halogen, nitro, amino or lower alkylamino.

4,295,664

MEDICATION RECORD-KEEPING PACKAGE

Gloria T. Cutting, 1426 Camden Ave., Los Angeles, Calif. 90025
Continuation of Ser. No. 741,454, Nov. 12, 1976, abandoned.

This application Oct. 11, 1978, Ser. No. 950,306

Int. Cl.² B42D 15/00

U.S. Cl. 283—1 A

16 Claims


1. A medication record-keeping package for hospital use comprising:

- a retention sheet having a plurality of parallel, spaced-apart, adhesive strips thereon;
- a plurality of elongated, separately removable protective strips overlying and adhering to said adhesive strips;
- a cover sheet overlying said retention sheet and said protective strips;
- a plurality of transfer sheets each of a different size, said

transfer sheets being arranged between said cover sheet and said retention sheet in order of increasing size; pressure sensitive duplication coating means for reproducing on said retention sheet and said transfer sheets information recorded on said cover sheet;

binding means for releasably attaching said retention sheet, said transfer sheets, and said cover sheet in a predetermined overlying relationship; and

a plurality of administration columns delineated on said cover sheet and at least one such column delineated on each of said transfer sheets, each of said columns provid-



ing a space for recording the administration of medicine during a particular time period, each successively wider transfer sheet including at least one more of said columns than the preceding transfer sheet, the spacing of said columns corresponding to the spacing of said adhesive strips,

whereby said retention sheet can be detached from said binding means, and said transfer sheets can be sequentially detached from said binding means and attached to said retention sheet along said adhesive strips and thereby combined to provide a progressively updated supplemental record of the information recorded on said cover sheet.

4,295,665

WELL CASING SUSPENSION SYSTEM


Elwood K. Pierce, Coldspring, Tex., assignor to Petroleum Designers, Inc., Houston, Tex.

Filed Sep. 4, 1979, Ser. No. 72,068

Int. Cl.³ F16L 35/00

U.S. Cl. 285—3

13 Claims



1. A well casing suspension mechanism for suspending an inner well casing within and from an outer well casing, said casing suspension mechanism comprising:

casing suspension coupling means adapted to be connected to outer well casing extending into a well bore, said coupling means being formed internally to define an internal

key recess means and internal lock recess means, said lock recess means defining upwardly directed stop shoulder surface means and said key recess means defining internal tapered surface means;

a tubular hanger body being receivable within said coupling means and being connectable to said inner well casing and defining an external lock receiving recess, an external key receiving recess and an external lock positioner recess, said tubular hanger body further defining external tapered downwardly directed shoulder means;

a split ring type locking element being movably positioned about said tubular hanger body and defining lock means adapted to be received within said lock recess means and in engagement with said stop shoulder surface means, said locking element defining key means adapted to be received within said key recess means, said key means defining external tapered surface means being engagable with said internal tapered surface means of said key recess means, said locking element being of spring nature and being normally expanded to a position locating said lock and key means respectively within said lock and key recess means, said locking element being radially contractable by externally applied mechanical force by reaction of said internal and external tapered surface means to withdraw said lock and key means from said lock and key recess means, in said radially contractable condition said locking element being at least partially received within said external lock receiving recess of said tubular hanger body; and

split ring type lock positioning means being received between said tubular hanger body and said casing suspension coupling means and being of spring nature normally contacting said lock positioning element into said lock positioner recess of said tubular hanger body, said lock positioning element being positioned for contact by said tapered downwardly directed shoulder means upon downward movement of said hanger body relative thereto and being radially movable by reacting engagement thereof by said downwardly directed shoulder means against the spring tension thereof into load supporting engagement with said casing suspension coupling and into load transferring engagement with said locking element, said locking element supporting said lock positioning means during said radial movement of said lock positioning means.

4,295,666

SHROUDED TUBE AND COUPLING THEREFOR


Donald G. Melanson, Glastonbury, Conn., assignor to United Technologies Corporation, Hartford, Conn.

Filed Nov. 5, 1979, Ser. No. 91,680

Int. Cl.³ F16L 19/02

U.S. Cl. 285—14

3 Claims



1. A coupling fabricated from aluminum for attaching an inner fuel carrying tube and an outer containment tube, said coupling having an attaching member having a central passage in axial alignment with the opening in the inner fuel carrying

tube, a seating surface at the mating end of said attaching member, a concentric threaded surface axially spaced from said seating surface, a flexible rubber composite sealing element, toroidal in shape frictionally fitted on the outer diameter of said inner fuel carrying tube, a collar on said latter mentioned tube axially restraining said sealing element,

an inner nut having a concentric threaded surface on its inner diameter and a concentric threaded surface on its outer diameter both of said threaded surfaces being disposed on the end adjacent said concentric threaded surface on said attaching member and said threaded surface on the inner diameter being threadably engageable therewith,

an outer nut having a concentric threaded surface on its inner diameter threadably engaging said outer threaded surface of said inner nut,

said inner nut having a depending shoulder engageable with said collar for urging said sealing element in sealing engagement with said seating surface and urging the end of said inner tubes into said central passage, said outer diameter of said inner fuel carrying tube and said inner nut upon coupling said outer nut to bear against said attaching member and a ferrule at the end of said sealing element mounted on the end of said inner fuel carrying tube for preventing the rubber composite material from extruding when said sealing element engages said seating surface.

4,295,667

ROTARY PIPE SWITCH

Gernot Zahs, and Hans-Jürgen Wahle, both of Dortmund, Fed. Rep. of Germany, assignors to Vaccum Gesellschaft für Vakuum-Metallurgie mbH, Dortmund, Fed. Rep. of Germany


Filed Aug. 2, 1979, Ser. No. 62,933

Claims priority, application Fed. Rep. of Germany, Aug. 29, 1978, 7825611[U]

Int. Cl.³ F16L 55/00

U.S. Cl. 285—18

8 Claims



1. A rotary pipe switch for selectively interconnecting a central pipe to a selected one of a plurality of distributing pipes arranged in a circular pattern around said central pipe comprising a pipe elbow having a first end and a second end with a curved portion therebetween, rotary joint means at said first end for connecting said pipe elbow to a central pipe and for enabling rotary motion of said pipe elbow relative to said central pipe, axial compensator means located intermediate said curved portion and said second end of said pipe elbow, connector means attached at said second end of said pipe elbow for enabling connection and disconnection of said second end of said elbow to and from a distributing pipe, and at least two adjusting devices attached to said connector means, said adjusting devices and said axial compensator means being structured to enable axial movement of said connector means toward and away from each of a plurality of distributing pipes to enable said connector means to be attached with and detached from said distributing pipes, said rotary pipe switch also including means at said second end for driving said pipe elbow

to enable selective attachment and detachment of said central pipe and said distributing pipes.

4,295,668

ADAPTER FOR CONNECTING PLASTIC PIPE SYSTEM TO CAST IRON PIPE SYSTEM


Jean H. Louthan, Dallas, Tex.; Russell C. Cox, Taylor, S.C., and William V. Crawford, Williamstown, Ky., assignors to Phillips Petroleum Company, Bartlesville, Okla.

Filed Jun. 27, 1979, Ser. No. 52,900

Int. Cl.³ F16L 55/00

U.S. Cl. 285—21

18 Claims



1. Adapter means for connecting a plastic pipe system to a metallic pipe system, comprising:

(a) an elongated, plastic sleeve having a substantially equal wall thickness throughout its length and having a first end adapted to be joined to said plastic pipe system and a second end adapted to be joined to said metallic pipe system; and

(b) an elongated, metallic reinforcing sleeve, having an outside diameter substantially equal to the inside diameter of said second end of said plastic sleeve and a length less than the length of said plastic sleeve and mounted in said second end of said plastic sleeve with a first end thereof terminating inside said plastic sleeve intermediate the ends of said plastic sleeve and a second end thereof terminating flush with said second end of said plastic sleeve, said first end of said metallic reinforcing sleeve having a significant length thereof tapered from the diametric exterior and an intermediate point along the length thereof inwardly toward the central axis and to said first end thereof.

4,295,669

THERMAL INSULATION ESPECIALLY FOR PIPE, FLANGES AND FITTINGS


Steve A. LaPrade, and John M. Pallo, both of Englewood, Colo., assignors to Johns-Manville Corporation, Denver, Colo.

Filed Apr. 11, 1977, Ser. No. 786,746

Int. Cl.³ F16L 11/12

U.S. Cl. 285—47

9 Claims



1. A thermal insulation device for insulating irregularly shaped objects such as pipe flanges and fittings which comprises:

(a) a single flexible thermal insulation member which has a width at least equal to the width of the object to be insulated and a length equal to the circumference of the object to be insulated;

(b) a single flexible cover sheet having a width and length

each greater than the respective width and length of said thermal insulation member, and to one side of which said thermal insulation member is adhered, said cover sheet forming the outer surface of said thermal insulation device when said device is installed;

(c) detection means passing through said thermal insulation member and said cover sheet to detect leakage of fluid from said object to be insulated and to provide observable indication outside of said thermal insulation device that leakage has occurred from said object; and

(d) securing means to removably secure said device in position surrounding said object to be insulated.

4,295,670

QUICK-DISCONNECT CAM LOCKING SAFETY COUPLING


Richard B. Goodall, Worton, and Richard L. Goodall, Chestertown, both of Md., assignors to Dixon Valve & Coupling Co., Chestertown, Md.

Filed Jun. 11, 1980, Ser. No. 158,501

Int. Cl.³ F16L 37/18

U.S. Cl. 285—91

3 Claims



1. A quick-disconnect cam locking safety coupling comprising:

a hollow male plug having an external peripheral groove, a socket receiving said male plug and having a pair of opposed side openings opposite said peripheral groove, a gasket for sealing between the male plug and the socket, a pair of cam members each having a lever with an opening and lying adjacent the socket and a cam portion passing through one of said side openings and engaging said peripheral groove and each being pivotally connected to the socket for outward movement of the levers away from the socket to disengage the cam portions from the said peripheral groove,

a lug on the socket adjacent each cam member lever and extending through the opening in the lever, the exterior of each of said levers having a recessed portion adjacent the opening in the lever to minimize the distance the lug must protrude from the body of the socket, each lug having an opening therethrough lying substantially in a plane perpendicular to the axis of the coupling, and a wire pin clipped to the lug with a straight arm of the pin passing through each lug opening and accommodated in the recessed portion of the adjacent lever to hold the adjacent cam member in the groove engaging position, and a bent arm of the pin outside the lug and having a bent portion on each side of the lug to center and lock the pin onto the lug.

4,295,671

FLEXIBLE UNION WITH PASSIVE COMPENSATION

Jean C. Clebant, Carbon-Blanc, France, assignor to Societe Europeenne de Propulsion, Puteaux, France


Filed Aug. 27, 1979, Ser. No. 69,738

Claims priority, application France, Sep. 19, 1978, 78 26846

Int. Cl.³ F16L 27/10

U.S. Cl. 285—223

5 Claims



1. A flexible union for connecting together first and second rigid tubular sections capable of oscillating with respect to each other about a central point with a limited angular amplitude, said union comprising:

a first rigid body fast with or forming part of said first tubular section, said first body having an annular projecting portion at one end of said first tubular section, and said projecting portion having a front external surface directed toward said second tubular section and a back external surface directed toward said first tubular section;

a second rigid body fast with or forming part of said second tubular section, said second body having an annular recess completely surrounding said projecting portion and defining therewith an annular gap, said first and second bodies being entirely separated from each other by said annular gap bordered by first and second surfaces belonging respectively to said first and second bodies;

at least a first and a second separate elastic annular elements located in said gap, each element being formed in one piece and having inner and outer faces bound to annular surfaces having the shape of spherical surface parts belonging respectively to said first and second surfaces; and at least one closed annular chamber formed in said gap between said first and second elastic elements and having opposite walls belonging respectively to said first and second bodies, said chamber being completely filled with a substantially non-compressible liquid and being adjacent to at least a portion of the rearward surface of said projecting portion so as to allow the transmission of axial traction forces between said first and second tubular sections through said liquid.

4,295,672

FLEXIBLE TUBE TERMINATING MEANS


Robert A. Williams, 2721 White Settlement Rd., Fort Worth, Tex. 76107

Filed May 14, 1979, Ser. No. 38,650

Int. Cl.³ F16L 13/08

U.S. Cl. 285—287

8 Claims



1. A fitting located around the end portion of a tube and having a shoulder for engagement by a threaded coupling

member, said fitting having a first annular portion located around the end of said tube and a second annular portion located around said tube and extending from said first annular portion, said first annular portion having a diameter greater than that of said second annular portion defining said shoulder therebetween, comprising:

first and second annular members attached together and to said tube by fused metallic means, said first annular member comprising annular means connected to said first annular portion and defining a generally flat annular surface engaging the end face of the terminal end of said tube and extending radially outward therefrom defining one end of an annular cavity surrounding the exterior of said tube, said second annular member comprising an annular portion connected to said second annular portion and spaced axially inward from said generally flat annular surface of said annular means and defining an opposite end of said cavity spaced axially inward from said one end of said cavity, said fused metallic means being located in said cavity bonding said first and second annular members together and to said tube.

4,295,673

VERTICAL ROD EXIT DEVICE


Theodore H. Miller, New Britain, Conn., assignor to Emhart Industries, Inc., Farmington, Conn.

Filed Oct. 9, 1979, Ser. No. 82,538

Int. Cl.³ E05C 9/04, 15/02

U.S. Cl. 292—21

16 Claims



1. In a vertical rod exit device for securing an outwardly opening door in closed position and having at least one latch, means for mounting the one latch on the inner face of the door, a vertically extending latch operating rod having one end portion operably connected to said one latch, a latch rod shift mechanism operably connected to the other end portion of the latch operating rod, means for mounting said shifting mechanism on the inner face of the door, a rotary outside latch operator for attachment to the outer face of the door and journaled for angular movement about a horizontal axis normal to the faces of the door; the vertical extending latch operating rod being horizontally offset from said horizontal axis and in the direction of the free side edge of the door, the rod shifting mechanism being operable to shift the latch operating rod in one vertical direction and to a latch releasing position in response to operation of the rotary outside latch operator, and an inside latch actuator operably associated with the latch shifting mechanism and at all times operable independently of the outside latch operator to shift the latch operating rod in the one direction and to a latch releasing position in response to pressure applied in a door opening direction to the inside latch actuator, the improvement wherein said rod shifting mechanism includes a frame assembly comprising said mounting means, a rod connector, means supporting said rod connector for limited reciprocal vertical movement on and relative to said frame assembly, means for connecting said latch operating

rod to said rod connector, actuating means for moving said rod and said rod connector in said one vertical direction in response to pressure applied in a door opening direction to said inside latch actuator, a key plate, means supporting said key plate for vertical movement on said frame assembly, said key plate being engageable with said rod connector for moving said rod connector and said rod in said one vertical direction and to a latch releasing position in response to angular movement of said outside latch operator and independent of the movement of said actuating means, and a key center operably engaged with said key plate and said outside operator and journaled on said frame assembly for coaxial angular movement with said outside operator, and wherein said rod connector overlies an associated marginal portion of said key plate and said key center underlies another marginal portion of said key plate.

4,295,674

LATCH MECHANISM


John A. Duran, Glendora, Calif., assignor to Avibank Mfg., Inc., Burbank, Calif.

Filed Oct. 1, 1979, Ser. No. 80,246

Int. Cl.³ E05C 3/14

U.S. Cl. 292—190

15 Claims



1. A latch mechanism which comprises:
 - a housing;
 - a rotor assembly rotatably journaled within said housing and rotatable between fully locked and unlocked positions, said rotor assembly having an interior latching surface and an exterior surface;
 - a flag mounted in longitudinally slidable relation with said rotor assembly, said flag having an exterior portion and an interior end and slidable between recessed and extended positions wherein rotation of said flag is restricted to common rotation with said rotor assembly;
 - biasing means for normally biasing said flag to said extended position wherein said exterior portion extends out of said rotor assembly;
 - coupling means for coupling said flag to said housing to prevent rotatable movement of said flag and rotor assembly only when said rotor assembly is in said fully locked position and said exterior portion of said flag is not visible externally of said rotor assembly, said coupling means including a plunger slidably mounted within said housing substantially perpendicular to said flag and slidable between flag engaged and flag disengaged positions, biasing means for biasing said plunger to said flag engaged position and a single indentation having a bottom and wall located on said flag for receiving said plunger only when said rotor is in said fully locked position and said exterior portion of said flag is not visible externally of said rotor assembly; and
 - disengaging means for disengaging said flag from said housing.

4,295,675

COVER FOR PORT LIGHT


Shale J. Niskin, 3415 Chase Ave., Miami Beach, Fla. 33140

Filed Feb. 26, 1980, Ser. No. 124,828

Int. Cl.³ E05C 17/54

U.S. Cl. 292—256.6

4 Claims



1. A locking and sealing arrangement for a port light of a floating vessel, comprising:
 - said port light;
 - a cover member with an outwardly facing rim having formed thereon a pair of spaced-apart, peripheral grooves, a first groove and a second groove;
 - a cover mounting member adapted to be secured to said floating vessel in surrounding relationship to said port light;
 - said cover mounting member having an inwardly facing surface dimensioned and configured to substantially conform to the said outwardly facing rim of said cover member;
 - at least portions of said inwardly facing surface having dimensions larger than said port light to provide a ledge when said cover mounting member is secured to said floating vessel;
 - said inwardly facing surface having a third groove formed therein, said third groove being aligned to be in opposed relationship to said first groove to form a channel when said cover mounting member is in abutting relationship to said ledge;
 - an access bore extending through said cover mounting member and connecting with said channel;
 - an elongated and pliable locking member being adapted to be threaded through said access bore into said channel, whereby said pliable member spans the juncture of said cover member and said cover mounting member; and
 - a resilient sealing gasket being mounted in said second groove, whereby said gasket forms a substantially watertight seal with said inwardly facing surface of said cover mounting member;
 - said cover mounting member being formed of a plastic;
 - said cover member being formed of a transparent plastic material;
 - said cover member having at least one handle mounted thereon for disengaging said cover member from said cover mounting member;
 - said locking member terminating at one end with an enlarged portion, said enlarged portion having dimensions greater than the cross-sectional dimensions of said access bore.

4,295,676

PATIO DOOR SECURITY LOCK

James A. Smith, 1314 Kingstown Pkwy., Smyrna, Ga. 30080

Filed Jan. 15, 1980, Ser. No. 112,216

Int. Cl.³ E05C 17/30


U.S. Cl. 292—262

11 Claims

1. Locking apparatus for use with a pair of panels at least one of which is mounted for sliding movement between an open

position and a closed position in parallel relation to the other panel, said locking apparatus comprising:

- a first member disposed to be stationary with respect to said sliding panel;
- a second member selectably connectable to the sliding panel and being selectably extensible with respect to said first member to occupy at least two positions relative to said first member;



said second member when in one such position cooperating with said first member to maintain said sliding panel at a closed position; and

- said second member when in another such position cooperating with said first member to permit said sliding panel to occupy a partially open position, and operatively associated with said sliding panel to prevent disconnection of said second member from said partially open sliding panel.

4,295,677

SELF-DUMPING HOISTING BUCKET ASSEMBLY


Jerome A. Petrin, 9105 SW. Mt. View La., Tigard, Oreg. 97223

Filed Nov. 14, 1979, Ser. No. 94,046

Int. Cl.³ E04G 21/02

U.S. Cl. 294—73

4 Claims



1. A self dumping hoisting bucket assembly of the class releasable for dumping upon slackening a flexible hoisting suspension by which it is supported, the bucket assembly comprising:
 - (a) a box comprising a bottom, two upstanding side walls, an upstanding rear wall and a front end providing a discharge chute which is substantially open the width and depth of the front of the box and configured to receive a dump truck for loading the bucket;
 - (b) a pair of downwardly opening hooks adjacent the front of the box and substantially exterior of the space vertically above the interior of the box, one being attached to one side wall and the other being attached to the other side wall, each hook comprising an upright shank segment attached at its base to the front portion of one of the side walls, and a retainer segment attached to the top of the

shank segment and arranged reversely to form a recess between the shank segment and the retainer segment; and

- (c) a hoisting suspension for the box comprising
 - (1) a cross beam substantially as long as the box is wide and suspendable horizontally by a hoist above the box,
 - (2) at least one flexible rearward suspensory member connecting the rear of the box to the cross beam,
 - (3) a pair of flexible forward suspensory members connecting the front of the box to the cross beam, each including a coupler configured and dimensioned for releasable engagement with one of the hooks, and each being attached to the cross beam at a location such that it lies substantially exterior of the space vertically above the box, each hook having a coupler guard segment extending outwardly from the top of the shank and arranged upon slackening of the suspension to be engaged by the coupler to effect disengagement of the coupler from the hook.

4,295,678

VAN MODIFIERS


Robert L. Morris, c/o Morr-Van Products, 322 Division La., Beaver, Pa. 15009

Filed Sep. 12, 1978, Ser. No. 941,477

Int. Cl.³ B60P 3/34

U.S. Cl. 296—156

5 Claims



1. An apparatus for rearwardly extending a van body having a rear door opening with vertically spaced apart rear door hinge mountings at each side of the opening comprising an integral hollow generally quadrangular module having a continuous outer shell free from supporting structural framework attached to the vehicle and having a top, spaced side walls, a bottom and a back wall and an inner shell laminated to and supporting said outer skin over at least a major portion of the total area of each of said top, side walls, bottom and back to form a unitary self-supporting structure, said module including spaced apart roof and bottom members connected by a back wall and two side walls, a front wall opening corresponding to width of the rear door opening in the van and defined by said roof, bottom and side walls and vertically spaced fastening means on said module on each side thereof entering said rear door opening and replacing said hinges in said rear door opening for fastening said module therein.

4,295,679

VAN STRUCTURE

Wolfgang Artweger, Windischgarsten, and Walter Freller, Sierning, both of Austria, assignors to "Wohn-Art" Freizeitartikel Gesellschaft m.b.H., Windischgarsten, Austria

Filed Jul. 17, 1979, Ser. No. 58,184

Claims priority, application Austria, Jul. 20, 1978, 5293/78


Int. Cl.³ E04B 1/346

U.S. Cl. 296—171

24 Claims

1. A van structure comprising
 - (a) a box-like main cabin having a floor, two side walls and a roof, the opposite ends of the main cabin being open,
 - (b) two box-like extension cabins each having a floor, two

- side walls, a roof and an end wall interconnecting the side walls, an open end of each extension cabin opposite the end wall thereof being received in a respective one of the open ends of the main cabin,
- (c) longitudinally extending guide means slidably guiding the extension cabins for sliding movement relative to the main cabin and to each other whereby the extension cabins may be telescopically moved into and out of the main cabin,
- (d) means for moving the extension cabins out of the main cabin under a tensile force, and
- (e) a utility unit in the main cabin centered between the opposite ends thereof and constituting a vertically extending separation substantially parallel to the opposite open ends and dividing the main cabin into two compartments, the utility unit including



- (1) two load-bearing carrier elements affixed to the main cabin and spaced from each other in a longitudinal direction and facing the two open ends of the main cabin, the moving means being anchored to the carrier elements and the carrier elements being capable of sustaining the tensile force,
- (2) two transverse walls extending perpendicularly to the side walls of the main cabin and supported by the carrier elements, the transverse walls defining a space with one of the main cabin side walls sufficient to permit passage of a person,
- (3) a wash room facility arranged between the transverse walls,
- (4) a kitchen facility and
- (5) a storage facility, the transverse walls constituting rear walls for the kitchen and storage facilities, respectively, the kitchen and storage facilities facing the respective open ends of the main cabin.

4,295,680

UTILITY BUCKET SEAT


Michael Grasso, 24 Laurie Rd., Brentwood, N.Y. 11717

Filed Nov. 7, 1979, Ser. No. 92,109

Int. Cl.³ A47C 31/00; B63C 9/08

U.S. Cl. 297-193

1 Claim



1. A seat used in association with a pail for sitting, for use as

a buoy, for use as a table top and for use as a cover, which comprises:

- (a) a top seat section for sitting;
- (b) a weight bearing flange for resting on the open end of a pail;
- (c) a buoyant internal section so that the seat will float; and
- (d) means to attach and store a rope to said seat.

4,295,681

SEAT HAVING LUMBAR SUPPORT AND VERTICAL HEIGHT ADJUSTMENT MECHANISM THEREFOR


Leslie A. Gregory, Northampton, England, assignor to UOP Inc., Des Plaines, Ill.

Filed Feb. 19, 1980, Ser. No. 122,152

Int. Cl.³ A47C 3/00, 7/46

U.S. Cl. 297-284

8 Claims



1. A seat backrest comprising a rigid back portion and a resilient upholstered cushion member attached to said back portion, a generally horizontal lumbar pad having an elongated, convex-shaped forward surface located between said back portion and said cushion, said pad being pivotally mounted to one end of a pair of spaced link members; each of said link members being supported at its other end for pivotal movement about trunnions located on each of a pair of threaded adjusting nuts; an adjusting shaft having a left handed thread portion in engagement with one of said adjusting nuts and a right handed thread portion in engagement with the other of said adjusting nuts; spaced bearing means for rotationally mounting said adjusting shaft relative to said backrest; first control means for rotating said shaft to cause said adjusting nuts to move toward or away from each other to cause said links to move, respectively, toward a generally parallel position or toward a generally perpendicular position relative to said lumbar pad, said lumbar pad being fully extended when said links are in said generally perpendicular position and fully retracted when said links are in said generally parallel position, and second control means mounted on said rigid back portion for producing a limited degree of rotation of said adjusting nuts about said adjusting shaft and causing a corresponding pivotal movement of said link members and said lumbar pad so as to tilt said lumbar pad and vary the vertical position of the forwardmost portion of its convex-shaped forward surface relative to the back portion.

4,295,682

SUPERFINE TOOTH SEAT BACK ADJUSTER

Bernd A. Kluting, Radevormwald, Fed. Rep. of Germany, and Vikram H. Zaveri, Springfield, Mich., assignors to Keiper U.S.A., Inc., Battle Creek, Mich.

Filed Nov. 1, 1979, Ser. No. 90,343


Int. Cl.³ A47C 1/026

U.S. Cl. 297-367

25 Claims

1. A hinge fitting for vehicle seats having a tiltable backrest member comprising a first hinge member connectable to a seat rest member, a second hinge member connectable to a backrest member, pivot means connecting said hinge members for relative pivoting movement, an adjustment quadrant for regulating

the operative position of said second hinge member relative to said first having a toothed sector centered on said pivot means provided with fine pitch teeth, toothed pawl means and integral dual side tension linkage mounted on said first hinge mem-



ber on either side of said pawl and toothed sector and in relatively movable compressively clamping and release relationship with said pawl and toothed sector, and manual means for effecting said clamping and release relationships.

4,295,683

ORTHOPEDIC CHAIR


David T. Dubbink, 1339 N. Sultana, Ontario, Calif. 91764, and Lynda L. Vogler, 8855 Mustang Ave., Alta Loma, Calif. 91701

Filed Jul. 11, 1979, Ser. No. 56,532

Int. Cl.³ A47C 5/06

U.S. Cl. 297-377

2 Claims



1. An orthopedic chair particularly adapted for bathing handicapped persons comprising:

- (a) a frame assembly having a pair of spaced side members, a bottom member connected between said side members on one of the ends of said side members, and a top member connected in parallel to said bottom member between said side members on the ends thereof opposite said bottom member, said frame assembly further including support means for supporting said frame assembly and for maintaining the top and bottom members horizontal with said top member above said bottom member when said frame assembly is placed on a substantially horizontal surface, said bottom member further being in the shape of two upward facing U-shaped sections; and,
- (b) a body portion of flexible sheeting connected to said frame assembly between said bottom member and said side members to a point close adjacent the top member to form a sling chair wherein the person can sit supported from a point about the knees up to and including the person's head, said body portion including means for selectively releasing only a portion of said connection of said body portion between said side members adjacent the top portion sufficient to not support the person's head and provide access for washing the back of the person's head and hair while continuing to support the remainder of the person's torso, said releasing means comprising a pair of zippers extending from an edge of said body portion adja-

cent said top member toward said bottom member and disposed to have respective ones of said zippers on opposite sides of the head of the person in the seat, said body portion further being attached to said bottom member so as to form a U-shaped sling in each of said U-shaped sections whereby the legs of the person when placed in respective ones of said slings are supported and separated.

4,295,684

SAFETY BELT WIND-UP DEVICE

Katsumi Naitoh, Fujisawa, Japan, assignor to NSK-Warner K.K., Tokyo and Nissan Motor Co., Ltd., Yokohama, both of, Japan


Filed Nov. 14, 1979, Ser. No. 94,200

Claims priority, application Japan, Jan. 19, 1979, 54-3874

Int. Cl.³ A62B 35/00; B65H 75/48

U.S. Cl. 297-475

8 Claims




1. A safety belt wind-up device including an engageable and disengageable buckle, comprising: a rotatable webbing wind-up shaft driven in a direction for winding up a webbing of the device, wind-up force lock means capable of assuming interlocked and uninterlocked positions with said wind-up shaft, said lock means in said interlocked position preventing a drawn webbing from being further wound up but providing for said webbing to be drawn and wound up within a predetermined length of said drawn webbing, and means for bringing said lock means into said interlocked and uninterlocked positions, respectively, depending upon engagement and disengagement of the buckle of said device, said wind-up force lock means comprising (1) a first member engaged with and being rotatively driven by said wind-up shaft while said wind-up force lock means are in said interlocked position, (2) a first cam rotating together with said first member, (3) a second member engaged with and being rotatively driven by said first member, and (4) a second cam rotating together with said second member, said first and second cams being substantially in a first engagement position when said wind-up force lock means are brought into said interlocked position and said first and second cams being substantially in a second engagement position when said wind-up force lock means are in said interlocked position and said webbing has been drawn said predetermined length out of the device, whereby in the first engagement position even if said first member is rotatively driven by said wind-up shaft in a webbing wind-up direction so as to be rotated together with said first cam, the rotation of said first member is prevented by the first and second cams in the first engagement position, and in the second engagement position even if said first member is rotatively driven by said wind-up shaft in a webbing drawing out direction so as to be rotated together with said first cam, the rotation of said first member is prevented by the first and second cams in the second engagement position.

4,295,685

PLASTIC AND METAL WHEEL TRIM ASSEMBLY
Edward G. Spisak, 35700 Oakwood La., Westland, Mich. 48185
Continuation of Ser. No. 856,309, Dec. 1, 1977, abandoned. This
application Apr. 30, 1979, Ser. No. 34,938
Int. Cl.³ B60B 7/00

U.S. Cl. 301—37 P

4 Claims



1. A composite wheel trim assembly of metal and plastic for attachment to a vehicle wheel, comprising: a unitary disc-shaped body member of plastic material having axially outwardly disposed primary surfaces and deep recesses having axially extending walls forming secondary surfaces extending from adjacent said primary surfaces for reinforcing said body member, said primary surfaces occupying a substantial portion of the area within the circumference of the body member, a metal cover member of thin sheet metal having an outline and axially inward surface configuration corresponding to the shape of said primary surfaces, fastening means coacting with said metal cover member and an inboard surface portion of said plastic body member to hold said cover member to said primary surface to reinforce said body member and provide a decorative metal layer having substantially all of its said inner surface in contacting relationship with all of said primary surface area and leaving said secondary surfaces exposed, and a retainer assembly attached to said body member for attachment to a vehicle wheel.


4,295,686

DISK WHEEL WITH RESILIENT BEARING SUPPORT AND RIGID ANNULAR TREAD MOUNTING SURFACE
John W. Black, Hickory Corners, Mich., assignor to Pemco-Kalamazoo, Inc., Kalamazoo, Mich.

Continuation of Ser. No. 964,130, Nov. 27, 1978, abandoned.
This application May 5, 1980, Ser. No. 146,895
Int. Cl.³ B60B 1/06; F16C 33/00

U.S. Cl. 301—63 DD

5 Claims



1. A wheel construction, comprising: rigid circular disk means having means thereon defining a hole in approximately the center thereof, said disk means having a radially outwardly facing surface thereon, a pair

of laterally spaced axially outwardly facing surfaces contiguous with said radially outwardly facing surface and at least a pair of laterally spaced, radially inwardly facing surfaces on opposite axial sides thereof each contiguous with an axially facing surface;

bearing means and resilient means for mounting said bearing means in said hole to facilitate the rotation of said rigid circular disk means about a defined axis of rotation;

an annulus made of a rigid first moldable synthetic resin material and securing means for fixedly securing said annulus to said rigid circular disk means, said securing means comprising at least a pair of integral portions of the material of said annulus on opposite lateral sides thereof extending radially inwardly around said axially facing surfaces and axially inwardly and in contact with said axially facing and said radially inwardly facing surfaces on said disk means, said annulus having no fusion bonding affinity to the material of said disk means, said annulus also having a peripheral surface thereon defining a tread mounting surface; and

an annular tread made of a second moldable synthetic resin material in close and intimate contact with said peripheral surface on said annulus and fusion bonding said tread and said annulus together thereby to firmly and securely lock said tread to said annulus.

4,295,687

ELECTRIC BRAKE SYSTEM


James Becker, Ann Arbor, and Daniel L. Neill, Belleville, both of Mich., assignors to Kelsey Hayes Company, Romulus, Mich.

Filed Feb. 26, 1979, Ser. No. 15,572

Int. Cl.³ B60T 13/68

U.S. Cl. 303—20

7 Claims



1. A braking system for controlling electrically operated brakes for a driver controlled vehicle comprising braking means electrically energizable for applying a braking force to the brakes, an electric energy source, control means selectively adjustable by the driver in accordance with a desired braking force, said control means developing a control signal only after a predetermined initial adjustment that varies rapidly from a threshold magnitude to a certain magnitude and thereafter varies linearly with a further adjustment thereof, controller means operative to couple said braking means to said source in response to such control signal, said controller means developing a pulsating output for energizing said brake means having a predetermined frequency and having a pulse width determined by the magnitude of such control signal, and excessive current protection means operative in response to a predetermined high current level in such controller means output for inhibiting such controller means output for a predetermined limited period of time including an AND gate having a plurality of inputs and an output, means supplying the pulsating output to one of said gate inputs, means connecting said gate output to energize said brake means, and means connected to another of said gate inputs for blocking said gate output for such predetermined limited time period in response to such predetermined high current level in the controller output.

4,295,688

BEARING CONSTRUCTION


William Blasnik, Demarest, N.J., assignor to Hardware Designers, Inc., Mt. Kisco, N.Y.

Filed Feb. 25, 1980, Ser. No. 124,094

Int. Cl.³ F16C 19/16, 29/04, 35/06

U.S. Cl. 308—3.8

5 Claims



1. A bearing device for supporting drawers or the like for translatable movement, said device comprising a generally disk-shaped polymeric tire member including a circular peripheral surface defining a runner, an enlarged bore portion extending axially from one end face of said tire member and terminating in an outer bearing race directed toward said one end face, a reduced bore portion extending from the other end face of said tire member and merging with said outer race at the radial innermost end of said race, an annular recess formed on the outer face of said other end of said tire member and forming a radial outward extension of said reduced bore portion, a metallic stud member forming a fixed component of said bearing member, said stud member including an enlarged head portion at one end disposed within said enlarged bore portion and a generally cylindrical shank extending outwardly through said reduced bore portion, an inner bearing race formed on said stud member at the transition between said head portion and shank portion, a plurality of spherical members interposed between said outer and inner bearing races, an annular collar member formed at the other end of said stud member and projecting outwardly beyond said reduced diameter bore, a plurality of tab portions struck from said collar member, said tab portions being disposed within said recess at positions axially outwardly of said reduced diameter bore whereby the axially outwardly directed face of said collar member, after formation of said tab portions, presents an axially directed, discontinuous crown configuration, the axial terminal portions of said crown configuration lying in a plane axially beyond all portions of said other face of said tire member, said stud member including, in addition, a cylindrical deformable attachment member extending axially beyond said plane of said crown configuration whereby said bearing member may be mounted within an aperture in a bracket with said crown configuration engaging one face of said bracket and turned-over increments of said attachment member engaging the opposite face of said bracket.

4,295,689

ADJUSTABLE CLEARANCE FOIL JOURNAL BEARING AND METHOD OF MANUFACTURING FOIL ELEMENT THEREFOR

Lazar Licht, San Mateo, Calif., assignor to United Technologies Corporation, Hartford, Conn.

Filed Aug. 30, 1979, Ser. No. 71,508


Int. Cl.³ F16C 32/06

U.S. Cl. 308—9

13 Claims

1. A hydrodynamic foil journal bearing comprising a stationary retaining member having a bore and a slit communicating with said bore; a resilient foil insert assembly mounted on said retaining member in said bore and having a first bearing surface; a rotatable journal disposed within said bore and having a

second bearing surface cooperative with said first bearing surface to induce a fluid film therebetween; and



means on said retaining member associated with said slit for varying the size of said bore to provide desired clearance and loading in said journal bearing.

4,295,690

HYDROSTATIC BEARING FOR A RADIAL PISTON MACHINE

Peter Rutz, Brunnelihofstrasse 2, CH-8400 Winterthur, Switzerland


Filed Jan. 29, 1980, Ser. No. 116,492

Claims priority, application Switzerland, Mar. 1, 1979, 2029/79

Int. Cl.³ F16C 32/06

U.S. Cl. 308—9

7 Claims



1. A hydrostatic bearing for a radial piston machine, said bearing comprising

a stationary cylindrical pintle having at least one bore therein for conducting a flow of high pressure medium, a hydrostatic bearing pocket in one surface thereof and a throttle communicating said bore with said bearing pocket to deliver a throttled flow of pressure medium thereto, said surface having a radius larger than the adjacent surfaces on either side of said bearing pocket; and a member rotatably mounted on said pintle, said member having a circular cylindrical bore of a radius approximately equal to said radius of said one surface.

4,295,691

MOUNTING GROMMET

Randall J. Rubenthaler, Lincoln, Nebr., assignor to Caterpillar Tractor Co., Peoria, Ill.

Continuation of Ser. No. 742,145, Nov. 15, 1976, abandoned.

This application Feb. 15, 1978, Ser. No. 878,009


Int. Cl.³ F16C 27/00

U.S. Cl. 308—238

2 Claims

1. A mounting grommet comprising: a sleeve of hard material; a tubular, elastomeric element extending about and along the

length of said sleeve, said element having a length greater than that of said sleeve and including
a cylindrical shank having an enlarged head at one end, said head having an axial length considerably shorter than that of said element;
an axially opening and extending annular recess in said head at its interface with said shank, the radially inner wall of said recess being of the same diameter as said shank,



said head having a generally frusto-conical surface on its side opposite said recess, the radially outer portion of said frusto-conical surface being located intermediate the ends of said elastomeric element; and
means for axially compressing said element to a length about equal to that of said sleeve;
whereby said recess will deflect radially inwardly to a location partly in said head and partly in said shank.

4,295,692

DISHWASHER TUB ASSEMBLY


Thomas E. Jenkins, Louisville, Ky., assignor to General Electric Company, Louisville, Ky.

Filed Dec. 5, 1979, Ser. No. 100,682

Int. Cl.³ A47B 77/06; B08B 3/00

U.S. Cl. 312-228

12 Claims



10. A dishwasher tub assembly comprising a plastic open front tub having a generally rectangular cross-section;

a plastic supporting rib frame comprising a plurality of ribs extending parallel to and spaced equidistantly from each other formed on the external periphery of said tub adjacent the front opening thereof;

a plurality of plastic cross-ribs formed on the external periphery of said tub and intersecting said rib frame at an angle thereto;

plastic support ribs formed on the external periphery of each side of said tub spaced apart from said rib frame;

a plastic base mounted on the bottom of said tub comprising a generally hollow box-like structure with horizontal dimensions approximating those of the lower wall of said tub, and having an open bottom generally rectangular cut-outs in the front and two side sections, and a generally semielliptical cut-out in the rear section; and
said plastic tub, rib frame, cross-ribs, support ribs, and base

comprising a single unit of homogeneous one-piece construction.

4,295,693

KNOCKED-DOWN CABINET

Ake E. Viklund, Sjöfö, Sweden, assignor to Aktiebolaget Electrolux, Stockholm, Sweden


Filed Nov. 14, 1979, Ser. No. 94,181

Claims priority, application Sweden, Apr. 9, 1979, 7903119

Int. Cl.³ A47B 43/00

U.S. Cl. 312-257 R

5 Claims



1. A cabinet which is assembled without the use of fastening means and having a rear wall, two side walls, and a frame-shaped front wall which are all interconnected to form a box-like structure, the adjacent edges of said rear and side walls having bent portions which upon abutment and pivoting hook one another to form a joint which prevents separation of said side walls and rear wall wherein said adjacent edges of said rear wall and side walls are bent to extend generally vertically to said rear wall and abut each other, aligned apertures in each of said generally vertical edges, and shelf supports having means for insertion through said apertures in order to lock said rear and side walls together, said rear wall having an edge which is generally bent at right angles to the plane of said rear wall and which projects into the interior of the cabinet, an outer portion of said edge having a reverse bend, said adjacent side walls having a bent edge which is inserted in a groove formed between said outer portion of the edge of said rear wall and the reverse bend portion, and a portion intermediate said bent edge and said side wall which forms an extension to said rear wall and is coextending therewith to form an outer even surface of the rear wall of said cabinet, and a top part having opposite edge portions that are bent at an angle to said top part and are adapted to slide over adjacent edges of said side walls and interconnect with said frame-shaped front wall, and rear and side walls.

4,295,694

INTERCEPTOR PLUG

Robert E. Manning, 310 Siesta Ave., Thousand Oaks, Calif. 91360

Filed Jun. 21, 1979, Ser. No. 50,709

Int. Cl.³ H01R 15/00

U.S. Cl. 339-8 P

1 Claim


1. An interceptor plug for intercepting an phone signal available at a standard electrical jack comprising:

(A) a central shaft of electrically conductive material having an integral interior tip, said tip being eccentric relative to said central shaft;

(B) an electrically insulating sleeve concentric and coextensive with said central shaft except for said tip;

(C) an electrically conductive sleeve concentric and coextensive with and exterior to said insulating sleeve except

that the length of said conductive sleeve is adjusted to expose said insulating sleeve at said interior tip end;
(D) a positioning sleeve of electrically insulating material surrounding the combination of said central shaft, insulating sleeve and conductive sleeve so as to insulate said conductive sleeve from the body of said jack;



(E) a grip of nonconductive material firmly affixed to said positioning sleeve, said grip surrounding two conductive wires running lengthwise through said grip and extending beyond the ends of said grip; and,
(F) a connection means for connecting one of said wires to said exterior end of said central shaft and the other of said wires to said exterior end of said conductive sleeve.

4,295,695

ELECTRICAL CONNECTORS

Robert J. Dodds, Crewe, England, assignor to International Computers Limited, London, England


Filed Oct. 5, 1979, Ser. No. 82,095

Claims priority, application United Kingdom, Oct. 12, 1978, 40355/78; Oct. 21, 1978, 41471/78

Int. Cl.³ H01R 1/11

U.S. Cl. 339-17 F

9 Claims



1. An electrical connector cable assembly having an integrally formed edge connector element at each end thereof for electrically interconnecting first and second edge type connector units each having first and second contact arrays located on opposite sides of a connector unit receiving region so that the first contact arrays of the first and second connector units are interconnected and the second contact arrays of the first and second connector units are interconnected, the assembly comprising:

two elongate connector element stiffening members each providing first and second surfaces separated by a predetermined distance; a length of electrically non-conductive substrate folded about the two stiffening members so that the first and second surfaces of the stiffening members are covered by the substrate material and are interconnected by at least three side-by-side layers of the substrate;

the substrate having on a first surface thereof two groups of contact areas each including first and second arrays of electrical contact areas, extending across the width of the substrate, the arrays being so located on the substrate first surface that when the substrate is folded about the stiffening members a said first contact array coincides with each of the stiffening member first surfaces and a said second

contact array coincides with each of the stiffening member second surface;
a first electrical conductor system provided on the substrate first surface interconnecting the first arrays of the first and second groups and a second electrical conductor system provided on the substrate first surface interconnecting the second arrays of the first and second groups.

4,295,696

STRAIN RELIEF FOR CONNECTOR WIRES


Vincent F. Gray, Oklahoma City, Okla., assignor to Western Electric Company, Incorporated, New York, N.Y.

Filed Dec. 17, 1979, Ser. No. 104,241

Int. Cl.³ H01R 13/58

U.S. Cl. 339-17 C

1 Claim



1. A connector and strain relief assembly, which comprises: a flat circuit board for mounting the connector, said board having an array of terminals interconnected to said connector;

a cable comprising a jacket and a plurality of insulated wires, the ends of which extend beyond the end of the jacket and are fanned across the board and solder secured to the terminals;

a T-shaped strain relief having a crossarm overlaying the wires and a stem with a knob formed thereon and positioned beneath an end section of said cable jacket, the crossarm of said strain relief being provided at one end section thereof with a projecting member that is undercut along one edge to form a nub, said undercut extending as a bevel surface to a straight line post section which is approximately equal in length to the thickness of the board, and the other end section of the crossarm being provided with a projecting cylindrical boss having a frusto-conical head, the central axes of the boss and the head being offset with respect to each other so that a lobe portion of the head overhangs the boss;

said board having a slot formed across one edge to receive the projecting member with the nub thereof underlying the circuit board, and said board having a hole formed therein to receive the projecting boss with the lobe portion underlying the circuit board, said hole and cylindrical boss being so positioned that the lobe deflects the boss when the strain relief is pressed to move and snap the lobe through the hole into the circuit board underlying position, said movement of the frusto-conical head through the hole acting to move, the bevel surface of the projecting member along the bottom edge of the slot to seat the straight line post section, against the bottom of the slot, and

means projecting from the crossarm to limit the movement of the crossarm toward the circuit board and thus limit the strain relief force applied to the array of wires by the assembled circuit board and strain relief while holding both the overhanging lobe portion of the frusto-conical head and the juncture of bevel surface with the post in close proximity to the underside of the board.

4,295,697

ELECTRICAL POWER DISTRIBUTION SYSTEM PRINCIPALLY FOR SPACE-DIVIDING PANELS IN OFFICE BUILDINGS


Paul R. Grime, Erie, Mich., assignor to Owens-Corning Fiberglass Corporation, Toledo, Ohio

Filed Jan. 31, 1980, Ser. No. 117,405

Int. Cl.³ H02G 3/28

U.S. Cl. 339—22 R

5 Claims



1. An electrical power distribution kit comprising an elongated molded plastic electrical power distribution block having electrically conductive members molded therein, the conductive members of the block having terminals accessible respectively from opposite ends of the block, and an elongated molded plastic slide-in duplex receptacle having electrically conductive members molded therein, each of the block and receptacle members having aligning and interlocking means thereon cooperable with aligning and interlocking means on the other, the receptacle being fastenable to the block by sliding the receptacle in the direction of its length along one side of the block in the direction of the length of the block and thereby engaging the cooperable aligning and interlocking means with each other, the receptacle being engaged with a portion of one end of the block and with the one side of the block when fastened thereto, the conductive members of the receptacle having terminals cooperatively engageable respectively with terminals of the conductive members of the block adjacent the one end thereof as the receptacle is fastened to the block by engagement of the cooperable aligning and interlocking means with each other, the terminals of the conductive members of the block being recessed within the block respectively in recesses therein, the terminals of the conductive members of the receptacle respectively being shielded by plastic sleeve portions of the receptacle, the plastic sleeve portions being receivable respectively in recesses of the block as the terminals of the conductive members of the receptacle are cooperatively engaged respectively with terminals of conductive members of the block, the conductive members of the receptacle also having two sets of socket terminals accessible from a front face of the receptacle parallel to the sides of the block when the receptacle and block are assembled, the two sets of socket terminals being spaced longitudinally of the receptacle, and the cooperable aligning and interlocking means being an aligning means when the receptacle is being fastened to the block and an interlocking means when a service cord is being pulled out of one of said sets of socket terminals.

4,295,698

ELECTRICAL CONNECTOR HOUSING

Weichien Chow, Park Forest, Ill., assignor to Bunker Ramo Corporation, Oak Brook, Ill.

Continuation of Ser. No. 949,843, Oct. 10, 1978, abandoned.

This application Dec. 21, 1979, Ser. No. 106,228

Int. Cl.³ H01R 13/42


U.S. Cl. 339—59 R

6 Claims

1. An electrical connector housing for retaining an electrical contact having a forward engagement section, a rearward

termination section and contact shoulders disposed between the engagement and termination sections, the housing comprising:

- a dielectric body having a passageway for receiving a contact, said passageway being defined by a bottom wall, a top wall and two side walls;
- a forward stop positioned at the mating end of said passageway to limit forward movement of a contact inserted therein;
- an abutment shoulder within said passageway positioned on said bottom wall at a distance to the rear of said forward stop generally equal to the length of the contact engagement section and at a distance from one side wall gener-



ally less than the width of the contact engagement section and greater than the width of the contact termination section, said abutment shoulder limiting rearward movement of the contact; and

flexible latching means deflected by the contact engagement section during insertion of the contact into said passageway, for engaging the contact without interference from the contact termination section, said latching means biasing the engagement section against said bottom wall within the space defined by said forward stop and said abutment shoulder, said latching means further co-operating with said abutment shoulder and said forward stop to retain the contact within said passageway.

4,295,699

PRESSURE SENSITIVE COMBINATION SWITCH AND CIRCUIT BREAKER CONSTRUCTION


Gideon A. DuRocher, Mt. Clemens, Mich., assignor to Essex International, Inc., Fort Wayne, Ind.

Continuation of Ser. No. 857,941, Sep. 15, 1969, abandoned. This application May 22, 1974, Ser. No. 472,582

Int. Cl.³ H01R 13/24

U.S. Cl. 339—61 M

19 Claims



1. In an electrical system comprising first and second electrical devices, each of said first and second electrical devices having a plurality of spaced apart contacts, at least one of said plurality of contacts comprising raised land portions, a one piece sheet connector having elastomericlike properties positioned between the devices and overlapping superimposed contacts of said first and second devices, means to compress the sheet connector between superimposed contacts of said first and second devices on opposite surfaces of said sheet connector, said sheet connector having a low resistance through the volume between superimposed contacts where compressed and a high resistance where not directly com-

4,295,700

INTERCONNECTORS

Ryoichi Sado, Saitama, Japan, assignor to Shin-Etsu Polymer Co., Ltd., Tokyo, Japan


Filed Oct. 9, 1979, Ser. No. 82,719

Claims priority, application Japan, Oct. 12, 1978, 53-140085

Int. Cl.³ H01R 9/09

U.S. Cl. 339—61 M

2 Claims



1. An interconnector comprising
 - (a) a rectangular connecting piece of a film or sheet made of an elastic material having anisotropic electro-conductivity in the direction parallel to one edge line thereof, and formed from alternating sandwiched stripes of conductive and nonconductive elastomer, and
 - (b) a couple of holder members made of an electrically insulating material holding said rectangular connecting piece of an elastic material having anisotropic electro-conductivity as sandwiched therebetween in such a manner that the two opposite peripheral portions of said rectangular connecting piece at the edge lines perpendicular to the direction of the anisotropic electroconductivity are each extended out of the surfaces of the holder members in the direction forming an angle between 10° and 80° with said surface of the holder member by a height at least equal to the thickness of said rectangular connecting piece.

4,295,701

ELECTRICAL CONNECTOR FOR SUBMARINE REPEATERS OR THE LIKE

Duncan A. Gunn, Saffron Walden, England, assignor to International Standard Electric Corporation, New York, N.Y.

Filed Sep. 4, 1979, Ser. No. 71,876

Claims priority, application United Kingdom, Sep. 7, 1978, 35914/78

Int. Cl.³ H01R 13/52

U.S. Cl. 339—94 A


4 Claims

1. A detachable electrical connector assembly including a pair of mateable connector sub-assemblies providing an electrical connection between separated high and low fluid pressure environments, the combination comprising:
 - a bulkhead separating said high and low pressure fluid environments and having an aperture therethrough;
 - a first connector assembly;
 - first means for mounting said first connector sub-assembly partially through said bulkhead aperture and adjacent the low pressure side of said bulkhead, said first means includ-

ing means providing a resilient compressive retaining force between a surface of the body of said first connector sub-assembly and the surface of said bulkhead low pressure side when said sub-assemblies are not mated;

second means including a first seal compressed between said first connector sub-assembly body surface and said bulkhead low pressure side in response to said retaining force, an inert gas present against said low pressure side of said bulkhead;

a second connector assembly mateable from the high pres-



sure side of said bulkhead into said first connector assembly, the dimensions of said bulkhead and said connectors being such that, upon mating of said connector assemblies said first connector overtravels against said resilient compressive retaining force to an extent permitting said inert gas to readily flow past said first seal into the volume surrounding the electrical connection between said connector assemblies, said first seal being restored by said resilient compressive force to retain said low pressure fluid when said second connector sub-assembly is withdrawn to break said electrical connection.

4,295,702

MULTI-OUTLET ADAPTER FOR PLUG-IN TELEPHONES


Dennis R. Snyder, Des Moines, Iowa, assignor to Bell Telephone Laboratories, Incorporated, Murray Hill, N.J.

Continuation of Ser. No. 912,467, Jun. 5, 1978, abandoned, which is a continuation of Ser. No. 714,525, Aug. 16, 1976, Pat. No. T958,009. This application Dec. 21, 1979, Ser. No. 105,900

Int. Cl.³ H01R 13/514

U.S. Cl. 339—97 P

7 Claims



1. A multi-outlet adapter for plug-in telephones comprising:
 - a male member including a plug portion having a plurality of troughs respectively communicating with a like plurality of slots in the plug portion;
 - a plurality of conductors totally contained within the adapter, each conductor being doubled over within an individual trough in the plug portion and both ends of each conductor being terminated with a wire spring jack contact;
 - a plurality of blade-like plug contacts respectively positioned within the slots in the plug portion, each plug contact making electrical connection with the conductor positioned in the associated trough whereby the jack

contacts terminating the ends of the conductor are connected in parallel to the associated plug contact;
a pair of contact carriers, each contact carrier having one of the jack contacts mounted therein; and
a female member joined to the male member, the female member having a pair of jack openings open to the outside of the adapter, the female member also having means for accommodating an individual carrier adjacent to each of the jack openings such that the jack contacts mounted in the carriers are exposed within the jack openings.

4,295,703

CONNECTOR BLOCK


Brian T. Osborne, Kanata, Canada, assignor to Northern Telecom Limited, Montreal, Canada

Filed Nov. 27, 1978, Ser. No. 963,935

Int. Cl.³ H01R 13/38

U.S. Cl. 339—98

12 Claims



1. An electrical connector block for interconnecting two pluralities of wires fanned along two opposite edges thereof comprising:

an elongate layered structure of three elements, a flat center element for supporting two staggered rows of flat, slotted, electrical connectors one on each surface thereof, and two insulating covers substantially coextensive, and compatible, with the center element, one on each side thereof and secured thereto, for positively retaining said connectors in place; said center element being an insulator having transversal slots in both of said opposite edges aligned with slots in said connectors for guiding and retaining wires to be inserted into the slots of said connectors for establishing electrical contact therewith.

4,295,704


SIDE PROBEABLE CONNECTOR USING FLAT CABLE
Ronald S. Narozny, Panorama City, and Robert P. Wyss, Manhattan Beach, both of Calif., assignors to Thomas & Betts Corporation, Raritan, N.J.

Filed Dec. 3, 1979, Ser. No. 99,521

Int. Cl.³ H01R 13/50

U.S. Cl. 339—99 R

18 Claims



1. A side probeable electrical connector for terminating a multiconductor electrical cable comprising: a body portion having a first and a second surface in parallel spaced apart relationship and first and second walls spaced apart from each other and generally orthogonal with said first and second

surfaces; said body portion defining at least two spaced bores from said first to said second surface; at least two electrical contacts, one such contact positioned in an associated bore and extending from said second surface to and beyond said first surface; a cover portion for locking engagement with said body portion and having a first surface and a second surface spaced apart from and generally parallel with said first surface of said cover portion for receipt respectively of a portion of said electrical contacts after same passes through an electrical cable placed between said first surfaces of said body portion and said cover portion; and at least one passage in said body portion having an axis transverse to the longitudinal axes of said bores and extending from one of said first and second walls to and communicating with said bores to permit said contacts to be probed by probe means inserted from outside of said body portion.

4,295,705

ONE PIECE CONNECTOR

Frank L. Ciliberti, Jr., Ossining, N.Y., assignor to Duracell International Inc., Bethel, Conn.


Division of Ser. No. 787,683, Apr. 14, 1977. This application

Mar. 26, 1979, Ser. No. 24,122

Int. Cl.³ H01R 13/415

U.S. Cl. 339—220 R

6 Claims



1. A connector assembly comprising a one piece connector attached to a support; said connector having a connecting means with an integral bottom wall; said connecting means comprising a generally cylindrical outer wall, the diameter of said outer wall adjacent said support being less than the diameter thereof at a point nearer its opposite end, said outer wall being adapted to be received within and to make good contact with the inner wall of a mating connecting means; said bottom wall having an integral boss with a closed end protruding from said bottom wall in a direction away from said connecting means; an inner wall joining the top edge of the outer wall to the bottom wall; said support having an aperture therein through which the boss extends; the bottom end of said boss being pressed flat against and in intimate contact with the surface of said support remote from said connecting means in the form of an outwardly extending shoulder having a diameter greater than the diameter of said aperture; whereby said support is secured between the shoulder of said boss and said bottom wall in sealing relationship and whereby said one piece connector is securely attached to said support.

4,295,706

COMBINED LENS CAP AND SUNSHADE FOR A CAMERA

George H. Frost, 544 Ivan Dr., Kent, Ohio 44240

Filed Jul. 30, 1979, Ser. No. 61,840


Int. Cl.³ G02B 11/04

U.S. Cl. 350—58

11 Claims

1. A compact and collapsible sunshade and lens cover for a camera having a tubular mount extending around and outwardly of the lens of the camera comprising ring means attachable to the tubular mount, sunshade means collapsible from a first position outward of the tubular mount to a second position

around the tubular mount to be compact therewith, lens cover means movable from a first position exposing the lens to a second position covering the lens as said sunshade means is being collapsed, means connecting said ring means to said



sunshade means to maintain said lens cover means in said first and second positions, and means connecting said ring means to said lens cover means to move said lens cover means from said first to said second position.

4,295,707

FEED THROUGH FOR OPTICAL SUBMERGED REPEATER

Taichiro Nakai, Fujisawa; Kahei Furusawa, Kamifukuoka, and Yoshihiro Ejiri, Tokyo, all of Japan, assignors to Kokusai Denjin Denwa Kabushiki Kaisha, Japan


Filed Oct. 3, 1979, Ser. No. 81,466

Claims priority, application Japan, Oct. 6, 1978, 53-122503

Int. Cl.³ G02B 5/14; H02G 3/00

U.S. Cl. 350—96.20

4 Claims



1. In a feedthrough for an optical submerged repeater, which is disposed on an end face plate of the pressure resisting casing of the repeater for introducing an optical fiber and a power supplying feeder of an optical fiber submarine cable into a repeater circuit disposed in the pressure resisting casing of the repeater of an optical fiber submarine cable repeating system, the improvement comprising:

a metal coating deposited on the clad part of at least one optical fiber to be introduced through the feedthrough;
a metal pipe into which said optical fiber deposited with said metal coating is introduced for reinforcement and hermetically fixed therein;

a disc sleeve connected to the power supplying feeder of the optical fiber submarine cable at the outside and inside of the end face plate to form a part of the power supplying feeder and having at least one insertion hole for inserting and air-tightly fixing therein said metal pipe;

a metal body air-tightly fixed to said end face plate for housing therein said disc sleeve; and

an insulator layer molded in a gap between said disc sleeve and said metal body and further molded together at at least the seawater side of said disc sleeve.

4,295,708


ELECTRO-MECHANICALLY ROTATABLE MIRROR
Robert D. Albrecht, Bethany; Michael Presley, Shawnee; William E. Waller, Ardmore; Gerald L. Cook, and William E. Presley, both of Stroud, all of Okla., assignors to Presley, Waller & Presley, Ardmore, Okla.

Filed Nov. 30, 1979, Ser. No. 98,754

Int. Cl.³ G02B 7/18

U.S. Cl. 350—289

10 Claims



1. An apparatus connectible to a vehicle for providing rearward vision to a driver of the vehicle at a plurality of selectable angles on either side of a neutral position, said apparatus comprising:

a support member connectible to said vehicle;
a rearview structure connected to said support member, said rearview structure including:

a housing;
a mirror;
means for rotatably connecting said mirror to said housing;

a motor having a drive shaft extending therefrom in acute angular relationship to said mirror;
means extending from said mirror for engaging said drive shaft in a fixed angular relationship;
means for maintaining said fixed angular relationship during periods of interaction between said motor drive shaft and said drive shaft engaging means;

means associated with said rearview structure operable by said driver for actuating said rotating means wherein said drive shaft includes a first segment secured to the rotor of said motor, a second segment having one end portion threadedly connected to said drive shaft engaging means in said fixed angular relationship, and said fixed angular relationship maintaining means includes a flexible sleeve element for pivotably coupling said first segment to said second segment, so that said second segment pivots with respect to said first segment to maintain said fixed angular relationship during said interaction.

4,295,709

PARABOLIC REFLECTOR COMPRISING A PLURALITY OF TRIANGULAR REFLECTING MEMBERS FORMING A REFLECTING SURFACE SUPPORTED BY A FRAMEWORK HAVING A PARTICULAR GEOMETRIC PATTERN

Douglas E. Wood, Box 32, Fox Island, Wash. 98333

Filed Aug. 29, 1979, Ser. No. 70,914


Int. Cl.³ G02B 5/10

U.S. Cl. 350—292

33 Claims

1. A parabolic reflector apparatus, comprising:
(a) a rigid support matrix of substantially parabolic configuration, comprising a plurality of strut-like members jointed together in a geometric pattern which is substantially identical to the pattern of lines on a parabolic surface created by

projecting an icosahedron or a subdivided portion thereof onto the parabolic surface;
(b) a plurality of reflecting members;



(c) means on said support matrix for supporting said reflecting members in such an arrangement that said reflecting members form a substantially parabolic reflecting surface.

4,295,710

DEFORMABLE MIRROR WITH DITHER


Theodore A. Heinz, Simi Valley, Calif., assignor to Rockwell International Corporation, El Segundo, Calif.

Filed Sep. 4, 1979, Ser. No. 71,898

Int. Cl.³ G02B 7/18, 5/08

U.S. Cl. 350—310

9 Claims



1. A deformable mirror for correcting wavefront aberrations in a laser fusion optical system, which comprises:
support means;
at least one ball screw mirror actuator interconnected with said support means;
a faceplate, which comprises:
a reflecting surface for reflecting a signal; and
a flex strut mounted at one end to said reflecting surface and at the other end to said ball screw mirror actuator;
and
a dither actuator connected in series with said ball screw mirror actuator for either tagging or for real time dynamic correction.

4,295,711

LIQUID CRYSTAL DISPLAY DEVICE

Hironari Tanaka, Shigeru Matsuyama, Tadashi Ishibashi, Kiyoshige Kinugawa, and Yukihiko Sato, all of Mobara, Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Filed Aug. 22, 1979, Ser. No. 68,576

Claims priority, application Japan, Aug. 23, 1978, 53-101776


Int. Cl.³ G02F 1/133

U.S. Cl. 350—334

4 Claims

1. A liquid crystal display device comprising:
a liquid crystal portion disposed between upper and lower substrates,
a plurality of electrode terminals provided on said upper substrate,
insulating binder material connected to said electrode terminals

and including electrically conductive islands penetrating through said insulating binder material, and
a plurality of lead electrodes provided on a sheet, wherein



said insulating binder material bonds said electrode terminals to said lead electrodes with said lead electrodes connected through said electrically conductive islands to said plurality of electrode terminals.

4,295,712

LIQUID CRYSTAL DISPLAY DEVICE

Masumi Ishiwatari, Zushi, Japan, assignor to Canon Kabushiki Kaisha, Tokyo, Japan


Filed Jul. 25, 1979, Ser. No. 60,281

Claims priority, application Japan, Aug. 19, 1978, 53-99994

Int. Cl.³ G02F 1/133

U.S. Cl. 350—344

3 Claims



1. A liquid crystal display device comprising:
a pair of flexible, transparent plates each having a transparent electrode on one surface; and
a spacer interposed between said plate surfaces for maintaining a constant space gap therebetween, said spacer being a honeycomb-shaped structure which extends over the entire display device surface.

4,295,713

FILM AND PHOTOGRAPHIC APPARATUS


Evan A. Edwards, Pittsford, N.Y., assignor to Eastman Kodak Company, Rochester, N.Y.

Division of Ser. No. 20,283, Mar. 14, 1979. This application Apr. 9, 1980, Ser. No. 138,481

Int. Cl.³ G03C 1/76

U.S. Cl. 352—235

2 Claims



1. In a photographic filmstrip having an image portion and a leader; the improvement comprising:
at least one row of perforations of a pre-determined size along the image portion; and
at least one row of perforations in the leader, said perforations in the leader being aligned with and smaller in a

direction longitudinally of said filmstrip than the perforations along the image portion.

4,295,714

ELECTROSTATIC CAMERAS

John M. Payne, Northborough, Peterborough, England
Continuation-in-part of Ser. No. 896,823, Apr. 17, 1978, Pat. No. 4,198,139. This application Feb. 19, 1980, Ser. No. 122,636


Claims priority, application United Kingdom, Apr. 16, 1977, 15873/77; Dec. 13, 1977, 51901/77

The portion of the term of this patent subsequent to Apr. 15, 1997, has been disclaimed.

Int. Cl.³ G03G 15/00; G03B 9/02

U.S. Cl. 354—3

4 Claims



1. A portable electrostatic camera comprising:
a light-tight housing having an aperture for admitting light;
a surface within the housing;
a shutter for controlling the passage of light through said aperture to said surface to form an optical image thereon;
a single point discharge electrode disposed within said housing between the aperture and the surface for electrically charging said surface prior to the formation of the optical image thereon, which surface modifies the charge to form an electrical image corresponding to the optical image;
a piezo-electric crystal generator disposed within said housing;
means for activating said piezo-electric generator to produce a high voltage charge for application to said single point discharge electrode;
means for ensuring that charge of only one polarity is applied to said single point discharge electrode;
means disposed within said housing for applying a printing medium to said surface for retention thereon in dependence on the level of electrical charge remaining at different points over said surface; and
an additional electrode situated within the camera housing and close to said surface on which the electrical image is formed to assist in the transfer of printing medium thereto.

4,295,715

CAMERA MECHANISM EMPLOYING A MULTIFUNCTION CONTROL MEMBER

John J. Breen, West Henrietta, N.Y., assignor to Eastman Kodak Company, Rochester, N.Y.

Filed Dec. 13, 1979, Ser. No. 103,259


Int. Cl.³ G03B 3/10

U.S. Cl. 354—25

4 Claims

1. A control mechanism for use in a photographic camera, comprising:
a multifunction control member moveable between an initial position and a final position;
means for moving said control member from said initial position to said final position;
position sensor means, responsive to the movement of said control member for producing a signal representing the position of said control member;
adjustable lens means moveable from an initial position to a final position for providing a plurality of focus adjustments, said lens means including control member follower

means for moving said adjustable lens means in concert with movement of said control member;
lens arresting means responsive to a focus control signal for arresting movement of said lens mean at one of said plurality of focus adjustments;
adjustable aperture means, moveable from an initial position to a final position for providing a plurality of aperture adjustments, said aperture means including control mem-



ber follower means for moving said aperture means in concert with movement of said control member;
aperture arresting means responsive to an aperture control signal for arresting movement of said aperture means at one of said plurality of aperture adjustments; and
control circuit means responsive to measured scene parameter inputs, including at least subject distance and brightness, and responsive to said position signal for producing said focus control signal and said aperture control signal.

4,295,716

MODE CHANGE-OVER DEVICE FOR AUTOMATIC EXPOSURE CONTROL CAMERA

Saburo Numata, Urawa, Japan, assignor to Fuji Photo Optical Co., Ltd., Omiya, Japan


Filed Apr. 25, 1979, Ser. No. 33,217

Claims priority, application Japan, Apr. 28, 1978, 53-51985

Int. Cl.³ G03B 7/14

U.S. Cl. 354—30

3 Claims



1. In a dual priority automatic exposure control camera in which mode is selected among aperture priority, shutter speed priority, program control and manual control comprising a shutter speed setting means, an aperture size setting means, a light measuring means, a film speed setting means, a shutter speed control means, an aperture control means, and an exposure control means having input means connected with said shutter speed setting means, aperture setting means, light measuring means and film speed setting means and output means connected with said shutter speed control means and aperture size control means for controlling the shutter speed and the

aperture size in accordance with information inputted thereinto, each of said shutter speed setting means and said aperture size setting means comprising a variable resistor having a brush slidable therealong,

a mode change-over device comprising a first signal generating means which gives a first signal indicating whether the shutter speed is automatically controlled or manually selected, a second signal generating means which gives a second signal indicating whether the aperture size is automatically controlled or manually selected, and a mode discriminating means having input means connected with said first and second signal generating means and output means connected with said exposure control means, said first signal generating means comprising a first pair of contacts located at an end of the variable resistor of said shutter speed setting means, at least one of the first pair of contacts being connected with said mode discriminating means, and a second pair of contacts located at an end of the variable resistor of said aperture size setting means, at least one of the second pair of contacts being connected with said mode discriminating means, wherein said brush is selectively put into contact with said variable resistor or said pair of contacts in each of said first and second signal generating means, wherein the mode of aperture priority, shutter speed priority, program control and manual control is represented by the combination of said first and second signal.

4,295,717

CAMERA WITH OPERATION INDICATOR FOR AUTO-STROBO UNIT


Masahiro Kitagawa, Hachioji, Japan, assignor to Olympus Optical Company, Ltd., Tokyo, Japan

Filed Apr. 25, 1979, Ser. No. 33,165

Claims priority, application Japan, May 31, 1978, 53-65128
Int. Cl.³ G03B 15/05, 17/18

U.S. Cl. 354-33

28 Claims



1. A camera with means to receive an auto-strobo unit, said auto-strobo unit including a first light emitting element for indicating the completion of a proper flashlight illumination and a second light emitting element for indicating the completion of a charging operation of said strobo unit; a viewfinder; and an operation indicator comprising a third light emitting element which is located within said viewfinder and which is responsive to a current flow through said first and second light emitting elements provided within said auto-strobo unit for providing an indication within said viewfinder that said charging operation and said flashlight illumination of the strobo unit have been properly completed.

4,295,718

EXPOSURE CONTROL CIRCUIT OF CAMERA


Kazunori Mizokami, Hachioji, Japan, assignor to Olympus Optical Company Ltd., Japan

Filed Jan. 7, 1980, Ser. No. 109,763

Claims priority, application Japan, Mar. 2, 1979, 54/24147
Int. Cl.³ G03B 7/081

U.S. Cl. 354-50

11 Claims



1. An exposure control circuit for a camera, comprising:
a photoelectric transducer element for determining the amount of light being received by a camera containing said transducer element from an object being photographed, and for generating a current proportional to the amount of said light;
an operational amplifier having its non-inverting input terminal connected to said transducer element and its output terminal coupled to its inverting input terminal for generating an output voltage representative of the integral of said current when an object is being photographed;
a first trigger switch comprising semiconductor switch means of the type which is capable of exhibiting a leakage current when the voltage across first and second terminals of said switch means is other than zero, said first terminal of said switch means being connected to said non-inverting input terminal of said operational amplifier and to said transducer element for applying a trigger signal to said transducer element which enables said transducer element to produce said current when an object is being photographed; and
potential equalizing means for maintaining said second terminal of said trigger switch at said output voltage of said operational amplifier at all times while said transducer element is generating said current, thereby to apply a zero voltage drop across said trigger switch and eliminate the flow of leakage current therethrough.

4,295,719

BATTERY CONSERVATION BY CONTROL OF THE CHARGING CIRCUIT FOR A BUILT-IN ELECTRONIC FLASH


Karl H. Lange, Bünde, Fed. Rep. of Germany, assignor to Balda-Werke, Bünde, Fed. Rep. of Germany

Filed Jan. 25, 1980, Ser. No. 115,191

Int. Cl.³ G03B 7/08, 15/05

U.S. Cl. 354-50

4 Claims



1. In a photographic camera system having a shutter and a flash unit for providing momentary artificial illumination of the photographic subject, the combination comprising means adaptable for connection of said camera system to a D.C.

power source, a shutter release member movable from a rest position through an intermediate position to a fully depressed position, a pivotally mounted holder member mounting an electromagnet and movable in response to said movement of said shutter release member from a rest position, through an intermediate position to a fully extended position respectively, an armature pivotally mounted on said holder member and operative to move into first and second positions into and out of contact with said electromagnet in response to the energization and deenergization of said electromagnet respectively, and latching means for latching and releasing said shutter in response to said movement of said armature into and out of contact with said electromagnet, whereby when said holder member is in said intermediate position and said armature is in said second position said shutter is released.

4,295,720

APPARATUS FOR DETERMINING LIGHT REFLECTION FROM A FOCAL PLANE SHUTTER


Kazunori Mizokami, and Masahiro Kitagawa, both of Hachioji, Japan, assignors to Olympus Optical Company Ltd., Japan

Filed Jan. 7, 1980, Ser. No. 109,762

Claims priority, application Japan, Mar. 9, 1979, 54/27848
Int. Cl.³ G03B 7/083

U.S. Cl. 354-51

10 Claims



1. An apparatus for determining light reflection from a focal plane shutter of the type that includes a first shutter blind which initiates exposure of a photographic film and which has a light-reflective surface facing a direction from which light is to be admitted for exposing a photographic film, and a second shutter blind which terminates said exposure; said apparatus comprising:

a photoelectric transducer element for determining the amount of light that is reflected from the surface of the shutter blind and also from the surface of a negative when a camera that includes said apparatus contains photographic film in a position which will cause said film to be exposed by the light; said photoelectric transducers element further being for generating a photocurrent which is representative of the amount of light being received;
an integrating capacitor for integrating said photocurrent for determining proper exposure time;
a correcting capacitor for compensating for the different reflectivities of the surface of the first shutter blind and the film surface;
switch means for connecting said correcting capacitor in parallel with said integrating capacitor a predetermined time after a shutter operation; and
means for charging said correcting capacitor in such a manner that the voltage thereacross is the same as the voltage across said integrating capacitor at the time said correcting capacitor is connected in parallel with said integrating capacitor.

4,295,721

HIGH PRESSURE AND HIGH SPEED OPTICAL ENCLOSURE SYSTEM


Dimitri Rebikoff, 3060 SE 4th Ave., Ft. Lauderdale, Fla. 33315

Filed Apr. 23, 1980, Ser. No. 143,140

Int. Cl.³ G03B 17/08

U.S. Cl. 354-64

3 Claims



1. A high pressure and high speed optical enclosure system for use with a film loaded camera comprising:
an external housing cylinder;
said external cylinder having a closed end and an open end; correcting lens system means for correcting the focus of the camera when said external cylinder is submerged;
pressure resistant means for sealingly covering said open end;
said correcting lens system means operably connected to said pressure resistant means;
an internal cylinder;
a primary lens, said primary lens connected to said internal cylinder;
connecting means for connecting said internal cylinder to said pressure resistant means;
mounting means for mounting the camera within said internal cylinder;
said connecting means includes a support which centers said internal cylinder and the primary lens of the camera mounted therein on its optical axis and holds said internal cylinder independently of said external cylinder and therefore maintains a constant distance between said primary lens and the film focal plane, and constant distance between said correcting lens system and said primary lens, connected to said pressure resistant means.

4,295,722

CAMERA FOR DAYLIGHT AND FLASH PHOTOGRAPHY

Uchiyama Takashi; Tokuichi Tsunekawa, both of Yokohama, and Takehiko Kiyohara, Kanagawa, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan

Division of Ser. No. 10,904, Feb. 9, 1979, Pat. No. 4,268,139, which is a continuation of Ser. No. 638,084, Dec. 5, 1975, abandoned. This application Dec. 17, 1979, Ser. No. 104,691

Claims priority, application Japan, Dec. 10, 1974, 49-141740
Int. Cl.³ B03B 15/03


U.S. Cl. 354-146

2 Claims

1. In a camera comprising a film gate, a focal plane shutter having leading and trailing shutter curtains and a control means for triggering movement of the trailing shutter curtain, a flash synchronizing device for enabling the flash illumination of a flash unit, comprising:

(a) motion transmitting means to be driven in association with the movement of the leading shutter curtain, said motion transmitting means being located at a first position when the film gate is covered by the leading shutter curtain, and being located at a second position when the film gate is fully opened by the running of the leading shutter curtain; and
(b) a single synchronous contact switch for enabling the

flash illumination of the flash unit when the single synchronous switch is set to an operative state, said single synchronous switch being located at a position where it is driven to an operative state in response to arrival at the second position of the motion transmitting means before



the control means triggers the movement of the trailing shutter curtain, and being fixedly mounted on a part of the control means in such a positional relation that it is located at a position beyond the second position of the motion transmitting means after the control means has triggered the movement of the trailing shutter curtain.

4,295,723

SINGLE LENS REFLEX CAMERA

Kikuo Momiyama, Yokohama, and Kenichi Kumazawa, Machida, both of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan


Filed Nov. 26, 1979, Ser. No. 97,833

Claims priority, application Japan, Nov. 24, 1978, 53-145114

Int. Cl.³ G03B 17/20, 19/12

U.S. Cl. 354—155

4 Claims



1. A single lens reflex camera comprising: an objective lens for forming an image of an object on a photosensitive surface and a focusing plate;
- a viewfinder optical system including a pentagonal roof prism having a front non-reflecting surface and an eyepiece for observing the object's image formed on the focusing plate;
- a first photographic data indicating means mounted on a lens barrel of said objective lens;
- a second photographic data indicating means located on the camera off said lens barrel;
- two information bearing light introducing windows on a front non-reflecting surface of said pentagonal roof prism, said two information bearing light introducing windows being arranged laterally of said front non-reflecting surface of the prism, one of said information bearing light introducing windows being offset from the middle section of said front non-reflecting surface and having a relatively small opening area, the other window being disposed across the middle section of the front non-reflecting surface and being of a laterally elongated shape having a relatively large opening area;
- first optical means facing said first data indicating means for

deflecting first information bearing light from said first data indicating means either to the left or right of said front non-reflecting surface of the pentagonal roof prism and for directing the first information bearing light to one of said two information bearing light introducing windows on said front non-reflecting surface;

second optical means for directing second information bearing light from said second data indicating body to the other information bearing light introducing window on said front non-reflecting surface; and

third optical means for directing said first and second information bearing light to said eyepiece.

4,295,724

ELECTRIC SELF-TIMER DEVICE FOR CAMERAS

Masayoshi Sahara, Sennan, and Masaaki Nakai, Nara, both of Japan, assignors to Minolta Camera Kabushiki Kaisha, Osaka, Japan


Continuation of Ser. No. 940,107, Sep. 6, 1978, abandoned. This application Jul. 9, 1979, Ser. No. 55,518

Claims priority, application Japan, Sep. 12, 1977, 52/123438

Int. Cl.³ G03B 17/18, 17/40

U.S. Cl. 354—238

6 Claims



1. An electronic self-timer device for a camera having a shutter comprising: a manually operable self-timer starter;
- a timer circuit including means for generating a first signal after a first predetermined time duration from the actuation of said self-timer starter and before commencement of an exposure;
- an oscillator responsive to the actuation of said self-timer starter for generating a first oscillating signal of a predetermined frequency, said oscillator being also responsive to said first signal for generating a second oscillating signal of a frequency distinguishably different from that of the first oscillating signal, a variable time constant R-C circuit, a circuit for generating an oscillating signal having a frequency dependent upon the value of the time constant of said R-C circuit, and a switching circuit responsive to said first signal from said timer circuit for changing the time constant of said R-C circuit from one value to another; and
- luminous indicating means responsive to the first and second oscillating signals to be lit intermittently in accordance with the respective frequencies of the first and second oscillating signals.

4,295,725

PHOTOGRAPHIC SHUTTER

Roger Durand, Ballaigues, Switzerland, assignor to Pignons S.A., Ballaigues, Switzerland

Filed Oct. 11, 1979, Ser. No. 83,614

Claims priority, application Switzerland, Oct. 19, 1978, 10808/78

Int. Cl.³ G03B 9/34

U.S. Cl. 354—244

4 Claims

1. A photographic shutter comprising two flexible curtains, each curtain attached by one of its edges to a first roller urged in a winding direction by a spring, each of said curtains connected by two flexible strips to a second roller which is con-

4,295,727

ELECTRICAL APPARATUS FOR COMPARING DARK AND LIGHT AREAS ON A SUBSTRATE AND WHICH SUBSTRATE IS IN A LIQUID


Douglas K. Robinson, 7512 Beverly, Edmonds, Wash. 98020

Filed Oct. 17, 1978, Ser. No. 952,202

Int. Cl.³ G03D 13/08

U.S. Cl. 354—298

15 Claims



1. An apparatus for comparing opaque area and clear area on a substrate with a predetermined standard of transparency to light, said apparatus comprising:

- a source of infra-red light and a solid state device with a spectral response peak in the infra-red region;
- said source of infra-red light and said solid state device being spaced apart so as to be capable of receiving an edge of said substrate between them;
- said substrate being immersed in a developing solution;
- said infra-red light continuously travels through the developing solution between the source of said infra-red light and the edge of the substrate, the edge of the substrate and the developing solution between the edge of the substrate and the solid state device;
- said predetermined standard of transparency being a dot structure in the substrate;
- an indicator, operatively, connecting with said solid state device; and,
- said indicator indicating when the dot structure in said substrate meets said predetermined standard of transparency.

4,295,726

BLADE TYPE FOCAL PLANE SHUTTER

Nobuyoshi Inoue, Kawagoe, Japan, assignor to Copal Company Limited, Tokyo, Japan


Filed Sep. 18, 1980, Ser. No. 188,286

Claims priority, application Japan, Sep. 20, 1979, 54-130844

Int. Cl.³ G03B 9/40, 9/08

U.S. Cl. 354—246

7 Claims



1. A focal plane shutter comprising a shutter plate having a rectangular exposure aperture formed therein, a plurality of auxiliary shutter blades rotatably supported on said shutter plate at one side of said exposure aperture to open and close said exposure aperture and having cam slots therein, an actuating member rotatably supported on said shutter plate at one side of said exposure aperture and having thereon a driving pin fitted in said cam slots, and a main shutter blade rotatably supported on two said auxiliary shutter blades adjacent to said main shutter blade with each other to open and close said exposure aperture in cooperation with said plurality of auxiliary shutter blades and capable of forming an exposure slit on said exposure aperture.

4,295,728

CONVEYING SYSTEM WITH SNAKE MOTION PREVENTION MEMBERS INCORPORATED THEREIN FOR PHOTO TREATMENT APPARATUS OF LONG LENGTH PHOTO-SENSITIVE SHEET MATERIALS

Kanichi Nishimoto, Wakayama, Japan, assignor to Noritsu Koki Co., Ltd., Wakayama, Japan


Filed Aug. 28, 1979, Ser. No. 70,539

Claims priority, application Japan, Sep. 5, 1978, 53-108104

Int. Cl.³ G03D 3/73

U.S. Cl. 354—321

7 Claims



1. In an improved automatic developing apparatus for long-

length photo-sensitive sheet materials of the type having a treatment bath containment means into which means are immersed and suspended for directing, locating and controlling the path of travel of a plurality of long-length photo-sensitive sheet materials attached to the trailing end of a wide leader, said means including a plurality of roller means to fix the path of travel of a wide leader, and guide means to position said leader along said directing means, the improvement which comprises:

- said directing means has a plurality of free roller means rotatably mounted on respective shafts;
- a plurality of guide means for guiding and curl prevention extending parallel to the path of travel and spaced in juxtaposition to said free roller means which confine the long-length photo-sensitive sheet materials to a narrow gap path of travel between said free roller means and said guide means;
- a plurality of motion prevention means for prevention of relative sideways motion of said sheet materials, each said means being rotatably mounted on respective said shafts and having a pair of arms extending horizontally forming a space between each pair of arms into which fit said free roller means and which horizontal arms extend toward said guide means to close up the sides of the narrow gap formed between said guide means and said free roller means so as to limit the amount of relative sideways motion in the long-length photo-sensitive sheet materials by further defining the desired travel path; and
- a plurality of counter balancing means respectively associated with the rotatably mounted plurality of said motion prevention means which normally locate the said pairs of arms thereof in the horizontal position and which provide forces to return said motion prevention means to the original position after the arms are displaced by contact with a wide leader so as to allow the wide leader to pass by.

4,295,729

AUTOMATIC ANTI-OXIDATION REPLENISHER CONTROL


Kenneth M. Kaufmann, Minneapolis, Minn., assignor to Pako Corporation, Minneapolis, Minn.

Filed Jul. 14, 1980, Ser. No. 168,020

Int. Cl.³ G03D 3/06

U.S. Cl. 354—324

8 Claims



- In a processor of photosensitive material in which anti-oxidation replenishment is provided to processor fluid to compensate for changes in chemical activity of the processor fluid due to aerial oxidation, the improvement comprising:
 - real time clock means for providing time of day signals;
 - storage means for storing an operating schedule of the processor; and
 - control means for controlling anti-oxidation replenishment as a function of the time of day signals and the operating schedule.

4,295,730 WASHER FOR RESIN-COATED PHOTOGRAPHIC PRINTS


David R. Fraser, Davis, Calif., assignor to The United States of America as represented by the Secretary of Health and Human Services, Washington, D.C.

Filed Jul. 31, 1980, Ser. No. 174,238

Int. Cl.³ G03D 3/04

U.S. Cl. 354—325

16 Claims



- A print-washing apparatus comprising a tank; a water inlet conduit mounted in the upper portion of said tank; a plurality of spaced parallel vertically arranged looped spray pipes located beneath the upper liquid level of said tank and communicatively connected to said water inlet conduit and defining vertical print-receiving spaces therebetween below the upper surface level of said tank; said looped spray pipes each having a plurality of water jet-forming apertures located along the entire length thereof; means to force water through said water inlet conduit and through said looped spray pipes and through said plurality of water jet-forming apertures so as to provide water jets on the surface of prints received in said vertical print-receiving spaces; means to soften the impact of said water jets to achieve a gentle washing action when in use, said means comprising a level of water in said tank when in use above the upper level of said looped spray pipes; a horizontally extending drain pipe array in the bottom portion of said tank and having a plurality of spaced inlet ports to receive waste water; and vertically arranged siphon discharge conduit means communicatively connected to said drain pipe array.

4,295,731

ELECTROSTATIC COPYING APPARATUS

Koichi Sasaki, Osaka; Yasuji Sumida, Nara, and Hiroshi Ishida, Ibaragi, all of Japan, assignors to Mita Industrial Company Limited, Osaka, Japan

Filed Apr. 11, 1979, Ser. No. 29,053

Claims priority, application Japan, Apr. 17, 1978, 53-45490; Apr. 17, 1978, 53-50972[U]; Apr. 17, 1978, 53-50973[U]; Apr. 19, 1978, 53-47309; May 23, 1978, 53-61822; May 23, 1978, 53-70043[U]; May 23, 1978, 53-70044[U]; May 23, 1978, 53-70045[U]; May 23, 1978, 53-70046[U]; May 23, 1978, 53-70047[U]; May 30, 1978, 53-65949; May 30, 1978, 53-74580[U]; May 30, 1978, 53-74581[U]; May 30, 1978, 53-74582[U]; May 31, 1978, 53-66119[U]


Int. Cl.³ G03G 15/00

U.S. Cl. 355—14 R

6 Claims

- An electrostatic copying apparatus comprising:
 - an original document carrier;
 - an optical device including an exposure lamp;
 - an endless loop member mounted for movement about first and second wheels and connected to a part of one of said original document carrier or said optical device;
 - a moving member fixed to said part for movement thereby in an exposure moving direction;
 - a roll supply of copying paper from which copying paper is movable along a path sequentially through a paper cutting zone including a paper cutting unit, a charging zone including a charging device, an exposure zone including an

exposure device, a developing zone including a developing device, and a fixing zone including a fixing device; paper feed means for feeding copying paper from said supply to said paper cutting zone whereat said paper cutting unit severs said copying paper into predetermined lengths; pivotally mounted paper feed detecting, exposure detecting, paper cut detecting and de-energization detecting members sequentially disposed along the path of said moving member in said exposure moving direction and spring biased to locations to be sequentially contacted by said moving member and moved thereby to respective actuated positions; copying paper feed linkage means, associated with said paper feed detecting member and with said paper feed means, for, upon said moving member moving said paper feed detecting member to said actuated position thereof, actuating said paper feed means to initiate feeding of said copying paper; exposure linkage means, associated with said exposure detecting and de-energization detecting members and with



- said exposure lamp, for, upon said moving member moving said exposure detecting member to said actuated position thereof, actuating said exposure lamp, and for, upon said moving member moving said de-energization detecting member to said actuated position thereof, de-energizing said exposure lamp;
- paper cut linkage means, associated with said paper cut detecting means and paper cutting unit, for upon said moving member moving said paper cut detecting member to said actuated position thereof, actuating said paper cutting unit to sever copying paper being fed by said paper feed means;
- position detecting means for adjusting and setting the positions of said paper cut detecting member and of said de-energization detecting member along said path of said moving member; and
- the distance between said paper cut detecting member and said de-energization detecting member being at least as great as the distance between the cutting position of said paper cutting unit and the upstream end of said exposure zone in the direction of feeding of said copying paper.

4,295,732

BOUND DOCUMENT APPARATUS LATCHING MECHANISM

Charles J. Hull, Fairport; James E. Hutton, Webster, and Teri J. Mahuson, Rochester, all of N.Y., assignors to Xerox Corporation, Stamford, Conn.

Filed Oct. 30, 1979, Ser. No. 89,341



Int. Cl.³ G03G 15/00

U.S. Cl. 355—14 R

9 Claims

- In an electrostatic reproduction machine having a support frame, document handling apparatus for advancing document sheets from a stack to an exposure platen, and an electrostatic processor for processing copy sheets of the document sheets when exposed, the improvement comprising:
 - a housing for containing the document handling apparatus;
 - pivotal support means on the machine frame and connected to said housing for permitting the pivotal movement of the

document handling apparatus toward and away from the exposure platen, a bound document cover assembly detachably retained by said housing, said cover assembly being connected to said pivotal support means and movable as a unit with said housing to expose the exposure platen for manual use, said housing being pivotally related to said cover assembly



- whereby the latter may be maintained on said platen while said housing is in a pivoted raised position, so as to permit bound document copying,
- a latching arrangement including a first latch mechanism associated with said housing for attaching the same to said cover assembly and a second latch mechanism associated with said cover assembly for attaching the same to the support frame of the machine.

4,295,733

AUTOMATIC ERROR COLLATOR CAPACITY CONSTRAINTS USING SPARE BIN STRATEGY

Donovan M. Janssen, and William S. Seaward, both of Boulder, Colo., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Dec. 10, 1979, Ser. No. 101,678

Int. Cl.³ B65H 31/24; G03G 15/00


U.S. Cl. 355—14 SH

12 Claims

- In a copying-system having a cycling automatic document feed and an automatic unloading apparatus, a device to recover from an overflow collator condition comprising in combination:
 - a sorter means for containing a plurality of copy sheets of an original document, said sorter means having an advertised set of bins and a number of spare bins for containing overflow copies from the advertised bins;
 - a loading means associated with the sorter means and operable to load an optimum number of copies into the advertised bins and overflow copies into the spare bins; and
 - an unloading means including an automatic unloading apparatus for forming a complete collated set of copies by merging copies from the advertised bins and the spare bins.
- A method for controlling the operation of a sheet collator when the capacity M of each primary bin is less than the

number of sheets N to be collated in one set, said method comprising of the following steps:

- (1) providing a set of auxiliary bins for containing overflow copy sheets;
- (2) loading each primary bin to its capacity with M copy sheets;
- (3) loading the auxiliary bins with the (N-M) copy sheets;



- (4) forming collated copy sets by combining sheets from the primary and secondary bins;
- (5) increasing the initial set of auxiliary bins by adding newly emptied primary bins; and
- (6) loading the newly emptied primary bins with (N-M) copy sheets.

4,295,734

FILTER ASSEMBLY FOR COLLECTING USED TONER OF ELECTROPHOTOGRAPHIC COPYING MACHINE
Hiroshi Tsuda, Mitaka; Kiyoshi Miyashita, Hachioji; Masaji Nishikawa, Hachioji; Akira Shimizu, Hachioji, and Munee Kasuga, Hachioji, all of Japan, assignors to Olympus Optical Company Ltd., Japan


Filed Dec. 17, 1979, Ser. No. 104,444

Claims priority, application Japan, Feb. 1, 1979, 54/10912

Int. Cl.³ G03G 15/00

U.S. Cl. 355—15

11 Claims



1. In an electrophotographic copying machine including a brush which rotates while maintaining its contact with a member which carries an electrostatic latent image to remove any residue of unnecessary toner which remains attached to said member, a suction fan for producing an airstream which conveys the toner removed by said brush, and a filter assembly disposed in the path of the airstream for collecting used toner; the improvement comprising:

- (a) a one piece filter cassette having a toner receiver compartment and a separate filter holder compartment formed therein, said filter holder compartment receiving a replaceable filter element therein, said toner receiver compartment being located upstream of said filter holder compartment in a position which permits toner which strikes said filter element and falls down in front of said filter element to form a pile therein; and
- (b) means for positioning said filter cassette in the path of the

airstream formed within the copying machine, said filter cassette and positioning means cooperating in such a manner that said filter cassette can be slidably placed in and slidably removed from said positioning means, said positioning means including a labyrinth arrangement for forming a labyrinth seal between said filter cassette and said positioning means when said filter cassette is mounted in said positioning means such that said airstream passes through said cassette but does not pass between said cassette and said positioning means.

4,295,735

OPTICAL PROJECTION SYSTEM HAVING A PHOTOREPETITION FUNCTION
Michel Lacombat, and Andre Gerard, both of Paris, France, assignors to Thomson-CSF, Paris, France


Filed Feb. 26, 1980, Ser. No. 124,743

Claims priority, application France, Feb. 27, 1979, 79 05008

Int. Cl.³ G03B 27/52, 27/70

U.S. Cl. 355—43

9 Claims



1. An optical system for projecting patterns in order to reproduce the image of at least one modulating object on a semiconductor wafer coated with photo-sensitive material or on a mask, said optical system being provided with a projection objective and with at least one source of light energy for the illumination of the modulating object, wherein said projection system comprises at least one first reticle and a second reticle each adapted to carry a modulating object, and reflecting optical means comprising at least one movable plane mirror adapted to permit the formation of at least one first optical path and a second optical path in order that the image of said modulating objects carried by said first and second reticles may be projected alternately on said semiconductor wafer or on said mask by switching said movable mirror.

4,295,736

OPTICAL ASSEMBLY FOR USE IN COPYING MACHINE
Hiroshi Ikeda, Aichi, Japan, assignor to Minolta Camera Kabushiki Kaisha, Osaka, Japan

Filed Nov. 14, 1979, Ser. No. 94,313

Claims priority, application Japan, Nov. 14, 1978, 53-157174


Int. Cl.³ G03B 27/34, 27/40, 27/70

U.S. Cl. 355—57

10 Claims

1. An optical assembly for use in a copying machine of a type including an enlarged size reproduction mode and a reduced size reproduction mode each having the same conjugate distance, said assembly comprising: a projecting lens assembly, a reflective mirror assembly, a drive mechanism connected to said projecting lens assembly for driving said lens assembly between first and second lens assembly positions corresponding to the positions of said lens assembly for the respective reproduction modes, a mechanism connected to said mirror assembly for driving said mirror assembly to a single predetermined

mined mirror assembly position which is the position of said mirror assembly for both reproduction modes, means for adjusting the mirror assembly position of said mirror assembly for proper focal adjustment for the condition in which said projecting lens assembly is at the first lens assembly position



corresponding to the one reproduction mode, and means for adjusting the second lens assembly position of said projecting lens assembly for proper focal adjustment for the condition in which said projecting lens assembly is at the second lens assembly position for the other reproduction mode and said mirror assembly is in the adjusted mirror assembly position.

4,295,737


GROOVED BELT DOCUMENT REGISTRATION SYSTEM
Morton Silverberg, Rochester, N.Y., assignor to Xerox Corporation, Stamford, Conn.

Filed Jan. 10, 1980, Ser. No. 111,062

Int. Cl.³ G03B 27/62, 27/64

U.S. Cl. 355—76

8 Claims



1. In an original document handling apparatus for moving successive individual document sheets on the surface of a movable belt into a registered position for copying at a copier imaging station, including registration means cooperatively engaging said belt and movable into and out of the path of said documents for their registration, the improvement wherein:

- said movable belt has a plurality of narrow elongated permanent grooves therein,
- said grooves extend in the direction of movement of said belt below said surface thereof,
- said grooves are transversely spaced on said belt,
- said grooves have gently sloped walls to avoid reproducible shadows thereof at said copier imaging station, and
- said registration means comprises at least two registration fingers transversely spaced corresponding to at least two of said grooves and narrower than said grooves and adapted to interfit into said grooves for the registration of said documents against said registration fingers without slippage between said documents and said fingers.

4,295,738


FIBER OPTIC STRAIN SENSOR

Gerald Meltz, Avon, and Elias Snitzer, West Hartford, both of Conn., assignors to United Technologies Corporation, Hartford, Conn.

Continuation-in-part of Ser. No. 71,512, Aug. 30, 1979, abandoned. This application Jun. 23, 1980, Ser. No. 162,283
Int. Cl.³ G01B 11/16

U.S. Cl. 356—32

11 Claims



1. A strain monitor, comprising: strain responsive means including an optical fiber positionable where strain is to be measured, said optical fiber having a plurality of cores which are spaced apart from each other in a cladding, said cladding and each of said plurality of cores being sized and fabricated from such materials as to support only the lowest order propagation mode, thereby allowing cross-talk to occur between said cores; source means for generating light to be coupled into one of said cores, said light being cross-talked to adjacent cores in a manner related to strain acting on said optical fiber; detector means for receiving light energy emerging from each of said plurality of cores, and for providing an electrical signal related to the intensity of said emerging light; and whereby a strain acting on said optical fiber causes a change in the dimensions and refractive indices of said plurality of cores and said cladding such that mode interference between the modes of propagating light energy within said plurality of cores produces a change in the intensity of light emerging from said cores which is uniquely related to such strain acting on said optical fiber.

4,295,739

FIBER OPTIC TEMPERATURE SENSOR

Gerald Meltz, Avon, and Elias Snitzer, West Hartford, both of Conn., assignors to United Technologies Corporation, Hartford, Conn.


Continuation-in-part of Ser. No. 71,512, Aug. 30, 1979, abandoned. This application Jun. 23, 1980, Ser. No. 162,284
Int. Cl.³ G01J 5/38

U.S. Cl. 356—43

11 Claims

1. A temperature monitor, comprising: temperature responsive means including an optical fiber having a plurality of cores in a cladding, said plurality of cores being positioned in an array and extending continuously along the entire length of said optical fiber to allow cross-talk therebetween, said cladding and each of said plurality of cores being sized and formed from such materials as to support only the lowest order mode; source means for generating light to be coupled into one of said plurality of cores, said light being cross-talked to adjacent cores in a manner related to the temperature along the length of said optical fiber; detector means for receiving light energy emerging from

each of said plurality of cores and for providing an electrical signal indicating the intensity of said emerging light; and
whereby a temperature change along the length of said optical fiber causes a change in dimensions and refractive



indices of said optical fiber such that the beat phase of light propagating along said plurality of cores varies as a function of temperature causing a change in intensity of light emerging from said plurality of cores of said optical fiber which is uniquely related to the temperature along said optical fiber.

4,295,740

PHOTOELECTRIC DOCKING DEVICE


Robert H. Sturges, Jr., Plum Borough, Pa., assignor to Westinghouse Electric Corp., Pittsburgh, Pa.

Filed Sep. 5, 1978, Ser. No. 939,555

Int. Cl.³ G01B 11/26; B64G 1/62

U.S. Cl. 356-152

13 Claims



1. A photoelectric docking device for remotely positioning in three dimensional space a first member relative to a second member comprising:

a point light source fixedly connected to the first member and directed to focus a narrow beam of light along a pre-established path;

a photosensor fixedly connected to the second member, which is responsive to the reception of light from the point light source on the first member to provide electrical outputs representative of the relative position of the point source with respect to the photosensor in three dimensional space, the photosensor having at least three electrical outputs taken from substantially symmetric locations over the photosensitive area of the cell;

means for processing the photosensor outputs into a second set of electrical outputs representative of the cartesian coordinates of the first member with respect to the second;

means for displaying the electrical outputs as a pictorial representation of the relative position of the first and second members in three dimensional space;

means for detecting physical contact between the first and

second members and providing an electrical signal representative thereof; and
means responsive to the signal to provide a remote indication of such contact.

4,295,741

TWO-WAVELENGTH PHASE CONTROL SYSTEM


Gary E. Palma, Rocky Hill, and Francois M. Mottier, South Windsor, both of Conn., assignors to United Technologies Corporation, Hartford, Conn.

Filed Aug. 30, 1979, Ser. No. 71,509

Int. Cl.³ G01B 9/02

U.S. Cl. 356-349

12 Claims



1. An adaptive optics control system for mitigating $2\pi N$ ambiguity in error signals for the control of the phase distribution of an output beam from a multi-line laser comprising:

an interferometer having a reference leg, a phase leg, means for directing a first portion of an input beam having a multi-line spectrum from a laser to the phase leg for providing phase beams and for directing a second portion of the input beam to the reference leg for providing a reference beam and means for combining the reference beam and phase beams for providing signal beams;

means disposed within the reference leg for separating from the second portion of the input beam at least a first beam at a first wavelength and a second beam at a second wavelength and for directing said first beam to a first frequency shifter and said second beam to a second frequency shifter;

a first frequency shifter disposed within the reference leg for providing a first frequency shift of the first beam; a second frequency shifter disposed within the reference leg for providing a second frequency shift of the second beam; means for combining the first beam and the second beam into a reference beam having two frequency shifted wavelengths and for directing said reference beam to the means for combining the reference and phase beams;

means disposed within the phase leg for separating the first portion of the input beam into at least two amplifier beams and for directing said amplifier beams to at least two optical amplifiers;

at least two optical amplifiers disposed within the phase leg for amplifying each of said amplifier beams to provide at least two output beams having high power;

coupler means for passing a first portion of each of the output beams out of the interferometer as target beams and for directing a second portion of the output beams through the phase leg as phase beams to the means for combining the reference beam and the phase beams;

at least two detectors in optical alignment with the signal beams wherein each detector is in register with the output beam of one of the optical amplifiers for providing electrical output signals and wherein one detector is a standard detector;

a phase control system responsive to the electrical output signals for providing fine error signals and coarse error signals to actuator means; and

actuator means responsive to the fine and coarse error sig-

nals attached to the means for directing said amplifier beams to the optical amplifiers for adjusting the optical path difference between each of the output beams for providing phase-matching of the phase distribution of each of the output beams for providing target beams having high optical quality.

4,295,742

LONGITUDINAL MEASURING DEVICE

Gunther Nelle, Bergen, and Gunter Swassek, Traunreut, both of Fed. Rep. of Germany, assignors to Dr. Johannes Heidenhain GmbH, Traunreut, Fed. Rep. of Germany


Filed Mar. 2, 1979, Ser. No. 17,057

Claims priority, application Fed. Rep. of Germany, Mar. 10, 1978, 2810341

Int. Cl.³ G01B 11/14

U.S. Cl. 356-373

6 Claims



1. An apparatus for positioning a scanning unit in a longitudinal measuring device, said measuring device including a measuring scale, a driving unit for connecting the device to an object whose position is to be measured, and first and second mutually perpendicular guide surfaces for guiding the scanning unit along the scale, said apparatus comprising:

a support structure positioned alongside the scale;

means for connecting the scanning unit to the driving unit in a flexible manner, said connecting means including a coupling element connected between the scanning unit and the driving unit and operative to maintain a substantially constant spacing therebetween;

first spring means positioned to exert a spring force between the scanning unit and the support structure, for biasing the scanning unit into contact with the first guide surface formed by the scale and substantially in no other direction; and

second spring means positioned to exert a spring force between the scanning unit and the support structure, for biasing and scanning unit into contact with the second guide surface formed by the support structure and substantially in no other direction, said two spring means operating substantially independently of each other.

4,295,743

APPARATUS FOR DETERMINING FAULTS IN STRIP MATERIAL

Erwin Sick, Icking, Fed. Rep. of Germany, assignor to Erwin Sick GmbH, Optik-Elektronik, Fed. Rep. of Germany

Filed Jun. 18, 1979, Ser. No. 49,534

Claims priority, application Fed. Rep. of Germany, Jun. 23, 1978, 2827705

Int. Cl.³ G01B 11/30


U.S. Cl. 356-431

18 Claims

2. Apparatus for determining faults in a strip of material comprising means for generating a scanning light bead on the strip, a first cylindrical lens extending over the scanning region with its focal line extending optically parallel to the direction of movement of the scanning light bead on the strip, first and second strip-like cylindrical mirrors arranged behind the focal line and optically spaced apart from one another by the distance of their focal lengths and with their focal lines optically at right angles to the direction of movement of the scanning

light bead on the strip, a second cylindrical lens cooperating with the first and second cylindrical mirrors, and a light receiving device illuminated from the second cylindrical lens and having at least one light conducting rod for receiving light from the second cylindrical lens along a surface region and for transmitting this light to at least one photoelectric converter arranged at an end face of the light conducting rod the arrangement being such that:

(a) the first cylindrical lens images the scanning light bead on the first cylindrical mirror;



(b) the first cylindrical mirror reflects the incident light to the second cylindrical lens which is arranged parallel to the first cylindrical lens and spaced from the first cylindrical mirror by its focal length;

(c) a plane mirror is arranged behind the cylindrical lens at least along a part of its length and reflects the incident light through the second cylindrical lens to the second cylindrical mirror; and

(d) the second cylindrical lens is passed through twice on account of the arrangement of the plane mirror and images the surface of the first cylindrical mirror on the surface of the second cylindrical mirror.

4,295,744

SLURRY GUN


William F. Scriminger, Muskogee, Okla., assignor to Muskogee Environmental Conservation Co., Muskogee, Okla.

Filed Apr. 23, 1979, Ser. No. 32,165

Int. Cl.³ B28C 5/06

U.S. Cl. 366-3

3 Claims



1. A method for mixing a slurry of fly ash and a wetting agent comprising the steps of:

(a) introducing the wetting agent horizontally into an intro-

- duction chamber under pressure and at a controlled volume;
- (b) introducing aerated fly ash downwardly into said chamber under a pressure less than that of the wetting agent and at a controlled volume of air and a controlled amount of fly ash carried by the air; and
- (c) creating turbulence downstream of the introduction chamber by passing the wetting agent and aerated fly ash through a contorted path for thoroughly mixing the fly ash and wetting agent.


4,295,745

APPARATUS FOR CONDITIONING BIOINJURIOUS WASTE

Herbert Brunner, Hanau, Fed. Rep. of Germany, assignor to Nuken GmbH, Hanau, Fed. Rep. of Germany
 Filed Mar. 10, 1980, Ser. No. 128,815
 Claims priority, application Fed. Rep. of Germany, Mar. 20, 1979, 2910878

Int. Cl.³ B01F 7/32

U.S. Cl. 366—302



1. In apparatus for conditioning bioinjuriously pumpable waste, especially radioactive waste, by forced mixing with a settable binder in a final storage container having stirrer means installed therein, the improvement comprising:
- said stirrer means being constructed of a rotatable portion and a portion fixed to the container,
- said rotatable portion comprising closed frame means providing at least two opposite stirrer arm means secured to a hollow central shaft having at least two axially spaced parts,
- said fixed portion comprising a rod-like part extending upright from the central portion of the bottom of the container with said hollow shaft being journaled thereon, said rod-like part being provided with at least one mixing element secured thereto at a location thereon between said shaft parts.

4,295,746

ARRANGEMENT FOR FEEDING ELECTRODES IN METAL PAPER PRINTERS

Kurt Hartmann, Calw-Heumaden, Fed. Rep. of Germany, assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Apr. 25, 1980, Ser. No. 143,691

Claims priority, application Fed. Rep. of Germany, Sep. 4, 1979, 2935595


Int. Cl.³ B41J 3/02

U.S. Cl. 400—119

4 Claims

4. Apparatus for allowing the withdrawal of one of a pair of contacting electrodes with respect to the other comprising:
- at least one first and one second elongate electrode;
- a flexible tube surrounding said electrodes for holding said

electrodes in contacting juxtaposition, said tube being of an electrically insulative material; and



guide means having at least one groove therein adapted to receive a said tube, said groove being a depth less than the diameter of a said tube.

4,295,747

INTEGRALLY MOLDED, LOOSELEAF BOOKS WITH RING-BINDER-MOUNTING POSTS MOLDED ON SPINE


Dominic R. Errichiello, 389 Meadowlark Rd., Bloomingdale, Ill. 60108

Filed Aug. 6, 1979, Ser. No. 63,864

Int. Cl.³ B42F 13/12; B42D 3/00

U.S. Cl. 402—75

5 Claims



1. An integrally molded looseleaf book constructed of a thermoplastic polymer material having a snap-ring assembly mounted therein, said looseleaf book comprising:
- a spine having front and rear cover panels hingedly mounted on respective opposite, longitudinal edges thereof by means of living hinges;
- two or more posts formed in the inner front face of said spine;
- means for mounting the matrix strip of said snap-ring on said posts; and
- a longitudinal cavity formed in the inner front face of said spine and extending substantially the full length of said spine, said posts being integrally molded in the bottom wall of said spine cavity, and said matrix strip being positioned longitudinally in said cavity.

4,295,748

MOUNTING STRUCTURE FOR MAGNETRONS

Ichiro Ohara, Mobara, Japan, assignor to Hitachi, Ltd., Tokyo, Japan

Filed Jan. 18, 1979, Ser. No. 4,292

Claims priority, application Japan, Jun. 9, 1978, 53-77920[U]


Int. Cl.³ F16B 17/00

U.S. Cl. 403—24

1 Claim

1. A mounting structure for magnetrons comprising a flange having bolting bore-holes therein secured to a wave guide to provide a surface side to be mounted with the magnetron, a mounting plate secured to said magnetron, and a plurality of stud bolts each having a head, a mounting portion adjacent said head, threads and a tip portion without threads having a diameter which is equal, at the most, to the diameter of bottom of thread of said stud bolt, fastening means operative on said mounting portion of said stud bolts with said tip aligned with

said bore-holes for permanently fixing said stud bolts integral with said mounting plate and clamping means aligned by said



tips for engaging said threads on said stud bolts passed through said bore-holes and tightened by rotating said clamping means on said tips as an axis on the other side of said flange.

4,295,750

SHAFT-COMPONENT CONNECTION MEANS


Erwin F. Geppert, Oakland, Mich., assignor to The United States of America as represented by the Secretary of the Army, Washington, D.C.

Filed May 23, 1980, Ser. No. 152,920

Int. Cl.³ B25G 3/00

U.S. Cl. 403—259

5 Claims



1. In an assembly comprising a circular shaft, a mechanical component having two external planar faces and a circular bore extending therebetween, said shaft extending through the bore as a non-wobble fit therein: the improvement wherein at least one of the aforementioned external planar faces is acutely angled to the bore axis; first abutment means carried by the shaft in facial engagement with the acutely angled planar face on the mechanical component; and second abutment means carried by the shaft in facial engagement with the other planar face on the mechanical component; the angle taken by the acutely angled planar face being sufficient to prevent relative rotation between the shaft and the mechanical component; said first abutment means being a snap ring seated in a peripheral groove in the shaft so that a side surface of the ring engages the acutely angled planar face on the mechanical component.

4,295,749

EYE SPLICE FITTING


Jack L. McBride, 3622 Barbara St., San Pedro, Calif. 90731

Filed Aug. 15, 1979, Ser. No. 66,621

Int. Cl.³ F16G 11/04

U.S. Cl. 403—211

3 Claims



1. A fitting for anchoring therein a section of a rope-like strand comprising a housing having a hole extending through, said hole having a frustoconical interior shape with a small end thereof greater in diameter than the diameter of said rope-like strand, a pair of longitudinally separated wedge sections which when placed together comprise a composite plug having a frustoconical exterior complementary to the frustoconical interior of the hole in the housing, each said wedge section having a semi-cylindrical recess presenting an arcuate surface extending from end to end with a curvature substantially matching the curvature on the surface of the strand, said wedge sections being adapted to fit around opposite sides of the strand and jamb into the hole whereby to anchor the strand in the housing, the combined depths of the semi-cylindrical recesses being less than the diameter of the rope-like strand, said housing having a second hole substantially parallel to the first hole, said second hole having a smooth interior of diameter greater than the diameter of said rope-like strand.

4,295,751

THREAD STRUCTURE FOR PERCUSSION DRILL ELEMENTS

John M. Holmberg, Selcourt Springs, South Africa, assignor to Boart International Limited, Johannesburg, South Africa


Filed Sep. 21, 1979, Ser. No. 77,549

Claims priority, application South Africa, Sep. 21, 1978, 78/5370

Int. Cl.³ F16B 7/00

U.S. Cl. 403—306

20 Claims



1. A coupling thread structure for percussion drill elements including a rod having an external thread and a sleeve having an internal thread with the threads, when the rod and sleeve are coupled together, presenting abutting and non-abutting flanks and with the flanks being joined by crest and bottom portions, wherein the thread has at least two starts; the abutting flanks are straight along their whole abutting contact portions; the abutting flank portions form an angle of between 10° and 25° with the drill axis; and the pitch angle of the threads is between 9° and 20°.

4,295,752

RETAINING ASSEMBLY


John A. Lerch, Signal Mountain, Tenn., assignor to Vulcan Iron Works Inc., Chattanooga, Tenn.

Filed Jan. 29, 1979, Ser. No. 7,316

Int. Cl.³ B25G 3/00; F16D 1/00; F16G 11/00

U.S. Cl. 403—317

12 Claims



1. A retaining assembly for retaining a key in a housing of a ram or the like wherein said housing includes a slot in which said key is to be retained, said assembly comprising,
 - a mechanical connecting member secured to said key, said connecting member including an aperture,
 - a force application member including a first end extending through said aperture and a second end abutting said housing, and
 - a force generating element mounted on said force application member between said housing and said mechanical connecting member, said force generating member adapted to generate a force against said mechanical coupling member and said housing whereby said key is retained in said slot.

4,295,753

TORQUE TRANSMITTING APPARATUS


Adolf Luerken, Palos Verdes, and William D. Vogel, Arcadia, both of Calif., assignors to McCulloch Corporation, Los Angeles, Calif.

Filed Nov. 10, 1977, Ser. No. 850,137

Int. Cl.³ F16D 1/08

U.S. Cl. 403—365

12 Claims



1. Apparatus for mounting a rotatable component on a tapered rotating drive shaft comprising
 - an intermediate torque transmitting hub member having
 - a tapered internal bore extending in a longitudinal direction from a shaft receiving aperture at a first surface of said member to a narrowed exit aperture at a second surface of said member,
 - a recessed shoulder extending around a peripheral surface of the member, for seating said rotatable component,

said shoulder being substantially concentric with the longitudinal axis of said bore, a shoulder cutout around an inner periphery of said shoulder, a plurality of narrow, longitudinally extending rib members spaced apart on and supported by an outside peripheral surface of said member, whereby said tapered drive shaft passes through said intermediate member, the internal taper of the intermediate member matches the taper of the drive shaft, said rotatable component, when it is seated, contacts said shoulder only at an outside annulus of said shoulder, and the rotatable component, when seated against said recessed shoulder for the first time, mechanically distorts the original shape of said rib members, and drive torque is transferred from said drive shaft to said intermediate member through the interior surface of the member tapered bore, and from the member shoulder, through friction contact, to the rotatable component.

4,295,754

DISPLAY STRUCTURES AND THE LIKE

Christopher J. Ashton, Kimpton; Andrew C. Diamond, Wellwyn Garden City, and Derek H. Greenhill, Bromsgrove, all of England, assignors to Marler Haley Exposystems Limited, England


Filed Mar. 29, 1979, Ser. No. 24,943

Claims priority, application United Kingdom, Apr. 7, 1978, 13831/78

Int. Cl.³ F16B 2/14

U.S. Cl. 403—369

5 Claims



1. A plug and socket connection including a first member defining a socket and a second member defining a plug which is received in said socket, a diametrically split collet being disposed in the socket and being wedged between, and resiliently deformed between, a surface constituted by the periphery of the plug and a surface constituted by an opposing socket wall, at least one of the surfaces between which the collet is disposed being substantially cylindrical, the collet being formed by two similar half-round parts, whereby in the assembled plug and socket connection the collet has a said longitudinal slit in opposite longitudinal sides thereof, each said half-round part of the collet being of greater curvature at one end than at the other so that each said edge of each said slit forms a cutting edge which penetrates said substantially cylindrical surface and is forced into the member providing said surface, thereby preventing relative rotation, about the axis of said substantially cylindrical surface, between, on the one hand, the collet and, on the other hand, the member providing said substantially cylindrical surface, said two parts of the collet being nonrotatably engaged with the other of the members between which the collet is wedged, whereby relative rotational movement of the collet is prevented.

4,295,755

REEL MOUNTABLE BOOM ARRANGEMENT


Frank Meyers, 317 Calle Mayor, Redondo Beach, Calif. 90277

Filed Apr. 30, 1980, Ser. No. 145,217

Int. Cl.³ E02B 15/04

U.S. Cl. 405—66

66 Claims



1. In an improved containment boom section, the improvement comprising, in combination:
 - flotation means having a predetermined buoyancy to provide upper portions thereof above the surface level of a liquid body for the condition of the boom section deployed in said liquid body, and a lower portion, below the surface level of said liquid body;

said flotation means comprising:

- a longitudinally elongated, flexible, generally tubular member having walls defining an internal cavity, upper portions and lower portions and said tubular member transversely collapsible-expandable, between a transversely flattened, storage condition and a transversely expanded, deployed condition, and said elongated, flexible, generally tubular member windable on a reel in said transversely flattened storage condition;
- a resilient, generally spring-like member having a plurality of helical coil means about a longitudinally extending helix axis and said helical coils having a predetermined helix angle in a helical condition thereof, and said spring-like member extending longitudinally in said cavity of said tubular member, and said helical coils maintaining said walls of said tubular member in said transversely expanded, deployed condition thereof for said spring-like member in said helical condition thereof, and said spring-like member resiliently deformable from said helical condition to a transversely flattened condition for said tubular member in said transversely flattened storage condition thereof, and said spring-like member having a predetermined energy stored therein in said transversely flattened condition, and said predetermined energy having a value at least equal to the energy required to cause said spring-like member to move from said transversely flattened condition to said helical condition thereof for said flotation means deployed in said liquid body;
- a plurality of pocket means in said cavity of said tubular member, and coupled to the walls thereof in a predetermined, spaced array, each of said pocket means having walls defining a coil receiving cavity having side edges extending a predetermined distance around said walls of said tubular member, from regions adjacent said lower portions thereof toward regions adjacent said upper portions thereof, and said side edges of said pocket means positionable adjacent said walls of said tubular member for said tubular member in said transversely expanded, deployed condition thereof, and one of a first group of said plurality of coil means of said spring-like member in said coil receiving cavity of each of said pocket means, and each of said pocket means movable from a transversely upright position for said tubular member in said transversely expanded, deployed condition thereof to a flat-

tened position for said tubular member in said transversely flattened condition thereof.

4,295,756

FLOATING BOOM END CONNECTORS


Russell M. Blair, Westport, Conn., assignor to Slickbar, Inc., Southport, Conn.

Filed Apr. 24, 1979, Ser. No. 32,748

Int. Cl.³ E02B 15/04

U.S. Cl. 405—70

7 Claims



1. A tension transmitting connector for the end of a flat vertically arrayed fin of an elongated floating material containment boom, for joining said end thereof to a tension-applying towing or anchoring plate or to the juxtaposed end of a similar boom, comprising:

- a vertically elongated central tow flange portion juxtaposed to said flat fin end and incorporated a distal engaging portion for interlocking engagement with the adjacent distal towing plate or anchoring plate of an adjacent connector, wherein the engaging portion comprises a raked, tension-carrying scarf jaw forming a scarf joint interlocking the tow flange with a mating scarf jaw of a tow flange of the adjacent connector;
- two intermediate vertically elongated sidewall portions extending laterally divergently from the central flange portion to define an enlarged vertical central cavity embracing the vertical fin end and reconverging to form facing proximal end flanges sandwiching the fin end therebetween in a narrow vertical proximal entrance portal slot; and
- a vertically elongated anchoring core positioned inside the central cavity co-acting with the fin end and blocking its withdrawal through the portal slot.

4,295,757

JET SLED SPOIL SCOOP APPARATUS

Randal Gaspar, P.O. Box 2352, Morgan City, La. 70380

Filed Aug. 23, 1979, Ser. No. 68,919

Int. Cl.³ E02F 5/02; F16L 1/04


U.S. Cl. 405—163

11 Claims

1. A pipe burying apparatus comprising:

- a frame;
- means on said frame adapting said frame for undersea towing;
- left and right jetting means on said frame for cutting at least the left and right side walls of an undersea pipe trench as said frame is towed;
- left and right air lift conduit means, each providing spoil intake and spoil discharge portions for removing soil cuttings from the trench cut by said jetting means, said spoil intake portions being placed generally behind and between said left and right jetting means;
- spoil collection scoop means surrounding said spoil intake portions on at least four sides including at least the rear side thereof for collecting soil cuttings about said spoil intake portions of said left and right air lift conduit means, said spoil collection means having independently movable

rear and bottom door portions which move to a first open position to allow placement of said frame about a pipeline



to be buried, and subsequent closure of said rear and bottom door portions after said frame is placed about a pipeline to be buried.

4,295,758

WORKING PLATFORM FOR OIL DRILLING OPERATIONS IN ICE COVERED SEA AREAS

Nobuyoshi Yashima, Funabashi, Japan, assignor to Mitsui Engineering and Shipbuilding Co., Ltd., Tokyo, Japan


Filed Nov. 27, 1979, Ser. No. 97,933

Claims priority, application Japan, Nov. 30, 1978, 53-148875; Nov. 30, 1978, 53-14876

Int. Cl.³ E02D 17/00

U.S. Cl. 405—201

13 Claims



1. A working platform for oil drilling operations in ice-covered sea areas, said working platform comprising a platform means floating on the surface of the sea-water, oil drilling equipment mounted on said platform means, an oil drilling pipe extending from said oil drilling equipment to the bottom of said sea, a buoyant floating frame disposed around said platform means such that said frame is spaced from said platform means, said frame enclosing the surface of the sea water surrounding said drilling pipe, wherein said frame has sufficient strength to withstand the pressure of the ice and is movable in accordance with the movements of the ice, and heat insulating means for heat insulating the surface of the sea-water inside of said floating frame and is between said frame and said platform means.

4,295,759 DEVICE FOR THE CONTROL OF THE INTERNAL PRESSURE IN A DRILL PIPE FOR THE CONSTRUCTION OF FOOTINGS

Hans Mathieu, and Jürgen Hochstrasser, both of Saarbrücken, Fed. Rep. of Germany, assignors to Elisabeth Hochstrasser geb. Wack and Jürgen Hochstrasser, both of, Fed. Rep. of Germany


Filed Feb. 4, 1980, Ser. No. 118,504

Claims priority, application Fed. Rep. of Germany, Feb. 7, 1979, 2905042

Int. Cl.³ E02D 15/04

U.S. Cl. 405—243

9 Claims



1. Device for the control of the internal pressure in a drill pipe for the construction of footings especially of compressed concrete footings with a valve, which valve is located in a lid, which lid serves for the tight seal of the drill pipe, which valve is equipped with venting holes, which valve is subjected to the internal pressure of the drill pipe in the direction of closing, which valve is subjected to a counterpressure, the effective power of which counterpressure is greater than the effective power of the internal pressure and where a hoisting cable is connected to the valve stem, the power of which hoisting cable is adjustable in the closing direction, and the power of which hoisting cable under normal operating conditions in combination with the internal pressure of the drill pipe is large enough to overcome the counterpressure, and where the valve shaft is equipped with a valve hat of a smaller diameter, which valve hat serves to seal the inner space of the drill pipe, and where the valve shaft is further equipped with a ring-shaped piston of larger diameter, which ring-shaped piston forms a counterpressure chamber with the valve housing, and where the counterpressure chamber is connected with the inside of the drill pipe by means of a drilled hole, which drilled hole is axially located in the valve shaft, and which drilled hole extends through the valve hat, characterized by the fact that a check valve (13) is located in the axial drilled hole (11) and that a parallel line (14) is provided which extends through the valve hat (8) and the ring-shaped piston (9), and which parallel line constitutes a restrictor.

4,295,760

ROCK BOLT ANCHOR

Clifford C. Warner, 7381 Bryant St., Westminster, Colo. 80030

Continuation-in-part of Ser. No. 898,632, Apr. 21, 1978, abandoned. This application Oct. 22, 1979, Ser. No. 86,994


Int. Cl.³ E21D 21/00; F16B 13/04

U.S. Cl. 405—259

19 Claims

1. A rock bolt anchor, comprising:
a head of a diameter to fit within a borehole in rock;

a stem connected to said head and extending axially therefrom, said head extending laterally beyond said stem;
a foot connected to said stem opposite said head, said foot having a lateral dimension less than said head and an inclined surface spaced from said head but comprising a surface of said foot nearest said head, said surface being inclined with respect to the axis of said anchor;
a longitudinal hole in said head, said hole being provided with threads for engaging corresponding threads of a bolt by which said anchor may be moved into said borehole in said rock, said bolt extending through said foot and said stem;
a series of adjoining cam discs surrounding said stem and having a width less than the diameter of said borehole and a length greater than the diameter of said borehole, said cam discs having apertures therein permitting said discs to surround said stem and engaging said inclined surface of said foot in an angular position on said foot during movement of said anchor into said borehole, said stem having a length sufficient to accommodate said angular position of said cam discs;
said anchor being movable into said borehole by said bolt with said cam discs in said angular position to a predetermined point in said borehole;
said anchor being rotatable with said bolt at a sufficient speed to cause said ends of said discs to engage the wall of said borehole and terminate rotation of said discs; and



said inclined surface of said foot being constructed so as to then be engageable with the disc remote from said head to terminate rotation of said head and permit said bolt to thread through said head and said head then retracted by rotation of said bolt, whereby said head engages said cam discs and forces the ends thereof outwardly into the rock of said borehole to restrain further downward movement of said anchor.

14. A method of installing a rock bolt anchor in a borehole in rock, comprising:

mounting a series of adjoining cam discs on a foot having an inclined surface and surrounding a stem connecting said foot and a head of a diameter to fit within said borehole; said stem extending axially from said head and said inclined surface being spaced from said head but comprising a surface of said foot having an apex nearest said head, said surface being inclined with respect to the axis of said anchor;
said head having a longitudinal hole provided with threads for engaging corresponding threads of a bolt by which said anchor is moved into said borehole in said rock, said bolt extending through said foot and said stem;
said cam discs having a width less than the diameter of said borehole and a length greater than the diameter of said borehole, said cam discs having apertures therein permitting said discs to surround said stem and engaging said inclined surface of said foot in an angular position on said foot during movement of said anchor into said borehole,

said stem having a length sufficient to accommodate said angular position of said cam discs;
moving said anchor into said borehole by said bolt with said cam discs in said angular position to a predetermined point in said borehole; and
rotating said bolt at a sufficient rate to cause said cam discs to begin movement toward a position perpendicular to the axis of said bolt and thereby cause the ends of said cam discs to engage the wall of said borehole and terminate rotation of said cam discs, whereby further rotation of said foot causes said apex of said inclined surface to engage the cam disc remote from said head and reduce rotation of said head, thereby permitting said bolt to thread into said head and draw said head into engagement with said cam discs to force the ends thereof outwardly into the rock of said borehole.

4,295,761

POST TENSIONABLE GROUTED ANCHOR ASSEMBLY


Roger M. Hansen, Birmingham, Ala., assignor to Stratabolt Corporation, Pelham, Ala.

Filed Dec. 10, 1979, Ser. No. 101,723

Int. Cl.³ E21D 20/02

U.S. Cl. 405—261

9 Claims



1. A post tensionable rock and mine roof anchor and nut assembly of the grouted or resin anchored type to be installed in a bore hole in a mine roof rock formation or the like and tensioned after mixing and setting of the grouting or resin for strengthening the same, comprising an elongated anchor including a generally cylindrical portion at its upper end having a shorter length than the depth of the bore hole in which it is to be fitted and having an elongated externally threaded rod portion at its lower end adapted to project a predetermined short distance externally of the bore hole when the anchor is normally positioned in substantially fully inserted condition in the bore hole, an internally threaded nut member to threadably receive the threaded rod portion therein providing companion thread surfaces forming a screw thread coupling assembling said nut member and anchor together and said nut member having an end surface to exert bearing force against the face of the rock formation, the anchor being adapted to be introduced into the bore hole in assembled relation with the nut member after insertion of a destructible cartridge containing quick-setting adhesive resin or grouting material therein to crush the cartridge and mix and distribute the resin or grouting material throughout the space outwardly surrounding most of the anchor and fixing the anchor in the bore hole upon hardening of such material thereabout, the nut member having a bore there-through including a first smaller diameter bore portion extending from said end surface through a major portion of the axial depth of the nut member threaded to mate with the threads of the external threaded rod portion and having a second enlarged diameter bore portion forming the exit end of the bore communicating with the first bore portion, a disc seated in the second bore portion, and inwardly crimped lip formations integral with the nut surrounding the exit end of the bore and inwardly lapping the periphery of the disc in said second bore portion to retain the disc therein in position to bar penetration of the anchor rod portion through the nut until a predetermined torque force level is exceeded, the nut member being

initially assembled in threaded relation with the threaded rod portion of the anchor to occupy an initial assembled position wherein the disc restrains relative rotation of the nut member with respect to the anchor until said predetermined torque force level is exceeded, and said crimped lip formations releasing the disc and accommodating further threaded insertion of the rod portion through the bore of the nut when the anchor is restrained against rotation by setting of the adhesive resin or grouting material and torque force in excess of the predetermined torque force level is applied to the nut member.

4,295,762

GROUTING-SOIL CONDITIONING SYSTEMS USING POLYOXYETHYLENE DIACRYLATES

Manuel Slovinsky, Woodridge, Ill., assignor to Nalco Chemical Company, Oak Brook, Ill.

Continuation-in-part of Ser. No. 13,105, Feb. 21, 1979, abandoned. This application Sep. 18, 1980, Ser. No. 188,185
Int. Cl.³ C09K 17/00

U.S. Cl. 405—264

10 Claims

1. A process of stabilizing soil which comprises contacting from about 3 to about 20 parts by weight of such soil with about one part by weight of an aqueous solution containing at least 0.5 weight percent of a water-soluble diacrylate ester of a polyoxyalkylene glycol monomer having a molecular weight of at least 300, which solution also contains a water-soluble free radical polymerization catalyst capable of polymerizing the monomer into a water-insoluble gel.

4,295,763


PLUG CUTTER

James J. Cunniff, 46 Lynnrich Dr., Thomaston, Conn. 06787

Continuation-in-part of Ser. No. 960,603, Nov. 14, 1978, abandoned. This application May 29, 1979, Ser. No. 43,364
Int. Cl.³ B27C 5/00

U.S. Cl. 408—86

17 Claims



1. A plug cutter adapted for use in a drill press or the like, said cutter comprising

a holder having one portion adapted to be held for rotation on an axis coincident with the spindle of a drill press, and a second portion defining at least two symmetrically arranged sets of sockets with lands of each set circumaxially spaced and oriented at the same angle to said axis, each set having lands oriented at different angles with respect to said axis, cutting blades with portions adapted to be received in said sockets and having projecting portions extending beyond said holder in parallel relationship to said lands to produce a multitapered plug, and means for securing said blades in said sockets.

4,295,764 MOBILE MACHINE FOR REMOVING SURFACE IRREGULARITIES FROM RAIL HEADS

Josef Theurer, and Klaus Riessberger, both of Vienna, Austria, assignors to Franz Plasser Bahnbaumaschinen-Industriegesellschaft m.b.H., Vienna, Austria


Filed Dec. 11, 1978, Ser. No. 968,264

Claims priority, application Austria, Dec. 30, 1977, 9451/77

Int. Cl.³ B23D 1/10; B24B 23/00; B23D 7/06

U.S. Cl. 409—296

18 Claims



1. A mobile machine mounted on a track having two rails including heads and the machine being arranged for advancement along the track for removing irregularities from the surfaces of the rail heads to a predetermined depth, which comprises

- (a) a machine frame,
- (b) an elongated tool carrier extending in a plane substantially parallel to the track and rigidly resistant to bending out of said plane, and vertically adjustably mounted on the machine frame and arranged thereon for vertical and lateral guidance without play along a respective one of the track rails,
- (c) a cutter head on the tool carrier, the cutter head having
 - (1) a cutting tool capable of machining the surface of the head of the respective track rail continuously upon advance of the tool carrier along the track rail, and
- (d) a hydraulic jack unit linking the tool carrier to the machine frame for vertically adjusting the tool carrier and subjecting the tool carrier to a vertically directed loading force sufficient to obtain the predetermined machining depth.

4,295,765

TIE-DOWN STRUCTURE


Michael R. Burke, 1017 Poplar Ct., Mt. Carmel, Ill. 62863

Filed Apr. 23, 1979, Ser. No. 32,551

Int. Cl.³ A62B 35/00; B61D 45/00

U.S. Cl. 410—101

6 Claims



1. A tie-down structure comprising a body member having a head with a top wall and an outwardly flaring side wall and a threaded stem, said threaded stem adapted to extend through an opening formed in a supporting surface, and a plug member and threaded means disposed on said threaded stem on a side of said supporting surface opposite to that of said head, said plug member freely movable on said threaded stem of said body member and having an outwardly flaring inner wall complementary in shape to said outwardly flaring side wall of said head and said threaded means in a stopping relationship therewith, where said top wall of said head is substantially flush

with a deformed portion of said opening in said supporting surface at an installed position.

therebetween from an electrical discharge passing through the base member from the other side of said support member.

4,295,766

SELF-ALIGNING DOME NUT

Francis Shaw, Old House Landing and Bianca Rd., East Hampton, N.Y. 11937


Continuation-in-part of Ser. No. 928,542, Jul. 27, 1978,

abandoned. This application Jan. 25, 1979, Ser. No. 6,667

Int. Cl.³ F16B 37/14, 39/00

U.S. Cl. 411—113

17 Claims



1. A self-aligning dome nut comprising:

- (a) a base member having:
 - (1) a neck portion extending from one side thereof for attachment into an aperture of a support member with at least part of the one side of said base member resting directly on the support member,
 - (2) a hole extending through said neck portion in the direction of the extension thereof, and
 - (3) a cavity in the other side of the base member in communication with the hole in the neck portion;
- (b) a nut member loosely positioned within said cavity and in adjustable alignment with the hole in said neck portion, said nut being held against extended rotation within the cavity; and
- (c) a protective covering dome enclosing said cavity and covering the nut member, said dome having an open end connected to the base member radially inwardly of its outer periphery to leave generally the entire other side of the base member available for direct application of a clamping force during attachment of the dome nut to the support member, the available portion being in alignment with the part of the one side of the base member resting directly on the support member.

11. A lightning-safe connection between a self-aligning dome nut and a support member comprising:

- (a) an electrically conductive support member having an aperture therethrough;
- (b) a dome nut including:
 - (i) an electrically conductive base member having:
 - (ii) a neck portion extending from one side thereof and secured in the aperture of the support member with the one side of said base member facing the support member,
 - (iii) a hole extending through said neck portion in the direction of extension thereof, and
 - (iv) a cavity in the other side of the base member in communication with the hole in the neck portion,
 - (2) a nut member loosely positioned within said cavity and in adjustable alignment with the hole in said neck portion, said nut being held against extended rotation within the cavity, and
 - (3) a protective covering dome enclosing said cavity and covering the nut member, said dome having an open end connected to the base member; and
 - (c) a non-conductive insulating washer disposed around said neck portion and between the one side of the base member and the underlying side of the support member, said washer being dimensioned to electrically isolate the base member from the radially surrounding area of the underlying support member by a distance sufficient to prevent electrical arcing

4,295,767

CORROSION RESISTANT FASTENER


John W. Temple, Jr., Box 43, Signal Mountain, Tenn. 37377

Filed Nov. 26, 1979, Ser. No. 97,361

Int. Cl.³ F16B 27/00

U.S. Cl. 411—377

7 Claims



1. A corrosion resistant screw-type fastener comprising a ferrous metal body having an axially extending shank with external threads and a retaining head, said retaining head having a cylindrical portion adjacent said threads and a retaining portion adjacent said cylindrical portion remote from said threads, said retaining portion having a larger radial cross-sectional configuration than that of said cylindrical portion, a non-ferrous metal head fixedly disposed in engagement with and encapsulating the retaining portion and an adjacent part of the cylindrical portion, said non-ferrous head having an axially depending skirt spaced radially from the non-encapsulated part of the cylindrical portion to define an annular recess between the skirt and the non-encapsulated cylindrical portion, and a disk shaped seal positioned about said non-encapsulated, cylindrical portion wholly within the circumferential confines of said recess and extending partly outside the axial confines of said recess.

4,295,768

CHIP BREAKER SCREWS


Edwin J. Skierski, Campbellsville, Ky., assignor to USM Corporation, Farmington, Conn.

Filed Sep. 21, 1979, Ser. No. 77,664

Int. Cl.³ F16B 25/00

U.S. Cl. 411—387

8 Claims



1. A drilling and thread-forming screw comprising a threaded shank and a pilot end disposed on a common centerline, a pair of flutes extending longitudinally of said pilot end to provide a pair of cutting surfaces disposed substantially parallel to a common plane and a pair of drag surfaces substantially perpendicular to said cutting surfaces, each of said cutting surfaces terminating at a cutting edge forming an angle with said common centerline, each of said cutting surfaces further having disposed thereon a discrete chip breaker in the form of a truncated cylindrical element having its cylindrical centerline substantially perpendicular to said cutting edge, and an end surface having an arcuate periphery, said surface forming

initially assembled in threaded relation with the threaded rod portion of the anchor to occupy an initial assembled position wherein the disc restrains relative rotation of the nut member with respect to the anchor until said predetermined torque force level is exceeded, and said crimped lip formations releasing the disc and accommodating further threaded insertion of the rod portion through the bore of the nut when the anchor is restrained against rotation by setting of the adhesive resin or grouting material and torque force in excess of the predetermined torque force level is applied to the nut member.

4,295,762

GROUTING-SOIL CONDITIONING SYSTEMS USING POLYOXYETHYLENE DIACRYLATES

Manuel Slovinsky, Woodridge, Ill., assignor to Nalco Chemical Company, Oak Brook, Ill.

Continuation-in-part of Ser. No. 13,105, Feb. 21, 1979, abandoned. This application Sep. 18, 1980, Ser. No. 188,185
Int. Cl.³ C09K 17/00

U.S. Cl. 405—264

10 Claims

1. A process of stabilizing soil which comprises contacting from about 3 to about 20 parts by weight of such soil with about one part by weight of an aqueous solution containing at least 0.5 weight percent of a water-soluble diacrylate ester of a polyoxyalkylene glycol monomer having a molecular weight of at least 300, which solution also contains a water-soluble free radical polymerization catalyst capable of polymerizing the monomer into a water-insoluble gel.

4,295,763


PLUG CUTTER

James J. Cunniff, 46 Lynnrich Dr., Thomaston, Conn. 06787

Continuation-in-part of Ser. No. 960,603, Nov. 14, 1978, abandoned. This application May 29, 1979, Ser. No. 43,364
Int. Cl.³ B27C 5/00

U.S. Cl. 408—86

17 Claims



1. A plug cutter adapted for use in a drill press or the like, said cutter comprising

a holder having one portion adapted to be held for rotation on an axis coincident with the spindle of a drill press, and a second portion defining at least two symmetrically arranged sets of sockets with lands of each set circumaxially spaced and oriented at the same angle to said axis, each set having lands oriented at different angles with respect to said axis, cutting blades with portions adapted to be received in said sockets and having projecting portions extending beyond said holder in parallel relationship to said lands to produce a multitapered plug, and means for securing said blades in said sockets.

4,295,764 MOBILE MACHINE FOR REMOVING SURFACE IRREGULARITIES FROM RAIL HEADS

Josef Theurer, and Klaus Riessberger, both of Vienna, Austria, assignors to Franz Plasser Bahnbaumaschinen-Industriegesellschaft m.b.H., Vienna, Austria


Filed Dec. 11, 1978, Ser. No. 968,264

Claims priority, application Austria, Dec. 30, 1977, 9451/77

Int. Cl.³ B23D 1/10; B24B 23/00; B23D 7/06

U.S. Cl. 409—296

18 Claims



1. A mobile machine mounted on a track having two rails including heads and the machine being arranged for advancement along the track for removing irregularities from the surfaces of the rail heads to a predetermined depth, which comprises

- (a) a machine frame,
- (b) an elongated tool carrier extending in a plane substantially parallel to the track and rigidly resistant to bending out of said plane, and vertically adjustably mounted on the machine frame and arranged thereon for vertical and lateral guidance without play along a respective one of the track rails,
- (c) a cutter head on the tool carrier, the cutter head having
 - (1) a cutting tool capable of machining the surface of the head of the respective track rail continuously upon advance of the tool carrier along the track rail, and
- (d) a hydraulic jack unit linking the tool carrier to the machine frame for vertically adjusting the tool carrier and subjecting the tool carrier to a vertically directed loading force sufficient to obtain the predetermined machining depth.

4,295,765

TIE-DOWN STRUCTURE


Michael R. Burke, 1017 Poplar Ct., Mt. Carmel, Ill. 62863

Filed Apr. 23, 1979, Ser. No. 32,551

Int. Cl.³ A62B 35/00; B61D 45/00

U.S. Cl. 410—101

6 Claims



1. A tie-down structure comprising a body member having a head with a top wall and an outwardly flaring side wall and a threaded stem, said threaded stem adapted to extend through an opening formed in a supporting surface, and a plug member and threaded means disposed on said threaded stem on a side of said supporting surface opposite to that of said head, said plug member freely movable on said threaded stem of said body member and having an outwardly flaring inner wall complementary in shape to said outwardly flaring side wall of said head and said threaded means in a stopping relationship therewith, where said top wall of said head is substantially flush

with a deformed portion of said opening in said supporting surface at an installed position.

therebetween from an electrical discharge passing through the base member from the other side of said support member.

4,295,766

SELF-ALIGNING DOME NUT


Francis Shaw, Old House Landing and Bianca Rd., East Hampton, N.Y. 11937

Continuation-in-part of Ser. No. 928,542, Jul. 27, 1978, abandoned. This application Jan. 25, 1979, Ser. No. 6,667

Int. Cl.³ F16B 37/14, 39/00

U.S. Cl. 411—113

17 Claims



1. A self-aligning dome nut comprising:

- (a) a base member having:
 - (1) a neck portion extending from one side thereof for attachment into an aperture of a support member with at least part of the one side of said base member resting directly on the support member,
 - (2) a hole extending through said neck portion in the direction of the extension thereof, and
 - (3) a cavity in the other side of the base member in communication with the hole in the neck portion;
- (b) a nut member loosely positioned within said cavity and in adjustable alignment with the hole in said neck portion, said nut being held against extended rotation within the cavity; and
- (c) a protective covering dome enclosing said cavity and covering the nut member, said dome having an open end connected to the base member radially inwardly of its outer periphery to leave generally the entire other side of the base member available for direct application of a clamping force during attachment of the dome nut to the support member, the available portion being in alignment with the part of the one side of the base member resting directly on the support member.

11. A lightning-safe connection between a self-aligning dome nut and a support member comprising:

- (a) an electrically conductive support member having an aperture therethrough;
- (b) a dome nut including:
 - (i) an electrically conductive base member having:
 - (ii) a neck portion extending from one side thereof and secured in the aperture of the support member with the one side of said base member facing the support member,
 - (iii) a hole extending through said neck portion in the direction of extension thereof, and
 - (iv) a cavity in the other side of the base member in communication with the hole in the neck portion,
 - (2) a nut member loosely positioned within said cavity and in adjustable alignment with the hole in said neck portion, said nut being held against extended rotation within the cavity, and
 - (3) a protective covering dome enclosing said cavity and covering the nut member, said dome having an open end connected to the base member; and
 - (c) a non-conductive insulating washer disposed around said neck portion and between the one side of the base member and the underlying side of the support member, said washer being dimensioned to electrically isolate the base member from the radially surrounding area of the underlying support member by a distance sufficient to prevent electrical arcing

4,295,767

CORROSION RESISTANT FASTENER


John W. Temple, Jr., Box 43, Signal Mountain, Tenn. 37377

Filed Nov. 26, 1979, Ser. No. 97,361

Int. Cl.³ F16B 27/00

U.S. Cl. 411—377

7 Claims



1. A corrosion resistant screw-type fastener comprising a ferrous metal body having an axially extending shank with external threads and a retaining head, said retaining head having a cylindrical portion adjacent said threads and a retaining portion adjacent said cylindrical portion remote from said threads, said retaining portion having a larger radial cross-sectional configuration than that of said cylindrical portion, a non-ferrous metal head fixedly disposed in engagement with and encapsulating the retaining portion and an adjacent part of the cylindrical portion, said non-ferrous head having an axially depending skirt spaced radially from the non-encapsulated part of the cylindrical portion to define an annular recess between the skirt and the non-encapsulated cylindrical portion, and a disk shaped seal positioned about said non-encapsulated, cylindrical portion wholly within the circumferential confines of said recess and extending partly outside the axial confines of said recess.

4,295,768

CHIP BREAKER SCREWS


Edwin J. Skierski, Campbellsville, Ky., assignor to USM Corporation, Farmington, Conn.

Filed Sep. 21, 1979, Ser. No. 77,664

Int. Cl.³ F16B 25/00

U.S. Cl. 411—387

8 Claims



1. A drilling and thread-forming screw comprising a threaded shank and a pilot end disposed on a common centerline, a pair of flutes extending longitudinally of said pilot end to provide a pair of cutting surfaces disposed substantially parallel to a common plane and a pair of drag surfaces substantially perpendicular to said cutting surfaces, each of said cutting surfaces terminating at a cutting edge forming an angle with said common centerline, each of said cutting surfaces further having disposed thereon a discrete chip breaker in the form of a truncated cylindrical element having its cylindrical centerline substantially perpendicular to said cutting edge, and an end surface having an arcuate periphery, said surface forming

an angle greater than 90° with said cutting surface to thereby form a ramp to direct a continuous chip formed by said cutting surface away from said surface to form a small radius of curvature and thereby cause breakage of the chip, said chip breaker being spaced from the edges of said cutting surface, including said cutting edge whereby the configuration of said pilot end is substantially unchanged by the addition of said discrete chip breaker.

4,295,769

COPPER AND NITROGEN CONTAINING AUSTENITIC STAINLESS STEEL AND FASTENER

Joseph A. Douthett, Monroe, and Ronald H. Espy, West Chester, both of Ohio, assignors to Armco Inc., Middletown, Ohio
Filed Feb. 28, 1980, Ser. No. 125,551

Int. Cl.³ C22C 38/16; F16B 53/06

U.S. Cl. 411—411

8 Claims

1. Austenitic stainless steel having good hot working properties, a 0.2% offset yield strength of 165 to 182 ksi and an elongation in 5 cm of at least 10% if cold reduced 60%, said steel consisting essentially of, in weight percent, 0.05% maximum carbon, 1.5% to 3.0% manganese, about 0.06% maximum phosphorus, about 0.035% maximum sulfur, about 1% maximum silicon, about 15% to about 20% chromium, 3% to 4.7% nickel, 1.75% to 3% copper, 0.10% to 0.30% nitrogen, up to about 0.3% columbium, titanium, tantalum or mixtures thereof, and balance essentially iron, said steel having an austenite stability factor ranging between about 30 and about 33 calculated by the formula $30 \times \%C + \%Mn + \%Cr + \%Ni + \%Cu + 30 \times \%N$.

4. The steel claimed in claim 1 in the form of cold headed fasteners fabricated from 60% cold reduced wire.

4,295,770

HOOKBOLT ADAPTER

Gordon H. S. Alderton, Bingley, England, assignor to Henry Lindsay Limited, Shipley, England


Filed Oct. 11, 1979, Ser. No. 83,831

Claims priority, application United Kingdom, Oct. 16, 1978, 40653/78

Int. Cl.³ F16B 43/02

U.S. Cl. 411—531

8 Claims



1. A hookbolt adapter for use with a bolt in order to convert the latter into a hookbolt, the hookbolt comprising:

- a member having therein a hole of circular cross-section through which a shank of a bolt can be taken, said hole having an entrance thereto and a wall;
- a nose portion and a tail portion of said member diametrically opposed to one another with respect to said hole;
- a support surface of said member surrounding said entrance to said hole to be engaged by a head or by a nut of a bolt, said hole having an axis which is slightly inclined to a line perpendicular to said support surface; and
- two diametrically opposed substantially semi-circular contact portions of said member provided on said wall of said hole and each associated with a respective one of said nose portion and said tail portion, said contact portions being made of malleable material so as to allow a bolt to take-up a position in which the axis of such a bolt will extend substantially perpendicular to said support surface

and such a bolt will be held rigidly with the hookbolt adapter by said contact portions.

4,295,771

PORTABLE LOAD HANDLING APPARATUS


Thomas C. Mehesan, Jr., Hoppers, Iowa, assignor to Banner Industries, Inc., Hoppers, Iowa

Filed Aug. 20, 1979, Ser. No. 68,201

Int. Cl.³ B60P 3/00; B65G 61/00

U.S. Cl. 414—5

9 Claims



1. A load handling apparatus comprising, a movable vehicle including a frame, an elongated boom arm having opposite end portions, means for operatively connecting said boom arm to said frame for pivotal movement about a first generally horizontal axis and a first generally vertical axis, primary power means connected to said boom arm and frame for pivotally moving said boom arm about said first horizontal axis and first vertical axis, said boom arm being longitudinally extendable and retractable for movement of one end portion toward and away from said first horizontal axis and said primary power means including means for longitudinally extending and retracting said boom arm,

a load support member, wrist means interconnecting said load support member and said one end portion of said boom arm for pivotal movement of said load support member adjacent said one end portion of said boom arm and about first and second axes disposed generally perpendicular to one another and to the longitudinal centerline of said boom arm, means for supporting said wrist means on said one end portion of said boom arm for pivotal movement of said wrist means about a third axis disposed generally parallel to the longitudinal centerline of said boom arm, secondary power means connected to said wrist means for pivotally moving said load support member about said first and second axes and for pivotally moving said wrist means about said third axis, and

control means for selectively actuating said primary and secondary power means for movement of at least one of said boom arm and load support member about at least a selected one of said axes, said control means including an elongated control arm having opposite ends, means for connecting said control arm to said frame for pivotal movement about a second generally horizontal axis and a second generally vertical axis, means for extending and retracting said control arm for movement of said one end toward and away from said second horizontal axis, means for actuating said primary power means to pivotally move said boom arm about said first horizontal axis and first vertical axis in response to pivotal movement of the control arm about the second horizontal axis and second vertical axis respectively and means for actuating said primary power means to longitudinally extend and retract said boom arm in response to extension and retraction of said control arm such that said boom arm follows the movements of said control arm,

a control handle operatively connected to said one end of said control arm with freedom of pivotal movement of at least a portion of said handle about fourth and fifth axes disposed generally perpendicular to one another and to the longitudinal centerline of said control arm, means for supporting said control handle on said one end of said control arm for pivotal movement of said control handle about a sixth axis disposed generally parallel to the longitudinal centerline of said control arm, and means for actuating said secondary power means to pivotally move said load support member about said first and second axes in response to pivotal movement of at least said portion of the control handle about said fourth and fifth axes respectively and to pivotally move said wrist means about said third axis in response to pivotal movement of said control handle about said sixth axis such that said load support member follows the movements of said control handle.

4,295,772

HAY BALE STACKER


Lawrence Zimmerman, R.F.D. 2, New Richmond, Wis. 54017

Filed May 7, 1980, Ser. No. 147,463

Int. Cl.³ A01D 87/12; B65G 57/28

U.S. Cl. 414—38

8 Claims



1. A tiltable device for stacking bales behind a hay baler and for lifting and transporting stacks of bales so formed comprising in combination,

- (a) a trailer assembly comprising an axle provided with wheels at each end and a hitch unit attached thereto adapted to be attached to a towing vehicle;
- (b) a bale carrying bed of generally "L" shaped cross-section pivotally attached to said axle, said bed being attached to said axle at a point on the forward leg of said "L", spaced from the junction of said legs a distance which is less than the radius of said wheels; the angle between the legs of said "L" being greater than 90°;
- (c) the more forward leg of said "L" forming a platform suitable to support a standing person and being equipped with side rails;
- (d) the rearward leg of said "L" comprising a plurality of bale supporting tines adapted to support a stack of bales manually assembled there-against, the extremities of said tines on said rearward leg adapted to touch the ground on pivoting of said assembly, and
- (e) means for pivoting said assembly about said axle.

4,295,773

APPARATUS AND METHOD FOR INTRODUCING SOLIDS INTO A SOLIDS UPFLOW VESSEL

Roland O. Dhondt, Long Beach, Calif., assignor to Union Oil Company of California, Brea, Calif.

Filed Nov. 9, 1979, Ser. No. 92,688

Int. Cl.³ C10B 31/02


U.S. Cl. 414—187

24 Claims

1. An apparatus for introducing particulate solids upwardly

into a solids upflow vessel having a bottom solids inlet, which comprises:

- a stationary feed cylinder mounted below said upflow vessel in coaxial alignment with said solids inlet, said feed cylinder having a substantially solids-tight upper cylindrical section of a preselected height and a lower cylindrical section having at least one solids inlet opening;
- at least one solids feed chute mounted adjacent said upflow vessel and having a discharge end communicating with said feed cylinder through said inlet opening, said feed chute having an inlet end communicating with an elevated feed reservoir and being adapted to transport particulate solids from said feed reservoir into said lower section by mechanically unassisted gravity flow through said feed chute;
- a piston movably mounted in said feed cylinder for vertical reciprocation along the common axis of said feed cylinder and said solids inlet;
- piston actuator means for reciprocating said piston along said common axis;
- backflow prevention means interposed between said feed cylinder and said solids inlet, said backflow prevention means being adapted to prohibit backflow of solids from said upflow vessel during the filling of said feed cylinder and to allow displacement of solids from said feed cylinder upwardly through said solids inlet; and
- sealing means for sealing the inlet opening of said feed cylinder during the displacement of said solids into said upflow vessel.



12. A method for transporting particulate solids from an elevated solids feed reservoir and introducing said solids upwardly into a solids upflow vessel having a bottom solids inlet, said method comprising:

- (a) transporting a charge of particulate solids by mechanically unassisted gravity flow from said feed reservoir downwardly through at least one solids feed chute into a lower cylindrical section of a stationary feed cylinder mounted below and in coaxial alignment with said solids inlet, said feed cylinder being fitted with a piston axially reciprocable among at least three piston positions along the common axis of said feed cylinder and said solids inlet;
- (b) extending said piston from a lowermost first piston position upwardly to a second piston position so as to displace said charge of particulate solids from said lower section upwardly into a substantially solids-tight upper cylindrical section of said feed cylinder;
- (c) communicating said upper section of said feed cylinder with said solids inlet;
- (d) thereafter further extending said piston upwardly to an uppermost third piston position so as to displace substantially all of said charge of particulate solids upwardly into said solids upflow vessel;
- (e) thereafter positioning a backflow prevention element directly below said solids inlet so as to prevent backflow of said solids downwardly through said solids inlet; and
- (f) retracting said piston to said first piston position.


4,295,774

APPARATUS FOR AUTOMATICALLY TURNING OVER AND FOR STORING SECTIONS OF ELASTOMERIC MATERIAL

Silvio Manini, and Antonio Pacciarini, both of Milan, Italy,
assignors to Industrie Pirelli S.p.A., Milano, Italy
Continuation of Ser. No. 825,764, Aug. 18, 1977, which is a
division of Ser. No. 577,459, May 14, 1975, Pat. No. 4,062,458.
This application Jul. 26, 1979, Ser. No. 61,047
Claims priority, application Italy, Jun. 28, 1974, 24491 A/74
Int. Cl.³ B65G 1/00

U.S. Cl. 414—331

9 Claims



1. An apparatus for handling sections of elastomeric material
having first and second side comprising:
a frame;

a first transporting device and a means for receiving said
sections which advance on a given plane and according to
a stated direction along the line of arrival, and for transfer-
ring them onto said first transporting device;
means for overturning each section about an axis parallel to
one of said sides of said section;
means for collecting each section coming from a first given
direction and for positioning it on said overturning means;
means for blocking said section on said overturning means;
means for releasing and transferring said section from said
overturning means in an overturned position onto said
first transporting device;
said overturning means comprising a substantially cylindrical
member mounted on said frame and rotatable about its
substantially horizontal longitudinal axis;
said collecting means comprising at least one supporting
surface for said section, obtained by means of two planes
mating together along a side parallel to said longitudinal
axis of the cylindrical member and having a length equal
to that of said cylindrical member, said two planes form-
ing together an obtuse angle having its concavity directed
towards the outside of said cylindrical member, said sup-
porting surface defining a portion of the peripheral surface
of said cylindrical member;

said blocking means comprising pliers for blocking the sec-
tions, having one end pivoted to said cylindrical member
along a second axis arranged parallel to the side common
to the two planes, and of such a shape whereby the other
end of said pliers upon rotation of said second axis
contacts said side common to the two planes at the side of
the concavity;

said transferring means comprising first and second rollers
rotatably mounted on said frame and a first system of
laterally spaced conveyor belts wound about said first and
second rollers, said system of belts defining a transport
plane situated below said cylinder, said rollers being de-
fined with respect to the direction of motion of the plane
as a front roller and a back roller respectively, the motion
of said transport plane taking place from the front to the
back roller, said belts and pliers being situated so that said
pliers are situated at the spaces between said conveyor
belts.


4,295,775

UNLOADER FOR HOPPER CARS AND METHOD William P. Cottrill, Tampa, Fla., and Andrew J. Cisternino, Atlanta, Ga., assignors to Evacuators, Inc., Tampa, Fla.

Filed Oct. 9, 1979, Ser. No. 82,963
Int. Cl.³ B65G 67/24

U.S. Cl. 414—375

7 Claims



2. A method for unloading material from a hopper car or the
like wherein said material is normally flowable and is packed,
which retards such flowing, said method including the steps of
opening the gate to one hopper of said hopper car, placing a
tube through the top of said hopper car into said hopper car
and in said material with the end of said tube generally at said
one hopper, and discharging a blast aerator through said tube
for discharging some of said material through said one hopper
and fluidizing material within said car to render such material
flowable, and including the steps of rotating said tube about its
axis while urging said material away from said end of said tube
to prevent entry of material into said tube, and inserting said
tube into said material in order to perform the step of placing
a tube in said material.

4. Unloading apparatus for facilitating material flow from a
hopper car or the like, said hopper car having an open top, at
least one hopper on the bottom thereof through which material
is to flow for unloading said material, said apparatus compris-
ing a housing disposable over said open top of said hopper car,
a tube rotatably carried by said housing and depending there-
from, said tube being of sufficient length to extend from said
housing through said material generally to said hopper of said
hopper car, a blast aerator receivable on said housing in com-
munication with said tube, and means for discharging said blast
aerator through said tube, and including seal means fixed to
said housing, said seal means rotatably receiving said tube in
one end thereof, said seal means communicating with said blast
aerator at the other end thereof, and further including a tip
carried by said tube, said tip including a plurality of flanges
disposed across the lower end of said tube generally radially of
said tube and pointed at their lowermost ends, said flanges
converging to a common point.

4,295,776

PORTABLE INVERTER FOR TRANSFERRING BULK GOODS BETWEEN PALLETS

Alan Payne, Poplar Lodge, Beeston, Kings Lynn, Norfolk, and
Robin G. Bunning, Willow House, Gressenhall, East Dere-
ham, Norfolk, both of England

Continuation of Ser. No. 945,278, Sep. 25, 1978, abandoned. This
application Aug. 20, 1980, Ser. No. 179,869

Int. Cl.³ B65G 7/00
U.S. Cl. 414—405


4 Claims

1. A free-standing, portable palletized load inverter for
transferring bulk goods, packed in a plurality of sacks, boxes
and the like and supported on a first generally rectangular
pallet, to a second similar pallet, said palletized load inverter
comprising:

a unitary, three-sided load platform of sheet metal adapted to
be selectively rotated as a unit between an upright attitude
and an inverted attitude, said load platform when in its

said upright attitude being adapted to receive and support
bulk goods stacked onto the first pallet, said load platform
including a sheet metal floor constituting one side of said
three-sided platform onto which the first pallet can be
placed, a sheet metal side wall constituting a second side
of said three-sided platform for retaining the stacked bulk
goods resting against it, said sheet metal side wall being
disposed at substantially right angles to said floor and
being located in abutment with one end edge of said floor,
and a sheet metal rear wall constituting the third side of
said platform and disposed at substantially right angles to
said floor and side wall, said rear wall having edges which
are in abutment with edges of said floor and side wall and
having a length corresponding to that of said floor and a
height corresponding to that of said side wall, and said
sheet metal floor, side wall and rear wall being fixedly
attached to one another at their abutting edges respec-
tively in a unitary configuration which defines a three-
sided load receiving region and which is rotatable as a unit
between said upright and inverted attitudes, said rear wall
being longer than said side wall so that the first pallet can
be loaded widthwise onto the load platform from the front
thereof;

a plurality of intersecting horizontal and transverse reinforc-
ing ribs attached to said floor, to said side wall, and to said
rear wall on the faces thereof which are remote from said



three-sided load receiving region, at least some of said ribs
extending across said faces at positions thereon inward of
the boundary edges of said faces;

means defining a slideway on said rear wall directed parallel
to the rear wall at right angles to said floor;

a sliding member in said slideway which slideably supports a
sheet metal lid projecting therefrom in overlying relation
to said three-sided load receiving region and in spaced
parallel relationship to said sheet metal floor for rotation
as a unit with said load platform and for movement along
a line normal to the plane of said floor, said lid also having
intersecting reinforcing ribs attached to the face thereof
remote from said load receiving region, said lid being
adapted in the said inverted attitude of the load platform
to support the second pallet which had previously been
placed in said load platform, when said load platform was
in its said upright attitude, with the load accepting surface
of the second pallet resting on the top of the said bulk
goods;

hydraulic ram actuating means connected directly between
said load platform and said lid and operative to selectively
extend said lid away from said floor while said load plat-
form is in its said upright attitude to allow the first and
second pallets to be loaded into said load platform, and
said actuating means also being operative selectively to
retract said lid towards said floor to engage the base of the
second pallet after the first and second pallets and the said

bulk goods therebetween have been loaded into said load
platform;

a stand having a rotatable shaft mounted thereon and affixed
to said sheet metal rear wall for supporting the load plat-
form rotatably above ground level, said stand including a
ground-contacting base which extends underneath the
load platform to provide stable support therefor and an
upstanding support frame for the load platform, said
ground-contacting base having at least one structural
portion thereof located above ground level and adapted
to receive the forks of a fork lift truck in lifting engage-
ment therewith for moving said load transfer device from
one location to another; and

means in driving engagement with said rotatable shaft for
selectively rotating said load platform between its said
upright attitude and its said inverted attitude, the direction
of rotation being such that said rib reinforced side wall
supports said bulk goods during the rotation of said load
platform from its said upright attitude into its said inverted
attitude.

4,295,777


ROLL LIFTING DOLLIES

Dwain C. Bell, 1400 Marshall St. NE., Minneapolis, Minn.
55413, and Lloyd E. Anderson, 6408-74th Ave. North, Minne-
apolis, Minn. 55428

Filed Oct. 6, 1980, Ser. No. 194,619
Int. Cl.³ B60P 3/00

U.S. Cl. 414—458

2 Claims



1. Lifting apparatus comprising, in combination:
(A) first and second jack assemblies each comprising
(a) an elongated frame member having first and second
caster wheels supported on the undersurface and at
opposite ends thereof;
(b) a jack shaft affixed to the upper surface of said frame
member generally midway between said opposite ends
and extending perpendicularly to said upper surface of
said frame members;
(c) a jack runner mounted on said jack shaft for reciprocal
motion therealong upon operation of a jack handle;
(d) a stub member of a predetermined length affixed to
said jack runner and extending generally perpendicu-
larly to the longitudinal axis to said jack shaft;
(B) an elongated tubular member coupled between the stub
member on said first jack assembly and the stub member
on said second jack assembly, said tubular member com-
prising a plurality of tubular sections coupled end-to-end
and further including a plurality of relatively short stem
elements connected to at least one of said frame mem-
bers, projecting generally parallel to said jack shaft, said
stem elements having a diameter to telescopically re-
ceive one or more of said tubular segments for storage
when not in use.

4,295,778

APPARATUS FOR LIFTING WASTE CONTAINERS ON TO TRUCKS


Claude Hergaux, 6 & 8 Rue de l'Avenir, 76120 Grand Quevilly, France

Filed Dec. 13, 1978, Ser. No. 969,072

Claims priority, application France, Mar. 17, 1978, 78 08249 Int. Cl.³ B60P 1/00

U.S. Cl. 414—525 R

8 Claims



1. Apparatus for unloading the contents of a relatively large waste container onto a vehicle comprising a lifting assembly located on each side of said vehicle, each of said assemblies comprising a first elongated lever member pivotally mounted at one end to said vehicle and extending along the side of the vehicle for pivotable movement in a generally vertical plane; first means mounted on said vehicle for applying a force to said first lever member to effect pivotable movement thereof; a second elongated lever member carried at one end by the extended end of said first lever member for movement conjointly therewith in said vertical plane and for pivotable movement relative thereto; second means for applying a force to said second lever member mounted on said first lever member to effect pivotable movement thereof; a third lever member carried on the extended end of said second lever member for conjoint movement therewith in said vertical plane and also for pivotable movement relative thereto, said third lever member including means for supporting at least two chains or cables in spaced relation; and third means for applying a force to said third lever member mounted on said second lever to effect pivotable movement thereof, said lever members in each of said assemblies being selectively movable from a first position in which said levers extend along a substantially horizontal axis at the sides of the vehicle and a second position wherein said levers are articulated in said vertical plane to carry the containers above said vehicle, said second and third levers being selectively movable with respect to each other and the first lever to tilt said container in said second position said third lever being movable in an arc sufficient to invert said container beyond the vehicle.

4,295,779

STRAIGHT ARM LOADER


John F. Shumaker, Mt. Pleasant, Iowa, assignor to J. I. Case Company, Racine, Wis.

Filed Apr. 8, 1980, Ser. No. 138,331

Int. Cl.³ E02F 3/70

U.S. Cl. 414—685

7 Claims



1. A loader comprising: a frame having a rearwardly dis-

posed support member; a material handling element disposed adjacent the front end of said frame; a pair of substantially straight lift arms disposed on opposite sides of said frame, each lift arm is pivotally joined at one end to said support member and at the opposite end to said material handling element; means, interconnecting said frame and at least one lift arm, for moving said lift arms between a raised and a lowered position; and wheel means for movably supporting said frame relative to the ground, said wheel means defining two channels at the front end of said frame adapted to receive said lift arms in their lowered position.

4,295,780

APPARATUS FOR AUTOMATICALLY TRANSFERRING WORKPIECES

Yoshimasa Wada, 2411 Ietomi-cho, Ashikaga-shi, Tochigi-ken; Sigeki Yamazaki, 382-36 Oaza-Takabayashi; Isamu Kobayashi, 837 Dainosato, both of Ota-shi, Gunma-ken; Noriyuki Haraguchi, 2-3717 Sakae-cho, Ashikaga-shi, Tochigi-ken, and Minoru Fukuda, 1048 Ishihara, Ota-shi, Gunma-ken, all of Japan


Filed Jul. 6, 1979, Ser. No. 55,167

Claims priority, application Japan, Sep. 24, 1978, 53-117008

Int. Cl.³ B65G 47/34

U.S. Cl. 414—749

4 Claims



1. An apparatus for automatically transferring workpieces, said apparatus comprising:

- a long arm having a first end that is adapted to reciprocally move in the lengthwise direction of the apparatus and a second end which is adapted to reciprocate in a direction perpendicular to the movement direction of said first end;
- a carriage mounted on said first end for movement together therewith;
- a guide for engaging and guiding said second end of said long arm only in an end position thereof remote from the path of said first end;
- a pair of short arms having a length equal to one half of the length of said long arm and disposed in each side of said long arm, one end of each said short arm being pivotally mounted on said long arm at the midpoint thereof and the other end of each said short arm being pivotally located at each side of a crossing point of the movement path of said first end of said long arm and the movement path of said second end of said long arm; and
- a combination crank mechanism and transmission means adapted to oscillate each said short arm about said other end thereof, the second end of said long arm being adapted to move out of engagement with said guide in order to oscillate each said short arm in an angular range up to about 180° from one direction of the movement path of said first end of said long arm to the opposite direction of the same by means of said crank mechanism, both said long arm and said short arms being disposed in the same direction and in a common plane at each stroke end to thereby enable highly smooth carriage movements and accurate positioning thereof at each stroke end.

4,295,781

METHOD FOR OPERATING FLUID MACHINES IN SPINNING-IN-AIR MODE

Kenzyu Ogiwara; Minoru Kawada, and Teiji Ashida, all of Hitachi, Japan, assignors to Hitachi, Ltd., Tokyo and Hitachi Service Engineering Co., Ltd., Ibaraki, both of, Japan


Filed Jun. 22, 1979, Ser. No. 51,173

Claims priority, application Japan, Jul. 21, 1978, 53-88401

Int. Cl.³ F01D 17/00, 19/00

U.S. Cl. 415—1

9 Claims



1. A method for operating a fluid machine in a spinning-in-air mode in synchronism with a transmission system, wherein the fluid machine includes a serial arrangement of working fluid inlet valve, closeable guide vanes, runner within a runner chamber of a casing and draft pipe, so as to define a water retaining chamber immediately adjacent the outer peripheral portion of the runner that will tend to retain water during rotation of the runner in spinning-in-air mode and further includes a leak-water exhaust valve in a pipe having an inlet in the water retaining chamber and a discharge in the draft tube, comprising the steps of:

- with the runner drivingly connected in synchronism with the system and drivingly connected with a rotary machine having power to rotate the runner, and with the runner operating under no load with the inlet valve and guide vanes open and passing working fluid toward and through the runner, closing the guide vanes to shut off the flow of working fluid through the runner;
- thereafter feeding compressed air to the runner chamber to fill the runner chamber within the casing with compressed air and lower the working fluid level in the draft pipe below the runner while continuing rotating the runner in synchronism so that the runner is rotating primarily in compressed air with working fluid remaining in the water retaining chamber between the runner and closeable guide vanes and closing the inlet valve; and
- thereafter opening the leak-water exhaust valve to simultaneously pass the water from the water retaining chamber directly to the draft tube while bypassing the runner, which such opening being conducted after the inlet valve has closed and the pressure within the water retaining chamber substantially equals the pressure within the draft tube while maintaining the synchronized rotational speed of the runner so as to prevent excess rise of water within the draft pipe.

4,295,782

STARTING OF PUMPS OR TURBOPUMPS

Pierre Boussuges, Grenoble, France, assignor to Neyrpic, Grenoble, France


Filed Oct. 19, 1979, Ser. No. 86,675

Claims priority, application France, Oct. 20, 1978, 78 29899

Int. Cl.³ F03B 3/10

U.S. Cl. 415—1

2 Claims



1. A method of starting pumps with immersed wheels, said pumps being of the type with a fixed distributor-diffuser, and according to which the curve of variation of the power at working speed as a function of the flow of fluid passes through a minimum which is between the zero-flow point and the operating point, wherein the method comprises the following sequence:

- putting the pumps into rotation, at a speed lower than operating speed of the motor of the pump with a flow valve closed,
- when the pressure on either side of the said flow valve has reached a differential value which is sufficiently low for its opening to be effected without risk of damage, opening said flow valve to such an extent that it allows, when the unit approaches its operating speed, the flow corresponding to the said minimum of the curve of power-flow at operating speed, and
- progressively opening of said flow valve until it allows the operating flow to pass.

4,295,783

FLUID TURBINE


Barry A. Lebest, 1116 Warburton Ave., Apt. 1K, Yonkers, N.Y. 10701

Filed Feb. 9, 1978, Ser. No. 876,217

Int. Cl.³ F03D 1/04

U.S. Cl. 415—2 R

25 Claims



1. A fluid turbine for generating power when disposed in a free flowing fluid, comprising a rotor means including

a housing, and
 a plurality of rotor blades within said housing adapted to rotate in a reference plane about a longitudinal axis when exposed to said free flowing fluid,
 said housing being provided with a first fluid entrance passage therein for allowing fluid to enter said turbine in a direction lying within said reference plane to engage at least certain ones of said rotor blades, said housing being further provided with a second fluid entrance passage therein contiguous with said first fluid entrance passage for allowing fluid to enter said turbine in another direction oblique to said reference plane,
 means operatively connected to said rotor blades for generating power in response to rotation of said rotor blades, and
 means on said housing adjacent said first and second fluid entrance passages for directing fluid from said passages in a direction lying essentially within said reference plane to impinge upon said rotor blades, and in a direction oblique to said reference plane toward said blades to impinge upon all of said rotor blades, said means on said housing including
 side wall means spaced from said reference plane and inclined with respect to said longitudinal axis, said side wall means extending at least approximately two quadrants around the rotational path of said rotor blades to provide a space adjacent said rotor blades for producing spiral flow of fluid within said housing and between said wall means adjacent said rotor blades.

4,295,784

VARIABLE STATOR


Frank B. Manning, Vernon, Conn., assignor to United Technologies Corporation, Hartford, Conn.

Filed Sep. 26, 1979, Ser. No. 78,980

Int. Cl.³ F01D 17/16

U.S. Cl. 415—162

4 Claims



1. A stator vane actuation system for a compressor of a gas turbine engine including a plurality of axially spaced rows of circumferentially pivotally mounted vanes, an actuator having a connecting rod, a synchronizing ring for each row of vanes mounted external of the engine connecting each vane for pivotal movement, means interconnecting said connecting rod and at least one of said synchronizing rings for positioning each of said vanes in said row upon actuation of said actuator, linkage means connecting said interconnecting means and at least a second synchronizing ring so that actuating said actuator positions said one synchronizing ring for moving said one row of vanes at a given rate and the movement of said second synchronizing ring for moving the attached row of vanes to said second synchronizing ring at a different rate, a fixed elongated member, bell crank means for each of said synchronizing rings pivotally mounted on said fixed elongated member, means interconnecting said bell crank and said synchronizing rings, the bell crank means actuating said one synchronizing ring and the bell crank means actuating said second synchronizing ring being disposed at respectively different angles relative to said elongated member.

4,295,785

REMOVABLE SEALING GASKET FOR DISTRIBUTOR SEGMENTS OF A JET ENGINE

Alain M. J. Lardellier, Melun, France, assignor to Societe Nationale d'Etude et de Construction de Moteurs d'Aviation, Paris, France


Filed Mar. 18, 1980, Ser. No. 131,459

Claims priority, application France, Mar. 27, 1979, 79 07590

Int. Cl.³ F01D 11/02

U.S. Cl. 415—174

8 Claims



1. In a removable seal for guide vane segments of a jet engine wherein a plurality of blades are interconnected by an outer ferrule engageable with a turbine housing and by an inner ferrule upon which the seal is mounted, the improvement comprising:

said seal being mounted in an inwardly facing channel-shaped member removably attached to said inner ferrule, said inner ferrule being an inwardly facing channel-shaped member having, in its outer sides, a plurality of L-shaped recesses each having a leg opening radially inwardly to the inner edge of said outer sides and a circumferentially extending leg, said recesses being engaged by locking tongues on said channel-shaped member.

4,295,786

COMPOSITE SEAL FOR TURBOMACHINERY

Robert C. Bill, Rocky River, and Lawrence P. Ludwig, Fairview Park, both of Ohio, assignors to The United States of America as represented by the Administrator of the National Aeronautics and Space Administration, Washington, D.C.

Division of Ser. No. 931,090, Aug. 8, 1978, Pat. No. 4,207,024, which is a division of Ser. No. 801,290, May 27, 1977, Pat. No. 4,135,851. This application Nov. 20, 1979, Ser. No. 96,255


Int. Cl.³ F01D 11/08

U.S. Cl. 415—174

10 Claims

1. A gas path seal for a turbine or the like having a plurality of blades mounted for rotation about an axis comprising
 a stator shroud having an aerodynamic smooth surface on a thin layer of a deformable metallic material that is wearable relative to said blades and closely spaced to the blade tips whereby said shroud is deformed when said blades rub against said surface,
 a yielding deformable porous backing surrounding said layer to receive said deformed shroud thereby reducing said blade wear by limiting the magnitude of normal

forces measured radially inward which are developed between the blade tips and the shroud, and



a rigid mounting housing surrounding said backing and being secured to the outermost surface of said backing.

4,295,787

REMOVABLE SUPPORT FOR THE SEALING LINING OF THE CASING OF JET ENGINE BLOWERS

Alain M. J. Lardellier, Melun, France, assignor to Societe Nationale d'Etude et de Construction de Moteurs d'Aviation, Paris, France


Filed Mar. 21, 1980, Ser. No. 132,642

Claims priority, application France, Mar. 30, 1979, 79 08583

Int. Cl.³ F04D 29/54; F01D 11/08

U.S. Cl. 415—197

7 Claims



1. In a removable support for sealing linings in the blower casings of jet engines, the casing being at least partially attached to acoustic panels, the improvement comprising: at least two concentric ferrules; an inner ferrule having a part of its internal surface conforming to the flow of the air stream and the other part extending over a zone covered by blades of a rotor, said inner ferrule supporting a lining, an outer ferrule being provided on its external surface with cylindrical surfaces adapted to engage surfaces provided on the internal surface of the casing by means of force fitting, the space between the two ferrules being filled with a filler material, and at least one ferrule of U-shaped cross section, connecting the two concentric ferrules at their ends, with the integral part of the outer ferrule receiving securing means, which immobilize said support against rotation relative to the casing.

4,295,788


TURBINE WHEEL AND NOZZLE ARRANGEMENT
 Jules L. Dussourd, Princeton, and George W. Pfannebecker, Skillman, both of N.J., assignors to Terry Corporation, Windsor, Conn.

Filed Mar. 10, 1980, Ser. No. 129,038

Int. Cl.³ F01D 9/02

U.S. Cl. 415—202

2 Claims



1. An improved milled-bucket turbine wheel and nozzle arrangement, for a machine comprising:
 a milled-bucket turbine wheel mounted for rotation; and
 an energized-fluid-discharging nozzle mounted in adjacency to the periphery of said wheel, for discharging energized fluid onto said periphery; wherein
 said wheel has a plurality of substantially parallel, arcuate buckets formed in, and in traverse of, the periphery thereof; and
 said nozzle has a fluid-exit orifice opening onto, and in aligned registry with a given side portion or area of said periphery whereat there subsist lateral terminations of said buckets; wherein the improvement comprises:
 said buckets are substantially semicircular in cross-section, having a given radius; and
 said orifice has a width, measured along a plane traversing said wheel periphery, which is not less than approximately fifteen and one third percent, nor more than approximately eighteen and one fifth percent of twice said given radius.

4,295,789

COVER PLATES FOR TANK HEADS


Howard L. Gutzwiller, Zelienople, Pa., assignor to Robinson Industries, Inc., Zelienople, Pa.

Filed Aug. 9, 1979, Ser. No. 65,122

Int. Cl.³ F04D 29/18, 29/32

U.S. Cl. 416—213 A

4 Claims



1. An axial flow fan comprising:
 A. a hub having a central axis;
 B. an annular rim concentrically positioned and spaced from the hub;
 C. a disc extending normal to the central axis substantially midway of the hub and connecting the hub to the rim said disc being a structural member providing the primary structural support for the rim;
 D. a plurality of blades, each blade extending outward from the rim and angularly disposed thereto to form a leading and trailing edge;
 E. first and second reinforcement plates extending radially

outward in opposite directions and spaced from and along the central axis, said plates welded to the hub, disc and rim, said first plate extending subjacent the leading edge of each blade and said second plate extending subjacent the trailing edge; and

F. a pair of nonstructural disc-shaped cover plates, each plate welded to the hub and to a terminal edge of the annular rim, wherein said nonstructural cover plates protect structural members, is sacrificial in relation thereto and is accessible and refurbishable in the field.

4,295,790


BLADE STRUCTURE FOR USE IN A WINDMILL
Walter S. Eggert, Jr., Huntington Valley, Pa., assignor to The Budd Company, Troy, Mich.

Filed Jun. 21, 1979, Ser. No. 50,687

Int. Cl.³ F03D 1/06; B64C 11/26

U.S. Cl. 416-226

10 Claims



1. A tapered blade structure for use in a windmill including a spar assembly extending the full length of said blade structure and twisted along its length to a predetermined angle and having leading and trailing edge assemblies attached thereto comprising:

- (a) top and bottom spaced flat tapered elongated longitudinally extending metal sheets,
- (b) a pair of tapered angle metal strip elements secured to each of said extending sheets along opposite longitudinal edges thereof,
- (c) a plurality of relatively short pairs of flat metal shear web channels secured to said angle strip elements between said top and bottom sheets along the length of said sheets,
- (d) said tapered angle strip elements extending from the inner end of said blade structure towards the tip of said blade structure more than one-half and less than the length of said blade structure,
- (e) said metal sheets, tapered strip elements, and web channels forming a said spar assembly having a substantially rectangular cross-section,
- (f) a fitting secured to the ends of said sheets and said shear web channels,
- (g) a leading edge assembly secured to one side of said spar assembly extending outwardly from one of said pairs of flat metal shear web channels,
- (h) said leading edge assembly including an outer fiberglass plastic sheet having edge portions extending partly over said top and bottom flat tapered metal sheets,
- (i) a reinforcing plate bonded to said fiberglass plastic sheet to prevent impact damage,
- (j) a trailing edge assembly secured to the side opposite said one side of said spar assembly extending outwardly from the other of said pairs of flat metal shear web channels, and
- (k) said trailing edge assembly including top and bottom fiberglass sheets each having edge portions extending partly over said top and bottom flat tapered metal sheets to join the edge portions of said outer fiberglass plastic sheet of said leading edge assembly.

4,295,791

SCALLOPED CERAMIC TURBINE


Jesse F. Johnson, St. Clair Shores, Mich., assignor to General Motors Corporation, Detroit, Mich.

Filed Aug. 20, 1979, Ser. No. 67,797

Int. Cl.³ F01D 5/14, 5/28

U.S. Cl. 416-241 B

1 Claim



1. A unitary ceramic gas turbine wheel comprising: a hub with a radially extending disc thereon, a wheel rim having a plurality of spaced, fore face segments and an aft face, a neck integrally joining said wheel rim to said disc, a plurality of blades with roots integrally joined to said rim at the outer surface thereof, each of said blades having a leading edge and a trailing edge, concave convex airfoil surfaces joining said leading and trailing edges, said wheel rim having an axial length less than that of said blade roots, each of said blades having its leading edge located upstream of said fore faces and being joined to said neck and fore faces by a faired root region, said faired root regions and said fore faces on said rim forming scallops in said wheel between each of said leading edges to reduce differential thermal expansion strain at the leading edges to prevent excessive thermal stress concentrations in said blades and wherein said scallops further are configured to reduce the polar movement of inertia of said turbine wheel to improve the acceleration characteristics thereof.

4,295,792

APPARATUS FOR CONTROLLING OPERATION OF FLUID PRESSURE RAISING SYSTEM

Keiji Tachibana, Tokyo; Yoshihiko Nakayama, Shimoinayoshi; Junichi Kaneko, Amimachi, and Susumu Ishii, Tsuchiura, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed Aug. 29, 1978, Ser. No. 937,806

Claims priority, application Japan, Sep. 9, 1977, 52-107830

Int. Cl.³ F04B 49/00; F16D 25/063

U.S. Cl. 417-15

25 Claims



1. An apparatus for controlling the operation of a fluid pressure raising system including at least a motor having a constant rotational speed and a centrifugal fluid machine connected to said motor, said centrifugal fluid machine including a casing provided with a suction passage and a discharge passage, inlet guide vanes disposed in said suction passage, an impeller shaft connected to said motor and rotatably mounted in said casing and at least one impeller carried by said impeller

shaft, so that a fluid may be sucked through said suction passage and pressurized by said impeller as said impeller is driven by said motor and then discharged through said discharge passage, said apparatus comprising:

- an overdrive gear having a variable overdrive ratio and disposed between said motor and said centrifugal fluid machine, said overdrive gear including a gear box, a driven shaft connected to said impeller shaft of said centrifugal fluid machine and rotatably carried by said gear box, at least two pinions having different numbers of gear teeth and carried by said driven shaft, a drive shaft extending substantially in parallel with said driven shaft and rotatably carried by said gear box, said drive shaft being connected to said motor, gears rotatably carried by said drive shaft and adapted to engage their respective corresponding pinions, and clutch means adapted to connect selected one of said gears to said drive shaft, whereby said driven shaft is rotated at least at two overdrive ratios of a set overdrive ratio and a low overdrive ratio;
 - detecting means for detecting a condition of said fluid pressure raising system to produce a signal representative of said condition; and
 - an actuator for actuating said clutch means in response to said signal delivered by said detecting means,
- said fluid pressure raising system further includes a condenser having an inlet communicating said discharge passage and an outlet, and an evaporator having an inlet communicating said outlet of said condenser and an outlet communicating said suction passage, and wherein said detecting means detects the pressure at said inlet of said condenser.

4,295,793


FLUID SENSITIVE SWITCHING CONTROLLER
James D. McGalliard, 11171 Fenwick Pl., Santa Ana, Calif. 92705

Filed Nov. 6, 1978, Ser. No. 958,143

Int. Cl.³ F04B 49/06

U.S. Cl. 417-36

2 Claims



1. A device for controlling the level of fluid in a container comprising:
 - a first fluid probe;
 - a second fluid probe;
 - a unitary light source;
 - a unitary light sensor illuminated by said unitary light source;
 means for initiating illumination of said unitary light source when one of said probes contacts said fluid, regardless of the conductive state of said unitary light sensor; means responsive to said unitary light sensor for maintaining illumination of said unitary light source whenever said sensor is illuminated and the other of said probes contacts said fluid; and means for controlling the level of fluid in said container, said means being connected in series with said sensor.

4,295,794


SELECTIVE MODE MULTI-STAGE VACUUM PUMP
Robert L. Cain, Bryan, Ohio, assignor to Robinair Manufacturing Corporation, Montpelier, Ohio

Filed Jan. 22, 1979, Ser. No. 5,604

Int. Cl.³ F04B 23/04

U.S. Cl. 417-62

2 Claims



1. In a rotary vacuum pump having a pair of pump casings each having a pumping chamber defined therein housing a rotary displacer, an electric motor in driving connection with said displacers, an inlet defined in each of said casings in communication with the associated chamber, an oil reservoir defined in each of said casings above the associated chamber, an outlet passage interconnecting the chamber and reservoir of a common casing, a single head superimposed upon said casings enclosing the reservoirs thereof, the improvement comprising a cross-over conduit mounted upon one of said pump casings within the oil reservoir thereof having a first end communicating with the outlet passage of said one casing and a second end communicating with a cross-over passage defined in said head, said conduit including sealing means adjacent said ends, said cross-over passage communicating with the inlet of the other pump casing whereby said cross-over conduit and passage establish a series interconnection between the pumping chambers of said casings, and an outlet port defined in said head in communication with said oil reservoir of said other casing.

4,295,795

METHOD FOR FORMING REMOTELY ACTUATED GAS LIFT SYSTEMS AND BALANCED VALVE SYSTEMS MADE THEREBY

John C. Gass, Wichita, Kans.; Noell C. Kerr, Liberty, and Robert W. Pittmann, Sugarland, both of Tex., assignors to Texaco Inc., White Plains, N.Y.

Continuation-in-part of Ser. No. 889,470, Mar. 23, 1978, abandoned. This application Jun. 11, 1979, Ser. No. 47,657


Int. Cl.³ F04F 1/20; F16K 31/08

U.S. Cl. 417-111

5 Claims

1. A remotely actuated gas lift system for improved efficiency in lifting oil in a production tube internally of a well casing comprising,
 - (a) remote valve control means at the surface,
 - (b) valve means having a magnetic core in the well responsive to said remote valve control means for being opened to eject casing fluid through a passage into the production tube for lifting the oil in the production tube and for being closed for stopping flow of casing fluid into the production tube,
 - (c) said valve means has means for equalizing the casing fluid pressure on both ends of said magnetic core for reducing resistance to movement and providing a balanced valve means requiring a minimum of energy for operation thereof, and
 - (d) said means for equalizing said casing fluid pressure on

both ends of said magnetic core comprising casing fluid passage means extending completely through said mag-



netic core for the length thereof for circulating casing fluids freely to both ends thereof.

4,295,796

GAS LIFT APPARATUS


Howard H. Moore, Houston, Tex., assignor to McMurtry-Hughes, Inc., Huntsville, Tex.

Filed Jun. 29, 1979, Ser. No. 53,302

Int. Cl.³ F04F 1/20

U.S. Cl. 417-115

18 Claims



13. A gas lift valve assembly including a valve body having central longitudinal bore means, said valve body having a first lateral opening therethrough from said bore means, a second lateral opening therethrough from said bore means and longitudinally spaced from said first lateral opening, and a third lateral opening therethrough from said bore means disposed longitudinally between but spaced from said first and second lateral openings;

a first valve element movably mounted on said valve body for opening and closing said bore means between said first and third lateral openings; and a second valve element movably mounted on said valve body for opening and closing said bore means between said second and third lateral openings.

4,295,797

FUEL SUPPLY PUMP

Karl Ruhl, Gerlingen, and Ulrich Kemmer, Sachsenheim, both of Fed. Rep. of Germany, assignors to Robert Bosch GmbH, Stuttgart, Fed. Rep. of Germany


Continuation of Ser. No. 932,388, Aug. 9, 1978, abandoned. This application Dec. 14, 1979, Ser. No. 103,775

Claims priority, application Fed. Rep. of Germany, Oct. 12, 1977, 2745818

Int. Cl.³ F02M 37/08; F04B 23/14, 17/00

U.S. Cl. 417-203

13 Claims



1. In a fuel supply pumping system arranged together with a driving electromotor in a common housing, said system including a first pumping stage, a second pumping stage, a first rotary coupling connection between said first and second pumping stages, and a second rotary coupling connection between said electromotor and one of said pumping stages, the improvement wherein said first rotary coupling includes oppositely extending hub portions, each hub portion being provided with a permanent magnet element, said permanent magnet elements together forming a magnetic coupling.

4,295,798

AUTOMATIC TWO-SPEED PUMP ASSEMBLY


Arthur M. McIntosh, Arlington Heights, Ill., assignor to Borg-Warner Corporation, Chicago, Ill.

Filed Oct. 1, 1979, Ser. No. 80,767

Int. Cl.³ F04B 35/00

U.S. Cl. 417-212

11 Claims



1. An automatic two-speed pump assembly comprising a transmission shiftable to first and second operating modes, said transmission including fluid operated means movable between first and second positions for respectively shifting said transmission to said first and second modes, and means biasing said fluid operated means toward its first position; a pump engaged with said transmission so as to be driven thereby; and means operative in response to pump pressure for controlling the shift of said transmission from said first to said second mode at a first pump pressure and from said second to said first mode at a second pump pressure, said controlling means including valve means movable between first and second positions, said valve means in its first position communicating said fluid operated means with a fluid reservoir such that said fluid operated means is moved to its first position by said biasing means, and

said valve means in its second position communicating said pump with said fluid operated means such that said fluid operated means is moved to its second position in opposition to said biasing means, said controlling means also including resilient means biasing said valve means toward its first position, said valve means defining a relatively small surface area subject to pump pressure when in its first position and a relatively large surface area subject to pump pressure when in its second position such that said valve means is movable from its first to its second position by a relatively high pump pressure and from its second to its first position by said resilient means in opposition to a relatively low pump pressure.

4,295,799

SONIC PRESSURE WAVE SURFACE OPERATED PUMP


Arthur P. Bentley, P.O. Box 1952, Roswell, N. Mex. 88201

Filed Nov. 8, 1978, Ser. No. 958,552

Int. Cl.³ F04B 47/12

U.S. Cl. 417-240

18 Claims



1. A sonic pressure wave surface operated single tube pump for pumping liquid from an underground level to a ground surface comprising:

(a) a sonic pressure wave generator including,

I. a vertical cylinder having a bore for containing liquid in the lower portion thereof and having a port extending laterally from that bore,

II. a piston reciprocal in the bore of said cylinder for opening and closing the port thereof and for reciprocally impacting the liquid contained therein,

III. said piston having a liquid impacting end face with a central recess formed therein which generates a sonic pressure wave upon impacting the liquid contained therein,

IV. a sonic nozzle located in the lower portion of the bore of said vertical cylinder;

(b) a power operated drive means coupled to said piston for reciprocal driving thereof;

(c) a metallic tube having one of its ends coupled to the lower end of said cylinder, said tube having a bore formed therethrough for containing liquid with that bore in communication with the bore of said cylinder for receiving and transmitting the sonic pressure waves upon generation in said cylinder; and

(d) pumping mechanism means connected to the other end of said tube and in communication with the liquid to be pumped, said pumping mechanism means including a reciprocally operable plunger for impingingly receiving the sonic pressure waves when transmitted by said tube and reflecting those waves into a centrally and upwardly moving column.

4,295,800

ENERGY CONVERTOR

Bernard A. Packer, 328 Duthie Ave., Rockhampton North, Queensland, 4701, Australia


Filed Sep. 4, 1979, Ser. No. 72,162

Claims priority, application Australia, Sep. 7, 1978, PD5859; Nov. 10, 1978, PD6730; Mar. 9, 1979, PD7983

Int. Cl.³ F04B 17/00

U.S. Cl. 417-333

4 Claims



1. In an energy conversion device of the type including: a support frame; a carriage member which is movable in an upward or downward direction relative to the support frame; track means associated with said carriage member whereby the track means is orientated at an angle relative to the horizontal so as to define a downward location and an upward location, said track means being curved towards the upward location from the downward location, the radius of curvature decreasing from the downward location to the upward location; and a float member movable on said track means from said downward location to said upward location due to pressure from ocean waves or swells whereby energy generated by movement of said float member may be converted to mechanical or other forms of energy; the improvement comprising: a pump means pivotally mounted on said carriage member, and linkage means pivotally attached to said pump means and to said float member.

4,295,801

FLUID-POWERED SUBMERSIBLE SAMPLING PUMP

Robert W. Bennett, 5116 Bonham, Amarillo, Tex. 79110

Filed Jul. 31, 1979, Ser. No. 62,364

Int. Cl.³ F04B 47/08

U.S. Cl. 417-397

25 Claims



1. A fluid-powered sampling pump system comprising: a tube bundle reel assembly; a tube bundle reeled upon said reel assembly and including: a fluid sample tubing;

a power fluid charging tubing; and an exhaust power fluid tubing;

a pump connected to one end of said tube bundle for lowering into the earth, said pump comprising:

a hollow cylindrical upper motor piston chamber defining an axially extending fluid passageway in the wall thereof for receiving pressurized power fluid from said power fluid charging tubing, and further defining an axially extending fluid passageway in the wall thereof for delivering exhaust power fluid to said exhaust power fluid tubing;

an upper motor piston in said upper motor piston chamber;

a hollow cylindrical lower motor piston chamber;

means detachably interconnecting said upper and lower motor piston chambers and positioned therebetween to facilitate independent removal of said motor piston chambers from the pump;

a lower motor piston in said lower motor piston chamber;

means interconnecting said upper and lower motor pistons for concurrent movement within their respective piston chambers;

a lower pump piston chamber connected to said lower motor piston chamber;

an upper pump piston chamber connected to said upper motor piston chamber;

an upper pump piston connected to said upper pump piston and having a portion positioned in said upper pump piston chamber for reciprocation therein during the concurrent reciprocation of said upper motor piston;

a lower pump piston having a portion positioned in said lower pump piston chamber and connected to said lower motor piston for reciprocation in said lower pump piston chamber when said lower motor piston undergoes reciprocation;

a lower pump valve subassembly connected to said lower pump piston chamber and including an intake valve and a discharge valve;

an upper pump valve subassembly connected to said upper pump piston chamber and including an intake valve and a discharge valve;

manifold tubing means commonly interconnecting said discharge valves to said fluid sample tubing of said tube bundle;

a pilot valve subassembly interposed between said upper and lower motor piston chambers and detachably mounted on said means interconnecting said upper and lower motor piston chambers;

a distribution valve subassembly interposed between said upper motor piston chamber and said lower motor piston chamber and detachably mounted on said means interconnecting said upper and lower motor piston chambers, said distribution valve subassembly being operatively connected to said pilot valve subassembly and to said motor pistons to respond to shifting movement of said pilot valve subassembly during operation of the pump, and to distribute power fluid to said motor pistons; and

means interconnecting said pilot valve subassembly and said distribution valve subassembly with said axial fluid passageways in said upper motor piston chamber.

4,295,802

VAPOR CONTROL SYSTEM

Norman Peschke, Kentwood, Mich., assignor to Dover Corporation, Grand Rapids, Mich.

Filed Jul. 2, 1979, Ser. No. 53,808

Int. Cl.³ F04B 17/00

U.S. Cl. 417—405

7 Claims

1. In an apparatus for withdrawing vapors from the zone adjacent the fill opening of a fuel tank, said apparatus having a motor-pump unit for association with a fuel conducting conduit and a vapor conducting conduit, the improvement comprising:


a central component defining a central housing having first

and second enlarged end walls which face in opposite directions and are substantially parallel, said central housing being bounded by peripheral sidewall means;

said central housing having a fuel inlet port connectible to the fuel conduit and communicating with a first fuel passage which extends interiorly of the central housing and terminates in a first opening formed in said first end wall, and a fuel discharge port connectible to the fuel conduit and communicating with a second fuel passage which extends interiorly of said central housing and terminates in a second opening formed in said first end wall;

said central housing also including a vapor inlet port connectible to the vapor conduit and communicating with a first vapor passage which extends interiorly of said central housing and terminates in a third opening formed in said second end wall, and a vapor discharge port connectible to the vapor conduit and communicating with a second vapor passage which extends interiorly of said central housing and terminates in a fourth opening formed in said second end wall;

elongate shaft means rotatably supported on said central housing so that the rotational axis of said shaft means is substantially perpendicular to said first and second end walls, said shaft means having first and second end portions which respectively project outwardly beyond said first and second end walls;



a motor component connectible into the fuel-flow path for rotating or stopping as the fuel flows or stops flowing, respectively;

said motor component including a motor housing removably but fixedly attached to said central housing directly adjacent said first end wall, said motor housing having an elliptical central cavity, and a vane-carrying rotor rotatably mounted within said cavity and nonrotatably secured to the first end portion of said shaft means, said first and second openings respectively communicating with high and low pressure zones of said cavity adjacent said rotor;

a pump component drivingly connected for rotation with said motor component and introducible into the vapor flow path for creating a vapor withdrawing suction in said vapor conduit simultaneous with the flow of fuel in the fuel conduit;

said pump component comprising a pump housing removably and fixedly secured to said central housing adjacent said second end wall, said pump housing defining an elliptical central cavity, and a vane-carrying rotor rotatably mounted within said cavity, and nonrotatably secured to the second end portion of said shaft means, said third and fourth openings respectively communicating with low and high pressure zones within said pump cavity.

4,295,803

SEPARATING MACHINE

Ulrich Barthelmeß, Niederstotzingen, Fed. Rep. of Germany, assignor to Omya GmbH, Cologne, Fed. Rep. of Germany


Filed Jun. 1, 1979, Ser. No. 44,623

Claims priority, application Fed. Rep. of Germany, Jun. 9, 1978, 2825400

Int. Cl.³ F04B 17/00, 35/04

U.S. Cl. 417—423 R

10 Claims



1. A flow machine for separating particles in a flowable medium, the machine having a rotor rotatably mounted in a housing, said rotor comprising two face rings spaced apart in the axial direction of the rotor and a plurality of blades extending axially therebetween, said rings being supported for rotation about their outer circumferences in the housing and at least one of the rings being driven, and an inlet and an outlet in the housing for flowable medium, said flowable medium being drawn through the flow machine so that it flows axially through the rotor and traverses the blades substantially radially as it flows between the inlet and the outlet effecting a separation of particles in the flowable medium.

4,295,804

INTERMEDIATELY COOLED AIR VACUUM PUMP WITH BALANCING OF THE PRESSURES

Adriano Pezzot, Via Udine, 8, 33094 Cordenons (Pordenone), Italy


Filed Jul. 5, 1979, Ser. No. 54,842

Claims priority, application Italy, Nov. 7, 1978, 83499 A/78

Int. Cl.³ F04C 18/00, 29/04

U.S. Cl. 418—15

1 Claim



1. An improved pump apparatus of the type having a stator body with an internal chamber for suction and compression, an input port, an output port, an eccentrically mounted rotor located within the chamber, the rotor including a plurality of radial lamellae mounted thereon, the lamellae adapted to make contact with the inside of the chamber through the influence

of centrifugal force, and passageway means for venting the chamber at the location where the chamber formed by adjacent lamellae has its largest volume, wherein the improvement comprises:

- the passageway means is positioned such that a first arc between the passageway means and the output port is as long as an arc between points at which adjacent lamellae contact the inside of the chamber including the thickness of one lamella;
- the output port subtends an angle as large as the arc between the points at which adjacent lamellae contact the inside of the chamber;
- the input port is positioned such that a second arc from the output port to the input port is as long as the arc between the points at which adjacent lamellae contact the inside of the chamber;
- the input port subtends an angle smaller than the arc between the points at which adjacent lamellae contact the inside of the chamber; and
- the passageway is positioned such that a third arc between the passageway and the input port is as long as the arc between the points at which adjacent lamellae contact the inside of the chamber, including the thickness of one lamella,

whereby, as each succeeding chamber volume is swept past the passageway means and on toward the output port, there occurs no significant compression of fluid enclosed within such chamber.

4,295,805

HYDRAULIC ROTARY TOOTHED PISTON ENGINE WITH FLOW THROUGH THE TOOTHED GAPS

Karl-Heinz Liebert, Schwabisch Gmund, Fed. Rep. of Germany, assignor to Zahnradfabrik Friedrichshafen, AG., Friedrichshafen, Fed. Rep. of Germany


Filed Oct. 12, 1979, Ser. No. 84,183

Claims priority, application Fed. Rep. of Germany, Oct. 20, 1978, 2845648

Int. Cl.³ F03C 2/08; F04C 2/10, 15/02

U.S. Cl. 418—61 B

4 Claims



1. In a combined fluid displacing device (8) and control valve assembly having a radially outer ring gear (14) provided with internal teeth spaced from each other by gaps in fluid communication with fluid displacing pockets formed between said ring gear and an inner member (20), valve means a valve housing therefor (2) within which axial flow passages (24) are formed, a fixed spacer (22) positioned axially between the ring gear and the housing and elongated assembly fasteners (10) extending through the ring gear and the spacer into the valve housing through the axial flow passages therein, the improve-


ment residing in said ring gear being formed with radial extensions (28) of said gaps between the internal teeth receiving the fasteners therethrough with flow clearance in substantial axial alignment with the axial flow passages in the valve housing, said spacer being formed with axial flow openings (32) through which the fasteners extend with partial radial clearance to conduct axial flow between the radial gap extensions and the axial flow passages in the housing without directional change with the fluid flow being into and out of said fluid displacing pockets through said gaps, radial gap extensions, openings, axial flow passages and valve means.

4,295,806

ROTARY COMPRESSOR WITH WIRE GAUZE LUBRICANT SEPARATOR

Naoki Tanaka, Amagasaki; Kunihiro Tsuchiya, and Toshizo Nishizawa, both of Shizuoka, all of Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan
Filed Apr. 27, 1979, Ser. No. 34,009


Claims priority, application Japan, May 26, 1978, 53/63088; Dec. 29, 1978, 53/179398[U]
Int. Cl.³ F04C 29/02; B01D 50/00
U.S. Cl. 418—97



1. A rotary compressor comprising: a horizontal cylindrical shell having a lubricant sump disposed at the bottom thereof; a compressor unit mounted within said shell for compressing a gaseous refrigerant, the size of the compressor unit being less than the size of the interior of said shell for leaving a space within said shell; a delivery tube connected to the main body of said compressor unit to deliver the compressed gaseous refrigerant to said space; a discharge tube connected to said shell to discharge the compressed refrigerant from said space to the exterior of said shell; a wire gauze positioned in said space within said shell perpendicular to the longitudinal axis of said shell and extending fully across said space within said shell to a level below the level of lubricant in said sump, thereby dividing said space into a first space containing said compressor unit and a second space, for separating lubricant from the compressed refrigerant and for directing said separated lubricant back to said lubricant sump; and means in said first space for blocking passage of refrigerant between said compressor unit and said shell for dividing the first space into two portions, said delivery tube opening into one of said space portions and said discharge tube opening out of the other space portion, whereby compressed refrigerant is delivered from said delivery tube to said one space portion, passes through the wire gauze to the second space, and then again passes through the wire gauze to said other space portion and said discharge tube

4,295,807
INTERNAL COMBUSTION ENGINE WITH OIL PUMP GEAR SURROUNDING AND DRIVEN BY CRANKSHAFT
Hermann Krüger, Wolfsburg, Fed. Rep. of Germany, assignor to Volkswagenwerk Aktiengesellschaft, Wolfsburg, Fed. Rep. of Germany

Filed Jul. 20, 1979, Ser. No. 59,475
Claims priority, application Fed. Rep. of Germany, Aug. 23, 1978, 2836766
Int. Cl.³ F04C 2/10; F04B 17/00; F01M 1/02
U.S. Cl. 418—170



1. In an internal combustion engine having a crankshaft mounted for rotation on at least one main crankshaft bearing and having a gear oil pump directly driven by said crankshaft and including at least one gear surrounding said crankshaft and rotationally driven by said crankshaft, the improvement wherein said gear also surrounds said main bearing and forms an operative gear of said pump whereby said bearing and said oil pump occupy common axial space on said crankshaft.

4,295,808

APPARATUS FOR THE PRODUCTION OF HIGH-PURITY METAL POWDER BY MEANS OF ELECTRON BEAM HEATING


Herbert Stephan, Bruchköbel; Hans Aichert, Hanau am Main, and Joseph Heimerl, Altenhässlau, all of Fed. Rep. of Germany, assignors to Leybold-Heraeus GmbH & Co. KG, Cologne, Fed. Rep. of Germany

Division of Ser. No. 902,475, May 7, 1978, Pat. No. 4,218,410, which is a continuation of Ser. No. 697,283, Jun. 17, 1976, abandoned. This application Oct. 15, 1979, Ser. No. 85,155
Claims priority, application Fed. Rep. of Germany, Jun. 28, 1975, 2528999

Int. Cl.³ B22F 9/00

U.S. Cl. 425—8

12 Claims



1. An apparatus for making high-purity metal powder from high purity metal while maintaining the initial high purity of the starting material, comprising:
a. a circular plate having a given diameter and a circumferential marginal area and means for rotating same at a high

speed about a vertical axis of rotation corresponding to the center of the plate;
b. means for electron beam melting high purity metal starting material in rod form in vacuo into molten metal droplets directed onto the circular plate;
c. means for producing an electron beam focusable to a given focal spot on the plate and for focusing the focal spot such that its diameter is many times smaller than the given diameter of the plate and deflecting the beam between the rotational center of the spinning plate and the marginal area to effect the scanning of the plate in a zone that extends radially of the axis of rotation of the plate to said marginal area when the plate is spinning to direct the molten metal droplets by centrifugal force from the plate when it is spinning in a controlled manner within a fixed narrow angular portion of the circumference of the spinning plate to define a fixed narrow angular range of flight paths of the molten metal droplets leaving the plate; and
d. means for collecting the metal particles formed from the droplets undergoing cooling and solidification due to loss of heat due to radiation during flight to form the metal powder.

4,295,809

DIE FOR A MELT BLOWING PROCESS


Takashi Mikami; Shigeo Fujii; Shuji Okano, and Tokuzo Ikeda, all of Ooi, Japan, assignors to Toa Nenryo Kogyo Kabushiki Kaisha, Tokyo, Japan

Filed Sep. 14, 1979, Ser. No. 75,816

Int. Cl.³ D01D 3/00

U.S. Cl. 425—72 S

16 Claims



1. An extrusion die assembly for a melt blowing process with a nose piece having a triangular cross-section and extrusion holes along the apex thereof, for extrusion of melted thermoplastic resin, said assembly having gas lips defining gas slots at either side of the apex and having movable spacers provided in the gas slots said spacers contacting said nose piece and said gas lips for determination of the gap of the gas slots.

4,295,810

APPARATUS FOR INSULATING BUILDING BLOCKS
Heinz Dennert, Bischberg, and Hans V. Dennert, Schlüsselfeld, both of Fed. Rep. of Germany, assignors to Veit Dennert KG Baustoffbetriebe, Schlüsselfeld, Fed. Rep. of Germany

Filed Jun. 5, 1979, Ser. No. 45,732

Claims priority, application Fed. Rep. of Germany, Jun. 10, 1978, 2825508


Int. Cl.³ B29C 27/30; B29D 27/00

U.S. Cl. 425—110

11 Claims

1. Apparatus for producing building blocks comprising conveying means for transporting building blocks each having at least one hollow chamber therein,
a filling station for filling the chambers of said building blocks with particles of preformed thermoplastic synthetic material,
a fusing station for fusing the surfaces of said particles of thermoplastic synthetic material together, and
synchronizing means for controlling the movements of said

conveying means, filling station and fusing station to fill the chambers of said building blocks with said particles of



thermoplastic synthetic material and then fuse said particles together.

4,295,811

APPARATUS FOR MAKING MULTILAYERED CONTAINERS


Donald G. Sauer, Harwinton, Conn., assignor to National Can Corporation, Chicago, Ill.

Continuation-in-part of Ser. No. 608,177, Aug. 27, 1975, which is a division of Ser. No. 448,191, Mar. 5, 1974, abandoned. This application Jul. 19, 1979, Ser. No. 58,781

Int. Cl.³ B29C 17/07

U.S. Cl. 425—112

5 Claims



1. In apparatus for forming a hollow multilayered thermoplastic article using a normally closed blow slot equipped core rod having a porous metal section incorporated into a forward outer surface portion thereof and wherein an internal fluid passageway longitudinally extends from a rear portion of said core rod to each of said blow slot and said porous metal section, said apparatus additionally including liner loading station means for loading a liner over said core rod, injection mold station means for forming a parison over said liner on said core rod to form a multilayered preform, blow mold station means for blow molding said preform on said core rod to form a blown article, blown article removal station means for removing said blown article from said core rod, core rod transfer means including rotary means and coaxial stationary means for relatively moving said core rod between said liner loading station means, said injection mold station means, said blow mold station means and said removal station means, and control means for operating said core rod transfer means, said liner loading station means, said injection mold station means, said blow mold station means, and said blown article removal station means for producing a hollow multilayered thermoplastic article by injection blow molding, the improvement which comprises:

- (A) means for opening and then closing said blow slot when said core rod is located functionally adjacent said blow station means;
- (B) first detachable connection means, located at said liner loading station means, for connecting said internal fluid passageway with a vacuum source;
- (C) second detachable connection means located at said blow mold station means for connecting said internal fluid passageway with a pressurized fluid source;
- (D) means to effectuate connection between said first detachable connection means and said internal passageway when said rotary means has moved said core rods into position at said liner loading station and between said second detachable connection means and said internal passageway when said rotary means has moved said core rods into position at said blow mold station means; and
- (E) valve means associated with said rotary means for closing said internal fluid passageway to maintain a vacuum in said liner loaded core rod during the period when (a) said internal fluid passageway is detached from said first detachable connection means, (b) said rotary means is advanced first to said injection mold station means and then to said blow mold station means, and (c) said second detachable connection means is so connected with said internal fluid passageway.

4,295,812

RIBBON CABLE EXTRUSION CROSSHEAD


David C. Hoddinott, Preston, Conn., assignor to Crompton & Knowles Corporation, New York, N.Y.

Filed Jun. 18, 1980, Ser. No. 160,416

Int. Cl.³ B29F 3/10

U.S. Cl. 425—114

8 Claims



1. An extrusion crosshead for encapsulating a sheet of parallel co-planar conductor wires with plastic insulating material, said extrusion head comprising:

- (a) an extrusion die having a plurality of interconnected extrusion passages dimensioned to accommodate the sheet of conductor wires, each extrusion passage having an inlet opening to receive a conductor wire;
- (b) a guide-block having a plurality of holes axially aligned with the die passages for receiving the wires and guiding the wires to the die;
- (c) an inlet bore for receiving plasticized insulating material from an extruder, the longitudinal axis of said bore being at an angle to the longitudinal axes of the extrusion passages extending through the die;
- (d) an elongated top distribution channel extending above the full width of said sheet and having a longitudinal axis that is transverse to the longitudinal axes of the extrusion passages, said top distribution channel having an inlet

opening at one end and an elongated outlet opening that extends at a downward angle from the inlet opening to the opposite end of the top distribution channel, the cross-sectional area of said top distribution channel gradually diminishing from the inlet opening to the opposite end thereof;

- (e) an elongated bottom distribution channel extending below the full width of said sheet and having a longitudinal axis that is transverse to the longitudinal axes of the extrusion passages, said bottom distribution channel having an inlet opening at one end and an elongated outlet opening that extends at an upward angle from the inlet opening to the opposite end of the bottom distribution channel, the cross-sectional area of the bottom distribution channel gradually diminishing from the inlet opening to the opposite end thereof;
- (f) an upper flow channel located above the full width of said sheet and having an inlet opening and an outlet opening that is connected to the inlet openings of the die passages;
- (g) a lower flow channel located below the full width of said sheet and having an inlet opening and an outlet opening that is connected to the inlet openings of the die passages;
- (h) a top feed bore connecting the inlet bore to the inlet opening of the top distribution channel;
- (i) a bottom feed bore connecting the inlet bore to the inlet opening of the bottom distribution channel;
- (j) a top flow compensating passage connecting the outlet opening of the top distribution channel to the inlet opening of the upper flow channel; and
- (k) a bottom flow compensating passage connecting the outlet opening of the bottom distribution channel to the inlet opening of the lower flow channel.

4,295,813

APPARATUS FOR MOLDING STRAND-MOUNTED PLASTIC MEMBERS

Irving Levine, 23555 Park Belmonte, Calabassas Park, Calif.


Filed Oct. 1, 1973, Ser. No. 401,979

The portion of the term of this patent subsequent to Oct. 20, 1994, has been disclaimed.

Int. Cl.³ B29F 1/00

U.S. Cl. 425—121

5 Claims



4. An apparatus for simultaneously fabricating a plurality of thermoplastic elements on a supporting string comprising:

- (a) a first plate having a first insert, said insert comprising a plurality of parallel pairs of element fabricating members, each pair of element fabricating members including a plurality of aligned element cavities, each element cavity being in communication with an adjacent element cavity by a supporting string channel, all of said support string channels being in alignment with one another, and being adapted to receive the supporting string therein whereby each of said cavities is sealed, a thermoplastic runner channel parallel to and intermediate the support string channels of the pair of element fabricating members, a plurality of thermoplastic subrunner channels depending from and communicating with said thermoplastic runner

4,295,815

GUIDE SKIRT


Frank Eltveld, 5 Lake Dr., Lake In The Hills, Ill. 60102

Filed Jul. 21, 1980, Ser. No. 170,847

Int. Cl.³ B29F 1/14

U.S. Cl. 425—556

18 Claims



1. Apparatus for producing parts and for ejecting said parts from an ejection location, comprising receptacle means mounted below said ejection location, and a generally tubular, limp flexible skirt mounted to said apparatus with a top opening disposed below and in proximity to said ejection location and with a bottom opening opening into said receptacle.

4,295,816

CATALYST DELIVERY SYSTEM

B. Joel Robinson, 501 Boylston St., Brookline, Mass. 02146


Continuation of Ser. No. 862,411, Dec. 20, 1977, abandoned.

This application Jun. 27, 1980, Ser. No. 163,865

Int. Cl.³ F23J 7/00

U.S. Cl. 431—4

6 Claims



1. A system for the delivery of a catalyst containing not more than 9 mg of a platinum group metal per kg of fuel to a combustion system having an intake port for air comprising: means for dispensing said catalyst in a liquid; and means for passing a portion of said air via said liquid for absorbing said catalyst into said air.

4,295,817

METHOD AND MEANS FOR CONTROLLING THE OPERATION OF FLUIDIZED BED COMBUSTION APPARATUS

Peter B. Caplin, Sunbury-on-Thames, and Maurice Harman, Milton Keynes, both of England, assignors to The Energy Equipment Co. Ltd., Olney, England

Filed Jul. 31, 1979, Ser. No. 62,340

Claims priority, application United Kingdom, Aug. 4, 1978, 32214/78; Dec. 11, 1978, 48028/78

Int. Cl.³ F23D 19/02

U.S. Cl. 431—7

21 Claims

1. A fluidized bed combustion apparatus comprising means for supplying fuel to said fluidized bed, means for injecting combustion air into the fluidized bed of the apparatus to cause fluidisation of the bed material and to support combustion of

channels, and gating means for providing communication between said thermoplastic subrunner channels and said bead cavities;

- (b) a second plate having a second insert adapted to be forced adjacent said first insert, said second insert having element cavities, support string channels, thermoplastic runner channels and thermoplastic subrunner channels complementary to those disposed in said first insert, and including thermoplastic input means for receiving flowable thermoplastic material, said thermoplastic input means being disposed through said second plate and in communication with said thermoplastic runner channels;
- (c) a severing pin secured to said first plate and adapted to be slidably engaged through said second plate in communication with said thermoplastic input means, the terminus of said pin adjacent said thermoplastic input means depending into a first axial member having a predetermined diameter, said first axial member depending into a second axial member having a diameter which is larger than that of said first axial member whereby the thermoplastic disposed in the thermoplastic input means is fractured in the vicinity of said first and second axial members when the first and second plates are separated;
- (d) supply means for supplying a pressurized source of flowable thermoplastic, said supply means coupled to said thermoplastic input means;
- (e) support string supply means for supplying a source of support string for each of said plurality of element fabricating members; and
- (f) means for imposing opposing forces upon said first and second plates whereby the complementary bead cavities, support string channels, thermoplastic runner channels and thermoplastic subrunner channels of said first and second inserts are adjacent one another.

4,295,814

METHOD AND APPARATUS FOR PRODUCING AND ASSEMBLING ARTICLES OF MOLDED PLASTIC PARTS

Peretz Rosenberg, Moshav Beit Shearim, Israel


Filed Jun. 27, 1979, Ser. No. 52,504

Claims priority, application Israel, Feb. 28, 1979, 56761

Int. Cl.³ B29C 24/00


U.S. Cl. 425—517

6 Claims



1. Apparatus for producing articles constituted of at least two plastic parts, characterized in that the apparatus includes: a pair of mold plates one overlying the other; means for effecting relative movement between said pair of mold plates towards and away from each other to close and open them; each of said pair of mold plates including at least two forming surfaces defining, in one closed position of the plates during a molding stroke of the apparatus, at least two cavities having shapes corresponding to the parts of the article, with one plate of said pair adapted to retain one of the molded parts and the other plate of said pair adapted to retain the other part when the pair of plates are open, the two forming surfaces of each plate of said pair being laterally spaced from each other; and means for effecting relative movement between said pair of plates in the lateral direction to align the two parts retained thereby in the open position of the pair of plates, such that in a subsequent closing of the pair of plates during an assembling stroke of the apparatus, the part retained by one plate of said pair is applied to the part retained by the other plate of said pair.

fuel fed to the bed, means for measuring at least one of the temperature of the bed and the thermal demand placed upon the apparatus, means for augmenting said supply of combustion air, prior to its injection into the fluidised bed with waste



gas drawn from a waste gas outlet of the apparatus, said augmenting means being operable to enable the volume of waste gas mixed with the combustion air to be varied in dependence upon at least one of the temperature of the fluidised bed and the thermal demand placed on the apparatus.

4,295,818

CATALYTIC MONOLITH AND METHOD OF ITS FORMULATION

Meredith J. Angwin, Palo Alto, Calif.; William C. Pfeiffer, Middletown, N.J., and John P. Kesselring, Mountain View, Calif., assignors to United States of America, Washington, D.C.

Filed May 27, 1980, Ser. No. 153,056

Int. Cl.³ F23D 3/40; B01J 23/10, 23/74, 35/04

U.S. Cl. 431—7

9 Claims

1. A monolithic catalytic structure formed by the steps of homogeneously interspersing throughout a carrier structure of ceramic composition a base metal oxide which upon calcination becomes catalytically active, forming the ceramic composition interspersed with the oxide into the shape of a monolithic structure, and calcining the shaped structure with the interspersed metal oxide at a temperature of at least about 1,000° C.

4,295,819

GAS LIGHTER

Goro Sugiyama, No. 17-5, 5-chome, Toro, Shizuoka-shi, Shizuoka-ken, Japan


Filed Aug. 11, 1978, Ser. No. 932,960

Claims priority, application Japan, Aug. 12, 1977, 52-108314[U]; Mar. 31, 1978, 53-43218[U]

Int. Cl.³ F23Q 2/00

U.S. Cl. 431—143

2 Claims



1. A gas lighter comprising:

- (a) a body having a tooth-like support portion on an upper portion thereof and an ignition portion disposed on another upper portion thereof,
- (i) said ignition portion comprising a projecting cylinder having a slantly stepped portion on either side thereof and containing a recessed portion, a flint disposed in

said cylinder and partially projecting therefrom, and an ignition file,

- (b) a bomb filled in its interior with a gas-evolving liquid detachably secured to said body,
- (ii) said bomb being provided with a nozzle for discharging vaporized gas and a rotatably adjustable valve means communicating said interior with said nozzle, said nozzle being normally biased in a downward position whereby said valve means is closed,
- (c) a member adapted to engage said nozzle for raising the same to thereby open said valve,
- (iii) said member comprising a lever having a longitudinal hole on its intermediate portion and flanges on either side of said hole, said flanges being adapted to engage and recessed portions, said projecting cylinder thereby projecting through said hole, one end of said lever slidably engaging said nozzle, and
- (d) a flame-adjusting member comprising a rotatable tooth form portion fixed to said valve means and engaging said tooth-like support portion, whereby rotation of said bomb causes adjustment of said valve.

4,295,820

GAS BLENDING FLAME CUTTER

Georg Röeder, and Helmut Sachs, both of Frankfurt am Main, Fed. Rep. of Germany, assignors to Messer Griesheim GmbH, Frankfurt am Main, Fed. Rep. of Germany


Filed Mar. 29, 1979, Ser. No. 25,287

Claims priority, application Fed. Rep. of Germany, Apr. 29, 1978, 2819132

Int. Cl.³ H01M 6/18; F23Q 7/06

U.S. Cl. 431—191

8 Claims



1. A gas-mixture flame cutter comprising a cutting torch having a torch head, a cutting nozzle detachably engaged to said torch head, said cutting nozzle having an upstream end and a downstream end, a cutting oxygen channel extending through said torch head and through said cutting nozzle and terminating at said downstream end of said cutting nozzle, a plurality of spaced combustible mixture blend passages in said cutting nozzle and terminating at said downstream end of said cutting nozzle adjacent said cutting oxygen channel whereby said cutting oxygen channel and said blend passages are exposed at said downstream end of said cutting nozzle, heating oxygen passage means in said torch head communicating with said blend passages for supplying heating oxygen to said blend passages, fuel gas passage means in said torch head communicating with said blend passages for supplying fuel gas to said blend passages, one of said blend passages being an ignition blend passage, an ignition device being in flow communication with said ignition blend passage at said upstream end of said cutting nozzle, and the remaining blend passages being out of flow communication with said ignition device whereby actuation of said ignition device causes the combustible mixture in

said ignition blend passage to ignite and to be extinguished after igniting the combustible mixture exiting from said remaining blend passages with the ignited combustible mixture from said remaining blend passages then re-igniting the combustible mixture from said ignition blend passage.

4,295,821

APPARATUS FOR BURNING LIQUID FUEL

Siegfried Schilling, Volketswil, Switzerland, assignor to Oertli AG Dubendorf, Zurich, Switzerland


Filed Aug. 21, 1979, Ser. No. 68,404

Claims priority, application Fed. Rep. of Germany, Aug. 21, 1978, 2836534

Int. Cl.³ F23D 15/02

U.S. Cl. 431—353

5 Claims




1. A liquid fuel burner particularly suited for low rates of fuel combustion, comprising an atomizer nozzle having a mouth at its front from which liquid fuel issues as a spray that is mainly in the form of a forwardly divergent cone of droplets substantially coaxial with said nozzle, and a combustion air duct through which combustion air flows forward to be mixed and combusted with the sprayed fuel, said fuel burner being characterized by:

- A. an annular flame holder coaxial with the nozzle and spaced a small distance forward from it, having a central aperture through which substantially all of said spray passes;
- B. a duct-like fuel vaporizer defining a zone in which combustion takes place, said fuel vaporizer being substantially concentric to the nozzle, spaced a small distance forward from said flame holder and
 - (1) having a forwardly convergent inlet section,
 - (2) having a diffuser section which extends forwardly from said inlet section and which has an inner surface that diverges forwardly and is so spaced from the mouth of the nozzle that between about 20% and about 40% of said spray can impact the same,
 - (3) being of a material that conducts heat readily so as to be quickly heated by combustion in said zone to a temperature at which spray droplets impacting said surface are vaporized, and
 - (4) being supported by said combustion air duct in thermally insulated relation thereto; and
- C. said combustion air duct having a portion connected with the inlet section of the fuel vaporizer and coaxially surrounding the flame holder in radially spaced relation thereto to cooperate with the periphery of the flame holder in defining an annular passage, said portion of the combustion air duct thus constraining all combustion air from said combustion air duct to enter the inlet section of the fuel vaporizer, part of such air through said central aperture in the flame holder and the remainder through said annular passage.

4,295,822
PRODUCER GAS FUELED BURNER SYSTEM AND DRYING APPARATUS
Crom B. Campbell, 222 Glenview Dr., Des Moines, Iowa 50312
Filed Oct. 1, 1979, Ser. No. 80,207
Int. Cl.³ F24H 1/00

U.S. Cl. 432—29

38 Claims



1. In combination with a gas producer, said gas producer being suitable for generating a combustible producer gas from the combustion of organic materials, said combustible producer gas comprising a producer gas flow traveling through a portion of said organic materials, said producer gas flow including distillates which distill out of said organic materials and comprising a producer gas/distillate flow, said distillates have a condensation temperature, comprising:

- a burner means for combustion of said combustible producer gases externally disposed with respect to said gas producer; and
- a burner throat means for providing fluid communication with and disposed between said producer and said burner means, said burner throat means carrying said producer gas/distillate flow from said producer to said burner means, said burner throat means including a superheating means for superheating said producer gas/distillate flow to a superheated temperature, said superheated temperature being above said condensation temperature, said superheated producer gas/distillate flow having a temperature above said condensation temperature while flowing through said burner throat means.

4,295,823

APPARATUS FOR CONTINUOUSLY PRODUCING A CEMENT CLINKER

Tadashi Ogawa, Ichikawa; Shunichiro Ono, Musashino, and Kyoichi Shibuya, Narashino, all of Japan, assignors to Sumitomo Cement Co., Ltd., Tokyo, Japan


Filed Mar. 27, 1980, Ser. No. 134,461

Claims priority, application Japan, Apr. 3, 1979, 54-39337

Int. Cl.³ F27B 7/02

U.S. Cl. 432—106

9 Claims



1. An improved apparatus for continuously producing a cement clinker, comprising:

means for feeding a cement material;
 means for preheating or calcining said cement material, which means is located downstream from said feeding means and is provided with a preheating or calcining chamber therein;
 a rotary kiln for converting said cement material to a cement clinker, which kiln is located downstream from said preheating or calcining means, said kiln comprising a heating chamber connected to said preheating or calcining means; means for cooling said cement clinker with air, which means is located downstream from said rotary kiln and comprises a cooling chamber connected to said heating chamber and air-blowing means connected to a lower portion of said cooling chamber, and;
 means for flowing an exhaust gas from said heating chamber through said preheating or calcining chamber, which apparatus is characterized by means for heat-decomposing a combustible material, which means is located between said preheating or calcining means and said rotary kiln and which means is provided with a heat-decomposing chamber which is connected to means for feeding said combustible material so that said combustible material is allowed to be fed into said heat-decomposing chamber, which heat-decomposing chamber is connected to said heating chamber in said rotary kiln in such a manner that at least a portion of the exhaust gas from said heating chamber is allowed to flow into said heat-decomposing chamber and a solid residue produced from said combustible material in said heat-decomposing chamber is allowed to be introduced into said heating chamber, and which heat-decomposing chamber is connected to said pre-heating or calcining chamber so that a combustible gas generated from said combustible material in said heat-decomposing chamber is allowed to flow into said preheating or calcining chamber.

4,295,824

SYSTEM FOR SEALING OF KILNS

Johannes C. Wens, Nijmegen, Netherlands, assignor to Smit Ovens Nijmegen B.V., Nijmegen, Netherlands


Filed Oct. 17, 1979, Ser. No. 85,526

Claims priority, application Fed. Rep. of Germany, Oct. 25, 1978, 2846387

Int. Cl.³ F27B 7/24; F27D 1/18; F26B 25/00

U.S. Cl. 432—115

9 Claims



1. In a rotating furnace, an internal rotating means carrying parts subjected to heat and internal gases, an outer supporting stationary means supporting the inner rotating means, a sealing assembly means for limiting the leakage of gas and heat from said rotating means, said sealing assembly means comprising: at least one outer sealing sleeve positioned for sealing engagement between said rotating means and said stationary means, means for delivering a barrier gas under pressure to urge said sealing sleeve by pressure contact into said sealing engagement, and an intermediate bearing ring between said internal rotating means and said outer supporting means for absorbing the compression pressure forces therebetween and for acting as a spacer ring between said rotating and stationary means, said

intermediate ring sealing a portion of said internal gas from flowing to said outer sealing sleeve.

4,295,825

SYSTEM FOR THE PROTECTION OF THE DELIVERY END OF A ROTARY KILN

Alain Chielens, Marcq en Baroeul, and Bernard Boussekey, Lille, both of France, assignors to Fives-Cail Babcock, Paris, France


Filed Dec. 4, 1979, Ser. No. 100,239

Claims priority, application France, Dec. 7, 1978, 78 34456

Int. Cl.³ F27B 7/38

U.S. Cl. 432—116

8 Claims



1. A tubular rotary kiln having a discharge end and comprising
 - (a) metal shell having an internal and an external surface, the metal shell terminating in an end adjacent the discharge end,
 - (b) a refractory lining covering the internal shell surface up to a distance from the shell end and leaving a remaining portion of the internal shell surface uncovered,
 - (c) a flange fastened to the shell end at the discharge end of the kiln and extending radially outwardly from the shell, the flange having a front face and a rear face,
 - (d) a discharge end protective device including a refractory concrete ring covering the uncovered portion of the internal shell surface and the front face of the flange, the refractory concrete ring being anchored to the shell and to the flange, and
 - (e) means for circulating cooling air along the rear face of the flange and the external shell surface.

4,295,826

INFRARED DRYER

Michael Vasilantone, 34 Columbia Rd., Somerville, N.J. 08876

Filed Jun. 20, 1980, Ser. No. 161,488


Int. Cl.³ F27B 17/00; F26B 19/00

U.S. Cl. 432—185

28 Claims

1. A heating device comprising:
 - (a) a heating chamber in which objects are to be exposed to heat;
 - (b) at least one heater in said heating chamber;
 - (c) a first air trough disposed above said heating chamber;
 - (d) first means of fluid communication for communicating effluent air from said heating chamber to said first air trough;
 - (e) a second air trough disposed above said first air trough, extending along the upper surface or cover of the heating device, and serving to continually cool the upper surface or cover of the heating device;
 - (f) a header disposed above said heating chamber, said

header being ported to permit air from said header to be directed onto the objects to be exposed to heat; and



(g) second means for recirculating air from said heating chamber into said header.

4,295,827

ENDODONTIC FLOW THROUGH ULTRASONIC INSTRUMENT HOLDER ATTACHMENT


Howard Martin, 909 Pershing Dr., Silver Spring, Md. 20907, and James P. Norris, 1207 Frederick Rd., Catonsville, Md. 21228

Filed Dec. 31, 1979, Ser. No. 108,969

Int. Cl.³ A61C 5/02

U.S. Cl. 433—81

12 Claims



1. In combination, an endodontic instrument, an ultrasonic transducer device, a holder attachment for said instrument and ultrasonic transducer device, and an instrument locking means, said holder attachment consisting of a first hollow tube-like member and a second hollow tube-like member, said first and second hollow tube-like members being permissively and selectively capable of being set at any one of a plurality of angular relationships to each other, said ultrasonic transducer being coupled to one end of said first hollow tube-like member and with the opposite end of said first hollow tube-like member being coupled and affixed to said second hollow tube-like member at one selected position of said plurality of angular relationships, the interior of said first hollow tube-like member communicating with the interior of said second hollow tube-like member, said instrument locking means being coupled to one end of said second hollow tube-like member, said endodontic instrument being mounted in said instrument locking means, the opposite end of said second hollow tube-like member being open for passing said endodontic instrument there-through, said opposite end of said second hollow tube-like member also being open for passing a solution therethrough as and when received from said first hollow tube-like member.

4,295,828

EJECTOR HOLDER FOR SYRINGE-TYPE CARTRIDGE


Helmut Rudler, York, Pa., assignor to Dentsply Research & Development Corp., Milford, Del.

Filed Sep. 25, 1980, Ser. No. 190,681

Int. Cl.³ A61C 5/04

U.S. Cl. 433—90

6 Claims



1. A manually-operable ejector holder for a loaded syringe-type cartridge provided with an annular collar on one end and a discharge tip on the other, said holder comprising in combination, an elongated barrel, a plunger reciprocable therein and one end thereof projecting beyond one end of said barrel, manually engageable means on said one end of said barrel operable to reciprocate said plunger toward and from the other end of said barrel, said other end of said barrel having a curved transverse recess positioned and operable to receive a portion of said collar on said cartridge, a locking member having one end pivotally connected to said barrel and also having a curved transverse recess complementary to said opposite recess in said other end of said barrel and operable to receive an opposite portion of said collar on said cartridge, and a securing member slidable over said locking member and along the other end of said barrel to releasably connect said cartridge to said holder and the other end of said plunger being slidable toward said cartridge in axial alignment with said collar of said cartridge to penetrate said cartridge and effect discharge to the contents thereof.

4,295,829

TOOL HOLDER

Claude Martinelli, and Marcelle Martinelli épouse Boisson, both of 5, Place du Marche, Gracay, France (18310)


Filed Jul. 17, 1979, Ser. No. 58,379

Claims priority, application France, Aug. 8, 1978, 78 23369

Int. Cl.³ A61C 1/02; B25G 3/00

U.S. Cl. 433—99

18 Claims



1. A tool holder for holding a tool, said tool holder having a bent handle and having first and second ends; said holder comprising:

- (a) a head comprising means for receiving said tool, said head being arranged at said first end of said tool holder;
- (b) an operating knob arranged intermediate said first and second ends, said operating knob being operatively associated with said head whereby rotation of said operating knob results in movement of said tool;
- (c) securing means for securing said head to said holder in a fixed angular position relative thereto, and whereby the angular position of said head is adjustable relative to said handle;
- (d) an auxiliary operating knob arranged at the second end of said holder on said handle, said auxiliary operating knob

being operatively associated with said head whereby rotation of said auxiliary operating knob results in movement of said tool; and
(e) a multiplier system for providing the desired magnitude of movement to said tool in response to movement of said operating knob.

4,295,830

MOTORIZED DENTAL HANDPIECE

Sakae Uchida, Machida, Japan, assignor to Setagayaseiki Co. Ltd., Tokyo, Japan


Filed Mar. 26, 1980, Ser. No. 134,254

Claims priority, application Japan, Nov. 14, 1979, 54/147493

Int. Cl.³ A61C 1/12

U.S. Cl. 433—115

3 Claims



1. A motorized dental handpiece having a head and a head cap portion connectable therewith, said head cap portion comprising:

- a head gear shaft including a threaded section;
- a head gear rotatable with said head gear shaft;
- a head cap having a threaded section;
- a flange rotatable with said head gear shaft, said flange including a threaded section cooperable with said threaded section of said head gear shaft;
- a seal ring positionable between said head cap and said flange, said head cap being provided with a circumferentially extending groove in the axially outer peripheral surface thereof for reception of the axially inner portion of said seal ring, said flange being provided on the axially inner surface thereof with a circumferentially extending guide groove for reception of the axially outer portion of said seal ring, said seal ring having a V-shaped groove formed in the outer peripheral surface thereof and thereby forming radially inner and outer circumferentially extending edges, said edges being engageable with opposing surfaces of said flange, a wall of said seal ring proximate said radially inner edge thereof being at least coextensive and engageable with the radially inner wall of said guide groove, said regions of engagement thereby providing a plurality of circumferential seals preventing the admission of water and dust to the interior of said cap portion;
- said head gear shaft, head cap, seal ring and flange constituting releasably connected members of a unitary head cap portion assembly, said cap portion assembly being releasably connectable to the head of the handpiece, said threaded section of said head cap being cooperable with a threaded section on the head of the handpiece for releasably connecting said unitary assembly thereto.

4,295,831

COMPUTER PROGRAMMING TRAINING DEVICE

Frederick C. Matt, 1566 Campus Dr., Maple Glen, Pa. 19002

Filed Apr. 16, 1979, Ser. No. 30,321

Int. Cl.³ G09B 19/00

U.S. Cl. 434—118

10 Claims



1. A computer programming training device for teaching an operator the fundamentals of computer programming and operation, said device being operated by the operator to duplicate the physical functions performed by a programmable computer, said device comprising:

- a base member serving as a console for said device;
- a substantially planar program storage member mounted on

said base member to be detachable as a unit, said program storage member having a plurality of storage compartments each bearing a unique address identification, each compartment having written therein a word comprising a step in a program to be executed by the operator in simulating the operation of a programmed computer, said program storage member being adapted to contain the entire program to be executed;

means on said base member for detachably receiving said program storage member;

a program step indicator on said main member, said program step indicator including means adjustable by the operator to display a number corresponding to the address of the storage compartment which contains a particular program step concurrently with the execution of said program step;



a substantially planar main storage member mounted on said base member, said main storage member having a plurality of storage compartments each bearing a unique address which is different from any address borne by a compartment of said program storage member, the operator providing intercommunication between said program storage member and said main storage member so that, upon instruction by one of the program steps in a compartment of said program storage member, data from a compartment of one thereof may be transferred and written into a compartment of the other;

means on said base member for receiving said main storage member;

input means on said base member for receiving data from the operator, said data being written by the operator directly into one of the compartments of said main storage member upon instruction by one of the program steps stored in a compartment of said program storage member;

output means for receiving data directly from a compartment of said main storage member, said output means including means for receiving data, said data being copied by the operator from said main storage means upon instruction from a program step stored on said program storage member; and

operational register means on said base member for storing data, the operator providing intercommunications between said register means and said main storage member so that, upon instructions by a program step stored on said program stored means, data from said register means is written into a prescribed compartment of said main storage member and data from prescribed compartment of said main storage member may be provided to said register means.

4,295,832

EDUCATIONAL TOY


Manuel L. Karell, 17925 Devonshire, Apt. 21, Northridge, Calif. 91325

Filed Nov. 5, 1979, Ser. No. 91,586

Int. Cl.³ G09B 1/06

U.S. Cl. 434—168

5 Claims



1. A novel educational toy comprising in combination:
- a. an elongated support rod;
 - b. a plurality of separate magnetic members slideably received on said rod, each said member having a pair of opposite sides of opposite magnetic polarity, said members being mutually magnetically attracted into separate groups on said rod, said groups being mutually magnetically repelled from each other so as to be spaced along said rod;
 - c. wherein some of said members bear identifying indicia;
 - d. wherein members of each of said groups collectively provide a separate distinctive group indicium; and
 - e. wherein said indicia are letters of the alphabet.

4,295,833

INBOARD-OUTBOARD DRIVING MECHANISM INCLUDING A HYDRAULICALLY ASSISTED STEERING SYSTEM

Gaylord M. Borst, Waukegan, Ill., assignor to Outboard Marine Corporation, Waukegan, Ill.

Filed Oct. 23, 1978, Ser. No. 953,566


Int. Cl.³ B63H 1/14, 5/06, 25/42

U.S. Cl. 440—63

9 Claims

1. An inboard-outboard driving mechanism for a boat, said mechanism including a support adapted to be fixed relative to a boat hull, a propulsion leg including a rotatably mounted propeller, means connecting said propulsion leg to said support for pivotal steering movement about a steering axis, and means for causing pivotal steering movement of said propulsion leg including a steering shaft having a second axis transverse to said steering axis and rotatably journaled in said support, means connecting said steering shaft and said propulsion leg for pivoting said propulsion leg in response to rotation of said steering shaft, a lever mounted for pivotal movement about an axis transverse to said steering axis and having a first end and a second end, gear means connecting said first end of said lever and said steering shaft and operable, in response to rotation of

said lever, to rotate said steering shaft at an angular rate greater than the rate of rotation of said lever, a fluid motor connected



to said second end of said lever, and means for actuating said fluid motor to cause pivotal movement of said lever.

4,295,834

DRIVE MECHANISM FOR A WATERCRAFT WITH A SURFACE PROPELLER

Fabio Buzzi, Annone Brianza Como, and Sergio Carniti, Ogionio Como, both of Italy, assignors to Carl Hurth Maschinen- und Zahnradfabrik GmbH & Co., Munich, Fed. Rep. of Germany


Filed Jul. 17, 1979, Ser. No. 58,168

Claims priority, application Italy, Jul. 18, 1978, 25840 A/78

Int. Cl.³ B63H 5/16

U.S. Cl. 440—76

14 Claims



1. In a drive mechanism for a watercraft having a surface propeller rotatably driven by a drive motor arranged inboard thereof through shaft means which extends through a transom plate on the hull of said watercraft, the improvement comprising wherein a hollow support arm is provided and has a flange plate on one end thereof directly rigidly fastened to said transom plate of said watercraft, wherein said shaft means includes a substantially straight propeller shaft positioned on the outboard side of said transom plate and extending through the interior of said hollow support arm and having a propeller on one end thereof adjacent the free end of said support arm remote from said one end, wherein in the region of said flange plate there is arranged a propeller thrust bearing for facilitating a transmitting of the propeller thrust on said straight shaft to said flange plate and thence to said transom plate of said watercraft, and wherein said hollow support arm is of a unitary construction, and comprises a box-shaped lower part which extends in longitudinal direction with coaxial openings therein to facilitate the support of said propeller shaft therein and of a box-shaped upper part which also extends in longitudinal direction and is provided thereabove, which upper part is designed as a cavitation plate and projects at its rear end beyond the lower part, and wherein rib means are provided for connecting said upper and lower parts together, said rib means extending in longitudinal direction and on the front end thereof merging into said flange plate.

4,295,835

HIGH SPEED OUTBOARD DRIVE UNIT


Charles W. Mapes, and Richard H. Snyder, both of Oshkosh, Wis., assignors to Brunswick Corporation, Skokie, Ill.

Filed Oct. 9, 1979, Ser. No. 83,176

Int. Cl.³ B63H 1/14, 5/06, 21/32

U.S. Cl. 440—78



8 Claims



1. An engine driven outboard drive unit for attachment to a watercraft comprising:

- (A) a generally vertical housing;
- (B) a generally vertical drive shaft journaled for rotation within said housing and driven by said engine;
- (C) a generally horizontal propeller shaft driven by the lower end of said drive shaft;
- (D) a propeller mounted on the aft end of said propeller shaft;
- (E) a streamlined torpedo of generally cylindrical shape fixed to the lower end of said housing with said propeller shaft journaled for rotation within said torpedo forward of said propeller, said torpedo comprising an engine exhaust passage for discharging exhaust gases through the plane of said propeller; and
- (F) an annular projection substantially encircling the aft end of said torpedo to prevent blowout at high speeds.

outer discs rotate relative to each other for producing a radial shift of position of the intersections of said guideways and their



associated drive elements, thereby changing the effective diameter of said pulley.

4,295,837

SYNCHRONOUS BELT DRIVE SYSTEM


Richard L. Marsh, Springfield, Mo., assignor to Dayco Corporation, Dayton, Ohio

Filed Mar. 17, 1980, Ser. No. 130,661

Int. Cl.³ F16H 7/02; B21D 53/28

U.S. Cl. 474—153

20 Claims



1. In a toothed pulley for use in a synchronous drive power transmission system with a toothed endless power transmission belt made primarily of a polymeric material, the improvement wherein said toothed pulley has an optimum radius for its pulley teeth addendum circle having a size between the limits of a maximum radius determined by the radius of a circle through the points of a regular polygon having N equal sides and a minimum radius determined by the radius of a circle

4,295,836

FLAT BELT TRANSMISSION WITH ROTARY ACTUATOR AND INTEGRATED CONTROL SYSTEM

Emerson L. Kumm, 1035 E. Laguna Dr., Tempe, Ariz. 85282

Filed Jun. 1, 1979, Ser. No. 44,747

Int. Cl.³ F16H 11/02, 55/54

U.S. Cl. 474—51

6 Claims

1. A variable diameter pulley comprising two spaced, axially fixed sheaves, each having an inner and outer rotatable disc, said inner discs being rigidly interconnected and said outer discs being rigidly interconnected, means in said inner and outer discs defining oppositely angled, intersecting guideways, and drive elements having means for movably engaging said guideways at their intersections, said inner and outer rotatable discs including at least one pair of first and second chambers and means for exerting variable fluid pressure within said chambers, whereby, responsive to changes in the differential fluid pressure of said first and second chambers, said inner and

having N arcs each equal in arcuate length to the length of each side of said polygon.

4,295,838

METHOD OF PRODUCING CYLINDRICAL CONTAINERS


Frank P. Richards, Prairie Village, Kans., and Raymond C. Taylor, Grandview, Mo., assignors to Phillips Petroleum Company, Bartlesville, Okla.

Division of Ser. No. 853,651, Nov. 21, 1977, Pat. No. 4,204,462, which is a division of Ser. No. 630,555, Nov. 10, 1975, Pat. No. 4,072,226. This application Dec. 31, 1979, Ser. No. 108,437

Int. Cl.³ B31C 1/06

U.S. Cl. 493—105

6 Claims



1. A method for forming a tubular container, said method comprising:
forming a closure blank into a closure member having a desired shape;
maintaining said closure member adjacent the end of a tubular mandrel;
heating opposing side margins of a sidewall blank having a thermoplastic coating on both sides thereof;
wrapping said sidewall blank around said mandrel to overlap and thermally bond said previously heated opposing side margins and to bring a continuous end of said sidewall blank into contact with a portion of said closure member;
heating said end of said sidewall blank and the adjacent portion of said closure member;
rolling said end of said sidewall blank and the adjacent portion of said closure member together to seal said closure member to said sidewall blank to form a container;
removing said container from said mandrel;
successively advancing individual containers of a series of open-topped containers so removed to a container finishing station;
gripping a bottom portion of the container located at said finishing station;
finishing the thus gripped container by altering the configuration of the open container top while said bottom portion is so gripped;
releasing said bottom portion upon completion of the finishing of said container; and
removing the thus released container from said finishing station.

4,295,839

METHOD AND APPARATUS FOR FORMING A FLANGED TRAY

Thomas R. Baker, and Peter C. Collura, both of Los Altos, Calif., assignors to Kliklok Corporation, Greenwich, Conn.

Filed Jul. 6, 1979, Ser. No. 55,050


Int. Cl.³ B31B 1/48

U.S. Cl. 493—143

16 Claims

1. A method of forming a tray from a paperboard blank or the like having inherent resiliency, the tray including a base panel, two pairs of wall panels attached to the base panel, panels formed at the corners of the wall panels, and flanges formed along the outer edge of each wall panel, comprising the steps of:
providing adhesive on at least one of each adjacent wall panel and corner panel;
forming said tray wall panels into an erected position;

folding each said corner panel to contact an adjacent wall panel such that the adhesive is in the area of contact;
folding said flanges outwardly and downwardly from said erected tray wall panels into an overbroken position to lie in an acute angle with respect to said wall panels, said flanges being folded through an angle sufficient to overbreak the flanges with respect to said walls such that said folded flanges may relax to a raised, approximately horizontal position when said tray is released;



retaining said flanges against the resiliency of the blank in said overbroken position over and in contact with said corner panels to retain said panels in contact with the adjacent wall panels for a time sufficient to allow an adhesive bond to form therebetween; and
releasing said tray to allow upward movement of the flanges to the raised position, whereby a tray is formed with a substantially continuous horizontal flange around the periphery thereof to allow sealing of a cover to the tray.

4,295,840

METHOD OF CONSTRUCTING COMPOSITE CONTAINERS

Jerry F. Sansbury, Hartsville, S.C., assignor to Sonoco Products Company, Hartsville, S.C.


Division of Ser. No. 865,799, Dec. 30, 1977, Pat. No. 4,158,425.

This application Nov. 2, 1978, Ser. No. 957,107

Int. Cl.³ B31C 3/04

U.S. Cl. 493—278

10 Claims



5. A method of forming a lined tubular body of composite construction comprising forming a liner of a tubular configuration with spaced adhesive bands about the exterior thereof, forming a composite tube about said liner, adhesively securing the composite tube to the liner solely by the spaced adhesive bands while retaining the liner, between the spaced adhesive bands, free of attachment to the composite tube and capable of movement relative thereto, and transversely severing the composite tube and liner through each adhesive band to define individual tubular bodies with liners secured solely at the opposed ends thereof.

4,295,841

BOX BLANK FOLDING APPARATUS


Henry D. Ward, Jr., Cockeysville, Md., assignor to The Ward Machinery Company, Cockeysville, Md.

Filed Oct. 19, 1979, Ser. No. 86,600

Int. Cl.³ B31B 1/42, 1/54

U.S. Cl. 493—295

10 Claims



1. Box blank folding apparatus comprising in combination: advancing means for serially advancing box blanks continuously through said apparatus; first folding means near an upstream end of said advancing means for folding outer panels of said box blanks to a substantially upright position as said blanks advance through said apparatus; said first folding means comprising pivotable bar folder means near an upstream end of said advancing means and reciprocable in the direction of travel of said blanks for engaging substantial portions of said outer panels during the advance of said blanks through said apparatus; and second folding means downstream from said first folding means for folding said outer panels from said upright position to a substantially horizontal position against inner panels of said blanks; said second folding means comprising pivotable bar folder means reciprocable in the direction of travel of said blanks for engaging substantial portions of said outer panels during the advance of said box blanks through said apparatus.

4,295,842

STRIPPING DEVICE FOR REMOVING WASTE SHEET BOARD

Clinton C. Bell, Carmel, Ind., assignor to The Ward Machinery Company, Cockeysville, Md.

Filed Dec. 31, 1979, Ser. No. 108,803


Int. Cl.³ B26D 7/18

U.S. Cl. 493—342

8 Claims

1. In a stripping device for removing waste sheet wedged within the cutting portion of a sheet cutting die rotatable about an axis comprising: a frame; a stripping pin holder rotatably mounted on said frame and having an axis of rotation extending in the same direction and parallel to said axis of said sheet cutting die; a plurality of stripping pins mounted to said stripping pin holder and extending outwardly therefrom, said stripping pins have length and are positionable adjacent said sheet cutting die as said stripping pin holder rotates to extend into said sheet cutting die piercing said waste sheet and removing said waste sheet from said sheet cutting die upon continued rotation of said sheet cutting die and said stripping pin holder; and means operably engaged with said stripping pin holder to rotate said stripping pin holder in synchronization with said sheet cutting die; the improvement comprising: means causing the stripping pins to exert lifting action pressure against said

waste sheet, including the radial distance from said stripping pin axis of rotation to the outermost extremity of each said



stripping pin exceeding the radial distance from said sheet cutting die axis of rotation to said sheet cutting die cutting portions.

4,295,843

ROTARY DIE CUTTER

Tadao Otomaru, Mihara, Japan, assignor to Mitsubishi Jukogyo Kabushiki Kaisha, Tokyo, Japan


Filed Dec. 28, 1979, Ser. No. 108,232

Claims priority, application Japan, Jan. 8, 1979, 54-815

Int. Cl.³ B31B 9/14

U.S. Cl. 493—354

6 Claims



1. A rotary die cutter comprising:
(a) a knife cylinder having a punching blade on its peripheral surface;
(b) an anvil cylinder positioned adjacent said knife cylinder and arranged to be engaged by said blade for punching a cardboard sheet passing between said cylinders;
(c) first and second meshing gears for driving said cylinders, said first gear being arranged at one end of said knife cylinder and said second gear being arranged at one end of said anvil cylinder;
(d) first and second interengaging helical gears disposed at said one end of said anvil cylinder, said first helical gear being mounted on said anvil cylinder, said second helical gear being connected to said second meshing gear;
(e) mechanism engaging said anvil cylinder for moving said anvil cylinder axially;
(f) said axial movement of said anvil cylinder causing relative axial movement of said helical gears to impart a rotational shift to said anvil cylinder; and
(g) adjusting means engaging one of said helical gears to move said one of said helical gears axially for imparting a further rotational shift to said anvil cylinder.

CHEMICAL

4,295,844

PROCESS FOR THE THERMAL STABILIZATION OF ACRYLIC FIBERS

Steven B. Warner, Bernardsville, N.J., assignor to Celanese Corporation, New York, N.Y.

Filed Apr. 18, 1980, Ser. No. 141,706

Int. Cl.³ D06Q 1/02

U.S. Cl. 8—115.5

12 Claims

1. An improved process for the thermal stabilization of an acrylic fibrous material selected from the group consisting of an acrylonitrile homopolymer and acrylonitrile copolymers containing at least about 85 mol percent of acrylonitrile units and up to about 15 mol percent of one or more monovinyl units copolymerized therewith comprising:

- contacting said fibrous material with a dilute solution of aniline and Group IA metal hydroxide which is provided at an elevated temperature for a residence time of approximately 5 to 30 minutes whereby said fibrous material is rendered capable of undergoing thermal stabilization on a more expeditious basis;
- removing the excess quantity of said solution adhering to said fibrous material following said contact; and
- heating said resulting fibrous material in an oxygen-containing atmosphere at a temperature of approximately 200° to 360° C. until a stabilized fibrous material formed which is black in appearance, retains its original configuration substantially intact and which is non-burning when subjected to an ordinary match flame.

4,295,845

PRETREATMENT COMPOSITION FOR STAIN REMOVAL

Ralph R. Sepulveda, Suffern, N.Y., and Lynn H. Lander, Harrington Pk., N.J., assignors to Lever Brothers Company, New York, N.Y.

Division of Ser. No. 49,774, Jun. 18, 1979. This application May 19, 1980, Ser. No. 151,227

Int. Cl.³ C11D 3/46, 7/26; D06L 1/02, 1/22

U.S. Cl. 8—139.1

4 Claims

1. A method for the pre-laundering treatment of stained fabrics comprising contacting said fabric with an active composition containing little or no water and having little tendency to exhibit separation, said composition comprising at least one ester formed of a fatty acid of about eight to about twenty-two carbon atoms chain length, and

- an alcohol of one to about four carbon atoms chain length or
 - a polyalkylene glycol which is a polyethylene or polypropylene glycol; and wherein said ester is a di-ester.
4. A method for the pre-laundering treatment of stained fabrics comprising contacting said stained fabric with an active composition containing little or no water and having little tendency to exhibit separation with an active composition, said composition comprising:
- about 25% to about 90% of at least one ester formed of a fatty acid of about eight to about twenty-two carbon atoms chain length, and
 - an alcohol of one to about four carbon atoms chain length or
 - a polyalkylene glycol which is a polyethylene or polypropylene glycol; and wherein said ester is a di-ester;
- 0 to about 75% of at least one nonionic surface-active agent; and
 - 0 to about 60% of at least one anionic surface-active agent.

4,295,846

PROCESS FOR THE PRODUCTION OF FORMALDEHYDE-FREE FINISHING AGENTS FOR CELLULOSIC TEXTILES AND THE USE OF SUCH AGENTS

Harro Petersen, Frankenthal, Fed. Rep. of Germany; Panemangalore S. Pai, Charlotte, N.C.; Friedrich Klippel, Ludwigshafen, and Friedrich Reinert, Wachenheim, both of Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Fed. Rep. of Germany

Filed Mar. 18, 1980, Ser. No. 131,409

Int. Cl.³ D06M 13/34

U.S. Cl. 8—186

2 Claims

1. A process for the production of formaldehyde-free, easy-care finishing agents with a long shelf life for textiles containing or consisting of cellulose on the basis of urea or N,N'-disubstituted ureas and glyoxal, comprising in the first stage of the process, reacting 1 to 1.1 mole of urea or symmetrically disubstituted urea of the general formula I



where

R¹ and R² are $-(CH_2)_nO$ or hydrogen,R³ is C₁₋₄ alkyl or, if m > 0, hydrogen, n is 2 to 4

m is 0 to 10,

for three hours in aqueous solution with 1 mole of glyoxal, in the presence of buffer mixtures sufficient to maintain the pH of the solution between 4 and 6.8, at a temperature of from 20° to 60° C., and, in the second stage, reacting the solution resulting from the first stage, after admixing, with at least 0.5 mole of an alcohol R⁴OH, where R⁴ is $[(CH_2)_nO]_mR^3$, where R³, except for hydrogen; m and n are defined above, and an acid, for one to three hours at a pH of between 2 and 4.5 and a temperature of from 30° to 65° C., and finally adjusting the pH of the solution to 4 to 7.

4,295,847

FINISHING PROCESS FOR TEXTILES

Harro Petersen, Frankenthal, Fed. Rep. of Germany; Panemangalore S. Pai, and Manfred Reichert, both of Charlotte, N.C., assignors to BASF Aktiengesellschaft, Fed. Rep. of Germany


Filed Jan. 25, 1980, Ser. No. 115,264

Int. Cl.³ D06M 13/38, 15/38, 15/54, 1/02

U.S. Cl. 8—189

2 Claims

1. A process for finishing a cellulosic textile which has been pretreated with liquid ammonia, by impregnating the textile with a finishing agent based on an aminoplast intermediate and heating for from 10 seconds to 6 minutes at from 110° to 230° C. in the presence of an acid or latent acid catalyst, wherein the finishing agent employed is a water-soluble compound of the formula III



where R¹ and R² independently of one another are hydrogen, methyl, ethyl, propyl or methoxyethyl and R² may also be the radical of an ethylene oxide and/or propylene oxide polymer chain comprising from 1 to 20 monomer units.

4,295,848

COMPOSITION FOR HAIR DYEING WHICH CONTAINS A PARA BASE AND AN ORTHO BASE


Jean F. Grollier, Paris; Andree Bugaut, Boulogne-Billancourt; Patrick Andriillon, Aulnay-sous-Bois, and Chantal Fourcadier, Paris, all of France, assignors to L'Oreal, Paris, France
Division of Ser. No. 27,363, Apr. 5, 1979. This application Oct. 29, 1980, Ser. No. 201,505

Claims priority, application France, Apr. 6, 1980, 78 10278

Int. Cl.³ C07C 50/80, 119/12

U.S. Cl. 8—421

1. A compound of the formula:



in which: Y represents



R₁' and R₂' independently of one another denoting an alkyl, mesylaminoalkyl, piperidinoalkyl or hydroxyalkyl group, the alkyl groups containing 1 to 6 carbon atoms, or a cosmetically acceptable salt thereof.

4,295,849

PROCESS FOR THE PREPARATION OF DYESTUFF FORMULATIONS

Konrad Nonn; Karlheinz Wolf; Artur Haus, and Reinhold Hörnle, all of Bayer AG, Leverkusen, Fed. Rep. of Germany (D-5090)

Filed Mar. 9, 1977, Ser. No. 775,898

Claims priority, application Fed. Rep. of Germany, Mar. 11, 1976, 2610094

Int. Cl.³ C09B 67/38; D06P 1/645

U.S. Cl. 8—524

7 Claims

1. Process for the preparation of pulverulent formulations suitable for use in transfer printing, which can be dispersed easily in organic media, of dyestuffs which are sublimable at 100°–230° C., wherein aqueous dispersions of said dyestuffs or aqueous solutions or dispersions of precursors of said dyestuffs are mixed with compounds of the formula



wherein

R is C₁₀–C₂₀-alkyl, and
Z is NH₂, NH(CH₂)₃–NH₂ or OH, converting any of said precursors into the corresponding dyestuffs, and drying the resulting aqueous solution or dispersion into a dry pulverulent product.

4,295,850

COMMERCIAL PREPARATIONS OF DRY ORGANIC SUBSTANCES

Roland Häberli, Würenlingen; Hans Mollet, Reinach, and Gustaf Scherer, Basel, all of Switzerland, assignors to Ciba-Geigy Corporation, Ardsley, N.Y.

Continuation of Ser. No. 14,194, Feb. 22, 1978, abandoned, which is a continuation of Ser. No. 846,041, Oct. 27, 1977, abandoned, which is a continuation of Ser. No. 713,556, Aug. 11, 1976, abandoned, which is a continuation of Ser. No. 521,309, Nov. 6, 1974, abandoned. This application May 23, 1980, Ser. No. 152,951

Claims priority, application Switzerland, Nov. 13, 1973, 15962/73

Int. Cl.³ D06P 67/02

U.S. Cl. 8—524

6 Claims

1. Stable dust-free commercial preparations of organic substances, which preparations comprise an organic dyestuff, optical brightener or dyeing auxiliary substance in dry powder form enclosed in a covering having a thickness of 10 to 80 μ, said covering forming a sack or bag sealed on all sides, made from polyethylene oxide having a molecular weight of more than 200,000.

4,295,851

PROCESS FOR THE PRODUCTION OF NEGLIGIBLY DUSTY PREPARATION

Konrad Neumann, Wyhlen; Ernst Schenkenberger, Rheinfelden, and Friedrich Resch, Lörrach, all of Fed. Rep. of Germany, assignors to Ciba-Geigy Corporation, Ardsley, N.Y.

Continuation of Ser. No. 858,031, Dec. 6, 1977, abandoned. This application Jun. 17, 1980, Ser. No. 160,256

Claims priority, application Fed. Rep. of Germany, Dec. 13, 1976, 2656408

Int. Cl.³ C09B 67/06, 67/08, 67/24, 67/32

U.S. Cl. 8—524

14 Claims

1. A process for the production of negligibly dusty preparations by spray drying an aqueous suspension consisting essentially of water, at least one water-soluble dye or optical brightener, at least one water-soluble adhesive containing at least five hydroxyl groups per molecule wherein said adhesive softens or melts in the temperature range of 30°–150° C., and in the presence or absence of diluting agents, dispersing agents, stabilisers against oxidative or reductive effects, pH-adjusting acids, bases or buffering agents; and wherein a dust-binding water-soluble surface-active agent is added to said aqueous suspension, or said dust-binding water-soluble surface-active agent is added to the spray-dried product, or partially to said aqueous suspension and partially to the spray-dried product.

4,295,852

PROCESS FOR DYEING POLYAMIDE FIBRES

Klaus Walz, Leverkusen, and Joachim Fiegel, Bergisch-Gladbach, both of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany
Filed Nov. 3, 1980, Ser. No. 202,907


Claims priority, application Fed. Rep. of Germany, Nov. 8, 1979, 2945102

Int. Cl.³ D06P 3/24

U.S. Cl. 8—560

3 Claims

1. Process for dyeing polyamide fibre materials with acid dyestuffs and/or metal complex dyestuffs, characterised in that the dyeing is carried out in the presence of compounds of the formula



in which

R represents a C₄–C₁₂-alkyl, C₁–C₁₂-alkoxy, phenyl, cyclohexyl or C₂–C₁₀-hydroxyalkoxy radical,
R₁ represents hydrogen or a C₁–C₄-alkyl radical,
n represents an integer from 1 to 10 and
m represents a number from 1 to n+1,
or water-soluble salts thereof.

4,295,853

METHOD FOR MEASURING PEROXIDIC SUBSTANCES

Shizuka Kasahara, Amagasaki; Kazuhiko Yamanishi, Tokyo; Toshiro Hanada; Kuniaki Tokuda, both of Kawagoe, and Shinzo Kobatake, Ibaraki, all of Japan, assignors to Wako Pure Chemical Industries, Ltd., Osaka, Japan

Filed Dec. 29, 1978, Ser. No. 974,148

Claims priority, application Japan, Dec. 29, 1977, 52-159070; Feb. 28, 1978, 53-22313

Int. Cl.³ G01N 31/22, 33/52, 33/92

U.S. Cl. 23—230 B

8 Claims

1. A method for determining lipoperoxides in a fluid sample obtained from a human being or other animal comprising:
(a) extracting a lipoperoxide from a sample of serum, blood plasma or blood with a solvent selected from the group consisting of a hydrocarbon, an alcohol, a halogenated hydrocarbon, dimethylformamide, dimethylsulfoxide and N-methyl-pyrrolidone;
(b) contacting the extracted lipoperoxides with an oxidizable color reagent in the presence of a metallic compound produced from a metal which is able to have two or more valences to produce color; and
(c) measuring the degree of coloring.

4,295,854

APPARATUS AND METHODS FOR SAMPLE ENRICHMENT FOR FLAMELESS ATOMIC ABSORPTION SPECTROSCOPY

Bernhard Huber, Überlingen, Fed. Rep. of Germany, assignor to Bodenseewerk Perkin-Elmer & Co., GmbH, Fed. Rep. of Germany


Filed Sep. 24, 1979, Ser. No. 78,367

Claims priority, application Fed. Rep. of Germany, Jan. 29, 1979, 2903246

Int. Cl.³ G01J 3/02; G01N 31/02

U.S. Cl. 23—230 PC

14 Claims



1. A method of forming an atomic cloud of a looked-for element in a graphite tube through which a measuring beam of an atomic absorption spectrometer may be passed for the

flameless atomic absorption spectroscopic measurement thereof; said method comprising the steps of:

inserting an electrode into a sample vessel containing a solution including said looked-for element;
passing an electric current through said solution to deposit components of said solution, including said looked-for element, on said electrode;
transferring said electrode having said looked-for element electrodeposited thereon from said sample vessel to said graphite tube such that said graphite tube and said electrode are in a heat transfer relationship, said transferring step including inserting said tip of said electrode carrying said electrodeposition into said graphite tube, via a lateral bore in the wall thereof, such that said tip is located inside said graphite tube; and
heating said graphite tube to a temperature whereat said components are atomized to form said atomic cloud.

4,295,855

METHOD FOR SEPARATING FIBRINOGEN AND ITS CONSTITUENT COMPONENTS

Susumu Sasaki, Nagoya; Kyoji Kito, Seto, and Akio Koide, Ichinomiya, all of Japan, assignors to Meito Sangyo Kabushiki Kaisha and Susumu Sasaki, both of Aichi, Japan


Filed Jan. 10, 1980, Ser. No. 110,946

Claims priority, application Japan, Jan. 16, 1979, 54/2162

Int. Cl.³ G01N 33/50, 33/68

U.S. Cl. 23—230 B

14 Claims



1. A method for obtaining fibrinogen or its constituent components, which comprises contacting a fibrinogen-containing composition with at least one aminocarboxylic acid of the formula



(I)

wherein n is a positive integer, in an aqueous medium in the presence of an ionic strength controlling agent capable of adjusting the ionic strength of the system to from about 0.02 to about 2.2 to collect at least one member selected from the group consisting of fibrinogen fraction 1 and fibrinogen fraction 2.

4,295,856

NITROSAMINE SPECIFICITY FOR ELECTROLYTIC CONDUCTIVITY DETECTOR

Rollen J. Anderson, Austin, Tex., assignor to Tracor, Inc., Austin, Tex.

Filed Apr. 21, 1980, Ser. No. 141,900


Int. Cl.³ G01N 31/08, 27/26

U.S. Cl. 23—232 E

29 Claims

1. A method for selectively pyrolyzing N-nitrosamines to ammonia from a sample containing other nitrogen compounds, which comprises:
contacting said sample with hydrogen at a temperature ranging from about 500° to about 700° C., in a non-

catalytic environment, which environment is free of nickel and is a reactor having a metallic surface exposed to



said sample during pyrolysis wherein said metal surface is gold or platinum.

4,295,857

PROCESS FOR THE CRYSTALLINE PRECIPITATION OF CHROMOGENS

Peter Schuler, Am Knie 7, 8000 München 60, BRD, and Erwin Braun, Unteranger 1, 8132 Tutzing, BRD, both of Fed. Rep. of Germany

Filed Apr. 3, 1980, Ser. No. 136,911

Claims priority, application Fed. Rep. of Germany, Apr. 6, 1979, 2913889

Int. Cl.³ B01D 9/02; G01N 33/15

U.S. Cl. 23—301 19 Claims

1. A process for crystalline precipitation of a chromogen from solution thereof in a solvent and within a capillary, comprising the steps of initiating a course of crystalline precipitation of the chromogen by initially and locally supersaturating the solution within the capillary, and thereafter evaporating the solvent at a rate and in an environment sufficient for further crystallization to proceed unimpeded by local supersaturation.

4,295,858

PROCESS FOR REMOVING SULFUR FROM COAL

Jui-Yuan Sun, South Holland; Emmett H. Burk, Jr., Glenwood; Jin S. Yoo, Flossmoor, all of Ill., and George P. Masologites, Columbus, N.C., assignors to Atlantic Richfield Company, Philadelphia, Pa.

Continuation-in-part of Ser. No. 944,452, Sep. 21, 1978, Pat. No. 4,249,910. This application Mar. 3, 1980, Ser. No. 126,248

Int. Cl.³ C10L 9/02

U.S. Cl. 44—1 SR 19 Claims

1. A process for reducing the sulfur and ash content of coal comprising the steps of:

- (1) contacting coal particles containing ash and iron pyrite mineral matter with a promoting amount of at least one conditioning agent, said conditioning agent having a ferrous component maintained at a pH of from about 5.5 to 11.0 and being capable of modifying or altering the existing surface characteristics of the pyrite under conditions to effectuate alteration of modification of at least a portion of the contained pyritic sulfur;
- (2) agglomerating the coal particles while said pyrite surfaces are altered or modified in an aqueous medium with hydrocarbon oil to form coal-hydrocarbon oil agglomerates;
- (3) separating said coal-hydrocarbon oil agglomerates from pyrite mineral matter and ash to recover coal-hydrocar-

bon oil agglomerates wherein the coal exhibits reduced sulfur and ash content.

2. The process of claim 1 wherein the conditioning agent is prepared externally and added to the coal particles.

4,295,859

FUELS AND HEATING OILS, A PROCESS FOR THEIR PREPARATION AND THEIR USE

Günther Boehmke, Leverkusen, Fed. Rep. of Germany, assignor to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Nov. 30, 1979, Ser. No. 99,124

Claims priority, application Fed. Rep. of Germany, Dec. 16, 1978, 2854437

Int. Cl.³ C10L 1/18

U.S. Cl. 44—51

6 Claims

1. A fuel for a combustion engine or heating oil comprising a hydrocarbon, water and a non-ionic emulsifier, said non-ionic emulsifier containing less than 1,000 ppm of salt constituents and less than 1 percent by weight of polyalkylene glycol ethers.

4,295,860

MULTIFUNCTIONAL GASOLINE ADDITIVES

Michael E. Childs, Wilmette, Ill., assignor to UOP Inc., Des Plaines, Ill.

Filed Jun. 23, 1980, Ser. No. 161,828


Int. Cl.³ C10L 1/18, 1/22

U.S. Cl. 44—63

3 Claims


1. A composition comprising a major amount of a fuel oil and an additive consisting of from about 10 ppm up to 100 ppm of the reaction product of:

(a) a glycidyl ether presented by the formula:



wherein R is either

(i) a saturated hydrocarbyl group possessing from about 6 to about 20 carbon atoms or



(ii)

wherein R₁ and R₂ are saturated hydrocarbyl radicals containing from 1 to 17 carbon atoms and wherein the sum of R₁ and R₂ is from about 4 to about 18 carbon atoms

with

(b) an N-monosubstituted alkylenediamine having from 2 to about 8 carbon atoms in the alkylene moiety.

4,295,861

MOTOR FUEL

Lyle D. Burns, Bartlesville, Okla., assignor to Phillips Petroleum Company, Bartlesville, Okla.

Filed Oct. 24, 1980, Ser. No. 200,293

Int. Cl.³ C10L 1/22

U.S. Cl. 44—63

9 Claims

1. An internal combustion fuel composition comprising a major proportion of a motor fuel containing a small but effective amount, sufficient to impart reduced knocking tendencies to said motor fuel, of an ashless antiknock additive selected from the group consisting of 2-(dimethylaminomethyl)-3-hydroxypyridine (I), 2-(diethylaminomethyl)-3-hydroxypyridine (II), 2-(pyrolidinomethyl)-3-hydroxypyridine (III), 2-

(piperidinomethyl)-3-hydroxypyridine (IV), and 2-(morpholinomethyl)-3-hydroxypyridine (V).

4,295,862

MOTOR FUEL

Lyle D. Burns, Bartlesville, Okla., assignor to Phillips Petroleum Company, Bartlesville, Okla.

Filed Oct. 24, 1980, Ser. No. 200,292

Int. Cl.³ C10L 1/22

U.S. Cl. 44—72

6 Claims

1. An internal combustion fuel composition comprising a major proportion of a motor fuel containing a small but effective amount, sufficient to impart reduced knocking tendencies to said motor fuel, of an ashless antiknock additive selected from the group consisting of (I) N-methylpropargylamine, (II) N-benzylpropargylamine, (III) N-phenylpropargylamine, (IV) dipropargylamine, and (V) N,N'-diethyl-2-butyne-1,4-diamine.

4,295,863

METHOD FOR AUTOMATING AND OPTIMIZING THE OPERATIVE CYCLE IN ADSORPTION DEHYDRATION PLANTS

Sergio Lattuada, Bergamo, Italy, assignor to S.T.I. Strumentazione Industriale S.p.A., Gorle, Italy


Filed May 27, 1980, Ser. No. 153,265

Claims priority, application Italy, Jun. 6, 1979, 2912 A/79

Int. Cl.³ B01D 53/04

U.S. Cl. 55—21

2 Claims



1. A method for automating and optimizing the steps of the working cycle in adsorption gas dehydration plants of the heatless regeneration type, having two tanks storing an adsorbing medium and alternating with each other in the function of adsorption and regeneration of the adsorbing medium, with a sequence of steps sequentially comprising the regeneration of the adsorbing medium in a tank by a small amount of dried gas drawn from the other tank that is in adsorption step, the repressurization of that tank which was in regeneration step and which is, therefore, brought to the same pressure as that of the tank that was in adsorption step, the exchange or reversal of the functions of the two tanks, whereby that tank that was in regeneration step is changed to adsorption step, while the tank that was in adsorption step is decompressed and then regenerated, repeating the above disclosed sequence, in which repressurization valves are provided for opening and closing at suitable time the passage to atmosphere, and the sequence and duration of the several steps are controlled by a programmer, wherein said operations of repressurization and reversal are effected upon a single pulse or control signal simultaneously requesting that the repressurization and reversal steps to be carried out, and wherein said single control signal for the repressurization and reversal steps is supplied to the servocontrol of a two- or three-way valve having an unbalanced type of shutter, in which the changeover of the shutter occurs only when a balance is provided between the force generated by the servocontrol and the force generated by the pressure differen-

4,295,864

PROCESS OF TREATING PRESSURIZED CONDENSATE

Paul Rudolph, Bad Homburg, and Paul D. Becker, Eschborn, both of Fed. Rep. of Germany, assignors to Metallgesellschaft Aktiengesellschaft, Frankfurt, Fed. Rep. of Germany


Filed Nov. 30, 1979, Ser. No. 99,179

Claims priority, application Fed. Rep. of Germany, Dec. 14, 1978, 2853989

Int. Cl.³ B01D 53/14, 19/00

U.S. Cl. 55—40

5 Claims



catching fine particles and noxious materials entrained in said flue gases which pass through the mist layers; permitting condensed droplets from said mist layers to flow down to an inclined surface located at the bottom of said chimney to form a liquid-sludge; discharging said liquid-sludge along said inclined surface through an outlet positioned at the lower end of said inclined surface into a precipitating vessel; and inhibiting cold air from entering the chimney through said outlet by disposing a checkered plate at an opening for said outlet in a wall of said chimney said method removing dust and noxious materials without appreciably affecting the normal ventilation of said chimney.

4,295,866

PAINT SPRAY BOOTH WITH WATER WASH

Thomas J. Kearny, 8 Oaklands, Green Lane, Malvern Wells, Worcester, England


PCT No. PCT/GB78/00022, § 371 Date Jun. 7, 1979, § 102(e) Date Jun. 7, 1979, PCT Pub. No. WO79/00209, PCT Pub. Date Apr. 19, 1979

PCT Filed Oct. 11, 1978, Ser. No. 46,475

Int. Cl.³ B01D 47/06

U.S. Cl. 55—228

10 Claims



1. A paint spray booth installation comprising a water tank, pump means for withdrawing water from the tank, a washing system for washing sprayed paint from the booth into the tank, said pump means feeding water to said washing system, a baffle plate dividing the tank into two communicating regions, said baffle plate extending from one end wall of the tank over a major part of the width of the tank and from the bottom of the tank to a height sufficient to break the surface of the water, an inlet for said pump means located near the said end wall in a first of said regions, a surface removal device located close to the pump inlet and arranged to transfer floating paint from the vicinity of the pump inlet into the second of the said regions, the water in the second region being subject to agitation by water falling onto the surface from said washing system, and a surface baffle extending between the baffle plate and a wall of the tank and arranged to hold back floating material while allowing free circulation below the surface baffle away from the second region towards the pump inlet.

4,295,867

APPARATUS FOR SEPARATING CARBON BLACK FROM CARBON-BLACK AEROSOL

Viktor M. Shopin, ulitsa 50 let VLKSM, 3, kv. 8; Leonid G. Turenko, ulitsa ozero Khasan, 12; Vitaly F. Surovikin, ulitsa Lermontova, 20, kv. 80, and Konstantin V. Suponev, prospekt Mendeleeva, 11, kv. 40, all of Omsk, U.S.S.R.

Filed Jun. 8, 1979, Ser. No. 46,650


Int. Cl.³ B01D 41/02, 39/16

U.S. Cl. 55—288

7 Claims

1. A filtering system for separating carbon black from a carbon-black aerosol, comprising: a plurality of compartments, each compartment partitioned by a fixed screen, having a mesh size ranging from about 50 to about 200 microns, into first and

second chambers, each of said screens supporting a granular bed of carbon black grains arranged on said screen; the ratio of the height of the granular bed of carbon black grains to the height of said first chamber being within 0.1–0.5; an intake manifold, for admission of the carbon-black aerosol, communicating with each said first chambers; first shutoff means, an exit manifold, for a cleaned discharge gas, communicating with



each of said second chambers and with said first shutoff means, second shutoff means; an entry manifold, for a regenerating gas, communicating with each of said second chambers, said exit manifold and with said second shut off means; blower means communicating with said exit manifold to enable said regenerating gas to flow from said exit manifold through said entry manifold.

4,295,868

FILTER FOR CLEANING HOT GASES

Heinz Hölter, Gladbeck; Heinz Gresch, Dortmund-Derne; Heinrich Igelbüscher, Gladbeck; Kurt Hübner, and Ekkehard Weber, both of Essen, all of Fed. Rep. of Germany, assignors to Industrie-Wert Beteiligungsgesellschaft mbH, Fed. Rep. of Germany


Filed Mar. 9, 1979, Ser. No. 19,371

Claims priority, application Fed. Rep. of Germany, Mar. 17, 1978, 2811641; May 22, 1978, 2822274; Jul. 5, 1978, 2829412; Jul. 5, 1978, 2829413; Sep. 4, 1978, 2838476

Int. Cl.³ B01D 27/30, 33/30, 39/06

U.S. Cl. 55—302

4 Claims



1. An apparatus for cleaning hot gases comprising a filter housing having an inlet for unfiltered gas and an outlet for filtered gas, and a plurality of filter inserts placed within the housing in a manner capable of filtering undesirable components from the gas feed stream, each said filter insert comprising a fibrous filter material, the fibers consisting of silicic-acid glass fibers with a silicic-acid content of at least 90%, absorbed into the pores of which and coated upon which is a metal oxide of at least one of the group consisting of aluminum, titanium, zirconium, chromium, nickel, or cobalt, further comprising a cage of a honeycombed structure filled with expanded high temperature resistant perlite located within the housing between the gas inlet and the filter inserts, wherein the cage has an inlet and an outlet, both external to the housing, for effecting replacement of the perlite, and further comprising a combustion chamber mounted within said housing having a discharge nozzle located so that said nozzle is directed at the filter inserts, said combustion chamber having means for the insertion of combustible air connected thereto, whereby combust-

ing materials in the chamber causes an explosive backflow of gases through the filter inserts.

4,295,869

PROCESS FOR PRODUCING OPTICAL TRANSMISSION FIBER

Satoshi Shiraishi; Kunio Fujiwara, and Shiro Kurosaki, all of Osaka, Japan, assignors to Sumitomo Electric Industries, Ltd., Osaka, Japan

Continuation of Ser. No. 648,997, Jan. 14, 1976, Pat. No.

4,161,505, which is a division of Ser. No. 419,011, Nov. 26, 1973, abandoned. This application Feb. 8, 1979, Ser. No. 10,644

Claims priority, application Japan, Nov. 25, 1972, 47-118345;

Nov. 25, 1972, 47-118346


The portion of the term of this patent subsequent to Jul. 17,

1996, has been disclaimed.

Int. Cl.³ C03C 25/02

U.S. Cl. 65—3.11

12 Claims



1. A process for producing an optical transmission fiber comprising depositing a doped fused silica layer containing F and then a fused silica layer on to the inner surface of a pipe of fused silica or water-repellant glass and melting and spinning said pipe into a fiber, said doped fused silica layers being formed by (A) oxidizing halides, hydrides or organic compounds of Si with OF₂ or oxygen containing a gaseous fluorine compound, or (B) by the oxidation of SiF₄ to form doped fused silica containing F and depositing said doped fused silica containing F as a layer.

4,295,870

PROCESS FOR THE PRODUCTION OF GLASS FOR A GLASS WORKPIECE FOR USE IN DRAWING A GLASS LIGHT CONDUCTING FIBER OF A LOW ATTENUATION

Hartmut Schneider, and Egon Lebetzki, both of Munich, Fed. Rep. of Germany, assignors to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany


Filed Jul. 18, 1980, Ser. No. 169,951

Claims priority, application Fed. Rep. of Germany, Aug. 31, 1979, 2935347

Int. Cl.³ C03B 37/075

U.S. Cl. 65—3.12

7 Claims



1. In a process for the production of a workpiece from which a glass fiber light waveguide of a low attenuation is drawn, said process comprising providing a body, providing a reaction gas, producing an amorphous glass powder from the reaction gas by a chemical reaction, precipitating said amorphous glass

powder on the body, and subsequently transforming the precipitated powder into a clear glass layer, the improvement comprising the step of providing the reaction gas including the steps of providing a filter composed of a powder of amorphous glass of an identical nature to the amorphous glass being precipitated on the body from the chemical reaction of the reaction gas, and contacting the reaction gas with the powder of the filter prior to the step of producing the amorphous glass powder by the chemical reaction.

4,295,871

SIZING COMPOSITION AND GLASS FIBERS TREATED WITH THE AID OF SUCH COMPOSITION

Michel Droux, La Ravoire, and Gilbert Bocquet, Challes les Eaux, both of France, assignors to Saint-Gobain Industries, Paris, France

Filed Apr. 2, 1979, Ser. No. 26,430

Claims priority, application France, Apr. 3, 1978, 78 09726

Int. Cl.³ C03C 25/02

U.S. Cl. 65—3.41

4 Claims

1. In a method of manufacturing coated glass fiber comprising the following operations in sequence:

- (a) mechanically drawing filaments of molten glass at high speed
- (b) coating said filaments with an aqueous sizing composition
- (c) collecting said coated glass filaments during the drawing operation in the form of strands which are wound into cakes, dried and then collected into roving slivers in the shape of a ball, or directly collected into ball-shaped rovings and dried;

the improvement which comprises coating the filaments with an aqueous sizing composition comprising a system of cross-linking adhesive agents consisting essentially of at least one compound having a number of functional groups which are N-methylol functions or N-CH₂OR functions or both, with R being an alkyl radical, at least one acrylic polymer which may be modified or unmodified, and an amino-alkoxy-silane.

4,295,872

PRODUCING A MULTI-COLOR IMAGE IN POLYCHROMATIC GLASS


George A. Luers, Horseheads, N.Y., assignor to Corning Glass Works, Corning, N.Y.

Filed Mar. 10, 1980, Ser. No. 128,831

Int. Cl.³ C03B 25/00, 32/00; C03C 3/22, 3/26

U.S. Cl. 65—30.11

14 Claims



11. An improved method of producing a multicolor image in polychromatic glass wherein the glass is initially exposed to develop a latent image, then heat treated to develop nuclei, and thereafter further exposed and heat treated to develop a full color image, characterized in that the initial exposure is made

through at least one high contrast film positive embodying a subject pattern in the form of a half tone transparency, and being further characterized by the fact that the glass is melted under reducing conditions so that opal formation occurs in unexposed areas of the glass.

4,295,873

METHOD AND APPARATUS FOR REWORKING A HOLLOW WORKPIECE


Donald G. Trutner, Chatham, N.J., and Luke Thorington, Easton, Pa., assignors to Duro-Test Corporation, North Bergen, N.J.

Filed Apr. 12, 1979, Ser. No. 29,310

Int. Cl.³ C03B 23/00

U.S. Cl. 65—108

27 Claims



1. A method of reworking a hollow workpiece comprising the steps of

providing a first fluid of temperature sufficient to soften said workpiece, placing said workpiece within the cavity of a mold, and introducing said first fluid into the interior of said workpiece to soften said workpiece, said first fluid of sufficient density so that the static pressure thereof forces said softened workpiece into contact with the interior surface of said mold.

13. Apparatus for reworking a hollow workpiece having an opening therein comprising means defining first and second joinable mold portions, the interior portions thereof aligned upon joining to define a mold cavity for receiving therein said hollow workpiece,

a source of liquid, means for heating the liquid to a molten state, means for introducing the heated liquid through the workpiece opening into the interior of the workpiece at a temperature to soften the workpiece and to produce a hydrostatic pressure to expand the workpiece into the mold cavity shape, and means for separating said first and second mold portion a distance sufficient to allow placement of the original workpiece therebetween and removal of the expanded workpiece therefrom, and means for removing the heated liquid contained within said workpiece.

4,295,874

ARYL-N-(TRICHLOROVINYLTIO)-HALOMETHANE SULFONAMIDES

Laroy H. Edwards, Napa, Calif., assignor to Chevron Research, San Francisco, Calif.


Filed Jan. 28, 1980, Ser. No. 115,590

Int. Cl.³ A01N 33/00, 59/02; C07C 143/74

U.S. Cl. 71—67

9 Claims

1. A compound of the formula



wherein R is alkyl of 1 to 8 carbon atoms, cycloalkyl of 5 to 8 carbon atoms substituted with up to 2 alkyl of 1 to 3 carbon atoms, or phenyl substituted with up to 2 fluoro, chloro, bromo, iodo or alkyl of 1 to 4 carbon atoms; X is fluoro, chloro, bromo or iodo and R' is trichlorovinyl.

4,295,875

TETRAHYDRO-1,3-OXAZINES

Karl Eicken, Wachenheim; Wolfgang Rohr, Mannheim; Hans J. Pander, Roedersheim-Gronau, and Bruno Wuerzer, Limburgerhof, all of Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Fed. Rep. of Germany

Continuation of Ser. No. 57,129, Jul. 12, 1979, abandoned. This application Mar. 24, 1980, Ser. No. 132,986


Claims priority, application Fed. Rep. of Germany, Jul. 27, 1978, 2832890

Int. Cl.³ A01N 43/86; C07D 265/04, 265/12

U.S. Cl. 71—88


10 Claims

1. A tetrahydro-1,3-oxazine of the formula




where R denotes linear or branched haloalkyl of up to 3 carbon atoms, R¹, R², R³, R⁴ and R⁵ are identical or different and each denotes hydrogen or linear or branched alkyl of up to 3 carbon atoms, R⁶ denotes hydrogen, or R⁷ denotes hydrogen.

4. A herbicidal agent comprising, as herbicidal active ingredient, at least one substituted acetanilide of the formula



where R denotes hydrogen, linear or branched alkyl or alkoxy of up to 5 carbon atoms, R¹ denotes hydrogen, halogen, or linear or branched alkyl or alkoxy of up to 5 carbon atoms, R² denotes hydrogen, halogen, or linear or branched alkyl or alkoxy of up to 5 carbon atoms, R together with R² denotes an alkylene chain of up to 6 carbon atoms which is linked in the o-position and may be substituted by linear or branched alkyl of up to 4 carbon atoms, X denotes chlorine or bromine, and A denotes azole which is attached via a ring nitrogen atom and may be mono- or polysubstituted by halogen, phenyl, alkyl, alkoxy, alkylthio or perfluoroalkyl, each of up to 4 carbon atoms, cyano, carboxy, carbalkoxy of up to 4 carbon atoms in the alkoxy, or alkanoyl of up to 4 carbon atoms, or A denotes salts of azoles containing 2 or 3 nitrogen atoms, and, as antagonistic agent, at least one tetrahydro-1,3-oxazine of the formula



where R denotes linear or branched haloalkyl of up to 3 carbon atoms, R¹, R², R³, R⁴ and R⁵ are identical or different and each denotes hydrogen or linear or branched alkyl of up to 3 carbon atoms, R⁶ denotes hydrogen, or R⁷ denotes hydrogen.

4,295,876

N-(2,5-DIAZOLYL)-ALKYL-HALOACETANILIDES, COMPOUNDS AND HERBICIDAL COMPOSITIONS

Jörg Stetter; Klaus Ditzgen; Rudolf Thomas, all of Wuppertal; Ludwig Eue, Leverkusen, and Robert R. Schmidt, Cologne, all of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Apr. 23, 1980, Ser. No. 143,053


Claims priority, application Fed. Rep. of Germany, May 12, 1979, 2919293

Int. Cl.³ A01N 43/64, 43/82; C07D 249/04, 271/08

U.S. Cl. 71—90

38 Claims

1. N-(2,5-diazolyl) alkyl-haloacetanilide compounds of the formula



wherein

A is oxygen, sulfur or the grouping >N-R in which R is alkyl with up to 4 carbon atoms;

R¹ is hydrogen, alkyl with up to 4 carbon atoms, or alkoxy with up to 4 carbon atoms;

R² is hydrogen, alkyl with up to 4 carbon atoms, alkoxy with up to 4 carbon atoms, or fluorine, chlorine, or bromine;

R³ is hydrogen, alkyl with up to 4 carbon atoms, alkoxy with up to 4 carbon atoms, or fluorine, chlorine or bromine;

R⁴ is hydrogen or alkyl with up to 4 carbon atoms;

R⁵ is hydrogen, alkyl with up to 4 carbon atoms, alkoxy with up to 4 carbon atoms, dialkylamino with up to 4 carbon atoms in each alkyl group, fluorine, chlorine or bromine, cyano or alkoxy carbonyl with up to 4 carbon atoms in the alkoxy group; and

Z is chlorine, bromine or iodine.

32. Herbicidal composition comprising a herbicidally acceptable carrier and, in herbicidally effective amounts, an N-(2,5-diazolyl)alkyl-haloacetanilide compound as claimed in claim 1.

4,295,877

SELECTIVE HERBICIDAL METHOD IN COTTON AND SOYBEANS

Andre Thizy; Pierre Poignant, and Daniel Pillon, all of Lyons, France, assignors to Phylagro, Lyons, France

Continuation of Ser. No. 809,903, Jun. 24, 1977, abandoned, which is a continuation-in-part of Ser. No. 162,643, Jul. 14, 1971, abandoned. This application Dec. 13, 1978, Ser. No. 969,003

Int. Cl.³ A01N 47/30

U.S. Cl. 71—120

8 Claims

1. A method for weed control in dicotyledonous crops comprising pre-emergence and post-emergence application of a herbicidally effective amount of N-(4-isopropylphenyl)-N',N'-dimethylurea to a dicotyledonous crop selected from the group consisting of soybeans and cotton.

4,295,878

PROCESSES OF IRON SEGREGATION

Donald J. Fensom, South Yarra, Australia, assignor to ICI Australia Limited, Melbourne, Australia


Continuation of Ser. No. 922,351, Jul. 6, 1978, abandoned. This application Oct. 10, 1979, Ser. No. 83,516

Claims priority, application Australia, Jul. 8, 1977, PD0750

Int. Cl.³ C22B 1/8

U.S. Cl. 75—1 T

16 Claims



1. A process for the beneficiation of particles of titaniferous material comprising as a first component titanium oxide and as a second component metallic iron, said first and second components being in intimate association in said particles which process comprises first subjecting said particles to a non-oxidizing environment, said environment being characterized in that it is at an elevated temperature and comprises vapour derived from an iron chloride salt so that at least part of the said metallic iron is segregated by translocation from within said particles to the outside of said particles and secondly in a separation step separating the thus segregated metallic iron and relicts of said particles, wherein the particles of titaniferous material are the product of reduction of ores comprising iron titanium oxides, and substantially all of the iron component is reduced to the metallic state, wherein the elevated temperature used in said segregation step is in a range from the melting point of the iron salt to 1000° C., and wherein said segregation step takes place in the absence of a solid carbonaceous reducing agent and a flux.

2. A process for the beneficiation of pre-reduced particles of titaniferous material comprising as a first component titanium oxide and as a second component metallic iron, said first and second components being in intimate association in said particles which process comprises the steps of: (i) segregating at least part of said metallic iron from said pre-reduced particles by contacting said pre-reduced particles in a non-oxidizing environment at an elevated temperature with vapour derived from an iron chloride salt, whereby segregated metallic iron is translocated from within said particles to the outside of said particles; and (ii) separating the thus segregated metallic iron and relicts of said particles, wherein the elevated temperature used in said segregation step (i) is in a range from the melting point of the iron salt to 800° C.

3. A process according to claim 2 wherein said titaniferous material is ilmenite.

4,295,879

MANUFACTURE OF ACICULAR FERROMAGNETIC IRON PARTICLES

Werner Steck, Mutterstadt; Wilhelm Sarnecki, Limburgerhof; Laszlo Marosi, Ludwigshafen; Manfred Ohlinger, Frankenthal, and Horst Autzen, Freinsheim, all of Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Fed. Rep. of Germany

Filed Jul. 31, 1980, Ser. No. 174,240

Claims priority, application Fed. Rep. of Germany, Sep. 1, 1979, 2935357

Int. Cl.³ B22F 9/00

U.S. Cl. 75—0.5 AA

2 Claims

1. A process for the manufacture of acicular ferromagnetic iron particles, comprising:

- coating the surface of acicular particles of iron(III) oxide hydroxide and consisting of 20 to 100 percent by weight of lepidocrocite and 0 to 80 percent by weight of goethite with an alkaline earth metal compound and a monobasic, dibasic or tribasic aliphatic carboxylic acid of up to 6 carbon atoms, or an alkaline earth metal chelate of an organic compound containing at least two groups capable of chelating an alkaline earth metal cation, or a hydrolysis-resistant substance consisting of a phosphorus oxyacid, its ester or its inorganic salt and an aliphatic mono-, di- or tribasic carboxylic acid of 1 to 6 carbon atoms,
- heating the so-coated particles at a temperature of from 250° to 390° C. for a period of from 10 minutes to 10 hours in an atmosphere containing water vapor at a partial pressure of from 30 to 1013 mbar, and
- reducing the iron(III) oxide particles thus obtained with hydrogen at temperatures of from 275° to 425° C. to form acicular ferromagnetic iron particles.

4,295,880

APPARATUS AND METHOD FOR RECOVERING ORGANIC AND NON-FERROUS METAL PRODUCTS FROM SHALE AND ORE BEARING ROCK


John W. Horner, Jr., 150 Martin St., Longmont, Colo. 80501

Filed Apr. 29, 1980, Ser. No. 144,831

Int. Cl.³ C22B 4/00

U.S. Cl. 75—10 R

16 Claims



1. An apparatus for extracting organic products from mineral raw materials, comprising:
 - an electric induction furnace of the type having a refractory crucible and capable of maintaining a charge of non-ferrous metal in a molten state with natural induction stirring thereof;
 - an extraction chamber closing said induction furnace crucible against free entry of oxygen and providing a space

above the crucible for receiving a batch of mineral raw material to be processed;

a fractionating tower means for collecting organic vapors that, in use, may be generated from mineral raw material by the furnace;

a connecting means for directing organic vapors from the extraction chamber to the fractionating tower means;

skimming means for removing processed mineral raw material from the crucible charge and extraction chamber;

intake means for delivering mineral raw material to the crucible;

outlet means for receiving spent raw material from said skimming means and discharging the raw material from the extraction chamber; and

means for substantially preventing oxygen entry during inlet and discharge of the raw material.

4,295,881

PROCESS FOR EXTRACTION OF PLATINUM GROUP METALS FROM CHROMITE-BEARING ORE


James Saville, Stamford, Conn., assignor to Texasgulf Inc., Stamford, Conn.

Continuation of Ser. No. 38,820, May 14, 1979, abandoned, which is a continuation-in-part of Ser. No. 32,680, Apr. 23, 1979, abandoned. This application Jun. 10, 1980, Ser. No. 158,184

Int. Cl.³ C22B 4/04

U.S. Cl. 75—10 R

18 Claims



1. A process for recovering platinum group metals from chromite-bearing ores, comprising the steps of:
 - subdividing chromite-bearing ore containing one or more platinum group metals;
 - subjecting a slurry of said subdivided ore to high intensity magnetic force to separate said ore into a magnetic fraction containing a substantial quantity of the chromite originally present in the ore and a non-magnetic fraction containing a substantial quantity of the platinum group metals originally present in the ore;
 - subjecting said non-magnetic ore fraction containing a substantial quantity of the platinum group metals originally present in the ore to a flotation process to produce a concentrated fraction containing platinum group metals;
 - smelting the concentrate in a high intensity heating furnace in the presence of one or more collector materials for the platinum group metals to produce a slag layer and collector material layer containing the platinum group metals in association with said collector metal;
 - separating said collector material from said slag layers; and

(f) separating platinum group metal from the collector material layer.

4,295,882

STEEL MAKING PROCESS

Ryoji Arima, Kobe; Kazushige Umezawa, and Tokuzo Nisugi, both of Himeji, all of Japan, assignors to Nippon Steel Corporation, Tokyo, Japan


Filed Oct. 16, 1979, Ser. No. 85,255

Claims priority, application Japan, Oct. 24, 1978, 53-130039; Nov. 2, 1978, 53-134584; Dec. 15, 1978, 53-154769; Dec. 30, 1978, 53-162538; Dec. 30, 1978, 53-162539; Jan. 13, 1979, 54-1780

Int. Cl.³ C21C 7/02

U.S. Cl. 75—52

16 Claims



1. A steelmaking process for desiliconizing, dephosphorizing, desulfurizing and decarburizing molten iron from a blast furnace, comprising the following sequence of steps:

- (1) a first step of agitating the molten iron in a vessel, supplying the molten iron with both gaseous oxygen and an iron oxide contaminative material reducing the Si content in the iron to a value between 0.05 and 0.20% at a controlled bath temperature between 1480 and 1480° C., and discharging the resulting slag;
- (2) a second step of agitating the molten iron from the first step having a bath temperature between 1380° and 1380° C., supplying the molten iron with a flux consisting essentially of CaO and 0.2 to 0.5 parts by weight of CaCl₂ or KCl or both CaCl₂ and KCl per part by weight of CaO and a source of oxygen, maintaining the basicity of the processing slag between 3.5 and 8.0 and the T.Fe value between 3 and 10%, desulfurizing and dephosphorizing the iron with the same slag to reduce the P, S and Si contents to no higher than 0.025%, 0.020% and a trace, respectively, and to hold the C content not lower than 3.8%, and discharging the resulting slag; and
- (3) a third step of decarburizing the molten iron from the second step by blowing oxygen onto the melt without using a refining flux.

4,295,883

DEVICE AND METHOD FOR INTRODUCING GASES INTO MOLTEN METAL

Rajko Lajh, Sierre, Switzerland, assignor to Swiss Aluminium Ltd., Chippis, Switzerland

Filed Jun. 26, 1980, Ser. No. 163,177

Claims priority, application Switzerland, Jul. 10, 1979, 6447/79


Int. Cl.³ C22C 1/02

U.S. Cl. 75—68 R

13 Claims

1. A device for introducing gas into a metal melt comprising a fluid/gas-jet-mixing facility having a converging conical inlet, a cylindrical hollow center piece having a passageway of substantially constant diameter and a diverging conical outlet all disposed sequentially along a first axis, said cylindrical hollow center piece being provided with a plurality of channels for passing a gas to said passage, first feeding means for

feeding said melt to said converging conical inlet and into said passage such that said melt sucks said gas through said channels and into said passage for mixing said gas with said melt in said passage wherein the angle of said diverging conical outlet measured from said first axis is equal to about 7° to 15°, the



ratio of the diameter of said passage to the maximum diameter of both said converging conical inlet and said diverging conical outlet is about 1:4 to 1:6 and the ratio of the length of said converging conical inlet plus the length of said passage to the length of said diverging conical outlet is about 1:5 to 1:8.

4,295,884

PROCESS FOR TREATING A MOLTEN METAL OR ALLOY USING LIQUID AND SOLID FLUX

Jean-Marie Hicter, Coulevie-Volron, and Pierre Guert, Chambéry, both of France, assignors to Societe de Vente de l'Aluminium Pechiney, Paris, France


Filed Jul. 26, 1979, Ser. No. 61,023

Claims priority, application France, Jul. 31, 1978, 78 23197

Int. Cl.³ C22B 9/12, 21/06

U.S. Cl. 75—93 R

6 Claims



1. A process for treating molten metal for the removal of inclusions by means of liquid and solid metal halide-based fluxes comprising the steps of:

- establishing in a column having an inlet end and an outlet end a complex treatment bed comprising a packing of granules at least in part comprising solid flux supported upstream of the column outlet and immersed in a bath of liquid flux, the melting point of the solid flux being higher than the melting temperature of the liquid flux and the temperature of the molten metal to be treated;
- establishing downstream and adjacent the supported end of the solid flux granules a molten metal droplet coalescence zone comprising liquid flux;
- passing molten metal as a dispersion of droplets through the liquid flux-immersed solid flux granules and into the coalescence zone while maintaining the granules immersed in liquid flux; and
- recovering treated coalesced molten metal.

4,295,885

MATERIAL AND METHOD FOR SECURING BORON FILAMENTS TO EACH OTHER AND TO A SUBSTRATE AND CUTTING TOOLS THEREFROM

William T. Kaarlela, Fort Worth, Tex.

Division of Ser. No. 644,005, Dec. 24, 1975. This application Sep. 11, 1978, Ser. No. 941,513

The portion of the term of this patent subsequent to Nov. 30, 1993, has been disclaimed.

Int. Cl.³ B22F 1/00, 3/00

U.S. Cl. 75—208 R

16 Claims

1. A method of bonding of boron filaments to a substrate by a modified brazing which comprises:

- providing a substrate for receiving boron filaments to be bonded thereto;
- cleaning said substrate;
- providing boron filaments of a desired length;
- at least partially coating said filaments with a liquidized metals containing slip formulated from a metals mixture consisting essentially of from about 60% to about 75% by weight of copper, tin in an amount between about 20% to 35% by weight, the remainder being essentially titanium;
- said slip being further prepared from about 4 parts of the copper, tin and titanium mixture to about 1 part of about a 1/4 to about a 1% liquid solution of a suspension agent for holding said metals mixture in suspension in said solution;

F. placing said at least partially coated filaments on said substrate;

G. drying said coated filaments;

H. bonding said coated filaments to said substrate by liquid-phase-sintering; and

I. cooling said coated filaments on said substrate.

9. A method of bonding together a plurality of boron filaments to hold them fixed in an alloy metal matrix which comprises:

- providing boron filaments of a desired length;
- at least partially coating said filaments with a liquidized metals containing slip formulated from a metals mixture consisting essentially of from about 60% to about 75% by weight of copper, tin in an amount between about 20% to 35% by weight, the remainder being essentially titanium;
- said slip being further prepared from about 4 parts of the copper, tin and titanium mixture to about 1 part of about a 1/4 to about a 1% solution containing a suspension agent for holding said metals mixture in suspension in said solution;
- placing said at least partially coated filaments juxtaposed together in a group;
- drying said juxtaposed group of coated filaments to at least partially remove the liquid vehicle of said solution;
- bonding said coated filaments together by liquid-phase-sintering to alloy the metals mixture about the filaments; and
- cooling said filaments and said metals.

4,295,886

FLAME-RETARDANT POLYESTER FIBER COMPOSITIONS

John T. Gresham, Somerset, N.J., assignor to Avtex Fibers Inc., Valley Forge, Pa.

Filed Oct. 9, 1973, Ser. No. 404,198

Int. Cl.³ C08K 5/53


U.S. Cl. 106—18.19

8 Claims

6. Flame retardant yarns and fabrics comprising a combination of the flame-retardant polyester fiber composition and a member of the group consisting of cotton, rayon, nylon, acetate and acrylic fibers, and further comprising from about 95 to 80 parts by weight of the fiber-forming polyester which is a member of the group consisting of poly(ethylene terephthalate), poly(1,4-cyclohexylenedimethylene terephthalate) and poly(ethylene 2,6-naphthalenedicarboxylate), and 5 to 20 parts

by weight of a two-component flame-retardant additive consisting essentially of, by weight:

- from about 20 to 80% of 3,9-diphenyl-2,4,8,10-tetraoxa-3,9-diphosphaspiro[5.5]undecane-3,9-dioxide, and
- from about 80 to 20% of a polychlorinated or polybrominated diaryl compound containing at least 40% by weight chlorine or bromine and having the general formula



where X represents chlorine or bromine and a and a' are integers, the sum of which is from 3 to 10; b and b' represent zero and 1; R represents a member selected from the group consisting of C₁-C₄ alkyl radicals, C₁-C₄ acyl radicals, phenyl and benzoyl radicals and chlorinated and brominated phenyl and benzoyl radicals; Z represents a direct bond or a member selected from the group consisting of oxygen, carbonyldioxy, sulfonyl, C₁-C₄ alkylene, phenylene, and chlorinated phenylene, and ether linkages of the formula —CH₂O—, —CH₂OCH₂— and —C₆H₄CH₂OCH₂C₆H₄—.

4,295,887

METHOD FOR THE CONTROL OF MICRO-ORGANISMS
Alan J. Buckley, and Michael Singer, both of Manchester, England, assignors to Imperial Chemical Industries Limited, London, England

Continuation of Ser. No. 922,361, Jul. 5, 1978, abandoned, which is a continuation of Ser. No. 841,908, Oct. 13, 1977, abandoned, which is a continuation of Ser. No. 667,439, Mar. 16, 1976, abandoned. This application Jun. 25, 1979, Ser. No. 51,853

Claims priority, application United Kingdom, Apr. 10, 1975, 14795/75

Int. Cl.³ C08K 5/16, 5/36; C09D 5/14

U.S. Cl. 106—18.33

3 Claims

1. A water-based paint or adhesive which is susceptible to infection with Pullularia pullulans when applied to a substrate, and which has been protected against infection by Pullularia pullulans and other microorganisms by adding to the paint or adhesive an effective amount, in the range 1 to 10,000 parts per million based on the weight of the paint or adhesive, of 2,2'-bis(methylaminocarbonyl)diphenyldisulfide, said paint or adhesive being in a container.

4,295,888

SOLVENT COMPOSITIONS

Gillian M. Greenwood, and Alan Woodstock, both of Runcorn, England, assignors to Imperial Chemical Industries Limited, London, England

Filed Dec. 27, 1976, Ser. No. 757,776

Claims priority, application United Kingdom, Jan. 19, 1976, 1999/76

Int. Cl.³ C09D 11/00

U.S. Cl. 106—21

11 Claims

1. A composition comprising a chlorinated substantially straight chain paraffin solvent having a range of carbon atoms between 7 and 35 and of chlorine content 10% by weight to 72% by weight, a compound capable of colour forming on contact with an electron-acceptive substance, an antioxidant for said chlorinated paraffin solvent, and at least one of the following adjuvants present in said solvent in amount sufficient to at least reduce the tendency of the solution of paraffin, antioxidant and colour-forming compound to discolor:

- a barium, calcium or magnesium sulphate;
- a barium, calcium or magnesium phenate of the structure:

4,295,890

SUBMICRON BETA SILICON CARBIDE POWDER AND SINTERED ARTICLES OF HIGH DENSITY PREPARED THEREFROM

Frederick G. Stroke, McMurray, Pa., assignor to PPG Industries, Inc., Pittsburgh, Pa.


Continuation of Ser. No. 637,342, Dec. 3, 1975, abandoned. This application Oct. 31, 1977, Ser. No. 847,347

Int. Cl.³ C04B 35/56

U.S. Cl. 501—90

25 Claims

1. A substantially pure submicron boron-containing beta silicon carbide powder composition consisting essentially of silicon carbide powder substantially all of the beta crystalline form, said powder having a surface area of between about 3 and about 15 square meters per gram, the number mean particle size of the silicon carbide particles comprising the powder being between 0.08 and 0.8 microns, coformed homogeneously distributed boron-containing additive in an amount equivalent to between 0.15 and 0.25 weight percent boron, based on the silicon carbide, and between 0.05 and 1.5 weight percent free carbon, based on the silicon carbide.



where M is an atom of barium, calcium or magnesium, R₁ is hydrogen or an alkyl group containing 1 to 10 carbon atoms and R₂ is an alkyl group containing 1 to 10 carbon atoms; and (c) a nitrogen containing derivative of an alkenyl succinic anhydride, said derivative being obtained by the reaction of polyisobutylene with maleic anhydride followed by further reaction with tetraethylene pentamine.

4,295,889

RECORDING LIQUID COMPOSITION

Tsuyoshi Eida, Chiba; Masahiro Haruta, Funabashi; Yasuhiro Yano; Yoji Matsufuji, both of Tokyo, and Tokuya Ohta, Yokohama, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan


Filed Nov. 28, 1979, Ser. No. 97,920

Claims priority, application Japan, Dec. 1, 1978, 53-148679; Jun. 22, 1979, 54-78952; Jun. 22, 1979, 54-78953; Sep. 11, 1979, 54-116427


Int. Cl.³ C09D 11/00

U.S. Cl. 106—22

30 Claims



1. A recording liquid composition for use in a recording system of the type in which the recording liquid composition is jetted from a small orifice in a form of droplet flying toward a recording material on which an image is to be printed, said recording liquid composition comprising, as its recording agent component, a compound of the general formula (B):



wherein

Q₃ and Q₆ each represents a substituted or unsubstituted phenyl or naphthyl group; Q₄ and Q₅ each represents a substituted or unsubstituted 1,4-phenylene or 1,4-naphthylene group;

R₅ and R₆ are selected from hydrogen, hydroxyl and amino group;

R₇ and R₈ each represents hydrogen atom or sulfo group in a form of sodium salt or quaternary ammonium salt;

X is —NH—, —N=N— or —CH=CH— and n is 0 or 1 provided that when n is 0, Q₄ and Q₅ are not unsubstituted 1,4-phenylene at the same time.

4,295,891

BLANKET POWDER FOR COVERING A MOLTEN METAL BATH

Jean-Charles Daussan; Gerard Daussan, both of Metz, and André Daussan, Longeville les Metz, all of France, assignors to Daussan et Compagnie, Woippy, France

Filed Aug. 5, 1980, Ser. No. 175,680

Claims priority, application France, May 16, 1980, 80 10983

Int. Cl.³ C04B 35/52

U.S. Cl. 501—99

9 Claims

1. A blanket powder for covering a molten metal bath, comprising a cereal-hull ash, wherein said powder further contains approximately 5 to 50% by weight of non-calcined cereal hulls.

4,295,892

CORDIERITE CERAMIC HONEYCOMB AND A METHOD FOR PRODUCING THE SAME

Tadaaki Matsuhisa; Shigeo Soejima, and Noboru Yamamoto, all of Nagoya, Japan, assignors to NGK Insulators, Ltd., Nagoya, Japan

Continuation of Ser. No. 772,953, Feb. 28, 1977, abandoned, which is a continuation of Ser. No. 674,933, Apr. 8, 1976, abandoned. This application Dec. 20, 1978, Ser. No. 971,485

Int. Cl.³ C04B 35/18

U.S. Cl. 501—120

3 Claims

1. Cordierite ceramic honeycomb having a softening shrinkage at 1,450° C. of not more than 0.5% which consists mainly of cordierite in crystal phase and contains 8 to 20% by weight of at least one crystal selected from the group consisting of spinel, mullite and corundum has a thermal expansion coefficient at a temperature range of 25°-1,000° C. being not more than 22×10⁻⁷(1/°C.).

4,295,893

ALUMINA-CONTAINING CALCIUM SILICATE AND PROCESS FOR PRODUCING SAME

Akira Takahashi, and Kenichi Ohashi, both of Gifu, Japan, assignors to Kabushiki Kaisha Osaka Packing Seizosho, Osaka, Japan

Filed Nov. 15, 1979, Ser. No. 94,500

Int. Cl.³ C04B 7/02

U.S. Cl. 106—120

21 Claims

1. Super-lightweight secondary particles of alumina-containing calcium silicate characterized in that the particles are composed of alumina-containing calcium silicate crystals having an index of crystallite antigrowth of at least 8 and interlocked with one another in the form of a globular shell, the particles being about 5 to about 70 μm in diameter, up to about 0.13

g/cm³ in apparent density and at least 10 g per particle in initial breaking load.

4,295,894

METHOD OF PREPARING SOLUBLE COLLAGEN FIBERS

Gheorge Cloca, Belleville, and Marcel Siegler, North Bergen, both of N.J., assignors to Seton Company, Newark, N.J.

Filed Nov. 19, 1979, Ser. No. 95,391

Int. Cl.³ C08L 89/06; C08K 3/24, 3/20, 3/30

U.S. Cl. 106—155

16 Claims

1. A method of forming soluble collagen fiber from a raw animal hide comprising:

- treating a raw hide with an aqueous solution of an alkali metal hydroxide and an organic dehydrating agent to remove the hair and fat therefrom, to yield a substantially hair and fat-free corium;
- stabilizing the interfibrillar bonds of the collagen in the corium with an aqueous solution of an alkali sulfate;
- neutralizing the corium;
- dissolving the corium in an aqueous acid solution to yield a collagen solution;
- precipitating collagen fibers from the solution; and
- drying the collagen fibers.

4,295,895

METHOD FOR STEAM CLEANING OF COMPRESSORS


Gunnar Kongshaug, Porsgrunn, Norway, assignor to Norsk Hydro a.s., Oslo, Norway

Filed Mar. 28, 1980, Ser. No. 136,070

Int. Cl.³ B08B 3/00

U.S. Cl. 134—22 R

8 Claims



1. In a method for removing and preventing the formation of salt deposits in critical sections of a plant where process gases containing impurities including ammonium nitrate are transferred and compressed, the improvement which comprises supplying steam to said sections in such amounts that a water vapour pressure is established in excess of the saturated water vapour pressure above the salt deposits at the existing temperatures.

4,295,896

METHOD FOR MAKING METAL ALLOY COMPOSITIONS AND COMPOSITION

Merton C. Flemings, and Frank E. Goodwin, both of Cambridge, Mass., assignors to Massachusetts Institute of Technology, Cambridge, Mass.

Continuation-in-part of Ser. No. 20,101, Mar. 12, 1979, abandoned. This application May 14, 1979, Ser. No. 39,226


Int. Cl.³ C22F 1/04

U.S. Cl. 148—1

34 Claims

1. The process for forming a metal alloy composition free of oxide inclusions, free of porosity and containing solutes derived from said alloy composition in an amount greater than 90 weight percent of the amount soluble at the temperature of maximum solubility and containing less than 2 volume percent of undissolved second phase which comprises heating a first alloy from the nonequilibrium solidus temperature to form a

solid-liquid composition, subjecting said solid-liquid composition to pressure for a time sufficient to overcome the inherent strength of the solid, to convert dendrites in the solid to a fine grain structure, to homogenize and compact the composition of the dendrites, and to cause the liquid to flow through and out of said solid and preventing the formation of secondary



phase material either by rapidly quenching said solid or by cooling said solid followed by heat treating said cooled solid at a temperature less than that at which liquid metal from said alloy forms for a period of time to dissolve substantially all said secondary phase into said primary phase and rapidly quenching said heat treated solid to form a cooled solid.

4,295,897

METHOD OF MAKING CMOS INTEGRATED CIRCUIT DEVICE


Graham S. Tubbs, Houston, and James E. Ponder, Cat Spring, both of Tex., assignors to Texas Instruments Incorporated, Dallas, Tex.

Filed Oct. 3, 1979, Ser. No. 81,513

Int. Cl.³ H01L 21/22, 29/78

U.S. Cl. 148—1.5

4 Claims



1. A method of making complementary insulated gate field effect transistors in an integrated circuit comprising the steps of:

- (a) introducing N-type impurity into a selected area of a face of a P-type semiconductor body to provide a tank region for forming a P-channel transistor,
- (b) selectively growing thick field oxide using an oxidation mask to provide a first enclosed surface area on said face spaced from said tank region and a second enclosed surface area on said face within said tank region,
- (c) depositing a layer of polycrystalline silicon on said face over a thin gate insulator and patterning the polycrystalline silicon to provide a gate of an N-channel transistor in said first surface area and a gate of a P-channel transistor in said second surface area,
- (d) introducing P-type impurity into the second surface area to produce source and drain regions of the P-channel transistor while masking the first surface area,
- (e) and introducing N-type impurity into the first surface

area to produce source and drain regions of the N-channel transistor while making said second surface area, both the gate of the N-channel transistor and the gate of the P-channel transistor being doped with N-type impurity upon the step of introducing N-type impurity into the first surface area.

4,295,898

METHOD OF MAKING ISOLATED SEMICONDUCTOR DEVICES UTILIZING ION-IMPLANTATION OF ALUMINUM AND HEAT TREATING

Masakatsu Yoshida, Ibaraki; Yoshihiko Tochio, Kyoto, and Atsutomu Tohi, Hirakata, all of Japan, assignors to Matsushita Electronics Corporation, Kadoma, Japan


Filed May 8, 1980, Ser. No. 147,715

Claims priority, application Japan, May 15, 1979, 54-60131

Int. Cl.³ H01L 21/265, 21/20

U.S. Cl. 148—1.5

3 Claims



1. Method of making semiconductor device comprising the steps of
ion-implanting Al-ions in a predetermined part of the surface of a p-type silicon substrate,
heat treating said substrate to diffuse said Al-ions thereby forming p⁺-type buried region in said substrate,
epitaxially growing an n-type epitaxial layer having a predetermined thickness on said p-type silicon substrate,
ion-implanting Al-ions on the part of the surface of said n-type epitaxial layer over said p⁺-type buried region thereby to form p⁺-type surface ion-implanted region,
heat treating said substrate and the n-type epitaxial layer thereby to make diffusions of Al-ions from said buried region and said surface ion-implanted region into said n-type epitaxial layer, thereby forming a p⁺-type isolation region continuously across said n-type epitaxial layer.

4,295,899

PROCESS FOR COATING IRON AND STEEL

Dieter Oppen, Rodgau, Fed. Rep. of Germany, assignor to Hooker Chemicals & Plastics Corp., Madison Heights, Mich.

Filed Feb. 19, 1980, Ser. No. 122,403

Claims priority, application Fed. Rep. of Germany, Feb. 23, 1979, 2907093

Int. Cl.³ C23F 7/10

U.S. Cl. 148—6.16

5 Claims

1. A process for producing non-metallic electrical resistance coatings on the surface of iron or steel, comprising contacting a composition free of organic components and comprising an alkali silicate water-glass, an alkali polyphosphate and insoluble Cr₂O₃ pigment wherein the molar ratio of Cr₂O₃:P₂O₅ (equivalent):SiO₂ is 0.005 to 1.5:0.005 to 0.1:1 with the surface at a viscosity of between 400 and 1000 mPa.S, (as measured at 20° C.), and baking the thus treated surface at a temperature of between 150° and 500° C.

4,295,900

ROLLED WIRE HAVING A FINE-GRAIN STRUCTURE

Nils-Gunnar Malmgren; Barry Solly, both of Fagersta, and Stig Tärnblom, Söderbärke, all of Sweden, assignors to Fagersta AB, Sweden

Filed May 26, 1978, Ser. No. 909,959

Claims priority, application Sweden, Jun. 14, 1977, 7706881

Int. Cl.³ C21D 9/52

U.S. Cl. 148—12 B

2 Claims

1. A hot rolled wire rod of fine-grain structure consisting of stainless steel and intended for the manufacture of drawn spring wire and rope wire of high mechanical strength and high ductility, characterized in that said wire rod contains 0.04–0.07% C, 18–19% Cr and 8–9.5% Ni wherein a Cr-content of 18% corresponds to a Ni-content of 8.0–8.8% when the C-content is 0.04% and to a Ni-content of 8.8–9.5% when the C-content is 0.07%, and a Cr-content of 19% corresponds to a Ni-content of below 8.3% when the C-content is 0.04% and to a Ni-content of 8.4–9.2% when the C-content is 0.07%, said wire rod having a uniform grain size along said wire rod, said grain size being 8–13 ASTM.

4,295,901

METHOD OF IMPARTING A FINE GRAIN STRUCTURE TO ALUMINUM ALLOYS HAVING PRECIPITATING CONSTITUENTS

Wayne M. Robertson, and John A. Wert, both of Thousand Oaks, Calif., assignors to Rockwell International Corporation, El Segundo, Calif.

Filed Nov. 5, 1979, Ser. No. 91,234

Int. Cl.³ C22F 1/04

U.S. Cl. 148—12.7 A

5 Claims

1. An improvement in a method of imparting a fine grain structure to an aluminum alloy having a precipitating constituent, said method having steps of:

- providing an aluminum alloy having a precipitating constituent;
 - dissolving at least some of said precipitating constituent in said alloy by heating said alloy to a solid solution temperature;
 - cooling said alloy to a temperature below said solid solution temperature;
 - overaging said alloy at an overaging temperature to form precipitates;
 - plastically straining said alloy; and
 - recrystallizing said alloy by heating it above the minimum recrystallization temperature, whereby said precipitates form nuclei for the recrystallization and controlled growth of a fine grain structure;
- said improvement being characterized in that said step of plastically straining said alloy comprises:
- heating said alloy to a temperature in the range above said overaging temperature and below said alloy's solvus temperature and reducing its cross-sectional area a total of 40% minimum at a sufficiently high rate to introduce strain energy into said alloy so that complete recovery of said alloy does not occur.

4,295,902

METHOD OF MANUFACTURING ROLLED STEEL PRODUCTS WITH HIGH ELASTIC LIMIT

Marios Economopoulos, Liege, Belgium, assignor to Centre de Recherches Metallurgiques-Centrum voor Research in de Metallurgie, Brussels, Belgium

Filed Feb. 26, 1980, Ser. No. 124,794

Claims priority, application Belgium, Feb. 28, 1979, 874535

Int. Cl.³ C21D 1/18; C22C 38/46

U.S. Cl. 148—144

4 Claims

1. A method of manufacturing a rolled steel product having an elastic limit in the range from about 500 to about 1200 MPa, the method comprising subjecting a rolled steel product to intense cooling from above its austenitization temperature in

such a way that at least part of the surface of the product is subjected to martensitic and/or bainitic quenching while the remainder of the product stays at a temperature sufficient to allow tempering of the quenched surface to occur subsequently by conduction of heat from the said remainder to the quenched surface, the rolled steel product containing 0.10 to 0.50% C, 0.90 to 1.50% Mn, 0.10 to 0.45% Si, 0.20 to 0.70% Ni, 0.10 to 0.80% Cr, and 0.02 to 0.10% V.

4,295,903

CONTAINER SPINNING APPARATUS FOR CONTAINER MANUFACTURING MACHINE OR THE LIKE


Silvio T. Farfaglia, Fulton, N.Y., assignor to Phillips Petroleum Company, Bartlesville, Okla.

Filed May 17, 1979, Ser. No. 39,929

Int. Cl.³ B65B 7/28; B05B 13/02

U.S. Cl. 156—69

19 Claims



1. Apparatus for clamping and rotating containers comprising:

- a support;
- table means rotatably positioned on said support for supporting a container for rotation about an axis of rotation intersecting said container;
- means on said support for mounting said table means on said support whereby said table means is free to rotate about said axis of rotation;
- drive means operatively connected to said table means for rotating said table means about said axis of rotation;
- a plurality of jaw means each movably mounted on said table means for moving between a first position wherein said jaw means are retracted out of engagement with a container, and a second position wherein said jaw means are actuated into engagement with a container;
- jaw-positioning means engageable with said plurality of jaw means and adapted for reciprocal movement coaxial with said axis of rotation of said table means for positioning said plurality of jaw means in the first positions thereof in a first position of said jaw-positioning means and, alternatively, for positioning said plurality of jaw means in the second positions thereof in a second position of said jaw-positioning means; and
- actuator means operatively related to said jaw-positioning means for actuating said jaw-positioning means into said first position thereof and, alternately, actuating said jaw-positioning means into said second position thereof.

12. A method of applying sealant to the inside of a container at the juncture between the inner surfaces of the bottom closure member and the side wall thereof, comprising:

- (a) positioning the container on a table adapted for rotation about an axis of rotation intersecting said container;
- (b) mechanically clamping the container on said table so that the container rotates with said table;
- (c) rotating said table and the container clamped thereto about the axis of rotation;
- (d) dispensing a stream of sealant on the juncture between the inner surfaces of the bottom closure member and the side wall of the container during rotation thereof so as to apply a continuous coating of sealant along the full length of said juncture;

- (e) stopping the rotation of said table and the container after dispensing the stream of sealant; and
- (f) releasing the container from thus stopped table.

4,295,904

METHOD OF HEAT SEALING A FILM TO THE LIP OF A CUP

Paul F. Schmit, Stillwater, Minn., assignor to Minnesota Mining and Manufacturing Company, St. Paul, Minn.


Division of Ser. No. 917,586, Jun. 21, 1978, Pat. No. 4,216,050.

This application Apr. 28, 1980, Ser. No. 144,613

Int. Cl.³ B29C 27/02; B65B 7/28

U.S. Cl. 156—69

2 Claims



1. A method for sealing to the lip of a cup a piece of heat sealable film which will shrink a small amount when heated to normal heat sealing temperatures so as to draw attention to a feature in the film, said method comprising the steps of:

- positioning a piece of the film adjacent the lip of the cup and over the cup opening with the feature surrounded by the lip of the cup;
- pushing the piece of film slightly into the opening of the cup; pressing the film into contact with the lip of the cup while heating the film to a first temperature adapted to fuse it to the lip; and
- heating a first portion of the film around the feature to a second temperature which exceeds said first temperature to shrink said first portion of the film and gather a portion of the piece of film surrounding said first portion into outwardly radially extending ridges and grooves.

4,295,905

FILL STRAND TRANSFER PROCESS FOR MAKING NON WOVEN FABRICS


Hollis H. Bascom, Livermore; Stephen Matweyou, Oakland; Alan J. Andersen, Livermore, and John J. Greci, Livermore, all of Calif., assignors to Orcon Corporation, Union City, Calif.

Filed Dec. 14, 1979, Ser. No. 103,621

Int. Cl.³ B65N 81/00

U.S. Cl. 156—174

14 Claims



1. A method of transferring fill strands to form a non woven fabric and comprising,

- guiding warp strands into the nip of a set of pressure rolls, supporting a preformed, planar set of adhesive coated or impregnated fill strands in a fixed orientation, a fixed spacing, and a fixed tension of the fill strands near the pressure rolls so that said set of fill strands can be subsequently transferred as a set with said fixed orientation, spacing and tension to said warp strands in the nip of the pressure rolls,

feeding said preformed, planar set of fill strands having said fixed orientation, spacing and tension into the nip of the pressure rolls with the warp strands, and transferring the fill strands with said fixed orientation, spacing and tension to the warp strands to form the fabric by causing the adhesive on the fill strands to adhere to the warp strands under the effect of the pressure produced in the nip of the pressure rolls.

4,295,906

METHOD FOR PRODUCING A MOTION PICTURE SCREEN

Wataru Shimada; Susumu Hoshinouchi; Kenji Kawaguchi, and Akio Yoshida, all of Amagasaki, Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan


Filed Feb. 28, 1980, Ser. No. 125,744

Claims priority, application Japan, Mar. 27, 1979, 54-36631

Int. Cl.³ G03B 21/56, 21/60

U.S. Cl. 156—214

6 Claims



1. A method for producing a motion picture screen comprising the steps of preparing a two-dimensional cutter the cutting edge of which comprises a number of circular arcs, connected together in a smooth wavy line, in the X-Z plane in a space coordinate system, each of said arcs having a predetermined curvature and a predetermined center angle, and the centers of the neighbouring ones of said circular arcs being located on opposite sides of said line, placing a workpiece from which said motion picture screen is to be produced and said two-dimensional cutter in the X-Z and X-Y planes, respectively, and machining the surface of said workpiece by said two-dimensional cutter while moving said workpiece and said cutter for producing a relative motion therebetween for forming a machined surface which comprises smooth connected wavy curves in sections parallel with both the X-Z and Y-Z planes, said curves respectively comprising a number of circular arcs, each of said last mentioned circular arcs having a predetermined curvature and a predetermined center angle, and the centers of the neighbouring ones of said circular arcs being positioned on opposite sides of said curves.

4,295,907

METHOD OF MAKING GLASS FIBER REINFORCED LAMINATE

Howard P. Cordts, Grafton, and Joan E. Karloske, Saukville, both of Wis., assignors to Freeman Chemical Corporation, Port Washington, Wis.

Filed Dec. 28, 1979, Ser. No. 107,834

Int. Cl.³ B29C 19/00


U.S. Cl. 156—246

5 Claims

1. In the method for manufacturing glass fiber reinforced plastic laminate which comprises applying glass fibers and unpolymerized unsaturated polyester resin syrup between two carrier films and thereafter heating the resulting sandwich until the said unsaturated polyester resin syrup is cured and thereafter removing the carrier films and recovering as a product a sheetlike mass of glass fibers which are embedded within the cured unsaturated polyester resin syrup, the improvement comprising:

- applying to a first of said carrier films a resin layer of UV

curable resinous composition containing an ultraviolet radiation sensitizer, exposing the said resin layer and the said first carrier film to ultraviolet radiation until the said resin layer is at least partially polymerized,



thereafter applying the said glass fibers and unsaturated polyester resin syrup to the said resin layer and thereafter applying the second of said carrier films to complete the sandwich; and subsequently heating the sandwich to cure the said unsaturated polyester resin syrup and to polymerize any unpolymerized components of the said resin layer.

4,295,908

METHOD AND APPARATUS FOR HEAT SEALING A PLURALITY OF SETS OF CONTINUOUS PLASTIC STRIPS TOGETHER BY RADIO FREQUENCY ENERGY


Hans G. Schaefer, Lakewood, and Alfred Langer, Westminster, both of Calif., assignors to Manhattan R. F. Die Company, South Gate, Calif.

Filed Dec. 10, 1979, Ser. No. 102,130

Int. Cl.³ B29C 27/04; B32B 31/18, 31/20

U.S. Cl. 156—251

27 Claims



1. Radio frequency powered apparatus for heat sealing a plurality of sets of plastic sheets together to form simultaneously a plurality of separate items comprising:

- at least three superimposed platens including an upper platen, a lower platen and an intermediate platen normally resiliently supported between and spaced from said upper and lower platens and including means electrically isolating said platens from one another;
- heat sealing die means on the opposed faces of said intermediate platen shaped to cooperate with the juxtaposed face of the adjacent one of said upper and lower platens to heat seal the sheets of each set of plastic sheets together in areas thereof held in pressurized contact with one another;
- a source of radio frequency energy having the output thereof connected to energize said platens when the same are held pressed against respective sets of plastic sheets on the remote sides of said sealing die means; and
- means supporting said platens for reciprocation toward one another to compress the sheets of said sets of sheets together in areas in contact with said die means while said platens are energized with radio frequency energy to heat seal the sheets of each of said sets of sheets together.

22. That method of simultaneously heat sealing two sets of a plurality of superimposed plastic strips together in predetermined selected areas thereof in successive heat sealing cycles which comprises:

- advancing separate sets of superimposed plastic strips past the opposite faces of a platen having heat sealing and tear forming dies fixed to and protruding from a respective face thereof and which platen is floatingly positioned directly between and electrically isolated from the upper

and lower platens of a radio frequency powered heat sealing press; and closing said upper and lower platens toward one another while energizing the same with radio frequency power thereby to heat seal said sets of strips together in predetermined selected areas before indexing said sets of strips forwardly for the next heat sealing cycle.

4,295,909

CURABLE POLYBUTADIENE-BASED RESINS HAVING IMPROVED PROPERTIES

Louis J. Baccei, Farmington, Conn., assignor to Loctite Corporation, Newington, Conn.

Continuation of Ser. No. 64,170, Aug. 6, 1979, abandoned, which is a continuation of Ser. No. 813,207, Jul. 5, 1977, abandoned, which is a continuation-in-part of Ser. No. 546,250, Feb. 3, 1975, abandoned. This application Oct. 10, 1980, Ser. No. 195,986

Int. Cl.³ C09J 5/02; C08F 8/30; C08L 75/04

U.S. Cl. 156—307.3

27 Claims

1. An adhesive and sealant composition having improved thermal and impact properties and curable through gaps of more than 40 mils, comprising:

I. a polymerizable product corresponding in structure to a reaction product of:

(a) a polybutadiene polyol of polyamine comprising about 5 to about 150 butadiene units and having at least about 70 percent of the butadiene units in the 1,4-configuration and selected from the group consisting of polybutadiene, butadiene-acrylonitrile copolymers, and butadiene-styrene copolymers, and,

(b) a molar excess of a reaction product of: a molar excess of an aromatic or cycloaliphatic polyisocyanate with a compound selected from the group consisting of an aromatic or cycloaliphatic polyol,

the product of (a) and (b) subsequently being reacted with a molar excess of a hydroxyalkyl acrylate, a hydroxyalkyl methacrylate, an aminoalkyl acrylate, or an aminoalkyl methacrylate; and

II. a free radical initiator.

4,295,910

PROCESS FOR PRODUCTION OF VINYL FILM-CELLULOSIC LAMINATES AND LAMINATES PRODUCED THEREBY

James Cooley, and Ozzie Fogle, both of Orangeburg, S.C., assignors to Champion International Corporation, Stamford, Conn.

Filed Apr. 25, 1980, Ser. No. 143,625

Int. Cl.³ C09J 5/04

U.S. Cl. 156—314

9 Claims

1. A process for bonding a polymeric film to a cellulosic substrate which comprises:

(A) coating said substrate with an organic polyisocyanate having at least two active isocyanate groups per molecule; (B) coating vinyl acetate-ethylene copolymer emulsion adhesive onto said polyisocyanate to form an interlaminar adhesive layer; and

(C) applying a vinyl polymeric film to said interlaminar adhesive layer; whereby a permanently bonded laminate is formed.

4,295,911


PROTECTIVE LAYER FOR SURFACE SEALS IN BUILDING CONSTRUCTION, UNDERGROUND CONSTRUCTION, AND CIVIL ENGINEERING CONSTRUCTION

Karl Haage, Troisdorf-Spich, and Dieter Scharff, Troisdorf-Sieglar, both of Fed. Rep. of Germany, assignors to Dynamit Nobel Aktiengesellschaft, Troisdorf, Fed. Rep. of Germany Division of Ser. No. 818,232, Jul. 22, 1977, Pat. No. 4,239,795, which is a continuation of Ser. No. 596,765, Jul. 17, 1975, abandoned. This application May 30, 1980, Ser. No. 155,000 Claims priority, application Fed. Rep. of Germany, Jul. 17, 1974, 2434328

Int. Cl.³ C09J 5/04, 5/02

U.S. Cl. 156—315

2 Claims



1. A process for the continuous production of a protective covering, wherein a first topcoat layer is applied as a soft PVC plastisol onto an endless carrier web at room temperature; gelling is initiated during a short-term heat application of about 160°–200° C.; whereupon a second topcoat layer is applied to the first topcoat layer and a lattice-like fabric is placed on said second topcoat layer, which is still in the un-gelled condition; then gelling is initiated in the first and second topcoat layers by heating in a temperature range of between 160° C. and 250° C., while simultaneously the bonding to the lattice-like fabric is taking place, said lattice-like fabric being a resilient fabric having fibers joined together at junctions that yield under the effect of a load, and said topcoat layers having differing composition, the first topcoat layer having a higher weatherability due to the addition of stabilizers and a lower filler content as compared to the second topcoat layer.

4,295,912

APPARATUS AND PROCESS FOR LAMINATING COMPOSITE TAPE


Carmen D. Burns, San Jose, Calif., assignor to National Semiconductor Corporation, Santa Clara, Calif.

Continuation-in-part of Ser. No. 921,644, Jul. 3, 1978, abandoned. This application Jul. 17, 1979, Ser. No. 58,404

Int. Cl.³ B32B 31/08, 31/20; B65H 17/40

U.S. Cl. 156—324

17 Claims



1. The process for precision laminating at least a pair of strips having substantially dissimilar mechanical properties and at least one of which has a surface coating of unactivated but activatable adhesive, said strips further having mating edge located perforations, said process comprising:

advancing said strips together in intermittent fashion, said intermittent advancing operating to advance said strips a

predetermined distance in a cyclic manner having a predetermined rest interval; aligning said strips to obtain registry therebetween; pressing a first bonding tool against said strips during said rest interval, said first bonding tool being contoured to contact a limited area of said strips; heating said strips to at least partly activate said adhesive during said rest interval and while said strips are in registry to create a tack bond between said strips; pressing a second bonding tool against said strips to heat and activate said adhesive during said rest interval, said second bonding tool being contoured to contact said strips over an area having a length of at least said predetermined distance; and heating said strips to a second temperature to activate said adhesive over the area of said second bonding tool whereby said strips are fully laminated together.

9. Apparatus for precision laminating at least a pair of strips having substantially dissimilar mechanical properties and at least one of which has a surface coating of unactivated but activatable adhesive, said strips further having mating edge located perforations, said apparatus comprising:

means for advancing said strips simultaneously through said apparatus on an intermittent cycle having a transport interval and a rest interval, said transport interval producing a predetermined advance;


means for locating said strips to register said perforations; means for pressing a first bonding tool against said strips during said rest interval said first bonding tool having a surface that contacts said strips over a limited area portion;

means for heating said strips to a first temperature to at least partly activate said adhesive and tack said strips together over a limited area;

means for pressing a second bonding tool against said strips, said second bonding tool having an area including the width of said strips and a length at least equal to said predetermined advance; and

means for heating said strips to a second temperature to activate said adhesive and to laminate said strips substantially over their entire area.

from the dip tank, whereby the dip tank can be drained when the printer is turned off and the dip tank will be filled to operating level when the printer is operated, without continuous operation of said pump means.



4,295,914

APPARATUS FOR APPLYING SEALANT MATERIAL TO A WORKPIECE


John C. Checko, 5 Northern Dr., Bridgewater, N.J. 08807

Filed Aug. 22, 1979, Ser. No. 68,691

Int. Cl.³ B32B 31/04, 31/14

U.S. Cl. 156—357

13 Claims



1. Apparatus for applying sealant material to a workpiece assembly, wherein said workpiece assembly includes two planar members separated by at least one spacer, comprising: a work supporting surface for receiving said workpiece assembly;

means for aligning said planar members and said spacer of said workpiece assembly relative to each other and in a fixed position relative to a sealant applying means; said aligning means including stop members for engaging an exposed edge of said workpiece assembly;

means for moving said stop members out of engagement with said exposed edge of said workpiece assembly; means for clamping said workpiece assembly in said fixed position on said supporting surface with at least one edge exposed for receiving sealant material;

means for applying sealant material being mounted to face the exposed edge of said workpiece assembly and operable to apply sealant material when said stop members are moved out of engagement with the exposed edge of said workpiece assembly; and

means for moving said sealant applying means relative to said workpiece assembly to apply sealant material along the edge of said workpiece assembly.

4,295,913

ELECTRICALLY OPERATED DEVICE, ESPECIALLY DUPLICATING DEVICE, WITH A RECEPTACLE TO ACCOMMODATE FLUID FOR THE CHEMICAL TREATMENT OF OBJECTS

Horst Purr, Tennenbronn; Manfred Kistler, Eisenbach, and Rolf Müller, St. Georgen, all of Fed. Rep. of Germany, assignors to Mathias Bauerle GmbH, Georgen, Fed. Rep. of Germany Filed Feb. 28, 1980, Ser. No. 125,666

Claims priority, application Fed. Rep. of Germany, Mar. 3, 1979, 2908283

Int. Cl.³ B41C 1/10

U.S. Cl. 156—345

15 Claims

1. An electrically operated offset printer including means for etching offset printing films, said means for etching comprising a dip tank having means for passing said offset printing films therethrough, a storage tank for storing the etching fluid, a supply conduit connecting said dip tank and said storage tank for passing etching fluid from said storage tank to said dip tank, pump means for causing etching fluid to pass from said storage tank to said dip tank, an automatic charging and metering unit for controlling said pump means to pump etching fluid into said dip tank when the fluid level in the dip tank is below a predetermined level, and a drain conduit, connecting the storage tank with the dip tank, for draining the etching fluid from the dip tank, said drain conduit including a solenoid valve which is adapted to be opened for draining the etching fluid

4,295,915

LABEL HANDLING APPARATUS

Tadahiro Sakaguchi, Nishinomiya; Masamichi Hino, Suita; Setsuo Tsuji, Hashimoto; Akiyoshi Hashido, Yao, and Kazuyoshi Enomoto, Kawachinagano, all of Japan, assignors to Kubota Ltd., Osaka, Japan

PCT No. PCT/JP79/00042, § 371 Date Sep. 24, 1979, § 102(e) Date Sep. 24, 1979, PCT Pub. No. WO80/00827, PCT Pub. Date May 1, 1980


PCT Filed Feb. 22, 1979, Ser. No. 103,948

Claims priority, application Japan, Oct. 13, 1978, 53-126332; Oct. 13, 1978, 53-126333; Oct. 13, 1978, 53-126335

Int. Cl.³ B65H 25/00

U.S. Cl. 156—361

51 Claims



1. A label handling apparatus comprising label preparing means for preparing labels each being temporarily retained on a backing strip through an adhesive agent applied to one surface thereof and having desired data visibly borne on the other surface thereof by stripping said labels from said backing strip in preparation for sticking said stripped labels to objects, sticking means for sticking said prepared labels to objects, said sticking means comprising air current producing means for producing air currents to produce a positive pressure atmosphere and a negative pressure atmosphere, an atmosphere chamber adapted to selectively communicate with either said positive pressure atmosphere or said negative pressure atmosphere produced by said air current producing means, said atmosphere chamber formed with a portion communicating with the ambient air, said ambient air communicating portion being provided with a label retaining port for blowing off and projecting labels and for sucking and retaining labels, gate means for selecting said negative pressure atmosphere or said positive pressure atmosphere, said gate means comprising two gate members, said two gate members comprising opposed end edge portions, said gate members operable in a symmetrical manner so that opposed end edges are brought close to each other in a path closing state and so that said end edges are moved away from each other in a path opening state, gate means driving apparatus for driving and controlling said gate means whereby labels are blown off and projected or sucked and retained at the label retaining port depending upon the position of said gate members, transfer means for transferring said labels from said label preparing means to said sticking means, said transfer means including a moving portion which contacts only a portion of the surface of said label having said adhesive agent applied thereto so as to contact withdraw and transfer said label, and controlling means for controlling the relative timing between the label preparing operation in said label preparing means and the label sticking operation in said sticking means.

4,295,916

TAPE BRAKE FOR TAPE WRAPPER


Samuel B. Stevens, Pekin, Ill., assignor to Caterpillar Tractor Co., Peoria, Ill.

Filed Sep. 11, 1979, Ser. No. 133,634

Int. Cl.³ B29H 17/00

U.S. Cl. 156—397

11 Claims



1. In an apparatus (10) for severing a tape (16) being applied to a body (15) as said body (15) is moved past said apparatus (10), a housing (20), an applicator roller (42) carried by said housing (20) for applying tape (16) to said body (15), a holder (50) movably carried on said housing (20), a stitching roller (72) rotatably mounted on said holder (50) and projecting outward from said housing (20) to a predetermined position relative to said applicator roller (42), resilient means (66) urging said holder (50) and said stitching roller (72) outward from said housing (20) to position said stitching roller (72) outboard of said applicator roller (42), in combination: brake means (94) carried by said housing (20) for arresting rotation of said applicator roller (42), and means (80) on said holder (50) for activating said brake means (94) in response to said holder (50) and stitching roller (72) being extended a predetermined amount outboard of said applicator roller (42) whereby the tape (16) extending from said applicator roller (42) to said stitching roller (72) is severed as said body (15) is moved past said stitching roller (72).

4,295,917

WINDING OF FIBRES

Wolf W. Stinnes, 31 Johann Rissik Dr., Waterkloof Ridge, Pretoria, South Africa


Filed Dec. 29, 1978, Ser. No. 974,422

Claims priority, application South Africa, Dec. 29, 1977, 77/7700

Int. Cl.³ B65H 8/00

U.S. Cl. 156—428

8 Claims



1. A machine for continuously winding endless fibres onto an object, the machine having an open ended hollow rotating fibre carrier and guide around the object, the carrier being adapted for the accumulation of turns of fibre on its outside, the guide being adapted to lead the fibre from underneath layers of the turns accumulated on the outside of the hollow carrier inwardly to the object and means adapted to rotate the

carrier with the guide wherein the outside of the carrier comprises fibre support means adapted for the easy rotation of the accumulated turns of fibre relative to the carrier, and further comprising a stationary fibre bank for supplying the carrier with fibre, means adapted to reverse the direction of rotation of the carrier and buffer means intermediate between the carrier and the fibre bank adapted to take up turns from the carrier during reverse rotation,

the buffer means comprising an outer hollow open-ended rotating carrier and guide, the fibres proceeding from the bank to the outer hollow carrier, being accumulated in several turns on this outer carrier, then proceeding from underneath layers of the turns of the outer carrier inwardly over a guide thereof to an inner hollow carrier, and means adapted to rotate the outer carrier with guide at rotational speeds bearing a constant ratio to rotational speeds at which the inner carrier is rotated both in forward and reverse direction.

4,295,918

APPARATUS FOR ASSEMBLING A PLASTIC MINING SCREEN


Henry E. Benson, Long Lake, and Terrence D. Moravec, Minneapolis, both of Minn., assignors to UOP Inc., Des Plaines, Ill.

Filed Dec. 26, 1979, Ser. No. 107,488

Int. Cl.³ B07B 1/46; B32B 1/00

U.S. Cl. 156—434

9 Claims



1. An assembly apparatus for assembling and thermally welding an elongated support rod having at least a thermoplastic coating simultaneously to a plurality of spaced, profiled screen surface members having at least a thermoplastic coating and which are arranged in a plane so as to be parallel to each other and transverse to said support rod; said apparatus having a pair of cooperating feed rollers, at least one of which is driven, for engaging and feeding said profiled members to a welding station wherein they are supported by a support roller; at least one of said feed rollers being grooved to accept said profiled members and to establish their spacing relative to each other; an elongated support rod positioning bar having at least one surface which includes a groove for receiving a support rod and retaining it, said support rod positioning bar being located above the welding station and said at least one surface comprising its bottom surface during a welding operation; an elongated welding bar mounted for movement into and out of a position in a vertical plane in the welding zone area between said support rod positioning bar and said profiled members, said welding bar containing heater means and having upper and lower heated portions for simultaneously heating the bottom side of said support rod carried by said support rod positioning bar and a top portion of each of said profiled members; and means for forcing said support rod positioning bar and the support rod positioned thereunder downwardly as the welding bar is removed from said welding zone area, said downward movement causing the intersecting portions of said support rod and profiled members which are at least partially melted or

softened by the welding bar to flow together into an intimate fused relationship.

4,295,919

FORMING AN INTEGRAL CLOSURE FOR A THERMOPLASTIC CONTAINER


Thomas A. Sutrina, Rockford, Ill., and R. Douglas Behr, Midland, Mich., assignors to The Dow Chemical Co., Midland, Mich.

Division of Ser. No. 969,911, Dec. 15, 1978. This application May 14, 1980, Ser. No. 149,861

Int. Cl.³ B29D 7/04

U.S. Cl. 156—498

8 Claims



1. An apparatus for forming an integral thermoplastic fastening means on a cast film or sheet, said apparatus comprising an extrusion die having an extrusion channel ending in extrusion die lips, said die lips presenting a surface defining a plane, a side of said die presenting a face angularly disposed towards said extrusion channel and die lips, an extrusion die block located adjacent said face, a die plate secured to the die block, said die plate having a leading edge, said leading edge located out of the plane of the die lips, said die block having an extrusion channel disposed angularly adjacent the exit of said die block so as to increase the acuteness of the angularity of the extrudate issuing from the die plate with respect to the extrudate issuing from said die lips, and cooling means located below said extrusion die and die plate.

4,295,920

APPARATUS FOR AUTOMATICALLY PRODUCING GLAZED INSULATING WINDOW OR DOOR PANELS


Luigi Bovone, 15070 Belforte Monferrato, Alessandria, Italy

Filed Nov. 26, 1979, Ser. No. 97,789

Int. Cl.³ B32B 31/00

U.S. Cl. 156—557

10 Claims



1. An apparatus for automatically manufacturing glazed insulating window or door panels constituted by two glass panes spaced apart by a frame interposed therebetween, comprising:

first means for situating a first pane in a predetermined position;
 second means located in operative relationship to said first means for raising the first pane from a predetermined position to an elevated position;
 mobile plate means located in operative relationship to said first means for situating a frame provided with at least a partial coating of adhesive in a certain position below the first pane when the latter is in its elevated position;
 said second means further comprising means for lowering the first pane from the elevated position when the frame is situated in a certain position until the first pane contacts one side of the frame to form an assembly therewith and for thereupon raising the assembly;
 said first means further comprising means for situating the second pane in a predetermined position below said assembly whereupon said second means lowers said assembly until the frame contacts the other side of the frame to form a panel.


4,295,921

SYSTEM FOR CONTROLLING THE MOVEMENT AND LOCKING OF TAPE APPARATUS

John H. Bopst, III, 409 Chalfonte Dr., Baltimore, Md. 21228
 Filed Apr. 16, 1980, Ser. No. 140,858
 Int. Cl.³ B44C 7/00

U.S. Cl. 156—577

1 Claim



1. In a tape reel system having a spool for unreeling tape therefrom and means for mounting the spool rotatably, the improvement comprising: the means for mounting including means for adjustably retarding rotation of the spool; means for locking the spool for preventing said rotation of the spool; the means for mounting including a spindle with first and second ends, the spool being cylindrical and having aperture-defining means in the circumference of a first end thereof, the spindle having spool-aperture engaging means adjacent the second end thereof for connecting the spool for rotation therewith; the mounting means further including a bracket comprising a base and first and second arms integral with the base, the means for adjustably retarding rotation including resilient means on the spindle; means for causing the resilient means to exert adjustable force against the first arm including said spool-aperture engaging means having threaded connection with the spindle; the spool aperture defining means defining first and second slots diametrically opposed in said first end of the spool, the aperture engaging means detachably engaging both said slots; the spool having a second end with an end cover thereover having a hole in the center thereof, said means for rotatably mounting the spool, mounting said end cover, by engagement at said hole, to the second arm of the bracket; means for exerting a retarding force on the spool at said second end, comprising a fixed protrusion from the second arm extending against the end cover adjacent the hole; the means for locking including the spindle having a shape permitting engagement of the first end thereof, means on the first arm for engaging said spindle shape, the shape being polygonal and the means on the first arm having an open-end wrench shape proportioned for fitting to said polygonal shape; the means on the first arm having a sliding engagement with the first arm and means for adjustably fixing the sliding position of said sliding engagement; the sliding engagement being on the outside of the first arm and the resilient means comprising a compression spring

held on said spindle in a space between said first arm and said spool aperture engaging means; the spindle second end having a closure with a hole therein, means protruding from the second arm into the hole, and means permitting ready removal and reloading of a spool comprising the compression spring having sufficient length to permit a spool to be thrust thereagainst and compress the spring to an extent clearing the second end of the spool from said means protruding.

4,295,922

TUBE SIDE SEAM HEAT SEALER


Jack R. Evers, Torrance, Calif., assignor to Developak Corporation, Redondo Beach, Calif.

Filed Sep. 17, 1979, Ser. No. 76,449

Int. Cl.³ B30B 5/02

U.S. Cl. 156—583.1

14 Claims



1. A heat sealer comprising first and second support members, mounting means mounting said support members in parallel relation for axial movement, opposed heat sealing members carried by said support members, drive means interconnecting said support members for axial movement in unison; and said drive means including fluid pressure means urging said support members to positions wherein said heat sealing members are in closed operative positions, and selectively operable mechanical means operable to overcome said fluid pressure means and to move said support members to positions separating said heat sealing members for receiving an article to be heat sealed therebetween.

4,295,923

METHOD OF MANUFACTURING A SEMICONDUCTOR/GLASS COMPOSITE MATERIAL

Erich Kasper, Senden, Fed. Rep. of Germany, assignor to Licentia Patent-Verwaltungs-G.m.b.H., Frankfurt am Main, Fed. Rep. of Germany


Filed Mar. 13, 1980, Ser. No. 130,122

Claims priority, application Fed. Rep. of Germany, Mar. 14, 1979, 2909985

Int. Cl.³ H01L 21/306

U.S. Cl. 156—630

5 Claims



1. A method of manufacturing a semiconductor/glass composite material, in which at least one semiconductor layer is permanently connected to a plate-shaped glass substrate comprising the steps of covering the glass substrate at least partially by a second layer on its surface facing the semiconductor; bringing the semiconductor and the glass substrate into contact in the surface areas not provided with the second layer; connecting them by means of the action of pressure and heat; and etching away the semi-conductor layer to the thickness of the second layer by means of etch polishing.

4,295,924

METHOD FOR PROVIDING SELF-ALIGNED CONDUCTOR IN A V-GROOVE DEVICE


Richard R. Garnache, South Burlington, and Donald M. Kenney, Shelburne, both of Vt., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Dec. 17, 1979, Ser. No. 103,981

Int. Cl.³ H01L 21/308

U.S. Cl. 156—643

10 Claims



1. The method of providing a conductive electrode for a semiconductor device comprising the steps of:
 providing a semiconductor substrate having a surface containing at least one recessed groove to which an electrode is to be provided;
 depositing a substantially uniform layer of electrode forming material over at least a portion of said surface including all of said groove;
 dispensing a layer of mask-forming organic material over said layer of electrode forming material and said surface to a depth sufficient to provide a substantially planar upper surface;
 heating said substrate to harden said layer of mask-forming organic material;
 selectively etching said layer of organic material in preference to said electrode forming material to a depth below the level of the surface of said substrate to expose the portion of said layer of electrode forming material outside of the area of said groove;
 applying a blocking mask over at least a part of said exposed layer of electrode forming material adjacent to, and extending over one end of the area of said groove;
 selectively etching and removing said layer of electrode forming material in preference to said masking material and said blocking mask to provide an electrode on said substrate having a first etch-defined portion terminating within said groove below said surface of said substrate and a second connected portion remaining on said surface; and removing both said masking material and said blocking mask.

9. The method of claim 1 wherein the step of providing said substrate further comprises the steps of:
 providing a silicon semiconductor substrate of a predetermined conductivity type;
 forming a first dielectric layer on said first surface of said silicon semiconductor substrate;
 providing at least one opening in said dielectric layer to expose a region of said first surface; and anisotropically etching said exposed region to form said groove therein.

4,295,925

TREATING PULP WITH OXYGEN

Jozef M. Bentzelzen, Sumner; Michael D. Meredith, Federal Way, both of Wash.; Henry Beppe, Kamloops, Canada; Louis O. Torregrossa, Puyallup, Wash.; Howard R. Battan, Auburn, Wash., and Dennis H. Justice, Everett, Wash., assignors to Weyerhaeuser Company, Tacoma, Wash.

Filed Jun. 15, 1979, Ser. No. 48,935

Int. Cl.³ D21C 9/04, 9/10; D21D 5/28


U.S. Cl. 162—19

40 Claims

1. A wood pulp process comprising continuously digesting wood chips with chemicals under heat and pressure to form delignification products and delignified wood chips,

removing at least a part of said delignification products, forming wood pulp from said delignified wood chips by partially releasing the pressure from said wood chips, transporting a slurry containing said wood pulp and remaining delignification products under pressure to a storage tank, and storing said slurry in said tank, prior to said storage, adjusting the pH of said slurry to a pH in the range of 8 to 14, between said pH adjustment and said storage, adding oxygen to said slurry, between said pH adjustment and said storage, mixing said oxygen with said slurry in a mixing zone in which a plurality of rotating members pass through said slurry in a direction transverse the direction of travel of said slurry, said members having a major axis extending in the direction of rotation, said members providing a swept area through said slurry of 10,000 to 1,000,000 square meters per metric ton of oven dry pulp, said members having leading and trailing edges, said leading edge having a radius of curvature in the range of 0.5 to 15 mm.

23. A pulping apparatus comprising a continuous digester for continuously digesting wood chips to form delignification products and delignified wood chips, and



a washer associated with said digester for removing at least a part of said delignification products, said digester having a pressure relief valve for forming wood pulp from said delignified wood chips by partially releasing the pressure from said wood chips, a pipe for transporting a slurry containing said wood pulp and remaining delignification products under pressure from said digester to a storage tank, and said storage tank, means, prior to said storage tank, for adding a pH adjustment chemical to said slurry, means, between said pH adjustment chemical addition means and said storage tank, for adding oxygen to said slurry, and means, prior to said storage tank, for mixing said oxygen with said slurry, said mixing means having a mixing zone, a plurality of rotors in said mixing zone, said rotors having leading and trailing edges, said leading edge having a radius of curvature in the range of 0.5 to 15 mm, said rotors having a major axis extending in the direction of rotation, said rotors being rotatable through said slurry in a direction transverse to the direction of travel of said slurry, means for rotating said rotors, and said rotors providing a swept area of from 10,000 to 1,000,000 square meters per metric ton of oven dry pulp.

4,295,926

METHOD AND APPARATUS FOR TREATING PULP WITH OXYGEN


Jozef M. Bentvelzen, Sumner; Michael D. Meredith, Federal Way, both of Wash.; Henry Beppe, Kamloops, Canada; Louis O. Torregrossa, Puyallup, Wash.; Howard R. Battan, Auburn, Wash., and Dennis H. Justice, Everett, Wash., assignors to Weyerhaeuser Company, Tacoma, Wash.

Filed Jun. 15, 1979, Ser. No. 49,001

Int. Cl.³ D21C 9/10; D21D 5/28

U.S. Cl. 162—57

88 Claims U.S. Cl. 162—57



1. The process of creating intimate contact between wood pulp having a consistency of 7 to 15% and a pH in the range of 8 to 14 and treating said pulp with said oxygen, comprising adding oxygen to said pulp, mixing said oxygen with said pulp, said mixing occurring in a mixing zone in which a plurality of rotating members pass through said pulp in a direction transverse the direction of travel of said pulp, said members having a major axis extending in the direction of rotation, said members providing a swept area through said pulp of 10,000 to 1,000,000 square meters per metric ton of oven dry pulp, said members having leading and trailing edges, said leading edge having a radius of curvature in the range of 0.5 to 15 mm, transporting said pulp to a washer, and washing said pulp in said washer.

53. A apparatus for creating intimate contact between a pulp having a consistency of 8 to 15% and oxygen and treating said pulp with said oxygen, comprising means for transporting said pulp to a washing means, said means for washing said pulp, before said washing means, means for adding alkali to said pulp, means for adding oxygen to said pulp, and means for mixing said oxygen with said pulp, said mixing means having a mixing zone, a plurality of rotors on said shaft in said mixing zone, said rotors having leading and trailing edges, said leading edge having a radius of curvature in the range of 0.5 to 15 mm, said rotors being rotatable through said slurry in a direction transverse in the direction of travel of said slurry, said rotors having a major axis extending in the direction of rotation, means for rotating said rotors, and said rotors providing a swept area of from 10,000 to 1,000,000 square meters per metric ton of oven dry pulp.

4,295,927

METHOD AND APPARATUS FOR TREATING PULP WITH OXYGEN AND STORING THE TREATED PULP


Jozef M. Bentvelzen, Sumner; Michael D. Meredith, Federal Way, both of Wash.; Henry Beppe, Kamloops, Canada; Louis O. Torregrossa, Puyallup, Wash.; Howard R. Battan, Auburn, Wash., and Dennis H. Justice, Everett, Wash., assignors to Weyerhaeuser Company, Tacoma, Wash.

Filed Jun. 15, 1979, Ser. No. 48,917

Int. Cl.³ D21C 9/10; D21D 5/28

88 Claims U.S. Cl. 162—57

88 Claims



1. The process of creating contact between a wood pulp having a consistency of 8 to 15% and a pH in the range of 8 to 14 and oxygen, and treating said pulp with said oxygen, comprising adding oxygen to said pulp, intimately mixing said oxygen with said pulp, said mixing occurring in a mixing zone in which a plurality of rotating members pass through said pulp in a direction transverse the direction of travel of said pulp, said members having a major axis extending in the direction of rotation, said members providing a swept area through said pulp of 10,000 to 1,000,000 square meters per metric ton of oven dry pulp, said members having leading and trailing edges, said leading edge having a radius of curvature in the range of 0.5 to 15 mm, transporting said pulp to a storage tank, and storing said pulp in said storage tank.

53. An apparatus for intimately mixing a pulp having a consistency of 8 to 15% with oxygen, and treating pulp with said oxygen, comprising means for transporting said pulp to a storage tank, and a storage tank, before said storage tank, means for adding alkali to said pulp, means for adding oxygen to said pulp, and means for mixing said oxygen with said pulp, said mixing means having a mixing zone, a plurality of rotors in said mixing zone, said rotors having leading and trailing edges, said leading edge having a radius of curvature in the range of 0.5 to 15 mm, said rotors being rotatable through said pulp in a direction transverse to the direction of travel of said pulp, said rotors having a major axis extending in the direction of rotation, means for rotating said rotors, and said rotors providing a swept area of 10,000 to 1,000,000 square meters per metric ton of oven dry pulp.

4,295,928

PHENOLIC COMPOUNDS AS VISCOSITY PRESERVATIVES DURING HYPOCHLORITE PULP BLEACHING

Michael D. Breslin, Downers Grove, Ill., assignor to Nalco Chemical Company, Oak Brook, Ill.

Filed Aug. 7, 1980, Ser. No. 176,229

Int. Cl.³ D21C 9/14

U.S. Cl. 162—73

5 Claims

1. In a method for the bleaching of aqueous slurries of chem-

ically produced cellulosic materials utilizing a hypochlorite bleaching agent selected from the group consisting of sodium hypochlorite and calcium hypochlorite, the improvement comprising maintaining in the aqueous slurry of the chemically produced cellulosic material during treatment with said bleaching agent from 0.01–0.5% by weight of an aromatic compound selected from the group consisting of: thymol and hydroquinone.

4,295,929

PROCESS FOR ACID SULFITE DIGESTION OF WOOD
Phyllis C. Leithem, McCleary, Wash., assignor to International Telephone and Telegraph Corp., New York, N.Y.

Continuation-in-part of Ser. No. 54,425, Jul. 3, 1979, abandoned.

This application Mar. 19, 1980, Ser. No. 131,813

Int. Cl.³ D21C 3/06

U.S. Cl. 162—83

13 Claims

1. In a process of digesting wood to produce chemical pulp by the acid sulfite digestion process in which the ratio by weight of total SO₂ to combined SO₂ is at least 4 to 1 comprising heating in a closed vessel wood chips in an acid sulfite cooking liquor having a concentration of free SO₂ no greater than 16% to a maximum cooking temperature no greater than 180° C. and at a maximum pressure no greater than 170 psig for a period of time sufficient to defiber the wood, the improvement in which the ratio by weight of one part of combined SO₂ to 100 parts of dry wood is from 4 to 12 and the minimum average rate of heating to a temperature which is the substantially maximum cooking temperature is 40° C. per hour.

4,295,930

ALKOXYLATED DIOXOLANES AS PAPER SIZING AGENTS

Thomas Aitken, Chicago; David J. Kowalski, Clarendon Hills, and K. G. Srinivasan, Oak Park, all of Ill., assignors to Nalco Chemical Company, Oak Brook, Ill.

Filed Mar. 17, 1980, Ser. No. 130,666

Int. Cl.³ D21H 3/02

U.S. Cl. 162—158

41 Claims

1. A composition for sizing paper comprising the acid catalysed reaction product of an aqueous solution of glyoxal containing no less than 40 wt % and no more than 80 wt % glyoxal, and a hydrophobe chosen from the group consisting of:

- (A) linear and branched, saturated and unsaturated fatty alcohols containing from 10 to 30 carbon atoms, and mixtures of such alcohols; and
- (B) esters of polyols containing from 2 to 5 carbon atoms with fatty acids containing from 10 to 30 carbon atoms which esters contain at least one free hydroxyl group, and mixtures of such esters;

and wherein from 0.1 mole to 3.0 moles of glyoxal is used per hydroxyl group in the hydrophobe.

4,295,931

SIZING METHOD AND SIZING COMPOSITION FOR USE THEREIN

David H. Dumas, Wilmington, Del., assignor to Hercules Incorporated, Wilmington, Del.

Continuation of Ser. No. 33,618, Apr. 26, 1979, abandoned, which is a continuation of Ser. No. 875,663, Feb. 6, 1978, abandoned, which is a continuation-in-part of Ser. No. 665,140, Mar. 8, 1976, abandoned. This application Jun. 2, 1980, Ser. No. 155,040

Int. Cl.³ D21H 3/02

U.S. Cl. 162—158

4 Claims

1. In the method of producing sized paper wherein there is employed in the internal or external sizing thereof an aqueous emulsion of a hydrophobic cellulose reactive sizing agent selected from the group consisting of ketene dimers, acid anhydrides, and organic isocyanates, the improvement wherein there is employed in combination with the sizing agent a sizing

accelerator, said accelerator being selected from a water-soluble poly(diallylamine)-epihalohydrin resin and a water-soluble poly(N-methyldiallylamine)-epihalohydrin resin in an amount sufficient to increase the off-the-machine sizing effect of the sizing agent, the amount of epihalohydrin used in reaction with the poly(diallylamine) being from about 0.5 mole to about 1.5 moles per mole of secondary amine present in the polymer and the amount used in reaction with the poly(N-methyldiallylamine) being from about 0.5 mole to about 1.5 moles per mole of tertiary amine present in the polymer.

4,295,932

SYNERGISTIC BLEND OF BIOCIDES

Frances C. Pocius, Westmont, Ill., assignor to Nalco Chemical Company, Oak Brook, Ill.

Filed Jul. 14, 1980, Ser. No. 168,858

Int. Cl.³ D21H 5/22

U.S. Cl. 162—161

5 Claims

1. A method for controlling aqueous systems heavily contaminated with microorganisms comprising treating such systems with 0.5–10 ppm of a mixture of 75% of 5-chloro-2-methyl-4-isothiazolin-3-one and 25% 2-methyl-4-isothiazolin-3-one and an effective amount of chlorine or chlorine dioxide, such amount being substantially effective with said mixture to control microorganisms in the aqueous system.

4,295,933

PRODUCING DISPERSIONS OF PREFLOCCULATED FILLERS FOR USE IN PAPERMAKING

David E. Smith, Longfield, England, assignor to Blue Circle Industries Limited, London, England


Continuation of Ser. No. 923,347, Jul. 10, 1978, abandoned. This application Apr. 3, 1980, Ser. No. 137,476

Claims priority, application United Kingdom, Jul. 12, 1977, 29209/77

Int. Cl.³ D21H 3/82

U.S. Cl. 162—168 NA

25 Claims




1. In a method of supplying filler to a papermaking furnish which comprises the steps of forming preflocculated filler and then adding it to papermaking furnish, the improvement which comprises forming the preflocculated filler by continuously forming a suspension of polymeric binder in particulate form in water in which the concentration of the binder solids in the suspension is at least 0.5 percent by weight, said binder being a starch-based polymer; continuously passing the formed suspension through a zone wherein the suspended particulate polymeric binder is allowed to swell in the water and is subjected to shear; regulating the rate of continuous flow of the resulting dispersion through the zone, and the degree of shear applied, so that the residence time of the dispersed polymeric binder in the zone is at least sufficient for optimum swelling of said polymeric binder in the water and the resulting solution of polymeric binder in the water is visually homogeneous; continuously passing said solution to the papermaking furnish; and introducing filler into the water sufficiently in advance of contact of said solution with the papermaking furnish such that said filler is preflocculated prior to contact thereof with the papermaking furnish.

4,295,934

LIQUID-METAL-COOLED NUCLEAR REACTOR
 Marcel Robin, 25, Avenue de l'Europe, 92310 Sevres, France
 Filed Jun. 22, 1979, Ser. No. 51,517

Claims priority, application France, Jun. 23, 1978, 78 18823
 Int. Cl.³ G21C 15/00, 11/08
 U.S. Cl. 376—203

6 Claims




1. A liquid metal cooled nuclear reactor comprising:
 - a core constituted by a plurality of fuel-assemblies provided with a tubular bottom fitting and by its neutronic protection means;
 - a main vessel comprising a bottom portion, a lateral wall and first supporting means arranged at a determined level, said first means being integral with the outer surface of said lateral wall;
 - a primary vessel, mounted inside said main vessel and coaxial therewith, said primary vessel comprising a corediagrid for supporting and feeding the reactor core, a lateral wall and second supporting-means integral with the primary vessel lateral wall and with the main vessel lateral wall, respectively, the two lateral walls of said two vessels defining an annular space;
 - a semi-tight horizontal partition in said annular passage;
 - at least one heat-exchanger outside said vessels for ensuring a heat-exchange between said hot liquid metal and cold water;
 - a first connection duct for the hot metal between the inlet of said exchanger and the inside of the primary vessel above said core, said first duct opening into said primary vessel above said core and passing through said annular space above said horizontal partition by means for passing through said space;
 - a second connection duct for said cold metal, between the outlet of the said exchanger and said annular space, said second duct opening into said annular space, so as to cause said cold liquid metal to flow in said core diagrid, then through said core, via the bottom-fittings of the fuel-assemblies, wherein:
 - said first supporting means and said second supporting means are substantially at the same horizontal level, said level being, in addition, in the vicinity of the level of said first and said second connecting ducts;
 - said primary vessel is constituted by an inner sleeve extending over at least a portion of the height of the lateral wall of the primary vessel, and an outer sleeve, parallel with said inner sleeve, said sleeves defining an interstice, containing thermally insulating means, said interstice being connected, in the lower portion thereof, to a manifold mounted under said core diagrid, for collecting the leaks of the liquid metal at the core bottom and the outer sleeve comprises a plurality of orifices opening into said annular space above said semi-tight horizontal partition;
 - the portion of said first duct passing through said annular space is surrounded by thermally insulating means adapted to withstand the differential expansion between said two vessels;
 - said semi-tight horizontal partition is constituted by said second supporting means, the latter being provided with calibrated orifices.

BIMETALLIC SPACER MEANS FOR A NUCLEAR FUEL ASSEMBLY
 Andrew J. Anthony, Tariffville, Conn., assignor to Combustion Engineering, Inc., Windsor, Conn.
 Filed Mar. 29, 1979, Ser. No. 25,228
 Int. Cl.³ G21C 3/30

U.S. Cl. 376—285

7 Claims



1. In a fuel assembly of the type that is employable in a nuclear reactor core and has a definable exterior surface, the fuel assembly including a multiplicity of fuel rods and at least one nuclear fuel assembly spacer grid, said nuclear fuel assembly spacer grid including perimeter means and first and second means each structurally associated with said perimeter means, said perimeter means including a plurality of perimeter strips each made of zircaloy and having their ends interconnected together to form a closed perimetric structure positioned in surrounding relation to said multiplicity of fuel rods thereby defining the exterior surface of the fuel assembly, said first means being operable to provide lateral support to said multiplicity of fuel rods, said second means being operable to effect the proper spacing between said multiplicity of fuel rods, the improvement comprising expandable means cooperatively associated with said perimeter means so as to be operable to preclude in-reactor bowing of the fuel assembly, said expandable means comprising a plurality of expandable strips each being formed from a material having a high thermal coefficient of expansion than zircaloy, said plurality of expandable strips being attached to said plurality of perimeter strips in equally spaced relations one to another, said plurality of expandable strips being thermally expandable between a first position wherein said plurality of expandable strips are located in relatively close proximity to the exterior surface of the fuel assembly and a second position wherein said plurality of expandable strips are displaced laterally relative to the exterior surface of the fuel assembly so as to preclude in-reactor bowing of the fuel assembly by occupying the space adjacent to the exterior surface of the fuel assembly otherwise available for receiving portions of the fuel assembly that have undergone bowing.

4,295,936
FRACTIONATION APPARATUS PROVIDING IMPROVED HEAT RECOVERY FROM BOTTOM STREAM

Robert A. Farnham, San Rafael, Calif., assignor to Chevron Research Company, San Francisco, Calif.

Filed Jun. 28, 1979, Ser. No. 53,124

Int. Cl.³ B01D 3/38

U.S. Cl. 202—153

9 Claims


1. In a fractionation apparatus comprising a vertically elongated fractionation column having a plurality of trays disposed therein, including a lowermost tray in a lower portion of said column, means for introducing a feed stream into the column at a point between the top and bottom thereof, means for removing a stream from a portion of said column above said feed means, means for removing a bottoms stream from a portion of said column below said feed means, and means for providing a

recycle portion of said bottoms stream to a lower portion of said column,

the improvement which comprises a perforated generally annular baffle positioned within a lower portion of said column for directing fluid from the generally cylindrical fluid-retaining space within said baffle to said bottoms stream removal means, said baffle (a) extending upwardly from the bottom portion of said column and forming between said baffle and the lower side portion of said column a generally annular fluid-retaining space, (b) said cylindrical fluid-retaining space being in fluid communica-

tion being comprised of a plurality of individual modules arranged atop one another, each such module comprising:

- a peripheral module wall;
- an evaporator means for vaporizing said substance and having a surface inclined downward in the direction of the axis of the module, an upper rim, a lower rim, and a liquid guide element for said liquid at the lower rim thereof inclined downward toward said module wall;
- a distributor channel disposed above the upper rim of the evaporator means for distributing the liquid thereto, the distributor channel being positioned to receive the liquid from the guide element of the module just above;
- a condenser means for condensing said vapor to a liquid, having at least one drain element thereon for channelling the condensed liquid; and
- a vapor guide element for guiding to the condenser means vapor from the module just below.



tion via said perforations with said annular fluid-retaining space, and (c) the lower portion of said cylindrical fluid-retaining space being in fluid communication with said bottoms stream removal means; means for directing fluid from said lowermost tray into said cylindrical fluid-retaining space, said fluid-directing means being positioned above and spaced apart from said baffle and being in open fluid communication with the top of said cylindrical fluid-retaining space; and said bottoms stream recycle means providing said portion of said bottoms stream to said annular fluid-retaining space.

4,295,937
RECTIFIER


Manfred Mayer, Niederrhausen, and Roland Volz, Liederbach, both of Fed. Rep. of Germany, assignors to Hoechst Aktiengesellschaft, Frankfurt am Main, Fed. Rep. of Germany
 Filed Mar. 20, 1980, Ser. No. 132,294

Claims priority, application Fed. Rep. of Germany, Mar. 22, 1979, 2911214

Int. Cl.³ B01D 3/14

U.S. Cl. 202—155

10 Claims



1. A rectifier for separating a refineable substance by evaporation to a vapor and condensation to a liquid, the rectifier

4,295,938
COKE-OVEN DOOR ASSEMBLY

Friedhelm Haaf, Velbert, Fed. Rep. of Germany, assignor to Fried. Krupp Gesellschaft mit beschränkter Haftung, Essen, Fed. Rep. of Germany


Filed Sep. 23, 1980, Ser. No. 190,166

Claims priority, application Fed. Rep. of Germany, Sep. 27, 1979, 2939070

Int. Cl.³ C10B 25/06

U.S. Cl. 202—248

10 Claims



1. A coke-oven door assembly comprising:
 - a doorjamb having an outwardly facing annular doorjamb surface;
 - a rigid door body having an annular outer edge aligned with and generally perpendicular to said doorjamb surface;
 - an annular and hollow rigid frame juxtaposed with said edge;
 - an annular seal strip engaging said edge and bearing inwardly on said doorjamb surface;
 - a rail inside said frame and movable toward and away from said doorjamb surface;
 - a plurality of elastically compressible biasing devices engaged between said rail and said strip and urging same toward said doorjamb surface; and
 - means including a plurality of spacers engaged between said doorjamb and said rail for maintaining said rail at a predetermined spacing from said doorjamb.

4,295,939
METHOD AND DEVICE FOR DETECTING A GASEOUS ANHYDRIDE IN AN OXYGEN BEARING GAS
 Marc Poirier, Chomedey; Michel Gauthier, Laprairie, and Andre Belanger, Ste-Julie, all of Canada, assignors to Hydro-Quebec, Montreal, Canada

Filed Nov. 30, 1979, Ser. No. 98,978

Claims priority, application Canada, Mar. 30, 1979, 324693
 Int. Cl.³ G01N 27/58


U.S. Cl. 204—1 T

31 Claims

1. A device for detecting a gaseous anhydride and measuring

its concentration in an oxygen-bearing gas, said device comprising:

- a first solid-electrolyte element containing oxyanions of the anhydride to be detected;
- a first reference electrode in contact with said first electrolyte element;
- means for fixing a constant potential near this first reference electrode;
- a second, O^{--} ion-conducting, solid-electrolyte element, said solid-electrolyte element being spaced from said first reference electrode and in direct contact with said first electrolyte element so as to create an electrolytic junction;
- a second reference electrode in contact with said second electrolyte element, said second reference electrode being spaced from said electrolytic junction;
- means for fixing a constant potential near this second reference electrode;
- means for bringing the gas containing the gaseous anhydride to be detected into contact with the electrolytic junction formed by the first and second electrolyte elements so as to form a triple junction, means for preventing contact of said gas and said first reference electrode;
- a potentiometer connected to said reference electrodes to measure the difference of potential existing between said reference electrodes when the gas containing the gaseous anhydride to be detected is in contact with the electrolytic junction formed by the first and second electrolyte elements, and
- means for heating said triple junction to a temperature at which a logarithmic variation in the concentration of the



anhydride to be detected produces a proportional, virtually linear variation in the measured difference of potential, provided that said temperature is lower than the melting temperatures of said first and second electrolyte elements.

22. A method for detecting a gaseous anhydride and measuring its concentration in an oxygen-bearing gas by measurement of a difference of potential, characterized in that it comprises the following steps:

- forming an electrolytic junction by contact between a first solid-electrolyte element containing oxyanions of the anhydride to be detected and a second, solid-electrolyte element containing O^{--} ions;
- bringing the gas containing the gaseous anhydride to be detected into contact with said electrolytic junction formed by the first and second electrolyte elements to form a triple junction;
- creating in this triple junction a difference of potential measurable by means of two reference electrodes in contact with said first and second electrolyte elements respectively, by fixing a constant potential in the vicinity of each of said reference electrodes, said reference electrodes being both spaced from the triple junction, the reference electrode in contact with said first electrolyte element being out of contact with the anhydride containing gas;
- heating said triple junction to a temperature at which a logarithmic variation in the concentration of the anhydride to be detected produces a proportional, virtually linear variation in the difference of potential in said triple junction, said temperature being lower than the melting

temperatures of said first and second electrolyte elements, and measuring said difference of potential with a potentiometer connected to said reference electrodes so as to obtain a measurement of the concentration of the anhydride to be detected.

4,295,940

METHOD FOR BATTERY PLATE

Brajendra P. Varma, Levittown, Pa., assignor to Eltra Corporation

Division of Ser. No. 64,650, Aug. 7, 1979, Pat. No. 4,230,779.

This application Aug. 29, 1980, Ser. No. 182,346

Int. Cl.³ H01M 10/44

U.S. Cl. 204—2.1

2 Claims

1. A method of forming a positive plate for a lead acid battery, said method comprising the steps of immersing a lead or lead alloy grid pasted with a lead oxide composition in an electrolyte containing from 10 to 5000 parts per million of at least one element selected from the group consisting of manganese and chromium, and applying an electric current to said grid and said electrolyte thereby introducing from 0.1 to 0.4 percent based upon the weight of said plate of said element into said plate.

4,295,941

METHOD OF MANUFACTURING A METAL CERAMIC DENTAL RESTORATION

Stewart J. Lustgarten, Holliston, Mass., assignor to Healthco Inc., Boston, Mass.

Filed Dec. 7, 1979, Ser. No. 101,203

Int. Cl.³ A61C 5/08

U.S. Cl. 204—35 R

5 Claims

1. A method of manufacturing a fixed prosthodontic metal ceramic dental restoration comprising casting a metal framework from a metal composition comprising an alloy of nickel and chromium having at least 4% nickel, electroplating a thin film deposit of gold between about 0.4 to 1 mil in thickness over a predetermined surface area of said framework with said gold deposit being in intimate contact with the nickel chromium alloy; distributing finely divided particles containing a major proportion of gold which vary in size between 1 to no more than about 20 microns over said electroplated gold surface and firing successive layers of porcelain over said predetermined surface area in a firing temperature range of between about 1600° F. to 1900° F. whereby the firing of said porcelain layers simultaneously causes said finely divided particles to form beads of substantially globular shape.

4,295,942

PROCESS FOR PREPARING MANGANESE OXIDE

Konrad Koziol, Rothenbach, and Erich Wenk, Nuremberg, both of Fed. Rep. of Germany, assignors to Conradt GmbH & Co. Metallelektroden KG, Pegnitz, Fed. Rep. of Germany

Continuation of Ser. No. 23,346, Mar. 23, 1979, abandoned. This application Feb. 15, 1980, Ser. No. 122,060

Claims priority, application Fed. Rep. of Germany, Dec. 13, 1978, 2853820


Int. Cl.³ C25B 1/18

U.S. Cl. 204—96

12 Claims

1. The process for the electrolytic preparation of manganese oxides using an anode having a core of valve metal, the working surface of which has an electrically conductive, corrosion-resistant, mechanically solid coating which impedes the passivation of the core, wherein the working surface of the anode

comprises the surfaces of a plurality of rods which are mounted in parallel, and the rods are connected by conductive



supports, wherein the desired electrolysis product is a solid and not a gas.

4,295,943

PROCESS FOR THE ELECTROLYTIC PRODUCTION OF MANGANESE DIOXIDE

Nenad R. Tomov, and Geoffrey M. Roberts, both of Geneva, Switzerland, assignors to Diamond Shamrock Technologies S.A., Geneva, Switzerland

Filed Apr. 17, 1980, Ser. No. 141,199

Int. Cl.³ C25B 1/18

U.S. Cl. 204—96

8 Claims

1. A process for the electrolytic production of manganese dioxide comprising electrolyzing an aqueous manganese containing electrolyte between a flexible anode and a cathode to deposit manganese dioxide on the anode, flexing the anode to fracture and remove the manganese dioxide deposit and recovering the manganese dioxide without removing the anode from the cell.

4,295,944

ELECTROLYSIS OF AQUEOUS SOLUTION OF ALKALI METAL CHLORIDE

Takao Satoh, and Toru Seita, both of Shin-nanyo, Japan, assignors to Toyo Soda Manufacturing Co., Ltd., Shin-nanyo, Japan


Filed Jul. 8, 1980, Ser. No. 166,787

Claims priority, application Japan, Sep. 11, 1979, 54-115659

Int. Cl.³ C25B 1/34

U.S. Cl. 204—98

9 Claims



3. The method of claim 2, wherein said temperature range is a difference of from 4° C. to 8° C.

4,295,945

PROCESS FOR THE PRODUCTION OF LIQUID CHLORINE

Dieter Bergner, Kurt Hannesen, both of Kelkheim; Wolfgang Müller, Bad Soden am Taunus, and Wilfried Schulte, Hofheim am Taunus, all of Fed. Rep. of Germany, assignors to Hoechst Aktiengesellschaft, Frankfurt am Main, Fed. Rep. of Germany


Filed May 2, 1980, Ser. No. 146,020

Claims priority, application Fed. Rep. of Germany, May 4, 1979, 2917974

Int. Cl.³ C25B 1/26

U.S. Cl. 204—128

10 Claims



1. A process for the production of liquid chlorine comprising the steps of electrolyzing an aqueous alkali metal chloride solution in an electrolytic cell under an operational pressure of at least 8 bars and at an anolyte temperature above the boiling point of chlorine at the operational pressure; obtaining from the electrolysis a mixture of anolyte and steam-saturated gaseous chlorine in an anode space of the electrolytic cell; separating the anolyte from the steam-saturated gaseous chlorine; liquefying the steam-saturated gaseous chlorine under a pressure of at least 8 bars to a condensate after the steam-saturated chlorine passes out of the electrolytic cell by cooling the steam-saturated gaseous chlorine, said cooling comprising maintaining a temperature of at least 28° C. of the condensate which includes a liquid water-saturated chlorine phase and a liquid chlorine-saturated water phase; and separating the water phase from the chlorine phase which has a heavier specific weight than the water phase.

4,295,946

METHOD AND APPARATUS FOR ELECTROCHEMICAL PURIFICATION OF CONTAMINATED LIQUIDS

Miron M. Nazarian, ulitsa Bljukhera, 13, kv. 138; Vyacheslav T. Efimov, ulitsa Sumskaya, 59, kv. 2; Alexandr A. Axenko, ulitsa Bairona, 152, kv. 25; Vladimir A. Kolyada, ulitsa Petrozavodskaya, 91a, kv. 30, and Ljudmila F. Shamsha, ulitsa Dinamovskaya, 3, kv. 23, all of Kharkov, U.S.S.R.

Filed Aug. 8, 1980, Ser. No. 176,334


Int. Cl.³ C02F 1/46

U.S. Cl. 204—149

3 Claims

1. A method of electrochemical purification of contaminated liquids, comprising: heating a contaminated liquid to a temperature at least in the order of 40° C.; cooling an electrolyte to at least in the order of 25° C.; passing said cooled electrolyte through a region having energized soluble electrodes provided within an electrocoagulation chamber;

mixing said heated contaminated liquid within said electrocoagulation chamber above said soluble electrodes with an ascending flow of said cooled electrolyte containing products of dissolution of said soluble electrodes;



separating formed foam and sludge from the mixture of contaminated liquid and electrolyte within a settling chamber.

4,295,947

PHOTO-CURABLE COATING COMPOSITIONS FOR BUILDING MATERIALS

Eiichi Ohtani; Kengo Kobayashi; Asao Isobe, and Shigeyoshi Tanaka, all of Hitachi, Japan, assignors to Hitachi Chemical Company, Ltd., Tokyo, Japan

Filed Sep. 12, 1979, Ser. No. 74,660

Claims priority, application Japan, Sep. 18, 1978, 53-114371

Int. Cl.³ C08F 2/50; B32B 27/16

U.S. Cl. 204—159.15

2 Claims

1. A photo-curable coating composition for building materials which comprises

- (a) an isocyanate-modified epoxy ester obtained by the reaction of an acrylic or methacrylic ester of an epoxy compound having not less than two epoxy groups in the molecule with a polyisocyanate;
- (b) a photopolymerizable monomer being copolymerizable with the epoxy ester (a);
- (c) a ketone resin formed by condensation of a ketone with an aldehyde;
- (d) a photo-sensitizer; and
- (e) a sensitizing auxiliary,

the amounts of the constituents (a) to (e) being as follows:

0/100	≡ (b)/(a) + (b)	≡ 70/100	(weight ratio)
1/100	≡ (c)/(a) + (b)	≡ 50/100	(weight ratio)
0.5/100	≡ (d) + (e)/(a) + (b)	≡ 15/100	(weight ratio)
0/1	≡ (e)/(d)	≡ 3/1	(molar ratio)

4,295,948

PHOTOCURABLE ADHESIVE FROM ACRYLIC ACID, ACRYLAMIDE, DIMETHYLAMINOETHYL METHACRYLATE, BENZOPHENONE AND METHYL ETHYL KETONE

Alain Roman, Bossey; Pierre Chevreux, St. Jean de Gonville, both of France; Manfred Wüst, Dardagny, and Jacques Ehretsmann, Conches, both of Switzerland, assignors to Battelle Memorial Institute, Geneva, Switzerland

Division of Ser. No. 605,055, Aug. 15, 1975, abandoned. This application Sep. 20, 1979, Ser. No. 77,472

Claims priority, application Switzerland, Aug. 16, 1974, 11220/74; Aug. 16, 1974, 11221/74; Aug. 16, 1974, 11222/74

Int. Cl.³ C08F 220/56, 220/70, 226/10; B32B 17/10

U.S. Cl. 204—159.23

2 Claims

1. The photopolymerizable adhesive which consists of:

acrylic acid:	15% to 88.5% by weight
benzophenone:	0.5% to 10% by weight
methyl-ethyl-ketone:	1% to 60% by weight
dimethylamino-ethyl-methacrylate:	5% to 35% by weight and
acrylic amide:	5% to 35% by weight.

4,295,949

METHOD FOR DETERMINING BOUNDARY POINTS IN ELECTROPHORESIS

Toshihide Fujiwara, Fuchu, and Ryo Fujimori, Hachioji, both of Japan, assignors to Olympus Optical Co., Ltd., Tokyo, Japan


Filed May 21, 1980, Ser. No. 151,889

Claims priority, application Japan, May 25, 1979, 54-64814

Int. Cl.³ G01N 27/26

U.S. Cl. 204—180 G

5 Claims



1. A method for determining boundary points in electrophoresis comprising a step to determine points on the abscissa corresponding to peak tops on a densitogram traced based on electrophoresis and select said points as standard positions, a step to locate said standard positions on a densitogram of an unknown sample traced based on electrophoresis of an unknown sample, a step to count number of points having minimum values existing between each pair of the neighboring standard positions on the densitogram of the unknown sample and a step to select the point having the minimum value as the normal boundary point when a single point is counted or the one corresponding to the lowest concentration as the normal boundary point when 2 or more points are counted.

4,295,950

DESALINATION WITH IMPROVED CHLOR-ALKALI PRODUCTION BY ELECTROLYTIC DIALYSIS

Marc Cole, 1057 C Argyle Cir., Lakewood, N.J. 08701


Continuation-in-part of Ser. No. 71,991, Sep. 4, 1979,

abandoned. This application Jun. 5, 1980, Ser. No. 156,735

Int. Cl.³ B01D 13/02; C25B 1/34, 1/46

U.S. Cl. 204—180 P

19 Claims



8. In a process, conducted in an electrolytic dialysis cell, for the electrolytic decomposition of a first part of the alkali metal halide solute of a separately maintained aqueous brine to produce substantially pure chlorine and substantially pure caustic soda in concentrated solution and hydrogen, and for the concomitant electro dialysis in said cell of the solute of a further part of said separately maintained aqueous brine to form at

least partly desalinated water and salt enriched water, the improvement consisting, in combination, of the electrical discharge of the cations of said first part of said solute to atoms at an immobilized liquid metal amalgam filling the interconnected micro-pores of novel cathode immersed in a separately maintained sea water catholyte, and subsequent reaction of said atoms with water of dilute caustic soda solution in a denuding chamber abutting said novel cathode to form said substantially pure concentrated caustic soda solution and hydrogen, and further consisting, in said combination, of the electrical discharge of the anions of said first part of said solute at an anode immersed in a separately maintained substantially saturated metal chloride solution as anolyte, to form substantially pure chlorine, an electric current being passed between said anode and the amalgam of said novel cathode.

4,295,951

FILM-COATED CATHODES FOR HALATE CELLS

Tilak V. Bommaraju, Grand Island; Theodore H. Dexter, Lewiston, and Charles G. Rader, Grand Island, all of N.Y., assignors to Hooker Chemicals & Plastics Corp., Niagara Falls, N.Y.

Filed May 14, 1980, Ser. No. 149,814

Int. Cl.³ C25B 9/00, 11/03, 11/10

U.S. Cl. 204—242

11 Claims

11. In an electrolytic halate cell comprising a cell container, an anode, a cathode, and an alkali metal halate solution, the improvement comprising eliminating the presence of chromium ions in the solution by utilizing, as said cathode, a film-coated cathode comprising a conductive substrate coated with an adherent, porous film of a substantially nonconductive, chemically inert material, said film having an average thickness of from about 10^{-4} microns to about 10^3 microns, an average porosity of from about 1% to about 85%, and an average pore size of from about 0.1 microns to about 30 microns.

4,295,952

NOVEL CATIONIC MEMBRANES

Oronzio de Nora; Luigi Giuffrè, and Giovanni Modica, all of Milan, Italy, assignors to Oronzio de Nora Impianti Elettrochimici S.p.A., Milan, Italy

Division of Ser. No. 138,290, Feb. 22, 1979, Pat. No. 4,246,090.

This application Mar. 24, 1980, Ser. No. 133,521

Claims priority, application Italy, Jan. 17, 1979, 19354 A/79

Int. Cl.³ C25B 13/08

U.S. Cl. 204—252

7 Claims

1. A membrane electrochemical cell comprising a cell housing containing at least one anode in an anode compartment and at least one cathode in a cathode compartment forming an interelectrode gap with a cation exchange membrane separating the anode and cathode compartments with the sulfonated polymer facing the anodic side.

5. A fluid impermeable cation exchange membrane comprising a first layer of a water wettable and water insoluble sulfonated polymer of styrene and about 8 to 20 molar percent of divinylbenzene and a second layer of an unsulfonated polymer of divinylbenzene and at least one monomer selected from the group consisting of 2-vinylpyridine and 4-vinylpyridine in a molar ratio of styrene to vinylpyridine of about 1:8 to 1:1.

4,295,953

FILTER PRESS TYPE ION EXCHANGE MEMBRANE-METHOD ELECTROLYSIS CELL

Shigeaki Fuseya, Gifu, and Teruo Ichisaka, Tamano, both of Japan, assignors to Chlorine Engineers Corp., Ltd., Tokyo, Japan

Filed Jan. 2, 1980, Ser. No. 109,029

Int. Cl.³ C25B 9/00, 15/08

U.S. Cl. 204—257

2 Claims

1. A filter-press type ion exchange membrane-method electrolysis cell comprising

- (a) an anode structure which comprises a rectangular anode


frame including a top element, a bottom element and two side elements and anode plates welded to the anode frame, (b) a cathode structure which comprises a rectangular cathode frame including a top element, a bottom element and two side elements and cathode plates welded to the cathode frame, and

(c) an ion exchange membrane interposed between the anode structure and the cathode structure;

wherein the two side elements of the anode frame and the two side elements of the cathode frame have a tubular structure with a rectangular cross section,

the top and bottom elements of the anode frame and the top and bottom elements of the cathode frame have a J-shaped cross section, and are secured such that their open portions face the inside of an anode compartment and a cathode compartment, respectively, and

at least one end of the top element of the anode frame communicates with the top end of the side element of the anode frame and at least one end of the top element of the



cathode frame communicates with the top end of the side element of the cathode frame so that the side element communicating with the top element of the anode frame, and the side element communicating with the top element of the cathode frame form conduits for withdrawing gas and solution flowing from the anode compartment and the cathode compartment, respectively,

(d) a current disperser surrounding an anode lead bar welded to anode plates within the anode structure and a current disperser surrounding a cathode lead bar welded to cathode plates within the cathode structure, whereby a region not permitting passage of gas is formed between the periphery of the anode lead bar and the inside of the current disperser welded to the anode plates and between the periphery of the cathode lead bar and the inside of the current disperser welded to the cathode plates, thus serving as a passage for a downwardly moving stream of electrolytic solution, and

(e) a pipe for supplying an anolyte solution disposed within the anode compartment and a pipe for supplying a catholyte solution disposed within the cathode compartment.

4,295,954

COAL CONVERSION CATALYSTS

Thomas O. Mitchell, Trenton, N.J., assignor to Mobil Oil Corporation, New York, N.Y.

Filed Oct. 18, 1979, Ser. No. 86,212

Int. Cl.³ C10G 1/06

U.S. Cl. 208—10

5 Claims

1. In a solvent extraction process for coal conversion wherein coal is slurried in an organic solvent and heated to a temperature sufficient to dissolve or liquefy most of the coal, the resulting coal liquefaction product is upgraded by catalytic

hydrogenation, and a process-derived recycle solvent is hydrogenated and returned to the initial dissolution stage; the improvement which comprises contacting a coal/solvent slurry, with a catalyst selected from the groups consisting of:

- (1) spent hydrogenation catalyst from processes for the hydrogenation of hydrocarbons selected from the group consisting of petroleum, petroleum-derived liquids, Fischer-Tropsch liquids, and shale oils;
- (2) spent adsorbent from guard chambers used to demetallize said hydrocarbons; and
- (3) mixtures thereof.

4,295,955

ATTENUATION OF METAL CONTAMINANTS ON CRACKING CATALYST WITH A BORON COMPOUND
Hosheng Tu, Shorewood, Ill., assignor to UOP Inc., Des Plaines, Ill.

Filed Mar. 10, 1980, Ser. No. 129,003
Int. Cl.³ C10G 11/04

U.S. Cl. 208—120

7 Claims

1. A process for attenuating a metal on fluidized cracking catalyst which has been contaminated with said metal, said catalyst being used in a fluidized cracking system wherein said catalyst is cycled between a cracking zone, in which said catalyst is contacted at cracking temperature with a hydrocarbon feedstock, and a regeneration zone, in which carbonaceous residual material is oxidized and thereby removed from said catalyst, the source of said metal contaminant being said feedstock or residual metals resulting from the synthesis of said catalyst, which process comprises withdrawing a portion of said catalyst being transferred from said regeneration zone to said cracking zone as a slip stream, passing said slip stream to an independent attenuation zone, wherein said withdrawn portion of said catalyst is cooled to a temperature less than about 100° C. and thereafter is contacted with an aqueous solution of a boron compound to impregnate said boron compound upon said catalyst, drying said impregnated catalyst to remove water resultant from said aqueous solution, calcining said dried impregnated catalyst at a temperature of from about 425° C. to about 815° C. and adding said dried and calcined impregnated catalyst from said attenuation zone to the remaining portion of the catalyst being transferred from said regeneration zone to said cracking zone.

4,295,956


FLUID COKING PROCESS

William J. Mettrailer, Baton Rouge, La., assignor to Exxon Research & Engineering Co., Florham Park, N.J.

Filed Mar. 3, 1980, Ser. No. 126,400
Int. Cl.³ C10G 9/32

U.S. Cl. 208—127

11 Claims



1. In a coking process comprising the steps of:
(a) contacting a carbonaceous chargestock under fluid coking

conditions in a coking zone comprising a first bed of fluidized solids to produce a vapor phase product, including normally liquid hydrocarbons, and coke, said coke depositing on said fluidized solids;

- (b) passing a portion of said solids with a coke deposit thereon to a vessel comprising a second bed of fluidized solids, and
- (c) passing a portion of solids from said second vessel to said coking zone, the improvement which comprises: said fluid bed in said second vessel being divided into two zones, introducing a fluidizing gas into the first of said zones in an amount sufficient to provide a superficial gas velocity at least sufficient to maintain said solids fluidized and introducing a fluidizing gas into the second of said zones in an amount sufficient to provide in said second zone a superficial gas velocity ranging from about 1.5 to about 5 times the superficial gas velocity of said first zone, said superficial velocity of said second zone being at least two feet per second, to entrain solid fines out of said second zone, and passing a portion of solids from said second zone to said coking zone.

4,295,957

REFORMING WITH MULTIMETALLIC CATALYSTS
Charles H. Mauldin, and William C. Baird, Jr., both of Baton Rouge, La., assignors to Exxon Research & Engineering Co., Florham Park, N.J.

Division of Ser. No. 34,596, Apr. 30, 1979, Pat. No. 4,251,392.
This application Jul. 14, 1980, Ser. No. 168,491
Int. Cl.³ C10G 35/09

U.S. Cl. 208—138

15 Claims

1. A process for reforming a hydrocarbon feed at reforming conditions which comprises palladium and platinum in total concentration ranging from about 0.2 to about 0.6 percent, with from about 15 to about 50 mol. percent of the composition being platinum, as contrasted with the amount of palladium contained in the composition, from about 0.1 to about 2 percent rhenium, and from about 0.01 to about 0.1 percent copper, composited with an inorganic oxide support.

4,295,958

REFORMING WITH MULTIMETALLIC CATALYSTS
Charles H. Mauldin, and William C. Baird, Jr., both of Baton Rouge, La., assignors to Exxon Research & Engineering Co., Florham Park, N.J.

Division of Ser. No. 29,675, Apr. 13, 1979, Pat. No. 4,251,391.
This application Jul. 14, 1980, Ser. No. 168,492
Int. Cl.³ C10G 35/09

U.S. Cl. 208—138

23 Claims

1. A process for reforming a hydrocarbon feed at reforming conditions which comprises contacting said feed with a catalyst which consists essentially of from about 0.1 to about 2 percent platinum, from about 0.1 to about 2 percent rhenium, and from about 0.01 to about 0.1 percent copper composited with an inorganic oxide support.

4,295,959

HYDROCARBON DEHYDROCYCLIZATION WITH AN ATTENUATED SUPERACTIVE MULTIMETALLIC CATALYTIC COMPOSITE

George J. Antos, Bartlett, Ill., assignor to UOP Inc., Des Plaines, Ill.

Continuation-in-part of Ser. No. 48,957, Jun. 15, 1979, Pat. No. 4,229,319, which is a division of Ser. No. 954,684, Oct. 25, 1978, Pat. No. 4,206,040, which is a continuation-in-part of Ser. No. 833,332, Sep. 14, 1977, Pat. No. 4,165,276. This application Oct. 20, 1980, Ser. No. 198,733

Int. Cl.³ C07C 15/8; B01J 27/08; C10G 35/09

U.S. Cl. 208—138

25 Claims

1. A method for dehydrocyclizing a dehydrocyclizable hydrocarbon comprising contacting the hydrocarbon at hydrocarbon dehydrocyclization conditions with an acidic cata-

lytic composite comprising a combination of a catalytically effective amount of a pyrolyzed rhenium carbonyl component with a porous carrier material containing catalytically effective amounts of a halogen component, a silver component and a uniform dispersion of a catalytically effective amount of a platinum group component maintained in the elemental metallic state.

4,295,960

HYDROCARBON DEHYDROCYCLIZATION WITH AN ATTENUATED SUPERACTIVE MULTIMETALLIC CATALYTIC COMPOSITE

George J. Antos, Bartlett, Ill., assignor to UOP Inc., Des Plaines, Ill.

Continuation-in-part of Ser. No. 36,120, May 4, 1979, Pat. No. 4,231,897, which is a division of Ser. No. 947,906, Oct. 2, 1978, Pat. No. 4,193,863, which is a continuation-in-part of Ser. No. 833,332, Sep. 14, 1977, now Pat. No. 4,165,276. This application Nov. 3, 1980, Ser. No. 203,018

1980, Ser. No. 203,018

Int. Cl.³ C07C 15/08; C10G 35/09; B01J 27/08

U.S. Cl. 208—139

25 Claims

1. A method for dehydrocyclizing a dehydrocyclizable hydrocarbon comprising contacting the hydrocarbon at hydrocarbon dehydrocyclization conditions with an acidic catalyst composite comprising a combination of a catalytically effective amount of a pyrolyzed rhenium carbonyl component with a porous carrier material containing catalytically effective amounts of a halogen component, a cadmium component and a uniform dispersion of a catalytically effective amount of a platinum group component maintained in the elemental metallic state.

4,295,961

METHOD AND APPARATUS FOR IMPROVED FLUID CATALYTIC RISER REACTOR CRACKING OF HYDROCARBON FEEDSTOCKS


Robert J. Fahrig, Lansing, and Lansing M. Hinrichs, Chicago, both of Ill., assignors to Standard Oil Company (Indiana), Chicago, Ill.

Filed Nov. 23, 1979, Ser. No. 96,939

Int. Cl.³ C10G 11/18

U.S. Cl. 208—161

4 Claims



1. In a method for the fluid catalytic cracking of hydrocarbon feedstocks wherein an ascending cocurrent stream of vaporous hydrocarbons and entrained catalyst particulates whose upward flow is at a rate substantially less than the flow rate of said hydrocarbons is effected in an elongated conduit reaction zone, the improvement which comprises:

- (1) altering the direction of flow of said stream of hydrocarbons and catalyst particulates to a downward direction by conducting said stream into a flow reversal means which discharges into a downwardly directed flow reversal conduit;
- (2) accelerating the rate of downward flow of said catalyst

particulates by gravitational force augmenting fluid flow drag forces to impart downward momentum thereto;

- (3) withdrawing cracked hydrocarbon products laterally from the downwardly flowing catalyst particulates and passing said products directly into cyclone separator means thereby effecting rapid disengagement of said cracked hydrocarbon products from said catalyst particulates; and
- (4) contacting the downwardly flowing catalyst particulates with an ascending flow of inert stripping gas after substantial withdrawal of said cracked hydrocarbon products, the downward momentum of said catalyst particulates preventing their passage laterally with the cracked hydrocarbon products and permitting their passage countercurrent to the upward flow of inert stripping gas.

4,295,962

RECOVERING COPPER BY FLOTATION USING N-MERCAPTOALKYL AMIDE DEPRESSANT

Robert M. Parlman, and Ralph P. Williams, both of Bartlesville, Okla., assignors to Phillips Petroleum Company, Bartlesville, Okla.

Filed Apr. 30, 1980, Ser. No. 145,093

Int. Cl.³ B03D 1/06

U.S. Cl. 209—167

6 Claims

1. A process for recovering copper-bearing mineral sulfides from a metallurgical concentrate, said process comprising in a froth flotation process admixing (1) froth floated metallurgical concentrate containing copper-bearing sulfides with (2) an amount of N-mercaptoalkyl amide sufficient to depress the flotation of said copper-bearing mineral sulfide and recovering the non-floated copper-bearing mineral sulfides.

4,295,963

BACKWASHABLE FLUID FILTER

Mordeki Drori, 89 Zahal St., Kiron, Israel


Filed Feb. 7, 1980, Ser. No. 119,388

Claims priority, application Israel, Feb. 15, 1979, 56682

Int. Cl.³ B01D 29/38

U.S. Cl. 210—108

15 Claims



1. A backwashable filtering device including a housing having an inlet connectable to an upstream fluid pipe and an outlet connectable to a downstream fluid pipe, a filter body having an upstream surface communicating with the housing inlet to intercept dirt particles in the fluid flowing in the forward direction from the housing inlet to the housing outlet, a backwash nozzle within the housing and having a nozzle inlet disposed adjacent to the upstream surface of the filter body, means for effecting relative movement between the filter body and the backwash nozzle, and means for connecting the backwash nozzle to the atmosphere for backwashing the filter body; characterized in that the device further includes a valve assembly movable to open or close a passage between the filter body and the housing outlet, spring means tending to move the valve assembly to close said passage, and pressure means for applying to the valve assembly the pressure at a point upstream

of the valve assembly tending to move same to open said passage, whereby under low pressure conditions the valve assembly closes or restricts said passage to the outlet and thereby maintains the pressure for backwashing the filter body via the nozzle.

4,295,964

MOTORCYCLE APPARATUS


James M. Preisler, Bloomington, Minn., assignor to Thomas H. Rudd, Wayzata, Minn.

Filed Feb. 4, 1980, Ser. No. 118,021

Int. Cl.³ B01D 27/10

U.S. Cl. 210—130

19 Claims



1. Device for filtering and cooling oil for attachment to a motorcycle comprising, in combination: an oil filter having a shape and an oil flow passageway including at least one opening; a casing having an outside surface and an inside surface; internal heat dissipating members extending from the inside surface of the casing for retarding oil flow therearound and for receiving and transferring heat from the oil to the casing; external heat dissipating members extending from the outside surface of the casing for receiving and transferring heat from the casing to the atmosphere, with the internal heat dissipating members terminating in and defining an oil filter capturing cavity of a shape and size for receiving the oil filter; an oil filter seat member located within the oil filter capturing cavity of the casing for seating with the opening of the oil filter; first means for allowing oil flow into the oil flow passageway of the oil filter; second means for allowing oil flow out of the casing; and third means for biasing the oil filter toward the oil filter seat member and for allowing the oil to bypass the oil filter when the oil pressure inside the oil filter overcomes the biasing means thus causing the oil filter to unseat from the seat member and allow oil to escape from the opening in the oil filter, wherein the casing includes a front, a back, a top, a bottom, a first side, and a second side, wherein the first and second means are located in the bottom, wherein the internal heat dissipating members comprise, in combination: a first shoulder located in the corner between the front and the top; a second shoulder located in the corner between the front and the bottom; a third shoulder located in the corner between the bottom and the back; a fourth shoulder located in the corner between the top and the back, and wherein a longitudinal cross section of the casing through the front, back, top, and bottom is an isosceles trapezoid.

8. Apparatus for mounting an accessory to a motorcycle frame, with the accessory including a back, comprising, in combination: at least a first member securable to the motorcycle frame, with the securable member including an elongated portion having an enlarged end; a mounting plate having a shape and a thickness, with the mounting plate including at least a first aperture having a size allowing the elongated portion of the securable member to pass therethrough but preventing the enlarged end of the securable member from passing therethrough; at least a first aperture formed in the back of the accessory and having a shape and size complementary to and for receiving the enlarged end of the securable member; means for securing the mounting plate to the back of the accessory with the securable member outstanding from the mounting plate and extending through the mounting plate aperture and

with the enlarged end captured within the accessory aperture by the mounting plate; two abutting members located on opposite sides of the accessory aperture for providing a three point connection with the securable member for preventing the accessory from turning or twisting about the securable member.

4,295,965

MULTI-FILTER CHAMBER AQUARIUM FILTER

Siegfried Köster, Paulsdorfer Strasse 2, D-8000 München 2, Fed. Rep. of Germany

PCT No. PCT/DE79/00006, § 371 Date Aug. 2, 1979, § 102(e) Date Aug. 2, 1979


PCT Filed Jan. 20, 1979, Ser. No. 63,115

Claims priority, application Fed. Rep. of Germany, Jan. 24, 1978, 2802908

Int. Cl.³ E04H 3/20

U.S. Cl. 210—169

10 Claims



1. Aquarium filter for combination with and connection to a suction device (107-109) having an essentially box-like filter cassette (6, 8) of elongated, essentially rectangular cross section adapted for vertically positioning in an aquarium, with a narrow dimension of the cassette facing the bottom of the aquarium, in which the cassette is formed to define two filter chambers (65, 67, 85, 86) spaced from each other, and a clear-water chamber (66, 84) positioned between the filter chamber and in fluid communication with the suction device, said clear-water chamber being separated from said filter chambers by an apertured vertical partitioning wall; and wherein, in accordance with the invention, the walls of the cassette separating said filter chambers from the aquarium comprise removable cover plates (61, 62, 81) extending parallel to the partitioning wall, and formed with openings (610, 620, 810) therein to permit aquarium water to pass therethrough and into the filter chambers, while permitting individual removal of filter material from the filter chambers; the cassette is formed with a lower opening (88) in communication with the clear-water chamber (66, 84); and the suction box (1, 3, 9) is essentially of rectangular or square cross section fitting against said narrow dimension of the cassette and positioned beneath the cassette, said suction box being formed with means (70, 90) communicating with the lower opening in the cassette and hence with the clear-water chamber (66, 84) at the side of the box in engagement with the cassette.

4,295,966

APPARATUS FOR REMOVING CONTAMINANTS FROM LUBRICATING OIL


Ralph W. LeBlanc, and Robert M. Bingham, both of P.O. Box 52734, New Orleans, La. 70152

Filed Jul. 17, 1980, Ser. No. 169,893

Int. Cl.³ B01D 35/18

U.S. Cl. 210—180

11 Claims



1. A refiner for removing contaminants from lubricating oil comprising:

- a fluid containment vessel having a top and a generally vertical axis;
- a plate removably secured in said vessel and dividing said vessel into an upper chamber and a lower chamber; said plate having an upper surface; said surface having a domed shape with a generally smooth arcuate configuration and being raised in a center portion thereof above the remainder thereof; said plate also having a plurality of passageways extending from a lower side of said plate whereat said passageways communicate with said lower chamber to said surface near said center portion thereof;
- filter media located in said vessel lower chamber;
- first conducting means for delivering the oil to said vessel and communicating with said vessel lower chamber such that oil entering said vessel passes through said filter media, then through said passageways, and then flows over said surface;
- second conducting means for removing the oil from said vessel after the oil has passed over said dispersion plate; and
- venting means for exhausting said vessel upper chamber;
- whereby solid contaminants in the oil are substantially removed by said filter media and whereby volatile contaminants in the oil are substantially removed by evaporation while the oil is on said surface in a thin uniform manner even when said vessel axis is canted from vertical and the evaporated volatile contaminants are exhausted from said vessel upper chamber by said venting means.

4,295,967

FLUIDIZED BED CONTACT APPARATUS

Akinori Kurima; Yasuhiro Iwase, and Tadao Kimiwa, all of Yokohama, Japan, assignors to Chiyoda Kako Kensetsu Kabushiki Kaisha, Tokyo, Japan

Continuation of Ser. No. 952,639, Oct. 19, 1978, abandoned, which is a continuation-in-part of Ser. No. 625,777, Oct. 24, 1975, abandoned. This application May 23, 1980, Ser. No. 62,049

Claims priority, application Japan, Oct. 26, 1974, 49-123028

Int. Cl.³ B01D 15/02


U.S. Cl. 210—189

3 Claims

1. An apparatus adapted for contact between divergent materials, and capable of forming a fluidized bed condition, comprising:

- a plurality of trays, each of said plurality of trays being structured so as to have thereon a multiplicity of inverted frustum-shaped depressions adjacent to each other, each

of said inverted frustum-shaped depressions being shaped so as to have a widened upper opening and inner lateral faces which incline inwardly from said upper opening to a narrowed lower opening at the bottom of said inverted frustum-shaped depressions, said trays being positioned vertically over each other so as to form a tower, said trays being positioned in such a manner that the lower narrowed opening of each of said inverted frustum-shaped depressions is vertically skewed with respect to each of the lower narrowed openings in each of the inverted



frustum-shaped depressions in the next vertically positioned tray, in said tower; a housing surrounding said trays so as to form a support for said tower; a particulate feeding means provided on said tower with respect to each of said trays; a particulate material withdrawing means located on said tower; a liquid feeding means located on said tower; and a liquid discharge means located on said tower.

4,295,968

SEPARATING MATERIALS FOR THIN LAYER CHROMATOGRAPHY AND THEIR PREPARATION

Herbert Halpaap, Jugenheim, and Karl-Friedrich Krebs, Darmstadt, both of Fed. Rep. of Germany, assignors to Merck Patent Gesellschaft mit beschränkter Haftung, Darmstadt, Fed. Rep. of Germany

Filed Mar. 20, 1978, Ser. No. 888,595

Claims priority, application Fed. Rep. of Germany, Mar. 19, 1977, 2712113

Int. Cl.³ B01D 15/08

U.S. Cl. 210—198.3

12 Claims

1. In a separating material for thin-layer chromatography, comprising a substrate material having a coating thereon which coating comprises a thin sorbent layer, the improvement wherein the sorbent layer has a surface modified by reacting the sorbent layer with a silanizing agent without the exclusion of moisture.

4,295,969

MAGNETIC FUEL PURIFIER WITH ROTATING PRE-PURIFIER

Gideon Hagberg, Halmstad, Sweden, assignor to Gunner Berg, Glumslöv and Sven-Olle Strömberg, Helsingborg, both of, Sweden

Filed Oct. 1, 1979, Ser. No. 80,304

Claims priority, application Sweden, Oct. 2, 1978, 7810289


Int. Cl.³ B01D 35/06

U.S. Cl. 210—223

5 Claims

1. Magnetic fuel purifier with rotating pre-purifier for liquid fuel and the like with separation of contaminations, partly by centrifugalizing and partly by magnetic action, comprising a conical pre-purifier (46); a tubular, non-magnetic center shaft (42) for supporting the pre-purifier, the center shaft being an inlet for the fuel and having a plurality of through-going ducts

(44) for the passage of fuel, said pre-purifier having pitching longitudinal wing blades (48) rotated by the fuel pressure, whereby the fuel is thrown against conical outer walls of the pre-purifier and thereafter falls downwards; a conical magnet (40) surrounding and firmly applied to the center shaft below the pre-purifier in such manner that the falling fuel strikes the magnet; a collecting container (34) positioned below the magnet; a conical filter (50) surrounding the pre-purifier in such manner that fuel flows from the collecting container through the conical filter out of the purifier, the conical filter being made from sintered bronze ball material; an outer case (22) for holding the pre-purifier, conical magnet, and conical filter and for forming the collecting container; and a lid (24) connected to the outer case, the outer case and lid being made from non-magnetic, transparent material; said blades (48) of said




pre-purifier (46) extending inwardly from the outer walls towards the center shaft (42), said pre-purifier (46) having a closed top with a portion of its upper surface shaped to mate with a portion of the conical filter (50) to thereby center said pre-purifier (46) in said outer case (22), said outer case (22) having a through duct (30) formed in a lower portion thereof communicating with the interior of said center shaft (42) for introducing fuel into said purifier, and said lid (24) having a through duct (32) for passage of purified fuel out of said purifier, said outer walls of said pre-purifier (46) being spaced from and at least partially encompassed by said conical filter (50) so that a fluid flow path is defined therebetween, fuel flowing upwardly from said collecting container (34) into said fluid flow path and through said conical filter (50) into said duct (32) of said lid (24).

4,295,970

FILTER CONVEYING DEVICE FOR FILTER PRESSES
Max Oelbermann, Remscheid, and Karl-August Rademacher, Wuppertal, both of Fed. Rep. of Germany, assignors to Ritter-shaus & Blecher GmbH, Wuppertal, Fed. Rep. of Germany
Filed Jun. 6, 1980, Ser. No. 157,154
Claims priority, application Fed. Rep. of Germany, Jun. 13, 1979, 2923864

Int. Cl.³ B01D 25/00

U.S. Cl. 210—230



1. A device for conveying respective filter plates from a filter plate pack of a filter press, the device including a carriage means adapted to move along the filter press, drive means for selectively moving the carriage means in a forward and reverse direction, means for automatically reversing a direction of the carriage means upon the carriage means encountering a predetermined resistance to movement, characterized in that a pawl means is swingably mounted on the carriage means for engaging behind a foremost filter plate of the filter plate pack during a movement of the carriage means in a first direction of move-

ment, a drop lever means is swingably mounted on the carriage means for engaging a forward portion of the foremost filter plate during a movement of the carriage means in a direction opposite said first direction of movement, said pawl means and said drop lever means being configured such that when they are swung upward into a stop position out of contact with the filter plates they cooperate with one another to hold themselves in said stop position whereby they may travel past the filter plates without contacting said filter plates, and wherein means are provided at a first end of the filter press for swinging the pawl means and drop lever means into the upward stop position so as to enable the pawl means and drop lever means to travel past the filter plates without contact, and in that means are provided on an opposite end of the filter press for swinging the pawl means into a release position so as to release the drop lever means from the stop position.

4,295,971

METHOD FOR CLARIFYING SLIMES

Sanaa E. Khalafalla, Minneapolis, and George W. Reimers, Burnsville, both of Minn., assignors to The United States of America as represented by the Secretary of the Interior, Washington, D.C.

Filed Aug. 14, 1980, Ser. No. 177,975

Int. Cl.³ C02B 9/02

U.S. Cl. 210—695

11 Claims

1. A method for clarifying slimes from the group consisting of iron oxide slimes, oxidized taconite slimes, scrubber water from iron-making furnaces, and kaolin slimes, said method comprising the steps of

- (a) treating the slime with a stabilized aqueous-base magnetic colloid comprising (1) colloidal magnetic particles and (2) at least one surfactant that bridges the slime particles electrostatically to said magnetic particles and that stabilizes said magnetic particles, said surfactant being present in an amount sufficient to perform the bridging and stabilization functions; said magnetic colloid becoming unstable and said magnetic particles thereof irreversibly flocculating when said magnetic colloid is sufficiently diluted, and said magnetic colloid being used in an amount sufficient to provide for particle-to-particle titration between said slime particles and said magnetic particles, whereby said magnetic particles form floccules with said slime particles; and
- (b) separating the clarified slime from the aggregated floccules.

4,295,972

METHOD FOR TREATING WATER CONTAINING WASTES

Takeji Kamei, Fuji, Japan, assignor to Nihon Automatic Machinery Mfg. Co., Ltd., Japan

Division of Ser. No. 35,201, Apr. 30, 1979, Pat. No. 4,226,712.
This application May 7, 1980, Ser. No. 147,381

Claims priority, application Japan, Apr. 28, 1978, 53-51916; Apr. 29, 1978, 53-51195

The portion of the term of this patent subsequent to Oct. 7, 1997, has been disclaimed.


Int. Cl.³ C02F 11/14

U.S. Cl. 210—710

1 Claim

1. A method of treating water containing organic waste comprising the steps of: mixing 100 parts by weight of the organic waste containing 50% to 99.8% by weight of water with from 5 to 40 parts by weight of calcium oxide to produce an exothermic reaction mixture of the calcium oxide and the water containing the waste; heating the reaction mixture using the heat from the exothermic reaction mixture to obtain a preliminary dried mixture; transferring the preliminarily dried mixture to a drying kiln; further drying the preliminarily dried mixture and granulating it in the drying kiln by continuously agitating and heating the preliminarily dried mixture to a temperature of between 100° C. and 300° C. to yield a granulated

product, collecting stinking exhaust gases produced by said mixing of the waste with calcium oxide; channeling the exhaust



gases to a furnace; and burning the exhaust gases in the furnace to produce substantially odorless gases.

4,295,973

PROCESS FOR SEPARATING SOLIDS FROM SUSPENSIONS OF INFLUENT

Kamlesh K. Jain, Phoenixville, Pa., assignor to Fram Industrial Filter Corp., Tulsa, Okla.


Division of Ser. No. 21,276, Mar. 16, 1979, Pat. No. 4,224,157.

This application Apr. 28, 1980, Ser. No. 144,721

Int. Cl.³ C02F 1/52

U.S. Cl. 210—738

3 Claims



1. A process for separating solids from suspensions wherein influent is mixed in an inner mixing compartment of a separator unit, and wherein said influent is transferred to an outer settling compartment from which clarified liquids and settled suspensions are withdrawn, wherein the improvement comprises separating said mixing compartment from said settling compartment with a hydrodynamic changing means, minimizing convective momentum of said influent with said hydrodynamic changing means while transferring said influent from said mixing compartment to said settling compartment, by which said agglomerated solids are prevented from breaking up and are caused to settle without interference from said influent, and continuously decreasing said momentum of said influent flowing through said mixing and settling compartments to cause said solids of increasingly smaller sizes to separate and settle, said step of minimizing said momentum further comprising directing said influent through perforations in said plate which perforations are orientated to eliminate or minimize tangential components of velocity and minimize axial components of said velocity, by which said momentum in said settling compartment is minimized, whereby to maximize a rate of said settling.

4,295,974

BLOOD SAMPLE COLLECTION AND PHASE SEPARATION DEVICE

William D. Cornell, Ballwin, Mo., assignor to Sherwood Medical Industries Inc., St. Louis, Mo.

Filed May 5, 1980, Ser. No. 146,845


Int. Cl.³ B01D 21/26

U.S. Cl. 210—789

19 Claims

19. The method of collecting a sample of whole blood, and separating and partitioning it into its relatively high and low

density phases comprising the steps of providing an evacuated container having a closed bottom end and an open upper end, a phase partitioning device in the container near the upper end of the container which has a main portion spaced from the inner sidewall of the container, a quantity of thixotropic gel-like blood phase partitioning material in an initial location between and in contact with said main portion and inner sidewall of the container, restricted orifice means communicating between the gel-like material and the interior of the container below the partitioning device, and a stopper in the open end of



the container, introducing a sample of whole blood into the interior of the container by piercing the stopper with a needle cannula connected to a source of whole blood, centrifuging the container to centrifugally separate the whole blood sample into its low and high density phases, and moving the gel-like material from its initial location through said restricted orifice means and into the interior of the container below the partitioning device under the influence of centrifugal forces during centrifugation at a flow rate requiring that the barrier formed by the gel-like material takes at least 1 minute to become completely formed.

4,295,975

OIL COLLECTING METHOD

Gösta Walin, L. Montörsgatan 3, Västra Frölunda, Sweden S-421 68


Division of Ser. No. 898,079, Apr. 20, 1978, Pat. No. 4,186,095.

This application Jan. 29, 1980, Ser. No. 116,647

Claims priority, application Sweden, Apr. 27, 1977, 7704814
Int. Cl.³ E02B 15/04

U.S. Cl. 210—800

8 Claims



1. A method of separating and collecting oil floating on the surface of a body of oil-polluted water comprising the steps of: fixedly positioning a stator on the water, said stator being substantially symmetrical about a generally vertical axis and having a downwardly opening central oil-collecting cavity, and a lower oil-contacting and diverting surface which slopes downwardly and inwardly from the periphery of said stator through the surface of the water to the submerged opening of said cavity; rotating a submerged hollow rotor about said vertical axis directly beneath said stator, the rotor having a sidewall defining therewithin a rotor interior, the interior of said rotor communicating with the surrounding body of water through an upper inlet near the surface of the water which

surrounds the lower surface of said stator, and a lower outlet spaced below said inlet in the lower portion of said rotor, said rotation establishing a vortex of liquid in the interior of said rotor which draws a surface layer of oil and water into the upper portion of said rotor through said outlet, and causes the rotating oil to contact the lower surface of said stator to be slowed thereby and diverted inward to said oil-collecting cavity.

4,295,976

FLUORINATED ANTI-STAIN AND SOIL RELEASE FINISHES

Andre L. Dessaint, Nogent sur Oise Creil, and Jean Perronin, Chantilly, both of France, assignors to Produits Chimiques Ugine Kuhlmann, Courbevoie, France

Filed Sep. 28, 1976, Ser. No. 727,497


Claims priority, application France, Oct. 17, 1975, 75 31794

Int. Cl.³ C14C 9/00; C07C 149/20, 149/40; C09K 15/10

U.S. Cl. 252-8.9 32 Claims


1. A fluorinated telomerization product consisting of the reaction product of:

(a) one mole of an ester of one or more polyols with one or more acids of the general formula:



wherein A represents an aliphatic or cyclic hydrocarbon radical and n is a whole number from 1 to 4, and
























(b) 1 to 5 moles of one or more compounds possessing at least one ethylene bond, at least one of these compounds corresponding to the general formula:



wherein Rf represents a perfluorinated chain, straight or branched, containing 1 to 20 carbon atoms,

one of the symbols R is hydrogen and the other is hydrogen or alkyl containing 1 to 4 carbon atoms; and

Rf-B is a residue selected from the group consisting of the residues of following formulae:



wherein

x is a whole number between 1 and 20;

y is a whole number from 1 to 4;

z is a whole number from 1 to 10;

R' is hydrogen, alkyl with 1 to 10 carbon atoms, cycloalkyl with 5 to 12 carbon atoms or hydroxyalkyl with 2 to 4 carbon atoms;

R'', R''', X and X' are the same or different and each represents hydrogen or alkyl with 1 to 4 carbon atoms.

12. A composition for treating a textile to render said textile resistant to soiling comprising an effective amount of a fluorinated product as defined in claim 1 in a solvent medium.

4,295,977

NONIONIC TEXTILE SOFTENER COMPOSITION

Edwin C. Sherburne, Wilmington, Del., assignor to ICI Americas Inc., Wilmington, Del.

Continuation-in-part of Ser. No. 123,874, Feb. 22, 1980, abandoned. This application May 12, 1980, Ser. No. 148,063

Int. Cl.³ D06M 13/02, 13/18

U.S. Cl. 252-8.9

10 Claims

1. A nonionic textile softening composition comprising: (1) from about 70% to about 80% by weight of a blend of (i) a mixture of linear and branched C₁₈ to C₃₂ monohydric alcohols and (ii) a mixture of C₂₄ to C₄₀ hydrocarbons, said blend of alcohols and hydrocarbons having a melting point between 110° F. and about 122° F.;

(2) from about 15% to about 25% by weight of the etherification reaction product of ethylene oxide and blend (1) where from about 30 to about 50 mols of ethylene oxide are reacted with each mol of hydroxyl groups in blend (1); and

(3) from about 3% to about 10% by weight of polyoxyethylene

ether of oxo decyl alcohol wherein the mol ratio of oxyethylene groups to oxo decyl alcohol groups is from about 5 to about 10.

4,295,978

USE OF ISOCHROMAN MUSK COMPOUNDS IN AUGMENTING OR ENHANCING THE AROMA OF DRYER-ADDED FABRIC SOFTENER ARTICLES

Wilhelmus J. Wiegers, Red Bank; Mark A. Sprecker, Sea Bright; Hugh Watkins, Lincroft; Manfred H. Vock, Locust, and Frederick L. Schmitt, Holmdel, all of N.J., assignors to International Flavors & Fragrances Inc., New York, N.Y.




Division of Ser. No. 63,374, Aug. 3, 1979, Pat. No. 4,250,200.

This application Nov. 13, 1980, Ser. No. 206,651


Int. Cl.³ D06M 13/18, 13/16, 15/00

U.S. Cl. 252-8.9





3 Claims











1. A dryer-added fabric softening article comprising a substrate, a substrate coating, and an outer coating, said outer coating coated on said substrate coating and said substrate coating coated on said substrate, said substrate comprising a water dissolvable paper and said outer coating comprising from 0.05% up to 5% by weight of said dryer-added fabric softener article of an indane alkanol or tricyclic isochroman having the structure:



wherein X is hydrogen, methyl or —CH₂—; the dashed line is either a carbon-carbon single bond or no bond; R₁ is hydrogen or methyl; R₂, R₃, R₄ and R₅ represent hydrogen, methyl or isopropyl; with the proviso that R₂ and R₃ are methyl when R₄ is hydrogen and R₅ is isopropyl or R₄ and R₅ represent methyl when R₂ is hydrogen and R₃ is isopropyl; and with the further proviso that the dashed line is a carbon-carbon single bond when X is —CH₂— and the dashed line is no bond when X is hydrogen or CH₃, said indane alkanol or tricyclic isochroman having a structure selected from the group consisting of:



-continued



4,295,979

METHOD AND COMPOSITION FOR INHIBITING CORROSION IN HIGH TEMPERATURE, HIGH PRESSURE GAS WELLS

Shelby P. Sharp, Tulsa, Okla., and Lyman Yarborough, Naperville, Ill., assignors to Standard Oil Company (Indiana), Chicago, Ill.

Filed May 29, 1979, Ser. No. 43,521

The portion of the term of this patent subsequent to Feb. 3, 1998, has been disclaimed.

Int. Cl.³ C23F 11/00

U.S. Cl. 252—8.55 E

5 Claims

1. A method for inhibiting corrosion in a high temperature, high pressure gas well, characterized in that an aqueous or

brine phase is present, but no petroleum condensate phase exists at bottomhole conditions, comprising the steps of:

- adding up to about 27 parts by weight of an alkyl amine per 100 parts by weight of a dialkyl disulfide producing an amine activated dialkyl disulfide solvent.
- adding to said activated dialkyl disulfide solvent at least about 40 parts by weight by elemental sulfur per 100 parts by weight alkyl disulfide oil producing a corrosion inhibitor carrier capable of existing in a liquid phase at bottomhole conditions at said high temperature, high pressure gas well,
- injecting said corrosion inhibitor carrier into said gas well to inhibit corrosion.

4,295,980

WATERFLOOD METHOD

Kaye L. Motz, Ponca City, Okla., assignor to Conoco Inc., Ponca City, Okla.

Continuation-in-part of Ser. No. 910,243, May 30, 1978, abandoned. This application Dec. 14, 1979, Ser. No. 103,642

Int. Cl.³ E21B 43/22

U.S. Cl. 252—8.55 D

13 Claims

1. An improvement in the method of recovering hydrocarbons from a petroliferous subterranean formation, said method including the step of injecting into said formation an aqueous saline mixture containing an alkali metal hydrocarbon sulfonate and a solubilizing agent, said improvement comprising injecting into said formation an aqueous saline mixture containing an effective amount of

- about 0.5 to about 25 weight percent of an alkali metal linear alkane sulfonate wherein the alkane moiety contains 20 to 24 carbon atoms,
 - about 1 to about 25 weight percent of a water-soluble solubilizing agent, and
 - about 0.5 to about 3 weight percent of a salinity agent which is an alkali metal salt,
- said method being characterized further in that the water-soluble solubilizing agent is a water-soluble C₁–C₅ alcohol.

4,295,981

PRODUCTION OF OVERBASED MAGNESIUM DETERGENT ADDITIVES

Victor C. Burnop, Church Croft, West Challow, Wantage, Oxfordshire, England

Filed Jul. 21, 1980, Ser. No. 169,513

Claims priority, application United Kingdom, Jul. 27, 1979, 26211/79

Int. Cl.³ C10M 1/40, 1/20, 3/34, 3/14

U.S. Cl. 252—33.4

7 Claims

1. A process comprising the following steps:

- forming a reaction mixture comprising:
 - a non-volatile diluent oil
 - magnesium alkoxylalkoxide as a solution in the alkoxylalcohol from which it is derived
 - one or more hydrocarbyl-substituted phenols or metal phenates wherein the or each hydrocarbyl group contains no more than 60 carbon atoms or one or more sulphurised phenols having one or more hydrocarbyl group substituents each substituent containing no more than 60 carbon atoms or mixtures of said surfactants
 - adjusting the concentration of the free alkoxylalcohol to be less than 5%
 - adding at least one mole of water for every gram atom of the magnesium present in excess of the amount of magnesium required to neutralise the surfactant and hydrolysing the magnesium alkoxylalkoxide
 - introducing carbon dioxide into the reaction mixture whilst at a temperature not above 100° C.
 - removing volatiles from the reaction mixture.
3. A process according to claim 1 in which sulphonate or a sulphonic acid is included in the reaction mixture.

4,295,982

SULFURIZED AMINOGUANIDINE REACTION PRODUCT AND LUBRICANT COMPOSITIONS CONTAINING SAME

Gerassimos Frangatos, Haddonfield, N.J., assignor to Mobil Oil Corporation, New York, N.Y.

Filed May 12, 1980, Ser. No. 148,898

Int. Cl.³ C10M 1/38

U.S. Cl. 252—42

10 Claims

1. A product obtained by (1) reacting an aminoguanidine or an acid salt thereof with an unsaturated monocarboxylic acid at a temperature of from about 150° C. to about 275° C. and (2) reacting the product of (1) with sulfur at from about 150° C. to about 225° C.

5. A lubricant composition comprising a major proportion of a mineral lubricating oil, a synthetic lubricating oil or a grease from either of these and an anti-rust amount of the product of claim 1.

9. The composition of claim 5 wherein the lubricant is a grease.

10. The composition of claim 9 wherein the thickener for said grease is a lithium hydroxystearate soap.

4,295,983

LUBRICATING OIL COMPOSITION CONTAINING BORONATED N-HYDROXYMETHYL SUCCINIMIDE FRICTION REDUCERS

Andrew G. Papay, Manchester, and Joseph P. O'Brien, Kirkwood, both of Mo., assignors to Ethyl Corporation, Richmond, Va.

Filed Jun. 12, 1980, Ser. No. 158,715

Int. Cl.³ C10M 1/10

U.S. Cl. 252—49.6

16 Claims

1. A friction reducing lubricating oil additive comprising the reaction product of an N-hydroxymethyl aliphatic hydrocarbyl succinimide with an amount of a boronating agent sufficient to impart about 0.1 to 1.5 weight percent boron to said reaction product, said reaction product being made at about 50°–200° C., said N-hydroxymethyl aliphatic hydrocarbyl succinimide prepared by reacting NH₃ with an aliphatic C₁₂–C₃₆ hydrocarbyl succinic anhydride to form the corresponding succinimide and subsequently reacting the succinimide with formaldehyde to form said N-hydroxymethyl aliphatic hydrocarbyl succinimide.

9. Lubricating oil formulated for use in the crankcase of an internal combustion engine containing a friction-reducing amount of the reaction product of claim 1.

4,295,984

PASTE-LIKE, VISCOUS DAMPING MEDIUM COMPRISING POLYGLYCOL ETHERS AND/OR ESTERS

Kaspar Lochner, Karlsburgstr. 7b, 8000 München, Fed. Rep. of Germany

Filed Oct. 3, 1979, Ser. No. 81,381

The portion of the term of this patent subsequent to Feb. 17, 1998, has been disclaimed.

Int. Cl.³ C04B 43/00

U.S. Cl. 252—62

24 Claims

1. A paste-like, viscous damping medium dispersion for damping mechanical and acoustic vibrations, comprising polyglycol ethers and/or polyglycol esters having a viscosity of about 10 cSt to 1000 cSt at 50° C. and a relative average molecular weight of about 700 to 20000, 30 to 70% by weight of ground graphite having a particle size of less than 100μ, 0.1 to 8% by weight of a wetting agent and 0.1 to 10% by weight of finely ground aluminum silicate or amorphous silicon dioxide as a viscosity stabilizer, the % weight being based in each case on the total weight of the dispersion, the viscosity of the dispersion being about (1 to 4) × 10⁶ cP at 25° C.

4,295,985

METHOD OF REMOVAL OF CHLORINE RETAINED BY HUMAN SKIN AND HAIR AFTER EXPOSURE TO CHLORINATED WATER, AND SOAP AND SHAMPOO COMPOSITIONS ADAPTED TO EFFECT SAID REMOVAL

Henry G. Petrow, 32 Garfield St., and Mark L. Weissman, 742 Belmont St., both of Watertown, Mass. 02172

Continuation-in-part of Ser. No. 88,144, Oct. 25, 1979, abandoned, which is a continuation of Ser. No. 900,601, Jun. 7, 1978, abandoned. This application May 1, 1980, Ser. No. 145,681

Int. Cl.³ C11D 7/32; D06L 3/10

U.S. Cl. 252—105

10 Claims

1. A toilet soap composition for cleansing and removing retained chlorine from human skin and hair after immersion in chlorine containing waters, said composition consisting essentially of a chemically stable, uniform mixture of a toilet soap and a water soluble, non-toxic and harmless-to-the-skin chlorine-reducing agent which is a mixture of from about 50 to about 30% by weight urea and from about 50 to about 70% by weight of an alkali metal thiosulfate, said agent being present in said mixture in amount between at least about 2% and less than about 15% by weight of said soap in said mixture and being compatible with said soap.

4,295,986

LOW TEMPERATURE CATALYTIC REDUCTION

Roy G. Gordon, 22 Highland St., Cambridge, Mass. 02138

Filed May 14, 1979, Ser. No. 38,898

Int. Cl.³ C07B 1/00; C09K 3/00

U.S. Cl. 252—188

15 Claims

1. A process for reducing compounds having reducible electronegative functionality, said process comprising the step of carrying out said reduction in a reaction medium which comprises a reducing agent which is a hydride of an alkali metal, and a catalyst which is the borohydride of an alkali metal, and an ether solvent in which the borohydride catalyst is soluble.

4,295,987

CROSS-LINKED SODIUM POLYACRYLATE ABSORBENT

Lawrence R. Parks, Cincinnati, Ohio, assignor to The Procter & Gamble Company, Cincinnati, Ohio

Filed Dec. 26, 1979, Ser. No. 106,958

Int. Cl.³ B01J 20/04; D21D 3/00; B01J 20/10, 20/26

U.S. Cl. 252—194

18 Claims

1. An absorbent composition comprising a copolymer of acrylic acid cross-linked with a first cross-linking component comprising a monomer having at least two vinyl groups and a second cross-linking component comprising an ionic divalent cation.

4,295,988

MAGNETO-OPTIC Bi₁Lu₂Fe₅O₁₂ CRYSTALS

Gary L. Nelson, Eagan, and William A. Harvey, Minneapolis, both of Minn., assignors to Sperry Corporation, New York, N.Y.

Filed Jul. 18, 1979, Ser. No. 58,710


Int. Cl.³ C30B 29/28

U.S. Cl. 252—584

2 Claims

1. A mixture for growing a Bi₁Lu₂Fe₅O₁₂ garnet crystal on a Gd₃Ga₅O₁₂ garnet substrate in a liquid phase epitaxial process, said mixture consisting essentially of PbO, Bi₂O₃, Fe₂O₃,

Lu_2O_3 and CaO in concentrations sufficient to grow said $\text{Bi}_2\text{Lu}_2\text{Fe}_5\text{O}_{12}$ garnet crystal and the latter CaO in a concentration



such that the molar ratio of CaO to Lu_2O_3 is in the range of 0.05 to 0.40.

4,295,989

LUMINESCENT HAFNIA COMPOSITION

Philipp H. Klein, Washington, D.C.; Arrigo Addamiano, and Roger Allen, both of Alexandria, Va., assignors to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Jun. 23, 1980, Ser. No. 162,347

Int. Cl.³ C09K 11/463

U.S. Cl. 252—301.4 F

11 Claims

1. A blue-luminescing material of $3\text{HfO}_2 \cdot \text{Y}_2\text{O}_3$ with a Ce^{3+} dopant in an amount of 0.1 to 1.0 weight percent exhibiting a cubic crystalline structure.

4,295,990

REAGENT FOR THE QUANTITATIVE DETERMINATION OF WATER

Antonie E. Verbeek, and Jozef M. J. Mattheij, both of Deventer, Netherlands, assignors to J. T. Baker Chemicals B.V., Deventer, Netherlands

Filed Jun. 9, 1980, Ser. No. 157,440

Claims priority, application European Pat. Off., Jul. 26, 1979, 79102673.5

Int. Cl.³ G01N 31/00; C09K 3/00

U.S. Cl. 252—408

6 Claims

1. A reagent for the quantitative determination of water in combination with a titration solution containing iodine, which reagent contains sulfur dioxide and an anhydrous alkali metal acetate in an anhydrous lower aliphatic alcohol as solvent, characterized in that the lower aliphatic alcohol is selected from the group consisting of 2-methoxy ethanol or a mixture of 2-methoxy ethanol and methanol in a volume ratio of at least 10:90.

4,295,991

TITANIUM TRICHLORIDE CATALYST COMPONENT AND THE PROCESS FOR THE PRODUCTION THEREOF
Harry J. Wristers, Baytown, Tex., assignor to Exxon Research & Engineering Co., Florham Park, N.J.

Filed Sep. 26, 1978, Ser. No. 945,929

Int. Cl.² C08F 4/64

U.S. Cl. 252—429 B

47 Claims

1. A non-friable, highly active Ziegler-type TiCl_3 catalyst composition obtained by:

- (1) contacting TiCl_4 with an organoaluminum compound at a temperature in the range of about -50°C . to about 30°C . to produce a TiCl_3 reduced solid product,
- (2) contacting the reduced solid TiCl_3 product with a minor amount of an α -olefin having at least three carbon atoms under polymerization conditions to obtain a reduced TiCl_3 solid product containing about 1 to about 1,000 wt.% of prepolymerized α -olefin based on the weight of TiCl_3 ,
- (3) treating said prepolymerized reduced solid with one of
 - (a) a chlorinated hydrocarbon having at least 2 carbon

atoms and a Lewis base complexing agent or (b) TiCl_4 and a Lewis base complexing agent to convert the prepolymerized TiCl_3 reduced solid to a substantially non-friable highly active, crystalline prepolymerized TiCl_3 composition.

4,295,992

SUPPORT PREPARED FROM ORGANOMAGNESIUM COMPOUNDS AND SILICON HALIDES; AND CATALYSTS FOR POLYMERIZING OLEFINS

Ronald L. Gibbs, Midland, Mich., assignor to The Dow Chemical Company, Midland, Mich.

Continuation-in-part of Ser. No. 102,808, Dec. 12, 1979, abandoned, which is a continuation of Ser. No. 24,487, Mar. 27, 1979, abandoned, which is a continuation-in-part of Ser. No. 920,769, Jun. 30, 1978, abandoned, which is a

continuation-in-part of Ser. No. 837,665, Sep. 29, 1977, abandoned. This application Jun. 17, 1980, Ser. No. 160,332

Int. Cl.³ C08F 4/02, 4/64, 10/02, 10/06

U.S. Cl. 252—429 C

30 Claims

1. A catalyst support which comprises the reaction product formed by reacting (1) a mixture of an organomagnesium compound represented by the formula MgR_2 and a silicon halide represented by the formula $\text{R}'_4\text{SiX}_n$, said mixture being in a non-polar solvent, with (2) an alcohol represented by the formula $\text{R}''\text{OH}$; wherein the organomagnesium compound is or can be rendered hydrocarbon soluble and wherein each R, R' and R'' is independently an aliphatic hydrocarbon group having from 1 to about 20 carbon atoms, X is Cl, Br or I, n has a value of from 1 to 4 and wherein the molar ratio of $\text{R}''\text{OH}:\text{MgR}_2$ is at least 2:1 and the molar ratio of $\text{R}''\text{OH}:\text{R}'_4\text{SiX}_n$ is sufficient so as to provide at least one X group per OH group.

2. The catalyst support of claim 1 wherein R has from about 2 to about 8 carbon atoms, R' has from about 1 to about 6 carbon atoms, R'' is an aliphatic group having from about 1 to about 6 carbon atoms, X is chlorine or bromine; wherein the ratio of $\text{R}''\text{OH}:\text{R}'_4\text{SiX}_n$ is sufficient so as to provide from 2 to about 3 X groups per OH group; and wherein said non-polar solvent has a hydrocarbon having from about 5 to about 10 carbon atoms.

3. A catalyst composition resulting from the addition of a reducing agent to a mixture of the support of claims 1, 2 or 3 suspended in an inert liquid hydrocarbon and a transition metal compound of Groups 4b, 5b, 6b, 7b, or 8 of Mendeleev's Periodic Table under conditions so as to produce a catalytically active product and in proportions such that the magnesium: transition metal atomic ratio is from about 0.1:1 to about 30:1 followed by washing the resultant solid catalyst product with an inert liquid hydrocarbon.

4,295,993

CATALYTIC COMPOSITE, METHOD OF MANUFACTURE AND PROCESS FOR USE

David H. J. Carlson, Park Ridge, Ill., assignor to UOP Inc., Des Plaines, Ill.

Filed Jan. 4, 1980, Ser. No. 109,934

The portion of the term of this patent subsequent to Jun. 30, 1998, has been disclaimed.

Int. Cl.³ B01J 31/22

U.S. Cl. 252—430

24 Claims

1. A catalytic composite comprising a metal chelate, an alkali metal hydroxide, and a quaternary ammonium hydroxide disposed on a molecular sieve support, the quaternary ammonium hydroxide represented by the structural formula:



wherein R is a hydrocarbon radical containing up to about 20 carbon atoms and selected from the group consisting of alkyl, cycloalkyl, aryl, alkaryl and aralkyl, and R' is a substantially straight-chain alkyl radical containing from about 5 to about 20 carbon atoms, said alkali metal hydroxide comprising at least about 10 wt. % of said catalytic composite.

4,295,994

CELLULOSE ACETATE BUTYRATE BOUND ZEOLITE ADSORBENTS

Santi Kulprathipanja, Hoffman Estates, Ill., assignor to UOP Inc., Des Plaines, Ill.

Continuation-in-part of Ser. No. 48,955, Jun. 15, 1979, Pat. No. 4,248,737. This application Apr. 11, 1980, Ser. No. 139,492

Int. Cl.³ B01J 29/08, 20/18

U.S. Cl. 252—430

14 Claims

1. An adsorbent comprising a zeolite crystalline aluminosilicate suitable for use in a process for the separation of a component from a feed mixture comprising an aqueous solution of a mixture of components by contacting said solution with said adsorbent, the silicon constituent of said adsorbent tending to dissolve in said solution resulting in the undesirable disintegration of said crystalline aluminosilicate, the adsorbent additionally containing a water permeable binder material comprising cellulose acetate butyrate which substantially reduces the extent of dissolution of said silicon constituent and the extent of said disintegration of said adsorbent.

3. The adsorbent of claim 2 further characterized in that said crystalline aluminosilicate contains cations at exchangeable cationic sites selected from the group consisting of alkali metals and alkali earth metals.

4,295,995

CATALYSTS HYDROCARBON TREATING PROCESSES

Roby Bearden, Jr., and Clyde L. Aldridge, both of Baton Rouge, La., assignors to Exxon Research & Engineering Co., Florham Park, N.J.

Continuation-in-part of Ser. No. 955,526, Oct. 30, 1978, which is a continuation-in-part of Ser. No. 847,898, Nov. 2, 1977, Pat. No. 4,134,825. This application Nov. 1, 1979, Ser. No. 90,415

Int. Cl.³ B01J 23/84, 23/85, 27/04, 31/12

U.S. Cl. 252—431 C

20 Claims

1. A catalyst comprising a composition comprising a metal component, carbon and hydrogen deposited on a support selected from the group consisting of solid metals and metal alloys of metals of Groups IB, II, III, IV, VB, VIB, VIIIB, VIII and mixtures thereof of the Periodic Table of Elements, said support having a surface area of less than about 5 square meters per gram, and the metal constituent of said metal component of said composition being selected from the group consisting of metals of Groups II, III, IV, V, VIB, VIIIB, VIII and mixtures thereof of the Periodic Table of Elements, said composition having a surface area of at least about $50\text{ m}^2/\text{g}$, said catalyst having been prepared by the steps which comprise:

- (a) dispersing in a hydrocarbon oil having a Conradson carbon content up to about 50 weight percent, (1) a thermally decomposable metal compound in an amount sufficient to provide a ratio of atoms of oil Conradson carbon to atom of metal constituent of said thermally decomposable compound of less than about 750 to 1, said metal constituent being selected from the group consisting of Group II, Group III, Group IV, Group V, Group VIB, Group VIIIB, and Group VIII of the Periodic Table of Elements and mixtures thereof, and (2) said support;
- (b) heating the resulting mixture in the presence of a gas selected from the group consisting of a hydrogen-contain-

ing gas, a hydrogen sulfide-containing gas and a gas comprising hydrogen and hydrogen sulfide, and
(c) recovering a supported catalyst.

4,295,996

CATALYSTS FOR HYDROCARBON TREATING PROCESSES

Roby Bearden, Jr.; Clyde L. Aldridge, and Lloyd A. Pine, all of Baton Rouge, La., assignors to Exxon Research & Engineering Co., Florham Park, N.J.

Filed Nov. 13, 1979, Ser. No. 93,698

Int. Cl.³ B01J 23/74, 27/04, 31/12

U.S. Cl. 252—431 C

21 Claims

1. A catalyst comprising a composition comprising a metal component, carbon and hydrogen deposited on a support, the metal constituent of said metal component of said composition being selected from the group consisting of metals of Groups II, III, IV, V, VIB, VIIIB, VIII and mixtures thereof of the Periodic Table of Elements, said composition having a surface area of at least about $50\text{ m}^2/\text{g}$ and said support being an aluminum alloy powder having a surface area of less than 5 square meters per gram, said alloy having been prepared by atomizing said aluminum alloy, in molten state, into a stream selected from the group consisting of water, a gas and mixtures thereof, said catalyst having been prepared by the steps which comprise:

- (a) dispersing in a hydrocarbon oil having a Conradson carbon content up to about 50 weight percent, (1) a thermally decomposable metal compound in an amount sufficient to provide a ratio of atoms of oil Conradson carbon to atom of metal constituent of said thermally decomposable metal compound of less than about 750 to 1, said metal constituent being selected from the group consisting of Group II, Group III, Group IV, Group V, Group VIB, Group VIIIB, and Group VIII of the Periodic Table of Elements and mixtures thereof, and (2) said support;
- (b) heating the resulting mixture in the presence of a gas selected from the group consisting of a hydrogen-containing gas, a hydrogen sulfide-containing gas and a gas comprising hydrogen and hydrogen sulfide, and
- (c) recovering a supported catalyst.

4,295,997

 SO_2 ACTIVATION OF SUPPORTED CHROMIUM OXIDE CATALYSTS

Max P. McDaniel, and Melvin B. Welch, both of Bartlesville, Okla., assignors to Phillips Petroleum Company, Bartlesville, Okla.

Continuation-in-part of Ser. No. 2,633, Jan. 11, 1979, abandoned. This application Feb. 28, 1980, Ser. No. 125,435

Int. Cl.³ B01J 27/02, 23/26, 21/08

U.S. Cl. 252—439

8 Claims

1. A method for producing an activated catalyst said method comprising:

- (1) contacting a catalyst comprising chromium on a silica-containing support with a gaseous environment consisting essentially of sulfur dioxide and oxygen at a temperature within a temperature range and for a time sufficient to activate the catalyst and subsequently
 - (2) maintaining a temperature within the contact temperature range of step (1) while contacting said catalyst with a gaseous environment consisting essentially of oxygen and gases inert to reaction with the catalyst.
2. A method of claim 1 wherein the catalyst is contacted

with a gaseous environment consisting essentially of oxygen and gases inert to reaction with the catalyst while the temperature is being increased prior to contact with sulfur dioxide.

4,295,998

SELENIUM OR TELLURIUM TREATED SILICA

Gil R. Hawley, Bartlesville, Okla., assignor to Phillips Petroleum Company, Bartlesville, Okla.

Filed Mar. 14, 1980, Ser. No. 130,632

Int. Cl.³ B01J 21/06, 27/00

U.S. Cl. 252—439

16 Claims

1. A process comprising a first step wherein silica is contacted with a treating agent selected from at least one of selenium or tellurium under nonoxidizing conditions at a temperature of at least 370° C. and a subsequent second step wherein it is contacted with an oxidizing ambient at a temperature within the range of 370°-900° C.

2. A method according to claim 1 for producing a catalyst wherein said silica contains a chromium compound and is heated in the presence of oxygen prior to said treatment with said selenium or tellurium, said selenium or tellurium being in elemental form and being used in an amount within the range of 0.05 to 1 weight percent of the element based on the weight of the oxidized catalyst and wherein said oxidizing ambient comprises oxygen.

4,295,999

POLYMERIZATION CATALYST

Lynn H. Slauch, Houston, Tex., assignor to Shell Oil Company, Houston, Tex.

Division of Ser. No. 86,013, Oct. 17, 1979, Pat. No. 4,239,872.

This application May 21, 1980, Ser. No. 152,209

Int. Cl.³ B01J 23/20, 23/24, 21/00

U.S. Cl. 252—455 R

16 Claims

1. A process for the preparation of a catalyst suitable for polymerization reactions which process comprises:

- impregnating a silica or alumina support with a transition metal salt decomposable upon calcination to the oxide wherein said metal salt is selected from the group consisting of vanadium, titanium, chromium or mixtures thereof;
 - calcining the metal impregnated support at a temperature ranging from about 450° C. to about 1000° C.;
 - impregnating the calcined support with a solution of aluminum hydride; and
 - heating the hydride impregnated support in hydrogen at a temperature range from about 200° C. to about 600° C.
4. The process of claims 1, 2 or 3 wherein the support is silica.

7. The process of claims 1, 2 or 3 wherein the transition metal ranges from about 0.1 to about 20 percent by weight (measured as the metal) of the total catalyst and the aluminum added as aluminum hydride ranges from about 0.1 to about 25 percent by weight (measured as the metal) of the total catalyst.

4,296,000

ADSORBENTS FOR POLYOL PURIFICATION

Satish K. Wason, Churchville, Md., assignor to J. M. Huber Corporation, Locust, N.J.

Continuation-in-part of Ser. No. 74,226, Sep. 10, 1979, which is a continuation of Ser. No. 869,347, Jun. 13, 1978, abandoned.

This application Jul. 25, 1980, Ser. No. 172,335

Int. Cl.³ B01J 20/10, 20/08, 20/04

U.S. Cl. 252—455 R

3 Claims

1. A method of producing an adsorbent for polyol purification comprising a synthetic amorphous silica having at least 70% of the silica larger than 44 microns produced by the method comprising the steps of:

(a) subjecting an aqueous dispersion including finely divided silica and a sodium hydroxide to hydrothermal treatment at a temperature in the range from about 138 to 210 degrees Celsius and for a period of time of from about 2.5 to 4.5 hours and sufficient to react the silica and said sodium hydroxide to form a reaction mixture of partly polymerized sodium silicate, said aqueous dispersion having a silica/sodium oxide weight ratio of at least 1.8:1;

(b) spray-drying said reaction mixture at a temperature of at least 204 degrees Celsius to form minute hollow spheres of sodium polysilicate having a bulk density of about 0.4 g/cc;

(c) reacting the polysilicate with a 5 to 15% sulfuric acid solution to form a synthetic amorphous silica; and

(d) filtering, washing and drying the synthetic amorphous silica.

2. A method of producing an adsorbent according to claim 1 wherein a metal cation adduct selected from the group consisting of aluminum, magnesium, zinc and calcium is added to said synthetic silica until the silica contains up to 5% by weight of said metal cation adduct.

4,296,001

TITANIUM IMPREGNATED SILICA-CHROMIUM CATALYSTS

Gil R. Hawley, Bartlesville, Okla., assignor to Phillips Petroleum Company, Bartlesville, Okla.

Filed Feb. 6, 1980, Ser. No. 118,838

Int. Cl.³ B01J 21/06, 23/26

U.S. Cl. 252—458

38 Claims

1. A process for producing a chromium-containing catalyst comprising impregnating a dry silica xerogel, formed by drying a silica hydrogel, with an aqueous solution of a hydrolysis resistant titanium compound.

11. A process for preparing a chromium-containing catalyst comprising forming a silica hydrogel containing a hydrolysis resistant titanium compound, and drying said hydrogel to form a xerogel.

4,296,002

METAL OXIDE VARISTOR MANUFACTURE


Theodore O. Sokoly, Racine, and John Niedzialkowski, Milwaukee, both of Wis., assignors to McGraw-Edison Company, Rolling Meadows, Ill.

Filed Jun. 25, 1979, Ser. No. 51,872

Int. Cl.³ H01B 1/06

U.S. Cl. 252—518

6 Claims



1. A method of making a metal oxide varistor, which comprises the steps of:

forming a powdered mixture comprised of at least one electrically conductive metal oxide powder, and a small percentage of at least one preselected powdered additive, said additive being selected from the group consisting of different metal oxides and metal fluorides;

forming of said powdered mixture, by pressing, a plurality of

blocks, each having complementary top and bottom surfaces, forming a stack of said plurality of blocks; (and) sintering said stack of blocks, whereby said complementary abutting top and bottom surfaces of adjacent blocks are bonded together to form a varistor; and applying metallic contacts only to the top and bottom surfaces of said varistor.

4,296,003

ATOMIZED DIELECTRIC FLUID COMPOSITION WITH HIGH ELECTRICAL STRENGTH

Ronald T. Harrold, Murrsville, and Lawrence E. Ottenberg, East Huntingdon Township, Westmorland County, both of Pa., assignors to Electric Power Research Institute, Inc., Palo Alto, Calif.

Filed Jun. 27, 1980, Ser. No. 163,901

Int. Cl.³ H01B 3/24

U.S. Cl. 252—570

14 Claims

1. A dielectric fluid composition consisting of a mixture of (a) a first fluid selected from the group consisting of electro-negative gases, electropositive gases, and mixtures thereof, and

(b) a second fluid including an atomized liquid selected from the group consisting of chlorinated liquids, fluorocarbon liquids, and mixtures thereof and having a droplet size of from about 0.1 μ to about 25 μ in diameter, and wherein the mixture has a pressure of from about 40 Torr to about 730 Torr.

4,296,004

POLYCYCLIC POLYAMINES

Edgar R. Rogier, Minnetonka, Minn., assignor to Henkel Corporation, Minneapolis, Minn.

Division of Ser. No. 74,368, Sep. 10, 1979, Pat. No. 4,229,376.


This application May 23, 1980, Ser. No. 152,905

Int. Cl.³ C08G 59/50

U.S. Cl. 260—18 EP

12 Claims

1. A process for curing a polyamine of the formula:



wherein the above formula m is equal to 0 or 1; x and y are selected from the group consisting of: $-\text{CH}_2\text{NH}_2$; $-\text{CH}_2\text{NH}(\text{CH}_2\text{CHR}_4\text{CH}_2\text{NH}_2)$; and $-\text{CH}_2\text{N}(\text{CH}_2\text{CHR}_4\text{CH}_2\text{NH}_2)_2$, and mixtures thereof, wherein R_1 , R_2 , R_3 , and R_4 are hydrogen or methyl and mixtures thereof, provided that both x and y may not be CH_2NH_2 comprising contacting the amine with an epoxy resin.

4,296,005

ADDUCTS CONTAINING HYDROXYL GROUPS FROM MONONUCLEAR HYDANTOIN GLYCIDYL COMPOUNDS AND NON-AROMATIC DICARBOXYLIC ACIDS

Marianne Di Benedetto, Pleasantville, N.Y., assignor to Ciba-Geigy Corporation, Ardsley, N.Y.

Continuation-in-part of Ser. No. 107,234, Dec. 26, 1979, abandoned. This application Oct. 27, 1980, Ser. No. 200,739

Int. Cl.³ C08G 59/26, 63/46, 63/42, 12/42


U.S. Cl. 260—18 EP

14 Claims

1. An advanced addition product containing hydroxyl groups, which is obtained by heating a mixture comprising:


(a) one equivalent of a mononuclear hydantoin glycidyl compound selected from the group consisting of

(1) a compound of the formula I




(I)

(2) a compound of the formula II



(II)

(3) a compound of the formula III



(III)

(4) any combination of compounds of the formulae I, II, or III,

wherein R_1 , R_2 , R_3 , R_4 , R_6 and R_7 are independently alkyl of 1 to 8 carbon atoms or cycloalkyl of 5 to 6 carbon atoms or R_1 and R_2 together, R_3 and R_4 together and R_6 and R_7 together are tetramethylene or pentamethylene, and R_5 and R_8 independently are hydrogen or methyl;

(b) 0.7 to 2.0 equivalents of a non-aromatic dicarboxylic acid of 9 to 44 carbon atoms; and

(c) 0.0 to 0.5 equivalents of a monocarboxylic acid of 6 to 18 carbon atoms.

4,296,006

BINDER FOR COATING COMPOSITIONS AND ITS USE
Volker Bugdahl; Gerhard Morlock; Werner Reidt, all of Hanau, and Emil Kerschner, Rodenbach, all of Fed. Rep. of Germany, assignors to Degussa Aktiengesellschaft, Frankfurt, Fed. Rep. of Germany

Filed Feb. 19, 1980, Ser. No. 122,492

Claims priority, application Fed. Rep. of Germany, Feb. 22, 1979, 2906844

Int. Cl.³ C09D 3/58

U.S. Cl. 260—23 EP

18 Claims

1. A binder for coating compositions based on a mixture of an unsaturated β -hydroxy ester with copolymerizable monomers, said binder consisting essentially of, on a total weight basis:

(A) 25 to 60 weight percent of an unsaturated β -hydroxy ester which is produced by reacting an epoxy resin based on bisphenol A and epichlorohydrin with an epoxide equivalent weight between 800 and 3000 and an epoxide equivalent weight between 400 and 2500 with a mixture of

(a) 74 to 64 mole percent of methacrylic acid, acrylic acid, or a mixture of methacrylic acid and acrylic acid, and

(b) 26 to 36 mole percent of at least one saturated aliphatic monocarboxylic acid having 8 to 20 carbon atoms or a mixture of at least one saturated aliphatic monocarboxylic acid having 8 to 20 carbon atoms with up to 20 mole percent of an unsaturated aliphatic monocarboxylic acid having 8 to 20 carbon atoms, and

(B) 75 to 40 weight percent of a mixture based on the weight of component (B) of

(a) 70 to 95 weight methyl methacrylate,

(b) 30 to 5 weight percent of at least one monomer of the

formula $\text{CH}_2=\text{CR}_1-\text{COOR}_2$ where R_1 is hydrogen or a methyl group and R_2 is a straight chain alkyl group with 4 to 10 carbon atoms, a branched alkyl group with 6 to 12 carbon atoms, a hydroxy-alkyl group with 2 to 4 carbon atoms or a saturated hydrocarbon group interrupted by ether oxygen atoms containing 3 to 10 carbon atoms; and

(c) 0 to 3 weight percent of at least one crosslinking agent for acrylate or methacrylate resins.

4,296,007

NITRILE RUBBER CONTAINING CADMIUM ANTIOXIDANTS

Roger E. Morris, Cuyahoga Falls, and August H. Jorgensen, Jr., Rocky River, both of Ohio, assignors to The B. F. Goodrich Company, Akron, Ohio


Filed Mar. 27, 1980, Ser. No. 134,591

Int. Cl.³ C08K 5/18, 5/13


U.S. Cl. 260—23.7 N

20 Claims


1. Nitrile rubber, which is a polymer of a nitrile and more than 40% diene, containing an effective amount of one or more of the following antioxidants in the form of cadmium salts:




where Ar is an aromatic group; R is hydrogen, alkyl group of 1 to 4 carbon atoms, or oxyalkylene group of 1 to 4 carbon atoms; R^1 is alkylene group of 1 to 20 carbon atoms,




where R^2 is alkylene group of 1 to 20 carbon atoms,




where R^3 is alkylene group of 1 to 8 carbon atoms, and n is a number of 1 to 20; R^4 is



or $\text{---} \text{OR}^2 \text{---}$ group; and R^5 and R^6 are same or different groups attached to the Ar group which are selected from hydrogen and alkyl radicals which individually contain 1 to 8 carbon atoms; the nitrile is defined by the formula




where R is selected from hydrogen, halogens, alkyl radicals of 1 to 8 carbon atoms, and aryl radicals; and the diene is defined by the formula




where X is selected from hydrogen, halogens, alkyl radicals of 1 to 5 carbon atoms, and aryl radicals.


13. In the process for making finished synthetic nitrile rubber, the improvement comprising contacting nitrile rubber latex wherein the nitrile rubber is a polymer of a nitrile and more than 40% diene with cadmium coagulating agent and an effective amount of one or more of the antioxidants, in the form of alkali metal salts which are converted to cadmium salts upon contact with the cadmium coagulating agent, the antioxidants are represented by the following formulas:




where Ar is an aromatic group; R is hydrogen, alkyl group of 1 to 4 carbon atoms, or oxyalkylene group of 1 to 4 carbon atoms; R^1 is alkylene group of 1 to 20 carbon atoms,



where R^2 is alkylene group of 1 to 20 carbon atoms,



where R^3 is alkylene group of 1 to 8 carbon atoms, and n is a number of 1 to 20; R^4 is



or $\text{---} \text{OR}^2 \text{---}$ group; and R^5 and R^6 are same or different groups attached to the Ar group which are selected from hydrogen and alkyl radicals which individually contain 1 to 8 carbon atoms.

4,296,008

SEALANT COMPOSITION

David J. St. Clair, and Earle E. Ewins, Jr., both of Houston, Tex., assignors to Shell Oil Company, Houston, Tex.

Filed Apr. 21, 1980, Ser. No. 142,311

Int. Cl.³ C08L 93/00; C08J 3/00

U.S. Cl. 260—27 BB

8 Claims

1. A sealant composition possessing excellent oxidative and UV stability along with improved tack, reduced melt viscosity, and a cohesive failure mechanism in the 180° peel test comprises:

(a) 100 parts by weight of a selectively hydrogenated block copolymer component comprising an A'B' block copolymer and a multiblock copolymer having at least two end blocks A and at least one mid block B wherein the A' and A blocks are monoalkenyl arene polymer blocks and the B' and B blocks are substantially completely hydrogenated conjugated diene polymer blocks, the number average molecular weight of the A' and A blocks are between about 3,000 and about 7,000, and the monoalkenyl arene content of the multiblock copolymer is between about 7% and about 22% by weight, wherein the weight ratio between the A' B' block copolymer and the multiblock copolymer is 20:80 to about 60:40;

about 50 to about 350 parts by weight of a tackifying resin compatible with block B;
(c) about 0 to about 100 parts by weight of a plasticizer; and
(d) about 0.1 to about 10 parts by weight of a silane coupling agent.

4,296,009

WAX-CONTAINING UNSATURATED POLYESTER LAMINATING COMPOSITION WITH AROMATIC TERTIARY AMINE

Edward J. Kerle, Granville, and Terry R. Beaver, Newark, both of Ohio, assignors to Owens-Corning Fiberglas Corporation, Toledo, Ohio

Filed Jan. 7, 1980, Ser. No. 110,166

Int. Cl.³ C08L 91/00

U.S. Cl. 260—28.5 R

3 Claims

1. In a laminating composition comprising (i) an ethylenically unsaturated polyester polymer, (ii) an ethylenically unsaturated curing agent comprising styrene, (iii) a free radical catalyst for the cure reaction of said polyester polymer and said curing agent and (iv) paraffin wax, the improvement for enhancing interlaminar adhesion in cured laminates prepared therefrom which comprises said composition (v) further comprising at least about 0.1 percent by weight of a tertiary monamine having a single aromatic group and two alkyl or hydroxy alkyl groups joined to the amino nitrogen atom thereof and (vi) containing no more than about 10 percent by weight of non-reinforcing filler, where both percentages are based on the total weight of said polymer and said curing agent.

4,296,010

RESIN COMPOSITION FOR CATIONIC ELECTRODEPOSITING PAINTS

Akira Tominaga, Hiratsuka, Japan, assignor to Kansai Paint Co., Ltd., Hyogo, Japan

Filed Jan. 30, 1980, Ser. No. 116,780

Claims priority, application Japan, Mar. 26, 1979, 54-34227

Int. Cl.³ C08L 75/04

U.S. Cl. 260—29.2 TN

14 Claims

1. A resin composition for cationic electrodepositing paints which has a high throwing power and does not foul a top coated film and is particularly suitable for two-coat finishing, said resin composition comprising the reaction product of

[A] a basic polyamino resin containing amino groups and/or hydroxyl groups capable of reacting with isocyanate groups, with

[B] a polyisocyanate mixture composed of

(i) 40 to 95 mole% of a low-volatile partially blocked aromatic polyisocyanate containing at least two benzene rings having an isocyanate group directly bonded to a nuclear carbon atom, in which substantially all isocyanate groups except one are blocked with an alcohol,

(ii) 2.5 to 50 mole% of a low-volatile fully blocked aromatic polyisocyanate containing at least two benzene rings having an isocyanate group directly bonded to a nuclear carbon atom, and

(iii) 2.5 to 40 mole% of a difunctional polyisocyanate, the mole percentages being based on the total amount of the polyisocyanates (i), (ii) and (iii).

4,296,011

EPOXY ESTER COPOLYMER AQUEOUS DISPERSIONS

Kazys Sekmakas, Palatine, and Raj Shah, Schaumburg, both of Ill., assignors to DeSoto, Inc., Des Plaines, Ill.

Division of Ser. No. 18,887, Mar. 9, 1979, Pat. No. 4,247,659, which is a continuation-in-part of Ser. No. 885,036, Mar. 9, 1978, abandoned. This application Oct. 6, 1980, Ser. No. 194,128

Int. Cl.³ C08L 61/06

U.S. Cl. 260—29.3

13 Claims

1. Epoxy ester copolymer soluble in water with the aid of an amine comprising the hydroxy functional epoxy ester of a polyepoxide having an average molecular weight of about 300

to about 1100 and a 1,2-epoxy equivalency of about 1.4 to about 2.0, esterified with an at least approximately stoichiometric proportion, based on epoxide functionality, of monocarboxylic acid selected from benzoic acid, $\text{C}_1\text{--C}_8$ alkyl substituted benzoic acid, and $\text{C}_6\text{--C}_{10}$ alkanic acid, the esterification reaction being continued to provide an acid number of less than 20, said hydroxy functional epoxy ester being polyesterified with from 1.5–8%, based on the weight of the epoxy ester, of a monoethylenically unsaturated dicarboxylic acid which resists homopolymerization to an acid number of less than 20, and said polyester being copolymerized with from 15% to 70% of monoethylenic monomers, based on the copolymer, said monoethylenic monomers including carboxyl functional monomer providing an acid number of from 20–100 in the copolymer, said copolymer being dispersed in water in the form of a salt with an amine.

12. Epoxy ester copolymer as recited in claim 1 in which said copolymer is present in admixture with from 5–40%, based on total resin solids, of an aminoplast or phenoplast resin.

4,296,012

SIZING COMPOSITIONS INCORPORATING KETENE DIMER

Toshiharu Okumichi, Osamu Oseto, both of Suita; Keizo Matsumoto, Hirakata; Shigenori Thuzimoto, and Hisanari Sanda, both of Osaka, all of Japan, assignors to Arakawa Kagaku Kogyo Kabushiki Kaisha, Japan

Filed Dec. 10, 1979, Ser. No. 101,768

Claims priority, application Japan, Dec. 28, 1978, 53-161560; Feb. 28, 1979, 54-23631

Int. Cl.³ C08L 23/18, 25/06, 95/00

U.S. Cl. 260—29.6 XA

7 Claims

1. A sizing composition for cellulosic fiber sheets comprising water and finely divided solid particles dispersed in the water, said solid particles being a uniform mixture of about 40 to about 96% by weight of a ketene dimer and about 4 to about 60% by weight of a noncrystalline hydrocarbon resin formed by dissolving one in the other.

4,296,013

VINYLDENE CHLORIDE POLYMER MICROGELS

Dale S. Gibbs, Midland, Mich., assignor to The Dow Chemical Co., Midland, Mich.

Division of Ser. No. 942,515, Sep. 15, 1978. This application Dec. 13, 1979, Ser. No. 103,020

Int. Cl.³ C08L 27/08

U.S. Cl. 260—29.6 TA

4 Claims

1. A coating latex containing discrete, cross-linked vinylidene chloride polymer microgels, said latex comprising the product obtained by emulsion polymerizing (a) about 88 to about 92 parts by weight of vinylidene chloride; (b) about 6 to about 12 parts by weight of methyl acrylate or methyl methacrylate; (c) about 1 to about 5 parts by weight of a copolymerizable crosslinking polyfunctional comonomer; and (d) about 1 to about 10 parts by weight of a comonomer selected from the group consisting of acrylic acid, methacrylic acid, itaconic acid, and fumaric acid, said microgels having a particle size of about 0.1 to about 0.5 micron, a gel content of about 1 to about 50 percent, and a second order transition temperature less than about 30° C.

4,296,014

AQUEOUS DISPERSION TYPE THERMOSETTING COATING COMPOSITION

Masaaki Hayashi, Tokyo; Hiroharu Sasaki, Yamato, and Kazuyoshi Tsuneta, Yokohama, all of Japan, assignors to Dai Nippon Toryo Co., Ltd., Japan

Filed Dec. 17, 1979, Ser. No. 104,447

Claims priority, application Japan, Oct. 26, 1978, 53-132000; Dec. 19, 1978, 53-156653; Dec. 26, 1978, 53-164179

Int. Cl.³ C08L 67/06

U.S. Cl. 260—29.6 NR

13 Claims

1. An aqueous dispersion type thermosetting coating composition comprising (A) fine thermosetting water-insoluble resin particles consisting essentially of (a) a preformed polyester-modified vinyl resin having a hydroxyl value of 30 to 200, which is formed by solution graft-polymerizing (i) an unsaturated polyester resin formed by reaction between an unsaturated dicarboxylic acid and a polyhydric alcohol, with (ii) at least one α,β -monoethylenically unsaturated monomer, and optionally with (iii) a phosphoric acid group-containing α,β -monoethylenically unsaturated monomer, and (b) a preformed cross-linkable copolymer resin derived from a monomer mixture comprising (iv) an N-alkoxymethylated monomer of an α,β -monoethylenically unsaturated carboxylic acid amide and (ii) at least one α,β -monoethylenically unsaturated monomer, (B) a surface active agent and/or a thickener, and (C) a necessary amount of water.

4,296,015

MOLDED ARTICLE OF HYDROUS POLYMER AND PROCESS FOR PRODUCING THE SAME

Seiji Aotani, Yokohama, and Hisanori Kanayama, Machida, both of Japan, assignors to Japan Synthetic Rubber Co., Ltd., Tokyo, Japan

Filed Jan. 24, 1980, Ser. No. 115,098

Claims priority, application Japan, Jan. 30, 1979, 54/8739

Int. Cl.³ C08K 5/06

U.S. Cl. 260—29.6 ME

22 Claims

1. A molded article of hydrous polymer comprising a polymer latex or a macromolecular substance latex, an oily substance, and an additive selected from the group consisting of a polyether and a combination of a polyvalent metal compound and a polyether, said polymer latex or macromolecular substance latex containing anionic groups, having a polymer concentration of 20–70% by weight, and being selected from the group consisting of:
(a) polymer latexes prepared by emulsion polymerization process;
(b) polymer latexes obtained by re-emulsification process, and
(c) natural macromolecular substance latexes;
wherein said polyether is selected from the group consisting of polyoxypropylene, oxyethylene-oxypropylene copolymer and polyoxytetramethylene; and
wherein the amounts of the oily substance and the polyether are 10–200 parts by weight and 0.5–30 parts by weight, respectively, per 100 parts by weight of said polymer latex.

4,296,016

METHOD OF PREPARING A POLYMERIC ELECTROLYTE PARTICULARLY FOR AN ELECTRO-OPTICAL DEVICE

Jean-Paul Randin, Neuchatel, Switzerland, assignor to Ebauches S.A., Neuchatel, Switzerland

Filed Apr. 2, 1980, Ser. No. 136,466

Claims priority, application Switzerland, May 3, 1979, 133/79


Int. Cl.³ C08K 3/00

U.S. Cl. 260—29.6 SQ

5 Claims

1. A method of preparing a proton polymeric electrolyte, particularly for an electro-optical device, which is a mixture of poly[2-acrylamido-methylpropanesulphonic acid] and water and containing pigment distributed substantially homoge-

neously, comprising forming a suspension of a said pigment in water, dissolving 5 to 50% by weight of a monomer of the formula



or a salt thereof in the suspension, adding a polymerisation initiator to the mixture, carrying out the polymerisation reaction with agitation, and evaporating part of the water until the water content is less than 52% of the weight of the dry polymer, the pigment being present in the amount of 2 to 25% by weight of the dry polymer.

4,296,017

GRAFT COPOLYMER PRESSURE-SENSITIVE ADHESIVES, THEIR MANUFACTURE AND USE

Rudolf Weissgerber, Alois Stoll, Herbert Kandler, Hans-Herbert Nunner, Christine Eichelseder, and Helmut Pangerl, all of Burghausen, Fed. Rep. of Germany, assignors to Wacker-Chemie GmbH, Munich, Fed. Rep. of Germany

Filed Jan. 18, 1980, Ser. No. 113,259

Claims priority, application Fed. Rep. of Germany, Jan. 31, 1979, 2903687

Int. Cl.³ C08F 261/04, 263/02, 263/04; C08L 39/06

U.S. Cl. 260—30.6 R

8 Claims

1. A graft copolymer for use as a polymeric pressure-sensitive adhesive consisting of:

- (I) from 5% to 30% by weight of a graft base soluble in the monomer component selected from the group consisting of
 - (i) a copolymer of 40% to 85% by weight of said copolymer of ethylene units, 15% to 60% by weight of said copolymer of vinyl acetate units and 0 to 10% by weight of said copolymer of monomer units copolymerizable with ethylene and vinyl acetate,
 - (ii) said copolymer with up to 10% by weight of said copolymer of vinyl alcohol units derived from vinyl acetate units, and
 - (iii) mixtures of 25% to 99.9% by weight of said copolymer with from 0.1% to 75% by weight of other graftable polymers soluble in the monomer component, and
- (II) from 70% to 95% by weight of a monomer mixture grafted to said graft base consisting of
 - (a) from 30% to 80% by weight of said mixture of vinyl esters of alkanolic acids having 2 to 4 carbon atoms,
 - (b) from 20% to 70% by weight of said mixture of monomers selected from the group consisting of vinyl esters of alkanolic acids having 6 to 18 carbon atoms, esters of α,β -alkenolic acids having 3 to 8 carbon atoms, with alkanols having 3 to 18 carbon atoms, esters of alkenedioic acids having 4 to 8 carbon atoms, with alkanols having 3 to 18 carbon atoms, and mixtures thereof,
 - (c) from 0.5% to 15% by weight of said mixture, of N-vinyl-2-pyrrolidone,
 - (d) from 0 to 20% by weight of other olefinically-unsaturated compounds copolymerizable with said components (a), (b) and (c), and
 - (e) from 0 to 25% by weight of a plasticizer.

4,296,018

CATECHOL OR PYROGALLOL CONTAINING FLEXIBLE INSULATING TAPE HAVING LOW GEL TIME


James D. B. Smith, Wilkins Township, Allegheny County, and Robert N. Kauffman, Monroeville, both of Pa., assignors to Westinghouse Electric Corp., Pittsburgh, Pa.

Filed May 17, 1979, Ser. No. 39,918

Int. Cl.³ B32B 19/02, 27/38; C08K 5/07, 5/13


U.S. Cl. 260—32.8 EP

8 Claims



1. A composition comprising:

- (A) semi-solid epoxide, a mixture of solid epoxide and liquid epoxide or a mixture of semi-solid epoxide and liquid epoxide, with a solvent for said epoxide selected from the group consisting of ketones, aromatic hydrocarbons, and mixtures thereof, where the weight ratio of total epoxide to total solvent is from about 85:15 to about 10:90;
- (B) about 0.01 to about 5.0 phr of an organo-tin compound having the structural formula:



where each R is independently selected from the group consisting of alkyl groups having from about 1 to 10 carbon atoms, aryl groups, Cl, Br, or NO₂ substituted aryl groups, alkaryl groups with the alkyl constituent having from 1 to 10 carbon atoms, Cl, Br, or NO₂ substituted alkaryl groups with the alkyl constituent having from about 1 to 10 carbon atoms, aralkyl groups with the alkyl constituent having from about 1 to 10 carbon atoms, cyclopentane groups, cyclopentene groups, cyclopentadiene groups, cyclohexane groups, cyclohexene groups, cyclohexadiene groups, pyrrolidine groups, pyrrole groups, tetrahydrofuran groups, dioxane groups, pyridine groups and piperidine groups, and each X is selected from the group consisting of halide, hydroxide, acetate, butyrate, propionate, and dimethyl phosphate; and
(C) about 0.001 to about 1 phr of an activator selected from the group consisting of catechol, pyrogallol, and mixtures thereof.

4,296,019

SOLVENT BLENDS FOR ETHYLENE COPOLYMERS

Alfred R. Nelson, Edenville, and Kenneth E. Johnsen, Midland, both of Mich., assignors to The Dow Chemical Co., Midland, Mich.

Filed Nov. 29, 1979, Ser. No. 98,465

The portion of the term of this patent subsequent to Jul. 21, 1998, has been disclaimed.

Int. Cl.³ C08K 5/05

U.S. Cl. 260—33.4 R

9 Claims

1. A solution comprising a solvent blend which comprises from about 5 to about 35 percent by weight of an acyclic alcohol selected from the group consisting of ethanol, propanol, isopropanol, n-butanol, isobutanol and t-butanol, based upon the total weight of said solvent blend, about 3 percent to about 90 percent by weight of a monocyclic aromatic hydrocarbon, based upon the total weight of said solvent blend, and from about 5 to about 92 percent by weight of a halogenated C₂ hydrocarbon, based upon the total weight of said solvent blend, and a copolymer of ethylene and ethylenically unsaturated carboxylic acid, or an ionic metal salt thereof, having from about 2.5 to about 30 percent by weight of said carboxylic

acid, based on the total weight of said copolymer, characterized in that said copolymer remains dissolved at a temperature of at least 60° C.

4,296,020

POLYUREA THICKENED MOLDING COMPOSITIONS

Juan J. Magrans, Jr., Newark, Del., assignor to ICI Americas Inc., Wilmington, Del.

Filed Oct. 29, 1979, Ser. No. 89,128

Int. Cl.³ C08L 67/00, 75/02, 75/06


U.S. Cl. 260—37 N

17 Claims

1. A resin blend useful in preparing non-sticky molding compositions by the reaction therewith of polyisocyanate which comprises: an ethylenically unsaturated monomer containing dissolved therein 30–70% by weight of a resin selected from the group consisting of vinyl terminated polyester urethane resin, ethylenically unsaturated polyester resins, and ethylenically unsaturated polyisocyanurate resins, and 1.5–30% by weight of at least organic polyamine polyurea precursor free of ethylenic unsaturation selected from the group consisting of polyalkylene polyamines and cyanoalkylated polyoxyalkylene polyamines having a molecular weight of about 190–2000 having a general formula selected from the group consisting of:




wherein X is H or an alkyl group having 1–18 carbon atoms and where y is a number of about 2 to about 16, A triamine of polyalkoxylated trimethylol propane having the general formula:



where z is an average of 1–11, and

A cyanoethylated polyoxyalkylated polyamines having the general formula:



where R is the nucleus of an oxylation-susceptible aliphatic polyhydric alcohol containing 2–12 carbon atoms and 2–8 hydroxyl groups, A is hydrogen or a cyano lower alkyl radical having 1 or 2 carbon atoms between the hydrogen and the cyano radical provided at least one A is a cyano-lower-alkyl radical, Z is an alkyl group containing 1–18 carbon atoms, X and Y are hydrogen or Z, n has an average value of 0–50 and m is 2–8, R saturated and consists of carbon and hydrogen wherein there is a reaction product of the polyisocyanate with the polyamine polyurea precursor.

4,296,021

REINFORCED THERMOPLASTIC POLYESTER COMPOSITIONS HAVING IMPROVED HIGH VOLTAGE BREAKDOWN RESISTANCE

Allen D. Wambach, Evansville, Ind., assignor to General Electric Company, Pittsfield, Mass.

Filed Dec. 6, 1976, Ser. No. 747,634

Int. Cl.³ C08K 3/34, 3/40

U.S. Cl. 260—40 R

12 Claims

1. A method of improving the high voltage dielectric breakdown characteristics of reinforced thermoplastic compositions comprising adding to a polybutylene terephthalate resin a reinforcing agent comprising (i) aluminum silicate, alone, or in combination with (ii) glass fibers, said reinforcing agent being present in an amount of up to 60% by weight of said reinforced thermoplastic composition and in an amount at least sufficient to reinforce the composition but in an amount not in excess of that which impairs the long term high voltage breakdown resistance of the composition in comparison with a corresponding unfilled composition or one wherein the filler consists essentially of glass fibers.

4,296,022

POLYPROPYLENE BLEND COMPOSITIONS

Robert L. Hudson, Severna Park, Md., assignor to Chevron Research, San Francisco, Calif.

Filed Jun. 4, 1980, Ser. No. 156,521

Int. Cl.³ C08L 23/12

U.S. Cl. 260—42.46

5 Claims

1. A polypropylene resin blend, useful for melt-spinning fine denier yarns, which comprises, per 100 parts by weight of total polypropylene resin, about from 70-95 parts of a first polypropylene resin having a melt flow index about of from 30 to 38 and a swell index of about from 1.8 to 2.3; about from 5 to 30 parts of a second polypropylene resin having a melt flow index of about from 4 to 35 and a swell index of about from 5 to 7; and about 0.2 to 0.5 parts of a hindered phenol melt flow stabilizer for retarding polypropylene polymer degradation during melt extrusion.

4,296,023

VINYL CHLORIDE POLYMER COMPOSITIONS WITH REDUCED COMBUSTIBILITY AND REDUCED SMOKE FORMATION UNDER CONDITIONS OF FIRE

Hubertus J. Vroomans, Beek, Netherlands, assignor to Stamcarbon, B.V., Geleen, Netherlands

Filed May 30, 1980, Ser. No. 154,898

Claims priority, application Netherlands, Jun. 1, 1979, 7904369; Jun. 27, 1979, 7904991; Oct. 17, 1979, 7907651

Int. Cl.³ C08K 3/24

U.S. Cl. 260—45.75 F

8 Claims

1. A vinyl chloride polymer composition having an oxygen index according to ASTM D 2863 of at least 60 and reduced smoke formation under conditions of fire, said composition contains a zinc titanate,

which zinc titanate is composed to a large extent of by weight of spinel crystal structure, present in an amount from 0.05 to 5 parts by weight per 100 parts by weight of said vinyl chloride polymer.

4,296,024

HUMAN IMMUNE SERUM GLOBULIN WITH HIGH HEPATITIS A ANTIBODY TITER

William J. McAleer, Ambler, and William J. Miller, North Wales, both of Pa., assignors to Merck & Co., Inc., Rahway, N.J.

Continuation-in-part of Ser. No. 813,566, Jul. 7, 1977, abandoned, which is a continuation-in-part of Ser. No. 610,499, Sep. 4, 1975, abandoned, which is a continuation-in-part of Ser. No. 531,020, Dec. 9, 1974, abandoned. This application Jan. 5, 1979, Ser. No. 1,133

Int. Cl.³ C07G 7/00

U.S. Cl. 260—112 B

5 Claims

1. Human immune serum globulin having a hepatitis A antibody titer of at least about 75,000 IAHA units/ml.

4,296,025

PROCESS FOR PREPARING HUMAN INTERFERON

Kaname Sugimoto, Okayama, Japan, assignor to Ken Haya-shibara, Okayama, Japan

Filed May 13, 1980, Ser. No. 149,533

Claims priority, application Japan, May 24, 1979, 54-63210

Int. Cl.³ C07G 7/00; A61K 45/02

U.S. Cl. 260—112 R

4 Claims

1. A process for preparing human interferon, comprising exposing human leukocyte suspension to both Type I and Type II interferon inducers to induce interferon, and purifying and collecting the induced interferon.

4,296,026

PRODUCTION OF SOYBEAN PROTEIN ISOLATE OF IMPROVED PURITY

Donald B. Millar, Toronto, Canada, assignor to General Foods Inc., Toronto, Canada

Filed Sep. 22, 1980, Ser. No. 189,646

Int. Cl.³ A23J 1/14

U.S. Cl. 260—123.5

8 Claims

1. In a process for the formation of a soybean protein isolate by contacting soybeans with an aqueous sodium chloride solution of ionic strength of at least about 0.2 molar to solubilize the protein, diluting the protein solution to an ionic strength sufficient to form a protein dispersion of protein in the aqueous phase, and collecting the protein from the dispersion as an amorphous mass of soybean protein isolate, the improvement which comprises using calcium chloride in said aqueous sodium chloride solution in an amount effective to increase the purity of said soybean protein isolate.

4,296,027

PURE INTRAVENOUS HUMAN AND ANIMAL GAMMA GLOBULINS

Richard M. Condie, Minneapolis, Minn., assignor to The Regents of the University of Minnesota, Minneapolis, Minn.

Continuation-in-part of Ser. No. 829,565, Aug. 31, 1977, Pat. No. 4,136,094. This application Jan. 22, 1979, Ser. No. 5,150

Int. Cl.³ C07G 7/00

U.S. Cl. 260—112 B

9 Claims

1. An isolated natural, unaltered, unfragmented, undenatured monomeric immune gamma globulin for intravenous administration characterized by 99% purity and containing less than 1% aggregates and less than 1% dissociated materials.

4,296,028

PYRAZOLONYL SUBSTITUTED DISAZO PIGMENTS

Ugo Moiso, 5, Viale Rimembranze; Vincenzo Massabo, 10, Viale Rimembranze, and Danilo Domenis, 43, Via S. Giuseppe, all of Saronno (Varese), Italy

Division of Ser. No. 274,670, Jul. 24, 1972, abandoned. This application Sep. 30, 1977, Ser. No. 838,128


Claims priority, application Italy, Jul. 26, 1971, 7669 A/71; Dec. 29, 1971, 33062 A/71

Int. Cl.³ C09B 33/12, 33/13, 33/153; D06P 1/04

U.S. Cl. 260—160

1 Claim

1. A disazo pigment of the formula:



4,296,029

PROCESS FOR PREPARING HEXAHYDROAZEPINE, PIPERIDINE AND PYRROLIDINE DERIVATIVES

Brian J. Bushell, Portsmouth; John F. Cavalla, Isleworth; Robin G. Shepherd, Burnham, and Alan C. White, Windsor, all of England, assignors to John Wyeth & Brother Limited, Maidenhead, England

Filed Jun. 23, 1980, Ser. No. 161,992


Claims priority, application United Kingdom, Jul. 3, 1979, 23123/79

Int. Cl.³ C07D 223/10


U.S. Cl. 260—239.3 R

15 Claims


1. A method for preparing a 2-oxo-hexahydroazepine, 2-oxo-piperidine or 2-oxo-pyrrolidine of formula I



wherein n is 2, 3 or 4, R is selected from the group consisting of hydrogen, lower alkyl, phenyl(lower)alkyl, loweralkenylmethyl and cycloalkylmethyl of 3-4 carbons in the cycloalkyl moiety, R¹ is selected from the group consisting of hydrogen and lower alkyl and R² is selected from the group consisting of hydrogen, lower alkyl and phenyl (lower)alkyl which comprises reacting an anion of a lactam of formula III



where n and R¹ are as defined above and R³ is lower alkyl, phenyl(lower)alkyl, trialkyl-, triaryl- or triaryllalkylsilyl, loweralkenylmethyl or cycloalkylmethyl of 3-4 carbon atoms in the cycloalkyl moiety with a benzyne of formula IV



where R⁴ is lower alkyl, phenyl(lower)alkyl, or trialkyl-, triaryl or triaryllalkyl-silyl to give an anion of the compound of formula I where R¹ is lower alkyl or a dianion of the compound of formula I where R¹ is hydrogen and protonating the anion or dianion of the compound of formula I to give a compound of formula I.

4,296,030

METAL CHELATES OF 1,4-BIS(SUBSTITUTED-AMINO-5,8-DIHYDROXY-ANTHRAQUINONES

Stanley A. Lang, Jr., Stony Point, and Keith C. Murdock, Pearl River, both of N.Y., assignors to American Cyanamid Company, Stamford, Conn.


Filed Apr. 9, 1980, Ser. No. 138,620

Int. Cl.³ C07F 3/06, 15/02, 15/06



U.S. Cl. 260—239 A

9 Claims



1. A chelated compound selected from the group consisting of those of the formula:




wherein Q is a divalent moiety selected from the group consisting of those of the formulae:



wherein n is an integer from 2 to 4 inclusive; R¹ and R² are each individually selected from the group consisting of hydrogen, alkyl(C₁-C₄), monohydroxyalkyl(C₁-C₄), with the proviso that the carbon atom alpha to the nitrogen atom does not bear an hydroxy group, dihydroxyalkyl(C₃-C₆), with the proviso that the carbon atom alpha to the nitrogen atom does not bear an hydroxy group, formyl, alkanoyl(C₂-C₄), trifluoroacetyl and moieties of the formulae:



wherein n is an integer 2 to 4 inclusive, R is alkyl(C₁-C₄) and R₃ and R₄ are each individually selected from the group consisting of hydrogen, alkyl(C₁-C₄) and monohydroxyalkyl(C₂-C₄), with the proviso that the carbon atom alpha to the nitrogen atom does not bear an hydroxy group and the group



is morpholino, thiomorpholino, piperazino, 4-methyl-1-piperazino or a moiety of the formula:



wherein m is an integer 2 to 6 inclusive; with the proviso that the ratio of the total number of carbon atoms to the sum of the total number of oxygen atoms plus the total number of nitrogen atoms in the side chains at the 1-position and the 4-position does not exceed 4 and with the further proviso that R₁ and R₂ are not both hydrogen or alkyl; M is selected from the group platinum, copper, iron, zirconium, cobalt, chromium and zinc; X is chloride, sulfate or nitrate and the pharmacologically acceptable acid-addition salts thereof.

4,296,031

BENZODIAZEPINE DERIVATIVES

Albert E. Fischli, and Andre Szente, both of Riehen, Switzerland, assignors to Hoffmann-La Roche Inc., Nutley, N.J.

Division of Ser. No. 63,288, Aug. 2, 1979, Pat. No. 4,251,443.

This application Sep. 11, 1980, Ser. No. 186,061


Claims priority, application Switzerland, Aug. 11, 1978, 8563/78; Jun. 6, 1979, 5270/79; Jul. 5, 1979, 6296/79

Int. Cl.³ C07D 243/24

U.S. Cl. 260—239.3 D

2 Claims

1. A compound of the formula



wherein R^1 is lower alkyl, R^2 is hydrogen or lower alkyl, R^3 is halogen and R^4 is hydrogen or halogen, A is a lower alkylene group, R^{54} is hydrogen or lower alkyl and L is selected from the group consisting of halogen, tosyloxy, mesyloxy and trimethylammonium.

4,296,032

METHOD FOR THE PREPARATION OF PENICILLANIC- β -LACTAMASE INHIBITORS

Paul M. Denerley, Horley, England, assignor to Beecham Group Limited, England

Filed Mar. 31, 1980, Ser. No. 135,316

Claims priority, application United Kingdom, Apr. 4, 1979, 11764/79

Int. Cl.³ C07D 277/60

U.S. Cl. 260—245.2 R

4 Claims

1. A process for the preparation of an in-vivo hydrolysable ester of 6 β -bromopenicillanic acid when substantially free from the corresponding in-vivo hydrolysable ester of 6 α -bromopenicillanic acid which process comprises mixing isomeric in-vivo hydrolysable esters of 6 α - and 6 β -bromopenicillanic acids and thereafter chromatographically separating the mixture of isomers into fractions and recovering the in-vivo hydrolysable ester of 6 β -bromopenicillanic acid from a fraction containing said in-vivo hydrolysable ester of 6 β -bromopenicillanic acid substantially free from the in-vivo hydrolysable ester of a 6 α -bromopenicillanic acid.

4,296,033

4-AZIDO-1-MERCAPTOACYL PROLINE

Edward W. Petrillo, Jr., Pennington, and Frank L. Weisenborn, Titusville, both of N.J., assignors to E. R. Squibb & Sons, Inc., Princeton, N.J.


Filed Jul. 23, 1980, Ser. No. 171,565

Int. Cl.³ A61K 31/40, 31/445; C07D 207/16, 211/34

U.S. Cl. 260—326.2

8 Claims

1. A compound having the formula



or a salt thereof, wherein,

R_1 is hydrogen, alkyl, aryl, arylalkyl, alkanoyl, or arylcarbo-

nyl;

R_2 is hydrogen, alkyl, alkylthio or trifluoromethyl;

R_3 is hydrogen, alkyl or arylalkyl; and

n is 1 or 2;

wherein the asymmetric center indicated by the asterisk (*) is in the L-configuration and wherein the term "aryl" refers to phenyl or phenyl substituted with halogen, alkyl, alkoxy, alkylthio, hydroxy, alkanoyl, nitro, amino, dialkylamino, phenyl or trifluoromethyl groups.

4,296,034

POLYFLUORINATED SULFONAMIDES

Pierre Bouvet, Rouen, and Jean-Pierre Lalu, La Mulatiere, both of France, assignors to Produits Chimiques Ugine Kuhlmann, Paris, France

Continuation of Ser. No. 466,051, May 1, 1974, abandoned, which is a continuation of Ser. No. 5,352, Jan. 23, 1970, abandoned. This application May 24, 1979, Ser. No. 41,926 Claims priority, application France, Jan. 22, 1969, 69 01059 Int. Cl.³ C07D 295/22; C07C 143/75, 143/74

U.S. Cl. 260—326.82

2 Claims

1. A polyfluorinated sulfonamide compound having the structure



wherein


(a) C_nF_{2n+1} corresponds to a straight or branched polyfluorinated carbon chain, n being a number of from 1 to 20;

(b) b is an integer of from 2 to 20;

(c) $-NRR'$ is selected from the group (d) or (e) below:

(d) N is nitrogen; R is hydrogen or an alkyl radical of from 1 to 10 carbon atoms; and R' is hydrogen, an alkyl radical of from 1 to 10 carbon atoms, a cyclic alkyl radical of from 5 to 12 carbon atoms, or an aryl hydrocarbon radical of from 6 to 12 carbon atoms;

(e) $-NRR'$ is a pyrrolidine radical having the structure



4,296,035

TOTAL SYNTHESIS OF THE UTERO-EVACUANT SUBSTANCE D,L-ZOAPATANOL

Vinayak V. Kane, Princeton, N.J., assignor to Ortho Pharmaceutical Corporation, Raritan, N.J.

Division of Ser. No. 971,471, Dec. 20, 1979, Pat. No. 4,237,053.


This application Mar. 17, 1980, Ser. No. 130,660

Int. Cl.³ C07D 313/04


U.S. Cl. 260—333

3 Claims

1. The process for the preparation of a compound selected from the group consisting of




which comprises reacting a compound of the formula




with ethylene glycol to form a ketal of the formula


-continued




reacting the product formed with sodium in liquid ammonia to form an alcohol of the formula





reacting the alcohol with t-butyldiphenylsilyl chloride in the presence of imidazole to form a compound of the formula





reacting the alcohol formed with dihydropyran and an acid selected from P-toluenesulfonic acid and camphorsulfonic acid to form a compound of the formula




reacting the ketone with triethylphosphonoacetate to form a mixture of isomers having the formulas




reacting the mixture with lithium aluminum hydride to form a mixture of alcohols having the formulas




separating the alcohols, and reacting the alcohol B with t-butyldiphenylsilyl chloride to form a compound of the formula




reacting the product with acetic acid to form an alcohol of the formula




reacting the alcohol with chromium trioxide to form an aldehyde of the formula




reacting the aldehyde with an acetylenic Grignard reagent prepared from




to form a compound of the formula




reacting the product with lithium aluminum hydride to form a compound of the formula




reacting the alcohol formed with an oxidizing agent selected from chromium trioxide and manganese dioxide to form a ketone of the formula




reacting the ketone with potassium t-butoxide followed by treatment with acetic acid to form a compound of the formula





reacting the product with sodium borohydride to form a compound of the formula




reacting the product formed with dihydropyran and an acid selected from P-toluenesulfonic acid and camphorsulfonic acid to form a compound of the formula



reacting the product formed with tetrabutylammonium fluoride to form a mixture of compounds of the formula




separating the compounds in the mixture, and then (a) reacting compound A with an esterifying agent selected from a lower alkyl anhydride or alkanoyl halide having 2-5 carbon atoms to form an ester of the formula




treating the product with an acid selected from acetic acid, wherein R is a t-butyl diphenylsilyl group, R₁ is lower alkanoyl


P-toluenesulfonic acid and camphorsulfonic acid to form an alcohol of the formula




treating the alcohol formed with chromium trioxide to form a ketone of the formula




and reacting the product formed with tetrabutylammonium hydroxide to form a compound of the formula



(b) reacting compound B with an esterifying agent selected from a lower alkyl anhydride or alkanoyl halide having 2-5 carbon atoms to form an ester of the formula




A treating the product formed with an acid selected from acetic acid, P-toluenesulfonic acid and camphorsulfonic acid to form an alcohol of the formula




B


treating the alcohol formed with chromium trioxide to form a ketone of the formula



and reacting the product formed with tetrabutylammonium hydroxide to form a compound of the formula



having 2-5 carbon atoms and R₂ is selected from the group consisting of benzyl, p-nitrobenzyl and p-methylbenzyl.



(II)

4,296,036

SELECTIVE METHOD FOR THE PREPARATION OF INSECT PHEROMONE

Kenji Mori, Tokyo, and Mitsuru Sasaki, Toyonaka, both of Japan, assignors to Sumitomo Chemical Company, Limited, Osaka, Japan

Filed Mar. 31, 1980, Ser. No. 135,274


Claims priority, application Japan, Apr. 6, 1979, 54-42138

Int. Cl.³ C07D 319/04, 305/14

U.S. Cl. 260-340.7


4 Claims

1. A method for the preparation of 3,3,7-trimethyl-2,9-dioxatricyclo[3.3.1.0^{4,7}]nonane represented by the formula (I),



(I)


which comprises reacting a keto lactone represented by the formula (II),



(II)


with diisobutylaluminum hydride and subsequently treating with an acid, wherein the reaction temperature is from -70° C. to +20° C., wherein the reaction time is from a moment up to one hour and wherein the molar ratio of the compound represented by the formula (II) to diisobutylaluminum hydride is 1:2-3.

2. A method for the preparation of a keto lactone represented by the formula (II),



(I)

which comprises oxidizing a hydroxy lactone represented by the formula (III),



(III)

with a chromic acid at 0° to 20° C. from a moment up to two hours, wherein the molar ratio of the compound represented by the formula (III) to the chromic acid is 1:1-3 equivalents.

4. 1,5,5-trimethyl-4-oxabicyclo[4.2.0]octa-3,7-dione represented by the formula (II),

4,296,037

4,5-DIHYDRO-3,3-DIPHENYL-4-HYDROCARBYLAMINOMETHYLFURAN-2(3H) ONES

Albert D. Cale, Jr., Mechanicsville, Va., assignor to A. H. Robins Company, Incorporated, Richmond, Va.

Division of Ser. No. 615,951, Sep. 23, 1975, Pat. No. 4,119,637.


This application Jul. 24, 1978, Ser. No. 127,001

Int. Cl.³ C07D 307/26

U.S. Cl. 260-343.6

6 Claims

1. A compound selected from those having the formula



wherein R is selected from the group consisting of lower alkyl having one to six carbon atoms, lower cycloalkyl having four to eight carbon atoms, or phenyl lower alkyl consisting of benzyl, phenethyl, phenpropyl and α-methylbenzyl.

4,296,038

PREPARATION OF (-)-DIHYDROCHRYSANTEMOLACTONE

T. L. Ho, and Zia U. Din, both of Jacksonville, Fla., assignors to SCM Corporation, New York, N.Y.

Filed Apr. 24, 1980, Ser. No. 143,299

Int. Cl.³ C07D 311/94

U.S. Cl. 260-343.21

5 Claims

1. A process for producing (-)-dihydrochrysanthemolactone from 2-caren-4-one comprising: methylating said 2-caren-4-one with a methylating agent selected from methyl lithium and methyl magnesium halide to produce 4-methyl-2-caren-4-ol; oxidizing said 4-methyl-2-caren-4-ol with ozone followed by cleaving at the double bond with removal of 2 carbon atoms to produce a tautomeric mixture of cis-2,2-dimethyl-3(2'-oxopropyl) cyclopropane-carboxylic acid and cis-2-oxo-3-oxa-4,7,7-trimethylbicyclo [4.1.0] heptan-4-ol; methylating with a methylating agent selected from methyl lithium and methyl magnesium halide said tautomeric mixture to produce a single compound that upon acidification forms a hydroxy acid; and lactonizing said hydroxy acid by dehydration to produce said (-)-dihydrochrysanthemolactone.

4,296,039

SELECTED PROCESS FOR PRODUCING MONOHALOGENATED DERIVATIVES OF 7-HYDROXY-COUMARIN

Francesco Della Valle, Padua, Italy, assignor to Fidia S.p.A., Padua, Italy

Division of Ser. No. 952,460, Oct. 18, 1978, abandoned. This application Jan. 15, 1980, Ser. No. 112,223


Claims priority, application Italy, Nov. 17, 1977, 29765 A/77

Int. Cl.³ C07D 311/08, 413/06, 405/06


U.S. Cl. 260-343.45

5 Claims


1. Process for the preparation of pure 7-hydroxycoumarin derivatives of the formula I:



wherein X represents a halogen atom, R₁ is selected from the group consisting of piperidino ethyl, morpholino ethyl, diethylamino ethyl and diethylamino propyl, R₂ is selected from the group consisting of methyl and phenyl, and R₃ is selected from the group consisting of ethoxy-carbonyl-methyl and ethoxy-carbonyl-ethyl, which process comprises (a) reacting a 2-halo-resorcinol of the formula V:



with a β-keto ester to obtain an intermediate of the formula



wherein R₁, R₂ and X are as hereinbefore indicated, and (b) subsequently reacting said intermediate VI with a compound of the formula R₃-Halogen, wherein R₃ is as before defined, in the presence of an acid-binding agent to obtain the desired compound I.

4,296,040

ANTIBIOTIC NANAOMYCIN E AND A PROCESS FOR PRODUCING THE SAME

Satoshi Omura, Tokyo; Haruo Tanaka, Machida; Itaru Takahashi, Kumamoto; Shinzo Ishii; Kazuyuki Mineura, both of Nagaizumi; Kunikatsu Shirahata, Machida; and Masaji Kasai, Fujisawa, all of Japan, assignors to Kyowa Hakko Kogyo Kabushiki Kaisha and Kitasato Kenkyusho, both of Tokyo, Japan

Continuation of Ser. No. 17,314, Mar. 5, 1979, abandoned. This application Nov. 23, 1970, Ser. No. 97,001


Claims priority, application Japan, Mar. 7, 1978, 53-25041

Int. Cl.³ C07D 311/78

U.S. Cl. 260—345.2

1 Claim

1. A compound represented by the formula:



said compound having the following specific rotation $[\alpha]_D^{20} = +89.0^\circ$ (c=0.95 in methanol).

4,296,041

19-HYDROXY-7A-HOMO-PGI₂ COMPOUNDS

John C. Sih, Portage, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.

Division of Ser. No. 54,811, Jul. 5, 1979, Pat. No. 4,225,508.


This application Mar. 3, 1980, Ser. No. 126,481

Int. Cl.³ C07D 311/94

U.S. Cl. 260—345.2

7 Claims

1. A prostacyclin-type compound of the formula




wherein A₁ is —O— (oxo) and E₂ is —CH₂CH₂—;

wherein L₂ is

- (1) —(CH₂)_j—, wherein j is one to 4, inclusive,
- (2) —(CH₂)_q—CF₂—, wherein q is one, 2, or 3, or
- (3) —CH=CH—;

wherein M₁ is



wherein Q is oxo, α-H:β-H, α-OH:β-R₄, or α-R₄:β-OH, wherein R₄ is hydrogen or alkyl of one to 4 carbon atoms, inclusive,

wherein R₁ is

- (1) —COOR₃,
- (2) —CH₂OH,
- (3) —CH₂N(R₇)(R₈),
- (4) —CO—N(R₇)(R₈),
- (5) —CO—NH—SO₂—R₁₅, or
- (6) tetrazolyl,

wherein R₃ is

- (a) hydrogen,
- (b) alkyl of one to 12 carbon atoms, inclusive,
- (c) cycloalkyl of 3 to 10 carbon atoms, inclusive,
- (d) aralkyl of 7 to 12 carbon atoms, inclusive,
- (e) phenyl,
- (f) phenyl substituted with one, 2, or 3 chloro or alkyl groups of one to 3 carbon atoms, inclusive;
- (g) —(Ph)—CO—CH₃,
- (h) —(p-Ph)—NH—CO—(p-Ph)—NH—CO—CH₃,
- (i) —(p-Ph)—NH—CO—(p-Ph),
- (j) —(p-Ph)—NH—CO—CH₃,
- (k) —(p-Ph)—NH—CO—NH₂,
- (l) —(p-Ph)—CH=N—NH—CO—NH₂,
- (m) β-naphthyl,
- (n) —CH₂—CO—R₁₆,

wherein —(Ph)— is inter-phenylene and —(p-Ph)— is inter-para-phenylene or para-phenyl;

wherein R₁₆ is phenyl, p-bromophenyl, p-biphenyl, p-nitrophenyl, p-benzamidophenyl, or 2-naphthyl, or

(o) a pharmacologically acceptable cation;

wherein R₇ and R₈ are hydrogen, alkyl of one to 12 carbon atoms, inclusive, benzyl, or phenyl, being the same or different, and wherein R₁₅ is hydrogen, alkyl of one to 12 carbon atoms, inclusive, phenyl, phenyl-substituted with one, 2, or 3 chloro or alkyl groups of one to 3 carbon atoms, inclusive, or

phenyl substituted with hydroxycarbonyl or alkoxy-carbonyl of 2 to 4 carbon atoms, inclusive, wherein R₂ is hydrogen, hydroxyl, or hydroxymethyl, wherein R₅ and R₆ are hydrogen, alkyl of one to 4 carbon atoms, inclusive, or fluoro, being the same or different, with the proviso that one of R₅ and R₆ is fluoro only when the other is hydrogen or fluoro, and wherein X is

- (1) trans—CH=CH—,
- (2) cis—CH=CH—,
- (3) —C=C—, or
- (4) —CH₂CH₂—.

4,296,042

PREPARATION OF UNSATURATED ALIPHATIC INSECT PHEROMONES USING CYCLIC PHOSPHONIUM YLIDS

Joseph M. Muchowski, Sunnyvale, and Michael C. Venuti, San Francisco, both of Calif., assignors to Syntex (U.S.A.) Inc., Palo Alto, Calif.


Filed Jun. 18, 1980, Ser. No. 160,711

Int. Cl.³ C07D 309/06; C07C 41/18; C07F 7/04

U.S. Cl. 260—345.9 R

14 Claims

1. A process for the preparation of a compound of the formula:



wherein

m is an integer from 1 to 11,


n is an integer from 1 to 9,

p is an integer from 1 to 6,

R₁ is selected from the group consisting of tetrahydropyranyl, benzyl, trimethylsilyl, t-butyl dimethylsilyl and triphenylmethyl;

which process comprises:

(a) contacting a cyclic phosphonium halide of the formula:



wherein

n is as set forth above,


R₂ is selected from the group consisting of hydrogen, and straight and branched chain lower alkyl groups, R₃ and R₄ are independently selected from the group consisting of phenyl, lower alkyl-substituted phenyl, lower alkoxy-substituted phenyl, and halo substituted phenyl; and

X is a halogen selected from the group consisting of chlorine, bromine, and iodine; with an alkali metal alkoxide to produce a ylid of the formula:




wherein n, R₂, R₃ and R₄ are as set forth above;


(b) treating said ylid with a protected hydroxy alkyl aldehyde of the formula



wherein R₁ and m are as set forth above, to produce a phosphine oxide of the formula:




wherein m, n, R₁, R₂, R₃ and R₄ are as set forth above; (c) contacting said phosphine oxide with an organo lithium compound in an aprotic solvent medium to produce a lithium salt of the formula:



wherein m, n, R₁, R₂, R₃, and R₄ are as set forth above; (d) treating said lithium salt with an aldehyde of the formula:




wherein p is as set forth above to produce an alcoholate of the formula:




wherein m, n, p, R₁, R₂, R₃ and R₄ are as set forth above; and

(e) heating said alcoholate in an aprotic solvent medium to produce a diene of the formula:



wherein m, n, p, R₁, and R₂ are as set forth above.

2. A process for the preparation of a compound of the formula:



wherein

m is an integer from 1 to 11,


n is an integer from 1 to 9,

p is an integer from 1 to 6,

R₁ is selected from the group consisting of tetrahydropyranyl, benzyl, trimethylsilyl, t-butyl dimethylsilyl and triphenylmethyl;

which process comprises:

(a) contacting a cyclic phosphonium halide of the formula:




wherein


n is as set forth above,
R₂ is selected from the group consisting of hydrogen, and straight and branched chain lower alkyl groups,
R₃ and R₄ are independently selected from the group consisting of phenyl, lower alkyl-substituted phenyl, lower alkoxy-substituted phenyl, and halo substituted phenyl; and
X is a halogen selected from the group consisting of chlorine, bromine, and iodine;
with an alkali metal alkoxide to produce an ylid of the formula:




wherein n, R₂, R₃ and R₄ are as set forth above;
(b) treating said ylid with an aldehyde of the formula




wherein p is as set forth above, to produce a phosphine oxide of the formula:





wherein n, p, R₂, R₃ and R₄ are as set forth above;
(c) contacting said phosphine oxide with an organo lithium compound in an aprotic solvent medium to produce a lithium salt of the formula:




wherein n, p, R₂, R₃, and R₄ are as set forth above;
(d) treating said lithium salt with a protected hydroxy aldehyde of the formula:




wherein m and R₁ are set forth above to produce an alcoholate of the formula:



wherein m, n, p, R₁, R₂, R₃ and R₄ are as set forth above;
and
(e) heating said alcoholate in an aprotic solvent medium to produce a diene of the formula:



wherein m, n, p, R₁, and R₂ are as set forth above.
3. The process of claim 1 or 2 further including the step of converting said diene to its corresponding acetate.



7. The process according to claim 1 or 2 wherein Compound IX is produced by replacement of Step (e) by treatment with a water solution in a dipolar aprotic solvent medium and treatment with an alkali or alkaline earth metal hydride.


4,296,043 PROCESS FOR THE PREPARATION OF BENZANTHRONES

Josef Schroeder, Leverkusen, Fed. Rep. of Germany, assignor to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany
Filed May 17, 1979, Ser. No. 39,790


Claims priority, application Fed. Rep. of Germany, May 26, 1978, 2823160

Int. Cl.³ C07C 50/22

U.S. Cl. 260—352 8 Claims
1. Process for the preparation of benzantrone of the formula



in which
R designates alkyl or halogen and
n represents 0, 1, 2 or 3,
which comprises contacting an anthraquinone of the formula



in which
R and n have the meaning indicated above, with acrolein or a compound from which acrolein is formed under the reaction conditions, in the presence of phosphorus or a phosphorus compound having a reducing action, in relatively highly concentrated sulphuric acid at elevated temperature, and working up the reaction mixture to give the benzantrone of the formula (I).

4,296,044 PROCESS FOR THE PREPARATION OF CATIONIC ANTHRAQUINONE DYESTUFFS

Karl H. Duchardt, and Günter Gehrke, both of Cologne, Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Jan. 31, 1980, Ser. No. 117,170


Claims priority, application Fed. Rep. of Germany, Feb. 17, 1979, 2906132

Int. Cl.³ C07C 97/25

U.S. Cl. 260—381

9 Claims


1. In the preparation of cationic anthraquinone dyestuffs of the formula




wherein

R₁ denotes hydrogen, alkyl or cycloalkyl,
R₂ denotes hydrogen, alkyl or bromine,
R₃ denotes alkylene,
R₄ and R₅ denote alkyl, aryl or aralkyl,
R₆ denotes alkyl or aralkyl and
X[−] denotes an anion,

by reacting a 4-bromoanthraquinone of the formula



with amines of the formula



in the presence of proton acceptors and copper salts as a catalyst, and subsequently quaternising the product with compounds of the formula



without intermediate isolation, the improvement which comprises carrying out the reaction of the 4-bromoanthraquinone with the amine in a solvent mixture consisting of 50–90% of one or more aprotic, non-polar or slightly polar solvents and 10–50% of one or more protic or aprotic, polar solvents, and in the presence of a base which does not precipitate the catalyst so as to trap the acid formed during the reaction.

4,296,045 PROCESS FOR THE PREPARATION OF POLY-(N-ALKYLIMINOALANES)

Salvatore Cucinella; Alessandro Mazzei, both of San Donato Milanese, and Giovanni Dozzi, Milan, all of Italy, assignors to Snamprogetti S.p.A., Milan, Italy

Continuation of Ser. No. 601,209, Aug. 1, 1975, abandoned. This application Feb. 18, 1977, Ser. No. 770,228

Claims priority, application Italy, Aug. 2, 1974, 25941 A/74; Jun. 24, 1975, 24706 A/75

Int. Cl.³ C07F 5/06

U.S. Cl. 260—448 R

10 Claims

1. In a process of preparing a poly-(N-alkyliminoalane) having the composition (HAlNR)_n, wherein R represents a member of the group consisting of aliphatic, cycloaliphatic, aromatic and alkylaromatic radicals, and n is a number in the range of 3 to 50, the process comprising reacting metallic aluminum with a primary amine having the formula H₂NR, wherein R has the significance given above, in the presence of hydrogen at a pressure in the range of from 1 to 1000 kg/cm² and at least a stoichiometric quantity of said aluminum with respect to the amine, at a temperature in the range of from room temperature to the dissociation temperature of the end product, and in the presence of an initiator composition, the improvement which comprises said initiator composition being present in an amount less than about 5 mole percent with respect to said amine, said initiator composition being selected from the group of initiators consisting of alkaline or earth-alkaline metals and hydrides of aluminum and alkaline or earth-alkaline metals, poly-(N-alkyliminoalanes) and alkyl aluminum derivatives.

4,296,046 PROCESS FOR THE MANUFACTURE OF ACRYLONITRILE

Robert A. Innes, Monroeville, and William L. Kehl, Pittsburgh, both of Pa., assignors to Gulf Research & Development Company, Pittsburgh, Pa.

Continuation-in-part of Ser. No. 972,933, Dec. 26, 1978, Pat. No. 4,222,899. This application Mar. 31, 1980, Ser. No. 135,523

Int. Cl.³ C07C 120/14

U.S. Cl. 260—465.3

10 Claims

1. A process for preparing acrylonitrile which comprises reacting propylene, ammonia and a gas containing molecular oxygen in contact with a catalyst wherein the atomic ratios of the components thereof are defined by the following empirical formula:



wherein X is an element from Group IV B of the Periodic Table; Y is at least one element selected from the group consisting of molybdenum and vanadium; a is a number falling within the range of about 1.35 to about 2.75; b is a number falling within the range of about 0.25 to about 1.65; and c is a number falling within the range of about 0.05 to about 0.25; d is a number falling within the range of about 8 to about 12; and the sum of a + b is a number falling within the range of about 2.5 to about 3.80 at a temperature in the range of about 375° to about 525° C. and a pressure of about 0 to about 100 pounds per square inch gauge for at least about 0.01 second.

4,296,047

CONTINUOUS PREPARATION OF PHOSPHORIC ACID ALKYL ESTER DICHLORIDES

Karl-Julius Schmidt; Friedrich Schmidt, both of Wuppertal; Peter Siegle, Cologne, all of Fed. Rep. of Germany, and Gert Hansen, Sao Paulo, Brazil, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Mar. 12, 1980, Ser. No. 129,852


Claims priority, application Fed. Rep. of Germany, Mar. 24, 1979, 2911700

Int. Cl.³ C07F 9/14

U.S. Cl. 260—974

7 Claims

1. In the preparation of a phosphoric acid alkyl ester dichloride by reacting phosphorus oxychloride with an aliphatic alcohol according to the equation



in which

R represents C₁–C₅-alkyl, the improvement which comprises carrying out the reaction continuously at a temperature of about 10° to 50° C. using an excess of phosphorus oxychloride of about 5 to 400%.

4,296,048

SUPPORT BRACKET FOR DISTRIBUTION PANEL FOR COOLING TOWERS AND THE LIKE


William J. Sim, 4068 Arjay Cir., Ellicott City, Md. 21043, and Ronald M. Marth, 5409 Lucy Dr., Waldorf, Md. 20601

Filed Apr. 1, 1980, Ser. No. 136,390

Int. Cl.³ B01F 3/04

U.S. Cl. 261—111

19 Claims



1. A support bracket for supporting a first beam on a second beam wherein relative movement of one beam with respect to the other beam may cause deterioration of a beam end, comprising a U-shaped strap passed over the underlying beam in inverted supported position thereon and proximate the supported beam, said strap having a supportive angle member with a flange portion being in operative supportive contact with the underside of said supported beam, the supportive engagement permitting a degree of relative movement of one said beam with respect to the other said beam.

16. A hyperbolic cross flow water cooling tower comprising an outer shell open at the top interior, a cooling ring base on said shell, a cool water basin therebelow, said cooling ring including a plurality of radially disposed superposed bent panels having upper beams thereon, a plurality of drip and water dispersing means formed as panels and supported from and suspended from at least some said bent panels, a precast concrete water distribution basin having a base comprised of curvilinear segments of double T-beams adjacently placed, with the bottoms of said T-beams supportedly resting on the said upper beam of the upper ones of said superposed bent panels, said bent panels and beams thereof being of precast concrete, said curvilinear segments having spaced ends supportedly in contact with the upper surface of said upper beam of said upper bent panel, the precast materials and environmental use causing relative movement between said T-beam bot-

toms and said upper beam, resulting in a wearing away of the ends of said T-beams, and a T-beam supportive bracket including an angle member having a horizontal and a vertical leg, inverted U-shaped straps placed over said said upper beam supporting said T-beams on each opposite side of said angle member, said vertical leg of said angle member being fixedly attached to depending legs of said strap, and integrated therewith, said horizontal leg of said angle member being operatively supportively disposed beneath said spaced ends and serving to permit relative movement of the precast members while limiting abrasive deterioration thereof.

4,296,049

DISTRIBUTOR FOR WASHING FLUID IN A SCRUBBER OR STRIPPER

Horst Ritter, Essen, Fed. Rep. of Germany, assignor to Dr. C. Otto & Comp. G.m.b.H., Bochum, Fed. Rep. of Germany


Filed Apr. 11, 1980, Ser. No. 139,504

Claims priority, application Fed. Rep. of Germany, Apr. 24, 1979, 2916462

Int. Cl.³ B01F 3/04

U.S. Cl. 261—111

8 Claims



1. Apparatus to distribute a downward flow of washing fluid in a scrubber or a stripper for treating a countercurrent gaseous or vaporous stream, said apparatus including the combination of a plurality of distributing trays each having an aperture for the upward flow of said stream, said aperture terminating at an elevation above the level of washing fluid contained by the tray thereof, a spigot extending above a tray and having a liquid receiving opening between the tray and the aperture thereabove, each spigot extending downwardly from a tray and including a liquid discharge nozzle at a lower end thereof and at least one fluid discharge opening thereabove, means for securing said spigot to a tray, a casing surrounding each spigot in a concentrically-spaced relation, and two fluid distributing members, one disposed underneath said nozzle of a spigot and the other member disposed between the nozzle and said fluid discharge opening on a portion of the spigot to project beyond said casing.

4,296,050

PACKING ELEMENT FOR AN EXCHANGE COLUMN

Werner Meier, Elgg, Switzerland, assignor to Sulzer Brothers Ltd., Winterthur, Switzerland

Filed Oct. 26, 1977, Ser. No. 845,784

Claims priority, application Switzerland, May 12, 1977, 5948/77


Int. Cl.³ B01F 3/04

U.S. Cl. 261—112

11 Claims

1. A packing element for an exchange column comprising a plurality of corrugated plates of foil-like material disposed in parallel relation, each said plate having corrugations disposed at an angle and in criss-crossing relation to the

corrugations of an adjacent plate, each said plate having a plurality of apertures distributed therein, and each said corrugation of each plate having a laterally extending fine



fluting therein whereby said apertures and said fine fluting effect a uniform distribution of a downwardly flowing liquid under capillary action.

4,296,051

METHOD OF PRODUCING GRANULAR SODIUM DICHLOROISOCYANURATE

Tadao Shimamura, and Tadayoshi Kojima, both of Tokushima, Japan, assignors to Shikoku Kasei Kogyo Co., Ltd., Marugame, Japan


Filed Oct. 22, 1979, Ser. No. 87,160

Claims priority, application Japan, Oct. 23, 1978, 53-130724

Int. Cl.³ B02C 4/00

U.S. Cl. 264—118

10 Claims



1. A method of producing granular sodium dichloroisocyanurate comprising the steps of extruding wet sodium dichloroisocyanurate having a moisture content of about 15–30% through a screen with a plurality of openings to form columnar pellets, passing said pellets through a fluidized bed heating chamber to dry said pellets until they contain substantially no free water, compacting said dried pellets to increase their bulk density, crushing said compacted pellets, and screening the crushed pellets to obtain the granular sodium dichloroisocyanurate product.

4,296,052

METHOD OF FABRICATING HELIUM-TIGHT TUBESHEET FOR HOLLOW FIBER TYPE BATTERY CELLS

Joginder N. Anand, Clayton; Timothy T. Revak, Concord, and Floris Y. Tsang, Walnut Creek, all of Calif., assignors to The Dow Chemical Company, Midland, Mich.

Division of Ser. No. 12,637, Feb. 16, 1979, Pat. No. 4,219,613.

This application Feb. 14, 1980, Ser. No. 121,357

Int. Cl.³ H05B 1/00

U.S. Cl. 264—25


6 Claims

1. A process for making a helium-tight, tubesheet/hollow fiber assembly comprising a ceramic tubesheet which has first and second generally opposed faces and is pierced by a plurality of inorganic hollow fibers having closed-ended sections

extending from said first face and open ends terminating in or beyond said second face, the portion of said tubesheet subjacent to and defining said second face being non-porous and sealingly engaged with the fibers, the remainder of the tubesheet being contiguous with said portion but not itself sealingly engaged with the fibers, and consisting essentially of sintered, ceramic particles having the same chemical composition as said portion;

said process comprising:

(a) providing a self-supporting, sintered, ceramic particle mass which has two generally opposed surfaces and is pierced by and adhered to said fibers, the closed-ended sections of which extend from one of said surfaces and the open ends of which terminate in or beyond said other surface,



the particles constituting said mass consisting of a material which

- (1) has a coefficient of thermal expansion not differing from the coefficient for the fiber material by more than 20×10^{-7} per °C.,
 - (2) is fusible, at a temperature below the softening point of the fibers, to a melt capable of bonding with them, and
 - (3) has a sufficiently low thermal conductivity so that the portion of said mass subjacent to and defining said other surface can be locally heated to said temperature and melted without causing the rest of said mass to lose its sintered, particulate structure,
- (b) so heating to said temperature said portion of said mass, and
- (c) cooling the so-heated mass to solidify the resulting layer of molten ceramic,
- thereby forming said helium-tight assembly.

4,296,053

METHOD OF MAKING FOAMED PLASTISOL INSOLES FOR SHOES

Daniel M. Doerer; Chesterfield, and Lloyd E. Brunkhorst, Florissant, both of Mo., assignors to Brown Group, Inc., St. Louis, Mo.

Filed May 24, 1979, Ser. No. 42,197


Int. Cl.³ B29D 27/04

U.S. Cl. 264—26

8 Claims

1. A process for molding insoles for footwear comprising: forming a mold cavity having a predetermined shape and surface texture; metering and depositing a foamable liquid vinyl material into the mold cavity; freely floating a stabilizing ply on the liquid vinyl material in the mold cavity; closing the mold cavity with a pressure applying head; placing gas release means between the foamable liquid vinyl material in the cavity and the head to release gaseous media and to prevent adhesion of the vinyl material to the head; applying a high frequency reversing AC field for agitating the foamable liquid vinyl

material into fusing and expanding to fill the mold cavity; and providing a reservoir for air and gas passing through the re-



lease means such that the mold cavity is vented during the agitating of the foamable liquid vinyl material.

4,296,054

METHOD FOR PRODUCTION OF POLYURETHANE CUSHION MATERIAL

Sadaaki Takagi, 39, Mikage-cho, Okazaki-shi, Aichi-ken, Japan Division of Ser. No. 893,277, Apr. 5, 1978, abandoned, which is a continuation of Ser. No. 742,568, Nov. 17, 1976, abandoned.


This application Dec. 31, 1979, Ser. No. 108,556

Claims priority, application Japan, Nov. 18, 1975, 50-138520

Int. Cl.³ B29D 27/04

U.S. Cl. 264-45.3

9 Claims



1. A method for production of a polyurethane cushion material comprising crimping a strand of large denier of a fiber filament by twisting the strand in a single twist and then further twisting it in the same direction to yield a double-twisted strand, setting it while double-twisted by wet heating, loosening the double-twisted, heat-set strand, and cutting it into staple lengths, and opening the cut staple lengths to form a three-oriented, crimped fiber filament, filling a mold with a mass of staple fiber thus formed together with polyurethane foam-forming components, foaming the polyurethane components, and post-curing the foam to complete polycondensation.

4,296,055

METHOD OF INJECTION MOLDING THERMOPLASTIC RESINOUS PRODUCTS SUBSTANTIALLY FREE FROM SINK MARKS, SWIRLS AND RELATED BLEMISHES

Wilford D. Harris, Midland, Mich., assignor to The Dow Chemical Company, Midland, Mich.

Continuation of Ser. No. 839,055, Oct. 3, 1977, abandoned, which is a continuation of Ser. No. 679,638, Apr. 22, 1976, abandoned. This application Feb. 7, 1979, Ser. No. 10,188

Int. Cl.³ B29D 27/00

U.S. Cl. 264-45.5

5 Claims

1. In a method for the injection molding of synthetic resinous thermoplastic injection moldable compositions, the method comprising providing a heat-plastified synthetic resinous composition, injecting the heat-plastified composition into a mold cavity to fill the cavity, the mold cavity having walls below the thermoplastic temperature of the composition, cooling the composition within the mold configuration until it is at

least self-supporting and removing the compositions from the mold, the improvement which comprises modifying said heat-plastified resinous composition by incorporating within the composition and in intimate admixture therewith a volatile fluid foaming agent, a particulate thermally decomposable blowing agent, the foaming agent being present in quantity sufficient to provide cell formation in the molded part and sufficient to compensate for shrinkage during cooling, a finely divided nucleating or cell inducing agent and providing a gas under pressure within the mold cavity sufficient to prevent foaming of the composition until the cavity is filled with the resinous composition, injecting said modified heat-plastified composition into said cavity, under said gas pressurized conditions which prevent foaming of the composition until the cavity is filled with the resinous composition whereby a molding substantially free from sink marks, swirls and related blemishes is obtained.

4,296,056

METHOD FOR PREPARING A FILTER MEDIUM

Alois J. Bumbalek, Hanover-Kleefeld, Fed. Rep. of Germany, assignor to Hermann Wegener Schiffgraben, Fed. Rep. of Germany


Filed Mar. 26, 1979, Ser. No. 23,832

Claims priority, application Fed. Rep. of Germany, Apr. 20, 1978, 2817176

Int. Cl.³ B29H 7/20

U.S. Cl. 264-49

8 Claims



1. A method for making a particulate filtering medium which comprises

- admixing a powder having a particle size not exceeding 70 microns, selected from the group consisting of basalt and lava, with borax and a metasilicate selected from the group consisting of sodium metasilicate and potassium metasilicate,
- sintering the mixture at a temperature between 700° and 900° C.,
- grinding the sintered product,
- treating the ground product with an inorganic acid,
- washing the acid-treated product with water, to increase the specific surface area thereof and
- drying the washed product to produce a particulate filter medium having a specific surface area in excess of 200 m²/g.

4,296,057

METHOD OF MAKING ALUMINA FIBERS

William C. Ziegenhain, Ponca City, Okla., assignor to Conoco Inc., Ponca City, Okla.

Division of Ser. No. 142,587, Apr. 21, 1980. This application Sep. 2, 1980, Ser. No. 182,878

Int. Cl.³ C04B 35/64

U.S. Cl. 264-63

3 Claims

1. A method for preparing alumina fibers comprising

- reacting aluminum alkoxides containing from 2 to about

30 carbon atoms with methanol at a temperature of from about 130° F. to about 450° F. to form solid aluminum methoxide and alcohols.

- recovering solid aluminum methoxide from the reaction mixture of (a), washing with methanol to remove higher alcohols, then
- reacting the aluminum methoxide with aqueous HCl containing from about 5 to about 15% by weight hydrochloric acid at reflux temperature of the solution for a time sufficient to convert substantially all aluminum methoxide to aluminum chlorohydrate in aqueous solution with methanol, then
- concentrating the aluminum chlorohydrate solution by removing methanol and sufficient water to a viscosity suitable for drawing fibers, then
- drawing fibers from the concentrated solution.

4,296,058

PROCESS FOR ENHANCING THE UNIFORMITY OF DYE UPTAKE OF FALSE TWIST TEXTURIZED POLYETHYLENE TEREPHTHALATE FIBROUS MATERIALS


John C. Chen, North Plainfield, and Herbert L. Davis, Convent Station, both of N.J., assignors to Celanese Corporation, New York, N.Y.

Filed Oct. 23, 1978, Ser. No. 953,662

Int. Cl.³ D01F 1/04

U.S. Cl. 264-78

18 Claims



1. In a process for providing a dyed, false twist texturized fibrous material comprising at least 85 mole percent polyethylene terephthalate which is subject to variations in dye uptake induced by a false twist texturizing treatment conducted on said fibrous material prior to or concurrently with a dyeing process, the improvement which comprises enhancing the uniformity of dye uptake of said fibrous material by:

- providing a fibrous material comprising at least 85 mole percent polyethylene terephthalate having a birefringence of at least 0.1 prior to said false twist texturizing treatment; and
- annealing said fibrous material of (a) at a temperature of about 120° to about 160° C. while controlling the length thereof in a manner sufficient to prevent a longitudinal shrinkage greater than about 10% and a longitudinal extension greater than about 5% based on the original length of the fibrous material prior to annealing, for a period of about 0.01 to about 1 second.

4,296,059

PRESSURE SEALING PROCESS


Francesco DeMaria, Gulf Breeze, Fla., assignor to American Cyanamid Company, Stamford, Conn.

Continuation-in-part of Ser. No. 938,203, Aug. 30, 1978, abandoned. This application Jul. 20, 1979, Ser. No. 59,928

Int. Cl.³ B29H 21/04

U.S. Cl. 264-130

3 Claims



1. A process for transferring a moving fiber tow bundle from a high pressure zone to a low pressure zone which comprises:

- passing said fiber tow bundle through a passageway contained in a sealing zone which provides liquid water under pressure thereto, said sealing zone being located between said high pressure zone and said low pressure zone, said passageway being confined and elongated and having a continuous longitudinal surface adapted to receive a coating of liquid water under pressure thereon by diffusion therethrough of liquid water under pressure from said sealing zone, and said passing being conducted while said coating of liquid water is continuously diffused onto said passageway surface so that said water coating and said fiber tow bundle cooperate to produce an effective pressure seal within the length and confines of said passageway and said water coating prevents contact of said fiber tow bundle with said passageway surface; and
- receiving said fiber tow bundle in said low pressure zone.

4,296,060

METHOD OF PRODUCING A PULTRUDED, FIBER REINFORCED ROD

Charles W. Killmeyer, deceased, late of Braddock Hills, Pa.; by Elizabeth A. Killmeyer, administrator, Pittsburgh, Pa.; James E. Lane, Henrietta, N.C.; Leslie L. Taylor, Jr., Forest City, N.C., and Joe T. Pearson, Lawndale, N.C., assignors to PPG Industries, Inc., Pittsburgh, Pa.

Division of Ser. No. 101,990, Dec. 7, 1979. This application Jul. 7, 1980, Ser. No. 166,522


Int. Cl.³ B29D 1/00

U.S. Cl. 264-137

7 Claims

1. An improved method of producing a pultruded, fiber reinforced, resinous rod comprising coating glass fiber continuous strands with resin, pulling the resin-coated continuous glass fiber strands through a shaping zone to provide a rod structure having at least one protrusion on the surface containing resin-coated continuous glass fiber strands, at least partially curing the resin-coated continuous glass fiber strands, passing the at least partially-cured rod through a second zone, rotating the at least partially-cured rod in said second zone relative to said first zone to form a solid rod in which at least a portion of

the continuous glass fiber strands follow the contour of at least one protrusion of the rod through the two zones and completely curing the rod; wherein the improvement comprises pulling the rod by rotating opposed surfaces against the rod



surface to move the rod through said second zone and simultaneously moving the opposed surface around the axis of the rod continuously to impart twist thereto as the surfaces are exerting pulling forces on the rod.

4,296,061

THERMOPLASTIC GLOB FEEDING AND TRANSFER METHOD AND APPARATUS


James W. Buckingham, Pemberville, Ohio, assignor to Owens-Illinois, Inc., Toledo, Ohio

Filed Mar. 19, 1980, Ser. No. 131,712

Int. Cl.³ B29B 5/06

U.S. Cl. 264—138

9 Claims



2. The method of feeding successive free falling gobs of heated thermoplastic material to successive molding cavities, comprising the steps of:

- (1) intercepting the free fall of each gob with a continuously horizontally moving transfer surface;
- (2) moving each gob solely by the movement of the transfer surface to a position horizontally spaced from its free fall path, and
- (3) deflecting each successive gob from the moving transfer surface into a molding cavity positioned below the transfer surface.

5. A gob feeding mechanism for converting a continuously extruded rod-like formation of heated thermoplastic material into a series of identical weight gobs and delivering the gobs respectively to molding members, comprising, in combination, shearing means periodically contacting the thermoplastic formation to shear freely falling gobs therefrom, a transfer plate mounted beneath the shear members, means mounting said transfer plate for continuous horizontal movement intersecting the free fall path of the gobs so that a portion of the transfer plate will periodically receive a falling gob thereon, a plurality of molding members each having an open top molding cavity, means for moving said molding members successively beneath the path of movement of said transfer plate and in timed relationship to the movement thereof, and means for deflecting

each gob on said transfer plate to fall into the open top molding cavity of a molding member passing beneath the transfer plate.

4,296,062

PROCESS FOR THE EXTRUSION OF COATED SKEIN-SHAPED PROFILES, PREFERABLY OF THERMOPLASTIC SYNTHETIC RESINS


Peter Gauchel, Alzenbach, and Waldemar Wissinger, Siegburg, both of Fed. Rep. of Germany, assignors to Dynamit Nobel Aktiengesellschaft, Troisdorf, Fed. Rep. of Germany
Division of Ser. No. 399,982, Sep. 24, 1973, Pat. No. 4,204,821.
This application Jul. 26, 1978, Ser. No. 927,985

Claims priority, application Fed. Rep. of Germany, Sep. 22, 1972, 2246679

Int. Cl.³ B29F 3/10

U.S. Cl. 264—173

12 Claims



1. A continuous process for the extrusion and sizing of an elongated multi-surfaced profile member for use as a structural component in the building industry having at least one hollow chamber formed therein, which comprises extruding a hard polyvinyl chloride to form an elongated multi-surfaced profile member having at least one hollow chamber formed therein, extruding a homopolymer or a copolymer of methyl methacrylate simultaneously and continuously with the extrusion of the elongated profile member to provide a continuous coating of the homopolymer or copolymer onto at least one partial circumferential portion of said member while said member is still within the plastic temperature range to provide a partially coated member having an exposed circumferential portion that is formed of said hard polyvinyl chloride and subsequently immediately after extrusion sizing the resulting partially coated member to provide the final precise profile configuration to said partially coated member.

4,296,063

METHOD OF PRODUCING BRACKET AND GEAR BOX OF ELECTRIC MOTOR WITH GEAR BOX AND METAL MOLD USED WITH THE SAME

Masaaki Sendo, and Kinzo Suzuki, both of Nakatsugawa, Japan, assignors to Mitsubishi Denki Kabushiki Kaisha, Tokyo, Japan

Filed Sep. 12, 1979, Ser. No. 75,209

Int. Cl.³ B29F 1/10


U.S. Cl. 264—273

10 Claims

1. A method for producing an integral unit including a metal bracket having attached thereto a gear box formed of synthetic resinous material, said unit being of the type to be used in an electric motor, said method comprising:

- providing a plate metal bracket;
- providing a composite metal mold including a stationary mold member, a first movable mold member and a second movable mold member;
- moving said first and second movable mold members relative to each other and to said stationary mold member to a mold open position providing an open space between said first movable mold member and said second movable mold member;

positioning said plate metal bracket on one of said movable mold members within said open space;
moving said first movable mold member in a first direction toward said stationary mold member while guiding said first movable mold member along a first guide means extending in said first direction, and moving said second movable mold member, in a second direction inclined to said first direction, toward both said first movable mold member and said stationary mold member while guiding said second movable mold member along a second guide means extending in said second direction and along a third guide means extending transverse to said first direction, to



thereby move said movable mold members to a mold closed position closing said open space and providing predetermined spacings between said plate metal bracket and said mold members;
introducing synthetic resinous material into said predetermined spacings, and thereby forming a gear box integrally connected to said plate metal bracket as a unit;
moving said movable mold members in directions opposite to said first and second directions to said mold open position; and
removing said integral unit of said gear box and said plate metal bracket from said mold.

4,296,064

METHOD AND STRUCTURE FOR RECYCLING SOAP CHIPS


Angel T. Satcher, 164 NE. 82 Ter., Miami, Fla. 33138

Filed Jul. 3, 1980, Ser. No. 165,604

Int. Cl.³ B29C 1/00

U.S. Cl. 264—322

1 Claim



1. A method of recycling soap chips wherein a container is utilized which comprises, an inwardly offset upper rim, the container including a floor, a space between the floor and the rim adapted to receive a charge of water therein, electrical heating means adjacent the container floor for heating the water in the container space, and separate rack including two septums perpendicular to one another, dividing the rack into four compartments; the rack compatibly mating with and suspended by the offset upper rim a predetermined distance above the water, the method comprising:
gathering chips of soap;
placing chips of soap into each of the compartments;

activating electrical heating means for heating water in container space;
melting the soap chips;
deactivating the heating means;
cooling the rack;
removing the rack from the container; and turning the rack over, emptying formed soap bars.

4,296,065

METHOD OF PRODUCING HIGHLY DENSIFIED CERAMIC ARTICLES

Takashi Ishii, Tokyo; Katsutoshi Nishida, Yokohama; Michiyasu Komatsu, Yokohama, and Akihiko Tsuge, Yokohama, all of Japan, assignors to Tokyo Shibaura Electric Co., Ltd., Kawasaki, Japan

Filed May 13, 1976, Ser. No. 685,980

Claims priority, application Japan, May 14, 1975, 50-55954

Int. Cl.³ C04B 35/58

U.S. Cl. 264—325

3 Claims

1. A method of producing ceramic articles of complicated shape having a density substantially equal to the theoretical density, said articles having a surface roughness R_{max} of from 3μ to 7μ and substantially no deformed portion, which method comprises:

- forming a preliminary molding by injection molding a powdered ceramic material selected from the group consisting of carbides, oxides and nitrides of W, Zr, Si, Al, Ta, Nb, B, V, Hf, Mo, Cr and mixtures thereof, said preliminary molding having a porosity of 30 to 70% with a uniform pore distribution;
- heating said preliminary molding at a temperature of from 1550°C . to 1900°C . to obtain a preliminarily sintered molding of a porosity below 30 percent;
- embedding said preliminarily sintered molding in a pressure transmitting powder which is nonreactive and nonfusible under the conditions of the subsequent sintering; and
- applying pressure to the pressure transmitting powder at a sintering temperature so as to compress uniformly the preliminarily sintered molding and remove the pores present in the molding.

4,296,066

MULTICHAMBER PHOTOREACTOR

Günther Schenck, Bismarckstrasse 31, 4330 Mülheim-Ruhr, Fed. Rep. of Germany


Continuation-in-part of Ser. No. 923,710, Jul. 11, 1978, Pat. No. 4,255,383. This application Jan. 28, 1980, Ser. No. 115,657

Claims priority, application Fed. Rep. of Germany, Feb. 5, 1979, 2904242

Int. Cl.³ A61L 2/10, 2/16, 2/24

U.S. Cl. 422—24

49 Claims



19. A process for purifying a fluid medium with a predetermined minimum radiation dose of ultraviolet radiation wherein, at a given location, a number n , less than four, of series connected flow paths to be passed consecutively by said medium are provided in juxtaposition to each other and the incident ultraviolet radiation is first introduced into one of said

paths and permitted to escape from said path into other of said paths, in which process the relationship between the irradiation intensities effective in each one of said flow paths and the total rate of flow of the medium through all said flow paths is established so that the sum of the fractional doses applied to the medium being passed through each one of said series connected flow paths equals said predetermined minimum radiation dose applied to the medium when it has passed consecutively through all said flow paths, said process being characterized by:

two of the flow paths provided in juxtaposition to each other having a depth ratio in the range of about 0.34 to about 0.47, said depth ratio being defined by the depth of the smaller one of said two flow paths divided by the sum of the depths of said two flow paths, and the relationship between the irradiation intensity, the character of the medium and the sum of the depths of the medium in said two flow paths being established so that the total radiation absorbed by the medium in both said two flow paths does not exceed 90 percent of the incident radiation.

4,296,067

METHOD OF STERILIZING MATERIAL, ESPECIALLY BANDAGE AND SURGICAL INSTRUMENTS, IN AN AUTOCLAVE OPERATING WITH VACUUM AND STEAM

John O. Näsman, Rapphönsvägen 15,, 122 39 Enskede, and Carl-Erik Högfeldt, Tideliussgatan 56, 116 69 Stockholm, both of Sweden


Filed Jan. 30, 1980, Ser. No. 116,843

Claims priority, application Sweden, Jan. 30, 1979, 7900813

Int. Cl.³ A61L 2/06

U.S. Cl. 422—26

3 Claims



1. A method of sterilizing material in an autoclave operating with vacuum and steam, consisting of the steps in sequence of creating vacuum in the autoclave chamber by connecting a vacuum source thereto until a predetermined pre-vacuum has been obtained, supplying steam to the autoclave chamber so that the pressure and the temperature rise to desired values during the sterilization period, interrupting the steam supply and creating an after-vacuum in the autoclave chamber, characterized in that during substantially the entire after-vacuum period the sterilization temperature prevailing in the autoclave chamber at the beginning of the after-vacuum period is maintained substantially constant by supplying dry heat in the chamber from a separate dry heat source and at the termination of the after-vacuum period, and as the vacuum is permitted to terminate, lowering the temperature slightly.

4,296,068

APPARATUS FOR STERILIZING A SUCCESSION OF FOOD CONTAINERS OR THE LIKE

Masaru Hoshino, Tokyo, Japan, assignor to Dai Nippon Insatsu Kabushiki Kaisha, Tokyo, Japan


Filed Feb. 15, 1980, Ser. No. 121,730

Claims priority, application Japan, Feb. 19, 1979, 54-17987; Jul. 31, 1979, 54-105847[U]; Aug. 8, 1979, 54-101036; Sep. 21, 1979, 54-121675

Int. Cl.³ B08B 3/12, 7/04

U.S. Cl. 422—62

26 Claims



21. A sterilizing apparatus for sterilizing successive articles being fed along a predetermined path, comprising: means for feeding the articles along the predetermined path at least in one row; means defining two opposed sterilizing chambers on the opposite sides of the predetermined path; means for supplying a sterilized liquid as a fine spray into the sterilizing chambers, whereby the successive articles traveling between the sterilizing chambers are sterilized; means for heating the sterilizing chambers and the supplying means; a light source for emitting a beam of light across at least one of the two opposing sterilizing chambers; means for receiving the light beam and generating electrical output representative of the density of the droplets of the sterilizing liquid in the sterilizing chambers; integrator means for integrating the output from the receiving and generating means during each of the successive prescribed period of time; and comparative means for comparing the output from the integrator means with a predetermined reference representative of the integral, during one of the prescribed periods of time, of the output from the receiving and generating means in the case where a desired amount of the finely sprayed sterilizing liquid is supplied into the sterilizing chamber.

4,296,069

APPARATUS FOR PROCESSING AN ANALYSIS SLIDE

Michael R. Smith, and Anthony P. DiFulvio, both of Rochester, N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.

Filed Jun. 16, 1980, Ser. No. 159,562


Int. Cl.³ G01N 35/04

U.S. Cl. 422—64

6 Claims

1. Apparatus for use in a chemical analyzer of the type which is adapted to measure a characteristic of a sample fluid deposited on an analysis slide, said apparatus comprising: incubator means including a temperature-controlled chamber having a transfer location at which an analysis slide may be transferred into or out of said chamber and conveyor means for supporting a plurality of slides in said chamber and selectively moving each of the analysis slides to and from said transfer location; means defining a read station wherein said characteristic can be measured; and slide transfer means for moving an analysis slide along a slide path extending between said incubator means and said read station, said slide transfer means including diverter means selectively conditionable in (1) a first condition wherein an analysis slide can be freely moved by said slide

transfer means along said slide path and (2) a second condition wherein an analysis slide being moved along



said slide path by said slide transfer means is diverted from said slide path.

4,296,070

SLIDE DISTRIBUTOR FOR A CHEMICAL ANALYZER


Michael S. Montalto; Douglass L. Blanding, and Michael R. Smith, all of Rochester, N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.

Filed Jun. 16, 1980, Ser. No. 159,564

Int. Cl.³ G01N 35/04

U.S. Cl. 422—65

14 Claims



1. Apparatus for use in measuring a characteristic of a sample fluid wherein the fluid is deposited on an analysis slide which is analyzed after an appropriate period of time, said apparatus comprising:

a plurality of apparatus elements, said elements being arranged in a preselected sequence along a path traveled by said slide in said apparatus, said elements including slide supply means, metering means for depositing a predetermined quantity of sample on a slide supported in a metering position, and incubator means; slide transfer means for moving a slide from said slide supply means along said slide path and for delivering a slide to a selected one of said elements; drive means for moving said slide transfer means through a series of slide advance cycles; and locating means engageable with said slide transfer means for precisely positioning said slide transfer means and a slide therein relative to each of said elements after each advance cycle to facilitate the processing of the slides and the transfer of slides between said elements and said transfer means.

4,296,071

PIPETTE WITH ELASTIC BELLOWS

Erich Weiss, Mannheim-Sandhofen, and Dieter Ungermann, Mannheim, both of Fed. Rep. of Germany, assignors to Boehringer Mannheim, Mannheim-Waldhof, Fed. Rep. of Germany

Filed Nov. 14, 1979, Ser. No. 94,134

Claims priority, application Fed. Rep. of Germany, Nov. 29, 1978, 2851532

Int. Cl.³ B01L 3/02; G01N 1/14; A61M 1/00

U.S. Cl. 73—864.11

8 Claims



1. A pipette comprising: an elongated casing; an elastic bellows disposed in the casing with one end thereof fixed to the casing; and means mounting the other end of the bellows for longitudinal movement relative to the casing from a rest position to a predetermined compressed position and wherein the bellows is prestressed over the entire range of travel between the rest and compressed positions and has sufficient elasticity to return to the rest position unaided, the mounting means comprising stop means forming two separate stops limiting movement of the other end of the bellows wherein one stop defines the rest position and the other stop defines the compressed position.

4,296,072

APPARATUS FOR THE TREATMENT OF WET SOLIDS, ESPECIALLY PULPY MATERIALS, BY HEATING OR COOLING

Istvan Takacs; Zoltan Banos; Janos Illes; Endre Vereczkey; Peter Rudolf, and György Kerey, all of Budapest, Hungary, assignors to Richter Gedeon Vegyeszeti Gyar, Budapest, Hungary


Filed Mar. 19, 1980, Ser. No. 131,825

Claims priority, application Hungary, Mar. 21, 1979, RI 702

Int. Cl.³ B01D 1/14, 9/02, 9/04, 11/00

U.S. Cl. 422—254

10 Claims



1. An apparatus for treatment of wet solids, especially pulpy organic materials comprising: a hollow treating body rotatable about a horizontal axis; means for feeding the material to be treated into said treating body; means for discharging the treated material from said treating body; and means for controlling the temperature of said treating body, said treating body comprising: a treating drum centered on said horizontal axis and communicating thereat with said feeding means, said drum having a polygonal cross section defined by an axially flared peripheral wall formed by a plurality of planar panels, each having a pair of nonparallel opposing edges, said peripheral wall being flanked by first and second polygonal end walls of different size centered on said horizontal

axis and perpendicular thereto, said first and second end walls being connected at corresponding edges to said peripheral wall,

a first duct having a polygonal cross section communicating with said drum at a location wholly offset from said horizontal axis and having a first longitudinal axis forming an angle therewith,

a second duct having a polygonal cross section communicating with said first duct at said horizontal axis and having a second longitudinal axis forming an angle therewith, said first and second longitudinal axes intersecting on said horizontal axis,

a third duct having a polygonal cross section communicating with said second duct at a location wholly offset from said horizontal axis and having a third longitudinal axis forming an angle therewith, and

a fourth duct having a polygonal cross section communicating with said third duct at said horizontal axis and having a fourth longitudinal axis forming an angle therewith, said third and fourth longitudinal axes intersecting at a location offset from said horizontal axis, said fourth duct having an outlet centered on said horizontal axis and communicating with the discharge means, said first, second, third and fourth ducts having substantially the same cross sectional area.

4,296,073

HIGH TEMPERATURE ATTACK OF ORES BY MEANS OF A LIQUOR ESSENTIALLY CONTAINING A SOLUBLE BICARBONATE

Pierre Maurel; Francois Nicolas, both of Aix-en-Provence, and Bernard Bosca, Gardanne, all of France, assignors to Aluminium Pechiney, Lyons, France

Filed Jan. 31, 1979, Ser. No. 7,920

Claims priority, application France, Sep. 2, 1978, 78 04468
Int. Cl.³ C01G 43/00

U.S. Cl. 423—3

13 Claims

1. In a process for the oxidizing attack at high temperature of ores containing at least one metal from the group formed by uranium, vanadium and molybdenum, by means of an aqueous liquor containing sodium bicarbonate and sodium carbonate in the presence of free oxygen blown into the reaction medium, the separation of the sterile fractions and the liquor emanating from the attack containing the dissolved metal or metals, the improvement comprising treating the ore with an aqueous liquor containing a majority of sodium bicarbonate and a minority of sodium carbonate in which the ratio by weight of sodium bicarbonate (NaHCO_3) to sodium carbonate (Na_2CO_3) is at least 1.5, injecting the free oxygen into the reaction medium while in a reaction vessel to provide a pressure of oxygen in the reaction vessel of at least 5 bars and maintaining the temperature of the reaction medium between 160° C. and 300° C. for a period of at most 6 hours.

4,296,074

METHOD OF DECLADDING

Samuel J. Yosim, Woodland Hills, Calif., assignor to Rockwell International Corporation, El Segundo, Calif.

Filed Apr. 10, 1978, Ser. No. 894,678

Int. Cl.³ G21C 19/34

U.S. Cl. 423—4

6 Claims


1. A method of decladding an assembly comprising an element selected from the group consisting of uranium, thorium and mixtures thereof, clad in stainless steel, zirconium or a zirconium alloy consisting essentially of zirconium and containing minor amounts of nickel, chromium, tin, iron and combinations thereof; said method comprising:

perforating the cladding material to expose the selected element;

reacting said selected element with hydrogen at a temperature of from 450° C. to 680° C. and a hydrogen pressure of

from 360 to 1400 torr for a time sufficient to form a hydride of substantially all of the selected element;

increasing the temperature to a range of from about 700° C. to 900° C. to dehydride the selected element to reduce it back to its elemental form;



separating the cladding material from the selected element; and
recovering the selected element in a friable particulate readily comminutable form.

4,296,075

METHOD FOR PROTECTING AN ION-EXCHANGE RESIN FROM CHEMICAL POISONING


Tsoungh-yuan Yan, Philadelphia, Pa., assignor to Mobil Oil Corporation, New York, N.Y.

Filed Nov. 24, 1978, Ser. No. 963,661

Int. Cl.³ C01G 43/00

U.S. Cl. 423—7

7 Claims



1. A method for protecting an ion-exchange resin used for adsorbing uranium and/or related values from a leach solution from poisoning caused by polythionates in the leach solution, the method comprising:

passing the leach solution through a catalytic material before passing the leach solution through said resin, said catalytic material converting said polythionates in the leach solution into non-poisoning thiosulfates, sulfites, and water.

4,296,076

CHROMIC OXIDE PRODUCTION

Danvers A. Swales, and Michael A. Marshall, both of Darlington, England, assignors to British Chrome & Chemicals Ltd., Stockton-on Tees, England

Continuation-in-part of Ser. No. 3,333, Jan. 15, 1979, abandoned. This application Jul. 7, 1980, Ser. No. 166,713

Int. Cl.³ C01G 37/033

U.S. Cl. 423—53

18 Claims

1. A process for the preparation of chromic oxide having a water insoluble sulphur content of below about 40 ppm, which comprises calcining a solid product feed material at a tempera-

ture ranging from above 1100° to 1600° C. for a time period of from about 10 minutes to 10 hours, said solid product containing at least 60 ppm water insoluble sulphur and from 0.1 to 50% by weight of water soluble material (based on chromic oxide), and optionally containing materials that will volatilize during calcining, and selected from the group consisting of

(a) impure chromic oxide, and

(b) a heat decomposable product that will decompose during calcining to form the said solid product feed material.

4,296,077

RECOVERY OF MOLYBDENUM VALUES FROM LEACH MUDS

Steven R. Heuer, Arvada, and Zdenka Zbrank, Littleton, both of Colo., assignors to Engelhard Min. & Chem. Corp., Iselin, N.J.

Filed Nov. 10, 1980, Ser. No. 205,843

Int. Cl.³ C01G 39/00

U.S. Cl. 423—53

4 Claims

1. In a process for the recovery of molybdenum values from molybdenite concentrates wherein the molybdenite concentrate is roasted in the presence of air to convert molybdenum sulfide to molybdenum trioxide and the resulting concentrate containing molybdenum trioxide leached with an aqueous alkaline solution whereby soluble molybdenum salts are extracted therefrom and dissolved in the leach solution and the insoluble solid leach mud separated from the leach solution, the improvement which comprises repulping the leach mud with an aqueous ammonia solution under pressure with an oxygen-containing gas, at a temperature in the range of about 50° to 150° C. for at least about 2 hours, separating residual undissolved solids from said aqueous ammonia solution, repulping said undissolved solids with an aqueous caustic leach solution at a temperature in the range of about 50° to 150° C. for at least about 2 hours, separating solid residue from said caustic leach solution, and recovering said leach solutions containing dissolved molybdenum salts.

4,296,078

SEPARATION OF HYDROGEN CHLORIDE FROM GASEOUS MIXTURES

Cyril B. Tellis, 818 Beaumont Rd., Charleston, W. Va. 25314

Filed Oct. 7, 1980, Ser. No. 194,775

Int. Cl.³ B01D 53/34

U.S. Cl. 423—240

3 Claims

1. The method for the selective separation of hydrogen chloride from a gaseous mixture containing hydrogen chloride, carbon dioxide and other gaseous impurities which comprises contacting said gaseous mixture with a cross-linked, water-insoluble polymer of N-glycidylpiperazine at a temperature between about -10° and 100° C.

4,296,079

METHOD OF MANUFACTURING ALUMINUM SULFATE FROM FLUE GAS

H. William Hauser, Marietta, Ga., assignor to Vinings Chemical Company, Atlanta, Ga.

Continuation of Ser. No. 877,038, Feb. 10, 1978, abandoned.

This application Apr. 21, 1980, Ser. No. 170,772

Int. Cl.³ C01B 17/00

U.S. Cl. 423—242

9 Claims

1. A continuous process for removing sulfur dioxide from sulfur dioxide containing flue gas which comprises:

(a) Continuously contacting an aqueous solution, at a temperature of from 40° to 70° C., containing from 1 to 15 percent by weight sodium aluminate and having a pH between 2 and 10 with a sulfur dioxide containing flue gas at a ratio of between 0.20 and 2 mols of sodium aluminate per mol of sulfur dioxide in a gas-liquid contacting device so that at least a substantial portion of the sulfur dioxide in the flue gas is absorbed into the aqueous solution where it

reacts with sodium aluminate to produce sodium sulfite and aluminum hydroxy sulfite;

(b) Transporting the aqueous solution of sodium sulfite and aluminum hydroxy sulfite to a solid-liquid separator and adjusting the pH and temperature of the solution until the aluminum hydroxy sulfite forms an insoluble precipitate, which is then separated from the solution by suitable separating means; and

(c) Transporting the aluminum hydroxy sulfite precipitate to an oxidizing reactor where water is added to form a slurry which is maintained at a temperature of from 60° to 90° C. and an oxidizing agent is used to oxidize the aluminum hydroxy sulfite to aluminum sulfate which is then separated from the slurry by suitable separating means.

4,296,080

PROCESS FOR THE REMOVAL OF PARTICULATES ENTRAINED IN A FLUID USING A MAGNETICALLY STABILIZED FLUIDIZED BED


Ronald E. Rosensweig, Summit, N.J., assignor to Exxon Research & Engineering Co., Florham Park, N.J.

Division of Ser. No. 786,613, Apr. 11, 1977, Pat. No. 4,115,927, which is a continuation-in-part of Ser. No. 610,071, Sep. 3, 1975, abandoned, which is a continuation-in-part of Ser. No. 514,003, Oct. 11, 1974, abandoned. This application Aug. 21, 1978, Ser. No. 935,566

Int. Cl.² C01B 17/60

U.S. Cl. 423—244

20 Claims



1. A process for the removal of contaminant particulates entrained in a fluid stream containing the same, which process comprises:

(a) removing said particulates by passing said fluid stream through at least one controllably moving particulate capture bed comprising magnetizable particles within a scrubber vessel, said bed being expanded and levitated by said stream and controllably moving said bed in response to a pressure differential in said bed, wherein at least a portion of said bed is subjected to an applied magnetic field having a substantial component along the direction of said external force field at a strength such that gross solids backmixing and fluid by-passing in said bed are suppressed but less than that which impairs the fluid-like properties of the bed; and (b) removing the retained particulates from said bed, wherein the product of the magnetic moment of the particulates in said fluid and the magnetic moment of the magnetizable particles is less than about 50(emu/gr)².

4,296,081

PROCESS FOR PURIFYING GASEOUS EFFLUENTS

Michel Nomine, and Gerard Chelu, both of Verneuil-en-Halatte, France, assignors to Charbonnages de France, France

Filed Feb. 1, 1980, Ser. No. 117,674

Claims priority, application France, Feb. 8, 1979, 79 03249

Int. Cl.³ B01D 53/34

U.S. Cl. 423—245

10 Claims

1. A process for purifying aldehyde-containing air comprising submitting the air to the simultaneous action of small quantities of sulphurous anhydride (SO_2) and ammonia, followed by washing with water.


4,296,082

PURIFICATION OF WET PROCESS PHOSPHORIC ACID
Edward J. Lowe, Stourbridge; Michael W. Minshall, Wombourne, and Arthur Wilson, Stourbridge, all of England, assignors to Albright & Wilson Limited, Warley, England

Continuation-in-part of Ser. No. 899,896, Apr. 26, 1978, Pat. No. 4,215,098. This application Apr. 10, 1979, Ser. No. 28,680. The portion of the term of this patent subsequent to Jul. 29, 1997, has been disclaimed.

Int. Cl.³ C01B 25/40, 25/16; B01D 1/00
U.S. Cl. 423—305

39 Claims



1. A method for the production of purified phosphoric acid or phosphatic derivatives of wet process phosphoric acid which comprises heating wet process phosphoric acid in an evaporator vessel having carbon walls which are electrically conducting and which are stable to the concentrated phosphoric acid at the evaporation temperatures, to evaporate water therefrom to leave a concentrated acid by direct electrical resistance heating by passing an alternating current through said wet process acid until the concentration of said acid is at least 76% by weight P_2O_5 , precipitating solid impurities in said concentrated acid and separating solid impurities from the purified phosphoric acid or phosphatic derivative.

4,296,083

ZEOLITE SYNTHESIS

Louis D. Rollmann, Princeton, N.J., assignor to Mobil Oil Corporation, New York, N.Y.


Continuation-in-part of Ser. No. 925,015, Jul. 17, 1978, abandoned, which is a continuation-in-part of Ser. No. 789,901, Apr. 22, 1977, abandoned. This application Nov. 14, 1979, Ser. No. 93,958

Int. Cl.³ C01B 33/28

U.S. Cl. 423—329

14 Claims

1. A method for synthesizing zeolites, said zeolites characterized by an alumina to silica mole ratio of not greater than 0.083 and a constraint index within the approximate range of 1 to 12, which comprises forming a reaction mixture containing one or more sources of alkali metal oxide, organic nitrogen-containing cations provided by an amine, hydrogen ions, an oxide of silicon, water and, optionally, an oxide of aluminum, in which the composition, in terms of mole ratios of oxides, is as follows:



wherein R is an organic nitrogen-containing cation source, M is an alkali metal ion, and wherein the pH of said reaction mixture is at least about 7 and maintaining the reaction mixture at a temperature and pressure for a time necessary to crystallize therefrom said zeolite.

4,296,084

METHOD OF AND APPARATUS FOR GAS GENERATION


Gary V. Adams, Brigham City, and Fred E. Schneider, Ogden, both of Utah, assignors to Thiokol Corporation, Newtown, Pa.

Filed Oct. 29, 1979, Ser. No. 88,992

Int. Cl.³ C01B 21/02

U.S. Cl. 423—351

26 Claims



1. A method of generating clean nitrogen gas in which most of the combustion residue product has been removed comprising

- providing a combustible composition essentially 60-80% sodium azide, 2-26% ferric oxide, 2-26% molybdenum disulfide and 0-6% sulfur,
- placing said combustible composition in a combustion chamber having gas discharge orifices,
- raising the temperature of said combustible composition sufficiently to ignite it, and
- providing filtering means and cooling means between said combustible composition and said gas discharge orifices, said filtering means being selected for its compatibility with the combustion process and for its characteristic property at the combustion temperature of said composition of becoming less porous for a short interval during an early stage of the combustion function time thereby, during such interval, to increase the restrictive effect thereof and to retard the flow of combustion products out of said gas discharge orifices to allow such combustion products to be cooled by and condensed on said cooling means.

4,296,085

PROCESS FOR THE PRODUCTION OF AMMONIA AND THE CORRESPONDING SYNTHESIS GAS

David L. Banquy, 39 Rue St-Placide, Paris, France (75006)


Filed Mar. 19, 1980, Ser. No. 131,837

Claims priority, application France, Jan. 7, 1980, 80 00196

Int. Cl.³ C01B 2/02, 2/30; C01C 1/04

U.S. Cl. 423—359

9 Claims



6. A process for producing ammonia synthesis gas from a desulfurized hydrocarbon containing feedstock available at a pressure of at least 30 bars, comprising:

4,296,087

METHOD FOR PRODUCING CARBON BLACK

Robert J. Lewis, Eden Prairie, Minn., assignor to Phillips Petroleum Company, Bartlesville, Okla.

Division of Ser. No. 946,654, Oct. 2, 1978, Pat. No. 4,237,092.

This application May 15, 1980, Ser. No. 150,124

Int. Cl.³ C01B 31/02; C09C 1/48

U.S. Cl. 423—449

13 Claims

1. In a method for producing carbon black comprising the steps of:

- contacting hot combustion gases and a carbonaceous feed in a reaction zone to thereby produce carbon black and gas; separating said carbon black from said gas; and
- utilizing at least a part of the thus separated gas as a recycle gas to supply at least a part of said hot combustion gases; the improvement comprising the step of: maintaining the ratio of the volume of said hot combustion gases to the volume of said carbonaceous feed substantially constant at a desired temperature for said hot combustion gases.

4,296,088

HEAT EXCHANGE TECHNIQUES FOR THE CATALYTIC OXIDATION OF GASEOUS SULFUR COMPOUNDS TO SULFUR TRIOXIDE

Adolf Stauffer, Pulheim, Fed. Rep. of Germany, assignor to International Aktiengesellschaft, Cologne, Fed. Rep. of Germany

Continuation of Ser. No. 888,597, Mar. 20, 1978, abandoned.


This application Nov. 20, 1979, Ser. No. 96,127

Claims priority, application Fed. Rep. of Germany, Mar. 18, 1977, 2711897

Int. Cl.³ C01B 17/76, 17/80

U.S. Cl. 423—533

13 Claims



1. In a process for the catalytic oxidation of gaseous sulfur compounds to sulfur trioxide comprising passing said gaseous sulfur compounds through a plurality of serially connected spatially separate zones, each zone being either a catalytic reaction zone which, optionally is in contact with a heat exchange medium or, an uncatalyzed heat exchange zone, and there being at least one catalytic zone in indirect contact with the heat exchange medium and one said heat exchange zone, the improvement which comprises using a liquid heat exchange medium and for each of said catalytic reaction zones which is in contact with said heat exchange medium and for said spatially separate heat exchange zones, the heat exchange is accomplished by circulating said liquid heat exchange medium in indirect heat exchange relationship therewith and with a heat consumer or heat source; the circulation rate being high enough and the amount of the medium being such that the liquid heat exchange medium exchanges heat in said heat exchange zones, said heat exchanged catalytic reaction zones and said heat consumer or source and has a temperature differential of no more than 5 centigrade degrees throughout the circula-

4,296,086

MONITORING PROCESS AND APPARATUS

Paul Whitehead, Binfield Heath, England, assignor to Johnson, Matthey & Co., Limited, London, England

Filed Dec. 10, 1979, Ser. No. 101,857

Claims priority, application United Kingdom, Dec. 15, 1978, 48663/78

Int. Cl.³ G01N 21/78; C01B 21/06

U.S. Cl. 423—392

16 Claims

1. A process of monitoring the ammonia oxidation conversion efficiency in a nitric acid plant which comprises taking samples of the reactant mixture and of the reaction product, and measuring both the ammonia content in the sample of reactant mixture and the nitrogen oxide content in the sample of reaction product by ultraviolet spectrophotometry using ultraviolet light of wavelength 200-220 nm, the nitrogen oxide content in the sample of reaction product being measured after converting any nitric oxide in said sample to nitrogen dioxide at elevated temperature and pressure.

tion path of said heat exchange medium, thereby controlling the temperature of said heat exchange zones; said liquid heat exchange medium remaining liquid throughout the circulation thereof.

4,296,089

INORGANIC FIBERS

Alois Aignesberger, Trostberg, Fed. Rep. of Germany; Walter Lukas, Innsbruck, Austria, and Ekkehard Weinberg, Trostberg, Fed. Rep. of Germany, assignors to Sueddeutsche Kalkstickstoff-Werke, Trostberg, Fed. Rep. of Germany Division of Ser. No. 792,081, Apr. 28, 1977. This application Feb. 28, 1979, Ser. No. 16,054

Claims priority, application Fed. Rep. of Germany, May 14, 1976, 2621611

Int. Cl.³ C01F 11/46; C04B 11/00

U.S. Cl. 423—555

8 Claims

1. Method for the preparation of calcium sulfate dihydrate fibers or their dehydration products having a ratio of average length to diameter of more than 100:1 and a length of at least 0.2 mm, which method comprises

reacting a dilute aqueous solution of at least one calcium salt at elevated temperature with a dilute aqueous solution of the stoichiometric amount of a water-soluble sulfate at pH values between 8 and 13,

the reaction mixture obtained to stand until the desired fiber length is achieved, and separating the fibers formed from the solution after achieving the desired length.

4,296,090

ANTI-D TEST AND REAGENT

Henry A. Graham, Jr.; David J. Olekna, both of Annandale; Johnna B. Hawk, Rocky Hill, and Diane M. Barrett, Somerville, all of N.J., assignors to Ortho Diagnostics, Inc., Raritan, N.J.

Continuation-in-part of Ser. No. 57,481, Jul. 13, 1979, abandoned. This application Oct. 5, 1979, Ser. No. 82,199 Int. Cl.³ G01N 33/80

U.S. Cl. 424—11

14 Claims

1. A method for rapidly determining the presence or absence of D antigen on the red blood cells of a given individual which comprises the steps of:

- obtaining a sample of red blood cells to be tested;
- adding to and mixing with said sample an antibody reagent to form a mixture; and
- without incubation observing said mixture to determine whether agglutination does or does not occur;

wherein said antibody reagent comprises reduced and S-alkylated anti-D IgG which has an average titer of at least 32 for Dce cells in the slide test or rapid tube test.

7. A method for preparing an antibody reagent useful for rapidly determining the presence or absence of D antigen on red blood cells, which antibody reagent has an average titer of at least 32 for Dce cells in the slide test or the rapid tube test, which comprises the steps of:

- obtaining a substantially lipid-free anti-D human antiserum;
- adjusting the pH of said antiserum to about 8.6 by addition of an effective buffering amount of a compatible buffer;
- reducing said buffered antiserum with a reducing agent;
- S-alkylating said reduced buffered antiserum with an S-alkylating agent;
- dialyzing said S-alkylated reduced antiserum at a pH between 7.5 and 8.3; and
- adjusting the total protein concentration to about 6–10% by weight by addition of a nonspecific protein.

4,296,091

NOVEL SYNERGISTIC INSECTICIDES

Robert Joly, Montmorency; Charles Pavan, Nogent-sur-Marn, and Pierre R. Carle, Rognonas, all of France, assignors to Roussel Uclaf, Paris, France

Filed Mar. 10, 1980, Ser. No. 128,461

Claims priority, application France, Mar. 16, 1979, 79 06712 Int. Cl.³ A01N 25/00, 37/00, 37/08, 25/06

U.S. Cl. 424—18

17 Claims

1. An insecticidal composition comprising as the active ingredient an insecticidally effective amount of a synergistic mixture of 80 to 70% by weight of (S) 1-oxo-2-allyl-3-methylcyclopent-2-en-4-yl d trans chrysanthemate and 20 to 30% by weight of (R) 1-oxo-2-allyl-3-methylcyclopent-2-en-4-yl d trans chrysanthemate.

4,296,092

MUCOLYTIC BENZENE AND THIOPHENE-CARBOTHIOIC ACID 2-AMINOALKYL ESTER ACID SALTS

Harry R. Munson, Jr., Richmond, Va., assignor to A. H. Robins Company, Inc., Richmond, Va.

Continuation-in-part of Ser. No. 932,747, Aug. 10, 1978,


abandoned. This application Nov. 19, 1979, Ser. No. 95,761

Int. Cl.³ A61K 9/00, 31/38, 31/265

U.S. Cl. 424—43

18 Claims

1. A method of combatting mucus build-up in an animal body for the purpose of alleviating lung congestion in an animal suffering therefrom which comprises administering to said animal an effective amount of a compound having the formula:



wherein;

R is 2-thiophene, benzene and benzene substituted by one to 3 radicals which may be the same or different, selected from halogen, lower-alkyl, lower-alkoxy, carboxy, trifluoromethyl;

X⁻ is a chlorine or bromine radical, and n is 2 or 3.

18. 2-thiophenecarbothioic acid, 2-aminoethyl ester monohydrochloride.

4,296,093

CYCLIC CARBOXAMIDES HAVING A PHYSIOLOGICAL COOLING EFFECT

David G. Rowsell, Staines; John M. Gascoyne, Southall, and Roger Hems, Maidenhead, all of England, assignors to Wilkinson Sword Limited, London, England

Division of Ser. No. 351,356, Apr. 16, 1973, abandoned. This application Feb. 4, 1980, Ser. No. 118,205

Int. Cl.³ A61K 9/68, 31/16


U.S. Cl. 424—45

12 Claims

1. In a manufactured consumer product for application to or consumption by the human body and being:

- a personal care product comprising a topically or orally administrable base medium containing a flavourant, colourant, perfume, surface active agent or antiseptic agent;
- an ingestible preparation comprising an edible or potable base containing a flavourant or colourant;
- a pharmaceutical preparation comprising a topically or orally administrable pharmaceutically acceptable carrier and an active pharmaceutical ingredient; or
- a tobacco containing consumer product, said consumer product also containing an ingredient capable of stimulating the cold receptors of the nervous system of the surface tissues of the body when brought into contact therewith by application or consumption of the said product, the

improvement which comprises using as said cold receptor stimulating ingredient an effective amount of a cyclic carboxamide of the formula



wherein

R' is C₁–C₅ alkyl and R'' is hydrogen or C₁–C₅ alkyl, with the proviso that R' and R'' together provide a total of from 1–8 carbon atoms; and

R₁ and R₂ are each hydrogen, C₁–C₅ alkyl or C₁–C₈ hydroxyalkyl and together provide a total of 0 to 8 carbon atoms, with the proviso that when R₁ is H then R₂ may also be alkylcarboxyalkyl of up to 6 carbon atoms.

4,296,094

DENTAL CLEANING COMPOSITION AND METHOD

Yoshio Matsushima; Teruhiko Kumura; Isamu Kawamura, all of Takamatsu, and Terushige Kawata, Tokushima, all of Japan, assignors to Kyowa Chemical Industry Co., Ltd., Tokyo, Japan


Filed Jun. 2, 1980, Ser. No. 155,165

Int. Cl.³ A61K 7/16, 7/18

U.S. Cl. 424—49

12 Claims

1. A dental cleaning composition comprising about 0.01 to about 30% by weight, based on the composition, of a hydrotalcite compound of the following formula



wherein

Aⁿ⁻ represents an anion having a valence of n, x is a positive number represented by 0 < x < 0.5, y is a positive number represented by 0 < y ≤ 0.5, and m is a positive number represented by 0 < m < 2, and at least one dentally acceptable carrier or diluent selected from the group consisting of polishing agents, moisture-retaining agents, binders, and foaming agents.

4,296,095

DENTAL AND MOUTH CARE PREPARATIONS

Udo Hoppe, Hamburg; Gerhard Sauermann, Wiemersdorf; Julius Curtis, Hamburg, all of Fed. Rep. of Germany; Per-Olof Glantz, Lund, Sweden; Bo Krasse, Askim, Sweden; Kare Larsson, Hovas, Sweden; Börje Noren, Upsala, Sweden; Göran Odham, Södra Sandby, Sweden, and Jan Olsson, Hovas, Sweden, assignors to Beiersdorf Aktiengesellschaft, Hamburg, Fed. Rep. of Germany

Filed Sep. 20, 1978, Ser. No. 944,195

Claims priority, application Fed. Rep. of Germany, Sep. 21, 1977, 2742411

Int. Cl.³ C07C 101/24; A61K 7/22

U.S. Cl. 424—52

10 Claims

1. A method for preventing the formation of dental plaque and tartar on teeth comprising applying to said teeth an effective amount of a composition comprising from 0.1 to 20% by weight, based on the total weight of the composition, of a compound of the formula



wherein R is selected from the group consisting of straight chain alkyl, branched chain alkyl and alkenyl all having 14 to 18 carbon atoms, X is a group which renders said compound a salt and n has a value of 0, 1 or 2, and a carrier suitable for application to said teeth, and the inside of the mouth.

4,296,096

HIGH VISCOSITY DENTIFRICE

Robert C. Pierce, Plainsboro, N.J., assignor to Colgate-Palmolive Company, New York, N.Y.

Continuation-in-part of Ser. No. 54,779, Jul. 5, 1979, abandoned.

This application Mar. 25, 1980, Ser. No. 133,706

Int. Cl.³ A61K 7/16, 7/18

U.S. Cl. 424—52

9 Claims

1. A dentifrice toothpaste or gel having a viscosity of about 50,000 to 420,000 cps (measured at 10 rpm with #7 spindle on Brookfield Viscometer Model RBF at 22° C.), said viscosity being sufficiently high so that said dentifrice is not liquid and runny and not so high that it is difficult to extrude from a dentifrice containing a normally water-insoluble dentally acceptable polishing agent, up to about 89.5% by weight of water and requiring added humectant and gelling agents, said dentifrice containing, as its sole essential humectant and gelling agent, a water-absorbent anionic polyelectrolyte polymer which provides and imparts both gelling and humectant characteristics to said dentifrice, said anionic polyelectrolyte polymer consisting essentially of a polyacrylic acid ionically complexed with a polyvalent metal cation selected from the group consisting of aluminum, zirconium, iron and zinc at a pH between 2.0 and 8.5 which pH is below the pH of reversibility of the ionic complex of said polyvalent cation and said water absorbent anionic polyelectrolyte, said ionically complexed polyelectrolyte polymer having a particle size such that at least about 90% of the particles are larger than 2 microns, each of said particles having a linkage density at the particle surface greater than the linkage density in the particle interior, the linkages at the particle surface comprising at least in part ionic complexing of said anionic polyelectrolyte polymer by said polyvalent metal cations, said anionic polyelectrolyte polymer being provided in said dentifrice in an amount of about 0.5–20% by weight, said dentifrice containing a humectant and gelling agent selected from the group consisting of: (a) said anionic polyelectrolyte polymer as the sole humectant and gelling agent; (b) said anionic polyelectrolyte polymer as the sole gelling agent and up to about 20% by weight of an additional humectant; (c) said anionic polyelectrolyte polymer as the sole humectant and up to about half the amount of said anionic polyelectrolyte polymer of an additional gelling agent; and (d) said anionic polyelectrolyte polymer with up to about 20% by weight of an additional humectant and up to about half the amount of said anionic polyelectrolyte polymer of an additional gelling agent; wherein said additional humectant and said additional gelling agent provide rheological modifications in the character of said dentifrice.

4,296,097

SUPPRESSION OF REAGINIC ANTIBODIES TO DRUGS EMPLOYING POLYVINYL ALCOHOL AS CARRIER THEREFOR

Weng Y. Lee, 99 Silver Ridge Rise NW., Calgary, Alberta, Canada (T3B 4P6), and Alec Sehon, 695 Academy Rd., Winnipeg, Manitoba, Canada (R3N 0E8)

Filed Feb. 27, 1979, Ser. No. 15,864

Int. Cl.³ A61K 31/74, 31/43


U.S. Cl. 424—78

9 Claims

1. A process for the suppression of the formation of anti-BPO (benzylpenicilloyl) antibodies in a person sensitive to penicillin which comprises administering to said person a suppressing effective amount of a conjugate that is prepared by the reaction of penicillin with an amino derivative of water-soluble, nonimmunogenic polyvinylalcohol polymers, said reaction being carried out in the presence of a suitable salt and at an alkaline pH.

9. A process for the suppression of IgE antibodies which are responsible for allergies to a wide spectrum of drugs which comprises administering a suppressing effective amount of a

conjugate that is prepared by the reaction of the potentially allergenic drug with an amino derivative of water-soluble,



nonimmunogenic polyvinylalcohol polymers in the presence of a suitable salt and at an alkaline pH.

4,296,098

COMPOSITIONS AND METHODS FOR THE TREATMENT OF ATHLETE'S FOOT

Masataro Sato, 2-chome, No. 28-26 Fukuokamachi, Takamasatu City, Japan

Continuation of Ser. No. 882,790, Mar. 2, 1978, abandoned, which is a division of Ser. No. 759,492, Jan. 14, 1977, Pat. No. 4,108,984. This application May 31, 1979, Ser. No. 44,305. The portion of the term of this patent subsequent to Aug. 22, 1995, has been disclaimed.

Int. Cl.² A61K 37/48

U.S. Cl. 424—94

1 Claim

1. A composition for the treatment of wet athlete's foot, comprising a dry mixture of finely powdered montmorillonite and pyroligneous acid in a weight ratio of about 4:1, and a small quantity of papain enzyme present in an amount of about 1/5000 by weight of the mixture.

4,296,099

PROCESS FOR EXTRACTING EMBRYONIC CALF SKIN AND PHARMACEUTICAL COMPOSITIONS CONTAINING THE SAME

Claudine Berrebi, and Georges Manoussos, both of Paris, France, assignors to L'Oreal, Paris, France

Continuation of Ser. No. 746,018, Nov. 30, 1976, abandoned. This application May 13, 1980, Ser. No. 149,561

Int. Cl.² A61K 35/48, 7/42

U.S. Cl. 424—105

10 Claims

1. A process for preparing an embryonic calf skin extract having improved cicatrizing activity from calf skin taken between the second month of gestation and birth comprising the steps of (i) grinding said embryonic calf skin, (ii) extracting the resulting ground embryonic calf skin in an aqueous medium at a pH of 4 obtained by the addition thereto of an organic acid selected from the group consisting of acetic acid, citric acid, trichloroacetic acid, succinic acid, ascorbic acid and lactic acid, the ratio of calf skin, kg/liter of said aqueous extraction medium being between 1:1 to 1:4 and at a temperature between 60° C. and 75° C. for 15 hours, (iii) separating the resulting extract from the insolubles, and (iv) lyophilizing the said separated extract.

2. An extract of embryonic calf skin having improved cicatrizing activity obtained in accordance with the process of claim 1.

4,296,100 METHOD OF TREATING THE HEART FOR MYOCARDIAL INFARCTION

Wayne P. Franco, 79 Two Stone Dr., Wethersfield, Conn. 06109
Filed Jun. 30, 1980, Ser. No. 164,074

Int. Cl.³ A61K 35/55

U.S. Cl. 424—108

13 Claims

1. A method of treating an area in the heart of a patient subjected to ischemic heart disease, to maintain viability in that area for a sustained time period to salvage said area, said method comprising applying an effective dose of FGF to the heart.

4,296,101

ANTIBIOTIC KRISTENIN


Frank L. Weisenborn, Titusville; William E. Brown, Princeton, and Edward Meyers, East Brunswick, all of N.J., assignors to E. R. Squibb & Sons, Inc., Princeton, N.J.

Filed Feb. 13, 1978, Ser. No. 877,199

Int. Cl.³ A61K 35/00; C12P 13/00, 1/04; C12R 1/125

U.S. Cl. 424—119

4 Claims



1. The antibiotic kristenin having the infrared spectrum in KBr 3350, 2950, 1660, 1620, 1525, 1455, 1225, 1160, 1110, 805 and 690 cm⁻¹ shown in the FIGURE, the ultraviolet spectrum in methanol λ_{max} 210 nm (27100), 247 nm (6090), 314 nm (4200), [α]_D^{methanol} -81.9°, and the approximate elemental analysis C, 56.58, H, 6.90, and N, 9.92.

4,296,102

METHOD OF COMBATING AMEBIASIS IN HUMANS

Felipe Laso, Montecito 59, Mexico City, Mexico

Filed Jun. 12, 1980, Ser. No. 158,649

Int. Cl.³ A61K 33/40, 33/22, 33/20

U.S. Cl. 424—130

4 Claims

1. The method of combating amebiasis in a human suffering from amebiasis, comprising orally administering to said human, an amount effective to combat said amebiasis, of a perborate stabilized aqueous solution of chlorine oxides formed by adding to 1000 cc of water the following:

- 80-120 grams sodium chlorite
- 90-130 grams sodium hypochlorite (13% aqueous solution)
- 5-7.5 cc of 37.7% hydrochloric acid
- 2-4.5 cc of 98.15% sulfuric acid
- 4-12 grams of an inorganic perborate selected from the group consisting of sodium perborate and potassium perborate, and
- 8-15 grams of sodium peroxide or an equivalent amount of potassium peroxide, hydrogen peroxide, potassium percarbonate, or sodium percarbonate.

4,296,103

STABILIZED SOLUTION OF CHLORINE OXIDES

Felipe Laso, Montecito 59, Mexico City DF, Mexico

Filed Aug. 8, 1980, Ser. No. 176,278

Int. Cl.³ A61K 33/40, 33/22, 33/20, 33/02

U.S. Cl. 424—130

7 Claims

1. A stabilized orally administrable aqueous therapeutic solution of chlorine oxides containing boron prepared by the addition to 1000 parts by weight of water the following:

- 80-120 parts by weight of sodium chlorite;
- 90-130 parts by weight of a 13% aqueous solution of sodium hypochlorite;

5-10 cc of 37.7% hydrochloric acid;
2-4.5 cc of 98.15% sulfuric acid;
4-15 parts by weight of an inorganic perborate selected from sodium perborate or potassium perborate; and
8-15 parts by weight of sodium peroxide.

4,296,104

THERAPEUTIC DIMETHYL SULFOXIDE COMPOSITION AND METHODS OF USE

Robert J. Herschler, 3080 NW. 8th St., Camas, Wash. 98607


Filed Aug. 30, 1979, Ser. No. 71,072

Int. Cl.³ A61K 31/10, 31/17, 33/14

U.S. Cl. 424—153

8 Claims

1. In a method for administering dimethyl sulfoxide to a host, the improvement comprising reducing the side effects of malodorous breath and skin reactions normally associated with such dimethyl sulfoxide administration, comprising the step of: administering to said host a composition comprising dimethyl sulfoxide and a side-effect reducing agent taken from the group consisting of urea, or ethanol or mixtures thereof in an amount which is effective for said purpose.



istamycin B of the formula

4,296,105

DERIVATIVES OF DOXORUBICINE, THEIR PREPARATION AND USE

Roger M. Baurain, Kraainem, and Andre B. L. Trouet, Winksele, both of Belgium, assignors to Institut International de Pathologie Cellulaire et Moléculaire, Brussels, Belgium

Filed Jul. 5, 1979, Ser. No. 55,291


Claims priority, application Belgium, Aug. 3, 1978, 869485

Int. Cl.³ A61K 31/71; C07H 15/24

U.S. Cl. 424—180


7 Claims

1. Derivatives of doxorubicine selected from the group consisting of a compound of the formula



wherein R is D—, L— and DL-leucyl and the acid addition salts thereof.

5. A veterinary composition, which contains an antitumoral effective amount of N-leucyl-doxorubicine or an acid addition salt thereof together with one or more compatible and pharmaceutically acceptable diluents or additives.



istamycin A of the formula

4,296,106

ISTAMYCINS AND PRODUCTION THEREOF

Hamao Umezawa; Yoshiro Okami, both of Tokyo, and Shinichi Kondo, Yokohama, all of Japan, assignors to Zaidan Hojin Biseibutsu Kagaku Kenkyu Kai, Tokyo, Japan

Filed Apr. 18, 1980, Ser. No. 141,492


Claims priority, application Japan, May 1, 1979, 54/52517; Sep. 17, 1979, 54/117912

Int. Cl.³ A61K 31/71; C07H 15/22


U.S. Cl. 424—181

7 Claims

1. The new compound, istamycin, which is selected from istamycin A of the formula



and istamycin B of the formula



and mixtures thereof, or a nontoxic pharmaceutically acceptable acid-addition salt thereof.

7. A method for inhibiting bacterial growth in an animal susceptible to said bacterial growth which comprises administering to said animal an antibacterially effective amount of at least one of istamycin A, istamycin B and nontoxic pharmaceutically acceptable acid-addition salts thereof.

4,296,107

MILDIOMYCIN ANALOGS AND A METHOD OF PRODUCTION

Takashi Suzuki, Takatsuki; Hidekazu Sawada, Neyagawa, and Kazuyoshi Katamoto, Suita, all of Japan, assignors to Takeda Chemical Industries, Ltd., Osaka, Japan

Filed Aug. 19, 1980, Ser. No. 179,555


Claims priority, application Japan, Aug. 24, 1979, 54-108330

Int. Cl.³ A61K 31/70; C07H 17/00

U.S. Cl. 424-180


10 Claims

1. A compound of the formula:




wherein R is hydrogen, a halogen atom or a lower alkyl group, or an acid salt thereof.

8. A process for producing a compound of the formula:




wherein R' is hydrogen, a halogen atom, a lower alkyl group or a hydroxymethyl group, or an acid salt thereof, which comprises cultivating a mildiomycin-microorganism belonging

to the genus Streptovercillium in a culture medium containing a compound of the formula:



wherein R' has the same meaning as above, or an acid salt thereof to have said compound elaborated and accumulated in the culture broth.

10. A plant fungicidal and acaricidal composition which comprises a fungicidally or acaricidally effective amount of a compound of the formula



wherein R is hydrogen, a halogen atom or a lower alkyl group, or an acid salt thereof and a carrier therefor.

4,296,108

2,2-DICHLOROCYCLOPROPYL-METHYL-PHOSPHORIC ACID DERIVATIVES

Rainer Bürstinghaus, Weinheim-Lützelbach; Karl Kiehs, Lampertheim, and Heinrich Adolph, Limburgerhof, all of Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Fed. Rep. of Germany

Filed Jul. 7, 1980, Ser. No. 166,573


Claims priority, application Fed. Rep. of Germany, Aug. 24, 1979, 2934229

Int. Cl.³ C07F 9/09, 9/165; C01N 57/04

U.S. Cl. 424-210

6 Claims

1. 2,2-Dichlorocyclopropyl-methyl-phosphoric acid derivatives of the formula



where

R¹, R² and R³ are identical or different and are hydrogen or methyl,

R⁴ is unbranched or branched alkoxy of up to 4 carbon atoms, unbranched or branched alkylthio of up to 4 carbon atoms, amino, or alkylamino or dialkylamino, wherein each alkyl is of up to 5 carbon atoms and is linear or branched,

Y is oxygen or sulfur and

X¹, X², X³ and X⁴ are identical or different and each is hydrogen, halogen, nitro, cyano, methyl or methylthio.

6. A process for combating pests, wherein an effective

amount of a 2,2-dichlorocyclopropyl-methyl-phosphoric acid derivative of the formula I as claimed in claim 1 is allowed to act on the pests or their habitat.

4,296,109

CORTICOID 21-SULFOPROPIONATES AND THE SALTS THEREOF, A PROCESS FOR THE PRODUCTION THEREOF AND PHARMACEUTICAL PREPARATIONS THEREOF

Henry Laurent; Peter Esperling; Joachim-Friedrich Kapp, and Rudolf Wiechert, all of Berlin, Fed. Rep. of Germany, assignors to Schering, Aktiengesellschaft, Berlin and Bergkamen, Fed. Rep. of Germany

Filed Oct. 9, 1979, Ser. No. 81,947


Claims priority, application Fed. Rep. of Germany, Oct. 4, 1978, 2843690; Aug. 6, 1979, 2032166

Int. Cl.³ A61K 31/56

U.S. Cl. 424-241

28 Claims

1. A corticoid 21-sulfopropionate of the formula



wherein


represents a single of double bond;

X is hydrogen, chlorine, fluorine or methyl;

Y is hydrogen, fluorine or chlorine;

Z is oxo, or hydrogen in the α-position and hydroxy in the β-position;

—U—V represents —CH₂—CH₂—, —CH=CH— or



wherein R₁ is hydrogen, hydroxy or acyloxy, wherein the acyl group is derived from a C₁₋₈ hydrocarbon carboxylic acid; R₂ is hydrogen or methyl; and R₃ and R₄ are independently each alkyl of 1-4 carbon atoms; and the salts thereof with physiologically acceptable bases.

28. A method of treating shock which comprises administering to a patient suffering from shock an amount of a compound of claim 1 effective for treatment of shock.

4,296,110

ANTIHYPERTENSIVE 1-SUBSTITUTED CYCLIC LACTAM-2-CARBOXYLIC ACIDS

Alexander L. Johnson, Wilmington, Del., assignor to E. I. Du Pont de Nemours and Company, Wilmington, Del.


Filed Oct. 28, 1980, Ser. No. 201,471

Int. Cl.³ A61K; C07D; A61K

U.S. Cl. 424-244

11 Claims


1. A compound of the formula:



where

R and R₃ are independently OH, C₁-C₄ alkoxy or benzoyloxy;

R₁ is H, CH₃, C₂H₅, CF₃, isobutyl, isoamyl, —(CH₂)_nNHR₅ or



R₂ is H or CH₃;

R₄ is C₁-C₁₀ alkyl, —(CH₂)_qC₆H₅ or —(CH₂)_nNH₂;

R₅ is H or C₁-C₄ alkyl;

m is 2, 3 or 4;

n is an integer from 1-6;

p is an integer from 1-6;

q is an integer from 0-6; and

r is an integer from 1-6;

and pharmaceutically acceptable salts thereof.

11. A method of treating hypertension in mammals which comprises administering to the mammal an effective hypertensive amount of a compound of claims 1 to 9.

4,296,111

7-SUBSTITUTED METHYL CEPHALOSPORINS DERIVATIVES AND ANALOGUES THEREOF

Thomas R. Beattie; Burton G. Christensen, both of Scotch Plains, and Frank P. Dinunno, Old Bridge, all of N.J., assignors to Merck & Co. Inc., Rahway, N.J.


Continuation-in-part of Ser. No. 815,475, Jul. 14, 1977, abandoned, which is a continuation of Ser. No. 634,082, Nov. 21, 1975, abandoned. This application Jun. 14, 1979, Ser. No. 48,551

Int. Cl.³ C07D 501/00

U.S. Cl. 424-246

3 Claims

1. A compound having the structural formula:



and the non-toxic, pharmaceutically acceptable salts thereof; wherein:

the dotted line indicates provision for both Δ² and Δ³ embodiments:

A is S and SO;

R³ is hydrogen, methoxy, and lower alkylthio;

X is OH, SH, NH₂, =O and =NH;

R¹ and R² are independently selected from the group consisting of hydrogen, lower alkyl, benzyl, phenethyl, 2-thienylmethyl, and phenyl;

R⁵ is hydrogen, chloro, lower alkoxy, formyl and —(CH₂)_nY wherein n is an integer from 1-6 and Y is

hydrogen, hydroxy, halogen, lower alkanoyloxy, lower alkanoylthio, lower alkoxy, phenoxy, benzyloxy, azido, amino, N-lower alkylamino, N,N-dilower alkylamino, N-lower alkanoylamino, N,N-dilower alkanoylamino, carbamoyl or thiocarbamoyl and the N-lower alkyl or N,N-dilower alkyl derivatives thereof, pyridinium, 3-methylpyridinium, 4-methylpyridinium, 3-chloropyridinium, 3-bromopyridinium, 3-iodopyridinium, 4-carbamoylpyridinium, 4-(N-hydroxymethylcarbamoyl)pyridinium, 4-(N-carbomethoxycarbamoyl)pyridinium, 4-(N-cyanocarbamoyl)pyridinium, 4-(carboxymethyl)pyridinium, 4-(hydroxymethyl)pyridinium, 4-(tri-fluoromethyl)pyridinium, quinolinium, and luthidinium; with the proviso that, when X is =O or =NH, one of R¹ and R² is absent, and that not all of R¹, R², R³ and R⁵ are hydrogen at the same time.

4,296,112

CEPHALOSPORINS

Akira Matsubara, Yokohama; Hideaki Sakai, Fujisawa; Makoto Odate, Yokohama; Toshio Suganuma, Mobara, and Takuo Nakano, Yokohama, all of Japan, assignors to Mitsui Toatsu Chemicals, Inc., Tokyo, Japan

Filed Dec. 17, 1979, Ser. No. 104,292


Claims priority, application Japan, Apr. 19, 1979, 54/47275

Int. Cl.³ C07D 501/20

U.S. Cl. 424-246

6 Claims

1. A cephalosporanic acid of the formula



and pharmaceutically acceptable salts and esters thereof.

4,296,113

MERCAPTOACYL DERIVATIVES OF KETO SUBSTITUTED PROLINE AND PIPECOLIC ACID

Miguel A. Ondetti, Princeton, N.J., assignor to E. R. Squibb & Sons, Inc., Princeton, N.J.


Filed Jan. 14, 1980, Ser. No. 112,004

Int. Cl.³ A61K 31/40, 31/44; C07D 207/16, 401/12

U.S. Cl. 424-246

20 Claims

1. A compound of the formula




or a physiologically acceptable salt thereof, wherein

R is hydrogen or lower alkyl;


R₁ and R₃ are independently selected from the group consisting of hydrogen, lower alkyl, lower alkylthio, -(CH₂)_n-SH, and halo substituted lower alkyl;R₂ is hydrogen or lower alkyl provided that R₂ is lower alkyl only when R₁ is lower alkyl;

m is zero, one or two;



n is one, two, or three;

R₄ is hydrogen,

p-methoxybenzyl, trityl, or provided that neither R₁ nor R₃ is -(CH₂)_n-SH




R₅ is lower alkyl, chloro, bromo or fluoro substituted lower alkyl, -(CH₂)_n-cycloalkyl wherein the cycloalkyl group is a saturated ring of 3 to 7 carbons,



r is zero, one, two, or three;

R₆ is hydrogen, lower alkyl of 1 to 4 carbons, lower alkoxy of 1 to 4 carbons, lower alkylthio of 1 to 4 carbons, chloro, bromo, fluoro, trifluoromethyl or hydroxy; and X is oxygen or sulfur.

16. A composition useful for treating hypertension comprising a pharmaceutically acceptable carrier and an effective amount of one or more hypotensive agents or physiologically acceptable salts thereof of the formula



wherein



R is hydrogen or lower alkyl;

R₁ and R₃ are independently selected from the group consisting of hydrogen, lower alkyl, lower alkylthio, -(CH₂)_n-SH, and halo substituted lower alkyl;



R₂ is hydrogen or lower alkyl provided that R₂ is lower alkyl only when R₁ is lower alkyl;

m is zero, one, or two;

n is one, two, or three;

R₄ is hydrogen,or provided that neither R₁ nor R₃ is -(CH₂)_n-SH

R₅ is lower alkyl, chloro, bromo, or fluoro substituted lower alkyl, -(CH₂)_n-cycloalkyl wherein the cycloalkyl group is a saturated ring of 3 to 7 carbons,



r is zero, one, two, or three;

R₆ is hydrogen, lower alkyl of 1 to 4 carbons, lower alkoxy of 1 to 4 carbons, lower alkylthio of 1 to 4 carbons, chloro, bromo, fluoro, trifluoromethyl, or hydroxy; and X is oxygen or sulfur.

20. The method of alleviating hypertension which comprises administering an effective amount of the composition of claim 16.

4,296,114

3,4-DIHYDRO-3-OXOPYRIDO[2,3-B]-PYRAZINES, COMPOSITIONS AND USE THEREOF

Richard A. Appleton, and David Johnston, both of Loughborough, England, assignors to Fisons Limited, London, England

Filed Aug. 2, 1979, Ser. No. 63,357


Claims priority, application United Kingdom, Aug. 15, 1978, 33431/78; Dec. 13, 1978, 48438/78

Int. Cl.³ A61K 31/495, 31/535; C07D 471/08

U.S. Cl. 424-248.52

10 Claims

1. A compound of formula I,



in which R₁ is phenyl substituted by halogen, alkoxy, alkyl, carboxy-alkyl, -NR₄R₅, carboxy or alkoxy carbonyl,

R₃ is hydrogen, alkyl, mono- or di-carboxy alkyl, halo, alkoxy, phenyl, halo-phenyl, hydroxy, phenoxy, thiol, thioalkoxy, thiophenoxy, -NR₄R₅, cyano, -COOH, carboxyureido, -CF₃, -COR₆, hydroxyalkyl, aminoalkyl, or alkoxy substituted by NR₄R₅,

ring A is a pyridine ring which optionally carries up to 4 substituents R₃, which may be the same or different,

R₄ and R₅, which may be the same or different, each represent hydrogen, phenyl, halophenyl or alkyl, the alkyl optionally being substituted by alkoxy or by a mono- or di-alkyl or unsubstituted amino group; or R₄ and R₅, together with the nitrogen atom to which they are attached, form a piperidine, morpholine or an optionally alkyl substituted piperazine ring, and

R₆ is hydrogen or alkyl,each of R₃ and any substituent on ring A or on the R₁ phenyl

group, when they contain carbon, containing up to and including 10 carbon atoms, provided that when R₁ is phenyl substituted by methoxy, R₃ is not phenyl,

or a pharmaceutically acceptable salt, ester or amide thereof.

9. A pharmaceutical composition for treatment of an inflammatory condition comprising an effective amount of a compound according to claim 1, as active ingredient, in admixture with a pharmaceutically acceptable adjuvant, diluent or carrier.

4,296,115

PYRIDYLALKYLAMINES

Leslie J. Browne, Morristown, N.J., assignor to Ciba-Geigy Corporation, Ardsley, N.Y.


Filed May 1, 1980, Ser. No. 145,533

Int. Cl.³ C07D 213/36; A61K 31/44

U.S. Cl. 424-263

8 Claims

1. A secondary hydroxypyridylalkylamine of the formula



wherein one of R₁, R₂ and R₄ is hydroxy, and the others, as well as R₃, are hydrogen or lower alkyl; m is an integer from 2 to 4; and n is an integer from 1 to 7; or a pharmaceutically acceptable acid addition salt thereof.

4,296,116

FUNGICIDAL AGENTS, PROCESSES FOR THEIR PREPARATION AND THEIR USE FOR COMBATING FUNGI

Helmut Kaspers, Leverkusen, and Wilhelm Brandes, Leichlingen, both of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Oct. 26, 1979, Ser. No. 88,688


Claims priority, application Fed. Rep. of Germany, Nov. 16, 1978, 2849695; Jul. 31, 1979, 2931034

Int. Cl.³ A01N 43/76, 41/06, 43/80, 43/50

U.S. Cl. 424-272

9 Claims


1. A fungicidal composition comprising a fungicidally effective amount of (1) at least one carboximide of the formula




in which

Y represents a bifunctional group linking the two carbonyl groups with formation of an optionally substituted 5-membered heterocyclic ring with a total of 1 or 2 hetero-atoms (O and N),

and (2),



-continued



the weight ratio of component (1) to component (2) ranging from about 1:1 to 1:4.

4,296,117

1-ARYLOXY-2-HYDROXY-3-[(BENZIMIDAZOLINONE-SUBSTITUTED ALKYL)-AMINO]PROPANES AND SALTS THEREOF

Herbert Kuppe, Ingelheim am Rhein; Anton Mentrup, Mainz-Kastel; Ernst-Otto Renth; Kurt Schromm, both of Ingelheim am Rhein; Wolfgang Hoeske, Budenheim, and Gorko Mucovic, Ingelheim am Rhein, all of Fed. Rep. of Germany, assignors to Boehringer Ingelheim GmbH, Ingelheim am Rhein, Fed. Rep. of Germany

Division of Ser. No. 4,279, Jan. 17, 1979, Pat. No. 4,256,756, which is a continuation-in-part of Ser. No. 838,450, Oct. 3, 1977, abandoned. This application Jan. 16, 1980, Ser. No. 112,640


Claims priority, application Fed. Rep. of Germany, Oct. 5, 1976, 2644833

Int. Cl.³ A61K 31/415; C07D 235/26

U.S. Cl. 424-273 B

7 Claims

1. A compound of the formula



wherein


R₁ is hydrogen; halogen; trifluoromethyl; nitro; alkyl of 1 to 8 carbon atoms; alkoxy of 1 to 4 carbon atoms; alkoxyalkyl of 2 to 8 carbon atoms; alkenyl of 2 to 5 carbon atoms; alkynyl of 2 to 5 carbon atoms; alkenyloxy of 3 to 6 carbon atoms; alkynyloxy of 3 to 6 carbon atoms; -(CH₂)_x-A', where x is 1, 2 or 3 and A' is cyano, amino, carboxamido or hydroxyl; phenoxy; benzyloxy; or -CH₂-SO₂-CH₃;

R₂ is hydrogen; halogen; alkyl of 1 to 4 carbon atoms; alkoxy of 1 to 4 carbon atoms; aralkoxy of 7 to 14 carbon atoms; alkenyl of 2 to 4 carbon atoms; nitro; or, together with R₃, -CH=CH-CH=CH-, which is attached to carbon atoms of the phenyl ring in o-position with respect to each other;

R₃ is hydrogen; halogen; alkyl of 1 to 4 carbon atoms; alkoxy of 1 to 4 carbon atoms; or aralkoxy of 7 to 14 carbon atoms; R₄ is hydrogen; alkyl of 1 to 5 carbon atoms; or aralkyl of 7 to 14 carbon atoms;

R₅ is

where B is

where R₁₂ is aryl;

D is alkylene of 1 to 12 carbon atoms; and

A is lower alkanoyl,

or a non-toxic, pharmacologically acceptable acid addition salt thereof.

3. The method of blocking the α- and β-adrenergic receptors in a warm-blooded animal in need thereof, which comprises perorally, parenterally or rectally administering to said animal an effective amount of a compound of claim 1.

4,296,118

FUNGICIDAL

3-[N-(PYRAZOL-1-YL-ACETYL)-N-(SUBSTITUTED PHENYL)]-AMINO-TETRAHYDRO-2-FURANONES

Walter Kunz, Oberwil, Switzerland; Wolfgang Eckhardt, Lörrach, Fed. Rep. of Germany, and Adolf Hubele, Magden, Switzerland, assignors to Ciba-Geigy Corporation, Ardsley, N.Y.

Division of Ser. No. 2,490, Jan. 11, 1979, abandoned, which is a division of Ser. No. 873,585, Jan. 30, 1978, Pat. No. 4,147,792.

This application Aug. 22, 1980, Ser. No. 180,266


Claims priority, application Switzerland, Feb. 4, 1977, 1381/77; Mar. 28, 1977, 3884/77

Int. Cl.³ A01N 43/56, 43/08; C07D 405/12

U.S. Cl. 424-273 P

4 Claims

1. A compound of the formula I



wherein

R represents C₁-C₄-alkyl, C₁-C₄-alkoxy or halogen,R₁ represents C₁-C₃-alkyl, C₁-C₄-alkoxy or halogen,R₂ represents hydrogen, C₁-C₃-alkyl, C₁-C₄-alkoxy or halogen,R₃ represents hydrogen or methyl, with the total number of C atoms of the substituents R, R₁, R₂ and R₃ in the phenyl ring not exceeding the number 8, andR₄ represents hydrogen or methyl,

4. A fungicidal composition containing as active substance a fungicidally effective amount of a compound according to claim 1 or 2, together with a suitable inert carrier therefor.

4,296,119

PROCESS AND COMPOSITION FOR REDUCING BLOOD PRESSURE IN ANIMALS

Richard J. Wurtman, Waban, Mass., assignor to Massachusetts Institute of Technology, Cambridge, Mass.

Continuation-in-part of Ser. No. 898,740, Apr. 24, 1978, abandoned. This application Nov. 27, 1978, Ser. No. 963,857

Int. Cl.³ A61K 31/40

U.S. Cl. 424-274

2 Claims

1. The process for reducing blood pressure in an animal afflicted with high blood pressure which comprises administering to said animal tryptophan to the animal in an amount effective to reduce blood pressure of at least about 5 mg/kg body weight.

4,296,120

(CARBOXY-OXO-PYRROLIDINO)PHENYLALKENAMIDES AND ESTERS THEREOF AS SRS-A ANTAGONISTS

Saul B. Kadin, New London, Conn., assignor to Pfizer Inc., New York, N.Y.


Filed Aug. 28, 1980, Ser. No. 182,162

Int. Cl.³ A61K 31/40; C07D 207/277

U.S. Cl. 424-274

21 Claims

1. An alkenamide compound of the formula




and a pharmaceutically-acceptable salt thereof;

wherein R¹ is selected from the group consisting of hydrogen, alkyl having 1 to 4 carbons and -CH₂-CH₂-NR³R⁴, wherein R³ and R⁴ are each alkyl having 1 to 3 carbons;

R² is selected from the group consisting of alkyl having 8 to 15 carbons and cycloalkyl having from 6 to 12 carbons; and R⁵ and R⁶ are selected from the group consisting of hydrogen and methyl.

11. A method for antagonizing the effect of slow-reacting substance of anaphylaxis in a human subject, which comprises administering to said subject a slow-reacting substance of anaphylaxis antagonizing amount of an alkenamide compound of the formula



or a pharmaceutically-acceptable salt thereof;

wherein R¹ is selected from the group consisting of hydrogen, alkyl having 1 to 4 carbons and -CH₂-CH₂-NR³R⁴, wherein R³ and R⁴ are each alkyl having 1 to 3 carbons;

R² is selected from the group consisting of alkyl having 8 to 15 carbons and cycloalkyl having from 6 to 12 carbons; and R⁵ and R⁶ are selected from the group consisting of hydrogen and methyl.

4,296,121

NOVEL PROSTAGLANDIN DERIVATIVES OF THE Δ2-PGF₂ AND Δ2-PGE₂ SERIES AND PROCESS FOR THEIR MANUFACTURE

Wilhelm Bartmann, Bad Soden am Taunus; Gerhard Beck, Frankfurt am Main; Ulrich Lerch, Hofheim am Taunus, and Elmar Konz, Bad Soden am Taunus, all of Fed. Rep. of Germany, assignors to Hoechst Aktiengesellschaft, Frankfurt am Main, Fed. Rep. of Germany

Filed Aug. 2, 1979, Ser. No. 62,937

Claims priority, application Fed. Rep. of Germany, Aug. 4, 1978, 2834248


Int. Cl.³ C07D 333/24; A61K 31/557; C07D 307/54; C07C

177/00

U.S. Cl. 424-275

7 Claims

1. A compound of the formula



wherein:

X¹ and Y¹ taken alone are different and are hydrogen or hydroxy, or taken together are oxygen;

R¹ is

(a) hydrogen or linear or branched, saturated or unsaturated, aliphatic or cycloaliphatic hydrocarbon having up to 10 carbon atoms, or is

(b) a physiologically acceptable metal ion, an NH₄⁺ ion, or an ammonium ion derived from a primary, secondary, or tertiary amine;

R² is linear or branched alkyl having 1 to 7 carbon atoms substituted with

(a) α- or β-thienyl or furyl, which thienyl or furyl in turn may be mono-, di-, or tri-substituted in the nucleus with at least one member selected from the group consisting of halogen, trifluoromethyl, alkyl having 1 to 6 carbon atoms, and alkoxy having 1 to 6 carbon atoms, or

(b) α- or β-thienyloxy or such thienyloxy mono-, di-, or tri-substituted in the nucleus with at least one member selected from the group consisting of halogen, trifluoromethyl, alkyl having 1 to 6 carbon atoms, and alkoxy having 1 to 6 carbon atoms; and

R³ is hydrogen, 1-ethoxyethyl, tetrahydropyran-2-yl, or tetrahydrofuran-2-yl, or is such tetrahydropyran-2-yl or tetrahydrofuran-2-yl mono- or poly-substituted by alkyl.

4,296,122

2,3-DIHYDRO-6,7-DISUBSTITUTED-5-(ACYL)BENZOFURAN-2-CARBOXYLIC ACIDS

Edward J. Cragoe, Jr., Lansdale, and Otto W. Woltersdorf, Jr., Chalfont, both of Pa., assignors to Merck & Co., Inc., Rahway, N.J.


Division of Ser. No. 678,529, Apr. 20, 1976, Pat. No. 4,087,542, which is a continuation-in-part of Ser. No. 594,839, Jul. 9, 1975, abandoned. This application Jan. 27, 1978, Ser. No. 873,024

Int. Cl.³ A61K 31/34; C07D 307/77

U.S. Cl. 424-285


13 Claims

1. A compound having the formula:




wherein R⁷ and R⁸ are each selected from the group consisting of hydrogen and methyl.

26. The method of antagonizing the effect of slow-reacting substance of anaphylaxis in a human subject, which comprises administering thereto a slow-reacting substance of anaphylaxis antagonizing amount of an alkenamide compound of the formula




or a pharmaceutically-acceptable salt thereof; wherein R¹ is selected from the group consisting of hydrogen, alkyl having 1 to 4 carbons, and —CH₂—CH₂—NR³R⁴, wherein R³ and R⁴ are each alkyl having 1 to 3 carbons;

R² is selected from the group consisting of alkyl having 8 to 15 carbons and cycloalkyl having from 6 to 12 carbons; R⁵ and R⁶ are selected from the group consisting of hydrogen and methyl; and X is selected from the group consisting of cis-vinylene, ethylene and




wherein R⁷ and R⁸ are each selected from the group consisting of hydrogen and methyl.

27. A pharmaceutical composition, which comprises a pharmaceutically-acceptable carrier and an alkenamide compound of the formula



or a pharmaceutically-acceptable salt thereof; wherein R¹ is selected from the group consisting of hydrogen, alkyl having 1 to 4 carbons, and —CH₂—CH₂—NR³R⁴, wherein R³ and R⁴ are each alkyl having 1 to 3 carbons;

R² is selected from the group consisting of alkyl having 8 to 15 carbons and cycloalkyl having from 6 to 12 carbons; R⁵ and R⁶ are selected from the group consisting of hydrogen and methyl; and X is selected from the group consisting of cis-vinylene, ethylene and



wherein R⁷ and R⁸ are each selected from the group consisting of hydrogen and methyl; and wherein the ratio of the pharmaceutically-acceptable carrier to the alkenamide compound is in the range from 1:6 to 6:1 by weight.

4,296,130

METHYLSULFONYLMETHANE AND METHODS OF USE

Robert J. Herschler, 3080 NW. 8th St., Camas, Wash. 98607
Filed Aug. 30, 1979, Ser. No. 71,068
Int. Cl.³ A61K 31/10

U.S. Cl. 424—337

2 Claims

1. A method of extending the blood supply of a warm blooded animal which method comprises: intravenously introducing into the blood of said warm blooded animal requiring such treatment a blood diluent comprising an aqueous solution of methylsulfonylmethane, present in an amount of about 0.1–50 weight percent.

4,296,131

PHARMACEUTICAL COMPOSITIONS AND THEIR USE IN THE PROPHYLAXIS AND/OR TREATMENT OF CERTAIN DISEASES

Cornelis A. Ladage, De Meern; Douwe J. Van Linge, Eemnes, and Huibert A. Van Riessen, Lunteren, all of Netherlands, assignors to ACF Chemiefarma N.V., Maarssen, Netherlands
Division of Ser. No. 3,968, Jan. 16, 1979, Pat. No. 4,250,089.
This application Aug. 10, 1979, Ser. No. 65,627
Claims priority, application Netherlands, Jan. 20, 1978, 7800762

Int. Cl.² A61K 31/055, 47/00

U.S. Cl. 424—347

8 Claims

1. A pharmaceutical composition for the treatment of distomatosis, comprising an amount, effective against distomatosis, of a member selected from the group consisting of 4,4'-dichloro-6,6'-dinitro-o,o'-bisphenol; 4,4',6,6'-tetrabromo-o,o'-bisphenol; 4,6'-dichloro-4,6'-dinitro-2,2'-methylenediphenol; and 6-bromo-4'-fluoro-4,6'-dinitro-2,2'-methylenediphenol, dissolved in a solvent vehicle comprising 5 to 50 w/v percent of dimethylsulfoxide (DMSO) in combination with a symmetric or unsymmetric ester of adipic acid wherein both alkyl groups together contain six to twelve carbon atoms and wherein the smaller alkyl group present if said ester is unsymmetric contains at least two carbon atoms.

4,296,132

DOG FOOD OF IMPROVED ACCEPTABILITY

Charles R. Lazarus, Ossining; Howard D. Stahl, Hartsdale, both of N.Y., and Gerhard J. Haas, Woodcliff Lake, N.J., assignors to General Foods Corporation, White Plains, N.Y.
Filed Mar. 13, 1980, Ser. No. 129,875
Int. Cl.³ A23K 1/00, 1/18

U.S. Cl. 426—2

9 Claims

1. An improved, nutritionally-balanced dog food comprising fat, protein, carbohydrates, vitamins and minerals wherein the improvement consists of magnesium oleate in admixture with at least a portion of the fat, the magnesium oleate being present in an amount effective to improve the palatability of the dog food for dogs.

4,296,133

METHOD FOR PRODUCING BREAD

Kenji Tanaka, Kawagoe, and Shigeru Endo, Tokyo, both of Japan, assignors to Nisshin Flour Milling Co., Ltd., Tokyo, Japan

Filed Aug. 24, 1979, Ser. No. 70,321

Int. Cl.³ A21D 2/08, 8/02

U.S. Cl. 426—23

13 Claims

1. A method for producing bread which comprises kneading

4,296,136

COCONUT POWDER

Salvatore F. Zicarelli, Downers Grove; Rey C. Ramos, and Robert M. Brown, both of Chicago, Ill., assignors to Beatrice Foods Company, Chicago, Ill.
Filed Feb. 1, 1980, Ser. No. 117,797
Int. Cl.³ A23L 1/221

U.S. Cl. 426—533

23 Claims

1. A process for producing reconstitutable natural coconut flavor comprising:

- (1) grinding coconut meat to an average particle size of 2000 microns or less and until a pulp containing coconut flavor liquor is obtained;
 - (2) separating the coconut flavor liquor from the coconut meat fiber wherein the separated liquor has no more than 2% fiber therein;
 - (3) deactivating enzymes in the flavor liquor by heating the flavor liquor at a temperature and for a time within enzyme deactivation conditions, whereby enzymes in the liquor are deactivated; and
 - (4) concentrating the deactivated liquor to a concentrated form by at least one step selected from (a) condensing the liquor to more than 25% solids, or (b) spray-drying the liquor to a free-flowing powder;
- whereby a concentrated coconut flavor is obtained.

4,296,134

LIQUID EGG BLEND

Wayne A. Boldt, S. 66 W20230 Tans Dr., Muskego, Wis. 53150
Continuation of Ser. No. 569,607, Apr. 21, 1975, abandoned, which is a continuation-in-part of Ser. No. 469,476, May 13, 1974, abandoned. This application Mar. 8, 1977, Ser. No. 786,301

Int. Cl.³ A23L 1/32

U.S. Cl. 426—250

30 Claims

1. A substantially fat-, oil-, cholesterol- and yolk-free fresh egg product with a maximum of 80 calories per 100 grams, a protein concentration of from 7.5 to 19 percent by weight and a maximum water content of about 1.3 times that found in fresh egg whites and which comprises from 60 to 96 parts by weight of liquid natural egg whites, zero to 18 parts by weight of added water, 2.0 to 10.5 parts by weight of egg-yolk-protein replacement, whereby said protein replacement with said natural egg whites provide combined protein-containing essential amino acids in approximately the same respective proportions as they occur in fresh whole eggs, 0.2 to 0.95 part by weight of stabilizer, 0.1 to 2.5 parts by weight of flavoring and 0.01 to 0.20 part by weight of coloring, which blend is useful, without reconstitution, for preparing scrambled eggs or omelets in the same manner as employed for whole fresh eggs and wherein said egg product, after doubler-boiler cooking, has a syneresis value of less than about 4 percent.


4,296,135

METHOD OF FORMING A LAYER OF PRE-DETERMINED THICKNESS FROM A FEEDSTOCK OF BUTTER OR MARGARINE

Jacques P. Rutten, Tilburg, Netherlands, assignor to Machinefabriek C. Rijkaart B.V., Asperen, Netherlands
Filed Jun. 6, 1979, Ser. No. 45,999
Int. Cl.³ A21D 13/00; A23C 15/00

U.S. Cl. 426—275

7 Claims



1. A method of forming a layer of a desired thickness of a substance which is butter or margarine, from a feedstock of said substance of any shape characterized by repeatedly scraping off an amount from said feedstock and by subsequently severing a portion of the desired thickness from said amount, after which the portions are joined in order of succession to form the desired layer.

4,296,137

FLAVORING WITH 1-ETHOXY-1-ETHANOL ACETATE


Richard M. Boden, Monmouth Beach, N.J., assignor to International Flavors & Fragrances Inc., New York, N.Y.
Filed Aug. 7, 1980, Ser. No. 176,111

Int. Cl.³ A23L 1/226, 1/235

U.S. Cl. 426—534

3 Claims

1. A process for augmenting or enhancing the aroma or taste of a consumable material selected from the group consisting of foodstuff and chewing gum, comprising the step of adding to said consumable material from 0.05 p.p.m. up to about 500 p.p.m. of 1-ethoxy-1-ethanol acetate having the structure:



4,296,138


FLAVORING WITH 1-N-BUTOXY-1-ETHANOL ACETATE

Richard M. Boden, Monmouth Beach, N.J., assignor to International Flavors & Fragrances Inc., New York, N.Y.
Continuation-in-part of Ser. No. 176,111, Aug. 7, 1980. This application Dec. 18, 1980, Ser. No. 217,810
Int. Cl.³ A23L 1/226

U.S. Cl. 426—534

3 Claims

1. A process for augmenting or enhancing the aroma or taste of a consumable material selected from the group consisting of foodstuff and chewing gum, comprising the step of adding to said consumable material from 0.05 p.p.m. up to about 500 p.p.m. of 1-n-butoxy-1-ethanol acetate having the structure:



4,296,139

BITTERING AGENTS

Riaz A. Khan, Sonning, and Michael R. Jenner, Pangbourne, both of England, assignors to Talres Development (N.A.) N.V., Curacao, Netherlands Antilles

Filed Oct. 17, 1979, Ser. No. 85,402

Claims priority, application United Kingdom, Oct. 18, 1978, 41115/78

Int. Cl.³ A23L 1/226, 2/00, 2/02

U.S. Cl. 426—536

8 Claims

1. In a method of bittering a substance by incorporating therein an effective amount of a bittering agent, the improvement which comprises employing 2,6,1',6'-tetrachloro-2,6,1',6'-tetraideoxymannosucrose as said bittering agent.

4,296,140

MOLDED GELLED PIMIENTO BODY

Jack B. Jaquith, Modesto, and Allen R. Church, Madera, both of Calif., assignors to Tri/Valley Growers, San Francisco, Calif.

Continuation-in-part of Ser. No. 775,556, Mar. 8, 1977, abandoned, and Ser. No. 946,115, Sep. 27, 1978, abandoned. This application May 27, 1980, Ser. No. 153,220

Int. Cl.³ A23L 1/04

U.S. Cl. 426—575

10 Claims

1. A molded gelled body produced by gelling a composition in calcium chloride, the composition comprising a mixture of macerated pimiento flesh, a water soluble alginate, at least one of the substances starch and a vegetable gum, and an acid, said pimiento flesh constituting the major ingredient by weight, the alginate being present in quantity such that upon cooling and subjecting said mixture to contact with the aqueous calcium chloride solution it will quickly gel the mixture, the starch or gum being present in quantity sufficient to result in a gel which can be manipulated without structural damage and the acid being present in quantity sufficient to provide a pH not exceeding about 4.5, and wherein the molded gelled body is characterized by dimensional stability such that after storage for two days in a brine containing 7% sodium chloride, 0.5% lactic acid and 500 to 1000 ppm calcium chloride it exhibits substantially no change in shape and dimensions.

4,296,141

CONCHLESS HIGH PROTEIN CHOCOLATE FLAVORED COMPOSITION AND METHOD OF MAKING SAME

Potito U. de Paolis, 131 Groverton Pl., Los Angeles, Calif. 90024

Filed Aug. 27, 1979, Ser. No. 69,857

Int. Cl.³ A23G 1/00; A23D 5/00

U.S. Cl. 426—613

8 Claims

1. A method of making a conchless chocolate composition which comprises:

initially admixing at least the following ingredients:

- 5-40 parts, by weight, edible fats;
- 40-70 parts, by weight, sweetener selected from the group consisting of a sugar and a sugar substitute;
- 2-60 parts, by weight, flavoring selected from the group consisting of cocoa powder and carob powder; and

(d) 3-40 parts, by weight, of soya protein isolate; to form a viscous paste;

admixing with said viscous paste additional edible fats to form a liquified admixture having a total fat content of between 10-65 parts, by weight;

heating said liquid admixture to a temperature of between about 110° F. and 140° F. for a period of time of between about 10 and 30 minutes, under agitation; and

cooling said heated liquified admixture to form said conchless chocolate product wherein said soya protein isolate acts as essentially the sole emulsifying agent for the said conchless chocolate composition.

4,296,142

METHOD FOR COATING A TUBULAR FOOD CASING


Ganapathy Vasudevan, Bolingbrook, and Stanley Lustig, Park Forest, both of Ill., assignors to Union Carbide Corporation, New York, N.Y.

Continuation of Ser. No. 919,067, Jun. 26, 1978, abandoned. This application Nov. 13, 1979, Ser. No. 93,434

Int. Cl.³ B05D 1/06

U.S. Cl. 427—28

17 Claims



1. A continuous process for forming a pin-hole free layer on the exterior surface of a flexible tubular cellulosic food casing, comprising the steps of:

- establishing a path for processing said food casing;
- providing two sets of pinch rollers at spaced apart locations along said path so that said food casing can move through said set of pinch rollers continuously while being maintained in a pinched state;
- maintaining an inflated section of said food casing in tension between said sets of pinch rollers;
- electrostatically coating a portion of said food casing section with dry particles of a resinous polymeric material having an average particle size of less than 125 microns to establish a coating having a thickness of at least about 0.5 mil;
- moving said food casing along said path so that the coated portion of said food casing moves to a location for sintering between said sets of pinch rollers; and
- sintering said coated portion to form said layer.

4,296,143

METHOD OF PRODUCING MICROLENSES

Adrianus J. J. Franken; Giok D. Khoe, both of Eindhoven, Netherlands, and Dieter Küppers, Aachen, Fed. Rep. of Germany, assignors to U.S. Philips Corporation, New York, N.Y.


Filed Oct. 5, 1979, Ser. No. 82,394

Claims priority, application Fed. Rep. of Germany, Apr. 6, 1979, 2913843

Int. Cl.³ G02B 1/10, 3/00; C03C 17/02

U.S. Cl. 427—38

6 Claims



1. A method of producing microlenses embedded in a glass plate, characterized in that rotation-symmetrical recesses are produced in a glass plate, whereafter vitreous layers are depos-

ited on the plate by means of a vapour deposition process until the recesses are fully filled up, whereafter the thickness of the coated glass plate is reduced to the original value or to a lower value.

4,296,144

ION IMPLANTED SYLUS

Edward W. Maby, Plainsboro; Hirohisa Kawamoto, Princeton, and Pierre V. Valembos, Cranbury, all of N.J., assignors to RCA Corporation, New York, N.Y.

Filed Apr. 23, 1980, Ser. No. 142,982

Int. Cl.³ C23C 11/00

U.S. Cl. 427—38

8 Claims

1. In a method for fabricating a playback stylus which comprises a diamond dielectric support element for use with a capacitive information system including a high density information conductive disc which comprises the steps of forming a bottom surface for contacting the disc and preparing a conductive layer adjacent to the bottom surface by ion implanting a portion of the diamond dielectric support element; the improvement comprising the additional step of annealing the ion implanted diamond at from about 850° to about 1500° C.

4,296,145

METHOD FOR COATING ONE SIDE ONLY OF STEEL STRIP WITH MOLTEN COATING METAL

Seizun Higuchi, Kitakyushu; Kazuhiro Tano, Nakama; Minoru Kamada, and Susumu Okamoto, both of Kitakyushu, all of Japan, assignors to Nippon Steel Corporation, Tokyo, Japan


Filed Dec. 28, 1979, Ser. No. 108,154

Claims priority, application Japan, Dec. 30, 1978, 53/165280

Int. Cl.³ B05C 3/18; C23C 1/02

U.S. Cl. 427—47

11 Claims



1. In a method of continuously coating one side only of a steel strip with a molten coating metal including the steps of:

- (1) passing the steel strip to be coated substantially horizontally above a bath of the molten coating metal, with guide rolls imposing longitudinal tension thereon, through a chamber containing a molten metal coating bath, the chamber being filled with a nonoxidizing atmosphere,
- (2) forcing the molten coating metal via an electromagnetic pump up from a submerged inlet of an adjacent molten metal guide to an outlet opening positioned above the molten coating metal bath surface forming a rising stream of the coating metal on the exit side of the outlet, and
- (3) contacting the rising metal stream with the bottom surface of the substantially flat steel strip to be coated,

the improvement comprising positively flowing the molten coating metal toward both edges of the substantially horizontal flat strip by passing the molten metal through the metal guide outlet offering less flow resistance to the rising molten metal stream on the exit side of the guide outlet along the width thereof and offering greater flow resistance to the rising molten metal along the length thereof with respect to the running strip, thus positively forcing the flow of molten metal out to both edges of the substantially horizontal, flat strip; and thereby forming a uniform layer of the coating metal on the bottom side of the strip thus contacted with the metal while preventing the coating metal from flowing over to the opposite non-coated side of the steel strip.

4,296,146

METHOD FOR REMOVING RESIST LAYER FROM SUBSTRATE WITH COMBUSTIBLE GAS BURNOFF

Thomas C. Penn, Richardson, Tex., assignor to Texas Instruments Incorporated, Dallas, Tex.

Filed Dec. 2, 1977, Ser. No. 856,900

Int. Cl.³ B05D 5/12

U.S. Cl. 427—58

16 Claims

1. In the fabrication of an electronic structure including a layer of semiconductor material and at least one electronic device formed thereon, wherein a patterned layer of resist material is disposed on a surface of different material than the resist material, a method of removing the patterned layer of resist material from the surface of different material, said method comprising:

- decomposing resist material via chemical reaction from said layer of resist material by exposing said layer of resist material to the flame of a combustible gas, wherein the flame contains resist-attacking reactive products;
- retaining the structure including the surface of different material in a condition, which is essentially unaltered physically and chemically with respect to its condition prior to the exposure of the layer of resist material to the flame of the combustible gas, during the decomposition of resist material; and
- discontinuing the exposure of the structure to the flame of the combustible gas when only said layer of resist material has been removed by decomposition of the resist material thereof while the structure including the surface of different material remains in its unaltered condition.

4,296,147

THALLOUS HALIDE MATERIALS FOR USE IN CRYOGENIC APPLICATIONS


William N. Lawless, 518 Illinois Ct., Westerville, Ohio 43081, assignor to William Nicholas Lawless, Westerville, Ohio

Filed May 21, 1979, Ser. No. 41,039

Int. Cl.³ D02G 3/00

U.S. Cl. 427—120

6 Claims



1. A structured, ceramic, dielectric, heat exchange material for use in cryogenic applications having a specific heat equal to or greater than that of lead at temperatures below about 20° K. comprising a mixture of components X and Y, where X is selected from the group consisting of thallous fluoride, thallous chloride, thallous bromide, and thallous iodide, and where Y is selected from the group consisting of thallous fluoride; thallous chloride; thallous bromide; thallous iodide; epoxy resin; AB₂O₄, where A is a Group IIB metal ion with or without other divalent metal ions and B is chromium ion with or without other trivalent metal ions; AB₂O₆, where A is manganese or nickel ion or both, with

or without other divalent metal ions and B is niobium, tantalum, or both; and A_2BCO_6 , where A is lead ion with or without other divalent metal ions, B is gadolinium or manganese with or without other trivalent metal ions, and C is niobium, tantalum, or both, with the proviso that X and Y cannot be the same compound.

4,296,148

METHOD TO APPLY MULTIPLE LAYERS, INCLUDING AN ELECTRODE LAYER, ON A SINTERED OR PRE-SINTERED ION CONDUCTIVE SOLID ELECTROLYTE BODY

Karl-Hermann Friese, Leonberg, Fed. Rep. of Germany, assignor to Robert Bosch GmbH, Stuttgart, Fed. Rep. of Germany


Filed Nov. 29, 1979, Ser. No. 98,602

Claims priority, application Fed. Rep. of Germany, Dec. 6, 1978, 2852647

Int. Cl.³ B05D 5/12

U.S. Cl. 427—125

24 Claims



1. Method of making a solid electrolyte ion conductive gas sensing element having

- a solid ion conductive electrolyte body (1) having two surface portions, one of which is adapted for exposure to the gas to be sensed
 - a layer of electrode material (2) on one surface portion of the body;
 - a layer of electrode material on the second surface portion of the body;
 - a cover layer of porous ceramic material on the layer of electrode material on said one surface portion of the body; and
 - a cover layer of porous ceramic material on the layer of electrode material on said second surface portion of the body,
- comprising the steps of
- providing a pre-sintered ion conductive solid electrolyte body having said two surface portions,
 - applying a layer of the electrode material on one surface portion of said body;
 - applying a layer of the electrode material on the second surface portion of said body;
 - applying a cover layer of ceramic material which, when sintered, becomes porous, on the layer of electrode material on one surface portion of said body;
 - applying a cover layer of ceramic material which, when sintered, becomes porous on the layer of electrode material on the second surface portion of said body; and
 - then in one step, sintering the electrode layers and the cover layers, by heating the body with the electrode layers and the cover layers applied thereon to a temperature in which the sintering process of the electrode layers at least commences and the ion conductive body and the cover layer are completely sintered.

4,296,149

MANUFACTURE OF ACICULAR COBALT-CONTAINING MAGNETIC IRON OXIDE

Peter Rudolf, Neuhausen; Werner Steck, Mutterstadt; Helmut Jakusch, Frankenthal; Guenter Vaeth, Limburgerhof, and Christof Jaech, Heidelberg, all of Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Fed. Rep. of Germany

Filed Jan. 29, 1980, Ser. No. 116,552

Claims priority, application Fed. Rep. of Germany, Feb. 13, 1979, 2905351

Int. Cl.³ C01G 49/06

U.S. Cl. 427—130

1 Claim

1. A process for the manufacture of acicular, magnetic iron oxide consisting of a core of gamma-iron(III) oxide surrounded by a ferrite shell which contains, based on the amount of magnetic material, from 0.2 to 12 percent by weight of cobalt(II) ions and from 0.1 to 15 percent by weight of iron(II) ions, which process comprises: suspending acicular gamma-iron(III) oxide in water, adding to said suspension an aqueous solution containing cobalt(II) ions, followed by the addition of an aqueous base to bring the pH to not less than 10, both additions being made at room temperature, thereafter introducing an aqueous solution containing iron(II) ions under an inert gas atmosphere, with continued stirring, and after the cobalt(II) hydroxide and iron(II) hydroxide has precipitated under the inert gas atmosphere, the solid product is filtered off, washed neutral with water and heated at from 100° to 200° C. for from one to seven hours, the steps of stirring, precipitating and filtering all taking place at room temperature.

4,296,150

TRANSPARENT IMAGE MARKING SHEET FOR PROJECTION SYSTEMS

Norbert Mecke; Franz U. Schmitt; Karl-Heinz Schrader, and Heinke Blutschkau, all of Hanover, Fed. Rep. of Germany, assignors to Pelikan A.G., Hanover, Fed. Rep. of Germany

Filed Apr. 1, 1980, Ser. No. 136,397

Claims priority, application Fed. Rep. of Germany, Mar. 26, 1979, 2911798

Int. Cl.³ B05D 3/10, 5/06; G02B 1/10

U.S. Cl. 427—164

12 Claims

1. A transparent image sheet carrier for overhead-projection systems based upon a dark-tone colored field with image markings in bright-tone contrasting colors, comprising a sheet bearing a layer containing at least one acid-resistant dye for imparting said dark-tone color to said field, said dye being dischargeable in the locale of said image markings by discharge means with a simultaneous appearance in said image locale of said bright-tone contrasting color.

9. A method of preparing acid-resistant transparent image bearing sheets for overhead projection systems based upon bright-colored images upon a contrasting dark-tone colored field, which comprises the steps of:

- providing a transparent substrate sheet bearing a dark-tone color field layer, said color being based upon a dischargeable transparent dark tone dye, and
- forming localized images on said field by the application to said image locale of a discharge agent to locally discharge said field dye with the simultaneous appearance in said discharged image locale of the bright-colored contrasting image.

4,296,151

FLUORINATED POLYMERIC SURFACES

Harold D. Boultinghouse, Bartlesville, Okla., assignor to Phillips Petroleum Company, Bartlesville, Okla.

Division of Ser. No. 968,713, Dec. 12, 1978, abandoned. This application Jun. 12, 1980, Ser. No. 158,768

Int. Cl.³ B05D 3/00, 3/12

U.S. Cl. 427—255.1

10 Claims

1. A process for treating a polymeric surface formed from (1) normally solid polymers of aliphatic mono-1-olefins and (2)

elastomeric and resinous copolymers of conjugated dienes and vinyl-substituted aromatic compounds which comprises contacting said surface with a fluorine-containing gas under conditions and for a period of time sufficient to render said surface water-wettable and receptive to adherence of a second material selected from adhesives, coatings, paints, inks, decorations, and the like, and then contacting said surface with said second material under conditions which cause said second material to adhere to said fluorinated surface.

4,296,152

METHOD AND COMPOSITION FOR TREATING WOOD WITH PENTACHLOROPHENOL

Roy P. Kirchner, Tallahassee, Fla., assignor to Iacon, Inc., Houston, Tex.

Filed May 8, 1980, Ser. No. 135,992

Int. Cl.³ C09D 5/16, 5/18; B05D 1/18, 3/00

U.S. Cl. 427—440

2 Claims

1. A method of impregnating wood with pentachlorophenol comprising the steps of preparing a solution of about 25 to 55 percent by weight of pentachlorophenol in an organic solvent comprising a petroleum fraction at least 50% of which will distill above 485° F., preparing a finely divided dispersion of the solution in water in which the pentachlorophenol content is from 0.1 to 10 percent by weight, and impregnating wood with the dispersion.

4,296,153

VACUUM CHAMBER DOOR ASSEMBLY AND METHOD


Gunard O. B. Mahl, San Francisco, Calif., assignor to CHA Industries, Menlo Park, Calif.

Filed May 15, 1978, Ser. No. 906,025

Int. Cl.³ B05D 3/00

U.S. Cl. 427—444

30 Claims



1. An apparatus comprising a cabinet defining a vacuum chamber therein, and a door assembly movably mounted on said cabinet to normally close an opening to said vacuum chamber, the improvement comprising mounting means mounting said door assembly on said cabinet (1) for initial pivotal movement between a closed position normally closing the opening to said vacuum chamber and an open position pivoted outwardly away from said vacuum chamber for fully exposing said opening, and (2) for further movement, following and independent of said pivotal movement, to a position remote from said opening.

22. A method for loading and unloading a vacuum chamber defined in an apparatus with at least one article to be processed comprising the steps of

movably mounting a door assembly on said apparatus for

movement between closed and opened positions relative to said chamber, pivoting said door assembly away from said chamber, moving said door assembly vertically downwardly to a remote, lowered position vertically below said chamber, placing an article to be processed in said chamber, moving said door assembly vertically upwardly to a raised position, and pivoting said door assembly inwardly into closed and sealed relationship with respect to said chamber.

4,296,154

STRIP BRICK FACING MATERIAL


Robert B. Ibberson, Gingerbread Hill, Arlington, Vt. 05250

Filed Feb. 8, 1980, Ser. No. 120,004

Int. Cl.³ B44F 9/04

U.S. Cl. 428—15

3 Claims



1. A simulated brick facing for application to a supporting member including individual strips, each simulating a layer of brick, at least one longitudinal groove along at least one side of each strip simulating the horizontal, recessed mortar layer between layers of brick, transverse grooves simulating vertical, recessed mortar bonds between side-by-side bricks, said grooves defining raised lands simulating the visible faces of individual bricks, side walls of both said longitudinal and transverse grooves being entirely substantially perpendicular to the lands and the groove bottoms and being entirely free of any undercuts therein into the body of the simulated bricks, said individual strips having planar undersurfaces adapted to be applied one above the other to the supporting member to represent a brick structure.

4,296,155

OVERCOATED DECORATIVE MOULDING


Ciro N. Madonia, 1390 Beaufort Dr., Burlington, Ontario; Christopher Hatzikelis, R.R. 1, Palgrave, Ontario, and Cesare C. Cosentino, 45 Grandview Ave., Thornhill, Ontario, all of Canada

Filed Oct. 16, 1979, Ser. No. 85,276

Int. Cl.³ B32B 3/02, 31/30

U.S. Cl. 428—31

6 Claims



1. An elongated decorative moulding for protecting vehicle bodies from minor impacts, said decorative moulding comprising:

- (a) an extruded strip of pliable material having a symmetrical lens shaped cross section with substantially flat first surface and an impact-absorbing outwardly convex second surface spanning said first surface;
- (b) adhesive means carried by said first surface and adapted to fasten said first surface to a vehicle body;
- (c) a decorative strip having two major surfaces and two

4,296,161

DRY-FORMED NONWOVEN FABRIC

Paul H. Kaiser, Glenolden; Rudolf Neuenschwander, Swarthmore, both of Pa., and Henry J. Norton, Wilmington, Del., assignors to Scott Paper Company, Philadelphia, Pa.
Continuation of Ser. No. 93,526, Nov. 13, 1979, abandoned. This application Sep. 26, 1980, Ser. No. 191,235
Int. Cl.³ B32B 5/14

U.S. Cl. 428—171

13 Claims

1. A dry-formed nonwoven fibrous web including a fiber composition which is at least 50%, by weight, wood pulp fibers less than about 0.635 cm ($\frac{1}{4}$ inch) in length with 25% or more of the fiber composition in the web, by weight, being kraft wood pulp fibers, and under 50%, by weight, reinforcing fibers intermixed with the wood pulp fibers throughout the web structure; an embossment in the web providing a plurality of compressed, densified valley regions and less-dense high loft regions, said web including no more than about 5.1 g/m² (3.0 lbs per ream of 2,880 ft.²) of a binder and having a cross machine direction wet tensile strength of at least about 0.107 Kg/cm (0.6 lbs./inch).

- (2) a weight of 10 to 100 g/m²; and
(3) a fiber density (Fd) of 3 to 100, in which the fiber density (Fd) is calculated in accordance with the following equation:

$$Fd = \frac{1}{a+b} \quad (1)$$

wherein a is the number of fibers which cross a straight line formed by connecting two arbitrary points 2 mm apart from each other on the plane of the sheet-like mesh structure (A), and b is the number of fibers which cross a straight line formed by connecting two arbitrary points 2 mm apart from each other on a straight line at right angles to the straight line referred to above with regard to the number of fibers (a); and

- (B) a mat, web- or sheet-like fibrous structure composed of short or long fibers, said fibrous structure having a recovery ratio after 10% stretch of less than 50% in at least one arbitrarily selected direction.


4,296,164

FIBROUS GLASS BLOWING INSULATION AND PROCESS

Richard S. Bemis, Granville, and Daniel A. McCartan, Heath, both of Ohio, assignors to Owens-Corning Fiberglas Corporation, Toledo, Ohio
Continuation of Ser. No. 52,518, Jun. 27, 1979, abandoned, which is a continuation-in-part of Ser. No. 930,946, Aug. 4, 1978, abandoned. This application Jul. 11, 1980, Ser. No. 168,954
Int. Cl.³ B32B 17/00

U.S. Cl. 428—219

21 Claims



1. Blowing insulation comprising fibrous glass prisms, approximate cubes, and flakes of various thicknesses, formed by delamination of columns at random upon handling, the columns having been cut from a generally laminated blanket of bonded glass fibers in such a manner that a maximum dimension of each column initially extends in the direction of a minimum dimension or thickness of the blanket, and the blowing insulation having a product of conductivity (k) and density (d) of less than 0.27 in a blown condition, where (k) is measured in terms of British thermal units/(hour)(square foot)(degree Fahrenheit/inch) at 75 degrees Fahrenheit mean temperature and (d) is measured in terms of pounds per cubic foot (less than 5.37 in a blown condition, where (k) is measured in terms of calories/(hour)(square centimeter)(degree Celsius/centimeter) at 24 degrees Celsius mean temperature and (d) is measured in terms of kilograms per cubic meter).

18. A continuous process of making blowing insulation comprising continuously forming glass fibers from molten glass, spraying the fibers with a thermosetting resin, continuously collecting the sprayed fibers on a moving conveyor to form a continuous generally laminated fibrous glass blanket, conveying the blanket through an oven to cure the binder, cutting the blanket longitudinally into a plurality of strips and cutting the strips generally transversely of but at an angle other

4,296,163

FIBROUS COMPOSITE HAVING ELASTICITY

Shingo Emi, and Noritsugu Saiki, both of Iwakuni, Japan, assignors to Teijin Limited, Osaka, Japan
Filed Jul. 20, 1979, Ser. No. 59,238
Claims priority, application Japan, Aug. 1, 1978, 53-93094; Jan. 16, 1979, 54-2165


Int. Cl.³ B32B 7/02

U.S. Cl. 428—212

10 Claims

1. A fibrous composite comprising a coalesced assembly of (A) a sheet-like mesh structure composed of fibers of a synthetic elastomeric polymer, the individual fibers being interconnected in irregular spaced-apart relationships thereby forming a number of meshes of different shapes and sizes, said mesh structure having

- (1) a recovery ratio after 10% stretch of at least 70% in two arbitrarily selected, mutually perpendicular directions on the plane of said mesh structure;



1. Flexible, unitary, multi-layer surface wallcovering material consisting of an outer layer of opaque vinyl having a thickness of 3 to 5 mils, a second layer of aluminum foil having a thickness of 0.00025 to 0.005 inches, a backing layer of material selected from the group consisting of paper, fabric, confill and scrim, and an adhesive layer between said first and second layers and said second and backing layers, wherein said adhesive is continuous and co-extensive with each adjacent layer such that said layers are laminated together to form a unitary composite structure.

4,296,167

COMPOSITIONS FOR USE IN SEAL COATS

Marcel Ceintrey, Anse de Kerjegu, 29120 Combrit, France
Continuation-in-part of Ser. No. 64,742, Aug. 8, 1979, abandoned. This application Mar. 10, 1980, Ser. No. 128,750
Claims priority, application France, Aug. 18, 1978, 78 24231
Int. Cl.³ B32B 7/00

U.S. Cl. 428—284

11 Claims

1. Seal coat for a structure comprising: (a) a binding layer deposited on said structure; and (b) a reinforcement layer comprising a non-woven material of synthetic fibres impregnated with a binder comprising a complex of a modified epoxy resin and a polyureide, which is the reaction product of a first component comprising a liquid epoxy resin and a blocked polyisocyanate prepolymer, with a second component comprising an aliphatic or cycloaliphatic polyamine, said binder covering the surface of said seal coat.


4,296,168

PADDING SHEET FORMED OF A MIXTURE OF FIBERS BONDED AT THEIR INTERSECTIONS

Jere B. Ambrose, 5645 Lakeshore, Holland, Mich. 48423
Filed Feb. 19, 1980, Ser. No. 122,134
Int. Cl.³ D04H 1/58

U.S. Cl. 428—288

1 Claim



1. In a relatively thick, dense, non-woven fiber matted padding formed of a mixture of hair-like fibers bonded together at their intersections, the improvement comprising: said fibers including cotton or other synthetic fibers and a minor proportion of a relatively low heat softening point thermo-plastic material which is shredded to provide fine fibers of thermo-plastic material, said fine fibers of thermo-plastic material randomly mixed within the over all mixture, said thermo-plastic fibers being formed of polypropylene, said polypropylene fibers being about 20-22 percent by weight compared with the total of the other fibers in the mixture; said thermo-plastic material fibers each being randomly oriented within the mixture and being bonded by moving the mixture through an elongated furnace at about 450°-525° F. for heat softening the thermo-plastic material fibers to the other fibers upon which they form overlapping contact, to thereby randomly bond the fibrous mixture together without a separate bonding additive, wherein the padding is substantially free of conventional bonding resins.

4,296,169

WALLBOARD HAVING IMPROVED DRYING RATE DUE TO PLURAL CONTACTING FIBER NETWORKS

Richard F. Shannon, Lancaster, Ohio, assignor to Owens-Corning Fiberglas Corporation, Toledo, Ohio
Filed Feb. 4, 1980, Ser. No. 118,332
Int. Cl.³ B32B 5/08, 5/12, 5/26, 13/02

U.S. Cl. 428—298

6 Claims

1. A board comprising: two sheets of paper spaced apart and bonded to a core of inorganic cementitious material, said core having a network of dispersed glass monofilaments jack-strawed into a three-dimensional water transmitting network extending between its surfaces, and at least one of said layers of paper having a network of dispersed glass monofilaments jack-strawed into a water transmitting network that extends

than a right angle to their longitudinal edges into columns in such a manner that a maximum dimension of each column initially extends in the direction of a minimum dimension or thickness of the blanket and the maximum dimension of each column is several times greater than either of two other dimensions measured at right angles to the maximum dimension, and delaminating the columns by subjecting them to further handling to effect the breaking up thereof at random into smaller prisms, approximate cubes, and flakes of various thicknesses.

4,296,165

ANTISTATIC NATURAL AND SYNTHETIC TEXTILE MATERIALS WHICH HAVE BEEN TREATED WITH SALTS OF ORTHOPHOSPHORIC OR POLYPHOSPHORIC ACID

Sarwan K. Kakar, Flat Rock; Frank R. Kappler, Wyandotte, and John J. Cramer, Grosse Ile, all of Mich., assignors to The Diversey Corporation, Northbrook, Ill.
Continuation of Ser. No. 899,130, Apr. 24, 1978, abandoned. This application Jul. 2, 1979, Ser. No. 53,824
Int. Cl.³ D06M 3/16, 5/00, 11/08

U.S. Cl. 428—264

11 Claims

1. An antistatic synthetic textile material or blend of natural and synthetic textile materials impregnated with an antistatic amount of an antistatic agent consisting essentially of at least one of

- (A) a neutral, ionically-bonded ammonium salt of an orthophosphoric acid,
(B) a neutral, ionically-bonded ammonium salt of a polyphosphoric acid,
(C) a neutral, ionically-bonded mixed ammonium and alkanolamine salt of orthophosphoric acid in which the alkanolamine is a 2 or 3 carbon atom alkanolamine or a mixture thereof and
(D) a neutral, ionically-bonded mixed ammonium and alkanolamine salt of polyphosphoric acid in which the alkanolamine is a 2 or 3 carbon atom alkanolamine or a mixture thereof.


4,296,166

AIR FILTER OF POLYURETHANE MESH CONTAINING CARBON ADSORBENT

Fumiichi Ogino, Kawanishi, Japan, assignor to Takeda Chemical Industries, Ltd., Osaka, Japan
Filed Sep. 25, 1979, Ser. No. 78,717
Claims priority, application Japan, Oct. 9, 1978, 53-124411
Int. Cl.³ B32B 5/16

U.S. Cl. 428—283

7 Claims



1. Air cleaning filter element which comprises at least two sheets of three dimensional mesh-structured elastic-flexible webs prepared by selective hydrolysis of a polyurethane foam having 3 mm to 10 mm thickness as superimposed, said webs containing 9 to 31 air spaces per 25 linear millimeters, and an activated carbon adsorbent having a BET specific surface area of 500 to 2000 m²/g and a grain size of 1 to 5 mm in diameter, said adsorbent being deposited in an amount between 200 and 2500 grams per square meter and bonded to and between the webs with an amount of adhesive agent.

between its major surfaces with said network in said paper being in water transmitting contact with said network of said core.

4,296,170

FIREPROOF LAMINATES

Takashi Ohashi, Iruma; Toru Okoyama, Sagami-hara, and Kat-suhiko Arai, Akigawa, all of Japan, assignors to Bridgestone Tire Company Limited, Tokyo, Japan

Filed Mar. 6, 1980, Ser. No. 127,669

Claims priority, application Japan, Mar. 6, 1979, 54/26042

Int. Cl.³ B32B 5/20

U.S. Cl. 428—313


11 Claims

1. A fireproof laminate comprising a urethane modified polyisocyanurate foam as a core material produced by reacting an organic polyisocyanate with a polyol in the presence of an isocyanate trimerization catalyst, a blowing agent and other additives, and a surface material piled on at least front surface of said core material, which comprises:

- (1) using an aluminum foil with a thickness of not less than 0.015 mm as a front surface material for said core material, said front surface material being united with said core material by self-adhesion of said foam;
- (2) using, as said polyol for the formation of said urethane modified polyisocyanurate foam, at least one low molecular weight diol (hereinafter referred to as A-group diol) selected from the group consisting of (a) compounds having the general formula



wherein n is 2, 3 or 4, (b) compounds having the general formula



wherein n is 2 or 3, (c) 2,3-butane diol and (d) 2-butene-1,4-diol together with at least one high molecular weight polyol (hereinafter referred to as B-group polyol) having 2 to 4 hydroxyl groups in its molecule and a hydroxyl equivalent of 600 to 2,000;

- (3) being a weight ratio of the sum of A-group diols to the sum of B-group polyols within a range of 0.55 to 7.0; and
- (4) being a total amount of A-group diols and B-group polyols used as said polyol within a range of 12.5 to 25 parts by weight per 100 parts by weight of said organic polyisocyanate.

4,296,171

TRANSFER SHEET SUITABLE FOR ELECTROPHOTOGRAPHIC PRESSURE-FIXING

Mitsuru Imai, Numazu, Japan, assignor to Ricoh Co., Ltd., Tokyo, Japan

Filed Sep. 6, 1979, Ser. No. 72,862

Claims priority, application Japan, Sep. 8, 1978, 53-109601

Int. Cl.³ B05D 5/12; B32B 5/16, 21/06, 27/10

U.S. Cl. 428—323

6 Claims

1. A transfer sheet adapted to have an electrophotographic image of dry toner affixed thereto by pressure, comprising: a paper support coated on at least one surface thereof with a transfer-accepting layer wherein the amount of said transfer-accepting layer is from 1 to 10 g per square meter of said paper support, on a dry basis, said transfer-accepting layer having been formed by applying on said paper support a coating of an aqueous solution or an aqueous dispersion of a resin obtained by neutralizing, with ammonia or volatile amine, the carboxyl groups of a copolymer consisting essentially of from 40 to 90% by weight of methyl methacrylate, from 3 to 60% by weight of acrylate selected from the group consisting of alkyl acrylate having 6 or more carbon atoms in the alkyl group, alkyl methacrylate having 6 or more carbon atoms in the alkyl group and

mixtures thereof, and from 0.5 to 10% by weight of unsaturated carboxylic acid, said resin being water-soluble or water-dispersible and having a gravimetric average molecular weight of from 5,000 to 100,000, and then drying said coating to form said transfer-accepting layer, said transfer-accepting layer having fine cracks on the surface thereof.

4,296,172

INK TRANSFER MEMBER

Edward D. Hill, 11212 Edgewater Dr., Cleveland, Ohio 44102

Filed Dec. 7, 1978, Ser. No. 967,130

Int. Cl.³ B32B 5/16

U.S. Cl. 428—331

11 Claims

1. A transfer member for ink, paint, and the like having an improved solvent-resistant, ink-contacting surface and substantially the same durometer rating throughout its useful life, said member comprising:

- (a) a polymerized, cross-linked polyurethane,
- (b) a sufficient amount of particulate silica dispersed in said polyurethane to assist in providing such solvent-resistance, said amount ranging from about 50 to about 250 parts of particulate silica per 100 parts of said polyurethane, and
- (c) a binding amount of a silane also dispersed in said polyurethane and having at least one reactive group reacted with at least said polyurethane to bind said polyurethane and particulate silica together,
- (d) said silane prior to reaction corresponding to the formula:



in which R may be halogen, amino, mercapto, vinyl, allyl, propenyl, isopropenyl, acrylic, methacrylic, ethylacrylic, butenyl, isobutenyl, vinylene benzene, propylene benzene, butylene benzene, and vinylene toluene; R' is hydrogen, methyl, ethyl, propyl, isopropyl, butyl, isobutyl, phenyl, benzyl, toluyl and xyl; X is methoxy, ethoxy, propoxy, butoxy, and acryloxy in which the acyl group is a hydrocarbon chain of a carboxylic acid having up to six carbon atoms; m is 1, 2, or 3; n is 0, 1, or 2; and p is 1, 2, or 3; the total of m, n and p always being 4.

4,296,173

GLASS FIBERS WITH REDUCED TENDENCY TO FORM GUMMING DEPOSITS AND SIZING COMPOSITION COMPRISING TWO STARCHES WITH DIFFERENT AMYLOSE CONTENT

Dennis M. Fahey, Lexington, N.C., assignor to PPG Industries, Inc., Pittsburgh, Pa.

Division of Ser. No. 75,069, Sep. 13, 1979, Pat. No. 4,259,190.

This application Sep. 8, 1980, Ser. No. 185,048

Int. Cl.³ B32B 17/00, 17/10; C03C 25/02

U.S. Cl. 428—378

2 Claims

1. An improved glass fiber strand having improved processibility and an improved strand package and having a reduced tendency to form gumming deposits on fabrication machinery under high relative humidity conditions having disposed on the glass fibers an amount from about 0.80 percent to about 2.5 percent by weight of the glass, the dried residue of an aqueous sizing composition comprising in weight percent of the non-aqueous components:

- (a) about 50 to about 75 percent by weight of a starch mixture having 75 to 95 weight percent of an underivatized high amylose starch component and 5 to about 25 weight percent of an easily cookable low amylose starch component;
- (b) 4 to 50 percent by weight of the salt of a polyamino-functional polyamide resin, said polyamino-functional polyamide resin salt being formed from the condensation reaction product of a polycarboxylic acid or carboxylic acid and a polyamine, wherein the polyamine has greater than two

amine groups per molecule and wherein the carboxylic acid has 1 to 5 carbon atoms;

- (c) 5 to 35 percent by weight of a wax selected from the group consisting of animal waxes, vegetable waxes, mineral waxes, synthetic waxes, and petroleum waxes;
 - (d) about 9 percent to about 77 percent by weight of a non-ionic lubricant with fatty triglycerides selected from the group consisting of hydrogenated vegetable oil;
 - (e) about 10 to about 45 percent by weight of an alkyl imidazoline;
 - (f) at least 0.01 part per part of wax and per part of nonionic lubricant of a mixture of sorbitan monostearate having an HLB of 4.7 and a polyoxyethylene (20) sorbitan monostearate having an HLB of 14.9 in a ratio to give an HLB of the mixture between about 8 and 12;
 - (g) about 1.5 to about 20 weight percent of gamma-methacryloxypropyltrimethoxysilane;
 - (h) about 0.1 to about 3 weight percent of a wetting agent; and
 - (i) about 0.5 to about 1 weight percent of an organotin bactericide.
2. Glass fiber reinforced polymer tape material having glass fiber strands of claim 1.

4,296,174

SPANDEX FILAMENTS CONTAINING CERTAIN METALLIC SOAPS


Robert S. Hanzel, Wilmington, Del., and Paul J. Sauer, Waynesboro, Va., assignors to E. I. Du Pont de Nemours and Company, Wilmington, Del.

Filed Aug. 8, 1980, Ser. No. 176,594

Int. Cl.³ D01F 6/70; D06M 11/04, 13/24; D02G 3/32

U.S. Cl. 428—389

6 Claims



1. An improved spandex filament of the type having a lubricating finish on its surface, the improvement comprising a soap dispersed within the filament in an amount equal to at least 0.3% by weight of the filament and being a metal salt of a fatty acid, the metal being selected from the group consisting of calcium, lithium and magnesium and the fatty acid being selected from the group consisting of saturated and unsaturated fatty acids having 10 to 22 carbon atoms.

3. The filament of claim 1 wherein the concentration of the soap dispersed within the filament is in the range of 0.5 to 1.0%.

4,296,175

HOLLOW ACRYLONITRILE POLYMER FIBER

Francesco De Maria, Gulf Breeze, and Ronald E. Pfeiffer, Pensacola, both of Fla., assignors to American Cyanamid Company, Stamford, Conn.

Continuation-in-part of Ser. No. 13,773, Feb. 21, 1979, abandoned. This application Mar. 24, 1980, Ser. No. 133,059

Int. Cl.³ D02G 3/00

U.S. Cl. 428—398

5 Claims

1. An acrylonitrile polymer fiber having a monolobal cross-sectional shape comprising (1) an inner hollow area extending uniformly throughout the entire fiber length and having a substantially fully opened cross-section and completely sur-

rounding said inner hollow area, (2) an outer solid polymer area having a uniform structure, said fiber being less than about 50 denier per filament and having suitable physical properties for textile uses and said acrylonitrile polymer being a hydrophilic polymer provided by adding a pre-formed polymer selected from the group consisting of polyvinyl alcohol, polyvinyl pyrrolidone, polyethylene oxide, polyacrylamide and polyacrylic acid to acrylonitrile and one or more monomers copolymerizable therewith in proportions which provide at least about 50 weight percent acrylonitrile and about 1 to about 10 weight percent of hydrophilic moieties in the resulting polymer.

4,296,176

INKS FOR PULSED ELECTRICAL PRINTING

Donald J. J. Lennon; John R. Hagerstrom, both of Acton, and C. Frederick W. Ekman, Bedford, all of Mass., assignors to EPP Corp., Boston, Mass.

Division of Ser. No. 710,282, Jul. 30, 1976, abandoned. This application Dec. 11, 1979, Ser. No. 102,569

Int. Cl.³ G03G 9/08

U.S. Cl. 428—407

3 Claims

1. A printing ink comprising particles each having a body of fusible resin with a colorant dispersed therein, said body being about two to ten microns in size, and an electrically conductive coating comprising a second resin with finely divided electrically conductive particles dispersed therein, said particles being in sufficiently close mutual proximity for continuous electrical conduction therebetween within said coating, said coating being substantially entirely situated on the surface of said body, adhering thereto, said printing ink having a volume resistivity of from 10 to 10³ ohm cm. measured at between one and two volts per cm.

4,296,177

FLEXIBLE GRAPHITE SHEET, MATERIAL OR LAYER CONTAINING METAL MOLYBDATE

Ernst Freundlinger, Meitingen-Langenreichen, and Alfred Hirschvogel, Langeweid, both of Fed. Rep. of Germany, assignors to Sigi Elektrographit GmbH, Meitingen bei Augsburg, Fed. Rep. of Germany

Filed Dec. 21, 1979, Ser. No. 106,167

Claims priority, application Fed. Rep. of Germany, Jan. 20, 1979, 2902252

Int. Cl.³ B32B 9/00

U.S. Cl. 428—408

7 Claims

1. Flexible graphite layer material containing a metal molybdate with a solubility in water of 10⁻² to 10⁻⁴ g/100 ml to inhibit corrosion.

4,296,178

ARTICLE COMPRISING A SUBSTRATE AND CHROMIUM ALLOY COATING

Neal M. Griesenauer, Grove City, and Julius J. Gersi, Worthington, both of Ohio, assignors to Varian Associates, Inc., Palo Alto, Calif.

Filed May 18, 1979, Ser. No. 40,356

Int. Cl.³ C23C 15/00

U.S. Cl. 428—462

10 Claims




1. An article comprising a substrate and a thin film metal

alloy coating formed on a surface of said substrate by a process of depositing small particles on said substrate, said metal alloy consisting of 78-97.5% by weight of chromium, at least two elements selected from the group consisting of molybdenum, nickel and cobalt in the combined proportion of 2-20% by weight, and 0.5-2% by weight of a scavenger element.

4,296,179

FRANGIBLE BONDING USING BLUSH LACQUER

Charles R. Wardwell, 559 Oak St., Winnetka, Ill. 60093
Division of Ser. No. 482,436, Jun. 24, 1974, Pat. No. 3,938,659.
This application Oct. 24, 1975, Ser. No. 625,506
Int. Cl.³ B32B 9/06; C09J 7/02; A61B 17/06
U.S. Cl. 428-498 3 Claims




1. A product with frangible bonding including the combination of a paper substrate having internal bonds bonding it together internally, and a frangible bonding system, said frangible bonding system comprising a bonding agent in the form of a dried blush lacquer bonded to said substrate by interlayer bonds, and heat seal material for bonding said blush lacquer to a surface, said heat seal material having internal bonds bonding it together internally and being bonded to said blush lacquer by interlayer bonds, said dried blush lacquer being formed of film-forming resin containing voids, the film-forming resin forming cohesive internal bonds of said blush lacquer, said voids making said cohesive internal bonds of said blush lacquer weaker than the internal bonds of said substrate and said heat seal material and the interlayer bonds between said blush lacquer and said substrate and between said blush lacquer and said heat seal material.

4,296,180

PROCESS FOR THE PRODUCTION OF METALLIC FORMED MEMBERS

Siegfried Rhau, Nuremberg, and Adolf Weber, Neunkirchen, both of Fed. Rep. of Germany, assignors to Diehl GmbH & Co., Fed. Rep. of Germany
Filed Nov. 19, 1979, Ser. No. 95,545
Claims priority, application Fed. Rep. of Germany, Dec. 6, 1978, 2852657
Int. Cl.³ B21B 00/00; F42B 13/48
U.S. Cl. 428-558 14 Claims



1. In a process for the production of a formed member, including discrete particles embedded in a metallic matrix, the improvement comprising: arranging said particles intermediate a metallic basic support member and a metallic outer casing; embedding said particles in said basic support member and said outer casing through round cold forging of said outer casing,


and having forging wedges which extend along and over all of said particles concurrently work over the full length of said outer casing in conformance with the length of the particle arrangement along the axial direction of said formed member during rotation of said formed member.

2. A formed member comprising discrete particles embedded in a metallic matrix including a metallic basic support member and a metallic outer casing, with said particles being embedded in said basic support member and in said outer casing.

4,296,181

PLATING METHOD AND STRUCTURE

Samuel A. Nehra, 12 Lake Shore La., Grosse Pointe Shores, Mich. 48236
Filed Jan. 16, 1980, Ser. No. 112,468
Int. Cl.³ C23C 7/00
U.S. Cl. 428-626 4 Claims




1. A plated article having a reactive surface constructed of one of plastic, resin, aluminum, steel and zinc, comprising a cleaned article surface, a flame sprayed tin zinc metal coating which is over 50% tin by weight and four or more mils thick adhering to the cleaned article surface and chrome metal plating over the sprayed metal surface including copper cyanide, bright copper, semi-bright nickel, bright nickel and chrome layers.

4,296,182

CAN COMPOSED OF ELECTROLYTICALLY CHROMATED STEEL

Hiroshi Matsubayashi, Kamakura; Michiko Tsurumaru, Tokyo; Makoto Horiguchi, Fujisawa; Hiroshi Ueno, Yokosuka, and Yoichi Kitamura, Yokohama, all of Japan, assignors to Toyo Seikan Kaisha Limited, Tokyo, Japan
Filed May 1, 1979, Ser. No. 35,333
Claims priority, application Japan, May 8, 1978, 53-53819; Dec. 13, 1978, 53-153202
Int. Cl.³ B65D 7/00; C25D 11/38; C23C 17/00; B32B 15/08
U.S. Cl. 428-629 4 Claims



1. A can at least a part of which is made of an electrolytically chromated steel sheet having a chromium-containing surface layer consisting of a layer of metallic chromium and a layer of chromium oxide, the thickness of the metallic chromium layer being from 20 to 300 mg/m² and the thickness of the chromium oxide layer being 5 to 50 mg/m² based on the amount of chro-

mium, said steel sheet having a surface such that when it is degreased in acetone for 1 minute and analyzed by an Auger electron spectrometer at an incident electron accelerating voltage of 3 KeV, a modulation voltage of 3 V, a modulation frequency of 12 to 20 KHz and a degree of vacuum of at least 6×10^{-8} torr, the ratio of the peak-peak distance (O_{P-P}) of $KL_{2,3}L_{2,3}$ of oxygen to the base-peak distance (Cr_{B-P}) of $L_{3}M_{2,3}M_{4,5}$ of chromium in the resulting Auger electron spectrum satisfies the following relation:
 $6.5 \geq (O_{P-P})/(Cr_{B-P}) \geq 1.5$.

4,296,183

AL-SN BASE BEARING ALLOY AND COMPOSITE

Keiiti Iwahana; Yoshimi Mathuda, and Kenichiro Futamura, all of Toyota, Japan, assignors to Taiho Kogyo Co., Ltd., Toyota, Japan
Filed Apr. 2, 1980, Ser. No. 136,638
Int. Cl.³ B32B 15/04 6 Claims

U.S. Cl. 428-653

1. An Al-Sn base bearing alloy consisting essentially of 3:5 to 25 wt.% of Sn; 0.1 to 1.0 wt.% of Cr; 0.5 to 9 wt.% in total of one or more members selected from the group consisting of Pb, Bi, In and Cd; and the remainder is Al.


3. A bearing material which is made by applying said bearing alloy as claimed in claim 1 to a backing steel sheet by pressure welding.

4,296,184

ELECTROCHEMICAL CELL

John Z. O. Stachurski, 220 Kaymar Dr., Amherst, N.Y. 14150
Filed Jan. 3, 1980, Ser. No. 109,241
Int. Cl.³ H01M 12/04 3 Claims

U.S. Cl. 429-14



1. A method of operating an electrochemical cell as a galvanic cell or as an electrolytic cell, said cell comprising a housing, a semipermeable membrane dividing the housing into two chambers, first and second, said first chamber containing protogenous ion-conducting liquid and a positive electrode, said second compartment containing an aprotic, ion-conducting liquid and also containing a negative electrode which corrodes when exposed to the protogenous liquid, said protogenous liquid being partly soluble in the aprotic liquid;
said method preventing the corrosive protogenous liquid from reaching said negative electrode, comprising the steps of
subdividing the second chamber by means of a porous partition into two compartments, one adjacent to said membrane, and the other containing the negative electrode;
flowing the aprotic liquid, free of the protogenous liquid, into the compartment containing the negative electrode;
flowing the aprotic liquid across the porous partition away from the negative electrode to prevent the protogenous

liquid present in the aprotic liquid from reaching the negative electrode;
flowing said aprotic liquid from the porous partition and between it and the semipermeable membrane and into the drying means, in order to remove the protogenous substance which gets into the aprotic liquid while it is in contact with the semipermeable membrane,
flowing aprotic liquid back to the negative electrode compartment.

4,296,185

COATING FOR LITHIUM ANODE, THIONYL CHLORIDE ACTIVE CATHODE ELECTROCHEMICAL CELL

Vincent O. Catanzarite, 7044 Mira Vista, Las Vegas, Nev. 89120
Continuation-in-part of Ser. No. 53,988, Jul. 2, 1979, abandoned, which is a continuation of Ser. No. 840,521, Oct. 11, 1977, Pat. No. 4,170,693. This application Apr. 25, 1980, Ser. No. 143,719
The portion of the term of this patent subsequent to Oct. 9, 1996, has been disclaimed.
Int. Cl.³ H01M 6/14 16 Claims


U.S. Cl. 429-48

1. An electrochemical cell comprising:
(a) a cathode current collector;
(b) an anode mechanically spaced from said cathode current collector;
(c) an ionically conductive electrolyte in physical contact with said anode and cathode current collector, said electrolyte consisting of a solute dissolved in a solvent that also performs the function of an active cathode depolarizer;
(d) a coating contiguous to said anode, said coating consisting of a compound in the cyanoacrylate family.

4,296,186

TWO PART PRESSURE RELIEF VALVE

Franz J. Wolf, Bad Soden-Salmunster, Fed. Rep. of Germany
Continuation of Ser. No. 715,463, Aug. 18, 1976, abandoned.
This application Jul. 13, 1979, Ser. No. 57,358
Int. Cl.³ B65D 51/16; F16K 15/14; H01M 2/12
U.S. Cl. 429-54 7 Claims



1. In combination, a sealing lid of plastic, a container subject to super-atmospheric internal pressure such as a capacitor or battery, said lid having a peripheral groove with elastomeric sealing material therein engaged by the container, said lid having a transverse opening therethrough, and a pressure relief valve molded directly in said opening comprising:

(a) a one piece valve housing of the same material as said sealing material, with the inner surface of the opening fitting firmly around the housing, the valve housing having an axial length substantially equal to the axial length of the opening, means defining a chamber in said housing including an annular valve seat, an axially opening conically upwardly flaring inlet communicating with said valve seat, an axially oriented outlet communicating with said chamber remote from said valve seat, and being eccentric relative to the axis of said valve seat, said chamber defining means comprising means defining a chamber surface conically outwardly flaring from said valve seat

and means defining wall means being formed in one piece with said means defining said flaring chamber surface and generally parallel to the plane of said valve seat and spaced therefrom,

- (b) a spherical valve body in said valve chamber engaging an imperforate portion of said wall means and being partially embedded in said wall means, and engaging said valve seat when said valve is closed,
- (c) said wall means being elastically strained when said valve is closed and forcing said valve body against said valve seat, and
- (d) means for preventing axial shifting of said valve housing relative to said lid comprising an inwardly directed collar intermediate the ends of said opening engaging an annular recess in the housing, the surface of the opening and collar fitting firmly around the housing.

4,296,187

INTEGRATED CARBON/INSULATOR STRUCTURE AND METHOD FOR FABRICATING SAME


John E. Barnes, Wakefield; Franz Goebel, Sudbury, and William T. McHugh, Westwood, all of Mass., assignors to GTE Products Corporation, Stamford, Conn.

Filed Jun. 13, 1980, Ser. No. 159,266

Int. Cl.³ H01M 6/14

U.S. Cl. 429—105

11 Claims



1. An integrated carbon/insulator structure for an electrochemical cell, comprising:
 - a porous substrate of an electrically-nonconductive material and having a predetermined thickness; and
 - a porous layer of a carbon material supported by the porous substrate, said layer of carbon material having a predetermined thickness and further having a portion thereof at its interface with the porous substrate permanently diffused into and interlocking with a portion of the porous substrate thereby to form an integrated structure with the porous substrate.
7. An electrochemical cell comprising:
 - a metal housing;
 - an electrochemical system within the metal housing and including an electrolytic solution and a battery stack exposed to said electrolytic solution, said battery stack comprising:
 - an anode; and
 - an integrated carbon/insulator structure adjacent to the anode, said integrated carbon/insulator structure comprising:
 - a porous substrate of an electrically-nonconductive material adjacent to the anode and having a predetermined thickness; and
 - a porous layer of a carbon material supported by the porous substrate, said layer of carbon material having a predetermined thickness and further having a portion thereof at its interface with the porous substrate permanently diffused into and interlocking with a portion of the porous substrate thereby to form an integrated structure with the porous substrate.

4,296,188

CD(SE,TE) ALLOY PHOTOVOLTAIC MATERIALS

Gary Hodes; David Cahen, and Joost Manassen, all of Rehovot, Israel, assignors to Yeda Research and Development Company Ltd., Rehovot, Israel

Filed Mar. 27, 1980, Ser. No. 134,665

Claims priority, application Israel, Jul. 7, 1979, 57908

Int. Cl.³ H01M 6/36

U.S. Cl. 429—111

8 Claims

2. A photoelectrochemical cell comprising a photoelectrode, an electrolyte, and a counterelectrode, said photoelectrode comprising a Cd(Se,Te) alloy comprising about 30 mole % to about 90% mole % CdSe and wherein said electrolyte comprises a S/S⁻ redox couple.

4,296,189

COLOR PICTURE TUBE HAVING IMPROVED SLIT TYPE SHADOW MASK AND METHOD OF MAKING SAME


Henry W. Kuzminski, Ephrata, Pa., assignor to RCA Corporation, New York, N.Y.

Division of Ser. No. 41,998, May 24, 1979. This application Nov. 17, 1980, Ser. No. 207,781

Int. Cl.³ G03C 5/00

U.S. Cl. 430—5

2 Claims



1. In a method of making a color picture tube having a slit type apertured mask, wherein the slit apertures are arranged in columns and the apertures in each column are separated by webs, said mask being formed by coating a metal sheet with a photosensitive material, exposing the photosensitive material through a photomaster having an apertured pattern thereon and thereafter etching the metal sheet to form apertures therein, the improvement comprising:
 - exposing said metal sheet through a photomaster having aperture images thereon which have greater width at the ends thereof than at the central portions of the aperture images,
 - whereby upon etching said metal sheet apertures are generated therein which are more nearly rectangular than are apertures formed in a mask which was exposed by a photomaster having rectangular aperture images.

4,296,190

PHOTOSENSITIVE MATERIAL FOR USE IN ELECTROPHOTOGRAPHY WITH A RADIATION CURED BINDER RESIN

Haruo Hasegawa; Hiroyoshi Taniguchi, and Takao Igawa, all of Tokyo, Japan, assignors to Ricoh Co., Ltd., Tokyo, Japan

Continuation of Ser. No. 809,795, Jun. 24, 1977, abandoned, which is a continuation of Ser. No. 627,544, Oct. 31, 1975, abandoned. This application Jun. 11, 1979, Ser. No. 47,229

Int. Cl.³ G03G 5/04

U.S. Cl. 430—57

14 Claims

1. An electrophotographic plate, comprising:
 - an electrically conductive substrate;
 - a first photoconductive layer coated over said substrate and having a thickness of from 0.1μ to 10μ, said first photoconductive layer consisting essentially of a mixture of an inorganic or organic first photoconductor and a resin that has been cured by ionizing radiation, said first photocon-

ductive layer having been prepared by applying onto said substrate a liquid dispersion or solution of said first photoconductor and from 0.2 to 50 percent by weight, based on the weight of said first photoconductor, of a radiation-curable resin selected from the group consisting of non-modified maleic anhydride-type unsaturated polyester, silicone-modified, urethane-modified or acrylic urethane-modified maleic anhydride-type unsaturated polyester, polyester having maleyl group therein, acrylic polymer having maleyl group therein, epoxide resin having maleyl group therein, acrylic polymer having acryloyl group as a side chain thereof, telomerized polyester acrylate, telomerized polyamide acrylate, epoxyacrylate, urethane acrylate, silicone acrylate, and reactive allyl group-containing resin, and then applying ionizing radiation to said first photoconductive layer, in a solvent-free state, until said radiation-curable resin has been cured; and

a second photoconductive layer coated over said first photoconductive layer and having a thickness of from 3μ to 50μ, said second photoconductive layer consisting essentially of an organic second photoconductor and a resin binder therefor, said second photoconductive layer having been prepared by applying a liquid dispersion or solution of said organic second photoconductor and said resin binder in an organic solvent onto said first photoconductive layer having said cured resin therein and then evaporating the solvent.

4,296,191

TWO-LAYERED PHOTORECEPTOR CONTAINING A SELENIUM-TELLURIUM LAYER AND AN ARSENIC-SELENIUM OVER LAYER


Richard L. Jacobson, Roseville, and Timothy T. Lin, Woodbury, both of Minn., assignors to Minnesota Mining and Manufacturing Company, St. Paul, Minn.

Filed Jun. 16, 1980, Ser. No. 159,878

Int. Cl.³ G03G 5/082

U.S. Cl. 430—57

14 Claims



1. A composite photoreceptor member including a support layer and only two layers of photoconductive materials, said two layers including:
 - a. a first layer of a vitreous selenium and tellurium composition carried on the support layer,
 - b. and a second layer comprising vitreous arsenic-selenium composition overlaying said layer of vitreous selenium-tellurium composition wherein said layer of selenium-tellurium composition is about 40 to 80 microns in thickness and said layer of arsenic-selenium composition is about 0.5 to 5.0 microns in thickness.

4,296,192

ELECTROSTATOGRAPHIC TONER COMPOSITION

Robert J. Gruber, Pittsford; Steven B. Bolte, Webster; John F. Knapp, Fairport; Dale R. Ims, Webster, and Richard B. Lewis, Williamson, all of N.Y., assignors to Xerox Corporation, Stamford, Conn.

Filed Jul. 2, 1979, Ser. No. 54,203

Int. Cl.³ G03G 9/00

U.S. Cl. 430—109

6 Claims

1. An improved electrostatographic toner composition comprising of a resin, and a colorant, the resin consisting essentially

4,296,193

PHOTOSENSITIVE POSITIVE DIAZO MATERIAL WITH COPOLYMER OF ACRYLAMIDE AND DIACETONEACRYLAMIDE AND A PROCESS FOR DEVELOPING TO FORM COLOR RELIEF IMAGE

Takeo Moriya, Kawagoe, and Toshio Yamagata, Urawa, both of Japan, assignors to Kimoto & Co., Ltd., Tokyo, Japan

Filed Jun. 20, 1980, Ser. No. 161,513

Claims priority, application Japan, Jan. 16, 1980, 55-3407

Int. Cl.³ G03C 1/60, 1/71, 1/74, 5/34

U.S. Cl. 430—149

7 Claims

1. A photosensitive material comprising a base material and a layer of a positive image forming, alkali developable photosensitive composition wherein, after exposure to light, the light exposed areas are removable by washing, and said layer is formed on said base material, said photosensitive composition comprising (A), 100 parts by weight of a water soluble resin binder containing at least 60 weight % of acrylamide-diacetoneacrylamide copolymer, the copolymerization of acrylamide to diacetoneacrylamide being 8:2-5:5 and the average polymerization degree being 300-1500, and (B), 5-20 parts by weight of a water-soluble, photosensitive diazonium salt.

4. A process for forming a color-developed positive relief image comprising: forming on a base material, a layer of a positive-image forming, alkali developable photosensitive composition comprising (A), 100 parts by weight of a water soluble resin binder containing at least 60 weight % of acrylamidediacetoneacrylamide copolymer, the polymerization ratio of acrylamide and diacetoneacrylamide being 8:2-5:5 and average polymerization degree being 300-1500, and (B), 5-20 parts by weight of a water-soluble, photosensitive diazonium salt;

exposing said photosensitive material to form an image thereon; and developing said exposed photosensitive material by contact with an alkali developer.

4,296,194

POSITIVE-WORKING LIGHT SENSITIVE DIAZO MATERIALS WITH AZO DYE

Terence Harper, Leeds, and Allen P. Gates, Knaresborough, both of Great Britain, assignors to Vickers Limited, London, England

Continuation of Ser. No. 895,070, Apr. 10, 1978, abandoned.

This application Feb. 19, 1980, Ser. No. 122,190

Claims priority, application United Kingdom, Apr. 12, 1977, 15144/77

Int. Cl.³ G03C 1/60, 1/54

U.S. Cl. 430—176

10 Claims

1. A positive working light-sensitive composition which exhibits a colour change upon exposure to light, which composition comprises in admixture (a) a first component which is an azo dye formed by reacting a p-aminobenzene diazonium salt and a compound selected from 3-hydroxy-2-naphthoic acid and acid derivatives thereof and (b) a second component which includes a non-light sensitive polymer and an o-quinone diazide and/or a diazonium compound and which, on exposure to light, produces an acidic light decomposition product which is capable of reacting with the azo dye to produce a material having a colour different to that of the azo dye.

4,296,195

TWO-SHEET DIFFUSION TRANSFER ASSEMBLAGES AND PHOTOGRAPHIC ELEMENTS

John F. Bishop, and Wayne A. Bowman, both of Rochester, N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.
Filed Aug. 1, 1980, Ser. No. 174,420Int. Cl.³ G03L 5/54, 7/00, 1/76

U.S. Cl. 430—215

23 Claims

1. In a photographic element comprising a support having thereon, in order, a polymeric acid layer, a timing layer and at least one unexposed photosensitive silver halide emulsion layer having associated therewith a dye image-providing material, the improvement wherein a primer layer is located between said polymeric acid layer and said timing layer, said primer layer comprising:

- (a) a mixture of gelatin and cellulose nitrate; or
(b) a mixture of an acrylic acid copolymer and an acrylic acid terpolymer, said acrylic acid copolymer comprising 60 to 90 weight percent of recurring units derived from acrylic acid and 10 to 40 weight percent of recurring units derived from an alkyl acrylate or alkyl methacrylate, wherein said alkyl group has 1 to about 10 carbon atoms; said acrylic acid terpolymer comprising 5 to 40 weight percent of recurring units derived from acrylic acid, 10 to 40 weight percent of recurring units derived from acrylonitrile and 20 to 85 weight percent of recurring units derived from vinylidene chloride, said acrylic acid copolymer comprising from about 40 to about 90 weight percent of said mixture; or
(c) an acrylic acid copolymer comprising 5 to 30 weight percent of recurring units derived from acrylic acid and 70 to 95 weight percent of recurring units derived from an alkyl acrylate or alkyl methacrylate, wherein said alkyl group has 1 to about 10 carbon atoms.

4,296,196


PHOTOPOLYMERIZABLE MIXTURE IN A TRANSFER ELEMENT

Raimund J. Faust, Wiesbaden, Fed. Rep. of Germany, assignor to Hoechst Aktiengesellschaft, Fed. Rep. of Germany
Division of Ser. No. 41,741, May 23, 1979, Pat. No. 4,250,248.
This application Jun. 27, 1980, Ser. No. 163,597Int. Cl.³ G03C 5/00, 1/68

U.S. Cl. 430—271



12 Claims

1. A light-sensitive transfer material, comprising a flexible temporary support and a thermoplastic photopolymerizable layer which layer comprises a polymeric, thermoplastic binder which is soluble or at least swellable in aqueous-alkaline solutions, a polyurethane with two terminal acrylic acid or methacrylic acid ester groups which is capable of addition polymerization, and a photoinitiator, said polyurethane corresponding to Formula I




wherein

—X— is one of the groups



Y is a saturated aliphatic or cycloaliphatic group with 2 to 12 carbon atoms, and
Z is



and wherein

R₁, R₂, and R₃ are hydrogen atoms or methyl groups,
n is a whole number from 2 to 15,
m is a whole number from 2 to 4,
p is a whole number from 1 to 4,
k is a whole number from 2 to 12, and
r is a whole number from 4 to 12.


4,296,197

HALFTONE PRINTING SYSTEM

Robert W. Stevie, Ft. Thomas, Ky., assignor to Innovative Photographic Enterprises, Inc., Cincinnati, Ohio
Continuation of Ser. No. 803,256, Jun. 3, 1977, abandoned. This application Nov. 1, 1979, Ser. No. 90,475Int. Cl.³ G03F 5/00; G03C 5/00

U.S. Cl. 430—300

5 Claims



1. A method of making a printing plate comprising focusing light into a gray scale image onto photographic printing paper through a halftone screen and irradiating said paper through said screen with light in addition to the light focused into said gray scale image, said printing paper being selected to have a sufficiently high contrast rating to produce dots which are uniformly black with no shades of gray over the area of each dot in the resulting halftone image produced on said printing paper, assembling said halftone print with cold type to make up a page, making a negative of the assembly of said cold type and said halftone print, and making a printing plate from said negative.

4,296,198

PHOTOGRAPHIC PROCESS USING A THIN FLEXUOUS LAYER AND REFLECTIVE LAYER

Franz Trautweiler, Fribourg, Switzerland, assignor to Ciba-Geigy AG, Basel, Switzerland

Filed Jul. 2, 1979, Ser. No. 54,044

Claims priority, application Switzerland, Jul. 7, 1978, 7421/78
Int. Cl.³ G03C 1/84, 11/14

U.S. Cl. 430—403

18 Claims

1. In a process for the production of a photographic print including the steps of providing a composite photographic material comprising a transparent support layer carrying photosensitive material, forming the print image including at least the steps of exposing the photosensitive material and developing the exposed photosensitive material, and then adhering the image-bearing composite material to a main support with the

developed photosensitive material disposed between said support layer and said main support, the improvement comprising providing said support layer as a flexuous layer having a thick-



ness of from about 5μ to 50μ and having a light reflective layer adhered to said main support with said developed photosensitive layer being in contact with said light reflective layer.

4,296,199

SILVER HALIDE PHOTOGRAPHIC LIGHT-SENSITIVE MATERIAL

Morio Yagihara, and Yukio Yokota, both of Minami-ashigara, Japan, assignors to Fuji Photo Film Co., Ltd., Minami-ashigara, Japan

Filed Jun. 19, 1980, Ser. No. 161,237


Claims priority, application Japan, Jun. 19, 1979, 54-77152

Int. Cl.³ G03C 1/40

U.S. Cl. 430—551

22 Claims

1. A silver halide photographic light-sensitive material containing a colorless photographic cyan color-forming coupler having, in a position for coupling with an oxidation product of an aromatic primary amine developing agent, a coupling-off group represented by the formula (I)



wherein R₁ and R₂ each represents an unsubstituted straight or branched chain alkylene group; R₃ represents a substituted or unsubstituted alkyl group, a cycloalkyl group, an aryl group, or a heterocyclic group; x represents a positive integer; and y represents 0 or a positive integer.

16. A light-sensitive material as in claim 1, wherein said coupler is present in a layer containing a p-substituted phenol derivative or in a layer adjacent to a layer containing a p-substituted phenol derivative.

4,296,200

SILVER HALIDE PHOTOGRAPHIC LIGHT-SENSITIVE MATERIAL

Morio Yagihara, and Yukio Yokota, both of Minami-ashigara, Japan, assignors to Fuji Photo Film Co., Ltd., Minami-ashigara, Japan

Filed Aug. 12, 1980, Ser. No. 177,337


Claims priority, application Japan, Aug. 13, 1979, 54-102963

Int. Cl.³ G03C 1/40

U.S. Cl. 430—551

18 Claims

1. A silver halide photographic light-sensitive material containing a colorless photographic cyan color forming coupler having, in a position for coupling with an oxidation product of an aromatic primary amine developing agent, a coupling-off group represented by the formula (I):



wherein R represents a substituted alkylene group containing from 1 to 18 carbon atoms or an unsubstituted or substituted alkenylene group, and said alkylene group or alkenylene group may be straight or branched chain; and R₁ represents a substituted or unsubstituted alkyl group, an alkenyl group, an aralkyl group, an aralkenyl group, a cycloalkyl group, or a heterocyclic group and said alkyl group, alkenyl group, aralkyl group and aralkenyl group may be straight chain or branched chain; and said heterocyclic group being connected with a thio group at the position of a carbon atom of the heterocyclic group.

15. A light-sensitive material as in claim 1, wherein said coupler is present in a layer adjacent to a layer containing a p-substituted phenol derivative or in a layer containing a p-substituted phenol derivative.

4,296,201

METHODS FOR THE DETECTION OF ANTIMITOCHONDRIAL AND ANTINUCLEAR ANTIBODIES

Wolfgang Ax, Marburg an der Lahn; Hartwig W. Bauer, Munich, and Hans-Harald Sedlacek, Marburg an der Lahn, all of Fed. Rep. of Germany, assignors to Behringwerke Aktiengesellschaft, Marburg an der Lahn, Fed. Rep. of Germany

Filed Aug. 16, 1979, Ser. No. 67,003

Claims priority, application Fed. Rep. of Germany, Aug. 19, 1978, 2836362

Int. Cl.³ G01N 33/54

U.S. Cl. 435—7

2 Claims

1. A method for testing for the presence of anti-mitochondrial antibodies which comprises coating air-dried unfixed hypernephroma cells with an isotonic salt solution of the antibody to be tested, incubating the coated cells for 10 minutes to 2 hours in a moist chamber, then washing the cells with an isotonic salt solution and coating them with a fluorescently-labeled antibody directed against antigen-determinants of the antibody sought for, incubating the cells for 10 minutes to 2 hours in a moist chamber, washing at least once with demineralized water, and examining the cells by immunofluorescence microscopy, whereby fluorescence of the mitochondria of the hypernephroma cells is considered a positive finding of said anti-mitochondrial antibodies.

4,296,202

DIAGNOSTIC COMPOSITION FOR THE DETECTION OF LEUKOCYTES AND CHROMOGENS USEFUL THEREIN

Dieter Berger, Viernheim; Franz Braun, Rimbach; Günter Frey, Ludwigshafen; Werner Güthlein, Mannheim-Neckarau, and Manfred Kuhr, Mannheim, all of Fed. Rep. of Germany, assignors to Boehringer Mannheim GmbH, Fed. Rep. of Germany

Filed Aug. 2, 1979, Ser. No. 63,211

Claims priority, application Fed. Rep. of Germany, Aug. 22, 1978, 2836644

Int. Cl.³ C12Q 1/29

U.S. Cl. 435—29

36 Claims

1. Diagnostic composition for the detection of leukocytes in body fluids, comprising an absorbent carrier impregnated with a buffer substance and a chromogen, wherein the chromogen is an azo dyestuff ester of the formula



wherein

A is a five- or six-membered heterocyclic radical of up to 2 hetero ring atoms selected from nitrogen, sulfur and oxygen, and wherein the heterocyclic ring may be substituted with at least one member of the group selected from halogen, lower alkyl and lower alkoxy; or

A is phenyl substituted by at least one member of the group selected from lower alkyl, lower alkoxy, nitro, sulphanato and acylamino;

B is benzene, naphthalene or quinoline, optionally substituted with one or two radicals selected from sulphanato, lower alkoxy and lower alkoxy-poly-alkyleneoxy;

R is a carboxylic acid residue or an amino acid or peptide residue having a nitrogen protective group; and
n is 1 or 2.

4,296,203

XANTHOMONAS BIPOLYMER FOR USE IN DISPLACEMENT OF OIL FROM PARTIALLY DEPLETED RESERVOIRS

William C. Wernau, Groton, Conn., assignor to Pfizer Inc., New York, N.Y.

Filed Nov. 15, 1977, Ser. No. 851,757

Int. Cl.³ C12P 19/06; C12N 15/00, 1/20; C12R 1/64

U.S. Cl. 435—104

9 Claims

1. A process for preparing a pyruvate-free xanthan-containing fermentation broth suitable for the preparation of mobility control solutions used in oil recovery which comprises aerobically fermenting a pyruvate-free xanthan producing strain of *Xanthomonas campestris* in an aqueous nutrient medium whose ingredients comprise a carbohydrate, a source of assimilable nitrogen and trace elements and continuing the fermentation until at least about 100 ppm of pyruvate-free xanthan is present in the broth.

7. A process for preparing deacetylated pyruvate-free xanthan suitable for use in the recovery of oil from an oil-bearing subterranean formation by injecting a mobility control solution containing said deacetylated pyruvate-free xanthan into said formation which comprises

- (a) fermenting by aerobic propagation a pyruvate-free xanthan producing strain of *Xanthomonas campestris* in an aqueous nutrient medium whose ingredients comprise a carbohydrate, a source of assimilable nitrogen and trace elements until at least about 100 ppm of pyruvate-free xanthan is present in the broth,
 - (b) adjusting the pH of the whole or filtered broth to about 9, allowing the resultant broth to stand at room temperature for at least 10 minutes and optionally neutralizing, and
 - (c) adding sufficient water miscible precipitating agent to cause precipitation of said deacetylated pyruvate-free xanthan and separating said precipitated deacetylated pyruvate-free xanthan therefrom.
9. A biologically pure culture of the microorganism *Xanthomonas campestris*, having the identifying characteristics of ATCC 31313, said culture being capable of producing pyruvate-free xanthan in a recoverable quantity upon fermentation in an aqueous nutrient medium containing assimilable sources of carbon, nitrogen and inorganic substances.

4,296,204

USE OF MOTIONLESS MIXER AS CELL CULTURE PROPAGATOR

Roy Grabner, Blue Bell, Pa., and Edward L. Paul, Chatham Township, Union County, N.J., assignors to Merck & Co., Inc., Rahway, N.J.

Continuation-in-part of Ser. No. 872,289, Jan. 25, 1978, abandoned. This application Jul. 7, 1980, Ser. No. 166,641

Int. Cl.³ C12M 7/00

U.S. Cl. 435—235

2 Claims

1. A process for propagating cells comprising attaching cells to the surfaces of a motionless mixer element disposed within a housing, the motionless mixer element comprising an assembly of parallel sheets shaped to provide a plurality of channels which converge and diverge to form a plurality of mixing cells, each cell being formed and bounded by the juncture of two inlet channels which converge toward each other at about right angles in one plane, and two outlet channels which diverge from each other at about right angles in another plane, the planes being rotated about 90° with respect to each other, supplying nutrients into the mixer and

maintaining the cells under conditions which permit cell growth and division, and harvesting the cells.

4,296,205

CELL CULTURE AND CONTINUOUS DIALYSIS FLASK AND METHOD


Dharmvir S. Verma, 5831 Rutherglen, Houston, Tex. 77096

Filed Feb. 22, 1980, Ser. No. 123,552

Int. Cl.³ C12M 3/04; C12N 5/00

U.S. Cl. 435—240

12 Claims



1. In a flask for the growth of cells or the preparation of conditioned media comprising a tissue culture chamber, a dialysis chamber and a dialysis or millipore membrane separating said chambers, the improvement comprising a tissue culture shelf separating the tissue culture chamber into a tissue culture compartment and a dialysis compartment, said shelf having one or more perforations, wherein the edges of said tissue culture shelf surrounding said perforations are upraised to form tray-like areas so that cells cultured on said shelf do not pass over said edges and through said perforations.

4,296,206

IRREVERSIBLE ANTI-GLUCOCORTICOIDS

S. Stoney Simons, Jr., Bethesda, Md., assignor to United States of America, Washington, D.C.

Filed Apr. 30, 1980, Ser. No. 145,350

Int. Cl.³ C12N 5/00

U.S. Cl. 435—240

5 Claims

1. In a method for inhibiting glucocorticoid action, the improvement which comprises the use as the inhibitor of a compound selected from the group consisting of cortisol-21-mesylate and dexamethasone-21-mesylate.

4,296,207

ANTIFREEZE PROTECTION OF ROADS

Werner Siegmund, Mannheim, Fed. Rep. of Germany, assignor to Mannesmann Aktiengesellschaft, Duesseldorf, Fed. Rep. of Germany

Filed Jun. 5, 1980, Ser. No. 156,747

Claims priority, application Fed. Rep. of Germany, Jun. 11, 1979, 2923939; Oct. 24, 1979, 2943447; Nov. 16, 1979, 2946823

Int. Cl.³ C08G 18/14

U.S. Cl. 521—53

15 Claims

1. An admixture for the surface layer of a road, comprising: a first and primary component thereof, being a granular, inorganic material, grains thereof being porous, in which the pore volume is at least 30 degrees, the pores containing a first antifreeze substance; a second and secondary component, being a granular, organic material, the grains thereof also being porous and having a pore volume in excess of 30 degrees, the pores containing a second antifreeze substance; at least one of the components being made hydrophobic through the addition of a silicon-organic compound; and the grains of said first and second component being embedded in a bituminous, or asphalt, binder.

4,296,208

METHODS OF PREPARING POLYIMIDES AND POLYIMIDE PRECURSORS


John Gagliani, and Usman A. K. Sorathia, both of San Diego, Calif., assignors to International Harvester Company, Chicago, Ill.

Filed Sep. 12, 1980, Ser. No. 186,670

Int. Cl.³ C08J 9/00; C08G 18/16

U.S. Cl. 521—77

18 Claims



1. A method of preparing a dry, foamable, particulate precursor which can be converted into a polyimide by heating it, said method comprising the steps of: forming a primary diamine, 3,3',4,4'-benzophenonetetracarboxylic acid ester solution by dissolving one or more such diamines and the aforesaid acid or an anhydride thereof in a lower alkyl alcohol, atomizing said solution, and drying the droplets obtained by atomizing the diamine, ester solution with a heated gas.

4,296,209

MATERIAL AS SPONGIOSACEMENT WITH EFFERVESCENT REABSORPTIVE EFFECT

Dobrivoje Tomic, Munich, Fed. Rep. of Germany

Continuation of Ser. No. 961,346, Nov. 17, 1978, abandoned.

This application Mar. 26, 1980, Ser. No. 133,973

Int. Cl.³ C08K 3/10, 3/24, 5/11; C08L 33/12

U.S. Cl. 521—85

2 Claims

1. A cement mixture for use in surgical and therapeutic procedures in animals, comprising

- (a) approximately 70% by weight polymethylmethacrylate as a cementitious substance,
- (b) approximately 20% CaCO₃ as effervescent medium,
- (c) approximately 10% Na₂HPO₄·12H₂O as reabsorptive substance, and,
- (d) phosphoric acid as an agent for activating said medium to cause said medium to effervesce whereby when said cement is mixed and applied to an animal bone, solid tissue and the like the effervescent effect and reabsorptive substance will produce voids in said cement prior to the curing of said cement in situ.

4,296,210

OPEN-CELL SHAPED ARTICLE MADE OF ACETALIZED POLYVINYL ALCOHOL AND PROCESS FOR ITS MANUFACTURE

Wolfgang Zimmermann, Kelkheim; Hermann Schindler, Hofheim am Taunus, and Günther Pospich, Frankfurt am Main, all of Fed. Rep. of Germany, assignors to Hoechst Aktiengesellschaft, Frankfurt am Main, Fed. Rep. of Germany

Filed Nov. 26, 1980, Ser. No. 211,332

Claims priority, application Fed. Rep. of Germany, Dec. 1, 1979, 2948508

Int. Cl.³ C08V 9/30

U.S. Cl. 521—85

9 Claims

1. An open-cell shaped article made of acetalized polyvinyl

alcohol which is characterized in that the shaped article (a) consists of acetalized polyvinyl alcohol which, prior to acetalization, has an ester number of 50 to 270 mg of KOH/g and the 4% by weight aqueous solution of which has a viscosity of 4 to 50 mPa·s at 20° C., (b) has cells with diameters in the range of from 0.5 to 5 mm in uniform distribution and (c) contains a nucleic acid.

4,296,211

PROCESS FOR THE PRODUCTION OF POLY(POLYISOCYANATE-POLYOL-ALKALI METAL SILICATE) SOLID OR FOAMED PRODUCTS

David H. Blount, 5450 Lea St., San Diego, Calif. 92105

Division of Ser. No. 146,474, May 5, 1980, which is a continuation-in-part of Ser. No. 36,350, May 7, 1979, which is a continuation-in-part of Ser. No. 889,932, Mar. 27, 1978, which is a continuation-in-part of Ser. No. 663,924, Mar. 4, 1976, which is a continuation-in-part of Ser. No. 599,000, Jul. 7, 1975, Pat. No. 4,072,637, which is a continuation-in-part of Ser. No. 262,485, Jun. 14, 1972, abandoned, which is a continuation-in-part of Ser. No. 71,628, Sep. 11, 1970, abandoned. This application Jan. 26, 1981, Ser. No. 228,083

Int. Cl.³ C08G 77/00

U.S. Cl. 521—154

26 Claims

1. The improved process for the production of poly(polyisocyanate-polyol-alkali metal silicate) foamed products by mixing and reacting the following components:

- (a) the improvement comprises of producing an emulsion of a polyol and alkali metal silicate, which contains only water molecules that are attached to the alkali metal silicate,
- (b) an organic polyisocyanate or polyisothiocyanate.

4,296,212

ELASTOMERIC POLYURETHANE-POLYUREA POLYMER PREPARED FROM AN ORGANIC POLYISOCYANATE A POLYOL AND AN AROMATIC DIAMINE HAVING AT LEAST ONE OF THE ORTHO POSITIONS TO EACH AMINE LOWER ALKYL

James H. Ewen, and Thomas R. McClellan, both of Seabrook, Tex., assignors to The Upjohn Company, Kalamazoo, Mich.

Filed Aug. 27, 1980, Ser. No. 181,720

Int. Cl.³ C08G 18/14

U.S. Cl. 521—163

11 Claims

1. In an elastomeric polyurethane-polyurea polymer prepared by the catalyzed reaction of an organic polyisocyanate, a polyol and an extender mixture comprising an aromatic polyamine and a low molecular weight diol the improvement which comprises employing in said reaction, with said organic polyisocyanate

A. a polyol having a primary hydroxyl functionality of from about 2 to about 4 and a molecular weight of from about 1500 to about 12,000, and

B. an extender mixture comprising,

- (i) an aromatic diamine wherein at least one of the positions ortho to each amine group of said diamine is substituted by a lower alkyl group, and
- (ii) a low molecular weight diol provided that said aromatic diamine comprises from about 5 to about 45 percent by weight of said extender mixture with the balance of from about 55 to about 95 percent by weight comprising the diol extender, and

wherein the equivalent proportions of said polyol (A) to said extender mixture (B) is within the range of about 1:4 to about 1:50, and the ratio of isocyanate equivalents to the total active hydrogen equivalents of said polyol, said aromatic diamine, and said diol is from about 0.85 to about 1.35.

4,296,213

POLYURETHANE FOAMS USING A POLYUREA POLYMER POLYOL

Michael Cuscrida, and George P. Speranza, both of Austin, Tex., assignors to Texaco Inc., White Plains, N.Y.

Continuation-in-part of Ser. No. 86,365, Oct. 17, 1979, abandoned. This application Oct. 31, 1980, Ser. No. 202,892
Int. Cl.³ C08G 18/14, 18/50, 18/32

U.S. Cl. 521-166

11 Claims

1. A polyurea polymer polyol made by the reaction of a hydroxyl-containing amine, a polyether polyol of about 3000 to 8000 molecular weight and an organic polyisocyanate wherein the ratio of moles of hydroxyl containing amine to moles of polyether polyol ranges from about 0.5 to 3.5 and the ratio of moles of active hydrogens to moles of isocyanate groups ranges from about 1.4 to 3.5.

6. A method for producing a polyurethane which comprises first making a polyurea polymer polyol by reacting a hydroxyl-containing amine, a polyether polyol and an organic polyisocyanate wherein the ratio of moles of hydroxyl containing amine to moles of polyether polyol ranges from about 0.5 to 3.5 and the ratio of moles of active hydrogens to moles of isocyanate groups ranges from about 1.4 to 3.5 and then reacting said polyurea polymer polyol with an organic polyisocyanate.

4,296,214

METHACRYLIC RESIN HAVING A HIGH SOLAR RADIANT ENERGY ABSORBING PROPERTY AND PROCESS FOR PRODUCING THE SAME

Kazumasa Kamada; Yoshio Nakai, and Kazunori Abe, all of Ootake, Japan, assignors to Mitsubishi Rayon Co., Ltd., Tokyo, Japan


Filed Apr. 11, 1980, Ser. No. 139,441

Claims priority, application Japan, Apr. 20, 1979, 54-49240

Int. Cl.³ C08K 5/09, 5/52

U.S. Cl. 525-2

22 Claims



A EXAMPLE 3 a CONTROL 1
B EXAMPLE 4 b CONTROL 2
C EXAMPLE 5 c CONTROL 3
D EXAMPLE 6 d CONTROL 4

1. A methacrylic resin having a high solar radiant energy absorbing property wherein an organic compound (A) containing cupric ion in an amount of 0.01 to 5 parts by weight calculated as cupric ion and a compound (B) having at least one P—O—H bond in a molecule in an amount to be 0.1 to 10 mols per mol of the above mentioned organic compound (A) are contained per 100 parts by weight of a methacrylic resin selected from homopolymer of methyl methacrylate or copolymers of polymerizable unsaturated monomer mixture containing at least 50% by weight of a methyl methacrylate.

4,296,215

METHOD TO THICKEN DISSOLVED THERMOSET RESINS

Kenneth H. Markiewicz, Wilmington, Del., assignor to ICI Americas Inc., Wilmington, Del.

Continuation of Ser. No. 928,691, Jul. 27, 1978, abandoned. This application Apr. 7, 1980, Ser. No. 137,896
Int. Cl.³ C08L 75/06, 67/06, 63/02

U.S. Cl. 525-28

28 Claims

1. A method of increasing the viscosity of a uniformly dispersed or solubilized composition comprising (A) at least 10 percent by weight of a polymerizable resin selected from the class consisting of a vinyl urethane resin and an unsaturated polyester resin which resin is curable to a thermoset resin and has a molecular weight of at least 500, and (B) up to 90% by weight of an ethylenically unsaturated monomer, which method comprises mixing into the composition an amount of at least 2% by weight of the composition of a polyisocyanate and a catalytic amount of a trimerization catalyst selected from the class consisting of quaternary ammonium hydroxides, quaternary ammonium acetates, quaternary ammonium formates, alkali metal acetates and alkali metal formates, and trimerizing the polyisocyanate in the composition.

4,296,216

THERMOPLASTIC RESIN COMPOSITION

Hajime Sakano, Hirakata; Mikio Kodama, Takatsuki; Koichi Nakayama; Isao Yoshida, both of Amagasaki, and Atsunori Inoue, Takatsuki, all of Japan, assignors to Sumitomo Naugatuck Co., Ltd., Osaka, Japan

Filed Mar. 5, 1980, Ser. No. 127,287

Int. Cl.³ C08L 55/02, 77/00, 59/02, 59/04

U.S. Cl. 525-66

1 Claim

1. A thermoplastic resin composition consisting essentially of (A) at least one of polyamide resins and polyacetal resins, (B) at least one of aromatic monovinyl compound/vinyl cyanide copolymers comprising units of aromatic monovinyl compounds and units of vinyl cyanides in a weight ratio of 60:40 to 80:20 and having an intrinsic viscosity of 0.3 to 1.1 and (C) at least one of conjugated diene rubber/vinyl cyanide graft copolymers comprising units of conjugated diene rubbers in an amount of 5 to 45% by weight based on the weight of the graft copolymers in a weight proportion of the components (A), (B) and (C) being respectively 0.1-10:5-90:5-94.9.

4,296,217

AROMATIC POLYETHERSULPHONES HAVING —OCH₂COR END GROUPS

John Stuart-Webb, Welwyn Garden City, England, assignor to Imperial Chemical Industries Limited, London, England

Filed Feb. 22, 1979, Ser. No. 14,249

Claims priority, application United Kingdom, Feb. 28, 1978, 7865/78

Int. Cl.³ C08G 65/48

U.S. Cl. 525-390

6 Claims

1. An aromatic polyethersulphone containing repeat units of the general formula



or, where E is the same as E',



in which E is the residuum obtained by the removal of the halogen atoms of a dihalobenzenoid compound in which each halogen atom is activated by an —SO₂— group ortho or para thereto, and E' is the residuum obtained by removal of the hydroxyl groups from a bisphenol; or where E is the same as E', it is the residuum obtained by the removal of the halogen atom and the hydroxyl group from a halophenol in which the halogen atom is activated by an —SO₂— group ortho or para thereto, said polyethersulphone having from 3 to 20 end

groups of the formula —OCH₂COR where R is alkyl or alkoxy, per 100 repeat units.

4,296,218

HEAT-CURABLE AND SOLVENT-SOLUBLE ESTER GROUP-CONTAINING POLYMER COMPOSITIONS AND PROCESS FOR THEIR PREPARATION

Shigeyoshi Hara, and Tateyoshi Yamada, both of Hino, Japan, assignors to Teijin Limited, Osaka, Japan

Division of Ser. No. 894,006, Apr. 6, 1978, Pat. No. 4,251,649, which is a division of Ser. No. 593,644, Jul. 7, 1975, Pat. No. 4,137,221. This application Apr. 23, 1980, Ser. No. 143,161

Claims priority, application Japan, Jul. 11, 1974, 49-78672; Sep. 30, 1974, 49-111649


Int. Cl.³ C08L 67/02; C08J 3/00

U.S. Cl. 525-439

16 Claims

1. A process for producing a heat-curable and solvent soluble ester group containing polymer composition which comprises:

- (1) reacting a highly polymerized linear aromatic polyester having an intrinsic viscosity (η), measured on an o-chlorophenol solvent at 35° C., of above 0.3 (component 1) with 10 to 70 mole percent, based on the total amount, in moles of dibasic acid contained in the polyester, of a diaryl carbonate (component 2) in the presence of a compound (component 3) containing at least two functional groups selected from the group consisting of (a) a carboxyl group or its functional derivatives, (b) a cyclic carboxylic anhydride group or its precursors, (c) a primary or secondary amino group, (d) an isocyanate group or its stabilized group or precursors, (e) an iminoacetic acid group or its functional derivatives, and (f) an hydroxyl group, to depolymerize the polyester and form a modified solvent-soluble low molecular weight polyester (component A') in which at least 30 mole percent of the entire terminal groups are aryl carboxylate groups,
- (2) mixing a monomeric or solvent soluble low molecular weight polymeric condensation product of at least two species of component 3 (component C) in which the main chain includes at least one linkage selected from the group consisting of amide, imide, hydantoin and ester linkages and at least 50 mole percent of the entire terminal groups and carboxyl groups or functional derivatives thereof, with component A' to form a mixture (D), and
- (3) (i) mixing or (ii) partially reacting the mixture (D) with a monomeric or polymeric solvent-soluble polyfunctional compound (component B) containing at least two reactive groups selected from the group consisting of hydroxyl, primary amino and secondary amino.



wherein R₁ is a group containing at least two carbon atoms, the nitrogen atoms of the imide rings being directly connected to different carbon atoms of the group R₁, R₂ is a group containing at least two carbon atoms, the carbonyl groups of the imide rings being directly connected to different carbon atoms of the group R₂, R'₂ is a group containing at least two carbon atoms and a carbon-carbon double bond, R₃ is an aromatic group, the oxygen atoms between the groups R₂ and R₃ being directly connected to different carbon atoms of the aromatic nucleus of the group R₃, and n is an integer of zero, 1 or larger than 1, the bisimide ether compound being soluble in an organic solvent having a boiling point not higher than 130° C. at normal temperature and under normal pressure.

4,296,219

BISMIDE-ETHER COMPOUNDS, COMPOSITIONS THEREOF, AND METHOD OF PRODUCING SAME

Akio Takahashi; Yutaka Itoh; Motoyo Wajima; Hirosada Morishita, and Akio Nishikawa, all of Ibaraki, Japan, assignors to Hitachi, Ltd. and Hitachi Chemical Co., Ltd., both of Tokyo, Japan

Filed Jan. 22, 1979, Ser. No. 5,233

Claims priority, application Japan, Mar. 31, 1978, 53-36592; Jun. 7, 1978, 53-67712

Int. Cl.³ C08G 73/12

U.S. Cl. 525-488

40 Claims

1. A bisimide-ether compound having the general formula:

4,296,220

METHOD FOR PREPARING VINYL ESTER RESINS
Harold O. Seeburger; Ralph G. Beattie, and Violette L. Stevens, all of Midland, Mich., assignors to The Dow Chemical Company, Midland, Mich.

Filed Jun. 2, 1980, Ser. No. 155,882

Int. Cl.³ C08G 8/32; C07C 57/00, 69/54

U.S. Cl. 525-507

11 Claims

1. A process for preparing vinyl ester resins wherein a hydroxy phenolic compound is reacted in the presence of a basic catalyst with tertiary alkyl glycidyl ether and the resulting reaction product is dealkylated and esterified with an ethylenically unsaturated carboxylic acid.

4,296,221


PROCESS AND APPARATUS FOR INTERMITTENT POLYMERIZATION AT ELEVATED PRESSURE
 Helmut Bauer, Basel, Switzerland, assignor to Maschinenfabrik Burckhardt AG, Basel, Switzerland

Filed Mar. 28, 1980, Ser. No. 135,122

Claims priority, application Switzerland, Apr. 26, 1979, 3960/79

Int. Cl.³ C08F 2/34, 10/02

U.S. Cl. 526—87



1. A process for an intermittent polymerization comprising the steps of:
 supplying a substance to be polymerized in gaseous form in timed relation to a working zone of a pump or compressor volumetrically operable between two pressure stages; thereafter compressing the substance in the working zone to a predetermined pressure and temperature; and adding a polymerization catalyst to the working zone at the latest in an initial range of expansion of the substance in the working zone to effect polymerization.

4,296,222

MANUFACTURE OF POLY- α -OLEFINS

Gerhard Staiger, Bobenheim-Roxheim, and Klaus Bronstert, Carlsberg, both of Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Fed. Rep. of Germany

Filed Mar. 24, 1977, Ser. No. 780,764

Claims priority, application Fed. Rep. of Germany, Apr. 13, 1976, 2616260

Int. Cl.³ C08F 4/66, 10/06

U.S. Cl. 526—119

8 Claims

1. In a process for the manufacture of an α -olefin polymer by polymerizing one or more α -olefins at from 0° to 150° C. and from 1 to 100 atmospheres absolute by means of a catalyst system comprising (1) a titanium-containing component obtained from (1.1) a compound of the formula $TiCl_3 \cdot \frac{1}{2} AlCl_3$ having a maximum particle diameter of 2 μm and (1.2) an organic electron donor, containing one or more phosphorus, nitrogen and/or oxygen atoms, which has been milled with the compound of the formula $TiCl_3 \cdot \frac{1}{2} AlCl_3$ (1.1) to form a complex compound, and (2) an aluminum-containing component consisting of a compound of the formula $Al(C_nH_{2n+1})_3$ or $Al(C_nH_{2n+1})_2Cl$ or a mixture of such compounds, n being, in each case, an integer from 2 to 6, with the provisos that the molar ratio of titanium contained in the compound of the formula $TiCl_3 \cdot \frac{1}{2} AlCl_3$ (1.1) to the electron donor (1.2) is from 10:5 to 10:1 and the molar ratio of titanium contained in the compound of the formula $TiCl_3 \cdot \frac{1}{2} AlCl_3$ (1.1) to the aluminum-containing component (2) is from 10:5 to 10:300, the catalyst system employed being a system in the preparation of which the milling of the compound of the formula $TiCl_3 \cdot \frac{1}{2} AlCl_3$ (1.1) with the electron donor (1.2) has been carried out without assistants or additives in a vibratory ball mill with steel balls of from 6 to 60 mm diameter under a milling acceleration of from 30 to 70 $m \cdot sec^{-2}$ for a period of from 10 to 70 hours at a temperature which is from 4° to 10° C. below the temperature at which the particles of the material being ground begin to agglomerate, the improvement wherein the titanium-containing catalyst component (1) of the catalyst system used is one which has been treated with from 0.2 to 2.0 parts by weight of (i) titanium tetrachloride per part by weight of the untreated

catalyst component (1) and (ii) from 0.15 to 1.5 parts by weight of an ether and/or ester per part by weight of the untreated catalyst component (1) after milling and before the polymerization.

4,296,223

POLYMERIZATION OF OLEFINS

Eugene Berger, Brussels, Belgium, assignor to Solvay & Cie, Brussels, Belgium

Continuation of Ser. No. 658,682, Feb. 17, 1976, abandoned, which is a continuation of Ser. No. 372,073, Jun. 21, 1973, abandoned. This application Oct. 8, 1980, Ser. No. 195,093

Claims priority, application Luxembourg, Jun. 22, 1972, 65587

Int. Cl.³ C08F 4/02, 10/02

U.S. Cl. 526—125

17 Claims

1. A solid catalytic complex comprising the solid reaction product formed by reacting together:
 (A) at least one reagent selected from magnesium dichloride and magnesium dichloride hydrate; with
 (B) at least one reagent which is a halogen-free titanium alkoxide containing C_1 - C_{20} organic radicals bonded to the metal via oxygen; and with
 (C) at least one reagent which is an alkyl aluminium chloride having the general formula AlR'_nX_{3-n} in which R' is a hydrocarbon radical containing 1 to 20 carbon atoms, X is a chloride and n is any number such that $1 \leq n \leq 2$.

4,296,224

PERFLUOROALKYL-ACR[METHACRYL]YLATE, HYDROXY-CHLOROPROPYL-ACRYLATE POLYMER
 Shosin Fukui, Shinsenrihigashi, and Tadashi Akazawa, Osaka, both of Japan, assignors to Daikin Kogyo Co., Ltd., Osaka, Japan

Filed Sep. 26, 1979, Ser. No. 79,217

Claims priority, application Japan, Sep. 28, 1978, 53-119694

Int. Cl.³ C08F 220/38, 220/30

U.S. Cl. 526—243

6 Claims

1. A water and oil repellent consisting essentially of a copolymer comprising units of (a) at least 25% by weight of at least one of perfluoroalkyl group-containing acrylates and methacrylates and of (b) from 0.1 to 10% by weight of at least one of 2-hydroxy-3-chloropropyl acrylate and methacrylate of the formula:



wherein R is hydrogen or methyl.

4,296,225

STABLE VINYL ACETATE AND AMINE MONOMER COPOLYMER EMULSIONS

David Rhum, Old Lyme, Conn., assignor to Celanese Corporation, New York, N.Y.

Filed Jan. 4, 1980, Ser. No. 109,574

Int. Cl.³ C08F 2/30, 2/24, 20/34

U.S. Cl. 526—260

2 Claims

1. A process for preparing a stable aqueous emulsion composition adapted for application as a wet abrasion-resistant paper coating binder which comprises simultaneously adding to an aqueous medium containing a vinyl polymerization catalyst a combination of copolymerizable monomer components comprising (1) between about 70-95 weight percent of vinyl acetate; (2) an aqueous solution of between about 0.5-10 weight percent of vinyl monomer containing an aliphatic amine-acid salt group; and (3) 0.5-20 weight percent of at least one other vinyl monomer, all based on total monomer weight; wherein the aqueous solution of amino-containing vinyl monomer is added as a separate feedstream.

4,296,226

VINYL POLYMER WITH ACETYLACETOXY GROUPS, PROCESS FOR ITS MANUFACTURE AND AN AGENT OBTAINED THEREOF

Helmut Braun, Krieffel; Helmut Rinno, Hofheim am Taunus, and Karl J. Rauterkus, Kelkheim, all of Fed. Rep. of Germany, assignors to Hoechst Aktiengesellschaft, Frankfurt am Main, Fed. Rep. of Germany

Filed Jul. 9, 1980, Ser. No. 167,052


Claims priority, application Fed. Rep. of Germany, Jul. 11, 1979, 2927932

Int. Cl.³ C08F 16/38, 216/38


U.S. Cl. 526—316

5 Claims

1. A vinyl copolymer having acetylacetoxy groups, which contains units of formula (I)



and/or of formula (II)



in which R is a hydrogen atom or a methyl group, R^1 is a hydrogen atom or an alkyl group having 1, 2 or 3 carbon atoms, and R^2 is a hydrogen atom or a hydrocarbon radical having from 1 to 8 carbon atoms and optionally containing one or several oxygen atoms or a halogen atom.

4,296,227

CURABLE POLYETHER RESINS

Harold O. Seeburger; George J. Atchison, and Violette L. Stevens, all of Midland, Mich., assignors to The Dow Chemical Company, Midland, Mich.


Filed Jan. 31, 1980, Ser. No. 117,154

Int. Cl.³ C08G 65/32

U.S. Cl. 526—320


9 Claims

1. A curable polyether compound of theoretical molecular weight less than 60,000 of the formula XA_m wherein:
 X is the residue left by the removal of m active hydrogen atoms from an initiator compound XH_m ; and
 a is a moiety of the formula



where:

R is independently each occurrence selected from




$-CH_2-CH=CH_2$ and hydrogen;


R' is independently each occurrence selected from hydrogen, halogen C_{1-4} alkyl or haloalkyl and phenyl;

R'' is independently each occurrence a chain-terminating moiety selected from R, tertiary butyl, hydrogen, and a

saturated or unsaturated ester functionality, or a chain-propagating moiety of the formula



and y and n are numbers from zero to 500 provided that in at least one occurrence of A n is at least one, and further provided that in at least one occurrence of A, R or R'' is



or $-CH_2-CH=CH_2$.

7. A curable mixture comprising Component (a) a compound of claim 1, and Component (b) an unsaturated reactive compound capable of curing with the compound of claim 1.

4,296,228

ROOM TEMPERATURE CURABLE COMPOSITIONS
 Ernst Innertsberger; Oswin Sommer; Erhard Bosch; Johann Müller, all of Burghausen, and August Schiller, Markt, all of Fed. Rep. of Germany, assignors to Wacker-Chemie GmbH, Munich, Fed. Rep. of Germany

Filed Mar. 3, 1980, Ser. No. 126,230

Claims priority, application Fed. Rep. of Germany, Mar. 22, 1979, 2911301

Int. Cl.³ C08G 77/04

U.S. Cl. 528—33

10 Claims

1. A curable composition which is stable under anhydrous conditions but when exposed to moisture at room temperature, cures to an elastomer comprising a diorganopolysiloxane having terminal condensable groups and a silicon compound containing acetoxy, tert-butoxy and SiC-bonded alkyl groups, in which at least a portion of the silicon compound containing acetoxy, tert-butoxy and SiC-bonded alkyl groups is obtained from the reaction of an alkyltriacetoxysilane with tert-butanol in the presence of aqueous acetic acid.

4,296,229

HOT-MELT POLYESTERIMIDE-POLYISOCYANATE ELECTRICAL COATING COMPOSITIONS

Denis R. Pauze, Scotia, and Otto S. Zamek, Schenectady, both of N.Y., assignors to General Electric Company, Schenectady, N.Y.

Filed May 30, 1980, Ser. No. 154,838

Int. Cl.³ C08G 18/80, 18/42; C08F 283/04

U.S. Cl. 528—45

6 Claims

1. A composition for hot-melt electrical wire coating comprising:
 a high solids content resinous polyester-imide-polyisocyanate reaction product obtained by heating ingredients comprising:
 (a) an aromatic diamine;
 (b) an aromatic carboxylic anhydride containing at least one additional carboxylic group;
 (c) terephthalic acid or a reactive derivative thereof;
 (d) a polyhydric alcohol having at least three hydroxyl groups;
 (e) an alkylene glycol; and a small amount of
 (f)(i) an alkylene glycol monoether or monoester;
 (ii) a polyalkylene glycol monoether or monoester; or
 (iii) a mixture of (i) and (ii),
 until an acid number of lower than 6 to 7 is attained, and adding to the hot reaction product a blocked polyisocyanate in an

amount of 1 to 40 parts by weight per 100 parts by weight of the polyesterimide and blocked polyisocyanate.

4,296,230

POLYURETHANE COATINGS PRODUCED FROM (1) A POLYISOCYANATE MIXTURE OF POLYISOCYANATES FROM THE DIPHENOL METHANE SERIES AND A POLYHYDROXY POLYETHER CONTAINING AT LEAST ONE TERTIARY AMINE NITROGEN WITH (2) A POLYOL IN A TWO COMPONENT COATING SYSTEM
Jösel Pedain, Cologne; Walter Uerdingen, Bergisch-Gladbach, and Hans-Jürgen Müller, Cologne, all of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Continuation of Ser. No. 747,568, Dec. 6, 1976, abandoned. This application Aug. 30, 1978, Ser. No. 938,165

Claims priority, application Fed. Rep. of Germany, Dec. 10, 1975, 2555535

Int. Cl.³ C08G 18/76

U.S. Cl. 528—67

15 Claims

1. A process for the production of coatings by coating substrates of any type with a coating composition of which the binder consists essentially of a mixture of:

- a polyisocyanate component and
- at least one organic polyhydroxyl compound, wherein the polyisocyanate component (a) is a reaction product obtained from:
 - a polyisocyanate mixture which, in addition to from about 20 to 80%, by weight, of 2,4'-diisocyanato diphenyl methane, contains a total of from about 80 to 20%, by weight of 2,2'-diisocyanato diphenyl methane, 4,4'-diisocyanato diphenyl methane, and optionally, higher nuclear polyisocyanates of the diphenyl methane series, and
 - a polyhydroxy polyether containing at least one tertiary amine nitrogen atom and having an average molecular weight of from about 500 to 10,000 or a polyhydroxy polyether mixture containing at least one such polyhydroxy polyether and having an average molecular weight of from about 500 to 10,000, components (i) and (ii) having been reacted in an NCO:OH equivalent ratio of from about 300:1 to 10:1 to form a reaction product containing free isocyanate groups and urethane groups.

4,296,231

CURABLE EPOXIDE RESIN MIXTURES

Ferdinand Gutekunst, Riehen, and Rolf Schmid, Gelterkinden, both of Switzerland, assignors to Ciba-Geigy Corporation, Ardsley, N.Y.

Filed May 1, 1980, Ser. No. 145,406


Claims priority, application Switzerland, May 8, 1979, 4307/79

Int. Cl.³ C08G 59/64


U.S. Cl. 528—93

10 Claims

1. A curable mixture comprising a polyepoxide compound having on average more than one epoxide group in the molecule, and optionally a polycarboxylic acid, an anhydride or a polyhydric phenol as the curing agent, the said mixture additionally containing a compound of the formula I



in which m is a number from 3 to 10, X is a group of the formula



in which R is an alkyl having 4 to 10 C atoms or a phenyl

which is unsubstituted or substituted by chlorine, bromine or alkyl or alkoxy each having 1 to 3 C atoms, and Y is a hydrogen atom or has the meaning defined for X, as the curing catalyst or as the curing accelerator for curing the epoxide compound with di- or poly-carboxylic acids or anhydrides of di- or poly-carboxylic acids or with polyhydric phenols.

4,296,232

PROCESS FOR PREPARING POLYARYLATES IN THE PRESENCE OF A DIPHENYL ETHER COMPOUND AND A CATALYST

Louis M. Maresca, Belle Mead; Peter J. Gill, North Brunswick, and Mitchell H. Berger, Somerville, all of N.J., assignors to Union Carbide Corporation, New York, N.Y.

Filed Aug. 27, 1979, Ser. No. 70,039


Int. Cl.³ C08G 63/18, 63/28, 63/30, 63/66

U.S. Cl. 528—179

19 Claims

1. A process for preparing a polyarylate having a reduced viscosity of from about 0.5 to greater than 1.0 dl/gm, which process comprises reacting:

- at least one diester derivative of a dihydric phenol having the following formula:



wherein R is independently selected from an alkyl radical having from 1 to about 6 carbon atoms or cycloalkyl having from 4 to about 7 carbon atoms, y is independently selected from alkyl groups of 1 to 4 carbon atoms, chlorine, or bromine, z independently has a value of from 0 to 4, inclusive, and R' is independently selected from a divalent saturated aliphatic hydrocarbon radical having 1 to 8 carbon atoms, a cycloalkylene, or cycloalkylidene radical having up to and including 9 carbon atoms, O S, SO, SO₂, CO, x is 0 or 1; with

- at least one aromatic dicarboxylic acid, in the presence of from about 10 to about 60 weight percent, based on the polyarylate produced, of a diphenyl ether compound, at a temperature of from about 260° to about 350° C. and in the presence of a catalytically effective amount of a magnesium catalyst.

4,296,233

CONJUGATE OF AMINO SUGAR-STEROID HORMONE
Satoru Enomoto, Fujisawa; Kiro Asano, Kikizaki, and Hiro-mitsu Tanaka, Tokyo, all of Japan, assignors to Kureha Kagaku Kogyo Kabushiki Kaisha, Tokyo, Japan

Filed Mar. 29, 1979, Ser. No. 25,073


Claims priority, application Japan, Apr. 14, 1978, 53-44034

Int. Cl.³ C07J 17/00

U.S. Cl. 536—5

5 Claims

1. A conjugate of an amino sugar and a steroid hormone having the formula:



wherein R₁C is a radical of a carboxyl group containing amino sugar selected from the group consisting of 2-amino-2-deoxy-glucuronic acid, 2-amino-2-deoxy-3-O-(1-carboxyethyl) D-glucose and 2-amino-2-deoxy-3-O-β-D-glucopyranosyl-D-galactose; R₂ is a radical of a steroid hormone selected from the group consisting of 17β-hydroxy-4-androsten-3-one; 3β-hydroxy-5-androsten-17-one; 1,3,5 (10)-estratriene-3,17 β-diol; 5β-pregnane-3α, 20α-diol; 4-pregnene-3, 20-dione; 11β, 17α, 21-trihydroxy-4-pregnene-3, 20-dione; 11β, 21-dihydroxy-4-

pregnene-3,20-dione; prednisone; desoxymethasone, mestanolone; androstanolone; unsodeoxycholic acid methanediene; β-sitosterol and Alphaxalone, the bonding between said amino sugar radical and said steroid hormone radical occurring only at the 3 or 17 position of said steroid radical; m is 0 or 1 and n is 1 or 2.

4,296,234

ABSORBENT MATERIALS

Lothar F. O. Mindt, deceased, late of Upper Dean, England; by Peter R. Payne, administrator, and George R. Sanderson, both of Bedford, England, assignors to Lever Brothers Company, New York, N.Y.

Continuation of Ser. No. 960,423, Nov. 13, 1978, abandoned, and a continuation of Ser. No. 766,524, Feb. 7, 1977, abandoned. This application Apr. 23, 1980, Ser. No. 142,908

Claims priority, application United Kingdom, Dec. 19, 1973, 58917/73; Dec. 19, 1973, 58918/73; Jul. 17, 1974, 31672/74

Int. Cl.³ A61L 15/00; C08B 31/00

U.S. Cl. 536—47

43 Claims

1. A highly absorbent material which is substantially dry and non-sticky to the touch in the swollen state being a substantially water-insoluble cross-linked gelatinised starch, in which the degree of substitution of the cross-linking groups is 0.001 to 0.02, which is substituted by ionic groups which are attached to the starch by ether linkages and which groups are associated with counterions selected from mono- and divalent counterions, and which has a urine retention value of at least 8 g/g.

4,296,235

PROCESS FOR THE REMOVAL OF ALKALI METAL HALIDES FROM CELLULOSE ETHERS SOLUBLE IN COLD WATER AND USE OF THE PURIFIED PRODUCTS IN WASHING AND CLEANSING AGENT COMPOSITIONS

Horst Ziche, Dusseldorf, Fed. Rep. of Germany, assignor to Henkel Kommanditgesellschaft Auf Aktien, Dusseldorf-Holthausen, Fed. Rep. of Germany

Filed Mar. 3, 1980, Ser. No. 126,901

Claims priority, application Fed. Rep. of Germany, Mar. 29, 1979, 2912486

Int. Cl.³ C08B 11/20, 11/22

U.S. Cl. 536—85

5 Claims

1. A process for the purification of cold-water soluble cellulose ethers containing alkali metal halides consisting essentially of suspending a cold-water-soluble cellulose ether crude reaction product containing 25% by weight or more of alkali metal halides, based on the dry weight, where said cellulose ethers are selected from the group consisting of methyl cellulose, ethyl cellulose, mixed methyl/ethyl cellulose, mixed ethyl/hydroxyethyl cellulose, mixed ethyl/hydroxypropyl cellulose and mixed ethyl/dihydroxypropyl cellulose, in an aqueous solution containing from 4% to about 25% by weight of one or more water-soluble salts selected from the group consisting of alkali metal sulfates, alkali metal phosphates, alkali metal silicates and alkali metal carbonates, with agitation at a temperature of from 10° C. to 50° C., separating the purified cellulose ether solids and repeating the suspending and separating steps zero, one or more times.

4,296,236

7-(OR 6-) SUBSTITUTED-7-(OR 6-)ACYLIMINO CEPHALOSPORIN (OR PENICILLIN) COMPOUNDS

Burton G. Christensen, Scotch Plains; David B. R. Johnston, Warren, and Raymond A. Firestone, Fanwood, all of N.J., assignors to Merck & Co., Inc., Rahway, N.J.

Division of Ser. No. 243,057, Apr. 11, 1972, Pat. No. 3,875,146.

This application Jan. 9, 1975, Ser. No. 539,881


Claims priority, application United Kingdom, Apr. 30, 1971, 13008/71; Sep. 1, 1971, 40813/71; Sep. 1, 1971, 40814/71; Nov. 29, 1971, 55232/71.

Int. Cl.³ C07D 499/02, 501/14

U.S. Cl. 542—420

7 Claims

1. The compound having the formula:



wherein M is benzyl, benzhydryl, trichloroethyl, methoxybenzyl; A is hydrogen, acetoxy, or pyridinium; each of G, K, and J are hydrogen, halo, or nitro; and R₁ is loweralkylthio.

4,296,237

4-(PYRIDYL, PIPERAZINYL AND THIAZOLYL) SUBSTITUTED THIAZOLYL-3-HYDROXY-3-PYRROLINE-2,5-DIONES

Edward J. Cragoe, Jr., Lansdale; Clarence S. Rooney, Worcester, both of Pa., assignor to Merck & Co., Inc., Rahway, N.J.


Filed Sep. 11, 1979, Ser. No. 74,466

Int. Cl.³ C07D 417/14; A61K 31/425, 31/44, 31/495


U.S. Cl. 544—405

5 Claims


1. The compounds having the structure:




2. The compound having the structure:




3. The compound having the structure:



4. The compound having the structure:



5. The compound having the structure:



4,296,238

2,6-METHANO-3-BENZAZOCINES


William F. Michne, Poestenkill, N.Y., assignor to Sterling Drug Inc., New York, N.Y.

Division of Ser. No. 9,594, Feb. 5, 1979, Pat. No. 4,255,579, which is a continuation-in-part of Ser. No. 877,166, Feb. 13, 1978, Pat. No. 4,180,667, which is a continuation-in-part of Ser. No. 741,227, Nov. 12, 1976, Pat. No. 4,100,164, which is a continuation-in-part of Ser. No. 695,977, Jun. 14, 1976, abandoned, which is a continuation-in-part of Ser. No. 576,313, May 12, 1975, abandoned, which is a continuation-in-part of Ser. No. 471,571, May 20, 1975, Pat. No. 3,932,422. This application May 7, 1980, Ser. No. 147,084

Int. Cl.³ C07D 221/26


U.S. Cl. 546-97

1. A compound having the formula




21 Claims

where R₁ is hydrogen, lower-alkyl, lower-alkanoyl (only when R₄ is hydrogen), lower-alkenyl, lower-alkynyl, halo-lower-alkenyl, cyclo-lower-alkyl, cyclo-lower-alkyl-lower-alkyl, 2- or 3-furylmethyl, or such 2- or 3-furylmethyl substituted on the unsubstituted ring carbon atoms by from one to three methyl groups, phenyl-lower-alkyl, or phenyl-lower-alkyl substituted in the phenyl ring by from one or two members of the group consisting of halogen, lower-alkyl, hydroxy, lower-alkanoyloxy, lower-alkoxy, lower-alkylmercapto, trifluoromethyl, amino, lower-alkanoylamino or a single methylenedioxy attached to adjacent carbon atoms; R₂, R₂', R₂'', and R₂''' are each hydrogen, or three of them are hydrogen and the fourth is halogen, lower-alkyl, hydroxy, lower-alkanoyloxy, lower-alkoxy, lower-alkylmercapto, trifluoromethyl, nitro, amino, lower-alkanoylamino, lower-alkoxycarbonylamino or phenyl, or two of the adjacent such groups together are methylenedioxy; R₃ is hydrogen or lower-alkyl; R₄ is hydrogen, lower-alkyl, lower-alkoxy-lower-alkyl, hydroxy-lower-alkyl, lower-alkylthio-lower-alkyl, lower-alkylsulfinyl-lower-alkyl, phenylthio-lower-alkyl, phenylsulfinyl-lower-alkyl, lower-alkenyl or halo-lower-alkyl, or R₃ and R₄ together are divalent lower-alkylene, —(CH₂)_n—, where n is one of the integers 3 or 4; and Z is the group



where either R₅ and R₆ are both lower-alkyl or one is hydrogen and the other is lower-alkyl, or a group of the formula



where R₅ and R₆ are the same or different hydrogen, lower-alkyl, cyclo-lower-alkyl-lower-alkyl, phenyl or phenyl-lower-alkyl; R₇ is hydrogen, lower-alkanoyl, benzoyl or benzoyl substituted by from one to three members of the group consisting of lower-alkyl, lower-alkoxy, hydroxy, halo or trifluoromethyl; and R₈ is hydrogen or lower-alkyl; or an acid-addition salt thereof.

4,296,239

AMINO-4H-S-TRIAZOLO[4,3-A][1,4]BENZODIAZEPINES

Jackson B. Hester, Jr., Galesburg, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.

Division of Ser. No. 804,627, Jun. 8, 1977, Pat. No. 4,180,668.


This application Jul. 30, 1979, Ser. No. 61,976

Int. Cl.³ C07D 211/68

U.S. Cl. 546-271

1. A compound of the formula

3 Claims



wherein

R is hydrogen, C₁ to C₃-alkyl or hydroxymethyl; R₁ is hydrogen or a halogen having an atomic number of from 9 to 35; and the two R₂ moieties are taken together with the nitrogen to which they are bonded to complete a 3,6-dihydro-1(2H)-pyridyl nitrogen ring moiety or a pharmacologically acceptable salt thereof.

4,296,240

SILACYCLOALKANE AMIDES

Robert E. Damon, II, Randolph, N.J., assignor to Sandoz, Inc., East Hanover, N.J.


Filed Apr. 24, 1980, Ser. No. 143,262

Int. Cl.³ C07F 7/10; C07D 209/10


U.S. Cl. 556-406

1. A compound of the formula:

14 Claims

wherein R¹ is either

- (a) alkyl having from 1 to 22 carbon atoms; or
(b) of the formula




in which

m is 0, 1 or 2, and each of R' and R'' is independently a hydrogen atom, alkyl having from 1 to 3 carbon atoms, alkoxy having from 1 to 3 carbon atoms, or halo having an atomic weight of from about 19 to 127;

R² and R³ are joined to form an acyclic hydrocarbon radical which together with the silicon atom forms a ring having from 3 to 20 ring members and having no more than 25 carbon atoms; and


R is of type (a) an aralkyl-type radical of the structure



wherein g is 0, 1 or 2;


R^a is a hydrogen atom, halo having an atomic weight of from about 19 to 127, alkoxy having from 1 to 4 carbon atoms, or alkyl having from 1 to 4 carbon atoms, or trifluoromethyl;

R^b is a hydrogen atom, alkyl having from 1 to 3 carbon atoms, alkoxy having from 1 to 3 carbon atoms, or halo having an atomic weight of from about 19 to 36; and R^c is subtype (i) a hydrogen atom; subtype (ii) a radical of the structure




in which p is 0, 1 or 2, and

y is a hydrogen atom, halo having an atomic weight of from about 19 to 127, alkoxy having from 1 to 4 carbon atoms, or alkyl having from 1 to 4 carbon atoms; and y' is a hydrogen atom, alkoxy having from 1 to 3 carbon atoms, alkyl having from 1 to 3 carbon atoms, or halo having an atomic weight of from about 19 to 36; or subtype (iii) alkyl having from 1 to 8 carbon atoms; or R is of type (b) a phenyl-type radical of the structure



in which

R^b is as defined above, and R^o is a hydrogen atom, halo having an atomic weight of from about 19 to 127, ie. alkoxy having from 1 to 4 carbon atoms, or alkyl having from 1 to 4 carbon atoms; or R^o is a radical of the structure R^o:




in which

D is —CH₂— or —O—;

f is 0 or 1; and

W is a hydrogen atom, halo having an atomic weight of from about 19 to 80, alkoxy having from 1 to 3 carbon atoms, or alkyl having from 1 to 3 carbon atoms; or

R is of type (c) an indolyl radical of the structure:




(c)

wherein

R^b is as defined above;

R⁴ is alkyl having from 1 to 8 carbon atoms or benzyl; and R⁵ is a hydrogen atom, alkyl having from 1 to 8 carbon atoms or benzyl; or

R is (d) a benzocycloalkyl nucleus of the structure:




(d)

wherein

y and y' are as defined above; and j is a whole integer of from 1 to 4.

14. A compound of the formula:




(ii)

wherein

R¹ is either

- (a) alkyl having from 1 to 22 carbon atoms; or
(b) of the formula




in which

m is 0, 1 or 2, and each of R' and R'' is independently a hydrogen atom, alkyl having from 1 to 3 carbon atoms, alkoxy having from 1 to 3 carbon atoms, or halo having an atomic weight of from about 19 to 127;

R² and R³ are joined to form an acyclic hydrocarbon radical which together with the silicon atom form a ring having from 3 to 20 ring members and having no more than 25 carbon atoms; and

R is of type (a) an aralkyl-type radical of the structure




(a)

wherein

g is 0, 1 or 2;


R^a is a hydrogen atom, halo having an atomic weight of from about 19 to 127, alkoxy having from 1 to 4 carbon atoms, or alkyl having from 1 to 4 carbon atoms, or trifluoromethyl;

R^b is a hydrogen atom, alkyl having from 1 to 3 carbon atoms, alkoxy having from 1 to 3 carbon atoms, or halo having an atomic weight of from about 19 to 36; and R^c is subtype (i) a hydrogen atom; subtype (ii) a radical of the structure




in which

p is 0, 1 or 2, and y is a hydrogen atom, halo having an atomic weight of from about 19 to 127, alkoxy having from 1 to 4 carbon atoms, or alkyl having from 1 to 4 carbon atoms; and y' is a hydrogen atom, alkoxy having from 1 to 3 carbon atoms, alkyl having from 1 to 3 carbon atoms, or halo having an atomic weight of from about 19 to 36; or subtype (iii) alkyl having from 1 to 8 carbon atoms; or R is of type (b) a phenyl-type radical of the structure




in which

R^b is as defined above, and R^o is a hydrogen atom, halo having an atomic weight of from about 19 to 127, ie. alkoxy having from 1 to 4 carbon atoms, or alkyl having from 1 to 4 carbon atoms; or R^o is a radical of the structure R^f :




in which

D is $-\text{CH}_2-$ or $-\text{O}-$; f is 0 or 1; and W is a hydrogen atom, halo having an atomic weight of from about 19 to 80, alkoxy having from 1 to 3 carbon atoms, or alkyl having from 1 to 3 carbon atoms; or R is of type (c) an indolyl radical of the structure:



wherein

R^b is as defined above; R^4 is alkyl having from 1 to 8 carbon atoms or benzyl; and R^5 is a hydrogen atom, alkyl having from 1 to 8 carbon atoms or benzyl; or R is (d) a benzocycloalkyl nucleus of the structure:



wherein

y and y' are as defined above; and j is a whole integer of from 1 to 4.

4,296,241

PREPARATION OF

3-(2,2-DICHLOROVINYL)-2,2-DIMETHYL-CYCLOPROPANE-1-CARBOXYLIC ACID DERIVATIVES
Hellmut Hoffmann; Fritz Maurer, both of Wuppertal; Uwe Priesnitz, Unna-Massen, and Hans-Jochem Riebel, Wuppertal, all of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany
Filed Jul. 2, 1980, Ser. No. 165,871


Claims priority, application Fed. Rep. of Germany, Jul. 21, 1979, 2929725; Mar. 11, 1980, 3009242

Int. Cl.³ C07C 69/743

U.S. Cl. 560—124

9 Claims


1. A process for the preparation of a 3-(2,2-dichlorovinyl)-2,2-dimethyl-cyclopropane-1-carboxylic acid or derivative of the formula




(b)

in which R is hydrogen, sodium, potassium or alkyl with 1 to 4 carbon atoms,

comprising reacting a 3-formyl-2,2-dimethyl-cyclopropane-1-carboxylic acid or a derivative of the formula



with a dichloromethane derivative of the formula



in which R^1 and R^2 each independently is alkyl, phenyl, alkoxy or phenoxy, or together are alkanediyl or alkanedioxy,

(c) in the presence of a base at a temperature between about -50° and $+50^\circ$ C.

4,296,242

PROCESS FOR THE PREPARATION OF CHIRAL 3-AMINO-2-HYDROXYPROPIONIC ACID AND N-BLOCKED DERIVATIVES THEREOF

Tattanahalli L. Nagabhushan, Parsippany, and Alan Cooper, West Caldwell, both of N.J., assignors to Schering Corporation, Kenilworth, N.J.

Filed Jun. 6, 1979, Ser. No. 46,076

Int. Cl.³ C07C 101/30

U.S. Cl. 560—160

7 Claims

1. The process of preparing chiral 3-amino-2-hydroxypropionic acid which comprises subjecting a glycamine in an aqueous lower alkanol medium to the successive steps of

- cyclic 1,2-N,O-carbonylation with alkoxycarbonyl chloride, phenoxycarbonyl chloride, or p-nitrophenoxycarbonyl chloride to produce the corresponding chiral 1,2-N,O-carbonyl glycamine,
- periodic cleavage, and (c) permanganate oxidation to produce chiral 2,3-N,O-carboxylisoserine,

- acid hydrolysis to produce an acid addition salt of chiral isoserine, followed by
- treatment with base to neutralize the acid addition salt to produce chiral isoserine.

4,296,243

PROCESS FOR PRODUCING SORBIC ACID OR ITS DERIVATIVES

Kazuo Sato, Arai, Japan, assignor to Daicel Ltd., Osaka, Japan
Filed Jul. 27, 1979, Ser. No. 61,780


Claims priority, application Japan, Aug. 3, 1978, 53-95186

Int. Cl.³ C07C 51/09, 57/10, 67/08, 69/587

U.S. Cl. 560—210

7 Claims

1. In a process for producing sorbic acid and its alkali salts in the presence of a catalyst to form a polyester and heat-decomposing or hydrolyzing the resulting polyester addition product, the improvement wherein the catalyst in the polyester synthesizing step comprises a zinc salt of an aliphatic carboxylic acid and only one of a phosphine or a pyridine, wherein said carboxylic acid is a saturated or unsaturated carboxylic acid having at least 2 carbon atoms, said phosphine is represented by the formula $R_1R_2R_3P$ in which each of R_1 , R_2 and R_3 represents an alkyl or aryl group, and said pyridine is represented by the formula:



in which each of R_4 , R_5 , R_6 , R_7 and R_8 represents a hydrogen atom or a lower alkyl group and wherein the amount of the zinc salt of the aliphatic carboxylic acid is about 0.1 to 5.0% by weight based on the crotonaldehyde, the amount of the phosphine is about 0.3 to 1.0 mol per mol of the zinc salt of the aliphatic carboxylic acid and the amount of the pyridine is about 0.5 to 3.0 mols per mol of the zinc salt of the aliphatic carboxylic acid.

4,296,244

(3-TRIFLUOROMETHYLPHENYL)-ALPHA-HYDROXYACETIC ACID AND PROCESS FOR PREPARATION

David Y. Tang, Eggertsville, and Arthur M. Foster, Snyder, both of N.Y., assignors to Hooker Chemicals & Plastics Corp., Niagara Falls, N.Y.

Filed Nov. 7, 1979, Ser. No. 92,118

Int. Cl.³ C07C 59/84

U.S. Cl. 562—470

6 Claims

1. (3-trifluoromethylphenyl)-alpha-hydroxyacetic acid.

4,296,245

METHOD FOR THE PREPARATION OF A PURE ALKALI METAL BENZOATE AND BENZYL ALCOHOL

Cornelis Jongasma, Oirsbeek; Leon H. B. Frijns, Valkenburg, and Paula A. M. Raven-Donners, Sittard, all of Netherlands, assignors to Stamicarbon, B.V., Geleen, Netherlands

Filed May 16, 1980, Ser. No. 150,690

Claims priority, application Netherlands, May 17, 1979, 7903878

Int. Cl.³ C07C 51/42, 27/04

U.S. Cl. 562—494

26 Claims

1. A method for the preparation of a food-grade pure alkali metal benzoate from crude benzyl benzoate, obtained by the oxidation of an alkylbenzene compound with a gas containing molecular oxygen, wherein said crude material is subjected to treatment with a reducing substance,

selected from the class of (a) hydrogen or (b) the metals with reducing properties in groups IA, IIA, IIB, IIIA, IVA, VIIB, and VIII of the periodic system in the presence of

water, to convert impurities therein to alkaline-aqueous soluble components without substantial conversion of any benzyl benzoate, and subsequently saponifying said benzoate to obtain said food-grade pure alkali metal benzoate.

4,296,246

13,14-DIDEHYDRO-11-DEOXY-11-HYDROXYMETHYL-19-OXO-PGF₁ COMPOUNDS

John C. Sih, Kalamazoo, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.


Division of Ser. No. 25,879, Apr. 2, 1979. This application Mar. 20, 1980, Ser. No. 131,970

Int. Cl.³ C07C 177/00

U.S. Cl. 562—503

4 Claims

1. A compound of the formula



wherein D is

(1) $(\text{CH}_2)_3-(\text{CH}_2)_g-\text{CH}_2-$, or

(2) $(\text{CH}_2)_3-(\text{CH}_2)_g-\text{CF}_2-$;

wherein g is zero, one, two, or three;

wherein Q is $\alpha\text{-OH}:\beta\text{-R}_5$ or $\alpha\text{-R}_5:\beta\text{-OH}$, wherein R_5 is hydrogen or methyl;

wherein R_6 is

(a) hydrogen,

(b) alkyl of one to 12 carbon atoms, inclusive,

(c) cycloalkyl of 3 to 10 carbon atoms, inclusive,

(d) aralkyl of 7 to 12 carbon atoms, inclusive,

(e) phenyl,

(f) phenyl substituted with one, 2, or 3 chloro or alkyl groups of one to 3 carbon atoms, inclusive,

(g) $-(p\text{-Ph})-\text{CO}-\text{CH}_3$,

(h) $-(p\text{-Ph})-\text{NH}-\text{CO}-(p\text{-Ph})-\text{NH}-\text{CO}-\text{CH}_3$,

(i) $-(p\text{-Ph})-\text{NH}-\text{CO}-(p\text{-Ph})$,

(j) $-(p\text{-Ph})-\text{NH}-\text{CO}-\text{CH}_3$,

(k) $-(p\text{-Ph})-\text{NH}-\text{CO}-\text{NH}_2$,

(l) $-(p\text{-Ph})-\text{CH}=\text{N}-\text{NH}-\text{CO}-\text{NH}_2$,

(m) β -naphthyl,

(n) $-\text{CH}_2-\text{CO}-\text{R}_{28}$,

wherein (p-Ph) is para-phenyl or inter-para phenylene, wherein R_{28} is phenyl, p-bromophenyl, p-biphenyl, p-nitrophenyl, p-benzamidophenyl, or 2-naphthyl, or

(o) a pharmacologically acceptable cation; wherein R_3 and R_4 are hydrogen, methyl, or fluoro, being the same or different, with the proviso that one of R_3 and R_4 is fluoro only when the other is hydrogen or fluoro; and

wherein X is $-\text{C}=\text{C}-$.

4,296,247

13,14-DIHYDRO-11-DEOXY-11-HYDROXYMETHYL-9-DEOXY-9-METHYLENE-19-OXO-PGF₁ COMPOUNDS

John C. Sih, Kalamazoo, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.


Division of Ser. No. 25,879, Apr. 2, 1979. This application Mar. 20, 1980, Ser. No. 132,008

Int. Cl.³ C07C 177/00

U.S. Cl. 562—503

4 Claims

1. A compound of the formula



wherein D is

- (1) $(CH_2)_3-(CH_2)_g-CH_2-$, or
 - (2) $(CH_2)_3-(CH_2)_g-CF_2-$;
- wherein g is zero, one, two, or three;
 wherein Q is $\alpha-OH:\beta-R_5$ or $\alpha-R_5:\beta-OH$, wherein R_5 is hydrogen or methyl;
 wherein R_6 is
- (a) hydrogen,
 - (b) alkyl of one to 12 carbon atoms, inclusive,
 - (c) cycloalkyl of 3 to 10 carbon atoms, inclusive,
 - (d) aralkyl of 7 to 12 carbon atoms, inclusive,
 - (e) phenyl,
 - (f) phenyl substituted with one, 2, or 3 chloro or alkyl groups of one to 3 carbon atoms, inclusive,
 - (g) $-(p-Ph)-CO-CH_3$,
 - (h) $-(p-Ph)-NH-CO-(p-Ph)-NH-CO-CH_3$,
 - (i) $-(p-Ph)-NH-CO-(p-Ph)$,
 - (j) $-(p-Ph)-NH-CO-CH_3$,
 - (k) $-(p-Ph)-NH-CO-NH_2$,
 - (l) $-(p-Ph)-CH=N-NH-CO-NH_2$,
 - (m) β -naphthyl,
 - (n) $-CH_2-CO-R_{28}$,
- wherein (p-Ph) is para-phenyl or inter-para-phenylene, wherein R_{28} is phenyl, p-bromophenyl, p-biphenyl, p-nitrophenyl, p-benzamidophenyl, or 2-naphthyl, or
- (o) a pharmacologically acceptable cation;
- wherein R_3 and R_4 are hydrogen, methyl, or fluoro, being the same or different, with the proviso that one of R_3 and R_4 is fluoro only when the other is hydrogen or fluoro; and wherein X is $-CH_2CH_2-$.

4,296,248


13,14-DIHYDRO-11-DEOXY-11-HYDROXYMETHYL-19-OXO-PGE₁ COMPOUNDS

John C. Sih, Kalamazoo, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.
 Division of Ser. No. 25,879, Apr. 2, 1979. This application Mar. 20, 1980, Ser. No. 132,009
 Int. Cl.³ C07C 177/00

U.S. Cl. 562-503

4 Claims

1. A compound of the formula



wherein D is

- (1) $(CH_2)_3-(CH_2)_g-CH_2-$, or
 - (2) $(CH_2)_3-(CH_2)_g-CF_2-$;
- wherein g is zero, one, two, or three;
 wherein Q is $\alpha-OH:\beta-R_5$ or $\alpha-R_5:\beta-OH$, wherein R_5 is hydrogen or methyl;
 wherein R_6 is
- (a) hydrogen,
 - (b) alkyl of one to 12 carbon atoms, inclusive,
 - (c) cycloalkyl of 3 to 10 carbon atoms, inclusive,
 - (d) aralkyl of 7 to 12 carbon atoms, inclusive,
 - (e) phenyl,

- (f) phenyl substituted with one, 2, or 3 chloro or alkyl groups of one to 3 carbon atoms, inclusive,
- (g) $-(p-Ph)-CO-CH_3$,
- (h) $-(p-Ph)-NH-CO-(p-Ph)-NH-CO-CH_3$,
- (i) $-(p-Ph)-NH-CO-(p-Ph)$,
- (j) $-(p-Ph)-NH-CO-CH_3$,
- (k) $-(p-Ph)-NH-CO-NH_2$,
- (l) $-(p-Ph)-CH=N-NH-CO-NH_2$,
- (m) β -naphthyl,
- (n) $-CH_2-CO-R_{28}$,

wherein (p-Ph) is para-phenyl or inter-para-phenylene, wherein R_{28} is phenyl, p-bromophenyl, p-biphenyl, p-nitrophenyl, p-benzamidophenyl, or 2-naphthyl, or

- (o) a pharmacologically acceptable cation;

wherein R_3 or R_4 are hydrogen, methyl, or fluoro, being the same or different, with the proviso that one of R_3 and R_4 is fluoro only when the other is hydrogen or fluoro; and wherein X is $-CH_2CH_2-$.

4,296,249


13,14-DIHYDRO-11-DEOXY-9-DEOXY-9-METHYLENE-19-OXO-PGE₁ COMPOUNDS

John C. Sih, Kalamazoo, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.
 Division of Ser. No. 25,879, Apr. 2, 1979. This application Mar. 20, 1980, Ser. No. 132,029
 Int. Cl.³ C07C 177/00

U.S. Cl. 562-503

4 Claims

1. A compound of the formula



wherein D is

- (1) $(CH_2)_3-(CH_2)_g-CH_2-$, or
 - (2) $(CH_2)_3-(CH_2)_g-CF_2-$;
- wherein g is zero, one, two, or three;
 wherein Q is $\alpha-OH:\beta-R_5$ or $\alpha-R_5:\beta-OH$, wherein R_5 is hydrogen or methyl;
 wherein R_6 is
- (a) hydrogen,
 - (b) alkyl of one to 12 carbon atoms, inclusive,
 - (c) cycloalkyl of 3 to 10 carbon atoms, inclusive,
 - (d) aralkyl of 7 to 12 carbon atoms, inclusive,
 - (e) phenyl,
 - (f) phenyl substituted with one, 2, or 3 chloro or alkyl groups of one to 3 carbon atoms, inclusive,
 - (g) $-(p-Ph)-CO-CH_3$,
 - (h) $-(p-Ph)-NH-CO-(p-Ph)-NH-CO-CH_3$,
 - (i) $-(p-Ph)-NH-CO-(p-Ph)$,
 - (j) $-(p-Ph)-NH-CO-CH_3$,
 - (k) $-(p-Ph)-NH-CO-NH_2$,
 - (l) $-(p-Ph)-CH=N-NH-CO-NH_2$,
 - (m) β -naphthyl,
 - (n) $-CH_2-CO-R_{28}$,

wherein (p-Ph) is para-phenyl or inter-para-phenylene, wherein R_{28} is phenyl, p-bromophenyl, p-biphenyl, p-nitrophenyl, p-benzamidophenyl, or 2-naphthyl, or

- (o) a pharmacologically acceptable cation;

wherein R_3 and R_4 are hydrogen, methyl, or fluoro, being the same or different, with the proviso that one of R_3 and R_4 is fluoro only when the other is hydrogen or fluoro; and wherein X is $-CH_2CH_2-$.

4,296,250


13,14-DIHYDRO-9-DEOXY-9-METHYLENE-19-OXO-PGE₁ COMPOUNDS

John C. Sih, Kalamazoo, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.
 Division of Ser. No. 25,879, Apr. 2, 1979. This application Mar. 20, 1980, Ser. No. 132,039
 Int. Cl.³ C07C 177/00

U.S. Cl. 562-503

4 Claims

1. A compound of the formula



wherein D is

- (1) $(CH_2)_3-(CH_2)_g-CH_2-$, or
 - (2) $(CH_2)_3-(CH_2)_g-CF_2-$;
- wherein g is zero, one, two, or three;
 wherein Q is $\alpha-OH:\beta-R_5$ or $\alpha-R_5:\beta-OH$, wherein R_5 is hydrogen or methyl;
 wherein R_6 is
- (a) hydrogen,
 - (b) alkyl of one to 12 carbon atoms, inclusive,
 - (c) cycloalkyl of 3 to 10 carbon atoms, inclusive,
 - (d) aralkyl of 7 to 12 carbon atoms, inclusive,
 - (e) phenyl,
 - (f) phenyl substituted with one, 2, or 3 chloro or alkyl groups of one to 3 carbon atoms, inclusive,
 - (g) $-(p-Ph)-CO-CH_3$,
 - (h) $-(p-Ph)-NH-CO-(p-Ph)-NH-CO-CH_3$,
 - (i) $-(p-Ph)-NH-CO-(p-Ph)$,
 - (j) $-(p-Ph)-NH-CO-CH_3$,
 - (k) $-(p-Ph)-NH-CO-NH_2$,
 - (l) $-(p-Ph)-CH=N-NH-CO-NH_2$,
 - (m) β -naphthyl,
 - (n) $-CH_2-CO-R_{28}$,
- wherein (p-Ph) is para-phenyl or inter-para-phenylene, wherein R_{28} is phenyl, p-bromophenyl, p-biphenyl, p-nitrophenyl, p-benzamidophenyl, or 2-naphthyl, or
- (o) a pharmacologically acceptable cation;
- wherein R_3 and R_4 are hydrogen, methyl, or fluoro, being the same or different, with the proviso that one of R_3 and R_4 is fluoro only when the other is hydrogen or fluoro; and wherein X is $-CH_2CH_2-$.

4,296,251

SYNTHESIS OF (+)-CIS-HOMOCARONIC ACID

T. L. Ho; Zia U. Din, and Carlos G. Cardenas, all of Jacksonville, Fla., assignors to SCM Corporation, New York, N.Y.
 Filed May 15, 1980, Ser. No. 150,197
 Int. Cl.³ C07C 51/34


U.S. Cl. 562-506

7 Claims

1. A process for producing (+)-cis-homocaronic acid from 2-carene-4-ol, 2-carene-4-one, 3-carene-2-ol, or mixtures thereof comprising the steps of:
 ozonizing the reactants,
 treating the ozonides produced with hydrogen peroxide and recovering (+)-cis-homocaronic acid.

4,296,252
 UREA SYNTHESIS PROCESS
 Ivo Mavrovic, 530 E. 72nd St., New York, N.Y. 10021
 Filed May 23, 1980, Ser. No. 152,534
 Int. Cl.³ C07C 126/02

3 Claims



1. In a cyclic process for producing urea comprising reacting CO_2 and NH_3 in the presence of an aqueous ammoniacal solution of at least one compound selected from the group consisting of ammonium carbonate and/or ammonium carbamate in a urea synthesis reactor at an elevated temperature of about 330° F. to about 400° F. and at a pressure from about 1,800 PSIG to about 6,000 PSIG, to form a urea synthesis reactor effluent fluid at high pressure, lowering the pressure of said reactor effluent fluid to flash off gaseous NH_3 , CO_2 and H_2O phase to obtain a residual reactor effluent solution comprising ammonium carbamate, ammonia, water and urea, recycling at least part of said flashed off gaseous NH_3 , CO_2 and H_2O phase to the urea reactor, passing said residual reactor effluent solution to a carbamate decomposer wherein it is heated and wherein the ammonia and water vapor contained in said effluent solution is taken off in a gaseous product and wherein the ammonium carbamate is decomposed to form gaseous ammonia and gaseous carbon dioxide which is also taken off in the gaseous product, at least part of said gaseous product from said carbamate decomposer is recycled to said urea synthesis reactor, and a liquid product solution is withdrawn from said carbamate decomposer containing urea, the improvement comprising splitting said urea synthesis reactor effluent fluid stream into a minor stream containing from about 5% to about 35% by weight of the total urea synthesis reactor effluent fluid stream, and a major stream containing the balance of said urea reactor effluent fluid stream, passing said major stream through a pressure release valve to lower the pressure to the range from about 30 PSIG to about 800 PSIG and then passing said major stream at said lower pressure to the lower section of a liquid gas separator having a midsection provided with a liquid gas contact means above said lower section and an upper section above said midsection, said major stream at said lower pressure comprising (i) a gaseous phase containing NH_3 , CO_2 and H_2O which rises into and through said midsection of said separator into said upper section, and is removed therefrom with the other gaseous contents thereof, and (ii) a liquid phase containing urea and unconverted ammonium carbamate which passes down through the lower section of said separator and is withdrawn as a liquid part of the liquid product from the separator which is passed to an ammonium carbamate decomposer, passing said minor stream through a heat exchanger wherein

its temperature is lowered between about 40° and 80° F., and then passing said cooled minor stream through a pressure release valve to lower the pressure to substantially the pressure of the major stream as it enters said liquid gas separator and passing said minor stream having said lowered pressure to the upper section of said liquid gas separator wherein it is separated into (a) a gaseous phase containing NH₃, CO₂ and H₂O which is removed therefrom with the other gaseous contents of said upper section of said separator and recycled to said urea synthesis reactor and (b) a liquid phase which is passed downwardly through said midsection of said separator wherein it contacts the gaseous phase (i) passing upward through said midsection and absorbs carbon dioxide and water vapor from said gaseous phase (i) and said liquid phase (b) then passes downwardly through the lower section of said separator and is withdrawn as part of the liquid product from the separator which is passed to said ammonium carbamate decomposer,

whereby the combined gaseous phase from said liquid separator which is recycled to said urea synthesis reactor has a lower CO₂ and H₂O content than said gaseous phase (i) flashed off from said major stream and rising into and through said midsection of said separator, and the combined liquid product withdrawn from the lower section of said separator containing ammonium carbamate which is passed to said carbamate decomposer, has a larger content of CO₂ and H₂O than the liquid phase (ii) of said major stream after reduction in pressure and before passing through the lower section of said separator and mixing with the liquid phase (b) of said minor stream passed downwardly through said midsection of said separator.


4,296,253

2,5-INTER-O-PHENYLENE-3,4-DINOR-PGF₂ AMIDES
Udo F. Axen, Plainwell, and John C. Sih, Kalamazoo, both of Mich., assignors to The Upjohn Company, Kalamazoo, Mich.
Division of Ser. No. 62,443, Jul. 31, 1979, which is a continuation-in-part of Ser. No. 962,845, Nov. 22, 1978, abandoned. This application Jul. 3, 1980, Ser. No. 165,596
Int. Cl.³ C07C 103/24

U.S. Cl. 564—153

1 Claim

1. A prostacyclin intermediate of formula VII



wherein R₈ is hydrogen, hydroxy, or hydroxymethyl;

wherein Y₁ is

- (1) trans-CH=CH—,
- (2) cis-CH=CH—,
- (3) —CH₂CH₂—, or
- (4) —C≡C—,

wherein M₁ is α-R₅:β-OH or α-OH:β-R₅, wherein R₅ is hydrogen or alkyl with one to 4 carbon atoms, inclusive; wherein L₁ is α-R₃:β-R₄, α-R₄:β-R₃, or a mixture of α-R₃:β-R₄ and α-R₄:β-R₃, wherein R₃ and R₄ are hydrogen, methyl, or fluoro, being the same or different, with the proviso that one of R₃ and R₄ is fluoro only when the other is hydrogen or fluoro;

wherein R₇ is

- (1) —(CH₂)_m—CH₃, wherein m is an integer from one to 5, inclusive;
- (2) phenoxy;
- (3) phenoxy substituted by one, 2 or 3 chloro, fluoro, trifluoromethyl, alkyl of one to 3 carbon atoms, inclusive, or

alkoxy of one to 3 carbon atoms, inclusive, with the proviso that not more than two substituents are other than alkyl;

(4) phenyl;

(5) phenyl substituted by one, 2 or 3 chloro, fluoro, trifluoromethyl, alkyl of one to 3 carbon atoms, inclusive, or alkoxy of one to 3 carbon atoms, inclusive, with the proviso that not more than two substituents are other than alkyl;

(6) phenylmethyl, phenylethyl, or phenylpropyl; or

(7) phenylmethyl, phenylethyl, or phenylpropyl substituted by one, 2 or 3 chloro, fluoro, trifluoromethyl, alkyl of one to 3 carbon atoms, inclusive, or alkoxy of one to 3 carbon atoms, inclusive, with the proviso that not more than two substituents are other than alkyl; with the proviso that R₇ is phenoxy or substituted phenoxy, only when R₃ and R₄ are hydrogen or methyl, being the same or different;

wherein L₄ is

(1) amino of the formula —NR₂₁R₂₂, wherein R₂₁ and R₂₂ are

(a) hydrogen;

(b) alkyl or one to 12 carbon atoms, inclusive;

(c) cycloalkyl of 3 to 10 carbon atoms, inclusive;

(d) aralkyl of 7 to 12 carbon atoms, inclusive;

(e) phenyl;

(f) phenyl substituted with one, 2, or 3 chloro, alkyl of one to 3 carbon atoms, inclusive, hydroxy, or nitro;

(g) carbamoylalkyl of 2 to 5 carbon atoms, inclusive;

(h) acetylalkyl of 3 to 6 carbon atoms, inclusive;

(i) benzoylalkyl of 7 to 11 carbon atoms, inclusive;

(j) benzoylalkyl substituted by one, 2 or 3 chloro, alkyl of one to 3 carbon atoms, inclusive, hydroxy, alkoxy of one to 3 carbon atoms, inclusive, or nitro;

(k) hydroxyalkyl of one to 4 carbon atoms, inclusive;

(l) dihydroxyalkyl of one to 4 carbon atoms, inclusive, or (m) trihydroxyalkyl of one to 4 carbon atoms, inclusive; with the further proviso that not more than one of R₂₁ and R₂₂ is other than hydrogen or alkyl; or

(2) carbonylamino of the formula —NR₂₃COR₂₁, wherein R₂₃ is hydrogen or alkyl of one to 4 carbon atoms, inclusive, and R₂₁ is other than hydrogen, but otherwise as defined above.

4,296,254

TRANSESTERIFICATION IN AMIDES

Robert E. Middlebrook, Coral Gables; George R. Harvey, Miami, both of Fla., and John P. Chupp, Kirkwood, Mo., assignors to Monsanto Company, St. Louis, Mo.


Filed Mar. 25, 1980, Ser. No. 133,752

Int. Cl.³ C07C 102/00


U.S. Cl. 564—214

19 Claims

1. Process for the preparation of N-methylene ether-substituted 2-haloacetamides having the formula



which comprises transesterification of N-methylene ether-2-haloacetamides of the formula



with a compound of the formula



wherein the above formulae

X is chloro, bromo or iodo,

R is a phenyl or cycloalkenyl radical or a phenyl or cycloalkenyl radical substituted with lower alkyl, alkoxy, polyalkoxy or alkoxymethyl having up to 6 carbon atoms, halogen, NO₂, —CF₃ or a tetrahydrofurfuryloxy radical containing up to 6 carbon atoms and

R¹ and R² are different C₁₋₆ alkyl, haloalkyl, alkenyl, haloalkenyl, alkynyl, haloalkynyl, alkoxyalkyl, cycloalkyl, cyanoalkyl or lower alkoxyalkyl radicals or 1,3-dioxolanylmethyl which may be substituted with lower alkyl groups, said transesterification being conducted in an inert solvent at elevated temperature and in the presence of an acid catalyst.

4,296,255

ACYCLIC CARBOXAMIDES HAVING A PHYSIOLOGICAL COOLING EFFECT

David G. Roswell, Staines; David J. Spring, Datchet, and Roger Hems, Maidenhead, all of England, assignors to Wilkinson Sword Limited, London, England

Division of Ser. No. 36,662, May 7, 1979, Pat. No. 4,230,688, which is a continuation of Ser. No. 768,219, Feb. 14, 1977, Pat. No. 4,153,679, which is a division of Ser. No. 351,357, Apr. 16, 1973, abandoned. This application Apr. 25, 1980, Ser. No. 143,948


Claims priority, application United Kingdom, Apr. 18, 1972, 17914/72

Int. Cl.³ C07C 103/127, 103/38, 101/30

U.S. Cl. 564—215

5 Claims

1. Monosubstituted aliphatic acyclic carboxamides of the formula



where

R₁, R₂ and R₃ are each C₁₋₅ straight or branched chain alkyl and together provide a total of at least 5 carbon atoms; and

R' is selected from C₁₋₅ alkyl, C₁₋₈ hydroxyalkyl and alkylcarboxyalkyl of up to 6 carbon atoms.

4,296,256

2-DECARBOXY-2-HYDROXYMETHYL-19-KETO-PG COMPOUNDS

John C. Sih, Kalamazoo, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.


Division of Ser. No. 25,879, Apr. 2, 1980, This application Mar. 20, 1980, Ser. No. 132,349

Int. Cl.³ C07C 177/00

U.S. Cl. 568—330

262 Claims

1. A compound of the formula



wherein D is

- (1) cis-CH=CH-CH₂-(CH₂)_g-CH₂—,
- (2) cis-CH=CH-CH₂-(CH₂)_g-CF₂—,
- (3) cis-CH₂-CH=CH-CH₂-CH₂—,
- (4) trans-(CH₂)₃-CH=CH—,
- (5) -(CH₂)₃-(CH₂)_g-CH₂—,
- (6) -(CH₂)₃-CH₂-CF₂—,
- (7) -(CH₂)₃-O-CH₂—,

- (8) -(CH₂)₃-O-(CH₂)₂—,
- (9) -CH₂-O-(CH₂)₃—,
- (10) -(m-Ph)-(CH₂)₂—, or
- (11) -(m-Ph)-O-CH₂—,

wherein (m-Ph) is inter-meta-phenylene and

wherein g is zero, one, two, or three;

wherein Q is α-OH:β-R₅ or α-R₅:β-OH, wherein R₅ is hydrogen or methyl;

wherein R₂ is hydrogen, hydroxyl, or hydroxymethyl,

wherein R₃ and R₄ are hydrogen, methyl, or fluoro, being the same or different, with the proviso that one of R₃ and R₄ is fluoro only when the other is hydrogen or fluoro; and

wherein W is oxo, methylene, α-OH:β-H, or α-H:β-OH; and wherein X is cis- or trans-CH=CH—, —C≡C— or —CH₂CH—.

4,296,257

PROCESS FOR PRODUCING DIHYDROCARVONE GEOMETRIC ISOMERS

Carlos G. Cardenas, and Zia U. Din, both of Jacksonville, Fla., assignors to SCM Corporation, New York, N.Y.

Filed Jan. 7, 1980, Ser. No. 109,989

Int. Cl.³ C07C 45/51, 45/58

U.S. Cl. 568—361

8 Claims

1. A process for producing a single dihydrocarvone isomer from mixed liquid phase cis- and trans-limonene oxide isomers under limonene oxide rearrangement conditions and to the substantial exclusion of the other dihydrocarvone isomer, which comprises:

(A) separating said limonene oxide isomers by either:

(a) rearranging substantially selectively cis-limonene oxide at a temperature of from 50° C. to 95° C. in the presence of an acid catalyst to the trans-dihydrocarvone isomer and terminating this rearrangement before substantial rearrangement of the trans-limonene oxide occurs to form a reaction mixture or

(b) first fractionally distilling said limonene oxide isomers to isolate the cis-limonene oxide isomer from the trans-limonene oxide isomer as separate distillate fractions and then rearranging one of the thus-separated limonene isomer distillate fractions in the presence of from 0.1% to 10% by weight of said separated limonene oxide isomer of an acid catalyst, at a temperature of from 50° C. to 95° C., until the corresponding dihydrocarvone isomer is formed in the reaction mixture to the substantial exclusion of the other dihydrocarvone isomer,

(B) neutralizing the acid catalyst in said reaction mixture with a base, and

(C) recovering the resulting dihydrocarvone isomer from the reaction mixture.

4,296,258

PROCESS FOR THE PREPARATION OF MACROCYCLIC KETONES

Charles Fehr, Geneva; Günther Ohloff, Bernex, both of Switzerland, and Georges H. Büchi, Cambridge, Mass., assignors to Firmenich SA, Geneva, Switzerland

Filed Dec. 28, 1979, Ser. No. 107,847


Claims priority, application Switzerland, Jan. 26, 1979, 796/79

Int. Cl.³ C07C 45/00

U.S. Cl. 568—364


7 Claims

1. A process for the preparation of acetylenic macrocyclic ketones of formula



wherein one of symbols R represents a lower alkyl radical containing 1 to 3 carbon atoms and the other a hydrogen atom, which comprises

- a. treating a hydrazone of formula



wherein symbols R are defined as above and A designates a sulphonyl radical of formula



wherein R¹ stands for an aryl radical, with a halogenating reagent selected from the group consisting of

- bromine,
- chlorine,
- iodine,
- 1,3-dibromo-5,5-dimethyl-hydantoin,
- N-bromosuccinimide,
- N-iodosuccinimide and
- N-chlorosuccinimide

in the presence of a lower aliphatic alcohol and at a temperature of from about -25° to about +25° C.;

- reducing the excess of halogenating reagent by addition of reducing agent, and
- heating the reaction mixture in an aqueous medium at a temperature of from about 20° to about 60° C.

4,296,259

PREPARATION OF A 1,4-PENTADIEN-3-OL


Urs Hengartner, Roseland, N.J., assignor to Hoffmann-La Roche Inc., Nutley, N.J.

Division of Ser. No. 24,296, Mar. 27, 1979, abandoned. This application Jun. 9, 1980, Ser. No. 157,574

Int. Cl.³ C07C 49/743

U.S. Cl. 568—378

1. A compound of the formula:



- (I) **4,296,260**
PROCESS FOR THE PREPARATION OF PHLOROGLUCINOL
Rainer Zielke, Erlenbach, and Helmut Maegerlein, Obernburg, both of Fed. Rep. of Germany, assignors to Akzona Incorporated, Asheville, N.C.
Filed Aug. 8, 1979, Ser. No. 64,691
Claims priority, application Fed. Rep. of Germany, Sep. 18, 1978, 2840597
Int. Cl.³ C07C 39/10, 37/01
U.S. Cl. 568—763 **8 Claims**

- (II) 1. A process for the preparation of phloroglucinol comprising reacting hexachlorobenzene with sodium propylate in a molar ratio of hexachlorobenzene:sodium propylate of from about 1:3 to about 1:20, in an aprotic solvent, and at a temperature from about 50° to about 250° C. to form trichlorophloroglucinol tripropylether, dechlorinating the trichlorophloroglucinol tripropylether with metallic sodium to form phloroglucinol tripropylether, and hydrolyzing the phloroglucinol tripropylether to form phloroglucinol.


4,296,261
PROCESS FOR THE MANUFACTURE OF ETHANOL FROM ETHYLENE

Don B. Carson, Mt. Prospect, Ill., assignor to UOP Inc., Des Plaines, Ill.

Filed Jun. 9, 1980, Ser. No. 157,773

Int. Cl.³ C07C 29/12

U.S. Cl. 568—890

9 Claims

1. A process for the manufacture of a C₂-C₅ alcohol which comprises the steps of:

- treating a C₂-C₅ olefin in an absorption zone in admixture with a C₂-C₅ alkyl hydrogen sulfate at conditions to form a C₂-C₅ dialkyl sulfate;
- treating said dialkyl sulfate in a hydrolyzing zone in admixture with a measured amount of water at conditions effecting the partial hydrolysis of said dialkyl sulfate and the formulation of a C₂-C₅ alkyl hydrogen sulfate and a C₂-C₅ alcohol;
- separating said alcohol; and
- recycling the alkyl hydrogen sulfate to said absorption zone and treating said C₂-C₅ olefin in admixture therewith in accordance with step (a).

4,296,262

MANUFACTURE OF TERTIARY BUTYL ALCOHOL
Henry R. Grane, Springfield; John C. Jubin, Jr., Wallingford, and G. Richard Worrell, Media, all of Pa., assignors to Atlantic Richfield Company, Los Angeles, Calif.

Continuation-in-part of Ser. No. 45,365, Jun. 4, 1979, abandoned. This application Feb. 25, 1980, Ser. No. 124,404

Int. Cl.³ C07C 29/50

U.S. Cl. 568—910

1 Claim

1. The method of preparing tertiary butyl alcohol (TBA) which includes the steps of:
maintaining in an oxidation reaction zone a liquid reaction mixture comprising TBA, tertiary butyl hydroperoxide

(TBHP), and (TBHP) isobutane at conditions favoring the oxidation of isobutane to a mixture of TBA and TBHP, said conditions comprising a temperature within the range from about 240° F. to about 340° F., a pressure maintaining most of the isobutane in said oxidation reaction zone in the liquid phase, said pressure being within the range from about 100 psig to about 1000 psig, a residence time within the range from about 1 to about 10 hours, and a concentration of soluble molybdenum catalyst corresponding to about 1 to about 500 ppm of the weight of isobutane in said liquid;


refluxing back into said reaction mixture a significant portion of any TBHP or other components boiling above TBA, while withdrawing from the oxidation reaction zone an overhead vapor stream comprising nitrogen, carbon monoxide, carbon dioxide, isobutane, acetone, methanol, water, and TBA;

selectively condensing from said overhead vapor stream a condensed TBA stream comprising acetone, methanol, water and TBA;

selectively condensing isobutane from the TBA depleted overhead vapor stream and recycling such condensed isobutane to the oxidation reaction zone;

withdrawing an isobutane-depleted overhead vapor stream comprising nitrogen, carbon monoxide, carbon dioxide from said overhead vapor stream;

directing at a controlled rate a slip stream of liquid reaction mixture from the oxidation reaction zone to a debutanizer-



ing zone in which the isobutane is selectively separated and recycled to the oxidation reaction zone, said slip stream being controlled to be sufficient to maintain in the liquid oxidate in the reaction zone a concentration of high-boiling byproducts from about 1% to about 10%, said high-boiling byproducts being those, other than TBHP and TBA, which are not completely codistilled with the TBA;

directing the debutanized slip stream to a decomposition zone maintained at a temperature from about 200° to 350° F. at a pressure from about 40 to about 100 psig for a residence time of from about 1 to about 6 hours to decompose a portion of the TBHP and to increase the TBA concentration;

directing the liquid effluent stream from the decomposition zone to a distillation zone to provide a distillate stream comprising acetone, methanol, and TBA, and to provide a residual liquid having a unit weight ratio of tertiary butyl alcohol to tertiary butyl hydroperoxide greater than one, byproducts which are not completely codistilled with tertiary butyl alcohol, and molybdenum catalyst;

withdrawing at least a portion of said residual liquid stream; directing a stream containing TBA to a cleanup zone maintained at 375°-475° F. for from 1 to 10 minutes under pressure to decompose any TBHP residues;

directing to a gasoline-blending zone a stream comprising TBA derived from the effluent stream from said cleanup zone; and

merging a debutanized distillate from the reactor overhead stream with a debutanized distillate derived from the slip

stream to provide a stream containing TBA at some stage prior to the directing of a TBA containing stream to said cleanup zone.

4,296,263


TERTIARY BUTYL ALCOHOL PRODUCTION

G. Richard Worrell, Media, Pa., assignor to Atlantic Richfield Company, Los Angeles, Calif.

Filed Sep. 19, 1980, Ser. No. 188,653

Int. Cl.³ C07C 27/12

U.S. Cl. 568—910

1 Claim

1. A method of preparing tertiary butyl alcohol which includes the steps of:

separating most C₃ hydrocarbons and most C₅ hydrocarbons from a mixed C₄ hydrocarbon stream in a crude butane purification zone to provide a stream of purified mixed C₄ hydrocarbons consisting essentially of from about 51 to about 85% isobutane and from about 49 to about 15% normal butane;

mixing said stream of purified mixed C₄ hydrocarbons with a stream of recycle C₄ hydrocarbons and with a catalyst stream in a feedstream preparation zone to provide a feedstream of mixed C₄ hydrocarbons, said catalyst being distributable in said mixed C₄ hydrocarbons, and said catalyst comprising a multivalent metal selected from the group consisting of chromium, cobalt, nickel, manganese, molybdenum, and mixtures thereof in a concentration of from about 1 to about 500 parts per million parts of isobutane, said catalyst stream optionally including a recycled stream derived from a high boiling stream;

maintaining in an oxidation zone, a pressurized liquid reaction mixture, said C₄ hydrocarbons derived from the feedstream being the most abundant component of said liquid reaction mixture;

directing said feedstream into said oxidation zone at a feedstream rate controlled to maintain said predominance of C₄ hydrocarbons in said liquid reaction mixture in said oxidation zone while maintaining an isobutane flow rate corresponding to a preselected residence time for the C₄ hydrocarbons;

injecting an oxygen containing gas into said oxidation zone at a normal rate stoichiometrically effective for converting to tertiary butyl alcohol at least one-sixth but less than half of said isobutane flow rate in said feedstream;

withdrawing from said oxidation zone a stream of liquid reaction mixture at a rate stoichiometrically equal, as regards C₄ components, to said feedstream rate and controlled to maintain the residence time of C₄ hydrocarbons in said oxidation zone at a predetermined residence time within a range from about 1 to about 10 hours;

maintaining the pressure in said oxidation zone at a predetermined pressure within a range from about 200 to about 1000 psig;

directing a portion of the vapors from said oxidation zone into a reflux zone and withdrawing gaseous products from said reflux zone at a rate adapted to maintain said predetermined pressure, said withdrawn gaseous products comprising oxygen and carbon dioxide;

maintaining the temperature in said oxidation zone substantially at a predetermined temperature within the range from 260° to 340° F., the combination of controlled temperature, pressure, catalyst concentration, high boiler concentration, and residence time providing a conversion of isobutane within the range from 15% to 45%;

subjecting the liquid effluent from the oxidation zone to a debutanizing distillation zone and separating and withdrawing overhead from said debutanizing zone an intermediate mixed butanes stream and separating and withdrawing a residual liquid stream of oxygenated organic liquid from said debutanizing zone;

subjecting said intermediate mixed butanes stream to distillation in a butane isomer distillation zone to prepare a residual normal butane stream containing less than 45% isobutane and an overhead isobutane stream which in isobutane and containing less than 45% impurities comprising normal butane and withdrawing from the process said residual normal butane stream, and directing to said feedstream preparation zone said isobutane stream as a stream of recycle isobutane,

subjecting said liquid stream of oxygenated organic liquid from the debutanizing zone to a distillation separation zone for the separation of at least one low boiling stream comprising overhead components selected from the group consisting of acetone, methanol, tertiary butyl alcohol, methyl ethyl ketone, methyl formate, ethyl formate, isopropyl formate, methyl acetate, ethyl acetate, and related compounds boiling below about 194° F., and for the separation of a residual high boiling stream comprising components selected from the group consisting of water, formic acid, secondary butyl alcohol, normal butyl alcohol, tertiary butyl hydroperoxide, acetic acid, high boiling esters, and related compounds boiling above about 194° F.;

subjecting a stream comprising said low boiling stream to hydrogenation in a hydrogenation zone at mild conditions favoring minimized hydrogenation of tertiary butyl alcohol to isobutane and significant conversion of methyl ethyl ketone to secondary butyl alcohol, and acetone to isopropanol, the liquid effluent from the hydrogenation zone being directed to a product separation zone;

optionally subjecting at least a portion of said residual high boiling stream to a tertiary butyl hydroperoxide decomposition zone, the effluent from which is distilled in a post-decomposition distillation zone for separating overhead a supplemental tertiary butyl alcohol stream from a residual effluent stream and directing said supplemental tertiary butyl alcohol stream to said hydrogenation zone, said tertiary butyl hydroperoxide decomposition zone being maintained at a temperature within the range from about 200° to about 350° F. for a residence time of about 1 to about 6 hours;

withdrawing from the process at least a portion of streams selected from the group consisting of said high boiling stream from the separation zone, said residual effluent stream from the post-decomposition distillation zone, and mixtures thereof;

optionally recycling to said feedstream preparation zone a portion of streams selected from the group consisting of said high boiling stream from the separation zone, said residual effluent stream from the post-decomposition zone, and mixtures thereof, as a catalyst recycle stream; and withdrawing in a product separation zone as the most valuable product of the process a liquid product stream containing minor amounts of isopropanol and methanol, said liquid product stream containing tertiary butyl alcohol as the principal component.

4,296,264

ETHYNYLBENZENE COMPOUNDS AND DERIVATIVES THEREOF


Julius Diamond, Morris Plains, N.J., assignor to William H. Rorer, Inc., Fort Washington, Pa.
Continuation of Ser. No. 753,273, Dec. 22, 1976, which is a division of Ser. No. 574,837, May 14, 1975, which is a continuation of Ser. No. 431,254, Jan. 7, 1974, Pat. No. 3,923,910, which is a division of Ser. No. 268,419, Jul. 3, 1972, Pat. No. 3,852,364. This application Oct. 19, 1977, Ser. No. 843,695

The portion of the term of this patent subsequent to Dec. 2, 1992, has been disclaimed.
Int. Cl.³ C07C 25/06

U.S. Cl. 570—128

2 Claims

1. A compound of the formula



wherein Y is halo.

2. A compound according to claim 1 which is 3-fluoro-4-phenylethynylbenzene.

4,296,265

PROCESS FOR PREPARING HEXAFLUOROPROPENE OLIGOMERS

Yohnosuke Ohsaka, Takatsuki, and Takashi Tohzuka, Settsu, both of Japan, assignors to Daikin Kogyo Co., Ltd., Osaka, Japan

Filed Jul. 18, 1980, Ser. No. 170,151

Claims priority, application Japan, Jul. 19, 1979, 54-91849; Aug. 15, 1979, 54-103713

Int. Cl.³ C07C 17/26

U.S. Cl. 570—138

5 Claims

1. A process for preparing hexafluoropropene oligomers which comprises contacting gaseous hexafluoropropene with a catalyst comprising an alkali metal fluoride supported on activated charcoal or nickel oxide.

4,296,266

PROCESS FOR THE MANUFACTURE OF LOWER OLEFINS FROM METHANOL/WATER MIXTURES

Friedrich Wunder, Flörsheim am Main; Ernst I. Leupold, Neu-Anspach; Horst Hachenberg, Walluf, and Hans-Joachim Schmidt, Königstein, all of Fed. Rep. of Germany, assignors to Hoechst Aktiengesellschaft, Frankfurt am Main, Fed. Rep. of Germany

Filed Jul. 16, 1980, Ser. No. 169,629

Claims priority, application Fed. Rep. of Germany, Jul. 18, 1979, 2928922

Int. Cl.³ C07C 1/00, 1/24

U.S. Cl. 585—640

6 Claims

1. Process for the manufacture of C₂-C₄-olefins from methanol and/or dimethyl ether in the presence of water, on an aluminum silicate catalyst containing manganese, which com-

prises washing the catalyst with a solution of ethylenediamine-tetraacetic acid or tartaric acid with a pH of 3 to 7.

4,296,267

Patent Not Issued For This Number

4,296,268

Patent Not Issued For This Number

ELECTRICAL

4,296,269

CONTROL OF ELECTRICAL ARC FURNACES

Alistair B. Stewart, and Ian J. Barker, both of Randburg, South Africa, assignors to National Institute for Metallurgy, Randburg, South Africa


Filed Jun. 13, 1978, Ser. No. 915,194

Claims priority, application South Africa, Jun. 29, 1977, 77/3923; Jan. 20, 1978, 78/0375

Int. Cl.³ H05B 7/18

U.S. Cl. 13—12

21 Claims



1. A method for controlling operating conditions of a multi-phase arc furnace, said furnace including a furnace bath, a transformer system defining a primary circuit and a secondary circuit, furnace control means, and electrodes operatively connected to the furnace control means and electrically connected to said secondary circuits, each of said electrodes, in conjunction with said furnace bath, having a reactance the method comprising the steps of:

measuring currents and voltages on at least one of said primary circuit and secondary circuit, excluding secondary phase voltages measured with respect to the furnace bath, and producing measurement signals related to said secondary circuit currents and voltages;
generating condition signals related to said operating conditions from said measurement signals on the basis that each said reactance is related to each other said reactance by an assumed relationship;
comparing the condition signals with predetermined signals; and
operating the furnace control means in accordance with any deviation of said condition signals from said predetermined signals to cause the conditioned signals to approach said predetermined signals.

4,296,270

ARRAY OF SOLAR CELLS

Kranz Köhler, Unterhaching, Fed. Rep. of Germany, assignor to Messerschmitt-Bölkow-Blohm GmbH

Filed Apr. 29, 1980, Ser. No. 144,954

Claims priority, application Fed. Rep. of Germany, May 11, 1979, 2919041

Int. Cl.³ H01L 31/04

U.S. Cl. 136—244

6 Claims



1. An improved array of solar cells of the type having a

plurality of solar cells having N-type and P-type conducting zones, a plurality of contacting connectors electrically interconnecting the N-type with the P-type conducting zone of adjacent cells, each contacting connector extending outwardly from the periphery of a respective cell, the improvement wherein each of the contacting connectors comprises a foil-type ribbon having a corrugated portion extending from each solar cell; and the connectors of adjacent solar cells being overlapped and connected to each other at the corrugated portions for electrical connection but without coming into contact with adjacent solar cells.

4,296,271

GAS INSULATED HIGH VOLTAGE LINE AND METHOD OF ASSEMBLING SAME

Carl D. Floessel, Fislisbach, Switzerland, assignor to BBC Brown, Boveri & Company Limited, Baden, Switzerland



Filed Apr. 1, 1980, Ser. No. 136,350

Claims priority, application Switzerland, Apr. 9, 1979, 3355/79

Int. Cl.³ H01B 9/04, 13/20; H02G 5/06

U.S. Cl. 174—28

6 Claims



1. A gas insulated, high-voltage electric line, comprising:
a pipe jacket having an inner surface;
a conductor centrally arranged within the pipe jacket;
a plurality of insulators arranged about the periphery of said conductor; and
spring means, arranged between said insulators and said conductor, for urging each of said insulators radially outwardly toward, and into contact with, said inner surface of said pipe jacket, said spring means including at least one carrier ring encircling said conductor, on which carrier ring said insulators are mounted, an inner diameter of which carrier ring is at least as large as an outer diameter of said conductor; and
a plurality of resilient, spring-like elements, each of which elements is interposed between said conductor and one of said insulators; and
said insulators being movable relative to said pipe jacket along a longitudinal axis of said pipe jacket.

6. A method for assembling a gas insulated, high-voltage electric line, comprising the steps of:
mounting at least first and second sets of radially directed insulators onto a conductor, each of said insulators includ-

ing a resilient member interposed between the conductor and the insulator;
simultaneously urging all of the insulators mounted on the conductor radially downwardly toward said conductor to produce a clearance between an outer end of each of said insulators and an inner surface of a pipe jacket;
moving said conductor and said at least first and second sets of insulators into an interior of said pipe jacket;
releasing all of the insulators when the first set of insulators has been moved to a first location to permit the resilient members interposed between the conductor and the first set of insulators to urge the first set of insulators radially outwardly into engagement with the inner surface of said pipe jacket;
simultaneously engaging and urging all of the insulators of the second set of insulators radially downwardly toward said conductor to produce a clearance between an outer end of each of said second set of insulators and the inner surface of said pipe jacket;
moving said conductor and said second set of insulators further into the interior of said pipe jacket; and
releasing all of the insulators of the second set of insulators when the second set of insulators has been moved to a second location to permit the resilient members interposed between the conductor and the second set of insulators to urge the second set of insulators radially outwardly into engagement with the inner surface of said pipe jacket.

4,296,272

COMPOSITE SUBSTRATE


Robert L. Schelhorn, Cinnaminson, N.J., assignor to RCA Corporation, New York, N.Y.

Filed Nov. 30, 1979, Ser. No. 98,927

Int. Cl.³ H05K 1/03

U.S. Cl. 174—68.5

7 Claims



1. An improved thick film composite substrate of the type having a plurality of patterned conductive layers interleaved with a plurality of electrically insulating ceramic layers and having a patterned electrically conductive layer of a refractory material on an exposed surface thereof, said original patterned conductive layer of refractory material having been shrunk during fabrication of said substrate and being substantially incapable of being functionally interconnected with means of fixed spacing, said improved substrate comprising:

a patterned electrically conductive compensation layer generally following said original patterned conductive layer of refractory material entirely covering and extending beyond said shrunken patterned refractory material by an amount about equal to the degree of shrinkage of said original pattern whereby said patterned conductive compensation layer is functionally interconnectable with said means of fixed spacing.

4,296,273

SUPPORT ASSEMBLY FOR HIGH CURRENT BUS BARS



Zygmunt Hologa; Krystyn Madeyski, and Adam Kurowski, all of Katowice, Poland, assignors to Przedsiębiorstwo Montażu Elektrycznego "Elektrobudowa", Katowice, Poland

Filed Mar. 3, 1980, Ser. No. 126,742

Int. Cl.³ H02G 5/06

U.S. Cl. 174—99 B

2 Claims



1. In a support assembly for high current bus bars, including an elongated tubular enclosure having a generally circular cross-section, a plurality of insulators arranged in groups of three and being radially inwardly directed with respect to said enclosure, and spaced circumferentially 120° from each other, and means for adjustably mounting said insulators relative to said enclosure and providing access to the interior of said enclosure, the improvements being characterized in that said insulator mounting and access means comprises a series of longitudinally extending oval-shaped openings in said tubular enclosure, an integral oval-shaped flange defining each said opening, a cuboid-shaped bracket means mounted across each oval flange between opposite elongated sides thereof, each said bracket means including a square base extending radially inwardly toward the center of said enclosure, said insulator being secured to said bracket base, said cuboid-shaped bracket mounted over said oval-shaped opening defining a pair of semicircular spaces providing access for inspection to the interior of said enclosure, and located at longitudinally spaced opposite sides of said bracket means, and an oval-shaped cover releasably secured to each said oval-shaped flange and overlying said bracket means.

4,296,274

HIGH VOLTAGE BUSHING HAVING WEATHERSHED AND SURROUNDING STRESS RELIEF COLLAR

Alan H. Cookson, Pittsburgh, Pa., assignor to The United States of America as represented by the United States Department of Energy, Washington, D.C.

Filed Jul. 11, 1980, Ser. No. 167,501


Int. Cl.³ H01B 17/26, 17/42

U.S. Cl. 174—142

12 Claims

1. A high voltage bushing comprising:
a hollow weathershed having an outside surface and a first end;
a high voltage conductor disposed within said weathershed exerting a region of high electric field stress concentration on the outside surface of said weathershed;
means contacting the electric field for outwardly directing the concentration of high electric field stress to a predeter-

mined portion of the outside surface of said weathershed; and
a dielectric collar surrounding said predetermined portion of said weathershed, said collar having adjacent the region of high electric field stress concentration, a thickness sub-



stantially greater than the thickness of said weathershed, said collar further having an outside surface which forms a portion of the outside surface of said bushing; and
means, separate from said collar, for supporting said weathershed, whereby the electric field stress concentration on the outside surface of said bushing is relieved.

4,296,275

HERMETIC REFRIGERATION TERMINAL


Benjamin Bowsky, Maineville, Ohio, assignor to Emerson Electric Co., St. Louis, Mo.

Filed Jun. 9, 1980, Ser. No. 157,411

Int. Cl.³ H01B 17/26

U.S. Cl. 174—152 GM

13 Claims



1. In a hermetic refrigeration terminal having a cup-shaped body with a generally flat bottom and at least one opening in said bottom defined by an annular sealing lip, a current conducting pin extending through said opening and beyond said lip on both ends thereof, the inner end of said pin being on the dish side and the outer end being on the outer side of said body, and a seal bonding said pin to an inside surface of said lip, the improvement comprising a flange extending generally radially from said pin and located axially between said lip and said inner end of said pin, and a sleeve surrounding said pin and extending axially between said flange and said lip, said sleeve being at least in part larger in diameter than said opening, said sleeve being bonded at its end opposite the flange to said seal.

4,296,276

ROD-TYPE SYNTHETIC RESIN INSULATOR WITH OVERCOAT AND METAL FITTINGS

Takeshi Ishihara, Toyooka; Daisaku Goto, Konan, and Hitoshi Sugiura, Toyohashi, all of Japan, assignors to NGK Insulators, Ltd., Nagoya, Japan

Filed Mar. 4, 1980, Ser. No. 127,038

Claims priority, application Japan, Nov. 17, 1979, 54-149317


Int. Cl.³ H01B 17/02

U.S. Cl. 174—179

6 Claims

1. A synthetic resin insulator comprising a fiber-reinforced plastic rod, metal fittings which hold both ends of the fiber-reinforced plastic rod, and a seamless unitary overcoat which

consists of an elastic insulating material, covers the total surface of the fiber-reinforced plastic rod located between the metal fittings and is provided at its outside with a plurality of sheds, said metal fittings having metal sleeves gastightly fixed thereto and being operative to receive both ends of the overcoat, both ends of said overcoat being sandwiched between the



metal sleeve and the fiber-reinforced plastic rod and fixed and sealed in the metal sleeve by pressing the sleeve in the radial direction so as to isolate gastightly the interface between the overcoat and the fiber-reinforced plastic rod from the external atmosphere, and wherein the elongation of the outer surface of the overcoat resulting from assembly with said fiber-reinforced plastic rod and pressing of said sleeves is not higher than 2%.

4,296,277

ELECTRONIC VOICE DETECTOR

Hansruedi Daneffel, Uerikon, Switzerland, assignor to Feller AG, Horgen, Switzerland


Filed Sep. 26, 1979, Ser. No. 79,186

Claims priority, application Switzerland, Sep. 26, 1978, 10033/78

Int. Cl.³ H04M 1/64

U.S. Cl. 179—1 VC

10 Claims



1. An electronic voice detector for use in an automatic telephone answering apparatus, said voice detector having input means for receiving audio signals from a telephone line, and output means for supplying a control signal indicating the presence of an incoming voice signal, wherein between said input means and said output means a first signal channel and a second signal channel are disposed in parallel configuration, said signal channels being commonly connected to said input means and said signal channels being connected to said output means through a logic means, said first signal channel comprising signal threshold means for generating an output signal if the signal from the input means has an amplitude exceeding a predetermined level, and signal delay means connected to the output of said threshold means for generating an output signal if said output signal from said threshold means has a duration exceeding a predetermined time interval, said second signal

tion connection between said first station (S3) and a first line on which a calling connection is being directed to a second station (S2).

a visual display field (214; FIGS. 3, 4 and 5; FIG. 14, RNG-CAL) at said first station operable when a call is directed to said first station for indicating the identity of the calling station (S1), said system characterized in that there is also provided determining means (FIGS. 3, 2, 7, 18 and 29, FIG. 10) for use on each incoming call to said first station (S3) to identify calls directed to said call coverage button (210B), and

means (FIG. 7; FIG. 9; FIG. 14; SL-ILJ) responsive to an identified call directed to said call coverage button (210B) for inhibiting said visual indication of said calling station (S1) and for substituting therefor on said visual display field an indication of the original called station (S2).

4,296,283

NORMALLY CLOSED WAFER SWITCH


Robert H. Koenig, Huntington Hills, and Victor D'Angelo, Port Washington, both of N.Y., assignors to Tapeswitch Corporation of America, Farmingdale, N.Y.

Filed May 17, 1979, Ser. No. 39,807

Int. Cl.³ H01H 1/14

U.S. Cl. 200—16 D

4 Claims



1. A wafer switch which is normally closed in relaxed position but which opens when squeezed comprising:

- a lower stiff plate,
- a first curved conductive contact member having a longitudinal axis of curvature and mounted on the lower plate with the curvature extending in the upward direction,
- an insulating plate mounted on the first curved conductive contact member, the insulating plate having a central aperture,
- a second curved conductive contact member having a longitudinal axis of curvature and mounted on the insulating plate and having its curvature extending in the downward direction, said longitudinal axes of the first and second curved contact members being at right angles to each other,
- the first and second conductive contact members being in contact through the aperture when they are in relaxed position,
- an upper stiff plate mounted on the second curved contact member whereby when the upper and lower stiff plates are squeezed together the contact is broken.

4,296,284

FLEXIBLE SHIELD FOR HIGH VOLTAGE DISCONNECT SWITCH

Donald L. Lott, Portland, Oreg., assignor to Siemens-Allis, Inc., Atlanta, Ga.

Filed Dec. 26, 1979, Ser. No. 106,720

Int. Cl.³ H01H 31/00, 9/00


U.S. Cl. 200—48 R

10 Claims

1. Ice shielding means for an outdoor, high voltage dis-

connect switch assembly having interengaging moveable and stationary members, comprising:

- rigid support means coupled to the stationary portion of the switch and extending generally vertically therefrom;
- flexible shielding means having one side thereof fixedly coupled to said support means and aside opposite said one side free and unsupported so as to extend above the sta-



tionary portion of the switch and in the path of the moveable portion thereof;

whereby movement of the moveable portion of the switch pursuant to disengagement of the switch members temporary elastically deforms the shielding means.

4,296,285

HIGH-VOLTAGE, BLAST-ACTUATED POWER SWITCH HAVING FIELD ELECTRODES

Ernst Lang, Würenlingen, and Lutz Niemeyer, Baden, both of Switzerland, assignors to BBC Brown, Boveri & Company Limited, Baden, Switzerland


Filed Jan. 9, 1980, Ser. No. 110,793

Claims priority, application Switzerland, Jan. 11, 1979, 243/79

Int. Cl.³ H01H 39/00

U.S. Cl. 200—61.08

8 Claims



1. A high voltage, blast-actuated power switch having a hollow switch casing and having first and second external electrical connections, said first and second external connections being electrically insulated from each other, said switch comprising:

- bridge conductor means included within said switch casing for electrically connecting said first external connection to said second external connection, said bridge conductor means having first and second bridge conductor elements electrically connected to said first and second external connections, respectively, and said first and second bridge conductor elements being separably connected to each other;

- means for physically separating said first bridge conductor element from said second bridge conductor element by a first distance so as to electrically disconnect said first external connection from said second external connection; and

- first and second field electrodes included within said switch casing, said first and second field electrodes being electri-

cally connected to said first and second external connections, respectively, and said first and second field electrodes being separated by a second distance; wherein said second distance is less than said first distance.

4,296,286

SELF-REFERENCING POSITION SWITCH


Warren N. Richardson, Mashpee, Mass., assignor to TRW Inc., Cleveland, Ohio

Filed Nov. 16, 1979, Ser. No. 95,042

Int. Cl.³ H01H 9/00

U.S. Cl. 200—61.54

19 Claims



1. A self-referencing position switch adapted to be responsive to the position of a movable member relative to a second member, the movable member being movable over a course between a location at one end of the course and a selected location along the course, said switch comprising

- A. a switch housing,
- B. a switch actuator projecting from the housing for engagement by one of said members and movable by that member relative to the housing along a track to selectively open or close the switch when positioned at a determined location along the track from one end thereof,
- C. means for mounting the housing to the other of said members so that the track extends in the same general direction as the course,
- D. means for movably connecting the housing to the mounting means so that the two can move relative to one another along a path which extends in the same general direction as said course, and
- E. means for adjustably maintaining the relative positions of the housing and mounting means along said path so that if the determined location is positioned beyond the selected location from said one course end, by moving said one member to said one course end, said switch actuator will be moved to said one track end and shift the housing relative to the mounting means by the amount required to align said determined track location with the selected course location.

4,296,287

WEATHERPROOFED CONDITION RESPONSIVE SWITCH

Henry J. Boulanger, Cumberland, R.I.; Victor Lowell, North Attleboro, and Elliot Whipple, Attleboro, both of Mass., assignors to Texas Instruments Incorporated, Dallas, Tex.

Filed Nov. 23, 1979, Ser. No. 97,018


Int. Cl.³ H01H 35/34

U.S. Cl. 200—83 P

13 Claims

11. Condition responsive apparatus comprising a generally cup shaped base having a bottom wall and a side wall depending therefrom, and forming a chamber therein, the side wall terminating at an open end, a motion transfer pin guide having a bore therethrough received at the open end of the base, a diaphragm assembly comprising a metallic annular diaphragm support plate disposed on the guide, a metallic diaphragm disposed on top of the support plate and a cup shaped metallic housing disposed on top of the diaphragm, the diaphragm

support, diaphragm and housing welded together along a common, continuous outer peripheral margin, a motion transfer pin slidingly received in the guide and having two opposite ends, one end adapted to engage the diaphragm, a stationary electrical contact mounted in the base, a movable contact arm mounted in the base and adapted to move into and out of engagement with the stationary contact, the other end of the motion transfer pin adapted to engage the movable contact



4,296,288

GAS INSULATED DISCONNECTING SWITCHES

Satoru Yanabu, Machida; Hitoshi Mizoguchi, and Naoaki Simogawara, both of Yokohama, all of Japan, assignors to Tokyo Shibaura Denki Kabushiki Kaisha, Kanagawa, Japan


Filed Oct. 24, 1979, Ser. No. 87,655

Claims priority, application Japan, Oct. 30, 1978, 53-132593

Int. Cl.³ H01H 33/12, 33/88

U.S. Cl. 200—146 R

3 Claims



1. A gas insulated disconnecting switch comprising:

- (A) a stationary contact assembly including:
 - a substantially rod-shaped stationary arc electrode, and
 - a stationary conductive contact, and
- (B) a movable contact assembly provided to confront said stationary contact assembly and including:
 - a stationary cylinder having an annular end plate extending inwardly from said stationary cylinder,
 - a cylindrical movable conductive contact coaxial with said stationary cylinder and having a piston extending outwardly from said movable conductive contact at a position farther from said stationary contact assembly than said end plate of said stationary cylinder, said piston slidably and gastightly engaging the inner surface of said stationary cylinder,
 - said end plate of said stationary cylinder slidably and gas-tightly engaging the outer surface of said movable conductive contact to form a compression chamber between said end plate and said piston and between said

stationary cylinder and said movable conductive contact, and
 said movable conductive contact further having an annular stopper extending inwardly from said movable conductive contact,
 a substantially rod-shaped movable arc electrode coaxial with said stationary cylinder and having a piston extending outwardly from said movable arc electrode at a position farther from said stationary contact assembly than said stopper of said movable conductive contact, said piston of said movable arc electrode slidably and gas-tightly engaging the inner surface of said movable conductive contact,
 said stopper of said movable conductive contact slidably and gas-tightly engaging the outer surface of said movable arc electrode to form a damping chamber between said stopper and said piston of said movable arc electrode and between said movable conductive contact and said movable arc electrode, and
 said movable conductive contact being provided with a perforation providing communication between said compression chamber and said damping chamber, said perforation being so positioned and sized that it extends, when said movable conductive contact is in engagement with said stationary conductive contact, over both sides of said end plate to provide communication between the two chambers and the exterior of the chambers, and,
 a spring engaging at one end with said movable conductive contact and at the other end with said movable arc electrode in such a manner that when said movable conductive contact is moved toward said stationary conductive contact said spring urges said movable arc electrode toward the stationary arc electrode;
 said stopper having a projection projecting toward said piston of said movable arc electrode to engage with and push said piston of said movable arc electrode when said movable conductive contact is separated from said stationary conductive contact.

4,296,289

ELECTRIC GAS-BLAST SWITCH

Hans-Rudolf Wüthrich, Oberentfelden; Peter Krebs, Hirschtal; Hubert Spiegel, Oberentfelden, and Franz Eicher, Aarau, all of Switzerland, assignors to Sprecher & Schuh AG, Aarau, Switzerland


Filed Mar. 26, 1979, Ser. No. 24,465

Claims priority, application Switzerland, Apr. 19, 1978, 4176/78

Int. Cl.³ H01H 33/70

U.S. Cl. 200—148 R

12 Claims



1. An electrical gas-blast switch comprising:

a fixed set of contacts;
 a movable, substantially tubular-shaped contact element which can be brought into and out of engagement with said fixed set of contacts;
 said fixed set of contacts comprising:
 a rim of rated current contacts which in a cut-on position of the switch engages about said movable contact element;
 a burn-off rim electrically connected with the rated current contacts;
 an intermediate electrode surrounded by said rim of rated current contacts but electrically insulated from the latter;
 said rim of rated current contacts having contact surfaces cooperating with said movable contact element;
 said burn-off rim being arranged within said rim of rated current contacts and rearwardly offset with respect to the contact surfaces of said rated current contacts which cooperate with said movable contact element;
 a substantially tubular-shaped burn-off tip mounted at an end region of the movable contact element;
 said burn-off rim, in the cut-on position of the switch, surrounds said burn-off tip and said burn-off tip engages with said intermediate electrode.

4,296,290

SAFETY LOCK-ON MOTOR CONTROL


David G. Peot, Easley, S.C., assignor to The Singer Company, Stamford, Conn.

Filed Jan. 16, 1980, Ser. No. 112,681

Int. Cl.³ H01H 9/20

U.S. Cl. 200—325

7 Claims



1. In a trigger control for motor tools, or the like, incorporating a lock-on button on the side thereof; blocking means for blocking the lock-on button in a first rotational position of said button preventing an inadvertent depression but which enables the lock-on button to be rotated to a second rotational position and then depressed to provide a lock-on mode of operation which is easy to effectuate intentionally and having biasing means for automatically rotating said button when released from said second rotational position to said first rotational position so that such lock-on action is yet difficult to effectuate accidentally.

4,296,291

ELEVATOR CONTROL ADAPTOR FOR HANDICAPPED USERS

Lester E. Johnson, Rte. #2, Box 40, Glyndon, Minn. 56547

Filed Jan. 25, 1980, Ser. No. 115,487

Int. Cl.³ H01H 3/20


U.S. Cl. 200—331

16 Claims

1. A method of making both the floor buttons and the car control buttons of a pre-installed self-service elevator system usable by persons unable to easily reach them, which comprises:

(a) establishing generally adjacent to each set of pre-installed floor and car control buttons an array of auxiliary buttons equal in number to the buttons in the adjacent set, wherein the auxiliary buttons in each array are located at a height

which is easily reached by the persons who are unable to easily reach the floor and car control buttons;
 (b) operatively connecting each of the auxiliary buttons in each array to a corresponding one of the buttons in the adjacent set by mechanically linking the auxiliary buttons to the corresponding buttons in the adjacent set such that



an inward actuating movement on one of the auxiliary buttons translates through the mechanical linkage to an inwardly actuating movement to its corresponding button in the adjacent set; and
 (c) allowing all of the pre-installed floor and car control buttons to be individually operable in a normal manner by other persons who can easily reach these buttons.

4,296,292

VARIABLE ELECTROMECHANICAL DEVICE

Christian Schuberth, Bad Neustadt, and Rudolf Hartmann, Salz, both of Fed. Rep. of Germany, assignors to Preh Elektrofeinmechanische Werke Jakob Preh Nachf. GmbH & Co., Bad Neustadt, Fed. Rep. of Germany


Filed Nov. 16, 1979, Ser. No. 94,891

Claims priority, application Fed. Rep. of Germany, Nov. 24, 1978, 2850835

Int. Cl.³ H01H 3/08; H01C 10/00

U.S. Cl. 200—336

7 Claims



1. A variable electromechanical device, comprising
 (a) a housing having a bore;
 (b) an actuation shaft rotatably mounted in the bore and having an annular groove;
 (c) a portion of the housing being displaced by stamping to extend into the annular groove of the shaft for preventing axial movement of the shaft within the bore;
 (d) at least one projection formed on the shaft within the annular groove to cooperate with said displaced portion for limiting the rotation of the shaft relative to the housing;
 (e) a high-viscosity liquid filling said annular groove, and
 (f) liquid passage means associated with said projection to allow said liquid to pass from one side of the projection to the other side thereof when the shaft is rotated.

4,296,293

PROGRESSIVE WELDING AND FORGING OF OVERLAPPED SEAMS IN TUBULAR BODIES


Howard L. Gerber, Park Forest, Ill., assignor to The Continental Group, Inc., New York, N.Y.

Filed Feb. 25, 1980, Ser. No. 124,414

Int. Cl.³ B23K 13/02; H05B 6/40

U.S. Cl. 219—8.5

30 Claims



1. A method of forming a tubular body with a welded longitudinal seam, said method comprising the steps of providing an unseamed tubular body, axially advancing the tubular body while guiding free edges of the body into overlapped relation, introducing electrical energy into the tubular body to heat the overlapped body free edges to a bonding temperature, lightly urging the heated free edges into bonding contact substantially without deformation of the free edges, and then forging the bonded still heated overlapped edges to effect a complete welding of the overlapped edges and materially reducing the thickness of a joint between the overlapped edges.

18. Apparatus for forming a welded side seam in a sheet metal tubular member, said apparatus comprising means for moving a rounded tubular member along a predetermined path with edge portions of the members in circumferentially overlapped relation, heating means disposed along said path for heating the edge portions to a welding temperature, pressing means disposed along said path adjacent said heating means for lightly urging the heated edge portions into bonded engagement, and forge means downstream of said pressing means for forging the bonded overlapped edge portions to effect a complete welding of the overlapped edge portions while materially reducing the thickness thereof.

4,296,294

METHOD AND APPARATUS FOR DRYING AND SETTING THE ADHESIVE ON BOOKS BY VAPORIZATION OF WATER USING RF ENERGY

Alexander Beckert, Wien-Osterreich, Austria, and Karl-Heinz Knobbe, Ellerbeck, Fed. Rep. of Germany, assignors to Reinhard Mohn GmbH, Gutersloh, Fed. Rep. of Germany


Continuation of Ser. No. 728,576, Oct. 1, 1976, abandoned, which is a continuation-in-part of Ser. No. 581,616, May 29, 1975, Pat. No. 4,014,732. This application Nov. 13, 1978, Ser. No. 960,269

Claims priority, application Fed. Rep. of Germany, Jun. 1, 1974, 2426704; Nov. 29, 1975, 2553816

Int. Cl.³ H05B 6/54; B32B 19/02

U.S. Cl. 219—10.41

7 Claims



1. An improved method for drying and setting an adhesive layer applied to the backs of book blocks by passing the book blocks by means of clamps along a travel path through a high

frequency leakage field to vaporize the water in the adhesive, the improvement comprising the steps of: subjecting the adhesive layer on the back of said book blocks to a high frequency leakage field of high strength to heat the adhesive layer to a desired vaporization and drying temperature; maintaining said desired temperature until said adhesive layer is completely dried and set by varying the strength of said high frequency leakage field along said travel path, said field strength initially being substantially reduced following heating of said adhesive layer to said desired temperature and thereafter continuously increased in inverse proportion to the dielectric loss factor of said adhesive layer, said high frequency leakage field being produced by a plurality of RF electrodes spaced apart along one side of the travel path of said book blocks in an oblique manner relative to said travel path and wherein said step of subjecting and maintaining comprises varying the spacing between said electrodes along said travel path, said electrodes being spaced relatively close together at the beginning and end of said travel path and being spaced further apart in the center range of said travel path, with the spacing between said electrodes decreasing from said center range to the end of said travel path, and wherein adjacent electrodes are fed with 180° phase displaced voltages so that the voltage difference between adjacent electrodes is larger than between an electrode and a clamp.

4,296,295

INDUCTION HEATING COIL

Mitsuyuki Kiuchi, Minoo, Japan, assignor to Matsushita Electric Industrial Co., Ltd., Kadoma, Japan
Filed Mar. 25, 1980, Ser. No. 133,685

Claims priority, application Japan, Apr. 4, 1979, 54/44205[U]
Int. Cl.³ H05B 5/04

U.S. Cl. 219—10.49 R

4 Claims

1. A flat spiral wound induction heating coil of inner and outer pitch for a cooking appliance of the induction heating type which comprises a coil winding of litz wire having inner and outer turns, the outer turns being directly adjacent with each other and having a substantially uniform pitch, and a strip of electrically insulating material which is wound along between and adjacent to only said inner turns of said coil winding of litz wire so as to provide a comparatively larger, substantially uniform winding pitch for said inner turns of litz wire than the pitch of said outer turns thereof and thereby providing a uniform temperature distribution across the bottom of the cooking appliance.

4,296,296

CONTROLLABLE-DUTY-CYCLE POWER SUPPLY FOR MICROWAVE OVEN MAGNETRON AND THE LIKE


Charles W. Eichelberger; Rudolph A. Dehn, both of Schenectady, and Robert J. Wojnarowski, Clifton Park, all of N.Y., assignors to General Electric Company, Schenectady, N.Y.

Filed Aug. 13, 1979, Ser. No. 66,300

Int. Cl.³ H05B 6/66

U.S. Cl. 219—10.55 B

9 Claims



1. A controllable-duty-cycle power supply for connection between a sinusoidal power source and a load consuming

appreciable amounts of power only if a minimum voltage applied thereto is exceeded, comprising:

- a power transformer having a primary winding connected to said source and a high-voltage secondary winding having first and second ends;
- a capacitance element connected in electrical series connection with said secondary winding first end and said load;
- means connected to the junction between said capacitance element and said load for allowing unidirectional flow of current in only one of the directions toward and from said junction;
- a non-linear resistance element in electrical series connection with said unidirectional means across said load; said non-linear resistance element providing a relatively high resistance for all voltages thereacross less than a predetermined breakdown voltage which is less than said minimum voltage and sufficiently large to prevent application of said minimum voltage to said load, and providing a relatively low resistance when the voltage thereacross exceeds said breakdown voltage;
- a gateable element in electrical parallel connection with said non-linear resistance element, said gateable element having a breakdown voltage greater than said non-linear resistance element and less than said minimum voltage and being controllable to conductive and nonconductive conditions respectively to cause the voltage across said load to be respectively at least said minimum voltage and less than said minimum voltage and said load to be respectively power-consuming and non-power-consuming responsive respectively to first and second amplitudes of a controlling signal; and

means for providing said controlling signal of said first amplitude at a frequency at least two orders of magnitude higher than the frequency, at all phase angle relationships of each cycle, of said sinusoidal power source and with a controllable ratio of the time interval during which said relatively high frequency control signal is present to the entire time interval between successive intervals of control signal.

4,296,297

DRIVE ARRANGEMENT FOR MICROWAVE OVEN MODE STIRRER


Matthew S. Miller, Louisville, Ky., assignor to General Electric Company, Louisville, Ky.

Filed Dec. 26, 1979, Ser. No. 106,649

Int. Cl.³ H05B 6/74

U.S. Cl. 219—10.55 F

6 Claims



1. A microwave energy stirrer assembly for a microwave oven, said stirrer including stirrer blades mounted for rotational movement in the path of microwave energy into said oven, a vertical mounting shaft, said blades mounted adjacent the lower end of said shaft, a drive fan carried by said shaft adjacent the end remote from said stirrer blades, said stirrer blades adapted when rotated to change the microwave energy field pattern in said oven, air channeling means for directing a flow of air into contact with said drive fan to rotate said fan and consequently said shaft and mode stirrer blades, and a

cylindrical bearing for supporting said assembly, said drive fan comprising a plurality of blades having surfaces facing said flow of air, said surfaces being shaped to lift said assembly axially from said bearing during rotation.

4,296,298

DIELECTRIC COOKING APPARATUS

George H. MacMaster, Lexington, and Kenneth W. Dudley, Sudbury, both of Mass., assignors to Raytheon Company, Lexington, Mass.


Continuation of Ser. No. 914,694, Jun. 12, 1978, abandoned.

This application Nov. 5, 1979, Ser. No. 91,004

Int. Cl.³ H05B 6/54

U.S. Cl. 219—10.81

3 Claims



1. A dielectric heating oven comprising: an enclosure; a source of RF energy; means for substantially terminating both ends of electric fields in a plane, said terminating means comprising a plurality of at least four elongated parallel electrodes positioned in said plane in said enclosure and spaced apart substantially less than a free space wavelength of said energy; means for electrically grounding alternate electrodes of said plurality; means for coupling said RF energy from said source to the remaining ungrounded electrodes of said plurality for cooking food positioned adjacent to said plane, said coupling means comprising means for selecting between deep or shallow cooking effects in said food, said selecting means including means for selectively varying the phase difference between the phase of energy coupled to one of said ungrounded electrodes and the phase of energy coupled to a second of said ungrounded electrodes; and said phase difference is selectable between approximately 90°, 180° and 270° out of phase.

4,296,299

APPARATUS FOR THAWING FROZEN FOOD IN A REFRIGERATION APPLIANCE

Richard L. Stottmann, Louisville, and Peter H. Smith, Anchorage, both of Ky., assignors to General Electric Company, Louisville, Ky.

Filed Dec. 31, 1979, Ser. No. 108,755


Int. Cl.³ H05B 6/46

U.S. Cl. 219—10.81

5 Claims

1. For use in a refrigeration appliance, apparatus for thawing a frozen food load comprising: a food thawing enclosure including top, bottom and side walls comprised of electromagnetic radiation shielding material and adapted to be positioned within and in good thermal communication with the low temperature atmosphere of the refrigeration appliance, said enclosure including first and second electrodes defining a food thawing zone therebetween; means for moving at least one of said electrodes to permit

removable placement of the food load in the thawing zone with both electrodes in close physical proximity to the food loads during the thawing process; and means for supplying high frequency electromagnetic energy to said electrodes to thaw the food,



whereby the food load can be thawed and subsequently maintained at the food preservation temperature of the refrigeration appliance.

4,296,300

METHOD AND DEVICE FOR WELDING PROTECTED METAL PARTS


Augusto Bottiglia, Milan, Italy, assignor to Sio-Societa per l'Industria Dell'Ossigeno e di Altri Gas, Milan, Italy

Filed Dec. 19, 1978, Ser. No. 971,105

Claims priority, application Italy, Dec. 23, 1977, 31263 A/77
Int. Cl.³ B23K 9/23

U.S. Cl. 219—61.7

9 Claims



1. A method for welding metal protected by a coating of a material which volatilizes at a temperature less than the welding or brazing temperature of the metal, the method comprising, in combination: forming a weld on the metal through the use of an electric arc; cooling a selected localized portion of the coating in the immediate vicinity of the weld by applying a cryogenic cooling fluid to the coating, to maintain said coating at a temperature below its volatilization temperature during the formation of the weld; detecting the temperature of the coating portion during the formation of the weld; and adjusting the cooling effect of the cryogenic fluid in accordance with the detected temperature.


4,296,301

DIE FORMING METHOD AND MACHINE
Romain H. Johnson, 925 - 6th St. SE., Minneapolis, Minn. 55414

Continuation of Ser. No. 772,433, Feb. 28, 1977, abandoned.
This application Sep. 12, 1978, Ser. No. 941,385
Int. Cl.³ B23P 1/00

U.S. Cl. 219—69 M

15 Claims



1. The method of forming a complete die from a blank and a die set having an upper shoe, a lower shoe, and guide means mounting the upper shoe on the lower shoe whereby the upper shoe can be moved toward and away from the lower shoe in a linear direction comprising the steps of:

severing a single blank to form a rough-cut female die block having an opening therethrough whereby the portion of the blank defined within the opening forms a rough-cut male die punch block complementary thereto and peripherally spaced from the female block when centered therein;

said severing forming adjacent rough-cut side walls on said female die block opening and said male punch block that are substantially parallel at any point therearound and tapered convergently in the direction of intended die draft to define respectively smaller and larger openings on said female block and end surfaces on said male block on either side thereof with the larger end surface of said male block greater in size than the smaller opening of the female block, said taper of the rough-cut walls being greater than the taper of the intended die draft;

securing said male block to an upper die set shoe with the larger end surface of the block spaced downwardly therefrom, securing said female die block to a lower die set shoe with the smaller block opening spaced upwardly therefrom and said female block in surrounding relation to said male block;

aligning said die set shoes with said guide means for vertical relative movement in said linear direction so as to center the male block within the female block opening and with said male and female block walls in laterally spaced relation;

securing said upper die set shoe to an extractor, securing said lower die shoe to a bed, and,

moving the male punch block and female die block relative to each other in a direction in opposition to the taper of the side walls of the punch block and die opening while simultaneously effecting material-removing erosion between the male die punch block and the female die block to generate preselected die clearance and die draft.

4,296,302


ADAPTIVE CONTROL OF GAP VOLTAGE AND POWER TO CONTROL SERVO OPERATION OF AN ELECTRICAL DISCHARGE MACHINING APPARATUS
Oliver A. Bell, Jr., Statesville; Randall C. Gilleland, Troutman, and Davey J. Chance, Concord, all of N.C., assignors to Colt Industries Operating Corp., New York, N.Y.

Filed Aug. 21, 1979, Ser. No. 68,329

Int. Cl.³ B23P 1/02

U.S. Cl. 219—69 G

7 Claims



1. In an electrical discharge machining apparatus, an adaptive control system for providing relative movement between an electrode and a workpiece defining a machining gap including a servo feed motor and an electrically operated element for controlling said motor, comprising:

a first servo feed circuit including a gap voltage sensing network and a reference voltage network operably connected to said element for operating it responsive to the difference of voltage therebetween;

a second servo feed circuit including a second network for sensing gap voltage;

means for converting the output of said second network for sensing gap voltage to a first digital value;

means for comparing such first digital value to a predetermined and prestored digital value; and representative of optimum machining level;

means for providing an analog output responsive to difference between said digital values and providing a second control output to modify the operation of said element and thus of said servo feed motor; and

a summing network operatively connected to the outputs of said first and second servo feed circuits for combining them before passing them to said electrically operated element.

4,296,303

METHOD FOR MAKING INTERCELL CONNECTIONS IN MULTI-CELL STORAGE BATTERY

Kensaku Tsuchida, Kamakura, and Shinji Karasawa, Chigasaki, both of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Kadoma, Japan


Filed Jul. 26, 1979, Ser. No. 60,873

Claims priority, application Japan, Oct. 6, 1977, 52-120576

Int. Cl.³ B23K 11/14

U.S. Cl. 219—78.13

14 Claims



1. In a method for making an intercell connection in a multi-cell storage battery including, in each unit cell separated by at

least a partition wall having an opening for said intercell connection, a pair of connectors integral with straps electrically conductive to electrode assemblies of one polarity and of the other polarity, wherein one of the connectors has a projection formed integral therewith and extending therefrom passing through said opening, and the other of the connectors has an aperture with an axis extending in the longitudinal direction of said projection to accept said projection extending through said opening, the method comprising the steps of:

(a) positioning said one and the other connectors of neighboring unit cells in contact with opposite sides of said partition wall so that said projection passes through said opening into said aperture to form a fit joint inbetween;

(b) causing said fit joint to be fused together by supplying said fit joint with heat sufficient for welding said projection with said aperture by applying an outside heating electrode to said fit joint with a back face of said other of the connectors being pressed by said heating electrode toward said connector and causing a heating current to flow between said projection and said heat electrode while pressing said connectors against said partition wall by a pair of pressing members, and

(c) continuing said pressing condition for a predetermined period of time after a completion of said heating operation.

4,296,304

ELECTRODE DISPLACEMENT MONITORING IN RESISTANCE WELDING

Jacques Defourny, Herstal, Belgium, assignor to Centre de Recherches Metallurgiques-Centrum voor Research in de Metallurgie, Brussels, Belgium


Filed Sep. 19, 1978, Ser. No. 943,798

Claims priority, application Luxembourg, Sep. 20, 1977, 78152

Int. Cl.³ B23K 11/10

U.S. Cl. 219—86.41

3 Claims



1. In combination with a resistance welding machine comprising a main welding machine frame structure supporting a pair of first and second electrodes having a common alignment axis, apparatus for monitoring the operation of the welding machine, the apparatus comprising:

a single sensor for measuring displacement of the electrodes relative to each other during welding, the sensor having an axis along which the said displacement is measured, the said axis of the sensor and said common alignment axis of the electrodes being mutually parallel, the distance between the said axes being sufficiently small to render negligible any inadvertent small variation in parallelism between said sensor axis and said common alignment axis, wherein said single sensor is fixed to the first electrode, the apparatus further comprising a second frame member, separate from said main frame structure and having two

transverse elements, which are substantially perpendicular to the said alignment axis, and a longitudinal element interconnecting the transverse elements, one of the transverse elements being fixed to the second electrode, the other of the transverse elements being connected to the sensor, the longitudinal element being spaced from the electrodes by a distance which is only slightly less than the spacing between the electrodes and the main welding machine frame.

4,296,305

MACHINE FOR CONTINUOUS FLASH BUTT WELDING


Viktor S. Lifshits, Kavkazsky bulvar, 21, korpus 2, kv. 41, Moscow; Vadim P. Krivonos, Krasnoarmeiskaya ulitsa, 45, kv. 92, Kiev; Nikolai V. Podola, ulitsa Pushkinskaya, 8, kv. 12, Kiev; Boris L. Grabchev, ulitsa Tupoleva, 5, kv. 4, Kiev; Vladimir R. Andrianov, proezd Zarevoi, 3, kv. 19, Moscow, and Rifkhat M. Shakirov, ulitsa Khudaiberdina, 1, kv. 16, Ufa, all of U.S.S.R.

Filed Apr. 10, 1979, Ser. No. 28,876

Int. Cl.³ B23K 11/04

U.S. Cl. 219—101

5 Claims



1. A machine for continuous flash butt welding of parts, comprising:

a welding transformer with a primary winding and a secondary winding;

a frame;

a movable clamping jaw and a stationary clamping jaw mounted on said frame for clamping workpieces mounted thereon;

a follow-up slide valve including a valve body and a rod; hydraulic actuator means for displacing said movable clamping jaw and governed by said follow-up slide valve;

an automatic flashing-off speed control device;

a computer having an output, and including an automatic beginning-of-upset control device and an automatic upset value control device having an input, said computer, said automatic beginning-of-upset control device and said automatic upset value control device being incorporated in one unit;

a welding current meter forming one element of a welding circuit, and having an input connected to said primary winding of the welding transformer, and having an output;

first sensor means connected to the output of said welding current meter for detecting a short-circuit duration in the welding circuit;

control means having an output for controlling an upset value deviation, and provided with second sensor means for detecting slippage of said workpieces mounted on and welded in said clamping jaws;

third sensor means mounted on said follow-up slide valve for indicating misalignment of said rod of said follow-up slide valve relative to said valve body, and having an input and an output, said output of the third sensor means being connected to the input of said control means;

a welding control enabling signal generator having an input and outputs, said input of the welding control enabling signal generator being connected to the output of said computer, said outputs of the welding control enabling

signal generator being connected to said first sensor means for detecting short-circuit duration in the welding circuit and to said control means; and
actuators of said automatic flashing-off speed, beginning-of-upset and upset value control devices for controlling the flashing-off speed, beginning of upset operation, and upset value, respectively, being combined in a further single unit.

4,296,306


METHOD OF WELDING CORRUGATED METALLIC MATERIALS

Hirokazu Nomura, and Tadashi Fujioka, both of Tsu, Japan, assignors to Nippon Kokan Kabushiki Kaisha, Tokyo, Japan
Filed Sep. 12, 1979, Ser. No. 75,165

Claims priority, application Japan, Sep. 29, 1978, 53-119264
Int. Cl.³ B23K 9/12

U.S. Cl. 219—124.34

1 Claim



1. A method for welding corrugated metallic materials wherein a lifting block is vertically movably mounted on a welding apparatus proper which is movable in a horizontal direction on a track extending along a weld line and a rotating block carrying a welding torch is mounted on said lifting block, comprising the steps of:

mounting said welding torch to said rotating block by way of an arc length controlling drive block; comparing a change in an arc voltage with an arc length setting voltage; controlling an arc length control motor mounted on said arc length controlling drive block in response to a difference signal resulting from said comparison so as to maintain the arc length constant; controlling a lifting block drive motor in accordance with the rotational angle of said arc length control motor so as to bring the tip position of said welding torch into coincidence with the center of rotation of said rotating block; controlling a rotating block drive motor in response to signals from an obliquity detector disposed integrally with said torch and ahead thereof with respect to the direction of welding so as to maintain said torch at an angle corresponding to the oblique angle of the material to be welded; and controlling a welding apparatus proper traversing motor in response to a signal corresponding to said torch angle so as to maintain the welding speed constant.

4,296,307

MANUFACTURING METHOD OF THE VALVE DISK OF SPRING LOADED SAFETY VALVES

Noboru Hagihara, Nishinomiya, Japan, assignor to TOA Valve Co. Ltd., Toribayashi Amagasaki, Japan

Filed Oct. 9, 1979, Ser. No. 82,909


Claims priority, application Japan, Oct. 9, 1978, 53-124440
Int. Cl.³ B23K 15/00

U.S. Cl. 219—121 ED

4 Claims

1. A method of manufacturing a valve disk for a spring-loaded safety valve, said valve disk comprising a cup-shaped center portion and a cylinder portion annularly fitted thereto, said center portion having a central longitudinal axis, a lower

end, an outer periphery, a stepped annular recess about said lower end, and an annular protrusion axially-extending from said lower end and spaced radially inward of said stepped recess, said cylinder portion having an upper end, a lower end, an inner periphery and a radially inward extending annular valve-lip flange, said annular flange being made of continuous metal fibers and being formed by bending said lower end radially inwards, said upper end of said cylinder portion being fitted in said stepped recess, thereby forming a first contacting surface in a radial plane, said method comprising forming at least one annular stage portion on said center portion radially inwardly of said stepped recess and radially outwardly of said annular protrusion;



forming at least one matching annular stage portion on said inner periphery of said cylinder portion;

fitting said cylinder portion to said center portion contacting said at least one annular stage portion to said at least one matching annular stage portion thereby forming a second contacting surface while establishing a uniform spacing between said annular protrusion and said annular flange; and welding said cylinder portion to said centering portion by electronic beam at said first contacting surface whereby said second contacting surface takes up any heat distortion generated by the welding so that said uniform spacing is maintained constant.

4,296,308

APPARATUS FOR WELDING IMPELLER


Syuhei Nakahama, and Etsu Yamashita, both of Chiba, Japan, assignors to Carrier Corporation, Syracuse, N.Y.

Filed Sep. 6, 1979, Ser. No. 72,843

Claims priority, application Japan, Sep. 6, 1978, 53/109274
Int. Cl.³ B23K 9/225

U.S. Cl. 219—136

10 Claims



1. An apparatus for welding an impeller blade to a supporting plate of an impeller in which the impeller is held in a position to define between the impeller blade and the plate a V-shaped channel having an apex constituting a weld line including a straight horizontal portion and further including a curved portion extending continuously from the straight hori-

zontal portion and within a plane inclined with respect to a horizontal plane, said apparatus comprising:

a welding torch assembly having a tungsten electrode, a nozzle surrounding said electrode and in which said electrode is mounted and having a passage for an inert gas, said nozzle having an exterior shape with the opposite sides thereof shaped for contacting the inner surfaces of said V-shaped channel for maintaining a substantially fixed distance between the tip of said electrode and the straight horizontal portion of the apex of said V-shaped channel, a torch rod having said torch nozzle mounted on one end thereof and a gas pipe for supplying the inert gas to said nozzle; and

a translating mechanism on which the other end of said torch rod is mounted for universal pivoting movement relative to said head, said translating mechanism being movable for moving said torch head along and above the weld line with said nozzle engaging the inner surfaces of said V-shaped channel under the effect of gravity;

the size of the lower portion of said nozzle from the center line thereof to at least one end of the nozzle facing in the direction of the length of the apex line being reduced sufficiently to give the nozzle a shape for keeping the space between said electrode and the apex of the channel substantially the same as the spacing in the straight horizontal portion of the apex during movement of said nozzle along the curved portion of the apex by avoiding interference of the nozzle with the inner surface of the V-shaped channel during movement along the curved portion of the apex.

4,296,309

THERMAL HEAD

Akira Shinmi, Kawasaki; Masahisa Fukui, Yokohama; Toshitami Hara, Tokyo; Yoshiaki Shirato, Yokohama, and Yoshiaki Hajimoto, Chofu, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan


Filed May 15, 1978, Ser. No. 906,359

Claims priority, application Japan, May 19, 1977, 52-57936; Aug. 30, 1977, 52-103975; Sep. 7, 1977, 52-107522; Sep. 16, 1977, 52-111329; Oct. 13, 1977, 52-122622; Oct. 13, 1977, 52-122623; Oct. 13, 1977, 52-122624; Oct. 13, 1977, 52-122625; Oct. 28, 1977, 52-129482; Oct. 28, 1977, 52-129483; Oct. 28, 1977, 52-129484; Oct. 28, 1977, 52-129485; Oct. 28, 1977, 52-129486; Oct. 31, 1977, 52-131260; Oct. 31, 1977, 52-131261; Oct. 31, 1977, 52-131262; Dec. 28, 1977, 52-160137; Dec. 28, 1977, 52-160138; Dec. 28, 1977, 52-160139; Dec. 28, 1977, 52-160140; Dec. 28, 1977, 52-160143; Dec. 28, 1977, 52-160144; Dec. 28, 1977, 52-160145; Dec. 28, 1977, 52-160146; Dec. 28, 1977, 52-160147; Dec. 28, 1977, 52-160148; Dec. 28, 1977, 52-160149; Jan. 9, 1978, 53-1033; Jan. 9, 1978, 53-1034; Jan. 9, 1978, 53-1035; Jan. 11, 1978, 53-1806; Feb. 10, 1978, 53-14282; Feb. 10, 1978, 53-14283

Int. Cl.³ H05B 1/00

U.S. Cl. 219—216

36 Claims



1. A thermal head comprising means for producing a pattern on a recording medium in accordance with information to be recorded, said means including a substrate, a thin film resistive heater element overlying the substrate, and electrically conductive members overlying the resistive heater element for supplying the resistive heater element with electric power, wherein the resistive heater element comprises a metal boride:

4,296,310

COOKING DEVICE WITH WATER DETECTING MEANS


Clement J. Luebke, Beloit, Wis.; John A. Mitchell, and Lowell W. Daniels, both of Rockford, Ill., assignors to Alco Standard Corporation, Valley Forge, Pa.

Filed Aug. 20, 1979, Ser. No. 68,108

Int. Cl.³ F27D 11/02

U.S. Cl. 219—440

7 Claims



1. A pressure fryer comprising a vessel adapted to hold a food product and cooking oil, a removable cover for establishing a pressure-tight condition within said vessel, means for heating said vessel and the contents thereof, an electrical circuit for controlling said heating means, means in the lower portion of said vessel for detecting the presence of water in the lower portion of said vessel and for producing an electrical signal when more than a predetermined quantity of water is present in said vessel, and means in said circuit for automatically disabling said heating means when said signal is produced.

4,296,311

ELECTRIC HOT PLATE


Erik H. M. Hagglund, New Canaan, and Roger R. Giler, Wilton, Conn., assignors to The Kanthal Corporation, Bethel, Conn.

Filed Aug. 15, 1979, Ser. No. 66,684

Int. Cl.³ H05B 3/74

U.S. Cl. 219—464

1 Claim



1. An electric cooking stove assembly comprising a glass plate, a convoluted molybdenum disilicide electric resistance heating wire forming a layer of interspaced convolutions substantially parallel with and spaced below said plate and having ends for connection with electric power, a refractory fibrous pad positioned below and completely free from contact with said layer and having a flat top surface substantially parallel with said layer, and means for supporting said layer so that when hot it radiates heat upwardly both directly and by reflection from said fibrous pad, the molybdenum disilicide wire of said element having a diameter and length which causes the wire to heat to temperatures substantially above 2000° F. when electrically powered at its rated voltage and at least the pad's said top surface having a substantially white color causing

appreciable diffused reflection of thermal energy having wave lengths inherent to said temperatures, said means comprising interspaced support wires having lower ends stuck in said fibrous pad, said support wires extending straight upwardly from the pad's said top surface, said wires having upper portions spaced above said pad and forming loops in which said molybdenum disilicide wire is positioned and thereby supported, said support wires having diameters no greater than said diameter of said molybdenum disilicide and made of metal alloy of the Fe-Cr-Al type and having an oxide coating protecting against reaction with said element.

4,296,312

ELECTRONIC TEMPERATURE SENSING SYSTEM FOR TOASTER APPLIANCES


Robert J. Salem, Danbury, Conn., assignor to General Electric Company, New York, N.Y.

Continuation of Ser. No. 802,422, Jun. 1, 1979, abandoned. This application Nov. 19, 1979, Ser. No. 95,867

Int. Cl.³ H05B 1/02

U.S. Cl. 219—501

31 Claims



1. A temperature sensing system for sensing the heat applied to bread or other food article when loaded within the toast compartment of a toaster appliance so as to provide a consistent toast color for a given toast color setting for each toasting operation irrespective of starting conditions, comprising:

- first means, including a single temperature sensor to be positioned within the toast compartment of a toaster appliance and having an electrical characteristic which varies as a function of temperature, for providing a first electrical signal that is a function of the temperature of bread or a food article loaded within said toast compartment,
- second means to be positioned remote from the toast compartment for providing a second electrical signal that is a function of the ambient temperature in the vicinity of the loaded bread or other food article, said second signal being a function of the integral of said first electrical signal,
- third means for providing a third electrical signal that is a function of the difference between said first and second signals,
- fourth means for providing a fourth electrical signal that is invariant with respect to a given toast color as determined by the toast color setting, and
- fifth means responsive to the third and fourth signals for providing a fifth electrical signal for terminating the toasting operation upon said loaded bread or other food article having reached said given toast color.

4,296,313

GEAR SYSTEM AND METHOD OF ASSEMBLY

John A. Horner, 211 Grove St., Kawkawlin, Mich. 48631, and Dale W. Wright, Saginaw, Mich., assignors to John A. Horner, Kawkawlin, Mich.

Filed Dec. 26, 1979, Ser. No. 106,913


Int. Cl.³ G06C 25/00

U.S. Cl. 235—61 L

12 Claims

1. An adapter bevel gear for interposition between a driving first bevel gear and a driven second bevel gear normally in

mesh with said first gear so as to be driven by the latter at a predetermined speed ratio relative thereto, said adapter gear comprising a body formed of resilient material and having an internal, frustoconical cavity of such size as snugly to accommodate one of said first and second gears, said cavity having tooth-accommodating recesses therein for the snug accommo-



date of each of the gear teeth of said one of said gears, said adapter gear having a frustoconical exterior provided with teeth of such size as to mesh with those of the other of said first and second gears, the number of said external teeth being greater than the number of tooth accommodating recesses in said cavity, thereby to change said ratio.

4,296,314

NON-CONTACT COUNTER


Kenneth W. Dabisch, and John S. Richards, both of Bolingbrook, Ill., assignors to Rockwell International Corporation, Pittsburgh, Pa.

Filed Nov. 26, 1979, Ser. No. 97,472

Int. Cl.³ G06M 7/00

U.S. Cl. 235—92 SB

2 Claims



1. Apparatus for counting newspapers moving in overlapped relationship in a continuous stream comprising:

- a source of pulsed radiant energy disposed to direct a stream of energy against the overlapped papers in a direction substantially normal to the direction in which the papers are moving;
- an energy sensor on each side of said radiant energy source to receive nonrefracted omnidirectional energy that is reflected from the stream of moving papers;
- sensor comparator means connected to each of said energy sensors;
- digital signal processing means connected to said sensor comparator means and responsive to the occurrence of a preselected number of consecutive validated pulses to deliver a count pulse indicating the passage of a paper past the energy source; and
- control and timing connected to (i) said source of radiant energy, (ii) to said sensor comparator means and (iii) to said digital signal processing means to pulse said source of radiant energy and to provide a clock pulse to said digital processing means.

4,296,315

CARD READER SECURITY SYSTEM


Dan G. Weimer, Scottsdale, and Bradford O. Van Ness, Paradise Valley, both of Ariz., assignors to Engineered Systems, Inc., Tempe, Ariz.

Filed Apr. 16, 1979, Ser. No. 30,308

Int. Cl.³ G06K 7/08, 7/10, 19/06

U.S. Cl. 235—460

6 Claims



1. A security system for a card reader for reading data encoded on cards having a magnetic shield area located on the cards and covering at least two spaced points therein, said security system including in combination;

- a card entry throat in the card reader having a slot therein to accommodate cards to be inserted into the reader;
- two spaced-apart magnetically actuated switch means located on one side of the slot in said card entry throat;
- two corresponding spaced-apart permanent magnet means located on the other side of the slot in said card entry throat opposite different ones of said two spaced-apart magnetically actuated switch means respectively, each of said magnet means having a field of sufficient strength to operate the corresponding switch means located opposite such magnet means, the relative locations of said switch means and said permanent magnet means being such that the shield area of an inserted card breaks the field from the permanent magnet means operating on the corresponding one of said switch means;
- card insertion sensing switch means operated from a first state of operation to a second state of operation only when a card is fully inserted into the card reader for reading thereby; and
- electrical control circuit means connected with each of said two spaced-apart magnetically actuated switch means and said card insertion switch means and operated thereby only when a card having a magnetic shield area covering said at least two spaced points thereon in the proper area thereof is fully inserted into the card reader for reading thereby.

4,296,316

OPTICAL FOCUSING DEVICE

Shigeo Tsuji, Fujisawa, and Takahisa Aikawa, Yokohama, both of Japan, assignors to Tokyo Shibaura Denki Kabushiki Kaisha, Kawasaki, Japan

Filed Dec. 18, 1979, Ser. No. 104,803

Claims priority, application Japan, Dec. 25, 1978, 53-158529


Int. Cl.³ G01J 1/36

U.S. Cl. 250—204

4 Claims

1. An optical focusing device for an optical information read-out system comprising:
 - an object lens for focusing a light beam onto the surface of a data carrier, thereby forming a projected image on the surface of the data carrier;
 - means for moving said objective lens along the optical axis of said objective lens;
 - light beams orienting means positioned in the light beam path between said objective lens and said light source for orienting the light beam toward said objective lens to change the position of the projected image of the light beam on the surface of the data carrier;
 - optical guiding means for guiding part of the light beams

reflecting from or transmitted through the surface of the data carrier onto an observation plane; photodetecting means disposed on said observation plane which detects a shape of the projected image of the light beam guided by said optical guiding means and is comprised of a first narrow photoelectric surface extending in the direction of movement of the projected image of the light beam which is effected by said light beam orienting



means, and second and third photoelectric surface closely disposed to the first photoelectric surface; means for summing the signals detected by said second and third surface; and electrical means for comparing the output signal from said summing means with the detected signal from said first photoelectric surface to provide a signal to said lens moving means, thereby moving said objective lens to a predetermined position.

4,296,317

PAINT APPLICATION METHOD AND MACHINE


Roland Kraus, Mainlande 7, 8702 Veitshöchheim, Fed. Rep. of Germany

Filed Jan. 8, 1979, Ser. No. 1,437

Int. Cl.³ G01D 15/18

U.S. Cl. 250—215

26 Claims



1. A paint application method comprising the steps of: guiding the spray opening of a spray gun at a constant distance from the working surface in the zone of picture reproduction; forcing paint into an air flow by pressure; controlling an amount of sprayed paint by the intensity of a light beam striking a photocell and controlled by a picture pattern; and moving photocell and the picture pattern synchronously with guide movement of the spray gun.

4,296,318


OPTO-ELECTRONIC INSTRUMENT FOR REMOTE TEMPERATURE MEASUREMENT

Sergio Mezzetti, Rho; Pierluigi Pizzolati, Cernusco Sul Naviglio, and Francesco Svelto, Rome, all of Italy, assignors to C.I.S.E. Centro Informazioni Studi Esperienze S.p.A., Italy
Filed Sep. 24, 1979, Ser. No. 78,322

Claims priority, application Italy, Sep. 22, 1978, 28012 A/78
Int. Cl.³ G02F 1/01

U.S. Cl. 250—225

7 Claims



1. An opto-electronic instrument for remote temperature measurement, comprising a measuring probe and a remote supply and processing unit connected together by at least one optical fibre, said supply and processing unit including a luminous signal generator for said optical fibre, said measuring probe including at least one polariser, and a temperature-sensitive element constituted by a square cross-section parallelepiped crystal of uniaxial double refraction material disposed with its optical axis at 45° to the plane of polarisation of said polariser, to receive the luminous signal transmitted through said optical fibre and to retransmit it to the same optical fibre in the form of a luminous signal the intensity of which varies sinusoidally with the wavelength, and in which the peaks are spaced apart by a distance dependent on the sensed temperature, said supply and processing unit including a variable frequency filter controlled by a ramp generator for transforming said retransmitted luminous signal into a luminous signal the intensity of which varies sinusoidally with time, an opto-electrical transducer able to convert this latter luminous signal into a corresponding electrical signal of sinusoidal oscillation, and means for calculating the period of oscillation of said electrical signal.

4,296,319

WAVEFORM SYNTHESIZER


Larry A. Franks, and Melvin A. Nelson, both of Santa Barbara, Calif., assignors to The United States of America as represented by the United States Department of Energy, Washington, D.C.

Filed Dec. 7, 1979, Ser. No. 101,369

Int. Cl.³ G02B 5/14

U.S. Cl. 250—227

10 Claims



1. A method of transforming a readily available preselected optical input pulse of one shape into a preselected output

waveform of an arbitrary but defined different shape comprising:

- Providing an array of a plurality of fiber optic waveguides having lengths preselected so that the illumination of one end of the array with said preselected optical input pulse will produce at the other end of said array a chain of optical pulses spaced apart in time in accordance with said preselected lengths, whereby the summation of said chain of pulses will approximate the preselected output waveform,
- Illuminating said one end of the array with said optical input pulse, and
- Combining the outputs of said waveguides at the other end of said array to form a synthesized optical pulse output approximating the preselected shape.

4,296,320

AUTOMATIC GAIN CONTROL FOR RADIATION ANALYZER


Samuel Miller, South Euclid, Ohio, assignor to Victoreen, Inc., Cleveland, Ohio

Filed Apr. 8, 1980, Ser. No. 138,652

Int. Cl.³ G01D 18/00

U.S. Cl. 250—252

9 Claims



8. A method of regulating the system gain of a radiation detecting system comprising the steps of: providing a known radiation source having a known peak in its energy spectrum; detecting radiation particles given off by said known radiation source and providing an electrical pulse in response to the detection of each said particle, said pulses each having an amplitude directly related to the energy of the corresponding detected particle; setting the gain of said pulses in accordance with a stored gain indication; counting the difference between the numbers of particles producing pulses having amplitudes falling within amplitude ranges above and below a preselected amplitude which is desired to correspond to the particle energy at which said known peak is located in said energy spectrum; adjusting said stored indication whenever said difference count exceeds a preselected limit; and, resetting said difference count to an initial value whenever more than a selected number of electrical pulses in a predetermined amplitude range have occurred since the previous reset.

4,296,321

BIT PRESSURE GAUGE FOR WELL DRILLING

Donald W. Blincow, Claremont; Kevin H. Cassidy, Laguna Beach, and Samuel C. Dominey, Jr., Glendora, all of Calif., assignors to Tyco Laboratories, Exeter, N.H.

Filed May 5, 1980, Ser. No. 146,207

Int. Cl.³ G01V 5/00

U.S. Cl. 250—254

6 Claims

1. Apparatus for measuring the pressure on a well drilling bit connected to a drilling platform by a string of drill pipe, including in combination:

first and second sections of drill pipe having telescoping

4,296,322

SECONDARY EMISSION MASS SPECTROMETER MECHANISM TO BE USED WITH OTHER INSTRUMENTATION


Robert L. Gerlach, Minnetonka, Minn., assignor to The Perkin-Elmer Corporation, Norwalk, Conn.

Filed Mar. 10, 1980, Ser. No. 128,932

Int. Cl.³ B01D 59/44

U.S. Cl. 250—289

11 Claims



first section end including window means providing a radiation path between said source and detector means; and

circuit means having said detector means connected as an input and providing as an output a signal varying as a function of radiation intensity at said detector means and hence of the position of said first section relative to said second section, the compression of said spring, and the pressure on said bit.

4,296,322

METHOD FOR ANALYZING ORGANIC SUBSTANCES

Reiner Wechsung, Cologne, Fed. Rep. of Germany, assignor to Leybold-Heraeus Gesellschaft mit beschränkter Haftung, Cologne, Fed. Rep. of Germany


Filed Aug. 27, 1979, Ser. No. 70,333

Claims priority, application Fed. Rep. of Germany, Aug. 30, 1978, 2837715



Int. Cl.³ B01D 59/44

U.S. Cl. 250—282

4 Claims



1. A method for analyzing high molecular weight organic substances exiting from a chromatograph comprising subjecting such substance to laser radiation to produce negative ions therefrom, and subjecting those negative ions to time-of-flight mass spectroscopy.



9. In a high definition spectroanalysis mechanism having capabilities of performing a plurality of analysis including a secondary ion mass spectrometry analysis of a preselected surface area, the mechanism comprising:

- a main vacuum chamber having an opening therein; said main vacuum chamber having means therein for producing secondary ions from said preselected surface area;
- a secondary vacuum chamber communicating with said main chamber through said opening therein;
- a flexible vacuum seal having an opening therein, said seal communicating with said main and secondary vacuum chambers permitting relative movement between said two vacuum chambers;
- means for imparting a limited movement of said secondary chamber with respect to said main chamber;
- a longitudinal extraction lens mechanism disposed adjacent the sample to be tested and extending between said main and secondary vacuum chambers and through said vacuum seal;
- a linear movement device connected to said longitudinal extraction lens mechanism to focus and withdraw said extraction lens with respect to said preselected surface area to be tested; and
- means, within said secondary vacuum chamber, for analyzing said secondary ions from said preselected surface area.

4,296,324


DUAL SPECTRUM INFRARED FIRE SENSOR

Mark T. Kern, Goleta, and Robert J. Cinzori, Santa Barbara, both of Calif., assignors to Santa Barbara Research Center, Goleta, Calif.

Filed Nov. 2, 1979, Ser. No. 90,701
Int. Cl.³ G01J 1/00

U.S. Cl. 250—339

11 Claims



1. An electrical detection system responsive to a fire or explosion for generating an output signal, including in combination:

- (a) long wavelength channel means responsive to radiant energy in a predetermined spectral band greater than about 4 μm of electromagnetic radiation and received from a fire or explosion for generating a first logic signal;
- (b) short wavelength channel means responsive to radiant energy in a predetermined spectral band less than about 3.5 μm of electromagnetic radiation and received from said fire or explosion for generating a second logic signal; and
- (c) output gate means coupled to receive both said first and second logic signals and responsive thereto to generate said output control signal which may be further processed to control the suppression of said fire or explosion, with the proviso that at least one of said channel means is responsive to an atmospheric absorption wavelength associated with at least one combustion product of said fire or explosion.

4,296,325


SCANNING MIRROR POSITION SYSTEM

Peter J. Berry, Glasgow, Scotland, assignor to Barr & Stroud Limited, Glasgow, Scotland

Filed Mar. 10, 1980, Ser. No. 128,551
Int. Cl.³ G01J 1/00

U.S. Cl. 250—347

2 Claims



1. A radiation scanning system including a radiation detector, a radiation-imaging means for forming an image of radiation from a field of view, a scan member and a relay lens arranged to scan an image of the detector across the radiation image, and an arrangement for applying a characteristic radiation feature to the detector at a selected part of the detector image locus lying outside the normal scanned field of the system, wherein the radiation detector forms part of an assem-

bly maintained at a temperature substantially below ambient, and said means for applying a characteristic radiation feature to the detector includes a mirror located on the scan locus of the detector image of the system and arranged to reflect radiation from the cooled assembly onto the detector.

4,296,326


WATERMARK DETECTION

John M. Haslop, Woodley; Reginald G. Knapman, Overton, and Michael A. West, London, all of England, assignors to Thomas De La Rue & Company Limited, London, England
Filed Mar. 5, 1980, Ser. No. 127,789

Claims priority, application United Kingdom, Mar. 6, 1979, 07936/79
Int. Cl.³ G01J 1/42; G01N 21/38; B42D 15/00; G06K 9/74

U.S. Cl. 250—372

19 Claims



- 1. A method of rejecting sheets which do not have a mould watermark (as herein defined), comprising the steps of: measuring for each sheet, in an area in which a watermark is expected to be present, the absorption of ultraviolet radiation by the sheet; measuring for each sheet, in the area in which a watermark is expected to be present, the transmittance of visible light by the sheet; and rejecting sheets for which the said absorption measurement does not show a substantially constant value and also sheets for which the said transmittance measurement shows a substantially constant transmittance of visible light over the said area.

4,296,327

MULTI-STAGE COLLECTIVE FIELD CHARGED PARTICLE ACCELERATOR

John L. Adamski, Bothell, Wash., assignor to The Boeing Company, Seattle, Wash.


Filed Jun. 2, 1980, Ser. No. 155,461
Int. Cl.³ H01J 27/00

U.S. Cl. 250—423 R

10 Claims

- 1. A multi-stage collective field charged particle accelerator, comprising: means forming a charged particle accelerator chamber; a source of particles which in operation generates a particle plasma for said accelerator chamber; first electron beam means, including a cathode source of electrons, power supply means for energizing said cathode, and an anode, having an opening therethrough, to which the electrons emitted from said cathode are discharged, the electron beam produced by said first electron beam means being characterized by a high current which exceeds the space charge limiting current, so that the electron beam stops downstream of the anode, thereby creating a space charge region which greatly accelerates a

portion of the particles in the particle plasma, said portion forming a high energy particle bunch; at least one successive electron beam means, positioned



downstream of said first electron beam means, for further accelerating the particle bunch by creating another space charge region after it leaves said first electron beam means.

4,296,328


APPARATUS FOR PRODUCING HIGH PURITY WATER

Michael D. Regan, 40 Maple St., Medway, Mass. 02053

Filed Feb. 11, 1980, Ser. No. 120,725
Int. Cl.³ G01N 21/00

U.S. Cl. 250—436

8 Claims



- 1. An apparatus for photochemically removing organic material from water comprising a container forming a non-continuously inflowing and outflowing type single chamber water reservoir for holding a batch of said water in said single chamber reservoir, means for producing electromagnetic radiation in the 185 nanometer wavelength range including a source of said radiation positioned in said container to effect a gentle steady state circulation of the water in said batch about said source of radiation, and means for venting to the atmosphere from said container gasses produced in said container by said radiation.

4,296,329

ALIGNMENT DEVICE FOR COMPUTERIZED TOMOGRAPHY PHANTOMS

Paul J. Mirabella, Waukesha, Wis., assignor to General Electric Company, Schenectady, N.Y.


Filed Oct. 22, 1979, Ser. No. 87,595
Int. Cl.³ G01N 21/00

U.S. Cl. 250—491

2 Claims

- 1. Improved means for aligning the center of a calibration phantom with the isocenter of a computed tomography scanner apparatus, said scanner including an x-ray detector and an x-ray source for projecting an x-ray beam toward said detector while said source and detector are being orbited jointly about a longitudinal axis extending through said isocenter and constituting the center of an image reconstruction circle which lies between said source and detector in the x-ray beam path, said

phantom comprising an x-ray transmissive cylinder having an end surface on which there are visible cross hairs which have a point of intersection coincident with the center of the cylinder and which point it is desired to establish coincident with the isocenter for calibrating the scanner apparatus, and means for supporting said phantom in said beam path and for being shifted in any direction required to get said cross hair intersection and said longitudinal axis to coincide, said improved aligning means comprising: a laser light source means for being fixed in a predetermined location remotely from said phantom and generally in the direction in which said longitudinal axis extends, said laser light source being operative to project thin intersecting beams of coherent light which have the same angles be-



tween them as said cross hairs onto said phantom surface as luminous lines with the point of intersection of said beams being coincident with said isocenter and with the beams being simultaneously coincident with said cross hairs, said laser light source being adjustable to cause said beams to be coincident with the cross hairs of one of said phantoms after said one phantom has been shifted by means of its supporting means to a position where said center of the phantom cylinder coincides with said isocenter such that when any similar phantom is mounted for calibration purposes it will only be necessary to shift it until said intersecting laser light beams are coincident with its cross hairs to establish the similar phantom on the isocenter.

4,296,330


FLOWING GAS DISCHARGE SOURCE OF VACUUM ULTRA-VIOLET LINE RADIATION SYSTEM

George M. Thomson, Churchville, and Keith A. Jamison, Aberdeen, both of Md., assignors to The United States of America as represented by the Secretary of the Army, Washington, D.C.

Filed Apr. 16, 1980, Ser. No. 140,646
Int. Cl.³ G01J 1/00

U.S. Cl. 250—504 R

4 Claims



- 1. A vacuum ultraviolet line radiation system comprising: (a) a gas supply; (b) a tube means having an inlet operatively connected to

- said gas supply, and an outlet end for carrying gas there-through;
- (c) a nozzle means fixedly mounted to the tube means at the outlet end of said tube means for sustaining an electrical discharge in an orifice positioned therein;
- (d) a vacuum vessel circumambient said nozzle means having an outlet valve and outlet port axially aligned with said nozzle means and an evacuation port operatively positioned therein;
- (e) a cooling jacket mounted longitudinally over said tube means;
- (f) an insulator mounted upon said tube means between the inlet and outlet ends of said tube means, said insulator separating the tube means electrically from the vacuum vessel; and
- (g) a power source for negatively biasing said source tube means with respect to said vacuum.

4,296,331

OPTICALLY COUPLED ELECTRIC POWER RELAY

Edward T. Rodriguez, Winchester, Mass., assignor to Theta Corporation, Woburn, Mass.

Filed Aug. 9, 1979, Ser. No. 65,072

Int. Cl.³ G02B 27/00

U.S. Cl. 250—551

14 Claims



1. Zero crossing a.c. power relay operable at several amperes and hundreds of volts, with optical isolation comprising, in a common plane,
- at least one photosensitive SCR and at least one solid state junction light emitter optically coupled, from emitter face to SCR face,
- the emitter and SCR being of planar form and housed in a common optical transmitting solid medium in substantially parallel and edge by edge relationship such that the emitter face does not directly oppose the SCR face,
- the medium comprising a non-hemispherical surface dome over the emitter face and SCR face which is reflective, control means for the SCR limiting its turn on to within 2 volts.

4,296,332

SPROCKET HOLE SENSING DETECTOR FOR MOVING TRANSLUCENT PAPER SHEETS


Roy K. Hill, Bristol, Va., assignor to Sperry Corporation, New York, N.Y.

Filed Dec. 28, 1979, Ser. No. 108,099

Int. Cl.³ G06K 7/14

U.S. Cl. 250—570

4 Claims



1. An apparatus for sensing sprocket apertures in a translucent moving paper sheet in a reflective dust environment, the combination comprising,
- a fixed source of light adapted to be directed in the path of

a plurality of regularly spaced open sprocket apertures in said translucent moving paper sheet,

said light source having an intensity sufficient to continuously pass light through said translucent moving paper sheet and dust clogged apertures as well as the open sprocket apertures,

a light sensing device separated from and fixed relative to said light source and adapted to continuously sense rays from said light source,

encapsulating mounting means supporting said light source and said light sensing device at a predetermined number of regularly spaced sprocket apertures from each other, and light ray directing means located on the opposite side of said translucent moving paper sheet from said light source and said sensing device,

said light ray directing means adapted for continuous receiving diffused light rays from said light source through said translucent moving paper sheet or dust clogged aperture in said moving sheet and for directing said diffused light rays through a different aperture in said same moving sheet to said light sensing device, whereby

said light sensing device is adapted to continuously sense the level of light intensity being received and to distinguish between the presence or the absence of at least two thicknesses of said translucent moving paper sheet by sensing the light to dark ratio.

4,296,333

METHOD AND APPARATUS FOR DETECTING SURFACE DEFECTS IN A WORKPIECE

Emilio Milana, Rivalta, and Franco Rasello, Gabiano, both of Italy, assignors to Centro Ricerche Fiat S.p.A., Orbassano, Italy


Filed Sep. 10, 1979, Ser. No. 74,027

Claims priority, application Italy, Oct. 24, 1978, 69439 A/78

Int. Cl.³ G01N 21/48

U.S. Cl. 250—572

7 Claims



1. A method of detecting surface defects in a workpiece which has undergone a mechanical operation, the method comprising the steps of:
- directing a beam of coherent monochromatic light radiation onto the surface of the workpiece in a direction normal thereto;
- moving the light radiation beam and workpiece relative to each other whereby to effectively scan an area of the workpiece surface with the light radiation beam;
- directing the specular component of the radiation beam which is reflected perpendicular to the workpiece by each point of the scanned area of said surface to a first photomultiplier arranged to output an electrical signal indicative of the intensity of said specular component;
- sampling the component of radiation beam scattered from each point of the scanned area of said surface via a second photomultiplier arranged to output an electrical signal indicative of the intensity of said scattered component;
- processing the output signals from the first and second pho-

tomultipliers so as to obtain a resultant signal substantially free of signal noise due to the surface roughness of the workpiece; and

comparing said resultant signal with a reference threshold whereby to derive an indication of the presence of possible surface defects in the workpiece.

4,296,334

PROGRAMMABLE ELECTRONIC STARTING DEVICE FOR AUTOS AND THE LIKE WITH MEANS SELECTABLE TO ACTUATE ACCESSORIES


Gim Wong, 1849 Gibbs Rd., Estevan, Saskatchewan, Canada

Filed Sep. 7, 1978, Ser. No. 940,357

Int. Cl.³ F02N 11/08

U.S. Cl. 290—37 R

16 Claims



1. A programmable electronic starter device for the engines of vehicles and the like which include a source of electric power, throttle linkage, a starter solenoid and other electrical auxiliary equipment, comprising in combination an electronic timer, a time display device operatively connected to said electronic timer, a time setting keyboard for producing pulses, a memory unit, means operatively connecting said memory unit to said time setting keyboard for injection "ON" time and "off time" within said memory unit, thereby controlling the duration time of the operation of the engine said means including an encoder to translate said pulse into electrical impulses, an address selector counter operatively connected to said keyboard, means whereby each pulse from said keyboard operates said address selector counter, said address counter being operatively connected to said memory unit, a comparator module operatively connected to said memory unit and to said address selector counter and a duration counter operatively connected to said comparator module, an alarm output module operatively connected to said alarm duration counter and timer means operatively connected between said alarm output module and said throttle linkage, said starter solenoid and said other auxiliary electrical equipment to operate same selectively.

4,296,335

HIGH VOLTAGE STANDOFF MOS DRIVER CIRCUITRY

Robert J. Simcoe, Liverpool, N.Y., assignor to General Electric Company, Schenectady, N.Y.

Filed Jun. 29, 1979, Ser. No. 53,300

Int. Cl.³ H01L 00/00; H02H 9/00

U.S. Cl. 307—200 B


24 Claims

1. A high voltage standoff circuit for driving high voltage low current display devices directly with constant current, said circuit being compatible with large scale integrated circuits, comprising:

first, second and third MOSFETs connected in a loop so as to form therein a junction of said first and second MOSFETs, a junction of said second and third MOSFETs, and a junction of said first and third MOSFETs, said first, second and third MOSFETs having their gates connected directly to each other in common with the junction of said second and third MOSFETs;

control means coupled to the junction of said first and sec-

ond MOSFETs; and diode means coupled to said junction of said second and third MOSFETs, and circuit being



adapted to support high voltage applied to the junction of said first and third MOSFETs.

4,296,336

SWITCHING CIRCUIT AND METHOD FOR AVOIDING SECONDARY BREAKDOWN


William R. Skanadore, Tempe, Ariz., assignor to General Semiconductor Co., Inc., Del.

Filed Jan. 22, 1979, Ser. No. 5,157

Int. Cl.³ H03K 17/10, 17/64; H01L 29/72

U.S. Cl. 307—300

1 Claim



1. A method of operating a power transistor circuit to avoid secondary breakdown in a power transistor included in said power transistor circuit, said power transistor having base, collector, and emitter terminals, said power transistor having a secondary breakdown which is less than the BV_{CBO} voltage of said power transistor, said power transistor circuit including a load element for supplying collector current to said collector terminal, said method comprising the steps of:

- (a) turning said power transistor on by conducting a first current into said base terminal, said first current being sufficiently large to cause a collector current to flow in said collector terminal and to cause said power transistor to become saturated;
- (b) turning said power transistor off by
- (i) conducting a first base turn-off current out of said base terminal to remove charge stored in the base and collector regions of said power transistor, said first base turn-off current being substantially less than said collector current, and
- (ii) conducting a second base turn-off current out of said base terminal, said second base turn-off current being at least equal to said collector current, said second base turn-off current being conducted out of said base terminal only after a substantial amount of said charge in said base and collector regions has been removed by said first base turn-off current.

4,296,337 RESISTANCE DETECTOR WITH DELAYED HYSTERESIS


Dale E. Stone, Cedar Knolls, N.J., assignor to Bell Telephone Laboratories, Incorporated, Murray Hill, N.J.

Filed Oct. 15, 1979, Ser. No. 84,915

Int. Cl.³ H03K 5/24

U.S. Cl. 307—356

4 Claims



1. A threshold detector characterized by a differential amplifier having two inputs and an output, means for applying a first signal across a voltage divider, a midpoint of which is connected to one of said inputs, means for applying a second signal to the other of said inputs, a first field effect transistor having its main electrodes connected across a portion of said voltage divider, delay means responsive to signals at said output for applying control signals to the control electrode of said field effect transistor and a second field effect transistor for connecting said voltage divider to ground potential.

4,296,338 POWER ON AND LOW VOLTAGE RESET CIRCUIT


James S. Thomas, Manor, Tex., assignor to Motorola, Inc., Schaumburg, Ill.

Filed May 1, 1979, Ser. No. 35,044

Int. Cl.³ H03K 5/153, 5/24, 17/687; H02J 13/00

U.S. Cl. 307—362

19 Claims



1. An integrated circuit for generating a reset signal when a first voltage falls below a second voltage, said first and second voltages derived from a supply voltage, said integrated circuit having connection means for coupling an external capacitor thereto, comprising: reset signal generating means; first means for generating a first reset enabling signal when

said first voltage falls below said second voltage, said first reset enabling signal coupled to an input of said reset signal generating means and terminating when said first voltage exceeds said second voltage; and second means for generating a second reset enabling signal, said second means responsive to said first reset enabling signal and coupled to an input of said reset signal generating means, said second reset enabling signal terminating a predetermined length of time after said first voltage exceeds said second voltage, said predetermined length of time dependent upon the charging time of said capacitor.

4,296,339 LOGIC CIRCUIT COMPRISING CIRCUITS FOR PRODUCING A FASTER AND A SLOWER INVERTED SIGNAL

Tatsunori Murotani, Tokyo, Japan, assignor to Nippon Electric Co., Ltd., Tokyo, Japan


Filed Dec. 27, 1978, Ser. No. 973,776

Claims priority, application Japan, Dec. 27, 1977, 52-158839

Int. Cl.³ H03K 19/094, 19/003, 19/20

U.S. Cl. 307—450

9 Claims



1. A logic circuit responsive to a variable input signal for producing a first and a second output signal that vary with phases opposite to and same as said input signal, respectively, said circuit comprising: a first and a second inverter circuit responsive to said input signal for producing a first and a second inverted signal, respectively, one of said first and said second inverted signals varying with said input signal faster than the other of said first and said second inverted signals; a first and a second buffer circuit; first means for supplying said first inverted signal to said first buffer circuit; and second means for supplying said second inverted signal to said second buffer circuit; and third means for supplying said input signal to both of said first and said second buffer circuits; whereby said first and said second buffer circuits produce said first and said second output signals, respectively.

4,296,340 INITIALIZING CIRCUIT FOR MOS INTEGRATED CIRCUITS

Douglas F. Horan, Los Gatos, Calif., assignor to Intel Corporation, Santa Clara, Calif.

Filed Aug. 27, 1979, Ser. No. 70,133


Int. Cl.³ H03K 17/284, 17/22, 17/16, 5/08

U.S. Cl. 307—550

10 Claims

1. In an MOS integrated circuit employing a substrate biasing potential, a protection circuit for initially preventing the transmission of signals on a line in said integrated circuit when power is applied to said integrated circuit, comprising: a transistor coupled to said line for preventing said transmission of said signals when said transistor is enabled, the gate of said transistor being coupled to receive said substrate biasing potential; the threshold voltage of said transistor being selected such that said transistor is enabled in the absence of said substrate biasing potential and said transistor is disabled when

said substrate biasing potential reaches a predetermined level;



whereby prior to and during the period when said integrated circuit is initially powered, said signals are prevented from being transmitted.

4,296,341 SELF-STARTING SINGLE-PHASE SYNCHRONOUS MOTOR

Kurt Güttinger, Murten, Switzerland, assignor to Sodeco-SAIA SA, Geneva, Switzerland


Filed Jun. 27, 1978, Ser. No. 919,737

Claims priority, application Switzerland, Jul. 15, 1977, 8763/77

Int. Cl.³ H02K 7/10

U.S. Cl. 310—41

10 Claims



1. A self-starting single-phase synchronous motor comprising: a generally bell-shaped permanently magnetized rotor; a stator having two parts each with distinct poles; a coil located inwardly of the rotor and having a core which is connected at its end to said two stator parts, one said stator part being located between said coil and rotor and the other said stator part being located outwardly of said rotor, said rotor being rotatably mounted on a shaft with defined friction; a resilient coupling element interposed between said rotor and shaft, said resilient coupling element engaging said rotor and shaft for resiliently transmitting torque from said rotor to said shaft; and locking means mounted on said rotor and acting on said rotor for locking said rotor preventing rotation in an undesired direction and for permitting starting of said rotor in the opposite, desired direction of rotation, said locking means located in front of said resilient coupling element on the power transmission path.

4,296,342 STARTER MOTOR

Donald A. Young, and Christopher P. Squires, both of Birmingham, England, assignors to Lucas Industries, Limited, Birmingham, England


Filed May 20, 1980, Ser. No. 151,755

Claims priority, application United Kingdom, May 25, 1979, 18384/79

Int. Cl.³ F16D 55/22; F02N 11/02

U.S. Cl. 310—77

13 Claims



1. A starter motor including an electric motor, a shaft rotatable by the motor, a pinion assembly carried by said shaft for rotation therewith, the pinion assembly being movable axially relative to the shaft between a rest position and an operative position, resilient means urging the pinion assembly to its rest position, and brake means operable to brake rotation of said driven shaft, said brake means comprising a brake disc mounted on said driven shaft for rotation therewith, a first friction member engageable with one face of the brake disc, a second friction member engageable with the opposite face of the disc, the first and second friction members being opposite one another, and a brake operating member movable in response to return movement of the pinion assembly to cause relative movement of the first and second friction members to grip the brake disc between them, so generating a braking action.

4,296,343 ELECTRIC MOTOR HOUSING, OR THE LIKE, WITH INTEGRAL POLE AND METHODS FOR MAKING SAME


Bobby E. McMillen, Columbus, Miss., assignor to AMBAC Industries, Incorporated, Farmington, Conn.

Filed Oct. 5, 1979, Ser. No. 82,178

Int. Cl.³ H02K 23/04

U.S. Cl. 310—154

6 Claims



1. An electric machine including an armature supported on a shaft for rotation within a housing, the housing comprising: a section of tubular ferrous material; at least two magnetic field pole pieces secured within the tubular ferrous material to provide alternate poles having curved surface areas spaced from and conforming generally to the curvature of the armature, and; at least two intermediate induced field pole pieces provided by inwardly projecting sections of side walls of the tubular ferrous material.

lar ferrous material and having arcuate face surfaces essentially equal in area to that of the magnetic pole pieces and spaced from the magnetic field pole pieces, said inwardly projecting pole pieces providing alternate intermediate poles for the machine by the induction effects generated from the magnetic field pole pieces in cooperation with the armature in the total magnetic flux path.

4,296,344

MULTI-SPEED MOTOR


Jerry R. Rabe, Holland, Mich., assignor to General Electric Company, Fort Wayne, Ind.

Filed Mar. 13, 1979, Ser. No. 20,182

Int. Cl.³ H02K 3/00

U.S. Cl. 310-184

11 Claims



1. A stator assembly for a multi-speed motor operational in a plurality of different speed ranges including a core having an axially extending bore and axially extending slots communicating with the bore, and further including a main winding energizable in more than one speed range and at least two distinct auxiliary windings comprising a lower speed range auxiliary winding and a higher speed range auxiliary winding, the lower speed range auxiliary winding being operable to start the motor for a lower speed range operation and the higher speed range auxiliary winding being operable to start the motor for higher speed range operation, the windings being accommodated within selected slots of the core with the main winding positioned radially outwardly of the lower speed range auxiliary winding relative to the bore and with the higher speed range auxiliary winding positioned radially inwardly of the lower speed range auxiliary winding relative to the bore; and said main winding comprising two pole groups selectively connectable to create four main poles for the lower speed range operation and to create two main poles for the higher speed range operation.

4,296,345

FLEXIBLE LOOP SLIP RING BRUSH

John B. Haberl, Dalton, Mass., assignor to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Jul. 14, 1980, Ser. No. 167,866


Int. Cl.³ H02K 13/00

U.S. Cl. 310-219

20 Claims

1. A brush for making electrical contact with peripheral portions of a slip ring rotatable within a housing comprising: flexible wire means having opposite extremities anchored at locations diametrically opposite the slip ring, said wire means having helical formations therein and including opposed runs defining a loop when passed on opposite sides of the slip ring, said wire means being stretched so that compressive force is exerted by the wire means

to resiliently contract the loop whereby the opposed runs are caused to embrace substantial arcuate peripheral portions on opposite sides of the slip ring defining a brush for sliding electrical contact therewith.



4,296,346

BRUSH HOLDING APPARATUS FOR ROTARY ELECTRIC MACHINE

Norihiro Ooki, Katsuta; Shoji Motegi, Hitachi; Yasuyuki Wachi, Takahagi; Yoshio Takikawa, Hitachi, and Norio Yamakawa, Ibaraki, all of Japan, assignors to Hitachi, Ltd. and Hitachi Chemical Co., Ltd., both of Tokyo, Japan


Filed Nov. 20, 1979, Ser. No. 95,951

Claims priority, application Japan, Nov. 29, 1978, 53-146562

Int. Cl.³ H02K 13/00

U.S. Cl. 310-242

9 Claims



1. A brush holding apparatus for a rotary electric machine comprising:
a plurality of brushes disposed along the outer periphery of rotatable slip rings for making sliding engagement therewith;
a brush holder holding said brushes while pressing said brushes against the outer periphery of said slip rings at a predetermined pressure, said brush holder being provided on its head with an insulated handle;
retaining means fixedly mounted on a portion of said brush holder and shaped in the form of a wedge having its transverse width gradually narrowed toward said slip rings;
stationary means shaped to be engageable with said retaining means and spaced from said slip rings by a predetermined distance;
securing means for detachably securing said retaining means to said stationary means, said securing means including a retaining lug protruding from and fixed to a portion of said brush holder, and a lug-engaging cam supported in said stationary means so as to be engageable with said retaining lug; and
a manipulating lever pivotally coupled at one end thereof to a portion of said lug-engaging cam to cause angular rotation of said cam around its axis, said securing means being engaged with or disengaged from said retaining means in response to the manipulation of said manipulating lever whereby said brush holder can be mounted on or detached from said stationary means.

4,296,347

SURFACE ACOUSTIC WAVE SENSOR


Donald F. Weirauch, Dallas, Tex., assignor to Texas Instruments Incorporated, Dallas, Tex.

Filed Sep. 28, 1979, Ser. No. 79,735

Int. Cl.³ H01L 41/02; H03H 9/05

U.S. Cl. 310-313 B

10 Claims



1. A surface acoustic wave sensor comprising a first member having a first relatively flat surface, a second member having a second relatively flat surface, a first surface acoustic wave array positioned upon said first surface, a second surface acoustic wave array positioned upon said second surface, first electrical connection means for making electrical connections to said first array, second electrical connection means for making electrical connections to said second array, said first surface acoustic wave array and said second surface acoustic wave array disposed in proximity one to the other so as to create a capacitive coupling effect between said arrays, and a fired glass frit bonding agent solely disposed between said first and second surfaces to form an enclosed chamber between said first and said second members while rigidly affixing said first and said second members each to the other, said chamber enclosing at least one of said first and said second arrays.

4,296,348

INTERDIGITATED ELECTRODE ULTRASONIC TRANSDUCER

Kohji Toda, Yokosuka, Japan, assignor to TDK Electronics Co., Ltd., Tokyo, Japan, a part interest


Filed Aug. 20, 1979, Ser. No. 68,273

Claims priority, application Japan, Aug. 21, 1978, 53/100929
The portion of the term of this patent subsequent to Oct. 30, 1996, has been disclaimed.

Int. Cl.³ H01L 41/08

U.S. Cl. 310-334

6 Claims



1. An ultrasonic transducer characterized by comprising a piezoelectric substrate whose thickness is substantially smaller than wavelength (λ) of an ultrasonic wave in said substrate and an interdigital electrode means disposed on one side surface of

said substrate, so that as AC voltages are applied to said interdigital electrode means while keeping the opposite side surface of said substrate in contact with a liquid medium ultrasonic waves are radiated toward said liquid medium.

4,296,349

ULTRASONIC TRANSDUCER

Toshiharu Nakanishi, Kamakura; Miyo Suzuki, Fujisawa, and Hiroji Ohigashi, Zushi, all of Japan, assignors to Toray Industries, Inc., Japan


Filed Feb. 12, 1980, Ser. No. 120,782

Claims priority, application Japan, Feb. 13, 1979, 54-15177

Int. Cl.³ H01L 41/08

U.S. Cl. 310-335

11 Claims



1. An improved ultrasonic transducer, comprising: a piezoelectric film with associated electrodes and a reflective layer bonded to the said piezoelectric element, said reflective layer having a thickness in a range from $1/32 \lambda$ to $3/16 \lambda$, and said λ being the wavelength of sound waves within said reflective layer at one half of free resonant frequency of the said piezoelectric film.

4,296,350

GASEOUS FLUORESCENT DISCHARGE LAMP


Jakob Maya, Boston, Mass., assignor to GTE Products Corporation, Stamford, Conn.

Filed Dec. 21, 1979, Ser. No. 106,297

Int. Cl.³ N01J 1/02

U.S. Cl. 313-26

5 Claims



1. An arc discharge device comprising a source of UV emission and a chamber external thereto containing a substance which, in vapor form, comprises gaseous molecules which absorb said UV emission and are raised to a highly excited state, from which the excited molecules relax to a lower intermediate energy state and then to a ground state, one of the two latter states being optically coupled to the immediate higher energy state so that the transition of said molecules from either the highly excited state to the intermediate state or from the intermediate state to the ground state results in the emission of visible radiation.

4,296,351

TUNGSTEN HALOGEN LAMP HAVING LEAD-IN WIRE COMPRISING TANTALUM ALLOY

Stephen F. Kimball, North Andover, and Peter R. Gagnon, Salem, both of Mass., assignors to GTE Products Corporation, Stamford, Conn.

Filed Oct. 17, 1979, Ser. No. 86,182


Int. Cl.³ H01K 1/28

U.S. Cl. 313-222

10 Claims

1. A tungsten halogen incandescent lamp comprising two

tungsten filaments supported on lead-in wires and disposed within a glass envelope, the glass envelope containing a fill of inert gas and halogen in elemental or compound form, the two tungsten filaments having different tungsten evaporation rates



during normal operation, the lead-in wires comprising an alloy including tantalum the purpose of which is to provide satisfactory lamp operation at the two different tungsten evaporation rates.

4,296,352

INCANDESCENT LAMP


Ivan Berlec, South Euclid, and Lewis V. McCarty, Cleveland Heights, both of Ohio, assignors to General Electric Company, Schenectady, N.Y.

Filed Dec. 19, 1979, Ser. No. 105,329

Int. Cl.³ H01K 1/42, 7/08

U.S. Cl. 313—315

16 Claims



1. An incandescent lamp filament comprising a tungsten wire having an inner core of tungsten crystals doped with grain growth promoting additives selected from aluminum, silicon and potassium compounds to exhibit sag resistance and a surface layer of chemically vapor deposited undoped tungsten crystals imparting increased vibration damping and lower shear modulus value at elevated temperatures to the lamp filament.

10. An incandescent lamp having a transparent envelope which contains a tungsten filament comprising a tungsten wire having an inner core of tungsten crystals doped with grain growth promoting additives selected from aluminum, silicon and potassium compounds to exhibit sag resistance and a surface layer of chemically deposited undoped tungsten crystals imparting increased vibration damping and a lower shear modulus value at elevated temperatures to improve the vibration resistance.

4,296,353 FLUORESCENT LAMP HAVING HIGH COLOR RENDERING INDEX


Wolfgang Walter, Brookline, Mass., assignor to GTE Products Corporation, Stamford, Conn.

Filed Oct. 29, 1979, Ser. No. 89,642

Int. Cl.³ H01J 1/62

U.S. Cl. 313—487

9 Claims



1. A fluorescent lamp having a high color rendering index and high efficacy comprising a glass envelope having electrodes at its ends and containing a fill including mercury and a starting gas, and a phosphor coating on the inner surface of the glass envelope, the phosphor coating comprising a blend of four narrow band emitting phosphors, the respective peak emissions of said four phosphors being in the regions of about 450–480 nm, 510–540 nm, 570–590 nm and 600–630 nm.

4,296,354

TRAVELING WAVE TUBE WITH FREQUENCY VARIABLE SEVER LENGTH


Michael L. Neubauer, Menlo Park, Calif., assignor to Varian Associates, Inc., Palo Alto, Calif.

Filed Nov. 28, 1979, Ser. No. 98,011

Int. Cl.³ H01J 25/34

U.S. Cl. 315—3.5

25 Claims



1. A traveling tube having internal gain compensation, comprising:

A helix-type interaction circuit for supporting interaction of an electron beam with microwave signals over an operable band of frequencies, said interaction tending to produce a gain varying with frequency, a first attenuator resonant at a first frequency within said operable band and coupled to said interaction circuit over a first length of said interaction circuit, and a second attenuator resonant at a second frequency within said band and coupled to said interaction circuit over a second length, said first and second frequencies being generally identified with frequencies in said operable band whose gain is sought to be compensated, whereby gain of said frequencies within said operable bandwidth is automatically compensated internally.

20. A traveling wave tube having noise-resistant internal gain compensation comprising:

a helix-type slow-wave circuit having an input end for microwave signals, said signals interacting with a linear electron beam over a selected band of frequencies, said interaction tending to produce a gain which varies with frequency, a dielectric rod near said circuit extending in the direction of the axis of said slow-wave circuit; and a first resistive conductor shaped to form a circuit resonant at a first frequency within said tube, said conductor being attached to the surface of said rod so as to extend over a first length of said slow-wave circuit; and a second resistive conductor shaped to form a circuit resi-

dent at a second frequency within said band, said conductor being attached to the surface of said rod so as to extend over a second length of said slow-wave circuit; said conductors both being spaced away from said input end, said conductors providing respective different degrees of attenuation about said first and second frequencies to compensate said gain varying with frequency without degrading the anti-noise properties of said tube.

4,296,355

MAGNETRON WITH COOLING MEANS

Akihiro Fukatsu, and Isao Tada, both of Yokohama, Japan, assignors to Toshiba Corporation, Kawasaki, Japan


Filed Nov. 13, 1979, Ser. No. 93,898

Claims priority, application Japan, Nov. 13, 1978, 53-155877[U]

Int. Cl.³ H01J 25/50

U.S. Cl. 315—39.51

5 Claims



1. An internal type magnetron comprising: an anode having an anode axis; a cathode disposed within said anode; an antenna terminal disposed along an antenna axis which is offset from and substantially parallel to said anode axis; and a cooling means surrounding said anode for cooling said anode, said cooling means having an outermost periphery, each point on the periphery lying at a substantially uniform radial distance from said antenna axis.

4,296,356

IONIZATION VACUUM GAUGE CIRCUIT

Karl Beinitz, Cologne, and Joachim Schubert, Wesseling, both of Fed. Rep. of Germany, assignors to Leybold-Heraeus GmbH, Postfach, Fed. Rep. of Germany


Filed Dec. 11, 1979, Ser. No. 102,480

Claims priority, application Fed. Rep. of Germany, Dec. 13, 1978, 2853677

Int. Cl.³ G08B 21/00; H05B 37/03

U.S. Cl. 315—135

9 Claims



1. In a circuit for an ionization vacuum gauge having a thermionic filament, a control circuit receptive of current for maintaining a constant current flow between the cathode and anode of the gauge and a switch for applying current to the control circuit, the improvement comprising: circuit means for

indicating a filament interruption independent of the state of the switch including at least one resistor by-passing the switch to provide a continuous sensing current to the filament and means for detecting an interruption in the sensing current and for indicating such an interruption.

4,296,357

PLASMA DISPLAY SYSTEM

Tsutomu Hirayama, and Hiroshi Hada, both of Tokyo, Japan, assignors to Nippon Electric Co., Ltd., Tokyo, Japan


Continuation of Ser. No. 947,227, Sep. 29, 1978, abandoned. This application Nov. 2, 1979, Ser. No. 90,718

Claims priority, application Japan, Sep. 29, 1977, 52-117622; Jul. 14, 1978, 53-86268; Aug. 8, 1978, 53-97079

Int. Cl.³ H05B 41/30

U.S. Cl. 315—169.4

12 Claims



1. An external electrode type plasma display apparatus comprising a group of first electrodes and a group of second electrodes disposed in an opposed relation to each other by the intermediary of a discharging gas to form cells therebetween, a dielectric coating covering the surface of the electrodes of at least one group exposed to said gas,

a first driver circuit applied to said first electrodes and having a plurality of input terminals, a second driver circuit coupled to said second electrodes and having a plurality of input terminals, a scanning control means for applying a first signal successively to said input terminals of said first driver circuit for a predetermined period at a predetermined interval, said first driver circuit including means for producing a group of first voltage pulses in response to said first signal and means for applying said first voltage pulses successively to said first electrodes, said first voltage pulses having a predetermined first amplitude with a predetermined polarity, said first amplitude being smaller than a firing voltage of the cells,

a signal means for selectively applying a second signal to at least one of said input terminals of said second driver circuit for said predetermined period in synchronism with said first signal,

said second driver circuit including means for producing at least one second voltage pulse of an amplitude smaller than said firing voltage in response to said second signal and means for applying said second voltage pulse to said second electrode group so as to produce a first alternating voltage between the electrodes associated with a selected cell in combination with said first voltage pulses, said first alternating voltage having a second amplitude with one and opposite polarities, said second amplitude being larger than said firing voltage,

means for applying a third signal simultaneously to all of said input terminals of said first driver circuit, said first driver circuit further including means for producing a third

voltage pulse and means for applying said third voltage pulse to a plurality of said first electrodes, and means for applying a fourth signal to all of said input terminals of said second driver circuit in synchronism with said third signal, said second driver circuit further including means for producing a fourth voltage pulse and means for applying said fourth voltage pulse to a plurality of said second electrodes so as to produce a second alternating voltage between said plurality of first electrodes and said plurality of second electrodes, said second alternating voltage having an amplitude larger than said firing voltage and a frequency lower than that of said first alternating voltage so that the number of discharging times due to said second alternating voltage is smaller than that due to said first alternating voltage.

4,296,358

HIGH-VOLTAGE SPARK SOURCE


John A. Bernier, Lexington, Mass., assignor to Fisher Scientific Company, Pittsburgh, Pa.

Filed Jul. 30, 1979, Ser. No. 62,244

Int. Cl.³ H05B 7/20

U.S. Cl. 315-241 R

18 Claims



1. A spark source for spectrochemical analysis comprising a spark gap for receiving a sample to be analyzed, a storage capacitor, a discharge circuit including reactive means connected in circuit between said capacitor and said spark gap, discharge control means for discharging said capacitor through said spark gap, and switching means for effectively removing said capacitor from said discharge circuit after a brief initial interval of current flow through said spark gap so that the current flow through said spark gap is essentially unidirectional.

4,296,359

TELEVISION DISPLAY ERROR CORRECTION


Dennis L. Dodds, Indianapolis, Ind., assignor to RCA Corporation, New York, N.Y.

Filed Oct. 29, 1979, Ser. No. 88,657

Int. Cl.³ H01J 29/56

U.S. Cl. 315-370

5 Claims



1. A method for correcting the effects on a display raster of

an electron gun mount rotation error in a color kinescope having in-line electron guns and a display screen, comprising the steps of:

aligning the horizontal deflection axis of a deflection yoke mounted on said kinescope with the axis of alignment of said kinescope electron guns; and generating, at a location adjacent to the exit end of said deflection yoke, an electron-influencing magnetic field extending in a direction orthogonal to the directions of the horizontal and vertical deflection fields produced by said deflection yoke and of a magnitude and polarity chosen to effect alignment of the horizontal axis of said display raster with the horizontal axis of the kinescope display screen.

4,296,360

SWITCHED-MODE FRAME-SCAN CONTROL CIRCUIT FOR A VIDEOFREQUENCY RECEIVER

Gerard Rilly, Paris, France, assignor to Thomson-Brandt, Paris, France


Filed Jun. 4, 1980, Ser. No. 156,462

Claims priority, application France, Jun. 7, 1979, 79 14590

Int. Cl.³ H01J 29/70, 29/72

U.S. Cl. 315-387

8 Claims



1. A switched-mode frame-scan control circuit comprising a circuit for generating a saw-tooth signal having an active switch monodirectional in voltage and bidirectional in current, connected to the terminals of a load comprising the vertical deflector in series with a measuring resistor and a connecting capacitor, wherein the active switch is controlled by a cyclic ratio control circuit connected, on the one hand, to a static servo-control circuit one input terminal of which is connected to the positive terminal of the connecting capacitor and the other input terminal to a reference DC voltage generator, so as to maintain a sufficiently high and stable voltage at the terminals of this capacitor for optimum operation of the active-switch circuit and, on the other hand, to a dynamic servo-control circuit one input terminal of which is connected to the measuring resistor and the other input terminal to a circuit for generating frame saw-teeth corrected into an S, so as to ensure conformity of the law of variation of the current in the deflector with respect to this corrected frame saw-tooth law; these two servo-control circuits taking effect on the moment when the active switch is triggered.

4,296,361

CONTROL SYSTEMS

Michael A. Archer, Hamburg, Fed. Rep. of Germany, assignor to Lucas Industries Limited, Birmingham, England

Filed Jul. 24, 1979, Ser. No. 60,001

Claims priority, application United Kingdom, Aug. 15, 1978, 33341/78


Int. Cl.³ H02P 1/54

U.S. Cl. 318-54

5 Claims

1. A control system for a pair of driving motors of a vehicle, the vehicle being of the kind in which road wheels on opposite sides of the vehicle are driven by the motors respectively, the

steering of the vehicle being achieved by varying the electric current flow to the two motors whereby, in use, one motor can drive its associated road wheel more quickly than the other to achieve a steering action, the control system comprising first and second motor control circuits for the motors respectively, each motor control circuit comprising first and second changeover switches, the switches having common terminals connected to the supply terminals respectively of the associated motor and each switch having first and second changeover terminals, diodes respectively connecting the first changeover terminals of each changeover switch to one terminal of a source of supply, the second changeover terminals being connected to the other terminal of the source of supply whereby



when said switches are in a neutral position, the common terminals of the switches will be connected to said first changeover terminals and to the one terminal of the source of supply through said diodes, and in a drive position one of the common terminals of a switch will be connected to said second changeover terminal corresponding therewith and to the other terminal of the source of supply, the first and second changeover switches in each motor control circuit being operable to change the direction of current flow through the associated motor, characterized by a pair of resistors connected between the motor control circuits, said changeover switches when in said neutral position connecting the motors in series with each other and with said pair of resistors.

4,296,362

MOTOR HAVING ELECTRONICALLY SWITCHED STATOR FIELD CURRENT AND INTEGRAL TORQUE CONTROL


Denny D. Beasley, Cincinnati, Ohio, assignor to Beasley Electric Corporation, Georgetown, Ohio

Filed May 18, 1978, Ser. No. 907,120

Int. Cl.³ H02P 6/02

U.S. Cl. 318-138

12 Claims



1. An electric motor comprising a stator, a rotor rotatably mounted on a shaft within said stator, a plurality of stator windings, and a circuit for switching stator field currents, said circuit comprising a positive current driver and a negative current driver for each stator winding, said positive current driver operating to permit current flow in one direction through said winding for part of the rotor rotation, said negative current driver operating to permit current flow in the opposite direction for a succeeding part of the rotor rotation, said circuit further comprising sensing means associated with each of said drivers to sense rotor position and produce outputs

to cause said associated driver to permit said current flow, said sensing means including means for successively causing current flow through each of said stator windings in turn such that current flows in only one stator winding at a time, said sensing means comprising a plurality of spaced optical interrupters fixedly mounted with respect to the rotor shaft and at substantially equal radial distances therefrom, each of said interrupters having an optical source, an optical receiver and a space therebetween defining an optical path, said sensing means further including a substantially circular plate coaxial with the rotor shaft and adapted to rotate therewith, said plate containing a slot extending circumferentially along the outer edge of said plate of a length corresponding to said part of the rotor rotation that current flows through the windings, said plate being interposed within said optical paths such that a particular one of said optical receivers produces an output only when said slot is within the optical path associated with that receiver, one of said interrupters including a second optical source, optical receiver and space therebetween defining an optical path, and said plate contains a plurality of spaced apertures substantially radially equidistant from the center of said plate such that said second optical receiver produces an output each time one of said apertures traverses said second optical path.

4,296,363

SPEED SELECTION FOR A DIRECT CURRENT PERMANENT MAGNET MOTOR


Charles H. Blake, Park City, and Donald H. Wood, Gurnee, both of Ill., assignors to Outboard Marine Corporation, Waukegan, Ill.

Continuation of Ser. No. 504,353, Sep. 9, 1974, abandoned. This application Aug. 12, 1976, Ser. No. 713,690

Int. Cl.³ B63H 21/26; H02B 7/00

U.S. Cl. 318-349

8 Claims



1. A speed control circuit for a permanent magnet, direct current motor comprising a source of direct current, a permanent magnet motor including an armature winding having opposed terminals, and speed control means including a first resistor connected between one of said armature winding terminals and said direct current source, a second resistor connected to said one armature winding terminal, a shunt lead connected to said one armature winding terminal, and a switch connected to said direct current source and selectively operable between a first position connecting said direct current source to said shunt lead in parallel with said first resistor and disconnected from said second resistor, a second position connecting said direct current source to said second resistor in parallel with said first resistor and disconnected from said shunt lead, and a third position disconnected from both of said shunt lead and said second resistor, whereby current flow from said current source to said armature winding is solely through said first resistor.

4,296,364

TOOL COMPENSATION SYSTEM

Hiroomi Fukuyama, Hachioji, and Shinichi Isobe, Tachikawa, both of Japan, assignors to Fujitsu Fanuc Limited, Japan

Filed Mar. 26, 1980, Ser. No. 134,120

Claims priority, application Japan, Sep. 27, 1978, 53-118840


Int. Cl.³ G05B 19/25

U.S. Cl. 318-572


11 Claims

1. In a tool compensation system of the type which includes

auxiliary winding upon the motor obtaining a predetermined speed during start up, said motor further including a centrifugal actuator mounted on said shaft and operatively connected to said starting switch for actuation of the latter in response to said rotor obtaining said predetermined speed, said centrifugal actuator having a portion thereof shiftable axially upon said shaft between a start position and a run position upon start up of the motor and upon said rotor obtaining said predetermined speed and being shiftable in reverse direction from its run to its start position upon slowing or stopping of the rotor thereby to reset said starting switch, the latter having a housing adapted to be secured in fixed position relative to said centrifugal actuator and having at least one switch contact therewithin movable in response to movement said centrifugal actuator between a start position in which said auxiliary winding is energized and a run position in which said auxiliary winding is de-energized, said housing having a wall, wherein the improvement com-




14 Claims



4 Claims

1. In a dynamoelectric machine, such as an electric motor, comprising a stator, a rotor and a shaft journaled with respect to the stator and supporting the rotor, said shaft having a longitudinal axis, said motor further including an auxiliary winding and a starting switch operable to de-energize said




7 Claims

setting up at least two frequency regions for the variable frequency;


setting the ratio of a percentage input voltage expressed in terms of a percentage of the rated input voltage to the AC motor, to a corresponding percentage input frequency expressed in terms of a percentage of the rated input frequency

setting said ratio of percentage input voltage to percentage input frequency in at least a second frequency region to a ratio higher than that of said one of said frequency regions to increase motor torque in said second frequency region.


10 Claims



4 Claims



8 Claims



particles having a polarity opposite to said one type, whereby the deposition of said charged particles adjacent said insulating film indicates the presence of said film.

4,296,371


SYSTEM FOR MEASURING STYLUS SHOE LENGTH
Eugene O. Keizer, and Gerard A. Alphonse, both of Princeton, N.J., assignors to RCA Corporation, New York, N.Y.

Filed Mar. 17, 1980, Ser. No. 131,044

Int. Cl.³ G01R 27/26

U.S. Cl. 324—61 R

23 Claims



12. Apparatus for measuring shoe length of a stylus having a tip at one end thereof, said tip including a prow terminating at a base thereof and a stern remote from said prow, said tip adapted to track a path along a surface of an information record and to measure capacitive variations between said stylus and the surface of said record when relative motion is established between said stylus and said record, the shoe length being the distance between said base and said stern along a line tangent to said path at the tracking location, comprising:

means attached to said stylus for positioning the tip of said stylus adjacent the surface of a substrate to allow capacitive coupling, between said stylus and said substrate acting as capacitive electrodes, to produce an output signal at one capacitive electrode in response to an input signal at the other capacitive electrode,

means for changing the orientation of said stylus relative to said substrate an angle of θ degrees about an axis passing through the base of said prow in a direction parallel to the surface of said substrate and perpendicular to the direction of said shoe length, in order to change said orientation from a first position to a second position,

circuit means connected to the one capacitive electrode for measuring the amplitude of said output signal while said stylus and said substrate are oriented in said first and said second positions to obtain a first and a second signal respectively, and

means connected to said circuit means for comparing said first signal with said second signal to obtain a difference signal proportional to the shoe length of said stylus.

4,296,372

TECHNIQUES FOR IMPRESSING A VOLTAGE WITH AN ELECTRON BEAM

Hans-Peter Feuerbaum, Munich, Fed. Rep. of Germany, assignor to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany

Filed May 23, 1979, Ser. No. 41,613

Claims priority, application Fed. Rep. of Germany, Jun. 2, 1978, 2824308

Int. Cl.³ G01N 27/00


U.S. Cl. 324—71 EB

6 Claims

1. In an electrical device of the type which includes an electrically conductive region which is covered with an insulating material, and the insulating material is covered with a passivating material, the improvement therein for non-destructive testing of the electrical integrity of the electrically conductive region, comprising:

a metal layer carried on the passivating material over the

electrically conductive region for connection to a supply potential, said metal layer and the insulating material and the passivating material permeable and responsive to electron radiation to form an electrical connection between the electrically conductive region and the metal layer, and thus carry the supply potential.



ing material permeable and responsive to electron radiation to form an electrical connection between the electrically conductive region and the metal layer, and thus carry the supply potential.

4,296,373

HEMATOLOGY CELL COUNTING APPARATUS INCORPORATING MULTIPLE TRANSDUCERS FOR SEQUENTIAL OPERATION


Henry R. Angel, Fairfield, and James W. Hennessy, Trumbull, both of Conn., assignors to Hycel, Inc., Houston, Tex.

Filed Jul. 12, 1979, Ser. No. 57,045

Int. Cl.³ G01N 27/00

U.S. Cl. 324—71 CP

9 Claims



1. In a particle counting apparatus of the impedance sensing type for counting particles passing in a liquid through an aperture by measuring the impedance between inner and outer electrodes on opposite sides of the aperture in the liquid path, including a transducer probe incorporating said aperture and a volumetric metering chamber for metering a predetermined volume of liquid in connection with counting particles, the improvement comprising a conduit system disposed between said transducer probe and said metering chamber in the fluid path, the cross section of the conduit system being of a dimension such that bubbles which can be formed therein are small with respect to the predetermined volume of liquid to be metered by said volumetric metering chamber, and wherein said inner electrode comprises a first impedance measuring inner electrode on that side of the conduit system proximate said transducer probe and a second impedance measuring inner electrode disposed on that side of the conduit system proximate said volumetric metering chamber, said first and second inner electrodes being connected in parallel.

4,296,374

WIDEBAND DIGITAL SPECTROMETER


Paul S. Henry, Holmdel, N.J., assignor to Bell Telephone Laboratories, Incorporated, Murray Hill, N.J.

Filed Oct. 11, 1979, Ser. No. 83,596

Int. Cl.³ G01R 23/16

U.S. Cl. 324—77 B

5 Claims



1. A wideband digital spectrometer comprising: low-pass filtering means (10) for low-pass filtering an input signal; means (12) connected to the output of said filtering means capable of converting an analog signal to a plurality of N digital signals, each digital signal having M bits of resolution;

Walsh function generating means (14) for generating a plurality of N Walsh functions, each Walsh function being either +1 or -1;

means (18) capable of performing an $N \times N$ Walsh-Fourier power transformation characterized in that

the wideband digital spectrometer further comprises power spectrum generating means (16) connected to both the output of the analog-to-digital converting means (12) and the output of the Walsh function generating means (14) and capable of generating as an output a signal representative of a Walsh power spectrum of said analog-to-digital converting means, the output of said power spectrum generating means being connected to the input of the Walsh-Fourier power transformation means.

4,296,375

LEVEL INDICATOR FOR INDICATION OF MAXIMUM VALUES

Tsuneo Takezaki, Kadoma, Japan, assignor to Matsushita Electric Industrial Company, Kadoma, Japan


Filed Apr. 13, 1979, Ser. No. 29,714

Claims priority, application Japan, Apr. 14, 1978, 53/50086[U]

Int. Cl.³ G01R 19/04

U.S. Cl. 324—103 P

15 Claims



1. A level indicator system having a plurality of successively

located luminous elements arranged to indicate the level of an input voltage by their respective location, comprising:

means for providing a plurality of graduated reference voltages; a plurality of comparators each associated with a respective luminous element, each comparator having a reference input terminal biased at a respective reference voltage and a signal input terminal responsive to said input voltage, each comparator deriving an output signal in response to the voltage at the signal input terminal thereof exceeding the reference voltage at said reference input terminal; and a plurality of storage circuits each associated with a respective luminous element and a respective comparator and responsive to a respective comparator output signal for delivering an output signal to the associated luminous element.

4,296,376

PROBE FOR SENSING CHARACTERISTICS OF ELECTRICAL DEVICES UTILIZING A MAGNETIC SWITCH SENSOR BIASED BY AN ENCIRCLING MAGNETIC BIASING MEANS

Robert J. Bartol, Jr., 931 E. Tenth Pl., Mesa, Ariz. 85203


Continuation of Ser. No. 889,838, Mar. 24, 1978, abandoned.

This application Jan. 29, 1979, Ser. No. 7,472

Int. Cl.³ G01N 27/72; G01R 33/12, 19/14

U.S. Cl. 324—235

5 Claims



1. A probe for sensing magnetic field characteristics generated by electric devices comprising in combination:

a non-magnetic housing, a magnetizable switch forming a pair of contactable members mounted within said housing,

at least one of said members being movable in said housing relative to the other for engaging the other when in a magnetic field,

a lamp,

battery means having a pair of terminals,

a first means for connecting said lamp and said members in a series arrangement across the terminals of said battery means,

said members when exposed to a first magnetic field generated by an electric device deflecting relative to each other to engage to complete a circuit across said battery means to illuminate said lamp,

encapsulating means for said probe,

said encapsulating means comprising a first part, forming a cylindrical configuration encasing said lamp and battery means and a second part forming an elongated constant diameter cylindrical projection of said first part and of a size reduced from said first part and containing said housing,

and

a magnetic means for mounting on and surrounding at least a part of said projection for producing a second constant magnetic field which passes substantially longitudinally through the axis of said switch to aid in closing said switch,

said magnetic means comprises a magnet in the shape of a toroid slidably mounted around and snugly fitting the periphery of said projection for increasing the sensitivity of said probe with the center of said magnet being substantially in longitudinal alignment with said members,

said magnet being movable along said projection and over said members to a given position causing engagement of said members and when moved from said position along said projection to another position opening said contacts.

4,296,377

MAGNETIC SIGNAL FIELD SENSOR THAT IS SUBSTANTIALLY IMMUNE TO ANGULAR DISPLACEMENT RELATIVE TO THE SIGNAL FIELD
Hiroyuki Ohkubo, Chiba, Japan, assignor to Sony Corporation, Tokyo, Japan


Filed Mar. 23, 1979, Ser. No. 23,270

Claims priority, application Japan, Mar. 27, 1978, 53-34095; Mar. 27, 1978, 53-34096; Jun. 20, 1978, 53-83573[U]

Int. Cl.³ G01R 33/06

U.S. Cl. 324-252

16 Claims



1. Apparatus for sensing an external magnetic field to produce an output signal whose magnitude corresponds to the strength of said external magnetic field and is substantially insensitive to deviations in the direction of said external magnetic field, comprising a magnetic field sensor have only two coplanar magnetoresistive elements, each magnetoresistive element having a main current conducting path and each magnetoresistive element having anisotropic resistance as a function of the direction of the resultant magnetic field applied thereto, and bias means for supplying first and second equal bias magnetic fields to said first and second magnetoresistive elements, respectively, the intensity of the bias fields being sufficient to saturate said first and second magnetoresistive elements, said first bias magnetic field being supplied at an angle with respect to the first main current conducting path which differs from the angle at which said second bias magnetic field is supplied with respect to the second main current conducting path, said first and second magnetoresistive elements being connected in series with each other; said apparatus further comprising means for supplying a d.c. current to said series-connected first and second magnetoresistive elements; and means coupled to the junction defined by said series-connected first and second magnetoresistive elements to produce an output signal representing the magnitude of an external magnetic field as supplied to said first and second magnetoresistive elements, whereby said output signal is substantially immune to angular displacements of said magnetic field sensor relative to said external magnetic field.

4,296,378

APPARATUS PROVIDING ENHANCED DETECTION OF SPECIMENS IN INHOMOGENEOUS FIELDS
James D. King, San Antonio, Tex., assignor to Southwest Research Institute, San Antonio, Tex.

Filed Apr. 5, 1979, Ser. No. 27,302


Int. Cl.³ G01N 27/00

U.S. Cl. 324-313

18 Claims

1. Improvements in a nuclear magnetic or electron spin resonance detection apparatus which tests a sample for the presence and quantity of nuclei of interest which apparatus forms a magnetic field on the sample and wherein a magnetic field intensity of a specified value coacts with a transmitted RF pulse of a specified shape and frequency in the sample, which apparatus includes

- (a) a magnet control means;
 - (b) an electromagnet operated by said control means;
 - (c) a pulsed RF transmitter operable to form an RF pulse of a specified pulse shape and frequency;
 - (d) a receiver positioned to receive an RF signal from the sample as a result of the transmitted RF pulse;
- wherein the improvement comprises:
- (1) first means for selectively operating the magnet control means to form different magnetic field strengths acting on the sample to expose multiple incremental portions of the sample to a magnetic field intensity within specified limits;



- (2) timing means for controllably operating the transmitter to form repetitively transmitted pulses for the sample which pulses are transmitted into the sample synchronized with the operation of said first means; and
- (3) summing means connected to the receiver for summing repetitively formed received signals from the sample, said summing means summing the received signals after synchronization thereof relative to the relative occurrence of the transmitted RF signals.

4,296,379

GROUND PROSPECTING METHOD UTILIZING ELECTRICAL RESISTIVITY MEASUREMENTS FOR MEASURING THE RESISTIVITY OF UNIT BLOCKS OF THE GROUND


Eizaburo Yoshizumi, 402 Manhegm Kamogawa, 14 Yoshida Kawara-machi, Sakyo-ku Kyoto-shi, Kyoto-fu, Japan
Filed Aug. 23, 1978, Ser. No. 936,057

Claims priority, application Japan, Aug. 25, 1977, 52-102040; Dec. 26, 1977, 52-156766; Dec. 27, 1977, 52-159646; Apr. 17, 1978, 53-44932

Int. Cl.³ G01V 3/02

U.S. Cl. 324-357

7 Claims



1. A ground prospecting method, comprising dividing the entire region of the ground to be probed into a plurality of unit blocks in two-dimensional, areal, form or three-dimensional, volumetric, form, measuring by means of a plurality of sets of spaced current and voltage electrodes the apparent resistivity of each said unit block, and analytically determining the true resistivity of each said unit block from said measured apparent resistivity thereof to ascertain the condition of said ground region.

4,296,380

PROGRAMMABLE DIGITAL FREQUENCY DIVIDER FOR SYNTHESIZING SIGNALS AT DESIRED FREQUENCY


Hiroshi Minakuchi, Kadoma, Japan, assignor to Matsushita Electric Industrial Co., Osaka, Japan

Filed May 21, 1979, Ser. No. 40,618

Int. Cl.³ H03K 21/34; H03L 7/18

U.S. Cl. 328-48

22 Claims



1. A programmable digital frequency divider comprising:
 - a programmable binary counter responsive of input pulses from a pulse source and having a plurality of control terminals for generating output pulses at a frequency variable in accordance with a set of binary states of said control terminals; and
 - a binary code converter comprising a plurality of input terminals to which is applied an M-bit input binary signal, a plurality of output terminals connected to said control terminals of said programmable counter, and a logic circuit connected between said input and output terminals for converting said M-bit input binary signal into an N-bit output binary signal for application to said output terminals, where N equals an integral multiple of M minus an error compensating number which causes the frequency of said output pulses to vary substantially linearly as a function of discrete variations of said input binary signal.

4,296,381

DISTORTION REDUCTION CIRCUIT FOR AN INVERTING FEEDBACK AMPLIFIER


Bruce E. Hofer, Beaverton, Oreg., assignor to Tektronix, Inc., Beaverton, Oreg.

Filed Oct. 1, 1979, Ser. No. 80,711

Int. Cl.³ H03D 1/00

U.S. Cl. 330-149

3 Claims



1. An amplifier circuit, comprising:
 - an inverting feedback amplifier having inverting and non-inverting inputs and an output, an input impedance element connected to said inverting input, and a feedback impedance element connected from said output to said inverting input; and
 - a distortion reduction amplifier comprising a field-effect transistor, the gate of which is directly connected to said inverting input of said feedback amplifier, and the drain of which is coupled to said non-inverting input of said feedback amplifier.

4,296,382


CLASS AB PUSH-PULL FET AMPLIFIERS
Merle V. Hoover, Flemington, N.J., assignor to RCA Corporation, New York, N.Y.

Filed Dec. 28, 1979, Ser. No. 108,027

Int. Cl.³ H03F 3/30

U.S. Cl. 330-264

21 Claims



1. A Class AB quasi-linear push-pull amplifier comprising:
 - first and second supply terminals for receiving a relatively positive operating voltage and a relatively negative operating voltage respectively;
 - input and output signal terminals;
 - a p-channel, field-effect output transistor with a source electrode connected at said first supply terminal, with a drain electrode connected at said output signal terminal, and with a gate electrode;
 - an n-channel, field-effect output transistor with a source electrode connected at said second supply terminal, with a drain electrode connected at said output signal terminal, and with a gate electrode;
 - first potential translating means for maintaining a positive direct offset potential between said input signal terminal and the gate electrode of said p-channel output transistor during quiescent conditions and during positive excursions of input signal, which means includes a p-channel, field-effect source-follower transistor having the potential at said signal input terminal applied without translation to its gate electrode; and
 - a number N, at least one, of first forward-biased field-effect transistors having gate-source paths connected between the source electrode of said p-channel source-follower transistor and the gate electrode of said p-channel output transistor;
 - second potential translating means for maintaining a negative direct offset potential between said input signal terminal and the gate electrode of said n-channel output transistor during quiescent conditions and during negative excursions of input signal, which means includes an n-channel, field-effect source-follower transistor having the potential at said input signal terminal applied without translation to its gate electrode; and
 - a number N, of second forward-biased field-effect transistors having gate-source paths connected between the source electrode of said n-channel source-follower transistor and the gate electrode of said n-channel output transistor;
 - means for maintaining the quiescent potential at said input signal terminal at a potential between said relatively positive and relatively negative operating voltages, which means includes:
 - a direct-coupled feedback connection from said output signal terminal to said input signal terminal;
 - pull-up means for pulling up the potential at the gate electrode of said p-channel output transistor during substantially positive excursions of input signal; and
 - pull-down means for pulling down the potential at the gate electrode of said n-channel output transistor during substantially negative excursions of input signal.

conduit for the flow of said fluid upstream of said channel, portions of said wall member being adjacent a perimeter of said window and being in sealing engagement therewith;

means for reducing heat absorbed by said wall member comprising:

- a bevelled surface formed on said wall member externally of said conduit on said portions adjacent said perimeter of said window to provide a reduction in transverse thickness in said wall member portions adjacent said perimeter;
- a highly reflective surface formed on said bevelled surface and facing away from said channel, said reflective surface being adapted to reflect away from said wall member said light and said fluorescent radiation directed theretoward and emanating from within said channel and said light directed theretoward and reflected from said first interface;
- means in a confronting spaced relationship with said reflective surface for receiving and absorbing light energy reflected from said reflective surface.

4,296,389


CRIMPED COAX REFLECTIVE DISPERSIVE DELAY LINE

Harrison W. Fuller, Lexington, Mass., and Chester E. Stromswold, Nashua, N.H., assignors to Sanders Associates, Inc., Nashua, N.H.

Filed May 14, 1979, Ser. No. 39,229
Int. Cl.³ H01P 1/202, 3/06, 9/00, 11/00

U.S. Cl. 333—160

12 Claims



1. A crimped coax reflective broad band dispersive delay line with precisely linear delay vs. frequency characteristics so that the output of said delay line will function as a pulse compression filter when the input to said delay line is linearly fm frequency swept in a manner is matched to the linear delay vs. frequency characteristic of said delay line.

4,296,390


SOLDERLESS FILTER MOUNTING FOR HEADER ASSEMBLIES

Eric E. Vanderheyden, Hummelstown, and Albert Casciotti, Hershey, both of Pa., assignors to AMP Incorporated, Harrisburg, Pa.

Filed Apr. 21, 1980, Ser. No. 142,535
Int. Cl.³ H01R 19/06, 19/10, 13/66; H03H 7/01

U.S. Cl. 333—182

11 Claims



1. A filtered header or feedthrough connector comprising:

- a ground plane;
- a pair of hermaphroditic housing members of insulative material each having a planar first mating face and a profiled second mating face, a recess in each said planar

face, said recesses together defining a cavity, and a plurality of terminal bores each extending from said second faces to said cavity, said housing members adapted to be mounted by their first mating faces on opposite sides of said ground plane;

- a rubber block in each said cavity, each said block having a plurality of apertures therein, each aligned with a respective terminal bore in said housing members;
- a conductive rubber gasket in one cavity held in compression between said first mating face and said ground plane and having a like plurality of apertures therein; and
- a plurality of filtered terminal assemblies each including an elongated terminal with a filter sleeve secured intermediate the ends thereof and received in said blocks with the filter sleeve engaging said conductive gasket and the ends of the terminal projecting from said second mating faces to engage associated terminals, said conductive rubber gasket establishing electrical contact between said filter sleeve and said ground plane.

4,296,391

SURFACE-ACOUSTIC-WAVE FILTER FOR CHANNEL SELECTION SYSTEM OF TELEVISION RECEIVER

Katashi Hazama, Zushi, and Akitsuna Yuhara, Yokohama, both of Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed Oct. 24, 1978, Ser. No. 954,124

Claims priority, application Japan, Oct. 28, 1977, 52-128699; Oct. 28, 1977, 52-128700

Int. Cl.³ H03H 9/64, 9/68

U.S. Cl. 333—193

12 Claims



1. A surface-acoustic-wave filter for a channel selection tuning system comprising:

- a piezoelectric substrate;
- a plurality of surface-acoustic-wave comb filter means provided integrally on a surface of said substrate and exhibiting as a whole a comb frequency characteristic which corresponds to a channel frequency distribution for a plurality of channel bands corresponding to different programs over a wide channel range, each surface-acoustic-wave comb filter means comprising:

an input transducer for converting a local oscillator output of a corresponding channel band into an acoustic surface wave;

first and second output transducers electrically connected and physically spaced for converting surface acoustic waves from the input transducer into electric signals, said first and second output transducers being located along a surface-acoustic-wave propagation path on the substrate with different distances from and on the same side of said input transducer, the respective spacings of said first and second output transducers from said input transducer being such that the reciprocal of a differential delay time between the output electrical signals from said first and second output transducers is equal to a divisor of a channel spacing in the corresponding channel band;

input and output terminal means coupled on the substrate for connecting at least two of said filter means in parallel, said output terminal means being directly coupled with said first and second output transducers to provide a sum of

outputs of the first and second output transducers as the output of the comb filter.

4,296,392

SWITCHED CAPACITOR BILINEAR RESISTORS


Man S. Lee, Belmont, Calif., assignor to GTE Automatic Electric Laboratories, Inc., Northlake, Ill.

Filed Jun. 30, 1980, Ser. No. 164,394

Int. Cl.³ H03H 11/46

U.S. Cl. 333—213

24 Claims



1. An integratable switched capacitor circuit for simulating a resistor comprising:

- a capacitor having a pair of terminals;
- first means for effectively establishing a negative capacitance between a pair of terminals thereof;
- second means connecting associated ones of said terminals of said first means to said first and second nodes, respectively;
- third means for periodically connecting one side of said capacitor to ground and to one of said nodes at a prescribed switching frequency so as to simulate a resistor across said nodes.

4,296,393

CONTACT SPRING ARRANGEMENT FOR AN ELECTROMAGNETIC RELAY

Hans Sauer, Fichtenstrasse 5, Deisenhofen, Fed. Rep. of Germany (D-8024); Wolf Steinbichler, Am Hoehenpark, Bad Feilnbach, Fed. Rep. of Germany (D-8201), and Sepp Antonitsch, Holzham 2d, Otterfing, Fed. Rep. of Germany (D-8156)


Filed Jan. 24, 1980, Ser. No. 115,093

Claims priority, application Fed. Rep. of Germany, Jan. 25, 1979, 2902885

Int. Cl.³ H01H 67/02

U.S. Cl. 335—125

13 Claims



1. A contact spring arrangement for an electromagnetic relay including

- (a) a contact spring mounted on a terminal and having at least one portion serving as a movable contact cooperating with a fixed contact, and
- (b) an actuator engaging the contact spring and having a first actuator portion for moving the movable contact towards the fixed contact and a second actuator portion for withdrawing the movable contact from the fixed contact,
- (c) a first distance between the location at which the first actuator portion engages the contact spring and the contacting location of the movable and fixed contacts being greater than a second distance between the location at

which the second actuator portion engages the contact spring and said contacting location.

4,296,394


MAGNETIC SWITCHING DEVICE FOR CONTACT-DEPENDENT AND CONTACTLESS SWITCHING

A. Kadry Ragheb, 100 Francois, Montreal, Quebec, Canada
Filed Feb. 13, 1978, Ser. No. 870,846

Int. Cl.³ H01H 36/00

U.S. Cl. 335—207

72 Claims



1. A magnetic switch comprising:

- a. a switch mounting structure,
- b. a first driver member comprising:
 - 1. a first mounting portion by which said first member is moveably mounted relative to said switch structure,
 - 2. a first magnetically attractive portion having a first magnetically attractive surface portion,
 - 3. a first bearing portion,
- c. mounting means, attached to said switch structure, providing support for the movement of said first member,
- d. a second slave member comprising:
 - 1. a second mounting portion by which said second member is moveably mounted relative to said switch structure,
 - 2. a second magnetically attractive portion having a second magnetically attractive surface portion,
 - 3. a second bearing portion,
- e. first pivot means, attached to said switch structure, providing support for the movement of said second member,
- f. first stop means, mounted to said switch structure, located in the path of travel of said second member,
- g. said first and second members having a first position where the first and second magnetically attractive surface portions are located adjacent one another in a manner to cause said first and second members to be magnetically held in said first position, said first and second members also having a second position,
- h. said first member being moveable by an applied force to said second position in a manner causing the said first bearing portion to engage the said second bearing portion, the resulting engaged movement further causing a corresponding movement of said second member to said second position wherein said second member makes contact with said first stop means, said engaged movement further causing said first and second magnetically attractive surface portions to become spaced from one another by an air gap,
- i. at least one of said first and second members being mounted for angular movement relative to said switch structure in a manner that said first and second members move angularly relative to one another.

4,296,395

STRUCTURE FOR PREVENTING WINDING COLLAPSE
Bertil Moritz, Vesteras, Sweden, assignor to ASEA Aktiebolag, Vesteras, Sweden


Filed Nov. 2, 1979, Ser. No. 90,699

Claims priority, application Sweden, Nov. 9, 1978, 7811561; Feb. 28, 1979, 7901797

Int. Cl.³ H01F 27/08, 27/30

U.S. Cl. 336—60

13 Claims



1. A power transformer comprising at least two concentric, cylindrical windings, at least the innermost of which being wound from a conductor of tape or foil and having a circular cross-section, said innermost winding having an axial length greater than the axial length of an adjacent surrounding winding, an inner supporting cylinder made of metallic material for supporting said innermost winding, said inner supporting cylinder including a longitudinally extending, electrically insulating slot, and ring girders surrounding the ends of said innermost winding, said innermost winding being supported against said an adjacent surrounding winding and against said ring girders.

4,296,396

MANUAL ELECTRIC SWITCH WITH THERMAL RELEASE

Raymond A. Ingrain, Quetigny, and Jacques Cohen, Fontaine, both of France, assignors to La Telemecanique Electrique, France


Filed Jan. 29, 1980, Ser. No. 116,508

Claims priority, application France, Jan. 31, 1979, 79 02479

Int. Cl.³ H01H 71/16

U.S. Cl. 337—66

6 Claims



1. In a switch, with manual closing and opening and with thermal release, having a housing, an operating member in the housing and coupled to a control arm which is movable about a first fixed pivot and an end of which is coupled by a first articulation to a first end of a connecting rod to constitute a knee joint, a second end of said connecting rod being coupled by a second articulation to a loading lever, a first end of which loading lever is abutted on a latch displaced rotatably about a second fixed pivot, by the movement of overload bi-metallic strips, and a second end of which loading lever cooperates with a transmission lever which is associated with movable

contacts, and which pivots about a third pivot, the improvement that:

- (i) the first pivot and the second pivot are disposed in the proximity of an upper part of said housing near to said operating member,
- (ii) said third pivot is fixed and disposed at the lower part,
- (iii) said three pivots are placed substantially at the apices of a right-angled triangle, and
- (iv) said second and third pivots are placed on a straight line substantially parallel to the direction of movement of said operating member and to the direction of movement of said movable contacts.

4,296,397

FUSE STRUCTURE FOR CORROSIVE ATMOSPHERE
Donald C. Sedberry, Erdenheim, Pa., assignor to Welsbach Ozone Systems Corporation, Philadelphia, Pa.

Filed May 30, 1980, Ser. No. 155,799

Int. Cl.³ H01H 1/06

U.S. Cl. 337—199

12 Claims



1. A fuse structure for use with ozonators and corrosive atmosphere applications comprising:

- a fine ozone corrosion resistant fuse wire;
- conductive terminal means to which the fuse wire is conductively attached and which in turn enable fuse connection into a circuit;
- rigid insulator spacing means engaging and spacing the terminal means so that the fuse wire is extended and so that the structure constitutes a unitary structure which may be handled as a unit; and
- insulator shield means placed over the fuse wire over a substantial portion of its length and serving to shield the insulator spacing means from vaporized filament material when the fuse opens in order to avoid a conductive path being formed by vaporized fuse metal condensing on the insulator through which an alternate electrical path exists through the fuse.

4,296,398

PRINTED CIRCUIT FUSE ASSEMBLY


James D. McGalliard, Santa Ana, Calif.

Filed Dec. 18, 1978, Ser. No. 970,632

Int. Cl.³ H01H 85/04

U.S. Cl. 337—297

1 Claim




1. A printed circuit, including multiple printed circuit fuse elements, comprising:

- a circuit substrate;
- a printed circuit formed on said substrate for interconnecting

circuit components, said printed circuit including a circuit bus;

- a first printed circuit fuse element formed on said substrate, interconnected to limit the current in said printed circuit to protect said printed circuit from abnormally high currents, said first printed circuit fuse element having a predetermined current capacity which is lower than the current capacity of the conductors of said printed circuit which are connected to said first printed circuit fuse element; and
- a second printed circuit fuse element on said substrate, having a solder land adjacent said circuit bus, said land separated from said bus sufficiently to electrically isolate said land from said bus, but spaced close enough to said bus to permit molten solder to be applied as a jumper from said land to said bus, said second printed fuse element, when solder is applied connecting said land to said bus, being in parallel circuit connection with said first printed circuit fuse element.

waves, said means for modulating is adapted to provide two types of modulated signals which are orthogonal to one another, one for the modulation of bearing information and the other for the modulation of transfer messages or commands, change-over switch means selectively connecting said means



for modulating to said first antenna over a shunt means or to said second antenna, and control means connected to said change-over switch means and said means for modulating for selectively controlling the type of modulation utilized and the antenna employed for a selected transmission.

4,296,399

MICROMINIATURE PALLADIUM OXIDE GAS DETECTOR AND METHOD OF MAKING SAME

Frank T. John, Williamsville, N.Y., assignor to A-T-O Inc., Willoughby, Ohio


Division of Ser. No. 862,974, Dec. 21, 1977, Pat. No. 4,193,964.

This application Aug. 6, 1979, Ser. No. 64,020

Int. Cl.³ H01L 17/04, 7/00

U.S. Cl. 338—34

2 Claims



1. A method for making a miniature platinum or palladium wire coil comprising winding a wire having a diameter of from about 0.0001 cm to about 0.005 cm about a mandrel, said mandrel being made of a material which can be removed by oxidation without oxidizing said wire; coating the wire wound about said mandrel with a ceramic precursor; drying and curing the ceramic precursor to form a ceramic binder and removing said mandrel by oxidation, said precursor comprising aluminum phosphate, phosphoric acid, chromium phosphate, submicron aluminum oxide and water.

4,296,400

INSTALLATION FOR CONTROL OF A TRAFFIC LIGHT SYSTEM BY VEHICLES HAVING AN AUTOMATIC LOCATION DETERMINATION

Becker Friedbert; Johann Steinkamp, both of Munich, and Klaus Koenen, Berg, all of Fed. Rep. of Germany, assignors to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany

Filed Nov. 28, 1978, Ser. No. 964,431

Int. Cl.³ G08G 1/07

U.S. Cl. 340—32

2 Claims

1. In an installation for the control of a traffic light system from a vehicle, the combination of means carried by the vehicle for supplying information for automatic determination of position, i.e. bearing determination, a first directional antenna for transmission/reception, carried by the vehicle for transmission of such bearing information and having its transmission direction oriented essentially perpendicular to the direction of travel of the vehicle, a second directional antenna carried by the vehicle and oriented in the direction of travel of the vehicle for transmission of transfer messages or commands for the control of lights of such a traffic light system, means for producing carrier waves, means for modulating said carrier

1. A vehicle detector circuit for use with an inductive detector loop for sensing the presence of a vehicle in the vicinity of the loop, comprising:

- first means connectable to an inductive detector loop to impress on the loop a voltage of predetermined waveform including a discontinuity and produce therein a current whose relationship to the impressed voltage is essentially determined by the inductive time constant of the loop;
- second means responsive to the current in the loop and having a non-resonant response to provide a signal having the waveform of the current in the loop;
- comparator means responsive to said voltage waveform and to said current waveform signal to provide a signal dependent on the lag of the current waveform with respect to said discontinuity of the voltage waveform due to the inductive time constant of the loop circuit; and
- analyzer means responsive to changes in said lag-dependent signal to provide an output signal indicative of the presence of a vehicle in the vicinity of the detector loop.

4,296,402

VEHICLE ANTI-THEFT DEVICE

Slawomir Z. Szczepanski, 5455 N. Sheridan Rd., Chicago, Ill. 60640

Filed Apr. 2, 1980, Ser. No. 136,412

Int. Cl.³ B60R 25/04

U.S. Cl. 340—64


15 Claims

1. An anti-theft device for a motor vehicle having an electrical system including a starter relay, said device comprising: a four-node electrical network including a first resistive segment having a predetermined resistance R_1 between a first interface node and a first intermediate node, a second

resistive segment having a predetermined resistance R_2 between the first intermediate node and a second interface node, a third resistive segment having a predetermined resistance R_3 between the second interface node and a second intermediate node, a fourth resistive segment having a predetermined resistance R_4 between the second intermediate node and the first interface node, said resistances R_1 , R_2 , R_3 , and R_4 satisfying the equation

$$R_1 R_3 = R_2 R_4$$

at least a part of said third resistive segment being removable, said first and second interface nodes being connected to the



electrical system of the motor vehicle such that a voltage differential is created between the first and the second interface nodes when the electrical system is activated;

means for detecting an imbalance in an electrical property between said first intermediate node and said second intermediate node whenever the resistance of the third resistive segment is different from R_3 and for generating in response thereto an output signal;

an electrical component; and

means for receiving the output signal and for disabling in response thereto said electrical component, said component selected such that means for receiving and disabling does not prevent normal operation of the starter relay but prevents operation of the engine.

4,296,403

METHOD AND CIRCUIT ARRANGEMENT FOR SWITCHING AND TRANSMITTING SIGNALS IN, OR FROM, A STORED PROGRAM CONTROLLED SWITCHING SYSTEM

Eckhart Haensel, Munich, Fed. Rep. of Germany, assignor to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany

Filed Nov. 29, 1979, Ser. No. 98,387

Claims priority, application Fed. Rep. of Germany, Dec. 8, 1978, 2853138

Int. Cl.³ H04Q 3/00

U.S. Cl. 340—147 P

3 Claims

1. A circuit arrangement for switching and emitting signals in or from, respectively, a stored program controlled switching system having a plurality of addressable feeder channels supplying signals in the incoming transmission direction and a plurality of like-addressed receiving channels for feeding signals out in the outgoing direction, comprising:

a stored program controlled switching system connected to the plurality of feeder channels which supply signals in the incoming transmission direction and to the plurality of receiving channels which feed signals in the outgoing transmission direction;

control means including programs stored therein for determining the processing steps to be executed;


said control means including a memory storing the processing programs;

an addressing device connected to said memory for receiving

addresses and emitting a channel address designating a feeder channel and a receiving channel for the duration of the handling of the processing program relating thereto;

a control device including a control input, said control input connected to said addressing device for feeding addresses thereto;

a plurality of terminating devices connected to the feeder channels for receiving and recognizing the occurrence of



signals therein, said terminating devices connected to said control input of said control device and operable to cause said control device to feed channel addresses to said addressing device; and

means connected between said addressing device and said terminating devices and operable in response to addresses to condition the addressed terminating devices for transmission in both directions over the respective addressed channels.

4,296,404

REMOTE VERIFICATION LOCKOUT SYSTEM


James R. Sheldon, Phoenix, Ariz., assignor to Engineered Systems, Inc., Tempe, Ariz.

Filed Oct. 18, 1979, Ser. No. 85,895

Int. Cl.³ G06K 5/00; H04Q 3/02

U.S. Cl. 340—149 A

5 Claims



1. A system for providing a verification check of uniquely encoded multibit binary words at a plurality of remote locations, the system having a central station for supplying address signals and verification "valid/non-valid" control signals through a transmission link interconnecting said central station with each of said plurality of remote locations, each of said remote locations including in combination:

read/write memory means having a plurality of address locations therein, each address location storing a single binary bit indicative of the "valid/non-valid" status of the item represented by each such address location, said memory means further having a single output on which an output signal is produced corresponding to the binary bit stored at the address location selected in said memory means;

lockout utilization means coupled to the output of said mem-

ory means and operated in response to output signals appearing thereon;

address control means operated in response to addressing signals and coupled to said memory means for selecting particular address locations for the writing of bits into and the reading of bits from those address locations of said memory means;

read/write control means coupled to said memory means and further coupled with said transmission link and responsive to signals applied thereto from said central station over said transmission link for controlling the read/write mode of operation of said memory means and for supplying said verification control signals to said memory means to selectively change the "valid/non-valid" status of the binary bits stored in said memory means when said memory means is in the write mode of operation;

gating circuit means having a plurality of inputs and having outputs coupled with said address control means for supplying said addressing signals thereto;

address decoding means coupled to selected inputs of said gating circuit means and further coupled with said transmission link and responsive to address signals supplied thereto from said central station over said transmission link for supplying address input signals to said gating circuit means;

further circuit means coupled to others of the inputs of said gating circuit means for supplying input addressing signals thereto; and

selecting means coupled with said read/write control means and operated thereby and further coupled to said gating circuit means for causing the signals appearing on the outputs of said gating circuit means to be selected from the input signals from said address decoding means or the input signals from said further circuit means, thereby causing the signal on the output of said memory means to correspond to the binary bit stored at the address location selected by the addressing signals from said gating circuit means.

4,296,405

DEVICE FOR CONVERTING ANALOG SIGNALS FROM A NATURAL LEAF SCANNER INTO DIGITAL SIGNALS AND METHOD OF OPERATING SAME


Leonard G. Rich, West Hartford, Conn., assignor to Gulf & Western Corporation, New York, N.Y.

Filed May 2, 1978, Ser. No. 902,253

Int. Cl.³ G06K 9/00; A24C 1/00

U.S. Cl. 340—146.3 AG

9 Claims



1. A device for converting a succession of analog voltage signals representative of the light intensity of light from and controlled by a corresponding succession of finite surface locations of a natural leaf into a white, black or gray digital signal for each given location, said device comprising: means for creating a white digital signal when an analog voltage signal at a given location exceeds a first threshold voltage corresponding to a given light intensity value; means for creating a black digital signal when an analog voltage signal at a given location is below a second threshold voltage; averaging means for creating said second threshold voltage by averaging at least a majority of previous analog signals of said succession of locations; means for excluding said analog signal for a given

location from said averaging means when said analog signal creates said white digital signal; and, means for creating a gray digital signal in the absence of said white and black signals for a given location.

4,296,406

PRESSURE SENSITIVE SWITCH STRUCTURE


Billy J. Pearson, Bluff City, Tenn., assignor to Sperry Corporation, New York, N.Y.

Filed Dec. 28, 1979, Ser. No. 107,970

Int. Cl.³ G08C 21/00

U.S. Cl. 340—166 R

6 Claims



1. A pressure sensitive matrix switch device comprising: an insulative base, a first conductive pad means having a plurality of switch pads, a second conductive pad means, at least one of said pads being mounted on said base, a pressure sensitive conductive-resistive material intermediate said conductive pad means, said conductive-resistive material normally displaying a very high resistance therebetween when no pressure is applied, said conductive-resistive material displaying a low resistance therebetween when a light pressure is applied, means for applying pressure to said conductive pads to compress said conductive-resistive material and to change the resistance of said conductive-resistive material from a relatively high ohmic value to a relatively low ohmic value, voltage source means connected to the said second conductive pad means, said change of said conductive-resistive material from a relatively high ohmic value to a relatively low ohmic value for generating a voltage signal from one of said switch pads indicative of a particular switch device being operated, and logic encoder means coupled to said voltage signal for generating binary coded signals indicative of one of said matrix switch devices being operated.

4,296,407

DIGITAL FREQUENCY SYNTHESIZER WITH FREQUENCY DIVIDER PROGRAMMABLE IN RESPONSE TO STORED DIGITAL CONTROL SIGNAL

Hiroshi Minakuchi, Osaka, Japan, assignor to Matsushita Electric Industrial Co., Osaka, Japan

Filed May 14, 1979, Ser. No. 38,991

Int. Cl.³ H03L 7/18; H03K 13/20

U.S. Cl. 340—347 CC

10 Claims

1. A digital frequency synthesizer having a programmable frequency divider for dividing the frequency of a standard frequency signal by a variable integral multiple, comprising: means for generating a manually adjustable analog control signal, analog-to-digital converter means for converting said

solvent supply means for supplying solvent to the cap means; and
control means for moving the cap means into covering engagement with the nozzle means and controlling the solvent supply means to supply solvent to the cap means in response to the sensor means sensing the ink clog.

4,296,419

MEMBER FOR RECORDING INFORMATION


Motoyasu Terao, Tokyo; Kazuo Shigematsu, Kawasaki; Masahiro Ojima, Kokubonji, and Seiji Yonezawa, Hachioji, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan
Filed Sep. 17, 1979, Ser. No. 76,424

Claims priority, application Japan, Sep. 19, 1978, 53-127535[U]

Int. Cl.³ G01D 15/34

U.S. Cl. 346—135.1

20 Claims



1. A member for recording information by forming apertures or recesses in a thin film owing to heat generated by projecting a recording beam onto the thin film, comprising a thin film on a substrate, wherein said thin film comprises an antimony-bismuth alloy having an antimony content lying within a range of from 1% to 15% inclusive in terms of percentage of an average number of atoms in a thickness direction of said thin film, whereby deterioration of the recording characteristic of the thin film with aging of the member is suppressed.

4,296,420

CHART RECORDER HAVING PRESSURIZED INK SUPPLY AND Z FOLD PAPER FEED AND IMPROVED CHART RECORDING METHOD


Thomas F. Dambach, Glendale, and James R. Ricketts, Milwaukee, both of Wis., assignors to Marquette Electronics, Inc., Milwaukee, Wis.

Filed Nov. 8, 1976, Ser. No. 740,003

Int. Cl.³ G01D 15/16, 15/34

U.S. Cl. 346—140 R

17 Claims



1. A chart recorder for providing a graphic recording on a Z-folded recording medium strip having a path of movement through the recorder from a supply stack to a discharge, said recorder comprising:

- a frame;
- a writing platen mounted on said frame along the path of movement of the strip and presenting a flat, hard surface over which said strip passes;
- a pressurized ink supply system having at least one pen positioned above said platen and having a tip urged into contact with said strip as it passes over said platen;
- drive means positioned downstream of said writing platen for engaging the strip to draw it off the supply stack and over the writing platen; and
- pressure means mounted on said frame, said pressure means including a flat pressure plate positioned over the surface of said platen and lying generally parallel thereto, said

plate being positioned adjacent said pen tip immediately upstream thereof for pressing the strip flat onto the platen under said pressure plate and pen tip and for generating tension in the strip when it is moved by the drive means which further causes the strip to lie flat across the platen.

4,296,421

INK JET RECORDING DEVICE USING THERMAL PROPULSION AND MECHANICAL PRESSURE CHANGES


Toshitami Hara, Tokyo; Yashushi Sato, Kawasaki; Yasushi Takatori, Machida, and Yoshiaki Shirato, Yokohama, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan
Filed Oct. 24, 1979, Ser. No. 87,801

Claims priority, application Japan, Oct. 26, 1978, 53-131860; Oct. 26, 1978, 53-131861; Oct. 30, 1978, 53-133376; Nov. 14, 1978, 53-140111; Nov. 14, 1978, 53-139978; Nov. 14, 1978, 53-139979; Dec. 4, 1978, 53-150377; Dec. 15, 1978, 53-156102; Dec. 20, 1978, 53-157148; Dec. 27, 1978, 53-165883

Int. Cl.³ G01D 15/18

U.S. Cl. 346—140 R

23 Claims



1. A device for recording comprising ejecting a liquid recording medium by heat energy which comprises a recording head composed of
a discharging orifice for ejecting the liquid recording medium in a form of droplets,
an inlet for introducing the liquid recording medium,
a liquid chamber for holding the liquid recording medium, and
a heating element for applying heat energy to the liquid recording medium in the liquid chamber, and
a means for generating a mechanical pressure change in the liquid recording medium flowing into the liquid chamber, a means for synchronizing the application of heat energy to the liquid recording medium with the generation of the mechanical pressure change, and
a means for applying voltage pulse to control heating by the heating element, the distance between the surface of the heating element and the liquid recording medium being not more than 100 microns.

4,296,422

IMAGE RECORDING MATERIAL AND IMAGE RECORDING METHOD USING THE SAME

Kazuhiro Kawaziri; Masato Fujiwara; Isamu Hatanaka; Masatoshi Tabel; Akio Higashi, and Mitsuharu Nirasawa, all of Asaka, Japan, assignors to Fuji Photo Film Co., Ltd., Kanagawa, Japan

Filed Jan. 24, 1979, Ser. No. 6,022

Claims priority, application Japan, Feb. 8, 1978, 53-13300


Int. Cl.³ G01D 15/14; G03G 15/00

U.S. Cl. 346—160

13 Claims

7. A method of recording an image on an image recording member comprising (a) a recording medium including a support base, at least one surface of which is electrically conductive and a recording layer provided on the electrically conductive surface of said support base containing an oxidizable or reducible compound, and (b) a photoconductor disposed in contact with a surface of said recording layer of said recording

medium, said photoconductor having a specific resistance of not more than $10^9 \Omega \text{cm}$, where the boundary between the photoconductor and the recording layer is electrically rectifying, said method comprising the steps of



applying a reverse bias voltage across the said boundary and imagewise exposing the photoconductor while said bias voltage is being applied to the boundary.

4,296,423

DEVICE FOR ADJUSTING IMAGE DENSITY IN COMPOSITE INFORMATION RECORDING APPARATUS

Hiroya Nakamura, Hino, Japan, assignor to Konishiroku Photo Industry Co., Ltd., Tokyo, Japan


Filed Aug. 14, 1979, Ser. No. 66,423

Claims priority, application Japan, Aug. 18, 1978, 53-100017

Int. Cl.³ G01D 15/40; G03G 15/00, 15/00

U.S. Cl. 346—160

2 Claims



1. In a composite information recording apparatus including a photoconductive medium on which an electrostatic latent image is formable in accordance with a copying and/or a recording operation, a developing device having a developing electrode for developing the latent image on the photoconductive medium, means for supplying a bias voltage applied between the developing electrode and the photoconductive medium, and a signal reproducing device for use in the recording operation; an image density adjusting device, comprising: switch means operable for selectively adjusting the bias voltage applied to the developing electrode in accordance with the density of an original to be copied; means supplying a variable voltage to said signal reproducing device; and further means operable by said switch means for controlling said variable voltage supply means to apply a variable voltage to said signal reproducing device in correspondence with the selectively adjusted bias voltage applied to the developing electrode, whereby image density of the recording operation is controlled in accordance with image density control of the copying operation.

4,296,424

COMPOUND SEMICONDUCTOR DEVICE HAVING A SEMICONDUCTOR-CONVERTED CONDUCTIVE REGION

Ichiro Shibasaki; Kaoru Ohmura, and Takeo Kimura, all of Fuji, Japan, assignors to Asahi Kasei Kogyo Kabushiki Kaisha, Osaka, Japan


Filed Mar. 22, 1979, Ser. No. 22,916

Claims priority, application Japan, Mar. 27, 1978, 53-34062; Mar. 27, 1978, 53-34063; Aug. 9, 1978, 53-96114

Int. Cl.³ H01L 27/24, 45/00, 23/48

U.S. Cl. 357—1

20 Claims



1. A compound semiconductor device comprising a functional portion of a compound semiconductor mainly comprising a group III-V compound semiconductor and an electrode portion connected to said semiconductor functional portion, wherein said electrode portion comprises a region of the compound semiconductor in which the material of said compound semiconductor is changed in the solid phase state to cause a change in its energy band structure and is thereby converted to a conductor in ohmic contact with the contiguous portion of the compound semiconductor.

4,296,425

LUMINESCENT DIODE HAVING MULTIPLE HETERO JUNCTIONS

Jun-ichi Nishizawa, Sendai, Japan, assignor to Handotai Kenkyu Shinkokai, Sendai, Japan


Continuation of Ser. No. 867,158, Jan. 5, 1978, abandoned, which is a continuation-in-part of Ser. No. 761,468, Jan. 21, 1977, abandoned, which is a continuation of Ser. No. 543,617, Jan. 24, 1975, abandoned, which is a continuation-in-part of Ser. No. 314,393, Dec. 12, 1972, abandoned. This application Sep. 18, 1979, Ser. No. 76,675

Claims priority, application Japan, Dec. 14, 1971, 46-100623

Int. Cl.³ H01L 33/00, 29/203, 29/205

U.S. Cl. 357—17

14 Claims



2. A luminescent diode comprising:

- A p+ type substrate;
- at least one unit consisting of a p-type layer of a certain band gap and an n-type layer of a band gap wider than said certain band gap and epitaxially grown on said p-type layer to form a heterojunction at the interface between said p-type layer and said n-type layer, said unit being disposed in such a way that said p-type layer is located closer to said substrate than is said n-type layer, the band gap of said p-type layer increasing monotonically with distance from said substrate;
- said substrate being capable of absorbing light entering there into from said p-type layer; and
- a low resistivity contact disposed on an outermost surface of

said unit opposite to said substrate, said contact having an area contacting said outermost surface smaller than the area of said outermost surface for allowing a light output to be taken at said outermost surface.

4,296,426


PROCESS FOR PRODUCING AN MOS-TRANSISTOR AND A TRANSISTOR PRODUCED BY THIS PROCESS
Jean Gilles, Paris, France, assignor to Thomson-CSF, Paris, France

Filed Feb. 13, 1979, Ser. No. 11,923

Claims priority, application France, Feb. 17, 1978, 78 04528
Int. Cl.³ H01L 29/78

U.S. Cl. 357—23

13 Claims



1. A method for making an insulated gate field effect transistor of the type having a source region with a source contact electrode of polycrystalline silicon, a drain region with a drain contact electrode of polycrystalline silicon, and a channel region between the source and drain regions with an insulated control gate above the channel region, the method comprising the steps of:

providing a semiconductor substrate;
forming source and drain contact electrodes of polycrystalline silicon on the upper surface of the semiconductor substrate, each of said electrodes being doped with an impurity of a first type of conductivity and wherein at least one of the source and drain electrodes contains an impurity of the opposite type of conductivity to said first type and has a rate of diffusion greater than the rate of diffusion of the impurity of the first type of conductivity; and

heating the substrate so as to simultaneously form a source region and a drain region in the semiconductor substrate by diffusion of the impurity of the first type of conductivity from the electrodes into the substrate so as to produce a laterally diffused part of the channel adjacent to the source or drain region, said step of heating being effected at a predetermined temperature during a predetermined time to control the length of the laterally diffused part of the channel.

4,296,427

REVERSE CONDUCTING AMPLIFIED GATE THYRISTOR WITH PLATE-LIKE SEPARATOR SECTION
Minami Takenchi, Tokyo, and Minoru Kuriki, Kawasaki, both of Japan, assignors to Tokyo Shibaura Electric Co., Ltd., Japan

Continuation of Ser. No. 802,070, May 31, 1977, abandoned.

This application Aug. 28, 1979, Ser. No. 70,655

Claims priority, application Japan, May 31, 1976, 51/63242
Int. Cl.³ H01L 29/747

U.S. Cl. 357—39


1 Claim

1. A reverse conducting thyristor comprising a thyristor section, diode section and a semiconductor separator section interposed between the thyristor and diode sections so as to prevent electrical interference between the thyristor and diode sections, said three sections being integrally formed into a cylindrical body,

said thyristor section including a first region of a first conductivity type formed on a first electrode; a second region of a second conductivity type formed on the first region, a third region of the first conductivity type formed on the

type formed in the third region, a cathode electrode a part of which is formed on the main emitter region, an auxiliary emitter region formed in the third region, an auxiliary gate electrode formed partly on the third region and partly on the auxiliary emitter region, and a main gate electrode formed on that surface portion of the third region which is adjacent to that lateral surface of the auxiliary emitter region which does not face the main emitter region;

said diode section including a fourth region of the second conductivity formed on the first electrode, a fifth region of the first conductivity type formed on the fourth region, and a part of said cathode electrode formed on the fifth region;



said semiconductor separator section including a sixth region of the first conductivity type formed on the first electrode, a seventh region of the second conductivity type formed on the sixth region, and an eighth region of the first conductivity type formed on the seventh region, said sixth, seventh and eighth regions being integrally formed into a flat plate;

said cathode electrode having a first portion disposed on a first part of said main emitter region and having a radius smaller than that of said first part of said main emitter region and a second portion disposed on said fifth region and on a remaining second part of said main emitter region and having a radius larger than that of said remaining second part of said main emitter region;

said auxiliary gate electrode surrounding the outer periphery of said first portion of said cathode electrode.

4,296,428

MERGED FIELD EFFECT TRANSISTOR CIRCUIT AND FABRICATION PROCESS


Tegzi P. Haraszti, Garden Grove, Calif., assignor to Rockwell International Corporation, El Segundo, Calif.

Filed Jun. 28, 1979, Ser. No. 52,881

Int. Cl.³ H01L 27/02

U.S. Cl. 357—41

48 Claims



1. A semiconductor device comprising:

a first body of semiconductor material having first and second spaced apart surfaces, including a first surface zone of a first conductivity type and a first dopant concentration adjacent said first surface, a second surface zone of a second conductivity type and a second dopant concentration different from said first concentration adjacent said

first surface and said first surface zone, and a third surface zone of said first conductivity type and said first dopant concentration adjacent said first surface and said second surface zone, said third surface zone being spaced apart from said first surface zone such that said second surface zone lies between said first and said third surface zones; said first and said second surface zones forming respectively first and second active regions of a first transistor device, and said second surface zone forming a control region of said first transistor device; a fourth surface zone of said first conductivity type and said first dopant concentration formed in said first body, said fourth surface zone being disposed adjacent said second surface, and directly connected with said third surface zone through a semiconductor body portion of said first body;

means for applying an electrical potential to said first and said third surface zones; and

control means disposed adjacent said second surface zone for controlling the flow of current through said second surface zone.

4,296,429


VMOS TRANSISTOR AND METHOD OF FABRICATION
James E. Schroeder, Indialantic, Fla., assignor to Harris Corporation, Melbourne, Fla.

Division of Ser. No. 932,232, Aug. 9, 1978. This application Nov. 26, 1979, Ser. No. 97,457

Int. Cl.³ H01L 29/06

U.S. Cl. 357—55

8 Claims



1. In a vertical insulated gate field effect transistor having a first layer of a first conductivity type, a second layer of a second conductivity type on said first layer, a horizontal surface region in said second layer of said first conductivity type, a groove extending from said horizontal surface region through said second layer and into said first layer, a layer of insulation in said groove and a gate material in said groove and on said layer of insulation, the portion of said second region adjacent said gate material being a vertical channel between said first layer and said horizontal surface region, the improvement comprising a vertical surface region in the lateral surface of said second layer adjacent said gate, contiguous to said horizontal surface region and terminating vertically within said second layer, said vertical channel being between the end of said vertical surface region and said first layer.

4,296,430

MAGNETIC RECORDING WITH REDUCED CROSS-TALK AND INTERCHANNEL TIME DISPLACEMENT

Henry R. Warren, Belle Mead, N.J., assignor to RCA Corporation, New York, N.Y.

Filed Oct. 12, 1979, Ser. No. 84,395


Int. Cl.³ H04N 5/78

U.S. Cl. 358—8

4 Claims

1. A magnetic head device for recording on magnetic tape, said device comprising a rotating drum, two pairs of magnetic heads, each pair comprising a wide width head for recording high frequency information and a narrow width head for recording low frequency information, each of said pairs having a gap between the heads comprising the pair, the order of the high and low frequency heads within one of said pairs being

reversed with respect to the order of the high and low frequency heads of the remaining pair, said pairs being mounted on said drum to provide that the recording tracks laid down on



the tape by the low frequency heads have a guardband therebetween of the sum of the amounts by which the narrow heads differ in widths from the wide heads of the same pair respectively.

4,296,431


HIGH-RESOLUTION TELEVISION SYSTEM
Kenneth F. Holland, Canyon Country, Calif., assignor to Ygnacio Inc., Santa Barbara and Compact Video Systems Inc., Burbank, both of Calif.

Filed Apr. 11, 1980, Ser. No. 139,475

Int. Cl.³ H04N 9/38

U.S. Cl. 358—12

17 Claims



1. A method for conveying color information in a television system, comprising the steps of:

- producing first and second color signals together containing said color information;
- using each of said color signals to separately modulate a carrier signal;
- reversing the phase of said carrier signal modulated by said first color signal at a first rate;
- reversing the phase of said carrier signal modulated by said second color signal at a second rate different from said first rate;
- combining said modulated carrier signals into a single modulated color subcarrier;
- transmitting said color subcarrier;
- demodulating said subcarrier upon receipt to obtain said first and second color signals.

4,296,432

DYNAMIC ENABLING NETWORK FOR A COLOR CORRECTION CIRCUIT


Christopher M. Engel, Arlington Heights, and Gopal K. Srivastava, Buffalo Grove, both of Ill., assignors to Zenith Radio Corporation, Glenview, Ill.

Filed Jul. 28, 1980, Ser. No. 172,903

Int. Cl.³ H04N 9/535

U.S. Cl. 358—28

12 Claims



1. In a television receiver which provides color-difference signals having A.C. components superimposed on a D.C. bias level, and in which a color correction circuit automatically operates on the color-difference signals to adjust their effective phase toward a fleshtone axis, a dynamic enabling and disabling network for the color correction circuit, comprising:

means for combining selected color-difference signals to generate a first control signal having a D.C. level corresponding to the D.C. bias level of the color-difference signals and having an A.C. component whose magnitude is near a maximum when the color-difference signals are representative of fleshtone hues;

means responsive to said selected color-difference signals for generating a second D.C. control signal whose amplitude is a function of the D.C. bias level of the selected color-difference signals;

a comparator receiving the first and second control signals for generating an enable output signal when the difference in amplitude between the first and second control signals is indicative of color-difference signals having a phase within a preselected range of fleshtone hues, and for generating a disable output signal when no such difference in amplitude exists; and

means for coupling the output signals of the comparator to the color correction circuit.

4,296,433

COLOR TELEVISION RECEIVING SYSTEM WITH FORCED CHROMA TRANSIENTS


Theodore S. Rzeszewski, Lombard, Ill., assignor to Matsushita Electric Corporation of America, Franklin Park, Ill.

Filed May 19, 1980, Ser. No. 151,360

Int. Cl.³ H04N 9/535

U.S. Cl. 358—37

9 Claims



1. In a television receiver including processing circuits pro-

ducing signals for application to a picture tube, a system for improving transient response, including in combination:

sensing means coupled with the processing circuits of the television receiver for sensing changes in the level of a signal and providing an output indicative thereof;

second means coupled with the output of said sensing means for producing an output signal when a predetermined output signal level is obtained from said sensing means; and

control circuit means coupled with said sensing means and said second means for forcing the signal level applied to the picture tube to a predetermined signal level proportional to the output of said sensing means irrespective of the level of the signal applied to the picture tube by the processing circuits.

2. The combination according to claim 1 wherein the television receiver is a color television receiver, the processing circuits produce demodulated color signals for application to a color picture tube, and said system is for improving color transient response; and wherein said control circuit means forces said predetermined signal level for a predetermined period of time.

4,296,434

METHOD OF AND APPARATUS FOR MOVEMENT PORTRAYAL WITH A RASTER E.G. TELEVISION, DISPLAY

John O. Drewery, Coulsdon, and Richard Storey, Sutton, both of England, assignors to British Broadcasting Corporation, London, England


Filed May 29, 1979, Ser. No. 43,608

Claims priority, application United Kingdom, May 30, 1978, 23924/78

Int. Cl.³ H04M 5/30

U.S. Cl. 358—105

22 Claims



1. A method of portraying movement with a raster display, comprising the steps of:

storing a scan of the display;

comparing a subsequent input scan with the stored scan to detect differences therebetween which may represent motion of a displayed object;

retaining a continuing indication of the positions on the display of the differences thus detected;

retaining the portions of the input scan at positions for which a new difference is detected, and no difference has been detected previously; and

including in the output display the thus-retained portions.

4,296,435

LUMINANCE SIGNAL PROCESSING CIRCUIT

Alain H. d'Hautecourt, Prospect Heights; Wayne E. Bretl, Schaumburg, and Ronald B. Lee, Skokie, all of Ill., assignors to Zenith Radio Corporation, Glenview, Ill.

Filed Aug. 18, 1980, Ser. No. 179,142

Int. Cl.³ H04N 5/14

U.S. Cl. 358—166


15 Claims

1. In a television receiver of the type having means developing a full bandwidth luminance signal including a low pass component and first and second derivative components of said

low pass component, an improved luminance signal processing circuit comprising:

means responsive to said luminance signal for developing a first control voltage representing said low pass component and a second control voltage representing the combination of said low pass and second derivative components; amplifier means responsive to said first and second control voltages for developing first and second current mode signals representing, respectively, in phase and 180° out of phase combinations of said low pass and second derivative components;

peaking signal processor means selectively operable for



controlling the levels of only the second derivative components of said first and second current mode signals for developing corresponding third and fourth current mode signals respectively;

picture processor means selectively operable for simultaneously controlling the levels of both the second derivative and low pass components of at least one of said third and fourth current mode signals for developing a corresponding output luminance signal; and

a single source of DC potential coupled only to said picture processor means for supplying the bias energy from which said first, second, third and fourth current mode signals are derived.

4,296,436

NOISE REDUCING SYSTEM

Masahiko Achiha, Iruma, Japan, assignor to Hitachi, Ltd. and Hitachi Denshi Kabushiki Kaisha, both of Tokyo, Japan


Filed Aug. 21, 1979, Ser. No. 68,527

Claims priority, application Japan, Aug. 21, 1978, 53-100951

Int. Cl.³ H04N 5/21

U.S. Cl. 358—167

5 Claims



1. A noise reducing system comprising first circuit means for detecting a variation of a picture from an input picture signal

and a past picture signal by mixing said signals with a selectively variable ratio; second circuit means for controlling the mixing ratio between the input picture signal and the past picture signal in response to an output signal of said first circuit means; and memory circuit means for delaying the output of said second circuit means a fixed time period to provide said past picture signal; said second means comprising movement detector circuit means for detecting displacement of the variation of the picture per frame from the output of said memory circuit means and the output of said first circuit means, and movement compensator circuit means coupled between said memory circuit means and said first circuit means and controlled by an output of said movement detector circuit means for generating and providing to the first circuit means a past picture signal which corresponds to the same area as the input picture signal.

4,296,437

CLAMPING CIRCUIT FOR A VIDEO SIGNAL

Martinus F. A. M. Geurts, Nijmegen, Netherlands, assignor to U.S. Philips Corporation, New York, N.Y.


Filed Jan. 21, 1980, Ser. No. 113,885

Claims priority, application Netherlands, Mar. 5, 1979, 7901722

Int. Cl.³ H04N 5/16

U.S. Cl. 358—173

5 Claims



1. A clamping circuit for a video signal comprising an input and an output, a differential amplifier having a first and a second input and an output, a capacitor connected between said clamping circuit input and said differential amplifier first input, a capacitor charging and discharging circuit connected to said capacitor at said differential amplifier first input and to said differential amplifier output, a diode coupled between said differential amplifier output and said output of said clamping circuit, means for coupling said clamping circuit output to said differential amplifier second input, means for supplying a reference voltage, and a resistor for coupling said reference voltage to said differential amplifier second input.

4,296,438

PROJECTION AND SCANNING SYSTEM FOR PRODUCING VIDEO SIGNALS FROM MOTION PICTURE FILM AND CONTROL SYSTEM USED THEREIN

Otto Stemme; Wolfgang Ruf, both of Munich, and Eduard Wagenonner, Aschheim, all of Fed. Rep. of Germany, assignors to AGFA-Gevaert Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Mar. 31, 1980, Ser. No. 136,114

Claims priority, application Fed. Rep. of Germany, Mar. 30, 1979, 2912667

Int. Cl.³ H04N 3/36


U.S. Cl. 358—214

15 Claims

1. A projection and scanning system designed to repeatedly project images from a motion picture film or from a still picture film onto a fixed horizontal line along which a charge-cou-

pled image sensor may be placed, in order to produce a flickerless video signal from a motion or still picture, comprising:

- a projector which can be loaded with a motion or still picture film and which operates in a manner that images on the film are projected from the projector;
- a movable mirror upon which images projected from the projector are directed;
- a scanner connected to the mirror and cooperating with the projector in a manner that the mirror is moved to reflect successive horizontal lines of images projected by the projector onto a fixed horizontal line in sequence;
- a synchronizer synchronizing operation of the scanner or the mirror movement with the movement of the motion picture film or with the position of each image of the motion



or still picture film being projected in still projection, so that the sequence runs in synchronism from a top horizontal line of each image being moved or unmoved during projection by the projector to a bottom horizontal line of each image projected by the projector;

- a phase detecting element located in the plane of the charge-coupled image sensor in a fixed relationship which operates in a manner that the projector projects a phase signal from a phase mark of each image onto the phase detecting element; and

- a phase detecting circuit being connected with said phase detecting element in which a phase error signal is produced when the phase of the vertical sync pulses of the video picture differs from the phase of the scanned moved or unmoved picture of the motion or still picture film.


4,296,439

DIGITAL SIGNAL CONTROL SYSTEM IN A FACSIMILE COMMUNICATION

Hiroichi Teramura, Tokyo; Yasuhiro Yamazaki, Hiratsuka; Yasushi Wakahara, Tokyo; Naohiko Hattori, Tokyo; Seichi Yamamoto, Tokyo, and Kouzo Nakao, Hoya, all of Japan, assignors to Kokusai Denshin Denwa Co., Ltd., Tokyo, Japan Continuation-in-part of Ser. No. 917,163, Jun. 20, 1978, abandoned. This application May 15, 1980, Ser. No. 150,100 Claims priority, application Japan, Jun. 20, 1977, 52-71995 Int. Cl.³ H04N 7/12

U.S. Cl. 358—257

5 Claims



1. A method for controlling a facsimile system characterized

in that the scanning lines of a picture signal are encoded so that (k) number of continuous scanning lines are encoded by a relative address encoding system and the next one scanning line is encoded by run length encoding system and that sequence is repeated, a pair of synchronization codes are defined for each encoding system, and each synchronization code is positioned at the head of each scanning line of a picture signal, each of the synchronization codes have m_1 and m_2 number of continuous 0's inserted between a pair of 1's, a facsimile transmission station interpolates "1" for each series of $(\text{MIN}(m_1) - 1)$ number of continuous 0's of the picture signal in order to distinguish the picture signal from synchronization codes where $\text{MIN}(m_i)$ is the minimum value among m_i and i is 1 or 2, and a receiving station eliminates the interpolated "1" to provide a clean output, wherein the value of (k) is switched according to the instantaneous quality of a communication line so that the value (k) when said quality is good is larger than that when said quality is bad.

4,296,440

START OF MESSAGE GENERATOR FOR A FACSIMILE SYSTEM


Bernard Rosenheck, Dix Hills, N.Y., assignor to Litton Systems, Inc., Melville, N.Y.

Filed Dec. 20, 1976, Ser. No. 752,757

Int. Cl.³ H04M 1/36

U.S. Cl. 358—257

2 Claims



1. A start of message generator including means for providing a substantial immunity to transmission line noise for a facsimile system comprising

means for selecting a specific mode of operation from any of a plurality of available modes, each of said modes having a discrete code,

means for encoding the selected mode with its respective code,

synchronizing word generator means for generating a start of message synchronizing word,

clock generator means for generating a selected number of clocks corresponding to the encoded selected mode,

sequencer means including

means for enabling said synchronizing word generator

means for generating the start of message synchronizing word,

means for enabling said clock generator means immediately after said start of message synchronizing word has been generated for generating the selected number of clocks corresponding to the encoded selected mode,

means for enabling said synchronizing word generator means immediately after said selected number of clocks has been generated by said clock generator means for generating a second start of message synchronizing word, and

start of message decoder means including

start of message synchronizing word detector means for detecting the first and second start of message synchronizing words,

means for counting clocks,

means for enabling said counting means during the interval between the first and second start of message synchronizing words, and

means for decoding said number of counted clocks into one of said available modes.

4,296,441

PHOTOELECTRIC SCANNING APPARATUS


Fumihito Ogasawara, Tokyo, Japan, assignor to Ricoh Company, Ltd., Tokyo, Japan

Filed Dec. 3, 1979, Ser. No. 99,787

Claims priority, application Japan, Dec. 14, 1978, 53-153753 Int. Cl.³ H04N 1/10

U.S. Cl. 358—293

4 Claims and



1. A photoelectric scanning apparatus including a charge accumulation type photosensor array having a plurality of photosensor elements arranged in a row, the array being reciprocated for scanning perpendicular to the row, characterized by comprising:

pulse generator means for producing timing pulses in response to incremental movements of the array, the array producing data signals from outputs of all of the elements in response to each timing pulse;

sensor means for producing an enable signal when the array is within an effective scan area in which periods of timing pulses are constant; and

gate means for enabling transmission of the data signals only in response to the enable signal.

4,296,442

ON-BOARD ANALOG REPRODUCER UNIT FOR OCEAN-BOTTOM SEISMOMETER


Edgar A. Bowden, Arlington, Tex., assignor to Mobil Oil Corporation, New York, N.Y.

Filed Apr. 14, 1980, Ser. No. 140,354

Int. Cl.³ G11B 5/00

U.S. Cl. 360—6

8 Claims



1. In a marine exploration seismic exploration system wherein an ocean bottom seismometer unit deployed on the ocean bottom records digitized seismograms on a magnetic medium which is retrieved so that the recorded seismograms can be analyzed, an analog reproducer unit for installation on the exploration vessel which retrieves said magnetic medium comprising:

a magnetic reproducer unit for reproducing said digitized seismograms recorded on said magnetic medium;

a digital memory for storing digital samples reproduced from said medium;

digital to analog converter means for converting said digital samples into an analog signal;

an analog reproduction device for displaying said analog signal so that an operator can monitor said seismograms;

means for producing strobe pulses indicating the time of occurrence of the recording of a digital sample on said medium;

a discriminator for checking the repetition rate of said strobe pulses to discriminate valid strobe pulses from noise;

gating means responsive to said discriminator and to said strobe pulses for storing said digital samples in said memory only when a valid detection of strobe pulses is obtained.

4,296,443

MAGNETIC HEAD TRACKING CONTROL SYSTEM


Hitoshi Sakamoto, Zama, and Yoshiaki Wakisaka, Atsugi, both of Japan, assignors to Sony Corporation, Tokyo, Japan

Filed Feb. 23, 1979, Ser. No. 14,764

Claims priority, application Japan, Feb. 23, 1978, 53-20332 Int. Cl.³ H04N 5/78

U.S. Cl. 360—10

62 Claims



1. An apparatus for reproducing information signals recorded in successive parallel tracks on a record medium, with each of said tracks further containing a positional signal at a predetermined position therealong, comprising:

transducer means movable along each said track for reproducing the information and positional signals recorded therein;

transducer deflecting means mounting said transducer means and being operative in response to the reception of an electrical drive signal for deflecting said transducer means in a direction which is transverse in respect to the direction along each of said tracks;

means separating said positional signals from the signals reproduced by said transducer means;

means receiving the separated positional signals for detecting a time base error of said positional signal reproduced from each of said tracks; and

control circuit means for providing said electrical drive signal and including means for varying the latter in accordance with the detected time base error so as to control the deflection of said transducer means in said transverse direction at least in accordance with the detected time base error.

4,296,444


**INDUCTIVE SIGNAL TRANSDUCER SUPPLY CIRCUIT
PARTICULARLY FOR VIDEO RECORDING USE**

Josef Sochor, Darmstadt, Fed. Rep. of Germany, assignor to Robert Bosch GmbH, Stuttgart, Fed. Rep. of Germany
Continuation-in-part of Ser. No. 929,938, Aug. 1, 1978, abandoned. This application Feb. 1, 1980, Ser. No. 117,432
Claims priority, application Fed. Rep. of Germany, Aug. 6, 1977; 2735498

Int. Cl.³ G11B 5/45, 5/02

U.S. Cl. 360—65

7 Claims



1. Inductive signal transducer supply circuit, particularly for video recording use, to supply signals of essentially square wave pulse form to an inductive transducer to effect a recording in essentially square wave form with minimum wave shape degradation, as the frequency of applied pulse signals and hence the wave length thereof varies, said circuit comprising the combination of

- a frequency-dependent compensating network (4) connected in advance of the inductive transducer (5), emphasizing high frequency components of the signal;
- a current supply circuit (11, 12, 13; 41) supplying current to the compensating network in accordance with the applied signals;
- and a current amplifier (6; 19-29) connected between the compensation network (4) and the inductive transducer (5) and supplying energizing current to said transducer;
- with
- a connecting cable (33) between the output of the amplifier (6; 19-29) and the input to the transducer (5), said cable having a length which is substantially less than the minimum wave length of the supply signals being applied to the transducer, and presenting essentially only capacitive impedance;
- and wherein the compensating network has a frequency component-output signal transfer characteristic which is the inverse of a series network comprising the amplifier and the connecting cable and the transducer.

4,296,445

PHASE SENSOR

Lester F. Schowe, Jr., Morrison, Colo., assignor to Honeywell, Inc., Minneapolis, Minn.

Filed Apr. 11, 1980, Ser. No. 139,257

Int. Cl.³ G11B 5/45, 5/09


U.S. Cl. 360—65

8 Claims

1. In a magnetic recording/playback system, a method of detecting phase shift errors in the playback portion of said system, said method comprising:

- recording on a magnetic tape a square wave signal having a frequency of one-third of the bandedge frequency of the system;
- playing back the recorded signal through said playback portion to produce a resultant signal having a waveform representing the first and third harmonics of said recorded signal, said waveform having a first and second peak in each positive half cycle;
- extracting a time-averaged sample of the amplitude of each of said first and second peaks;

comparing the magnitude of the two time-averaged signals; and



producing a difference signal commensurate with and representative of said phase shift error.

4,296,446

MOTOR SPEED CONTROL CIRCUIT


George S. Zorbalas, Cherry Hill, N.J., assignor to RCA Corporation, New York, N.Y.

Filed Nov. 15, 1979, Ser. No. 94,690

Int. Cl.³ G11B 15/46

U.S. Cl. 360—73

6 Claims



1. A circuit for controlling the speed of a motor, said circuit comprising:

- a speed synthesizer having first input means for receiving a digital speed command signal, a second input means, and an output means for supplying a variable speed control signal;
- a means for supplying a reference signal to said second input means;
- a motor drive circuit having an input means for receiving said variable speed control signal and adapted to be coupled to said motor for speed control thereof; and
- wherein said speed synthesizer comprises a frequency comparator having a first input coupled to said reference signal means, a second input, and an output;
- a filter coupled to said comparator output;
- a voltage controlled oscillator having a control input coupled to said filter and an output; and
- a programmable divider having an input coupled to said oscillator output, a control input comprising said synthesizer first input means for receiving said digital speed

command signal, and an output coupled to said frequency comparator second input.

4,296,447

MAGNETIC RECORDING AND REPRODUCTION

John A. Lewis, Southampton, England, assignor to Racal Recorders, Ltd., Bracknell, England


Filed Dec. 11, 1979, Ser. No. 102,540

Claims priority, application United Kingdom, Dec. 11, 1978, 47983/78

Int. Cl.³ G11B 5/30

U.S. Cl. 360—113

9 Claims



1. A system for reproducing signals stored magnetically on a magnetic storage medium, comprising

- a magneto-resistive member having a predetermined input/output characteristic curve relating changes in the magnetic field which is produced upon it by the stored signals, when it is mounted in juxtaposition to the magnetic storage medium, to the corresponding changes in its electrical resistance,

biasing means for alternately producing biasing magnetic fields acting in opposite directions but parallel to the magnetic field produced by the stored signals and thereby alternately biasing the magneto-resistive member to first and second predetermined operating points on its characteristic curve, whereby the magneto-resistive member produces a succession of first outputs which are dependent on the strength of the field produced by the stored signals in relation to the field represented by the first operating point and a succession of second outputs which alternate in time with the first outputs and are dependent on the strength of the field produced by the stored signals in relation to the field represented by the second operating point, and

output means for producing a composite output from the succession of first and second outputs, the first and second operating points being selected such that the composite output is more linearly related to the strength of the stored signals than are either the first or the second outputs taken alone.

4,296,448

RECORDING CARTRIDGE HAVING A FLAT SMOOTHING PLANE WITH A RAISED PORTION

Felix Garcia, Jr., Round Rock; Roger A. Hergert, Georgetown; Don C. Mann, Richardson, and Sheldon H. Brown, Garland, all of Tex., assignors to Texas Instruments Incorporated, Dallas, Tex.

Filed Jun. 4, 1979, Ser. No. 45,378

Int. Cl.³ G11B 5/82, 5/016, 17/32


U.S. Cl. 360—135

13 Claims

1. A cartridge comprising:

- (a) a sheet of flexible information storage media having first and second opposite major surfaces, at least one of said major surfaces for storing information thereon; and
- (b) a cartridge housing in the form of a rigid envelope having an internal chamber with first and second surfaces oppositely positioned, at least portions of said first and second surfaces being relatively flat, said media being retained within said chamber, said cartridge housing having:
 - (i) a first opening extending through a central region of

one of said first and second surfaces for providing access to said media to impart rotational motion thereto; (ii) a second opening extending through said first surface for receiving a magnetic head transducer for respectively reading and/or writing information on said media; and



(iii) said first surface including a raised portion having a curved surface in facing relationship with said media for causing said media to conform to the curvature of said curved surface as it passes over said raised portion, said second opening being substantially contained within said raised portion.

4,296,449

RELAY SWITCHING APPARATUS


Charles W. Eichelberger, Schenectady, N.Y., assignor to General Electric Company, Schenectady, N.Y.

Filed Aug. 27, 1979, Ser. No. 69,618

Int. Cl.³ H02H 3/033

U.S. Cl. 361—3

17 Claims



1. A switching circuit for selectively coupling a load to an A.C. power source, said switching circuit comprising:

- (a) a master relay including a master relay contact and a master relay coil;
- (b) a pilot relay including a pilot relay and a pilot relay coil, said master and pilot relay contacts being coupled in series with each other and being coupled between said load and said power source to cause said power source to be coupled to said load whenever both said master and pilot relay contacts are closed; and to cause said power source to be completely disconnected from said load whenever at least said pilot relay contact is open; said pilot relay contact being devoid of any additional conductive element thereacross;
- (c) a single commutating diode coupled in parallel only with said master relay contact; and

(d) timing and control circuit means for performing a switching operation in which:

- (1) said master relay contact is opened during a first half-cycle of the A.C. waveform of said power source during which said single commutating diode is forward-biased;
- (2) the state of said pilot relay contact is changed during a second half-cycle of said A.C. waveform, said second half-cycle being that half-cycle of said A.C. waveform immediately following said first half-cycle, and during which said single commutating diode is reverse-biased;
- (3) said master relay contact is closed during a third half-cycle of said A.C. waveform, said third half-cycle being that half-cycle of said A.C. waveform immediately following said second half-cycle.

4,296,450


DISCRIMINATING CIRCUIT BREAKER PROTECTION SYSTEM DIRECT CURRENT POWER DISTRIBUTION SYSTEMS

Derek A. Paice, Murrysville, and Alan B. Shimp, Monroeville, both of Pa., assignors to The United States of America as represented by the Secretary of the Interior, Washington, D.C.

Filed Oct. 5, 1979, Ser. No. 82,383
Int. Cl.³ H02H 3/17

U.S. Cl. 361—50

3 Claims



1. A discriminating circuit breaker system for the protection of an electrically grounded power distribution system having a power supply and a transmission line, said circuit breaker system comprising:

- an electrically controlled circuit breaker operable to be closed when energized and to open when de-energized, said breaker being connected between the power supply and the transmission line; and
- a control circuit for controlling the operation of the circuit breaker, said control circuit comprising in combination:
 - means for producing an electric energizing signal for the circuit breaker;
 - a pilot wire through which said energizing signal must flow to energize the circuit breaker, said wire being mounted adjacent the transmission line;
 - means for producing and superimposing an alternating current signal on the grounded transmission line at a location adjacent the power supply;
 - current detecting means for detecting the level of the superimposed signal and producing a control signal when the current level from said alternating current signal exceeds a predetermined maximum level, which level corresponds to the presence of an illegitimate load on the power distribution system;
 - voltage detector means for detecting the voltage level of the superimposed signal above ground potential and producing a control signal when the voltage level of said alternating current signal in the transmission line falls below a predetermined minimum level, said level corresponding to the presence of an illegitimate load on the power distribution system; and
 - switch means responsive to the control signals produced by

the voltage detecting means and current detecting means, said switch means being connected in series with the pilot wire whereby the circuit breaker may be opened by a control signal from the voltage or the current detecting means or by the cessation of current flow through the pilot wire.

4,296,451

ULTRA HIGH SPEED PROTECTIVE RELAY CIRCUIT

Stanley B. Wilkinson, Havertown, Pa., assignor to General Electric Company, Philadelphia, Pa.


Filed Dec. 31, 1979, Ser. No. 108,436

Claims priority, application United Kingdom, Oct. 11, 1979, 35313/79

Int. Cl.³ H02H 3/28

U.S. Cl. 361—80

18 Claims



1. In a protective relay for one or more transmission lines in a three-phase ac power system, the relay being of a phase comparator type and including phase coincidence detecting means responsive to at least two input signals supplied thereto, one input signal being an operating signal and a second input signal being a polarizing signal, and timer circuit means responsive to an output signal from said phase coincidence detecting means when the phase coincidence of the input signals is of a predetermined duration, an improvement wherein:

- a. said operating signal comprises that portion of a first difference signal which exceeds a predetermined threshold value, the first difference signal being related to the difference between (1) the product of a signal proportional to transmission line current and a replica impedance of the transmission line and (2) a signal proportional to transmission line voltage; and
- b. said polarizing signal comprises that portion of a second difference signal which exceeds a predetermined threshold value, the second difference signal being related to the difference between (1) a signal proportional to a voltage representative of the transmission line voltage and (2) the product of the signal proportional to transmission line current and the replica impedance of the transmission line multiplied by a predetermined constant.

4,296,452

MULTIPHASE FAULT PROTECTION CIRCUITRY WITH VARIABLE FUNCTIONAL LEVEL DETECTION

Leif Eriksson, Sala, Sweden, and Salomon Liberman, Ra'anana, Israel, assignors to Asea Aktiebolag, Vasteras, Sweden

Continuation-in-part of Ser. No. 964,202, Nov. 28, 1978, abandoned. This application Jun. 1, 1979, Ser. No. 44,388

Claims priority, application Sweden, Nov. 28, 1977, 7713411

Int. Cl.³ H02H 7/26, 3/38

U.S. Cl. 361—82

11 Claims


1. Circuitry for generating tripping and blocking signals for the protection of electrical components in an electrical power supply network as a result of the occurrence of faults therein, comprising:

- means for generation of respective tripping signals and

blocking signals for each phase of the electrical power supply network in dependence on whether the fault lies ahead or behind the electrical component to be protected, respectively, in response to measurement of the voltage and current associated with transient waves generated by faults in each phase of the electrical power supply network;

detection means having a predetermined operating level, for determining the presence of a first tripping signal resulting

excess-pressure break-away structure, the combination of a hollow tubular electric conductor means mounted within the housing electrically connected to the capacitor and mechanically connected to the housing for the subsection of tension loads thereon in the presence of excessive pressure in the housing, said electrical conductor means having a localized cross-sectional reduction in material at a predetermined location which constitutes a rated break point, and reinforcing means at the break point to prevent accidental rupture of the break point except by said tension loads.



from the occurrence of a single phase fault and the presence of a second tripping signal resulting from the occurrence of a fault in another phase, and means for changing the operating level for detection of said second tripping signal upon detection of the first tripping signal; and means responsive to said detection means for generating respective tripping and blocking outputs for each phase of said electrical power supply network, whereby double or triple pole tripping is prevented unless the presence of said second tripping signal is detected.

4,296,453

WOUND ELECTRICAL CAPACITOR WITH EXCESSIVE PRESSURE PROTECTIVE DEVICE

Karl Aigle; Udo Hieber, both of Heidenheim; Wilhelm Huebscher, Heidenfingen; Hans H. Rheindorf, Herbrechtingen, and Rolf Wiedemann, Nattheim, all of Fed. Rep. of Germany, assignors to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany


Filed May 17, 1979, Ser. No. 39,877

Claims priority, application Fed. Rep. of Germany, Jun. 9, 1979, 2825377

Int. Cl.³ H01G 1/11

U.S. Cl. 361—275

7 Claims



1. In a wound electrical capacitor, particularly a power capacitor, which is enclosed in a housing provided with an

1. An enclosure-type circuit support structure to support electrical components of a circuit including resistive and reactive devices, the circuit support structure comprising:

- a base chassis structure and a retaining chassis structure joined together by interlocking apparatus which locks the two chassis structures together in order to secure the electrical components in place, the base chassis structure including a plurality of drop-in receptacles each adapted dimensionally for receiving a specific electrical component of the circuit to be supported including at least a receptacle for a reactive device, the electrical components of the circuit being inserted into the receptacles;
- the retaining chassis structure including retaining means for applying a constraining force to the electrical components in order to secure the electrical components into assigned drop-in receptacles; and
- the retaining means comprising at least a clamp nodule applying clamping pressure to at least a selected reactive device of said electrical components, the clamp nodule comprising a projecting member set in an aperture in the retaining chassis structure which is aligned with a drop-in receptacle in which the selected electrical component is situated, the projecting member being connected as a cantilever-type beam to a periphery of the aperture and including a protuberance at a free end of the projecting member, the protuberance applying clamping pressure to the selected electrical component to hold it in its drop-in receptacle.


4,296,455

SLOTTED HEAT SINKS FOR HIGH POWERED AIR COOLED MODULES

Edgar C. Leaycraft, Woodstock; Sevgin Oktay, Poughkeepsie, and Carl D. Ostergren, Montgomery, all of N.Y., assignors to International Business Machines Corporation, Armonk, N.Y.
Filed Nov. 23, 1979, Ser. No. 96,942
Int. Cl.³ H05K 7/20

U.S. Cl. 361—383

15 Claims



1. An air cooling system for high density integrated circuit modules comprising:
 - a module containing integrated circuit chips and having a heat conductive covering surface;
 - a plurality of hollow heat sinks, each having a top opening at one end and the opposite end attached to said covering surface and each having a side opening therein extending from said covering surface and extending toward said top opening of each said hollow heat sink; and
 - means for impingement air flow substantially parallel to each said hollow heat sink which causes air flow through said top openings of each of said hollow heat sinks and out of said side opening in each said hollow heat sink as well as between said plurality of heat sinks whereby the heat is removed from said hollow heat sinks.

4,296,456

ELECTRONIC PACKAGE FOR HIGH DENSITY INTEGRATED CIRCUITS


Gilbert R. Reid, Norristown, Pa., assignor to Burroughs Corporation, Detroit, Mich.

Filed Jun. 2, 1980, Ser. No. 155,533

Int. Cl.³ H05K 1/14

U.S. Cl. 361—403

7 Claims



1. An electronic package for an integrated circuit chip having a plurality of signal pads along its periphery comprising:
 - a base member and at least a first and a second circuit layer, said first circuit layer being mounted on said base member and said second circuit layer being mounted on said first circuit layer, each of said circuit layers being frame-like and having a central opening, a plurality of electrically conductive chip-connection tabs disposed on a planar surface of each of said circuit layers and situated adjacent the periphery of its central opening, respective pluralities of electrically conductive pin-mounting pads and metalized lines disposed on said planar surface of each of said circuit layers, each of said lines connecting a chip-connection tab to a pin-mounting pad on a common circuit layer; the dimensions of the central opening of said second circuit

layer being greater than those of the central opening of said first circuit layer, and the area of the planar surface of said second circuit layer being less than that of said first circuit layer, whereby the chip-mounting tabs and the pin-mounting pads of said first circuit layer remain uncovered in the presence of the mounted second circuit layer; a plurality of input/output pins affixed respectively to the plurality of pin-mounting pads on each of said circuit layers; the central openings of said circuit layers forming a well for receiving said chip, the latter being adapted to be mounted on said base member and to have said signal pads connected respectively to said chip-connection tabs on both said first and second circuit layers.

4,296,457

APPARATUS FOR ELECTRICALLY CONNECTING A PLURALITY OF CONTACTS

Günter Hahlganss, Kriftel, Fed. Rep. of Germany, assignor to VDO Adolf Schindling AG, Fed. Rep. of Germany


Filed Dec. 21, 1979, Ser. No. 106,082

Claims priority, application Fed. Rep. of Germany, Jan. 15, 1979, 2901416

Int. Cl.³ H05K 01/14

U.S. Cl. 361—413

8 Claims



1. Apparatus for electrically connecting a plurality of closely positioned contacts of a device, preferably a display device, with a plurality of spaced contacts of an electronic circuit controlling the device, comprising a plurality of flexible printed circuit boards each having a narrow mid-section and two outer end areas each of which is spaced from said mid-section and has a width greater than the width of said mid-section, and a plurality of conductor lines extending from said mid-section for connection with a portion of the closely positioned contacts of the device to said outer areas for connection with a portion of the spaced contacts of the electronic circuit, wherein the device has a width and a central axis passing transversely therethrough, said plurality of circuit boards including a first flexible printed circuit board having a configuration symmetrical about said axis, a second flexible printed circuit board having its mid-section disposed on one side of said axis and its end areas extending from its mid-section toward the opposite side of said axis, and a third flexible printed circuit board having its mid-section disposed on said opposite side of said axis and its end areas extending from its mid-section toward said one side of said axis, said end areas of said first, second and third flexible printed circuit boards each having the same width.

4,296,458

ELECTROLYTE CAPACITORS WITH IMPROVED ANODE-TO-LEAD CONNECTION

Leslie Smith, Towcester; William Tew, Stoke Bruene, and Jack Woolley, Haversham, all of England, assignors to Plessey Handel und Investments A.G., Zug, Switzerland

Filed Nov. 20, 1978, Ser. No. 961,919

Claims priority, application United Kingdom, Nov. 24, 1977, 48885/77

Int. Cl.³ H01G 9/00; B01J 17/00

U.S. Cl. 361—433

11 Claims



1. A wet electrolyte capacitor comprising:
 - a can made from non-solderable valve metal,
 - an annular shaped cathode disposed within said can,
 - an anode made from non-solderable valve metal mounted substantially concentrically within said annular shaped cathode and separated therefrom by an electrolyte, contained within said can surrounding the cathode, the can being a hollow construction initially open at one end for insertion of the cathode and the anode,
 - an anode lead, the anode being provided with a recess for reception of said anode lead,
 - a seal for hermetically sealing the open end of the can, the seal including means for connecting the anode lead through the seal in electrical isolation from the can, and
 - a further seal within said can comprising a bung which is tightly fitted to surround the anode lead, said further seal being positioned between the anode and said seal and preventing the electrolyte from contacting the seal at least during the sealing operation,
 - said anode lead comprising a continuous piece of metal extending without jointing from the anode to the outside of the seal.

4,296,459

LIGHT EMITTING ELECTRONIC JEWELRY


Frederick P. DeLuca, 3520 Jewel Dr., Ames, Iowa 50010

Filed Aug. 6, 1979, Ser. No. 64,036

Int. Cl.³ F21L 15/08

U.S. Cl. 362—104

6 Claims



1. A light emitting electronic earring comprising,
 - an earring post adapted for securement to a wearer's earlobe,
 - a light emitting diode operatively supported on said post,
 - a battery means, and

an electrical circuit, said light emitting diode and battery means being electrically connected in said circuit such that said light emitting diode is illuminated at times by said battery means, said electrical circuit comprising a mercury switch electrically connected between said light emitting diode and battery means so as to make and break the electrical connection therebetween in response to movements of the wearer's earlobe, a casing, said battery means and mercury switch being supported in said casing, said electrical circuit including elongated conductor chains electrically connecting said light emitting diode to said mercury switch, said casing being suspended from said post by said conductor chains.

4,296,460

LAMPS


William E. Minoprio, Blackburn, and Arthur K. Horsfield, Preston, both of England, assignors to Dorman Smith Traffic Products Limited, Southport, England

Division of Ser. No. 833,098, Sep. 14, 1977. This application Dec. 10, 1979, Ser. No. 101,588

Int. Cl.³ F21L 7/00

U.S. Cl. 362—200

8 Claims



1. A battery-powered lamp comprising a casing in the form of a box-like body part having a top and front and rear and side walls for housing at least one battery, at least the front wall having a depression which provides a generally planar depressed portion in which an opening is disposed; a light source supported in the casing; and a lens through which light from the light source can be transmitted, which lens has a peripheral rim which is a friction fit in said opening and has, on the peripheral rim, a plurality of ratchet-like teeth which are mutually spaced around the periphery of the lens and which make snap fits with and locate behind the material of the front wall bounding the opening to resist removal of the lens from its opening.

4,296,461

BATTERY PACKAGE WITH DC TO DC CONVERTER

Henry R. Mallory, Greenwich, Conn., and Steven J. Nichols, North Tarrytown, N.Y., assignors to Duracell International Inc., Bethel, Conn.

Filed Jan. 29, 1979, Ser. No. 7,456


Int. Cl.³ H02M 3/335; H01M 2/34

U.S. Cl. 363—22

10 Claims

1. A battery package comprising a casing having therein one cell of a type which is subject to damage by cell reversal, said cell having an anode comprising lithium, a DC to DC converter circuit electrically connected to said cell, and means for electrically connecting the output of said converter circuit to a load, said converter circuit comprising means to substantially prevent current flow through said converter circuit unless a load is connected to the output of said converter circuit, whereby said cell discharges only when the load is connected

to said converter circuit, said converter circuit being adapted to provide a voltage output substantially in excess of the volt-



age of the one cell in said package, and said converter circuit including means to electrically prevent recharging of the cell.

4,296,462

INVERTER CONTROLLER


George P. Gurr, Dunwoody, Ga., assignor to Sangamo Weston, Inc., Atlanta, Ga.

Filed Jul. 2, 1979, Ser. No. 54,024

Int. Cl.³ H02M 7/515

U.S. Cl. 363-96

25 Claims



1. An inverter controller for controlling the firing time and sequence of gated conduction controlled rectifiers in an inverter used for generating a pulse code signal for injection upon electrical transmission lines, which comprises:

- an address bus for providing address information;
- means responsive to functional commands indicative of the desired mode of operation of said inverter for providing a portion of said address information on said address bus;
- first memory means responsive to said address information on said address bus for generating next address information;
- first register means for receiving said next address information from said first memory means and for delivering the other portion of said address information to said address bus;
- second memory means responsive to said address information on said address bus for generating next gate control signals; and
- second register means for receiving said next gate control signals from said second memory means for providing signals for the gate controlled rectifiers of said inverter.

4,296,463

SELECT SYSTEM FOR PRIORITY INTERFACE CIRCUITRY

Gerard Dalbousiere, La Colle, Loup, France, and Wilburn D. Draper, Raleigh, N.C., assignors to International Business Machines Corp., Armonk, N.Y.


Filed May 17, 1979, Ser. No. 39,714

Claims priority, application France, Jun. 7, 1978, 78 17709

Int. Cl.³ G06F 3/04

U.S. Cl. 364-200

5 Claims



1. A selection system for making the selection amongst interface circuits, each interface circuit interfacing a plurality of units making service requests at different priority levels, and a central unit, said selection being carried out according to said priorities, and said system being characterized in that it includes:

- a central unit bus for connecting the interface circuits to the central unit,
- a priority bus having an upline and down line extent and carrying priority level information,
- a group of n interface circuits connected along said priority bus and each including a preselection means comprising: a priority request register for registering the highest priority level received from the pending requests of the units connected to the interface circuit,
- an adapter priority register connected to said priority request register for receiving the contents of the said priority request register at a predetermined time,
- driving means connected to the priority bus for placing on the priority bus the priority level information from the adapter priority register,
- receiving means connected to the priority bus and to the driving means and providing on its output the priority level information corresponding to the service requests pending in the interface circuits upline of the said interface circuit,
- comparison means receiving on its first inputs the priority registered in the adapter priority register and on its second inputs the priority level provided by said receiving means and providing on its output a logic level "1" when the priority registered in the adapter priority register for that interface has a level higher than or equal to the priority level of the request having the highest priority among the requests pending in said interface circuits upline of the considered interface,
- a serial select line interconnecting the n interface circuits of the group through one input connection and one output connection provided at each interface circuit,
- means at each said interface circuit for propagating a serial selection information through the output connection of the serial select line, said means comprising an OR circuit having two inputs one receiving the logic level of the serial select line at the input connection and the other one receiving the logic level provided at the output of the comparison means and providing on its output the serial selection information to the output connection,
- a select latch for enabling connection of said interface circuit to said central unit bus, and
- logic means at each of the said interface circuits responsive to the results provided by the comparison means, the

condition of the serial select line input and the presence of a select order from the central unit for setting the select latch of only one of the interface circuits and resetting the select latches of the other interface circuits whereby the said one interface circuit which has its select latch set is enabled for communication with the central unit over said central unit bus.

4,296,464

PROCESS CONTROL SYSTEM WITH LOCAL MICROPROCESSOR CONTROL MEANS


Rodney G. Woods, Glendale; Charles J. Clarke, Jr., and Robert C. Sodergren, both of Phoenix, all of Ariz., assignors to Honeywell Inc., Minneapolis, Minn.

Filed Mar. 3, 1977, Ser. No. 773,913

Int. Cl.³ G06F 9/22

U.S. Cl. 364-200

18 Claims



- 1. A process control computer system comprising: a central processor unit as a primary controller;
- said central processor including a main computer memory and a control unit;
- a two conductor communication bus;
- an interface control unit including direct memory access with respect to said main computer memory, said interface control unit being interconnected between said central processor unit and said communication bus;
- a plurality of process data point devices including input and output devices; and
- a process interface unit connected to interface between said process data point devices and said communication bus;
- said process interface unit including a microprocessor unit, local memory means operative under the control of said microprocessor unit, means further controlled by said microprocessor unit for continuously gathering data from said input data point devices, means including said microprocessor unit for manipulating said gathered data in accordance with selected instructions, means under the control of said microprocessor unit for storing said manipulated data in said local memory means, said manipulated data being compared within said process interface unit with predetermined criteria stored in said local memory means to detect extra-criteria data, means for storing said extra-criteria data in said local memory means, means including said microprocessor unit for transmitting said stored extra-criteria data by way of said communication bus and said direct memory access to said central process unit while retaining said manipulated data in said local memory, said process interface unit including means for receiving from said central processor unit, by way of said communication bus, output control signals, and means including said microprocessor unit for transmitting said output control signals to designated output data point devices.

4,296,465

DATA MOVER


Nicholas S. Lemak, Phoenix, Ariz., assignor to Honeywell Information Systems Inc., Phoenix, Ariz.

Filed Nov. 3, 1977, Ser. No. 848,172

Int. Cl.³ G06F 1/00

U.S. Cl. 364-200

18 Claims



- 1. A data mover comprising: a data in bus;
- a data out bus;
- a control bus;
- data register means connected to the data in bus for storing at least one data word;
- control register means connected to the data in bus for storing at least one control word;
- means connected to the data out bus for issuing memory read commands and memory write commands; and
- control means connected to the control bus, to the data register means, and to the means for issuing memory commands for causing the means for issuing memory commands to issue a write command after issuing a read command on the data out bus only if a data word is stored in said data register means in response to a previously issued read command and to issue the data words stored in the data register means on the data out bus immediately following the issuing of write command.

4,296,466

DATA PROCESSING SYSTEM INCLUDING A SEPARATE INPUT/OUTPUT PROCESSOR WITH MICRO-INTERRUPT REQUEST APPARATUS

James M. Guyer, Marlboro, and Joseph T. West, Foxborough, both of Mass., assignors to Data General Corporation, Westboro, Mass.

Filed Jan. 23, 1978, Ser. No. 871,689

Int. Cl.³ G06F 13/00, 15/16

U.S. Cl. 364-200

13 Claims

- 1. A data processing system comprising a host processor having a microprogram control store, a host processor memory, and a host memory management unit, the contents of which permit the conversion of logical addresses received by said host processor into physical addresses for said host memory, and further comprising: an input/output processor;
- input/output bus means for providing communication between said input/output processor and said host processor, said host processor being capable of generating a specified coded signal in response to any interrupt request from said input/output processor;
- said input/output processor including means for generating a micro-interrupt request signal for said host processor to request a re-allocation of a selected position of the contents of said memory management unit; and
- micro-interrupt identifying means responsive to said specified coded signal received from said host processor and to said micro-interrupt request signal of said input/output processor for providing a signal to said host processor for identifying said interrupt request as one requiring the re-allocation of said selected portion of the contents of said memory management unit, whereby said host proces-

- (d) control means coupled to said instruction register and responsive to the contents thereof for providing first control signals to cause transfer of said starting addresses from said memory means at memory locations designated by said first memory addressing means to said second addressing means and for causing said second memory addressing means to sequentially access said graphics information in synchronism with said image forming beam;
- (e) transfer means coupled to said memory means and responsive to the contents of said instruction register for receiving and converting said display graphics information to video data of a format defined by said operation code, said transfer means including first buffer storage means for containing information indicative of a plurality of second display characteristics of said graphics information and selection means responsive to said video data for selecting a predetermined one of said plurality of second display characteristics, said buffer storage means being coupled to and addressable by said microprocessor for the transfer thereto of said display characteristic information.

4,296,477


REGISTER DEVICE FOR TRANSMISSION OF DATA HAVING TWO DATA RANKS ONE OF WHICH RECEIVES DATA ONLY WHEN THE OTHER IS FULL
Maurice L. Hutson, Vadnais Heights, Minn., assignor to Control Data Corporation, Minneapolis, Minn.

Filed Nov. 19, 1979, Ser. No. 95,698

Int. Cl.³ G06F 13/00; G11C 19/00

U.S. Cl. 364-900

31 Claims



6. A data transmission system consisting of a plurality of identical ripple register devices adapted to be connected serially between a sending device and a receiving device in which each of said ripple register devices has a data "in" port and a data "out" port, a Hold "in" port connected to a succeeding device and a Hold "out" port connected with a preceding device and a Full "out" port connected with a succeeding device and a Full "in" port connected with a preceding device wherein said Full "out" port transmits information that the particular ripple register device is prepared to transmit data and wherein said Hold "out" port transmits information that the particular ripple register device cannot receive data, wherein each particular ripple register device has at least two data registers so that data may be both received and transmitted simultaneously in response to independent signals at the Full "in" and Hold "in" ports.

4,296,478

READOUT OF ELECTROSTATICALLY STORED INFORMATION

Helmut G. Kless, Niedersteinmaur, and Bruno K. Binggeli, Arni, both of Switzerland, assignors to RCA Corporation, New York, N.Y.

Filed Oct. 12, 1979, Ser. No. 84,394


Int. Cl.³ G11C 11/23

U.S. Cl. 365-112

6 Claims

1. A method of producing an electrical signal representing a charge pattern on an insulating dielectric film, without destroying the charge pattern, comprising placing a transparent electrode on the free top surface of said dielectric film, placing the insulating dielectric film having the charge pat-

tern in close contact with the free surface of an uncharged photoconductor having a back electrode connected through a signal output impedance to a point of reference potential, scanning said photoconductor through said transparent



electrode and said dielectric film with a flying spot of light to produce a video electrical signal across said impedance during said scanning, and removing the dielectric film from the photoconductor, whereby the original charge pattern on the dielectric film is retained.

4,296,479

METHOD FOR OPTICAL RECORDING IN PHOTO-DICHOIC GLASS SURFACES


Che-Kuang Wu, Horseheads, N.Y., assignor to Corning Glass Works, Corning, N.Y.

Filed Nov. 15, 1979, Ser. No. 94,364

Int. Cl.³ G11C 13/04

U.S. Cl. 365-119

6 Claims



1. In a method for writing and erasing images in the surface of a photosensitive glass which demonstrates alterable photoanisotropic effects wherein an image is written into the surface of said glass through exposure thereof to a beam of linearly-polarized red light having a wavelength between about 600-650 nm and said image is erased from the surface of said glass through exposure thereof to a beam of linearly-polarized red light having a wavelength between about 600-650 nm and having a different orientation of polarization, the improvement comprising erasing said image with a beam of linearly-polarized red light having a wavelength between about 600-650 nm but with about a 45° change in the direction of polarization from said writing beam.

4,296,480

REFRESH COUNTER

Sargent S. Eaton, Jr., and Paul R. Schroeder, both of Colorado Springs, Colo., assignors to Mostek Corporation, Carrollton, Tex.

Filed Aug. 13, 1979, Ser. No. 66,149

Int. Cl.³ G11C 11/40


U.S. Cl. 365-222

16 Claims

1. An n-bit address refresh counter comprising: an address buffer for each address bit adapted to receive an address buffer strobe for inverting a pair of complementary input signals and placing the inverted signals onto a pair of output terminals;

a refresh address storage circuit for each address buffer connected to the address buffers for storing and providing the pair of complementary input signals; and n-1 decoders for n-1 address buffers wherein the ith

M-109



decoder receives a transfer clock signal and at least i address bits, where $i=1, 2, \dots, N-1$ and controls the transfer of the inverted signals on the pair of output terminals of the ith address buffer to an input of its corresponding refresh storage circuit.

4,296,481

STREAMER BULKHEAD


Benjamin F. L. Weiss, Houston, Tex., assignor to Exploration Company, Houston, Tex.

Filed Dec. 17, 1979, Ser. No. 104,168

Int. Cl.³ G01V 1/38

U.S. Cl. 367-20

9 Claims



5. Bulkhead for a streamer section comprising a two sector annulus adapted to receive an electrical conductor bundle adapted to extend therethrough, said annulus including a major sector of greater than 180 degrees arcuate extent and a correlative minor sector of less than 180 degrees arcuate extent, said annulus having an annular groove in its outer periphery, said annular groove being adapted to receive a girth cinch to hold said sections together, said annulus having a plurality of radial slots in its outer periphery adapted to receive tension lines adapted to extend therethrough, each sector having planar sides disposed at an angle to each other, said planar sides of one sector being engaged with the adjacent planar sides of the other sector.

4,296,482

PARAMETRIC ARRAY DOPPLER SONAR APPARATUS
Jacob A. Kritz, Westbury, N.Y., assignor to Sperry Corporation, New York, N.Y.

Filed Mar. 24, 1980, Ser. No. 133,158


Int. Cl.³ G01S 15/60

U.S. Cl. 367-91

12 Claims

1. Parametric array Doppler sonar apparatus comprising a plurality of piston-type transducers, each being positioned to launch and receive acoustic energy along a different specified axis, means to energize each transducer during specified time

intervals with a signal comprising a combination of first and second primary excitation frequencies, a hybrid acoustic lens having a central disk shaped portion and an annular ray-converging portion surrounding said central portion, each of said transducers having a diameter sufficiently large to launch a substantially collimated acoustic beam along



the axis of that transducer and being oriented to direct the collimated beam through the central portion of said lens, each of said transducers being further positioned within the focal region of the converging portion of said lens so as to intercept substantially all of the acoustic energy reflected from a remote target and passing through the lens along the axis of that transducer.

4,296,483

METHOD AND MEANS FOR MEASURING GEOPHONE PARAMETERS



Harry K. Haill, Houston, Tex., assignor to Litton Resources Systems, Inc., Houston, Tex.

Filed Jun. 30, 1980, Ser. No. 164,622

Int. Cl.³ G01V 13/00

U.S. Cl. 367-13

8 Claims



1. A device for substantially simultaneously testing the respective active elements of a plurality of electrically interconnected geophones that generate a signal output in response to a mechanical input and that will generate a mechanical output in response to a signal input, comprising: means for applying a signal input in series to said active elements; means for detecting the resultant mechanical force outputs of said geophones; and means for sequentially determining selected characteristics of the individual active elements from the detected mechanical force outputs.

4,296,484

DATA DISPLAY SYSTEM

Terry A. Miller, Bartlesville, Okla., assignor to Phillips Petroleum Company, Bartlesville, Okla.

Filed Oct. 30, 1978, Ser. No. 955,842

Int. Cl.³ G01V 1/22, 1/34

U.S. Cl. 367—71

23 Claims



19. Apparatus comprising:
a cathode ray tube screen;
means for supplying a sample of data from each of a plurality of data channels to said cathode ray tube screen to thereby display at least one sample of data from each of said plurality of data channels, on said cathode ray tube screen, in such a manner that all samples of data displayed on said cathode ray tube screen at any one time are displayed in an alternating sequence in a horizontal pattern across said cathode ray tube screen with no sample of data being displayed directly above or below another sample of data and in such a manner that each particular sample of data is displayed with respect to the data channel from which that particular sample of data was provided; and
means for controlling the display of data on said cathode ray tube screen so as to spread the display of said at least one sample of data from each of said plurality of data channels across substantially the entire screen of said cathode ray tube.

4,296,486

SHIELDED ELECTROMAGNETIC ACOUSTIC TRANSDUCERS


Carmino F. Vasile, Huntington, N.Y., assignor to Rockwell International Corporation, El Segundo, Calif.

Filed Jan. 24, 1980, Ser. No. 114,862

Int. Cl.³ H04R 15/00

U.S. Cl. 367—140

13 Claims



1. An electromagnetic acoustic transducer for use near a surface of an electrically conductive object, comprising:
a source of magnetic flux for establishing a static magnetic field in said object;
an electrical conductor disposed between said source of magnetic flux and said surface and proximate to said surface for conducting an alternating current in said static magnetic field; and
a thin, electrically conductive, nonmagnetic shield disposed between said source of magnetic flux and said conductor.

4,296,487

PRESSURE SENSITIVE LINE TRANSDUCER


Milton Green, New London, Conn., assignor to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Oct. 22, 1979, Ser. No. 87,285

Int. Cl.³ G01V 1/16, 1/38

U.S. Cl. 367—169

4 Claims



1. A line transducer for sensing pressure variations due to acoustic waves generated by an acoustic source comprising:
an elongated cable including a pressure sensitive electrical core element generating electrical signals in response to said acoustic waves of said acoustic source, said electrical core element of said elongated cable is an electrically conducting rubber that is insulated for preventing flow of electric current between said electrically conducting core element and a medium around said line transducer;
means for isolating said electrical signals from ambient noise including a solenoid for shorting an internal cladding of said elongated cable and an external cladding thereof; and
means for processing said electrical signals.

4,296,485

TILT ALARM IN A SEISMIC EXPLORATION SYSTEM


Lawrence G. Clemens, Bartlesville, Okla., assignor to Phillips Petroleum Company, Bartlesville, Okla.

Filed Oct. 30, 1978, Ser. No. 955,904

Int. Cl.³ G01V 1/22

U.S. Cl. 367—77

8 Claims



5. A method for indicating that a remote geophone monitoring means has been tilted with respect to a desired position of said remote geophone monitoring means comprising the steps of:
sensing that said remote geophone monitoring means has been tilted with respect to a desired position of said remote geophone monitoring means and generating an enabling signal when said remote geophone monitoring means is tilted;
generating a tilt alarm signal in response to said enabling signal; and
automatically transmitting said tilt alarm signal from said remote geophone monitoring means to a central control station to thereby provide an indication that said remote geophone monitoring means has been tilted.

4,296,488

WATCH MOVEMENT CONSTRUCTION

Yasuaki Nakayama, Hanno, Japan, assignor to Citizen Watch Company Limited, Tokyo, Japan


Filed Jun. 22, 1978, Ser. No. 918,010

Claims priority, application Japan, Jun. 28, 1977, 52/77029; Nov. 24, 1977, 52/141033; Dec. 21, 1977, 52/153715

Int. Cl.³ G04B 19/04; G04C 23/02

U.S. Cl. 368—80

34 Claims



1. A movement construction for an electronic wristwatch driven by a stepping motor powered by a battery, comprising:
a base plate having a first cutout formed in close proximity to one portion of an outer periphery of said base plate to accommodate therein said battery, and a second cutout formed in close proximity to another portion of the outer periphery of said base plate;
a disk type driving coil forming part of said stepping motor and disposed in said second cutout of said base plate, said disk type driving coil having its upper and lower end surfaces substantially aligned on the same plane as upper and lower surfaces of said base plate;
a wheel train mounted on said base plate in an area between said battery and said driving coil in a manner to be concentric with said driving coil; and
a circuit board having an IC chip and a quartz crystal vibrator mounted in horizontal spaces, respectively, and supported by said base plate outside an area occupied by said driving coil, said battery and said wheel train which are aligned in a single plane.

4,296,489

ELECTRONIC TIMEPIECE

Hiromitsu Mitsui, Suwa, Japan, assignor to Kabushiki Kaisha Suwa Seikosha, Tokyo, Japan

Continuation of Ser. No. 678,339, Apr. 19, 1976, abandoned.


This application Apr. 25, 1979, Ser. No. 33,277

Claims priority, application Japan, Apr. 17, 1975, 50-46728

Int. Cl.³ G04B 1/00

U.S. Cl. 368—205

1 Claim



1. In an electronic timepiece including timekeeping circuitry having a solar battery for producing charging current in response to light being incident thereon, the improvement comprising said solar battery being formed of a plurality of solar cells, said solar cells being disposed on a surface of said timepiece, a circuit substrate including leads formed thereon for coupling said solar cells to said timepiece circuitry, and a

conductive adhesive layer for physically securing said solar cells to said circuit substrate and for electrically coupling each of said solar cells to the leads on said circuit substrate, said conductive adhesive layer being conductive in a first predetermined direction perpendicular to the opposed surface thereof in contact with said solar cells and as an electrical insulator in the direction parallel to said opposed surface thereof.

4,296,490

CRYSTAL OSCILLATION-TYPE ELECTRONIC TIMEPIECE

Yasuhiko Nishikubo, Iruma, Japan, assignor to Citizen Watch Co. Ltd., Tokyo, Japan


Continuation-in-part of Ser. No. 757,025, Jan. 5, 1977, abandoned. This application Feb. 23, 1979, Ser. No. 14,641

Claims priority, application Japan, Jan. 14, 1976, 51-2073; Oct. 21, 1976, 51-140664

Int. Cl.³ G04C 19/00, 3/00, 5/00; H03B 5/30

U.S. Cl. 368—87

11 Claims



1. A crystal oscillation-type electronic timepiece comprising an oscillator having a crystal oscillator with an input and an output as a time base, means for dividing the frequency of the oscillator, display driving means connected to said frequency dividing means, time display means connected to said display driving means, said oscillator having a complementary metal oxide semiconductor logic circuit having an inverter with a gated N-channel transistor and a gated P-channel transistor, said gated N-channel transistor having a channel with a width/length ratio of less than one, said gated P-channel transistor having a channel with a width/length ratio of less than two, an input capacitor with a given capacitance connected to the input of the crystal oscillator and an output capacitor having a capacitance less than the given capacitance of said input capacitor connected to the output of the crystal oscillator.

4,296,491

INFORMATION CARRIER HAVING INTER-TRACK IDENTIFICATION CODE INFORMATION

Jonathan A. Jerome, Palo Alto, Calif., assignor to Atlantic Richfield Company, Los Angeles, Calif.

Filed Jul. 30, 1979, Ser. No. 61,794

Int. Cl.³ G11B 7/00

U.S. Cl. 369—59

8 Claims



1. Information-containing apparatus comprising:
(A) a substrate;
(B) a recording medium deposited on said substrate;
(C) a plurality of discrete signal data-containing tracks recorded in said medium;
(D) a discrete address code representative of each of said data-containing tracks recorded at a preselected position

in said medium and in line with said data-containing track with which the discrete address code is associated, said address codes all appearing within a predetermined region in said medium; and

(E) an index code recorded in said medium and disposed in a direction laterally of said data-containing tracks and between adjacent address codes, said index code being representative of the location on said medium at which it is recorded.

4,296,492

CONTINUITY VERIFICATION ARRANGEMENT


Edward H. Hafer, Winfield, Ill., assignor to Bell Telephone Laboratories, Incorporated, Murray Hill, N.J.

Filed Dec. 26, 1979, Ser. No. 106,393

Int. Cl.³ H04J 3/12

U.S. Cl. 370-14

11 Claims



1. A continuity verification arrangement for verifying continuity of communication paths through a time division switching means comprising a first communication unit, a second communication unit, a time division switching means comprising means for generating communication path identity signals and means responsive to said communication path identity signals for completing a communication path between said first and said second communication units characterized in that said time division switching means further comprises means for transmitting to said first and said second communication units said communication path identity signals; said first communication unit comprises means responsive to said communication path identity signals for transmitting a unique character on said communication path; and said second communication unit comprises receive means for receiving from said communication path said unique character transmitted by said originating unit, and continuity indicating means for generating continuity signals when said unique character is received on said communication path.

4,296,493

METHOD OF AND ARRANGEMENT FOR REGENERATING START-STOP SIGNALS

Robert Bodart, and Jean P. A. R. J. Werts, both of Brussels, Belgium, assignors to U.S. Philips Corporation, New York, N.Y.

Filed Sep. 12, 1979, Ser. No. 75,049

Claims priority, application Netherlands, Sep. 13, 1978, 7809299


Int. Cl.³ H04L 5/24

U.S. Cl. 370-48

2 Claims

1. A method of regenerating start-stop signals having a stop polarity which is maintained for a certain period of time T after a start-stop transition, T being either greater than or equal to a minimum value, or greater than or equal to a minimum value and smaller than or equal to a maximum value, and of converting the regenerated signals into isochronous output signals, wherein the method includes taking signal samples of the start-stop signals at consecutive sampling instants by means of a regeneration process initiated by the start-stop transition,

consecutively storing said signal samples in a storage device and reading out the stored signal samples at isochronous instants for forming the isochronous output signals, characterized in that the method comprises taking the signal samples at



sampling instants having unequal time intervals between them such that the $(n+1)^{st}$ signal sample, wherein $n \geq 7$, is taken at more than 20-n msec. but less than 20-n+5 msec. after the start-stop transition.

4,296,494

ERROR CORRECTION AND DETECTION SYSTEMS

Sakou Ishikawa, Yutaka Watanabe, and Katsuro Wakai, all of Hadano, Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed Oct. 12, 1979, Ser. No. 84,452

Claims priority, application Japan, Feb. 7, 1979, 54-12275

Int. Cl.³ G06F 11/10

U.S. Cl. 371-13

10 Claims



1. An error correction and detection system for detecting and correcting, at most, an m-bit error and for detecting a greater than $(m+1)$ -bit error where $m \geq 1$, using a Hamming code comprising:

means for generating a Hamming code by adding a number of redundant bits to data bits;

a memory for storing said Hamming code;

error correcting and detecting means for checking the Hamming code read out from said memory, to thereby correct an error encompassing at most m bits, while detecting an error encompassing more than $(m+1)$ bits;

means for inverting the corrected data bits output from said error correcting and detecting means in response to the detection of said at most m bit error by said error correcting and detecting means;

means for transferring said data bits, subsequent to said inversion, to said Hamming code generating means;

a data register for temporarily storing said inverted data bits as first data bits;

means for controlling said inverting means and said memory in response to the detection of said m-bit error in said error correcting and detecting means, to transfer the first data bits

to said Hamming code generating means, to obtain output data bits as second data bits from said error correcting and detecting means;

means for comparing said first data bits from said data register with said second data bits; and

means for indicating a miscorrection which has been made by said error correcting and detecting means in response to the result of the comparison by said comparing means.

4,296,495

DEVICE FOR MEASURING THE QUALITY OF A DIGITAL RADIO LINK

Jacques Bursztejn, Paris, France, assignor to Thomson CSF, Paris, France


Filed Oct. 24, 1979, Ser. No. 88,098

Claims priority, application France, Oct. 31, 1978, 78 30848

Int. Cl.³ G06F 11/10

U.S. Cl. 371-22

6 Claims



1. A device for measuring the quality of a digital radio link comprising transmission means and reception means respectively for transmitting a digital information signal and for receiving said transmitted digital information signal, said transmission means comprising means for generating parity bits for sequences of n successive bits of information in said digital information signal; control means determining the beginning of said sequences and means for transmitting with said information signal at least part of said parity bits; said receiving means comprising detection means for detecting the transmitted parity bits, means for generating parity bits for sequences of n successive bits of information in said digital information signal received, control means determining the beginning of said sequences, and comparing means for comparing the transmitted parity bits and the generated parity bits; said control means in said receiving means comprising means for bit by bit recognition of any sequence of k predetermined bits forming a refer-

ence sequence, k being smaller than n, and supplying a control signal to said means for generating parity bits.

4,296,496

EMERGENCY RADIO FREQUENCY WARNING DEVICE


William S. Sadler, 2000 Fernwood Ave., St. Paul, Minn. 55113

Continuation of Ser. No. 674,727, Apr. 6, 1976, abandoned, which is a continuation-in-part of Ser. No. 485,761, Jul. 3, 1974, Pat. No. 3,949,300. This application Nov. 28, 1978, Ser. No. 964,152

Int. Cl.³ H04K 3/00; H04B 1/02

U.S. Cl. 455-1

9 Claims



1. A radio frequency warning device for communicating with an AM radio receiver adapted to receive signals on any one of a plurality of AM broadcast carrier frequencies comprising:

means for generating a signal having components ranging across a broad frequency band;

means for generating an R-F signal;

means responsive to an audio frequency signal and said R-F signal for causing the generation of a suppressed carrier modulation signal;

means for modulating said suppressed carrier modulation signal and said broad band frequency signal to thereby generate a broad band AM radio interference signal having respective components at frequencies simulating sidebands to each of said plurality of AM broadcast carrier signals; and

means for transmitting said broad band interference signal, said broad band interference signal generating an intelligible audio signal when received by said AM radio receivers tuned to any of said plurality of carrier frequencies.

DESIGN PATENTS

GRANTED OCT. 20, 1981

ERRATA

For	See
CLASS	PATENT NO.
D32-058	261,350
D34-033	261,377

DESIGNS

OCTOBER 20, 1981

261,320

POCKET FOR JEANS OR THE LIKE


Martin Heinfliß, Bayside, N.Y., assignor to Englishtown Sportswear, Ltd., New York, N.Y.

Filed Jan. 29, 1980, Ser. No. 116,423

Term of patent 14 years

Int. Cl. D2-02

U.S. Cl. D2-25



261,322

POCKET FOR JEANS OR THE LIKE


Martin Heinfliß, Bayside, N.Y., assignor to Englishtown Sportswear, Ltd., New York, N.Y.

Filed Jan. 29, 1980, Ser. No. 116,427

Term of patent 14 years

Int. Cl. D2-02

U.S. Cl. D2-25



261,321

POCKET FOR JEANS OR THE LIKE


Martin Heinfliß, Bayside, N.Y., assignor to Englishtown Sportswear, Ltd., New York, N.Y.

Filed Jan. 29, 1980, Ser. No. 116,425

Term of patent 14 years

Int. Cl. D2-02

U.S. Cl. D2-25



261,323

JEANS OR THE LIKE

George W. Catron, Sacramento, Calif., assignor to Leo R. LeSueur, Carmichael, Calif.

Filed Aug. 8, 1979, Ser. No. 64,856

Term of patent 14 years

Int. Cl. D2-02

U.S. Cl. D2-28



261,324

JEANS OR THE LIKE

George W. Catron, Sacramento, Calif., assignor to Leo R. Le-
Sueur, Carmichael, Calif.

Filed Aug. 8, 1979, Ser. No. 64,857

Term of patent 14 years

Int. Cl. D2-02

U.S. Cl. D2-28



261,327

SKI CARRIER


Tommy D. Raye, 976 Welch Ct., Golden, Colo. 80401

Filed Aug. 1, 1977, Ser. No. 820,801

Term of patent 14 years

Int. Cl. D3-02

U.S. Cl. D3-36



261,328

LUGGAGE CASE


Michael Davis, New Castle, Pa., assignor to Airway Industries,
Inc., Ellwood City, Pa.

Filed Jul. 30, 1979, Ser. No. 61,816

Term of patent 14 years

Int. Cl. D3-01

U.S. Cl. D3-71



261,325

SHOE


Brian G. Niro, 1005 Arlington Heights Road, Arlington Heights,
Ill. 60004

Filed Mar. 17, 1980, Ser. No. 131,217

Term of patent 14 years

Int. Cl. D2-04

U.S. Cl. D2-309



261,326

TAPE CASSETTE HOLDER FOR A SUNVISOR


Ted A. Bell, and Timothy S. Cooksey, both of Coshocton, Ohio,
assignors to Pretty Products, Inc., Coshocton, Ohio

Filed Oct. 9, 1979, Ser. No. 82,828

Term of patent 14 years

Int. Cl. D3-02

U.S. Cl. D3-35



261,329

CHAIR

Robert L. Van Horn, 8165 University Blvd., Des Moines, Iowa
50311

Filed May 7, 1979, Ser. No. 36,408

Term of patent 14 years

Int. Cl. D6-01

U.S. Cl. D6-30



261,330

CHAIR

Louis M. Meier, Dubuque, Iowa, assignor to Flexsteel Indus-
tries, Inc., Dubuque, Iowa

Filed May 3, 1979, Ser. No. 35,500

Term of patent 14 years

Int. Cl. D6-01

U.S. Cl. D6-37



261,332

CHAIR

Eduard Rohr, Mägenwil, Switzerland, assignor to Wibe Treu-
hand AG, Sarmenstorf, Switzerland

Division of Ser. No. 675,302, Apr. 9, 1976.


Filed Feb. 9, 1978, Ser. No. 876,426

The portion of the term of this patent subsequent to Nov. 21,
1992, has been disclaimed.

Term of patent 14 years

Int. Cl. D6-01

U.S. Cl. D6-55



261,331

ADJUSTABLE LOUNGE CHAIR OR SIMILAR ARTICLE

Rolf Benz, Halterbacher Strasse 104, 7270 Nagold, Fed. Rep. of
Germany


Filed Jul. 11, 1979, Ser. No. 56,712

Claims priority, application Fed. Rep. of Germany, Jan. 13,
1979, MR 550-NA

Term of patent 14 years

Int. Cl. D6-01

U.S. Cl. D6-37



261,333

CHAIR OR THE LIKE

Joseph E. Adkinson, 3807 Leland St., Chevy Chase, Md. 20015


Filed Aug. 28, 1979, Ser. No. 70,443

Claims priority, application Fed. Rep. of Germany, Sep. 15,
1978, 2840125

Term of patent 14 years

Int. Cl. D6-01


U.S. Cl. D6-57



261,334
SEAT

Rex E. Light, 2836 Broadway, Fort Wayne, Ind. 46807
Filed May 19, 1978, Ser. No. 907,782
Term of patent 3½ years
Int. Cl. D6—01


U.S. Cl. D6—63

261,335
CHAIR

Marjorie M. Conner, New York, N.Y., assignor to Trigere, Inc.,
New York, N.Y.

Filed Aug. 14, 1979, Ser. No. 66,426
Term of patent 14 years
Int. Cl. D6—01


U.S. Cl. D6—72

261,336
BED HEADBOARD

Robert Thorpe, 2400 W. Coast Hwy. #H, Newport Beach, Calif.
92663


Filed Mar. 6, 1980, Ser. No. 127,823
Term of patent 14 years
Int. Cl. D6—01

U.S. Cl. D6—79

261,337
AUXILIARY TOWEL RACK

Raymond W. Fink, Maple Heights, Ohio, assignor to Tool Dynamics, Inc., Bedford Hts., Ohio
Filed Dec. 26, 1979, Ser. No. 106,756
Term of patent 14 years
Int. Cl. D23—02


U.S. Cl. D6—99

261,338
ROTATABLE TIE RACK

Grover A. Miller, 6307 Everest Way, Sacramento, Calif. 95842

Filed Jun. 11, 1979, Ser. No. 47,365
Term of patent 14 years
Int. Cl. D6—04; D8—08


U.S. Cl. D6—113

261,339
DISPLAY STAND

Kenneth E. Johnson, Sr., Waco, Tex., assignor to T-Shirts Plus, Inc., Waco, Tex.


Filed Sep. 14, 1979, Ser. No. 75,726
Term of patent 14 years
Int. Cl. D20—02

U.S. Cl. D6—152

261,340
FURNITURE LEG AND RAIL CONNECTOR

Charles W. Clyburn, Reading, Ohio, assignor to James David Incorporated, Maryland Heights, Mo.
Filed Sep. 18, 1979, Ser. No. 76,789
Term of patent 14 years
Int. Cl. D6—99


U.S. Cl. D6—191

261,341
BASE FOR A TABLE OR THE LIKE

Gunter F. Eberle, Dallas, Tex., assignor to Vecta Contract, Inc.,
Grand Prairie, Tex.

Filed Jan. 24, 1979, Ser. No. 6,100
Term of patent 14 years
Int. Cl. D6—06


U.S. Cl. D6—196

261,342
TABLE BASE

Stephen K. Frye, Fort Lauderdale, Fla., assignor to Lion in Frost Inc., Ft. Lauderdale, Fla.

Filed Feb. 26, 1979, Ser. No. 14,880
Term of patent 14 years
Int. Cl. D6—06

U.S. Cl. D6—196



261,343
BASKET INSERT FOR A KITCHEN MACHINE

Oswald Gibiec, Wuppertal, Fed. Rep. of Germany, assignor to Vorwerk & Co. Elektrowerke KG, Wuppertal, Fed. Rep. of Germany

Filed Mar. 27, 1979, Ser. No. 24,312
Claims priority, application Fed. Rep. of Germany, Dec. 4, 1978, 14145

Term of patent 14 years
Int. Cl. D07—04

U.S. Cl. D7—47


261,344
WALL-HUNG COFFEE MACHINE

Rudolf Maass, Solingen-Widdert, Fed. Rep. of Germany, assignor to Robert Krups Stiftung & Co. KG, Solingen, Fed. Rep. of Germany

Filed Sep. 13, 1979, Ser. No. 74,997
Claims priority, application Fed. Rep. of Germany, May 5, 1979, 5MR8981

Term of patent 14 years
Int. Cl. D7—02

U.S. Cl. D7—62





261,345

DECANTING CRADLE

Fritz Koepfel, 39 Tappan St., Everett, Mass. 02149, and Jean-Yves Loizance, 131 Commonwealth Ave., Boston, Mass. 02116

Filed Sep. 7, 1979, Ser. No. 73,278
Term of patent 14 years
Int. Cl. D07-06

U.S. Cl. D7-70



261,346

CUP CAKE STAMPER

Marjorie A. Thornley, c/o McCaleb, Lucas & Brugman, 230 W. Monroe St., Room 2040, Chicago, Ill. 60606

Filed Dec. 26, 1979, Ser. No. 106,384
Term of patent 14 years
Int. Cl. D07-04

U.S. Cl. D7-101




261,347

POT STAND ASSEMBLY FOR A PORTABLE CAMP STOVE

William R. Lütz, Chamblee, Ga., assignor to Conceptual Factors, Inc., Atlanta, Ga.

Filed May 31, 1979, Ser. No. 44,201
Term of patent 14 years
Int. Cl. D7-99

U.S. Cl. D7-130




261,348

RIBBED COFFEE URN LID

Leo A. Groh; Douglas D. Ludwig, both of West Bend, Wis.; David L. Painter, Glenview, Ill., and John H. Free, Kalispell, Mont., assignors to Dart Industries Inc., Los Angeles, Calif.

Filed Feb. 4, 1980, Ser. No. 118,124
Term of patent 14 years
Int. Cl. D07-02

U.S. Cl. D7-131




261,349

POT COVER HANDLE

Theophil Ryser, Beckenried, Switzerland, assignor to AMC International Alfa Metalcraft Corporation AG, Rotkreuz, Switzerland

Filed Aug. 1, 1979, Ser. No. 62,866
Term of patent 14 years
Int. Cl. D07-02

U.S. Cl. D7-132




261,350

CLOTHES DRYER RACK

Taro Koshiyama, 46, 2-chome, Minamikinomoto, Yao-shi, Osaka-fu, Japan

Filed Oct. 24, 1978, Ser. No. 954,219
Claims priority, application Japan, Aug. 25, 1978, 53-16577
Term of patent 14 years
Int. Cl. D7-05

U.S. Cl. D32-58




261,351

SNOW SCOOP BODY

William B. Carper, Harvard, Ill., assignor to Suntrak Industries, Inc., Harvard, Ill.

Filed Oct. 18, 1978, Ser. No. 952,574
Term of patent 14 years
Int. Cl. D8-01

U.S. Cl. D8-10




261,352

GUIDE WHEEL FOR WELDING TORCHES

Louis E. Miller, 409 E. 13th St., Odessa, Tex. 79761

Filed Aug. 28, 1979, Ser. No. 70,448
Term of patent 14 years
Int. Cl. D8-05

U.S. Cl. D8-30




261,353

MITRE BOX

E. Curtis Ambler, Newington, and Sylvester W. Bies, Bloomfield, both of Conn., assignors to The Stanley Works, New Britain, Conn.

Filed May 29, 1979, Ser. No. 42,864
Term of patent 14 years
Int. Cl. D8-05

U.S. Cl. D8-71




261,354

CARD EJECTOR HANDLE FOR A PRINTED CIRCUIT BOARD OR SIMILAR ARTICLE

Donald L. Clemens, The Colony, Tex., assignor to Thermalloy Incorporated, Dallas, Tex.

Filed Feb. 11, 1980, Ser. No. 120,578
Term of patent 14 years
Int. Cl. D8-06

U.S. Cl. D8-306




261,355

CATCH ASSEMBLY FOR DRAWERS AND CUPBOARDS

Alf Sundberg, Box 428, Sollentuna, Sweden

Filed May 17, 1979, Ser. No. 39,787
Claims priority, application Sweden, Nov. 17, 1978, 782667
Term of patent 14 years
Int. Cl. D8-07

U.S. Cl. D8-331



261,356

STRIP OF INSULATED CABLE CLIPS

Douglas Robinson, Preston, England, assignor to Ofrex Group Limited, London, England


Filed Mar. 3, 1978, Ser. No. 883,329

Claims priority, application United Kingdom, Sep. 7, 1977, 981432/77

Term of patent 14 years

Int. Cl. D8—08

U.S. Cl. D8—382



261,359

PACKAGE OF BLOCK-SHAPED ARTICLES


Henry E. Nass, 137 N. 4th St., Philadelphia, Pa. 19106

Filed Apr. 17, 1978, Ser. No. 896,782

Term of patent 14 years

Int. Cl. D9—03

U.S. Cl. D9—337



261,360

CONTAINER FOR LIQUIDS OR THE LIKE


Charles N. Epperson, Okmulgee, Okla., assignor to Invention Development Equity Assoc., Inc., Okmulgee, Okla.

Filed Aug. 10, 1979, Ser. No. 65,597

Term of patent 14 years

Int. Cl. D9—01

U.S. Cl. D9—375



261,357

INSULATION INJECTION HOLE PLUG

R. Dean Doonan, 1001 Sunnyside Dr., Montezuma, Iowa 50171


Filed Jul. 28, 1978, Ser. No. 929,210

The portion of the term of this patent subsequent to Feb. 6, 1995, has been disclaimed.

Term of patent 14 years

Int. Cl. D8—99; D9—07

U.S. Cl. D8—499



261,361

CONTAINER FOR LIQUID PRODUCTS OR THE LIKE


Charles N. Epperson, Okmulgee, Okla., assignor to Invention Development Equity Assoc., Inc., Okmulgee, Okla.

Filed Aug. 10, 1979, Ser. No. 65,598

Term of patent 14 years

Int. Cl. D9—01

U.S. Cl. D9—375



261,358

BLANK FOR THREE COMPARTMENT BOX


Rudolph A. Faller, Edina, Minn., assignor to Champion International Corporation, Stamford, Conn.

Filed Jun. 4, 1979, Ser. No. 31,328

Term of patent 14 years

Int. Cl. D9—03

U.S. Cl. D9—346



261,362

STACKABLE CONTAINER FOR LIQUIDS OR THE LIKE


Charles N. Epperson, Okmulgee, Okla., assignor to Invention Development Equity Assoc., Inc., Okmulgee, Okla.

Filed Aug. 10, 1979, Ser. No. 65,596

Term of patent 14 years

Int. Cl. D9—01

U.S. Cl. D9—376



261,364

TAB FOR EASY OPENING CAN END


George F. Smyth, Los Angeles, Calif., assignor to Ermal C. Frazee, Dayton, Ohio

Filed Mar. 2, 1979, Ser. No. 17,157

Term of patent 14 years

Int. Cl. D09—99

U.S. Cl. D9—438



261,365

WATCH

Alain Carre, Paris, France, assignor to Waterman S.A., Paris, France

Continuation-in-part of Ser. No. 948,655, Oct. 3, 1978, abandoned. This application Sep. 17, 1979, Ser. No. 76,275

Claims priority, application France, Apr. 7, 1979, 76 482

Term of patent 14 years

Int. Cl. D10—02

U.S. Cl. D10—38



261,363

BOTTLE


Joseph Sandor, Reseda, Calif., assignor to California Sounds Ltd., Tarzana, Calif.

Filed Apr. 30, 1979, Ser. No. 34,770

Term of patent 14 years

Int. Cl. D09—01

U.S. Cl. D9—413



261,366

MICROWAVE DETECTOR


Yanta H. T. Lam, Kowloon, Hong Kong, assignor to Meyer Aluminium Limited, Kowloon, Hong Kong

Filed Jun. 25, 1979, Ser. No. 51,496

Term of patent 14 years

Int. Cl. D10—04

U.S. Cl. D10—47



261,367

FRONT COVER FOR THERMOSTAT REGULATOR HOUSING

Mats Janson, Port, Switzerland, assignor to Tylo Sauna S.A., Biel-Bienne, Switzerland


Filed Apr. 6, 1979, Ser. No. 27,897

Claims priority, application Sweden, Oct. 16, 1978, 2389

Term of patent 14 years

Int. Cl. D10-07

U.S. Cl. D10-60



261,368

DRAWING INSTRUMENT


Joseph E. Barreca, Old Bridge Township, Mercer County, N.J., assignor to McGraw-Hill, Inc., New York, N.Y.

Filed Dec. 3, 1979, Ser. No. 99,562

Term of patent 14 years

Int. Cl. D10-04

U.S. Cl. D10-62



261,369

COMBINED TORPEDO LEVEL AND PERIPHERAL ANGLE MEASURING DEVICE


James L. Smith, 17139 River Rd., Channelview, Tex. 77530

Filed Dec. 7, 1979, Ser. No. 102,109

Term of patent 14 years

Int. Cl. D10-04

U.S. Cl. D10-69



261,370

DIAL GAUGE

Yoshikazu Kikuchi, Tochigi, Japan, assignor to Mitutoyo Mfg. Co., Ltd., Tokyo, Japan


Filed Nov. 6, 1979, Ser. No. 92,065

Claims priority, application Japan, Jun. 22, 1979, 54-26354

Term of patent 14 years

Int. Cl. D10-04

U.S. Cl. D10-73



261,371

BURGLAR ALARM HOUSING

Kenneth T. Lewis, 300 N. Sixth, Longview, Tex. 75601

Filed Feb. 5, 1979, Ser. No. 9,437

Term of patent 14 years

Int. Cl. D10-05

U.S. Cl. D10-106



261,372

EARRING

Leo A. Fried, Box 371, Poulsbo, Wash. 98370

Filed Jul. 23, 1979, Ser. No. 59,611

Term of patent 14 years

Int. Cl. D11-01

U.S. Cl. D11-40



261,373

LIGHT-REFLECTING SCULPTURE


Stanley C. Fisher, 2434 Tocayo #158, San Diego, Calif. 92154

Filed Mar. 31, 1980, Ser. No. 135,263

Term of patent 14 years

Int. Cl. D11-02

U.S. Cl. D11-131



261,374

FIGURINE OF A DOLPHIN

Jesus A. Santa-Eulalia Carvajales, and Javier B. Santa-Eulalia Carvajales, both of Montevideo, Uruguay, assignors to John J. Madison Company, Inc., Laguna Hills, Calif.

Filed Jun. 22, 1978, Ser. No. 918,319

Term of patent 14 years

Int. Cl. D11-02

U.S. Cl. D11-158



261,375

FIGURINE OF A OKAPI

Jesus A. Santa-Eulalia Carvajales, and Javier B. Santa-Eulalia Carvajales, both of Montevideo, Uruguay, assignors to John J. Madison Company, Inc., Laguna Hills, Calif.

Filed Jun. 22, 1978, Ser. No. 918,320

Term of patent 14 years

Int. Cl. D11-02

U.S. Cl. D11-158



261,376

CONSTRUCTION TROLLEY


James A. Tipton, 1243 Browns Ferry Rd., Chattanooga, Tenn. 37419

Filed Jul. 2, 1979, Ser. No. 53,746

Term of patent 14 years

Int. Cl. D12-13

U.S. Cl. D12-1



261,377

TUB MOUNTED BATH LIFT


Benton H. Grant, 126 Chestnut Hill Rd., Stamford, Conn. 06903

Filed May 3, 1979, Ser. No. 35,621

Term of patent 14 years

Int. Cl. D12-05

U.S. Cl. D34-33



261,378

CHILD'S CRAWLER


Timothy J. Bergeron, Dolgeville, N.Y., assignor to J. A. Preston Corporation, New York, N.Y.

Filed Jun. 11, 1979, Ser. No. 47,383

Term of patent 14 years

Int. Cl. D12-12

U.S. Cl. D12-128




261,379
TIRE

Jean-Claude Peron, Greenville, S.C., assignor to Compagnie Generale des Etablissements Michelin, Clermont-Ferrand, France

Filed Sep. 7, 1979, Ser. No. 73,267
Term of patent 14 years
Int. Cl. D12-15

U.S. Cl. D12-143




261,381
TIRE

Guy Amarger, Clermont-Ferrand, France, assignor to Compagnie Generale des Etablissements Michelin, Clermont-Ferrand, France

Filed Oct. 25, 1979, Ser. No. 88,121
Claims priority, application France, Apr. 27, 1979, 599
Term of patent 14 years
Int. Cl. D12-15

U.S. Cl. D12-146




261,380
TIRE

Guy Amarger, Clermont-Ferrand, France, assignor to Compagnie Generale des Etablissements Michelin, Clermont-Ferrand, France

Filed Nov. 29, 1979, Ser. No. 98,558
Term of patent 14 years
Int. Cl. D12-15

U.S. Cl. D12-143




261,382
TIRE

Jean-Claude Peron, Greenville, S.C., assignor to Compagnie Generale des Etablissements Michelin, Clermont-Ferrand, France

Filed Sep. 7, 1979, Ser. No. 73,268
Term of patent 14 years
Int. Cl. D12-15

U.S. Cl. D12-147




261,383
TIRE

Guy Amarger, Clermont-Ferrand, France, assignor to Compagnie Generale des Etablissements Michelin, Clermont-Ferrand, France

Filed Nov. 29, 1979, Ser. No. 98,557
Term of patent 14 years
Int. Cl. D12-15

U.S. Cl. D12-147




261,385
TIRE

Jean-Claude Peron, Greenville, S.C., assignor to Compagnie Generale des Etablissements Michelin, Clermont-Ferrand, France

Filed Jan. 24, 1980, Ser. No. 114,822
Term of patent 14 years
Int. Cl. D12-15

U.S. Cl. D12-147




261,384
TIRE

Jean-Claude Peron, Greenville, S.C., assignor to Compagnie Generale des Etablissements Michelin, Clermont-Ferrand, France

Filed Jan. 10, 1980, Ser. No. 110,922
Term of patent 14 years
Int. Cl. D12-15

U.S. Cl. D12-147




261,386
MOTORCYCLE TOTE BOX

Thomas S. Beaubien, Rancho Palos Verdes; Dennis C. Rich, Long Beach, and Robert E. Oehring, Norwalk, all of Calif., assignors to Bates Industries, Inc., Long Beach, Calif.

Filed Sep. 17, 1979, Ser. No. 77,164
Term of patent 14 years
Int. Cl. D12-16

U.S. Cl. D12-158




261,387

CONTROL PANEL FOR AIRCRAFT OR THE LIKE
Harry Weitz, New Hyde Park, and Diego M. Cacciatore, Farmingdale, both of N.Y., assignors to Instrument Systems Corporation, Jericho, N.Y.

Filed Apr. 20, 1979, Ser. No. 31,805
Term of patent 14 years
Int. Cl. D12-16

U.S. Cl. D12-192




261,389

FERMENTATION AND BEVERAGE STORAGE APPARATUS

Donald P. Pilla, 648 Cedar Ave., Burlington, Canada (L7T 2R5)
Filed Dec. 19, 1978, Ser. No. 971,067

Claims priority, application Canada, Oct. 31, 1978, 3110784
Term of patent 14 years
Int. Cl. D15-08; D23-01

U.S. Cl. D15-112




261,388

RECORD TURNTABLE

Raymond Vachus, Yzeure, France, assignor to Thomson-Brandt, Paris, France

Filed Jun. 4, 1979, Ser. No. 44,890
Claims priority, application France, Feb. 5, 1979, 77 277
The portion of the term of this patent subsequent to Sep. 15, 1995, has been disclaimed.
Term of patent 14 years
Int. Cl. D14-01

U.S. Cl. D14-25




261,390

BEVERAGE DISPENSER

William A. Harvill, Stone Mountain, Ga., assignor to The Coca-Cola Company, Atlanta, Ga. and The Cornelius Company, Anoka, Minn.

Filed Jan. 29, 1980, Ser. No. 116,503
Term of patent 14 years
Int. Cl. D15-08

U.S. Cl. D15-116




261,391

BEVERAGE DISPENSER VALVE

Walter E. Ranua, Blaine, and William B. Mackrell, New Brighton, both of Minn., assignors to The Cornelius Company, Anoka, Minn.

Filed Feb. 8, 1980, Ser. No. 119,735
Term of patent 14 years
Int. Cl. D15-08

U.S. Cl. D15-120



261,393


MOVIE CAMERA

Norbert Schlagheck, Fuerstenfeldbruck, Fed. Rep. of Germany, assignor to AGFA-Gevaert AG, Leverkusen, Fed. Rep. of Germany

Filed Feb. 28, 1979, Ser. No. 15,781
Claims priority, application Fed. Rep. of Germany, Sep. 7, 1978, 15578

Term of patent 14 years
Int. Cl. D16-01

U.S. Cl. D16-4




261,392

SPINDLECASE ATTACHMENT FOR TAPPING MACHINES TO CHANGE THE ROTATION OF THE TOOL

Elji Miyakawa, Tokyo, Japan, assignor to Miyakawa Industry Company, Limited, Seki, Japan

Filed Jun. 12, 1979, Ser. No. 47,856
Claims priority, application Japan, Dec. 15, 1978, 53-53014
Term of patent 14 years
Int. Cl. D15-09

U.S. Cl. D15-140



261,394


CAMERA

Udo M. Geissler, Munich, Fed. Rep. of Germany, assignor to Planbel, Feinmechanik & Optik GmbH, Frankfurt am Main-Bergen-Enkheim, Fed. Rep. of Germany

Filed Jun. 7, 1978, Ser. No. 913,497
Claims priority, application Fed. Rep. of Germany, Dec. 7, 1977, 738671

Term of patent 14 years
Int. Cl. D16-01

U.S. Cl. D16-06



261,395


TARGET SLIDE PROJECTORS CONSOLE

Brain T. Brooksby, 156 Earlsbrook Rd., Redhill, Surrey; Harold J. Murray, 32 New Odiham Rd., Alton, Hampshire; Anthony Simpson, 65 South Hill, Godalming, Surrey, and Stuart M. Peterkin, 30 Leewood Way, Effingham, Surrey, all of England
Filed Feb. 21, 1979, Ser. No. 13,262

Claims priority, application United Kingdom, Aug. 24, 1978, U.S. Cl. D16-131 986059/78

Term of patent 14 years
Int. Cl. D16-02

U.S. Cl. D16-11



261,397


MICROSCOPE STAND OR SIMILAR ARTICLE

Edwin A. Speaker, Brockport, N.Y., assignor to Bausch & Lomb Incorporated, Rochester, N.Y.

Filed Apr. 30, 1979, Ser. No. 34,223

Term of patent 14 years

Int. Cl. D16-06



261,398

DESK TOP ELECTRONIC CALCULATOR

Takashi Hirata, and Hideo Fushimoto, both of Kawasaki, Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan


Filed Aug. 8, 1979, Ser. No. 64,904

Claims priority, application Japan, Feb. 23, 1979, 54-6649

Term of patent 14 years

Int. Cl. D18-01

U.S. Cl. D18-7



261,396

PHOTOGRAPHIC PRINT WASHER


Roger Wilken, R.F.D. 2-Bonnyvale Rd., Guilford, Vt. 05301

Filed Apr. 30, 1979, Ser. No. 34,837

Term of patent 14 years

Int. Cl. D16-04

U.S. Cl. D16-35



261,399

BLACK JACK SLIDE RULE


Robert G. Wagner, 1077 Wakefield Ave., St. Paul, Minn. 55106

Filed Oct. 15, 1979, Ser. No. 84,939

Term of patent 14 years

Int. Cl. D19-99

U.S. Cl. D18-10



261,400

COMBINED ADHESIVE CONTAINER AND DISPENSER
Glenn L. Beall, Gurnee, Ill.; Lawrence Petersen, Mount Vernon, N.Y., and Richard J. Dauksys, Glastonbury, Conn., assignors to Loctite Puerto Rico, Sabana Grande, P.R.

Continuation of Ser. No. 921,620, Jul. 3, 1978, abandoned. This application Jan. 28, 1980, Ser. No. 116,350

Term of patent 14 years

Int. Cl. D19-06

U.S. Cl. D19-66



261,402

BASKETBALL GAME DISPLAY AND CONTROL PANEL OR SIMILAR ARTICLE


Robert B. Lovejoy, Torrance, Calif., assignor to Mattel, Inc., Hawthorne, Calif.

Filed Oct. 16, 1978, Ser. No. 951,903

Term of patent 14 years

Int. Cl. D21-01

U.S. Cl. D21-13



261,401

SIGN POST SUPPORT

Carroll E. Collis, 5640 Shull Street, Bell Gardens, Calif. 90201

Filed Dec. 7, 1979, Ser. No. 83,589

Term of patent 14 years

Int. Cl. D20-03

U.S. Cl. D20-41



261,403

TOY HOOP ROLLER

Joseph Pataki, 112 Graham Rd., Ithaca, N.Y. 14850

Filed Jun. 21, 1978, Ser. No. 917,688

Term of patent 14 years

Int. Cl. D21-02

U.S. Cl. D21-101



261,404

TOY KITCHEN


Mel Appel, Nine Nottingham Rd., Livingston, N.J. 07039, and George Kress, Scotch Plains, N.J., assignors to Mel Appel, Livingston, N.J.

Filed Jan. 16, 1980, Ser. No. 112,718

Term of patent 14 years

Int. Cl. D21-01

U.S. Cl. D21-122



261,406

SKATE WHEEL



Gary L. Corbin, 11117 Klingerman St., El Monte, Calif. 91733

Filed Jul. 11, 1979, Ser. No. 56,546

Term of patent 14 years

Int. Cl. D21-02

U.S. Cl. D21-226



261,405

TOY RABBIT

Karen D. Marconi, East Aurora, N.Y., assignor to The Quaker Oats Company, Chicago, Ill.

Filed Jan. 15, 1980, Ser. No. 112,359

Term of patent 14 years

Int. Cl. D21-01

U.S. Cl. D21-187



261,407

SHELTER

Charles W. Moss, c/o Moss Tent Works, Mt. Battle St., Camden, Me. 04843

Filed Jun. 1, 1979, Ser. No. 44,592

Term of patent 14 years

Int. Cl. D21-04

U.S. Cl. D21-253



261,408

GAFF HOLDER FOR THE SPUR OF A GAMECOCK


John W. Bryan, 3501 Washington Dr., Falls Church, Va. 22042

Filed Mar. 14, 1980, Ser. No. 130,538

Term of patent 14 years

Int. Cl. D22-02; D30-99

U.S. Cl. D22-1



261,411

FISHING ROD GRIP

Tetsuyuki Doi, and Takeshi Shohoji, both of Fukuyama, Japan, assignors to Ryobi Limited, Hiroshima, Japan

Filed Feb. 4, 1980, Ser. No. 118,236

Term of patent 14 years

Int. Cl. D22-05

U.S. Cl. D22-23



261,409

LONG BARREL HOLSTER

John E. Bianchi, 1601 Wilt Rd., and Richard D. E. Nichols, 813

Cozy Ct., both of Fallbrook, Calif. 92390

Filed Dec. 7, 1979, Ser. No. 101,200

Term of patent 14 years

Int. Cl. D3-02

U.S. Cl. D22-13



261,412

LINE GUIDE FOR FISHING ROD

Ryuichi Ohmura, Shizuoka, Japan

Filed Oct. 10, 1979, Ser. No. 83,521

Term of patent 14 years

Int. Cl. D22-05

U.S. Cl. D22-24



261,410

FISHING LURE

Dewey C. Mullins, Virginia Beach, Va., assignor to Mullins Lure Company, Virginia Beach, Va.

Filed Dec. 10, 1979, Ser. No. 101,670

Term of patent 14 years

Int. Cl. D22-05

U.S. Cl. D22-29



261,413

VACUUM FILTER


Roy T. Eddleman, 60916 Terminal Annex, Los Angeles, Calif. 90054

Filed Oct. 1, 1979, Ser. No. 80,437

Term of patent 14 years

Int. Cl. D23-01

U.S. Cl. D23-4



261,414

SPRINKLER BASE


Jerry R. Hayes, Peoria, Ill., assignor to L. R. Nelson Corporation, Peoria, Ill.

Filed Mar. 8, 1979, Ser. No. 18,757

Term of patent 14 years

Int. Cl. D23—01

U.S. Cl. D23—7



261,417

SHOWERHEAD

Odo Klose, Wuppertal, Fed. Rep. of Germany, assignor to Friedrich Grohe Armaturenfabrik GmbH & Co., Hemer, Fed. Rep. of Germany


Filed Aug. 27, 1979, Ser. No. 70,171

Claims priority, application Fed. Rep. of Germany, Mar. 26, 1979, MR6936

Term of patent 14 years

Int. Cl. D23—01

U.S. Cl. D23—35



261,418

COMBINED STRAINER AND PLUG FOR A SINK OR THE LIKE


Edward Jackson, 26 McGahan St., Carina, Queensland, 4152, Australia

Filed Jun. 7, 1979, Ser. No. 46,546

Term of patent 14 years

Int. Cl. D23—01

U.S. Cl. D23—42



261,419

SAFETY SUCTION FITTING FOR HYDRO-THERAPY SPAS


Gerald W. Moreland, 11651 Pickett La., Garden Grove, Calif. 92640

Filed Nov. 5, 1979, Ser. No. 91,478

Term of patent 14 years

Int. Cl. D23—01

U.S. Cl. D23—42



261,416

CAN PIERCING SPRAYING TOOL


Larry O. Siefken, R.R. 1, Box 75, Palmer, Iowa 50571

Filed Aug. 2, 1978, Ser. No. 930,583

Term of patent 14 years

Int. Cl. D23—01

U.S. Cl. D23—34



261,420

COMBINED PLUMBING FIXTURE BOWL AND CABINET


Lawrence E. Wolske, St. Joseph, Mich., assignor to Whirlpool Corporation, Benton Harbor, Mich.

Filed Dec. 30, 1977, Ser. No. 866,174

Term of patent 14 years

Int. Cl. D23—02

U.S. Cl. D23—59



261,421

HUMIDIFIER FOR A HOT AIR FURNACE OR THE LIKE


William B. Morrow, Hillsville, Va., assignor to Aqua-Mist, Inc., Winston-Salem, N.C.

Filed Aug. 24, 1979, Ser. No. 70,518

Term of patent 14 years

Int. Cl. D23—04

U.S. Cl. D23—147



261,424

RACK FOR HOLDING DENTAL INSTRUMENTS


Robert A. Anson, 1423 Stony Brook Rd., Stony Brook, N.Y. 11790

Filed Mar. 9, 1978, Ser. No. 885,100

Term of patent 14 years

Int. Cl. D24—02

U.S. Cl. D24—16



261,422

HUMIDIFIER FOR A HOT AIR FURNACE OR THE LIKE


William B. Morrow, Hillsville, Va., assignor to Aqua-Mist, Inc., Winston-Salem, N.C.

Filed Aug. 24, 1979, Ser. No. 70,519

Term of patent 14 years

Int. Cl. D23—04

U.S. Cl. D23—147



261,425

BONE CEMENT INJECTOR HANDPIECE


John A. Bruhn, New Paris, Ind., assignor to Zimmer USA, Inc., Warsaw, Ind.

Filed Feb. 11, 1980, Ser. No. 120,407

Term of patent 14 years

Int. Cl. D24—02

U.S. Cl. D24—26



261,428

CHIROPRACTIC VIBRATOR


Edward D. Noble, 29 Havenbrook Blvd., Willowdale, Ontario, Canada (M2J 1A3)

Filed Nov. 20, 1978, Ser. No. 962,451

Term of patent 14 years

Int. Cl. D28—03

U.S. Cl. D24—41



261,426

HYDROTHERAPY SPA



Richard G. Reineman, Newport Beach, Calif., assignor to Marlin Fiberglass, Inc., Huntington Beach, Calif.

Filed Aug. 27, 1979, Ser. No. 69,802

Term of patent 14 years

Int. Cl. D24—01; D23—02

U.S. Cl. D24—38



261,427

WHIRLPOOL BATHTUB


Philip I. Ogden, 1051 Boeing, Boise, Id. 83705

Filed Sep. 24, 1979, Ser. No. 78,097

Term of patent 14 years

Int. Cl. D24—01; D25—99; D23—02

U.S. Cl. D24—38



261,429

BED PAN SEAT LINER


Joan Hanna-Burns, 3630 S. Sepulveda 1-239, Los Angeles, Calif. 90034

Filed Aug. 31, 1979, Ser. No. 71,697

Term of patent 14 years

Int. Cl. D24—04

U.S. Cl. D24—51



261,430

VACUUM SPLINT


Peter Baturin, Winnipeg, Canada, assignor to Medical Products Institute Incorporated, Winnipeg, Canada

Filed Oct. 10, 1978, Ser. No. 949,904

Term of patent 14 years

Int. Cl. D24—04

U.S. Cl. D24—64



261,431

VENDING TRAILER


Shirley Barton, P.O. Box 2065, Sarasota, Fla. 33578

Filed Jan. 26, 1979, Ser. No. 6,631

Term of patent 14 years

Int. Cl. D25—03

U.S. Cl. D25—10



261,432

EMERGENCY SHELTER FOR UNDERGROUND INSTALLATION


James H. Ballard, 513 Bexar Ave., Hamilton, Ala. 35570

Filed Mar. 13, 1980, Ser. No. 130,076

Term of patent 14 years

Int. Cl. D25—01

U.S. Cl. D25—36



261,433

AUTOMATIC TICKET GATE

Yoshihiko Sugano, Tokyo, Japan, assignor to Tokyo Shibaura Denki Kabushiki Kaisha, Kawasaki, Japan


Filed Jan. 4, 1980, Ser. No. 109,517

Claims priority, application Japan, Jul. 13, 1979, 54-28925

Term of patent 14 years

Int. Cl. D25—02; D20—01

U.S. Cl. D25—50



261,434

AUTOMATIC TICKET GATE

Yoshihiko Sugano, Tokyo, Japan, assignor to Tokyo Shibaura Denki Kabushiki Kaisha, Kawasaki, Japan


Filed Jan. 4, 1980, Ser. No. 109,518

Claims priority, application Japan, Jul. 13, 1979, 54-28924

Term of patent 14 years

Int. Cl. D20—01; D25—02

U.S. Cl. D25—50



261,435

ACOUSTICAL CEILING PANEL

Mark R. Weitzman, Toledo, Ohio; Jared R. Kies, Perrysburg, Ohio, assignor to Owens-Corning Fiberglas Corporation, Toledo, Ohio

Filed Sep. 27, 1979, Ser. No. 79,396

Term of patent 14 years

Int. Cl. D25—01

U.S. Cl. D25—97



261,436

LIGHTING FIXTURE

James J. Palka, Arlington Heights, and Robert Rekart, Villa Park, both of Ill., assignors to General Bathroom Products Co., Elk Grove Village, Ill.

Filed May 4, 1979, Ser. No. 35,995

Term of patent 3 1/2 years

Int. Cl. D26—05

U.S. Cl. D26—80




261,437

DECORATIVE WALL LAMP

Terry C. Stekelberg, R.R. #1, Pardeeville, Wis. 53954
Filed Nov. 27, 1978, Ser. No. 963,846

Term of patent 14 years
Int. Cl. D26—05


U.S. Cl. D26—87

261,438
PIPE

S. Franklin Sher, 609 Lochmoor, Danville, Calif. 94526
Filed Jun. 2, 1980, Ser. No. 156,318

Term of patent 14 years
Int. Cl. D27—02

U.S. Cl. D27—03

261,439
PIPE

S. Franklin Sher, 609 Lochmoor, Danville, Calif. 94526
Filed Jun. 2, 1980, Ser. No. 156,319

Term of patent 14 years
Int. Cl. D27—02

U.S. Cl. D27—03




261,440

SHAMPOO DRAINAGE TRAY

Edward J. Pasquarello, 5 Silvermine Rd., Woburn, Mass. 01801
Filed Feb. 5, 1979, Ser. No. 9,111

Term of patent 14 years
Int. Cl. D28—03

U.S. Cl. D28—20


261,441
CURLING IRON

Robert Oberheim, Liederbach; Jürgen Greubel, Heidenrod, and
Dieter Rams, Kronberg, all of Fed. Rep. of Germany, assign-
ors to Braun Aktiengesellschaft, Kronberg, Fed. Rep. of Ger-
many

Filed Jun. 19, 1980, Ser. No. 158,840
Claims priority, application Fed. Rep. of Germany, Jan. 8,
1980, 73 MR 8842

Term of patent 14 years
Int. Cl. D28—03

U.S. Cl. D28—35



261,442


OROPHARYNGEAL AIRWAY

Charles C. Anderson, 2827 W. Meadowwood Dr., Chesapeake,
Va. 23321

Filed Apr. 17, 1979, Ser. No. 30,826
Term of patent 14 years

Int. Cl. D24—02

U.S. Cl. D29—6




261,443

WALL-MOUNTED MAILBOX

William DeLange, 5826 Foxboro Trail, Springfield, Mo. 65804
Filed Jun. 4, 1979, Ser. No. 44,958

Term of patent 14 years
Int. Cl. D99—00

U.S. Cl. D99—33



261,444


BAKERY TRAY

Emil L. Munch, Cincinnati, Ohio, assignor to Nestier Corpora-
tion, Cincinnati, Ohio

Filed Nov. 30, 1978, Ser. No. 965,154
Term of patent 14 years

Int. Cl. D3—99

U.S. Cl. D34—43



LIST OF PATENTEEES

TO WHOM

PATENTS WERE ISSUED ON THE 20TH DAY OF OCTOBER, 1981

NOTE—Arranged in accordance with the first significant character or word of the name
(in accordance with city and telephone directory practice).

- A. C. Company: *See—*
Gibson, Joseph T.; and Duhon, Gerald L., 4,295,366, Cl. 73-155.000.
- A. H. Robins Company, Incorporated: *See—*
Cale, Albert D., Jr., 4,296,037, Cl. 260-343.600.
Munson, Harry R., Jr., 4,296,092, Cl. 424-43.000.
- A. Menarini S.A.S.: *See—*
Ghelardoni, Mario; Pestellini, Vittorio; Del Soldato, Piero; Volterra, Giovanna; and Meli, Alberto, 4,296,124, Cl. 424-285.000.
- A.P.V. Spiro-Gills Limited: *See—*
Gale, John A., 4,295,341, Cl. 62-100.000.
- A. Stucki Company: *See—*
Wiebe, Donald, 4,295,429, Cl. 105-197.0DB.
- A-T-O Inc.: *See—*
John, Frank T., 4,296,399, Cl. 338-34.000.
Mitchell, Hal D., 4,295,227, Cl. 2-2.000.
- AAI Corporation: *See—*
Davis, William O., 4,295,425, Cl. 102-326.000.
- Abe, Kazunori: *See—*
Kamada, Kazumasa; Nakai, Yoshio; and Abe, Kazunori, 4,296,214, Cl. 525-2.000.
- Abendroth, Paul; and Dettinger, Dietrich, to M.A.N.-Roland Druckmaschinen Aktiengesellschaft. Safety device for guarding nips in a sheet-fed rotary printing press. 4,295,421, Cl. 101-216.000.
- Abraham, Fayez F., to Tyler Refrigeration Corporation. Refrigerated display case having ambient air defrost. 4,295,340, Cl. 62-82.000.
- Acco Industries Inc.: *See—*
Neal, Warren D.; and Nicodemus, Robert N., Jr., 4,295,559, Cl. 198-598.000.
- ACF Chemiefarma N.V.: *See—*
Ladage, Cornelis A.; Van Linge, Douwe J.; and Van Riessen, Huibert A., 4,296,131, Cl. 424-347.000.
- Achiha, Masahiko, to Hitachi, Ltd.; and Hitachi Denshi Kabushiki Kaisha. Noise reducing system. 4,296,436, Cl. 358-167.000.
- Acra-Plant, Inc.: *See—*
Williams, Donald E.; Robertson, Forrest E.; Gigot, C. Dean; and Gigot, Terry K., 4,295,532, Cl. 172-184.000.
- Acres, Alexander D. Dispensing container with improved air valve. 4,295,582, Cl. 222-213.000.
- Adamek, Radomil: *See—*
Kupf, Lubomir; Travnick, Jiri; Adamek, Radomil; and Kyzlink, Josef, 4,295,628, Cl. 249-80.000.
- Adams, Gary V.; and Schneider, Fred E., to Thiokol Corporation. Method of and apparatus for gas generation. 4,296,084, Cl. 423-351.000.
- Adams, John E.; Evans, Robert F.; and Gavin, John H., to Du Pont de Nemours, E. I., and Company. Transmission line cable applicator machine. 4,295,254, Cl. 29-33.00M.
- Adams, John M., to Medtronic, Inc. Heart rate monitor. 4,295,472, Cl. 128-690.000.
- Adamski, John L., to Boeing Company, The. Multi-stage collective field charged particle accelerator. 4,296,327, Cl. 250-423.00R.
- Adcock, Marty E., to Babcock & Wilcox Company, The. Stud handling tool. 4,295,393, Cl. 81-57.400.
- Addamiano, Arrigo: *See—*
Klein, Philipp H.; Addamiano, Arrigo; and Allen, Roger, 4,295,989, Cl. 252-301.40F.
- Adolphi, Heinrich: *See—*
Burstinghaus, Rainer; Kiehs, Karl; and Adolphi, Heinrich, 4,296,108, Cl. 424-210.000.
- Advanced Marine Concepts, Inc.: *See—*
Upchurch, Lonnie W., 4,295,236, Cl. 9-2.00S.
- Aerojet-General Corporation: *See—*
Hoffman, Lawrence C., 4,295,346, Cl. 62-500.000.
- AGA AB: *See—*
Stavlo, Lars G., 4,295,431, Cl. 108-55.100.
- AGFA-Gevaert Aktiengesellschaft: *See—*
Stemme, Otto; Ruf, Wolfgang; and Wagensonner, Eduard, 4,296,438, Cl. 358-214.000.
- Aichert, Hans: *See—*
Stephan, Herbert; Aichert, Hans; and Heimerl, Joseph, 4,295,808, Cl. 425-8.000.
- Aigle, Karl; Hieber, Udo; Huebscher, Wilhelm; Rheindorf, Hans H.; and Wiedemann, Rolf, to Siemens Aktiengesellschaft. Wound electrical capacitor with excessive pressure protective device. 4,296,453, Cl. 361-275.000.
- Aignesberger, Alois; Lukas, Walter; and Weinberg, Ekkehard, to Suddeutsche Kalkstickstoff-Werke. Inorganic fibers. 4,296,089, Cl. 423-555.000.
- Aikawa, Takahisa: *See—*
Tsuiji, Shigeo; and Aikawa, Takahisa, 4,296,316, Cl. 250-204.000.
- Air Shields, Inc.: *See—*
Torzala, Terence A., 4,295,475, Cl. 128-736.000.
- Aisin Seiki Kabushiki Kaisha: *See—*
Hayashi, Masaharu, 4,295,550, Cl. 192-58.00B.
- Aitken, Thomas; Kowalski, David J.; and Srinivasan, K. G., to Nalco Chemical Company. Alkoxyated dioxolanes as paper sizing agents. 4,295,930, Cl. 162-158.000.
- Akazawa, Tadashi: *See—*
Fukui, Shosin; and Akazawa, Tadashi, 4,296,224, Cl. 526-243.000.
- Aktiebolaget Electrolux: *See—*
Viklund, Ake E., 4,295,693, Cl. 312-257.00R.
- Aktiebolaget SKF: *See—*
Lundstrom, Sten, 4,295,591, Cl. 227-142.000.
- Aktieselskabet Brodrene Hartmann: *See—*
Petersen, Jorgen N., 4,295,597, Cl. 229-2.5EC.
- Akzona Incorporated: *See—*
Zielke, Rainer; and Maegerlein, Helmut, 4,296,260, Cl. 568-763.000.
- Albrecht, Robert D.; Presley, Michael; Waller, William E.; Cook, Gerald L.; and Presley, William E., to Presley, Waller & Presley. Electro-mechanically rotatable mirror. 4,295,708, Cl. 350-289.000.
- Albright & Wilson Limited: *See—*
Lowe, Edward J.; Minshall, Michael W.; and Wilson, Arthur, 4,296,082, Cl. 423-305.000.
- Alco Standard Corporation: *See—*
Luebke, Clement J.; Mitchell, John A.; and Daniels, Lowell W., 4,296,310, Cl. 219-440.000.
- Alderton, Gordon H. S., to Henry Lindsay Limited. Hookbolt adapter. 4,295,770, Cl. 411-531.000.
- Aldridge, Clyde L.: *See—*
Bearden, Roby, Jr.; and Aldridge, Clyde L., 4,295,995, Cl. 252-431.00C.
- Bearden, Roby, Jr.; Aldridge, Clyde L.; and Pine, Lloyd A., 4,295,996, Cl. 252-431.00C.
- Alexander Schoeller & Co., A.G.: *See—*
Steinlein, Rudolf F., 4,295,576, Cl. 220-21.000.
- Alfa Romeo S.p.A.: *See—*
Toti, Gabriele; Lenzi, Giuliano; and Monti, Paolo, 4,295,660, Cl. 280-714.000.
- Allen, Forrest: *See—*
Racz, Gabor; and Allen, Forrest, 4,295,465, Cl. 128-11.000.
- Allen, Roger: *See—*
Klein, Philipp H.; Addamiano, Arrigo; and Allen, Roger, 4,295,989, Cl. 252-301.40F.
- Allen, Walter E. Solenoid operated valve. 4,295,631, Cl. 251-30.000.
- Allied Chemical Corporation: *See—*
Long, E. David, 4,295,451, Cl. 123-438.000.
- Allison, Richard: *See—*
Harrington, Alan L.; Rodov, Vladimir; and Allison, Richard, 4,295,267, Cl. 29-571.000.
- Alpha Farmaceutici S.p.A.: *See—*
Borzatta, Valerio; Cristofori, Manlio; Morotti, Mauro; and Mascellani, Giuseppe, 4,296,125, Cl. 424-315.000.
- Alphonse, Gerard A.: *See—*
Keizer, Eugene O.; and Alphonse, Gerard A., 4,296,371, Cl. 324-61.00R.
- Altec Corporation: *See—*
Cullison, Steven B.; and Slack, Charles B., 4,296,278, Cl. 179-1.0VL.
- Aluminum Company of America: *See—*
Carlson, Lawrence E., 4,295,316, Cl. 52-588.000.
- Aluminum Pechiney: *See—*
Maurel, Pierre; Nicolas, Francois; and Bosca, Bernard, 4,296,073, Cl. 423-3.000.
- AMBAC Industries, Incorporated: *See—*
McMillen, Bobby E., 4,296,343, Cl. 310-154.000.
- Amberg, Christopher P., to Owens-Illinois, Inc. Closure dispenser. 4,295,580, Cl. 221-268.000.
- Ambrose, Jere B. Padding sheet formed of a mixture of fibers bonded at their intersections. 4,296,168, Cl. 428-288.000.
- American Cyanamid Company: *See—*
DeMaria, Francesco, 4,296,059, Cl. 264-130.000.
- De Maria, Francesco; and Pfeiffer, Ronald E., 4,296,175, Cl. 428-398.000.
- Lang, Stanley A., Jr.; and Murdock, Keith C., 4,296,030, Cl. 260-239.00A.
- American Home Products Corporation: *See—*
Krupey, John, 4,295,280, Cl. 34-5.000.
- Ammo Tools, Inc.: *See—*
Spainhour, Phillip A.; Morrison, Leonard A.; and Hampton, Robert S., Jr., 4,295,634, Cl. 254-10.500.

- AMP Incorporated: See—
Vanderheyden, Eric E.; and Casciotti, Albert, 4,296,390, Cl. 333-182.000.
- Amtel, Inc.: See—
Pomoniak, George M., 4,295,237, Cl. 9-8.00P.
- Anand, Joginder N.; Revak, Timothy T.; and Tsang, Floris Y., to Dow Chemical Company, The. Method of fabricating helium-tight tube-sheet for hollow fiber type battery cells. 4,296,052, Cl. 264-25.000.
- Andersen, Alan J.: See—
Bascom, Hollis H.; Matweyou, Stephen; Andersen, Alan J.; and Greci, John J., 4,295,905, Cl. 156-174.000.
- Anderson, Lloyd E.: See—
Bell, Dwain C.; and Anderson, Lloyd E., 4,295,777, Cl. 414-458.000.
- Anderson, Rollen J., to Tracor, Inc. Nitrosamine specificity for electrolytic conductivity detector. 4,295,856, Cl. 23-232.00E.
- Andrianov, Vladimir R.: See—
Lifshits, Viktor S.; Krivonos, Vadim P.; Podola, Nikolai V.; Grabchev, Boris L.; Andrianov, Vladimir R.; and Shakhov, Rifkhat M., 4,296,305, Cl. 219-101.000.
- Andrillon, Patrick: See—
Grollier, Jean F.; Bugaut, Andree; Andrillon, Patrick; and Fourcader, Chantal, 4,295,848, Cl. 8-421.000.
- Angel, Henry R.; and Hennessy, James W., to Hycel, Inc. Hematology cell counting apparatus incorporating multiple transducers for sequential operation. 4,296,373, Cl. 324-71.0CP.
- Angwin, Meredith J.; Pfefferle, William C.; and Kesseling, John P., to United States of America, America. Catalytic monolith and method of its formulation. 4,295,818, Cl. 431-7.000.
- Anisimov, Vyacheslav I.; Bulgakov, Evgeny G.; Gurin, Vasily N.; Radjuevich, Leonid V.; Trishevsky, Igor S.; Trishevsky, Oleg I.; Kheifets, Grigory R.; and Jurchenko, Anatoly B. Mill stand for forming discontinuous longitudinal deformations in sheet metal. 4,295,353, Cl. 72-180.000.
- Anthony, Andrew J., to Combustion Engineering, Inc. Bimetallic spacer means for a nuclear fuel assembly. 4,295,935, Cl. 376-285.000.
- Antonitsch, Sepp: See—
Sauer, Hans; Steinbichler, Wolf; and Antonitsch, Sepp, 4,296,393, Cl. 335-125.000.
- Antos, George J., to UOP Inc. Hydrocarbon dehydrocyclization with an attenuated superactive multimetallic catalytic composite. 4,295,959, Cl. 208-138.000.
- Antos, George J., to UOP Inc. Hydrocarbon dehydrocyclization with an attenuated superactive multimetallic catalytic composite. 4,295,960, Cl. 208-139.000.
- Aotani, Seiji; and Kanayama, Hisanori, to Japan Synthetic Rubber Co., Ltd. Molded article of hydrous polymer and process for producing the same. 4,296,015, Cl. 260-29.6ME.
- Appleton, Richard A.; and Johnston, David, to Fisons Limited. 3,4-Dihydro-3-oxopyridido[2,3-b]-pyrazines, compositions and use thereof. 4,296,114, Cl. 424-248.520.
- Arai, Katsuhiko: See—
Ohashi, Takashi; Okoyama, Toru; and Arai, Katsuhiko, 4,296,170, Cl. 428-313.000.
- Arakawa Kagaku Kogyo Kabushiki Kaisha: See—
Okumichi, Toshiharu; Oseto, Osamu; Matsumoto, Keizo; Thuzimoto, Shigenori; and Sanda, Hisanari, 4,296,012, Cl. 260-29.6XA.
- Archer, Michael A., to Lucas Industries Limited. Control systems. 4,296,361, Cl. 318-54.000.
- Arends, Roger R.; Bailey, Wayne B.; Duffy, John W.; and Springer, Brice D., to Fisher Controls Company, Inc. Pilot-operated back pressure regulator. 4,295,489, Cl. 137-488.000.
- Arima, Ryoji; Umezawa, Kazushige; and Nisugi, Tokuzo, to Nippon Steel Corporation. Steel making process. 4,295,882, Cl. 75-52.000.
- Armco Inc.: See—
Douthett, Joseph A.; and Espy, Ronald H., 4,295,769, Cl. 411-411.000.
- Armstrong World Industries, Inc.: See—
Davis, Charles D., 4,295,498, Cl. 139-196.200.
- Arthur Fulmer of Mississippi, Inc.: See—
Miller, Fred J., 4,295,564, Cl. 206-279.000.
- Artweger, Wolfgang; and Freller, Walter, to "Wohn-Art" Freizeitartikel Gesellschaft m.b.H. Van structure. 4,295,679, Cl. 296-171.000.
- Asahi Kasei Kogyo Kabushiki Kaisha: See—
Shibasaki, Ichiro; Ohmura, Kaoru; and Kimura, Takeo, 4,296,424, Cl. 357-1.000.
- Asano, Kiro: See—
Enomoto, Satoru; Asano, Kiro; and Tanaka, Hiromitsu, 4,296,233, Cl. 536-5.000.
- Asea Aktiebolag: See—
Eriksson, Leif; and Liberman, Salomon, 4,296,452, Cl. 361-82.000.
- Moritz, Bertil, 4,296,395, Cl. 336-60.000.
- Ashfield, Herbert E.; Horsfall, Harry; and Wade, Philip M., to David Brown Tractors Limited. Lower link draft sensing system on tractor. 4,295,530, Cl. 172-7.000.
- Ashida, Teiji: See—
Ogiwara, Kenzyu; Kawada, Minoru; and Ashida, Teiji, 4,295,781, Cl. 415-1.000.
- Ashland Oil, Inc.: See—
Tordoff, William L., 4,295,515, Cl. 164-158.000.
- Ashton, Christopher J.; Diamond, Andrew C.; and Greenhill, Derek H., to Marler Haley Expositystems Limited. Display structures and the like. 4,295,754, Cl. 403-369.000.
- Atari, Inc.: See—
Mayer, Steven T.; Miner, Jay G.; Neubauer, Douglas G.; and Decuir, Joseph C., 4,296,476, Cl. 364-900.000.
- Atchison, George J.: See—
Seeburger, Harold O.; Atchison, George J.; and Stevens, Violette L., 4,296,227, Cl. 526-320.000.
- Atkinson, Lyle H. Cooling container for canned beverages. 4,295,345, Cl. 62-371.000.
- Atlantic Richfield Company: See—
Grane, Henry R.; Jubin, John C., Jr.; and Worrell, G. Richard, 4,296,262, Cl. 568-910.000.
- Jerome, Jonathan A., 4,296,491, Cl. 369-59.000.
- Sun, Jui-Yuan; Burk, Emmett H., Jr.; Yoo, Jin S.; and Masologites, George P., 4,295,858, Cl. 44-1.0SR.
- Worrell, G. Richard, 4,296,263, Cl. 568-910.000.
- Atlas Powder Company: See—
Smith, Don H.; Bowman, Arthur F.; and Junk, Norman M., 4,295,424, Cl. 102-322.000.
- Auto-Flush Systems Ltd.: See—
Gilmour, Alfred J., 4,295,503, Cl. 141-90.000.
- Automobiles Peugeot: See—
Goux, Jacques, 4,296,471, Cl. 364-424.000.
- Autzen, Horst: See—
Steck, Werner; Sarnecki, Wilhelm; Marosi, Laszlo; Ohlinger, Manfred; and Autzen, Horst, 4,295,879, Cl. 75-0.5AA.
- Avery, Grant D.: See—
Higgs, Jacob K.; and Avery, Grant D., 4,296,410, Cl. 340-686.000.
- Avibank Mfg., Inc.: See—
Duran, John A., 4,295,674, Cl. 292-190.000.
- Avtex Fibers Inc.: See—
Gresham, John T., 4,295,886, Cl. 106-18.190.
- Ax, Wolfgang; Bauer, Hartwig W.; and Sedlacek, Hans-Harald, to Behringwerke Aktiengesellschaft. Methods for the detection of antimitochondrial and antinuclear antibodies. 4,296,201, Cl. 435-7.000.
- Axen, Udo F.; and Sih, John C., to Upjohn Company, The. 2,5-Inter-phenylene-3,4-dinor-PGF₂ amides. 4,296,253, Cl. 564-153.000.
- Axenko, Alexandr A.: See—
Nazarian, Miron M.; Efimov, Vyacheslav T.; Axenko, Alexandr A.; Kolyada, Vladimir A.; and Shamsha, Ljudmila F., 4,295,946, Cl. 204-149.000.
- B. F. Goodrich Company, The: See—
Morris, Roger E.; and Jorgensen, August H., Jr., 4,296,007, Cl. 260-23.70N.
- Babcock & Wilcox Company, The: See—
Adcock, Marty E., 4,295,393, Cl. 81-57.400.
- Bey, Roger, 4,295,493, Cl. 138-43.000.
- Weber, Charles M., 4,295,255, Cl. 29-157.30V.
- Babitzka, Rudolf: See—
Schlagmuller, Walter; and Babitzka, Rudolf, 4,295,554, Cl. 192-105.0CE.
- Baccai, Louis J., to Loctite Corporation. Curable polybutadiene-based resins having improved properties. 4,295,909, Cl. 156-307.300.
- Baclit, Paul S. Nursing bottle holder. 4,295,293, Cl. 46-202.000.
- Bailey, James P.: See—
Betsinger, James D.; and Bailey, James P., 4,295,612, Cl. 239-310.000.
- Bailey, Wayne B.: See—
Arends, Roger R.; Bailey, Wayne B.; Duffy, John W.; and Springer, Brice D., 4,295,489, Cl. 137-488.000.
- Baird, William C., Jr.: See—
Mauldin, Charles H.; and Baird, William C., Jr., 4,295,957, Cl. 208-138.000.
- Mauldin, Charles H.; and Baird, William C., Jr., 4,295,958, Cl. 208-138.000.
- Baker, Eugene E.; and Szarka, David D., to Halliburton Company. Isolation gravel packer. 4,295,524, Cl. 166-278.000.
- Baker International Corporation: See—
Carmody, Michael, 4,295,528, Cl. 166-315.000.
- Swift, Edward R., Jr.; and Schmuck, Philip W., 4,295,525, Cl. 166-312.000.
- Baker, Thomas R.; and Collura, Peter C., to Kliklok Corporation. Method and apparatus for forming a flanged tray. 4,295,839, Cl. 493-143.000.
- Balda-Werke: See—
Lange, Karl H., 4,295,719, Cl. 354-50.000.
- Baldwin-Korthe Web Controls, Inc.: See—
Larson, Clifford L., 4,295,400, Cl. 83-545.000.
- Bandoh, Tadaaki; and Fukunaga, Yasushi, to Hitachi, Ltd. Address conversion unit for data processing system. 4,296,468, Cl. 364-200.000.
- Bangor Punta Corporation: See—
Mergen, Joseph, 4,295,659, Cl. 280-405.00R.
- Banner Industries, Inc.: See—
Mehesan, Thomas C., Jr., 4,295,771, Cl. 414-5.000.
- Banos, Zoltan: See—
Takacs, Istvan; Banos, Zoltan; Illes, Janos; Vereczkey, Endre; Rudolf, Peter; and Kerey, Gyorgy, 4,296,072, Cl. 422-254.000.
- Banquy, David L. Process for the production of ammonia and the corresponding synthesis gas. 4,296,085, Cl. 423-359.000.
- Barber-Colman Company: See—
Engelke, Roger P., 4,295,632, Cl. 251-127.000.
- Barker, Ian J.: See—
Stewart, Alistair B.; and Barker, Ian J., 4,296,269, Cl. 13-12.000.

- Barnes, John E.; Goebel, Franz; and McHugh, William T., to GTE Products Corporation. Integrated carbon/insulator structure and method for fabricating same. 4,296,187, Cl. 429-105.000.
- Barr & Stroud Limited: See—
Berry, Peter J., 4,296,325, Cl. 250-347.000.
- Barrett, Diane M.: See—
Graham, Henry A., Jr.; Olekna, David J.; Hawk, Johnna B.; and Barrett, Diane M., 4,296,090, Cl. 424-11.000.
- Bartelt, James T., to Cardiac Pacemakers, Inc. Cardiac pacer testing system. 4,295,468, Cl. 128-419.0PT.
- Barth, Charles F.; Stelson, Thomas S.; and Blake, David E., to TRW Inc. Dressing apparatus with means for detecting grinding wheel wear. 4,295,301, Cl. 51-165.880.
- Barthelmess, Ulrich, to Omya GmbH. Separating machine. 4,295,803, Cl. 417-423.00R.
- Bartmann, Wilhelm; Beck, Gerhard; Lerch, Ulrich; and Konz, Elmar, to Hoechst Aktiengesellschaft. Novel prostaglandin derivatives of the Δ^2 -PGF₂ and Δ^2 -PGE₂ series and process for their manufacture. 4,296,121, Cl. 424-275.000.
- Bartol, Robert J., Jr. Probe for sensing characteristics of electrical devices utilizing a magnetic switch sensor biased by an encircling magnetic biasing means. 4,296,376, Cl. 324-235.000.
- Bascom, Hollis H.; Matweyou, Stephen; Andersen, Alan J.; and Greci, John J., to Orcon Corporation. Fill strand transfer process for making non woven fabrics. 4,295,905, Cl. 156-174.000.
- BASF Aktiengesellschaft: See—
Burstinghaus, Rainer; Kiehs, Karl; and Adolphi, Heinrich, 4,296,108, Cl. 424-210.000.
- Eicken, Karl; Rohr, Wolfgang; Pander, Hans J.; and Wuerzer, Bruno, 4,295,875, Cl. 71-88.000.
- Knopp, Hans; Herion, Dieter; Conzelmann, Gerhard; and Gehrig, Heinz, 4,295,253, Cl. 28-255.000.
- Petersen, Harro; Pai, Panemangalore S.; Klippel, Friedrich; and Reinert, Friedrich, 4,295,846, Cl. 8-186.000.
- Petersen, Harro; Pai, Panemangalore S.; and Reichert, Manfred, 4,295,847, Cl. 8-189.000.
- Rudolf, Peter; Steck, Werner; Jakusch, Helmut; Vaeth, Guenter; and Jaekch, Christof, 4,296,149, Cl. 427-130.000.
- Staiger, Gerhard; and Bronstert, Klaus, 4,296,222, Cl. 526-119.000.
- Steck, Werner; Sarnecki, Wilhelm; Marosi, Laszlo; Ohlinger, Manfred; and Autzen, Horst, 4,295,879, Cl. 75-0.5AA.
- Battan, Howard R.: See—
Bentvelzen, Jozef M.; Meredith, Michael D.; Bepple, Henry; Torregrossa, Louis O.; Battan, Howard R.; and Justice, Dennis H., 4,295,925, Cl. 162-19.000.
- Bentvelzen, Jozef M.; Meredith, Michael D.; Bepple, Henry; Torregrossa, Louis O.; Battan, Howard R.; and Justice, Dennis H., 4,295,926, Cl. 162-57.000.
- Bentvelzen, Jozef M.; Meredith, Michael D.; Bepple, Henry; Torregrossa, Louis O.; Battan, Howard R.; and Justice, Dennis H., 4,295,927, Cl. 162-57.000.
- Battelle Memorial Institute: See—
Roman, Alain; Chevreux, Pierre; Wust, Manfred; and Ehretsmann, Jacques, 4,295,948, Cl. 204-159.230.
- Bauer, Hartwig W.: See—
Ax, Wolfgang; Bauer, Hartwig W.; and Sedlacek, Hans-Harald, 4,296,201, Cl. 435-7.000.
- Bauer, Helmut, to Maschinenfabrik Burckhardt AG. Process and apparatus for intermittent polymerization at elevated pressure. 4,296,221, Cl. 526-87.000.
- Baurain, Roger M.; and Trouet, Andre B. L., to Institut International de Pathologie Cellulaire et Molculaire. Derivatives of doxorubicine, their preparation and use. 4,296,105, Cl. 424-180.000.
- Baxter Travenol Laboratories, Inc.: See—
Kulin, Ralph; and Stauber, Ronald C., 4,295,619, Cl. 248-95.000.
- Bayer Aktiengesellschaft: See—
Boehmke, Gunther, 4,295,859, Cl. 44-51.000.
- Duchardt, Karl H.; and Gehrke, Gunter, 4,296,044, Cl. 260-381.000.
- Hoffmann, Hellmut; Maurer, Fritz; Priesnitz, Uwe; and Riebel, Hans-Jochem, 4,296,241, Cl. 560-124.000.
- Kaspers, Helmut; and Brandes, Wilhelm, 4,296,116, Cl. 424-272.000.
- Pedain, Josef; Uerdingen, Walter; and Muller, Hans-Jurgen, 4,296,230, Cl. 528-67.000.
- Schmidt, Karl-Julius; Schmidt, Friedrich; Siegle, Peter; and Hansen, Gert, 4,296,047, Cl. 260-974.000.
- Schroeder, Josef, 4,296,043, Cl. 260-352.000.
- Stetter, Jorg; Ditzgen, Klaus; Thomas, Rudolf; Eue, Ludwig; and Schmidt, Robert R., 4,295,876, Cl. 71-90.000.
- Walz, Klaus; and Fiegl, Joachim, 4,295,852, Cl. 8-560.000.
- BBC Brown, Boveri & Company Limited: See—
Floessel, Carl D., 4,296,271, Cl. 174-28.000.
- Lang, Ernst; and Niemeyer, Lutz, 4,296,285, Cl. 200-61.080.
- Mastner, Jiri, 4,296,412, Cl. 340-870.190.
- Bearden, Roby, Jr.; and Aldridge, Clyde L., to Exxon Research & Engineering Co. Catalysts hydrocarbon treating processes. 4,295,995, Cl. 252-431.00C.
- Bearden, Roby, Jr.; Aldridge, Clyde L.; and Pine, Lloyd A., to Exxon Research & Engineering Co. Catalysts for hydrocarbon treating processes. 4,295,996, Cl. 252-431.00C.
- Beasley, Denny D., to Beasley Electric Corporation. Motor having electronically switched stator field current and integral torque control. 4,296,362, Cl. 318-138.000.
- Beasley Electric Corporation: See—
Beasley, Denny D., 4,296,362, Cl. 318-138.000.
- Beatrice Foods Company: See—
Ziccarelli, Salvatore F.; Ramos, Rey C.; and Brown, Robert M., 4,296,136, Cl. 426-533.000.
- Beattie, Ralph G.: See—
Seeburger, Harold O.; Beattie, Ralph G.; and Stevens, Violette L., 4,296,220, Cl. 525-507.000.
- Beattie, Thomas R.; Christensen, Burton G.; and Dininno, Frank P., to Merck & Co. Inc. 7-Substituted methyl cephalosporins derivatives and analogues thereof. 4,296,111, Cl. 424-246.000.
- Beaver, Bryan: See—
Fitzgerald, Stella; and Beaver, Bryan, 4,295,292, Cl. 46-201.000.
- Beaver, Terry R.: See—
Kerle, Edward J.; and Beaver, Terry R., 4,296,009, Cl. 260-28.50R.
- Beck, Gerhard: See—
Bartmann, Wilhelm; Beck, Gerhard; Lerch, Ulrich; and Konz, Elmar, 4,296,121, Cl. 424-275.000.
- Beck, Richard A.; and Presley, Glen T., to Parno Corporation. Auxiliary drive system. 4,295,539, Cl. 180-243.000.
- Becker Friedbert; Steinkamp, Johann; and Koenen, Klaus, to Siemens Aktiengesellschaft. Installation for control of a traffic light system by vehicles having an automatic location determination. 4,296,400, Cl. 340-32.000.
- Becker, James; and Neill, Daniel L., to Kelsey Hayes Company. Electric brake system. 4,295,687, Cl. 303-20.000.
- Becker, Paul D.: See—
Rudolph, Paul; and Becker, Paul D., 4,295,864, Cl. 55-40.000.
- Becker, Reinhold; Michel, Wolfgang; and Hartmann, Gerhard, to Hoechst Aktiengesellschaft. Packaging sheath with contents. 4,295,563, Cl. 206-205.000.
- Beckert, Alexander; and Knobbe, Karl-Heinz, to Reinhard Mohn GmbH. Method and apparatus for drying and setting the adhesive on books by vaporization of water using RF energy. 4,296,294, Cl. 219-10.410.
- Beckman Instruments, Inc.: See—
Cowell, Mark J., 4,295,601, Cl. 233-26.000.
- Becton, Dickinson and Company: See—
Christinger, Werner, 4,295,477, Cl. 128-766.000.
- Percarpio, Edward P., 4,295,572, Cl. 215-247.000.
- Quaas, Gary F., 4,295,476, Cl. 128-764.000.
- Vincek, Robert C., 4,295,566, Cl. 206-457.000.
- Beecham Group Limited: See—
Denerley, Paul M., 4,296,032, Cl. 260-245.20R.
- Knudsen, Eric T., 4,295,567, Cl. 206-534.000.
- Behr, R. Douglas: See—
Sutrina, Thomas A.; and Behr, R. Douglas, 4,295,919, Cl. 156-498.000.
- Behringwerke Aktiengesellschaft: See—
Ax, Wolfgang; Bauer, Hartwig W.; and Sedlacek, Hans-Harald, 4,296,201, Cl. 435-7.000.
- Beiersdorf Aktiengesellschaft: See—
Hoppe, Udo; Sauermann, Gerhard; Curtis, Julius; Glantz, Per-Olof; Krasse, Bo; Larsson, Kare; Noren, Borje; Odham, Goran; and Olsson, Jan, 4,296,095, Cl. 424-52.000.
- Beinitz, Karl; and Schubert, Joachim, to Leybold-Heraeus GmbH. Ionization vacuum gauge circuit. 4,296,356, Cl. 315-135.000.
- Belanger, Andre: See—
Poirier, Marc; Gauthier, Michel; and Belanger, Andre, 4,295,939, Cl. 204-1.00T.
- Bell, Clinton C., to Ward Machinery Company, The. Stripping device for removing waste sheet board. 4,295,842, Cl. 493-342.000.
- Bell, Dwain C.; and Anderson, Lloyd E. Roll lifting dollies. 4,295,777, Cl. 414-458.000.
- Bell, Oliver A., Jr.; Gilleland, Randall C.; and Chance, Davey J., to Colt Industries Operating Corp. Adaptive control of gap voltage and power to control servo operation of an electrical discharge machining apparatus. 4,296,302, Cl. 219-69.00G.
- Bell, Robert L., to Besco Industries, Inc. Force responsive transducer. 4,295,376, Cl. 73-724.000.
- Bell Telephone Laboratories, Incorporated: See—
Hafer, Edward H., 4,296,492, Cl. 370-14.000.
- Henry, Paul S., 4,296,374, Cl. 324-77.00B.
- O'Neil, Joseph T.; Quinn, Thomas M.; and Wang, Tse L., 4,296,282, Cl. 179-99.0LS.
- Snyder, Dennis R., 4,295,702, Cl. 339-97.00P.
- Stone, Dale E., 4,296,337, Cl. 307-356.000.
- Wong, William H., 4,296,454, Cl. 361-380.000.
- Bellaff, Leslie. Heat reclaimers. 4,295,519, Cl. 165-11.00R.
- Bemis, Richard S.; and McCartan, Daniel A., to Owens-Corning Fiberglass Corporation. Fibrous glass blowing insulation and process. 4,296,164, Cl. 428-219.000.
- Benedictine Monks Inc.: See—
Reedy, Charles B., 4,295,459, Cl. 126-60.000.
- Beneke, Wolfgang; and Teichmann, Paul, to Trutzschler GmbH & Co. KG. Carding wire brush arrangement. 4,295,248, Cl. 19-113.000.
- Bennett, Alan F.: See—
Clayton, Edward R. C.; and Bennett, Alan F., 4,295,605, Cl. 236-56.000.
- Bennett, Robert W. Fluid-powered submersible sampling pump. 4,295,801, Cl. 417-397.000.
- Benson, Henry E.; and Moravec, Terrence D., to UOP Inc. Apparatus for assembling a plastic mining screen. 4,295,918, Cl. 156-434.000.
- Bentley, Arthur P. Sonic pressure wave surface operated pump. 4,295,799, Cl. 417-240.000.
- Bentvelzen, Jozef M.; Meredith, Michael D.; Bepple, Henry; Torregrossa, Louis O.; Battan, Howard R.; and Justice, Dennis H., to

- Weyerhaeuser Company. Treating pulp with oxygen. 4,295,925, Cl. 162-19.000.
- Bentvelzen, Jozef M.; Meredith, Michael D.; Bepple, Henry; Torregrossa, Louis O.; Battan, Howard R.; and Justice, Dennis H., to Weyerhaeuser Company. Method and apparatus for treating pulp with oxygen. 4,295,926, Cl. 162-57.000.
- Bentvelzen, Jozef M.; Meredith, Michael D.; Bepple, Henry; Torregrossa, Louis O.; Battan, Howard R.; and Justice, Dennis H., to Weyerhaeuser Company. Method and apparatus for treating pulp with oxygen and storing the treated pulp. 4,295,927, Cl. 162-57.000.
- Bepple, Henry: See—
- Bentvelzen, Jozef M.; Meredith, Michael D.; Bepple, Henry; Torregrossa, Louis O.; Battan, Howard R.; and Justice, Dennis H., 4,295,925, Cl. 162-19.000.
- Bentvelzen, Jozef M.; Meredith, Michael D.; Bepple, Henry; Torregrossa, Louis O.; Battan, Howard R.; and Justice, Dennis H., 4,295,926, Cl. 162-57.000.
- Bentvelzen, Jozef M.; Meredith, Michael D.; Bepple, Henry; Torregrossa, Louis O.; Battan, Howard R.; and Justice, Dennis H., 4,295,927, Cl. 162-57.000.
- Berg, Gunter: See—
- Hagberg, Gideon, 4,295,969, Cl. 210-223.000.
- Berg, Ramon A.: See—
- Bjorklund, Lowell L.; Berg, Ramon A.; and Sygnator, Henry A., 4,295,351, Cl. 72-38.000.
- Berger, Dieter; Braun, Franz; Frey, Gunter; Guthlein, Werner; and Kühr, Manfred, to Boehringer Mannheim GmbH. Diagnostic composition for the detection of leukocytes and chromogens useful therein. 4,296,202, Cl. 435-29.000.
- Berger, Eugene, to Solvay & Cie. Polymerization of olefins. 4,296,223, Cl. 526-125.000.
- Berger, Mitchell H.: See—
- Maresca, Louis M.; Gill, Peter J.; and Berger, Mitchell H., 4,296,232, Cl. 528-179.000.
- Bergner, Dieter; Hannesen, Kurt; Müller, Wolfgang; and Schulte, Wilfried, to Hoechst Aktiengesellschaft. Process for the production of liquid chlorine. 4,295,945, Cl. 204-128.000.
- Berlec, Ivan; and McCarty, Lewis V., to General Electric Company. Incandescent lamp. 4,296,352, Cl. 313-315.000.
- Bernier, John A., to Fisher Scientific Company. High-voltage spark source. 4,296,358, Cl. 315-241.00R.
- Berrebi, Claudine; and Manoussos, Georges, to L'Oreal. Process for extracting embryonic calf skin and pharmaceutical compositions containing the same. 4,296,099, Cl. 424-105.000.
- Berry, Peter J., to Barr & Stroud Limited. Scanning mirror position system. 4,296,325, Cl. 250-347.000.
- Besco Industries, Inc.: See—
- Bell, Robert L., 4,295,376, Cl. 73-724.000.
- Betsinger, James D.; and Bailey, James P. Shower apparatus. 4,295,612, Cl. 239-310.000.
- Bey, Roger, to Babcock & Wilcox Company. The Drag ball valve including variable pressure reducing means. 4,295,493, Cl. 138-43.000.
- Beyer, Franz; and Sedlmair, Siegfried, to Siemens Aktiengesellschaft. P-I-N type diode high frequency switch for secondary radar interrogation devices and transponders. 4,296,414, Cl. 343-5.0SW.
- Bezverkhnay, Alexandr M.: See—
- Zhivotov, Yuri G.; Kupchinsky, Igor I.; Plokhuta, Vyacheslav D.; Bezverkhnay, Alexandr M.; Nabutovsky, Samoil I., deceased; and Eroshevskaya, Elena D., administrator, 4,295,387, Cl. 74-573.00F.
- Biela, John A., to Schiffman, Jerome D., deceased. Comb and the method of making same. 4,295,480, Cl. 132-151.000.
- Bigalke, Erhard: See—
- Zimmermann, Frank; Heidemeyer, Paulus; and Bigalke, Erhard, 4,295,551, Cl. 192-0.076.
- Bill, Robert C.; and Ludwig, Lawrence P., to United States of America, National Aeronautics and Space Administration. Composite seal for turbomachinery. 4,295,786, Cl. 415-174.000.
- Binggeli, Bruno K.: See—
- Kiess, Helmut G.; and Binggeli, Bruno K., 4,296,478, Cl. 365-112.000.
- Bingham, Robert M.: See—
- LeBlanc, Ralph W.; and Bingham, Robert M., 4,295,966, Cl. 210-180.000.
- Bishop, John F.; and Bowman, Wayne A., to Eastman Kodak Company. Two-sheet diffusion transfer assemblages and photographic elements. 4,296,195, Cl. 430-215.000.
- Bixby, Guy T., to Gates Rubber Company. The Hose with internal insert member. 4,295,496, Cl. 138-122.000.
- Bjorklund, Lowell L.; Berg, Ramon A.; and Sygnator, Henry A., to Illinois Tool Works Inc. Self-tapping stainless steel screw and method for producing same. 4,295,351, Cl. 72-38.000.
- Black, John W., to Pemco-Kalamazoo, Inc. Disk wheel with resilient bearing support and rigid annular tread mounting surface. 4,295,686, Cl. 301-63.00D.
- Blair, Russell M., to Slickbar, Inc. Floating boom end connectors. 4,295,756, Cl. 405-70.000.
- Blake, Charles H.; and Wood, Donald H., to Outboard Marine Corporation. Speed selection for a direct current permanent magnet motor. 4,296,363, Cl. 318-349.000.
- Blake, David E.: See—
- Barth, Charles F.; Stelson, Thomas S.; and Blake, David E., 4,295,301, Cl. 51-165.880.
- Blanding, Douglass L.: See—
- Montalto, Michael S.; Blanding, Douglass L.; and Smith, Michael R., 4,296,070, Cl. 422-65.000.
- Blanks, James A.: See—
- Moore, W. Edward C.; and Blanks, James A., 4,295,613, Cl. 241-2.000.
- Blasnik, William, to Hardware Designers, Inc. Bearing construction. 4,295,688, Cl. 308-3.800.
- Blevins, Charles W.: See—
- Whitaker, Roger B.; and Blevins, Charles W., 4,296,409, Cl. 340-684.000.
- Blinchow, Donald W.; Cassidy, Kevin H.; and Dominey, Samuel C., Jr., to Tyco Laboratories. Bit pressure gauge for well drilling. 4,296,321, Cl. 250-254.000.
- Blodgett, Camille C. Children's sleeping garments. 4,295,230, Cl. 2-69.500.
- Blodgett, Norman S.: See—
- Nicholson, William H., 4,295,506, Cl. 144-193.00D.
- Blount, David H. Process for the production of poly (polyisocyanate-polyol-alkali metal silicate) solid or foamed products. 4,296,211, Cl. 521-154.000.
- Blue Circle Industries Limited: See—
- Smith, David E., 4,295,933, Cl. 162-168.0NA.
- Blutschkau, Heinke: See—
- Mecke, Norbert; Schmitt, Franz U.; Schrader, Karl-Heinz; and Blutschkau, Heinke, 4,296,150, Cl. 427-164.000.
- Boart International Limited: See—
- Holmberg, John M., 4,295,751, Cl. 403-306.000.
- Bocquet, Gilbert: See—
- Droux, Michel; and Bocquet, Gilbert, 4,295,871, Cl. 65-3.410.
- Bodart, Robert; and Werts, Jean P. A. R. J., to U.S. Philips Corporation. Method of and arrangement for regenerating start-stop signals. 4,296,493, Cl. 370-48.000.
- Boden, Richard M., to International Flavors & Fragrances Inc. Flavoring with 1-ethoxy-1-ethanol acetate. 4,296,137, Cl. 426-534.000.
- Boden, Richard M., to International Flavors & Fragrances Inc. Flavoring with 1-n-butoxy-1-ethanol acetate. 4,296,138, Cl. 426-534.000.
- Bodenseewerk Perkin-Elmer & Co., GmbH: See—
- Huber, Bernhard, 4,295,854, Cl. 23-230.0PC.
- Boehmke, Gunther, to Bayer Aktiengesellschaft. Fuels and heating oils, a process for their preparation and their use. 4,295,859, Cl. 44-51.000.
- Boehringer Ingelheim GmbH: See—
- Koppe, Herbert; Mentrup, Anton; Renth, Ernst-Otto; Schromm, Kurt; Hoefke, Wolfgang; and Muacevic, Gojko, 4,296,117, Cl. 424-273.00B.
- Boehringer Mannheim: See—
- Weiss, Erich; and Ungermann, Dieter, 4,296,071, Cl. 73-864.110.
- Boehringer Mannheim GmbH: See—
- Berger, Dieter; Braun, Franz; Frey, Gunter; Guthlein, Werner; and Kühr, Manfred, 4,296,202, Cl. 435-29.000.
- Boeing Company, The: See—
- Adamski, John L., 4,296,327, Cl. 250-423.00R.
- Boldt, Wayne A. Liquid egg blend. 4,296,134, Cl. 426-250.000.
- Bolte, Steven B.: See—
- Gruber, Robert J.; Bolte, Steven B.; Knapp, John F.; Ims, Dale R.; and Lewis, Richard B., 4,296,192, Cl. 430-109.000.
- Bommaraju, Tilak V.; Dexter, Theodore H.; and Rader, Charles G., to Hooker Chemicals & Plastics Corp. Film-coated cathodes for halate cells. 4,295,951, Cl. 204-242.000.
- Bond, Ned J., III. Pneumatically operated grain handling apparatus. 4,295,614, Cl. 241-34.000.
- Boogers, Wilhelmus P. L., to B.V. Arencio P.M.B. Method and device for manufacturing cigars. 4,295,479, Cl. 131-60.000.
- Book, Harold M. Diaphragm and ball valve. 4,295,488, Cl. 137-414.000.
- Boone, Jacob J.: See—
- Terry, Robert R.; and Boone, Jacob J., 4,295,573, Cl. 215-348.000.
- Bopst, John H., III. System for controlling the movement and locking of tape apparatus. 4,295,921, Cl. 156-577.000.
- Borg-Warner Corporation: See—
- McIntosh, Arthur M., 4,295,798, Cl. 417-212.000.
- Borowitz, Raymond P. Side dispensing closure. 4,295,584, Cl. 222-519.000.
- Borst, Gaylord M., to Outboard Marine Corporation. Inboard-outboard driving mechanism including a hydraulically assisted steering system. 4,295,833, Cl. 440-63.000.
- Borsting, Otto W.: See—
- Card, Lorin P.; and Borsting, Otto W., 4,295,630, Cl. 251-14.000.
- Bortolussi, Everest J. Magnetic safety clutch for rotary lawnmower. 4,295,327, Cl. 56-11.300.
- Borzatta, Valerio; Cristofori, Manlio; Morotti, Mauro; and Mascellani, Giuseppe, to Alpha Farmaceutici S.p.A. Derivatives of benzoyl-phenoxyalkanoic acids having normolipemizing activity. 4,296,125, Cl. 424-315.000.
- Bosca, Bernard: See—
- Maurel, Pierre; Nicolas, Francois; and Bosca, Bernard, 4,296,073, Cl. 423-3.000.
- Bosch, Erhard: See—
- Innertsberger, Ernst; Sommer, Oswin; Bosch, Erhard; Müller, Johann; and Schiller, August, 4,296,228, Cl. 528-33.000.
- Boswell, George T., to Frontier Industries, Inc. Toy projectile. 4,295,290, Cl. 46-74.00C.
- Bott, John A. Article carrier for automotive vehicles. 4,295,587, Cl. 224-321.000.
- Bottiglia, Augusto, to Sio-Societa per l'Industria Dell'Ossigeno e di Altri Gas. Method and device for welding protected metal parts. 4,296,300, Cl. 219-61.700.
- Boucher, Pierre, to Etablissements Boucher Freres. Device for holding a workpiece to be machined in a specific position in relation to a machine-tool on which it may be fixed. 4,295,641, Cl. 269-136.000.

- Boudreau, Archie E. Milking apparatus. 4,295,490, Cl. 137-595.000.
- Boulanger, Henry J.; Lowell, Victor; and Whipple, Elliot, to Texas Instruments Incorporated. Weatherproofed condition responsive switch. 4,296,287, Cl. 200-83.00P.
- Boultinghouse, Harold D., to Phillips Petroleum Company. Fluorinated polymeric surfaces. 4,296,151, Cl. 427-255.100.
- Boussey, Bernard: See—
- Chielens, Alain; and Boussey, Bernard, 4,295,825, Cl. 432-116.000.
- Boussuges, Pierre, to Neyrpic. Starting of pumps or turbopumps. 4,295,782, Cl. 415-1.000.
- Bouvet, Pierre; and Lalu, Jean-Pierre, to Produits Chimiques Ugine Kuhlmann. Polyfluorinated sulfonamides. 4,296,034, Cl. 260-326.820.
- Bovone, Luigi. Apparatus for automatically producing glazed insulating window or door panels. 4,295,920, Cl. 156-557.000.
- Bowden, Edgar A., to Mobil Oil Corporation. On-board analog reproducer unit for ocean-bottom seismometer. 4,296,442, Cl. 360-6.000.
- Bowman, Arthur F.: See—
- Smith, Don H.; Bowman, Arthur F.; and Junk, Norman M., 4,295,424, Cl. 102-322.000.
- Bowman, Wayne A.: See—
- Bishop, John F.; and Bowman, Wayne A., 4,296,195, Cl. 430-215.000.
- Bowsky, Benjamin, to Emerson Electric Co. Hermetic refrigeration terminal. 4,296,275, Cl. 174-152.0GM.
- Brady, Michael B. C.: See—
- Esterson, Maurice; and Brady, Michael B. C., 4,296,385, Cl. 331-90.000.
- Brand, Derek A.; and Brand, Derek R., to Tyco Industries, Inc. Pick-up shoe and motor contact assembly for toy vehicle. 4,295,295, Cl. 46-259.000.
- Brand, Derek R.: See—
- Brand, Derek A.; and Brand, Derek R., 4,295,295, Cl. 46-259.000.
- Brandes, Wilhelm: See—
- Kaspers, Helmut; and Brandes, Wilhelm, 4,296,116, Cl. 424-272.000.
- Brandt, Howard C.; and Grabowski, Leonard R., to General Motors Corporation. Ball nut and screw assembly with travel limit stop. 4,295,384, Cl. 74-424.8NA.
- Brandwijk, Willem; and Dam, Herman, to IHC Holland N.V. Support frame for motor, pump and suction tube of a suction dredger. 4,295,286, Cl. 37-58.000.
- Braun, Erwin: See—
- Schuler, Peter; and Braun, Erwin, 4,295,857, Cl. 23-301.000.
- Braun, Franz: See—
- Berger, Dieter; Braun, Franz; Frey, Gunter; Guthlein, Werner; and Kühr, Manfred, 4,296,202, Cl. 435-29.000.
- Braun, Helmut; Rinno, Helmut; and Rauterkus, Karl J., to Hoechst Aktiengesellschaft. Vinyl polymer with acetylacetoxy groups, process for its manufacture and an agent obtained thereof. 4,296,226, Cl. 526-316.000.
- Breen, John J., to Eastman Kodak Company. Camera mechanism employing a multifunction control member. 4,295,715, Cl. 354-25.000.
- Brendel, Thomas E.: See—
- Hannett, William J.; Brendel, Thomas E.; and Wilson, David S., 4,295,344, Cl. 62-324.500.
- Breslin, Michael D., to Nalco Chemical Company. Phenolic compounds as viscosity preservatives during hypochlorite pulp bleaching. 4,295,928, Cl. 162-73.000.
- Bretl, Wayne E.: See—
- d'Hautecourt, Alain H.; Bretl, Wayne E.; and Lee, Ronald B., 4,296,435, Cl. 358-166.000.
- Bricher, Charles W.; and Herpers, Ferdinand J., to Tennant Company. Scarifying machine. 4,295,274, Cl. 30-347.000.
- Bridgestone Tire Company Limited: See—
- Kawaguchi, Yasuyosi; Shimotake, Munetoshi; and Yamamoto, Fujio, 4,295,512, Cl. 152-354.00R.
- Ohashi, Takashi; Okoyama, Toru; and Arai, Katsuhiko, 4,296,170, Cl. 428-313.000.
- Saito, Tasuku; Noma, Tutomu; Matsunaga, Tsutomu; Naito, Nagayoshi; Tanaka, Chiaki; and Hiratsuka, Motoki, 4,295,652, Cl. 273-235.00R.
- Brink, Dirk Marinus: See—
- Foxcroft, Garth, 4,295,510, Cl. 152-220.000.
- Brinkerhoff, VerDon C. Regenerative absorption engine apparatus and method. 4,295,335, Cl. 60-673.000.
- Bristol, Robert G., to Emhart Industries, Inc. Capacitive scheme for measuring the level of a liquid. 4,295,370, Cl. 73-304.00C.
- British Broadcasting Corporation: See—
- Drewery, John O.; and Storey, Richard, 4,296,434, Cl. 358-105.000.
- British Chrome & Chemicals Ltd.: See—
- Swales, Danvers A.; and Marshall, Michael A., 4,296,076, Cl. 423-53.000.
- Bronstert, Klaus: See—
- Staiger, Gerhard; and Bronstert, Klaus, 4,296,222, Cl. 526-119.000.
- Brookfield Athletic Shoe Company, Inc.: See—
- Landay, David L.; and Wolf, Alvan H., 4,295,655, Cl. 280-11.200.
- Brooklyn Union Gas Company: See—
- McGowan, John B.; and Trimble, John, 4,295,494, Cl. 138-89.000.
- Brown, Frank, Jr., to Sunroc Corporation. Wall mounted drinking fountain with push bar actuator. 4,295,609, Cl. 239-29.000.
- Brown Group, Inc.: See—
- Doerer, Daniel M.; and Brunkhorst, Lloyd E., 4,296,053, Cl. 264-26.000.
- Brown, Robert M.: See—
- Zicarelli, Salvatore F.; Ramos, Rey C.; and Brown, Robert M., 4,296,136, Cl. 426-533.000.
- Brown, Sheldon H.: See—
- Garcia, Felix, Jr.; Hergert, Roger A.; Mann, Don C.; and Brown, Sheldon H., 4,296,448, Cl. 360-135.000.
- Brown, Thomas R.: See—
- Natzke, Ronald C.; and Brown, Thomas R., 4,295,287, Cl. 37-103.000.
- Brown, William E.: See—
- Weisenborn, Frank L.; Brown, William E.; and Meyers, Edward, 4,296,101, Cl. 424-119.000.
- Browne, Leslie J., to Ciba-Geigy Corporation. Pyridylalkylamines. 4,296,115, Cl. 424-263.000.
- Brunkhorst, Lloyd E.: See—
- Doerer, Daniel M.; and Brunkhorst, Lloyd E., 4,296,053, Cl. 264-26.000.
- Brunner, Herbert, to Nuken GmbH. Apparatus for conditioning bioinert waste. 4,295,745, Cl. 366-302.000.
- Brunswick Corporation: See—
- Mapes, Charles W.; and Snyder, Richard H., 4,295,835, Cl. 440-78.000.
- Buchi, Georges H.: See—
- Fehr, Charles; Ohloff, Gunther; and Buchi, Georges H., 4,296,258, Cl. 568-364.000.
- Buchta, Ervin A., to FMC Corporation. Manual override control for double-acting actuator. 4,295,390, Cl. 74-625.000.
- Buck, Gordon K.; and Kozin, Cynthia H., to Harris Corporation. Apparatus for diagnosing faults in individual cylinders in an internal combustion engine. 4,295,363, Cl. 73-117.300.
- Buckingham, James W., to Owens-Illinois, Inc. Thermoplastic gob feeding and transfer method and apparatus. 4,296,061, Cl. 264-138.000.
- Buckley, Alan J.; and Singer, Michael, to Imperial Chemical Industries Limited. Method for the control of micro-organisms. 4,295,887, Cl. 106-18.330.
- Budd Company, The: See—
- Dickhart, William W., III; and Marvin, Richard H., 4,295,428, Cl. 105-168.000.
- Eggert, Walter S., Jr., 4,295,790, Cl. 416-226.000.
- Bugaut, Andree: See—
- Grollier, Jean F.; Bugaut, Andree; Andriol, Patrick; and Fourcader, Chantal, 4,295,848, Cl. 8-421.000.
- Bugdahl, Volker; Morlock, Gerhard; Reidt, Werner; and Kerschner, Emil, to Degussa Aktiengesellschaft. Binder for coating compositions and its use. 4,296,006, Cl. 260-23.0EP.
- Bulgakov, Evgeny G.: See—
- Anisimov, Vyacheslav I.; Bulgakov, Evgeny G.; Gurin, Vasily N.; Radjuevich, Leonid V.; Trishevsky, Igor S.; Trishevsky, Oleg I.; Kheifets, Grigory R.; and Jurchenko, Anatoly B., 4,295,353, Cl. 72-180.000.
- Bulmer, J. Stewart. Hydraulic press. 4,295,358, Cl. 72-453.060.
- Bumbalek, Alois J., to Hermann Wegener Schiffgraben. Method for preparing a filter medium. 4,296,056, Cl. 264-49.000.
- Bunch, Jesse C. Energy concentrator system. 4,295,462, Cl. 126-424.000.
- Bunker Ramo Corporation: See—
- Chow, Weichien, 4,295,698, Cl. 339-59.00R.
- Bunning, Robin G.: See—
- Payne, Alan; and Bunning, Robin G., 4,295,776, Cl. 414-405.000.
- Burk, Emmett H., Jr.: See—
- Sun, Jui-Yuan; Burk, Emmett H., Jr.; Yoo, Jin S.; and Masologites, George P., 4,295,858, Cl. 44-1.05R.
- Burke, Michael R. Tie-down structure. 4,295,765, Cl. 410-101.000.
- Burnett, Roy E.: See—
- Reeves, H. Neal; Burnett, Roy E.; Denham, Leslie R.; and Shields, George E., 4,295,542, Cl. 181-108.000.
- Burnop, Victor C. Production of overbased magnesium detergent additives. 4,295,981, Cl. 252-33.400.
- Burns, Carmen D., to National Semiconductor Corporation. Apparatus and process for laminating composite tape. 4,295,912, Cl. 156-324.000.
- Burns, Lyle D., to Phillips Petroleum Company. Motor fuel. 4,295,861, Cl. 44-63.000.
- Burns, Lyle D., to Phillips Petroleum Company. Motor fuel. 4,295,862, Cl. 44-72.000.
- Burroughs Corporation: See—
- Nahar, Rathindra; and Dietze, Robert H., 4,295,645, Cl. 271-34.000.
- Reid, Gilbert R., 4,296,456, Cl. 361-403.000.
- Burstinghaus, Rainer; Kiehs, Karl; and Adolphi, Heinrich, to BASF Aktiengesellschaft. 2,2-Dichlorocyclopropyl-methyl-phosphoric acid derivatives. 4,296,108, Cl. 424-210.000.
- Bursztajn, Jacques, to Thomson CSF. Device for measuring the quality of a digital radio link. 4,296,495, Cl. 371-22.000.
- Bushnell, Brian J.; Cavalla, John F.; Shepherd, Robin G.; and White, Alan C., to John Wyeth & Brother Limited. Process for preparing hexahydroazepine, piperidine and pyrrolidine derivatives. 4,296,029, Cl. 260-239.30R.
- Butler Manufacturing Co.: See—
- Flachbarth, Charles T., 4,295,575, Cl. 220-3.920.
- Buzzi, Fabio; and Carniti, Sergio, to Carl Hurth Maschinen- und Zahnradfabrik GmbH & Co. Drive mechanism for a watercraft with a surface propeller. 4,295,834, Cl. 440-76.000.
- B.V. Arencio P.M.B.: See—
- Boogers, Wilhelmus P. L., 4,295,479, Cl. 131-60.000.

- C.I.S.E. Centro Informazioni Studi Esperienze S.p.A.: See—
Mezzetti, Sergio; Pizzolati, Pierluigi; and Svelto, Francesco, 4,296,318, Cl. 250-225.000.
- Cahen, David: See—
Hodes, Gary; Cahen, David; and Manassen, Joost, 4,296,188, Cl. 429-111.000.
- Cain, Robert L., to Robinair Manufacturing Corporation. Selective mode multi-stage vacuum pump. 4,295,794, Cl. 417-62.000.
- Cale, Albert D., Jr., to A. H. Robins Company, Incorporated. 4,5-Dihydro-3,3-diphenyl-4-hydrocarbylaminoethylfuran-2(3H) ones. 4,296,037, Cl. 260-343.600.
- Calspan Corporation: See—
Pelton, Frank M.; Miller, Clyde A.; and Leney, Thomas F., 4,296,415, Cl. 343-16.00M.
- Calvert, Rodney K., to Mead Corporation, The. Carton with carrying strap. 4,295,598, Cl. 229-52.0AL.
- Camirand, Wayne M.; Randall, John M.; and Hautala, Earl, to United States of America, Agriculture. Melting icebergs to produce fresh water and mechanical energy. 4,295,333, Cl. 60-641.600.
- Cammarata, Jacob J., to Medtronic, Inc. Electrode positioning system. 4,295,270, Cl. 29-828.000.
- Campbell, Charles A.: See—
Wynosky, Thomas A.; and Campbell, Charles A., 4,295,611, Cl. 239-265.370.
- Campbell, Christopher J.: See—
Johnson, Harry D.; Campbell, Christopher J.; Turner, Thomas O.; Poole, Carl W.; Gilmore, James E.; and Thomas, James R., 4,295,337, Cl. 62-54.000.
- Campbell, Crom B. Producer gas fueled burner system and drying apparatus. 4,295,822, Cl. 432-29.000.
- Campbell, Henry F., to Campbell Research Corporation. Building construction. 4,295,312, Cl. 52-408.000.
- Campbell Research Corporation: See—
Campbell, Henry F., 4,295,312, Cl. 52-408.000.
- Canadian Patents & Dev. Ltd.: See—
Moore, William J. M.; Kusters, Norbert L.; and So, Eddy, 4,296,369, Cl. 323-218.000.
- Cannavan, Christopher J. Sugar cane harvester. 4,295,325, Cl. 56-13.900.
- Canon Kabushiki Kaisha: See—
Eida, Tsuyoshi; Haruta, Masahiro; Yano, Yasuhiro; Matsufuji, Yoji; and Ohta, Tokuya, 4,295,889, Cl. 106-22.000.
- Hara, Toshitami; Sato, Yashushi; Takatori, Yasushi; and Shirato, Yoshiaki, 4,296,421, Cl. 346-140.00R.
- Ishiwatari, Masumi, 4,295,712, Cl. 350-344.000.
- Momiyama, Kikuo; and Kumazawa, Kenichi, 4,295,723, Cl. 354-155.000.
- Shinmi, Akira; Fukui, Masahisa; Hara, Toshitami; Shirato, Yoshiaki; and Hajimoto, Yoshioki, 4,296,309, Cl. 219-216.000.
- Takashi, Uchiyama; Tsunekawa, Tokuchi; and Kiyohara, Takehiko, 4,295,722, Cl. 354-146.000.
- Canron Corp.: See—
Rhodes, Curtis A.; Jur, Tim A.; and Keating, Donald A., 4,295,259, Cl. 29-402.180.
- Caplin, Peter B.; and Harman, Maurice, to Energy Equipment Co. Ltd., The. Method and means for controlling the operation of fluidized bed combustion apparatus. 4,295,817, Cl. 431-7.000.
- Card, Lorin P.; and Borsting, Otto W., to Greer Hydraulics, Incorporated. Fail-safe actuator and hydraulic system incorporating the same. 4,295,630, Cl. 251-14.000.
- Cardenas, Carlos G.; and Din, Zia U., to SCM Corporation. Process for producing dihydrocarvone geometric isomers. 4,296,257, Cl. 568-361.000.
- Cardenas, Carlos G.: See—
Ho, T. L.; Din, Zia U.; and Cardenas, Carlos G., 4,296,251, Cl. 562-506.000.
- Cardiac Pacemakers, Inc.: See—
Bartelt, James T., 4,295,468, Cl. 128-419.0PT.
- Carl Hurth Maschinen- und Zahnradfabrik GmbH & Co.: See—
Buzzi, Fabio; and Carniti, Sergio, 4,295,834, Cl. 440-76.000.
- Carl Kurt Walther GmbH & Co. KG: See—
Walther, Carl K.; and Temme, Karl, 4,295,300, Cl. 51-163.200.
- Carle, Pierre R.: See—
Joly, Robert; Pavan, Charles; and Carle, Pierre R., 4,296,091, Cl. 424-18.000.
- Carlson, Alfred D.: See—
Herpers, Ferdinand J.; Kroll, Harley E.; Carlson, Alfred D.; and Dodge, Paul D., 4,295,244, Cl. 15-320.000.
- Carlson, David H. J., to UOP Inc. Catalytic composite, method of manufacture and process for use. 4,295,993, Cl. 252-430.000.
- Carlson, Lawrence E., to Aluminum Company of America. Nestable building wall panel. 4,295,316, Cl. 52-588.000.
- Carmody, Michael, to Baker International Corporation. Selective lock with setting and retrieving tools. 4,295,528, Cl. 166-315.000.
- Carniti, Sergio: See—
Buzzi, Fabio; and Carniti, Sergio, 4,295,834, Cl. 440-76.000.
- Carrier Corporation: See—
Hannett, William J.; Brendel, Thomas E.; and Wilson, David S., 4,295,344, Cl. 62-324.500.
- Nakahama, Syuhei; and Yamashita, Etsu, 4,296,308, Cl. 219-136.000.
- Carroll, Noel; and Carroll, William F. Revolving security door. 4,295,297, Cl. 49-42.000.
- Carroll, William F.: See—
Carroll, Noel; and Carroll, William F., 4,295,297, Cl. 49-42.000.
- Carson, Don B., to UOP Inc. Process for the manufacture of ethanol from ethylene. 4,296,261, Cl. 568-890.000.
- Casciotti, Albert: See—
Vanderheyden, Eric E.; and Casciotti, Albert, 4,296,390, Cl. 333-182.000.
- Cassedy, Kevin H.: See—
Blinchow, Donald W.; Cassedy, Kevin H.; and Dominey, Samuel C., Jr., 4,296,321, Cl. 250-254.000.
- Catanzarite, Vincent O. Coating for lithium anode, thionyl chloride active cathode electrochemical cell. 4,296,185, Cl. 429-48.000.
- Caterpillar Tractor Co.: See—
Cemenska, Richard A.; and Grim, George B., 4,295,449, Cl. 123-300.000.
- Ellington, Rayburn P., III, 4,295,276, Cl. 33-181.00R.
- Garman, Ronald H., 4,295,306, Cl. 52-208.000.
- Rubenthaler, Randall J., 4,295,691, Cl. 308-238.000.
- Sommars, Mark F., 4,295,521, Cl. 165-69.000.
- Stevens, Samuel B., 4,295,916, Cl. 156-397.000.
- Cavalla, John F.: See—
Bushnell, Brian J.; Cavalla, John F.; Shepherd, Robin G.; and White, Alan C., 4,296,029, Cl. 260-239.30R.
- Ceintrey, Marcel. Compositions for use in seal coats. 4,296,167, Cl. 428-284.000.
- Celanese Corporation: See—
Chen, John C.; and Davis, Herbert L., 4,296,058, Cl. 264-78.000.
- Rhum, David, 4,296,225, Cl. 526-260.000.
- Warner, Steven B., 4,295,844, Cl. 8-115.500.
- Cemenska, Richard A.; and Grim, George B., to Caterpillar Tractor Co. Rotary fuel injection with sequencing. 4,295,449, Cl. 123-300.000.
- Centre de Recherches Metallurgiques-Centrum voor Research in de Metallurgie: See—
Defourny, Jacques, 4,296,304, Cl. 219-86.410.
- Economopoulos, Marios, 4,295,902, Cl. 148-144.000.
- Centro Ricerche Fiat S.p.A.: See—
Milana, Emilio; and Rasello, Franco, 4,296,333, Cl. 250-572.000.
- Centromini Company Establishment: See—
Haas, Eduard, 4,295,579, Cl. 221-229.000.
- Certain-teed Corporation: See—
Kopenhaver, Robert, 4,295,445, Cl. 118-695.000.
- CHA Industries: See—
Mahl, Gunard O. B., 4,296,153, Cl. 427-444.000.
- Chambers Corporation: See—
Scherer, Richard M., 4,295,261, Cl. 29-451.000.
- Champion International Corporation: See—
Cooley, James; and Fogle, Ozzie, 4,295,910, Cl. 156-314.000.
- Chance, Davey J.: See—
Bell, Oliver A., Jr.; Gilleland, Randall C.; and Chance, Davey J., 4,296,302, Cl. 219-69.00G.
- Charbonnages de France: See—
Nomine, Michel; and Chelu, Gerard, 4,296,081, Cl. 423-245.000.
- Checko, John C. Apparatus for applying sealant material to a work-piece. 4,295,914, Cl. 156-357.000.
- Chelu, Gerard: See—
Nomine, Michel; and Chelu, Gerard, 4,296,081, Cl. 423-245.000.
- Chen, John C.; and Davis, Herbert L., to Celanese Corporation. Process for enhancing the uniformity of dye uptake of false twist texturized polyethylene terephthalate fibrous materials. 4,296,058, Cl. 264-78.000.
- Chevreaux, Pierre: See—
Roman, Alain; Chevreaux, Pierre; Wust, Manfred; and Ehretsmann, Jacques, 4,295,948, Cl. 204-159.230.
- Chevron Research: See—
Edwards, Laroy H., 4,295,874, Cl. 71-67.000.
- Hudson, Robert L., 4,296,022, Cl. 260-42.460.
- Chevron Research Company: See—
Farnham, Robert A., 4,295,936, Cl. 202-153.000.
- Chielens, Alain; and Boussekey, Bernard, to Fives-Cail Babcock. System for the protection of the delivery end of a rotary kiln. 4,295,825, Cl. 432-116.000.
- Childs, Michael E., to UOP Inc. Multifunctional gasoline additives. 4,295,860, Cl. 44-63.000.
- Chiyoda Kako Kensetsu Kabushiki Kaisha: See—
Kurima, Akinori; Iwase, Yasuhiro; and Kimiwada, Tadao, 4,295,967, Cl. 210-189.000.
- Chlorine Engineers Corp., Ltd.: See—
Fuseya, Shigeaki; and Ichisaka, Teruo, 4,295,953, Cl. 204-257.000.
- Chow, Weichien, to Bunker Ramo Corporation. Electrical connector housing. 4,295,698, Cl. 339-59.00R.
- Christensen, Burton G.; Johnston, David B. R.; and Firestone, Raymond A., to Merck & Co., Inc. 7-(or 6-) Substituted-7-(or 6-)acylimino cephalosporin (or penicillin) compounds. 4,296,236, Cl. 542-420.000.
- Christensen, Burton G.: See—
Beattie, Thomas R.; Christensen, Burton G.; and Dinno, Frank P., 4,296,111, Cl. 424-246.000.
- Christinger, Werner, to Becton, Dickinson and Company. Multiple sampling device having molded valve and hub. 4,295,477, Cl. 128-766.000.
- Chupp, John P.: See—
Middlebrook, Robert E.; Harvey, George R.; and Chupp, John P., 4,296,254, Cl. 564-214.000.
- Church, Allen R.: See—
Jaquith, Jack B.; and Church, Allen R., 4,296,140, Cl. 426-575.000.
- Ciba-Geigy AG: See—
Trautweiler, Franz, 4,296,198, Cl. 430-403.000.

- Ciba-Geigy Corporation: See—
Browne, Leslie J., 4,296,115, Cl. 424-263.000.
- Di Benedetto, Marianne, 4,296,005, Cl. 260-18.0EP.
- Gutekunst, Ferdinand; and Schmid, Rolf, 4,296,231, Cl. 528-93.000.
- Haberli, Roland; Mollet, Hans; and Scherer, Gustaaf, 4,295,850, Cl. 8-524.000.
- Kunz, Walter; Eckhardt, Wolfgang; and Hubele, Adolf, 4,296,118, Cl. 424-273.00P.
- Neumann, Konrad; Schenkenberger, Ernst; and Resch, Friedrich, 4,295,851, Cl. 8-524.000.
- Petitpierre, Jean C.; and Garner, Robert, 4,295,663, Cl. 282-27.500.
- Sallmann, Alfred; and Goschke, Richard, 4,296,128, Cl. 424-309.000.
- Ciliberti, Frank L., Jr., to Duracell International Inc. One piece connector. 4,295,705, Cl. 339-220.00R.
- Cinzori, Robert J.: See—
Kern, Mark T.; and Cinzori, Robert J., 4,296,324, Cl. 250-339.000.
- Cioca, Gheorge; and Siegler, Marcel, to Seton Company. Method of preparing soluble collagen fibers. 4,295,894, Cl. 106-155.000.
- Cisternino, Andrew J.: See—
Cottrill, William P.; and Cisternino, Andrew J., 4,295,775, Cl. 414-375.000.
- Citizen Watch Company Limited: See—
Nakayama, Yasuaki, 4,296,488, Cl. 368-80.000.
- Nishikubo, Yasuhiko, 4,296,490, Cl. 368-87.000.
- Citron, Jeffrey M. Flexible V-shaped solar tracking concentrating solar energy collector. 4,295,463, Cl. 126-425.000.
- Clark, Eugene A.; and Zubkewych, Morris. Football gloves. 4,295,229, Cl. 2-20.000.
- Clark, Lancelot P., to Clarks Limited. Footwear. 4,295,238, Cl. 12-142.0RS.
- Clarke, Charles J., Jr.: See—
Woods, Rodney G.; Clarke, Charles J., Jr.; and Sodergren, Robert C., 4,296,464, Cl. 364-200.000.
- Clarks Limited: See—
Clark, Lancelot P., 4,295,238, Cl. 12-142.0RS.
- Clayton, Edward R. C.; and Bennett, Alan F., to Spirax Sarco Limited. Steam traps. 4,295,605, Cl. 236-56.000.
- Cleban, Jean C., to Societe Europeenne de Propulsion. Flexible union with passive compensation. 4,295,671, Cl. 285-223.000.
- Clemens, Lawrence G., to Phillips Petroleum Company. Tilt alarm in a seismic exploration system. 4,296,485, Cl. 367-77.000.
- Clemens, Ronald: See—
Maier, Martin; Purrer, Josef; and Clemens, Ronald, 4,295,323, Cl. 56-10.200.
- Clements, Lloyd W. Irrigation sprinklers. 4,295,610, Cl. 239-230.000.
- Clouser, Michael T., to Emhart Industries, Inc. Means controlling a flue damper. 4,295,603, Cl. 236-1.00G.
- Cohen, Jacques: See—
Ingrain, Raymond A.; and Cohen, Jacques, 4,296,396, Cl. 337-66.000.
- Cole, Marc. Desalination with improved chlor-alkali production by electrolytic dialysis. 4,295,950, Cl. 204-180.00P.
- Coles, Carl R., to Zero-Seal, Inc. Pressure-compensated diaphragm seals for actuators, with self-equalization. 4,295,653, Cl. 277-2.000.
- Colgate-Palmolive Company: See—
Pierce, Robert C., 4,296,096, Cl. 424-52.000.
- Collura, Peter C.: See—
Baker, Thomas R.; and Collura, Peter C., 4,295,839, Cl. 493-143.000.
- Colt Industries Operating Corp.: See—
Bell, Oliver A., Jr.; Gilleland, Randall C.; and Chance, Davey J., 4,296,302, Cl. 219-69.00G.
- Combustion Engineering, Inc.: See—
Anthony, Andrew J., 4,295,935, Cl. 376-285.000.
- Comizzoli, Robert B.; and Vibronex, Robert D., to RCA Corporation. Method of detecting a thin insulating film over a conductor. 4,296,370, Cl. 324-54.000.
- Commissariat a l'Energie Atomique: See—
LeClou, Andre, 4,295,620, Cl. 248-154.000.
- Compact Video Systems Inc.: See—
Holland, Kenneth F., 4,296,431, Cl. 358-12.000.
- Conair Corporation: See—
Tomaro, Patrick M.; deceased, 4,295,283, Cl. 34-97.000.
- Concast AG: See—
Gloor, Hans, 4,295,278, Cl. 33-182.000.
- Condie, Richard M., to University of Minnesota, The Regents of the. Pure intravenous human and animal gamma globulins. 4,296,027, Cl. 260-112.00B.
- Conoco Inc.: See—
Jones, Emrys H., Jr.; and Lauer, Stephen D., 4,295,536, Cl. 175-214.000.
- Motz, Kaye L., 4,295,980, Cl. 252-8.55D.
- Ziegenhain, William C., 4,296,057, Cl. 264-63.000.
- Conradty GmbH & Co. Metallelektroden KG: See—
Kozio, Konrad; and Wenk, Erich, 4,295,942, Cl. 204-96.000.
- Construction Specialties, Inc.: See—
Lynn-Jones, David M.; and Stewart, R. Gordon, 4,295,315, Cl. 52-573.000.
- Conti, Allen C. Tube with weakened side wall segment. 4,296,157, Cl. 428-36.000.
- Continental Group, Inc., The: See—
Gerber, Howard L., 4,296,293, Cl. 219-8.500.
- Control Data Corporation: See—
Hutson, Maurice L., 4,296,477, Cl. 364-900.000.
- Conzelmann, Gerhard: See—
Knopp, Hans; Herion, Dieter; Conzelmann, Gerhard; and Gehrig, Heinz, 4,295,253, Cl. 28-255.000.
- Cook, Gerald L.: See—
Albrecht, Robert D.; Presley, Michael; Waller, William E.; Cook, Gerald L.; and Presley, William E., 4,295,708, Cl. 350-289.000.
- Cookson, Alan H., to United States of America, Energy. High voltage bushing having weathered and surrounding stress relief collar. 4,296,274, Cl. 174-142.000.
- Cooley, James; and Fogle, Ozzie, to Champion International Corporation. Process for production of vinyl film-cellulosic laminates and laminates produced thereby. 4,295,910, Cl. 156-314.000.
- Cooper, Alan: See—
Nagabhushan, Tattanahalli L.; and Cooper, Alan, 4,296,242, Cl. 560-160.000.
- Cooper, Julius, to Ideal Toy Corporation. Toy miniature vehicle racing game. 4,295,649, Cl. 273-86.00B.
- Copal Company Limited: See—
Inoue, Nobuyoshi, 4,295,726, Cl. 354-246.000.
- Cordts, Howard P.; and Karloske, Joan E., to Freeman Chemical Corporation. Method of making glass fiber reinforced laminate. 4,295,907, Cl. 156-246.000.
- Corinco, Inc.: See—
Frantello, Alfred A.; and Kefauver, Lester R., 4,295,324, Cl. 56-12.700.
- Cornell, William D., to Sherwood Medical Industries Inc. Blood sample collection and phase separation device. 4,295,974, Cl. 210-789.000.
- Corning Glass Works: See—
Luers, George A., 4,295,872, Cl. 65-30.110.
- Wu, Che-Kuang, 4,296,479, Cl. 365-119.000.
- Cosentino, Cesare C.: See—
Madonia, Ciro N.; Hatzikelis, Christopher; and Cosentino, Cesare C., 4,296,155, Cl. 428-31.000.
- Cottrill, William P.; and Cisternino, Andrew J., to Evacuators, Inc. Unloader for hopper cars and method. 4,295,775, Cl. 414-375.000.
- Couchman, James C., to General Dynamics Corporation. Fastener incorporating removable ultrasonic transducer. 4,295,377, Cl. 73-761.000.
- Cowell, Mark J., to Beckman Instruments, Inc. Centrifuge tube holder. 4,295,601, Cl. 233-26.000.
- Cox, Russell C.: See—
Louthan, Jean H.; Cox, Russell C.; and Crawford, William V., 4,295,668, Cl. 285-21.000.
- Cragoe, Edward J., Jr.; and Woltersdorf, Otto W., Jr., to Merck & Co., Inc. 2,3-Dihydro-6,7-disubstituted-5-(acyl)benzofuran-2-carboxylic acids. 4,296,122, Cl. 424-285.000.
- Cragoe, Edward J., Jr., to Merck & Co., Inc. 4-(Pyridyl, piperazinyl and thiazolyl substituted thiazolyl)-3-hydroxy-3-pyrroline-2,5-diones. 4,296,237, Cl. 544-405.000.
- Cramer, John J.: See—
Kakar, Sarwan K.; Kappler, Frank R.; and Cramer, John J., 4,296,165, Cl. 428-264.000.
- Cranston, Douglas R.: See—
Zangari, Dominic V.; and Cranston, Douglas R., 4,295,436, Cl. 113-80.00D.
- Crase, Gary M.; and Trzeciak, Kurt M., to Smith International, Inc. In-hole motor drill with locking bit clutch. 4,295,535, Cl. 175-101.000.
- Crawford, William V.: See—
Louthan, Jean H.; Cox, Russell C.; and Crawford, William V., 4,295,668, Cl. 285-21.000.
- Creative Tool Company: See—
Dooley, Joseph L.; and Dooley, Daniel J., 4,295,364, Cl. 73-119.00A.
- Cristofori, Manlio: See—
Borzatta, Valerio; Cristofori, Manlio; Morotti, Mauro; and Mascellani, Giuseppe, 4,296,125, Cl. 424-315.000.
- Crompton & Knowles Corporation: See—
Hoddinott, David C., 4,295,812, Cl. 425-114.000.
- Cross, Billy J., to Cross, Billy J. Material handling apparatus. 4,295,560, Cl. 198-517.000.
- Cucinella, Salvatore; Mazzei, Alessandro; and Dozzi, Giovanni, to Snamprogetti S.p.A. Process for the preparation of poly-(N-alkyliminoalanes). 4,296,045, Cl. 260-448.00R.
- Cugini, John J.: See—
Cugini, Larry, Sr.; and Cugini, John J., 4,295,275, Cl. 33-1.00G.
- Cugini, Larry, Sr.; and Cugini, John J. Method and apparatus for making raised and flat letter signs. 4,295,275, Cl. 33-1.00G.
- Cullison, Steven B.; and Slack, Charles B., to Altec Corporation. Loud-speaker overload protection circuit. 4,296,278, Cl. 179-1.0VL.
- Cummings, J. Francis; and Werner, Alfred O. Friction heat generator apparatus. 4,295,461, Cl. 126-247.000.
- Cunniff, James J. Plug cutter. 4,295,763, Cl. 408-86.000.
- Curts, Julius: See—
Hoppe, Udo; Sauermann, Gerhard; Curts, Julius; Glantz, Per-Olof; Krasse, Bo; Larsson, Kare; Noren, Borje; Odham, Goran; and Olsson, Jan, 4,296,095, Cl. 424-52.000.
- Cuscudra, Michael; and Speranza, George P., to Texaco Inc. Polyurethane foams using a polyurea polymer polyol. 4,296,213, Cl. 521-166.000.
- Cutler, Barry L. Framework holder for attaching container to floor machine. 4,295,622, Cl. 248-313.000.
- Cutting, Gloria T. Medication record-keeping package. 4,295,664, Cl. 283-1.00A.
- Dabisch, Kenneth W.; and Richards, John S., to Rockwell International Corporation. Non-contact counter. 4,296,314, Cl. 235-92.05B.

Dahlberg, Anders, to Tatis Plastatningar AB. Expansion joint element. 4,295,311, Cl. 52-396.000.

Dai Nippon Insatsu Kabushiki Kaisha: See—
Hoshino, Masaru, 4,296,068, Cl. 422-62.000.

Dai Nippon Toriy Co., Ltd.: See—
Hayashi, Masaaki; Sasaki, Hiroharu; and Tsuneta, Kazuyoshi, 4,296,014, Cl. 260-29.6NR.

Daicel Ltd.: See—
Sato, Kazuo, 4,296,243, Cl. 560-210.000.

Daikin Kogyo Co., Ltd.: See—
Fukui, Shosin; and Akazawa, Tadashi, 4,296,224, Cl. 526-243.000.
Ohsaka, Yohnosuke; and Tohzuca, Takashi, 4,296,265, Cl. 570-138.000.

Daimler-Benz Aktiengesellschaft: See—
Wulf, Helmut, 4,295,520, Cl. 165-41.000.

Dalboussiere, Gerard; and Draper, Wilburn D., to International Business Machines Corp. Select system for priority interface circuitry. 4,296,463, Cl. 364-200.000.

Daly, James E. Game and article for use therewith. 4,295,647, Cl. 273-1.00G.

Dam, Herman: See—
Brandwijk, Willem; and Dam, Herman, 4,295,286, Cl. 37-58.000.

Dambach, Thomas F.; and Ricketts, James R., to Marquette Electronics, Inc. Chart recorder having pressurized ink supply and Z fold paper feed and improved chart recording method. 4,296,420, Cl. 346-140.00R.

Damon, Robert E., II, to Sandoz, Inc. Silacycloalkane amides. 4,296,240, Cl. 556-406.000.

Daneffel, Hansruedi, to Feller AG. Electronic voice detector. 4,296,277, Cl. 179-1.0VC.

D'Angelo, Victor: See—
Koenig, Robert H.; and D'Angelo, Victor, 4,296,283, Cl. 200-16.00D.

Daniel, Alger T.: See—
Nicholson, Robert D.; and Daniel, Alger T., 4,295,594, Cl. 228-160.000.

Daniels, Lowell W.: See—
Luebke, Clement J.; Mitchell, John A.; and Daniels, Lowell W., 4,296,310, Cl. 219-440.000.

Data General Corporation: See—
Guyer, James M.; and West, Joseph T., 4,296,466, Cl. 364-200.000.

Daussan, Andre: See—
Daussan, Jean-Charles; Daussan, Gerard; and Daussan, Andre, 4,295,891, Cl. 501-99.000.

Daussan et Compagnie: See—
Daussan, Jean-Charles; Daussan, Gerard; and Daussan, Andre, 4,295,891, Cl. 501-99.000.

Daussan, Gerard: See—
Daussan, Jean-Charles; Daussan, Gerard; and Daussan, Andre, 4,295,891, Cl. 501-99.000.

Daussan, Jean-Charles; Daussan, Gerard; and Daussan, Andre, to Daussan et Compagnie. Blanket powder for covering a molten metal bath. 4,295,891, Cl. 501-99.000.

David Brown Tractors Limited: See—
Ashfield, Herbert E.; Horsfall, Harry; and Wade, Philip M., 4,295,530, Cl. 172-7.000.

Davis, Charles D., to Armstrong World Industries, Inc. Gripper shuttles. 4,295,498, Cl. 139-196.200.

Davis, Harry C. Circular insulation saw system. 4,295,263, Cl. 29-561.000.

Davis, Herbert L.: See—
Chen, John C.; and Davis, Herbert L., 4,296,058, Cl. 264-78.000.

Davis, William O., to AAI Corporation. Rocket assisted projectile and cartridge arrangement with pressure relief skirt. 4,295,425, Cl. 102-326.000.

Davison, Michael J.: See—
Seilly, Alec H.; Mowbray, Dorian F.; Mardell, John E.; and Davison, Michael J., 4,295,453, Cl. 123-499.000.

Davy Powergas GmbH: See—
Stauffer, Adolf, 4,296,088, Cl. 423-533.000.

Dayco Corporation: See—
Marsh, Richard L., 4,295,837, Cl. 474-153.000.

de la Vega, Alejandro J. Apparatus and method for handling jackets of printed matter. 4,295,643, Cl. 270-57.000.

DeCaro, Charles J., to Textron Inc. Installation tool barrel assembly. 4,295,394, Cl. 81-57.370.

Decuir, Joseph C.: See—
Mayer, Steven T.; Miner, Jay G.; Neubauer, Douglas G.; and Decuir, Joseph C., 4,296,476, Cl. 364-900.000.

Deere & Company: See—
Hurt, James J., 4,296,474, Cl. 364-560.000.

Deflecto Corporation: See—
Meyer, Stephen T., 4,295,571, Cl. 211-200.000.

Defourny, Jacques, to Centre de Recherches Metallurgiques-Centrum voor Research in de Metallurgie. Electrode displacement monitoring in resistance welding. 4,296,304, Cl. 219-86.410.

Degger, Wolter W. J.; and Van Kasteren, Adrianus C., to U.S. Philips Corporation. Precision adjusting device. 4,295,625, Cl. 248-466.000.

Degussa Aktiengesellschaft: See—
Bugdahl, Volker; Morlock, Gerhard; Reidt, Werner; and Kerschner, Emil, 4,296,006, Cl. 260-23.0EP.

DeHart, John R.; and Majewski, Robert A., to Docutronics, Inc. Envelope processing machine. 4,295,321, Cl. 53-381.00R.

Dehn, Rudolph A.: See—
Eichelberger, Charles W.; Dehn, Rudolph A.; and Wojnarowski, Robert J., 4,296,296, Cl. 219-10.55B.

Deitz, Bernard, to Deitz Plastic Formers. Waterproof cushion for outdoor use and method for manufacturing the same. 4,295,235, Cl. 5-473.000.

Deitz Plastic Formers: See—
Deitz, Bernard, 4,295,235, Cl. 5-473.000.

Della Valle, Francesco, to Fidia S.p.A. Selected process for producing monohalogenated derivatives of 7-hydroxy-coumarin. 4,296,039, Cl. 260-343.450.

Del Soldato, Piero: See—
Ghelardoni, Mario; Pestellini, Vittorio; Del Soldato, Piero; Volterra, Giovanna; and Meli, Alberto, 4,296,124, Cl. 424-285.000.

Delta Mouldings (Leicester) Limited: See—
Williams, William, 4,295,629, Cl. 249-160.000.

DeLuca, Frederick P. Light emitting electronic jewelry. 4,296,459, Cl. 362-104.000.

DeMaria, Francesco, to American Cyanamid Company. Pressure sealing process. 4,296,059, Cl. 264-130.000.

De Maria, Francesco; and Pfeiffer, Ronald E., to American Cyanamid Company. Hollow acrylonitrile polymer fiber. 4,296,175, Cl. 428-398.000.

De Matteo, John; and Villani, Frank, to United States of America, Navy. Gravity measurement apparatus for ships. 4,295,372, Cl. 73-382.00G.

Denerley, Paul M., to Beecham Group Limited. Method for the preparation of penicillanic- β -lactamase inhibitors. 4,296,032, Cl. 260-245.20R.

Denham, Leslie R.: See—
Reeves, H. Neal; Burnett, Roy E.; Denham, Leslie R.; and Shields, George E., 4,295,542, Cl. 181-108.000.

Dennert, Hans V.: See—
Dennert, Heinz; and Dennert, Hans V., 4,295,810, Cl. 425-110.000.

Dennert, Heinz; and Dennert, Hans V., to Veit Dennert KG Baustoffbetriebe. Apparatus for insulating building blocks. 4,295,810, Cl. 425-110.000.

Dennesen Electronics Inc.: See—
Dennesen, Francis G.; Wilson, Richard S.; Toulon, Roy D., Jr.; and Madnick, Peter, 4,295,277, Cl. 33-181.00R.

Dennesen, Francis G.; Wilson, Richard S.; Toulon, Roy D., Jr.; and Madnick, Peter, to Dennesen Electronics Inc. Stylus positioner. 4,295,277, Cl. 33-181.00R.

de Nora, Oronzio; Giuffre, Luigi; and Modica, Giovanni, to Oronzio de Nora Impianti Elettrochimici S.p.A. Novel cationic membranes. 4,295,952, Cl. 204-252.000.

Dentsply Research & Development Corp.: See—
Rudler, Helmut, 4,295,828, Cl. 433-90.000.

de Paolis, Potito U. Conchless high protein chocolate flavored composition and method of making same. 4,296,141, Cl. 426-613.000.

DeSoto, Inc.: See—
Sekmakas, Kazys; and Shah, Raj, 4,296,011, Cl. 260-29.300.

Desprez, Alfred; Sauerland, Heinz; and Teetz, Wolfgang, to Maschinenfabrik Carl Zangs Aktiengesellschaft. Take-up drive for a multi-head embroidery machine. 4,295,433, Cl. 112-241.000.

Dessaint, Andre L.; and Perronin, Jean, to Produits Chimiques Ugine Kuhlmann. Fluorinated anti-stain and soil release finishes. 4,295,976, Cl. 252-8.900.

Dettinger, Dietrich: See—
Abendroth, Paul; and Dettinger, Dietrich, 4,295,421, Cl. 101-216.000.

Deutsch, Leslie J.: See—
Deutsch, Ralph; and Deutsch, Leslie J., 4,295,402, Cl. 84-1.030.

Deutsch, Ralph; and Deutsch, Leslie J., to Kawai Musical Instrument Mfg. Co., Ltd. Automatic chord accompaniment for a guitar. 4,295,402, Cl. 84-1.030.

Developak Corporation: See—
Evers, Jack R., 4,295,922, Cl. 156-583.100.

de Waard, Peter J.: See—
Tijburg, Rudolf P.; de Waard, Peter J.; and van Dongen, Teunis, 4,296,386, Cl. 331-94.50H.

Dexter, Theodore H.: See—
Bommaraju, Tilak V.; Dexter, Theodore H.; and Rader, Charles G., 4,295,951, Cl. 204-242.000.

d'Hauteourt, Alain H.; Bretl, Wayne E.; and Lee, Ronald B., to Zenith Radio Corporation. Luminance signal processing circuit. 4,296,435, Cl. 358-166.000.

Dhondt, Roland O., to Union Oil Company of California. Apparatus and method for introducing solids into a solids upflow vessel. 4,295,773, Cl. 414-187.000.

Diamond, Andrew C.: See—
Ashton, Christopher J.; Diamond, Andrew C.; and Greenhill, Derek H., 4,295,754, Cl. 403-369.000.

Diamond, George; Forrester, James; Hirsch, Michael; and Vas, Ran. Apparatus and method for analysis of motion of a dynamic structure. 4,295,473, Cl. 178-695.000.

Diamond, Julius, to William H. Rorer, Inc. Ethynylbenzene compounds and derivatives thereof. 4,296,264, Cl. 570-128.000.

Diamond Shamrock Technologies S.A.: See—
Tomov, Nenad R.; and Roberts, Geoffrey M., 4,295,943, Cl. 204-96.000.

Di Benedetto, Marianne, to Ciba-Geigy Corporation. Adducts containing hydroxyl groups from mononuclear hydantoin glycidyl compounds and non-aromatic dicarboxylic acids. 4,296,005, Cl. 260-18.0EP.

Dickey-john Corporation: See—
Whitaker, Roger B.; and Blevins, Charles W., 4,296,409, Cl. 340-684.000.

Dickhart, William W., III; and Marvin, Richard H., to Budd Company, The. Steerable truck for a railway vehicle. 4,295,428, Cl. 105-168.000.

Diehl GmbH & Co.: See—
Rhaue, Siegfried; and Weber, Adolf, 4,296,180, Cl. 428-558.000.

Dietze, Robert H.: See—
Nahar, Rathindra; and Dietze, Robert H., 4,295,645, Cl. 271-34.000.

DiFulvio, Anthony P.: See—
Smith, Michael R.; and DiFulvio, Anthony P., 4,296,069, Cl. 422-64.000.

DiMarzio Musical Instrument Pickups, Inc.: See—
Smith, Paul R., 4,295,404, Cl. 84-314.00N.

Din, Zia U.: See—
Cardenas, Carlos G.; and Din, Zia U., 4,296,257, Cl. 568-361.000.
Ho, T. L.; and Din, Zia U., 4,296,038, Cl. 260-343.210.
Ho, T. L.; Din, Zia U.; and Cardenas, Carlos G., 4,296,251, Cl. 562-506.000.

Dinunno, Frank P.: See—
Beattie, Thomas R.; Christensen, Burton G.; and Dinunno, Frank P., 4,296,111, Cl. 424-246.000.

Disko, Harry: See—
Rosenwinkel, Donald A.; Meyer, Burton C.; and Disko, Harry, 4,295,294, Cl. 46-205.000.

Ditgens, Klaus: See—
Stetter, Jorg; Ditgens, Klaus; Thomas, Rudolf; Eue, Ludwig; and Schmidt, Robert R., 4,295,876, Cl. 71-90.000.

Divers, Robert M. Tool for removing sleeves from cylinders. 4,295,260, Cl. 29-426.500.

Diversey Corporation, The: See—
Kakar, Sarwan K.; Kappler, Frank R.; and Cramer, John J., 4,296,165, Cl. 428-264.000.

Dixon Valve & Coupling Co.: See—
Goodall, Richard B.; and Goodall, Richard L., 4,295,670, Cl. 285-91.000.

Dixon, William. Corner beading cleaner. 4,295,242, Cl. 15-235.700.

Dr. C. Otto & Comp. G.m.b.H.: See—
Ritter, Horst, 4,296,049, Cl. 261-111.000.

Dr. Johannes Heidenhain GmbH: See—
Nelle, Gunther; and Swasek, Gunter, 4,295,742, Cl. 356-373.000.

Docutronics, Inc.: See—
DeHart, John R.; and Majewski, Robert A., 4,295,321, Cl. 53-381.00R.

Dodds, Dennis L., to RCA Corporation. Television display error correction. 4,296,359, Cl. 315-370.000.

Dodds, Robert J., to International Computers Limited. Electrical connectors. 4,295,695, Cl. 339-17.00F.

Dodge, Paul D.: See—
Herpers, Ferdinand J.; Kroll, Harley E.; Carlson, Alfred D.; and Dodge, Paul D., 4,295,244, Cl. 15-320.000.

Doerer, Daniel M.; and Brunkhorst, Lloyd E., to Brown Group, Inc. Method of making foamed plastisol insoles for shoes. 4,296,053, Cl. 264-26.000.

Domenis, Danilo: See—
Moiso, Ugo; Massabo, Vincenzo; and Domenis, Danilo, 4,296,028, Cl. 260-160.000.

Dominey, Samuel C., Jr.: See—
Blinow, Donald W.; Cassidy, Kevin H.; and Dominey, Samuel C., Jr., 4,296,321, Cl. 250-254.000.

Dooley, Daniel J.: See—
Dooley, Joseph L.; and Dooley, Daniel J., 4,295,364, Cl. 73-119.00A.

Dooley, Joseph L.; and Dooley, Daniel J., to Creative Tool Company. Transducer device for monitoring of fuel injection. 4,295,364, Cl. 73-119.00A.

Dorman Smith Traffic Products Limited: See—
Minoprio, William E.; and Horsfield, Arthur K., 4,296,460, Cl. 362-200.000.

Doten, Bradford O.; and Svitak, John J., to Western Electric Company, Inc. Methods and apparatus for bonding an article to a metallized substrate. 4,295,596, Cl. 228-180.00A.

Douthett, Joseph A.; and Espy, Ronald H., to Armco Inc. Copper and nitrogen containing austenitic stainless steel and fastener. 4,295,769, Cl. 411-411.000.

Dover Corporation: See—
Peschke, Norman, 4,295,802, Cl. 417-405.000.

Dow Chemical Company, The: See—
Anand, Joginder N.; Revak, Timothy T.; and Tsang, Floris Y., 4,296,052, Cl. 264-25.000.
Gibbs, Dale S., 4,296,013, Cl. 260-29.6TA.
Gibbs, Ronald L., 4,295,992, Cl. 252-429.00C.
Harris, Wilford D., 4,296,055, Cl. 264-45.500.
Jenkins, Randall C.; Taylor, Clyde G.; Turner, Robert B.; and Ridgway, Donald H., 4,296,159, Cl. 428-95.000.
Nelson, Alfred R.; and Johnsen, Kenneth E., 4,296,019, Cl. 260-33.40R.

Seeburger, Harold O.; Beattie, Ralph G.; and Stevens, Violette L., 4,296,220, Cl. 525-507.000.

Seeburger, Harold O.; Atchison, George J.; and Stevens, Violette L., 4,296,227, Cl. 526-320.000.

Sutrina, Thomas A.; and Behr, R. Douglas, 4,295,919, Cl. 156-498.000.

Dozzi, Giovanni: See—
Cucinella, Salvatore; Mazzei, Alessandro; and Dozzi, Giovanni, 4,296,045, Cl. 260-448.00R.

Dragoo, Vaughn G., to Jersey Nuclear-Avco Isotopes, Inc. Thermally improved dye laser flow channel. 4,296,388, Cl. 331-94.50L.

Dragomir, Stojicic. Boxing gloves without a seam on the frontal strike portion thereof. 4,295,228, Cl. 2-18.000.

Draper, Wilburn D.: See—
Dalbousiere, Gerard; and Draper, Wilburn D., 4,296,463, Cl. 364-200.000.

Dresser Industries, Inc.: See—
Purton, Robert M., 4,295,487, Cl. 137-242.000.

Drewery, John O.; and Storey, Richard, to British Broadcasting Corporation. Method of and apparatus for movement portrayal with a raster e.g. television, display. 4,296,434, Cl. 358-105.000.

Droni, Mordeki. Backwashable fluid filter. 4,295,963, Cl. 210-108.000.

Droux, Michel; and Bocquet, Gilbert, to Saint-Gobain Industries. Sizing composition and glass fibers treated with the aid of such composition. 4,295,871, Cl. 65-3.410.

Dubbink, David T.; and Vogler, Lynda L. Orthopedic chair. 4,295,683, Cl. 297-377.000.

Duchardt, Karl H.; and Gehrke, Gunter, to Bayer Aktiengesellschaft. Process for the preparation of cationic anthraquinone dyestuffs. 4,296,044, Cl. 260-381.000.

Dudley, Kenneth W.: See—
MacMaster, George H.; and Dudley, Kenneth W., 4,296,298, Cl. 219-10.810.

Duffy, John W.: See—
Arends, Roger R.; Bailey, Wayne B.; Duffy, John W.; and Springer, Brice D., 4,295,489, Cl. 137-488.000.

Duffy, Robert J.: See—
Steyer, William; and Duffy, Robert J., 4,295,332, Cl. 60-264.000.

Duhon, Gerald L.: See—
Gibson, Joseph T.; and Duhon, Gerald L., 4,295,366, Cl. 73-155.000.

Duke, Steven R.: See—
Patenaude, Raymond A.; Duke, Steven R.; and Proulx, Edward A., 4,295,410, Cl. 89-12.000.

Duley, Richard K., to Redland Automation Limited. Inductive vehicle detector. 4,296,401, Cl. 340-38.00L.

Dumas, David H., to Hercules Incorporated. Sizing method and sizing composition for use therein. 4,295,931, Cl. 162-158.000.

Dumont, Claude: See—
Nedelec, Lucien; Frechet, Daniel; and Dumont, Claude, 4,296,126, Cl. 424-316.000.

Dungan, D. Patrick. Brake assembly for small vehicles. 4,295,547, Cl. 188-2.00R.

Du Pont de Nemours, E. I., and Company: See—
Adams, John E.; Evans, Robert F.; and Gavin, John H., 4,295,254, Cl. 29-33.00M.

Fountain, Frank S., 4,295,360, Cl. 73-15.600.

Hanzel, Robert S.; and Sauer, Paul J., 4,296,174, Cl. 428-389.000.

Johnson, Alexander L., 4,296,110, Cl. 424-244.000.

Kusy, Robert P., 4,295,374, Cl. 73-579.000.

Robinson, Bruce A.; and Thompson, John R., 4,295,252, Cl. 28-248.000.

Windley, William T., 4,295,329, Cl. 57-245.000.

Dupuy, James A. Cable dead ending. 4,295,250, Cl. 24-122.600.

Duracell International Inc.: See—
Ciliberti, Frank L., Jr., 4,295,705, Cl. 339-220.00R.

Mallory, Henry R.; and Nichols, Steven J., 4,296,461, Cl. 363-22.000.

Duran, John A., to Avibank Mfg., Inc. Latch mechanism. 4,295,674, Cl. 292-190.000.

Durand, Roger, to Pignons S.A. Photographic shutter. 4,295,725, Cl. 354-244.000.

Duro-Test Corporation: See—
Trutner, Donald G.; and Thorington, Luke, 4,295,873, Cl. 65-108.000.

DuRocher, Gideon A., to Essex International, Inc. Pressure sensitive combination switch and circuit breaker construction. 4,295,699, Cl. 339-61.00M.

Dussourd, Jules L.; and Pfannebecker, George W., to Terry Corporation. Turbine wheel and nozzle arrangement. 4,295,788, Cl. 415-202.000.

Dynamit Nobel Aktiengesellschaft: See—
Gauchel, Peter; and Wissinger, Waldemar, 4,296,062, Cl. 264-173.000.

Haage, Karl; and Scharff, Dieter, 4,295,911, Cl. 156-315.000.

E. R. Squibb & Sons, Inc.: See—
Ondetti, Miguel A., 4,296,113, Cl. 424-246.000.

Petrillo, Edward W., Jr.; and Weisenborn, Frank L., 4,296,033, Cl. 260-326.200.

Weisenborn, Frank L.; Brown, William E.; and Meyers, Edward, 4,296,101, Cl. 424-119.000.

E-Systems, Inc.: See—
Harader, Wayne R., 4,296,416, Cl. 343-792.500.

Eastman Kodak Company: See—
Bishop, John F.; and Bowman, Wayne A., 4,296,195, Cl. 430-215.000.

Breen, John J., 4,295,715, Cl. 354-25.000.

Edwards, Evan A., 4,295,713, Cl. 352-235.000.

Montalto, Michael S.; Blanding, Douglass L.; and Smith, Michael R., 4,296,070, Cl. 422-65.000.

Smith, Michael R.; and DiFulvio, Anthony P., 4,296,069, Cl. 422-64.000.

Eaton, Sargent S., Jr.; and Schroeder, Paul R., to Mostek Corporation. Refresh counter. 4,296,480, Cl. 365-222.000.

Ebauches S.A.: See—
Randin, Jean-Paul, 4,296,016, Cl. 260-29.6SQ.

- Eckhardt, Wolfgang: See—
Kunz, Walter; Eckhardt, Wolfgang; and Hubele, Adolf, 4,296,118, Cl. 424-273.000.
- Economopoulos, Marios, to Centre de Recherches Metallurgiques-Centrum voor Research in de Metallurgie. Method of manufacturing rolled steel products with high elastic limit. 4,295,902, Cl. 148-144.000.
- Edwards, Evan A., to Eastman Kodak Company. Film and photographic apparatus. 4,295,713, Cl. 352-235.000.
- Edwards, Laroy H., to Chevron Research. N-Alkyl or aryl-N-(trichlorovinylthio)-halomethane sulfonamides. 4,295,874, Cl. 71-67.000.
- Efimov, Vyacheslav T.: See—
Nazarian, Miron M.; Efimov, Vyacheslav T.; Axenko, Alexander A.; Kolyada, Vladimir A.; and Shamsha, Ljudmila F., 4,295,946, Cl. 204-149.000.
- Eggert, Walter S., Jr., to Budd Company, The. Blade structure for use in a windmill. 4,295,790, Cl. 416-226.000.
- Ehretsmann, Jacques: See—
Roman, Alain; Chevreux, Pierre; Wust, Manfred; and Ehretsmann, Jacques, 4,295,948, Cl. 204-159.230.
- Eichelberger, Charles W.; Dehn, Rudolph A.; and Wojnarowski, Robert J., to General Electric Company. Controllable-duty-cycle power supply for microwave oven magnetron and the like. 4,296,296, Cl. 219-10.55B.
- Eichelberger, Charles W., to General Electric Company. Relay switching apparatus. 4,296,449, Cl. 361-3.000.
- Eichelseder, Christine: See—
Weissgerber, Rudolf; Stoll, Alois; Kandler, Herbert; Nunner, Hans-Herbert; Eichelseder, Christine; and Pangeri, Helmut, 4,296,017, Cl. 260-30.60R.
- Eicher, Franz: See—
Wuthrich, Hans-Rudolf; Krebs, Peter; Spiegel, Hubert; and Eicher, Franz, 4,296,289, Cl. 200-148.00R.
- Eicken, Karl; Rohr, Wolfgang; Pander, Hans J.; and Wuerzer, Bruno, to BASF Aktiengesellschaft. Tetrahydro-1,3-oxazines. 4,295,875, Cl. 71-88.000.
- Eida, Tsuyoshi; Haruta, Masahiro; Yano, Yasuhiro; Matsufuji, Yoji; and Ohta, Tokuya, to Canon Kabushiki Kaisha. Recording liquid composition. 4,295,889, Cl. 106-22.000.
- Ejiri, Yoshihiro: See—
Nakai, Taiichiro; Furusawa, Kahei; and Ejiri, Yoshihiro, 4,295,707, Cl. 350-96.200.
- Ekman, C. Frederick W.: See—
Lennon, Donald J. J.; Hagerstrom, John R.; and Ekman, C. Frederick W., 4,296,176, Cl. 428-407.000.
- Eldeen, Gene H. Newal post assembly. 4,295,638, Cl. 256-59.000.
- Electric Power Research Institute, Inc.: See—
Harrold, Ronald T.; and Ottenberg, Lawrence E., 4,296,003, Cl. 252-570.000.
- Ellington, Rayburn P., III, to Caterpillar Tractor Co. Template for aligning a shaft. 4,295,276, Cl. 33-181.00R.
- Elmendorf Research, Inc.: See—
Etzold, Roland; Impellizzeri, Julius S.; and Vaughan, Thomas W., 4,295,557, Cl. 198-382.000.
- Elsner, Ernst: See—
Helfer, Friedrich; Elsner, Ernst; and Zaiser, Wolfgang, 4,295,348, Cl. 64-27.00L.
- Eltra Corporation: See—
Varma, Brajendra P., 4,295,940, Cl. 204-2.100.
- Eltvedt, Frank. Guide skirt. 4,295,815, Cl. 425-556.000.
- Emerson Electric Co.: See—
Bowsky, Benjamin, 4,296,275, Cl. 174-152.0GM.
- Hildebrandt, Eugene F.; and Ottersbach, Thomas V., 4,296,366, Cl. 318-793.000.
- Punshon, William D.; and Peachee, C. Theodore, 4,295,268, Cl. 29-596.000.
- Emhart Industries, Inc.: See—
Bristol, Robert G., 4,295,370, Cl. 73-304.00C.
- Clouser, Michael T., 4,295,603, Cl. 236-1.00G.
- Miller, Theodore H., 4,295,673, Cl. 292-21.000.
- Emi, Shingo; and Saiki, Noritsugu, to Teijin Limited. Fibrous composite having elasticity. 4,296,163, Cl. 428-212.000.
- Endo, Shigeru: See—
Tanaka, Kenji; and Endo, Shigeru, 4,296,133, Cl. 426-23.000.
- Energy Equipment Co. Ltd., The: See—
Caplin, Peter B.; and Harman, Maurice, 4,295,817, Cl. 431-7.000.
- Engel, Christopher M.; and Srivastava, Gopal K., to Zenith Radio Corporation. Dynamic enabling network for a color correction circuit. 4,296,432, Cl. 358-28.000.
- Engelhard Min. & Chem. Corp.: See—
Heuer, Steven R.; and Zbrank, Zdenka, 4,296,077, Cl. 423-53.000.
- Engelke, Roger P., to Barber-Colman Company. Method and apparatus for reducing torque on an air damper. 4,295,632, Cl. 251-127.000.
- Engineered Systems, Inc.: See—
Sheldon, James R., 4,296,404, Cl. 340-149.00A.
- Weimer, Dan G.; and Van Ness, Bradford O., 4,296,315, Cl. 235-460.000.
- English Electric Valve Company: See—
Esterson, Maurice; and Brady, Michael B. C., 4,296,385, Cl. 331-90.000.
- Enomoto, Kazuyoshi: See—
Sakaguchi, Tadahiro; Hino, Masamichi; Tsuji, Setsuo; Hashido, Akiyoshi; and Enomoto, Kazuyoshi, 4,295,915, Cl. 156-361.000.
- Enomoto, Satoru; Asano, Kiro; and Tanaka, Hiromitsu, to Kureha Kagaku Kogyo Kabushiki Kaisha. Conjugate of amino sugar-steroid hormone. 4,296,233, Cl. 536-5.000.
- Epoxon Products, Inc.: See—
Wilson, Thomas T., 4,295,460, Cl. 126-121.000.
- EPP Corp.: See—
Lennon, Donald J. J.; Hagerstrom, John R.; and Ekman, C. Frederick W., 4,296,176, Cl. 428-407.000.
- Erb, Tom L.; and Miller, Wendell D., to Ramsey Engineering Company. Method and apparatus for flow measurement using Doppler frequency shift. 4,295,378, Cl. 73-861.250.
- Eriksson, Leif; and Liberman, Salomon, to Asea Aktiebolag. Multiphase fault protection circuitry with variable functional level detection. 4,296,452, Cl. 361-82.000.
- Erlach, Hans, to Sulzer Brothers Limited. Means for coupling a hand drive with a rotatable shaft. 4,295,552, Cl. 192-81.00C.
- Eroshkevskaya, Elena D., administrator: See—
Zhivotov, Yuri G.; Kupchinsky, Igor I.; Plokhuta, Vyacheslav D.; Bezverkhnay, Alexandr M.; Nabutovsky, Samoil I., deceased; and Eroshkevskaya, Elena D., administrator, 4,295,387, Cl. 74-573.00F.
- Errichello, Dominic R. Integrally molded, looseleaf books with ring-binder-mounting posts molded on spine. 4,295,747, Cl. 402-75.000.
- Erwin Sick GmbH, Optik-Elektronik: See—
Sick, Erwin, 4,295,743, Cl. 356-431.000.
- Esperling, Peter: See—
Laurent, Henry; Esperling, Peter; Kapp, Joachim-Friedrich; and Wiechert, Rudolf, 4,296,109, Cl. 424-241.000.
- Espy, Ronald H.: See—
Douthett, Joseph A.; and Espy, Ronald H., 4,295,769, Cl. 411-411.000.
- Essex International, Inc.: See—
DuRocher, Gideon A., 4,295,699, Cl. 339-61.00M.
- Esterson, Maurice; and Brady, Michael B. C., to English Electric Valve Company. X-Ray assisted multipactor discharge tuned resonant cavity device. 4,296,385, Cl. 331-90.000.
- Etablissements Boucher Freres: See—
Boucher, Pierre, 4,295,641, Cl. 269-136.000.
- Ethyl Corporation: See—
Papay, Andrew G.; and O'Brien, Joseph P., 4,295,983, Cl. 252-49.600.
- Etzold, Roland; Impellizzeri, Julius S.; and Vaughan, Thomas W., to Elmendorf Research, Inc. Apparatus and method for aligning elongated ligno-cellulosic strands into parallelism. 4,295,557, Cl. 198-382.000.
- Eue, Ludwig: See—
Stetter, Jorg; Ditzgen, Klaus; Thomas, Rudolf; Eue, Ludwig; and Schmidt, Robert R., 4,295,876, Cl. 71-90.000.
- Evacuators, Inc.: See—
Cottrill, William P.; and Cisternino, Andrew J., 4,295,775, Cl. 414-375.000.
- Evans, Robert F.: See—
Adams, John E.; Evans, Robert F.; and Gavin, John H., 4,295,254, Cl. 29-33.00M.
- Evers, Jack R., to Developak Corporation. Tube side seam heat sealer. 4,295,922, Cl. 156-583.100.
- Ewen, James H.; and McClellan, Thomas R., to Upjohn Company, The. Elastomeric polyurethane-polyurea polymer prepared from an organic polyisocyanate a polyol and an aromatic diamine having at least one of the ortho positions to each amine lower alkyl. 4,296,212, Cl. 521-163.000.
- Ewins, Earle E., Jr.: See—
St. Clair, David J.; and Ewins, Earle E., Jr., 4,296,008, Cl. 260-27.00B.
- Exploration Company: See—
Weiss, Benjamin F. L., 4,296,481, Cl. 367-20.000.
- Exxon Research & Engineering Co.: See—
Bearden, Roby, Jr.; and Aldridge, Clyde L., 4,295,995, Cl. 252-431.00C.
- Bearden, Roby, Jr.; Aldridge, Clyde L.; and Pine, Lloyd A., 4,295,996, Cl. 252-431.00C.
- Mauldin, Charles H.; and Baird, William C., Jr., 4,295,957, Cl. 208-138.000.
- Mauldin, Charles H.; and Baird, William C., Jr., 4,295,958, Cl. 208-138.000.
- Metrailler, William J., 4,295,956, Cl. 208-127.000.
- Rosensweig, Ronald E., 4,296,080, Cl. 423-244.000.
- Wristers, Harry J., 4,295,991, Cl. 252-429.00B.
- Fabris, Mario. Roller entry guides for rod mills. 4,295,356, Cl. 72-250.000.
- Fagersta AB: See—
Malmgren, Nils-Gunnar; Solly, Barry; and Tarnblom, Stig, 4,295,900, Cl. 148-12.00B.
- Fahey, Dennis M., to PPG Industries, Inc. Glass fibers with-reduced tendency to form gumming deposits and sizing composition comprising two starches with different amylose content. 4,296,173, Cl. 428-378.000.
- Fahrig, Robert J.; and Hinrichs, Lansing M., to Standard Oil Company (Indiana). Method and apparatus for improved fluid catalytic riser reactor cracking of hydrocarbon feedstocks. 4,295,961, Cl. 208-161.000.
- Fairchild, Peter T.; and Leininger, Joel C., to International Business Machines Corp. Link register storage and restore system for use in an instruction pre-fetch micro-processor interrupt system. 4,296,470, Cl. 364-200.000.
- Falk, Edward J., to Wagner Electric Corporation. Master cylinder assembly with detachable reservoir. 4,295,336, Cl. 60-562.000.

- Farfaglia, Silvio T., to Phillips Petroleum Company. Container spinning apparatus for container manufacturing machine or the like. 4,295,903, Cl. 156-69.000.
- Farnham, Robert A., to Chevron Research Company. Fractionation apparatus providing improved heat recovery from bottom stream. 4,295,936, Cl. 202-153.000.
- Faust, Raimund J., to Hoechst Aktiengesellschaft. Photopolymerizable mixture in a transfer element. 4,296,196, Cl. 430-271.000.
- Fehr, Charles; Ohloff, Gunther; and Buchi, Georges H., to Firmenich SA. Process for the preparation of macrocyclic ketones. 4,296,258, Cl. 568-364.000.
- Feller AG: See—
Daneffel, Hansruedi, 4,296,277, Cl. 179-1.0VC.
- Fensom, Donald J., to ICI Australia Limited. Processes of iron segregation. 4,295,878, Cl. 75-1.00T.
- Ferguson, Stewart. Shouldered shake and filler roof structure. 4,295,314, Cl. 52-553.000.
- Ferris, Ray: See—
Knippel, Willis H.; and Ferris, Ray, 4,295,430, Cl. 105-308.00E.
- Feuerbaum, Hans-Peter, to Siemens Aktiengesellschaft. Techniques for impressing a voltage with an electron beam. 4,296,372, Cl. 324-71.0EB.
- F'Geppert, Erwin, to United States of America, Army. Shaft-component connection means. 4,295,750, Cl. 403-259.000.
- Fidia S.p.A.: See—
Della Valle, Francesco, 4,296,039, Cl. 260-343.450.
- Fiegel, Joachim: See—
Walz, Klaus; and Fiegel, Joachim, 4,295,852, Cl. 8-560.000.
- Finsterwalder, Kurt; Philipp, Karl-Heinz; Riedisser, Gunter; and Voss, Wilfried, to L. Schuler GmbH. Apparatus for intermittent feeding of web-type or strip-type material. 4,295,399, Cl. 83-251.000.
- Firestone, Raymond A.: See—
Christensen, Burton G.; Johnston, David B. R.; and Firestone, Raymond A., 4,296,236, Cl. 542-420.000.
- Firmenich SA: See—
Fehr, Charles; Ohloff, Gunther; and Buchi, Georges H., 4,296,258, Cl. 568-364.000.
- Fischell, Robert E., to Johns Hopkins University, The. Recorder with patient alarm and service request systems suitable for use with automatic implantable defibrillator. 4,295,474, Cl. 128-697.000.
- Fischli, Albert E.; and Szente, Andre, to Hoffmann-La Roche Inc. Benzodiazepine derivatives. 4,296,031, Cl. 260-239.30D.
- Fisher Controls Company, Inc.: See—
Arends, Roger R.; Bailey, Wayne B.; Duffy, John W.; and Springer, Brice D., 4,295,489, Cl. 137-488.000.
- Fisher Scientific Company: See—
Bernier, John A., 4,296,358, Cl. 315-241.00R.
- Fisons Limited: See—
Appleton, Richard A.; and Johnston, David, 4,296,114, Cl. 424-248.520.
- Fitzgerald, Stella; and Beaver, Bryan, to Beaver, Bryan. Demolition derby toy. 4,295,292, Cl. 46-201.000.
- Fives-Cail Babcock: See—
Chielens, Alain; and Boussekey, Bernard, 4,295,825, Cl. 432-116.000.
- Flachbarth, Charles T., to Butler Manufacturing Co. Surface raceway box. 4,295,575, Cl. 220-3.920.
- Flemings, Merton C.; and Goodwin, Frank E., to Massachusetts Institute of Technology. Method for making metal alloy compositions and composition. 4,295,896, Cl. 148-1.000.
- Floessel, Carl D., to BBC Brown, Boveri & Company Limited. Gas insulated high voltage line and method of assembling same. 4,296,271, Cl. 174-28.000.
- FMC Corporation: See—
Buchta, Ervin A., 4,295,390, Cl. 74-625.000.
- Fogle, Ozzie: See—
Cooley, James; and Fogle, Ozzie, 4,295,910, Cl. 156-314.000.
- Follett Corporation: See—
Hornbeck, Clarence J., 4,295,309, Cl. 52-309.700.
- Forlenza, Nicholas G., to Mateflex/Mele Corporation. Method of zoning grate surfaces. 4,296,160, Cl. 428-117.000.
- Forrester, James: See—
Diamond, George; Forrester, James; Hirsch, Michael; and Vas, Ran, 4,295,473, Cl. 178-695.000.
- Forstner, Anton; and Schatzmann, Kurt, to Siemens-Albis Aktiengesellschaft. Apparatus for applying solder to the connections of integrated circuit components. 4,295,441, Cl. 118-425.000.
- Foster, Arthur M.: See—
Tang, David Y.; and Foster, Arthur M., 4,296,244, Cl. 562-470.000.
- Fountain, Frank S., to Du Pont de Nemours, E. I., and Company. Tension measuring apparatus. 4,295,360, Cl. 73-15.600.
- Four Star Corporation: See—
Kowalski, Daniel J.; and Mareydt, Ray G., 4,295,588, Cl. 224-321.000.
- Fourcadier, Chantal: See—
Grollier, Jean F.; Bugaut, Andree; Andriillon, Patrick; and Fourcadier, Chantal, 4,295,848, Cl. 8-421.000.
- Fox, Bryce J., to Minnesota Mining and Manufacturing Company. Heat and liquid recovery using open cycle heat pump system. 4,295,282, Cl. 34-27.000.
- Fox Valley Process Systems & Supply, Inc.: See—
Galloway, Tod R., 4,295,491, Cl. 137-625.460.
- Foxcroft, Garth, to Brink, Dirk Marinus. Protective tire chain assembly. 4,295,510, Cl. 152-220.000.
- Fram Industrial Filter Corp.: See—
Jain, Kamlesh K., 4,295,973, Cl. 210-738.000.
- Franco, Wayne P. Method of treating the heart for myocardial infarction. 4,296,100, Cl. 424-108.000.
- Frangatos, Gerassimos, to Mobil Oil Corporation. Sulfurized aminoguanidine reaction product and lubricant compositions containing same. 4,295,982, Cl. 252-42.000.
- Franken, Adrianus J. J.; Khoe, Giok D.; and Kuppers, Dieter, to U.S. Philips Corporation. Method of producing microlenses. 4,296,143, Cl. 427-38.000.
- Franks, Larry A.; and Nelson, Melvin A., to United States of America, Energy. Waveform synthesizer. 4,296,319, Cl. 250-227.000.
- Frantello, Alfred A.; and Kefauver, Lester R., to Corinco, Inc. Balanced mower head for carrying a plurality of monofilament lines. 4,295,324, Cl. 56-12.700.
- Franz Plasser Bahnmaschinen-Industriegesellschaft m.b.H.: See—
Theurer, Josef; and Riessberger, Klaus, 4,295,764, Cl. 409-296.000.
- Fraser, David R., to United States of America, Health and Human Services. Washer for resin-coated photographic prints. 4,295,730, Cl. 354-325.000.
- Frechet, Daniel: See—
Nedelec, Lucien; Frechet, Daniel; and Dumont, Claude, 4,296,126, Cl. 424-316.000.
- Freeman Chemical Corporation: See—
Cordts, Howard P.; and Karloske, Joan E., 4,295,907, Cl. 156-246.000.
- Frei, Willi. Process for the production of a tubular heat exchanger, and a tubular heat exchanger produced according to this process. 4,295,522, Cl. 165-79.000.
- Freller, Walter: See—
Artweger, Wolfgang; and Freller, Walter, 4,295,679, Cl. 296-171.000.
- Freundlinger, Ernst; and Hirschvogel, Alfred, to Sigr Elektrographit GmbH. Flexible graphite sheet, material or layer containing metal molybdate. 4,296,177, Cl. 428-408.000.
- Frey, Gunter: See—
Berger, Dieter; Braun, Franz; Frey, Gunter; Guthlein, Werner; and Kuhr, Manfred, 4,296,202, Cl. 435-29.000.
- Fried, Krupp Gesellschaft mit beschränkter Haftung: See—
Haaf, Friedrich, 4,295,938, Cl. 202-248.000.
- Frielinghaus, Rainer: See—
Ganglbauer, Otto; Wallner, Felix; Scheidl, Helmut; Reindl, Hermann; and Frielinghaus, Rainer, 4,295,375, Cl. 73-582.000.
- Friese, Karl-Hermann, to Robert Bosch GmbH. Method to apply multiple layers, including an electrode layer, on a sintered or pre-sintered ion conductive solid electrolyte body. 4,296,148, Cl. 427-125.000.
- Frijns, Leon H. B.: See—
Jongsma, Cornelis; Frijns, Leon H. B.; and Raven-Donners, Paula A. M., 4,296,245, Cl. 562-494.000.
- Frontier Industries, Inc.: See—
Boswell, George T., 4,295,290, Cl. 46-74.00C.
- Frost, George H. Combined lens cap and sunshade for a camera. 4,295,706, Cl. 350-58.000.
- Frost, John W., to W. R. Grace & Co. Variable speed drive. 4,295,383, Cl. 474-83.000.
- Fuhrer, Reginald S.: See—
Philpott, Arthur; and Fuhrer, Reginald S., 4,295,391, Cl. 74-782.000.
- Fuji Photo Film Co., Ltd.: See—
Kawaziri, Kazuhiro; Fujiwara, Masato; Hatanaka, Isamu; Tabei, Masatoshi; Higashi, Akio; and Nirasawa, Mitsuharu, 4,296,422, Cl. 346-160.000.
- Oosaka, Shigenori; and Murakoshi, Makoto, 4,295,589, Cl. 226-122.000.
- Yagihara, Morio; and Yokota, Yukio, 4,296,199, Cl. 430-551.000.
- Yagihara, Morio; and Yokota, Yukio, 4,296,200, Cl. 430-551.000.
- Fuji Photo Optical Co., Ltd.: See—
Numata, Saburo, 4,295,716, Cl. 354-30.000.
- Fujii, Hiroshi: See—
Yasuura, Seishi; Teranuma, Jun; Shinzawa, Motohiro; and Fujii, Hiroshi, 4,295,455, Cl. 123-569.000.
- Fujii, Shigeo: See—
Mikami, Takashi; Fujii, Shigeo; Okano, Shuji; and Ikeda, Tokuzo, 4,295,809, Cl. 425-72.00S.
- Fujimori, Ryo: See—
Fujiwara, Toshihide; and Fujimori, Ryo, 4,295,949, Cl. 204-180.00G.
- Fujioka, Tadashi: See—
Nomura, Hirokazu; and Fujioka, Tadashi, 4,296,306, Cl. 219-124.340.
- Fujitsu Fanuc Limited: See—
Fukuyama, Hiroomi; and Isobe, Shinichi, 4,296,364, Cl. 318-572.000.
- Imazeki, Ryoji; and Yamazaki, Etuo, 4,296,473, Cl. 364-520.000.
- Fujiwara, Kunio: See—
Shiraishi, Satoshi; Fujiwara, Kunio; and Kurosaki, Shiro, 4,295,869, Cl. 65-3.110.
- Fujiwara, Masato: See—
Kawaziri, Kazuhiro; Fujiwara, Masato; Hatanaka, Isamu; Tabei, Masatoshi; Higashi, Akio; and Nirasawa, Mitsuharu, 4,296,422, Cl. 346-160.000.
- Fujiwara, Toshihide; and Fujimori, Ryo, to Olympus Optical Co., Ltd. Method for determining boundary points in electrophoresis. 4,295,949, Cl. 204-180.00G.
- Fukatsu, Akihiro; and Tada, Isao, to Toshiba Corporation. Magnetron with cooling means. 4,296,355, Cl. 315-39.510.

- Fukuda, Minoru: See—
Wada, Yoshimasa; Yamazaki, Sigeaki; Kobayashi, Isamu; Haraguchi, Noriyuki; and Fukuda, Minoru, 4,295,780, Cl. 414-749.000.
- Fukui, Masahisa: See—
Shinmi, Akira; Fukui, Masahisa; Hara, Toshitami; Shirato, Yoshiaki; and Hajimoto, Yoshiaki, 4,296,309, Cl. 219-216.000.
- Fukui, Osamu, to Takara Co., Ltd. Toy figure having repositionable head and limbs, 4,295,291, Cl. 46-161.000.
- Fukui, Shosin; and Akazawa, Tadashi, to Daikin Kogyo Co., Ltd. Perfluoroalkyl-acrylate, hydroxy-chloropropyl-acrylate polymer, 4,296,224, Cl. 526-243.000.
- Fukunaga, Yasushi: See—
Bandoh, Tadaaki; and Fukunaga, Yasushi, 4,296,468, Cl. 364-200.000.
- Fukuyama, Hiroomi; and Isobe, Shinichi, to Fujitsu Fanuc Limited. Tool compensation system, 4,296,364, Cl. 318-572.000.
- Fuller, Harrison W.; and Stromswold, Chester E., to Sanders Associates, Inc. Crimped coax reflective dispersive delay line, 4,296,389, Cl. 333-160.000.
- Furukawa, Yoshimi: See—
Sano, Shoichi; and Furukawa, Yoshimi, 4,295,657, Cl. 280-91.000.
- Furusawa, Kahei: See—
Nakai, Taichiro; Furusawa, Kahei; and Ejiri, Yoshihiro, 4,295,707, Cl. 350-96.200.
- Fuseya, Shigeaki; and Ichisaka, Teruo, to Chlorine Engineers Corp., Ltd. Filter press type ion exchange membrane-method electrolysis cell, 4,295,953, Cl. 204-257.000.
- Futamura, Kenichiro: See—
Iwahana, Keiiti; Mathuda, Yoshimi; and Futamura, Kenichiro, 4,296,183, Cl. 428-653.000.
- G. H. Products, Inc.: See—
Griffin, Kary A., 4,295,319, Cl. 52-785.000.
- Gagliani, John; and Sorathia, Usman A. K., to International Harvester Company. Methods of preparing polyimides and polyimide precursors, 4,296,208, Cl. 521-77.000.
- Gagnon, Peter R.: See—
Kimball, Stephen F.; and Gagnon, Peter R., 4,296,351, Cl. 313-222.000.
- Gale, John A., to A.P.V. Spiro-Gills Limited. Water chilling plant, 4,295,341, Cl. 62-100.000.
- Galloway, Tod R., to Fox Valley Process Systems & Supply, Inc. Double angled-disc diverter valve or the like, 4,295,491, Cl. 137-625.460.
- Gambro Dialysatoren GmbH & Co. KG.: See—
Rosemeier, Friedrich; and Killmaier, Horst, 4,295,495, Cl. 138-89.000.
- Ganglbauer, Otto; Wallner, Felix; Scheidl, Helmut; Reindl, Hermann; and Frielinghaus, Rainer, to Voest-Alpine Aktiengesellschaft; and Krautkraemer GmbH. Ultrasonic method of testing welded joints, 4,295,375, Cl. 73-582.000.
- Garcia, Felix, Jr.; Hergert, Roger A.; Mann, Don C.; and Brown, Sheldon H., to Texas Instruments Incorporated. Recording cartridge having a flat smoothing plane with a raised portion, 4,296,448, Cl. 360-135.000.
- Garman, Ronald H., to Caterpillar Tractor Co. Window clip retainer, 4,295,306, Cl. 52-208.000.
- Garnache, Richard R.; and Kenney, Donald M., to International Business Machines Corporation. Method for providing self-aligned conductor in a V-groove device, 4,295,924, Cl. 156-643.000.
- Garner, Robert: See—
Petitpierre, Jean C.; and Garner, Robert, 4,295,663, Cl. 282-27.500.
- Garrison, Judd F., to John Thomas Batts, Inc. Multi-piece hanger, 4,295,585, Cl. 223-96.000.
- Gascoyne, John M.: See—
Rowse, David G.; Gascoyne, John M.; and Hems, Roger, 4,296,093, Cl. 424-45.000.
- Gaspar, Randal. Jet sled spoil scoop apparatus, 4,295,757, Cl. 405-163.000.
- Gass, John C.; Kerr, Noel C.; and Pittmann, Robert W., to Texaco Inc. Method for forming remotely actuated gas lift systems and balanced valve systems made thereby, 4,295,795, Cl. 417-111.000.
- Gates, Allen P.: See—
Harper, Terence; and Gates, Allen P., 4,296,194, Cl. 430-176.000.
- Gates Rubber Company, The: See—
Bixby, Guy T., 4,295,496, Cl. 138-122.000.
- Gauchel, Peter; and Wissinger, Waldemar, to Dynamit Nobel Aktiengesellschaft. Process for the extrusion of coated skein-shaped profiles, preferably of thermoplastic synthetic resins, 4,296,062, Cl. 264-173.000.
- Gauthier, Michel: See—
Poirier, Marc; Gauthier, Michel; and Belanger, Andre, 4,295,939, Cl. 204-1.00T.
- Gavin, John H.: See—
Adams, John E.; Evans, Robert F.; and Gavin, John H., 4,295,254, Cl. 29-33.00M.
- Gee, Charles E., deceased. Convertible sun shade, 4,295,481, Cl. 135-5.00R.
- Gehrig, Heinz: See—
Knopp, Hans; Herion, Dieter; Conzelmann, Gerhard; and Gehrig, Heinz, 4,295,253, Cl. 28-255.000.
- Gehrke, Gunter: See—
Duchardt, Karl H.; and Gehrke, Gunter, 4,296,044, Cl. 260-381.000.
- Geisthoff, Hubert; and von Allwoerden, Wilhelm, to Jean Walterscheid GmbH. Adjustable length upper guide member, 4,295,389, Cl. 74-586.000.
- Genco, Vito; and Turco, Vincenzo L., to Snia Viscosa Societa Nazionale Industria Applicazioni Viscosa S.p.A. Plastic wads and wad assemblies for shot cartridges, 4,295,426, Cl. 102-451.000.
- General Dynamics Corporation: See—
Couchman, James C., 4,295,377, Cl. 73-761.000.
- General Electric Company: See—
Berlec, Ivan; and McCarty, Lewis V., 4,296,352, Cl. 313-315.000.
- Eichelberger, Charles W.; Dehn, Rudolph A.; and Wojnarowski, Robert J., 4,296,296, Cl. 219-10.55B.
- Eichelberger, Charles W., 4,296,449, Cl. 361-3.000.
- Jenkins, Thomas E., 4,295,692, Cl. 312-228.000.
- Kruszona, Edward G., 4,295,439, Cl. 118-317.000.
- Milkovic, Miran, 4,296,413, Cl. 340-870.380.
- Miller, Matthew S., 4,296,297, Cl. 219-10.55F.
- Mirabella, Paul J., 4,296,329, Cl. 250-491.000.
- Patenaude, Raymond A.; Duke, Steven R.; and Proulx, Edward A., 4,295,410, Cl. 89-12.000.
- Paule, Denis R.; and Zamek, Otto S., 4,296,229, Cl. 528-45.000.
- Rabe, Jerry R., 4,296,344, Cl. 310-184.000.
- Salem, Robert J., 4,296,312, Cl. 219-501.000.
- Simcoe, Robert J., 4,296,335, Cl. 307-200.00B.
- Steyer, William; and Duffy, Robert J., 4,295,332, Cl. 60-264.000.
- Stottmann, Richard L.; and Smith, Peter H., 4,296,299, Cl. 219-10.810.
- Wambach, Allen D., 4,296,021, Cl. 260-40.00R.
- Wilkinson, Stanley B., 4,296,451, Cl. 361-80.000.
- General Foods Corporation: See—
Lazarus, Charles R.; Stahl, Howard D.; and Haas, Gerhard J., 4,296,132, Cl. 426-2.000.
- General Foods Inc.: See—
Miller, Donald B., 4,296,026, Cl. 260-123.500.
- General Motors Corporation: See—
Brandt, Howard C.; and Grabowski, Leonard R., 4,295,384, Cl. 74-424.8NA.
- Johnson, Jesse F., 4,295,791, Cl. 416-241.00B.
- General Semiconductor Co., Inc.: See—
Skanadore, William R., 4,296,336, Cl. 307-300.000.
- General Tire & Rubber Co.: See—
Roper, Ralph E., 4,295,357, Cl. 72-344.000.
- Geosource Inc.: See—
Wendelboe, Fred E., 4,295,369, Cl. 73-261.000.
- Gerard, Andre: See—
Lacombat, Michel; and Gerard, Andre, 4,295,735, Cl. 355-43.000.
- Gerber, Howard L., to Continental Group, Inc., The. Progressive welding and forging of overlapped seams in tubular bodies, 4,296,293, Cl. 219-8.500.
- Gerlach, Robert L., to Perkin-Elmer Corporation, The. Secondary emission mass spectrometer mechanism to be used with other instrumentation, 4,296,323, Cl. 250-289.000.
- Gersi, Julius J.: See—
Griesenauer, Neal M.; and Gersi, Julius J., 4,296,178, Cl. 428-462.000.
- Geurts, Martinus F. A. M., to U.S. Philips Corporation. Clamping circuit for a video signal, 4,296,437, Cl. 358-173.000.
- Ghelardoni, Mario; Pestellini, Vittorio; Del Soldato, Piero; Volterra, Giovanna; and Meli, Alberto, to A. Menarini S.A.S. Pharmaceutical methods, 4,296,124, Cl. 424-285.000.
- Gibbs, Dale S., to Dow Chemical Co., The. Vinylidene chloride polymer microgels, 4,296,013, Cl. 260-29.6TA.
- Gibbs, Ronald L., to Dow Chemical Company, The. Support prepared from organomagnesium compounds and silicon halides; and catalysts for polymerizing olefins, 4,295,992, Cl. 252-429.00C.
- Gibson, Joseph T.; and Duhon, Gerald L., to A. C. Company. Drilling fluid circulating and monitoring system and method, 4,295,366, Cl. 73-155.000.
- Gigot, C. Dean: See—
Williams, Donald E.; Robertson, Forrest E.; Gigot, C. Dean; and Gigot, Terry K., 4,295,532, Cl. 172-184.000.
- Gigot, Terry K.: See—
Williams, Donald E.; Robertson, Forrest E.; Gigot, C. Dean; and Gigot, Terry K., 4,295,532, Cl. 172-184.000.
- Giler, Roger R.: See—
Hagglund, Erik H. M.; and Giler, Roger R., 4,296,311, Cl. 219-464.000.
- Gill, Peter J.: See—
Maresca, Louis M.; Gill, Peter J.; and Berger, Mitchell H., 4,296,232, Cl. 528-179.000.
- Gilleland, Randall C.: See—
Bell, Oliver A., Jr.; Gilleland, Randall C.; and Chance, Davey J., 4,296,302, Cl. 219-69.00G.
- Gilles, Jean, to Thomson-CSF. Process for producing an MOS-transistor and a transistor produced by this process, 4,296,426, Cl. 357-23.000.
- Gilmore, James E.: See—
Johnson, Harry D.; Campbell, Christopher J.; Turner, Thomas O.; Poole, Carl W.; Gilmore, James E.; and Thomas, James R., 4,295,337, Cl. 62-54.000.
- Gilmour, Alfred J., to Auto-Flush Systems Ltd. Automatic glass fragmentation decontaminating system for glass containers, 4,295,503, Cl. 141-90.000.
- Girling Limited: See—
Quiney, Kenneth M., 4,295,548, Cl. 188-72.700.
- Giuffrè, Luigi: See—
de Nora, Oronzio; Giuffrè, Luigi; and Modica, Giovanni, 4,295,952, Cl. 204-252.000.

- Glantz, Per-Olof: See—
Hoppe, Udo; Sauermann, Gerhard; Curts, Julius; Glantz, Per-Olof; Krasse, Bo; Larsson, Kare; Noren, Borje; Odham, Goran; and Olsson, Jan, 4,296,095, Cl. 424-52.000.
- Gloor, Hans, to Concast AG. Method and apparatus for measuring out a strand guide arrangement, 4,295,278, Cl. 33-182.000.
- Goebel, Franz: See—
Barnes, John E.; Goebel, Franz; and McHugh, William T., 4,296,187, Cl. 429-105.000.
- Goodall, Richard B.; and Goodall, Richard L., to Dixon Valve & Coupling Co. Quick-disconnect cam locking safety coupling, 4,295,670, Cl. 285-91.000.
- Goodall, Richard L.: See—
Goodall, Richard B.; and Goodall, Richard L., 4,295,670, Cl. 285-91.000.
- Goodwin, Frank E.: See—
Flemings, Merton C.; and Goodwin, Frank E., 4,295,896, Cl. 148-1.000.
- Goodyear Tire & Rubber Company, The: See—
Lovell, John A.; and McIntosh, Kenneth W., 4,295,513, Cl. 152-358.000.
- Gorchev, Dimitir; Ingard, Karl U.; and Willke, Herbert L., Jr., to Mitco Corporation. Air distribution system, 4,295,416, Cl. 98-33.00R.
- Gordon, Roy G. Low temperature catalytic reduction, 4,295,986, Cl. 252-188.000.
- Goschke, Richard: See—
Sallmann, Alfred; and Goschke, Richard, 4,296,128, Cl. 424-309.000.
- Goto, Daisaku: See—
Ishihara, Takeshi; Goto, Daisaku; and Sugiura, Hitoshi, 4,296,276, Cl. 174-179.000.
- Goux, Jacques, to Automobiles Peugeot; and Societe Anonyme Automobiles Citroen. Device for initiating in particular the ignition of an internal combustion engine, 4,296,471, Cl. 364-424.000.
- Grabchev, Boris L.: See—
Lifshits, Viktor S.; Krivoson, Vadim P.; Podola, Nikolai V.; Grabchev, Boris L.; Andrianov, Vladimir R.; and Shakhov, Rifkhat M., 4,296,305, Cl. 219-101.000.
- Grabner, Roy; and Paul, Edward L., to Merck & Co., Inc. Use of motionless mixer as cell culture propagator, 4,296,204, Cl. 435-235.000.
- Grabowski, Leonard R.: See—
Brandt, Howard C.; and Grabowski, Leonard R., 4,295,384, Cl. 74-424.8NA.
- Graham, Finlay M. Fire escape apparatus, 4,295,543, Cl. 182-3.000.
- Graham, Henry A., Jr.; Olekna, David J.; Hawk, Johnna B.; and Barrett, Diane M., to Ortho Diagnostics, Inc. Anti-D test and reagent, 4,296,090, Cl. 424-11.000.
- Granada, Wilfredo A. Reading stand, 4,295,624, Cl. 248-456.000.
- Grane, Henry R.; Jubin, John C., Jr.; and Worrell, G. Richard, to Atlantic Richfield Company. Manufacture of tertiary butyl alcohol, 4,296,262, Cl. 568-910.000.
- Grantmyre, Innes; and Miedema, Brent, to Joy Manufacturing Company. Impactor, 4,295,411, Cl. 91-165.000.
- Grasso, Michael. Utility bucket seat, 4,295,680, Cl. 297-193.000.
- Graves, Kevin, to UOP Inc. Spring suspensions for vehicle seats, 4,295,627, Cl. 248-588.000.
- Gray, Vincent F., to Western Electric Company, Incorporated. Strain relief for connector wires, 4,295,696, Cl. 339-17.00C.
- Greci, John J.: See—
Bascom, Hollis H.; Matweyou, Stephen; Andersen, Alan J.; and Greci, John J., 4,295,905, Cl. 156-174.000.
- Green, Douglas F., to Royer Mowers (Aust.) Pty. Ltd. Self-propelled flail blade lawn mower, 4,295,326, Cl. 56-11.300.
- Green, Milton, to United States of America, Navy. Pressure sensitive line transducer, 4,296,487, Cl. 367-169.000.
- Greenhill, Derek H.: See—
Ashton, Christopher J.; Diamond, Andrew C.; and Greenhill, Derek H., 4,295,754, Cl. 403-369.000.
- Greenwood, Gillian M.; and Woodstock, Alan, to Imperial Chemical Industries Limited. Solvent compositions, 4,295,888, Cl. 106-21.000.
- Greer Hydraulics, Incorporated: See—
Card, Lorin P.; and Borsting, Otto W., 4,295,630, Cl. 251-14.000.
- Zahid, Abdul, 4,295,492, Cl. 138-30.000.
- Gregory, Leslie A., to UOP Inc. Seat having lumbar support and vertical height adjustment mechanism therefor, 4,295,681, Cl. 297-284.000.
- Gresch, Heinz: See—
Holler, Heinz; Gresch, Heinz; Igelbuscher, Heinrich; Hubner, Kurt; and Weber, Ekkehard, 4,295,868, Cl. 55-302.000.
- Gresham, John T., to Avtex Fibers Inc. Flame-retardant polyester fiber compositions, 4,295,886, Cl. 106-18.190.
- Griesenauer, Neal M.; and Gersi, Julius J., to Varian Associates, Inc. Article comprising a substrate and chromium alloy coating, 4,296,178, Cl. 428-462.000.
- Griffin, Kary A., to G. H. Products, Inc. Floor panel, 4,295,319, Cl. 52-785.000.
- Grigoleit Company, The: See—
Howie, Robert K., Jr., 4,295,246, Cl. 16-121.000.
- Grim, George B.: See—
Cemenska, Richard A.; and Grim, George B., 4,295,449, Cl. 123-300.000.
- Grime, Paul R., to Owens-Corning Fiberglass Corporation. Electrical power distribution system principally for space-dividing panels in office buildings, 4,295,697, Cl. 339-22.00R.
- Grinage, Kim D. Keyhole sighter, 4,295,350, Cl. 70-454.000.
- Grollier, Jean F.; Bugaut, Andree; Andriillon, Patrick; and Fourcadier, Chantal, to L'Oreal. Composition for hair dyeing which contains a para base and an ortho base, 4,295,848, Cl. 8-421.000.
- Grote, Daniel; Raymond, Duane; and Mosher, Joseph C., to Thermoplastics, Inc. Method of making truck bed cover assembly, 4,295,262, Cl. 29-462.000.
- Gruber, Robert J.; Bolte, Steven B.; Knapp, John F.; Ims, Dale R.; and Lewis, Richard B., to Xerox Corporation. Electrostatic toner composition, 4,296,192, Cl. 430-109.000.
- GTE Automatic Electric Laboratories, Inc.: See—
Lee, Man S., 4,296,392, Cl. 333-213.000.
- GTE Products Corporation: See—
Barnes, John E.; Goebel, Franz; and McHugh, William T., 4,296,187, Cl. 429-105.000.
- Kimball, Stephen F.; and Gagnon, Peter R., 4,296,351, Cl. 313-222.000.
- Maya, Jakob, 4,296,350, Cl. 313-26.000.
- Walter, Wolfgang, 4,296,353, Cl. 313-487.000.
- Guerit, Pierre: See—
Hicet, Jean-Marie; and Guerit, Pierre, 4,295,884, Cl. 75-93.00R.
- Guex, Woldemar; Klauel, Heinrich; Pauling, Horst; and Voirol, Felix. Reusable heat devices containing xylitol as the heat-storage material, 4,295,517, Cl. 165-1.000.
- Gulf Research & Development Company: See—
Innes, Robert A.; and Kehl, William L., 4,296,046, Cl. 260-465.300.
- Gulf & Western Corporation: See—
Rich, Leonard G., 4,296,405, Cl. 340-146.3AG.
- Gunderson, Gary M.: See—
Locatelli, John D.; and Gunderson, Gary M., 4,295,599, Cl. 229-34.00R.
- Gunn, Duncan A., to International Standard Electric Corporation. Electrical connector for submarine repeaters or the like, 4,295,701, Cl. 339-94.00A.
- Gunter, Thomas G.; Tredennick, Harry L.; and McAlister, Doyle V., to Motorola, Inc. Execution unit for data processor using segmented bus structure, 4,296,469, Cl. 364-200.000.
- Gurin, Vasily N.: See—
Anisimov, Vyacheslav I.; Bulgakov, Evgeny G.; Gurin, Vasily N.; Radjuevich, Leonid V.; Trishevsky, Igor S.; Trishevsky, Oleg I.; Kheifets, Grigory R.; and Jurchenko, Anatoly B., 4,295,353, Cl. 72-180.000.
- Gurr, George P., to Sangamo Weston, Inc. Inverter controller, 4,296,462, Cl. 363-96.000.
- Gutekunst, Ferdinand; and Schmid, Rolf, to Ciba-Geigy Corporation. Curable epoxide resin mixtures, 4,296,231, Cl. 528-93.000.
- Guthlein, Werner: See—
Berger, Dieter; Braun, Franz; Frey, Gunter; Guthlein, Werner; and Kuhr, Manfred, 4,296,202, Cl. 435-29.000.
- Guttinger, Kurt, to Sodeco-SAIA SA. Self-starting single-phase synchronous motor, 4,296,341, Cl. 310-41.000.
- Gutzwiller, Howard L., to Robinson Industries, Inc. Cover plates for tank heads, 4,295,789, Cl. 416-213.00A.
- Guyer, James M.; and West, Joseph T., to Data General Corporation. Data processing system including a separate input/output processor with micro-interrupt request apparatus, 4,296,466, Cl. 364-200.000.
- H. L. Plast H. Lundvall AB: See—
Westberg, Ake G., 4,295,288, Cl. 40-16.400.
- Haaf, Friedhelm, to Fried. Krupp Gesellschaft mit beschränkter Haftung. Coke-oven door assembly, 4,295,938, Cl. 202-248.000.
- Haage, Karl; and Scharff, Dieter, to Dynamit Nobel Aktiengesellschaft. Protective layer for surface seals in building construction, underground construction, and civil engineering construction, 4,295,911, Cl. 156-315.000.
- Haas, Eduard, to Centromint Company Establishment. Tablet dispenser, 4,295,579, Cl. 221-229.000.
- Haas, Gerhard J.: See—
Lazarus, Charles R.; Stahl, Howard D.; and Haas, Gerhard J., 4,296,132, Cl. 426-2.000.
- Haberl, John B., to United States of America, Navy. Flexible loop slip ring brush, 4,296,345, Cl. 310-219.000.
- Haberli, Roland; Mollet, Hans; and Scherer, Gustaaf, to Ciba-Geigy Corporation. Commercial preparations of dry organic substances, 4,295,850, Cl. 8-524.000.
- Hachenberg, Horst: See—
Wunder, Friedrich; Leupold, Ernst I.; Hachenberg, Horst; and Schmidt, Hans-Joachim, 4,296,266, Cl. 585-640.000.
- Hachiro, Nobuaki, to Nissin Kogyo Kabushiki Kaisha. Hose with a one-way valve for a vacuum operated servomotor, 4,295,412, Cl. 91-468.000.
- Hada, Hiroshi: See—
Hirayama, Tsutomu; and Hada, Hiroshi, 4,296,357, Cl. 315-169.400.
- Haensel, Eckhart, to Siemens Aktiengesellschaft. Method and circuit arrangement for switching and transmitting signals in, or from, a stored program controlled switching system, 4,296,403, Cl. 340-147.00P.
- Hafer, Edward H., to Bell Telephone Laboratories, Incorporated. Continuity verification arrangement, 4,296,492, Cl. 370-14.000.
- Hagberg, Gideon, to Berg, Gunner; and Stroberg, Sven-Olle. Magnetic fuel purifier with rotating pre-purifier, 4,295,969, Cl. 210-223.000.
- Hagerstrom, John R.: See—
Lennon, Donald J. J.; Hagerstrom, John R.; and Ekman, C. Frederick W., 4,296,176, Cl. 428-407.000.
- Hagglund, Erik H. M.; and Giler, Roger R., to Kanthal Corporation, The. Electric hot plate, 4,296,311, Cl. 219-464.000.

- Hagihara, Noboru, to TOA Valve Co. Ltd. Manufacturing method of the valve disk of spring loaded safety valves. 4,296,307, Cl. 219-121.0ED.
- Hahlganss, Gunter, to VDO Adolf Schindling AG. Apparatus for electrically connecting a plurality of contacts. 4,296,457, Cl. 361-413.000.
- Hall, Harry K., to Litton Resources Systems, Inc. Method and means for measuring geophone parameters. 4,296,483, Cl. 367-13.000.
- Hajimoto, Yoshioki: See—
Shinmi, Akira; Fukui, Masahisa; Hara, Toshitami; Shirato, Yoshiaki; and Hajimoto, Yoshioki, 4,296,309, Cl. 219-216.000.
- Hakoi, Tsutomu, to Yoshida Kogyo K.K. Automatic selection and delivery apparatus of assembled mechanical parts. 4,295,570, Cl. 209-657.000.
- Halliburton Company: See—
Baker, Eugene E.; and Szarka, David D., 4,295,524, Cl. 166-278.000.
McMahan, Michael E., 4,295,361, Cl. 73-40.50R.
- Halpaap, Herbert; and Krebs, Karl-Friedrich, to Merck Patent Gesellschaft mit beschränkter Haftung. Separating materials for thin layer chromatography and their preparation. 4,295,968, Cl. 210-198.300.
- Hampton, Robert S., Jr.: See—
Spainhour, Phillip A.; Morrison, Leonard A.; and Hampton, Robert S., Jr., 4,295,634, Cl. 254-10.500.
- Hanada, Toshiro: See—
Kasahara, Shizuka; Yamanishi, Kazuhiko; Hanada, Toshiro; Tokuda, Kuniaki; and Kobatake, Shinzo, 4,295,853, Cl. 23-230.00B.
- Handotai Kenkyu Shinkokai: See—
Nishizawa, Jun-ichi, 4,296,425, Cl. 357-17.000.
- Hannesen, Kurt: See—
Bergner, Dieter; Hannesen, Kurt; Muller, Wolfgang; and Schulte, Wilfried, 4,295,945, Cl. 204-128.000.
- Hannett, William J.; Brendel, Thomas E.; and Wilson, David S., to Carrier Corporation. Refrigeration unit with water. 4,295,344, Cl. 62-324.500.
- Hansen, Gert: See—
Schmidt, Karl-Julius; Schmidt, Friedrich; Siegle, Peter; and Hansen, Gert, 4,296,047, Cl. 260-974.000.
- Hansen, Roger M., to Stratabol Corporation. Post tensionable grouted anchor assembly. 4,295,761, Cl. 405-261.000.
- Hanzel, Robert S.; and Sauer, Paul J., to Du Pont de Nemours, E. I., and Company. Spandex filaments containing certain metallic soaps. 4,296,174, Cl. 428-389.000.
- Hara, Shigeyoshi; and Yamada, Tateyoshi, to Teijin Limited. Heat-curable and solvent-soluble ester group-containing polymer compositions and process for their preparation. 4,296,218, Cl. 525-439.000.
- Hara, Toshitami; Sato, Yashushi; Takatori, Yasushi; and Shirato, Yoshiaki, to Canon Kabushiki Kaisha. Ink jet recording device using thermal propulsion and mechanical pressure changes. 4,296,421, Cl. 346-140.00R.
- Hara, Toshitami: See—
Shinmi, Akira; Fukui, Masahisa; Hara, Toshitami; Shirato, Yoshiaki; and Hajimoto, Yoshioki, 4,296,309, Cl. 219-216.000.
- Harader, Wayne R., to E-Systems, Inc. Dual mode log periodic monopole array. 4,296,416, Cl. 343-792.500.
- Haraguchi, Noriyuki: See—
Wada, Yoshimasa; Yamazaki, Sigeki; Kobayashi, Isamu; Haraguchi, Noriyuki; and Fukuda, Minoru, 4,295,780, Cl. 414-749.000.
- Harashima, Noboru: See—
Kawamura, Toshio; Harashima, Noboru; Ueda, Hideo; and Sano, Seijiro, 4,295,654, Cl. 277-92.000.
- Haraszi, Tegzi P., to Rockwell International Corporation. Merged field effect transistor circuit and fabrication process. 4,296,428, Cl. 357-41.000.
- Hardware Designers, Inc.: See—
Blasnik, William, 4,295,688, Cl. 308-3.800.
- Harman, Maurice: See—
Caplin, Peter B.; and Harman, Maurice, 4,295,817, Cl. 431-7.000.
- Harper, Terence; and Gates, Allen P., to Vickers Limited. Positive-working light sensitive diazo materials with azo dye. 4,296,194, Cl. 430-176.000.
- Harrington, Alan L.; Rodov, Vladimir; and Allison, Richard, to TRW Inc. Two-mask VJ-FET transistor structure. 4,295,267, Cl. 29-571.000.
- Harris Corporation: See—
Buck, Gordon K.; and Kozin, Cynthia H., 4,295,363, Cl. 73-117.300.
Schroeder, James E., 4,296,429, Cl. 357-55.000.
- Harris, Jeff B. Adjustable neck attachment for stringed instruments. 4,295,403, Cl. 84-293.000.
- Harris, Wilford D., to Dow Chemical Company, The. Method of injection molding thermoplastic resinous products substantially free from sink marks, swirls and related blemishes. 4,296,055, Cl. 264-45.500.
- Harrold, Ronald T.; and Ottenberg, Lawrence E., to Electric Power Research Institute, Inc. Atomized dielectric fluid composition with high electrical strength. 4,296,003, Cl. 252-570.000.
- Hartmann, Gerhard: See—
Becker, Reinhold; Michel, Wolfgang; and Hartmann, Gerhard, 4,295,563, Cl. 206-205.000.
- Hartmann, Kurt, to International Business Machines Corporation. Arrangement for feeding electrodes in metal paper printers. 4,295,746, Cl. 400-119.000.
- Hartmann, Rudolf: See—
Schuberth, Christian; and Hartmann, Rudolf, 4,296,292, Cl. 200-336.000.
- Haruta, Masahiro: See—
Eida, Tsuyoshi; Haruta, Masahiro; Yano, Yasuhiro; Matsufuji, Yoji; and Ohta, Tokuya, 4,295,889, Cl. 106-22.000.
- Harvey, George R.: See—
Middlebrook, Robert E.; Harvey, George R.; and Chupp, John P., 4,296,254, Cl. 564-214.000.
- Harvey, William A.: See—
Nelson, Gary L.; and Harvey, William A., 4,295,988, Cl. 252-584.000.
- Hasegawa, Haruo; Taniguchi, Hiroyoshi; and Igawa, Takao, to Ricoh Co., Ltd. Photosensitive material for use in electrophotography with a radiation cured binder resin. 4,296,190, Cl. 430-57.000.
- Hashido, Akiyoshi: See—
Sakaguchi, Tadahiyo; Hino, Masamichi; Tsuji, Setsuo; Hashido, Akiyoshi; and Enomoto, Kazuyoshi, 4,295,915, Cl. 156-361.000.
- Haslop, John M.; Knapman, Reginald G.; and West, Michael A., to Thomas De La Rue & Company Limited. Watermark detection. 4,296,326, Cl. 250-372.000.
- Hasselmann, Detlev E. M. Gasoline vapor recovery system. 4,295,504, Cl. 141-290.000.
- Hasselmann, Detlev E. M.; and Labonte, Paul D. Gasoline vapor recovery system. 4,295,505, Cl. 141-301.000.
- Hasslauer, Heinz, to Hermann Traub GmbH & Co. Bar feeding mechanism for machines for working rotating bar stock. 4,295,396, Cl. 82-1.00C.
- Hatanaka, Isamu: See—
Kawaziri, Kazuhiro; Fujiwara, Masato; Hatanaka, Isamu; Tabei, Masatoshi; Higashi, Akio; and Nirasawa, Mitsuharu, 4,296,422, Cl. 346-160.000.
- Hatta, Masami; Iwata, Katsumi; and Sasaki, Masao, to Hitachi Metals Precision, Ltd. Automatic coating system for lost wax process. 4,295,444, Cl. 118-668.000.
- Hattori, Naohiko: See—
Teramura, Hiroichi; Yamazaki, Yasuhiro; Wakahara, Yasushi; Hattori, Naohiko; Yamamoto, Seiichi; and Nakao, Kouzo, 4,296,439, Cl. 358-257.000.
- Hatzikis, Christopher: See—
Madonia, Ciro N.; Hatzikis, Christopher; and Cosentino, Cesare C., 4,296,155, Cl. 428-31.000.
- Hauk, Ernest D.; and Stewart, Larry, to Service Equipment Design Co., Inc. Method and apparatus for connecting steel pipe sections. 4,295,526, Cl. 166-315.000.
- Haus, Artur: See—
Nonn, Konrad; Wolf, Karlheinz; Haus, Artur; and Hornle, Reinhold, 4,295,849, Cl. 8-524.000.
- Hauser, H. William, to Vinings Chemical Company. Method of manufacturing aluminum sulfate from flue gas. 4,296,079, Cl. 423-242.000.
- Hautala, Earl: See—
Camirand, Wayne M.; Randall, John M.; and Hautala, Earl, 4,295,333, Cl. 60-641.600.
- Hawk, Johnna B.: See—
Graham, Henry A., Jr.; Olekna, David J.; Hawk, Johnna B.; and Barrett, Diane M., 4,296,090, Cl. 424-11.000.
- Hawley, Gil R., to Phillips Petroleum Company. Selenium or tellurium treated silica. 4,295,998, Cl. 252-439.000.
- Hawley, Gil R., to Phillips Petroleum Company. Titanium impregnated silica-chromium catalysts. 4,296,001, Cl. 252-458.000.
- Hayashi, Masaaki; Sasaki, Hiroharu; and Tsuneta, Kazuyoshi, to Dai Nippon Toray Co., Ltd. Aqueous dispersion type thermosetting coating composition. 4,296,014, Cl. 260-29.6NR.
- Hayashi, Masaharu, to Aisin Seiki Kabushiki Kaisha. Viscous fluid coupling device. 4,295,550, Cl. 192-58.00B.
- Hayashibara, Ken: See—
Sugimoto, Kaname, 4,296,025, Cl. 260-112.00R.
- Hazama, Katashi; and Yuhara, Akitsuna, to Hitachi, Ltd. Surface-acoustic-wave filter for channel selection system of television receiver. 4,296,391, Cl. 333-193.000.
- Healthco Inc.: See—
Lustgarten, Stewart J., 4,295,941, Cl. 204-35.00R.
- Heckmann, Werner, to Holstein und Kappert GmbH. Device for conveying containers. 4,295,558, Cl. 198-440.000.
- Heeb, Adolf, to Interliz Anstalt. Heating boiler and temperature control therefor. 4,295,447, Cl. 122-136.00R.
- Heidelberger Druckmaschinen Aktiengesellschaft: See—
Thunker, Norbert, 4,295,422, Cl. 101-232.000.
- Heidemeyer, Paulus: See—
Zimmermann, Frank; Heidemeyer, Paulus; and Bigalke, Erhard, 4,295,551, Cl. 192-0.076.
- Heimerl, Joseph: See—
Stephan, Herbert; Aichert, Hans; and Heimerl, Joseph, 4,295,808, Cl. 425-8.000.
- Heinz, Theodore A., to Rockwell International Corporation. Deformable mirror with dither. 4,295,710, Cl. 350-310.000.
- Helfer, Friedrich; Elsner, Ernst; and Zaiser, Wolfgang, to Voith Getriebe KG. Progressive torque transmission in leaf-spring coupling. 4,295,348, Cl. 64-27.00L.
- Hems, Roger: See—
Roswell, David G.; Spring, David J.; and Hems, Roger, 4,296,255, Cl. 564-215.000.
- Rowell, David G.; Gascoyne, John M.; and Hems, Roger, 4,296,093, Cl. 424-45.000.
- Hengartner, Urs, to Hoffmann-La Roche Inc. Preparation of a 1,4-pentadien-3-ol. 4,296,259, Cl. 568-378.000.

- Henkel Corporation: See—
Rogier, Edgar R., 4,296,004, Cl. 260-18.0EP.
- Henkel Kommanditgesellschaft Auf Aktien: See—
Ziche, Horst, 4,296,235, Cl. 536-85.000.
- Hennessy, James W.: See—
Angel, Henry R.; and Hennessy, James W., 4,296,373, Cl. 324-71.0CP.
- Henry Lindsay Limited: See—
Alderton, Gordon H. S., 4,295,770, Cl. 411-531.000.
- Henry, Paul S., to Bell Telephone Laboratories, Incorporated. Wide-band digital spectrometer. 4,296,374, Cl. 324-77.00B.
- Hercules Incorporated: See—
Dumas, David H., 4,295,931, Cl. 162-158.000.
- Hergaux, Claude. Apparatus for lifting waste containers on to trucks. 4,295,778, Cl. 414-525.00R.
- Hergert, Roger A.: See—
Garcia, Felix, Jr.; Hergert, Roger A.; Mann, Don C.; and Brown, Sheldon H., 4,296,448, Cl. 360-135.000.
- Herion, Dieter: See—
Knopp, Hans; Herion, Dieter; Conzelmann, Gerhard; and Gehrig, Heinz, 4,295,253, Cl. 28-255.000.
- Hermann Traub GmbH & Co.: See—
Hasslauer, Heinz, 4,295,396, Cl. 82-1.00C.
- Hermann Wegener Schiffgraben: See—
Bumbalek, Alois J., 4,296,056, Cl. 264-49.000.
- Herpers, Ferdinand J.; Kroll, Harley E.; Carlson, Alfred D.; and Dodge, Paul D., to Tennant Company. Scrubbing machine with water regeneration. 4,295,244, Cl. 15-320.000.
- Herpers, Ferdinand J.: See—
Bricher, Charles W.; and Herpers, Ferdinand J., 4,295,274, Cl. 30-347.000.
- Herschler, Robert J. Therapeutic dimethyl sulfoxide composition and methods of use. 4,296,104, Cl. 424-153.000.
- Herschler, Robert J. Methylsulfonylmethane and methods of use. 4,296,130, Cl. 424-337.000.
- Hesston Corporation: See—
Hill, Amos G., 4,295,616, Cl. 241-241.000.
- Hester, Jackson B., Jr., to Upjohn Company, The. Amino-4H-s-triazolo[4,3-a][1,4]benzodiazepines. 4,296,239, Cl. 546-271.000.
- Heuer, Steven R.; and Zbrank, Zdenka, to Engelhard Min. & Chem. Corp. Recovery of molybdenum values from leach muds. 4,296,077, Cl. 423-53.000.
- Hicter, Jean-Marie; and Guert, Pierre, to Societe de Vente de l'Aluminium Pechiney. Process for treating a molten metal or alloy using liquid and solid flux. 4,295,884, Cl. 75-93.00R.
- Hieber, Udo: See—
Aigle, Karl; Hieber, Udo; Huebscher, Wilhelm; Rheindorf, Hans H.; and Wiedemann, Rolf, 4,296,453, Cl. 361-275.000.
- Hiei, Shoki, to Toyooki Kogyo Kabushiki Kaisha. Lubricator. 4,295,545, Cl. 184-55.00A.
- Higashi, Akio: See—
Kawaziri, Kazuhiro; Fujiwara, Masato; Hatanaka, Isamu; Tabei, Masatoshi; Higashi, Akio; and Nirasawa, Mitsuharu, 4,296,422, Cl. 346-160.000.
- Higgs, Jacob K.; and Avery, Grant D., to Sprague Electric Company. Two-state Hall element proximity sensor device with lamp indicator. 4,296,410, Cl. 340-686.000.
- Higuchi, Seizun; Tano, Kazuhiro; Kamada, Minoru; and Okamoto, Susumu, to Nippon Steel Corporation. Method for coating one side only of steel strip with molten coating metal. 4,296,145, Cl. 427-47.000.
- Hildebrandt, Eugene F.; and Ottersbach, Thomas V., to Emerson Electric Co. Motor starting switch. 4,296,366, Cl. 318-793.000.
- Hildebrecht, Harold V., to Towmotor Corporation. Vehicle brake and engine interlock. 4,295,540, Cl. 180-271.000.
- Hilker, Dennis C., to Honeywell Information Systems Inc. Calibration apparatus for CML circuit test unit. 4,295,359, Cl. 73-5.000.
- Hill, Amos G., to Hesston Corporation. Chopping mechanism with remote shearbar adjuster. 4,295,616, Cl. 241-241.000.
- Hill, Edward D. Ink transfer member. 4,296,172, Cl. 428-331.000.
- Hill, Roy K., to Sperry Corporation. Sprocket hole sensing detector for moving translucent paper sheets. 4,296,332, Cl. 250-570.000.
- Hinds, Virgil A. Crankless reciprocating engine and gyroscopic power transmission system. 4,295,381, Cl. 74-5.00R.
- Hinkel, Lester H.; and Wolske, Lawrence E., to Whirlpool Corporation. Automatic hand washer and drier. 4,295,233, Cl. 4-619.000.
- Hino, Masamichi: See—
Sakaguchi, Tadahiyo; Hino, Masamichi; Tsuji, Setsuo; Hashido, Akiyoshi; and Enomoto, Kazuyoshi, 4,295,915, Cl. 156-361.000.
- Hinrichs, Lansing M.: See—
Fahrig, Robert J.; and Hinrichs, Lansing M., 4,295,961, Cl. 208-161.000.
- Hiraoka & Co., Ltd.: See—
Nakai, Shinzo; and Shimizu, Chitomi, 4,295,440, Cl. 118-412.000.
- Hirata, Akio, to Tokyo Shibaura Denki Kabushiki Kaisha. Speed control method for AC motors and an apparatus for the control. 4,296,367, Cl. 318-808.000.
- Hiratsuka, Motoki: See—
Saito, Tasuku; Noma, Tutomu; Matsunaga, Tsutomu; Naito, Nagayoshi; Tanaka, Chiaki; and Hiratsuka, Motoki, 4,295,652, Cl. 273-235.000.
- Hirayama, Tsutomu; and Hada, Hiroshi, to Nippon Electric Co., Ltd. Plasma display system. 4,296,357, Cl. 315-169.400.
- Hirose, Chuji: See—
Yamaguchi, Takashi; Okuno, Yoshitoshi; and Hirose, Chuji, 4,295,581, Cl. 222-192.000.
- Hirsch, Michael: See—
Diamond, George; Forrester, James; Hirsch, Michael; and Vas, Ran, 4,295,473, Cl. 178-695.000.
- Hirschvogel, Alfred: See—
Freundlinger, Ernst; and Hirschvogel, Alfred, 4,296,177, Cl. 428-408.000.
- Hitachi Chemical Company, Ltd.: See—
Ohtani, Eiichi; Kobayashi, Kengo; Isobe, Asao; and Tanaka, Shigeyoshi, 4,295,947, Cl. 204-159.150.
- Ooki, Norihiro; Motegi, Shoji; Wachi, Yasuyuki; Takikawa, Yoshio; and Yamakawa, Norio, 4,296,346, Cl. 310-242.000.
- Takahashi, Akio; Itoh, Yutaka; Wajima, Motoyo; Morishita, Hirosada; and Nishikawa, Akio, 4,296,219, Cl. 525-488.000.
- Hitachi Denshi Kabushiki Kaisha: See—
Achiha, Masahiko, 4,296,436, Cl. 358-167.000.
- Hitachi Koki Company, Limited: See—
Kubota, Toshifumi, 4,295,272, Cl. 30-276.000.
- Hitachi, Ltd.: See—
Achiha, Masahiko, 4,296,436, Cl. 358-167.000.
Bandoh, Tadaaki; and Fukunaga, Yasushi, 4,296,468, Cl. 364-200.000.
- Hazama, Katashi; and Yuhara, Akitsuna, 4,296,391, Cl. 333-193.000.
- Horiuchi, Masataka; and Katto, Hisao, 4,295,265, Cl. 29-571.000.
- Imai, Kuninori; and Takahashi, Soji, 4,295,595, Cl. 228-161.000.
- Ishikawa, Sakou; Watanabe, Yutaka; and Wakai, Katsuro, 4,296,494, Cl. 371-13.000.
- Nakazima, Kooichi; Kazama, Keizo; and Oki, Hiroshi, 4,295,574, Cl. 220-2.10A.
- Ogiwara, Kenyu; Kawada, Minoru; and Ashida, Teiji, 4,295,781, Cl. 415-1.000.
- Ohara, Ichiro, 4,295,748, Cl. 403-24.000.
- Ooki, Norihiro; Motegi, Shoji; Wachi, Yasuyuki; Takikawa, Yoshio; and Yamakawa, Norio, 4,296,346, Cl. 310-242.000.
- Saito, Cyuichi; and Teranishi, Katsuya, 4,295,556, Cl. 198-325.000.
- Sayo, Kosaku; Suginuma, Atsushi; Tatsumi, Hideo; and Kanamaru, Hisanobu, 4,295,553, Cl. 192-84.00C.
- Tachibana, Keiji; Nakayama, Yoshihiko; Kaneko, Junichi; and Ishii, Susumu, 4,295,792, Cl. 417-15.000.
- Takahashi, Akio; Itoh, Yutaka; Wajima, Motoyo; Morishita, Hirosada; and Nishikawa, Akio, 4,296,219, Cl. 525-488.000.
- Tanaka, Hironari; Matsuyama, Shigeru; Ishibashi, Tadashi; Kinugawa, Kiyoshige; and Sato, Yukihiko, 4,295,711, Cl. 350-334.000.
- Terao, Motoyasu; Shigematsu, Kazuo; Ojima, Masahiro; and Yonezawa, Seiji, 4,296,419, Cl. 346-135.100.
- Hitachi Metals Precision, Ltd.: See—
Hatta, Masami; Iwata, Katsumi; and Sasaki, Masao, 4,295,444, Cl. 118-668.000.
- Hitachi Service Engineering Co., Ltd.: See—
Ogiwara, Kenyu; Kawada, Minoru; and Ashida, Teiji, 4,295,781, Cl. 415-1.000.
- Ho, T. L.; and Din, Zia U., to SCM Corporation. Preparation of (—)-dihydrochrysanthemolactone. 4,296,038, Cl. 260-343.210.
- Ho, T. L.; Din, Zia U.; and Cardenas, Carlos G., to SCM Corporation. Synthesis of (+)-cis-homocaronic acid. 4,296,251, Cl. 562-506.000.
- Hochiki Corporation: See—
Sawa, Hiroshi, 4,295,371, Cl. 73-359.00A.
- Hochstrasser geb. Wack, Elisabeth: See—
Mathieu, Hans; and Hochstrasser, Jurgen, 4,295,759, Cl. 405-243.000.
- Hochstrasser, Jurgen: See—
Mathieu, Hans; and Hochstrasser, Jurgen, 4,295,759, Cl. 405-243.000.
- Hodddinott, David C., to Crompton & Knowles Corporation. Ribbon cable extrusion crosshead. 4,295,812, Cl. 425-114.000.
- Hodes, Gary; Cahen, David; and Manassen, Joost, to Yeda Research and Development Company Ltd. Cd(Se,Te) Alloy photovoltaic materials. 4,296,188, Cl. 429-111.000.
- Hoechst Aktiengesellschaft: See—
Bartmann, Wilhelm; Beck, Gerhard; Lerch, Ulrich; and Konz, Elmar, 4,296,121, Cl. 424-275.000.
- Becker, Reinhold; Michel, Wolfgang; and Hartmann, Gerhard, 4,295,563, Cl. 206-205.000.
- Bergner, Dieter; Hannesen, Kurt; Muller, Wolfgang; and Schulte, Wilfried, 4,295,945, Cl. 204-128.000.
- Braun, Helmut; Rinno, Helmut; and Rauterkus, Karl J., 4,296,226, Cl. 526-316.000.
- Faust, Raimund J., 4,296,196, Cl. 430-271.000.
- Mayer, Manfred; and Volz, Roland, 4,295,937, Cl. 202-155.000.
- Wunder, Friedrich; Leupold, Ernst I.; Hachenberg, Horst; and Schmidt, Hans-Joachim, 4,296,266, Cl. 585-640.000.
- Zimmermann, Wolfgang; Schindler, Hermann; and Pospich, Gunther, 4,296,210, Cl. 521-85.000.
- Hoefke, Wolfgang: See—
Koppe, Herbert; Mentrup, Anton; Renth, Ernst-Otto; Schromm, Kurt; Hoefke, Wolfgang; and Muacevic, Gojko, 4,296,117, Cl. 424-273.00B.
- Hofer, Bruce E., to Tektronix, Inc. Distortion reduction circuit for an inverting feedback amplifier. 4,296,381, Cl. 330-149.000.
- Hoffman, Lawrence C., to Aerojet-General Corporation. Recirculating vapor system for gelling cryogenic liquids. 4,295,346, Cl. 62-500.000.
- Hoffmann, Hellmut; Maurer, Fritz; Priesnitz, Uwe; and Riebel, Hans-Jochem, to Bayer Aktiengesellschaft. Preparation of 3-(2,2-dichlorovinyl)-2,2-dimethyl-cyclopropane-1-carboxylic acid derivatives. 4,296,241, Cl. 560-124.000.

- Hoffmann-La Roche Inc.: See—
Fischli, Albert E.; and Szente, Andre, 4,296,031, Cl. 260-239.30D.
Hengartner, Urs, 4,296,259, Cl. 568-378.000.
- Hogfeldt, Carl-Erik: See—
Nasman, John O.; and Hogfeldt, Carl-Erik, 4,296,067, Cl. 422-26.000.
- Holland, Kenneth F., to Ygnacio Inc.; and Compact Video Systems Inc. High-resolution television system. 4,296,431, Cl. 358-12.000.
- Holmberg, John M., to Boart International Limited. Thread structure for percussion drill elements. 4,295,751, Cl. 403-306.000.
- Holaga, Zygmunt; Madeyski, Krystyn; and Kurowski, Adam, to Przedsiębiorstwo Montażu Elektrycznego "Elektrobudowa". Support assembly for high current bus bars. 4,296,273, Cl. 174-99.00B.
- Holset Engineering Company Limited: See—
Vollett, Eric M., 4,295,546, Cl. 188-378.000.
- Holstein und Kappert GmbH: See—
Heckmann, Werner, 4,295,558, Cl. 198-440.000.
- Holter, Heinz; Gresch, Heinz; Igelbuscher, Heinrich; Hubner, Kurt; and Weber, Ekkehard, to Industrie-Wert Beteiligungsgesellschaft mbH. Filter for cleaning hot gases. 4,295,868, Cl. 55-302.000.
- Honda Giken Kogyo Kabushiki Kaisha: See—
Sano, Shoichi; and Furukawa, Yoshimi, 4,295,657, Cl. 280-91.000.
- Honeywell, Inc.: See—
Schowe, Lester F., Jr., 4,296,445, Cl. 360-65.000.
Woods, Rodney G.; Clarke, Charles J., Jr.; and Sodergren, Robert C., 4,296,464, Cl. 364-200.000.
- Honeywell Information Systems Inc.: See—
Hilker, Dennis C., 4,295,359, Cl. 73-5.000.
Lemak, Nicholas S., 4,296,465, Cl. 364-200.000.
Neuhoff, Donald; Mones, Arthur H.; and Lam, Man K., 4,295,271, Cl. 29-840.000.
Nibby, Chester M., Jr.; and Panepinto, William, Jr., 4,296,467, Cl. 364-200.000.
- Hooker Chemicals & Plastics Corp.: See—
Bommaraju, Tilak V.; Dexter, Theodore H.; and Rader, Charles G., 4,295,951, Cl. 204-242.000.
Oppen, Dieter, 4,295,899, Cl. 148-6.160.
Tang, David Y.; and Foster, Arthur M., 4,296,244, Cl. 562-470.000.
- Hoover, Merle V., to RCA Corporation. Class AB push-pull FET amplifiers. 4,296,382, Cl. 330-264.000.
- Hope, Henry F.; and Hope, Stephen F. Apparatus for processing photographic materials. 4,295,590, Cl. 226-183.000.
- Hope, Stephen F.: See—
Hope, Henry F.; and Hope, Stephen F., 4,295,590, Cl. 226-183.000.
- Hoppe, Udo; Sauermann, Gerhard; Curtis, Julius; Glantz, Per-Olof; Krasse, Bo; Larsson, Kalle; Noren, Borje; Odham, Goran; and Olsson, Jan, to Beiersdorf Aktiengesellschaft. Dental and mouth care preparations. 4,296,095, Cl. 424-52.000.
- Horan, Douglas F., to Intel Corporation. Initializing circuit for MOS integrated circuits. 4,296,340, Cl. 307-550.000.
- Horie, Takashi: See—
Satake, Toshihiko; Kono, Akira; Horie, Takashi; and Mitoma, Yasuharu, 4,295,420, Cl. 99-486.000.
- Horiguchi, Makoto: See—
Matsubayashi, Hiroshi; Tsurumaru, Michiko; Horiguchi, Makoto; Ueno, Hiroshi; and Kitamura, Yoichi, 4,296,182, Cl. 428-629.000.
- Horiuchi, Masatada; and Katto, Hisao, to Hitachi, Ltd. Method for producing a nonvolatile semiconductor memory. 4,295,265, Cl. 29-571.000.
- Hornbeck, Clarence J., to Follett Corporation. Load support structure. 4,295,309, Cl. 52-309.700.
- Horner, John A.; and Wright, Dale W., to Horner, John A. Gear system and method of assembly. 4,296,313, Cl. 235-61.00L.
- Horner, John W., Jr. Apparatus and method for recovering organic and non-ferrous metal products from shale and ore bearing rock. 4,295,880, Cl. 75-10.00R.
- Hornle, Reinhold: See—
Nonn, Konrad; Wolf, Karlheinz; Haus, Artur; and Hornle, Reinhold, 4,295,849, Cl. 8-524.000.
- Horsfall, Harry: See—
Ashfield, Herbert E.; Horsfall, Harry; and Wade, Philip M., 4,295,530, Cl. 172-7.000.
- Horsfield, Arthur K.: See—
Minoprio, William E.; and Horsfield, Arthur K., 4,296,460, Cl. 362-200.000.
- Hoshino, Masaru, to Dai Nippon Insatsu Kabushiki Kaisha. Apparatus for sterilizing a succession of food containers or the like. 4,296,068, Cl. 422-62.000.
- Hoshinouchi, Susumu: See—
Shimada, Wataru; Hoshinouchi, Susumu; Kawaguchi, Kenji; and Yoshida, Akio, 4,295,906, Cl. 156-214.000.
- Hosmer/Dorrance Corporation: See—
Prout, Wesley C., 4,295,466, Cl. 128-80.00R.
- Howie, Robert K., Jr., to Grigoleit Company, The. Knob. 4,295,246, Cl. 16-121.000.
- Hoxan Co. Ltd.: See—
Kuraoka, Yasuo; and Tsuchida, Yasuhiro, 4,295,339, Cl. 62-64.000.
- Hrehovcik, Michael: See—
Mann, Samuel J.; and Hrehovcik, Michael, 4,295,467, Cl. 128-303.180.
- Hsiao, James C., to Union Special Corporation. Feed mechanism for sewing machines. 4,295,434, Cl. 112-314.000.
- Hsu, Sheng T., to RCA Corporation. Method of manufacturing bulk CMOS integrated circuits. 4,295,266, Cl. 29-571.000.
- Hubele, Adolf: See—
Kunz, Walter; Eckhardt, Wolfgang; and Hubele, Adolf, 4,296,118, Cl. 424-273.00P.
- Huber, Bernhard, to Bodenseewerk Perkin-Elmer & Co., GmbH. Apparatus and methods for sample enrichment for flameless atomic absorption spectroscopy. 4,295,854, Cl. 23-230.0PC.
- Hubner, Kurt: See—
Holter, Heinz; Gresch, Heinz; Igelbuscher, Heinrich; Hubner, Kurt; and Weber, Ekkehard, 4,295,868, Cl. 55-302.000.
- Hudson, Robert L., to Chevron Research. Polypropylene blend compositions. 4,296,022, Cl. 260-42.460.
- Huebscher, Wilhelm: See—
Aigle, Karl; Hieber, Udo; Huebscher, Wilhelm; Rheindorf, Hans H.; and Wiedemann, Rolf, 4,296,453, Cl. 361-275.000.
- Hulek, Anton. Guard rail. 4,295,637, Cl. 256-13.100.
- Hulke, Donald B. Hanging shelves. 4,295,432, Cl. 108-149.000.
- Hull, Charles J.; Hutton, James E.; and Mahuson, Teri J., to Xerox Corporation. Bound document apparatus latching mechanism. 4,295,732, Cl. 355-14.00R.
- Hurt, James J., to Deere & Company. Inspection system and apparatus therefor. 4,296,474, Cl. 364-560.000.
- Hurt, Roger W.: See—
Schmid, Michael G.; and Hurt, Roger W., 4,295,577, Cl. 220-86.0AT.
- Hutson, Maurice L., to Control Data Corporation. Register device for transmission of data having two data ranks one of which receives data only when the other is full. 4,296,477, Cl. 364-900.000.
- Huttenhow, George H. Pivoted lever actuator. 4,295,385, Cl. 74-478.000.
- Hutton, James E.: See—
Hull, Charles J.; Hutton, James E.; and Mahuson, Teri J., 4,295,732, Cl. 355-14.00R.
- Hycel, Inc.: See—
Angel, Henry R.; and Hennessy, James W., 4,296,373, Cl. 324-71.0CP.
- Hydriil Company: See—
Mott, James D., 4,295,523, Cl. 166-250.000.
- Hydro-Quebec: See—
Poirier, Marc; Gauthier, Michel; and Belanger, Andre, 4,295,939, Cl. 204-1.00T.
- Ibberson, Robert B. Strip brick facing material. 4,296,154, Cl. 428-15.000.
- Ichisaka, Teruo: See—
Fuseya, Shigeaki; and Ichisaka, Teruo, 4,295,953, Cl. 204-257.000.
- ICI Americas Inc.: See—
Magrans, Juan J., Jr., 4,296,020, Cl. 260-37.00N.
Markiewicz, Kenneth H., 4,296,215, Cl. 525-28.000.
Sherburne, Edwin C., 4,295,977, Cl. 252-8.900.
- ICI Australia Limited: See—
Fensom, Donald J., 4,295,878, Cl. 75-1.00T.
- Idacon, Inc.: See—
Kirchner, Roy P., 4,296,152, Cl. 427-440.000.
- Ideal Toy Corporation: See—
Cooper, Julius, 4,295,649, Cl. 273-86.00B.
- Igawa, Takao: See—
Hasegawa, Haruo; Taniguchi, Hiroyoshi; and Igawa, Takao, 4,296,190, Cl. 430-57.000.
- Igelbuscher, Heinrich: See—
Holter, Heinz; Gresch, Heinz; Igelbuscher, Heinrich; Hubner, Kurt; and Weber, Ekkehard, 4,295,868, Cl. 55-302.000.
- IHC Holland N.V.: See—
Brandwijk, Willem; and Dam, Herman, 4,295,286, Cl. 37-58.000.
- Iida, Yoshihiko, to Toyo Kogyo Co., Ltd. Heated fuel intake system in automobile engine. 4,295,454, Cl. 123-556.000.
- Ikeda, Hiroshi, to Minolta Camera Kabushiki Kaisha. Optical assembly for use in copying machine. 4,295,736, Cl. 355-57.000.
- Ikeda, Tokuzo: See—
Mikami, Takashi; Fujii, Shigeo; Okano, Shuji; and Ikeda, Tokuzo, 4,295,809, Cl. 425-72.00S.
- Ikegami, Shiro: See—
Ishikawa, Akira; Ishida, Yukihito; Ikegami, Shiro; Satoh, Hiroshi; Sato, Ryuichi; Tomisawa, Setsuo; and Toyoshima, Shigeru, 4,296,123, Cl. 424-287.000.
- Illes, Janos: See—
Takacs, Istvan; Banos, Zoltan; Illes, Janos; Vereczkey, Endre; Rudolf, Peter; and Kerey, Gyorgy, 4,296,072, Cl. 422-254.000.
- Illinois Tool Works Inc.: See—
Bjorklund, Lowell L.; Berg, Ramon A.; and Sygnator, Henry A., 4,295,351, Cl. 72-38.000.
- Imai, Kuninori; and Takahashi, Soji, to Hitachi, Ltd. Method of producing magnetron anode. 4,295,595, Cl. 228-161.000.
- Imai, Mitsuru, to Ricoh Co., Ltd. Transfer sheet suitable for electrophotographic pressure-fixing. 4,296,171, Cl. 428-323.000.
- Imazeki, Ryoji; and Yamazaki, Etuo, to Fujitsu Fanuc Limited. Profile control system. 4,296,473, Cl. 364-520.000.
- Impellizzeri, Julius S.: See—
Etzold, Roland; Impellizzeri, Julius S.; and Vaughan, Thomas W., 4,295,557, Cl. 198-382.000.
- Imperial Chemical Industries Limited: See—
Buckley, Alan J.; and Singer, Michael, 4,295,887, Cl. 106-18.330.
Greenwood, Gillian M.; and Woodstock, Alan, 4,295,888, Cl. 106-21.000.
- Stuart-Webb, John, 4,296,217, Cl. 525-390.000.
- Ims, Dale R.: See—
Gruber, Robert J.; Bolte, Steven B.; Knapp, John F.; Ims, Dale R.; and Lewis, Richard B., 4,296,192, Cl. 430-109.000.

- INCA Limited: See—
Tutty, Geoffrey C., 4,295,662, Cl. 282-27.500.
- Industrie Pirelli S.p.A.: See—
Manini, Silvio; and Pacciarini, Antonio, 4,295,774, Cl. 414-331.000.
- Industrie-Wert Beteiligungsgesellschaft mbH: See—
Holter, Heinz; Gresch, Heinz; Igelbuscher, Heinrich; Hubner, Kurt; and Weber, Ekkehard, 4,295,868, Cl. 55-302.000.
- Ingard, Karl U.: See—
Gorchev, Dimitir; Ingard, Karl U.; and Willke, Herbert L., Jr., 4,295,416, Cl. 98-33.00R.
- Ingrain, Raymond A.; and Cohen, Jacques, to La Telemecanique Electrique. Manual electric switch with thermal release. 4,296,396, Cl. 337-66.000.
- Innertsberger, Ernst; Sommer, Oswin; Bosch, Erhard; Muller, Johann; and Schiller, August, to Wacker-Chemie GmbH. Room temperature curable compositions. 4,296,228, Cl. 528-33.000.
- Innes, Robert A.; and Kehl, William L., to Gulf Research & Development Company. Process for the manufacture of acrylonitrile. 4,296,046, Cl. 260-465.300.
- Innovative Photographic Enterprises, Inc.: See—
Stevie, Robert W., 4,296,197, Cl. 430-300.000.
- Inoue, Atsunori: See—
Sakano, Hajime; Kodama, Mikio; Nakayama, Koichi; Yoshida, Isao; and Inoue, Atsunori, 4,296,216, Cl. 525-66.000.
- Inoue, Nobuyoshi, to Copal Company Limited. Blade type focal plane shutter. 4,295,726, Cl. 354-246.000.
- Institut International de Pathologie Cellulaire et Moleculaire: See—
Baurain, Roger M.; and Trouet, Andre B. L., 4,296,105, Cl. 424-180.000.
- Intel Corporation: See—
Horan, Douglas F., 4,296,340, Cl. 307-550.000.
- Interliz Anstalt: See—
Heeb, Adolf, 4,295,447, Cl. 122-136.00R.
- International Business Machines Corp.: See—
Dalbousiere, Gerard; and Draper, Wilburn D., 4,296,463, Cl. 364-200.000.
Fairchild, Peter T.; and Leininger, Joel C., 4,296,470, Cl. 364-200.000.
Garnache, Richard R.; and Kenney, Donald M., 4,295,924, Cl. 156-643.000.
Hartmann, Kurt, 4,295,746, Cl. 400-119.000.
Janssen, Donovan M.; and Seaward, William S., 4,295,733, Cl. 355-14.0SH.
- Leaycraft, Edgar C.; Oktay, Sevgin; and Ostergren, Carl D., 4,296,455, Cl. 361-383.000.
- International Computers Limited: See—
Dodds, Robert J., 4,295,695, Cl. 339-17.00F.
- International Flavors & Fragrances Inc.: See—
Boden, Richard M., 4,296,137, Cl. 426-534.000.
Boden, Richard M., 4,296,138, Cl. 426-534.000.
Wieggers, Wilhelmus J.; Sprecker, Mark A.; Watkins, Hugh; Vock, Manfred H.; and Schmitt, Frederick L., 4,295,978, Cl. 252-8.900.
- International Harvester Company: See—
Gagliani, John; and Sorathia, Usman A. K., 4,296,208, Cl. 521-77.000.
- International Standard Electric Corporation: See—
Gunn, Duncan A., 4,295,701, Cl. 339-94.00A.
- International Telephone and Telegraph Corp.: See—
Leithem, Phyllis C., 4,295,929, Cl. 162-83.000.
- Inverness International Corp.: See—
Mann, Samuel J.; and Hrehovcik, Michael, 4,295,467, Cl. 128-303.180.
- Investment Rarities, Inc.: See—
Schweizer, Eduard H., 4,295,623, Cl. 248-456.000.
- Isayama, Takuro: See—
Yamazaki, Hiroshi; and Isayama, Takuro, 4,296,418, Cl. 346-75.000.
- Ishibashi, Tadashi: See—
Tanaka, Hironari; Matsuyama, Shigeru; Ishibashi, Tadashi; Kinugawa, Kiyoshige; and Sato, Yukihito, 4,295,711, Cl. 350-334.000.
- Ishida, Hiroshi: See—
Sasaki, Koichi; Sumida, Yasuji; and Ishida, Hiroshi, 4,295,731, Cl. 355-14.00R.
- Ishida, Yukihito: See—
Ishikawa, Akira; Ishida, Yukihito; Ikegami, Shiro; Satoh, Hiroshi; Sato, Ryuichi; Tomisawa, Setsuo; and Toyoshima, Shigeru, 4,296,123, Cl. 424-287.000.
- Ishihara, Takeshi; Goto, Daisaku; and Sugiura, Hitoshi, to NGK Insulators, Ltd. Rod-type synthetic resin insulator with overcoat and metal fittings. 4,296,276, Cl. 174-179.000.
- Ishii, Shinzo: See—
Omura, Satoshi; Tanaka, Haruo; Takahashi, Itaru; Ishii, Shinzo; Mineura, Kazuyuki; Shirahata, Kunikatsu; and Kasai, Masaji, 4,296,040, Cl. 260-345.200.
- Ishii, Susumu: See—
Tachibana, Keiji; Nakayama, Yoshihiko; Kaneko, Junichi; and Ishii, Susumu, 4,295,792, Cl. 417-15.000.
- Ishii, Takashi; Nishida, Katsutoshi; Komatsu, Michiyasu; and Tsuge, Akihiko, to Tokyo Shibaura Electric Co., Ltd. Method of producing highly densified ceramic articles. 4,296,065, Cl. 264-325.000.
- Ishikawa, Akira; Ishida, Yukihito; Ikegami, Shiro; Satoh, Hiroshi; Sato, Ryuichi; Tomisawa, Setsuo; and Toyoshima, Shigeru, to Sato, Ryuichi. Germanium-containing organic polymer and its use in the treatment of ophthalmological disorders. 4,296,123, Cl. 424-287.000.
- Ishikawa, Sakou; Watanabe, Yutaka; and Wakai, Katsuro, to Hitachi, Ltd. Error correction and detection systems. 4,296,494, Cl. 371-13.000.
- Ishiwatari, Masumi, to Canon Kabushiki Kaisha. Liquid crystal display device. 4,295,712, Cl. 350-344.000.
- Isley, Raymond H., to Isley Window Manufacturing Co., Inc. Window unit. 4,295,417, Cl. 98-88.00R.
- Isley Window Manufacturing Co., Inc.: See—
Isley, Raymond H., 4,295,417, Cl. 98-88.00R.
- Isobe, Asao: See—
Ohtani, Eiichi; Kobayashi, Kengo; Isobe, Asao; and Tanaka, Shigeoyoshi, 4,295,947, Cl. 204-159.150.
- Isobe, Shinichi: See—
Fukuyama, Hiroomi; and Isobe, Shinichi, 4,296,364, Cl. 318-572.000.
- Itakura, Takahiro: See—
Uemura, Tamio; Ito, Yoshimasa; and Itakura, Takahiro, 4,295,435, Cl. 112-322.000.
- Ito, Yoshimasa: See—
Uemura, Tamio; Ito, Yoshimasa; and Itakura, Takahiro, 4,295,435, Cl. 112-322.000.
- Itoh, Koichi; Koshida, Osamu; and Nakayama, Katsuchi, to Sumitomo Metal Industries, Ltd. Method for producing beam blank for large size H-beam from flat slab. 4,295,354, Cl. 72-225.000.
- Itoh, Kunio: See—
Sugino, Takashi; and Itoh, Kunio, 4,296,387, Cl. 331-94.50H.
- Itoh, Yutaka: See—
Takahashi, Akio; Itoh, Yutaka; Wajima, Motoyo; Morishita, Hirosada; and Nishikawa, Akio, 4,296,219, Cl. 525-488.000.
- Iwahana, Keiiti; Mathuda, Yoshimi; and Futamura, Kenichiro, to Taiho Kogyo Co., Ltd. Al-Sn Base bearing alloy and composite. 4,296,183, Cl. 428-653.000.
- Iwano, Yoshimi: See—
Suzuki, Hajime; and Iwano, Yoshimi, 4,295,499, Cl. 139-370.200.
- Iwase, Yasuhiro: See—
Kurima, Akinori; Iwase, Yasuhiro; and Kimiada, Tadao, 4,295,967, Cl. 210-189.000.
- Iwata, Katsumi: See—
Hatta, Masami; Iwata, Katsumi; and Sasaki, Masao, 4,295,444, Cl. 118-668.000.
- Izuhara, Wataru: See—
Shibatani, Juichi; Nakamura, Kenichi; Izuhara, Wataru; and Obu, Yuichiro, 4,295,549, Cl. 188-218.00A.
- Izumi, Masahiko. Microbe-removing and air-conditioning apparatus. 4,295,343, Cl. 62-309.000.
- J. I. Case Company: See—
Maurer, Herman J., 4,295,661, Cl. 280-765.000.
Natzke, Ronald C.; and Brown, Thomas R., 4,295,287, Cl. 37-103.000.
- Shumaker, John F., 4,295,779, Cl. 414-685.000.
- J. M. Huber Corporation: See—
Wason, Satish K., 4,296,000, Cl. 252-455.00R.
- J. T. Baker Chemicals B.V.: See—
Verbeek, Antonie E.; and Mattheij, Jozef M. J., 4,295,990, Cl. 252-408.000.
- Jacobson, Richard L.; and Lin, Timothy T., to Minnesota Mining and Manufacturing Company. Two-layered photoreceptor containing a selenium-tellurium layer and an arsenic-selenium over layer. 4,296,191, Cl. 430-57.000.
- Jaechh, Christof: See—
Rudolf, Peter; Steck, Werner; Jakusch, Helmut; Vaeth, Guenter; and Jaechh, Christof, 4,296,149, Cl. 427-130.000.
- Jagenberg-Werke AG: See—
Lollert, Bernd; and Risse, Heinrich, 4,295,382, Cl. 74-68.000.
Matzner, Erwin, 4,295,502, Cl. 141-11.000.
- Jain, Kamlesh K., to Fram Industrial Filter Corp. Process for separating solids from suspensions of influent. 4,295,973, Cl. 210-738.000.
- Jakusch, Helmut: See—
Rudolf, Peter; Steck, Werner; Jakusch, Helmut; Vaeth, Guenter; and Jaechh, Christof, 4,296,149, Cl. 427-130.000.
- Jamison, Keith A.: See—
Thomson, George M.; and Jamison, Keith A., 4,296,330, Cl. 250-504.00R.
- Jannone, Joseph. Method for measuring the full range in quality of a vapor. 4,295,368, Cl. 73-192.000.
- Janssen, Donovan M.; and Seaward, William S., to International Business Machines Corporation. Automatic error collator capacity constraints using spare bin strategy. 4,295,733, Cl. 355-14.0SH.
- Japan Synthetic Rubber Co., Ltd.: See—
Aotani, Seiji; and Kanayama, Hisanori, 4,296,015, Cl. 260-29.6ME.
- Jaquith, Jack B.; and Church, Allen R., to Tri/Valley Growers. Molded gelled pimiento body. 4,296,140, Cl. 426-575.000.
- Jean, Raymond W. Wallcoverings. 4,296,162, Cl. 428-213.000.
- Jean Walterscheid GmbH: See—
Geisthoff, Hubert; and von Allwoerden, Wilhelm, 4,295,389, Cl. 74-586.000.
- Jeandot, Jean-Louis; and Lefort, Emmanuel, to Telecommunications Radioelectriques et Telephoniques T.R.T. Balancing amplifier. 4,296,383, Cl. 330-301.000.
- Jenkins, Randall C.; Taylor, Clyde G.; Turner, Robert B.; and Ridgway, Donald H., to Dow Chemical Company, The. Polyurethane backed carpet. 4,296,159, Cl. 428-95.000.
- Jenkins, Thomas E., to General Electric Company. Dishwasher tub assembly. 4,295,692, Cl. 312-228.000.
- Jenner, Michael R.: See—
Khan, Riaz A.; and Jenner, Michael R., 4,296,139, Cl. 426-536.000.

Jensen, David C. Modular building structure. 4,295,307, Cl. 52-236.100.
Jentzsch, Arndt: See—
John, Hans; Muller, Wolfgang; Jentzsch, Arndt; and Schumann, Gunter, 4,295,423, Cl. 101-349.000.
Jerome, Jonathan A., to Atlantic Richfield Company. Information carrier having inter-track identification code information. 4,296,491, Cl. 369-59.000.
Jersey Nuclear-Avco Isotopes, Inc.: See—
Dragg, Vaughn G., 4,296,388, Cl. 331-94.50L.
John, Frank T., to A-T-O Inc. Microminiature palladium oxide gas detector and method of making same. 4,296,399, Cl. 338-34.000.
John Thomas Batts, Inc.: See—
Garrison, Judd F., 4,295,585, Cl. 223-96.000.
John Wyeth & Brother Limited: See—
Bushnell, Brian J.; Cavalla, John F.; Shepherd, Robin G.; and White, Alan C., 4,296,029, Cl. 260-239.30R.
John, Hans; Muller, Wolfgang; Jentzsch, Arndt; and Schumann, Gunter, to VEB Kombinat Polygraph "Werner Lamberz". Liquid distributing roller assembly for printing machines. 4,295,423, Cl. 101-349.000.
Johns Hopkins University, The: See—
Fischell, Robert E., 4,295,474, Cl. 128-697.000.
Walser, Mackenzie, 4,296,127, Cl. 424-319.000.
Johns-Manville Corporation: See—
LaPrade, Steve A.; and Pallo, John M., 4,295,669, Cl. 285-47.000.
Johnsen, Kenneth E.: See—
Nelson, Alfred R.; and Johnsen, Kenneth E., 4,296,019, Cl. 260-33.40R.
Johnson, Alexander L., to Du Pont de Nemours, E. I., and Company. Antihypertensive 1-substituted cyclic lactam-2-carboxylic acids. 4,296,110, Cl. 424-244.000.
Johnson, Harry D.; Campbell, Christopher J.; Turner, Thomas O.; Poole, Carl W.; Gilmore, James E.; and Thomas, James R., to Philip Morris Incorporated. Cooling apparatus and method in a liquid cryogen treatment process. 4,295,337, Cl. 62-54.000.
Johnson, Jesse F., to General Motors Corporation. Scaloped ceramic turbine. 4,295,791, Cl. 416-241.00B.
Johnson, Larry K., to Lawrence Brothers, Inc. Bifold door hinge assembly. 4,295,514, Cl. 160-206.000.
Johnson, Lester E. Elevator control adaptor for handicapped users. 4,296,291, Cl. 200-331.000.
Johnson, Matthew & Co., Limited: See—
Whitehead, Paul, 4,296,086, Cl. 423-392.000.
Johnson, Richard N. Parametric energy converter. 4,295,334, Cl. 60-669.000.
Johnson, Romain H. Die forming method and machine. 4,296,301, Cl. 219-69.00M.
Johnston, David: See—
Appleton, Richard A.; and Johnston, David, 4,296,114, Cl. 424-248.520.
Johnston, David B. R.: See—
Christensen, Burton G.; Johnston, David B. R.; and Firestone, Raymond A., 4,296,236, Cl. 542-420.000.
Joly, Robert; Pavan, Charles; and Carle, Pierre R., to Roussel Uclaf. Novel synergistic insecticides. 4,296,091, Cl. 424-18.000.
Jones, Emrys H., Jr.; and Lauer, Stephen D., to Conoco Inc. Pressure seal for pumping instruments through drill rod. 4,295,536, Cl. 175-214.000.
Jongsma, Cornelis; Frijns, Leon H. B.; and Raven-Donners, Paula A. M., to Stamicarbon, B.V. Method for the preparation of a pure alkali metal benzoate and benzyl alcohol. 4,296,245, Cl. 562-494.000.
Jorgensen, August H., Jr.: See—
Morris, Roger E.; and Jorgensen, August H., Jr., 4,296,007, Cl. 260-23.70N.
Joy Manufacturing Company: See—
Grantmyre, Innes; and Miedema, Brent, 4,295,411, Cl. 91-165.000.
Jubin, John C., Jr.: See—
Grane, Henry R.; Jubin, John C., Jr.; and Worrell, G. Richard, 4,296,262, Cl. 568-910.000.
Junk, Norman M.: See—
Smith, Don H.; Bowman, Arthur F.; and Junk, Norman M., 4,295,424, Cl. 102-322.000.
Jur, Tim A.: See—
Rhodes, Curtis A.; Jur, Tim A.; and Keating, Donald A., 4,295,259, Cl. 29-402.180.
Jurchenko, Anatoly B.: See—
Anisimov, Vyacheslav I.; Bulgakov, Evgeny G.; Gurin, Vasily N.; Radjukevich, Leonid V.; Trishevsky, Igor S.; Trishevsky, Oleg I.; Kheifets, Grigory R.; and Jurchenko, Anatoly B., 4,295,353, Cl. 72-180.000.
Justice, Dennis H.: See—
Bentvelzen, Jozef M.; Meredith, Michael D.; Bepple, Henry; Torregrossa, Louis O.; Battan, Howard R.; and Justice, Dennis H., 4,295,925, Cl. 162-19.000.
Bentvelzen, Jozef M.; Meredith, Michael D.; Bepple, Henry; Torregrossa, Louis O.; Battan, Howard R.; and Justice, Dennis H., 4,295,926, Cl. 162-57.000.
Bentvelzen, Jozef M.; Meredith, Michael D.; Bepple, Henry; Torregrossa, Louis O.; Battan, Howard R.; and Justice, Dennis H., 4,295,927, Cl. 162-57.000.
K S L Corporation: See—
Korfanta, Carl, 4,295,308, Cl. 52-296.000.
Kaarlela, William T. Material and method for securing boron filaments to each other and to a substrate and cutting tools therefrom. 4,295,885, Cl. 75-208.00R.

Kabushiki Kaisha Kawai Gakki Seisakusho: See—
Mishima, Toshio, 4,296,384, Cl. 331-78.000.
Kabushiki Kaisha Komatsu Seisakusho: See—
Kawamura, Toshio; Harashima, Noboru; Ueda, Hideo; and Sano, Seiji, 4,295,654, Cl. 277-92.000.
Kabushiki Kaisha Osaka Packing Seizosho: See—
Takahashi, Akira; and Ohashi, Kenichi, 4,295,893, Cl. 106-120.000.
Kabushiki Kaisha Suwa Seikosha: See—
Mitsui, Hiromitsu, 4,296,489, Cl. 368-205.000.
Kabushiki Kaisha Toyota Jidoshokki Seisakusho: See—
Suzuki, Hajime; and Iwano, Yoshimi, 4,295,499, Cl. 139-370.200.
Kadin, Saul B., to Pfizer Inc. (Carboxy-oxo-pyrrolidino)phenylalkenamides and esters thereof as SRS-A antagonists. 4,296,120, Cl. 424-274.000.
Kadin, Saul B., to Pfizer, Inc. (Carboxyacylamino)phenylalkenamides and esters thereof as SRS-A antagonists. 4,296,129, Cl. 424-309.000.
Kaiser, Paul H.; Neuenschwander, Rudolf; and Norton, Henry J., to Scott Paper Company. Dry-formed nonwoven fabric. 4,296,161, Cl. 428-171.000.
Kakar, Sarwan K.; Kappler, Frank R.; and Cramer, John J., to Diversy Corporation. The. Antistatic natural and synthetic textile materials which have been treated with salts of orthophosphoric or polyphosphoric acid. 4,296,165, Cl. 428-264.000.
Kamada, Kazumasa; Nakai, Yoshio; and Abe, Kazunori, to Mitsubishi Rayon Co., Ltd. Methacrylic resin having a high solar radiant energy absorbing property and process for producing the same. 4,296,214, Cl. 525-2.000.
Kamada, Minoru: See—
Higuchi, Seizun; Tano, Kazuhiro; Kamada, Minoru; and Okamoto, Susumu, 4,296,145, Cl. 427-47.000.
Kamei, Takeji, to Nihon Automatic Machinery Mfg. Co., Ltd. Method for treating water containing wastes. 4,295,972, Cl. 210-710.000.
Kamimura, Toshio, to Teijin Seiki Company, Limited. Hydraulic actuator. 4,295,413, Cl. 92-5.00L.
Kamm, Lawrence J. Limit switch assembly manufacturing machine. 4,295,555, Cl. 192-139.000.
Kanamaru, Hisanobu: See—
Sayo, Kosaku; Suginuma, Atsushi; Tatsumi, Hideo; and Kanamaru, Hisanobu, 4,295,553, Cl. 192-84.00C.
Kanayama, Hisanori: See—
Aotani, Seiji; and Kanayama, Hisanori, 4,296,015, Cl. 260-29.6ME.
Kandler, Herbert: See—
Weissgerber, Rudolf; Stoll, Alois; Kandler, Herbert; Nunner, Hans-Herbert; Eichelseder, Christine; and Pangeri, Helmut, 4,296,017, Cl. 260-30.60R.
Kane, Vinayak V., to Ortho Pharmaceutical Corporation. Total synthesis of the utero-evacuant substance d,l-zoapatanol. 4,296,035, Cl. 260-333.000.
Kaneko, Junichi: See—
Tachibana, Keiji; Nakayama, Yoshihiko; Kaneko, Junichi; and Ishii, Susumu, 4,295,792, Cl. 417-15.000.
Kansai Paint Co., Ltd.: See—
Tominaga, Akira, 4,296,010, Cl. 260-29.2TN.
Kanthal Corporation, The: See—
Hagglund, Erik H. M.; and Giler, Roger R., 4,296,311, Cl. 219-464.000.
Kapp, Joachim-Friedrich: See—
Laurent, Henry; Esperling, Peter; Kapp, Joachim-Friedrich; and Wiechert, Rudolf, 4,296,109, Cl. 424-241.000.
Kappler, Frank R.: See—
Kakar, Sarwan K.; Kappler, Frank R.; and Cramer, John J., 4,296,165, Cl. 428-264.000.
Karasawa, Shinji: See—
Tsuchida, Kensaku; and Karasawa, Shinji, 4,296,303, Cl. 219-78.130.
Karell, Manuel L. Educational toy. 4,295,832, Cl. 434-168.000.
Karloske, Joan E.: See—
Cordts, Howard P.; and Karloske, Joan E., 4,295,907, Cl. 156-246.000.
Karlsson, Einar. Limbing and barking device. 4,295,507, Cl. 144-208.00B.
Kasahara, Shizuka; Yamanishi, Kazuhiko; Hanada, Toshiro; Tokuda, Niaki; and Kobatake, Shinzo, to Wako Pure Chemical Industries, Ltd. Method for measuring peroxidic substances. 4,295,853, Cl. 23-230.00B.
Kasai, Masaji: See—
Omura, Satoshi; Tanaka, Haruo; Takahashi, Itaru; Ishii, Shinzo; Mineura, Kazuyuki; Shirahata, Kunikatsu; and Kasai, Masaji, 4,296,040, Cl. 260-345.200.
Kashima, Mitsuhiro, to Kayaba Kogyo Kabushiki Kaisha. Front end shock absorbing apparatus for wheeled vehicle. 4,295,658, Cl. 280-276.000.
Kaspari, William J. Non-invasive vascular waveform transducer and apparatus. 4,295,471, Cl. 128-675.000.
Kasper, Erich, to Licentia Patent-Verwaltungs-G.m.b.H. Method of manufacturing a semiconductor/glass composite material. 4,295,923, Cl. 156-630.000.
Kaspers, Helmut; and Brandes, Wilhelm, to Bayer Aktiengesellschaft. Fungicidal agents, processes for their preparation and their use for combating fungi. 4,296,116, Cl. 424-272.000.
Kasuga, Muneco: See—
Tsuda, Hiroshi; Miyashita, Kiyoshi; Nishikawa, Masaji; Shimizu, Akira; and Kasuga, Muneco, 4,295,734, Cl. 355-15.000.
Katamoto, Kazuyoshi: See—
Suzuki, Takashi; Sawada, Hidekazu; and Katamoto, Kazuyoshi, 4,296,107, Cl. 424-180.000.

Katto, Hisao: See—
Horiuchi, Masatada; and Katto, Hisao, 4,295,265, Cl. 29-571.000.
Kauffman, Robert N.: See—
Smith, James D. B.; and Kauffman, Robert N., 4,296,018, Cl. 260-32.8EP.
Kaufmann, Kenneth M., to Pako Corporation. Automatic anti-oxidation replenisher control. 4,295,729, Cl. 354-324.000.
Kawada, Minoru: See—
Ogiwara, Kenzuru; Kawada, Minoru; and Ashida, Teiji, 4,295,781, Cl. 415-1.000.
Kawaguchi, Kenji: See—
Shimada, Wataru; Hoshinouchi, Susumu; Kawaguchi, Kenji; and Yoshida, Akio, 4,295,906, Cl. 156-214.000.
Kawaguchi, Yasuyoshi; Shimotake, Munetoshi; and Yamamoto, Fujio, to Bridgestone Tire Company Limited. Thick-cord lightweight tire body having an improved fatigue life. 4,295,512, Cl. 152-354.00R.
Kawai Musical Instrument Mfg. Co., Ltd.: See—
Deutsch, Ralph; and Deutsch, Leslie J., 4,295,402, Cl. 84-1.030.
Kawamoto, Hirohisa: See—
Maby, Edward W.; Kawamoto, Hirohisa; and Valembois, Pierre V., 4,296,144, Cl. 427-38.000.
Kawamura, Isamu: See—
Matsushima, Yoshio; Kumura, Teruhiko; Kawamura, Isamu; and Kawata, Terushige, 4,296,094, Cl. 424-49.000.
Kawamura, Toshio; Harashima, Noboru; Ueda, Hideo; and Sano, Seiji, to Kabushiki Kaisha Komatsu Seisakusho. Seal assembly for a linkage. 4,295,654, Cl. 277-92.000.
Kawata, Terushige: See—
Matsushima, Yoshio; Kumura, Teruhiko; Kawamura, Isamu; and Kawata, Terushige, 4,296,094, Cl. 424-49.000.
Kawaziri, Kazuhiro; Fujiwara, Masato; Hatanaka, Isamu; Tabei, Masatoshi; Higashi, Akio; and Nirasawa, Mitsuhiro, to Fuji Photo Film Co., Ltd. Image recording material and image recording method using the same. 4,296,422, Cl. 346-160.000.
Kayaba Kogyo Kabushiki Kaisha: See—
Kashima, Mitsuhiro, 4,295,658, Cl. 280-276.000.
Kazama, Keizo: See—
Nakazima, Kooichi; Kazama, Keizo; and Oki, Hiroshi, 4,295,574, Cl. 220-2.10A.
Kearny, Thomas J. Paint spray booth with water wash. 4,295,866, Cl. 55-228.000.
Keating, Donald A.: See—
Rhodes, Curtis A.; Jur, Tim A.; and Keating, Donald A., 4,295,259, Cl. 29-402.180.
Keeble, Joseph D. Surface projectile game with mallets and three-sided targets. 4,295,650, Cl. 273-118.00R.
Kefauver, Lester R.: See—
Frantello, Alfred A.; and Kefauver, Lester R., 4,295,324, Cl. 56-12.700.
Kehl, William L.: See—
Innes, Robert A.; and Kehl, William L., 4,296,046, Cl. 260-465.300.
Keiper U.S.A., Inc.: See—
Kluting, Bernd A.; and Zaveri, Vikram H., 4,295,682, Cl. 297-367.000.
Keizer, Eugene O.; and Alphonse, Gerard A., to RCA Corporation. System for measuring stylus shoe length. 4,296,371, Cl. 324-61.00R.
Kelly, Robert J., to Reynolds and Reynolds Company, The. Roll fed shingling machine with predetermined numbering. 4,295,642, Cl. 270-53.000.
Kelsey Hayes Company: See—
Becker, James; and Neill, Daniel L., 4,295,687, Cl. 303-20.000.
Kemmer, Ulrich: See—
Ruhl, Karl; and Kemmer, Ulrich, 4,295,797, Cl. 417-203.000.
Kendall Company, The: See—
McAvinn, James D.; Meister, Arthur R.; and Tucker, Samuel M., 4,295,537, Cl. 177-15.000.
Kenney, Donald M.: See—
Garnache, Richard R.; and Kenney, Donald M., 4,295,924, Cl. 156-643.000.
Kensrue, Milo M. Welding seam back-up means. 4,295,593, Cl. 228-50.000.
Kerey, Gyorgy: See—
Takacs, Istvan; Banos, Zoltan; Illes, Janos; Vereckey, Endre; Rudolf, Peter; and Kerey, Gyorgy, 4,296,072, Cl. 422-254.000.
Kerle, Edward J.; and Beaver, Terry R., to Owens-Corning Fiberglass Corporation. Wax-containing unsaturated polyester laminating composition with aromatic tertiary amine. 4,296,009, Cl. 260-28.50R.
Kern, Mark T.; and Cinzori, Robert J., to Santa Barbara Research Center. Dual spectrum infrared fire sensor. 4,296,324, Cl. 250-339.000.
Kerr, Noel C.: See—
Gass, John C.; Kerr, Noel C.; and Pittmann, Robert W., 4,295,795, Cl. 417-111.000.
Kerschner, Emil: See—
Buddahl, Volker; Morlock, Gerhard; Reidt, Werner; and Kerschner, Emil, 4,296,006, Cl. 260-23.0EP.
Kesseling, John P.: See—
Angwin, Meredith J.; Pfefferle, William C.; and Kesseling, John P., 4,295,818, Cl. 431-7.000.
Khalafalla, Sanaa E.; and Reimers, George W., to United States of America, Interior. Method for clarifying slimes. 4,295,971, Cl. 210-695.000.
Khan, Riaz A.; and Jenner, Michael R., to Talres Development (N.A.) N.V. Bittering agents. 4,296,139, Cl. 426-536.000.
Kheifets, Grigory R.: See—
Anisimov, Vyacheslav I.; Bulgakov, Evgeny G.; Gurin, Vasily N.; Radjukevich, Leonid V.; Trishevsky, Igor S.; Trishevsky, Oleg

I.; Kheifets, Grigory R.; and Jurchenko, Anatoly B., 4,295,353, Cl. 72-180.000.
Khoe, Giok D.: See—
Franken, Adrianus J. J.; Khoe, Giok D.; and Kuppers, Dieter, 4,296,143, Cl. 427-38.000.
Kiehs, Karl: See—
Burstinghaus, Rainer; Kiehs, Karl; and Adolphi, Heinrich, 4,296,108, Cl. 424-210.000.
Kiess, Helmut G.; and Binggeli, Bruno K., to RCA Corporation. Read-out of electrostatically stored information. 4,296,478, Cl. 365-112.000.
Killmaier, Horst: See—
Rosemeier, Friedrich; and Killmaier, Horst, 4,295,495, Cl. 138-89.000.
Killmeyer, Charles W., deceased; by Killmeyer, Elizabeth A., administrator; Lane, James E.; Taylor, Leslie L., Jr.; and Pearson, Joe T., to PPG Industries, Inc. Method of producing a pultruded, fiber reinforced rod. 4,296,060, Cl. 264-137.000.
Killmeyer, Elizabeth A., administrator: See—
Killmeyer, Charles W., deceased; Killmeyer, Elizabeth A., administrator; Lane, James E.; Taylor, Leslie L., Jr.; and Pearson, Joe T., 4,296,060, Cl. 264-137.000.
Kim, Kwon S., to Star Manufacturing Company of Oklahoma. Prefabricated panel construction system. 4,295,304, Cl. 52-90.000.
Kimball, Stephen F.; and Gagnon, Peter R., to GTE Products Corporation. Tungsten halogen lamp having lead-in wire comprising tantalum alloy. 4,296,351, Cl. 313-222.000.
Kimiwada, Tadao: See—
Kurima, Akinori; Iwase, Yasuhiro; and Kimiwada, Tadao, 4,295,967, Cl. 210-185.000.
Kimoto & Co., Ltd.: See—
Moriya, Takeo; and Yamagata, Toshio, 4,296,193, Cl. 430-149.000.
Kimura, Takeo: See—
Shibasaki, Ichiro; Ohmura, Kaoru; and Kimura, Takeo, 4,296,424, Cl. 357-1.000.
King, James D., to Southwest Research Institute. Apparatus providing enhanced detection of specimens in inhomogeneous fields. 4,296,378, Cl. 324-313.000.
King, Virginia B. Floor treating apparatus. 4,295,243, Cl. 15-320.000.
Kinghorn, Michael H. Vertical garden. 4,295,296, Cl. 47-82.000.
Kinugawa, Kiyoshige: See—
Tanaka, Hironari; Matsuyama, Shigeru; Ishibashi, Tadashi; Kinugawa, Kiyoshige; and Sato, Yukihiko, 4,295,711, Cl. 350-334.000.
Kirchner, Roy P., to Idacorn, Inc. Method and composition for treating wood with pentachlorophenol. 4,296,152, Cl. 427-440.000.
Kistler, Manfred: See—
Purr, Horst; Kistler, Manfred; and Muller, Rolf, 4,295,913, Cl. 156-345.000.
Kitagawa, Masahiro, to Olympus Optical Company, Ltd. Camera with operation indicator for auto-strobe unit. 4,295,717, Cl. 354-33.000.
Kitagawa, Masahiro: See—
Mizokami, Kazunori; and Kitagawa, Masahiro, 4,295,720, Cl. 354-51.000.
Kitamura, Yoichi: See—
Matsubayashi, Hiroshi; Tsurumaru, Michiko; Horiguchi, Makoto; Ueno, Hiroshi; and Kitamura, Yoichi, 4,296,182, Cl. 428-629.000.
Kitasato Kenkyusho: See—
Omura, Satoshi; Tanaka, Haruo; Takahashi, Itaru; Ishii, Shinzo; Mineura, Kazuyuki; Shirahata, Kunikatsu; and Kasai, Masaji, 4,296,040, Cl. 260-345.200.
Kito, Kyoji: See—
Sasaki, Susumu; Kito, Kyoji; and Koide, Akio, 4,295,855, Cl. 23-230.00B.
Kiuchi, Mitsuyuki, to Matsushita Electric Industrial Co., Ltd. Induction heating coil. 4,296,295, Cl. 219-10.49R.
Kiyohara, Takehiko: See—
Takashi, Uchiyama; Tsunekawa, Tokuchi; and Kiyohara, Takehiko, 4,295,722, Cl. 354-146.000.
Klaui, Heinrich: See—
Guex, Woldemar; Klaui, Heinrich; Pauling, Horst; and Voirol, Felix, 4,295,517, Cl. 165-1.000.
Klebe, Wilmer A. Geodetic dome. 4,295,303, Cl. 52-81.000.
Klein, Philipp H.; Addamiano, Arrigo; and Allen, Roger, to United States of America, Navy. Luminescent hafnia composition. 4,295,989, Cl. 252-301.40F.
Kliklok Corporation: See—
Baker, Thomas R.; and Collura, Peter C., 4,295,839, Cl. 493-143.000.
Klippel, Friedrich: See—
Petersen, Harro; Pai, Panemangalore S.; Klippel, Friedrich; and Reinert, Friedrich, 4,295,846, Cl. 8-186.000.
Klockner-Humboldt-Deutz AG (Zweigniederlassung Fahr): See—
Maier, Martin; Purrer, Josef; and Clemens, Ronald, 4,295,323, Cl. 56-10.200.
Klockner-Humboldt-Deutz Aktiengesellschaft: See—
Schleiermacher, Herbert, 4,295,457, Cl. 123-574.000.
Kluting, Bernd A.; and Zaveri, Vikram H., to Keiper U.S.A., Inc. Superfine tooth seat back adjuster. 4,295,682, Cl. 297-367.000.
Knapman, Reginald G.: See—
Haslop, John M.; Knapman, Reginald G.; and West, Michael A., 4,296,326, Cl. 250-372.000.
Knapp, Heinrich: See—
Lembke, Manfred; and Knapp, Heinrich, 4,295,452, Cl. 123-470.000.

- Knapp, John F.: See—
Gruber, Robert J.; Bolte, Steven B.; Knapp, John F.; Ims, Dale R.; and Lewis, Richard B., 4,296,192, Cl. 430-109.000.
- Knippel, Willis H.; and Ferris, Ray, to Pullman Incorporated. Railway hopper car latch mechanism. 4,295,430, Cl. 105-308.00E.
- Knobbe, Karl-Heinz: See—
Beckert, Alexander; and Knobbe, Karl-Heinz, 4,296,294, Cl. 219-10.410.
- Knopp, Hans; Herion, Dieter; Conzelmann, Gerhard; and Gehrig, Heinz, to BASF Aktiengesellschaft. Process and apparatus for texturizing filament bundles. 4,295,253, Cl. 28-255.000.
- Knudsen, Eric T., to Beecham Group Limited. Medicament container. 4,295,567, Cl. 206-534.000.
- Kobatake, Shinzo: See—
Kasahara, Shizuka; Yamanishi, Kazuhiko; Hanada, Toshiro; Tokuda, Kuniaki; and Kobatake, Shinzo, 4,295,853, Cl. 23-230.00B.
- Kobayashi, Isamu: See—
Wada, Yoshimasa; Yamazaki, Sigeaki; Kobayashi, Isamu; Haraguchi, Noriyuki; and Fukuda, Minoru, 4,295,780, Cl. 414-749.000.
- Kobayashi, Kengo: See—
Ohtani, Eiichi; Kobayashi, Kengo; Isobe, Asao; and Tanaka, Shigeyoshi, 4,295,947, Cl. 204-159.150.
- Kodama, Mikio: See—
Sakano, Hajime; Kodama, Mikio; Nakayama, Koichi; Yoshida, Isao; and Inoue, Atsunori, 4,296,216, Cl. 525-66.000.
- Koehring Company: See—
Nicholson, Robert D.; and Daniel, Alger T., 4,295,594, Cl. 228-160.000.
- Koenen, Klaus: See—
Becker, Friedbert; Steinkamp, Johann; and Koenen, Klaus, 4,296,400, Cl. 340-32.000.
- Koenig, Robert H.; and D'Angelo, Victor, to Tapeswitch Corporation of America. Normally closed wafer switch. 4,296,283, Cl. 200-16.00D.
- Kohler, Kranz, to Messerschmitt-Bolkow-Blohm GmbH. Array of solar cells. 4,296,270, Cl. 136-244.000.
- Kohyama, Mitsuaki, to Toshiba Corporation. Developing apparatus for electrostatic copying machine. 4,295,443, Cl. 118-657.000.
- Koide, Akio: See—
Sasaki, Susumu; Kito, Kyoji; and Koide, Akio, 4,295,855, Cl. 23-230.00B.
- Kojima, Tadayoshi: See—
Shimamura, Tadao; and Kojima, Tadayoshi, 4,296,051, Cl. 264-118.000.
- Kokusai Denshin Denwa Co., Ltd.: See—
Teramura, Hiroichi; Yamazaki, Yasuhiro; Wakahara, Yasushi; Hattori, Naohiko; Yamamoto, Seiichi; and Nakao, Kouzo, 4,296,439, Cl. 358-257.000.
- Kokusai Denshin Denwa Kabushiki Kaisha: See—
Nakai, Taiichiro; Furusawa, Kahei; and Ejiri, Yoshihiro, 4,295,707, Cl. 350-96.200.
- Kokusen Denki Co., Ltd.: See—
Kubo, Masaaki, 4,296,368, Cl. 322-75.000.
- Kolyada, Vladimir A.: See—
Nazarian, Miron M.; Efimov, Vyacheslav T.; Axenko, Alexander A.; Kolyada, Vladimir A.; and Shamsha, Ljudmila F., 4,295,946, Cl. 204-149.000.
- Komatsu, Michiyasu: See—
Ishii, Takashi; Nishida, Katsutoshi; Komatsu, Michiyasu; and Tsuge, Akihiko, 4,296,065, Cl. 264-325.000.
- Kondo, Shinichi: See—
Umezawa, Hamao; Okami, Yoshiro; and Kondo, Shinichi, 4,296,106, Cl. 424-181.000.
- Kongshaug, Gunnar, to Norsk Hydro a.s. Method for steam cleaning of compressors. 4,295,895, Cl. 134-22.00R.
- Konishiroku Photo Industry Co., Ltd.: See—
Nakamura, Hiroya, 4,296,423, Cl. 346-160.000.
- Kono, Akira: See—
Satake, Toshihiko; Kono, Akira; Horie, Takashi; and Mitoma, Yasuharu, 4,295,420, Cl. 99-486.000.
- Konta, Yukio, to Tomy Kogyo Co., Inc. Pinball actuator and feed mechanism. 4,295,651, Cl. 273-121.00D.
- Konz, Elmar: See—
Bartmann, Wilhelm; Beck, Gerhard; Lerch, Ulrich; and Konz, Elmar, 4,296,121, Cl. 424-275.000.
- Kopenhaver, Robert, to Certain-teed Corporation. Apparatus for manufacturing roofing shingles having multiple ply-appearance. 4,295,445, Cl. 118-695.000.
- Koppe, Herbert; Mentrup, Anton; Renth, Ernst-Otto; Schromm, Kurt; Hoeft, Wolfgang; and Muacevic, Gojko, to Boehringer Ingelheim GmbH. 1-Aryloxy-2-hydroxy-3-[(Benzimidazolone-substituted alkyl)-amino]propanes and salts thereof. 4,296,117, Cl. 424-273.00B.
- Korfanta, Carl, to K S L Corporation. Pole base assembly, bolt circle adaptor. 4,295,308, Cl. 52-296.000.
- Koshida, Osamu: See—
Itoh, Koichi; Koshida, Osamu; and Nakayama, Katsuichi, 4,295,354, Cl. 72-225.000.
- Koster, Siegfried. Multi-filter chamber aquarium filter. 4,295,965, Cl. 210-169.000.
- Kowalski, Daniel J.; and Mareydt, Ray G., to Four Star Corporation. Slotted side rail and movable bracket for article carrier. 4,295,588, Cl. 224-321.000.
- Kowalski, David J.: See—
Aitken, Thomas; Kowalski, David J.; and Srinivasan, K. G., 4,295,930, Cl. 162-158.000.
- Kozin, Cynthia H.: See—
Buck, Gordon K.; and Kozin, Cynthia H., 4,295,363, Cl. 73-117.300.
- Kozio, Konrad; and Wenk, Erich, to Conradt GmbH & Co. Metal-elektroden KG. Process for preparing manganese oxide. 4,295,942, Cl. 204-96.000.
- Krasse, Bo: See—
Hoppe, Udo; Saueremann, Gerhard; Curtis, Julius; Glantz, Per-Olof; Krasse, Bo; Larsson, Kare; Noren, Borje; Odham, Goran; and Olsson, Jan, 4,296,095, Cl. 424-52.000.
- Kraus, Roland. Paint application method and machine. 4,296,317, Cl. 250-215.000.
- Krautkraemer GmbH: See—
Ganglbauer, Otto; Wallner, Felix; Scheidl, Helmut; Reindl, Hermann; and Frielinghaus, Rainer, 4,295,375, Cl. 73-582.000.
- Krebs, Karl-Friedrich: See—
Halpaap, Herbert; and Krebs, Karl-Friedrich, 4,295,968, Cl. 210-198.300.
- Krebs, Peter: See—
Wuthrich, Hans-Rudolf; Krebs, Peter; Spiegel, Hubert; and Eicher, Franz, 4,296,289, Cl. 200-148.00R.
- Krejcir, Oldrich: See—
Pustka, Zdenek; and Krejcir, Oldrich, 4,295,635, Cl. 254-93.0HP.
- Kritz, Jacob A., to Sperry Corporation. Parametric array Doppler sonar apparatus. 4,296,482, Cl. 367-91.000.
- Krivosos, Vadim P.: See—
Lifshits, Viktor S.; Krivosos, Vadim P.; Podola, Nikolai V.; Grabchev, Boris L.; Andrianov, Vladimir R.; and Shakhov, Rifkhat M., 4,296,305, Cl. 219-101.000.
- Kroll, Harley E.: See—
Herpers, Ferdinand J.; Kroll, Harley E.; Carlson, Alfred D.; and Dodge, Paul D., 4,295,244, Cl. 15-320.000.
- Kruger, Hermann, to Volkswagenwerk Aktiengesellschaft. Internal combustion engine with oil pump gear surrounding and driven by crankshaft. 4,295,807, Cl. 418-170.000.
- Krupey, John, to American Home Products Corporation. Method of obtaining a lyophilized product. 4,295,280, Cl. 34-5.000.
- Krupp-Koppers GmbH: See—
Waldhofer, Reinhard, 4,295,448, Cl. 122-164.000.
- Kruszona, Edward G., to General Electric Company. Hand operated apparatus for applying a gasketing composition. 4,295,439, Cl. 118-317.000.
- Kubo, Masaaki, to Kokusan Denki Co., Ltd. Internal combustion engine driven generator. 4,296,368, Cl. 322-75.000.
- Kubota Ltd.: See—
Sakaguchi, Tadahiyo; Hino, Masamichi; Tsuji, Setsuo; Hashido, Akiyoshi; and Enomoto, Kazuyoshi, 4,295,915, Cl. 156-361.000.
- Kubota, Toshifumi, to Hitachi Koki Company, Limited. Vibration control for mowing machine. 4,295,272, Cl. 30-276.000.
- Kuhr, Manfred: See—
Berger, Dieter; Braun, Franz; Frey, Gunter; Guthlein, Werner; and Kuhr, Manfred, 4,296,202, Cl. 435-29.000.
- Kuipers, Peter, to Nordson Corporation. Tube forming shoe and methods of forming a flexible web into a tube. 4,295,322, Cl. 53-450.000.
- Kulin, Ralph; and Stauber, Ronald C., to Baxter Travenol Laboratories, Inc. Solution container hanger. 4,295,619, Cl. 248-95.000.
- Kulprathipanja, Santi, to UOP Inc. Cellulose acetate butyrate bound zeolite adsorbents. 4,295,994, Cl. 252-430.000.
- Kumazawa, Kenichi: See—
Momiya, Kikuo; and Kumazawa, Kenichi, 4,295,723, Cl. 354-155.000.
- Kumm, Emerson L. Flat belt transmission with rotary actuator and integrated control system. 4,295,836, Cl. 474-51.000.
- Kumura, Teruhiko: See—
Matsushima, Yoshio; Kumura, Teruhiko; Kawamura, Isamu; and Kawata, Terushige, 4,296,094, Cl. 424-49.000.
- Kunz, Walter; Eckhardt, Wolfgang; and Hubele, Adolf, to Ciba-Geigy Corporation. Fungicidal 3-[N-(pyrazol-1-yl-acetyl)-N-(substituted phenyl)-amino]-tetrahydro-2-furanones. 4,296,118, Cl. 424-273.00P.
- Kupchinsky, Igor I.: See—
Zhivotov, Jury G.; Kupchinsky, Igor I.; Plokhuta, Vyacheslav D.; Bezverkhnay, Alexandr M.; Nabutovsky, Samoil I.; deceased; and Eroshevskaya, Elena D., administrator, 4,295,387, Cl. 74-573.00F.
- Kupf, Lubomir; Travnick, Jiri; Adamek, Radomil; and Kyzlink, Josef, to Statni vyzkumny ustav materialu. Mold for the injection molding of objects of large dimension and complicated surfaces from plastic material. 4,295,628, Cl. 249-80.000.
- Kuppers, Dieter: See—
Franken, Adrianus J. J.; Khoe, Giok D.; and Kuppers, Dieter, 4,296,143, Cl. 427-38.00A.
- Kuraoka, Yasuo; and Tsuchida, Yasuhiro, to Hoxan Co. Ltd. Cryostat system utilizing a liquefied gas. 4,295,339, Cl. 62-64.000.
- Kureha Kagaku Kogyo Kabushiki Kaisha: See—
Enomoto, Satoru; Asano, Kiro; and Tanaka, Hiromitsu, 4,296,233, Cl. 536-5.000.
- Kuriki, Minoru: See—
Takeuchi, Minami; and Kuriki, Minoru, 4,296,427, Cl. 357-39.000.
- Kurima, Akinori; Iwase, Yasuhiro; and Kimiwa, Tadao, to Chiyoda Kako Kensetsu Kabushiki Kaisha. Fluidized bed contact apparatus. 4,295,967, Cl. 210-189.000.
- Kurosaki, Shiro: See—
Shiraishi, Satoshi; Fujiwara, Kunio; and Kurosaki, Shiro, 4,295,869, Cl. 65-3.110.

- Kurowski, Adam: See—
Hologa, Zygmunt; Madeyski, Krystyn; and Kurowski, Adam, 4,296,273, Cl. 174-99.00B.
- Kusters, Norbert L.: See—
Moore, William J. M.; Kusters, Norbert L.; and So, Eddy, 4,296,369, Cl. 323-218.000.
- Kusy, Robert P., to Du Pont de Nemours, E. I., and Company. Specimen grips for dynamic mechanical analyzer. 4,295,374, Cl. 73-579.000.
- Kuzminski, Henry W., to RCA Corporation. Color picture tube having improved slit type shadow mask and method of making same. 4,296,189, Cl. 430-5.000.
- Kyosan Denki Kabushiki Kaisha: See—
Mochizuki, Hiroshi; and Seki, Tokio, 4,295,414, Cl. 92-98.000.
- Kyowa Chemical Industry Co., Ltd.: See—
Matsushima, Yoshio; Kumura, Teruhiko; Kawamura, Isamu; and Kawata, Terushige, 4,296,094, Cl. 424-49.000.
- Kyowa Hakko Kogyo Kabushiki Kaisha: See—
Omura, Satoshi; Tanaka, Haruo; Takahashi, Itaru; Ishii, Shinzo; Mineura, Kazuyuki; Shirahata, Kunikatsu; and Kasai, Masaji, 4,296,040, Cl. 260-345.200.
- Kyzlink, Josef: See—
Kupf, Lubomir; Travnick, Jiri; Adamek, Radomil; and Kyzlink, Josef, 4,295,628, Cl. 249-80.000.
- L. Schuler GmbH: See—
Finsterwalder, Kurt; Philipp, Karl-Heinz; Riedisser, Gunter; and Voss, Wilfried, 4,295,399, Cl. 83-251.000.
- La Telemecanique Electrique: See—
Ingrain, Raymond A.; and Cohen, Jacques, 4,296,396, Cl. 337-66.000.
- Labonte, Paul D.: See—
Hasselmann, Detlev E. M.; and Labonte, Paul D., 4,295,505, Cl. 141-301.000.
- Lacombat, Michel; and Gerard, Andre, to Thomson-CSF. Optical projection system having a photorepetition function. 4,295,735, Cl. 355-43.000.
- Ladage, Cornelis A.; Van Linge, Douwe J.; and Van Riessen, Huibert A., to ACF Chemiefarma N.V. Pharmaceutical compositions and their use in the prophylaxis and/or treatment of certain diseases. 4,296,131, Cl. 424-347.000.
- Lajh, Rajko, to Swiss Aluminium Ltd. Device and method for introducing gases into molten metal. 4,295,883, Cl. 75-68.00R.
- Lalu, Jean-Pierre: See—
Bouvet, Pierre; and Lalu, Jean-Pierre, 4,296,034, Cl. 260-326.820.
- Lam, Man K.: See—
Neuhoff, Donald; Mones, Arthur H.; and Lam, Man K., 4,295,271, Cl. 29-840.000.
- Lamarque, Bernard: See—
Mialon, Jacques; and Lamarque, Bernard, 4,295,388, Cl. 74-579.00R.
- Landay, David L.; and Wolf, Alvan H., to Brookfield Athletic Shoe Company, Inc. Roller skating shoe. 4,295,655, Cl. 280-11.200.
- Lander, Lynn H.: See—
Sepulveda, Ralph R.; and Lander, Lynn H., 4,295,845, Cl. 8-139.100.
- Lane, James E.: See—
Killmeyer, Charles W.; deceased; Killmeyer, Elizabeth A.; administrator; Lane, James E.; Taylor, Leslie L., Jr.; and Pearson, Joe T., 4,296,060, Cl. 264-137.000.
- Lang, Ernst; and Niemeyer, Lutz, to BBC Brown, Boveri & Company Limited. High-voltage, blast-actuated power switch having field electrodes. 4,296,285, Cl. 200-61.080.
- Lang-Ree, Nils, to NPI Corporation. Chain broiler doctor blade. 4,295,418, Cl. 99-355.000.
- Lang, Stanley A., Jr.; and Murdock, Keith C., to American Cyanamid Company. Metal chelates of 1,4-bis(substituted-amino)-5,8-dihydroxy-anthraquinones. 4,296,030, Cl. 260-239.00A.
- Lange, Karl H., to Balda-Werke. Battery conservation by control of the charging circuit for a built-in electronic flash. 4,295,719, Cl. 354-50.000.
- Langer, Alfred: See—
Schaefer, Hans G.; and Langer, Alfred, 4,295,908, Cl. 156-251.000.
- Langford, Frederic E., to Washington Logging Equipment, Inc. System for inhauling and outhauling lines. 4,295,636, Cl. 254-304.000.
- Langhammer, Jerome, to Poulson, Larry. Confined air food heating apparatus. 4,295,419, Cl. 99-427.000.
- LaPrade, Steve A.; and Pallo, John M., to Johns-Manville Corporation. Thermal insulation especially for pipe, flanges and fittings. 4,295,669, Cl. 285-47.000.
- Lardellier, Alain M. J., to Societe Nationale d'Etude et de Construction de Moteurs d'Aviation. Removable sealing gasket for distributor segments of a jet engine. 4,295,785, Cl. 415-174.000.
- Lardellier, Alain M. J., to Societe Nationale d'Etude et de Construction de Moteurs d'Aviation. Removable support for the sealing lining of the casing of jet engine blowers. 4,295,787, Cl. 415-197.000.
- Large, Eddie A. J. Resilient mounting for a reclining seat. 4,295,626, Cl. 248-575.000.
- Larson, Clifford L., to Baldwin-Korthe Web Controls, Inc. Web severing device. 4,295,400, Cl. 83-545.000.
- Larsson, Kare: See—
Hoppe, Udo; Saueremann, Gerhard; Curtis, Julius; Glantz, Per-Olof; Krasse, Bo; Larsson, Kare; Noren, Borje; Odham, Goran; and Olsson, Jan, 4,296,095, Cl. 424-52.000.
- Laso, Felipe. Method of combating amebiasis in humans. 4,296,102, Cl. 424-130.000.
- Laso, Felipe. Stabilized solution of chlorine oxides. 4,296,103, Cl. 424-130.000.
- Lattuada, Sergio, to S.T.I. Strumentazione Industriale S.p.A. Method for automating and optimizing the operative cycle in adsorption dehydration plants. 4,295,863, Cl. 55-21.000.
- Lauer, Stephen D.: See—
Jones, Emrys H., Jr.; and Lauer, Stephen D., 4,295,536, Cl. 175-214.000.
- Laurent, Henry; Esperling, Peter; Kapp, Joachim-Friedrich; and Wiechert, Rudolf, to Schering, Aktiengesellschaft. Corticoid 21-sulfo-propionates and the salts thereof, a process for the production thereof and pharmaceutical preparations thereof. 4,296,109, Cl. 424-241.000.
- Lawless, William N., to Lawless, William Nicholas. Thallous halide materials for use in cryogenic applications. 4,296,147, Cl. 427-120.000.
- Lawless, William Nicholas: See—
Lawless, William N., 4,296,147, Cl. 427-120.000.
- Lawrence Brothers, Inc.: See—
Johnson, Larry K., 4,295,514, Cl. 160-206.000.
- Lazarus, Charles R.; Stahl, Howard D.; and Haas, Gerhard J., to General Foods Corporation. Dog food of improved acceptability. 4,296,132, Cl. 426-2.000.
- Leaycraft, Edgar C.; Oktay, Sevgin; and Ostergren, Carl D., to International Business Machines Corporation. Slotted heat sinks for high powered air cooled modules. 4,296,455, Cl. 361-383.000.
- Lebetzki, Egon: See—
Schneider, Hartmut; and Lebetzki, Egon, 4,295,870, Cl. 65-3.120.
- LeBlanc, Ralph W.; and Bingham, Robert M. Apparatus for removing contaminants from lubricating oil. 4,295,966, Cl. 210-180.000.
- Lebost, Barry A. Fluid turbine. 4,295,783, Cl. 415-2.00R.
- LeClou, Andre, to Commissariat a l'Energie Atomique. Device for anchoring a vessel in a horizontal foundation raft. 4,295,620, Cl. 248-154.000.
- Lee, Man S., to GTE Automatic Electric Laboratories, Inc. Switched capacitor bilinear resistors. 4,296,392, Cl. 333-213.000.
- Lee, Ronald B.: See—
d'Hautecourt, Alain H.; Bretl, Wayne E.; and Lee, Ronald B., 4,296,435, Cl. 358-166.000.
- Lee, Weng Y.; and Sehon, Alec. Suppression of reaginic antibodies to drugs employing polyvinyl alcohol as carrier therefor. 4,296,097, Cl. 424-78.000.
- Lefort, Emmanuel: See—
Jeandot, Jean-Louis; and Lefort, Emmanuel, 4,296,383, Cl. 330-301.000.
- Leggett & Platt, Incorporated: See—
Wells, Thomas J., 4,295,639, Cl. 267-91.000.
- Whitehead, Larry W., 4,295,234, Cl. 5-184.000.
- Leininger, Joel C.: See—
Fairchild, Peter T.; and Leininger, Joel C., 4,296,470, Cl. 364-200.000.
- Leithem, Phyllis C., to International Telephone and Telegraph Corp. Process for acid sulfite digestion of wood. 4,295,929, Cl. 162-83.000.
- Lemak, Nicholas S., to Honeywell Information Systems Inc. Data mover. 4,296,465, Cl. 364-200.000.
- Lembke, Manfred; and Knapp, Heinrich, to Robert Bosch GmbH. Fuel injection system. 4,295,452, Cl. 123-470.000.
- Leney, Thomas F.: See—
Felton, Frank M.; Miller, Clyde A.; and Leney, Thomas F., 4,296,415, Cl. 343-16.00M.
- Lennon, Donald J. J.; Hagerstrom, John R.; and Ekman, C. Frederick W., to EPP Corp. Inks for pulsed electrical printing. 4,296,176, Cl. 428-407.000.
- Lenzi, Giuliano: See—
Toti, Gabriele; Lenzi, Giuliano; and Monti, Paolo, 4,295,660, Cl. 280-714.000.
- Leonard, Verna M. Keyboard simulation with vertical inversion indexes. 4,295,407, Cl. 84-471.00R.
- Lerch, John A., to Vulcan Iron Works Inc. Retaining assembly. 4,295,752, Cl. 403-317.000.
- Lerch, Ulrich: See—
Bartmann, Wilhelm; Beck, Gerhard; Lerch, Ulrich; and Konz, Elmar, 4,296,121, Cl. 424-275.000.
- Leslie, Wayne B. Speed indicating device. 4,295,367, Cl. 73-184.000.
- Leupold, Ernst I.: See—
Wunder, Friedrich; Leupold, Ernst I.; Hachenberg, Horst; and Schmidt, Hans-Joachim, 4,296,266, Cl. 585-640.000.
- Lever Brothers Company: See—
Mindt, Lothar F. O.; deceased; Payne, Peter R., administrator; and Sanderson, George R., 4,296,234, Cl. 536-47.000.
- Sepulveda, Ralph R.; and Lander, Lynn H., 4,295,845, Cl. 8-139.100.
- Levine, Irving. Apparatus for molding strand-mounted plastic members. 4,295,813, Cl. 425-121.000.
- Lewis, John A., to Racal Recorders, Ltd. Magnetic recording and reproduction. 4,296,447, Cl. 360-113.000.
- Lewis, Richard B.: See—
Gruber, Robert J.; Bolte, Steven B.; Knapp, John F.; Ims, Dale R.; and Lewis, Richard B., 4,296,192, Cl. 430-109.000.
- Lewis, Robert J., to Phillips Petroleum Company. Method for producing carbon black. 4,296,087, Cl. 423-449.000.
- Lewis, Terry W., to Minnesota Mining and Manufacturing Company. Information carrying discs. 4,296,158, Cl. 428-65.000.
- Lewus, Alexander J. Auxiliary power system for automotive vehicle. 4,295,538, Cl. 180-165.000.
- Lex, Franz. Cleaning device. 4,295,240, Cl. 15-22.00R.
- Leybold-Heraeus GmbH: See—
Beinitz, Karl; and Schubert, Joachim, 4,296,356, Cl. 315-135.000.

- Wechsung, Reiner, 4,296,322, Cl. 250-282.000.
 Leybold-Heraeus GmbH & Co. KG: See—
 Stephan, Herbert; Aichert, Hans; and Heimerl, Joseph, 4,295,808, Cl. 425-8.000.
 Liberman, Salomon: See—
 Eriksson, Leif; and Liberman, Salomon, 4,296,452, Cl. 361-82.000.
 Licentia Patent-Verwaltungs-G.m.b.H.: See—
 Kasper, Erich, 4,295,923, Cl. 156-630.000.
 Licht, Lazar, to United Technologies Corporation. Adjustable clearance foil journal bearing and method of manufacturing foil element therefor. 4,295,689, Cl. 308-9.000.
 Liebert, Karl-Heinz, to Zahnradfabrik Friedrichshafen, AG. Hydraulic rotary toothed piston engine with flow through the toothed gaps. 4,295,805, Cl. 418-61.00B.
 Lifshits, Viktor S.; Krivosos, Vadim P.; Podola, Nikolai V.; Grabchev, Boris L.; Andrianov, Vladimir R.; and Shakirov, Rifkhat M. Machine for continuous flash butt welding. 4,296,305, Cl. 219-101.000.
 Lin, Timothy T.: See—
 Jacobson, Richard L.; and Lin, Timothy T., 4,296,191, Cl. 430-57.000.
 Lindgren, Hazelle C. Brassiere construction. 4,295,469, Cl. 128-480.000.
 Litton Resources Systems, Inc.: See—
 Haill, Harry K., 4,296,483, Cl. 367-13.000.
 Litton Systems, Inc.: See—
 Rosenheck, Bernard, 4,296,440, Cl. 358-257.000.
 Liu, Morris. Inflatable tent. 4,295,302, Cl. 52-2.000.
 Locatelli, John D.; and Gunderson, Gary M., to Locatelli, John D. File box. 4,295,599, Cl. 229-34.00R.
 Lochner, Kaspar. Paste-like, viscous damping medium comprising polyglycol ethers and/or esters. 4,295,984, Cl. 252-62.000.
 Locit Corporation: See—
 Bacci, Louis J., 4,295,909, Cl. 156-307.300.
 Lollert, Bernd; and Risse, Heinrich, to Jagenberg-Werke AG. Irregular-motion mechanism. 4,295,382, Cl. 74-68.000.
 Long, E. David, to Allied Chemical Corporation. Closed loop fuel control for internal combustion engine. 4,295,451, Cl. 123-438.000.
 L'Oreal: See—
 Berrebi, Claudine; and Manoussos, Georges, 4,296,099, Cl. 424-105.000.
 Grollier, Jean F.; Bugaut, Andree; Andriillon, Patrick; and Fourcadier, Chantal, 4,295,848, Cl. 8-421.000.
 Lott, Donald L., to Siemens-Allis, Inc. Flexible shield for high voltage disconnect switch. 4,296,284, Cl. 200-48.00R.
 Louthan, Jean H.; Cox, Russell C.; and Crawford, William V., to Phillips Petroleum Company. Adapter for connecting plastic pipe system to cast iron pipe system. 4,295,668, Cl. 285-21.000.
 Lovell, John A.; and McIntosh, Kenneth W., to Goodyear Tire & Rubber Company, The. Tire and method of reinforcement. 4,295,513, Cl. 152-358.000.
 Lowe, Edward J.; Minshall, Michael W.; and Wilson, Arthur, to Albright & Wilson Limited. Purification of wet process phosphoric acid. 4,296,082, Cl. 423-305.000.
 Lowell, Victor: See—
 Boulanger, Henry J.; Lowell, Victor; and Whipple, Elliot, 4,296,287, Cl. 200-83.00P.
 Lucas Industries Limited: See—
 Archer, Michael A., 4,296,361, Cl. 318-54.000.
 Seilly, Alec H.; Mowbray, Dorian F.; Mardell, John E.; and Davison, Michael J., 4,295,453, Cl. 123-499.000.
 Young, Donald A.; and Squires, Christopher P., 4,296,342, Cl. 310-77.000.
 Ludwig, Lawrence P.: See—
 Bill, Robert C.; and Ludwig, Lawrence P., 4,295,786, Cl. 415-174.000.
 Luebke, Clement J.; Mitchell, John A.; and Daniels, Lowell W., to Alco Standard Corporation. Cooking device with water detecting means. 4,296,310, Cl. 219-440.000.
 Luerken, Adolf; and Vogel, William D., to McCulloch Corporation. Torque transmitting apparatus. 4,295,753, Cl. 403-365.000.
 Luers, George A., to Corning Glass Works. Producing a multi-color image in polychromatic glass. 4,295,872, Cl. 65-30.110.
 Lukas, Walter: See—
 Aignesberger, Alois; Lukas, Walter; and Weinberg, Ekkehard, 4,296,089, Cl. 423-555.000.
 Lundstrom, Sten, to Aktiebolaget SKF. Nail press. 4,295,591, Cl. 227-142.000.
 Lustgarten, Stewart J., to Healthco Inc. Method of manufacturing a metal ceramic dental restoration. 4,295,941, Cl. 204-35.00R.
 Lustig, Stanley; and Vick, Stephen J., to Union Carbide Corporation. Multilayer film including a polyurethane. 4,296,156, Cl. 428-35.000.
 Lustig, Stanley: See—
 Vasudevan, Ganapathy; and Lustig, Stanley, 4,296,142, Cl. 427-28.000.
 Lynn-Jones, David M.; and Stewart, R. Gordon, to Construction Specialties, Inc. Expansion joint cover. 4,295,315, Cl. 52-573.000.
 M.A.N.-Roland Druckmaschinen Aktiengesellschaft: See—
 Abendroth, Paul; and Dettinger, Dietrich, 4,295,421, Cl. 101-216.000.
 Maby, Edward W.; Kawamoto, Hirohisa; and Valembois, Pierre V., to RCA Corporation. Ion implanted stylus. 4,296,144, Cl. 427-38.000.
 Machinefabriek C. Rijkaart B.V.: See—
 Rutten, Jacques P., 4,296,135, Cl. 426-275.000.
 MacMaster, George H.; and Dudley, Kenneth W., to Raytheon Company. Dielectric cooking apparatus. 4,296,298, Cl. 219-10.810.
 Madeyski, Krystyn: See—
 Hologa, Zygmunt; Madeyski, Krystyn; and Kurowski, Adam, 4,296,273, Cl. 174-99.00B.
 Madnick, Peter: See—
 Dennesen, Francis G.; Wilson, Richard S.; Toulon, Roy D., Jr.; and Madnick, Peter, 4,295,277, Cl. 33-181.00R.
 Madonia, Ciro N.; Hatzikelis, Christopher; and Cosentino, Cesare C. Overcoated decorative moulding. 4,296,155, Cl. 428-31.000.
 Maegerlein, Helmut: See—
 Zielke, Rainer; and Maegerlein, Helmut, 4,296,260, Cl. 568-763.000.
 Magnaflux Corporation: See—
 White, Michael L., 4,295,362, Cl. 73-104.000.
 Magrans, Juan J., Jr., to ICI Americas Inc. Polyurea thickened molding compositions. 4,296,020, Cl. 260-37.00N.
 Mahl, Gunard O. B., to CHA Industries. Vacuum chamber door assembly and method. 4,296,153, Cl. 427-444.000.
 Mahuson, Teri J.: See—
 Hull, Charles J.; Hutton, James E.; and Mahuson, Teri J., 4,295,732, Cl. 355-14.00R.
 Maier, Martin; Purrer, Josef; and Clemens, Ronald, to Klockner-Humboldt-Deutz AG (Zweigniederlassung Fahr). Towed crop harvester. 4,295,323, Cl. 56-10.200.
 Majewski, Robert A.: See—
 DeHart, John R.; and Majewski, Robert A., 4,295,321, Cl. 53-381.00R.
 Malcom, George E. Combination hinge and overcenter closure for a door. 4,295,245, Cl. 16-80.000.
 Malecha, Richard J., to Towmotor Corporation. Apparatus for supporting loads. 4,295,541, Cl. 180-315.000.
 Mallory, Henry R.; and Nichols, Steven J., to Duracell International Inc. Battery package with DC to DC converter. 4,296,461, Cl. 363-22.000.
 Malmgren, Nils-Gunnar; Solly, Barry; and Tarnblom, Stig, to Fagersta AB. Rolled wire having a fine-grain structure. 4,295,900, Cl. 148-12.00B.
 Manassen, Joost: See—
 Hodes, Gary; Cahen, David; and Manassen, Joost, 4,296,188, Cl. 429-111.000.
 Manhattan R. F. Die Company: See—
 Schaefer, Hans G.; and Langer, Alfred, 4,295,908, Cl. 156-251.000.
 Manini, Silvio; and Pacciarini, Antonio, to Industrie Pirelli S.p.A. Apparatus for automatically turning over and for storing sections of elastomeric material. 4,295,774, Cl. 414-331.000.
 Mann, Don C.: See—
 Garcia, Felix, Jr.; Hergert, Roger A.; Mann, Don C.; and Brown, Sheldon H., 4,296,448, Cl. 360-135.000.
 Mann, Samuel J.; and Hrehovcik, Michael, to Inverness International Corp. Electrolysis apparatus with retractable probe. 4,295,467, Cl. 128-303.180.
 Mannesmann Aktiengesellschaft: See—
 Siegmund, Werner, 4,296,207, Cl. 521-53.000.
 Manning, Frank B., to United Technologies Corporation. Variable stator. 4,295,784, Cl. 415-162.000.
 Manning, Robert E. Interceptor plug. 4,295,694, Cl. 339-8.00P.
 Manoussos, Georges: See—
 Berrebi, Claudine; and Manoussos, Georges, 4,296,099, Cl. 424-105.000.
 Mapes, Charles W.; and Snyder, Richard H., to Brunswick Corporation. High speed outboard drive unit. 4,295,835, Cl. 440-78.000.
 Mardell, John E.: See—
 Seilly, Alec H.; Mowbray, Dorian F.; Mardell, John E.; and Davison, Michael J., 4,295,453, Cl. 123-499.000.
 Maresca, Louis M.; Gill, Peter J.; and Berger, Mitchell H., to Union Carbide Corporation. Process for preparing polyarylates in the presence of a diphenyl ether compound and a catalyst. 4,296,232, Cl. 528-179.000.
 Mareydt, Ray G.: See—
 Kowalski, Daniel J.; and Mareydt, Ray G., 4,295,588, Cl. 224-321.000.
 Mark Controls Corporation: See—
 Priesmeyer, Charles H., 4,295,602, Cl. 236-93.00B.
 Markham, Roger G.; and Skinner, Doyle P., Jr., to Xerox Corporation. Ink jet method and apparatus using a thin film piezoelectric excitor for drop generation with spherical and cylindrical fluid chambers. 4,296,417, Cl. 346-75.000.
 Markiewicz, Kenneth H., to ICI Americas Inc. Method to thicken dissolved thermoset resins. 4,296,215, Cl. 525-28.000.
 Marler Haley Exposystems Limited: See—
 Ashton, Christopher J.; Diamond, Andrew C.; and Greenhill, Derek H., 4,295,754, Cl. 403-369.000.
 Marosi, Laszlo: See—
 Steck, Werner; Sarnecki, Wilhelm; Marosi, Laszlo; Ohlinger, Manfred; and Autzen, Horst, 4,295,879, Cl. 75-0.5AA.
 Marquette Electronics, Inc.: See—
 Dambach, Thomas F.; and Ricketts, James R., 4,296,420, Cl. 346-140.00R.
 Marsh, Richard L., to Dayco Corporation. Synchronous belt drive system. 4,295,837, Cl. 474-153.000.
 Marshall, Jerald E. Device for human body waste elimination during incapacitation. 4,295,232, Cl. 4-480.000.
 Marshall, Michael A.: See—
 Swales, Danvers A.; and Marshall, Michael A., 4,296,076, Cl. 423-53.000.
 Marshall and Williams Company: See—
 Witkin, Philip M., 4,295,284, Cl. 34-155.000.

- Marth, Ronald M.: See—
 Sim, William J.; and Marth, Ronald M., 4,296,048, Cl. 261-111.000.
 Martin, Howard; and Norris, James P. Endodontic flow through ultrasonic instrument holder attachment. 4,295,827, Cl. 433-81.000.
 Martinek, Harold H.: See—
 Trimble, Roy L.; Story, Alfred D.; and Martinek, Harold H., 4,295,247, Cl. 17-1.00R.
 Martinelli, Claude; and Martinelli eponse Boisson, Marcelle. Tool holder. 4,295,829, Cl. 433-99.000.
 Martinelli eponse Boisson, Marcelle: See—
 Martinelli, Claude; and Martinelli eponse Boisson, Marcelle, 4,295,829, Cl. 433-99.000.
 Marvin Glass & Associates: See—
 Rosenwinkel, Donald A.; Meyer, Burton C.; and Disko, Harry, 4,295,294, Cl. 46-205.000.
 Marvin, Richard H.: See—
 Dickhart, William W., III; and Marvin, Richard H., 4,295,428, Cl. 105-168.000.
 Mascellani, Giuseppe: See—
 Borzatta, Valerio; Cristofori, Manlio; Morotti, Mauro; and Mascellani, Giuseppe, 4,296,125, Cl. 424-315.000.
 Maschinenfabrik Burckhardt AG: See—
 Bauer, Helmut, 4,296,221, Cl. 526-87.000.
 Maschinenfabrik Carl Zangs Aktiengesellschaft: See—
 Desprez, Alfred; Sauerland, Heinz; and Teetz, Wolfgang, 4,295,433, Cl. 112-241.000.
 Masologites, George P.: See—
 Sun, Jui-Yuan; Burk, Emmett H., Jr.; Yoo, Jin S.; and Masologites, George P., 4,295,858, Cl. 44-1.0SR.
 Massabo, Vincenzo: See—
 Moiso, Ugo; Massabo, Vincenzo; and Domenis, Danilo, 4,296,028, Cl. 260-160.000.
 Massachusetts Institute of Technology: See—
 Flemings, Merton C.; and Goodwin, Frank E., 4,295,896, Cl. 148-1.000.
 Wurtman, Richard J., 4,296,119, Cl. 424-274.000.
 Mastner, Jiri, to BBC Brown, Boveri & Company Limited. Method and apparatus for signal transmission. 4,296,412, Cl. 340-870.190.
 Mateflex/Mele Corporation: See—
 Forlenza, Nicholas G., 4,296,160, Cl. 428-117.000.
 Mathias Bauerle GmbH: See—
 Purr, Horst; Kistler, Manfred; and Muller, Rolf, 4,295,913, Cl. 156-345.000.
 Mathieu, Hans; and Hochstrasser, Jurgen, to Hochstrasser geb. Wack, Elisabeth; and Hochstrasser, Jurgen. Device for the control of the internal pressure in a drill pipe for the construction of footings. 4,295,759, Cl. 405-243.000.
 Mathuda, Yoshimi: See—
 Iwahana, Keiiti; Mathuda, Yoshimi; and Futamura, Kenichiro, 4,296,183, Cl. 428-653.000.
 Matsubara, Akira; Sakai, Hideaki; Odate, Makoto; Suganuma, Toshio; and Nakano, Takuo, to Mitsui Toatsu Chemicals, Inc. Cephalosporins. 4,296,112, Cl. 424-246.000.
 Matsubayashi, Hiroshi; Tsurumaru, Michiko; Horiguchi, Makoto; Ueno, Hiroshi; and Kitamura, Yoichi, to Toyo Seikan Kaisha Limited. Can composed of electrolytically chromated steel. 4,296,182, Cl. 428-629.000.
 Matsufuji, Yoji: See—
 Eida, Tsuyoshi; Haruta, Masahiro; Yano, Yasuhiro; Matsufuji, Yoji; and Ohta, Tokuya, 4,295,889, Cl. 106-22.000.
 Matsuhisa, Tadaaki; Soejima, Shigeo; and Yamamoto, Noboru, to NGK Insulators, Ltd. Cordierite ceramic honeycomb and a method for producing the same. 4,295,892, Cl. 501-120.000.
 Matsui, Kazuma: See—
 Nomura, Eisui; Matsui, Kazuma; Miyazaki, Toshikuni; Sami, Hiroshi; and Ueda, Tatehito, 4,295,456, Cl. 123-569.000.
 Matsumoto, Keizo: See—
 Okumichi, Toshiharu; Oseto, Osamu; Matsumoto, Keizo; Thuzimoto, Shigenori; and Sanda, Hisanari, 4,296,012, Cl. 260-29.6XA.
 Matsunaga, Tsutomu: See—
 Saito, Tasuku; Noma, Tsutomu; Matsunaga, Tsutomu; Naito, Nagayoshi; Tanaka, Chiaki; and Hiratsuka, Motoki, 4,295,652, Cl. 273-235.00R.
 Matsushima, Yoshio; Kumura, Teruhiko; Kawamura, Isamu; and Kawata, Terushige, to Kyowa Chemical Industry Co., Ltd. Dental cleaning composition and method. 4,296,094, Cl. 424-49.000.
 Matsushita Electric Corporation of America: See—
 Rzeszewski, Theodore S., 4,296,433, Cl. 358-37.000.
 Matsushita Electric Industrial Co.: See—
 Minakuchi, Hiroshi, 4,296,380, Cl. 328-48.000.
 Minakuchi, Hiroshi, 4,296,407, Cl. 340-347.0CC.
 Takezaki, Tsuneo, 4,296,375, Cl. 324-103.00P.
 Matsushita Electric Industrial Co., Ltd.: See—
 Kiuchi, Mitsuyuki, 4,296,295, Cl. 219-10.49R.
 Sugino, Takashi; and Itoh, Kunio, 4,296,387, Cl. 331-94.50H.
 Tsuchida, Kensaku; and Karasawa, Shinji, 4,296,303, Cl. 219-78.130.
 Matsushita Electronics Corporation: See—
 Yoshida, Masakatsu; Tochio, Yoshihiko; and Tohi, Atsutomu, 4,295,898, Cl. 148-1.500.
 Matsuyama, Shigeru: See—
 Tanaka, Hironari; Matsuyama, Shigeru; Ishibashi, Tadashi; Kinugawa, Kiyoshige; and Sato, Yukihiro, 4,295,711, Cl. 350-334.000.
 Matt, Frederick C. Computer programming training device. 4,295,831, Cl. 434-118.000.
 Mattheij, Jozef M. J.: See—
 Verbeek, Antonie E.; and Mattheij, Jozef M. J., 4,295,990, Cl. 252-408.000.
 Matthews, James. Combination carpet razor knife and guide. 4,295,273, Cl. 30-293.000.
 Matweyou, Stephen: See—
 Bascom, Hollis H.; Matweyou, Stephen; Andersen, Alan J.; and Greci, John J., 4,295,905, Cl. 156-174.000.
 Matzner, Erwin, to Jagenberg Werke AG. Method and apparatus for the elimination of foam above the level of a liquid, and particularly above a packaged liquid such as milk. 4,295,502, Cl. 141-11.000.
 Mauldin, Charles H.; and Baird, William C., Jr., to Exxon Research & Engineering Co. Reforming with multimetallic catalysts. 4,295,957, Cl. 208-138.000.
 Mauldin, Charles H.; and Baird, William C., Jr., to Exxon Research & Engineering Co. Reforming with multimetallic catalysts. 4,295,958, Cl. 208-138.000.
 Maurel, Pierre; Nicolas, Francois; and Bosca, Bernard, to Aluminum Pechiney. High temperature attack of ores by means of a liquor essentially containing a soluble bicarbonate. 4,296,073, Cl. 423-3.000.
 Maurer, Fritz: See—
 Hoffmann, Hellmut; Maurer, Fritz; Priesnitz, Uwe; and Riebel, Hans-Jochem, 4,296,241, Cl. 560-124.000.
 Maurer, Herman J., to J. I. Case Company. Latching mechanism for machine stabilizer arms using hydraulic cylinders. 4,295,661, Cl. 280-765.000.
 Mavrovic, Ivo. Urea synthesis process. 4,296,252, Cl. 564-70.000.
 Maya, Jakob, to GTE Products Corporation. Gaseous fluorescent discharge lamp. 4,296,350, Cl. 313-26.000.
 Mayer, Manfred; and Volz, Roland, to Hoechst Aktiengesellschaft. Rectifier. 4,295,937, Cl. 202-155.000.
 Mayer, Steven T.; Miner, Jay G.; Neubauer, Douglas G.; and Decuir, Joseph C., to Atari, Inc. Data processing system with programmable graphics generator. 4,296,476, Cl. 364-900.000.
 Mazzei, Alessandro: See—
 Cucinella, Salvatore; Mazzei, Alessandro; and Dozzi, Giovanni, 4,296,045, Cl. 260-448.00R.
 McAleer, William J.; and Miller, William J., to Merck & Co., Inc. Human immune serum globulin with high hepatitis A antibody titer. 4,296,024, Cl. 260-112.00B.
 McAlister, Doyle V.: See—
 Gunter, Thomas G.; Tredennick, Harry L.; and McAlister, Doyle V., 4,296,469, Cl. 364-200.000.
 McAvinn, James D.; Meister, Arthur R.; and Tucker, Samuel M., to Kendall Company, The. Sponge measuring device. 4,295,537, Cl. 177-15.000.
 McBride, Jack L. Eye splice fitting. 4,295,749, Cl. 403-211.000.
 McCabe, Francis J., to Prefco Products, Inc. Low cost, diffuser concealable, volume control, heat responsive, resettable, butterfly damper operator. 4,295,486, Cl. 137-80.000.
 McCartan, Daniel A.: See—
 Bemis, Richard S.; and McCartan, Daniel A., 4,296,164, Cl. 428-219.000.
 McCarty, Lewis V.: See—
 Berlec, Ivan; and McCarty, Lewis V., 4,296,352, Cl. 313-315.000.
 McCleery, Jerry E.: See—
 Waterman, Fred W.; McCleery, Jerry E.; and McKie, Robert T., 4,295,427, Cl. 104-32.00R.
 McClellan, Thomas R.: See—
 Ewen, James H.; and McClellan, Thomas R., 4,296,212, Cl. 521-163.000.
 McCulloch Corporation: See—
 Luerken, Adolf; and Vogel, William D., 4,295,753, Cl. 403-365.000.
 McDaniel, Max P.; and Welch, Melvin B., to Phillips Petroleum Company. SO₂ Activation of supported chromium oxide catalysts. 4,295,997, Cl. 252-439.000.
 McGalliard, James D. Fluid sensitive switching controller. 4,295,793, Cl. 417-36.000.
 McGalliard, James D. Printed circuit fuse assembly. 4,296,398, Cl. 337-297.000.
 McGowan, John B.; and Trimble, John, to UMAC, Inc.; and Brooklyn Union Gas Company, a part interest to each. Method and apparatus for plugging and cutting a gas line or the like without excavation. 4,295,494, Cl. 138-89.000.
 McGraw-Edison Company: See—
 Sokoly, Theodore O.; and Niedzialkowski, John, 4,296,002, Cl. 252-518.000.
 McHugh, William T.: See—
 Barnes, John E.; Goebel, Franz; and McHugh, William T., 4,296,187, Cl. 429-105.000.
 McIntosh, Arthur M., to Borg-Warner Corporation. Automatic two-speed pump assembly. 4,295,798, Cl. 417-212.000.
 McIntosh, Kenneth W.: See—
 Lovell, John A.; and McIntosh, Kenneth W., 4,295,513, Cl. 152-358.000.
 McKie, Robert T.: See—
 Waterman, Fred W.; McCleery, Jerry E.; and McKie, Robert T., 4,295,427, Cl. 104-32.00R.
 McMahan, Michael E., to Halliburton Company. Drill pipe tester with automatic fill-up. 4,295,361, Cl. 73-40.50R.
 McManus, Ira J. Precast concrete joist composite system. 4,295,310, Cl. 52-334.000.

McMillen, Bobby E., to AMBAC Industries, Incorporated. Electric motor housing, or the like, with integral pole and methods for making same. 4,296,343, Cl. 310-154.000.

McMullen, Harold F. Valance support. 4,295,482, Cl. 135-8.000.

McMurry/Hughes, Inc.: See—

Moore, Howard H., 4,295,796, Cl. 417-115.000.

Mead Corporation, The: See—

Calvert, Rodney K., 4,295,598, Cl. 229-52.0A.L.

Wood, Prentice J., 4,295,562, Cl. 206-158.000.

Mecke, Norbert; Schmitt, Franz U.; Schrader, Karl-Heinz; and Blutschkau, Heine, to Pelikan A.G. Transparent image marking sheet for projection systems. 4,296,150, Cl. 427-164.000.

Medtronic, Inc.: See—

Adams, John M., 4,295,472, Cl. 128-690.000.

Cammarata, Jacob J., 4,295,270, Cl. 29-828.000.

Mehesan, Thomas C., Jr., to Banner Industries, Inc. Portable load handling apparatus. 4,295,771, Cl. 414-5.000.

Meier, Werner, to Sulzer Brothers Ltd. Packing element for an exchange column. 4,296,050, Cl. 261-112.000.

Meisenheimer, Daniel T., Jr. Frangible connector for self-closing breakaway valve assemblies or similar structures. 4,295,484, Cl. 137-68.00R.

Meister, Arthur R.: See—

McAvinn, James D.; Meister, Arthur R.; and Tucker, Samuel M., 4,295,537, Cl. 177-15.000.

Meito Sangyo Kabushiki Kaisha: See—

Sasaki, Susumu; Kito, Kyoji; and Koide, Akio, 4,295,855, Cl. 23-230.00B.

Melanson, Donald G., to United Technologies Corporation. Shrouded tube and coupling therefor. 4,295,666, Cl. 285-14.000.

Meli, Alberto: See—

Ghelardoni, Mario; Pestellini, Vittorio; Del Soldato, Piero; Volterra, Giovanna; and Meli, Alberto, 4,296,124, Cl. 424-285.000.

Meltz, Gerald; and Snitzer, Elias, to United Technologies Corporation. Fiber optic strain sensor. 4,295,738, Cl. 356-32.000.

Meltz, Gerald; and Snitzer, Elias, to United Technologies Corporation. Fiber optic temperature sensor. 4,295,739, Cl. 356-43.000.

Mentrup, Anton: See—

Koppe, Herbert; Mentrup, Anton; Renth, Ernst-Otto; Schromm, Kurt; Hoefke, Wolfgang; and Muacevic, Gojko, 4,296,117, Cl. 424-273.00B.

Merck & Co. Inc.: See—

Beattie, Thomas R.; Christensen, Burton G.; and Dinno, Frank P., 4,296,111, Cl. 424-246.000.

Christensen, Burton G.; Johnston, David B. R.; and Firestone, Raymond A., 4,296,236, Cl. 542-420.000.

Cragoe, Edward J., Jr.; and Woltersdorf, Otto W., Jr., 4,296,122, Cl. 424-285.000.

Cragoe, Edward J., Jr., 4,296,237, Cl. 544-405.000.

Grabner, Roy; and Paul, Edward L., 4,296,204, Cl. 435-235.000.

McAleer, William J.; and Miller, William J., 4,296,024, Cl. 260-112.00B.

Merck Patent Gesellschaft mit beschränkter Haftung: See—

Halpaap, Herbert; and Krebs, Karl-Friedrich, 4,295,968, Cl. 210-198.300.

Meredith, Michael D.: See—

Bentvelzen, Jozef M.; Meredith, Michael D.; Bepple, Henry; Torregrossa, Louis O.; Battan, Howard R.; and Justice, Dennis H., 4,295,925, Cl. 162-19.000.

Bentvelzen, Jozef M.; Meredith, Michael D.; Bepple, Henry; Torregrossa, Louis O.; Battan, Howard R.; and Justice, Dennis H., 4,295,926, Cl. 162-57.000.

Bentvelzen, Jozef M.; Meredith, Michael D.; Bepple, Henry; Torregrossa, Louis O.; Battan, Howard R.; and Justice, Dennis H., 4,295,927, Cl. 162-57.000.

Mergen, Joseph, to Bangor Punta Corporation. Steerable self-supporting trailer. 4,295,659, Cl. 280-405.00R.

Merrell, Charles E. Jeweler's tool. 4,295,640, Cl. 269-47.000.

Meshri, Indurani D., to Standard Oil Company (Indiana). NMR Analysis of subterranean reservoir samples immersed in liquid halocarbons. 4,295,365, Cl. 73-153.000.

Messer Griesheim GmbH: See—

Roeder, Georg; and Sachs, Helmut, 4,295,820, Cl. 431-191.000.

Messerschmitt-Bolkow-Blohm GmbH: See—

Kohler, Kranz, 4,296,270, Cl. 136-244.000.

Metallgesellschaft Aktiengesellschaft: See—

Rudolph, Paul; and Becker, Paul D., 4,295,864, Cl. 55-40.000.

Metrailler, William J., to Exxon Research & Engineering Co. Fluid coking process. 4,295,956, Cl. 208-127.000.

Meitzger, Harold L. Flexible garbage can lid. 4,295,508, Cl. 150-52.00R.

Meyer, Burton C.: See—

Rosenwinkel, Donald A.; Meyer, Burton C.; and Disko, Harry, 4,295,294, Cl. 46-205.000.

Meyer, Stephen T., to Deflecto Corporation. File folder support rack. 4,295,571, Cl. 211-200.000.

Meyers, Edward: See—

Weisenborn, Frank L.; Brown, William E.; and Meyers, Edward, 4,296,101, Cl. 424-119.000.

Meyers, Frank. Reel mountable boom arrangement. 4,295,755, Cl. 405-66.000.

Mezzanotte, Mario; and Turchetti, Gianni, to Societa Pneumatici Pirelli S.p.A. Radial tires provided with a stiffening structure in the sidewalls. 4,295,511, Cl. 152-354.00R.

Mezzetti, Sergio; Pizzolati, Pierluigi; and Svelto, Francesco, to C.I.S.E. Centro Informazioni Studi Esperienze S.p.A. Opto-electronic instru-

ment for remote temperature measurement. 4,296,318, Cl. 250-225.000.

Mialon, Jacques; and Lamarche, Bernard, to Societe Nationale Industrielle Aerospatiale. Control rod and a process for fitting a connecting member at one end of a control rod. 4,295,388, Cl. 74-579.00R.

Michel, Wolfgang: See—

Becker, Reinhold; Michel, Wolfgang; and Hartmann, Gerhard, 4,295,563, Cl. 206-205.000.

Michne, William F., to Sterling Drug Inc. 2,6-Methano-3-benzazocines. 4,296,238, Cl. 546-97.000.

Middlebrook, Robert E.; Harvey, George R.; and Chupp, John P., to Monsanto Company. Transesterification in amides. 4,296,254, Cl. 564-214.000.

Miedema, Brent: See—

Grantmyre, Innes; and Miedema, Brent, 4,295,411, Cl. 91-165.000.

Mikami, Takashi; Fujii, Shigeo; Okano, Shuji; and Ikeda, Tokuzo, to Toa Nenryo Kogyo Kabushiki Kaisha. Die for a melt blowing process. 4,295,809, Cl. 425-72.00S.

Milana, Emilio; and Rasello, Franco, to Centro Ricerche Fiat S.p.A. Method and apparatus for detecting surface defects in a workpiece. 4,296,333, Cl. 250-572.000.

Milkovic, Miran, to General Electric Company. Resistance-bridge to frequency converter with automatic offset correction. 4,296,413, Cl. 340-870.380.

Millar, Donald B., to General Foods Inc. Production of soybean protein isolate of improved purity. 4,296,026, Cl. 260-123.500.

Miller, Clyde A.: See—

Pelton, Frank M.; Miller, Clyde A.; and Leney, Thomas F., 4,296,415, Cl. 343-16.00M.

Miller, Fred J., to Arthur Fulmer of Mississippi, Inc. Hanger assembly for merchandise. 4,295,564, Cl. 206-279.000.

Miller, Matthew S., to General Electric Company. Drive arrangement for microwave oven mode stirrer. 4,296,297, Cl. 219-10.55F.

Miller, Samuel, to Victoreen, Inc. Automatic gain control for radiation analyzer. 4,296,320, Cl. 250-252.000.

Miller, Terry A., to Phillips Petroleum Company. Data display system. 4,296,484, Cl. 367-71.000.

Miller, Theodore H., to Emhart Industries, Inc. Vertical rod exit device. 4,295,673, Cl. 292-21.000.

Miller, Wendell D.: See—

Erb, Tom L.; and Miller, Wendell D., 4,295,378, Cl. 73-861.250.

Miller, William J.: See—

McAleer, William J.; and Miller, William J., 4,296,024, Cl. 260-112.00B.

Minakuchi, Hiroshi, to Matsushita Electric Industrial Co. Programmable digital frequency divider for synthesizing signals at desired frequency. 4,296,380, Cl. 328-48.000.

Minakuchi, Hiroshi, to Matsushita Electric Industrial Co. Digital frequency synthesizer with frequency divider programmable in response to stored digital control signal. 4,296,407, Cl. 340-347.0CC.

Mindt, Lothar F. O., deceased; by Payne, Peter R., administrator; and Sanderson, George R., to Lever Brothers Company. Absorbent materials. 4,296,234, Cl. 536-47.000.

Miner, Jay G.: See—

Mayer, Steven T.; Miner, Jay G.; Neubauer, Douglas G.; and Decuir, Joseph C., 4,296,476, Cl. 364-900.000.

Mineura, Kazuyuki: See—

Omura, Satoshi; Tanaka, Haruo; Takahashi, Itaru; Ishii, Shinzo; Mineura, Kazuyuki; Shirahata, Kunikatsu; and Kasai, Masaji, 4,296,040, Cl. 260-345.200.

Minneapolis Electric Steel Castings Company: See—

Mishek, James E., 4,295,615, Cl. 241-182.000.

Minnesota Mining and Manufacturing Company: See—

Fox, Bryce J., 4,295,282, Cl. 34-27.000.

Jacobson, Richard L.; and Lin, Timothy T., 4,296,191, Cl. 430-57.000.

Lewis, Terry W., 4,296,158, Cl. 428-65.000.

Schmit, Paul F., 4,295,904, Cl. 156-69.000.

Minolta Camera Kabushiki Kaisha: See—

Ikeda, Hiroshi, 4,295,736, Cl. 355-57.000.

Myochin, Hisashi, 4,295,239, Cl. 151-50R.

Sahara, Masayoshi; and Nakai, Masaaki, 4,295,724, Cl. 354-238.000.

Minoprio, William E.; and Horsfield, Arthur K., to Dorman Smith Traffic Products Limited. Lamps. 4,296,460, Cl. 362-200.000.

Minshall, Michael W.: See—

Lowe, Edward J.; Minshall, Michael W.; and Wilson, Arthur, 4,296,082, Cl. 423-305.000.

Mirabella, Paul J., to General Electric Company. Alignment device for computerized tomography phantoms. 4,296,329, Cl. 250-491.000.

Mishek, James E., to Minneapolis Electric Steel Castings Company. Shell liner assembly for ore comminuting machine. 4,295,615, Cl. 241-182.000.

Mishima, Toshio, to Kabushiki Kaisha Kawai Gakki Seisakusho. Noise generator. 4,296,384, Cl. 331-78.000.

Mita Industrial Company Limited: See—

Sasaki, Koichi; Sumida, Yasuji; and Ishida, Hiroshi, 4,295,731, Cl. 355-14.00R.

Mitchell, Hal D., to A-T-O Inc. Shoulder pad. 4,295,227, Cl. 2-2.000.

Mitchell, John A.: See—

Luebke, Clement J.; Mitchell, John A.; and Daniels, Lowell W., 4,296,310, Cl. 219-440.000.

Mitchell, Thomas O., to Mobil Oil Corporation. Coal conversion catalysts. 4,295,954, Cl. 208-10.000.

Mitco Corporation: See—

Gorchev, Dimitar; Ingard, Karl U.; and Willke, Herbert L., Jr., 4,295,416, Cl. 98-33.00R.

Mitoma, Yasuharu: See—

Satake, Toshihiko; Kono, Akira; Horie, Takashi; and Mitoma, Yasuharu, 4,295,420, Cl. 99-486.000.

Mitsubishi Denki Kabushiki Kaisha: See—

Sendo, Masaaki; and Suzuki, Kinzo, 4,296,063, Cl. 264-273.000.

Shimada, Wataru; Hoshinouchi, Susumu; Kawaguchi, Kenji; and Yoshida, Akio, 4,295,906, Cl. 156-214.000.

Tanaka, Naoki; Tsuchiya, Kunihiko; and Nishizawa, Toshizo, 4,295,806, Cl. 418-97.000.

Mitsubishi Jukogyo Kabushiki Kaisha: See—

Otomaru, Tadao, 4,295,843, Cl. 493-354.000.

Mitsubishi Rayon Co., Ltd.: See—

Kamada, Kazumasa; Nakai, Yoshio; and Abe, Kazunori, 4,296,214, Cl. 525-2.000.

Mitsui Engineering and Shipbuilding Co., Ltd.: See—

Yashima, Nobuyoshi, 4,295,758, Cl. 405-201.000.

Mitsui, Hiromitsu, to Kabushiki Kaisha Suwa Seikosha. Electronic timepiece. 4,296,489, Cl. 368-205.000.

Mitsui Toatsu Chemicals, Inc.: See—

Matsubara, Akira; Sakai, Hideaki; Odate, Makoto; Suganuma, Toshio; and Nakano, Takuo, 4,296,112, Cl. 424-246.000.

Miyagawa, Kiyoshi: See—

Sugata, Yoshiaki; and Miyagawa, Kiyoshi, 4,295,398, Cl. 82-31.000.

Miyashita, Kiyoshi: See—

Tsuda, Hiroshi; Miyashita, Kiyoshi; Nishikawa, Masaji; Shimizu, Akira; and Kasuga, Munee, 4,295,734, Cl. 355-15.000.

Miyazaki, Toshikuni: See—

Nomura, Etsuji; Matsui, Kazuma; Miyazaki, Toshikuni; Sami, Hiroshi; and Ueda, Tatehito, 4,295,456, Cl. 123-569.000.

Mizoguchi, Hitoshi: See—

Yanabu, Satoru; Mizoguchi, Hitoshi; and Simogawara, Naoaki, 4,296,288, Cl. 200-146.00R.

Mizokami, Kazunori, to Olympus Optical Company Ltd. Exposure control circuit of camera. 4,295,718, Cl. 354-50.000.

Mizokami, Kazunori; and Kitagawa, Masahiro, to Olympus Optical Company Ltd. Apparatus for determining light reflection from a focal plane shutter. 4,295,720, Cl. 354-51.000.

Mobil Oil Corporation: See—

Bowden, Edgar A., 4,296,442, Cl. 360-6.000.

Frangatos, Gerassimos, 4,295,982, Cl. 252-42.000.

Mitchell, Thomas O., 4,295,954, Cl. 208-10.000.

Rollmann, Louis D., 4,296,083, Cl. 423-329.000.

Yan, Tsoung-yuan, 4,296,075, Cl. 423-7.000.

Mochizuki, Hiroshi; and Seki, Tokio, to Kyosan Denki Kabushiki Kaisha. Diaphragm-type fuel pump. 4,295,414, Cl. 92-98.000.

Mock, George W., Jr.; and Mock, George W., Sr. Automatic flare signal apparatus. 4,295,437, Cl. 116-202.000.

Mock, George W., Sr.: See—

Mock, George W., Jr.; and Mock, George W., Sr., 4,295,437, Cl. 116-202.000.

Modica, Giovanni: See—

de Nora, Oronzio; Giuffre, Luigi; and Modica, Giovanni, 4,295,952, Cl. 204-252.000.

Moffatt, E. Marston, to United Technologies Corporation. Fluidic angular rate sensor with integrated impulse jet pump assembly. 4,295,373, Cl. 73-505.000.

Moiso, Ugo; Massabo, Vincenzo; and Domenis, Danilo. Pyrazolonyl substituted disazo pigments. 4,296,028, Cl. 260-160.000.

Mollet, Hans: See—

Haberli, Roland; Mollet, Hans; and Scherer, Gustaaf, 4,295,850, Cl. 8-524.000.

Momiyama, Kikuo; and Kumazawa, Kenichi, to Canon Kabushiki Kaisha. Single lens reflex camera. 4,295,723, Cl. 354-155.000.

Monash University: See—

Potter, Owen E., 4,295,281, Cl. 34-10.000.

Mones, Arthur H.: See—

Neuhoff, Donald; Mones, Arthur H.; and Lam, Man K., 4,295,271, Cl. 29-840.000.

Monex Corporation: See—

Perlman, Milton, 4,295,318, Cl. 52-693.000.

Monsanto Company: See—

Middlebrook, Robert E.; Harvey, George R.; and Chupp, John P., 4,296,254, Cl. 564-214.000.

Montalto, Michael S.; Blanding, Douglass L.; and Smith, Michael R., to Eastman Kodak Company. Slide distributor for a chemical analyzer. 4,296,070, Cl. 422-65.000.

Monti, Paolo: See—

Toti, Gabriele; Lenzi, Giuliano; and Monti, Paolo, 4,295,660, Cl. 280-714.000.

Moore, Arlan G., to von Hellens, C. Robert. Skateboard having flexible sides. 4,295,656, Cl. 280-87.04A.

Moore, Howard H., to McMurry/Hughes, Inc. Gas lift apparatus. 4,295,796, Cl. 417-115.000.

Moore, W. Edward C.; and Blanks, James A., to VPI Educational Foundation. Apparatus for breaking bacterial cells. 4,295,613, Cl. 241-2.000.

Moore, William J. M.; Kusters, Norbert L.; and So, Eddy, to Canadian Patents & Dev. Ltd. Active quadrature current reference source. 4,296,369, Cl. 323-218.000.

Moravec, Terrence D.: See—

Benson, Henry E.; and Moravec, Terrence D., 4,295,918, Cl. 156-434.000.

Mori, Kenji; and Sasaki, Mitsuru, to Sumitomo Chemical Company, Limited. Selective method for the preparation of insect pheromone. 4,296,036, Cl. 260-340.700.

Morishita, Hirosada: See—

Takahashi, Akio; Itoh, Yutaka; Wajima, Motoyo; Morishita, Hirosada; and Nishikawa, Akio, 4,296,219, Cl. 525-488.000.

Moritz, Bertil, to ASEA Aktiebolag. Structure for preventing winding collapse. 4,296,395, Cl. 336-60.000.

Moriya, Takeo; and Yamagata, Toshio, to Kimoto & Co., Ltd. Photosensitive positive diazo material with copolymer of acrylamide and diacetoneacrylamide and a process for developing to form color relief image. 4,296,193, Cl. 430-149.000.

Morlock, Gerhard: See—

Bugdahl, Volker; Morlock, Gerhard; Reidt, Werner; and Kerschner, Emil, 4,296,006, Cl. 260-23.0EP.

Morota, Kazutoshi; and Yuda, Takuo, to Nissan Motor Co., Ltd.; and Nifco, Inc. Device for fixing pipes, rods and other elongated bodies. 4,295,618, Cl. 248-73.000.

Morotti, Mauro: See—

Borzatta, Valerio; Cristofori, Manlio; Morotti, Mauro; and Mascellani, Giuseppe, 4,296,125, Cl. 424-315.000.

Morris, Robert L. Van modifiers. 4,295,678, Cl. 296-156.000.

Morris, Roger E.; and Jorgensen, August H., Jr., to B. F. Goodrich Company, The. Nitrile rubber containing cadmium antioxidants. 4,296,007, Cl. 260-23.70N.

Morrison-Knudsen Co., Inc.: See—

Waterman, Fred W.; McCleery, Jerry E.; and McKie, Robert T., 4,295,427, Cl. 104-32.00R.

Morrison, Leonard A.: See—

Spainhour, Phillip A.; Morrison, Leonard A.; and Hampton, Robert S., Jr., 4,295,634, Cl. 254-10.500.

Mosher, Joseph C.: See—

Grote, Daniel; Raymond, Duane; and Mosher, Joseph C., 4,295,262, Cl. 29-462.000.

Mostek Corporation: See—

Eaton, Sargent S., Jr.; and Schroeder, Paul R., 4,296,480, Cl. 365-222.000.

Motegi, Shoji: See—

Ooki, Norihiro; Motegi, Shoji; Wachi, Yasuyuki; Takikawa, Yoshio; and Yamakawa, Norio, 4,296,346, Cl. 310-242.000.

Motorola, Inc.: See—

Gunter, Thomas G.; Tredennick, Harry L.; and McAlister, Doyle V., 4,296,469, Cl. 364-200.000.

Thomas, James S., 4,296,338, Cl. 307-362.000.

Mott, James D., to Hydriol Company. Well safety system method and apparatus. 4,295,523, Cl. 166-250.000.

Mottier, Francois M.: See—

Palma, Gary E.; and Mottier, Francois M., 4,295,741, Cl. 356-349.000.

Motz, Kaye L., to Conoco Inc. Waterflood method. 4,295,980, Cl. 252-8.55D.

Mowbray, Dorian F.: See—

Seilly, Alec H.; Mowbray, Dorian F.; Mardell, John E.; and Davidson, Michael J., 4,295,453, Cl. 123-499.000.

Muacevic, Gojko: See—

Koppe, Herbert; Mentrup, Anton; Renth, Ernst-Otto; Schromm, Kurt; Hoefke, Wolfgang; and Muacevic, Gojko, 4,296,117, Cl. 424-273.00B.

Muchowski, Joseph M.; and Venuti, Michael C., to Syntex (U.S.A.) Inc. Preparation of unsaturated aliphatic insect pheromones using cyclic phosphonium ylids. 4,296,042, Cl. 260-345.90R.

Muhling, Alois; Reissner, Frank; and Schmidt, Helmut, to Siemens Aktiengesellschaft. Gearing for a motor driven timing relay. 4,295,380, Cl. 74-3.500.

Muller, Hans-Jürgen: See—

Pedain, Josef; Uerdingen, Walter; and Muller, Hans-Jürgen, 4,296,230, Cl. 528-67.000.

Muller, Johann: See—

Innertsberger, Ernst; Sommer, Oswin; Bosch, Erhard; Muller, Johann; and Schiller, August, 4,296,228, Cl. 528-33.000.

Muller, Rolf: See—

Purr, Horst; Kistler, Manfred; and Muller, Rolf, 4,295,913, Cl. 156-345.000.

Muller, Wolfgang: See—

Bergner, Dieter; Hannesen, Kurt; Muller, Wolfgang; and Schulte, Wilfried, 4,295,945, Cl. 204-128.000.

Johne, Hans; Muller, Wolfgang; Jentsch, Arndt; and Schumann, Gunter, 4,295,423, Cl. 101-349.000.

Mullett, William L., to NUS Corporation. Apparatus for disposing of radioactive fuel channels. 4,295,401, Cl. 83-864.000.

Munson, Harry R., Jr., to A. H. Robins Company, Inc. Mucolytic benzene and thiophene-carbathioic acid 2-aminoalkyl ester acid salts. 4,296,092, Cl. 424-43.000.

Murakoshi, Makoto: See—

Oosaka, Shigenori; and Murakoshi, Makoto, 4,295,589, Cl. 226-122.000.

Murdock, Keith C.: See—

Lang, Stanley A., Jr.; and Murdock, Keith C., 4,296,030, Cl. 260-239.00A.

Murotani, Tatsunori, to Nippon Electric Co., Ltd. Logic circuit comprising circuits for producing a faster and a slower inverted signal. 4,296,339, Cl. 307-450.000.

Muscattell, Ralph. Thermal and vacuum tracking carburetor jet. 4,295,450, Cl. 123-435.000.

Muskogee Environmental Conservation Co.: See—

Scriminger, William F., 4,295,744, Cl. 366-3.000.

Myochin, Hisashi, to Minolta Camera Kabushiki Kaisha. Apparatus for removing residual toner. 4,295,239, Cl. 151-50R.

N.A.D., Inc.: See—
Racz, Gabor; and Allen, Forrest, 4,295,465, Cl. 128-11.000.
Nabutovsky, Samoil I., deceased: See—
Zhirovotv, Yuri G.; Kupchinsky, Igor I.; Plokhuta, Vyacheslav D.; Bezverkhnny, Alexandr M.; Nabutovsky, Samoil I., deceased; and Eroshevskaya, Elena D., administrator, 4,295,387, Cl. 74-573.00F.
Nagabhushan, Tattanahalli L.; and Cooper, Alan, to Schering Corporation. Process for the preparation of chiral 3-amino-2-hydroxypropionic acid and N-blocked derivatives thereof. 4,296,242, Cl. 560-160.000.
Nahar, Rathindra; and Dietze, Robert H., to Burroughs Corporation. Document hopper with eccentric floor cylinders and a front auger. 4,295,645, Cl. 271-34.000.
Naito, Nagayoshi: See—
Saito, Tasuku; Noma, Tutomu; Matsunaga, Tsutomu; Naito, Nagayoshi; Tanaka, Chiaki; and Hiratsuka, Motoki, 4,295,652, Cl. 273-235.00R.
Naitoh, Katsumi, to NSK-Warner K.K.; and Nissan Motor Co., Ltd. Safety belt wind-up device. 4,295,684, Cl. 297-475.000.
Nakahama, Syuhei; and Yamashita, Etsu, to Carrier Corporation. Apparatus for welding impeller. 4,296,308, Cl. 219-136.000.
Nakai, Masaaki: See—
Sahara, Masayoshi; and Nakai, Masaaki, 4,295,724, Cl. 354-238.000.
Nakai, Shinzo; and Shimizu, Chitomi, to Hiraoka & Co., Ltd. Apparatus for continuously coating a sheet material concurrently with a plurality of stripes. 4,295,440, Cl. 118-412.000.
Nakai, Taiichiro; Furusawa, Kahei; and Ejiri, Yoshihiro, to Kokusai Denzetsu Denwa Kabushiki Kaisha. Feed through for optical submerged repeater. 4,295,707, Cl. 350-96.200.
Nakai, Yoshio: See—
Kamada, Kazumasa; Nakai, Yoshio; and Abe, Kazunori, 4,296,214, Cl. 525-2.000.
Nakamura, Hiroya, to Konishiroku Photo Industry Co., Ltd. Device for adjusting image density in composite information recording apparatus. 4,296,423, Cl. 346-160.000.
Nakamura, Kenichi: See—
Shibatani, Juichi; Nakamura, Kenichi; Izuhara, Wataru; and Obu, Yuichiro, 4,295,549, Cl. 188-218.00A.
Nakanishi, Toshiharu; Suzuki, Miyo; and Ohigashi, Hiroji, to Toray Industries, Inc. Ultrasonic transducer. 4,296,349, Cl. 310-335.000.
Nakano, Takuo: See—
Matsubara, Akira; Sakai, Hideaki; Odate, Makoto; Suganuma, Toshio; and Nakano, Takuo, 4,296,112, Cl. 424-246.000.
Nakao, Kouzo: See—
Teramura, Hiroichi; Yamazaki, Yasuhiro; Wakahara, Yasushi; Hattori, Naohiko; Yamamoto, Seiichi; and Nakao, Kouzo, 4,296,439, Cl. 328-257.000.
Nakayama, Katsuchi: See—
Itoh, Koichi; Koshida, Osamu; and Nakayama, Katsuchi, 4,295,354, Cl. 72-225.000.
Nakayama, Koichi: See—
Sakano, Hajime; Kodama, Mikio; Nakayama, Koichi; Yoshida, Isao; and Inoue, Atsunori, 4,296,216, Cl. 525-66.000.
Nakayama, Yasuaki, to Citizen Watch Company Limited. Watch movement construction. 4,296,488, Cl. 368-80.000.
Nakayama, Yoshihiko: See—
Tachibana, Keiji; Nakayama, Yoshihiko; Kaneko, Junichi; and Ishii, Susumu, 4,295,792, Cl. 417-15.000.
Nakazima, Kooichi; Kazama, Keizo; and Oki, Hiroshi, to Hitachi, Ltd. Banded-type implosion protection cathode ray tubes. 4,295,574, Cl. 220-2.10A.
Nalco Chemical Company: See—
Aitken, Thomas; Kowalski, David J.; and Srinivasan, K. G., 4,295,930, Cl. 162-158.000.
Breslin, Michael D., 4,295,928, Cl. 162-73.000.
Slovinsky, Manuel, 4,295,762, Cl. 405-264.000.
Nalco Chemical Company: See—
Pocius, Frances C., 4,295,932, Cl. 162-161.000.
Narozny, Ronald S.; and Wyss, Robert P., to Thomas & Betts Corporation. Side probeable connector using flat cable. 4,295,704, Cl. 339-99.00R.
Nasman, John O.; and Hogfeldt, Carl-Erik. Method of sterilizing material, especially bandage and surgical instruments, in an autoclave operating with vacuum and steam. 4,296,067, Cl. 422-26.000.
National Can Corporation: See—
Sauer, Donald G., 4,295,811, Cl. 425-112.000.
National Institute for Metallurgy: See—
Stewart, Alistair B.; and Barker, Ian J., 4,296,269, Cl. 13-12.000.
National Semiconductor Corporation: See—
Burns, Carmen D., 4,295,912, Cl. 156-324.000.
Penn, Eric J.; and Teegarden, Derylle L., 4,295,258, Cl. 29-283.000.
Natzke, Ronald C.; and Brown, Thomas R., to J. I. Case Company. Backhoe bucket quick coupler. 4,295,287, Cl. 37-103.000.
Nazarian, Miron M.; Efimov, Vyacheslav T.; Axenko, Alexandr A.; Kolyada, Vladimir A.; and Shamsha, Ljudmila F. Method and apparatus for electrochemical purification of contaminated liquids. 4,295,946, Cl. 204-149.000.
Neal, Warren D.; and Nicodemus, Robert N., Jr., to Acco Industries Inc. Conveyor system with diverter. 4,295,559, Cl. 198-598.000.
Nedelec, Lucien; Frechet, Daniel; and Dumont, Claude, to Roussel Uclaf. 3-Aryloxy-3-aryl-propaneamines and their method of use. 4,296,126, Cl. 424-316.000.
Nederlof, Leendert; and Salters, Roelof H. W., to U.S. Philips Corporation. Word-organized, content-addressable memory. 4,296,475, Cl. 364-900.000.

Nehra, Samuel A. Plating method and structure. 4,296,181, Cl. 428-626.000.
Neill, Daniel L.: See—
Becker, James; and Neill, Daniel L., 4,295,687, Cl. 303-20.000.
Nelle, Gunther; and Swassek, Gunter, to Dr. Johannes Heidenhain GmbH. Longitudinal measuring device. 4,295,742, Cl. 356-373.000.
Nelson, Alfred R.; and Johnsen, Kenneth E., to Dow Chemical Co., The. Solvent blends for ethylene copolymers. 4,296,019, Cl. 260-33.40R.
Nelson, David M., to United States Gypsum Company. Steel clad wood door frame. 4,295,299, Cl. 49-504.000.
Nelson, Gary L.; and Harvey, William A., to Sperry Corporation. Magneto-optic Bi₁Lu₂Fe₅O₁₂ crystals. 4,295,988, Cl. 252-584.000.
Nelson, Melvin A.: See—
Franks, Larry A.; and Nelson, Melvin A., 4,296,319, Cl. 250-227.000.
Neubauer, Douglas G.: See—
Mayer, Steven T.; Miner, Jay G.; Neubauer, Douglas G.; and Decuir, Joseph C., 4,296,476, Cl. 364-900.000.
Neubauer, Michael L., to Varian Associates, Inc. Traveling wave tube with frequency variable sever length. 4,296,354, Cl. 315-3.500.
Neuenschwander, Rudolf: See—
Kaiser, Paul H.; Neuenschwander, Rudolf; and Norton, Henry J., 4,296,161, Cl. 428-171.000.
Neuhoff, Donald; Mones, Arthur H.; and Lam, Man K., to Honeywell Information Systems Inc. Method of soldering a lead to a sintered lead pad. 4,295,271, Cl. 29-840.000.
Neumann, Konrad; Schenkenberger, Ernst; and Resch, Friedrich, to Ciba-Geigy Corporation. Process for the production of negligibly dusty preparation. 4,295,851, Cl. 8-524.000.
Neuringer, Jules K., to Portronix Communications Inc. Location transmitting system. 4,296,408, Cl. 340-539.000.
Neyrpic: See—
Boussuges, Pierre, 4,295,782, Cl. 415-1.000.
NGK Insulators, Ltd.: See—
Ishihara, Takeshi; Goto, Daisaku; and Sugiura, Hitoshi, 4,296,276, Cl. 174-179.000.
Matsuhisa, Tadaaki; Soejima, Shigeo; and Yamamoto, Noboru, 4,295,892, Cl. 501-120.000.
Nibby, Chester M., Jr.; and Panepinto, William, Jr., to Honeywell Information Systems Inc. Rotating chip selection technique and apparatus. 4,296,467, Cl. 364-200.000.
Nichols, Steven J.: See—
Mallory, Henry R.; and Nichols, Steven J., 4,296,461, Cl. 363-22.000.
Nicholson, Robert D.; and Daniel, Alger T., to Koehring Company. Laminated jet pipe receiver plug assembly method and structure. 4,295,594, Cl. 228-160.000.
Nicholson, William H., to Blodgett, Norman S. Wedge. 4,295,506, Cl. 144-193.00D.
Nicodemus, Robert N., Jr.: See—
Neal, Warren D.; and Nicodemus, Robert N., Jr., 4,295,559, Cl. 198-598.000.
Nicolas, Francois: See—
Maurel, Pierre; Nicolas, Francois; and Bosca, Bernard, 4,296,073, Cl. 423-3.000.
Niederer, Kurt W., to Terrell Machine Company, The. Apparatus for sorting textile bobbins. 4,295,569, Cl. 209-634.000.
Niedzialkowski, John: See—
Sokoly, Theodore O.; and Niedzialkowski, John, 4,296,002, Cl. 252-518.000.
Niemeyer, Lutz: See—
Lang, Ernst; and Niemeyer, Lutz, 4,296,285, Cl. 200-61.080.
Nifco, Inc.: See—
Morota, Kazutoshi; and Yuda, Takuo, 4,295,618, Cl. 248-73.000.
Nihon Automatic Machinery Mfg. Co., Ltd.: See—
Kamei, Takeji, 4,295,972, Cl. 210-710.000.
Nippon Electric Co., Ltd.: See—
Hirayama, Tsutomu; and Hada, Hiroshi, 4,296,357, Cl. 315-169.400.
Murotani, Tatsunori, 4,296,339, Cl. 307-450.000.
Nippon Kokan Kabushiki Kaisha: See—
Nomura, Hirokazu; and Fujioka, Tadashi, 4,296,306, Cl. 219-124.340.
Nippon Soken, Inc.: See—
Nomura, Etsuji; Matsui, Kazuma; Miyazaki, Toshikuni; Sami, Hiroshi; and Ueda, Tatehito, 4,295,456, Cl. 123-569.000.
Nippon Steel Corporation: See—
Arima, Ryoji; Umezawa, Kazushige; and Nisugi, Tokuzo, 4,295,882, Cl. 75-52.000.
Higuchi, Seizun; Tano, Kazuhiro; Kamada, Minoru; and Okamoto, Susumu, 4,296,145, Cl. 427-47.000.
Nirasawa, Mitsuharu: See—
Kawaziri, Kazuhiro; Fujiwara, Masato; Hatanaka, Isamu; Tabei, Masatoshi; Higashi, Akio; and Nirasawa, Mitsuharu, 4,296,422, Cl. 346-160.000.
Nishida, Katsutoshi: See—
Ishii, Takashi; Nishida, Katsutoshi; Komatsu, Michiyasu; and Tsuge, Akihiko, 4,296,065, Cl. 264-325.000.
Nishikawa, Akio: See—
Takahashi, Akio; Itoh, Yutaka; Wajima, Motoyo; Morishita, Hirosada; and Nishikawa, Akio, 4,296,219, Cl. 525-488.000.
Nishikawa, Masaji: See—
Tsuda, Hiroshi; Miyashita, Kiyoshi; Nishikawa, Masaji; Shimizu, Akira; and Kasuga, Muneco, 4,295,734, Cl. 355-15.000.
Nishikubo, Yasuhiko, to Citizen Watch Co. Ltd. Crystal oscillation-type electronic timepiece. 4,296,490, Cl. 368-87.000.

Nishimoto, Kanichi, to Noritsu Koki Co., Ltd. Conveying system with snake motion prevention members incorporated therein for photo treatment apparatus of long length photo-sensitive sheet materials. 4,295,728, Cl. 354-321.000.
Nishizawa, Jun-ichi, to Handotai Kenkyu Shinkokai. Luminescent diode having multiple hetero junctions. 4,296,425, Cl. 357-17.000.
Nishizawa, Toshio: See—
Tanaka, Naoki; Tsuchiya, Kunihiko; and Nishizawa, Toshio, 4,295,806, Cl. 418-97.000.
Niskin, Shale J. Cover for port light. 4,295,675, Cl. 292-256.600.
Nissan Motor Co., Ltd.: See—
Morota, Kazutoshi; and Yuda, Takuo, 4,295,618, Cl. 248-73.000.
Naitoh, Katsumi, 4,295,684, Cl. 297-475.000.
Nissan Motor Co. Ltd.: See—
Yasuhashi, Seishi; Teranuma, Jun; Shinzawa, Motohiro; and Fujii, Hiroshi, 4,295,455, Cl. 123-569.000.
Nissin Flour Milling Co., Ltd.: See—
Tanaka, Kenji; and Endo, Shigeru, 4,296,133, Cl. 426-23.000.
Nissin Kogyo Kabushiki Kaisha: See—
Hachiro, Nobuaki, 4,295,412, Cl. 91-468.000.
Nisugi, Tokuzo: See—
Arima, Ryoji; Umezawa, Kazushige; and Nisugi, Tokuzo, 4,295,882, Cl. 75-52.000.
Noble, Allen T. Land irrigating system and method. 4,295,607, Cl. 239-1.000.
Noma, Tutomu: See—
Saito, Tasuku; Noma, Tutomu; Matsunaga, Tsutomu; Naito, Nagayoshi; Tanaka, Chiaki; and Hiratsuka, Motoki, 4,295,652, Cl. 273-235.00R.
Nordine, Michel; and Chelu, Gerard, to Charbonnages de France. Process for purifying gaseous effluents. 4,296,081, Cl. 423-245.000.
Nomura, Etsuji; Matsui, Kazuma; Miyazaki, Toshikuni; Sami, Hiroshi; and Ueda, Tatehito, to Nippon Soken, Inc.; and Toyota Jidosha Kogyo Kabushiki Kaisha. Exhaust-gas-recirculation system for use in diesel engines. 4,295,456, Cl. 123-569.000.
Nomura, Hirokazu; and Fujioka, Tadashi, to Nippon Kokan Kabushiki Kaisha. Method of welding corrugated metallic materials. 4,296,306, Cl. 219-124.340.
Nonn, Konrad; Wolf, Karlheinz; Haus, Artur; and Hornle, Reinhold. Process for the preparation of dyestuff formulations. 4,295,849, Cl. 8-524.000.
Nordson Corporation: See—
Kuipers, Peter, 4,295,322, Cl. 53-450.000.
Terry, Robert R.; and Boone, Jacob J., 4,295,573, Cl. 215-348.000.
Noren, Borje: See—
Hoppe, Udo; Sauermann, Gerhard; Curtis, Julius; Glantz, Per-Olof; Krasse, Bo; Larsson, Kare; Noren, Borje; Odham, Goran; and Olsson, Jan, 4,296,095, Cl. 424-52.000.
Noritsu Koki Co., Ltd.: See—
Nishimoto, Kanichi, 4,295,728, Cl. 354-321.000.
Norris, James P.: See—
Martin, Howard; and Norris, James P., 4,295,827, Cl. 433-81.000.
Norsk Hydro a.s.: See—
Kongshaug, Gunnar, 4,295,895, Cl. 134-22.00R.
Northern Telecom Limited: See—
Osborne, Brian T., 4,295,703, Cl. 339-98.000.
Udayasekaran, Rajasekaran, 4,296,281, Cl. 179-18.0EB.
Norton, Henry J.: See—
Kaiser, Paul H.; Neuenschwander, Rudolf; and Norton, Henry J., 4,296,161, Cl. 428-171.000.
NPI Corporation: See—
Lang-Ree, Nils, 4,295,418, Cl. 99-355.000.
NSK-Warner K.K.: See—
Naitoh, Katsumi, 4,295,684, Cl. 297-475.000.
Nuken GmbH: See—
Brunner, Herbert, 4,295,745, Cl. 366-302.000.
Numata, Saburo, to Fuji Photo Optical Co., Ltd. Mode change-over device for automatic exposure control camera. 4,295,716, Cl. 354-30.000.
Nunner, Hans-Herbert: See—
Weissgerber, Rudolf; Stoll, Alois; Kandler, Herbert; Nunner, Hans-Herbert; Eichelseder, Christine; and Pangner, Helmut, 4,296,017, Cl. 260-30.60R.
NUS Corporation: See—
Mullett, William L., 4,295,401, Cl. 83-864.000.
O'Brien, Joseph P.: See—
Papay, Andrew G.; and O'Brien, Joseph P., 4,295,983, Cl. 252-49.600.
Obu, Yuichiro: See—
Shibatani, Juichi; Nakamura, Kenichi; Izuhara, Wataru; and Obu, Yuichiro, 4,295,549, Cl. 188-218.00A.
Odate, Makoto: See—
Matsubara, Akira; Sakai, Hideaki; Odate, Makoto; Suganuma, Toshio; and Nakano, Takuo, 4,296,112, Cl. 424-246.000.
Odham, Goran: See—
Hoppe, Udo; Sauermann, Gerhard; Curtis, Julius; Glantz, Per-Olof; Krasse, Bo; Larsson, Kare; Noren, Borje; Odham, Goran; and Olsson, Jan, 4,296,095, Cl. 424-52.000.
Oelbermann, Max; and Rademacher, Karl-August, to Rittershaus & Blecher GmbH. Filter conveying device for filter presses. 4,295,970, Cl. 210-230.000.
Oertli AG Dubendorf: See—
Schilling, Siegfried, 4,295,821, Cl. 431-353.000.
Officine Savio, S.p.A.: See—
Pfeifer, Hermann, 4,295,330, Cl. 57-263.000.

Ogasawara, Fumihiro, to Ricoh Company, Ltd. Photoelectric scanning apparatus. 4,296,441, Cl. 358-293.000.
Ogawa, Tadashi; Ono, Shunichiro; and Shibuya, Kyoichi, to Sumitomo Cement Co., Ltd. Apparatus for continuously producing a cement clinker. 4,295,823, Cl. 432-106.000.
Ogino, Fumiichi, to Takeda Chemical Industries, Ltd. Air filter of polyurethane mesh containing carbon adsorbent. 4,296,166, Cl. 428-283.000.
Ogiwara, Kenzyu; Kawada, Minoru; and Ashida, Teiji, to Hitachi, Ltd.; and Hitachi Service Engineering Co., Ltd. Method for operating fluid machines in spinning-in-air mode. 4,295,781, Cl. 415-1.000.
Ohara, Ichiro, to Hitachi, Ltd. Mounting structure for magnetrons. 4,295,748, Cl. 403-24.000.
Ohashi, Takashi; Okoyama, Toru; and Arai, Katsuhiko, to Bridgestone Tire Company Limited. Fireproof laminates. 4,296,170, Cl. 428-313.000.
Ohigashi, Hiroji: See—
Nakanishi, Toshiharu; Suzuki, Miyo; and Ohigashi, Hiroji, 4,296,349, Cl. 310-335.000.
Ohkubo, Hiroyuki, to Sony Corporation. Magnetic signal field sensor that is substantially immune to angular displacement relative to the signal field. 4,296,377, Cl. 324-252.000.
Ohlinger, Manfred: See—
Steck, Werner; Sarnecki, Wilhelm; Marosi, Laszlo; Ohlinger, Manfred; and Autzen, Horst, 4,295,879, Cl. 75-0.5AA.
Ohloff, Gunther: See—
Fehr, Charles; Ohloff, Gunther; and Buchi, Georges H., 4,296,258, Cl. 568-364.000.
Ohmura, Kaoru: See—
Shibasaki, Ichiro; Ohmura, Kaoru; and Kimura, Takeo, 4,296,424, Cl. 357-1.000.
Ohsaka, Yohnosuke; and Tohzuka, Takashi, to Daikin Kogyo Co., Ltd. Process for preparing hexafluoropropene oligomers. 4,296,265, Cl. 570-138.000.
Ohta, Tokuya: See—
Eida, Tsuyoshi; Haruta, Masahiro; Yano, Yasuhiro; Matsufuji, Yoji; and Ohta, Tokuya, 4,295,889, Cl. 106-22.000.
Ohtani, Eiichi; Kobayashi, Kengo; Isobe, Asao; and Tanaka, Shigeyoshi, to Hitachi Chemical Company, Ltd. Photo-curable coating compositions for building materials. 4,295,947, Cl. 204-159.150.
Ojima, Masahiro: See—
Terao, Motoyasu; Shigematsu, Kazuo; Ojima, Masahiro; and Yonezawa, Seiji, 4,296,419, Cl. 346-135.100.
Okami, Yoshiro: See—
Umezawa, Hamao; Okami, Yoshiro; and Kondo, Shinichi, 4,296,106, Cl. 424-181.000.
Okamoto, Susumu: See—
Higuchi, Seizun; Tano, Kazuhiro; Kamada, Minoru; and Okamoto, Susumu, 4,296,145, Cl. 427-47.000.
Okano, Shuji: See—
Mikami, Takashi; Fujii, Shigeo; Okano, Shuji; and Ikeda, Tokuzo, 4,295,809, Cl. 425-72.005.
Oki, Hiroshi: See—
Nakazima, Kooichi; Kazama, Keizo; and Oki, Hiroshi, 4,295,574, Cl. 220-2.10A.
Okoyama, Toru: See—
Ohashi, Takashi; Okoyama, Toru; and Arai, Katsuhiko, 4,296,170, Cl. 428-313.000.
Oktay, Sevgin: See—
Leaycraft, Edgar C.; Oktay, Sevgin; and Ostergren, Carl D., 4,296,455, Cl. 361-383.000.
Okumichi, Toshiharu; Osoto, Osamu; Matsumoto, Keizo; Thuzimoto, Shigenori; and Sanda, Hisanari, to Arakawa Kagaku Kogyo Kabushiki Kaisha. Sizing compositions incorporating ketene dimer. 4,296,012, Cl. 260-29.6XA.
Okuno, Yoshitoshi: See—
Yamaguchi, Takashi; Okuno, Yoshitoshi; and Hirose, Chuji, 4,295,581, Cl. 222-192.000.
Olekna, David J.: See—
Graham, Henry A., Jr.; Olekna, David J.; Hawk, Johnna B.; and Barrett, Diane M., 4,296,090, Cl. 424-11.000.
Olsson, Jan: See—
Hoppe, Udo; Sauermann, Gerhard; Curtis, Julius; Glantz, Per-Olof; Krasse, Bo; Larsson, Kare; Noren, Borje; Odham, Goran; and Olsson, Jan, 4,296,095, Cl. 424-52.000.
Olympus Optical Co., Ltd.: See—
Fujiwara, Toshihide; and Fujimori, Ryo, 4,295,949, Cl. 204-180.00G.
Kitagawa, Masahiro, 4,295,717, Cl. 354-33.000.
Mizokami, Kazunori, 4,295,718, Cl. 354-50.000.
Mizokami, Kazunori; and Kitagawa, Masahiro, 4,295,720, Cl. 354-51.000.
Tsuda, Hiroshi; Miyashita, Kiyoshi; Nishikawa, Masaji; Shimizu, Akira; and Kasuga, Muneco, 4,295,734, Cl. 355-15.000.
Omura, Satoshi; Tanaka, Haruo; Takahashi, Itaru; Ishii, Shinzo; Mineura, Kazuyuki; Shirahata, Kunikatsu; and Kasai, Masaji, to Kyowa Hakko Kogyo Kabushiki Kaisha; and Kitasato Kenkyusho. Antibiotic nanaomycin E and a process for producing the same. 4,296,040, Cl. 260-345.200.
Omya GmbH: See—
Barthelme, Ulrich, 4,295,803, Cl. 417-423.00R.
Ondetti, Miguel A., to E. R. Squibb & Sons, Inc. Mercaptoacyl derivatives of keto substituted proline and pipercolic acid. 4,296,113, Cl. 424-246.000.

O'Neil, Joseph T.; Quinn, Thomas M.; and Wang, Tse L., to Bell Telephone Laboratories, Incorporated. Incoming call identification arrangement. 4,296,282, Cl. 179-99.0LS.

Ono, Shunichiro: See—
Ogawa, Tadashi; Ono, Shunichiro; and Shibuya, Kyoichi, 4,295,823, Cl. 432-106.000.

Ohashi, Kenichi: See—
Takahashi, Akira; and Ohashi, Kenichi, 4,295,893, Cl. 106-120.000.

Ooki, Norihiro; Motegi, Shoji; Wachi, Yasuyuki; Takikawa, Yoshio; and Yamakawa, Norio, to Hitachi, Ltd.; and Hitachi Chemical Co., Ltd. Brush holding apparatus for rotary electric machine. 4,296,346, Cl. 310-242.000.

Osaka, Shigenori; and Murakoshi, Makoto, to Fuji Photo Film Co., Ltd. Device for feeding web with temperature compensating means. 4,295,589, Cl. 226-122.000.

Oppen, Dieter, to Hooker Chemicals & Plastics Corp. Process for coating iron and steel. 4,295,899, Cl. 148-6.160.

Orcon Corporation: See—
Bascom, Hollis H.; Matweyou, Stephen; Andersen, Alan J.; and Greci, John J., 4,295,905, Cl. 156-174.000.

Oronzio de Nora Impianti Elettrochimici S.p.A.: See—
de Nora, Oronzio; Giuffrè, Luigi; and Modica, Giovanni, 4,295,952, Cl. 204-252.000.

Orpen, Kenneth S. E. Pressure frame with bowed side members. 4,295,568, Cl. 206-597.000.

Ortho Diagnostics, Inc.: See—
Graham, Henry A., Jr.; Olekna, David J.; Hawk, Johnna B.; and Barrett, Diane M., 4,296,090, Cl. 424-11.000.

Ortho Pharmaceutical Corporation: See—
Kane, Vinayak V., 4,296,035, Cl. 260-333.000.

Osborne, Brian T., to Northern Telecom Limited. Connector block. 4,295,703, Cl. 339-98.000.

Oseto, Osamu: See—
Okumichi, Toshiharu; Oseto, Osamu; Matsumoto, Keizo; Thuzimoto, Shigenori; and Sanda, Hisanari, 4,296,012, Cl. 260-29.6XA.

Ostergren, Carl D.: See—
Leaycraft, Edgar C.; Oktay, Sevgin; and Ostergren, Carl D., 4,296,455, Cl. 361-383.000.

Oswell, Herman R., to United States of America, Army. Selectable drag brakes for rocket range control. 4,295,617, Cl. 244-3.290.

Otomaru, Tadao, to Mitsubishi Jukogyo Kabushiki Kaisha. Rotary die cutter. 4,295,843, Cl. 493-354.000.

Ottenberg, Lawrence E.: See—
Harrold, Ronald T.; and Ottenberg, Lawrence E., 4,296,003, Cl. 252-570.000.

Ottersbach, Thomas V.: See—
Hildebrandt, Eugene F.; and Ottersbach, Thomas V., 4,296,366, Cl. 318-793.000.

Outboard Marine Corporation: See—
Blake, Charles H.; and Wood, Donald H., 4,296,363, Cl. 318-349.000.

Borst, Gaylord M., 4,295,833, Cl. 440-63.000.

Owens-Corning Fiberglass Corporation: See—
Bemis, Richard S.; and McCartan, Daniel A., 4,296,164, Cl. 428-219.000.

Grime, Paul R., 4,295,697, Cl. 339-22.00R.

Kerle, Edward J.; and Beaver, Terry R., 4,296,009, Cl. 260-28.50R.

Shannon, Richard F., 4,296,169, Cl. 428-298.000.

Owens-Illinois, Inc.: See—
Amberg, Christopher P., 4,295,580, Cl. 221-268.000.

Buckingham, James W., 4,296,061, Cl. 264-138.000.

Willingham, Wendell D., 4,295,320, Cl. 53-201.000.

Oximetrix, Inc.: See—
Shaw, Robert F.; and Sperinde, John, 4,295,470, Cl. 128-634.000.

Pacciarini, Antonio: See—
Manini, Silvio; and Pacciarini, Antonio, 4,295,774, Cl. 414-331.000.

Packer, Bernard A. Energy convertor. 4,295,800, Cl. 417-333.000.

Pai, Panemangalore S.: See—
Petersen, Harro; Pai, Panemangalore S.; Klippel, Friedrich; and Reinert, Friedrich, 4,295,846, Cl. 8-186.000.

Petersen, Harro; Pai, Panemangalore S.; and Reichert, Manfred, 4,295,847, Cl. 8-189.000.

Paice, Derek A.; and Shimp, Alan B., to United States of America, Interior. Discriminating circuit breaker protection system direct current power distribution systems. 4,296,450, Cl. 361-50.000.

Pako Corporation: See—
Kaufmann, Kenneth M., 4,295,729, Cl. 354-324.000.

Pallo, John M.: See—
LaPrade, Steve A.; and Pallo, John M., 4,295,669, Cl. 285-47.000.

Palma, Gary E.; and Mottier, Francois M., to United Technologies Corporation. Two-wavelength phase control system. 4,295,741, Cl. 356-349.000.

Pander, Hans J.: See—
Eicken, Karl; Rohr, Wolfgang; Pander, Hans J.; and Wuerzer, Bruno, 4,295,875, Cl. 71-88.000.

Panepinto, William, Jr.: See—
Nibby, Chester M., Jr.; and Panepinto, William, Jr., 4,296,467, Cl. 364-200.000.

Pangeri, Helmut: See—
Weissgerber, Rudolf; Stoll, Alois; Kandler, Herbert; Nunner, Hans-Herbert; Eichelseder, Christine; and Pangeri, Helmut, 4,296,017, Cl. 260-30.60R.

Papay, Andrew G.; and O'Brien, Joseph P., to Ethyl Corporation. Lubricating oil composition containing boronated N-hydroxymethyl succinimide friction reducers. 4,295,983, Cl. 252-49.600.

Parent, Daniel, to Plastiques Modernes Ltee. Contractable closure member. 4,295,578, Cl. 220-234.000.

Parks, Lawrence R., to Procter & Gamble Company. The Cross-linked sodium polyacrylate absorbent. 4,295,987, Cl. 252-194.000.

Parlman, Robert M.; and Williams, Ralph P., to Phillips Petroleum Company. Recovering copper by flotation using N-mercaptoalkyl amide depressant. 4,295,962, Cl. 209-167.000.

Parno Corporation: See—
Beck, Richard A.; and Presley, Glen T., 4,295,539, Cl. 180-243.000.

Parro, James. Heat exchange method using natural flow of heat exchange medium. 4,295,342, Cl. 62-119.000.

Pascal, Robert A. Molded heavy duty wheel. 4,295,256, Cl. 29-159.010.

Pasker, John W., to Pasker, John W. Music teaching apparatus and method. 4,295,408, Cl. 84-484.000.

Patenaude, Raymond A.; Duke, Steven R.; and Proulx, Edward A., to General Electric Company. Gun bolt locking system. 4,295,410, Cl. 89-12.000.

Paul, Edward L.: See—
Grabner, Roy; and Paul, Edward L., 4,296,204, Cl. 435-235.000.

Pauling, Horst: See—
Guex, Woldemar; Klauui, Heinrich; Pauling, Horst; and Voirol, Felix, 4,295,517, Cl. 165-1.000.

Paule, Denis R.; and Zamek, Otto S., to General Electric Company. Hot-melt polyesterimide-polyisocyanate electrical coating compositions. 4,296,229, Cl. 528-45.000.

Pavan, Charles: See—
Joly, Robert; Pavan, Charles; and Carle, Pierre R., 4,296,091, Cl. 424-18.000.

Payne, Alan; and Bunning, Robin G. Portable inverter for transferring bulk goods between pallets. 4,295,776, Cl. 414-405.000.

Payne, John M. Electrostatic cameras. 4,295,714, Cl. 354-3.000.

Payne, Peter R., administrator: See—
Mindt, Lothar F. O., deceased; Payne, Peter R., administrator; and Sanderson, George R., 4,296,234, Cl. 536-47.000.

Peachee, C. Theodore: See—
Punshon, William D.; and Peachee, C. Theodore, 4,295,268, Cl. 29-596.000.

Pearson, Billy J., to Sperry Corporation. Pressure sensitive switch structure. 4,296,406, Cl. 340-166.00R.

Pearson, Joe T.: See—
Killmeyer, Charles W., deceased; Killmeyer, Elizabeth A., administrator; Lane, James E.; Taylor, Leslie L., Jr.; and Pearson, Joe T., 4,296,060, Cl. 264-137.000.

Peck, Wallace C. Corked bottle opener. 4,295,392, Cl. 81-3.320.

Pedain, Josef; Uerdlingen, Walter; and Muller, Hans-Jurgen, to Bayer Aktiengesellschaft. Polyurethane coatings produced from (1) a polyisocyanate mixture of polyisocyanates from the diphenol methane series and a polyhydroxy polyether containing at least one tertiary amine nitrogen with (2) a polyol in a two component coating system. 4,296,230, Cl. 528-67.000.

Pelikan A.G.: See—
Mecke, Norbert; Schmitt, Franz U.; Schrader, Karl-Heinz; and Blutschkau, Heinke, 4,296,150, Cl. 427-164.000.

Pellerin, Albert. Device for increasing the uniformity of the air-fuel mixture in internal combustion engines. 4,295,458, Cl. 123-590.000.

Pelton, Frank M.; Miller, Clyde A.; and Leney, Thomas F., to Calspan Corporation. Method and apparatus for reducing the effects of scintillation and rejection of clutter in monopulse radars. 4,296,415, Cl. 343-16.00M.

Pemco-Kalamazoo, Inc.: See—
Black, John W., 4,295,686, Cl. 301-63.0DD.

Penn, Eric J.; and Teegarden, Derylle L., to National Semiconductor Corporation. Pin puller and inserter. 4,295,258, Cl. 29-283.000.

Penn, Thomas C., to Texas Instruments Incorporated. Method for removing resist layer from substrate with combustible gas burnoff. 4,296,146, Cl. 427-58.000.

Peot, David G., to Singer Company, The. Safety lock-on motor control. 4,296,290, Cl. 200-325.000.

Percarpio, Edward P., to Becton, Dickinson and Company. Cannula pierceable self-sealing closure. 4,295,572, Cl. 215-247.000.

Perkin-Elmer Corporation, The: See—
Gerlach, Robert L., 4,296,323, Cl. 250-289.000.

Perlman, Milton, to Monex Corporation. Connector for wooden truss. 4,295,318, Cl. 52-693.000.

Perronin, Jean: See—
Dessaint, Andre L.; and Perronin, Jean, 4,295,976, Cl. 252-8.900.

Peschke, Norman, to Dover Corporation. Vapor control system. 4,295,802, Cl. 417-405.000.

Pestellini, Vittorio: See—
Ghelardoni, Mario; Pestellini, Vittorio; Del Soldato, Piero; Volterra, Giovanna; and Meli, Alberto, 4,296,124, Cl. 424-285.000.

Petersen, Harro; Pai, Panemangalore S.; Klippel, Friedrich; and Reinert, Friedrich, to BASF Aktiengesellschaft. Process for the production of formaldehyde-free finishing agents for cellulosic textiles and the use of such agents. 4,295,846, Cl. 8-186.000.

Petersen, Harro; Pai, Panemangalore S.; and Reichert, Manfred, to BASF Aktiengesellschaft. Finishing process for textiles. 4,295,847, Cl. 8-189.000.

Petersen, Jorgen N., to Aktieselskabet Brodrene Hartmann. Tray blank for eggs. 4,295,597, Cl. 229-2.5EC.

Peterson, Donald J. Platform stepladder. 4,295,544, Cl. 182-106.000.

Petitpierre, Jean C.; and Garner, Robert, to Ciba-Geigy Corporation. 3-Indolyl-3-bis-amino-phenyl-phthalide compounds. 4,295,663, Cl. 282-27.500.

Petrillo, Edward W., Jr.; and Weisenborn, Frank L., to E. R. Squibb & Sons, Inc. 4-Azido-1-mercaptoacyl proline. 4,296,033, Cl. 260-326.200.

Petrin, Jerome A. Self-dumping hoisting bucket assembly. 4,295,677, Cl. 294-73.000.

Petroleum Designers, Inc.: See—
Pierce, Elwood K., 4,295,665, Cl. 285-3.000.

Petrow, Henry G.; and Weissman, Mark L. Method of removal of chlorine retained by human skin and hair after exposure to chlorinated water, and soap and shampoo compositions adapted to effect said removal. 4,295,985, Cl. 252-105.000.

Pezzot, Adriano. Intermediately cooled air vacuum pump with balancing of the pressures. 4,295,804, Cl. 418-15.000.

Pfannebecker, George W.: See—
Dussourd, Jules L.; and Pfannebecker, George W., 4,295,788, Cl. 415-202.000.

Pfefferle, William C.: See—
Angwin, Meredith J.; Pfefferle, William C.; and Kesselring, John P., 4,295,818, Cl. 431-7.000.

Pfeifer, Hermann, to Officine Savio, S.p.A. Re-attachment device for an open-end type spinning frame. 4,295,330, Cl. 57-263.000.

Pfeiffer, Ronald E.: See—
De Maria, Francesco; and Pfeiffer, Ronald E., 4,296,175, Cl. 428-398.000.

Pfizer Inc.: See—
Kadin, Saul B., 4,296,120, Cl. 424-274.000.

Kadin, Saul B., 4,296,129, Cl. 424-309.000.

Wernau, William C., 4,296,203, Cl. 435-104.000.

Philagro: See—
Thizy, Andre; Poignant, Pierre; and Pillon, Daniel, 4,295,877, Cl. 71-120.000.

Philip Morris Incorporated: See—
Johnson, Harry D.; Campbell, Christopher J.; Turner, Thomas O.; Poole, Carl W.; Gilmore, James E.; and Thomas, James R., 4,295,337, Cl. 62-54.000.

Philipp, Karl-Heinz: See—
Finsterwalder, Kurt; Philipp, Karl-Heinz; Riedisser, Gunter; and Voss, Wilfried, 4,295,399, Cl. 83-251.000.

Phillips Petroleum Company: See—
Boultinghouse, Harold D., 4,296,151, Cl. 427-255.100.

Burns, Lyle D., 4,295,861, Cl. 44-63.000.

Burns, Lyle D., 4,295,862, Cl. 44-72.000.

Clemens, Lawrence G., 4,296,485, Cl. 367-77.000.

Faraglia, Silvio T., 4,295,903, Cl. 156-69.000.

Hawley, Gil R., 4,295,998, Cl. 252-439.000.

Hawley, Gil R., 4,296,001, Cl. 252-458.000.

Lewis, Robert J., 4,296,087, Cl. 423-449.000.

Louthan, Jean H.; Cox, Russell C.; and Crawford, William V., 4,295,668, Cl. 285-21.000.

McDaniel, Max P.; and Welch, Melvin B., 4,295,997, Cl. 252-439.000.

Miller, Terry A., 4,296,484, Cl. 367-71.000.

Parlman, Robert M.; and Williams, Ralph P., 4,295,962, Cl. 209-167.000.

Richards, Frank P.; and Taylor, Raymond C., 4,295,838, Cl. 493-105.000.

Tatham, Jack R.; and Shelor, Jerry L., 4,295,251, Cl. 28-112.000.

Philpott, Arthur; and Fuher, Reginald S., to Ready Pen Limited. Transmission assembly. 4,295,391, Cl. 74-782.000.

Pierce, Elwood K., to Petroleum Designers, Inc. Well casing suspension system. 4,295,665, Cl. 285-3.000.

Pierce, Robert C., to Colgate-Palmolive Company. High viscosity dentifrice. 4,296,096, Cl. 424-52.000.

Pignons S.A.: See—
Durand, Roger, 4,295,725, Cl. 354-244.000.

Pillon, Daniel: See—
Thizy, Andre; Poignant, Pierre; and Pillon, Daniel, 4,295,877, Cl. 71-120.000.

Pine, Lloyd A.: See—
Bearden, Roby, Jr.; Aldridge, Clyde L.; and Pine, Lloyd A., 4,295,996, Cl. 252-431.00C.

Pittmann, Robert W.: See—
Gass, John C.; Kerr, Noel C.; and Pittmann, Robert W., 4,295,795, Cl. 417-111.000.

Pizzolati, Pierluigi: See—
Mezzetti, Sergio; Pizzolati, Pierluigi; and Svelto, Francesco, 4,296,318, Cl. 250-225.000.

Plastiques Modernes Ltee: See—
Parent, Daniel, 4,295,578, Cl. 220-234.000.

Plessey Handel und Investments A.G.: See—
Smith, Leslie; Tew, William; and Woolley, Jack, 4,296,458, Cl. 361-433.000.

Plokhuta, Vyacheslav D.: See—
Zhivotov, Jury G.; Kupchinsky, Igor I.; Plokhuta, Vyacheslav D.; Bezverkhny, Alexandr M.; Nabutovsky, Samoil I., deceased; and Eroshkevskaya, Elena D., administrator, 4,295,387, Cl. 74-573.00F.

Pocius, Frances C., to Nalco Chemical Company. Synergistic blend of biocides. 4,295,932, Cl. 162-161.000.

Podola, Nikolai V.: See—
Lifshits, Viktor S.; Krivonov, Vadim P.; Podola, Nikolai V.; Grabchev, Boris L.; Andrianov, Vladimir R.; and Shakhov, Rifkhat M., 4,296,305, Cl. 219-101.000.

Poignant, Pierre: See—
Thizy, Andre; Poignant, Pierre; and Pillon, Daniel, 4,295,877, Cl. 71-120.000.

Poirier, Marc; Gauthier, Michel; and Belanger, Andre, to Hydro-Quebec. Method and device for detecting a gaseous anhydride in an oxygen bearing gas. 4,295,939, Cl. 204-1.00T.

Pomonik, George M., to Amtel, Inc. Hose arm coupling for underwater fluid swivel. 4,295,237, Cl. 9-8.00P.

Ponder, James E.: See—
Tubbs, Graham S.; and Ponder, James E., 4,295,897, Cl. 148-1.500.

Poole, Carl W.: See—
Johnson, Harry D.; Campbell, Christopher J.; Turner, Thomas O.; Poole, Carl W.; Gilmore, James E.; and Thomas, James R., 4,295,337, Cl. 62-54.000.

Porter, Howard L. Rescue locator signal package. 4,295,438, Cl. 116-210.000.

Portronix Communications Inc.: See—
Neuringer, Jules K., 4,296,408, Cl. 340-539.000.

Pospich, Gunther: See—
Zimmermann, Wolfgang; Schindler, Hermann; and Pospich, Gunther, 4,296,210, Cl. 521-85.000.

Potter, Owen E., to Monash University. Drying solid materials. 4,295,281, Cl. 34-10.000.

Poulson, Larry: See—
Langhammer, Jerome, 4,295,419, Cl. 99-427.000.

PPG Industries, Inc.: See—
Fahey, Dennis M., 4,296,173, Cl. 428-378.000.

Killmeyer, Charles W., deceased; Killmeyer, Elizabeth A., administrator; Lane, James E.; Taylor, Leslie L., Jr.; and Pearson, Joe T., 4,296,060, Cl. 264-137.000.

Stroke, Frederick G., 4,295,890, Cl. 501-90.000.

Prefco Products, Inc.: See—
McCabe, Francis J., 4,295,486, Cl. 137-80.000.

Preh Elektrofeinmechanische Werke Jakob Preh Nachf. GmbH & Co.: See—
Schuberth, Christian; and Hartmann, Rudolf, 4,296,292, Cl. 200-336.000.

Preisler, James M., to Rudd, Thomas H. Motorcycle apparatus. 4,295,964, Cl. 210-130.000.

Presley, Glen T.: See—
Beck, Richard A.; and Presley, Glen T., 4,295,539, Cl. 180-243.000.

Presley, Michael: See—
Albrecht, Robert D.; Presley, Michael; Waller, William E.; Cook, Gerald L.; and Presley, William E., 4,295,708, Cl. 350-289.000.

Presley, Waller & Presley: See—
Albrecht, Robert D.; Presley, Michael; Waller, William E.; Cook, Gerald L.; and Presley, William E., 4,295,708, Cl. 350-289.000.

Presley, William E.: See—
Albrecht, Robert D.; Presley, Michael; Waller, William E.; Cook, Gerald L.; and Presley, William E., 4,295,708, Cl. 350-289.000.

Priesmeyer, Charles H., to Mark Controls Corporation. Control valve. 4,295,602, Cl. 236-93.00B.

Priesnitz, Uwe: See—
Hoffmann, Hellmut; Maurer, Fritz; Priesnitz, Uwe; and Riebel, Hans-Jochem, 4,296,241, Cl. 560-124.000.

Procter & Gamble Company, The: See—
Parks, Lawrence R., 4,295,987, Cl. 252-194.000.

Produits Chimiques Ugine Kuhlmann: See—
Bouvet, Pierre; and Lahu, Jean-Pierre, 4,296,034, Cl. 260-326.820.

Dessaint, Andre L.; and Perronin, Jean, 4,295,976, Cl. 252-8.900.

Proulx, Edward A.: See—
Patenaude, Raymond A.; Duke, Steven R.; and Proulx, Edward A., 4,295,410, Cl. 89-12.000.

Prout, Wesley C., to Hosmer/Dorrance Corporation. Limb engaging band for orthotic device. 4,295,466, Cl. 128-80.00R.

Przedsiębiorstwo Montażu Elektrycznego "Elektrobudowa": See—
Hologa, Zygmunt; Madeyski, Krystyn; and Kurowski, Adam, 4,296,273, Cl. 174-99.00B.

Pullman Incorporated: See—
Knippel, Willis H.; and Ferris, Ray, 4,295,430, Cl. 105-308.00E.

Pundt, Richard A. Window regulator. 4,295,298, Cl. 49-353.000.

Punshon, William D.; and Peachee, C. Theodore, to Emerson Electric Co. Method of assembling an electric motor. 4,295,268, Cl. 29-596.000.

Purr, Horst; Kistler, Manfred; and Muller, Rolf, to Mathias Bauerle GmbH. Electrically operated device, especially duplicating device, with a receptacle to accommodate fluid for the chemical treatment of objects. 4,295,913, Cl. 156-345.000.

Purrer, Josef: See—
Maier, Martin; Purrer, Josef; and Clemens, Ronald, 4,295,323, Cl. 56-10.200.

Purton, Robert M., to Dresser Industries, Inc. Cleanout apparatus for flow control valves. 4,295,487, Cl. 137-242.000.

Pustka, Zdenek; and Krejcir, Oldrich, to Vysoka skola strojni a textilni. Universal pneumatic bellows jack lifter. 4,295,635, Cl. 254-93.0HP.

Quaas, Gary F., to Becton, Dickinson and Company. Blood collection assembly for preventing outward movement of the blood container. 4,295,476, Cl. 128-764.000.

Quiney, Kenneth M., to Girling Limited. Brake actuator. 4,295,548, Cl. 188-72.700.

Quinn, Thomas M.: See—
O'Neil, Joseph T.; Quinn, Thomas M.; and Wang, Tse L., 4,296,282, Cl. 179-99.0LS.

Rabe, Jerry R., to General Electric Company. Multi-speed motor. 4,296,344, Cl. 310-184.000.

Racal Records, Ltd.: See—
Lewis, John A., 4,296,447, Cl. 360-113.000.

Racz, Gabor; and Allen, Forrest, to N.A.D., Inc. Laryngoscope blade. 4,295,465, Cl. 128-11.000.

- Rademacher, Karl-August: See—
Oelbermann, Max; and Rademacher, Karl-August, 4,295,970, Cl. 210-230.000.
- Rader, Charles G.: See—
Bommaraju, Tilak V.; Dexter, Theodore H.; and Rader, Charles G., 4,295,951, Cl. 204-242.000.
- Radjukevich, Leonid V.: See—
Anisimov, Vyacheslav I.; Bulgakov, Evgeny G.; Gurin, Vasily N.; Radjukevich, Leonid V.; Trishevsky, Igor S.; Trishevsky, Oleg I.; Kheifets, Grigory R.; and Jurchenko, Anatoly B., 4,295,353, Cl. 72-180.000.
- Ragheb, A. Kadry: Magnetic switching device for contact-dependent and contactless switching, 4,296,394, Cl. 335-207.000.
- Railcar Maint. Co.: See—
Waterman, Fred W.; McCleery, Jerry E.; and McKie, Robert T., 4,295,427, Cl. 104-32.00R.
- Ramos, Rey C.: See—
Ziccarelli, Salvatore F.; Ramos, Rey C.; and Brown, Robert M., 4,296,136, Cl. 426-533.000.
- Ramsey Engineering Company: See—
Erb, Tom L.; and Miller, Wendell D., 4,295,378, Cl. 73-861.250.
- Randall, John M.: See—
Camirand, Wayne M.; Randall, John M.; and Hautala, Earl, 4,295,333, Cl. 60-641.600.
- Randin, Jean-Paul, to Ebauches S.A.: Method of preparing a polymeric electrolyte particularly for an electro-optical device, 4,296,016, Cl. 260-29.65Q.
- Rannenber, George C., to United Technologies Corporation: Combined air cycle heat pump and refrigeration system, 4,295,518, Cl. 165-2.000.
- Rasello, Franco: See—
Milana, Emilio; and Rasello, Franco, 4,296,333, Cl. 250-572.000.
- Rassias, John N.: Building blocks, wall structures made therefrom and methods of making the same, 4,295,313, Cl. 52-438.000.
- Rauterkus, Karl J.: See—
Braun, Helmut; Rinno, Helmut; and Rauterkus, Karl J., 4,296,226, Cl. 526-316.000.
- Raven-Donners, Paula A. M.: See—
Jongsma, Cornelis; Frijns, Leon H. B.; and Raven-Donners, Paula A. M., 4,296,245, Cl. 562-494.000.
- Raymond, Duane: See—
Grote, Daniel; Raymond, Duane; and Mosher, Joseph C., 4,295,262, Cl. 29-462.000.
- Raytheon Company: See—
MacMaster, George H.; and Dudley, Kenneth W., 4,296,298, Cl. 219-10.810.
- RCA Corporation: See—
Comizzoli, Robert B.; and Vibronek, Robert D., 4,296,370, Cl. 324-54.000.
- Dodds, Dennis L., 4,296,359, Cl. 315-370.000.
- Hoover, Merle V., 4,296,382, Cl. 330-264.000.
- Hsu, Sheng T., 4,295,266, Cl. 29-571.000.
- Keizer, Eugene O.; and Alphonse, Gerard A., 4,296,371, Cl. 324-61.00R.
- Kiess, Helmut G.; and Binggeli, Bruno K., 4,296,478, Cl. 365-112.000.
- Kuzminski, Henry W., 4,296,189, Cl. 430-5.000.
- Maby, Edward W.; Kawamoto, Hirohisa; and Valembois, Pierre V., 4,296,144, Cl. 427-38.000.
- Schellhorn, Robert L., 4,296,272, Cl. 174-68.500.
- Sirij, Bohdan W., 4,295,621, Cl. 248-183.000.
- Warren, Henry R., 4,296,430, Cl. 358-8.000.
- Zorbalas, George S., 4,296,446, Cl. 360-73.000.
- Ready Pen Limited: See—
Philpott, Arthur; and Fuher, Reginald S., 4,295,391, Cl. 74-782.000.
- Rebikoff, Dimitri: High pressure and high speed optical enclosure system, 4,295,721, Cl. 354-64.000.
- Redland Automation Limited: See—
Duley, Richard K., 4,296,401, Cl. 340-38.00L.
- Reedy, Charles B., to Benedictine Monks Inc.: Stove, 4,295,459, Cl. 126-60.000.
- Reeves, H. Neal; Burnett, Roy E.; Denham, Leslie R.; and Shields, George E., to Seiscom Delta Inc.: Seismic exploration with disposable seismic detectors, 4,295,542, Cl. 181-108.000.
- Regan, Michael D.: Apparatus for producing high purity water, 4,296,328, Cl. 250-436.000.
- Reichert, Manfred: See—
Petersen, Harro; Pai, Panemangalore S.; and Reichert, Manfred, 4,295,847, Cl. 8-189.000.
- Reid, Gilbert R., to Burroughs Corporation: Electronic package for high density integrated circuits, 4,296,456, Cl. 361-403.000.
- Reidt, Werner: See—
Bugdahl, Volker; Morlock, Gerhard; Reidt, Werner; and Kerschner, Emil, 4,296,006, Cl. 260-23.0EP.
- Reimers, George W.: See—
Khalaifalla, Sanaa E.; and Reimers, George W., 4,295,971, Cl. 210-695.000.
- Reindl, Hermann: See—
Ganglbauer, Otto; Wallner, Felix; Scheidl, Helmut; Reindl, Hermann; and Frielinghaus, Rainer, 4,295,375, Cl. 73-582.000.
- Reinert, Friedrich: See—
Petersen, Harro; Pai, Panemangalore S.; Klippel, Friedrich; and Reinert, Friedrich, 4,295,846, Cl. 8-186.000.
- Reinhard Mohn GmbH: See—
Beckert, Alexander; and Knobbe, Karl-Heinz, 4,296,294, Cl. 219-10.410.
- Reissner, Frank: See—
Muhling, Alois; Reissner, Frank; and Schmidt, Helmut, 4,295,380, Cl. 74-3.500.
- Rekant, Uriel: Process for the production of energy from solid hydrocarbon fuels, 4,295,331, Cl. 60-39.020.
- Renth, Ernst-Otto: See—
Koppe, Herbert; Mentrup, Anton; Renth, Ernst-Otto; Schromm, Kurt; Hoefke, Wolfgang; and Muacevic, Gojko, 4,296,117, Cl. 424-273.00B.
- Resch, Friedrich: See—
Neumann, Konrad; Schenkenberger, Ernst; and Resch, Friedrich, 4,295,851, Cl. 8-524.000.
- Revak, Timothy T.: See—
Anand, Joginder N.; Revak, Timothy T.; and Tsang, Floris Y., 4,296,052, Cl. 264-25.000.
- Reynolds and Reynolds Company, The: See—
Kelly, Robert J., 4,295,642, Cl. 270-53.000.
- Rhau, Siegfried; and Weber, Adolf, to Diehl GmbH & Co.: Process for the production of metallic formed members, 4,296,180, Cl. 428-558.000.
- Rheindorf, Hans H.: See—
Aigle, Karl; Hieber, Udo; Huebscher, Wilhelm; Rheindorf, Hans H.; and Wiedemann, Rolf, 4,296,453, Cl. 361-275.000.
- Rhodes, Curtis A.; Jur, Tim A.; and Keating, Donald A., to Canon Corp.: Method of filling spike holes in railway ties, 4,295,259, Cl. 29-402.180.
- Rhum, David, to Celanese Corporation: Stable vinyl acetate and amine monomer copolymer emulsions, 4,296,225, Cl. 526-260.000.
- Rich, Leonard G., to Gulf & Western Corporation: Device for converting analog signals from a natural leaf scanner into digital signals and method of operating same, 4,296,405, Cl. 340-146.3AG.
- Richards, Frank P.; and Taylor, Raymond C., to Phillips Petroleum Company: Method of producing cylindrical containers, 4,295,838, Cl. 493-105.000.
- Richards, John S.: See—
Dabisch, Kenneth W.; and Richards, John S., 4,296,314, Cl. 235-92.0SB.
- Richardson, Warren N., to TRW Inc.: Self-referencing position switch, 4,296,286, Cl. 200-61.540.
- Richie, Ronald A.: Wall mounted speaker system, 4,296,280, Cl. 179-1.00E.
- Richter Gedeon Vegyeszeti Gyar: See—
Takacs, Istvan; Banos, Zoltan; Illes, Janos; Vereczkey, Endre; Rudolf, Peter; and Kerey, Gyorgy, 4,296,072, Cl. 422-254.000.
- Ricketts, James R.: See—
Dambach, Thomas F.; and Ricketts, James R., 4,296,420, Cl. 346-140.00R.
- Ricoh Co., Ltd.: See—
Hasegawa, Haruo; Taniguchi, Hiroyoshi; and Igawa, Takao, 4,296,190, Cl. 430-57.000.
- Imai, Mitsuru, 4,296,171, Cl. 428-323.000.
- Ogasawara, Fumihiko, 4,296,441, Cl. 358-293.000.
- Yamazaki, Hiroshi; and Isayama, Takuro, 4,296,418, Cl. 346-75.000.
- Ridgway, Donald H.: See—
Jenkins, Randall C.; Taylor, Clyde G.; Turner, Robert B.; and Ridgway, Donald H., 4,296,159, Cl. 428-95.000.
- Riebel, Hans-Jochem: See—
Hoffmann, Hellmut; Maurer, Fritz; Priesnitz, Uwe; and Riebel, Hans-Jochem, 4,296,241, Cl. 560-124.000.
- Riedisser, Gunter: See—
Finsterwalder, Kurt; Philipp, Karl-Heinz; Riedisser, Gunter; and Voss, Wilfried, 4,295,399, Cl. 83-251.000.
- Rieke Corporation: See—
Schurr, Robert E., 4,295,583, Cl. 222-478.000.
- Riessberger, Klaus: See—
Theurer, Josef; and Riessberger, Klaus, 4,295,764, Cl. 409-296.000.
- Rilly, Gerard, to Thomson-Brandt: Switched-mode frame-scan control circuit for a videofrequency receiver, 4,296,360, Cl. 315-387.000.
- Rinno, Helmut: See—
Braun, Helmut; Rinno, Helmut; and Rauterkus, Karl J., 4,296,226, Cl. 526-316.000.
- Risse, Heinrich: See—
Lollert, Bernd; and Risse, Heinrich, 4,295,382, Cl. 74-68.000.
- Ritter, Horst, to Dr. C. Otto & Comp. G.m.b.H.: Distributor for washing fluid in a scrubber or stripper, 4,296,049, Cl. 261-111.000.
- Rittershaus & Blecher GmbH: See—
Oelbermann, Max; and Rademacher, Karl-August, 4,295,970, Cl. 210-230.000.
- RJR Archer, Inc.: See—
Yeatts, Roy E., 4,295,478, Cl. 131-336.000.
- Robert Bosch GmbH: See—
Friesse, Karl-Hermann, 4,296,148, Cl. 427-125.000.
- Lembke, Manfred; and Knapp, Heinrich, 4,295,452, Cl. 123-470.000.
- Ruhl, Karl; and Kemmner, Ulrich, 4,295,797, Cl. 417-203.000.
- Schlagmuller, Walter; and Babitzka, Rudolf, 4,295,554, Cl. 192-105.0CE.
- Sochor, Josef, 4,296,444, Cl. 360-65.000.
- Roberts, Geoffrey M.: See—
Tomov, Nenad R.; and Roberts, Geoffrey M., 4,295,943, Cl. 204-96.000.
- Robertson, Forrest E.: See—
Williams, Donald E.; Robertson, Forrest E.; Gigot, C. Dean; and Gigot, Terry K., 4,295,532, Cl. 172-184.000.

- Robertson, Wayne M.; and Wert, John A., to Rockwell International Corporation: Method of imparting a fine grain structure to aluminum alloys having precipitating constituents, 4,295,901, Cl. 148-12.70A.
- Robin, Marcel: Liquid-metal-cooled nuclear reactor, 4,295,934, Cl. 376-203.000.
- Robinar Manufacturing Corporation: See—
Cain, Robert L., 4,295,794, Cl. 417-62.000.
- Robinson, B. Joel: Catalyst delivery system, 4,295,816, Cl. 431-4.000.
- Robinson, Bruce A.; and Thompson, John R., to Du Pont de Nemours, E. I., and Company: Method for measuring yarn shrinkage and crimp development, 4,295,252, Cl. 28-248.000.
- Robinson, Douglas K.: Electrical apparatus for comparing dark and light areas on a substrate and which substrate is in a liquid, 4,295,727, Cl. 354-298.000.
- Robinson Industries, Inc.: See—
Gutzwiller, Howard L., 4,295,789, Cl. 416-213.00A.
- Rockwell International Corporation: See—
Dabisch, Kenneth W.; and Richards, John S., 4,296,314, Cl. 235-92.0SB.
- Haraszti, Tegzi P., 4,296,428, Cl. 357-41.000.
- Heinz, Theodore A., 4,295,710, Cl. 350-310.000.
- Robertson, Wayne M.; and Wert, John A., 4,295,901, Cl. 148-12.70A.
- Sarkis, Barkhoudarian, 4,296,472, Cl. 364-509.000.
- Vasile, Carmine F., 4,296,486, Cl. 367-140.000.
- Yosim, Samuel J., 4,296,074, Cl. 423-4.000.
- Rodov, Vladimir: See—
Harrington, Alan L.; Rodov, Vladimir; and Allison, Richard, 4,295,267, Cl. 29-571.000.
- Rodriguez, Edward T., to Theta-Corporation: Optically coupled electric power relay, 4,296,331, Cl. 250-551.000.
- Roeder, George; and Sachs, Helmut, to Messer Griesheim GmbH: Gas blending flame cutter, 4,295,820, Cl. 431-191.000.
- Rogers, Gerald D., to Texas Instruments Incorporated: Method of making integrated circuit MOS capacitor using implanted region to change threshold, 4,295,264, Cl. 29-571.000.
- Rogier, Edgar R., to Henkel Corporation: Polycyclic polyamines, 4,296,004, Cl. 260-18.0EP.
- Rohr, Wolfgang: See—
Eicken, Karl; Rohr, Wolfgang; Pander, Hans J.; and Wuerzer, Bruno, 4,295,875, Cl. 71-88.000.
- Rollmann, Louis D., to Mobil Oil Corporation: Zeolite synthesis, 4,296,083, Cl. 423-329.000.
- Roman, Alain; Chevreux, Pierre; Wust, Manfred; and Ehretsmann, Jacques, to Battelle Memorial Institute: Photocurable adhesive from acrylic acid, acrylamide, dimethylaminoethyl methacrylate, benzophenone and methyl ethyl ketone, 4,295,948, Cl. 204-159.230.
- Romanelli, Pat; and Romanelli, Robert J.: Electronic remote meter reading apparatus, 4,296,411, Cl. 340-870.020.
- Romanelli, Robert J.: See—
Romanelli, Pat; and Romanelli, Robert J., 4,296,411, Cl. 340-870.020.
- Roper, Ralph E., to General Tire & Rubber Co.: Apparatus for making metal outers and inners, 4,295,357, Cl. 72-344.000.
- Rosemeier, Friedrich; and Killmaier, Horst, to Gambro Dialysatoren GmbH & Co. KG: Connection nipple, 4,295,495, Cl. 138-89.000.
- Rosenberg, Peretz: Method and apparatus for producing and assembling articles of molded plastic parts, 4,295,814, Cl. 425-517.000.
- Rosenheck, Bernard, to Litton Systems, Inc.: Start of message generator for a facsimile system, 4,296,440, Cl. 358-257.000.
- Rosenzweig, Ronald E., to Exxon Research & Engineering Co.: Process for the removal of particulates entrained in a fluid using a magnetically stabilized fluidized bed, 4,296,080, Cl. 423-244.000.
- Rosenwinkel, Donald A.; Meyer, Burton C.; and Disko, Harry, to Marvin Glass & Associates: Toy lawn mower, 4,295,294, Cl. 46-205.000.
- Roster, Theodore J.: See—
Sergev, Sergius S.; and Roster, Theodore J., 4,295,604, Cl. 236-21.00R.
- Roswell, David G.; Spring, David J.; and Hems, Roger, to Wilkinson Sword Limited: Acyclic carboxamides having a physiological cooling effect, 4,296,255, Cl. 564-215.000.
- Rota Cota Pty. Ltd.: See—
Woolcock, Kenneth W., 4,295,241, Cl. 15-230.110.
- Roussel Uclaf: See—
Joly, Robert; Pavan, Charles; and Carle, Pierre R., 4,296,091, Cl. 424-18.000.
- Nedelec, Lucien; Frechet, Daniel; and Dumont, Claude, 4,296,126, Cl. 424-316.000.
- Rowell, David G.; Gascoyne, John M.; and Hems, Roger, to Wilkinson Sword Limited: Cyclic carboxamides having a physiological cooling effect, 4,296,093, Cl. 424-45.000.
- Royer Mowers (Aust.) Pty. Ltd.: See—
Green, Douglas F., 4,295,326, Cl. 56-11.300.
- Rubenthaler, Randall J., to Caterpillar Tractor Co.: Mounting grommet, 4,295,691, Cl. 308-238.000.
- Rudd, Thomas H.: See—
Preisler, James M., 4,295,964, Cl. 210-130.000.
- Rudler, Helmut, to Dentsply Research & Development Corp.: Ejector holder for syringe-type cartridge, 4,295,828, Cl. 433-90.000.
- Rudolf, Peter; Steck, Werner; Jakusch, Helmut; Vaeth, Guenter; and Jaekch, Christof, to BASF Aktiengesellschaft: Manufacture of acicular cobalt-containing magnetic iron oxide, 4,296,149, Cl. 427-130.000.
- Rudolf, Peter: See—
Takacs, Istvan; Banos, Zoltan; Illes, Janos; Vereczkey, Endre; Rudolf, Peter; and Kerey, Gyorgy, 4,296,072, Cl. 422-254.000.
- Rudolph, Paul; and Becker, Paul D., to Metallgesellschaft Aktiengesellschaft: Process of treating pressurized condensate, 4,295,864, Cl. 55-40.000.
- Ruf, Wolfgang: See—
Stemme, Otto; Ruf, Wolfgang; and Wagensooner, Eduard, 4,296,438, Cl. 358-214.000.
- Ruhl, Karl; and Kemmner, Ulrich, to Robert Bosch GmbH: Fuel supply pump, 4,295,797, Cl. 417-203.000.
- Russe Rolf, A.: Process and device for the centering of casings as used for underground drilling, 4,295,527, Cl. 166-315.000.
- Rutten, Jacques P., to Machinefabriek C. Rijkaart B.V.: Method of forming a layer of pre-determined thickness from a feedstock of butter or margarine, 4,296,135, Cl. 426-275.000.
- Rutz, Peter: Hydrostatic bearing for a radial piston machine, 4,295,690, Cl. 308-9.000.
- Rzeszewski, Theodore S., to Matsushita Electric Corporation of America: Color television receiving system with forced chroma transients, 4,296,433, Cl. 358-37.000.
- S.T.I. Strumentazione Industriale S.p.A.: See—
Lattuada, Sergio, 4,295,863, Cl. 55-21.000.
- Sachs, Helmut: See—
Roeder, George; and Sachs, Helmut, 4,295,820, Cl. 431-191.000.
- Sadler, William S.: Emergency radio frequency warning device, 4,296,496, Cl. 455-1.000.
- Sado, Ryoichi, to Shin-Etsu Polymer Co., Ltd.: Interconnectors, 4,295,700, Cl. 339-61.00M.
- Saget, Pierre L.: Apparatus for the centrifugal separation of at least two liquid phases and one sedimentary phase of a mixture, 4,295,600, Cl. 233-7.000.
- Sahara, Masayoshi; and Nakai, Masaaki, to Minolta Camera Kabushiki Kaisha: Electric self-timer device for cameras, 4,295,724, Cl. 354-238.000.
- Saiki, Noritsugu: See—
Emi, Shingo; and Saiki, Noritsugu, 4,296,163, Cl. 428-212.000.
- St. Clair, David J.; and Ewins, Earle E., Jr., to Shell Oil Company: Sealant composition, 4,296,008, Cl. 260-27.0BB.
- Saint-Gobain Industries: See—
Droux, Michel; and Bocquet, Gilbert, 4,295,871, Cl. 65-3.410.
- Saito, Cuyichi; and Teranishi, Katsuya, to Hitachi, Ltd.: Passenger conveyor, 4,295,556, Cl. 198-325.000.
- Saito, Tasuku; Noma, Tutomu; Matsunaga, Tutomu; Naito, Nagayoshi; Tanaka, Chiaki; and Hiratsuka, Motoki, to Bridgestone Tire Co., Ltd.; and Toray Industries, Inc.: Golf ball, 4,295,652, Cl. 273-235.00R.
- Sakaguchi, Tadahiyo; Hino, Masamichi; Tsuji, Setsuo; Hashido, Akiyoshi; and Enomoto, Kazuyoshi, to Kubota Ltd.: Label handling apparatus, 4,295,915, Cl. 156-361.000.
- Sakai, Hideaki: See—
Matsubara, Akira; Sakai, Hideaki; Odate, Makoto; Suganuma, Toshio; and Nakano, Takuo, 4,296,112, Cl. 424-246.000.
- Sakamoto, Hitoshi; and Wakisaka, Yoshiaki, to Sony Corporation: Magnetic head tracking control system, 4,296,443, Cl. 360-10.000.
- Sakano, Hajime; Kodama, Mikio; Nakayama, Koichi; Yoshida, Isao; and Inoue, Atsunori, to Sumitomo Naugatuck Co., Ltd.: Thermoplastic resin composition, 4,296,216, Cl. 525-66.000.
- Salem, Robert J., to General Electric Company: Electronic temperature sensing system for toaster appliances, 4,296,312, Cl. 219-501.000.
- Sallmann, Alfred; and Goschke, Richard, to Ciba-Geigy Corporation: Carboxylic acid hydrazides and processes for their manufacture, 4,296,128, Cl. 424-309.000.
- Salter, Roelof H. W.: See—
Nederlof, Leendert; and Salter, Roelof H. W., 4,296,475, Cl. 364-900.000.
- Sami, Hiroshi: See—
Nomura, Etsuji; Matsui, Kazuma; Miyazaki, Toshikuni; Sami, Hiroshi; and Ueda, Tatehito, 4,295,456, Cl. 123-569.000.
- Sanda, Hisanari: See—
Okumichi, Toshiharu; Oseto, Osamu; Matsumoto, Keizo; Thuzimoto, Shigenori; and Sanda, Hisanari, 4,296,012, Cl. 260-29.6XA.
- Sanders Associates, Inc.: See—
Fuller, Harrison W.; and Stromswold, Chester E., 4,296,389, Cl. 333-160.000.
- Sanderson, George R.: See—
Mindt, Lothar F. O.; deceased; Payne, Peter R., administrator; and Sanderson, George R., 4,296,234, Cl. 536-47.000.
- Sandoz, Inc.: See—
Damon, Robert E., II, 4,296,240, Cl. 556-406.000.
- Sangamo Weston, Inc.: See—
Gurr, George P., 4,296,462, Cl. 363-96.000.
- Sano, Seiji: See—
Kawamura, Toshio; Harashima, Noboru; Ueda, Hideo; and Sano, Seiji, 4,295,654, Cl. 277-92.000.
- Sano, Shochi; and Furukawa, Yoshimi, to Honda Giken Kogyo Kabushiki Kaisha: Steering apparatus for vehicles, 4,295,657, Cl. 280-91.000.
- Sansbury, Jerry F., to Sonoco Products Company: Method of constructing composite containers, 4,295,840, Cl. 493-278.000.
- Santa Barbara Research Center: See—
Kern, Mark T.; and Cinzori, Robert J., 4,296,324, Cl. 250-339.000.
- Sarkis, Barkhoudarian, to Rockwell International Corporation: Non-intrusive fluid measuring system, 4,296,472, Cl. 364-509.000.
- Sarnecki, Wilhelm: See—
Steck, Werner; Sarnecki, Wilhelm; Marosi, Laszlo; Ohlinger, Manfred; and Autzen, Horst, 4,295,879, Cl. 75-0.5AA.

LIST OF PATENTEES

Sasaki, Hiroharu: See—
Hayashi, Masaki; Sasaki, Hiroharu; and Tsuneta, Kazuyoshi, 4,296,014, Cl. 260-29.6NR.

Sasaki, Koichi; Sumida, Yasuji; and Ishida, Hiroshi, to Mita Industrial Company Limited. Electrostatic copying apparatus. 4,295,731, Cl. 355-14.00R.

Sasaki, Masao: See—
Hatta, Masami; Iwata, Katsumi; and Sasaki, Masao, 4,295,444, Cl. 118-668.000.

Sasaki, Mitsuru: See—
Mori, Kenji; and Sasaki, Mitsuru, 4,296,036, Cl. 260-340.700.

Sasaki, Susumu; Kito, Kyoji; and Koide, Akio, to Meito Sangyo Kabushiki Kaisha; and Susumu Sasaki. Method for separating fibrinogen and its constituent components. 4,295,855, Cl. 23-230.00B.

Satake Engineering Co., Ltd.: See—
Satake, Toshihiko; Kono, Akira; Horie, Takashi; and Mitoma, Yasuharu, 4,295,542, Cl. 99-486.000.

Satake, Toshihiko; Kono, Akira; Horie, Takashi; and Mitoma, Yasuharu, to Satake Engineering Co., Ltd. Automatic control system for hulling machine. 4,295,420, Cl. 99-486.000.

Satcher, Angel T. Method and structure for recycling soap chips. 4,296,064, Cl. 264-322.000.

Sato, Kazuo, to Daicel Ltd. Process for producing sorbic acid or its derivatives. 4,296,243, Cl. 560-210.000.

Sato, Masataro. Compositions and methods for the treatment of athlete's foot. 4,296,098, Cl. 424-94.000.

Sato, Ryuichi: See—
Ishikawa, Akira; Ishida, Yukihito; Ikegami, Shiro; Satoh, Hiroshi; Sato, Ryuichi; Tomisawa, Setsuo; and Toyoshima, Shigeru, 4,296,123, Cl. 424-287.000.

Sato, Yashushi: See—
Hara, Toshitami; Sato, Yashushi; Takatori, Yasushi; and Shirato, Yoshiaki, 4,296,421, Cl. 346-140.00R.

Sato, Yukihoro: See—
Tanaka, Hironari; Matsuyama, Shigeru; Ishibashi, Tadashi; Kinugawa, Kiyoshige; and Sato, Yukihoro, 4,295,711, Cl. 350-334.000.

Satoh, Hiroshi: See—
Ishikawa, Akira; Ishida, Yukihito; Ikegami, Shiro; Satoh, Hiroshi; Sato, Ryuichi; Tomisawa, Setsuo; and Toyoshima, Shigeru, 4,296,123, Cl. 424-287.000.

Satoh, Takao; and Seita, Toru, to Toyo Soda Manufacturing Co., Ltd. Electrolysis of aqueous solution of alkali metal chloride. 4,295,944, Cl. 204-98.000.

Sauer, Donald G., to National Can Corporation. Apparatus for making multilayered containers. 4,295,811, Cl. 425-112.000.

Sauer, Hans; Steinbichler, Wolf; and Antonitsch, Sepp. Contact spring arrangement for an electromagnetic relay. 4,296,393, Cl. 335-125.000.

Sauer, Paul J.: See—
Hanzel, Robert S.; and Sauer, Paul J., 4,296,174, Cl. 428-389.000.

Sauerland, Heinz: See—
Desprez, Alfred; Sauerland, Heinz; and Teetz, Wolfgang, 4,295,433, Cl. 112-241.000.

Sauermann, Gerhard: See—
Hoppe, Udo; Sauermann, Gerhard; Curts, Julius; Glantz, Per-Olof; Krasse, Bo; Larsson, Kare; Noren, Borje; Odham, Goran; and Olsson, Jan, 4,296,095, Cl. 424-52.000.

Saville, James, to Texasgulf Inc. Process for extraction of platinum group metals from chromite-bearing ore. 4,295,881, Cl. 75-10.00R.

Sawa, Hiroshi, to Hochiki Corporation. Temperature detecting device. 4,295,371, Cl. 73-359.00A.

Sawada, Hidekazu: See—
Suzuki, Takashi; Sawada, Hidekazu; and Katamoto, Kazuyoshi, 4,296,107, Cl. 424-180.000.

Sayo, Kosaku; Suginuma, Atsushi; Tatsumi, Hideo; and Kanamaru, Hisanobu, to Hitachi, Ltd. Electromagnetic clutch. 4,295,553, Cl. 192-84.00C.

Schaefer, Hans G.; and Langer, Alfred, to Manhattan R. F. Die Company. Method and apparatus for heat sealing a plurality of sets of continuous plastic strips together by radio frequency energy. 4,295,908, Cl. 156-251.000.

Schafer, August W., to Wilhelm Schafer Maschinenbau. Apparatus for joining and cladding pipe sections. 4,295,592, Cl. 228-17.000.

Scharff, Dieter: See—
Haage, Karl; and Scharff, Dieter, 4,295,911, Cl. 156-315.000.

Schatzmann, Kurt: See—
Forstner, Anton; and Schatzmann, Kurt, 4,295,441, Cl. 118-425.000.

Scheidt, Helmut: See—
Ganglbauer, Otto; Wallner, Felix; Scheidt, Helmut; Reindl, Hermann; and Frielinghaus, Rainer, 4,295,375, Cl. 73-582.000.

Schellhorn, Robert L., to RCA Corporation. Composite substrate. 4,296,272, Cl. 174-68.500.

Schenck, Gunther. Multichamber photoreactor. 4,296,066, Cl. 422-24.000.

Schenkemberger, Ernst: See—
Neumann, Konrad; Schenkemberger, Ernst; and Resch, Friedrich, 4,295,851, Cl. 8-524.000.

Scherer, Gustaaf: See—
Haberli, Roland; Mollet, Hans; and Scherer, Gustaaf, 4,295,850, Cl. 8-524.000.

Scherer, Richard M., to Chambers Corporation. Method of mounting a thermal insulating door gasket. 4,295,261, Cl. 29-451.000.

Schering, Aktiengesellschaft: See—
Laurent, Henry; Espertling, Peter; Kapp, Joachim-Friedrich; and Wiechert, Rudolf, 4,296,109, Cl. 424-241.000.

Schering Corporation: See—
Nagabhushan, Tattanahalli L.; and Cooper, Alan, 4,296,242, Cl. 560-160.000.

Schiffman, Jerome D., deceased: See—
Biela, John A., 4,295,480, Cl. 132-151.000.

Schiller, August: See—
Innertsberger, Ernst; Sommer, Oswin; Bosch, Erhard; Muller, Johann; and Schiller, August, 4,296,228, Cl. 528-33.000.

Schilling, Siegfried, to Oertli AG Dubendorf. Apparatus for burning liquid fuel. 4,295,821, Cl. 431-353.000.

Schindler, Hermann: See—
Zimmermann, Wolfgang; Schindler, Hermann; and Pospich, Gunther, 4,296,210, Cl. 521-85.000.

Schlagmuller, Walter; and Babitzka, Rudolf, to Robert Bosch GmbH. Centrifugal frictional clutch. 4,295,554, Cl. 192-105.0CE.

Schleiermacher, Herbert, to Klockner-Humboldt-Deutz Aktiengesellschaft. Crankcase ventilating device for reciprocating piston internal combustion engine. 4,295,457, Cl. 123-574.000.

Schmid, Michael G.; and Hurt, Roger W. Anti-theft device for liquid storage tanks. 4,295,577, Cl. 220-86.0AT.

Schmid, Rolf: See—
Gutekunst, Ferdinand; and Schmid, Rolf, 4,296,231, Cl. 528-93.000.

Schmidt, Friedrich: See—
Schmidt, Karl-Julius; Schmidt, Friedrich; Siegle, Peter; and Hansen, Gert, 4,296,047, Cl. 260-974.000.

Schmidt, Hans-Joachim: See—
Wunder, Friedrich; Leupold, Ernst I.; Hachenberg, Horst; and Schmidt, Hans-Joachim, 4,296,266, Cl. 585-640.000.

Schmidt, Helmut: See—
Muhling, Alois; Reissner, Frank; and Schmidt, Helmut, 4,295,380, Cl. 74-3.000.

Schmidt, Karl-Julius; Schmidt, Friedrich; Siegle, Peter; and Hansen, Gert, to Bayer Aktiengesellschaft. Continuous preparation of phosphoric acid alkyl ester dichlorides. 4,296,047, Cl. 260-974.000.

Schmidt, Paul. Pneumatically operated ram borer. 4,295,533, Cl. 175-19.000.

Schmidt, Robert R.: See—
Stetter, Jorg; Dittgens, Klaus; Thomas, Rudolf; Eue, Ludwig; and Schmidt, Robert R., 4,295,876, Cl. 71-90.000.

Schmit, Paul F., to Minnesota Mining and Manufacturing Company. Method of heat sealing a film to the lip of a cup. 4,295,904, Cl. 156-69.000.

Schmitt, Franz U.: See—
Mecke, Norbert; Schmitt, Franz U.; Schrader, Karl-Heinz; and Blutschkau, Heinke, 4,296,150, Cl. 427-164.000.

Schmitt, Frederick L.: See—
Wiegiers, Wilhelmus J.; Sprecker, Mark A.; Watkins, Hugh; Vock, Manfred H.; and Schmitt, Frederick L., 4,295,978, Cl. 252-8.900.

Schmuck, Philip W.: See—
Swift, Edward R., Jr.; and Schmuck, Philip W., 4,295,525, Cl. 166-312.000.

Schneider, Hartmut; and Lebetzki, Egon, to Siemens Aktiengesellschaft. Process for the production of glass for a glass workpiece for use in drawing a glass light conducting fiber of a low attenuation. 4,295,870, Cl. 65-3.120.

Schneider, Peter J., Jr. Environmentally heated and cooled pre-fabricated insulated concrete building. 4,295,415, Cl. 98-31.000.

Schneider, Fred E.: See—
Adams, Gary V.; and Schneider, Fred E., 4,296,084, Cl. 423-351.000.

Schowe, Lester F., Jr., to Honeywell, Inc. Phase sensor. 4,296,445, Cl. 360-65.000.

Schrader, Karl-Heinz: See—
Mecke, Norbert; Schmitt, Franz U.; Schrader, Karl-Heinz; and Blutschkau, Heinke, 4,296,150, Cl. 427-164.000.

Schroeder, James E., to Harris Corporation. VMOS Transistor and method of fabrication. 4,296,429, Cl. 357-55.000.

Schroeder, Josef, to Bayer Aktiengesellschaft. Process for the preparation of benzantrones. 4,296,043, Cl. 260-352.000.

Schroeder, Paul R.: See—
Eaton, Sargent S., Jr.; and Schroeder, Paul R., 4,296,480, Cl. 365-222.000.

Schromm, Kurt: See—
Koppe, Herbert; Menstrup, Anton; Renth, Ernst-Otto; Schromm, Kurt; Hoefke, Wolfgang; and Muacevic, Gojko, 4,296,117, Cl. 424-273.00B.

Schubert, Joachim: See—
Beinitz, Karl; and Schubert, Joachim, 4,296,356, Cl. 315-135.000.

Schubert & Salzer: See—
Siemon, Bernhard, 4,295,249, Cl. 19-225.000.

Schuberth, Christian; and Hartmann, Rudolf, to Preh Elektrofeinmechanische Werke Jakob Preh Nachf. GmbH & Co. Variable electro-mechanical device. 4,296,292, Cl. 200-336.000.

Schuler, Peter; and Braun, Erwin. Process for the crystalline precipitation of chromogens. 4,295,857, Cl. 23-301.000.

Schulte, Wilfried: See—
Bergner, Dieter; Hanesen, Kurt; Muller, Wolfgang; and Schulte, Wilfried, 4,295,945, Cl. 204-128.000.

Schumacher, Gunter: See—
Schumacher, Gustav, II; and Schumacher, Gunter, 4,295,328, Cl. 56-313.000.

Schumacher, Gustav, II; and Schumacher, Gunter. Holding means for grain lifters, support skids and the like. 4,295,328, Cl. 56-313.000.

Schumann, Gunter: See—
Johns, Hans; Muller, Wolfgang; Jentzsch, Arndt; and Schumann, Gunter, 4,295,423, Cl. 101-349.000.

LIST OF PATENTEES

Schurr, Robert E., to Rieke Corporation. Closure cap vent. 4,295,583, Cl. 222-478.000.

Schweer, Wilhelm, to Th. Kieserling & Albrecht. Apparatus for peeling pipes. 4,295,397, Cl. 82-20.000.

Schweizer, Edward H., to Investment Rarities, Inc. Variable position article holder. 4,295,623, Cl. 248-456.000.

SCM Corporation: See—

Cardenas, Carlos G.; and Din, Zia U., 4,296,257, Cl. 568-361.000.

Ho, T. L.; and Din, Zia U., 4,296,038, Cl. 260-343.210.

Ho, T. L.; Din, Zia U.; and Cardenas, Carlos G., 4,296,251, Cl. 562-506.000.

Scott Paper Company: See—

Kaiser, Paul H.; Neuschwander, Rudolf; and Norton, Henry J., 4,296,161, Cl. 428-171.000.

Scriminger, William F., to Muskogee Environmental Conservation Co. Slurry gun. 4,295,744, Cl. 366-3.000.

Seaward, William S.: See—

Janssen, Donovan M.; and Seaward, William S., 4,295,733, Cl. 355-14.0SH.

Sedberry, Donald C., to Welsbach Ozone Systems Corporation. Fuse structure for corrosive atmosphere. 4,296,397, Cl. 337-199.000.

Sedlacek, Hans-Harald: See—

Ax, Wolfgang; Bauer, Hartwig W.; and Sedlacek, Hans-Harald, 4,296,201, Cl. 435-7.000.

Sedlmair, Siegfried: See—

Beyer, Franz; and Sedlmair, Siegfried, 4,296,414, Cl. 343-5.0SW.

Seeburger, Harold O.; Beattie, Ralph G.; and Stevens, Violette L., to Dow Chemical Company, The. Method for preparing vinyl ester resins. 4,296,220, Cl. 525-507.000.

Seeburger, Harold O.; Atchison, George J.; and Stevens, Violette L., to Dow Chemical Company, The. Curable polyether resins. 4,296,227, Cl. 526-320.000.

Sehon, Alec: See—

Lee, Weng Y.; and Sehon, Alec, 4,296,097, Cl. 424-78.000.

Seilly, Alec H.; Mowbray, Dorian F.; Mardell, John E.; and Davison, Michael J., to Lucas Industries Limited. Fuel system for an internal combustion engine. 4,295,453, Cl. 123-499.000.

Seiscom Delta Inc.: See—

Reeves, H. Neal; Burnett, Roy E.; Denham, Leslie R.; and Shields, George E., 4,295,542, Cl. 181-108.000.

Seita, Toru: See—

Satoh, Takao; and Seita, Toru, 4,295,944, Cl. 204-98.000.

Seki, Tokio: See—

Mochizuki, Hiroshi; and Seki, Tokio, 4,295,414, Cl. 92-98.000.

Sekmakas, Kazys; and Shah, Raj, to DeSoto, Inc. Epoxy ester copolymer aqueous dispersions. 4,296,011, Cl. 260-29.300.

Sendo, Masaaki; and Suzuki, Kinzo, to Mitsubishi Denki Kabushiki Kaisha. Method of producing bracket and gear box of electric motor with gear box and metal mold used with the same. 4,296,063, Cl. 264-273.000.

Senzimir, Tadeusz. Beam-backed strip mill with attached inserts. 4,295,355, Cl. 72-242.000.

Sepulveda, Ralph R.; and Lander, Lynn H., to Lever Brothers Company. Pretreatment composition for stain removal. 4,295,845, Cl. 8-139.100.

Sergev, Sergius S.; and Roster, Theodore J., to United States of America, Navy. Automatic temperature control system for diver heating system. 4,295,604, Cl. 236-21.00R.

Service Equipment Design Co., Inc.: See—

Hauk, Ernest D.; and Stewart, Larry, 4,295,526, Cl. 166-315.000.

Setagayaseiki Co. Ltd.: See—

Uchida, Sakae, 4,295,830, Cl. 433-115.000.

Seton Company: See—

Cioca, Gheorge; and Siegler, Marcel, 4,295,894, Cl. 106-155.000.

Shah, Raj: See—

Sekmakas, Kazys; and Shah, Raj, 4,296,011, Cl. 260-29.300.

Shakirov, Rifkhat M.: See—

Lifshits, Viktor S.; Krivonos, Vadim P.; Podola, Nikolai V.; Grabchev, Boris L.; Andrianov, Vladimir R.; and Shakirov, Rifkhat M., 4,296,305, Cl. 219-101.000.

Shamsha, Ljudmila F.: See—

Nazarian, Miron M.; Efimov, Vyacheslav T.; Axenok, Alexandr A.; Kolyada, Vladimir A.; and Shamsha, Ljudmila F., 4,295,946, Cl. 204-149.000.

Shannon, Richard F., to Owens-Corning Fiberglas Corporation. Wall-board having improved drying rate due to plural contacting fiber networks. 4,296,169, Cl. 428-298.000.

Sharp, Shelby P.; and Yarbrough, Lyman, to Standard Oil Company (Indiana). Method and composition for inhibiting corrosion in high temperature, high pressure gas wells. 4,295,979, Cl. 252-8.55E.

Shaw, Francis. Self-aligning dome nut. 4,295,766, Cl. 411-13.000.

Shaw, Robert F.; and Sperinde, John, to Oximetrix, Inc. Optical catheters and method for making same. 4,295,470, Cl. 128-634.000.

Sheldon, James R., to Engineered Systems, Inc. Remote verification lockout system. 4,296,404, Cl. 340-149.00A.

Shell Oil Company: See—

St. Clair, David J.; and Ewins, Earle E., Jr., 4,296,008, Cl. 260-27.0BB.

Slaugh, Lynn H., 4,295,999, Cl. 252-455.00R.

Shelor, Jerry L.: See—

Tatham, Jack R.; and Shelor, Jerry L., 4,295,251, Cl. 28-112.000.

Shelver, Lyle N. Thermal glass structure and method for forming same. 4,295,305, Cl. 52-172.000.

Shepherd, Robin G.: See—

Bushnell, Brian J.; Cavalla, John F.; Shepherd, Robin G.; and White, Alan C., 4,296,029, Cl. 260-239.30R.

LIST OF PATENTEES

Sherburne, Edwin C., to ICI Americas Inc. Nonionic textile softener composition. 4,295,977, Cl. 252-8.900.
 Sherwood Medical Industries Inc.: See—
 Cornell, William D., 4,295,974, Cl. 210-789.000.
 Shibasaki, Ichiro; Ohmura, Kaoru; and Kimura, Takeo, to Asahi Kasei Kogyo Kabushiki Kaisha. Compound semiconductor device having a semiconductor-converted conductive region. 4,296,424, Cl. 357-1.000.
 Shibatani, Juichi; Nakamura, Kenichi; Izuhara, Wataru; and Obu, Yuichiro, to Toyota Jidosha Kogyo Kabushiki Kaisha. Anti-rust cover for a disc rotor of a vehicle disc brake. 4,295,549, Cl. 188-218.00A.
 Shibuya, Kyoichi: See—
 Ogawa, Tadashi; Ono, Shunichiro; and Shibuya, Kyoichi, 4,295,823, Cl. 432-106.000.
 Shields, George E.: See—
 Reeves, H. Neal; Burnett, Roy E.; Denham, Leslie R.; and Shields, George E., 4,295,542, Cl. 181-108.000.
 Shigematsu, Kazuo: See—
 Terao, Motoyasu; Shigematsu, Kazuo; Ojima, Masahiro; and Yonezawa, Seiji, 4,296,419, Cl. 346-135.100.
 Shihata, Alfred A. Ureteric stone extractor with two ballooned catheters. 4,295,464, Cl. 128-1.00R.
 Shikoku Kasei Kogyo Co., Ltd.: See—
 Shimamura, Tadao; and Kojima, Tadayoshi, 4,296,051, Cl. 264-118.000.
 Shimada, Wataru; Hoshinouchi, Susumu; Kawaguchi, Kenji; and Yoshida, Akio, to Mitsubishi Denki Kabushiki Kaisha. Method for producing a motion picture screen. 4,295,906, Cl. 156-214.000.
 Shimamura, Tadao; and Kojima, Tadayoshi, to Shikoku Kasei Kogyo Co., Ltd. Method of producing granular sodium dichloroisocyanurate. 4,296,051, Cl. 264-118.000.
 Shimizu, Akira: See—
 Tsuda, Hiroshi; Miyashita, Kiyoshi; Nishikawa, Masaji; Shimizu, Akira; and Kasuga, Muneo, 4,295,734, Cl. 355-15.000.
 Shimizu, Chitomi: See—
 Nakai, Shinzo; and Shimizu, Chitomi, 4,295,440, Cl. 118-412.000.
 Shimotake, Munetoshi: See—
 Kawaguchi, Yasuyosi; Shimotake, Munetoshi; and Yamamoto, Fujio, 4,295,512, Cl. 152-354.00R.
 Shimp, Alan B.: See—
 Paice, Derek A.; and Shimp, Alan B., 4,296,450, Cl. 361-50.000.
 Shin-Etsu Polymer Co., Ltd.: See—
 Sado, Ryoichi, 4,295,700, Cl. 339-61.00M.
 Shinmi, Akira; Fukui, Masahisa; Hara, Toshitami; Shirato, Yoshiaki; and Hajimoto, Yoshioki, to Canon Kabushiki Kaisha. Thermal head. 4,296,309, Cl. 219-216.000.
 Shinzawa, Motohiro: See—
 Yasuhara, Seishi; Teranuma, Jun; Shinzawa, Motohiro; and Fujii, Hiroshi, 4,295,455, Cl. 123-569.000.
 Shirahata, Kunikatsu: See—
 Omura, Satoshi; Tanaka, Haruo; Takahashi, Itaru; Ishii, Shinzo; Mineura, Kazuyuki; Shirahata, Kunikatsu; and Kasai, Masaji, 4,296,040, Cl. 260-345.200.
 Shiraishi, Satoshi; Fujiwara, Kunio; and Kurosaki, Shiro, to Sumitomo Electric Industries, Ltd. Process for producing optical transmission fiber. 4,295,869, Cl. 65-3.110.
 Shirato, Yoshiaki: See—
 Hara, Toshitami; Sato, Yashushi; Takatori, Yasushi; and Shirato, Yoshiaki, 4,296,421, Cl. 346-140.00R.
 Shinni, Akira; Fukui, Masahisa; Hara, Toshitami; Shirato, Yoshiaki; and Hajimoto, Yoshioki, 4,296,309, Cl. 219-216.000.
 Shockley, Norman E. Receptacle support apparatus for bicycle. 4,295,586, Cl. 224-32.00R.
 Shopin, Viktor M.; Turenko, Leonid G.; Surovikin, Vitaly F.; and Suponev, Konstantin V. Apparatus for separating carbon black from carbon-black aerosol. 4,295,867, Cl. 55-288.000.
 Shumaker, John F., to J. I. Case Company. Straight arm loader. 4,295,779, Cl. 414-685.000.
 Sick, Erwin, to Erwin Sick GmbH, Optik-Elektronik. Apparatus for determining faults in strip material. 4,295,743, Cl. 356-431.000.
 Siegle, Peter: See—
 Schmidt, Karl-Julius; Schmidt, Friedrich; Siegle, Peter; and Hansen, Gert, 4,296,047, Cl. 260-974.000.
 Siegler, Marcel: See—
 Cioca, George; and Siegler, Marcel, 4,295,894, Cl. 106-155.000.
 Siegmund, Werner, to Mannesmann Aktiengesellschaft. Antifreeze protection of roads. 4,296,207, Cl. 521-53.000.
 Siemens Aktiengesellschaft: See—
 Aigle, Karl; Hieber, Udo; Huebscher, Wilhelm; Rheindorf, Hans H.; and Wiedemann, Rolf, 4,296,453, Cl. 361-275.000.
 Becker Friedbert; Steinkamp, Johann; and Koenen, Klaus, 4,296,400, Cl. 340-32.000.
 Beyer, Franz; and Sedlmair, Siegfried, 4,296,414, Cl. 343-5.0SW.
 Feuerbaum, Hans-Peter, 4,296,372, Cl. 324-71.0EB.
 Haensel, Eckhart, 4,296,403, Cl. 340-147.00P.
 Muhling, Alois; Reissner, Frank; and Schmidt, Helmut, 4,295,380, Cl. 74-3.500.
 Schneider, Hartmut; and Lebetzki, Egon, 4,295,870, Cl. 65-3.120.
 Siemens-Albis Aktiengesellschaft: See—
 Forstner, Anton; and Schatzmann, Kurt, 4,295,441, Cl. 118-425.000.
 Siemens-Allis, Inc.: See—
 Lott, Donald L., 4,296,284, Cl. 200-48.00R.
 Siemon, Bernhard, to Schubert & Salzer. Combing machine. 4,295,249, Cl. 19-225.000.
 Siennknecht, Walter F. Hand tool leveling apparatus. 4,295,279, Cl. 33-334.000.

- Signon, James W. Expandable device. 4,295,633, Cl. 251-172.000.
 Sigr Elektrographit GmbH: See—
 Freundlinger, Ernst; and Hirschvogel, Alfred, 4,296,177, Cl. 428-408.000.
 Sih, John C., to Upjohn Company, The. 19-Hydroxy-7a-homo-PG₁₂ compounds. 4,296,041, Cl. 260-345.200.
 Sih, John C., to Upjohn Company, The. 13,14-Didehydro-11-deoxy-11-hydroxymethyl-19-oxo-PGF₁ compounds. 4,296,246, Cl. 562-503.000.
 Sih, John C., to Upjohn Company, The. 13,14-Dihydro-11-deoxy-11-hydroxymethyl-9-deoxy-9-methylene-19-oxo-PGF₁ compounds. 4,296,247, Cl. 562-503.000.
 Sih, John C., to Upjohn Company, The. 13,14-Dihydro-11-deoxy-11-hydroxymethyl-19-oxo-PGE₁ compounds. 4,296,248, Cl. 562-503.000.
 Sih, John C., to Upjohn Company, The. 13,14-Dihydro-11-deoxy-9-deoxy-9-methylene-19-oxo-PGE₁ compounds. 4,296,249, Cl. 562-503.000.
 Sih, John C., to Upjohn Company, The. 13,14-Dihydro-9-deoxy-9-methylene-19-oxo-PGF₁ compounds. 4,296,250, Cl. 562-503.000.
 Sih, John C., to Upjohn Company, The. 2-Decarboxy-2-hydroxymethyl-19-keto-PG compounds. 4,296,256, Cl. 568-330.000.
 Sih, John C.: See—
 Axen, Udo F.; and Sih, John C., 4,296,253, Cl. 564-153.000.
 Silverberg, Morton, to Xerox Corporation. Grooved belt document registration system. 4,295,737, Cl. 355-76.000.
 Sim, William J.; and Marth, Ronald M. Support bracket for distribution panel for cooling towers and the like. 4,296,048, Cl. 261-111.000.
 Simcoe, Robert J., to General Electric Company. High voltage standoff MOS driver circuitry. 4,296,335, Cl. 307-200.00B.
 Simogawara, Naoki: See—
 Yanabu, Satoru; Mizoguchi, Hitoshi; and Simogawara, Naoki, 4,296,288, Cl. 200-146.00R.
 Simons, S. Stoney, Jr., to United States of America, America. Irreversible anti-glucocorticoids. 4,296,206, Cl. 435-240.000.
 Simpson, Frank H. Shot and powder dispenser attachment. 4,295,409, Cl. 86-31.000.
 Singer Company, The: See—
 Peot, David G., 4,296,290, Cl. 200-325.000.
 Singer, Michael: See—
 Buckley, Alan J.; and Singer, Michael, 4,295,887, Cl. 106-18.330.
 Sio-Societa per l'Industria Dell'Ossigeno e di Altri Gas: See—
 Bottiglia, Augusto, 4,296,300, Cl. 219-61.700.
 Siryj, Bohdan W., to RCA Corporation. Solar tracking apparatus. 4,295,621, Cl. 248-183.000.
 Skanadore, William R., to General Semiconductor Co., Inc. Switching circuit and method for avoiding secondary breakdown. 4,296,336, Cl. 307-300.000.
 Skierski, Edwin J., to USM Corporation. Chip breaker screws. 4,295,768, Cl. 411-387.000.
 Skinner, Doyle P., Jr.: See—
 Markham, Roger G.; and Skinner, Doyle P., Jr., 4,296,417, Cl. 346-75.000.
 Slack, Charles B.: See—
 Cullison, Steven B.; and Slack, Charles B., 4,296,278, Cl. 179-1.0VL.
 Slaugh, Lynn H., to Shell Oil Company. Polymerization catalyst. 4,295,999, Cl. 252-455.00R.
 Sleishman, Donald E. Musician's drum. 4,295,405, Cl. 84-413.000.
 Slickbar, Inc.: See—
 Blair, Russell M., 4,295,756, Cl. 405-70.000.
 Slovinsky, Manuel, to Nalco Chemical Company. Grouting-soil conditioning systems using polyoxyethylene diacrylates. 4,295,762, Cl. 405-264.000.
 Smit Ovens Nijmegen B.V.: See—
 Wens, Johannes C., 4,295,824, Cl. 432-115.000.
 Smith, David E., to Blue Circle Industries Limited. Producing dispersions of preflocculated fillers for use in papermaking. 4,295,933, Cl. 162-168.0NA.
 Smith, Don H.; Bowman, Arthur F.; and Junk, Norman M., to Atlas Powder Company. Explosive container for cast primer. 4,295,424, Cl. 102-322.000.
 Smith International, Inc.: See—
 Crase, Gary M.; and Trzeciak, Kurt M., 4,295,535, Cl. 175-101.000.
 Smith, James A. Patio door security lock. 4,295,676, Cl. 292-262.000.
 Smith, James D. B.; and Kauffman, Robert N., to Westinghouse Electric Corp. Catechol or pyrogallol containing flexible insulating tape having low gel time. 4,296,018, Cl. 260-32.8EP.
 Smith, Larry C. Note translation device. 4,295,406, Cl. 84-470.00R.
 Smith, Leslie; Tew, William; and Woolley, Jack, to Plessey Handel und Investments A.G. Electrolyte capacitors with improved anode-to-lead connection. 4,296,458, Cl. 361-433.000.
 Smith, Michael R.; and DiFulvio, Anthony P., to Eastman Kodak Company. Apparatus for processing an analysis slide. 4,296,069, Cl. 422-64.000.
 Smith, Michael R.: See—
 Montalto, Michael S.; Blanding, Douglass L.; and Smith, Michael R., 4,296,070, Cl. 422-65.000.
 Smith, Paul R., to DiMarzio Musical Instrument Pickups, Inc. Compensated nut for a lute-type instrument. 4,295,404, Cl. 84-314.00N.
 Smith, Peter H.: See—
 Stottmann, Richard L.; and Smith, Peter H., 4,296,299, Cl. 219-10.810.
 Smith, Samuel W. Crutch-mounted accessory pouch. 4,295,483, Cl. 135-66.000.
 Snamprogetti S.p.A.: See—
 Cucinella, Salvatore; Mazzei, Alessandro; and Dozzi, Giovanni, 4,296,045, Cl. 260-448.00R.
 Snia Viscosa Societa Nazionale Industria Applicazioni Viscosa S.p.A.: See—
 Genco, Vito; and Turco, Vincenzo L., 4,295,426, Cl. 102-451.000.
 Snitzer, Elias: See—
 Meltz, Gerald; and Snitzer, Elias, 4,295,738, Cl. 356-32.000.
 Meltz, Gerald; and Snitzer, Elias, 4,295,739, Cl. 356-43.000.
 Snyder, Dennis R., to Bell Telephone Laboratories, Incorporated. Multi-outlet adapter for plug-in telephones. 4,295,702, Cl. 339-97.00P.
 Snyder, Richard H.: See—
 Mapes, Charles W.; and Snyder, Richard H., 4,295,835, Cl. 440-78.000.
 Snyder, Wesley L. Laser aiming device with lateral shock absorber. 4,295,289, Cl. 42-1.00A.
 So, Eddy: See—
 Moore, William J. M.; Kusters, Norbert L.; and So, Eddy, 4,296,369, Cl. 323-218.000.
 Sochor, Josef, to Robert Bosch GmbH. Inductive signal transducer supply circuit particularly for video recording use. 4,296,444, Cl. 360-65.000.
 Societa Pneumatici Pirelli S.p.A.: See—
 Mezzanotte, Mario; and Turchetti, Gianni, 4,295,511, Cl. 152-354.00R.
 Societe Anonyme Automobiles Citroen: See—
 Goux, Jacques, 4,296,471, Cl. 364-424.000.
 Societe de Vente de l'Aluminium Pechiney: See—
 Hicter, Jean-Marie; and Guerit, Pierre, 4,295,884, Cl. 75-93.00R.
 Societe Europeenne de Propulsion: See—
 Clebant, Jean C., 4,295,671, Cl. 285-223.000.
 Societe Nationale d'Etude et de Construction de Moteurs d'Aviation: See—
 Lardellier, Alain M. J., 4,295,785, Cl. 415-174.000.
 Lardellier, Alain M. J., 4,295,787, Cl. 415-197.000.
 Societe Nationale Industrielle Aerospatiale: See—
 Mialon, Jacques; and Lamarche, Bernard, 4,295,388, Cl. 74-579.00R.
 Sodeco-SAIA SA: See—
 Guttiger, Kurt, 4,296,341, Cl. 310-41.000.
 Sodergren, Robert C.: See—
 Woods, Rodney G.; Clarke, Charles J., Jr.; and Sodergren, Robert C., 4,296,464, Cl. 364-200.000.
 Soejima, Shigeo: See—
 Matsuhisa, Tadaaki; Soejima, Shigeo; and Yamamoto, Noboru, 4,295,892, Cl. 501-120.000.
 Sokoly, Theodore O.; and Niedzialkowski, John, to McGraw-Edison Company. Metal oxide varistor manufacture. 4,296,002, Cl. 252-518.000.
 Solly, Barry: See—
 Malmgren, Nils-Gunnar; Solly, Barry; and Tarnblom, Stig, 4,295,900, Cl. 148-12.00B.
 Solvay & Cie: See—
 Berger, Eugene, 4,296,223, Cl. 526-125.000.
 Sommars, Mark F., to Caterpillar Tractor Co. Heat exchanger core mounting apparatus. 4,295,521, Cl. 165-69.000.
 Sommer, Oswin: See—
 Innertsberger, Ernst; Sommer, Oswin; Bosch, Erhard; Muller, Johann; and Schiller, August, 4,296,228, Cl. 528-33.000.
 Sonoco Products Company: See—
 Sansbury, Jerry F., 4,295,840, Cl. 493-278.000.
 Sony Corporation: See—
 Ohkubo, Hiroyuki, 4,296,377, Cl. 324-252.000.
 Sakamoto, Hitoshi; and Wakisaka, Yoshiaki, 4,296,443, Cl. 360-10.000.
 Sorathia, Usman A. K.: See—
 Gagliani, John; and Sorathia, Usman A. K., 4,296,208, Cl. 521-77.000.
 Southwest Research Institute: See—
 King, James D., 4,296,378, Cl. 324-313.000.
 Spainhour, Phillip A.; Morrison, Leonard A.; and Hampton, Robert S., Jr., to Ammco Tools, Inc. Strut compressor. 4,295,634, Cl. 254-10.500.
 Speech Technology Corporation: See—
 Stork, John E., 4,296,279, Cl. 179-1.0SM.
 Speranza, George P.: See—
 Cuscurida, Michael; and Speranza, George P., 4,296,213, Cl. 521-166.000.
 Sperinde, John: See—
 Shaw, Robert F.; and Sperinde, John, 4,295,470, Cl. 128-634.000.
 Sperry Corporation: See—
 Hill, Roy K., 4,296,332, Cl. 250-570.000.
 Kritz, Jacob A., 4,296,482, Cl. 367-91.000.
 Nelson, Gary L.; and Harvey, William A., 4,295,988, Cl. 252-584.000.
 Pearson, Billy J., 4,296,406, Cl. 340-166.00R.
 Thaxter, James B., 4,295,442, Cl. 118-657.000.
 Spiegel, Hubert: See—
 Wuthrich, Hans-Rudolf; Krebs, Peter; Spiegel, Hubert; and Eicher, Franz, 4,296,289, Cl. 200-148.00R.
 Spirax Sarco Limited: See—
 Clayton, Edward R. C.; and Bennett, Alan F., 4,295,605, Cl. 236-56.000.
 Spisak, Edward G. Plastic and metal wheel trim assembly. 4,295,685, Cl. 301-37.00P.

- Sprague Electric Company: See—
 Higgs, Jacob K.; and Avery, Grant D., 4,296,410, Cl. 340-686.000.
 Sprecher & Schuh AG: See—
 Wuthrich, Hans-Rudolf; Krebs, Peter; Spiegel, Hubert; and Eicher, Franz, 4,296,289, Cl. 200-148.00R.
 Sprecker, Mark A.: See—
 Wiegner, Wilhelmus J.; Sprecker, Mark A.; Watkins, Hugh; Vock, Manfred H.; and Schmitt, Frederick L., 4,295,978, Cl. 252-8.900.
 Spring, David J.: See—
 Roswell, David G.; Spring, David J.; and Hems, Roger, 4,296,255, Cl. 564-215.000.
 Springer, Brice D.: See—
 Arends, Roger R.; Bailey, Wayne B.; Duffy, John W.; and Springer, Brice D., 4,295,489, Cl. 137-488.000.
 Squire, Derek. Karate board holding and storage device. 4,295,646, Cl. 272-76.000.
 Squires, Christopher P.: See—
 Young, Donald A.; and Squires, Christopher P., 4,296,342, Cl. 310-77.000.
 Srinivasan, K. G.: See—
 Aitken, Thomas; Kowalski, David J.; and Srinivasan, K. G., 4,295,930, Cl. 162-158.000.
 Srivastava, Gopal K.: See—
 Engel, Christopher M.; and Srivastava, Gopal K., 4,296,432, Cl. 358-28.000.
 Stachurski, John Z. O. Electrochemical cell. 4,296,184, Cl. 429-14.000.
 Stahl, Howard D.: See—
 Lazarus, Charles R.; Stahl, Howard D.; and Haas, Gerhard J., 4,296,132, Cl. 426-2.000.
 Staiger, Gerhard; and Bronstert, Klaus, to BASF Aktiengesellschaft. Manufacture of poly- α -olefins. 4,296,222, Cl. 526-119.000.
 Stamcarbon, B.V.: See—
 Jongma, Cornelis; Frijs, Leon H. B.; and Raven-Donners, Paula A. M., 4,296,245, Cl. 562-494.000.
 Vroomans, Hubertus J., 4,296,023, Cl. 260-45.75F.
 Standard Oil Company (Indiana): See—
 Fahrig, Robert J.; and Hinrichs, Lansing M., 4,295,961, Cl. 208-161.000.
 Meshri, Indurani D., 4,295,365, Cl. 73-153.000.
 Sharp, Shelby P.; and Yarbrough, Lyman, 4,295,979, Cl. 252-8.55E.
 Star Manufacturing Company of Oklahoma: See—
 Kim, Kwon S., 4,295,304, Cl. 52-90.000.
 Statni vyzkumny ustav materialu: See—
 Kupf, Lubomir; Travnicek, Jiri; Adamek, Radomil; and Kyzlink, Josef, 4,295,628, Cl. 249-80.000.
 Stauber, Ronald C.: See—
 Kulin, Ralph; and Stauber, Ronald C., 4,295,619, Cl. 248-95.000.
 Stauffer, Adolf, to Davy Powergas GmbH. Heat exchange techniques for the catalytic oxidation of gaseous sulfur compounds to sulfur trioxide. 4,296,088, Cl. 423-533.000.
 Stavlo, Lars G., to AGA AB. Pallet for pressurized gas cylinders. 4,295,431, Cl. 108-55.100.
 Steck, Werner; Sarnecki, Wilhelm; Marosi, Laszlo; Ohlinger, Manfred; and Autzen, Horst, to BASF Aktiengesellschaft. Manufacture of acicular ferromagnetic iron particles. 4,295,879, Cl. 75-0.5AA.
 Steck, Werner: See—
 Rudolf, Peter; Steck, Werner; Jakusch, Helmut; Vaeth, Guenter; and Jaekch, Christof, 4,296,149, Cl. 427-130.000.
 Stein, Hermann, to Vorwerk & Sohn GmbH & Co. KG. Emergency track ring for pneumatic vehicle tires. 4,295,509, Cl. 152-158.000.
 Steinbichler, Wolf: See—
 Sauer, Hans; Steinbichler, Wolf; and Antonitsch, Sepp, 4,296,393, Cl. 335-125.000.
 Steinkamp, Johann: See—
 Becker, Friedbert; Steinkamp, Johann; and Koenen, Klaus, 4,296,400, Cl. 340-32.000.
 Steinlein, Rudolf F., to Alexander Schoeller & Co., AG. Molded case for returnable beverage bottles. 4,295,576, Cl. 220-21.000.
 Stelson, Thomas S.: See—
 Barth, Charles F.; Stelson, Thomas S.; and Blake, David E., 4,295,301, Cl. 51-165.880.
 Stemme, Otto; Ruf, Wolfgang; and Wagensonner, Eduard, to AGFA-Gevaert Aktiengesellschaft. Projection and scanning system for producing video signals from motion picture film and control system used therein. 4,296,438, Cl. 358-214.000.
 Stephan, Herbert; Aichert, Hans; and Heimerl, Joseph, to Leybold-Heraeus GmbH & Co. KG. Apparatus for the production of high-purity metal powder by means of electron beam heating. 4,295,808, Cl. 425-8.000.
 Sterling Drug Inc.: See—
 Michne, William F., 4,296,238, Cl. 546-97.000.
 Stetter, Jorg; Ditzgen, Klaus; Thomas, Rudolf; Eue, Ludwig; and Schmidt, Robert R., to Bayer Aktiengesellschaft. N-(2,5-Diazolyl)-alkyl-haloacetanilides, compounds and herbicidal compositions. 4,295,876, Cl. 71-90.000.
 Stevens, Eric, to Toro Company, The. Snowthrower. 4,295,285, Cl. 37-43.00D.
 Stevens, Samuel B., to Caterpillar Tractor Co. Tape brake for tape wrapper. 4,295,916, Cl. 156-397.000.
 Stevens, Violette L.: See—
 Seeburger, Harold O.; Beattie, Ralph G.; and Stevens, Violette L., 4,296,220, Cl. 525-507.000.
 Seeburger, Harold O.; Atchison, George J.; and Stevens, Violette L., 4,296,227, Cl. 526-320.000.
 Stevie, Robert W., to Innovative Photographic Enterprises, Inc. Half-tone printing system. 4,296,197, Cl. 430-300.000.
 Stewart, Alistair B.; and Barker, Ian J., to National Institute for Metallurgy. Control of electrical arc furnaces. 4,296,269, Cl. 13-12.000.
 Stewart, Larry: See—
 Hawk, Ernest D.; and Stewart, Larry, 4,295,526, Cl. 166-315.000.
 Stewart, R. Gordon: See—
 Lynn-Jones, David M.; and Stewart, R. Gordon, 4,295,315, Cl. 52-573.000.
 Steyer, William; and Duffy, Robert J., to General Electric Company. Infrared suppressor system. 4,295,332, Cl. 60-264.000.
 Stifano, Vincent A., Jr., to Veeder Industries Inc. Tool attachment having spring eject release. 4,295,395, Cl. 81-121.00R.
 Stinnes, Wolf W. Winding of fibres. 4,295,917, Cl. 156-428.000.
 Stokes, Richard P.; and Stokes, William, to Unlimited Steel Fabricators, Inc. Die for the formation of semi-closed channels or other complex configurations. 4,295,352, Cl. 72-57.000.
 Stokes, William: See—
 Stokes, Richard P.; and Stokes, William, 4,295,352, Cl. 72-57.000.
 Stoll, Alois: See—
 Weissgerber, Rudolf; Stoll, Alois; Kandler, Herbert; Nunner, Hans-Herbert; Eichelseder, Christine; and Pangeri, Helmut, 4,296,017, Cl. 260-30.60R.
 Stone, Dale E., to Bell Telephone Laboratories, Incorporated. Resistance detector with delayed hysteresis. 4,296,337, Cl. 307-356.000.
 Storey, Richard: See—
 Drewery, John O.; and Storey, Richard, 4,296,434, Cl. 358-105.000.
 Stork, John E., to Speech Technology Corporation. Speech synthesizer. 4,296,279, Cl. 179-1.0SM.
 Story, Alfred D.: See—
 Trimble, Roy L.; Story, Alfred D.; and Martinek, Harold H., 4,295,247, Cl. 17-1.00R.
 Stottmann, Richard L.; and Smith, Peter H., to General Electric Company. Apparatus for thawing frozen food in a refrigeration appliance. 4,296,299, Cl. 219-10.810.
 Stratabolt Corporation: See—
 Hansen, Roger M., 4,295,761, Cl. 405-261.000.
 Strickland, Hubert E. Auger-equipped plow. 4,295,531, Cl. 172-42.000.
 Strickland, William N. Blow-out preventor. 4,295,529, Cl. 166-325.000.
 Stroberg, Sven-Olle: See—
 Hagberg, Gideon, 4,295,969, Cl. 210-223.000.
 Strohs, Robert F. Work stand for vertical turbine pumps. 4,295,257, Cl. 29-240.000.
 Stroke, Frederick G., to PPG Industries, Inc. Submicron beta silicon carbide powder and sintered articles of high density prepared therefrom. 4,295,890, Cl. 501-90.000.
 Stromback, Theodore D. Baseball pitcher's target. 4,295,648, Cl. 273-26.00A.
 Stromswold, Chester E.: See—
 Fuller, Harrison W.; and Stromswold, Chester E., 4,296,389, Cl. 333-160.000.
 Stuart-Webb, John, to Imperial Chemical Industries Limited. Aromatic polyethersulphones having —OCH₂COR end groups. 4,296,217, Cl. 525-390.000.
 Sturges, Robert H., Jr., to Westinghouse Electric Corp. Photoelectric docking device. 4,295,740, Cl. 356-152.000.
 Su, Wen-Shen. Method for removing dust from flue gases. 4,295,865, Cl. 55-84.000.
 Suddesche Kalkstickstoff-Werke: See—
 Aignesberger, Alois; Lukas, Walter; and Weinberg, Ekkehard, 4,296,089, Cl. 423-555.000.
 Suganuma, Toshio: See—
 Matsubara, Akira; Sakai, Hideaki; Odate, Makoto; Suganuma, Toshio; and Nakano, Takuo, 4,296,112, Cl. 424-246.000.
 Sugata, Yoshiaki; and Miyagawa, Kiyoshi, to Toyoda Koki Kabushiki Kaisha. Workpiece supporting device. 4,295,398, Cl. 82-31.000.
 Sugimoto, Kaname, to Hayashibara, Ken. Process for preparing human interferon. 4,296,025, Cl. 260-112.00R.
 Sugino, Takashi; and Itoh, Kunio, to Matsushita Electric Industrial Co., Ltd. Semiconductor laser. 4,296,387, Cl. 331-94.50H.
 Suginuma, Atsushi: See—
 Sayo, Kosaku; Suginuma, Atsushi; Tatsumi, Hideo; and Kanamaru, Hisanobu, 4,295,553, Cl. 192-84.00C.
 Sugiura, Hitoshi: See—
 Ishihara, Takeshi; Goto, Daisaku; and Sugiura, Hitoshi, 4,296,276, Cl. 174-179.000.
 Sugiyama, Goro. Gas lighter. 4,295,819, Cl. 431-143.000.
 Sulzer Brothers Limited: See—
 Erlach, Hans, 4,295,552, Cl. 192-81.00C.
 Meier, Werner, 4,296,050, Cl. 261-112.000.
 Sumida, Yasuji: See—
 Sasaki, Koichi; Sumida, Yasuji; and Ishida, Hiroshi, 4,295,731, Cl. 355-14.00R.
 Sumitomo Cement Co., Ltd.: See—
 Ogawa, Tadashi; Ono, Shunichiro; and Shibuya, Kyoichi, 4,295,823, Cl. 432-106.000.
 Sumitomo Chemical Company, Limited: See—
 Mori, Kenji; and Sasaki, Mitsuru, 4,296,036, Cl. 260-340.700.
 Yamaguchi, Takashi; Okuno, Yoshitoshi; and Hirose, Chuji, 4,295,581, Cl. 222-192.000.
 Sumitomo Electric Industries, Ltd.: See—
 Shiraiishi, Satoshi; Fujiwara, Kunio; and Kurosaki, Shiro, 4,295,869, Cl. 65-3.110.
 Sumitomo Metal Industries, Ltd.: See—
 Itoh, Koichi; Koshida, Osamu; and Nakayama, Katsuichi, 4,295,354, Cl. 72-225.000.

- Sumitomo Naugatuck Co., Ltd.: See—
Sakano, Hajime; Kodama, Mikio; Nakayama, Koichi; Yoshida, Isao; and Inoue, Atsunori, 4,296,216, Cl. 525-66.000.
- Sun, Jui-Yuan; Burk, Emmett H., Jr.; Yoo, Jin S.; and Maslogites, George P., to Atlantic Richfield Company. Process for removing sulfur from coal. 4,295,858, Cl. 44-1.0SR.
- Sunroc Corporation: See—
Brown, Frank, Jr., 4,295,609, Cl. 239-29.000.
- Suponev, Konstantin V.: See—
Shopin, Viktor M.; Turenko, Leonid G.; Surovikin, Vitaly F.; and Suponev, Konstantin V., 4,295,867, Cl. 55-288.000.
- Surovikin, Vitaly F.: See—
Shopin, Viktor M.; Turenko, Leonid G.; Surovikin, Vitaly F.; and Suponev, Konstantin V., 4,295,867, Cl. 55-288.000.
- Susumu Sasaki: See—
Sasaki, Susumu; Kito, Kyoji; and Koide, Akio, 4,295,855, Cl. 23-230.00B.
- Sutrina, Thomas A.; and Behr, R. Douglas, to Dow Chemical Co., The. Forming an integral closure for a thermoplastic container. 4,295,919, Cl. 156-498.000.
- Suzuki, Hajime; and Iwano, Yoshimi, to Kabushiki Kaisha Toyoda Jidoshokki Seisakusho. Detection of weft in shuttleless loom. 4,295,499, Cl. 139-370.200.
- Suzuki, Kinzo: See—
Sendo, Masaki; and Suzuki, Kinzo, 4,296,063, Cl. 264-273.000.
- Suzuki, Miyo: See—
Nakanishi, Toshiharu; Suzuki, Miyo; and Ohigashi, Hiroji, 4,296,349, Cl. 310-335.000.
- Suzuki, Takashi; Sawada, Hidekazu; and Katamoto, Kazuyoshi, to Takeda Chemical Industries, Ltd. Miltidomycin analogs and a method of production. 4,296,107, Cl. 424-180.000.
- Svaty, Vladimir, to Zbrojovka Vsetin. Method of and a device for forming an additional stream of air in a guide comb of an air jet loom. 4,295,500, Cl. 139-435.000.
- Svelto, Francesco: See—
Mezzetti, Sergio; Pizzolati, Pierluigi; and Svelto, Francesco, 4,296,318, Cl. 250-225.000.
- Svitak, John J.: See—
Doten, Bradford O.; and Svitek, John J., 4,295,596, Cl. 228-180.00A.
- Swales, Danvers A.; and Marshall, Michael A., to British Chrome & Chemicals Ltd. Chromic oxide production. 4,296,076, Cl. 423-53.000.
- Swassek, Gunter: See—
Nelle, Gunther; and Swassek, Gunter, 4,295,742, Cl. 356-373.000.
- Swenson, Paul F. Heating system. 4,295,606, Cl. 237-12.100.
- Swift, Edward R., Jr.; and Schmuck, Philip W., to Baker International Corporation. Method and apparatus for quick replacement of cartridge filters used in well fluid cleaning operations. 4,295,525, Cl. 166-312.000.
- Swiss Aluminium Ltd.: See—
Lajh, Rajko, 4,295,883, Cl. 75-68.00R.
- Sygnator, Henry A.: See—
Bjorklund, Lowell L.; Berg, Ramon A.; and Sygnator, Henry A., 4,295,351, Cl. 72-38.000.
- Syntex (U.S.A.) Inc.: See—
Muchowski, Joseph M.; and Venuti, Michael C., 4,296,042, Cl. 260-345.90R.
- Szarka, David D.: See—
Baker, Eugene E.; and Szarka, David D., 4,295,524, Cl. 166-278.000.
- Szczepanski, Slawomir Z. Vehicle anti-theft device. 4,296,402, Cl. 340-64.000.
- Szente, Andre: See—
Fischli, Albert E.; and Szente, Andre, 4,296,031, Cl. 260-239.30D.
- Tabei, Masatoshi: See—
Kawaziri, Kazuhiro; Fujiwara, Masato; Hatanaka, Isamu; Tabei, Masatoshi; Higashi, Akio; and Nirasawa, Mitsuhiro, 4,296,422, Cl. 346-160.000.
- Tachibana, Keiji; Nakayama, Yoshihiko; Kaneko, Junichi; and Ishii, Susumu, to Hitachi, Ltd. Apparatus for controlling operation of fluid pressure raising system. 4,295,792, Cl. 417-15.000.
- Tada, Isao: See—
Fukatsu, Akihiro; and Tada, Isao, 4,296,355, Cl. 315-39.510.
- Taiho Kogyo Co., Ltd.: See—
Iwahana, Keiiti; Mathuda, Yoshimi; and Futamura, Kenichiro, 4,296,183, Cl. 428-653.000.
- Takacs, Istvan; Banos, Zoltan; Illes, Janos; Vereczkey, Endre; Rudolf, Peter; and Kerey, Gyorgy, to Richter Gedeon Vegyeszeti Gyar. Apparatus for the treatment of wet solids, especially pulpy materials, by heating or cooling. 4,296,072, Cl. 422-254.000.
- Takagi, Sadaaki. Method for production of polyurethane cushion material. 4,296,054, Cl. 264-45.300.
- Takahashi, Akio; Itoh, Yutaka; Wajima, Motoyo; Morishita, Hirosada; and Nishikawa, Akio, to Hitachi, Ltd.; and Hitachi Chemical Co., Ltd. Bismide-ether compounds, compositions thereof, and method of producing same. 4,296,219, Cl. 525-488.000.
- Takahashi, Akira; and Oohashi, Kenichi, to Kabushiki Kaisha Osaka Packing Seizosho. Alumina-containing calcium silicate and process for producing same. 4,295,893, Cl. 106-120.000.
- Takahashi, Itaru: See—
Omura, Satoshi; Tanaka, Haruo; Takahashi, Itaru; Ishii, Shinzo; Mineura, Kazuyuki; Shirahata, Kunikatsu; and Kasai, Masaji, 4,296,040, Cl. 260-345.200.
- Takahashi, Soji: See—
Imai, Kuninori; and Takahashi, Soji, 4,295,595, Cl. 228-161.000.
- Takara Co., Ltd.: See—
Fukui, Osamu, 4,295,291, Cl. 46-161.000.
- Takashi, Uchiyama; Tsunekawa, Tokuchi; and Kiyohara, Takehiko, to Canon Kabushiki Kaisha. Camera for daylight and flash photography. 4,295,722, Cl. 354-146.000.
- Takatori, Yasushi: See—
Hara, Toshitami; Sato, Yashushi; Takatori, Yasushi; and Shirato, Yoshiaki, 4,296,421, Cl. 346-140.00R.
- Takeda Chemical Industries, Ltd.: See—
Ogino, Fumiichi, 4,296,166, Cl. 428-283.000.
- Suzuki, Takashi; Sawada, Hidekazu; and Katamoto, Kazuyoshi, 4,296,107, Cl. 424-180.000.
- Takeuchi, Kiyoyuki, to Tokyo Shibaura Denki Kabushiki Kaisha. Film containing magazine. 4,295,565, Cl. 206-455.000.
- Takeuchi, Minami; and Kuriki, Minoru, to Tokyo Shibaura Electric Co., Ltd. Reverse conducting amplified gate thyristor with plate-like separator section. 4,296,427, Cl. 357-39.000.
- Takezaki, Tsuneo, to Matsushita Electric Industrial Company. Level indicator for indication of maximum values. 4,296,375, Cl. 324-103.00P.
- Takikawa, Yoshio: See—
Ooki, Norihiro; Motegi, Shoji; Wachi, Yasuyuki; Takikawa, Yoshio; and Yamakawa, Norio, 4,296,346, Cl. 310-242.000.
- Talres Development (N.A.) N.V.: See—
Khan, Riaz A.; and Jenner, Michael R., 4,296,139, Cl. 426-536.000.
- Tanaka, Chiaki: See—
Saito, Tasuku; Noma, Tutomu; Matsunaga, Tsutomu; Naito, Nagayoshi; Tanaka, Chiaki; and Hiratsuka, Motoki, 4,295,652, Cl. 273-235.00R.
- Tanaka, Haruo: See—
Omura, Satoshi; Tanaka, Haruo; Takahashi, Itaru; Ishii, Shinzo; Mineura, Kazuyuki; Shirahata, Kunikatsu; and Kasai, Masaji, 4,296,040, Cl. 260-345.200.
- Tanaka, Hiromitsu: See—
Enomoto, Satoru; Asano, Kiro; and Tanaka, Hiromitsu, 4,296,233, Cl. 536-5.000.
- Tanaka, Hironari; Matsuyama, Shigeru; Ishibashi, Tadashi; Kinugawa, Kiyoshige; and Sato, Yukihiko, to Hitachi, Ltd. Liquid crystal display device. 4,295,711, Cl. 350-334.000.
- Tanaka, Kenji; and Endo, Shigeru, to Nisshin Flour Milling Co., Ltd. Method for producing bread. 4,296,133, Cl. 426-23.000.
- Tanaka, Naoki; Tsuchiya, Kunihiko; and Nishizawa, Toshizo, to Mitsubishi Denki Kabushiki Kaisha. Rotary compressor with wire gauge lubricant separator. 4,295,806, Cl. 418-97.000.
- Tanaka, Shigeyoshi: See—
Ohtani, Eiichi; Kobayashi, Kengo; Isobe, Asao; and Tanaka, Shigeyoshi, 4,295,947, Cl. 204-159.150.
- Tang, David Y.; and Foster, Arthur M., to Hooker Chemicals & Plastics Corp. (3-Trifluoromethylphenyl)-alpha-hydroxyacetic acid and process for preparation. 4,296,244, Cl. 562-470.000.
- Taniguchi, Hiroyoshi: See—
Hasegawa, Haruo; Taniguchi, Hiroyoshi; and Igawa, Takao, 4,296,190, Cl. 430-57.000.
- Tano, Kazuhiro: See—
Higuchi, Seizun; Tano, Kazuhiro; Kamada, Minoru; and Okamoto, Susumu, 4,296,145, Cl. 427-47.000.
- Tapeswitch Corporation of America: See—
Koenig, Robert H.; and D'Angelo, Victor, 4,296,283, Cl. 200-16.00D.
- Tarnblom, Stig: See—
Malmgren, Nils-Gunnar; Solly, Barry; and Tarnblom, Stig, 4,295,900, Cl. 148-12.00B.
- Tatham, Jack R.; and Shelor, Jerry L., to Phillips Petroleum Company. Method for controlling edge uniformity in nonwoven fabrics. 4,295,251, Cl. 28-112.000.
- Tatis Plastatningar AB: See—
Dahlberg, Anders, 4,295,311, Cl. 52-396.000.
- Tatsumi, Hideo: See—
Sayo, Kosaku; Suginuma, Atsushi; Tatsumi, Hideo; and Kanamaru, Hisanobu, 4,295,553, Cl. 192-84.00C.
- Taylor, Clyde G.: See—
Jenkins, Randall C.; Taylor, Clyde G.; Turner, Robert B.; and Ridgway, Donald H., 4,296,159, Cl. 428-95.000.
- Taylor, Leslie L., Jr.: See—
Killmeyer, Charles W., deceased; Killmeyer, Elizabeth A., administrator; Lane, James E.; Taylor, Leslie L., Jr.; and Pearson, Joe T., 4,296,060, Cl. 264-137.000.
- Taylor, Raymond C.: See—
Richards, Frank P.; and Taylor, Raymond C., 4,295,838, Cl. 493-105.000.
- TDK Electronics Co., Ltd.: See—
Toda, Kohji, 4,296,348, Cl. 310-334.000.
- Teegarden, Derylle L.: See—
Penn, Eric J.; and Teegarden, Derylle L., 4,295,258, Cl. 29-283.000.
- Teepak, Inc.: See—
Trimble, Roy L.; Story, Alfred D.; and Martinek, Harold H., 4,295,247, Cl. 17-1.00R.
- Teetz, Wolfgang: See—
Desprez, Alfred; Sauerland, Heinz; and Teetz, Wolfgang, 4,295,433, Cl. 112-241.000.
- Teichmann, Paul: See—
Beneke, Wolfgang; and Teichmann, Paul, 4,295,248, Cl. 19-113.000.
- Teijin Limited: See—
Emi, Shingo; and Saiki, Noritsugu, 4,296,163, Cl. 428-212.000.
- Hara, Shigeyoshi; and Yamada, Tateyoshi, 4,296,218, Cl. 525-439.000.

- Teijin Seiki Company, Limited: See—
Kamimura, Toshio, 4,295,413, Cl. 92-5.00L.
- Tektronix, Inc.: See—
Hofer, Bruce E., 4,296,381, Cl. 330-149.000.
- Telecommunications Radioelectriques et Telephoniques T.R.T.: See—
Jeandot, Jean-Louis; and Lefort, Emmanuel, 4,296,383, Cl. 330-301.000.
- Tellis, Cyril B. Separation of hydrogen chloride from gaseous mixtures. 4,296,078, Cl. 423-240.000.
- Temme, Karl: See—
Walther, Carl K.; and Temme, Karl, 4,295,300, Cl. 51-163.200.
- Temple, John W., Jr. Corrosion resistant fastener. 4,295,767, Cl. 411-377.000.
- Tennant Company: See—
Bricher, Charles W.; and Herpers, Ferdinand J., 4,295,274, Cl. 30-347.000.
- Herpers, Ferdinand J.; Kroll, Harley E.; Carlson, Alfred D.; and Dodge, Paul D., 4,295,244, Cl. 15-320.000.
- Teramura, Hiroichi; Yamazaki, Yasuhiro; Wakahara, Yasushi; Hattori, Naohiko; Yamamoto, Seiichi; and Nakao, Kouzo, to Kokusai Den-shin Denwa Co., Ltd. Digital signal control system in a facsimile communication. 4,296,439, Cl. 358-257.000.
- Teranishi, Katsuya: See—
Saito, Cuyichi; and Teranishi, Katsuya, 4,295,556, Cl. 198-325.000.
- Teranuma, Jun: See—
Yasuhara, Seishi; Teranuma, Jun; Shinzawa, Motohiro; and Fujii, Hiroshi, 4,295,455, Cl. 123-569.000.
- Terao, Motoyasu; Shigematsu, Kazuo; Ojima, Masahiro; and Yonezawa, Seiji, to Hitachi, Ltd. Member for recording information. 4,296,419, Cl. 346-135.100.
- Terrell Machine Company, The: See—
Niederer, Kurt W., 4,295,569, Cl. 209-634.000.
- Terry Corporation: See—
Dussourd, Jules L.; and Pfannebecker, George W., 4,295,788, Cl. 415-202.000.
- Terry, Robert R.; and Boone, Jacob J., to Nordson Corporation. Method of obtaining a seal upon the interior surface of a container closure and resulting product. 4,295,573, Cl. 215-348.000.
- Tew, William: See—
Smith, Leslie; Tew, William; and Woolley, Jack, 4,296,458, Cl. 361-433.000.
- Texaco Inc.: See—
Cuscirida, Michael; and Speranza, George P., 4,296,213, Cl. 521-166.000.
- Gass, John C.; Kerr, Noel C.; and Pittmann, Robert W., 4,295,795, Cl. 417-111.000.
- Texas Instruments Incorporated: See—
Boulanger, Henry J.; Lowell, Victor; and Whipple, Elliot, 4,296,287, Cl. 200-83.00P.
- Garcia, Felix, Jr.; Hergert, Roger A.; Mann, Don C.; and Brown, Sheldon H., 4,296,448, Cl. 360-135.000.
- Penn, Thomas C., 4,296,146, Cl. 427-58.000.
- Rogers, Gerald D., 4,295,264, Cl. 29-571.000.
- Tubbs, Graham S.; and Ponder, James E., 4,295,897, Cl. 148-1.500.
- Weirauch, Donald F., 4,296,347, Cl. 310-313.00B.
- Texasgulf Inc.: See—
Saville, James, 4,295,881, Cl. 75-10.00R.
- Texton Inc.: See—
DeCaro, Charles J., 4,295,394, Cl. 81-57.370.
- Th. Kieserling & Albrecht: See—
Schweer, Wilhelm, 4,295,397, Cl. 82-20.000.
- Thaxter, James B., to Sperry Corporation. Magnetic toner apparatus. 4,295,442, Cl. 118-657.000.
- Thermoplastics, Inc.: See—
Grote, Daniel; Raymond, Duane; and Mosher, Joseph C., 4,295,262, Cl. 29-462.000.
- Theta Corporation: See—
Rodriguez, Edward T., 4,296,331, Cl. 250-551.000.
- Theurer, Josef; and Riessberger, Klaus, to Franz Plasser Bahnbaumaschinen-Industriegesellschaft m.b.H. Mobile machine for removing surface irregularities from rail heads. 4,295,764, Cl. 409-296.000.
- Thiokol Corporation: See—
Adams, Gary V.; and Schneider, Fred E., 4,296,084, Cl. 423-351.000.
- Thizy, Andre; Poignant, Pierre; and Pilon, Daniel, to Philagro. Selective herbicidal method in cotton and soybeans. 4,295,877, Cl. 71-120.000.
- Thomas & Betts Corporation: See—
Narozny, Ronald S.; and Wyss, Robert P., 4,295,704, Cl. 339-99.00R.
- Thomas De La Rue & Company Limited: See—
Haslop, John M.; Knapman, Reginald G.; and West, Michael A., 4,296,326, Cl. 250-372.000.
- Thomas, James R.: See—
Johnson, Harry D.; Campbell, Christopher J.; Turner, Thomas O.; Poole, Carl W.; Gilmore, James E.; and Thomas, James R., 4,295,337, Cl. 62-54.000.
- Thomas, James S., to Motorola, Inc. Power on and low voltage reset circuit. 4,296,338, Cl. 307-362.000.
- Thomas, Rudolf: See—
Stetter, Jorg; Diggins, Klaus; Thomas, Rudolf; Eue, Ludwig; and Schmidt, Robert R., 4,295,876, Cl. 71-90.000.
- Thompson, John R.: See—
Robinson, Bruce A.; and Thompson, John R., 4,295,252, Cl. 28-248.000.
- Thomson-Brandt: See—
Rilly, Gerard, 4,296,360, Cl. 315-387.000.
- Thomson CSF: See—
Bursztejn, Jacques, 4,296,495, Cl. 371-22.000.
- Gilles, Jean, 4,296,426, Cl. 357-23.000.
- Lacombat, Michel; and Gerard, Andre, 4,295,735, Cl. 355-43.000.
- Thomson, George M.; and Jamison, Keith A., to United States of America, Army. Flowing gas discharge source of vacuum ultra-violet line radiation system. 4,296,330, Cl. 250-504.00R.
- Thorington, Luke: See—
Trutner, Donald G.; and Thorington, Luke, 4,295,873, Cl. 65-108.000.
- Thunker, Norbert, to Heidelberger Druckmaschinen Aktiengesellschaft. Camless drive of a swinging pre-gripper feeder. 4,295,422, Cl. 101-232.000.
- Thuzimoto, Shigenori: See—
Okumichi, Toshiharu; Oseto, Osamu; Matsumoto, Keizo; Thuzimoto, Shigenori; and Sanda, Hisanari, 4,296,012, Cl. 260-29.6XA.
- Tijburg, Rudolf P.; de Waard, Peter J.; and van Dongen, Teunis, to U.S. Philips Corporation. Semiconductor injection laser having a movable laser beam. 4,296,386, Cl. 331-94.50H.
- Timex Corporation: See—
Wilson, Robert, 4,295,516, Cl. 164-464.000.
- Toa Nenryo Kogyo Kabushiki Kaisha: See—
Mikami, Takashi; Fujii, Shigeo; Okano, Shuji; and Ikeda, Tokuzo, 4,295,809, Cl. 425-72.00S.
- TOA Valve Co. Ltd.: See—
Hagihara, Noboru, 4,296,307, Cl. 219-121.0ED.
- Tochio, Yoshihiko: See—
Yoshida, Masakatsu; Tochio, Yoshihiko; and Tohi, Atsumoto, 4,295,898, Cl. 148-1.500.
- Toda, Kohji, to TDK Electronics Co., Ltd., a part interest. Interdigitated electrode ultrasonic transducer. 4,296,348, Cl. 310-334.000.
- Tohi, Atsumoto: See—
Yoshida, Masakatsu; Tochio, Yoshihiko; and Tohi, Atsumoto, 4,295,898, Cl. 148-1.500.
- Tohzu, Takashi: See—
Ohsaka, Yohnosuke; and Tohzu, Takashi, 4,296,265, Cl. 570-138.000.
- Tokuda, Kuniaki: See—
Kasahara, Shizuka; Yamanishi, Kazuhiko; Hanada, Toshiro; Tokuda, Kuniaki; and Kobatake, Shinzo, 4,295,853, Cl. 23-230.00B.
- Tokyo Juki Industrial Co., Ltd.: See—
Uemura, Tamio; Ito, Yoshimasa; and Itakura, Takahiro, 4,295,435, Cl. 112-322.000.
- Tokyo Shibaura Denki Kabushiki Kaisha: See—
Hirata, Akio, 4,296,367, Cl. 318-808.000.
- Takeuchi, Kiyoyuki, 4,295,565, Cl. 206-455.000.
- Tsuji, Shigeo; and Aikawa, Takahisa, 4,296,316, Cl. 250-204.000.
- Yanabu, Satoru; Mizoguchi, Hitoshi; and Simogawara, Naoki, 4,296,288, Cl. 200-146.00R.
- Tokyo Shibaura Electric Co., Ltd.: See—
Ishii, Takashi; Nishida, Katsutoshi; Komatsu, Michiyasu; and Tsuge, Akihiko, 4,296,065, Cl. 264-325.000.
- Takeuchi, Minami; and Kuriki, Minoru, 4,296,427, Cl. 357-39.000.
- Tolliver, Wilbur E. Variegated stirrup mat. 4,295,497, Cl. 138-175.000.
- Tolliver, Wilbur E. Spacer bar and related method for concrete pipe manufacture. 4,295,501, Cl. 140-92.100.
- Tomaro, Patrick M., deceased (by Tomaro, Rita, executrix), to Conair Corporation. Air diffuser for a hair dryer. 4,295,283, Cl. 34-97.000.
- Tomaro, Rita, executrix: See—
Tomaro, Patrick M., deceased, 4,295,283, Cl. 34-97.000.
- Tomic, Dobrovoje. Material as spongiosacment with effervescent reabsorptive effect. 4,296,209, Cl. 521-85.000.
- Tominaga, Akira, to Kansai Paint Co., Ltd. Resin composition for cationic electrodeposition paints. 4,296,010, Cl. 260-29.2TN.
- Tomisawa, Setsuo: See—
Ishikawa, Akira; Ishida, Yukihito; Ikegami, Shiro; Satoh, Hiroshi; Sato, Ryuchi; Tomisawa, Setsuo; and Toyoshima, Shigeru, 4,296,123, Cl. 424-287.000.
- Tomov, Nenad R.; and Roberts, Geoffrey M., to Diamond Shamrock Technologies S.A. Process for the electrolytic production of manganese dioxide. 4,295,943, Cl. 204-96.000.
- Tomy Kogyo Co., Inc.: See—
Konta, Yukio, 4,295,651, Cl. 273-121.00D.
- Toray Industries, Inc.: See—
Nakanishi, Toshiharu; Suzuki, Miyo; and Ohigashi, Hiroji, 4,296,349, Cl. 310-335.000.
- Saito, Tasuku; Noma, Tutomu; Matsunaga, Tsutomu; Naito, Nagayoshi; Tanaka, Chiaki; and Hiratsuka, Motoki, 4,295,652, Cl. 273-235.00R.
- Tordoff, William L., to Ashland Oil, Inc. Automatic cone and mold-making machine. 4,295,515, Cl. 164-158.000.
- Toro Company, The: See—
Stevens, Eric, 4,295,285, Cl. 37-43.00D.
- Torregrassa, Louis O.: See—
Bentvelzen, Jozef M.; Meredith, Michael D.; Bepple, Henry; Torregrassa, Louis O.; Battan, Howard R.; and Justice, Dennis H., 4,295,925, Cl. 162-19.000.
- Bentvelzen, Jozef M.; Meredith, Michael D.; Bepple, Henry; Torregrassa, Louis O.; Battan, Howard R.; and Justice, Dennis H., 4,295,926, Cl. 162-57.000.

- Bentvelzen, Jozef M.; Meredith, Michael D.; Beppie, Henry; Torregrossa, Louis O.; Batten, Howard R.; and Justice, Dennis H., 4,295,927, Cl. 162-57.000.
- Torzala, Terence A., to Air Shields, Inc. Probe and system for detecting probe dislodgement. 4,295,475, Cl. 128-736.000.
- Toshiba Corporation: See—
Fukatsu, Akihiro; and Tada, Isao, 4,296,355, Cl. 315-39.510.
Kohyama, Mitsuaki, 4,295,443, Cl. 118-657.000.
- Toshin Kogyo Co. Ltd.: See—
Yoshikawa, Takaharu, 4,296,365, Cl. 318-632.000.
- Toti, Gabriele; Lenzi, Giuliano; and Monti, Paolo, to Alfa Romeo S.p.A. Active suspensions assembly for a motor car. 4,295,660, Cl. 280-714.000.
- Toulan, Roy D., Jr.: See—
Dennesen, Francis G.; Wilson, Richard S.; Toulan, Roy D., Jr.; and Madnick, Peter, 4,295,277, Cl. 33-181.00R.
- Towmotor Corporation: See—
Hildebrecht, Harold V., 4,295,540, Cl. 180-271.000.
Malecha, Richard J., 4,295,541, Cl. 180-315.000.
- Toyo Kogyo Co., Ltd.: See—
Iida, Yoshihiko, 4,295,454, Cl. 123-556.000.
- Toyo Seikan Kaisha Limited: See—
Matsubayashi, Hiroshi; Tsurumaru, Michiko; Horiguchi, Makoto; Ueno, Hiroshi; and Kitamura, Yoichi, 4,296,182, Cl. 428-629.000.
- Toyo Soda Manufacturing Co., Ltd.: See—
Satoh, Takao; and Seita, Toru, 4,295,944, Cl. 204-98.000.
- Toyoda Koki Kabushiki Kaisha: See—
Sugata, Yoshiaki; and Miyagawa, Kiyoshi, 4,295,398, Cl. 82-31.000.
- Toyooki Kogyo Kabushiki Kaisha: See—
Hiei, Shoki, 4,295,545, Cl. 184-55.00A.
- Toyoshima, Shigeru: See—
Ishikawa, Akira; Ishida, Yukihito; Ikegami, Shiro; Satoh, Hiroshi; Sato, Ryuichi; Tomisawa, Setsuo; and Toyoshima, Shigeru, 4,296,123, Cl. 424-287.000.
- Toyota Jidosha Kogyo Kabushiki Kaisha: See—
Nomura, Etsuji; Matsui, Kazuma; Miyazaki, Toshikuni; Sami, Hiroshi; and Ueda, Tatehito, 4,295,456, Cl. 123-569.000.
Shibatani, Juichi; Nakamura, Kenichi; Izuhara, Wataru; and Obu, Yuichiro, 4,295,549, Cl. 188-218.00A.
- Tracor, Inc.: See—
Anderson, Rollen J., 4,295,856, Cl. 23-232.00E.
- Trautweiler, Franz, to Ciba-Geigy AG. Photographic process using a thin flexuous layer and reflective layer. 4,296,198, Cl. 430-403.000.
- Travnicek, Jiri: See—
Kupf, Lubomir; Travnicek, Jiri; Adamek, Radomil; and Kyzlink, Josef, 4,295,628, Cl. 249-80.000.
- Tredennick, Harry L.: See—
Gunter, Thomas G.; Tredennick, Harry L.; and McAlister, Doyle V., 4,296,469, Cl. 364-200.000.
- Tri/Valley Growers: See—
Jaquith, Jack B.; and Church, Allen R., 4,296,140, Cl. 426-575.000.
- Trimble, John: See—
McGowan, John B.; and Trimble, John, 4,295,494, Cl. 138-89.000.
- Trimble, Roy L.; Story, Alfred D.; and Martinek, Harold H., to Teepak, Inc. Gripper-separator device for continuously shirred casings. 4,295,247, Cl. 17-1.00R.
- Trishevsky, Igor S.: See—
Anisimov, Vyacheslav I.; Bulgakov, Evgeny G.; Gurin, Vasily N.; Radjuevich, Leonid V.; Trishevsky, Igor S.; Trishevsky, Oleg I.; Kheifets, Grigory R.; and Jurchenko, Anatoly B., 4,295,353, Cl. 72-180.000.
- Trishevsky, Oleg I.: See—
Anisimov, Vyacheslav I.; Bulgakov, Evgeny G.; Gurin, Vasily N.; Radjuevich, Leonid V.; Trishevsky, Igor S.; Trishevsky, Oleg I.; Kheifets, Grigory R.; and Jurchenko, Anatoly B., 4,295,353, Cl. 72-180.000.
- Trouet, Andre B. L.: See—
Baurain, Roger M.; and Trouet, Andre B. L., 4,296,105, Cl. 424-180.000.
- Trutner, Donald G.; and Thorington, Luke, to Duro-Test Corporation. Method and apparatus for reworking a hollow workpiece. 4,295,873, Cl. 65-108.000.
- Trutzschler GmbH & Co. KG: See—
Beneke, Wolfgang; and Teichmann, Paul, 4,295,248, Cl. 19-113.000.
- TRW Inc.: See—
Barth, Charles F.; Stelson, Thomas S.; and Blake, David E., 4,295,301, Cl. 51-165.880.
Harrington, Alan L.; Rodov, Vladimir; and Allison, Richard, 4,295,267, Cl. 29-571.000.
Richardson, Warren N., 4,296,286, Cl. 200-61.540.
- Trzeciak, Kurt M.: See—
Cruse, Gary M.; and Trzeciak, Kurt M., 4,295,535, Cl. 175-101.000.
- Tsang, Floris Y.: See—
Anand, Joginder N.; Revak, Timothy T.; and Tsang, Floris Y., 4,296,052, Cl. 264-25.000.
- Tsuchida, Kensaku; and Karasawa, Shinji, to Matsushita Electric Industrial Co., Ltd. Method for making intercell connections in multi-cell storage battery. 4,296,303, Cl. 219-78.130.
- Tsuchida, Yasuhiro: See—
Kuraoka, Yasuo; and Tsuchida, Yasuhiro, 4,295,339, Cl. 62-64.000.
- Tsuchiya, Kunihiko: See—
Tanaka, Naoki; Tsuchiya, Kunihiko; and Nishizawa, Toshizo, 4,295,806, Cl. 418-97.000.
- Tsuda, Hiroshi; Miyashita, Kiyoshi; Nishikawa, Masaji; Shimizu, Akira; and Kasuga, Muneo, to Olympus Optical Company Ltd. Filter assembly for collecting used toner of electrophotographic copying machine. 4,295,734, Cl. 355-15.000.
- Tsuge, Akihiko: See—
Ishii, Takashi; Nishida, Katsutoshi; Komatsu, Michiyasu; and Tsuge, Akihiko, 4,296,065, Cl. 264-325.000.
- Tsuji, Setsuo: See—
Sakaguchi, Tadahiyo; Hino, Masamichi; Tsuji, Setsuo; Hashido, Akiyoshi; and Enomoto, Kazuyoshi, 4,295,915, Cl. 156-361.000.
- Tsuji, Shigeo; and Aikawa, Takahisa, to Tokyo Shibaura Denki Kabushiki Kaisha. Optical focusing device. 4,296,316, Cl. 250-204.000.
- Tsunekawa, Tokuchi: See—
Takashi, Uchiyama; Tsunekawa, Tokuchi; and Kiyohara, Takehiko, 4,295,722, Cl. 354-146.000.
- Tsuneta, Kazuyoshi: See—
Hayashi, Masaaki; Sasaki, Hiroharu; and Tsuneta, Kazuyoshi, 4,296,014, Cl. 260-29.6NR.
- Tsurumaru, Michiko: See—
Matsubayashi, Hiroshi; Tsurumaru, Michiko; Horiguchi, Makoto; Ueno, Hiroshi; and Kitamura, Yoichi, 4,296,182, Cl. 428-629.000.
- Tu, Hosheng, to UOP Inc. Attenuation of metal contaminants on cracking catalyst with a boron compound. 4,295,955, Cl. 208-120.000.
- Tubbs, Graham S.; and Ponder, James E., to Texas Instruments Incorporated. Method of making CMOS integrated circuit device. 4,295,897, Cl. 148-1.500.
- Tucker, Samuel M.: See—
McAvinn, James D.; Meister, Arthur R.; and Tucker, Samuel M., 4,295,537, Cl. 177-15.000.
- Turchetti, Gianni: See—
Mezzanotte, Mario; and Turchetti, Gianni, 4,295,511, Cl. 152-354.00R.
- Turco, Vincenzo L.: See—
Genco, Vito; and Turco, Vincenzo L., 4,295,426, Cl. 102-451.000.
- Turenko, Leonid G.: See—
Shopin, Viktor M.; Turenko, Leonid G.; Surovikin, Vitaly F.; and Suponev, Konstantin V., 4,295,867, Cl. 55-288.000.
- Turner, Robert B.: See—
Jenkins, Randall C.; Taylor, Clyde G.; Turner, Robert B.; and Ridgway, Donald H., 4,296,159, Cl. 428-95.000.
- Turner, Thomas O.: See—
Johnson, Harry D.; Campbell, Christopher J.; Turner, Thomas O.; Poole, Carl W.; Gilmore, James E.; and Thomas, James R., 4,295,337, Cl. 62-54.000.
- Tutty, Geoffrey C., to INCA Limited. Image wise developable system. 4,295,662, Cl. 282-27.500.
- Tyco Industries, Inc.: See—
Brand, Derek A.; and Brand, Derek R., 4,295,295, Cl. 46-259.000.
- Tyco Laboratories: See—
Blinow, Donald W.; Cassidy, Kevin H.; and Dominey, Samuel C., Jr., 4,296,321, Cl. 250-254.000.
- Tyler Refrigeration Corporation: See—
Abraham, Faye F., 4,295,340, Cl. 62-82.000.
- Uchida, Sakae, to Setagayaseiki Co. Ltd. Motorized dental handpiece. 4,295,830, Cl. 433-115.000.
- Udayasekaran, Rajasekaran, to Northern Telecom Limited. Static, solid state originating register compatible with an electromechanical telephone cross-bar switching system. 4,296,281, Cl. 179-18.00E.
- Ueda, Hideo: See—
Kawamura, Toshio; Harashima, Noboru; Ueda, Hideo; and Sano, Seijiro, 4,295,654, Cl. 277-92.000.
- Ueda, Tatehito: See—
Nomura, Etsuji; Matsui, Kazuma; Miyazaki, Toshikuni; Sami, Hiroshi; and Ueda, Tatehito, 4,295,456, Cl. 123-569.000.
- Uemura, Tamio; Ito, Yoshimasa; and Itakura, Takahiro, to Tokyo Juki Industrial Co., Ltd. Cloth feed apparatus. 4,295,435, Cl. 112-322.000.
- Ueno, Hiroshi: See—
Matsubayashi, Hiroshi; Tsurumaru, Michiko; Horiguchi, Makoto; Ueno, Hiroshi; and Kitamura, Yoichi, 4,296,182, Cl. 428-629.000.
- Uerdinger, Walter: See—
Pedain, Josef; Uerdinger, Walter; and Muller, Hans-Jurgen, 4,296,230, Cl. 528-67.000.
- UMAC, Inc.: See—
McGowan, John B.; and Trimble, John, 4,295,494, Cl. 138-89.000.
- Umezawa, Hamao; Okami, Yoshiro; and Kondo, Shinichi, to Zaidan Hojin Biseibutsu Kagaku Kenkyu Kai. Istamycins and production thereof. 4,296,106, Cl. 424-181.000.
- Umezawa, Kazushige: See—
Arima, Ryoji; Umezawa, Kazushige; and Nisugi, Tokuzo, 4,295,882, Cl. 75-52.000.
- Ungermann, Dieter: See—
Weiss, Erich; and Ungermann, Dieter, 4,296,071, Cl. 73-864.110.
- Union Carbide Corporation: See—
Lustig, Stanley; and Vicik, Stephen J., 4,296,156, Cl. 428-35.000.
- Maresca, Louis M.; Gill, Peter J.; and Berger, Mitchell H., 4,296,232, Cl. 528-179.000.
- Vasudevan, Ganapathy; and Lustig, Stanley, 4,296,142, Cl. 427-28.000.
- Union Oil Company of California: See—
Dhondt, Roland O., 4,295,773, Cl. 414-187.000.
- Union Special Corporation: See—
Hsiao, James C., 4,295,434, Cl. 112-314.000.
- United States Gypsum Company: See—
Nelson, David M., 4,295,299, Cl. 49-504.000.

- United States of America
- Agriculture: See—
Camirand, Wayne M.; Randall, John M.; and Hautala, Earl, 4,295,333, Cl. 60-641.600.
- America: See—
Angwin, Meredith J.; Pfeifferle, William C.; and Kesseling, John P., 4,295,818, Cl. 431-7.000.
- Simons, S. Stoney, Jr., 4,296,206, Cl. 435-240.000.
- Army: See—
F'Geppert, Erwin, 4,295,750, Cl. 403-259.000.
- Oswell, Herman R., 4,295,617, Cl. 244-3.290.
- Thomson, George M.; and Jamison, Keith A., 4,296,330, Cl. 250-504.00R.
- Zura, Boris, 4,295,379, Cl. 73-862.620.
- Energy: See—
Cookson, Alan H., 4,296,274, Cl. 174-142.000.
- Franks, Larry A.; and Nelson, Melvin A., 4,296,319, Cl. 250-227.000.
- Health and Human Services: See—
Fraser, David R., 4,295,730, Cl. 354-325.000.
- Interior: See—
Khalafalla, Sanaa E.; and Reimers, George W., 4,295,971, Cl. 210-695.000.
- Paice, Derek A.; and Shimp, Alan B., 4,296,450, Cl. 361-50.000.
- National Aeronautics and Space Administration: See—
Bill, Robert C.; and Ludwig, Lawrence P., 4,295,786, Cl. 415-174.000.
- Navy: See—
De Matteo, John; and Villani, Frank, 4,295,372, Cl. 73-382.00G.
- Green, Milton, 4,296,487, Cl. 367-169.000.
- Haberl, John B., 4,296,345, Cl. 310-219.000.
- Klein, Philipp H.; Addamiano, Arrigo; and Allen, Roger, 4,295,989, Cl. 252-301.40F.
- Sergev, Sergius S.; and Roster, Theodore J., 4,295,604, Cl. 236-21.00R.
- U.S. Philips Corporation: See—
Bodart, Robert; and Werts, Jean P. A. R. J., 4,296,493, Cl. 370-48.000.
- Degger, Wolter W. J.; and Van Kasteren, Adrianus C., 4,295,625, Cl. 248-466.000.
- Franken, Adrianus J. J.; Khoe, Giok D.; and Kuppers, Dieter, 4,296,143, Cl. 427-38.000.
- Geurts, Martinus F. A. M., 4,296,437, Cl. 358-173.000.
- Nederlof, Leendert; and Salters, Roelof H. W., 4,296,475, Cl. 364-900.000.
- Tijburg, Rudolf P.; de Waard, Peter J.; and van Dongen, Teunis, 4,296,386, Cl. 331-94.50H.
- United Technologies Corporation: See—
Licht, Lazar, 4,295,689, Cl. 308-9.000.
- Manning, Frank B., 4,295,784, Cl. 415-162.000.
- Melanson, Donald G., 4,295,666, Cl. 285-14.000.
- Meltz, Gerald; and Snitzer, Elias, 4,295,738, Cl. 356-32.000.
- Meltz, Gerald; and Snitzer, Elias, 4,295,739, Cl. 356-43.000.
- Moffatt, E. Marston, 4,295,373, Cl. 73-505.000.
- Palma, Gary E.; and Mottier, Francois M., 4,295,741, Cl. 356-349.000.
- Rannenberg, George C., 4,295,518, Cl. 165-2.000.
- Wynosky, Thomas A.; and Campbell, Charles A., 4,295,611, Cl. 239-265.370.
- University of Minnesota, The Regents of the: See—
Condie, Richard M., 4,296,027, Cl. 260-112.00B.
- Unlimited Steel Fabricators, Inc.: See—
Stokes, Richard P.; and Stokes, William, 4,295,352, Cl. 72-57.000.
- UOP Inc.: See—
Antos, George J., 4,295,959, Cl. 208-138.000.
- Antos, George J., 4,295,960, Cl. 208-139.000.
- Benson, Henry E.; and Moravec, Terrence D., 4,295,918, Cl. 156-434.000.
- Carlson, David H. J., 4,295,993, Cl. 252-430.000.
- Carson, Don B., 4,296,261, Cl. 568-890.000.
- Childs, Michael E., 4,295,860, Cl. 44-63.000.
- Graves, Kevin, 4,295,627, Cl. 248-588.000.
- Gregory, Leslie A., 4,295,681, Cl. 297-284.000.
- Kulprathipanja, Santi, 4,295,994, Cl. 252-430.000.
- Tu, Hosheng, 4,295,955, Cl. 208-120.000.
- Upchurch, Lonnie W., to Advanced Marine Concepts, Inc. Pontoon boat. 4,295,236, Cl. 9-2.00S.
- Upjohn Company, The: See—
Axen, Udo F.; and Sih, John C., 4,296,253, Cl. 564-153.000.
- Ewen, James H.; and McClellan, Thomas R., 4,296,212, Cl. 521-163.000.
- Hester, Jackson B., Jr., 4,296,239, Cl. 546-271.000.
- Sih, John C., 4,296,041, Cl. 260-345.200.
- Sih, John C., 4,296,246, Cl. 562-503.000.
- Sih, John C., 4,296,247, Cl. 562-503.000.
- Sih, John C., 4,296,248, Cl. 562-503.000.
- Sih, John C., 4,296,249, Cl. 562-503.000.
- Sih, John C., 4,296,250, Cl. 562-503.000.
- Sih, John C., 4,296,256, Cl. 568-330.000.
- USM Corporation: See—
Skierski, Edwin J., 4,295,768, Cl. 411-387.000.
- Vacmetal Gesellschaft fur Vakuum-Metallurgie mbH: See—
Zahs, Gernot; and Wahle, Hans-Jurgen, 4,295,667, Cl. 285-18.000.
- Vaeth, Guenter: See—
Rudolf, Peter; Steck, Werner; Jakusch, Helmut; Vaeth, Guenter; and Jaechk, Christof, 4,296,149, Cl. 427-130.000.
- Valembos, Pierre V.: See—
Maby, Edward W.; Kawamoto, Hirohisa; and Valembos, Pierre V., 4,296,144, Cl. 427-38.000.
- Vanderheyden, Eric E.; and Casciotti, Albert, to AMP Incorporated. Solderless filter mounting for header assemblies. 4,296,390, Cl. 333-182.000.
- van der Meulen, Leonard. Device for stacking thin-walled bags. 4,295,644, Cl. 270-60.000.
- van Dongen, Teunis: See—
Tijburg, Rudolf P.; de Waard, Peter J.; and van Dongen, Teunis, 4,296,386, Cl. 331-94.50H.
- Van Kasteren, Adrianus C.: See—
Degger, Wolter W. J.; and Van Kasteren, Adrianus C., 4,295,625, Cl. 248-466.000.
- Van Linge, Douwe J.: See—
Ladage, Cornelis A.; Van Linge, Douwe J.; and Van Riessen, Huibert A., 4,296,131, Cl. 424-347.000.
- Van Ness, Bradford O.: See—
Weimer, Dan G.; and Van Ness, Bradford O., 4,296,315, Cl. 235-460.000.
- Van Riessen, Huibert A.: See—
Ladage, Cornelis A.; Van Linge, Douwe J.; and Van Riessen, Huibert A., 4,296,131, Cl. 424-347.000.
- Van Tielen, Willem R. Modular tower and method of constructing same. 4,295,317, Cl. 52-637.000.
- Varian Associates, Inc.: See—
Griesenauer, Neal M.; and Gersi, Julius J., 4,296,178, Cl. 428-462.000.
- Neubauer, Michael L., 4,296,354, Cl. 315-3.500.
- Welch, Kimo M., 4,295,338, Cl. 62-55.500.
- Varma, Brajendra P., to Eltra Corporation. Method for battery plate. 4,295,940, Cl. 204-2.100.
- Vas, Ran: See—
Diamond, George; Forrester, James; Hirsch, Michael; and Vas, Ran, 4,295,473, Cl. 178-695.000.
- Vasilantone, Michael. Infrared dryer. 4,295,826, Cl. 432-185.000.
- Vasile, Carmine F., to Rockwell International Corporation. Shielded electromagnetic acoustic transducers. 4,296,486, Cl. 367-140.000.
- Vasudevan, Ganapathy; and Lustig, Stanley, to Union Carbide Corporation. Method for coating a tubular food casing. 4,296,142, Cl. 427-28.000.
- Vaughan, Thomas W.: See—
Etzold, Roland; Impellizzeri, Julius S.; and Vaughan, Thomas W., 4,295,557, Cl. 198-382.000.
- VDO Adolf Schindling AG: See—
Hahlgans, Gunter, 4,296,457, Cl. 361-413.000.
- VEB Kombinat Polygraph "Werner Lamberz": See—
Johns, Hans; Muller, Wolfgang; Jentsch, Arndt; and Schumann, Gunter, 4,295,423, Cl. 101-349.000.
- Veeder Industries Inc.: See—
Stifano, Vincent A., Jr., 4,295,395, Cl. 81-121.00R.
- Veit Dennert KG Baustoffbetriebe: See—
Dennert, Heinz; and Dennert, Hans V., 4,295,810, Cl. 425-110.000.
- Venuti, Michael C.: See—
Muchowski, Joseph M.; and Venuti, Michael C., 4,296,042, Cl. 260-345.90R.
- Verbeek, Antonie E.; and Mattheij, Jozef M. J., to J. T. Baker Chemicals B.V. Reagent for the quantitative determination of water. 4,295,990, Cl. 252-408.000.
- Vereckey, Endre: See—
Takacs, Istvan; Banos, Zoltan; Illes, Janos; Vereckey, Endre; Rudolf, Peter; and Kerey, Gyorgy, 4,296,072, Cl. 422-254.000.
- Verma, Dharmvir S. Cell culture and continuous dialysis flask and method. 4,296,205, Cl. 435-240.000.
- Vibronex, Robert D.: See—
Comizzoli, Robert B.; and Vibronex, Robert D., 4,296,370, Cl. 324-54.000.
- Vicik, Stephen J.: See—
Lustig, Stanley; and Vicik, Stephen J., 4,296,156, Cl. 428-35.000.
- Vickers Limited: See—
Harper, Terence; and Gates, Allen P., 4,296,194, Cl. 430-176.000.
- Victoreen, Inc.: See—
Miller, Samuel, 4,296,320, Cl. 250-252.000.
- Viklund, Ake E., to Aktiebolaget Electrolux. Knocked-down cabinet. 4,295,693, Cl. 312-257.00R.
- Villani, Frank: See—
De Matteo, John; and Villani, Frank, 4,295,372, Cl. 73-382.00G.
- Vincek, Robert C., to Becton, Dickinson and Company. Air-evacuated package with vacuum integrity indicator means. 4,295,566, Cl. 206-457.000.
- Vinings Chemical Company: See—
Hauser, H. William, 4,296,079, Cl. 423-242.000.
- Visconti, James. Simulated gem. 4,295,347, Cl. 63-32.000.
- Vock, Manfred H.: See—
Wieggers, Wilhelmus J.; Sprecker, Mark A.; Watkins, Hugh; Vock, Manfred H.; and Schmitt, Frederick L., 4,295,978, Cl. 252-8.900.
- Voest-Alpine Aktiengesellschaft: See—
Ganglbauer, Otto; Wallner, Felix; Scheidl, Helmut; Reindl, Hermann; and Frielinghaus, Rainer, 4,295,375, Cl. 73-582.000.
- Vogel, William D.: See—
Luerken, Adolf; and Vogel, William D., 4,295,753, Cl. 403-365.000.

- Vogler, Lynda L.: See—
Dubink, David T.; and Vogler, Lynda L., 4,295,683, Cl. 297-377.000.
- Voirol, Felix: See—
Guex, Woldemar; Klacui, Heinrich; Pauling, Horst; and Voirol, Felix, 4,295,517, Cl. 165-1.000.
- Voith Getriebe KG.: See—
Helfer, Friedrich; Elsner, Ernst; and Zaiser, Wolfgang, 4,295,348, Cl. 64-27.00L.
- Volkswagenwerk Aktiengesellschaft: See—
Kruger, Hermann, 4,295,807, Cl. 418-170.000.
Zimmermann, Frank; Heidemeyer, Paulus; and Bigalke, Erhard, 4,295,551, Cl. 192-0.076.
- Vollett, Eric M., to Holset Engineering Company Limited. Torsional vibration dampers. 4,295,546, Cl. 188-378.000.
- Volterra, Giovanna: See—
Ghelardoni, Mario; Pestellini, Vittorio; Del Soldato, Piero; Volterra, Giovanna; and Meli, Alberto, 4,296,124, Cl. 424-285.000.
- Volz, Roland: See—
Mayer, Manfred; and Volz, Roland, 4,295,937, Cl. 202-155.000.
- von Allwoerden, Wilhelm: See—
Geisthoff, Hubert; and von Allwoerden, Wilhelm, 4,295,389, Cl. 74-586.000.
- von Hellens, C. Robert: See—
Moore, Arlan G., 4,295,656, Cl. 280-87.04A.
- Vorwerk & Sohn GmbH & Co. KG.: See—
Stein, Hermann, 4,295,509, Cl. 152-158.000.
- Voss, Clifford C. Collapsible shelter. 4,295,446, Cl. 119-19.000.
- Voss, Wilfried: See—
Finsterwalder, Kurt; Philipp, Karl-Heinz; Riedisser, Gunter; and Voss, Wilfried, 4,295,399, Cl. 83-251.000.
- VPI Educational Foundation: See—
Moore, W. Edward C.; and Blanks, James A., 4,295,613, Cl. 241-2.000.
- Vroomans, Hubertus J., to Stamicarbon, B.V. Vinyl chloride polymer compositions with reduced combustibility and reduced smoke formation under conditions of fire. 4,296,023, Cl. 260-45.75F.
- Vulcan Iron Works Inc.: See—
Lerch, John A., 4,295,752, Cl. 403-317.000.
- Vysoka skola strojni a textilni: See—
Pustka, Zdenek; and Krejcir, Oldrich, 4,295,635, Cl. 254-93.0HP.
- W. R. Grace & Co.: See—
Frost, John W., 4,295,383, Cl. 474-83.000.
- Wachi, Yasuyuki: See—
Ooki, Norihiro; Motegi, Shoji; Wachi, Yasuyuki; Takikawa, Yoshio; and Yamakawa, Norio, 4,296,346, Cl. 310-242.000.
- Wacker-Chemie GmbH: See—
Innersberger, Ernst; Sommer, Oswin; Bosch, Erhard; Muller, Johann; and Schiller, August, 4,296,228, Cl. 528-33.000.
Weissgerber, Rudolf; Stoll, Alois; Kandler, Herbert; Nunner, Hans-Herbert; Eichelseder, Christine; and Pangeri, Helmut, 4,296,017, Cl. 260-30.60R.
- Wada, Yoshimasa; Yamazaki, Sigeaki; Kobayashi, Isamu; Haraguchi, Noriyuki; and Fukuda, Minoru. Apparatus for automatically transferring workpieces. 4,295,780, Cl. 414-749.000.
- Wade, Philip M.: See—
Ashfield, Herbert E.; Horsfall, Harry; and Wade, Philip M., 4,295,530, Cl. 172-7.000.
- Wagensonner, Eduard: See—
Stemme, Otto; Ruf, Wolfgang; and Wagensonner, Eduard, 4,296,438, Cl. 358-214.000.
- Wagner Electric Corporation: See—
Falk, Edward J., 4,295,336, Cl. 60-562.000.
- Wahle, Hans-Jurgen: See—
Zahs, Gernot; and Wahle, Hans-Jurgen, 4,295,667, Cl. 285-18.000.
- Wajima, Motoyo: See—
Takahashi, Akio; Itoh, Yutaka; Wajima, Motoyo; Morishita, Hirotsada; and Nishikawa, Akio, 4,296,219, Cl. 525-488.000.
- Wakahara, Yasushi: See—
Teramura, Hiroichi; Yamazaki, Yasuhiro; Wakahara, Yasushi; Hattori, Naohiko; Yamamoto, Seiichi; and Nakao, Kouzo, 4,296,439, Cl. 358-257.000.
- Wakai, Katsuro: See—
Ishikawa, Sakou; Watanabe, Yutaka; and Wakai, Katsuro, 4,296,494, Cl. 371-13.000.
- Wakisaka, Yoshiaki: See—
Sakamoto, Hitoshi; and Wakisaka, Yoshiaki, 4,296,443, Cl. 360-10.000.
- Wako Pure Chemical Industries, Ltd.: See—
Kasahara, Shizuka; Yamanishi, Kazuhiko; Hanada, Toshiro; Tokuda, Kuniaki; and Kobatake, Shinzo, 4,295,853, Cl. 23-230.00B.
- Waldhofer, Reinhard, to Krupp-Koppers GmbH. Gas generator for fine-grained coal fuels. 4,295,448, Cl. 122-164.000.
- Walsh, Gosta. Oil collecting method. 4,295,975, Cl. 210-800.000.
- Waller, William E.: See—
Albrecht, Robert D.; Presley, Michael; Waller, William E.; Cook, Gerald L.; and Presley, William E., 4,295,708, Cl. 350-289.000.
- Wallner, Felix: See—
Ganglbauer, Otto; Wallner, Felix; Scheidl, Helmut; Reindl, Hermann; and Frielinghaus, Rainer, 4,295,375, Cl. 73-582.000.
- Walser, Mackenzie, to Johns Hopkins University. The mixed salts of essential or semi-essential amino acids and nitrogen-free analogs thereof. 4,296,127, Cl. 424-319.000.
- Walter, Wolfgang, to GTE Products Corporation. Fluorescent lamp having high color rendering index. 4,296,353, Cl. 313-487.000.
- Walther, Carl K.; and Temme, Karl, to Carl Kurt Walther GmbH & Co. KG. Flap arranged on discharge and separating devices of vibratory abrasive containers. 4,295,300, Cl. 51-163.200.
- Walz, Klaus; and Fiegel, Joachim, to Bayer Aktiengesellschaft. Process for dyeing polyamide fibres. 4,295,852, Cl. 8-560.000.
- Wambach, Allen D., to General Electric Company. Reinforced thermoplastic polyester compositions having improved high voltage breakdown resistance. 4,296,021, Cl. 260-40.00R.
- Wang, Tse L.: See—
O'Neil, Joseph T.; Quinn, Thomas M.; and Wang, Tse L., 4,296,282, Cl. 179-99.0LS.
- Ward, Henry D., Jr., to Ward Machinery Company, The. Box blank folding apparatus. 4,295,841, Cl. 493-295.000.
- Ward Machinery Company, The: See—
Bell, Clinton C., 4,295,842, Cl. 493-342.000.
Ward, Henry D., Jr., 4,295,841, Cl. 493-295.000.
- Wardwell, Charles R. Frangible bonding using blush lacquer. 4,296,179, Cl. 428-498.000.
- Warner, Clifford C. Rock bolt anchor. 4,295,760, Cl. 405-259.000.
- Warner, Steven B., to Celanese Corporation. Process for the thermal stabilization of acrylic fibers. 4,295,844, Cl. 8-115.500.
- Warren, Henry R., to RCA Corporation. Magnetic recording with reduced cross-talk and interchannel time displacement. 4,296,430, Cl. 358-8.000.
- Washington Logging Equipment, Inc.: See—
Langford, Frederic E., 4,295,636, Cl. 254-304.000.
- Wason, Satish K., to J. M. Huber Corporation. Adsorbents for polyol purification. 4,296,000, Cl. 252-455.00R.
- Wasserfaller, Georg. Door lock. 4,295,349, Cl. 70-111.000.
- Watanabe, Yutaka: See—
Ishikawa, Sakou; Watanabe, Yutaka; and Wakai, Katsuro, 4,296,494, Cl. 371-13.000.
- Waterfield Engineering Limited: See—
Waterfield, Timothy O. W., 4,295,485, Cl. 137-74.000.
- Waterfield, Timothy O. W., to Waterfield Engineering Limited. Diaphragm valve. 4,295,485, Cl. 137-74.000.
- Waterman, Fred W.; McCleery, Jerry E.; and McKie, Robert T., to Morrison-Knudsen Co., Inc.; and Railcar Maint. Co. Car repair apparatus. 4,295,427, Cl. 104-32.00R.
- Watkins, Hugh: See—
Wieggers, Wilhelmus J.; Sprecker, Mark A.; Watkins, Hugh; Vock, Manfred H.; and Schmitt, Frederick L., 4,295,978, Cl. 252-8.900.
- Weber, Adolf: See—
Rhau, Siegfried; and Weber, Adolf, 4,296,180, Cl. 428-558.000.
- Weber, Charles M., to Babcock & Wilcox Company, The. Expanded cooling jacket assembly. 4,295,255, Cl. 29-157.30V.
- Weber, Ekkehard: See—
Holter, Heinz; Gresch, Heinz; Igelbuscher, Heinrich; Hubner, Kurt; and Weber, Ekkehard, 4,295,868, Cl. 55-302.000.
- Wechsung, Reiner, to Leybold-Heraeus Gesellschaft mit beschränkter Haftung. Method for analyzing organic substances. 4,296,322, Cl. 250-282.000.
- Weimer, Dan G.; and Van Ness, Bradford O., to Engineered Systems, Inc. Card reader security system. 4,296,315, Cl. 235-460.000.
- Weinberg, Ekkehard: See—
Aignesberger, Alois; Lukas, Walter; and Weinberg, Ekkehard, 4,296,089, Cl. 423-555.000.
- Weirauch, Donald F., to Texas Instruments Incorporated. Surface acoustic wave sensor. 4,296,347, Cl. 310-313.00B.
- Weisenborn, Frank L.; Brown, William E.; and Meyers, Edward, to E. R. Squibb & Sons, Inc. Antibiotic kristenin. 4,296,101, Cl. 424-119.000.
- Weisenborn, Frank L.: See—
Petrillo, Edward W., Jr.; and Weisenborn, Frank L., 4,296,033, Cl. 260-326.200.
- Weiss, Benjamin F. L., to Exploration Company. Streamer bulkhead. 4,296,481, Cl. 367-20.000.
- Weiss, Erich; and Ungermann, Dieter, to Boehringer Mannheim. Pipette with elastic bellows. 4,296,071, Cl. 73-864.110.
- Weissgerber, Rudolf; Stoll, Alois; Kandler, Herbert; Nunner, Hans-Herbert; Eichelseder, Christine; and Pangeri, Helmut, to Wacker-Chemie GmbH. Graft copolymer pressure-sensitive adhesives, their manufacture and use. 4,296,017, Cl. 260-30.60R.
- Weissman, Mark L.: See—
Petrov, Henry G.; and Weissman, Mark L., 4,295,985, Cl. 252-105.000.
- Welch, Kimo M., to Varian Associates, Inc. Cryogenic pumping apparatus with replaceable pumping surface elements. 4,295,338, Cl. 62-55.500.
- Welch, Melvin B.: See—
McDaniel, Max P.; and Welch, Melvin B., 4,295,997, Cl. 252-439.000.
- Wells, Thomas J., to Leggett & Platt, Incorporated. Coil spring assembly and forming method. 4,295,639, Cl. 267-91.000.
- Welsbach Ozone Systems Corporation: See—
Sedberry, Donald C., 4,296,397, Cl. 337-199.000.
- Wendelboe, Fred E., to Geosource Inc. Dual magnetic drive for gear meters. 4,295,369, Cl. 73-261.000.
- Wenk, Erich: See—
Kozio, Konrad; and Wenk, Erich, 4,295,942, Cl. 204-96.000.
- Wens, Johannes C., to Smit Owens Nijmegen B.V. System for sealing of kilns. 4,295,824, Cl. 432-115.000.
- Wernau, William C., to Pfizer Inc. Xanthomonas bipolymer for use in displacement of oil from partially depleted reservoirs. 4,296,203, Cl. 435-104.000.

- Werner, Alfred O.: See—
Cummings, J. Francis; and Werner, Alfred O., 4,295,461, Cl. 126-247.000.
- Wert, John A.: See—
Robertson, Wayne M.; and Wert, John A., 4,295,901, Cl. 148-12.70A.
- Werts, Jean P. A. R. J.: See—
Bodart, Robert; and Werts, Jean P. A. R. J., 4,296,493, Cl. 370-48.000.
- West, Joseph T.: See—
Guyer, James M.; and West, Joseph T., 4,296,466, Cl. 364-200.000.
- West, Michael A.: See—
Haslop, John M.; Knapman, Reginald G.; and West, Michael A., 4,296,326, Cl. 250-372.000.
- Westberg, Ake G., to H. L. Plast H. Lundvall AB. Holder for information carriers in strip form. 4,295,288, Cl. 40-16.400.
- Western Electric Company, Inc.: See—
Doten, Bradford O.; and Svitak, John J., 4,295,596, Cl. 228-180.00A.
- Gray, Vincent F., 4,295,696, Cl. 339-17.00C.
- Westinghouse Electric Corp.: See—
Smith, James D. B.; and Kauffman, Robert N., 4,296,018, Cl. 260-32.8EP.
- Sturges, Robert H., Jr., 4,295,740, Cl. 356-152.000.
- Weyerhaeuser Company: See—
Bentvelzen, Jozef M.; Meredith, Michael D.; Bepple, Henry; Torregrossa, Louis O.; Battan, Howard R.; and Justice, Dennis H., 4,295,925, Cl. 162-19.000.
- Bentvelzen, Jozef M.; Meredith, Michael D.; Bepple, Henry; Torregrossa, Louis O.; Battan, Howard R.; and Justice, Dennis H., 4,295,926, Cl. 162-57.000.
- Bentvelzen, Jozef M.; Meredith, Michael D.; Bepple, Henry; Torregrossa, Louis O.; Battan, Howard R.; and Justice, Dennis H., 4,295,927, Cl. 162-57.000.
- Whipple, Elliot: See—
Boulanger, Henry J.; Lowell, Victor; and Whipple, Elliot, 4,296,287, Cl. 200-83.00P.
- Whirlpool Corporation: See—
Hinkel, Lester H.; and Wolske, Lawrence E., 4,295,233, Cl. 4-619.000.
- Whitaker, Roger B.; and Blevins, Charles W., to Dickey-john Corporation. Combine performance monitor. 4,296,409, Cl. 340-684.000.
- White, Alan C.: See—
Bushnell, Brian J.; Cavalla, John F.; Shepherd, Robin G.; and White, Alan C., 4,296,029, Cl. 260-239.30R.
- White, Jeffrey A. Snowmaking nozzle. 4,295,608, Cl. 239-14.000.
- White, Michael L., to Magnallux Corporation. Pentaerythritol in dry developers. 4,295,362, Cl. 73-104.000.
- Whitehead, Larry W., to Leggett & Platt, Incorporated. Bed frame. 4,295,234, Cl. 5-184.000.
- Whitehead, Paul, to Johnson, Matthey & Co., Limited. Monitoring process and apparatus. 4,296,086, Cl. 423-392.000.
- Wiede, Donald, to A. Stucki Company. Railway truck bolster friction assembly. 4,295,429, Cl. 105-197.0DB.
- Wiechert, Rudolf: See—
Laurent, Henry; Esperling, Peter; Kapp, Joachim-Friedrich; and Wiechert, Rudolf, 4,296,109, Cl. 424-241.000.
- Wiedemann, Rolf: See—
Aigle, Karl; Hieber, Udo; Huebscher, Wilhelm; Rheindorf, Hans H.; and Wiedemann, Rolf, 4,296,453, Cl. 361-275.000.
- Wieggers, Wilhelmus J.; Sprecker, Mark A.; Watkins, Hugh; Vock, Manfred H.; and Schmitt, Frederick L., to International Flavors & Fragrances Inc. Use of isochroman musk compounds in augmenting or enhancing the aroma of dryer-added fabric softener articles. 4,295,978, Cl. 252-8.900.
- Wilhelm Schafer Maschinenbau: See—
Schafer, August W., 4,295,592, Cl. 228-17.000.
- Wilkinson, Stanley B., to General Electric Company. Ultra high speed protective relay circuit. 4,296,451, Cl. 361-80.000.
- Wilkinson Sword Limited: See—
Roswell, David G.; Spring, David J.; and Hems, Roger, 4,296,255, Cl. 564-215.000.
- Rowell, David G.; Gascoyne, John M.; and Hems, Roger, 4,296,093, Cl. 424-45.000.
- William H. Rorer, Inc.: See—
Diamond, Julius, 4,296,264, Cl. 570-128.000.
- Williams, Donald E.; Robertson, Forrest E.; Gigot, C. Dean; and Gigot, Terry K., to Acra-Plant, Inc. Planter with cooperating trash clearing discs. 4,295,532, Cl. 172-184.000.
- Williams, Ralph P.: See—
Parlman, Robert M.; and Williams, Ralph P., 4,295,962, Cl. 209-167.000.
- Williams, Robert A. Flexible tube terminating means. 4,295,672, Cl. 285-287.000.
- Williams, William, to Delta Mouldings (Leicester) Limited. Mould assembly for use in the manufacture of spherical or substantially spherical articles. 4,295,629, Cl. 249-160.000.
- Willingham, Wendell D., to Owens-Illinois, Inc. Closure conversion apparatus for existing closure applying machines. 4,295,320, Cl. 53-201.000.
- Willke, Herbert L., Jr.: See—
Gorchev, Dimitir; Ingard, Karl U.; and Willke, Herbert L., Jr., 4,295,416, Cl. 98-33.00R.
- Wilson, Arthur: See—
Lowe, Edward J.; Minshall, Michael W.; and Wilson, Arthur, 4,296,082, Cl. 423-305.000.
- Wilson, David S.: See—
Hannett, William J.; Brendel, Thomas E.; and Wilson, David S., 4,295,344, Cl. 62-324.500.
- Wilson, Richard S.: See—
Dennesen, Francis G.; Wilson, Richard S.; Toulan, Roy D., Jr.; and Madnick, Peter, 4,295,277, Cl. 33-181.00R.
- Wilson, Robert, to Timex Corporation. Symmetrical horizontal continuous casting. 4,295,516, Cl. 164-464.000.
- Wilson, Thomas T., to Epoxon Products, Inc. Combination heat transfer panel and wall shield for use with stoves and other radiant heaters. 4,295,460, Cl. 126-121.000.
- Windley, William T., to Du Pont de Nemours, E. I., and Company. Cobulked continuous filament heather yarn method and product. 4,295,329, Cl. 57-245.000.
- Wissinger, Waldemar: See—
Gauchel, Peter; and Wissinger, Waldemar, 4,296,062, Cl. 264-173.000.
- Witkin, Philip M., to Marshall and Williams Company. Dryer range. 4,295,284, Cl. 34-155.000.
- "Wohn-Art" Freizeitartikel Gesellschaft m.b.H.: See—
Artweiger, Wolfgang; and Freller, Walter, 4,295,679, Cl. 296-171.000.
- Wojnarowski, Robert J.: See—
Eichelberger, Charles W.; Dehn, Rudolph A.; and Wojnarowski, Robert J., 4,296,296, Cl. 219-10.55B.
- Wolf, Alvan H.: See—
Landay, David L.; and Wolf, Alvan H., 4,295,655, Cl. 280-11.200.
- Wolf, Franz J. Two part pressure relief valve. 4,296,186, Cl. 429-54.000.
- Wolf, Karlheinz: See—
Nonn, Konrad; Wolf, Karlheinz; Haus, Artur; and Hornle, Reinhold, 4,295,849, Cl. 8-524.000.
- Wolske, Lawrence E.: See—
Hinkel, Lester H.; and Wolske, Lawrence E., 4,295,233, Cl. 4-619.000.
- Woltersdorf, Otto W., Jr.: See—
Cragoe, Edward J., Jr.; and Woltersdorf, Otto W., Jr., 4,296,122, Cl. 424-285.000.
- Wong, Gim. Programmable electronic starting device for autos and the like with means selectable to actuate accessories. 4,296,334, Cl. 290-37.00R.
- Wong, William H., to Bell Telephone Laboratories, Incorporated. Molded circuit retaining enclosure with a receptacle means for securing individual circuit components. 4,296,454, Cl. 361-380.000.
- Wood, Donald H.: See—
Blake, Charles H.; and Wood, Donald H., 4,296,363, Cl. 318-349.000.
- Wood, Douglas E. Parabolic reflector comprising a plurality of triangular reflecting members forming a reflecting surface supported by a framework having a particular geometric pattern. 4,295,709, Cl. 350-292.000.
- Wood, Prentice J., to Mead Corporation. The article carrier and blank therefor. 4,295,562, Cl. 206-158.000.
- Woods, Rodney G.; Clarke, Charles J., Jr.; and Sodergren, Robert C., to Honeywell Inc. Process control system with local microprocessor control means. 4,296,464, Cl. 364-200.000.
- Woodstock, Alan: See—
Greenwood, Gillian M.; and Woodstock, Alan, 4,295,888, Cl. 106-21.000.
- Woolcock, Kenneth W., to Rota Cota Pty. Ltd. Paint roller. 4,295,241, Cl. 15-230.110.
- Woolley, Jack: See—
Smith, Leslie; Tew, William; and Woolley, Jack, 4,296,458, Cl. 361-433.000.
- Worrell, G. Richard, to Atlantic Richfield Company. Tertiary butyl alcohol production. 4,296,263, Cl. 568-910.000.
- Worrell, G. Richard: See—
Grane, Henry R.; Jubin, John C., Jr.; and Worrell, G. Richard, 4,296,262, Cl. 568-910.000.
- Wright, Dale W.: See—
Horner, John A.; and Wright, Dale W., 4,296,313, Cl. 235-61.00L.
- Wright, Earl R., to Wright Leather Goods Manufacturing Co. Filigreed belt with solid center portion. 4,295,231, Cl. 2-338.000.
- Wright Leather Goods Manufacturing Co.: See—
Wright, Earl R., 4,295,231, Cl. 2-338.000.
- Wright, Ronald F. Truss assembly apparatus. 4,295,269, Cl. 29-798.000.
- Wristers, Harry J., to Exxon Research & Engineering Co. Titanium trichloride catalyst component and the process for the production thereof. 4,295,991, Cl. 252-429.00B.
- Wu, Che-Kuang, to Corning Glass Works. Method for optical recording in photo-dichroic glass surfaces. 4,296,479, Cl. 365-119.000.
- Wuerzer, Bruno: See—
Eicken, Karl; Rohr, Wolfgang; Pander, Hans J.; and Wuerzer, Bruno, 4,295,875, Cl. 71-88.000.
- Wulf, Helmut, to Daimler-Benz Aktiengesellschaft. Heat transfer system. 4,295,520, Cl. 165-41.000.
- Wunder, Friedrich; Leupold, Ernst I.; Hachenberg, Horst; and Schmidt, Hans-Joachim, to Hoechst Aktiengesellschaft. Process for the manufacture of lower olefins from methanol/water mixtures. 4,296,266, Cl. 585-640.000.
- Wurtman, Richard J., to Massachusetts Institute of Technology. Process and composition for reducing blood pressure in animals. 4,296,119, Cl. 424-274.000.
- Wust, Manfred: See—
Roman, Alain; Chevreux, Pierre; Wust, Manfred; and Ehretsmann, Jacques, 4,295,948, Cl. 204-159.230.

Wuthrich, Hans-Rudolf; Krebs, Peter; Spiegel, Hubert; and Eicher, Franz, to Sprecher & Schuh AG. Electric gas-blast switch. 4,296,289, Cl. 200-148.00R.

Wynosky, Thomas A.; and Campbell, Charles A., to United Technologies Corporation. Two-dimensional nozzle. 4,295,611, Cl. 239-265.370.

Wyss, Robert P.: See—
Narozny, Ronald S.; and Wyss, Robert P., 4,295,704, Cl. 339-99.00R.

Xerox Corporation: See—
Gruber, Robert J.; Bolte, Steven B.; Knapp, John F.; Ims, Dale R.; and Lewis, Richard B., 4,296,192, Cl. 430-109.000.
Hull, Charles J.; Hutton, James E.; and Mahuson, Teri J., 4,295,732, Cl. 355-14.00R.
Markham, Roger G.; and Skinner, Doyle P., Jr., 4,296,417, Cl. 346-75.000.
Silverberg, Morton, 4,295,737, Cl. 355-76.000.

Yagihara, Morio; and Yokota, Yukio, to Fuji Photo Film Co., Ltd. Silver halide photographic light-sensitive material. 4,296,199, Cl. 430-551.000.

Yagihara, Morio; and Yokota, Yukio, to Fuji Photo Film Co., Ltd. Silver halide photographic light-sensitive material. 4,296,200, Cl. 430-551.000.

Yamada, Tateyoshi: See—
Hara, Shigeyoshi; and Yamada, Tateyoshi, 4,296,218, Cl. 525-439.000.

Yamagata, Toshio: See—
Moriya, Takeo; and Yamagata, Toshio, 4,296,193, Cl. 430-149.000.

Yamaguchi, Takashi; Okuno, Yoshitoshi; and Hirose, Chuji, to Sumitomo Chemical Company, Limited. Insecticidal aerosol formulation having a liquified petroleum gas propellant. 4,295,581, Cl. 222-192.000.

Yamakawa, Norio: See—
Ooki, Norihiro; Motegi, Shoji; Wachi, Yasuyuki; Takikawa, Yoshio; and Yamakawa, Norio, 4,296,346, Cl. 310-242.000.

Yamamoto, Fujio: See—
Kawaguchi, Yasuyoshi; Shimotake, Munetoshi; and Yamamoto, Fujio, 4,295,512, Cl. 152-354.00R.

Yamamoto, Noboru: See—
Matsuhisa, Tadaaki; Soejima, Shigeo; and Yamamoto, Noboru, 4,295,892, Cl. 501-120.000.

Yamamoto, Seiichi: See—
Teramura, Hiroichi; Yamazaki, Yasuhiro; Wakahara, Yasushi; Hattori, Naohiko; Yamamoto, Seiichi; and Nakao, Kouzo, 4,296,439, Cl. 358-257.000.

Yamanishi, Kazuhiko: See—
Kasahara, Shizuka; Yamanishi, Kazuhiko; Hanada, Toshiro; Tokuda, Kuniaki; and Kobatake, Shinzo, 4,295,853, Cl. 23-230.00B.

Yamashita, Etsu: See—
Nakahama, Syuhei; and Yamashita, Etsu, 4,296,308, Cl. 219-136.000.

Yamazaki, Etuo: See—
Imazeki, Ryoji; and Yamazaki, Etuo, 4,296,473, Cl. 364-520.000.

Yamazaki, Hiroshi; and Isayama, Takuro, to Ricoh Company, Ltd. Ink jet printing apparatus with reverse solvent flushing means. 4,296,418, Cl. 346-75.000.

Yamazaki, Sigeki: See—
Wada, Yoshimasa; Yamazaki, Sigeki; Kobayashi, Isamu; Haraguchi, Noriyuki; and Fukuda, Minoru, 4,295,780, Cl. 414-749.000.

Yamazaki, Yasuhiro: See—
Teramura, Hiroichi; Yamazaki, Yasuhiro; Wakahara, Yasushi; Hattori, Naohiko; Yamamoto, Seiichi; and Nakao, Kouzo, 4,296,439, Cl. 358-257.000.

Yan, Tsoung-yuan, to Mobil Oil Corporation. Method for protecting an ion-exchange resin from chemical poisoning. 4,296,075, Cl. 423-7.000.

Yanabu, Satoru; Mizoguchi, Hitoshi; and Simogawara, Naoki, to Tokyo Shibaura Denki Kabushiki Kaisha. Gas insulated disconnecting switches. 4,296,288, Cl. 200-146.00R.

Yano, Yasuhiro: See—
Eida, Tsuyoshi; Haruta, Masahiro; Yano, Yasuhiro; Matsufuji, Yoji; and Ohta, Tokuya, 4,295,889, Cl. 106-22.000.

Yarborough, Lyman: See—
Sharp, Shelby P.; and Yarborough, Lyman, 4,295,979, Cl. 252-8.55E.

Yashima, Nobuyoshi, to Mitsui Engineering and Shipbuilding Co., Ltd. Working platform for oil drilling operations in ice covered sea areas. 4,295,758, Cl. 405-201.000.

Yasuhara, Seishi; Teranuma, Jun; Shinzawa, Motohiro; and Fujii, Hiroshi, to Nissan Motor Co. Ltd. Exhaust gas recirculation control system for a compression-ignition internal combustion engine. 4,295,455, Cl. 123-569.000.

Yasukawa, Masaru; and Yasukawa, Soji. Conveyor with scrapers. 4,295,561, Cl. 198-735.000.

Yasukawa, Soji: See—
Yasukawa, Masaru; and Yasukawa, Soji, 4,295,561, Cl. 198-735.000.

Yeatts, Roy E., to RJR Archer, Inc. Composite tipping structure for use on an air-ventilated cigarette and method of manufacturing same. 4,295,478, Cl. 131-336.000.

Yeda Research and Development Company Ltd.: See—
Hodes, Gary; Cahen, David; and Manassen, Joost, 4,296,188, Cl. 429-111.000.

Ygnacio Inc.: See—
Holland, Kenneth F., 4,296,431, Cl. 358-12.000.

Yokota, Yukio: See—
Yagihara, Morio; and Yokota, Yukio, 4,296,199, Cl. 430-551.000.
Yagihara, Morio; and Yokota, Yukio, 4,296,200, Cl. 430-551.000.

Yonezawa, Seiji: See—
Terao, Motoyasu; Shigematsu, Kazuo; Ojima, Masahiro; and Yonezawa, Seiji, 4,296,419, Cl. 346-135.100.

Yoo, Jin S.: See—
Sun, Jui-Yuan; Burk, Emmett H., Jr.; Yoo, Jin S.; and Masologites, George P., 4,295,858, Cl. 44-1.05R.

Yoshida, Akio: See—
Shimada, Wataru; Hoshinouchi, Susumu; Kawaguchi, Kenji; and Yoshida, Akio, 4,295,906, Cl. 156-214.000.

Yoshida, Isao: See—
Sakano, Hajime; Kodama, Mikio; Nakayama, Koichi; Yoshida, Isao; and Inoue, Atsunori, 4,296,216, Cl. 525-66.000.

Yoshida Kogyo K.K.: See—
Hakoi, Tsutomu, 4,295,570, Cl. 209-657.000.

Yoshida, Masakatsu; Tochio, Yoshihiko; and Tohi, Atsutomu, to Matsushita Electronics Corporation. Method of making isolated semiconductor devices utilizing ion-implantation of aluminum and heat treating. 4,295,898, Cl. 148-1.500.

Yoshikawa, Takaharu, to Toshin Kogyo Co. Ltd. Method and apparatus for correcting errors of feeding of endless belt in automatic screen printing. 4,296,365, Cl. 318-632.000.

Yoshizumi, Eizaburo. Ground prospecting method utilizing electrical resistivity measurements for measuring the resistivity of unit blocks of the ground. 4,296,379, Cl. 324-357.000.

Yosim, Samuel J., to Rockwell International Corporation. Method of decladding. 4,296,074, Cl. 423-4.000.

Young, Donald A.; and Squires, Christopher P., to Lucas Industries, Limited. Starter motor. 4,296,342, Cl. 310-77.000.

Yuda, Takuo: See—
Morota, Kazutoshi; and Yuda, Takuo, 4,295,618, Cl. 248-73.000.

Yuhara, Akitsuna: See—
Hazama, Katashi; and Yuhara, Akitsuna, 4,296,391, Cl. 333-193.000.

Zachmeier, Thomas R. Well boring rigs and spoil handling conveyor apparatus therefor. 4,295,534, Cl. 175-88.000.

Zahid, Abdur, to Greer Hydraulics, Incorporated. Low cost accumulator device. 4,295,492, Cl. 138-30.000.

Zahnradfabrik Friedrichshafen, AG.: See—
Liebert, Karl-Heinz, 4,295,805, Cl. 418-61.00B.

Zahs, Gernot; and Wahle, Hans-Jurgen, to Vaccumetal Gesellschaft fur Vakuum-Metallurgie mbH. Rotary pipe switch. 4,295,667, Cl. 285-18.000.

Zaidan Hojin Biseibutsu Kagaku Kenkyu Kai: See—
Umezawa, Hamao; Okami, Yoshiro; and Kondo, Shinichi, 4,296,106, Cl. 424-181.000.

Zaiser, Wolfgang: See—
Helfer, Friedrich; Elsner, Ernst; and Zaiser, Wolfgang, 4,295,348, Cl. 64-27.00L.

Zamek, Otto S.: See—
Pauze, Denis R.; and Zamek, Otto S., 4,296,229, Cl. 528-45.000.

Zangari, Dominic V.; and Cranston, Douglas R., to Zangari, Dominic V. Cap lining machine. 4,295,436, Cl. 113-80.00D.

Zaverni, Vikram H.: See—
Kluting, Bernd A.; and Zaverni, Vikram H., 4,295,682, Cl. 297-367.000.

Zbrank, Zdenka: See—
Heuer, Steven R.; and Zbrank, Zdenka, 4,296,077, Cl. 423-53.000.

Zbrojovka Vsetin: See—
Svaty, Vladimir, 4,295,500, Cl. 139-435.000.

Zenith Radio Corporation: See—
d'Hauteourt, Alain H.; Bretl, Wayne E.; and Lee, Ronald B., 4,296,435, Cl. 358-166.000.

Engel, Christopher M.; and Srivastava, Gopal K., 4,296,432, Cl. 358-28.000.

Zero-Seal, Inc.: See—
Coles, Carl R., 4,295,653, Cl. 277-2.000.

Zhivotov, Jury G. Apparatus for balancing bodies of revolution. 4,295,386, Cl. 74-573.00F.

Zhivotov, Jury G.; Kupchinsky, Igor I.; Plokhuta, Vyacheslav D.; Bezverkhy, Alexandr M.; Nabutovsky, Samoil I., deceased; and by Eroshevskaya, Elena D., administrator. Apparatus for balancing bodies of revolution. 4,295,387, Cl. 74-573.00F.

Ziccarelli, Salvatore F.; Ramos, Rey C.; and Brown, Robert M., to Beatrice Foods Company. Coconut powder. 4,296,136, Cl. 426-533.000.

Ziche, Horst, to Henkel Kommanditgesellschaft Auf Aktien. Process for the removal of alkali metal halides from cellulose ethers soluble in cold water and use of the purified products in washing and cleansing agent compositions. 4,296,235, Cl. 536-85.000.

Ziegenhain, William C., to Conoco Inc. Method of making alumina fibers. 4,296,057, Cl. 264-63.000.

Zielke, Rainer; and Maegerlein, Helmut, to Akzona Incorporated. Process for the preparation of phloroglucinol. 4,296,260, Cl. 568-763.000.

Zimmerman, Lawrence. Hay bale stacker. 4,295,772, Cl. 414-38.000.

Zimmermann, Frank; Heidemeyer, Paulus; and Bigalke, Erhard, to Volkswagenwerk Aktiengesellschaft. Automatic clutch system. 4,295,551, Cl. 192-0.076.

Zimmermann, Wolfgang; Schindler, Hermann; and Pospich, Gunther, to Hoechst Aktiengesellschaft. Open-cell shaped article made of acetalized polyvinyl alcohol and process for its manufacture. 4,296,210, Cl. 521-85.000.

Zorbalas, George S., to RCA Corporation. Motor speed control circuit. 4,296,446, Cl. 360-73.000.

Zubkewych, Morris: See—
Clark, Eugene A.; and Zubkewych, Morris, 4,295,229, Cl. 2-20.000.

Zura, Boris, to United States of America, Army. Gage to measure track tension. 4,295,379, Cl. 73-862.620.

LIST OF REISSUE PATENTEES

TO WHOM

PATENTS WERE ISSUED ON THE 20TH DAY OF OCTOBER, 1981

NOTE.—Arranged in accordance with the first significant character or word of the name (in accordance with city and telephone directory practice).

Alfa-Laval AB: See—
Stenstrom, Lennart A., Re. 30,780, Cl. 219-10.55M.

Commonwealth Scientific and Industrial Research Organization: See—
Plate, Dieter E. A.; and Feehan, John D., Re. 30,776, Cl. 57-86.000.

Cooper, Roydon B., to Pall Corporation. Filter assembly with replaceable filter element. Re. 30,779, Cl. 210-232.000.

Dahlbeck, Edwin L.; and Dahlbeck, Verna H. Lightweight removable cover for a pool, greenhouse or the like. Re. 30,774, Cl. 4-498.000.

Dahlbeck, Verna H.: See—
Dahlbeck, Edwin L.; and Dahlbeck, Verna H., Re. 30,774, Cl. 4-498.000.

Delvy, Robert J.: See—
Miller, Fredric S.; De Mauro, Armando A.; and Delvy, Robert J., Re. 30,775, Cl. 29-25.420.

De Mauro, Armando A.: See—
Miller, Fredric S.; De Mauro, Armando A.; and Delvy, Robert J., Re. 30,775, Cl. 29-25.420.

Extraversion, Inc.: See—
Ytter, Willy, Re. 30,777, Cl. 160-135.000.

Feehan, John D.: See—
Plate, Dieter E. A.; and Feehan, John D., Re. 30,776, Cl. 57-86.000.

Hahn, William F.; Nigro, Joseph P.; and Wallitsch, Frank, Jr., to Pennsylvania Crusher Corporation. Crusher-dryer and method of crushing. Re. 30,778, Cl. 241-18.000.

Miller, Fredric S.; De Mauro, Armando A.; and Delvy, Robert J., to Universal Manufacturing Corporation. Automatic capacitor winding machine and method. Re. 30,775, Cl. 29-25.420.

Miyamoto, Yukihiro, to Trio Kabushiki Kaisha. Logarithmic amplifier. Re. 30,781, Cl. 307-490.000.

Nigro, Joseph P.: See—
Hahn, William F.; Nigro, Joseph P.; and Wallitsch, Frank, Jr., Re. 30,778, Cl. 241-18.000.

Pall Corporation: See—
Cooper, Roydon B., Re. 30,779, Cl. 210-232.000.

Pennsylvania Crusher Corporation: See—
Hahn, William F.; Nigro, Joseph P.; and Wallitsch, Frank, Jr., Re. 30,778, Cl. 241-18.000.

Plate, Dieter E. A.; and Feehan, John D., to Commonwealth Scientific and Industrial Research Organization. Break-out apparatus for fault prevention in the production of multi-strand yarns. Re. 30,776, Cl. 57-86.000.

Stenstrom, Lennart A., to Alfa-Laval AB. Heat treatment of heat-sensitive products. Re. 30,780, Cl. 219-10.55M.

Trio Kabushiki Kaisha: See—
Miyamoto, Yukihiro, Re. 30,781, Cl. 307-490.000.

Universal Manufacturing Corporation: See—
Miller, Fredric S.; De Mauro, Armando A.; and Delvy, Robert J., Re. 30,775, Cl. 29-25.420.

Wallitsch, Frank, Jr.: See—
Hahn, William F.; Nigro, Joseph P.; and Wallitsch, Frank, Jr., Re. 30,778, Cl. 241-18.000.

Ytter, Willy, to Extraversion, Inc. Portable display system. Re. 30,777, Cl. 160-135.000.

LIST OF DESIGN PATENTEES

Adkinson, Joseph E. Chair or the like. 261,333, 10-20-81, Cl. D6-57.000.

AGFA-Gevaert AG: See—
Schlagheck, Norbert, 261,393, Cl. D16-4.000.

Airway Industries, Inc.: See—
Davis, Michael, 261,328, Cl. D3-71.000.

Amarger, Guy, to Compagnie Generale des Etablissements Michelin. Tire. 261,380, 10-20-81, Cl. D12-143.000.

Amarger, Guy, to Compagnie Generale des Etablissements Michelin. Tire. 261,381, 10-20-81, Cl. D12-146.000.

Amarger, Guy, to Compagnie Generale des Etablissements Michelin. Tire. 261,383, 10-20-81, Cl. D12-147.000.

Ambler, E. Curtis; and Bies, Sylvester W., to Stanley Works, The. Mitre box. 261,353, 10-20-81, Cl. D8-71.000.

AMC International Alfa Metalcraft Corporation AG: See—
Ryser, Theophil, 261,349, Cl. D7-132.000.

Anderson, Charles C. Oropharyngeal airway. 261,442, 10-20-81, Cl. D29-6.000.

Anson, Robert A. Rack for holding dental instruments. 261,424, 10-20-81, Cl. D24-16.000.

Appel, Mel; and Kress, George, to Appel, Mel. Toy kitchen. 261,404, 10-20-81, Cl. D21-122.000.

Aqua-Mist, Inc.: See—
Morrow, William B., 261,421, Cl. D23-147.000.
Morrow, William B., 261,422, Cl. D23-147.000.

Ballard, James H. Emergency shelter for underground installation. 261,432, 10-20-81, Cl. D25-36.000.

Barreca, Joseph E., to McGraw-Hill, Inc. Drawing instrument. 261,368, 10-20-81, Cl. D10-62.000.

Barton, Shirley. Vending trailer. 261,431, 10-20-81, Cl. D25-10.000.

Bates Industries, Inc.: See—
Beaubien, Thomas S.; Rich, Dennis C.; and Oehring, Robert E., 261,386, Cl. D12-158.000.

Baturin, Peter, to Medical Products Institute Incorporated. Vacuum splint. 261,430, 10-20-81, Cl. D24-64.000.

Bausch & Lomb Incorporated: See—
Speaker, Edwin A., 261,397, Cl. D16-131.000.

Beall, Glenn L.; Petersen, Lawrence; and Dauksys, Richard J., to Loctite Puerto Rico. Combined adhesive container and dispenser. 261,400, 10-20-81, Cl. D19-66.000.

Beaubien, Thomas S.; Rich, Dennis C.; and Oehring, Robert E., to Bates Industries, Inc. Motorcycle tote box. 261,386, 10-20-81, Cl. D12-158.000.

Bell, Ted A.; and Cooksey, Timothy S., to Pretty Products, Inc. Tape cassette holder for a sunvisor. 261,326, 10-20-81, Cl. D3-35.000.

Benz, Rolf. Adjustable lounge chair or similar article. 261,331, 10-20-81, Cl. D6-37.000.

Bergeron, Timothy J., to J. A. Preston Corporation. Child's crawler. 261,378, 10-20-81, Cl. D12-128.000.

Bianchi, John E.; and Nichols, Richard D. E. Long barrel holster. 261,409, 10-20-81, Cl. D22-13.000.

Bies, Sylvester W.: See—
Ambler, E. Curtis; and Bies, Sylvester W., 261,353, Cl. D8-71.000.

Braun Aktiengesellschaft: See—
Oberheim, Robert; Greubel, Jurgen; and Rams, Dieter, 261,441, Cl. D28-35.000.

Brooksby, Brain T.; Murray, Harold J.; Simpson, Anthony; and Peterkin, Stuart M. Target slide projectors console. 261,395, 10-20-81, Cl. D16-11.000.

Bruhn, John A., to Zimmer USA, Inc. Bone cement injector handpiece. 261,425, 10-20-81, Cl. D24-26.000.

Bryan, John W. Gaff holder for the spur of a gamecock. 261,408, 10-20-81, Cl. D22-1.000.

Cacciatore, Diego M.: See—
Weitz, Harry; and Cacciatore, Diego M., 261,387, Cl. D12-192.000.

California Sounds Ltd.: See—
Sandor, Joseph, 261,363, Cl. D9-413.000.

Canon Kabushiki Kaisha: See—
Hirata, Takashi; and Fushimoto, Hideo, 261,398, Cl. D18-7.000.

Carper, William B., to Suntrak Industries, Inc. Snow scoop body. 261,351, 10-20-81, Cl. D8-10.000.

Carre, Alain, to Waterman S.A. Watch. 261,365, 10-20-81, Cl. D10-38.000.

Catron, George W., to LeSueur, Leo R. Jeans or the like. 261,323, 10-20-81, Cl. D2-28.000.

Catron, George W., to LeSueur, Leo R. Jeans or the like. 261,324, 10-20-81, Cl. D2-28.000.

Champion International Corporation: See—
Faller, Rudolph A., 261,358, Cl. D9-346.000.

Clemens, Donald L., to Thermalloy Incorporated. Card ejector handle for a printed circuit board or similar article. 261,354, 10-20-81, Cl. D8-306.000.

Clyburn, Charles W., to James David Incorporated. Furniture leg and rail connector. 261,340, 10-20-81, Cl. D6-191.000.

Coca-Cola Company, The: See—
Harvill, William A., 261,390, Cl. D15-116.000.

Collis, Carroll E. Sign post support. 261,401, 10-20-81, Cl. D20-41.000.

- Compagnie Generale des Etablissements Michelin: See—
 Amarger, Guy, 261,380, Cl. D12-143.000.
 Amarger, Guy, 261,381, Cl. D12-146.000.
 Amarger, Guy, 261,383, Cl. D12-147.000.
 Peron, Jean-Claude, 261,379, Cl. D12-143.000.
 Peron, Jean-Claude, 261,382, Cl. D12-147.000.
 Peron, Jean-Claude, 261,384, Cl. D12-147.000.
 Peron, Jean-Claude, 261,385, Cl. D12-147.000.
 Conceptual Factors, Inc.: See—
 Lutz, William R., 261,347, Cl. D7-130.000.
 Conner, Marjorie M., to Trigere, Inc. Chair. 261,335, 10-20-81, Cl. D6-72.000.
 Cooksey, Timothy S.: See—
 Bell, Ted A.; and Cooksey, Timothy S., 261,326, Cl. D3-35.000.
 Corbin, Gary L. Skate wheel. 261,406, 10-20-81, Cl. D21-226.000.
 Cornelius Company, The: See—
 Harvill, William A., 261,390, Cl. D15-116.000.
 Ranua, Walter E.; and Mackrell, William B., 261,391, Cl. D15-120.000.
 Dart Industries Inc.: See—
 Groh, Leo A.; Ludwig, Douglas D.; Painter, David L.; and Free, John H., 261,348, Cl. D7-131.000.
 Dauksys, Richard J.: See—
 Beall, Glenn L.; Petersen, Lawrence; and Dauksys, Richard J., 261,400, Cl. D19-66.000.
 Davis, Michael, to Airway Industries, Inc. Luggage case. 261,328, 10-20-81, Cl. D3-71.000.
 DeLange, William. Wall-mounted mailbox. 261,443, 10-20-81, Cl. D99-33.000.
 Doi, Tetsuyuki; and Shohoji, Takeshi, to Ryobi Limited. Fishing rod grip. 261,411, 10-20-81, Cl. D22-23.000.
 Doonan, R. Dean. Insulation injection hole plug. 261,357, 10-20-81, Cl. D8-499.000.
 Eberle, Gunter F., to Vecta Contract, Inc. Base for a table or the like. 261,341, 10-20-81, Cl. D6-196.000.
 Eddleman, Roy T. Vacuum filter. 261,413, 10-20-81, Cl. D23-4.000.
 Englishtown Sportswear, Ltd.: See—
 Heinfling, Martin, 261,320, Cl. D2-25.000.
 Heinfling, Martin, 261,321, Cl. D2-25.000.
 Heinfling, Martin, 261,322, Cl. D2-25.000.
 Epperson, Charles N., to Invention Development Equity Assoc., Inc. Container for liquids or the like. 261,360, 10-20-81, Cl. D9-375.000.
 Epperson, Charles N., to Invention Development Equity Assoc., Inc. Container for liquid products or the like. 261,361, 10-20-81, Cl. D9-375.000.
 Epperson, Charles N., to Invention Development Equity Assoc., Inc. Stackable container for liquids or the like. 261,362, 10-20-81, Cl. D9-376.000.
 Faller, Rudolph A., to Champion International Corporation. Blank for three compartment box. 261,358, 10-20-81, Cl. D9-346.000.
 Fink, Raymond W., to Tool Dynamics, Inc. Auxiliary towel rack. 261,337, 10-20-81, Cl. D6-99.000.
 Fisher, Stanley C. Light-reflecting sculpture. 261,373, 10-20-81, Cl. D11-131.000.
 Flexsteel Industries, Inc.: See—
 Meier, Louis M., 261,330, Cl. D6-37.000.
 Frazee, Ermal C.: See—
 Smyth, George F., 261,364, Cl. D9-438.000.
 Free, John H.: See—
 Groh, Leo A.; Ludwig, Douglas D.; Painter, David L.; and Free, John H., 261,348, Cl. D7-131.000.
 Fried, Leo A. Earring. 261,372, 10-20-81, Cl. D11-40.000.
 Friedrich Grohe Armaturenfabrik GmbH & Co.: See—
 Klose, Odo, 261,417, Cl. D23-35.000.
 Frye, Stephen K., to Lion in Frost Inc. Table base. 261,342, 10-20-81, Cl. D6-196.000.
 Fushimoto, Hideo: See—
 Hirata, Takashi; and Fushimoto, Hideo, 261,398, Cl. D18-7.000.
 Geissler, Hans-Jürgen, to Rowenta-Werke, GmbH. Denture cleaner or the like. 261,423, 10-20-81, Cl. D24-10.000.
 Geissler, Udo M., to Plaubel, Feinmechanik & Optik GmbH. Camera. 261,394, 10-20-81, Cl. D16-06.000.
 General Bathroom Products Co.: See—
 Palka, James J.; and Rekart, Robert, 261,436, Cl. D26-80.000.
 Gibiec, Oswald, to Vorwerk & Co. Elektrowerke KG. Basket insert for a kitchen machine. 261,343, 10-20-81, Cl. D7-47.000.
 Grant, Benton H. Tub mounted bath lift. 261,377, 10-20-81, Cl. D34-33.000.
 Greubel, Jürgen: See—
 Oberheim, Robert; Greubel, Jürgen; and Rams, Dieter, 261,441, Cl. D28-35.000.
 Groh, Leo A.; Ludwig, Douglas D.; Painter, David L.; and Free, John H., to Dart Industries Inc. Ribbed coffee urn lid. 261,348, 10-20-81, Cl. D7-131.000.
 Hanna-Burns, Joan. Bed pan seat liner. 261,429, 10-20-81, Cl. D24-51.000.
 Harvill, William A., to Coca-Cola Company, The; and Cornelius Company, The. Beverage dispenser. 261,390, 10-20-81, Cl. D15-116.000.
 Hayes, Jerry R., to L. R. Nelson Corporation. Sprinkler base. 261,414, 10-20-81, Cl. D23-7.000.
 Heinfling, Martin, to Englishtown Sportswear, Ltd. Pocket for jeans or the like. 261,320, 10-20-81, Cl. D2-25.000.
 Heinfling, Martin, to Englishtown Sportswear, Ltd. Pocket for jeans or the like. 261,321, 10-20-81, Cl. D2-25.000.
 Heinfling, Martin, to Englishtown Sportswear, Ltd. Pocket for jeans or the like. 261,322, 10-20-81, Cl. D2-25.000.
 Hirata, Takashi; and Fushimoto, Hideo, to Canon Kabushiki Kaisha. Desk top electronic calculator. 261,398, 10-20-81, Cl. D18-7.000.
 Instrument Systems Corporation: See—
 Weitz, Harry; and Cacciatore, Diego M., 261,387, Cl. D12-192.000.
 Invention Development Equity Assoc., Inc.: See—
 Epperson, Charles N., 261,360, Cl. D9-375.000.
 Epperson, Charles N., 261,361, Cl. D9-375.000.
 Epperson, Charles N., 261,362, Cl. D9-376.000.
 J. A. Preston Corporation: See—
 Bergeron, Timothy J., 261,378, Cl. D12-128.000.
 Jackson, Edward. Combined strainer and plug for a sink or the like. 261,418, 10-20-81, Cl. D23-42.000.
 James David Incorporated: See—
 Clyburn, Charles W., 261,340, Cl. D6-191.000.
 Janson, Mats, to Tylo Sauna S.A. Front cover for thermostat regulator housing. 261,367, 10-20-81, Cl. D10-60.000.
 John J. Madison Company, Inc.: See—
 Santa-Eulalia Carvajales, Jesus A.; and Santa-Eulalia Carvajales, Javier B., 261,374, Cl. D11-158.000.
 Santa-Eulalia Carvajales, Jesus A.; and Santa-Eulalia Carvajales, Javier B., 261,375, Cl. D11-158.000.
 Johnson, Kenneth E., Sr., to T-Shirts Plus, Inc. Display stand. 261,339, 10-20-81, Cl. D6-152.000.
 Kikuchi, Yoshikazu, to Mitutoyo Mfg. Co., Ltd. Dial gauge. 261,370, 10-20-81, Cl. D10-73.000.
 Klose, Odo, to Friedrich Grohe Armaturenfabrik GmbH & Co. Show-erhead. 261,417, 10-20-81, Cl. D23-35.000.
 Koepfel, Fritz; and Loizance, Jean-Yves. Decanting cradle. 261,345, 10-20-81, Cl. D7-70.000.
 Koshiyama, Taro. Clothes dryer rack. 261,350, 10-20-81, Cl. D32-58.000.
 Kress, George: See—
 Appel, Mel; and Kress, George, 261,404, Cl. D21-122.000.
 L. R. Nelson Corporation: See—
 Hayes, Jerry R., 261,414, Cl. D23-7.000.
 Lam, Yanta H. T., to Meyer Aluminium Limited. Microwave detector. 261,366, 10-20-81, Cl. D10-47.000.
 LeSueur, Leo R.: See—
 Catron, George W., 261,323, Cl. D2-28.000.
 Catron, George W., 261,324, Cl. D2-28.000.
 Lewis, Kenneth T. Burglar alarm housing. 261,371, 10-20-81, Cl. D10-106.000.
 Light, Rex E. Seat. 261,334, 10-20-81, Cl. D6-63.000.
 Lion in Frost Inc.: See—
 Frye, Stephen K., 261,342, Cl. D6-196.000.
 Locitite Puerto Rico: See—
 Beall, Glenn L.; Petersen, Lawrence; and Dauksys, Richard J., 261,400, Cl. D19-66.000.
 Loizance, Jean-Yves: See—
 Koepfel, Fritz; and Loizance, Jean-Yves, 261,345, Cl. D7-70.000.
 Lovejoy, Robert B., to Mattel, Inc. Basketball game display and control panel or similar article. 261,402, 10-20-81, Cl. D21-13.000.
 Ludwig, Douglas D.: See—
 Groh, Leo A.; Ludwig, Douglas D.; Painter, David L.; and Free, John H., 261,348, Cl. D7-131.000.
 Lutz, William R., to Conceptual Factors, Inc. Pot stand assembly for a portable camp stove. 261,347, 10-20-81, Cl. D7-130.000.
 Maass, Rudolf, to Robert Krups Stiftung & Co. KG. Wall-hung coffee machine. 261,344, 10-20-81, Cl. D7-62.000.
 Mackrell, William B.: See—
 Ranua, Walter E.; and Mackrell, William B., 261,391, Cl. D15-120.000.
 Marconi, Karen D., to Quaker Oats Company, The. Toy rabbit. 261,405, 10-20-81, Cl. D21-187.000.
 Marlin Fiberglass, Inc.: See—
 Reineman, Richard G., 261,426, Cl. D24-38.000.
 Mattel, Inc.: See—
 Lovejoy, Robert B., 261,402, Cl. D21-13.000.
 McGraw-Hill, Inc.: See—
 Barreca, Joseph E., 261,368, Cl. D10-62.000.
 Medical Products Institute Incorporated: See—
 Baturin, Peter, 261,430, Cl. D24-64.000.
 Meier, Louis M., to Flexsteel Industries, Inc. Chair. 261,330, 10-20-81, Cl. D6-37.000.
 Meyer Aluminium Limited: See—
 Lam, Yanta H. T., 261,366, Cl. D10-47.000.
 Miller, Grover A. Rotatable tie rack. 261,338, 10-20-81, Cl. D6-113.000.
 Miller, Louis E. Guide wheel for welding torches. 261,352, 10-20-81, Cl. D8-30.000.
 Mitutoyo Mfg. Co., Ltd.: See—
 Kikuchi, Yoshikazu, 261,370, Cl. D10-73.000.
 Miyakawa, Eiji, to Miyakawa Industry Company, Limited. Spindlecase attachment for tapping machines to change the rotation of the tool. 261,392, 10-20-81, Cl. D15-140.000.
 Miyakawa Industry Company, Limited: See—
 Miyakawa, Eiji, 261,392, Cl. D15-140.000.
 Moreland, Gerald W. Safety suction fitting for hydro-therapy spas. 261,419, 10-20-81, Cl. D23-42.000.
 Morrow, William B., to Aqua-Mist, Inc. Humidifier for a hot air furnace or the like. 261,421, 10-20-81, Cl. D23-147.000.
 Morrow, William B., to Aqua-Mist, Inc. Humidifier for a hot air furnace or the like. 261,422, 10-20-81, Cl. D23-147.000.
 Moss, Charles W. Shelter. 261,407, 10-20-81, Cl. D21-253.000.
 Mullins, Dewey C., to Mullins Lure Company. Fishing lure. 261,410, 10-20-81, Cl. D22-29.000.

- Mullins Lure Company: See—
 Mullins, Dewey C., 261,410, Cl. D22-29.000.
 Munch, Emil L., to Nestier Corporation. Bakery tray. 261,444, 10-20-81, Cl. D34-43.000.
 Murray, Harold J.: See—
 Brooksby, Brain T.; Murray, Harold J.; Simpson, Anthony; and Peterkin, Stuart M., 261,395, Cl. D16-11.000.
 Nass, Henry E. Package of block-shaped articles. 261,359, 10-20-81, Cl. D9-337.000.
 Nestier Corporation: See—
 Munch, Emil L., 261,444, Cl. D34-43.000.
 Nichols, Richard D. E.: See—
 Bianchi, John E.; and Nichols, Richard D. E., 261,409, Cl. D22-13.000.
 Niro, Brian G. Shoe. 261,325, 10-20-81, Cl. D2-309.000.
 Noble, Edward D. Chiropractic vibrator. 261,428, 10-20-81, Cl. D24-41.000.
 Oberheim, Robert; Greubel, Jürgen; and Rams, Dieter, to Braun Aktiengesellschaft. Curling iron. 261,441, 10-20-81, Cl. D28-35.000.
 Oehring, Robert E.: See—
 Beaubien, Thomas S.; Rich, Dennis C.; and Oehring, Robert E., 261,386, Cl. D12-158.000.
 Ofrex Group Limited: See—
 Robinson, Douglas, 261,356, Cl. D8-382.000.
 Ogden, Philip I. Whirlpool bathtub. 261,427, 10-20-81, Cl. D24-38.000.
 Ohmura, Ryuichi. Line guide for fishing rod. 261,412, 10-20-81, Cl. D22-24.000.
 Owens-Corning Fiberglass Corporation: See—
 Weitzman, Mark R., 261,435, Cl. D25-97.000.
 Painter, David L.: See—
 Groh, Leo A.; Ludwig, Douglas D.; Painter, David L.; and Free, John H., 261,348, Cl. D7-131.000.
 Palka, James J.; and Rekart, Robert, to General Bathroom Products Co. Lighting fixture. 261,436, 10-20-81, Cl. D26-80.000.
 Pasquarello, Edward J. Shampoo drainage tray. 261,440, 10-20-81, Cl. D28-20.000.
 Pataki, Joseph. Toy hoop roller. 261,403, 10-20-81, Cl. D21-101.000.
 Peron, Jean-Claude, to Compagnie Generale des Etablissements Michelin. Tire. 261,379, 10-20-81, Cl. D12-143.000.
 Peron, Jean-Claude, to Compagnie Generale des Etablissements Michelin. Tire. 261,382, 10-20-81, Cl. D12-147.000.
 Peron, Jean-Claude, to Compagnie Generale des Etablissements Michelin. Tire. 261,384, 10-20-81, Cl. D12-147.000.
 Peron, Jean-Claude, to Compagnie Generale des Etablissements Michelin. Tire. 261,385, 10-20-81, Cl. D12-147.000.
 Peterkin, Stuart M.: See—
 Brooksby, Brain T.; Murray, Harold J.; Simpson, Anthony; and Peterkin, Stuart M., 261,395, Cl. D16-11.000.
 Petersen, Lawrence: See—
 Beall, Glenn L.; Petersen, Lawrence; and Dauksys, Richard J., 261,400, Cl. D19-66.000.
 Pilla, Donald P. Fermentation and beverage storage apparatus. 261,389, 10-20-81, Cl. D15-112.000.
 Plaubel, Feinmechanik & Optik GmbH: See—
 Geissler, Udo M., 261,394, Cl. D16-06.000.
 Pretty Products, Inc.: See—
 Bell, Ted A.; and Cooksey, Timothy S., 261,326, Cl. D3-35.000.
 Quaker Oats Company, The: See—
 Marconi, Karen D., 261,405, Cl. D21-187.000.
 Rams, Dieter: See—
 Oberheim, Robert; Greubel, Jürgen; and Rams, Dieter, 261,441, Cl. D28-35.000.
 Ranua, Walter E.; and Mackrell, William B., to Cornelius Company, The. Beverage dispenser valve. 261,391, 10-20-81, Cl. D15-120.000.
 Raye, Tommy D. Ski carrier. 261,327, 10-20-81, Cl. D3-36.000.
 Reineman, Richard G., to Marlin Fiberglass, Inc. Hydrotherapy spa. 261,426, 10-20-81, Cl. D24-38.000.
 Rekart, Robert: See—
 Palka, James J.; and Rekart, Robert, 261,436, Cl. D26-80.000.
 Rich, Dennis C.: See—
 Beaubien, Thomas S.; Rich, Dennis C.; and Oehring, Robert E., 261,386, Cl. D12-158.000.
 Robert Krups Stiftung & Co. KG: See—
 Maass, Rudolf, 261,344, Cl. D7-62.000.
 Robinson, Douglas, to Ofrex Group Limited. Strip of insulated cable clips. 261,356, 10-20-81, Cl. D8-382.000.
 Rohr, Eduard, to Wibe Treuhand AG. Chair. 261,332, 10-20-81, Cl. D6-55.000.
 Rowenta-Werke, GmbH: See—
 Geissler, Hans-Jürgen, 261,423, Cl. D24-10.000.
 Ryobi Limited: See—
 Doi, Tetsuyuki; and Shohoji, Takeshi, 261,411, Cl. D22-23.000.
 Ryser, Theophil, to AMC International Alfa Metalcraft Corporation AG. Pot cover handle. 261,349, 10-20-81, Cl. D7-132.000.
 Sandor, Joseph, to California Sounds Ltd. Bottle. 261,363, 10-20-81, Cl. D9-413.000.
 Santa-Eulalia Carvajales, Javier B.: See—
 Santa-Eulalia Carvajales, Jesus A.; and Santa-Eulalia Carvajales, Javier B., 261,374, Cl. D11-158.000.
 Santa-Eulalia Carvajales, Jesus A.; and Santa-Eulalia Carvajales, Javier B., 261,375, Cl. D11-158.000.
 Santa-Eulalia Carvajales, Jesus A.; and Santa-Eulalia Carvajales, Javier B., to John J. Madison Company, Inc. Figurine of a dolphin. 261,374, 10-20-81, Cl. D11-158.000.
 Santa-Eulalia Carvajales, Jesus A.; and Santa-Eulalia Carvajales, Javier B., to John J. Madison Company, Inc. Figurine of a okapi. 261,375, 10-20-81, Cl. D11-158.000.
 Schlagheck, Norbert, to AGFA-Gevaert AG. Movie camera. 261,393, 10-20-81, Cl. D16-4.000.
 Sher, S. Franklin. Pipe. 261,438, 10-20-81, Cl. D27-03.000.
 Sher, S. Franklin. Pipe. 261,439, 10-20-81, Cl. D27-03.000.
 Shohoji, Takeshi: See—
 Doi, Tetsuyuki; and Shohoji, Takeshi, 261,411, Cl. D22-23.000.
 Siefken, Larry O. Can piercing spraying tool. 261,416, 10-20-81, Cl. D23-34.000.
 Simpson, Anthony: See—
 Brooksby, Brain T.; Murray, Harold J.; Simpson, Anthony; and Peterkin, Stuart M., 261,395, Cl. D16-11.000.
 Smith, James L. Combined torpedo level and peripheral angle measuring device. 261,369, 10-20-81, Cl. D10-69.000.
 Smyth, George F., to Frazee, Ermal C. Tab for easy opening can end. 261,364, 10-20-81, Cl. D9-438.000.
 Speaker, Edwin A., to Bausch & Lomb Incorporated. Microscope stand or similar article. 261,397, 10-20-81, Cl. D16-131.000.
 Stanley Works, The: See—
 Ambler, E. Curtis; and Bies, Sylvester W., 261,353, Cl. D8-71.000.
 Stelkelberg, Terry C. Decorative wall lamp. 261,437, 10-20-81, Cl. D26-87.000.
 Sugano, Yoshihiko, to Tokyo Shibaura Denki Kabushiki Kaisha. Automatic ticket gate. 261,433, 10-20-81, Cl. D25-50.000.
 Sugano, Yoshihiko, to Tokyo Shibaura Denki Kabushiki Kaisha. Automatic ticket gate. 261,434, 10-20-81, Cl. D25-50.000.
 Sundberg, Alf. Catch assembly for drawers and cupboards. 261,355, 10-20-81, Cl. D8-331.000.
 Suntrak Industries, Inc.: See—
 Carper, William B., 261,351, Cl. D8-10.000.
 T-Shirts Plus, Inc.: See—
 Johnson, Kenneth E., Sr., 261,339, Cl. D6-152.000.
 Thermalloy Incorporated: See—
 Clemens, Donald L., 261,354, Cl. D8-306.000.
 Thomson-Brandt: See—
 Vachus, Raymond, 261,388, Cl. D14-25.000.
 Thornley, Marjorie A. Cup cake stamper. 261,346, 10-20-81, Cl. D7-101.000.
 Thorpe, Robert. Bed headboard. 261,336, 10-20-81, Cl. D6-79.000.
 Tipton, James A. Construction trolley. 261,376, 10-20-81, Cl. D12-1.000.
 Tokyo Shibaura Denki Kabushiki Kaisha: See—
 Sugano, Yoshihiko, 261,433, Cl. D25-50.000.
 Sugano, Yoshihiko, 261,434, Cl. D25-50.000.
 Tool Dynamics, Inc.: See—
 Fink, Raymond W., 261,337, Cl. D6-99.000.
 Trigere, Inc.: See—
 Conner, Marjorie M., 261,335, Cl. D6-72.000.
 Tylo Sauna S.A.: See—
 Janson, Mats, 261,367, Cl. D10-60.000.
 Vachus, Raymond, to Thomson-Brandt. Record turntable. 261,388, 10-20-81, Cl. D14-25.000.
 Van Horn, Robert L. Chair. 261,329, 10-20-81, Cl. D6-30.000.
 Vecta Contract, Inc.: See—
 Eberle, Gunter F., 261,341, Cl. D6-196.000.
 Vorwerk & Co. Elektrowerke KG: See—
 Gibiec, Oswald, 261,343, Cl. D7-47.000.
 Wagner, Robert G. Black jack slide rule. 261,399, 10-20-81, Cl. D18-10.000.
 Waterman S.A.: See—
 Carre, Alain, 261,365, Cl. D10-38.000.
 Weitz, Harry; and Cacciatore, Diego M., to Instrument Systems Corporation. Control panel for aircraft or the like. 261,387, 10-20-81, Cl. D12-192.000.
 Weitzman, Mark R., to Owens-Corning Fiberglass Corporation. Acoustical ceiling panel. 261,435, 10-20-81, Cl. D25-97.000.
 Whirlpool Corporation: See—
 Wolske, Lawrence E., 261,420, Cl. D23-59.000.
 Wibe Treuhand AG: See—
 Rohr, Eduard, 261,332, Cl. D6-55.000.
 Wilken, Roger. Photographic print washer. 261,396, 10-20-81, Cl. D16-35.000.
 Wolske, Lawrence E., to Whirlpool Corporation. Combined plumbing fixture bowl and cabinet. 261,420, 10-20-81, Cl. D23-59.000.
 Yates, Dow. Chlorine generator. 261,415, 10-20-81, Cl. D23-3.000.
 Zimmer USA, Inc.: See—
 Bruhn, John A., 261,425, Cl. D24-26.000.

LIST OF PLANT PATENTEES

Duffett, William E.: See—
Jessel, Walter H., Jr.; and Duffett, William E., 4,778, Cl. 68.000.
Hartman, Marsha W., heir: See—
Wassiliew, Fedor, deceased; Wassiliew, Nicolaus, heir; Wassiliew, Alexander, heir; Hartman, Marsha W., heir; and Wassiliew, Valentina, heir, 4,780, Cl. 43.000.
Jackson & Perkins Co.: See—
Wassiliew, Fedor, deceased; Wassiliew, Nicolaus, heir; Wassiliew, Alexander, heir; Hartman, Marsha W., heir; and Wassiliew, Valentina, heir, 4,780, Cl. 43.000.
Jessel, Walter H., Jr.; and Duffett, William E., to Yoder Brothers, Inc. Geranium plant. 4,778, 10-20-81, Cl. 68.000.
Ryan, John J. Impatiens plant named Chinook. 4,779, 10-20-81, Cl. 68.000.

Wassiliew, Alexander, heir: See—
Wassiliew, Fedor, deceased; Wassiliew, Nicolaus, heir; Wassiliew, Alexander, heir; Hartman, Marsha W., heir; and Wassiliew, Valentina, heir, 4,780, Cl. 43.000.
Wassiliew, Fedor, deceased; by Wassiliew, Nicolaus, heir; by Wassiliew, Alexander, heir; by Hartman, Marsha W., heir; and by Wassiliew, Valentina, heir, to Jackson & Perkins Co. Dwarf peach W-114. 4,780, 10-20-81, Cl. 43.000.
Wassiliew, Nicolaus, heir: See—
Wassiliew, Fedor, deceased; Wassiliew, Nicolaus, heir; Wassiliew, Alexander, heir; Hartman, Marsha W., heir; and Wassiliew, Valentina, heir, 4,780, Cl. 43.000.
Wassiliew, Valentina, heir: See—
Wassiliew, Fedor, deceased; Wassiliew, Nicolaus, heir; Wassiliew, Alexander, heir; Hartman, Marsha W., heir; and Wassiliew, Valentina, heir, 4,780, Cl. 43.000.
Yoder Brothers, Inc.: See—
Jessel, Walter H., Jr.; and Duffett, William E., 4,778, Cl. 68.000.

PI 46

CLASSIFICATION OF PATENTS

ISSUED OCTOBER 20, 1981

NOTE.—First number, class; second number, subclass; third number, patent number

CLASS 2	347	4,295,274	CLASS 57	782	4,295,391	CLASS 113	370.2	4,295,499
2	4,295,227	CLASS 33	86	Re.30,776	CLASS 75	80 D	435	4,295,500
18	4,295,228	1 G	245	4,295,329	0.5 AA	202	92.1	4,295,501
20	4,295,229	181 R	263	4,295,330	1 T	210	11	4,295,502
69.5	4,295,230	182	263	4,295,330	10 R	317	90	4,295,503
338	4,295,231	334	39.02	4,295,331	52	412	290	4,295,504
CLASS 4	4,295,232	CLASS 34	264	4,295,332	68 R	425	301	4,295,505
480	Re.30,774	5	562	4,295,336	93 R	657	193 D	4,295,506
498	4,295,233	10	641.6	4,295,333	208 R	668	208 B	4,295,507
619	4,295,233	27	669	4,295,334	CLASS 81	695	1	4,295,508
CLASS 5	4,295,234	97	673	4,295,335	3.32	19	1.5	4,295,509
473	4,295,235	155	54	4,295,337	57.37	136 R	6.16	4,295,510
CLASS 8	4,295,244	CLASS 37	55.5	4,295,338	57.4	164	12.7 A	4,295,511
115.5	4,295,245	43 D	64	4,295,339	121 R	300	144	4,295,512
139.1	4,295,246	58	82	4,295,340	CLASS 82	435	52 R	4,295,513
186	4,295,247	103	100	4,295,341	1 C	449	158	4,295,514
189	4,295,248	CLASS 40	119	4,295,342	20	556	220	4,295,515
421	4,295,249	16.4	309	4,295,343	31	569	354 R	4,295,516
524	4,295,250	CLASS 42	324.5	4,295,344	CLASS 83	574	358	4,295,517
560	4,295,251	1 A	371	4,295,345	251	590	69	4,295,518
CLASS 9	4,295,252	CLASS 44	500	4,295,346	545	60	121	4,295,519
2 S	4,295,253	1 SR	32	4,295,347	864	121	174	4,295,520
8 P	4,295,254	51	CLASS 64	4,295,348	CLASS 84	247	214	4,295,521
CLASS 12	4,295,255	63	27 L	4,295,349	1.03	424	246	4,295,522
142 RS	4,295,256	72	CLASS 65	4,295,350	293	425	251	4,295,523
CLASS 13	4,295,257	CLASS 46	3.11	4,295,351	314 N	425	307.3	4,295,524
12	4,295,258	74 C	3.12	4,295,352	413	425	314	4,295,525
CLASS 15	4,295,259	161	3.41	4,295,353	470 R	425	315	4,295,526
1.5 R	4,295,260	201	30.11	4,295,354	471 R	425	315	4,295,527
22 R	4,295,261	202	108	4,295,355	484	425	315	4,295,528
230.11	4,295,262	205	CLASS 70	4,295,356	CLASS 86	425	315	4,295,529
235.7	4,295,263	259	111	4,295,357	CLASS 89	425	315	4,295,530
320	4,295,264	CLASS 47	454	4,295,358	12	425	315	4,295,531
CLASS 16	4,295,265	82	CLASS 71	4,295,359	CLASS 91	425	315	4,295,532
80	4,295,266	CLASS 49	67	4,295,360	11	425	315	4,295,533
121	4,295,267	42	88	4,295,361	80 R	425	315	4,295,534
CLASS 17	4,295,268	353	90	4,295,362	303.18	425	315	4,295,535
1 R	4,295,269	504	120	4,295,363	419 PT	425	315	4,295,536
CLASS 19	4,295,270	CLASS 51	38	4,295,364	5 L	425	315	4,295,537
113	4,295,271	163.2	57	4,295,365	98	425	315	4,295,538
225	4,295,272	165.88	180	4,295,366	CLASS 98	425	315	4,295,539
CLASS 23	4,295,273	CLASS 52	225	4,295,367	31	425	315	4,295,540
230 B	4,295,274	2	242	4,295,368	33 R	425	315	4,295,541
230 PC	4,295,275	81	250	4,295,369	88 R	425	315	4,295,542
232 E	4,295,276	90	453.06	4,295,370	CLASS 99	425	315	4,295,543
301	4,295,277	172	CLASS 73	4,295,371	355	425	315	4,295,544
CLASS 24	4,295,278	208	5	4,295,372	427	425	315	4,295,545
122.6	4,295,279	236.1	15.6	4,295,373	486	425	315	4,295,546
CLASS 28	4,295,280	296	40.5 R	4,295,374	CLASS 101	425	315	4,295,547
112	4,295,281	309.7	104	4,295,375	216	425	315	4,295,548
248	4,295,282	334	117.3	4,295,376	232	425	315	4,295,549
255	4,295,283	396	119 A	4,295,377	349	425	315	4,295,550
CLASS 29	4,295,284	408	153	4,295,378	CLASS 102	425	315	4,295,551
25.42	Re.30,775	438	155	4,295,379	322	425	315	4,295,552
33 M	4,295,285	553	184	4,295,380	326	425	315	4,295,553
157.3 V	4,295,286	573	192	4,295,381	451	425	315	4,295,554
159.01	4,295,287	588	261	4,295,382	CLASS 104	425	315	4,295,555
240	4,295,288	637	304 C	4,295,383	32 R	425	315	4,295,556
283	4,295,289	693	359 A	4,295,384	CLASS 105	425	315	4,295,557
402.18	4,295,290	785	382 G	4,295,385	168	425	315	4,295,558
426.5	4,295,291	CLASS 53	505	4,295,386	197 DB	425	315	4,295,559
451	4,295,292	201	579	4,295,387	308 E	425	315	4,295,560
462	4,295,293	381 R	582	4,295,388	80	425	315	4,295,561
561	4,295,294	450	724	4,295,389	242	425	315	4,295,562
571	4,295,295	CLASS 55	761	4,295,390	18.19	425	315	4,295,563
CLASS 30	4,295,296	21	861.25	4,295,391	18.33	425	315	4,295,564
276	4,295,297	40	862.62	4,295,392	21	425	315	4,295,565
293	4,295,298	84	864.11	4,295,393	22	425	315	4,295,566
CLASS 31	4,295,299	228	CLASS 74	4,295,394	120	425	315	4,295,567
276	4,295,300	302	3.5	4,295,395	155	425	315	4,295,568
CLASS 32	4,295,301	CLASS 56	5 R	4,295,396	CLASS 108	425	315	4,295,569
276	4,295,302	10.2	68	4,295,397	55.1	425	315	4,295,570
293	4,295,303	11.3	424.8 NA	4,295,398	149	425	315	4,295,571
CLASS 33	4,295,304	12.7	478	4,295,399	241	425	315	4,295,572
276	4,295,305	13.9	579 R	4,295,400	314	425	315	4,295,573
293	4,295,306	313	586	4,295,401	322	425	315	4,295,574

PI 47

CLASSIFICATION OF PATENTS

CLASS 172	279	4,295,564	52 AL	4,295,598	584	4,295,988	92	4,295,654	793	4,296,366
7	4,295,530	455	CLASS 233		CLASS 254		CLASS 280		CLASS 322	4,296,367
42	4,295,531	457	7	4,295,600	10.5	4,295,634	11.2	4,295,655	75	4,296,368
184	4,295,532	534	26	4,295,601	93 HP	4,295,635	87.04 A	4,295,656	CLASS 323	
		597	CLASS 235		304	4,295,636	91	4,295,657	CLASS 324	
CLASS 174		CLASS 208	61 L	4,296,313	CLASS 256		276	4,295,658	218	4,296,369
28	4,296,271	10	92 SB	4,296,314	13.1	4,295,637	405 R	4,295,659	CLASS 325	
68.5	4,296,272	120	460	4,296,315	59	4,295,638	714	4,295,660	CLASS 326	
99 B	4,296,273	127	CLASS 236		18 EP	4,296,004	765	4,295,661	54	4,296,370
142	4,296,274	138	1 G	4,295,603	23 EP	4,296,005	27.5	4,295,662	61 R	4,296,371
152 GM	4,296,275		21 R	4,295,604	23.7 N	4,296,007		4,295,663	71 CP	4,296,372
179	4,296,276		56	4,295,605	27 BB	4,296,008	1 A	4,295,664	71 EB	4,296,373
			93 B	4,295,602	28.5 R	4,296,009	CLASS 283		77 B	4,296,374
CLASS 175		CLASS 209	CLASS 237		29.2 TN	4,296,010	CLASS 285		103 P	4,296,375
19	4,295,533	167	12.1	4,295,606	29.3	4,296,011	3	4,295,665	235	4,296,376
88	4,295,534	634	CLASS 239		29.6 ME	4,296,015	14	4,295,666	252	4,296,377
101	4,295,535	657	1	4,295,607	29.6 NR	4,296,014	18	4,295,667	313	4,296,378
214	4,295,536		14	4,295,608	29.6 SQ	4,296,016	21	4,295,668	357	4,296,379
CLASS 177		CLASS 210	29	4,295,609	29.6 TA	4,296,013	47	4,295,669	CLASS 328	
15	4,295,537	108	230	4,295,610	29.6 XA	4,296,012	91	4,295,670	48	4,296,380
CLASS 178		130	265.37	4,295,611	30.6 R	4,296,017	223	4,295,671	CLASS 330	
695	4,295,473	169	310	4,295,612	32.8 EP	4,296,018	287	4,295,672	149	4,296,381
CLASS 179		180	CLASS 241		33.4 R	4,296,019	CLASS 290		264	4,296,382
1 E	4,296,280	198.3	2	4,295,613	37 N	4,296,020	37 R	4,296,334	301	4,296,383
1 SM	4,296,279	223	18	Re.30,779	40 R	4,296,021	CLASS 292		CLASS 331	
1 VC	4,296,277	230	34	4,295,614	42.46	4,296,022	78	4,296,384	78	4,296,384
1 VL	4,296,278	232	182	4,295,615	45.75 F	4,296,023	90	4,296,385	90	4,296,385
18 EB	4,296,281	695	241	4,295,616	112 B	4,296,024	94.5 H	4,296,386	94.5 H	4,296,386
99 LS	4,296,282	710	CLASS 244		112 R	4,296,025	94.5 L	4,296,387	94.5 L	4,296,388
		738	3.29	4,295,617	123.5	4,296,026	CLASS 333		160	4,296,389
CLASS 180		789	CLASS 248		160	4,296,028	160	4,296,390	182	4,296,390
165	4,295,538	800	73	4,295,618	239 A	4,296,030	182	4,296,391	193	4,296,391
243	4,295,539		95	4,295,619	239.3 D	4,296,031	213	4,296,392	CLASS 335	
271	4,295,540	200	154	4,295,620	239.3 R	4,296,029	125	4,296,393	207	4,296,394
315	4,295,541	247	183	4,295,621	245.2 R	4,296,032	193	4,296,395	CLASS 336	
CLASS 181		348	313	4,295,622	326.2	4,296,033	171	4,296,396	60	4,296,395
108	4,295,542	CLASS 219	456	4,295,623	333	4,296,035	CLASS 337		CLASS 337	
CLASS 182		8.5	466	4,295,624	340.7	4,296,036	125	4,296,393	66	4,296,396
3	4,295,543	10.41	575	4,295,625	343.21	4,296,038	207	4,296,394	199	4,296,397
106	4,295,544	10.49 R	588	4,295,626	343.45	4,296,039	60	4,296,395	297	4,296,398
CLASS 184		10.55 B	CLASS 249		343.6	4,296,037	CLASS 338		CLASS 338	
55 A	4,295,545	10.55 F	80	4,295,628	345.2	4,296,040	125	4,296,393	34	4,296,399
CLASS 188		10.55 M	160	4,295,629	345.9 R	4,296,041	CLASS 339		8 P	4,295,694
2 R	4,295,547	10.81	204	4,296,316	345.9 R	4,296,042	8 P	4,295,694	17 C	4,295,696
72.7	4,295,548	61.7	215	4,296,317	352	4,296,043	17 C	4,295,696	17 F	4,295,695
218 A	4,295,549	69 G	225	4,296,318	352	4,296,043	17 F	4,295,695	22 R	4,295,697
378	4,295,546	69 M	227	4,296,319	352	4,296,043	17 F	4,295,695	59 R	4,295,698
CLASS 192		78.13	252	4,296,320	352	4,296,043	17 F	4,295,695	61 M	4,295,699
0.076	4,295,551	86.41	254	4,296,321	352	4,296,043	17 F	4,295,695	94 A	4,295,701
58 B	4,295,550	101	282	4,296,322	352	4,296,043	17 F	4,295,695	97 P	4,295,702
81 C	4,295,552	121 ED	339	4,296,323	352	4,296,043	17 F	4,295,695	98	4,295,703
84 C	4,295,553	124.34	347	4,296,324	352	4,296,043	17 F	4,295,695	99 R	4,295,704
105 CE	4,295,554	136	372	4,296,325	352	4,296,043	17 F	4,295,695	220 R	4,295,705
139	4,295,555	216	423 R	4,296,326	352	4,296,043	17 F	4,295,695	CLASS 340	
CLASS 198		440	436	4,296,327	352	4,296,043	17 F	4,295,695	32	4,296,400
325	4,295,556	501	453	4,296,328	352	4,296,043	17 F	4,295,695	38 L	4,296,401
382	4,295,557	504 R	455	4,296,329	352	4,296,043	17 F	4,295,695	64	4,296,402
440	4,295,558	517	457	4,296,330	352	4,296,043	17 F	4,295,695	146.3 AG	4,296,403
517	4,295,560	598	459	4,296,331	352	4,296,043	17 F	4,295,695	147 P	4,296,404
598	4,295,559	735	461	4,296,332	352	4,296,043	17 F	4,295,695	149 A	4,296,405
735	4,295,561		570	4,296,333	352	4,296,043	17 F	4,295,695	166 R	4,296,406
CLASS 200		16 D	572	4,296,334	352	4,296,043	17 F	4,295,695	347 CC	4,296,407
48 R	4,296,284	48 R	CLASS 251		352	4,296,043	17 F	4,295,695	539	4,296,408
61.08	4,296,285	61.08	14	4,295,630	352	4,296,043	17 F	4,295,695	684	4,296,409
61.54	4,296,286	83 P	30	4,295,631	352	4,296,043	17 F	4,295,695	686	4,296,410
83 P	4,296,287	146 R	127	4,295,632	352	4,296,043	17 F	4,295,695	870.02	4,296,411
146 R	4,296,288	148 R	172	4,295,633	352	4,296,043	17 F	4,295,695	870.19	4,296,412
325	4,296,290	325	CLASS 252		352	4,296,043	17 F	4,295,695	870.38	4,296,413
331	4,296,291	331	8.55 D	4,295,980	352	4,296,043	17 F	4,295,695	CLASS 343	
336	4,296,292	336	8.55 E	4,295,979	352	4,296,043	17 F	4,295,695	5 SW	4,296,414
CLASS 202		153	8.9	4,295,976	352	4,296,043	17 F	4,295,695	16 M	4,296,415
155	4,295,936	155	33.4	4,295,981	352	4,296,043	17 F	4,295,695	792.5	4,296,416
248	4,295,938	248	42	4,295,982	352	4,296,043	17 F	4,295,695	CLASS 346	
CLASS 204		32 R	49.6	4,295,983	352	4,296,043	17 F	4,295,695	75	4,296,417
1 T	4,295,939	321	62	4,295,984	352	4,296,043	17 F	4,295,695	135.1	4,296,418
2.1	4,295,940	35 R	105	4,295,985	352	4,296,043	17 F	4,295,695	140 R	4,296,419
35 R	4,295,941	96	188	4,295,986	352	4,296,043	17 F	4,295,695	160	4,296,420
96	4,295,942	96	194	4,295,987	352	4,296,043	17 F	4,295,695	241 R	4,296,421
98	4,295,943	98	301.4 F	4,295,988	352	4,296,043	17 F	4,295,695	370	4,296,422
128	4,295,944	128	429 B	4,295,989	352	4,296,043	17 F	4,295,695	387	4,296,423
149	4,295,945	149	429 C	4,295,990	352	4,296,043	17 F	4,295,695	CLASS 350	
159.15	4,295,946	159.15	430	4,295,991	352	4,296,043	17 F	4,295,695	58	4,295,706
159.23	4,295,947	159.23	431 C	4,295,992	352	4,296,043	17 F	4,295,695	96.20	4,295,707
180 G	4,295,948	180 G	439	4,295,993	352	4,296,043	17 F	4,295,695	289	4,295,708
180 P	4,295,949	180 P	455 R	4,295,994	352	4,296,043	17 F	4,295,695	292	4,295,709
242	4,295,950	242	458	4,295,995	352	4,296,043	17 F	4,295,695	310	4,295,710
252	4,295,951	252	518	4,295,996	352	4,296,043	17 F	4,295,695	334	4,295,711
257	4,295,952	257	570	4,295,997	352	4,296,043	17 F	4,295,695		
CLASS 206		257	CLASS 229		352	4,296,043	17 F	4,295,695		
158	4,295,562	158	2.5 EC	4,295,597	352	4,296,043	17 F	4,295,695		
205	4,295,563	205	34 R	4,295,599	352	4,296,043	17 F	4,295,695		

CLASSIFICATION OF PATENTS

344	4,295,712	96	4,296,462	377	4,295,767	119	4,296,101	398	4,296,175		
CLASS 352		CLASS 364		387	4,295,768	130	4,296,102	407	4,296,176	CLASS 521	
235	4,295,713	200	4,296,463	411	4,295,769	153	4,296,103	408	4,296,177	53	4,296,207
CLASS 354			4,296,464	531	4,295,770	180	4,296,104	462	4,296,178	77	4,296,208
3	4,295,714		4,296,465	CLASS 414			4,296,105	498	4,296,179	85	4,296,209
25	4,295,715		4,296,466	5	4,295,771	181	4,296,107	558	4,296,180	154	4,296,210
30	4,295,716		4,296,467	38	4,295,772	210	4,296,106	626	4,296,181	154	4,296,211
33	4,295,717		4,296,468	187	4,295,773	241	4,296,108	629	4,296,182	163	4,296,212
50	4,295,718		4,296,469	331	4,295,774	244	4,296,109	653	4,296,183	166	4,296,213
424	4,295,719		4,296,470	375	4,295,775	246	4,296,110			CLASS 525	
51	4,295,720	424	4,296,471	405	4,295,776		4,296,111	CLASS 429		2	4,296,214
509	4,295,721	509	4,296,472	458	4,295,777		4,296,112	14	4,296,184	28	4,296,215
64	4,295,722	520	4,296,473	525 R	4,295,778		4,296,113	48	4,296,185	66	4,296,216
146	4,295,722	560	4,296,474	685	4,295,779	248.52	4,296,114	54	4,296,186	390	4,296,217
155	4,295,723	900	4,296,475	749	4,295,780	263	4,296,115	105	4,296,187	439	4,296,218
238	4,295,724		4,296,476	CLASS 415		272	4,296,116	111	4,296,188	488	4,296,219
244	4,295,725		4,296,477	1	4,295,781	273 B	4,296,117			507	4,296,220
246	4,295,726	CLASS 365		1	4,295,782	273 P	4,296,118	CLASS 430			
298	4,295,727		4,296,478	2 R	4,295,783	274	4,296,119	5	4,296,189	CLASS 526	
321	4,295,728	112	4,296,479	162	4,295,784	285	4,296,120	57	4,296,190	87	4,296,221
324	4,295,729	229	4,296,480	174	4,295,785	275	4,296,121		4,296,191	119	4,296,222
325	4,295,730	CLASS 366		197	4,295,786	287	4,296,122	109	4,296,192	125	4,296,223
CLASS 355		3	4,295,744	202	4,295,788	309	4,296,123	149	4,296,193	243	4,296,224
14 R	4,295,731	302	4,295,745	CLASS 367			4,296,124	176	4,296,194	260	4,296,225
14 SH	4,295,733	CLASS 367		213 A	4,295,789	315	4,296,125	215	4,296,195	316	4,296,226
15	4,295,734	13	4,296,483	226	4,295,790	316	4,296,126	271	4,296,196	320	4,296,227
43	4,295,735	20	4,296,481	241 B	4,295,791	337	4,296,127	300	4,296,197	CLASS 528	
57	4,295,736	71	4,296,484	CLASS 416		339	4,296,128	403	4,296,198	33	4,296,228
76	4,295,737	77	4,296,485	CLASS 417		347	4,296,129	551	4,296,199	45	4,296,229
CLASS 356		91	4,296,482	15	4,295,792	CLASS 425	4,296,131	CLASS 431		67	4,296,230
32	4,295,738	140	4,296,486	36	4,295,793	7	4,295,808	4	4,295,816	179	4,296,232
43	4,295,739	169	4,296,487	62	4,295,794	72 S	4,295,809	7	4,295,817	CLASS 536	
152	4,295,740	CLASS 368		111	4,295,795	110	4,295,810		4,295,818	CLASS 536	
349	4,295,741	80	4,296,488	115	4,295,796	112	4,295,811	143	4,295,819	5	4,296,233
373	4,295,742	87	4,296,490	203	4,295,797	114	4,295,812	191	4,295,820	47	4,296,234
431	4,295,743	205	4,296,489	212	4,295,798	121	4,295,813	353	4,295,821	85	4,296,235
CLASS 357		CLASS 369		240	4,295,799	517	4,295,814	CLASS 432		CLASS 542	
1	4,296,424	59	4,296,491	333	4,295,800	556	4,295,815	29	4,295,822	420	4,296,236
17	4,296,425	CLASS 370		397	4,295,801	CLASS 426		106	4,295,823	CLASS 544	
23	4,296,426	405	4,295,802	423 R	4,295,803	2	4,296,132	115	4,295,824	CLASS 544	
39	4,296,427	14	4,296,492	CLASS 418		23	4,296,133	116	4,295,825	405	4,296,237
41	4,296,428	48	4,296,493	15	4,295,804	250	4,296,134	185	4,295,826	CLASS 546	
55	4,296,429	CLASS 371		61 B	4,295,805	275	4,296,135	CLASS 433		CLASS 546	
CLASS 358		13	4,296,494	97	4,295,806	534	4,296,136	81	4,295,827	97	4,296,238
8	4,296,430	22	4,296,495	170	4,295,807	536	4,296,137	90	4,295,828	271	4,296,239
12	4,296,431	CLASS 376		CLASS 422		575	4,296,138	99	4,295,829	CLASS 556	
28	4,296,432	203	4,295,934	24	4,296,066	613	4,296,140	115	4,295,830	406	4,296,240
37	4,296,433	285	4,295,935	26	4,296,067	CLASS 427	4,296,141	CLASS 434		CLASS 560	
105	4,296,434	CLASS 400		62	4,296,068	47	4,296,142	118	4,295,831	124	4,296,241
166	4,296,435	119	4,295,746	64	4,296,069	28	4,296,143	168	4,295,832	160	4,296,242
167	4,296,436	CLASS 402		65	4,296,070	38	4,296,144	CLASS 435		210	4,296,243
173	4,296,437	75	4,295,747	254	4,296,072	47	4,296,145	7	4,296,201	CLASS 562	
214	4,296,438	CLASS 403		CLASS 423		58	4,296,146	29	4,296,202	470	4,296,244
257	4,296,439	24	4,295,748	3	4,296,073	120	4,296,147	104	4,296,203	494	4,296,245
293	4,296,441	7	4,295,749	4	4,296,074	125	4,296,148	235	4,296,204	503	4,296,246
CLASS 360		211	4,295,750	7	4,296,075	130	4,296,149	240	4,296,205	CLASS 564	
6	4,296,442	259	4,295,751	53	4,296,076	164	4,296,150	CLASS 440		CLASS 564	
10	4,296,443	306	4,295,752	240	4,296,077	255.1	4,296,151	63	4,295,833	70	4,296,252
65	4,296,444	317	4,295,753	242	4,296,078	440	4,296,152	76	4,295,834	153	4,296,253
73	4,296,445	369	4,295,754	244	4,296,079	444	4,296,153	78	4,295,835	215	4,296,254
113	4,296,446	CLASS 405		245	4,296,080	CLASS 428		1	4,296,496	215	4,296,255
135	4,296,448	66	4,295,755	305	4,296,081	15	4,296,154	CLASS 445		CLASS 568	
CLASS 361		70	4,295,756	321	4,296,082	31	4,296,155	51	4,295,836	330	4,296,256
3	4,296,449	163	4,295,757	351	4,296,083	35	4,296,156	83	4,295,837	361	4,296,257
50	4,296,450	201	4,295,758	359	4,296,084	36	4,296,157	153	4,295,838	364	4,296,258
80	4,296,451	243	4,295,759	392	4,296,085	65	4,296,158	CLASS 474		378	4,296,259
82	4,296,452	259	4,295,760	449	4,296,086	95	4,296,159	51	4,295,839	763	4,296,260
275	4,296,453	261	4,295,761	533	4,296,087	117	4,296,160	83	4,295,840	890	4,296,261
380	4,296,454	264	4,295,762	555	4,296,088	97	4,296,161	153	4,295,841	910	4,296,262
383	4,296,455	CLASS 408		CLASS 424		212	4,296,162	342	4,295,842	CLASS 570	
403	4,296,456	86	4,295,763	11	4,296,090	213	4,296,163	354	4,295,843	128	4,296,264
413	4,296,457	CLASS 409		18	4,296,091	219	4,296,164	CLASS 493		138	4,296,265
433	4,296,458	296	4,295,764	43	4,296,092	264	4,296,165	105	4,295,838	CLASS 585	
CLASS 362		101	4,295,765	45	4,296,093	284	4,296,166	90	4,295,890	640	4,296,266
104	4,296,459	CLASS 410		49	4,296,094	288	4,296,167	99	4,295,891		
200	4,296,460	113	4,295,766	52	4,296,095	298	4,296,168	120	4,295,892		
CLASS 363		CLASS 411		78	4,296,096	313	4,296,169	CLASS 501			
22	4,296,461	105	4,295,767	94	4,296,097	321	4,296,170	90	4,295,890		
		108	4,296,766	105	4,296,098	378	4,296,171	99	4,295,891		
				108	4,296,100	389	4,296,172	120	4,295,892		

CLASSIFICATION OF DESIGNS

D2—	25	261,320		196	261,341		413	261,363		261,385		226	261,406			261,427	
		261,321			261,342		438	261,364		158	261,386		253	261,407		41	261,428
		261,322	D7—	47	261,343	D10—	38	261,365		192	261,387	D22—	1	261,408		51	261,429
	28	261,323		62	261,344		47	261,366	D14—	25	261,388		13	261,409		64	261,430
		261,324		70	261,345		60	261,367	D15—	112	261,389		23	261,411	D25—	10	261,431
	309	261,325		101	261,346		62	261,368		116	261,390		24	261,412		36	261,432
D3—	35	261,326		130	261,347		69	261,369		120	261,391		29	261,410		50	261,433
	36	261,327		131	261,348		73	261,370		140	261,392	D23—	3	261,415			261,434
	71	261,328		132	261,349		106	261,371	D16—	4	261,393		4	261,413			261,435
D6—	30	261,329	D8—	10	261,351	D11—	40	261,372		06	261,394		7	261,414		97	261,436
	37	261,330		30	261,352		131	261,373		11	261,395		34	261,416	D26—	80	261,437
		261,331		71	261,353		158	261,374		35	261,396		35	261,417		03	261,438
	55	261,332		306	261,354			261,375		131	261,397		42	261,418	D27—	87	261,439
	57	261,333		331	261,355	D12—	1	261,376	D18—	7	261,398			261,419			261,440
	63	261,334		382	261,356		128	261,378		10	261,399		59	261,420	D28—	20	261,441
	72	261,335		499	261,357		143	261,379	D19—	66	261,400		147	261,421		35	261,442
	79	261,336	D9—	337	261,359			261,380	D20—	41	261,401			261,422	D29—	6	261,443
	99	261,337		346	261,358		146	261,381		13	261,402	D24—	10	261,423	D32—	58	261,444
	113	261,338		375	261,360		147	261,382	D21—	101	261,403		16	261,424	D34—	33	261,445
	152	261,339			261,361			261,383		122	261,404		26	261,425		43	261,446
	191	261,340		376	261,362			261,384		187	261,405		38	261,426	D99—	33	261,447

CLASSIFICATION OF PLANTS

P—	43	4,780	68	4,778	4,779				
----	----	-------	----	-------	-------	--	--	--	--

GEOGRAPHICAL INDEX OF RESIDENCE OF INVENTORS

(U.S. States, Territories and Armed Forces, the Commonwealth of Puerto Rico, and the Canal Zone)

Alabama	1	Kentucky	21	Oregon	41
Alaska	2	Louisiana	22	Pennsylvania	42
American Samoa	3	Maine	23	Puerto Rico	43
Arizona	4	Maryland	24	Rhode Island	44
Arkansas	5	Massachusetts	25	South Carolina	45
California	6	Michigan	26	South Dakota	46
Canal Zone	7	Minnesota	27	Tennessee	47
Colorado	8	Mississippi	28	Texas	48
Connecticut	9	Missouri	29	Utah	49
Delaware	10	Montana	30	Vermont	50
District of Columbia	11	Nebraska	31	Virginia	51
Florida	12	Nevada	32	Virgin Islands	52
Georgia	13	New Hampshire	33	Washington	53
Guam	14	New Jersey	34	West Virginia	54
Hawaii	15	New Mexico	35	Wisconsin	55
Idaho	16	New York	36	Wyoming	56
Illinois	17	North Carolina	37	U.S. Air Force	57
Indiana	18	North Dakota	38	U.S. Army	58
Iowa	19	Ohio	39	U.S. Navy	59
Kansas	20	Oklahoma	40		

(First number in listing denotes location according to above key. Refer to patent number in body of the Official Gazette to obtain details as to inventor name, location, etc.)

PATENTS

6 : 4,296,476	4,295,651	4,295,760	4,295,324	4,295,765	20 : 4,296,474
01 : 4,295,617	4,295,664	4,295,880	4,295,400	4,295,798	4,295,532
	4,295,761	4,295,674	4,295,401	4,295,815	4,295,616
04 : 4,295,271	4,295,683	4,296,077	4,295,438	4,295,833	4,295,795
	4,295,359	4,295,689	4,295,450	4,295,858	4,295,838
	4,295,463	4,295,694	4,295,481	4,295,860	4,295,692
	4,295,472	4,295,704	4,295,482	4,295,916	4,295,768
	4,295,538	4,295,710	4,295,483	4,295,919	4,296,197
	4,295,836	4,295,730	4,295,355	4,295,928	4,296,297
	4,296,315	4,295,749	4,295,373	4,295,930	4,296,299
	4,296,336	4,295,753	4,295,395	4,295,932	4,295,263
	4,296,376	4,295,755	4,295,484	4,295,955	4,295,366
	4,296,404	4,295,773	4,295,518	4,295,959	4,295,529
	4,296,464	4,295,793	4,295,611	4,295,960	4,295,757
	4,296,465	4,295,813	4,295,631	4,295,961	4,295,956
	4,296,465	4,295,818	4,295,666	4,295,975	4,295,957
06 : 4,295,237	4,295,832	4,295,673	4,295,673	4,295,994	4,295,958
	4,295,258	4,295,738	4,295,738	4,295,996	4,295,966
	4,295,267	4,295,839	4,295,739	4,296,254	4,295,966
	4,295,279	4,295,874	4,295,741	4,296,257	4,295,995
	4,295,285	4,295,901	4,295,741	4,296,429	4,295,996
	4,295,293	4,295,905	4,295,756	4,296,142	4,295,996
	4,295,295	4,295,908	4,295,763	4,296,156	4,295,232
	4,295,303	4,295,912	4,295,784	4,296,179	4,295,334
	4,295,333	4,295,922	4,295,811	4,295,573	4,295,404
	4,295,338	4,295,936	4,295,812	4,295,598	4,295,425
	4,295,346	4,296,042	4,295,881	4,295,676	4,295,462
	4,295,376	4,296,052	4,295,909	4,296,079	4,295,474
	4,295,402	4,296,074	4,295,935	4,296,462	4,295,559
	4,295,406	4,296,140	4,296,100	4,296,470	4,295,670
	4,295,407	4,296,141	4,296,120	4,296,470	4,295,827
	4,295,418	4,296,153	4,296,129	4,296,470	4,295,841
	4,295,427	4,296,208	4,296,203	4,296,470	4,295,921
	4,295,460	4,296,211	4,296,225	4,296,470	4,296,000
	4,295,466	4,296,278	4,296,311	4,296,470	4,296,022
	4,295,470	4,296,279	4,296,312	4,296,470	4,296,048
	4,295,471	4,296,319	4,296,373	4,296,470	4,296,127
	4,295,473	4,296,321	4,296,405	4,296,470	4,296,206
	4,295,487	4,296,324	4,296,461	4,296,470	4,296,330
	4,295,490	4,296,340	4,296,487	4,296,470	4,296,330
	4,295,492	4,296,354	4,295,329	4,295,329	4,295,277
	4,295,504	4,296,392	4,295,360	4,295,430	4,295,332
	4,295,505	4,296,398	4,295,609	4,295,434	4,295,370
	4,295,526	4,296,428	4,295,931	4,295,480	4,295,392
	4,295,535	4,296,431	4,295,977	4,295,514	4,295,416
	4,295,555	4,296,491	4,296,020	4,295,521	4,295,442
	4,295,557	4,295,308	4,296,110	4,295,537	4,295,506
	4,295,584	4,295,367	4,296,174	4,295,602	4,295,655
	4,295,593	4,295,385	4,296,215	4,295,619	4,295,816
	4,295,601	4,295,496	4,295,989	4,295,624	4,295,896
	4,295,604	4,295,547	4,295,273	4,295,632	4,295,941
	4,295,610	4,295,656	4,295,318	4,295,634	4,295,985
	4,295,630	4,295,669	4,295,321	4,295,698	4,295,986
	4,295,650	4,295,733		4,295,747	4,296,119
				4,295,762	4,296,176

GEOGRAPHICAL INDEX OF RESIDENCE OF INVENTORS

4,296,187	4,295,638	4,296,090	4,296,417	42 : Re.30,778	4,295,523
4,296,286	4,295,729	4,296,096	4,296,440	4,295,254	4,295,525
4,296,298	4,295,777	4,296,101	4,296,449	4,295,309	4,295,528
4,296,328	4,295,904	4,296,111	4,296,455	4,295,315	4,295,542
4,296,331	4,295,918	4,296,113	4,296,479	4,295,316	4,295,560
4,296,345	4,295,964	4,296,115	4,296,482	4,295,369	4,295,614
4,296,350	4,295,971	4,296,137	4,296,486	4,295,394	4,295,665
4,296,351	4,295,988	4,296,138	4,295,234	4,295,415	4,295,668
4,296,353	4,296,004	4,296,144	4,295,374	4,295,428	4,295,672
4,296,358	4,296,027	4,296,232	4,295,478	4,295,429	4,295,796
4,296,389	4,296,087	4,296,236	4,295,498	4,295,445	4,295,801
4,296,466	4,296,158	4,296,240	4,295,569	4,295,475	4,295,856
4,296,467	4,296,191	4,296,242	4,295,633	4,295,486	4,295,885
26 : 4,295,233	4,296,291	4,296,259	4,296,173	4,295,494	4,295,897
4,295,257	4,296,301	4,296,264	4,296,302	4,295,590	4,295,991
4,295,262	4,296,323	4,296,272	4,295,534	4,295,647	4,295,999
4,295,312	4,296,477	4,296,282	4,295,555	4,295,678	4,296,008
4,295,317	4,296,496	4,296,337	4,295,301	4,295,740	4,296,146
4,295,340	28 : 4,295,250	4,296,370	4,295,320	4,295,789	4,296,159
4,295,350	4,295,261	4,296,371	4,295,393	4,295,790	4,296,205
4,295,379	4,296,343	4,296,374	4,295,461	4,295,828	4,296,212
4,295,381	29 : 4,295,227	4,296,382	4,295,488	4,295,831	4,296,213
4,295,384	4,295,247	4,296,411	4,295,513	4,295,890	4,296,280
4,295,446	4,295,260	4,296,430	4,295,515	4,295,940	4,296,338
4,295,464	4,295,268	4,296,446	4,295,540	4,295,973	4,296,347
4,295,497	4,295,336	4,296,454	4,295,577	4,296,003	4,296,378
4,295,501	4,295,639	35 : 4,295,799	4,295,580	4,296,018	4,296,416
4,295,585	4,295,837	36 : Re.30,779	4,295,606	4,296,024	4,296,442
4,295,587	4,295,974	4,295,313	4,295,642	4,296,046	4,296,448
4,295,588	4,295,983	4,295,342	4,295,706	4,296,060	4,296,469
4,295,594	4,296,053	4,295,344	4,295,769	4,296,075	4,296,481
4,295,645	4,296,366	4,295,347	4,295,786	4,296,122	4,296,483
4,295,648	31 : 4,295,691	4,295,363	4,295,794	4,296,161	4,295,335
4,295,685	32 : 4,295,292	4,295,368	4,295,987	4,296,189	4,295,345
4,295,686	4,295,305	4,295,372	4,296,007	4,296,204	4,296,084
4,295,687	4,296,185	4,295,408	4,296,009	4,296,237	4,295,410
4,295,697	33 : 4,296,410	4,295,439	4,296,061	4,296,262	4,295,924
4,295,699	34 : Re.30,775	4,295,451	4,296,147	4,296,263	4,296,154
4,295,750	4,295,235	4,295,649	4,296,157	4,296,274	4,295,290
4,295,791	4,295,242	4,295,680	4,296,164	4,296,390	4,295,337
4,295,802	4,295,266	4,295,705	4,296,169	4,296,397	4,295,531
4,295,992	4,295,283	4,295,713	4,296,172	4,296,450	4,295,613
4,296,013	4,295,310	4,295,715	4,296,178	4,296,451	4,296,037
4,296,019	4,295,352	4,295,732	4,296,275	4,296,456	4,296,092
4,296,041	4,295,436	4,295,737	4,296,320	4,296,287	4,296,332
4,296,055	4,295,467	4,295,766	4,296,352	4,295,251	35 : Re.30,774
4,296,165	4,295,476	4,295,783	4,296,362	4,295,259	4,295,314
4,296,168	4,295,477	4,295,845	4,295,304	4,295,284	4,295,599
4,296,181	4,295,519	4,295,872	4,295,361	4,295,322	4,295,636
4,296,220	4,295,566	4,295,903	4,295,365	4,295,840	4,295,709
4,296,227	4,295,572	4,295,951	4,295,524	4,295,910	4,295,727
4,296,239	4,295,596	4,296,005	4,295,696	4,296,290	4,295,925
4,296,246	4,295,621	4,296,030	4,295,708	4,295,243	4,295,926
4,296,247	4,295,622	4,296,069	4,295,744	4,295,544	4,295,927
4,296,248	4,295,646	4,296,070	4,295,861	4,295,564	4,295,929
4,296,249	4,295,688	4,296,132	4,295,862	4,295,586	4,296,104
4,296,250	4,295,788	4,296,160	4,295,962	4,295,752	4,296,130
4,296,253	4,295,826	4,296,162	4,295,979	4,295,767	4,296,327
4,296,256	4,295,844	4,296,184	4,295,980	4,296,406	4,296,388
4,296,313	4,295,873	4,296,192	4,295,997	4,295,231	54 : 4,295,536
4,296,344	4,295,886	4,296,195	4,295,998	4,295,236	4,295,575
4,296,472	4,295,894	4,296,229	4,296,001	4,295,264	4,296,078
27 : 4,295,244	4,295,914	4,296,238	4,296,057	4,295,269	4,295,383
4,295,270	4,295,950	4,296,244	4,296,151	4,295,289	4,295,491
4,295,274	4,295,954	4,296,252	4,296,484	4,295,319	4,295,772
4,295,282	4,295,978	4,296,283	4,296,485	4,295,377	4,295,835
4,295,327	4,295,982	4,296,296	4,295,403	4,295,378	4,295,907
4,295,432	4,296,033	4,296,335	4,295,409	4,295,390	4,296,002
4,295,468	4,296,035	4,296,399	4,295,640	4,295,424	4,296,134
4,295,469	4,296,058	4,296,408	4,295,677	4,295,437	4,296,310
4,295,541	4,296,080	4,296,413	4,296,284	4,295,465	4,296,329
4,295,615	4,296,083	4,296,415	4,296,381	4,295,508	4,296,420

DESIGN PATENTS

6 : 261,363	261,429	261,414	261,399	261,337	261,341
261,364	261,439	261,436	261,443	261,340	261,352
01 : 261,432	08 : 261,327	18 : 261,334	29 : 261,368	261,435	261,354
06 : 261,323	09 : 261,353	261,425	34 : 261,404	261,444	261,369
261,324	261,377	19 : 261,329	36 : 261,320	261,360	261,371
261,336	12 : 261,342	261,330	261,321	261,361	261,415
261,338	261,431	261,357	261,322	261,362	261,396
261,373	13 : 261,347	261,416	261,335	261,328	261,410
261,386	261,390	23 : 261,407	261,378	261,359	261,421
261,401	14 : 261,438	24 : 261,333	261,387	261,379	261,422
261,402	16 : 261,427	25 : 261,345	261,397	261,384	261,442
261,406	17 : 261,325	261,440	261,403	261,385	261,443
261,409	261,346	26 : 261,420	261,405	261,376	261,372
261,413	261,351	27 : 261,358	261,424	47 : 261,376	261,348
261,419	261,351	261,391	261,326	48 : 261,339	261,437
261,426	261,400				

PLANT PATENTS

06 : 4,778	4,779	4,780			
------------	-------	-------	--	--	--

CHANGE OF ADDRESS FORM

NAME—FIRST, LAST									
COMPANY NAME OR ADDITIONAL ADDRESS LINE									
STREET ADDRESS									
CITY					STATE		ZIP CODE		

PLEASE PRINT OR TYPE

(or) COUNTRY

Mail this form to: NEW ADDRESS

Superintendent of Documents
Government Printing Office SSOM
Washington, D.C. 20402

Attach last subscription
label here.

SUBSCRIPTION ORDER FORM

SUBSCRIPTION ORDER FORM

ENTER MY SUBSCRIPTION TO:

@ \$ Domestic; @ \$ Foreign.

NAME—FIRST, LAST									
COMPANY NAME OR ADDITIONAL ADDRESS LINE									
STREET ADDRESS									
CITY					STATE		ZIP CODE		


PLEASE PRINT OR TYPE

(or) COUNTRY

☐ Remittance Enclosed (Make
checks payable to Superin-
tendent of Documents)

☐ Charge to my Deposit
Account No.

MAIL ORDER FORM TO
Superintendent of Documents
Government Printing Office
Washington, D.C. 20402



Vol. 1011 Number 4

OFFICIAL GAZETTE

of the
UNITED STATES PATENT AND TRADEMARK OFFICE

October 27, 1981



U.S.
DEPARTMENT
OF COMMERCE

Patent
and
Trademark
Office

OFFICIAL GAZETTE of the
UNITED STATES PATENT and TRADEMARK OFFICE

October 27, 1981

Volume 1011

Number 4

CONTENTS

	Page
Patent and Trademark Office Notices	
Patent Cooperation Treaty (PCT) Information	1011 OG 26
Reissue Applications Filed	1011 OG 26
Requests for Reexamination Filed	1011 OG 26
Dept. of Commerce Automation Study	1011 OG 26
Dept. of the Treasury U.S. Customs Service	1011 OG 27
Patent Certificates of Correction	1011 OG 28
Reference Collections of U.S. Patents Available for Public Use in Patent Depository Libraries	1011 OG 29
Condition of Patent Applications	1011 OG 30
Reissue Patents Granted (30,782)	1335
Plant Patents Granted (4,781)	1337
Patents Granted	
General and Mechanical (4,296,497)	1339
Chemical (4,297,098)	1541
Electrical (4,297,521)	1657
Design Patents Granted (261,445)	1733
Index of Patentees	PI 1
Indices of Reissue, Design and Plant Patentees	PI 44
Classification of	
Patents (Including Reissues)	PI 47
Designs and Plants	PI 50
Geographical Index of Residence of Inventors	
Patents (Including Reissues)	PI 51
Designs and Plants	PI 52
Change of Address Form and Subscription Order Form	Back Page

The following are mailed under direction of the Superintendent of Documents, Government Printing Office, Washington, D.C., 20402, to whom all subscriptions should be made payable and all communications addressed:

THE OFFICIAL GAZETTE (PATENT SECTION), issued weekly, subscription \$325.00 per annum for first-class mailing, also available as fourth-class mail at \$225.00 domestic; \$281.25 foreign; foreign first-class mailing rates will be furnished upon request; single copies each, \$5.50 domestic, \$6.90 foreign.

THE OFFICIAL GAZETTE (TRADEMARK SECTION), issued weekly, subscription \$105.00 per annum, foreign mailing \$131.25 per annum; single copies \$2.75 each domestic, \$3.45 foreign.

GENERAL INFORMATION concerning PATENTS, price \$2.25 each.

GENERAL INFORMATION concerning TRADEMARKS, price \$1.70 each.

PRINTED COPIES OF PATENTS are furnished by the Patent and Trademark Office at 50 cents each; PLANT PATENTS in color, \$1.00 each; copies of TRADEMARKS AND DESIGN PATENTS at 20 cents each. Address orders to the Commissioner of Patents and Trademarks, Washington, D.C., 20231.

PATENT AND TRADEMARK OFFICE NOTICES

Patent Cooperation Treaty Information

For information concerning the PCT, consult Chapter 1800 of the Manual of Patent Examining Procedure and notices 90-95 in the consolidated listing of notices appearing in the Official Gazette of Jan. 6, 1981.

The PCT fees in effect after May 19, 1981 are as follows:

Transmittal fee	\$ 35.00
Search fee	300.00
International Basic Fee (for the first 30 sheets of an international application)	215.00
Basic Supplemental Fee (for each sheet over 30)	4.00
International Designation Fee (for each State for which a national patent is sought, or group of States for which the same regional patent is sought)	50.00

RENE D. TEGTMEYER,
Assistant Commissioner
for Patents.

REISSUE APPLICATIONS FILED

Notice under 37 CFR 1.11(b). The reissue applications listed below are open to inspection by the general public in the indicated Examining Groups and copies may be obtained by paying the fee therefor (37 CFR 1.21(b)).

3,621,323, Re. S.N. 269,599, Filed June 2, 1981, Cl. 313/317, COATED INCANDESCENT ELECTRIC LAMP, William R. Tooke, Jr., Owner of Record: Thomas Manufacturing Co., Parkton, Md., Attorney or Agent: A. W. Breiner, Ex. Gp.: 256

4,156,973, Re. S.N. 270,420, Filed June 3, 1981, Cl. 34/86, HEATING VENT FOR ELECTRIC CLOTHES DRYER, James D. Bede, Owner of Record: Bede Industries, Inc., Bay Village, Ohio, Attorney or Agent: Charles B. Lyon, et al., Ex. Gp.: 344

4,174,281, Re. S.N. 282,001, Filed July 10, 1981, Cl. 210/786, COUNTERCURRENT DECANTATION, Christopher C. Dell, Owner of Record: National Research Development Corp., London, England, Attorney or Agent: None, Ex. Gp.: 176

4,216,062, Re. S.N. 254,250, Filed April 15, 1981, Cl. 202/248, SEALING MEANS FOR A COKE OVEN CHUCK DOOR, Calvin E. Kelly, et al., Owner of Record: United States Steel Corp., Pittsburgh, Pa., Attorney or Agent: William F. Riesmeyer, III, Ex. Gp.: 177

4,253,447, Re. S.N. 282,086, Filed July 10, 1981, Cl. 128/6, COLOR ENDOSCOPE WITH CHARGE COUPLED DEVICE AND TELEVISION VIEWING, William C. Moore, et al., Owner of Record: Welch Allyn, Inc., Skaneateles Falls, N.Y., Attorney or Agent: Richard von K. Bruns, et al., Ex. Gp.: 335

REQUESTS FOR REEXAMINATION FILED

Notice under 37 CFR 1.11(c). The requests for reexamination listed below are open to inspection by the general public in the indicated Examining Groups. Copies of the requests and related papers may be obtained by paying the fee therefor established in the Rules (37 CFR 1.21(b)).

In the event correspondence to the patent owner is not received, this notice will be considered to be constructive notice to the patent owner and reexamination will proceed (37 CFR 1.248(a)(5) and 1.525(b)).

D. 233,463, Reexam. No. 90/000,063, Requested: Sept. 3, 1981, Cl. D11/90, BEAD, Harold Roger, Owner of Record: Inventor, Attorney or Agent: Amster & Rothstein, Ex. Gp.: 292, Requester: Harold Mangelsen & Sons, Inc., c/o Henderson & Sturm, Omaha, Neb.

3,328,231, Reexam. No. 90/000,072, Requested: Sept. 18, 1981, Cl. 521/131, METHOD OF PRODUCING CAST SURFACES AND PRODUCTS OBTAINED THEREBY, John A. Sergovic, Owner of Record: The Burns & Russell Co. of Baltimore City, Baltimore, Md., Attorney or Agent: Louis F. Reed, Ex. Gp.: 143, Requester: Trenwyth Industries, Inc., Emigsville, Pa.

3,817,333, Reexam. No. 90/000,074, Requested: Sept. 25, 1981, Cl. 172/283, PLOW SYSTEM WITH PLURALITY OF PLOW UNITS AND MEANS FOR ADJUSTING SPACING BETWEEN UNITS IN A CONTINUOUS MANNER, Jon E. Kinzenbaw, Owner of Record: Dietrich Manufacturing, Inc., Goodfield, Ill., Attorney or Agent: James J. Hill, Ex. Gp.: 334, Requester: International Harvester Co., Chicago, Ill.

4,061,481, Reexam. No. 90/000,077, Requested: Sept. 30, 1981, Cl. 62/29, NATURAL GAS PROCESSING, Roy E. Campbell, et al., Owner of Record: The Orloff Corp., Midland, Tex., c/o Allan H. Bonnell, Esq., Attorney or Agent: Allan H. Bonnell, Esq., Ex. Gp.: 177, Requester: The Orloff Corp., New York, N.Y.

DEPARTMENT OF COMMERCE

Patent and Trademark Office AUTOMATION STUDY

Agency: Patent and Trademark Office, Commerce

Action: Request for Automation Technology Information

Summary: The Patent and Trademark Office requests information from firms which can provide applicable state-of-the-art technology to support automation in the areas of Patent Automation, Trademark Automation, Internal Operations, Public/Office Communications, and Printing. Such firms should provide sufficient information to allow the Patent and Trademark Office to assess the capability of the technology to meet the requirements which will be established. Such automation efforts are intended to modernize the PTO's patent, trademark, information dissemination, printing, and administrative management programs. This information should be limited to fifteen (15) pages or less and specifically address the type of support (hardware or software) offered, the programs to be supported, and how the support would be applied. If deemed appropriate, the information provided will be included in the final report of the study required by Section 9 of P.L. 96-517, which study must be submitted to the Congress on or before December 12, 1982. Proprietary information should not be submitted.

Date: Information must be submitted on or before Nov. 6, 1981.

Address Information to:
Commissioner of Patents and Trademarks
Washington, D.C. 20231
ATTN: James A. Green

For Further Information Contact: James A. Green by telephone at (703) 557-1610 or by mail marked to his attention and addressed to the Commissioner of Patents and Trademarks, Washington, D.C. 20231.

OCTOBER 27, 1981

U.S. PATENT AND TRADEMARK OFFICE

1011 OG 27

Supplemental Information: Section 9 of P.L. 96-517, which is the basis for the development of the automation plan, states:

"Sec. 9. The Commissioner of Patents and Trademarks shall report to Congress, within two years after the effective date of this Act [Dec. 12, 1980], a plan to identify and if necessary develop or have developed computerized data and retrieval systems equivalent to the latest state of the art which can be applied to all aspects of the operation of the Patent and Trademark Office, and particularly to the patent search file, the patent classification system and the trademark search file. The report shall specify the cost of implementing the plan, how rapidly the plan can be implemented by the Patent and Trademark Office, without regard to funding which is or which may be available for this purpose in the future."

During the development of the automation plan, analyses of the current state-of-the-art in a wide variety of technological areas will be conducted. The technology which will be addressed includes all types of software for search, retrieval and processing large text data bases, and hardware for mass data storage, text retrieval systems, image enhancement and retrieval, engineering graphics, optical character recognition, automated photocomposition, electronic facsimile transfer, and source data automation.

Oct. 7, 1981. GERALD J. MOSSINGHOFF,
Commissioner of
Patents and Trademarks.

Oct. 8, 1981. ROBERT B. ELLERT,
Acting Assistant Secretary for
Productivity, Technology
and Innovation.

DEPARTMENT OF THE TREASURY UNITED STATES CUSTOMS SERVICE (TMK-2-CO:R:E:E)

Notice of Application for Recordation of Trade Name "BULGARI"

Application has been filed pursuant to section 133.12, Customs Regulations (19 CFR 133.12), for the recordation under section 42 of the Act of July 5, 1946, as amended (15 U.S.C. 1124), of the trade name "BULGARI" or printed with a Roman u i.e., "BULGARI", used by Ditta Sotirio Bulgari di Costantino e Giorgio Bulgari S.A.S., a partnership organized under the laws of Italy, located at 10 Via dei Condotti, Rome, Italy.

The application states that the trade name is used in connection with a wide variety of fine watches, jewelry, ornamental works and artwork made of precious metal and precious or semi-precious stones and various other items made of precious metals, manufactured in Italy. The application states further that Bulgari Distribuzione S.P.A., 6 Via Gregoriana, Rome, Italy and Bulgari S.P.A., 10 Via Dei Condotti, Rome, Italy are authorized to use the trade name. Appropriate accompanying papers were submitted with the application.

Before final action is taken on the application, consideration will be given to any relevant data, views, or arguments submitted in writing by any person, in opposition to the recordation of this trade name. Any such submission should be addressed to the Commissioner of Customs, Washington, D.C. 20229, in time to be received no later than 30 days from the date of publication of this notice in the Federal Register.

Notice of the action taken on the application for recordation of this trade name will be published in the Federal Register.

Sept. 15, 1981. A. PIAZZA,
Acting Director, Entry Procedures
and Penalties Division.

Patent and Trademark Office

Taking Effect in the United States of the International Convention for the Protection of New Varieties of Plants

The International Convention for the Protection of New Varieties of Plants (the UPOV Convention) will take effect in the United States on November 8, 1981. It will apply to all applications for the patenting of plants under the provisions of Title 35, United States Code, which are filed on or after November 8, 1981. The actual filing date will govern in determining whether the Convention will apply to an application, even though the application may be entitled to an earlier effective date under section 119 or 120 of Title 35, United States Code.

In addition to the United States, the UPOV Convention will be in effect as of November 8, 1981, in the following fourteen States: Belgium, Denmark, Federal Republic of Germany, France, Ireland, Israel, Italy, Netherlands, New Zealand, Republic of South Africa, Spain, Sweden, Switzerland, and the United Kingdom.

No changes in the patent law are needed to implement the UPOV Convention in the United States. An applicant for a plant patent will be required, however, to submit for registration a variety name for the plant to be patented. Registration is required by Article 13 of the UPOV Convention.

Registrability shall be determined in accordance with the International Code of Nomenclature for Cultivated Plants (1980). As an interim procedure pending the promulgation of an appropriate rule, inclusion of the variety name in the application will be accepted as a submission of the name for registration. No plant patent as a result of an application filed on or after November 8, 1981, shall be issued without the registration of a variety name. Questions concerning this variety naming requirement or the UPOV Convention may be addressed to:

Mr. Michael K. Kirk, Director
Office of Legislation and International Affairs
Box 4
U.S. Patent and Trademark Office
Washington, D.C. 20231

Mr. Kirk's telephone number is (703) 557-3065.

Date: Oct. 15, 1981. GERALD J. MOSSINGHOFF,
Commissioner of Patents
and Trademarks.

PATENT NOTICES

Certificates of Correction for the Week of Oct. 27, 1981

Re. 30,610	4,260,371	4,272,999	4,279,986
Re. 30,635	4,260,892	4,273,176	4,280,073
3,624,205	4,260,960	4,273,300	4,280,332
3,730,185	4,261,285	4,273,357	4,280,370
3,783,976	4,262,115	4,273,661	4,280,384
3,897,238	4,262,657	4,274,053	4,280,476
4,142,837	4,263,251	4,274,262	4,280,688
4,150,864	4,263,494	4,274,332	4,280,898
4,170,818	4,264,201	4,274,598	4,281,426
4,179,602	4,264,495	4,274,814	4,281,627
4,183,040	4,264,682	4,274,979	4,281,658
4,184,489	4,264,685	4,275,062	4,281,717
4,185,709	4,265,305	4,275,347	4,281,884
4,195,157	4,265,977	4,275,524	4,282,043
4,201,560	4,266,067	4,275,582	4,282,096
4,205,561	4,266,747	4,275,964	4,282,379
4,214,157	4,267,039	4,276,066	4,282,483
4,218,267	4,267,107	4,276,071	4,282,622
4,227,439	4,267,167	4,276,428	4,282,719
4,228,580	4,267,344	4,276,431	4,282,908
4,230,970	4,267,619	4,276,887	4,282,932
4,231,158	4,267,824	4,277,207	4,282,934
4,231,662	4,267,999	4,277,250	4,283,306
4,233,182	4,268,777	4,277,286	4,283,516
4,233,303	4,268,789	4,277,508	4,283,660
4,233,620	4,268,827	4,277,531	4,283,832
4,237,764	4,269,556	4,277,612	4,284,259
4,243,925	4,269,988	4,277,613	4,284,479
4,245,047	4,269,995	4,277,893	4,284,694
4,246,077	4,270,038	4,277,913	4,284,806
4,249,132	4,270,269	4,278,071	4,284,812
4,251,636	4,270,921	4,278,161	4,284,936
4,253,252	4,271,312	4,278,367	4,284,992
4,253,760	4,271,605	4,278,564	4,285,420
4,254,848	4,272,106	4,278,565	4,285,424
4,255,323	4,272,185	4,278,812	4,285,589
4,256,650	4,272,289	4,278,815	4,285,986
4,257,164	4,272,357	4,279,017	4,286,039
4,257,601	4,272,409	4,279,287	4,286,082
4,257,874	4,272,469	4,279,432	
4,259,674	4,272,986	4,279,836	

Reference Collections of U.S. Patents Available for Public Use in Patent Depository Libraries

The libraries listed herein, designated as patent depository libraries, receive current issues of U.S. Patents and maintain collections of earlier issued patents. The scope of these collections varies from library to library, ranging from patents of only recent months or years in some libraries to all or most of the patents issued since 1870, or earlier, in other libraries.

These patent collections are open to public use and each of the patent depository libraries, in addition, offers the publications of the patent classification system (e.g. The Manual of Classification, Index to the U.S. Patent Classification, Classification Definitions, etc.) and provides technical staff assistance in their use to aid the public in gaining effective access to information contained in patents. With one exception, as noted in the

table following, the collections are organized in patent number sequence.

Depending upon the library, the patents may be available in microfilm, in bound volumes of paper copies, or in some combination of both. Facilities for making paper copies from either microfilm in reader-printers or from the bound volumes in paper-to-paper copies are generally provided for a fee.

Owing to variations in the scope of patent collections among the patent depository libraries and in their hours of service to the public, anyone contemplating use of the patents at a particular library is advised to contact that library, in advance, about its collection and hours, so as to avert possible inconvenience.

State	Name of Library	Telephone Contact
Alabama	Birmingham Public Library	(205) 254-2555
Arizona	Tempe: Science Library, Arizona State University	(602) 965-7607
California	Los Angeles Public Library	(213) 626-7555 Ext. 273
	Sacramento: California State Library	(916) 322-4572
	Sunnyvale: Patent Information Clearinghouse*	(408) 738-5580
Colorado	Denver Public Library	(303) 573-5152 Ext. 222
Delaware	Newark: University of Delaware	(302) 738-2238
Georgia	Atlanta: Price Gilbert Memorial Library, Georgia Institute of Technology	(404) 894-4519
Illinois	Chicago Public Library	(312) 269-2814
Louisiana	Baton Rouge: Troy H. Middleton Library, Louisiana State University	(504) 388-2570
Massachusetts	Boston Public Library	(617) 536-5400 Ext. 265
Michigan	Detroit Public Library	(313) 833-1450
Minnesota	Minneapolis Public Library & Information Center	(612) 372-6552
Missouri	Kansas City: Linda Hall Library	(816) 363-4600
	St. Louis Public Library	(314) 241-2288 Ext. 214, 215
Nebraska	Lincoln: University of Nebraska-Lincoln, Engineering Library	(402) 472-3411
New Hampshire	Durham: University of New Hampshire Library	(603) 862-1777
New Jersey	Newark Public Library	(201) 733-7814
New York	Albany: New York State Library	(518) 474-5125
	Buffalo and Erie County Public Library	(716) 856-7525 Ext. 267
	New York Public Library (The Research Libraries)	(212) 790-6291
North Carolina	Raleigh: D. H. Hill Library, N.C. State University	(919) 737-3280
Ohio	Cincinnati & Hamilton County, Public Library of	(513) 369-6936
	Cleveland Public Library	(216) 623-2870
	Columbus: Ohio State University Libraries	(614) 422-6286
	Toledo/Lucas County Public Library	(419) 255-7055 Ext. 212
Oklahoma	Stillwater: Oklahoma State University Library	(405) 624-6546
Pennsylvania	Philadelphia: Franklin Institute Library	(215) 448-1321**
	Pittsburgh: Carnegie Library of Pittsburgh	(412) 622-3138
	University Park: Pattee Library, Pennsylvania State University	(814) 865-4861
Rhode Island	Providence Public Library	(401) 521-7722 Ext. 226
Tennessee	Memphis & Shelby County Public Library and Information Center	(901) 528-2957
Texas	Dallas Public Library	(214) 748-9071
	Houston: The Fondren Library, Rice University	(713) 527-8101 Ext. 2587
Washington	Seattle: Engineering Library, University of Washington	(206) 543-0740
Wisconsin	Madison: Kurt F. Wendt Engineering Library, University of Wisconsin	(608) 262-6845
	Milwaukee Public Library	(414) 278-3043

*Collection organized by subject matter.

**Call only between the hours of 10:00 a.m. and 5:00 p.m.

PATENT EXAMINING CORPS
RENE D. TEGMEYER, Assistant Commissioner
WILLIAM FELDMAN, Deputy Assistant Commissioner
CONDITION OF PATENT APPLICATIONS AS OF September 5, 1981

PATENT EXAMINING GROUPS	Actual Filing Date of Oldest New Case Awaiting Action
CHEMICAL EXAMINING GROUPS	
GENERAL CHEMISTRY AND PETROLEUM CHEMISTRY, GROUP 110—D. E. TALBERT, Director Inorganic Compounds; Inorganic Compositions; Organo-Metal and Organo-Metalloid Chemistry; Metallurgy; Metallurgical Apparatus; Metal Stock; Electro Chemistry; Batteries; Hydrocarbons; Mineral Oil Technology; Lubricating Compositions; Gaseous Compositions; Fuel and Igniting Devices.	5-12-80
GENERAL ORGANIC CHEMISTRY, GROUP 120—C. E. VAN HORN, Director Heterocyclic Amides; Alkaloids; Azo; Sulfur; Misc. Esters; Carbohydrates; Herbicides; Poisons; Medicines; Cosmetics; Steroids; Oxo and Oxy; Quinones; Acids; Carboxylic Acid Esters; Acid Anhydrides; Acid Halides.	10-11-79
HIGH POLYMER CHEMISTRY, PLASTICS AND MOLDING, GROUP 140—J. O. THOMAS, JR., Director Synthetic Resins; Rubber; Proteins; Macromolecular Carbohydrates; Mixed Synthetic Resin Compositions; Synthetic Resins With Natural Polymers and Resins; Reclaiming; Pore-Forming; Compositions (Part) e.g., Coating; Molding; Ink; Prosthetics; Adhesive and Abrading Compositions; Molding, Shaping, Treating Process, and Apparatus Therefor; Irradiation (Part); Bleaching; Dyeing; Leather, Fur and Textile Treating Compositions.	7-09-80
COATING, LAMINATING AND PHOTOGRAPHY, GROUP 160—S. N. ZAHARNA, Director Coating; Processes, Apparatus and Misc. Products; Laminating Methods and Apparatus; Stock Materials; Adhesive Bonding; Special Chemical Manufactures; Special Utility Compositions; and Photography.	1-12-80
SPECIALIZED CHEMICAL INDUSTRIES AND CHEMICAL ENGINEERING, GROUP 170— R. F. WHITE, Director Fertilizers; Foods; Fermentation; Analytical Chemistry; Reactors; Sugar and Starch; Paper Making; Glass Manufacture; Gas; Heating and Illuminating; Cleaning Processes; Liquid Purification; Distillation; Preserving; Liquid, Gas, and Solid Separation; Gas and Liquid Contact Apparatus; Refrigeration; Concentrative Evaporators; Mineral Oils Apparatus; Misc. Physical Processes.	5-06-80
ELECTRICAL EXAMINING GROUPS	
INDUSTRIAL ELECTRONICS, PHYSICS AND RELATED ELEMENTS, GROUP 210—S. W. ENGLE, Director Generation and Utilization; General Applications; Conversion and Distribution; Heating and Related Art Conductors; Switches; Photography; Motion Pictures; Horology; Acoustics; Recorders; Weighing Scales.	1-07-80
SPECIAL LAWS ADMINISTRATION, GROUP 220—KENNETH L. CAGE, Director Ordnance, Firearms and Ammunition; Lubrication; Illumination; Nuclear Reactors; Acoustics, Communications, Optics; Radar; Directional Radio; Torpedoes; Seismic Exploring; Cathode Ray Tube Circuitry; Cryptography; Laser Devices; Radioactive Materials; Powder Metallurgy; Rocket Fuels; Special, Fuel, Explosive and Thermic Compositions; Thermal and Photoelectric Batteries.	1-18-80
INFORMATION TRANSMISSION, STORAGE, AND RETRIEVAL, GROUP 230—VACANT Communications; Multiplexing Techniques; Television; Facsimile; Data Processing, Computation and Conversion; Storage Devices and Related Arts.	1-23-80
RECEPTACLES, SANITATION AND CLEANING, WINDING, AND MEASURING, GROUP 240— A. L. SMITH, Director Receptacles; Bearings; Joint Packing; Conduits; Switches; Presses; Plumbing Fixtures; Textile Spinning; Cleaning; Food Treating; Agitating; Centrifugal Separating; Geometrical Instruments; Sound Recording; Image Projectors; Web Feeding; Winding and Reeling; Cable Hoists; Measuring and Testing; Indicating; Fluent Material Handling.	12-07-79
ELECTRONIC COMPONENT SYSTEMS AND DEVICES, GROUP 250—S. S. MATTHEWS, Director Semi-Conductor and Space Discharge Systems and Devices; Electronic Component Circuits; Wave Transmission Lines and Networks; Optics; Radiant Energy; Measuring.	4-20-79
DESIGN, GROUP 290—KENNETH L. CAGE, Director Industrial Arts; Household, Personal and Fine Arts.	2-08-80
MECHANICAL EXAMINING GROUPS	
HANDLING AND TRANSPORTING MEDIA, GROUP 310—B. R. GRAY, Director Conveyors; Hoists; Elevators; Article Handling Implements; Store Service; Sheet Feeding; Dispensing; Fluid Sprinkling; Fire Extinguishers; Coin Handling; Check Controlled Apparatus; Classifying and Assorting Solids; Boats; Ships; Aeronautics; Motor and Land Vehicles and Appurtenances; Brakes; Railways and Railway Equipment.	1-09-80
MATERIAL SHAPING, ARTICLE MANUFACTURING, TOOLS, GROUP 320—M. M. NEWMAN, Director Manufacturing Processes, Assembling, Combined Machines, Special Article Making; Metal Deforming; Sheet Metal and Wire Working; Metal Fusion-Bonding; Metal Founding; Machine Tools for Shaping or Dividing; Work and Tool Holders, Woodworking; Tools; Cutlery; Jacks; Fishing, Etc.; Butchering; and Books and Printed Matter.	6-12-79
AMUSEMENT, HUSBANDRY, PERSONAL TREATMENT, INFORMATION, GROUP 330— R. E. AEGERTER, Director Amusement and Exercising Devices; Projectors; Animal and Plant Husbandry; Plants; Harvesting; Earth Working and Excavating; Tobacco; Artificial Body Members; Dentistry; Jewelry; Surgery; Toiletry; Printing; Typewriters; Information Dissemination.	1-30-80
HEAT, POWER, AND FLUID ENGINEERING, GROUP 340—D. J. STOCKING, Director Power Plants; Combustion Engines; Fluid Motors; Reaction Motors; Pumps; Rotary Engines and Pumps; Heat Generation and Exchange; Refrigeration; Ventilation; Drying; Temperature and Humidity Regulation; Couplings; Gearing; Fluid Handling and Control; Lubrication.	10-22-79
GENERAL CONSTRUCTIONS, TEXTILES, MINING AND GEARING, GROUP 350— G. M. FORLENZA, Director Building Structures; Racks; Cabinets; Closures; Supports; Furniture; Fasteners; Locks; Pipe Couplings; Joints; Miscellaneous Hardware; Textiles; Sewing Machines; Apparel; Footwear; Earth Engineering; Earth Drilling; Mining; Wells; Roads; Bridges; Tool Driving; Gearing; Machine Elements; Clutches.	2-19-80

Expiration of patents: The patents within the range of numbers indicated below expire during September 1981, except those which may have expired earlier due to shortened terms under the provisions of Public Law 690, 79th Congress, approved August 8, 1946 (60 Stat. 940) and Public Law 619, 83rd Congress, approved August 23, 1954 (68 Stat. 764), or which may have had their terms curtailed by disclaimer under the provisions of 35 U.S.C. 253. Other patents, issued after the dates of the range of numbers indicated below, may have expired before the full term of 17 years for the same reasons, or have lapsed under the provisions of 35 U.S.C. 151.

Patents Numbers 3,146,459 to 3,151,328, inclusive
Plant Patents Numbers 2,444 to 2,448, inclusive

REISSUES

OCTOBER 27, 1981

Matter enclosed in heavy brackets [] appears in the original patent but forms no part of this reissue specification; matter printed in italics indicates additions made by reissue.


Re. 30,782
METHOD FOR THE MANUFACTURE OF AN ELECTRET FIBROUS FILTER

Jan van Turnhout, Delft, Netherlands, assignor to Minnesota Mining and Manufacturing Company, Saint Paul, Minn.
Original No. 3,998,916, dated Dec. 21, 1976, Ser. No. 561,872, Mar. 25, 1975. Application for reissue Jul. 31, 1978, Ser. No. 929,680
Claims priority, application Netherlands, Mar. 25, 1974, 7403975

Int. Cl.³ B29D 27/00

U.S. Cl. 264—22

48 Claims



1. A method for the manufacture of an electrically charged fibrous filter from a high molecular non-polar material, comprising the steps of:

continuously feeding a film of high molecular isotactic polypropylene material at a rate of 12.2 meters per minute; stretching said film in two stages, said first stage of stretching stretches said film at a ratio of 1:6 at a temperature of approximately 110° C., said second stage of stretching stretches said film at a ratio of 1:1.5 at a temperature of substantially 130° C.; homopolarly charging at least one side of the stretched film with a plurality of corona charging elements, said plurality of corona discharge elements being connected to minus 10 KV, said step of charging including the use of a metal plate connected to an opposite polarity voltage source and a grid whereby said charging corona elements are between said metal plate and said film, said metal plate being connected to a voltage of plus 3 KV, said grid being connected to a voltage of minus 2.3 KV, said corona charging elements being spaced substantially 5 mm from the means for supporting said film during said second stage of stretching; fibrillating the charged film into fiber material; and collecting the fiber material [] and processing the collected fiber material into a filter [] to form a filter.

10. A method for the manufacture of an electrically charged fibrous filter from a highly molecular non-polar material, comprising the steps of:

continuously feeding a film of said material; heating said film stretching said film along the longitudinal axis thereof as defined by the path of movement of said film; homopolarly electrically charging at least one side of said film; fibrillating the charged film into fiber material; and collecting the fiber material to form a filter.

Re. 30,783
FLAME RETARDING LINEAR POLYESTERS AND SHAPED ARTICLES THEREOF

Hans-Jerg Kleiner, Kronberg; Manfred Finke, Fischbach; Ulrich Bollert, Diedenbergen, and Walter Herwig, Neuenhain, all of Fed. Rep. of Germany, assignors to Hoechst Aktiengesellschaft, Frankfurt am Main, Fed. Rep. of Germany
Original No. 3,941,752, dated Mar. 2, 1976, Ser. No. 505,686, Sep. 13, 1974. Continuation of Ser. No. 880,866, Feb. 23, 1978, abandoned. Application for reissue Feb. 11, 1980, Ser. No. 120,465


Claims priority, application Fed. Rep. of Germany, Sep. 17, 1973, 2346787

Int. Cl.³ C08G 63/76

U.S. Cl. 528—287

13 Claims

1. A linear polyester which is the polycondensation product of a dicarboxylic acid, a diol and a flame-retarding carboxyphosphinic acid monomer, said monomer being used in an amount of from 3 to 20 mol percent, based on the total amount of dicarboxylic acid and monomer, said monomer being a source of structural units in said polyester of the formula



wherein R is saturated, open-chain or cyclic alkylene, arylene or aralkylene having one to 15 carbon atoms, and may contain one or more hetero atoms selected from F, Cl, Br, O and S, and R₁ is alkyl having up to six carbon atoms, aryl, or alkaryl and may contain one or more hetero atoms selected from F, Cl, Br, O and S, provided that in the R and R₁ groups the O, if present, is the oxygen of an ether group, and the S, if present, is the sulfur of a thioether, sulfoxide, sulfone or sulfonate group.

Re. 30,784
GROUP OPERATED CIRCUIT DISCONNECT APPARATUS FOR OVERHEAD ELECTRIC POWER LINES

Ronald P. Bridges, 9 S. 681 Brookeridge Rd., Downers Grove, Ill. 60515
Original No. 4,095,061, dated Jun. 13, 1978, Ser. No. 783,940, Apr. 1, 1977. Application for reissue Aug. 20, 1979, Ser. No. 68,474

Int. Cl.³ H01H 31/00


U.S. Cl. 200—48 KB

16 Claims

15. A group operated electric circuit disconnect apparatus for a plurality of overhead electric power distribution lines carried on poles, said apparatus comprising, in combination:

a base adapted to be mounted adjacent the top of a pole; a first disconnect switch surmounting the base; second and third disconnect switches mounted at opposite sides of the base; an upright shaft means journaled on said base, said upright shaft means being operatively connected to said first switch so that axial rotation of the shaft means opens and closes the first switch; transverse shaft means journaled on said base and operatively connected to said second and third switches so that axial rotation of said transverse shaft means opens and closes said second and third switches; means on one of said shaft means to which a rotational force may be applied to rotate said one of said shaft means axially;

and a mechanical connection between said upright shaft means and said transverse shaft means so that axial rotation of said



one of said shaft means causes axial rotation of the other of said shaft means.

Re. 30,785

MICROCOMPUTER TERMINAL SYSTEM

Lawrence R. Lovercheck, Palo Alto; Russell K. Hileman, and Richard W. Calfee, both of San Jose, all of Calif., assignors to Zentec Corporation, Santa Clara, Calif.

Original No. 3,973,244, dated Aug. 3, 1976, Ser. No. 553,654, Feb. 27, 1975. Application for reissue May 18, 1979, Ser. No. 40,140

Int. Cl.³ G06F 3/00, 3/153


U.S. Cl. 364—200

31 Claims

1. An information terminal system comprising:

- a memory storing character data;
- data means for entering character data into said memory;

- a first set of shift registers receiving character data from said memory for storage therein;
- a second set of shift registers receiving character data from said first set of shift registers for storage therein;
- video circuit means receiving successive rows of character data from said second set of shift registers for producing video signals; [and]
- means including a character display receiving said video signals from said video circuit means for displaying [a character element] successive rows of characters corresponding to said successive rows of character data; and



- timing and control means for controlling transfer of character data from said first set of shift registers to said second set of shift registers so that a row of character data transferred to said second set of shift registers causes said video circuit means to produce video signals that produce a display of a row of characters in said character display while the succeeding row of character data is received and stored in said first set of shift registers ready to be transferred to said second set of shift registers to produce video signals in said video circuit means for the succeeding row of characters displayed in said character display.

PLANT PATENTS

GRANTED OCTOBER 27, 1981

Illustrations for plant patents are usually in color and therefore it is not practicable to reproduce the drawing.

4,781

BEGONIA PLANT

James C. Mikkelsen, and Cornelis P. Van den Berg, both of Ashtabula, Ohio, assignors to Mikkelsens Inc., Ashtabula, Ohio

Filed Mar. 25, 1980, Ser. No. 133,900

Int. Cl.³ A01H 5/00

U.S. Cl. Plt.—68

1 Claim

1. A new and distinct cultivar of begonia plant referred to by the cultivar name Fresco, as described and illustrated, and particularly characterized by its large semi-double to double, deep orange-red flowers; heavy infusion of red pigmentation in the foliage; pleasant contrast of flower and foliage color; year round flowering with proper environmental conditions, and by its vigorous growth habit.

4,782

AFRICAN VIOLET PLANT

Reinhold Holtkamp, Werther Strasse 112, D-4294 Isselburg, Fed. Rep. of Germany

Filed Jul. 1, 1980, Ser. No. 165,076

Int. Cl.³ A01H 5/00

U.S. Cl. Plt.—69

1 Claim

1. A new and distinctive cultivar of African Violet plant

4,783

CARNATION PLANT

Jack M. Meek, Salinas, Calif., assignor to Yoder Brothers, Inc., Barberton, Ohio

Filed Aug. 5, 1980, Ser. No. 175,421

Int. Cl.³ A01H 5/00

U.S. Cl. Plt.—72

1 Claim

1. A new and distinct cultivar of carnation known by the cultivar name Duchess, as described and illustrated, and particularly characterized as to uniqueness by the combined characteristics of commercial double flower type; flat flower form, twisting slightly with maturity; medium flower size, dark salmon pink flower color with minimum color oxidation; medium flowering response; 4 to 7 flowers and buds showing color per flowering stem; medium peduncle length; strong peduncle strength; and tall plant height.

PATENTS

GRANTED OCT. 27, 1981

ERRATA

For	See
CLASS	PATENT NO.
474-262	4,296,640
294-144	4,296,880
501-002	4,297,139
428-310	4,297,140
501-067	4,297,141
501-077	4,297,142
501-103	4,297,143
376-103	4,297,165
376-194	4,297,166
376-273	4,297,167
376-418	4,297,168
376-418	4,297,169
376-442	4,297,170
376-440	4,297,171
136-256	4,297,391
028-042	4,297,403
030-215	4,297,432

PATENTS

GRANTED OCTOBER 27, 1981

GENERAL AND MECHANICAL

4,296,497

HOSPITAL PATIENT GOWN


Seymour S. Herman, New York, N.Y., assignor to Stan Herman Studio, Inc., New York, N.Y.

Filed May 16, 1980, Ser. No. 150,324

Int. Cl.³ A41B 9/00

U.S. Cl. 2—114

5 Claims



1. A hospital patient gown comprising a front panel, a first and a second rear panel, longitudinal side margins on each of the said panels, means to secure the front panel and side panels together to form a gown having an elongated vertical rear opening therein, a neck band on said panels, a free portion on the first and the second rear panel, an inverted pleat on one of said free portions said pleated portion extending across the rear opening and underlying the other free portion and means carried by the neck band and pleated portion to secure the rear panels together.

4,296,498

REVERSIBLE GARMENT

Joseph J. Vinson, 2009 Blossom La., Marshalltown, Iowa 50159

Filed Jun. 2, 1980, Ser. No. 155,417

Int. Cl.³ A41B 1/00

U.S. Cl. 2—115

3 Claims



1. A reversible garment such as a jersey or the like for the upper part of the body, comprising:
 (a) a front and back panel joined together at seams having sleeves and a neck opening that form a pullover upper-body garment,
 (b) said front panel having an identifying characteristic different from the back panel,
 (c) said front and back panels being of substantially the same size and shape,
 (d) a reversible flap having cutouts for said sleeves and conforming in size and shape to said front and said back panel and having side and bottom edges.
 (e) said flap being permanently affixed to said garment so as

to be selectively movable from a position over either the entire front panel or the entire back panel to cover the identifying characteristics of one of said panels when moved into a panel covering position,
 (f) said flap having different identifying characteristics on its opposite sides which characteristics correspond to those contained on the front and back panels so that the same identifying characteristics will be displayed on the front and the back of the garment simultaneously regardless of the selected position of the flap, and
 (g) a first and a second fastening means for securing the side edges of the flap in one of said selected positions over at least one of said panels.

4,296,499

BLISTER PREVENTING FOOT COVER


Theodore P. Patterson, 5207 Twilight La., Fort Wayne, Ind. 46815, and Stephen E. Winner, Fort Wayne, Ind., assignors to Theodore P. Patterson, Fort Wayne, Ind.

Filed May 29, 1979, Ser. No. 43,459

Int. Cl.³ A41B 11/00

U.S. Cl. 2—239

5 Claims



1. A method for the prevention of blisters on the feet comprising:
 providing a foot cover made of one or more porous, non-woven film-fibril sheets of plexifilamentary strands, said strands having about 200 to 800 point bonds per square inch comprising about 5 to 10 percent of the planar area of the sheet or sheets, and a plurality of minute perforations extending through the thickness of the sheet or sheets with the total cross-sectional area of the perforations being at least 3 percent of the planar area of the sheet or sheets, said sheet or sheets being formed into a foot enveloping shape comprising a bottom portion adapted to lie underneath the sole of the foot, side portions extending upwardly from the bottom portion and adapted to cover the sides of the foot, a heel portion adapted to cover the heel of the foot, and a front portion adapted to cover at least the forward portion of the top of the foot, said cover having a relatively smooth inner surface and a relatively rough outer surface; and placing and wearing the foot cover on the foot directly in contact with the foot and directly underneath an overlying sock such that the smooth inner surface contacts the foot and clings to it and prevents the formation of blisters and the relatively rough outer surface engages the sock and provides some stability with the overlying sock.

4,296,500

ARTIFICIAL HEART


Jean R. Monties, Auriol, and Patrick J. C. Havlik, Marseilles, both of France, assignors to Agence Nationale de valorisation de la Recherche (ANVAR), France

Filed May 3, 1978, Ser. No. 902,364

Claims priority, application France, May 6, 1977, 77 14470
Int. Cl.³ A61F 1/24; A61M 1/03

U.S. Cl. 3—1.7

10 Claims



1. An artificial heart comprising a cylindrical rotor and a body which defines a cylindrical cavity, the cross-sections of said rotor and said cavity being respectively a trochoid and the envelope of said trochoid when the rotor is driven both in circular translation and in rotation about its centre, means for driving the rotor in rotation at a uniform speed, the number of revolutions per minute of which is the same as the normal pulse rate of the patient, whereby the body has at least one fixed narrow region parallel to the generating lines within which the rotor is permanently in substantially tight contact with the inner wall of the cavity, said body having two elongated openings located on either side of the fixed region which are adapted to be connected respectively to the venous system and to an artery leading to the heart of the patient.

4,296,501

INTRAOCULAR LENS AND METHOD OF MAKING THE SAME


Charles D. Kelman, 269 Grand Central Pkwy., Floral Park, N.Y. 11005

Filed Jul. 14, 1980, Ser. No. 168,544

Int. Cl.³ A61F 1/16, 1/24

U.S. Cl. 3—13

14 Claims



1. An intraocular lens suitable for use as an artificial lens implant anteriorly of the iris, the lens comprising: a medial, light-focusing lens body; and at least a pair of lateral position fixation elements connected with said lens body; at least one of said pair of position fixation elements having a first portion contiguous to and extending generally laterally outwardly from a first region of the periphery of said lens body, and the other of said pair of position fixation elements having a first portion contiguous to and extending generally laterally outwardly from a second region of the periphery of said lens

body spaced from and generally opposite said first region and in a direction generally opposite to that of said first portion of said one position fixation element; said other of said pair of position fixation elements having a second portion pivotable about the end of said first portion of said other of said pair of position fixation elements before being attached to said first portion of said other of said pair of position fixation elements at a selected position before implantation in the eye.

4,296,502

SELF-PACKAGING URINE CONDUIT



Bonnie Bortle, 62 Newtonville Ave., Newton, Mass. 02158

Filed Mar. 17, 1980, Ser. No. 130,738

Int. Cl.³ A61G 9/00; E03D 13/00; A47K 11/12

U.S. Cl. 4—144.1

6 Claims



1. A self packaging urine conduit for women, comprising a flexible and reversibly deformable fluid-tight tubular medial element, having a first portion of generally uniform inner dimension, and a second generally funnel-shaped portion continuous therewith and having an inner dimension increasing from that of said first portion to a rim dimension at its free edge, a relatively rigid tubular end piece having an inner dimension approximately equal to that of said medial element first portion, said medial element first portion being connected to said tubular end piece to define at least one connecting area, said medial element first portion and said tubular end piece together forming a continuous fluid-tight channel, a rim integrally connected to said medial element funnel-shaped portion at said free edge, said rim having an undeformed dimension greater than the inner dimension of said tubular end piece and being resiliently deformable to fit within said tubular end piece, and a relatively rigid handle element integrally and rigidly connected to said rim and generally coplanar with said rim, said medial element first portion having a length at least as great as the length of said tubular end piece, said medial element first portion being reversibly inverted for storage of said rim, said handle and said funnel shaped portion within said tubular end piece.

4,296,503

IN-TANK BATHROOM DEODORIZER/CLEANER

Anthony Leardi, Middletown, N.Y., assignor to Hercules Incorporated, Wilmington, Del.

Filed Feb. 20, 1980, Ser. No. 122,970




Int. Cl.³ E03D 9/02

U.S. Cl. 4—228

1 Claim

1. An in-tank toilet bowl cleansing and fragranting device comprising a floatable container adapted to float on the surface of the water in a toilet bowl hold tank and to enclose a solid detergent material while leaving one of the surfaces of said solid detergent material exposed, means for securing said container in a toilet bowl hold tank with the exposed surface of the solid detergent out of contact with the body of water in the

tank, and means for causing said container to rotate between a substantially horizontal and a substantially vertical position as



the water level in the tank falls due to flushing and thereafter to return to the horizontal position as the water level recovers.

4,296,504

TOILET SEAT LOCK

Daniel C. Lawson, 6611 W. 174th St., Tinley Park, Ill. 60477

Filed Jul. 7, 1980, Ser. No. 166,160

Int. Cl.³ A47K 13/00

U.S. Cl. 4—253

10 Claims



1. A device for use with a toilet and toilet seat cover comprising: a lever adapted to fit through a hole in said toilet seat cover so as to allow rotation of said lever when said toilet seat cover is in a horizontal position; a latch connected to said lever so that said latch will rotate in direct relationship to said lever and pivotally connected to said lever so that when said toilet seat cover is in a vertical position, said latch will lay substantially against said toilet seat cover and when said toilet seat cover is in a horizontal position, said latch will hang away from said toilet seat cover; and, a retainer which is adapted to be affixed to said toilet and positioned so that when said toilet seat cover is in a horizontal position, rotation of said lever will allow rotation of said latch into or out from said retainer.

4,296,505

STEPLESS CONTROLLED FLUSH CLOSET


Chiang Chien-Sheng, 6, Alley 15, La. 174, Ta Tung St., Peitu District, Taipei, Taiwan

Filed Jan. 16, 1980, Ser. No. 112,467

Int. Cl.³ E03D 1/14, 3/12

U.S. Cl. 4—324

4 Claims



1. A stepless controlled water tank for a flush toilet comprising a tank having at its bottom an outlet opening, a pivoted closure for said outlet opening, a pivoted control lever for releasably holding said closure in open position, a low level float connected with said control lever and acting by its flotation to position said control lever to hold said closure in open position when the water level is above a predetermined low level, an operating lever shaft rotatably mounted in said tank above normal high water level and extending to the outside of said tank, an operating handle outside said tank fixed to said shaft, an arm on said shaft inside said tank, linkage connecting said arm with said closure to open said closure by operation of said handle, whereupon said closure is held open by said control lever, a high level float on an arm pivotably mounted in said tank at approximately high water level, a slider slidable longitudinally on said float arm, lost-motion means connecting said slider with said control lever, volume discharge control means including a setting member on the outside of said tank, and means connecting said discharge control member with said slider to move said slides to different positions along said float arm, whereby said high water float, as it descends during discharge of water from said tank, acts through said slides and said means connecting said slides with said control means to release said closure to close said outlet at a time depending on the position of said slides on said float arm.

4,296,506

INVALID CHAIR

Neville Stoute, Sr., New York, N.Y., and Robert J. Pennise, Colmar, Pa., assignors to James A. Falborn and Richard M. Bird, both of New York, N.Y., part interest to each

Continuation-in-part of Ser. No. 99,187, Nov. 30, 1979, abandoned. This application Feb. 29, 1980, Ser. No. 126,147

Int. Cl.³ A47K 11/06; A61G 7/02; A47K 11/04


U.S. Cl. 4—480

14 Claims

1. A replacement for a collapsible invalid wheelchair which comprises a left side frame member, a right side frame member and means effective between the frame members to hold them apart, said seat comprising:

a flexible padded seat member having a left side edge and right side edge for attachment to the left side frame member and the right side frame member respectively of an existing collapsible wheelchair, said seat member being formed with an elongated, generally rectangular opening extending substantially parallel to the left and right side edges of the seat member, reinforcing means located within the seat member and at the

underside of the seat member respectively on each side of said opening;
means defining tracks on the underside of the seat member and extending substantially parallel to the left and right side edges of the seat member on each side of the opening; a removable receptacle adapted to fit slidably in said tracks and extend over the full length of said opening; and a detachable flexible padded flap removably attached to the seat member at the underside thereof for closing said



opening after the receptacle has been removed, the arrangement being such that the removal and attachment of the flap, and the insertion and removal of the receptacle can all be accomplished from the underside of the seat member, and such that upon removal of the receptacle the seat member can be folded about a line extending substantially parallel to the left and right side edges of the seat member without interference from the reinforcing means or the track defining means.

4,296,507

SAUNA HEATING UNIT AND SHIELD THEREFOR

Mats O. Janson, Port, Switzerland, assignor to Tylo Sauna S.A., Biel-Bienne, Switzerland


Filed Oct. 29, 1979, Ser. No. 89,135

Claims priority, application Sweden, Nov. 8, 1978, 7811514

Int. Cl.³ A61H 33/06


U.S. Cl. 4—524

6 Claims



1. A sauna heating unit having a shield for guiding the stream of hot air from said unit into the sauna room comprising a substantially planar sheet member of heat resistant material detachably supported on the sauna heating unit in spaced relationship directly above it, upright members attached to said sheet member and said sauna unit to support said sheet member, said sheet being arranged at an angle to the horizontal plane for directing the stream of hot air from the sauna heating unit obliquely upwards into the sauna room, said sheet member having a shape and dimensions so that it covers an area corresponding to at least a substantial portion of the upper open end of the sauna heating unit.

4,296,508
BATHTUB FOR INVALIDS
Malachy J. Moran, 13915 Saratoga Rd., Saratoga, Calif. 94070
Filed Mar. 31, 1980, Ser. No. 135,393
Int. Cl.³ A47K 3/022; A61H 33/02; A47K 3/12
U.S. Cl. 4—540 10 Claims



1. A bathtub which can be entered without stepping over a sidewall and which provides for increased leg room during entry, the bathtub comprising:

a fixed part having a bottom closure, sidewalls extending upwardly on three sides from the bottom closure and having one open side, wherein the faces of the bottom closure and the two sidewalls along the open side form a portion of a concave cylindrical surface having a first radius about a first vertical axis;

an end part rotatable on a second vertical axis located on the bathtub centerline and having bottom closure, a back wall and two parallel sidewalls extending upwardly on three sides from the bottom closure, and having one open side, wherein the faces of the bottom closure and the two parallel sidewalls along the open side form portion of a convex cylindrical surface having a second radius about the first vertical axis; and

said end part being rotatably operable from a first position wherein the open side thereof faces away from the fixed part and provides an entrance to and exit the end part and a second position wherein the cylindrical faces of the rotatable end part and fixed part abut for providing a seal therebetween.

4,296,509

PORTABLE INVALID LIFT


Dwane P. Simmons, 7465 Olive Tree La., Highland, Calif. 92346, and Ray E. Lynn, 5172 Acacia St., San Bernardino, Calif. 92407

Filed Oct. 23, 1979, Ser. No. 87,343

Int. Cl.³ A61G 7/08

U.S. Cl. 5—81 R

1 Claim



1. A portable apparatus for transferring an invalid from a

wheel chair to a bed or chair, and vice versa, said apparatus comprising:

an elongated track extending transversely over said bed or chair with one end projecting laterally from one side thereof with aligned holes at both ends of said track's vertical sidewalls;

first support means a tripod with telescoping legs, connected one to another on the upper portion thereof by a safety chain, said tripod set under the outermost portion of said laterally projecting section of said track, said tripod having a short section of channel open at the top mounted horizontally on the apex thereof in which the outer end of the laterally projecting end of said track section rests, said channel having aligned holes in its vertical sidewalls to line up with said aligned holes in said outermost portion of laterally projecting section of track to receive a locking pin, each said tripod leg being in two or more nearly equal sections with the lower sections being of a smaller size than the immediate section above and telescoping therein with each lower section on its upper end having a spring activated inset hard material ball on the outer surface thereof projected laterally when pulled clear by said spring sufficiently to prevent said immediate upper leg section from sliding downward thereon when said leg sections are extended, said ball also preventing said sections from extending downward accidentally when telescoped together by being projected laterally by said spring against the inner wall of said immediate upper leg section with sufficient pressure to cause enough friction to resist the force of gravity;

second support means a tripod identical to said first support means with an identical horizontal channel mounted at the apex thereof in which the outermost portion of the non-laterally projecting section of said track rests identically to said first support means and is secured identically to said first support means by an identical locking pin inserted through identical aligned holes in said channel's vertical sidewalls and aligned holes in the vertical sidewalls of said outermost portion of said non-laterally projecting section of track;

a wheeled carriage movable along the laterally projecting section of said track;

a winch with a rope depending therefrom mounted on said movable wheeled carriage;

a sling in which an invalid person sits; and means on said rope attachable to said sling, said winch being operable to raise said invalid from said wheel chair or chair and to lower said person into said bed or chair or vice versa, said wheeled carriage being movable with said invalid between a first position on the laterally projecting portion of said track directly over said wheel chair, and a second position over said bed or chair.

4,296,510

ANTI-SURGE FLOTATION MATTRESS

Raymond M. Phillips, 5500 W. 83rd St., Los Angeles, Calif. 90045

Filed Sep. 4, 1979, Ser. No. 72,126


Int. Cl.³ A47C 27/08

U.S. Cl. 5—450

8 Claims

1. A flotation mattress engageable in a frame having a horizontal platform and vertical side and end rails about and projecting upwardly from the platform; said mattress including an outer bladder of flexible, supple, water impervious sheet material with a flat, horizontal platform engaging bottom wall, vertical rail engaging side and end walls and a flat normally horizontal depressable top wall; a volume of fluid medium within and slackly filling the bladder; a normally flat, horizontal intermediate wall of flexible material in spaced relationship between the top and bottom walls and dividing the interior of the bladder into upper and lower portions; a plurality of spaced, vertical partitions of flexible, supple material fixed with and extending between the bottom and intermediate walls and cooperating therewith to define elongate fluid conducting

tunnels with opposite ends in said lower portion of the bladder; flow metering fluid transfer means communicating with and between related ends of the tunnels; flotation means at the intermediate wall normally buoying up and maintaining that wall and the partitions in their normal position within the



bladder and wherein said flow metering transfer means includes fluid conducting chambers at and extending between adjacent ends of adjacent tunnels and membranes of flexible material overlying the ends of the tunnels and having flow metering openings communicating with the tunnels and the chambers.

4,296,511

WATER SKI WITH INCREASED STABILITY


Joe B. Wright, 3728 Gratia Ave., Sacramento, Calif. 95821

Filed Jun. 8, 1978, Ser. No. 913,856

Int. Cl.³ A63C 5/00, 15/06

U.S. Cl. 9—310 A

24 Claims



1. A water ski comprising:

a longitudinally and laterally extending member, said member having a front longitudinal end and a rear longitudinal end;

means for causing said member to lie in the water in the rest position with said front longitudinal end pointing upward and said rear longitudinal end pointing downward, said means comprising:

an aperture disposed in the lower surface of and situated toward said rear longitudinal end of said member;

a channel within said member communicating with said aperture; and

a vane pivotally mounted in said aperture for selectively inhibiting the flow of water through said aperture in a direction into said member.

4,296,512

METHOD FOR MAKING FASTENERS

William A. Kilinskas, Amherst; Ronald J. Selines, Yorktown Heights, and Jaak S. Vand den Sype, Scarsdale, all of N.Y., assignors to Union Carbide Corporation, New York, N.Y.

Filed Nov. 9, 1979, Ser. No. 93,014

Int. Cl.³ B21K 1/48

U.S. Cl. 10—27 E

9 Claims

1. A method for making a fastener having a head and a shank from wire or rod consisting essentially of AISI 200 or 300 series stainless steel comprising the following steps:

- (a) cooling the wire or rod to a temperature of less than about minus 75° C.;
- (b) drawing the cold wire or rod through a die at a strain sufficient to provide a tensile strength for the wire or rod in the range of about 75 ksi to about 160 ksi, the strain and the die size being such that the area of the wire or rod will be reduced by at least about 3 percent; and
- (c) dividing the wire or rod into slugs and cold heading each slug to provide the fastener.

4,296,513

SEAT AND WAIST LASTING MACHINE-INDEPENDENTLY PIVOTABLE SIDE LASTING FINGERS

David W. Halford; Frank C. Price, and George H. Bosworth, all of Leicester, England, assignors to USM Corporation, Farmington, Conn.


Filed Mar. 27, 1980, Ser. No. 134,459

Claims priority, application United Kingdom, Apr. 21, 1979, 13952/79

Int. Cl.³ A43D 21/00

U.S. Cl. 12—12

16 Claims



1. A shoe machine for use in the lasting of side portions of shoe uppers, said machine comprising:

- a support for a shoe last on which an upper, the side portions of which are to be lasted, and an insole are positioned, and a pair of side lasting assemblies arranged so as to act on opposite side portions of an upper placed on a last supported by said support;

each side lasting assembly comprising a plurality of wiping elements arranged side-by-side so as to engage a corresponding side portion of the upper along the length thereof;

said wiping elements being movable inwardly so as to wipe the upper portion engaged thereby over the insole margin and to press it thereagainst, each element also being mounted for limited pivotal movement independently of the element adjacent thereto about a first axis extending transversely of the last bottom, and also about a second axis extending lengthwise of said last bottom, the arrangement being such that the distance between the second axis and the work-engaging surface of the element along a perpendicular to said surface passing through said second axis is generally equal to the distance between the first axis

and a reference plane in which the second axis lies and which extends parallel to said first axis, along a perpendicular to said reference plane passing through said first axis.

4,296,514

METHOD FOR CONTINUOUS PROCESSING OF FLEXIBLE WORKPIECES

Jiri Dokoupil, Hochstrasse 9, 6251 Gückingen, and Kurt Hacker, Birkenwaldstrasse 155, 7000 Stuttgart 1, both of Fed. Rep. of Germany


Division of Ser. No. 904,496, May 10, 1978. This application Mar. 10, 1980, Ser. No. 128,977

Claims priority, application Switzerland, May 17, 1977, 6167/77; Fed. Rep. of Germany, Dec. 27, 1977, 2758349

Int. Cl.³ A43D 9/00

U.S. Cl. 12—142 R

8 Claims



1. A method of continuous processing of laminar flexible workpieces, especially in leather, shoe or clothing production, with pressing, especially hot-press gluing of the workpieces, where the workpieces are carried through at least one pressure zone, characterized in that a continuous path of the workpieces comprises at least one low-pressure zone on the input side for spreading or smoothing the workpieces and at least one succeeding high-pressure zone for pressing the workpieces traversing the path from the input side in a generally upwardly direction toward an outlet side with an outlet motion of the workpieces essentially in the opposite direction to and spatially above the infeed motion of the workpieces.

4,296,515

FASTENING OF SHOE UPPERS FOR LASTING


John Hauser, Calle Chama, Qta. Tony, Colinas de Bello Monte, Caracas 101, Venezuela

Filed Jun. 9, 1980, Ser. No. 157,717

Int. Cl.³ A43D 5/00, 9/00

U.S. Cl. 12—142 LC

6 Claims



1. A process for the temporary fastening of the flaps of a shoe upper prior to lasting of the upper, comprising aligning pairs of opposed eyelets formed in said upper, propelling fastening elements including a pair of substantially parallel legs and a bridging element extending between and connecting said

legs through said aligned eyelets such that one of said legs of each fastening element passes through both aligned eyelets following a path which is generally normal to the planes of said eyelets until it passes through the second of the aligned eyelets and then adopts a disposition generally parallel to said second eyelet, the legs of said fastening elements thereafter preventing separation of said flaps beyond a predetermined distance established by the length of the bridging elements.

4,296,516

VERTICALLY ADJUSTABLE BRIDGE FOR CONNECTION WITH SHIPS

Lennart Järnum, Helsingborg, Sweden, assignor to AB Jarnkonstruktioner, Helsingborg, Sweden


Filed May 30, 1979, Ser. No. 43,836

Claims priority, application Sweden, Sep. 6, 1978, 7809372

Int. Cl.³ E01D 1/00

U.S. Cl. 14—71.7

10 Claims



1. A vertically adjustable bridge for connection with ships comprising a plurality of bridge units, each bridge unit having a ramp including girders and an upper surface suitable as bedding for transport and a land side end rotatably connected to a permanently applied bearing arrangement, the other end of the bridge unit being adjustable to a desired height within a suitable adjustment range and being temporarily lockable in the adjusted position, supporting legs and locking means cooperating with the legs for locking the other end of the bridge unit in the adjusted position, the bridge units being mountable side by side adjacent one another, each bridge unit having straight sides parallel to one another, a raising and lowering arrangement including the supporting legs with fittings located under the ramps of each unit at suitable distances from both ends of the ramp and from its side edges in such a way that a plurality of units, which are individually maneuverable, can be adjusted, when necessary, at the same height close to one another, to effectively widen the bridge.

4,296,517

PORTABLE SPINNERET CLEANER

Joachim Böhrer, Grosswallstadt, and Hans Jordon, Rudenau, both of Fed. Rep. of Germany, assignors to Akzona Incorporated, Asheville, N.C.


Filed Oct. 17, 1979, Ser. No. 85,839

Claims priority, application Fed. Rep. of Germany, Oct. 27, 1978, 7832006[U]

Int. Cl.³ B08B 13/00

U.S. Cl. 15—93 R

3 Claims



1. A portable spinneret cleaning unit, comprising: a base plate; an essentially cylindrical housing mounted on said base

plate, said housing having a plane striker face at its free end; at least two guide bars, and means for mounting said guide bars on said housing whereby said guide bars pivot about and move linearly along their axis; mountings on the free end of said guide bars to receive at least one blade, the cutting edge of said blade being aligned parallel with the free end of said housing; spring means mounted on said housing for yieldably urging said blade slightly above said striker face; and means for rotating at least one guide bar.

4,296,518

TOOTHBRUSH AND GUM MASSAGING ACCESSORY

Joseph P. Furrier, Northvale, and Allan H. Gilbert, Oradell, both of N.J., assignors to Lever Brothers Company, New York, N.Y.

Filed Nov. 30, 1979, Ser. No. 99,343

Int. Cl.³ A61H 13/00

U.S. Cl. 15—110

4 Claims



1. In a toothbrush including a handle and an array of bristles affixed to one end portion of said handle, an improvement comprising a gum massaging accessory movably secured to an opposite end portion of said handle for articulation between a first position in general alignment with said handle to at least a second position askew to said handle, said handle including a recess, said accessory including a resilient member terminating in a free-end portion for gum massaging treatment and an opposite end portion arranged in said recess, and pivot means for movably interconnecting said opposite end portion of said resilient member to said handle in said recess, said pivot means including a generally spherical-like socket, said free-end portion of said resilient member including a generally spherical-like region constrained in said socket for movement between said first and second positions.

4,296,519

BRUSH

Wilhelm E. Schmitt, Bensenville, Ill., assignor to Jack S. Friedman, Highland Park, Ill.


Continuation of Ser. No. 933,641, Aug. 14, 1978, abandoned, which is a continuation-in-part of Ser. No. 782,176, Mar. 28, 1977, abandoned, and Ser. No. 802,793, Jun. 2, 1977, abandoned.

This application Nov. 1, 1979, Ser. No. 90,101

Int. Cl.³ A46B 9/10

U.S. Cl. 15—184

16 Claims



1. A brush having retractable bristles comprising: (a) a casing defining an arcuate panel having a plurality of openings therein, (b) a cradle member positioned in the casing, said cradle carrying a plurality of elongate support members rotatable with respect to the cradle member, (c) a plurality of bristles mounted on the elongate support members, with each of the bristles extending into one of the openings in said panel in a close fitting relationship, and

(d) means to retract the bristles into the casing through the openings, said means including a wing member mounted for sliding movement within the casing, said wing member having cam slots therein, said cradle member being mounted in the casing and having follower means thereon engaging said cam slots whereby advancing the wing member in one direction within the casing operates to retract the bristles into the casing through the openings, thereby causing the elongate support members to rotate relative to the cradle and thereby prevent the bristles from being subjected to excessive deformation while the openings exert a cleaning action on the bristles to clean foreign matter therefrom, and advancing the wing member in the opposite direction within the casing operates to extend the bristles from the casing.

4,296,520

PIN CONNECTOR


John J. Arndt, Chesterton, Ind., assignor to The Anderson Company of Indiana, Gary, Ind.

Filed Oct. 10, 1979, Ser. No. 83,512

Int. Cl.³ B60S 1/40

U.S. Cl. 15—250.32

6 Claims



1. A pin (18) having a cylindrically-shaped body portion (60) for attaching an adaptor (16) to a wiper blade (10), said body portion (60) having an annular recessed midportion (62), a head (70) on one end of said pin (18) extending radially outward from said body portion (60), and a pair of spaced apart tabs (72) lying in the plane of said head (70) and extending parallel to each other in an outward direction from said body portion (60) for retaining said pin (18) on said adaptor (16) prior to use.

4,296,521

WIPER BLADES

Peter Mower, Twickenham, England, assignor to Trico Products Corporation, Buffalo, N.Y.


Filed Feb. 6, 1980, Ser. No. 119,127

Claims priority, application United Kingdom, Feb. 13, 1979, 5036/79; Apr. 4, 1979, 11853/79

Int. Cl.³ B60S 1/40

U.S. Cl. 15—250.32

6 Claims



1. A connecting clip assembly for connecting a wiper arm to a wiper blade, said wiper blade having between its ends an opening with opposite parallel side walls for receiving the connecting clip and the arm for pivotal movement therebetween, and a first pair of aligned holes in said opposite parallel side walls, the connecting clip comprising an elongate unitary body forming a pair of opposite parallel external side faces, a

portion for supporting an end portion of a wiper arm longitudinally of the connecting clip including means for retaining the end portion of the wiper arm, a transverse opening through said body at right angles to the side faces terminating in a second pair of aligned holes through the side faces, and a separable pin of a length greater than the distance between the side faces extending through said first and second pairs of aligned holes and said transverse opening in assembled position, interlocking, cooperating abutment means on said body and said pin for retaining said pin in assembled position, the end portions of said pin pivotally engaging said first pair of aligned holes.

4,296,522

REVERSIBLE DUAL WINDSHIELD WIPER


Frederick Brack, 67 Pine St., Massapequa, N.Y. 11758

Filed Jun. 20, 1979, Ser. No. 50,474

Int. Cl.³ B60S 1/38

U.S. Cl. 15—250.36

4 Claims



1. A reversible dual blade windshield wiper assembly comprising:

a blade holder formed of an elongated piece of material having upper and lower faces and substantially flat edge portions,

a flexible blade of elastomeric material extending from each of the faces of said blade holder, each of said blades having a base which is mounted to said blade holder and from which said blades extend; said blade holder spanning the entire base of each said blade and leaving a said edge portion thereof exposed on each side of each blade, each blade being of the same general shape,

an arm,

and a plurality of retaining clips mounted to said arm, each said retaining clip having a pair of legs which can be spread apart, a slot on the inner face of each of the legs of a said retaining clip in which the edge portions of the blade holder are placed.

4,296,523

DUST-COLLECTION HEAD FOR A DUST COLLECTION SYSTEM

William J. Clark, Richmond, Calif., assignor to Chevron Research Company, San Francisco, Calif.

Filed Mar. 31, 1980, Ser. No. 135,834

Int. Cl.³ A47L 9/02

U.S. Cl. 15—415 R


20 Claims

16. A vacuum-operated dust-collection system for removing dust particles from dust-laden air produced when dumping dust-producing materials into a container, comprising: a dust-collection head including

(i) a housing having a chamber formed therein, said housing having an outer section, a central section and an inner section juxtaposed sequentially along one dimension of said housing,

(ii) a curved substantially C-shaped face formed in said outer section, said face have a plurality of parallel slots formed therein to extend generally along the length of said face,

the maximum distance across said face being approximately equal to that across the top of the container, and (iii) a plurality of flow directors disposed within said chamber to extend inwardly from said face to a location spaced from but proximate to said central section to form a plurality of flow passages in said chamber so that a substantially even dust-capture velocity is provided along said face;



one end of a conduit means connected to said inner section for evacuating the dust particles from said chamber; and means connected to the opposite end of said conduit means for creating a vacuum at said face and for removing the dust particles from the air drawn from said chamber.

4,296,524

JOINING MEMBER

Anders Hörholt, 9 Avenue d'Ostende, Monte Carlo, Monaco, and Ulrik Kvist, Virvelvägen 42, 184 00 Åkersberga, Sweden


Filed Mar. 20, 1978, Ser. No. 888,399

Claims priority, application Sweden, Mar. 23, 1977, 7703319

Int. Cl.³ E05D 7/00

U.S. Cl. 16—150

1 Claim



1. A joining member for joining structure elements having plane connecting portions comprising at least two profiles the cross-section of each of which is substantially U-shaped for receiving said plane connecting portions between the legs of said U-shaped profiles, said U-shaped profiles including a V-shaped bottom from the arms of which said legs extend, a thin web made in one and the same piece as said U-shaped profiles extending between the tips of each of said V-shaped bottoms articulatingly connecting said profiles, and said arms of said V-shaped bottom extending at a pre-determined angle from each of said tips, the degree to which adjacent of said U-shaped profiles are foldable about said web relative to each other being dependent upon the degree of said angle.

4,296,525

SWIVEL FITTING FOR FITTING PARTS OF A SAFETY BELT

Johann Schmid, Schwäbisch-Gmünd, Fed. Rep. of Germany, assignor to REPA Feinstanzwerk GmbH, Alfdorf, Fed. Rep. of Germany

Filed Feb. 14, 1980, Ser. No. 121,473

Claims priority, application Fed. Rep. of Germany, Feb. 15, 1979, 2905863


Int. Cl.³ E05D 1/06

U.S. Cl. 16—174

6 Claims

1. Swivel fitting for fitting parts of a safety belt which are connectible together in a swivel relationship, comprising a first

fitting part having a fitting portion and a cylindrically-shaped bearing eye integral therewith, said bearing eye having a cut-out formed therein with converging edges about said cylindrically-shaped bearing eye forming a wide part thereof disposed adjacent to said fitting portion and a narrow part thereof forming a centering slot centrally disposed in said cylindrical bearing eye, a plastic cylinder pin having a slot formed therein and being inserted in said bearing eye, a second fitting part having



a substantially T-shaped extension integral therewith with a center leg and two side legs, said T-shaped extension being radially insertable into said slot formed in said plastic cylinder pin through the wide part of said cutout formed in said bearing eye and said center leg thereof being swingable into the narrow part of said cutout formed in said bearing eye and lockable therein in the axial direction of said bearing eye in an operating position.

4,296,526

SKINNING MACHINE FOR THE HEADS AND LIMBS OF SLAUGHTERED ANIMALS

Claude Tournier, Lioujas, 12000 Rodez, France


Filed Dec. 4, 1979, Ser. No. 100,227

Claims priority, application France, Dec. 4, 1978, 78 34719

Int. Cl.³ A22B 5/16

U.S. Cl. 17—21

3 Claims



1. Skinning machine, especially for the external processing of a part of a slaughtered animal, comprising a frame, two parallel horizontal rolls rotatably mounted in bearings connected to the said frame, one at least of the said rolls being a drive roll, the rolls being sufficiently separated from each other at their peripheries to allow introduction between them of a flap of skin and to remove said skin by peripheral friction by rotation in opposite directions, a work table allowing support and maintenance of the part that is to be processed, said work table being movably mounted between a first position remote from the drive roll and a second position close to the drive roll with the drive roll being disposed in an extension of the said work table at a short distance from the end of the said table, such that a flap of skin extending over the said end of the table is gripped between the said end and the drive roll to thus initiate gripping of the skin by the drive roll, the second roll being disposed below the said table.

4,296,527

TEXTILE COMBING ROLLER


Brian K. M. Eadie, Johnstone, Scotland, assignor to Eadie Bros. & Co. Limited, Paisley, Scotland

Filed Apr. 19, 1979, Ser. No. 31,472

Int. Cl.³ D01G 19/10

U.S. Cl. 19—112

9 Claims



1. An opening roller for an open-end spinning apparatus comprising: a support part adapted for driving attachment to the spindle of the apparatus and a sleeve-like adapter constructed for releasable connection to said support part, said adapter having teeth secured to a cylindrical external surface thereof, providing the fibre engaging teeth of the roller, the releasable connection being such that it both establishes driving attachment of said adapter to said support part and secures said adapter on said support part without the intervention of a third element.

4,296,528

DRAWING MECHANISM

Gennady N. Shlykov, Chilanar, kvartal 19, 31 kv. 3; Vitaly I. Zhestkov, Chilanar, kvartal 19, 26, kv. 41; Valentin N. Tikhonov, ulitsa Shota Rustaveli, 55, kv. 28; Vasily M. Dyachkov, Kuljuk - 4, 23-a, kv. 11; Vladimir G. Glazov, Chilanar, kvartal 19, 58, kv. 25, all of Tashkent, and Timur P. Krjuk, prospekt Mira, 90, kv. 11, Moscow, all of U.S.S.R.


Filed Jun. 11, 1979, Ser. No. 47,054

Claims priority, application U.S.S.R., Jul. 13, 1978, 2643332

Int. Cl.³ D01H 5/88

U.S. Cl. 19—255

7 Claims



1. In an improved drawing mechanism embodying a ringless spinning frame comprising a housing accommodating therein a feed couple including two endless belts, one of said belts being mounted about a driving cylinder and adapted to move in engagement with a movable guide and to drive the other one of said two belts, mounted about the pressure roller of said feed couple and adapted to move in engagement with a stationary guide, and a delivery couple including its own driving cylinder and its own pressure roller adapted to pass therebetween a fibrous material coming from said feed couple, there being mounted at the inlet of said feed couple a guiding member and a compacting member adapted to effect the precompacting of the fibrous material being fed into said feed couple, the improvement comprising mounting said pressure roller of said delivery couple, and the pressure roller of said feed couple jointly with the stationary guide and the respective belt thereof, the compacting member and the guiding

member on a resiliently biased common removable plate which is associated with an adjustable means for retaining said removable plate in a required position; whereby said pressure rollers are uniformly urged against said driving cylinders, thereby providing improved driving conditions, and a handle for said drawing mechanism which when pulled disengages the adjustable means for retaining said removable plate in place.

4,296,529

BAG SEALING DEVICE


Stanley E. Brown, P.O. Box 69, Harriman, N.Y. 10926

Filed Jul. 11, 1979, Ser. No. 56,445

Int. Cl.³ B65D 77/10

U.S. Cl. 24—30.5 P

8 Claims



1. A closure device for temporarily sealing flexible bags comprising: first and second longitudinally extended arms, each arm having an outer end and an inner end and at least one substantially flat inner surface, a hinge connecting said arms at the inner ends thereof, permitting said arms to pivot in one direction into stacked disposition with said inner surfaces disposed adjacent to each other, a locking assembly disposed on said inner surfaces adjacent to the outer ends of said arms comprising an upwardly projecting male snap lock element located on the inner surface of one of said arms, and a female snap lock element disposed within the inner surface of the other of said arms, said female snap lock element comprising an opening defined primarily by parallel walls being adapted to receive and releasably engage said male snap lock element therein, a clasping assembly located along said inner surfaces comprising an elongated longitudinal ridge extending along the inner surface of one arm and a longitudinal slot disposed matingly with said ridge along the opposite adjacent inner surface of the other arm, said slot extending only partially through said arm and being adapted to seat said ridge to crimpingly engage the entire girth of said bag, longitudinally extending reinforcement means located on the outer surface of and being integral with the arm defining said slot being parallel to said slot to maintain the stiffness of said arm when said slot and said ridge engage the surface of said bag, and release means located at the free end of one of said arms to disengage said locking assembly and release said bag.

4,296,530

CLAMP FOR TRIM STRIP

Klaus Muller, Weilhalingen, and Gerhard Mack, Rheinfelden-Adelhausen, both of Fed. Rep. of Germany, assignors to A. Raymond, Lorrach, Fed. Rep. of Germany


Filed Dec. 3, 1979, Ser. No. 99,747

Claims priority, application Fed. Rep. of Germany, Dec. 9, 1978, 2853254

Int. Cl.³ E04F 19/02

U.S. Cl. 24—295

4 Claims



1. A clamp for fastening trim or protective strips on a support surface having T-shaped studs mounted thereon, said studs having a head and a shank, said trim strip having an inwardly extending projection, said clamp being formed from a one-piece strip of sheet metal and having three spaced superposed legs, the middle one of said legs together with an outer one of said legs constructed to clamp said trim strip projection therebetween, the other of said outer legs being formed with a slot which receives the shank of said stud, said other outer leg and said middle leg clampingly engaging the top and bottom of the head of said stud, said outer legs being joined at the rear of said clamp across the width thereof, by a bridge, said middle leg being bent inwardly from the free end of said lower leg and extending towards said bridge and between said outer legs.

4,296,531

STRAP FASTENING MEANS

Sigurd W. Bengtsson, Bruksgatan 17, 41451 Gothenburg, Sweden


Filed Jun. 8, 1979, Ser. No. 46,702

Claims priority, application Sweden, Jun. 9, 1978, 7806704

Int. Cl.³ A44B 11/25

U.S. Cl. 24—200

5 Claims



1. A buckle for a strap comprising: (a) a generally planar housing including a pair of oppositely located rectangular sidewalls, and at least three parallel bars extending between said sidewalls for the adjustable retention of the strap, said bars being arranged to provide: (b) a first strap passage having an entrance end through the endmost portion of said housing at the narrower ends of said rectangular sidewalls, and an outlet end disposed centrally of said rectangular sidewalls and opening within said housing into an enlarged recess within said housing between said rectangular walls, said first passage extending substantially in the direction of the longer sides of said rectangular sidewalls, said sidewalls and said recess defining an extension of said first strap passage within said housing beyond said outlet end, and said first passage being defined at one side by one of said bars and at its opposite side by two further ones of said bars, the side of

said one bar remote from said first passage being an outside surface of the buckle, and

(c) a second strap passage having an external entrance end at one of said longer sides of said rectangular side-walls remote from the endmost portion of said housing and an outlet end opening into said first strap passage, and separating said two further bars and extending substantially parallel to said narrower ends of said rectangular side-walls.

4,296,532

CLASP FOR WATCH STRAP


Kok-Kit Ho, Kam Tin, N.T., Hong Kong, assignor to Timex Corporation, Waterbury, Conn.

Filed Mar. 21, 1980, Ser. No. 132,486

Int. Cl.³ A44B 21/00

U.S. Cl. 24—206 R

5 Claims



1. A clasp construction for releasably connecting the ends of a bracelet together, comprising: (a) an elongated U-shaped frame having a base plate and spaced upright walls along the sides thereof; (b) a resilient spring plate mounted between the sidewalls of the frame in spaced relation above the base plate to define a longitudinal passage therebetween for receiving one end of the bracelet and shaped to clamp the bracelet end against the base plate at a selected position, said spring plate having a transversely-oriented hook-engaging surface at one end and a transversely-oriented cam engaging surface at the other end with a pressure surface therebetween to bear against said bracelet end for effecting said clamping action, said bracelet end being adjustable in position along the passage by sliding while the spring plate bias is temporarily released; and (c) a cover member attached permanently at one end to the other bracelet end with at least one of said other bracelet end and said cover member end having a cam surface adapted to engage in snap-fit relation against the cam-engaging surface of said spring plate, said cover member having at the other end a hook surface adapted to engage around the hook-engaging surface of said spring plate, whereby said cover member is releasably attached to said spring plate by first engaging the hook and hook-engaging surfaces and then pressing down on the cover member to snap-fit the cam and cam-engaging surfaces together.

4,296,533

SNAP FASTENER COMPONENT STRIP

Randall H. Doerter, Meadville, Pa., assignor to Talon, Inc., Meadville, Pa.

Filed Mar. 13, 1980, Ser. No. 129,912


Int. Cl.³ A44B 17/00

U.S. Cl. 24—216

5 Claims

1. A snap fastener component strip particularly adapted for manipulation by automatic machinery comprising a plurality of like plastic snap components aligned in a row, a pair of integrally molded plastic connecting portions joining each pair of adjacent components, and a pair of flexible reinforcing polymer filaments extending

along the row of snap components, a portion of each filament being embedded in each component,



said filaments having substantially greater flexibility than said molded connecting portions to maintain continuity between components even if said molded connecting portions are broken by flexure.

4,296,534

CLAMP FOR FLEXIBLE HOSES

Kenji Nagano, Minoo, Japan, assignor to Osakasanko Kabushiki Kaisha and Kabushiki Kaisha Taiyohatsujyo Seisakusho, both of Osaka, Japan


Filed Feb. 12, 1980, Ser. No. 120,790

Claims priority, application Japan, Nov. 1, 1979, 54-151895[U]

Int. Cl.³ B65D 63/00, 45/34; F16L 33/00

U.S. Cl. 24—270

3 Claims



1. A clamp for flexible hoses consisting of:

- a clamping band formed by continuously winding a single springy metal wire to provide a pair of concentric circular rings partly overlapping each other to receive a hose and facing each other with a predetermined spacing therebetween, an inverted U-shaped rising bracket arm spanning the space between said circular rings at one of the respective ends of said rings, and a pair of eyelets formed by bending back the other ends thereof;
- an operating lever of metal strip integrally formed with a hook at one end thereof, a pair of eyelets having insertion holes in a middle portion thereof, and a substantially inverted L-shaped finger rest at the other end thereof, said operating lever being mounted immediately above the overlap region of said circular rings with said hook being pivotally engageable with said bracket arm; and
- a substantially U-shaped prop arm of metal wire pivotally supported at the upper end thereof in said insertion holes of said operating lever and at the lower end thereof in said eyelets of said circular rings, said prop arm being normally held in its rising position, the arrangement being such that by pressing said lever at said finger rest on its free end side downwardly against said circular rings of the clamping band, the opposite ends of the winding of the clamping band are forced to move away from each other under the resulting lever action, thereby contracting the diameter of the circular rings to clamp the hose.

4,296,535 APPARATUS FOR TEXTURIZING CONTINUOUS FILAMENTS

Hsin L. Li, Parsippany; Hendrikus J. Oswald, Morristown, and Alfred L. Liland, Lake Shawnee, all of N.J., assignors to Allied Chemical Corporation, Morris Township, Morris County, N.J.


Continuation-in-part of Ser. No. 799,066, May 20, 1977, Pat. No. 4,133,087, which is a continuation-in-part of Ser. No. 619,085, Oct. 2, 1975, Pat. No. 4,024,611. This application Jan. 8, 1979, Ser. No. 1,618

The portion of the term of this patent subsequent to Jan. 9, 1996, has been disclaimed.

Int. Cl.³ D02G 1/12, 1/16

U.S. Cl. 28—257

10 Claims



1. Apparatus for crimping continuous filaments comprising:
 - (a) a rotatable drum (44) having a peripheral recess (42) in which a screen (17), (58) forms a wall, said screen having a mesh size from 50 to 400 and being designed and constructed to permit escape of fluid therethrough to a discharge passageway (56), (59);
 - (b) a stationary cover (34) having a wall (39), (60) opposite to said screen, defining with said recess an arcuate chamber (12) through which chamber said screen in said recess continuously moves; said chamber having an inlet through the inlet tube (35), (70) specified below, and having an outlet opening (18);
 - (c) fluid directing means (37, 70) comprising an inlet tube adapted to carry fluid and filaments therethrough and positioned with its discharge end in close proximity to a portion (20) of said screen which portion changes continuously as the periphery of the drum rotates, said inlet tube making an angle (θ) of 15° to 75° with the surface of said portion of the screen closely proximate to the discharge end of the inlet tube;
 - (d) a rear extension (34), (54) affixed to said cover to the rear of said inlet tube, positioned to prevent broken filaments or plugs thereof from re-entering said chamber after being moved to and emerging from the outlet opening thereof;
 - (e) heating means upstream of said inlet tube; and
 - (f) fluid jet heating means (80) disposed in said cover in communication with said chamber downstream from said inlet tube.

4,296,536

METHOD OF MANUFACTURING CARTRIDGE CASES

David W. Hicke, Joplin, Mo., assignor to Reagent Chemical and Research, Inc., Middlesex, N.J.

Filed Jul. 25, 1980, Ser. No. 172,391


Int. Cl.³ B21D 51/54; B21K 21/04; B23P 15/22

U.S. Cl. 29—1.3

40 Claims

1. A method of manufacturing cartridge cases comprising the steps of:

providing an initial workpiece having substantially flat upper and lower surfaces;
forming a cup-shaped article from said workpiece without any intermediate annealing operations during formation of such cup-shaped article, said formed cup-shaped article having a side wall, a bottom wall defined by inner and outer bottom wall surfaces, and an upper open end, said outer bottom wall surface of said cup-shaped article being formed from said substantially flat lower surface of said initial workpiece; and
engaging said formed cup-shaped article with a punch element and forcing said cup-shaped article through a series of die members to produce said cartridge case without annealing said cup-shaped article after passage through any of said die members, said punch element having an outer side wall and a bottom wall, said bottom wall of said punch element being dimensioned so that the diameter of the peripheral edge of said bottom wall is substantially the



same as the diameter of the peripheral edge of said inner bottom wall surface of said cup-shaped article whereby at least said peripheral edge of said bottom wall of said punch element will contact the peripheral edge of said inner bottom wall surface of said cup-shaped article when said punch element engages said cup-shaped article to thereby align said punch element and said cup-shaped article with one another for forcing said cup-shaped article through said series of die members, and the side wall of said punch element and said die members being of predetermined dimensions in relation to the dimensions of said cup-shaped article so that said cup-shaped article is only subjected to ironing during passage through said die members to thereby increase the length of the side wall of said cup-shaped article while reducing the thickness of the side wall of said cup-shaped article, and so that the thickness of said side wall of said cup-shaped article at a point adjacent the upper open end thereof is reduced during passage through said die members by at least 65%.

4,296,537

VARIABLE DEFLECTION ROLL CONTROLLED BY HYDRAULICALLY ACTUATED RECIPROCATING ELEMENTS

Eduard Küsters, Gustav-Fünders-Web 18, 4150 Krefeld, Fed. Rep. of Germany, and Karl-Heinz Ahrweiler, Krefeld, Fed. Rep. of Germany, assignors to Eduard Küsters, Krefeld, Fed. Rep. of Germany

Filed Oct. 3, 1979, Ser. No. 81,327

Claims priority, application Fed. Rep. of Germany, Feb. 14, 1979, 2905542


Int. Cl.³ B21B 13/02

U.S. Cl. 29—116 AD

5 Claims

1. A hydraulically controlled variable deflection roll comprising a rotative shell having an external workrolling surface and a cylindrical inside, a fixed shaft extending through said inside with radial clearance permitting independent bending of the roll and shaft, said shaft having on one side a longitudinally extending series of blind bores extending radially into the shaft and containing reciprocating elements having outer sides connecting with bearing shoes bearing on the shell's said inside,

and means for introducing hydraulic pressure behind said elements so that said shoes apply outwardly directed force to the shell's inside and stressing said shaft with force in a direction away from the shell's said inside on which said shoes bear,



said shaft, shaped so as to taper towards its ends and bulge toward its middle, whereby when said shaft is stressed by said force, its said side will form substantially a uniform clearance from the shell's said inside substantially throughout the extent of said series of elements.

4,296,538

METHOD OF PROVIDING A SEALING ASSEMBLY BETWEEN A STEAM CHEST AND TURBINE CASING


William A. Straslicka, Norvelt, Pa., assignor to Carrier Corporation, Syracuse, N.Y.

Division of Ser. No. 909,132, May 24, 1978, Pat. No. 4,219,201. This application Nov. 2, 1979, Ser. No. 90,724

Int. Cl.³ B23P 15/00

U.S. Cl. 29—156.4 R

4 Claims



1. A method of establishing a reduced pressure across an interface between a steam chest and a turbine casing, wherein the steam chest and turbine casing define a fluid aperture for conducting high pressure steam from the steam chest, past the interface, and into an interior of the turbine casing, the method comprising the steps of:
 - forming a chamber at an end of the interface adjacent the fluid aperture;
 - separating the interface and the chamber from the fluid aperture to prevent direct contact between the high pressure steam and the interface as steam is conducted through the fluid aperture;
 - defining a fluid flow path for conducting fluid from the interior of the casing to the chamber;
 - restricting the fluid flow path from the interior of the casing to the chamber; and

venting the chamber to maintain a reduced pressure lower than the steam chest pressure in the chamber and at the end of the interface adjacent the fluid aperture.

4,296,539

HEAT TRANSFER TUBING FOR NATURAL GAS EVAPORATOR

Takayoshi Asami, Otsu, Japan, assignor to Kobe Steel, Limited, Kobe, Japan


Filed Jan. 29, 1979, Ser. No. 7,324

Claims priority, application Japan, Jan. 27, 1978, 53-8601

Int. Cl.³ B23P 15/26

U.S. Cl. 29—157.3 A

13 Claims



1. A method of making a heat transfer tube which comprises the steps of:

fabricating an elongate tubular body with two integrally attached planar fin members thereon extending longitudinally to the axis of said tubular body and projecting radially outward from the peripheral surface of said tubular body, and at the same time forming a plurality of longitudinally extending flutes on only the outer surfaces of the tubular body and fin members, while leaving the internal surface of the tubular body smooth and free of surface irregularities;

fabricating a helical fin member including at least three fin elements, each of said fin elements radially projecting from and extending longitudinally to a common axis; inserting said helical fin member into said tubular body; and drawing said tubular body alone in the direction of the longitudinal axis of said tubular body such that a pressure-fitting relationship is formed between said helical fin member and the inner surface of said tubular body.

4,296,540

METHOD FOR SEALING A DRYER

George R. Potter, Coos Bay, Ore., assignor to Burley Industries, Inc., Coos Bay, Ore.

Continuation-in-part of Ser. No. 971,845, Dec. 21, 1978,

abandoned. This application Sep. 30, 1980, Ser. No. 192,244

Int. Cl.³ B23P 3/00, 19/04

U.S. Cl. 29—460


12 Claims

1. A method for sealing a veneer dryer, having a chamber defined by planar panels connected to each other at respective elongate joints extending along respective mutually adjacent edges of said panels for confining gas at a dryer operating temperature exceeding the ambient temperature outside the chamber, against leakage of said gas from said chamber, said method comprising:

(a) while said panels are connected to each other, fastening respective elongate enclosing members into abutment with mutually adjacent pairs of said panels along said respective joints such that each of said enclosing members bridges and is longitudinally coextensive with a respective one of said joints and thereby forming respective enclosures between said enclosing members and said panels, the

interiors of said respective enclosures being exposed to respective ones of said joints;

(b) injecting into said enclosures, at a temperature less than said dryer operating temperature, a heat-resistant, gas-impermeable closed cell curable foam in such quantity that said enclosures are substantially filled with said closed cell foam;



(c) permitting said foam to cure; and

(d) thereafter operating said dryer at said dryer operating temperature and thereby increasing the temperature of said closed cell foam so as to expand said foam within said enclosures into tight sealing abutment with said joints to prevent leakage of said gas from said chamber through said joints.

4,296,541

TOOL STORAGE MAGAZINE FOR A MACHINE TOOL

Akira Tsuboi, and Shiro Kato, both of Kariya, Japan, assignors to Toyota Koki Kabushiki Kaisha, Kariya, Japan


Filed Dec. 6, 1979, Ser. No. 100,722

Claims priority, application Japan, Jan. 13, 1979, 54-3320

Int. Cl.³ B23Q 3/157

U.S. Cl. 29—568

5 Claims



1. A tool storage magazine for a machine tool comprising: a plurality of tool sockets mounted to be selectively indexable to an exchange position and pivotable at said exchange position;

a holding plunger slidably received in each of said tool sockets and engageable with a tool stored in an associated one of said tool sockets for holding said tool therein; first bias means provided in each of said tool sockets for urging said holding plunger toward engagement with said tool stored in an associated one of said tool sockets;

a cradle member pivotably mounted at said exchange position about the same axis as the pivotable movement of any of said tool sockets indexed to said exchange position and having means to carry any of said tool sockets indexed to said exchange position;

a pivot drive mechanism connected to said cradle member

for pivoting the same between first and second angular positions;

a locking member carried on said cradle member and movable onto the sliding path of said holding plunger of any of said tool sockets carried in said cradle member for inhibiting disengagement of said holding plunger from said tool stored in any of said tool sockets;

second bias means provided on said cradle member for urging said locking member onto the sliding path of said holding plunger of any of said tool sockets carried on said cradle member; and

unlocking means engageable with said locking member for retracting the same against said second bias means from the sliding path of said holding plunger of any tool socket carried on said cradle member when said cradle member is pivoted by said pivot drive mechanism to the vicinity of said second angular position.

4,296,542

CONTROL OF SMALL PARTS IN A MANUFACTURING OPERATION


Alexander Gotman, Santa Monica, Calif., assignor to Presco, Inc., Beverly Hills, Calif.

Filed Jul. 11, 1980, Ser. No. 167,667

Int. Cl.³ H01L 21/66

U.S. Cl. 29—574

14 Claims



1. In the process of manufacture of microminiature electronic circuits in which first a flat wafer is formed having a plurality of contact bumps protruding from one flat surface, then the wafer is cut into a number of individual chips each having at least two such contacts, then each chip is individually electrically tested, and thereafter selected chips are incorporated into electrical circuit assemblies;

a method of forming and handling the chips comprising the steps of:

selecting a resilient diaphragm that is larger than the wafer; stretching the diaphragm and at the same time supporting it in a substantially horizontal position;

placing the wafer upon the upper surface of the prestretched diaphragm with its contacts uppermost;

adhesively securing the entire under surface of the wafer to the upper surface of the diaphragm;

cutting the wafer along two sets of parallel lines so as to form a predetermined array of individual chips supported on the diaphragm;

selectively raising and thereby further stretching a selected portion of the diaphragm so as to elevate a selected one of the chips above the array;

while the selected chip is thus elevated, engaging the protruding contacts thereof for purpose of testing its electrical characteristics;

returning the selected portion of the diaphragm to its original position so that the selected chip resumes its position in the array;

raising other portions of the diaphragm so as to elevate and test other chips;

thereafter again raising the selected portion of the diaphragm so as to again elevate the selected chip; and

then incorporating the selected chip into an electrical assembly.

4,296,543

METHOD OF AND APPARATUS FOR FABRICATING STATOR ASSEMBLIES OF ELECTRICAL MACHINES

Tokuhiro Hamane, Hirakata; Toshio Kinoshita, Katano, and Masafumi Kihira, Osaka, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan


Filed May 29, 1979, Ser. No. 43,027

Claims priority, application Japan, May 30, 1978, 53-65209

Int. Cl.³ H02K 15/06

U.S. Cl. 29—596

10 Claims



1. A method of fabricating stator assemblies for electrical machines on an automated assembly line, each of said stator assemblies having a stator core, main coils and auxiliary coils, said assembly line including a plurality of transfer tools each having a plurality of blades rotatably arranged thereon for carrying said main and auxiliary coils; a plurality of conveyors arranged in a closed loop for successively moving said plurality of transfer tools in one direction, said closed loop conveying path including a first main path having an inlet end, first branch paths extending from said first main path, a second main path merging said first branch paths, second branch paths extending from said second main path and a third main path merging said second branch paths and having a terminal end connected to the inlet end of said first main path; a plurality of main coil winding devices located along corresponding ones of said first branch paths a plurality of auxiliary coil winding devices located along corresponding ones of said second branch paths; and a drawing-in device positioned along said third main path for drawing said main and auxiliary coils into said stator core, said method comprising the steps of:

distributing selectively each of said transfer tools into a corresponding one of said main coil winding devices, said devices being in a stand-by state;

transferring at least one of said main coils to each of said transfer tools;

moving each of said transfer tools from its main coil winding device to merge said tools onto said second main path;

pushing said main coils into the bottom of each of said transfer tools;

indexing each of said transfer tools while on said second main path by rotating the blades therein;

distributing selectively each of said transfer tools into a corresponding one of said auxiliary coil winding devices, said devices being in a stand-by state;

transferring at least one of said auxiliary coils to each of said transfer tools;

moving each of said transfer tools from its auxiliary coil winding devices to merge said tools onto said third main path; and

drawing in the main auxiliary coils carried by each of said transfer tools into said stator core, each of said stator assemblies being thereby fabricated by a single operation of said drawing-in device.

4,296,544


METHOD OF MAKING ROTOR ASSEMBLY WITH MAGNET CUSHIONS

Lyman R. Burgmeier, Cypress; Frederick B. McCarty, San Pedro, and Alexander Silver, Tarzana, all of Calif., assignors to The Garrett Corporation, Los Angeles, Calif.
Division of Ser. No. 973,343, Dec. 26, 1978. This application Mar. 11, 1980, Ser. No. 129,546

Int. Cl.³ H02K 15/02

U.S. Cl. 29—598

8 Claims



1. A method of inserting outwardly converging wedge-shaped magnets into outwardly converging wedge-shaped slots in a rotor assembly, comprising the steps of: placing cushions in contact with the walls of the slots; placing the magnets into the outwardly converging wedge-shaped slots in the rotor assembly; and rotating the rotor assembly until the magnets become wedged in place in the slots by flowing the material of the cushions therebetween.

4,296,545


CASING HOOK USED TO IMPREGNATE CHOKE OR TRANSFORMER

Esko Lampinen, Helsinki, and Kari Kajava, Espoo, both of Finland, assignors to Oy Helvar, Helsinki, Finland
Filed Mar. 31, 1980, Ser. No. 135,890

Int. Cl.³ H01F 41/00

U.S. Cl. 29—602 R

6 Claims



1. A method of conveying chokes or transformers through an impregnation vessel containing an impregnating agent comprising: forming a plurality of hooks which are of one-piece construction with a casing substantially enclosing said choke or transformer; engaging said hooks with a suspension means; suspending said casing and enclosed choke or transformer from said hooks; immersing said suspended casing and enclosed choke or transformer, exclusive of said hooks and said suspension means, in said impregnating agent for periods sufficient to allow impregnation; and removing said casing and enclosed choke or transformer from said impregnating agent while said hooks remain engaged by said suspension means; whereby said casing and enclosed choke or transformer are impregnated with said agent and air dried without immersing said hooks or said suspension means.

4,296,546


APPARATUS FOR ASSEMBLING ELECTROCHEMICAL CELL

Michael S. Hill, and David A. Poff, both of Gainesville, Fla., assignors to General Electric Company, Gainesville, Fla.
Filed Feb. 15, 1979, Ser. No. 12,659

Int. Cl.³ B23P 19/04

U.S. Cl. 29—730

14 Claims



1. Apparatus for inserting an electrode assembly core into a casing for an electrochemical cell, comprising: support means for the casing, the casing having an open end for receiving the core; a collet assembly comprised of a plurality of closely spaced tubular segments which together form a smooth, substantially continuous ring conforming generally to the perimeter of the core to be inserted, said casing support means being disposed to position the open end of the casing proximate to and in axial alignment with an exit end of said ring, said ring being inwardly tapered to engage and guide the perimeter of the core into the casing during passage of the core through the collet assembly, said tapered guiding surface being movable radially inwardly and outwardly for selectively altering the dimension of the perimeter defined thereby; means for mounting said collet assembly in fixed relation to said casing support means; controllable mechanical stop means for restricting the radially outward movement of the guiding surface to a first radial dimension, during one portion of the travel of the core through the collet assembly, and to a second radial dimension during another portion of the travel of the core through the collet assembly, core stuffer means for axially pushing the core through the collet assembly and into the casing; and means responsive to the axial location of the core for controlling the mechanical stop means.

4,296,547

APPARATUS FOR LOADING A PULL TAB ON A SLIDER BODY

Tsutomu Hakoi, Kurobe, Japan, assignor to Yoshida Kogyo K.K., Tokyo, Japan

Filed Dec. 21, 1979, Ser. No. 106,041

Int. Cl.³ B23P 19/00

U.S. Cl. 29—766

3 Claims

1. An apparatus for loading a pull tab on a slider body in a machine for progressively assembling sliders for slide fasteners, said machine comprising a base, a turret supported on the base for intermittent rotation about its center axis and having a plurality of spaced-apart recesses arranged circumferentially around and on said turret for receiving and holding a slider body, a plurality of assembling stations arranged around the periphery of said turret, and means for intermittently rotating said turret so as to position a slider body holding recess successively opposite each of the stations, said apparatus being at one assembling station of said assembling stations and comprising a pull tab supply means and a pull tab holding means; said pull tab supply means includes a holder provided on the base, a

chute supported by said holder and extending substantially vertically for receiving longitudinally aligned pull tabs therein and directing them toward a pull tab receiving portion in said recess by gravity, and means for discharging pull tabs one by one from the chute; said pull tab holding means is positioned between an outlet of said chute and the pull tab receiving portion of said recess and is movable between an advanced

tightening the fastening means around the sleeve means over the grommet.

4,296,549


METHOD OF MAKING A LEAD SOCKET INSERT

Guido Bertoglio, Viganella, Switzerland, assignor to Augat Inc., Attleboro, Mass.
Division of Ser. No. 926,227, Jul. 19, 1978, Pat. No. 4,186,990.
This application Aug. 3, 1979, Ser. No. 63,382

Int. Cl.³ H01R 43/00

U.S. Cl. 29—874

4 Claims



position and a retracted position; said pull tab holding means being arranged to form a guide channel for receiving a pull tab discharged from the chute between said outlet of said chute and the pull tab receiving portion of said recess in said advanced position, and means for opening the guide channel in said retracted position to thereby release a pull tab therefrom to drop said tab into said pull tab receiving portion of said turret recess.

4,296,548

METHOD FOR SPLICING AN ELECTRICAL CABLE

James N. Zehren, Bartlesville, Okla., assignor to TRW Inc., Cleveland, Ohio

Division of Ser. No. 816,493, Jul. 18, 1977, Pat. No. 4,198,173, which is a continuation of Ser. No. 616,318, Sep. 24, 1975, abandoned. This application Oct. 15, 1979, Ser. No. 84,756

Int. Cl.³ H01R 43/04

U.S. Cl. 29—871

3 Claims



1. A method of splicing first and second sections of electrical cable, comprising the steps of: providing transversely constrictive sleeve means; sliding said sleeve means onto said first cable section; forming an electrical splice between conductors in said first and second cable sections; positioning said sleeve means over said electrical splice so that the sleeve means receives opposed end portions of said first and second cable sections; attaching one end of said sleeve means to said first cable section; pushing said cable sections toward each other to provide slack in said opposed end portions of the cable sections; and attaching the other end of said sleeve means to said second cable section, wherein each of said attaching steps comprises: providing a grommet having mating parts adapted to be forced together around a cable section; forcing the mating parts of the grommet together around the respective cable section to grip the section therebetween; slipping the respective end of the sleeve means over the grommet; providing encircling fastening means around the sleeve means; and

1. A method for making a lead socket insert, said method comprising the steps of: center boring a wire segment to form a hollow cylinder; removing material for a portion of the length of said cylinder parallel to its longitudinal axis and tangential to the inner peripheral surface thereof thereby forming at least two oppositely disposed fingers having confronting spaced parallel flat surfaces; and then bending said fingers inwardly toward the longitudinal axis of said cylinder to provide a converging configuration; whereby said fingers flex in the manner of a leaf spring fixed at its proximate end connected with said cylinder.

4,296,550

METHOD OF MANUFACTURING ELECTRICAL CONNECTOR RECEPTACLE


Robert J. Kobler, Harrisburg, Pa., assignor to AMP Incorporated, Harrisburg, Pa.

Division of Ser. No. 944,095, Sep. 20, 1978, Pat. No. 4,186,988.
This application Nov. 8, 1979, Ser. No. 92,618

Int. Cl.³ H01R 43/00

U.S. Cl. 29—884

1 Claim



1. A method of manufacturing an electrical connector receptacle of the type comprising an insulating housing having a plug-receiving end and a rearward end, a plug-receiving opening extending into said plug-receiving end, said plug-receiving opening having opposed internal sidewalls and opposed internal endwalls, said housing having oppositely directed external sidewalls and oppositely directed external endwalls, a plurality of electrical conductors in side-by-side spaced-apart relationship, each of said conductors comprising a contact spring

extending from one of said internal sidewalls at a location adjacent to said plug-receiving end diagonally into said plug-receiving opening and towards the opposite internal sidewall, and each conductor having a lead portion extending from said plug-receiving end through said housing between said one internal sidewall and the adjacent external sidewall and towards said rearward end, said plug-receiving opening being dimensioned to receive a connector plug having spaced-apart contact members therein which engage contact spring portions of said conductors, said method comprising the steps of:

manufacturing said housing as a one-piece molding having a single conductor-receiving opening extending there-through from said rearward end to said plug-receiving end, which opening is between said one internal sidewall and the adjacent external sidewall and which has a constricted width at said plug-receiving end which is sufficient to receive all of said conductors,

manufacturing said conductors as a continuous strip of stamped and formed conductors in side-by-side spaced-apart relationship with said conductors extending from a continuous carrier strip means and with the spacing between at least portions of adjacent conductors in said strip the same as the required spacing between adjacent conductors in said connector receptacle,

severing a section of said strip having a number of conductors thereon equal to the number of conductors required in said connector receptacle,

inserting said conductors in said section through said conductor-receiving opening and positioning intermediate portions of said conductors in said conductor-receiving opening,

severing said carrier strip means from said section of strip, and reversely bending first end portions of said conductors which extend beyond said plug-receiving end and positioning said first end portions in said plug-receiving opening whereby said first end portions constitute said contact springs and said intermediate portions constitute said lead portions with second end portions of said conductors extending beyond said rearward face and being adapted for connection to further conductors.

4,296,551

RATCHETING PIPE CUTTER


Leroy Boyd, 1900 Fox Ave., Moore, Okla. 73160

Filed Dec. 10, 1979, Ser. No. 102,821

Int. Cl.³ B23D 21/06; B26B 27/00

U.S. Cl. 30—98

10 Claims

**1. A pipe cutter comprising:**

a cylindrical pipe-receiving body having a turning gear at one end thereof, a pipe cutting means at the other end thereof and a central portion disposed longitudinally therebetween connecting said pipe cutting means and said turning gear, said pipe-receiving body comprising two longitudinal portions joined by a hinge to allow said pipe-receiving body to be opened and closed about a pipe, said hinge being disposed longitudinally on said central portion between said turning gear and said pipe cutting means such that said hinge does not contact and does not extend into said turning gear and said pipe cutting means; and lever means for rotating said pipe-receiving body about a pipe, said lever means having a lever arm for manual

operation of the pipe cutter and a pawl for engaging said turning gear in a ratchet motion, and said lever means having a race for receiving said turning gear.

4,296,552

CUTTING AND SPLITTING TOOL


David B. Sabatino, 253 N. California, Mundelein, Ill. 60060

Filed Oct. 25, 1979, Ser. No. 87,985

Int. Cl.³ B26B 17/00

U.S. Cl. 30—183

19 Claims

**1. An improved cutting tool comprising:**

a housing means having a first channel extending along an axis therethrough and at least one second channel substantially perpendicularly intersecting said first channel, said housing means being formed to have an opening at the intersection of said channels;

a shaft means slidably disposed for linear movement in said first channel, said shaft means including a first portion configured to have a tapered camming surface and a second portion;

cutting means slidably disposed for linear movement in said at least one second channel, said cutting means including a cutting edge movable into said opening from one side, said cutting edge being constructed and disposed so that it is substantially parallel to said axis during linear movement of said cutting means;

means coupled to said housing means for forming a surface on a side of said opening opposite to said one side;

cam follower means pivotally mounted in said housing means and having a first surface for engaging said camming surface and a second surface for engaging said cutting means; and

means coupled to said second portion of said shaft means for causing linear movement of said shaft means and corresponding movement of said camming surface;

said camming surface being coupled to rotate said cam follower means upon movement of the shaft means in one direction to cause linear movement of said cutting means in said at least one second channel and corresponding linear movement of said cutting edge in said opening and towards said surface means.

4,296,553

PORTABLE POWER CHAIN SAW

Rudolf Dirks, Weinstadt-Schnait, and Karl Nitschmann, Schorndorf, both of Fed. Rep. of Germany, assignors to Adreas Stihl, Waiblingen, Fed. Rep. of Germany


Filed Nov. 16, 1979, Ser. No. 95,053

Claims priority, application Fed. Rep. of Germany, Mar. 23, 1979, 2911498

Int. Cl.³ B27B 17/00

U.S. Cl. 30—381

21 Claims



1. A portable power chain saw, comprising in combination: a housing;
- at least one grip including an end for connection and operatively connected to said housing;
- vibration attenuating means for each grip connection having a longitudinal central axis as well as being arranged between the end of a grip and said housing;
- a support part operatively connected to said housing and the end of said grip belonging therewith for each grip connection as well as being exchanged and installed subsequently for the motor chain saw without great cost and complexity, said support part extending between said housing and a grip belonging therewith, said support part extending generally parallel to the longitudinal central axis of said vibration attenuating means;
- at least one of said support part and said housing including an opening, and a securing member inserted in said opening with play and serving to limit movement of said support simultaneously as overload protection for said vibration attenuating means.

4,296,554

TAPE MEASURE AND MARKING DEVICE

Everett A. Hammerstrom, 34016 Edmonton, Farmington Hills, Mich. 48024

Filed Aug. 18, 1980, Ser. No. 179,026


Int. Cl.³ G01B 3/10; B43L 9/04

U.S. Cl. 33—138

4 Claims

1. A marking device for a measuring tape of the type carried in a housing with the tape coiled inside, comprising: a spring clip attached at one end to the side of the housing, said spring clip having a 180-degree bend adapted to engage the belt, a pocket, or edge of clothing,
- a marking member,
- said spring clip having an opening adapted to receive said marking member in the bend portion thereof,
- said clip further having an ovoid aperture in the end removed from the end attached to said housing, and being adapted to engage said marking member when inserted through said opening.

said spring clip further being curved at said ovoid aperture away from the end attached to said housing,



said spring clip being fixed to said housing at an angle to position said marking member engaged within said opening and said ovoid aperture in alignment with the point on said housing where said tape exits from said housing.

4,296,555

METHODS AND APPARATUS FOR CONDITIONING PLYWOOD VENEER WITH HIGH FREQUENCY RADIO ENERGY


Mark D. Preston, Meeting House Hill Rd., Mason, N.H. 03048

Filed Jan. 21, 1980, Ser. No. 113,659

Int. Cl.³ F26B 3/34

U.S. Cl. 34—1

15 Claims



1. A method of conditioning a multiplicity of sheets of veneer in a batch comprising the steps of arranging the sheets in a stack, placing the stack between a pair of electrodes, applying a predetermined pressure to the stack between the electrodes, applying radio frequency energy to the electrodes, sensing changes in moisture content of the stack under the influence of the radio frequency energy, partially relieving the pressure in response reaching a predetermined level of moisture content and continuing the application of radio frequency energy to the electrodes.

4,296,556

ROD COOLING BOX AIR WIPE NOZZLE

Lynn W. Bray, Antioch, Calif., assignor to United States Steel Corporation, Pittsburgh, Pa.

Filed Apr. 10, 1980, Ser. No. 139,074

Int. Cl.³ F26B 13/28


U.S. Cl. 34—107

2 Claims

1. An air wipe nozzle apparatus for removing water from a rod in a rod mill, said apparatus including:
 - (a) compressed air housing means, including means defining an air inlet connected to a source of compressed air and an air reservoir for receiving compressed air from said air inlet;
 - (b) air nozzle means extending through said compressed air

housing and being configured as a tube having an entrance end and an exit end permitting the passage of rods axially therethrough, said air nozzle means including:

- (i) first air passage means comprising a plurality of holes extending from said air reservoir and communicating at an acute angle with said tube proximate the entrance end to direct compressed air from said reservoir against a rod entering said tube, and
- (ii) second air passage means positioned downstream from said first air passage means and comprising a pair of slits



extending through a portion of said tube from said air reservoir oriented at about forty-five degrees with respect to the axis of said tube and the direction of rod movement therethrough and being oriented substantially normal to each other for producing a venturi effect within said tube whereby air is drawn in from the exit end and moved toward the entrance end for wiping a contained tube clean of water and to create water stripping air turbulence at said entrance end and a vacuum at said exit end for ensuring the complete removal of water from said rod.

4,296,557

SHOE WITH SOLE CUSHIONING ASSEMBLY

Paul D. Pajevic, 475 N. Northwest Hwy., Park Ridge, Ill. 60068
Filed Jan. 31, 1980, Ser. No. 118,076

Int. Cl.³ A43B 3/10; A43C 15/00

U.S. Cl. 36—7.8

14 Claims



1. A shoe with a sole cushioning assembly comprising a sole, a substantially flat flexible sole segment juxtaposed with said shoe sole and including a plurality of hinges spaced along the length of said sole segment to provide flexibility to said sole segment, a plurality of cushioning means attached to said sole segment and a plurality of cushion pads associated with said cushioning means, said cushion pads being the surface contacting portion of said shoe and being flexibly mounted substantially along the entire length of said sole.

4,296,558
ADJUSTABLE AND FLEXIBLE CLOSURE ASSEMBLY FOR SHOES WITH SEGMENTED UPPERS


Anthony J. Antonious, 205 E. Joppa Rd., Towson, Md. 21204

Filed Feb. 12, 1979, Ser. No. 11,511

Int. Cl.³ A43B 11/00

U.S. Cl. 36—50

11 Claims



1. A shoe having a sole, uppers and an opening, said uppers being segmented to form upper and lower sections, each of said sections including a fastening means to independently adjust and fasten said sections, said upper section including a single fastener means formed of an adjustable and flexible closure assembly comprising:

a flexible, multi-adjustable, separable fastener means having first and second fastening members including arrays of complementary, coacting, flexible gripping elements for securing said closure assembly;

a fastener strap included on one side of said shoe having a fixed portion and a free end, said free end including said first fastening member, said second fastening member positioned adjacent said fixed portion of said fastener strap; and

an anchor strap having a fixed portion and a free end, said free end having an opening, said fastener and anchor straps overlaying said upper section and having fixed portions being attached adjacent said sole of said shoe and located to support the arch of the wearer's foot whereby said free end of said fastener strap passes through said opening in said anchor strap permitting the shoe to be adjusted to the precise desired tautness across said upper section of said shoe.

4,296,559

ATHLETIC SHOE POCKET


Robert J. Gamm, Olivette, Mo., assignor to Envoys U.S.A., Inc., St. Louis, Mo.

Continuation-in-part of Ser. No. 938,098, Aug. 30, 1978. This application Dec. 26, 1979, Ser. No. 107,092

Int. Cl.³ A43B 23/00

U.S. Cl. 36—136

14 Claims



1. In a pocket for an athletic shoe and designed to hold smaller size personal items such as keys, coins, or the like as during jogging, comprising, said shoe having a quarter portion fixed to the sole shank at its lower extent, a pocket being stitched to the shoe quarter approximately along its front, back, and lower edges, the upper edge of the pocket being substantially free of connection with the shoe quarter and forming a pocket slot that is capable of being pulled open for

insertion of the aforementioned items therein, a cover flap stitched to the shoe along its upper edge approximately along the shoe eyestay and capable of folding over into contiguity upon the said pocket and provide it and its opening slot with coverage; and fastening means provided upon both the cover flap and the exterior of the pocket and cooperating to hold the said flap against the said pocket during shoe usage.

4,296,560

WATER INJECTION DEVICE FOR A STEAM IRON

Pierre Schwob, Lyons, France, assignor to SEB S.A., Selongey, France


Filed Jan. 30, 1980, Ser. No. 116,810

Claims priority, application France, Feb. 13, 1979, 79 03622

Int. Cl.³ D06F 75/06, 75/18

U.S. Cl. 38—77.81

8 Claims



1. A water injection device for a steam iron, comprising a plunger adapted to be moved axially over a predetermined range of travel within the orifice of a nozzle formed of elastic material and adapted to encircle said plunger in closely fitting relation thereto, the nozzle orifice being substantially coaxial with the plunger and intended to provide a communication between a water reservoir and a vaporization chamber, a longitudinal groove being formed along part of the length of the plunger, the range of travel of said plunger being such that the two ends of said groove are located on each side of the orifice in a first end position and that the two ends of said groove are located on one side of said orifice in a second end position in which second end position said plunger closes said orifice, wherein the nozzle comprises an annular portion of elastic material, a thin lip being formed on the internal wall of said annular portion in order to delimit the orifice of said nozzle, said nozzle and plunger being in contact with each other in both of said positions.

4,296,561

PICTURE FRAME HAVING INTEGRAL LATCHING MEANS

Peter Lawrence, 33 E. 22nd St., New York, N.Y. 10010


Continuation-in-part of Ser. No. 34,545, Apr. 30, 1979. This

application Mar. 5, 1980, Ser. No. 127,328

Int. Cl.³ A47G 1/06; G09F 1/10

U.S. Cl. 40—158 R

22 Claims



1. A frame for pictures, prints, or the like, comprising:

a relatively rigid, flat base, having marginal edges; the base having a front surface and an opposite rear surface; a flat cover formed of flexible material having a degree of resiliency; the cover having a front and a rear surface; the rear surface of the cover being placed over the front surface of the base; the cover having a first edge portion and a second edge portion opposite the first edge portion; latch means secured to the cover at the first edge portion of the cover; the latch means including a relatively rigid relatively rigid strip having greater rigidity than the flexible material of the cover, the strip being located at the first edge portion and also extending in a distance partway from the relatively rigid first edge portion to the second edge portion, and the strip also extending along the first edge portion; the strip including a surface thereof secured to the adjacent surface of the cover, whereby the strip secured to the flexible cover prevents the cover from flexing where the cover surface and strip surface are secured together; a rigid flap on the rigid strip for extending down the rear surface of the base; the flap having greater rigidity than the flexible material of the cover; the latch means flap being long enough that the relatively rigid flap holds the cover securely on the base; the cover being secured to the base at a location away from the first edge portion of the cover, thereby enabling the first edge portion to be latched to the base and to be moved away from the base.

4,296,562

TRAVELING LIGHT DISPLAY


George A. Sanborn, 19210 NE. Clackamas St., Portland, Oreg. 97230

Continuation of Ser. No. 887,753, Mar. 7, 1978, abandoned. This application Dec. 14, 1979, Ser. No. 103,848

Int. Cl.³ G09F 19/00

U.S. Cl. 40—438

4 Claims



1. A traveling light display, comprising:

- (a) an elongated reader member having therethrough a multiplicity of light passageways arranged in laterally and longitudinally spaced-apart relationship,
- (b) a source of light spaced from the reader member and arranged for directing light through said passageways, the source of light including an electric lamp in an electric circuit of a source of electric potential,
- (c) an elongated opaque tape having therethrough a multiplicity of holes spaced apart laterally and longitudinally for registration with passageways in the reader member and arranged in patterns forming a plurality of longitudinally spaced indicia,
- (d) drive means engaging the tape for moving the latter longitudinally past the reader member for producing at the light passageways said indicia patterns as spots of light moving across the reader member from one end to the other, the tape drive means including an electric drive motor in an electric circuit of a source of electric potential, an air fan driven by the tape drive motor, and an electric switch arranged in the electric circuits of the electric lamp and drive motor and operable by a predeter-

mined velocity of air driven from the fan to complete said electric circuits and operable in the absence of said predetermined velocity of air to open said electric circuits, (e) an elongated viewing member, and (f) coupler means registering with each passageway in the reader member for causing a spot of light appearing at a passageway to result in the display of a spot of light at the viewing member moving across the latter from one end to the other.

4,296,563


DISPLAY DEVICE WITH PRICE CHANGE CARTRIDGES
Joseph Clement, Bradenton, Fla., assignor to The Mead Corporation, Dayton, Ohio

Filed Aug. 5, 1980, Ser. No. 175,476

Int. Cl.³ G09F 11/18

U.S. Cl. 40—518

7 Claims



1. In a display device of the type comprising a translucent facia, a carrier disposed behind said facia and including a display area, at least one information strip bearing a series of characters and being mounted on said carrier for slidable adjustment so that the characters can be sequentially displayed in said display area, support means on which said carrier is detachably mounted with the display area located adjacent said facia, said facia and support means together defining a space in which said carrier is accommodated, the improvement wherein said support means comprises panels located adjacent opposite ends of said facia and complementary attachment means provided on said carrier and on said support means, said complementary means comprising rails provided on said panels and flanges provided on said carrier.

4,296,564


SEMI-AUTOMATIC RELOADING FIREARM
E. Ernest Oberst, Cheshire, Conn., assignor to The Marlin Firearms Company, North Haven, Conn.

Filed Jun. 18, 1979, Ser. No. 49,347

Int. Cl.³ F41C 27/12

U.S. Cl. 42—1 C

2 Claims



1. In a firearm having a receiver member, a firing chamber, a breech bolt member spring-urged into closed position and retracted therefrom into open position by the powder gases of a fired cartridge, a cartridge magazine, a device for feeding a

cartridge from the magazine into the firing chamber on each cycle of the breech bolt member into open and closed position, a hidden hammer in said receiver member moved into cocked position by the breech bolt member on its retraction from closed position and spring-advanced into firing position on release in its cocked position, and means including a trigger for releasing said hammer in its cocked position on pulling the trigger, the combination of a visible signal element movable on the receiver member, and an actuator pivoted on said breech bolt member for turning movement thereon, with said actuator being spring-urged into a first position in the path of said hammer to be cammed thereby into a second position on the advance of said hammer into firing position, and said signal element is in and out of follower relation with said actuator in said closed and open positions, respectively, of said breech bolt member, with said signal element when in follower relation with said actuator assuming in said first and second actuator positions corresponding first and second positions denoting firing and non-firing response, respectively, of said hammer to the next trigger pull.

4,296,565

APPARATUS FOR COLLECTING EJECTED CARTRIDGES


Harry A. Jaffin, 190 Parish St., Canandaigua, N.Y. 14424, and Russell H. Gilwee, R.D. 3, Holcomb, N.Y. 14469

Filed Oct. 15, 1979, Ser. No. 84,555

Int. Cl.³ F41C 27/00

U.S. Cl. 42—1 T

8 Claims



1. A free-standing structure for receiving cartridges automatically ejected from a firearm upon firing from a predetermined location, said structure comprising:

- wall means of flexible, resilient, unstretched material forming a bag-like enclosure with an unobstructed opening at one end;
- a rigid frame attached to said wall means and holding said one end of said wall means in a position laterally adjacent said predetermined location and physically separated from said firearm, with said opening fully occupying a plane intersected by cartridges ejected by said firearm when fired from said predetermined location, whereby said ejected cartridges pass through said opening and strike the interior of said bag-like enclosure; and
- support means holding said wall means outwardly from said frame to provide a portion of said wall means directly opposite and spaced from said opening in a slack, unstretched condition to substantially prevent rebound of said cartridges.

4,296,566


ARM OR SHOULDER ATTACHMENT FOR GUNSTOCKS
Conrad Campos, P.O. Box 687, Tonopah, Nev. 89049

Filed Aug. 28, 1979, Ser. No. 70,420

Int. Cl.³ F41C 23/00

U.S. Cl. 42—71 R

2 Claims



1. In combination with a firearm having a barrel and a rearwardly extending gunstock when the firearm is in the firing position, a gunstock attachment comprising:
a butt plate attachable to the butt end of the gunstock;
track means formed in the butt plate with the longitudinal axis of the track extending in a vertical direction when the firearm is in the firing position;
a first gunstock extending member having a foot portion and a leg portion normal to the foot portion;
track engaging means formed on the foot portion and adapted to engage the track means on the butt plate;
means for releasably securing the track means and track engaging means to each other;
a second gunstock extending member comprising a body engaging arm member and a rod member, said rod member telescopically engaging the leg member of the first gunstock extending member;
means for securing said rod member to the leg member, wherein the second gunstock member is rotatable relative to the first gunstock extending member;
wherein the means for securing said rod member to the leg member prevents relative telescopic movement and relative rotational movement between the members; and
wherein the securing means for said rod member and the leg member comprise a bolt and split sleeve carried by the extended rearward end of the leg member.

4,296,567


FIGURE TOY WITH FLEXIBLE APPENDAGES
Pascal M. Kamar, Palos Verdes Estates, Calif., assignor to Kamar International, Inc., Torrance, Calif.

Filed Apr. 22, 1980, Ser. No. 142,786

Int. Cl.³ A63H 3/46

U.S. Cl. 46—163

6 Claims



1. A figure toy adapted for undergoing simulated contortions, comprising a body part, the body part having a plurality

of appendages, such appendage including a flexible manipulatable portion and an end section, the said portion being between the body part and the end section, the said end section having a construction which is weighted whereby to have a holding capability whereby the toy can be supported or suspended from a surface by way of at least one of the appendages and its end section having engagement with the surface, said end section having sufficient weight to hold the toy suspended.

4,296,568


AGRICULTURAL CROP COVER
Jesse M. Dukes, P.O. Box 1184, Hemet, Calif. 92343

Filed Nov. 5, 1979, Ser. No. 91,472

Int. Cl.³ A01G 13/00

U.S. Cl. 47—20

10 Claims



1. An apparatus for protecting crops against frost damage, said apparatus of the type having a framework supported by a plurality of erect posts planted permanently in the earth and a movable cover supported by and above said framework and above the crops, said cover being capable of being extended over the top of the framework to protect the crops from damage resulting from still air radiation frost, the improvement comprising:

a static rigging attached to said posts;
means for connecting said cover to said static rigging at a location along a center row of said posts; and
means for transporting at least one outer edge of said cover between a first outer edge of said framework and any position between said center row location and said outer edge, said transporting means being supported by said static rigging; and being moved by running rigging, and means for scooping portions of said cover from said static rigging and gathering said cover on said transporting means as said transporting means moves from said first outer edge to said other positions.

4,296,569

NESTABLE AND STACKABLE TRANSPLANTING SYSTEM

Bryant Edwards, Clarendon Hills, Ill., assignor to Illinois Tool Works Inc., Chicago, Ill.

Filed Oct. 22, 1979, Ser. No. 87,286


Int. Cl.³ A01G 23/02

U.S. Cl. 47—73

9 Claims

1. An assembly adapted for growing a plurality of plants intended to be transplanted, said assembly comprising a support tray, a plurality of integrally interconnected sleeves, said tray having sidewalls and a grid-like upper structure, said sidewalls being inclined upwardly and inwardly from an open bottom of said support tray to said grid-like upper structure, said upper structure comprising a plurality of vertical wall means spaced apart longitudinally and laterally of said tray, said vertical wall means defining a first predetermined vertical dimension from the uppermost surface of the grid-like structure to the lowermost surface of the vertical wall means, the sidewalls defining a second predetermined vertical dimension

from the uppermost surface of the grid-like structure to the lowermost edge surface of the tray, the second predetermined vertical dimension being greater than the first predetermined vertical dimension, said plurality of integrally interconnected sleeves including a plastic sheet forming web means interconnecting the upper extremities of the sleeves, the sleeves depending downwardly from the web means and arranged in a pattern permitting the web means to be disposed on the uppermost surface of the grid-like structure with the sleeves depend-



ing between the vertical wall means, each of the sleeves having walls tapering downwardly and inwardly from the uppermost extremity to the lowermost extremity thereof, the vertical dimension of the sleeve being substantially greater than said first predetermined vertical dimension and less than said second predetermined vertical dimension, whereby a plurality of said assemblies are stackable and nestable with each sleeve nesting in a sleeve below, the upper sleeve being spaced from the below sleeve so that said assemblies are freely denested from each other.

4,296,570

HYDRAULIC DOOR OPERATOR


George C. Balbach, Lake Forest, Ill., and Robert J. Peterman, Cedarburg, Wis., assignors to Arthur Smith Industries, Inc., Milwaukee, Wis.

Filed Sep. 7, 1979, Ser. No. 73,275

Int. Cl.³ E05F 15/02

U.S. Cl. 49—360

14 Claims



1. A door operator having a hydraulic system for opening and closing a door, comprising:
a hydraulic pump for pumping fluid;
an electric motor for rotating said pump;
an electric control circuit which activates said electric motor to rotate said pump in the appropriate direction;
a reversible hydraulic motor connected through hydraulic control lines with said pump to be driven thereby, said

hydraulic control lines comprising a first line between a first side of said hydraulic pump and a corresponding side of said hydraulic motor and a second line between a second side of said hydraulic pump and a corresponding side of said hydraulic motor;

valve means in each of said hydraulic control lines between said hydraulic pump and said hydraulic motor that are normally closed to lock fluid in said hydraulic motor to block turning thereof;

a pilot line extending between each hydraulic control line and the valve means in the other hydraulic control line, whereby pump pressure in one control line opens the valve means in the other control line;

drive means driven by said hydraulic motor to open and close said door; and

a pressure relief valve connected to said control lines for diverting fluid from said motor.

4,296,571

PROFILE GRINDING APPARATUS


Joseph Horvath, 11 Notch Rd., Clifton, N.J. 07013

Filed Aug. 16, 1979, Ser. No. 66,945

Int. Cl.³ B24B 17/02, 49/12, 17/04

U.S. Cl. 51—32

14 Claims



1. A profile grinding apparatus comprising a stationary frame, a first table adapted for holding a template thereon and mounted on said frame, a second table mounted on said frame, said second table being arranged to hold a workpiece at a fixed position, pantograph means movable in a horizontal plane and comprising guiding means for movement in said plane, first movable support means mounted on said stationary frame and coupled to said pantograph means for following the movement of said guiding means, second movable support means mounted on said stationary frame at a spaced location below said first movable support means and connected to said first movable support means for corresponding movement therewith, grinding means carried by said first and second movable support means and arranged for reciprocation along a vertical axis between said first and second support means to grind a contour on a workpiece held on said second table, both said first and second movable support means being mounted on said stationary frame by a movable support assembly, said movable support assembly comprising first rod means having a longitudinal axis about which said first rod means is rotatable, said first rod means being mounted on said stationary frame with said longitudinal axis vertical, first bracket means fixedly secured to said first rod means below said first bracket means, second rod means having a longitudinal axis about which said second rod means is rotatable, said second rod means being supported with its axis vertical and for rotation thereabout by first and second bracket means, third bracket means fixedly secured to said second rod means, fourth bracket means fixedly secured to said second rod means below said third bracket means, said third bracket means being pivotally connected to

said pantograph means and to said first movable support means at a vertical pivot axis, said fourth bracket being pivotally connected to said second movable support means at said vertical pivot axis, said grinding means including a grinding surface located tangent to said vertical pivot axis.

4,296,572

DUST REMOVING ATTACHMENT DEVICE FOR AUTOMATIC AIR FILES

Pedro Quintana, 1920 E. Wilder Ave., Tampa, Fla. 33610


Division of Ser. No. 887,517, Mar. 17, 1978, abandoned. This

application Oct. 12, 1979, Ser. No. 84,330


Int. Cl.³ B24B 55/06

U.S. Cl. 51—170 TL

5 Claims



1. A dust removing attachment device for pneumatically driven straight-line power files of the type having a reciprocative sole plate comprising, in combination, an elongated, rectangular replacement shoe member, means for removably attaching a flat upper surface portion of said replacement shoe member to said sole plate, said shoe member being substantially hollow to define an end-to-end internal chamber, the underside of said shoe member being formed with a plurality of peripherally-spaced through openings, means energized by pressurized air for creating a vacuum in said chamber operative to withdraw air peripherally from the underside of said shoe member into said vacuum chamber together with abraded particles generated upon use of the automatic air file, a dust bag communicating with one end of said replacement shoe member, said vacuum creating means comprising an air jet directed into the interior of said dust bag through said one end of said dust bag for inflating it with dust-carrying air from said vacuum chamber, said air jet being disposed adjacent said one end of said replacement shoe member, and a second air jet within said vacuum chamber and longitudinally spaced from said first mentioned air jet.



relation to said stage, and means interconnecting said modules in edge-to-edge relationship.

4,296,574

FLOOR PANEL-FURNITURE SUPPORT SYSTEM

William I. Stephens, Telford, Pa., assignor to Knoll International, Inc., New York, N.Y.


Continuation of Ser. No. 877,619, Feb. 14, 1978, abandoned.

This application Oct. 22, 1979, Ser. No. 86,751

Int. Cl.³ E04F 15/024

U.S. Cl. 52—27

6 Claims



1. In a floor panel system that includes a plurality of floor panels, and support means positioned upon a fixed base floor supporting said floor panels in fixed position above said base floor, the improvement in which at least one of said floor panels rests upon said support means in freely-removable relationship therewith and includes as an operatively interconnected part thereof means for holding and supporting a furniture item.

4,296,575

AUTOMOBILE SHED

Diara Verable, and Willie M. Gibson, both of 3803 Groton St., San Diego, Calif. 92110

Filed Dec. 26, 1979, Ser. No. 106,911

Int. Cl.³ E04B 7/16

U.S. Cl. 52—66

1 Claim

1. A liftable vehicle storage shed comprising:
(a) a horseshoe-shaped box-beam frame having two legs and a rear cross member;
(b) a substantially flattened housing conforming generally to the exterior shape of a vehicle and hinged to said frame crossbeam to fall flush against said horseshoe-shaped frame when in lowered position to define an enclosed space over the surface on which it rests, said housing

4,296,573

AUDIENCE CONTROL BARRIER

Kermit H. Wilson, Edina, and Ronald R. Carlson, Excelsior, both of Minn., assignors to Sico Incorporated, Minneapolis, Minn.

Filed Jul. 18, 1979, Ser. No. 58,669


Int. Cl.³ E04D 3/10; E04H 17/18

U.S. Cl. 52—6

13 Claims

1. In combination, an elevated stage having support legs, and a modular audience control barrier secured to said legs near the bottoms thereof, said barrier comprising a plurality of

- being pivotal on said crossbeam from said lowered position to a raised position providing access therewithin;
- (c) said box-beam being bolted down to a flat driving surface by inwardly directed L-shaped flanges to prevent tampering with mounting bolts in said flanges when said housing is lowered, and said box beam also mounting upwardly directed parallel guide members to guide the periphery of said housing into seated position;
- (d) an access door positioned to substantially align with a vehicle stowed in said shed;



- (e) means for maintaining said housing in raised position comprising a rigid strut pivoted at the lower end thereof at a first point on said frame and defining a tracking member at its upper end, and further including an adjustable extension spring means connected between an upper portion of said strut and a point on said frame rearward of said first point, and said housing defines a longitudinal track slideable engaging said tracking member; and
- (f) a tether connected between said housing and said frame to limit the extent of opening of said housing.


4,296,576

SLOPED WALL STRUCTURE AND ANCHOR CLIP
Hoyt G. Rice, Jr., Ellenwood, and Daniel J. Reynolds, Austell, both of Ga., assignors to The Anaconda Company, Denver, Colo.

Filed Sep. 12, 1979, Ser. No. 74,875
Int. Cl.³ E04B 7/02

U.S. Cl. 52-90

10 Claims



1. A sloped wall structure for extending between a lower horizontal support and an upper vertical support, a plurality of rectilinear rafters positioned in spaced relationship with respect to one another and inclined upwardly from the lower horizontal support to the upper vertical support, infill sheets mounted on said rafters and forming with said rafters a sloped wall, each of said rafters including in cross section a pair of spaced vertically oriented parallel walls, an anchor clip connected between the lower end of each of said rafters and the lower horizontal support, each of said anchor clips including a

base plate and a leg, said base plate including means for rigidly mounting said base plate to the lower horizontal support and a hinge boss at one edge portion thereof, said leg including means for rigidly mounting said leg between the spaced walls of the rafters and a hinge boss at one edge portion thereof constructed to mate with the hinge boss of said base plate, a pivot pin extending through the hinge bosses of the base plate and the leg of each anchor clip to hingedly anchor the sloped wall structure to the lower horizontal support.

4,296,577

HELICAL STAIRCASE SUPPORT


Heinz G. Schuette, 26145 Shook, Mt. Clemens, Mich. 48045

Filed Oct. 22, 1979, Ser. No. 87,040

Int. Cl.³ E04F 11/00

U.S. Cl. 52-187

6 Claims



1. A helical staircase comprising:
a plurality of brackets for supporting stair treads;
each bracket including a first vertical tube having an upper end and a lower end;
a transverse member affixed the first vertical tube upper end;
a second vertical tube axially spaced from the first tube having an upper end and a lower end;
a horizontal member extending between tubes affixed at one end to the first tube upper end and affixed at another end to the second tube lower end;
a stair tread abutting said horizontal member longitudinally along a transverse central portion and abutting said transverse member; and
said brackets joinable with said first tube lower end abutting said second tube upper end.

4,296,578

SKYLIGHT APPARATUS

Heikki Keckman, Itäharjutie 11, 07900 Loviisa, Finland


Filed Jun. 12, 1979, Ser. No. 47,867

Claims priority, application Finland, Jun. 13, 1978, 780690; Jun. 13, 1978, 781893; Oct. 20, 1978, 783238

Int. Cl.³ E04B 7/18

U.S. Cl. 52-200

14 Claims



1. Skylight apparatus adapted to be located within a skylight aperture defined by aperture forming building frame components, comprising:

at least two dome-shaped light-transmitting window elements having outer dimensions which vary with respect to each other defining larger and smaller window elements, each of said window elements including peripherally extending outer support edge portions, said window ele-

ments being mounted in vertically spaced relationship one above the other at their respective peripheral support edge portions with the largest of said window elements being located at the uppermost position; and

means for mounting said window elements in a manner such that the mutual spacing between regions adjacent to said peripherally extending outer support edge portions of vertically adjacent window elements are substantially equal to the mutual spacing between the central portions thereof and such that the spacing between at least the lowermost window element and the next vertically adjacent window element is located within the skylight aperture forming building component, said mounting means including a frame structure defining a plurality of vertically spaced supporting portions, each of said supporting portions extending around the inner periphery of said supporting structure and wherein each of said plurality of supporting portions extends inwardly to a greater extent than the supporting portion located immediately thereabove, said supporting portions comprising surfaces which slope downwardly and inwardly and wherein said peripheral edge support portions of said window elements extend continuously upwardly and outwardly at a slope which substantially corresponds to the slope of said frame supporting portions, and wherein a plurality of said vertically spaced window elements are provided, each having a dimension which varies with respect to the other of said window elements, said window elements being mounted at their peripheral edge support portions on corresponding supporting portions of said frame structure with the smallest window element being the lowest of said window elements and the largest window element being uppermost, and wherein said frame structure is adapted to be mounted on said skylight aperture forming building frame component.

4,296,579

SCREEN PANEL


Norman Proud, 16 West St., Oakville, Ontario, Canada (L6L 2Y6)

Filed May 9, 1979, Ser. No. 37,563

Int. Cl.³ E04B 2/72; A47G 5/00

U.S. Cl. 52-239

6 Claims



1. A screen panel comprising:

(a) a frame for said panel, said frame having a closed perimeter and defining front and rear planar surfaces spaced apart in a front to rear direction and extending in parallel lateral planes.

(b) a plurality of clips fixed to said frame and spaced around the perimeter of said frame, some of said clips being associated with said front surface and some of said clips being associated with said rear surface, each clip having a support portion extending in said front to rear direction be-

yond its associated front or rear surface and a retainer portion extending from the outer end of said support portion and directed outwardly in a direction having a component parallel to a said lateral plane,

- (c) two sleeves, each sleeve having:

(i) a self supporting subframe formed from a resilient wire rod which defines a closed perimeter,

(ii) a fabric material extending across said subframe and covering said wire rod,

(d) said wire rod of one sleeve being fitted over said support portions of said clips associated with said front surface and said wire rod of the other sleeve being fitted over said support portions of said clips associated with said rear surface,

whereby a said sleeve may be removed from said panel by deforming a portion of its wire rod in a direction generally laterally outwardly to move such portion clear of the retaining portion of a clip on which such portion is fitted, and then moving such portion outwardly in a front to rear direction, away from said frame.

4,296,580

WALL CONSTRUCTED FROM PANELS HELD IN POSITION WITH THE AID OF CONCEALED FASTENERS AND CONCEALABLE FASTENERS FOR USE IN ASSEMBLING SUCH WALL

Roger N. Weiner, 19 Parkside Ave., Hamburg, N.Y. 14075


Continuation-in-part of Ser. No. 947,078, Sep. 29, 1978, Pat. No. 4,221,095, which is a continuation-in-part of Ser. No. 736,425,

Oct. 28, 1976, Pat. No. 4,117,644. This application Jul. 23, 1980, Ser. No. 171,331

Int. Cl.³ E04B 1/00

U.S. Cl. 52-281

22 Claims



1. A wall or partition comprising first and second coplanar end-abutting panels, substantially invisibly secured together along a joinder line at a wall framing member by a first series of a plurality of spaced apart fasteners joined to the first panel at the abutting end thereof and held to the framing member, and a second series of spaced apart fasteners joined to the second panel at the abutting end thereof and with parts of each of the fasteners of each of both series of fasteners extending parallel to said panels at concealed back major surfaces thereof, said fasteners of the second series of fasteners being so located as to avoid contact with said fasteners of the first series of fasteners, and said extending parts of said fasteners of the second series of fasteners, when the wallboard panels are in coplanar end-abutting relationship, contacting the back major surface of the first panel and, in conjunction with the framing member, the first series of fasteners, means for holding the fasteners of the first series to the framing member, and the first panel, preventing said second panel from moving away from said framing member and from said first panel in a direction having a component at right angles to the plane of the panels, which fasteners of the first series are each comprised of directly connected plate and tongue portions which are essentially flat, with the plate portion contacting the first panel and the tongue portion contacting the second panel, a pair of web portions extending only from the plate portion and installed between first and second panel ends, a pair of impaling portions extending from said web portions and overlying said plate portion and penetrating said first panel at an abutting end

thereof, a framing contacting part of the fastener, and a panel contacting part of the fastener, with such framing contacting and panel contacting parts being connected by a wall member or plurality of wall members, which space(s) them apart and strengthen(s) the fastener, and which fasteners of the second series are of the same structure as those of the first series.


4,296,581

ROOFING STRUCTURE

Robert E. Heckelsberg, Germantown, Tenn., assignor to AMCA International Corporation, Hanover, N.H.
Continuation-in-part of Ser. No. 875,524, Feb. 6, 1978, Pat. No. 4,213,282. This application Jul. 31, 1979, Ser. No. 62,300
The portion of the term of this patent subsequent to Mar. 18, 1997, has been disclaimed.
Int. Cl.³ E04D 1/00, 1/34

U.S. Cl. 52—520

5 Claims



1. In a paneling construction adapted to be installed by attachment to spaced parallel structural supporting elements such as the roof purlins of buildings, said construction comprising a plurality of elongated panels laid over and transversely to such supporting elements with the side edges of the panels abutting, said panels having generally planar mid-portions lying close to the supporting elements and having upstanding seaming flanges on said side edges folded over and crimped together to provide a mechanical interlock, each of said panels having supporting portions for said seaming flanges, said supporting portions extending angularly upwardly away from each other and from the mid-portion of the panel whereby the supporting portions of adjacent panels define a tunnel-like area and clip means securing the panels to the structural supporting elements, each clip means including a base member, attaching means rigidly securing said base members and clip means to a structural supporting element in the tunnel-like area defined by the supporting portions of adjacent panels, said construction being characterized by:

- A. A rim portion incorporated in an intermediate part of each of the supporting portions of each panel, said rim portions lying substantially in a common plane and extending inwardly toward one another from and substantially perpendicularly to the seaming flanges,
- B. The base member of each of said clip means having an upstanding column with a top portion closely underlying and supporting said rim portions of the adjacent panels,
- C. A holding portion secured to the base member of each clip means and preventing outward movement of the holding portion, said holding portions projecting upwardly from the base member between, and being folded over and crimped together with, the seaming flanges of the adjacent panels to prevent relative movement therebetween,

whereby said holding portion and the top portion of the base member co-act with the seaming flanges and with said attaching means to prevent movement of the seaming flanges and of the supporting portions of the panels toward and away from the structural supporting elements and also to hold the holding portion against movement toward the base member.

4,296,582 CONSTRUCTION SYSTEM AND FASTENERS THEREFORE


Harold G. Simpson, and Michael W. Davis, both of Oklahoma City, Okla., assignors to Star Manufacturing Company of Oklahoma, Oklahoma City, Okla.

Filed Dec. 31, 1975, Ser. No. 645,566

Int. Cl.³ E04C 1/10

U.S. Cl. 52—590

19 Claims



1. A fastener adapted to interlock with another similar fastener to provide a seal between the fastener, said fastener including a body portion including a plurality of male and female members for interlocking engagement with similar such members of said similar fastener, said fastener being made by a process including the steps of:
mixing and combining a fastener material including Hypalon, and
manufacturing the fastener from said material; and
utilizing a dust cap prior to connection of said fastener to said similar such fastener to transfer a lubricant to said fastener while protecting the fasteners from an accumulation of dirt.

4,296,583

SLAP TRIM INTERIOR MOLDING


Louis D. Egenlauf, 12634 Saginaw Ave., Chicago, Ill. 60633

Filed Aug. 27, 1979, Ser. No. 69,889

Int. Cl.³ E04C 2/38

U.S. Cl. 52—717

1 Claim



1. A slap trim interior molding, comprising, in combination, an elongated plastic extrusion and a plurality of separate holding pins for holding said extrusion against a room wall; said extrusion comprising a hollow shell having an elongated, decorative-shaped, front wall, and a rear wall intercepted along its longitudinal center by an elongated, straight slot; each said holding pin including an enlarged head having a groove on its opposite sides, for elongated edges of said extrusion rear wall along said slot to snap-fit therein; a portion of said rear wall adjacent each said slot edge being thin-walled respective to a remaining thicker-walled portion of said rear wall, and an angularly inclined flange extending inwardly into said shell from each said slot edge, and a plurality of longitudinally extending, thin-walled accordion pleats are formed between each said thin-walled portion and said thicker-walled portion of said rear wall, for flexing of any portion of said slot edges in a transverse direction either toward or away from each other.

4,296,584

METHOD FOR OFFSET ANCHORING A FENCE POST


Bernard J. Lempa, Jr., 8422 Carvel La., Houston, Tex. 77036

Filed Sep. 4, 1979, Ser. No. 71,988

Int. Cl.³ E02D 27/42

U.S. Cl. 52—742

7 Claims



1. A method of reanchoring a fence post which is no longer firmly supported in the ground without disturbing the existing post foundation or the fence structure associated therewith comprising the steps of:

- digging a hole in said ground adjacent said post foundation;
- attaching to the lower end of said post and next to said post foundation the vertical leg of a bracket which also has a horizontal leg from which depends an anchor member for disposition within said hole;
- pouring a concrete mixture into said hole and around said anchor member to a level substantially flush with said horizontal bracket leg; and
- allowing said concrete mixture to set without disturbing said post and bracket.

4,296,585

PERMANENT WEATHER COVERS

Dante Bini, 48 Chandos St., Crows Nest, N.S.W. 2065, Australia


Filed May 9, 1979, Ser. No. 37,925

Claims priority, application Australia, May 30, 1978, PD4545

Int. Cl.³ E04B 1/34

U.S. Cl. 52—745

5 Claims



1. A method of forming a self-supporting domed space frame comprising the steps of:

- (a) taking a plurality of elongated longitudinal elements, each of said elements having a longitudinal axis and opposed ends and at least some of said elements being extensible and having
 - (i) a minimum length and an operative length greater than said minimum length, and
 - (ii) arresting means to prevent a reduction in the length of the element to a value less than said operative length, said arresting means being automatically operable when the element has had its length increased to a value not less than said operative length;
- (b) assembling said elements into a substantially planar grid, wherein
 - (i) an end of each element is pivotally connected to an end of the next adjacent element for pivotal movement about a horizontal axis extending transversely of said elements, and

- (ii) the elements are free to twist about the longitudinal axes thereof;
- (c) anchoring elements of the grid at the grid periphery in a manner permitting such anchored elements to swing upwardly;
- (d) locating an inflatable membrane in lifting relationship to the grid;
- (e) inflating the membrane to lift the grid to a point wherein all of the extensible elements have been extended to at least their respective operative lengths;
- (f) locking at least certain of the elements against return pivotal movement about said transversely extending axes; and,
- (g) releasing the inflation pressure from the membrane to permit said gridwork to be self-supporting.

4,296,586

FASTENING DEVICE FOR A HONEYCOMBED PANEL EMPLOYED IN PARTICULAR IN AERONAUTIC STRUCTURES

Bernard M. Heurteux, Verviers, Belgium, assignor to Shur-Lok International, S.A., Petit-Rechain, Belgium


Filed Oct. 30, 1979, Ser. No. 89,459

Claims priority, application France, Nov. 6, 1978, 78 31314

Int. Cl.³ E04C 2/54

U.S. Cl. 52—787

2 Claims



1. A fastening device for mounting in a marginal region of a panel comprising a honeycombed network and skins respectively covering opposed large sides of the network and imparting a required stiffness to the panel, said device comprising a sleeve for placing in an opening formed transversely in the panel, the sleeve having opposed end portions of a given shape, a fastening member extending through the sleeve, and two strengthening means for contributing to the connection of the sleeve with the skins of the panel, said strengthening means comprising thin plates for respectively adhering to the skins of the panel in a region which surrounds the opening formed in the panel and having an area which distinctly exceeds the cross-sectional area of the sleeve, each plate comprising an aperture for substantial alignment with the sleeve, an edge portion of each plate defining the plate aperture substantially conforming to said given shape of the corresponding end portion of the sleeve so as to ensure the transmission of transverse forces exerted on the sleeve by said fastening member to an area of the skins corresponding to at least the extent of said plates, the aperture of at least one of the plates being bordered by an annular flange obtained by deformation of the plate and extending in a direction perpendicular to the general plane of the plate, the corresponding end portion of the sleeve having a bearing surface on which said flange is an interference fit, and at least one of the plates having a flange folded at a right angle for bearing against a lateral edge of the panel.

4,296,587


SPACER FOR DOUBLE GLAZED WINDOWS
INCORPORATING INTERLOCK MEANSGunter Berdan, Weston, Canada, assignor to Custom Rollform-
ing Company Limited, Weston, Canada

Filed Nov. 27, 1979, Ser. No. 97,773

Int. Cl.³ E04C 2/38

U.S. Cl. 52-788

6 Claims



1. A spacer tube for a hermetically sealed double glazed window, the spacer tube being formed from an elongated strip of metal bent into a hollow elongated tubular shape, the spacer tube having opposing side wall portions, a base extending between and connecting the side wall portions and a further wall spaced from the base, such further wall defining a region wherein the longitudinal edges of the strip extend toward each other, and wherein a surface of the spacer tube which faces into the interior of the spacer tube has a plurality of closely spaced ridges therein, said surface having said ridges therein being the interiorly facing surface of said base, the ridges being spaced apart in the lengthwise direction of the spacer tube and the individual ridges extending generally transversely of the longitudinal axis of the spacer tube, the ridges being located at least in the regions adjacent the ends of the spacer tube whereby, in use, to provide for locking engagement with teeth on the arms of corner pieces when inserted endwise into the ends of the spacer tube, said base being shaped in cross-section so as to define a crest projecting a short distance into the interior of the hollow spacer tube, said transversely disposed ridges being formed in said crest.

4,296,588


SEALING STATION OF VACUUM PACKAGING
MACHINESArtur Vetter, Wolfertschwenden, Fed. Rep. of Germany, as-
signor to Multivac Sepp Haggenmuller KG, Fed. Rep. of
Germany

Filed Sep. 26, 1979, Ser. No. 79,043

Claims priority, application Fed. Rep. of Germany, Oct. 7,
1978, 2843894Int. Cl.³ B65B 31/02

U.S. Cl. 53-86

18 Claims



1. A vacuum packaging machine for producing sealed vacuum packages having an evacuating and sealing station comprising first and second station portions, a heatable sealing member in said first station portion, means for cooling a por-


tion of said first station portion, a backing member in said second station portion, said sealing member and backing member being movable toward and away from each other, means for moving the sealing member and backing member toward and away from each other, an evacuating chamber defined by said first and second station portions, said evacuating chamber being connected with evacuating means through suction opening means and deflector means to deflect, in operation, a fluid stream sucked off from said evacuation chamber under the action of said evacuation means away from said sealing means, said deflecting means being connected to said first station portion.

4,296,589

PACKAGING MACHINE WITH CAM-OPERATED
CUTTER AND CONTAINER SUPPORTS THEREFORGary L. Kruse, Spring Lake, Mich., assignor to Dake Corpora-
tion, Division of JSJ Corporation, Grand Haven, Mich.Continuation-in-part of Ser. No. 904,216, May 9, 1978, Pat. No.
4,196,561. This application Aug. 23, 1979, Ser. No. 69,100Int. Cl.³ B65B 7/28, 41/16

U.S. Cl. 53-300

14 Claims



1. A packaging machine for applying and securing a web of material to containers comprising:

conveyor means for supporting and conveying containers in one direction along a path, said conveyor means including a plurality of spaced container support members mounted thereon;

web applying and securing means for applying and securing a continuous web of material to the containers supported by said conveyor means; and

cutting means for separating said web of material intermediate said container support members; said cutting means including a rotatable cutter having two ends and at least three cutting edges equally spaced in fixed positions around the exterior thereof and extending across said conveyor means, support means for rotatably supporting said cutter transversely across and above said conveyor means, said support means including camming means at each of said two ends of said cutter for intermittently rotating said cutter in a circular path, said camming means being offset circumferentially from said cutting edges; said container support members each including at least two projecting means for engaging said camming means, at least one projecting means being aligned with one of said two camming means and at least the other projecting means aligned with the other of said two camming means whereby said cutter is intermittently rotated such that said cutting edges are rotated to a first position by said one projecting means engaging said one camming means and thereafter rotated through a second position between said container support members to sever said web of material therebetween by said other projecting means aligned with the other of said two camming means.

4,296,590

METHOD AND APPARATUS FOR CONVEYING
SIX-PACK CONTAINERS TO CARTON BLANKHeinz Focke, Verden, Fed. Rep. of Germany, assignor to Focke
& Co., Bremen, Fed. Rep. of Germany


Continuation of Ser. No. 955,827, Oct. 30, 1978, abandoned.

This application Nov. 14, 1980, Ser. No. 207,040

Claims priority, application Fed. Rep. of Germany, Nov. 11,
1977, 2750533Int. Cl.³ B65B 35/30

U.S. Cl. 53-531

16 Claims



1. An apparatus for forming and conveying packs of articles, particularly bottles and cans, to a packing container, comprising:

(a) a feed conveyor (15) for continuously supplying article packs (10) to an input end of a transport path of the apparatus in two distinct lines (13,14);

(b) means including a stopping device (38) and a beginning conveyor (19) disposed in the transport path following the feed conveyor for receiving the article packs, separating them into plural pack groups (18), and delivering the groups to an input end of an intermediate conveyor (20) disposed in the transport path following said means, said beginning conveyor (19) accelerating the groups (18) to the speed of said intermediate conveyor (20);

(c) an end conveyor (21) disposed in the transport path following the intermediate conveyor for receiving the pack groups therefrom and transporting them to a final stop position at a packing station, said end conveyor comprising:

(1) a movable slide member (31) disposed above the transport path,

(2) means for lowering the slide member,

(3) a pusher plate (32) depending downwardly from the slide member for engaging the rear ends of pack groups upon the lowering of the slide member,

(4) a counterstop (41) spaced from the pusher plate and depending downwardly from the slide member for engaging the front ends of pack groups,

(5) means for driving the slide member at a higher horizontal conveying speed than the intermediate conveyor to thereby accelerate pack groups engaged by the slide member away from those behind to provide sufficient handling time at the stop position before the next pack groups arrive, and

(d) a yieldable end stop (36) for determining the stopping position of the pack groups, said end stop being operable to move toward the approaching groups and then be driven back with the groups to said stopping position.

4,296,591


DAMPED APPARATUS FOR QUICK-STOPPING
ROTATING MEMBERSWayne B. Martenas, New Holland; Edward H. Priepke, Stevens,
and Robert A. Wagstaff, New Holland, all of Pa., assignors to
Sperry Corporation, New Holland, Pa.

Filed Oct. 1, 1980, Ser. No. 192,783

Int. Cl.³ A01D 75/18

U.S. Cl. 56-10.3

9 Claims



1. A damped apparatus for quick-stopping a rotating member comprising:

a reaction member supported adjacent said rotating member, said reaction member including a slide and a slide support, said slide movable relative to said support;

a stop carried by said slide, said stop movable relative to said slide between a first position, free of engagement with said rotating member, and a second position in engagement with said rotating member;

means connected for damping movement of said slide in response to said stop being in said second position; and means connected for moving said stop between said first and second positions.

4,296,592

AUGER FLOATATION LIMIT


Irwin D. McIlwain, Lancaster, Pa., assignor to Sperry Corpora-
tion, New Holland, Pa.

Filed Nov. 3, 1980, Ser. No. 203,084

Int. Cl.³ A01D 41/12

U.S. Cl. 56-14.4

6 Claims



1. In a crop harvesting header attachable to a mobile crop

harvesting machine to initiate the crop harvesting process, said header having a frame; opposing first and second side sheets supported by said frame, said side sheets being generally vertically inclined and positioned substantially parallel to the direction of travel of said crop harvesting machine; a floor member extending between said side sheets substantially perpendicular thereto, said floor member having a forward edge; a substantially vertical rear wall connected to said floor member rearwardly of said forward edge and extending between said side sheets generally transverse to said forward direction of travel; said rear wall having an opening therethrough for the passage of crop material to said crop harvesting machine; a crop cutting means supported by said frame adjacent said forward edge of said floor member for the severing of standing crop material; crop conveying means mounted on said frame for the movement of severed crop material rearwardly over said floor member; a crop consolidating auger mounted between said side sheets rearwardly of said crop cutting means and forwardly of said rear wall to consolidate severed crop material and discharge rearwardly through said opening in said rear wall towards said crop harvesting machine; an elongated support arm pivotally mounted on said frame adjacent each said side sheet, said auger being rotatably mounted to said support arm at a center of rotation spaced from said pivot such that said auger can generally vertically float relative to said floor member; limit means cooperable with each said support arm for limiting the amount of movement of said auger relative to said floor member; and drive means for operatively powering said cutting means, said conveying means and said auger, an improved limit means comprising:

- a first stop selectively movably affixed to the respective side sheet below said support arm to provide a lower limit for the movement of said auger;
- a second stop selectively movably affixed to said respective side sheet above said support arm to provide an upper limit for the movement of said auger;
- a vertical adjusting means for selectively moving said first stop in a generally vertical direction so as to position said lower limit of movement of said auger at a desired location relative to said floor member; and
- a strap mechanism interconnecting said first and second stops and including a locking means cooperable therewith to selectively lock said first and second stop in a selective position relative to said side sheet, said strap mechanism simultaneously providing equal movement of both said first and second stops such that the amount of rotational movement permitted to said auger does not vary when said vertical adjusting means is manipulated to change the lower limit of movement of said auger.

4,296,593

UNIVERSAL CROP DIVIDER MECHANISM

Bryant F. Webb, Ephrata; Stanley J. Makofka, New Holland; Emmett G. Webster, New Holland, and Edward A. Blakeslee, New Holland, all of Pa., assignors to Sperry - New Holland, New Holland, Pa.

Filed Jun. 9, 1980, Ser. No. 157,624


Int. Cl.³ A01D 45/02

U.S. Cl. 56—98

15 Claims

1. Crop divider mechanism for use with an agricultural harvesting and conditioning machine having on the forward end thereof a transverse crop knockdown bar spaced above a cutting head thereon, said divider comprising a pair of similar interchangeable left-hand and right-hand rod members bent substantially into trapezoidal shape with two relatively long and short sides parallel to each other and two intermediate sides sloping toward each other from the said long side toward the short side to provide dividing elements, pairs of bracket members respectively adapted to be attached to said knockdown bar adjacent opposite ends thereof and having bearings therein respectively pivotally receiving one of said intermediate sides of said dividing elements with the long sides of said elements facing each other in spaced relationship along said knockdown bar, similar positioning plates respectively fixed to

one of said brackets of each pair and having a first hole through which said one of said intermediate sides of said elements extends and two additional positioning holes spaced even distances from said first hole substantially along axes at ninety degrees to each other relative to said first hole, a second plate fixed to said one of said intermediate sides of said dividing elements adjacent said one of said brackets, and a positioning

4,296,594
FRUIT PICKER

Richard J. Faulconer, P.O. Box 164, Barstow, Calif. 92311


Continuation-in-part of Ser. No. 92,321, Nov. 8, 1979. This

application Jun. 3, 1980, Ser. No. 156,045

Int. Cl.³ A01D 46/24

U.S. Cl. 56—336

12 Claims



1. A fruit picker comprising

- an elongated tubular member having an inlet and an outlet at opposite ends thereof defining a bore therethrough, and a plurality of perforations in the wall surrounding said bore;
- a handle affixed to the exterior of said tubular member, and a lever mounted on said handle and spaced therefrom a distance such that said handle and said lever may be gripped in one hand and the lever squeezed toward the handle;
- a cover member mounted on said tubular member in overlying relation to said inlet and having an outwardly opening notch;
- at least one blade guard formed on one side of said notch;
- a knife comprising a shank and at least one blade confronting

said blade guard, and means mounting said knife on said cover member for reciprocal slidable movement of said knife in a plane normal to the axis of said tubular member along a line bisecting said notch;

force transmitting means linking said lever and said knife mounting means for moving said knife from a first position wherein said blade is spaced from said blade guard into a second position wherein said blade is received in said blade guard upon actuation of said lever; and

resilient means connecting said knife and said cover member for moving said knife from said second to said first position upon release of said lever.

4,296,595

APPARATUS FOR WRAPPING A COVER MATERIAL AROUND ROUND BALES

Elmo R. Meiners, Anchor, Ill., assignor to M & W Gear Company, Gibson City, Ill.

Division of Ser. No. 928,507, Jul. 27, 1978, Pat. No. 4,173,112.


This application Aug. 29, 1979, Ser. No. 70,621

The portion of the term of this patent subsequent to Nov. 6, 1996, has been disclaimed.

Int. Cl.³ A01D 39/00

U.S. Cl. 56—341

9 Claims



1. In a round baler of the type having a bale forming mechanism for transport over a field of cut material to gather and form the material into a round bale, the improvement of apparatus for applying a cover sheet over the round bale during the bale forming operation, said improvement comprising in combination:

- (a) a wrapping material roll storage member affixed to the baler forward of the bale forming mechanism, said roll storage member being oriented to position an end of a sheet of wrapping material on the roll member in the path of the cut material for wrapping the bale as the bale is being formed;
- (b) drive means for the storage member for removing the sheet of wrapping material from the roll member and directing the end of said sheet along the ground for gathering by the bale forming mechanism about the outside surface of the formed bale;
- (c) means forward of the bale forming mechanism for terminating flow of cut material to the bale forming mechanism; and
- (d) means for cutting the wrapping material intermediate the bale forming mechanism and the roll storage member whereby the sheet may be wrapped about the bale and cut to permit the end of the sheet to be held against the ground by the bale thereby providing means for holding a cut end of sheet material to a bale formed by the bale forming mechanism.

4,296,596

AUTOMATIC BALE EJECTION DRIVE

T. William Waldrop, New Holland, and Willis R. Campbell, Ephrata, both of Pa., assignors to Sperry Corporation, New Holland, Pa.

Division of Ser. No. 25,161, Mar. 29, 1979, Pat. No. 4,208,862.


This application Jan. 16, 1980, Ser. No. 112,600

The portion of the term of this patent subsequent to Jun. 24, 1997, has been disclaimed.

Int. Cl.³ A01D 39/00

U.S. Cl. 56—341

6 Claims



1. A method for forming crop material rolls from a windrow of preformed crop material in a large roll forming machine having a tailgate movable between an open and a closed position and a roll forming region defined generally by upper bale forming means and conveying means comprising the steps of:

- (a) moving the machine along and across the windrow of crop material;
- (b) picking the crop material up from the windrow and directing it into the roll forming region;
- (c) forming the crop material into a roll of crop material of predetermined length and predetermined diameter;
- (d) wrapping the bale with a binding material about its periphery upon the bales reaching the predetermined diameter;
- (e) raising the tailgate along a predetermined path of travel;
- (f) automatically disengaging the drive to the upper bale forming means as the tailgate is raised along the path of travel to stop the upper bale forming means movement in a first direction and then automatically reversing the movement to a second direction of travel of the upper bale forming means as the tailgate continues to be raised along the path of travel to cause the formed bale to be ejected from the roll forming region;
- (g) lowering the tailgate upon ejection of the bale;
- (h) automatically disengaging the drive to the upper bale forming means as the tailgate is lowered along the path of travel to stop the movement in the second direction of travel and then automatically reversing the movement to the first direction of travel; and
- (i) recommencing movement of the machine along and across the windrow of crop material.

4,296,597

COTTON YARN-LIKE TEXTURED COMPOSITE YARN AND A PROCESS FOR MANUFACTURING THE SAME

Masayuki Tani; Mitsuhiro Okui, and Mitsuo Matsumoto, all of Ibaraki, Japan, assignors to Teijin Limited, Osaka, Japan

Filed Feb. 6, 1980, Ser. No. 118,987

Claims priority, application Japan, Jul. 24, 1979, 54-93189


Int. Cl.³ D02G 3/36, 3/38

U.S. Cl. 57—205

15 Claims

1. A false twist textured composite yarn having the appearance and touch of a cotton yarn, said textured composite yarn comprising a core yarn and a sheath yarn composed of a plurality of filaments, said sheath yarn wrapping around the core yarn with a length difference ratio of at least 15%, wherein a part of said filaments of the sheath yarn wrap around the core

yarn with a successive alternate twist, while said part of filaments being substantially cohered and at least partially adhered to the core yarn by fusion of the core yarn at the boundary region where the component filaments of the sheath yarn and



the core yarn meet, and the remaining component filaments of the sheath yarn being individually separate from each other wrap around the core yarn and the coherent filaments while the remaining filaments are in a crimped state, so that a three-layer structure is formed.

4,296,598

APPARATUS FOR PROVIDING FALSE TWIST TO MOVING YARN

Jean-Louis Faure, 21, rue des Lilas, Mably - 42300 Roanne, France


Filed May 16, 1980, Ser. No. 150,642

Claims priority, application France, May 22, 1979, 79 13915

Int. Cl.³ D02G 1/06; D01H 7/92

U.S. Cl. 57-284

10 Claims



1. Apparatus for providing a false-twist by friction to a moving yarn, comprising
a first endless apron,
a second endless apron positioned at an angle with respect to said first apron, at least one strand of said second apron being in contact with a strand of said first apron, the moving yarn being directed to pass between said first strand and said second strand in the zone of contact to a downstream location,
a first set of rollers fitting said first apron, and
a second set of rollers of external diameter fitting said second apron to permit said second apron to pass inside said first apron,
whereby relative movement of said contacted strands of said first and second aprons impart false-twist to the yarn in the contact zone.

4,296,599

TURBINE COOLING AIR MODULATION APPARATUS

Arthur P. Adamson, Cincinnati, Ohio, assignor to General Electric Company, Cincinnati, Ohio

Filed Mar. 30, 1979, Ser. No. 25,300


Int. Cl.³ F02C 7/18

U.S. Cl. 60-39.23

13 Claims

1. An improved turbomachine cooling air delivery system of the type having a source of cooling air and an air delivery channel for fluidly connecting the air delivery system to machine components to be cooled, wherein the improvement

comprises a plurality of valves disposed in mutually parallel relationship in the air delivery channel and means for automatically operating each of said valves individually in response to



predetermined conditions of said cooling air for thereby selectively varying the amount of cooling airflow in said air delivery channel.

4,296,600

FUEL CONTROL DEVICE FOR A GAS TURBINE

Toshimi Abo, and Hidetoshi Kanegae, both of Yokohama, Japan, assignors to Nissan Motor Company, Limited, Kanagawa, Japan


Filed Jan. 30, 1980, Ser. No. 116,866

Claims priority, application Japan, Feb. 6, 1979, 54-12615

Int. Cl.³ F02C 9/32

U.S. Cl. 60-39.28 R

6 Claims



1. A fuel control device for a gas turbine, comprising:
(a) sensing means for sensing the load on the turbine to output a first signal representative of the rate of change thereof;
(b) increase means responsive to the first signal for temporarily increasing the amount of fuel supplied to the turbine when the rate of increase of the load with time is higher than a reference value;
(c) decrease means responsive to the first signal for temporarily decreasing the amount of fuel supplied to the turbine when the rate of decrease of the load with time is higher than a certain predetermined value; and
(d) reducing means for reducing the amount of increase of fuel supplied by the increase means during a certain predetermined time interval after the end of functioning of the decrease means.

4,296,601

ELECTRONIC FUEL CONTROL SYSTEM

Anthony N. Martin, Simsbury, Conn., assignor to Otis Elevator Company, Hartford, Conn.

Filed Aug. 23, 1979, Ser. No. 69,142

Int. Cl.³ F02C 9/42

U.S. Cl. 60-224

7 Claims

1. A fuel control system for gas turbine engines, comprising:
a hydromechanical fuel section for providing fuel flow to the engine at commanded power settings and including
means for augmenting said fuel flow in response to a fuel flow modifying signal, and
signal processing means for providing said fuel flow modify-

4,296,603

TEMPERATURE RESPONSIVE PISTON AND CYLINDER UNIT HAVING A HEATER CARRIED THEREBY

Siegfried E. Manecke, and Thomas M. Buckshaw, both of Indiana, Pa., assignors to Robertshaw Controls Company, Richmond, Va.


Division of Ser. No. 856,404, Dec. 1, 1977, Pat. No. 4,206,780.

This application Jan. 28, 1980, Ser. No. 116,318


Int. Cl.³ F03G 7/06

U.S. Cl. 60-528

9 Claims



ing signal in response to signals applied thereto, said signals reflecting power setting, engine speed and ambient and engine conditions,
characterized in that said processing means comprises means for providing a correction signal which is summed with an engine speed signal, said correction signal being selected from a plurality of signals each reflecting a maximum



1. In a temperature responsive piston and cylinder unit wherein the piston thereof is extended relative to the cylinder thereof when the unit is heated and said piston is adapted to be retracted into said cylinder when the unit is cooled, an annular electrical heater means being carried in substantially a concentric manner on said cylinder of said unit for heating said unit to extend said piston thereof when said heater means is activated, the improvement wherein said heater means comprises a pair of telescoping annular electrical insulating members telescoped on said cylinder of said unit, and an electrical heater member disposed between said insulating members to be energized by having an electrical current passed therethrough.

4,296,602

APPARATUS FOR EXTRACTING ENERGY FROM WATER WAVES


Marwood J. Hales, Box 116, Redmond, Utah 84652, and Cameron L. Thorpe, Axtell, Utah 84621

Filed Jan. 10, 1980, Ser. No. 110,932

Int. Cl.³ F03B 13/12

U.S. Cl. 60-398

11 Claims



1. Apparatus for extracting energy from water waves, comprising an elongate water-wheel; foundation means rotatably mounting the water wheel and anchoring it to the bottom of a body of water in which waves are produced, so that at least a portion of the wheel is above the surface of said body of water; a ramp extending substantially the length of the wheel, shielding the wave side of the wheel from the wave impact, and directing water of the wave upwardly over the top of the wheel to impact said water wheel on the side thereof removed from the wave and to effect rotation thereof; and means for extracting energy from the rotation of the wheel.

4,296,604

TANDEM MASTER CYLINDER

Jiro Kizaki, and Takashi Fujii, both of Toyota, Japan, assignors to Aisin Seiki Kabushiki Kaisha, Kariya and Toyota Jidosha Kogyo Kabushiki Kaisha, Toyota, both of Japan


Continuation of Ser. No. 966,596, Dec. 5, 1978, abandoned. This application Oct. 6, 1980, Ser. No. 194,620

Claims priority, application Japan, Dec. 5, 1977, 52-163754

Int. Cl.³ B60T 11/20

U.S. Cl. 60-562

2 Claims



1. A tandem master cylinder comprising:
a. a body having an axial bore therein;
b. a first plunger sealingly and slidably fitted within said axial bore;
c. a second plunger sealingly and slidably fitted within the axial bore and being axially spaced from said first plunger for defining a first chamber between said first and second plungers, and being axially spaced from the end of said body remote from said first plunger for defining a second chamber between said body and said second plunger, said second plunger including a reduced diameter flange at its axial end proximate said first plunger and a protrusion extending from the central portion of said flange;

- d. first seal means for sealing said first chamber;
 e. second seal means for sealing said second chamber;
 f. an intermediate member disposed between and movable with respect to said first and second plungers for defining the distance between said plungers, said member including a stick-shaped stem having a head portion secured to one end thereof in slidable engagement with an axial hole in said first plunger and having a hat-shaped head secured to the other end thereof movably abutting said flange and including a centrally located recess complementary to and movably seated over said protrusion on said second plunger, the outer diameter of said hat-shaped head and said flange being substantially equal and being less than the inner diameter of said axial bore for providing an annular gap between said intermediate member and the inner wall of said axial bore and the inner dimensions of said recess restricting radial movement of said hat-shaped head to maintain the gap between the axial bore and the intermediate member;
 g. a sleeve-shaped retainer secured to the end of said first plunger opposite said second plunger for retaining said head portion of said intermediate member in said axial hole;
 h. a first return spring interposed between said retainer and a seat portion of said hat-shaped head for urging said first and second plungers apart;
 i. a second return spring having a setting load smaller than said first return spring disposed in said second chamber for urging said second plunger towards said first plunger;
 j. a first compensating port for fluid communication with said first chamber being opened and closed by said first seal means during axial movement of said first plunger; and
 k. a second compensating port for fluid communication with said second chamber being opened and closed by said second seal means during axial movement of said second plunger.

4,296,605

COMPRESSION RELIEF RETARDERS FOR SUPERCHARGED INTERNAL COMBUSTION ENGINES


Robert B. Price, Manchester, Conn., assignor to The Jacobs Manufacturing Company, Bloomfield, Conn.

Filed Feb. 11, 1980, Ser. No. 120,557

Int. Cl.³ F02B 37/00

U.S. Cl. 60—599

20 Claims



1. In an engine braking system of the gas compression relief type including an internal combustion engine having inlet and exhaust manifolds, an exhaust gas driven supercharger communicating with said inlet and exhaust manifolds respectively through inlet and exhaust ducts, an air-to-air intercooler communicating with said inlet duct and driven by a turbofan powered by air extracted from said inlet duct through a by-pass duct, engine exhaust valve means, engine exhaust valve opening means to open said engine exhaust valve means near the end of the compression stroke of said engine and electrical circuit means to control said engine exhaust valve opening means, the improvement comprising normally open control valve means located in said by-pass duct and solenoid means

mechanically interconnected with said control valve means and electrically interconnected with said electrical circuit means whereby actuation of said electrical circuit means excites said solenoid means and moves said normally open control valve to a closed position to inhibit the flow of air through said by-pass duct.

4,296,606

POROUS LAMINATED MATERIAL


Samuel B. Reider, Indianapolis, Ind., assignor to General Motors Corporation, Detroit, Mich.

Filed Oct. 17, 1979, Ser. No. 85,818

Int. Cl.³ F02C 7/18

U.S. Cl. 60—754

3 Claims



1. A porous laminated metal fabrication for a high temperature gas turbine engine component comprising first and second walls each having plural lamina with a free edge portion thereon, each of said first and second walls having a first lamina with a surface having a first preformed hole pattern therein, each of said first and second walls including a second lamina bonded to said first lamina, said second lamina having a surface with a second preformed hole pattern therein to form a tortuous air flow path through said first and second walls for cooling the metal therein, said wall holes directing coolant flow to form an air barrier on one of the lamina surfaces, each of said lamina having a solid metal section formed therein between said holes and said edge portions to define a weldable region of uniform metal density throughout a predetermined width between said first and second walls, a weld in said weldable region connecting said edge portions and having a width limited to the width of said region of uniform metal density whereby air flow through the first and second walls is free to flow through the full extent of all the preformed hole patterns in said lamina thereby to maintain full coolant flow there-through during gas turbine engine operation.

4,296,607

CRYOGENIC CERAMIC AND APPARATUS

William N. Lawless, Westerville, Ohio, assignor to Corning Glass Works, Corning, N.Y.

Division of Ser. No. 29,554, Apr. 13, 1979, Pat. No. 4,231,231.

This application May 19, 1980, Ser. No. 150,810


Int. Cl.³ C04B 35/00; F25B 9/00; F28D 17/00

U.S. Cl. 62—6

18 Claims

1. Sintered ceramic material:
 (a) characterized by
 (1) being a dielectric insulator and
 (2) having values of specific heat at selected temperatures below 15° K. that are greater than or at least equal to the values of specific heat of pure Pb at those same temperatures, and
 (b) consisting essentially of a crystalline phase with a composition defined by the molar formula ANb_2O_6 wherein A is selected from one or both of Mn and Ni ions.
 8. In cryogenic refrigeration apparatus comprising a load to be refrigerated, a refrigerant adapted to refrigerate the load at temperatures below 15° K., thermal energy absorbing elements associated with the refrigerant and adapted to function at temperatures below 15° K., wherein the improvement comprises at least one of the thermal energy absorbing elements being composed of sintered ceramic material:

- (a) characterized by
 (1) being a dielectric insulator and
 (2) having values of specific heat at selected temperatures below 15° K. that are greater than or at least equal to the values of specific heat of pure Pb at those same temperatures, and
 (b) consisting essentially of a crystalline phase with



a composition defined by the molar formula AB_2O_6 wherein A is selected from one or both of Mn and Ni ions alone or in combination with one or more of other divalent metal ions where at least about 90 mole % of A is ion or ions of Mn and Ni, and B is selected from one or both of Nb and Ta ions.

4,296,608

CRYOGENIC CERAMIC AND APPARATUS

William N. Lawless, Westerville, Ohio, assignor to Corning Glass Works, Corning, N.Y.


Division of Ser. No. 29,554, Apr. 13, 1979, Pat. No. 4,231,231.

This application May 22, 1980, Ser. No. 152,404

Int. Cl.³ C04B 35/00; F25B 9/00; F28D 17/00

U.S. Cl. 62—6

19 Claims



1. Sintered ceramic material:
 (a) characterized by
 (1) being a dielectric insulator and
 (2) having values of specific heat at selected temperatures below 15° K. that are greater than or at least equal to the values of specific heat of pure Pb at those same temperatures, and

- (b) consisting essentially of a crystalline phase with a composition defined by the molar formula A_2BCO_6 wherein A is selected from Pb ion alone or in combination with one or more of other divalent metal ions where at least about 90 mole % of A is Pb ion, B is Gd ion alone or in combination with one or more of other trivalent metal ions where at least about 90 mole % of B is Gd ion, and C is selected from one or both of Nb and Ta ions.

8. In cryogenic refrigeration apparatus comprising a load to be refrigerated, a refrigerant adapted to refrigerate the load at temperatures below 15° K., thermal energy absorbing elements associated with the refrigerant and adapted to function at temperatures below 15° K.,

wherein the improvement comprises at least one of the thermal energy absorbing elements being composed of sintered ceramic material:

- (a) characterized by
 (1) being a dielectric insulator and
 (2) having values of specific heat at selected temperatures below 15° K. that are greater than or at least equal to the values of specific heat of pure Pb at those same temperatures, and
 (b) consisting essentially of a crystalline phase with a composition defined by the molar formula A_2BCO_6 wherein A is selected from Pb ion alone or in combination with one or more of other divalent metal ions where at least about 90 mole % of A is Pb ion, B is either Gd ion or Mn ion alone or in combination with one or more of other trivalent metal ions where at least about 90 mole % of B is Gd ion or Mn ion, and C is selected from one or both of Nb and Ta ions.

4,296,609

³He-⁴He REFRIGERATOR

Adrianus P. Severijns, and Frans A. Staas, both of Eindhoven, Netherlands, assignors to U.S. Philips Corporation, New York, N.Y.


Filed Mar. 19, 1980, Ser. No. 132,468

Claims priority, application Netherlands, Mar. 29, 1979, 7902438

Int. Cl.³ F25B 19/00

U.S. Cl. 62—514 R

3 Claims



1. A ³He-⁴He refrigerator which comprises a mixing chamber for mixing liquid concentrated ³He and superfluid ⁴He; a segregating chamber accommodated at a lower level than the mixing chamber for separating a diluted ³He phase and a concentrated ³He phase; a connection duct between the mixing chamber and the upper part of the segregating chamber; and a thermomechanical pumping device based on the fountain pump effect for circulating superfluid ⁴He including a first superleak communicating with the lower part of the segregat-

ing chamber for withdrawing superfluid ^4He from the segregating chamber and a second superleak opening into the mixing chamber for injecting superfluid ^4He into the mixing chamber, said thermomechanical pumping device being constituted by a plurality of series-arranged fountain pumps.

4,296,610

LIQUID CRYOGEN DELIVERY SYSTEM


Robert B. Davis, Nyack, N.Y., assignor to Union Carbide Corporation, New York, N.Y.

Filed Apr. 17, 1980, Ser. No. 140,988

Int. Cl.³ F37C 7/02

U.S. Cl. 62—55

7 Claims



1. Apparatus capable of delivering small controlled quantities of a liquid cryogen to a use point in an intermittent manner comprising an on-period during which a predetermined amount of liquid cryogen is delivered to said use point continuously during said on-period, followed by an off-period during which no liquid cryogen is desired at said use point, said apparatus comprising in combination:

- (a) insulated conduit means for transferring cryogen from a liquid cryogen supply source to said use point;
- (b) subcooling means adjacent said use point and upstream thereof, adapted to condense vaporized cryogen in said conduit means and to subcool said cryogen; and
- (c) flow control means located downstream of said subcooling means, adapted to cause a low flow of cryogen downstream of said subcooling means during said off-period, said low flow being sufficient upon vaporization to offset heat leaks in, as well as purge cryogen vapor from, said conduit means downstream of said subcooler, said flow control means also being adapted to cause a high flow of said cryogen during said on-period so that said predetermined amount of liquid cryogen is delivered to said use point essentially free of vapor.

4,296,611

HOUSEHOLD REFRIGERATOR AIR FLOW CONTROL AND METHOD

James R. Griffin, and Raymond M. Schreck, both of Louisville, Ky., assignors to General Electric Company, Louisville, Ky. Division of Ser. No. 967,743, Dec. 8, 1978, Pat. No. 4,229,945.

This application Mar. 24, 1980, Ser. No. 133,209

Int. Cl.³ F25D 17/06

U.S. Cl. 62—89


7 Claims

1. The method of controlling the temperature in a refrigerator having a freezer compartment and a fresh food compartment separated by a partition comprising:

- (a) flowing a stream of cold air into the fresh food compartment;
- (b) locating a temperature sensing element at the top of the fresh food compartment;
- (c) shielding the temperature sensing element from the

stream of cold air being directed into the fresh food compartment;

- (d) controlling the temperature in both the freezer and fresh food compartments without significantly changing the constant ratio of those respective compartment temperatures by utilizing the temperature sensing element;



- (e) dividing the stream of cold air entering the fresh food compartment into two streams, one going to the top of the fresh food compartment, and the other going to the bottom of the fresh food compartment; and
- (f) controlling in equal ratio the amount of air flowing in the two streams to thereby change the ratio of the temperatures in the freezer and fresh food compartments.

4,296,612

FREEZE EXCHANGER WITH REMOVABLE TUBE LINER


Vincent F. Allo, Warrenville, Ill., assignor to Chicago Bridge & Iron Company, Oak Brook, Ill.

Filed Jun. 18, 1980, Ser. No. 160,667

Int. Cl.³ B01D 9/04

U.S. Cl. 62—123

8 Claims



1. A freeze exchanger comprising:
- at least one freeze tube secured in, and penetrating, first and second spaced-apart tube sheets;
 - a cover beyond the first tube sheet;
 - a shell around the tube sheets and connected thereto, with said cover supported by the shell;
 - a removable tubular liner, in the freeze tube, of smaller outside diameter than the inside diameter of the freeze tube thereby defining an annulus between the two tubes; means to deliver a liquid feed stream into a feed box space between the first tube sheet and the cover; and
 - means to deliver a cooling fluid around the freeze tube inside

of the shell between the first and second tube sheets and means to remove cooling fluid therefrom.

4,296,613

ABSORPTION REFRIGERATOR

Nicholas Eber, CH-1830 Untereggstrassen, Switzerland


Filed Oct. 9, 1979, Ser. No. 82,929

Claims priority, application Switzerland, Oct. 18, 1978, 10763/78

Int. Cl.³ F25B 39/02; F25F 1/30

U.S. Cl. 62—515

14 Claims



1. An absorption refrigerator comprising a heat-insulated box having a wall and a layer of insulation therein; an absorption refrigeration unit having an evaporator tube for passage of a refrigerant therethrough; and at least one finned body having a base plate mounted on said wall and defining a convexly curved section receiving said evaporator tube in heat-conductive relation and a plurality of vertically disposed cooling fins mounted on said plate in heat-conductive relation therewith and in spaced vertical relation to said curved section to define a gap, said curved section and said fins being directed towards the interior of said box.

4,296,614

LEATHER PRESS

Robert K. Valks, Wetherby, England, assignor to USM Corporation, Farmington, Conn.


Continuation-in-part of Ser. No. 895,740, Apr. 13, 1978. This application Aug. 17, 1978, Ser. No. 934,602

Claims priority, application United Kingdom, Aug. 27, 1977, 36086/77

Int. Cl.³ C14B 1/30

U.S. Cl. 69—48

2 Claims



1. A machine for effecting a pressing operation on an article, said machine comprising:
- a first platen and a second platen mounted in a frame of said machine;
 - a first closing means for urging movement of the first and

second platens relative to one another, said article being disposed therebetween;

a second closing means for applying final predetermined pressure on said article disposed between said first and second platens;

said second closing means comprising at least two pressurizable members arranged with one of said platens, each of said pressurizable members includes a pancake ram slidably disposed in a pancake cylinder in a cylinder plate disposed on a support plate, said pancake rams occupying a substantial surface portion of said platen, with a periphery having a step-like configuration thereon; and

said pancake rams also have a sealing member arranged along its step-like periphery to ensure a sealing fit between said rams and said cylinders, said pancake rams being of elongated shape to permit said rams to extend generally into the corners of said platens.

4,296,615

ANTI-THEFT ARRANGEMENT, PARTICULARLY FOR A MAST OF A SAILING CRAFT

Reinhold Zoor, Dachau, Fed. Rep. of Germany, assignor to Heinrich Wunder KG, Dachau, Fed. Rep. of Germany


Filed Jul. 31, 1979, Ser. No. 62,295

Claims priority, application Fed. Rep. of Germany, Aug. 4, 1978, 2834338

Int. Cl.³ E05B 73/00

U.S. Cl. 70—19

16 Claims



1. An arrangement for preventing unauthorized removal of a rod-shaped object, particularly a mast of a sailing or similar craft, from a support, comprising an annular attachment in the form of a sleeve consisting of a rigid material and configured to substantially fittingly embrace a region of the object when in operative position; at least one screw meshing with and penetrating into the interior of said sleeve for clampingly engaging said region of the object; means for locking said screw, at least in said operative position of said attachment; and means for confining said attachment to a particular area of the support.

4,296,616

ADAPTOR FOR PLUNGER LOCK OPERATING TOOL


Richard S. Guiler, Stewartville, N.J., assignor to E. J. Brooks Company, Newark, N.J.

Filed Sep. 14, 1979, Ser. No. 75,849

Int. Cl.³ E05B 67/36

U.S. Cl. 70—34

6 Claims



1. An adaptor tool for temporary assembly onto a plunger lock unlocking tool of a type having forwardly projecting

members which operate to grasp the external surface of the unlocking pin of a plunger lock and pull the pin to the unlocking position, said adaptor tool enabling the unlocking tool to be used to unlock a plunger lock of the type in which the unlocking member is a hollow tube, and comprising a hollow housing having means at the rear end for engaging the front end of the unlocking tool so that the forwardly projecting members extend into the housing, operating means in said housing having a portion positioned for engagement by said members when the tool is operated, said means being spring biased toward the front end of the housing and being movable toward the rear end by the operation of said tool, expandable mechanism projecting from the forward end of the housing for insertion into the hollow unlocking pin of a plunger lock, and means responsive to the movement of said means toward the rear of the housing to cause the expansion of said expandable mechanism and retraction thereof toward the housing.

4,296,617

LOCKABLE KEY HOLDING RECEPTACLE


Barry A. Campagna, Oak Park, Mich., assignor to Teledyne Industries, Inc., Los Angeles, Calif.

Filed Dec. 10, 1979, Ser. No. 101,455

Int. Cl.³ E05B 65/52

U.S. Cl. 70—63

8 Claims



1. A receptacle for a key, said receptacle being attachable to a door or like structure having an interior surface and an exterior surface, said receptacle comprising:
an elongated housing having a length greater than the width of said door, said housing having a longitudinally extending cavity which is open through only one axial end of the housing, said housing being positioned through an aperture in said door so that the open end of said housing faces outwardly flush from the exterior surface of said door so that a portion of the housing protrudes radially inwardly from the interior surface of the door;
means for attaching said housing to the interior surface of said door;
a closure plug receivable within the open axial end of said housing; and
means for removably locking said plug to said housing wherein said cavity is circular in cross-sectional shape and has a circumferentially extending groove formed about its inner periphery at a position spaced from said open end of the housing, and wherein said means for locking said plug to said housing comprises a lock cylinder having a detent a portion of which enters said groove upon rotation of said lock cylinder.

4,296,618

LOCK AND KEY DEVICE

Francois Guiraud, Chambourcy, France, assignor to Fichet-Bauche, Velizy, France


Filed Dec. 29, 1978, Ser. No. 974,557

Claims priority, application France, Dec. 30, 1977, 77 39747

Int. Cl.³ E05B 19/02, 29/02

U.S. Cl. 70—358

3 Claims



1. A lock and key device, with the key comprising two pairs of slotted wings and the lock comprising a fixed hollow shaft with a rear traverse wall having a notching for the passage of the key, inside the fixed hollow shaft a rotary barrel with a rear partition provided with a conjugate slot of the key profile and interposed between the rotary barrel and the fixed hollow shaft coupling means which can only be rotated when the key has reached a driven-in position which is predetermined by a stop, a housing in back of the rear partition of the rotary barrel provided by extensions thereon, a cylindrical ring complementary to said housing extensions through external ears, a passage in said cylindrical ring of the key profile and having an internal slot with the same width as the wings; said key having, in addition to the slotted wings, on a connecting portion between the wings of one pair and a body of the key a projecting part with the same conjugate shape as said internal slot of the cylindrical ring so that when the key, after being driven into place, is under load stress to make a rotative motion, it will rotate the assembly made up of the ring and the rotary barrel through cooperation of one lateral face of its projecting part with a face opposite the slot, and the other face of the projecting part cooperating, through sliding during the rotative motion, with the front face of said rear traverse wall of the fixed hollow shaft so as to prevent the key from being withdrawn as long as it has not made a complete turn.

4,296,619

ANCHORING MEANS FOR DOOR LOCK PLATES

Bo G. Widen, Torshälla, Sweden, assignor to GKN-Stenman AB, Eskilstuna, Sweden

Filed Dec. 20, 1979, Ser. No. 105,490

Claims priority, application Sweden, Dec. 29, 1978, 7813472


Int. Cl.³ E05B 9/08

U.S. Cl. 70—451

9 Claims

1. An anchoring arrangement for a door plate of a lock, said plate being secured to a door or the like by means of at least one upper and one lower securing means, said door accommodating a lock housing secured in a recess formed in a side edge of the door adjacent said plate and covered by a lock pillar, said securing means each cooperating with an anchoring element inserted from the pillar side of the door, said securing means including a rotatable part which is locked against rota-

tion by the anchoring element inserted from the lock-pillar side of the door, each of said anchoring elements comprising a



screw, and wherein said screws also secure the lock pillar to the side edge of the door.

4,296,620

SMOOTHING ROLLING MILL

Siegfried Bagusche, Loevenich, Fed. Rep. of Germany, assignor to W. Hegenscheidt Gesellschaft mbH, Erkelenz, Fed. Rep. of Germany


Filed Sep. 24, 1979, Ser. No. 77,995

Claims priority, application Fed. Rep. of Germany, Oct. 16, 1978, 2844974

Int. Cl.³ B21D 19/00

U.S. Cl. 72—100

8 Claims



1. A smoothing rolling mill apparatus for smoothing roller action on a work piece mounted for rotation about a longitudinal central axis of the work piece, comprising a plurality of smoothing roller means, support means operatively supporting said roller means relative to said work piece, said roller means being distributed unevenly around the longitudinal central axis of said work piece, said support means holding said roller means in spaced positions such that a relative axial offset or displacement Kz is established between the facing ends of said roller means, and wherein said relative axial displacement Kz satisfies at least approximately the following equation:

$$Kz = s \left(1 - \frac{\alpha z \cdot n}{360} \right)$$

wherein s is the feed advance produced by each roller means for each rotation of the work piece, n is the number of roller means distributed about the work piece, and wherein

αz is the angle enclosed by the two lines extending radially through said longitudinal central axis of said work piece and radially through the rotational axis of the respective roller means of two neighboring roller means whereby the full feed advance capacity of each said roller means is cumulatively effective.

4,296,621

MACHINES FOR FORMING COILED SPRINGS

Yozo Ohdoi, and Yasuyuki Takahata, both of Kasugai, Japan, assignors to Asahi-Seiki Manufacturing Co., Ltd., Owariasahi, Japan


Filed Dec. 4, 1979, Ser. No. 100,246

Claims priority, application Japan, Feb. 28, 1979, 54/23921

Int. Cl.³ B21F 35/02, 11/00, 3/027

U.S. Cl. 72—130

9 Claims



1. A machine for forming coil springs of the type having a coiled body portion and first and second end loops at opposed ends of said body portion comprising:

a wire guide member having a void in one side thereof for receiving a coiled body portion and a wire guide groove therethrough, said wire guide groove permitting a wire to be fed therethrough;
a first tool member having a tapered free end, said first tool members being mounted for movement from a retracted position to an advanced position in which said tapered free end is effective to contact said wire fed through said guide groove for bending and coiling thereof at a first position adjacent an outlet orifice of said guide groove;
a second tool member;
a complementary tool member;
said second and complementary tool members being mounted for movement into gripping abutment with said wire at said first position;
a third tool member for contacting and bending said wire through a large angle while it is gripped at said first position by said second and complementary tool members at a first end of said body adjacent said first position where said wire is gripped;
first holding means operative to grip said body at a first portion thereof;
second holding means operative to grip said body at a second portion thereof; and
bending means for forming a large angle bend at a second end of said body adjacent a second position where said body is gripped by one of said first and second holding means.

4,296,622

DEVICE FOR INSERTING AND THRUSTING A BAR INTO A PRESS PIERCING MILL

Aurindo Nessi, Albate (Como), Italy, assignor to Innocenti Santestacchio S.p.A., Brescia, Italy

Filed Apr. 11, 1979, Ser. No. 29,072

Claims priority, application Italy, Apr. 21, 1978, 22600 A/78

Int. Cl.³ B21B 17/00, 19/04

U.S. Cl. 72—208


6 Claims

1. A device for inserting and thrusting a bar into a press piercing mill including a rolling machine having a pair of rolls, a piercing bit mounted along the rolling axis (A) of the machine and on the outlet side thereof, an inlet guide for the rolling machine and a bedplate holding the bar and extending along the rolling axis (A) from the inlet side of the guide, such device comprising:

a motor driven shaft rotatably borne by the inlet guide and having its axis of rotation parallel to the rolling axis (A); a substantially drum-shaped bedplate coaxially keyed to the said motor-driven shaft;

a first thrust means mounted on the said drum-shaped bedplate and acting in a line (R) parallel to the axis of rotation of the said motor-driven shaft and separated therefrom by a distance equal to the distance between the axis of rotation and the rolling axis (A), the first thrust means being adapted to subject a bar to a thrust having a given value in order to roll and simultaneously pierce the bar;

a second thrust means mounted on the said bedplate and acting in a line (R₁) parallel to the line of action (R) of the first thrust means and circumferentially spaced therefrom by a center angle (α) of predetermined value, the line of



action (R₁) being also at a distance from the axis of rotation of the said motor-driven shaft equal to the distance between the axis of rotation and the rolling axis (A), the second thrust means being adapted to subject said bar to a thrust for inserting it into the rolling machine through the inlet guide thereof; and

a motor for angularly moving the motor-driven shaft around its axis of rotation from a position in which the line of action (R) of the said first thrust means coincides with the rolling axis (A) and the line of action (R₁) of the said second thrust means is at an angular distance from the rolling axis (A) to a second position in which the line of action (R₁) of the said second thrust means coincides with the rolling axis (A) and the line of action (R) of the first thrust means is at an angular distance therefrom.

4,296,623


SEMI-CONTINUOUS HOT ROLLING OF METAL STRIP AND PLATES

Werner W. Eibe, McCandless Township, Allegheny County, Pa., assignor to Blaw-Knox Foundry & Mill Machinery, Inc., Pittsburgh, Pa.

Filed Sep. 12, 1979, Ser. No. 74,876
Int. Cl.³ B21B 1/34; B21C 47/00

U.S. Cl. 72-227

30 Claims



1. Apparatus for hot rolling metal workpieces into strip or plate without reheating comprising a mill table, a heating furnace adjacent the mill table positioned to discharge heated workpieces thereon, a roughing stand following the mill table, collecting means at the other end of the roughing stand from the mill table for accumulating the rolled product of the roughing stand, a finishing stand spaced both laterally and longitudi-

nally from the roughing stand, delivery means preceding the entry end of the finishing stand laterally adjacent the collecting means, but at a different elevation therefrom, whereby both stands can be driven by separate motors on the same side of the stand, the delivery means feeding the rolled product of the roughing stand into the finishing stand, and means for transferring the rolled product of the roughing stand while it is hot from the collecting means to the delivery means, and a run out table following the finishing stand and extending in a direction different from the path of travel of workpieces leaving the delivery means in front of the discharge end of the heating furnace.

19. An upcoiler and uncoiler for hot rolled strip comprising a cylindrical housing in scroll form split on a vertical plane into a larger and a smaller element, means pivoting each element of the housing about a fixed pivot at its lower edge, those lower edges being spaced vertically from each other so as to form the upper and lower edges of an entry into the housing at the bottom thereof, an entry guide leading into the entry, and parallel driven coil-supporting rolls at the same elevation straddling the vertical plane and forming a continuation of the lower end of the smaller element.

4,296,624

ACCESSORY FOR AN APPARATUS FOR REPAIRING AND STRAIGHTENING


Gerald A. Specktor, 409 Cleveland Ave. South, St. Paul, Minn. 55105

Division of Ser. No. 722,825, Sep. 13, 1976, Pat. No. 4,138,877, which is a continuation of Ser. No. 550,378, Feb. 18, 1975, abandoned. This application Jan. 5, 1979, Ser. No. 1,082

Int. Cl.³ B21D 1/12, 1/14

U.S. Cl. 72-308

10 Claims



1. Accessory for an apparatus for repairing and straightening including a support surface for supporting a vehicle thereon comprising, in combination: a flexible pulling member including means at one end for attaching to the vehicle; down pull means for directing the flexible pulling member at an angle to the vehicle including substantially vertically of the vehicle; and means, for rotation about a vertical axis, for attaching the down pull means to the support surface vertically below the vehicle, for allowing rotational self-alignment of the down pull means about the vertical axis, and for allowing the down pull means to be substantially in line with the flexible pulling member when a repair force is applied to the other end of the flexible pulling member, wherein the down pull means comprises: a pulley, and means for removably, rotatably mounting the pulley, wherein the removably, rotatably mounting means comprises, in combination: a pin, and a first arm and a second arm upstanding from a center section, with the first and second arms having apertures formed therein for removably receiving the pin, and wherein the support surface has a top surface and a bottom surface defining a finite thickness and further includes at least one regularly shaped aperture passing vertically through the support surface and wherein the attaching, self-alignment, and allowing means comprises, in combination: attachment means having a cross sectional size substantially equal to but slightly less than the size of the aperture and having a removed portion of a thickness substantially equal to but slightly greater than the thickness of the support surface for allowing the attachment means to be vertically inserted

into the support surface aperture and moved in a first lateral direction parallel to the support surface to engage the support surface within the removed portion, with a lip being defined by the removed portion for abutting with the bottom surface of the support surface; means for preventing the attachment means from moving in a second lateral direction opposite to the first lateral direction and for preventing unintentional removal of the attachment means from the aperture; and means extending around the preventing means, located on the opposite side of the attachment means from the lip, for abutting with the top surface of the support surface.

4,296,625

CRANK PRESS WITH LATERAL ROD EJECTOR

Alois Weller, Erkrath, and Wolfgang Mai, Kaarst, both of Fed. Rep. of Germany, assignors to Kieserling & Albrecht, Solingen, Fed. Rep. of Germany


Filed Jun. 22, 1979, Ser. No. 51,235

Claims priority, application Fed. Rep. of Germany, Jun. 23, 1978, 2827561

Int. Cl.³ B21D 45/00

U.S. Cl. 72-345

3 Claims



1. In an improved crank press arrangement having a frame, a lateral ejector rod, and reciprocating sled movably mounted on said frame which is driven by a crank drive, wherein the ejector rod is slidably mounted in the sled and a positioning bush and coacts with a die, a toggle lever being pivotally mounted on said sled and having a first arm coacting with said ejector rod, and having a second arm on which a cam-follower roller is rotatably mounted, a control cam rotatably mounted and being in operative contact with said cam-follower roller, the improvement comprising that the contour and shape of the control cam, rotatably mounted in said frame, is such that while the cam-follower roller is in continuous contact therewith, nevertheless a temporary standstill of the ejector rod occurs relative to the frame during the operative cycles of the arrangement.

4,296,626

WHEEL ALIGNMENT APPARATUS

Davis R. Jarman, 610 Ward Dr., and Virgil H. Hinson, 206 Fairway Oaks, both of Brunswick, Ga. 31520

Filed Jun. 21, 1979, Ser. No. 50,528


Int. Cl.³ B21D 1/12

U.S. Cl. 72-392

11 Claims

1. An alignment apparatus for a motor vehicle front end system including body sheet metal supported upper suspension strut end anchor locations, a pair of adaptor assemblies, said adaptor assemblies including mounting means for removably anchoring to said anchor locations, an elongated adjustable length thrust member of the push and pull type, means pivotally attaching the opposite end portions of said thrust member to said adaptor assemblies, a stand anchorable to the supporting surface for said vehicle on one side of the latter, an elongated pull structure having one end anchored to an upper portion of said stand and the other end thereof anchored to the adjacent adaptor assembly of said vehicle, an intermediate

portion of said stand including a horizontally outwardly projecting adjustable length arm supported therefrom, the outer end of said arm including abutment structure for abutting and securement to an adjacent wheel hub of the associated vehicle, said stand being generally L-shaped in configuration including



a lower horizontal leg and an upper vertical leg whose lower end is anchored to one end of the lower leg and from an intermediate height portion of which said adjustable length arm is supported, the outer end of said lower horizontal leg including a turntable supported therefrom upon which a wheel supported from said wheel hub may rest.

4,296,627

METHOD AND DEVICE FOR MEASURING THE REQUIRED COOLING CAPACITY OF A COLD SPACE AND THE REFRIGERATION CAPACITY OF THE REFRIGERATING MACHINERY

Jyrö V. Lindström, Helsinki, Finland, assignor to Alnor Oy, Finland


Filed Dec. 28, 1979, Ser. No. 107,767

Claims priority, application Finland, Jan. 4, 1979, 790022

Int. Cl.³ G01K 17/00

U.S. Cl. 73-15 R

5 Claims



1. A method of determining the cooling capacity of a container comprising, cooling contents of the container to a first low temperature below an ambient temperature, permitting the contents of the container to rise to a second higher temperature below the ambient temperature during a first period, measuring the length of the first period, cooling the contents of the space again to the first low temperature during a second period, permitting the temperature to rise to the second higher temperature during a third period, heating the contents of the container during the third period by a known amount, and measuring the length of the third period to determine the thermal capacity of the container using the known amount of heating and the measured first and third periods.

4,296,628

SYSTEM FOR DETECTING PARTICLES CARRIED BY A FLUID FLOW

Harm Mast, Rijswijk, Netherlands, assignor to Shell Oil Company, Houston, Tex.


Filed Jun. 5, 1980, Ser. No. 156,847

Claims priority, application United Kingdom, Jun. 26, 1979, 22277/79

Int. Cl.³ G01N 15/07

U.S. Cl. 73—28

6 Claims



1. A system for detecting particles carried by a fluid flow, said system including:

- at least two metal bodies each cooperating with an acoustical transducer means adapted to detect acoustic energy in the relevant body and to generate electric signals representative of such energy, one of the bodies having at least part of the metal surface thereof covered with a layer of acoustic dampening material; and,
- means for subtracting one of the electric signals from the other signal and recording the resulting signal.

4,296,629

PISTON TOP-DEAD-CENTER DETECTOR


John M. Vuyovich, 1369 McDuff St., Los Angeles, Calif. 90026

Filed Dec. 17, 1979, Ser. No. 104,374

Int. Cl.³ G01M 15/00

U.S. Cl. 73—116

8 Claims



1. A piston top-dead-center detector comprising the combination of:

- an adapter assembly for making electrical contact with a piston in an internal combustion engine when the piston is in a top-dead-center position, the piston being at a given electrical potential and the adapter assembly comprising a first member adapted to be seated within a sparkplug hole in an internal combustion engine and a second member of electrically conductive material extending through and electrically insulated from the first member, the second member being capable of sliding within the first member and at the same time having a sufficiently snug fit within the first member so as to avoid sliding movement relative to the first member in the absence of the application of a substantial force to the second member;

an electrical terminal having a different potential from the given electrical potential; and
a lamp coupled between the adapter assembly and the electrical terminal.

4,296,630

APPARATUS FOR CAPACITIVE FILLING-LEVEL MEASURING, PARTICULARLY IN A MOTOR VEHICLE TANK

Wilhelm Jung, Giessen-Kleinlinden, and Karl Rau, Mühlheim, both of Fed. Rep. of Germany, assignors to VDO Adolf Schindling AG, Fed. Rep. of Germany


Filed Feb. 25, 1980, Ser. No. 124,116

Claims priority, application Fed. Rep. of Germany, Mar. 5, 1979, 2908449

Int. Cl.³ G01F 23/26

U.S. Cl. 73—304 C

11 Claims



1. For use with a container from which a medium is withdrawn through a suction passage to establish a variable level of the medium above a bottom of the container,

- and apparatus for measuring said level of the medium within the container having insulated electrodes immersed in said medium to form measuring and compensation capacitors, the capacitances of which are dependent on the dielectric constant of the medium, the improvement comprising insulating means within which said electrodes are disposed in non-conductive relation to the medium and having separate sections within which the electrodes respectively form the measuring and compensation capacitors, and support means mounting only one of the separate sections of the insulating means in constant operative relation to the medium within said suction passage and the other of the sections externally of the suction passage within the container.

4,296,631

LIQUID CRYSTAL COMPOSITIONS AND DEVICES

James L. Ferguson, Kent, Ohio, assignor to Becton, Dickinson and Company, Rutherford, N.J.

Filed Sep. 21, 1979, Ser. No. 77,612

Int. Cl.³ C09K 3/34; C01K 3/00, 11/16

U.S. Cl. 73—356


32 Claims

14. A process for inhibiting the growth of domains in the isotropic liquid state of a cholesteric-to-liquid crystal composition, which comprises: adjusting the viscosity of said liquid state composition to about 20 to 6500 poise while retaining the twisting power of the cholesteric liquid crystal composition to selectively scatter visible light below the cholesteric-to-liquid transition point.

16. An improved temperature recording device, which comprises:

- an opaque support member;
- a cholesteric liquid crystal composition disposed on said support member, said composition comprising a mixture of

- (a) an optically active liquid crystal compound characterized in part by an intrinsic left-handed helical structure and a liquid viscosity of between about 25 poise and 6500 poise; and
 - (b) a liquid crystal compound selected from those having an intrinsic right-handed helical structure, nematic liquid crystals and mixtures thereof;
- the proportions of (a) and (b) being such as to provide said composition with a cholesteric-to-liquid transition point, a twisting power such that the resulting composition will selectively scatter visible light below said liquid transition point, and will cease to scatter visible light above said



cholesteric-to-liquid transition point; and a liquid viscosity of from about 20 to 6500 poise at the liquid transition point temperature.

31. A temperature indicating cholesteric liquid crystal composition, which comprises: an optionally active liquid crystal composition characterized by an intrinsic helical structure such as to provide a clearing point for the composition within the range of from about 10° to about 70° C. and a twisting power whereby the composition will selectively scatter visible light at a temperature below the clearing point, said composition having a viscosity of from 20 to 6500 poise at the clearing point temperature.

4,296,632

TEMPERATURE-TO-FREQUENCY CONVERSION APPARATUS


Milton D. Bloomer, and William P. Kornumpf, both of Schenectady, N.Y., assignors to General Electric Company, Schenectady, N.Y.

Filed Feb. 14, 1980, Ser. No. 121,489

Int. Cl.³ G01K 7/16

U.S. Cl. 73—362 AR

27 Claims



1. In apparatus for converting the magnitude of a sensed parameter to the frequency of an output waveform, of the type having means providing an output waveform cyclically alternating, relative to a preselected potential of fixed magnitude, between first and second output voltage levels, responsive to a voltage at a single input respectively less than or equal to a first

reference potential and greater than or equal to a second reference potential, the improvement comprising:
a timing capacitance element connected between the single input and the preselected potential; and
network means connected between said output and said single input for providing an electrical conductance therebetween of magnitude substantially linearly related to the magnitude of the sensed parameter; the conductance of said network means causing said timing capacitance element to cyclically charge and discharge to said second and first reference potentials respectively to provide said output waveform substantially as a squarewave having a frequency established by said preselected timing capacitance and network conductance values and substantially linearly proportional to the conductance value of said network means.

4,296,633

DEVICE FOR TEMPERATURE MEASUREMENT

Hakan B. Hakansson; Lennart P. E. Persson, both of Lund, and Berth-Ove G. Wall, Bjäred, all of Sweden, assignors to Gambro AB, Sweden

PCT No. PCT/SE78/00012, § 371 Date Mar. 3, 1980, § 102(e)


Date Jun. 1, 1979, PCT Pub. No. WO80/00191, PCT Pub. Date Feb. 7, 1980

PCT Filed Jul. 3, 1978, Ser. No. 131,079

Int. Cl.³ G01K 7/22

U.S. Cl. 73—362 AR

21 Claims



1. A device for temperature measurement comprising a temperature-sensitive sensor (1), whose electrical properties, e.g. the resistance, vary with the temperature, e.g. a thermistor, and which is connected via two contacts (3, 4) to two electric conductors (9, 10) arranged on a support (7), characterized in that the two electric conductors (9, 10) are arranged on both sides of the support (7) which is in the form of an elongated strip and that the one conductor (9) extends directly or via a suitable extension (11) over one edge of the support (7) in the direction towards the other conductor (10) but without reaching as far as the same thus forming a gap, slit or the like (12) which is arranged so that it is bridged by the sensor (1) one contact (3, 4) of which is connected to each conductor (9, 10).

4,296,634

SEPTUM FOR USE IN GAS CHROMATOGRAPHY AND METHOD OF OPERATION

Robert H. Goodale, 7355 Yucca Ct., Boulder, Colo. 80301, and George M. DuJack, Jr., 391 Fourth St., Troy, N.Y. 12180

Filed Feb. 20, 1980, Ser. No. 122,916

Int. Cl.³ G01N 37/00


U.S. Cl. 73—864.86

16 Claims

1. A septum for use in gas chromatographic apparatus, the septum comprising,

- a septum member of an elastomeric material, and
- cooling means positioned internally of the septum member,

whereby the temperature of the septum may be maintained at a lowered level when exposed to column gases at



elevated temperatures while avoiding substantial cooling of such gases by the septum.

4,296,635

TRANSDUCER DEVICE FOR MEASURING THE INTERNAL PRESSURE IN PIPES


Peter Claassen; Helmut List, and Rudolf Zeiringer, all of Graz, Austria, assignors to Hans List, Graz, Austria

Filed Jun. 11, 1980, Ser. No. 158,515

Int. Cl.³ G01L 7/02

U.S. Cl. 73—730

10 Claims



1. A transducer device for measuring the internal pressure in pipes, comprising two housing parts and a connecting element, wherein said housing parts are articulately connected with one another by said connecting element and adapted to be fixedly mounted on the pipe by means of a clamping device, each of said housing parts contains at least one measuring element with a bipolar take-off of test signals, at least one pole of each take-off is electrically conductively connected with a part of said connecting element which is electrically insulated relative to the other pole, and the connecting element comprises connection terminals for the further conduction or transmission of the test signals, the said other pole being potentially in direct connection with the pipe.

4,296,636

NOISE-REDUCING ELECTRODES FOR ELECTROMAGNETIC FLOWMETER

Elmer D. Mannherz, Bucks County, Pa., assignor to Fischer & Porter Co., Warminster, Pa.

Filed May 22, 1980, Ser. No. 152,479

Int. Cl.³ G01F 1/58


U.S. Cl. 73—861.12

6 Claims

1. An electromagnetic flowmeter for measuring the flow rate of a slurry containing solid particles, said flowmeter comprising:

- A flow tube having a pair of electrodes mounted thereon at diametrically-opposed positions, said electrodes having a surface with a metallurgical hardness of at least Rockwell A85, whereby the impingement of said solid particles thereon does not result in the substantial generation of noise components; and
- An electromagnet having a coil which is excited by a low frequency wave derived from a standard a-c power line, the frequency of the wave being low relative to that of the

line to produce a transverse magnetic field within the tube which is intersected by the slurry, the voltage induced in



the slurry being transferred to said electrodes to provide a flow-induced signal relatively free of noise components.

4,296,637

METHOD AND APPARATUS FOR SAMPLING HOT HOMOGENEOUS MIXTURES


Narasimhan Calamur, and Morris R. Schoenberg, both of Naperville, Ill., assignors to Standard Oil Company (Indiana), Chicago, Ill.

Filed Mar. 28, 1980, Ser. No. 134,879

Int. Cl.³ G01N 1/22; H05B 3/06

U.S. Cl. 73—863.11

9 Claims



7. A method for sampling hot homogeneous mixtures which form multiple phases at a temperature above ambient temperature which comprises:

- heating a sample vessel and attached inlet and outlet means and valve means to a temperature above the dew point of said homogeneous mixture;
- purging said sample vessel and said inlet and outlet means and valve means with an inert gas;
- collecting a portion of said hot homogeneous mixture in said sample vessel;
- sealing said sample vessel with said valve means; and
- maintaining the temperature of said mixture above the dew point of said mixture.

4,296,638

SAMPLING MOLTEN METAL

Gustav Kolb, Im Ohl 52, 5870 Hemer, Fed. Rep. of Germany, assignor to Mannesmann Aktiengesellschaft, Duesseldorf and Gustav Kolb, Hemer, both of, Fed. Rep. of Germany


Filed Nov. 9, 1979, Ser. No. 92,849

Claims priority, application Fed. Rep. of Germany, Nov. 11, 1978, 2849333

Int. Cl.³ G01N 1/12

U.S. Cl. 73—863.21

6 Claims



1. Apparatus for sampling molten metal, e.g., steel, and including a body which contains a plurality of chambers, comprising:

- an upper, mold-defining chamber in the body for a sample;
- a lower slag retention chamber disposed underneath the mold-defining chamber;
- a duct in the body, ending upwardly in a bottom of the mold-defining chamber;
- an upright refractory tube, communicating with the duct at its lower end and traversing the slag retention chamber, the tube having a lower end disposed in a lower portion of the slag retention chamber, the tube being held by the body at least at an upper portion of the slag retention chamber;
- an eccentrically disposed, flow-reversing chamber as part of the slag retention chamber and extending under, and at a lower level of, the lower end of the tube; and
- a feed duct leading from an outside surface to the slag retention chamber.

4,296,639

FREE ROTOR GYRO WITH THREE TORQUERS AND THREE PICKOFFS


Menno G. Koning, Dover, Mass., assignor to Northrop Corporation, Los Angeles, Calif.

Filed Jan. 16, 1980, Ser. No. 112,870

Int. Cl.³ G01C 19/28, 19/30

U.S. Cl. 74—5.46

12 Claims



1. In a free gyro having a case, a rotor having an inertial mass distributed about a spin axis, means in said case for imparting constant rotation to said rotor, and means for freely suspending said rotor within said case to make the orientation of the spin axis independent of the orientation of said case over a given range with respect to a nominal reference orientation of said spin axis fixed relative to said case, the improvement comprising

torquer means for applying discretely variable forces to said

rotor at three coplanar locations fixed with respect to said case and equally spaced circumferentially about the spin axis in said nominal orientation.

4,296,640

POWER TRANSMISSION V-BELT AND METHOD OF MANUFACTURE

Soukichi Nosaka, Kobe, Japan, assignor to Mitsubishi Belting Ltd., Kobe, Japan


Filed May 31, 1979, Ser. No. 44,289

Claims priority, application Japan, Dec. 16, 1978, 53-156030

Int. Cl.³ F16G 5/16, 5/00

U.S. Cl. 474—262

16 Claims



1. A power transmission V-belt comprising: a tensile member (11) arranged in the form of a layer along the center line of said belt; elastic rubber layers (13, 14) formed respectively on opposite surfaces of the layer of said tensile member; fabric layers (15, 16) bonded to the outside surfaces of said elastic rubber layers respectively, said fabric layers having different amounts of stretchability in the longitudinal direction of said belt, and said belt having a trapezoid cross-section.

4,296,641

RACK AND PINION GEAR BEARING SUPPORT


James I. May, Royal Oak, Mich., assignor to Ford Motor Company, Dearborn, Mich.

Filed Mar. 31, 1980, Ser. No. 135,601

Int. Cl.³ F16H 1/04

U.S. Cl. 74—422

5 Claims



1. A rack and pinion gear mechanism comprising:


- a driving pinion;
- a rack in meshing engagement with and driven by said pinion having at least two bearing surfaces whose center of curvature is located at the midpoint of a radial plane disposed perpendicular to the rack axis and passing through the center of a pinion tooth, the plane extending radially between the projection onto the plane of the radial extremities between which the contact point between a pinion tooth and a rack tooth moves on the face of the pinion tooth; and
- a saddle bearing for supporting said rack having bearing surfaces disposed on opposite sides of the plane, mating with and complementary to the bearing surfaces of said rack.

4,296,642

TRANSMISSION INTERLOCK

Thomas C. Schetter, Toledo, Ohio, assignor to Dana Corporation, Toledo, Ohio

Filed Aug. 20, 1979, Ser. No. 67,932

Int. Cl.³ B60K 20/00; F16H 57/06; G05G 5/10; F16H 3/02
U.S. Cl. 74—475 13 Claims


8. A vehicle transmission and mechanical interlock disposed within a unitary housing comprising, in combination, an input shaft, an output shaft, a first gear ratio selection means for effecting at least two distinct gear drive ratios between said input shaft and said output shaft, at least one axially translatable first shift rail associated with said first gear selection means, a second gear ratio selection means in tandem with said first gear ratio selection means for effecting at least two distinct gear drive ratios between said input shaft and said output shaft, at least one axially translatable second shift rail associated with said second gear selection means, an axially translatable auxiliary rail disposed generally between and parallel to said first and second shift rail, a linkage means between said auxiliary rail and one of said first and second shift rails for positively axially translating said auxiliary rail with said one of said rails, a locking member positioned transversely between said auxiliary rail and the other of said first and second shift rails, a plurality of re-entrant detents defined by said auxiliary rail and the other of said shift rails, whereby seating and interference of said locking member within said detents permits and precludes selection of certain combinations of gear drive ratios.

4,296,643

MOTORCYCLE THROTTLE GRIPPER

Morris E. Cornelius, Box 91, Yale, Iowa 50277

Filed Aug. 13, 1979, Ser. No. 66,429

Int. Cl.³ G05G 5/16
U.S. Cl. 74—531 3 Claims

1. A motorcycle throttle gripper comprising: an upper friction lever and a lower friction lever with one said friction lever positioned above the throttle grip hand control and brake lever hand control and with one said friction lever positioned below the throttle grip hand control and brake lever hand control, and with an offset concave portion on each said friction lever to provide efficient rotational frictional contact with the throttle grip hand control, and with a straight portion on each said

friction lever to provide efficient sliding friction contact with the brake lever hand control, and with the right hand extremities of the two said friction levers bent or hooked slightly to accept a flexing elastic member to keep the two said friction levers in efficient sliding contact with the brake lever hand control, and with the left hand extremities of the two said friction levers bent or hooked slightly to accept a flexing elastic member to keep the two said friction levers in efficient rotational frictional contact with the throttle grip hand control, with the two said efficient friction levers providing near zero backlash throttle gripping control.

4,296,644

CASING FOR A TRANSMISSION

Kenzo Sada, and Shigeyuki Hayashi, both of Sakai, Japan, assignors to Kubota, Ltd., Osaka, Japan


Filed Apr. 5, 1979, Ser. No. 27,341

Claims priority, application Japan, Aug. 10, 1978, 53-110967[U]

Int. Cl.³ F16H 57/02

U.S. Cl. 74—606 R

10 Claims



7. A casing for a transmission comprising: a first transmission case having a running system transmission shaft, a running system input shaft mounted below the transmission shaft, and a PTO transmission shaft mounted below the input shaft; a second transmission case connected to a forward portion of the first transmission case, said input shaft extending forwardly through the second transmission case and operatively connected to a running system clutch, said PTO transmission shaft having a forward end thereof located in the second transmission case; a tubular PTO input shaft relatively rotatably fitted on said running system input shaft and operatively connected at a forward end thereof to a PTO system clutch, a rearward end of said PTO input shaft being located in the second transmission case; a gear coupling mechanism mounted in the second transmission case to operatively connect said PTO input shaft and said PTO transmission shaft; a lower tubular member fitted between the first transmission case and the second transmission case at a position where the PTO transmission shaft extends through the cases, the PTO transmission shaft extending through said lower tubular member; an oil channel between the lower tubular member and the PTO transmission shaft to provide communication between the first and second transmission cases; an upper tubular member fitted between the first transmission case and the second transmission case at a position where the running system transmission shaft is supported, said upper tubular member defining an air channel to communicate between the first and second transmission cases; and oil seals respectively interposed between an outer periphery


of the lower tubular member and the first and second transmission cases and between an outer periphery of the upper tubular member and the first and second transmission cases whereby the first and second transmission cases are interconnected in oiltight condition.

4,296,645

POWERSHIFT TRANSMISSION WITH DIRECT DRIVE AND MODULATED TORQUE CONVERTER DRIVE IN FORWARD AND REVERSE

James J. Jameson, Coffeyville, Kans., assignor to Cooper Industries, Inc., Houston, Tex.

Filed Sep. 14, 1979, Ser. No. 75,465

Int. Cl.³ F16H 47/08, 57/00
U.S. Cl. 74—688 19 Claims

1. A multispeed gear transmission comprising: a housing; an input shaft rotatably mounted in said housing; a hydrokinetic torque converter disposed in said housing including an impeller and a turbine; first and second gears drivenly connected to said turbine; a countershaft rotatably mounted in said housing and disposed in generally parallel relation to said input shaft; third and fourth gears mounted on said countershaft and intermeshed respectively with said first and second gears; clutch means drivingly interconnecting said third gear to said countershaft; a first fluid actuated clutch drivingly connecting said input shaft to said impeller; an output shaft; and, a reversing mechanism interconnecting said countershaft and said output shaft for reversing the direction of rotation of said output shaft with respect to said countershaft.

4,296,646

AUTOMATIC TRANSMISSION

Kenneth Thornton, Nantwich, England, assignor to Rolls-Royce Motors Limited, Crewe, England

Filed Dec. 6, 1978, Ser. No. 967,150

Claims priority, application United Kingdom, Jan. 5, 1978, 00284/78

Int. Cl.³ F16H 47/08, 47/00


U.S. Cl. 74—688

2 Claims

1. A transmission comprising: an input means; an output means; planetary gearing means disposed between said input means and said output means for providing one reverse speed ratio and four forward speed ratios with the fourth forward speed ratio being an overdrive ratio; said planetary gearing means being operatively associated with a first friction clutch and a second friction clutch and first, second and third reaction brakes and first, second, third and fourth members; a hydrodynamic torque converter operatively associated

with said planetary gearing means and through which drive from said input means to said output means is provided in reverse speed ratio and first speed ratio only, said hydrodynamic torque converter being drivably connected to said first friction clutch and being arranged to be driven from said input means and drivably connected to said second friction clutch which is driven directly and mechanically from said input means, said hydrodynamic torque converter including an impeller, a stator and a turbine;

a one-way clutch provided between said impeller and said turbine to prevent said turbine from rotating at a higher forward speed than said impeller to eliminate power loss in the third speed ratio; said first member being arranged to be driven from said input means through said fluid coupling and said first




- clutch in reverse speed ratio, first speed ratio and third speed ratio; said second member being arranged to be driven directly from said input means in said second speed ratio and said third speed ratio and held stationary through said first reaction brake in reverse speed ratio; said third member being arranged to be held stationary through said second reaction brake in said first speed ratio and said second speed ratio; said fourth member being permanently connected to said output means; and said third reaction brake being provided to operatively hold said first member stationary to provide said fourth speed ratio from said planetary gearing means and said second member being driven through said second friction clutch in said fourth speed ratio.

4,296,647

DIFFERENTIAL TRANSMISSION DRIVE UNIT

Yves J. Kemper, Birmingham, Mich., assignor to Vadtac Corporation, Troy, Mich.

Filed May 30, 1979, Ser. No. 43,686

Int. Cl.³ F16H 37/06, 15/16, 37/08, 15/50
U.S. Cl. 74—690 18 Claims

1. A differential transmission unit for transmitting a mechanical power input to a pair of independently rotatable outputs, said unit comprising: a unit frame defining a first axis;

an alpha body supported by said frame for rotation on said first axis;

a pair of beta bodies carried by said alpha body on a second axis inclined with respect to and intersecting said first axis at a point of axes intersection, said beta bodies being axially spaced to be positioned on opposite sides of said point of axes intersection and each having a beta rolling surface of revolution about said second axis;

a pair of omega bodies supported by said frame and each having an omega rolling surface of revolution about said first axis, said omega rolling surfaces being positioned on opposite sides of said point of axes intersection;

said beta and omega rolling surfaces being in frictional engagement at two contact points located one on each side of said point of axes intersection thereby to establish one such contact point between each beta and omega body of said pairs and whereby nutational movement of said beta body pair results in torque transmission between said beta and omega rolling surfaces, at least one of said beta and omega rolling surfaces having variable radii along the length thereof relative to the other of said beta and omega surfaces so that the ratio of beta/omega surface radii at said contact points is varied by relative shifting of said beta and omega bodies;

means for drivably connecting the power input and said alpha body;

a pair of rotatable unit output shafts;

means for supporting the respective bodies of one pair of said beta and omega bodies for independent rotation;

means drivably connecting said one pair of said beta and omega bodies to said pair of output shafts;

means holding the other of said beta and omega body pairs against rotation on the rolling surface axis thereof; and

means for relative shifting of said beta and omega bodies in frictional engagement at each of said two contact points to vary the ratio of beta/omega surface radii independently at said respective contact points.

4,296,648


LUBRICATED FRICTION SPEED CHANGE GEARING
Hiroshi Okano, and Akira Sato, both of Susono, Japan, assignors to Toyota Jidosha Kogyo Kabushiki Kaisha, Aichi and Kabushiki Kaisha Fujikoshi, Toyama, both of, Japan

Filed Oct. 16, 1979, Ser. No. 85,256

Claims priority, application Japan, Dec. 15, 1978, 53-156712
Int. Cl.³ F16H 13/08

U.S. Cl. 74-798

4 Claims



1. A lubricated friction speed change gearing comprising a housing, first and second rotary shafts rotatably supported in said housing on collinear axes, an inner race supported by said first rotary shaft, an outer race supported by said housing to be coaxial with said inner race, a plurality of cylindrical rollers mounted between said inner and outer races and compressed and elastically deformed therebetween, and a spider member supported by said second rotary shaft to engage among said rollers in sliding contact therewith and arranged to drive or be driven by said rollers when they perform planetary movement, said spider member having substantially plane rigid surfaces at its portions where it opposes and slidably contacts said rollers, said surfaces each having a groove extending in the direction

of relative movement of the outer surfaces of the co-operating rollers.

4,296,649

HYDRAULICALLY OPERATED TRANSMISSION CONTROL


Gordon L. Marquart, Jesup, Iowa, assignor to Deere & Company, Moline, Ill.

Filed Apr. 4, 1979, Ser. No. 27,158

Int. Cl.³ F16H 5/78; F16D 67/04; B60K 17/34

U.S. Cl. 74-751

20 Claims



1. A control device for a transmission comprising the combination of a source of pressurized fluid, a housing, a pressure regulating valve mounted within the housing, a first chamber within the housing communicating with the pressure regulating valve, means coupling the source of pressurized fluid to the first chamber, an additional chamber within the housing connecting with the pressure regulating valve for providing a path for pressurized fluid provided the first chamber by the source of pressurized fluid, and means for coupling the additional chamber to the transmission to provide pressurized fluid to the transmission, the pressure regulating valve normally coupling the additional chamber to the first chamber and including means responsive to fluid pressure below a predetermined threshold value within the first chamber for cutting off the first chamber from the additional chamber.

4,296,650

TWO-SPEED TRANSAXLE


Ilmaris Kalns, Northville, Mich., assignor to Eaton Corporation, Cleveland, Ohio

Filed Jun. 25, 1979, Ser. No. 51,576

Int. Cl.³ F16H 37/08, 3/74, 3/56

U.S. Cl. 74-751

7 Claims



1. A transmission comprising:
a housing;

an input and output means mounted for rotation in said housing;

a planetary gear set including an input member rotatably driven by said input means, an output member rotatably driving said output means, and a rotatable reaction member;

a clutch mechanism operative when applied to prevent relative rotation between said members for locking said planetary gear set and effecting a one-to-one speed ratio between said input and output members and operative when released to allow said relative rotation;

a brake mechanism operative when applied to prevent rotation of said reaction member for effecting a different speed ratio between said input and output members and operative when released to allow rotation of said reaction member; and

first and second means operative to apply and release said mechanisms, said first means including preloaded spring means for applying one of said mechanisms and means responsive to pressurized fluid for opposing the force of spring means and releasing said one mechanism, and said second means including means responsive to pressurized fluid for applying the other of said mechanisms and means operative to release said other mechanism in the absence of said pressurized fluid, whereby one of said speed ratios is effected in the absence of pressurized fluid to both of said mechanisms and whereby the other speed ratio is effected in the presence of said pressurized fluid to both of said mechanisms.

4,296,651

AUTOMATIC POWER TRANSMISSION SHIFT VALVE
Kazuyoshi Iwanaga, Yokohama; Kazuhiko Sugano, Tokyo, and Kunio Ohtsuka, Yokohama, all of Japan, assignors to Nissan Motor Company, Limited, Yokohama, Japan


Filed Nov. 24, 1978, Ser. No. 963,648

Claims priority, application Japan, Sep. 5, 1978, 53-108039

Int. Cl.³ B60K 41/06, 41/10

U.S. Cl. 74-869

15 Claims



1. A hydraulic control system for an automatic transmission for a motor vehicle, the transmission being shiftable by at least one servo-actuator between a plurality of gear ratios, including at least a pair of relatively higher and lower forward drive ratios, the control system comprising:
a source of fluid;
means communicating with said source of fluid for producing in the hydraulic system a plurality of fluid pressures including a control pressure variable with operating conditions of the motor vehicle, an actuating fluid pressure selectively fed to the servo-actuator to effect shifting between gear ratios, and a kickdown fluid pressure for overriding said control fluid pressure in response to a vehicle condition wherein sudden acceleration is required;

a shift valve, including a movable valve element, communicating with said producing means such that said control pressure effects controlled movement of said valve element in response to vehicle operating conditions and such that movement of said valve element effects selective communication of fluid under the actuating pressure with the servo-actuator to cause shifting from one gear ratio to another, said valve element including a first position for establishing the

lower gear ratio and a second position for establishing the higher gear ratio;

said valve element including a first effective kickdown pressure acting area which is selectively exposed to said kickdown pressure when said valve element is in said first position; said first effective kickdown pressure area, when acted upon by said kickdown pressure, urging said valve element to remain in said first position;

said valve element including a second effective kickdown pressure acting area, which is different in area from said first effective kickdown pressure acting area, and which is selectively exposed to said kickdown pressure when said valve element is in said second position, said second effective kickdown pressure area, when acted upon by said kickdown pressure, urging said valve element to move from said second position to said first position;

a passageway extending between said producing means and said shift valve to effect communication therebetween;

a single kickdown pressure port in said shift valve effecting communication between said passageway and both said first and second kickdown pressure acting area.

4,296,652

HYDRAULIC CONTROL FOR AN AUTOMATIC VEHICLE TRANSMISSION

Gerd Oberpichler, Brunswick, and Ernst-August Honig, Wolfsburg, both of Fed. Rep. of Germany, assignors to Volkswagenwerk Aktiengesellschaft, Wolfsburg, Fed. Rep. of Germany


Filed Jul. 20, 1979, Ser. No. 59,204

Claims priority, application Fed. Rep. of Germany, Jul. 22, 1978, 2832345

Int. Cl.³ B60K 41/06

U.S. Cl. 74-868

5 Claims



1. In a hydraulic control device for an automatic vehicle transmission including a main pressure control valve for delivering an engine load-dependent main output pressure for operating actuating components of the vehicle transmission; and a pressure-limiting valve for delivering an engine load-dependent, upwardly limited control pressure; said pressure-limiting valve including a control piston exposed to said control pressure and to the force of a spring opposing the control pressure; the improvement comprising an additional control valve means for applying to said main pressure control valve an output pressure being a function of a vehicle speed-dependent pressure and said control pressure and being modulated by said control pressure and a higher main input pressure.

4,296,653

METHOD AND A DEVICE FOR REMOVING CORKS FROM VESSELS

Sune I. Lundgren, Lulea, and Leif E. L. Rehnberg, Boden, both of Sweden, assignors to Kemi-Intressen AB, Sundbyberg, Sweden


PCT No. PCT/SE78/00070, § 371 Date Jun. 20, 1979, § 102(e) Date Jun. 20, 1979, PCT Pub. No. WO79/00268, PCT Pub. Date May 17, 1979

PCT Filed Nov. 8, 1978, Ser. No. 118,803

Claims priority, application Sweden, Nov. 10, 1977, 7712690 Int. Cl.³ B67B 7/00

U.S. Cl. 81—3,46 R

9 Claims



3. A device for removing corks from vessels in situations when the upper part of the cork extends above the orifice of the vessel, which device comprises two elongated knives, each equipped with a knife-edge, and a holding device which supports the knives in a spaced apart relationship in the same horizontal plane and fixes the knives with their knife-edges oriented substantially parallel to each other in the same horizontal plane, directed towards each other and separated by a distance less than the largest diameter of the cork to be removed, said holding device having an inlet opening and an outlet opening and being elongated so as to form a free space which allows linear passage of a cork from said inlet opening to said outlet opening between the substantially parallel spaced apart knife-edges.

4,296,654

ADJUSTABLE ANGLED SOCKET WRENCH EXTENSION


Albert E. Mercer, Box 531, Jacumba, Calif. 92034

Filed Aug. 20, 1979, Ser. No. 68,097

Int. Cl.³ B25B 17/00

U.S. Cl. 81—57.26

8 Claims



1. A tool drive mechanism for producing a rotational motion at an output shaft from a selectable motion at an input shaft, said drive mechanism comprising:

- (a) an input shaft mounting bracket having said input shaft captured in journaled relation therein such that said shaft is rotational about its longitudinal axis;
- (b) an output shaft mounting bracket having said output shaft captured in journaled relation therein, such that said shaft is rotational about its longitudinal axis;
- (c) said mounting brackets being pivotally interconnected to define an axis of angular adjustment perpendicular to the rotational axes of said shafts and permitting relative piv-

otal motion of said shafts in their respective brackets in a common plane substantially including the shafts;

- (d) each of said shafts having a pivotally inner end mounting an integral bevel shaft gear captured by the mounting bracket which mounts same;
- (e) a gear spool rotational between said brackets about said axis of angular adjustment and defining two inwardly facing bevel gears engaging respective ones of said shaft gears whereby clockwise rotation of one of said shafts about its longitudinal axis produces clockwise motion of the other of said shafts about its longitudinal axis such that rotation of a first one of said shafts can be selectable caused by either the rotation of the other shaft about its longitudinal axis, or the non-rotational pivoting of the other shaft about said axis of angular adjustment, or the non-rotational pivoting of the other shaft about the longitudinal axis of said first one of said shafts;
- (f) each of said shaft gears, on the side thereof opposite the side engaging the respective inwardly facing bevel gear, engaging a gear in idling relation; and,
- (g) one of said shafts having an idler gear journaled thereon engaging the inwardly facing bevel gear which engages a shaft gear of the other of said shafts, and the last-mentioned gear engaging an inwardly facing idler beveled gear journaled coaxially with the first-mentioned two inwardly facing beveled gears.

4,296,655

SLIP JOINT PLIERS


Joseph Tesoro, 9 Dade Rd., New City, N.Y. 10956

Filed May 12, 1980, Ser. No. 149,043

Int. Cl.³ B25B 7/04

U.S. Cl. 81—405

4 Claims



1. Slip joint pliers comprising in combination: a first lever member having one end thereof shaped as a plier's first jaw; a second lever member having one end thereof shaped as a plier's second jaw; the respective first and second lever members having respectively first and second handles; the first lever member having a first single through-aperture intermediate between said first jaw and said first handle; the second lever member having a plurality of consecutively aligned through-apertures in series interconnected by a series of consecutive joining-through-apaces; each consecutive joining-through-space being of smaller linear distance between opposing spaced-apart walls than diameter of each of said plurality of consecutively aligned through-apertures; and said first single through-aperture and said plurality each having substantially the same diameters; and pivot means mounted axially through said first single through-aperture and at least one of said plurality, said pivot means being for pivoting said first and second lever members, and the pivot means including first and second portions continuous with one-another and axially-aligned end-to-end with one-another with the first portion being of a diameter greater than said smaller linear distance and lesser than said diameters of each of said plurality and with the second portion being of a diameter smaller than said smaller linear distance, whereby the first portion is retainable against lateral movement when mounted within one of said plurality and whereby the second portion is movable through said consecutive joining-through-spaces alternately when the second portion is mounted within one of said plurality, said first portion

being axially movable to and from any one of said plurality and said second portion being mounted within at least one of said plurality when said first portion is removed therefrom whereby said first lever member may be shifted to alternate pivot positions of said plurality of said second lever member when said first portion is removed from a pivot position of one of said plurality, said pivot means including a spring normally spring biasing said first portion into a pivot-mounting position within one of said plurality, said spring being a coil spring, said first and second portions being of cylindrical shapes and with central axially-extending bores and said coil spring being mounted substantially within said bores, the pivot means additionally including a lock pin and the second portion including an axially-extending slot therein with said lock pin locking said pin to said larger portion and said lock pin being mounted through said axially-extending slot.

4,296,656

DRIVER BIT ATTACHMENT


Richard J. Ernst, Palatine, Ill., assignor to Illinois Tool Works Inc., Chicago, Ill.

Filed Apr. 21, 1980, Ser. No. 141,863

Int. Cl.³ B25B 23/00

U.S. Cl. 81—429

5 Claims



1. An attachment for a power tool to permit driving of threaded fasteners said attachment comprising a generally cylindrical body; projection means extending from one end of said body, said projection means being adapted for connection to said power tool to receive rotational torque therefrom; a first longitudinal bore extending axially within said body; a driver bit having a portion which is received within said first bore; securing means within said first bore for retaining the driver bit therein; a second bore which has a larger mean diameter than said first bore, said second bore extending from said first bore to the end opposite the end having the projection, said second bore having an axial length approximately equal to the height of the fastener head with which the adaptor is to be used and a mean diameter larger than the maximum width dimension of the fastener head, a portion of said driver bit being received therein; a set screw threadably engaged in a tapped hole in the projecting means and extending into said first bore from said projection means end to position the driver bit within the first and second bores so that the point of disengagement of the driver bit from the fastener head may be varied in order to prevent over torquing of the fastener.

4,296,657

METHOD AND APPARATUS FOR POSITIONING WORK ON A NUMERICALLY CONTROLLED LATHE

Shoichi Yasuba, Seto, and Takaharu Ito, Kasugai, both of Japan, assignors to Okuma Machinery Works, Ltd., Nagoya, Japan

Filed Mar. 18, 1980, Ser. No. 131,540

Claims priority, application Japan, Mar. 23, 1979, 54/34840


Int. Cl.³ B23B 3/00, 13/00, 3/16

U.S. Cl. 82—1 C

10 Claims

1. In a numerically controlled lathe, a method of automatically carrying work from a preassigned standby position on the lathe to a machining position, which method comprises providing a pair of saddles which are mounted on a lathe bed for movement in a first direction as dictated by a numerical control system, providing a pair of cross slides which are mounted

on the respective saddles for movement in a second direction at right angles to the first direction as dictated by the numerical control system, the cross slides having mounted thereon a cooperative pair of gripper means for releasably engaging and holding the work therebetween, causing the numerical control system to move the pair of saddles to such positions that the



4,296,658

CLAMPING DEVICE FOR SIMULTANEOUSLY MACHINING INTERNALLY AND/OR EXTERNALLY, THE TWO ENDS OF A WORKPIECE


Marcel Champeau, Niort, and Andre Tabutin, La Celle Saint Cloud, both of France, assignors to Societe Anonyme dite: Ramo S.A., France

Filed Jun. 25, 1979, Ser. No. 51,796

Claims priority, application France, Jun. 30, 1978, 78 19632 Int. Cl.³ B23B 19/02, 25/06

U.S. Cl. 82—30

7 Claims



1. A clamping device for simultaneously machining, internally and/or externally, two ends of a workpiece, comprising a headstock housing in which a tubular spindle is mounted to rotate, said spindle being internally provided with two annular, monolithic pistons sliding axially and acting respectively on two collets for clamping the workpiece, located at both ends of said spindle, wherein said clamping collets which are respectively mounted in said two pistons have a cone-shaped portion, which cooperates with a corresponding cone-shaped portion in said pistons, and a cylindrical part centered in the boring of said pistons, said collets resting, on the side opposite their cylindrical part, against covers fast with said spindle by means of a cone-shaped face extending radially in order to allow a radial tightening of said collets on the workpiece, and wherein a central sleeve is placed inside said pistons and constitutes a spacer against the ends of which abut said cylindrical parts of said collets so as to ensure the guiding and the positioning of the workpiece in said collets, said central sleeve being provided at its two ends with flanges engaging corresponding counterborings in said collets.

5. A clamping device for simultaneously machining, internally and/or externally, two ends of a workpiece, comprising a headstock housing in which a tubular spindle is mounted to rotate, said spindle being internally provided with two annular pistons sliding axially and acting respectively on two collets for clamping the workpiece, located at both ends of said spindle, wherein said clamping collets which are respectively mounted in said two pistons have a cone-shaped portion, which cooperates with a corresponding cone-shaped portion in said pistons, and a cylindrical part centered in the boring of said pistons, said collets resting, on the side opposite their cylindrical part, against covers fast with said spindle by means of a cone-shaped face extending radially in order to allow a radial tightening of said collets on the workpiece, each end of said spindle being provided with means for detecting the clamping and loosening positions of said collets, each of said detecting means including a housing mounted on said headstock housing and in which extends one end of said spindle on which is secured an annular piece carrying two collars, fast in rotation with said spindle and adapted to move radially, one by a means sensitive to the movement of the collet while in the clamping position and the other by a means sensitive to the movement of the collet while in the loosening position, said collars being provided with a magnetic screen cooperating, when said collars are in an eccentric position, with members for detecting the clamping and loosening positions of the collet.

4,296,659

JACK-O-LANTERN FORMING METHOD


Christopher A. Nauman, 160-A Willowdale Dr., #103, Frederick, Md. 21701

Filed Sep. 21, 1979, Ser. No. 77,554

Int. Cl. B26D 3/00; B26F 1/46

U.S. Cl. 83—54


6 Claims



1. A method of forming a Jack-O-Lantern from a pumpkin including the steps of:

- providing a closed contour pumpkin die element defining a continuous sidewall element forming a through opening, said pumpkin die element having an upper edge and a lower edge;
- positioning said pumpkin die element adjacent an outer surface of said pumpkin at a predetermined location;
- striking said upper edge of said pumpkin die element; and
- displacing said pumpkin die element entirely through a wall of said pumpkin to a position internal said pumpkin.

4,296,660
DEVICE FOR FEEDING ROD-LIKE ARTICLES
Athos Cristiani, Bologna, Italy, assignor to CIR - S.p.A. Divisione SASIB, Bologna, Italy
Filed Jan. 19, 1979, Ser. No. 4,873
Claims priority, application Italy, Jan. 31, 1978, 12445 A/78
Int. Cl. A24C 5/50; B26D 7/06; B23Q 7/16; B65G 65/42
U.S. Cl. 83—100 8 Claims



1. A device for feeding rod-like articles, such as cigarette filter plugs, comprising, in combination:

- a hopper for containing a bulk supply of the articles, said hopper being closed at its bottom end by a rotatable removing drum presenting flutes capable of housing said articles, whereby rotation of the drum causes removal of the articles from the hopper;
- a suction belt arranged substantially horizontal below the removing drum to receive from the said removing drum the articles removed from the hopper;
- a fixed horizontal sliding surface which receives the articles moving in at least one row transversely to their length, the movement of the articles on the said sliding surface being caused by the pushing action of the articles delivered from the suction belt;
- an abutment member provided at the delivery end of the fixed sliding surface, in order to stop the horizontal movement of the leading article of the row of articles on the sliding surface;
- a rotatable collecting drum arranged at the delivery end of the fixed sliding surface, and provided with pick-up elements for collecting the leading article which has been stopped by the said abutment member.

5. A device according to claim 1, in which the articles are multiple length filter or cigarette rods, further comprising cutting means arranged in the arc of the removing drum between the hopper and the delivery point on the suction belt, said cutting means being provided to cut the articles in at least two segments; and parallel and interspaced side partitions provided along the said suction belt and along the said fixed sliding surface in order to subdivide the said suction belt and sliding surface into at least two parallel longitudinal tracks, each track terminating with an abutment member for stopping the leading segment of each row of segments.

4,296,661
FEED CONTROL FOR HORIZONTAL BANDSAW MACHINES

Tomonobu Kaneko, Isehara, Japan, assignor to Amada Company, Limited, Isehara, Japan

Filed Apr. 24, 1979, Ser. No. 32,924

Claims priority, application Japan, Apr. 28, 1978, 53-50155; Apr. 28, 1978, 53-50156


Int. Cl. B23D 53/04; B27B 13/04

U.S. Cl. 83—796

2 Claims

1. In a horizontal bandsaw machine having a hydraulic piston-cylinder unit for pivotally operating a cutting head assembly relative to a fixed base, wherein the flow of hydraulic fluid bled from unit during a cutting operation is controlled by a valve which is adjusted in response to movement of a cam follower along an inclined cam surface, the improvement

comprising: the cam surface and the cam follower being connected respectively to the piston and cylinder of said unit in a



manner such that axial movement of said piston relative to said cylinder will produce corresponding movement of said cam surface relative to said cam follower.

4,296,662
METHOD OF AND APPARATUS FOR CUTTING SHEETS OF GLASS


Ronald R. Reed, Toledo; William F. Crone, Jr., Bowling Green, and G. Robert Meyer, Toledo, all of Ohio, assignors to Libbey-Owens-Ford Company, Toledo, Ohio

Filed Mar. 17, 1980, Ser. No. 130,746

Int. Cl. B26D 3/08; C03B 33/02

U.S. Cl. 83—880

11 Claims



4. An apparatus for scoring glass sheets, the apparatus comprising:


- a scoring station;
- a continuously operating means for conveying the glass sheets along a rectilinear path beneath said scoring station and for supporting the glass sheet at said scoring station;
- means for capturing and holding the glass sheet in a stationary position at the scoring station during scoring of the glass sheet;
- at least one guide rail extending along the rectilinear path at an angle other than 90° relative thereto, and bridged over the glass sheets above said predetermined location;
- means for positionably suspending said guide rail above said conveying means above said predetermined location of the glass sheet; and
- a scoring tool movable along said guide rail for scoring the captured glass sheet along a predetermined path.

4,296,663
ELECTRONIC MUSICAL INSTRUMENT
Masanobu Chibana, Hamamatsu, Japan, assignor to Nippon Gakki Seizo Kabushiki Kaisha, Japan
Filed Sep. 13, 1979, Ser. No. 75,227
Claims priority, application Japan, Sep. 14, 1978, 53-113735; Sep. 14, 1978, 53-127397[U]

Int. Cl. G10H 1/00

U.S. Cl. 84—1.01

10 Claims




1. An electronic musical instrument comprising: keyboard means including keys to be operated for musical performance; a pulse signal generating circuit connected to said keyboard means and for generating a plurality of pulse trains of a same frequency corresponding to the tonal pitch of the operated key but of different phases, each said pulse train being constituted by "logic 1's" and "logic 0's"; an envelope waveshape generator connected to said keyboard means and for generating an envelope waveshape having a selected polarity upon every key operation; and musical tone waveshape generating means for sampling said envelope waveshape and selectively reversing the polarity of sampled values therefrom, said musical tone waveshape generating means being connected to said pulse signal generating circuit and to said envelope waveshape generator, and sampling said envelope waveshape as a function of said pulse trains applied thereto, and said musical tone waveshape generating means further acting to reverse the polarity of sampled values of said envelope waveshape as a function of said pulse trains.

4,296,664
SOUND BROADCASTING APPARATUS
Kenneth O. Woolbright, 5601 NW, 37th, Oklahoma City, Okla.
Filed Nov. 19, 1979, Ser. No. 95,424
Int. Cl. G10H 1/42, 7/00

U.S. Cl. 84—1.03

9 Claims



1. An apparatus for reproducing sound from data electrically stored in an electronic memory device, said apparatus comprising: timing control means; element duration control means including a first counter

receiving input from said timing control and means providing output to a first pulse generator;
 element sequence control means including a second counter controlled by said element duration control means, and including a first controllable switch means;
 internal program storage means controlled by said element duration control means and said first controllable switch means to provide data output;
 element pitch decoder means receiving said data output to output retrieved individual signal elements;
 means for converting the retrieved elements into respective audio signals;
 means for audibly broadcasting the respective audio signals.

4,296,665


FILL NOTE GENERATOR FOR ELECTRONIC ORGAN
 Stephen L. Howell, Huntingburg, Ind., assignor to Kimball International, Inc., Jasper, Ind.

Filed May 12, 1980, Ser. No. 149,262

Int. Cl.³ G10F 1/00; G10H 1/02

U.S. Cl. 84—1.03

20 Claims



1. An electronic musical instrument comprising:
 - a keyboard having a plurality of playing keys actuating respective keyswitches and comprising a solo portion customarily played by the right hand and an accompaniment portion customarily played by the left hand, said playing keys corresponding to notes of the musical scale, multiplexer means for scanning the keyswitches of the solo portion of said keyboard and generating on an output a time division multiplexed solo data stream on each scan of the keyboard comprising keydown signals in respective discrete time slots for each actuated keyswitch of the solo portion of the keyboard,
 - at least a group of the keyswitches of the accompaniment portion of the keyboard being interconnected in a plurality of sets such that each set comprises all of the keyswitches in said group corresponding to a particular diverse pitch of an octave length chromatic scale, and the keyswitches in each set being connected to a common output,
 - a multistage shift register means synchronized with said multiplexer means and having a plurality of load inputs at respective ones of its stages connected to the respective outputs of said accompaniment portion keyswitches, and producing on an output a fill note time division multiplexed data stream comprising keydown signals in time slots corresponding to keydown signals loaded into its inputs from the outputs of the sets of accompaniment portion keyswitches,
 - window means having an input connected to the output of said shift register means and an input connected to the output on which the solo data stream appears and an output, said window means gating to its output the data stream on the output of said shift register means for a predetermined number of time slots following receipt by said window means of a predetermined keydown signal in the solo data stream, and
 - output means connected to the output of said window means and controlled by the fill note data stream on the output of said window means for producing tones in accordance

with the keydown signals in the fill note data stream on the output of said window means.

4,296,666

SOLO SUSTAIN KEYS SYSTEM


Brian N. Wilcox, Kettering, Ohio, and John W. Robinson, Jasper, Ind., assignors to Kimball International, Inc., Jasper, Ind. Division of Ser. No. 962,003, Nov. 20, 1978, Pat. No. 4,217,801.

This application May 15, 1980, Ser. No. 150,089

Int. Cl.³ G10H 1/02

U.S. Cl. 84—1.26

3 Claims



1. In an electronic organ or the like having a source of tone signals, a plurality of keyers each including a control terminal, and keyboard controlled means for selectively supplying keyer actuating voltages to the control terminals of the keyers, a plurality of envelope generators interposed between the keyboard controlled means and the keyers each comprising: an input terminal connected with the keyer actuating voltage, an output terminal connected with the control terminal of the respective keyer, first means for storing a voltage, second means connected to said output terminal for storing a voltage, third variable conductivity means connected between said first means and said input terminal for providing when actuated a path between said input terminal and said first means whereby the voltage level at said input terminal can be transferred to said first means, and fourth variable conductivity means connected between said first and second means providing when actuated a path between said first and second means whereby the voltage level at said first means can be transferred to said second means, the improvement being means for repetitively and alternately actuating said third and fourth means to transfer the voltage level at said input through said first means to said second means by increments over a period of time comprising a clock driven counter having a variable effective count length and having its output connected to said third and fourth means for actuating the same, and means connected to said counter for varying the effective count length of said counter so as to vary the rate at which said third and fourth means are repetitively and cyclically actuated, said means for varying the effective length of said counter comprising a source of count length control signals, and said means for varying comprising a plurality of multilevel decoders connected respectively to the count length control signals, each said decoder having one input terminal connected to at least one of said count length control signals and to at least one of the tone signals and further having a plurality of outputs on which the signals on its input terminal appear, respectively, the outputs of said multilevel decoders that carry the tone signals being operatively coupled to respective ones of the keyers.

4,296,667

CAPTURE COMBINATION ACTION SYSTEM FOR ELECTRONIC ORGANS


David R. Wade, Cincinnati, Ohio, and Walter Munch, Ft. Thomas, Ky., assignors to Baldwin Piano & Organ Company, Cincinnati, Ohio

Filed Feb. 14, 1980, Ser. No. 121,591

Int. Cl.³ G09B 15/00; G10B 3/10

U.S. Cl. 84—345

26 Claims



1. A capture combination action system for use in an electronic organ for selecting a predetermined combination of stops to define the organ voicing, said system comprising:
 - a. a plurality of stop tabs for setting and resetting said stops, each of said tabs including a switch having a pair of normally open contacts which are momentarily closed to provide an electrical path when said tab is manually actuated by the organist;
 - b. a plurality of pistons for setting a desired combination of said stops to a predetermined condition, each of said pistons including a pair of normally open contacts which are closed to provide an electrical path when said piston is actuated;
 - c. random access memory means for storing data and for storing the current status of all organ stops associated with a selected combination of stops;
 - d. read only memory means containing a permanently stored operating program comprising a plurality of operating instructions; and
 - e. processing means responsive to said operating instructions including:
 - i. means for continually and sequentially scanning each pair of said stop tab and piston contacts to detect a contact closure;
 - ii. means for selecting stops having contacts detected momentarily closed by said scanning means;
 - iii. means for storing in said random access memory means data associated with a selected one of said pistons for a selected combination of stops;
 - iv. means for recalling from said random access memory means said selected stop combination data when said scanning means detects closure of said selected piston contacts;
 - v. means utilizing said recalled data to select said combination of stops and;
 - vi. means responsive to said scanning means for continually updating the data stored in said memory means to reflect the current status of all organ stops.

4,296,668

REED PROTECTOR FOR A WOODWIND INSTRUMENT

Robert A. Lorenzini, P.O. Box 91, Hancock, Mass. 01237

Continuation-in-part of Ser. No. 967,989, Dec. 11, 1978,

abandoned. This application Apr. 25, 1980, Ser. No. 143,753

Int. Cl.³ G03D 9/02


U.S. Cl. 84—383 R

2 Claims

1. An improved reed protector for a mouthpiece of a woodwind instrument utilizing a reed held by a ligature, said instru-

ment having a back end where the mouthpiece is located and a forward end opposite from said mouthpiece, said improvement comprising:

- a sleeve adapted to slip fit over the mouthpiece of a woodwind instrument, and to be located on the mouthpiece adjacent and separate from the ligature toward the forward end of said instrument, the interior of said sleeve being generally circular, a pair of protrusions, parallel to one another and extending from the exterior of said sleeve, each of said protrusions having interior surfaces which face each other, the interior of said sleeve including a flat sector located between said pair of protrusions for providing clearance between said sleeve and said reed;
- a unitary protective cap having a back end and a forward end with two substantially parallel sides extending between the back end and the forward end, said protective



cap being rotatably mounted on the pair of protrusions, and being adapted to be held in its protective position over the reed on the mouthpiece and being adapted to be held in its playing position away from the reed and on the instrument;

- each of said protrusions having an opening therein;
- said unitary protective cap having a reinforced bar at its forward end, said reinforced bar having pins extending from each end, said pins mounted in said openings on said protrusions for rotatably mounting said unitary protective cap;
- said reinforced bar having two pair of lugs thereon, one pair of lugs engaging a portion of said sleeve between said protrusions to hold said protective cap in its protective position, the other pair of lugs engaging a portion of said sleeve between said protrusions to hold said protective cap in its playing position.

4,296,669

ROCKET TUBE LAUNCHER WITH CAST-IN PLACE TUBE SUPPORT BULKHEAD


Edward J. Debona; Boyd L. Neblett; Walter J. Krueger; William J. Laird; Billy H. Campbell, and Gerald H. Matthews, all of Huntsville, Ala., assignors to The United States of America as represented by the Secretary of the Army, Washington, D.C.

Filed May 25, 1979, Ser. No. 42,667

Int. Cl.³ F41F 3/04

U.S. Cl. 89—1.816

7 Claims



1. A rocket tube launcher comprising an elongated housing structure having forward and rear ends, a rear bulkhead mounted at said rear end of said elongated housing structure, a

forward bulkhead mounted at said forward end of said elongated housing structure, a pair of center bulkheads mounted in said elongated housing structure and being relatively close together relative to the spacing between said pair of center bulkheads and said forward and rear bulkheads; each of said rear bulkhead, said forward bulkhead, and said pair of center bulkheads having a multiplicity of openings therethrough with the openings of each bulkhead being aligned with the openings of each of the other bulkheads; a launch tube mounted in each of said openings and being welded to the forward bulkhead and secured to the rear bulkhead; rigid foam means of polyurethane foam mounted between said pair of center bulkheads and surrounding the launch tubes to provide a unibody structural support for the launch tubes near a center portion thereof, center structural support means secured to said front bulkhead, said rear bulkhead, said center bulkheads and said elongated housing structure to brace these members relative to each other, said front bulkhead, said rear bulkhead, and said pair of center bulkheads each being bolted to said elongated housing structure, and said pair of center bulkheads having bolt securing means at spaced positions about said center bulkheads to maintain a substantially constant spacing between said pair of center bulkheads.

4,296,670


ORDNANCE RECOIL ENERGY CONTROL AND RECOVERY SYSTEM

Robert P. Northup, and Robert L. Anderson, both of Pittsfield, Mass., assignors to General Electric Company, Schenectady, N.Y.

Filed Jun. 29, 1979, Ser. No. 53,336
Int. Cl.³ F41F 19/14

U.S. Cl. 89—43 R

15 Claims



1. A recoil mechanism for controlling movement of a recoil mass relative to a mount comprising:

- (a) a pressurized gas recuperator system including available capacity gas chamber means interconnecting said recoil mass and said mount for opposing recoil, for collecting recoil energy in the form of gas pressure in a gas recuperator as recoil movement of said recoil mass decreases the capacity of said variable capacity gas chamber means forcing gas therefrom into said gas recuperator, for driving said recoil mass in counterrecoil with use of only part of said collected energy and for transferring the remainder of said collected energy to another system subsequent to counterrecoil;
- (b) a hydraulic accumulator system for supplying, holding and distributing hydraulic fluid under pressure including a variable capacity hydraulic pump chamber; and
- (c) interface means responsive to said gas recuperator means for utilizing gas pressure collected in said recuperator for reducing the capacity of said hydraulic pump chamber to force hydraulic fluid from said chamber under pressure to effect a transfer of recoil energy from gas pressure to hydraulic pressure, whereby recoil energy can be generated and collected in the form of gas pressure during recoil, partially dissipated to drive the recoil mass in counterrecoil and thereafter transferred to a hydraulic system for use.


4,296,671 HYDRAULIC BRAKE BOOSTER AND CONTROL VALVE THEREFOR

Louis S. Tang, South Bend, Ind., assignor to The Bendix Corporation, Southfield, Mich.

Filed Jan. 24, 1980, Ser. No. 114,799
Int. Cl.³ F15B 20/00

U.S. Cl. 91—5

11 Claims



1. In a hydraulic brake booster, a housing having an inlet and substantially defining a pressure chamber, a control valve movably disposed within the housing and being operable to communicate fluid pressure from the inlet to the pressure chamber, an accumulator normally storing fluid pressure and communicating with the pressure chamber when the control valve is operable and the fluid pressure within the pressure chamber is below a predetermined value, valve means cooperating with the accumulator to normally close communication between the accumulator and the pressure chamber, a sleeve member carried by the control valve and being movable relative to the control valve to close communication between the inlet and the pressure chamber when the fluid pressure in the latter is below the predetermined value, and an annular member engageable with the valve means to open communication between the accumulator and the pressure chamber, characterized by the sleeve member including a portion which is engageable with the housing to limit movement of the sleeve member when the control valve is operable and the annular member is movable with the control valve when the portion is engageable with the housing to engage the annular member with the valve means.

4,296,672


RECIPROCATING PISTON-CYLINDER COMBINATION AND VALVING CONTROL THEREFOR

Harold G. Inhofer, Hopkins, Minn., assignor to Proteus Corporation, Minneapolis, Minn.

Filed Nov. 13, 1979, Ser. No. 93,876
Int. Cl.³ F01L 15/16, 25/06, 23/00

U.S. Cl. 91—271

9 Claims



1. A reciprocating, piston-cylinder assembly and valving control therefore, including:

- a. a cylinder;
- b. a piston arranged for reciprocating movement within said cylinder;
- c. means for providing fluid under pressure to said assembly;
- d. a pair of inlet valving members receiving fluid under pressure and each being shiftable from a first open, fluid admitting position to direct fluid to one side of said piston for movement thereof to a second closed position;

- e. said inlet valving members being fluidically connected to provide fluid under pressure from one of said valve members in said first position to the other of said valve members to positively hold said other of said valves in the second closed position; and,
- f. a pair of exhaust valving members arranged to exhaust fluid from said cylinder in response to the movement of the piston therein.

4,296,673

POWER STEERING MECHANISM

Juan S. Bacardit, Barcelona, Spain, assignor to Bendiberica S.A., Barcelona, Spain


Filed Jun. 8, 1978, Ser. No. 913,620

Claims priority, application Spain, Jun. 11, 1977, 459,711; Jun. 14, 1977, 459,740

Int. Cl.³ F15B 9/10, 15/22, 13/042

U.S. Cl. 91—375 A

11 Claims



1. Control valve in particular for power steering mechanism having rotatable coaxial input and output members, characterized in that said control valve comprises a substantially disc-shaped chamber defined in one of said input and output members and coaxial with said members, and a rotor rotatably connected to the other of said input and output members, said rotor sealingly separating said disc-shaped chamber into a plurality of peripheral chambers communicating alternately with corresponding working chambers of a double acting servo actuating cylinder of the power steering mechanism, at least one of the axial surfaces of the disc-shaped chamber being formed with ports connected alternately to the fluid inlet and outlet of a fluid supply and arranged at angular positions such as to be partially closed by the rotor when the valve is in its normal position, while in every operating position the inlet and outlet communicate with the corresponding chambers of the servo-actuator, one of the axial surfaces of the disc-shaped chamber being defined by a member movable along the axis of said chamber, between a first position in which it engages with the adjacent surface of the rotor to sealingly separate the distribution chambers, and a second position away from the rotor surface, in which second position it interconnects said distributing chambers and equalizes the pressure in the working chambers of the actuating cylinder.

4,296,674

QUICK TAKE-UP BRAKE BOOSTER

William E. Monroe, Syracuse, Ind., assignor to The Bendix Corporation, Southfield, Mich.

Filed Jun. 21, 1979, Ser. No. 50,912


Int. Cl.³ F15B 13/10

U.S. Cl. 91—391 R

6 Claims

1. In a hydraulic brake booster, a housing substantially defining a pressure chamber, a control valve cooperating with the housing to communicate fluid pressure to the pressure cham-

ber, a pressure responsive member carried by the housing and movable in response to fluid pressure within the pressure chamber from a rest position to effectuate a brake application, an input member extending into the housing and being movable by an operator during a brake application, a lever engageable with the input member, the pressure responsive member



and the control valve, the lever forming a connection with the pressure responsive member which permits the pressure responsive member to move relative to the lever in response to fluid pressure within the pressure chamber, and a resilient member engages the housing and the lever to bias the latter to a rest position engaging the housing.

4,296,675

CYLINDER CUSHION WITH CONTRACTABLE RING


Paul E. Gies, Jackson, Mich., assignor to Aeroquip Corporation, Jackson, Mich.

Filed Jul. 16, 1979, Ser. No. 57,598

Int. Cl.³ F15B 15/22

U.S. Cl. 91—396

6 Claims



1. A fluid pressure actuator comprising, in combination, a cylinder defining a chamber and having a head provided with a port through which fluid may be admitted to the cylinder or exhausted therefrom, piston structure slidable in said cylinder toward and away from said head, an annular ring of non-compressible material mounted on said head adjacent and substantially coaxial to said port, said ring including annular inner and outer surfaces defining a radial dimension, said ring being severed through said radial dimension whereby the diametrical dimension of said ring may vary between a normal radially contracted diameter and a radially expanded diameter, an elongated valve member mounted on said piston structure telescopically received within said port and ring when said piston structure is adjacent said head controlling the flow of fluid through said port, said valve member including an outer surface slidably engaged by said ring inner surface, the normal contracted diameter of said ring inner surface being slightly less than the diameter of said valve member outer surface whereby said ring firmly receives said valve member, ring expanding means defined on said valve member initially engaging and expanding said ring to said expanded diameter upon engagement by said valve member, and ring mounting means mounting said ring upon said head limiting axial movement of said ring and permitting radial contraction and expansion thereof.

4,296,676

CONTROL MECHANISM

David K. Andrews, Cheltenham, and Michael W. Smart, Gloucester, both of England, assignors to Dowty Fuel Systems Limited, Cheltenham, England


Filed Dec. 11, 1979, Ser. No. 102,416

Claims priority, application United Kingdom, Dec. 15, 1978, 48787/78

Int. Cl.³ F15B 13/044

U.S. Cl. 91—417 R

9 Claims



1. A mechanism for controlling the position of a movable member comprising a valve having a closed position and an open position, a hydraulic displacement device secured for movement with the member and a hydraulic connection between the valve and the device such that for the valve-closed position the device and member are hydraulically locked against movement and for the valve-open position the member and device may move, the valve being formed by a pair of relatively-slidable valve components having co-operating flat surfaces, one of said components being slidably carried in and projecting outwardly from an aperture formed in a pivotally mounted arm and the other being fixed so that angular movement of the arm causes sliding movement of the one component over the fixed component, at least one of said components having at least one port in its flat surface closable by the other of said components in the valve-closed position, loading means housed within said arm and bearing on said one component to urge it in a direction outwardly of said arm and thereby hold its flat surface in sliding sealing engagement with the co-operating flat surface of said fixed component, a preloaded spring assembly comprising a pair of stops carried by said arm, a pair of leaf springs mounted to press oppositely with pre-load on said arm stops, and a pair of fixed stops adapted to contact the leaf springs at positions adjacent said arm stops, said leaf springs thereby acting between said components in a direction parallel to said co-operating flat surfaces so that the spring pre-load on its own may move said components to the valve-closed position, and a force motor which is capable, when energised, of exerting a force to move one said component relative to the other against the pre-load of the spring assembly towards the valve-open position.

4,296,677

TANDEM HYDRAULIC ACTUATOR

Jane Little, Long Beach, and Del F. Greene, Los Angeles, both of Calif., assignors to McDonnell Douglas Corporation, Long Beach, Calif.

Filed Jun. 25, 1979, Ser. No. 51,815


Int. Cl.³ F15B 13/00

U.S. Cl. 91—510

10 Claims

1. A fluid actuated cylinder comprising: a housing having a cylindrical bore; gland means dividing said cylindrical bore in said housing into a first chamber and a second chamber; an end wall, having an internal tail rod with an area 'A' closing said second chamber of said housing; a first piston for movement in said first chamber; a second piston for movement in said second chamber; rod means penetrating said gland means, operatively connecting said first piston to said second piston in tandem,

said pistons are axially aligned and moveably disposed in their respective chambers to move in cooperation between extend and retract positions with one end of said rod means having a bore to accommodate said internal tail rod, an output rod connected to said first piston having an area 'A', extending from said first chamber; a rod end wall closing said first chamber of said cylindrical bore in said housing and having a bore therein to accommodate said output rod extending from said first chamber; and



means for admitting pressure fluid against a first pressure surface on one side of said first piston and second pressure surface on one side of said second piston while exhausting fluid acting on a third pressure surface on the opposing side of said first piston and fourth pressure surface on the opposing side of said second piston so as to move said pistons in either direction, alternatively, the first and fourth pressure surfaces being equally dimensioned and the second and third pressure surfaces being equally dimensioned, whereby to define a fluid actuated, tandem, linear actuator having redundant chambers and equal combined areas in both extend and retract positions.

4,296,678

POLISH ROD JACK SYSTEM


Donald W. Felder, 1609 S. Vaden, Sherman, Tex. 75090

Filed Feb. 12, 1979, Ser. No. 11,692

Int. Cl.³ F01B 31/14; F15B 15/24

U.S. Cl. 92—13.1

3 Claims



1. In an oil well pumping unit including a walking beam pivotally mounted in a stationary support and supporting a horse head for vertical reciprocal movement, and a carrier bar suspended from the horse head reciprocally carrying a polish rod constituting the upper section of a sucker rod for operating a bottom hole pump, a hydraulic polish rod jack system comprising:

- (a) a hydraulic ram mounted on the carrier bar,
- (b) a ram piston mounted in said ram for vertical reciprocal movement,
- (c) support means operatively connected to the polish rod for vertical reciprocal movement of the polish rod with said ram piston,
- (d) a hydraulic conduit having first and second ends,
- (e) a hydraulic quick-disconnect inlet fitting mounted on the stationary support and connected to said first end of said hydraulic conduit, said inlet fitting being adapted to be quickly connected to and disconnected from a pressurized source of hydraulic fluid,

- (f) a hydraulic fluid quick-disconnect ram fitting on said ram, said ram fitting being adapted to be quickly connected to and disconnected from said second end of said hydraulic conduit,
- (g) at least portions of said hydraulic conduit being flexible,
- (h) clamp means holding portions of said conduit on the stationary support and on at least a portion of the horse head or the walking beam, so that said ram is in continuous fluid communication with said inlet fitting, even during the reciprocal movement of said ram.

4,296,679

CYLINDER WITH TWO-STAGE MOVEMENT, ESPECIALLY A WELDING CYLINDER

Karl-Erik H. Mattsson, Näsum, Sweden, assignor to AB Volvo, Gothenburg, Sweden


Filed Oct. 31, 1979, Ser. No. 90,055

Claims priority, application Sweden, Nov. 7, 1981, 7811488

Int. Cl.³ F01B 7/20

U.S. Cl. 92—52

5 Claims



1. In a cylinder with two-stage movement, in which a first piston which seals against the inside of a housing is axially displaceable in the housing, and in which a second piston, arranged coaxially with the first piston, seals in an axial cavity in one end of the first piston, is axially displaceable in said cavity and carries a piston rod which slides sealingly through one housing end which faces the cavity in the first piston, and in which in the other housing end there is arranged a pressure medium inlet tube which extends through the first piston and into the piston rod, via which tube pressure medium can be brought into or out of a first chamber delimited by the first and the second pistons, and in which second and third chambers in the housing, on the sides of the first and second pistons that face away from each other, have pressure medium connections; the improvement comprising, on the side of the second piston facing away from the piston rod, a tubular, axially oriented guide member which is sealingly guided in the first piston and slides on the inlet tube and seals against the outside of the tube and extends through the first piston, the inlet tube, at its end facing away from the guide member, being movably mounted in said other housing end.

4,296,680

COUPLED SHELLS FOR VACUUM POWER SERVO BOOSTER

Ryuji Ohta, and Michio Kobayashi, both of Matsuyama, Japan, assignors to Jidosha Kiki Co., Ltd., Tokyo, Japan

Filed Oct. 17, 1979, Ser. No. 85,830

Claims priority, application Japan, Dec. 1, 1978, 53/148803; Dec. 1, 1978, 53/148804


Int. Cl.³ F01B 19/00; F16J 3/02

U.S. Cl. 92—98 D

6 Claims

1. A vacuum power servo booster comprising: a generally disc-shaped first shell, a generally cup-shaped second shell, said first and second shells defining an outer casing of said booster, and a diaphragm secured between said first and second shells which divides the casing into two chambers, an annular groove being integrally formed at a peripheral end portion of said first shell, said annular groove opening

radially outwardly and said annular groove being defined by a first annular bent portion bulging radially inwardly from the peripheral end portion of said first shell and a second annular bent portion at an inward position of said first shell, said second annular bent portion being oriented approximately along the axial direction of said booster and bulging toward said second shell, said second shell having a cylindrical portion adapted for insertion of said first shell therein, peripheral end portions of said diaphragm being interposed between said annular groove and said cylindrical portion, and said second shell being provided with at least one axial recess in said cylindrical portion, said first shell being



provided with at least one radially outward protrusion adapted to be received in said recess, said first shell being further provided with a plurality of arcuate radial recesses at the outer peripheral surface thereof, and a plurality of locking portions arranged in an alternating manner between said recesses, said second shell being provided with locking means for engaging said locking portions, said locking means comprising radially inwardly extending arcuate locking pawls, said pawls being inclined toward the axis of said second shell so as to define guide surfaces, whereby peripheral portions of said diaphragm may smoothly pass over said guide surfaces in sliding contact therewith, without damage to said diaphragm.

4,296,681

FLUID DRIVEN SERVOMECHANISM


Mark E. Rosheim, 1851 Chester #4, Royal Oak, Mich. 48073

Continuation-in-part of Ser. No. 884,903, Mar. 9, 1978, Pat. No. 4,194,437. This application Nov. 14, 1979, Ser. No. 94,045

Int. Cl.³ F01C 9/00

U.S. Cl. 92—122

12 Claims



1. A fluid driven servomechanism comprising: a support means; a central drive member mounted on said support means in a manner which permits rotational motion about one axis and also about a second axis which is generally perpendicular to said one axis; channel means disposed about said central drive member having a first channel partially circumscribing said one axis and a second channel partially circumscribing said second axis, each channel having walls and a bottom; a first sealing means disposed along a substantial portion of said first channel so as to enclose said substantial portion of said channel, said first sealing means including fluid admission ports therein to permit fluid to enter said sub-

stantial portion of said first channel and further including second sealing means disposed along a substantial portion of said second channel so as to enclose said substantial portion of said second channel, said second sealing means including fluid admission ports to allow fluid to enter said substantial portion of said second channel; and


a first dividing means on said drive member and in said substantial portion of said first channel so as to divide the enclosed portion of said first channel and move said drive member about said one axis in response to a differential fluid pressure on opposite sides of said first dividing means and further including second dividing means similar to said first dividing means except located in said substantial portion of said second channel.

4,296,682

ENGLISH MUFFIN, METHOD AND APPARATUS
Jerome B. Thompson, Box 231 - Rte. 3, Cumberland, Md. 21502
Division of Ser. No. 964,509, Nov. 29, 1978, Pat. No. 4,216,241, which is a continuation-in-part of Ser. No. 843,498, Oct. 19, 1977, abandoned. This application Nov. 26, 1979, Ser. No. 97,212
Int. Cl.³ A47J 37/01

U.S. Cl. 99-426

5 Claims



1. Apparatus for the baking of an English muffin in a conventional bun oven comprising a baking pan, a plurality of spaced cup units positioned in said pan, each of said cup units comprising an outer cup portion which will be in direct engagement with the oven heat and an inner cup portion positioned within said outer cup portion in inwardly spaced relationship therewith forming a dead air space between the sidewalls of each inner cup portion and each outer cup portion, means associated between each of said inner and outer cup portions adjacent the respective bottom ends of each to close the dead air space formed between the respective sidewalls of each and to place the bottom surface of each inner cup portion in an open state and to position the bottom surface of each of said inner cup portions in upwardly spaced relationship from an oven heating surface, said inner cup portion adapted to receive the English muffin dough piece therein and will be baked indirectly by the oven heat, and complementary cover plate means for positioning on the top of said baking pan to cover same, said cover means having a plurality of spaced areas having pattern-creating openings therein, one of each of said areas being in vertically spaced registry with one of said cup units, means for retaining the cover plate means and the baking means in tight engagement with one another so that said cover means will remain in contact with the baking pan throughout the baking operation and thereby forming on the surface of the English muffin a pattern effect corresponding to the perforations in said cover, said cover means being perforated to an extent such that a considerable portion of the cover means will be open, thus exposing a considerable area of the dough pieces to the direct heat of the baking oven, but the size and configuration of the perforations in the cover means are such that the dough will not rise or extrude through the openings to a point above the top surface of the cover means.


4,296,683

CAN CRUSHER

Albert F. Lidik, 105 Cherry St., and Randall E. Talley, III, 2910 Johnson St., both of Kissimmee, Fla. 32741
Filed Jul. 6, 1979, Ser. No. 55,205
Int. Cl.³ B30B 9/32

U.S. Cl. 100-53

8 Claims



1. A can crusher comprising:

a housing;

a hopper removably attached to the housing;

a first frame secured within the housing, including motor mounting means at one end thereof, ram support mounting means at the opposite end, and sprocket wheels supporting means on the frame between the motor mounting means and the ram support mounting means;

a motor secured to the motor mounting means;

a ram support pivotally mounted to the ram support mounting means comprising, a can engaging plate, a pair of plates secured to a block, the space between the ends of said pair of plates and said block define guide means, said pair of plates and said block secured to the can engaging plate, an aperture extending through the pair of plates and the block, and means secured in said aperture for rotatably supporting the ram support to the ram support mounting means;

a sprocket wheel rotatably supported on the sprocket wheel supporting means, said sprocket wheel having a hub integrally secured thereto, a crank pin block secured to said hub and rotatable therewith, said crank pin block having an aperture therein;

means for connecting the sprocket wheel and the motor whereby the sprocket wheel turns upon actuation of the motor;

a ram comprising a pair of horizontally spaced apart guide rails for reciprocating in said guide means, a can engaging plate secured to one end of the guide rails, a can cradle secured between the guide rails for supporting a can between the can engaging plate secured to the guide rails and the can engaging plate of the ram support, means for connecting the opposite ends of the guide rails to the crank pin block of the sprocket wheel hub so that as the sprocket wheel turns, the guide rails pivot with the ram support and reciprocate in the guide means whereby the can engaging plate of the guide rails advances toward the can engaging plate of the ram support crushing a can supported between said can engaging plates;

a second frame having means for securing one end thereof to the motor, and hopper supporting means at the opposite ends of the frame whereby the hopper is removably attached thereto, ram support plate mounted on the frame and means for securing the ram support plate, the ram support and the first frame together;

a switch mounted on the inside of the housing;

a switch arm extending from the switch into the housing a distance sufficient to contact the crank pin during rotation thereof, said switch arm inoperable to activate the switch during counterclockwise revolution of the crank pin and operable to activate the switch to stop the motor during clockwise rotation of the crank pin; and

an indicator operable in response to activation of the switch and stopping of the motor to indicate a jammed condition.

4,296,684

APPARATUS FOR STACKING FOLDED PRINTING PRODUCTS


Jochen Wangermann, Appen, Fed. Rep. of Germany, assignor to Gruner & Jahr AG & Co., Itzehoe, Fed. Rep. of Germany
Filed Jan. 14, 1980, Ser. No. 111,924

Claims priority, application Fed. Rep. of Germany, Jan. 22, 1979, 2902285

Int. Cl.³ B30B 1/26; B65H 29/38, 31/10

U.S. Cl. 100-292

8 Claims



1. Apparatus for forming a vertical stack from folded printing products sequentially conveyed along a path with the folds in the leading position, said apparatus comprising: conveyor means (1, 2) for defining the path and for conveying the products (P) sequentially therealong; stop means (6a, 6b, 6c) interposed in the path and toward which the products move; support means (8) adjacent said stop means for receiving the sequentially conveyed printing products in a vertical stack with the folds abutting said stop means; pressing means (14-20) operatively associated with said stop means, said pressing means including at least three groups of presser members (14, 14') arranged in spaced relationship along said stop means and across said path; said presser member groups having drive means (21) for driving said presser members in an endless path, said path having a first upper position in which said presser members overlie the product stack, a second, lower position in which said presser members contact and press the stack on the support means, and having a portion in which said presser members have a component of motion, when in contact with the stack, drawing the product toward the stop means; the movements of said presser member groups being phase shifted with respect to each other such that one group returns from the lower position to the upper position when a second group overlies the product stack and a third group presses the stack; and control means coupled to said conveyor means and drive means for synchronizing the supply of the printing products with the operation of said pressing means.

4,296,685

WARHEAD WITH SLAVE MISSILES DISPOSED IN A FIRING TUBE

Rudolf Romer, Kaarst, and Hans-Egon Schepp, Duesseldorf, both of Fed. Rep. of Germany, assignors to Rheinmetall GmbH, Duesseldorf, Fed. Rep. of Germany

Filed Sep. 4, 1979, Ser. No. 72,434

Claims priority, application Fed. Rep. of Germany, Sep. 2, 1978, 2838347


Int. Cl.³ F42B 25/02

U.S. Cl. 102-387

6 Claims

1. In a warhead adapted to be disposed with a plurality of similar warheads axially in a load-carrying missile for ejection therefrom behind the other, the warhead carrying slave missiles disposed in firing tubes, the warhead having a parachute connected thereto to cause the directional, braked descent thereof in the target area, the slave missiles having proximity fuses causing their firing, the improvement wherein the war-

head comprises a firing tube which is open at both ends and in which two slave missiles are disposed with a common propel-



lant charge between them, the parachute being secured to the firing tube centrally of the length of the firing tube.

4,296,686

REMOTE CONTROL DEVICE FOR ACTIVATING OR INACTIVATING A PNEUMATIC WAR MINE

Joseph Marer, Lyss, Switzerland, assignor to Redon Trust, Schaan, Liechtenstein


Filed Jul. 25, 1979, Ser. No. 60,333

Claims priority, application Switzerland, Jul. 27, 1978, 8072/78

Int. Cl.³ F42C 15/14

U.S. Cl. 102-427

2 Claims



1. In a pneumatic war mine, a remote control device for activating and deactivating the mine, comprising an electromagnetic relay operative for arming and disarming the mine; a self-contained power supply; a receiver circuit operative for receiving a transmitted control signal; and an electric control circuit connected with said relay, power supply and receiver circuit, said control circuit being normally passive and beginning to draw power from said power supply only upon being triggered by receipt of a control signal at said receiver circuit.

4,296,687

SEGMENTED SABOT PROJECTILE

Harold E. Garrett, Santa Ana, Calif., assignor to The United States of America as represented by the Secretary of the Army, Washington, D.C.

Filed Jul. 16, 1979, Ser. No. 57,778


Int. Cl.³ F42B 13/16

U.S. Cl. 102-518

1 Claim

1. A spin-stabilized discarding sabot projectile comprising a base, a core seated on the base, a multi-piece sabot encircling the core and the forward section of the base; said sabot comprising a first set of plastic segments evenly spaced around the core circumference, a second set of plastic segments occupying

circumferential spaces between adjacent ones of the first segments, and a plastic spinner band located at the rear end of the sabot to project radially outwardly beyond the sabot side surface, said band being integrally formed with the second set of plastic segments to define a one piece molding; said plastic band having a relatively thin radial dimension corresponding to the rifling thickness in a gun barrel whereby the band is severed by the rifling lands in the gun barrel as the projectile is fired out of the barrel; the plastic band being arranged in surrounding relation to the first plastic segments whereby the band constitutes a mechanism for retaining the plastic segments on the core, such that severing of the band enables the segments to be centrifugally separated from the core as the projectile exits from the gun barrel; each sabot segment having a circumferentially projecting rib (34) in one of its side edges, and a circumferentially projecting slot (32) in its other side



edge, the ribs and slots extending forwardly from the aforementioned base to the front end of the sabot, the ribs and slots on adjacent segments being interlocked together only while the projectile is within the gun barrel; the sabot segments having cylindrical outer surfaces cooperatively defining a cylindrical sabot outer surface, said segments occupying the entire circumferential space around the core without any intervening void spaces; one set of plastic segments being formed as a one piece molding using the base and core as a mold surface, the other set of plastic segments being formed by material molded into the circumferential spaces defined by said one segments, adjacent ones of the segments having non-adherent engagement with each other; the ogive portion of the core extending forwardly beyond the sabot segments so that adjacent segments are interconnected solely by the aforementioned plastic band and interlocked rib-slot connections.

4,296,688

ELECTRIC CIRCUIT FOR FIRING A DETONATOR
Robert G. Orlandi, Prilly, Switzerland, assignor to S.A. PRB Societe Anonyme, Brussels, Belgium


Filed Sep. 4, 1979, Ser. No. 72,100

Claims priority, application Switzerland, Sep. 5, 1978, 9329/78

Int. Cl. F42C 11/06

U.S. Cl. 102-218

3 Claims



1. Electric circuit for firing a detonator for a projectile, comprising a generator for charging a first condenser and a second condenser connected in series, the aforesaid first condenser being connected in series with a contactor, a primer and a semi-conductor component with a controlled conductivity, and means for stabilizing the voltage of one of the aforesaid condensers and for preventing the firing of the primer during

a predetermined time, in which the aforesaid means comprise a first voltage divider connected in parallel with the series connection of the aforesaid first condenser and second condenser and aforesaid contactor, the control electrode of the aforesaid semi-conductor component being connected with the intermediate point of the aforesaid first voltage divider comprising a resistor and a transistor, the base of which is connected with the intermediate point of a second voltage divider connected in parallel with the aforesaid second condenser, the capacity of which is many times greater than the capacity of the first condenser.

4,296,689

ROTARY LOCKING MECHANISM


Thomas K. C. Hardesty, Ednor, Md., assignor to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Jul. 25, 1979, Ser. No. 60,557

Int. Cl. F42C 15/20

U.S. Cl. 102-260

6 Claims



1. A rotary-acting, safing and arming, ball-lock mechanism for releasably locking an arming shaft of a weapon against axial movement, said arming shaft having an engageable surface, comprising:

- a base member having a central longitudinal aperture therein for receiving the arming shaft;
- a rotor mounted for limited rotary movement on said base member;
- a plurality of radial apertures formed in said base member and communicating with said central longitudinal aperture;
- a plurality of balls disposed in said radial apertures;
- a plurality of cam surfaces formed on said rotor for moving said balls partially through said radial apertures into said central aperture and into engagement with the arming shaft engageable surface to lock the shaft against movement when said rotor is moved to a safe position;
- means for locking said base member and said rotor in the safe position; and
- a pair of compression springs interposed between said base member and said rotor for moving said rotor to an arming position when said locking means is released whereby said balls are free to disengage the arming shaft engageable surface, release the arming shaft and permit axial movement of the arming shaft to the arming position to arm the weapon.

4,296,690

HANGER FOR TRACK-TYPE SUSPENDED RAILWAY
Rudolf Baltensperger, Alte Keiserstr. 157, CH 8181 Höri, and Hans B. Pfister, Frohaldenstr. 20, CH 8180 Bülach, both of Switzerland

Filed Nov. 1, 1978, Ser. No. 956,654

Claims priority, application Switzerland, Nov. 11, 1977, 13779/77

Int. Cl. E01B 3/00


U.S. Cl. 104-91

9 Claims

1. In a suspended railway having at least one suspension cable lying generally in a vertical plane and an at least gener-

ally horizontally elongated track formed by a pair of generally parallel hollow beams having upper sides constituting an upper surface and a predetermined transverse horizontal width and lying generally in said plane below said cable, a hanger comprising:

- an upper part secured to said suspension cable;
- a lower part secured to said track below said upper part;
- a rigid T-shaped intermediate part between said upper and lower parts;
- an upper pivot interconnecting said upper and intermediate



- parts and defining therebetween a generally horizontal upper pivot axis extending generally in said plane and spaced at said hanger above said upper surface of said track by a vertical distance at least equal to said transverse width; and
- a lower pivot interconnecting said intermediate and lower parts and defining therebetween a lower pivot axis extending generally perpendicular to said plane and closely juxtaposed with said upper surface at said hanger, said pivot axes being relatively fixed and immovable relative to each other.

4,296,691

APPARATUS FOR USE ON VEHICLE TRANSPORTERS
Robert Lohr, 14, rue du 14 Juillet, 67980 Hangenbieten, France


Filed Sep. 11, 1978, Ser. No. 941,246

Claims priority, application France, Sep. 16, 1977, 77 28555

Int. Cl. B60P 3/06; B61D 3/06

U.S. Cl. 105-370

12 Claims



1. In an apparatus for vertically moving an upper platform of

vehicle transporter trailer comprising a lower platform disposed on a chassis and an upper platform supported at a distance from the lower platform for movement toward and away from the lower platform, front and rear vertical support posts secured to the lower platform for supporting front and rear portions of the upper platform, vertical screws housed in at least one of said front and rear posts, drive means for rotating the screws, and a nut and guide assembly on each rotatable screw adapted for vertical displacement along the screw in response to rotation thereof by the drive means, said assembly supportably and drivably engaging the upper platform, the improvement wherein the nut and guide assembly comprises a screw driven nut vertically displaced upon rotation of the screw and a separate support fork disconnected from and resting on the nut for vertical movement therewith, said support fork being transversely moveable relative to the drive nut to permit guiding of the upper platform while only imposing axial forces on the screw and the drive nut.

4,296,692

RAILWAY CAR CEILING PANEL

Marc Roux, La Rochelle, France, assignor to Alsthom-Atlantique, Paris, France


Filed Sep. 6, 1979, Ser. No. 73,037

Claims priority, application France, Sep. 13, 1978, 78 26247

Int. Cl. B60R 13/08; B61D 17/18; E04B 13/08

U.S. Cl. 105-397

4 Claims



1. A ceiling component, in particular for rail vehicles, said component being formed by a curved panel and having a support which supports a layer of sound-proofing and heat insulating material, the improvement wherein the support is made in one piece and is constituted by a metal sheet having double edge portions forming a peripheral flange spaced slightly inwardly projecting from one surface of said panel, said double edge portions alone providing the rigidity necessary for the panel and wherein each edge portion is bent twice, firstly completely inwards on itself and, secondly, in a plane which is substantially perpendicular to the first bend and which alone forms the peripheral flange.

4,296,693

BEACH UMBRELLA SUPPORT

Richard W. Archer, 4/66 Beresford Rd., Rose Bay, New South Wales, 2029, Australia

Filed Feb. 8, 1979, Ser. No. 10,407


Int. Cl. A47B 41/04, 35/00

U.S. Cl. 108-28

3 Claims

1. A support for the shaft of a beach umbrella comprising a flat bottom collapsible container adapted to receive solid or liquid material, said container having a top part with a filler opening therein, a tubular member extending centrally from the top part of said container and adapted to receive the shaft of said beach umbrella, means to clamp said beach umbrella

shaft to said tubular member, a central opening in the bottom of said container large enough to allow said beach umbrella



shaft to pass therethrough and a doughnut shaped water-tight insert in said container.

4,296,694

GUITARIST'S FOOT-REST

Itaru Kobayashi, 1-15-2, Motomachi, Kiyose City, Tokyo, Japan


Filed Dec. 20, 1979, Ser. No. 105,569

Claims priority, application Japan, Dec. 26, 1978, 53/159122

Int. Cl.³ A47C 9/12

U.S. Cl. 108—116

2 Claims



1. Guitarist's foot-rest comprising:

a tread-board,
a pair of cross legs for supporting said tread-board,
a rod connecting the upper ends of the free legs having single wire staple or double wire staples, and
a pair of parallel height regulating plates attached below the tread-board, each of said height regulating plates being provided with a number of recesses for receiving the connecting rod and recesses for receiving single or double wire staples.

4,296,695

SEEDING DEVICE WITH AIR DISTRIBUTION SYSTEM
Sherman H. Quanbeck, Aneta, N. Dak., assignor to Wil-Rich, Inc., Wahpeton, N. Dak.

Continuation of Ser. No. 892,985, Apr. 3, 1978, abandoned. This application Mar. 7, 1980, Ser. No. 128,250


Int. Cl.³ A01C 7/20, 7/06, 15/04

U.S. Cl. 111—34

20 Claims

1. In a pneumatic distributor arrangement for distributing particulate materials from a storage tank and having a pair of elastomeric rollers having a length extending across the storage tank for metering discrete particles from said storage tank in a substantially continuous line extending along the length of said metering rollers, the rollers being substantially contiguous along the length thereof, the improvement comprising a plurality of individual cups positioned below said metering rollers to receive material being dispensed, said cups being individually removably attached to said storage tank and positioned therebelow, said cups having fore and aft walls and side walls joining said fore and aft walls to form an open topped cup, the fore and aft walls having lower portions, a bottom wall joining the lower portions and extending therebetween to define a chamber adjacent the bottom of each of said cups, an inlet orifice defined in one of the lower portions and an outlet opening of

larger diameter than the inlet orifice substantially directly axially aligned with said inlet orifice and defined in the other lower portion, each side wall having an upper edge substantially contiguous with the upper edges of the side walls of adjacent cups, the upper edges of the side walls of adjacent cups extending transverse to the length of said metering rollers



4,296,696

DEVICE FOR PRODUCING SEWING SEAM PATTERNS OF STITCH GROUPS

Hermann Taddicken, Schwäbisch Gmünd-Unterbettingen, and Wolfgang Sachs, Mögglingen, both of Fed. Rep. of Germany, assignors to Eisele Apparate-und Gerätebau GmbH, Fed. Rep. of Germany


Filed Aug. 29, 1980, Ser. No. 182,777

Claims priority, application Fed. Rep. of Germany, Sep. 5, 1979, 2935763

Int. Cl.³ D05B 3/06

U.S. Cl. 112—70

13 Claims



1. A device for producing sewing seam patterns of stitch groups in a workpiece, for example buttonholes, including a holding mechanism for displacing the work intermittently to perform individual sewing operations, and a sewing machine equipped with a work clamping mechanism which is displaceable relative to a needle bar performing a swinging motion, and which engages the work in the area of the seam pattern to be sewn, comprising, guide means connected to the sewing machine for displacement of the sewing machine parallel to the direction of displacement of the clamping mechanism, and a drive mechanism connected to the guide means and controlled

by motion of the clamping mechanism through which cyclic motions in conformity with stitch formation are imparted to the sewing machine along a distance corresponding to the length of a seam pattern to be formed, which motions are opposite in direction to those of the clamping mechanism.

12. A method of producing sewing seam patterns as stitch groups comprising:
intermittently displacing a workpiece to receive seam patterns in a workpiece feed direction;
clamping the workpiece in an area thereof to receive a seam pattern;
moving the clamped workpiece area from an initial position past a sewing needle and looper of a sewing machine, in a first seam forming direction for a length of one side of a seam pattern to be formed, to form the one side of the seam pattern;
moving the sewing machine in a direction opposite the first seam forming direction for the length of the one side to return the workpiece area to its initial position;
unclamping the workpiece area; and
intermittently displacing the workpiece by a distance equal to a spacing between adjacent seam patterns to be formed.

4,296,697

SEWING MACHINE WITH A WORK HOLDER FOR WRAPPING BUTTON SHANKS

Karl Barth; Ernst Albrecht, both of Hochspeyer, and Horst Stahlschmitt, Kaiserslautern, all of Fed. Rep. of Germany, assignors to Pfaff Industriemaschinen GmbH, Fed. Rep. of Germany



Filed Dec. 3, 1980, Ser. No. 212,563

Claims priority, application Fed. Rep. of Germany, Dec. 5, 1979, 7934154

Int. Cl.³ D05B 3/16, 53/00

U.S. Cl. 112—109

8 Claims



1. A device for wrapping button shanks connecting a workpiece to a button, with thread in a sewing machine comprising, a first holding element against which the workpiece can bear, a second holding element against which the button can bear spaced from the first holding element with the shank extending between the first and second holding elements, and adjustment means connected to the first and second holding elements for adjusting the spacing therebetween.

4,296,698

BUTTON ATTACHING HAND TOOL WITH BUTTON STORAGE COMPARTMENT



Donald R. Davidson, Berkeley Heights, and Walter H. W. Marsh, Fanwood, both of N.J., assignors to The Singer Company, Stamford, Conn.

Filed Jul. 14, 1980, Ser. No. 167,984

Int. Cl.³ D05B 3/14

U.S. Cl. 112—110

10 Claims



1. A button attaching hand tool including a box-like structure with a button storage compartment, a needle affixed in said structure, a second needle movable in said structure, means for adjusting the position of the second needle in said structure relative to the fixed needle to establish a spacing between the needles corresponding to the spacing between the holes of a button to be attached to a piece of material with said tool, and a slidable shroud on the box-like structure for use in removing the material and button from the tool, the shroud being slidable between one position wherein the shroud shields an operator from injury by the needles and another position wherein the needles are exposed for button attaching use.

4,296,699

FABRIC CLAMP

Artin G. Vartoukian, Roselle Park, N.J., assignor to The Singer Company, Stamford, Conn.


Division of Ser. No. 952,901, Oct. 19, 1978, Pat. No. 4,186,673.

This application Jun. 27, 1979, Ser. No. 53,144

Int. Cl.³ D05C 9/04; D05B 19/32

U.S. Cl. 112—121.15

4 Claims



1. A fabric clamp for supporting and guiding fabric to be

sewn in cooperative disposition with respect to the needle of a sewing machine, for use with a variable translation fabric feeding mechanism, said clamp comprising:

- a lower supporting structure;
- an upper supporting structure rigidly connected to the lower supporting structure;
- a lower, flat plate extending from the lower supporting structure and having a cutout in its interior portion of a size and shape slightly larger than the excursion of said variable translation fabric feeding mechanism;
- an upright section connected in vertically slidable fashion to one end of the upper supporting structure; and
- an upper clamp plate having a fork-shaped section which is fixedly secured to the upright section, and a rigid, open frame pivotably mounted at two diagonally opposed corners to the ends of the fork-shaped section, the opening in said open frame being about the same size and shape as the cutout in the lower, flat plate.

4,296,700

DEVICE FOR THE AUTOMATIC GUIDING OF A WORKPIECE ON A SEWING MACHINE

Fritz Jehle, Enkenbach-Alsenborn, and Erich Willenbacher, Kaiserslautern, both of Fed. Rep. of Germany, assignors to Pfaff Industriemaschinen GmbH, Fed. Rep. of Germany


Filed Apr. 28, 1980, Ser. No. 144,039

Claims priority, application Fed. Rep. of Germany, May 4, 1979, 2917950

Int. Cl.³ D05B 35/10

U.S. Cl. 112—153

4 Claims



1. A device for the automatic guiding of a workpiece on a sewing machine so as to produce a curved edge parallel seam and in a sewing machine which includes a reciprocating needle and a presser foot which are engageable with the workpiece and a feed member which is engageable with the workpiece as it moves through a substantially rectangular feed path to move it relative to the needle and, including a guide rule disposed in spaced relationship to the needle for guiding the edge of the workpiece and a scanner scanning the workpiece edge for sensing its position, the improvement comprising a plunger mounted above the workpiece and being movable into and out of engagement with the workpiece to hold the workpiece upon engagement therewith so as to permit the turning thereof during the feeding movement of said feed member, first drive means connected to said plunger to move said plunger toward and away from engagement with the workpiece, a stitch length setting mechanism connected to said feed member including a stitch length setting lever which is movable to change the length of feeding movement of said feeding member, a second drive mechanism including a rod movable through a path to engage said stitch length setting lever and displace it to adjust a feeding length of said feed member, said first drive means being connected to said second drive means so as to operate said second drive means as a function of said first drive means.

4,296,701 THREADING ARRANGEMENT FOR CHAINSTITCH SEWING ON A SEWING MACHINE


Robert H. Larsen, Middletown, N.J., assignor to The Singer Company, Stamford, Conn.

Filed Nov. 6, 1980, Ser. No. 204,420

Int. Cl.³ D05B 1/14

U.S. Cl. 112—168

9 Claims



1. In a sewing machine which includes a partitioning wall in a bracket arm between thread receiving channels, and wherein needle thread extends down one of said channels, around the bottom edge of the partition wall and into the other channel, upwardly through a check spring to a movable thread pulling and thread supplying take-up lever, and downwardly from the take-up lever on the way to a sewing needle; a chainstitch thread guide attached to the partitioning wall and including a thread guiding trough extending into said other channel to receive the needle thread extending from the check spring to the take-up lever and the thread extending downwardly from the take-up lever on the way to the needle, the inner end of the trough being located to decrease the thread supplying capability of the take-up lever.

4,296,702

STORAGE COMPARTMENT FOR SEWING MACHINE FOOT CONTROLLER

Willi Meier, Karlsruhe-Durlach, and Bernd Rojahn, Herxheim, both of Fed. Rep. of Germany, assignors to Dorina Nähmaschinen GmbH, Fed. Rep. of Germany

Filed Mar. 19, 1979, Ser. No. 21,834

Claims priority, application Fed. Rep. of Germany, Mar. 23, 1978, 7808896[U]


Int. Cl.³ D05B 69/10, 75/00

U.S. Cl. 112—258

10 Claims

1. A sewing machine comprising, a casing, a drive motor for driving said sewing machine mounted on said casing, a recess defined within said casing opening outwardly to one side thereof, a foot control member for said motor having a housing portion removably positionable in said recess and a control portion for regulating the speed of said motor in said housing portion, a cable fixedly attached to said casing and electrically interconnected with said control portion and said motor through said housing portion, a winding reel rotatably mounted in said housing portion about said control portion and having a drum portion around which at least part of said cable is wound, said winding reel rotatable with respect to said

housing portion for winding and unwinding said cable to permit movement to said control member out said recess, and



spring means mounted on said drum portion for biasing said winding reel in a direction to rewind said cable.

4,296,703

SEWING MACHINE CONVERSION APPARATUS


Elmer R. Thompson, 2408 47th St., Lubbock, Tex. 79412

Filed Oct. 3, 1979, Ser. No. 81,345

Int. Cl.³ D05D 27/00, 27/20

U.S. Cl. 112—310

16 Claims



1. Apparatus for converting a sewing machine capable of sewing lightweight material to one capable of sewing heavier material and also capable of maintaining the material's seam connectible designs in alignment, the unconverted sewing machine having a main crankshaft coupled to a primary lift shaft and to a primary feed shaft and further having a feed dog for feeding a workpiece across a workpiece supporting surface of the machine, said apparatus comprising:

- means for pivotally connecting a needle bar and a feed foot to said sewing machine;
- means, responsive to actuation of said primary feed shaft, for oscillatably pivoting said connecting means in a feed direction and a reverse feed direction;
- means, responsive to actuation of said primary lift shaft, for clamping said workpiece against said workpiece supporting surface during said reverse-feed direction pivotation; and
- means, responsive to actuation of said primary lift shaft, for lowering and raising said feed dog at the substantial extreme of said feed direction pivotation and at the substantial extreme of said reverse-feed direction pivotation, respectively.

4,296,704 ANTI-GRAVITY SPINNAKER


John G. Bridge, P.O. Box 503, Poughkeepsie, N.Y. 12601

Filed May 7, 1979, Ser. No. 36,802

Int. Cl.³ B63H 9/04

U.S. Cl. 114—103

8 Claims



1. A spinnaker large enough to aid a sailboat when sailing with the wind behind the boat, comprising:
a piece of flexible sail fabric having a top end, a bottom end and at least two sides, an interior surface and an exterior surface;
a plurality of tubular shaped inflatable bags of variable widths attached to the exterior surface of the fabric and containing a lighter-than-air gas;
stabilizing lines extending from the corners of the interior surface of the fabric said lines joined above the surface of the fabric at about the mid-point of the interior surface; and
means at three points on the spinnaker for attaching riggings from the spinnaker to both sides of the hull of the boat and to the top of the mast.

4,296,705

PNEUMATIC MARINE FENDER

Hisanari Uruta, Tokyo; Kaneaki Takahashi, Yokohama; Hirotugu Masuda, Yokohama, and Tomoyuki Kurata, Yokohama, all of Japan, assignors to Bridgestone Tire Co., Ltd., Tokyo, Japan


Filed Feb. 28, 1979, Ser. No. 16,705

Claims priority, application Japan, Mar. 3, 1978, 53/23601

Int. Cl.³ B63B 59/02

U.S. Cl. 114—219

2 Claims



1. A pneumatic marine fender composed of cylindrical barrel serving as a shock receiving face, comprising a hollow cylindrical shell formed of rubber or rubber-like elastic material and a composite inner reinforcement composed of two kinds of cord layers comprising an axially extending cord layer substantially covering the end surface of said cylindrical shell and at least two circumferentially extending cord layers whose cords are slightly inclined at an angle of the order of smaller than 30°, preferably 19° with respect to the circumferential line of the cylindrical barrel and symmetrical arranged with respect to the circumferential line of the cylindrical shell in reverse directions and helically wound around the cylindrical

shell, the inclined cut ends of said circumferentially extending cords aligned at one end of said cylindrical barrel.


4,296,706
ANCHOR

Eugene M. Hughes, Richmond, England, assignor to The British Petroleum Company Limited, London, England
Filed Aug. 28, 1979, Ser. No. 70,442
Claims priority, application United Kingdom, Jul. 13, 1978, 29741/78

Int. Cl.³ B63B 21/24

U.S. Cl. 114—294

5 Claims



4. A gravity anchor comprising:

- a set of buoyancy tanks;
- a container affixed to said tanks and having an interior volume for the reception of liquid ballast;
- a conduit extending vertically to the interior of said container from an opening in an upper surface of said container; and
- a wall upstanding from a floor of said container and surrounding an opening at the bottom of said conduit to serve as a weir for the distribution of ballast conducted into said container via said conduit.

4,296,707

RAILROAD CAR HAND BRAKE SIGNAL DEVICE


Leroy P. Kennedy, Mahwah, N.J., assignor to Abex Corporation, New York, N.Y.

Filed Feb. 13, 1980, Ser. No. 120,964

Int. Cl.³ B61D 49/00; G01L 19/12

U.S. Cl. 116—58 A

2 Claims



1. A railroad car hand brake signal device for alerting a train crew that a hand brake is applied when air is supplied to a train brake pipe during operation of the train, the signal device comprising a housing and means for mounting the housing on a railroad car; characterized by a port formed laterally in a wall in the housing which is connected to the railroad car brake pipe, blocking means for blocking the port movable within the housing between a first position which blocks the port and a second position which opens the port to bleed air in the brake pipe into the housing, an air operated whistle formed in the housing, a passage formed in means connecting the whistle to the housing which connects the port with the whistle, the passage being sized to cause significant bleed off of air in the brake pipe when the port is open to signal the train crew, and means for connecting the blocking means with a movable element of the hand brake wherein when the hand brake is applied the element moves in one direction to thereby move

the blocking means to the second position to uncover the port to cause air to bleed from the brake pipe and the whistle to operate.

4,296,708

APPARATUS FOR COATING METAL SUBSTRATES WITH ADHESIVE


Kenneth L. Robertson, Covington, and Curtis A. Heslep, Piqua, both of Ohio, assignors to Ken-Koat, Inc., Troy, Ohio

Filed Feb. 1, 1980, Ser. No. 117,693

Int. Cl.³ B05C 1/00

U.S. Cl. 118—233

3 Claims



1. Apparatus for uniformly coating a metal substrate with an adhesive comprising at least one coating station and at least one drying station, said coating station including a coating roll covered with an all natural fiber felt, means to rotate said coating roll, a reservoir means for supplying a solvent-based adhesive to said coating roll, and an idler roll adapted to be disposed on the opposite side of said metal substrate from said coating roll, and belt means connecting said idler roll to said coating roll for rotating said idler roll in the same direction as said coating roll and for pressing said metal substrate against said coating roll, said drying station including means to heat the air in said station, and means for conveying said metal substrate successively to said at least one coating station and at least one drying station said means for conveying comprising an endless chain having a mandrel extending outwardly from each link.

4,296,709

ANIMAL LITTER PREPARATION

Benjamin M. Schuelein, Jr., St. Louis, Mo., assignor to Alfa-Pet, Inc., St. Louis, Mo.

Filed Jun. 22, 1979, Ser. No. 51,209

Int. Cl.³ A01K 1/015

U.S. Cl. 119—1

6 Claims

1. An animal litter consisting essentially of a chlorophyll-containing agent from the class consisting of alfalfa, algae, broom grass and timothy grass, and a relatively high density cellulosic agent consisting of corn cob grits, said chlorophyll-containing agent and said grits being physically intermixed in a dry, discrete state, said intermixture being free of chemical agents, compounds, and preparations, said grits constituting between approximately 50% to 70% by weight of the litter and said chlorophyll-containing agent constituting approximately 50% to 30% of the litter.

4,296,710

AUTOMATIC FEEDING APPARATUS

William M. Sillers, III, P.O. Box 227, Grant, Fla. 32949

Filed Apr. 8, 1980, Ser. No. 138,355


Int. Cl.³ A01K 61/02

U.S. Cl. 119—51.11

11 Claims

1. An automatic feeding apparatus for periodically dispensing fish food into an aquarium, said apparatus comprising in combination:
 - a body member for being removably coupled to the aquarium;

a hopper carried by said body member for receiving a storage canister of fish food; valve means movably coupled to said body member for periodically receiving in a first position the fish food from said hopper and for discharging in a second position the fish food into the aquarium, said valve means including, a generally cylindrical drum dispenser which is rotatably carried within a circumferential section of said body member, with said drum dispenser including therein an open metering bore, and



- a first piston movable within said bore so as to adjust the capacity of a first food receptacle defined by said metering bore, said first piston and said circumferential section of said body member;
- actuator means for rotating said valve means between said first and said second positions; and
- clutch means interposed between said actuator means and said valve means for allowing the operating position of said valve means to be continuously adjusted between said first and said second positions, whereby the exact discharge time of the fish food into the aquarium may be adjusted.

4,296,711

HEATING BOILER

Erik A. Bilberg, Strängnäs, Sweden, assignor to EABVV Utvecklings Aktiebolag, Strängnäs, Sweden


Filed Feb. 15, 1980, Ser. No. 121,659

Claims priority, application Sweden, Apr. 10, 1979, 7903172

Int. Cl.³ F22B 31/04

U.S. Cl. 122—22

6 Claims



1. In a heating boiler for combined firing with liquid fuel and/or solid fuel, comprising a liquid fuel combustion chamber, a solid fuel combustion chamber having a grate, at least

one flue in communication with said chambers and in contact with water, and at least the walls of the solid fuel combustion chamber in contact with water, the improvement comprising a first connection between said liquid fuel combustion chamber and said flue, a second connection between said liquid fuel combustion chamber and said solid fuel combustion chamber, closure means for closing said first connection while opening said second connection to couple said combustion chambers in series through said grate, and for closing said second connection while opening said first connection, whereby the available fuels can be adapted to the heat requirements of said boiler.

4,296,712

TWO-CHAMBER BOILER FOR BURNER FIRING AND SOLID FUEL FIRING

Alfred Vogt, Schaan, Liechtenstein, assignor to Hoval Interliz AG, Vaduz-Neugut, Liechtenstein


Filed Mar. 27, 1980, Ser. No. 134,613

Claims priority, application Fed. Rep. of Germany, Apr. 3, 1979, 2913205

Int. Cl.³ F22B 31/04

U.S. Cl. 122—22

6 Claims



1. A two-chamber boiler comprising
 - a horizontal outer boiler body enclosing a common water region,
 - a burner chamber adapted for a burner firing system and a combustion chamber adapted for a solid fuel firing system being arranged laterally adjacent one another in said outer boiler body in the common water region,
 - two separate horizontal ancillary heating passages disposed in said water region, one of said passages respectively being disposed above said chambers respectively communicating therewith and leading to a flue gas collector of the boiler,
 - a fire grate disposed at the bottom of said boiler body and formed with air passage openings communicating with said combustion chamber,
 - said combustion chamber comprises a horizontally extending hollow body closed at a rear end and having an approximately elliptical cross-section with a vertical major diameter tapering downwards approximately conically to said fire grate, the cross-section of said hollow body below said fire grate transferring into an ash space of box form,
 - a first ancillary heating passage of rectangular cross-section arranged axially parallel to and above said combustion chamber in the boiler water region and communicating with a forward end of said combustion chamber, said first ancillary heating passage having a large cross-sectional width extending horizontally and said first ancillary heating passage having vertically directed ribbing of comb-type cross-section, disposed inside said first ancillary heating passage,
 - said burner chamber comprises a horizontally extending round cylinder closed at a rear end, a longitudinal center line of said burner chamber being substantially at the level of a longitudinal center line of said combustion chamber.

a second ancillary heating passage of rectangular cross-section arranged axially parallel to and above said burner chamber in the boiler water region and communicating with a forward end of said burner chamber, said second ancillary heating passage having a larger cross-sectional width extending horizontally and said second ancillary heating passage having vertically directed ribbing of comb-type cross section disposed inside second ancillary heating passage,

said outer boiler body comprising a metal sheet shaped in one piece by rolling into a hollow body having a noncircular round-like cross-section comprising an upper curve portion, a lower curve portion and two lateral curve portions constituting four curve portions,

three transition curve portions having smaller radii of curvature than said four curve portions, said upper, said lower and said lateral curve portions merging into one another above said two chambers and below said burner chamber via said three transition curve portions, one of said lateral curve portions being laterally adjacent said combustion chamber and the other of said lateral curve portions being laterally adjacent said burner chamber,

said lower curve portion and said one of said lateral curve portions terminating at the ash space of said combustion chamber, and

the height of said other of said lateral curve portions being less than the height of said one of said lateral curve portions.

4,296,713

VAPOR GENERATOR


Edward S. Taylor, Del Mar, Calif., and George W. Hirschle, Wiesendangen, Switzerland, assignors to General Atomic Company, San Diego, Calif.

Filed Feb. 7, 1979, Ser. No. 10,090

Int. Cl.³ F22B 1/18

U.S. Cl. 122—32

7 Claims



1. A vapor generator comprising, a high temperature section having a plurality of substantially straight tubes substantially parallel with each other forming an elongated tube bundle, a low temperature section having a plurality of substantially helical tubes forming an annular tube bundle positioned axially of said high temperature section, said tubes of said low temperature section being comprised of different metals having different coefficients of thermal expansion, said high temperature and low temperature sections being subject to thermal expansion of different amounts, means for directing a heating fluid through one of said tube bundles substantially parallel to the coaxes of said bundles and then through the other of said tube bundles in the opposite direction, said directing means including plate means extending transversely at one end of said vapor generator for turning the heating fluid through a substantially 180° turn, and a plurality of cross-over loops joining the tubes

in said high temperature section to the tubes in said low temperature section, said cross-over loops each having portions of said different metals joined, respectively, to said section having the same metal, said cross-over loops each having a bimetal weld joining said portions of different metals, said bimetal welds being positioned on opposite sides of said plate means from said high temperature and low temperature sections to be out of the flow of the heating fluid.

4,296,714

DUAL PISTON TWO STROKE ENGINE

Bernhard Büchner, Ott-Heinrich-Strasse 25, D-8070 Ingolstadt-Unsernherrn, Fed. Rep. of Germany


Filed Apr. 18, 1980, Ser. No. 141,569

Claims priority, application Fed. Rep. of Germany, Jun. 13, 1979, 2923941

Int. Cl.³ F02B 25/12

U.S. Cl. 123—53 B

12 Claims



1. In a two stroke reciprocating engine, the combination of: first and second cylinders; first and second pistons reciprocally disposed in corresponding ones of said cylinders; a crank chamber connecting said cylinders on corresponding ends thereof; a combustion chamber connecting said cylinders on the ends thereof opposite said corresponding ends; a crank rotatable in said crank chamber; means connecting both of said pistons to said crank such that for one direction of rotation of said crank said first piston precedes said second piston during a reciprocating cycle thereof; a transfer port for transferring at least combustion air from the crank chamber sides of said pistons to the combustion chamber sides of said pistons, said transfer port having first and second inlets in said first and second cylinders respectively and an outlet only in said second cylinder; and control surfaces on said pistons for opening and closing said inlets and outlet such that said second inlet remains open later in said reciprocating cycle than said first inlet to thereby lengthen the period in said reciprocating cycle during which said transfer of at least combustion air may occur.

4,296,715

APPARATUS FOR EXTERNAL COOLING OF AN EXHAUST VALVE

Remi Curtil, Montsault, and Alain Devaux, Saint Mande, both of France, assignors to Societe d'Etudes de Machines Thermiques S.E.M.T., Saint-Denis, France


Filed Feb. 2, 1979, Ser. No. 9,072

Claims priority, application France, Feb. 24, 1978, 78 05399

Int. Cl.³ F01L 1/34

U.S. Cl. 123—90.15

5 Claims



1. Apparatus for improving the external cooling of an exhaust valve of an internal combustion engine having a working piston in a cylinder, an intake valve for admitting air into said cylinder, an exhaust valve for exhausting combustion gases from said cylinder, and operating cams, each having a circular base profile and a main boss with a leading valve opening profile, an intermediate full open profile, and a trailing valve closing profile, for controlling the opening and closing of said intake valve and exhaust valve, respectively, such that the open periods of the intake valve and the exhaust valve normally mutually overlap by a predetermined value, wherein the improvement comprises:

said operating cam of the exhaust valve having a residual lift portion of substantially constant radius, the leading part of which merges smoothly and progressively with the valve closing profile of the main boss of said cam and the trailing part of which merges smoothly and progressively with the circular base profile of the cam, said residual lift portion extending through a circular angle corresponding to at least the major part of the intake valve opening period, and the radial height of the residual lift portion being such that the residual lift portion produces a small free flow section between the valve and its seat relative to the free flow section of the fully open valve.

4,296,716

INTERNAL COMBUSTION ENGINE FOR AN AUTOMOBILE WITH A DIVIDED OIL PAN

Peter Hofbauer, Michael Willmann, and Egon Wundrak, all of Wolfsburg, Fed. Rep. of Germany, assignors to Volkswagenwerk Aktiengesellschaft, Wolfsburg, Fed. Rep. of Germany

Filed May 31, 1979, Ser. No. 44,050

Claims priority, application Fed. Rep. of Germany, Jun. 3, 1978, 2824415

Int. Cl.³ F01M 11/06

U.S. Cl. 123—195 C


12 Claims

1. An internal combustion engine for an automobile with an oil pan divided into two chambers from which two lubricating oil quantities having different temperatures are obtained, the two chambers are in communication with each other and are equipped with suction lines, the bottom of a first one of said chambers being placed at a distance above the bottom of the oil pan, which is also the bottom of the second one of said chambers, characterized in that

at least the bottom region of the oil pan is exposed to the slip stream of the automobile and is designed in a heat-transmitting manner; and

a suction line from each chamber opens into a common delivery line by way of a thermostat valve, said thermostat valve forms a connection means wherein at low oil temperatures, at least predominantly, effects communica-

tion of the delivery line only with the first of the chambers and at oil temperatures above a preselected level, at least



predominantly, effects communication of the delivery line only with the second chamber instead of the first.

4,296,717

DRIVE ARRANGEMENT FOR AUXILIARY AGGREGATES OF AN INTERNAL COMBUSTION ENGINE

Walter Schlagmüller, Schwieberdingen, Fed. Rep. of Germany, assignor to Robert Bosch GmbH, Stuttgart, Fed. Rep. of Germany


Filed Jun. 1, 1979, Ser. No. 44,553

Claims priority, application Fed. Rep. of Germany, Sep. 2, 1978, 2838343

Int. Cl.³ F02F 7/00

U.S. Cl. 123—195 A

8 Claims



1. A drive arrangement of the character described, especially for motor vehicles, comprising a combustion engine having a drive shaft and a cam shaft driven by the drive shaft; a first pulley freely rotatably mounted on said drive shaft; centrifugal clutch means on said drive shaft for connecting said first pulley to said drive shaft when the latter rotates up to a predetermined speed and for disconnecting the drive of said first pulley by said drive shaft when the latter rotates above said predetermined speed; an intermediate pulley having a free wheel coupling driven at least indirectly by said cam shaft; a belt connecting said first pulley with said intermediate pulley; a plurality of auxiliary aggregates each having a shaft and a pulley fixedly mounted thereon, said first pulley, said intermediate pulley and the pulleys of said auxiliary aggregates being located in one plane and said belt connecting said first pulley to said intermediate pulley extending also about the pulleys of said auxiliary aggregates, whereby during rotation of said drive shaft up to said predetermined speed said auxiliary aggregates are driven by said first pulley and when said drive shaft rotates above said predetermined speed said auxiliary aggregates are driven by said intermediate pulley which is at least indirectly driven by said cam shaft.


4,296,718

DIESEL ENGINE SHUTDOWN CONTROL SYSTEM
Edward D. Baugh, and Mark B. Hoffman, both of Union Lake, Mich., assignors to General Motors Corporation, Detroit, Mich.

Filed Sep. 17, 1979, Ser. No. 75,954
Int. Cl.³ F02M 63/02

U.S. Cl. 123—198 D

4 Claims



1. A diesel engine fuel supply and shutdown control system comprising fuel injection means to inject fuel into the engine combustion chambers, a control lever movable into "stop" and "run" positions to respectively prevent or permit fuel injection to the combustion chambers, an engine driven fuel pump capable of generating pressure in either direction of rotation and connected to supply fuel to the fuel injection means from a source of supply, a check valve to prevent reverse fuel flow from the fuel pump to the supply source and shutdown means including a pressure actuator operatively engaging said control lever and responsive to fuel pump pressure to move said lever to its stop position, said actuator being biased toward a nonoperative position that permits location of said lever in its run position, first and second conduit means connecting said actuator with opposite sides of said fuel pump to supply pressure therefrom in either direction of pump operation and selector valve means connected in said first and second conduit means and movable into "on" and "off" positions to control engine operation, said selector valve means being operative in the "on" position to shut off the first conduit from the engine side of the pump and open the second conduit from the supply side of the pump to permit normal engine operation but prevent reverse operation and said selector valve means being operative in the "off" position to shut off the second conduit from the supply side of the pump and open the first conduit from the engine side of the pump to supply pump pressure to the actuator during normal operation and thereby shut down the engine.

4,296,719

MULTIPLE CYLINDER INTERNAL COMBUSTION ENGINE HAVING MIXTURE CUT OFF MEANS
Koichi Takahashi, Fumio Hinata, and Akira Shibana, all of Hiroshima, Japan, assignors to Toyo Kogyo Co., Ltd., Hiroshima, Japan

Filed Sep. 20, 1979, Ser. No. 77,278


Claims priority, application Japan, Sep. 22, 1978, 53/117120; Sep. 25, 1978, 53/118158; Sep. 26, 1978, 53/118778
Int. Cl.³ F02D 17/00

U.S. Cl. 123—198 F

9 Claims

1. Internal combustion engine comprising a plurality of cylinders, intake passage means including first passage means leading to at least one of said cylinders and second passage means leading to the remainder of said cylinders, throttle valve means provided in said intake passage means and having a minimum opening position, means for providing a supply of combustible air and fuel mixture to said first and second passage means, shut-off valve means provided in said first passage

means downstream of said mixture supply means and movable to a closed position for blocking the supply of the mixture to the cylinder associated with said first passage means, means for detecting that the throttle valve means is in the minimum opening position and moving the shut-off valve means to said closed position when the throttle valve means is in the minimum opening position, means for providing a supply of air to



4,296,720


COMBUSTION CHAMBER OF AN INTERNAL COMBUSTION ENGINE

Kiyoshi Nakanishi, Takeshi Okumura, Ryuichi Deguchi, all of Susono, and Toshio Tanahashi, Toyota, all of Japan, assignors to Toyota Jidosha Kogyo Kabushiki Kaisha, Toyota, Japan
Filed May 30, 1979, Ser. No. 43,670

Claims priority, application Japan, Jul. 20, 1978, 53-87662
Int. Cl.³ F02B 23/08; F02P 15/08

U.S. Cl. 123—309

12 Claims



1. An internal combustion engine comprising:
a cylinder block having a cylinder bore therein;
a cylinder head having an inner wall mounted on said cylinder block;
a first raised portion formed on the periphery of the inner wall of said cylinder head, having a flat bottom face and projecting downwardly;
a piston reciprocally movable in said cylinder bore and

having a top face with a flat peripheral portion approachable to said flat bottom face, creating a first squish area therebetween at the end of the compression stroke for spouting out a first squish flow along the top face of said piston, said first squish area comprising an annular area between the flat peripheral portion of the top face of the piston and the flat bottom face of the cylinder head, said first squish area extending substantially along the entire periphery of the top face of said piston;
a combustion chamber defined by the inner wall of the cylinder head and the top face of said piston;
an intake valve movably mounted on said cylinder head in fluid communication with said combustion chamber;
an exhaust valve movably mounted on said cylinder head in fluid communication with said combustion chamber;
a second raised portion formed on the top face of said piston at a position opposite to said first raised portion with respect to an axis of said piston, having a rear face and a front face exposed to said combustion chamber, said rear face being approachable to the inner wall of said cylinder head so as to create a second squish area therebetween at the end of compression stroke for spouting out a second squish flow which moves forward in the upper interior of said combustion chamber in a direction opposite to the spouting direction of said first squish flow, said first and second squish flows cooperating with each other to create a strong swirl motion rotating about a horizontal axis in said combustion chamber;
a third raised portion formed on the inner wall of said cylinder head above said second raised portion having a bottom wall which cooperates with said rear face of said second raised portion for creating said second squish area; and
a pair of spark plugs located in said combustion chamber, comprising a first spark plug located near said first raised portion in a recess formed on the inner wall of said combustion chamber, said recess being located on an extension of said second squish area and extending outwardly beyond a straight line extending between the peripheries of said intake and exhaust valves, and a second spark plug located near said third raised portion, said first squish area extending inwardly from the periphery of the top face of the piston to a continuous, sinuous inner periphery which extends around and is almost vertically under the intake valve, the exhaust valve, and said spark plug recess and adjacent to said second raised portion, the surface area ratio of the sum of the first and second squish areas formed on the inner wall of the cylinder head and the first and second squish areas formed on the top face of the piston to the sum of the cross-sectional area of the cylinder bore and the surface area of the inner wall of the cylinder head, excluding the surface area of the vertical side wall of said first raised portion, is in the range of from 30 to 50 percent.

4,296,721

CONTROL SYSTEM HAVING AN IMPROVED CONDITION RESPONSIVE VALVE CONSTRUCTION
Everett T. Steele, Jr., Knoxville, Tenn., assignor to Robertshaw Controls Company, Richmond, Va.
Division of Ser. No. 808,875, Jun. 22, 1977, Pat. No. 4,147,180.
This application Jan. 10, 1979, Ser. No. 2,381


Int. Cl.³ F02P 5/04

U.S. Cl. 123—407

1 Claim

1. In a control system for an internal combustion engine having a vacuum manifold and a vacuum operated control device that is to be always interconnected to said manifold by a self-contained condition responsive valve construction when the temperature of said engine is above a certain temperature and is to be only substantially interconnected to said manifold through said valve construction when the vacuum value of said manifold is greater than the vacuum value at said control device and the temperature of said engine is below said certain temperature, said self-contained condition responsive valve construction having a check valve means therein that substan-

tially blocks the fluid interconnection between said manifold and said control device when said manifold vacuum value is less than the vacuum value of said control device and said temperature of said engine is below said certain temperature whereby said check valve means forms part of the self-contained structure of said valve construction, said valve construction having valve seat means disposed between a pair of ports to interconnect the same together and having valve member means for opening and closing said valve seat means in response to a condition sensed thereby, one of said ports being interconnected to said manifold and the other of said ports being interconnected to said control device, said valve member means having a by-pass passage means therein for fluidly interconnecting said ports together even though said valve seat means is closed by said valve member means, said by-pass passage means having said check valve means therein to permit fluid flow through said by-pass passage means in only one



direction, said valve construction having a housing means carrying said valve seat means and said valve member means, said valve seat means being annular and said valve member means comprising a plunger that axially moves in said annular valve seat means, said plunger having a free end portion that projects beyond one side of said valve seat means in all positions of said plunger, said by-pass passage means having one end thereof leading to the exterior of said plunger at said free end portion thereof, said check valve means comprising a valve seat in said by-pass passage means at said free end portion of said plunger and a valve member for opening and closing said valve seat, the improvement wherein, said free end portion of said plunger has a restrictor means therein that leads from the exterior of said free end portion to said by-pass passage means intermediate said check valve seat and the other side of said valve seat means to always fluidly interconnect said ports together at a controlled rate.

4,296,722

CONTROL APPARATUS FOR AN INTERNAL COMBUSTION ENGINE


Toshio Furuhashi, and Osamu Abe, both of Ibaraki, Japan, assignors to Hitachi, Ltd., Tokyo, Japan

Filed Jul. 26, 1979, Ser. No. 60,751

Claims priority, application Japan, Jul. 26, 1978, 53-90432
Int. Cl.³ F02B 3/10; G06F 15/20

U.S. Cl. 123—492

13 Claims



1. A control apparatus for an internal combustion engine comprising:

first means for generating a pulse train having a predetermined relation to the angle of rotation of the engine crankshaft, said pulse train including a plurality of reference pulses generated within each time period corresponding to one revolution of the engine crankshaft;

second means for generating a normal fuel injection signal, to control a fuel injector, the time of occurrence of which signal depends upon the time of occurrence of one of said reference pulses;

third means for detecting an accelerating engine condition;

fourth means, coupled to said third means, for detecting whether the accelerating condition has occurred at a time between said one of the reference pulses and an adjacent subsequent reference pulse; and

fifth means for generating a corrective fuel injection signal, the initiation of which is governed by a subsequent to said adjacent subsequent reference pulse in response to the detected information from said fourth means, so that said corrective fuel injection signal does not overlap the normal fuel injection signal.

10. A method of controlling the supply of fuel to an internal combustion engine so as to augment the supply of fuel normally supplied to the engine, in the event of an acceleration condition, comprising the steps of:

- generating a train of pulses in accordance with the rotation of the engine crankshaft, said train of pulses containing a plurality of reference pulses for every one revolution of the engine crankshaft;
- generating a first fuel supply signal to control the normal supply of fuel to the engine, the time of occurrence of which is governed by one of said reference pulses;
- detecting an acceleration condition of the engine;
- detecting whether the occurrence of the acceleration condition of the engine has occurred at a time between said one of said reference pulses and a subsequent adjacent reference pulse; and
- generating a second fuel supply signal the time of occurrence of which is synchronized with or subsequent to said subsequent adjacent reference pulse, whereby the supply of fuel to the engine is augmented so as not to overlap the normal supply of fuel to the engine.

4,296,723

ENGINE FUEL SYSTEM WITH FUEL/WATER SEPARATION

Frederic C. Aldrich, Lansing, Mich., assignor to General Motors Corporation, Detroit, Mich.

Filed Dec. 17, 1979, Ser. No. 104,308

Int. Cl.³ F02M 55/00; B01D 17/00


U.S. Cl. 123—510

1 Claim

1. A liquid fuel supply system for an engine in which the fuel may have some water entrained therein which should be removed before the fuel is used in the engine, said system comprising:

- a fuel storage tank having a fuel inlet, a fuel outlet, a return inlet and means for detecting a predetermined level of water in the tank and alerting the engine operator that the predetermined water level has been reached;
- a fuel pump connected with said fuel outlet to receive fuel from said tank and when operating pressurizing the fuel so received;
- a fuel/water separator having an inlet receiving pressurized fuel from said fuel pump, means separating the fuel and any water entrained in the fuel received from the fuel pump, a first outlet delivering pressurized fuel from said separating means to said engine for use therein, a second outlet including orifice means receiving water from said separating means, said second outlet being connected to

said tank return inlet for returning pressurized separated water to said tank;



said separated water being retained in said tank and activating said detecting and alerting means when said predetermined water level in said tank is reached; and means for removing water from said tank.

4,296,724

INTERNAL COMBUSTION ENGINE

Haruhiko Iizuka, Yokosuka, and Fukashi Sugawara, Yokohama, both of Japan, assignors to Nissan Motor Company, Limited, Yokohama, Japan


Filed Dec. 28, 1979, Ser. No. 108,228

Claims priority, application Japan, Jan. 8, 1979, 54-1186

Int. Cl.³ F02M 25/06

U.S. Cl. 123—568

8 Claims



1. An internal combustion engine comprising:

- a plurality of cylinders split into first and second groups;
- an intake passage provided therein with a throttle valve and being divided downstream of said throttle valve into first and second branches, said first branch communicating with said first group of cylinders, and said second branch communicating with said second group of cylinders;
- an exhaust passage having its upstream portion divided into first and second branches, said first branch communicating with said first group of cylinders, and said second branch communicating with said second group of cylinders;
- an EGR passage having its one end opening into said second branch of said exhaust passage and the other end opening into said second branch of said intake passage;
- control means for providing a first signal under high

engine load conditions and a second signal under low engine load conditions;

- first valve means provided in said second branch of said exhaust passage downstream of the opening of said EGR passage, said first valve means being responsive to the first signal for opening said second branch of said exhaust passage and being responsive to the second signal for closing the same;
- second valve means provided in said second branch of said intake passage, said second valve means being responsive to the first signal for opening said second branch of said intake passage and being responsive to the second signal therefrom for closing the same; and
- third valve means provided in said EGR passage, said third valve means being responsive to the first signal for closing said EGR passage and being responsive to the second signal for opening the same.

4,296,725

ARCHERY BOW IMPROVEMENT AND CAMERA THEREFOR


Ronald J. Broderick, 3183 S. 8240 West, Magna, Utah 84044

Filed Jul. 27, 1979, Ser. No. 61,483

Int. Cl.³ F41B 5/00

U.S. Cl. 124—24 R

3 Claims



1. In combination, an archery bow, and forwardly-facing camera means attached to said archery bow, said camera means comprising a camera, a padded case encasing said camera and having aperture means accommodating exposure-functioning of said camera, said case being provided with spring-biased means for effecting selective camera film-advance, said case also being provided with shutter-trip control means adjustably secured relative to said archery bow.

4,296,726

COLLAPSIBLE CHARCOAL LIGHTING HOLDER


Jim Ross, P.O. Box 5204, and John Vilicich, 836 S. Gaffey St., both of San Pedro, Calif. 90731

Filed Nov. 26, 1979, Ser. No. 97,518

Int. Cl.³ A47J 37/00

U.S. Cl. 126—25 B

6 Claims



1. An operably collapsible device for holding charcoal in a manner to facilitate ignition, comprising a series of successively larger, nesting, similar, plane geometric shapes at least three slidable interconnecting means spaced equidis-

tant around the circumference of said plane geometric shapes such that, when the largest of said plane geometric shapes is suspended horizontally, the series of shapes depend therefrom, spaced apart approximately equally, to form an inverted truncated cone or pyramid, and when said plane geometric shapes are allowed to rest on a horizontal surface said plane geometric shapes nest together in one horizontal plane

at least two support members foldably connected to the largest of said plane geometric shapes such that

as a first alternative, said support members may be positioned fully erect causing the largest said plane geometric shape be suspended approximately horizontally, with the remaining plane geometric shapes depending therefrom to form an inverted truncated cone or pyramid, the lowest portion of which is suspended slightly above the plane of the lower extremities of said support members, and

as a second alternative, said support members may be positioned extending radially out from the largest of said plane geometric shapes, and

as a third alternative, said support members may be positioned folded over said plane geometric shapes.

4,296,727

FURNACE MONITORING SYSTEM



Edward L. Bryan, Dallas, Tex., assignor to Micro-Burner Systems Corporation, Addison, Tex.

Filed Apr. 2, 1980, Ser. No. 136,719

Int. Cl.³ F24H 3/00; G01L 3/26; F23N 1/00

U.S. Cl. 126—116 A

8 Claims



1. A monitoring and display apparatus for use in combination with a heating system of the type having a combustion chamber, adjustable means for supplying air to said combustion chamber to support combustion, an exhaust duct for exhausting combustion products from the combustion chamber, a fuel input nozzle and conduit means connectable to a fuel source for supplying fuel to the combustion chamber, and a heat exchanger in the gas flow path between the combustion chamber and the exhaust duct for heating a fluid medium, the apparatus comprising

first and second transducer means for sensing the temperatures at the combustion chamber and the exhaust duct, respectively, and for producing electrical signals representative of said temperature;

third transducer means coupled to said conduit means for

sensing the rate of flow of fuel to said fuel input nozzle and;
 logic display means electrically connected to said transducer means for calculating and selectively displaying parameters representative of the operation of said heating system comprising a clock;
 memory means for storing digital data representative of the temperature and flow rate parameters sensed by said transducers and of preselected limit values for selected ones of said parameters;
 input means including a keyboard for manually supplying said preselected limit values to said memory means;
 calculator means responsive to said clock and to the sensed parameters stored in said memory means for calculating fuel usage per unit time and for supplying signal representative thereof to said memory means; and
 alarm means for periodically comparing said limit values with the sensed parameters and for providing a perceivable indication when said limit values are exceeded.

4,296,728

ENERGY SAVING POTS, PANS AND ADAPTER

Robert A. Hofstetter, 2436 Birch Log Way, Hacienda Heights, Calif. 91745

Filed Oct. 30, 1978, Ser. No. 899,984

Int. Cl.³ A47J 27/00; B65D 8/06

U.S. Cl. 126—376

1 Claim



1. An energy saving cooking vessel, comprising a container member including a bottom wall and a first side wall extending upwardly from said bottom wall, a continuous, peripheral, transverse wall extending radially outwardly from the top periphery of said first side wall, a second wall extending downwardly from the outer periphery of said transverse wall, said second side wall surrounding and spaced from said first side wall from said outer periphery to substantially the same plane as said bottom wall, the space defined between the first and second side walls being axially opened at the bottom thereof while being otherwise enclosed, said second side wall and said transverse wall together defining heat shield means to retain rising heat from a stove burner entering said space to thereby conserve energy needed during cooking, a heat shield extension adjustably attached by securement means to said cooking vessel at the lower portion of said second side wall, said securement means including said second side wall and said heat shield extension each being screw-threaded for adjustably telescoping one within the other by relative rotary movement of the vessel and extension, said heat shield extension allowing said cooking vessel to be elevated at different heights and aiding in retaining rising heat within said space at the elevated heights.

4,296,729

SOLAR HOT WATER HEATING SYSTEM

George H. Cooper, Bridgton, Me., assignor to Suntime, Inc., Bridgton, Me.

Filed Feb. 4, 1980, Ser. No. 118,486



Int. Cl.³ F24J 3/02; F24D 11/00

U.S. Cl. 126—421

8 Claims

7. A solar hot water heating system comprising a solar heat collector
 a primary water heating and storage tank located at a level above said collector
 a heat exchanger within said tank
 means for circulating a heat absorbing medium through said

collector and heat exchanger so that it receives heat in the collector and releases its heat in the heat exchanger and returns by gravity to the collector
 a secondary water preheating and storage tank located at a level below said collector and said primary tank
 the inlet of said secondary tank being adapted to be connected to a source of cold water under pressure and having its outlet connected to the inlet of said primary tank
 means for recirculating hot water from said primary tank to said secondary tank,



said recirculating means comprising a conduit connecting the hot water outlet of said primary tank to the inlet of said secondary tank, a circulating pump in said conduit and a check valve in said conduit to prevent reverse flow of cold water therethrough, and
 control means responsive to a condition in said primary tank for activating and deactivating said pump so that only surplus hot water from said primary tank will be returned to said secondary tank.

4,296,730

CONTROL SYSTEM FOR A SOLAR STEAM GENERATOR

Allan J. Zadiraka, Akron, Ohio, assignor to The Babcock & Wilcox Company, New Orleans, La.

Division of Ser. No. 941,700, Sep. 12, 1978. This application

May 5, 1980, Ser. No. 146,925



Int. Cl.³ F24J 3/00

U.S. Cl. 126—421

5 Claims

1. A control system for a solar steam generator comprising: a series of solar-heated panels connected together to allow fluid flow therethrough;
 first measuring means for measuring the temperature of the fluid at one point in said series of solar-heated panels and establishing a signal indicative thereof;
 second measuring means for measuring the temperature of the fluid at another point in said series of solar-heated panels and establishing a signal indicative thereof;
 attemperament means for controllably adding attemperament fluid into said series of solar-heated panels;
 first combining means for combining the temperature measurement signals of said first and second means to establish a first control signal for controlling the amount of flow through said attemperament means;
 variable fluid flow means for providing a variable flow of fluid through said solar-heated panels;
 fluid flow measuring means for measuring the amount of

fluid flow through said solar-heated panels and establishing a signal indicative thereof; and
 second combining means for combining said first control



signal from said first combining means with the signal from said fluid flow measuring means to establish a second control signal for controlling fluid flow from said variable fluid flow means.

4,296,731

TRACKING BOOSTER AND MULTIPLE MIRROR CONCENTRATOR FLOATING COLLECTOR


C. Brent Cluff, 5525 N. Grande, Tucson, Ariz. 85704

Continuation-in-part of Ser. No. 836,356, Sep. 26, 1977, Pat. No. 4,148,301. This application Jun. 1, 1978, Ser. No. 911,434

Int. Cl.³ F24J 3/02

U.S. Cl. 126—424

15 Claims



1. A heat exchange means comprising:
 a floating platform,
 means for positioning said platform for arcuate movement through a given path when floating on a liquid,
 a plurality of arrays of juxtapositioned parallel arranged reflectors each mounted on the top of said platform,
 at least one solar ray collector panel mounted on each array

to extend longitudinally of said reflectors and disposed with its axis in the focal zone of said reflectors,
 each array of said reflectors comprising at least one pair of reflector surfaces with one of each pair being angularly arranged on different sides of a given collector panel for directing the solar rays toward the collector panel, and
 platform actuating means for moving said platform about an arcuate path for tracking the sun in an azimuthal mode.

4,296,732

SOLAR RADIATION COLLECTOR

Winfried Bernhardt, Edgard Grundmann, and Rudolf Kroll, all of Wolfsburg, Fed. Rep. of Germany, assignors to Volkswagenwerk AG, Wolfsburg, Fed. Rep. of Germany


Filed Jan. 29, 1980, Ser. No. 116,397

Claims priority, application Fed. Rep. of Germany, Feb. 1, 1979, 2903775

Int. Cl.³ F24J 3/02

U.S. Cl. 126—426

4 Claims



1. In a solar radiation collector composed of a mat formed of a black foil member and a radiation pervious foil member, the two members being joined together along the outer edges of the mat and at interior locations of the mat to form an extended flow path and an inlet and outlet for a fluid heat carrier medium, the collector further including cover means connected to the mat along opposed edges thereof and arranged to be disposed in the path of solar radiation toward the mat with an air space being defined between the mat and the cover means, the improvement wherein said cover means includes flexible mounting means formed adjacent opposed edges thereof for holding at least one radiation pervious pane and at least one reflecting panel, and said flexible mounting means and said mat are dimensioned such that, when such pane and panel are held by said flexible mounting means and said mat is filled with such carrier medium, said flexible mounting means holds the pane and panel in relative positions such that the pane, the panel and said mat constitute the legs of a triangle enclosing the air space.

4,296,733

HEATING, LIGHTING AND VENTILATION SYSTEMS

Norman B. Saunders, 15 Ellis Rd., Weston, Mass. 02193

Filed Aug. 5, 1976, Ser. No. 712,098

Int. Cl.³ F24J 3/02




U.S. Cl. 126—428

30 Claims

1. A device for controlling the amount of incoming solar radiation entering an enclosed structure and for reducing the amount of interior heat radiation loss from said structure, said device comprising, in combination:
 a first plurality of substantially flat members each substantially reflective to said solar radiation;
 a second plurality of substantially flat members, each substantially transmissive to said solar radiation; means for securing said first and second plurality of substantially flat members to one another and to said enclosed structure so that said members of said first plurality are oriented in substantially horizontal parallel planes between adjacent members of said

second plurality and members of said second plurality are oriented in substantially vertical parallel planes between adjacent members of said first plurality so as to form a stair-case-like construction, and so that said construction is inclined from the top of said construction to the bottom of said construction toward the equator and so that said incoming solar radiation, the direction of which varies according to the altitude and azimuth of the sun, is transmitted at least in part directly through said members of said second plurality when the sun is at average winter altitudes and substantially reflected from said members of said first plurality away from said enclosed structure when the sun is at average summer altitudes; and

a pair of panel assemblies mountable on said enclosed structure so as to be spaced and disposed parallel to one another on the interior and exterior sides of said first and second plurality of said members.



22. Apparatus for controlling the amount of solar radiation entering an enclosed structure comprising, in combination; a plurality of window units, each of said units including means for reducing the amount of heat transfer through said unit, at least two panels transmissive to said solar radiation, and means for drawing air from the exterior of said structure along a path defined between said panels to the interior of said structure so as to reduce the loss of heat from the interior of said structure through said units; and means disposable around the perimeter of said structure for providing air exterior of and from all sides of said structure to said path defined between said panels of each unit so as to substantially equalize the pressure of said air drawn through said units.

24. Apparatus for controlling the amount of direct solar heat and light entering an enclosed structure, said apparatus comprising, in combination;

absorbing at least a part of said direct solar heat and for reradiating stored heat into the interior of said enclosed structure; and

a plurality of adjustable louvers disposed between said tank storage means and said interior of said enclosed structure for controlling the heat and light transfer between the sun and the interior of said enclosed structure and the heat and light transfer between said tank means and the interior of said enclosed structure.

28. For use in an enclosed structure, a device including a window unit comprising:

at least two spaced apart panels transmissive to solar radiation; a retractable shade disposed between said panels for controlling the amount of said solar radiation transmitted through said panels, said shade being retractable to a retracted position wherein solar radiation is transmitted through said panels and extendable to an extended position so as to reduce the amount of solar radiation transmitted through said panels;

means for drawing air along a path from the exterior of said enclosed structure, through the space between said panels to the interior of said enclosed structure so as to reduce the loss of heat from the interior of said enclosure to the exterior of said enclosure; and

means for guiding said shade so that when said shade is extended to said extended position said shade assumes a convex, contoured shape to define said path for said air between said panels.

4,296,734

SOLAR COLLECTOR


Robert L. Nevins, Rte. 28A, Boiseville, N.Y. 12412

Filed Mar. 10, 1980, Ser. No. 129,033

Int. Cl.³ F24J 3/02

U.S. Cl. 126—431

2 Claims



1. A heating and cooling structure comprising a pair of spaced translucent glazes, a frame for mounting said spaced glazes, said frame having members at two opposite ends of said glazes for engaging said glazes therebetween, passageways formed in said oppositely disposed members to selectively establish fluid communication from either of the sides of said members with the volume established within said frame, a heat sink mounted within said frame between said spaced translucent glazes in order to absorb radiant solar heat applied to said structure and to transfer the heat to said fluid flowing through said volume established within said frame from either of said selected sides of said frame members, said heat sink being a mesh disposed within said frame volume, said mesh being generally coextensive with said spaced glazes, a laterally slidable vent cover received in said frame for movement there-within, and a plurality of uniformly spaced apertures formed in said vent cover for selective alignment and misalignment with said frame passageways in order to promote and to stop fluid

flow between the side of the frame member in which said vent cover is received and the volume established within said frame.

4,296,735

DEVICES TO EXPLOIT SOLAR ENERGY

Alfredo B. Llorach, 17-B Bellavista St., San Antonio Abad (Ibiza), Spain



Filed Oct. 13, 1978, Ser. No. 951,240

Claims priority, application Spain, Oct. 20, 1977, 463.413; Sep. 22, 1978, 473.620

Int. Cl.³ F24J 3/02; G02B 11/04, 5/08

U.S. Cl. 126—438

6 Claims



1. An improved solar collector comprising, in combination, a plurality of concave reflecting elements, each of said reflecting elements being disposed adjacent to another reflecting element to define a panel, each of said reflecting elements having an identical reflecting surface with a focal point, said focal point of each other reflecting surface not coinciding, a solar radiation absorbing element having an absorbing surface disposed on said focal points of each of said elements, means for directing a fluid medium through the radiation absorbing element to convey heat from said absorbing element, each of said reflecting elements having a periphery defined by a projection of a polygon so that the periphery of all the reflecting elements match the periphery of their adjacent reflecting elements, the concavity of each of said adjacent elements contacting each other along the periphery of each polygon, the total surface areas of the reflecting surface of said elements not being less than the area defined by the periphery of said panel, the concavity of each of said reflecting elements being defined by a predetermined curvature to achieve in the solar beam reflecting a focal zone above the reflection surface thereof due to the course of the sun, and said absorbing surface of said absorbing element being coincident with said focal zone.

4,296,736

FOLDED PLATE SOLAR ENERGY COLLECTOR

Olaf Soot, 9 Tomahawk La., Greenwich, Conn. 06830

Filed Dec. 3, 1979, Ser. No. 100,016



Int. Cl.³ F24J 3/02

U.S. Cl. 126—438

15 Claims

5. A wall or roof panel for use in a building in a solar collector system, comprising an elongated folded plate structural member composed of at least one collector first plate element and at least one adjoining connecting second plate element alternately arranged in a substantially zig-zag manner, structural means connecting together the adjacent edges of each collector first plate with the adjoining connecting second plate, the plane of the collector first plate extending at a predetermined tilt angle with respect to the plane of the second plate whereby the collector first plate can be located transverse to impinging solar energy when the panel is mounted in operative

position, said collector first plate having an areal portion absorbent of solar energy and a wall transparent to solar energy mounted in front of the absorbent portion, means for heat insulating the absorbent portion from ambient temperature, and means providing fluid flow across the collector first plate and in heat-exchange relationship with the absorbent portion, whereby solar energy when impinging on said transparent wall will be transmitted therethrough to be absorbed by the absor-



bent portion which in turn transfers heat to the fluid passing across the collector first plate, said folded plate structural member and said edge connections between connecting first and second plate elements forming a stiffened integral structure which is substantially self-supporting and capable of functioning as a load-bearing solar-energy-receiving structural element when installed in said operative position as an integral wall or roof panel of a building.

4,296,737

PARABOLIC TROUGH CONCENTRATING SOLAR COLLECTOR


John K. Silk, Wellesley, Mass., assignor to American Science and Engineering, Inc., Cambridge, Mass.

Filed Dec. 5, 1979, Ser. No. 100,612

Int. Cl.³ F24J 3/02

U.S. Cl. 126—438

11 Claims



1. A concentrating solar collector for use in a solar energy system, said collector comprising a radiation reflective surface having the configuration of a paraboloid of translation, said paraboloid defining a focal line that is spaced from the parabolic cross section of said surface and extends in a direction transverse to the axis of said parabolic cross section, one of the outermost extremities of said reflective surface being defined by an elongated lip that is positioned substantially in a plane passing through said focal line and oriented perpendicular to said axis, and means for supporting an elongated solar energy

receiver along said focal line, said receiver having an elongated entrance aperture of fixed dimensions therein for admission of solar energy reflected by said surface, said entrance aperture being oriented at an angle to said axis, the plane of said entrance aperture being displaced from said axis by a fixed angle in the range of 20° to 40°.

8. A concentrating solar collector for use in a solar energy system, comprising a radiation reflective surface which includes a pair of paraboloids, the axial extent of each said paraboloid being substantially confined between a first plane lying along the axis of the parabolic cross section of said paraboloid and passing through the apex of said paraboloid and a second plane oriented perpendicular to said axis and passing through the focus of said parabolic cross section, said collector including a solar energy receiver having a pair of elongated fixed entrance apertures therein which are oppositely disposed to one another and which are associated with said pair of paraboloids respectively, each of said apertures being disposed substantially along the focal line of an associated one of said paraboloids for the admission to said receiver of solar energy reflected by said paraboloid with the plane of said entrance aperture being disposed at an angle to said axis, and said pair of paraboloids being interconnected to one another adjacent their respective apices by an intervening elongated flat region which separates said apices from one another by a distance substantially equal to the diameter of said solar energy receiver.


4,296,738

CYLINDRICAL SOLAR ENERGY COLLECTOR
Wallace G. Kelton, 1748 NE. 58th St., Fort Lauderdale, Fla. 33334

Filed Jun. 3, 1980, Ser. No. 156,147
Int. Cl.³ F24J 3/02; F28F 1/00

U.S. Cl. 126—443

15 Claims



1. A solar energy collector for utilizing solar energy to heat a working fluid, said solar energy collector comprising:
 - a generally hollow metallic core cylinder having a working fluid inlet at one end thereof and closure means fitted across the other end thereof;
 - a single metallic return conduit means having an inlet end tapped into said core cylinder in a posture generally at the other end of said core cylinder and a fluid outlet end extending generally adjacent to said inlet end of said core cylinder, said return conduit means being wrapped in intimate heat exchange contact about said core cylinder;
 - transparent cylindrical tube means coaxially mounted about said core cylinder and having a diameter sufficiently greater than said core cylinder such that a peripheral space exists between the interior of said transparent cylinder and the exterior of said return conduit means wrapped about said core cylinder; and
 - annular means at each end of said transparent cylinder means and said core cylinder for maintaining the spatial coaxial

relationship of said core cylinder within said transparent cylindrical tube means and for forming an annular air insulation chamber around said core cylinder and said metallic return conduit means, wherein working fluid may be pumped into said core cylinder, pass through said core cylinder and said metallic return conduit within said transparent tube means and be heated by solar energy within the air insulation envelope.



4,296,739

SOLAR COLLECTOR USING COTTON SEED OIL TO TRANSFER HEAT TO HEAVY OIL WELLS
Gaines H. Bolding, Box 389, Farmington, N. Mex. 87401
Filed Jun. 23, 1980, Ser. No. 162,367

Int. Cl.³ F24J 3/02

U.S. Cl. 126—444

3 Claims



1. A solar collector having a generally truncated pyramid shape comprising a top, a bottom and four side panels wherein: each side panel is constructed of a heat conductive metal, and has a center plate, an interior plate and an exterior plate, and; the interior plate is dimpled and the exterior plate is dimpled and the center plate is flat, and the sides of each panel are sealed and a plurality of outlet ports are sealed into the top of each panel, and a plurality of inlet ports are sealed into the bottom of each panel, and the panels are mounted in a pyramid frame, and the top and the bottom of the collector are sealed with non conductive material, and a suitable heat transfer fluid is forced to pass between the exterior plate and center plate, and between the interior plate and center plate, and wherein the collector is connected to circulating pipes of the system using heat.

4,296,740


MODULAR SOLAR INSOLATION PANELS
Milton Meckler, 16348 Tupper St., Sepulveda, Calif. 91343
Continuation-in-part of Ser. No. 828,773, Aug. 29, 1977, Pat. No. 4,165,036. This application Jun. 26, 1979, Ser. No. 52,434
Int. Cl.³ F24J 3/02

U.S. Cl. 126—448

22 Claims

1. A solar insulation panel for installation upon an inclined roof plane substantially normal to the plane of the sun's traverse across the sky, and including: a multiplicity of transparent light focusing tubes disposed in substantially normal relation to the traverse plane of the sun and extending between spaced headers and open therethrough for the transport of fluid media therein, the transport tubes having elongated prismatic lens walls exposed to the sun's rays and focused to con-

dense the sun's rays into the fluid media within the tubes to absorb heat during the sun's traverse across the sky, and a



structural backing of insulation material underlying the tubes mounted thereto and secured to the roof.

4,296,741


SOLAR ENERGY COLLECTING PANEL ASSEMBLY
Willard J. Harder, Minneapolis, Minn., assignor to Bethany Fellowship, Inc., Minneapolis, Minn.

Filed Feb. 26, 1979, Ser. No. 15,313

Int. Cl.³ F24J 3/02

U.S. Cl. 126—449

22 Claims



1. A solar energy collector unit comprising: an elongated generally flat plate having a first side, a second side, a first side edge, and a second side edge, a plurality of ribs secured to and projected away from the first side of the plate, said ribs extended in the longitudinal direction of the plate and disposed generally parallel to each other and having substantially the same height, a plurality of fins secured to and projected away from the second side of the plate, said fins extended in the longitudinal direction of the plate and disposed generally parallel to each other, each rib is a flat continuous rib member, said rib members being laterally spaced from each other a distance greater than the height of a rib, each fin is a flat continuous fin member, each of said rib members being in longitudinal alignment with a fin member, a longitudinal single foot secured to and projected away from the second side of the plate, said foot having a height greater than the height of the fins, first means on the first side edge of the plate adapted to be connected to a first adjacent collector unit, said first means comprising a flange extended generally parallel with said plate and spaced therefrom forming a longitudinal groove extended in a direction generally parallel to the plate, and second means on the second side edge of the collector unit adapted to be connected to a second adjacent collector unit, said second means comprising a tongue projected laterally away from the plate and extended in a direction generally parallel to the plate, said tongue adapted to fit into a longitudinal groove of the second adjacent collector unit.

4,296,742

FLAT SOLAR ENERGY COLLECTOR WITH LOW HEAT CONTACT BETWEEN ABSORBER AND EDGE OF COLLECTOR


Eckart Hussmann, Ober-Olm, Fed. Rep. of Germany, assignor to JENAer Glaswerk Schott & Gen., Fed. Rep. of Germany
Filed Jun. 6, 1978, Ser. No. 913,189

Claims priority, application Fed. Rep. of Germany, Jun. 7, 1977, 2725633

Int. Cl.³ F24J 3/02

U.S. Cl. 126—450

9 Claims



1. A gas-tight solar collector unit for converting solar radiation into heat, said solar collector comprising: a solar energy and infrared absorber means; a cover means transparent to radiant solar energy overlying and in a spaced relation to said absorber means; edge structure means for maintaining said absorber means and cover means in spaced relation to provide an airspace located therebetween; and said absorber means having means for connecting said absorber means to said edge structure means such that no direct thermal contact exists between the edge of said absorber means and said edge structure means and providing a gas-tight seal for said airspace.

4,296,743

HYPERBARIC OXYGEN CHAMBER WITH FLUIDIC CONTROL


Robert A. Lasley, 11 Wardell Ave., Rumson, N.J. 01760

Filed May 24, 1979, Ser. No. 42,114

Int. Cl.³ A61H 31/02

U.S. Cl. 128—30

2 Claims



1. A low pressure hyperbaric device for treatment of a patient including a two part chamber with means for holding the two parts in assembled and sealed condition, the chamber having an entrance adapted to allow the introduction of a body part, means associated with the entrance to seal the body part to thereby provide an air tight chamber, a pressurized source of oxygen and means for cyclically pressurizing the hyperbaric chamber with oxygen and exhausting the hyperbaric chamber said means comprising: timing means for controlling overall treatment time connected in series with the pressurized source of oxygen.

said timing means including an on-off valve for starting and stopping flow, a spool valve fluidly connected to the timing means, said spool valve being moved to the open position upon receiving the oxygen flow from the valve in the timing means, a flow control device connected on its inlet side to the spool valve and to the hyperbaric chamber on its outlet side, said flow control device controlling flow into the hyperbaric chamber, a second flow line extending from the spool valve to an exhaust valve for the hyperbaric chamber, pressure control means having an inlet in communication with the pressure in the hyperbaric chamber and an outlet in communication with the spool valve whereby when the prescribed pressure is reached within the hyperbaric chamber the pressure control means closes the spool valve thereby releasing the exhaust valve so that the hyperbaric chamber pressure will be exhausted and whereby upon the return of the chamber to ambient pressure the spool valve is returned to open position for a new cycle.


4,296,744

DYNAMIC PATELLAR BRACE

Pasquale M. Palumbo, 906 Frome La., McLean, Va. 22101
Continuation of Ser. No. 949,121, Oct. 6, 1978, abandoned. This application May 27, 1980, Ser. No. 153,708
Int. Cl.³ A61F 3/00

U.S. Cl. 128—80 C

12 Claims



1. A dynamic patellar brace for preventing subluxation of a patella throughout the complete physiologic range of flexion and movement of the knee comprising:
means for bracing the patella;
means for maintaining said patellar bracing means positioned laterally of the patella throughout the complete physiologic range of flexion and movement of the knee when the brace is in use; and
means for causing said patellar bracing means positioned laterally of the patella to apply a resultant force in the medial direction to the patella throughout the complete physiologic range of flexion and movement of the knee when the brace is in use.

4,296,745

SURGICAL SEALANT COMPOSITION

Christopher D. Raymond, High Wycombe, England, assignor to G. D. Searle & Co., Skokie, Ill.
Filed Nov. 13, 1979, Ser. No. 93,351
Claims priority, application United Kingdom, Nov. 20, 1978, 45281/78

Int. Cl.³ A61L 15/00

U.S. Cl. 128—156

10 Claims

1. An adhesive surgical dressing which comprises a backing material provided on one side with a composition comprising per 100 parts, by weight, of a non-biodegradable, tacky, polymeric binding agent, selected from a group consisting of polyisoprene, polyurethane, silicone, and polyisobutylene, from 12 to 25 parts, by weight, of an inert reinforcing filler and a coating on at least the intended skin contacting face of the dressing

of a non-biodegradable, water-activated polyacrylamide adhesive/thickener.

4,296,746

DISPOSABLE FULL-FACE SURGICAL MASK


Stanley I. Mason, Jr., Weston, and Michael D. Handler, Ridgefield, both of Conn., assignors to Surgikos, New Brunswick, N.J.

Filed Dec. 18, 1979, Ser. No. 104,948

Int. Cl.³ A62B 7/10

U.S. Cl. 128—201.15

11 Claims



9. A comfortable, lightweight, disposable full face mask adapted to be worn without claustrophobic effect, said face mask comprising:

a shell having an upper portion and a lower portion and formed of transparent plastic material having a generally oval periphery having a rim extending outwardly of the periphery at a substantial angle to the periphery;
the upper portion of the mask having vent means to dissipate heat and moisture, said vent means including a filtration means to prevent escape of particulate matter through said vent means,
the lower portion of the mask covering the mouth of the wearer and having a region comprising an air filtration medium which is an effective bacterial filtration medium, a strip of soft, flexible material fixed to said rim along the periphery and extending inwardly of said rim; and
means for securing said face mask on the head of the wearer such that, when said mask is worn, said strip is hingedly flexed and lightly compressed against the head of a wearer with said shell covering the face of a wearer but positioned from a wearer's face.

4,296,747

CATH-A-JET


Robert W. Ogle, Newport Beach, Calif., assignor to IMS Limited, El Monte, Calif.

Filed Feb. 11, 1980, Ser. No. 120,532

Int. Cl.³ A61M 5/00

U.S. Cl. 128—220

5 Claims



1. A device for introducing fluid into catheters of the type which are partially receivable in the human urethra to drain urine from the bladder and have a free end fitment and/or a pierceable injection site, comprising:

syringe means actuatable to expel fluid from an outlet at one end thereof;
connector means extending from said one end of the syringe

means and defining an axial fluid passage communicating with said outlet;
a first axially tapered surface portion of the connector means receivable in sealing relationship within the free end fitments of urethral catheters;
a second axially tapered surface portion of the connector means engageable in sealing relationship with a luer needle fitment;
said second tapered surface portion being smaller in diameter than and positioned outwardly of said first tapered surface portion; and
a transition surface portion between the first and second tapered surface portions, said transition surface portion comprising a step in the diameter of the connector means, whereby fluid can be introduced into urethral catheters either through a free end fitment or an injection site for passage toward the human urethra.

4,296,748

UNDERWATER DRAINAGE APPARATUS WITH SEPARABLE SUCTION CONTROL CHAMBER


Leonard D. Kurtz, Woodmere, and Robert E. Bidwell, Melville, both of N.Y., assignors to BioResearch Inc., Farmingdale, N.Y.

Filed Jun. 27, 1979, Ser. No. 52,825

Int. Cl.³ A61M 1/00

U.S. Cl. 128—276

5 Claims



1. An underwater drainage apparatus comprising an integral container having an inlet adapted to be connected to the pleural cavity of a patient, an underwater seal chamber disposed beneath said inlet, a tube extending from said inlet into the lower end of said underwater seal chamber, a collection chamber for receiving fluid overflowing from said underwater seal chamber, an outlet in the upper end of said container, an outlet chamber surrounding said outlet within the container, a passageway interconnecting said outlet chamber with said underwater seal chamber, diaphragm means disposed within said outlet chamber, a separable suction control chamber attachable to said integral container, said suction control chamber including a U tube manometer having a small arm open to atmosphere and a large arm, a passageway extending downwardly from the upper end of the large arm of the U tube manometer and needle means having a bore therethrough disposed at the lower end of said passageway.

4,296,749

COLOSTOMY APPLIANCE

Edward J. Pontifex, Virginia Beach, Va., assignor to Louis B. Fine, Norfolk, Va., a part interest

Filed Jul. 18, 1980, Ser. No. 170,057

Int. Cl.³ A61F 5/44

U.S. Cl. 128—283

17 Claims

1. A colostomy appliance comprising, in combination, a first pouch formed from first and second impermeate wall members of flexible plastic material connected together to form a flexible generally flat elongated container having a closed top and an open bottom,

an inlet opening formed in the first sheet of the first pouch in downwardly spaced relation to the closed top, attaching means surrounding the inlet opening for attaching the first pouch to the body of the person using the appliance,
a gas outlet opening formed in the second sheet of the first pouch adjacent the closed top thereof,
means for closing the open bottom end of the first pouch, a second pouch formed from flexible synthetic resin sheet material and having a gas inlet opening therein, and



coupling means for releasably connecting the gas inlet opening of the second pouch to the gas outlet opening of the first pouch and providing a sealed gas flow path therebetween,
the coupling means including valve means for closing the gas outlet opening and the gas inlet opening when the gas inlet opening of the second pouch is not connected to the gas outlet opening of the first pouch.

4,296,750

REFASTENABLE PRESSURE-SENSITIVE TAPE CLOSURE SYSTEM FOR DISPOSABLE DIAPERS AND METHOD FOR ITS MANUFACTURE


Lin-Sun Woon, Appleton, and John C. Wilson, Neenah, both of Wis., assignors to Kimberly-Clark Corporation, Neenah, Wis.

Filed Jun. 22, 1979, Ser. No. 51,048

Int. Cl.³ A41B 13/02

U.S. Cl. 128—287

9 Claims



1. A pressure-sensitive tape closure system for disposable diapers, said diaper having in combination:
a fluid permeable facing sheet;
a backing sheet of a thin polyolefin film attached to the facing sheet along the periphery of the latter;
an absorbent pad disposed between said facing sheet and said backing sheet;
a pair of pressure-sensitive tape tab strips having a higher peel adhesion value than the tensile strength and tear resistance of said backing sheet attached to the backing sheet near the diaper corners along a portion of the length of said strips, said unattached portions being designed to

engage the exterior of said backing sheet in a predetermined attachment zone; and
 a hot melt adhesive layer having a lower modulus of elasticity and a Ring & Ball softening point lower than the modulus of elasticity and the heat distortion temperature of said backing sheet, respectively, the adhesive layer selectively located in the interior of said backing sheet underneath said attachment zone thereby increasing the stiffness of the film in said zone, said adhesive layer attached only to said backing in said zone.


4,296,751 SURGICAL DEVICE

Joseph W. Blake, III, R.R. #2, Box 106, Kitchewan Rd., South Salem, N.Y. 10590, and Jack W. Kaufman, 357 Frankel Blvd., Merrick, N.Y. 11566

Filed Aug. 2, 1979, Ser. No. 63,268
 Int. Cl.³ A61B 17/12

U.S. Cl. 128—325

19 Claims



1. A surgical device, particularly a hemostat, comprising an applicator having a pair of cooperating jaws provided with anvils and being movable between an open and a closed position; and
 supply means for feeding surgical clips to said jaws, said supply means comprising a cartridge including a housing adapted to accommodate a string of clips, means for advancing the string towards the jaws for serial insertion of the respectively leading clip of the string between said anvils while the jaws are in said open position so as to become cinched between said anvils when the jaws move to said closed position, and means for retracting all except the respectively leading clip in direction away from said anvils prior to movement of said anvils from said open end towards said closed position, said housing comprising a body having a leading end section and a trailing end section and two substantially parallel tracks both extending between said end sections, said advancing means comprising biasing means for biasing a string of clips in one of said tracks lengthwise of the same towards said leading end section, and said retracting means including a retracting member in the other of said tracks and having a leading portion extending into and moveable in said one track between one position in which said leading portion is disengaged from said clips and permits the respectively leading clip to issue from said leading end section and another position in which said leading portion engages the clip immediately upstream of the leading clip and retracts it, and thereby said string of clips, in direction towards said trailing end section.


4,296,752 TRANSCUTANEOUS OXYGEN SENSOR WITH ADJACENT HEATER

Luther Welsh, San Clemente; Daryl J. Bergquist, Huntington Beach, and Hideo Watanabe, Fullerton, all of Calif., assignors to Johnson & Johnson, New Brunswick, N.J.

Division of Ser. No. 726,710, Sep. 24, 1976. This application May 11, 1979, Ser. No. 37,650
 Int. Cl.³ A61B 5/00

U.S. Cl. 128—635

10 Claims



1. A sensor for transcutaneous measurement of partial pressure of gas, comprising:
 a heater assembly;
 a transcutaneous gas sensing cell which includes (a) a cathode, (b) a reservoir, (c) a membrane, and (d) electrolyte in the reservoir and forming an electrolyte path between the cathode and the reservoir;
 said membrane including (i) a first portion having a front side disposed for direct contact with the patient's skin, and a back side adjacent the cathode but being separated from the cathode by a layer of said electrolyte defining said electrolyte path, and (ii) a second portion surrounding the gas sensing cell and disposed to be out of contact with the skin of the patient when the sensor is in use;
 said heater assembly comprising (i) an annular heat conductive element surrounding said gas sensing cell but so spaced therefrom that heat is substantially not coupled from said element directly to said gas sensing cell, and (ii) means for heating said element;
 said heater assembly being so constructed, disposed and spaced relatively to said gas sensing cell as to be attachable to the skin of the patient for transfer of heat from said element to the skin, without such heat passing to the skin through the membrane and without substantial transfer of heat from said element to said gas sensing cell.

4,296,753 SUPPORT FOR A TRANSDUCER FOR EMITTING AND/OR RECEIVING ULTRASONIC SIGNALS IN A GIVEN ANGULAR SECTOR


Robert Goudin, La Varenne-St-Hilaire, France, assignor to U.S. Philips Corporation, New York, N.Y.

Filed Sep. 17, 1979, Ser. No. 76,025

Claims priority, application France, Sep. 19, 1978, 78 26771
 Int. Cl.³ A61B 10/00

U.S. Cl. 128—660

5 Claims




1. A support for a transducer for emitting and/or receiving

ultrasound signals in a given angular sector with respect to a plane at the surface of an object, comprising:

a series of rotationally symmetrical, coaxial rings which includes a first ring, one or more intermediate rings, and a last ring, disposed one behind another along a line which connects the transducer with the surface of the object, the first ring being adapted for placement adjacent the surface of the object and the last ring being adapted for attachment to the transducer, the first and each succeeding intermediate ring in the series being pivotably connected to the following ring in the series so that the transducer can achieve a total angular rotation with respect to the first ring which at least equals the given angular sector and so that the distance between the transducer and the plane remains substantially constant as the transducer is rotated through that sector;
 a deformable, liquid-tight bag enclosing the rings; and
 coupling liquid means which fill the bag and surrounds the rings for coupling ultrasound signals from the transducer to the object.

ents representative of bandwidth and mean frequency of said signal over a short time interval; and
 comparing said coefficient of bandwidth with a preselected threshold value to determine whether it exceeds same, and



comparing said coefficient of mean frequency with a range of values to determine whether it falls within said range, and if both said determinations are positive, declaring ventricular fibrillation to be present.

4,296,756 REMOTE PULMONARY FUNCTION TESTER


Ted E. Dunning, Denver, and Paul L. Enright, Englewood, both of Colo., assignors to Cyber Diagnostics, Inc., Denver, Colo.

Filed Jul. 26, 1979, Ser. No. 61,051

Int. Cl.³ A61B 5/08

U.S. Cl. 128—716

8 Claims



1. A pulmonary function tester capable of accurately producing, storing, transmitting, receiving and displaying selected information relating to the breathing maneuver of a test subject comprising:

a remote unit,
 entry means associated with said remote unit for entering test subject data;
 means communicating with said remote unit for accepting the breathing maneuver of a test subject,
 means communicating with said accepting means for producing electrical signals proportional to the flow rates of the breathing maneuver of the test subject;
 digitizing means communicating with said signal production means for converting the signals produced by the flow rates from the breathing maneuver into digital form representative of expiration flow rate and expiration time;
 read/write memory means communicating with said entry means and said digitizing means for retrievably storing the test subject data entered through said entry means, and digitized test subject data from said digitizing means,
 communication interface means communicating with said digitizing means and said read/write memory means for communication of signals including digitized test subject data, to and from at least one locus external to said remote unit,
 display means communicating with said digitizing means, said read/write memory means, said entry means and said communication interface means, for the display of test

4,296,754 METHOD FOR DETERMINING THE VALUE OF CARDIOLOGIC QUANTITIES AND APPARATUS FOR PERFORMING SAID METHOD

Ewald M. C. Hennig, Ostendstrasse 62, D-6000 Frankfurt 1, and Klaus Nicol, Adelheidstrasse 13, D-6000 Frankfurt 50, both of Fed. Rep. of Germany


Filed Jul. 3, 1979, Ser. No. 54,438

Claims priority, application Fed. Rep. of Germany, Jul. 4, 1978, 2829269

Int. Cl.³ A61N 5/02

U.S. Cl. 128—694

9 Claims



1. A method for determining the value of cardiologic quantities comprising:

encircling a portion of a body having a blood-conveying vessel with capacitor plates of a capacitor, so that the body portion engages the capacitor and defines the dielectric of the capacitor;
 maintaining the capacitor plates fixed relative to one another; and
 measuring changes in the capacitance of the capacitor.

4,296,755 METHOD AND APPARATUS FOR DETERMINING VENTRICULAR FIBRILLATION

Neil H. K. Judell, N. Kingstown, R.I., assignor to Datamedix Inc., Boca Raton, Fla.

Filed Mar. 19, 1980, Ser. No. 131,587

Int. Cl.³ A61B 5/04

U.S. Cl. 128—705

30 Claims

1. A method for declaring the presence of ventricular fibrillation from an incoming electrocardiograph signal comprising:
 sampling said signal at a first frequency;
 filtering said sampled signal to produce an output signal at a second frequency lower than said first frequency and to remove any DC components and baseline wander;
 examining the spectrum of said filtered signal by passing the same to a linear predictor which fits a model signal spectrum to the actual signal spectrum and computes coefficient

subject data, entry data and communications fed back to said communication interface means; and computer processing means for controlling the functioning of said remote unit including the representations displayed by said display means and responsive to preselected criteria obtained from said read/write memory, means said communication interface means and input from said entry means, and the sequence of function and manner of function of said communication interface means and said read/write memory means, so as to provide data on a test subject breathing maneuver which compares test subject flow rates with total expired volume for the subsequent diagnostic interpretation of pulmonary function.

4,296,757


RESPIRATORY MONITOR AND EXCESSIVE INTRATHORACIC OR ABDOMINAL PRESSURE INDICATOR

Thomas Taylor, 421 Randolph St., N.W., Washington, D.C. 20011

Filed Apr. 14, 1980, Ser. No. 139,686
Int. Cl.³ A61B 5/08, 5/10

U.S. Cl. 128—721

12 Claims



1. A respiratory monitor for monitoring the respiration of a person said respiratory monitor comprising:

- (a) detector means for detecting the expansion of the chest of the person;
- (b) alarm circuit means coupled to said detector means for producing an alarm signal if said detector means does not detect expansion of the chest for a predetermined period of time; and
- (c) strap means for mounting said detector means on the persons chest said strap means including compression means for compressing when the persons weight is placed thereon wherein said detector means are mounted on said strap means such that when the person lies on his chest the persons weight is absorbed by said compression means whereby said detector means is not affected by the position of the person.

4,296,758

SPIROMETERS

Dietmar R. Garbe, Maids Moreton House, Maids Moreton, Buckingham, England

Filed Oct. 16, 1979, Ser. No. 85,273

Claims priority, application United Kingdom, Oct. 16, 1978, 40690/78; Jan. 25, 1979, 02625/79


Int. Cl.³ A61B 5/08

U.S. Cl. 128—728

13 Claims

1. A spirometer having an inflatable bellows, inlet means for inflating said bellows, a movable member connected to said bellows having a locus along which said member is drivable progressively by said bellows during progressive inflation thereof, track means positioned, and having a course configured, to be engaged by and followed by said movable member during the progressive driving thereof along said locus and

adjusting means for adjusting said configuration of said track means to provide locally adjustable opposition to movement of



the movable member and, thereby, to the inflation of said bellows.

4,296,759

BLOOD COLLECTION DEVICE AND METHOD WITH ANTI-BACKFLOW MEANS


Joel A. Joslin, Sunset Hills, and Alan B. Ranford, Des Peres, both of Mo., assignors to Sherwood Medical Industries Inc., St. Louis, Mo.

Filed Jun. 27, 1977, Ser. No. 810,257

Int. Cl.³ A61M 5/00

U.S. Cl. 128—766

14 Claims



1. A blood collection device comprising a container having one end closed and a blood collection chamber for receiving a blood sample, a needlepierceable stopper closing the opposite end of said container, said collection chamber normally having a negative pressure maintained therein by said stopper, and a one-way valve disposed in said container between said stopper and said collection chamber and operable to allow blood flow from a needle piercing said stopper to said collection chamber but preventing blood flow from said collection chamber to the needle.

4,296,760

ELECTRICAL STIMULATOR

Per-Olov A. V. Carlsson, Sosdala, and Bo H. Hakansson, Lund, both of Sweden, assignors to Gambro AB, Sweden

Filed Nov. 26, 1979, Ser. No. 97,380

Claims priority, application Sweden, Nov. 27, 1978, 7812159


Int. Cl.³ A61N 1/04

U.S. Cl. 128—788

13 Claims

1. An electrical stimulator comprising an elongated element adapted for vaginal placement, said elongated element including a longitudinal axis, said longitudinal axis including a first end corresponding with a first end of said electrical stimulator and a second end corresponding with a second end of said electrical stimulator, said elongated element including a transverse cross-section throughout the length of said elongated element from said first end of said longitudinal axis to said second end of said longitudinal axis, said transverse cross-section having first and second perpendicular axes, said first perpendicular axis being greater than said second perpendicular

axis, and a plurality of electrodes carried by said elongated element, said electrodes being located on the surface of said elongated element on one side of a longitudinal cross-section of said elongated element corresponding with said first perpen-



dicular axis, so that when said stimulator is vaginally placed in a direction corresponding with said longitudinal axis said elongated element is stabilized against rotation with all of said electrodes facing in a predetermined direction.

4,296,761

CONVERTIBLE PARAPODIUM


James H. Tyo, Jackson, Mich., assignor to Camp International, Inc., Jackson, Mich.

Filed Apr. 25, 1980, Ser. No. 143,608

Int. Cl.³ A61F 3/00

U.S. Cl. 128—80 G

7 Claims



1. A parapodium for permitting crutchless standing and convertible to a seat without structural modification comprising, in combination, a base having a standing surface defined thereon and including lateral sides, a column mounted adjacent each base lateral side extending upwardly from said base each having an upper end, a pivot plate mounted upon each column upper end, a pair of parallelogram linkages each having a first end pivotally mounted upon a pivot plate and a second end each pivotally affixed to a back supporting member, horizontal leg bracing means extending between said pivot plates, a seat affixed to said linkages adjacent said back supporting member, elongated leg means supported by said back supporting member, and linkage locking means defined upon said pivot plates selectively engaging and releasing said linkages permitting said linkages to be pivoted from a vertical standing position wherein said seat is substantially vertically oriented and said leg means are in a raised position above said base to a substantially horizontal sitting position wherein said seat is substantially horizontally oriented and said leg means are in a lowered ground supported position off-set with respect to said base.

4,296,762

SMOKABLE PRODUCTS

Theobald Eicher, Dormagen, and Friedemann Müller, Neuss, both of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Jun. 14, 1978, Ser. No. 915,490

Claims priority, application Fed. Rep. of Germany, Jul. 1, 1977, 2729759

Int. Cl.³ A24B 15/30, 15/42; A24D 1/18

U.S. Cl. 131—359

12 Claims

1. A process for the preparation of a smokable product based on cellulose and combustion-modifying substances which comprises saturating, spraying or coating a combustible, prefabricated material which is based on cellulose and optionally contains fillers customarily used in smokable products and which can be used as a smokable product with an electrostatically stabilized dispersion of solids as the internal phase in an external aqueous phase, the solids being electrically charged and having an average particle diameter of less than 2μ, the aqueous phase being a solution of salts of monobasic or polybasic carboxylic acids, whereby the solids are preferentially distributed on the surfaces of the smokable product.

4,296,763

HAIR CONDITIONER


Clayton W. Priest, 1413 E. 19th St., Santa Ana, Calif. 92701, and Edward T. Solomon, Huntington Beach, Calif., assignors to Clayton W. Priest, Redlands, Calif.

Filed Mar. 7, 1979, Ser. No. 18,424

Int. Cl.³ A45D 1/00

U.S. Cl. 132—7

4 Claims



1. Process of applying hot oil to human hair including: selecting a pervious, flexible, open celled, inert synthetic foam substrate which is generally uniformly preimpregnated with a hair revitalizing oil composition and adapted to conform generally to the scalp portion of a human head, said composition being generally a solid having a melting point from about 115 to 130 degrees Fahrenheit and being substantially all retained in said preimpregnated substrate at room temperature; placing said preimpregnated substrate in direct contact with the scalp portion of a human head; placing an oil impervious film over substantially the entire exterior of said substrate; and applying heat at said substrate for a period of at least approximately 15 minutes to melt said composition and to release said composition from said substrate and to allow said composition to permeate said hair.

4,296,764

HAIR WAVING AND STRAIGHTENING METHOD

Thomas J. Pallone, Monroe; Mark Lynch, Southbury; Janice E. Corvino, Stratford, and John P. McCook, Madison, all of Conn., assignors to Chesebrough-Pond's Inc., Greenwich, Conn.

Filed Dec. 26, 1979, Ser. No. 107,746
Int. Cl.³ A45D 7/00

U.S. Cl. 132—7

11 Claims

1. In a process for the cold waving or straightening of hair, the improvement which serves to provide longer-lasting results with less tendency to undergo hair lightening and increased tightness and springiness when used as a waving solution, comprising contacting the hair with an alkaline cold waving or straightening solution containing acidic metal sulfite and/or acidic metal bisulfite, capable of generating sulfur dioxide, followed by treating with an aqueous neutralizer solution having a pH between 2.0 and 5.0 and containing hydrogen peroxide in a concentration between 0.65 and 3.4 percent by weight giving a ratio of weight percent hydrogen peroxide in the neutralizer to weight percent sulfur dioxide from the waving/straightening solution of between 0.26 and 0.34.

4,296,765


METHOD AND APPARATUS FOR SECURING A HAIRPIECE

Stephen R. Bachtell, 1727 Crystal La., Mt. Prospect, Ill. 60056
Filed Dec. 18, 1978, Ser. No. 970,104

Int. Cl.³ A41G 3/00

U.S. Cl. 132—53

2 Claims



1. A method of attaching a hairpiece to the head of a recipient having at least some natural hair with the use of apparatus that includes two lines each having one end for attachment to the hair and the other end for attaching selected line tension weights, the hairpiece having a plurality of loops to which natural hair can be secured, comprising the steps of:

- positioning the hairpiece on the head of the recipient so that a series of the loops are disposed adjacent the recipient's natural hair;
- pulling a first group of the natural hair through an adjacent loop at a first attachment site;
- securing a first line to the end of said first group of hair;
- orienting said line and the first group of hair secured thereto to a predetermined angle with respect to the head of the recipient;
- applying a weight of preselected size to the other end of said line so as to impart a controlled amount of tension to said line and the group hair secured thereto such that said first group of hair is held without manual assistance in predetermined outwardly extending orientation with respect to said head;
- pulling a second group of natural hair adjacent said first attachment site outwardly from the recipient's head;
- securing a second line to the ends of said second group of hair;
- orienting said second line and said second group of hair attached thereto to a predetermined angle to the head while said first group of hair is held by said first line such

that the first and second groups cross against each other over the loop;

- applying a weight of preselected size to the other end of said second line so as to impart a controlled amount of tension to said second line and said second group of hair secured thereto so that said first and second crossing groups of hair dispose the loop against the recipient's head without manual assistance;
- securing together said two groups of hair while they are held in crossing relation extending outwardly from the recipient's head by said first and second lines so as to secure said loop in position on the head; and
- detaching said first and second lines from said groups of hair.

4,296,766

MANICURING CASE AND SUPPORTING APPARATUS


Isak Benis, 525 N. Kings Rd., Los Angeles, Calif. 90048

Filed Jul. 14, 1980, Ser. No. 167,817

Int. Cl.³ A45D 29/00

U.S. Cl. 132—73

5 Claims



1. A manicuring case and supporting apparatus for use with liquid storing bottles having a tapered cross-section, said manicuring case and supporting apparatus comprising:

- a container having top and bottom members which define an interior cavity therebetween, said top and bottom members being pivotally coupled to one another to provide access to said interior cavity, said top member having a plurality of apertures disposed therethrough which are adapted to receive the liquid storing bottles;
- a resilient layer disposed upon and secured to the bottom member within the interior cavity whereby the liquid storing bottles are held in place intermediate said top and bottom members when the top and bottom members are pivoted adjacent one another; and
- support means for supporting the user's hand depending upwardly from the top member of said container, said support means including a base having a plurality of substantially uniform depressions disposed upon the top surface thereof.

4,296,767

METHOD AND APPARATUS FOR CLEANING A CONTINUOUS WEB OF MATERIAL

Jan E. Hammar, Enebyberg, Sweden, assignor to Forenade Fabriksverken, Eskilstuna, Sweden

Filed Mar. 12, 1980, Ser. No. 129,673

Claims priority, application Sweden, Mar. 16, 1979, 7902382


Int. Cl.³ B08B 5/04

U.S. Cl. 134—15

16 Claims

4. A method for cleaning a web of material (1) to remove dust and other loose particles from the material (1) and comprising the steps of moving the web of material (1) through a suction chamber (2) having a web inlet (12) and a web outlet (13) having substantially the same cross sectional area, and at least one air outlet (11), connecting the one air outlet (11) to a source of sub-pressure, and restricting the amount of air enter-

ing the suction chamber (2) through the web inlet (12) to cause a greater amount of air to flow into the suction chamber (2)



through the web outlet (13) than flows into the suction chamber (2) through the web inlet (12).

4,296,768

PORTABLE DISHWASHER



Rudy E. Saucedo, 1508 Bahama Way, San Jose, Calif. 95122

Filed Oct. 1, 1979, Ser. No. 80,416

Int. Cl.³ B08B 3/02

U.S. Cl. 134—47

18 Claims



1. A dishwasher of the type intended to receive therein and wash dishes and including a source of electrical power, said dishwasher comprising:

- a housing; said housing comprises a plurality of dish-receiving compartments;
- means within said housing for washing dishes so as to act upon dishes within said compartments;
- means for selectively coupling said washing means to at least a predetermined one of said compartments; and
- means for operating said dishwasher upon condition that said coupling means having first coupled said washing means to said compartment.

4,296,769

CLOSURE TREATMENT MACHINE

Arie van der Lugt, Krimpen an der IJssel, Netherlands, assignor to Gist-Brocades N.V., Delft, Netherlands


Filed Mar. 20, 1980, Ser. No. 131,911

Claims priority, application Netherlands, Mar. 21, 1979, 7902218

Int. Cl.³ B08B 3/02

U.S. Cl. 134—68

13 Claims



1. Machine for the treatment of head-shaped closures especially rubber closures fit for vials for containment of infusion or injection liquids provided with at least a means holding said closures during the cleansing stage and with nozzles in such positions that the cleansing liquid may be sprayed under several angles towards the closures characterized in that the means holding the closures comprises one or more caskets having a number of parallel bars which are connected at both ends to each other by coupling plates whereby the parallel bars are arranged in such a way that the closures may find a place there between in the form of a row of a previously defined number and thereby held in such a way that the closures cannot be moved out of the space between the bars but do have such a tolerance that the cleansing liquid can reach any side of the closures whereby at least one of the coupling plates has an opening for passing the closures and the other coupling plate may form an eventual temporary barrier for the closures whereas a carrying means may lead the caskets filled with closures along nozzles spraying cleansing liquid.

4,296,770

FREEZE DRAIN VALVE


Robert A. Rice, Chicago, Ill., assignor to Eaton Corporation, Cleveland, Ohio

Filed Jan. 28, 1980, Ser. No. 116,368

Int. Cl.³ F16K 17/00; G05D 23/02

U.S. Cl. 137—62

12 Claims



1. A temperature responsive valve for connection to a fluid conduit, said valve comprising:

- housing means defining a fluid chamber having an inlet and an outlet in communication therewith, said inlet being adapted for connection to a fluid conduit;
- valve means disposed without said chamber adjacent said outlet and including means movable between a first position effecting blockage of fluid flow from said inlet to said outlet and a second position enabling such fluid flow;
- means biasing said movable means to said first position;
- temperature sensitive means associated with said housing means and disposed adjacent said inlet, said temperature sensitive means operative to sense the temperature of fluid at said inlet and including actuator means movable with

respect to said housing means in response to said sensed fluid temperature; and,

- (e) tension means operatively connecting said actuator means to said movable means wherein said tension means normally exerts no force on said movable means, but upon said temperature sensitive means experiencing fluid temperatures less than a predetermined value, said tension means enables said actuator means to move said movable means to said second position and at all fluid temperatures above said predetermined value said tension means is inoperative to transmit force from said actuator means to said movable means.

4,296,771

QUIET IMPULSE STEAM TRAP


Richard D. Claffy, Glen Burnie, Md., and Reginald B. Lovelace, West Palm Beach, Fla., assignors to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Continuation-in-part of Ser. No. 969,741, Dec. 14, 1978, abandoned. This application Aug. 27, 1980, Ser. No. 181,931

Int. Cl.³ G05D 11/00

U.S. Cl. 137—110

9 Claims



1. A steam trap comprising:

- a first orifice and a second orifice connected in series, the first orifice connected to the input of the trap and the second orifice connected to the output of the trap wherein the flow of fluid through the two orifices is continuous and, the size of the orifices proportioned to minimize the leakage of steam therethrough;
- an annular fluid throttling element positioned between the input and the output of the trap, the throttling element having a plurality of resistive fluid flow passages;
- inlet and outlet passageways respectively connecting the fluid throttling element to the input and the output of the trap;
- a cylinder formed in the steam trap and located adjacent to the throttling element;
- a control piston positioned in the cylinder, the cylinder is pressurized at one end portion by the fluid flowing between the first orifice and the second orifice wherein the fluid pressure between the orifices is applied to one end portion of the control piston, and the other end portion of the cylinder is connected to the trap output wherein the output fluid pressure is applied to the other end portion of the control piston; and
- an elongated valve plug positioned within the throttling element for movement between an open and a closed position wherein one end portion of the valve plug is connected to the control piston, and the other end portion of the valve plug communicates with the inlet passageway for applying the inlet fluid pressure to said other end portion of the valve plug to urge the valve plug toward an

open position wherein the fluid flow through the resistive fluid flow passages is increased.

4,296,772

NON-RETURN VALVE

Robert Nilsson, Bromölla, Sweden, assignor to Evak Sanitar AB, Bromölla, Sweden


Filed Jan. 23, 1980, Ser. No. 114,773

Claims priority, application Sweden, Feb. 2, 1979, 7900925

Int. Cl.³ F16K 17/12

U.S. Cl. 137—269.5

5 Claims



1. A reversible flap-type non-return valve comprising a valve housing with two through-flow openings substantially facing each other, said valve housing minimizing its interior volume and having in a first plane the basic cross-sectional form of a trapezoid, the parallel sides of said trapezoid being lower and upper transverse sides of said housing and the non-parallel sides of said trapezoid being transverse sides of the housing including said openings;
- a removable inspection cover forming one side of said housing being substantially plane and disposed substantially parallel to said first plane;
- bearing means attached to the valve housing defining two turning axes perpendicular to said first plane and including two pairs of bearing bushings, each pair having a fixed position one for each of said turning axes and one bearing bushing of each pair being at least in part in said removable inspection cover; and
- a movable valve flap disposed at one of the turning axes of the bearing means and suitable as a closing member at both of the two through-flow openings.

4,296,773

HYDRAULIC SELECTOR VALVE HAVING JOY STICK CONTROL

Ronald W. Harshman, Greencastle, and Lynn A. Dietrich, Chambersburg, both of Pa., assignors to Walter Kidde & Company, Inc., Clifton, N.J.

Filed Feb. 12, 1979, Ser. No. 11,762


Int. Cl.³ F16K 29/00

U.S. Cl. 137—312

3 Claims

1. A selector valve comprising a valve body having plural spaced parallel bores, motive fluid inlet passage means leading to said bores and plural motive fluid delivery ports corresponding in number to said bores and leading from the bores, a valve spool positioned in each said bore of the valve body and being biased to a closing position in relation to the adjacent delivery port and having an extension projecting exteriorly of the valve body at one end thereof, a joy stick controller for said valve spools and having a universal swiveled connection with the valve body at said one end and between said bores, an end cover plate for the valve body at the end thereof remote from said joy stick controller and having an annular collector recess in its interior face in registration with said bores, said cover plate having a drain port in communication with said collector recess, and an actuating disc mounted on said joy stick controller and cammingly engaging all of said valve spool extensions

and movable with the joy stick controller to selectively shift a single valve spool or a pair of such spools to an open position



in relation to a single delivery port or a pair of such ports of the valve body.

4,296,774

DEVICE FOR DETACHABLY COUPLING THE ORIFICE OF A BRANCHLINE TO A LINE CARRYING A PRESSURE MEDIUM

Bruno Kägi, Meilen; Georg Hirmann, Zurich, and Rolf Luginbühl, Küsnacht, all of Switzerland, assignors to Bachofen AG., Uster, Switzerland



Filed Aug. 22, 1979, Ser. No. 68,614

Claims priority, application Switzerland, Aug. 25, 1978, 9003/78; Apr. 17, 1979, 3595/79; Jul. 20, 1979, 6788/79

Int. Cl.³ F16L 29/00, 37/28

U.S. Cl. 137—322

20 Claims



1. A device for detachably coupling an orifice of a branchline to a conduit carrying a pressure medium and having a plurality of discharge valves disposed spaced apart from each other along said conduit, each of said valves having a discharge opening, and a closing element as well as opening means for each of said openings, each of said discharge valves including an expansible chamber for receiving the pressure medium therein for maintaining said closing element in a position to close the respective openings, a coupling device having said orifice disposed therein, said coupling device being longitudinally displaceable along said conduit and connectable with the conduit by opening one of the discharge valves, said coupling device being guided along said conduit and having sealing and coupling means becoming effective automatically in the coupling position with the discharge opening being at least

partially in alignment with the orifice, and actuating means effective to open the respective one of said discharge valves magnetically via pre-control means without physically contacting the same in the coupling position of the coupling device for bleeding the expansible chamber of the respective discharge valve, said actuating means including magnetic control elements on the side of the displaceable coupling device and on the side of any of the different discharge valves such that by displacing the coupling device a selected one of the discharge valves can be opened and connected with the orifice of the branchline.

4,296,775

DEVICE FOR DETACHABLY COUPLING A BRANCHLINE TO A PRESSURE LINE

Bruno Kägi, Meilen; Georg Hirmann, Zurich, and Rolf Luginbühl, Küsnacht, all of Switzerland, assignors to Bachofen AG., Uster, Switzerland



Filed Aug. 22, 1979, Ser. No. 68,879

Claims priority, application Switzerland, Nov. 27, 1978, 12139/78; Apr. 17, 1979, 3595/79; Jul. 20, 1979, 6788/79

Int. Cl.³ F16L 29/00, 37/28

U.S. Cl. 137—322

13 Claims



1. A device for detachably coupling an orifice of a branchline to a conduit carrying a pressure medium and having a plurality of discharge valves disposed spaced apart from each other along said conduit, each of said valves having a discharge opening, and a closing element for each of said openings, each of said discharge valves including an expansible chamber for receiving the pressure medium therein for maintaining said closing element in a position to close the respective openings, a coupling device having said orifice disposed therein, said coupling device being longitudinally displaceable along said conduit and connectable with the conduit by opening one of the discharge valves, said coupling device being guided along said conduit and having sealing and coupling means becoming effective automatically in the coupling position with the discharge opening being at least partially in alignment with the orifice, and actuating means effective to open by contact a respective one of said discharge valves in the coupling position of the coupling device, wherein said actuating means actuates the respective discharge valve indirectly via pre-control means for bleeding the expansible chamber of the respective discharge valve.

4,296,776

GATE VALVE FOR USE IN LARGE SIZE CONDUITS
Rudolf Müller, Merzenich; Franz Lengsfeld, Jülich, and Johannes Uerlich, Woffelsbach, all of Fed. Rep. of Germany, assignors to Hermann Rappold & Co. GmbH, Duren, Fed. Rep. of Germany


Filed Feb. 22, 1980, Ser. No. 123,885

Claims priority, application Fed. Rep. of Germany, Mar. 10, 1979, 2909467

Int. Cl. F16K 49/00

U.S. Cl. 137—340

10 Claims



1. In a gate valve for use in large size conduits or pipe lines, particularly hot air conduits, said gate valve being of the type including a water cooled valve casing coaxially attachable to a conduit and a valve plate mounted in said valve casing for sliding movement relative thereto between open and closed positions of the conduit, the improvement wherein said valve casing comprises:

- a pair of annular mounting flanges adapted to be connected to the conduit;
- a pair of annular U-shaped sealing rings, each said sealing ring being positioned radially inwardly of a respective said mounting flange, said sealing rings being positioned on opposite axial sides of said valve plate;
- each said sealing ring including a web portion, an inner leg extending generally radially outwardly from said web portion and forming a sealing surface for said valve plate, and an outer leg extending generally radially outwardly from said web portion;
- means for connecting each said outer leg to the respective said mounting flange;
- said valve casing defining therein an enclosed interior space through which cooling water is adapted to flow; and
- support means, positioned within said interior space, for transmitting to at least one said mounting flange stress applied to the respective said sealing surface by said valve plate, said support means including a first end portion supported against and fixed to said one mounting flange and a second end portion freely contacting the respective said inner leg without attachment thereto, said support means having a cross-section substantially transverse to the direction of flow of cooling water within said interior space such that said support means does not appreciably interfere with or restrict such flow.

4,296,777

MULTIPLE COUPLING FOR LUBRICATING SYSTEMS
Karl Rodemer, Heidelberg, Fed. Rep. of Germany, assignor to Lincoln-Helios GmbH, Walldorf, Fed. Rep. of Germany

Filed Jun. 18, 1979, Ser. No. 49,843

Claims priority, application Fed. Rep. of Germany, Jun. 21, 1978, 2827137

Int. Cl. B60R 17/00; F16L 29/00


U.S. Cl. 137—351

13 Claims

13. Liquid coupling apparatus for coupling a liquid under pressure from a source to a utilization device comprising in combination,

- a plug box, said plug box having means forming an inlet passageway adapted to be connected to said source of liquid, means forming a return passageway to said source of liquid, means forming an outlet passageway, a valve chamber in said plug box forming a connecting passage-

way between said inlet passageway, said return passageway and said outlet passageway, valve seat means formed at the entrance to each of said return passageway and said outlet passageway, a pair of piston valve elements in said valve chamber, each piston valve element assigned and adapted to seat on one of said valve seats, respectively, a first compression spring between said piston valve elements, a second compression spring biasing both said valve elements in a direction to seat the valve element associated with the valve seat at said outlet passageway, an extension member on the piston valve element associated with said outlet passageway,



a plug-in piece coupled to said utilization device and having an inlet passageway corresponding and adapted to be aligned with said outlet passageway, a valve actuator member forming an extension of said plug-in piece at said inlet passageway and adapted, when said plug-in piece is mated with said plug box, to engage said extension member and unseat the valve element associated with said outlet valve seat and, through said first compression spring, seat the said piston valve element on the valve seat associated with said return passageway.

4,296,778

ANTI-BACKFLOW VALVE FOR SEWER TRAPS


Alonzo B. Anderson, 1238 Pagos Ave., Salt Lake City, Utah 84117

Filed Aug. 13, 1979, Ser. No. 66,088

Int. Cl. F16K 31/22, 33/00

U.S. Cl. 137—433

6 Claims



1. An anti-backflow valve for installation in a sewer catch basin, comprising in combination:

- a valve housing having an upper cover plate for attachment to a catch basin and an open lower end; said valve housing being adapted for mounting within a catch basin; said valve housing having first fluid flow apertures therein;
- an upper sealing seat means disposed within the upper end of said valve housing;
- a bouyant sealing member reciprocally disposed within said valve housing for vertical movement and having means for sealing upwardly against said upper sealing seat to shut-off fluid flow through said first apertures, said

sealing member having a downwardly extending elongate guide member attached thereto;

a detachable bottom plate means for mounting on the bottom side of said valve housing, said bottom plate means includes second fluid flow apertures for permitting fluid flow therethrough in an upward direction to move said sealing member against said sealing seat means to shut-off fluid flow through said first apertures and to prevent upward fluid flow simultaneously, and when said sealing member moves downwardly said first apertures are open to fluid therethrough and the second apertures are closed to upward fluid therethrough by said sealing member, and said bottom plate means having a guide way member for receiving and reciprocally holding said guide member of said sealing member.

4,296,779

TURBULATOR WITH GANGED STRIPS


Ronald H. Smick, 745 Chapel St., Ottawa, Ill. 61350

Filed Oct. 9, 1979, Ser. No. 82,576

Int. Cl. B01F 15/06; F15D 1/02

U.S. Cl. 138—38

10 Claims



1. An improved turbulator unit for insertion in a heat exchanger tube having substantially straight longitudinal internal walls, comprising, in combination, a plurality of elongated turbulator strips of metal each formed of a series of alternately angling and oppositely tilting deflection panels successively joined together by substantially triangular bridging portions, said strips being ganged together with every other one of said triangular bridging portions of opposing ones of said strips being disposed and anchored substantially on the axis of the heat exchanger tube and the other ones of said triangular bridging portions of each turbulator strip disposed with the apex thereof directed toward and adjacent the inner wall of said tube.

4,296,780

APPARATUS INCLUDING THROTTLING DEVICE FOR USE IN VENTILATION DUCT

Per Norbäck, Askrikevagen, Sweden, assignor to A. B. Carl Munters, Sollentuna, Sweden

Continuation-in-part of Ser. No. 50,519, Jun. 21, 1979,

abandoned. This application Feb. 28, 1980, Ser. No. 125,442

Claims priority, application Sweden, Jun. 21, 1978, 7807129; Norway, Dec. 13, 1979, 794084

Int. Cl. F15D 1/02


U.S. Cl. 138—40

12 Claims

1. An apparatus for use in ventilation ducts comprising a throttling device including a body having opposite air inlet and outlet sides and a plurality of fine elongated through passages extending therebetween and producing a pressure drop for conveying air flowing from said inlet through said elongated passages to said outlet side thereof, and deflector shield means mounted adjacent said inlet side of said body to allow relative movement of said body with respect thereto while cleaning the surface of said inlet side of the body, said apparatus including means for rotating one of said body and said deflector shield means relative to the other, said shield means having an opening facing said inlet side of the body which is caused to sweep over said inlet side of the body during such relative movement and means for providing flow communication between said shield means and the lower air pressure on the outlet side of the throttling device whereby the drop of pressure across the

throttling device diverts a partial air flow through said shield means in another direction than the main air flow into the body of the throttling device in order to clean the surface of said inlet side of the body and then discharges said partial air flow downstream of the body in the same direction as the main air flow.

11. The combination comprising a ventilation duct and a throttling device rotatably mounted in said duct including a body having opposite air inlet and outlet sides and a plurality of fine elongated through passages extending therebetween and producing a pressure drop for conveying air flowing from said inlet through said elongated passages to said outlet side thereof, and deflector shield means fixed in said duct adjacent



said inlet side of said body to allow relative movement of said body with respect thereto while cleaning the surface of said inlet side of the body, and means for rotating said body, said shield means having an opening facing said inlet side of the body which is caused to sweep over said inlet side of the body during rotation of the body and means for providing flow communication between said shield means and the lower air pressure on the outlet side of the throttling device whereby the drop of pressure across the throttling device diverts a partial air flow through said shield means in another direction than the main air flow into the body of the throttling device in order to clean the surface of said inlet side of the body and then discharges said partial air flow downstream of the body in the same direction as the main air flow.

4,296,781

SECTIONAL PIPE AND TUBULAR MEMBERS FOR FORMING SAME


Paul G. Magnus, Apple Valley, Minn., assignor to Magnus-system, Inc., Apple Valley, Minn.

Filed Apr. 23, 1979, Ser. No. 32,249

Int. Cl. F16L 9/22; E04H 12/18

U.S. Cl. 138—155

16 Claims



1. A tubular member which is elongated along a longitudinal axis extending therethrough and which is made from a plurality of sections, wherein each section has a transverse cross-section

tional configuration which includes a radially outward circumferential surface that defines part of the exterior of the tubular member and two generally radially extending side surfaces which converge from the radially outward circumferential surface to a radially inward circumferential surface that extends parallel to the longitudinal axis, and further including a plurality of longitudinally spaced lugs, one of said lugs located on the radially inward circumferential surface of each section, wherein the lugs on adjacent sections are colinear with and longitudinally staggered relative to one another to interfit with one another to lock the plural sections together to form the tubular member and also to prevent relative longitudinal movement between the sections, wherein the lugs extend inwardly from the radially inward circumferential surfaces of their respective sections to lie generally along the longitudinal axis of the tubular member.

4,296,782

DOUBLE-LIFT OPEN-SHED JACQUARD MACHINE
Hubert Kremer, Grefrath, Fed. Rep. of Germany, assignor to Maschinenfabrik Carl Zangs Aktiengesellschaft, Krefeld, Fed. Rep. of Germany


Filed Oct. 26, 1979, Ser. No. 88,381

Claims priority, application Fed. Rep. of Germany, Oct. 27, 1978, 2846792

Int. Cl.³ D03C 3/06, 3/30

U.S. Cl. 139—65

11 Claims



1. In a double-lift open-shed Jacquard machine with two lifting bars which are movable in opposite directions relative to each other and pass each other, and with flat-bar lifters which can be controlled by main needles, whose maximum moment of resistance is parallel to the direction of movement of the main needles, and which have two main projections associated with the movable knives, a holder-up projection associated with a fixed upper-shed knife, and at the lower end an engagement point for a harness cord, the improvement wherein

a flat-bar lifter has two main projections, a holder-up projection and an engagement point for the harness cord, said two main projections, said holder-up projection and said engagement point lie on a straight line oriented crosswise to the direction of movement of the main needles, said holder-up projection is positioned adjacent the flat-bar lifter in a direction transverse to the direction of movement of the main needles.

4,296,783 WEFT YARN END TREATING DEVICE FOR SHUTTLELESS LOOM

Eiji Ichimatsu, Koganei, Japan, assignor to Nissan Motor Company, Ltd., Japan


Filed Nov. 29, 1978, Ser. No. 964,716

Claims priority, application Japan, Dec. 1, 1977, 52-143308

Int. Cl.³ D03D 49/70

U.S. Cl. 139—302

34 Claims



1. In a shuttleless loom having yarn inserting means located adjacent a first side of the array of warp yarns from which inserting means a weft yarn is picked into the shed of the warp yarns to weave a fabric, a weft yarn end treating device for treating an end portion of the picked weft yarn which end portion is projected from a second side of the array of the warp yarns, the second side being opposite to the first side and remote away from the yarn inserting means, said weft yarn end treating device comprising:

conveying means for conveying the projected end portion of the weft yarn in a direction generally the same as the moving direction of woven fabric from a portion adjacent the weave front of a woven fabric, when the projected end portion is held to contact therewith;

holding means for holding the projected end portion to contact with said conveying means;

thrusting means for thrusting the projected end portion of the weft yarn into a location at which the projected end portion begins to be held to contact with the conveying means, said thrusting means being actuated in connection with the operation of said loom, said thrusting means including a movable rod member swingably supported on the frame of a reed of said shuttleless loom, said movable rod member including upper and lower portions which extend generally oppositely with respect to a portion at which said movable rod member is swingably supported, and a push rod member disposed stationary relative to the frame of said shuttleless loom, said push rod member being strikable against the upper portion of said movable rod member to move the lower portion of said movable rod member so as to carry the projected end portion of the weft yarn into said location; and

cutting means for cutting the projected end portion of the weft yarn in close proximity to a side of the fabric corresponding to the second side of the warp yarn array, after the projected end portion is thrust into said location, said cutting means being located between the fabric and said conveying means.

4,296,784 WIRE VIBRATION DAMPING DEVICE AND METHOD FOR COIL WINDING APPARATUS


Philip G. Rodenbeck, and Fredrick Koenig, both of Fort Wayne, Ind., assignors to General Electric Company, Fort Wayne, Ind.

Filed Oct. 26, 1979, Ser. No. 88,569

Int. Cl.³ H02K 15/04

U.S. Cl. 140—92.2

10 Claims



1. Apparatus for forming coils of wire windings for electric motors, said apparatus comprising: a coil form support structure, a coil form adapted for having wire wound thereabout, said coil form being connected to and supported by said support structure and having a free end, flyer means rotatable about said coil form for winding turns of wire about said coil form, said flyer means having a wire discharge point from which wire is fed directly about said coil form, the discharge point rotating in a winding plane, and a wire vibration damping device having a surface at least partially encircling said coil form and which defines a plane parallel and in close proximity to the winding plane on the opposite side of the winding plane as the free end of the coil form, said surface being inside the path of rotation of said flyer.

10. In a method of forming coils of wire for electric motor windings, the method comprising generating a plurality of turns of wire about coil form means by dispensing wire thereabout and moving at least some turns of a given coil along the coil form means toward and into turn receiving means while at least one other turn for the same coil is being generated, and wherein all of the turns are generated in the same general winding plane, by a flyer arm that guides wire along a path in which the wire is caused to make a turn with respect to a center of curvature prior to exiting the arm at the wire discharge point, wherein the center of curvature is located on one side of the winding plane, the improvement comprising: interfering with oscillatory wire movement on said one side of the winding plane and thereby damping oscillations of the wire while the turns are being generated.

4,296,785

SYSTEM FOR GENERATING AND CONTAINERIZING RADIOISOTOPES

John P. Vitello, Weston, Mass., and Glenn D. Grummon, Richmond Heights, Mo., assignors to Mallinckrodt, Inc., St. Louis, Mo.

Filed Jul. 9, 1979, Ser. No. 55,784

Int. Cl.³ B65B 3/04

U.S. Cl. 141—105

10 Claims


1. A system for eluting a daughter radioisotope from a parent radioisotope and for containerizing the resultant eluate in

an evacuated container having a closure adapted to be pierced by a needle, said apparatus comprising:

a generator containing a supply of the parent radioisotope, said generator having an inlet for an eluant for eluting the daughter radioisotope from the parent radioisotope and an outlet for the resultant eluate;

a reservoir for holding a supply of the eluant, said reservoir having an outlet for delivery of eluant to the inlet of the generator and an air inlet for admission to the reservoir of air from the atmosphere to apply atmospheric air pressure to eluant in the reservoir;

a tubular needle for piercing the closure of an evacuated container;



and valve means comprising a first port constituting an air inlet in communication with the atmosphere, a second port in communication with said reservoir air inlet, a third port interconnected with said reservoir outlet, a fourth port interconnected with said generator inlet, a fifth port interconnected with said generator outlet for delivery of eluate to the needle, and means for blocking communication between said first and second ports, between said third and fourth ports, and between said fifth port and the needle, and operable to place the first port in communication with the second, the third in communication with the fourth and the fifth in communication with the needle.

4,296,786

TRANSFER DEVICE FOR USE IN MIXING A PRIMARY SOLUTION AND A SECONDARY OR ADDITIVE SUBSTANCE

Dominic J. Brignola, Phoenixville, Pa., assignor to The West Company, Phoenixville, Pa.

Continuation of Ser. No. 661,869, Feb. 27, 1967, abandoned, which is a continuation-in-part of Ser. No. 333,650, Feb. 20, 1973, abandoned. This application Sep. 28, 1979, Ser. No. 79,867


Int. Cl.³ B65B 3/06

U.S. Cl. 141—309

32 Claims

1. A transfer device for use in mixing substances in different containers comprising a central body portion and a pair of cannulas projecting from opposite sides of said central body portion, each of said cannulas having an outer tip portion, means defining at least one pair of transfer passages extending through said cannulas and extending the full length of said cannulas from the tip portion of one cannula to the tip portion of the other cannula, the cross sectional area of one of said transfer passages adjacent the tip of one cannula being greater than the cross sectional area of said one transfer passage adja-

cent the tip of said other cannula, each of the transfer passages being of circular cross section, one of said transfer passages



converging toward the tip of one cannula and the other transfer passage converging toward the tip of the other cannula.

4,296,787

CONNECTION DEVICE FOR GOLF CLUB HEAD COVERS


C. D. Barton, 815 W. 53rd Ter., Kansas City, Mo. 64112

Filed Apr. 15, 1980, Ser. No. 140,439

Int. Cl.³ B65B 11/00; B65D 65/02; B65N 81/00

U.S. Cl. 150—52 G

10 Claims



1. A device for interconnecting a plurality of golf club head covers each having an eyelet, said device comprising:

an elongate flexible member extending between the eyelets of the head covers, said flexible member passing through the eyelet of each head cover to connect the head covers to one another;

means associated with opposite end portions of said flexible member for preventing the opposite end portions from passing through the eyelets located nearest the end portions; and

a plurality of tubular elements sleeved on said flexible member and extending substantially between the eyelets of the respective head covers in a manner to maintain the head covers spaced apart from one another, said tubular elements being resilient to permit flexing thereof.

4,296,788

CARRYING DEVICE

Peter G. Slater, 9 Ganung Dr., Ossining, N.Y. 10562

Filed Jun. 10, 1980, Ser. No. 158,150

Int. Cl.³ B65B 11/00; B65D 65/02; B65N 81/00

U.S. Cl. 150—52 R

5 Claims


1. A flexible fabric carrier comprising:

(a) a sheet member of substantially rectangular shape, positioned along a first side portion of the sheet,

(b) an elongated substantially rigid member adapted to be positioned along a first side portion of the sheet,

(c) supporting elements affixed to the sheet along said first side portion and adapted to receive the elongated rigid member, and

(d) attachment means at each of the end portions of the sheet not opposite said first side portion,



4,296,789

TREAD FOR PNEUMATIC TIRE

Charles W. Roberts, Akron; Michael A. Kolowski, Tallmadge;

Daniel J. Lindner, North Canton; John E. Lynch, Bedford;

Terrence M. Ruip, Akron, all of Ohio, and Harold D. Fetty,

Birmingham, Mich., assignors to The Goodyear Tire & Rubber Company, Akron, Ohio


Continuation of Ser. No. 877,790, Feb. 14, 1978, abandoned.

This application Dec. 11, 1980, Ser. No. 215,208

Int. Cl.³ B60C 11/10

U.S. Cl. 152—209 R

8 Claims



1. A pneumatic tire having a ground-engaging tread portion, said tread portion consisting of a plurality of independent buttons or projections placed circumferentially about said tire, said independent buttons or projections being spaced apart so as to provide a plurality of grooves adjacent the periphery of said buttons or projections, said grooves being sufficiently wide so as not to close up at the ground contacting surface when in the footprint of the tire, said tire characterized in that said tread is provided with a central zone and two shoulder zones which extend circumferentially about said tire, the width of said central zone and each of said shoulder zones being substantially less than the width of said tread, said central zone being located such that the longitudinal axial edges of said zone are spaced equidistant from the mid-circumferential plane of said tire, said central zone having a width ranging from 5% to 20% of the width of the tread of said tire and the depth of the recesses in between said projections in said central zone being between 25% and 60% of the depth of the recesses in between said projection in said remaining portion in between said central zone and said shoulder zones, said shoulder zones are spaced from and located axially outward from said central zone, one on either side of said central zone, and extend from each tread edge toward the mid-circumferential plane of said

tire, said shoulder zones having a width from about 5% to 20% of the width of said tread of said tire and the recesses in between said projections in said shoulder zone being from about 25% to 60% of the depth of the recesses in between said projection in said remaining portion in between said central zone and said shoulder zone.

4,296,790

LIGHT TIRE BODIES USING THICK CORDS

Yoshihiro Sakai, Kawasaki; Ryosaku Tanaka, Akigawa; Toshio Kita; Munetoshi Shimotake, both of Kodairo; Tsuguyoshi Yamada, Higashimurayama, and Hiroshi Ueda, Akigawa, all of Japan, assignors to Bridgestone Tire Company Limited, Tokyo, Japan

Filed Dec. 17, 1979, Ser. No. 104,217

Claims priority, application Japan, Dec. 27, 1978, 53/159694

Int. Cl.³ B60C 9/06, 15/06

U.S. Cl. 152—354 R

2 Claims



1. A light tire body for heavy vehicles comprising, a bias-structured carcass composed of rubberized plies each including thick organic fiber cords having a cord diameter equal to or larger than that of nylon 1,890 d/2, rubber interposed between said carcass plies having a thickness corresponding to $hm/ho \leq 0.5$ where, hm is an average rubber gauge between said plies at a center position in the widthwise direction of the tire, and ho is a diameter of said thick cord and being prepared from a compounding recipe of at least one rubber ingredient selected from natural rubber and diene synthetic rubbers, a softener, an organic vulcanization accelerator and sulfur as well as at least 30% by weight of carbon black having an average iodine adsorption value of 40–90 mg/g and an average dibutyl phthalate absorption value of 60–140 ml/100 g, and said rubber having a dynamic modulus of elasticity at 100° C. under 2% elongation of not less than 6.0×10^7 dyne/cm², a dynamic loss angle the tangent of which is not more than 0.095 and a tensile strength of not less than 100 kg/cm² as properties after vulcanization; and said carcass being provided with an apex rubber for stiffening a turnup portion of the carcass and a ratio in the dynamic modulus of elasticity of said apex rubber to said rubber interposed between the plies is within a range of 0.9–1.3.

4,296,791

FOLDING DOOR OR LIKE CLOSURE DEVICE

Bernard Chaumat, 10 Bd. Jourdan, 75014 Paris; Georges Gallet, 6 rue du 11 Novembre, 95110 Sannois; Jacques Lamare, 21 Bd. Richard Wallace, 92200 Neuilly-sur-Seine, and Guy Peysard, 30 rue Raze, 33000 Bordeaux, all of France

Filed Jan. 22, 1980, Ser. No. 114,429

Claims priority, application France, Jan. 25, 1979, 79 01931

Int. Cl.³ E05D 15/26


U.S. Cl. 160—206

9 Claims

1. A door or like closure device, comprising a fixed frame, a primary panel pivoted about a first axis A on the frame and at least one secondary panel connected to the primary panel by a link articulated by a second axis B to the primary panel and a third axis C to the secondary panel, said secondary panel being

in addition guided at a fourth axis D in a slide guide extending perpendicular to the first axis A, and wherein:

- (i) the four axes A, B, C, and D are disposed in the centre of the thickness of the panels;
- (ii) the distance between the second axis B and the third axis C is equal to the thickness of the panels;



- (iii) the distance between the third axis C and the fourth axis D is equal to the distance between the first axis A and the second axis B;
- (iv) the fourth axis D is carried by the secondary panel at an intermediate point thereof; and
- (v) means are provided for holding said link constantly perpendicular to the bisector plane of the primary and secondary panels.

4,296,792

TRANSPARENT REACH-THROUGH CURTAIN FOR OPEN REFRIGERATORS


Kenneth N. Gidge, Nashua, N.H., and Henry J. Richard, Lowell, Mass., assignors to BSL Corporation, Nashua, N.H.

Filed Feb. 5, 1979, Ser. No. 9,049

Int. Cl.³ A47H 1/00

U.S. Cl. 160—332

6 Claims



1. A reach-through curtain for use over the opening in an open display type refrigerator or the like, comprising

- (a) a plurality of elongated, flexible, transparent, imperforate panels of generally rectangular outline each connectable at least at one end to said refrigerator proximate to an edge of said opening,
- (b) said panels extending in parallel, overlapped relation across said opening and defining slit access means between adjacent panels,
- (c) each of said panels being of a length sufficient to span said opening in one direction,
- (d) said panels being of a sufficient number and width to span said opening in another direction perpendicular to said one direction,
- (e) the long edges of each of said panels being tubular, and,
- (f) a colored, relatively short sleeve mounted in each tubular edge of said panel for visibly enhancing the access joints between adjacent panels and for reinforcing the tubular shape of the long edges.

4,296,793

REFRACTORY SUSPENSION FOR MAKING FOUNDRY MOULDS

Konstantin K. Yasinsky, ulitsa Spartakovskaya, 18, kv. 52; Sergei G. Glazunov, Leninsky prospekt, 41, kv. 62, both of Moscow; Jury N. Ross, ulitsa Patrioticheskaya, 74, kv. 36, and Igor D. Bykov, ulitsa Turgenyeva, 44, kv. 6, both of Zaporozhie, all of U.S.S.R.

Continuation of Ser. No. 835,689, Sep. 22, 1977, abandoned. This application May 10, 1979, Ser. No. 37,839

Int. Cl.³ B28B 7/36

U.S. Cl. 164—24

9 Claims

1. A refractory suspension for making lost wax foundry moulds for casting pieces of chemically-active metals, the ratio of suspension constituents consisting essentially of as follows (parts by weight): coke, 10-60; a powdered metal selected from the group consisting of titanium, zirconium and a mixture thereof, 0.3-5.0; resol resins, 5-50; a hardener selected from the group consisting of an organic and inorganic acids, 2-30; an organic solvent, 20-60.

8. A method for making lost wax foundry moulds comprising the steps of:

- (a) forming a suspension consisting essentially, in percent by weight, of coke, 10-60; a powdered metal selected from the group consisting of titanium, zirconium, and mixtures thereof, 0.3-5.0; resol resins, 5-50; a hardener selected from the group consisting of organic and inorganic acids, 2-30; and an organic solvent, 20-60;
- (b) providing a wax pattern;
- (c) coating the pattern with the suspension at least four times, and sprinkling said pattern with powdered coke;
- (d) drying the coating to obtain a rigid mould;
- (e) melting the wax pattern from its rigid mould; and
- (f) curing the mould by heating to about 1300°-1350° C.

4,296,794

METHOD OF TRANSMISSION OF SONIC ENERGY TO WORK PIECES


Raymond M. Leliaert, South Bend, Ind., assignor to Wheelabrator-Frye Inc., Hampton, N.H.

Filed Jan. 14, 1980, Ser. No. 111,487

Int. Cl.³ B22D 29/00

U.S. Cl. 164—131

3 Claims



1. A method for transmitting vibratory energy to a part from a vibratory member adapted to vibrate at sonic frequency comprising securing a fixture to said vibratory member, said fixture having spaced abutment surfaces, inserting the part into the fixture to between said abutment surfaces whereby the clearance between one abutment surface and the adjacent surface of the work piece, while the work piece is at rest on the other abutment surface, is within the range of $\pm 50\%$ of the amplitude of the vibrations at the point of attachment of the fixture to the vibration generator.

4,296,795

PNEUMATICALLY OPERATED CONTROL SYSTEM AND UNIT THEREFOR AND METHODS OF MAKING THE SAME


Jay L. Lewis, Knoxville, Tenn., assignor to Robertshaw Controls Company, Richmond, Va.

Filed May 2, 1980, Ser. No. 146,337

Int. Cl.³ F25B 29/00

U.S. Cl. 165—27

40 Claims



1. In a pneumatically operated system having control means provided with a single inlet interconnected to a one pressure level pneumatic source and having outlet means interconnected to pneumatically operated heating and cooling heat exchanger means to control the same in either its heating mode or its cooling mode in relation to the pressure value of the pneumatic signal means being directed thereto from said control means through said outlet means thereof, said control means having temperature sensing means for controlling said value of said signal means in relation to the sensed output temperature effect of said heat exchanger means by operating bleed means of said control means, the improvement wherein said outlet means comprises a single outlet and said bleed means comprises a single bleed device having an arrangement of parts thereof that is the same regardless of whether said heat exchanger means is operating in its heating mode or in its cooling mode whereby said heat exchanger means is adapted to be operated in either its heating mode or its cooling mode by said single bleed device without changing said arrangement of said parts of said bleed means.

2. In a pneumatically operated system having control means provided with a single inlet interconnected to a one pressure level pneumatic source and having outlet means interconnected to pneumatically operated heating and cooling heat exchanger means to control the same in either its heating mode or its cooling mode in relation to the pressure value of the pneumatic signal means being directed thereto from said control means through said outlet means thereof, said control means having temperature sensing means for controlling said value of said signal means in relation to the sensed output temperature effect of said heat exchanger means by operating bleed means of said control means, the improvement wherein said outlet means comprises a single outlet and said bleed means comprises a single bleed device whereby said heat exchanger means is adapted to be operated in either its heating mode or its cooling mode by said single bleed device, said sensing means having means providing a "dead band" temperature range so that said bleed device will remain in a certain condition thereof to provide said signal means with a certain value as long as said sensed output temperature effect falls within said "dead band" temperature range.

4,296,796

HEAT TRANSFER SYSTEM

Helmut Wulf, Ostfildern, Fed. Rep. of Germany, assignor to Daimler-Benz Aktiengesellschaft, Stuttgart, Fed. Rep. of Germany


Filed Aug. 28, 1979, Ser. No. 70,505

Claims priority, application Fed. Rep. of Germany, Sep. 21, 1978, 2841051

Int. Cl.³ F28D 15/00

U.S. Cl. 165—46

6 Claims



1. A heat transfer system for transferring heat between a heat-emitting means and a heat-consuming means in accordance with a heat pipe principle, characterized in that a vacuum-tight hose conduit means is arranged between the heat-emitting means and the heat-transfer means for communicating the respective means with each other, a longitudinally-extending groove structure is disposed interiorly of the hose conduit means for supporting the hose conduit means against excessive external pressure and for providing an internal capillary structure, and in that a threaded connection means is provided for connecting respective ends of the hose conduit means into a heat transfer path.

4,296,797

RIGID SHELL FOR BUILDING STRUCTURES

George R. Beggs, 602 S. Tejon, Colorado Springs, Colo. 80903

Filed Dec. 6, 1979, Ser. No. 100,954

Int. Cl.³ F25B 29/00

U.S. Cl. 165—48 S

8 Claims


1. A rigid shell for a building structure, which comprises:

- (a) a pair of rigid, vertical supporting frames disposed parallel to and spaced from one another by a distance equal to the length of the shell, each of the frames comprising:
 - (1) a pair of spaced, horizontally disposed load-bearing elements and
 - (2) a pair of spaced, vertically disposed load-bearing members integral with and secured to the pair of horizontal elements at points spaced from the ends of said elements by from $\frac{1}{4}$ th to $\frac{3}{4}$ th their respective lengths;
- (b) a second pair of rigid, vertical supporting frame disposed parallel to and spaced from one another widthwise of the shell and at right angles to the first pair of supporting frames, each of the second pair of frames comprising:
 - (1) a second pair of spaced, horizontally disposed load-bearing elements and
 - (2) a second pair of spaced, vertically disposed load-bearing members integral with and secured to the second pair of horizontal elements, said members abutting the vertical load-bearing members of the first pair of supporting frames and being secured thereto along substan-

tially their entire length to define four vertically disposed, load-bearing columns for the shell;

(c) a plurality of further rigid, vertical supporting frames in spaced relation lengthwise of the shell, intermediate and parallel to the first pair of supporting frames, each of the plurality of frames comprising:

- (1) a third pair of spaced, horizontally disposed load-bearing elements extending across and being supported by the respective members of the pair of horizontal load-bearing elements of each of the second pair of supporting frames, and



(2) a third pair of spaced, vertically disposed load-bearing members integral with and secured to the third pair of horizontal elements;

the plurality of further supporting frames being supported by the first and second pairs of supporting frames and, in turn, providing the structural support for the side walls, roof and floor of the building structure defined by said shell; and

(d) structurally supporting materials covering at least 20% of the side and end wall and roof surfaces defined by said shell to impart sufficient stability to resist climatic torsional and eccentric loading conditions imposed thereon.

4,296,798

INTEGRATED HOUSE

Horst Schramm, Schellingstr. 16., D-6000 Frankfurt am Main, Fed. Rep. of Germany

Filed Nov. 13, 1978, Ser. No. 959,417

Claims priority, application Fed. Rep. of Germany, Nov. 15, 1977, 2750918

Int. Cl.³ F24D 5/10; F24J 3/02; E04B 1/70


U.S. Cl. 165—56

8 Claims

6. An integrated house comprising:

- an intensively insulated outside shell comprising:
 - an intensively insulated exterior walls;
 - an insulated roof attached to and disposed above said exterior walls;
 - an insulated cellar attached to and disposed below said exterior walls; and
 - at least one window located on said exterior walls and each of which comprise:
 - two panes;
 - a window frame spacing apart and holding said panes; and
 - an inner and outer portion formed by said exterior wall and receiving said window frame in sealed-together relationship; and
- a plurality of connected interior walls and floors, forming a structure which is attached to and surrounded by said outer shell, and comprising:
 - two ribbed, pre-formed concrete slabs, interpositioned in

order to have hollow spaces therebetween, said interior walls and floors arranged in order to integrate said hollow spaces and form air circuits;
a heating means connected to said air circuits; and
a cooling means connected to said air circuits,




whereby heat may be transferred to and taken from said interior walls and floors via air passing through said interior walls and floors in said air circuit thus heating or cooling said integrated house.

4,296,799 SOLAR WATER TANK AND METHOD OF MAKING SAME

Richard S. Steele, 897 E. 12th Ave., Broomfield, Colo. 80020
Filed May 29, 1979, Ser. No. 43,131
Int. Cl.³ F28D 1/06

U.S. Cl. 165—74

26 Claims



1. A water tank adapted for solar heating systems, comprising:

an insulated rigid shell enclosing a chamber therein adapted for containing a fluid medium, said shell having an access hole therein, including a flexible plastic liner positioned within said chamber around the periphery thereof a spaced distance inwardly from said shell, and a foam insulation material uniformly filling the space between said shell and said liner;

an insulated cover for said access hole adapted to be positioned over said access hole and to be removably attached in that position to said shell;

a flow systems assembly extending through and attached to said cover, said flow systems assembly including fluid inlet and outlet tubes and water inlet and outlet tubes for conducting the flow of fluids and water, respectively, into and out of said chamber, and heat exchanger means for facilitating heat transfer from the fluid to the water within said chamber; and

attachment means on said cover and said shell for removably attaching said cover to said shell over said access hole

with said flow systems assembly extending therethrough and positioned inside said shell.

4,296,800 WASTE HEAT RECOVERY


Paul H. Johnson, Bartlesville, Okla., assignor to Phillips Petroleum Company, Bartlesville, Okla.

Filed Apr. 18, 1980, Ser. No. 141,502

Int. Cl.³ F28D 13/00

U.S. Cl. 165—95

3 Claims



1. A fluidized bed shell-tube heat exchange vessel adapted to recover heat from or transfer heat to gas streams containing suspended light solids flowing upwardly through a multiplicity of vertically disposed tubes on the tube side of said exchanger, said tubes containing particulate heat exchange solids, said solids being maintained as a fixed fluidized bed of solids within each of said tubes by the upward flow through said tubes of said fluid containing light suspended solids which comprises, in combination:

(a) an elongated substantially vertical vessel having an inlet conduit connected to a lower portion and an outlet conduit connected to an upper portion of said vessel,

(b) a grid or distributor plate in the lower portion of said vessel adapted to support a bed of particulate solids above said grid and allow gas to pass into said bed of particulate solids,

(c) a fixed bed of particulate fluidizable solids extending a substantial distance above said grid into an intermediate portion of said vessel,

(d) a shell-tube heat exchanger section having a plurality of tubes positioned within said vessel above said grid but below the top of said fixed bed of solids with the tubes being substantially vertical and all being filled with said particulate solids and in open communication with the inlet and outlet conduits so that the heat exchange fluid passing through the shell side can absorb heat from or transfer heat to a gas stream containing entrained solids passing through the tubes containing said particulate solids, said tubes in said shell-tube heat exchanger being so sized as to be of a diameter of at least one foot and sufficient height to diameter ratio to allow recirculation of the particulate solids within each tube to maintain the inner peripheries of the tubes substantially freed from deposits to permit efficient heat exchange, and

(e) a gas-solids separator positioned within an upper portion of said vessel connected to said outlet conduit and adapted to separate entrained particulate solids from the gas stream exiting said vessel and return same to said bed.

4,296,801 REUSABLE HEAT DEVICES CONTAINING XYLITOL AS THE HEAT-STORAGE MATERIAL

Woldemar Guex, 4 Spechtweg, Bottmingen; Heinrich Klauel, 77 Kilchgrundstrasse, Riehen; Horst Pauling, 39 Ruchholzstrasse, Bottmingen, and Felix Voirel, 26 Poolstrasse, Füllinsdorf, all of Switzerland

Continuation of Ser. No. 916,242, Jun. 16, 1978, abandoned. This application May 20, 1980, Ser. No. 151,568

Claims priority, application Fed. Rep. of Germany, Oct. 24, 1977, 2747664

Int. Cl.³ F28D 13/00; F24H 7/00

U.S. Cl. 165—104.17

6 Claims

1. A heat device comprising a container having therein xylitol as a heat-storage material.

4,296,802 STEAM CONDENSING APPARATUS


Michael W. Larinoff, Houston, Tex., assignor to Hudson Products Corporation, Houston, Tex.

Continuation-in-part of Ser. No. 585,951, Jun. 16, 1975, abandoned. This application May 28, 1976, Ser. No. 690,883

Int. Cl.³ F28B 9/06

U.S. Cl. 165—110

4 Claims



1. Apparatus for use in condensing steam from the turbine exhaust of a power plant or the like, comprising a steam condenser having inlet means for receiving steam from the turbine exhaust, hot well means to receive condensed steam, and outlet means for returning condensate from the hot well to the power cycle, cooling tower means having a wet section and a dry section, the wet tower section having an inlet to receive a first cooling medium, an outlet for discharging the first medium, and means for cooling the first medium with ambient air as it passes from the inlet to the outlet, the dry tower section having an inlet to receive a second cooling medium, an outlet for discharging the second medium, and means for cooling the second medium with ambient air as it passes from the inlet to the outlet, means for circulating the first medium from the outlet from the wet cooling tower section into and through tubes within the condenser and then returning it to the inlet to said wet cooling tower section, means for circulating the second medium from the outlet from the dry cooling tower section into and through the condenser and then returning it to the inlet to said dry cooling tower section, means for interrupting the circulation of said first medium between said wet tower section and said condenser tubes, means for emptying said first medium from the tubes and then filling said tubes with the second medium, when such circulation is interrupted, and means for emptying the second medium from the tubes and then refilling the tubes with the first medium, whereby circulation of said first medium between said wet tower section and said condenser tubes may be resumed.

4,296,803 PLATE USED IN CONDENSER

Hiroyuki Sumitomo, Osaka, Japan, assignor to Hisaka Works, Ltd., Osaka, Japan


Continuation of Ser. No. 927,689, Jul. 25, 1978, Pat. No. 4,228,853. This application Nov. 14, 1979, Ser. No. 93,983

Claims priority, application Japan, Nov. 8, 1977, 52-134254

Int. Cl.³ F28B 9/08; F28D 9/02; F28F 3/08

U.S. Cl. 165—110

1 Claim



1. A plate for use in a condenser for condensing a vapor to a condensate, said plate having a surface and including condensate collecting and discharging elements, said vapor and said condensate flowing downwardly through the condenser, said condensate collecting and discharging elements comprising a plurality of V-shaped inclined grooves downwardly sloped towards a central portion of said plate, and a single vertical groove formed along said central portion of said plate connecting with a lowest portion of each of said inclined grooves, said vertical groove having an axis, each of said inclined grooves having a pair of edges comprising a first edge and a second edge at the intersection of said inclined groove and the vertical groove, each pair of edges being in a single plane perpendicular to the plane of the surface of said plate and perpendicular to the axis of the vertical groove, wherein said inclined grooves form ramps leading to said vertical groove and said vertical groove forms a recessed channel, the direction of flow of said condensate substantially coinciding with the direction of flow of said vapor across the entire surface of the plate, whereby said inclined grooves and said vertical groove minimizes the area of a filmy downflow liquid layer and prevents a film from growing too thick, thereby improving the heat transfer surface of said plate.

4,296,804 CORROSION RESISTANT HEAT EXCHANGER ELEMENT AND METHOD OF MANUFACTURE

Irving D. Press, West Orange; Harvey R. Nickerson, Roseland, and Helm Rink, North Haledon, all of N.J., assignors to Resistoflex Corporation, N.J.

Filed Jun. 28, 1979, Ser. No. 52,759


Int. Cl.³ F28F 9/16, 19/04

U.S. Cl. 165—133

12 Claims

1. A heat exchanger element for use in a corrosive environment comprising a metal tube jacketed at least over a substantial portion of its length including at least one end with an extruded layer of a given fluorocarbon resin having a thickness within the limits affording efficient heat transfer combined with resistance to corrosion of said tube, said given resin being of the type which has a high viscosity in the melt stage, a nipple of corrosion resistant metal, said nipple having a first end with a circumferential shoulder thereat and an axial region adjacent said shoulder which region has a lesser diameter than said shoulder providing an undercut annular groove therebehind, said first end of said nipple being telescopically engaged within said one end of said metal tube, and said nipple having an opposite end which projects from said one end of said metal tube, a sleeve of fluorocarbon resin surrounding said one end of said metal tube and at least a portion of said opposite end of


said nipple, said sleeve extending over said metal tube and its jacket layer of resin to a point beyond the location of said nipple shoulder, and a corrosion resistant metal ferrule surrounding said sleeve of resin and being substantially coextensive therewith, said ferrule being contracted radially squeezing



extending through said volume between said front and rear walls and in spaced relationship to said peripheral wall for defining a clearance hole allowing access through said core between the opposite faces thereof, said peripheral wall including a plurality of ferrules integral therewith with each ferrule surrounding and in sealing engagement with one of said first and second ends of said group of tubes said peripheral wall including top and bottom walls and said ferrules extending from said top and bottom walls in the same direction.

4,296,806
HIGH TEMPERATURE WELL PACKER
Donald F. Taylor, Dallas, and James H. Bostock, Denton, both of Tex., assignors to Otis Engineering Corporation, Dallas, Tex.

Filed Oct. 5, 1979, Ser. No. 82,406
Int. Cl.³ E21B 33/128, 33/129; F16J 15/12, 15/14
U.S. Cl. 166—120 22 Claims



11. In a packer for forming a seal with the inner wall of a casing string and having a sealing unit carried on a mandrel means, the sealing unit comprising:

- each end element having a partially elliptical cross section with parallel cylindrical inside and outside diameters;
- the major axis of the partially elliptical cross sections forming an acute angle with the exterior of the mandrel means when the sealing unit is in its first position; and
- the major axis moving towards a position normal to the mandrel means when the sealing unit is in its second position.


17. In a well packer, for sealing between the outside diameter of a tubing string and the inside diameter of a casing string disposed within a well bore, the sealing unit, carried on the exterior of a mandrel means, comprising a center element, end elements, and backup rings wherein:

- the center element is selected from the group consisting of ethylene propylene-diene terpolymer, vinylidene fluoride and hexafluoropropylene copolymer, and polytetrafluoroethylene; and
- the end elements are selected from the group consisting of vinylidene fluoride, hexafluoropropylene copolymer, asbestos, graphite, and ceramic fibers with each being reinforced by wire mesh.

said metal tube within said axial region behind said nipple shoulder thereby effecting interlocking engagement between said metal tube and said nipple and establishing a fluid-tight seal between said ferrule, said nipple, said metal tube and the intervening resin material.

4,296,805
ACCESSORY CLEARANCE HOLE
James C. Fleury, Ora, Ind., assignor to Ex-Cell-O Corporation, Troy, Mich.


Filed Dec. 17, 1979, Ser. No. 104,588
Int. Cl.³ F28D 1/04
U.S. Cl. 165—151 10 Claims



1. A heat exchanger assembly comprising: a core having front and rear faces and including tubes parallel to said faces and fins extending transversely to said faces and said tubes respectively and interconnecting said tubes, a group of said tubes and a first plurality of said fins defining an opening extending between said faces along the lengths thereof and between the opposite ends of said tubes and said fins, said opening being defined by each of said tubes in said group being devoid of a length thereof so that each of said tubes in said group has spaced first and second open ends and each of said fins in said first plurality being devoid of a length thereof so that each of said fins in said plurality has spaced ends, a single tank in fluid communication with said first and second ends to establish fluid communication therebetween, said tank having front and rear walls disposed adjacent said front and rear faces respectively of said core and a peripheral wall extending about said opening and interconnecting said front and rear walls to define an enclosed volume within said tank, and a tubular member

4,296,807
CROSSOVER TOOL
James D. Hendrickson, Carrollton, and Pat M. White, Lewisville, both of Tex., assignors to Halliburton Company, Duncan, Okla.

Filed Dec. 27, 1979, Ser. No. 107,752
Int. Cl.³ E21B 33/124
U.S. Cl. 166—184 23 Claims




1. A crossover tool for use in a well bore, comprising: body means having first and second passage means therethrough, said first passage means extending from the top of said body to the bottom thereof at a first location, said second passage means extending from at least one side of said body to the bottom thereof at a second location; sleeve means longitudinally slidably disposed about said body means, said first passage means communicating with the bore of said sleeve means, said sleeve means having at least one port therethrough circumferentially aligned with said side extent of said second passage means and being juxtaposed therewith in a first sleeve position and longitudinally removed therefrom in a second sleeve position; packer means disposed about said body means below the lowest point of longitudinal travel of said sleeve means; selectively closeable bypass passage means in said body means extending from the outside of said body means above said packer means to the outside of said body means below said packer means; and selection means to select each of said positions in response to longitudinal movement of said sleeve means.

4,296,808
ISOLATION PACKER EXTENSION
Eugene E. Baker, and Ernest E. Carter, Jr., both of Duncan, Okla., assignors to Halliburton Services, Duncan, Okla.
Division of Ser. No. 958,706, Nov. 8, 1978. This application Aug. 4, 1980, Ser. No. 174,820
Int. Cl.³ E21B 33/124

U.S. Cl. 166—191 5 Claims

1. An isolation packer extension, comprising: a cylindrical middle body, said middle body including an axial bore therethrough for receiving an upper inner mandrel therein, a first axial counterbore communicating with an upper end of said middle body, and a second axial counterbore communicating with a lower end of said middle body; a bypass means, communicating said first axial counterbore with said second axial counterbore; a spacer coupling, connected at an upper end to said middle body, said spacer coupling being constructed for connection at its lower end to a lower body, to which lower body is attached a lower packer assembly; and

a lower inner mandrel, an upper end of which is closely received in said axial bore of said middle body, and a



lower end of which is constructed to be closely received within an axial bore of said lower body.

4,296,809
IN SITU GASIFICATION OF BITUMINOUS COAL
Shirley C. Tsai, Pittsburgh; Richard H. Graham, O'Hara Township, Allegheny County, and Robin R. Oder, Export, all of Pa., assignors to Gulf Research & Development Company, Pittsburgh, Pa.

Filed Jul. 21, 1980, Ser. No. 170,796
Int. Cl.³ E21B 43/247; E21C 43/00
U.S. Cl. 166—259 11 Claims


1. In the underground gasification of a swellable bituminous coal by the injection of air into the high gas flow linkage between an injection hole and a production hole accompanied by the concurrent underground partial combustion and gasification of said coal, a method for pretreating and conditioning the coal proximate to said linkage before said partial combustion and gasification is initiated which comprises the step of injecting pretreating air at a temperature between about 100° C. and up to about the softening temperature of said coal into said injection hole and through said linkage to said production hole in the absence of combustion at a flow rate and for such time as will substantially reduce the swelling of said coal proximate to said linkage, whereby the gas permeability of said coal proximate to said linkage is enhanced and the plugging of said linkage in the subsequent partial combustion and gasification step is suppressed.

4,296,810
METHOD OF PRODUCING OIL FROM A FORMATION FLUID CONTAINING BOTH OIL AND WATER
Ernest H. Price, 1266 Pepper Dr., El Centro, Calif. 99243
Filed Aug. 1, 1980, Ser. No. 174,350
Int. Cl.³ E21B 43/02, 43/38

U.S. Cl. 166—265 6 Claims

1. A method of producing oil from a formation fluid containing both oil and water comprising the steps of: providing a production casing in a well bore traversing both a production zone and a disposal zone located at vertically spaced apart levels with respective sets of perforations connecting the interior of the production casing with the two said zones; drawing formation fluid from the production zone through said perforations into a separator assembly disposed within said casing in the region of the production zone, causing the formation fluid to pass in contact with a sur-

face of filter medium of the separator assembly, which filter medium is permeable to one component of the formation fluid; maintaining a pressure gradient across said filter medium; and



pumping the separated oil from one side of the filter medium to the surface and pumping the separated water from the other side of the filter medium through the production casing to said disposal region and discharging said water at said disposal level.

4,296,811

METHOD FOR PERMEABILITY CORRECTION BY IN SITU GENESIS OF MACROEMULSIONS IN HARD BRINE

Charles W. Morris, Sante Fe Springs, Calif., and Ronald E. Terry, Lawrence, Kans., assignors to Phillips Petroleum Company, Bartlesville, Okla.

Filed Jul. 6, 1978, Ser. No. 922,453

Int. Cl.³ E21B 33/138, 43/22

U.S. Cl. 166—273

17 Claims

1. A process for recovering oil from a subterranean oil-bearing reservoir having zones of varying permeability and containing connate water having divalent ions comprising the steps of:

(a) injecting into said reservoir through at least one injection well a surfactant system, thereby selectively plugging high permeability zones, said surfactant system comprising: water; 0.5 to 12 weight percent based on the weight of said water of a petroleum sulfonate surfactant having an average equivalent weight within the range of 375 to 500; 250 to 17,000 parts per million by weight of a predominantly sodium chloride electrolyte based on the weight of said water; and 1 to 12 weight percent based on the weight of said water of a cosurfactant selected from the group consisting of amides, amines, esters, aldehydes and ketones containing 1 to 20 carbon atoms and alcohols containing 4 to 7 carbon atoms, which cosurfactant has a solubility in water within the range of 0.5 to 20 grams per 100 grams of water, said surfactant system having less than 1 weight percent oil;

(b) thereafter injecting a secondary or tertiary oil recovery system through at least one injection well so as to displace oil toward at least one recovery well; and

(c) recovering oil from said at least one production well.

4,296,812 SURFACANT WATERFLOODING OIL RECOVERY METHOD

George Kalfoglou, Houston, Tex., assignor to Texaco Inc., White Plains, N.Y.

Continuation-in-part of Ser. No. 46,132, Jun. 6, 1979, abandoned. This application Dec. 21, 1979, Ser. No. 106,212
Int. Cl.³ E21B 43/22

U.S. Cl. 166—274

14 Claims

1. In a method for recovering petroleum from a subterranean, permeable, petroleum-containing earth formation penetrated by at least one injection well and by at least one production well, by a surfactant waterflooding method comprising injecting an aqueous fluid containing from 0.5 to 10.0 percent of an alkylpolyalkoxyalkylene sulfonate, an alkylarylalkoxyalkylene sulfonate, or a mixture thereof, having the following formula:



wherein R_a is an alkyl group having from 6 to 24 carbon atoms, or an alkylaryl consisting of benzene, toluene or xylene having attached thereto at least one alkyl group containing from 5 to 22 carbon atoms, R_a' is ethylene or a mixture of ethylene and higher molecular weight alkylene with relatively more ethylene than higher alkylene, R_a'' is ethylene, propylene, hydroxypropylene or butylene, n_a is a number from 1 to 20, and M is sodium, potassium, lithium or ammonium, said fluid being injected into the formation via the injection well and displacing petroleum through the formation to the producing well where it is recovered to the surface of the earth, the improvement which for increasing the oil recovery effectiveness of the aqueous surfactant fluid comprises:

incorporating in the surfactant fluid, an effective amount in the range of from 10 to 1000 parts per million of silica-polydialkylsiloxane comprising silica having particle size in the range from 0.005 microns to 2.0 microns wherein the polydialkylsiloxane has the following formula:



wherein R_b and R_b' are each a C_1 to C_6 alkyl, nb is a number from 1 to 2000, H is hydrogen, O is oxygen, and Si is silicon.

4,296,813

WELL CEMENTING

William J. Detroit, Schofield, and Michael E. Sanford, Wausau, both of Wis., assignors to American Can Company, Greenwich, Conn.


Division of Ser. No. 671,159, Mar. 29, 1976, Pat. No. 4,065,318.

This application Feb. 7, 1977, Ser. No. 766,079

Int. Cl.³ C04B 7/02, 7/35; C07G 1/00; E21B 33/13

U.S. Cl. 166—293

18 Claims



1. In the process of drilling wells and borings into the earth's surface, including the injection of a hydraulic cement mixture thereto, the improvement that comprises including in said hydraulic cement mixture, between about 0.05 percent and

about 3 percent by weight of the resulting mixture, of a retarding agent composition for said hydraulic cement mixture that is an alkaline oxidized, hydrolyzed, partially desulfonated and subsequently resulfonated lignosulfonate, said resulfonated lignosulfonate having substituted therein as the resulfonation units, those of the formula:



said resulfonated lignosulfonate containing, on a percent by weight basis, based on composition weight, between about 1½ weight percent and about 15 weight percent of total sulfur in combined organic sulfonic sulfonate form; said lignosulfonate prior to resulfonation having a relative molecular size of substantially 1,000 to 20,000.

4,296,814

METHOD FOR THERMALLY INSULATING WELLBORES


John L. Stalder, Ventura, Calif., and William L. Martin, Ponca City, Okla., assignors to Conoco Inc., Ponca City, Okla.

Filed Jul. 18, 1980, Ser. No. 170,273

Int. Cl.³ E21B 43/24

U.S. Cl. 166—303

23 Claims



1. A method of thermally insulating a well bore containing a tubing string to reduce heat transfer between the well bore and surrounding formations comprising the steps of: introducing a heat-activated gel-forming fluid having heat insulating properties when gelled between said well bore and tubing string; and causing said gel-forming fluid to be heated and thereby gelled.

4,296,815

DEFLECTOR WITH CONVERGING LOWER TINES FOR HORIZONTAL SPRINKLER

James W. Mears, Warwick, R.I., assignor to Grinnell Fire Protection Systems Company, Inc., Cranston, R.I.

Filed Mar. 10, 1980, Ser. No. 128,818


Int. Cl.³ A62C 37/08

U.S. Cl. 169—37

6 Claims

1. A fire protection sprinkler head including a throat through which a nearly horizontal stream of fire retardant fluid can flow and a deflector spaced downstream from the flow emerging out of said throat, said deflector including a generally planar confining element more nearly horizontal than vertical which is positioned above the longitudinal axis of said throat for the purpose of confining the upward trajectory of a portion of the stream and a plurality of fluid-deflecting ele-

ments positioned below the confining element for the purpose of deflecting and distributing other portions of the stream, some of said fluid-deflecting elements defining between themselves a plurality of slots extending generally outwardly from beneath said axis, at least one of said slots extending generally



downward from said axis, the improvement wherein said downwardly-extending slot is substantially narrower in width at its outermost extremity than at an intermediate location that is closer to said axis, so as to raise the trajectory of fluid passing through said slot.

4,296,816

HORIZONTAL SPRINKLER DEFLECTOR WITH FLOW LIFTING FORMATION


Michael A. Fischer, North Kingstown, R.I., assignor to Grinnell Fire Protection Systems Company, Inc., Cranston, R.I.

Filed Mar. 10, 1980, Ser. No. 128,820

Int. Cl.³ A62C 37/08

U.S. Cl. 169—37

19 Claims



1. In a fire-protection sprinkler head of the horizontal-sidewall type, including a throat through which a horizontal stream of fire-retardant fluid can flow, a deflector spaced from said throat and in the path of said stream for generating a spray into an area, said deflector including a generally planar confining element more nearly horizontal than vertical disposed above the longitudinal axis of said throat for the purpose of confining the upward trajectory of a portion of said stream and a deflector structure below said element for the purpose of deflecting and distributing other portions of said stream in various desired directions, said confining element extending generally longitudinally along the direction of said axis from an upstream end to a downstream end, a portion of said stream being incident upon the undersurface of said confining element and being caused to flow generally parallel to said undersurface from said upstream end to said downstream end, the improvement wherein

said confining element is deformed upwardly along an area extending longitudinally from said downstream end to a region intermediate said upstream and downstream ends, thereby forming an upwardly-deformed area and generally undeformed areas laterally adjacent to said upwardly-deformed area, the undersurface of said upwardly-deformed area being inclined upward relative to the undersurfaces of said generally undeformed areas, and

said upward inclination being chosen so that a portion of said stream entering said upwardly-deformed area is lifted upwardly from a flow direction generally parallel to the undersurface of said generally undeformed areas to a relatively upwardly inclined flow direction, whereby the lifted portion of said stream departs from said confining element with a trajectory more upwardly inclined than the trajectory of other portions of said stream, thereby causing said lifted portion to reach more distant areas from said sprinkler head.


4,296,817

FIRE SUPPRESSION SYSTEM FOR MILITARY TANKS
Anthony J. Monte, Utica, Mich., assignor to The United States of America as represented by the Secretary of the Army, Washington, D.C.

Filed Nov. 5, 1979, Ser. No. 91,423
Int. Cl.³ A62C 35/12

U.S. Cl. 169—62

1 Claim



1. In a military tank, a hull having an internal bulkhead defining a driver compartment and an engine compartment, a rotary turret carried by the hull, and a man-accommodating basket depending from the turret into the drive compartment; the improvement consisting of means for suppressing fires in the engine compartment or in the hull space beneath the basket; said fire-suppressing means comprising first, second and third pressure-resistant bottles positioned in the driver compartment; vaporizable pressurized fire-suppressant charged into each bottle; first conduit means oriented to discharge first bottle suppressant into the engine compartment; a first electrically-operated valve for controlling flow through the first conduit means; second conduit means oriented to discharge second bottle suppressant into the engine compartment; a second electrically-operated valve for controlling flow through the second conduit means; third conduit means oriented to discharge third bottle suppressant into the hull space beneath the basket; a third electrically-operated valve for controlling flow through the third conduit means; a cabinet located in the hull within reach of the human driver; first, second and third manual switches located in the cabinet for actuation by the driver to trigger respective ones of the valves to their open conditions; flame-responsive sensor means for detecting the occurrence of a fireball in the engine compartment; an alarm device located in the cabinet and energizable by said sensor means to alert the driver to the presence of a fire in the engine compartment; an electrical circuit operated by the sensor means to trigger at least one of the first and second valves to the open condition, whereby fires in the engine compartment can be suppressed automatically or under manual control, and fires in the hull space beneath the basket can be suppressed under manual control; fourth, fifth and sixth manual switches located within the cabinet in electrical parallelism with respective ones of the first, second and third switches; and a cable operator for each of the fourth, fifth and sixth switches; each cable operator being accessible from a point external to the hull; each of the fourth, fifth and sixth switches being a toggle switch having a lever operator; each cable operator

including an apertured element (66) and a tension spring (70); each apertured element having one of its ends thereof connected to a cable and its other end connected to a spring; each spring being anchored within the aforementioned cabinet to draw the associated toggle switch to a circuit-open position.

4,296,818

ROTARY ROCK PICKER


Leon Malinowski, and Kenneth Lange, both of Yorkton, Canada, assignors to Leon's Manufacturing Co., Ltd., Saskatchewan, Canada

Filed Apr. 10, 1979, Ser. No. 28,661

Claims priority, application Canada, Jan. 16, 1979, 319699
Int. Cl.³ A01B 43/00

U.S. Cl. 171—63

4 Claims



1. A rock picking apparatus comprising a mobile frame, a pair of spaced assembly support members on said frame, a fork and reel assembly on said support members of the frame for picking rocks from the ground and a dumpable stone storage bucket mounted on said frame behind said fork, said fork and reel assembly including an axle and a pair of spaced side plates at each end of the axle, and journaled for rotation in the assembly support members and supporting between them a plurality of rakes; each said rake having a pair of spaced legs pivotally mounted to said side plates; and compression spring means connecting the trailing sides of said rakes to said pairs of side plates and biasing said rakes to an operative position wherein one end of each spring means is pivotally secured to the trailing side of a rake and the other end of the spring means is supported between one of said pairs of side plates; the fork and reel assembly including a lower cross member extending between and secured to said assembly support members adjacent the lower ends thereof and a parallel, upper cross member also secured to the support members, said fork having a plurality of tines spaced along said cross members at right angles thereto to mesh with the teeth of said rakes; all of the tines being secured adjacent their lower ends to the lower cross members and alternate tines being secured adjacent their upper ends to the upper cross member.

4,296,819

CABLE TENSIONER FOR A DOWNCROWDING DEVICE FOR EARTH BORING MACHINES

Charles R. Griste, Corsicana, Tex., assignor to Hughes Tool Company, Houston, Tex.

Filed May 12, 1980, Ser. No. 147,999


Int. Cl.³ B23Q 5/027, 5/033

U.S. Cl. 173—147

2 Claims

1. In an earth boring apparatus having a kelly suspended by a mast, a downcrowding device having a rotatable drum, hydraulic ram means for moving the drum downwardly, brake means for preventing rotation of the drum, and a downcrowding cable connected directly to the top of the kelly and wrapped around the drum, an improved take-up means for removing slack in the downcrowding cable when raising the drum, comprising in combination:
a take-up sheave carried below the mast;
a take-up cable wrapped around the drum and extending from the drum on a side opposite to the side that the downcrowding cable extends from, the take-up cable

being reeved over the take-up sheave and connected to the top of the kelly; and
cable tensioner means connected between the take-up sheave and the mast for allowing the take-up sheave to



drill bit for drilling a hole into the earth, the improvement comprising:

- (a) a drill rod rack mounted for rotation about an axis within said elongated frame and adapted to carry a plurality of angularly spaced drill rod sections with said drill rod sections being movable sequentially into axial alignment with said driven head upon rotation of said drill rod rack to selected angular positions about said axis so that as each drill rod section carried by said drill rod rack is moved into axial alignment with said driven head it is positioned to drill a hole while said drill rod section and said driven head move through said drill rod rack, and
- (b) a breaker unit carried by the end of said elongated frame adjacent the hole being drilled into the earth and in axial alignment with said driven head for breaking the joint selectively between said driven head and a drill rod section, between drill rod sections and between a drill rod section and a drill bit.

4,296,821

DRILLING RIG AND CONVERSION APPARATUS


Leslie Larson, P.O. Box 334, Mabel, Minn. 55954

Filed Feb. 7, 1980, Ser. No. 119,461

Int. Cl.³ E21B 4/06, 6/00, 7/20

U.S. Cl. 175—87

13 Claims



move downwardly with respect to the mast as the kelly and drum move downwardly during drilling, and for urging the take-up sheave upwardly with respect to the mast to rotate the drum and take up slack as the drum is moved upwardly with the brake being released.

4,296,820

DRILLING APPARATUS


James B. Loftis, P.O. Box 38, Remlap, Ala. 35217

Filed Feb. 1, 1980, Ser. No. 117,562

Int. Cl.³ E21C 11/02

U.S. Cl. 175—52

19 Claims



1. The combination with drilling apparatus having an elongated frame supporting a transmission unit for longitudinal movement therein with the transmission unit operatively connecting a longitudinally extending polygonal drive shaft to a driven head disposed to be threadedly connected to one end of an adjacent drill rod section extending in axial alignment therewith with the other end of the drill rod section being threadedly connected selectively to another drill rod section and a

1. Apparatus for converting a bottom-hole percussion drilling rig of the type including a ram adapted to apply linear force in a desired direction to a length of drill rod extending from said ram in said direction, a percussion assembly attached to said drill rod at an end opposite the end at which said drill rod extends from said ram and having a receptacle open and extending axially in the direction in which the linear force is applied, to which assembly the linear force and rotational movement about the axis with respect to which the receptacle extends are applied by said drill rod, a piston mounted within the receptacle for reciprocating axial movement, and a bit element normally disposed within the receptacle so that the piston can percussively engage an anvil portion of the element, to a top-of-the-hole rig wherein said percussion assembly is mounted to said rig proximate said ram with said receptacle open and extending axially in the direction in which said ram applies linear force, and wherein said drill rod extends generally from said percussion assembly with said bit element attached to said drill rod at an end opposite an end by which said rod extends generally from said percussion assembly, which rig can simultaneously effect hole drilling and driving of casing, enclosing said drill rod, for retaining the inner surface of the hole, comprising:

- first means configured to be operatively connected to the percussion assembly and disposed within said receptacle in place of said bit element for transmitting percussive force generated by the reciprocating axial movement of the piston and the linear force of the ram to an axial end of the casing; and
- second means attached to said first means for transmitting said percussive force, the linear force of the ram, and the rotational movement to the drill rod.

4,296,822

MULTIPURPOSE FLUID FLOW ASSISTED DOWNHOLE TOOL


Ronald D. Ormsby, Woodlands, Tex., assignor to Omega Tools International, Houston, Tex.

Filed Nov. 26, 1979, Ser. No. 97,496

Int. Cl.³ E21B 25/12

U.S. Cl. 175—249

21 Claims



1. A multipurpose fluid flow assisted downhole tool for removing metal objects and formation core samples from the bottom of wells, said downhole tool comprising:

- a tubular connection sub for connecting said tool to a pipe string to be extended into a well bore;
- elongated tubular housing means being secured to said connection means and defining an internal object receiving chamber, said housing means further defining fluid flow means allowing circulation of fluid from said pipe string through said connection sub and through at least a portion of said housing means, said housing means including
- an outer barrel being connected at the upper extremity thereof to said tubular connection sub, said outer barrel defining velocity jet means;
- an inner barrel being fixedly disposed within said outer barrel, said inner barrel defining an internal chamber and cooperating with said outer barrel to define first fluid passage means between said inner and outer barrels, said first fluid passage means being in communication with said velocity jet means; and
- means for selectively directing fluid flowing through said tubular connection sub to said fluid passage means and for selectively directing fluid flowing through said tubular connection to said internal chamber;
- an object receptacle being provided at the lower extremity of said housing means and defining an object receiving opening;
- a plurality of flexible radial fingers being connected to the interior of said object receptacle and extending transversely toward the center of said object receptacle and being positioned in upwardly inclined relation, said radial fingers being sufficiently flexible in the upward direction to allow passage of an object past said fingers into said object receptacle and being sufficiently rigid in the downward direction to prevent objects from falling out of said object receptacle.

4,296,823


CABLE TOOL WITH CIRCULATING DRILL STEM
Wayne Gholson, Scottsville, Ky., assignor to Varel Manufacturing Company, Dallas, Tex.

Filed Oct. 11, 1979, Ser. No. 83,988

Int. Cl.³ E21B 7/00, 10/36, 27/00

U.S. Cl. 175—308

18 Claims



1. In a cable tool for crushing and cutting rock and earth by a dropping action to form a well hole, the cable tool having a tool bit with a cutting face for dropping against rock and earth and having an upper tool body connected to the tool bit with an upper body end for connection to a cable for extending down the well hole, the improvement comprising:

- at least one opening in the cutting face of the tool bit for receiving and removing rock and earth particles from the bottom of the well hole to facilitate the crushing and cutting of the rock and earth;
- a passageway in the tool bit extending from said opening to the upper tool body for transmitting rock and earth particles upwardly away from the cutting face and the bottom of the well hole;
- a retention chamber formed in the upper tool body for receiving rock and earth particles from said passageway to contain and store the rock and earth particles for subsequent removal when the cable tool is removed from the well hole; and
- pressure relief drain means formed through the side of the upper tool body from the exterior thereof to the retention chamber for draining liquid and releasing pressure from said retention chamber, whereby liquid, rock and earth particles are received through the opening, transmitted through said passageway, with rock and earth particles retained within the retention chamber and liquid passing through said chamber and out of said pressure relief drain means.

4,296,824

NOZZLE PLACEMENT IN LARGE DIAMETER EARTH BORING BITS

Kerry S. Kennington, Houston, Tex., assignor to Hughes Tool Company, Houston, Tex.

Filed Jun. 29, 1978, Ser. No. 920,561

Int. Cl.³ E21B 10/18


U.S. Cl. 175—340

6 Claims

1. In a drill bit for drilling a borehole in the earth of the type having cutter support means, a plurality of rotatable cutters mounted to the cutter support means for cutting an annular outer zone at the periphery of the borehole and a circular inner zone bounded by the outer zone, connection means for con-

necting the cutter support means to a string of drill pipe having at least one input and one return flow passage extending from the drill bit to the surface for pumping fluid to the drill bit and returning fluid and cuttings to the surface, and an intake port in the cutter support means in communication with the return flow passage for transmitting cuttings to the return flow passage, an improved nozzle means for discharging fluid from the input passage against the borehole, comprising:

- at least one outer zone nozzle mounted adjacent the periphery of the cutter support means, the outer zone nozzle being in communication with the input passage and pointed so that the center of its discharge strikes the outer zone; and
- a plurality of inner zone nozzles spaced at selected points on the cutter support means and pointed so that the centers of



their discharges strike the inner zone, one of the inner zone nozzles being located near the outer zone nozzle, another inner zone nozzle near the intake port, and at least one inner zone nozzle spaced between, the outer zone nozzle and each inner zone nozzle having a nonrotating area of influence, the area of influence of the outer zone nozzle leading, being further outward, and overlapping the area of influence of the nearest inward inner zone nozzle, the area of influence of each inner zone nozzle leading, being further outward, and overlapping the area of influence of its nearest inward inner zone nozzle, the area of influence of the inner zone nozzle closest to the intake port extending below the intake port, to create a continuous stream flowing from the periphery of the borehole to the intake port.

4,296,825

ROCK DRILL


Lars E. Larsson, Sandviken, Sweden, assignor to Sandvik Aktiebolag, Sandviken, Sweden

Continuation-in-part of Ser. No. 854,752, Nov. 25, 1977, abandoned. This application Oct. 4, 1979, Ser. No. 81,785

Int. Cl.³ E21C 13/01

U.S. Cl. 175—410

11 Claims



1. A rock drill for percussion drilling comprising a bit body,

said bit body including a front face extending generally transversely relative to the longitudinal axis of said bit body, a substantially central button insert of hard material, said central button insert extending longitudinally outwardly of said front face substantially in alignment with said longitudinal axis, and at least a first row of circumferentially spaced outer button inserts of hard material, there being more than two outer inserts disposed on more than two different radii from said axis, said outer button inserts extending outwardly of said front face and being inclined at an angle relative to said longitudinal axis and being arranged to define an outer diameter (D) of the hole drilled by the rock drill, said central and outer inserts each including a working surface disposed on the front of a mounting portion of the insert, said mounting portion being embedded along substantially all of its length within said bit body, said working surface being characterized by an absence of an edge extending radially of said longitudinal axis when viewed along said axis, the improvement wherein the ratio of Y to D is in the range of 8% to 22%, where Y is the distance between opposed side faces on said central button insert and at least one of said outer button inserts when measured at said front face, and the ratio of X to D is no greater than 20%, where X is the outward extent of the outer end of said central button insert beyond a transverse plane through the outer end of at least one of said outer button inserts.

4,296,826

VEHICLE HAVING BOGIE MOUNTED WHEELS

Cornelis van der Lely, 7, Brüschenrain, Zug, Switzerland


Filed Apr. 20, 1979, Ser. No. 32,030

Claims priority, application Netherlands, Apr. 26, 1978, 7804438

Int. Cl.³ B62D 61/10

U.S. Cl. 180—24

10 Claims



1. An agricultural tractor comprising a frame, an engine carried by said frame, a tractor hitching device mounted on the rear of said frame, at least three ground engaging wheels mounted on each side of said frame, said ground engaging wheels mounted on each side being aligned one behind the other with respect to the tractor's direction of travel, a cradle frame part, said cradle frame part comprising two carrier beams which are effectively parallel to the tractor's plane of symmetry, at least two but not all of said aligned wheels on each side of said frame mounted on a corresponding said carrier beam of said cradle frame part, each said carrier beam being independently pivotable relative to said tractor frame about a substantially fixed axis extending normally relative to the tractor's plane of symmetry and between the axes of rotation of said two wheels which are mounted on each said carrier beam, steerable wheels mounted at the front of said frame forward of said cradle frame part, said steerable wheels being pivotable relative to said frame about at least one horizontal axis substantially directed parallel to the tractor's plane of symmetry, drive means connecting said front steerable wheels and the rear wheels mounted on said cradle frame part whereby such wheels are driven by said engine, and steering means for said tractor connected to said steerable wheels, and only the rearmost

wheels of said wheels mounted on each side of said cradle frame part.

4,296,827

AIR-GUN FIRE TIME SENSOR


Ben B. Thigpen, and James A. Porter, Jr., both of Houston, Tex., assignors to Western Geophysical Company of America, Houston, Tex.

Filed Jul. 10, 1978, Ser. No. 922,952

Int. Cl.³ G01V 1/137, 1/38

U.S. Cl. 181—107

8 Claims



1. A resistive sensor for determining the firing instant of an air gun that is used in seismic exploration in a body of water, the air gun including an air exhaust port for emitting a jet of compressed air, the sensor comprising:

an electrode assembly exposed to the surrounding water mounted adjacent the air exhaust port; and means for detecting the change in electrical resistance across said electrode assembly when said air gun is fired.

4,296,828

MOBILE DEVICE FOR GENERATING ACOUSTIC SHEAR WAVES

Pierre-Claude Layotte, Les Mathes, and Andre James, Royan, both of France, assignors to Institut Francais du Petrole, Ruell-Malmaison, France


Filed Jul. 5, 1979, Ser. No. 55,098

Claims priority, application France, Jul. 5, 1978, 78 20009

Int. Cl.³ G01V 1/047

U.S. Cl. 181—121

8 Claims



1. A device for generating acoustic shear waves in the earth comprising;

a target-member having a coupling surface for coupling with the earth;
mass means for striking said target-member when coupled to the earth;
moving means operatively associated with said mass means for imparting to said mass means a velocity component parallel to said coupling surface;

coupling means comprising a plurality of independent zones on said coupling surface for coupling with the earth; and suction means connected to said target-member for generating a suction in each zone of said plurality of independent zones for coupling said target-member with the earth at said each zone.

4,296,829

HOOK-SHAPED PART OF A BEHIND-THE-EAR HEARING AID

Jorgen R. Pedersen, Gentofte, Denmark, assignor to Danavox A/S, Copenhagen, Denmark


Filed Dec. 14, 1979, Ser. No. 103,651

Claims priority, application Denmark, Dec. 15, 1978, 5662/78

Int. Cl.³ H04R 25/02

U.S. Cl. 181—129

6 Claims



1. An improved hook shaped part for a behind-the-ear hearing aid, said hook shaped part being hollow and at one end formed to be connected to an acoustic output from the upper front end of the hearing aid case and serving to transmit sound from the hearing aid in the direction of the ear, normally through a tube and an ear plug, and also serving to support the hearing aid upon the outer ear, the improvement comprising an acoustic filter arranged in the hook shaped part at the end furthest from the hearing aid and the hook shaped part having a channel of progressively increasing cross-sectional area in the direction away from the hearing aid.

4,296,830

PRODUCT PROVIDED WITH SOUND DAMPING ELEMENT

Bror L. E. Rossander; Lennart C. Ernebrant, both of Fagersta, and Martin Lesser, Lulea, all of Sweden, assignors to Fagersta A.B., Fagersta, Sweden

Filed Jul. 10, 1979, Ser. No. 56,293

Claims priority, application Sweden, Jul. 12, 1978, 7807779

Int. Cl.³ F16F 15/00

U.S. Cl. 181—208

9 Claims



1. In a product of metal formed with a hole or cavity, particularly a rock drill steel, and provided with at least one element of hard material for damping noise produced during use deriving from the product when it is subjected to impacts, percussions or vibrations generating in the product sound waves annoying to the human ear, the improvement comprising the

sound damping element, which is arranged within the hole in the product, is a hollow tubular member and has at least one contact surface, which contacts the wall of the hole during use, loosely arranged relative to the wall of the hole, said sound damping element being fixedly attached within said hole to said product at at least one position of the damping element other than said contact surface to prevent longitudinal displacement of said element with respect to said product, and at least along said contact surface having a small cross-sectional area in relation to the cross-section of the hole, and said contact surface being located between the nodes of the sound waves so as to create a dry friction-producing relative movement between said contact surface of the damping element and the wall of the hole.

4,296,831

ACOUSTIC LINER FOR ATTENUATING NOISE

Stuart C. Bennett, Derby, England, assignor to Coal Industry (Patents) Limited, London, England


Filed Apr. 17, 1980, Ser. No. 141,250

Claims priority, application United Kingdom, May 23, 1979, 17965/79

Int. Cl.³ E04F 17/04

U.S. Cl. 181—224

10 Claims



1. An acoustic liner for attenuating noise, comprising a backing face, a perforated facing sheet and a wave guide assembly extending between the backing face and the perforated facing sheet to define a plurality of cells, the portion of the perforated facing sheet associated with each cell having a non-uniform thickness.

4,296,832

EXHAUST MUFFLER


Kenneth J. Kicinski, Stoughton, Wis., assignor to Nelson Industries, Inc., Stoughton, Wis.

Filed Nov. 14, 1979, Ser. No. 94,001

Int. Cl.³ F01N 1/00

U.S. Cl. 181—255

7 Claims



1. An exhaust muffler, comprising an outer casing including a body having open opposite ends and including a pair of heads to enclose the open ends of the body, an exhaust inlet tube adapted to conduct exhaust gas to the muffler and mounted within an opening in the casing, a gas outlet tube mounted within an opening in the casing, a first baffle disposed within the casing and secured across the inner end of the inlet tube, said baffle extending radially outward beyond said inlet tube, and the peripheral edge of said baffle being spaced from the inner wall of said body, a flange disposed on the outer peripheral edge of said baffle and extending longitudinally of said body to provide an annular passage between said flange and

said body said baffle being free of attachment to said body, said inlet tube being spaced inwardly from said body to provide a chamber therebetween and said inlet tube having a plurality of perforations providing communication between the interior of the inlet tube and said chamber, said baffle having an imperforate central section closing off the inner end of said inlet tube, whereby the exhaust gas and the sound energy is directed outwardly through said perforations into said chamber and then passes through said annular passage for discharge through said outlet tube.

4,296,833

HYDRAULICALLY OPERATED ACCESS EQUIPMENT


Denis H. Ashworth, Wombourne, England, assignor to Simon Engineering Dudley Limited, Dudley, England

Filed Apr. 13, 1979, Ser. No. 30,447

Int. Cl.³ B66F 11/04

U.S. Cl. 182—2

11 Claims



1. Access equipment of the kind comprising a supporting structure upon which is mounted an articulated boom assembly comprising one or more booms, the or each boom being connected to the supporting structure or to the next adjacent boom so as to be pivotable relative thereto about a horizontal axis to enable the outermost end of the boom assembly to be raised and lowered with respect to the supporting structure, and including hydraulic actuating rams for effecting movements of the boom assembly, characterised in that a guide member is provided at each end of the or each boom, in that at least one support line, being flexible throughout at least a part of its length, is attached at one end to the supporting structure and extends to dispose its other end at the outermost end of the boom assembly, lying substantially parallel to the boom or booms, and passing around said guide members at the ends thereof and is secured at the said outermost end, in that the said support line is maintained taut along a path whose length remains constant irrespective of the configuration of the boom assembly, and in that one or more flexible control lines are arrayed parallel with said support line, from said supporting structure, around said guide members and to the outermost end of said boom assembly, whereby said one or more control lines are retained taut and in close association with said support line in all phases of articulation of said boom to thus minimize wear of said one or more control lines caused by boom movement.

4,296,834

FOLDING SAWHORSE

Walter Kroger, P.O. Box 331, Custer, S. Dak. 57730

Filed Jun. 1, 1979, Ser. No. 44,454


Int. Cl.³ F16M 11/00

U.S. Cl. 182—155

14 Claims

1. In a folding sawhorse having a top, two sets of folding leg pairs, and a pair of braces of resilient material each associated with one of said sets of leg pairs, each of said braces pivotally mounted at one end on one of said associated leg pairs so as to extend between said associated leg pair and said top in the sawhorse set set up position, and brace locking means on said

top engagable with the other end of each of said braces to retain said brace in a state of compression between said associated leg pair and said top with said sawhorse in a set up position, and interlock latching means for each of said braces,




which interlock means extends rigidly between a brace and either a leg pair of said sawhorse top maintaining said brace in said state of compression to provide a highly stable folding sawhorse.

4,296,835 BRACKET

Leonard E. Koffski, R.R. #4, 7534 Trans Canada Hwy., Duncan, British Columbia, Canada (V9L 3W8)
Continuation-in-part of Ser. No. 916,143, Jun. 16, 1978. This application Jun. 21, 1979, Ser. No. 50,558
Int. Cl.³ F16M 11/00

U.S. Cl. 182—184



1. A bracket for carrying a plank by means of support legs, which have a predetermined rectangular cross sectional configuration, comprising:

- a cross piece of predetermined length for carrying a plank;
- respective open faced channel members connected at each end of said cross piece and extending downwardly and outwardly therefrom, the open faces of said channel members opening in opposite directions and in the direction of the length of said cross piece, said channel members having a pair of internally rounded corners and an internal cross sectional widthwise dimension slightly larger than the widthwise dimension of said support legs such that said support legs engage with said channel members by respective contact of two corners of said support legs with the pair rounded corners of said channel members when said support legs are inserted in said channel members; and
- a bracket sleeve pivotally connected to each of the channel members for receiving and retaining support legs in a stationary position relative to said channel members.

4,296,836


SKY SEAT SAFETY DESCENT APPARATUS
Thomas F. Cooper, Lisco, Garden County, Nebr. 69148
Filed Mar. 20, 1978, Ser. No. 888,573
Int. Cl.³ A62B 1/00

U.S. Cl. 182—193

2 Claims

1. A descent apparatus comprising of a seat frame with an attached center post for retention and descending of a support rope, whereas the said support rope is placed through a confin-

ing means at the top of said center post wrapped several times around said center post placed through a lower confining



means at the lower portion of said center post and fastened to a tie-off hook attached to said center post directly below top said confining means.

4,296,837

APPARATUS AND PROCESS FOR LUBRICATING ELECTRICAL CABLE


Webster T. Charlton, Lowell, Mass., assignor to Stone & Webster Engineering Corp., Boston, Mass.

Filed May 15, 1979, Ser. No. 39,484

Int. Cl.³ F16N 9/00

U.S. Cl. 184—15 R

13 Claims



10. A process for lubricating cable being pulled through a conduit comprising the steps of:
delivering lubricant through a nozzle to the cable at the entry end of the conduit; and
delivering lubricant to the walls of the conduit in advance of the leading end of the cable as the cable moves through the conduit.

4,296,838

AUTOMOTIVE OIL SYSTEM

Merrill L. Cohen, 222 Summer St., Worcester, Mass. 01608

Filed Jul. 27, 1979, Ser. No. 61,507


Int. Cl.³ B65D 85/00; F16N 31/00

U.S. Cl. 184—106

7 Claims

1. Automotive oil system, comprising:
(a) a new oil container having a pouring spout,
(b) a container for used oil having an admission opening,

- (c) first means holding the two containers together before use, and



- (d) second means holding the containers together after use, including a closure for the admission opening in the container for used oil.

4,296,839

STRUCTURALLY DAMPED BOLT


Robert C. Peller, and Jack E. Dyer, both of San Diego, Calif., assignors to General Dynamics Corporation, San Diego, Calif.

Filed Sep. 26, 1979, Ser. No. 79,237

Int. Cl.³ F16F 7/08

U.S. Cl. 188—378

1 Claim



1. A structurally damped device for attenuating the vibrations between two structural members and having means for connecting said device to said structural members comprising:
means defining a first primary load path designed to take the basic load between said structural elements; and
means defining a second structural load path in parallel with said primary load path;
said means for defining a primary load path is a spring comprising a bolt having end bosses integral therewith and wherein said means for defining a secondary load path comprises sleeves of material one attached to each of the end bosses and placed in overlapping relationship with viscoelastic damping material located between the sleeves and loaded in shear.

4,296,840

TRACTOR PULL SLED


Richard J. Payne, R.R. #1, Box 293, Grand Island, Nebr. 68801

Filed Oct. 11, 1979, Ser. No. 83,748

Int. Cl.³ B62B 17/08

U.S. Cl. 188—8

18 Claims



1. A tractor pull sled comprising:

a frame having a forward end and a rearward end;
a plurality of ground engaging wheels attached to and supporting said forward end and said rearward end;
a pan movably mounted on said frame; said pan being movable between a first position wherein the weight of said pan is supported by said frame, and a second lowered position wherein said pan engages the ground and the weight of said pan is unsupported by said frame; and
means for moving said pan between said first position and said second position at a rate which is a function of the distance of forward travel of said sled.

4,296,841

ANTIRATTLE SPRING FOR A DISC BRAKE OF VEHICLES


Fumio Fujimori, Masatada Yokoi, Masakazu Ishikawa, Hiroshi Uemura, and Akira Shirai, all of Aichi, Japan, assignors to Aisin Seiki Kabushiki Kaisha, Kariya and Toyota Jidosha Kogyo Kabushiki Kaisha, Toyota, both of Japan

Continuation of Ser. No. 868,214, Jan. 9, 1978, Pat. No. 4,214,649. This application Jan. 31, 1980, Ser. No. 117,358
Claims priority, application Japan, Jan. 8, 1977, 52-1095

Int. Cl.³ F16D 65/04

U.S. Cl. 188—73.38

5 Claims



a fixed torque taking member;
a pair of frictional elements, respectively disposed adjacent the opposite friction faces of the rotor;
a caliper straddling a part of said rotor together with said friction elements and free to slide on said torque taking member in the direction of the axis of rotation of the rotor; hydraulic fluid acting means incorporated into said caliper and adapted to respectively urge said friction elements to the opposite friction faces of said rotor;
a pair of radially extending portions projecting from said caliper which includes internal faces and connecting with one of said friction elements;
a resilient member comprising a middle portion, a pair of radially extending portions extending radially inwardly from opposite ends of said middle portion, opposite end portions spaced radially outwardly from said middle portion and intermediate portions interconnecting said opposite end portions with said pair of radially extending portions, respectively, said resilient member being sustained at said middle portion thereof by said one of said friction elements and resiliently abuts said radially extending portions of said caliper at said opposite end portions thereof to thereby normally urge said one of said friction elements toward abutment against said internal faces of said radially extending portions of said caliper, wherein said radially extending portions of said caliper, respectively, include a pair of axially extending projections for restraining said opposite end portions of said resilient member from upward free movement and wherein said one of said friction elements includes a projection formed at a middle part thereof and having a receiving portion formed therein such that said resilient member is force fitted in said receiving portion;

said resilient member comprising a single wire;
a pair of notches formed in said radially extending portions of said caliper;
a pair of circumferentially spaced projections on said one of said pair of friction elements respectively slidably fitted in said pair of notches; and
said resilient member being bent at both ends of said middle portion to form said pair of radially extending portions which abut said one of said friction elements; said intermediate portions, said pair of radially extending portions and said pair of axially extending projections of said caliper restraining said opposite end portions from radial free movement while radially urging said one of said friction elements against said pair of notches at said pair of projections.

4,296,842

PAWL AND RATCHET MECHANISM

Larry G. Keast, Houston, Tex., and Herbert D. Horton, Mayhill, N. Mex., assignors to World Wide Oil Tools, Inc., Houston, Tex.

Filed Oct. 9, 1979, Ser. No. 83,162
Int. Cl.³ F16D 63/00

U.S. Cl. 188—61

12 Claims



1. A pawl and ratchet mechanism comprising:
a housing having portions defining a plurality of apertures, each aperture of said plurality of apertures disposed within said housing at a fixed distance from each of the other apertures in said plurality of apertures;
a toothed track associated with said housing, said teeth of said track having spaces therebetween; and
a pawl element disposed within and movable within each of said plurality of apertures within said housing, said pawl elements being movable into and out of the spaces between the teeth of said toothed track and wherein at least one of said plurality of said pawl elements is movable into at least one of the spaces between the teeth of said toothed track irrespective of the location of said housing with respect to said toothed track when said housing engages said toothed track.

4,296,843

DISC BRAKE FOR TWO-WHEELED VEHICLE

Yukinori Nishiyama, and Hideji Ichikawa, both of Itami, Japan, assignors to Sumitomo Electric Industries, Ltd., Osaka, Japan

Filed Jan. 18, 1980, Ser. No. 113,422


Claims priority, application Japan, Jan. 19, 1979, 54-7036[U]
Int. Cl.³ F16D 55/224

U.S. Cl. 188—73.43

2 Claims

1. A floating type disc brake for a two-wheeled vehicle comprising: two pad assemblies, a caliper including a caliper cylinder and a caliper arm, one of said pad assemblies being operatively coupled to said caliper cylinder and the other of said pad assemblies being supported by said caliper arm, a pin for securing said caliper to a stationary member of a fork member of said vehicle, said pin being disposed in a through-hole in said stationary member, recesses being provided in one of said stationary member and said pin within said through-hole, elastic members disposed in said recesses to at least partially fill a portion of a gap between said stationary member and said pin wherein upon application of a sufficiently high force said pin is brought into operative abutment with said

stationary member so as to stop compression of said elastic members, and a collar member positioned around said pin, said



recesses in which said elastic members are disposed being provided in an outer wall of said collar.

4,296,844

FLOATING CALIPER TYPE DISC BRAKE


Koichi Tamura, Tokyo, and Tetsuo Haraikawa, Funabashi, both of Japan, assignors to Tokico Ltd., Japan

Filed Sep. 11, 1979, Ser. No. 74,807

Claims priority, application Japan, Sep. 20, 1978, 53-129172
Int. Cl.³ F16D 65/04

U.S. Cl. 188—73.38

5 Claims



1. A floating caliper disc brake which comprises:
a. a rotatable disc to be braked,
b. a stationary member adapted to be secured to a non-rotatable structure carrying said disc,
c. a caliper slidably mounted on said stationary member through a resilient member and said caliper having a bridge portion which bridges said disc in the direction of the rotational axis of said disc and a pawl portion which is substantially normal to said rotational axis.
d. a brake actuating means providing within said caliper,
e. first and second friction pads, respectively having first and second backing plates, said pads positioned on opposite sides of said disc,
said first friction pad being adjacent to said stationary member and said second friction pad being adjacent to said pawl portion,
said second backing plate having a projection on the back portion thereof,
f. a stationary guide member attached to said stationary member and said second backing plate being suspended from said guide member and slidably guided thereon in the direction of the rotational axis of said disc,
g. a pad spring provided beneath said bridge portion, said spring imparting a biasing force on said second backing plate in the radially inward direction with respect to the circumference of said disc and a reaction force on said bridge portion,
h. a retaining member formed in said pawl portion of said caliper and being engaged by and retaining said projection, thereby countering the reaction force of said pad spring on said bridge portion.

4,296,845

ANCHOR PLATE FOR A DRUM BRAKE ASSEMBLY


James K. Roberts, South Bend, Ind., assignor to The Bendix Corporation, South Bend, Ind.

Filed Sep. 10, 1979, Ser. No. 73,754

Int. Cl.³ F16D 51/00

U.S. Cl. 188—341

4 Claims



1. In a drum brake assembly having a backing plate and a pair of brake shoes arranged in end-to-end relationship on said backing plate, each brake shoe comprising an arcuate rim and a substantially planar web extending transversely from said rim, the improvement comprising said backing plate having an embossed knob adjacent one end of the shoes and defining a pair of knob faces extending into the plane defined by the planar webs;

an anchor plate being force-fit into overlying engagement with said knob, said anchor plate having a substantially rectangular plate with three tabs located along two opposite edges of the plate, the central tab of said three tabs extending substantially perpendicular to said plate and defining a load bearing tab, the two tabs adjacent said central tab lying coplanar with said plate and overlying said planar webs to retain said webs in engagement with said load bearing tab; and
retaining means for securing said anchor plate to said knob.

4,296,846

BRAKE RELEASE MECHANISM


Samuel L. Benson, Clinton Vermillion, Ind., assignor to J. I. Case Company, Racine, Wis.

Filed Feb. 19, 1980, Ser. No. 122,545

Int. Cl.³ B60K 41/26

U.S. Cl. 192—4 A

6 Claims



1. A brake release mechanism for a machine having a brake and a hydrostatic transmission, a transmission control means rotatable about one axis to control the input to said hydrostatic transmission, a brake control means including a brake control arm rotatable about a pivot axis and a brake cable connected to said control arm spaced from said pivot axis, the rotation of said brake control arm tensioning said brake cable to actuate said brake, and a latch means adapted to releasably retain said control arm rotational position with said brake cable tensioned to lock said brake, the improved brake release mechanism, comprising a lever connected to said transmission control

means and rotatable therewith, said latch means having a rotatable latching element, said latching element rotatable into and out of latching engagement with said brake control arm, and a cable connector means interconnecting said lever and said latch means, said cable means adapted to rotate said latching element out of latching engagement with said brake control arm upon rotation of said transmission control means in either direction from a neutral position.

4,296,847

TRANSMISSION SHIFT LEVER BACKDRIVE AND COLUMN LOCKING MECHANISM


Frederick P. Arndt, Saginaw, Mich., assignor to General Motors Corporation, Detroit, Mich.

Filed Mar. 25, 1980, Ser. No. 133,890

Int. Cl.³ B60K 41/26

U.S. Cl. 192—4 A

2 Claims



1. A transmission shift lever backdrive and column locking mechanism for use in a motor vehicle having a floor-mounted transmission shift lever movable in a plurality of operating conditions including "Park" and "Reverse", and a lockable steering column shift bowl operable to be positioned for locking only when the transmission is in the "Park" operating condition, said mechanism comprising: a support bracket mounted on the steering column and having integrally formed guide means; coupling means slidably disposed in said guide means and including cam means and linear guide means; flexible force and motion transmitting means connected between said coupling means and the transmission shift lever for transmitting the selected operative condition from the transmission shift lever to the coupling means; and actuator means pivotally mounted on said steering column and operatively connected with the shift bowl, said actuator means including cam slot means selectively engageable by said cam means for enforcing pivoting of the actuator means when the shift lever is moved from the "Reverse" operating condition to the "Park" operating condition for positioning the shift bowl to permit locking of the steering column, and linear guide slot means for selectively engaging said linear guide means when the transmission shift lever is moved from the "Reverse" operating condition to the other operating conditions for preventing pivoting of the actuator means and thereby preventing positioning of the shift bowl to prevent locking of the steering column.

4,296,848

FREE WHEEL HUB MECHANISM

Tooru Kagata, Toyota, and Hiromi Goto, Chiryu, both of Japan, assignors to Aisin Seiki Kabushiki Kaisha, Kariya, Japan

Filed Jul. 26, 1978, Ser. No. 928,263

Claims priority, application Japan, Jul. 27, 1977, 52-100981[U]


Int. Cl.³ F16D 13/04

U.S. Cl. 192—35

4 Claims

1. A free wheel hub mechanism comprising:
a body secured to a wheel;
an inner race secured to an axle shaft and rotatable therewith;
means for engaging said inner race with said body only upon

- rotation of said shaft and for permitting the free rotation of said body upon non-rotation of said shaft;
- a shoe receiving member secured to a spindle sleeve of said axle shaft and having a receiving surface located entirely in a plane which crosses said axle shaft at a substantially right angle;
- a shoe means for maintaining said engaging means in its engaged condition and having a sliding surface located entirely in a plane which crosses said axle shaft at a substantially right angle; and



- a spring biasing said sliding surface of said shoe means against said receiving surface of said shoe receiving member whereby the sliding contact between said sliding surface and said receiving surface maintains the engagement of said engaging means,
- wherein said engaging means comprises a cage arranged between said inner race and said body, and rollers positioned within said cage, said rollers being urged outwardly by a cam surface provided on said inner race upon rotation of said shaft and being thus squeezed against said body.

4,296,849

AUTOMATIC TORQUE REGULATOR


Luigi Pellegrino, Conicit Apdo. 70,617 Los Ruices, Caracas, Venezuela (107)

Filed Jul. 9, 1979, Ser. No. 55,604

Claims priority, application Venezuela, Jan. 12, 1979, 44/68
Int. Cl.³ F16D 31/04

U.S. Cl. 192—61

15 Claims



1. An automatic torque regulator comprising:
- a chassis defining a cavity;
- a central gear positioned in said cavity;
- axis means for rotatably mounting said chassis and said central gear so that said central gear can be rotated independently from said chassis;
- a satellite gear positioned in said cavity in engagement with said central gear;
- means for rotatably mounting said satellite gear to said chassis;
- means for defining first and second pressure chambers near

the initial and final areas of contact between said central gear and said satellite gear;

means for providing fluid communication between said pressure chamber means and said cavity; and

means for regulating the flow of fluid in said communication means; and

wherein said regulating means includes passages means for providing greater resistance to fluid flow therethrough in one direction than in the reverse direction.

4,296,850

REAR HUB HAVING IMPROVED MOUNTING OF A CYLINDRICAL BEARING MEMBER TO AN INNER MEMBER

Mitsuhide Isobe, Toyonaka, Japan, assignor to Shimano Industrial Company, Limited, Osaka, Japan


Filed Mar. 10, 1980, Ser. No. 128,832

Claims priority, application Japan, Mar. 19, 1979, 54-36082

Int. Cl.³ F16D 41/18; F16C 35/07; F16H 55/30

U.S. Cl. 192—64

9 Claims



1. In a rear hub for a bicycle, which is provided with a tubular hub shell having first and second hub flanges, an inner member fixed to said hub shell and having a ball race formed axially inwardly of the inner member, an outer member supported rotatably with respect to said inner member and having at least one sprocket at the outer periphery of the outer member, first and second bearings carrying said outer member rotatably with respect to said inner member, a unidirectional rotary transmission interposed between the outer periphery of said inner member and the inner periphery of said outer member, and a cylindrical bearing member mounted on said inner member axially outwardly thereof and having ball races, the improvement comprising: a tubular receiving portion provided at said inner member axially outwardly thereof for insertably receiving said cylindrical bearing member; a fitting portion provided at one axial side of said cylindrical bearing member and having an inner periphery of larger diameter than an outer diameter of said receiving portion, to form an annular space between the outer periphery of said receiving portion and the inner periphery of said fitting portion; and, a sleeve press-fit into said annular space, said sleeve having a thickness larger than a radial width of said annular space, said sleeve, when inserted within said annular space, said cylindrical bearing member at a desired position on said receiving portion.

4,296,851

DRIVE HUB WITH CURVED SPRINGS AND DRIVE KEYS FOR ELECTRO-MAGNETIC CLUTCH

William C. Pierce, Dallas, Tex., assignor to Pitts Industries, Inc., Dallas, Tex.

Filed Jun. 1, 1979, Ser. No. 44,775


Int. Cl.³ F16D 3/00, 27/10

U.S. Cl. 192—84 C

3 Claims

1. In a magnetic clutch for driving a shaft including a rotatable element having a friction face positioned around and independent of the shaft, an armature disk positioned around the shaft and including a friction face in opposed relation to the

friction face on the rotatable element, an electromagnet for selectively moving the friction faces into driving engagement, that improvement comprising a flexible drive coupling between the armature disk and drive shaft, said coupling comprising a plurality of arcuately curved leaf springs, each spring having one end connected with the armature disk, means drivingly connecting the other end of each spring with the shaft to enable flexibly resilient axial, radial and circumferential relative movement between the armature disk and drive shaft, said means drivingly connecting the springs and drive shaft comprising a hub affixed to the drive shaft and including a hub plate, the armature disk being positioned around the hub plate with the inner ends of the arcuately curved springs being connected to the hub plate, each of the springs being generally



U-shaped and including an elongated central arcuate portion and radially inwardly offset ends anchored to said hub plate and armature disk, respectively, the end of each spring attached to the armature disk lying along a radius of the hub plate and armature disk and the end of the spring attached to the hub plate being disposed adjacent to but in slightly trailing relation to the same radius when the springs are not deflected, the central portion of each spring including a concave edge opening in the direction of rotation with transmission of torque between the armature disk and hub plate being transmitted through the springs with the degree of deflective elongation of the springs being determined by the torque transmitted thereby causing the central portions of the springs to straighten to increase the distance between the ends.

4,296,852

AUTOMATIC TWO-WAY CENTRIFUGAL CLUTCH FOR MOTOR DRIVEN APPARATUS

Adolf Luerken, Palos Verdes, Calif., assignor to McCulloch Corporation, Los Angeles, Calif.

Continuation of Ser. No. 850,136, Nov. 10, 1977, abandoned.

This application Mar. 6, 1978, Ser. No. 883,655

Int. Cl.³ F16D 23/10, 43/24

U.S. Cl. 192—104 B

6 Claims

5. An automatically acting centrifugal clutch comprising a rotating support member having a first rotation axis, first and second single element clutch members, each said clutch member being supported by said support member along a respective pivot axis for pivotal rotation movement about said pivot axis in a plane normal to said rotation axis, and each pivot axis being parallel to, separated from, and symmetrically placed with respect to said rotation axis,
- a rotatable clutch drum having
- an axis of rotation concentric with said first rotation axis, and
- a circular, inwardly facing, frictional drive surface radially spaced from and parallel to said rotation axis,
- said clutch members each further having a center of gravity a driving surface and a driven surface, said surfaces having a radius of curvature substantially equal to the radius of curvature of said frictional drive surface, and said clutch members being pivotably supported so that said driven surfaces each engage said friction drive surface in a first pivotal position of each clutch member, and said driving clutch surfaces each engage said fric-



tional drive surface in a second pivotal position of said clutch members,

first and second spring members, each connected in a fixed positional relationship relative to said driven and driving surfaces, and between the first and second clutch members,

said first and second springs each having a first end connected to the first and second clutch members respectively substantially at the respective pivot axis of the clutch member whereby said first ends maintain a substantially fixed position as the respective clutch member pivots about the respective pivot axis,

each of said springs being under tension, and

each spring, at a respective second end, being connected to a respective clutch member for urging said corresponding driving surface against said frictional drive surface in a start-up state, and connected at a position spaced further from said clutch pivot point than the center of gravity of said respective clutch member and said single element clutch members each having a fixed mass distribution and said springs having a spring constant whereby



whenever the rate of rotation of said support member is below a first rotational speed, said driven surface engages and is in contact with said frictional drive surface,

upon rotation of said support member beyond said first rotation speed and less than a second rotation speed greater than the first rotation speed, said driven clutch surface pivots out of engagement with the frictional drive surface, and

upon rotation of said support member beyond said second rotation speed, said driving clutch surface is urged against and engages said friction drive surface with a force which is a monotonically increasing function of the rotation speed, and

whereby, when said clutch members pivot from said first position wherein said driven clutch surfaces engage said frictional drive surface to said second position wherein said driving clutch surfaces engage said frictional drive surface, said spring members extend at a rate greater than the radial rate of travel of each clutch member center of gravity thereby defining a range of rotational speed in which the clutch surfaces do not engage the frictional drive surface.

4,296,853

ROTATION-ELASTIC, SHOCK AND VIBRATION DAMPING CLUTCH


Curt Krönert, Mülheim, Fed. Rep. of Germany, assignor to Thyssen Industrie AG, Fed. Rep. of Germany
Filed Oct. 16, 1979, Ser. No. 85,220

Claims priority, application Fed. Rep. of Germany, Oct. 14, 1979, 2844849

Int. Cl.³ F16D 3/68

U.S. Cl. 192—106.1

7 Claims



1. A rotation-elastic, shock and vibration damping clutch, comprising, an outer ring part, an inner ring part arranged within said outer ring part, each of said outer and inner ring parts having a plurality of generally axially extending apertures therethrough which are arranged in circumferentially spaced locations, an elastic pressure pad of arc-shaped cross-section extending between said inner and outer ring portions and having respective ends abutting against respective sides of said inner and outer ring portions around each of the respective apertures, at least one non-elastic rope having a diameter substantially smaller than that of said apertures extending through said elastic pressure pad and being connected thereto and also extending through each of the respective apertures and being evenly distributed around the circumference of said rings, and spring means resiliently supporting said rope adjacent each of said apertures so that said rope does not touch said ring parts in any areas bounding the apertures.

4,296,854

FLEXIBLE CLUTCH WITH AN ELASTOMERIC VIBRATION DAMPER


Vincent M. Staub, Jr., Dayton, Ohio, assignor to General Motors Corporation, Detroit, Mich.

Filed Mar. 21, 1980, Ser. No. 131,923

Int. Cl.³ F16D 3/14

U.S. Cl. 192—106.1

1 Claim



1. An elastomeric drive mechanism disposed in series with a friction drive mechanism, comprising: an input pressure plate member; an output shaft having a splined exterior; a plurality of gear members rotatably mounted on said pressure plate and meshing with said splined portion of said output shaft, a cam member secured to each of said gear members for unitary rotary movement therewith; and an elastomeric band means operatively connected with and circumscribing the outer portion of said cam members, said gear members providing a drive

connection between said pressure plate and said output shaft and said elastomeric band means permitting relative angular excursion between said pressure plate and said output shaft, and said cam members generating increased tension forces within said band means upon increased angular excursion between said pressure plate and said output shaft to provide increased torque capacity in said elastomeric drive mechanism while limiting the transmission of torsional vibrations.

4,296,855

ELECTRICALLY CONDUCTIVE FABRIC


Gary L. Blalock, Canal Fulton, Ohio, assignor to The B. F. Goodrich Company, Akron, Ohio

Continuation of Ser. No. 941,871, Sep. 13, 1978, abandoned. This application Feb. 27, 1980, Ser. No. 125,291

Int. Cl.³ B65G 43/00

U.S. Cl. 198—502

5 Claims



3. For use as a controlling antenna to detect rips in a flexible conveyor belt in which it is located, a flexible fabric constructed of first yarns extending in a first direction and second yarns extending in a second direction transverse to said first direction, the yarns in at least one of said directions extending from end to end of the fabric and being formed of a plurality of strands previously and continuously provided along their entire lengths with electrically conductive particles to form a continuous electrically conductive path across the fabric and substantially from edge to edge of the conveyor belt in which it is located, said first and second yarns being joined together in an open mesh configuration with interstices therebetween, and elastomeric material of the conveyor belt in which the fabric is located being on both sides of said yarns and in contact therewith and extending through the interstices of said fabric to hold said fabric in its open mesh configuration and fixedly positioned within the conveyor belt in which it is located.

4,296,856

MATERIAL GATHERING DEVICE FOR A MINING MACHINE

Donald L. Freed, Jr., Belleville, Ill., assignor to National Mine Service Company, Pittsburgh, Pa.

Filed Jan. 3, 1980, Ser. No. 109,333


Int. Cl.³ B65G 65/02

U.S. Cl. 198—514

9 Claims

1. A material gathering device for a mining machine comprising, a gathering platform extending forwardly from said mining machine for slidable engagement with the mine floor, said gathering platform having a forward edge portion and opposite side portions extending rearwardly from said forward edge portion, deflector means for deflecting loose material deposited on the mine floor adjacent said forward edge portion and said opposite side portions onto said gathering platform, means for pivotally mounting said deflector means on said gathering platform adjacent said opposite side portions, said deflector means having an upstanding wall portion adapted to be positioned closely adjacent the mine wall and a material receiving surface extending from said up-

standing wall portion toward said respective opposite side portion of said gathering platform, resilient means extending between said gathering platform and said deflector means for urging said deflector means upstanding wall portion to a position to deflect the loose material located on the mine floor at the mine wall onto said material receiving surface for movement therefrom onto said gathering platform, said resilient means being freely movable between a compressed length and an uncompressed, free length to permit pivotal movement of said deflector means between a retracted position and an extended position relative to said gathering platform side portions,



a stop plate secured to each of said gathering platform side portions, said deflector means including a portion overlying and movable relative to said gathering platform, said deflector means portion having an abutment surface positioned oppositely of said respective stop plate so that upon pivotal movement of said deflector means said abutment surface is movable into and out of abutting contact with said stop plate, and said deflector means being restrained from outward pivotal movement when said resilient means extends to said uncompressed, free length by abutting contact of said abutment surface with said stop plate.

4,296,857

PROTECTIVE BAND FOR PHOTOSENSITIVE FILM ON SPOOLS


William V. Huck, White Bear Lake, Minn., assignor to Minnesota Mining and Manufacturing Company, St. Paul, Minn.

Filed Jan. 16, 1980, Ser. No. 112,159

Int. Cl.³ B65D 85/67, 85/671

U.S. Cl. 206—53

10 Claims



1. A spool and photosensitive film comprising a core and flanges extending from the core and having photosensitive film wrapped in a spiral about the core and between the flanges having as an improvement thereon an opaque band having a width nearly equal to or greater than the width between the flanges, a length in excess of the circumference of the outermost layer of film on the spool, so that the band overlaps itself, and a pitch in its relaxed state of from one eighth to eight times

the width of the band, and a portion of the film extending out from the area where the band overlaps itself.

4,296,858

TWO-WAY CONTAINER PACKAGE


John R. Platt, Wheaton, Ill., assignor to Illinois Tool Works Inc., Chicago, Ill.

Continuation-in-part of Ser. No. 40,620, May 21, 1979, abandoned. This application Dec. 14, 1979, Ser. No. 103,772

Int. Cl.³ B65D 75/00

U.S. Cl. 206—150

3 Claims



1. In a two-way package for can-type containers which have lids configured to include retained tear tab opening devices, the package including a predetermined plurality of such containers secured in an array by a thermoplastic strip device having a plurality of container carrying bands, each band surrounding, resiliently engaging and retaining a predetermined circumferential region of side wall of an associated container, said strip further including finger hole means of predetermined dimension and located within the outer perimeter of the package thus formed, a flat sheet-like member overlying the lids of the packaged array of containers, means for securing the sheet-like member to the package, a plurality of elongated slot means formed in the sheet-like member, the major dimension of said slot means being not less than the width of the retained pull-tab so that the tab may be inserted therethrough, the slot means further including means to lockingly retain the tabs to the sheet member after the tabs are inserted therethrough, the slot means being equal in number to the containers included in the array with each slot means spaced inwardly from the outer perimetrical margin of the sheet member and located so as to generally overlie the center of the lids of the associated containers when retained by the thermoplastic device, the retained tear tabs include an aperture formed therein, the means for lockingly retaining the tabs to the sheet member including a flap extending across the minor dimension of each slot means, the flaps having a width less than the major dimension of the slot means and not greater than the transverse dimension of the aperture in the retained tab, the length of the flap being substantially equal to the minor dimension of the slot means so the flap may snap into and through the aperture in the tab when the tab is inserted through the slot means, wherein the sheet member may be utilized to repack the empty containers.

4,296,859

PIGMENT PACKAGE

John L. McClinton, Hanover, Md., assignor to The Burns and Russell Company, Baltimore, Md.

Filed Aug. 22, 1979, Ser. No. 68,599


Int. Cl.³ B65D 81/32; B32B 7/02; C08L 51/00

U.S. Cl. 206—219

12 Claims

1. A package comprising an external rigid container, a removable lid for said rigid container, an internal container suitable to be filled into and removed from the rigid container as an assembly, said internal container including an oriental polystyrene film having a pigmented 100% liquid unsaturated reactive polyester resin therein in the form of a viscous substantially non-flowing paste, the film of said internal container being in at least partially wrinkled condition within said rigid

container, the volume of said paste being sufficiently less than the volume of said external rigid container with said lid thereon that the remaining volume when filled with said kringled film of the internal container that it acts as a cushion and shock absorber during transportation and prevent the internal container from moving unnecessarily while permitting ready removal of said internal container from said external container.



6. A unitary storing and shipping container assembly for bulk solid material comprising: a box having a removable top; a body member, and a base member, and a rigid pallet secured to and supporting said box at its base; said box formed of heavy corrugated material, having eight rectangular, vertical, integral face sections positioned around the outer periphery thereof and a plurality of downwardly-depending integral flaps inwardly folded within said outer periphery to form a portion of the base of said box and providing, when infolded, two opposing pairs of infolded flaps, the first of said opposed pairs having panels defining a rectangular configuration and the second of said opposed pairs having panels defining a trapezoidal configuration, said base member having opposite ends which interlock with each of the panels of said first opposed pair; said infolded flaps and base member providing the base and alignment of said box to said supporting pallet and the resultant unitary container assembly.

4,296,860


BULK MATERIAL BOX

Fu-Tong Hsu, Bridgewater, and John F. Kantz, Oxford, both of N.J., assignors to Union Carbide Corporation, New York, N.Y.

Filed Nov. 28, 1979, Ser. No. 98,066
Int. Cl.³ B65D 19/06

U.S. Cl. 206—386

13 Claims




4,296,861 ELASTIC BAND AND HANDLE STRUCTURE FOR FORMING PACKAGES OF GROUPS OF CONTAINERS

Marshall J. Barrash, Atlanta, Ga., assignor to The Coca-Cola Company, Atlanta, Ga.
Continuation-in-part of Ser. No. 65,421, Aug. 10, 1979. This application Jun. 20, 1980, Ser. No. 161,493
The portion of the term of this patent subsequent to May 26, 1998, has been disclaimed.

Int. Cl.³ B65D 75/56, 85/62

U.S. Cl. 206—428

7 Claims



1. In combination with a wrapper of material defining a package configuration:
an elongated handle strap of finite length extending over substantially a like finite adjacent surface length of a said wrapper;
said handle strap having first and second ends secured to said wrapper and having the surface area intermediate its ends substantially juxtaposed with the adjacent said surface of said wrapper;
said wrapper comprising an endless band of elastic material for surrounding a said package configuration in a stretched and tensioned condition;
said handle strap being in substantially unstretched condition when said endless band is in said stretched and tensioned condition;
said handle strap being in a relatively loose and nonjuxtaposed condition with respect to said adjacent surface of said endless band when the latter is in an unstretched condition; and
said handle strap comprising:
an elongated strip of material having a coextensive layer of adhesive thereon;
a central gripping portion defined by a centrally disposed laminate adhered to said adhesive layer while leaving an exposed area of said layer of adhesive at each end thereof; said exposed areas of said layer of adhesive providing securing means for holding said handle strap on said wrapper.

4,296,862

DEVIOUS PATH BACTERIAL BARRIER

James L. Armentrout, 21 Barlovento Ct., Newport Beach, Calif. 92663, and George H. Schneider, 22475 Overlake Dr., El Toro, Calif. 92630

Filed Aug. 27, 1979, Ser. No. 70,134


Int. Cl.³ B65D 81/24, 33/16, 51/16

U.S. Cl. 206—439

24 Claims

1. A devious path bacterial barrier for providing an air/gas pathway into and out of a sealed package from an exterior environment through an aperture in one wall of the package, including
a flat member lying within a plane and having spaced openings extending into the flat member on opposite sides of the flat member and with one of the openings for communicating with the exterior environment and with the other of the openings for overlying the aperture in the one wall of the package,
a pathway extending between the openings of the flat member and with the pathway extending within the flat member and along the plane of the flat member for intercon-

necting the openings and providing an air/gas pathway for both directions of air/gas flow between the one opening of the flat member and the other opening, and



the pathway including a plurality of bends along its length and with each bend providing an area to trap any bacteria introduced into the pathway from the exterior environment to the one opening and with all the bacteria trapped at a distance along the pathway before the other opening.

4,296,863

LIDDED CONTAINER STRUCTURE AND PACKAGE STRUCTURE FOR SAME

Henk Stokkers, Groenlo, Netherlands, assignor to Maryland Cup Corporation, Owings Mills, Md.


Division of Ser. No. 900,743, Apr. 27, 1978, Pat. No. 4,195,465.

This application Dec. 18, 1979, Ser. No. 104,821

Int. Cl.³ B65D 21/02, 85/62

U.S. Cl. 206—504

3 Claims



3. A package structure characterized by minimized exterior dimensions for a given number of filled, open-mouthed containers each having a circular bottom wall and an initially frusto-conical sidewall initially defining an open container mouth of circular configuration opposite said bottom wall, said package structure comprising:

- a square configured lid means on each of said filled containers deformably engaging each said sidewall and covering said container mouth therein to constrain said container mouth to assume a square configuration and said sidewall to assume a transitional configuration from said circular bottom wall to said square configured lid and container mouth;
- a said given number of said filled containers in juxtaposition through their respective square configured lid means to define a rectangular grouping of said given number of containers; and
- a bulk package means confining said rectangular group of containers.

4,296,864

AIR CLASSIFIER

Takaaki Misaka, Koganei; Takeshi Furukawa, Kawasaki, and Eiichi Onuma, Narashino, all of Japan, assignors to Onoda Cement Co., Ltd., Japan


Filed Jul. 9, 1980, Ser. No. 167,048

Claims priority, application Japan, Jul. 17, 1979, 54/89793; Jul. 17, 1979, 54/89794

Int. Cl.³ B04C 5/103

U.S. Cl. 209—144

31 Claims



1. An air classifier which comprises:
a casing formed of a generally hollow cylindrical vertical casing body and a hopper fitted to the lower end of said casing body;
a fine product outlet duct set at the center of the upper end wall of the casing body;
an air-powder raw material inlet duct tangentially projecting outward from the casing body;
a rotary shaft concentrically extending through the casing body;
a rotary disc member concentrically fixed in the casing body and set at a boundary between the casing body and the hopper to concurrently carry out the dispersion and classification of a powdered material; and
guide vanes provided in the casing body in a state equidistantly spaced from each other in the circumferential direction of said casing body to conduct a mixture of air and a powder raw material into said casing.

4,296,865

MAGNETIC SEPARATOR HAVING TWO ROTATING MAGNETIC DRUMS OF OPPOSITE POLARITY

Heinrich Spodig, Netteberge 202, D-4714 Selm/Westf., Fed. Rep. of Germany

PCT No. PCT/DE78/00009, § 371 Date Mar. 25, 1979, § 102(e) Date Mar. 19, 1979, PCT Pub. No. WO79/00060, PCT Pub. Date Feb. 22, 1979

PCT Filed Jul. 5, 1978, Ser. No. 24,181

Claims priority, application Fed. Rep. of Germany, Jul. 25, 1977, 2733473

The portion of the term of this patent subsequent to Jun. 12, 1996, has been disclaimed.


Int. Cl.³ B03C 1/02, 1/26

U.S. Cl. 209—216

1 Claim

1. A magnetic separator comprising the combination of two rotatable magnetic drums of opposite polarity forming a working air-gap therebetween, each said drum including a plurality of grooves distributed in a radial direction around their peripheries and extending in an axial direction, said combination further including two directionally magnetized block magnets arranged on each side of said magnetic drums, said drums being arranged in a housing comprising a pair of slide plates positioned in the working air-gap, said plates converging at the inlet and diverging at the outlet, said block magnets being disposed in a closed magnetic circuit and being connected in pairs at the bottom part of their poles of unlike polarity by means of soft-iron parts, said block magnets having on the

upper side of their poles of unlike polarity a pair of axially spaced apart pole shoes in which soft-iron parts are disposed



and which last mentioned soft-iron parts serve as the axles for said rotatable magnetic drums.

4,296,866

ARTICLE DISPLAY STAND


Stanley J. Learnard, 12659 Willow Spring Ct., Herndon, Va. 22070

Filed Apr. 5, 1979, Ser. No. 27,385

Int. Cl.³ A47F 5/01, 5/02

U.S. Cl. 211—131

12 Claims



1. An article display stand, comprising: a frame; and a plurality of pairs of stacked wire baskets supported on the frame, with each pair including a top basket and a bottom basket, the top basket including first wires spaced apart a first distance, and the bottom basket including second wires spaced apart a second distance less than the first distance, and the wires of both baskets of each pair defining a plurality of article supporting and display pockets wherein the first wires of the top basket define side supports for the articles in the pockets and the second wires of the bottom basket define bottom supports for the articles in the pockets.

4,296,867

DEVICE FOR LOCKING SLEWING PORTION OF CARGO CRANE

Iosif M. Berkhin, prospekt Gagarina, 17, kv. 35; Robert A. Gudze, prospekt Gagarina, 17, kv. 11; Vasily I. Kekalo, ulitsa Letchikov, 33, kv. 88, all of Sevastopol; Nikolai N. Panasenko, Volgogradsk, ulitsa Morskaya, 118, kv. 46, Rostovskaya oblast; Viktor I. Podbeltsev, ulitsa B. Morskaya, 38, kv. 4, Sevastopol; Zinaida D. Tsypina, ulitsa Volodarskogo, 5, kv. 5, Sevastopol, and Vladislav N. Mukhin, ulitsa B. Morskaya, 52/2, kv. 36, Sevastopol, all of U.S.S.R.

Filed Sep. 16, 1979, Ser. No. 75,108

Int. Cl.³ B66C 23/62

U.S. Cl. 212—229


7 Claims

1. In a cargo crane having a slewing portion movable with

respect to a stationary portion, a device for locking the slewing portion relative to the stationary portion comprising:

first stop means rigidly secured on the slewing portion of the crane;

second stop means rigidly secured on the stationary portion of the crane, said first and said second stop means having confronting surfaces spaced from each other when said slewing portion is in a position to be locked;



wedge means movable into a space between the confronting surfaces for frictionally engaging each of the confronting surfaces to thereby lock said first stop means relative to said second stop means; and

drive means for bringing said wedge means into and out of frictional engagement with said confronting surfaces.

4,296,868

HOUSING FOR DRAFT GEAR

Richard J. Housman, Dolton, Ill., assignor to Westinghouse Air Brake Company, Pittsburgh, Pa.


Continuation of Ser. No. 841,769, Oct. 13, 1977, abandoned.

This application Nov. 21, 1979, Ser. No. 96,342

Int. Cl.³ B61G 9/20

U.S. Cl. 213—50

3 Claims



1. A draft gear housing of a generally rectangular cross section defined by a top wall, a bottom wall, a pair of opposing side walls, a rear wall and an open end opposite said rear wall; said top wall and said bottom wall having internally disposed thereon longitudinally extending strengthening ribs partially defining a main spring chamber and corner spring chambers, each of said ribs having a rear portion comprising a pair of opposing arcuate sides culminating at a peak, one of said arcuate sides of each rib partially defining one of said corner spring chambers, and the other of said arcuate sides of each rib partially defining said main spring chamber, said other of said arcuate side of each of said ribs gradually increasing in radius of curvature from said rear wall toward said open end so as to produce a decrease in both width and height of each said ribs.

4,296,869

PRESSURE VESSEL HEAD


Maan Jawad, Collinsville, Ill., assignor to Nooter Corporation, St. Louis, Mo.

Filed May 18, 1979, Ser. No. 40,597

Int. Cl.³ E04B 1/32

U.S. Cl. 220—3

10 Claims



1. A head for a pressure vessel, said head comprising: a frame having stiffeners arranged to form a grid, with each stiffener having a series of alternate lands and shoulders; plates closing the openings in the grid, there being a plurality of plates in each opening of the grid with the plates of each opening becoming progressively larger in surface area through the opening, the plates in each grid opening being stacked one upon the other such that the adjacent plates of each opening are directly against each other, the plates of each grid opening further being configured and positioned such that the shoulders for the stiffeners that are along the opening face the side edges of the stacked plates and the lands of the stiffeners underlie the peripheral portions of the plates; and welds along the peripheries of the plates and adjacent surfaces of the stiffeners for attaching the plates to the stiffeners, the welds for successive plates being offset from each other by reason of the variances in the size of the plates.

4,296,870

COVERS FOR ELECTRICAL BOXES

G. Russell Balkwill, 2429 Howard Ave., Windsor, Ontario, Canada (N8X 3Y5); Jules P. Robinet, 2865 Virginia Park, Windsor, Ontario, Canada (N9E 2B8), and John F. Tamasovics, 2530 Todd La., Windsor, Ontario, Canada (N9H 1K5)


Continuation-in-part of Ser. No. 36,436, May 7, 1979, abandoned, which is a continuation of Ser. No. 908,223, May 22, 1978, Pat. No. 4,158,420. This application Jun. 12, 1979, Ser. No. 47,793

The portion of the term of this patent subsequent to Jun. 19, 1996, has been disclaimed.

Int. Cl.³ H02G 3/08

U.S. Cl. 220—3.3

14 Claims



1. In combination, a metal electrical box having an open face, a cover of flexible plastic material having a receptacle extending around and enclosing the back and at least portions of the sides of said box and forming an air and vapor barrier around said box, said cover leaving the open face of said box uncovered, said cover having a slanted flange around the perimeter near the open face of said box and having a slanted

front surface extending outwardly therefrom and slanting away from said cover, whereby the peripheral edge of the flange can tightly contact the back surface of a wall or the like around the open face of the box, said cover providing a barrier to prevent water from entering the outlet box through the sides and back thereof, and said cover having means by which the open face of said electrical box can extend beyond said slanted flange by varying distances.

4,296,871

RECEPTACLE WITH A COVER OF PLASTICS MATERIAL


Poul G. Andersson, Salzburg, Austria, assignor to Ring Lock Container S. A., Panama City, Panama

Filed Jul. 23, 1979, Ser. No. 59,685

Int. Cl.³ B65D 43/10, 43/03, 17/28

U.S. Cl. 220—306

11 Claims



1. In a receptacle of the type which has a continuous sidewall with an open top end; an external circumferential bead on said sidewall substantially at said open top end, a cover of plastic material which has a depending circumferential flange provided with an internal circumferential bead which snaps beneath the lower portion of said external bead to tightly close the cover onto the receptacle sidewall, and a downward extension of said flange below said internal bead, the improvement comprising, in combination:

an integral external locking ring surrounding said receptacle sidewall, said locking ring being effectively L-shaped in cross section with a lower ledge beneath the cover flange and an upright annular rib encircling at least a major portion of the downward extension of the cover flange, an integral annular wall on said cover having an outwardly facing surface fitting snugly against the inner surface of the receptacle sidewall radially inwardly of said beads, connecting means connecting the locking ring lower ledge to the receptacle sidewall, said connecting means being defined at least in part by circumferentially spaced connections creating a zone of weakening, and reinforcing means extending downwardly from said spaced connections in close proximity to the container wall, said reinforcing means permitting rupture of said connections by a downward translational force applied to the locking ring parallel to the receptacle sidewall to give access to the lower edge of the cover flange to remove the cover from the container, while the close proximity of said reinforcing means to the container wall limits inward displacement of said reinforcing means and correspondingly limits outward displacement of said rib to a distance insufficient to give access to the lower edge of the cover flange, thereby to effectively prevent removal of said cover from the container as long as said connections remain unruptured.

4,296,872

DELIVERY BOX ASSEMBLY FOR MERCHANDISING MACHINE


Robert P. Mitchell, Pequannock, and Frank T. Scalera, Maplewood, both of N.J., assignors to Rowe International, Inc., Whippany, N.J.

Filed Sep. 21, 1979, Ser. No. 77,611

Int. Cl.³ G07F 11/00

U.S. Cl. 221—195

11 Claims



5. A delivery box assembly for receiving an article of merchandise from a dispensing unit and for holding the article at a location at which it is accessible to a customer including in combination, a box having a first opening through which said box is to receive an article from said dispensing unit and having a second opening through which said article may be removed by a customer, a door, first shaft means mounting said door adjacent to said second opening for movement between an open position and a closed position, a baffle, second shaft means mounting said baffle for movement between an inoperative position and an operative position at which it effectively blocks said first opening, respective left-hand and right-hand first cranks on said door mounting shaft means for movement therewith, respective left-hand and right-hand second cranks on said baffle shaft means for movement therewith, pins carried respectively by one of each of said first and second cranks, the other of each of said first and second cranks being formed with a slot for receiving one of said pins to provide connections between said first and second cranks, said pin and slot connections being such that said baffle moves to its operative position in response to movement of said door to its open position.

4,296,873

AUTOMATIC VENDING ARRANGEMENT

Alois Schlumpf, Zumikon, Switzerland, assignor to Tax o mex AG, Switzerland

Filed Dec. 11, 1979, Ser. No. 102,362

Claims priority, application Switzerland, Dec. 12, 1978, 12645/78


Int. Cl.³ B65H 3/22

U.S. Cl. 221—213

6 Claims

1. In an automatic vending arrangement for the sale of newspapers or periodicals, a housing having a dispensing slot at the upper front side thereof; including a cash box arrangement and a dispensing arrangement, said cash box arrangement including coin testing means, coin return means and coin receiving means; and actuating means for said dispensing arrangement, said dispensing arrangement including a vertically displaceably guided support table and a lever-actuated dispenser, the improvement comprising: at least one set of pulleys for raising said support table having one end of the pulley fastened to said

table and another end to said housing; spring means for pulling said pulley downwardly; sensor means having sensor arm means supported in a horizontal pivot bearing at one end thereof, including a sensor feeler directed against said support table and sensor pin means engageable in the raised position into a sprocket roll for rendering stationary said set of pulleys; a pivot lever pivotable in a horizontal plane about a vertical



rotational axle arranged sidewise of the area of said support table; linkage means connecting the free end of said pivot lever with a handgrip for changing a direction of movement; and a gripper arm being vertically movably linked to said pivot lever and arranged at least approximate the middle axis of said support table, said gripper arm including a vertically movable gripper pawl linked thereto having gripper needles and release and latching means for said gripper latch.

4,296,874

BALL HOLDER


Roger C. Evans, 10214 Dogwood Ave., Palm Beach Gardens, Fla. 33410

Filed Dec. 1, 1976, Ser. No. 746,592

Int. Cl.³ B65D 85/58

U.S. Cl. 221—307

1 Claim



1. A ball holder comprising a tubular body member for holding balls, said tubular body member having a bottom for supporting balls, said bottom having a slot therein, a flattened tubular member extending from the bottom of said tubular body member around said slot and forming the bottom end of the holder, said tubular body member having a closed top, said top having a holding means for supporting the ball holder, said bottom of said tubular body member and said flattened tubular member being formed of a resilient material so that they can be temporarily deformed to a size to permit a ball to pass there-through, the interior of the bottom of the tubular body member

being spherically shaped for matching the contour of the balls being held to support a ball by having surface contact.

4,296,875

FOAM DISPENSING APPARATUS FOR MARKING ON A GROUND SURFACE THE WORKING PATTERN OF A SURFACE WORKING VEHICLE


Richard P. Borglum, Janesville, Iowa, assignor to Richway Industries Ltd., Janesville, Iowa

Filed Nov. 29, 1979, Ser. No. 98,500

Int. Cl.³ A01C 15/00; B05B 7/30

U.S. Cl. 222—617

3 Claims



1. A foam dispensing apparatus mountable on a ground surface working vehicle for marking on the ground surface the working pattern of the vehicle on said surface, said apparatus comprising:

- (a) a storage tank on said vehicle for containing a foaming agent solution;
- (b) a combination air pump and foam generating unit including a rotary driven member rotatably mounted on said vehicle;
- (c) a series of circumferentially spaced roller members;
- (d) means mounting said roller members on said rotatable member in a circular row about the axis of rotation of said rotary member;
- (e) a flexible tube member arranged in a plane parallel to the plane of rotation of said rotary member having an inlet section, an outlet section, and an intermediate section;
- (f) means mounting said tube member on the vehicle with said intermediate section trained about and in pressing engagement with certain of said rollers, said pressing engagement acting to close said tube at each of said certain rollers;
- (g) means for fluid coupling said inlet section of the tube, with said tank to receive the foaming agent solution;
- (h) an air inlet for supplying air to said tube inlet section;
- (i) a valve unit in said fluid coupling means located between said tank and said air inlet for controlling the rate of admission of the foaming agent solution into said inlet section for mixing with the air from said air inlet, with portions of the foaming agent solution and air being mixed and successively moved through the tube by the engaged rollers for flow into the outlet section in a foam form and,
- (j) a foam discharge unit connected to the outlet section for directing the foam to the ground surface adjacent one side of said vehicle.

4,296,876

GARMENT CHECKING BAG

Henry R. Lefebvre, Laguna Hills, Calif., assignor to Sun Aired Bag Co., Inc., Sunland, Calif.

Filed Mar. 29, 1979, Ser. No. 25,197


Int. Cl.³ A47J 51/08, 51/14

U.S. Cl. 223—91

3 Claims

1. A garment bag structure including horizontal bar means, hook means projecting upwardly from an opening in an inter-

mediate portion of said horizontal bar means, a foraminous bag attached to and depending from said bar means, and a horizontal rod means attached to said bar means, said horizontal bar means comprising a cylindrical member having an opening in



each end thereof, and said horizontal rod means having bent portions at each end thereof that rotatably engage the openings at the ends of said horizontal bar means, said horizontal rod means being rotatable to a position contiguous with said bag, whereby said structure occupies a relatively narrow space.

4,296,877

NEEDLE THREADER


Allen Lubow, 300 Clinton Ave., Brooklyn, N.Y. 11205

Filed Jan. 7, 1977, Ser. No. 757,685

Int. Cl.³ D05B 87/02

U.S. Cl. 223—99

6 Claims



1. A needle threader usable by individuals who find it difficult to thread a needle in a conventional manner, said needle having an elongated eye with a predetermined length and width, said threader comprising:

- A. a blade whose upper end is of uniform width and thickness and is cut to define a V-notched head, across whose trough the end of the yarn or filament to be threaded is loosely laid, said blade end having a width which is less than the length of the eye and a thickness which is less than the width of the eye which makes it possible to pass the eye of the needle to be threaded over the end of the blade to a point well below the trough to cause the end of the yarn or filament to be curved into a sizable loop whose feet are clamped to the sides of the blade by the eye of the needle, whereby when the needle is thereafter retracted from the head it carries from the loop therewith, which loop can then be grasped and pulled out to thread the needle, said head being effectively divided into at least two notched sections of different width, with troughs of different depths; and
- B. means to anchor the lower end of the blade.

4,296,878

SURFBOARD CARRIER


Franklin D. Ward, and Rock A. Engeman, both of 5582 Kern, Huntington Beach, Calif. 92649

Filed Jun. 8, 1979, Ser. No. 46,989

Int. Cl.³ B62J 7/00

U.S. Cl. 224—32 A

4 Claims

**1. A surfboard carrier for bicycles comprising:**

a pair of U-shaped members extending rearward of and opening toward the bicycle for being positioned on opposite sides of the rear wheel of the bicycle, each U-shaped member having an upper attachment end for being attached to an upper portion of the bicycle and a lower attachment end for being attached to a lower portion of the bicycle;

first and second cross members attached between the pair of U-shaped members at spaced locations rearward of the bicycle for defining a lower, generally rectangular, retention region;

a third cross member attached between the pair of U-shaped members at a location above the first and second cross members for defining an upper, generally U-shaped, retention region opening away from the bicycle, wherein the third cross member is forward of the first and second cross members for positioning the upper U-shaped retention region forward of the lower rectangular retention region for holding the surfboard with its nose end down and its skag end tilted forward for positioning the center of gravity of the board generally over the rear wheel of the bicycle;

first elastomeric holding means attached about the inside of the lower retention region for simultaneously pressing against a top and an opposite bottom surface region and opposite edge regions about a nose end peripheral portion of the surfboard for holding the nose end peripheral portion substantially immovable side-to-side and back-and-forth; and

second elastomeric holding means attached about the inside of the upper retention region for pressing against a top and opposite bottom surface region at a central portion of the surfboard for holding the surfboard at the central portion substantially immovable side-to-side.

4,296,879

BIKE CARRYING ADAPTER

Harold G. Jordening, 1541 E. La Palma, A-3, Anaheim, Calif. 92805

Filed Aug. 29, 1980, Ser. No. 182,477

Int. Cl.³ B60R 9/10

U.S. Cl. 224—42.45 R

4 Claims

1. A device for adapting a vehicle mountable bicycle carrier capable of carrying one size bicycle to permit the carrier to carry bicycles of various sizes comprising:


(a) an extensible support member,

(b) means for securing the length of the extensible support member at a selected one of a plurality of selectable lengths,

(c) means for fastening the extensible support member to a vehicle-mountable bicycle carrier,

(d) means near the rear end of the extensible support member for supporting the rear portion of a bicycle, and

(e) means near the front end of the extensible support member for supporting the handle bars of a bicycle, said bicycle handle bar supporting means, comprising a pair of parallel J-hooks fastened to either side of the extensible support member near said front end of the extensible



support member, the J-hooks extending outward from said front end of the extensible support member with the long straight portions of the J's parallel to the axis of extensibility of the extensible support member and the U-shaped ends of the J-hooks lying in parallel vertical planes on opposite sides of the extensible support member with the interior portions of the U-shaped ends facing towards the rear end of the extensible support member.

4,296,880

COMBINATION STORAGE AND CARRYING DEVICE

Frank A. Olshefsky, 3578 Gunderland Rd., Schenectady, N.Y. 12306

Filed Jul. 2, 1979, Ser. No. 53,863

Int. Cl.³ A47G 23/06

U.S. Cl. 294—144

10 Claims

**1. A combination storage and carrying device for transporting and storing a quantity of firewood and the like, and comprising:**

a substantially flat base portion having first and second pairs of spaced apertures extending therethrough;

a first handle member positioned on an upwardly facing side of said base portion and having a pair of separate leg sections extending through and beyond said first pair of apertures to a downwardly facing side of said base portion, and a second handle member also positioned on said upwardly facing side of said base portion and having a pair of separate leg sections extending through and beyond said second pair of apertures;

each leg section extending through and beyond one of said apertures including first and second portions having longitudinal axes forming an acute angle, and a third, smoothly curved portion joining said first and second portions to one another, whereby the first portions of a pair of leg sections forming a handle member rest against the upwardly facing side of said base portion and the second portions contact a storage support surface to elevate said

base portion above said storage support surface when said respective handle member assumes a fully reclined position, whereby the third portions of each pair of leg sections forming a handle member contact the storage support surface and the second portions each contact a downwardly facing side of said base portion to elevate said base portion above said support surface when said respective handle member assumes a fully open position;

side wall means extending from predetermined locations on the upwardly facing side of said base portion for resisting pivotal movement of said first and second handle members away from said upwardly facing side of said base portion beyond a predetermined location corresponding to their fully open positions.

4,296,881

SURGICAL STAPLER USING CARTRIDGE


Sukoo Lee, 30 Widewaters La., Pittsford, N.Y. 14534

Filed Apr. 3, 1980, Ser. No. 136,785

Int. Cl.³ B27F 7/00; A61B 17/04

U.S. Cl. 227—30

6 Claims

**1. A surgical stapling tool using disposable cartridge elements and having a staple folding anvil, an actuator movable toward and away from said anvil, a holder for an array of staples oriented toward said anvil, and a pusher for pushing said staples from said holder through tissue to be stapled and against said anvil, said tool comprising:**

- said movable actuator and said staple pusher being shaped relative to each other so said pusher mounts on said actuator in a retention fit and moves with said actuator toward said anvil;
- said holder being shaped for a retention fit on said pusher for movement with said pusher independently of said actuator and said anvil;
- said pusher being movable relative to said holder by force overcoming a predetermined frictional resistance between said pusher and said holder; and
- said actuator being movable through a distance sufficient to advance said pusher and said holder until said holder presses against and is stopped by tissue supported by said anvil and then continuing to advance said pusher into said holder to drive said staples through said tissue and against said anvil to staple said tissue.

4,296,882

CENTRIFUGAL FLUID PROCESSING DEVICE

Susumu Kobayashi, Fujinomiya, Japan, assignor to Terumo Corporation, Tokyo, Japan

Filed Feb. 19, 1980, Ser. No. 122,188

Claims priority, application Japan, Feb. 26, 1979, 54-21716

Int. Cl.³ B04B 11/00, 9/08

U.S. Cl. 233—21

16 Claims

1. A centrifugal fluid processing device comprising:

a stationary base;


a vertically extended support mounted on said stationary base and having a vertical axis;

a rotor rotatably supported on said vertically extended support and being rotatable about the vertical axis of said vertically extended support;

a rotor drive assembly coupled to said rotor;

fluid processing container means rotatable along with said rotor about said vertical axis and being further rotatable independently of said rotor about an axis of rotation disposed radially or perpendicular to said vertical axis;

a flexible communication conduit which has one end thereof



extended into said fluid processing container means and the other end thereof led to the outside of the device and through which a fluid to be processed is fed into said fluid processing container means, said flexible fluid communication conduit comprising at least a radially extending section which extends along said radially disposed axis of rotation and a vertically extending section which extends along said vertical axis of said vertically extended support; and

means to drive said fluid processing container means for rotating the same about said radially disposed axis of rotation.

4,296,883

HEAT GENERATION AND DISTRIBUTION SYSTEM


Andrew F. Yanna, 4389 Jean Rd., Bay City, Mich. 48706

Filed May 18, 1979, Ser. No. 40,457

Int. Cl.³ F24D 3/00

U.S. Cl. 237—59

7 Claims



1. In combination with a heat source, a closed heat distribution system for delivery of heat from the heat source to a location of use for dissipation of heat below or level with the heat source wherein the system contains a liquid heat transfer medium, a generating tank adjacent said heat source and containing said liquid medium for absorption of heat by the liquid medium, radiator means for withdrawal of heat from the liquid medium and delivery of heat to the location of use, the radiator means being located in a horizontal or downwardly sloping run from said generating tank and being connected thereby to

the generating tank, a return tank connected to the radiator means for receiving the output of liquid medium from the radiator means, a vacuum tank for receiving the output of liquid medium from the return tank, said vacuum tank having a vacuum space adjacent the tanktop, said output being received within the vacuum space and a supply tank for receiving the output of liquid medium from the vacuum tank and for feeding liquid medium to the generating tank, said supply tank being connected to the generating tank by a connecting line which extends upwardly into the supply tank and has an opening within the space defined inside the supply tank, said supply tank being open to ambient surroundings and being connected to the vacuum tank by a downwardly sloping traverse pipe from adjacent the bottom of said vacuum tank, said vacuum tank being located above said return tank and supply tank and is enclosed, having covering means provided with a valve for selectively admitting air from the ambient surroundings to the interior of the vacuum tank, said generating tank, said radiator means and said return tank being closed and sequentially connected, the return tank being higher in elevation than the generating tank and radiator means, the distribution system being operable continuously through application of heat from the heat source to the generating tank without use of any mechanical pumping means.


4,296,884

CONTAINMENT RESERVOIR AND METHOD
Robert W. Luebke, Hudson, Ohio, assignor to True Temper Corporation, Cleveland, Ohio

Filed Jan. 23, 1979, Ser. No. 5,699
Int. Cl.³ E01B 2/00; E02D 27/48

U.S. Cl. 238—2

19 Claims



1. A containment reservoir for a liquid, such as petroleum based oil, comprising, a walled containment space opening upwardly, said space containing a flexible liquid impervious liner generally following the contour thereof, in at least one direction thereof, said liner comprising a layer of liquid pervious fabric material having on at least one of its sides an attached layer of liquid impervious material, such as rubber, which is resistant to oil degradation, said liner being operable to prevent escape of liquid from said reservoir through said liner from said containment space, a relatively coarse particle bed located on said liner and filling said containment space, a layer of liquid pervious flexible fabric filter material supported on said bed and covering the open top of said bed, and means coacting with said liner covered containment space for removing liquid therefrom.

4,296,885

PROCEDURE FOR THE CAREFUL APPLICATION OF LIQUIDS TO PLANTS IN AGRICULTURAL STANDS
Jürgen Norden, Bochum, and Bruno Ucinhaszka, Dülmen, both of Fed. Rep. of Germany, assignors to Ruhr-Stickstoff Aktiengesellschaft, Bochum, Fed. Rep. of Germany


Filed Dec. 13, 1979, Ser. No. 103,542

Claims priority, application Fed. Rep. of Germany, Dec. 13, 1978, 2853773

Int. Cl.³ A01C 23/00

U.S. Cl. 239—1

18 Claims



1. A method of spraying agricultural stands with a liquid, comprising the steps of:

supplying said liquid from a portable source of plant spray liquid, including a spray rod having apertures for liquids at 50 cm intervals to a distributor element connected to each of said apertures, at least one flexible drag hose connected at one end to each said distributor element, each said flexible drag hose having at least one nozzle adjacent the other end, said drag hoses having a length such that said other end of said drag hoses are free hanging at a point below the leafy rooves of said stands, and at least one metering device associated with each said distributor element; and

feeding said liquid to said agricultural stands from said nozzles, whereby the leafy rooves of said stands are not damaged by said liquid.

4,296,886

SHOWER FITTINGS

Lionel T. Bloyce, Maidenhead, and Michael J. Morley, Bray, both of England, assignors to Albany International Corporation, Albany, N.Y.


Filed Sep. 17, 1979, Ser. No. 76,292

Claims priority, application United Kingdom, Sep. 21, 1978, 37666/78

Int. Cl.³ B05B 3/18

U.S. Cl. 239—264

4 Claims



1. A shower fitting comprising in combination a first tubular member with an interior passageway therethrough, closure means at one end of said passageway, fluid connection means positioned at the other end of said first member to enable the

passageway to be connected to a source of fluid, a series of aligned spray jets mounted upon the said first tubular member at spaced intervals along the length thereof and being in communication with said passageway, a second tubular member, said first tubular member being housed within said second tubular member, said spray jets being wholly contained within said second tubular member, support means at the ends of said second tubular member, further support means located at spaced points along the length of said first tubular member and being secured to the latter, said support means and said further support means supporting said first tubular member within said second tubular member for reciprocatory movement relatively thereto, a longitudinal slot in said second tubular member, said slot being aligned with said spray jets and permitting fluid discharged therefrom to emerge from said second member, driving means mounted upon said second tubular member, and drive connection means extending within the second member from the driving means to said closure means to impart reciprocatory movement to said first tubular member.

4,296,887

HEAT PROTECTED FUEL INJECTION PLUG FOR INTERNAL COMBUSTION ENGINES

Karl Hofmann, Remscheid, Fed. Rep. of Germany, assignor to Robert Bosch GmbH, Stuttgart, Fed. Rep. of Germany



Filed Sep. 17, 1979, Ser. No. 75,907

Claims priority, application Fed. Rep. of Germany, Sep. 15, 1978, 7827497[U]

Int. Cl.³ F02N 61/14

U.S. Cl. 239—397.5

4 Claims



1. Heat protection construction for a fuel injection plug (10), adapted for insertion into an opening (15, 16) in the cylinder block (14) of a Diesel internal combustion (IC) engine, wherein the plug has an end surface (12) facing the combustion chamber of the engine and a fuel injection opening formed in said end surface; and comprising a bushing (20, 30) surrounding the plug in the region of the injection opening thereof, said bushing integrally including, in accordance with the invention, an external flange (21, 31) fitting against a matching seat (17) formed in the opening (15, 16) of the cylinder block, and a resiliently deformable terminal sealing lip (22, 32) integrally connected with said external flange and formed as an in-turned inwardly directed resilient flange portion overlapping a portion of the terminal end face surface (12) of the plug (10) and in resilient sealing and heat protecting engagement with said terminal end face surface.

4,296,888

POWDERED COAL AIR DISPERSION NOZZLE


Thomas P. Kosek, East Detroit, and Eric A. Steinhilper, Mt. Clemens, both of Mich., assignors to General Motors Corporation, Detroit, Mich.

Filed Feb. 28, 1980, Ser. No. 125,469

Int. Cl.³ B05B 7/10

U.S. Cl. 239—403

4 Claims



1. A powdered coal/air dispersion nozzle for introducing a fluidized coal/air fuel mixture as a finely atomized dispersed spray for uniform combustion in a gas turbine engine combustor apparatus comprising: an elongated nozzle tube having an inlet for connection to a fluidized coal/air source with a coal particle size in the range of one to three hundred microns, said elongated nozzle tube having an outlet therefrom, scroll means including a sheet element located within said nozzle tube having spaced longitudinal edges thereon in engagement with said tube, said sheet element having a thin cross-section at all points throughout the twisted length thereof to prevent build-up of coal particles through the length of said scroll means, said sheet element being twisted along its length to impart a continuous swirl to the fluidized coal/air fuel mixture supplied to the inlet and said sheet element having a length-to-width ratio greater than one to impart a swirl in the fluidized coal/air mixture which is sustained as the fluidized coal/air fuel mixture is directed from said outlet, and pintle means overlying said outlet and operative to direct said sustained swirl of the fluidized coal/air mixture as a spray cone for combustion within the combustor.

4,296,889

METHOD AND APPARATUS FOR WINDING TEXTILE YARNS

Gerhard Martens, Remscheid, Fed. Rep. of Germany, assignor to Barmag Barmer Maschinenfabrik Aktiengesellschaft, Fed. Rep. of Germany


Filed Dec. 18, 1979, Ser. No. 104,969

Claims priority, application Fed. Rep. of Germany, Dec. 22, 1978, 2855616

Int. Cl.³ B65H 54/38

U.S. Cl. 242—18.1

40 Claims



1. In a method of winding textile yarns into core-supported packages in which the yarn is wound about the core at a substantially constant rate while the yarn is guided onto the core by a traversing yarn guide and in which the traverse motion speed of the yarn guide is continually changed by accelerating and decelerating the traverse motion of the yarn guide, the improvement therein comprising changing aperiodically the traverse motion speed of the yarn guide by varying aperiodically at least one of the time intervals between switching from acceleration to deceleration or vice versa, the rate of acceleration and/or deceleration and the traverse motion speed attained between switching from acceleration to deceleration or

vice versa to prevent undesirable pattern formation in the yarn windings in the package formed thereby.

4,296,890

PROCESS FOR THE SIMPLIFIED PACKING OF A MAGNETIC TAPE FOR COMPUTER AND WINDING CORE FOR CARRYING OUT THIS PROCESS


Patrick Posso, 10, Avenue Jurigoz, Lausanne, Switzerland (CH-1006)

Filed May 7, 1980, Ser. No. 147,520

Claims priority, application France, May 14, 1979, 79 12221
Int. Cl.³ B65H 75/18

U.S. Cl. 242—71.8

6 Claims



1. Process for the simplified packing of a magnetic tape for a computer consisting in delivering large width magnetic film under tension, in splitting this film lengthwise into a plurality of tapes having the required width, in providing a plurality of cores, in winding each tape on a core and in mounting on this core when it is filled with tape at least one side element in order to constitute a packing spool, this process making it possible to eliminate the operation of rewinding the tape stored around a core in a preconstituted spool, each core comprising a peripheral tubular ring for winding and a central drive hub, concentric with respect to each other and connected together by a web, each core further comprising reinforcing means disposed in the free space existing between said ring and said hub over virtually the whole width of said core, in order to ensure the strength and precision of the core, and each core also comprising means for mounting said side element on the side of said core.

4,296,891

EXPANDABLE CORE FOR ROLLS OF TUBING


H. John Sidaway, Findlay, Ohio, and Maynard Good, Elkhart, Ind., assignors to Hancor, Inc., Findlay, Ohio

Filed Feb. 4, 1980, Ser. No. 118,085

Int. Cl.³ B65H 75/24, 75/40

U.S. Cl. 242—110

19 Claims



1. An expandable reel for rolls of tubing comprising a base rod extending generally along the longitudinal axis of said reel; a plurality of support members disposed radially outwardly from said base rod and extending substantially parallel thereto;

a plurality of connecting links extending between and operatively connecting said support members and said base rod, said links hingedly connected to a first point along the length of said links for pivotal movement about a hinge; camming surfaces at the terminal ends of said support members; and, means for selectively expanding said reel from a first to second expanded position adapted to engage said camming surfaces.

4,296,892

SPHERICAL LIVING MODULE OR SPACE


Presley O. Barge, 2868 Pine Pl., St. Louis, Mo. 63115

Filed Jan. 2, 1979, Ser. No. 26

Int. Cl.³ B64C 35/00, 37/00, 39/02

U.S. Cl. 244—2

2 Claims



1. A substantially spherical self-propelled human living space comprising a shell, a plurality of elongated coaxial shafts journaled for rotation in said shell and projecting radially therefrom, helicopter blades mounted on said shafts outside said shell, and means within said shell for rotating said blades; and elongated pontoons, a set of said pontoons projecting chordally from said shell, spaced apart and parallel to one another, in one direction, and another set of said pontoons projecting chordally from said shell in the opposite direction, said sets of pontoons being aligned with one another, and coupling means carried by and at the ends of said pontoons, for engaging and coupling the complementary coupling means carried by pontoons of another of said living spaces.

4,296,893

PROJECTILE WITH SPIN-PRODUCING FLOW PASSAGES

Josef Ballmann, Oberforstbacher Str. 228, D-5100 Aachen, Fed. Rep. of Germany


PCT No. PCT/DE78/00007, § 371 Date Mar. 9, 1979, § 102(e)
Date Mar. 8, 1979, PCT Pub. No. WO79/00038, PCT Pub.
Date Feb. 8, 1979

PCT Filed Jul. 3, 1978, Ser. No. 21,606

Int. Cl.³ F42B 13/24, 15/14

U.S. Cl. 244—3.23

12 Claims



1. A projectile for shooting from a gun barrel in response to

the force of a propellant gas emanating from the aperture of a propellant container, comprising a projectile body having a plurality of spin-producing propellant gas flow passages associated therewith, said passages annularly surrounding, and having their respective axes extending obliquely to, the longitudinal axis of the projectile body, wherein each passage has an inlet portion converging to an adjoining constricted portion, and a diverging portion extending downstream from the constricted portion, the axis of each passage being curved over the entire length of its converging inlet portion and substantially rectilinear over its diverging portion, and the walls of the diverging portion of each passage having a substantially rectilinear form, as viewed in the direction of propellant gas flow.

4,296,894

DRONE-TYPE MISSILE

Werner Schnäbele, Wolftrathshausen; Jack Buckley, Albaching, and Ulrich Rieger, Feldkirchen-Westerham, all of Fed. Rep. of Germany, assignors to Messerschmitt-Bölkow-Blohm GmbH, Munich, Fed. Rep. of Germany


Filed Feb. 23, 1979, Ser. No. 14,720

Claims priority, application Fed. Rep. of Germany, Feb. 8, 1979, 2904749

Int. Cl.³ F42B 13/32, 15/16

U.S. Cl. 244—3.27

8 Claims



1. A drone missile system, comprising:
a missile having a target-seeking head,
a guidance system,
a self-propulsion and take-off system,
electronic means for storing individual mission data prior to the mission,
a pair of wings,
a tail assembly, and
a propeller,
said missile having a shape defining a longitudinal direction, said wings, as well as said tail assembly and said propeller being foldable in the longitudinal direction of the missile and automatically unfoldable transverse to the longitudinal direction of the missile,
said wings and said propeller being automatically detachable in flight after launching, and
a container for storing as well as transporting and launching the missile when the wings as well as said tail assembly and said propeller are folded in the longitudinal direction.

2. A drone missile system, comprising:
a missile having a target-seeking head,
a guidance system,
a self-propulsion and take-off system,
electronic means for storing individual mission data prior to the mission,
a pair of wings,
a tail assembly, and
a propeller,
said missile having a shape defining a longitudinal direction, means for allowing folding of said wings as well as said tail assembly and said propeller in the longitudinal direction of the missile and for automatically unfolding them transverse to the longitudinal direction of the missile, means for automatically detaching said wings and said propeller in flight after launching, and
a container for storing as well as transporting and launching

the missile when the wings as well as said tail assembly and said propeller are folded in the longitudinal direction.

4,296,895

FIN ERECTION MECHANISM


Ladislao Pazmany, San Diego, Calif., assignor to General Dynamics Corporation, San Diego, Calif.

Filed Jan. 15, 1979, Ser. No. 3,358

Int. Cl.³ F12B 15/16

U.S. Cl. 244—3.29

7 Claims



1. Fin erection mechanism for a missile having a longitudinally cylindrical body frame and a plurality of foldable fins for flight control comprising,
means longitudinally of said missile for connecting said fins to said missile,
means for bracing said fins toward an erect position,
means for interconnecting said fins together so that erection of all of said fins occurs simultaneously, said means for interconnecting comprises cable means for connecting one fin to fins located on each side of said one fin so that erection of said one fin influences the erection of said fins located on each side of one fin,
each fin of said fins is formed with a pulley means and wherein said cable means is attached and guided by said pulley means during the erection of said fins, and
control means disposed radially of said main axis of said missile for rotating said fins while erected for flight control and wherein said pulley means is located on the axis of rotation of said control means so that said cable means do not interfere with limited rotation of said fins.

4,296,896

VTOL AIRPLANE


Robert W. Kress, Lloyd Harbor, and Anthony C. Bacchi, Massapequa, both of N.Y., assignors to Grumman Aerospace Corporation, Bethpage, N.Y.

Filed Aug. 27, 1979, Ser. No. 70,260

Int. Cl.³ B64C 29/00, 15/12

U.S. Cl. 244—12.4

6 Claims



1. An airplane and powerplant combination comprising:
an airplane fuselage;
a stub wing mounted through said fuselage so as to be movable relative thereto;

fan jet means mounted to said stub wing at least one on either side of said fuselage;
 an airplane wing joined to said fuselage behind said stub wing with said fan jet means extending from ahead of said stub wing, under the airplane wing to a position adjacent the trailing edge of the airplane wing;
 a pivot arm means fixed to said stub wing;
 a means to connect said pivot arm means to said fuselage so as to rotate about an axis above said stub wing;
 an actuator connected between said fuselage and said stub wing to rotate said stub wing about the axis above said stub wing in positioning said fan jet means in a plane ahead of, and normal to the chord of the airplane wing whereby the thrust axis of said fan jet means may be rotated from a position parallel to a longitudinal axis of the fuselage to a position normal to said longitudinal axis of the fuselage.

4,296,897

BRAKE TORQUE LIMITER


Bernard B. Thompson, Bainbridge Island, Wash., assignor to The Boeing Company, Seattle, Wash.

Filed Jan. 22, 1979, Ser. No. 5,253

Int. Cl.³ B60T 8/12; B64C 25/46

U.S. Cl. 244—111

6 Claims



1. A torque responsive brake control apparatus for controlling a fluid pressure operated brake mechanism, operatively connected to a rotatable member, comprising: said fluid pressure operated brake mechanism being mounted substantially coaxial with said rotatable member and adapted for exerting a braking force to resist rotation of said rotatable member; a metering valve being manually operated for controlling a flow of pressurized fluid to said brake mechanism; a torque arm connected to said brake mechanism; said torque arm being angularly movable in response to brake reaction torque associated with said rotatable member when a braking force is applied to resist rotation of said rotatable member; said torque responsive control apparatus having a brake rod assembly attached at one end to said torque arm and attached at an opposite end to a fixed support; said brake rod assembly being arranged between said torque arm and said fixed support, for resisting angular displacement of said torque arm; a brake torque limiter incorporated within said brake rod assembly and being interposed in the fluid circuit between said manually operated metering valve and said brake mechanism, for controlling the supply and release of fluid under pressure to and from said brake mechanism; said brake torque limiter comprising a cylinder head section with a dual-diameter internally stepped cylinder section, and a matching dual-diameter stepped piston slidably mounted therein; said brake rod assembly comprising a first brake rod segment fixedly attached to said dual-diameter stepped piston, and a second brake rod segment fixedly attached to said dual-diameter stepped cylinder and head section of said brake torque limiter; a first chamber formed between said cylinder head section and said dual-diameter stepped piston; said brake torque limiter being constructed and arranged with respect to said brake rod assembly, so as to normally bias said brake rod assembly in one direction

of extending said brake rod assembly to its maximum overall length, by directing fluid pressure from said manually operated metering valve into said first chamber, and in the opposite direction for decreasing the overall length of said brake rod assembly by torque resulting from application of brakes; a control valve incorporated within said brake torque limiter and interposed in the fluid circuit through which fluid under pressure from said manually operated metering valve, is supplied to the brake mechanism; said control valve being normally in an open position, when said brake rod assembly is at its maximum overall length, for circulating fluid pressure from said metering valve through said control valve to said brake mechanism; said control valve being actuated to a closed position, when said brake rod assembly is decreased from its maximum overall length by predetermined excessive braking torque of said rotatable member, for blocking fluid flow between said brake mechanism and said manually operated metering valve, and for trapping metered fluid pressure between said brake torque limiter and said brake mechanism; a second chamber formed between said step sections of the dual-diameter piston and matching internal dual-diameter cylinder, for creating an expanding annulus volume in response to contraction of the overall length of said brake rod assembly, to receive hydraulic fluid trapped between said brake torque limiter and said brake mechanism, and thereby decrease the pressure of said trapped hydraulic fluid resulting in a decrease in the ratio of brake torque reaction relative to metered hydraulic pressure.

4,296,898

ANCHOR DEVICE FOR PROPELLER ROTATOR


Ronald S. Watson, P.O. Box 9599, San Diego, Calif. 92109
 Division of Ser. No. 863,984, Dec. 23, 1977, Pat. No. 4,131,249.

This application Dec. 21, 1978, Ser. No. 974,169

Int. Cl.³ B64F 1/12, 1/16; B64D 31/04

U.S. Cl. 244—115

14 Claims



1. An anchor means for placing between a forward portion of a propeller driven aircraft and a landing surface including, a section of said anchor means located behind the plane of a propeller of said aircraft and engaged by said aircraft to hold the anchor means fixedly against said landing surface, a pair of arms extending forwardly from said section held by said aircraft, said arms having forward ends for positioning substantially under a propeller, said forward ends of said arms having holding means for positioning substantially under the center mounting of the propeller adapted to be connected to said propeller.

4,296,899

APPARATUS AND METHOD FOR MANUFACTURING LAMINAR FLOW CONTROL AIRCRAFT STRUCTURE

Jack M. Isenberg, Bellevue, Wash., assignor to The Boeing Company, Seattle, Wash.

Continuation of Ser. No. 811,744, Jun. 30, 1977, Pat. No. 4,171,785. This application Feb. 26, 1979, Ser. No. 15,085

Int. Cl.³ B64C 3/26, 21/06


U.S. Cl. 244—207

6 Claims

1. A self-positioning slot assembly tape for defining a pas-

sageway for boundary layer air on an aircraft having a laminar flow control means comprising:

- a removable cover plate having an upper and a lower surface; and
- a pair of sidewall members each including an upper surface removably bonded to the lower surface of said cover plate with a first adhesive and spaced apart a predetermined



distance so as to form a continuous longitudinal slot of uniform width therebetween for passage of boundary layer air to said laminar flow control means, said removable cover plate providing means for maintaining a fixed spacing between said sidewalls and having sufficient transverse rigidity for maintaining a coplanar relationship between the respective upper surfaces of said sidewalls.

4,296,900

AIRFOIL CONSTRUCTION


Kenneth M. Krall, Arlington, Tex., assignor to Vought Corporation, Dallas, Tex.

Filed Apr. 23, 1979, Ser. No. 32,438

Int. Cl.³ B64C 3/48

U.S. Cl. 244—119

4 Claims



1. An airfoil construction, comprising:

- (a) upper and lower surface structure which connects leading and trailing edges so as to form a relatively thin profile which is adapted to foster high speed flight, with one portion of the upper surface structure being pivotable upward about a hinge line that coincides generally with the leading edge of the airfoil, for increasing the thickness of the airfoil, and the chordwise length of said pivotable portion being substantially less than the chord length;
- (b) a connecting section which forms part of the airfoil upper surface structure immediately aft of the pivotable portion, and said section being positionable for presenting a substantially continuous and rigid surface to the air moving over the upper surface structure during such times as the pivotable portion is being pivoted upward and downward, and the connecting section cooperating with the remainder of the airfoil upper surface when the connecting section is lowered to establish an elongated convex cross section for high speed flight, and the connecting section also cooperating with the remainder of the airfoil upper surface when the connecting section is fully raised to establish a compound curvature having both concave and convex portions for fostering low speed flight;
- (c) a rearwardly directed nozzle located adjacent the aft edge of the pivotable portion and oriented such that it can discharge a gaseous fluid over the connecting section;
- (d) a source of pressurized fluid adapted to be connected with said nozzle; and

- (e) control means for adjusting the discharge of fluid from said source over the connecting section.

4,296,901

TRANSPORTATION SYSTEMS

Francis C. Perrott, The Manor House, South Cerney, Cirencester, Gloucestershire, England


Filed Jan. 2, 1980, Ser. No. 109,182

Claims priority, application United Kingdom, Jan. 2, 1979, 00046/79; Apr. 27, 1979, 14658/79; Sep. 29, 1979, 33865/79

Int. Cl.³ B61L 3/00

U.S. Cl. 246—167 R

12 Claims



1. A transportation system comprising a track, driven vehicles movable along the track, and control means for generating control signals effectively defining a series of spaced control areas movable along the track, each control area being of such length as to be capable of accommodating a plurality of vehicles simultaneously, wherein each vehicle is provided with on-board detection means responsive to the control signals for maintaining the vehicle within the confines of a control area, and the control means includes vehicle closing means for sensing the presence of gaps between a plurality of vehicles confined within a single control area and for causing relative movement of said vehicle with respect to one another to close up the gaps.

4,296,902

BABY BOTTLE SUPPORT JIG


William G. Dachtler, 1021 Emory, Imperial Beach, Calif. 92032

Filed Sep. 10, 1979, Ser. No. 74,004

Int. Cl.³ A47D 15/00

U.S. Cl. 248—102

5 Claims



1. A baby bottle support jig comprising:

- (a) a soft strap to loop over the head and pass behind the neck of a baby in a reclining position;
- (b) a pair of substantially rigid support arms having ends lying alongside the opposite sides of the neck and being connected respectively to the ends of said strap, passing down in contact with the baby's chest, and extending to upper ends spaced from the baby's face and chest; and
- (c) a bottle-holding cradle mounted to the upper ends of said support arms, whereby a baby bottle with the nipple thereof in the baby's mouth can be supported at its upper portion in said cradle.

4,296,903

ACTUATOR BUTTON APPARATUS FOR ADJUSTABLE CHAIRS

Hans J. Edel, Minden, Fed. Rep. of Germany, assignor to Drabert Söhne Minden, Fed. Rep. of Germany


Filed Oct. 19, 1979, Ser. No. 86,610

Claims priority, application Fed. Rep. of Germany, Oct. 23, 1978, 7831578[U]

Int. Cl.³ F16M 11/00; A47C 3/22

U.S. Cl. 248—162.1

8 Claims



1. An actuator button apparatus for actuating a chair positioning linkage mounted for movement within a chair base housing, said apparatus comprising:

- an aperture in said housing;
- a linkage element mounted for movement within said housing;
- an actuator button moveable within said aperture, said button being slidably mounted on said linkage element and adapted for movement with said linkage element at least partially into said housing and then along said linkage element at an angle transverse to the initial direction of pressure exerted to move said button into said housing; and
- means located within said housing for releasably retaining said button after said button has been pressed into said housing and moved along said linkage element.

4,296,904

ELECTRICAL EQUIPMENT MOUNT


Marion R. Farmer, Germantown, Tenn., assignor to Aluma Form, Inc., Memphis, Tenn.

Filed Aug. 9, 1979, Ser. No. 65,076

Int. Cl.³ E04G 3/00

U.S. Cl. 248—218.4

9 Claims



1. An improved electrical equipment mount for holding transformers or related electrical equipment and for attachment to a utility pole, the mount being formed from components that interengage to provide enhanced structural support, comprising, a horizontally disposed crossarm, said crossarm fabricated having a channel member and including front and back surfaces and end edges, means for holding said crossarm to a utility pole, a bracket having a mounting pad connecting to each end of the crossarm, said bracket being mounted to the crossarm and disposed for orienting its held transformer towards the front, rear, or side of the equipment mount, each crossarm end being formed to accommodate the mounting of its associated bracket in its desired disposition, connectors securing with the front and back edges of each end of the crossarm for securing its respective bracket to the crossarm end, the connector securing with the back end edge of the crossarm including a first leg, said leg provided for abutting against the back surface of the crossarm and capable of being

secured thereto, an integral second leg extending angularly from the first leg of the connector, and said second leg securing with the bracket for retention of the same.

4,296,905

BUILDING SCAFFOLD SUPPORT


Charles R. Powell, 6729 N. Richmond Ave., Portland, Oreg. 97203

Continuation-in-part of Ser. No. 836,027, Sep. 23, 1977, abandoned. This application Jul. 26, 1978, Ser. No. 928,237

Int. Cl.³ A47G 29/02

U.S. Cl. 248—237

3 Claims



1. A scaffold support for buildings comprising
- (a) an elongated base member having front and rear end portions and arranged to lie on a top surface of a building with said front end portion projecting beyond a side of the building,
 - (b) means on said base member arranged to hold it down on a building,
 - (c) rigid plate means depending integrally from the front end of said base member,
 - (d) a rigid scaffold supporting arm having upper and lower ends,
 - (e) means on the lower end of said arm for connecting a scaffold thereto,
 - (f) pivot support means pivotally connecting the upper end of said arm to the lower end of said plate means,
 - (g) rigid extension means having upper and lower ends,
 - (h) the lower end of said extension means being secured integrally to said arm at a point downward from said pivot connection of said arm with said plate means,
 - (i) said extension means extending upwardly along a rearward side portion of said plate means,
 - (j) said rearward portion of said plate means having a pin receiving aperture above said base member and said extension means having a plurality of spaced pin receiving apertures,
 - (k) and cross pin means arranged for removable mounting in the apertures in said plate means and in said extension means to provide selected angular disposition of said arm relative to said base member.

4,296,906

DEVICE HAVING A BALANCED PIVOTABLE ARM

Matthijs Matthijse, Eindhoven, Netherlands, assignor to U.S. Philips Corporation, New York, N.Y.

Filed Sep. 20, 1979, Ser. No. 77,423

Claims priority, application Netherlands, Sep. 29, 1978, 7809850


Int. Cl.³ E04G 3/00

U.S. Cl. 248—280.1

4 Claims

1. A counterbalancing device comprising:
- a first axle (5);
 - an arm (1) pivotably affixed for rotation around the first axle in a first plane;
 - a second axle (9) disposed in the first plane perpendicular to the first axle;
 - means pivotably affixing the first axle and the arm for rota-

tion around the second axle so that the center of gravity of the arm is disposed on a first side of the second axle; a counterweight (23) disposed on a second side of the second axle opposite the center of gravity of the arm; and



transmission means which couple pivoting motion of the arm around the first axle to motion of the counterweight so that the counterweight moves in an approximately straight line in the first plane when the arm is rotated around the first axle.

4,296,907

SUPPORT ASSEMBLY FOR AN EXHAUST SYSTEM OF A MOTOR VEHICLE

Takashi Ishida, Yokohama, and Mamoru Tanaka, Yokosuka, both of Japan, assignors to Nissan Motor Company, Limited, Yokohama, Japan


Filed Oct. 29, 1979, Ser. No. 88,755

Claims priority, application Japan, Nov. 14, 1978, 53-156954[U]

Int. Cl.³ F16M 13/00

U.S. Cl. 248—573

2 Claims



1. A support assembly for an exhaust system of a motor vehicle, comprising:
- (a) a first U-shaped bracket adapted to be mounted at one side to the body of the motor vehicle and provided with two substantially parallel spaced side walls in such a manner that the open side of said U-shaped bracket faces upwardly;
 - (b) a second bracket of substantially strip construction adapted for mounting at one end portion to the exhaust system and inserted at a second end portion between, and substantially parallel to, the two side walls of said U-shaped bracket in such a manner that the surface of said strip is normal to the bottom surface of the U-shaped bracket so as to form two spaces between the second end portion of the second bracket and each of the two side walls of the first bracket;
 - (c) two vibration absorbing members being inserted into the two spaces, the two members being respectively joined firmly to the second end portion of the second bracket and the two parallel side walls of the first bracket to absorb lateral and vertical vibrations of the second bracket;
 - (d) a stop extending from an upper portion of one of said two side walls toward the other side wall so as to prevent the movement of the second end portion of the second bracket beyond the stop; and
 - (e) a third vibration absorbing member disposed on one of the facing surfaces of said stop and said second end portion of said second bracket in such a manner that there is an appropriate spacing between the third vibration ab-

sorbing member and the other of said stop and said second end portion of said second bracket.

4,296,908

MOLD FOR INTEGRAL BASE FOR CASTING CERAMIC MATERIAL IN THE FORM OF A SLIP

Giuseppe Lippa, Brescia, Italy, assignor to American Standard Inc., New York, N.Y.


Filed Jul. 28, 1980, Ser. No. 172,792

Claims priority, application Italy, Aug. 8, 1979, 46864 A/79

Int. Cl.³ B29C 1/14; B28C 7/06, 7/34, 7/16

U.S. Cl. 249—58

15 Claims



1. A mold for casting ceramic material in slip form, which comprises a lower mold part resting on a support; at least two further mold parts adapted to be assembled with said lower mold part to define, in combination therewith, a cavity for casting and molding the article to be cast in the mold, said further mold parts including a removable ring and shelf portions on lateral mold members adapted to be positioned on said lower mold part to define the base of said cavity; said further mold parts being removable from said lower mold part after completion of the cast article so that the latter remains positioned on said lower part of the mold; said lower part bearing said ring to support said cast article on its lower rim in relation to its casting position, said ring being removably positioned on the inside of said lower part of the mold, and being supported by the lower part of the mold below said shelf portions so that, after casting, when the further mold parts have been removed from the lower mold part and the molded article, said ring may be lifted to contact said molded article so as to lift it out from the lower mold part.

4,296,909

APPARATUS FOR FORMING RECESS AROUND A PICKUP BOLT OF A CONCRETE BODY

Ernst Haeussler, Grashofstr. 47, 4300 Essen-Bredene, Fed. Rep. of Germany

Filed Sep. 3, 1980, Ser. No. 183,925

Claims priority, application Fed. Rep. of Germany, Sep. 5, 1979, 2935825


Int. Cl.³ B28B 7/04, 7/30, 7/16

U.S. Cl. 249—94

10 Claims

1. An apparatus for forming in a concrete body during casting thereof a recess around the head of a pickup bolt having a stem imbedded in said body, said recess having a part-spherical inner surface, said apparatus comprising:
- a pair of like elements each having an outer surface complementary to a respective half of said inner surface defined by a line bisecting said inner surface at said stem, said elements being formed with respective halves of a seat

complementarily surrounding said bolt head and stem in said recess;



a bridge provided with a pair of pivots defining pivot axes parallel to said line, said elements being pivoted on said bridge element at said pivot axes; and
a manipulating member connected to said bridge.

4,296,910

HYDRAULICALLY CONTROLLED SAFETY VALVE

Jean L. Gratzmuller, 66 Boulevard Maurice Barres, 92200 Neuilly sur Seine, France


Filed Aug. 24, 1978, Ser. No. 936,510

Claims priority, application France, Aug. 29, 1977, 77 26157; Jul. 12, 1978, 78 20767

Int. Cl.³ F16K 31/12, 31/122

U.S. Cl. 251-28

11 Claims



1. In a safety valve control installation comprising:
a control station having a source of fluid under pressure;
a safety valve situated at a receiving station remote from said control station, said safety valve having a closure member;
a fluid operated jack attached to said closure member for actuating said closure member in an opening direction on pressurization of said jack;
resilient means acting in opposition to said jack for returning said closure member to the closed position when said jack is under low pressure;
a single small-section fluid flow line connecting the source of fluid under pressure at said control station to said receiving station and comprising, at said control station, a control valve permitting to selectively connect said line to said source or to a discharge means;
a fluid energy accumulator at said receiving station; and
a pressure-controlled feed/bleed relay connected between said accumulator and said actuating jack and having a control input;
the improvement comprising manostat means sensitive to the pressure in said line for successively actuating individual valve means which regulate, in response solely to said line pressure, a unidirectional communication of said line pressure with said accumulator, a closing of a communication of said relay control input with an outlet through one of said valve means in response to increased line pressure detected by said manostat means, and a communication of said line pressure through one of said valve means to said

relay control input and unidirectionally to said accumulator in response to a further increase in line pressure detected by said monostat means.

4,296,911

HYDRAULIC CONTROLLED SONIC INDUCTION SYSTEM


Alfonso S. Escobosa, 2034 Brittany Pl., Placentia, Calif. 92670

Filed Feb. 7, 1979, Ser. No. 10,001

Int. Cl.³ F16V 31/122; F01L 1/34, 9/02

U.S. Cl. 251-57

4 Claims



1. A hydraulic controlled sonic induction system including a hydraulic actuation system adapted to provide a prescribed lift profile to engine intake valves, said actuation system receives hydraulic fluid for effecting the opening of each of the said intake valves by a cam follower piston, said hydraulic fluid conveyed to an actuator/port unit by means of a valve-opening control line, said actuator/port unit containing a single-ended, doubleacting valve actuator including, a piston, an actuator, an actuator cylinder, a poppet valve, a valve seat and a valve port, the shaft of said actuator being connected with the stem of the valve, the top face of said actuator piston being connected with the face of said cam follower piston by means of said valve-opening control line, the bottom annular piston face of said actuator piston being connected to a valve-closing circuit, said valve-closing circuit consisting of a first fluid compliance, a third fluid compliance, a check valve allowing the passage of fluid from the first fluid compliance to the third fluid compliance, and a variable pressure source connected to said first compliance, the bottom annular face of the actuator piston being connected to the third fluid compliance of the valve-closing circuit by means of a valve-closing control line, said variable pressure source comprising a hydraulic fluid charging pump, a pressure release valve, and a flow restricting orifice being in series with each other and being connected in shunt with the charging pump, the pressure relief fluid of said pressure release valve is returned to a oil sump, through said flow restricting orifice said cam follower piston, said actuator piston, and said actuator shaft define sliding surface clearances within the interior of said cylinder and forming finite leakage seals therewith, the actuator shaft finite leakage seal, in turn, divided into interior and exterior seals with leakage from the interior seal returned to the oil sump, a retractable elastomeric seal in series with the finite leakage interior shaft seal for the purpose of positively containing the interior (control) fluid and for latching each of the intake valves at some time during the engine turn-off period, another retractable elastomeric seal in series with the finite leakage seal of the cam follower piston again for the purpose of holding the interior fluid during the engine turn-off period, said hydraulic controlled induction system further includes lift control members for varying the opening of said intake valves, said control members comprising (1) a bypass piston contained in each of said intake valve actuator/port units and connected therein in parallel with the actuator piston through the valve-opening control line to a first bypass piston chamber and through the valve-closing control line to a second bypass piston chamber, (2) a flow distribution orifice connected to each of the valve-opening control lines, (3) a second fluid compliance means being connected to the flow distribution orifices that lead to the valve-opening control

lines, and (4) a three-way pressure control valve, a supply pressure port thereof being connected to said first fluid compliance means, a return port thereof being connected to the oil sump and a control pressure port thereof being connected to said second fluid compliance means, the two sliding surface clearances of said bypass piston form two finite leakage seals with leakage from the finite leakage seal of the smaller diameter being returned to the oil sump, a retractable elastomeric seal in series with the smaller diameter finite leakage seal for the purpose of positively holding the interior (control) fluid and latching the bypass piston corresponding to each of the intake valves at sometime during the engine turn-off period.

4,296,912

MAGNETICALLY ACTUATED METERING VALVE


Robert F. Ruyak, Erie, Pa., assignor to Autoclave Engineers, Inc., Erie, Pa.

Filed Aug. 30, 1979, Ser. No. 71,014

Int. Cl.³ F16K 31/08

U.S. Cl. 251-65

1 Claim



1. A valve suitable for metering fluids pressurized in excess of 2000 psi comprising a pressurizable valve body defining a metering passage, a first fluid passage in communication with one of the metering passage and a second fluid passage in communication with the other end of the metering passage and a valve actuator passage extending away from the metering passage,

a nonmagnetic elongate cylindrical tubular pressurizable bonnet having an extending axis passing through the metering passage and in direct fluid communication with the passages in said valve body,
a cylindrical holder coaxial with and surrounding said tubular bonnet, said holder mounted rotatably thereto, said holder carrying rare earth cobalt magnets defining an even number of north and south poles,
a driven magnet assembly carrying rare earth cobalt magnets defining an even number of north and south poles rotatably supported in the bonnet substantially coaxial with said bonnet by thrust bearings to resist axial movement of the driven magnet assembly,
a valve stem substantially coaxial with said bonnet journaled for free axial movement in the valve actuator passage threadably engaging the driven magnet assembly,
a tapered metering element fixed to said valve stem which when moved axially enlarges or decreases the minimum area of the metering passage through which flow may take place, means for keying the valve stem to prevent rotation thereof,
whereby rotation of said driven magnet assembly in one direction concomitantly raises the valve stem and rotation

of said driven magnet assembly in the other direction lowers said valve stem.

4,296,913

BALL VALVE

Ernst H. J. Hoyer, Lohwurt 11, D-2000 Hamburg 57, Fed. Rep. of Germany


Filed Jun. 19, 1979, Ser. No. 49,882

Claims priority, application Fed. Rep. of Germany, Jun. 21, 1978, 2827720

Int. Cl.³ F16K 31/44

U.S. Cl. 251-76

11 Claims



1. A ball valve comprising:
a housing having inlet and outlet openings for a flow medium;
a perforated ball floatingly supported in a pair of rings in the housing for rotation about first and second rotary axes displaced from each other and extending through the center of the ball, said ball being rotatable about said first rotary axis to a first position in which the ball connects the inlet and outlet openings and to a second position in which the ball interrupts the inlet and outlet openings; and
an actuator rotatable with the ball and in engagement therewith, said ball and actuator being so formed that their coaction is capable of imparting an initial movement to the ball about said second rotary axis for overcoming adhesion friction of the ball and thereafter imparts a rotation to the ball about said first rotary axis.

4,296,914

FULL FLOW BREAKAWAY COUPLING


Alan R. Allread, Jackson, Mich., assignor to Aeroquip Corporation, Jackson, Mich.

Filed Dec. 26, 1979, Ser. No. 107,152

Int. Cl.³ F16L 37/22, 37/28

U.S. Cl. 251-149.2

6 Claims



1. A breakaway fluid coupling comprising, in combination, male and female body parts each having an axis, an axially extending passage, conduit attachment means in communication with the associated passage, a valve within the associated passage adapted to close upon the parts being uncoupled, a tapered metering element fixed to said valve stem which when moved axially enlarges or decreases the minimum area of the metering passage through which flow may take place, means for keying the valve stem to prevent rotation thereof, whereby rotation of said driven magnet assembly in one direction concomitantly raises the valve stem and rotation of said driven magnet assembly in the other direction lowers said valve stem.

connection end, and latch means adapted to engage with the latch means defined on the other part for maintaining said parts in coupled intercommunication, said latch means defined on one part including a radially extending abutment surface facing said conduit attachment means of the associated part, a detent support axially slidably mounted on the other part between latched and release positions thereon, biasing means interposed between said other part and said detent support axially biasing said support toward said latched position, at least one radially displaceable detent mounted on said detent support adapted to engage said abutment surface upon said parts being coupled maintaining said parts coupled, detent positioning means defined on said other part having a first axial portion engaging said detent when said detent support is in said latched position maintaining said detent in engagement with said abutment surface and a second axial portion permitting radial displacement of said detent when said detent support is in said release position to disengage said detent and abutment surface and permit said parts to uncouple solely upon tension forces within said body parts compressing said biasing means to permit alignment of said second axial portion with said detent, and means supporting said detent positioning means on said other part having a normal condition restraining said detent positioning means against axial movement toward the associated connection end and permitting manual axial displacement away from said connection end whereby said detent positioning means may be manually axially displaced to disengage said detent and abutment surface.


4,296,915

ECCENTRIC ROTARY DISK VALVE WITH ELASTIC METAL SEAL

Hans D. Baumann, 32 Pine St., Rye, N.H. 03870
Filed Aug. 21, 1980, Ser. No. 179,944
Int. Cl.³ F16K 1/226

U.S. Cl. 251-174

5 Claims



1. Eccentric rotary disk valve for tight shut-off purposes comprising:
 - a. tubular housing;
 - b. one inlet and one outlet formed in said housing, inlet and outlet ends adapted to be coupled to a pipeline;
 - c. a straight cylindrical passage formed in said housing towards a stop shoulder, forming a reduced cross section at that point;
 - d. a ring shaped seal retainer removably and adjustably placed within the straight cylindrical passage having an inner bore on an axis which is parallel to but offset from that of the exterior diameter of the seal retainer;
 - e. a shaft located perpendicular to and offset from the longitudinal axis of the tubular housing and being retained on either end by the outer walls of said housing;
 - f. an eccentric rotating disk tiltingly engaged with said shaft and within the reduced cross section of said housing, said disk having an annular continuous, partially spherical periphery forming a seating surface;
 - g. a flexible metal seal ring having a generally U-shaped cross-sectional configuration when viewed in the circum-

ferential direction, wherein the outer straight portion of said U-shaped configuration is engaged within the inner bore of said seal retainer and suitably fastened to the same at its terminating end, while the inner straight portion of said U-shaped configuration forms a central circular seating bore to engage the eccentric disk in the closed valve position, the bottom portion of said U-shaped configuration facing said disk and the straight portions of said U-shaped configuration being generally parallel to said longitudinal axis of said tubular housing.


4,296,916

SUBMERSIBLE PUMP PULLER

M. Pearson Jewett, P.O. Box 442, Rockland, Me. 04841
Filed Nov. 26, 1979, Ser. No. 97,526
Int. Cl.³ B66D 3/00

U.S. Cl. 254-380

2 Claims



1. A device for pulling a submersible pump from a well casing in which it is suspended by a cable, said device comprising:
 - a pair of rails, one of which is longer than the other;
 - a threaded bolt, spacer and wing-nut assembly connecting the upper end of the shorter rail to the longer rail at a point spaced below the upper end of the latter so that said rails are adjustably held in parallel spaced relation with portions of the longer rail protruding both above and below the corresponding ends of the shorter rail;
 - a second threaded bolt and wing-nut assembly interconnecting said rails at a location spaced both from said first assembly and from the lower end of said shorter rail, and a winch mounted on the upwardly protruding portion of said longer rail,
 whereby said device may be clamped to the rim of a well casing by tightening said wing-nut assemblies with said longer leg extending inside the casing and a portion of said shorter leg extending downwardly outside said casing so that said winch is suspended over the casing in position to pull a submerged pump by means of said cable.

4,296,917

CONTOURED CABLE ROLLER


Ralph R. Day, Aurora, and B. James Wulff, Montgomery, both of Ill., assignors to Caterpillar Tractor Co., Peoria, Ill.
Filed Apr. 3, 1980, Ser. No. 137,068
Int. Cl.³ B66D 1/36

U.S. Cl. 254-400

14 Claims

1. A fairlead (26) for a log skidder (10) having a power winch (229, said fairlead (26) having a pair of vertically oriented, spaced apart side rollers (44,46) and a main guide roller (54) extending transverse to said side rollers (44,46), said main guide roller (54) having a pair of side portions (62,62) and a central portion (66) intermediate said side portions (62,62), a shoulder (68) formed on each of said side portions (62,62), each shoulder (68) having a convex section (72) and a concave

section (76) merging into each other and extending toward the central portion (66) of said main guide roller (54), said concave section (76) lying tangent to said central portion (66), said main guide roller (54) being of a construction sufficient for urging a



cable (32), passing through said fairlead (26) and in contact with one of said side rollers (44,46) from the adjacent shoulder (68) toward the central portion (66) of said main guide roller (54).

4,296,918

ANIMAL PEN POST

Werner Hölscher, Emsbüren, Fed. Rep. of Germany, assignor to Hölscher & Leuschner GmbH & Co., Emsbüren, Fed. Rep. of Germany

Filed May 6, 1980, Ser. No. 147,003

Claims priority, application Fed. Rep. of Germany, May 15, 1979, 2919414; May 15, 1979, 7913963[U]
Int. Cl.³ E04H 17/14

U.S. Cl. 256-68

2 Claims



1. A post for an animal pen installed in a livestock shed or the like having at least two outwardly facing longitudinally extending surfaces which are adjacent to one another and which extend generally in planes disposed at right angles with respect to one another, the post being made in one piece and comprising semi-cylindrically shaped recesses in each of said longitudinal surfaces for receiving horizontal rigid tubular rails, said semi-cylindrical recesses having a diameter corresponding to the diameter of said tubular rails such that said semi-cylindrical portions of said tubular rails, said recesses extending transversely of said longitudinal extending surfaces and being open at both ends, said recesses being disposed in said surfaces in pairs with one recess of each pair being in one of said longitudinal surfaces and the other of said pair being in the other longitudinal surface and with the spacing between said pairs de-

creasing toward the bottom of said post, said recesses being offset in height with respect to one another by at least the diameter of said recesses so that a tubular rail seated in one recess of a pair of recesses will be offset from the tubular rail seated in the other recess of said pair a distance in height at least equal to the diameter of said semi-cylindrical recesses, and for each recess at least one securing hole passing through the post for receiving a securing element for securing the tubular rail in its seated position in its respective semi-cylindrical recess in said pole, thereby providing a highly rigid animal pen.

4,296,919

APPARATUS FOR CONTINUOUSLY PRODUCING A HIGH STRENGTH DUAL-PHASE STEEL STRIP OR SHEET


Koichi Sakurai, Kitakyusyu; Takashi Furukawa, Machidashi; Hiroshi Takechi, Kisarazushi, and Munetsugu Matsuo, Kawasaki, all of Japan, assignors to Nippon Steel Corporation, Tokyo, Japan

Filed Aug. 13, 1980, Ser. No. 178,015

Int. Cl.³ C21D 9/56

U.S. Cl. 266-111

3 Claims



1. An apparatus for continuously producing a high strength dual-phase steel strip or sheet having a metallurgical composition which produces a dual-phase structure composed of ferrite grains and a low temperature transformed phase when rapidly cooled from the ($\alpha + \gamma$) temperature range or from the γ temperature range, which apparatus comprises a vertical type continuous heat treatment furnace having a heating zone, a soaking zone and a cooling zone, said cooling zone having an upper hearth roll group, a lower hearth roll group and means for cooling the strip at a rate in the range between 1° and 300° C./sec. for retaining the austenite, the hearth rolls of each hearth roll group being positioned for guiding the strip coming from the soaking zone up and down and alternatively around the upper hearth rolls and the lower hearth rolls from the inlet end to the outlet end of the cooling zone, and the hearth roll at the position where the strip is subjected to straining and begins to work harden as a result of the bending and the subsequent hearth rolls having a diameter D in millimeters according to the formula which is for the condition where the strip temperature is greater than 200° C.:

$$\frac{t}{D} + \beta \cdot T \cdot \log(CR) \cdot \frac{1}{100} \leq \epsilon_{WH}$$

Wherein;

t=Maximum strip thickness in millimeters;

ϵ_{WH} =0.2% (Strain at which the retained austenite starts to undergo strain induced transformation into martensite and the strip begins to work harden);

β =Linear thermal expansion coefficient (12×10^{-6});

T=Temperature at which the strip is subjected to cooling, in degrees C;

CR=Cooling rate of the strip in degrees/second. whereby the strain induced phase transformation of the retained austenite and consequently the work hardening of the strip when it is passed around the hearth rolls is avoided.

4,296,920

MOLTEN METAL TREATMENT

Kirk D. Miller, Rexdale; John B. Flood, Willowdale; George Dimou, Toronto; Frederick E. Kara, Islington, and Richard W. Amos, Etobicoke, all of Canada, assignors to Canron Inc., Montreal, Canada


Division of Ser. No. 806,094, Jan. 13, 1977, Pat. No. 4,199,353.

This application Jan. 23, 1980, Ser. No. 114,726

Claims priority, application Canada, Jan. 18, 1977, 269973

Int. Cl.³ C21C 7/00

U.S. Cl. 266—216



2. An apparatus, as defined in claim 1, including, a mounting device for a plunging rod of the type described, comprising, an adapter having a base plate provided with a socket for receiving the end of an elevating rod extending upwards therefrom, a boss extending downwards from said plate and having a recess for receiving a connector from the rod, a bracket slidably seated on the base plate and having a fixed connection to the adapter, and means for clamping the plate and bracket together to prevent their relative movement.

4,296,921

LANCE PIPE FOR REFINING AND METHOD OF MAKING THE SAME


Yoshihiro Hayashi, Ohtsu, Japan, assignor to Aikoh Co., Ltd., Tokyo, Japan

Filed Aug. 2, 1979, Ser. No. 63,121

Claims priority, application Japan, Aug. 28, 1978, 53-104745; Oct. 13, 1978, 53-125163

Int. Cl.³ C21B 7/16

U.S. Cl. 266—270



1. A method of producing a heat-resistant lance pipe which comprises:

- providing a hollow refractory tube, and
- applying to at least part of the outer surface thereof a first layer of an impregnated fibrous refractory material, with said fiber being based on alumina or silica and having a diameter ranging from 0.5 to 15.0 mm, said fibers being impregnated with a mixture consisting of 40-90% by weight of a refractory aggregate having a particle size of less than -10 mesh which contains in excess of 15% by

weight of particles having a particle size of -200 mesh and in excess of 15% by weight of particles having a particle size of 28-200 mesh, and from 10-50% by weight of a refractory binder which includes at least one material from the group consisting of silica sol including 5-40% by weight of solid parts, hydrolyzed ethyl silicate and fire clay suspension.

4,296,922

BENCH CLAMP DEVICE


Lindsay T. McGrath, 89 Sydney St., Muswellbrook, New South Wales, and Gilbert T. McGrath, 25 Mulcare Crescent, Churchill, Victoria, both of Australia

Filed May 19, 1980, Ser. No. 151,399

Int. Cl.³ B25B 1/14

U.S. Cl. 269—211

8 Claims



1. A tension clamp device which comprises, in combination, a movable jaw co-extensive with an elongated adjusting arm, a hollow housing through which said adjusting arm is adapted to pass freely, said hollow housing being adapted to be mounted on a fixed base and having a main jaw integral therewith, a tension lever pivotally attached to and between two spaced, parallel side cheeks of said housing, a secondary lever pivotally fastened at one end thereof to said tension lever, the other end of said secondary lever being constrained with respect to said housing by means of a pin in sliding relationship with respect to a pair of registering travelling slots, each formed within a respective one of said side cheeks of said housing, said pin being adapted to engage selectively one of a plurality of notches formed in a rack extending longitudinally of said adjusting arm, and said pair of travelling slots being adapted to guide sliding movement of said pin therealong from a first position wherein said pin is free of engagement with said notches to a second position wherein said pin engages said one of said notches, whereby pivotal movement of said tension lever with respect to said housing initially causes said pin to slide along said pair of travelling slots from said first position to said second position whereby free sliding motion of said adjusting arm within said housing is prevented by the engagement of said pin in said notch, and then causes said housing to lock securely with respect to said adjusting arm by an over-centre action to grip firmly within said jaws any work-piece located therebetween, each of said pair of travelling slots being arcuate at the end thereof corresponding to said first position of said pin.

4,296,923

PLAYGROUND SWING

Paul W. Ahrens, Grinnell, Iowa, assignor to Miracle Recreation Equipment Company, Grinnell, Iowa

Filed Oct. 11, 1979, Ser. No. 84,053


Int. Cl.³ A63G 9/00

U.S. Cl. 272—85

1 Claim

1. A playground swing comprising: an elevated support; a flexible line having upper and lower ends, and being connected at its upper end to said support;

an integral hollow plastic body including a seat unit and an upstanding stem, wherein said seat unit is substantially rigid, substantially circular in cross-section, and has a cylindrical seat portion with a flat top section including rounded upper and lower edges, and an outer convex peripheral surface, and being of a depth sufficient to allow the seat portion to be comfortably gripped between the user's thighs and the back of the user's legs to stabilize the user on said body during the operation of said swing, and wherein said upstanding stem is substantially rigid, fixably connected to and substantially centrally disposed on said seat portion cylindrical along its substantial length and flaring outwardly into said seat portion at its lower end, and outwardly into an enlarged portion at its upper end, and being substantially longer than the maximum dimensions of said seat portion, whereby a hand hold is provided for a user seated on said seat portion;



a pressure plate having a centrally disposed aperture and a nut means; and a rod having an eyelet at one end and engaging the aperture and nut means at the other end, and extending from beyond the bottom of said seat portion through and beyond the length of said stem, and wherein said eyelet is connected to the lower end of said flexible line and said other end extends through the aperture of said pressure plate into engagement with said nut means to press said plate against the outer bottom surface of said seat portion, whereby a user pulls on said stem in a pumping action to initiate the swinging motion of the swing with said stem pivoting about a horizontal axis through said eyelet, thereby moving the swing out of the plane of the flexible line and at an angle to the vertical plane.

4,296,924

TORSION EXERCISE APPARATUS

Alfred B. Anzaldua; David A. Anzaldua, and Benjamin R. Sturgeon, all of Peoria, Ill., assignors to Health Innovations, Inc., Peoria, Ill.

Filed Aug. 4, 1980, Ser. No. 175,147


Int. Cl.³ A63B 21/06

U.S. Cl. 272—117

12 Claims

1. Exercise apparatus comprising: a vertically oriented framework; wheel means carried by said framework and rotatable about a vertical axis; adjustable resistance means connected to said wheel means and adapted to resist rotation thereof; and a pair of horizontally spaced handle means connected to said wheel means for simultaneous rotation in the same direction, each said handle means including a handle, said handles being spaced apart sufficiently to accommodate a user therebetween and permit the user to grip both

handles simultaneously with his hands and, by rotating the handles and his torso about the wheel's vertical axis, rotate



said wheel means in either a clockwise or counterclockwise direction and work against said resistance means.

4,296,925

JUMP TRAINER


William G. Alston, 151-A Treestop Dr., Fayetteville, N.C. 28301

Filed Jun. 23, 1980, Ser. No. 161,746

Int. Cl.³ A63B 5/16, 69/00

U.S. Cl. 273—1.5 A

12 Claims



1. A jump training device comprising: a pair of beat boards disposed back to back; means for supporting said beat boards a predetermined distance from a playing surface; and a game type ball suspended adjacent to and below said beat boards whereby an improved jump training device is provided.

4,296,926

RED LIGHT - GREEN LIGHT GAME

Gordon H. Buck, Torrance, and Martha K. Hardwick, Redondo Beach, both of Calif., assignors to Mattel, Inc., Hawthorne, Calif.

Filed Dec. 26, 1979, Ser. No. 106,715


Int. Cl.³ A63F 9/14

U.S. Cl. 273—86 R

15 Claims

1. An electronic game comprising: a first array of discrete, illuminatable display elements for displaying the position of a first player's piece indicium, a second array of discrete, illuminatable display elements for displaying the position of a second player's piece indicium, a stop/go indicator having first and second states, a first manual input, comprising a first momentary contact switch, inputting to a position control means,

a second manual input, comprising a momentary contact switch, inputting to said position control means, stop and go control means, outputting to said stop/go indicator alternately establishing the first and second states of said indicator, for controlling said position control means, said position control means being for moving the first player's piece indicium in one direction by sequentially turning on one display element and turning off another in response to each contact of said first momentary contact switch in said first array when the first manual input is



operated during the first state of said indicator and in the opposite direction in said first array when the first manual input is operated during the second state of said indicator and moving the second player's piece indicium in one direction by sequentially turning on one display element and turning off another in response to each contact of said second momentary contact switch in said second array when the second manual input is operated during the first state of said indicator and in the opposite direction in said second array when the second manual input is operated during the second state of said indicator.

4,296,927

GAME BOARD AND CARDS

Russell E. Larsen, 1517 E. Garfield, Apt. #71, Glendale, Calif. 91205


Filed Oct. 30, 1978, Ser. No. 956,022

The portion of the term of this patent subsequent to Jul. 8, 1997, has been disclaimed.

Int. Cl.³ A63F 3/00

U.S. Cl. 273-248

8 Claims



1. A game apparatus including:

- a game board with a plurality of separate movement zones for each player, each zone having multiple locations for movement of markers positioned therein;
- markers for placement in each respective zone; and
- a plurality of cards defining movement instructions, each card having at least two symbols representing separate but concurrent move options for a player having possession of said card, each of said symbols having corresponding identity relationship with a specific movement zone based on total numbers of columns representing directions of movement within the given movement zone to limit marker movement within said zone.

4,296,928

INTERPLANETARY CONFLICT GAME


Howard H. Nick, Darren Rd., La Grangeville, N.Y. 12540

Filed Dec. 5, 1979, Ser. No. 100,463

Int. Cl.³ A63F 3/00, 3/04

U.S. Cl. 273-262

7 Claims



1. An interplanetary conflict game comprising:

- a gameboard having first indicia thereon symbolic of the solar system including planets, stars, and travel routes between the stars, said gameboard further including second indicia to determine the distance between said stars,
- a plurality of rocket markers for each player to be manually moved by a player between said stars and planets and to fire at an opponent player's rocket or to capture an opponent's planet,
- a group of colored rating spheres, each having an external curved surface, a conical-shaped passageway extending along a center line through a rating sphere, and a slot extending the length of the center line for easy removal of the rating sphere from a rocket marker to which it is attached in order to indicate the numerical rating of the rocket markers,
- a firing chart for determining a firing range between a player's rocket and an opponent's rocket,
- a promotion chart for determining the proper rating sphere for said rocket markers,
- a legend chart for indicating the number of moves for a rocket marker as indicated by its rating sphere,
- a group of firing cards to be drawn by a player desiring to fire his rocket at a rocket belonging to an opponent player instructing the player as to whether the rocket hits or misses.

4,296,929

ELECTRIC EYE ACTUATED GUN ARCADE

Burton C. Meyer, Downers Grove; Gunars Licitis, Lombard, and Derek A. Brand, Naperville, all of Ill., assignors to Marvin Glass & Associates, Chicago, Ill.

Filed Feb. 19, 1976, Ser. No. 659,216

Int. Cl.³ F41J 5/02


U.S. Cl. 273-310

11 Claims

1. A target shooting apparatus, comprising:

- a plurality of target devices;
- a frame for removably supporting said plurality of target devices;
- a plurality of actuable target impellers mounted on the frame and each associated with one of said targets to knock the respective target off of said frame when the respective target impeller is actuated;
- circuit means including a photodetector remotely disposed

from the targets providing an output signal upon the sensing of a properly aimed light beam; control means including a power supply and drive means associated with said circuit means and one of said target impellers for actuation thereof in response to receipt of the output signal from said circuit means, said circuit means and control means being movably mounted on a carriage for movement from a first target impeller serially to a



second target impeller after actuation of said first target impeller whereupon each of said targets may be sequentially knocked off of said frame upon sequential actuation of the respective target impellers; and a selectively operable aiming device including a light source therein for directing a beam of light therefrom, said light source being arranged so as to direct the light beam toward the photodetector when the aiming device is properly aimed toward the respective target.

4,296,930

TV GAME APPARATUS

Jeffrey E. Frederiksen, Milwaukee, Wis., assignor to Bally Manufacturing Corporation, Chicago, Ill.

Continuation of Ser. No. 635,406, Nov. 26, 1975, abandoned.



This application Jul. 5, 1977, Ser. No. 812,662

Int. Cl.³ A63F 9/22

U.S. Cl. 273-313

26 Claims

2. A player-operated game apparatus for use with a display screen means having an intensity control means for varying the intensities of picture elements for the presentation of movable symbols on a screen, said apparatus comprising player-operated means including input elements adapted to be operated by a player and signal means actuable by said input elements for affecting the display of symbols and initiation interaction of the player with the symbols on the screen; random access memory for storing in a digital form a set of digital bits representing the intensities necessary for generating a display on said screen and locating the symbols within the display; display controller means for addressing said random access memory and reading the set of bits in the random access memory in time-spaced read periods separated by reading idle periods, in each of which read periods one or more bits associated with a desired display are read from the random access memory, said display controller means being adapted for connection to said intensity control means of the display means to transmit the bits to said intensity control means to present the desired display stored in said random access memory; a microprocessor; program means; communicating port means for connecting the signal means of the player-operated means to the microprocessor, said microprocessor having means for accessing said program means and means for reading from and writing to said random access memory to represent symbols in response to said signal means and said program means whereby the microprocessor revises and controls interaction of the symbols within the display; control means operatively cou-



processing means for transforming the symbol signals to produce transformed symbol signals so that a symbol represented by the transformed symbol signals is different than a symbol represented by the symbol signals relative to the display, and for providing smooth appearing continuous movement of the symbols on the display.

4,296,931

PROJECTING-TYPE SHOOTING GAME APPARATUS
Gunpei Yokoi, Kyoto, Japan, assignor to Nintendo Co., Ltd., Kyoto, Japan

Filed Mar. 26, 1979, Ser. No. 23,780

Claims priority, application Japan, Apr. 20, 1978, 53-047325; Apr. 20, 1978, 53-047326; Apr. 29, 1978, 53-051869; Apr. 29, 1978, 53-059077[U]


Int. Cl.³ A63F 9/02

U.S. Cl. 273-316

5 Claims

- A projector-type shooting game apparatus comprising:
 - a screen;
 - a housing having a longitudinal axis and for projecting a target image onto said screen;
 - a mirror rotatably coupled to said housing such that said mirror is rotatable in first and second axes mutually perpendicular to each other and both of said first and second axes being perpendicular to said longitudinal axis;
 - a means for changing an angle of said mirror about said first axis;

a means for changing an angle of said mirror about said second axis;
a driving means for driving both said angle changing means;
a lever manually movable about third and fourth axes;



a means for mechanically coupling said lever's movement to both said means for changing the angle of said mirror, whereby the motion of said mirror is effected by said driving means and by a player's manual operation of said lever.

4,296,932


SEALING OF LEAKS IN TANKS AND THE LIKE

Johannes H. Grobler, 668 Main Pretoria Rd., Wynberg, Johannesburg, South Africa

Filed Sep. 13, 1979, Ser. No. 74,858

Int. Cl.³ F16J 15/02

U.S. Cl. 277-1



1. The method of sealing a fluid passage in a body comprising forming in the body a second passage which intersects the fluid passage and introducing through the second passage to the fluid passage a composition comprising a rubber latex and a bituminous material in sufficient quantity to form an aggregate which effectively seals the fluid passage in the presence of a coagulating agent.

4,296,933

PIPE JOINT SEAL

Wilbur E. Tolliver, 364 Hamilton Dr., Holland, Mich. 49423
Division of Ser. No. 40,273, May 17, 1979, Pat. No. 4,209,179.

This application Jan. 18, 1980, Ser. No. 113,358


Int. Cl.³ F16J 15/32, 15/46

U.S. Cl. 277-34.3

3 Claims

1. A pipe joint seal and coupler collar for sealing and connecting pipe sections comprising: an annular channel in said coupler collar; said seal being annular and being positioned in said channel; said seal including a hollow, annular inflatable bladder; said coupler collar including an inflation access means extending from an external surface of said coupler collar to said channel whereby inflating means can be inserted through said inflation access means and into said bladder for inflating said seal when it is in its operative sealing position and wherein said seal further includes an annular base member and at least one annular and outwardly curved sealing flange curving

upwardly, outwardly and then downwardly from said base member for tightening against the pipe joint surface which it



abuts when fluid pressure is exerted against the seal; said bladder being located in said base member.

4,296,934

SEALING ASSEMBLY

Howard S. Atkin, Leeds, England, assignor to Holset Engineering Company Limited, Huddersfield, England


Filed Jun. 7, 1979, Ser. No. 46,409

Claims priority, application United Kingdom, Jun. 9, 1978, 26635/78

Int. Cl.³ F16J 15/34, 15/46

U.S. Cl. 277-81 R

3 Claims



1. A turbine assembly comprising:

a turbine housing having an internal cylindrical surface;
a turbine wheel shaft rotatable relative to said housing and having an external cylindrical surface opposing the internal cylindrical surface, said turbine wheel shaft having an annular groove formed therein;
a sealing ring positioned in said annular groove and having a cylindrical radially outer surface engaging the cylindrical surface of said turbine housing;

one of the axial faces of said sealing ring having a chamfered portion so that the axial dimension of the radially inner surface of the sealing ring is less than the axial dimension of the cylindrical radially outer surface of the sealing ring, the annular groove including a complementary shaped cone-like wedging surface for cooperating engagement with the chamfered surface of the sealing ring.

4,296,935

MECHANICAL SEAL

Hiroshi Inouye, Minorimachi, Japan, assignor to Hitachi, Ltd., Tokyo, Japan


Filed Oct. 10, 1979, Ser. No. 83,340

Claims priority, application Japan, Oct. 9, 1978, 53-123620

Int. Cl.³ F16J 15/34, 15/48

U.S. Cl. 277-81 R

2 Claims



1. A mechanical seal for sealing the rotary shaft of a rotary machine wherein the pressure difference between the internal and external liquid acting on said mechanical seal changes from positive to negative or from negative to positive, characterized in that

an axially movable but nonrotatable ring and a seat ring are formed with seal faces which coact to seal between the internal liquid present externally of a retainer and the external liquid present internally of said retainer, said seat ring is liquid-tightly and securely mounted on said rotary shaft, said retainer is disposed for axial movement, but is prevented from rotating about the axis of said rotary shaft by a bias spring and a stop means, said bias spring normally biases said retainer against said seat ring and provides the sealing force for pressing the seal face of said retainer against the seal face of said seat ring when the external liquid pressure becomes higher than the internal liquid pressure, but the difference therebetween is small and less than a predetermined level, said retainer is disposed within a casing and is forced to move axially depending upon the difference in pressure between the internal and external liquids, and O-rings are interposed between the casing and the retainer and between the retainer and the axially movable, but nonrotatable ring.

4,296,936

SEAL MECHANISM FOR THE ROTOR PERIPHERY OF A ROTARY PISTON ENGINE

Felix Wankel, Bregenzer Strasse 82, D-899 Lindau, Fed. Rep. of Germany


Filed Mar. 25, 1980, Ser. No. 133,784

Claims priority, application Switzerland, Mar. 27, 1979, 2841/79

Int. Cl.³ F16J 15/48; F01C 19/02

U.S. Cl. 277-81 P

18 Claims



1. A seal mechanism for the periphery of the rotor of a rotary piston engine operating with a fluid working medium

comprising: a sealing ledge extending generally parallel to the axis of said rotor and supported on said rotor so as to be pivotable about an axis extending in the longitudinal direction thereof, said sealing ledge being arranged for sealing contact along a limited region of its periphery with an opposed sealing surface in said engine; and secondary seal means provided at at least one point on the periphery of said sealing ledge extending parallel thereto and acting between said sealing ledge and said rotor, said secondary seal means operating to establish on said sealing edge a surface area upon which the pressure of said fluid working medium acts such that there are developed on said sealing ledge resulting forces having a desired magnitude and directed to place said limited region of said sealing ledge into sealing contact with said opposed sealing surface.

4,296,937

RUBBING-CONTACT SEALING STRUCTURE FOR ROTARY HEAT REGENERATOR

Noritoshi Handa, Yokosuka, Japan, assignor to Nissan Motor Company, Limited, Yokohama, Japan


Filed Jul. 13, 1979, Ser. No. 57,291

Claims priority, application Japan, Jul. 20, 1978, 53-100631[U]

Int. Cl.³ F28D 19/04

U.S. Cl. 277-88

15 Claims



1. A rubbing-contact sealing structure for a heat regenerative core rotatable within a stationary housing structure having high-pressure and low-pressure fluid chambers arranged in counter-flow relationship adjacent one face of the heat regenerative core and a high-pressure space surrounding the heat regenerative core and communicating with the high-pressure fluid chamber, comprising: a main seal element having an inner end face to be in rubbing contact with said face of the heat regenerative core, and an elastic pressing member in the form of a substantially flat single plate provided in sealing engagement between said main seal element and said housing structure and at least in part elastically deformable toward and away from said face of the heat regenerative core, the pressing member having an outer face at least in part exposed to said fluid space and laterally extending substantially in parallel with said face of the heat regenerative core in the absence of a differential fluid pressure between the two sides of the pressing member, one end of said pressing member being secured to the housing structure while the other end thereof elastically presses said main seal element against the regenerative core with the aid of the pressure difference between the two sides of said pressing member.

4,296,938

IMMERSION-TYPE SEAL FOR THE STANDPIPE OPENING OF COKE OVENS

Ludwig Offermann, Olfen, and Reinhold Wippich, Recklinghausen, both of Fed. Rep. of Germany, assignors to Firma Carl Still GmbH & KG, Recklinghausen, Fed. Rep. of Germany

Filed May 2, 1980, Ser. No. 145,976

Claims priority, application Fed. Rep. of Germany, May 17, 1979, 7914320[U]


Int. Cl.³ C10B 25/20; F16J 15/40

U.S. Cl. 277-135

6 Claims

1. An immersion-type seal for a standpipe opening of coke

ovens, comprising a standpipe having a top opening with an annular encircling rim, an annular seal frame having a bottom peripheral spherical edge overlying said rim and sealing the



opening, said seal frame having wall portions defining an open topped water sealing trough, and a standpipe lid having an annular skirt portion engaged in said water trough and a top closing the top of said seal frame.

4,296,939

SPEED UP DEVICE FOR BICYCLE

Masaru Iwamoto, 98 Otsukawa-Hiedacho, Handa City, Aichi Prefecture, Japan


Filed Feb. 9, 1979, Ser. No. 10,838

Claims priority, application Japan, Jun. 2, 1978, 53-75718[U]

Int. Cl.³ B62M 1/10

U.S. Cl. 280—212

1 Claim



1. In the known combination of a bicycle wheel that includes a rim, an axle and two sets of spokes extending from opposite ends of said axle outwardly toward said rim, the improvement which comprises:

- at least two devices located within said rim, around said axle and between said two sets of spokes,
- each said device including a pair of axe-shaped sheet members positioned in opposed relationship with each other with portions of said sheet members being joined together at their edge portions, and other portions of said sheet members being spaced apart with respect to each other,
- the bottom edge of each sheet member being disposed adjacent the axle of the wheel,
- the top edge of each sheet member being disposed adjacent the rim of the wheel,
- each sheet member having spaced apart side edges that extend between said top and bottom edges,
- the top edges of each pair of opposed sheet members being joined together so as to essentially form an elongated outer edge,
- one of the two pairs of opposed side edges of each pair of

opposed sheet members being joined together so as to form a leading side edge,

- guide grooves located along the bottom edge of each sheet member,
- a spacing member mounted in said guide grooves intermediate each pair of opposed sheet members, which spacing member is shaped so that when it is inserted in said guide grooves it causes one of said two pair of side edges of opposed sheet members to be spread apart with respect to each other, and causes the other of said two pair of side edges of opposed sheet members to converge with respect to each other, and
- mounting means for securely mounting each said device in a position between said two sets of spokes,
- each said device being widest near the axles, somewhat less wide near the rim and narrowest at a point intermediate the rim and said axle.

4,296,940

FOLDING BICYCLE

Hugh G. Herbert, 1^B Limsfield Ave., London SW19 6DL, England


Filed May 14, 1979, Ser. No. 38,732

Claims priority, application United Kingdom, May 22, 1978, 21056/78

Int. Cl.³ B62K 15/00

U.S. Cl. 280—278

12 Claims



1. In a folding bicycle comprising a frame, a front wheel and handlebars at the front end of the frame, a rear wheel at the rear end of the frame, and a saddle carried at an intermediate part of the frame, the improvement wherein said frame comprises a base including generally-aligned end-to-end tie members having adjacent ends and remote ends, a bearing unit to which said tie members are pivotally connected at their adjacent ends, an apex joint having a bearing opening, strut members connected between said apex joint and the remote ends of the tie members, and a support member, which extends from said bearing unit to which it is secured and slidably through said bearing opening in the apex joint to carry said saddle, said frame being collapsible on raising said support member to move said bearing unit towards said apex joint and so swing the front and rear wheels downwardly into positions alongside one another.

4,296,941

FOLDING GOOSENECK ASSEMBLY

Bernard Van Wassenhove, Oklahoma City, Okla., assignor to CMI Corporation, Oklahoma City, Okla.

Filed Aug. 6, 1979, Ser. No. 63,955

Int. Cl.³ B60P 1/04


U.S. Cl. 280—423 B

18 Claims

1. An improved linkage assembly for use with a folding gooseneck trailer having a forward gooseneck member and a load carrying means, said forward gooseneck member having a forward end portion and a rearward end portion, the rear-

ward end portion including an upper portion and a lower portion, said load carrying means having a forwardly extending end portion and a rearward end portion, said linkage assembly operably connecting the forward end portion of the load carrying means to the rearward end portion of the forward gooseneck member, said improved linkage assembly comprising:

- first linkage means for connecting the forward gooseneck member to said load carrying means, said first linkage means having a forward end portion and an opposed rearward end portion, the forward end portion of the first linkage means pivotally secured to the upper portion of the rearward end portion of said forward gooseneck member;
- camming means operatively connecting the opposed rearward end portion of said first linkage means to the forwardly extending end portion of said load carrying means, said camming means being pivotally connected to the opposed rearward end portion of said first linkage means and connected to said forwardly extending end portion of said load carrying means for permitting sliding movement of said first linkage means along a longitudinal axis which is substantially parallel to the longitudinal axis of said load carrying means, said camming means comprising:
 - a housing having an elongated opening therein;
 - a cam positionable within the elongated opening of said housing for movement along the longitudinal axis of said housing; and
 - a pin having said cam operatively connected thereto so that one end portion of said pin extends outwardly from said housing and said cam, the outwardly extending end portion of said pin pivotally secured to the rearward end portion of said first linkage means;



- second linkage means for connecting the forward gooseneck member to said load carrying means, said second linkage means having a forward end portion and an opposed rearward end portion, the forward end portion of said second linkage means pivotally secured to the lower portion of the rearward end portion of said forward gooseneck member at a position below the pivotal attachment of said forward end portion of said first linkage means, the opposed rearward end portion of the second linkage means pivotally secured to the forwardly extending end portion of said load carrying means at a position below and forward the slidable attachment of said rearward end portion of said first linkage means to said load carrying means; and
- linkage assembly stabilizing means operatively connected to the rearward end portion of said first linkage means and the forward portion of said load carrying means for securing said first linkage means in a first position when the forward gooseneck member and the linkage assembly are in a first folded position and said linkage assembly stabilizing means is in a first position, said linkage assembly stabilizing means securing said first linkage means in a second position when the forward gooseneck member and the linkage assembly are in a second folded position and said linkage assembly stabilizing means is in a second position, said first and second linkage means cooperating to form a linkage assembly substantially having a parallelogram configuration when the forward gooseneck member and linkage assembly are in one of the first and second folded positions, and said first and second linkage means cooperating to form a linkage assembly having a non-parallelo-

gram configuration when the forward gooseneck member and linkage assembly are in an unfolded position.

4,296,942

EMERGENCY RELEASE SYSTEMS

Roy Clifford, Amptill, England, assignor to Kangol Magnet Limited, Carlisle, England


Continuation of Ser. No. 893,418, Apr. 4, 1978. This application Sep. 26, 1979, Ser. No. 79,235

Claims priority, application United Kingdom, Apr. 18, 1975, 16198/75

Int. Cl.³ B60R 21/10

U.S. Cl. 280—803

5 Claims



- A vehicle comprising:
 - two separate vehicle seats located in said vehicle in adjacency,
 - two passive seat belt systems each associated with a respective one of said vehicle seats, each system being adapted to occupy either a position of use or an out of use position in dependence on a vehicle condition and comprising a seat belt means extending in the position of use across the associated seat,
 - connector means adapted to releasably connect both said seat belt means together to said vehicle at a position between said seats, said connector means being manually operable by a single operation to effect disconnection of said seat belt means from said vehicle to render both said seat belt systems incapable of restraining the occupants of the seats therein, each of said seat belt systems comprising a retractor having a retractor spring, said seat belt means being withdrawable from said retractor against the pull of said spring, said seats being located between two vehicle doors and the retractor of each of said seat belt systems being mounted on the one of said doors adjacent the associated seat, and a guide means for said seat belt means carried by each of said doors at a position above the associated retractor at about the level of the faces of the occupants of the seats, each of said belts extending upwardly from said retractor to said guide means and diagonally downwards from said guide means to said connector means, whereby said seat belt means extend across and above said seats in front of the faces of the occupants on release of the seat belt means from said connection means.

4,296,943

DEVICE FOR HOLDING A PASSIVE VEHICLE RESTRAINT BELT AT A RESTRAINING POSITION

Juichiro Takada, 3-12-1 Shinmachi Setagayaku, Tokyo, Japan

Filed Feb. 28, 1980, Ser. No. 125,541

Claims priority, application Japan, Mar. 2, 1979, 54-023431


Int. Cl.³ B60R 21/10

U.S. Cl. 280—804

6 Claims

1. In a passive vehicle restraint belt system which includes a moving anchor that is coupled by a sheathed drive wire to a drive device for moving the anchor along a predetermined path in the vehicle between an occupant-restraining location and an occupant-releasing location, the sheath of the drive wire extending from adjacent the drive device to adjacent a stop means at the occupant-restraining location of the moving

anchor, the improvement wherein the sheath of the drive wire is composed of two sections, one of which is affixed to a portion of the vehicle at a location adjacent the occupant-restraining location of the moving anchor, the other of which is affixed to a portion of the vehicle at a location adjacent the drive device and at least one of which is non-rigid and deflectable,



and the two sections are connected to each other by a resilient lost-motion coupling that normally urges the sections axially away from each other to increase the effective length of the sheath by deflecting at least the deflectable section thereof but allows them to move toward each other to shorten the effective length of the sheath.


4,296,944

COVERING CONSTRUCTION OF A GUIDE RAIL
Hideoki Matsuoka, Yokohama, and Yoshinobu Kondo, Kosai, both of Japan, assignors to Nissan Motor Company, Limited, Yokohama and Fuji Kiko Co., Ltd., Tokyo, both of Japan
Filed Feb. 4, 1980, Ser. No. 118,432

Claims priority, application Japan, Feb. 5, 1979, 54-13974[U]
Int. Cl.³ B60R 21/10

U.S. Cl. 280—804

3 Claims



1. A covering construction of a guide rail of a safety seat belt device of a vehicle having a guide rail with an opening and mounted on an inner wall of the vehicle and a sliding member arranged to slide freely in the guide rail and extending beyond the opening and connected to a seat belt, the improvement lies in that a flexible cover sheet, having a slit extending in the middle thereof and along the opening of the guide rail, is arranged to normally close said opening of the guide rail and allowing passage of the sliding member in the slit.

4,296,945


POCKET SECRETARY OR THE LIKE
Kathleen W. Pavlik, R.D. #1, Box 328A, Rehoboth, Del. 19971
Continuation of Ser. No. 874,609, Feb. 2, 1978, abandoned. This application Dec. 5, 1979, Ser. No. 100,596
Int. Cl.³ B42D 3/00; A45C 1/08

U.S. Cl. 281—1

8 Claims

1. A pocket secretary or the like, comprising:
a flexible foldable member with at least two folding areas;
three pocket means secured to said foldable member, one of said pocket means being narrow, for holding writing implements, and being disposed in a folding area of said foldable member;
means for detachably mounting a separately bound notebook, secured to another folding area of said foldable member;

an envelope means secured to said foldable member together with said detachable mounting means; and
releasable closure means for retaining said foldable member in a folded condition, including an overlapping flap and releasable attachment means, wherein said narrow pocket



means is disposed opposite said detachable mounting means when said member is folded, and said other two pocket means are disposed opposite one another, said mounting means and said writing implements, when held in said narrow pocket means, providing structural support for said flexible member, when folded.

4,296,946


BOOK SUPPORT

Frank J. Larre, and Jeannine G. Larre, both of Box 452, St. Walburg, Saskatchewan, Canada
Filed Aug. 27, 1979, Ser. No. 69,719

Int. Cl.³ B42D 9/00

U.S. Cl. 281—45

10 Claims



1. A book holder and support comprising in combination a front book supporting panel and a rear panel hingedly secured by the upper edge thereof to the upper edge of said front panel to form, when open, an inverted V-shape when viewed in side elevation, means cooperating between said panels to adjust the angularity between same and within limits, and means to detachably retain a book in the open position upon said front panel, said means to adjust the angularity between said front and rear panels including a flexible cord anchored by each end thereof adjacent each side of said front panel, guide means adjacent the side edges of said rear panel, said cord passing freely through said guide means, and a plurality of vertically situated cord anchoring means extending outwardly from the rear surface of said rear panel, the looped center portion of said cord detachably engaging one of said anchoring means in non-sliding relationship.

4,296,947

PRESSURE-SENSITIVE TRANSFER SHEETS USING NOVEL RADIATION CURABLE COATINGS

Sydney M. Spatz, Circleville; Robert C. Hydell, and Gerald T. Davis, both of Chillicothe, all of Ohio, assignors to The Mead Corporation, Dayton, Ohio

Continuation of Ser. No. 697,019, Jun. 17, 1976, Pat. No. 4,138,508. This application Feb. 2, 1979, Ser. No. 9,382

The portion of the term of this patent subsequent to Feb. 6, 1996, has been disclaimed.

Int. Cl.³ B41M 5/22

U.S. Cl. 282—27.5

2 Claims

1. A pressure-sensitive, carbonless transfer sheet comprising a paper substrate, said paper substrate having coated thereon a barrier layer and a cured resinous film coated on said barrier layer, said cured resinous film comprising:

- a carrier oil;
- at least one color precursor selected from the group consisting of lactone phthalides, lactone fluorans and mixtures thereof, said color precursor being dissolved in said carrier oil to form a color precursor solution; and
- a radiation curable substance, said radiation curable substance being selected from the group consisting of: isocyanate modified acrylic, methacrylic and itaconic acid esters of polyhydric alcohols, acrylic prepolymers derived from partial esterification of pentaerythritol with acrylic acid and acrylic acid esters and mixtures thereof;

said resinous film being cured by radiation to a frangibility that will permit passage of said color precursor and said carrier oil to the surface of said cured resinous film when said cured resinous film is broken, said color precursor solution being retained as small occlusions within a matrix of closely packed cross-linked molecular chains of cured resin.

4,296,948

COLOR-DEVELOPING SHEET FOR NO-CARBON COPYING PROCESS

Tsutomu Satoh; Hideo Ohye; Hirokazu Tsukahara; Hideaki Senoh, and Takahiro Torii, all of Takasago, Japan, assignors to Mitsubishi Paper Mills, Ltd., Tokyo, Japan

Filed Nov. 28, 1979, Ser. No. 98,176

Int. Cl.³ B41M 5/16, 5/22

U.S. Cl. 282—27.5

7 Claims

1. A color-developing pressure sensitive sheet for use in no-carbon copying system, comprising a support and an electron-accepting color-developing layer thereon of a combination of a phenol-formaldehyde resin with a solid acid which is an active silicic acid, which are capable of developing color upon reacting with an electron-donating colorless dye, characterized in that titanium dioxide is incorporated into the said electron-accepting color-developing layer in an amount of from about 2 to about 4 parts by weight based on one part by weight of the phenol-formaldehyde resin.

4,296,949

ROTATABLE CONNECTING DEVICE FOR I.V. ADMINISTRATION SET

Andrew J. Muetterties, Gages Lake; John L. Vcelka, Zion, and Wayne R. Kelsey, Des Plaines, all of Ill., assignors to Abbott Laboratories, North Chicago, Ill.

Filed Aug. 6, 1979, Ser. No. 64,141

Int. Cl.³ F16L 19/02


U.S. Cl. 285—18

20 Claims

1. A connecting device for an intravenous administration set comprising:

- a first member defining a fluid passage means and having a longitudinal axis;
- a second member defining a fluid passage means and having a longitudinal axis;
- tapering interfitment means constructed and arranged with respect to each said member for fluid-tight engagement;

a length of tubing secured to at least one member opposite said tapering interfitment means;
a flange extending from one of said first or second members adjacent said tapering interfitment means;
a collar member alternately and rotatably mounted on one of said first or second members opposite said flange, said collar member having internal threads for engagement with said flange; and
captive means operatively associated with one of said members and said collar member to permit free movement along the longitudinal axis of said member while retaining said collar on said member yet permitting rotatable engagement with said flange, said captive means including a tapering surface defined by said member mounting said collar for interference therewith, said captive means constructed and arranged to permit said collar member to be positioned a substantial distance away from said tapering interfitment means carried by said member mounting said



collar member for complete exposure for sterilization purposes, said captive means further including cooperating means defined by said member mounting said collar member and said collar member to provide an interlocking mechanism, said cooperating means positioned on said collar member opposite said internal threads and on said mounting member opposite said tapering surface;
so that when said tapering interfitment means is interengaged, said collar member will engage said flange and upon rotation of said collar the interfitment means will be forced into fluid-tight engagement and said collar member will engage said tapering surface without rotation of said first or second members, and upon a reverse rotation of said collar member and movement of said collar member away from said flange, said interlocking mechanism will interengage whereby rotation of said collar will cause rotation of said member mounting said collar without rotation of said member with said flange.

4,296,950

CORROSION RESISTANT PIPE JOINT

Richard L. Chamberlin, Bradford, Pa., assignor to Dresser Industries, Inc., Dallas, Tex.

Filed Jul. 18, 1979, Ser. No. 58,697

Int. Cl.³ F16L 19/06


U.S. Cl. 285—45

8 Claims

1. In pipe joint forming members including a first metal component having a male thread and a second metal component having a female thread, corrosion protection for the joint adapted to be provided by said components and comprising in combination:

- a first polymeric plastic coating formed about the periphery of said male threaded component and terminating behind the thread thereof;
- a second polymeric plastic coating formed about the periphery of said female threaded component and terminating in an annular flexible skirt extending beyond the joint forming end thereof, said skirt being adapted when said male and female components are threadedly assembled

bled in joint formation to surroundingly overlap a portion of the coating on said male component; and
(c) at least one polymeric plastic annular lip of locally beaded cross-section integrally formed extending radially inward on an opposing surface of at least one of said overlapped skirt or coating thereat;



(d) said lip being adapted to cooperate with said opposing surface at any longitudinal location along the mutual overlap therebetween in the course of assembling said components to effect a threadlessly compressive sealing engagement enclosing the metal threads of the joint formation.

4,296,951

SPHEROIDAL INTERCONNECTOR FOR FILTRATION MODULES


Robert D. Zimmerly, Kenosha, Wis., assignor to Ladish Co., Cudahy, Wis.

Filed Jun. 29, 1979, Ser. No. 53,636

Int. Cl.³ F16L 17/00

U.S. Cl. 285—95

7 Claims



1. A coupling assembly comprising two coaxial conduit members, an interconnector means for coupling and sealing said coaxial members, and wall means defining a pressure chamber around said members adapted to contain a pressurized fluid between said members and said wall means, said interconnector means having a spheroidal body located within said pressure chamber and comprised of elastomeric material, said body having coaxial bores extending into it from opposite sides for receiving the respective ends of said members in a snug fitting relationship, and said body being operative to transmit pressure exerted by the fluid on its outside surface to the surface constituting the interface area between said bores and the members in the bores, the area of said outside surface of the body being substantially larger than said interface area so that the force on a unit area of said interfacing surface is greater than the force exerted by said fluid on a unit area of said outside surface to enhance the seal between said members.

4,296,952

ROTARY JOINT

Donald G. McCracken, Horton, Mich., assignor to Aeroquip Corporation, Jackson, Mich.

Filed Jul. 30, 1979, Ser. No. 61,598


Int. Cl.³ F16L 00/00

U.S. Cl. 285—98

5 Claims

1. A rotary joint comprising, in combination, an annular housing having a first port in communication with a chamber

defined therein, a single annular anti-friction bearing mounted upon said housing within said chamber, a tubular sleeve mounted within said bearing for rotation within said chamber about an axis, a second port defined by said sleeve communicating with said chamber, an annular elastic cushion mounted on said sleeve adjacent said second port, an annular rigid seal element supported upon said cushion defining an annular radially disposed sealing surface defined on said sleeve concentric with said axis, an annular seal within said chamber concentric with said axis sealingly and slidably engaging said sealing surface, annular resilient seal support means sealed with re-



spect to said housing flexibly supporting said annular seal and constituting the sole support of said seal whereby said seal is self-aligning with respect to said sealing surface, a cylindrical surface defined in said chamber coaxial to said axis, said seal support means comprising an elastomeric ring having a first lip seal portion sealingly engaging said cylindrical surface, a cylindrical surface defined on said annular seal coaxial to said axis, said ring having a second lip seal portion engaging said seal cylindrical surface wherein said seal is supported within said ring, fluid pressure within said housing biasing said seal into engagement with said sealing surface and said lip seals into sealing relation to their associated cylindrical surface.

4,296,953

SLIPPING-OFF PREVENTING PIPE JOINT

Shozo Nagao; Yoshinobu Ohashi; Yuichi Watanabe, and Yoshikazu Wakushima, all of Amagasaki, Japan, assignors to Kubota, Ltd., Osaka, Japan


Filed Nov. 13, 1979, Ser. No. 93,613

Claims priority, application Japan, Dec. 22, 1978, 53-162499; Dec. 22, 1978, 53-179613[U]; Dec. 22, 1978, 53-179614[U]; Dec. 22, 1978, 53-179615[U]

Int. Cl.³ F16L 27/12

U.S. Cl. 285—302

6 Claims



1. In a pipe joint comprising a socket having a seal accommodating portion in its inner periphery, a spigot insertable into the socket, and an annular seal retained in the accommodating portion and compressively engageable by the outer periphery of the spigot against the accommodating portion for sealing the clearance between the socket and the spigot when the spigot is inserted into the socket, the improvement wherein: an engaging member comprising a second split lock ring is detachably attached to the inner periphery of the socket and is positioned away from the seal accommodating portion toward the opening of the socket, the second split lock ring being capable of exerting a diametrically expansive force and being engageable from inside the socket axially thereof with a radially inwardly extending face forming a stepped portion on the inner periphery of the socket between the second split lock ring and the socket

opening, the second split lock ring providing an engaging portion projecting radially inward from the inner periphery of the socket;

a protrusion is formed on the outer periphery of the spigot and is positioned between the seal accommodating portion and the engaging member on the socket;

a first split lock ring capable of exerting a diametrically contractive force is fitted to the outer periphery of the spigot between the protrusion on the spigot and the engaging member on the socket, the first lock ring being normally spaced from and engageable with the engaging portion of said engaging member and with said protrusion in response to relative axial separating movement between the socket and spigot; and

each of said first and second lock rings has a radial thickness less than the radial clearance between the inner surface of the socket opening and the outer surface of the spigot whereby said lock rings are insertable through said clearance to their respective assembled positions after the spigot has been inserted into the socket and into compressive engagement with said annular seal.

4,296,954

PIPE COUPLING AND PIPE JOINT CONNECTION

Kiyoshi Fujimaki, Kusatsu; Yoshiaki Bando, Shiga; Takeshi Okuyama, Kyoto, and Tutomu Hashimoto, Shiga, all of Japan, assignors to Sekisui Kagaku Kogyo Kabushiki Kaisha, Osaka, Japan


Filed Sep. 11, 1979, Ser. No. 74,806

Claims priority, application Japan, Sep. 14, 1978, 53-126827[U]; Dec. 4, 1978, 53-167386[U]

Int. Cl.³ F16L 17/06

U.S. Cl. 285—331

4 Claims



1. A pipe coupling comprising:

a main annular body having a central axis and an internally threaded portion at the open end thereof for threaded engagement with an inside-coated pipe having an exterior mating threaded end portion, an internal annular groove at the inner end of said internally threaded portion, and an annular projection at the inner side of said annular groove and projecting toward said axis of said annular body;

a short cylindrical body mounted within said main body having an outer cylindrical surface and having one end abutting said annular projection; and

an annular packing mounted within the space defined by said internally threaded portion, said annular groove and the outer cylindrical surface of said cylindrical body, the dimension of the circumferential surface of the annular packing parallel to said axis of said annular body and when said packing is in the uncompressed state being greater than the corresponding dimension of the circumferential surface of the annular groove and less than the corresponding dimension of the cylindrical outer surface of said short cylindrical body, and the end of the annular packing toward the open end of the main body being pressed into the internally threaded portion for being provisionally fixed in position in said pipe coupling.

4,296,955

COMPOSITE COUPLING DEVICE WITH HIGH RECOVERY DRIVER


Charles L. Martin, Palo Alto, Calif., assignor to Raychem Corporation, Menlo Park, Calif.

Continuation-in-part of Ser. No. 404,724, Oct. 9, 1973, abandoned, and a continuation-in-part of Ser. No. 404,723, Oct. 9, 1973, abandoned. This application Aug. 27, 1975, Ser. No. 608,207

Claims priority, application Sweden, Apr. 9, 1975, 6975040 Int. Cl.³ F16L 25/00

U.S. Cl. 285—381

46 Claims



1. A composite device which comprises:

(a) a hollow, heat-recoverable, helical spring member made from helically wound sheet or wire of memory metal, said heat-recoverable member having a cross-section such that sections perpendicular to the axis of the heat-recoverable member each show a discontinuity; and

(b) a hollow sleeve, open at both ends, disposed coaxially with said heat-recoverable member, and adapted to be deformed to grip a substrate, said deformation resulting from force exerted on the sleeve by the heat-recoverable member when the heat-recoverable member is heated above its transition temperature and recovers in the direction of said sleeve.

4,296,956

CAM OPERATED LOCK, PARTICULARLY FOR DOORS

Angelo Colombo, Lazzate, Italy, assignor to Valli & Colombo S.p.A., Italy


Filed Jul. 19, 1979, Ser. No. 58,957

Claims priority, application Italy, Aug. 8, 1978, 26568 A/78; Oct. 27, 1978, 23159/78[U]

Int. Cl.³ E05C 1/16

U.S. Cl. 292—169.18

17 Claims



1. A door lock comprising:

latch means adapted to be mounted in a door or the like, said latch means including a tubular guide and a latch member mounted for reciprocation therein between a latched position and an unlatched position;

a housing assembly adapted to be mounted in a door;
a slide member mounted for reciprocation in said housing assembly and coupled to said latch member, said slide member including a thrust portion fixed thereto;
a single cam member rotatably mounted in said housing assembly having an eccentric portion and a central hub portion having a bore formed therethrough adapted to receive a shaft therein, the axis of said bore being substantially coincident with the axis of rotation of said cam member;
said slide member thrust portion being situated in the path of said cam member eccentric portion so that when said cam member is rotated, said eccentric portion will engage said thrust portion to move said slide member;
stop means fixed within said housing assembly; and
first spring means for urging said cam member in a direction such that said eccentric portion normally engages said stop means.

4,296,957

CHAIN-LOCK ACTUATED MAGNETIC SWITCH


David E. Belles, Pittsford, N.Y., assignor to Lok-A-Wat, Inc., Adamsville, Tenn.

Filed Sep. 24, 1979, Ser. No. 78,132

Int. Cl.³ E05C 17/36, 13/10

U.S. Cl. 292—264

3 Claims



1. A chain-lock actuated magnetic switch for use with a door having a stile, and a frame for the door having a striker jamb comprising:

- a magnet-responsive switch adapted to be mounted on a door striker jamb and having a normal circuit-controlling condition and being magnetically actuatable to an abnormal circuit-controlling condition,
- a chain-lock keeper adapted to be mounted on a door stile opposite the switch, said keeper having a permanent magnet whose flux is normally capable of actuating the switch to its abnormal condition when the door is closed,
- a chain having anchor means on one end thereof for anchoring the same to the striker jamb, and
- a bolt on the other end of the chain, said bolt constituting pole piece means for said magnet for shunting the flux thereof when said bolt is seated home in said keeper whereby to prevent the same from actuating said magnet-responsive switch to said abnormal condition.

4,296,958

HOLDER FOR LIQUID PACKAGING CONTAINERS

Roelof J. Stranders, Thalwil, Switzerland, assignor to Werner Weber Holding AB, Baar, Switzerland

Filed Jan. 24, 1980, Ser. No. 114,788

Claims priority, application Switzerland, Feb. 9, 1979, 1310/79; Mar. 12, 1979, 2344/79


Int. Cl.³ A47B 95/02

U.S. Cl. 294—27 H

9 Claims

1. A detachable container holder for liquid packaging containers having upstanding front and rear walls, side walls extending between said front and rear walls and end margins of said side, front and rear walls defining flaps infolded into overlapping relationship to form an end closure of the container, wherein said holder incorporates a first supporting element

arranged to lie at least partly along the rear wall of the container, handle means associated with said first supporting element, a further supporting element integral with said first supporting element and being arranged to engage a further



portion of the container, and retaining means provided on one of said supporting elements and arranged to receive and retain the flap defined by the upper end margin of the container end wall when said flap is pried away from the infolded closed position.

4,296,959

RACK HANGING DEVICE FOR GARMENTS


Rolf W. Helbig, 24-6679 Shelter Bay Rd., Mississauga, Ontario, Canada (L5N 2A2)

Filed Jul. 2, 1979, Ser. No. 53,914

Int. Cl.³ A47J 51/084

U.S. Cl. 294—143

7 Claims



1. A device for supporting a plurality of hangers such as garment hangers or the like, comprising:

- a substantially planar lower leg portion having a front side and a rear side;
- an upper channel portion for pendently supporting the device, and having a concave surface defining a rearwardly and downwardly facing hook;
- said substantially planar leg portion having at least one aperture for a plurality of garment hangers or the like; and
- a lifting lug formation on the front side of said substantially planar lower leg portion beneath said rearwardly and downwardly facing hook, comprising at least one forwardly directed lug and at least one downwardly directed flange spaced at a distance from the front face of said substantially planar lower leg portion so as to provide a counter-bearing surface for an operating member to be engaged therewith.

4,296,960

INFLATABLE CAMPER

Loren R. Winchester, 105 Southwest St., Yorktown, Ind. 47396


Continuation-in-part of Ser. No. 52,486, Jun. 7, 1979,

abandoned. This application Sep. 21, 1979, Ser. No. 77,857

Int. Cl.³ B60P 3/32

U.S. Cl. 296—167

4 Claims



1. An inflatable camper for pickup trucks comprising: four generally rectangular inflatable walls including a front wall, a rear wall, and two side walls;
- valve means in at least one of said inflatable walls for inflating or deflating same;
- an inflatable top connected to said inflatable walls;
- flexible floor means connected to a base of said inflatable walls;
- internal wall means of said inflatable walls and top to help form said inflatable camper in a general external configuration similar to a pickup truck camper, said internal walls allowing air flow therethrough for said inflating or deflating;
- entrance opening in said rear wall for allowing entry into said inflatable camper;
- portholes in said inflatable walls to allow light into said inflatable camper, said portholes being covered by flexible releasable transparent material;
- screen means secured at said portholes and said entrance opening to prevent most insects from entering said inflatable camper;
- flexible door means removably connected to said rear wall for closing said entrance opening;
- zipper means for holding said flexible transparent material in position to cover said portholes and to hold said flexible door means and said screen means at said entrance opening; and
- magnetic strips embedded in said flexible floor means to magnetically hold said flexible floor to the contour of the bed of said pickup truck and embedded in portions of said inflatable walls to magnetically attach to contiguous portions of said pickup truck.

4,296,961

OPENING ROOFS FOR VEHICLES

Keith R. Hunt, Devon, and Sidney E. Fisher, Birmingham, both of England, assignors to Britax Weathershields Limited, Birmingham, England

Filed Oct. 18, 1979, Ser. No. 85,862

Claims priority, application United Kingdom, Oct. 18, 1978, 41037/78; Jan. 23, 1979, 02430/79


Int. Cl.³ B60J 7/18

U.S. Cl. 296—216

9 Claims

1. An opening roof for a vehicle having a roof provided with an opening comprising a frame for surrounding said opening and including spaced side members and spaced end members, and a panel assembly co-operating with said frame and movable with respect to said frame to expose portions of said opening for ventilation purposes, wherein said frame includes a flange adapted to overlie a portion of said roof surrounding said opening, said flange having an inner edge and a web depending from said inner edge of said flange and having an outer face, a lower end, and being provided with openings, and

clamping means are provided to clamp said flange against said roof, said clamping means comprising a separate resilient clamping strip extending along each of said side members and along each of said end members of said frame, each of said clamping strips including a generally flat base which is clamped against said outer face of said web and an integral



clamping tongue which is inclined to said base at an obtuse angle and projects from one edge of said base to engage with a face of said roof remote from said flange, and screws which project through said openings in said webs to urge said flat base into engagement with said web and said flange into engagement with said roof.

4,296,962

WIND DEFLECTOR FOR SLIDING ROOFS OF MOTOR VEHICLES

Hans Jardin, Inning, and August Hirschberger, Munich, both of Fed. Rep. of Germany, assignors to Webasto-Werk W. Baier GmbH & Co., Munich, Fed. Rep. of Germany


Filed Sep. 28, 1979, Ser. No. 80,022

Claims priority, application Fed. Rep. of Germany, Sep. 28, 1978, 7828941[U]

Int. Cl.³ B60J 7/18

U.S. Cl. 296—217

14 Claims



1. Wind deflector for sliding roofs of motor vehicles, said deflector being mountable near the forward edge of a roof opening so that it is swivelable near its forward edge about an axis which runs at right angles to the lengthwise axis of the vehicle, and being comprised of a sheet metal strip and an overlying plastic strip connected thereto, characterized by the fact that the plastic strip is mounted upon said sheet metal strip with a rear edge of the sheet metal strip retained within a groove formed in said plastic strip.

4,296,963

FIREARM SHOOTING SUPPORT TABLE

Kenneth G. Blanchard, Rt. 5, Box 484, and Reuben N. Ronne, Rte. 3, Box 470 R, both of Detroit Lakes, Minn. 56501

Filed Oct. 16, 1979, Ser. No. 85,213


Int. Cl.³ A47B 83/02, 3/14

U.S. Cl. 297—170

2 Claims

1. A shooting table device comprising a table for supporting a firearm, a seat for supporting an operator while firing the firearm, with the firearm supported on the table, said table having a pair of front legs pivotally mounted to the front of said table and adapted to extend vertically from said table for supporting said table, at least one telescoping horizontal supporting means, one end of said telescoping means being pivotally mounted to the front legs of said table at a height intermediate the height of said table, the telescoping means having its other end fixed to said seat, said pivotal mounting of said one end of said telescoping means to said front legs of said table serving as front legs for said seat, said seat having a pair of legs

mounted to support said seat at its rearward end, said telescoping means enabling said seat to be adjusted forward and rear-



ward with respect to said table, said table extending in length at an angle across said seat, said table having a leg at its rearward end to support the rearward end of said table.

4,296,964

STRUCTURAL COMPONENT FOR UPHOLSTERED FURNITURE AND METHOD OF MAKING


Dennis A. Haack, Troy, Ohio, assignor to Denack Design Corporation, Troy, Ohio

Filed Sep. 14, 1979, Ser. No. 75,449

Int. Cl.³ A47C 31/02

U.S. Cl. 297—218

16 Claims



1. A structural component for upholstered furniture, comprising: a three-dimensional wire frame including a plurality of wires welded together to form a wire mat, said wire frame including a border wire extending adjacent the outer edge of said frame, upholstery means including a flexible sheet substrate and an upholstery material cover with padding means disposed between said substrate and said cover, means securing an outer edge portion of said upholstery material cover to an adjacent outer edge portion of said substrate to confine said padding means and to form an upholstery assembly, said upholstery assembly covering said wire frame, and plastic clip means attaching said upholstery assembly to said border wire of said wire frame.

4,296,965

SEAT WITH ADJUSTABLE LUMBAR SUPPORTER

Kenichi Sakurada, Yokohama, and Takaichi Nishino, Hachioji, both of Japan, assignors to Nissan Motor Company, Limited, Yokohama and Tachikawa Spring Company, Limited, Aki-shima, both of Japan

Filed Jul. 11, 1979, Ser. No. 56,607

Claims priority, application Japan, Jul. 31, 1978, 53-93776

Int. Cl.³ A47C 7/46


U.S. Cl. 297—284

8 Claims

1. A seat with a backrest having spaced support portions by which a contoured portion constituted by padding means is supported, and an adjustable lumbar supporter for imparting a

curvature to said contoured portion to produce a desired contour, said lumbar supporter comprising:

- a first rod member transversely crossing said support portions in a manner so as to be rotatable about the axis thereof relative to said support portions;
- an arm member secured at its one portion to said first rod member to be rotatable therewith;
- a second rod member held by said arm member in a manner so as to be rotatable about the axis thereof relative to said arm member;
- lumbar pressing means fixedly mounted on said second rod member;
- a first control mechanism for forcing a unit of said arm member, said second rod member and said lumbar pressing means to swing about the axis of said first rod member when operated; and
- a second control mechanism for forcing a unit of said lumbar pressing means and said second rod member to swing the axis of said second rod member relative to said arm member when operated;



said first control mechanism comprising:

- a first cam having a cam periphery operatively contacting said second rod member;
- a first axle member connected to said first cam to be rotatable therewith about the axis of said first axle member; and
- first stopping means for causing said axle member to assume a predetermined rest position under rotation thereof;

said second control mechanism comprising:

- a second cam supported via a pivot by said arm member and having therein an elongated slot;
- a stud secured to said lumbar pressing means and movably received in said elongated slot of said second cam;
- second stopping means for causing said second cam to assure a predetermined rest position under the swingable rotation of it about said pivot;
- a second axle member; and
- a linkage operatively interposed between said second axle member and said second cam in such a manner that when said second axle member is rotated about the axis thereof, said second cam is swung about said pivot.

4,296,966

SEAT FOR AN AUTOMOTIVE VEHICLE

Takami Terada, Toyota, Japan, assignor to Aisin Seiki Kabushiki Kaisha, Kariya and Shatai Kogyo Kabushiki Kaisha, Yamato, both of Japan

Filed Oct. 3, 1979, Ser. No. 81,459

Claims priority, application Japan, Oct. 18, 1978, 53-128944


Int. Cl.³ A47C 1/025

U.S. Cl. 297—369

6 Claims

1. A seat for an automotive vehicle having a back rest disposed tiltably relative to said seat and at least one adjusting mechanism for adjusting the angle of said back rest relative to said seat, said back rest having a pair of parallel side frame portions which extend forwardly and downwardly from the lower end of the back rest and which are pivoted at the free ends thereof to said seat, said adjusting mechanism comprising

a first link pivoted at one end thereof to one of said pair of parallel side frame portions at a point spaced from said pivoted free end, a second link rotatably connected at one end thereof to the other end of said first link and further pivoted at the other end thereof to said seat, a latch means integrally extending from said second link and provided with an arcuate series



of teeth concentric to the pivoting axis of said second link to said seat, a manual handle pivoted to a part of said adjusting mechanism and having a pin for engagement with said teeth of said latch means and spring means normally urging said manual handle toward engagement with said teeth of said latch means so that said adjusting mechanism is locked and hence said back rest is locked in a selected position of reclination.

4,296,967

PASSENGER SEAT


Ignaz Vogel, Kleinsteinbacherstr. 44, Karlsruhe-Stu 41, Fed. Rep. of Germany (7500)

Filed Nov. 1, 1979, Ser. No. 90,245

Int. Cl.³ A47C 3/12, 5/12

U.S. Cl. 297—451

11 Claims



1. A passenger seat for people moving vehicles such as buses, railways cars, ships and airplanes, said seat comprising: a base; a seating member supported on said base; a backrest member mounted on said seating member, said seating and backrest members consisting of sandwiched plate structures each having spaced plates with a cellular structured core disposed therebetween and a sleeve fully incorporated into the sandwiched plate structure by being disposed between and firmly connected to each of said spaced plates, a bracket structure having its ends extending into the sleeves of said seating and backrest members and being mounted therein for supporting said backrest member on said seating member, and mounting means disposed at the underside of said seating member and connected to said sleeve incorporated in said seating member for supporting said seating and backrest members on said base.

4,296,968

IN SITU OIL SHALE RETORT HAVING HORIZONTALLY OFFSET PILLARS

Thomas E. Ricketts, Bakersfield, Calif.; Ned M. Hutchins, and Irving G. Studebaker, both of Grand Junction, Colo., assignors to Occidental Oil Shale, Inc., Grand Junction, Colo.


Continuation of Ser. No. 951,527, Oct. 16, 1978, This application

Sep. 19, 1979, Ser. No. 77,024

Int. Cl.³ E21C 41/10

U.S. Cl. 299—2

58 Claims



1. A method for recovering liquid and gaseous products from an in situ oil shale retort formed in a retort site within a subterranean formation containing oil shale, such as in situ oil shale retort containing a fragmented permeable mass of formation particles containing oil shale, comprising the steps of:

- excavating formation from within the retort site for forming an upper void extending horizontally across the retort site, leaving an upper zone of unfragmented formation above the upper void, and leaving at least a first pillar of unfragmented formation within the upper void for providing temporary support for the upper zone of unfragmented formation;
- excavating formation from within the retort site for forming a lower void extending horizontally across the retort site, the lower void being spaced immediately below the upper void, leaving an intermediate zone of unfragmented formation extending horizontally across the retort site between the upper and lower voids, leaving a lower zone of unfragmented formation below the lower void, and leaving at least a second pillar of unfragmented formation within the lower void for providing temporary support for the intermediate zone of unfragmented formation, the second pillar being offset horizontally from the first pillar so that at least a portion of a floor of the upper void lies vertically above at least a portion of the second pillar;
- placing explosive in the lower zone of unfragmented formation, at least a portion of such explosive being placed in at least one vertical blast hole extending from said portion of the floor of the upper void through the second pillar and into the lower zone of unfragmented formation below the second pillar;
- placing explosive in the upper and intermediate zones of unfragmented formation;
- detonating such explosive in the upper, intermediate and lower zones of unfragmented formation for explosively expanding formation within such zones toward the upper and lower voids for forming a fragmented permeable mass of formation particles containing oil shale in an in situ oil shale retort;

establishing a retorting zone in an upper portion of the fragmented mass;
introducing a retorting gas into the fragmented mass for sustaining the retorting zone and for advancing the retorting zone through the fragmented mass; and
withdrawing liquid and gaseous products of retorting from a lower portion of the fragmented mass on the advancing side of the retorting zone.

4,296,969


THERMAL RECOVERY OF VISCOUS HYDROCARBONS USING ARRAYS OF RADIAL SPACED HORIZONTAL WELLS

Bertram T. Willman, Calgary, Canada, assignor to Exxon Production Research Company, Houston, Tex.

Filed Apr. 11, 1980, Ser. No. 139,618
Int. Cl.³ E21C 41/10

U.S. Cl. 299—2

21 Claims



1. A method for recovering normally immobile mineral values from a subterranean formation, the method comprising:
 - (a) penetrating said formation with an access shaft;
 - (b) extending first and second radially-spaced substantially horizontal wells from said shaft into said formation;
 - (c) extending a third substantially horizontal well from said shaft into said formation, said third well being located between said first and second wells and being substantially shorter than either of said first and second wells;
 - (d) injecting a mobilizing fluid into said first well and recovering mobilized mineral values via said second well so that a path of high fluid mobility is created in said formation between the ends of said first and second wells;
 - (e) injecting said mobilizing fluid into said first and second wells to further mobilize and drive mineral values through said formation to said third well, the end of said third well being located a sufficient distance from said high mobility path to provide for good sweep efficiency of the mineral values located between said first and second wells; and
 - (f) recovering said mobilized mineral values via said third well.

4,296,970

HYDRAULIC MINING TOOL APPARATUS

Everett L. Hodges, 49 Royal St. George, Newport Beach, Calif. 92660

Filed Feb. 15, 1980, Ser. No. 121,712
Int. Cl.³ E21C 45/00


U.S. Cl. 299—67

11 Claims

1. In a hydraulic mining tool for recovering minerals from subterranean formations, including a hydraulic cutting jet for dislodging said minerals from said formations and forming a resultant mineral slurry, and a hydraulic venturi pump for lifting said mineral slurry to ground surface, the improvement comprising:

an Archimedes screw carried on one end of said mining tool and disposed below said hydraulic venturi pump for transporting a continuous quantity of said minerals toward said hydraulic venturi pump; said Archimedes screw including a sleeve rigidly attached about a portion of its diameter to direct said continuous quantity of minerals toward said hydraulic venturi pump; said Archimedes screw and said

sleeve being axially spaced from said one end of said mining tool with said axial spacing defining a radial inlet for said mineral slurry into said hydraulic venturi pump;



and said Archimedes screw and sleeve being mounted to said one end of said mining tool by means for adjusting said axial spacing to vary the size of said radial inlet.

4,296,971

ANTISKID DEVICE

Hiroshi Nakazato, Hanyu, Japan, assignor to Akebono Brake Industry Co., Ltd., Saitama, Japan


Filed Nov. 27, 1979, Ser. No. 97,891

Claims priority, application Japan, Nov. 30, 1978, 53-165254[U]

Int. Cl.³ B60T 8/10

U.S. Cl. 303—115

6 Claims



1. An antiskid pressure reducing device comprising:

a closed casing;
a power piston located within said casing and dividing the interior of said casing into two pressure chambers and said power piston is movable by differential pressure developed between said two pressure chambers by detection of a skidding state of a wheel;
a brake device;
a pressure source;
a braking pressure transmission line arranged between the pressure source and the brake device;
a valve mechanism arranged to close said braking pressure transmission line;
a pressure reducing chamber disposed between said valve mechanism and said brake device;
said casing including a cylinder containing said valve mechanism;
a plunger slidable within said cylinder, said plunger being

arranged to receive pressure at one end thereof from said pressure reducing chamber; and
a spring means disposed between the other end of the said plunger and said power piston for spacing them a given distance apart, said spring means being arranged to push said plunger with a force greater than the sliding resistance of said plunger;
said plunger is in operative engagement with said valve mechanism; and said valve mechanism is arranged to be closed when pressure from said pressure reducing chamber causes said plunger to move toward said power piston against the force of spring means even if said power piston does not move.

4,296,972

ANTI-SKID BRAKE CONTROL DEVICE

Makoto Sato, Kamifukuoka; Hiroshi Takamatsu, Ohimachi; Yoshitaka Miyagawa, Kawagoe, and Etsuo Fujii, Wako, all of Japan, assignors to Honda Giken Kogyo Kabushiki Kaisha, Tokyo, Japan

Continuation of Ser. No. 871,186, Jan. 20, 1978, which is a division of Ser. No. 762,782, Jan. 25, 1977, Pat. No. 4,129,342.


This application Jun. 20, 1979, Ser. No. 50,204

Claims priority, application Japan, Jan. 29, 1976, 51/8682; Feb. 2, 1976, 51/10195; Feb. 16, 1976, 51/15607

Int. Cl.³ B60T 8/08, 13/68

U.S. Cl. 303—119

1 Claim



1. An anti-skid brake control system for use with four wheeled vehicles, comprising: a brake fluid pressure producing unit, said unit having a pair of two independent power chambers defined therein; a pair of first front and rear wheel cylinders each having a piston slidable therein with a brake applying element connected thereto and a first hydraulic chamber formed therein on one side of said piston, said first hydraulic chamber being connected to one of said power chambers for applying hydraulic pressure to said piston for brake application; said rear wheel cylinder having a second hydraulic chamber formed therein, on the opposite side of said piston and being hydraulically connected to high and low pressure lines for applying a regulated hydraulic pressure to said piston for counteracting hydraulic pressure applied thereto; a pair of second front and rear wheel cylinders, each having a corresponding piston slidable therein with a brake applying element connected thereto and a third hydraulic chamber formed therein on one side of said last-named piston, said third hydraulic chamber being connected to the other of said power chambers for applying hydraulic pressure to said last-named piston for brake application; said second rear wheel cylinder having a fourth hydraulic chamber formed therein on the opposite side of said last-named piston and being hydraulically connected to said high and low pressure lines for applying a regulated hydraulic pressure to said last-named piston for counteracting hydraulic pressure applied thereto; a first control valve interposed in said high pressure line for selectively establishing and blocking hydraulic communication between said second and fourth hydraulic chambers and a hydraulic pressure source; a

second control valve interposed in said low pressure line for selectively establishing and blocking hydraulic communication between said second and fourth hydraulic chambers and a hydraulic reservoir; and means for sensing locking of said rear wheels to properly control said first and second valves such that pressure in said second and fourth hydraulic chambers is reduced when at least one of said rear wheels is being locked.

4,296,973

SEGMENTED HARDFACED COLLAR FOR TOOL JOINTS


Charles A. Hartwell, P.O. Box 36589, Houston, Tex. 77036

Filed Jan. 9, 1980, Ser. No. 110,646

Int. Cl.³ F16C 29/02

U.S. Cl. 308—4 A

5 Claims



1. In a well pipe tool joint formed of a lower threaded tubular body serially affixed to a drill pipe and adapted to be connected with a complementary threaded tubular tool joint body for supporting a drill string, the improvement which comprises wear protector means extending circumferentially about the lower tubular body in an axially extending region wherein said wear protector means comprises an elongate, externally located tubular sleeve terminating at a lower circumferential shoulder located on the lower tubular body at or beyond a specified distance from a weld joining the lower tubular body to a lower pipe and which wear protector means has the form of an encircling cylindrical sleeve supporting hard metal facing thereon wherein said sleeve extends externally upwardly toward a shoulder on the lower tubular body defining a throat area within the lower tubular body which throat area is equal to or exceeds a specified dimensional size from the shoulder to a set of threads formed on the interior of the lower tubular body and wherein said sleeve terminates at a sloping circular shoulder constructed at an angle and extent in accordance with an industry standard and at least one hole drilled therein at said sloping shoulder has a hard metal facing insert therein.

4,296,974

LINEAR BALL BEARING UNIT

Hiroshi Teramachi, 2-34-8 Higashi-Tamagawa, Setagaya-ku, Tokyo, Japan (158)

Filed Feb. 11, 1980, Ser. No. 120,670

Claims priority, application Japan, Feb. 14, 1979, 54-15911


Int. Cl.³ F16C 29/06

U.S. Cl. 308—6 C

2 Claims

1. A linear ball bearing unit, comprising:
a bearing body having a cavity of substantially trapezoidal shape in section and provided with longitudinal ball grooves with the same radius of curvature as the balls along four corners of said cavity and longitudinal ball

recirculating holes extending parallel with the respective ball grooves in radially spaced positions; end lids to be attached to the opposite ends of said bearing body through aligning bushes and provided with turn grooves of U-shape in section to interconnect the opposing ball grooves and ball recirculating holes of said bearing body, said end lids having square recesses at opposite sides of said U-shaped turn grooves to receive a guide strip across each U-shaped groove, said guide strip having a semi-cylindrical ball guide portion over the entire width of said U-shaped groove;



retainers to be fitted on the inner wall surfaces of said cavity of the bearing body and provided with longitudinal slits in horizontal portions opposing said ball grooves, said slits having a width slightly smaller than the diameter of balls and being provided with round-tongues integrally at opposite ends thereof; a number of balls placed in the bearings constituted by said bearing body and end lids through said retainers; and an elongated track shaft located in said cavity and having longitudinally therealong ball grooves of a radius of curvature same as the radius of load-carrying balls.

4,296,975

DEVICE FOR TRANSMITTING LINEAR MEASURING MOTION

Lars Ö. Forsman, Helsingborg, Sweden


PCT No. PCT/SE78/00076, § 371 Date Jul. 10, 1979, § 102(e) Date Jul. 10, 1979, PCT Pub. No. WO79/00292, PCT Pub. Date May 31, 1979

PCT Filed Nov. 13, 1978, Ser. No. 118,802

Claims priority, application Sweden, Nov. 14, 1977, 7712828 Int. Cl.³ F16C 29/04

U.S. Cl. 308—6 R

7 Claims



1. A device for providing linear measuring motion comprising:

- a U-shaped element and a T-shaped element, the stem of the T-shaped element being received between the limbs of the U-shaped element, so that said elements are relatively displaceable with respect to one another, so as to provide said linear measuring motion;
- a body fixedly connected to said U-shaped element and received in a cylindrical opening extending through the stem of the T-shaped element;
- the T-shaped element being mounted to said body by ball bearing means for allowing relative axial motion of said

stem of the T-shaped element between the limbs of said U-shaped element and rotational motion of said T-shaped element about said body; and means for preventing said rotational motion and ensuring accurate guidance of said elements during relative axial displacement thereof, comprising anti-friction bearing means disposed on at least one axial race between said T-shaped element and said U-shaped element.

4,296,976

CROSS-PLIES SUPPORT ELEMENT FOR COMPLIANT BEARINGS


Hooshang Heshmat, Schenectady, N.Y., assignor to Mechanical Technology Incorporated, Latham, N.Y.

Filed Apr. 3, 1980, Ser. No. 136,958

Int. Cl.³ F16C 32/06

U.S. Cl. 308—9

10 Claims



1. A compliant hydrodynamic fluid film bearing, comprising:

- first and second relatively movable members having opposing surfaces defining therebetween a gap;
- a bearing sheet attached to one of said members and having a bearing surface facing said surface of the other of said members;
- a support element lying between said bearing sheet and said one member, and supporting said bearing sheet on said one member;
- said support element including a first corrugated foil module lying on said one member and formed as a plurality of strips whose length runs generally perpendicular to the axis of said corrugations;
- a second corrugated foil module lying between said bearing sheet and said first corrugated foil module, formed as a plurality of strips whose length runs generally perpendicular to the axis of its corrugations and to the strips of said first corrugated foil module;
- said support element thereby forming a matrix of substantially independently compliant support zones including a plurality of zones in orthogonal directions distributed across the area of said support element, each zone of said support element having an angular compliance that is substantially equal about orthogonal axes directions in the plane of said bearing sheet.

4,296,977

SELF-ALIGNING SHAFT BEARING MOUNTING ASSEMBLY

Eli M. Ladin, Ann Arbor, Mich., assignor to Federal-Mogul Corporation, Southfield, Mich.

Filed Jan. 11, 1980, Ser. No. 111,449


Int. Cl.³ F16C 13/02

U.S. Cl. 308—19

7 Claims

- 1. A pivotable shaft bearing mounting assembly comprising a supporting strut, a pair of ball-studs each formed with a ball and a shank affixed in spaced relationship to said strut, a bearing carrier comprised of a pair of overlying plates each formed

with an aligned central aperture and an encircling outwardly projecting annular flange defining therebetween a tubular bearing housing, a bearing including an annular outer race disposed with its periphery clamped within said housing, an annular inner race adapted to receive and rotatably support a shaft, and a plurality of anti-friction elements interposed between said outer and inner race, each of said plates formed with a pair of substantially hemispherical opposed cavities



defining a pair of ball sockets disposed at diametrically spaced positions on each side of said central aperture, said carrier formed with access ports for receiving said shank of said ball-studs in radial-spaced clearance relationship, and fastening means for securing said plates together in face-to-face relationship to clamp said bearing in said housing and said balls in said sockets permitting pivoting movement of said carrier about an axis passing through said balls.

4,296,978

SLIDING BEARING

Norbert Löser, and Leopold Tilgner, both of Heusweiler, Fed. Rep. of Germany, assignors to SKF Kugellagerfabriken GmbH, Schweinfurt, Fed. Rep. of Germany


Filed Dec. 10, 1979, Ser. No. 101,647

Claims priority, application Fed. Rep. of Germany, Dec. 21, 1978, 7837851

Int. Cl.³ F16C 17/10

U.S. Cl. 308—37

6 Claims



- 1. A bearing for transmitting radial and axial forces, comprising an inner and an outer bushing, one of said bushings being provided with flanges projecting radially to at least partially embrace the other bushing thus fixing the other bushing therebetween, a sliding annular insert having a U-shaped cross-section of antifriction material being arranged between said bushings, and having annular projections extending axially outward to embrace said flanges of said one of said bushings.

4,296,979

JOURNAL BEARING FOR THE SHAFT OF A WATER PUMP OR THE LIKE

Heinrich Hofmann, and Günther Markfelder, both of Schweinfurt, Fed. Rep. of Germany, assignors to Fag Kugelfischer Georg Schäfer & Co., Schweinfurt, Fed. Rep. of Germany


Filed Feb. 20, 1980, Ser. No. 123,027

Claims priority, application Fed. Rep. of Germany, Feb. 24, 1979, 2907342

Int. Cl.³ F16C 19/49, 19/18, 33/46

U.S. Cl. 308—174

4 Claims



1. In an assembly of a rotatable shaft and a journal bearing therefor,

- the improvement wherein said journal bearing comprises: a sleeve with a cylindrical inner peripheral surface having a first zone with two closely spaced annular track grooves offset from the axial midpoint of the sleeve adjacent one end thereof and a second zone with an annular retaining groove adjacent the other end thereof, said shaft being provided with two closely spaced peripheral track grooves respectively confronting the annular track grooves of said first zone;
- two sets of balls respectively received in said track grooves of said shaft and said sleeve, the balls of each set being respectively engaged by a first and a second cage;
- a set of rollers inserted in said second zone between said shaft and said sleeve; and
- a third cage engaging said rollers, said third cage being provided with a peripheral rib snap-fitted into said retaining groove.

4,296,980

AUTOMATON FOR DEALING OUT FOOD AND DRINK


Tauno K. Takaniemi, Näsälinnankatu 30 B 31, SF-33200 Tampere 20, Finland

Filed Jun. 20, 1979, Ser. No. 50,846

Int. Cl.³ A47F 3/02; B65B 59/00; B65D 83/08

U.S. Cl. 312—35

8 Claims



- 1. An apparatus for dispensing products, comprising: a plurality of product receiving shelf spaces arranged one above the other;
- a door comprising a corresponding plurality of interconnected panels each sized to close one of said product receiving shelf spaces, said door being arranged for movement due to the effects of gravity, downward past said shelf spaces; and
- means for selectively stopping movement of said door

downwardly past said shelf spaces to permit serial removal of products from said shelf spaces.

4,296,981

DESK WITH A CHANNEL FOR RECEIVING CABLES, WIRES ETC.

Norbert Hildebrandt, Grüner Winkel 32, 4782 Erwitte 1; Norbert Becker, Weringhauser Str. 15, 4782 Erwitte 2; Rolf Walter, Jügergasse 1, 6302 Lich 4, and Manfred Hoffman, Bahnhofstrasse 23, 6305 Grossen Buseck I, all of Fed. Rep. of Germany


Filed Oct. 22, 1979, Ser. No. 87,179

Claims priority, application Fed. Rep. of Germany, Oct. 21, 1978, 7831436

Int. Cl.³ A47B 13/02, 77/08

U.S. Cl. 312—194

13 Claims



1. In a desk having a first channel which extends directly below and parallel to the table top of the desk at the back side of the desk, which channel can be pulled out from and is guided in the desk, which channel is of U- or L-shaped cross section for receiving cables and wires, the outer leg of which channel is in alignment, in its retracted condition, with the desk wall and has openings for facilitating an exiting of cables and wires, the improvement comprised in that said first channel opens upwardly and in its retracted condition is closed by said table top, at least on one end of said first channel there is secured a further channel which extends vertically downwardly from the horizontally extending first channel, said further channel being movable with said first channel, said further channel being movable into a recess in a base of the desk, said further channel being open to said horizontally extending first channel, and including webs extending longitudinally in and subdividing both channels.

4,296,982

KNOCK-DOWN CABINET ASSEMBLY

Jan O. Kullander, Sjöfle, Sweden, assignor to Aktiebolaget Electrolux, Stockholm, Sweden

Filed Nov. 14, 1979, Ser. No. 94,346

Claims priority, application Sweden, Apr. 9, 1979, 7903120


Int. Cl.³ A47B 43/00; A47F 5/00

U.S. Cl. 312—257 R

5 Claims

1. A cabinet having a top work surface comprising: a rear wall and two side walls, the adjacent edges of said rear and side walls having bent portions which upon abutment and pivoting hook one another to form a joint which prevents separation of said side walls and rear wall, a frame-shaped front wall having vertical posts adapted to snap over to join said front wall to said side walls to thereby form a box-like structure, the upper portions of both of said side walls and rear wall having inwardly directed horizontal portions, a top part having three edges bent back on itself in a reverse direction and terminating in an oppositely directed bent portion forming outwardly directed grooves between said bent back portion and said oppositely directed bent part, said grooves being adapted to engage with said inwardly directed horizontal portions, and wherein said top part is a flat plate forming a work surface, said upper parts of said side walls each being provided with a

horizontal portion upon which the grooves of said top part are slid, and an additional part above said horizontal portion in the form of a triangular surface which forms an edge portion



projecting above the top surface of said top part, and whose height increases in a direction toward the rear wall of said cabinet.

4,296,983

EDGE JOINT FOR SHEETS

Stanley J. C. Rogers, Gravesend, and John F. Taplin, Thornton Heath, both of England, assignors to Vickers Limited, London, England


Filed Aug. 29, 1979, Ser. No. 70,714

Claims priority, application United Kingdom, Aug. 31, 1978, 35230/78

Int. Cl.³ A47B 47/02

U.S. Cl. 312—263

11 Claims



1. A locking means for joining a pair of sheets together to form a corner comprising:

a first rigid planar portion connected at one end thereof directly to a first sheet of the pair of sheets to form a corner with that first sheet;

a first rigid hook member including a second planar portion connected at one end thereof to another end of said first planar portion and extending in the direction of the first sheet and a hook forming portion connected to said second planar portion to open toward the first sheet;

a second rigid hook member including a first planar segment connected at one end thereof directly to a first edge of the second sheet of the pair of sheets and extending away from that second hook, a hook forming segment connected to said first planar segment to open toward said first planar segment;

said hook forming portion receiving said hook forming segment and interlocking the sheets together with said second sheet first edge being immediately adjacent said first planar portion another end to form a joint between the two sheets which is located at a location spaced from the corner a distance corresponding to the length of said first planar portion and in a manner such that said first planar portion is coplanar with the second sheet, the

sheets being interlockable by superposing said first hook member over said second member with said second planar portion behind said first planar segment and with the edges thereof spaced slightly apart and relatively rotating the sheets to a fully interlocked position defined by abutment of such edges.

4,296,985

INTEGRAL ELECTRICAL CONTACT AND METHOD OF MAKING SAME


James J. Karol, Unadilla; Richard W. Normann, Otego, and Lloyd C. Hotchkiss, Downsville, all of N.Y., assignors to The Bendix Corporation, Southfield, Mich.

Filed Oct. 9, 1979, Ser. No. 82,440

Int. Cl.³ H01R 43/12, 43/14

U.S. Cl. 339—48

20 Claims



4,296,984

CABINET STORAGE CONVEYOR

John C. Lehman, Marietta, Pa., assignor to John C. Lehman, Inc., Lancaster, Pa.


Continuation-in-part of Ser. No. 883,294, Mar. 3, 1978. This application Nov. 6, 1979, Ser. No. 91,392

The portion of the term of this patent subsequent to Mar. 4, 1997, has been disclaimed.

Int. Cl.³ B65G 1/12; A47B 49/00

U.S. Cl. 312—268

7 Claims



1. A modular preassembled article storage and transport conveyor apparatus comprising a substantially rigid unitized support housing having at least one access opening in a side thereof, a pair of endless conveyor chains forming arcuate curved portions at opposite ends in offset relationship and disposed in laterally spaced parallel planes, each chain having multiple articulated links, plural spaced article storage and transport trays suspended at diagonally opposite corners in level relationship from said chains, said trays adapted to pass in succession adjacent to said at least one access opening of the housing, fixed guide track means for said chains on said housing and defining continuous substantially uninterrupted guidance paths for the endless chains along their entire movement paths, said fixed guide track means including arcuate support and guide portions for said arcuate curved portions of said chains and disposed interiorly of said chains, and power drive means for said chains on said housing including a pair of sprocket gears respectively in operative engagement with the exteriors of said pair of chains away from said arcuate support and guide portions and at a fixed point on the arcuate curved portion of each chain that face each other.

4,296,986

HIGH VOLTAGE HERMETICALLY SEALED CONNECTOR


Henry O. Herrmann, Jr., Mt. Joy, Pa., assignor to AMP Incorporated, Harrisburg, Pa.

Filed Jun. 18, 1979, Ser. No. 49,770

Int. Cl.³ H01R 13/62, 14/648

U.S. Cl. 339—89 C

7 Claims



1. In a high voltage connector for terminating coaxial cable, of the connector type including an elastomeric plug member having a frustoconical profiled forward portion having first contact means therein connected to a cable center conductor; a receptacle member having a blind bore of complementarily tapered profile in a forward face for receiving the plug forward portion therein and second contact means in said bore mateable with said first contact means; and means for pressurizing the plug member against a rearward wall within the receptacle bore, the improvement comprising:

said plug member having a rearward portion connected to a metallic outer shield of the cable, and an integral annular flange portion between said forward and rearward plug

portions having frontwardly, rearwardly, and outwardly facing surfaces, and said plug member having conductive coating means over said plug rearward portion and over said flange rearwardly and outwardly facing surfaces; conductive collar means peripherally secured to a forward end of said receptacle member and having a flared portion diverging outwardly from said forward receptacle face, said plug flange being normally displaced from said receptacle forward face and said flared collar portion upon insertion of said plug forward portion into said receptacle bore; said pressuring means engaging against said plug flange rearward surface and axially pressing said plug member against said receptacle rearward wall, whereby, said forward plug portion flexes outwardly to conform to the interior dimension and profile of said receptacle bore, and, upon continued application of said pressuring means, said plug flange is compressed against said receptacle forward face, and influences said outward plug flange surface progressively into engagement against said flared collar portion.

4,296,987

PRESSURE LOCK TERMINAL


Bhartoor Lingaraju, Allentown, Pa., assignor to Square D Company, Palatine, Ill.

Filed Oct. 23, 1979, Ser. No. 87,369

Int. Cl.³ H01R 4/26

U.S. Cl. 339—95 D

2 Claims



1. An improved electrical conductive double action pressure lock terminal assembly for use with an electrical wiring device capable of holding various diameter sized conductors, said pressure lock terminal assembly comprising:

- an electrically non-conductive base;
- an electrically conductive contact strip supported by said base, said contact strip having a main section with at least one jaw section extending from the end of said main section;
- an electrically conductive double action pressure lock attached to and extending at a right angle from said main section such that said double action pressure lock is positioned a predetermined distance beneath said jaw section of said contact strip, said double action pressure lock comprising:
- a spring support having a first and second end and an elongated interior opening, said spring support being attached to said contact strip along a predetermined portion of a first side of said spring support,
- a spring arm having a first and second end, said first end of said spring arm being attached to said first end of said spring support, said spring arm lying within said interior

opening of said spring support, and said second end being free, a cavity stop means in said base, said stop means being positioned a predetermined distance beneath said first end of said spring support of said double action pressure lock;

whereby, when a conductor is inserted in said pressure lock assembly the conductor contacts said second end of said spring arm, causing said second end of said spring arm to deflect upward and in turn causing said first end of said spring arm and a portion of said spring support near said first end of said spring arm to contact said jaw section of said contact strip,

thereafter, as the conductor is inserted further into said pressure lock terminal assembly, said second end of said spring arm continues to deflect upward and said first end of said spring support rotates downward about said jaw section and eventually contacts said cavity stop in said base, thereby resulting in said second free end of said spring arm deflecting a greater amount than said first end of said spring arm, said deflections of said first and second ends of said spring arm resulting in a double action.

4,296,988

CONNECTOR WITH IMPROVED TERMINAL SUPPORT


Gary N. Warner, Harrisburg, Pa., assignor to AMP Incorporated, Harrisburg, Pa.

Filed Feb. 20, 1980, Ser. No. 122,932

Int. Cl.³ H01R 11/20

U.S. Cl. 339—97 R

5 Claims



1. A pre-loaded electrical connector of the type comprising an insulating housing having a wire-receiving face and a cavity extending inwardly from said wire-receiving face, a wire admitting opening in said housing communicating with said cavity, said opening extending from said wire-receiving face partially along one external sidewall of said housing, said cavity having opposed internal endwalls extending normally of said one external sidewall, and an electrical contact terminal in said cavity, said terminal having wire-receiving means proximate to said wire-receiving face, said connector being characterized in that:

said wire-receiving means comprises at least one plate-like member disposed in said cavity at a location proximate to said wire-receiving face, said plate-like member being in a plane which extends substantially normally of said opposed internal endwalls and having an outer end which is proximate to said one external sidewall of said housing, a wire-receiving slot in said plate-like member extending inwardly from said outer end, each of said opposed internal endwalls of said cavity having a supporting shoulder which is in a plane generally parallel to the plane of said one external sidewall, each said shoulder extending from said wire-receiving face into said cavity to said plate-like member, said wire-receiving means having integral supporting projections extending laterally outwardly therefrom proximate

mate said external sidewall and overlapping said shoulders, said terminal having been axially inserted into said cavity from said wire-receiving face whereby, upon locating a wire with its axis beside said one external sidewall in alignment with said wire admitting opening, and upon movement of said wire laterally of its axis, into said wire admitting opening and into said wire-receiving slot, said plate-like member is supported by said integral supporting projections and said member is stressed in tension.

4,296,989

MULTI-CONDUCTOR FLAT CABLE CONNECTOR


Roderick W. Larson, Hudson, Wis., and Ralph D. Whaley, Roseville, Minn., assignors to Minnesota Mining and Manufacturing Company, St. Paul, Minn.

Continuation-in-part of Ser. No. 44,909, Jun. 4, 1979, abandoned. This application Mar. 24, 1980, Ser. No. 128,527

Int. Cl.³ H01R 11/20

U.S. Cl. 339—99 R

8 Claims



1. A multi-conductor flat cable connector comprising:
 - a base carrying a plurality of insulation stripping contact elements which extend from one surface of said base for making electrical connection to conductors of a said flat cable, said base being formed centrally at each end with a generally rectangular cover guide extending perpendicularly from said one surface,
 - a cover on said base formed at its ends to slidably mate with said cover guides on said base,
 - latching means on said cover including a pair of resilient metal latching legs, one extending from each end of said cover,
 - means for latching said latching legs to said base in an open position permitting a said flat cable to be inserted between said cover and said contact elements and for latching said latching legs to said base in a closed position whereat conductors of a said cable are connected by said contact elements, and
 - a pair of shearable latch stops, one at each end of said base, positioned to be contacted by portions of said latching legs when said connector is in an open position and shearable by said latching legs when said base and cover are forced together to move them to their closed position carrying the conductors of a said cable into said contact elements.

4,296,990

ELECTRICAL CONNECTOR HAVING INSULATED LOCKING SHELL FOR USE ON PANEL HAVING METAL GROUND PLANE

Jeffery P. Stowers, Mt. Sidney, and Kimball E. Stowers, Ft. Defiance, both of Va., assignors to Virginia Panel Corporation, Waynesboro, Va.

Filed Feb. 22, 1980, Ser. No. 123,894


Int. Cl.³ H01R 13/627

U.S. Cl. 339—128

4 Claims

1. An electrical connector for making a connection through a support panel having a metallic layer thereon and having an aperture formed entirely therethrough, said connection being between a conductor spaced from one side of the panel and a

circuit element spaced from the other side thereof, said connector comprising a holding shell formed of insulating material and adapted for placement through said aperture of the panel and metallic layer with opposite end portions of the shell projecting beyond the opposite faces of the panel and metallic layer, said shell having a cross slot in one end thereof forming two yielding jaws, camming enlargements on said jaws including oppositely tapering faces engageable with the entrances of the aperture to collapse the jaws toward each other to enable inserting the shell through said aperture and withdrawing the shell therefrom, said shell being hollow, a spring contact probe snugly engaged within the shell and including a spring-biased



4,296,991

ELECTRICAL CONNECTOR RECEPTACLE


Donald W. K. Hughes, Mechanicsburg, and Ronald W. Myers, Landisburg, both of Pa., assignors to AMP Incorporated, Harrisburg, Pa.

Continuation-in-part of Ser. No. 940,536, Sep. 8, 1978, Pat. No. 4,221,458. This application Dec. 10, 1979, Ser. No. 101,676

Int. Cl.³ H01R 13/50

U.S. Cl. 339—176 MP

4 Claims



1. An electrical connector receptacle of the type comprising an insulating housing having a plug-receiving end and a rearward end, a plug-receiving opening extending into said plug-receiving end, said opening having opposed first and second internal sidewalls and opposed internal endwalls, said housing having oppositely directed first and second external sidewalls, which are proximate to said first and second internal sidewalls respectively, and opposed external endwalls, a plurality of

spaced-apart side-by-side conductors, each of said conductors having a contact spring portion which extends from said first internal sidewall at a location adjacent to said plug-receiving end diagonally into said opening and towards said rearward end, said connector receptacle being characterized in that:

each of said conductors comprises a one-piece stamped and formed sheet metal member,
said first external sidewall has a plurality of side-by-side conductor-receiving channel means therein extending from said location adjacent to said plug-receiving end to said rearward end, every other said channel means being of increasing depth along its length from said location to said rearward end, the remaining channel means being of decreasing depth along their length whereby said channel means are alternately deep and shallow at said rearward end,
intermediate portions of said conductors being in said channel means, said conductors having reverse bends at said location and extending diagonally toward first end portions in said opening, second end portions of said conductors extending normally of, and beyond, said rearward end whereby,

said contact springs are formed between said reverse bends and said first end portions, and said second end portions of adjacent conductors are offset from each other and can be inserted into holes in a circuit board which are on staggered centers.

4,296,992

ELECTRICAL CONNECTOR ASSEMBLY


David A. Gallagher, Romeoville, Ill., assignor to Bunker Ramo Corporation, Oak Brook, Ill.

Continuation-in-part of Ser. No. 836,325, Sep. 26, 1977, Pat. No. 4,154,496. This application Apr. 9, 1979, Ser. No. 28,156

Int. Cl.³ H01R 13/506

U.S. Cl. 339—186 M

16 Claims



1. A connector assembly comprising:

- a shell;
- an elastomeric insert member for supporting at least one electrical contact;
- a retaining ring comprising at least two portions which may be opened to receive said insert and closed to permit insertion of said ring and insert member into said shell, said ring including retention means for engaging and maintaining said insert member in fixed position within said ring and a plurality of radially movable axially extending arms for engaging said shell to maintain said ring and insert member in fixed axial position within said shell; and
- a passageway providing access to said axially extending arms to permit disengagement of said ring and insert member from said shell.

4,296,993

ELECTRICAL CONTACT WITH IMPROVED MEANS FOR SOLDER WICKING AND DEGASSING

Roger D. Wellington, Cumberland, R.I., assignor to Augat Inc., Attleboro, Mass.

Continuation of Ser. No. 936,485, Aug. 24, 1978, Pat. No. 4,236,776. This application Jan. 7, 1980, Ser. No. 109,850

Int. Cl.³ H01R 9/06

U.S. Cl. 339—275 B

6 Claims



1. A contact adapted to be soldered in a cylindrical plated-through hole in an interconnection board so as to facilitate solder wicking and degassing when so soldered, said contact comprising:

- a cylindrical body, larger in diameter than said plated-through hole;
 - an elongated pin axially projecting from one end of and being substantially smaller in cross section than said cylindrical body;
 - a conical transitional surface connecting said cylindrical body and said pin; and
 - a plurality of ribs substantially parallel to and projecting outwardly from said transitional surface;
- whereby when said contact is mounted in said plated-through hole with said pin projecting thereinto, said ribs make surface contact with the rim of said plated-through hole thereby spacing said transitional surface from said rim and providing escape paths for gases between said ribs and between said transitional surface and said rim.

4,296,994

METHOD AND APPARATUS FOR HOLOGRAPHIC PROCESSING

William H. Quick, La Habra Heights; Kenneth A. James, Corona Del Mar, and Virgil H. Strahan, Orange, all of Calif., assignors to Rockwell International Corporation, El Segundo, Calif.

Filed Jan. 22, 1979, Ser. No. 5,619


Int. Cl.³ G02B 5/32

U.S. Cl. 350—3.73

22 Claims

1. A method of reporting the status of a physical parameter to a receiving station, the method comprising the steps of:
- sensing said physical parameter;
 - supplying a first beam of light and varying the spectral wavelength distribution of said light beam as a function of the status of said parameter being sensed;
 - applying said spectrally-varied beam of light to a hologram for focusing responsive beams of light on an image plane at predetermined points, the locations of said points being responsive to an encoded signal that is dependent upon the spectral distribution of said beam of light; and

transferring said encoded signal to said receiving station by inputting said responsive beams of light to a light transmiss-



sion means having one end at said image plane and having another end at said receiving station.

4,296,995

OPTICAL FIBER BEAM SPLITTER COUPLERS EMPLOYING COATINGS WITH DICHROIC PROPERTIES


Gary W. Bickel, Roanoke, Va., assignor to International Telephone and Telegraph Corporation, New York, N.Y.

Filed Feb. 1, 1980, Ser. No. 117,425

Int. Cl.³ G02B 5/172

U.S. Cl. 350—96.15

10 Claims



1. An optical coupling device comprising:

- a first optical layer having a front surface at a given angle, and having deposited directly thereon by an evaporation technique a plurality of relatively thin layers in excess of ten such layers of a material with dichroic properties capable of reflecting a first beam of light of a first frequency propagating in said fiber, and transmitting a second beam of light of a second frequency propagating in said first optical fiber,
- a second optical fiber having a front surface at said given angle and adjacent said front surface of said first fiber to form an interface between said first and second surfaces to enable transmitted light at said second frequency to propagate within said second fiber with said second fiber receiving at least 80% of said light at said second frequency, and optical means positioned relatively transverse to said interface and adapted to solely receive reflected light at said first frequency from said interface as reflected by said thin layer with said optical means receiving at least 70% of said reflected light at said first frequency.

4,296,996

FEEDTHROUGH FOR OPTICAL FIBER

Yasuhiko Niino, Yokohama; Kahei Furusawa, Kamifukuoka, and Akira Okada, Tokyo, all of Japan, assignors to Kokusai Den-shin Denwa Kabushiki Kaisha, Tokyo, Japan


Filed Jul. 17, 1979, Ser. No. 58,251

Claims priority, application Japan, Jul. 18, 1978, 53-86734

Int. Cl.³ G02B 7/26

U.S. Cl. 350—96.20

3 Claims



1. In a submarine repeater, a pressure-resisting solid container having a feed-through opening for receiving an optical fiber, an optical fiber extending longitudinally through said opening, a sealing thermoplastic material filling space between the fiber and inner surfaces of said through opening in said pressure-resisting solid container, said optical fiber having a metallic film coating circumferentially and longitudinally thereon in close contact with said sealing thermoplastic material to ensure a seal having resistance to high fluid pressure and airtightness between the optical fiber and said thermoplastic material, said metallic film coating having an oxide film thereon to provide enhanced sealing close contact between the metallic film coating and the thermoplastic material.

4,296,997

DEVICE FOR CENTERING AN OPTICAL FIBER WITHIN A TERMINAL, AND A TERMINAL CONSTRUCTED BY MEANS OF SAID DEVICE

Christian Malsot, and Jean Bouygues, both of Suresnes, France, assignors to Socapex, Suresnes, France


Filed Oct. 25, 1979, Ser. No. 88,458

Claims priority, application France, Oct. 31, 1978, 78 30849

Int. Cl.³ G02B 7/26

U.S. Cl. 350—96.20

7 Claims



1. A device for centering an optical fiber within a connector terminal comprising:

- a reference dihedron block having two faces, fabricated from a rigid material, one end thereof being adapted to receive the terminal;
- a centering assembly adapted to be received by the other end of the reference dihedron block, including two packing blocks of equal thickness, each such block being applied against a face of the reference dihedron block, and
- two cylinders, each having a diameter equal to 2.421 times the diameter of the optical fiber in the case of a right dihedron, the cylinders being tangent to each other and to the faces of the dihedron block.

to at least one packing block, one of the cylinders being tangent to both packing blocks; the centering assembly operating to position the optical fiber in the plane bisecting the dihedral angle defined by the faces of the reference dihedron block in a direction parallel to the edge of the dihedron block.


4,296,998

ENCAPSULATED LIGHT SOURCE WITH COUPLED FIBERGUIDE

William H. Dufft, Shillington, Pa., assignor to Bell Telephone Laboratories, Incorporated, Murray Hill, N.J.
Filed Dec. 17, 1979, Ser. No. 104,364
Int. Cl.³ G02B 7/26

U.S. Cl. 350—96.20

4 Claims



1. An encapsulated light source comprising a housing having walls, light generating means in the housing comprising a semiconductor light emitting device having a light output face, light transmitting means comprising a fiberguide penetrating a wall of the housing for transmitting light from the light emitting device to the exterior of the housing, a pedestal member within the housing having a top surface adjoining the light output face of the light emitting device, an unhoused body of low melting metal mounted on the top surface of the pedestal, the metal body having a portion of the fiberguide embedded therethrough to lock the fiberguide in position relative to the light output from the light emitting device.


4,296,999

OPTICAL FIBRE CONNECTORS

John F. Mead, Princes Risborough, England, assignor to Plessey Handel und Investments AG, Zug, Switzerland
Filed Oct. 23, 1979, Ser. No. 87,529
Int. Cl.³ G02B 7/26

U.S. Cl. 350—96.21

12 Claims



1. An optical connector for the end of an optical fibre, comprising:
a hollow cylinder adapted to be secured to the end of said optical fibre;
an elongate housing assembly axially slidably mounted on

said hollow cylinder and being intimately in contact therewith;
a main body secured to said hollow cylinder and also surrounding said elongate housing assembly, wherein said elongate housing assembly is axially slidable between said hollow cylinder and said main body; and
actuating means extending from said elongate housing assembly through said main body for enabling movement to be imparted to said elongate housing assembly externally of said main body;
said optical connector being adapted to be mated to a further identical connector secured to the end of a further optical fibre having a hollow cylinder and a main body, with the ends of said hollow cylinders and said main bodies of respective said optical connector and said further optical connector abutting, and said elongate housing assembly moved axially to project within the main body of said further optical connector and to abut the elongate housing assembly thereof and to span the abutting ends of said hollow cylinders and said main bodies.

4,297,000

SOLAR LIGHTING SYSTEM


James E. Fries, 7860 Valley View, Apt. 242, Buena Park, Calif. 90620

Filed Jan. 11, 1979, Ser. No. 2,620

Int. Cl.³ G02B 5/16

U.S. Cl. 350—96.24

12 Claims



10. A lighting system employing solar light energy comprising:
a collector device in the form of a dish having an aperture in the center thereof, a parabolic reflective surface on one side thereof,
a fiber optical cable formed from a plurality of optical fiber lines joined together into a bundle,
ring holder means for holding one end of said fiber optical bundle together,
support means for supporting said collector device for rotatable movement about a predetermined axis,
means for supporting said ring holder means on said collector device for movement therewith with said one end of said cable on the opposite side of said collector device and facing directly opposite said aperture, the one end of the fiber optical bundle held by the ring holder means moving along with the collector device to maintain said one end of said cable facing directly opposite said aperture,
a convex mirror,
means for supporting said convex mirror on said collector device on said one side thereof approximately at the parabolic focal distance from said parabolic surface,
light utilization means,
means for coupling the other end of said cable to said light utilization means, and
means for slewing said collector device about said predeter-

mined axis so as to maintain said collector device directed at the sun,
whereby the sun's rays are focused on said convex mirror by said parabolic surface, said convex mirror directing the focused rays onto said one end of said fiber optical cable and transmitted to said light utilization means.

4,297,001

PROJECTION SCREEN AND METHOD FOR MAKING SAME

Gregor Antes, Zurich, and David L. Greenaway, Oberwil, both of Switzerland, assignors to LGZ Landis & Gyr Zug AG, Zug, Switzerland

Continuation of Ser. No. 852,089, Nov. 16, 1977, abandoned.

This application Nov. 16, 1979, Ser. No. 95,097

Claims priority, application Switzerland, Nov. 16, 1976, 14379/76

Int. Cl.³ G03B 21/60

U.S. Cl. 350—129

22 Claims



1. In a method of producing an optical projection screen on a body,
the steps comprising:
forming a plurality of adjacent randomly distributed and irregularly sized micro-structural bubble-shaped elements on one major curved surface of said body, said bubble-shaped elements having a predetermined range of angles of inclination with respect to at least one direction tangent to said surface, and
limiting said predetermined range of angles of inclination by stretching said body by a first incremental length in said one direction, so that in an operative position of said screen light operatively incident on said screen is scattered therefrom in a predetermined plane at an angle to said surface and including said one direction within a selectable first scattering angle, said first scattering angle being at least partially dependent on said first incremental length.

4,297,002

ARRANGEMENT OF CYLINDER ELEMENTS FOR A LENS BARREL

Tsuneyo Meatabi, Sakai, Japan, assignor to Minolta Camera Kabushiki Kaisha, Osaka, Japan

Continuation of Ser. No. 6,973, Jan. 26, 1979, which is a continuation-in-part of Ser. No. 1,796, Jan. 8, 1979. This application May 13, 1980, Ser. No. 149,359

Claims priority, application Japan, Jan. 31, 1978, 53-8881


Int. Cl.³ G02B 7/02; G03B 3/00

U.S. Cl. 350—255

17 Claims

1. An arrangement of cylinder elements for a lens barrel comprising:
an externally accessible outer cylinder element made of plastic material and having a central axis, an annular ridge carried on an inner peripheral surface of said outer cylinder element;
an inner cylinder element carried within said outer cylinder element;
an annular member being separate and independent from said outer and inner cylinder elements and being attachable to said annular ridge with an axis of said annular

member being coincident with the central axis of said outer cylinder element, said annular member being made of a material which is stronger than said plastic material; and



means for fixedly attaching said annular member to said annular ridge with the axis of said annular member being coincident with the central axis of said outer cylinder element.

4,297,003

SOLAR COLLECTOR MODULE


Joseph A. Hutchison, Dallas, Tex., assignor to Solar Kinetics, Inc., Dallas, Tex.

Filed Oct. 19, 1979, Ser. No. 86,314

Int. Cl.³ G02B 5/10

U.S. Cl. 350—292

21 Claims



1. A parabolic trough solar collector comprising: at least two collector modules, means rigidly connecting said modules together, each of said modules comprising at least two end skin members each having a front surface and a rear surface, said front surface of each of said end skin members being formed in a portion of a parabola; a rear stressed sheet metal skin rigidly affixed to at least a portion of said rear surface of each of said end skin members; a front stressed sheet metal skin rigidly affixed to at least a portion of said front surface of each of said end skin members; and a reflective surface on said front stressed sheet metal skin, said reflective surface being adapted to reflect solar radiation.

4,297,004

LIQUID CRYSTAL DISPLAY CELL

Katsuo Nishimura, and Takanori Nanya, both of Tokorozawa, Japan, assignors to Technical Research of Citizen Watch Co., Ltd., Tokorozawa, Japan

Filed Sep. 17, 1979, Ser. No. 76,189

Claims priority, application Japan, Sep. 20, 1978, 53-114487; Oct. 26, 1978, 53-132029


Int. Cl.³ G02F 1/133

U.S. Cl. 350—336

10 Claims

1. In a liquid crystal display cell composed of two transparent supporting substrates arranged parallel to one another, sealed together peripherally to form an enclosed chamber containing a liquid crystal material, and having a transparent display electrode formed on an inner face of at least one of said transparent supporting substrates composed of a thin film of an

electrically conductive substance and a lead electrode provided on said inner substrate face for providing electrical connection between said transparent display electrode and external drive means, the improvement comprising a multi-layer construction for said lead electrode for thereby reducing the electrical resistance thereof, said multi-layer lead electrode



construction comprising a metallic electrode layer of a metallic substance formed on said inner substrate face and a lead electrode layer formed over said metallic electrode layer, said lead electrode layer being formed integrally with said display electrode and having a width which is substantially equal to the width of said metallic electrode layer, measured in a direction parallel to the substrate plane.

4,297,005

PERSISTENT MEMORY CELL


David W. Johnson, Jr., Pluckemin; Shobha Singh, Summit; LeGrand G. Van Uiter, Morristown, and George J. Zyzdik, Columbia, all of N.J., assignors to Bell Telephone Laboratories, Incorporated, Murray Hill, N.J.

Filed Jun. 25, 1979, Ser. No. 51,807

Int. Cl.³ G02F 1/17

U.S. Cl. 350—357

45 Claims



1. An electrochemical display device comprising:
 - (a) first and second electrodes;
 - (b) electrochemical solution in contact with the first and the second electrodes;
 - (c) said electrochemical solution comprising:
 - i. organic quinone which changes color under the influence of an electrical signal,
 - ii. electrolyte,
 - iii. organic solvent capable of dissolving said organic quinone;
 - (d) characterized in that a solid cation ionic conductor separates the device into two cavities, each with its own electrode, one comprising the first electrode and the other comprising the second electrode and the two cavities are at least partially filled with said electrochemical solution.


4,297,006 PROTECTIVE MEMBRANE FOR ELECTROCHROMIC DISPLAYS

Saadi J. Bissar, Waterbury, Conn., assignor to Timex Corporation, Waterbury, Conn.

Continuation-in-part of Ser. No. 973,833, Dec. 28, 1978, abandoned. This application Sep. 21, 1979, Ser. No. 77,863
Int. Cl.³ G02F 1/17

U.S. Cl. 350—357

25 Claims



1. An electrochromic display having a display electrode with an electrochromic layer thereon, a counter electrode spaced from the display electrode and display electrolyte between the electrochromic layer and counter electrode, characterized in that a protective membrane is interposed between the electrochromic layer and electrolyte for protecting the layer from erosion resulting from contact with the electrolyte, said membrane comprising a mixture of:
 - (a) a long chain organic acid; and
 - (b) a compound selected from at least one of amine and amide present in an effective amount to form a salt with the organic acid imparting water repellency and ionic conductivity to said membrane for minimizing contact between said electrochromic layer and electrolyte while maintaining ionic conductivity therebetween for display purposes.

4,297,007

OPTICAL APPARATUS AND METHOD FOR CHANGING A ZOOM CAMERA TO A FIXED FOCUS CAMERA


R. Calvin Owen, Jr., Belmont, Mass., assignor to Polaroid Corporation, Cambridge, Mass.

Filed Apr. 24, 1979, Ser. No. 32,969

Int. Cl.³ G02B 3/04, 9/60, 15/14

U.S. Cl. 350—432

8 Claims



1. In combination with a fixed-focus, four-element air spaced lens having the following characteristics

Lens	n_d	V	Radii (in.)	Thickness (in.)
I	1.6911	54.8	$R_1 = .614$ $R_2 = -1.245$ $R_3 = -.450$ $R_4 = .48$	$t_1 = .126$ $s_1 = .133$ $t_2 = .040$ $s_2 = .023$
II	1.7508	27.8	$R_5 = -2.0187$ $R_6 = -0.5755$	$t_3 = .100$ $s_3 = .005$

-continued

Lens	n_d	V	Radii (in.)	Thickness (in.)
IV	1.6111	58.8	$R_7 = 0.599$ $R_8 = -0.5564$	$t_4 = .128$

wherein Roman numerals identify lens elements from front to rear; n_d is the refractive index; V is the Abbe number; $R_1, R_2, \dots$ represent radii of successive refractive surfaces from front to rear; and t and s represent thickness of lens elements and air spaces respectively, an improvement comprising:

an aspheric corrector plate spaced ahead of element I of the four element lens by a predetermined distance, having an index of refraction, n_d , of 1.492, and Abbe V-number of 57.2, a plano front surface, and a concave rotationally symmetric aspheric rear surface facing element I and given by:

$$Z = 0.170171y^4 + 1.47874y^6$$

where Z is the height of the asphere along the optical axis, measured from a reference plane tangent to its vertex and perpendicular to the axis and Y is the radial distance of the aspheric surface from the optical axis.

4,297,008

METHOD AND APPARATUS FOR MAKING A NON SPHERICAL BEVELED CONTACT LENS


Donald L. Woodford, 9925 Broadmoor Dr., Omaha, Nebr. 68114

Filed Jan. 16, 1979, Ser. No. 3,833

Int. Cl.³ B24B 9/14; G02C 7/04

U.S. Cl. 351—177

5 Claims



1. A method of producing a non-spherical bevel on the posterior surface of a contact lens comprising the steps of:
 - providing a rotatably mounted working surface having a central axis about which said working surface is symmetrical, said working surface further having a smooth three-dimensional curvilinear surface configuration generated by the rotation of an S-shaped curve produced by the circumferential arcs of two tantential conic-section curves about said central axis;
 - providing an abrasive material on said working surface;
 - rotating said working surface about said central axis; and
 - bringing the posterior surface of the contact lens into contact with said working surface to selectively abrade away portions of the posterior peripheral surface thereof.

4,297,009

IMAGE STORAGE AND DISPLAY

Reuben S. Mezrich, Miami, Fla.; Alec Colleoni, New Brunswick, and David J. Lyons, Trenton, both of N.J., assignors to Technicare Corporation, Solon, Ohio

Filed Jan. 11, 1980, Ser. No. 111,512

Int. Cl.³ G03B 21/32


U.S. Cl. 352—86

9 Claims

1. In a system employing a rotatable, disk-type phototransparency record of a plurality of sequentially associated images, said disk having said plurality of images sequentially, circumferentially disposed about a center of rotation, each image

having a respectively associated reference timing indicium on said disk, a system for displaying said images comprising:

- (a) a projection system for selectively, intermittently illuminating a zone of said disk through which said images pass upon disk rotation;
- (b) means for displaying images on said disk which are so illuminated;
- (c) means for sensing the rate of disk rotation and the position of specific ones of said images thereon by detecting movement of said indicia past a given point;
- (d) means, responsive to said means for sensing, for generating a first pulse signal representative of frequency of said



- detected movement, and a second pulse signal representative of full disk rotations;
- (e) first counter means, incremented by said first pulse signal and reset by said second pulse signal, for developing a first count;
- (f) second counter means incremented by select pulses of said second pulse signal, for developing a second count; and
- (g) comparator means, responsive to said first and second counter means, for energizing said projection system to illuminate a given number of next occurring images in said zone, after said first count equals said second count.

4,297,010

SLIDE TRAY PROTECTOR


Robert P. Koehler, 653 O'Dell St., Madison, Wis. 53711

Filed Dec. 31, 1979, Ser. No. 108,780

Int. Cl.³ G03B 23/06, 21/14

U.S. Cl. 353—122

6 Claims



1. A dirt excluding cover for use with a slide tray that cooperates with a projector which has a cooling air propelling fan in it, the slide tray comprising a generally cylindrical body, a plurality of axially and radially extending circularly arranged spaced apart separator walls on the body defining slide receiving slots in the tray, a locking member having a cylindrical portion selectively engageable and disengageable with said body concentrically with said circular arranged partition walls, said locking member having a radially outwardly ex-

tending flange for overhanging radially inward portions of said partition walls to retain slides in the slots of said tray, said cover comprising:

a disk composed of non-metallic material having a radial dimension from its center to its outer circular edge substantially equal to the radial extent of said partition walls for said disk to overlay the slots in the tray, said disk having a central opening through which said cylindrical portion of said locking member passes to enable it to engage said tray and to dispose said flange of the locking member over a radially extending portion of said disk to thereby retain said disk superimposed over said slots, said disk material being selected from a class of materials consisting of paper and synthetic resin and the disk being sufficiently thin for it to fit loosely between said flange on the locking member and the separator walls and for it to flex slightly to increase the size of the hot air discharge path between said disk and said slots when said disk is locked by said locking member and said projector is operating.

4,297,011

PHOTOFLASH DEVICE


James R. Adams, Jr., Littleton, Colo., assignor to Rollei of America, Inc., Littleton, Colo.

Filed May 10, 1979, Ser. No. 37,814

Int. Cl.³ G03B 7/16

U.S. Cl. 354—23 D

45 Claims



1. In a photoflash system having a flash device and means for firing the latter to produce light on a subject to be photographed, a display apparatus for visually displaying, prior to flash of the flash device, a maximum distance value representative of the maximum distance from the subject at which a subsequent flash will properly expose the film of an associated camera, comprising:

memory means having a plurality of memory address locations, each of which storing distance display signals representative of a maximum distance value, said memory means being responsive to memory address signals for outputting distance display signals;

ASA input means manually actuable by the photographer for inputting ASA data representative of one of a plurality of ASA film speeds, each of the film speeds representable being a power of two multiple of an ASA film speed, said input means commanding generation of first binary signals representative of the power of two change in ASA of the represented ASA input from an initiated ASA film speed value;

f-number means manually actuable by the photographer for inputting f-number data representative of a camera f-number, said f-number input means commanding generation of second binary signals representative of a change in f-stop positions of the represented f-number input from an initialized f-number value;

arithmetic means for receiving inputs of said first and said

second binary signals, and generating memory address signals for addressing a memory address location in said memory means for commanding output of distance display signals from said memory means, said address location being dependent on the relative change of both the represented ASA and f-number from their respective said initialized values; and

display means responsive to said distance display signals output from said memory means for displaying a maximum distance value representative of the maximum distance at which a subsequent flash will properly expose film of an ASA speed inputted by said ASA input means, of an associated camera set at an f-number inputted by said f-number input means.

4,297,012

EXPOSURE CONTROL ARRANGEMENT FOR PHOTOGRAPHIC CAMERAS

Masaaki Nakai, Nara, Japan, assignor to Minolta Camera Kabushiki Kaisha, Osaka, Japan


Filed Dec. 7, 1979, Ser. No. 101,252

Claims priority, application Japan, Dec. 13, 1978, 53-154841; Dec. 25, 1978, 53-163800

Int. Cl.³ G03B 7/097

U.S. Cl. 354—23 D

8 Claims



1. Digital exposure control arrangement for cameras comprising:

means for measuring light intensity and for generating an analog light measuring signal;

an A-D converter, operatively connected to said light intensity measuring means, for converting said analog light measuring signal into a digital light measuring signal;

means for setting exposure information and for producing exposure information signals;

a microprocessor for controlling camera operation, said microprocessor processing said digital light measuring signal and said exposure information signals to generate a diaphragm aperture control signal;

a diaphragm aperture capable of changing its aperture size; means for generating a changing signal which changes in accordance with the changes in the aperture size of said diaphragm aperture;

means for comparing said changing signal with said diaphragm aperture control signal to generate a detecting signal when said changing signal has a predetermined relationship with said diaphragm aperture control signal, said comparing means being connected to said microprocessor for transmitting said detecting signal thereto, wherein said microprocessor advances into a next step of camera control upon receipt of said detecting signal; and

means directly connected with said comparing means for interrupting said change in aperture size of said diaphragm aperture upon receiving said detecting signal from said comparing means.

4,297,013

COORDINATING CONTROL SYSTEM FOR CAMERA

Masaharu Kawamura, Kawasaki; Masanori Uchidoi, Yokohama; Yoshihiro Shigeta, Tokyo; Yoji Sugiura, and Hiroshi Yamamoto, both of Yokohama, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan


Filed Jan. 28, 1980, Ser. No. 116,314

Claims priority, application Japan, Jan. 31, 1979, 54-10195; Jan. 31, 1979, 54-10196; Jan. 31, 1979, 54-10197

Int. Cl.³ G03B 7/093, 9/62, 17/38

U.S. Cl. 354—23 D

3 Claims



1. A camera having changeover positions for automatic exposure and bulb exposure modes including:

(a) a count switch for the automatic exposure mode arranged to be opened when the shutter is opened;

(b) a bulb switch arranged to be closed when set to the bulb exposure mode, said switch being manually operated;

(c) signal forming means for producing a detection signal when said count switch and said bulb switch are both opened;

(d) a timer for producing a signal after a predetermined time from the initiation of an actuation of release; and

(e) changeover means for selecting the automatic exposure mode and bulb exposure mode, said means rendering the automatic exposure mode effective when the detection signal is applied from said signal forming means until elapse of a predetermined time from the initiation of the release actuation, and rendering the bulb mode effective when the detection signal from the signal forming means is not applied but instead when the signal from the timer is applied.

4,297,014

CAMERA FOCUS DETECTING DEVICE

Kazuo Nakamura, Shiki; Masao Jyojiki, Tsurugashima, and Harumi Aoki, Kiyose, all of Japan, assignors to Asahi Kogaku Kogyo Kabushiki Kaisha, Tokyo, Japan


Filed Feb. 4, 1980, Ser. No. 117,921

Claims priority, application Japan, Feb. 14, 1979, 54-15904

Int. Cl.³ G03B 3/10, 13/18

U.S. Cl. 354—25

9 Claims



6. An automatic focus detecting device comprising: a self-scanning type photoelectric conversion element array; brightness detecting means; focus detecting means; switch means for coupling outputs of photodiode elements of said array in paral-

lel and to said brightness detecting means for a brightness detection operation and alternately in serial fashion to said focus detecting means; and means for varying a scanning frequency of said array in response to an output of said brightness detecting means.

4,297,015

CAMERA AUTOMATIC FOCUS APPARATUS

Toshiaki Matsumoto, Izumisano, and Keisuke Maeda, Sakai, both of Japan, assignors to Minolta Camera Kabushiki Kaisha, Osaka, Japan


Filed Mar. 4, 1980, Ser. No. 127,044

Claims priority, application Japan, Mar. 5, 1979, 54-25840

Int. Cl.³ G03B 7/083, 3/10

U.S. Cl. 354—25

5 Claims



1. Automatic focus mechanism for a camera enabling sequential automatic focus adjustment and exposure operation in response to a shutter release operation, and automatic focus memory adjustment independently of exposure operation at any time prior to shutter release operation, comprising:

a shutter;

a release member movable by shutter release operation;

a range finding means;

a movable member movable from an initial position to a terminal position for operating said range finding means;

a focus memory operating member movable between a neutral position for normal photography and an operative position for focus memory photography;

a locking member adapted to lock said movable member at said initial position and operatively connected to said release member and said focus memory operating member for releasing said movable member either with said release member moved by a given first stroke or with said focus memory operating member moved to said operative position;

an objective;

an objective setting member for setting said objective and biased to follow said movable member upon movement thereof from said initial position to said terminal position; arresting means connected to said range finding means for arresting said objective setting member to set said objective at an optimum focus with respect to an object being viewed by said range finding means;

a shutter actuating member biased to follow said movable member for actuation of said shutter with movement of said movable member from said initial position to said terminal position;

a first arresting member for preventing said shutter actuating member from following said movable member, and also adapted to be engaged by said movable member prior to the terminal position thereof being reached to enable said shutter actuating member to follow said movable member; and

a second arresting member for preventing said shutter actuating member from following said movable member upon the movement thereof from said initial position to said terminal position, and also adapted to be engaged by said

release member when said release member is moved by a given second stroke shorter than said first stroke to enable said shutter actuating member to follow said movable member.



4,297,016
SCANNING SHUTTER BLADE ARRANGEMENT WITH DYNAMIC APERTURES FOR AMBIENT AND FLASH EXPOSURES

Bruce K. Johnson, Andover, and George D. Whiteside, Lexington, both of Mass., assignors to Polaroid Corporation, Cambridge, Mass.

Filed Jul. 7, 1980, Ser. No. 166,970
Int. Cl.³ G03B 7/08

U.S. Cl. 354—27

14 Claims



1. A photographic camera apparatus of the type for use with a source of artificial illumination in either a predominantly ambient scene lighted mode or in a predominantly artificial scene lighted mode and which includes means for mounting photographic film material at a given film plane comprises: a blade mechanism; means for mounting said blade mechanism for displacement along a predetermined path to define a range of differently sized apertures; means for providing a flash fire signal to ignite the source of artificial illumination at a time subsequent to the commencement of an exposure interval; and drive means for displacing said blade mechanism along said predetermined path to define the exposure interval, said blade mechanism and said drive means being cooperatively structured and arranged with respect to each other such that, for the predominantly ambient scene lighted exposures where the ambient scene light is above a select level, said drive means first displaces said blade mechanism from a first closed arrangement wherein it precludes scene light from reaching the film plane toward a second arrangement defining a maximum size aperture in said range of apertures and then displaces said blade mechanism back toward its said first closed arrangement prior to said blade mechanism being displaced beyond a third intermediate arrangement wherein it defines an aperture size substantially less than said maximum aperture size, and such that for the predominantly


artificial scene lighted exposures said drive means first displaces said blade mechanism from its said first arrangement to its said second arrangement at said flash fire signal time and then displaces said blade mechanism back to its said closed arrangement wherein the rate at which said aperture sizes increase immediately prior to said blade mechanism being displaced into its said third arrangement from its said first arrangement is substantially less than the rate at which said aperture sizes increase immediately subsequent to said blade mechanism being displaced away from its said third arrangement toward its said second arrangement.

4,297,017
PHOTOGRAPHIC CAMERA APPARATUS
Zane M. Farmer, Ashburnham, Mass., assignor to Polaroid Corporation, Cambridge, Mass.

Filed Aug. 2, 1979, Ser. No. 63,043
Int. Cl.³ G03B 7/089, 15/05, 29/00

U.S. Cl. 354—34

11 Claims




1. Photographic apparatus for adapting an exposure control system of a self-contained automatic camera for use in photographing an image formed by an optical viewing device with which the camera is mechanically and optically coupled wherein the camera automatic exposure control system is of the type which upon camera actuation begins a photographic cycle during which film exposure commences upon the opening of a shutter and thereafter is terminated by a light sensing system which measures scene brightness and commands the shutter to close upon detection of a predetermined exposure value related to scene brightness and film speed, said apparatus comprising:

means for sensing the brightness of the image formed by the optical viewing device and storing a signal corresponding to the image brightness prior to actuation of the camera; means for precluding ambient light from entering the camera light sensing system so that when the camera is actuated its exposure cycle is initiated and exposure of the film commences and continues so long as the camera light sensing system remains in the dark; and means responsive for sensing said brightness related signal and for providing an exposure parameter related signal and a high intensity light pulse within said light precluding means to cause the camera light sensing system to terminate exposure such that the exposure delivered to the film is appropriate for the film speed and image brightness.

4,297,018
PRINTED CIRCUIT UNIT FOR A CAMERA
Hiroyasu Murakami, Tokyo; Tadashi Ito, and Fumio Ito, both of Kanagawa, all of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan
Continuation of Ser. No. 920,645, Jun. 30, 1978, abandoned, which is a continuation of Ser. No. 746,297, Dec. 1, 1976, Pat. No. 4,134,654. This application Jul. 9, 1979, Ser. No. 55,964
Claims priority, application Japan, Dec. 2, 1975, 50-144159
Int. Cl.³ G03B 7/08, 9/56, 17/20
U.S. Cl. 354—50

12 Claims




1. For a camera which is provided with: P1 a photo-taking lens system, view finder optical means, and aperture frame means to define a photographing picture frame, a printed circuit unit comprising:

(A) photo-sensing means to measure the brightness of an object to be photographed by said camera, means to produce an electric signal as corresponding to the object brightness,
(B) exposure operation circuit means to determine a proper exposure value based on the output signal of said photo-sensing means, and to produce an electric signal corresponding to a proper exposure value,
(C) display means to electro-optically display the proper exposure value information based on the output signal from said exposure operation circuit means,
(D) electrically insulating flexible circuit supporting means; said supporting means being adapted to be bent into a configuration to fit in a desired space within said camera and having an opening with a size at least equal to the size of the photographing picture frame defined by said aperture frame means,
(E) electrically conductive means being carried on said flexible supporting means,
said photo-sensing means, said exposure operation circuit means and said display means being carried on said flexible supporting means, and said photo-sensing means and said display means being electrically connected to said exposure operation circuit means through said electrically conductive means, and
said supporting means being constructed so that:
said photo-sensing means is placed at a position to receive a light beam from said object through at least a part of said view finder optical means,
said display means is placed at a position having the display information light beam display said proper exposure value information and impinge into at least a part of said view finder optical means, and
said opening of the supporting means matches with said photographing picture frame defined by said aperture frame means, and is mounted in a camera so at least to utilize a restricted space near said aperture frame means, electric shutter means of the physico-optical type mounted on said flexible supporting means for covering said opening in said supporting means, and
shutter control circuit means to control said shutter means

4,297,019
AUTOMATIC FILM FEEDING APPARATUS FOR PHOTOGRAPHIC CAMERA
Michio Yagi; Kunio Nakajima; Yasutsugu Nakagawa; Sizuo Ishii, and Kazuhisa Aratame, all of Hachioji, Japan, assignors to Konishiroku Photo Industry Co., Ltd., Tokyo, Japan
Filed Aug. 14, 1979, Ser. No. 66,337
Claims priority, application Japan, Aug. 22, 1978, 53-102104
Int. Cl.³ G03B 17/36, 19/04
U.S. Cl. 354—171

2 Claims



1. An automatic film feeding apparatus for a photographic camera which utilizes a film strip and which includes a motor drive mechanism for winding the film strip to photographic exposure enabling frame positions therealong, a counter operable for indicating the frame positions of the film strip, and a rear cover of the camera movable between an open position for film loading and removal and a closed position for photographic exposure of the film, said film feeding apparatus comprising:


a first switch operable in response to the position of the rear cover of the camera and switchable between a first state when the rear cover is closed and a second state when the rear cover is open;
a second switch operable in response to the position of the film counter and switchable between a first state until the counter indicates movement of the film strip to a first photographic exposure frame position and a second state when the counter indicates movement of the film strip to at least said first exposure frame position;
a third switch operable in accordance with the position of the film strip and switchable between a first state when the film strip is at a photographic exposure frame position and a second state when the film strip is remote from an exposure frame position; and
electronic control circuit means for operating the motor drive mechanism in response to the states of said first, second and third switches, said circuit means being adapted to operate the motor drive mechanism when said first and second switches are switched to said first states thereof and independently of the state of said third switch so as to automatically wind and feed the film strip substantially to said first photographic exposure frame on loading of the film strip into the camera and movement of the rear cover to its closed position, and said control circuit being further adapted to operate the motor drive mechanism when said first switch is in its first state and said third switch is in its second state and independently of the state of said second switch so as to wind the film strip to the next exposure frame position after photographic exposure at the preceding frame position.

4,297,020

VIEW FINDER FOR SINGLE-LENS REFLEX CAMERA
Yasuyuki Yamada, Tokyo, and Youichi Okuno, Yokohama, both of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan
Filed Feb. 5, 1980, Ser. No. 118,799

Claims priority, application Japan, Feb. 7, 1979, 54-12992
Int. Cl.³ G03B 13/08, 17/20
U.S. Cl. 354—225

5 Claims




1. A viewfinder for a single-lens reflex camera, comprising:
a viewfinder prism having an entrance face for receiving imaging light representing an image of an object to be photographed, an exit face which allows the incident light to exit therethrough and a notch in the lower part of said exit face outside the area thereof through which rays of imaging light pass;
a photographic data source;
an optical system for guiding data coming from said photographic data source to the inside of said viewfinder prism and then allows the data light to pass from said exit face of the viewfinder prism;
a reflection arrangement at least partly disposed in said ghost cut groove, said reflection body being arranged to direct the data light coming from said photographic data source and allowed to pass from said exit face towards an eye-piece.

4,297,021

POWDER MATERIAL TRANSPORTATION APPARATUS
Tatsuo Tani, Tokyo; Yasumori Nagahara, Yokosuka; Sakae Ohta, Tokyo; Minoru Suzuki, Yokohama, and Kiyozo Hashizume, Tokyo, all of Japan, assignors to Ricoh Company, Ltd., Japan

Filed Jun. 6, 1979, Ser. No. 45,964
Claims priority, application Japan, Jun. 9, 1978, 53-69431; Jun. 9, 1978, 53-69432
Int. Cl.³ G03G 15/00; G01F 11/20
U.S. Cl. 355—3 R

11 Claims



1. Apparatus for handling powdered material, said apparatus comprising: a housing comprising an upper portion and a bottom portion to receive the powdered material; a rotating member located in the bottom portion of the housing to transport the powdered material; a shaft in the housing to support the member rotatably, the member extending axially relative to the shaft; stirring means movably mounted in the housing between the upper portion of the housing and the rotating member to direct the powdered material to the rotating member; the rotating member comprising a helical structure; a second helical structure located to receive the powdered material from the first-named helical structure and convey the

received powdered material in a direction at an angle to the direction the powdered material is conveyed by the first-named helical structure; electrophotographic means for electrophotographic reproduction; the powdered material comprising toner; and means to effect separate rotation of the first-named and second helical structures and to rotate both of the helical structures at a first speed during formation of electrophotographic reproductions and to continue to rotate the second helical structure at a speed less than the first speed for a predetermined period of time after formation of an electrophotographic reproduction.

4,297,022



LIGHT PIPE VALVE LIQUID CRYSTAL TRANSMISSIVE DISPLAY FOR DIRECT IMAGING ON PHOTSENSITIVE MATERIALS

Robert W. Lester, Manhasset, N.Y., assignor to Static Systems Corporation, New York, N.Y.

Filed Dec. 3, 1979, Ser. No. 99,685
Int. Cl.³ G03G 15/00

U.S. Cl. 355—3 R

21 Claims





14. A method for producing a liquid crystal display, the steps comprising:
applying a transparent conductive coating to the inner surface to a transparent, non-conductive, first sheet and to a substantially opaque, non-conductive second sheet, the latter of which has a plurality of discrete transparent channels formed therethrough, said coating being applied to said second sheet so as to separate said coating into discrete character forming segments, each of which overlies one of said transparent channels;
securing to said coatings on each of said sheets, means for electrically coupling said coatings to an external power source;
sealing a normally transparent liquid crystal material between said inner surfaces of said non-conductive sheets; and
securing a linear polarizer sheet to the outer surface of each of said non-conductive sheets.

4,297,023

ELECTROPHOTOGRAPHIC COPYING APPARATUS
Mitsuru Nagoshi, Hachioji, Japan, assignor to Konishiroku Photo Industry Co., Ltd., Tokyo, Japan

Filed Jul. 26, 1979, Ser. No. 61,053
Claims priority, application Japan, Jul. 31, 1978, 53-93449
Int. Cl.³ G03G 15/28; G03B 27/62
U.S. Cl. 355—8

4 Claims



1. In an electrophotographic copying apparatus including a machine body and a copy board movable thereon along a path, suspension means on the machine body and comprising a pair of predeterminedly spaced apart elements disposed along the path of the copy board, at least one of said elements being driven during operation of the copying apparatus,
an endless power transmitting means suspended between said spaced apart elements of the suspension means for driven movement of the power transmitting means during operation of the copying apparatus,
intermediator means including a closed vertical slot, engaging means on said power transmitting means for non-releasable engagement in and movement along the vertical slot of said intermediary means such that driven movement of said power transmitting means causes said intermediary means to be carried by said engaging means reciprocatingly between said spaced apart elements of said suspension means, and
coupling means between said intermediary means and the copy board for releasable coupled engagement therebetween so as to normally couple said intermediary means and the copy board for reciprocating movement of the copy board along the path when said suspension means is driven during operation of the copying apparatus.

4,297,024

EXPOSURE DEVICE OF AN ELECTROGRAPHIC COPYING APPARATUS

Kiyohito Ebisawa, Tokyo; Satoshi Hisabayashi, Hachioji; Toshio Koike, Hachioji, and Kazuyuki Hashimoto, Hachioji, all of Japan, assignors to Iwatsu Electric Co., Ltd., Tokyo, Japan

Filed Apr. 23, 1979, Ser. No. 32,345
Claims priority, application Japan, Apr. 25, 1978, 53-54166[U]; Apr. 25, 1978, 53-54167[U]; Apr. 25, 1978, 53-54168[U]

Int. Cl.³ G03G 15/00



U.S. Cl. 355—14 E

4 Claims

1. An exposure device of an electrographic copying apparatus which comprises at least one heat generative exposure lamp for creating an electrostatic latent image on a photosensitive

paper corresponding to an original to be copied, wherein the device comprises:

paper detector means for detecting said photosensitive paper when it is fed from a paper case to a paper feed device; an exposure device disposed above said paper feed device and reciprocally movable with said exposure lamp; exposure device detector means for detecting said exposure device at its start position;
cam means which is rotated by a drive means through a clutch means when said paper detector means detects the rear end of said paper, said cam means comprising a first



switch which represents an initial condition, second and third switches which represent an exposure start condition; and
exposure lamp control means comprising a relay means which is self-latched when said paper detector means and said exposure device detector means are turned off, and when said second and third switches are turned off and said relay remains latched until said exposure device detector means detects the start position, said exposure lamp being turned on during the time said relay means is operated.

4,297,025


DOCUMENT FEEDER SYSTEM HAVING A SUSPENDING/COMMENCING MODE

Paul S. Bach, Boulder, Colo.; Steven R. Harding, Idaho Falls, Id.; Richard A. Lamos, Boulder, Colo.; Harvey R. Markham, Westminster, Colo., and Roger D. Shepherd, Nederland, Colo., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Jul. 9, 1979, Ser. No. 55,679
Int. Cl.³ G03G 15/00

U.S. Cl. 355—14 SH

8 Claims



1. In a document reproduction system including a document feeder system, an electrophotographic copier system and a copy exit system, configured to suspend processing a prior task, commence processing a subsequent task and then, re-commence processing said prior task, the improvement comprising: means for entering a suspending/commencing mode; first document feeder means of said document feeder system

for feeding original documents to a document viewing glass of said electrophotographic copier system for copying thereof;

second document feeder means of said document feeder system for feeding original documents to a document viewing glass of said electrophotographic copier system for copying thereof; and

logic control means operatively connected and responsive to said means for entering said suspending/commencing mode, and operatively connected to said first document feeder means, said second document feeder means and said electrophotographic copier system for immediately entering said suspending/commencing mode, for suspending operation of either said first or said second document feeder means processing said prior task, and in turn, for immediately thereafter commencing operation of said second or said first document feeder means, respectively, processing said subsequent task, and upon the completion thereof, for immediately re-commencing said prior task.

4,297,026

CLEANING APPARATUS FOR COPY MACHINES

Hiroaki Honda, and Hiroaki Ura, both of Hachioji, Japan, assignors to Konishiroku Photo Industry Co., Ltd., Tokyo, Japan


Filed Dec. 21, 1979, Ser. No. 106,157

Claims priority, application Japan, Dec. 27, 1978, 53-160001

Int. Cl.³ G03G 21/10

U.S. Cl. 355-15

2 Claims



1. In a cleaning apparatus for a copying machine including a photosensitive drum detachably mounted on the machine frame, cleaning means for scraping toner from the drum surface, and a thin plate normally applied to the drum surface for guiding toner scraped therefrom by the cleaning means into a toner recovery box, the improvement comprising:

a pivotally mounted member normally supporting the thin plate in engagement with the drum surface;

a lever operatively engagable with said pivotally mounted member;

biasing means urging said lever into engagement with said pivotally mounted member to rotate the same to move the thin plate to a position withdrawn from the drum surface; and

an action piece associated with the photosensitive drum and disposed for engagement with said lever when the drum is mounted on the machine frame to cause said lever to become disengaged from said member against the action of said biasing means so that the member normally supports the thin plate in contact with the drum surface; whereby detachment of the drum from the machine frame causes said action piece to disengage said lever which there upon moves into engagement with said member under the action of said biasing means to move the thin plate to a position withdrawn from the drum surface and thereby prevent damage to the thin plate or to the drum surface as the drum is detached from or reattached to the machine frame.

4,297,027

APPARATUS FOR EXPOSING AND DEVELOPING PHOTSENSITIVE MATERIAL

Otto Stemme, Munich; Berthold Fergg; Viktor Osegowitsch, both of Taufkirchen, and Wolfgang Viehrig, Munich, all of Fed. Rep. of Germany, assignors to Agfa-Gevaert AG, Leverkusen, Fed. Rep. of Germany


Filed Nov. 27, 1979, Ser. No. 97,720

Claims priority, application Fed. Rep. of Germany, Nov. 30, 1978, 2851893

Int. Cl.³ G03B 27/32, 27/52

U.S. Cl. 355-27

20 Claims



1. Apparatus for exposing and developing film units wherein two sheets overlap each other, comprising an exposing unit including means for supporting successive film units in a predetermined plane during exposure of such units to light; and a developing unit including advancing means, a carriage mounting at least a portion of said advancing means and including a lever, means for pivoting said lever about a predetermined axis between a first position in which said advancing means can engage a film unit located in said plane and a second position in which the thus engaged film unit is at least partially withdrawn from said plane, and a vessel containing a supply of liquid developing agent and being adjacent to said portion of said advancing means in said second position of said lever, said portion of said advancing means comprising two parallel rolls rotatably mounted on said lever.

4,297,028

MULTI-ITEM DATA INPUT APPARATUS

Yashiro Seki; Hideo Kobayashi; Kiyoshi Kimura, and Masayuki Naito, all of Tokyo, Japan, assignors to Anritsu Electric Company Limited, Tokyo, Japan


Filed Apr. 17, 1980, Ser. No. 141,182

Claims priority, application Japan, Jun. 21, 1979, 54-78295

Int. Cl.³ G03B 27/52, 23/02

U.S. Cl. 355-41

17 Claims



1. A multi-item data input apparatus for manually actuated generation of data to specify selected ones of a plurality of items, comprising:

a housing;

a sheet holder of substantially cylindrical configuration rotatably mounted in said housing;

a plurality of flexible sheets each having a page of data appearing thereon in visible form, each of said pages comprising a plurality of said items, each of said flexible sheets being attached at one end thereof to said sheet holder, said flexible sheets being axially rolled around said sheet holder such as to successively overlap at equidistant angular intervals;

keyboard means including a plurality of page selection keys coupled to switching means for generating corresponding page selection data when each of said page selection keys is actuated and a plurality of item selection keys coupled to switching means for generating corresponding item selection data when each of said item selections keys is actuated, each of said item selection keys being transparent through at least a portion thereof, said item selection keys being arranged in positions corresponding to positions of said items on each of said pages;

guide means disposed adjacent to said sheet holder; and drive means coupled to rotate said sheet holder, being responsive to said page selection data for rotating said sheet holder in a first direction of rotation which is opposite to a direction in which said flexible sheets are rolled on said sheet holder, said rotation being continued until a selected one of said flexible sheets corresponding to a page designated by said page selection data is positioned adjacent to said guide means, said drive means then rotating said sheet holder in a second direction of rotation opposite to said first direction through a predetermined angular displacement, whereby said selected flexible sheet is directed by said guide means to be positioned in a substantially flat condition below said item selection keys, such that said items on the selected flexible sheet are visible through corresponding ones of said item selection keys.

4,297,029

APPARATUS AND METHOD FOR DIAGNOSTIC ENTRY



Gerald E. Carlson, Webster, N.Y., assignor to Xerox Corporation, Stamford, Conn.

Filed Apr. 9, 1979, Ser. No. 28,636

Int. Cl.³ G03G 15/00

U.S. Cl. 355-133

6 Claims



2. In an electrostatic printing apparatus having a plurality of

processing stations and an operator's console provided with a plurality of machine instruction devices, the electrostatic printing apparatus adapted for operating in a first state for reproducing a predetermined number of copies of an original and adapted for operation in a second state for diagnosing operation of selected processing stations, the method of placing the electrostatic printing apparatus in the second state comprising the steps of:

initiating a malfunction condition, activating one of the plurality of instruction devices, again activating one of the plurality of instruction devices, whereby the apparatus is placed in the second state.

4,297,030

METHOD AND APPARATUS FOR MEASURING THE DISTANCE AND/OR RELATIVE ELEVATION BETWEEN TWO POINTS

Hoiko Chaborski, Ottobrunn, Fed. Rep. of Germany, assignor to MITEC-Moderne-Industrietechnik GmbH, Ottobrunn, Fed. Rep. of Germany


Continuation-in-part of Ser. No. 926,099, Jul. 19, 1978, abandoned, which is a continuation of Ser. No. 743,801, Nov. 22, 1976, abandoned. This application May 31, 1979, Ser. No. 44,344

Claims priority, application Fed. Rep. of Germany, Nov. 28, 1975, 2553591

Int. Cl.³ G01C 3/08

U.S. Cl. 356-5

8 Claims



1. A method for opto-electronically measuring the distance between a measuring point and a reflecting target, comprising the following steps: pg.22

(a) producing a fixed frequency signal having a given fixed frequency,

(b) modulating the light of a light source with said fixed frequency signal to produce a modulated light beam,

(c) dividing the modulated light beam into a reference light beam and into a measuring light beam, both beams having said fixed frequency modulated thereon,

(d) processing, during a first portion of a complete measuring sequence, said reference light beam through receiver means for producing a first electrical signal representing the reference phase of said reference light beam,

(e) repeatedly producing, in response to said first electrical signal a time raster signal which is phase locked with said reference phase of the first electrical signal even after the reference light beam is not received any more,

(f) processing, during a second portion of said complete measuring sequence, said measuring light beam after reflection from said target through said receiver means, which are the same receiver means which processed said reference light beam in the first portion of the measuring sequence, for producing a second electrical signal representing the phase shift of said reflected, measuring light beam relative to said reference phase, said phase shift representing the distance to be measured, and

(g) measuring in said second portion of said complete measuring sequence said phase shift of said reflected, measuring light beam, whereby said phase shift measuring begins in response to said time raster signal and is terminated in response to said phase shifted second electrical signal.

4,297,031

APPARATUS AND PROCESS FOR SWEEPING A FLAT OPTICAL LIGHT PLANE


Martin R. Hamar, 70 Linden Tree Rd., Wilton, Conn. 06897

Filed Sep. 26, 1979, Ser. No. 78,933

Int. Cl.³ G07B 11/26; G02B 7/18

U.S. Cl. 356—247

6 Claims



1. A process for sweeping a flat optical light plane perpendicular to a primary input laser beam emanating from a laser device comprising the steps of:

- providing a spindle having its actual axis of rotation intersecting the primary laser beam at a point;
- rotatably mounting a solid penta prism onto said spindle such that the entrance face of the penta prism intersects the primary laser beam and the first reflecting surface of the penta prism is located intermediate the laser device and said point, said primary laser beam centrally intersecting the entrance face of the penta prism, said point being located at a distance from the first reflecting surface according to the following,

$$R = D \left(1.024 - 3.414 \left[1 - \frac{1}{N'} \right] \right)$$

where D is the distance that the beam traverses within the penta prism between the first reflecting surface and the second reflecting surface, and N' is the index of refraction of the prism; and

rotating said penta prism about said spindle to sweep a flat optical light plane.

4,297,032

DARK FIELD SURFACE INSPECTION ILLUMINATION TECHNIQUE

Paul A. Temple, Ridgecrest, Calif., assignor to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Feb. 14, 1980, Ser. No. 121,625

Int. Cl.³ G01N 21/21, 21/47, 21/88; G01J 4/00

U.S. Cl. 356—366


17 Claims

1. A surface inspection method for finding defects contained in or on an optical sample comprising the steps of:

- coating one side of a prism whose index of refraction is similar to said optical sample with an index matching fluid;
- placing said optical sample on said fluid coated side;
- establishing an observation point above said optical sample to view the surface at a normal angle;
- directing a beam of monochromatic polarized light into said prism such that said beam reflects off of the upper surface of said optical sample at the critical angle beneath said observation point so as to create a standing wave pattern which scatters light off of imperfections smaller than the wavelength of said standing waves except when said

imperfections are located at null points of said standing waves;

varying the standing wave pattern so that the null points of said standing waves occur at different depths within the optical sample, the imperfections appear and disappear as null points pass through it;



comparing the possible depths at which the imperfections appear for a plurality of different standing wave patterns to uniquely identify the depth in the sample of each imperfection; and

moving said optical sample so that all areas of said optical sample are viewed from said observation point to observe said scattered light which has been scattered toward said upper surface at less than the critical angle.

4,297,033

INCREMENTAL PHOTOELECTRIC MEASURING DEVICE

Günther Nelle, Bergen, Fed. Rep. of Germany, assignor to Dr. Johannes Heidenhain GmbH, Traunreut, Fed. Rep. of Germany


Filed Jun. 4, 1979, Ser. No. 45,295

Claims priority, application Fed. Rep. of Germany, Jun. 15, 1978, 2826213

Int. Cl.³ G01B 11/14, 11/04

U.S. Cl. 356—374

2 Claims



1. A photoelectric incremental measuring device comprising:

- a measuring scale having a first line grid with a first grid spacing wherein the ratio of the bright-field width of the scale to the first grid spacing is about 1:(2×n), where n is a positive integer greater than one;
- a scanning plate having a second line grid with a second grid spacing, wherein the ratio of the bright-field width of the scanning plate to the second grid spacing is about 1:2 and the first grid spacing is substantially an integral multiple of the second grid spacing;
- means for generating a collimated beam of light;
- means for measuring light intensity; and
- means for mounting the scanning plate adjacent the scale to modulate the intensity of the collimated beam of light generated by the generating means which reaches the measuring means such that the scanning plate is movable substantially parallel to the scale and no focusing elements are mounted between the scale and the scanning plate.

4,297,034

APPARATUS FOR MEASURING CONTOUR CONFIGURATION OF ARTICLES

Isao Ito, Nagoya, and Seichi Tunashima, Kasugai, both of Japan, assignors to NGK Insulators, Ltd., Nagoya, Japan


Filed Jun. 15, 1979, Ser. No. 48,735

Claims priority, application Japan, Sep. 11, 1978, 53-110599

Int. Cl.³ G01B 11/24, 11/00

U.S. Cl. 356—394

4 Claims



1. An apparatus for measuring contour configuration of articles comprising:

- a turn table on which the article to be measured is placed;
- a detector for detecting a rotational angle of said turn table to produce a rotational angle signal;
- a light source for illuminating at least a portion of the article on the turn table, the contour configuration of said portion being to be measured;
- a pick-up device including a lens for forming an optical image of said portion of article to be measured and an image detector for receiving said image to produce a video signal;
- a memory for storing a standard signal which corresponds to a standard article having given contour configuration;
- an operation circuit for receiving said rotational angle signal, the video signal and the standard video signal and producing a signal which represents deviation in the contour configuration of the article to be measured from the standard article;

means for detecting a distance l between the portion of article to be measured and the pick-up device; and means for driving the pick-up device in a direction of its optical axis in accordance with the detected distance in such a manner that the optical image of article is always focused on the image detector in the pick-up device, wherein an edge of the article is illuminated by said light source and an optical axis of said pick-up device is aligned on a corresponding edge of the standard article whereby said operation circuit detects a deviation of height of article from a standard height and a deviation of the contour dimension of article to be measured from the standard value.

4,297,035

METHOD AND DEVICE FOR DETECTING A SPECIFIC SPECTRAL FEATURE

Gary C. Bjorklund, Los Altos, Calif., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Sep. 14, 1979, Ser. No. 75,436

Int. Cl.³ G01N 21/27


U.S. Cl. 356—402

10 Claims

1. A method of detecting a single narrow spectral feature in a sample comprising

- providing a beam of light having an optical frequency bandwidth which is narrow compared to the width of the narrow spectral feature and having a center frequency ω_c which lies near the feature;
- phase modulating the beam of light with a single RF frequency to provide a pure FM spectrum having upper and lower sidebands;
- exposing the sample containing the narrow spectral feature

to the modulated light so that only one of the FM sidebands probes the narrow spectral feature; photodetecting the light emerging from the sample to detect a beat at the specific RF frequency used for phase modulation; and



electronically monitoring the amplitude of the RF beat signal to indicate the strength of the narrow spectral feature.

4,297,036

EXTRUDER FOR PREPLASTICIZATION OF THERMOSET MOLDING MATERIALS

Klaus Schröder, Marienheide, Fed. Rep. of Germany, assignor to Firma C. & W. Berges Maschinenfabrik, Marienheide, Fed. Rep. of Germany


Filed Jun. 11, 1979, Ser. No. 47,787

Claims priority, application Fed. Rep. of Germany, Jun. 9, 1978, 2825349

Int. Cl.³ B29B 1/06, 5/04

U.S. Cl. 366—77

1 Claim



1. In an extrusion machine for the preplasticization of thermosetting plastics including a rotating screw and a heated screw cylinder which compresses pulverulent material against a pressure head to impart plasticization, the improvement comprising:

- (a) a receiving cylinder positioned adjacent the discharge end and coaxial with the screw cylinder, said receiving cylinder having a hydraulic discharge piston which continually retracts when an adjustable pressure head has been exceeded; and
- (b) a sliding pressure cylinder for moving said receiving cylinder at right angles to the direction of the longitudinal axis of said screw.

4,297,037

VACUUM ATTACHED VIBRATOR APPARATUS


David M. O'Meara, Joliet, Ill., assignor to Chicago Bridge & Iron Company, Oak Brook, Ill.

Filed May 8, 1980, Ser. No. 147,857

Int. Cl.³ B01F 11/00

U.S. Cl. 366—114

7 Claims



1. Apparatus for removable attachment to a rigid surface for vibrating the same comprising:

a vacuum plate having a face with an elastomeric gasket around the face periphery and contactable with said rigid surface;

a vibrator mount on the vacuum plate; a vibrator joined to the vibrator mount; and said elastomeric gasket projecting sufficiently forward from the vibrator mount and the vacuum plate to prevent the vibrator mount and the vacuum plate from touching the rigid surface when attached thereto so that all vibrations developed by the vibrator are transmitted to the rigid surface through the elastomeric gasket and the pressure waves in the vacuum plate.

4,297,038

ELECTRIC BLENDER

Guenther Falkenbach, Eschborn, Fed. Rep. of Germany, assignor to Braun AG, Kronberg, Fed. Rep. of Germany


Filed Oct. 29, 1979, Ser. No. 88,917

Claims priority, application Fed. Rep. of Germany, Apr. 19, 1978, 2817044

Int. Cl.³ B01F 7/16

U.S. Cl. 366—206

7 Claims



1. An electric household blender including a motor base having a housing, an electric operating switch mounted in said motor base to turn on an electric motor, and a removable

container which can be mounted on said motor base, comprising:

(a) a container holder (2) adapted to be placed on said motor base;

(b) a lock ring (9) mounted and guided in said motor base and capable of rotating about the longitudinal axis of said motor base;

(c) lock bolts (8) arranged on said lock ring;

(d) lock bolt supports (12) arranged on said container holder;

(e) a lock bar (11) arranged to extend through an opening in said motor base and operable to engage with said lock ring in order to rotate said lock ring;

(f) a lock rod (26) arranged within said motor base so as to be capable of longitudinal movement in the vertical direction of said motor base, said lock rod being operatively engaged with said switch, and cooperating with said lock ring in a manner such that said lock ring, when in a first position, locks said lock bar against longitudinal movement to prevent operation of said electric switch, and when in a second position, allows said electric switch to be selectively operated.

4,297,039

THERMAL PRINTER


Robert Lees, Newark, Del., assignor to Autotote, Ltd., Newark, Del.

Filed Dec. 29, 1978, Ser. No. 974,440

Int. Cl.³ B41J 3/20

U.S. Cl. 400—120

6 Claims



1. A document printer for printing documents on thermally sensitive paper and driving said paper through cut-off means to cut the paper to predetermined lengths comprising:

a frame having generally parallel spaced apart walls;

a drive motor on the frame having drive engaging means for driving said thermally sensitive paper;

actuator means on the frame for actuating the cut-off means;

a first sub-frame having generally parallel spaced apart walls parallel to the walls of the frame, which first sub-frame is pivotally supported on and within the frame walls by first pivot means generally perpendicular to the parallel walls and has an operational position;

a thermal printing element on a separate removable base supported on the first sub-frame by a pivot pin engaging portion open on one side which enables the base in alternate position of the first sub-frame to be lifted away from the first sub-frame and supported at the opposite end by means which rests against the first sub-frame on the side opposite from a friction drive roller means, the thermal printing element being supported in position to define a portion of a paper path and comprising at least a row of high resistance printing dots;

a second sub-frame having generally parallel spaced apart walls parallel to the walls of the frame, which second sub-frame is pivotally supported on the frame by second pivot means generally perpendicular to the parallel walls

and has an operational position adjacent and opposed to the operational position of the first sub-frame; the friction drive roller means being rotatably supported on the second sub-frame opposite from the thermal printing element and positioned to drive the thermally sensitive paper along a path past the thermal printing element by contacting the paper on the side opposite from the thermal printing element, the friction drive roller means being positioned on the second sub-frame opposite the thermal printing element in such position as to urge through its inherent resiliency the paper to engage the thermal printing element so that the thermal printing element is effective to print on the paper and having drive coupling means positioned to engage the drive engaging means of the drive motor to move said thermally sensitive paper along the paper path past the thermal printing element when the second sub-frame is in operational position, the motor being supported on the frame, said drive coupling means comprising gear means and the gear means being rotatably supported on the second sub-frame so that the gear means are engaged on the second sub-frame in operational position and disengaged as the second sub-frame is moved from operational position;

the cut-off means being positioned on the second sub-frame to cut off the paper at selected lengths to include predetermined ticket information on the selected length and linkage means placed into actuating position with the actuator means when the second sub-frame is in operational position;

separate releasable means for normally maintaining each of the sub-frames in its operational position but permitting pivotal movement to at least an alternate position upon release of the releasable means, such that in the alternate positions the thermal printing element may be reached for cleaning; and

means to selectively heat individual dots to generate patterns on said thermally sensitive paper moved past the thermal printing element.

4,297,040

METHOD AND APPARATUS FOR POSITIONING A TYPE DISC IN A BALANCED FORCE SYSTEM


Diethelm Puch, and Norbert F. Will, both of Nuremberg, Fed. Rep. of Germany, assignors to Triumph-Werke Nurnberg A.G., Nuremberg, Fed. Rep. of Germany

Filed Jun. 13, 1980, Ser. No. 159,117

Int. Cl.³ B41J 1/30, 23/14, 23/16

U.S. Cl. 400—144.2

10 Claims



1. The method for positioning a type disc in a fixed cycle balanced force system, wherein applied forces to effect angular positioning movement from an old to a new position are brought into equilibrium with opposing spring forces without damping or overshoot, comprising the steps of

applying positioning forces to effect angular positioning movement from an old to a new position according to the natural oscillation of the system about a selected reference position, whereby the new position is reached at the maxi-

mum amplitude of the oscillation of the system about the reference position when angular velocity is zero, and applying a force corresponding to the new position when the new position is reached to maintain the system at the new position.

4. Apparatus for positioning a type disc in a fixed cycle balanced force system, wherein applied forces to effect angular positioning movement from an old to a new position are brought into equilibrium with opposing spring forces without damping or overshoot comprising

means for applying positioning forces to effect angular positioning movement from an old to a new disc position according to the natural oscillation of the system about a selected reference position whereby the new position is reached at the maximum amplitude of the oscillation of the system about the reference position when angular velocity is zero,

and means for applying a force corresponding to the new position when the new position is reached to maintain the system at the new position.

4,297,041

VARIABLE CAM PROFILE SELECTION SYSTEM FOR SINGLE ELEMENT TYPEWRITER


John O. Schaefer, Lexington, Ky., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed Apr. 2, 1979, Ser. No. 25,824

Int. Cl.³ B41J 1/32

U.S. Cl. 400—161.4

22 Claims



1. A cam controlled selection apparatus, for a single element typewriter, for controlling at least one of two degrees of movement required for selecting a character on a single typing element, comprising:

a rotatable shaft,

a cam means mounted for rotating with said shaft and having a camming surface thereon;

cam follower means abutting said camming surface;

means for altering the angle of inclination of said camming surface upon axial displacement of said cam means;

means for selectively controlling the axial displacement of said cam means, thereby controlling the cam rise of said cam means; and

linkage means interposed between said cam follower means and said typing element for transmitting movement of said cam follower means to said typing element.

4,297,042

HELICAL PRINT HEAD MECHANISM

An Wang, Lincoln, Mass., assignor to Wang Laboratories, Inc., Lowell, Mass.

Filed May 29, 1980, Ser. No. 154,385

Int. Cl.³ B41J 1/40, 7/52


U.S. Cl. 400—163.2

4 Claims

1. An impact printer head mechanism for serially printing a line of characters on a print medium comprising

a generally cylindrical print head having its axis generally perpendicular to said print line

said print head having
a matrix of characters formed on its exterior surface parallel to said axis in a multi-turn helical row of predetermined pitch
a screw thread of said predetermined pitch and coaxial with said axis, and
a spline coaxial with said axis and axially spaced from said matrix
print head supporting means for supporting said print head for rotational and axial movement relative to said print medium, said print head supporting means having
a rotatably fixed screw thread coaxial with said axis and of



said predetermined pitch cooperating with said print head screw thread, and
print head drive means for simultaneously rotatably and axially moving said print head to position a desired character relative to said print line, including
gear means cooperating with said spline for rotating said print head,
the relative rotation of said screw threads of said print head and said supporting means producing simultaneous rotational and axial movement of said print head relatively to said print line, and
operating means for operating said mechanism to cause a selected character to be printed on said print medium.

4,297,043


IMPACT PRINTER INCLINED RIBBON SCANNER
Dayton O. Dargatz, Anaheim, Calif., assignor to Plessey Peripheral Systems, Irvine, Calif.

Filed Nov. 1, 1978, Ser. No. 956,737

Int. Cl.³ B41J 33/56

U.S. Cl. 400—224

8 Claims



1. An impact printer comprising:

a frame;
guide means mounted on said frame, comprising: primary guide means; and secondary guide means obliquely disposed with respect to said primary guide means;
a carriage supporting a print head, said carriage movably mounted on said guide means for reciprocation along a printing line;
a ribbon supported on said carriage; and
means in communication with said secondary guide means

for adjusting the position of said ribbon relative to said print head so that said printing line is not parallel to the longitudinal axis of said ribbon.

4,297,044

ADDITIONAL ATTACHMENT FOR ALL TYPES OF KEY OPERATED MACHINES

Harald Hornberg, Berlin; Günter Trotzek, and Fedor Hahnefeld, both of Unterhaching, all of Fed. Rep. of Germany, assignors to H. Berthold Aktiengesellschaft, Fed. Rep. of Germany


Filed May 8, 1979, Ser. No. 37,045

Claims priority, application Fed. Rep. of Germany, May 8, 1978, 2820422

Int. Cl.³ B41J 5/08

U.S. Cl. 400—473

6 Claims



1. Additional attachment for machines operated by a first set of keys disposed in a keyboard comprising:
a frame, said frame covering said keyboard;
said frame having the shape of a first plate, said first plate including a plurality of perforations, said perforations being aligned with said keys of said first set of keys in said keyboard, said first plate being a solid plate with side and edge areas, complementary to outer edges of said first set of keys, said side and edge areas abutting the outer edges of the rows of said first set of keys which form the boundaries of said keyboard, to vertically support the attachment solely by said abutment, said side and edge areas aligning said attachment with said first set of keys;
a second set of keys, said second set of keys being disposed in said perforations in said first plate;
and
a second plate disposed in a detachable manner on the surface of said first plate, said second plate including a plurality of perforations in agreement and conformity with said perforations in said first plate, said second plate carrying the symbols associated with each of said keys in said second set of keys.

4,297,045

PAPER FEED SYSTEM FOR A TYPEWRITER OR THE LIKE

Robert L. Burton, and Thomas P. Finan, both of Lexington, Ky., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Sep. 21, 1979, Ser. No. 77,884


Int. Cl.³ B41J 13/076, 13/048

U.S. Cl. 400—641

17 Claims

1. In a paper feed system for a typewriter or the like including:
a rotatable platen;
rear feed roller means engageable with said platen when no paper is therebetween so as to be rotatable with said platen when said platen rotates;
and front feed roller means engageable with said platen when no paper is therebetween so as to be rotatable with said platen when said platen rotates;
the improvement comprising:
said rear feed roller means including a plurality of rear feed rollers engageable with said platen when no paper

is therebetween so as to be rotatable with said platen when said platen rotates;
each of said rear feed rollers including an annular outer portion formed of a material sufficiently compressible when a plurality of sheets of paper with adjacent sheets having different coefficients of friction is simultaneously disposed between said platen and said rear feed rollers not having paper between said rear feed roller and said platen remain in engagement with said platen for driving of each of said rear feed rollers during rotation of said platen while another portion of each of said rear feed rollers has the sheets of paper between said rear feed roller and said platen until the rotation of said rear feed rollers advances the sheets of paper completely



between each of said rear feed rollers and said platen, the material of each of said rear feed rollers having a sufficiently high coefficient of friction with the material of said platen for each of said rear feed rollers to be driven by said platen and a sufficiently high coefficient of friction with the sheets of paper for each of said rear feed rollers to advance the sheets of paper in conjunction with said platen, and the material of each of said rear feed rollers being sufficiently hard to avoid treeing;
said rear feed roller means including support means for each of said annular outer portions;
each of said annular outer portions having its width substantially less than its diameter;
and each of said annular outer portions having its thickness equal to or less than its width.

4,297,046

TURNBUCKLE


Roy F. McGill, 538 W. Popular St., Gastonia, N.C. 28052

Filed Jan. 29, 1980, Ser. No. 117,644

Int. Cl.³ F16B 7/06; F16G 11/12

U.S. Cl. 403—46

7 Claims



1. A turnbuckle construction including a pair of first and second opposite end generally parallel and oppositely threaded shank members having adjacent and remote ends, center nut means defining a pair of oppositely threaded generally parallel bores formed therethrough in which said adjacent ends are threadably engaged, the remote ends of said first and second shank members including first and second anchor means, respectively, for anchoring relative to associated tension members, said first anchor means including an open throat hook formed on the end of said first shank remote from and opening toward said second shank and with which a closed ring type anchor member may be engaged, said first shank including a throat closing member mounted on said first shank for move-

ment therealong toward and away from position closing and opening said throat, said throat closing member being engageable by said nut means, upon threaded movement of the latter on said first shank toward said throat, to move said throat closing member into position closing said throat to prevent disengagement of said anchor member from said hook, said nut means including a first nut member in which said pair of oppositely threaded bores are formed in side-by-side relation and a second nut member threaded on one of said shank members, and an axially compressible and radially expandable friction member having a friction bore formed therethrough and disposed on said one shank member between said nuts for adjustable axial compression therebetween and radial inward expansion into frictional engagement with the portion of said one shank passing through said friction bore.

4,297,047

BALL AND SOCKET JOINT

David J. R. Farrant, Radford Semele, England, assignor to Automotive Products Limited, Warwickshire, England


Filed Jun. 5, 1980, Ser. No. 156,801

Claims priority, application United Kingdom, Jun. 9, 1979, 20172/79

Int. Cl.³ F16C 11/06

U.S. Cl. 403—138

5 Claims



1. A ball and socket assembly for the steering and suspension system of a motor vehicle and comprising:
a socket housing having a cavity defined therein;
a ball pin, the head of which is located in the cavity and the shank of which extends through the mouth of said cavity;
a resilient cup shaped lining located in the cavity and the mouth of which provides a bearing surface for the head of the pin adjacent the mouth of the cavity; and
a resilient end cap located in the base of the cup shaped lining to provide a bearing surface for the head of the pin in the base of the cavity, said end cap having a face thereon that is opposed to a co-operating face of the cup shaped lining, said opposed faces being spaced apart by resilient projections held in compression by the assembly of the joint.

4,297,048

FASTENERS FOR JOINING ANGULARLY RELATED WOODEN MEMBERS

John C. Jureit, Coral Gables, and Henry R. Greenley, Fort Lauderdale, both of Fla., assignors to Automated Building Components, Inc., Miami, Fla.

Continuation of Ser. No. 748,679, Dec. 8, 1976, abandoned. This application Mar. 23, 1979, Ser. No. 23,186


Int. Cl.³ F16B 7/00

U.S. Cl. 403—189

15 Claims

1. A fastener for joining angularly related wooden members comprising: a flat sheet metal plate bent to provide first and second planar plate portions lying in respective first and second planes intersecting one another and forming an included angle; said plate being further bent to provide a third planar plate portion lying in a third plane intersecting said first and

second planes; a first group of elongated nail-like teeth struck from said one plate portion to project to one side thereof for embedment into one of the members; and a second group of elongated teeth struck from said second plate portion to project to one side thereof and leaving a plurality of elongated slots in said second plate portion, the teeth of said second group having angularly related shank and tip portions with said shank portions extending from said second plate portion to



form an included angle therewith, said tip portion extending from said shank portions in a direction toward said second plate portion and poised for insertion through the slots from which the teeth are struck for embedment into the other of the members; and a third group of teeth struck from said third plate portion to project to one side thereof for embedment into a third member and leaving a plurality of slots in said third plate portion.

4,297,049

DEVICE FOR ATTACHING TWO METAL SHEETS OR BLANKS TOGETHER

Günter Smitka, Friedenstr. 9, 5868 Letmathe, Fed. Rep. of Germany


Filed May 4, 1979, Ser. No. 36,049

Claims priority, application Fed. Rep. of Germany, Aug. 2, 1978, 2833801

Int. Cl.³ F16B 17/00

U.S. Cl. 403—403

2 Claims



1. A device for fastening to each other two metal sheets or blanks arranged approximately perpendicular to each other by means of a fastening clamp which has a head and a double-arm slit shank and the shank of which is passed through the one metal sheet so that the head lies at least indirectly on said sheet and the other sheet is clamped between the slots of the arms of the shank which are arranged parallel to each other, wherein the two arms forming the shank are at a distance apart which is greater than the thickness of the metal sheet which is to be clamped and is equal particularly to a multiple of said sheet thickness, the slot of each arm widening upwardly to bevels at the tops of the arms and extending approximately perpendicular to the head and being bent in the vicinity of the head, the width of the slot at the tops of the arms being about two-thirds the width of the slot at the start of the bend, the bend of the slot the two arms being arranged at approximately the same level

and extending in opposite directions so that an interlocking of the sheet metal clamped into the slots is effected.

4,297,050

HIGHWAY GUIDE POST


John C. Gmelch, 242 Pleasant St., Wakefield, Mass. 01880

Filed Aug. 15, 1979, Ser. No. 66,807

Int. Cl.³ E01F 9/00

U.S. Cl. 404—10

10 Claims



6. In combination, apparatus characterized as a post to the lower portion of which is fitted a complimentary foot member for attaching and vertically positioning the post, via use of a rigid elongated member, within the soil for delineation of a section of highway, is capable of flexing in any direction, and then rebounding to substantially its original position which comprises:

a resilient, flexible tubular body of trapezoidal cross-section throughout its length, the four walls which adjoin to form the trapezoidal cross-section including parallel walls and adjoining non-parallel walls, one of the parallel walls forming the trapezoidal cross-section being of greater length than the other walls, and said tubular body is constituted of thermoplastic rubber characterized as an elastomeric blend of mono-olefin polymers with polyolefins which is partially cured while in admixture with a resin, and

a foot member of rigid material provided with an upper portion of cross-section corresponding substantially with, and to which said resilient, flexible thermoplastic rubber body is fitted, and retained, and a lower portion which is provided with vertically downwardly projection serrated edges, the edges being beveled, tapered and sharp for cutting into said soil within which said post is to be erected,

whereby said rigid elongated member can be passed through said resilient, flexible tubular thermoplastic rubber body for contact with said foot member, force being exerted on said elongate member to drive said foot member into the soil, and the elongated member thereafter withdrawn to leave the post in erected position.

4,297,051

DEFORMABLE HIGHWAY MARKER


Jesse L. Robinson, P.O. Box 11544, Tahoe Paradise, Calif. 95708

Filed Jun. 1, 1979, Ser. No. 44,501

Int. Cl.³ E01F 9/04

U.S. Cl. 404—11

12 Claims



9. A deformable roadway marker installation, comprising: a bore in the roadway pavement; a flexible, resilient plastic skirt portion of a rounded shape, having substantially vertical walls, positioned in the bore below the surface of the roadway, with the top of the walls generally flush with the surface of the roadway; a rounded dome-shaped deformable top of the same material, integrally molded with the skirt portion to form a unitary marker structure, said top being free of angled corners and sharp breaks, meeting the skirt portion walls at a peripheral edge generally flush with the roadway surface and extending above the roadway surface as a visible marker for traffic on the roadway, the top portion being of resilience and deformability such as to be readily deformable downwardly into the space encompassed by the skirt portion under the weight of a snowplow blade on the road; and grout means retaining the roadway marker in position and sealing its interior such that air is substantially prevented from escaping the interior; whereby the marker's top will deflect downwardly when struck by the blade of a snowplow and will quickly return to its original configuration, aided by the compression and re-expansion of the air in the interior.

4,297,052

BANK EROSION CONTROL UNITS

William J. Rankin, 37811 Lake Shore Blvd., Willoughby, Ohio 44094


Continuation-in-part of Ser. No. 574,009, May 2, 1975, abandoned, and Ser. No. 755,499, Dec. 29, 1976, abandoned.

This application Jul. 24, 1978, Ser. No. 927,658

Int. Cl.³ E02B 3/06, 3/14

U.S. Cl. 405—16

5 Claims



1. Units for controlling erosion of a bank adjacent a body of water due to waves of the body of water striking the bank, which bank extends upwardly from a strand and which units are positioned generally parallel to the shoreline of the body of water, said units comprising a retaining wall means located on the strand and extending generally parallel to the shoreline for restricting material of the bank from progressing into the body of water, means defining a sand-gravel collecting area immedi-

ately adjacent said retaining wall means and on the side thereof facing the body of water, said means defining said sand-gravel collecting area comprising structure having surfaces which define a chamber open at the top for receiving water and sand and gravel therethrough and passages for directing water and sand and gravel into the sand-gravel collecting area and from the sand-gravel collecting area toward the shoreline and laterally of said retaining wall and generally parallel to the shoreline, said structure including means for breaking the waves before reaching said retaining wall means and said sand-gravel collecting area, said last-recited means comprising a plurality of wave breakers projecting toward said body of water and from said sand-gravel collecting area against which the waves impact, said wave breakers having respective surfaces facing said body of water and against which waves impact, said respective surfaces being spaced different distances from said retaining wall means.

4,297,053

GUTTERING

Terry G. Nicholas, Berkshire, England, assignor to Wavin B.V., Zwolle, Netherlands


Filed Dec. 19, 1979, Ser. No. 105,401

Claims priority, application United Kingdom, Dec. 20, 1978, 49375/78

Int. Cl.³ E02B 9/04

U.S. Cl. 405—121

13 Claims



1. A gutter fitting comprising a body member defining a channel for receiving therein a gutter length, a sealing member extending through a slot in said body member, said sealing member having a sealing portion protruding inwardly of said channel for sealing against a gutter length therein in use and a retaining portion extending transversely of said slot and located within a passage defined between the body member and a retaining member extending over the outside of said body member to retain said sealing member in said fitting.

4,297,054

METHOD OF LAYING OFFSHORE PIPELINE FROM A REEL CARRYING VESSEL

Dennis E. Yenzler, Norco; John H. Cha, Orange, and Dan Abramovich, Mission Viejo, all of Calif., assignors to Santa Fe International Corporation, Orange, Calif.

Filed Aug. 8, 1979, Ser. No. 64,826

Int. Cl.³ B63B 35/04; F16L 1/00


U.S. Cl. 405—168

15 Claims

1. A method of laying pipe offshore from a self-propelled reel pipe laying vessel, said vessel having self-propulsion means, a reel for spooling relatively inflexible pipe thereon, pipe handling means for straightening the pipe as it is unspooled and for guiding the straightened pipe into the water at a presettable adjustable pipe exit angle, and means for maintaining the pipe under a predetermined adjustable tension, said method comprising the steps of:

setting the pipe handling means to establish a desired pipe exit angle at which the pipeline substantially enters its

catenary configuration before exiting the vessel and pipe handling means; and
setting the tensioning means to hold the pipe under a predetermined nominal tension in conjunction with the pipe exit




angle, to establish a minimum radius of curvature of the pipe in the sag bend region which is greater than the minimum radius to which that pipe may be bent without exceeding its elasticity limits as it is unspooled and paid out from the vessel.

4,297,055

METHOD OF INSTALLING UNDERGROUND PIPE
Richard C. Peacock, 2726 Waiwai Loop, Honolulu, Hi. 96819
Filed Feb. 8, 1980, Ser. No. 119,826
Int. Cl.³ E03F 3/06

U.S. Cl. 405—184

5 Claims



1. A method of installing underground pipe comprising forming a horizontal or lateral hole underneath the ground surface by securing a jacking mechanism to one end of a hollow casing, securing a tapered power head at the opposite end of said casing and moving said jacking mechanism to move said power head and associated casing through the ground, providing an open ended flexible tubing, said tubing including an end cap covering one end thereof, inserting a push rod inside said tubing and in contact with said end cap, and after said power head and associated casing have been moved the desired distance pushing said tubing through said hollow casing by use of force applied to said push rod, said push rod contacting said end cap and pushing the tube through said casing without lateral or vertical displacement of said flexible tubing, and removing said push rod and said casing from said power head after said end cap reaches said power head.

4,297,056

METHOD AND H-PILE TIP FOR DRIVING PILES IN PERMAFROST

Dennis Nottingham, 2610 Sorbus Cir., Anchorage, Ak. 99504
Filed Aug. 3, 1979, Ser. No. 63,381
Int. Cl.³ E02D 5/74


U.S. Cl. 405—232

5 Claims

1. A method for driving piles in frozen soil comprising the following steps:

- drilling a pilot hole along the desired pile alignment;
- inserting water into the pilot hole at a temperature suitably above the freezing point of water; and
- driving the pile through said pilot hole a predetermined

period of time thereafter calculated to permit the transfer of a sufficient amount of heat from the water to the frozen



soil surrounding said pilot hole to reduce the resistance of the frozen soil to the driving of said pile.

4,297,057

PIVOTAL ROOF BOLTER AND EXTENDABLE ROTATABLE PROTECTIVE CANOPY FOR MINING MACHINE


John C. O'Neil, deceased, late of Columbus, Ohio (by Jean M. O'Neil, executor), assignor to Dresser Industries, Inc., Dallas, Tex.

Filed Dec. 26, 1978, Ser. No. 972,759

Int. Cl.³ E21D 19/04

U.S. Cl. 405—303

5 Claims



1. A pivotal protective canopy for an underground mining machine which has a work performing apparatus which is pivotable about a vertical axis in order to perform its work at different locations without moving the machine, which canopy is pivotable independent of but associable with the apparatus such that an operator can operate the apparatus while under protection of the canopy, comprising:

- a vertically extensible support mast including a first tubular section affixed to the mining machine, and a second tubular section slidably engaged with the first section;
 - a fluid-pressure operated cylinder disposed interiorally of the tubular sections with one of its ends connected to the first section and its other end connected to the second section; and
 - a canopy shield pivotally mounted on the second tubular section and cantilevered extending therefrom;
- wherein the mast and cylinder are cooperatively operable to raise and lower the canopy shield with respect to the mine roof, and the sliding fit between the tubular mast sections is such that all the moment loads from the canopy shield are transferred through the mast sections to the mining machine, while the fluid cylinder incurs substantially only axial compressive load.

4,297,058

INDEXABLE CUTTING INSERT


William D. Armbrust, Greensburg, and James F. McCreery, Latrobe, both of Pa., assignors to Kennametal Inc., Latrobe, Pa.

Filed Jun. 30, 1980, Ser. No. 164,808

Int. Cl.³ B26D 1/00

U.S. Cl. 407—113

11 Claims



1. An indexable polygonal cutting insert designed to be driven in a forward direction comprising: a top face; a bottom face; a peripheral wall joining said top and bottom faces; said peripheral wall having a plurality of groups of angularly related faces; said angularly related faces within one of said groups having a planar clearance face adjoining said bottom face and obliquely sloping upwardly and outwardly at an acute angle, A; a substantially vertical wiper face, inclined at an acute angle, B, to a vertical plane and having a height, X, interposed between and joining said clearance face to said top face; a planar lead clearance face joining and located forward of said clearance face and inclined at an oblique acute angle, C, forwardly and inwardly from said planar clearance face; said lead clearance face adjoining said bottom face and obliquely sloping upwardly and outwardly at an acute angle, D; a substantially vertical lead wiper face, inclined at an acute angle, E, to a vertical plane and having a height, Y, interposed between and joining said lead clearance face to said top face; said lead wiper face located forward of said wiper face and inclined at an oblique acute angle, C, forwardly and inwardly from said wiper face; a rear relief face joining and located to the rear of said wiper and said clearance faces and joining said top face; and said rear relief face sloping rearwardly and inwardly from said wiper face at an angle, F.

4,297,059

APPARATUS FOR FORMING HOLES IN PLATE GLASS
Masaaki Miyana, 5-15-109 Matsuhamacho, Ashiya, Hyogo, Japan


Division of Ser. No. 919,407, Jun. 26, 1978, Pat. No. 4,209,272.

This application Aug. 6, 1979, Ser. No. 64,133

Int. Cl.³ B23B 51/04

U.S. Cl. 408—202

1 Claim



1. A core drill for plate glass, comprising:
a driving spindle,
a slide member slidably surrounding said spindle and having an outer thread and a chuck part, a sleeve having an inner thread for engagement with said outer thread and adapted

to compress said chuck part against said spindle so that said slide member is fixed to said spindle,
a cup-shaped blade fixed to said slide member and having cutting teeth at its forward end, said blade having an axial wall formed with at least one axial, forwardly open slot, stopper means secured to said forward end of said spindle within said blade for preventing said blade from cutting beyond a predetermined depth,
said chuck part including an axially divided portion having an outer taper, and said sleeve having an inner taper for engagement with said outer taper, such that when said sleeve is turned relative to said slide member, said chuck part will be fixed to or released from said spindle.

4,297,060

ENGRAVING MACHINE


Byron W. Ross, 5839 Avenal Ave., Oakland, Calif. 94605

Filed Nov. 1, 1979, Ser. No. 90,493

Int. Cl.³ B23C 3/00; B43L 13/10

U.S. Cl. 409—86

11 Claims



1. A mechanism for duplicating an image which comprises:
a first generally planar surface having a slot therein;
an elongated slide disposed in said slot which is dimensioned and configured to engage said slot to allow movement thereof;
first and second elongated members each having one end pivotally carried on said elongated slide at respectively first and second points spaced a first distance;
a connecting member which is pivotally connected to the other end of said first and second elongated members at third and fourth points thereof, said third and fourth points being spaced said first distance apart;
third and fourth elongated members each having one end pivotally carried on said connecting member at respectively fifth and sixth points which are spaced said first distance apart;
a support pivotally engaging the other end of said third and fourth elongated members at respectively seventh and eighth points which are spaced said first distance;
means for producing an image on an associated member carried on said support; and
means for following an associated master image carried on said support, said means for following comprising an elongated pointed member which is axially spring biased toward the associated master and which is mounted to allow axial movement of said elongated-pointed member toward and away from the associated master.

4,297,061


STEAM GENERATOR SHELL PARTING METHOD AND APPARATUS

Donald L. Wolfe, Hampton Township, Allegheny County, Pa.; Donald D. Modglin, Nashville, and George J. Merrick, Franklin, both of Tenn., assignors to Westinghouse Electric Corp., Pittsburgh, Pa.

Filed May 10, 1978, Ser. No. 904,686

Int. Cl.³ B23C 1/20, 3/02

U.S. Cl. 409—131



1. Method for effecting horizontal separation of the vertically-extending shell of a steam generator, comprising the steps of:

- installing a plurality of hinged-section tension bands at vertical intervals around said shell,
- adding vertically extending anchor members clamped to the bands and distributed circumferentially therearound,
- hanging and locking track support brackets onto the anchor members,
- assembling, locating, and securing a multiple-section rigidized circular track onto the support brackets, and
- utilizing a milling machine assembly roller guided and supported by such track to cut through said cylindrical shell around its circumference.

4,297,062


CARGO SECURING APPARATUS

Charles J. Sauber, 10 N. Sauber Rd., Virgil, Ill. 60182

Filed Feb. 14, 1980, Ser. No. 121,373

Int. Cl.³ B62D 63/08

U.S. Cl. 410—37



1. A securing apparatus for use with extendable strap means having one of its ends fixed to a support structure and positionable about a cargo to be held, comprising, a generally U-shaped body adapted to be pivotally mounted for rotation about a fixed axis with respect to the support structure, said body defining an opening to receive a looped portion of the free end of said strap means, a shiftable wedge member captively mounted within the body for movement toward and

away from said opening to frictionally bind the strap means with respect to said body, and handle means projecting from said body to pivotally rotate said body about said axis so that said strap means when looped about the wedge member through the body opening is pulled tightly to force said wedge member into binding position within said body opening.

4,297,063

TELESCOPING SELF-RETAINING SAFETY BOLT ASSEMBLY


Dale H. Hart, Seal Beach, Calif., assignor to Hi Shear Corporation, Torrance, Calif.

Filed Jun. 11, 1979, Ser. No. 47,370

Int. Cl.³ F16B 39/02

U.S. Cl. 411—199

9 Claims



1. A self-retaining safety bolt assembly comprising an element having a head, a cylindrical shank with an axis, and an outer cylindrical wall, the element having a first and a second end, an axial passage opening into one of said ends, and a laterally-extending passage in the cylindrical shank and intersecting the axial passage;

- a dog in said laterally-extending passage slidably movable between an extended and a retracted position, whereby the dog extends beyond the maximum diameter of the cylindrical shank in the extended position and retracts entirely within said shank in the retracted position;
- a cam member axially movable in said axial passage and reactive with said dog to retract or to extend the same;
- said cylindrical shank having threads on one end;
- biasing means biasing the cam member in a direction which forces the dog toward its extended position;
- an element having a radially enlarged head and a tubular shank, said tubular shank having a cylindrical bore with an interior wall adapted closely to fit said outer cylindrical wall, said element having an internal thread;
- said tubular shank having an interior groove in said interior wall being axially spaced from said threads in said last named element;
- said tubular shank telescopically fitting over said cylindrical shank with the thread of said element engaging the threads on said cylindrical shank;
- said dog being so disposed and arranged as to extend, when in its extended position, into said groove in at least one relative axial telescoped position of said elements, whereby to prevent separation of said elements unless said dog is retracted.

4,297,064

STAPLE-NAIL FOR SECURING CEILING SUPPORT STRIP TO WALLBOARD

Gene A. Berndtson, Rte. 2, Box 145, Barrington, Ill. 60010

Filed Jan. 4, 1980, Ser. No. 109,546


Int. Cl.³ F16B 15/00

U.S. Cl. 411—470

4 Claims

1. As an article of manufacture, a staple-nail for nailing a thin strip of soft steel to a panel of wallboard comprising a length of relatively hard steel wire bent into "U" shape to form substantially straight long and short legs approximately parallel to one

another joined by a bridging portion, the long leg having a length of substantially one and one-quarter to substantially one and five-eighths inch and which is approximately one-quarter inch to approximately three-eighths of an inch longer than the short leg, the long leg being chamfered to an acute point, the short leg providing a tip which is chamfered on its inner surface to a less acute point so that when the staple-nail is hammered into the strip the long leg readily penetrates the strip



while the short leg resists penetration serving as a fulcrum for the long leg to impart broadwise swinging movement and the bridging portion being in the form of a unidirectional curve which merges smoothly with the straight legs to that as the long leg continues its penetrating movement is regionally compresses the wallboard in the direction of the strip until the short leg assumes a final position in which it lies flatly and snugly against the strip.

4,297,065

SELF-LOADING APPARATUS FOR TRANSPORTING LARGE BALES OF MATERIAL


Phillip W. Love, P.O. Box 323, Smithville, Tenn. 37166

Filed Apr. 16, 1980, Ser. No. 140,769

Int. Cl.³ A01D 90/02; B60P 1/08

U.S. Cl. 414—24.5

3 Claims



1. Apparatus for picking up and transporting a large bale of material, such as a bale of hay, comprising:

- a main frame;
- wheel means supporting the main frame through a first pivot axis transverse to the main frame at the rear end portion of the main frame;
- braking means for braking the wheels relative to the main frame;
- a hitch frame having one end pivotally connected to the front end portion of the main frame, with the other end of the hitch frame adapted to be connected to a tow vehicle, so that when the braking means are activated and the tow vehicle is backed up, the front end portion of the main frame swings upwardly, and when the braking means are activated and the tow vehicle moves forward, the front end portion of the main frame swings back downwardly;
- a pair of load engaging and clamping swing arm members pivotally attached to the respective sides of the main frame, each swing arm member being adapted to pivot about an axis substantially parallel to the corresponding side of said main frame to which it is attached; and
- means associated with the main frame and hitch frame for pivotally moving the outward ends of the swing arms away from each other when the forward end of the main frame is swung upwardly and, conversely for pivotally moving the outward ends of the swing arms toward each other when the forward end of the main frame moves back downwardly, whereby a bale of material is picked

up for transportation by raising the front end portion of the main frame member and positioning the apparatus adjacent to the bale so that the swing arms extend outwardly adjacent opposite ends of the bale of material, applying the braking means, and moving towing vehicle forward to simultaneously lower the front end portion of the main frame and pivotally move the swing arms into engagement with the ends of the bale of material, whereupon the bale is engaged, lifted up, and supported by the swing arms.

4,297,066

PAPER SHEET LAYER FORMING AND TRANSFERRING ARRANGEMENT

Bernd Ramcke, Hamburg; Karl-Heinz Schlottke, Tangstedt; Eckhard Brandt, and Klaus Reissmann, both of Hamburg, all of Fed. Rep. of Germany, assignors to E. C. H. Will (GmbH & Co.), Hamburg, Fed. Rep. of Germany


Filed Aug. 13, 1979, Ser. No. 65,874

Claims priority, application Fed. Rep. of Germany, Aug. 12, 1978, 2835416

Int. Cl.³ B65H 31/30, 31/32

U.S. Cl. 414—43

8 Claims



1. An arrangement for forming successive layers of sheets of paper and the like from a stream of individual sheets supplied in succession to a collecting location by a supply conveyor, and for transferring the formed layers to a continuously advancing discharge conveyor, comprising abutment means arranged at the collecting location and movable between a first position in which it extends into, and a second position in which it is spaced from, the stream of the sheets; clamping means including jaws movable together and apart and mounted for movement between the collecting location and the discharge conveyor; and means for moving said abutment means and said clamping means in coordination with one another, including a mechanical transmission interposed between said abutment means and said clamping means, an electric motor kinematically separated from the supply and discharge conveyors and operating said mechanical transmission, and means for controlling the speed of operation of said motor, said controlling means comprising means for effecting acceleration including adjustable counting means, means for effecting deceleration including a first sensor operative to sense a certain position of said clamping means, means for effecting stoppage including a second sensor operative to sense a predetermined initial position of said clamping means, and means for limiting the rotational speed including a signal generator operative to sense the speed of advancement of at least one of said conveyors.

4,297,067

METHOD AND APPARATUS FOR HANDLING PACKED LAYERS OF SUPPORT RODS IN AN ELECTROLYTIC REFINING PLANT


Leo Uusitalo, Tampere, and Pertti Tuominen, Kaaro, both of Finland, assignors to Outokumpu Oy, Finland

Filed Jan. 14, 1980, Ser. No. 111,713

Int. Cl.³ B65G 59/02

U.S. Cl. 414—114

9 Claims



trailing arm; resilient spring means (42) trained between the frame and the rear end of each trailing arm to yieldably resist movement of the wheel in an upward direction relative to the frame; two laterally spaced landing leg mechanisms carried on the frame at corner areas thereof in close adjacency to the cargo container; each landing leg mechanism including inner and outer telescoped tubes bodily adjustable as a unit between a retracted position spaced above ground level and an extended position engaged with the ground, a container lift bracket (72) carried by each outer tube at its lower end for connection with a lower corner area of the container, a nut carried on the upper end of each inner tube, a vertical screw carried by each outer tube in meshed engagement with the nut, and means (78) carried by each outer tube for rotating the associated screw to produce upward motion of the outer tube and associated lift action on the container when the leg mechanism is in its extended position; each container lift bracket being located to have a lifting line of action in the immediate vicinity of the associated landing leg mechanism whereby the landing leg mechanism effectively absorbs the container load.

4,297,069

CHAIR CARRIER


Byron C. Worthington, P.O. Box 434, Gainesville, Fla. 32602

Filed Jan. 2, 1980, Ser. No. 109,690

Int. Cl.³ B60R 9/06

U.S. Cl. 414—462

7 Claims



4. Apparatus for handling a plurality of groups of support rods which have been stacked in layers within a transporting and storage crate in an electrolytic refining plant comprising: transferring means including a pusher member for pushing the uppermost group of supporting rods of the plurality of stacked layers thereof in a longitudinal direction onto a platform located above the seed plate machine; a platform located above a seed plate machine adjacent the transferring means adapted to receive the group of support rods pushed by the pusher member of the transferring means; transporting means for moving the support rod group which has been moved onto the platform onto a rod distribution magazine; and lifting means for lifting the remaining groups of support rods upwardly until the height of the new uppermost group of support rods in the transporting and storage crate is at the same height as the initially uppermost group of support rods.

4,297,068

CARGO CONTAINER TRANSPORTER


Edward Concha, Santa Barbara; Max Jaffe, Pacific Palisades, and Riley Bedford, Torrance, all of Calif., assignors to The United States of America as represented by the Secretary of the Army, Washington, D.C.

Filed Sep. 21, 1979, Ser. No. 77,862

Int. Cl.³ B60P 3/40

U.S. Cl. 414—458

1 Claim



1. A wheeled transporter attachable to one end of a cargo container, said transporter comprising a frame (32) have a leading end and a trailing end; said frame having a depending section (34) adjacent its leading end; a pair of trailing arms (36) swingably connected to the lower end of the frame depending section for movement in vertical planes; a ground-engaged wheel having an axle mounted at an intermediate point on each

1. A wheeled vehicle carrier for motor vehicles comprising: a framework, at least one vertical slide rail attached to said framework; a slide disposed on and movable along said one slide rail; mounting means attached to said slide for mounting a wheeled vehicle thereon; power means for causing powered motion of said slide along said one slide rail; and further including a hood disposed atop said frame and extending outwardly therefrom to cover a portion of said slide and cover a portion of a wheeled vehicle mounted upon said slide in a carrying position, said hood being spaced from said mounting means so as to inhibit the removal of a mounted wheeled vehicle from said mounting means when said slide has moved the wheeled vehicle in a vertical position adjacent said hood.

4,297,070

APPARATUS FOR AUTOMATICALLY DEPOSITING A LOAD IN A PREDETERMINED POSITION

Stuart R. Didtel, Gresham, Oreg., assignor to Cascade Corporation, Portland, Oreg.

Filed Dec. 31, 1979, Ser. No. 108,802


Int. Cl.³ B66F 9/075

U.S. Cl. 414—497

32 Claims

14. In a lift truck having a prime mover for selectively driving said lift truck rearwardly, a load-carrying member extending forwardly from said lift truck, a selectively extendible and retractable push frame mounted on said lift truck for pushing a load from said load-carrying member in a direction forwardly of said lift truck by extension of said push frame with respect to said lift truck and selectively actuated push frame power means connected to said push frame for extending said push frame at a speed of extension with respect to said lift truck, the

improvement which comprises synchronizing means connecting said prime mover responsively to said push frame power



means for actuating said prime mover to drive said lift truck rearwardly in response to actuation of said push frame power means to extend said push frame.

4,297,071

WEIGHT TRANSFER APPARATUS


Glenn G. Dunbar, 2608 Overbrook Dr., Toledo, Ohio 43614

Filed Oct. 1, 1979, Ser. No. 81,026

Int. Cl.³ B60P 1/00

U.S. Cl. 414—542

18 Claims



1. A weight handling vehicle having a rear cargo compartment, said cargo compartment having a bed and opposed sidewalls, frame means positioned adjacent said sidewalls, said frame means including a plurality of ribs positioned adjacent said opposed sidewalls and opposed parallel tracks positioned on the end of said ribs spaced apart from said bed, a telescoping carriage means moveably positioned on said tracks of said frame means, carriage rollers positioned on said carriage means to engage said opposed tracks, a drive means operatively connected to said frame means and said carriage means, said drive means acting to move said carriage means, a first guide means connected to said carriage means to maintain said carriage means in alignment with said tracks, a trolley means moveably mounted on said telescoping carriage means, said trolley means being movable from a first position adjacent the front of the rear cargo compartment to a second position exterior of and spaced from the rearward end of said cargo compartment, a second drive means operatively connected to said carriage means and said trolley means, said second drive means acting to move said trolley means, a second guide means connected to said trolley means to maintain said trolley in alignment with said carriage means, and a vertical lifting means mounted on said trolley means for lifting one or more weight units.

4,297,072

MANWAY HANDLING APPARATUS


Siddharth A. Shah, South Portland; Sidney J. Woodcock, Scarborough, and Robert D. Fagan, Cape Elizabeth, all of Me., assignors to General Electric Company, Schenectady, N.Y.

Filed Oct. 10, 1979, Ser. No. 83,280

Int. Cl.³ B66C 23/06

U.S. Cl. 414—684.3

11 Claims



1. Apparatus for handling elliptical manway covers and the like for sealable tanks and shells and located interior thereof comprising:

- (a) a support arm;
- (b) means for pivotally mounting one end of said support arm on the exterior of the tank or shell adjacent a manway opening therein adapted to receive an internal cover and whereby said arm may be swung horizontally inwardly inboard of said opening;
- (c) a shaft slidably movable and rotatable along its longitudinal axis, and lineary adjustable vertically and horizontally relative to said support arm;
- (d) means for pivotally coupling one end of said shaft to the center of a cover interior of said opening;
- (e) means for actuating said shaft linearily for inserting said cover into and removing said cover from said opening by motion inwardly of said opening; and
- (f) means for rotating said shaft to enable rotation of said cover about the axis of said shaft interior of said opening during insertion and removal operations.

4,297,073

METHOD AND APPARATUS FOR WITHDRAWING AGRICULTURAL MATERIAL FROM STORAGE

Franz Schmid, Bergstr. 5, and Reinhard Schmid, Vordertal 2, both of D-7612 Fischerbach, Fed. Rep. of Germany


Filed Jul. 3, 1979, Ser. No. 54,616

Claims priority, application Fed. Rep. of Germany, Jul. 8, 1978, 2830068

Int. Cl.³ B65G 65/04; A01F 25/20

U.S. Cl. 414—704

16 Claims



2. Apparatus for withdrawing pressed agricultural material from a pile of such material, comprising vehicle-mounted supporting means; a mobile material engaging tool having a predetermined width; an arm for said engaging tool, said arm having a first portion articulately connected with said support-

ing means and a second portion articulately connected with said first portion and said tool; means for moving said engaging tool relative to said arm and for moving said portions relative to each other as well as relative to said supporting means so that said tool can be caused to penetrate into the pile of pressed material from above to separate a quantity of material from the pile while leaving the consistency of the remainder of the material of the pile at least substantially unchanged; and a vehicle-mounted receptacle pivotable between a plurality of positions and having an opening whose width at least equals said predetermined width, said receptacle being located in the path of movement of said tool so that the latter can enter the receptacle while advancing the separated quantity of material away from the remainder of the pile, said first portion of said arm being moveable independently of said receptacle.

4,297,074

DEMOUNTABLE INTERCONNECTION


Paul V. Ballinger, 7630 Westwood, Findlay, Ohio 45840

Filed Jan. 7, 1980, Ser. No. 110,238

Int. Cl.³ E02F 3/81

U.S. Cl. 414—723

15 Claims



1. Apparatus for use with material handling equipment comprising, in combination, a first engageable member for securement to an implement and a second engageable member for securement to said implement, said first and said second members generally defining parallel radially spaced-apart axes, a locking structure rotatably disposed about one of said members and moveable between a first, unlocked position and a second, locked position, and a carriage adapted for securement to a boom of a material handler, said carriage defining at least one first slot for engaging said first member and at least one second slot for engaging said second member, and means for selectively maintaining said locking structure in said second, locked position.

4,297,075

AUTOMATIC STORM PROTECTION CONTROL FOR WIND ENERGY SYSTEM


Marcellus L. Jacobs, and Paul R. Jacobs, both of Rte. 13 - Box 722, Fort Myers, Fla. 33908

Filed May 14, 1979, Ser. No. 38,885

Int. Cl.³ F03D 7/04

U.S. Cl. 416—14

7 Claims



1. A means for protecting a wind energy plant against damage thereto caused in high winds comprising:

a propeller assembly pivotally mounted on a wind energy plant support means;
a hypoid gear drive means mounting said propeller assembly on said support means, said gear drive means offsetting the pivot axis of said propeller assembly from the center of that propeller assembly;
a generator driven by said propeller assembly;
a variable pitch speed control governor on said propeller assembly for changing the pitch of propellers of said propeller assembly in response to wind velocity generated pressure against those propellers in a manner such that propeller speed is independent of any electrical load on said generator, said governor controlling propeller speed until the propellers of said propeller assembly reach maximum speed and feather, means for keeping said propellers facing directly into the wind over the entire power producing range of wind speed until said propellers feather;
pivot means pivotally connecting said propeller assembly to a tail assembly of a wind energy plant, said pivot means including pivot control means for actuating said pivot means after said propellers have feathered so that said propeller assembly will pivot with respect to said tail assembly and said plant support means under the influence of wind pressure exerted on said propeller assembly because of the combination of the hypoid gear drive propeller axis offset and the increased wind pressure created against the feathered propellers when the pitch angle of such propellers is no longer changed by the action of said variable pitch speed control governor; and
said pivot control means further including a snubber assembly connected to said propeller assembly for controlling movement of said propeller assembly during a return movement of said assembly from a pivoted position back to a normal operating position, said snubber further including means for bypassing the control of said propeller assembly during movement of said propeller assembly from a normal operating position to said pivoted position.

4,297,076

WIND TURBINE


Robert E. Donham, Sherman Oaks, and Richard L. Heimbald, Glendale, both of Calif., assignors to Lockheed Corporation, Burbank, Calif.

Filed Jun. 8, 1979, Ser. No. 46,771

Int. Cl.³ F03D 7/04

U.S. Cl. 416—37

13 Claims



1. A wind turbine comprising:
a rotor, said rotor including a plurality of blades, the tip portions of said blades being variable in pitch and adapted to aerodynamically interact with the wind;
support means for supporting said rotor;
load measurement means coupled to said blades for measuring the bending moment on said blades and for providing an output signal representative thereof; and
adjustment means coupled to said load measurement means for varying the pitch of said tip portions in response to said output signal.

4,297,077

COOLED TURBINE VANE


George A. Durgin, Schenectady, and Daniel E. Demers, Melrose, both of Mass., assignors to Westinghouse Electric Corp., Pittsburgh, Pa.

Filed Jul. 9, 1979, Ser. No. 55,833

Int. Cl.³ F01D 5/08

U.S. Cl. 416—97 R

8 Claims



1. A turbine vane having an airfoil portion providing a leading edge, a suction side, a pressure side and a trailing edge, and wherein said airfoil portion is generally hollow to define an internal chamber to receive cooling air, a slit from said internal chamber through said trailing edge generally throughout the radial extent of said airfoil portions, and wherein the opposed internal walls defining said slit converge from generally a broad inlet area adjacent said chamber to a relatively narrow passage downstream thereof, a plurality of radial rows of pin-like members extending transversely across said slit and integral with the opposed walls defining said slit, and wherein the members of each row are radially offset with respect to the members of any adjacent row to intercept the cooling air flowing through said slit at different levels, a hollow insert disposed within said chamber for initially receiving at least a portion of the cooling air entering said chamber, said insert having a wall member generally adjacent said slit inlet area and apertures in said insert wall for directing cooling air exiting therethrough primarily in a direction to impinge on a selected plurality of junctures of said members and at least one wall of said slit to provide sufficient velocity in said cooling air to cause said juncture to induce turbulence in said cooling air as it flows adjacent said wall and downstream of said juncture to effectively cool said vane.

4,297,078

HELICOPTER ROTORS

Alfred C. Martin, Shepton Mallet, England, assignor to Westland Aircraft Limited, Yeovil, England

Filed May 9, 1979, Ser. No. 39,492

Claims priority, application United Kingdom, May 17, 1978, 20226/78


Int. Cl.³ B64C 27/38

U.S. Cl. 416—134 A

25 Claims

1. A helicopter rotor including a rotor head arranged to support a plurality of rotor blades for rotation about a generally vertical axis, said rotor head including, for each rotor blade, an elastomeric bearing having a geometric center and arranged to permit flap, lead/lag and feathering movements of

its associated rotor blade, a lead/lag damper, and resilient support means axially spaced apart from said bearing geomet-



ric center and arranged during operation to provide controlled restraint of blade flap movements.

4,297,079

VARIABLE PITCH MARINE PROPELLER


Don J. Marshall, Churchton, Md., assignor to Goodall Semi-Metallic Hose & Mfg. Co., Chestertown, Md.

Filed Jul. 14, 1980, Ser. No. 168,034

Int. Cl.³ B63H 1/22

U.S. Cl. 416—140

10 Claims



1. A variable pitch marine propeller comprising:
a hub having a central axis of rotation for coaxial mounting on a rotatable shaft;
a plurality of circumferentially spaced apart blades pivotally mounted on axles on said hub through the root portion of said blades to permit independent movement of each of said blades about an axis of rotation substantially parallel to the axis of said hub between a first nested position adjacent said hub and a second extended position;
each of said blades including leading and trailing segments in said root portion of said blades which are hub engageable depending upon the direction of initial rotation of said blades;
cushioning means having at least a portion thereof intermediate said leading and trailing segments of said blades and said hub and mounted in one of said blades and hub for inhibiting the shock of engagement of said blades and said hub;
said cushioning means including water entrance and exit means and means to capture water therein to act as a shock absorber for said blades and hub upon commencement of rotation of said hub.

4,297,080


ROTOR BLADE PITCH CONTROL LINKAGE

Timothy A. Krauss, Sandy Hook, and Stephan Roman, Shelton, both of Conn., assignors to United Technologies Corporation, Hartford, Conn.

Filed Dec. 17, 1979, Ser. No. 104,605
Int. Cl.³ B64C 27/38

U.S. Cl. 416—141

6 Claims



1. A helicopter rotor having:
 - (A) a hub mounted for rotation about an axis,
 - (B) at least one blade extending radially from said hub and supported therefrom for rotation therewith and including:
 - (1) a radially extending flexible spar member connected to the hub to be rotatable therewith,
 - (2) an airfoil section supported from the spar for rotation therewith, and including:
 - (a) a torque tube enveloping the flexible spar and connected thereto at a radial station therealong and extending inwardly from said radial station to form the inner end of the airfoil sections
 - (C) pitch control and support means connected to the inner end of the torque tube and forming a parallelogram therewith including:
 - (1) a bell crank pivotally connected to the hub, and
 - (2) two side link members of equal length connecting opposite ends of the bell crank to the torque tube to thereby form a substantially vertically oriented parallelogram linkage among said bell crank, side links, and torque tube.

4,297,081


LIQUID LEVEL CONTROL SYSTEM

William A. Irvin, 2384 Corbett St., Jacksonville, Fla. 32204
Filed Nov. 5, 1979, Ser. No. 91,102

Int. Cl.³ F04B 41/06, 49/00

U.S. Cl. 417—2

16 Claims



1. In a system for controlling the level of a liquid in a reservoir, said system having motor driven pumps for filling and emptying the reservoir, the pump control subsystem comprising:
 - an air pressure line having one end thereof disposed in said liquid;
 - air pump means for producing pressure in said air pressure line in which said pressure is proportional to the level of said liquid;
 - a mercury manometer utilizing a U-tube and having a pressure input to a first vertical mercury column connected to said air line and an outlet for a second vertical mercury column open to atmospheric pressure;
 - a common electrical contact disposed at the base of said

U-tube and in conductive contact with said mercury columns;

a plurality of electrical pump-up control contacts disposed along said vertical mercury column below the zero pressure level of said mercury, said contacts adapted to be sequentially contacted as said mercury column rises in response to drops in said pressure and to thereby provide a conductive path from said column contact to each pump-up control contact contacted;

a plurality of electrical pump-down control contacts disposed along said second vertical mercury column above the zero pressure level of said mercury, said contacts to be sequentially contacted as said second mercury column rises in response to increases in said pressure and to thereby provide a conductive path from said common contact to each pump-down control contact contacted; and

pump motor control means connected to selected ones of said pump-up and pump-down control contacts for providing a pump starting function when said mercury columns make contact with specific ones of said control contacts and a pump stopping function when said mercury columns breaks contact with other ones of said control contacts; and

subsystem test means connected to said pump and said input to said first vertical mercury column for controlling said pressure to vary from a zero value to a predetermined maximum value to thereby cause said first mercury column to fall and said second mercury column to rise and to therefore sequentially contact each of said control contacts for testing of said pump starting and said pump stopping functions.

4,297,082

VACUUM GETTERING ARRANGEMENT


Howard P. Wurtz, and Eugene W. Peterson, both of Santa Barbara, Calif., assignors to Hughes Aircraft Company, Culver City, Calif.

Filed Nov. 21, 1979, Ser. No. 96,583

Int. Cl.³ F04B 37/02

U.S. Cl. 417—51

19 Claims



1. A vacuum gettering system comprising:
 - a first getter, said first getter being a bulk getter;
 - a second getter, said second getter being a bulk getter;
 - a vacuum enclosure enclosing both said first and second getters in communication with each other; and
 - means for heating both said first and second getters so that when gas is pumped from said vacuum enclosure, said second getter can be heated to an activation temperature to drive off adsorbed gases on said second getter to activate said second getter without high temperature baking of the entire vacuum enclosure.

4,297,083

POSITIVE CONTROL SYSTEM FOR PISTON COMPRESSOR VALVES

Curt von Petery, Denkendorf, Fed. Rep. of Germany, assignor to Gutehoffnungshütte Sterkrade A.G., Oberhausen, Fed. Rep. of Germany


Filed Nov. 7, 1979, Ser. No. 91,951

Claims priority, application Fed. Rep. of Germany, Nov. 11, 1978, 2849048

Int. Cl.³ F04B 39/08

U.S. Cl. 417—53

2 Claims



1. Positive control system for opening and closing piston compressor valves comprising a piston compressor including a cylinder forming a suction-compression space, a piston reciprocally mounted in said space for alternately effecting a suction stroke and a compression stroke, a suction line for supplying gas into said space, a delivery line for conveying gas out of said space, a suction valve in said suction line, and a delivery valve in said delivery line, wherein the improvement comprises a rated value comparator unit, a first pressure sensor located in said space and connected to said comparator unit, a second pressure sensor located in said delivery line and separated from said space by said delivery valve, said second pressure sensor being connectible to said comparator unit during the compression stroke of said piston, a third pressure sensor located in said suction line and separated from said space by said suction valve, said third pressure sensor being connectible to said comparator unit during the suction stroke of said piston, a control unit, a conduit connecting said comparator unit and said control unit, a first control line extending between said control unit and said delivery valve, a second control line extending between said control unit and said suction valve, so that during the suction stroke said first and third pressure sensors convey signals to said comparator unit and based on the differential in pressure sensed and rated differential value said comparator unit conveys a signal to said control unit for selectively opening said suction valve when the differential pressure is equal or approximately equal to zero and for selectively closing said suction valve when the differential pressure varies by a specific value, and during the delivery stroke said first and second pressure sensors convey signals to said comparator unit and based on the differential in pressure sensed and a rated differential value said comparator unit conveys a signal to said control unit for selectively opening said delivery valve when the differential pressure is equal or approximately equal to zero and for selectively closing said delivery valve when the differential pressure varies by a specific value.

4,297,084

GAS ANCHOR

Newell E. Wayt, 2272 Dominguez St., Torrance, Calif. 90501
Filed Dec. 10, 1979, Ser. No. 101,624


Int. Cl.³ F04F 5/46

U.S. Cl. 417—179

5 Claims

1. A gas anchor comprising an elongate vertical coupling with means at its upper end to connect with the lower end of a production tubing, an elongate vertical pipe with an upper end connected with the lower end of the coupling, said pipe having an upper perforated portion to allow for the flow of gas and liquid radially into and out of the pipe and having a closed lower end defining a liquid catch basin below said upper perforated portion, aspirator means within the coupling including an

upwardly opening central liquid conducting means and gas jet nozzle means about the central liquid conducting means and communicating with the pipe below the coupling and directing gas longitudinally upwardly and radially inwardly to converge



4,297,085

GUIDE MECHANISM FOR COMPRESSOR SOCKET PLATE


Byron L. Brucken, Miamisburg, Ohio, assignor to General Motors Corporation, Detroit, Mich.

Filed Oct. 31, 1979, Ser. No. 89,996

Int. Cl.³ F04B 1/28

U.S. Cl. 417—222

3 Claims



1. In a variable stroke wobble plate type compressor having a cylinder block, a drive shaft rotatable in said cylinder block a plurality of cylinder bores in said block substantially parallel to the axis of said shaft, pistons arranged to reciprocate in said cylinder bores, a journal plate operated in response to rotation of said drive shaft and drivingly connected to said pistons, the connection of said journal plate to said pistons including a socket (wobble) plate is relatively slidable interface relation with said journal plate, and means for varying the angle of the journal plate relative to said drive shaft and thus the stroke of the pistons in their bores, the improvement comprising a longitudinally extending guide rod supported in a common plane with said drive shaft, said socket plate provided with a radially extending slot of predetermined size receiving said guide rod therethrough for longitudinal and arcuate travel of said socket plate along said rod as a result of said journal plate movement, said slot having semi-cylindrical radially extending guides on opposing surfaces thereof, a bearing body having a central passage through which said rod extends with said central

passage being defined by an inner surface which conforms to and slidably engages the outer surface of said rod, said bearing body having a convex spherical portion thereon, a pair of semi-cylindrical shaped guide shoe members positioned in said slot on opposite sides of said bearing body, each of said guide shoe members configured to conform with its associated guide for radial sliding contact therewith spread over a substantial area, each of said guide shoe members having a concave semi-spherical recess facing each other for receiving and relatively slidably retaining said bearing body convex spherical portion therebetween for relative swiveling movement with a substantial contact area, each of said guide shoe members at each end of said concave semi-spherical recess having a portion substantially slidably bearing on said guide rod to maintain the guide shoe members in substantially parallel planes, whereby said guide shoe members reciprocate radially in their associated guides and reciprocate longitudinally along said rod together with said bearing body retained by said guide shoe members in relative swiveling relationship during the operation of said journal plate in response to rotation of said drive shaft.

4,297,086

FLUID MOTOR-PUMP UNIT


Peter T. McGowan, Fort Lauderdale, Fla., assignor to The Garrett Corporation, Los Angeles, Calif.

Filed Feb. 16, 1979, Ser. No. 12,913

Int. Cl.³ F04B 1/16, 17/00; F01L 33/02

U.S. Cl. 417—271

22 Claims



1. A fluid motor-pump assembly for transferring power between first and second hydraulic fluid systems, comprising a housing having first high and low pressure ports coupled to said first hydraulic fluid system and second high and low pressure ports coupled to said second hydraulic fluid system; a first motor-pump unit for moving fluid from said first high pressure port to said first low pressure port, and a second motor-pump unit driven by said first motor-pump unit for pumping fluid from said second low pressure port to said second high pressure port, said first and second motor-pump units each comprising a cylinder block rotatably fixed within said housing having a plurality of axially extending cylinders formed therein each receiving a reciprocal piston and including a cylinder block port for communication with the associated high and low pressure ports, a central rotatable shaft within said housing with said cylinders circumferentially arranged with respect thereto, means coupled between said shaft and said pistons for converting between rotational and reciprocal motion, a valve plate rotatable with the shaft in running alignment with said cylinder block and between the associated high and low pressure ports, said valve plate including valve ports for sequentially communicating said cylinder block ports respectively with the associated high and low pressure ports upon shaft rotation, and a pressure-balancing member rotatably fixed within said housing in running alignment with said valve plate opposite said cylinder block and including a plurality of means generally aligned axially with respective ones of said cylinder block ports and each responsive to fluid pressure at its associated cylinder block port for urging said member axially against said valve plate for dynamically pressure-balancing axial forces applied to said valve plate regardless of the position of valve plate rotation, said plurality of means of each of said first and second motor-pump units in-

cludes a plurality of circumferentially arranged, generally axially extending fluid passages formed in said pressure-balancing member for communicating with said cylinder block ports through said valve ports upon valve plate rotation for receiving fluid under pressure whereby the fluid pressure within each said passage corresponds with the fluid pressure on the opposite side of said valve plate regardless of valve plate rotational position, each of said passages comprising a relatively small orifice passage for communicating with said valve ports, and a relatively enlarged cylinder, said relatively enlarged cylinders formed within said pressure-balancing member being radially staggered with respect to each other, radially inwardly staggered ones of said balancing member cylinders being formed to have a diameter relatively larger than radially outwardly staggered ones of said balancing member cylinders, and including fluid sealing means for sealing said passages and for engaging said housing for pressure-reacting against said housing to urge said member axially toward said valve plate, said fluid sealing means comprising a plurality of sealing pistons respectively received within said passages; said means for converting between rotational and reciprocal motion being common to said first and second motor-pump units whereby said second motor-pump unit is drivingly operated by said first motor-pump unit for power transfer therebetween, said valve plates of said first and second motor-pump units being mounted on their respective shafts generally in phase with each other.

4,297,087

APPARATUS FOR PUMPING FLUID FROM A WELL THROUGH A TUBING STRING


Neil H. Akkerman, Kingwood, Tex., assignor to Baker International Corporation, Orange, Calif.

Filed Aug. 23, 1979, Ser. No. 69,209

Int. Cl.³ F04B 9/08

U.S. Cl. 417—378

27 Claims



1. An apparatus for pumping fluid from a subterranean well through a tubing string, comprising: pump means connected to the tubing string and responsive to the cyclic application of pressure to the fluid in the tubing string for pumping fluid from the well into the tubing string; and means for cyclically applying pressure to the fluid in the tubing string to actuate said pump means and to supply energy to the tubing string, said means for cyclically applying pressure being responsive to the fluid in the tubing string to capture and substantially reuse said energy within and through the tubing string.

4,297,088

PUMP ASSEMBLY COMPRISING GAS SPRING MEANS


Neil H. Akkerman, Kingwood, Tex., assignor to Baker International Corporation, Orange, Calif.

Filed Sep. 7, 1979, Ser. No. 73,335

Int. Cl.³ F04B 47/08

U.S. Cl. 417—378

28 Claims



1. In an apparatus for pumping fluid from a source through a conduit, including pump means connected to the conduit and responsive to the cyclic application and withdrawal of pressure to the fluid in the conduit for pumping fluid from the source into the conduit, the pump means comprising: piston means for pumping the fluid and responsive to the application of pressure to the fluid in the conduit for moving in a first direction; gas spring means for moving said piston means in the opposite direction when said pressure is removed from the fluid in the conduit; a fluid filled chamber defined by a cylinder closed at one end by said piston means and at another end by said gas spring means and in fluid communication between said piston means and said gas spring means; and means for connecting said chamber to the conduit to replace any fluid lost from said chamber during the operation of said piston means.

4,297,089

ARCuate TUBULAR PUMP


Dante S. Giardini, Dearborn Heights, Mich., assignor to Ford Motor Company, Dearborn, Mich.

Filed Dec. 26, 1978, Ser. No. 973,278

Int. Cl.³ F01B 19/00; F04B 45/06

U.S. Cl. 417—437

15 Claims



1. A fuel pump for pumping noncompressible fuel to a multi-chambered internal combustion engine comprising: a plurality of C-shaped tubular members being resiliently flexible in a generally radial direction;

each C-shaped tubular member being arced about a common line; each C-shaped tubular member having a hollow interior; a housing member anchoring one end of each C-shaped tubular members; said housing member connected to said engine; said housing member having a plurality of passageways; each passageway having an inlet and outlet; each of said hollow interiors of each respective C-shaped tubular member in fluid communication through said respective anchored end with said passageway between said inlet and outlet; a one-way check valve means operably connected to said inlet for allowing fuel to pass through said inlet into said passageway; camming means mounted in proximity to a free opposing end of each C-shaped tubular members and opposing said anchored ends movable to flex said free ends to change the volume of said hollow interiors a predetermined amount and movable to allow said C-shaped tubular members to resiliently flex back to return the volume of said hollow interiors to their initial amounts, whereby fuel passes into each hollow interior and is forced out from each hollow interior through said outlets upon a decrease in volume of said hollow interiors; said camming means sequentially flexing and releasing each C-shaped tubular member in a predetermined sequence corresponding to the firing sequence of the respective combustion chambers of said engine; a cam shaft rotatably mounted about its longitudinal axis through a generally convex shaped area bordered by said C-shaped tubular members; a plurality of cams on said cam shaft; a plurality of deflector members pivotably connected about substantially aligned pivot axes to said C-shaped tubular members in proximity of said free end spaced away from said pivot axes; said respective cams abutting said deflector member at a distance from where said deflectors abut said C-shaped members.

4,297,090

ROTARY EXPANSION POWER UNIT WITH VALVE DISC CONNECTED TO CRANKSHAFT


Ralph M. Hoffmann, Eden Prairie, Minn., assignor to Trochoid Power Corporation, Eden Prairie, Minn.

Filed Oct. 29, 1979, Ser. No. 89,220

Int. Cl.³ F01C 1/22, 19/00, 21/12

U.S. Cl. 418—61 A

13 Claims



1. A rotary expansion power unit including a housing having opposite end walls spaced apart along a first axis by a peripheral wall shaped to define an epitrochoidal cavity symmetrical about said first axis, a rotor symmetrical about a second axis, parallel to said first axis, and movable in said cavity in sealing

relationship to define a plurality of working chambers, crankshaft means, having an eccentric member on which said rotor rotates on said second axis eccentrically with respect to said first axis, for limiting motion of said rotor in said cavity to planetating movement about said first axis, and means for conducting and controlling expansion fluid flow into and from said working chambers comprising:

- at least one valve disc secured to a corresponding side face of said eccentric member and extending between a corresponding said end wall and said rotor, said at least one valve disc defining an annular disc cavity facing said corresponding end wall,
- supply passage means for directing a continuous flow of expansion fluid to said disc cavity,
- bridging passage means in the inner surface of said corresponding end wall to conduct expansion fluid from said disc cavity to said working chambers during first predetermined portions of rotor movement, and
- exhaust passage means for affording egress of expansion fluid from said working chambers during second predetermined portions of rotor movement.

4,297,091

ALFALFA PELLETIZING APPARATUS


Michael R. Strefling, 425 S. 27th St., South Bend, Ind. 46615

Filed Mar. 10, 1980, Ser. No. 129,398

Int. Cl. A01F 29/00; B29J 1/00

U.S. Cl. 425-84

8 Claims



1. Apparatus for pelletizing small alfalfa particles mixed with water comprising a frame, spaced sprockets journaled on said frame, a belt unit trained around said sprockets, means for driving a sprocket, said belt having a plurality of pellet-forming open ended apertures therein and a drain passage located at the central portion of each aperture, opposed pelletizing rollers journaled on said frame and each including a plurality of pelletizing fingers, each finger being adapted to enter an aperture and cooperate with an opposed finger to compress alfalfa particles in the central portion of the aperture and to expel liquid from said compressed particles and through said drain passage of each aperture, and means for releasing pellets from said apertures at a discharge station.

4,297,092

ACCUMULATOR HEAD USED IN THE FORMATION OF A MULTI-LAYER PARISON

John Goron, Bridgewater, N.J., assignor to Midland-Ross Corporation, Cleveland, Ohio

Filed Jun. 30, 1980, Ser. No. 164,787

Int. Cl. B29D 23/03, 23/04; B29C 17/07

U.S. Cl. 425-133.1


15 Claims

1. An apparatus used in the formation of an article composed of resinous material, comprising:

- (a) at least one annular accumulation chamber for receiving and holding resinous material, the chamber having a longitudinal axis;
- (b) an annular discharge orifice spaced from the chamber;
- (c) an annular discharge passageway connecting the orifice and chamber, the portion of the passageway leading from

the chamber being cylindrical about a longitudinal axis which coincides with the longitudinal axis of the chamber;

- (d) an annular ring-piston disposed in the chamber and movable axially thereof, to force resinous material from the chamber through the discharge passageway and orifice;
- (e) an annular compartment with a circular cross-section surrounding the cylindrical portion of the discharge passageway;



- (f) an annular entrance opening in the cylindrical portion of the passageway between the chamber and orifice;
- (g) an annular entrance passageway connecting the compartment and entrance opening, the entrance passageway converging in the direction of the discharge orifice; and
- (h) means communicating with the compartment for moving resinous material into the compartment and through the entrance passageway and opening into the discharge passageway.

4,297,093

COMBUSTION METHOD FOR REDUCING NOX AND SMOKE EMISSION

Kotaro Morimoto, and Tomio Suzuki, both of Kobe, Japan, assignors to Kobe Steel, Ltd., Kobe, Japan


Filed Aug. 31, 1979, Ser. No. 71,487

Claims priority, application Japan, Sep. 6, 1978, 53-110003

Int. Cl. F23M 3/00

U.S. Cl. 431-10

8 Claims



1. A combustion method for reducing the emission of NOx and smoke in a boiler or furnace having a combustion chamber, a burner and a passage of combustion air around said burner, comprising:

- injecting fuel from a fuel injector into a fuel rich zone of said combustion chamber and with a predetermined spread angle;
- introducing combustion air with low velocity into said fuel rich zone; and
- utilizing a swirler located in said passage for combustion air

at a distance of not greater than 200 mm from said fuel injector to swirl combustion air into a fuel lean zone surrounding said fuel rich zone, wherein said swirler is adjusted to provide the swirled air with a mean velocity between 10 m/sec and 30 m/sec, with a swirl number between 0.35 and 1.5 and with a spread angle greater than said spread angle of said fuel, wherein said fuel and said low velocity combustion air in said fuel rich zone are enveloped by said swirled air, whereby the rapid mixing of fuel and air in the initial stage of combustion is suppressed.

4,297,094

FREE-FLOATING COMBUSTION CHAMBER AND STACK


Robert D. Reed; Robert E. Schwartz, and Raymond D. Kraft, all of Tulsa, Okla., assignors to John Zink Company, Tulsa, Okla.

Filed Feb. 19, 1980, Ser. No. 122,274

Int. Cl. F23D 13/20

U.S. Cl. 431-202

8 Claims



1. An improved structure for a burner-stack-furnace system comprising:

- (a) a horizontal base ring of selected horizontal shape and size;
- (b) a vertical stack of selected height, and of horizontal shape and size related to said base ring, attached to and supported on said base ring;
- (c) a plurality of circumferentially-spaced support columns of selected height arranged in a ring of shape and size to receive and support said base ring;
- (d) a combustion section of substantially the same size and shape in cross-section as said stack, and including a plurality of re-entrant vertical channels in the outer wall of said combustion section, one positioned at each of the positions of said support columns, the dimensions of said channels such as to provide air space between said columns and said outer wall; said combustion section pendulously supported from said support ring;
- (e) said combustion section having at least one opening through its circumferential wall in the spaces between columns, for the insertion of at least one fuel burner.

4,297,095

FILAMENT WINDING APPARATUS

David R. Silcox, Gainesville, and John L. Doster, Oakwood, both of Ga., assignors to RCA Corporation, New York, N.Y.

Filed Jan. 28, 1980, Ser. No. 116,260


Int. Cl. F27B 9/28; B65H 54/20, 54/42

U.S. Cl. 432-59

9 Claims

1. A filament winding apparatus comprising: means for transporting a plurality of filaments wound side by side about a moving core, each filament being in contact with said core, means for heat setting said filaments during said transporting, adjustable filament tension control means for simultaneously receiving said plurality of filaments from said means for

transporting and for applying substantially identical tension to each of said received filaments during the time the filaments are being wound by the winding means set forth below, said tension control means including a pair of facing members and means for adjustably resiliently urging said members together, the facing surfaces of said members receiving said filaments therebetween, each said facing surface being in contact with each filament, and winding means including means for receiving a like plurality of filament receiving spools for simultaneously winding



each of said filaments on a different spool, said winding means including a like plurality of friction drive means, each drive means for rotating a corresponding spool by frictional engagement with the outer surface of the windings on the spool, means for urging each friction drive means into continuous engagement with the outer surface of its corresponding spool with negligible slippage between said friction drive means and said outer surface, and timing means for synchronously rotating each of said plurality of, friction drive means.

4,297,096

ALKYL, ALKENYL, AND ARYL SUBSTITUTED TRIAZENE COMPOUNDS, THEIR SALTS AND PRODUCTION THEREOF

Keizo Yoshida, Ibaraki; Hirokazu Tanaka, Takarazuka; Masanori Okamoto; Eiko Iguchi, both of Osaka; Masanobu Kohsaka, Sakai; Hatsuo Aoki, Ikeda, and Hiroshi Imanaka, Osaka, all of Japan, assignors to Fujisawa Pharmaceutical Co. Ltd., Osaka, Japan

Continuation-in-part of Ser. No. 18,158, Mar. 7, 1979, abandoned, and a continuation-in-part of Ser. No. 92,476, Nov. 8, 1979, abandoned. This application Apr. 24, 1980, Ser. No. 143,310

Int. Cl. A01G 47/08, 51/00; C07C 107/02; C12P 13/00

U.S. Cl. 435-128


11 Claims

1. A compound of the formula:




wherein R is alkyl, alkenyl or aryl or its pharmaceutically acceptable salts.

10. A process for the production of FR-900184 substance having the formula:



or FR-900190 substance having the formula



or both, which comprises culturing a FR-900184 and/or FR-900190 producing strain belonging to the genus Streptomyces in an aqueous nutrient medium under aerobic condition and recovering FR-900184 or FR-900190 or both substances from the resultant cultured broth.

11. A process for the preparation of the compound of the formula



wherein R is alkyl, alkenyl or aryl or its pharmaceutically acceptable salts, which comprises reacting a compound of the formula



wherein R is the same as defined above, with hydrazine, reacting the resultant hydrazone derivative with a silylating agent taken from the class consisting of trialkylhalosilane, trialkylsilylamide, dialkyldihalosilane, alkyltrihalosilane, dialkylarylhalosilane, triarylhalosilane, dialkylaralkylhalosilane, dialkoxydihalosilane, and trialkoxyhalosilane and reacting the resultant silylated compound with an n-nitrosating agent.

4,297,097

STERN DRIVE MECHANISM

Elmer C. Kieckhafer, 2408 Cypress Gardens Rd., Winter Haven, Fla. 33880

Filed Feb. 23, 1978, Ser. No. 880,713


Int. Cl.³ B60F 3/00

U.S. Cl. 440—59

13 Claims

1. In a stern drive mechanism for watercraft, a mounting bracket assembly for securement to the transom of a watercraft, said bracket assembly having a horizontal transverse bore therein rearwardly with respect to the transom, a drive unit having an upper housing and a lower housing, said upper housing including a horizontal cylindrical portion with one end of the cylindrical portion being rotatably received in the bore of the bracket assembly, and a bracket assembly addition

having a horizontal bore for rotatably receiving the opposite end of the cylindrical portion and being secured to the bracket assembly, said bracket assembly and the addition thereto serving to rotatably support the drive unit and providing for tilt movement of said unit on a horizontal transverse axis relative to the transom, said upper housing further including a downwardly extending portion generally normal to the horizontal



cylindrical portion, said downwardly extending portion of said upper housing and said lower housing being telescoped one within the other and being threadedly engaged to provide a dirigible connection therebetween for support of the lower housing and to provide for pivotal movement of the lower housing relative to the upper housing whereby to provide for steering control of the watercraft.

CHEMICAL

4,297,098

METHOD FOR GRADUAL COLORING OF HAIR TO A LIGHT BROWN SHADE AND PREPARATIONS FOR USE THEREIN


George F. Dasher, Inverness, and Thomas J. Schamper, Chicago, both of Ill., assignors to Alberto-Culver Company, Melrose Park, Ill.

Filed Aug. 26, 1976, Ser. No. 718,019

Int. Cl.³ A61K 7/13

U.S. Cl. 8—412

4 Claims



1. A preparation for gradual coloring of living human hair to a light brown shade by air oxidation, comprising an aqueous carrier containing from 0.1 to 0.6 percent by weight based on the weight of the preparation of an oxidative dye combination, said dye combination consisting essentially of a mixture selected from the group consisting of (a) the mixture of p-phenylenediamine, pyrogallol, and m-aminophenol, and (b) the mixture of (a) in which p-toluenediamine is substituted on a molar equivalent basis for p-phenylenediamine, the said components of (a) being present in said mixture in the relative weight percents defined by the points within Area F of FIG. 2 including the points falling on Boundary G, or as further defined in (b) with respect to the substitution of p-toluenediamine for p-phenylenediamine, said preparation being free of oxygen prior to application to the hair and being capable of undergoing a progressive light brown color forming reaction on contact with atmospheric oxygen.

4,297,099

PROCESS FOR THE PRODUCTION OF A SYNTHETIC RESIN SHEET MATERIAL WHICH IS DYED UNICOLORED OR MULTICOLORED IN ACCORDANCE WITH A PATTERN

Manfred Simon, Nieder-Kassel; Erwin Möschter, Neunkirchen Seelscheid; Karl-Heinz Spiess, Königswinter, and Richard Weiss, Troisdorf, all of Fed. Rep. of Germany, assignors to Dynamit Nobel Aktiengesellschaft, Troisdorf, Fed. Rep. of Germany


Filed Nov. 15, 1978, Ser. No. 961,012

Claims priority, application Fed. Rep. of Germany, Nov. 15, 1977, 2750984

Int. Cl.³ D06P 5/02

U.S. Cl. 8—484

27 Claims



1. A process for the production of a synthetic resin sheet material having a unicolored or multicolored dye coating applied to at least a selective portion of one surface thereof, said dye coating penetrating uniformly into said sheet material, which comprises applying a dye-containing material to at least one selective portion of a surface of a synthetic resin sheet material, said synthetic resin sheet material containing at least one reactive, crosslinkable component that crosslinks with

itself or with another crosslinkable component contained in said synthetic resin sheet material, and said dye-containing material being capable of migrating into a non-porous sheet formed of said synthetic resin sheet material; controlling the migration of the dye-containing material into the sheet material to a desired depth of penetration; then initiating crosslinking of said at least one crosslinkable component contained in said sheet material and crosslinking said at least one crosslinkable component to a different degree, within said synthetic resin sheet material, to stop further migration of the dye-containing material into said sheet material.

4,297,100

AQUEOUS DYE PREPARATIONS

Zdenek Koci, Binningen, and Hans Mollet, Reinach, both of Switzerland, assignors to Ciba-Geigy Corporation, Ardsley, N.Y.

Continuation of Ser. No. 896,418, Apr. 14, 1978, abandoned.

This application Aug. 17, 1979, Ser. No. 67,584

Claims priority, application Switzerland, Apr. 19, 1977, 4808/77

Int. Cl.³ D06P 1/52, 1/16, 1/10, 1/41

U.S. Cl. 8—527

9 Claims

1. A storage-stable aqueous dye preparation consisting essentially of, relative to the total amount of the preparation:

5 to 50 percent by weight of at least one water-soluble dye; 0.1 to 5 percent by weight of a dispersing agent;

0.1 to 30 percent by weight of at least one further additive, said further additive being an auxiliary selected from the group consisting of:

(a) glycine, 1-aminopropionic acid, 2-aminopropionic acid, betaine hydrate, choline, potassium glutamate, N-methyl glucamine, 2-amino-2-methyl-propanediol-1,3,2-amino-2-ethyl-propanediol-1, 3, tris-(hydroxymethyl)-aminomethane, and hydrolysed proteins having a molecular weight up to 10,000;

(b) ethylenediaminetetraacetic acid, nitrilotriacetic acid, N-hydroxyethyl-ethylenediaminetriacetic acid, diethylenetriaminepentaacetic acid, N,N-(dihydroxyethyl)-glycine, N-(hydroxyethyl)-iminodiacetic acid, amino-tri-(methylenephosphonic acid), 1-hydroxyethane-1,1-diphosphonic acid, α-aminoethanediphosphonic acid, methylenediphosphonic acid, ethylenediphosphonic acid, and the Na, K, NH₄, Li, mono-, di- and triethanolammonium salts thereof;

(c) maltose, saccharose-monolaurate, adducts of 1 mol of methyl glucoside with 5 to 20 mols of ethylene oxides, and xanthane gum;

(d) potassium salts, lithium salts, ammonium salts, choline salts, and amine salts optionally substituted by lower alkyl or hydroxy-lower-alkyl, of lactic acid, α-hydroxyisobutyric acid, gluconic acid, glycolic acid, pyrrolidone-2-carboxylic acid, pyridine-3-carboxylic acid, and pyridine-2,6-dicarboxylic acid;

0.5 to 30 percent by weight of at least one water-soluble anionic polyelectrolyte which is a synthetic polymerisation product containing carboxyl groups, having a molecular weight of 400 to 300,000, and is selected from the group consisting of (a) homopolymers of α, β-ethylenic unsaturated monocarboxylic acids or polyvalent carboxylic acids or their anhydrides, which have been subsequently saponified, (b) co- and ter-polymers of α, β-ethylenic unsaturated monocarboxylic acids or polyvalent carboxylic acids or anhydrides thereof with other polymerisable monomers selected from unsaturated aliphatic or aromatic hydrocarbons, vinyl ethers, vinyl esters, methacrylic acid alkyl esters and unsaturated glyceride oils and diene polymers, and (c) homopolymers of (a) or co- and terpolymers of (b) which are substituted by hydroxyl groups, aldehyde groups, or hydroxyl groups and aldehyde groups;

and water to make up the remainder of the preparation.

4,297,101
PROCESS FOR THE DYEING OF SYNTHETIC
POLYAMIDE FIBERS WITH REACTIVE DYES
ACCORDING TO THE BATCHWISE EXHAUSTION
METHOD

Hans-Ulrich von der Eltz, Frankfurt am Main; Armand Lehmann, Offenbach; Joachim W. Lehmann, Kelkheim, and Hans-Peter Maier, Sulzbach, all of Fed. Rep. of Germany, assignors to Hoechst Aktiengesellschaft, Frankfurt am Main, Fed. Rep. of Germany

Continuation of Ser. No. 64,775, Aug. 8, 1979, abandoned. This application Jan. 13, 1980, Ser. No. 159,443

Claims priority, application Fed. Rep. of Germany, Aug. 10, 1978, 2834997

Int. Cl.³ D06P 3/82

U.S. Cl. 8—531

4 Claims

1. In a process for the dyeing of a textile consisting of or containing synthetic polyamide fibers, with reactive dyes according to the batchwise exhaustion method, the improvement which comprises contacting the textile with an aqueous dye liquor containing one or more water-soluble reactive dyes, the initial pH value of said dye liquor being in the slightly acid to neutral range, for a time of from 5 to 30 minutes while maintaining the temperature of said liquor in the range of from 105° to 140° C., without the addition of an alkali or alkali-yielding agent and without the addition of an acid or acid-yielding agent.

4,297,102
CYCICAL TENSIO-ACTIVE POLYETHERS
 Guy Vanlerberghe, Claye-Souilly, and Henry Sebag, Paris, both of France, assignors to L'Oreal, Paris, France

Filed Mar. 15, 1979, Ser. No. 20,656


Claims priority, application France, Mar. 17, 1978, 78 07914

Int. Cl.³ C07D 323/00

U.S. Cl. 8—406


28 Claims

1. Cyclical tensio-active polyethers of the general formula:



in which A is an amphiphile grouping selected from the group consisting of:


(a) the grouping:



where R₁ and R₂, identical or different, refer to aliphatic radicals having from 1 to 20 carbon atoms, with one of the radicals including at least 8 carbon atoms, or substituted aliphatic radicals having from 6 to 20 carbon atoms, or alkylaryl radicals having from 6 to 20 carbon atoms, the sum of the carbon atoms of R₁ and R₂ being less than or equal to 28, or one of the radicals refers to a dimethylamino-ethyl or -propyl radical, diethylamino-ethyl or


-propyl radical, piperidino-ethyl or -propyl radical, morpholino-ethyl or -propyl radical or alkyl polyhydroxy propylene radical, and u refers to the number zero or 1;

(a₁) the grouping:




where R₄ refers to a non-substituted or substituted aliphatic radical or an alkylaryl radical having from 6 to 20 carbon atoms, n refers to a whole number or a fraction from 1 to 20, and u refers to a number 0 or 1;

(a₂) the grouping:




where u, R₄ and n having the meaning indicated above;


(b) the grouping:



(b₁) the grouping:




(b₂) the grouping:



where in the groupings (b), (b₁), and (b₂) V⁻ refers to a formate, acetate, citrate or lactate anion, and u, n, R₁, R₂ and R₄ have the meanings indicated for the groupings a and a₁;

(c) the grouping:



where R₁, R₂ and u having the meaning indicated for the grouping (a), R₃ refers to an alkyl or hydroxyalkyl radical having from 1 to 3 carbon atoms or to a benzyl radical, and X⁻ refers to a chloride, bromide, iodide, monomethyl sulphate, methyl sulphate or p-toluene sulphate anion;

(c₁) the grouping:

4,297,103
PROCESS FOR THE CONTINUOUS ONE-BATH DYEING
OF PILE FABRICS MADE OF
POLYACRYLONITRILE/COTTON

Udo-Winfried Hendricks, Odenthal, and Klaus Wollny, Monheim, both of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Oct. 26, 1979, Ser. No. 88,680


Claims priority, application Fed. Rep. of Germany, Nov. 16, 1978, 2849667

Int. Cl.³ D06P 3/87

U.S. Cl. 8—534

4 Claims

1. In the continuous one-bath dyeing of a pile fabric composed of a cotton base and an acrylic pile comprising padding the fabric with a dyebath containing a basic dyestuff and a substantive dyestuff, and thereafter steaming the fabric to effect dyeing, the improvement which comprises including in the dyebath a nitrile which swells the acrylic fiber and a salt of an alkyl sulphate of the formula



in which

R' is alkyl with 10 to 16 carbon atoms, and

M is an alkali metal, alkaline earth metal, ammonium, alkylammonium or hydroxyalkylammonium ion.

4,297,104
METHOD OF DETECTING OR IDENTIFYING VIRUS
ANTIGENS, ERYTHROCYTE OR CELL ANTIGENS OR
ANTIBODIES IN A BIOLOGICAL MEDIUM

Matte Claude, Paris, France, assignor to Centre National de Transfusion Sanguine, France


Filed Feb. 23, 1979, Ser. No. 14,547

Claims priority, application France, Feb. 28, 1978, 78 05758


Int. Cl.³ G01N 33/54, 33/80

U.S. Cl. 23—230 B


33 Claims



1. A method of analysing a biological medium to detect or identify virus, antigens or erythrocyte or cell antigens or antibodies in the medium, the method involving immunological reactions between cells or particles, a serum and an antiglobulin, the reaction of analysis being conducted in a vessel the wall of which has a point of convergence or apex situated on the axis of symmetry of the vessel, wherein molecules of a reactant capable of immunologically reacting with the antiglobulin are fixed on the walls of the vessel, said antiglobulin being chosen for its capacity to immunologically and independently bind the cells or particles characterizing either positive or negative reaction with said molecules of reactant, then subjecting the reaction medium to a centrifugal force substantially parallel to said axis under conditions such that in a first period all the cells or particles, whether they characterize a reaction with a positive result or a negative result, progressively stick to and remain stuck to the wall of the vessel, the centrifugal force in said first period being such as to prevent a collection of said particles at the apex of the vessel, and then in a second period, only the cells or particles characterizing one kind of reaction remain stuck to the wall of the vessel whereas the cells or particles characterizing the other kind of reaction are collected at the apex of the vessel.




(c₂) the grouping:



where in these groupings (c₁) and (c₂) u refers to the number 0 or 1, n refers to a whole number or a fraction from 1 to 20, and R₄ has the meanings indicated for the grouping (a₁);


(d) the grouping:



where Q⁻ refers to one of the following groupings:



where m refers to 1, 2, or 3,




or




and R₁ and R₂ have the meaning indicated for the grouping (a);

(d₁) the grouping:



and

(d₂) the grouping:



where in groupings (d₁) and (d₂) n refers to a whole number or a fraction from 1 to 20 and Q⁻ has the meaning indicated for grouping (d).

27. A dye composition for the hair containing in an water or water-alcohol solution at least one polyether of claim 1 and one or more dyes selected from the group consisting of anthraquinone dyes, azoic dyes, nitrobenzene dyes, indoaniline dyes, indophenol dyes, and indamine dyes in an amount of 0.001 to 1% by weight of said dye composition.

4,297,105

AUTOMATIC PHOTOMETRIC TITRATOR


Ghyslain Dube, Arvida, Canada, assignor to Alcan Research and Development Limited, Montreal, Canada

Filed Jun. 27, 1980, Ser. No. 163,701

Int. Cl.³ G01N 21/76, 31/16

U.S. Cl. 23—230 R

12 Claims



1. A method for detection of end-point in acid-base titration reactions to determine acid in an acid-containing material, said method comprising placing a quantity of a chemiluminescent indicator together with a sample of the acid-containing material to be analyzed into a vessel, gradually adding a suitable basic titrant to the vessel whilst monitoring by means of a light detector the intensity of light emission from the indicator, obtaining the first derivative with respect to time of the output signal of the light detector and detecting when the first derivative of the output signal reaches an amplitude level indicative of the acid-base reaction end-point.

4,297,106

RAPID METHOD FOR THE MEASUREMENT OF IODINE VALUE

Akira Makino, Yokosuka, Japan, assignor to The Nisshin Oil Mills, Ltd., Tokyo, Japan

Filed Aug. 1, 1980, Ser. No. 174,427

Claims priority, application Japan, Aug. 2, 1979, 54/98127

Int. Cl.³ G01N 31/00

U.S. Cl. 23—230 HC

3 Claims

1. A rapid method for the measurement of iodine value according to the Wijs method wherein reaction is greatly reduced by means of a catalyst selected from the group consisting of magnesium acetate or sodium acetate.

4,297,107

FUELS AND THEIR USE

Günther Boehmke, Leverkusen, Fed. Rep. of Germany, assignor to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Nov. 30, 1979, Ser. No. 99,122

Claims priority, application Fed. Rep. of Germany, Dec. 16, 1978, 2854540

Int. Cl.³ C10L 1/18, 1/22

U.S. Cl. 44—51

12 Claims

1. A fuel for a combustion engine consisting essentially of a hydrocarbon, water and a non-ionic emulsifier, said non-ionic emulsifier consisting essentially of the addition product of ethylene oxide or propylene oxide and a carboxylic acid amide with 9 to 21 carbon atoms, said non-ionic emulsifier being present in said fuel in an amount of 0.5 to 6% by weight.

4,297,108

DESULFURIZATION OF COAL

Carl Horowitz, and Michael Dichter, both of Brooklyn, N.Y., assignors to Polymer Research Corp. of America, Brooklyn, N.Y.

Continuation-in-part of Ser. No. 904,505, May 10, 1978, abandoned. This application Apr. 22, 1980, Ser. No. 142,828

Int. Cl.³ C10L 9/02

U.S. Cl. 44—1 SR

10 Claims

1. Method of removing organic sulfur from coal from which

the main portion of pyritic sulfur has been removed by froth flotation but which still contains sulfur mainly in the form of organic sulfur and to some extent in the form of pyritic sulfur, which comprises treating such coal containing said organic sulfur with dilute nitric acid, thereby oxidizing any remaining pyritic sulfur and also oxidizing organic sulfur, thereby solubilizing the pyritic sulfur and a substantial portion of the organic sulfur, filtering and washing the thus treated coal, thereby removing the solubilized sulfur and nitric acid therefrom, and treating the thus obtained coal still containing organic sulfur with an unsaturated hydrocarbon which binds remaining organic sulfur thereto thus removing the same from the coal, thereby obtaining substantially completely desulfurized coal.

4,297,109

FUEL COMPOSITION

Kazuo Sugito, Kashiwara, and Sakuza Takeda, Tsu, both of Japan, assignors to Sekisui Kaseihin Kogyo Kabushiki Kaisha, Nara, Japan


Filed Jul. 2, 1980, Ser. No. 165,267

Claims priority, application Japan, Jul. 4, 1979, 54/85436

Int. Cl.³ C10L 1/18

U.S. Cl. 44—56

11 Claims



1. A composition useful as a fuel, said composition comprising an admixture of gasoline and a vegetable oil containing 1,8-cineole as a major component, said gasoline and said vegetable oil being admixed in amounts effective for forming fuel having a ratio of gasoline to said vegetable oil of 95:5 to 5:95 by volume.

4,297,110

Nicholas Feldman, Woodbridge, N.J., assignor to Exxon Research & Engineering Co., Florham Park, N.J.

Filed Mar. 31, 1980, Ser. No. 135,994

Int. Cl.³ C01L 1/18

U.S. Cl. 44—66

15 Claims

1. A process for the combustion of a residual fuel oil comprising the steps of:

- dissolving in said fuel oil an effective trace amount of an additive consisting essentially of a zirconium salt of a carboxylic acid selected from the group consisting of C₄–C₂₂ linear or branched fatty acids, tall oil, naphthenic acid, or mixture thereof, said amount being effective in reducing the amount of particulate matter formed during combustion; and
- combusting said resulting fuel oil.

4,297,111

PROCESS AND APPARATUS FOR THE CONTACT AND SEPARATION OF IMMISCIBLE FLUIDS

Leon I. Ross, Grand Cayman, Cayman Islands, assignor to Caribbean Properties Limited, Grand Cayman, Cayman Islands

Continuation of Ser. No. 76,676, Sep. 19, 1979, abandoned,


which is a continuation of Ser. No. 878,389, Feb. 16, 1978,

abandoned. This application Aug. 6, 1980, Ser. No. 175,841

Int. Cl.³ B01D 47/16, 47/18

U.S. Cl. 55—92

38 Claims



26. A process for the continuous contact of a liquid feed with a less dense fluid feed and the subsequent separation of a resultant fluid product from a less dense immiscible fluid product, the process comprising:

- directing a denser liquid feed into and axially through a first conduit, having a generally circular transverse cross-section surrounding a central longitudinal axis, into an overlapping coaxial second conduit, the second conduit also having a generally circular transverse cross-section overlapping the outlet from the first conduit, and defining a generally annular passage between the interlapped walls of the coaxial first and second conduits,
- spinning the denser liquid feed emerging from the generally circular outlet of the first conduit around the longitudinal axis thereof fast enough to form the emerging denser liquid into a generally continuous spinning liquid curtain connecting the rim of said first conduit outlet directly with the overlapping wall of the second conduit, thereby curtaining off the annular passage between the interlapped walls of the coaxial conduits,
- directing a less dense fluid feed into and through said annular passage axially and into and through the spinning curtain, the liquid and less dense fluid feeds consequently interacting with one another within the second conduit to yield spinning immiscible fluid products differing in density from one another; two immiscible spinning fluid products separating centrifugally from one another, the less dense fluid product flowing relatively radially inwardly towards the longitudinal axis,
- withdrawing the less dense fluid product from a location relatively near the longitudinal axis; and
- separately withdrawing the denser fluid product from the second conduit.

32. An apparatus for the continuous contact of a denser liquid feed with a less dense fluid feed and the subsequent separation of a resultant denser fluid product from a less dense immiscible fluid product, the apparatus comprising:

- a first conduit, having a generally circular transverse cross-section and a central longitudinal axis, the conduit

being open at one end to provide an outlet having a circular rim, centered upon the longitudinal axis of the conduit and located in a plane generally perpendicular thereto,

- a second conduit, coaxial with and overlapping the first conduit, the second conduit also having a generally circular transverse cross-section and extending axially beyond the rim of the first conduit, the first and second conduits defining a generally annular passage between the interlapped portions, the annular passage having an outlet into the second conduit defined by the rim of the first conduit,
- means for introducing a denser liquid feed into the first conduit and for directing the flow of the denser liquid feed through the first conduit axially toward and into the overlapping coaxial second conduit,
- means for causing the denser liquid feed to spin about the longitudinal axis of the conduit as the liquid emerges from the outlet of the first conduit fast enough to form the emerging denser liquid into a generally continuous spinning fluid curtain connecting the rim of the said first conduit outlet with the overlapping second conduit, thereby curtaining off the outlet from the annular passage between the interlapped coaxial conduits,
- means for introducing a less dense fluid feed into and through the annular passage between the interlapped walls of the coaxial conduits and into the second conduit, so as to intercept the spinning denser fluid curtain,
- an outlet for the less dense fluid product located relatively near the longitudinal axis; and
- separate outlet for the denser fluid product from the second conduit.

4,297,112

DEODORIZATION OF EDIBLE OILS

Leonard Naylor, Hull, England, assignor to Simon-Rosedowns Limited, Hull, England


Filed Nov. 19, 1979, Ser. No. 95,359

Claims priority, application United Kingdom, Dec. 1, 1978, 46896/78

Int. Cl.³ B01D 53/00

U.S. Cl. 55—195

9 Claims



1. A semi-continuous deodoriser comprising a vessel divided into three zones, means for collecting oil to be deodorised in the first zone, means for transferring oil from said first zone to said second zone and means for deodorising oil in the second zone and means for receiving and holding deodorised oil from the second zone in the third zone, means for passing oil continuously to the first zone and withdrawing deodorised oil continuously from the third zone, means for pre-heating the oil to be fed to the first zone by heat exchange with oil from the third zone, means for heating said pre-heated oil to full process temperatures in said first zone prior to transferring it to said second zone comprising oil heating means connected to receive said preheated oil, and means for recirculating the oil through said oil heating means and through said first zone

comprising oil flow passages interconnecting said oil heating means and said first zone to provide a recirculation circuit and means for introducing a motive gas effectively under pressure into said circuit.

4,297,113

GAS FILTRATION APPARATUS


Louis Theodore, 51 Maple Dr., New Hyde Park, N.Y. 11040

Filed Mar. 3, 1980, Ser. No. 126,553

Int. Cl.³ B01D 46/00

U.S. Cl. 55—213

5 Claims



1. Apparatus, for removing particulate material from a gas stream, comprising a housing having inlet means and outlet means, a plurality of gas-permeable hollow mesh filter bags supported in said housing and serving to partition the interior of the housing into a first chamber communicating with the inlet means and a second chamber communicating with the outlet means, the interior of all of said filter bags communicating through means defining respective openings with said second chamber, a respective closure for the opening of each filter bag, said closure being a plate hingedly mounted to means defining said opening and responsive to a predetermined increase of gas velocity through the opening, as a result of rupture of the filter bag, to close the opening, a cord attached between the plate and retaining means mounted adjacent to the plate, said retaining means releasably retaining the cord responsive to gas flow and non-rupture of the bag, means on said cord for receiving the retaining means and for releasing the cord upon rupture of the bag, and pressure-sensing means communicating with said first housing chamber and arranged, upon sensing of a predetermined change of pressure in said first chamber as a result of closing of a predetermined proportion of said openings to terminate entry of said gas stream into said housing through said inlet means.

4,297,114

VACUUM CLEANER HAVING BAG CLEANING APPARATUS

Alma A. Hutchins, Pasadena, Calif., assignor to Hutchins Manufacturing Co., Pasadena, Calif.

Continuation of Ser. No. 871,819, Jan. 24, 1978, abandoned. This application Oct. 9, 1979, Ser. No. 82,595

Int. Cl.³ B01D 46/04

U.S. Cl. 55—299

28 Claims

1. A vacuum cleaner comprising:
a casing having an air inlet and an air outlet;
a flexible filter bag in said casing;
a motor driven fan for producing a flow of suction air through said casing between said inlet and outlet and through the material of said bag from the exterior of the bag to its interior to collect dust at the outside of the bag;
a bag cleaning rotor mounted within said bag to turn about an axis and against which the bag is constricted inwardly by said flow of suction air when the fan is in operation; and
means for turning said rotor about said axis;
said rotor having at least one arm which projects outwardly away from said axis in an extended position of the arm

when the rotor is turned while the fan is not in operation, and which has a radially outer portion acting in said extended position of the arm to contact the inside of the bag as the rotor turns and displace dust from the exterior thereof;

said arm being constructed to flex longitudinally in a relation swinging said outer portion thereof from said extended position inwardly toward said axis to a position substantially reducing the effective diameter of the rotor, under the influence of force exerted inwardly by the bag when constricted by said flow of suction air;


said arm including a coil spring and said outer portion thereof including a bag contacting element received about and movable axially along said coil spring.

2. A vacuum cleaner comprising:

a casing having an air inlet and an air outlet;

a flexible filter bag in said casing;

a motor driven fan for producing a flow of suction air through said casing between said inlet and outlet and through the material of said bag from the exterior of the bag to its interior to collect dust at the outside of the bag;



a bag cleaning rotor mounted within said bag to turn about an essentially vertical axis and against which the bag is constricted inwardly by said flow of suction air when the fan is in operation;

means for turning said rotor about said axis;

said rotor having at least one arm which projects outwardly away from said axis in an extended position of the arm when the rotor is turned while the fan is not in operation, and which has a radially outer portion acting in said extended position of the arm to contact the inside of the bag as the rotor turns and displace dust from the exterior thereof;

said arm being constructed to flex longitudinally in a relation swinging said outer portion thereof from said extended position inwardly toward said axis to a position substantially reducing the effective diameter of the rotor, under the influence of force exerted inwardly by the bag when constricted by said flow of suction air; and

a member within the bag at a location beneath said rotor and acting to limit constriction of the lower portion of the bag.

4,297,115

BAG-TYPE FILTER WITH AIR DIFFUSER TUBES OF HELICAL CONSTRUCTION

Allen S. Johnson, Jr., Salisbury, N.C., assignor to Staclean Diffuser Company, Salisbury, N.C.

Continuation-in-part of Ser. No. 76,605, Sep. 18, 1979, Pat. No. 4,231,770. This application Aug. 18, 1980, Ser. No. 178,847

Int. Cl.³ B01D 46/04

U.S. Cl. 55—302

10 Claims

1. In a filter apparatus of the type wherein a particulate-laden gas is directed through a tubular filter bag for filtering and retaining the particulate material on the exterior of the bag, and wherein the filter bag is cleaned by a periodic reverse purge of air into the bag, said filter bag having an outlet end for

discharge of the filtered gas and being supported by a tubular supporting cage positioned within said filter bag, the combination therewith of

a hollow air diffuser tube formed from a perforated strip of helically wound sheet metal and extending longitudinally within said tubular supporting cage, and wherein adjacent edges of said strip are interconnected by a seam in which said adjacent edges overlap each other in interlocking relationship and with said seam thus extending helically



around said air diffuser tube, and said tube being in communication with said outlet end of said filter bag for receiving a reverse purge of air therein for diffusing and distributing the air throughout said filter bag when a periodic reverse purge of air is directed into the outlet end of the filter bag so as to more effectively clean the filter bag while also reducing excessive flexing of the filter bag and abrasive wear thereof to thereby provide a substantial increase in the efficiency of the filter apparatus and a significant increase in the life of the filter bag.

4,297,116

APPARATUS FOR SEPARATING FOREIGN MATTER FROM A GAS STREAM

Kenneth M. Cusick, Amarillo, Tex., assignor to Aitken, Inc., Houston, Tex.


Continuation of Ser. No. 922,904, Jul. 10, 1978, abandoned, which is a continuation-in-part of Ser. No. 754,366, Dec. 27, 1976, abandoned, which is a continuation-in-part of Ser. No. 598,566, Jul. 24, 1975, abandoned, which is a

continuation-in-part of Ser. No. 572,352, Apr. 28, 1975, abandoned. This application Jan. 31, 1980, Ser. No. 117,045

Int. Cl.³ B01D 50/00

U.S. Cl. 55—319

15 Claims



1. A separator for receiving an incoming contaminated gas stream containing foreign suspended particles therein, comprising:

(a) an elongate vessel defining a chamber having an inlet for

receiving said contaminated gas stream and an outlet for discharging gas substantially free of said foreign particles;
(b) an impermeable wall in said chamber between said inlet and said outlet for dividing said chamber into a separate gravity chamber having said inlet and a separate filter chamber having said outlet, said wall having at least one port therethrough;

(c) a conical strainer-diffuser member disposed inside said gravity chamber and connected relative to said inlet to receive contaminated gas flow therefrom, said strainer-diffuser member having:

(1) a conical side wall forming a conical bore tapering inwardly relative to the direction of contaminated gas flow from said inlet, said conical side wall having a plurality of spaced holes extending transversely therethrough, said holes having a diameter ranging between 1/16 inch to 1/8 inch and opening in multiple radial directions from said conical bore within said gravity chamber;

(2) an open front end substantially coextensive with said inlet to said vessel, and connected relative thereto for said front end to receive all of the incoming contaminated gas;

(3) said holes in said conical side wall forming substantially the only exit for said contaminated gas entering said gravity chamber, said holes having a total area greater than the area of said inlet and having inner edge portions protruding inwardly into said conical bore and forming barriers around the inner edges of said holes, damming the flow of liquid particles over the inner surface of said conical side wall and through said holes, causing said liquid particles to form large drops which are subsequently jetted outside of said diffuser member through said holes with said gas and into said gravity chamber, most of the jetted-out large liquid drops falling to the bottom of said gravity chamber; and

(d) at least one filter element disposed in said filter chamber and with said filter element in communication with said port in said chamber dividing wall for receiving the gas stream from said gravity chamber and filtering out fine foreign particles from gas passing through said filter element so that substantially particle free gas will exit from said outlet of said vessel.

4,297,117

RESPIRATORY DEVICE FOR CATASTROPHIC FIRES AND/OR SMOG WEATHER CONDITIONS

Heinz Holter, Gladbeck; Heinz Gresch, Dortmund-Derne, and Heinrich Igelbuscher, Gladbeck, all of Fed. Rep. of Germany, assignors to Industrie-Wert Beteiligungsgesellschaft mbH, Mainz, Fed. Rep. of Germany


Filed Jun. 19, 1979, Ser. No. 50,277

Claims priority, application Fed. Rep. of Germany, Jun. 21, 1978, 2827115; Aug. 28, 1978, 2837469

Int. Cl.³ B01D 39/14, 53/04, 53/22

U.S. Cl. 55—389

11 Claims



1. A respiratory filter element for catastrophic fires and/or smog weather conditions characterized by a fleece-like material that is reinforced with adsorption materials comprising soda lime, active carbon dust, and either copper dust or manga-

nese dioxide dust or both copper dust and manganese dioxide dust, and thus characterized in that the adsorption material is deposited on a base material made of expanded calcium-aluminum-silicate and that the base material is embedded in the fleece-like material.

4,297,118


CONTROLLING OVERHEATING OF VACUUM MOLD USED TO SHAPE GLASS SHEETS

John D. Kellar, Pontypool, and Gordon F. Pereman, Columbus, both of Canada, assignors to PPG Industries, Inc., Pittsburgh, Pa.

Filed Mar. 18, 1980, Ser. No. 131,337
Int. Cl.³ C03B 25/035

U.S. Cl. 65—104

10 Claims



1. A method of shaping a glass sheet, comprising the steps of: supporting a heated sheet on support means in a shaping chamber having a heated interior, the sheet heated to approximately its shaping temperature; transferring the heated sheet in the shaping chamber to shaping means to remove the sheet from the support means; shaping the sheet in the shaping chamber by way of the shaping means; transferring the shaped sheet from the shaping means to transfer means, said transferring step practiced in the shaping chamber; advancing the shaped sheet on the transfer means out of the shaping chamber; cooling the shaped sheet; removing the shaping means out of the shaping chamber into an environment cooler than the heated interior of the shaping chamber to permit cooling of the shaping means; and practicing said removing step before practicing said transferring the heated sheet step, shaping step and transferring the shaped sheet step for next subsequent heated sheet on the support means in the shaping chamber.
4. An apparatus for shaping a glass sheet, comprising: elongated heating means to heat a glass sheet to approximately its shaping temperature, said means including a heated shaping chamber; first advancing means to advance a sheet from said heating means to said shaping chamber; means for shaping a sheet; means for moving said shaping means into and out of said heated shaping chamber; second advancing means to advance a shaped sheet out of said heated shaping chamber; first transferring means to transfer a sheet from said first advancing means to said shaping means; second transferring means to transfer a sheet from said shaping means to said second advancing means; means responsive to the movement of a said first advancing means for actuating in succession said shaping means, said

first transferring means and said second transferring means to move a sheet from said first advancing means to said shaping means, to shape a sheet and to transfer a sheet from said shaping means to said second transferring means; means for actuating said moving means to move said shaping means out of the shaping chamber after the shaped sheet is transferred to said second advancing means; and means for activating said second advancing means to move said second advancing means out of said shaping chamber.

4,297,119


APPARATUS FOR VITRIFYING BLAST FURNACE SLAG

Ryo Ando, and Kazuyoshi Sato, both of Yokohama, Japan, assignors to Nippon Kokan Kabushiki Kaisha, Tokyo, Japan

Filed Dec. 4, 1979, Ser. No. 100,055
Int. Cl.³ C03B 5/23

U.S. Cl. 65—141

12 Claims



1. An apparatus for vitrifying blast furnace slag, comprising: an endless conveyor belt including a pair of pulleys, said conveyor belt being formed by endlessly connecting a plurality of rectangular cooling metal members, each of said plurality of cooling metal members being of high thermal conductivity and having, on the outer surface thereof, a plurality of elongated narrow and deep cooling grooves, the longitudinal directions of said cooling grooves being substantially in parallel with the travelling direction of said endless conveyor belt, each of said plurality of cooling grooves comprising an outwardly flaring inlet section for receiving a molten blast furnace slag and an inwardly narrowing cooling section, following said inlet section, for rapidly cooling and solidifying the molten blast furnace slag into a vitreous blast furnace slag, said cooling section of each of said cooling grooves having a top end maximum width within the range of from 3 to 10 mm and a depth within the range of from 2 to 20 times said top end maximum width so as to cool the molten blast furnace slag under constraint to thereby produce a large internal strain in the vitrified blast furnace slag, the vitrified blast furnace slag being in the form of elongated sheets having a maximum thickness of 3 to 10 mm; driving means, connected to at least one of said pair of pulleys, for driving said endless conveyor belt; a molten slag container arranged above the upstream of the upper forwarding position of said endless conveyor belt, said molten slag container being adapted to receive a molten blast furnace slag discharged from a blast furnace and pour said molten blast furnace slag thus received into said plurality of cooling grooves of said cooling metal member reaching the upstream of the upper forwarding position of said endless conveyor belt along with the travel of said endless conveyor belt; a stripper arranged, in the upstream of the lower returning position of said endless conveyor belt, at a prescribed position adjacent to the back surface of said endless conveyor belt, said stripper being adapted to take out a cooled

and solidified vitreous blast furnace slag in said plurality of cooling grooves of said cooling metal member; and, a cooling means arranged at a prescribed position in the lower returning position of said endless conveyor belt, said cooling means being adapted to sequentially cool said cooling metal members heated by the high-temperature molten blast furnace slag poured into said cooling grooves after stripping the vitreous blast furnace slag.

4,297,120


GLASS BENDING TABLE

Robert J. Smith, S. 1215 Mica Park Dr., Spokane, Wash. 99206; Mark A. Smith; Michael E. Jensen, both of S. 1922 Bannen, Veradale, Wash. 99216, and Robert L. Smith, N. 3950 McGuire Rd., Post Falls, Id. 83854

Filed Jul. 28, 1980, Ser. No. 172,994
Int. Cl.³ C03B 23/06

U.S. Cl. 65—281

10 Claims



1. A table for supporting and insulating a flat forming pattern from heated glass tubing to be formed according to the pattern, comprising: a frame; a light transmitting plate mounted to the frame, said plate having a flat top surface and a parallel flat bottom surface; pattern holding means mounted to the frame below the plate for releasably receiving and holding the flat pattern adjacent the flat bottom surface of said plate; screen means supported on the flat top surface of the plate having a working surface thereon spaced above said flat top plate surface and defining an air space between the working surface and top plate surface; wherein said screen means is adapted to support heated glass on its working surface for forming purposes according to a flat pattern viewable on said pattern holding means through the plate and screen means.

4,297,121


GLASS TEMPERING FURNACES AND SYSTEMS

Donald E. Rhonehouse, Cecil, Ohio, assignor to TGS Systems, Inc., Antwerp, Ohio

Filed May 29, 1979, Ser. No. 43,357
Int. Cl.³ C03B 27/00

U.S. Cl. 65—348

20 Claims



1. A conveyor for a glass-tempering system having a supporting frame section, comprising: a first elongated glass-supporting conveyor roller;

an upwardly-open roller support; means mounting said roller support on a frame section; a second roller rotatably mounted in said roller support with its axis parallel to that of said glass-supporting conveyor roller; a driving belt extending between said first and second rollers within said roller support and operable to rotate said conveyor roller; said second roller supporting said driving belt, with said driving belt vertically supporting said first conveyor roller above said second roller; a roller guide supported upon said roller support; a vertically-extending upwardly-open guide slot in said roller guide extending in the same vertical plane as the axis of said second roller and being directly above said axis; said conveyor roller having a projecting axle-like pin received in said guide slot and freely movable vertically therein but restrained horizontally thereby, with said axle-like pin of said conveyor roller being in the same vertical plane as the axle of said second roller; said roller guide having a portion defining a bottom for said slot; said second roller being mounted beneath said conveyor roller at a distance with respect to the bottom of said guide slot such that said conveyor roller axle-like pin is maintained above and out of contact with said bottom of said slot; said conveyor roller being removable by lifting upwardly out of said guide slot whereupon said belt can be removed from said second roller and through said upwardly open roller support; and drive means for driving said belt.

4,297,122


PROCESS FOR THE BIOLOGICAL DEGRADATION OF ORGANIC-CONTAINING WASTE MATTER

Christopher B. Wallace, Fitchburg, Mass., assignor to Bio-Group, Inc., Va.

Filed Apr. 18, 1979, Ser. No. 31,332
Int. Cl.³ C05F 7/00; C02F 3/02

U.S. Cl. 71—12

11 Claims



1. A biological degradation process for the treatment of organic-containing waste matter for producing a waste matter sludge material, the process containing a step for contacting microorganisms with the organic-containing waste matter, which comprises adding to the organic-containing waste matter a microbial activity and microbial population-enhancing concentration of a mineral composite consisting essentially of a naturally occurring glacial deposit comprising from about 4-48 wt. percent Si, 2-35 wt. percent Ca, 1-20 wt. percent Al, 1-15 wt. percent Fe, 0.5-12 wt. percent Mg, 0.1-8 wt. percent Na, 0.01-5 wt. percent K, 0.001-2 wt. percent Ti, 0.0005-2 wt. percent Mn, 0.0005-2 wt. percent P, 0.0005-1 wt. percent Ba and 0.0005-0.5 wt. percent Zn, the mineral composite being in a biologically active size of below about 70% mesh size at 100 mesh, said concentration being below about 1 part by weight mineral composite per 15 parts by weight of organic matter

contained in the waste matter to be treated and above about 1 part by weight mineral composite per 400 parts by weight of organic matter.

4,297,123

METHOD AND APPARATUS FOR PRODUCING A NITRATE FERTILIZER

Harold G. Wyse, 3629 N. Dixie Dr., Dayton, Ohio 45414, and Millard S. Smith, 5625 W. Kochville Rd., Saginaw, Mich. 48604


Filed Feb. 7, 1980, Ser. No. 119,638

The portion of the term of this patent subsequent to Feb. 27, 1996, has been disclaimed.

Int. Cl.³ B01K 1/00; C05C 5/00

U.S. Cl. 71—58

21 Claims



1. A method adapted for efficiently producing a nitrate fertilizer, comprising the steps of forming an air combustion unit including a combustion chamber having a first electrode element defining a circular restriction aperture, arranging a second electrode element concentrically with said aperture, supplying an electrical voltage across said electrode elements to produce an electrical arc therebetween within the aperture, producing a spiral flow of air within the chamber and directing the flow through the restriction aperture at an increased velocity to effect rotation of the arc within the aperture and to assure the air is exposed to the arc for efficiently generating a nitrogen dioxide gas, and introducing the gas from the combustion chamber into a flow of water contained within a tank and being recirculated through an elongated absorption tube having substantial length to produce a nitric acid solution usable as a nitrate fertilizer.

4,297,124

N-TETRACHLORO-ETHYLTHIO-SUBSTITUTED HALOMETHANESULFONAMIDES AS AQUATIC WEED CONTROL AGENTS

Laroy H. Edwards, Napa, Calif., assignor to Chevron Research Company, San Francisco, Calif.


Filed Jan. 28, 1980, Ser. No. 115,586

Int. Cl.³ A01N 31/02

U.S. Cl. 71—66

2 Claims

1. A method for controlling the growth of aquatic weeds comprising applying to said aquatic weeds or their growth environment an amount of the compound of the formula



effective to control the growth of said aquatic weeds.

4,297,125

TREE ROOTING USING SYNTHETIC AUXINS

Bruce E. Haissig, Rhinelander, Wis.; Jack R. Gaines, Rapid City, S. Dak., and Glen Giacometto, Richland, Wash., assignors to The United States of America as represented by the Secretary of Agriculture, Washington, D.C.

Filed Jun. 27, 1979, Ser. No. 52,656


Int. Cl.³ A01N 21/00

U.S. Cl. 71—77


7 Claims

1. A composition for stimulating adventitious root formation in difficult-to-root cuttings, comprising:


an amount sufficient to stimulate adventitious root formation of a compound of the formula




wherein R₁ is



X is (CH₂)_n wherein n is 1-3,



or —O—CH₂—; and R₂ is phenyl or substituted phenyl, with the proviso that n is not 1 when R₁ is



and R₂ is phenyl; and a volatile or inert non-toxic carrier.

4,297,126

IMIDAZOLINYL BENZAMIDES AS PLANT GROWTH REGULANTS

Thomas D. O'Neal, Princeton, N.J., assignor to American Cyanamid Co., Stamford, Conn.

Division of Ser. No. 868,090, Jan. 9, 1978, Pat. No. 4,201,565.

This application Dec. 17, 1979, Ser. No. 103,898

Int. Cl.³ A01N 43/50

U.S. Cl. 71—78

2 Claims

1. A method for eliminating and/or inhibiting bud growth on tobacco plants comprising, applying to the foliage of topped tobacco plants a bud growth inhibiting amount of the compound o-(5-isopropyl-5-methyl-4-oxo-2-imidazolin-2-yl)-N,N-dimethyl-benzamide.

4,297,127

HERBICIDAL USE OF 2,6-DINITROANILINE HERBICIDES

Albert W. Lutz, Princeton, and Robert E. Diehl, Lawrenceville, both of N.J., assignors to American Cyanamid Company, Stamford, Conn.


Division of Ser. No. 777,271, Mar. 11, 1977, Pat. No. 4,165,231, which is a continuation-in-part of Ser. No. 639,729, Dec. 11, 1975, abandoned, which is a division of Ser. No. 538,980, Jan. 6, 1975, Pat. No. 4,066,441, which is a division of Ser. No. 323,000, Jan. 12, 1973, Pat. No. 3,920,742, which is a continuation-in-part of Ser. No. 262,807, Jun. 14, 1972, abandoned, which is a continuation-in-part of Ser. No. 174,938, Aug. 25, 1971, abandoned. This application Jan. 8, 1979, Ser. No. 1,660

Int. Cl.³ A01N 43/84

U.S. Cl. 71—88

4 Claims

1. A method for the preemergence control of undesirable plant species comprising applying to soil containing seeds of the undesirable plant species a herbicidally effective amount of a compound of the formula:



wherein:

Y represents CH₃, C₂H₅, n-C₃-H₇, i-C₃-H₇, sec-C₄H₉ or i-C₄H₉;

R₁ and R₂ taken together with the nitrogen to which they are attached represent morpholino, or dimethylmorpholino.

4,297,128

USE OF IMIDAZOLINYL BENZOATES AS HERBICIDAL AGENTS

Marinus Los, Pennington, N.J., assignor to American Cyanamid Co., Stamford, Conn.


Division of Ser. No. 914,244, Jun. 9, 1978, Pat. No. 4,188,487, which is a continuation-in-part of Ser. No. 822,458, Aug. 8, 1977, abandoned. This application Sep. 13, 1979, Ser. No. 74,940

Int. Cl.³ A01N 43/50

U.S. Cl. 71—92

25 Claims

1. A method for the control of undesirable plant species comprising, applying to the foliage of the plants or to soil containing seeds, seedlings or propagating organs of the plants, a herbicidally effective amount of a compound having the structure:



wherein X is hydrogen, alkyl C₁-C₃, halogen or nitro; R₁ is alkyl C₁-C₄; R₂ is alkyl C₁-C₆, cycloalkyl C₃-C₆, alkenyl C₂-C₄, phenyl, halophenyl or benzyl or when R₁ and R₂ are taken together with the carbon to which they are attached they may represent cycloalkyl C₃-C₆ optionally substituted with methyl; R₃ is hydrogen, alkyl C₁-C₁₂ optionally substituted with one C₁-C₃ alkoxy group or one C₃-C₆ cycloalkyl group or one phenyl group or one furyl group, alkenyl C₃-C₅ optionally substituted with one or two C₁-C₃ alkyl group(s) or one phenyl group or with one to two halogen substituent(s) alkynyl C₃-C₅ optionally substituted with one or two C₁-C₃ alkyl

group(s) or one phenyl group or with one to two halogen substituent(s), benzyl, cyclohexenylmethyl, ethynylcyclohexyl, ethynylallyl or pentadienyl, cycloalkyl C₃-C₆ optionally substituted with one or two C₁-C₃ alkyl group(s); or a salt-forming cation of alkali metals, ammonium or C₁-C₁₈ aliphatic ammonium; and when R₁ and R₂ are not the same the optical isomer thereof, or an isomeric mixture thereof; or except when R₃ is a salt-forming cation, the strong acid addition salt thereof.

4,297,129

3,5-DIOXO-1,2,4-TRIAZINES

Yuzuru Sanemitsu, Masato Mizutani, Seizo Sumida, Haruhiko Katoh, all of Hyogo; Hiromichi Oshio, Osaka, and Shunichi Hashimoto, Sonehigashimachi, all of Japan, assignors to Sumitomo Chemical Company, Limited, Osaka, Japan

Filed Apr. 25, 1980, Ser. No. 143,549


Claims priority, application Japan, Apr. 27, 1979, 54-52968; Aug. 9, 1979, 54-102074; Aug. 17, 1979, 54-105442; Aug. 17, 1979, 54-105443; Aug. 20, 1979, 54-106482; Oct. 30, 1979, 54-140915; Nov. 1, 1979, 54-142539; Nov. 5, 1979, 54-143551; Dec. 7, 1979, 54-159455; Dec. 13, 1979, 54-162305; Dec. 19, 1979, 54-166240; Jan. 14, 1980, 55-2958; Jan. 24, 1980, 55-7544

Int. Cl.³ C07D 253/06; A01N 43/64

U.S. Cl. 71—93


20 Claims

1. A herbicidal composition which comprises as an active ingredient at least one of the 3,5-dioxo-1,2,4-triazine derivatives of the formula:



wherein


(1) (a) —X—Y— represents —N=CH—, (b) R¹ is a hydrogen atom, a hydroxymethyl group, an aminomethyl group of the formula:



(in which R³ and R⁴ are each hydrogen, C₁-C₁₂ alkyl, allyl, propargyl, cyanoethyl, phenyl or C₃-C₁₀ cycloalkyl or, when taken together with the adjacent nitrogen atom, represent a 3 to 13-membered saturated nitrogen-containing heterocyclic group optionally containing an oxygen atom or an additional nitrogen atom and/or optionally bearing not more than three methyl or ethyl groups), an acyloxymethyl group of the formula:




(in which R⁵ is C₁-C₉ alkyl, C₂-C₅ alkenyl, C₂-C₅ alkynyl or cyclohexyl, these R⁵ groups being optionally substituted with not more than five halogen, C₁-C₅ alkoxy, phenyl or phenoxy groups, or phenyl, naphthyl, nicotinyl or isonicotinyl, these being optionally substituted with not more than five methyl, methoxy, halogen, nitro or trihalomethyl groups or with 3,4-methylenedioxy) or a cyclic ether group of the formula:




(in which Z is —CH₂CH₂— and m is an integer of 1 or 2

or Z is $-\text{CHX}'\text{CH}_2-$, $-\text{CHX}'\text{CHX}'-$ or $-\text{CH}=\text{CH}-$ (X' being halogen) and m is 1) and (c) R^2 is a hydrogen atom, an aminomethyl group of the formula:




(in which R^3 and R^4 are each as defined above) or a cyclic ether group of the formula:




(in which Z' is $-\text{CH}_2\text{CH}_2-$ and n is an integer of 1 or 2 or Z is $-\text{CHY}'\text{CH}_2-$ (Y' being halogen) and n is 1), provided that when R^2 is a hydrogen atom, R^1 is a hydroxymethyl group, an acyloxymethyl group of the formula:




or a cyclic ether group of the formula:




when R^2 is an aminomethyl group of the formula:




R^1 is an aminomethyl group of the formula:



or when R^2 is a cyclic ether group of the formula:




R^1 is a hydrogen atom or a group of the formula:




or
(2) (a) $-\text{X}-\text{Y}-$ represents $-\text{NH}-\text{CH}_2-$, (b) R^1 is a hydrogen atom, an acyloxymethyl group of the formula:
 $-\text{CH}_2-\text{OOC}-\text{R}^6$


(in which R^6 is C_1 - C_9 alkyl, cyclohexyl or phenyl, these being optionally substituted with not more than five methyl, methoxy, fluorine, chlorine or trihalomethyl groups or with 3,4-methylenedioxy) or a cyclic ether group of the formula:




(in which p is an integer of 3 or 4) and (c) R^2 is a hydrogen atom or a cyclic ether group of the formula:



(in which p is as defined above), provided that when R^2 is a cyclic ether group of the formula:



R^1 is a hydrogen atom or a cyclic ether group of the formula:



in the free or salt form in a herbicidally effective amount, and at least one inert carrier or diluent.

11. A method for exterminating wild oats, which comprises applying a herbicidally effective amount of at least one of the 3,5-dioxo-1,2,4-triazine derivatives as defined in claim 1 in the free or salt form to the area where it is desired to exterminate or control the wild oats.

4,297,130

METHOD FOR INCREASING THE NUMBER OF PODS IN LEGUMES BY FOLIAR FEEDING

William P. Moore, Jr., P.O. Box 943, Hopewell, Va. 23860
Continuation-in-part of Ser. No. 829,140, Aug. 30, 1977, abandoned. This application Jun. 19, 1979, Ser. No. 50,047
Int. Cl.³ A01N 47/28; C05C 9/00

U.S. Cl. 71-119

6 Claims

1. A method for increasing the conversion of flowers of a leguminous plant to seed pods consisting of applying to the foliage of the plant during the flowering period an aqueous spray of a non-burning plant food comprising the condensation product of urea and formaldehyde composed of from 25-50% water-soluble nitrogenous compounds involving unreacted urea and correspondingly from 75-50% water-insoluble nitrogenous compounds capable of progressively degrading to water-soluble compounds under the influence of the urease and other enzymes and microbes present on the foliage.

4,297,131

PROCESSING OF TITANIFEROUS MATERIALS

John G. Miller, Philadelphia, Pa., and Thomas C. Schwab, Plainfield, N.J., assignors to Engelhard Minerals & Chemicals Corporation, Edison, N.J.

Filed Aug. 30, 1979, Ser. No. 71,018

Int. Cl.³ C22B 1/08, 3/00

U.S. Cl. 75-1 T


16 Claims

1. A process for extracting titanium from a titaniferous material selected from the group consisting of minerals containing titanium, titaniferous concentrates or tailings arising from beneficiation of minerals containing titanium and titaniferous waste products or by-products of the processing of minerals containing titanium or mixtures thereof, said titaniferous material containing alumina, silica or combinations thereof, which comprises contacting said titaniferous material at a temperature in the range of about 200° to 500° C. with a chlorinating agent consisting essentially of vaporous thionyl chloride to react at least a part of the titanium contained in said titaniferous material to form titanium tetrachloride without substantially consuming silica and alumina components of said titaniferous material, and separating said titanium tetrachloride from the remainder of said titaniferous material.

11. A process for extracting titanium from a titaniferous material selected from the group consisting of minerals containing titanium, titaniferous concentrates or tailings arising

from beneficiation of minerals containing titanium and titaniferous waste products or by-products of the processing of minerals containing titanium or mixtures thereof which comprises contacting said titaniferous material with vaporous thionyl chloride and elevated temperature to react at least a part of the titanium contained in said titaniferous material to form titanium tetrachloride, and separating said titanium tetrachloride from the remainder of said titaniferous material by extraction with a solvent.

12. A process for extracting titanium from a hydrated clay containing a colored titanium oxide as a minor impurity which comprises reacting said clay with vaporous thionyl chloride at elevated temperature to convert at least a part of the titanium contained in said hydrated clay to titanium tetrachloride, the temperature of reaction being insufficient to permanently dehydrate said clay, and separating said titanium tetrachloride from the remainder of said hydrated clay.



opposite ends of said paper tube, and a treating agent packed in said paper tube.

4,297,132

METHOD OF RECOVERING GOLD

Keita Yamada, Asaka Riken Kohyo Co., Ltd., 47 Aza Maseguchi, Tamura-cho, Kanaya, Koriyama, Fukushima-ken, Japan
Filed Jul. 3, 1980, Ser. No. 165,716

Claims priority, application Japan, Dec. 27, 1979, 54-173793
Int. Cl.³ C22B 11/06

U.S. Cl. 75-118 R

3 Claims

1. A process for recovering gold from a raw material containing gold comprising the steps of treating the raw material with either aqua regia or 6.0 to 6.5 normal hydrochloric acid to form chloroauric acid; extracting the chloroauric acid with an organic solvent selected from the group consisting of ethyl ether, methyl isobutyl ketone and a mixture of methyl isobutyl ketone and isoamyl acetate; separating and washing the organic solvent; stripping the gold contained in the organic solvent into an aqueous phase as gold hydroxide by adding a 30 to 50% solution of NaOH or NH_4OH to the organic solvent and agitating the resulting mixture; separating the aqueous layer; reacting the gold hydroxide in the aqueous layer with 3 to 5 normal hydrochloric acid to form chloroauric acid; reducing the chloroauric acid to precipitate the gold; and separating and recovering the gold.

4,297,135

HIGH STRENGTH IRON, NICKEL AND COBALT BASE CRYSTALLINE ALLOYS WITH ULTRAFINE DISPERSION OF BORIDES AND CARBIDES

Bill C. Giessen, Cambridge, Mass.; Donald E. Polk, Washington, D.C., and Ranjan Ray, Waltham, Mass., assignors to Marko Materials, Inc., North Billerica, Mass.

Filed Nov. 19, 1979, Ser. No. 95,383

Int. Cl.³ C22C 19/05, 38/22

U.S. Cl. 75-123 B

10 Claims

1. A crystalline metal alloy of the formula $\text{M}_a\text{R}_b\text{X}_c$, where M is at least one element selected from the group consisting of iron, nickel, cobalt and chromium and mixtures thereof, R is at least one element selected from the group consisting of zirconium, tantalum, niobium, molybdenum, tungsten, titanium and vanadium and mixtures thereof and X is at least one element selected from the group consisting of boron, silicon and carbon and mixtures thereof, wherein a, b and c are atomic percentages ranging from 85 to 95, 1 to 12 and 3 to 12, respectively, and boron is present at the level of at least 3 at %, said alloy having been prepared from the melt thereof by a rapid solidification process characterized by cooling rates in the range of about 10^5 to 10^7 °C./sec, said alloy subsequently subjected to the application of heat thereto and characterized by a fine grained microstructure with primary grains having an average grain size of less than about 10 microns with a substantially uniform dispersion of ultra fine particles of borides in the fine primary metallic grains, said ultra fine particles having a characteristic particle size of less than 0.5 micron and being dis-

4,297,133

METHOD AND MEANS FOR ADDING TREATING AGENT FOR MOLTEN METAL

Kenji Fujii, Nishinomiya, Japan, assignor to Yoshida Iron Works Co., Ltd., Hyogo, Japan

Continuation of Ser. No. 907,587, May 19, 1978, Pat. No. 4,200,456, which is a continuation-in-part of Ser. No. 799,000, May 20, 1977, abandoned. This application Mar. 4, 1980, Ser. No. 127,203

Claims priority, application Japan, Jul. 15, 1976, 51/84806; Jul. 22, 1976, 51/87983; Jul. 23, 1976, 51/88373; Sep. 16, 1976, 51/111521; Sep. 16, 1976, 51/111522; Sep. 16, 1976, 51/111523
Int. Cl.³ C22B 9/00

U.S. Cl. 75-53

13 Claims

1. A member for adding a treating agent for molten metal, comprising a paper tube formed of kraft paper wound in layers,

persed throughout the inside of the primary grains and along the grain boundaries.

4,297,136

HIGH STRENGTH ALUMINUM ALLOY AND PROCESS
Joseph R. Pickens, Ringwood, N.J.; Robert D. Schelleng, Suffern; Stephen J. Donachie, New Windsor, both of N.Y., and Thomas J. Nichol, Cheshire, Conn., assignors to The International Nickel Co., Inc., New York, N.Y.

Filed Oct. 16, 1978, Ser. No. 951,590

Int. Cl.³ B22F 3/14, 3/00

U.S. Cl. 75—206

22 Claims

1. In a process for treating a dispersion-strengthened mechanically alloyed aluminum consisting essentially, by weight, of a small but effective amount for increased strength up to about 7% magnesium, up to about 2½% carbon, up to about 4% oxygen, and the balance essentially aluminum and said dispersoid content being a small but effective amount of dispersoid for improved strength up to about 8½ volume %, comprising working said aluminum at an elevated temperature to form a hot worked product having a required strength, the improvement comprising:

(a) selecting as the initial charge material a dispersion-strengthened mechanically alloyed aluminum material having in compacted form prior to working, a room temperature strength at least equal to the room temperature strength of the hot worked product, said charge material having the property in a temperature range up to incipient melting of increased workability with increasing working temperature;

(b) determining the working temperature-strength profile of the selected charge material, said profile being characterized by an overall decrease in strength relative to the working temperature; and

(c) working the charge material at a temperature selected with reference to the working temperature-strength profile to optimize the workability of the charge material and the strength of the hot worked product.

11. A process for treating a dispersion-strengthened mechanically alloyed aluminum consisting essentially, by weight, of a small but effective amount for increased strength up to about 7% magnesium, up to about 2½% carbon, about 0.3% up to about 4% oxygen, and the balance essentially aluminum, the improvement comprising working said aluminum at an elevated temperature to form a worked product of required strength, wherein said aluminum is characterized by increased workability as temperature increases within a temperature range up to incipient melting of said aluminum, and wherein said aluminum is characterized by a working temperature-strength profile for extrusion equivalent to the pattern of FIG. 1 and an extrusion ratio strength pattern equivalent to FIG. 2 Curve A, which comprises:

(a) selecting as the initial charge material a dispersion-strengthened mechanically alloyed aluminum having in compacted form prior to working a room temperature tensile strength at least equal to the room temperature strength of the hot worked product; and

(b) extruding the charge material at a temperature selected with reference to the working-strength profile equivalent to the pattern shown in FIG. 1 to optimize the workability of the charge material and strength of the worked product.

4,297,137

ANTI-FOULING PAINT

Jean-Pierre Sachetto, Saint-Julien-en-Genevois, France, and Sergio Cuccolo, Geneva, Switzerland, assignors to Centre National pour l'Exploitation des Océans, Paris, France

Continuation of Ser. No. 885,850, Mar. 13, 1978, abandoned.

This application Jun. 20, 1980, Ser. No. 161,242

Claims priority, application France, Mar. 15, 1977, 77 07626

Int. Cl.³ C09D 5/14

U.S. Cl. 106—15.05

5 Claims

1. In an anti-fouling paint for application to structures immersed in sea water to inhibit attachment of marine organisms to the structures, the paint containing a vehicle comprising a film-forming resin, solvent and a toxic substance; the improvement comprising, as said toxic substance, cuprous oxide or an organic tin compound uniformly dispersed in a discontinuous solid matrix selected from the group consisting of coagulated albumin and regenerated cellulose in the form of a gel, said matrix being insoluble in sea water having no marine organisms or bacterial film, and which becomes soluble in sea water only after being contacted by enzymes produced by the marine organisms and/or the bacterial film,

whereby said matrix dissolves and releases said toxic substance only in the presence of the marine organisms and/or the bacterial film.

4,297,138

COPOLYCONDENSATION PRODUCTS OF β-HALOALKYL PHOSPHATES AND DIALKYL PHOSPHONATES

Edward D. Weil, Hastings-on-Hudson, N.Y., assignor to Stauffer Chemical Company, Westport, Conn.

Division of Ser. No. 858,316, Dec. 7, 1977, Pat. No. 4,152,371, which is a division of Ser. No. 811,972, Aug. 5, 1977, Pat. No. 4,086,303, and a continuation-in-part of Ser. No. 783,995, Apr. 4, 1977, abandoned, which is a continuation-in-part of Ser. No. 558,862, Mar. 17, 1975, abandoned, which is a


continuation-in-part of Ser. No. 410,583, Nov. 12, 1973, abandoned. This application Jan. 2, 1979, Ser. No. 231

Int. Cl.³ C08K 5/53; C09D 5/18; D21H 5/00

U.S. Cl. 106—18.18

10 Claims

1. A flame retardant composition comprising in admixture a polymer and, as a flame retardant, a copolycondensation product of a beta-haloalkyl phosphate having from 2 to 4 carbon atoms in the alkyl moiety and a dialkyl phosphonate of the formula



where R' is alkyl of from 1 to 20 carbon atoms, alkenyl of from 3 to 20 carbon atoms, or phenyl optionally substituted with alkyl of from 1 to 4 carbon atoms and/or halogen, and R is alkyl of from 1 to 4 carbon atoms, said product being obtained by heating the phosphate with the dialkyl phosphonate until at least about one molar equivalent of alkyl halide is evolved.

4,297,139

INORGANIC GELS AND CERAMIC PAPERS, FILMS, FIBERS, BOARDS, AND COATINGS MADE THEREFROM

George H. Beall, Big Flats; David G. Grossman, Corning; Syed N. Hoda, Horseheads, and Karen R. Kubinski, Elmira Heights, all of N.Y., assignors to Corning Glass Works, Corning, N.Y.

Division of Ser. No. 23,907, Mar. 26, 1979, Pat. No. 4,239,519.

This application Jun. 25, 1980, Ser. No. 162,764

Int. Cl.³ C03C 3/22

U.S. Cl. 501—2

9 Claims

1. Inorganic gels containing a polar liquid and relatively

4,297,142

OPTICAL COLORED AND FILTER GLASS

Willy Ritze, Mainz, Fed. Rep. of Germany, assignor to Jenaer Glaswerk, Schott & Gen., Mainz, Fed. Rep. of Germany


Filed Jun. 16, 1980, Ser. No. 159,700

Claims priority, application Fed. Rep. of Germany, Jul. 3, 1979, 2926721

Int. Cl.³ C03C 3/16, 3/24

U.S. Cl. 501—77

7 Claims



1. A low alkali, high phosphate and high Al₂O₃ content glass suitable for optical colored and filter glasses characterized by having a glass transformation temperature T_g > 450° C. and consisting essentially of the following composition, in percent by weight:

P ₂ O ₅	71.0-76.0
SiO ₂	0.25-2.5
B ₂ O ₃	2.4-3.75
Al ₂ O ₃	8.6-11.6
R ₂ O (alkali oxide)	1.25-6.5
CaO	0.5-1.65
MgO	2.0-3.5
Refining Agent	0.2-0.6
CeO ₂	0.1-0.4
F'	0.2-0.4 and
CuO	1.0-10.0.

7. The composition according to any one of claims 1 thru 6 in the form of an optical filter glass.

4,297,143

TEMPERATURE STABILIZED SILICON DIOXIDE-MIXED OXIDE, THE PROCESS FOR ITS PRODUCTION AND USE

Peter Kleinschmidt, Hanau, and Rudolf Schwarz, Alzenau, both of Fed. Rep. of Germany, assignors to Degussa Aktiengesellschaft, Frankfurt, Fed. Rep. of Germany

Filed Jul. 31, 1980, Ser. No. 174,341

Claims priority, application Fed. Rep. of Germany, Aug. 6, 1979, 2931810

Int. Cl.³ C04B 35/14; C01B 33/12

U.S. Cl. 501—103

26 Claims

1. Pyrogenically produced, temperature stabilized silicon dioxide-mixed oxide having a BET surface of 50 to 400 m²/g, the other component of the mixed oxide being

0.01 to 10 weight % zirconium dioxide or 0.01 to 10 weight % ferric oxide or 0.1 to 9.9 weight % titanium dioxide.

19. A process of preparing a stabilized silicon dioxide-mixed oxide having a BET surface of 50 to 400 m²/g, the other component of the mixed oxide being

0.01 to 10 weight % zirconium dioxide or 0.01 to 10 weight % ferric oxide or 0.1 to 9.9 weight % titanium dioxide and wherein the silicon dioxide is stabilized up to a temperature of 1150° C. against reduction in surface area to below 50 m²/g, comprising vaporizing silicon tetrachloride, diluting it with

uniformly-sized crystals consisting essentially of a lithium and/or sodium water-swelling mica selected from the group of fluorhectorite, hydroxyl hectorite, boron fluorphlogopite, hydroxyl boron fluorphlogopite, and solid solutions among those and between those and other structurally-compatible species selected from the group of talc, fluortalc, polyolithionite, fluorpolyolithionite, phlogopite, and fluorphlogopite, at least a substantial portion of said crystals exhibiting a morphology of a continuum of flakes, rectangular-like strips, and interwoven ribbons in parallel or sub-parallel zones or sheaths with said strips and ribbons being about 0.5-10 microns long, about 500 Å-5000 Å wide, and less than about 100 Å thick, and said flakes being irregularly shaped with diameters between about 0.5-10 microns and cross sections of less than about 100 Å.

4,297,140

CERAMIC FOAM CEMENT

Robert J. Paisley, Corning, N.Y., assignor to Corning Glass Works, Corning, N.Y.

Filed Jul. 3, 1980, Ser. No. 165,647

Int. Cl.³ C04B 33/00

U.S. Cl. 428—310

15 Claims

1. A foamable particulate ceramic cement capable of forming a sintered cordierite foamed ceramic mass and consisting essentially, by weight, of:

1-40% cordierite grog,

99-60% ceramic base material and an effective amount of a foaming agent to effect foaming of the cement upon firing to produce the foamed ceramic mass,

the base material being raw ceramic material that has an analytical molar composition consisting essentially of about:

1.7-2.4 MO-1.2-2.4 Al₂O₃ 4.5-5.4 SiO₂ wherein MO comprises, as mole % of MO, about 0-55% MgO and at least 45% MnO, and

the grog being ceramic material that has been previously fired and comminuted, and that has an analytical molar composition consisting essentially of about:

1.7-2.4 RO-1.9-2.4 Al₂O₃ 4.5-5.2 SiO₂ wherein RO comprises, as mole % of RO, MnO in an amount of 0% up to a mole % that is about 20 mole % lower than the mole % of MO that is MnO and the balance is substantially MgO.

4,297,141

OPTICAL GLASS FOR OPTICAL PATHS

Shinobu Tokunaga, Yono, and Yuichi Shiina, Warabi, both of Japan, assignors to Sumita Optical Glass Manufacturing Co., Ltd., Japan

Continuation-in-part of Ser. No. 69,107, Aug. 21, 1979, abandoned. This application Nov. 19, 1980, Ser. No. 208,481

Claims priority, application Japan, Sep. 5, 1978, 53-108882; Apr. 9, 1979, 54-42921

Int. Cl.³ C03C 3/04, 3/08

U.S. Cl. 501—67

1 Claim

1. An optical glass for an optical path having a refractive index of at least 1.55, an Abbe number of at least 48 and a specific gravity of at most 2.90, which consists essentially of

SiO ₂	55 to 65% by weight
B ₂ O ₃	0 to 10
TiO ₂ + ZrO ₂	1 to 5
TiO ₂	0 to 5
ZrO ₂	0 to 5
CaO + ZnO	20 to 33
CaO	5 to 20
ZnO	3 to 20
Al ₂ O ₃	0 to 4
at least one of	
R ₂ O (Li ₂ O, Na ₂ O, K ₂ O)	5 to 9
As ₂ O ₃	0 to 1

preheated air in the ratio of 0.5 to 1.2 kg of silicon-tetrachloride to 0.8 to 1.2 Nm³ of air, supplying it to a burner having a mixing chamber, mixing the diluted silicon tetrachloride in the mixing chamber with hydrogen and vapor form ferric chloride, zirconium tetrachloride or titanium tetrachloride in the ratio as to give an silicon dioxide-other component mixed oxide containing

0.01 to 10% zirconium dioxide or
0.1 to 10% ferric oxide or



0.1 to 9.9% titanium dioxide,
and wherein the ratio of hydrogen to the total of silicon tetrachloride and the chloride of the other element is 0.8 to 1.5 Nm³ of hydrogen to 2.8 to 3.3 kg of total chlorides, buring the 4-component mixture in a reaction chamber, separating the solid silicon dioxide-mixed from the gaseous reaction products and freeing the solid silicon dioxide-mixed oxide from adhering hydrogen chloride by heating in moist air.

4,297,144

HIGH SPEED CORRUGATING ADHESIVES

Gary H. Klein, LaGrange; Howard L. Arons, LaGrange Park; Joseph F. Stejskal, Brookfield; Donald G. Stevens, Clarendon Hills, and Henry F. Zobel, Darien, all of Ill., assignors to CPC International Inc., Englewood Cliffs, N.J.

Continuation of Ser. No. 795,253, May 9, 1977, abandoned, which is a division of Ser. No. 598,095, Jul. 22, 1975, abandoned.

This application Aug. 13, 1979, Ser. No. 66,269

Int. Cl.³ C08L 1/26, 3/06; C09J 3/06

U.S. Cl. 106—197 C

15 Claims

1. In a process for the preparation of a corrugating adhesive composition of the no-carrier type, comprising the steps of preparing a heated reaction mixture of ungelatinized starch material, water and alkali, allowing the reaction to proceed until a Stein-Hall viscosity of about 20 to about 90 seconds is reached, and adding a reaction stopper to the mixture, the improvement which consists of replacing at least a portion of the starch material with a saponifiable starch ester derived from a non-waxy grain source characterized as having at least about 30% greater area under an Instron force-time heating curve, and at least about 30% greater area under an Instron force-time cooling curve compared with unmodified corn starch under the same test conditions and having a saponifiable D.S. of at least about 0.015.

4. An adhesive composition for use in a high speed corrugating process which comprises an aqueous dispersion of the reaction product of:

(1) a starch material formed by saponification of a starch ester derived from a non-waxy grain source having a saponifiable degree of substitution of at least about 0.015 and characterized as having at least about 30% greater area under an Instron force-time heating curve and at least

about 30% greater area under an Instron force-time cooling curve than unmodified corn starch under the same test conditions; and

(2) an amount of alkali sufficient to substantially completely saponify said ester and to render said composition effective in said process.

4,297,145

SILANE/FILLER PREPARATIONS, PROCESS FOR THEIR PRODUCTION AND THEIR USE

Siegfried Wolff, Bornheim-Merten; Lothar Rothbühr, Hürth-Hermülheim, and Heinz Grewatta, Cologne, all of Fed. Rep. of Germany, assignors to Degussa Aktiengesellschaft, Frankfurt, Fed. Rep. of Germany

Filed Aug. 14, 1980, Ser. No. 178,159

Claims priority, application Fed. Rep. of Germany, Aug. 17, 1979, 2933346

Int. Cl.³ C09C 1/28

U.S. Cl. 106—308 Q

23 Claims

1. A silane/filler preparation, consisting essentially of from 5 to 70% by weight of at least one silane corresponding to the following formula



I

in which

X=a halogen atom

p=1 or 2,

m=1 to 5,

R¹=a C₁- to C₅-alkyl group, a C₅- to C₈-cycloalkyl group or the phenyl group,

R=a C₁- to C₅-alkyl group, a C₅- to C₈-cycloalkyl group, the phenyl group, the benzyl group or a C₁- to C₅-alkoxy-C₁- to C₅-alkyl group, and

n=0, 1 or 2,

and—respectively balanced to 100%—from 95 to 30% by weight of at least one inorganic filler based on the two components.

4,297,146

METHOD FOR THE PRODUCTION OF POWDERED DEXTROSE

Yoshinari Mise, Inagi, and Eijiro Tomimura, Tokyo, both of Japan, assignors to CPC International Inc., Englewood Cliffs, N.J.

Filed Oct. 4, 1976, Ser. No. 729,325

Int. Cl.³ C13F 1/02, 3/00

U.S. Cl. 127—60

8 Claims

1. A method for the production of powdered dextrose containing a substantial portion of anhydrous β-dextrose from an aqueous solution containing dextrose comprising the steps of:

(a) concentrating said solution containing dextrose to a concentration of within the range of about 90% and about 98%, by weight dry substance;

(b) introducing into said concentrated solution at least about 0.2%, by weight of sugar, of seed crystals containing β-dextrose at a temperature above about 80° C.; and

(c) vacuum dehydrating said concentrated solution with stirring while maintaining said temperature above about 80° C. to remove free water.

4,297,147

METHOD FOR DECOCKING FIRED HEATER TUBES

David J. Nunciato, Missouri City, Tex.; Norman H. White, Huntington Beach, Calif., and William A. Woodburn, Kingwood, Tex., assignors to Union Carbide Corporation, New York, N.Y.


Continuation-in-part of Ser. No. 906,748, May 17, 1978, Pat. No. 4,203,778. This application Apr. 24, 1980, Ser. No. 143,333

The portion of the term of this patent subsequent to May 20, 1997, has been disclaimed.

Int. Cl.³ B08B 9/02

U.S. Cl. 134—7

12 Claims



1. A method for decoking fired heater tubes used in hydrocarbon or chemical processing, while maintaining the integrity of the straight sections of tube walls and the return bends of said fired heater tubes, or of said tubes having equivalent continuous helical tube configurations, comprising:

(a) establishing a gas inlet to and a gas outlet from said fired heater tubes having straight sections of tube walls and return bends, or equivalent continuous helical tube configurations;

(b) injecting a purge gas stream into the inlet while the outlet is open to the atmosphere to purge the tubes of loose debris until the effluent is essentially clear;

(c) entraining impact resistant, non-angular, non-abrasive particles into a propelling gas stream at a concentration of from about 0.1 to about 10.0 pounds of particles per pound of propellant;

(d) introducing the impact resistant, non-angular, non-abrasive particle entrained gas stream into the inlet of said fired heater tubes having straight sections and return bends, or equivalent continuous helical tube configurations, while the outlet remains open to the atmosphere at a gas flow rate corresponding to an outlet gas velocity of from about 5,000 feet per minute up to the sonic velocity of said propelling gas;

(e) maintaining the flow of the gas stream in step (d) for a sufficient time to effect decoking of said tubes;

(f) discontinuing the entraining of impact resistant, non-angular, non-abrasive particles into said propelling gas stream;

(g) continuing the flow of propelling gas into said tubes to clear such tubes of loose coke debris; and

(h) repeating steps (c), (d), (e) and (f) until the tubes are clean, as evidenced by an essentially coke-free clear effluent from the outlet, whereby grinding—type abrasion of the straight sections of tube walls and gouging—type abrasion of the return bends, or of equivalent continuous helical tube configurations, are eliminated.

4,297,148

MASONRY CLEANING PROCESS AND COMPOSITION

Panagiotis Zervopoulos, 514 Pape Ave., Toronto, Canada (M4K 3R2)

Filed Apr. 14, 1980, Ser. No. 139,942

Claims priority, application Canada, Apr. 17, 1979, 325783

Int. Cl.³ B08B 3/08

U.S. Cl. 134—3

5 Claims

4. A method of cleaning masonry surfaces comprising: ap-

plying to said surface, for a predetermined time sufficient to loosen deposits therefrom, a composition comprising, by weight, about 8 to 30% sulphuric acid; about 23 to 30% hydrogen fluoride; about 0.1 to 0.2% chromic acid; about 0.9 to 1.8% water miscible wetting agent, and the balance water, and then washing said surface with water.

4,297,149

METHOD OF TREATING SIPOS PASSIVATED HIGH VOLTAGE SEMICONDUCTOR DEVICE

Patrick R. Koons, Round Rock, Tex., and John M. S. Neilson, Mountaintop, Pa., assignors to RCA Corporation, New York, N.Y.

Filed May 5, 1980, Ser. No. 146,380

Int. Cl.³ H01L 21/265, 21/205; G06F 15/46

U.S. Cl. 148—1.5

6 Claims

1. In a process of fabricating a semiconductor device having oxygenated polycrystalline silicon passivation layers the improvement comprising:

annealing the devices at at least 525° C. prior to metallization;

cooling the devices rapidly through the 500° C. to 450° C. temperature range at the end of said annealing;

preventing the devices from subsequently being heated to any temperature higher than 425° C.; and

preventing the devices from being exposed to any temperature above 400° C. for longer than a total of ten minutes subsequent to the annealing whereby the devices will have near the maximum breakdown voltage of which their structure is capable.

4,297,150

PROTECTIVE METAL OXIDE FILMS ON METAL OR ALLOY SUBSTRATE SURFACES SUSCEPTIBLE TO COKING, CORROSION OR CATALYTIC ACTIVITY

Alan I. Foster, Ashford; Malcolm L. Sims, Hersham, and Dennis Young, Staines, all of England, assignors to The British Petroleum Company Limited, London, England

Filed Jun. 27, 1980, Ser. No. 163,866

Claims priority, application United Kingdom, Jul. 7, 1979, 23787/79

Int. Cl.³ C23C 7/02

U.S. Cl. 148—6.3

14 Claims

1. A process for forming protective films on a structural metal or alloy substrate surface which comprises first pre-oxidizing the surface at an elevated temperature in an oxidizing atmosphere and then depositing on the preoxidized substrate surface a film of a high temperature stable, non-volatile oxide of a metal selected from calcium, magnesium, aluminium, gallium, titanium, zirconium, hafnium, tantalum, niobium and chromium by thermal decomposition from the vapour phase of a volatile compound of the metal having at least one metal-oxygen bond in admixture with an inert or oxygenated carrier gas in contact with the pre-oxidized surface.

4,297,151

METHOD FOR DIVIDING A STRAND INTO SLABS

Erich Höffken, Dinslaken; Werner Kleine-Kleffmann; Rolf Bertram, both of Duisburg; Karl-Heinz Abele, Dinslaken, and Günter Michalski, Kamp-Lintfort, all of Fed. Rep. of Germany, assignors to Thyssen Aktiengesellschaft vormals August Thyssen-Hütte, Duisburg, Fed. Rep. of Germany

Division of Ser. No. 884,788, Mar. 9, 1978, Pat. No. 4,208,039. This application Dec. 18, 1979, Ser. No. 104,991

Claims priority, application Fed. Rep. of Germany, Mar. 11, 1977, 2710564; Mar. 11, 1977, 2710574


Int. Cl.³ B23K 7/00

U.S. Cl. 148—9 R

3 Claims

1. A method of cutting a cast strand into longitudinal sections which comprises initially severing said strand transversely to form a slab, transporting said slab to a first longitudinal

nal cutting means, longitudinally cutting said slab in said first longitudinal cutting means, cutting said strand transversely a second time to form a second slab, transporting said second



slab to a second longitudinal cutting means, longitudinally cutting said second slab in said second longitudinal cutting means and recovering longitudinally cut slabs from said first and second longitudinal cutting means.

4,297,152

ENERGETIC MONOPROPELLANT

Milton B. Frankel, Tarzana; Harry A. Arbit, Encino; Glen D. Artz, Canoga Park, and John C. Gray, Ventura, all of Calif., assignors to The United States of America as represented by the Secretary of the Air Force, Washington, D.C.

Filed Jan. 10, 1980, Ser. No. 110,888
Int. Cl.³ C06B 25/00

U.S. Cl. 149—88

4 Claims

1. A liquid monopropellant composition comprising a mixture of bis (2,2-dinitropropyl) acetal, bis (2,2-dinitropropyl) formal and bis (2,2,2-fluorodinitroethyl) formal.

4,297,153


METHOD AND APPARATUS FOR MAKING DOLL CLOTHING AND DOLL HOUSE ACCESSORIES

Erick E. Erickson; Allison W. Katzman, both of Chicago, and Jeffrey D. Breslow, Highland Park, all of Ill., assignors to Marvin Glass & Associates, Chicago, Ill.

Continuation-in-part of Ser. No. 10,806, Feb. 9, 1979, abandoned. This application Jun. 19, 1980, Ser. No. 160,917
Int. Cl.³ B44C 3/02; B29C 13/04; A41D 1/00

U.S. Cl. 156—63

15 Claims



1. A method for making doll house accessories which comprises the steps of:

- providing a mold having physical dimensions similar to a portion of the accessory to be formed;
- applying a water soluble resinous film forming liquid to the surfaces of said mold;

forming a plastic film on said surfaces by allowing said liquid to dry;
removing the finished accessory from the mold; and
attaching decorative elements to said plastic film by moistening the contact surface of said film to which said element is to be attached.

4,297,154

METHOD OF MANUFACTURING EXPANDED REINFORCING SHEET MATERIAL


Robert N. Keller, Utica, Mich., assignor to National Steel Corporation, Pittsburgh, Pa.

Division of Ser. No. 10,791, Feb. 9, 1979, Pat. No. 4,259,385.
This application Nov. 3, 1980, Ser. No. 203,382

Int. Cl.³ B32B 31/16, 3/24

U.S. Cl. 156—79

41 Claims



1. A method of reinforcing an article, the method comprising:

- bonding a layer of a foamable adhesive material to at least one surface of a flat sheet of structural material capable of being formed into an expanded sheet,
- forming a series of laterally spaced lines of slits through the sheet of structural material and the adhesive material bonded thereto with the slits in each line being spaced from one another and being offset longitudinally with respect to the slits in adjacent lines of slits,
- simultaneously expanding the sheet of structural material and the foamable adhesive bonded thereto by spreading said slits to form a uniform pattern of generally diamond-shaped openings in the sheet of structural material and foamable adhesive,
- positioning the expanded structural sheet having the foamable adhesive thereon in contact with the article to be reinforced, and
- activating the foamable adhesive material to enlarge its volume and form a bond between the expanded structural sheet and the article.

4,297,155


HEAT-SHRINKABLE HOLLOW ARTICLE

James E. Jervis, Atherton, Calif., assignor to Raychem Corporation, Menlo Park, Calif.

Filed Feb. 3, 1978, Ser. No. 875,110

Int. Cl.³ B29C 27/00; H02G 15/02; F10L 57/00; B65D 59/06
U.S. Cl. 156—86

3 Claims



1. A process for covering the end of a cable comprising

positioning over the end of the cable a heat-recoverable cap having a closed end and an open end and a dimensionally heat-unstable boss projecting into the internal cavity of the cap from said closed end of the cap so that the end of the cable abuts the boss, and heating the cap including the boss to cause the cap to shrink about the cable end and to cause the boss to retract to a dimensionally heat-stable form to leave a gap between the end of the cable and the closed end of the cap, wherein the boss in its dimensionally heat-stable form does not project into said gap.

2. A heat-recoverable hollow cap having a wall defining a closed end and an open end, at least a portion of the wall being heat-unstable, the open end of the cap affording access to a relatively large internal cavity of relatively large circumference, the heat-unstable wall of the cap defining the shape of the relatively large internal cavity and being shaped to provide a boss which projects into said relatively large internal cavity from said closed end, at least part of the boss being in a dimensionally heat-unstable form, wherein upon heating of the cap to cause recovery thereof, the heat-unstable wall of the cap recovers to form a relatively small internal cavity of relatively small circumference compared to the circumference of the relatively large internal cavity, such recovery resulting in the boss being in a dimensionally heat-stable form that projects less into the relatively small internal cavity than the boss projects into the relatively large internal cavity.

4,297,156

PROCESS FOR MANUFACTURE OF WALL COVERINGS AND WALL COVERINGS THUS OBTAINED


Joël Dalle, Bondues, France, assignor to Dalle & Cie, S.A., Wervicq, France

Filed Feb. 1, 1979, Ser. No. 8,581

Claims priority, application France, Feb. 24, 1978, 78 06257
Int. Cl.³ B32B 7/08

U.S. Cl. 156—93

1 Claim



1. Process of manufacture of a complex providing a wall covering and composed of an element of textile nature associated with a support of dimensionally indeformable material on which support the textile element is fixed by fusion of a film of thermoplastic material interposed between the textile element and the support, the steps of forming the textile element on a crocheting machine for the deposit of at least one warp band of threads or meshes in zigzags the peaks of which are substantially perpendicular to the direction of advance of the work, prefixing the warp in position by chain stitching parallel to the direction of advance of the work, forming the textile element in at least one layer exactly to the width of the final covering, stabilizing the textile element in width and straightness by supplying the machine with a support and fusible film of greater width than that of the said element, prefixing the warp to the support and film by the chain stitching which also positions the sections of the warp, locating certain of said chain stitching on the warp along each edge of the warp to prevent the marginal portions of the warp from moving before fixing by fusion of the film and in such a way that each edge stitching of the warp provides a line of precutting of the support and of its film to facilitate the ultimate tearing away of the excessive width of the support, and then heating the warp fiber and support to fuse the film and positively fix the textile element on the support.

4,297,157

METHOD FOR APPLICATION OF ELASTIC TO ARTICLES


Raymond A. Van Vliet, Auburn, Wash., assignor to Weyerhaeuser Company, Tacoma, Wash.

Filed Jun. 23, 1980, Ser. No. 161,722

Int. Cl.³ B32B 31/08

U.S. Cl. 156—164

17 Claims



1. A method of applying units of an elastic material to a predetermined area of an article comprising:

- a. providing a continuous source of the elastic material;
- b. tensioning the elastic material;
- c. grasping the leading end of the elastic material in a first clamping means;
- d. grasping the tensioned elastic material in a second clamping means at a predetermined distance from the first clamping means, said distance being greater than the length of the elastic unit applied to the article;
- e. severing the portion of elastic held between the clamping means from the main body of elastic material at a location adjacent to the second clamping means;
- f. moving the clamping means closer together to a separation which defines the length of the elastic unit applied to the article;
- g. bonding the elastic unit to the desired area of at least one component of the article; and
- h. releasing the elastic from the clamps after the bond has been established.

4,297,158

NON-TOXIC ACTIVATORS FOR ADHESIVE COMPOSITIONS

Leon E. Wolinski, Cheektowaga, and Peter D. Berezuk, Kenmore, both of N.Y., assignors to Pratt & Lambert, Inc., Buffalo, N.Y.

Division of Ser. No. 858,702, Dec. 8, 1977, Pat. No. 4,155,950, and a continuation-in-part of Ser. No. 763,145, Jan. 27, 1977, Pat. No. 4,126,504, and Ser. No. 705,333, Jul. 14, 1976, Pat. No. 4,080,238. This application Apr. 2, 1979, Ser. No. 26,015

Int. Cl.³ C09J 5/04

U.S. Cl. 156—305


7 Claims

1. In the method of adhesively joining a pair of mating surfaces comprising applying to at least one of said mating surfaces an activatable, curable adhesive comprising a non-reactive thermoplastic polyurethane resin or a non-reactive elastomer dissolved in a non-acid methacrylic or acrylic monomer and a methacrylic or acrylic acid monomer, said monomers being essentially devoid of peroxy catalyst activation capability, said solution containing an effective amount of peroxy catalyst, the said adhesive being activatable by contact with a peroxy catalyst activator; the improvement comprising, in any order, the steps of joining said pair of mating surfaces together in a contact relationship and activating the adhesive

by contacting it with an activator compound selected from the group consisting of:



- (a) R=H or phenyl, a=0 or 1, a+b=3 and when R is phenyl, a is 1,
 (b) $CH_2=CH(CH_3)COOCH_2CH(OH)CH_2A$, which is different from the other acrylic or methacrylic monomers in the adhesive, wherein A is one of:



- (c) homopolymers of the compounds of (b),
 (d) a copolymer of at least 25% by weight of a compound of (b) with a member selected from the group consisting of methyl methacrylate, methyl acrylate, 2-ethyl hexyl acrylate, or butyl acrylate, the reaction products of epoxy polymers with secondary amines selected from the group consisting of N-methyl aniline, N-methyl-p-toluidine, N-β-hydroxy ethyl aniline, N-ethyl aniline, N-n-propyl aniline, N-β-hydroxy ethyl-p-toluidine, diethanol amine, dihexyl amine, p-chloro-N-methylaniline, N,N'-dimethyl-p-phenylene diamine, N,N'-di-2-naphthyl-p-phenylene diamine and N-methyl-3,5-xylidene wherein from 0.25 to one amino equivalent weight is reacted with one oxirane

equivalent weight, and then maintaining the contact relationship of the surfaces until the adhesive cures to a set.

4,297,159

METHOD TO DIRECTLY BOND RUBBER TO METAL
 Bohuslav Dobias, Regensburg, Fed. Rep. of Germany, and Klaus Heckmann, Zum Aichahof 20, D-8400, Regensburg, Fed. Rep. of Germany, assignors to Klaus Heckmann, Regensburg, Fed. Rep. of Germany

Filed Jul. 11, 1979, Ser. No. 56,732

Claims priority, application Fed. Rep. of Germany, Jul. 21, 1978, 2832235

Int. Cl.³ C09J 5/00

U.S. Cl. 156—307.7

11 Claims

1. A process for directly bonding a rubber composition to metal surfaces comprises:

- (a) contacting the surface of a metal selected from the group consisting of iron, copper, brass, zinc, aluminum, bronze and brass-plated steel with a composition comprising a vulcanizable rubber and conventional rubber-sulfur vulcanization compounding ingredients, a bonding aid selected from the group consisting of elemental tellurium and organotellurium compounds being used to improve the bond between said metal surface and said composition by incorporation thereof in said composition or by application thereof directly to said metal surface; and
 (b) subjecting the product of step (a) to pressure and temperature conditions sufficient to effect the vulcanization of said composition.

4,297,160

LOCKING AND SEALING COMPOSITIONS AND METHODS FOR THEIR APPLICATION

Senji Kusayama, Toyonaka; Eijiro Nishi, Otsu, both of Japan, and Hugh J. Stock, Saratoga, Calif., assignors to Pacer Technology and Resources, Inc., Campbell, Calif. and Sumitomo Chemical Company, Ltd., Osaka, Japan


Filed Jul. 16, 1979, Ser. No. 57,666

Int. Cl.³ C09J 5/00


U.S. Cl. 156—331.1

11 Claims

1. A method of bonding threaded parts and analogous structures while sealing them from extraneous injurious substances which comprises adding to a rapidly polymerizable monomer of an alpha cyanoacrylate ester of general formula,




wherein R is a radical containing a total of 1 to 16 carbon atoms, said radical being selected from the group which consists of alkyl, alkenyl (with 2 to 6 carbon atoms), alkoxyalkyl (with 2 to 6 carbon atoms), cyclohexyl, and phenyl, a coloring agent in proportions of 100 to 5000 parts per million parts by weight of the monomer, selected from the group which consists of modified dyestuffs, red, blue or yellow in color, and mixtures thereof, having respectively the formulas,



(i)

-continued



applying said monomer as a coating film to the surfaces to be joined and protected, contacting the coated surfaces, and polymerizing said monomer in situ to form a visibly colored bonding film on said surface while limiting the ultimate strength of said film by reason of strength modifying properties of said coloring agent, without retarding the rapid curing properties of the monomer.

4,297,161

METHOD AND APPARATUS FOR HEAT-SEALING LIDS ON GLASS CONTAINERS

Andre J. Graffin, La Ferte Bernard, France, assignor to Serac, France

Continuation of Ser. No. 952,227, Oct. 17, 1978, abandoned.


This application Jul. 22, 1980, Ser. No. 171,182

Claims priority, application France, Nov. 3, 1977, 77 33046

Int. Cl.³ B30B 5/02, 15/34; B65B 7/28

U.S. Cl. 156—583.3

4 Claims



1. A device for sealing a heat-sealable composite lid onto a glass container, said lid comprising a foil of a ductile light alloy coated on one side with a layer of heat sealable thermoplastic material, said device comprising:

- means for supporting said container;
 a hinged and movably supported applying head, having a supporting frame, a flexible membrane supported by its outer periphery on said supporting frame, so as to extend in rest position substantially in a plane, said membrane having an outer contacting surface and an inner face, a heat transfer mass arranged on the side of said inner face of said membrane and means for controllably heating said heat transfer mass;
 means for selectively and controllably displacing toward

and away from each other said applying head and said container supporting means; and,
 said applying head further comprising a metallic body on one end of which is mounted said membrane supporting frame, said body being provided with at least one inner chamber closed by at least a portion of said inner face of said membrane, said membrane consisting of a simple metal sheet which is not self-heating, said metallic body forming said heat transfer mass, said inner chamber having a relatively small thickness and being limited, on the side opposite said membrane, by a substantially flat face of said metallic body, said inner face of said membrane being adapted for coming into contact engagement with said flat face as a result of a distortion of said membrane caused by said container during relative displacement one toward the other of said container supporting means and of said applying head.

4,297,162


PLASMA ETCHING USING IMPROVED ELECTRODE
 Randall S. Mundt, Houston; Timothy A. Wooldridge, Missouri City, and Thomas O. Blasingame, Houston, all of Tex., assignors to Texas Instruments Incorporated, Dallas, Tex.

Filed Oct. 17, 1979, Ser. No. 85,564

Int. Cl.³ H01L 21/306; C23F 1/00

U.S. Cl. 156—643

14 Claims



12. A method of etching a coating on a generally circular silicon slice comprising

- (a) positioning the slice symmetrically in a chamber on a conductive holder,
 (b) positioning an electrode facing the slice in the chamber, the electrode being of generally symmetrical shape with respect to the slice and having a central part closer to the slice than peripheral parts,
 (c) admitting reaction gas to the chamber while vacuum-pumping the chamber,
 (d) applying radio frequency voltage between the holder and the electrode.

13. A method according to claim 12 wherein said central part is shaped in a convex manner generally symmetrical with respect to the slice.

4,297,163

DRYING OF POTASSIUM SILICATE

Jeffrey R. Thomas, Aston, Pa., assignor to PQ Corporation, Valley Forge, Pa.

Filed Jan. 7, 1980, Ser. No. 110,276

Int. Cl.³ B01D 1/18

U.S. Cl. 159—48 R

2 Claims

1. In the process of spray drying potassium silicate solution to obtain powders, comprising the steps of atomizing said potassium silicate solution in a spray drying tower and subjecting the resulting droplets to elevated temperatures in said spray tower thereby removing water from the droplets and drying them: the improvement consisting of dispersing a hydrophilic silane in said potassium silicate before atomizing the solution, wherein 0.05 to 2.5 parts by weight of the hydrophilic silane are added for each 100 parts by weight of potassium silicate solids contained in said potassium silicate solution.

4,297,164

PROCESS FOR DISPLACEMENT WASHING OF POROUS MEDIA

Peter F. Lee, Auburn, Wash., assignor to Weyerhaeuser Company, Tacoma, Wash.

Filed Mar. 10, 1980, Ser. No. 129,009

Int. Cl.³ D21C 9/06

U.S. Cl. 162—60

23 Claims

1. In a process for separating a liquid from an insoluble material which includes the steps of thickening said insoluble material by draining excess liquid therefrom while retaining the material in a porous formation on a porous support means and displacing a substantial portion of the liquid remaining in the insoluble porous material after thickening from said material by injecting a wash liquid into said material, without substantially disturbing said porous formation of the retained material, the improvement, comprising:

reducing the mobility of said wash liquid in the porous formation of the insoluble material with respect to the mobility of said liquid originally retained in the porous insoluble material,

wherein the mobility of a liquid with respect to a porous formation is proportional to the permeability of the porous formation to a liquid and inversely proportional to the viscosity of said liquid,

such that the ratio of wash liquid mobility to the mobility of the liquid to be displaced is about 0.05–2.0.

4,297,165

FUEL PELLETS FOR CONTROLLED NUCLEAR FUSION


Keith A. Breuckner, San Diego, Calif., assignor to KMS Fusion, Inc., Ann Arbor, Mich.

Filed Jul. 13, 1970, Ser. No. 65,756

Int. Cl.³ G21B 1/00

U.S. Cl. 376—103

7 Claims



1. A method of increasing the efficiency of a fusion burn of a small quantity of fusion fuel which comprises:

(a) surrounding the fusion fuel with a contiguous envelope of uranium,

(b) encasing the fuel and the uranium envelope in a contiguous layer of a relatively light material selected from aluminum and beryllium,

(c) directing a laser beam toward said fuel to cause a transfer of fast neutrons from said fuel to said uranium and a fission reaction in said uranium to heat said fuel and maintain a high pressure on said fuel to retard the disassembly of the fusion fuel.

4,297,166

THALLIUM-CARRYING TARGET MATERIAL AND ITS PRODUCTION

Makoto Kato, Kobe; Nobuo Ueda, Takarazuka, and Hiroaki Matsushima, Nishinomiya, all of Japan, assignors to Nihon Medi-Physics, Co., Ltd., Hyogo, Japan

Filed Feb. 16, 1979, Ser. No. 12,809

Claims priority, application Japan, Feb. 20, 1978, 53-18678

Int. Cl.³ C25D 3/02, 3/54; G21G 1/10

U.S. Cl. 376—194

10 Claims

1. A method for production of a thallium-carrying target

material comprising a thermo-conductive support and metallic thallium electro-plated thereon, which comprises applying a DC-AC overlapped electric current between an anode made of a metal or its alloy having a lower ionization tendency than hydrogen and the electro-conductive support as a cathode, both electrodes being immersed in a bath of an electro-plating solution comprising monovalent thallium ions in the presence of at least one of aromatic amines and phenols, so as to deposit the thallium metal on the surface of the thermo-conductive support.

4,297,167

NUCLEAR REACTOR INSTALLATION

Hans-Peter Schabert, Erlangen, Fed. Rep. of Germany, assignor to Kraftwerk Union Aktiengesellschaft, Mulheim an der Ruhr, Fed. Rep. of Germany


Filed Jul. 29, 1977, Ser. No. 820,117

Claims priority, application Fed. Rep. of Germany, Jul. 30, 1976, 2634295

Int. Cl.³ G21C 9/00

U.S. Cl. 376—273

25 Claims



16. Nuclear reactor installation having a concrete cell disposed beneath the earth and having a hill of fill-earth directly covering the top of the concrete cell for enclosing activity-carrying components comprising at least one additional self-enclosed concrete cell disposed in the earth and being isolated and separated from the first-mentioned concrete cell by a given distance forming a space between said cells, said additional concrete cell having at most one-fortieth the volume of the first-mentioned concrete cell and being at least predominantly of shell-like construction, and including equipment of use for the nuclear reactor installation received in said additional concrete cell and a conical attachment located in said additional concrete cell for a valve mounted thereat, said valve being in at least one of a live steam and a feedwater line for closing said line, said line extending to said first-mentioned concrete cell and being formed as a double-wall pipe.

4,297,168

Willard T. Grubb, Schenectady, N.Y., assignor to General Electric Company, Schenectady, N.Y.

Filed Jun. 29, 1976, Ser. No. 700,735

Int. Cl.³ G21C 3/18

U.S. Cl. 376—418

10 Claims

1. For use in a nuclear reactor, an oxide composition nuclear fuel material in compacted pellet form containing at least one fissionable isotope and an amount of an oxide selected from the group consisting of V_2O_4 and V_2O_5 and mixtures thereof effective to immobilize cadmium resulting from nuclear fission chain reactions of the nuclear fuel material through a reaction between the said cadmium and the said oxide and thereby prevent cadmium embrittlement of nuclear fuel cladding at reactor operating temperatures.

4,297,169

NUCLEAR FUEL ASSEMBLY AND PROCESS

Willard T. Grubb, Schenectady, N.Y., assignor to General Electric Company, Schenectady, N.Y.

Filed Jun. 29, 1976, Ser. No. 700,737

Int. Cl.³ G21C 3/18

U.S. Cl. 376—418

11 Claims

1. For use in a nuclear reactor, an oxide composition nuclear fuel material in compacted pellet form containing at least one fissionable isotope and an amount of a chemical displacement compound selected from the group consisting of $CuFe_2O_4$ and $CuTiO_3$ and mixtures thereof effective to immobilize cadmium resulting from nuclear fission chain reactions of the nuclear fuel material through a reaction between the said cadmium and the said chemical displacement compound and thereby prevent cadmium embrittlement of nuclear fuel cladding at reactor operating temperatures.

4,297,170

DEVICES FOR TRANSVERSELY HOLDING THE FUEL RODS OF A NUCLEAR REACTOR ASSEMBLY


Joseph Leclercq, Le Vesinet, France, assignor to Framatome, Courbevoie, France

Filed May 9, 1979, Ser. No. 37,483

Int. Cl.³ G21C 3/30

U.S. Cl. 376—442

8 Claims



1. A device for transversely holding the fuel rods of a bundle of fuel rods for a nuclear reactor assembly, which rods are arranged parallel to one another, in a uniform arrangement, having a plurality of support means for exerting forces on the rods in transverse directions to restrict vibrations thereof, while permitting axial lengthening of the rods, each of said support means comprising three sub-units comprising grids arranged adjacent one another in the longitudinal direction of the assembly, said sub-units comprising:

two end grids each formed by small metal plates which are assembled in a uniform network delimiting cells inside which the rods pass, and whose side walls, parallel to the longitudinal axis of the assembly, are formed by said small metal plates arranged transversely, relative to the assembly, so that their width constitutes the thickness of said grid in the longitudinal direction, said end grids being identical and each grid having the same network as the other, each wall of each cell of one grid being located in the same longitudinal plane as the corresponding wall of the other grid, said grids being made integral with one another with a longitudinal spacing along the fuel rods, and

an intermediate grid comprising small, elastic metal plates, the width of which is less than the width of said plates of said end grids, and which are assembled in a uniform network delimiting cells inside which the rods pass and arranged between said end grids in said longitudinal space provided therebetween, in a staggered manner in a transverse direction relative to said end grids, so that two adjacent elastic walls of the cells of said intermediate grid exert on each fuel rod transverse forces which press the rods against two walls of said cells of each end grid, said intermediate grid resting on at least one of said end grids.

4,297,171

NUCLEAR REACTOR FUEL ASSEMBLY

Torsten Olsson, Vesterås, Sweden, assignor to AB ASEA-ATOM, Sweden


Filed Oct. 10, 1979, Ser. No. 83,488

Claims priority, application Sweden, Oct. 13, 1978, 7810686

Int. Cl.³ G21C 3/30

U.S. Cl. 376—440

6 Claims



1. A nuclear reactor fuel assembly, comprising: an elongated box; a plurality of fuel rods vertically disposed within said box, said fuel rods each comprising an upper and lower end plug; and upper and lower grid means disposed within said box for supporting said fuel rods, at least one of said grid means comprising a plurality of prismatic, vertical channels, each one of a first portion of said channels being occupied by an end plug of one said fuel rod, the minimum width of the channels of said first portion being less than the maximum thickness of the associated fuel rod, and a second portion of said channels being open in order to function as coolant channels and further being distributed among the first portion so that each channel of said first portion is surrounded by at least eight adjacent coolant channels of said second portion.

4,297,172

LOW ENERGY PROCESS OF PRODUCING GASOLINE-ETHANOL MIXTURES


Benjamin G. Kyle, Manhattan, Kans., assignor to Kansas State University Research Foundation, Manhattan, Kans.

Filed Jan. 23, 1980, Ser. No. 114,699

Int. Cl.³ B01D 3/14; C07C 29/26, 31/08

U.S. Cl. 203—19

9 Claims



5. The energy saving process of producing gasoline-ethanol mixtures from aqueous ethanol for motor fuel use, comprising: (a) subjecting aqueous ethanol of 1 to 15 weight percent ethanol to fractional distillation and producing an overhead distillate in vapor form containing 75 to 90 weight

percent ethanol together with at least 10 weight percent water;

(b) condensing said distillate to provide reflux for said distillation column and a feed for a countercurrent multiple stage liquid-liquid extraction column; and without employing an azeotropic ethanol distillation;

(c) thereafter in a separate step subjecting said condensed distillate containing at least said 10% water in said extraction column to extraction with gasoline at a temperature of from 30° to 60° C. and producing a gasoline phase extract and a water phase raffinate, said gasoline extract containing from 8 to 14% ethanol by weight.

4,297,173

METHOD FOR DETERMINING AMMONIA AND SENSOR THEREFOR


Motohiko Hikuma; Tatsuru Kubo; Takeo Yasuda, all of Yokohama; Isao Karube, Tachikawa, and Shuichi Suzuki, Tokyo, all of Japan, assignors to Ajinomoto Company, Incorporated, Tokyo, Japan

Filed May 22, 1980, Ser. No. 152,177

Int. Cl.³ C12Q 1/00; G01N 27/30

U.S. Cl. 204—1 T

15 Claims



1. A method for determining ammonia concentration in an aqueous liquid which contains dissolved oxygen, which comprises:

- (a) Contacting a sample of said liquid with a microbial electrode comprising:
- an oxygen-sensitive electrode having a diaphragm, bacteria capable of oxidizing ammonium ion and thereby consuming oxygen in direct or close contact with the diaphragm of said oxygen sensitive electrode, said bacteria being confined or immobilized by a porous membrane permeable to ammonia and to oxygen and impermeable to microbial cells; and
- (b) electrochemically sensing the rate of consumption or their decrease in steady state concentration of said oxygen caused by said microorganisms, and thereby
- (c) detecting the concentration of ammonia from said rate or said decrease of the oxygen.

9. An ammonia-detecting electrode which comprises: an oxygen-sensitive electrode having a diaphragm; bacteria capable of oxidizing ammonium ion and thereby consuming oxygen in direct or close contact with the diaphragm of said oxygen sensitive electrode; said bacteria being confined or immobilized by a porous membrane permeable to ammonia or ammonium ions and to oxygen, and impermeable to microbial cells.

4,297,174

PYROELECTROCHEMICAL PROCESS FOR REPROCESSING IRRADIATED NUCLEAR FUELS

Giovanni Brambilla, Stagno, and Adelmo Sartorelli, Forlì, both of Italy, assignors to Agip Nucleare, S.p.A., Rome, Italy

Filed Mar. 8, 1979, Ser. No. 18,730

Int. Cl.³ C25C 1/22

U.S. Cl. 204—1.5

7 Claims

1. A pyroelectrochemical method for the reprocessing of

irradiated nuclear fuels coming preferably from fast reactors, characterized in that it comprises the steps of:

- (a) dissolving the nuclear fuel, containing fission products, in a bath comprising molten alkali metal sulfates,
- (b) thermally decomposing the plutonium sulfate, $\text{Pu}(\text{SO}_4)_2$, formed in said molten bath to plutonium oxide, PuO_2 ,
- (c) electrodepositing uranium oxide on the cathode of an electrolytic cell provided in said molten bath,
- (d) recycling the melted sulfates of said molten bath to the start of the process, and
- (e) conditioning said fission products and said melted sulfates.

4,297,175

PROCESS FOR PARTIALLY ELECTROPLATING FLAT SILVER

Hans Schlegel, Ulm, and Theodor Nowotny, Geislingen, both of Fed. Rep. of Germany, assignors to Württembergische Metallwarenfabrik, Geislingen, Fed. Rep. of Germany


Filed Dec. 8, 1980, Ser. No. 214,252

Claims priority, application Fed. Rep. of Germany, Feb. 21, 1980, 3006569

Int. Cl.³ C25D 5/00, 5/02; B21K 11/02

U.S. Cl. 204—15

8 Claims



1. a process for partially silver electroplating a flat silver part, the part including two metal components to be joined lengthwise, the first component to be covered with a plating-resistant dipping enamel and the second component to be electroplated with silver, the process comprising the steps of:

- (a) joining lengthwise the said two metal components;
- (b) providing a thin separation surface between exposed surfaces of said two components, said separation surface consisting of a material which is more difficult to wet with the dipping enamel than the metal of the first component to be covered;
- (c) dipping said first component into said enamel until contact is achieved between said enamel and said separation surface; and
- (d) silver electroplating said second component.

4,297,176

SURFACE PASSIVATION OF COMPOUND SEMICONDUCTORS

Stephen J. Hannah, Cockermouth, and Bryan Livingstone, Felling, both of England, assignors to National Research Development Corporation, London, England

Filed Feb. 27, 1980, Ser. No. 125,048

Claims priority, application United Kingdom, Mar. 9, 1979, 08453/79

Int. Cl.³ C25D 11/32

U.S. Cl. 204—37 R

17 Claims

1. A method of surface-passivating a compound semiconductor whose elements are differently volatile, comprising the steps of (a) anodizing a compound semiconductor to produce a layer thereon of native semiconductor oxide, (b) reducing all of the layer of oxide at elevated temperature and allowing the more volatile element of the reduced oxide to evaporate away, to leave predominantly the less volatile element overlying the

compound semiconductor, (c) depositing an anodisable metal on the surface of the less volatile element, (d) re-anodising the resulting structure until oxidation has proceeded to beyond the layer containing predominantly the less volatile element and from 10 A to 50 A into the compound semiconductor, and optionally at any suitable stage (e) applying an ohmic contact to the back surface of the compound semiconductor or selectively to the top surface as required.

4,297,177

METHOD AND COMPOSITION FOR ELECTRODEPOSITING PALLADIUM/NICKEL ALLOYS

Augustus Fletcher, Bristol, and William L. Moriarty, South Meriden, both of Conn., assignors to American Chemical & Refining Company Incorporated, Waterbury, Conn.

Filed Sep. 19, 1980, Ser. No. 188,977

Int. Cl.³ C25D 3/56

U.S. Cl. 204—43 N

8 Claims

1. In an aqueous bath for producing bright and relatively stress-free electroplate of palladium/nickel alloy, the combination, expressed as gram moles per liter, comprising: 0.01 to 0.25 of palladium ion; 0.015 to 0.85 of nickel ion; 0.15 to 1.5 of a soluble electrolyte selected from the group consisting of alkali metal and ammonium sulfates, sulfamates, phosphates, nitrates, nitrites, and mixtures thereof; 0.005 to 0.15 of a saccharin or soluble saccharate stress reducer; 1.5×10^{-4} to 10×10^{-4} of 3-butyne-2-ol brightener; up to 6×10^{-4} of cetyltrimethylammonium bromide; up to an effective amount of ammonium hydroxide; and water to volume, said palladium and nickel ions being substantially in the form of amino complexes, and said bath having a pH of 7 to 11, with said amount of ammonium hydroxide being effective to insure said complexed state of said ions and said pH value of said bath.

4,297,178

RUTHENIUM ELECTROPLATING AND BATHS AND COMPOSITIONS THEREFOR

Jeffrey N. Crosby, Worcester, England, assignor to The International Nickel Company, Inc., New York, N.Y.

Filed Apr. 9, 1980, Ser. No. 138,786

Claims priority, application United Kingdom, Apr. 10, 1979, 12648/79

Int. Cl.³ G01N 3/52; C07F 17/02

U.S. Cl. 204—47

34 Claims

22. A composition of matter adapted to be used in aqueous solution as an electroplating bath comprising as components:

- (a) a ruthenium-containing material having two ruthenium atoms linked by a nitrogen bridge atom, and
- (b) a water-soluble compound from the group oxalic acid, alkali metal salts of oxalic acid and alkali metal acid salts of oxalic acid.

24. An aqueous bath for electrodepositing ruthenium consisting essentially of as components:

- a. a ruthenium-containing material having two ruthenium atoms linked by a nitrogen bridge atom, and
- b. a water-soluble compound selected from the group consisting of a dibasic carboxylic acid, alkali metal salts of such acid, and alkali metal acid salts of such acid;

said bath having a pH in the range of above 4 up to about 10.

4,297,179

PALLADIUM ELECTROPLATING BATH AND PROCESS

Robert M. Skomoroski, Paterson, N.J., assignor to American Chemical & Refining Company Incorporated, Waterbury, Conn.

Filed Sep. 2, 1980, Ser. No. 183,318

Int. Cl.³ C25D 3/52

U.S. Cl. 204—47

11 Claims

1. An aqueous alkaline bath for the electrodeposition of palladium, comprising:

- (a) about 0.035 to 0.4 gram mole per liter of palladium ion;

- (b) at least about 1.5 gram moles per liter of ammonium radical;
- (c) about 1.25×10^{-5} to 125×10^{-5} gram mole per liter of 3-butyne-2-ol as a brightener; and
- (d) at least 0.1 gram mole of electrolyte per liter; said bath having a pH of about 9 to 11.5, and being free of cyanide radical.

4,297,180

ELECTROLYTIC PRODUCTION OF METAL


Perry A. Foster, Jr., New Kensington, Pa., assignor to Aluminum Company of America, Pittsburgh, Pa.

Division of Ser. No. 717,700, Aug. 25, 1976, Pat. No. 4,219,391, which is a continuation-in-part of Ser. No. 645,533, Dec. 21, 1975, abandoned. This application Sep. 26, 1979, Ser. No. 79,025

Int. Cl.³ C25C 3/06, 3/00

U.S. Cl. 204—67

13 Claims



1. A method for the electrolytic production of metal, including electrolyzing, between anodic and cathodic surface areas, a compound of the metal dissolved in a molten solvent, the electrolyzing being performed at a temperature such that the metal is formed in the molten state, the metal collecting in a molten metal pad, the anodic surface area being formed by at least one anode block, wherein the improvement comprises the provision of cathodic surface area in the form of an array of islands protruding out of the pad into the solvent toward said block for establishing a series of locations at which the anode-cathode distance is up to $1\frac{1}{4}$ inches, whereby anode-cathode distances less than the distance separating the metal pad from the anode block are achieved without hindrance from magnetic turbulence in the metal pad, the voltage drop experienced in the solvent becomes less than it would be in the absence of the islands, and replenishment of the dissolved compound is improved over what it would be with a planar cathode.

4,297,181

PROCESS FOR PREPARING KETONES

Tatsuya Shono, 13, Ichikawacho 1-chome, Kamitakano, Sakyo-ku, Kyoto-shi, Kyoto 606, Japan

PCT No. PCT/JP79/00257, § 371 Date Jun. 11, 1980, § 102(e) Date Jun. 11, 1980, PCT Pub. No. WO80/00714, PCT Pub. Date Apr. 17, 1980

PCT Filed Oct. 11, 1979, Ser. No. 198,958

Claims priority, application Japan, Oct. 11, 1978, 53-125406

Int. Cl.³ C25B 3/02

U.S. Cl. 204—78

6 Claims

1. Process for preparing a ketone, characterized in that a secondary alcohol is subjected to a catalytic electrode oxidation in the presence of iodine or/and an iodine compound.

4,297,182

PRODUCTION OF ALKALI METAL HYDROXIDE
Yoshio Oda; Takeshi Morimoto, and Kohji Suzuki, all of Yokohama, Japan, assignors to Asahi Glass Company, Ltd., Tokyo, Japan

Filed Apr. 18, 1980, Ser. No. 141,401

Claims priority, application Japan, May 4, 1979, 54-54040

Int. Cl.³ C25B 1/34, 11/03, 11/06, 13/08

U.S. Cl. 204—98

7 Claims

1. In a process for producing an alkali metal hydroxide by electrolyzing an aqueous solution of an alkali metal chloride by using a gas and liquid-permeable cathode bonded on an ion-exchange membrane, the improvement wherein said gas and liquid permeable cathode consists essentially of a nickel containing powder selected from the group consisting of a thermally decomposed nickel obtained from a nickel salt of fatty acid; Raney nickel; stabilized Raney nickel; and carbonyl nickel and a polytetrafluoroethylene.

4,297,183

PROCESS FOR THE TREATMENT OF SOLUTIONS OF LEAD CHLORIDE

André Georgeaux, Rambouillet, France, assignor to Societe Miniere et Metallurgique de Penarroya, Paris, France

Filed Aug. 12, 1980, Ser. No. 177,434

Claims priority, application France, Aug. 24, 1979, 79 21325

Int. Cl.³ C25L 1/18

U.S. Cl. 204—117

13 Claims

1. A process for the treatment of solutions of lead chloride containing as impurities at least one metal selected from the group consisting of silver, copper and bismuth, comprising the following steps:

- (a) contacting the solution with a cation exchange resin whose active group is a sulfhydryl group to separate impurities from the solution by absorption on the resin; and
- (b) recovering the lead from the solution after the solution has contacted the resin in step (a).

4,297,184

METHOD OF ETCHING ALUMINUM


Christopher K. Dyer, Summit, N.J., assignor to United Chemical, Inc., Rosemont, Ill.

Filed Feb. 19, 1980, Ser. No. 122,460

Int. Cl.³ C25F 3/04

U.S. Cl. 204—129.4

7 Claims



1. In a method of etching aluminum by applying an alternating electric current to aluminum which is in contact with an electrolyte containing hydrochloric acid, the improvement in which the alternating current has a wave form wherein the current rises rapidly from zero to a maximum, then subsequently decreases rapidly in a first stage to an intermediate value which is about one-third to about one-half of the maximum, and thereafter decreases more slowly to zero in a second stage, the ratio of time of the second stage to time of the first stage being in the range from 1 to 6, whereby higher capacitance values of the etched aluminum are obtained.

PHOTOSETTING ADHESIVE FROM UNSATURATED OLIGOMER, PHOTOINITIATOR, AND BETAINE-FORMING MIXTURE OF UNSATURATED TERT-AMINE AND UNSATURATED ACID

Pierre Chevreux, St Jean De Gonv, France; Van-Tao Nguyen, Petit-Lancy, Switzerland; Alain Roman, Bossey, France, and Daniel Turpin, Nyon, Switzerland, assignors to Techinter S.A., Geneva, Switzerland

Filed Sep. 18, 1979, Ser. No. 76,780

Claims priority, application Switzerland, Sep. 20, 1978, 9815/78

Int. Cl.³ C08F 2/50, 220/28; C08L 75/04; B32B 27/16

U.S. Cl. 204—159.15

16 Claims

1. A photohardenable composition polymerizable by irradiation under u.v. light to provide an adhesive and including:

- (A) at least one olefinic photopolymerizable prepolymer having an olefinic double bond activated by an electrophilic substituent, and
- (B) a polymerization photoinitiator, characterised in that the composition also includes
- (C) a substituted or unsubstituted aliphatic or cycloaliphatic N,N-dialkylamino alcohol ester of an α,β -ethylenically unsaturated carboxylic acid, said alcohol having an alkylene moiety of up to six carbon atoms between the hydroxy and the amino functions, and
- (D) an α,β -ethylenically unsaturated carboxylic acid in an amount equal to one mole per mole of C, (C) and (D) being capable of reacting together to form a betaine, and said oligomer or prepolymer (A) is an ester of an α,β -ethylenically unsaturated acid and a hydroxylated product containing urethane and/or urea links in the molecule thereof and having a molecular weight from about 500 to 10,000.

4,297,186

METHOD AND APPARATUS FOR REDUCING THE ACTIVATION ENERGY OF CHEMICAL REACTIONS

Walter HP Killer, Burghalde 10, Lenzburg, Switzerland


Continuation of Ser. No. 775,229, Mar. 7, 1977, abandoned. This application Apr. 11, 1979, Ser. No. 29,100

Claims priority, application Switzerland, Mar. 16, 1976, 3292/76

Int. Cl.³ C08F 2/52

U.S. Cl. 204—165

9 Claims



1. A method of reducing the activation energy of polymerization reactions between organic molecules selected from the group consisting of olefins, dienes, O-vinyl compounds, halogenated hydrocarbons and aldehydes; and of polymerization reactions or aldol condensation reactions between molecules of benzaldehyde and acetophenone, comprising the steps of:

4,297,189


DEPOSITION OF ORDERED CRYSTALLINE FILMS
Elroy C. Smith, Jr., La Habra, and Shi K. Yao, Anaheim, both of Calif., assignors to Rockwell International Corporation, El Segundo, Calif.

Filed Jun. 27, 1980, Ser. No. 163,532

Int. Cl.³ C23C 15/00

U.S. Cl. 204—192 SP

29 Claims



13. A method of forming a film of ordered polycrystalline material on a selected object in a cross-field radio frequency magnetron sputtering chamber having sputtering elements in the ceiling thereof, said method comprising the steps of:

- orienting a line normal to the deposition surface of said selected object at an angle of about sixty degrees away from the vertical; and
- deflecting charged particles away from said selected object by means of a positively charged electrode disposed in the vicinity of said selected object and spaced a significant distance away from said sputtering elements, wherein said electrode is electrically isolated from said sputtering elements.

4,297,187

SURFACE TREATMENT OF PLASTIC MATERIAL
Yukichi Deguchi; Hideki Yamagishi, and Shunichiro Kirimura, all of Tokyo, Japan, assignors to Toray Industries, Inc., Tokyo, Japan


Filed Oct. 5, 1979, Ser. No. 82,271

Claims priority, application Japan, Oct. 5, 1978, 53-123013

Int. Cl.³ C08F 2/52

U.S. Cl. 204—165

8 Claims



1. In a process for treating the surface of a plastic material, the step which comprises subjecting the surface of the material to corona discharge in contact with a mixed gas which substantially consists of nitrogen and carbon dioxide, the volume of nitrogen to carbon dioxide in said mixed gas being in the range of 99.5:0.5 to 50:50.

4,297,188

PROCESS FOR THE ELECTROLYTIC COATING OF CONDUCTIVE SUBSTRATES WITH PROTECTIVE FILMS OF PHENOLIC RESINS

Sergio Daolio, Luzzara; Giuliano Mengoli, Padua; Carlo Folonari, Turin, and Marco Musiani, Casalecchio di Reno, all of Italy, assignors to Centro Ricerche Fiat S.p.A., Orbassano and Consiglio Nazionale Delle Ricerche, Rome, both of Italy

Filed Sep. 23, 1980, Ser. No. 189,989

Claims priority, application Italy, Sep. 24, 1979, 68853 A/79

Int. Cl.³ C25D 13/08

U.S. Cl. 204—181 R

13 Claims

1. A process for coating a conductive substrate used as the anode in an electrochemical cell in which a direct electric current is passed from a cathode to the said anode through an electrolytic liquid containing one or more phenolic monomers to form a polymeric film of phenolic resin on the substrate, which comprises using an electrolyte which includes from 10 to 200 g/l of phenolic monomer consisting of allylphenol or a mixture thereof with one or more other phenols, and from 5 to 200 g/l of an aliphatic amine, in solution in a mixture of water and alcohol in a volume ratio of from 20:1 to 0.05:1, forming the polymeric film by using an electric current of density not greater than 50 mA/cm² of substrate, and heating the polymeric film thus deposited at a temperature of from 100° to 200° C. to induce hardening of the said resin.

4,297,190

METHOD FOR REMOVING HEAT FROM A WORKPIECE DURING PROCESSING IN A VACUUM CHAMBER


Robert W. Garrett, Reading, Pa., assignor to Western Electric Co., Inc., New York, N.Y.

Division of Ser. No. 38,741, May 14, 1979. This application Dec. 1, 1980, Ser. No. 211,603

Int. Cl.³ C23C 15/00

U.S. Cl. 204—192 E

5 Claims



1. In a sputter etch process performed on a workpiece in an RF sputtering chamber wherein a highly conductive thermal path is provided between the workpiece and a cold plate and the workpiece is held securely in place during the sputtering operation, the improvement comprising using an expandable heat pipe for providing a highly conductive thermal path from the workpiece to a cold plate.

4,297,191

ISOTOPIC SEPARATION


Cheng-Lin Chen, Pittsburgh, Pa., assignor to Westinghouse Electric Corp., Pittsburgh, Pa.

Division of Ser. No. 864,344, Dec. 27, 1977. This application Aug. 30, 1979, Ser. No. 70,939

Int. Cl.³ B01D 59/00

U.S. Cl. 204—193

2 Claims



1. Apparatus for separating isotopes in an isotopic mixture having a first species including a first isotope of a particular element and a second species including a second isotope of said element, said apparatus comprising:

structure defining a flow passage, said passage serially including means for inletting a flowing gas, means for passing said inletted flowing gas through a curved centrifuge section having an inner radius of curvature and an outer radius of curvature, and means for segmenting said passage into a plurality of outlets including an inner segment disposed toward said inner radius and an outer segment disposed toward said outer radius;

means for creating a magnetic field within said centrifuge section;

means for creating a discharge zone between said gas inlet means and said centrifuge section;

means for injecting said mixture in a gaseous phase into said flow passage downstream of said discharge means; and

means for irradiating said injected mixture between said injecting means and at least a portion of said centrifuge section so as to selectively excite said first species.

2. Apparatus for separating isotopes in an isotopic mixture having a first species including a first isotope of a particular element and a second species including a second isotope of said element, said apparatus comprising:

means for creating an electrical discharge zone;

means for flowing a selected gas through said zone;

means for injecting said mixture into said flowing gas at a preselected distance downstream of said discharge zone such that said mixture flows in a direction substantially similar to the flow of said gas;

means for irradiating said mixture subsequent to said injection so as to selectively excite said first species and cause a predetermined release of reaction products, some of said products being of differing mass and including a species of said first isotope in a form different than its initial form prior to said irradiation;

curved means for deflecting said products of differing mass along differing flow paths;

means for creating a magnetic field in the region of said curved deflecting means; and

means for collecting said deflected products including a segment for collecting said species of said first isotope in a different form.

4,297,192

CATALYST SUPPORTED OXYGEN SENSOR ELEMENT

AND A METHOD OF MANUFACTURING SAME


Hiroshi Shinohara, Okazaki; Yasuhiro Otsuka, Toyota; Shinichi Matsumoto, Toyota; Hiroshi Wakisaka, Toyota, and Toshinobu Furutani, Toyota, all of Japan, assignors to Toyota Jidosha Kogyo Kabushiki Kaisha, Toyota, Japan

Filed Dec. 18, 1979, Ser. No. 104,966

Int. Cl.³ B05D 1/08; G01N 27/58

U.S. Cl. 204—195 S

12 Claims



1. In an oxygen sensor element detecting the oxygen concentration in exhaust gas from vehicle engines comprising a tubular container of a solid electrolyte conductive of ions with one end portion closed, an inner electrode positioned on the inner circumference of the tubular container and an outer electrode positioned on the outer circumference thereof, the improvement which comprises a protective layer of MgO·Al₂O₃ formed on the outer circumference of the outer electrode and a catalyst layer formed on the outer circumference of the protective layer, said catalyst layer comprising an alumina carrier and one or more oxidation catalysts.

9. A method of manufacturing an oxygen sensor element which comprises the steps of: forming an inner electrode on the inner circumference of a tubular container of a solid electrolyte conductive of ion with one terminal portion closed and an outer electrode on the outer circumference thereof; forming a protective layer of MgO·Al₂O₃ on the outer circumference of the outer electrode by flame spraying; and thereafter forming a catalyst layer on the outer circumference of the protective layer by applying an aqueous slurry comprising an alumina carrier, an oxidation catalyst and binder, followed by drying and burning.

4,297,193

PH ELECTRODE GLASS COMPOSITIONS

Donald P. Brezinski, Corning, and Leroy R. Morse, Campbell, both of N.Y., assignors to Corning Glass Works, Corning, N.Y.

Filed May 22, 1980, Ser. No. 152,358

Int. Cl.³ G01N 27/36; C03C 3/04

U.S. Cl. 204—195 G

22 Claims

1. A glass composition for use in pH-responsive glass electrodes consisting essentially of (in mole percent on the oxide basis):

- from about 30 to about 37 mole percent Li₂O;
- from 0 to about 4 mole percent of at least one oxide selected from the group consisting of Cs₂O and Rb₂O;
- from about 2 to about 12 mole percent of at least one oxide selected from the group consisting of La₂O₃ and Pr₂O₃;
- from about 2 to about 10 mole percent of at least one oxide selected from the group consisting of Ta₂O₅ and Nb₂O₅;
- from 0 to about 4 mole percent UO₂; and
- the balance SiO₂;

with the proviso that there is present in the composition at least about 2 mole percent of at least one oxide selected from the group consisting of Pr₂O₃ and Nb₂O₅.

12. A glass electrode having a pH-responsive membrane of glass having a composition consisting essentially of (in mole percent on the oxide basis):

- from about 30 to about 37 mole percent Li₂O;

- from 0 to about 4 mole percent of at least one oxide selected from the group consisting of Cs₂O and Rb₂O;
 - from about 2 to about 12 mole percent of at least one oxide selected from the group consisting of La₂O₃ and Pr₂O₃;
 - from about 2 to about 10 mole percent of at least one oxide selected from the group consisting of Ta₂O₅ and Nb₂O₅;
 - from 0 to about 4 mole percent UO₂; and
 - the balance SiO₂;
- with the proviso that there is present in the composition at least about 2 mole percent of at least one oxide selected from the group consisting of Pr₂O₃ and Nb₂O₅.

4,297,194

ELECTROLYTIC PRODUCTION OF HIGH PURITY ALKALI METAL HYDROXIDE

Ronald L. Dotson, Mentor, and Kevin J. O'Leary, Cleveland Heights, both of Ohio, assignors to Diamond Shamrock Corporation, Dallas, Tex.


Division of Ser. No. 191,424, Oct. 21, 1971, Pat. No. 4,025,405.

This application Feb. 16, 1977, Ser. No. 769,098

Int. Cl.³ C25B 9/00


U.S. Cl. 204—257

5 Claims




1. An electrolytic cell for the production of aqueous alkali metal hydroxide solution substantially free of alkali metal halide and other impurities comprising

- a first hollow cell section having disposed therein a dimensionally stable anode, an electrolyte inlet, a spent electrolyte outlet, a halogen gas outlet and electrical connection means for supplying current to said anode;
- a second hollow cell section having disposed therein a metal cathode, an outlet for the aqueous solution of alkali metal hydroxide product, an outlet for hydrogen gas and electrical connection means for conducting current from said cathode; and
- a hydrated fluorinated copolymer cationic exchange resin film membrane having pendant sulfonic acid groups or derivatives thereof arranged between said hollow cell sections closely spaced between a surface of each said anode and said cathode and held in fixed juxtaposed position by said hollow cell sections, said film membrane having the structural formula:



and

(2) $-\text{CXX}'-\text{CF}_2-$
wherein R represents the group



in which R' is fluorine or perfluoroalkyl of 1 to 10 carbon atoms, Y is fluorine or trifluoromethyl, and m is 1, 2 or 3, n is 0 or 1;

X is fluorine, chlorine, hydrogen or trifluoromethyl; and X' is X or CF₃—CF₂— wherein z is 0 or an integer from 1 to 50; the units of formula (1) being present in an amount from 3 to 20 mole percent.

4,297,195

ELECTRODE FOR USE IN ELECTROLYSIS AND PROCESS FOR PRODUCTION THEREOF

Hideo Sato, Chiba, and Takayuki Shimamune, Ichihara, both of Japan, assignors to Permelec Electrode Ltd., Tokyo, Japan


Filed Sep. 20, 1979, Ser. No. 77,224

Claims priority, application Japan, Sep. 22, 1978, 53-115894

Int. Cl.³ C25B 11/08

U.S. Cl. 204—290 F

2 Claims



1. An electrode for use in the electrolysis of an aqueous solution of a metal halide, said electrode comprising an electrically conductive substrate and, formed thereon, a coating comprising

- 50 to 95 mole % of the platinum and
- (a) 5 to 50 mole % of tin oxide, or
- (b) 5 to 50 mole % of tin oxide and cobalt oxide wherein the tin oxide is present in an amount of at least 5 mole % and the cobalt oxide is present in an amount up to 20 mole %, the total of (1) and (2) being 100 mole %.

4,297,196

STABLE LOW VOLTAGE MICROPOROUS DIAPHRAGM FOR ELECTROLYTIC CELLS


Christine A. Lazarz, and Edward H. Cook, Jr., both of Niagara Falls, N.Y., assignors to Hooker Chemicals & Plastics Corp., Niagara Falls, N.Y.

Filed Mar. 17, 1980, Ser. No. 130,766

Int. Cl.³ C25B 13/04, 13/08

U.S. Cl. 204—296

8 Claims



pores, by porosimeter analysis, being of pores in the range of 0.1 to 100 microns in diameter and with over 80% of the volume of the pores being in pores in the range of 0.12 to 33 microns in diameter, and with the ratio of the number of pores in the 0.09 to 0.3 micron diameter range to the number of pores in the 0.8 to 20 micron diameter range being less than about 50.


4,297,197

ELECTROPLATING RACK

Syed Salman, Sterling Heights, Mich., assignor to International Telephone and Telegraph Corp., New York, N.Y.
Filed Nov. 13, 1980, Ser. No. 206,400
Int. Cl.³ C25D 17/08

U.S. Cl. 204—297 W

6 Claims



1. In an electroplating rack composed of an electrically conductive metal coated with an insulating coating, said rack having tips at extremities thereof, said tips being uncoated to provide electrical contact for a part being plated, the improvement in which the portion of the rack adjacent the tip has at least one opening therein through said rack, said opening being coated with said insulating coating, such that a continuous coating is formed with the coating on the opposite surfaces of said portion of the rack.

4,297,198

CONCENTRATING ELECTROPHORESIS APPARATUS

Mochihiko Ohashi, 2-33-16-507, Tokiwadai, Itabashi-ku, Tokyo, and Tosifusa Toda, 2-6-4, Shinpo-cho, Higashikurume-shi, Tokyo, both of Japan

PCT No. PCT/JP79/00137, § 371 Date Jan. 8, 1980, § 102(e) Date Jan. 8, 1980, PCT Pub. No. WO79/01141, PCT Pub. Date Dec. 27, 1979


PCT Filed May 29, 1979, Ser. No. 190,869

Claims priority, application Japan, May 29, 1978, 53-64307

Int. Cl.³ G01N 27/26; C25B 7/00

U.S. Cl. 204—299 R

11 Claims



1. A concentrating electrophoresis apparatus comprising: supply means for a buffer solution containing terminating ions and electrically connected to one electrode of a direct-current or alternating-current superposed direct-current electric power source; a supporting medium for separation electrically connected to the other electrode of the power source and comprising a water-retentive membrane or sheet material wetted with a buffer solution containing leading ions; a supporting medium for concentration comprising a water-retentive membrane material wetted with a buffer solution containing leading ions and having a pH different from that of the

buffer solution wetting the supporting medium for separation; and a movable mechanism for causing the supporting medium for concentration at its one end to contact the supply means and at its other end to contact the supporting medium for separation and imparting electrical connection through these supply means, supporting medium for concentration, and supporting medium for separation.

4,297,199

SPECIMEN APPLICATOR


Kazuo Hijikata, Hachioji, Japan, assignor to Olympus Optical Company Limited, Tokyo, Japan
Filed Nov. 12, 1980, Ser. No. 210,512

Claims priority, application Japan, Nov. 14, 1979, 54-146386

Int. Cl.³ G01N 27/26

U.S. Cl. 204—299 R

5 Claims



1. A specimen applicator comprising a wetting means to wet a carrier with a certain electrolytic solution, an applying means to apply a specimen onto the thus wetted carrier, a detector to detect electric resistivity of the carrier so as to generate an electric signal representing wetness of the carrier as determined by the thus detected electric resistivity, and a control means to control the application of the specimen onto the carrier based on said electric signal from said detector so as to always apply a certain amount of the specimen onto said carrier in a uniform fashion.

4,297,200

METHOD FOR HYDROCONVERSION OF SOLID CARBONACEOUS MATERIALS

Patrick B. Briley, 131 Lee La., Bolingbrook, Ill. 60439

Filed Jan. 18, 1980, Ser. No. 113,222

Int. Cl.³ C10G 1/06, 1/00

U.S. Cl. 208—10

42 Claims

1. A process for hydroconversion of solid carbonaceous materials comprising the steps of: contacting in a dissolution zone particulate solid carbonaceous material with a hydrocarbon solvent; removing from said dissolution zone a first stream containing hydrocarbon liquids, hydrocarbon gases, and particulate carbonaceous material; separating said first stream into a second stream and a third stream, said second stream consisting substantially of gas phase material; separating with a solids separation device said third stream into a fourth stream and a fifth stream, said fourth stream having an average solid size smaller than the average solid size in said fifth stream; introducing at least a portion of said fifth stream into said dissolution zone; separating said fourth stream into a sixth stream and a seventh stream; introducing at least a portion of said seventh stream into said third stream; adding molecular hydrogen to said sixth stream; heating said sixth stream; introducing said sixth stream into a catalytic hydrogenation zone; removing from said catalytic hydrogenation zone an eighth stream; separating said eighth stream into a ninth stream and a tenth

stream, said ninth stream consisting substantially of gas phase materials; introducing at least a portion of said tenth stream into said fourth stream; and repeating the above steps until the desired amount of hydro-conversion is achieved.

4,297,201

PROCESS FOR OIL SHALE RETORTING

John B. Jones, and S. Kumar Kunchal, both of 300 Enterprise Bldg., Grand Junction, Colo. 80501

Filed Jan. 3, 1978, Ser. No. 866,358

Int. Cl.³ C10G 1/00; C10B 21/18, 47/20, 57/12

U.S. Cl. 208—11 R

6 Claims

1. A continuous process for the recovery of energy containing products from oil shale consisting essentially of:

- retorting a particulate oil shale in a separated retort vessel by injecting a heated, generally non-oxygenous recycle gas, from retorting oil shale, into a bed of such oil shale in the retort vessel;
- withdrawing gas and products of retorting from said retort vessel, and withdrawing hot retorted shale containing carbon residue from said separated retort vessel;
- passing said gas and products of retorting to a separation process to remove liquid products from gas, and withdrawing a portion of the gas as a high Btu product gas, and recycling the remainder of the gas to a second heat exchanger;
- passing the hot, retorted shale into a separated combustion vessel;
- injecting oxygen containing gas into said hot retorted shale to burn at least some of the carbon residue to produce hot gases of combustion and retorted and spent shale as waste;
- passing said hot gases of combustion to a first heat exchanger to produce high temperature steam, and
- passing hot gases of combustion from said first heat exchanger to said second heat exchanger to heat recycle gas passing into said retort vessel.

4,297,202

TWO-STAGE INTEGRATED COKING FOR CHEMICALS AND COKE GASIFICATION PROCESS

Don E. Blaser, Randolph, N.J., assignor to Exxon Research & Engineering Co., Florham Park, N.J.


Continuation-in-part of Ser. No. 789,569, Apr. 21, 1977,

abandoned. This application Jul. 5, 1978, Ser. No. 922,044

Int. Cl.³ C10G 9/28, 37/06

U.S. Cl. 208—54

10 Claims



1. In an integrated coking and gasification process comprising the steps of:

- reacting a carbonaceous material having a Conradson carbon content of at least 10 weight percent in a coking zone containing a bed of fluidized solids maintained at fluid coking conditions including a temperature ranging from about 850° F. to about 1195° F., to form a vaporous coking zone conversion product and coke, said coke depositing on said fluidized solids;
- introducing a portion of said solids with the coke deposi-

tion thereon into a heating zone operated at a temperature greater than said coking zone temperature to heat said portion of solids;

- recycling a first portion of heated solids from said heating zone to said coking zone and introducing a second portion of said heated solids to a fluid bed gasification zone maintained at a temperature greater than the temperature of said heating zone; and
- passing said vaporous coking zone conversion product with entrained solids to a gas-solids separation zone, the improvement which comprises withdrawing a portion of solids from the gasification zone and introducing said portion of solids into said gas-solids separation zone in an amount sufficient to maintain said gas-solids separation zone at a temperature in the range of about 1200 to about 1700 degrees Fahrenheit to convert at least 20 weight percent of the coking zone vaporous product to unsaturated hydrocarbons having less than 6 carbon atoms.

4,297,203

APPARATUS FOR THE CATALYTIC CRACKING OF HYDROCARBONS


William D. Ford, Downers Grove, Ill., and Michael J. Clark, Chesterton, Ind., assignors to Standard Oil Company (Indiana), Chicago, Ill.

Filed Apr. 14, 1980, Ser. No. 139,894

Int. Cl.³ C10G 11/18, 51/06

U.S. Cl. 208—74

14 Claims



1. In a fluidized catalytic cracking system comprising in combination a spent catalyst stripper, a spent catalyst regenerator, and multiple reactors, apparatus for the fluidized catalytic cracking of hydrocarbon feedstocks in multiple reactors comprising:

- a first elongated transfer line reactor which is adapted for the fluid catalytic cracking of hydrocarbon feedstock, having an upper and lower end, said lower end having both a regenerated catalyst inlet means and a hydrocarbon feedstock inlet means;
- a reactor vessel communicating with and enclosing the upper end of said first transfer line reactor;
- an outlet means for removing spent catalyst from the lower portions of said vessel;
- a first cyclone separation system located within said vessel and adapted to separate catalyst particles from vapors, which comprises at least one cyclone gas-solids separation means having a dip-leg depending therefrom;
- a vapor outlet means connected to said first cyclone separation system;
- a second elongated transfer line reactor which is adapted for the fluidized catalytic cracking of hydrocarbon feedstock, having an upper and lower end, said lower end having both a regenerated catalyst inlet means and a hydrocarbon feedstock inlet means;

4,297,210

CENTRIFUGAL SEPARATOR


Claude Delfosse, Hellemes, France, assignor to Fives-Cail Babcock, Paris, France

Filed Jul. 31, 1980, Ser. No. 173,961

Int. Cl.³ B01D 33/02, 33/34

U.S. Cl. 210—107

5 Claims



1. An apparatus for the centrifugal separation of solids from a liquid, which comprises
 - (a) a cylindrical basket having a perforate side wall defining an interior chamber, the basket being mounted for rotation about a vertical axis,
 - (b) means for charging a solids-liquid mixture into the interior chamber of the basket, rotation of the basket causing a cake of the solids to be built up on the side wall while the liquid is centrifugally removed therethrough,
 - (c) a control for the charging means, the control including
 - (1) a sensing element for sensing the thickness of the cake built up on the side wall,
 - (d) a vertically extending manifold delivering a wash fluid adjustably positioned in the interior chamber,
 - (e) a mobile support for the manifold, movement of the support causing the position of the manifold to be adjusted, and
 - (f) means movably connecting the mobile support to the control whereby the position of the manifold is a function of the thickness of the cake sensed by the sensing element of the control.

4,297,211

FILTERING APPARATUS

Edwin Hiesinger, Jenbach; Klaus Keplinger, and Hermann Nessler, both of Innsbruck, all of Austria, assignors to Inkomag, Basel, Switzerland

Continuation-in-part of Ser. No. 907,628, May 19, 1978, abandoned. This application Aug. 29, 1979, Ser. No. 70,799

Claims priority, application Austria, May 20, 1977, 3609/77

Int. Cl.³ B01D 37/02

U.S. Cl. 210—136


45 Claims

1. A filtering apparatus comprising:
 - a housing defining a filter chamber;
 - a rigid partition extending through said chamber and subdividing same into an upstream compartment and a downstream compartment communicating with said upstream compartment via throughgoing openings formed in said partition;
 - a support fabric overlying said partition and permeable to a fluid, said support fabric lying along a side of said partition turned toward said upstream compartment;
 - means including a closable inlet opening communicating with said upstream compartment and a closable outlet opening communicating with said downstream compartment for passing through said chamber from said upstream compartment to said downstream compartment a carrier

medium entraining a particulate filter-aid layer onto said fabric in said upstream compartment;

means including a closable inlet opening communicating with said upstream compartment and a closable outlet opening communicating with said downstream compartment for passing a filterable medium through said chamber from said upstream compartment to said downstream compartment whereby said filterable medium traverses said layer and said fabric;

washing means including a closable inlet opening connect-



able with said chamber on the downstream side of said fabric and a closable outlet opening communicating with said upstream compartment at an upstream side of said fabric for passing a washing medium through said chamber from said inlet to said outlet opening and thereby backwashing said layer from said fabric and entraining material of said layer out of said chamber through said outlet opening;

means to close each of said inlet and outlet openings; and

displacement means for downstream removing media residues completely from each of said compartments.

4,297,212

OIL FILTER UNIT


Henry A. Padgett, Sr., Rte. 1, Monetta, S.C. 29105

Filed Jun. 9, 1980, Ser. No. 157,875

Int. Cl.³ B01D 27/08; F01M 1/00

U.S. Cl. 210—168

9 Claims



1. An improved oil filter unit for use with an oil lubricating system of an engine having a filter-receiving fitting which includes a central, threaded oil flow pipe and oil flow passage-way means radially disposed thereabout for circulating engine oil from the engine through the filter unit attached thereto; said filter unit comprising a generally cylindrical filter housing

having an end wall and an initially open opposite end for receiving a disposable filter medium therein, said end wall having a central opening therethrough for receiving the oil pipe of the engine fitting, and a plurality of openings radially disposed about said central opening for communicating with the oil flow passageway means of the engine fitting to permit circulation of oil into and out of the housing, elongate tube means in said housing extending from said end wall opening along the central axis of the housing and terminating in an open end adjacent the initially open end of the housing, a generally cylindrical disposable filter medium with central opening therethrough supportably received in said housing around and along the length of said tube means in engagement with the outer surface of the tube means and inner surface of the cylindrical wall of the housing, a closure cap threadably received on the open end of said cylindrical housing in fluid-tight relationship therewith, said tube means, filter housing, and closure cap defining an elongate oil flow path between the central opening of the housing end wall and the radially disposed openings of the end wall for circulating oil through the length of said filter medium for filtration thereby, gasket means on the outside of the housing end wall disposed radially outwardly of said end wall openings to sealingly engage the housing with the engine, filter medium support means adjacent the open end portion of said elongate tube means to supportably position the filter medium within the housing above the open end of the tube and in spaced relation from the closure cap, and means for securing the filter housing to the engine fitting flow pipe to maintain it thereon during removal of the closure cap for replacement of a filter medium in the housing.

4,297,213

APPARATUS FOR SEPARATING AND CONTACTING FRIABLE PARTICULATE ORGANIC MATTER FROM AND WITH LIQUIDS

Frederick K. Airey, "Swanlands", Hilltop La., Chinnor Hill, Chinnor, Oxon, and Arthur R. Evans, Well House, Hopton, Nesscliffe, both of England


Filed Dec. 6, 1979, Ser. No. 100,988

Claims priority, application United Kingdom, Dec. 6, 1978, 47413/78

Int. Cl.³ B01D 25/04

U.S. Cl. 210—195.1

6 Claims



1. An apparatus comprising a series of troughs or retention tanks positioned on different levels to operate in a cascade fashion provided with perforate screens, supply means for supplying a mixture of carrier liquid and friable particulate matter to a first trough, collecting means for receiving separated friable matter from the last perforate screen in the series; said perforate screens being concave and disposed with a generally downward slope immediately downstream of each trough to separate liquid from a mixture of liquid and friable matter overflowing from the immediately preceding trough, a trough receiving means associated with each perforate screen for receiving liquid passing through its associated perforate screen, the outlet of each perforation in each perforate screen being larger than the inlet thereof and a recycling supply means for supplying liquid to each of said troughs after the first trough, said recycling supply means being associated with each

trough receiving means and connecting its associated trough receiving means with the trough next but one upstream of said associated receiving means.

4,297,214

AERATOR

Claudio Guarnaschelli, 5583 Spruce St., Burnaby, British Columbia, Canada (V5G 1Y7)


Filed Nov. 2, 1979, Ser. No. 90,525

Claims priority, application Canada, Feb. 5, 1979, 320978

Int. Cl.³ C02F 1/74

U.S. Cl. 210—219

5 Claims



1. An apparatus for mixing gases with a body of liquid having a surface, the apparatus comprising:
 - a hollow rotatable surface for extending downwardly from near the surface, the shaft having a top and a bottom end, said bottom end having apertures formed therethrough;
 - an intake for gas near the top end of the shaft for positioning above the surface;
 - an impeller connected to the shaft near the outlet for gas, the impeller comprising two spaced-apart discs with a plurality of vane elements therebetween;
 - an annular opening in a top said disc about the shaft;
 - a tube connected to the top disc and extending towards the top end of the shaft, above the annular opening;
 - a mixing zone for the gas and the liquid defined adjacent the exterior of the apertured bottom end of the shaft, the interior of the tube and a central portion of the impeller, surrounding the shaft;
 - an outlet for gas near the bottom end of the shaft within the mixing zone defined by said apertures formed through said shaft bottom end;
 - the impeller drawing liquid through the tube, through the opening past the gas outlet, for mixing the liquid with the gas in the mixing zone, and expelling the liquid outwardly from the vane elements as the impeller rotates.

4,297,215

BELT FILTER PRESS

Hans J. Altmeyer, and Josef Gebel, both of Schwalbach, Fed. Rep. of Germany, assignors to Hein, Lehmann AG, Dusseldorf, Fed. Rep. of Germany

Filed Mar. 31, 1980, Ser. No. 135,839

Claims priority, application Fed. Rep. of Germany, Mar. 26, 1979, 2911760


Int. Cl.³ B01D 33/02

U.S. Cl. 210—386

16 Claims

1. In a belt filter press of the type having a lower and an upper endless filter belt and a lower and an upper support belt which respectively support said lower and upper filter belts against an upper and a lower row of rollers for transport along a press path, which rows of rollers define a press slot therebetween, the improvement comprising:
 - means for laterally sealing said press slot including two additional rows of rollers, each additional row of rollers being disposed laterally adjacent to, and on opposite sides

of, one of said upper and lower rows of rollers for cooperative engagement with the support belt and filter belt associated with said one of said rows, said additional rows of rollers being disposed at an angle with respect to said one of said rows so that it bends and presses an edge



portion of said belts associated therewith against the associated edge portion of the other belts associated with the other of said upper and lower rows of rollers, so as to thereby prevent a lateral discharge between the edges of said belts of material fed along said press slot.

4,297,216

METHOD FOR TREATMENT OF BIOCHEMICAL WASTE


Masahiko Ishida; Ryooichi Haga, and Youji Odawara, all of Hitachi, Japan, assignors to Hitachi, Ltd., Tokyo, Japan
Continuation of Ser. No. 651,586, Jan. 22, 1976, abandoned. This application Jan. 5, 1978, Ser. No. 867,361

Claims priority, application Japan, Jan. 22, 1975, 50/8729
The portion of the term of this patent subsequent to Jan. 10, 1997, has been disclaimed.

Int. Cl.³ C02F 11/04

U.S. Cl. 210—613

8 Claims



1. A method for the treatment of a biochemical waste slurry, with the biochemical waste selected from the group of sewage sludge and garbage, comprising the steps of:
providing a slurry of the biochemical waste with a solid density greater than 3% by weight;
adding acid to the slurry to adjust its pH to a value below 3.5;
heating the slurry having its pH below 3.5 within a temperature range of 60° to 200° C. for a period of 1 to 10 minutes to reduce the viscosity of the slurry;
thereafter substantially neutralizing the acidity of the slurry to a pH of 5 to 8;
anaerobically digesting the substantially neutralized slurry at a temperature within the range of 20° to 50° C. for 20 to 40 days with mechanical agitation through the action of methane producing bacteria to convert the slurry to methane and a digested sludge; and
separating the methane from the digested sludge.

4,297,217

TREATMENT OF WASTEWATER

David A. Hines, Bishopton, and David H. Bolton, Linthorpe, both of England, assignors to Imperial Chemical Industries Limited, London, England


Filed May 12, 1980, Ser. No. 149,622

Claims priority, application United Kingdom, May 23, 1979, 17971/79

Int. Cl.³ C02F 3/22

U.S. Cl. 210—621

7 Claims



1. A method for treating wastewater utilizing a downcomer-riser system, the downcomer and riser communicating directly only at their lower ends and indirectly, through a pump means, only at their upper ends, with the level of wastewater in the downcomer being maintained above the level of wastewater in the riser to provide a hydrostatic pressure head which causes circulation of the wastewater around the system at a pre-selected rate, the level of wastewater in the downcomer fluctuating between a maximum and minimum level for which self-rectification of the flow rate will occur, said method comprising the steps of:

supplying a gas containing free oxygen to the wastewater in the downcomer as it circulates down the downcomer; effecting disengagement of gas bubbles from the wastewater prior to recirculation from the riser to the downcomer; pumping the wastewater from an upper portion of the riser back into the downcomer so that the wastewater is discharged into the downcomer at an area above said level of wastewater, and varying the position at which the wastewater is discharged into said downcomer in response to said level of wastewater.

4. Apparatus for treating wastewater, comprising:

a downcomer;
a riser communicating directly with said downcomer only at the bottom ends of said riser and downcomer, and communicating indirectly only at the upper ends thereof;
a level of wastewater being maintained in said downcomer above the uppermost part of said riser so that a hydrostatic head is provided effecting circulation of wastewater down said downcomer and up said riser, at a pre-selected rate, and the level of wastewater in said downcomer fluctuating between maximum and minimum levels for which self-rectification of the flow rate around the system will occur;
oxygen-containing gas introducing means disposed in said downcomer for introducing oxygen-containing gas into the wastewater circulating down said downcomer;
pumping means for pumping wastewater from an upper portion of said riser back into said downcomer so that the wastewater is discharged into the downcomer at an area above said level of wastewater, and means for varying the position at which the wastewater is discharged into said downcomer in response to said level of wastewater.

4,297,218

PROCESS AND APPARATUS FOR EXTRACTING A SUBSTANCE FROM A BODY OF WATER

Hans G. Bals, Blümgesgrund 44, 6460 Gelnhausen, Fed. Rep. of Germany


Continuation-in-part of Ser. No. 882,447, Mar. 1, 1978, which is a continuation of Ser. No. 741,130, Nov. 11, 1976, abandoned. This application Sep. 26, 1979, Ser. No. 79,059

Claims priority, application Fed. Rep. of Germany, Sep. 27, 1978, 2842058

Int. Cl.³ C02F 1/28

U.S. Cl. 210—661

22 Claims



2. In a process for obtaining a dissolved, suspended or chemically bonded substance from a body of water, wherein water is taken from a substantially horizontal relative flow of said body of water and directed substantially into a vertical direction and through a fluidized bed of adsorber particles to bond said substance for extraction thereof from the water, the improvement that said water which is to be passed through the fluidized bed is passed through a diffuser means at least before being deflected into the vertical direction, thereby to increase the static pressure of said water wherein at least a low-energy boundary layer of said water, which is produced by surface friction before said flow of water reaches said diffuser means, is prevented from passing into the diffuser means by being directed therefrom by a diversion passage.

4,297,219

TEMPORARY STREAM FILTRATION SYSTEM


Joseph R. Kirk, Findlay, and Edward C. Campbell, Forest, both of Ohio, assignors to The KBI Corp., Findlay, Ohio

Filed Jan. 28, 1980, Ser. No. 115,991

Int. Cl.³ B01D 35/02

U.S. Cl. 210—669

19 Claims



1. A temporary method of purifying a contaminated and polluted water stream comprising:

- (A) inserting a temporary ramp weir in the stream,
- (B) forming an earth dam across said stream on each side of said ramp weir to form a dam so that all the water in said stream is caused to flow down over the weir edge of said ramp to form a falling path,
- (C) positioning replaceable frames of sorbent filter material in said falling path of water from said weir whereby said ramp catches the sediment in said stream at its lower end and said filter material removes chemical contaminants and pollutants from said stream that flows over said weir edge, and
- (D) removing said frame and said ramp weir from the stream after the stream water is purified.

4,297,220

MACRORETICULATED COPOLYMER ADSORPTION PROCESS


Erich F. Meitzner, Glenside, and James A. Oline, Wyncote, both of Pa., assignors to Rohm and Haas Company, Philadelphia, Pa.

Division of Ser. No. 749,526, Jul. 18, 1958, Pat. No. 4,224,415. This application May 23, 1980, Ser. No. 152,941

Int. Cl.³ C02F 1/28

U.S. Cl. 210—690

3 Claims



1. Method for adsorbing an organic material from a fluid or fluid mixture containing the same which comprises contacting the fluid or fluid mixture containing organic material with a macroreticulated crosslinked copolymer having a plurality of microscopic channels resulting from liquid expulsion of a precipitating agent during polymerization of a monomer mixture under suspension polymerization conditions in an aqueous media of (1) a polyvinylidene monomer containing a plurality of ethylenically unsaturated groups in a non-conjugated relationship and (2) at least one monoethylenically unsaturated monomer, said copolymerization taking place in the presence of a liquid which is a solvent for the monomer mixture and which does not swell the copolymer resulting from said copolymerization, said liquid being present in an amount sufficient to cause separation of the copolymer from the monomer phase, whereby the organic material is adsorbed by the macroreticulated crosslinked copolymer.

4,297,221

PROCESS AND APPARATUS FOR THE TREATMENT OF UNTREATED WATER

Hans-Georg Moll, Görzallee 49a, 1000 Berlin 45; Ulrich Hässelbarth, Adolfstrasse 3, 1000 Berlin 37; Andreas Grohmann, Drakestrasse 52a, 1000 Berlin 45, and Helmut Marks, Maulbeerallee 34, 1000 Berlin 20, all of Fed. Rep. of Germany

Filed Sep. 12, 1979, Ser. No. 74,665


Int. Cl.³ B01D 21/01, 21/02

U.S. Cl. 210—702

6 Claims

1. An apparatus for the treatment of untreated water containing substances causing turbidity in a cylindrical tank by sedimentation using a flocculating agent added to the water causing said substance in the water to form into flakes, in which the water flows through the tank and after an adequate residence time is removed from the water surface of the tank at a rising speed which is less than the sinking speed of the flakes, said apparatus comprising:
a cylindrical tank;
one feed connection in the tank directed tangentially at the lower portion of the circumferential wall of the tank;

- a cylindrical partition disposed in the tank, the circumferential wall of the partition forming an annular clearance with the circumferential wall of the tank;
- a bottom wall of the tank and a lower end of the partition spaced apart placing the lower end of the annular clearance in free communication with the center of the tank;
- the partition having perforations distributed over the circumference thereof such that the water mixed with the flocculating agent is introduced tangentially into the circumferential area of the tank and the circumferential speed of the inflowing water is reduced to such an extent by braking as it passes radially through the partition that the occurrence of upwardly directed secondary flows is prevented; and
- a pipe disposed in the tank including an inlet near the top of said tank, the pipe passing axially through the tank bottom and carrying a circular overflow disc at its upper end disposed at substantially the same level as the upper end of said partition of the tank such that clean water is led off downwards through the center of the tank.
6. A process for the treatment of water containing substances causing turbidity in a cylindrical tank comprising the steps of:



- (1) adding flocculent to the water in order to form said substances causing turbidity into flakes;
- (2) passing the flocculent containing water tangentially into the lower periphery of the tank into an annular clearance formed by a perforated cylindrical partition and the circumferential wall of the tank, the lower end of said partition being spaced apart from the bottom wall of said tank placing the lower end of said annular clearance in free communication with the center of the tank;
- (3) directing the water radially inward through said perforated cylindrical partition to reduce the circumferential speed of the inflowing water sufficiently to prevent the occurrence of upwardly directed secondary flows;
- (4) maintaining the flocculent containing water in the tank for an adequate time for said flakes to form;
- (5) allowing said flakes to be deposited at the bottom of said tank;
- (6) drawing clean water through a centrally disposed overflow in said tank beneath the water surface in the tank, said overflow being at substantially the same level as the upper end of said partition.

4,297,222

METHOD OF PURIFYING WATER IN FISH KEEPING WATER TANK

Masanobu Takeguchi, and Isao Oyobe, both of Fujisawa, Japan, assignors to Marui Industry Co., Ltd., Tokyo, Japan
Filed Apr. 4, 1980, Ser. No. 137,269
Claims priority, application Japan, Apr. 10, 1979, 54-42474
Int. Cl.³ C02B 1/38


U.S. Cl. 210—748

5 Claims

1. A method of purifying water in a fish keeping water tank comprising:
- (A) circulating water at a rate such that at least half the volume of water in the tank is circulated per hour;
- (B) passing the water through a UV irradiation vessel providing UV radiation having a predominant wavelength of

less than 280 nm, wherein the water is exposed to at least $170 \mu\text{W}\cdot\text{min}/\text{cm}^2$ of UV radiation at one pass through said vessel, or a given volume of water is exposed to a total of at least $1000 \mu\text{W}\cdot\text{min}/\text{cm}^2$ of UV radiation during a one-hour circulation of the water;

- (C) introducing the water into a first purifying tank having an inlet and an outlet and which includes a support cylinder wrapped with a first microorganism-growing bed of free-permeable nonwoven fabric made of synthetic resin and having a predetermined mesh size no smaller than 100μ , passing all of said water through said growing bed,



to thereby bring the introduced water into contact with microorganisms and to separate some of said microorganisms from said growing bed, introducing said water into a space in said first purifying tank downstream from said first microorganism growing bed, where microorganisms separated from said first growing bed are suspended and grow, to thereby bring the water into contact with such microorganisms in said space; and

introducing the water into at least one second purifying tank located downstream from said first purifying tank, each said second purifying tank having a free-permeable synthetic resin microorganism-growing bed.

4,297,223

METHOD AND APPARATUS FOR FORMING A CHLORINE-WATER SOLUTION AND FOR UTILIZING THE SAME TO DISINFECT WATER LINES AND THE LIKE


Morrison Rivenbark, Kinston, N.C., assignor to Douglas R. Smith, Kinston, N.C.

Filed Jul. 28, 1980, Ser. No. 172,679

Int. Cl.³ C02B 3/06

U.S. Cl. 210—754

9 Claims



1. A chlorinator design for such use as sterilizing water lines and the like comprising: a chlorine tank having chlorine therein and adapted to receive water therein and to form a concentrated chlorine water solution; mixing tank means for receiving both water and the concentrated chlorine-water solution from said chlorine tank and mixing the two together to form a mixed chlorine solution; line means communicatively

connected between said chlorine tank and said mixing tank for transferring the concentrated chlorine-water solution from said chlorine tank to said mixing tank; inlet water line means operatively connected to both said chlorine tank and said mixing tank for simultaneously directing water to both said chlorine tank and said mixing tank wherein the circulation of water through said chlorine tank forms the concentrated chlorine-water solution and wherein the water directed to said mixing tank acts to combine with said concentrated chlorine-water solution to form a final mixed chlorine solution; valve means operatively associated with said chlorine tank for adjusting the flow of water directed through said chlorine tank from said inlet water line means; and outlet line means communicatively connected to said mixing tank and extending therefrom for directing the mixed chlorine solution from said mixing tank, whereby the formed chlorine solution can be directed through water lines or the like for sterilizing the same.

4,297,224

METHOD FOR THE CONTROL OF BIOFOULING IN RECIRCULATING WATER SYSTEMS

Nick T. Macchiarolo; Billy G. McGuire, and John M. Scalise, all of El Dorado, Ark., assignors to Great Lakes Chemical Corporation, West Lafayette, Ind.

Filed Jun. 4, 1980, Ser. No. 156,508

Int. Cl.³ C02F 1/76, 1/50

U.S. Cl. 210—755

6 Claims

1. A method of controlling biofouling in recirculating water systems for heat exchange systems without disinfecting the bulk recirculating water comprising the steps of:
- introducing a biocidally effective amount of 1-bromo-3-chloro-5,5-dimethylhydantoin into the water in order to kill biofouling microorganisms at film-forming surfaces of the system; and
- thereafter maintaining the concentration of 1-bromo-3-chloro-5,5-dimethylhydantoin at a level effective to inhibit regrowth of such microorganisms at such surfaces without maintaining a continuous measurable halogen residual in the recirculating water and without disinfecting the bulk recirculating water.

4,297,225

RECYCLING CENTRIFUGE FOR THE REDUCTION OF VISCOSITY AND GEL STRENGTH OF DRILLING FLUIDS


Bobby G. Hartley, 1011 Iberville St., Donaldsonville, La. 70346

Continuation-in-part of Ser. No. 838,388, Sep. 30, 1977, abandoned, which is a continuation-in-part of Ser. No. 755,973, Dec. 30, 1976, abandoned, which is a continuation-in-part of Ser. No. 622,078, Oct. 14, 1975, abandoned. This application Aug. 10, 1978, Ser. No. 932,536

Int. Cl.³ B04B 5/00

U.S. Cl. 210—779

8 Claims



1. A process for reducing the viscosity and gel strength of a hydratable clay containing drilling mud which comprises contacting said mud with the inner surface of a revolving cone, the total included angle of the cone ranging from about 40° to

about 120° , the cone revolving at a speed ranging from about 400 to about 6000 revolutions per minute, sufficient to impart adequate compression force to dewater the hydrated clay constituent and thereby reduce the viscosity and gel strength of said mud.

4,297,226

PROCESS FOR SECONDARY RECOVERY

Walter D. Hunter, Houston, Tex., assignor to Texaco Development Corp., White Plains, N.Y.

Continuation-in-part of Ser. No. 917,056, Jun. 19, 1978, abandoned. This application Feb. 19, 1980, Ser. No. 122,141
Int. Cl.³ E21B 43/22

U.S. Cl. 252—8.55 D

17 Claims

1. A process for recovering hydrocarbons from a subterranean hydrocarbon-bearing formation penetrated by an injection well and a production well which comprises:
- (A) injecting into the formation via an injection well a drive fluid comprising water having dissolved therein about 0.01 to about 5.0 weight percent of an N-substituted polyacrylamide bearing N-substituents of the formula:



wherein m is an integer of from 1 to 5 and M is selected from the group consisting of hydrogen, sodium, potassium and ammonium,

- (B) forcing the said fluid through the formation, and
- (C) recovering hydrocarbons through the production well, and wherein the number average molecular weight of the said N-substituted polyacrylamide is about 10,000 to about 2,000,000.

4,297,227

METHOD FOR CONTINUOUS GREASE MANUFACTURE

Arnold C. Witte, Port Neches, and Richard L. Coleman, Port Arthur, both of Tex., assignors to Texaco Inc., White Plains, N.Y.

Continuation-in-part of Ser. No. 16,597, Mar. 2, 1979, abandoned. This application Jan. 18, 1980, Ser. No. 113,162

Int. Cl.³ C10M 5/16, 5/14, 5/02, 7/22

U.S. Cl. 252—18

8 Claims

1. In a continuous grease manufacturing process wherein a saponifiable material is reacted with an aqueous solution of a metal base in a saponification zone at saponification conditions of elevated temperature and superatmospheric pressure to produce a soap containing saponification reaction product, wherein said saponification reaction product is passed through a pressure reducing means to effect pressure reduction and to flash vaporize substantially all the water present in said saponification reaction product and the said flashed vaporized water as well as any remaining water is removed from said saponification reaction product by flash vaporization in a dehydration zone to produce a dehydrated saponification product, and wherein said dehydrated saponification product in said dehydration zone is recycled through a shear valve for conditioning said soap contained therein, and wherein lubricating oil is added to said recycled dehydrated saponification product for producing a grease product; the improvement which comprises:

- (a) admixing an aqueous solution of at least one water soluble additive compound, which improves properties of said grease product, with said saponification reaction product under conditions of superatmospheric pressure sufficient to maintain water present in the liquid phase and at an elevated temperature sufficiently high for flash vaporizing substantially all water present in the resulting admixture upon subsequent substantial pressure reduction, thereby forming a hot combined mixture of saponification reaction product and aqueous additive solution; and
- (b) passing said formed hot combined mixture through a

pressure reducing means that is maintained at a pressure not greater than about atmospheric and sufficient for flash vaporizing substantially all water present in said hot formed mixture and passing the resulting substantially dehydrated mixture and vaporized water into said dehydration zone to flash vaporize any remaining water in said mixture and for producing additive particles of a size not greater than about 10 microns distributed within said dehydrated mixture.

4,297,228

DECORATED SOAP AND METHOD FOR PRODUCING THE SAME

Masataka Kamada, 94-4071banchi, Haishima-cho, Akishima-city, Tokyo, and Seiji Satoh, 6-140banchi, Segasaki, Urawa-city, Saitama-district, both of Japan


Filed Jul. 14, 1980, Ser. No. 168,674

Claims priority, application Japan, Apr. 19, 1980, 55-51119

Int. Cl.³ B44C 1/16; C11D 17/00, 17/04

U.S. Cl. 252-92

4 Claims



1. Decorated soap which comprises, in combination, a cake of soap, a synthetic resin layer formed on one side surface of said soap, said synthetic resin layer being formed by applying a composition of 30% acrylic resin, 15% nitrocellulose and 55% solvents, a release layer having a printed layer representing a pattern consisting of designs and/or characters, said release layer being formed by applying a composition of 15 to 25% cellulose ester plus plasticizer and 75 to 85% solvents, and an adhesive layer which joins said synthetic resin layer with said release layer, said adhesive layer being formed by applying a composition of 23 to 50% adhesive base materials and 50 to 77% solvents.

3. A method for producing decorated soap which comprises the steps of:

- forming a synthetic resin layer on one side surface of soap to be treated by applying a composition of 30% acrylic resin, 15% nitrocellulose and 55% solvents;
- forming a release layer on a backing film by applying a composition of 15 to 25% cellulose ester plus plasticizer and 75 to 85% solvents, reversely printing a desired pattern on said release layer, and forming an adhesive layer on said printed release layer by applying a composition of 23 to 50% adhesive base materials and 50 to 77% solvents, thereby forming a transfer sheet;
- bringing said adhesive layer of transfer sheet into contact with said synthetic resin layer on said soap by moving said transfer sheet in front of a rotary rubber roller which is heated at a temperature between about 180° C. and about 250° C., with said synthetic resin layer on said soap being opposed to said adhesive layer of said transfer sheet, and then pressing said soap together with said transfer sheet to said rotary rubber roller under a pressure between about 200 g/cm² and 1000 g/cm²; and
- peeling only said backing film of transfer sheet from said joined product.

4,297,229

PARTICULATE BORATE-SOAP COMPOSITIONS

Richard C. Speak, and Donald J. Fern, both of Fullerton, Calif., assignors to United States Borax & Chemical Corporation, Los Angeles, Calif.

Filed Oct. 23, 1979, Ser. No. 87,377

Int. Cl.³ C11D 9/16, 11/00, 17/06

U.S. Cl. 252-109

20 Claims

1. The method of producing a particulate borate soap composition comprising heating C₈-C₁₈ fatty acid at a temperature of from about 40° to 100° C. at which temperature said fatty acid is a liquid and intimately mixing said liquid fatty acid with a mixture of finely divided alkali metal carbonate and hydrated sodium tetraborate to form the alkali metal salt of said fatty acid and thereby produce a particulate hydrated sodium tetraborate-soap-alkali metal bicarbonate composition containing about 25 to 50% as anhydrous sodium tetraborate, wherein the mole ratio of said fatty acid to alkali metal carbonate is in the range of from 1:1 to about 1:2, said finely divided alkali metal carbonate is substantially of a particle size smaller than 100 mesh, and the soap content of the resultant particulate product is in the range of about 5 to 35% by weight.

4,297,230

NON-CRYSTALLIZING TRANSPARENT SOAP BARS

Jacobus C. Rasser, Grimbergen, Belgium, assignor to The Procter & Gamble Company, Cincinnati, Ohio

Filed Jan. 31, 1980, Ser. No. 117,320

Claims priority, application United Kingdom, Feb. 6, 1979, 04197/79; Nov. 1, 1979, 37809/79

Int. Cl.³ C11D 9/30, 3/10

U.S. Cl. 252-117

10 Claims

1. A transparent soap bar, consisting essentially of from about 4% to about 20% potassium soap, the balance of the soap component of said soap bar comprising sodium, ammonium or alkanolamine soap, at least about 0.2% chloride anions, from about 4% to about 25% moisture and from about 0.2% to about 5% of an electrolyte selected from the group consisting of potassium carbonate, sodium formate, potassium formate, sodium tartrate, potassium tartrate, sodium citrate, potassium citrate, sodium acetate, potassium acetate, potassium ammonium tartrate, ammonium acetate, ammonium carbonate, ammonium formate, ammonium citrate, ammonium lactate, ammonium bisulfate, and mixtures thereof.

4,297,231

PROCESS FOR PRODUCING A POSITIVE ELECTRODE FOR A NON-AQUEOUS ELECTROLYTIC CELL

Toshiki Kahara; Kohki Tamura; Noboru Ebata; Fumio Sato, and Tomio Yoshida, all of Ibaraki, Japan, assignors to Hitachi, Ltd. and Hitachi Chemical Co., Ltd., both of Tokyo, Japan

Filed Dec. 28, 1979, Ser. No. 107,926

Claims priority, application Japan, Jan. 6, 1979, 54-865

Int. Cl.³ H01M 4/50, 4/04

U.S. Cl. 252-182.1

9 Claims

1. A process for producing a positive electrode for a non-aqueous electrolytic cell comprising the steps of:

- heat-treating manganese dioxide;
- adding the thus heat-treated manganese dioxide with a conducting agent and a binder to be mixed together;
- heat-treating the resultant mixture; and
- molding the thus heat-treated mixture to form a positive electrode.

4,297,232

GLYCOL-IODINE COMPOSITION AND METHOD OF PREPARATION


Samuel Ruben, 271 North Ave., New Rochelle, N.Y. 10801

Continuation-in-part of Ser. No. 868,769, Jan. 12, 1978, abandoned, which is a continuation of Ser. No. 714,760, Aug. 16, 1976, abandoned. This application Jan. 25, 1979, Ser. No. 6,946

Int. Cl.³ A61K 33/18; A01N 59/12

U.S. Cl. 252-187 R

29 Claims



1. A composition consisting essentially of a glycol component selected from the group consisting of ethylene glycol, the polymers thereof and mixtures thereof, and iodine, said iodine present in an amount up to the saturation point of said iodine in said glycol component,

said composition characterized by the absence of a spectroscopically identifiable complex between said glycol component and said iodine, and the absence of free iodine therein.

4,297,233

DEODORIZING COMPOSITION FOR ASH TRAYS

Paolo Gualandi, 16/A, Via Rosario, Bologna, Italy

Filed May 14, 1979, Ser. No. 38,751

Claims priority, application Italy, Jun. 27, 1978, 12684 A/78

Int. Cl.³ C09K 3/00; A61K 7/46; C11B 9/00

U.S. Cl. 252-259.5

8 Claims

1. A deodorizing composition comprising, in combination;
- (a) A solid absorbent granular material, of a grain size in the range of 20 to 65 mesh per cm², composed in weight % of: SiO₂: from 90 to 95%, Al₂O₃: from 4 to 7%, Fe₂O₃: from 1 to 2%, CaO: from 0 to 0.5%, MgO: from 0 to 0.5%, the remainder comprising water and traces of alkalies or other metallic oxides;
 - (b) An oily essence absorbed in said absorbent material, the ratio of oily essence to absorbent material being, in parts by weight, in the range of 1:1.5 to 1:1; and
 - (c) A vapor diffusion fixation agent selected from the class consisting of silicone oils, higher alcohols, plastifiers, and mixtures thereof.

4,297,234

BENZOXAZOLYL-STILBENES

Kurt Burdeska, Basel, and Guglielmo Kabas, Aesch, both of Switzerland, assignors to Ciba-Geigy Corporation, Ardsley, N.Y.

Filed May 5, 1980, Ser. No. 146,960


Claims priority, application Switzerland, May 17, 1979, 4596/79

Int. Cl.³ C07D 413/10, 413/14


U.S. Cl. 252-301.24

14 Claims

1. A benzoxazolyl-stilbene of the formula



in which R is one of the ring systems of the formulae



in which R₃ is hydrogen, alkyl having 1 to 4 C atoms, unsubstituted phenyl or phenyl substituted by chlorine or methyl, R₄ and R₅ independently of one another are hydrogen, alkyl having 1 to 4 C atoms, unsubstituted phenyl or phenyl substituted by chlorine or methyl, alkoxy having 1 to 4 C atoms, alkoxyalkoxy having a total of 3 to 8 C atoms, unsubstituted phenoxy or phenoxy substituted by chlorine or methyl, chlorine, alkylthio having 1 to 4 C atoms, phenylthio, alkylamino having 1 to 4 C atoms, dialkylamino having a total of 2 to 8 C atoms, morpholino, piperidino, piperazino, pyrrolidino or anilino, R₆ is alkyl having 1 to 4 C atoms, unsubstituted phenyl or phenyl substituted by chlorine or methyl and R₇ is alkoxy having 1 to 4 C atoms, alkoxyalkoxy having a total of 2 to 8 C atoms, alkylthio having 1 to 4 C atoms, unsubstituted phenoxy or phenoxy substituted by chlorine or methyl, cycloalkyloxy, alkylthio having 1 to 4 C atoms, unsubstituted phenylthio or phenylthio substituted by chlorine or methyl, alkylamino having 1 to 4 C atoms, dialkylamino having a total of 2 to 8 C atoms, morpholino, piperidino, piperazino, pyrrolidino or anilino, one of Z and Z₀ is hydrogen and the other is hydrogen or chlorine and the benzene nucleus A is unsubstituted or substituted by non-chromophoric substituents selected from alkyl, halogenalkyl, cyanoalkyl, hydroxyalkyl, alkoxyalkyl, phenoxyalkyl, carboxyalkyl, salts, esters and amides of carboxylalkyl, aralkyl, cycloalkyl, alkenyl, alkoxy, hydroxyalkoxy, alkoxyalkoxy, aralkoxy, phenoxyalkoxy, cyanoalkoxy, alkenyloxy, carboxy, sulfo, carboxylic and sulfonic acid salts, esters and amides, alkylsulfonyl, phenylsulfonyl, aryl, aryloxy and two adjacent radicals forming together the remaining members of an aromatic carbocyclic ring system.

4,297,235

METHOD OF PREPARING A MICROCAPSULE DISPERSION

Yoshiyuki Hoshi, Takayuki Hayashi, and Fujio Kakimi, all of Fujinomiya, Japan, assignors to Fuji Photo Film Co., Ltd., Minami-ashigara, Japan

Filed Nov. 5, 1979, Ser. No. 91,309

Claims priority, application Japan, Nov. 7, 1978, 53-136964
Int. Cl.³ B01J 13/02

U.S. Cl. 252—316

9 Claims

1. In a method of preparing a dispersion of microcapsules whose walls comprise formaldehyde as one of the wall components, the improvement which comprises

preparing a dispersion containing microcapsules with microcapsule walls of an amino-formaldehyde condensation resin,

adding urea to the capsule dispersion in the range from about 1/10 to 5 times greater on a molar basis than the formaldehyde contained in the dispersion,

heating the capsule dispersion with stirring, and adding a solution of sulfite, hydrogensulfite or a mixture thereof to the capsule dispersion in the range from about 0.02 to 1 mol per mol of formaldehyde.

4,297,236

WATER MISCIBLE CORROSION INHIBITORS

Helmut Diery, Kerkheim; Rainer Helwerth, Eschborn; Horst Fröhlich, Eppstein, and Horst Lorke, Liederbach, all of Fed. Rep. of Germany, assignors to Hoechst Aktiengesellschaft, Fed. Rep. of Germany

Filed Sep. 14, 1978, Ser. No. 942,337


Claims priority, application Switzerland, Sep. 19, 1977, 11419/77

Int. Cl.³ C23F 11/14, 11/16, 11/18

U.S. Cl. 252—389 R

3 Claims

1. Corrosion inhibitors consisting essentially of a mixture of (A) reaction products of boric acid and diethanolamine, and (B) arylsulfonamidocarboxylic acids of the formula I



in which

R₁ and R₂ each represent hydrogen, fluorine, chlorine, bromine, an alkyl or alkoxy radical having from 1 to 4 carbon atoms, with the proviso that the sum of the carbon atoms of R₁ and R₂ does not exceed 7;

Ar is a benzene, naphthalene or anthracene radical;

R₃ is hydrogen, an aryl radical having up to 4 carbon atoms, a β-cyanoethyl or hydroxyalkyl radical having from 2 to 4 carbon atoms;

R₄ is an alkylene radical having more than 3 carbon atoms, optionally substituted by one or more methyl or ethyl radicals; and

n is 1 or 2; or

alkyl- and/or cycloalkylsulfonamidocarboxylic acids obtained by sulfochlorination of a saturated aliphatic and/or cycloaliphatic hydrocarbon having from 12 to 22 carbon atoms and a boiling temperature range of from about 200° to 350° C., subsequent reaction with ammonia and final condensation with chloroacetic acid.

4,297,237

POLYPHOSPHATE AND POLYMALEIC ANHYDRIDE COMBINATION FOR TREATING CORROSION

Bennett P. Boffardi, Bethel Park, Pa., assignor to Calgon Corporation, Pittsburgh, Pa.

Filed Mar. 6, 1980, Ser. No. 127,675

Int. Cl.³ C23F 11/18, 11/14, 11/16

U.S. Cl. 252—389 A


11 Claims

1. A method of inhibiting corrosion in an aqueous system comprising the step of treating said system with from 1.0 to 300 parts per million by weight of the total aqueous content of said system, of a corrosion inhibiting composition comprising


(1) polyphosphate; and

(2) one or more polymers selected from the group consisting of polymaleic anhydride and amine adducts of polymaleic anhydride selected from the group consisting of:

(a) polymers having recurring units of the formula:




wherein M⁺ may be H⁺, alkali metal cation, or quaternary ammonium cation of the formula:



wherein for all of the above formulas, R₁, R₂, R₃, R₄, R₅, and R₆ are each independently selected from the group consisting of hydrogen, alkyl of from one to ten carbon atoms, and substituted alkyl of from one to ten carbon atoms, where the substituent is hydroxyl; carbonyl; and carboxylic acid groups, and alkali metal ion and ammonium salts thereof; and

wherein n is an integer of from 2 to 100; and

(b) polymers having recurring units of the formula:



wherein R₁, R₂, R₃, R₄, R₅, and R₆ are each independently selected from the group consisting of hydrogen, alkyl of from one to ten carbon atoms, and substituted alkyl of from one to ten carbon atoms, where the substituent is hydroxyl; carbonyl; and carboxylic acid groups, and alkali metal ion and ammonium salts thereof;

wherein p is an integer of from 1 to 6;

wherein m is an integer of from 2 to 100; and

wherein n is an integer of from 2 to about 100, provided that, n not equal to m, the lesser of m or n is multiplied by a factor such that n=m;

wherein the polymaleic anhydride and amine adducts of polymaleic anhydride have a weight average molecular weight of from about 200 to about 10,000; and wherein the weight ratio of polyphosphate to polymer is from 10:1 to 1:10.

4,297,238

HEMOLYSING SOLUTION PREPARING HEMOLYSED BLOOD HAVING A STABILIZED GLUCOSE CONTENT

Rolf Vormbrock, and Roland Helger, both of Darmstadt, Fed. Rep. of Germany, assignors to Merck Patent Gesellschaft mit beschränkter Haftung, Darmstadt, Fed. Rep. of Germany

Filed Nov. 21, 1979, Ser. No. 96,347

Claims priority, application Fed. Rep. of Germany, Nov. 22, 1978, 2850603

Int. Cl.³ G01N 33/48; C09K 3/00

U.S. Cl. 252—408

7 Claims

1. In a hemolysing solution used in the determination of glucose in a whole blood sample, consisting essentially of a lysing reagent and a glycolysis inhibitor which inhibits glycolysis in the hemolysate obtained by contacting the blood sample with the hemolysing solution, the improvement wherein the hemolysing solution consists essentially of

(a) a buffer providing a pH of about 6–8;

(b) 0.8–3.0 moles/liter of sodium chloride;

(c) 1–4 g/l of a surface active agent;

(d) 0.5–2 g/l of a chelating agent which in the presence of component (c) serves as a stabilizer against glycolysis in the hemolysate; and, optionally,

(e) an effective amount of an antimicrobial agent.

4,297,239

HYDROFORMYLATION CATALYST REACTIVATION

David R. Bryant, and Richard A. Galley, both of South Charleston, W. Va., assignors to Union Carbide Corporation, New York, N.Y.

Continuation-in-part of Ser. No. 58,123, Jul. 16, 1979, abandoned. This application Feb. 28, 1980, Ser. No. 120,101

Int. Cl.³ B01J 31/40, 31/24; C07C 45/50; B01J 31/20

U.S. Cl. 252—412

54 Claims

1. A process for preparing a hydroformylation medium, said medium comprising a rhodium complex and triarylphosphine, which comprises mixing a rhodium complex concentrate with a sufficient amount of triarylphosphine so that there is at least about 10 moles of free triarylphosphine per mole of rhodium present in said medium; said rhodium complex concentrate having been produced by a process which comprises concentrating a spent hydroformylation reaction medium that contains a partially deactivated rhodium complex catalyst, free triarylphosphine, aldehyde products and higher boiling aldehyde condensation by-products, into at least two separate material streams so as to remove free triarylphosphine, aldehyde products and higher boiling aldehyde condensation by-products from said spent hydroformylation reaction medium by means of distillation at temperatures of about 20° C. to about 350° C. and at pressures of about 1000 mm Hg. to about 1 × 10⁻⁶ mm Hg., wherein one stream is said rhodium complex concentrate distillation residue containing a major amount of the rhodium of said catalyst and which has been concentrated to about 0.1 to about 30 percent by weight of said spent hydroformylation reaction medium, and the other material stream or streams consist essentially of one or more of the distilled volatile components of said spent hydroformylation reaction medium.

28. A hydroformylation medium comprising a rhodium complex and at least about 10 moles of free triarylphosphine per mole of rhodium present in said medium, said rhodium complex having been derived from a rhodium complex concentrate which has been produced by a process which comprises concentrating a spent hydroformylation reaction medium that contains a partially deactivated rhodium complex catalyst, free triarylphosphine, aldehyde products and higher boiling aldehyde condensation by-products, into at least two separate material streams so as to remove free triarylphosphine, aldehyde products and higher boiling aldehyde condensation by-products from said spent hydroformylation reaction medium by means of distillation at temperatures of about 20° C. to about 350° C. and at pressures of about 1000 mm Hg. to about 1 × 10⁻⁶ mm Hg., wherein one stream is said rhodium complex concentrate distillation residue containing a major

amount of the rhodium of said catalyst and which has been concentrated to about 0.1 to about 30 percent by weight of said spent hydroformylation reaction medium, and the other material stream or streams consist essentially of one or more of the distilled volatile components of said spent hydroformylation reaction medium.

31. A hydroformylation medium as defined in claim 28, wherein the distillation takes place in two stages and wherein the second distillation stage is distilled at a lower pressure than the first distillation stage.

4,297,240

SOLUTION POLYMERIZATION

Robert E. Bingham, Cuyahoga Falls; Richard R. Durst, Stow; Hubert J. Fabris, Akron; Ivan G. Hargis, Tallmadge; Russell A. Livigni, and Sundar L. Aggarwal, both of Akron, all of Ohio, assignors to The General Tire & Rubber Company, Akron, Ohio

Division of Ser. No. 124,373, Feb. 25, 1980. This application Aug. 15, 1980, Ser. No. 178,248

Int. Cl.³ C08F 4/10

U.S. Cl. 252—431 R

8 Claims

1. A composition of matter useful as an anionic polymerization catalyst comprising (1) an alcoholate selected from the group consisting of barium alcoholate, calcium alcoholate and strontium alcoholate and mixtures thereof, (2) an organoaluminum compound selected from the group consisting of alkyl and cycloalkyl aluminum compounds and mixtures of the same and (3) an organomagnesium compound selected from the group consisting of alkyl and cycloalkyl magnesium compounds and mixtures of the same, where the mol ratio computed as metal of barium, calcium and/or strontium to magnesium is from about 1:10 to 1:2 and where the mol ratio computed as metal of magnesium to aluminum is from about 105:1 to 1.5:1.

4,297,241

METHOD OF PREPARING AN OLEFIN HYDRATION CATALYST

Percy R. Kavasmaneck; David B. Stanton, and Paul D. Sherman, Jr., all of South Charleston, W. Va., assignors to Union Carbide Corporation, New York, N.Y.

Filed Mar. 21, 1980, Ser. No. 132,496

Int. Cl.³ B01J 21/08, 21/12, 27/16

U.S. Cl. 252—435

2 Claims

1. Method of preparing an olefin hydration catalyst which comprises the steps of:

(1) blending a mixture of about 30 to about 70 parts by weight of diatomaceous earth, about 15 to about 30 parts by weight of bentonite, about 15 to about 30 parts by weight of a synthetic silica having a surface area of about 150 to about 200 meters² per gram, about 5 to about 25 parts by weight of cornmeal and about 5 to about 25 parts by weight of cellulose with sufficient water to form a paste;

(2) extruding the paste from step 1 into pellets;

(3) drying said pellets;

(4) calcining said dried pellets at a temperature of about 650° to about 730° C.;

(5) leaching the calcined pellets with aqueous 85 percent phosphoric acid until metallic impurities are reduced to a minimum;

(6) washing the leached pellets with water until the wash water is approximately neutral;

(7) drying the pellets;

(8) impregnating the dried pellets with 65 percent phosphoric acid at room temperature;

(9) draining off excess phosphoric acid; and

(10) drying the pellets at a temperature of about 100° to about 400° C.

4,297,242

PROCESS FOR DEMETALLATION AND DESULFURIZATION OF HEAVY HYDROCARBONS
 Albert L. Hensley, Jr., Munster, Ind., and Leonard M. Quick, Naperville, Ill., assignors to Standard Oil Company (Indiana) Division of Ser. No. 928,141, Jul. 26, 1978, Pat. No. 4,212,729. This application Jul. 14, 1980, Ser. No. 168,297
 Int. Cl.³ B01J 27/02, 23/16

U.S. Cl. 252—439 15 Claims


1. A hydrosulfurization catalyst consisting essentially of at least one active original hydrogenation metal selected from Group VIB deposited on a catalytically active support comprising alumina, said Group VIB metal being in at least one form selected from the group consisting of the elemental form, the oxide, and the sulfide, said catalyst having a surface area within the range of about 150 m²/gm to about 300 m²/gm, having a majority of its pore volume in pore diameters within the range of about 80 Å to about 130 Å, and a pore volume within the range of about 0.4 cc/gm to about 0.9 cc/gm.

4,297,243

MOLYBDENUM-EXCHANGED CRYSTALLINE ALUMINOSILICATE ZEOLITE
 Eric L. Moorehead, Diamond Bar, Calif., assignor to Union Oil Company of California, Los Angeles, Calif.
 Filed Oct. 2, 1979, Ser. No. 81,105
 Int. Cl.³ B01J 29/16, 29/26, 29/36

U.S. Cl. 252—455 Z 26 Claims

1. A crystalline aluminosilicate zeolite having a composition expressed in molar ratios of oxides as:



where $cM_{\frac{2}{n}}O$ represents the sum of all components, on a per mole of Al_2O_3 in the crystal framework basis, required to balance that portion of the charge on the crystal framework not balanced by molybdenum constituents, with the valence of M being represented by n, and where MoO_3 represents all molybdenum constituents balancing a charge on the crystal framework, and c, b, x, and y represent the moles of $M_{\frac{2}{n}}O$, MoO_3 , SiO_2 , and the water of hydration, H_2O , respectively, present in the zeolite to each mole of Al_2O_3 in the crystal framework, x being between 2 and 100, y being a non-negative number, c being 0 or a positive number less than 1, and b being a positive number no greater than 1, with c + b being a positive number no greater than 1.0, said zeolite being characterized by the ion exchange of molybdenum-containing cations from the zeolite when the zeolite is immersed for at least one hour in an aqueous sodium salt solution having a temperature in the range of 20° to 80° C. and an initial pH between 6.0 and 8.5; said solution containing sodium ions in a concentration between 1.0 and 15.0% by weight, calculated as Na, and said immersion being such that the weight ratio of zeolite to solution is between about 1:4 and 1:12.

14. A catalyst composition comprising a molybdenum-containing crystalline aluminosilicate zeolite having an ordered crystalline structure prepared by the method comprising (1) contacting a crystalline aluminosilicate zeolite having a substantially ordered crystalline structure with an aqueous solution containing a precursor of MoO_2^{+2} cations, said solution having sufficient of an organic base added thereto to maintain the pH of the solution below 7.0 but higher than that which would substantially affect the crystalline structure of the zeolite, said contacting being under conditions sufficient to replace at least some of the cations in the zeolite with molybdenum-containing cations and increase the molybdenum-containing cation content of the zeolite, and (2) subsequently calcining the zeolite containing the molybdenum-containing cations in an oxygen-containing oxidizing atmosphere.

21. A method for ion-exchanging molybdenum-containing cations into a crystalline aluminosilicate zeolite having an

ordered crystalline structure comprising contacting a crystalline aluminosilicate zeolite having an ordered crystalline structure with an aqueous solution containing a precursor of MoO_2^{+2} cations, said solution having sufficient of an organic base added thereto to maintain the pH of the solution during said contacting below 7.0 but higher than that which would substantially affect the crystal structure of the zeolite, said contacting being under conditions sufficient to replace at least some of the cations in said zeolite with molybdenum-containing cations, and recovering the zeolite containing the molybdenum-containing cations from said solution.

4,297,244

CATALYST AND PROCESS FOR CONVERSION OF HYDROCARBONS

John Mooi, Homewood, Ill., assignor to Atlantic Richfield Company, Philadelphia, Pa.
 Continuation of Ser. No. 846,046, Oct. 27, 1977, abandoned, which is a continuation-in-part of Ser. No. 681,657, Apr. 29, 1976, Pat. No. 4,252,632. This application Apr. 21, 1980, Ser. No. 142,484
 Int. Cl.³ B01J 29/06, 23/56

U.S. Cl. 252—455 Z 34 Claims

1. Combined particles comprising (A) a major amount of solid particles capable of promoting the cracking of hydrocarbon feedstock at hydrocarbon cracking conditions to produce at least one hydrocarbon product and to cause deactivating carbonaceous material to be formed on said combined particles and (B) a minor amount of discrete entities comprising (1) a major amount by weight of substantially accessible alumina, (2) a minor, catalytically effective amount of at least one platinum group metal component deposited on said alumina, said platinum group metal component deposited on said alumina, said platinum group metal component being capable of promoting the oxidation of carbon monoxide to carbon dioxide at carbon monoxide oxidation conditions, and (3) minor, catalytically effective amount of at least one crystalline aluminosilicate zeolite capable of promoting hydrocarbon cracking at the conditions in said reaction zone.

8. A composition of matter suitable for use in a chemical reaction zone-regeneration zone system comprising in intimate admixture (A) a major amount of solid particles capable of promoting the cracking of sulfur-containing hydrocarbon feedstock at hydrocarbon cracking conditions to produce at least one hydrocarbon product and to cause sulfur-containing carbonaceous material to be formed on said solid particles and (B) a minor amount of discrete entities comprising a major amount of alumina capable of associating with sulfur trioxide at the conditions in said regeneration zone and disassociating with sulfur trioxide at the conditions of said reaction zone and a minor, catalytically effective amount of at least one crystalline aluminosilicate zeolite capable of promoting hydrocarbon cracking.

4,297,245

CATALYST FOR THE PREPARATION OF METHANE
 Burton H. Bartley, Fishkill, and John H. Estes, Wappingers Falls, both of N.Y., assignors to Texaco Inc., White Plains, N.Y.

Continuation-in-part of Ser. No. 636,237, Nov. 28, 1975, Pat. No. 4,065,514, which is a continuation-in-part of Ser. No. 272,528, Jul. 17, 1972, abandoned. This application Nov. 21, 1977, Ser. No. 853,079
 Int. Cl.³ B01J 21/08, 23/56, 23/74

U.S. Cl. 252—460 7 Claims

1. A finely-divided, high surface area supported catalyst, particularly characterized by its ability to catalyze the production of methane by the reaction of hydrogen and a hydrocarbon containing at least two carbon atoms at a temperature of 300° C.—800° C. which consists essentially of a support, a metal of the platinum-palladium group and a metal of the iron group, each of said platinum-palladium group metal and said iron

group metal being substantially distributed throughout the body of the catalyst.

4,297,246

METHOD OF PRODUCING DENSE REFRACTORY OXIDE COATINGS ON METALLIC SUBSTRATES AND THE PRODUCTION OF CATALYSTS FROM THE COATED SUBSTRATES

James A. Cairns, Wantage; Robert L. Nelson, Kingston Bagpuize, and James L. Woodhead, Didcot, all of England, assignors to United Kingdom Atomic Energy Authority, England
 Filed Oct. 25, 1978, Ser. No. 954,532
 Claim: priority, application United Kingdom, Nov. 1, 1977, 45471/77

Int. Cl.³ B01J 21/08, 23/10, 23/56; B32B 15/18

U.S. Cl. 252—465 10 Claims

1. A method of coating a substrate with a refractory oxide selected from the group consisting of ceria, zirconia and titania which comprises the steps of

(i) contacting the substrate with a sol of said refractory oxide comprising a dispersion, in a liquid medium, of substantially unaggregated colloidal primary particles of the refractory oxide or of aggregated colloidal primary particles of the refractory oxide and ions which occupy gaps in said aggregated particles, said sol being capable of being converted to a gel of the refractory oxide, the bulk density of the gel being at least 40% of the theoretical density of the refractory material;

(ii) converting the sol to a gel to provide the substrate with a gel coating; and
 (iii) firing to convert the gel coating to said refractory oxide coating.

3. A method according to claim 1 wherein catalytically active material is applied to the coated substrate.

4,297,247

PREPARATION OF COATED CATALYSTS

Richard Krabetz, Kirchheim; Walter Herrmann, Mannheim; Heinz Engelbach, Limburgerhof; Peter Palm, Gerolsheim; Karl Sommer, Ludwigshafen, and Heinrich Spahn, Mannheim, all of Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Ludwigshafen, Fed. Rep. of Germany
 Filed Mar. 3, 1980, Ser. No. 126,385
 Claims priority, application Fed. Rep. of Germany, Mar. 12, 1979, 2909671

Int. Cl.³ B01J 23/22, 23/28, 23/30, 23/72

U.S. Cl. 252—468 6 Claims

1. In a process for the preparation of a coated catalyst comprising

(a) an inert carrier having a particle diameter of not less than 100 μm and a surface area of up to 20 m²/g and

(b) a coating which firmly adheres to the outer surface and in the edge zone, near the surface, of the carrier particles, and which contains the catalytic material, by applying the catalytic material, in the form of a powder of particle size not more than 300 μm, in the presence of water, to the vigorously agitated carrier, the improvement wherein catalytically active material in an amount of from 1 to 40 g/minute/liter of carrier, and water in a weight ratio of catalytic material to water of from 1:1 to 30:1, are applied continuously and spatially separate from one another, each at a constant speed, onto the carrier particles, which may or may not have been pre-moistened with water in the amount of up to 95% of the particle absorbency, in such a way that the water content of the coating which forms is less than the maximum degree of saturation of the coating of catalytic material.

4,297,248

METHOD FOR PACKING CATALYSTS

Kazunobu Abe, Izumi; Tadao Nakatsuji, Matsubara, and Toshikatsu Umaba, Sakai, all of Japan, assignors to Sakai Chemical Industry Co., Ltd., Japan

Continuation of Ser. No. 27,440, Apr. 5, 1979, abandoned. This application Jul. 8, 1980, Ser. No. 167,099

Claims priority, application Japan, Apr. 15, 1978, 53-40738
 Int. Cl.³ B01J 35/04

U.S. Cl. 252—477 R 3 Claims

1. A method of horizontally and vertically packaging a plurality of individual honeycomb catalyst units having through holes in the direction of an intended gas flow to form a composite catalyst structure having a plurality of through holes in the direction of an intended gas flow through the structure, which method comprises arranging the individual catalyst units in a manner such that the interface in the path of intended gas flow between two such catalyst units does not lie on the same plane as the interface in the path of intended gas flow between at least one vertically or horizontally adjacent pair of said catalyst units.

4,297,249

METHOD OF TREATING SILVER OXIDE POWDER AND THE PRODUCT FORMED THEREFROM

Franciszek J. Przybyla, Mississauga, and Eleanor J. Rossler, Lorne Park, both of Canada, assignors to Duracell International Inc., Bethel, Conn.

Filed Nov. 3, 1978, Ser. No. 957,597
 Int. Cl.³ H01B 1/06

U.S. Cl. 252—518 13 Claims

1. The process of producing a silver oxide powder mixture for use in the cathode of an alkaline silver oxide galvanic cell, including the steps of partially reducing a mixture having at least 10% divalent silver oxide powder, the remainder including at least a minor amount of monovalent silver oxide powder, by reacting said silver oxide powder mixture with a reagent which is a fatty acid or a fatty acid salt where the fatty acid has a chain length of at least twelve carbon atoms, and removing the reagent from the reacted silver oxide powder mixture.

4,297,250

METHOD OF PRODUCING HOMOGENEOUS ZNO NON-LINEAR POWDER COMPOSITIONS

Tapan K. Gupta, Monroeville, Pa., and Herbert E. Pietsch, Mukwonago, Wis., assignors to Westinghouse Electric Corp., Pittsburgh, Pa.

Filed Jan. 7, 1980, Ser. No. 110,278
 Int. Cl.³ H01B 1/08

U.S. Cl. 252—518 9 Claims



1. A method of making a ZnO powder composition, which can exhibit non-linear V-I characteristics, comprising the steps of:

(1) mixing:
 (a) 75 mole % to 98 mole % of finely divided, ZnO particles and 2 mole % to 25 mole % of finely divided, additive particles effective to produce non-linear V-I characteristics, with
 (b) an aqueous binder solution comprising an organic,

- water soluble binder that will decompose at temperatures of between about 150° C. and 600° C., to provide a mixed particle-binder slurry, and then
- (2) simultaneously dry, mix, agglomerating the slurry to form a mass of larger spherical particles, said particles containing binder, ZnO and additive compound distributed therethrough, and then
 - (3) pressing a mass of the agglomerated particles to provide a consolidated body, and then (4) heating the pressed body;
 - (a) first at a temperature rate increase effective to slowly decompose and remove the binder, and then,
 - (b) between about 1,050° C. and 1,400° C., for a time effective to sinter together the particles of the pressed body, forming additive doped ZnO grains within a body exhibiting non-linear V-I characteristics, and then
 - (5) crushing the sintered body to provide finely divided powder particle fragments, and then
 - (6) passing the finely divided particle fragments from the crushed sintered body through a means to measure particle size, in a manner effective to provide a powder fraction where substantially all of the particles in the powder fraction contain at least two attached additive doped ZnO grain fragments, providing a powder exhibiting non-linear V-I characteristics, where said fragments contain microfractures after crushing, and then
 - (7) heating the non-linear particles at a temperature of between 500° C. and 1,050° C., to eliminate any microfractures without re-sintering the particles.
3. The method of claim 1, where, as a last step, the non-linear ZnO powder is dispersed in a resinous medium, to provide a ZnO stress grading paint composition.

4,297,251

PROCESS FOR REMOVING HARD-TO-REMOVE SOILS FROM HARDWARE

Lowell W. Bernardino, Cincinnati, Ohio, assignor to The Procter & Gamble Company, Cincinnati, Ohio
Filed May 2, 1977, Ser. No. 792,966
Int. Cl.³ C11D 1/12, 7/44

U.S. Cl. 252—545

2 Claims

1. The process of removing hard-to-remove soils from housewares including pots, pans, dishes, glasses and utensils using aqueous solutions containing from about 0.1% to about 0.5% of a stable, single-phase light duty liquid detergent composition consisting essentially of:
 - (a) from about 5% to about 35% of a synthetic anionic surfactant having the formula $R-(Y)_n-(O)_mSO_3M$ wherein R is a group containing from 8 to about 24 carbon atoms which can be either straight or branched chain, saturated or unsaturated and attached either at the terminal position, a secondary position, or random attachment or mixtures thereof; Y is a group selected from the group consisting of $(OC_2H_4)_x$ where x is a number from 1 to 30; $(O-CH_2-CHOH-CH_2)_m$ wherein m is a number from 1 to 3; or a benzene ring, each n is either 0 or 1; and M is selected from the group consisting essentially of sodium; potassium; mono-, di-, or trialkanolammonium wherein the alkanol groups contain from 2 to 4 carbon atoms; mono-, di-, or trialkylammonium wherein the alkyl groups contain from 2 to 4 carbon atoms; ammonium; magnesium; calcium; or mixtures thereof;
 - (b) from 0% to about 15% of a suds boosting ingredient selected from the group consisting of amine oxide surfactants and amide surfactants;
 - (c) from 0.8% to about 5% of a detergency boosting ingredient which is a vegetable lecithin; and,
 - (d) water, the pH of the composition being above about 7.5 and less than about 8.5.

4,297,252

AGING-RESISTANT FIREPROOFING MATERIAL

Arndt C. Caesar, Frankenthal; Wolfram Koegel, Manneheim; Ludwig Zuern, Bad Dürkheim, and Friedheim Gaertner, Worms, all of Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Fed. Rep. of Germany
Filed May 22, 1979, Ser. No. 41,521

Claims priority, application Fed. Rep. of Germany, Jun. 24, 1978, 2827828

Int. Cl.³ C09D 5/18; C09K 3/28

U.S. Cl. 252—606

1 Claim

1. A fireproofing material which retains excellent foaming properties on aging and which comprises
 - (A) 99–90 percent by weight of an alkali metal silicate containing 20–60 percent by weight of water;
 - (B) 1–10 percent by weight of an aluminate; and
 - (C) 2–20 percent by weight, based on the sum of A + B, of glass fibers.

4,297,253

METHOD OF MAKING MOLDABLE PRODUCT

Pierre Sorbier, Place de la Mairie, 84210 Pernes Les Fontaines, France
Filed Aug. 20, 1979, Ser. No. 68,144

Claims priority, application France, Sep. 1, 1978, 78 25291

Int. Cl.³ C08L 97/00; B05D 7/00, 3/02

U.S. Cl. 260—17.3

8 Claims

1. A process for manufacturing a moldable product composed of minute fibers of a ligneous material, said fibers having a length greater than their width, comprising the steps of: impregnating thin elongated slivers of the ligneous material with a polymerizable resin, then drying the slivers, then again impregnating the slivers with polymerizable resin, then again drying the slivers, and then homogenizing the slivers to reduce their size and form said minute fibers.

4,297,254

LOW TEMPERATURE CURING EPOXY RESIN

Martin P. Seidel, Monroeville, Pa., assignor to Westinghouse Electric Corp., Pittsburgh, Pa.
Filed Nov. 28, 1979, Ser. No. 98,108

Int. Cl.³ C08G 59/50

U.S. Cl. 260—18 EP

11 Claims

1. A solventless anhydride-free liquid composition comprising:
 - (A) an oil-modified epoxy resin having an EEW of about 300 to about 600 which comprises the reaction product of:
 - (1) about 5 to about 50% of a triglyceride of a C_{10} to C_{20} fatty acid;
 - (2) about 50 to about 95% of an epoxy resin averaging at least one aliphatic hydroxyl group per molecule, an ash content of less than 0.1%, and an acid content of less than 0.01%; and
 - (3) about 0.01 to about 0.3 phr of a catalyst;
 - (B) up to about 80% of a glycidyl ether of a phenol;
 - (C) about 1 equivalent $\pm 20\%$, per equivalent of epoxy resin, of menthane diamine; and
 - (D) about 0.02 to about 3% of an accelerator for said menthane diamine.

4,297,255

ADDUCT AND ITS USE

Hans-Uwe Schenck, Wachenheim, and Erich Gulbins, Heidelberg-Neuenheim, both of Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Fed. Rep. of Germany
Filed Mar. 24, 1980, Ser. No. 133,437

Claims priority, application Fed. Rep. of Germany, Apr. 7, 1979, 2914085

Int. Cl.³ C08L 63/00; C09D 3/58, 5/40

U.S. Cl. 260—18 PF

12 Claims

1. An adduct which has been obtained by reacting
 - (a) an epoxide compound selected from the group consisting

- of glycidyl ether of a polyhydric alcohol or phenol, epoxidized oils and reaction products of aliphatic or aromatic polyepoxy resins with polyols or polyphenols with
- (b) guanidine or a guanidine derivative using not less than 1 mole of guanidine or alkylguanidine or a guanidinium salt
 - (b) per epoxide equivalent of the epoxide compound (a), and which may or may not have been partially or completely neutralized by adding an acid.

4,297,256

PREPARATION OF WATER-IMMISCIBLE, ACID-SOLUBLE

N-(AMINOMETHYL)- α,β -ETHYLENICALLY UNSATURATED CARBOXAMIDES, QUATERNARY DERIVATIVES AND POLYMERS THEREOF


Charles J. McDonald, Midland, Mich., assignor to The Dow Chemical Company, Midland, Mich.
Filed Dec. 26, 1979, Ser. No. 106,823

Int. Cl.³ C08L 33/24

U.S. Cl. 260—29.4 UA

15 Claims

1. A process for preparing an acid soluble water-immiscible N-(aminomethyl)carboxamide (cationic carboxamide) which comprises (1) contacting a reaction mixture comprising an aqueous phase and a carboxamide reactant represented by the formula:



wherein R_1 is hydrogen or alkyl and R_2 is hydrogen or an inert substituent with an aldehyde having 1 to 3 carbons and a moderately water-soluble amine under conditions including a pH of less than about 7 sufficient to cause reaction of the carboxamide reactant, aldehyde and amine to form at least 5 mole percent of the water-immiscible cationic carboxamide based on moles of the carboxamide reactant and (2) thereafter increasing the pH of the resulting reaction mixture to a value of at least 7, thereby causing the water-immiscible cationic carboxamide to separate from the aqueous phase of the reaction mixture.

4,297,257

METAL STRIPPING COMPOSITION AND METHOD
Moenes L. Elias, Canfield, and Narendra K. Shah, Youngstown, both of Ohio, assignors to Dart Industries Inc., Los Angeles, Calif.

Filed Apr. 17, 1980, Ser. No. 141,013

Int. Cl.³ C08L 33/26; C09K 13/08

U.S. Cl. 260—29.6 H

12 Claims

1. An aqueous stripping solution which contains in solution from about 0.5% to about 35% of hydrogen peroxide, from about 5% to about 50% of a reactive composition of ammonia and hydrofluoric acid or a salt thereof, and from about 0.01% to about 10% of a polyacrylamide.

4,297,258

NON-YELLOWING PAINT FORMULATIONS CONTAINING IODO SUBSTITUTED ALKYNYL URETHANES AS FUNGICIDES

William P. Long, Jr., Wilmington, Del., assignor to ICI Americas Inc., Wilmington, Del.


Filed Apr. 28, 1980, Ser. No. 144,313

Int. Cl.³ C08K 5/16

U.S. Cl. 260—29.6 MN

11 Claims

1. A water-dispersible solvent solution concentrate for use as a fungicide in water-base coating systems having an aqueous phase and a binder resin phase which comprises:
 - (a) an iodo substituted low molecular weight alkyne urethane having the general formula:



wherein R is selected from the group consisting of substituted or unsubstituted alkyl, aryl or alkylaryl groups having from 1 to 20 carbon atoms and having from one to three linkages corresponding to m, and m and n are whole integers of from 1–3 and may be the same or different, and R' is —H, methyl or alkyl radical which may be the same or different;

- (b) a substantially water immiscible organic solvent;
- (c) a surfactant selected from the group consisting of ionic and nonionic surfactants having an HLB in the range of 10–17.1 whereby said concentrate can be dispersed such that said iodo compound is not partitioned into said aqueous phase of said water-base coating systems.

4,297,259

SYNTHETIC POLYMER EMULSIFIER

John G. Papalos, Ledgewood, and Ronald W. Kavchok, Belle Mead, both of N.J., assignors to Diamond Shamrock Corporation, Dallas, Tex.

Division of Ser. No. 31,113, Apr. 18, 1979, Pat. No. 4,256,871. This application May 7, 1980, Ser. No. 147,383

Int. Cl.³ C08L 61/00

U.S. Cl. 260—29.6 NR

8 Claims

1. In the process of manufacturing a synthetic latex, using a recipe containing a diluent, a primary emulsifier, an initiator, at least one polymer monomer and a secondary emulsifier or co-emulsifier, with optionally, a chelating agent, an electrolyte and a chain transfer agent, the improvement comprising having present in the recipe an effective amount of a secondary emulsifier or co-emulsifier which is a condensation product of 1 mole of naphthalenesulfonic acid, from about 0.1 to about 5 moles of linear alkylbenzenesulfonic acid having an alkyl moiety of from about 4 to about 20 carbon atoms, and from about 0.26 to about 3.1 moles of formaldehyde and salts thereof thereby reducing secondary emulsifier or co-emulsifier pollution in polymer plant effluent.

4,297,260

ERASABLE WRITING MEDIUM COMPOSITION

William I. Ferree, Jr., and Gao V. Nguyen, both of Dallas, Tex., assignors to Liquid Paper Corporation, Dallas, Tex.

Filed Nov. 19, 1979, Ser. No. 95,574

Int. Cl.³ C08K 5/17

U.S. Cl. 260—29.7 H

11 Claims

1. A writing medium composition that is erasable by an ordinary pencil eraser and suitable for use in ballpoint or porous tip pens comprising:
 - (a) a carboxylated styrene-butadiene latex emulsion, said emulsion having a styrene-butadiene ratio of from about 40:60 to about 55:45, a viscosity of from about 50 to about 300 cps, a pH of from about 6 to about 10, a surface tension of from about 45 dynes per cm to about 72 dynes per cm and containing from about 40% to about 60% water by weight of said emulsion, said emulsion being further characterized by its ability to rapidly form a cohesive film at ambient temperature on a dry writing surface and having a low adhesion to paper to permit removal therefrom with an ordinary pencil eraser; and
 - (b) a basic dye that is a salt of a triarylmethyl cation which is dissolvable in said emulsion but which dye, when combined with said emulsion, does not, when said emulsion is applied to paper, penetrate into the paper fibers or paper voids sufficiently to form visible images on the paper.

4,297,261

CATIONIC POLYMERS AND THEIR USE IN ELECTRODEPOSITION

Edward L. Jozwiak, Jr., Gibsonia, Pa., assignor to PPG Industries, Inc., Pittsburgh, Pa.

Filed Jun. 23, 1980, Ser. No. 162,225

Int. Cl.³ C08L 63/10

U.S. Cl. 260—29.7 RP

34 Claims

1. A stable, aqueous dispersion of a cationic polymeric product prepared by polymerizing in aqueous medium under free radical initiated addition polymerization conditions:

(A) an aqueous dispersed phase of a polymerizable, ethylenically unsaturated monomer composition, in the presence of

(B) an at least partially acid neutralized polyepoxide-primary and/or secondary amine adduct which contains pendent unsaturation.

4,297,262

POLYVINYL BUTYRAL PLASTICIZED WITH TETRAETHYLENEGLYCOL DI-N-HEPTANOATE

Thomas R. Phillips, Belpre, Ohio, assignor to E. I. Du Pont de Nemours and Company, Wilmington, Del.


Filed Aug. 31, 1979, Ser. No. 71,537

The portion of the term of this patent subsequent to Oct. 28, 1997, has been disclaimed.

Int. Cl.³ C08K 5/10

U.S. Cl. 260—31.6

5 Claims



1. A plastic composition comprising polyvinyl butyral and, in compatible admixture therewith, about from 20 to 55 parts per hundred of polyvinyl butyral of a plasticizer consisting essentially of tetraethyleneglycol di-n-heptanoate of the general formula:



4,297,263

METHOD OF MAKING POLYPROPYLENE PRINTING PLATE USING PAPER MATRIX

Kinzo Miyamoto, Mitaka; Takayasu Tanaka, Tokyo, and Yoshimi Inoue, Yokohama, all of Japan, assignors to Mitsui Toatsu Chemicals Inc., Tokyo and Kabushikikaisha Asahi Shinbunsha, Osaka, both of Japan

Filed Mar. 24, 1976, Ser. No. 669,817

Claims priority, application Japan, Apr. 2, 1975, 50-39262

Int. Cl.³ C08K 5/20

U.S. Cl. 260—32.6 PQ

2 Claims

1. A reproducing printing plate made by using a paper matrix, comprising a crystalline ethylene-propylene copolymer whose melt flow index is selected in a range of 3-10, which contains ethylene less than 20 weight % and which has the tensile yield strength of 220-330 kg/cm².

4,297,264

PROCESS FOR PREPARING ALKOXYLATED CROSS LINKING AGENTS BY PREPARING (A) AN AQUEOUS ALKANOLIC ALKOXYLATED AMINO RESIN (B) AZEOTROPIC DISTILLATION AND (C) DISTILLING EXCESS ALCOHOL

Robert S. De Ruiter, Downsview, and Stamatis M. Kambanis, Toronto, both of Canada, assignors to Reichhold Limited, Islington, Canada

Filed Jun. 6, 1980, Ser. No. 157,174

Claims priority, application Canada, Jun. 4, 1980, 353359

Int. Cl.³ C08L 61/24; C08G 12/06, 12/12, 12/32

U.S. Cl. 260—33.4 R

13 Claims

1. A process for the preparation of an alkoxyated amino resin comprising:

(1) preparing an aqueous-alkalolic solution of an alkoxyated amino resin by either:

(a) converting an aqueous formaldehyde solution into an alcoholic formaldehyde-amino compound concentrate by admixing an amino compound chosen from the group consisting of urea, thiourea, guanidine, and melamine, and an alkanol, and removing the water by azeotropic distillation, the alkanol having up to 8 carbon atoms inclusive and

(b) reacting the thus formed formaldehyde-amino compound concentrate with an amino compound chosen from the group consisting of urea, thiourea, guanidine, and melamine, to provide an alkoxyated amino resin;

or:

(c) converting an aqueous formaldehyde solution into a formaldehyde-amino compound concentrate by admixing aqueous formaldehyde and an amino compound chosen from the group consisting of urea, thiourea, guanidine, and melamine and removing the water by distillation; and

(d) reacting the thus formed formaldehyde-amino compound concentrate with an amino compound chosen from the group consisting of urea, thiourea, guanidine, and melamine and an alkanol having up to 8 carbon atoms to provide an alkoxyated amino resin;

(2) removing the water remaining in the alkoxyated amino resin by azeotropic distillation with the alkanol; and

(3) removing excess remaining alkanol by distillation to provide a desired resin solids content.

4,297,265

SILICONE RUBBER COATING MATERIAL HAVING REDUCED SURFACE TENSION

Thomas O. Olsen, Wichita, Kans., assignor to Otto Fabric, Inc., Sedgwick County, Kans.

Filed Nov. 23, 1979, Ser. No. 96,940

Int. Cl.³ C08K 5/01

U.S. Cl. 260—33.6 SB

8 Claims

1. A composition for coating a substrate comprising:

a first component comprising silicone rubber and a solvent therefor, said silicone rubber comprising between 50% and 70% by weight of said first component; and

a second component comprising particulate SiO₂ having a particle size of less than 45 microns, said second component comprising 90 to 110% by weight of said first component.

4,297,266

MICROFILLED DENTAL COMPOSITE AND METHOD USING THE SAME

Robert L. Ibsen, and William R. Glace, both of Santa Maria, Calif., assignors to Den-Mat, Inc., Santa Maria, Calif.

Filed Feb. 8, 1980, Ser. No. 120,119

Int. Cl.³ A61K 6/08; C08K 3/26, 3/40, 9/06

U.S. Cl. 260—42.14

11 Claims

1. A filled-resin dental composite consisting essentially of

4,297,270

MANUFACTURE AND USE OF NON-IONOGENIC INTERFACE-ACTIVE AGENTS BASED ON MODIFIED ROSINS

Heinz Uhrig, Steinbach, and Reinhold Deubel, Bad Soden am Taunus, both of Fed. Rep. of Germany, assignors to Hoechst Aktiengesellschaft, Frankfurt am Main, Fed. Rep. of Germany

Filed Sep. 13, 1979, Ser. No. 75,034


Claims priority, application Fed. Rep. of Germany, Sep. 15, 1978, 2840113; Jun. 16, 1979, 2924354

Int. Cl.³ C09F 1/04; D06M 15/02

U.S. Cl. 260—104

8 Claims



1. A compound of the formula



wherein

A is a cycloalkyl-, aralkyl- or aryl-modified rosin acid radical or a radical of an ester of a polyhydric alcohol with such an acid,

X stands for the same or different group or groups of, the formulae



n is a number of from 1 to 100 and
m is an integer of from 1 to 5.

4,297,267

HEXAVALENT CHROMIUM INTERNAL COLORANTS FOR DIOL BIS (ALLYL CARBONATE) POLYMERIZATES

Ivan R. Leatherman, Wadsworth, Ohio, assignor to PPG Industries, Inc., Pittsburgh, Pa.

Filed Feb. 4, 1980, Ser. No. 118,357

Int. Cl.³ C08K 3/10, 3/18

U.S. Cl. 260—42.53

9 Claims

1. A liquid composition comprising diol bis(allyl carbonate) or monomer and chlorochromate ion.

4,297,268

1,4-DIHYDRO-2,6

DIMETHYLRYRIDINE-3,5-DICARBOXYLIC ACID ESTER COMPOSITIONS

Gerd Abeler, Griesheim über Darmstadt, and Rudolf Maul, Lorsch, both of Fed. Rep. of Germany, assignors to Ciba-Geigy Corporation, Ardsley, N.Y.

Division of Ser. No. 958,760, Nov. 8, 1978, Pat. No. 4,214,088.

This application Dec. 20, 1979, Ser. No. 105,796

Claims priority, application Switzerland, Nov. 11, 1977, 13799/77

Int. Cl.³ C08K 5/34


U.S. Cl. 260—45.8 N

13 Claims

1. A stabilized composition which comprises

(a) a chlorine-containing thermoplastic polymer, and

(b) from 0.5 to 2.5 percent by weight, relative to the total composition, of a compound of formula I



in which R is branched-chain or straight-chain C₁-C₂₀ alkyl, X is sulfur, and p denotes the numbers 1-8 inclusive.

4,297,269

N,N'-BIS(1-CYCLOHEXYL-1-ETHYL)-P-PHENYLENEDIAMINE, AND RUBBER COMPOUNDS CONTAINING THE SAME

Helmut L. Merten, Hudson, and Gene R. Wilder, Medina, both of Ohio, assignors to Monsanto Company, St. Louis, Mo.

Filed Oct. 16, 1980, Ser. No. 197,400

Int. Cl.³ C08K 5/18; C07C 87/38

U.S. Cl. 260—45.9 QB

8 Claims

1. N,N'-bis(1-cyclohexyl-1-ethyl)-p-phenylenediamine.

2. A vulcanizable rubber compound containing a stabilizing amount of N,N'-bis(1-cyclohexyl-1-ethyl)-p-phenylenediamine.

3. Process for the preparation of guaiacetic acid A which

comprises dissolving natural guaiac resin in acetone, removing the residue obtained by the addition of toluene, evaporating the remaining solution to dryness, dissolving the evaporation residue in n-heptane/ethyl acetate or toluene/acetone, separating the solution chromatographically over a column containing neutral silica gel, which has been pretreated with acid, using n-heptane/ethyl acetate or toluene/acetone, collecting and evaporating the fractions with R_F=0.45 (toluene/dioxan/glacial acetic acid; 90:25:10 v/v/v) and recrystallizing the evaporation residue from xylene.

4,297,272

PROCESS FOR THE PREPARATION OF PURIFIED BACTERIAL MEMBRANAL PROTEOGLYCAN

Lucien D. D'Hinterland; Gerard Normier; Anne-Marie Pinel, and Jacques Durand, all of Castres, France, assignors to Pierre Fabre S.A., France

Filed Dec. 13, 1979, Ser. No. 103,202

Claims priority, application France, Dec. 19, 1978, 78 35649 Int. Cl.³ C07G 7/00; A61K 39/108, 39/02

U.S. Cl. 260—112 R

8 Claims

1. A process for the preparation of purified water soluble bacterial membranar proteoglycans which comprises at least one step in which crude proteoglycans are treated in an aqueous medium with a reactant selected from the group consisting of bases and hypobromites, followed by removal of the excess reactant and the insoluble residue, the purified proteoglycans being present in aqueous solution.

4,297,273

CHEMILUMINESCENT PHTHALHYDRAZIDE-LABELED PROTEIN AND POLYPEPTIDE CONJUGATES

Robert T. Buckler, Edwardsburg, Mich., and Hartmut R. Schroeder, Elkhart, Ind., assignors to Miles Laboratories, Inc., Elkhart, Ind.

Division of Ser. No. 927,621, Jul. 24, 1978, This application Jan. 14, 1980, Ser. No. 111,809

Int. Cl.³ C07G 7/00


U.S. Cl. 260—112 B

10 Claims

1. In a chemiluminescent-labeled conjugate for use in specific binding assays of the general formula:

L(CO—NH) labeling substance

wherein L(CO)— is an antigenic protein or polypeptide bound to said labeling substance through an amide bond, characterized in that said —NH) labeling substance has the formula:



wherein R³ is hydrogen or straight chain alkyl containing 1-4 carbon atoms and n=2-8.

4,297,274

PROTEIN FROM RED BLOOD CELLS AND PROCESS FOR ISOLATING IT

Hans Bohn, and Heinz Haupt, both of Marburg an der Lahn, Fed. Rep. of Germany, assignors to Behringwerke Aktiengesellschaft, Marburg an der Lahn, Fed. Rep. of Germany

Continuation of Ser. No. 898,519, Apr. 20, 1978, abandoned.

This application Mar. 7, 1980, Ser. No. 128,253

Claims priority, application Fed. Rep. of Germany, Apr. 25, 1977, 2718326

Int. Cl.³ C07G 7/00

U.S. Cl. 260—112 B

8 Claims

1. A process for isolating a protein characterized by (a) a protein content of 99%±1% and a content of carbohydrates of 0.9%±0.5%, and a compositional analysis including the following major amino-acid and carbohydrate fractions:

Amino Acids	Mol %	Variation Coefficient %
Aspartic acid	11.39	1.21
Glutamic acid	8.44	4.35

-continued

Amino Acids	Mol %	Variation Coefficient %
Glycine	9.13	2.22
Alanine	7.35	1.68
Valine	8.96	1.36
Leucine	8.79	3.83

Carbohydrates	% by weight
Hexoses (Gal/Man 1:1)	0.9 ± 0.2
Acetylhexoseamine	0.3 ± 0.1;

(b) a sedimentation coefficient $S_{20w}^{C=O}$ of 6.88±0.5S;
(c) a molecular weight of 160,000±15,000;
(d) an iso-electric point of 5.5±0.2;
(e) an electrophoretic mobility in the range of the β_1 -globulins of human serum; and
(f) a specific immunological reaction with an antibody specifically directed against the protein,

which process comprises extracting the protein from red blood cells or from an aqueous solution having an electrical conductivity of from 1 to 10 μ S/cm and containing the protein; adsorbing said protein from the aqueous solution on an anion exchanger at a pH value of between 6.5 and 7.5, thereby separating the protein from the supernatant of said aqueous solution; treating the anion exchanger and adsorbed protein with a series of salt solutions of varying concentration to elute that which was adsorbed on the exchanger in various fractions; identifying each fraction containing the protein; concentrating the protein by ultra-filtration; fractionating the concentrate by gel-filtration and elution; identifying each resultant fraction containing the protein, and concentrating the protein by ultra-filtration.

5. An isolated, concentrated, protein obtained by fractionating an extract of blood or of a blood-rich organ, said protein having

(a) a protein content of 99%±1% and a content of carbohydrates of 0.9%±0.5%, and a compositional analysis as follows:

Amino Acids	Mol %	Variation Coefficient %
Lysine	6.68	2.67
Histidine	1.61	5.08
Arginine	5.05	3.97
Aspartic acid	11.39	1.21
Threonine	5.05	2.23
Serine	4.98	4.12
Glutamic acid	8.44	4.35
Proline	5.66	6.95
Glycine	9.13	2.22
Alanine	7.35	1.68
½ Cystine	1.65	2.04
Valine	8.96	1.36
Methionine	0.32	28.87
Isoleucine	4.84	1.17
Leucine	8.79	3.83
Tyrosine	3.34	4.24
Phenylalanine	5.92	3.81
Tryptophan	1.01	10.30

Carbohydrates	% by weight
Hexoses (Gal/Man 1:1)	0.9 ± 0.2
Acetylhexoseamine	0.3 ± 0.1
Acetyl-neuraminic acid	0
Fucose	0

(b) a sedimentation coefficient $S_{20w}^{C=O}$ of 6.88±0.5S;
(c) a molecular weight of 160,000±15,000;
(d) an iso-electric point of 5.5±0.2;

(e) an electrophoretic mobility in the range of the β_1 -globulins of human serum; and
(f) a specific immunological reaction with an antibody specifically directed against the protein.

4,297,275

INHIBITORS OF MAMMALIAN COLLAGENASE
Joseph E. Sundeen, Yardley, Pa., and Tamara Dejneka, Skillman, N.J., assignors to E. R. Squibb & Sons, Inc., Princeton, N.J.

Division of Ser. No. 51,195, Jun. 25, 1979, Pat. No. 4,235,885.


This application Feb. 14, 1980, Ser. No. 121,352

Int. Cl.³ C07C 103/52; C07G 7/00; C07C 147/02



U.S. Cl. 260—112.5 R

22 Claims

1. A compound having the formula



or a salt thereof wherein

R₁ is hydrogen or alkanoyl of 2 to 10 carbon atoms;R₂ is hydroxy, orR₃ is hydrogen, alkyl of 1 to 4 carbon atoms,

R₄ is hydroxy, amino, arginine, leucine, glutamine, alanine or glycine; and
m is 0 or an integer of 1 to 9.

4,297,276

THYMOSIN BETA 3 AND BETA 4

Allan L. Goldstein, Washington, D.C., and Teresa L. K. Low, Annandale, Va., assignors to Hoffman-La Roche Inc., Nutley, N.J.


Continuation-in-part of Ser. No. 23,115, Mar. 23, 1979, abandoned, which is a continuation-in-part of Ser. No. 967,675, Dec. 8, 1978, abandoned. This application Jun. 16, 1980, Ser. No. 159,430

Int. Cl.³ C07C 103/52; A61K 37/00

U.S. Cl. 260—112.5 R

2 Claims

1. Thymosin β_3 being a polypeptide essentially free of other thymic polypeptides and having the following amino acid sequence:



-Lys-Phe-Asp-Lys-Ser¹⁵-Lys-
-Leu-Lys-Lys-Thr²⁰-Glu-Thr-Gln-Glu-Lys²⁵-Asn-
-Pro-Leu-Pro-Ser³⁰-Lys-Glu-Thr-Ile-Glu³⁵-Gln-Glu-
-Lys-Gln-Ala⁴⁰-Gly-Glu-Ser-(Asx, Glx, Ile, Thr)Ala-Lys-
Thr⁵⁰-OH

and the pharmaceutically acceptable acid addition salts or base salts thereof.

4,297,277

DERIVATIVES OF A-30912B NUCLEUS

Manuel Debono, Indianapolis, Ind., assignor to Eli Lilly and Company, Indianapolis, Ind.



Continuation-in-part of Ser. No. 103,018, Dec. 13, 1979, abandoned. This application Aug. 25, 1980, Ser. No. 181,434

Int. Cl.³ C07C 103/52; A61K 37/00; C12P 21/04


U.S. Cl. 260—112.5 R

40 Claims


1. A compound of the formula:

wherein R¹ is a group of the formula:

(a)



(b)



(c)

wherein A is divalent oxygen, sulfur, sulfinyl, or sulfonyl; A¹ is divalent oxygen, sulfur, sulfinyl, sulfonyl or —NH—; X is hydrogen, chloro, bromo, iodo, nitro, C₁–C₃ alkyl, hydroxy, C₁–C₃ alkoxy, mercapto, C₁–C₃ alkylthio, carbamyl or C₁–C₃ alkylcarbamyl; X¹ is chloro, bromo or iodo; R² is hydrogen, C₁–C₁₈ alkyl or C₂–C₁₈ alkenyl; W is C₁–C₁₀ alkylene or C₂–C₁₀ alkenylene; m, n and p are 0 or 1, but if m=0, n must=0; provided: that the sum of the carbon atoms in the R² and W groups must be greater than 4 but cannot exceed 21; that when X is mercapto, A and A¹ cannot be sulfinyl or sulfonyl and that when A and A¹ are sulfinyl or sulfonyl, they must be in equal oxidation states.


4,297,278

PENTAKIS-AND HEPTAKIS-AZOXY DYESTUFFS
 Horst Nickel, Leverkusen, Fed. Rep. of Germany, assignor to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany
 Filed Mar. 7, 1980, Ser. No. 128,201

Claims priority, application Fed. Rep. of Germany, Mar. 16, 1979, 2910458

Int. Cl.³ C09B 57/00; C07C 105/00; D06P 3/24, 3/32
 U.S. Cl. 260—143 4 Claims

1. A polyazo dyestuff of the formula



wherein

D denotes the radical of a diazo component and n denotes 1 or 2.


4,297,279

IMIDAZOLEDICARBOXYLIC ACID DERIVATIVE
 Naohiko Yasuda, Yokosuka, and Eiji Nakanishi, Kawasaki, both of Japan, assignors to Ajinomoto Co., Inc., Tokyo, Japan
 Filed Mar. 27, 1980, Ser. No. 134,681


Claims priority, application Japan, Mar. 27, 1979, 54-36133

Int. Cl.³ C07D 499/04, 501/02, 487/04
 U.S. Cl. 260—239.1 5 Claims


2. A process for producing a compound having the formula:



wherein A is an organic radical selected from the group consisting of




and




wherein Z is a radical selected from the group consisting of hydrogen, acyloxy, carbamoyloxy, heteroaromaticthio and quaternary ammonium, and X is a radical selected from the group consisting of hydrogen and hydroxyl, which comprises

reacting an imidazolidicarboxylic acid derivative having the following formula:



with a compound having the following formula:



wherein A and X are as defined above.

4,297,280

4,1-BENZOXAZEPINES

Kentaro Hirai, Kyoto; Shigeru Matsutani, Sakai; Teruyuki Ishiba, Takatsuki, and Itsuo Makino, Kobe, all of Japan, assignors to Shionogi & Co., Ltd., Osaka, Japan


Filed Nov. 6, 1979, Ser. No. 91,814

Claims priority, application Japan, Nov. 27, 1978, 53-146949
 Int. Cl.³ C07D 498/04

U.S. Cl. 260—245.5

11 Claims

1. A compound of the formula:



wherein

R² is C₁ to C₃ alkyl or C₁ to C₃ α-aminoalkyl,
 X is halogen or nitro,
 Y is hydrogen or halogen, and
 Z is hydrogen, C₁ to C₃ alkoxy or C₃ to C₉ dialkylaminoalkoxy;
 or a pharmaceutically acceptable acid addition salt thereof.

4,297,281

PROCESS FOR HALOGENATING COPPER PHTHALOCYANINE

Diether Wessling, Cologne, Fed. Rep. of Germany, assignor to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany
 Filed Dec. 31, 1979, Ser. No. 108,935

Claims priority, application Fed. Rep. of Germany, Jan. 18, 1979, 2901859

Int. Cl.³ C09B 47/04

U.S. Cl. 260—314.5

2 Claims

1. A process for halogenating copper phthalocyanine to a halogen content of about 14 to about 15.5 halogen atoms per

CuPc molecule, in an aluminium chloride/sulphuryl chloride mixture which contains 8 to 25% by weight, relative to the amount of AlCl₃, of an anhydrous alkali metal halide, characterised in that the AlCl₃/SO₂Cl₂ mixture contains 70 to 150% by weight, relative to the amount of AlCl₃, of sulphuryl chloride and the halogenation is carried out under an excess pressure of 1 to 20 bars.

4,297,282

RESOLUTION OF MERCAPTOPROPIONIC ACIDS
 Naohito Ohashi, Nishinomiya; Shoji Nagata, and Junki Katsube, both of Toyonaka, all of Japan, assignors to Sumitomo Chemical Company, Limited, Osaka, Japan

Filed Nov. 2, 1979, Ser. No. 90,857


Claims priority, application Japan, Mar. 2, 1979, 54-24820; Mar. 2, 1979, 54-24821; Mar. 13, 1979, 54-29548; Jun. 28, 1979, 54-82412; Jul. 25, 1979, 54-95228

Int. Cl.³ C07D 207/16; C07C 153/017


U.S. Cl. 260—326.2

9 Claims


1. A process for the optical resolution of DL-α-methyl-β-acylthiopropionic acid, which comprises contacting a DL-α-methyl-β-acylthiopropionic acid of the formula,




wherein R is a lower alkyl, phenyl or substituted phenyl bearing a methyl or chloro radical, with an optically active amine of the formula,



wherein R₁ is methyl and R₂ is α-naphthyl or R₁ is




and R₂ is




(wherein X and Y are each hydrogen, methyl or halogen) to form diastereoisomeric salts, subjecting the formed diastereoisomeric salts to fractional crystallization in an organic solvent to separate the D-acid salt from the L-acid salt, and then contacting the individual diastereoisomeric salts with acid to give D-α-methyl-β-acylthiopropionic acid and L-α-methyl-β-acylthiopropionic acid.


9. A process for producing captopril of the formula,




which comprises (A) contacting DL-α-methyl-β-acylthiopropionic acid of the formula,




wherein R is lower alkyl, phenyl or substituted phenyl bearing methyl or chloro radical with an optically active amine of the formula,



wherein R₁ is methyl and R₂ is α-naphthyl or R₁ is



and R₂ is



(wherein X and Y are each hydrogen, methyl or halogen) to form diastereoisomeric salts, subjecting the product to fractional crystallization to separate the D-acid salt from the L-acid salt, and then contacting the thus obtained D-acid salt with an acid to give D-α-methyl-β-acylthiopropionic acid, (B) reacting the resulting D-α-methyl-β-acylthiopropionic acid with thionyl chloride to form its acid chloride, subjecting the resulting acid chloride to condensing reaction with L-proline in the presence of a base to give N-(D-α-methyl-β-acylthiopropionyl)-L-proline, and (C) deacylating of the resulting N-(D-α-methyl-β-acylthiopropionyl)-L-proline with a base to give N-(D-α-methyl-β-thiopropionyl)-L-proline.

4,297,283

CHLORINATION OF PHTHALIC ANHYDRIDE
 John W. Verbicky, Scotia, N.Y., assignor to General Electric Company, Schenectady, N.Y.

Filed Oct. 9, 1980, Ser. No. 195,669

Int. Cl.³ C07D 307/89

U.S. Cl. 260—346.3

7 Claims

1. The process for chlorinating phthalic anhydride to produce a predominantly monochlorinated compound containing a single chlorine in the 4-position so that the molar ratio of chlorine in the 4-position as contrasted to chlorine in the 3-position ranges from 5 to 11 molar equivalents of the former per molar equivalent of the 3-position compound, which process comprises passing chlorine and phthalic anhydride in the vapor phase with an inert gas, in the absence of a chlorination catalyst, through a reaction chamber maintained at a temperature above 350° C., but below 600° C., and thereafter isolating the 4-substituted phthalic anhydride.

4,297,284
PREPARATION OF
2,3-DIHYDRO-2,2-DIMETHYL-7-HYDROXYBENZOFU-
RAN

Daniel Michelet, Tassin la Demi-Lune, France, assignor to Rhone-Poulenc Agrochimie, Lyons, France

Continuation of Ser. No. 170,977, Jul. 18, 1980, abandoned. This application Jul. 22, 1980, Ser. No. 171,087

Claims priority, application France, Jul. 18, 1979, 79 19127
Int. Cl.³ C07D 307/86

U.S. Cl. 260—346.22 14 Claims

1. A process for the preparation of 2,3-dihydro-2,2-dimethyl-7-hydroxybenzofuran, comprising heating a member selected from the group consisting of 3-isobutenyl-1,2-dihydroxybenzene, and admixture of at least 10% by weight of 3-isobutenyl-1,2-dihydroxybenzene with 3-methyl-1,2-dihydroxybenzene, at cyclization/isomerization temperatures, in the presence of a catalytic amount of an organic sulfonic acid.

4,297,285
2,3-DIHYDRO-2,3-DIMETHYL-7-BENZOFURYL
N-[(PHOSPHINYLA)AMINO]THIO- AND
N-[(PHOSPHINOTHIOYL)AMINO]THIO-
METHYLCARBAMATES

Stephen J. Nelson, Kalamazoo, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.

Continuation-in-part of Ser. No. 115,474, Jan. 25, 1980, which is a continuation-in-part of Ser. No. 962,266, Nov. 20, 1978, Pat. No. 4,208,409, which is a continuation-in-part of Ser. No. 874,959, Feb. 3, 1978, abandoned, which is a continuation-in-part of Ser. No. 765,807, Feb. 4, 1977, Pat. No. 4,081,536. This application Jul. 31, 1980, Ser. No. 174,049

The portion of the term of this patent subsequent to Jun. 17, 1997, has been disclaimed.

Int. Cl.³ C07D 307/86

U.S. Cl. 260—346.73 34 Claims

1. 2,3-dihydro-2,2-dimethyl-7-benzofuranyl methyl[(methoxy)(5,5-dimethyl-2-thioxo-1,3,2-dioxaphosphorinan-2-yl)-amino]thio]carbamate.

4,297,286
PROCESS FOR SELECTIVELY PRODUCING
ISOSORBIDE-5-NITRATE

Klaus Sandrock, Langenfeld, and Günter Cordes, Leichlingen, both of Fed. Rep. of Germany, assignors to Sanol Schwarz-Monheim GmbH, Monheim, Fed. Rep. of Germany

Filed Jan. 24, 1980, Ser. No. 114,906

Claims priority, application Fed. Rep. of Germany, Feb. 2, 1979, 2903927

Int. Cl.³ C07D 307/00

U.S. Cl. 260—347.8 6 Claims

1. A process for preparing isosorbide-5-nitrate comprising (a) reacting isomannide in an organic solvent or in an aqueous-organic reaction medium with an equivalent amount of a compound selected from the group consisting of: (1) the acid halogenides of an aromatic sulfonic acid of the general formula I




wherein A is a benzene or a naphthalene ring, R is a lower alkyl group with 1 to 4 carbon atoms, a lower alkoxy group with 1 to 4 carbon atoms or a halogen, and n is a numeral from 0 to 3,

(2) a perfluoroalkanesulfonic acid with 1 to 4 carbon atoms or anhydride thereof, (3) an alkanesulfonic acid with 1 to 4 carbon atoms or anhydride thereof,

(4) a perfluoroalkanoic acid with 1 to 4 carbon atoms or anhydride thereof, (5) a carbamic acid, and (6) sulphurous acid;

(b) reacting the resulting isomannide-2-ester in the presence of a solvent with a compound selected from the group consisting of:

(1) the alkali metal and ammonium salts of a benzoic acid of the general formula II



wherein R' is a lower alkyl group with 1 to 4 carbon atoms, a lower alkoxy group with 1 to 4 carbon atoms or a halogen, and m is a numeral from 0 to 3, and

(2) a lower alkanic acid with 1 to 4 carbon atoms in the alkane group, at a temperature sufficient to produce an isosorbide-2-ester,

(c) converting the hydroxy group in the 5-position of the resulting isosorbide-2-ester into the nitrate group by subjecting the ester to reaction with nitric acid, and

(d) splitting off the 2-ester group from the resulting isosorbide-2-ester-5-nitrate to yield the isosorbide-5-nitrate by hydrolysis in an aqueous organic solvent with an alkali metal hydroxide or by alcoholysis in an organic solvent comprising an alcohol with an alkali metal hydroxide.

4,297,287
PRODUCTION OF EPOXIDES FROM LOWER
ALKANE-1,2-DIOLS

Michel Costantini, Lyons, and Michel Jouffret, Francheville-le-Bas, both of France, assignors to Rhone-Poulenc Industries, Paris, France

Continuation of Ser. No. 942,361, Sep. 14, 1978, abandoned, which is a continuation-in-part of Ser. No. 889,732, Mar. 24, 1978, abandoned. This application Jun. 10, 1980, Ser. No. 158,317

Claims priority, application France, Mar. 24, 1977, 77 10140
Int. Cl.³ C07D 301/02

U.S. Cl. 260—348.16 21 Claims

1. A process for the preparation of a lower alkylene oxide, which comprises dehydrating a lower alkane-1,2-diol selected from the group consisting of ethylene glycol and propylene glycol, in liquid phase, under a pressure of at least atmospheric, at a temperature of from 200° to 400° C., and in the presence of a mixture comprising at least one heavy carboxylic acid and at least one alkali metal or alkaline earth metal carboxylate, wherein the amount of heavy carboxylic acid present per mole of carboxylate ranges from 0.01 to 100 mols and the concentration of the heavy carboxylic acid/carboxylate admixture in the reaction mixture being at least 0.1% by weight, wherein the dehydration is conducted in the presence of a solvent for the heavy carboxylic acid/carboxylate admixture, selected from the group consisting of poly (oxyalkylene) glycols, ethers, alkylbenzenes and polyphenyls, and wherein the product epoxide is continuously removed as it is formed.

4,297,288
5-AMINO-1,2,3,4-TETRAHYDROANTHRAQUINONE
AND ITS PREPARATION


Serge Y. Delavarenne, Francheville Le Haut; Bernard Dubreux, Francheville Le Bas, and Pierre Tellier, Sainte Foy Les Lyon, all of France, assignors to P C U K Produits Chimiques Ugine Kuhlmann, Courbevoie, France

Filed Jan. 14, 1980, Ser. No. 112,002


Claims priority, application France, Jan. 19, 1979, 79 01326
Int. Cl.³ C07C 97/24

U.S. Cl. 260—378 10 Claims

1: 5-amino-1,2,3,4-tetrahydroanthraquinone, as a new industrial product.



wherein Y is hydrogen, hydroxy or protected-hydroxy, and R is selected from the group consisting of hydrogen, alkyl



4,297,289
VITAMIN D COMPOUNDS ISOTOPICALLY
SUBSTITUTED AT CARBON 6 AND PROCESS FOR
THEIR PREPARATION


Hector F. DeLuca; Heinrich K. Schnoes, both of Madison; Herbert E. Paaren, Verona, and Mary A. Fivizzani, Madison, all of Wis., assignors to Wisconsin Alumni Research Foundation, Madison, Wis.

Filed Jul. 17, 1980, Ser. No. 169,567

Int. Cl.³ C07J 9/00

U.S. Cl. 260—397.2 28 Claims

1. A method for preparing vitamin D- and 5,6-trans vitamin D-compounds which are isotopically labeled at carbon 6 of the molecule with deuterium or tritium which comprises, reducing, a compound having the general formula



where R represents the sidechain as desired in the labeled product and Y is hydrogen, hydroxy or protected-hydroxy

with a tritio- or deuterio-borohydride reducing reagent, whereby the corresponding 6-deutero- or 6-tritio-substituted-6-hydroxy product is obtained

subjecting said reduction product to acid catalyzed solvolysis, whereby the 6-deutero- or 6-tritio-vitamin D and 5,6-trans vitamin D compound is obtained, and recovering the desired labeled product.

7. Compounds having the formula

4,297,290
PROCESS FOR PREPARING SORBITAN ESTERS

George J. Stockburger, Wilmington, Del., assignor to ICI Americas Inc., Wilmington, Del.

Filed Jul. 17, 1980, Ser. No. 169,768

Int. Cl.³ C09F 5/08

U.S. Cl. 260—410.6 8 Claims

1. A process for preparing a sorbitan fatty acid ester or mixture thereof which comprises reacting an anhydro sorbitol containing a preponderance of sorbitans with a fatty acid in the presence of an alkaline catalyst at a temperature from about 180° to about 215° C., the amount of said catalyst not exceeding the equivalent of about 1% of NaOH, based on product weight, thereby producing said sorbitan fatty acid ester or mixture thereof.

4,297,291
METHOD OF PREPARING THE METHYL ESTER OF
α-ELEOSTEARIC ACID

Joseph E. Lionelle, and Jeffrey A. Staffa, both of Salida, Colo., assignors to Bio Systems Research, Inc., Salida, Colo.

Filed Jun. 30, 1980, Ser. No. 164,567

Int. Cl.³ C09F 5/02; C11C 3/02

U.S. Cl. 260—410.9 R 13 Claims

1. A method of preparing the methyl ester of α-eleostearic acid which comprises:

providing a reaction mixture comprising tung oil, methanol, water and a saponification agent;

maintaining the temperature of said reaction mixture at a temperature of not more than about 35° C. for a time sufficient to effect saponification of said tung oil; acidifying the saponification reaction mixture while cooling to maintain temperature of the reaction mixture at not more than 35° C. to form an aqueous phase and a non-aqueous phase comprising α -eleostearic acid; separating said aqueous and non-aqueous phases; admixing said separated non-aqueous phase and methanol to form an esterification reaction mixture; heating said esterification reaction mixture in the presence of an acidic esterification catalyst to form an aqueous phase and a non-aqueous phase comprising the methyl ester of α -eleostearic acid; and separating said aqueous and non-aqueous phases of said esterification reaction mixture to provide a non-aqueous product phase comprising the methyl ester of α -eleostearic acid.

4,297,292

FRACTIONATION OF TRIGLYCERIDE MIXTURES

Ted J. Logan, Cincinnati, and Timothy A. Lubsen, Worthington, both of Ohio, assignors to The Procter & Gamble Company, Cincinnati, Ohio

Continuation-in-part of Ser. No. 43,394, May 25, 1979, abandoned. This application Mar. 26, 1980, Ser. No. 134,029
Int. Cl.³ C09F 5/10

U.S. Cl. 260—428.5

17 Claims

1. A process for separating a mixture of triglycerides with different Iodine Values and having their carboxylic acid moieties containing from 6 to 26 carbon atoms, to produce fractions of higher Iodine Value and lower Iodine Value, said process comprising the steps of

- contacting a solution of said mixture in solvent with macroreticular strong acid cation exchange resin to selectively adsorb triglyceride of higher Iodine Value and to leave in solution a fraction of said mixture enriched in content of triglyceride of lower Iodine Value,
- removing solution of fraction enriched in content of triglyceride of lower Iodine Value from contact with resin which has selectively adsorbed triglyceride of higher Iodine Value,
- contacting resin which has selectively adsorbed triglyceride of higher Iodine Value with solvent to cause desorption of adsorbed triglyceride and provide a solution in solvent of fraction enriched in content of triglyceride of higher Iodine Value,
- removing solution of fraction enriched in content of triglyceride of higher Iodine Value from contact with resin;

the solvent in step (a) and the solvent in step (c) being of the same or of different composition and being characterized by a solubility parameter (on a 25° C. basis) ranging from about 7.0 to about 15.0, a solubility parameter dispersion component (on a 25° C. basis) ranging from about 7.0 to about 9.0, a solubility parameter polar component (on a 25° C. basis) ranging from 0 to about 6.0 and a solubility parameter hydrogen bonding component (on a 25° C. basis) ranging from 0 to about 11.5; said resin having its exchangeable cation substituents consisting essentially of from about 3% to 100% of metal cation substituents capable of forming π complexes, the balance being metal ions incapable of forming π complexes; the solvent in step (a) and the solvent in step (c) and the percentage of metal cation substituents capable of forming π complexes being selected to provide selectivity in step (a) and desorption in step (c).

4,297,293

SODIUM ALUMOGLUCOHEPTONATE AND A PROCESS FOR ITS PREPARATION

Peter Suhac, Natasa Hafner-Milac, and Bozidar Dolenc, all of Ljubljana, Yugoslavia, assignors to LEK, tovarna farmacevtskih in kemskih izdelkov, n.s.o., Ljubljana, Yugoslavia

Filed Feb. 6, 1980, Ser. No. 118,952


Claims priority, application Yugoslavia, Feb. 14, 1979, 354/79

Int. Cl.³ C07F 5/06


U.S. Cl. 260—448 B

11 Claims

1. Sodium alumoglucoheptonate of the general formula



wherein Z represents a residue of the formula



wherein

R represents a residue of a molecule of sodium D-glycero-D-gulo-heptonate or of sodium D-glycero-D-ido-heptonate and

R₁ and R₂ represent moieties of a molecule of sodium D-glycero-D-gulo-heptonate or of sodium D-glycero-D-ido-heptonate,

Y represents a hydroxy group or three Y are joined to represent the residue Z.

2. A process for the preparation of sodium alumoglucoheptonate characterized in that a solution of sodium aluminate is added to the solution of sodium glucoheptonate in such a quantity that the ratio between the number of aluminum atoms and the number of sodium glucoheptonate molecules amounts to from 0.50:1 to 1.50:1.

4,297,294

PROCESS FOR MAKING 4,4'-METHYLENE DIPHENYL DIISOCYANATE

Frank D. Mango, Houston, Tex., assignor to Shell Oil Company, Houston, Tex.

Filed Sep. 29, 1980, Ser. No. 191,889

Int. Cl.³ C07C 118/02, 119/048

U.S. Cl. 260—453 PH

9 Claims

1. A process for the selective production of 4,4'-methylene diphenyl diisocyanate and corresponding oligomers, consisting essentially of the steps of:

- condensing formaldehyde with aniline under neutral or basic conditions to yield an anil condensate;
- reacting said anil condensate with aniline and a protonic salt of aniline under acidic conditions to yield an intermediate product selected from the group consisting of 4,4'-methylene dianiline, its corresponding oligomers and mixtures thereof; and
- reacting said intermediate product with phosgene to yield the corresponding diisocyanate or polyisocyanate.

4,297,295

N-(BENZENESULFONYL)

THIOCARBAMATES-HERBICIDAL ANTIDOTES

Edmund J. Gaughan, Berkeley, and Charles Kezerian, Orinda, both of Calif., assignors to Stauffer Chemical Company, Westport, Conn.


Division of Ser. No. 723,251, Sep. 17, 1976, abandoned, which is a continuation-in-part of Ser. No. 619,115, Oct. 2, 1975, abandoned. This application Dec. 31, 1979, Ser. No. 108,890

Int. Cl.³ C07C 155/02

U.S. Cl. 260—455 A

1 Claim

1. The compound having the formula



4,297,296

QUATERNIZED POLYAMINES

Hans-Peter Baumann, Ettingen, Switzerland, assignor to Sandoz Ltd., Basel, Switzerland

Filed Jun. 21, 1979, Ser. No. 50,881


Claims priority, application Switzerland, Jun. 26, 1978, 6933/78

Int. Cl.³ C07C 87/28, 87/29

U.S. Cl. 260—459 A

8 Claims

1. A quaternized polyamine having the basic structure of formula I



in which

each R, independently, is (C₁₀₋₂₂)alkyl, (C₁₀₋₂₂)alkenyl, phenyl(C₁₋₃)alkyl or naphthyl(C₁₋₃)alkyl, each R₁, independently, is phenyl(C₁₋₃)alkyl or naphthyl(C₁₋₃)alkyl, z is 1 to 5, each y₁, independently, is an integer from 2 to 8, y₂ is an integer from 2 to 8, with the proviso that when z = 1 y₁ ≠ y₂ and when z > 1 and the y₁'s are the same y₂ ≠ y₁ and wherein an average of 0.5 to 2.0 nitrogen atoms are quaternized with alkyl radicals containing from 1 to 6 carbon atoms.

4,297,297

 α -CYANO- β -(SUBSTITUTED-ANILINO)-N-ETHOXYCARBONYLACRYLAMIDE INTERMEDIATES

Clive A. Henrick; Jeffrey N. Labovitz, both of Palo Alto, Calif.; Roland T. V. Fox, Crowthorne, England; William G. Rathmell, Wokingham, England, and Margaret C. Shephard, Maidenhead, England, assignors to Zeecon Corp., Palo Alto, Calif. and Imperial Chemical Industries Limited, England


Division of Ser. No. 23,517, Mar. 23, 1979, Pat. No. 4,266,056, which is a continuation-in-part of Ser. No. 894,307, Apr. 7, 1978, abandoned, which is a continuation-in-part of Ser. No. 892,560, Apr. 3, 1978, abandoned. This application Jul. 18, 1980, Ser. No. 170,243

Int. Cl.³ C07C 121/78

U.S. Cl. 260—465 D

19 Claims

1. A compound of the following formula (III):



wherein,

R is hydrogen, methyl or ethyl;

R² is lower alkyl, lower alkoxy, bromo, chloro, fluoro, lower haloalkyl, cyano, nitro, lower alkylthio, hydroxy, lower alkylcarbonyl, lower alkoxy, lower haloalkoxy, cycloalkyl, cycloalkylthio, lower haloalkylthio, lower alkenyl or lower alkynyl;

R³ is hydrogen or independently selected from the values of R²;

R⁴ is hydrogen or independently selected from the values of R²; and

y is zero, one, two or three, provided that:

- when R is hydrogen, R² is bromo, and y is one—then either R³ or R⁴ is other than hydrogen and
- when R is hydrogen—then either R³ or R⁴ is other than hydrogen or y is one, two or three.

4,297,298

METHOD OF PREPARING STABLE DILUTE SOLUTIONS OF ALIPHATIC CARBOXYLIC PERACIDS, AND THE RESULTING SOLUTIONS

Francois Crommelynck, Saint Martin Le Vinoux; Michel Granger, Chalon-sur-Saone; Michel Rio, Elancourt, and Jacques Tourdot, Paris, all of France, assignors to L'Air Liquide, Societe Anonyme pour l'Etude Procédés Georges Claude, Paris, France

Filed Jul. 22, 1980, Ser. No. 171,047

Claims priority, application France, Aug. 1, 1979, 79 19761

Int. Cl.³ C07C 279/10

U.S. Cl. 260—502 R

14 Claims

1. A method of preparing a dilute solution, containing a rated concentration between 1 and 20% by weight, of an aliphatic carboxylic peracid with a stable concentration titer in time, notwithstanding the possible presence of trace amounts of decomposition catalysts, comprising the steps of:

preparing a concentrated solution of aliphatic peracid from the corresponding carboxylic acid or anhydride and hydrogen peroxide in a concentration of between 60 and 90% in the presence of the substantially minimal amount of a strong acid catalyst necessary to obtain equilibrium of the system in a maximum period of 48 hours; and diluting the concentrated solution of aliphatic peracid, prepared in said preparing step, with a solution containing at least one of the reagents used in said preparing step in an amount and concentration sufficient to bring the concentration of aliphatic peracid at least to the rated concentration of the mixture and such that (a) the maximum concentration of peracid during storage at ambient temperature is at most 10% above the rated concentration of peracid and (b) the concentration after storage for 12 months is at least equal to the rated concentration of aliphatic peracid.

4,297,299
NOVEL

N-(ALKYL)-N-(2-HALOETHYL)-AMINOMETHYLPHOSPHONIC ACIDS, A METHOD FOR THE PREPARATION THEREOF AND THEIR USE IN THE PREPARATION OF STARCH ETHER DERIVATIVES

Martin M. Tessler, Edison, N.J., assignor to National Starch and Chemical Corporation, Bridgewater, N.J.


Division of Ser. No. 110,926, Jan. 10, 1980, Pat. No. 4,260,738, which is a continuation-in-part of Ser. No. 66,526, Aug. 15, 1979, Pat. No. 4,243,479. This application Aug. 29, 1980, Ser. No. 182,547

Int. Cl.³ C07F 9/38

U.S. Cl. 260—502.5

3 Claims

1. As a composition of matter, a compound of the general structure

wherein X is a halogen, M is a cation, and R₁ is a C₁-C₆ group or a C₃-C₆ cycloalkyl group.

4,297,300

NOVEL α-HALOALKYLCARBAMIC ACID HALIDES, AND A PROCESS FOR THE PREPARATION OF α-HALOALKYLCARBAMIC ACID HALIDES

Karl-Heinz Koenig, Frankenthal, and Karl-Heinz Feuerherd, Ludwigshafen, both of Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Fed. Rep. of Germany

Filed Jun. 25, 1979, Ser. No. 51,744


Claims priority, application Fed. Rep. of Germany, Jul. 14, 1978, 2830969

Int. Cl.³ C07C 53/50

U.S. Cl. 260—544 C

1 Claim

1. An α-haloalkylcarbamic acid halide of the formula

where R¹, R² and R³ may be identical or different and each is cycloalkyl of 5 or 6 carbon atoms, R¹ and R² together with the adjoining carbon or R² and R³ together with the two adjoining carbons may also be members of a monocyclic or bicyclic alicyclic ring of 5 to 9 carbon atoms, one or two of R¹, R² and R³ may also be hydrogen, and X is halogen.

4,297,301

PROCESS FOR THE MANUFACTURE OF ORGANIC ACID CHLORIDES

Serge L. Lecolier, Janville sur Juine, and Jean-Pierre G. Senet, La Chapelle la Reine, both of France, assignors to Societe Nationale des Poudres et Explosifs, Paris, France

Filed Nov. 23, 1979, Ser. No. 96,657


Claims priority, application France, Nov. 29, 1978, 78 33670; Aug. 30, 1979, 79 21730

Int. Cl.³ C07C 51/60

U.S. Cl. 260—544 K

15 Claims

1. Process for the manufacture of a carboxylic acid chloride which consists of phosgenating at a temperature of 90°-150° C., the corresponding acid or acid anhydride in the presence of a catalyst, wherein the catalyst is at least one member selected from the group consisting of compounds of formula (I)

in which X is oxygen or nitrogen which is monosubstituted by R₅, which is an alkyl containing from 1 to 6 carbon atoms, and in which formula R₁, R₂, R₃ and R₄ are all different, or at least two of them are the same, and are hydrogen or an organic radical which contains at most 20 carbon atoms and wherein the proportion of the catalyst relative to said acid or anhydride, is between 0.01 and 10% by weight.

4,297,302

BUTTERFLY THROTTLE VALVE WITH A RAISED UPPER LIP

Ken Nakamura, Kawasaki; Hiromichi Ofuji, Yokohama, and Junichi Yokoyama, Ebina, all of Japan, assignors to Nissan Motor Company, Limited, Yokohama, Japan


Filed Oct. 3, 1979, Ser. No. 81,432

Claims priority, application Japan, Oct. 7, 1978, 53-137328[U]

Int. Cl.³ F02M 3/08

U.S. Cl. 261—65

1 Claim



1. In an air-fuel mixture supply device for an internal combustion engine having an intake passage into which fuel is supplied: a disk-shaped butterfly throttle valve rotatably mounted on a valve shaft in the intake passage below the position where fuel is supplied thereto, said throttle valve having an essentially flat upstream face which has an upstream part and a downstream part, a groove formed in said essentially flat upstream face and extending adjacent the entire outer periphery of said throttle valve essentially parallel to said outer periphery of the throttle valve; and an outlet passage formed on said downstream part of said upstream face and extending from said groove to the outer periphery, whereby fuel trickling onto the upstream face of said throttle is directed into said groove and guided to the downstream part of said upstream face and discharged to air flow passing through a clearance formed between the inner periphery of said intake passage and the downstream part of said throttle valve to be effectively atomized.

4,297,303

PREPARATION AND REACTION OF ENERGY PRODUCING WASTE MATERIAL COMPOSITION

Paul A. Deardorff, 1128 Dix, Lincoln Park, Mich. 48146; Robert C. Wood, 36002 Huron River Dr., New Boston, Mich. 48164, and Sante M. Cundari, 530 Woodcrest, Dearborn, Mich. 48124

Division of Ser. No. 901,492, May 1, 1978, Pat. No. 4,208,226. This application Jan. 14, 1980, Ser. No. 111,724

Int. Cl.³ C06B 21/00

U.S. Cl. 264—3 R

16 Claims

16. A method for preparing a composition for the production of heat comprising the steps of:

- mixing an iron-containing waste by-product with a mineral acid, said iron containing waste by-product including an iron oxide,
- adding any water required to make the substance pliable,
- adding a reducing metal,
- then molding the composition and letting it stand.

4,297,304

METHOD FOR SOLIDIFYING AQUEOUS RADIOACTIVE WASTES FOR NON-CONTAMINATING STORAGE

Knut Scheffler, Eggenstein-Leopoldshafen, and Ulrich Riege, Linde-Hochstetten, both of Fed. Rep. of Germany, assignors to Kernforschungszentrum Karlsruhe, GmbH, Karlsruhe, Fed. Rep. of Germany

Filed Jun. 9, 1978, Ser. No. 914,152

Claims priority, application Fed. Rep. of Germany, Jun. 10, 1977, 2726087

Int. Cl.³ G21C 21/00

U.S. Cl. 264—0.5

24 Claims

1. Method for solidifying high radioactivity aqueous waste concentrates, medium radioactivity aqueous waste concentrates, actinide containing aqueous waste concentrates, or suspensions of fine-grained solid wastes suspended in water, which concentrates or suspensions contain a metal ion and/or metal oxide, for final noncontaminating storage in which the waste concentrates or the suspensions are subjected together with an absorbing and/or hydraulically binding inorganic material, to a ceramic firing process so as to produce a solid sintered body, comprising the steps of:

- treating the waste concentrates or suspensions by evaporation, to form an evaporate, to a water content in the range between 40 and 80 percent by weight and a solid content whose metal ion and/or metal oxide concentration lies between 10 and 30 percent by weight of the evaporate being formed, and adjusting the pH of the evaporate to between 5 and 10;
- kneading the evaporate obtained from step (a) with a clay-like substance containing a small quantity of cement or mixture of a clay-like substance with a small quantity of cement containing an additive for suppressing the volatility of alkali metals or alkaline earth metals which may be present in the evaporate and/or an additive for suppressing the volatility of any decomposable anions which may be present in the evaporate selected from the group consisting of sulfate, phosphate, molybdate and uranate ions, at a weight ratio range of evaporate to clay-like substance of 1:1 to 2:1, said clay-like substance being at least one substance selected from the group consisting of pottery clays, stoneware clays, porcelain clay mixtures and kaolins;
- producing molded bodies from the kneaded mass obtained from step (b);
- heat treating the molded bodies, including drying at temperatures between room temperature and 150° C., calcining at temperatures of about 150° to 800° C., and subsequently firing at temperatures between 800° and 1400° C. to form practically undissolvable mineral phases having a chemical composition corresponding approximately to that of natural, stable minerals or rocks; and
- enclosing the molded bodies containing the fired mineral phases on all sides in a dense, continuous ceramic or metallic matrix.

4,297,305

NUCLEAR FUEL RECYCLING SYSTEM

Harvey R. Lee, Omamee; Arnold K. Koch, Etobicoke, and Adam Krawczyk, Mississauga, all of Canada, assignors to Canadian General Electric Company Limited, Toronto, Canada

Filed Jul. 26, 1979, Ser. No. 60,884

Int. Cl.³ G01C 21/00

U.S. Cl. 264—0.5

6 Claims

1. The method of producing nuclear fuel comprising re-

trieved nuclear fuel material selected from the group comprising substantially uncontaminated grinding swarf, sintered pellets and green pellet forms, including the steps of:

- crushing pelleted material to fine powder in a substantially inert atmosphere;
 - mixing with grinding swarf and liquid to form a slurry having a content between about 70 to 85 weight percent solids;
 - adding sintered UO₂ pellets as grinding media to the slurry within a wet mill and
 - wet grinding the slurry with the pellets in the wet mill, to a predetermined consistency.
2. The method as claimed in claim 1 including the steps of drying said ground slurry to a powder, and recycling the powder for manufacture to pellet form.

4,297,306

NECK ORIENTING METHOD OF BOTTLES OF SATURATED POLYESTER RESINS


Yataro Yoshino; Sadao Suzuki, and Takuzo Takada, all of Tokyo, Japan, assignors to Yoshino Kogyosho Co., Ltd., Tokyo, Japan

Filed Nov. 7, 1979, Ser. No. 92,428

Int. Cl.³ B29C 17/02, 17/07

U.S. Cl. 264—23

8 Claims



1. A method of forming the neck portion of a synthetic resin bottle, the method comprising the steps of:

- forming a parison of synthetic resin, the parison having a neck portion and an outwardly projecting lip at the upper outer circumferential end of the neck portion;
- heating the neck portion of the parison to an orientable temperature;
- holding the parison so that the outwardly projecting lip is retained by a plurality of radially extending arms, said arms being movable back and forth on a horizontal plane;
- inserting an orienting rod into the neck portion of the parison, the orienting rod having a converging tapered head and a straight body portion, the straight body portion being of a diameter greater than the diameter of the neck portion prior to insertion of the orienting rod, the neck portion being radially stretched thereby; and
- moving the arms radially outwardly as the tapered portion of the orienting rod is inserted into the neck portion of the parison whereby said arms continue to hold the parison as the neck portion thereof is radially stretched.

4,297,307

PROCESS FOR PRODUCING CARBON-CARBON FIBER COMPOSITES SUITABLE FOR USE AS AIRCRAFT BRAKE DISCS

Gordon J. Taylor, Hinckley, Ohio, assignor to Union Carbide Corporation, New York, N.Y.

Filed Jun. 29, 1979, Ser. No. 53,535

Int. Cl.³ B29C 25/00; B29D 3/02

U.S. Cl. 264—29.5

16 Claims

1. A process for producing carbon-carbon fiber composites of high strength which comprises forming an aqueous gelled mixture containing between about 5 and 15% by weight chopped carbonaceous fibers and a water-soluble binder-thickening agent selected from the group consisting of polyethylene

oxide, ethyl methyl cellulose, hydroxyethyl cellulose, hydroxyethyl methyl cellulose, hydroxypropyl methyl cellulose, methyl cellulose, polyacrylamid, polyvinyl alcohol, polyvinyl methyl ether, starch and gelatin, said binder-thickening agent having a viscosity of at least about 10,000 centipoises at 25° C., extruding the gelled mixture into the form of a continuous elongated ribbon wherein the individual carbon fibers are aligned substantially in the direction of fluid flow, arranging said elongated ribbon in a spiral pattern to form a flat disc shaped article, drying said article to remove water, heating the dried article to a temperature of at least about 300° C. and then impregnating said article with a liquid thermosetting resin binder followed by heating said article under pressure in a mold to a temperature of at least about 1200° C.

4,297,308

METHOD OF MANUFACTURING GAMES RACKETS

Frank W. Popplewell, Essex, England, assignor to Dunlop Limited, London, England


Filed Feb. 28, 1979, Ser. No. 15,912

Claims priority, application United Kingdom, Mar. 7, 1978, 8925/78

Int. Cl.³ B29C 1/14; B29D 23/02, 27/00

U.S. Cl. 264—46.6

7 Claims



1. A method of making a frame for a games racket, said frame comprising a head and a shaft, in which at least said head is a molding formed by the steps of placing a fusible core material in a mold, said fusible core material containing holes oriented in a radial direction from the center of said mold, placing a plurality of pins in said injection mold, said pins passing centrally through at least some of the holes in said core material, said pins having a smaller diameter than said holes, injecting a thermoplastics material into said mold around said fusible core, said core having a melting point below the injection temperature, the holes of said core causing the injected thermoplastics material to form internal support means between the wall of said molding that is to lie at the outer circumference of said head and that wall of said molding that is to lie at the inner circumference of said head, at least some of said support means being hollow due to the presence of said pins, allowing said molding to set, removing said pins from the core, raising the temperature of said molding to an amount sufficient to melt said core but insufficient to melt or deform said molding, and, removing the molten core from said molding.

4,297,309

PROCESS OF USING AND PRODUCTS FROM FUME AMORPHOUS SILICA PARTICULATES

John W. North, 1520 Farnell Ct., Apt. 533, Decatur, Ga. 30033
Continuation-in-part of Ser. No. 965,233, Dec. 1, 1978, abandoned. This application Jun. 25, 1980, Ser. No. 162,802

Int. Cl.³ C04B 35/14

U.S. Cl. 264—56

45 Claims

1. Process of producing an amorphous silica product comprising:

- (a) mixing fume amorphous silica material and water to produce a plastic mixture wherein said silica material consists essentially of stack gas particulate issuing from

an electric furnace producing silicon metal by the reduction of silica with carbon;
(b) shaping said plastic mixture into a prescribed shape; and
(c) drying the shaped plastic mixture.

4,297,310

PROCESS FOR PRODUCING ELECTRIC CONDUCTORS COATED WITH CROSSLINKED POLYETHYLENE RESIN

Susumu Akutsu; Tsutomu Isaka, and Mitsugu Ishioka, all of Yokkaichi, Japan, assignors to Mitsubishi Petrochemical Co., Ltd., Tokyo, Japan

Filed Nov. 13, 1979, Ser. No. 93,126

Claims priority, application Japan, Nov. 13, 1978, 53/139707
Int. Cl.³ B29F 3/10; C08G 77/20

U.S. Cl. 264—83

8 Claims

1. A process for producing electric conductors coated with a crosslinked polyethylene resin which comprises fabricating a coated electric conductor having an extrusion-coated layer of a polyethylene resin comprising a random copolymer on a conductor, the copolymer comprising predominantly units of ethylene monomer and an unsaturated silane monomer represented by the formula $RSiR'_nY_{3-n}$, wherein: R is a member selected from the group consisting of ethylenically unsaturated hydrocarbyl and hydrocarbyloxy groups; R' is an aliphatic saturated hydrocarbyl group; Y is a hydrolyzable organic group; and n is zero, 1, or 2, and subjecting the coated conductor to a crosslinking process step comprising causing the coated conductor to contact water in the presence of a silanol condensation catalyst, said random copolymer having been produced by the polymerization of said monomers in the presence of a radical initiator under elevated pressure.

4,297,311

METHOD OF MANUFACTURING IMPROVED MINERAL BOARD


Norman Sherman, Ramsey, and John H. Cameron, St. Paul, both of Minn., assignors to Conwed Corporation, St. Paul, Minn.

Continuation of Ser. No. 967,217, Dec. 7, 1978, abandoned. This application Oct. 17, 1979, Ser. No. 85,501

Int. Cl.³ B29J 1/00

U.S. Cl. 264—109

33 Claims



1. A method of manufacturing a mineral product comprising the sequential steps of:

- (a) forming an admixture comprising perlite and a resin binder therefor, at least 75% by weight of the solids content of said admixture being composed of the perlite/resin binder combination, the perlite being in the expanded form and having an initial average bulk density no greater than about 10 pounds per cubic foot, the said perlite/resin binder combination containing by weight from about 50% to about 95% perlite and from about 5% to about 50% resin binder where the expanded perlite is derived from an active perlite, and the said perlite/resin binder combination containing by weight from about 60% to about 95%

perlite and from about 5% to about 40% resin binder, where the expanded perlite is derived from an inactive perlite;
(b) mixing said admixture;
(c) forming a shaped product from said admixture;
(d) subjecting said shaped product to pressure to form it into its final shape, said pressure being sufficient to reduce the bulk volume of the perlite by a crushing factor of at least about;
(i) where the expanded perlite has been derived from an active perlite:
(1) $y = 6.5 - 0.26x$ where x is from about 5 to about 15
(2) $y = 3.1 - 0.035x$ where x is from about 15 to about 50
(ii) where the expanded perlite has been derived from an inactive perlite:
(3) $y = 2.3 - 0.03x$ where x is from about 5 to about 40
wherein in each of formulas (1), (2) and (3): y is the crushing factor and x is the percent by weight of binder in the perlite/resin binder combination; and, thereafter,
(e) curing the resin binder.

4,297,312

METHOD FOR PREPARING STYLUS LAPPING DISCS


Charles B. Carroll, Trenton, and Howard G. Scheible, Livingston, both of N.J., assignors to RCA Corporation, New York, N.Y.

Filed Feb. 4, 1980, Ser. No. 118,088

Int. Cl.³ B32B 3/26; B29C 1/02; B28B 19/00

U.S. Cl. 264—134

4 Claims



1. In a method of replicating a groove pattern in the formation of a lapping disc comprising the steps of:
1. recording the pattern in a photoresist layer,
2. developing the photoresist layer to form a photoresist master,
3. transferring the pattern of the photoresist master to a metal matrix master pattern by coating the photoresist master with a metal to form an electroform, and separating the electroform from the photoresist master to produce the said metal matrix master pattern, and
4. replicating the metal matrix master pattern in the surface of a plastic article;

the improvement which comprises the step of forming concave junctions on the metal matrix master by filling in material at the intersections of the walls and base portions of the metal matrix master.

4,297,313

METHOD FOR MANUFACTURING A PACIFIER

Stuart S. Duckstein, 111 Tall Oaks Dr., Wayne, N.J. 07470
Division of Ser. No. 934,673, Aug. 18, 1978, Pat. No. 4,195,638.

This application Jul. 30, 1979, Ser. No. 62,114


Int. Cl.³ B29C 6/02

U.S. Cl. 264—273

2 Claims

1. A process for making a pacifier comprising the steps of:
(a) forming a rigid shield having a centrally disposed hole and an array of holes concentrically arranged around the centrally disposed hole;
(b) locating the rigid shield member in an injection molding cavity configured in the form of a pacifier which has a ring, nipple, and shield, said shield being located in a

section of the cavity between the ring and nipple section with the holes in the shield arranged to provide communication between the ring and nipple sections of the cavity;
(c) locating an interference member within the cavity spaced apart from the edge of the centrally disposed hole in the



rigid shield and extending axially from the rigid shield through the ring section and into the nipple section; and
(d) injecting material from the group comprising thermosetting and thermoplastic material into the cavity to fill the ring and nipple section and to pass through the holes of the shield to retain the shield captive.

4,297,314

METHOD FOR PERMANENT DEFORMATION OF AN ELASTIC MEMBER

Waldemar Schmidt, Waiblingen, Fed. Rep. of Germany, assignor to Robert Bosch GmbH, Stuttgart, Fed. Rep. of Germany


Filed Nov. 27, 1978, Ser. No. 963,710

Claims priority, application Fed. Rep. of Germany, Dec. 1, 1977, 2753541

Int. Cl.³ B29C 17/03; B29D 23/10; B29H 5/01, 5/16

U.S. Cl. 264—320

1 Claim



1. A method for producing a permanently deformed flexible diaphragm, comprising the steps of:

applying to a permanently deformable flexible diaphragm essentially consisting of a coated rubberized web intended for use as a valve closing member, distending forces to selected parts of a diaphragm which parts are to be displaced out-of-plane thereof to produce a dish-shaped depression in the diaphragm;

applying heat to only said selected parts of the diaphragm which are subjected to the out-of-plane distending forces and while cooling only parts, other than said selected parts, of the diaphragm which are free from distending forces including passing of a cooling medium through channels in a base plate and in a cover plate confining the diaphragm therebetween.

4,297,315

METHOD OF MAKING WIG ARCHETYPE

Goro Kasai, Ichikawa; Sanjuro Takechi, and Hiroshi Harima, both of Hasaki, all of Japan, assignors to Kuraray Company, Ltd., Kurashiki, Japan

Filed Dec. 27, 1979, Ser. No. 107,564

Claims priority, application Japan, Dec. 29, 1978, 53/161914
Int. Cl.³ B29C 17/00

U.S. Cl. 264—322

8 Claims

1. A method for making a wig archetype to the shape of the human head, comprising:

- softening a sheet of a thermoplastic composition comprising polyisoprene, said polyisoprene having at least 90% of the isoprene monomer units in the trans-1,4 configuration and an intrinsic viscosity of 1.2 to 3 when measured in toluene at 30° C., said sheet having a thickness from 0.5 to 4.0 millimeters and said thermoplastic composition being sufficiently transparent when held to the head to allow registering of the hair distribution;
- applying the sheet to the scalp of a human head, shaping said sheet to the shape of said human head and registering the distribution of the hair thereon by marking the location of the hair while said sheet is in contact with said human head;
- hardening the sheet whereby the thermoplastic composition clearly shows the registered hair density distribution after hardening; and
- removing the sheet from the scalp.

4,297,316

MAINTAINING THE DIMENSIONAL INTEGRITY OF THERMOPLASTIC TUBING ENDS FOR RECEIVING A LUER


Joel Cunningham, Del Mar, Calif., assignor to Baxter Travenol Laboratories, Inc., Deerfield, Ill.

Filed Jan. 7, 1980, Ser. No. 110,261

Int. Cl.³ A61L 2/04

U.S. Cl. 422—1

3 Claims



1. A method of maintaining the dimensional integrity of an end of thermoplastic tubing having a normal uniform interior diameter which undergoes dimensional distortion at a temperature sufficient to effect heat sterilization treatment thereof, said method comprising the steps of

- rigidly supporting with a thermosetting member the interior portion of the tubing end at a diameter which is generally equal to the normal interior diameter thereof,
- compressing with a thermosetting member the exterior portion of the tubing end inwardly toward the rigidly supported interior portion thereof, and
- exposing the tubing to the temperature sufficient to effect heat sterilization treatment thereof.

4,297,317

LOW LEVEL CHROMATE-BASED CORROSION INHIBITION IN AQUEOUS MEDIUMS

Frederick G. Vogt, deceased, late of Philadelphia, Pa. (by Mary J. Vogt, executrix), and Patricia T. Sparrell, Freehold, N.J., assignors to Betz Laboratories, Inc., Trevose, Pa.

Filed Mar. 28, 1980, Ser. No. 134,812


Int. Cl.³ C23F 11/12, 11/14, 11/18

U.S. Cl. 422—16

20 Claims

1. A method for reducing the amount of corrosion of metal surfaces in contact with an aqueous medium comprising adding to said aqueous medium an effective amount for the purpose of a zinc-free and phosphate-free treatment consisting essentially of effective:

- water-soluble chromate, and
- water-soluble polymer comprising moieties derived from acrylic acid or water-soluble salt thereof and moieties of hydroxylated lower alkyl acrylate, wherein the moieties of said polymer have the following formulas:



where R is hydrogen or a lower alkyl of from 1 to 3 carbon atoms; R₁ is OH, NH₂ or OM where M is a water-soluble cation; R₂ is a lower alkyl of from about 2 to 6 carbon atoms; R₃ is H or lower alkyl of from 1 to 3 carbon atoms and the mole ratio of x:y is 1:4 to 36:1, wherein said water soluble chromate is added in an amount of from about 0.5 to about 150 parts of active chromate per million parts of said aqueous medium.

4,297,318

BLOOD OXYGENATOR


Donald A. Raible, Santa Ana, Calif., assignor to Bentley Laboratories, Inc., Irvine, Calif.

Continuation-in-part of Ser. No. 823,149, Aug. 9, 1977, which is a continuation-in-part of Ser. No. 689,971, May 26, 1976, Pat. No. 4,268,476, which is a continuation-in-part of Ser. No. 584,464, Jun. 6, 1975, abandoned, and a continuation-in-part of Ser. No. 689,971. This application Jul. 2, 1979, Ser. No. 54,268

The portion of the term of this patent subsequent to May 19, 1998, has been disclaimed.
Int. Cl.³ A61M 1/03

U.S. Cl. 422—46

18 Claims



1. Apparatus for oxygenating blood comprising: means for combining oxygen-containing gas with liquid blood to form a

mixture of blood and gas, a substantial portion of said mixture being in the form of bubbles; means defining a flow path for the mixture; means in the flow path defining a passageway configured in a manner capable of imparting rotational movement to at least a portion of the bubbles, said passageway having a transverse dimension large enough to permit rotation of the bubbles; and defoaming means downstream of said passageway.

4,297,319

APPARATUS FOR REMOVING NITROGEN OXIDES FROM FLUE GAS

Yoji Ishibashi; Yoshihiro Uchiyama, both of Hitachi; Hidetoshi Akimoto, Tokaimura, and Makoto Sasaki, Morioka, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed Dec. 6, 1978, Ser. No. 967,052

Claims priority, application Japan, Dec. 7, 1977, 52-146021

Int. Cl.³ B01J 8/02; F01N 3/08, 3/28

U.S. Cl. 422—114

7 Claims



1. An apparatus for removing nitrogen oxides from a combustion flue gas, which comprises a flue gas duct for passing a combustion flue gas containing nitrogen oxides therethrough, means for adding ammonia and hydrogen peroxide into the flue gas passing through the flue gas duct, thereby reducing the nitrogen oxides in the flue gas in a gas phase, catalyst means comprised of a metallic oxide system for further reducing the remainder of nitrogen oxides, by directly contacting the flue gas, provided in the flue gas duct downstream of said means for adding ammonia and hydrogen peroxide to the flue gas duct and cooling means for cooling the catalyst means being provided within the catalyst means; the means for adding ammonia and hydrogen peroxide into the flue gas comprising one injector means for the ammonia and another injector means for the hydrogen peroxide.

4,297,320

COATING POLYMERIZATION REACTORS WITH THE REACTION PRODUCTS OF THIODIPHENOLS AND A BLEACH

Louis Cohen, Avon Lake, Ohio, assignor to The B. F. Goodrich Company, Akron, Ohio


Continuation-in-part of Ser. No. 34,106, Apr. 30, 1979, abandoned. This application Jun. 23, 1980, Ser. No. 161,711

Int. Cl.³ B01J 19/00; B05D 7/22; C08F 2/00

U.S. Cl. 422—131

16 Claims

1. A process for substantially eliminating the buildup of polymers on the internal surfaces of a polymerization reaction vessel which comprises applying to said surfaces an aqueous coating solution having a pH in the range of about 7.5 to about 13.0 and containing the reaction product of a thiodiphenol and a chlorine containing bleaching agent, said thiodiphenol having the general structure




wherein R is selected from the group consisting of —S—, and



R' is selected from the group consisting of —H, —OH, and an alkyl group containing from 1 to 4 carbon atoms, and R'' is —H or —Cl, and conducting the polymerization of monomer(s) while in contact with the coated internal surfaces of said vessel.

14. A polymerization reaction vessel having on all the internal surfaces thereof a coating comprised of the reaction product of a thiodiphenol and a chlorine containing bleaching agent, said thiodiphenol having the general structure



wherein R is selected from the group consisting of —S—, and



R' is selected from the group consisting of —H, —OH, and an alkyl group containing from 1 to 4 carbon atoms, and R'' is —H, or —Cl, and wherein the coated surfaces are characterized by having a critical surface tension of at least 72 dynes/cm² and a contact angle with water of about zero.

4,297,321

APPARATUS HAVING MAIN AND AUXILIARY FLUIDIZED BEDS THEREIN

Jaroslav Beranek, Prague, Czechoslovakia, assignor to Ceskoslovenska Akademie Ved, Prague, Czechoslovakia


Filed Apr. 8, 1980, Ser. No. 138,323

Claims priority, application Czechoslovakia, Apr. 10, 1979, 2441-79

Int. Cl.³ B01J 8/28, 8/44; F27B 15/08

U.S. Cl. 422—143

4 Claims



1. Apparatus for feeding solid particles at multiple points of a fluidized bed, comprising:


- a housing means having a main chamber for formation of a main fluidized bed of solid particles therein, the bottom of said main chamber comprising a main grid for the distribution of a fluidization fluid to said main fluidized bed;
- said housing means having a first space below and communicating with said main grid for receiving a fluidization fluid;
- an inlet to said first space for introduction of a fluidization fluid thereto;

said housing means having an auxiliary chamber below said first space for formation of an auxiliary fluidized bed of solid particles therein, the bottom of said auxiliary chamber comprising an auxiliary grid for the distribution of a fluidization fluid to said auxiliary fluidized bed; an inlet to said auxiliary chamber for introduction of solid particles thereto; said housing means having a second space below and communicating with said auxiliary grid for receiving a fluidization fluid; an inlet to said second space for introduction of a fluidization fluid thereto; and a system of inlet pipes extending between said auxiliary chamber and the lower portion of said main chamber for transporting said solid particles from the auxiliary fluidized bed to the main fluidized bed.

4,297,322

EQUIPMENT FOR TREATING AND RESOURCE RECOVERY FROM SOLID WASTE

Hsin Liu, 40-25 Hampton St., Elmhurst, N.Y. 11373
Division of Ser. No. 827,693, Aug. 25, 1977, Pat. No. 4,204,906.
This application Mar. 11, 1980, Ser. No. 129,609
Int. Cl.³ B01D 9/00, 11/00; B01F 9/08, 15/02
U.S. Cl. 422—184 18 Claims




1. An equipment for treating a solid waste containing fibrous combustible matters and fusible plastics comprising:
means for heating said equipment to provide therein a vertically elongated, heating zone;
means for feeding said solid waste to a top portion of said heating zone and dropping said solid waste into said heating zone, said solid waste falling freely under gravity inside said zone;
during the free gravitational fall through said heating zone said solid waste being heated to a treatment temperature sufficiently high to fuse said fusible plastics and also to exceed the combustion temperature of said fibrous combustible matters in air;
means for establishing in said heating zone a gaseous atmosphere which will not support combustion of said fibrous combustible matters at said treatment temperature; and
means for providing a separating force having at least a horizontal component to separate said falling and fusing plastics from said falling fibrous combustible matters.

4,297,323

PRESSURE VESSEL HAVING QUICK-ACTION LOCKING MEANS

Karl-Heinz Tetzlaff, Kelkheim; Wilhelm Riemenschneider, Frankfurt am Main, and Günter Leuschner, Schwalbach, all of Fed. Rep. of Germany, assignors to Hoechst Aktiengesellschaft, Frankfurt am Main, Fed. Rep. of Germany
Filed Aug. 27, 1980, Ser. No. 181,807
Claims priority, application Fed. Rep. of Germany, Aug. 29, 1979, 2934789
Int. Cl.³ B01J 3/03, 3/04
U.S. Cl. 422—208 9 Claims



1. A pressure vessel having quick-action locking means therefor which comprises a holder to which the top of the pressure vessel containing connections and/or measuring equipment is rigidly mounted, a presser, and a sliding spacer device positioned between the detachable lower part of the pressure vessel and the presser; the top of the pressure vessel and the lower part thereof positioned on the spacer device being tightly compressed by the presser.


4,297,324

APPARATUS FOR THE CONTINUOUS PROCESSING OF COMPOUNDS IN A LIQUID

Henri Sauvage, and Maurice Tarnero, both of Bagnols sur Ceze, France, assignors to Commissariat a l'Energie Atomique, Paris, France
Filed Nov. 24, 1980, Ser. No. 209,601
Claims priority, application France, Dec. 18, 1979, 79 30951
Int. Cl.³ B01D 11/02
U.S. Cl. 422—268 10 Claims

1. An apparatus for processing compounds in a liquid, wherein it is constituted by a helical vibrating elevator having a cylindrical tank with a vertical axis, a fixed cover, an annular helical ramp fixed to the tank wall, means for imparting a reciprocating movement about its axis and in a vertical plane to the ramp, said movement being such that the rotation speed of the ramp in one direction exceeds the rotation speed thereof in the opposite direction, at least one liquid supply pipe in the cover, at least one lateral discharge opening for the liquid in

the tank, a supply chute for supplying the compounds carried by the cover and whose axis coincides with that of the tank and



a discharge chute for discharging the compounds located at the top of the helical ramp and in an extension of the latter.

4,297,325

METHOD OF PRODUCING PSEUDOBOEHMITE FROM ALUMINUM SALT SOLUTIONS

Julius Scherzer, Anaheim; Anh-Thu Liu, Santa Ana, and Yih-Yau Sun, Montebello, all of Calif., assignors to Filtrol Corporation, Los Angeles, Calif.
Filed Dec. 8, 1980, Ser. No. 214,215
Int. Cl.³ C01F 7/34 7 Claims

U.S. Cl. 423—122

1. A method for producing pseudoboehmite from aluminum sulfate solutions containing Fe^{+++} , and alkaline earth ions which comprises adding a reducing agent and reducing Fe^{+++} to Fe^{++} without precipitating compounds of the Fe, or alkaline earth ions and then adjusting the pH in the range of about 4 to about 5 to form alumina hydrate gel without precipitating any substantial quantities of Fe or alkaline earth compounds, separating the gel from the leach solution aging the gel at a pH in excess of about 9 and forming pseudoboehmite substantially free of Fe and of alkaline earth cations.

4,297,326

METHOD OF PRODUCING A PURE ALUMINIUM OXIDE FROM SOLUTIONS CONTAINING DISSOLVED IONS OF ALUMINIUM AND IRON

Norvald Gjelsvik, Oslo, and Ingleif Hundere, Frogner, both of Norway, assignors to Elkem-Spigerverket a/s, Oslo, Norway
Filed Feb. 4, 1980, Ser. No. 118,601
Claims priority, application Norway, Feb. 13, 1979, 790460
Int. Cl.³ C01F 7/22 1 Claim

U.S. Cl. 423—126

1. A method of continuously producing hexahydrated aluminium chloride which on calcining forms an aluminium oxide with a ferric oxide content of less than 0.05% from an ore containing aluminium and iron constituents comprising:

- (a) treating a first quantity of said ore with sulfuric or hydrochloric acid or a mixture thereof to form a solution comprising aluminium and iron ions;
- (b) treating the solution of step (a) with hydrochloric acid gas to form a precipitate of hexahydrated aluminium chloride and to form a mother liquor containing iron ions;
- (c) treating a further quantity of said ore with said mother liquor to form a further solution comprising aluminium and iron ions, the iron ions being present in approximately the cumulative of their presence in the first and the further quantity of ore;
- (d) treating said further solution with hydrochloric acid gas

to form a precipitate of hexahydrated aluminium chloride and to form a mother liquor containing iron ions;
(e) continuing the treatment of further quantities of said ore in the manner of steps (c) and (d) and with the amount of iron ions in said mother liquor being between 8 and 28 grams per liter; and
(f) calcining the hexahydrated aluminium chloride to aluminium oxide with a ferric oxide content of less than 0.05%.

4,297,327

METHOD OF PRECIPITATION OF PURE ALUMINIUM CHLORIDE FROM SOLUTIONS WHICH CONTAIN IONS OF ALUMINIUM AND MAGNESIUM

Norvald Gjelsvik, Oslo; Gunnar Hannestad, Skedsmo; Ingleif Hundere, Frogner, and Jan H. Torgersen, Skjetten, all of Norway, assignors to Elkem-Spigerverket A/S, Oslo, Norway
Filed Feb. 4, 1980, Ser. No. 118,602
Claims priority, application Norway, Feb. 13, 1979, 790458
Int. Cl.³ C01F 7/22, 7/30 4 Claims

U.S. Cl. 423—126

1. A method of producing aluminium chloride hexahydrate with a low content of magnesium from hydrochloric acid solutions containing aluminium and magnesium comprising:

- (a) in a first step treating said solution with hydrochloric acid gas whereby aluminium chloride hexahydrate crystals are precipitated while the mother liquor solution maintains a ratio between aluminium and magnesium at a ratio above 0.5 for grams of Al^{+3} : grams of Mg^{+2} ; and
- (b) separating the precipitated aluminium chloride hexahydrate crystals from the mother liquor;
- (c) in at least one second step transferring said mother liquor solution to a separate container, adding additional hydrochloric acid gas, and continuing to maintaining the ratio between said Al^{+3} and said Mg^{+2} above said 0.5 ratio, while continuing to precipitate further aluminium chloride hexahydrate crystals;
- (d) separating the further precipitated aluminium chloride hexahydrate crystals from the mother liquor; and
- (e) in a subsequent step precipitating substantially all remaining aluminium as aluminium chloride with additional hydrochloric acid gas and returning the precipitated aluminium chloride to solution and renewed precipitation.

4,297,328

THREE-WAY CATALYTIC PROCESS FOR GASEOUS STREAMS

James S. Ritscher, Ossining, and Michael R. Sandner, Chappaqua, both of N.Y., assignors to Union Carbide Corporation, New York, N.Y.
Filed Sep. 28, 1979, Ser. No. 80,132
Int. Cl.³ B01D 53/36 12 Claims

U.S. Cl. 423—213.2

1. A process for the concurrent catalytic reduction of oxides of nitrogen and the oxidation of carbon monoxide and hydrocarbons contained in a gas stream wherein said process consists essentially of contacting the gas stream with a high-silica zeolite containing copper metal or ions, said zeolite having a silica to alumina ratio of at least 20, and wherein said gas stream contains a stoichiometric excess of oxidant.

4,297,329

VAPOR-LIQUID CONTACTING SYSTEM


Paul W. Sigmund, Tarrytown, and Kenneth F. Butwell, Newburgh, both of N.Y., assignors to Union Carbide Corporation, New York, N.Y.
Division of Ser. No. 863,350, Dec. 22, 1977, abandoned. This application May 14, 1980, Ser. No. 149,733
Int. Cl.³ B01D 53/34 3 Claims

U.S. Cl. 423—228

1. In a process for absorbing hydrogen sulfide from a gas mixture containing hydrogen sulfide and carbon dioxide by an

amine liquid solvent in an absorption zone containing a plurality of generally horizontally aligned, vertically spaced-apart perforated trays on which liquid solvent, flowing generally downwardly through the absorption zone from tray to tray, is contacted with upwardly flowing gas mixture, the improvement comprising:

- (a) providing an open area of from 3 to 5% on each of said trays, formed by fixed size perforation openings of from 1/16 to 3/32 inch diameter;



- (b) flowing said gas mixture through said open area perforation openings at a velocity of from 50 to 133 ft/sec; and
(c) maintaining the liquid height of said amine solvent on said trays in the range of from 1/8 to 3/8 inch, whereby upwardly directed laminar jetting of liquid is obtained over said tray perforation openings for solvent-gas mixture contacting and selective hydrogen sulfide absorption.

4,297,330

PROCESS OF SELECTIVELY DESULFURIZING GASES
Johann Schlauer, Frankfurt am Main; Georg Kempf, Schöneck, and Alexander Doerges, Frankfurt am Main, all of Fed. Rep. of Germany, assignors to Metallgesellschaft AG, Frankfurt am Main, Fed. Rep. of Germany


Filed Mar. 27, 1980, Ser. No. 134,360

Claims priority, application Fed. Rep. of Germany, Mar. 27, 1979, 2912115

Int. Cl.³ B01D 53/34

U.S. Cl. 423—232

7 Claims



1. A process for selectively desulfurizing gases which contain hydrogen sulfide and carbon dioxide which comprises scrubbing said gases with an aqueous potassium carbonate solution under a superatmospheric pressure at a temperature of about 100° C., said aqueous potassium carbonate solution having a mass ratio of 1.0 to 3.0 vials (gram equivalent) of alkali in the solution per mole of CO₂ and H₂S in the gases to be purified, regenerating the laden scrubbing solution by stripping the same with a gas in which the CO₂ partial pressure is above 0.2 bar and recycling the so regenerating scrubbing solution.

4,297,331
CATALYSIS

Paul A. Sermon, Cowley, England, assignor to Johnson, Matthey & Co., Limited, London, England

Continuation of Ser. No. 948,508, Oct. 4, 1978, which is a continuation of Ser. No. 826,831, Aug. 22, 1977, abandoned. This application Jun. 11, 1980, Ser. No. 158,492

Claims priority, application United Kingdom, Aug. 24, 1976, 35202/76

Int. Cl.³ B01D 53/36

U.S. Cl. 423—239

7 Claims

1. A method for the decomposition of NO present in a gas stream which comprises contacting the gas with a catalyst consisting essentially of a compound selected from the group consisting of TiB₂, ZrB₂, MoB, WB, Ta₂N, BN, MoSi₂ and WSi₂.

4,297,332

METHOD FOR TREATMENT OF A DISCHARGE LIQUID PRODUCED IN TREATMENT OF AN EXHAUST GAS
Atsushi Tatani, Hiroshima, and Susumu Okino, Yamaguchi, both of Japan, assignors to Mitsubishi Jukogyo Kabushiki Kaisha, Tokyo, Japan


Filed Jan. 16, 1980, Ser. No. 112,444

Claims priority, application Japan, Jan. 18, 1979, 54-4132

Int. Cl.³ C01B 7/00

U.S. Cl. 423—240

6 Claims



4. In a method for treatment of an exhaust gas which comprises the steps of treating an exhaust gas discharged from a coal combustion apparatus in a dry type dust collecting device to remove fly ash from said exhaust gas, treating the resultant exhaust gas from said dry type dust collecting device in an absorption tower where halogen gas and SO₂ in said exhaust gas are absorbed to produce a slurry containing calcium sulfite, oxidizing said slurry containing calcium sulfite into a gypsum slurry, and separating said gypsum slurry into solid and liquid to recover gypsum and at the same time to obtain filtrate separated from said gypsum, the improvement wherein:

- (1) said dry type dust collecting device is divided into at least two sections along the direction of gas flow to separate the collected fly ash into at least two parts, one part being fly ash collected on the most upstream side of said gas flow, and a second part being fly ash collected on the downstream side of said gas flow;
- (2) said filtrate separated from said gypsum is mixed with a part of said fly ash collected at said most upstream side of said gas flow in said dry type dust collecting device to form a mixed slurry; and
- (3) said mixed slurry is separated into clear water and sludge, said clear water is supplied to said absorption tower, and said sludge is mixed with a part of said fly ash collected in said dry type dust collecting device.

4,297,333

METHOD OF DECOMPOSING HYPOCHLORITE ION IN A BASIC SOLUTION

Roger A. Crawford, Wadsworth, and Robert B. Simmons, Norton, both of Ohio, assignors to PPG Industries, Inc., Pittsburgh, Pa.

Filed Jul. 7, 1980, Ser. No. 166,020

Int. Cl.³ B01D 53/34; C01D 3/08; C01B 13/02; C02F 1/72

U.S. Cl. 423—241

24 Claims

18. In a method of removing chlorine from a gas stream comprising scrubbing the gas stream with an aqueous alkaline solution, and thereafter contacting the resulting solution with a solid hypochlorite decomposition catalyst, whereby to form oxygen molecules and chloride ion, the improvement wherein said hypochlorite decomposition catalyst is a solid comprising nickel (II) oxide and bimetal NiCo₂O₄ spinel.

4,297,336

PREPARATION OF SOLUTIONS OF BASIC ALUMINIUM NITRATE

Robert S. Marsden, Kelsall, England, assignor to Imperial Chemical Industries Limited, London, England

Filed Jun. 19, 1980, Ser. No. 160,841

Claims priority, application United Kingdom, Jun. 26, 1979, 22209/79

Int. Cl.³ C01F 7/66

U.S. Cl. 423—395

21 Claims

1. A process for the preparation of a stable, liquid aqueous solution of basic aluminium nitrate which comprises:

- (i) reacting an aluminium oxide with nitric acid solution at a temperature of below 25° C. to form aluminium hydroxide,
- (ii) separating the resulting aluminium hydroxide precipitate,
- (iii) if necessary removing alkali metal ions and other undesirable ions from the precipitate, and
- (iv) digesting the aluminium hydroxide precipitate in nitric acid or aluminium nitrate.

4,297,337

SOLID-PHASE IMMUNOASSAYS USING MAGNETIC GLASS

Gerald R. Mansfield, Painted Post; Karen L. Travis, Corning, and William P. Vann, Beaver Dams, all of N.Y., assignors to Corning Glass Works, Corning, N.Y.

Filed Apr. 13, 1979, Ser. No. 29,576

Int. Cl.³ G01N 33/48; G01T 1/00

U.S. Cl. 424—1

34 Claims

1. In a process for carrying out a solid-phase immunoassay wherein a biological material is complexed with a water-insoluble, inert particulate carrier and, during the assay, the particulate carrier is separated from a fluid, the improvement which comprises utilizing, as said particulate carrier, water-insoluble, inert, magnetically-dilute particles of a glass and/or crystal-containing material having iron-containing, magnetic crystals incorporated therein with dimensions of less than about 1000 Å which are essentially enveloped within the glass and/or crystal structure, and magnetically separating said particulate carrier from said fluid.

4,297,338

MALIGNANT TUMOR IMMUNITY LEVEL DETECTION

Jack G. Makari, 88 Everett Rd., Demarest, N.J. 07627

Continuation-in-part of Ser. No. 14,827, Feb. 26, 1979, abandoned, which is a continuation-in-part of Ser. No. 920,258, Jun. 29, 1978, abandoned, which is a continuation of Ser. No. 679,926, Apr. 26, 1976, abandoned, which is a

continuation-in-part of Ser. No. 342,097, Mar. 16, 1973, abandoned, which is a continuation-in-part of Ser. No. 37,406, May 11, 1970, abandoned, which is a continuation of Ser. No. 421,683, Dec. 28, 1964, abandoned, which is a

continuation-in-part of Ser. No. 75,454, Aug. 26, 1959, abandoned, and a continuation-in-part of Ser. No. 31,855, May 1, 1970, abandoned, which is a continuation of Ser. No. 530,774, Mar. 1, 1966, abandoned, which is a continuation-in-part of Ser. No. 127,849, Jul. 31, 1961, abandoned, which is a

continuation-in-part of Ser. No. 75,454, Aug. 26, 1959, abandoned, and a continuation-in-part of Ser. No. 159,473, Jul. 2, 1971, abandoned, which is a continuation-in-part of Ser. No. 535,364, Mar. 18, 1966, abandoned, which is a

continuation-in-part of Ser. No. 421,683, Dec. 28, 1964, abandoned. This application Sep. 12, 1980, Ser. No. 186,781

Int. Cl.³ A61K 49/00, 39/00

U.S. Cl. 424—9

6 Claims

1. The method of detecting the level of immunity to the development of a malignant tumor in a human subject, which method comprises the combination of steps of

- (a) intradermally injecting into the subject to be tested a level of immunity to malignant tumor development detecting effective dosage of a diagnostic isotonic aqueous

4,297,334

PROCESS FOR REMOVING COLOR BODIES FROM BROWN PHOSPHORIC ACID

Thomas A. McConomy, Coraopolis, and Bruce D. Wells, Pittsburgh, both of Pa., assignors to Calgon Corporation, Pittsburgh, Pa.

Continuation-in-part of Ser. No. 93,347, Nov. 13, 1979, abandoned, which is a continuation-in-part of Ser. No. 13,495, Feb. 21, 1979, abandoned. This application Aug. 4, 1980, Ser. No. 174,979

Int. Cl.³ C01B 25/16

U.S. Cl. 423—321 R

2 Claims

1. In a process for purifying brown phosphoric acid by means of filtration through activated carbon and recovering the phosphoric acid wherein the improvement consists of filtering the brown phosphoric acid through a bed of activated carbon having a total pore volume of 1.0 cc/g or greater with about half of the total pore volume located in pores 35 Å or less in radius.

4,297,335

ALUMINUM DEFICIENT ZEOLITE COMPOSITIONS AND PROCESS FOR PREPARING SAME

Brent M. T. Lok, New City, N.Y., and Thomas J. P. Izod, Holliston, Mass., assignors to Union Carbide Corporation, New York, N.Y.

Filed Mar. 25, 1980, Ser. No. 133,848

Int. Cl.³ C01B 33/28

U.S. Cl. 423—328

10 Claims

1. Process for enhancing the hydrophobicity of crystalline zeolites which comprises:

- (a) providing an activated crystalline zeolitic aluminosilicate having a SiO₂/Al₂O₃ molar ratio of at least 2, and having at least 60 percent, of the framework aluminum atoms not associated with metal cations;
- (b) contacting said activated aluminosilicate with a gas mixture comprising
 - (i) from 0.1 to 20 volume percent fluorine
 - (ii) from zero to 21 volume percent oxygen
 - (iii) and as the remainder, one or a mixture of two or more inert gases,
 said contact being at a temperature of from about 50° F. to 400° F. for a period of at least 1 minute.

sodium or potassium chloride solution containing essentially a glycoprotein-polysaccharide-like antigenic substance derived from malignant tumor tissue and which readily disperses in cold to boiling water and in aqueous sodium or potassium chloride solutions to a stable, non-dialyzable solution, is stable to boiling in water and in aqueous sodium or potassium chloride solutions, is non-dialyzable at a cutoff point of 3500 from water, inert to alkali and to phosphate buffered isotonic aqueous sodium or potassium chloride solutions, precipitated from aqueous media by isopropanol and insoluble in it, ether, chloroform, and butanol, withstands autoclaving at 250° F. and 16 lbs. per square inch pressure for at least 30 minutes and retains its activity after autoclaving even up to 6 hours, gives a positive Molisch test and a negative Dische test, and on acid hydrolysis as by heating it in a 2 N aqueous solution of trifluoroacetic acid or in contact with the acid form of polystyrene nuclear-sulfonic acid cation exchange resin, in a sealed tube in a boiling water bath for 24 hours, yields a hydrolysate containing identifiable sugars and on finite analysis shows also trace amounts of various amino acids typical of N-glycoprotein; and which glycoprotein-polysaccharide-like antigenic substance when dispersed in an isotonic aqueous sodium or potassium chloride solution in an amount for it to contain about 0.25 micrograms of said antigenic substance per milliliter and thereafter one-tenth milliliter of the resulting solution is injected intradermally into a human subject to be tested, produces an erythema about the injection site;

- (b) measuring separately the two longest diameters perpendicular to one another of the resulting injection-produced bleb and any erythema encircling it, and
- (c) calculating the mean of those two diameters and from the magnitude of the mean determining the level of immunity from a scale, on which a mean of 10 mm. or less indicates no immunity and a mean of at least from over 10 to 15 mm. indicates minimum immunity and a mean of 30 to 50 mm. or more indicates best immunity.

4,297,339

CONTROLLED RELEASE CYCLOHEXIMIDE COMPOSITIONS

Richard L. Craven, Kalamazoo, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.

Continuation-in-part of Ser. No. 49,823, Jun. 18, 1979, abandoned. This application Aug. 25, 1980, Ser. No. 180,732
Int. Cl.³ A01N 25/26, 25/34, 43/40

U.S. Cl. 424—19

6 Claims

1. A composition useful for the controlled release of cycloheximide, which consisting essentially of a hardened, substantially uniform mixture of:

- (a) from about 0.03 to 30 percent, by weight, of cycloheximide;
- (b) from about 0.01 to 25 percent, by weight, of an emulsifier having an HLB number within the range of from about 5 and 18; and
- (c) from about 45 to 99 percent, by weight, of an oxidized wax which contains about 5 to about 17 pounds of oxygen per 100 pounds of wax, prepared by adding the cycloheximide
- (a) and emulsifier,
- (b) to the melted wax,
- (c) making a homogeneous mixture thereof, and then cooling the resulting mixture to a solid form.

4,297,340 COSMETIC COMPOSITION FOR SKIN AND HAIR TREATMENT

Yoshiaki Abe, Tokyo; Shigeo Inoue, Ichikai, and Atsuo Ishida, Chiba, all of Japan, assignors to Kao Soap Co., Ltd., Tokyo, Japan


Filed Sep. 13, 1979, Ser. No. 75,009

Claims priority, application Japan, Sep. 26, 1978, 53/118413
Int. Cl.³ A61K 7/06, 7/08, 7/025, 7/027

U.S. Cl. 424—70

3 Claims

1. In a cosmetic composition for the treatment of skin and hair, the improvement comprising the addition, as a moisturizer, of from 0.1 to 50% by weight of the composition of a glycolipid ester represented by the formula,



wherein R₁ represents a methyl group or a hydrogen atom; R₂ represents a saturated or unsaturated hydrocarbon group having 11 to 15 carbon atoms when R₁ is a methyl group, or a saturated or unsaturated hydrocarbon group having 12 to 16 carbon atoms when R₁ is a hydrogen atom; and R₃ represents a saturated or unsaturated hydrocarbon group having 1 to 20 carbon atoms.

4,297,341

SPERMICIDAL COMPOSITION

Donald P. Waller, Elmhurst; Lourens J. D. Zaneveld, Forest Park, and Harry H. S. Fong, Glen Ellyn, all of Ill., assignors to University of Illinois Foundation, Urbana, Ill.

Filed May 9, 1980, Ser. No. 148,567

Int. Cl.³ A61K 31/11, 31/79

U.S. Cl. 424—80

4 Claims

1. A spermicidal composition for vaginal application comprising the complex formed from about 90 to about 50% by weight of polyvinylpyrrolidone and from about 10 to about 50% by weight of gossypol.

4,297,342

3-PYRIDYLMETHYLTHIOCARBAMATES

Edward E. Kilbourn, Chalfont; Ernest D. Weiler, Ambler, and William D. Weir, Levittown, all of Pa., assignors to Rohm and Haas Company, Philadelphia, Pa.


Division of Ser. No. 8,296, Jan. 31, 1979, Pat. No. 4,233,289, which is a division of Ser. No. 591,581, Jun. 30, 1975, Pat. No. 4,156,780. This application Jan. 17, 1980, Ser. No. 114,026

Int. Cl.³ C07D 213/59; A61K 31/44

U.S. Cl. 424—84

14 Claims

1. A metal salt complex of the formula



wherein

X is cyano, nitro, mercapto, (C₁-C₆)alkylthio, (C₁-C₆)alkylsulfinyl, (C₁-C₆)alkylsulfonyl or (C₁-C₆)alkylsulfamyl;
M is calcium, copper, manganese, nickel or zinc;
Y is an anion which satisfies the valence of the cation M which is selected from the group consisting of bromide, chloride, nitrate, sulfate or oxalate;
n is the integer one.

2. A rodenticidal composition which comprises a carrier and as the active ingredient a rodenticidally effective amount of a complex according to claim 1.

4,297,343

CONTRACEPTIVE AGENT

Hans Bohn, and Ernst Weinmann, both of Marburg an der Lahn, Fed. Rep. of Germany, assignors to Behringwerke Aktiengesellschaft, Marburg an der Lahn, Fed. Rep. of Germany
Continuation-in-part of Ser. No. 949,633, Oct. 10, 1978, abandoned. This application May 16, 1980, Ser. No. 150,572
Claims priority, application Fed. Rep. of Germany, Oct. 11, 1977, 2745680

Int. Cl.³ A61K 39/00; C07G 7/00; A61K 37/00

U.S. Cl. 424—85

2 Claims

1. A method for the passive immunization of a pregnant female primate to induce abortion, which method comprises parenterally administering to said primate an amount, effective for inducing abortion, of antibodies against the placenta-specific glycoprotein PP5.

4,297,344

BLOOD COAGULATION FACTORS AND PROCESS FOR THEIR MANUFACTURE

Horst Schwinn; Norbert Heimburger, both of Marburg an der Lahn; Gerhardt Kumppe, Wetter, and Bernd Herchenhan, Kirchhain, all of Fed. Rep. of Germany, assignors to Behringwerke Aktiengesellschaft, Marburg an der Lahn, Fed. Rep. of Germany

Filed Apr. 23, 1980, Ser. No. 142,962

Claims priority, application Fed. Rep. of Germany, Apr. 25, 1979, 2916711

Int. Cl.³ A61K 35/14, 31/00, 37/00

U.S. Cl. 424—101

4 Claims

1. A method for stabilizing against heat an aqueous solution containing at least one member selected from the group consisting of coagulation factors II, VIII, XIII, antithrombin III, and plasminogen, which method comprises adding to said solution from 1.0 to 3.0 mols per liter of at least one amino acid selected from the group consisting of glycine, α- and β-alanine, hydroxyproline, glutamine, and α-, β-, and γ-aminobutyric acid and from 20 to 60 w/w percent of a carbohydrate selected from the group consisting of monosaccharides, oligosaccharides, and sugar alcohols.

4,297,345

ANTIBACTERIAL AGENTS

Thomas T. Howarth, Ewhurst, England, assignor to Beecham Group Limited, England

Division of Ser. No. 857,112, Dec. 5, 1977, which is a division of Ser. No. 669,697, Mar. 23, 1976. This application Oct. 22, 1979, Ser. No. 87,030


Claims priority, application United Kingdom, Apr. 14, 1975, 15209/75; Sep. 27, 1975, 39663/75

Int. Cl.³ A61K 35/00

U.S. Cl. 424—114

17 Claims

10. A method of treating bacterial infection in humans and animals which comprises administering to humans or animals in need thereof synergistically effective amount of a compound of the formula (III):



or a pharmaceutically acceptable salt thereof, and an antibacterially effective amount of benzylpenicillin or the acetoxymethyl ester thereof, the weight ratio of said compound or pharmaceutically acceptable salt thereof and said benzylpenicillin or ester thereof being 20:1 to 1:5.

4,297,346

PSEUDOPEPTIDES USED AS MEDICAMENTS

Richard Rips, and Elisabeth Morier, both of Paris, France, assignors to Institut National de la Sante et de la Recherche Medicale, Paris, France

Continuation of Ser. No. 14,314, Feb. 23, 1979, abandoned, which is a continuation of Ser. No. 858,479, Dec. 8, 1977, abandoned. This application Dec. 7, 1979, Ser. No. 101,555
Claims priority, application United Kingdom, Dec. 10, 1976, 51632/76

Int. Cl.³ A61K 37/00; C07C 103/52; C07G 7/00

U.S. Cl. 424—177

15 Claims

1. Pseudopeptide formed by at least one peptide radical originated from a neuropeptide by removal of one of more of the terminal sequences, connected by a peptide bond to a molecule or to a derivative of a therapeutically active molecule acting on the central nervous system, said neuropeptide being selected from the group consisting of endorphine and neuropeptides having from 2 to 11 amino acid sequences and said therapeutically active molecular being selected from the group consisting of amphetamine (Amph), 4-nitro-amphetamine (Amph-NO₂), 4-amino-amphetamine (Amph-NH₂), 4-chloroamphetamine (Amph-Cl), N-phthaloyl-4-amino-amphetamine, 3,4-dibenzoxyphenyl ethylamine, phenyl ethylamine (PEA), dopamine, 5-(3-aminopropylidene dibenzo-(a,d)-cycloheptadi-1,4-ene (PDD), 1,3-dihydroxy-7-amino 5-phenyl-1H-benzodiazepine-(1,4)-one-(2) (BD), 20-(3-aminopropyl) 3-phenothiazine (PP), 1,5-dimethyl-2-phenyl-4-amino-3-pyrazolone (AP), 4-ethoxyaniline (PT), 4-phenyl-4-ethoxycarbonyl piperidine (NP), tryptamine (Try-NH₂) and 4-amino-barbituric acid (AB).

7. As a novel medicament for asthenia, an effective amount of a pseudopeptide of the class consisting of pGlu-His-Amph and Pro-Leu-Amph together with a pharmaceutically acceptable carrier therefor.

4,297,347

NUCLEOSIDE DERIVATIVES AND AN ANTILEUKEMIAL AGENT CONTAINING THE SAME AS AN ACTIVE INGREDIENT

Nobuhiko Katsunuma, No. 1-78, Shomachi, Tokushima-shi, Tokushima-ken, Japan

Filed Oct. 31, 1979, Ser. No. 89,887

Claims priority, application Japan, Oct. 31, 1978, 53-134708; Jan. 11, 1979, 54-2564; Jan. 11, 1979, 54-2565

Int. Cl.³ A61K 31/70; C07H 19/20, 19/10

U.S. Cl. 424—180

8 Claims

1. A compound selected from the group consisting of guanosine-3'-diphosphate, guanosine-3'-triphosphate, uridine-3'-diphosphate, uridine-3'-triphosphate, cytidine-3'-diphosphate, cytidine-3'-triphosphate, and a pharmaceutically acceptable salt thereof.

8. An agent effective against L5178Y lymphatic leukemia in mice containing a pharmaceutically acceptable carrier and a pharmaceutically acceptable amount of a compound in accordance with claim 1.

4,297,348

COMPOSITION AND METHOD FOR THE TREATMENT OF ACNE

Stephen E. Frazier, Orlando, Fla., assignor to Rush-Hampton Industries, Inc., Longwood, Fla.

Filed Apr. 11, 1980, Ser. No. 139,208


Int. Cl.³ A61K 31/70

U.S. Cl. 424—180

8 Claims


1. A therapeutic composition for the treatment of acne comprising:

- from about 0.1% to about 5% by weight naringin;
- from about 0.1% to about 10% by weight naringenin;
- from about 0.05% to about 5% by weight of an antimicrobially active partially hydrolyzed naringin; and
- from about 80% to about 98% by weight of a suitable solvent.




(ii)

in which p is 0, 1 or 2, and
y is a hydrogen atom, halo having an atomic weight of from about 19 to 127, alkoxy having from 1 to 4 carbon atoms, or alkyl having from 1 to 4 carbon atoms; and
y' is a hydrogen atom, alkoxy having from 1 to 3 carbon atoms, alkyl having from 1 to 3 carbon atoms, or halo having an atomic weight of from about 19 to 36; or subtype (iii) alkyl having from 1 to 8 carbon atoms; or R is of type (b) a phenyl-type radical of the structure




(b)

in which R^b is as defined above, and
R^o is a hydrogen atom, halo having an atomic weight of from about 19 to 127, ie. alkoxy having from 1 to 4 carbon atoms, or alkyl having from 1 to 4 carbon atoms; or
R^o is a radical of the structure R^f:




(c)

in which D is —CH₂— or —O—;
f is 0 or 1; and
W is a hydrogen atom, halo having an atomic weight of from about 19 to 80, alkoxy having from 1 to 3 carbon atoms, or alkyl having from 1 to 3 carbon atoms; or R is of type (c) an indolyl radical of the structure:



(d)

wherein R^b is as defined above;
R⁴ is alkyl having from 1 to 8 carbon atoms or benzyl (unsubstituted); and
R⁵ is a hydrogen atom, alkyl having from 1 to 8 carbon atoms or benzyl (unsubstituted); or
R is (d) a benzocycloalkyl radical of the structure:



wherein y and y' are as defined above; and
j is a whole integer of from 1 to 4.
14. A pharmaceutical composition suitable for reducing the cholesterol ester content of an arterial wall of a mammal comprising a cholesterol ester-reducing effective amount of a com-

4,297,349

SILICON-BEARING CARBOXYLIC ACIDS AND AMIDES
Sander Barcza, Mt. Lakes, N.J., assignor to Sandoz, Inc., E. Hanover, N.J.


Filed Apr. 15, 1980, Ser. No. 140,562

Int. Cl.³ A01N 55/00; C07F 7/10


U.S. Cl. 424—184

22 Claims


1. A compound of the formula:



wherein n is a whole integer of from 3 to 20, each of R¹, R² and R³ is, independently, either (a) alkyl having from 1 to 22 carbon atoms; or (b) a radical of the formula



in which m is 0, 1 or 2, and each of R' and R'' is, independently, a hydrogen atom, alkyl having from 1 to 3 carbon atoms, alkoxy having from 1 to 3 carbon atoms, or halo having an atomic weight of from about 19 to 127; provided that the sum of n and the number of carbon atoms in any one of R¹, R² or R³ is not greater than 34 when any of R¹, R² or R³ is of type (a); and R is of type (a) an aralkyl-type radical of the structure:



(a)

wherein g is 0, 1 or 2;

R^o is a hydrogen atom, halo having an atomic weight of from about 19 to 127, alkoxy having from 1 to 4 carbon atoms, or alkyl having from 1 to 4 carbon atoms, or trifluoromethyl;

R^b is a hydrogen atom, alkyl having from 1 to 3 carbon atoms, alkoxy having from 1 to 3 carbon atoms, or halo having an atomic weight of from about 19 to 36; and
R^c is subtype (i) a hydrogen atom; subtype (ii) a radical of the structure

pound of claim 1 and a non-toxic pharmaceutically-acceptable carrier.

4,297,350

MALE CONTRACEPTIVE STEROIDS AND METHODS OF USE

John C. Babcock; J. Allan Campbell, both of Kalamazoo, and Thomas J. Lobl, Portage, all of Mich., assignors to The Upjohn Company, Kalamazoo, Mich.


Filed Oct. 10, 1978, Ser. No. 949,797

Int. Cl.³ A61K 31/56


U.S. Cl. 424—238

17 Claims


1. A method of effecting male contraception which comprises oral administration of a contraceptively effective amount of a compound of the formula:




I




II




III




IV




V




VI




VII




VIII




IX



X




XI



XII


-continued




XIII

that for the compounds of formula (XIV) the Z's may be the same or different; where m is 4 thru 6; where n is 0 thru 4; where p is 0 thru 4; where q is 1 or 2, when q is 2 the M's can be the same or different; where r is 1 or 2, when r is 2 the A's can be the same or different; where y is 1 or 2, when y is 2 the D's can be the same or different; where μ is 0 thru 4; where ~ indicates the attached group can be in either the α or β configuration; and where is a single or double bond, if a single bond the hydrogen atom at C5 is α; including the oximers and O-substituted oximes of compounds I thru IV and VI made with NH₂-OR₃ to a male mammal post-puberty selected from the group consisting of man, male dog, tom, bull, stallion, ram, boar, male rat, and male mouse.


XIV




XV




where A is a methyl, methoxy, trifluoromethyl, hydroxyl or nitro group or a hydrogen, fluorine, chlorine or bromine atom; where D is a methyl, methoxy, trifluoromethyl, hydroxyl or nitro group or a hydrogen, fluorine, chlorine or bromine atom; where M is a methyl, methoxy, trifluoromethyl, hydroxyl or nitro group or a hydrogen, fluorine, chlorine or bromine atom; where R₂ is a hydrogen atom or methyl group; where R_{2α} is a hydrogen atom, alkyl 1 thru 4 carbon atoms or benzyl; where R_{2β} is a hydrogen atom or methyl group with the proviso that when R_{2β} is methyl, R_{2α} is also methyl; where R_{2α} is alkyl of 1 thru 3 carbon atoms or



where R₃ is alkyl of 1 thru 4 carbon atoms or phenyl; where R₆ is a hydrogen atom or methyl group; where R₇ is a hydrogen atom or methyl group; where R_{17α} is a hydrogen atom, alkyl of 1 thru 4 carbon atoms, alkenyl of 2 thru 4 carbon atoms or alkynyl of 2 thru 4 carbon atoms; where R_{17β} is alkyl of 1 thru 16 carbon atoms,



—(CH₂)_n—CH(CH₂)_m, —CH₂—alkenyl where alkenyl is 2 thru 15 carbon atoms or —CH₂—C=CH₂, and R_{17α} and R_{17β} can be connected to form a cyclic ether containing 4 or 5 carbon atoms; where Q is an oxygen atom; where X is a fluorine, chlorine or bromine atom; where Z is a hydrogen atom, alkyl of 1 thru 4 carbon atoms or



4,297,351
METHOD OF MANUFACTURE AND USE OF IMPROVED 2β, 16β-PIPERIDINO ANDROSTANES
Ian C. Carlyle, Hamilton; Thomas Sleigh, Wishaw, and David S. Savage, Glasgow, all of Scotland, assignors to Akzona Incorporated, Asheville, N.C.
Continuation of Ser. No. 67,878, Aug. 20, 1979, Pat. No. 4,237,126. This application Oct. 7, 1980, Ser. No. 194,942
Claims priority, application United Kingdom, Sep. 5, 1978, 35667/78

Int. Cl.³ A61K 31/58

U.S. Cl. 424—241

44 Claims


1. A method for the preparation of a pharmaceutically acceptable acid addition salt of the 16β-mono-quaternary ammonium derivative of either a 3α,17β-di-lower aliphatic ester of 2β,16β-dipiperidino-3α,17β-dihydroxy-5α-androstane or a 3α-lower aliphatic ester of 2β,16β-dipiperidino-3α-hydroxy-5α-androstane comprising adding a pharmaceutically acceptable acid to the 16β-mono-quaternary ammonium derivative of either a 3α,17β-di-lower aliphatic ester of 2β,16β-dipiperidino-3α,17β-dihydroxy-5α-androstane or a 3α-lower aliphatic ester of 2β,16β-dipiperidino-3α-hydroxy-5α-androstane in a suitable solvent.
2. In the method for the administration of a neuromuscular blocking agent by injection to a surgical patient, the improvement which comprises using as said neuromuscular blocking agent an effective amount of a pharmaceutically acceptable acid addition salt of the 16β-mono-quaternary ammonium derivative of either a 3α,17β-di-lower aliphatic ester of 2β,16β-dipiperidino-3α,17β-dihydroxy-5α-androstane or a 3α-lower aliphatic ester of 2β,16β-dipiperidino-3α-hydroxy-5α-androstane.

4,297,352
NOVEL OXIMES
Rene Heymes, Romainville, and Andre Lutz, Strasbourg, both of France, assignors to Roussel Uclaf, Paris, France
Division of Ser. No. 964,517, Nov. 29, 1978, Pat. No. 4,260,747.
This application Nov. 29, 1979, Ser. No. 98,636
Claims priority, application France, Dec. 5, 1977, 77 36513
Int. Cl.³ A61K 31/545

U.S. Cl. 424—246

7 Claims

1. The syn isomers of 3-substituted 7-amino-thiazolyl-acetamido-cephalosporanic acid compounds of the formula



wherein R is selected from the group consisting of cycloalkyl of 3 to 5 carbon atoms and —CH₂—S—R₁, R₁ is acyl of an organic carboxylic acid of 2 to 4 carbon atoms and A is selected from the group consisting of hydrogen, alkali metal, alkaline earth metal, magnesium and a non-toxic, pharmaceutically acceptable organic amine.

4. An antibacterial composition comprising an antibacterially effective amount of at least one compound of claim 1 and an inert pharmaceutical carrier.

4,297,353
NON-IRRITATING INJECTABLE DOSAGE FORMS
Hawkins V. Maulding, Mendham, N.J., assignor to Sandoz, Inc., E. Hanover, N.J.

Filed Aug. 4, 1980, Ser. No. 177,817
Int. Cl.³ A61K 31/23, 31/54, 47/00
U.S. Cl. 424—247

10 Claims

1. Method of administering without irritation an injectable dosage form of a tissue irritating medicament, which comprises administering to a patient in need of the medicament, a therapeutically effective amount of thioridazine, in base form in association with a sufficient amount of a pharmaceutically acceptable glyceride vehicle comprising a glycerol ester of a saturated or unsaturated fatty acid which fatty acid has from 6 to 20 carbon atoms or mixtures thereof to form an injectable dosage form.

4,297,354
SUBSTITUTED 4-AMINO-2,6-DIARYL-TETRAHYDROTHIOPYRANS AND SALTS THEREOF, AND USE AS ANTIDEPRESSANTS

Karl-Heinz Weber, Gau-Algesheim; Claus Schneider, Ingelheim am Rhein; Gerhard Walther, Bingen am Rhein; Karl-Heinz Pook; Karin Böke, both of Ingelheim am Rhein, and Wolf D. Bechtel, Appenheim, all of Fed. Rep. of Germany, assignors to Boehringer Ingelheim GmbH, Ingelheim am Rhein, Fed. Rep. of Germany


Filed Dec. 15, 1980, Ser. No. 216,423
Claims priority, application Fed. Rep. of Germany, Dec. 21, 1979, 2951634

Int. Cl.³ A61K 31/38, 31/445; C07D 335/02


U.S. Cl. 424—248.51

13 Claims

1. A compound of the formula



or



wherein

R₁ and R₂ are each phenyl; mono-, di- or tri-substituted phenyl, where the substituents are halogen, methyl or methoxy; thienyl; or furyl;
R₃ is hydrogen or alkyl of 1 to 3 carbon atoms; and
R₄ is alkyl of 1 to 3 carbon atoms; or
R₃ and R₄, together with each other and the nitrogen atoms to which they are attached, form a piperidino, 4-amino-piperidino, 4-(lower alkyl-amino)-piperidino, piperazino, 4-(alkyl of 1 to 2 carbon atoms)-piperazino or morpholino radical; or a non-toxic, pharmacologically acceptable acid addition salt thereof.

13. The method of preventing or relieving depression in a warm-blooded animal in need thereof, which comprises perorally, parenterally or rectally administering to said animal an effective antidepressant amount of a compound of claim 1.

4,297,355
(1H,3H,5H)-(1)-BENZOPYRANO-(2,3-D)-PYRIMIDINE-4-ONE-2-THIONES AND THEIR USE AS ANTI-ALLERGY AGENTS

David J. Blythin, North Caldwell, N.J., assignor to Schering Corporation, Kenilworth, N.J.

Filed Nov. 15, 1979, Ser. No. 94,407


The portion of the term of this patent subsequent to Jun. 9, 1998, has been disclaimed.

Int. Cl.³ A61K 31/505; C07D 491/052


U.S. Cl. 424—248.54

13 Claims

1. A compound of the formula



and the pharmaceutically acceptable salts thereof, wherein R represents hydrogen, lower alkyl, lower cyclo alkyl, acyloxy-lower alkyl, hydroxy-lower alkyl, lower alkoxy-lower alkyl, nitro, halogeno, hydroxy, lower alkoxy, carboxyl, carbox-amido, lower alkoxy-carbonyl, tetrazolyl or cyano, and n is one or two, wherein said carboxamido has the partial structural formula



wherein A is straight or branched chain alkyl with up to 12 carbon atoms, lowercycloalkyl, lowercycloalkyl-loweralkyl, loweralkoxy-loweralkyl, hydroxy-loweralkyl, fluoroloweralkyl, loweralkenyl, loweralkylthiol-loweralkyl, loweralkylsulfoxy-loweralkyl, loweralkylsulfonyl-loweralkyl, thiazolyl, oxazolyl, thiazolyl, methylthiazolyl, furyl, pyrazolyl, tetrazolyl, methyltetrazolyl, phenyl, or the grouping ER₄ wherein E is a straight or branched chain or cyclic loweralkylene optionally substituted with hydroxy or phenyl radicals, R₄ is phenyl, thiazolyl, oxazolyl, thiazolyl, methylthiazolyl, tetrazolyl, methyltetrazolyl, furyl, pyridyl, methylpyridyl or piperidinyl; and B is hydrogen, loweralkyl, lowercycloalkyl, lowercycloal-

kylloweralkyl, or loweralkenyl; or A and B, when taken together with the nitrogen atom to which they are attached, represent imidazolyl, morpholinyl, pyrrolidinyl, piperidinyl or piperazinyl, said heterocyclic rings being optionally substituted by hydroxy, loweralkyl or hydroxyloweralkyl.

10. A method for effecting an anti-allergic reaction useful in the prophylactic treatment of animals for allergic and anaphylactic reactions which comprises administering to an animal in need of such therapy a therapeutically useful quantity of a compound of claim 1.

11. An anti-allergy pharmaceutical composition comprising an effective amount of a compound of claim 1 and a pharmaceutically acceptable carrier.

4,297,356

MEMORY ENHANCER CONTAINING 2-(7-INDENYLOXYMETHYL)-MORPHOLINE

Minoru Yamamoto, Kanagawa; Shiro Tachikawa, Omiya, and Hiroo Maeno, Shiki, all of Japan, assignors to Yamanouchi Pharmaceutical Co., Ltd., Tokyo, Japan

Filed Aug. 25, 1980, Ser. No. 181,068

Claims priority, application Japan, Mar. 5, 1980, 55/26742

Int. Cl.³ A61K 27/00

U.S. Cl. 424—248.57

4 Claims

1. A method of enhancing memory in an adult requiring enhancement of said memory comprising administering to said adult an effective amount of a composition administering an effective amount of 2-(7-indenylloxymethyl)morpholine or an acid addition salt thereof and a pharmaceutically acceptable carrier therefor.

4,297,357

N-PHENETHYLACETAMIDE COMPOUNDS AND PROCESS FOR PREPARATION THEREOF

Tosaku Miki, and Masahide Asano, both of Minamifunabori, Japan, assignors to Daiichi Seiyaku Co., Ltd., Tokyo, Japan

Filed Aug. 27, 1979, Ser. No. 70,085


Claims priority, application Japan, Aug. 25, 1978, 53-103652; Jul. 25, 1979, 54-94597

Int. Cl.³ A61K 31/505, 31/44, 31/165

U.S. Cl. 424—251


9 Claims

1. N-phenethylacetamide compounds of the formula:



wherein X₁ represents a lower alkoxy group, X₂ represents a hydrogen atom or a lower alkoxy group and R represents a phenyl group, a pyridyl group or a pyrimidinyl group, each of which may have one or more substituents selected from a halogen atom, a carbamoyl group, a lower alkoxy group, a sulfamoyl group, an amino group, a lower alkylamino group, a lower alkylthio group, a hydroxy group and a lower alkoxy-carbonyl group; or the pharmaceutically acceptable acid addition salts and hydrates thereof.

6. A therapeutic agent for treating peptic ulcer comprising in an amount effective for treating peptic ulcer at least one N-phenethylacetamide compound of the formula:



wherein X₁ represents a lower alkoxy group, X₂ represents a hydrogen atom or a lower alkoxy group, and R represents a phenyl group, a pyridyl group or a pyrimidinyl group, each of which may have one or more substituents selected from a halogen atom, a carbamoyl group, a lower alkoxy group, a sulfamoyl group, an amino group, a lower alkylamino group, a lower alkylthio group, a hydroxy group and a lower alkoxy-carbonyl group; or the pharmaceutically acceptable acid addition salts and hydrates thereof, and a pharmaceutically acceptable carrier.

4,297,358

NOVEL 4,7-PHENANTHROLINE DERIVATIVES AND PHARMACEUTICAL COMPOSITIONS CONTAINING THEM AND THEIR USE

Georges Haas, Binningen; Knut A. Jaeggi, Basel; Alberto Rossi, Oberwil, and Alex Sele, Muttens, all of Switzerland, assignors to Ciba-Geigy Corporation, Ardsley, N.Y.

Filed Jan. 4, 1980, Ser. No. 109,715


Claims priority, application Switzerland, Jan. 16, 1979, 402/79

Int. Cl.³ C07D 487/04; A61K 31/435

U.S. Cl. 424—256

13 Claims

1. A 4,7-phenanthroline derivative of the formula



in which

Ch represents 5,6-quinolinyne which is unsubstituted or c-substituted by one or two substituents selected from the group consisting of lower alkyl, lower alkoxy, hydroxy and/or halogen,

R represents carboxy, lower alkoxy-carbonyl, hydroxylower alkoxy-carbonyl, lower alkoxy-lower alkoxy-carbonyl, di-lower alkylamino-lower alkoxy-carbonyl, and in which either

R_A and R_B together represent oxo,

R_C and R_D together represent an additional link and R_E represents hydrogen, or

R_A represents hydroxy, lower alkoxy or lower alkenyloxy and

R_B together with R_C and R_D together with R_E in each case represents an additional link,

or a pharmaceutically acceptable salt of a salt-forming compound of the formula (I).

13. A pharmaceutical composition useful as inhibitors of allergic reactions containing an effective amount of a compound as claimed in claim 1, together with customary pharmaceutical auxiliaries and carriers.

4,297,359

ANTI-ULCER COMPOSITIONS CONTAINING CERTAIN PYRIDYL OXIME ETHERS

Jacob A. van Zorge, Ameide, Netherlands, assignor to ACF Chemiefarma NV, Netherlands

Filed Jul. 11, 1979, Ser. No. 56,543


Claims priority, application United Kingdom, Jul. 25, 1978, 30951/78

Int. Cl.³ C07D 405/06, 409/06; A61K 31/44

U.S. Cl. 424—263

14 Claims

1. A compound selected from the group consisting of
(a) a pyridine compound of the formula:




wherein

Het is pyridin-2-yl, pyridin-3-yl, or pyridin-4-yl, unsubstituted or substituted with halo, alkyl of 1 to 6 carbon atoms or alkoxy of 1 to 6 carbon atoms;

Ar is thien-2-yl, thien-3-yl, fur-2-yl or fur-3-yl unsubstituted or substituted with halo, alkyl of 1 to 6 carbon atoms, alkoxy of 1 to 6 carbon atoms, trifluoromethyl or hydroxymethyl;

R is alkyl of 1 to 3 carbon atoms, alkenyl of 3 or 4 carbon atoms, alkynyl of 3 or 4 carbon atoms, or



wherein q has a value of 2 or 3 and each of R³ and R⁴ independently of the other is hydrogen or alkyl of 1 to 3 carbon atoms; and

each of m and n is 0 or 1, the sum of m and n being less than 2;

(b) the N-oxides thereof and (c) the pharmaceutically acceptable acid addition and quaternary addition salts of said pyridine compounds or said N-oxides thereof.

14. The method of treating gastric ulcers in humans which comprises administering thereto an effective amount of a compound according to claim 1.

4,297,360

5-(PYRIDINYL)PYRIDINE-2,3-DIAMINES, PREPARATION THEREOF AND THEIR CARDIOTONIC USE

George Y. Leshner; Chester J. Opalka, Jr., both of Schodack, and Donald F. Page, East Greenbush, all of N.Y., assignors to Sterling Drug Inc., New York, N.Y.


Filed Mar. 28, 1980, Ser. No. 135,100

Int. Cl.³ C07D 401/04; A61K 31/44; C07D 413/14; A61K 31/535

U.S. Cl. 424—263

14 Claims

1. A 2-R₃RN-3-R₁RN-5-PY-6-Q-pyridine having the formula



or pharmaceutically-acceptable acid-addition salt thereof, where Q, R and R' are each hydrogen or lower-alkyl, PY is 4- or 3-pyridinyl or 4- or 3-pyridinyl having one or two lower-alkyl substituents, and, R₁ and R₃ are each hydrogen, lower-alkyl, lower-hydroxyalkyl, 2,3-dihydroxypropyl, lower-alkoxyalkyl or Y-NB where Y is lower-alkylene having at least

two carbon atoms between its connecting linkages and NB is di-(lower-alkyl)amino or 4-morpholinyl.

12. The method for increasing cardiac contractility in a patient requiring such treatment which comprises administering orally or parenterally in a solid or liquid dosage form to such patient an effective amount of a cardiotonic 2-NRR-3-NR'R'-5-PY-6-Q-pyridine or pharmaceutically-acceptable acid-addition salt thereof, where Q is hydrogen or lower-alkyl, PY is 4- or 3-pyridinyl or 4- or 3-pyridinyl having one or two lower-alkyl substituents, and NRR and NR'R' are each amino, lower-alkylamino or di-(lower-alkyl)amino.

4,297,361

THIAZOLYLIDENE-OXO-PROPIONITRILES, INSECTICIDAL COMPOSITION CONTAINING THESE COMPOUNDS

Reinhold Puttner; Ulrich Bühlmann, and Harmut Joppjen, all of Berlin, Fed. Rep. of Germany, assignors to Schering Aktiengesellschaft, Berlin and Bergkamen, Fed. Rep. of Germany

Filed May 19, 1980, Ser. No. 151,109


Claims priority, application Fed. Rep. of Germany, May 17, 1979, 2920183

Int. Cl.³ C07D 417/04, 277/38; A01N 43/40, 43/78

U.S. Cl. 424—263

21 Claims

1. Thiazolylidene-oxo-propionitriles of the formula



wherein

R₁ is phenyl, methylphenyl, halogenophenyl, tert.-butyl, pyridyl or thienyl,

R₂ is hydrogen, bromine or methyl, and

R₃ is phenyl substituted in one or two positions by the same or different radicals selected from the group consisting of methyl, fluoro, chloro, bromo, iodo, trifluoromethyl, nitro or methoxy.

21. An insecticidal composition comprising about 5 to 95% by weight of a compound as defined in claim 1 and about 95 to 5% by weight of liquid or solid carrier materials to which there may be added, upon corresponding reduction of the carrier materials, up to 20% by weight of surface active agents.

4,297,362

4-(3,4-DIAMINOPHENYL)PYRIDINE OR SALTS, AND USE THEREOF AS CARDIOTONIC

George Y. Leshner, Schodack, and Baldev Singh, East Greenbush, both of N.Y., assignors to Sterling Drug Inc., New York, N.Y.

Continuation-in-part of Ser. No. 40,210, May 18, 1979, abandoned. This application Jul. 28, 1980, Ser. No. 173,003

Int. Cl.³ C07D 213/38; A61K 31/44

U.S. Cl. 424—263

5 Claims

1. 4-(3,4-Diaminophenyl)pyridine or pharmaceutically-acceptable acid-addition salt thereof.

4,297,363

2-AMINO-3(4 OR 5)-(PYRIDINYL)PHENOLS AND THEIR USE AS CARDIOTONICS

George Y. Leshner, Schodack, and Baldev Singh, East Greenbush, both of N.Y., assignors to Sterling Drug Inc., New York, N.Y.

Filed Jul. 21, 1980, Ser. No. 170,896

Int. Cl.³ C07D 213/30; A61K 31/44

U.S. Cl. 424—263

12 Claims

1. 2-Amino-3(4 or 5)-PY-phenol or pharmaceutically-acceptable acid-addition salt thereof, where PY is 4- or 3-pyridinyl or 4- or 3-pyridinyl having one or two lower-alkyl substituents.

9. The method for increasing cardiac contractility in a pa-

tient requiring such treatment which comprises administering orally or parenterally in a solid or liquid dosage form to such patient a cardiotionically-effective amount of 2-amino-3(4 or 5)-PY-phenol or pharmaceutically-acceptable acid-addition salt thereof, where PY is 4- or 3-pyridinyl or 4- or 3-pyridinyl having one or two lower-alkyl substituents.

4,297,364

α -AZOLYL- α -PHENYLACETIC ACID DERIVATIVES
Hubert Sauter, Bernd Zehe, both of Ludwigshafen; Costin Rentzea, Heidelberg, and Ernst-Heinrich Pommer, Limburgerhof, all of Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Fed. Rep. of Germany

Filed Oct. 10, 1979, Ser. No. 83,243

Claims priority, application Fed. Rep. of Germany, Oct. 18, 1978, 2845293

Int. Cl.³ A01N 43/64, 43/84; C07D 249/08, 401/06

U.S. Cl. 424—267

4 Claims

1. A compound selected from the group consisting of α -(2,4-dichlorophenyl)- α -(1,2,4-triazol-1-yl)-acetic acid-t-butyl ester, α -(2,4-dichlorophenyl)- α -(1,2,4-triazol-1-yl)-acetic acid-N,N-diisopropyl amide, α -(2,4-dichlorophenyl)- α -(1,2,4-triazol-1-yl)-acetic acid-N-cyclohexyl-N-methyl amide, α -(2,4-dichlorophenyl)- α -(1,2,4-triazol-1-yl)-acetic acid-N-t-butyl-N-cyclohexyl amide, α -(2,4-dichlorophenyl)- α -(1,2,4-triazol-1-yl)-acetic acid-N-[n-butyl-N-isopropyl amide, α -(2,4-dichlorophenyl)- α -(1,2,4-triazol-1-yl)-acetic acid-N-4-chlorophenyl-N-methyl amide, α -(2,4-dichlorophenyl)- α -(1,2,4-triazol-1-yl)-acetic acid-N-isopropyl-N-phenyl amide, α -(2,4-dichlorophenyl)- α -(1,2,4-triazol-1-yl)-acetic acid-N-2,6-dimethylpiperidine, α -(2,4-dichlorophenyl)- α -(1,2,4-triazol-1-yl)-acetic acid-N-t-butyl-N-methyl amide, α -phenyl- α -(1,2,4-triazol-1-yl)-acetic acid-N,N-diisopropyl amide, α -(4-chlorophenyl)- α -(1,2,4-triazol-1-yl)-acetic acid-N-methyl-N-but-1-yn-3-yl amide, α -(4-chlorophenyl)- α -(1,2,4-triazol-1-yl)-acetic acid-diisobutyl amide, α -(2,4-dichlorophenyl)- α -(1,2,4-triazol-1-yl)-acetic acid-N-methyl-N-isopropyl amide, α -(2,4-dichlorophenyl)- α -(1,2,4-triazol-1-yl)-acetic acid-N-methyl-N-isobutyl amide, α -(2,4-dichlorophenyl)- α -(1,2,4-triazol-1-yl)-acetic acid-isopentyl ester, α -(2,4-dichlorophenyl)- α -(1,2,4-triazol-1-yl)-acetic acid-N-propenyl-N-cyclohexyl amide, α -(2,4-dichlorophenyl)- α -(1,2,4-triazol-1-yl)-acetic acid-N-isopropyl-N-benzyl amide, α -phenyl- α -(1,2,4-triazol-1-yl)-acetic acid-N-methyl-N-t-butyl amide, α -(4-chlorophenyl)- α -(1,2,4-triazol-1-yl)-acetic acid-N-n-butyl-N-t-butyl amide, α -(4-chlorophenyl)- α -(imidazol-1-yl)-acetic acid-N-n-butyl-N-t-butyl amide, and α -(2-chlorophenyl)- α -(1,2,4-triazol-1-yl)-acetic acid-N-isopropyl-N-phenyl amide.

4. A fungicidal agent for combating powdery mildew consisting essentially of from 0.1 to 95% by weight of a compound selected from the group as claimed in claim 1 and a solid or liquid carrier.

4,297,365

BENZIMIDAZOLES AND PHARMACEUTICAL PREPARATIONS CONTAINING SUCH COMPOUNDS
Srinivasachari Rajappa, and Vasudevan Sudarsanam, both of Bombay, India, assignors to Ciba-Geigy Corporation, Ardsley, N.Y.

Filed Jul. 26, 1979, Ser. No. 61,097


Claims priority, application Switzerland, Aug. 4, 1978, 8359/78

Int. Cl.³ C07D 277/28

U.S. Cl. 424—270

10 Claims

1. A benzimidazole carbamate of the formula I,



in which R₁ is lower alkyl, R₂ is a member selected from the group consisting of hydrogen or lower alkyl and R₃ and R₄ are each a member selected from the group consisting of hydrogen, lower alkyl, lower alkenyl, cycloalkyl and phenyl and R₃ and R₄ taken together with adjacent nitrogen atom are lower alkylene-amino, a tautomeric compound thereof or a salt thereof.

4,297,366

COMBATING ARTHROPODS WITH 2,2-DIMETHYL-3-(2-FLUOROALKYL-2-OXY-VINYL)-CYCLOPROPANE-CARBOXYLIC ACID ESTERS

Rainer Fuchs, Wuppertal; Ingeborg Hammann, Cologne; Bernhard Homeyer, Leverkusen; Wolfgang Behrenz, Overath, and Wilhelm Stendel, Wuppertal, all of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Apr. 23, 1980, Ser. No. 142,928


Claims priority, application Fed. Rep. of Germany, May 16, 1979, 2919820

Int. Cl.³ A01N 53/00; C07C 69/743, 121/75; C07D 209/34

U.S. Cl. 424—274

10 Claims

1. A 2,2-dimethyl-3-(2-fluoroalkyl-2-oxy-vinyl)-cyclopropanecarboxylic acid ester of the formula




in which


R¹ is C₁-C₄-fluoroalkyl or C₁-C₄-chlorofluoroalkyl,

R² is C₁-C₄-alkyl, C₁-C₄-halogenoalkyl, C₅-C₆-cycloalkyl or benzyl,

R³ is



-continued



R⁵ is hydrogen, cyano, ethynyl, methyl or ethyl, and R⁶ and R⁷ each independently is hydrogen or halogen.

7. A method of combating arthropods which comprises applying to the arthropods, or to a habitat thereof, an arthropodically effective amount of a compound according to claim 1.

4,297,367

2-PHENYL-4-PYRONE DERIVATIVES, THEIR PREPARATION AND THEIR USE AS FUNGICIDES
Franco Guigues, Rillieux, and Stephane Trinh, Champagne au Mont d'Or, both of France, assignors to Rhone Poulenc Agrochimie, Lyons, France

Filed Mar. 24, 1980, Ser. No. 133,480


Claims priority, application France, Mar. 28, 1979, 79 08569

Int. Cl.³ A61K 31/35; C07D 309/32

U.S. Cl. 424—283

7 Claims

1. A 2-phenyl-4-pyrone derivative of the formula



in which X₁ and X₂, which are identical or different, each represent a hydrogen or halogen atom, with the proviso that at least one of these substituents represents a halogen atom, R₁ represents an alkoxy radical containing from 1 to 4 carbon atoms, an alkenyloxy radical containing from 2 to 4 carbon atoms, the propargyloxy radical, a halogenoalkoxy radical containing from 1 to 4 carbon atoms, an amino radical, an alkylamino radical in which the alkyl groups containing from 1 to 4 carbon atoms are identical or different, R₂ represents a halogen atom, an alkyl radical containing from 1 to 5 carbon atoms, an alkoxy radical containing from 1 to 4 carbon atoms, an alkenyloxy radical containing from 3 to 4 carbon atoms, an alkyloxy radical containing from 3 to 4 carbon atoms, an alkylthio radical containing from 1 to 4 carbon atoms, a halogenoalkyl radical containing from 1 to 4 carbon atoms, a halogenoalkoxy radical containing from 1 to 4 carbon atoms, a halogenoalkylthio radical containing from 1 to 4 carbon atoms or a nitro, hydroxyl, cyano or benzyloxy radical and n is an integer which can be equal to 0, 1, 2, 3, 4 or 5, it being understood that, if n is greater than or equal to 2, the substituents R₂ can be identical or different.

5. A composition for protecting plants against fungal diseases, which contains an effective amount of at least one compound according to claim 1, in association with a carrier and/or a surface-active agent which can be used in agriculture and are compatible with the said active ingredient.

4,297,368
PHARMACEUTICALLY USEFUL 5,6-SATURATED PGI COMPOUNDS

Carmelo Gandolfi, Milan; Carlo Passarotti, Gallarate; Alessandro Andreoni, Cologno Monzese; Angelo Fumagalli, Monza; Franco Faustini, Milan; Roberto Ceserani, Milan, and Maria M. Usardi, Milan, all of Italy, assignors to Farmitalia Carlo Erba S.p.A., Milan, Italy

Division of Ser. No. 859,703, Dec. 12, 1977, abandoned. This application Jun. 29, 1978, Ser. No. 920,166


Claims priority, application Italy, Dec. 31, 1976, 31041 A/76; Jan. 14, 1977, 19283 A/77; Mar. 14, 1977, 21171 A/77; Mar. 21, 1977, 21412 A/77; Mar. 31, 1977, 21863 A/77

Int. Cl.³ C07D 307/935

U.S. Cl. 424—285


50 Claims

1. A compound of the formula (I)




wherein

R is a free carboxy group or an esterified carboxy group of the formula —COOR_c, wherein R_c is a C₁-C₁₂alkyl radical or a C₂-C₁₂ alkenyl radical;
Z₁ is hydrogen or halogen;
p is zero or an integer of 1 to 7;
q is 1;
R₁ is hydrogen, hydroxy, C₁-C₆ alkoxy, benzyloxy C₂-C₁₂ alkanoyloxy or benzoyloxy;
Y is a member selected from the group consisting of —C≡C—,




wherein

Z₂ is halogen or —CH=CH—(cis);
one of R₂ and R₅ is hydrogen, C₁-C₆ alkyl, C₂-C₆ alkenyl, C₂-C₆ alkynyl or phenyl, α -naphthyl or β -naphthyl, and the other is hydroxy, C₁-C₆ alkoxy, benzyloxy, or R₂ and R₅, taken together form an oxo group;
each of R₃ and R₄, which are the same or different, may be hydrogen C₁-C₆ alkyl or fluorine or R₃ and R₄, taken together with the carbon atom to which they are linked, form the radical



or the radical



each of n₁ and n₂, which are the same or different, is zero or an integer of 1 to 6;

X is $-(CH_2)_m-$, wherein m is zero or 1;
 R₆ is a C₃-C₉ cycloalkyl or C₃-C₉ cycloalkenyl, unsubstituted or substituted by one or more substituents selected from the group consisting of C₁-C₆ alkyl and C₁-C₆ alkoxy;
 and the pharmaceutically or veterinarily acceptable salts thereof.

4,297,369

CERTAIN MUSCLE RELAXANT 3-METHYL-2-BENZOFURAN ACETAMIDES

Hiroshi Takizawa, Shizuoka; Yutaka Enomoto, Sakai; Yoshimasa Oiji, Shizuoka; Tatsuyuki Hirayama, Shizuoka, and Tamotu Hashimoto, Shizuoka, all of Japan, assignors to Kyowa Hakko Kogyo Co., Ltd., Tokyo, Japan
 Filed Jul. 28, 1980, Ser. No. 172,949


Claims priority, application Japan, Jul. 26, 1979, 54-94180; Mar. 12, 1980, 55-30312

Int. Cl.³ A61K 31/34; C07D 307/54

U.S. Cl. 424-285


8 Claims

1. A benzofuran derivative represented by the formula:



wherein R₁ represents an alkyl group having 1-4 carbon atoms, an alkoxy group having 1-4 carbon atoms, a phenyl group or a halogen atom, and R₂ and R₃ may be the same or different and represent a hydrogen atom or an alkyl group having 1-4 carbon atoms wherein, when one of R₂ and R₃ represents a hydrogen atom, the other represents an alkyl group.

5. A muscle relaxant pharmaceutical composition containing, as the active ingredient, a muscle relaxant amount of the benzofuran derivative represented by the formula:



wherein R₁ represents an alkyl group having 1-4 carbon atoms, an alkoxy group having 1-4 carbon atoms, a phenyl group or a halogen atom, and R₂ and R₃ may be the same or different and represent a hydrogen atom or an alkyl group having 1-4 carbon atoms wherein, when one of R₂ and R₃ represents a hydrogen atom, the other represents an alkyl group, and at least one pharmaceutically acceptable carrier.

4,297,370

INSECTICIDAL COMPOSITIONS

Edward J. Soboczenski, Chadds Ford, Pa., assignor to E. I. du Pont de Nemours and Company, Wilmington, Del.
 Continuation of Ser. No. 963,949, Nov. 27, 1979, abandoned, which is a continuation-in-part of Ser. No. 804,358, Jun. 7, 1977, abandoned. This application Feb. 6, 1980, Ser. No. 119,295

Int. Cl.³ A01N 37/00, 37/08, 37/34

U.S. Cl. 424-298

8 Claims

1. An insecticidal composition consisting essentially of
 (A) N,N'-[thiobis(methylaminocarbonyloxy)]bis[ethanimidothioic acid], dimethyl ester; and
 (B) cyano-(3-phenoxyphenyl)-methyl 4-chloro-α-(1-methylethyl)benzeneacetate, or (3-phenoxybenzyl) cis-trans-3-(2,2-dichlorovinyl)-2,2-dimethylcyclopropanecarboxylate, wherein a ratio of (A) to (B) is in a range of from 20:1 to 3:1 by weight.

4,297,371
COMBATING PESTS WITH
 (±)-TRANS-3-(E/Z-2-CHLORO-2-(4-CHLOROPHENYL)-VINYL)-2,2-DIMETHYL-CYCLOPROPANECARBOXYLIC ACID (±)-α-CYANO-3-PHENOXY-4-FLUORO-BENZYL ESTER AND THE INDIVIDUAL E- AND Z-ISOMERS
 Rainer Fuchs, Bernd Gallenkamp, and Wilhelm Stendel, all of Wuppertal, Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany
 Filed Aug. 29, 1980, Ser. No. 182,356


Claims priority, application Fed. Rep. of Germany, Sep. 12, 1979, 2936864

Int. Cl.³ A01N 53/00; C07C 61/35, 69/743, 121/75


U.S. Cl. 424-304

10 Claims


1. A substantially pure isomer mixture selected from the group consisting of (±)-trans-3-(E/Z-2-chloro-2-(4-chlorophenyl)-vinyl)-2,2-dimethyl-cyclopropanecarboxylic acid (±)-2-cyano-3-phenoxy-4-fluoro-benzyl ester of the formula



(±)-trans-3-(E/Z-2-chloro-2-(4-chlorophenyl)-vinyl)-2,2-dimethyl-cyclopropanecarboxylic acid (±)-α-cyano-3-phenoxy-4-fluoro-benzyl ester of the formula



(±)-trans-3-(E-2-chloro-2-(4-chlorophenyl)-vinyl)-2,2-dimethyl-cyclopropanecarboxylic acid (±)-α-cyano-3-phenoxy-4-fluoro-benzyl ester of the formula



6. A method of combating ectoparasites which comprises applying to such ectoparasites or to a habitat thereof an ectoparasitically effective amount of an isomer mixture according to claim 1.

4,297,372

UREIDE INHIBITORS OF CONNECTIVE TISSUE DESTRUCTION

Seymour Bernstein, New City, N.Y., assignor to American Cyanamid Company, Stamford, Conn.

Division of Ser. No. 971,174, Dec. 20, 1978, Pat. No. 4,216,164, which is a continuation-in-part of Ser. No. 833,319, Sep. 14, 1977, Pat. No. 4,131,684, which is a division of Ser. No. 684,601, May 10, 1976, abandoned. This application Feb. 4, 1980, Ser. No. 118,046


Int. Cl.³ A61K 31/185

U.S. Cl. 424-315

4 Claims

1. A method of inhibiting connective tissues destruction in a warm-blooded animal suffering from said connective tissue

destruction which comprises administering to said animal an effective connective tissue destruction inhibiting amount of a compound selected from those of the formula:



wherein A is hydrogen or a pharmaceutically acceptable salt cation; B is hydrogen, lower (C₁-C₆) alkanoyl or alkali metal; and R is hydrogen.

4,297,373


METHOD OF SUPPRESSING CARDIAC ARRHYTHMIAS
 Theodore S. Sulkowski, Wayne; James L. Bergey, Lansdale, and Albert A. Mascitti, Norristown, all of Pa., assignors to American Home Products Corporation, New York, N.Y.
 Filed Oct. 9, 1980, Ser. No. 195,568

Int. Cl.³ A61K 31/17; C07C 127/00

U.S. Cl. 424-322

6 Claims

1. A method of suppressing cardiac arrhythmias in warm-blooded animals comprising administering to an animal in need thereof an amount effective to suppress such arrhythmia of a compound of the formula:



wherein:

Y is 2,6-dimethylphenyl, 2,5-dimethylphenyl, 5-bromo-2-methylphenyl, or 5-chloro-2-methylphenyl; and
 X is propenyl, propynyl, or cyclopropyl;
 or a non-toxic, pharmaceutically acceptable acid addition salt thereof.

4,297,374

SKIN MOISTURIZING AND CLEANSING CREAM
 Beatrice M. Wess, 3590 Fenley Rd., Cleveland Heights, Ohio 44121

Filed Oct. 11, 1979, Ser. No. 83,597

Int. Cl.³ A61K 47/00

U.S. Cl. 424-364

13 Claims

1. A skin moisturizing and cleansing cream comprising by volume of mixture a predominant amount of fresh fruit selected from the group consisting of bananas and avocados, the remainder being orange juice, vegetable shortening and baking powder, and said orange juice and shortening together constituting the larger proportion of said remainder.

4,297,375

SALT SUBSTITUTES HAVING REDUCED BITTERNESS
 John R. Shackelford, LaGrange, Ill., assignor to Standard Oil Company (Indiana), Chicago, Ill.

Filed Sep. 21, 1979, Ser. No. 77,562

Int. Cl.³ A23L 1/237

U.S. Cl. 426-62

7 Claims

1. A sodium-free salt substitute comprising potassium chloride and an amount of autolyzed yeast effective to reduce the bitterness caused by the potassium chloride.

4,297,376

CORN-BASED SNACK PRODUCT OF NUT-LIKE CONSISTENCY

Richard L. Nelson, 699 Riverside Dr., Battle Creek, Mich. 49015, and Walter P. Nelson, 4045 Gull Lake Dr. West, Richland, Mich. 49083

Filed Mar. 17, 1980, Ser. No. 130,749

Int. Cl.³ A21D 2/36

U.S. Cl. 426-94

11 Claims

1. A method of making an edible food product having a binder of ground corn dough comprising the steps of: preparing a ground corn dough; adding about one to ten percent by weight of uncooked, unhulled sesame seeds and about 0.5 to 2 percent by weight of algin to form a firm doughy mixture having about forty to fifty percent by weight water; molding said mixture to form a relatively three-dimensional raw article having a thickness which is at least about twenty-five percent of the width of the molded mixture forming a raw article; frying said raw article in oil, at about 325°-375° F., for a period of about six to ten minutes to thoroughly cook said article to a crunchy nut-like consistency.

4,297,377

METHOD OF MAKING FRENCH FRYABLE FROZEN POTATO STRIPS

David L. Harney, and Harlow S. Young, both of Othello, Wash., assignors to Chef-Reddy Foods Corporation, Othello, Wash. Continuation of Ser. No. 6,099, Jan. 24, 1979, abandoned. This application Mar. 3, 1980, Ser. No. 126,708

Int. Cl.³ A23B 7/03; A23L 1/216

U.S. Cl. 426-438

5 Claims

1. The method of producing French fried potatoes which comprises dividing raw, unblanched potatoes into strips, heating the strips, thereby partially gelatinizing the strips substantially throughout, partially dehydrating the strips until the partially gelatinized and partially dehydrated strips weigh about 75% to 80% of their weight when raw and the cell structure is finely granular, par-frying the partially gelatinized and partially dehydrated strips, freezing the par-fried strips, and thereafter finish frying the strips without the strips having been blanched.

4,297,378

REFRIGERATED SHELF STABLE PIE CRUST DOUGH

Michael J. Haasl, Minneapolis; Paul D. Pratt, New Brighton; Rocky W. Chen, Brooklyn Park, and Helen M. Fett, Minneapolis, all of Minn., assignors to The Pillsbury Company, Minneapolis, Minn.

Filed Jan. 31, 1980, Ser. No. 117,311

Int. Cl.³ A21D 13/08

U.S. Cl. 426-532

14 Claims

1. A dough composition adapted for making pie crust which exhibits reduced Maillard browning, said composition including:

a flour blend present in the dough in an amount in the range of between about 38% and about 50% by weight, said proportion of flour blend being calculated on the basis of dry flour blend in the dough, said flour blend having an enzyme activity based on peroxidase of less than about 0.2 absorption units with said flour blend including (a) starch in an amount such that the dough contains starch in the range of between about 37% and 47% by weight of dough based on weight of dry starch, said starch having a damage level of less than about 10%; and (b) protein in an amount such that the dough contains protein in the range of between about 1.5% and about 6% by weight of dough; shortening having an SFI value in the range of between about 29 and about 36 and a Wiley Melting Point in the range of between about 108° F. and about 118° F., said shortening being present in the dough in an amount in the range of between about 24% and about 35% by weight of dough; and

water in an amount in the range of between about 19% and about 25% by weight of dough.

4,297,379

FROZEN AERATED READY-TO-EAT GELATIN COMPOSITION

Harry H. Topalian, Dover; Clement R. Wyss, Lewes; Ralph E. Kenyon, and Anthony F. Dec, both of Dover, all of Del., assignors to General Foods Corporation, White Plains, N.Y.

Filed Mar. 27, 1980, Ser. No. 134,609

Int. Cl.³ A23L 1/04

U.S. Cl. 426—565

20 Claims

1. Process for preparing a frozen aerated starch-free gelatin composition with smooth, creamy, continuous and uniform characteristics and which is ready-to-eat at freezer temperatures comprising:

dissolving a gelatin mix in water at a temperature sufficient to dissolve the mix, said mix comprising an amount of gelatin effective to stabilize the composition and provide a smooth and creamy texture without gummy or icy characteristics, said amount being within the range of from 0.6% to less than 5% of gelatin by weight of the composition, from 5% to 50% soluble solids by weight of the composition, and acid in an amount effective to impart a pH within the range of 2.5 to 7 to the composition.

cooling the dissolved mix to a temperature of from 10° to 32° F. to at least partially freeze the mix while simultaneously aerating and agitating the dissolved mix, the aeration creating an overrun of from 3 to 200% by volume of the composition;

shaping said aerated mix; and

freezing said shaped mix to a temperature less than 10° F., said frozen mix having ice crystals of a size within the range of 20 to 200 microns.

4,297,380

TEA FLAVORING PROCESS AND PRODUCT

Ian Horman, Corseaux, and Paul Cazenave, Chavornay, both of Switzerland, assignors to Societe d'Assistance Technique pour Produits Nestle S.A., Lausanne, Switzerland

Continuation of Ser. No. 519,627, Oct. 31, 1974, abandoned.

This application Feb. 23, 1977, Ser. No. 771,075

Int. Cl.³ A23F 3/40; A23L 1/226

U.S. Cl. 426—597

30 Claims

5. A tea composition, comprising soluble tea solids and from about 0.25 to about 3 ppm methyl anthranilate as an aromatizing agent, based on the weight of the soluble tea solids.

4,297,381

METHOD OF FREEZING TOMATOES

Antonio Tenuta, Mongrassano Scalo, Cosenza, Italy

Continuation-in-part of Ser. No. 796,398, May 12, 1977, abandoned. This application Jul. 5, 1979, Ser. No. 54,823

Int. Cl.³ A23L 1/212, 3/36; A23N 7/00

U.S. Cl. 426—615

8 Claims

1. A method of freezing tomatoes and forming them into solid members free of preservatives and adapted for cutting, shaping and placement into plastic bags, comprising the steps of:

reducing the ambient temperature of the tomatoes to a freezing temperature of -30° C. for solidification, cracking the external membrane of the solidified tomatoes by subjecting them to a temperature between 30° C. to 35° C. for a total temperature gradient of ΔT between 60° C. to 65° C. above said freezing temperature, said cracking step includes the step of dipping said tomatoes into heated water having said temperature between 30° C. and 35° C.,

peeling the external membrane from the solidified tomatoes after cracking the external membrane, and reducing the temperature of the peeled tomatoes again to the freezing

temperature of -30° C. for storage of peeled tomatoes free of preservatives.

4,297,382

PROCESS FOR DRYING COMPOSITIONS CONTAINING DERIVED PROTEIN-CONTAINING COMPOSITIONS AND ADDITIVES

Dennis B. Hosaka, Hastings-on-Hudson, N.Y., assignor to Stauffer Chemical Company, Westport, Conn.

Filed Apr. 17, 1980, Ser. No. 141,221

Int. Cl.³ A23J 3/02

U.S. Cl. 426—656

15 Claims

1. A process for preparing a dried egg albumen extender from an aqueous solution of an egg albumen extender comprising at least 65% of a low molecular weight protein-containing composition derived from plant or animal sources wherein the molecular weight of said derived protein-containing composition is less than 30,000, said composition having a total Kjeldahl nitrogen content of from about 0.45% to about 2.1% of which at least 60% of the nitrogen is non-protein nitrogen and a member selected from the group consisting of from about 1% to about 15% gelatin; from about 1% to about 15% gelatin and from about 5% to about 25% of a water soluble polyphosphate, the additive total of gelatin and phosphate not to exceed about 35%, from about 0.5% to about 5% of a gum, and mixtures thereof; and from 0% to about 30% of a whipping aid, all percentages being by weight based on the total dry solids weight of the egg albumen extender exclusive of starch which comprises preparing a blend of said egg extender solution and a starch which is water soluble or swellable under conditions of drying and which is used at a level sufficient to allow effective drying of said egg extender solution, adjusting the total solids of said blend to an amount between about 15% and about 35% by weight, and drying said solution.

4,297,383

APPARATUS AND METHOD FOR OBTAINING FINGERPRINTS

Louis P. Bourdon, R.R. #3, Hwy. 17, East Twin Lakes, North Bay, Ontario, Canada (P1B 8G4)


Filed Sep. 12, 1980, Ser. No. 186,624

Claims priority, application Canada, Jul. 15, 1980, 356161

Int. Cl.³ A61B 5/10; C23C 13/06

U.S. Cl. 427—1

8 Claims



1. An apparatus for developing latent fingerprints on an object comprising a first chamber adapted to contain an object being tested for fingerprints, and to close to form an air tight seal, said first chamber having an inlet and an outlet, a second chamber adapted to contain a pool of and the vapors of the chemical cyanoacrylate, said second chamber having an inlet and an outlet, the outlet of said second chamber being connected by suitable tubing to the inlet of said first chamber, a recirculating pump means having an intake and an exhaust, said exhaust being connected to the inlet of said second chamber, said intake being connected to the outlet of said first chamber, by suitable tubing, said recirculating pump means being adapted to circulate the vapors and air between said first and second chambers so as to expose said latent fingerprints to said vapors thereby developing visible fingerprints.

6. A method for developing latent fingerprints on an object comprising placing the object to be tested in a first chamber, sealing said first chamber, exposing the interior of said first chamber and the object therein to the vapors of the chemical cyanoacrylate until said latent fingerprints become visible.

4,297,384

METHOD OF DEVELOPING ELECTROSTATIC LATENT IMAGE

Yoshio Kudo; Masakazu Iwasa, and Hisashi Kato, all of Tokyo, Japan, assignors to Fuji Photo Film Co., Ltd., Minami-ashigara, Japan

Continuation of Ser. No. 886,446, Mar. 14, 1978, abandoned.


This application Jun. 23, 1980, Ser. No. 162,021

Claims priority, application Japan, Mar. 15, 1977, 52-28363

Int. Cl.³ G03G 13/08

U.S. Cl. 427—14.1

3 Claims



1. A method of developing an electrostatic latent image by use of an apparatus comprising an electrostatic latent image carrying member, a developing roller member for applying a toner layer on the electrostatic latent image carrying member, and a doctor blade associated with the developing roller member for scraping off a part of the toner layer for controlling the thickness of the toner layer wherein said doctor blade is applied with a voltage in the same polarity as that in which the toner is charged, said doctor blade having an edge located close to the surface of the developing member to scrape off a predetermined thickness of the toner layer, and the toner scraped off by said doctor blade is sucked and exhausted by a suction means connected with said doctor blade, whereby the toner is prevented from sticking to the doctor blade.

4,297,385

PARTICULATED POLYETHERIMIDE AND METHOD FOR MAKING

Eugene G. Banucci, Scotia, and Edith M. Boldebuck, Schenectady, both of N.Y., assignors to General Electric Company, Schenectady, N.Y.

Division of Ser. No. 37,437, May 9, 1979, abandoned. This

application Apr. 7, 1980, Ser. No. 137,832

Int. Cl.³ B05D 3/02, 5/12; C08G 12/00, 69/26

U.S. Cl. 427—27

7 Claims

1. A method of coating a substrate with a continuous polyetherimide film which comprises,

(1) applying an organic solvent-free particulated polyetherimide having at least 50 mole percent of imide radicals based on the total moles of imide radicals and amide acid radicals onto the substrate, and

(2) fusing the particulated polyetherimide film at a temperature of at least 225° C.

4,297,386

CONTROL GRID IN ELECTROSTATIC FLUIDIZED BED COATER

Donald J. Gillette, Guilford, Conn., assignor to Electrostatic Equipment Corporation, New Haven, Conn.

Filed Jan. 23, 1980, Ser. No. 114,656


Int. Cl.³ B05D 1/06

U.S. Cl. 427—27

19 Claims

1. Electrostatic fluidized bed coating apparatus comprising, in combination: a housing having a generally planar substantially horizontal porous support member mounted therein to define within said housing a fluidization chamber thereabove and a plenum therebelow; means for introducing gas into said

plenum for passage upwardly through said support member to effect fluidization of particulate coating material supplied to said chamber; means to effect electrostatic charging of such particulate material; and an electrically conductive, generally planar mesh-like control grid disposed within and substantially spanning the cross-sectional area of said chamber above said support member, said grid being substantially free of horizontal flat surfaces and being adapted for control of its electrical potential, and said housing being adapted for the passage of a workpiece therethrough at a location between and spaced from each of said support member and said grid, whereby the cooperative effects of fluidization and electrostatic charging may produce a cloud of electrostatically charged particulate



material above said support member, and whereby said control grid may be used to densify and regulate such cloud, for improved coating.

16. A method for depositing of particulate material upon a workpiece comprising the steps of: forming within a fluidized bed of particles an electrostatically charged cloud thereof; increasing the density and uniformity of said cloud with an electrically conducting grid at a potential different from that of said charged particles; and passing through said cloud, at a level below and out of contact with said grid, a workpiece maintained substantially at the potential of said grid, whereby said article may acquire upon all of its exposed surfaces a substantially uniform deposit of said particles.

4,297,387

CUBIC BORON NITRIDE PREPARATION

Harry A. Beale, Columbus, Ohio, assignor to Battelle Development Corporation, Columbus, Ohio

Filed Jun. 4, 1980, Ser. No. 156,433

Int. Cl.³ C23C 11/00

U.S. Cl. 427—38

9 Claims

1. A method for deposition of cubic boron nitride on a substrate, which method comprises the steps of:

(a) supporting a substrate in a vacuum and heating the substrate;

(b) supplying metal vapors into a zone between the substrate and a metals alloy source, said source consisting essentially of at least 60 percent by weight to a balance of boron with from 2 to 12 percent by weight of aluminum and at least 0.2 to 24 percent by weight of at least one of cobalt, nickel, manganese or other aluminide-forming metal;

(c) introducing ammonia gas into said zone; and

(d) generating electrical field in said zone ionizing the metal vapors and gas atoms in the zone;

whereby a deposit comprised of cubic boron nitride is placed on the surface of said substrate.

4,297,388

PROCESS OF MAKING PERMANENT MAGNETS


Kaplesh Kumar, Wellesley; Dilip K. Das, Bedford, and Ernest C. Wettstein, Acton, all of Mass., assignors to The Charles Stark Draper Laboratory, Inc., Cambridge, Mass.

Continuation of Ser. No. 957,756, Nov. 6, 1978, abandoned. This application Apr. 8, 1980, Ser. No. 138,650

Int. Cl.³ B05D 3/14

U.S. Cl. 427—47

3 Claims



3. A process for producing aligned permanent magnets comprising the steps of: depositing molten particulate rare earth-cobalt alloy magnet material on a substrate in a crystalline state; controlling the temperature of said substrate during deposition to provide a unidirectional heat flow across the deposit of magnet material; and magnetically aligning said material.

4,297,389

ANTIFOAMING RESIN COMPOSITIONS

Robert W. Smearing, Ballston Lake, N.Y., assignor to General Electric Company, Waterford, N.Y.

Continuation of Ser. No. 744,915, Nov. 26, 1976, abandoned, which is a division of Ser. No. 604,368, Aug. 13, 1975, abandoned, which is a continuation of Ser. No. 212,700, Dec. 23, 1971, abandoned. This application May 27, 1980, Ser. No. 153,306

Int. Cl.³ B05D 5/12

U.S. Cl. 427—58

1 Claim

1. In a method of providing electrical insulation for conductor bars which comprises vacuum-pressure impregnating electrical insulation with a polyester resin suitable for impregnating insulation, the improvement which consists of mixing with said resin from about 0.05 to 10 percent, based on the resin weight, of polybutadiene in which polybutadiene at least 80 percent of the olefinic unsaturation consists of pendant vinyl groups, said polybutadiene having no other functional groups, whereby foaming is substantially eliminated from the vacuum-pressure impregnating process.

4,297,390

PROCESS FOR THE PREPARATION OF A RED EMITTING PHOSPHOR COATED WITH RED IRON OXIDE AND ITS APPLICATION

Karl Franz, Barsinghausen, and Bernd Schönfeld, Bad Nendorf, both of Fed. Rep. of Germany, assignors to Riedel-de Haen Aktiengesellschaft, Seelze, Fed. Rep. of Germany

Filed Dec. 31, 1979, Ser. No. 108,638

Claims priority, application Fed. Rep. of Germany, Jan. 4, 1979, 2900209

Int. Cl.³ C09K 11/46, 11/477, 11/465, 11/22

U.S. Cl. 427—64

11 Claims

1. A method for the preparation of a red emitting phosphor coated with red iron oxide which comprises mixing an aqueous suspension of red emitting phosphor with a polysulfide solu-

tion and a solution containing iron (II) ions to form a mixture containing said phosphor with a coating of black iron sulfide precipitate, heating the mixture to a temperature in the range of 80° C. to 100° C. to form a grey pyrite coating on the phosphor, separating the grey pyrite coated phosphor from the aqueous phase of the mixture and heating and drying said coated phosphor at a temperature in excess of 250° C. in an oxidizing atmosphere to form a red iron oxide coating on said phosphor.

4,297,391

METHOD OF APPLYING ELECTRICAL CONTACTS TO A PHOTOVOLTAIC CELL


Joseph Lindmayer, Bethesda, Md., assignor to Solarex Corporation, Rockville, Md.

Filed Jan. 16, 1979, Ser. No. 3,945

Int. Cl.³ H01L 31/04, 21/283

U.S. Cl. 136—256

4 Claims



1. A method of applying an electrically conductive contact to the back surface of a photovoltaic cell, said back surface having a p-n junction located beneath and closely adjacent thereto, comprising forming particles of a metallic material at a temperature in excess of the alloying temperature of said material and silicon, and spraying said particles toward said back surface from a distance and at a temperature such that said particles penetrate said back surface and overcome said back surface p-n junction to form a high-low junction at said back surface as well as a back contact by a single process step.

4,297,392

HIGH FREQUENCY SPUTTERING PRODUCES THIN FILM AMORPHOUS SILICON PHOTOCONDUCTOR

Akio Higashi; Kazuhiro Kawaziri, and Yosuke Nakajima, all of Asaka, Japan, assignors to Fuji Photo Film Co., Ltd., Minami-ashigara, Japan


Filed Nov. 2, 1979, Ser. No. 90,721

Claims priority, application Japan, Nov. 2, 1978, 53-135179

Int. Cl.³ B05P 5/12; G03G 5/08

U.S. Cl. 427—75

6 Claims



1. A photoconductor cell comprising a base plate; a light-sensitive layer on said base plate; and electrodes ohmically contacting said light-sensitive layer, wherein said light-sensitive layer comprises a thin film of amorphous silicon prepared by high frequency sputtering of elemental silicon under an atmosphere containing at least hydrogen onto said base plate, while maintaining the temperature of said base plate at about 50° C. to 150° C.
2. An electrophotographic element comprising a base plate with an electrically conductive surface;

a light-sensitive layer on the electrically conductive surface of said base plate; and an electrically insulating layer on said light-sensitive layer, wherein said light-sensitive layer comprises a thin film of amorphous silicon prepared by high frequency sputtering of elemental silicon under an atmosphere containing at least hydrogen onto said base plate, while maintaining the temperature of said base plate at about 50° C. to 150° C.

4,297,393

METHOD OF APPLYING THIN METAL DEPOSITS TO A SUBSTRATE


Richard Denning, Springfield; Mark A. Spak, Edison, and Barry Polhemus, Hampton, all of N.J., assignors to RCA Corporation, New York, N.Y.

Filed Feb. 28, 1980, Ser. No. 125,639

Int. Cl.³ C23C 3/02; H01L 21/288

U.S. Cl. 427—88

20 Claims



1. A method of applying thin metal sensitizing deposits from aqueous solution to the exposed silicon areas of a silicon substrate having exposed areas of silicon and silicon oxide, which comprises, immersing the silicon substrate in a basic, aqueous solution containing a metal salt of the metal to be deposited, not containing a reducing agent and reducing the metal ion by use of the exposed silicon as the reducing agent to the elemental metal.

4,297,394

PIEZOELECTRIC POLYMER ANTIFOULING COATING AND METHOD OF USE AND APPLICATION


Bruce J. Wooden, Dickerson, and Seymour Edelman, Silver Spring, both of Md., assignors to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Continuation-in-part of Ser. No. 44,130, May 31, 1979. This application Mar. 18, 1980, Ser. No. 132,607

Int. Cl.³ B05D 5/12; H01L 41/22

U.S. Cl. 427—100

12 Claims



1. A method of coating the outer surface of an electrically conductive marine structure with a plural layer continuous film for reducing fouling thereon comprising the steps of: preparing the surface of the structure to insure maximum electrical conductivity; applying a layer of electrically conductive cement to sub-

stantially the entire outer surface to be contacted by water containing fouling organisms; applying a continuous layer of piezoelectric polymer over the cement; applying another layer of electrically conductive cement to the polymer layer; and applying another continuous layer of piezoelectric polymer for interfacing with water.

4,297,395

PRODUCTION OF COBALT-DOPED FERRIMAGNETIC IRON OXIDES

Gunter Buxbaum; Heinrich-Christian Schopper; Lutz Leitner, and Volker Hahnkamm, all of Krefeld, Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Jan. 10, 1980, Ser. No. 110,876

Claims priority, application Fed. Rep. of Germany, Jan. 31, 1979, 2903593

Int. Cl.³ C01G 49/02

U.S. Cl. 427—127

2 Claims

1. A process for the production of a cobalt-doped iron oxide acicular pigment protected at least partly against sintering comprising forming a suspension of FeOOH seeds in water containing zinc, phosphate and ferrous ions, introducing cobalt ions, adding alkali and air to precipitate ferric and cobalt ions onto the seeds, adding a phosphate solution in quantity of from about 0.2 to 1% by weight of P₂O₅ into the water containing the seeds which are now pigment, separating the pigment from the suspension, reducing the pigment to Fe₃O₄, oxidizing the Fe₃O₄ pigment in an oxygen-containing gas to bring the FeO content in the pigment to about 16 to 24% by weight, and heat treating the oxidized pigment under inert conditions at a temperature of about 600° to 800° C., the amount of zinc, cobalt and phosphate ions present being such as to impart to the end product a content by weight of about 0.7 to 2.4% of cobalt, about 0.1 to 2% of zinc, and about 0.1 to 2% of phosphorus expressed as P₂O₅, the coercive force of the resulting pigment amounting to at least about 425 Oe + 175 Oe/% by weight, of Co.

4,297,396

COATING METHOD

Nobumitsu Takehara, and Shogo Isayama, both of Minami-ashigara, Japan, assignors to Fuji Photo Film Co., Ltd., Minami-ashigara, Japan


Filed Dec. 7, 1979, Ser. No. 101,383

Claims priority, application Japan, Dec. 19, 1978, 53-158762

Int. Cl.³ B05D 5/00

U.S. Cl. 427—284

8 Claims



1. A slide bead coating method comprising the steps of: supplying a first coating liquid over at least a portion of a slide surface between guide plates disposed on both sides of said slide surface and supplying a second coating liquid lower in viscosity than said first coating liquid at a flow rate lower than that of said first coating liquid to both sides of said slide surface through an aperture in each of said guide plates.

4,297,397

CATALYTIC PROMOTERS IN ELECTROLESS PLATING CATALYSTS IN TRUE SOLUTIONS

Nathan Feldstein, 63 Hemlock Cir., Princeton, N.J. 08540
Continuation of Ser. No. 940,355, Sep. 7, 1978, abandoned, which is a division of Ser. No. 833,905, Sep. 16, 1977, Pat. No. 4,151,311, which is a continuation-in-part of Ser. No. 651,507, Jan. 22, 1976, abandoned. This application Apr. 28, 1980, Ser. No. 144,428

Int. Cl.³ C23C 3/02

U.S. Cl. 427—304

14 Claims

1. A process for the electroless metal deposition onto a non-conductor comprising:

- (1) contacting said non-conductor with a catalytic solution comprising the admixture of a principal catalytic agent wherein said principal catalytic agent is a compound of a metal selected from the group of metals consisting of copper, nickel, cobalt, and iron and mixtures thereof and a catalytic promoter agent wherein said catalytic promoter agent is a compound of a metal selected from the group of metals consisting of Mg, Ca, Sr, Sc, Y, La, Ti, Zr, Hf, Nb, Ta, Cr, Mn, Tc and Re and mixtures thereof and further wherein the concentrations for the principal catalytic agent and the catalytic promoter agent are so adjusted as to yield a catalytic solution having a greater catalytic activity for electroless metal deposition in comparison to the same catalytic solution in the absence of said catalytic promoter agent, and
- (2) contacting the treated non-conductor with an electroless metal deposition bath.

4,297,398

MANUFACTURING COATED STEEL STRIP

Philippe Paulus, Liege, Belgium, assignor to Centre de Recherches Metallurgiques-Centrum voor Research in de Metallurgie


Filed Mar. 3, 1980, Ser. No. 126,387

Claims priority, application Belgium, Nov. 2, 1979, 874599

Int. Cl.³ C23C 1/02, 1/08

U.S. Cl. 427—320

9 Claims



1. A method of manufacturing coated steel strips comprising the sequential steps of:

- heating the strip to a temperature higher than its recrystallization temperature,
- holding the strip at this temperature,
- cooling the strip to a temperature now lower than that of a subsequent bath in a preliminary cooling stage,
- immersing the strip in a molten metal bath maintained at a temperature higher than 500° C., the molten metal having a melting point lower than 800° C.,
- cooling the strip until the metal coating has solidified in a first cooling stage, and
- subjecting the strip immediately thereafter to a more intense and more rapid second cooling stage which does not impair the flatness of the strips to a temperature lower than 475° C. by quenching the strip in an aqueous bath held at a temperature higher than 75° C.,
- followed by more slowly cooling the strip to ambient temperature;
- with the proviso that the period of time between the beginning of the preliminary cooling stage and the beginning of

the second cooling stage is not shorter than 20 seconds and not longer than 100 seconds.

4,297,399

METHOD FOR CURING CONCRETE

John S. Perz, Mentor, Ohio, assignor to Martin Marietta Corporation, Bethesda, Md.

Filed Jan. 8, 1980, Ser. No. 110,294

Int. Cl.³ B05D 1/00

U.S. Cl. 427—385.5

9 Claims

1. A method for curing concrete comprising applying to the surface of the concrete, as a curing compound, a composition comprising Singapore dammar resin and an organic solvent for said resin.

4,297,400

PROCESS FOR IMPARTING TO TEXTILE MATERIALS A SOFT HANDLE USING UNSATURATED ALIPHATIC ACID AMIDES

Jörg Kern, Waldkraiburg, Fed. Rep. of Germany, and Christian Guth, Basel, Switzerland, assignors to Ciba-Geigy Corporation, Ardsley, N.Y.

Filed Aug. 8, 1979, Ser. No. 64,659


Claims priority, application Switzerland, Aug. 18, 1978, 8788/78

Int. Cl.³ B05D 3/02

U.S. Cl. 427—389

12 Claims

1. A process for imparting to a textile material a soft handle, which process comprises immersing the material at 20° to 100° C. for 5 to 120 minutes in an aqueous preparation containing an acid amide of the formula



or a reaction product from acrylic or methacrylic acid, or an alkyl ester thereof, and an amine of the formula



wherein R₁ is alkyl or alkenyl of 14 to 22 carbon atoms and X is hydrogen or methyl, and subsequently drying the material at 50° to 150° C.

4,297,401

LIQUID CRYSTAL DISPLAY AND PHOTOPOLYMERIZABLE SEALANT THEREFOR


Mao-Jin Chern, Woodbury, and Robert D. Lowrey, White Bear Lake, both of Minn., assignors to Minnesota Mining & Manufacturing Company, St. Paul, Minn.

Filed Dec. 26, 1978, Ser. No. 973,149

Int. Cl.³ B32B 17/10; C09K 3/34


U.S. Cl. 428—1

11 Claims



1. An improved liquid crystal display cell comprising a pair of half-cells having portions thereof bonded together by organic seal means wherein the improvement comprises an organic seal means comprising a photopolymerized sealant comprising a polymerized mixture of:

- (a) cationically polymerizable epoxide with a functionality of at least 1; and
- (b) an organic aromatic onium catalyst comprising an aromatic adduct of
 - (1) a diaromatic, triaromatic, or tetraaromatic organoatomic cation of a Group Va, VIa, or VIIa atom and
 - (2) an anion; said onium catalyst being represented by the formula:



wherein

R² is an aromatic group at least as electron withdrawing as benzene,

R¹ is an alkyl or alkenyl group,

A is a Group Va, VIa, or VIIa atom,

X is an anion,

n is a positive whole integer of at least 2 up to the valence of A plus one,

a is 0 or a positive whole integer up to the valence of A minus one, and

n plus a is equal to the valence of A plus one and wherein at least two of said R² groups are bonded to A;

said photopolymerized sealant being chemically resistant to liquid crystal materials.

4,297,402

PACKAGING BAG

Koichi Kinbara; Norimaro Sugimoto, both of Kawasaki, and Toshitaka Nakazawa, Kure, all of Japan, assignors to Meito Co. Ltd. and Toyo Pulp Co. Ltd., both of Tokyo, Japan


Filed Apr. 18, 1980, Ser. No. 141,580

Claims priority, application Japan, Apr. 21, 1979, 54-53536[U]; May 8, 1979, 54-60911[U]

Int. Cl.³ B65D 33/02; B32B 3/30, 5/12, 7/04

U.S. Cl. 428—35

5 Claims



1. A packaging bag fabricated by a reinforced sheet in which a non-woven cross-linked plastic sheet of split films with narrow width crossing each other is inserted between combination cellulose papers in a manner that the intersections of the split films of the non-woven plastic sheet are presented at least on one side surface of the sheet in protruded pattern.

4,297,403

CORELESS PRESSURE SENSITIVE LABEL SUPPLY ROLL

Thomas M. Smith, Dayton, Ohio, assignor to Monarch Marking Systems, Inc., Dayton, Ohio

Filed Feb. 6, 1980, Ser. No. 119,123


Int. Cl.³ B32B 3/16, 7/06

U.S. Cl. 428—42

9 Claims

1. A coreless pressure sensitive label supply roll comprising a series of pressure sensitive labels releasably bonded by pressure sensitive adhesive to a releasable surface of an elongated carrier web, the assembly of the carrier web and labels being wound into a supply roll adapted to be used in a label printing

and applying device where the labels are successively printed and then successively peeled from the carrier web, the carrier web having an inner convolution defining a center opening, the inner convolution of the carrier web having a folded end portion forming a first end section extending from



and folded back over a radially underlying second end section, and means connecting the first end section of the carrier web to a radially overlying portion of the carrier web to provide the carrier web with a connected loop forming the inner end of the carrier web.

4,297,404

NON-WOVEN FABRIC COMPRISING BUDS AND BUNDLES CONNECTED BY HIGHLY ENTANGLED FIBROUS AREAS AND METHODS OF MANUFACTURING THE SAME


Hien V. Nguyen, East Windsor, N.J., assignor to Johnson & Johnson, New Brunswick, N.J.

Continuation-in-part of Ser. No. 31,086, Apr. 18, 1979, abandoned, which is a continuation-in-part of Ser. No. 806,033, Jun. 13, 1977, abandoned. This application Jan. 9, 1980, Ser. No. 110,719

Int. Cl.³ D04H 1/46, 1/70

U.S. Cl. 428—85

11 Claims



1. A non-woven fabric with a plurality of patterns of groups of fiber segments that alternate and extend throughout the fabric which comprises: groups of fiber segments in discontinuous portions of the fabric, said discontinuous portions forming a first pattern, each of said groups including at least one nub of fiber segments interentangled in helter-skelter arrangement, said nub protruding out of the plane of the fabric, each of said groups also including at least one yarn-like bundle of fiber segments wherein the fiber segments are in close proximity and substantial parallelism to one another, said first discontinuous portions of the fabric being bound and interconnected by a continuous highly entangled, interlaced fibrous area, said continuous portion forming a second pattern and the fibers in said continuous portion being entangled in substantially all directions including the thickness of the fabric, said fabric having a bulk density of from 0.04 grams per cubic centimeter to 0.084 grams per cubic centimeter and a tenacity of at least 0.5 pounds per inch per 100 grains per square yard.

4,297,405

CORROSION RESISTANT METALLIC ARTICLE HAVING A MATT NACREOUS APPEARANCE

Nobuyoshi Kasahara, Sayama, and Koutaro Nonomura, Kunitachi, both of Japan, assignors to Mitsui Mining & Smelting Co., Ltd., Tokyo, Japan

Filed Jan. 5, 1979, Ser. No. 1,347

Claims priority, application Japan, Jan. 9, 1978, 53-537; Jan. 9, 1978, 53-538; Jan. 9, 1978, 53-539

Int. Cl.³ B32B 19/02; B05D 5/02

U.S. Cl. 428—141

9 Claims

1. A process for the production of a metallic article having a matt nacreous appearance and improved corrosion resistance, comprising the steps of:

subjecting to chemical treatment a metallic substrate made of a metal selected from the group consisting of zinc, aluminum, magnesium and alloys thereof as white-silvery metals to form a substantially colorless transparent film having improved corrosion resistance on the surface of the metallic substrate,

coating the corrosion resistant film-covered metallic substrate with a clear paint comprising a nacreous pigment in fine flaky form having a colorless and transparent appearance by spraying the paint to the corrosion resistant film at a lower feeding rate than that necessary for arranging the flaky pigment in substantially lamellate form and a spraying air pressure generally higher than that necessary therefor, the nacreous pigment being a nacreous compound selected from the group consisting of (1) oxides and salts of elements of Groups IV and V of the Periodic Table and (2) composite composed of mica and said nacreous compound coated thereon, to form a coating having a finely undulated surface on said corrosion resistant film and then drying the thus formed clear paint coating having the finely undulated surface on the film-covered metallic substrate to produce the metallic article.

9. A metallic article having a light reflectivity of 30–60% produced by the process of claim 1 or 2.

4,297,407

FINISH COMPOSITION FOR THE SPINNING OF HIGHLY CRIMPED CELLULOSE FIBERS USING A COMPOSITION CONT. FATTY ACID ESTER, ORGANIC PHOSPHORIC ACID ESTER, FATTY ACID ETHYLENE OXIDE COND. PROD. AND FATTY ACID SALT

Francesco Manca, Milan, Italy, assignor to Snia Viscosa Società Nazionale Industria Applicazioni Viscosa S.p.A., Italy

Filed May 31, 1979, Ser. No. 44,103

Claims priority, application Italy, Jun. 5, 1978, 24224 A/78


Int. Cl.³ D06M 13/26, 13/32, 13/18; D03D 3/00

U.S. Cl. 428—224

30 Claims

1. A composition adapted to facilitate the cotton type spinning of highly crimped cellulosic fibers comprising the following components:

(A) from 10 to 30%, by weight of at least one compound having the formula:



wherein R and R', equal to or different from one another are straight or branched chain alkyl radicals, comprising all together 8 to 40 carbon atoms;

(B) from 8 to 15%, by weight of at least an organic ester of phosphoric acid, wherein only a part of the acid groups have been esterified, the remaining acid groups being free or salified, said ester being in the form of a monomer or a polymer;

(C) from 50 to 70%, by weight of at least one product obtained by the condensation of fatty acids with alkylene oxide or polyalkyleneglycols, wherein the alkylene moiety contains 2 or 3 carbon atoms;

(D) up to 0.5% by weight of organic or inorganic alkali metal salts having a high solubility in water;

and

(E) the amount required to make up 100% of an composition, of at least one alkali metal salt of a fatty acid containing from 6 to 20, preferably 18 carbon atoms.

4,297,408

LAMINATES OF CLOTH AND FILLED CRYSTALLINE POLYPROPYLENE AND A METHOD FOR MAKING THEM

John C. Stead, Knebworth, and Peter E. Waghorn, Welwyn Garden City, both of England, assignors to Imperial Chemical Industries Limited, London, England

Filed Dec. 17, 1979, Ser. No. 104,058

Claims priority, application United Kingdom, Dec. 29, 1978, 50242/78

Int. Cl.³ B32B 27/12, 27/20, 27/32, 31/08

U.S. Cl. 428—240

5 Claims

1. A laminate comprising cloth or other sheet material and a layer of a filled crystalline polypropylene composition containing 20 to 80% by weight of a particulate filler wherein the cloth or other sheet material is adhered to a surface of the layer of filled polypropylene composition by means of a layer of unfilled random copolymer of propylene with up to 10% (by weight of the copolymer) of ethylene interspersed between the cloth or other sheet material and said surface.

3. A method for making a laminate as claimed in claim 1 wherein the method comprises:

(a) heating the filled and unfilled polypropylene compositions to temperatures above the crystalline melting points of their polypropylenes,

(b) contacting a surface of the filled composition with a surface of the unfilled composition before, during or after heating,

(c) contacting the cloth or other sheet material with another surface of the unfilled composition under conditions of

4,297,406

PRODUCT FOR TREATING FABRIC

John L. Metcalfe, Wirral, and Douglas Wraige, Newton, both of England, assignors to Lever Brothers Company, New York, N.Y.

Continuation of Ser. No. 842,827, Oct. 17, 1977, abandoned, which is a continuation of Ser. No. 782,191, Mar. 28, 1977, abandoned. This application Feb. 1, 1979, Ser. No. 8,650

Claims priority, application United Kingdom, Mar. 30, 1976, 12832/76

Int. Cl.³ B32B 7/02, 3/26

U.S. Cl. 428—215

9 Claims

1. A fabric treating product comprising:

(a) a first and second outer layer of resiliently flexible foamed polymer substrate having a relatively dense structure; laminated to;

(b) an inner layer of resiliently flexible foamed polymer substrate having a relatively less dense structure and being positioned between said first and second outer layers; and

(c) a fabric conditioning agent impregnated into said inner layer and said first and second outer layers.

2. A fabric treatment product according to claim 1, wherein said first and second outer layers and said inner layer are in sheet form, said first and second outer layers each have a thickness of from about 0.5 mm to about 4 mm and the overall thickness of the product is from about 0.2 cm to about 2.5 cm.

temperature and pressure such that some unfilled composition flows into the cloth or into intimate contact with the other sheet material and then

(d) cooling the filled and unfilled compositions to below their crystalline melting points whereupon the unfilled composition bonds the cloth or other sheet material to the filled composition to form the laminate.

4,297,409

MANUFACTURE OF ARTICLES FROM AN ORGANIC MATERIAL AND A WATER-HARDENABLE MASS

David J. Hannaht, Great Bookham, England, assignor to University of Surrey, Surrey, England, a part interest


Continuation-in-part of Ser. No. 30,428, Apr. 16, 1979, abandoned, which is a continuation-in-part of Ser. No. 809,394, Jun. 23, 1977, abandoned. This application Nov. 6, 1979, Ser. No. 92,416

Claims priority, application United Kingdom, Jul. 1, 1976, 27371/76

Int. Cl.³ B32B 7/00

U.S. Cl. 428—247

33 Claims



1. An article comprising a water-hardened mass and a continuous network of fibrillated film in the form of a plurality of layers embedded in the water-hardened mass, the volume of film amounting to more than 1½% by volume of the overall volume of the article and the fibrils of said film providing continuous mechanical and frictional bonding to reinforce the water-hardened mass so that under excess loading the article exhibits multiple fine cracks without rupture.

4,297,410

ABSORBENT MATERIAL

Yoshimi Tsuchiya, Utsunomiya, Masayuki Sagae, Tochigi, and Hiroshi Mizutani, Yachiyo, all of Japan, assignors to Kao Soap Co., Ltd., Tokyo, Japan


Filed Oct. 2, 1979, Ser. No. 81,234

Claims priority, application Japan, Oct. 12, 1978, 53-140165

Int. Cl.³ B32B 5/16

U.S. Cl. 428—283

7 Claims



1. An absorbent material consisting essentially of: a first, non-woven fabric, absorbent sheet consisting essentially of absorbent fibers capable of absorbing exudations from the human body and from 10 to 50% by weight of thermoplastic polyolefin fibers; a multitude of particles deposited on one surface of said first sheet so as to form a discrete layer of said particles on said one surface of said first sheet wherein said particles project upwardly above said one surface of said first sheet, said particles consisting essentially of hydrophilic polymeric substance capable of absorbing water in an amount at least 30 times the weight of said hydrophilic polymeric substance, said particles being meltadhered to said thermoplastic

4,297,411

HEAT SEALABLE PACKAGING FILM COMPRISING PROPYLENE POLYMER SUBSTRATE AND A SURFACE LAYER OF AN ETHYLENE COPOLYMER AND A DIFFERENT OLEFIN COPOLYMER

Milton L. Weiner, Rochester, N.Y., assignor to Mobil Oil Corporation, New York, N.Y.

Filed Oct. 5, 1979, Ser. No. 82,360

Int. Cl.³ C09J 7/02; B32B 27/08

U.S. Cl. 428—347

9 Claims

1. A multiple-layer, heat-sealable film comprising (a) a substrate layer consisting essentially of a homopolymer of polypropylene, a copolymer of polypropylene, or a blend of said homopolymer or copolymer containing up to 40% by weight of a different compatible polyolefin or polyolefin blend; and

(b) on at least one of the surfaces of the substrate layer, a surface layer comprising a blend of 5–95 weight percent of a copolymer of ethylene (10–75 mole percent) and a higher olefin having 4 or more carbon atoms (90–25 mole percent), and 95–5 weight percent of a different copolymer of an alpha olefin having 2 or more carbon atoms (2–98 mole percent) and a different higher olefin having 3 or more carbon atoms (98–2 mole percent);

4,297,412

TWO-COMPONENT MIXED ACRYLIC FIBRES WHEREIN ACRYLIC COMPONENTS HAVE DIFFERENT AMOUNTS OF NON-IONIZABLE PLASTICIZING COMONOMER

Georges Achard, Decines; Pierre Chion, Bron, and Jacques Menault, Charbonnières-les-Bains, all of France, assignors to Rhone-Poulenc-Textile, Paris, France

Filed Nov. 28, 1979, Ser. No. 97,954

Claims priority, application France, Nov. 30, 1978, 78 34054

Int. Cl.³ B32B 27/02; D01F 8/08; D02G 1/18, 3/00

U.S. Cl. 428—370

6 Claims

1. Two-component mixed acrylic composite fibres and yarns with a natural crimp, suitable for carding, stretch breaking and converting said fibers consisting of a mixture of monolaminar, bilaminar and multilaminar strands and made of two polymers A and B, polymer A comprising at least 83% by weight of acrylonitrile, 4 to 15% by weight of a non-ionisable plasticising comonomer, and up to 2% by weight of an acid comonomer which is copolymerisable with acrylonitrile, and polymer B comprising at least 94% by weight of acrylonitrile, 0 to 4% by weight of a non-ionisable plasticising comonomer and up to 2% by weight of an acid comonomer which is copolymerisable with acrylonitrile, the difference in the proportion of plasticising comonomer in the polymers A and B being between 4 and 15% by weight and the total number of milliequivalents of acid in the two polymers being at least 50 per kg of polymer, the said composite fibres and yarns possessing a three-dimensional crimp, the direction of which depends on the heat and/or mechanical treatments to which the composite fibres or yarns have been subjected, polymer B being located on the inside of the helix formed by strands which have been subjected, without tension, to a temperature below about 110° C. and at least equal to ambient temperatures (crimp C 1), and being located on the outside of the helix formed by strands which have been subjected to tension and/or heat treatment at a temperature above about 110° C. (crimp C 2), the contraction and frequency of the two types of crimp varying from one strand to the next and along the length of one strand.

4,297,413

CONCENTRIC COMPOSITE CONJUGATE YARNS AND A PROCESS FOR MANUFACTURING SAME

Tohru Sasaki, Hiroyuki Endoh, and Hiroshi Ohhira, all of Iwaki, Japan, assignors to Kureha Kagaku Kogyo Kabushiki Kaisha, Tokyo, Japan


Division of Ser. No. 928,301, Jul. 26, 1978, abandoned. This application Apr. 23, 1980, Ser. No. 143,145

Claims priority, application Japan, Jul. 27, 1977, 52-89197

Int. Cl.³ D02G 3/00

U.S. Cl. 428—394

8 Claims



1. A concentric stretched conjugated yarn having
 - (A) A polyfin core component which is initially pre-stretched to have a double refraction index of from 10×10^{-3} to 25×10^{-3} , and
 - (B) A concentric sheath component which is a polyamide or polyester fused resin and which is initially unoriented, with the proviso that the conjugated yarn is stretched until the double refraction index of the polyolefin core component is at least 30×10^{-3} .

4,297,414

REINFORCING MATERIAL FOR HYDRAULIC SUBSTANCES AND METHOD FOR THE PRODUCTION THEREOF

Hisashi Matsumoto, Iwakuni, Japan, assignor to Mitsui Petrochemical Industries, Ltd., Tokyo, Japan


Filed Jun. 25, 1979, Ser. No. 51,387

Claims priority, application Japan, Jul. 7, 1978, 53-81917; Jul. 17, 1978, 53-86182; Dec. 20, 1978, 53-160804

Int. Cl.³ D02G 3/00

U.S. Cl. 428—400

15 Claims



1. Reinforcing material for hydraulic substances, which consists essentially of an elongated, stretched product of a synthetic resin, the product having a thickness of 3000 denier to 12,000 denier and having discontinuous protrusions over its entire length, the height of the protrusions being not less than 0.1 mm.

4,297,415

HEAT-SEALABLE POLYPROPYLENE FILMS

Herbert J. Ward, Bristol; Derek J. Dobbie, and Brian Lyall, both of Bridgwater, all of England, assignors to British Cellophane Limited, Somerset, England

Filed Aug. 23, 1979, Ser. No. 69,091

Claims priority, application United Kingdom, Sep. 6, 1978, 35846/78

Int. Cl.³ B32B 27/32, 31/14

U.S. Cl. 428—516

9 Claims

1. A heat-sealable oriented polypropylene film comprising a base film of oriented polypropylene film having on one surface a layer of a random propylene/ethylene copolymer in which the ethylene content lies in the range between 2% and 6% by weight and on the other surface a predominantly linear random copolymer of ethylene and between 6% and 40% by weight of the random copolymer of at least one further alpha olefin having at least three carbon atoms per molecule.

5. A method of the manufacture of a heat-sealable oriented polypropylene film comprising applying to one surface of a base polypropylene film a layer of a random propylene/ethylene copolymer in which the ethylene content lies in the range between 2% and 6% by weight and to the other surface a predominantly linear random copolymer of ethylene and between 6% and 40% by weight of the random copolymer of at least one further alpha olefin having at least three carbon atoms per molecule, bringing the combination to a stretch orientable condition and stretching in at least one direction.

4,297,416

GOLD ALLOY WIRE FOR JEWELRY CHAINS

Hans Krug, Pforzheim, and Kurt Heilmann, Eisingen, both of Fed. Rep. of Germany, assignors to Ferd. Wagner, Pforzheim, Fed. Rep. of Germany


Filed Jun. 13, 1979, Ser. No. 48,586

Claims priority, application Fed. Rep. of Germany, Jul. 4, 1978, 2829284

Int. Cl.³ B23K 35/22, 35/30, 35/00

U.S. Cl. 428—576

6 Claims



1. In a gold alloy wire suitable for the production of jewelry, especially jewelry chains consisting essentially of a gold solder containing nucleus and a jacket of gold alloy the improvement comprising said solder containing nucleus having a core of fine gold surrounded by an adjacent layer of ductile, lower melting gold solder alloy.

4,297,417

PHOTOSENSITIVE COLORED GLASSES EXHIBITING ALTERABLE PHOTO-ANISOTROPIC EFFECTS

Che-Kuang Wu, Horseheads, N.Y., assignor to Corning Glass Works, Corning, N.Y.

Division of Ser. No. 924,508, Jul. 14, 1978, Pat. No. 4,191,547.

This application Oct. 19, 1979, Ser. No. 86,589

Int. Cl.³ B32B 17/00; G02F 3/00

U.S. Cl. 428—410

2 Claims

2. A photosensitive optical information storage medium for storing optical information utilizing photo-anisotropic effects comprising a photosensitive colored glass article exhibiting alterable photo-anisotropic effects consisting of a body portion

4,297,419

ANODE-MATRIX COMPOSITE FOR MOLTEN CARBONATE FUEL CELL


Richard C. Nickols, Jr.; John C. Trocicola, both of Glastonbury, Conn., and James E. Rourke, East Windsor, N.J., assignors to United Technologies Corporation, Hartford, Conn.

Filed Sep. 24, 1980, Ser. No. 189,888


Int. Cl.³ H01M 4/86

U.S. Cl. 429—44

10 Claims



- 10-17% Na₂O and/or K₂O, 5-15% ZnO, 0.5-5% Al₂O₃, and 0.1-3% Cl, said surface layer containing about 1-8% by weight H₂O and about 2-20% by weight Ag, the proportion of Na⁺ and/or K⁺ ions in said surface layer being less with a corresponding increase in Ag⁺ ions, and the Ag portion of said crystals is present as a layer on the surface of the crystals and/or is contained within said crystals.



1. A molten carbonate fuel cell anode-matrix composite comprising an alkali metal carbonate impregnated cerium oxide substrate having adjacent sections of greater and lesser pore sizes, the section of greater pore size being electron conductive and anode catalytic under molten carbonate fuel cell operating conditions, and the section of lesser pore size being substantially non-catalytic and non-electron-conductive under molten carbonate fuel cell operating conditions.

6. A molten carbonate fuel cell comprising an anode matrix composite comprising an alkali metal carbonate impregnated cerium oxide substrate having adjacent sections of greater and lesser pore sizes, the section of greater pore size being electron conductive and anode catalytic under molten carbonate fuel cell operating conditions and the section of lesser porosity being substantially non-catalytic and non-conductive under molten carbonate fuel cell operating conditions, and a cathode electrode in contact with the anode-matrix composite on the matrix side of the composite.

4,297,418

COMPONENT STRAND FOR WIRE FABRICS


Harmon W. Arnold, and Galen B. Erwin, both of Carthage, Mo., assignors to Flex-o-lators, Inc., Carthage, Mo.

Filed May 29, 1979, Ser. No. 43,112

Int. Cl.³ B21F 33/00

U.S. Cl. 428—595

5 Claims



1. A wire fabric formed of a plurality of component strands extending in generally parallel, spaced apart relation, and a plurality of cross wires extending transversely to said component strands in generally parallel, spaced apart relation, each of said cross wires being attached to each of said component strands at its point of intersection therewith by piercing said strand, at least one of said component strands comprising:

- a. a longitudinally extending core wire, and
- b. a longitudinally extending sheath in which said core wire is embedded, said sheath being formed of a relatively soft, flexible and pierceable material, and having its external surface formed to present at least a pair of diametrically opposite, longitudinally extending grooves to configurate said strand cross-sectionally to form a pair of enlarged heads connected by a neck of reduced thickness, said cross wires piercing said neck, said core wire being embedded in one of the heads of said sheath, offset from the neck thereof, whereby not to interfere with the piercing of said neck by said cross wires.

4,297,420

ELECTRODE FOR A LEAD ACCUMULATOR

Bernard Chenaux, Paris, and Alain Leroux, St-Cheron, both of France, assignors to Compagnie Generale d'Electricite, Paris, France


Continuation of Ser. No. 86,447, Oct. 19, 1979, abandoned. This application Sep. 24, 1980, Ser. No. 190,401

Claims priority, application France, Oct. 27, 1978, 78 30591

Int. Cl.³ H01M 4/62

U.S. Cl. 429—217

3 Claims



1. An electrode for a lead accumulator of the type which includes an electronically conductive core coated with an active material which contains grains of lead monoxide, lead sulphate and a binding agent which is suitable for forming a three-dimensional network of fibres, wherein said electrode further includes a material which is insoluble in sulphuric acid, is permeable to conductivity ions and forming a film over said

grains, the material being chosen from the group which includes polyacrylic acid and hydroxyethylmethacrylate and being used in a proportion by weight of 0.25 to 2% with respect to said lead monoxide.

4,297,421


BATTERY AND ELECTROLYTIC CELL ELECTRODES
Pierre P. Turillon, Ramsey, N.J.; Michael N. Hull, and George F. Nordblom, both of Yardley, Pa., assignors to The International Nickel Co., Inc., New York, N.Y.

Filed Nov. 10, 1977, Ser. No. 850,290

Int. Cl.³ H01M 4/56

U.S. Cl. 429—225

62 Claims



1. An article of manufacture, adapted to be used with an electrolyte such that when in use at least part of one surface of said article is exposed to said electrolyte and, at least part of the time, is at an oxidizing potential comprising, at least adjacent said at least part of one surface, a matrix of a metal anodically passivated in said electrolyte at said oxidizing potential containing a maze of tortuous paths essentially filled adjacent said at least part of one surface with an electroconductive oxide essentially insoluble in said electrolyte and the remainder of said maze paths of said maze is filled with metal in direct contact with said electroconductive oxide, said oxide being confined by the walls of said paths, essentially blocking entry of said electrolyte to the interior of said matrix thereby maintaining the electrolyte-article interface at the external surface of the article and providing a means of electrical conductivity at said oxidizing potential between said electrolyte and the interior of said article.

4,297,422

ELECTROPHOTOGRAPHIC PROCESS FOR PRINTING A PLURALITY OF COPIES

Eiichi Sato, Tama, Japan, assignor to Olympus Optical Company Limited, Tokyo, Japan

Filed Jul. 18, 1978, Ser. No. 925,693

Claims priority, application Japan, Jul. 21, 1977, 52-87556

Int. Cl.³ G03G 13/16, 13/22, 13/24

U.S. Cl. 430—54

14 Claims

1. An electrophotosensitive process for printing a plurality of copies with a single imagewise exposure of a document to be duplicated comprising

- a step for effecting a uniform primary electrification with one polarity for a photosensitive member;
- a step for forming on the uniformly charged photosensitive member a primary electrostatic latent image corresponding to an image of the document by effecting the imagewise exposure;
- a step for developing the primary latent image with toner developer having charged in the other polarity to form on the photosensitive member a toner image;
- a step for placing a transparent or translucent transfer member over a surface of the photosensitive member on which surface the toned image has been formed;
- a step for effecting a secondary electrification with the

one polarity by applying a transferring electric field from the side of the transfer member in such a manner that a potential at an imagewise dark portion on the photosensitive member on which portion the toner has been applied will assume a substantially same potential as that of the primary electrostatic latent image after a transfer and for effecting a secondary exposure with light having a wavelength which is substantially absorbed by the toner developer also from the side of the transfer member in such a manner that undesired charge applied at an imagewise bright portion on the photosensitive member is decayed, but the charge on the imagewise dark portion is not decayed due to the presence of the light impermeable toner so as to be able to form on the photosensitive member a secondary electrostatic latent image having an image information substantially corresponding to the primary latent image after the transfer, said secondary electrification and secondary exposure being simultaneously or successively effected, while the transfer member is placed over the photosensitive member; and

- a step for separating the transfer member from the photosensitive member to transfer the toner image onto the transfer member;

whereby the steps (c) to (f) are repeated successively for the secondary latent image repeatedly formed on the photosensitive member to form a number of duplicated copies.

4,297,423

ELECTROPHOTOGRAPHIC PROCESS FOR MULTIPLE IMAGES

Masaji Nishikawa, Hachioji, Japan, assignor to Olympus Optical Company Limited, Tokyo, Japan

Filed Nov. 24, 1978, Ser. No. 963,358

Claims priority, application Japan, Nov. 30, 1977, 52-142691

Int. Cl.³ G03G 13/16, 13/22

U.S. Cl. 430—54

3 Claims

1. An electrophotographic process using a composite photosensitive body which has an electrically conductive substrate, an inorganic photoconductive semiconductor layer and an organic photoconductive semiconductor layer, said inorganic and organic photoconductive semiconductor layers being applied on said substrate in this order comprises the following successive steps:

- a step of uniformly charging the composite photosensitive body in one polarity for which the composite photosensitive body exhibits a high response to visible light;
- a step of exposing the uniformly charged composite photosensitive body to an optical image of an original to be duplicated with the visible light for forming a first electrostatic latent image of one polarity;
- a step of developing the first electrostatic latent image with toners which have been charged in the opposite polarity and are impermeable to ultraviolet rays to form a primary toner image;
- a step of uniformly charging the composite photosensitive body in the opposite polarity for which the composite photosensitive body exhibits a small dark decay;
- a step of exposing the composite photosensitive body to ultraviolet rays from the side of the primary toner image, to form a second electrostatic latent image of opposite polarity;
- a step of cleaning the primary toner image out of the composite photosensitive body;
- a step of developing the second electrostatic latent image of opposite polarity with toners charged in one polarity to form a secondary toner image;
- a step of transferring the secondary toner image onto a record sheet to form a duplicated copy; and
- a step of repeating successively said steps (h) and (i) to form a plurality of duplicated copies.

4,297,424

OVERCOATED PHOTORECEPTOR CONTAINING GOLD INJECTING LAYER


Harvey J. Hewitt, Williamson, N.Y., assignor to Xerox Corporation, Stamford, Conn.

Filed Mar. 5, 1980, Ser. No. 127,174


Int. Cl.³ G03G 5/085, 5/14

U.S. Cl. 430—58


1 Claim



wherein R is



and wherein X is independently selected from the group consisting of an alkyl group having from 1 to about 4 carbon atoms and chlorine in the ortho, meta or para position, said charge transport layer being substantially nonabsorbing in the spectral region at which the photoconductive material generates and injects photogenerated holes but being capable of supporting the injection of photogenerated holes from said photoconductive material and transporting said holes through said charge transport layer, the improvement consisting of the inclusion in said transport layer of a stabilizing compound within the scope of the following structural formula:



wherein R₁ and R₂ are independently selected from the group consisting of a C₁-C₈ alkyl, aryl, alkaryl and aralkyl, where said aryl is a phenyl group or a condensed ring group, where the alkyl group of said alkaryl and aralkyl is a C₁-C₄ group, R₃ is independently selected from the group consisting of hydrogen and CH₃; and R₄ is the same as R₁ and R₂ or a disubstituted aminophenyl group wherein the substituents are independently selected from the group consisting of a C₁-C₈ alkyl, aryl, alkaryl and aralkyl as defined supra, said stabilizing compound being present in an amount sufficient to at least minimize the deleterious effects of ultraviolet radiation.

4,297,425

IMAGING MEMBER

Damodar M. Pai, Fairport; John M. Pochan, and Darlyn F. Pochan, both of Ontario, all of N.Y., assignors to Xerox Corporation, Stamford, Conn.

Continuation-in-part of Ser. No. 78,264, Sep. 24, 1979, abandoned. This application Jun. 26, 1980, Ser. No. 163,256

Int. Cl.³ G03G 5/04, 5/14

U.S. Cl. 430—58

5 Claims

1. In an imaging member comprising a hole generation layer and a contiguous hole transport layer, said generation layer comprising a photoconductive material exhibiting the capability of photogeneration of holes and injection of said holes, said hole transport layer comprising a transparent electrically inactive polycarbonate resinous material having a residual amount within the range of from about 0.01 to about 1.0 percent by weight of said transport layer in said layer of a halogen-containing organic solvent therein, and dispersed in said layer from about 25 to about 75 percent by weight based on said transport layer composition of a charge transport compound within the scope of the following structural formula:

4,297,426

ELECTROPHOTOGRAPHIC ELEMENT WITH CARBAZOLE HYDRAZONE OR ANILE CHARGE TRANSPORT COMPOUNDS

Kiyoshi Sakai; Mitsuru Hashimoto, both of Numazu, and Tomiko Kawakami, Tokyo, all of Japan, assignors to Ricoh Co., Ltd., Tokyo, Japan

Filed May 21, 1980, Ser. No. 152,069

Claims priority, application Japan, May 28, 1979, 54-65741; May 28, 1979, 54-65742


Int. Cl.³ G03G 5/06, 5/14

U.S. Cl. 430—59


17 Claims

1. An electrophotographic element comprising: an electrically conductive substrate, a charge generation layer, a charge transport layer adjacent the charge generation layer, the

charge transport layer comprising at least one charge transport compound selected from the group consisting of hydrazone compounds having the following formula (I) and anile compounds having the following formula (II):



wherein R₁ is methyl, ethyl, 2-hydroxyethyl or 2-chloroethyl; R₂ is methyl, ethyl, benzyl or phenyl; and R₃ is chlorine, bromine, C₁-C₄ alkyl, C₁-C₄ alkoxy, dialkylamino in which the alkyl has 1 to 4 carbon atoms or nitro,



wherein R₁ has the same meaning as defined above, and R₄ is substituted phenyl, non-substituted phenyl, naphthyl, a heterocyclic group or C₁-C₁₀ alkyl; and a binder agent.

4,297,427

POLYBLEND COATED CARRIER MATERIALS

Meurig W. Williams, and Christopher J. Auclair, both of Rochester, N.Y., assignors to Xerox Corporation, Stamford, Conn.
Filed Jan. 26, 1978, Ser. No. 872,518
Int. Cl.³ G03G 9/10

U.S. Cl. 430—108

9 Claims

1. A carrier particle for electrostatic developer mixtures, said carrier particle comprising a core having an average diameter of from between about 30 microns and about 1,000 microns, said core having an outer coating comprising a polyblend of a first polymer possessing negative triboelectric charging characteristics with respect to toner particles and a second polymer possessing strong adhesive properties with respect to said core, said first polymer comprising a fluoropolymer selected from the group consisting of polymers of vinylidene fluoride, tetrafluoroethylene, and fluorinated acrylates and methacrylates, and said second polymer being selected from the group consisting of polycaprolactone, polysulfones, polycarbonates, polyesters, polyamides, and polymers of styrene, alkyl acrylates, alkyl methacrylates, organosilanes, and acrylonitriles.

8. An electrostatic developer mixture comprising finely-divided toner particles electrostatically clinging to the surface of carrier particles, each of said carrier particles comprising a core having an average diameter of from between about 30 microns and about 1,000 microns, said core having an outer coating comprising a polyblend of a first polymer which comprises a halogenated polymer possessing negative triboelectric charging characteristics with respect to said toner particles and a second polymer which comprises an acrylic polymer possessing strong adhesive properties with respect to said core, said first polymer comprising a fluoropolymer selected from the group consisting of polymers of vinylidene fluoride, tetrafluoroethylene, and fluorinated acrylates and methacrylates, and said second polymer being selected from the group consisting of polycaprolactone, polysulfones, polycarbonates, polyesters, polyamides, and polymers of styrene, alkyl acrylates, alkyl methacrylates, organosilanes, and acrylonitriles.

4,297,428
PROCESS FOR MAKING DIAZO PHOTSENSITIVE PAPER

Kaneo Yamamoto, 4-1, Hirata-Kita-machi, Ashiya-shi, Hyogo-ken, Japan


Filed Mar. 26, 1980, Ser. No. 134,139

Claims priority, application Japan, Nov. 5, 1979, 54-141997
Int. Cl.³ G03C 1/86, 1/60

U.S. Cl. 430—169

6 Claims

1. In a process for making an acid stabilized diazo photosensitive paper which comprises adding an ultraviolet absorber to an acid stabilized diazo photosensitive layer on a paper substrate, said layer consisting essentially of a diazonium salt and a coupler, the improvement wherein said ultraviolet absorber is a benzotriazole derivative represented by the general formula (I)



wherein R denotes



wherein each of A and B denotes H or an alkyl group having 1-5 carbon atoms and X denotes H or Cl, (a) mixing said ultraviolet absorber represented by the general formula (I) with a solvent selected from the group consisting of ethyl acetate, methyl acetate and methylethyl ketone, so as to prepare a 3-10% by weight solution of the ultraviolet absorber in the solvent, dispersing 10 parts of said solution in 15-20 parts of an aqueous solution containing 1-3% of sulfosuccinate and 0.1-1% of polyvinyl alcohol and evaporating the ethylacetate, methyl acetate or methylethyl ketone, therefrom, (b) mixing the thus-prepared solution with a photosensitive liquid consisting of diazonium compound and a coupler so that the amount of said ultraviolet absorber represented by said formula (I) contained therein is 15-50% of the amount of the coupler contained in the photosensitive liquid, and, (c) applying the photosensitive liquid containing the ultraviolet absorber to a paper substrate to prevent discoloration of the texture of a copy of said paper.

4,297,429

PHOTOGRAPHIC MATERIAL AND DIFFUSION TRANSFER PROCESSING SOLUTION FOR MAKING PRINTING PLATES AND METHOD FOR MAKING PRINTING PLATES

Eiji Kanada; Shoji Yamada, and Yasuo Tsubai, all of Nagaoka-kyo, Japan, assignors to Mitsubishi Paper Mills, Ltd., Tokyo, Japan

Filed Jun. 11, 1980, Ser. No. 158,580

Claims priority, application Japan, Jun. 18, 1979, 54-76581; Jun. 28, 1979, 54-81831; Jul. 2, 1979, 54-83834; Jul. 4, 1979, 54-85743

Int. Cl.³ G03C 5/54

U.S. Cl. 430—204

26 Claims

1. Method for making a lithographic printing plate which utilizes the transfer silver as ink receptive portions which is formed by silver complex diffusion transfer process from a lithographic printing plate material which comprises a support having thereon at least both silver halide emulsion layer and physical development nuclei layer by imagewise-exposure of

the silver halide emulsion layer and diffusion transfer development thereof with an alkaline processing solution, characterized in that diffusion transfer development processing is carried out in the presence of 2-mercaptobenzoic acid derivative.

4,297,430

PHOTOGRAPHIC MATERIAL FOR PRODUCTION OF PRINTING PLATES AND METHOD FOR PRODUCTION OF PRINTING PLATES

Eiji Kanada; Shoji Yamada, and Yasuo Tsubai, all of Nagaoka-kyo, Japan, assignors to Mitsubishi Paper Mills, Ltd., Tokyo, Japan


Continuation-in-part of Ser. No. 142,822, Apr. 22, 1980, abandoned. This application Aug. 1, 1980, Ser. No. 174,696

Claims priority, application Japan, May 2, 1979, 54/54363
Int. Cl.³ G03C 5/54

U.S. Cl. 430—204

11 Claims

1. A method for producing a lithographic printing plate which comprises developing a photographic material exposed to light comprising a support having thereon at least both silver halide emulsion layer and surface physical development nuclei layer and having a thickness of 0.5μ or less by silver complex diffusion transfer process and utilizing transfer silver as ink receptive portions of printing plate, characterized in that the development is carried out in the presence of a cyclic imide compound having the general formula:



(wherein Z represents atoms of a series of completing a 5- or 6-membered cyclic imide nucleus which comprises from 1 to 3 nitrogen atoms and the remainder being carbon atoms and said atoms of Z may have substituent).

4,297,431


DIFFUSION CONTROL LAYERS IN DIFFUSION TRANSFER PHOTOGRAPHIC PRODUCTS

Charles I. Sullivan, Melrose, Mass., assignor to Polaroid Corporation, Cambridge, Mass.

Continuation-in-part of Ser. No. 942,490, Sep. 15, 1978, abandoned, which is a continuation-in-part of Ser. No. 774,599, Mar. 4, 1977, abandoned, which is a continuation-in-part of Ser. No. 681,140, Apr. 28, 1976, abandoned, which is a continuation-in-part of Ser. No. 487,228, Jul. 10, 1974, abandoned. This application Mar. 14, 1980, Ser. No. 130,532

Int. Cl.³ G03C 1/40, 1/76, 5/54, 1/48
U.S. Cl. 430—215

78 Claims



1. A photographic diffusion transfer film unit comprising:
a. a photosensitive element comprising at least a photosensi-


tive silver halide emulsion layer having associated therewith a processing composition soluble and diffusible image-forming material;

b. an image-receiving element;

c. means for discharging an alkaline processing composition within said film unit; and

d. a diffusion control layer in at least one of said photosensitive element or said image-receiving element;

said diffusion control layer comprising a polymerization product of a monomer capable of undergoing β-elimination in an alkaline environment, said diffusion control layer being substantially impermeable to alkali or material soluble in or solubilized by said alkaline processing composition until said β-elimination, said polymerization product comprising recurring units of the formula



wherein

R is the addition polymerization product of an ethylenically unsaturated alkyl group of two or three carbon atoms;

A, D and E are selected from the group consisting of hydrogen, methyl and phenyl provided that no more than one of A, E, or D may be methyl or phenyl; and

Y is an activating group.

4,297,432

TWO-SHEET DIFFUSION TRANSFER ASSEMBLAGES AND PHOTOGRAPHIC ELEMENTS

Wayne A. Bowman; John F. Bishop, and John M. Noonan, all of Rochester, N.Y., assignors to Eastman Kodak Company, Rochester, N.Y.

Filed Aug. 1, 1980, Ser. No. 174,405

Int. Cl.³ G03C 5/54, 7/00, 1/40


U.S. Cl. 430—215

21 Claims


1. In a photographic element comprising a support having thereon, in order, a neutralizing layer, a timing layer and at least one photosensitive silver halide emulsion layer having associated therewith a dye image-providing material,

the improvement wherein a layer of a vinylidene chloride polymer is present between said timing layer and said emulsion layer, and a co-extensive polymeric primer layer is present between said vinylidene chloride polymer layer and said silver halide emulsion layer, said primer layer comprising:

(A) an ionic vinyl polymer comprising 10 to 30 weight percent of recurring units which conform to the structure:




and 70 to 90 weight percent of recurring units which conform to the structure:




wherein:

- each R is independently hydrogen or methyl;
each R¹ is independently a straight or branched chain alkylene group of 1 to about 6 carbon atoms;
R², R³ and R⁴ are each an alkyl group of 1 to about 4 carbon atoms;
each G is independently oxygen or NH; and
X⁻ is an acid anion; or
(B) a ionic polyester comprising recurring units of:
(I) a diol component which comprises:
(a) at least 50 mole percent of units derived from diols having the structures:




wherein n is an integer of from 1 to 4; and

- (ii) O---R⁶O---, wherein m is an integer of from 2 to 4, and R⁶ is an alkylene group of 2 to about 4 carbon atoms; and
(b) 0 to 50 mole percent of units derived from one or more diols having the structure:



wherein R⁷ is an alkylene group of up to about 16 carbon atoms, a cycloalkylene group of 6 to about 20 carbon atoms, a cycloalkylenebisalkylene group of 8 to about 20 carbon atoms, an arylenebisalkylene group of 8 to about 20 carbon atoms, or an arylenegroup of 6 to about 12 carbon atoms; and
(II) an acid component which comprises:

- (a) 8 to 30 mole percent of units derived from one or more ionic dicarboxylic acids, said units having the structures:



4,297,433 LIGHT SENSITIVE COMPOSITIONS OF POLYMETHYL ISOPROPENYL KETONE

Minoru Tsuda, Isehara, and Yoichi Nakamura, Samukawa, both of Japan, assignors to Tokyo Ohka Kogyo Kabushiki Kaisha, Kawasaki, Japan

Continuation of Ser. No. 957,836, Nov. 6, 1978. This application Nov. 16, 1978, Ser. No. 961,120

Claims priority, application Japan, Nov. 4, 1977, 52-132234 Int. Cl.³ G03C 1/68, 5/00

U.S. Cl. 430—270

1 Claim

1. An ultraviolet ray-sensitive composition comprising polymethyl isopropenyl ketone having a molecular weight of 10,000–1,000,000 and a dispersity index of below 3 and 4,4'-dibromobenzophenone, the amount of the benzophenone being 1–25 parts by weight per 100 parts by weight of the polymethyl isopropenyl ketone.

4,297,434 PHOTODEFORMABLE ARTICLE HAVING PHOTOIONIZABLE GROUPS ON A POLYMER BACKBONE

Ari Aviram, Yorktown Heights, N.Y., assignor to International Business Machines Corporation, Armonk, N.Y.


Division of Ser. No. 50,931, Jun. 21, 1979, Pat. No. 4,247,622. This application Jun. 13, 1980, Ser. No. 159,098

Int. Cl.³ G03C 1/68

U.S. Cl. 430—270


2 Claims

1. A photodeformable article comprising
(a) a substrate, and
(b) a film disposed on said substrate, said film being composed of a polymer backbone having at least one photoionizable group attached thereto, a halogenated hydrocarbon and a crosslinking agent, wherein said polymeric backbone is selected from the group consisting of polyacrylics, polyglutamate, polyvinyl amines, polyvinyl alcohols and polystyrenes, and wherein said photoionizable



wherein M is ammonium or a monovalent metal; and
(b) 70 to 92 mole percent of recurring units derived from other diacids.

group is selected from the group consisting of N,N-dimethyl-p-phenylenediamine, tetrathiafulvalene, tetraselenafulvalenes, ferrocene, tetrathiatetracene and leuco dyes.



raselenafulvalenes, ferrocene, tetrathiatetracene and leuco dyes.

4,297,435
CONTRAST COLORANT FOR
PHOTOPOLYMERIZABLE COMPOSITIONS
Jennings L. Jolly, Santa Clara, and Leo Roos, San Jose, both of Calif., assignors to Hercules Incorporated, Wilmington, Del. Continuation-in-part of Ser. No. 15,980, Feb. 26, 1979, abandoned. This application Aug. 18, 1980, Ser. No. 179,310 Int. Cl.³ G03C 1/52, 1/68

U.S. Cl. 430—270

11 Claims

1. A contrast colorant for photopolymerizable compositions comprising in combination a leuco triarylmethane dye in combination with a sufficient amount for formation of the colored form of said dye upon irradiation with actinic light of a bromine-substituted cyclohexane wherein said substituents comprise at least five bromine atoms and from 0 to 1 chlorine atoms.

5. A photopolymerizable composition comprising:
(1) an addition polymerizable photoinitiator;
(2) a polymeric binder;
(3) a polymerizable monomer capable of photopolymerization initiated by said photoinitiator; and
(4) a contrast colorant composition comprising in combination a leuco triarylmethane dye in combination with a sufficient amount for formation of the colored form of said dye upon irradiation with actinic light of a bromine-substituted cyclohexane, wherein said substituents are other than geminally substituted and comprise at least five bromine atoms and from 0 to 1 chlorine atoms.

4,297,436 METHOD FOR PRODUCING A MULTILAYER PRINTING PLATE

Kikuo Kubotera, Masamichi Sato, Akira Kashiwabara, and Kotaro Sato, all of Asaka, Japan, assignors to Fuji Photo Film Co., Ltd., Minami-ashigara, Japan

Continuation of Ser. No. 645,049, Dec. 29, 1975, abandoned.

This application Jun. 12, 1978, Ser. No. 914,704

Claims priority, application Japan, Dec. 26, 1974, 49/443

Int. Cl.³ G03F 7/02; G03C 5/00

U.S. Cl. 430—310

55 Claims

1. A method for producing a multi-layer printing plate consisting essentially of image-wise exposing and tanning developing a light-sensitive printing plate material which comprises a support with an oleophilic surface having thereon a hydrophilic metal layer having thereon at least one silver halide emulsion layer comprising a silver halide and a water-soluble binder, either directly or on at least one subbing layer on the hydrophilic metal layer to thereby form hardened silver image areas and unhardened non-silver image areas; removing the



image, removing said hydrophilic metal layer at the non-resist image areas by etching and then removing the resist image.

4,297,437 PROCESSING METHOD OF SILVER HALIDE COLOR PHOTOGRAPHIC MATERIAL

Yutaka Kaneko, Shigeto Hirabayashi, Satoshi Kawakatsu, and Hidetaka Ninomiya, all of Hino, Japan, assignors to Konishiroku Photo Industry Co., Ltd., Tokyo, Japan

Filed Nov. 24, 1980, Ser. No. 209,582

Claims priority, application Japan, Nov. 22, 1979, 54-151511 Int. Cl.³ G03C 7/00

U.S. Cl. 430—376

4 Claims

1. A method for processing an exposed color photographic material which comprises on a support

- (1) at least one of hydrophilic colloidal layer one of which layer containing a silver halide emulsion and a coupler, and
(2) a color developing agent or a precursor thereof in the hydrophilic layer, wherein the exposed color photographic material is developed in a color developer containing a color developing agent which color developer is replenished with a replenisher containing 0 to 0.016 mol/l of a color developing agent.

4,297,438 COLOR-PHOTOGRAPHIC DEVELOPMENT PROCESS

Helmut Hüseler, Leverkusen; Heinz Meckl, Bergisch-Gladbach; Karl Lohmer, Leverkusen, and Willibald Pelz, Cologne, all of Fed. Rep. of Germany, assignors to AGFA-Gevaert Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Filed Jul. 27, 1979, Ser. No. 61,472

Claims priority, application Fed. Rep. of Germany, Aug. 1, 1978, 2833655

Int. Cl.³ G03C 7/00


U.S. Cl. 430—377

2 Claims

1. In the process for the chromogenic development of an exposed color photographic material having at least three silver halide emulsion layers of differing spectral sensitivities and non-diffusible color couplers associated therewith, including a diphasic system comprised of a hydrophilic binder and hydrophobic oil former and at least one of said color couplers being hydrophobic and incorporated in the hydrophilic binder by means of the hydrophobic oil former, wherein the improvement comprises

- at least one cyan coupler is hydrophobic and has been incorporated in the hydrophilic binder by means of the hydrophobic oil former and
at least one yellow coupler is hydrophilic and has been incorporated in the hydrophilic binder without the aid of an oil former or is hydrophobic and has been incorporated in the hydrophilic binder by means of a second oil former

having increased hydrophilic character as compared to the hydrophobic oil former and the chromogenic development of the exposed material is carried out with a developer composition comprising a first hydrophobic developer compound which in its oxidized form is penetratable into said oil former in an amount to react preferentially with the hydrophobic cyan coupler, and a second hydrophilic developer compound which in its oxidized form is present mainly in the aqueous phase in an amount to react predominantly with the hydrophilic yellow coupler and in which the first and the second color developer compound, each corresponds to the following formula:



wherein

R¹ represents hydrogen or methyl,
R² represents alkyl and
R³ represents sulfoalkyl in the second developer compound when
R³ represents alkoxy alkyl in the first developer compound,
R³ represents hydroxy alkyl in second developer compound when
R³ represents methylsulfonylaminoalkyl in said first compound,

or

the second hydrophilic developer compound is selected from N-butyl-N-sulfobutyl-p-phenylenediamine and 2-amino-5-(N-isopropyl-N-sulfobutylamino)-toluene

and

the first developer compound is 2-amino-5-(N-ethyl-N-methylsulfonylamido-ethylamino)-toluene.

4,297,439

PRODUCTION OF PHOTOGRAPHIC SILVER HALIDE EMULSION

Peter Berghaller, Cologne; Wilhelm Saleck, Bergisch-Gladbach; Otto Lapp, Leverkusen, and Bruno Mücke, Bergisch-Gladbach, all of Fed. Rep. of Germany, assignors to AGFA-Gevaert AG, Leverkusen, Fed. Rep. of Germany

Filed May 29, 1979, Ser. No. 42,974


Claims priority, application Fed. Rep. of Germany, Jun. 2, 1978, 2824249

Int. Cl.³ G03C 1/02, 1/28

U.S. Cl. 430-434

8 Claims

1. A process for the production of photographic materials containing at least one silver halide emulsion layer, characterized in that the silver halide emulsion is produced in the presence of at least one thioether corresponding to the following formula:



in which

R¹ represents an aliphatic or a cycloaliphatic or an aryl or an aralkyl radical;
R², R³, R⁴, R⁵, R⁶ and R⁷ are the same or different and represent hydrogen or alkyl;

R⁸ represents hydrogen;
Ac represents an acyl radical;
n=an integer with a value of at least 1.

4,297,440 COLOR PHOTOGRAPHIC LIGHT-SENSITIVE ELEMENT

Kozo Aoki; Satoru Sawada; Yoshiharu Yabuki, and Nobuo Furutachi, all of Minami-ashigara, Japan, assignors to Fuji Photo Film Co., Ltd., Minami-ashigara, Japan


Filed Nov. 25, 1980, Ser. No. 210,184

Claims priority, application Japan, Nov. 26, 1979, 54-153359
Int. Cl.³ G03C 1/76, 1/40


U.S. Cl. 430-505

12 Claims


1. A color photographic light-sensitive element comprising a support having thereon a silver halide emulsion layer containing therein a 3-anilino-5-pyrazolone magenta color forming coupler represented by formula (I)



wherein the



is present at the 4- or 5-position of the anilino group; X represents a halogen atom or an alkoxy group; Ar represents an aryl group; R₁ represents hydrogen, a halogen atom, an alkyl group, an alkoxy group, or an alkylthio group; Y represents a non-metallic atomic group forming a 5-membered or 6-membered ring together with the



group, except that Y does not include a carbonyl group; and Z represents hydrogen or a coupling-off group.

12. A color photographic light-sensitive element as in claim 1, wherein said silver halide emulsion layer containing said magenta color-forming coupler represented by formula (I) is a green-sensitive silver halide emulsion layer, and said color photographic light-sensitive element additionally includes a red-sensitive silver halide emulsion layer containing a phenolic or naphtholic cyan color-forming coupler, and a blue-sensitive silver halide emulsion layer containing a benzoylacetyl or pivaloylacetyl yellow color-forming coupler.

4,297,441

PHOTOGRAPHIC MATERIAL

Yutaka Kaneko; Satoshi Kawakatsu; Shigeto Hirabayashi, and Hidetaka Ninomiya, all of Hino, Japan, assignors to Konishiroku Photo Industry Co., Ltd., Tokyo, Japan

Filed Jun. 26, 1980, Ser. No. 163,347

Claims priority, application Japan, Jun. 28, 1979, 54/82175


Int. Cl.³ G03C 1/06

U.S. Cl. 430-543

8 Claims

1. A photographic material having a silver halide emulsion layer coated on a support, which material contains an ion compound which is composed from a compound having a quaternary nitrogen atom as a cation and a boron compound as

an anion wherein the ion pair compound is represented by the following formula:



wherein R₁, R₂, R₃, R₄, R₉ and R₁₀ individually represent a hydrogen atom or hydroxyl, alkyl, alkenyl, cycloalkyl, aryl, phenyl, acyl, amino, carbamoyl, sulfonyl or heterocyclic groups, R₁ and R₂, or R₁, R₂, and R₃ may form a hetero nitrogen-containing ring by bonding to each other, R₅, R₆, R₇ and R₈ individually represent an alkyl, alkenyl, cycloalkyl, aryl, phenyl, heterocyclic or cyano group, an n is an integer from 1 to 5.

4,297,442

CELLULAR ELASTOMERIC FOAMS AND METHOD OF PRODUCTION USING AN EXPANDING AGENT CONTAINING A COMPONENT REACTIVE WITH THE POLYAMINE CHAIN-LENGTHENING AGENT

Johannes Blahak, Gauting-Buchendorf, Fed. Rep. of Germany, assignor to Metzeler Kautschuk GmbH, Munich, Fed. Rep. of Germany

Filed Jun. 27, 1980, Ser. No. 163,732

Claims priority, application Fed. Rep. of Germany, Jul. 13, 1979, 2928357

Int. Cl.³ C08G 18/14

U.S. Cl. 521-107

12 Claims

1. Cellular elastomeric foams produced by foaming a polyurethane or a polyurethane prepolymer and cross-linked with a polyamine-chain lengthening agent in the presence of an organic expanding agent containing at least in part a gas-forming component, which reacts with the polyamine chain-lengthening agent or with the products of reaction thereof with polyisocyanates.

4,297,443

METHOD FOR POLYURETHANE FOAM USING A TRI-TERTIARY AMINE CATALYST

Paul E. Eckler; William A. Summers, both of Terre Haute, Ind., and Ollie W. Chandler, Kildeer, Ill., assignors to International Minerals & Chemical Corporation, Terre Haute, Ind.

Continuation-in-part of Ser. No. 79,845, Sep. 8, 1979, abandoned. This application Aug. 28, 1980, Ser. No. 182,243

Int. Cl.³ C08G 18/14, 18/18; C07C 87/18, 87/20

U.S. Cl. 521-129

4 Claims

1. In the method of preparing a polyurethane foam by reacting a polyisocyanate with polyol in the presence of a blowing agent and a catalyst to promote the reaction, the improvement consisting of conducting the reaction in the presence of 2-heptamethyl-N,N,N',N',N'',N''-1,2,3-propanetriamine.

4,297,444

PROCESS FOR RIM ELASTOMERS WITH SUPERIOR HIGH TEMPERATURE DIMENSIONAL STABILITY

Richard J. G. Dominguez, and Doris M. Rice, both of Austin, Tex., assignors to Texaco Development Corp., White Plains, N.Y.

Filed Feb. 11, 1980, Ser. No. 120,238

Int. Cl.³ C08G 18/14, 18/76, 18/10, 18/82

U.S. Cl. 521-160

17 Claims

1. In a method for making a polyurethane elastomer wherein an aromatic polyisocyanate, a polyether polyol based on trihydric initiators of about 4000 molecular weight and above and a

chain extending agent comprising a low molecular weight active hydrogen containing compound of at least 2 functionality is injected via a RIM machine into a mold cavity of the desired configuration the improvement which comprises mixing at least 30% of said polyether polyol with the entire amount of polyisocyanate and allowing them to react, adding the remaining polyether polyol and low molecular weight active hydrogen containing compound to the polyol and polyisocyanate reacted mixture and injecting this entire mixture into the mold cavity where it is allowed to react.

4,297,445

CONTINUOUS PRODUCTION OF OLEFIN BLOCK COPOLYMERS

James N. Short, and Donald D. Norwood, both of Bartlesville, Okla., assignors to Phillips Petroleum Co., Bartlesville, Okla.

Filed Sep. 28, 1979, Ser. No. 79,745

Int. Cl.³ C08F 255/02, 255/04

U.S. Cl. 525-52

6 Claims

1. A method for the continuous production of block copolymer comprising:

- producing in a first zone a first reaction mixture comprising an ethylene homopolymer by reacting ethylene monomer in the presence of a catalyst system comprising TiCl₄, MgCl₂, and an organo metallic compound at a temperature in the range of about 90° to about 200° F. and a pressure above about 500 psig sufficient to maintain non-boiling liquid conditions in said first zone for a time in the range of about 5 to about 20 minutes;
- continuously introducing a portion of said first reaction mixture, propylene monomer, and a catalyst modifier to a second zone; and
- producing in said second zone block copolymer comprising blocks of propylene homopolymer and random ethylene-propylene copolymer by reaction in the presence of a catalyst system comprising TiCl₄, MgCl₂, and an organo metallic compound at a temperature in the range of about 100° to about 180° F. and a pressure above about 500 psig sufficient to maintain non-boiling liquid conditions in said second zone for a time in the range of about 30 to about 110 minutes to provide a total copolymer composition of about 10 to about 30 percent by weight of polymers of ethylene and about 70 to about 90 percent by weight of propylene homopolymer.

4,297,446

ABS-MOULDING COMPOSITIONS HAVING HIGH NOTCHED IMPACT STRENGTH

Christian Lindner, Cologne; Karl-Heinz Ott, Leverkusen; Bernhard Arnold, Pulheim; Friedrich Kowitz, Dormagen; Harald Oertel, Odenthal, and Dieter Kuhlmann, Pulheim, all of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Fed. Rep. of Germany

Filed Aug. 24, 1979, Ser. No. 69,597

Claims priority, application Fed. Rep. of Germany, Aug. 29, 1978, 2837597

Int. Cl.³ C08L 51/04, 51/00

U.S. Cl. 525-66

2 Claims

- A molding composition comprising
- a) 5 to 70% by weight of at least one graft product made by graft polymerizing styrene, a mixture of styrene and acrylonitrile, a mixture of styrene and methylmethacrylate, or a mixture of styrene, acrylonitrile and methylmethacrylate onto a polybutadiene, a butadiene/styrene, or a butadiene/acrylonitrile rubber,
- b) 95 to 30% by weight of a thermoplastic resin selected from the group consisting of polystyrene, polymerized styrene and methylmethacrylate and polymerized styrene, acrylonitrile and methylmethacrylate, and 0.05-2% by weight based on the total mixture of a silico urethane

derivative which is the reaction product of an organofunctional silicone with a polyisocyanate.

4,297,447

COMPOUND FOR COATING CONTAINING FLUOROCARBONPOLYMER AND METHOD FOR ITS MANUFACTURE

Toshio Yasuda, Naka, Japan, assignor to Elastoflon Inc., Woodmere, N.Y.

Continuation of Ser. No. 930,580, Aug. 3, 1978, abandoned, which is a continuation-in-part of Ser. No. 684,639, May 12, 1976, abandoned. This application May 28, 1980, Ser. No. 153,967

Int. Cl.³ C08L 63/00, 75/04, 61/04, 27/18

U.S. Cl. 525-133

24 Claims

1. An improved flexible coating for a flexible heat-degradable substrate having the following essential components present together simultaneously in a percent by weight ratio based on the total weight of said coating, said essential components are (A) fluorocarbon present in said coating in an amount between 20 percent and 80 percent by weight, and (B) a thermosetting resin present in said coating in an amount between 4 percent and 14 percent by weight, said thermosetting resin selected from the group consisting of an epoxy resin, an alkyl-phenol resin, and a polyurethane resin which is entirely thermosetting, and (C) a rubbery elastomer present in said coating in an amount between 76 percent and 6 percent by weight, said rubbery elastomer selected from the group consisting of a nitrile rubber, a chloroprene rubber, and a rubbery polyurethane elastomer which is entirely thermoplastic, all three essential components defined as said fluorocarbon, said thermosetting resin, and said rubbery elastomer being present simultaneously together for flexibility of said coating on said heat-degradable substrate.

4,297,448

COATING COMPOSITION OF AMINOPLAST, HYDROXY POLYMERS AND VINYLIC MONOMERS

Yun-Feng Chang, Plymouth; Henk V. Oene, Detroit, and Elaine C. Beckwith, Riverview, all of Mich., assignors to Ford Motor Company, Dearborn, Mich.

Filed Oct. 17, 1979, Ser. No. 85,570

Int. Cl.³ C08L 71/02, 29/00, 33/20, 51/06

U.S. Cl. 525-162

15 Claims

1. A thermosetting coating composition comprising organic solvent, binder composition, and aminoplast crosslinking agent, wherein said binder composition comprises:

(A) between about 30 and about 75 weight percent of one or more low viscosity resins, each of which (1) is substantially soluble in the solvent of the composition, (2) has a number average molecular weight of between about 500 and about 3500 and (3) is selected from the group consisting of hydroxy functional acrylic polymers, hydroxy functional polyethers and hydroxy functional polyesters and bears no additional functionality which would interfere with the crosslinking reaction between the hydroxy functionality of the resin and the crosslinking agent of the composition; and

(B) between about 70 and about 25 weight percent of one or more crosslinked dispersion polymers, each of which is substantially insoluble in the solvent of the composition, said dispersion polymers being formed by free radical polymerization of 0.5 to 3.5 weight percent of di-, tri-, or tetra vinyl monomers and 99.5 to 96.5 weight percent of at least one other copolymerizable monoethylenically unsaturated monomer, in the presence of a (i) hydrocarbon dispersing liquid which is a solvent for the polymerizable monomers, but a non-solvent for the resulting crosslinked polymer, and (ii) polymeric dispersion stabilizer which is solvated by said dispersing liquid and associated with said crosslinked polymer so as to maintain a separation between particles thereof, thereby inhibiting coagulation of said particles, wherein polymerization is carried out at

elevated temperature such that the dispersion polymer first forms and then is crosslinked.

4,297,449

PRODUCTION OF CROSSLINKED POLYMERS USING AN OXAZOLINE DERIVATIVE

Jugo Goto, Kawanishi, and Takeo Saegusa, Kyoto, both of Japan, assignors to Takeda Chemical Industries, Ltd., Osaka, Japan

Filed May 7, 1980, Ser. No. 147,543


Claims priority, application Japan, May 15, 1979, 54-60067

Int. Cl.³ C08F 8/00, 222/04, 222/06, 222/08


U.S. Cl. 525-329

11 Claims


1. A process for producing a polymer having a crosslinked structure, which comprises reacting a polymer having in its molecule a partial structure of the formula:



with an oxazoline derivative of the formula:



wherein R is a di-valent aromatic hydrocarbon radical, and R₁, R₂, R₃ and R₄, which may be the same or different, are hydrogen or alkyl having not more than 3 carbon atoms, the ratio of the number of the oxazoline rings in the oxazoline derivative relative to each one of the partial structures of the formula:



in the polymer being within the range of about 1.5 to 3.0.

4,297,450

HOT MELT TYPE TRAFFIC PAINT COMPOSITIONS

Hisatake Sato, Masaharu Makino, and Hideo Hayashi, all of Yokohama, Japan, assignors to Nippon Oil Co. Ltd., Japan

Filed Jun. 2, 1980, Ser. No. 155,209

Claims priority, application Japan, Jun. 8, 1979, 54-72060

Int. Cl.³ C08F 8/04

U.S. Cl. 525-333

13 Claims

1. A hot melt type traffic paint composition characterized by containing as a binder a partially ring-hydrogenated resin obtained by hydrogenating from 20 to 70% of the aromatic rings of an aromatic hydrocarbon resin having a softening point between 60° and 120° C. and a bromine value of not greater than 15 obtained by polymerization in the presence of a Friedel-Crafts catalyst of a fraction prepared so as to have a conjugated diolefin content of not more than 1.0 wt % and in a ratio of not more than 3.0% with respect to the total amount of polymerizable ingredients and a total content of indene and its alkyl derivatives of not more than 4.0 wt % and in a ratio of

not more than 12.0% with respect to the total amount of polymerizable ingredients, said fraction being obtained by distillation of cracked oil fractions which have boiling points in the range of 140° to 220° C. and which are prepared by cracking of petroleum.

4,297,451

DIENYL LITHIUM INITIATED POLYMERS

Carl A. Uraneck, John E. Burleigh, and Paul W. Solomon, all of Bartlesville, Okla., assignors to Phillips Petroleum Company, Bartlesville, Okla.

Filed Jul. 10, 1979, Ser. No. 55,868

Int. Cl.³ C08L 49/00

U.S. Cl. 525-366

57 Claims

1. A process which comprises the steps of
(A) polymerizing to substantially complete conversion at least one first polymerizable olefinically unsaturated monomer under anionic solution polymerization conditions employing a dienyllithium initiator, thereby resulting in a polymerization admixture containing polymer terminated at least in part with a conjugated dienyl functional group, wherein said dienyllithium initiator is a product prepared by contacting at least one hydrocarbon lithium compound R(Li)_x with at least one hydrocarbon 1,4-diolefin in a mixed solvent of saturated hydrocarbon/polar compound, under dienyllithium initiator forming temperature conditions, wherein R is a hydrocarbyl radical of valence x, and x is an integer of 1 to 4;

(B) treating said polymerization admixture containing polymer terminated at least in part with a conjugated dienyl functional group by a treating mode to produce a polymer selected from the group consisting of:

(a) a polymer produced by treating with an effective amount of at least one polyfunctional coupling agent of at least difunctionality, thereby preparing at least in part a coupled conjugated dienyl terminated polymer if increased molecular weight characterized by conjugated dienyl groups on the extending terminal ends of the coupled polymer;

(b) a polymer produced by treating with at least one unsaturated compound selected from the group consisting of alicyclic conjugated trienes and tetraenes, and linear conjugated dienes, thereby providing a polymer containing at least in part terminal conjugated unsaturation at both ends of the polymer chain;

(c) a polymer produced by treating with an active hydrogen-containing compound sufficient to terminate active lithium, and thereafter reinitiating polymerization with a hydrocarbon lithium initiator R(Li)_x with or without the further addition of a second polymerizable monomer the same or different from said first polymerizable monomer, thereby forming a branched polymer with broadened molecular weight;

(d) a polymer produced by maintaining said conjugated dienyl terminated polymer at substantially polymerization temperatures for a time sufficient to effect at least partial self-coupling, and thereafter adding a second polymerization monomer and polymerizing thereonto, thereby resulting in a branched polymer at least in part;

(e) a polymer produced by treating as defined by substep (a) above followed by reinitiating polymerization with a further addition of a hydrocarbon lithium initiator R(Li)_x with or without the further addition of a second polymerizable monomer the same or different from said first polymerizable monomer, thereby resulting at least in part in a branched polymer;

(C) wherein when any polymer resulting from any of said (a) through (e) inclusive retains active lithium, thereafter treating with an active hydrogen-containing compound effective to terminate said active lithium.

PROCESS FOR THE MANUFACTURE OF OXAZOLINE AND/OR OXAZINE-MODIFIED ADSORBENT POLYMER RESINS

Robert J. De Koch, Wausau, Wis.; Gerald C. Kolb, Bay City, and James W. Lalk, Shepherd, both of Mich., assignors to The Dow Chemical Company, Midland, Mich.


Filed Jan. 4, 1980, Ser. No. 109,729

Int. Cl.³ C08F 8/20, 8/24

U.S. Cl. 525-367

8 Claims

1. In a process for graft polymerizing (i) an oxazoline or oxazine monomer corresponding to the formula




wherein:

R₂ is hydrogen, phenyl or alkyl of from 1 to about 24 carbon atoms;

R₃-R₆ are each independently hydrogen, lower alkyl or hydroxy-substituted lower alkyl, with the proviso that at least two of R₃-R₆ are hydrogen;

m is 0 or 1;

with (ii) a cross-linked, vinyl-addition polymer the backbone of which contains a plurality of units corresponding to the formula



wherein:

R₁ is hydrogen or methyl,

Ar is a carbocyclic aromatic nucleus, and

Y is chloro or bromo;

in an inert liquid reaction medium which dissolves the oxazoline or oxazine reactant, the improvement comprising the sequential steps of:

(A) contacting at reactive conditions the vinyl-addition polymer with a source of iodide ions, so as to introduce sufficient iodo moieties into the polymer to catalyze reaction of the polymer with the oxazoline or oxazine moiety; and

(B) contacting at reactive conditions the iodized cross-linked, vinyl-addition polymer of step (A) with from about 8 to about 24 equivalents of the oxazoline or oxazine monomer for each equivalent of halomethyl moieties borne by the polymer, so as to react up to about 50 percent of the total oxazoline or oxazine monomer present.

4,297,453

COMPOSITIONS OF EPICHLOROHYDRIN RUBBER AND NYLON

Aubert Y. Coran, and Raman Patel, both of Akron, Ohio, assignors to Monsanto Company, St. Louis, Mich.

Filed May 12, 1980, Ser. No. 149,075

Int. Cl.³ C08L 71/02, 77/00

U.S. Cl. 525-408

22 Claims

1. A composition comprising a blend of about 20-55 parts by weight of nylon, and, correspondingly, about 80-45 parts by weight of cured epichlorohydrin rubber.

4,297,454

MANUFACTURE OF A BLOCK COPOLYMER CONTAINING A POLYETHERAMIDE AND A POLYLACTAM

Robert M. Thompson, Wilmington, Del., assignor to Suntech,
Inc., Philadelphia, Pa.


Filed Nov. 14, 1979, Ser. No. 133,370

Int. Cl.³ C08L 77/02


U.S. Cl. 525—432

9 Claims

1. Method for preparing a block copolyamide comprising polymerizing a lactam in contact with a polyetheramide to form polylactam in situ to form block copolyamide by reaction of said polylactam and said polyetheramide, wherein at least one of the lactam and polyetheramide are molten during said lactam polymerization and block copolymer formation, the lactam is present in the mixture of lactam and polyetheramide in an amount of about 5 wt. % to about 70 wt. % of said mixture, and the polyetheramide is selected from polymers of the structures:



AND



wherein R₁, R₂ and R₃ each are H, C₁-C₁₀ alkyl or C₃-C₁₀ isoalkyl, R₄ is C₁-C₁₀ alkylene or C₃-C₁₀ isoalkylene, and R₅ is C₀-C₁₀ alkylene, C₃-C₁₀ isoalkylene or C₆-C₂₀ arylene.

4,297,455

PROCESS FOR THE PREPARATION OF CARBONIC ACID ARYL ESTERS OF POLYESTER-DIOLS LENGTHENED VIA CARBONATE GROUPS AND THEIR USE FOR THE PREPARATION OF POLYESTER-DIOL BIS-DIPHENOL CARBONATES AND POLYESTER/POLYCARBONATES

Christian Lindner, Cologne; Carlhans Siling; Herbert Bartl, both of Odenthal; Manfred Schreckenberger; Dieter Freitag, both of Krefeld, and Klaus König, Leverkusen, all of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Continuation-in-part of Ser. No. 886,212, Mar. 13, 1978, Pat. No. 4,217,297. This application May 30, 1978, Ser. No. 910,986. Claims priority, application Fed. Rep. of Germany, Mar. 22, 1977, 2712435; Jun. 11, 1977, 2726417

Int. Cl.³ C08G 63/64, 63/76, 63/00

U.S. Cl. 525—439


42 Claims

1. A process for the preparation of a polyesterdiol bis-diphenol carbonate, lengthened via carbonate groups, comprising:


- (i) heating a polyester-diol having a molecular weight $\bar{M}_n$ (number-average) of over 250 with a carbonic acid bis-aryl ester
 - (a) at a temperature between about 100° C. and about 200° C.,
 - (b) in vacuo below about 35 mm Hg, and
 - (c) in the presence of a catalyst, characterized in that less than 1 mol of carbonic acid bis-aryl ester is employed per mol of OH-groups of the polyester diol, and
- (ii) heating the resulting polyester-diol bis-carbonic acid aryl ester, lengthened via carbonate groups, with a diphenol
 - (a) at a temperature between about 100° C. and about 200° C.,
 - (b) in vacuo below about 35 mm Hg, and
 - (c) in the presence of a catalyst, characterized in that more

than 1 mol of diphenol is employed per mol of carbonic acid aryl ester groups of the polyester-diol bis-carbonic acid aryl ester, lengthened via carbonate groups.

16. A polyester/polycarbonate the molecular chain of which is terminated by residues of chain stoppers comprising from about 30 to about 95% by weight of aromatic polycarbonate structural units of the formula




wherein
X denotes



O, S or SO₂ and

Y₁ to Y₄ are identical or different and denote hydrogen or halogen

and from about 70 to about 5% by weight of polyester-diolate block units, lengthened via carbonate groups, of the simplified formula



wherein

-(polyester)-represents the bivalent radical of a polyester-diol, and n denotes an integer from 2 to 20.

4,297,456

PROCESS FOR WORKING UP ISOCYANATE DISTILLATION RESIDUES

Artur Reischl, and Kuno Wagner, both of Leverkusen, Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Continuation-in-part of Ser. No. 88,800, Oct. 29, 1979, abandoned. This application Jul. 17, 1980, Ser. No. 169,589. Claims priority, application Fed. Rep. of Germany, Oct. 27, 1978, 2846815

Int. Cl.³ C08G 18/70

U.S. Cl. 525—452

13 Claims

1. A process for working up tolylene diisocyanate distillation residues into useable starting products for the production of plastics, wherein such distillation residue is a substantially monomer-free, crosslinked distillation residue which is insoluble in inert organic solvents and which cannot be melted without decomposing, of the type accumulating as slag in the removal of monomeric tolylene diisocyanates by distillation from the crude phosgenation product of tolylene diamines, comprising grinding said distillation residues to a mean particle size of less than 800 μ m.

4,297,457

CURABLE EPOXY RESIN COMPOSITION

Charles J. Stark, Jr., Clifton Park, N.Y., assignor to General Electric Company, Schenectady, N.Y.


Filed Jul. 11, 1980, Ser. No. 168,635

Int. Cl.³ C08G 59/68

U.S. Cl. 525—507

33 Claims

1. A composition of matter comprising an epoxy resin, a cure initiator, and an accelerator of the general formula



where R is independently selected from the class consisting of hydrogen, monovalent alkyl, aryl, alkaryl, aralkyl, vinyl and allyl radicals; A is independently selected from the class consisting of hydrogen, monovalent alkyl, alkoxy, halogen, cyano and amino radicals, and m is a whole number from 1 to 2, inclusive.

2. A composition of matter as in claim 1, wherein the cure initiator is a titanium or zirconium ester.

4,297,458

CURABLE EPOXY RESINS

Charles J. Stark, Jr., Clifton Park, N.Y., assignor to General Electric Company, Schenectady, N.Y.


Filed Jul. 14, 1980, Ser. No. 168,037

Int. Cl.³ C08G 59/68

U.S. Cl. 525—507

33 Claims

1. A composition of matter comprising an epoxy resin, a cure initiator, and an accelerator of the general formula



where Q is independently selected from the class consisting of Si—R₃ or hydrogen and, R is independently selected from the class consisting of hydrogen, monovalent alkyl (including aralkyl) groups of from 1 to 8 carbon atoms; aryl, alkaryl, vinyl, and allyl radicals; A is independently selected from alkyl radicals the same as R above, halogen and the nitro radical, where A can be ortho-, meta-, or para- to either of the —OQ radicals, and m is an integer from 1 to 2, inclusive, with the proviso, that only one Q can be hydrogen, and only one R can be hydrogen on one silicon atom.

2. A composition of matter as in claim 1, wherein the cure initiator is a titanium or zirconium ester.

4,297,459

CURABLE EPOXY RESINS

Charles J. Stark, Jr., Clifton Park, N.Y., assignor to General Electric Company, Schenectady, N.Y.


Filed Aug. 8, 1980, Ser. No. 176,467

Int. Cl.³ C08G 59/68

U.S. Cl. 525—507

25 Claims

1. A composition of matter comprising an epoxy resin, a cure initiator, and an accelerator of the general formula



where Q is independently selected from the class consisting of allyl radicals having from 3 to 15 carbon atoms, or hydrogen radicals and A is independently selected from the class consist-

ing of monovalent alkyl (including aralkyl) groups of from 1 to 8 carbon atoms, halogen and the nitro radical, where A can be ortho-, meta-, or para- to either of the —OQ radicals, and m is an integer from 0 to 2, inclusive, with the proviso that only one Q can be hydrogen.

2. A composition of matter as in claim 1, wherein the cure initiator is a titanium or zirconium ester.

4,297,460

TREATMENT OF SILICA

Max P. McDaniel, and Melvin B. Welch, both of Bartlesville, Okla., assignors to Phillips Petroleum Co., Bartlesville, Okla. Division of Ser. No. 44,809, Jun. 1, 1979, Pat. No. 4,248,735, which is a continuation-in-part of Ser. No. 857,552, Dec. 5, 1977, abandoned. This application Jul. 30, 1980, Ser. No. 173,525

Int. Cl.³ C08F 4/02, 4/24, 4/78

U.S. Cl. 526—98

23 Claims

1. A polymerization process comprising contacting at least one mono-1-olefin having 2 to 8 carbon atoms with a catalyst prepared by subjecting a silica-containing support at an elevated temperature to a treating ambient selected from (1) carbon monoxide, (2) a halogen-containing component selected from bromine, iodine, HBr, HI, organic bromides, and organic iodides, which halogen-containing component also either contains air or is followed by air or (3) a carbon, oxygen and sulfur-containing composition, thereafter incorporating a chromium compound under anhydrous conditions to thus form said catalyst and thereafter activating said catalyst in an oxygen ambient.

22. A method according to claim 1 wherein said support is preoxidized by being subjected to oxidation conditions after being subjected to said ambient and prior to incorporation of said chromium compound.

4,297,461

OLEFIN POLYMERIZATION CATALYST

Anthony N. Specia, Cincinnati, Ohio, assignor to National Petrochemicals Corp., New York, N.Y.

Division of Ser. No. 46,985, Jun. 8, 1979, Pat. No. 4,238,353, which is a continuation-in-part of Ser. No. 924,470, Jul. 14, 1978, abandoned. This application Apr. 17, 1980, Ser. No. 141,095


Int. Cl.³ C08F 4/78

U.S. Cl. 526—100

7 Claims

1. A process for polymerizing an olefin which comprises contacting the olefin with a catalyst system produced by a process which comprises:

- (a) depositing an organophosphoryl chromium reaction product of chromium trioxide and phosphorus compound having the formula



wherein R is alkyl, aralkyl, aryl, cycloalkyl, or hydrogen but at least one R is other than hydrogen, upon a solid inorganic support material;

- (b) depositing the non-volatile aluminum-containing product obtained from the reaction of an aluminum alkoxide and an aluminum carboxylic acid salt upon said support material; and,
- (c) heat-activating said supported organophosphoryl chromium reaction product and non-volatile aluminum-containing reaction product in a non-reducing atmosphere at a temperature above about 300° C. up to the decomposition temperature of the support material.

4,297,462

POLYMERIZATION OF MONOOLEFINS USING AN ALUMINUM-TITANIUM CATALYST SYSTEM

Margherita Corbellini, Milan; Alberto Greco, Dresano, and Mirko Osellame, Ombriano, all of Italy, assignors to Snamprogetti S.p.A. Milan and Anic S.p.A. Palermo, both of Italy Division of Ser. No. 915,998, Jun. 16, 1978, Pat. No. 4,203,866. This application Sep. 25, 1979, Ser. No. 78,899

Claims priority, application Italy, Jun. 30, 1977, 25232 A/77 Int. Cl.³ C08F 4/64

U.S. Cl. 526—125

14 Claims

1. A method for the polymerization or copolymerization of monoolefins which comprises contacting said monolefin with a catalyst system composed of an aluminum derivative of the formula AlR_pX_{3-p} in which R is a hydrocarbonaceous radical, X is a halogen radical and p is a number from 1 to 3; in combination with a composition based on a titanium halide in which said titanium has a valence of three or greater and a halide of a metal, said metal selected from zirconium, molybdenum, zinc or calcium, said composition prepared by reacting a titanium compound with the vapors of one or more of said metals in the presence of a halogen donor, and wherein the metal:titanium molar ratio is greater than 1:n, n being the valency of the metal with the greatest valency.

4,297,463

METHOD FOR POLYMERIZING α -OLEFIN

Haruo Ueno, Chiba; Takefumi Yano, Ichihara; Tokuji Inoue, Ichihara; Shigeru Ikai, Ichihara; Yoshiyuki Kai, Ichihara, and Michimasa Shimizu, Ichihara, all of Japan, assignors to Ube Industries, Ltd., Chiba, Japan

Filed May 6, 1980, Ser. No. 147,279

Claims priority, application Japan, Sep. 21, 1979, 54-120726 Int. Cl.³ C08F 4/02, 10/06

U.S. Cl. 526—128

25 Claims

1. A method for polymerizing an α -olefin which comprises bringing, in the presence of an organic acid ester, a feed containing at least one α -olefin having 3 or more carbon atoms into contact with a catalyst comprising (A) a solid catalytic ingredient prepared by (a) reacting an aluminium halide with a tetraalkoxysilane to form a first reaction product, (b) reacting a Grignard compound with said first reaction product to form a second solid reaction product, (c) contacting said second solid reaction product with a titanium tetrahalide, (d) treating the resultant titanium-containing solid product with an organic acid ester and, finally, (e) contacting the treated solid product with a titanium tetrahalide; and (B) another catalytic ingredient consisting of at least one trialkyl aluminium.

4,297,464

ORTHOESTERS AS COUPLING AGENTS FOR PRODUCING MONOVINYLAENE HOMOPOLYMERS

William J. Trepka, Bartlesville, Okla., assignor to Phillips Petroleum Co., Bartlesville, Okla.

Division of Ser. No. 5,625, Jan. 22, 1979, Pat. No. 4,238,576.


This application Aug. 15, 1980, Ser. No. 178,402

Int. Cl.³ C08F 4/46, 8/06, 8/14

U.S. Cl. 526—181

4 Claims

1. A method of producing coupled monovinylarene homopolymers, said method comprising:
(a) forming a polymerization mixture comprising (1) at least one monomer selected from the group consisting of monovinylarenes and (2) an organo alkali metal initiator;
(b) polymerizing said at least one monomer so as to form living homopolymer molecules;
(c) coupling said living homopolymer molecules with an orthoester, said orthoester having the formula



wherein R, R', and R'' are the same or different and are individually selected from alkyl groups.

4,297,465

CATALYSTS FOR POLYMERIZING PROPYLENE IN A HIGH TEMPERATURE SOLUTION PROCESS

Thomas W. Smith, Longview, Tex., assignor to Eastman Kodak Company, Rochester, N.Y.

Filed Oct. 29, 1980, Ser. No. 201,955

Int. Cl.³ C08F 2/06, 10/06

U.S. Cl. 526—141

15 Claims

1. The process for polymerizing an α -mono-olefin containing at least 3 carbon atoms to solid, high molecular weight polymer having a crystallinity of at least 72% which comprises contacting said α -mono-olefins, at a temperature in the range of about 120° to about 300° C. and a pressure in the range of about atmospheric to about 2,000 atmospheres, with a catalyst mixture comprising (1) an aluminum trialkyl, (2) a halide of a transition metal selected from the group consisting of titanium and vanadium, the valence of the metal in said halide being at least one less than maximum and (3) a 2-amino alkyl carboxylate wherein the molar ratio of catalyst components is 0.5–10/1/0.05–1.

4,297,466

NOVEL ACRYLIC POLYMERS AND METHOD OF MAKING SAME

Bertrand Bloch, Paris; Chantal Cavalli born Meyer, Voisins le Bretonneux, and Denis Charrier, Antony, all of France, assignors to Office National d'Etudes et de Recherches Aerospatiales, Chatillon sous Bagneux, France


Filed Dec. 11, 1979, Ser. No. 102,427

Claims priority, application France, Dec. 15, 1978, 78 35459 Int. Cl.³ C08F 6/00, 14/18

U.S. Cl. 526—218

15 Claims

1. An acrylic polymer comprising recurring units of the formula:



4,297,467

POLYMERIZATION PRODUCTS OF POLYIMIDE DERIVATIVES HAVING UNSATURATED TERMINAL AMIDE GROUPS

Phillip A. Waitkus, Sheboygan, Wis., and Gaetano F. D'Alelio, deceased, late of South Bend, Ind. (by St. Joseph Bank and Trust Company, executor), assignors to Plastics Engineering Company, Sheboygan, Wis.


Filed Jan. 25, 1980, Ser. No. 115,483

Int. Cl.³ C08F 26/06

U.S. Cl. 526—259

21 Claims

1. A cured polymerization product of the unsaturated amide of the formula:



wherein:

Ar' is a tetravalent aromatic organic radical, the four carbonyl groups being attached directly to separate carbon atoms and each pair of carbonyl groups being attached to adjacent carbon atoms in the Ar' radical except that in the case of the Ar' being a naphthalene radical one or both pairs of the carbonyl groups may be attached to peri carbon atoms;

Ar is a divalent aromatic organic radical;

n is zero or an integer of at least one;

Y is —NRR';

R is an organic moiety containing 1 to 18 carbon atoms;

R' is an organic moiety containing 2 to 14 carbon atoms and having a terminal $\text{CH}_2=\text{CH}-$ structure;

Y' is —NRR, —OR, —OH or —X;

X is a halogen.

4,297,468

ALLYL AMIDO PHOSPHOROUS COPOLYMERS

Miroslav Chmelir, Krefeld, and Kurt Dahmen, Monchengladbach, both of Fed. Rep. of Germany, assignors to Chemische Fabrik Stockhausen & Cie, Krefeld, Fed. Rep. of Germany

Filed May 16, 1979, Ser. No. 39,614

Claims priority, application Fed. Rep. of Germany, May 23, 1978, 2822423


Int. Cl.³ C08F 230/02

U.S. Cl. 526—276

9 Claims

1. A cross-linked copolymer consisting of polymerized units of

- (A) at least one olefinically unsaturated carboxylic acid,
(B) at least one mono-olefinically unsaturated monomer in up to four times the weight of (A), and
(C) 0.1 to 4% by weight of (A) plus (B) of at least one allyl monomer of the formula



in which

n=0, 1 or 2,

m=1, 2 or 3,

n+m=3,

R₁=hydrogen, or an alkyl, alkoxyalkyl, haloalkyl, cycloalkyl, aryl, alkaryl, or alkenyl radical, andR₂ and R₃ each independently is hydrogen or an allyl, alkyl, cycloalkyl, aryl, aralkyl or alkaryl radical,

at least two of the radicals R₁, R₂ and R₃ being an allyl radical or a substituted allyl radical.

4,297,469

BIPOLYMER OF VINYL SULFONIC ACID-GLYCIDOL ADDUCT AND ACRYLAMIDE

Walter D. Hunter, Houston, Tex., assignor to Texaco Development Corp., White Plains, N.Y.

Division of Ser. No. 916,984, Jun. 19, 1978, Pat. No. 4,228,017.

This application Apr. 4, 1980, Ser. No. 137,183

Int. Cl.³ C08F 228/02

U.S. Cl. 526—287

3 Claims

1. A water-soluble copolymer consisting of repeating units of (a) vinyl sulfonic acid alkoxyated with 2,3-epoxy-1-

propanol, and (b) acrylamide having a number average molecular weight of about 10,000 to about 2,000,000.

4,297,470

IMAGE FORMING PROCESS

Chiaki Osada; Masato Satomura, and Hisatake Ono, all of Asaka, Japan, assignors to Fuji Photo Film Co., Ltd., Kanagawa, Japan

Continuation of Ser. No. 212,530, Dec. 27, 1971, abandoned.

This application Feb. 4, 1974, Ser. No. 439,685


Claims priority, application Japan, Dec. 26, 1970, 45/118984

Int. Cl.³ C08F 20/26, 20/58


U.S. Cl. 526—304

4 Claims

1. A process for producing photosensitive homopolymers containing the recurring unit:



wherein A is:




wherein R₈ is a hydrogen atom or an alkyl group having 1 to about 6 carbon atoms, n is the integer of 1, m is an integer or from 1 to 6;

R₂ is:R₃ and R₄ are each hydrogen;

R₅ is a hydrogen atom or an alkyl group having from 1 to about 6 carbon atoms;

R₆ is a hydrogen atom: X is —O— or —NH—

R₇ is hydrogen, which process comprises preparing a mixture containing a monomer represented by the general formula:



wherein A, X, R₂, R₃, R₄, R₅, R₆ and R₇ are as defined above, and a polymerization initiator under an inert atmosphere; and holding said mixture under an inert atmosphere for time sufficient for the polymer to form.

4,297,471

**ODORLESS OR LOW-ODOR CROSSLINKABLE
COMPOUND AND RESIN COMPOSITION CONTAINING
THE SAME**

Tohru Koyama, Hitachi; Toshikazu Narahara, Tokaimura, and
Yuji Aimon, Hitachi, all of Japan, assignors to Hitachi
Chemical Company, Ltd., Tokyo, Japan

Filed Apr. 10, 1980, Ser. No. 139,025

Claims priority, application Japan, Apr. 13, 1979, 54-45596;
Apr. 17, 1979, 54-47677

Int. Cl.³ C08G 10/04; C07C 69/54

U.S. Cl. 526—328

10 Claims

1. A crosslinkable compound obtained by reacting an aromatic hydrocarbon-formaldehyde resin with an α,β -unsaturated monocarboxylic acid or an ester thereof in the presence of an esterification or ester interchange catalyst.

4,297,472

**METHOD OF PRODUCING COLOR STABLE
THERMOPLASTIC POLYMETHANES AND PRODUCTS
MADE THEREBY**

Herbert L. Heiss, New Martinsville, W. Va., assignor to Mobay
Chemical Corporation, Pittsburgh, Pa.

Filed Aug. 26, 1977, Ser. No. 828,121

Int. Cl.³ C08G 18/32, 18/42

U.S. Cl. 528—84

6 Claims

1. A method of improving the color stability of thermoplastic polyurethanes prepared from a reaction mixture comprising
- (a) an aromatic polyisocyanate,
 - (b) a polyester polyol, and
 - (c) an active hydrogen containing chain extender, said method comprising
- (A) adding to said reaction mixture
 - (d) from 0.05 to 2 percent by weight based on the total weight of said reaction mixture of a hydroxyl group containing additive, said additive characterized as
- (i) having a molecular weight of 400 or less, and
 - (ii) containing 2 to 4 aliphatic hydroxyl groups with at least 2 of said hydroxyl groups being vicinal and with the vicinal hydroxyl groups being primary and/or secondary, said additive (d) not being present in component (b) or (c), and
- (B) reacting said components (a), (b), (c) and (d).

4,297,473

**QUICK-CURING PHENOLIC RESIN AND PROCESS FOR
PREPARING SAME**

Shigeru Koshibe, Toride, and Motoyuki Nanjo, Yokohama, both
of Japan, assignors to Sumitomo Bakelite Company Limited,
Tokyo, Japan

Filed May 9, 1980, Ser. No. 148,104

Claims priority, application Japan, May 21, 1979, 54-61478

Int. Cl.³ C08G 8/10

U.S. Cl. 528—144

5 Claims

1. A process for producing a quick-curing phenolic resin having an ortho linkage to para linkage ratio ranging from 0.85 to 2.5 and a number-average molecular weight of the resin exclusive of free phenol of 500 to 1,200, which comprises reacting phenol (P) with formaldehyde (F) in a F/P molar ratio ranging from 0.6 to 1.0 using only as a catalyst at least one acid selected from the group consisting of formic acid, oxalic acid, malonic acid, and succinic acid, said reaction being effected at a temperature of 105°–130° in at least the first stage for 3–5 hours.

4,297,474

**POLYETHERIMIDES PREPARED BY
SELF-CONDENSATION OF HYDROXYARYL
PHTHALIMIDE SALTS**

Frank J. Williams, III, Scotia, and Howard M. Relles, Rexford,
both of N.Y., assignors to General Electric Company, Schenectady, N.Y.


Filed Feb. 29, 1980, Ser. No. 125,796

Int. Cl.³ C08G 73/10

U.S. Cl. 528—170

7 Claims

1. Polyetherimides comprising chemically combined units of the formula,



where R is a trivalent $C_{(6-13)}$ aromatic organic radical, R¹ is a divalent $C_{(6-30)}$ aromatic organic radical and X is selected from —O—, or —S—.

4,297,475

**FLAME RETARDANT INTUMESCENT POLYAMIDE
FROM HALOAMIDE**


Linnea E. Nelson, and Charles E. Reineke, both of Midland,
Mich., assignors to The Dow Chemical Co., Midland, Mich.
Division of Ser. No. 870,312, Jan. 18, 1978. This application
Apr. 24, 1978, Ser. No. 899,185

Int. Cl.³ C08G 69/00, 69/22

U.S. Cl. 528—271

10 Claims

1. A solid polyamide composition consisting essentially of repeating structural units of the formulas



wherein

X is independently chloro or bromo, and n and n' are each independently a positive integer.

4,297,476

ESTER DIOL ALKOXYLATE BASED ALKYD RESINS
Joseph V. Koleske, Charleston, W. Va., assignor to Union Carbide Corporation, New York, N.Y.


Filed May 27, 1980, Ser. No. 153,457

Int. Cl.³ C08G 63/66

U.S. Cl. 528—300

21 Claims

1. An alkyd resin comprising the reaction product of (A) an ester diol alkoxyate of the formula



wherein m is an integer having a value of from 2 to 4, n is an integer having a value of from 1 to 5, x and y are integers each having a value of from 1 to 20, and R is an unsubstituted or substituted alkyl group having from 1 to 8 carbon atoms with (B) a polyol and (C) a polycarboxylic acid or anhydride thereof.

4,297,477

**POLYAMIDE HAVING
—NH—(CH₂)₄—CH(NRR')—CO—UNITS**

Minoru Nakata, Suzuka; Haruyo Sato, and Shinzo Imamura,
both of Nagoya, all of Japan, assignors to Toray Industries,
Incorporated, Tokyo, Japan

Filed Dec. 31, 1979, Ser. No. 108,941


Claims priority, application Japan, Jan. 5, 1979, 54-856; Jan. 5, 1979, 54-857; Jan. 5, 1979, 54-858

Int. Cl.³ C08G 69/14

U.S. Cl. 528—323

7 Claims

1. A basic polyamide having a repeating unit represented by the formula:



wherein R and R' each is a lower alkyl group having 1 to 4 carbon atoms, and having a relative viscosity of at least 1.5 measured at 25° C. in a solution of said basic polyamide at a concentration of 1 gr/100 ml. in a 98% sulfuric acid solvent.

4,297,478

**PROCESS FOR THE DISCONTINUOUS PRODUCTION
OF AROMATIC IN MIXTURE OF POLYAMIDES
CALCIUM CHLORIDE AND
N-METHYLPYRROLIDONE-2**

Vincent Rochina, L'Arbresle, and Jean Sacco, Lyons, both of
France, assignors to Rhone-Poulenc-Textile, Paris, France
Filed Apr. 18, 1978, Ser. No. 897,499


Claims priority, application France, Apr. 27, 1977, 77 13620

Int. Cl.³ C08G 69/28


U.S. Cl. 528—336

6 Claims

1. A process for the discontinuous production of a spinnable polyamide consisting of repeating units of the generic formula:



in which 50 to 100% of the radicals R are p-phenylene radicals and the remaining 0 to 50% of the radicals R consist essentially of n-butylene radicals, which polyamide has a fiber-forming viscosity, measured at 25° C. on a solution in 100% strength sulphuric acid which has a concentration of 0.5 g of polymer in 100 ml of solvent, characterized in that terephthaloyl chloride, or terephthaloyl chloride and adipoyl chloride, is reacted with a solution selected from the group consisting of para-phenylenediamine, 4,4'-diaminodiphenylamine, and a mixture of the same, in a mixture of N-methylpyrrolidone-2 and calcium chloride, under conditions such that: the acid chloride or chlorides and the diamine or diamines are in essentially stoichiometric proportions; the solution of diamine or diamines in the mixture of N-methylpyrrolidone-2 and CaCl₂ is homogeneous and substantially anhydrous; with the CaCl₂ initially being in and remaining in solution at the time of its use; the calcium chloride content is such that the ratio C_m of the number of mols of calcium chloride to the number of units:



is between 0.70 and 2.90; and the relative amounts of reactants and solvents are chosen such that, at the end of the reaction, the polymer content of the resulting polymer-containing com-

position obtained is between 5 and 16% by weight, relative to the N-methylpyrrolidone-2.

4,297,479

**PROCESS FOR THE CONTINUOUS PRODUCTION OF
AROMATIC POLYAMIDES IN A MIXTURE OF
CALCIUM CHLORIDE AND
N-METHYLPYRROLIDONE-2**

Vincent Rochina, L'Arbresle, and Jean Sacco, Lyons, both of
France, assignors to Rhone-Poulenc-Textile, Paris, France
Filed Apr. 18, 1978, Ser. No. 897,500


Claims priority, application France, Apr. 27, 1977, 77 13619;
Feb. 20, 1978, 78 05000

Int. Cl.³ C08G 69/28


U.S. Cl. 528—336

8 Claims

1. A process for the continuous production of a spinnable polyamide-containing composition consisting of repeating units of the generic formula:



in which 50 to 100% of the radicals R are p-phenylene radicals and the remaining 0 to 50% of the radicals R consist essentially of n-butylene radicals, which polyamide has a fiber-forming viscosity, measured at 25° C. on a solution in 100% strength sulphuric acid which has a concentration of 0.5 g of polymer in 100 ml of solvent, characterized in that (a) molten terephthaloyl chloride, or (b) molten terephthaloyl chloride in admixture with adipoyl chloride, is reacted continuously with a solution of (c) para-phenylenediamine, or (d) 4,4'-diaminodiphenylamine, or (e) a mixture of (c) and (d), or (f) a mixture of (c) and (g) a prepolymer formed from at least one chloride and at least one diamine from amongst those mentioned above, or (d) in admixture with (g), or (e) in admixture with (g), in a mixture of N-methylpyrrolidone-2 and calcium chloride, under conditions such that: the acid chloride or chlorides and the diamine or diamines are in essentially stoichiometric proportions; the solution of diamine or diamines, and when present the prepolymer, in the mixture of N-methylpyrrolidone-2 and calcium chloride, is homogeneous and substantially anhydrous; with the CaCl₂ being in and remaining in solution at the time of its use; the molar ratio of calcium chloride to the number of units:



is at least 1; and the relative amounts of reactants and solvents are chosen such that, at the end of the reaction, the resulting polymer-containing composition contains at least 5% by weight of polyamide, relative to the N-methylpyrrolidone-2.

4,297,480

**TRANSPARENT POLYAMIDE FROM BRANCHED
CHAIN C₁₁ DIAMINE**

Josef Pfeifer, Therwil, Switzerland, and Dieter Reinehr, Kandern, Fed. Rep. of Germany, assignors to Giba-Geigy Corporation, Ardsley, N.Y.

Filed Oct. 9, 1979, Ser. No. 83,142

Claims priority, application Switzerland, Oct. 18, 1978, 10771/78


Int. Cl.³ C08G 69/26

U.S. Cl. 528—346

5 Claims

1. A transparent polyamide having a reduced specific viscosity of at least 0.5 dl/g, measured on a 0.5% solution in m-cresol

at 25° C., which polyamide consists of recurring structural elements of formula 1a



wherein R₁' and R₂' are each methyl or ethyl, or together are alkylene having 4-7 C atoms, R₃' is methyl or ethyl, and R₄' is alkyl having 1-4 C atoms, or R₃' and R₄' together are alkylene having 4-7 C atoms.

4,297,481 PROCESS OF FORMING POLYMERIC POLYAMINE/AMIDE

Felek Jachimowicz, Columbia, Md., assignor to W. R. Grace & Co., New York, N.Y.

Filed Feb. 22, 1980, Ser. No. 123,739
Int. Cl.³ C08G 67/02

U.S. Cl. 528—392

8 Claims

1. A process for forming polymeric polyamine/amide wherein said amino/amido nitrogens are positioned in the polymer backbone comprising contacting, in a reaction zone containing an inert solvent, and, as reactants, a hydrocarbon compound containing at least two olefinic groups therein, water, carbon monoxide and a nitrogen containing compound having at least 2 labile hydrogens, at a temperature of from about 50° to 250° C. and at a pressure of from about 30 to about 300 atmospheres in the presence of a catalyst consisting essentially of a rhodium atom containing compound selected from metallic rhodium, rhodium salts, rhodium carbonyls, rhodium oxides or ligands thereof.

4,297,482 CHAIN-EXTENDED POLYOL COMPOSITIONS AND METHOD


Louis L. Wood, Rockville, and Donald W. Larsen, Marriotsville, both of Md., assignors to W. R. Grace & Co., New York, N.Y.

Division of Ser. No. 103,248, Dec. 13, 1979, which is a continuation-in-part of Ser. No. 23,912, Mar. 26, 1979, abandoned. This application Sep. 24, 1980, Ser. No. 190,114
Int. Cl.³ C08G 59/00


U.S. Cl. 528—405

4 Claims


1. A polyol composition containing at least three OH groups of the general formula:



wherein A is



B is selected from the group consisting of



at least one of R₁ and R₂ is H and the other is independently selected from the group consisting of H, CH₃ and phenyl; R₃ is

H, CH₃, CH₂CH₃ or —OCH₂—n is 0 or 2; x is 1-3; z is 1-10 and a and b are independently selected from 1 to 1000.


4,297,483 PROCESS FOR REDUCING THE VINYL CHLORIDE CONTENT OF AQUEOUS DISPERSIONS OF VINYL CHLORIDE POLYMERS

Glor T. Mejdell; Odd E. Palmgren; Arne Talmoen, and Bjarne Vik, all of Porsgrunn, Norway, assignors to Norsk Hydro a.s., Norway

Continuation-in-part of Ser. No. 891,116, Mar. 28, 1978, abandoned. This application Dec. 19, 1979, Ser. No. 105,740
Int. Cl.³ C08F 6/00, 14/06

U.S. Cl. 528—500

2 Claims



1. In a process for the reduction of the vinyl chloride content of aqueous dispersions of vinyl chloride polymers and copolymers after completion of polymerization and after pressure release and preceding removal of thereby released vinyl chloride, by counter-current stripping with steam in a perforated plate column, the plates of which are equipped with downcomers, the improvement wherein the amount of steam introduced at the bottom of the column is adjusted in such relation to the hole area of an individual plate that the pressure drop across one plate gives a steam space between two adjacent perforated plates of not more than 50 mm in height such that the steam space is established just underneath the upper perforated plate and whereby the liquid layer is maintained above the lower perforated plate, and the liquid by bubbling steam there-through, flushes the wall surfaces of the column in the steam space and said perforated plates to become clear of polymer particles, and further that the amount of dispersion fed to the top of the column and the amount of outgoing, stripped dispersion and adjusted in such relation to each other, that at any time, the liquid layer is maintained substantially above the downcomer of the uppermost perforated plate, and that above the liquid level and the level at which the dispersion is fed, a liquid is introduced which continuously or discontinuously flushes the wall of the column.

4,297,484 QUATERNIZED DERIVATIVES OF POLYMERIZED PYRIDINES AND QUINOLINES

Patrick M. Quinlan, Webster Groves, Mo., assignor to Petrolite Corporation, St. Louis, Mo.


Filed Apr. 23, 1979, Ser. No. 32,044

Int. Cl.³ C08G 73/06; C07D 213/04, 215/04, 221/06
U.S. Cl. 528—423

4 Claims

1. A quaternized derivative of polymerized pyridine or

quinoline compounds, which compounds prior to polymerization are selected from the group consisting of pyridine, 2-methyl pyridine, 4-methyl pyridine, 4-phenyl pyridine, 4-ethyl pyridine, 2-hydroxypyridine, 2,4-lutidine, quinoline, 2-methyl quinoline and 4-methyl quinoline, the nitrogen atoms of which are quaternized by treating said polymerized compounds with a quaternizing agent selected from the group consisting of methyl iodide, ethyl iodide, propyl iodide, ethyl bromide, benzyl bromide, butyl bromide, dodecyl bromide, benzyl chloride, dodecyl benzyl chloride, ethyl bromoacetate, dimethyl sulfate, tetradecyl bromide and octyl bromide at a temperature of at least about 100° C.



and the non-toxic acid addition salts thereof.

4,297,487 PHOSPHONIUM SALTS


Richard A. Mueller, Glencoe, Ill., assignor to G. D. Searle & Co., Skokie, Ill.

Filed Aug. 6, 1980, Ser. No. 175,791
Int. Cl.³ C07F 9/54

U.S. Cl. 542—412

16 Claims

1. A phosphonium salt represented by the formula:



wherein: R is selected from the group consisting of phenyl, substituted phenyl, benzyl and substituted benzyl; R₁ is hydrogen or lower alkyl; R₂ is hydrogen or loweralkyl; or R₁ and R₂ taken together form a 5 or 6 membered saturated or unsaturated carbocyclic ring with the limitation that R₁ is on the carbon atom adjacent the carbon atom bearing R₂, m is 1, 2 or 3; n is 0 or 1; o is 0 or 1; p is 0 or 1; R₃, R₄ and R₅ are the same or different members of the group consisting of hydrogen, lower alkyl, lower alkoxy and halo; R₆ is hydrogen or C₁-C₃ straight or branched chain alkyl; and X is a pharmaceutically acceptable anion.

4,297,488 7-α-METHOXY CEPHALOSPORINS

Burton G. Christensen, Scotch Plains; Lovji D. Cama, Edison; Sandor Karady, Elizabeth, and Meyer Sletzing, North Plainfield, all of N.J., assignors to Merck & Co., Inc., Rahway, N.J.

Filed Jun. 2, 1971, Ser. No. 149,364

Claims priority, application United Kingdom, Jun. 16, 1970, 29158/70; Jul. 9, 1970, 33415/70; Sep. 30, 1970, 46556/70; Dec. 10, 1970, 58731/70; Jan. 27, 1971, 3296/71; Jan. 27, 1971, 3297/71; Jan. 27, 1971, 3298/71; Feb. 8, 1971, 4179/71; Feb. 11, 1971, 4479/71; Feb. 11, 1971, 4480/71; Feb. 26, 1971, 5588/71; Apr. 30, 1981, 29158/81

Int. Cl.³ C07D 501/57; A61K 31/545

U.S. Cl. 544—21

11 Claims

1. The compound 3-A-7-methoxy-7-acylamido-3-cephem-4-carboxylic acid wherein A is methyl, hydroxymethyl, chloromethyl, bromomethyl, or fluoromethyl, mercaptomethyl, methoxymethyl, n-propoxymethyl, methylthiomethyl, acetoxymethyl, propionyloxymethyl, benzoyloxymethyl, (p-chlorobenzoyl)oxymethyl, (p-methylbenzoyl)oxymethyl,

4,297,485 PRODUCTION OF A SELECTIVELY PROTECTED N-ACYLATED DERIVATIVE OF AN AMINOGLYCOSIDIC ANTIBIOTIC

Hamao Umezawa; Sumio Umezawa, both of Tokyo; Tsutomu Tsuchiya; Yasushi Takagi, both of Yokohama, and Tomo Jikihara, Kawasaki, all of Japan, assignors to Zaidan Hojin Biseibutsu Kagaku Kenkyu Kai, Tokyo, Japan

Filed Nov. 2, 1979, Ser. No. 90,591

Claims priority, application Japan, Nov. 11, 1978, 53-138402; Jun. 12, 1979, 54-73064

Int. Cl.³ C07H 15/22

U.S. Cl. 536—10

20 Claims

1. A process for the production of a selectively acylated N-protected derivative of an aminoglycosidic antibiotic, this aminoglycosidic antibiotic consisting essentially of a 6-O (3'-amino- or 3'-alkylamino-3'-deoxyglycosyl)-2-deoxystreptamine having or not having a 4-O-(aminoglycosyl) group, and the selectively acylated N-protected derivative having all amino groups other than 1-amino and 3'-amino groups thereof selectively protected with an acyl group, which comprises the steps of:

- reacting an acylation reagent having an acyl group to be introduced as the amino-protecting group, with an aminoglycosidic antibiotic-zinc cation complex which has been formed by reaction of the aminoglycosidic antibiotic with a zinc salt in an inert organic solvent, to produce a complex of zinc cations with the selectively N-acylated derivative of the aminoglycosidic antibiotic having the initially non-complexed amino groups acylated,
- and reacting the complex of zinc cations with the selectively N-acylated derivative of the aminoglycosidic antibiotic, with a reagent which removes zinc cations from said complex, to produce the desired selectively acylated N-protected derivative of the aminoglycosidic antibiotic.

4,297,486 AMINOGLYCOSIDE ANTIBIOTIC G-367-1 AND METHOD FOR THE PRODUCTION THEREOF

Tadashi Fujii, Mishima; Shuzo Sato, Shizuoka; Naoki Muto, Shizuoka; Mitsuo Hayashi, Shizuoka; Akira Kodama, Shizuoka, and Masaru Otani, Shizuoka, all of Japan, assignors to Toyo Jozo Kabushiki Kaisha, Shizuoka, Japan

Filed Apr. 3, 1980, Ser. No. 137,292

Claims priority, application Japan, Apr. 4, 1979, 54-41274; Aug. 16, 1979, 54-104770


Int. Cl.³ C07H 15/22

U.S. Cl. 536—17 R

1 Claim

1. Aminoglycoside antibiotic of the formula


pivaloyloxymethyl, (1-adamantyl)carboxymethyl, butanoyloxymethyl, carbamoyloxymethyl, (N-methylcarbamoyl)oxymethyl, (N-ethylcarbamoyl)oxymethyl, [N-(2-chloroethyl)carbamoyl]oxymethyl, (N-phenylcarbamoyl)oxymethyl, (N-p-sulfonylphenylcarbamoyl)oxymethyl, p-carboxymethylphenylcarbamoyloxymethyl, methoxycarbonyloxymethyl, isobutanoyloxymethyl, cyclobutylcarbonyloxymethyl, carbamoylthiomethyl, (ethoxythiocarbonyl)thiomethyl, (n-propoxythiocarbonyl)thiomethyl, (cyclopentanoxythiocarbonyl)thiomethyl, N,N-diethylthiocarbonylthiomethyl, N-methylpiperazin-1-thiocarbonylthiomethyl, N,N-dimethylpiperazin-1-thiocarbonylthiomethyl, 2-furoylthiomethyl, isothiuroniummethyl, (5-methyl-1,3,4-thiadiazol-2-yl)thiomethyl, p-tolylsulfonylethiomethyl, mesyloxymethyl, 1-methyl-1,2,3,4-tetrazolyl-5-thiomethyl, tosyloxymethyl, sulfamoyloxymethyl, 1-naphthoyloxymethyl, 2-furylacetoxymethyl, cinnamoyloxymethyl, p-hydroxycinnamoyloxymethyl, p-sulfocinnamoyloxymethyl and 1R:2S-epoxypropylphosphonyloxymethyl, or pyridinium methyl; and acylamido is




wherein n is 0-4, Z is oxygen or sulfur, and R'' is benzyl, p-hydroxybenzyl, 4-amino-4-carboxybutyl, methyl, cyanomethyl, 2-pentenyl, n-amyl, n-heptyl, ethyl, 3- or 4-nitrobenzyl, phenethyl, β,β -diphenylethyl, methylphenylmethyl, triphenylmethyl, 2-methoxyphenyl, 2,6-dimethoxyphenyl, 2,4,6-trimethoxyphenyl, 3,5-dimethyl-4-isoxazolyl, 3-butyl-5-methyl-4-isoxazolyl, 5-methyl-3-phenyl-4-isoxazolyl, 3-(2-chlorophenyl)-5-methyl-4-isoxazolyl, 3-(2,6-dichlorophenyl)-5-methyl-4-isoxazolyl, D-4-amino-4-carboxybutyl, D-4-N-benzoylamino-4-carboxy-n-butyl, p-aminobenzyl, o-aminobenzyl, m-aminobenzyl, (3-pyridyl)methyl, 2-ethoxy-1-naphthyl, 3-carboxy-2-quinoxalyl, 3-(2,6-dichlorophenyl)-5-(2-furyl)-4-isoxazolyl, 3-phenyl-4-isoxazolyl, 5-methyl-3-(4-guanidinophenyl)-4-isoxazolyl, 4-guanidinomethylphenyl, 4-guanidinomethylbenzyl, 4-guanidinobenzyl, 4-guanidinophenyl, 2,6-dimethoxy-4-guanidinophenyl, o-sulfobenzyl, p-carboxymethylbenzyl, p-carbamoylmethylbenzyl, m-fluorobenzyl, m-bromobenzyl, p-chlorobenzyl, p-methoxybenzyl, 1-naphthylmethyl, 3-isothiazolylmethyl, 4-isothiazolylmethyl, 5-isothiazolylmethyl, 4-pyridylmethyl, 5-isoxazolylmethyl, 4-methoxy-5-isoxazolylmethyl, 4-methyl-5-isoxazolylmethyl, 1-imidazolylmethyl, 2-benzofuranylmethyl, 2-indolylmethyl, 2-phenylvinyl, 2-phenylethynyl, 2-(5-nitrofuranyl)vinyl, phenyl, o-methoxyphenyl, o-chlorophenyl, o-phenylphenyl, p-aminomethylbenzyl, 1-(5-cyanotriazolyl)methyl, difluoromethyl, dichloromethyl, dibromomethyl, 1-(3-methylimidazolyl)methyl, 2- or 3-(5-carboxymethylthienyl)methyl, 2- or 3-(4-carbamoylthienyl)methyl, 2- or 3-(5-methylthienyl)methyl, 2- or 3-(5-methoxythienyl)methyl, 2- or 3-(4-chlorothiophenyl)methyl, 2- or 3-(sulfothiophenyl)methyl, 2- or 3-(5-carboxythienyl)methyl, 3-(1,2,5-thiadiazolyl)methyl, 3-(4-methoxy-1,2,5-thiadiazolyl)methyl, 2-furylmethyl, 2-(5-nitrofuryl)methyl, 3-furylmethyl, 2-thienylmethyl, 3-thienylmethyl, and tetrazolylmethyl; and the pharmaceutically acceptable salts thereof, or the carboxylic acid protecting derivatives thereof wherein the derivative group is methyl, t-butyl, trichloroethyl, allyl, propargyl, benzyl, diphenylmethyl, o-nitrobenzyl, 3,5-dinitrobenzyl, p-methoxybenzyl, acetoxymethyl, pivaloyloxymethyl, phenacyl, trichloroethoxy carbonyl, trimethylsilyl or tributyltin.

4,297,489
7- α -AMINO-SUBSTITUTED
ACYLAMINO-3-(1-CARBOXYMETHYL)TETRAZOL-5-
YLTHIOMETHYL-3-CEPHEM-4-CARBOXYLIC ACIDS
William J. Gottstein, Fayetteville; Murray A. Kaplan, Syracuse,
and Alphonse P. Granatek, Baldwinsville, all of N.Y., assign-
ors to Bristol-Myers Company, New York, N.Y.
Continuation-in-part of Ser. No. 502,991, Sep. 3, 1974,
abandoned. This application Jun. 27, 1975, Ser. No. 590,971
Int. Cl.³ C07D 501/54, 501/56; A61K 31/545
U.S. Cl. 544-27 15 Claims

1. A compound of the formula



wherein R² is hydrogen, pivaloyloxymethyl, acetoxymethyl, methoxymethyl, acetonyl, phenacyl, p-nitrobenzyl, β,β,β -trichloroethyl, 3-phthalidyl or 5-indanyl and having the D configuration in the 7-side chain wherein R¹ has the structure




4,297,490
BICYCLIC HETEROCYCLIC AMINO DERIVATIVES
Peter Neumann, Berne, Switzerland, assignor to Sandoz Ltd.,
Basel, Switzerland
Continuation of Ser. No. 869,209, Jan. 13, 1978, abandoned. This
application Feb. 22, 1979, Ser. No. 14,213
Claims priority, application Switzerland, Jan. 14, 1977,
463/77

Int. Cl.³ C07D 277/08, 268/08

U.S. Cl. 544-55

1. A compound having the formula



wherein

X is oxygen or sulfur, the heterocyclic amino moiety is bonded to the benzene ring of the bicyclic moiety,

n is an integer 1 or 2,

R₁, which is bonded to the benzene ring of the bicyclic moiety, is hydrogen, halo, C₁₋₄alkyl, C₁₋₄alkylthio, C₁₋₄alkoxy, trifluoromethyl or hydroxy,

A is a five-membered heterocyclic ring selected from the group consisting of [b]pyrrole, [c]pyrrole, [d]triazole, [b]furan, [c]furan, [c]furazan, [d](1,2,3)-thiadiazole, [b]pyrroline, [c]pyrroline, [b]dihydrofuran, [c]dihydrofuran, [b]dihydrothiophene, [c]isoxazole and [d]isoxazole,

R₂, which is bonded to the A ring of the bicyclic moiety and attached to a carbon atom of said ring, is hydrogen, halo, C₁₋₄alkyl, C₁₋₄alkoxy, C₁₋₄alkylthio, trifluoromethyl or hydroxy, and

R₃, which is bonded to the A ring of the bicyclic moiety and attached to a nitrogen atom of said ring, is hydrogen or C₁₋₄alkyl, with the provisos that:

(i) when A is [c]pyrrole, the nitrogen atom is C₁₋₄alkyl-substituted, and

(ii) when A is [b]furan, X is oxygen and n is 1, the oxazolinyllamino group is attached to either the 4- or 7-position of the bicyclic moiety,

said compound being in free base or in pharmaceutically acceptable acid addition salt form.

4,297,491
PREPARATION OF 2,3-DIOXO-1,4-BENZOXAZINE
DERIVATIVES

Gernot Reissenweber, Ludwigshafen, and Dietrich Mangold,
Neckargemuend, both of Fed. Rep. of Germany, assignors to
BASF Aktiengesellschaft, Fed. Rep. of Germany

Filed Nov. 3, 1980, Ser. No. 203,447


Claims priority, application Fed. Rep. of Germany, Nov. 6, 1979, 2944696

Int. Cl.³ C07D 265/32


U.S. Cl. 544-105

3 Claims

1. A process for the preparation of a 2,3-dioxo-1,4-benzoxazine derivative of the formula I



where R¹ and R² are identical or different and each is hydrogen, alkyl, halogen, haloalkyl, alkoxy, haloalkoxy or nitro, wherein an isatin of the formula II



24 Claims

where R¹ and R² have the above meanings, is oxidized with a peroxydisulfate, dissolved or suspended in 30-98% strength sulfuric acid.

4,297,492
PHENOLIC-1,3,5-TRIAZINES
Michael Rasberger, Siegfried Rosenberger, and Samuel Evans,
all of Riehen, Switzerland, assignors to Ciba-Geigy Corpora-
tion, Ardsley, N.Y.

Filed Mar. 10, 1980, Ser. No. 128,987


Claims priority, application Switzerland, Mar. 23, 1979, 2739/79

Int. Cl.³ C07D 251/46, 251/48, 251/70, 251/26


U.S. Cl. 544-211

8 Claims


1. A compound of the general formula I




in which X, Y and Z independently of one another are —O—, —S— or —N(R₃)—, in which R₃ can be hydrogen, —NH₂, C₁₋₁₈ alkyl, C₂₋₁₈ oxaalkyl, C₂₋₁₈ thiaalkyl, C₃₋₆ alkenyl, C₃₋₄ alkynyl, C₅₋₁₂ cycloalkyl, C₆₋₁₄ aryl, which is unsubstituted or substituted by C₁₋₈ alkyl, or C₇₋₁₈ aralkyl, which can be substituted in the aryl moiety by —OH and C₁₋₈ alkyl, R₁ is C₂₋₁₈ alkylene which can be interrupted by one or two —O—, —S— or —COO— or by one —O—P(R₄)—O—, in which R₄ is C₁₋₁₈ alkyl, allyl, cyclohexyl or phenyl, or C₅₋₁₂ cycloalkylene, C₃₋₄ alkenylene, phenylene, biphenylene, 1,4-cyclohexylenedimethylene, 1,3,3-trimethylcyclohexylene or one of the two groups of the formulae




in which R₅ is —O—, —S—, —NH— or —(R₆)C(R₇)—, in which R₆ and R₇ are hydrogen or C₁₋₈ alkyl, or R₆ and R₇ together with the C atom to which they are bonded form C₅₋₁₂ cycloalkylene, or, furthermore, if X and Y are —N(R₃)—, R₁ is a direct bond or, together with the two radicals —N(R₃)—, forms a piperazine ring which can be substituted by C₁₋₄alkyl, and if X and Y are —N(R₃)— or —S—, R₁ can be one of the three bivalent groups of the formulae







in which R_8 is C_1 - C_{18} alkyl, C_3 - C_6 alkenyl, C_5 - C_{12} cycloalkyl, phenyl, benzyl or Q , and Q is a group of the formula




in which R_9 is C_1 - C_8 alkyl, and p is the numbers 1-3 and q is the number 1 or 2, or, furthermore, if X and Y are $-O-$, R_1 is a group of the formula II



in which Q is as defined above and R_{10} is C_1 - C_{18} alkyl, C_3 - C_6 alkenyl, C_5 - C_{12} cycloalkyl, phenyl, benzyl, Q or α, α -dimethylbenzyl, and R_2 is hydrogen, C_1 - C_{18} alkyl, C_2 - C_{18} oxaalkyl, C_2 - C_{18} thiaalkyl, C_3 - C_{19} alkoxyalkyl, C_3 - C_6 alkenyl, C_3 - C_4 alkynyl, C_5 - C_{12} cycloalkyl, C_6 - C_{14} aryl, which is unsubstituted or substituted by C_1 - C_8 alkyl, C_7 - C_{23} alkaryl, which can be substituted in the aryl moiety by $-OH$, or C_7 - C_{18} aralkyl which can be interrupted in the alkylene moiety by $-S-$ or $-COO-$ and can be substituted in the aryl moiety by $-OH$ and C_1 - C_8 alkyl, or, if Z is $-O-$, R_2 can be one of the two groups of the formulae



in which Q , p and q are as defined above, R_{11} is C_1 - C_8 alkyl, R_{12} is C_1 - C_{18} alkyl or phenyl and r is the number nought, 1 or 2 and, furthermore, if Z is $-N(R_3)-$, R_2 is one of the two groups of the formulae $-NH-CO-CH_2-Q$ or $NH-Q$, or p -anilinophenyl, in which Q is as defined above, or, furthermore, if Z is $-N(R_3)-$ or $-O-$, R_2 can be a group Q_1 of the formula



in which R_{13} is C_1 - C_4 alkyl and, if m is nought, R_2 can also be halogen, and m is nought or 1 and n is the numbers 2-200, it being possible for the recurring structural units to be identical or different, with the proviso that, in formula I, at least one of the radicals $-X-R_1-Y-$ and $-(Z)_m-R_2$ is a phenol radical hindered by at least one hydrocarbon radical.

4,297,493
MANUFACTURE OF
4-AMINO-5-CHLORO-1-PHENYLPYRIDAZ-6-ONE
USING AQUEOUS PHENOL-4-SULFONIC ACID
 Winfried Richarz, Helmut Froehlich, and Harald Schroeder, all of Ludwigshafen, Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Fed. Rep. of Germany
 Filed Sep. 8, 1980, Ser. No. 185,403


Claims priority, application Fed. Rep. of Germany, Sep. 15, 1979, 2937421

Int. Cl.³ C07D 237/14

U.S. Cl. 544-241 **2 Claims**
 I. A process for the manufacture of substantially pure 4-amino-5-chloro-1-phenylpyridaz-6-one by reaction of 4,5-dichloro-1-phenylpyridaz-6-one with ammonia, wherein the reaction is carried out with an aqueous solution of ammonia, at from 20° to 200° C. and from 1 to 20 bars, in the presence of phenol-4-sulfonic acid.


4,297,494
XANTHINE TRACERS
 Ernest V. Groman, Somerville, and Michael D. Cabelli, Waltham, both of Mass., assignors to Baxter Travenol Laboratories, Inc., Deerfield, Ill.
 Filed Aug. 9, 1978, Ser. No. 932,146
 Int. Cl.³ C07D 473/08, 473/12

U.S. Cl. 544-267 **12 Claims**
 I. Radioiodinatable xanthine derivatives having the formula:



wherein

- R_1 is an imidazole, pyrrole, thiophene, indole or polyunsaturated alkenyl radical;
- R_3 is a hydroxy-substituted, unsaturated cyclic hydrocarbon radical;
- R_7 is a pyrrole, furan, thiophene, polyunsaturated alkenyl, imidazole or indole radical, with the proviso that
 - the imidazole radical has the structure $-L(X)_n$ wherein L is a linking group containing at least one ester, ether, amide or amino bond, X is imidazole and n ranges from 1 to about 10; and
 - the indole radical has the structure:



wherein Q is hydrogen or hydroxyl and Y is hydrogen, halo or lower alkyl up to about 7 carbon atoms; and
 (d) R^8 is a pyrrole, furan or imidazole radical wherein the imidazole radical is set forth in part (c) (1); with the further proviso that no more than two of R_1 , R_3 , R_7 or R_8 are the above radicals and that if R_1 , R_3 , R_7 or R_8 are not one of the above radicals then R_1 is hydrogen, acetate or methyl; R_3 is methyl; R_7 is hydrogen, acetate or methyl; and R_8 is hydrogen.

4,297,495
PREPARATION OF 2-ISOPROPYLAMINO PYRIMIDINE
 Andre Esanu, Paris, France, assignor to Societe d'Etudes de Produits Chimiques, Paris, France
 Filed Jun. 30, 1980, Ser. No. 164,889
 Claims priority, application United Kingdom, Aug. 9, 1979, 27811/79


Int. Cl.³ C07D 239/42

U.S. Cl. 544-330 **1 Claim**
 1. Process for the preparation of 2-isopropylamino pyrimidine comprising reacting bis (isopropylguanidine) sulphate with 1,1,3,3-tetraethoxy-propane in stoichiometric proportions at 40°-60° C., in acidic aqueous solution.

4,297,496
NITRIMINE DERIVATIVES
 Royston H. Davis, Sittingbourne, and John H. Davies, Canterbury, both of England, assignors to Shell Oil Company, Houston, Tex.
 Filed Jun. 23, 1980, Ser. No. 162,340
 Claims priority, application United Kingdom, Jul. 30, 1979, 26479/79

Int. Cl.³ C07D 239/18

U.S. Cl. 544-332 **4 Claims**
 1. A nitriminoheterocyclic compound of the general formula:



wherein R is hydrogen, alkyl of from one to six carbon atoms or alkanoyl of up to seven carbon atoms, and R^1 is hydrogen or alkyl of from one to six carbon atoms.

4,297,497
SYNTHESIS OF 2-KETO-1,4-DIAZACYCLOALKANES
 John T. Lai, Broadview Heights, Ohio, assignor to The B. F. Goodrich Company
 Continuation-in-part of Ser. No. 916,640, Jun. 19, 1978, Pat. No. 4,167,512, which is a continuation-in-part of Ser. No. 835,066, Sep. 21, 1977, abandoned. This application Jul. 13, 1979, Ser. No. 57,238
 Int. Cl.³ C07D 241/08


U.S. Cl. 544-384 **5 Claims**
 1. A method which is directive for preparing symmetrical polysubstituted 2-keto-1,4-diazacycloalkanes, said method comprising:
 contacting a 1,2-diamine, a saturated monoketone and haloform in the presence of aqueous or solid alkali and a cata-

lytic effective amount of a phase transfer catalyst of the formula




wherein R and R' are independently selected from the group consisting of alkyl having 1 to 16 carbon atoms and substituted alkyl wherein said substituents can be hydroxy, sulfur, amine or ether.

4,297,498
4-TERTIARY-AMINO-2,6-DIAMINOPYRIDINE 1-OXIDES
 John E. Lawson, and Ronald D. Dennis, both of Evansville, Ind., assignors to Mead Johnson & Company, Evansville, Ind.
 Division of Ser. No. 873,294, Jan. 30, 1978, Pat. No. 4,182,888, which is a division of Ser. No. 773,041, Feb. 28, 1977, Pat. No. 4,080,500, which is a division of Ser. No. 638,473, Dec. 8, 1975, Pat. No. 4,021,562. This application Aug. 23, 1979, Ser. No. 68,983
 Int. Cl.³ C07D 411/12, 498/04, 401/12
U.S. Cl. 546-116 **3 Claims**
 1. A compound having Formula IV or Formula V



Formula IV



Formula V

wherein R is selected from the group consisting of diethylamino, pyrrolidino, piperidino, morpholino, thiomorpholino, and N -methylpiperazino.
 3. The compound according to claim 1 which is 5-amino-7-(piperidinyl)-2H-[1,2,4]oxadiazolo[2,3-a]pyridin-2-one.

4,297,499
NOVEL DISUBSTITUTED DICHLOROSILANE AND METHOD FOR PRODUCING SAME
 Isao Koga, Yokohamashi; Yohji Terui, Chibashi; Masuhito Ohgushi, and Tohru Kitahara, both of Minamata, all of Japan, assignors to Chisso Corporation, Osaka, Japan
 Filed Apr. 11, 1978, Ser. No. 895,332
 Claims priority, application Japan, Apr. 12, 1977, 52-41686; Jun. 30, 1977, 52-78186; Jan. 24, 1978, 53-6584
 Int. Cl.³ C07F 7/08

U.S. Cl. 556-465 **11 Claims**
 1. A disubstituted dichlorosilane having the general formula



wherein R' is an alkyl group having 2-3 carbon atoms and R'' is an alkyl group having 8-20 carbon atoms, or R' is an alkyl group having 4-20 carbon atoms and R'' is an alkyl group having 5-20 carbon atoms which is different from R' , or R' is phenethyl group and R'' is cyclohexyl group.

4,297,500

CONVERSION OF LOW-BOILING CONSTITUENTS FROM ALKYL-CHLOROSILANE SYNTHESIS

Ulrich Finke, Ettlingen, and Hans-Heinrich Moretto, Cologne, both of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany
Filed Nov. 24, 1980, Ser. No. 209,932

Claims priority, application Fed. Rep. of Germany, Dec. 14, 1979, 2950402

Int. Cl.³ C07F 7/08

U.S. Cl. 556—466

4 Claims

1. A process for converting the low-boiling constituents formed in the preparation of methylchlorosilane in the Müller-Rochow process and which consist essentially of tetramethylsilane, dimethylmonochlorosilane and 2-methylbut-2-ene into a product mixture consisting essentially of trimethylchlorosilane, dimethylchlorosilane and C₂₋₂₀ alkylchlorosilanes, comprising contacting the low-boiling product mixture with AlCl₃, AlOCl and/or AlBr₃, together with hydrogen chloride, in the liquid phase at about 40° to +25° C.

4,297,501

PROCESS FOR THE PREPARATION OF URETHANES

Robert Becker; Johann Grolig, both of Leverkusen, and Christian Rasp, Cologne, all of Fed. Rep. of Germany, assignors to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany
Filed Feb. 27, 1980, Ser. No. 125,394

Claims priority, application Fed. Rep. of Germany, Mar. 2, 1979, 2908251

Int. Cl.³ C07C 125/065

U.S. Cl. 560—24

9 Claims

1. A heat efficient process for the preparation of urethanes comprising reacting primary amines with carbon monoxide and organic compounds having at least one hydroxyl group in the presence of

- molecular oxygen as oxidizing agent,
- a noble metal and/or a compound of a noble metal of the 8th subgroup of the Periodic System of Elements, and
- a compound of an element of the 3rd to 5th main group and/or 1st to 8th subgroup of the Periodic System of Elements, said compound being capable of undergoing Redox reactions under the reaction conditions.

4,297,502

AROMATIC BISAZOMETHINES, A METHOD FOR THEIR PREPARATION, AND THEIR USE AS REACTIVE PIGMENTS

Hans-Joachim Herrmann; Günther Meyer, both of Troisdorf, and Klaus-Dieter Steffen, Hennef, all of Fed. Rep. of Germany, assignors to Dynamit Nobel Aktiengesellschaft, Troisdorf, Fed. Rep. of Germany

Filed Jun. 19, 1980, Ser. No. 161,182


Claims priority, application Fed. Rep. of Germany, Jun. 21, 1979, 2924964

Int. Cl.³ C07C 101/68, 119/10

U.S. Cl. 560—35

12 Claims

1. An aromatic bisazomethine prepared from disubstituted benzidines and aromatic aldehydes, characterized by the general formula



wherein

each R = COOCH₃, COOC₂H₅, COOH, CH₂Cl, CHCl₂, CH₂Br, CCl₃, Cl or Br and
each R' = Cl, OCH₃ or CH₃.

4,297,503

NOVEL BENZAMIDE DERIVATIVE AND METHOD OF PREPARING METOCLOPRAMIDE USING SAME

Joji Nishikido, Fuji; Nobuhiro Tamura, Chigasaki; Yohei Fukuoka, Kurashiki, and Hiroyuki Yamane, Nobeoka, all of Japan, assignors to Asahi Kasei Kogyo Kabushiki Kaisha, Osaka, Japan

Division of Ser. No. 58,809, Jul. 19, 1979, Pat. No. 4,250,110.

This application Sep. 26, 1980, Ser. No. 190,994


Claims priority, application Japan, Jul. 31, 1978, 53/92564

Int. Cl.³ C07C 101/74

U.S. Cl. 560—42

2 Claims

1. 2-Chloro-4-carboalkoxy-5-methoxybenzamide of the formula (II),



wherein R₁ is a C₁₋₇ alkyl group, a C₁₋₇ haloalkyl group or a phenyl group.

4,297,504

19-HYDROXY-6A-CARBA-PGI₂ COMPOUNDS

John C. Sih, Portage, Mich., assignor to The Upjohn Company, Kalamazoo, Mich.

Division of Ser. No. 54,811, Jul. 5, 1979, Pat. No. 4,225,508.


This application Mar. 3, 1980, Ser. No. 126,471

Int. Cl.³ C07C 177/00

U.S. Cl. 560—119

1 Claim

1. A prostacyclin-type compound of the formula

wherein L₃ is

- (CH₂)_n-, wherein n is one to 5, inclusive,
- (CH₂)_p-CF₂-, wherein p is 2, 3, or 4, or
- CH₂-CH=CH-;

wherein M₂ is

wherein Q is oxo, α-H:β-H, α-OH:β-R₄, or α-R₄:β-OH, wherein R₄ is hydrogen or alkyl of one to 4 carbon atoms, inclusive,

wherein R₃ is

- hydrogen,
- alkyl of one to 12 carbon atoms, inclusive,
- cycloalkyl of 3 to 10 carbon atoms, inclusive,
- aralkyl of 7 to 12 carbon atoms, inclusive;
- phenyl,

(f) phenyl substituted with one, 2, or 3 chloro or alkyl groups of one to 3 carbon atoms, inclusive;

(g) -(Ph)-CO-CH₃,(h) -(p-Ph)-NH-CO-(p-Ph)-NH-CO-CH₃,

(i) -(p-Ph)-NH-CO-(p-Ph)-

(j) -(p-Ph)-NH-CO-CH₃,(k) -(p-Ph)-NH-CO-NH₂,(l) -(p-Ph)-CH-N-NH-CO-NH₂,

(m) β-naphthyl,

(n) -CH₂-CO-R₁₆,

wherein -(Ph)- is inter-phenylene and -(p-Ph)- is inter-para-phenylene or para-phenyl;

wherein R₁₆ is phenyl, p-bromophenyl, p-biphenyl, p-nitrophenyl, p-benzamidophenyl, or 2-naphthyl, or

(o) a pharmacologically acceptable cation;

wherein R₅ and R₆ are hydrogen, alkyl of one to 4 carbon atoms, inclusive, or fluoro, being the same or different, with the proviso that one of R₅ and R₆ is fluoro only when the other is hydrogen or fluoro;

wherein R₉ is hydrogen or hydroxyl; and

wherein X is

(1) trans-CH=CH-,

(2) cis-CH=CH-,

(3) -C≡C-, or

(4) -CH₂CH₂-.

4,297,505

PROCESS FOR THE PREPARATION OF PENTACHLORO-3-BUTENOIC ACID ESTERS

Günther Maahs, and Konrad Rombusch, both of Marl, Fed. Rep. of Germany, assignors to Chemische Werke Huels, Aktiengesellschaft, Marl, Fed. Rep. of Germany
Filed Jun. 20, 1980, Ser. No. 161,617

Claims priority, application Fed. Rep. of Germany, Jun. 21, 1979, 2925012

Int. Cl.³ C07C 69/65

U.S. Cl. 560—219

11 Claims

1. A process for preparing a pentachloro-3-butenic acid alkyl ester which comprises reacting the corresponding 1-alkoxyheptachloro-3-butene with an aqueous solution of an alkali metal carbonate.

4,297,506

SYNTHESIS OF ESTERS

Kiplin D. Cowan, Bartlesville, Okla., assignor to Phillips Petroleum Co., Bartlesville, Okla.

Filed Jan. 8, 1980, Ser. No. 110,302

Int. Cl.³ C07C 67/04, 31/20

U.S. Cl. 560—246

4 Claims

1. In a process for producing a diacetoxalkene from a conjugated diene, a halogen, an alkali metal acetate, and an acid wherein there is obtained in a reaction zone a reaction mass comprising alkali metal acetate, alkali metal halide, acid, and diacetoxalkene occluded in said mass in the salts therein which cannot be separated by distillation of the non-occluded diacetoxalkene from said mass, the steps of (1) distilling non-occluded diacetoxalkene, and (2) recycling to the reaction zone at least a portion of said mass containing said occluded diacetoxalkene whereby the yield of diacetoxalkene from said reaction zone and said distillation is increased.

4,297,507

PROCESS AND APPARATUS FOR PRODUCING TEREPHTHALIC ACID WITH HIGH PURITY

Makoto Komatsu; Yuji Takamizawa, and Tazuo Ohta, all of Kurashiki, Japan, assignors to Mitsubishi Gas Chemical Co. Inc., Tokyo, Japan

Continuation of Ser. No. 9,963, Feb. 6, 1979, abandoned. This application Mar. 24, 1980, Ser. No. 133,106

Claims priority, application Japan, Feb. 20, 1978, 53-17649

Int. Cl.³ C07C 51/16

U.S. Cl. 562—416

13 Claims

1. A process for producing terephthalic acid of high purity

suitable for direct polymerization by oxidizing p-tolualdehyde at 180°-280° C. with a gas containing molecular oxygen in a solvent consisting of water in the presence of bromine ions, the concentration of the bromine ions being 0.5-12% by weight on the basis of the solvent, in a reactor using zirconium or a zirconium alloy as a reactor material.

4,297,508

PROCESS FOR PRODUCING 2-HYDROXY-NAPHTHALENE-3-CARBOXYLIC ACID

Yuzo Maegawa, Oita; Fujio Masuko, Oita, and Makoto Nakamura, Ibaraki, all of Japan, assignors to Sumitomo Chemical Company, Limited, Osaka, Japan

Filed Dec. 22, 1980, Ser. No. 218,973


Claims priority, application Japan, Dec. 25, 1979, 54-170056; Sep. 22, 1980, 55-132033

Int. Cl.³ C07C 51/15

U.S. Cl. 562—425

14 Claims

1. A process for producing 2-hydroxynaphthalene-3-carboxylic acid comprising reacting carbon dioxide with a homogeneous liquid mixture comprising an alkali metal salt of β-naphthol, β-naphthol and an alkylbenzene of the formula (I):



wherein R is the same or different and is a straight or branched alkyl group having 1 to 4 carbon atoms and n is an integer of 1 to 6.

4,297,509

PROCESS FOR PREPARING ALKALI METAL SALTS 3-AMINO-2,5-DICHLOROBENZOIC ACID

Bertrand A. Chiasson, South Charleston, W. Va., assignor to Union Carbide Corporation, New York, N.Y.

Filed Mar. 25, 1980, Ser. No. 133,787

Int. Cl.³ C07C 51/347

U.S. Cl. 562—456

8 Claims

1. A process for producing alkali metal salt of 3-amino-2,5-dichlorobenzoic acid in high yield comprising reacting alkali metal salt of 3-nitro-2,5-dichlorobenzoic acid with hydrogen under pressure at an elevated temperature in the presence of a molybdenum-promoted Raney nickel catalyst, said reaction being effected at a pH between about 6 and 12, and said reaction being effected in the presence of a water solvent.

4,297,510

UNSYMMETRICAL

DIPHOSPHATETRAAZACYCLOOCTATETRAENES

Kazimiera J. L. Paciorek, Corona Del Mar; Reinhold H. Kratzer, Irvine; Thomas I. Ito, Fountain Valley, and James H. Nakahara, Irvine, all of Calif., assignors to The United States of America as represented by the Secretary of the Air Force, Washington, D.C.

Filed Jun. 26, 1980, Ser. No. 163,135

Int. Cl.³ C07F 9/22; C10M 1/44

U.S. Cl. 564—13

2 Claims

1. The compound 1,3-bis(diphenylphospha)-5,7-bis[CF(CF₃)OC₃F₇]-2,4,6,8-tetraazacyclooctatetraene.

2. The compound 1,3-bis(diphenylphospha)-5,7-bis[CF(CF₃)OCF₂CF(CF₃)OC₃F₇]-2,4,6,8-tetraazacyclooctatetraene.

4,297,511

METHOD FOR THE MANUFACTURE OF POLYARYLAMINES HAVING METHYLENE BRIDGES
Efim Biller, Zurich, Switzerland, assignor to Sulzer Brothers Limited, Winterthur, Switzerland

Filed Sep. 4, 1979, Ser. No. 72,313

Claims priority, application Switzerland, Sep. 12, 1978, 9537/78

Int. Cl.³ C07C 87/28

U.S. Cl. 564—331

16 Claims

1. A method of making simultaneously monomeric 4,4'-methylene diarylamine and polyamines which comprises the steps of

condensing formaldehyde with a highly protonized aniline salt solution containing at least perfluoro-carbonic acid to obtain a homogeneous aqueous solution; and cooling the homogeneous solution in a given temperature range to crystallize and precipitate 4,4'-methylene diarylamine as a salt and to leave substantially the other condensed arylamines as salts in the residual liquid.

4,297,512

PROCESS FOR THE PREPARATION OF TRIETHYLAMINE

Klaus Mainusch, Bernhard Schleppinghoff, and Klaus Munter, all of Dormagen, Fed. Rep. of Germany, assignors to EC Erdolchemie GmbH, Cologne, Fed. Rep. of Germany

Filed Aug. 22, 1979, Ser. No. 68,849

Claims priority, application Fed. Rep. of Germany, Sep. 8, 1978, 2839135

Int. Cl.³ C07C 85/12

U.S. Cl. 564—490

14 Claims

1. In a process for the continuous preparation of triethylamine by catalytic hydrogenation of acetonitrile in the gas phase, the improvement which comprises employing as the catalyst a catalyst comprising a noble metal of Group VIII of the periodic system disposed on a lithium aluminum spinel catalyst, employing a temperature of 80° to 115° C. and a pressure of 1 to 60 bars gauge and carrying out the process in the presence of up to 3% by weight of monoethylamine and/or diethylamine relative to acetonitrile.

4,297,513

PROCESS FOR THE PREPARATION OF BENZOPHENONE THIOETHERS

Louis Felder, Basel, and Rudolf Kirchmayr, Aesch, both of Switzerland, assignors to Ciba-Geigy Corporation, Ardsley, N.Y.

Continuation of Ser. No. 39,465, May 16, 1979, abandoned. This application May 28, 1980, Ser. No. 153,985

Int. Cl.³ C07C 148/00, 149/32

U.S. Cl. 568—43

1 Claim

1. A process for the preparation of 4-(2-hydroxyethyl-mercapto)-benzophenone by reacting 4-chlorobenzophenone with 2-hydroxyethyl mercaptan in dimethylacetamide or dimethylformamide at 80° to 140° C. in the presence of an alkali metal carbonate or alkali metal hydroxide in an amount equivalent to the amount of 4-chlorobenzophenone.

4,297,514

METHOD OF OXIDIZING COMPOUNDS HAVING ACTIVATED METHYLENE RADICALS

King W. Ma, Midland, Mich., assignor to The Dow Chemical Company, Midland, Mich.

Continuation of Ser. No. 972,850, Dec. 26, 1978, abandoned.

This application Mar. 14, 1980, Ser. No. 130,325

Int. Cl.³ C07C 45/36, 45/28

U.S. Cl. 568—321

14 Claims

1. In a method for oxidizing fluorene to fluorenone comprising contacting fluorene with an oxidizing agent and an aqueous solution of a base of sufficient strength to deprotonate hydrogen from a —CH₂— radical of the fluorene in the presence of

a catalyst, the improvement comprising using as the catalyst a synergistic combination of:

- (1) a member from the group consisting of charcoal, graphite, carbon black, coke, activated carbon and mixtures thereof; and
- (2) a phase transfer catalyst.

4,297,515

DIKETONES USEFUL AS LIQUID CRYSTALS

Rudolf Eidenschink, Dieburg, and Ludwig Pohl, Darmstadt, both of Fed. Rep. of Germany, assignors to Merck Patent Gesellschaft mit Beschränkter Haftung, Darmstadt, Fed. Rep. of Germany

Filed May 9, 1980, Ser. No. 148,353


Claims priority, application Fed. Rep. of Germany, May 10, 1979, 2918775

Int. Cl.³ C07C 49/813, 49/792

U.S. Cl. 568—329

7 Claims

1. A diketone of the formula



wherein R₁ is alkyl, perfluoroalkyl or alkoxy, each of 1-18 carbon atoms; R₂ is alkyl of 1-12 carbon atoms; and X is 1,4-trans-cyclohexylene, 1,4-phenylene or 4,4'-cyclohexylphenyl.

4,297,516

1-SUBSTITUTED-1-OXO-PROSTANE-DERIVATIVES OF THE E, A AND F SERIES

Allan Wissner, Ardsley, N.Y., assignor to American Cyanamid Company, Stamford, Conn.


Continuation-in-part of Ser. No. 3,953, Jan. 16, 1979, Pat. No. 4,254,285, which is a continuation-in-part of Ser. No. 961,032, Nov. 18, 1978, abandoned, which is a continuation-in-part of Ser. No. 858,589, Dec. 8, 1977, Pat. No. 4,202,822, Ser. No. 858,588, Dec. 8, 1977, Pat. No. 4,170,597, Ser. No. 858,580, Dec. 8, 1977, Pat. No. 4,197,245, Ser. No. 858,487, Dec. 8, 1977, abandoned, Ser. No. 858,504, Dec. 8, 1977, Pat. No. 4,172,839, and Ser. No. 858,579, Dec. 8, 1977, Pat. No. 4,212,969. This application Jun. 7, 1979, Ser. No. 46,721

Int. Cl.³ C07C 177/00


U.S. Cl. 568—330

47 Claims


1. An optically active compound of the formula:




wherein Z is —(CH₂)_g— or




wherein g is an integer from 5 to 7 inclusive, and f is an integer from 2 to 4, inclusive; C₁₃—C₁₄ is ethylene or trans-vinylene; R₃ is hydrogen or hydroxyl; G is selected from the group consisting of:




wherein R is C₁—C₆ alkyl, phenyl or phenyl substituted with one or more substituents selected from the group consisting of C₁—C₄ alkyl, —OR₁₅, —SR₁₅, F or Cl wherein R₁₅ is C₁—C₄ alkyl; R₁₆ is C₁ to C₆ alkyl; R₂ is selected from the group consisting of:



-continued





wherein R_4 is hydrogen or methyl; R_5 is selected from the group consisting of C_4 - C_7 alkyl; R_6 is selected from the group consisting of C_3 - C_6 alkyl; R_7 is selected from the group consisting of C_2 - C_4 alkyl; R_8 is selected from the group consisting of C_1 - C_2 alkyl; R_9 is selected from the group consisting of C_3 - C_6 alkyl; R_{10} is selected from the group consisting of C_1 - C_4 alkyl; R_{11} is selected from the group consisting of C_3 - C_7 alkyl; R_{12} is selected from the group consisting of C_1 - C_4 alkyl; p is an integer from 0 to 3; q is 1 or 2; G' is $-O-$ or $-CH_2-$; and t is hydrogen, chloro, fluoro, dichloro, trifluoromethyl or methoxy.

4,297,517

PREPARATION OF CARBONYL COMPOUNDS FROM ALLYLETHERS

Johannes A. M. Van Broekhoven, and Eit Drent, both of Amsterdam, Netherlands, assignors to Shell Oil Company, Houston, Tex.

Filed Jul. 31, 1980, Ser. No. 174,074

Claims priority, application United Kingdom, Sep. 4, 1979, 30594/79

Int. Cl.³ C07C 45/59, 45/42

U.S. Cl. 568-361

11 Claims

1. A process for hydrolysing allylethers of the general formula:



(I)

wherein R_1 , R_2 , R_3 , R_4 , R_5 and R_6 , which may be the same or different, represent a hydrogen atom or an alkyl group of from 1 to 8 carbon atoms or one of R_1 , R_2 or R_3 and R_6 together represent a covalent bond, which comprises reacting at least one allylether according to the general formula I with water in the presence of a supported Group VIII metal catalyst selected

from the group consisting of platinum, palladium, rhodium and iridium.

4,297,518

DECOMPOSITION OF CUMENE HYDROPEROXIDE WITH A HOMOGENEOUS CATALYST

Ching-Yong Wu, O'Hara Township, Allegheny County; Wayne R. Pretzer, Oakmont, and Thaddeus P. Kobylinski, Gibsonia, all of Pa., assignors to Gulf Research & Development Company, Pittsburgh, Pa.

Filed Nov. 18, 1977, Ser. No. 852,923

Int. Cl.³ C07C 27/00, 45/00, 49/08, 39/04

U.S. Cl. 568-385

11 Claims

1. The method for cleaving cumene hydroperoxide at high selectivity approaching 100 percent to phenol and acetone using a homogeneous rhenium catalyst which comprises adding cumene hydroperoxide to a solution consisting essentially of phenol and acetone at a mol ratio of phenol to acetone of from about 1:1 to about 1:10 and up to about 15 weight percent cumene in an amount to form a reaction solution having between about 0.1 and about 20 weight percent cumene hydroperoxide, heating said reaction solution of cumene hydroperoxide, phenol and acetone in the presence of a rhenium catalyst consisting essentially of about 20 to about 60 parts of a soluble rhenium compound determined as rhenium heptoxide per million parts of the total reaction mixture for an average time of about one to about 60 minutes at a temperature between about 40° C. and about 80° C., and correlating the temperature, the concentration of rhenium compound and the average reaction time within said ranges whereby decomposition of the cumene hydroperoxide to phenol and acetone results with minimum decomposition to undesired products.

4,297,519

PROCESS FOR THE PREPARATION OF 2-NITROBENZALDEHYDE

Werner Ertel, Wuppertal, Fed. Rep. of Germany, assignor to Bayer Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany

Continuation-in-part of Ser. No. 8,633, Feb. 1, 1979, abandoned.

This application Feb. 28, 1980, Ser. No. 125,617

Claims priority, application Fed. Rep. of Germany, Mar. 2, 1978, 2808930

Int. Cl.³ C07C 45/28

U.S. Cl. 568-424

2 Claims

1. A process for the preparation of 2-nitrobenzaldehyde from 2-nitrotoluene which comprises brominating 2-nitrotoluene by a radical mechanism, to 2-nitrobenzyl bromide in the form of a bromination oil containing 20 to 50% of 2-nitrobenzyl bromide, and then oxidizing said bromination oil directly with a mixture of dimethylsulphoxide and sodium bicarbonate in a weight ratio of 3:1 to 10:1 at temperatures of up to 100° C. and subsequently isolating the 2-nitrobenzaldehyde via the bisulphite adduct.

4,297,520

PROCESS FOR PREPARING ANISALDEHYDE

Kozo Nakaoji, Osaka, Japan, assignor to Daiwa Chemical Company Ltd., Japan

Filed Mar. 4, 1980, Ser. No. 127,071

Claims priority, application Japan, Mar. 12, 1979, 54-29067

Int. Cl.³ C07C 45/28

U.S. Cl. 568-426

9 Claims

1. A process for preparing anisaldehyde comprising oxidizing p-methoxytoluene with a dichromate ion forming substance in an amount of 30 to 100 parts by weight calculated as CrO_3 per 100 parts by weight of p-methoxytoluene and sulfuric acid in a concentration of about 5 to 40% by weight, to provide an aqueous phase and an organic phase, separating said phases and recovering anisaldehyde and p-methoxytoluene from said organic phase.

ELECTRICAL

4,297,521

FOCUSING COVER SOLAR ENERGY COLLECTOR APPARATUS

Steven A. Johnson, 136 N. 1st West, Preston, Id. 83263


Filed Dec. 18, 1978, Ser. No. 970,762

The portion of the term of this patent subsequent to May 26, 1998, has been disclaimed.

Int. Cl.³ H01L 31/04; F24J 3/02

U.S. Cl. 136-248

20 Claims



1. A solar collector comprising:
a shell structure, the shell structure having an open top;
first mounting means for the shell structure;
solar energy absorber means inside the shell structure;
second mounting means for the shell structure and supporting the solar energy absorber means coaxially inside the shell structure in a nonrotatable position relative to the sun to thereby accommodate rotational movement of the shell about the solar energy absorber means to accommodate rotating the shell structure about an axis of the second mounting means to orient the open top of the shell structure toward the sun, the second mounting means comprising a first hollow shaft and a second shaft, the shell structure being rotatably mounted on the first hollow shaft and the second shaft, the second mounting means further comprising a bridge structure extending between and substantially aligned with the first hollow shaft and the second shaft, the bridge structure supporting the solar energy absorber means; and
optical means in the shell structure for directing solar energy toward the solar energy absorber means, said optical means comprising a Fresnel lens means for focusing solar flux and mirror means for reflecting the focused solar flux toward the solar energy absorber means, said Fresnel lens means comprising a transparent cover over the open top of the shell structure.

4,297,522

CABLE SHIELD


Harold W. Jesse, Amherst, and Peter M. Jones, Sandown, both of N.H., assignors to TME, Inc., Hudson, N.H.

Filed Sep. 7, 1979, Ser. No. 73,197

Int. Cl.³ H01B 11/10

U.S. Cl. 174-36

6 Claims



1. A cable shielding device comprising a length of a first sheet of self-supporting metal foil, said first sheet having longitudinal edge portions, a length of a second sheet of self-supporting metal foil of a width greater than said first sheet, said second sheet having longitudinal edges, portions of said second sheet forming flanges which are in electrical contact with said first sheet surface which it overlies, a first low friction surface coupled to the first sheet on the sheet side opposite the flange

4,297,523

GAS PIPE CABLE

Carl D. Floessel, Fislisbach, and Klaus Floessel, Wettingen, both of Switzerland, assignors to BBC Brown, Boveri & Company, Ltd., Baden, Switzerland


Filed May 21, 1980, Ser. No. 152,148

Claims priority, application Switzerland, Jul. 5, 1979, 6277/79

Int. Cl.³ H01B 9/06; H02G 5/06

U.S. Cl. 174-27

16 Claims



5. In a three phase gas pipe cable having at least one gas pipe cable section and having in said at least one gas pipe cable section three phase conductors arranged within an enclosing pipe in a triangular configuration, said three phase conductors each being held at support locations by at least one supporting insulator at each support location, a conductor supporting apparatus for each phase conductor comprising:

at least one supporting insulator for each phase conductor in each gas pipe cable section;
an insulator foot included on said supporting insulator, said foot facing said enclosing pipe;

a slide bearing, said slide bearing including:

a slide bearing block, said slide bearing block being rigidly connected to said enclosing pipe, and said slide bearing block having:

a bearing block groove, said bearing block groove being disposed substantially parallel to the longitudinal axis of said enclosing pipe and substantially parallel to the longitudinal axis of said phase conductor; and

a sliding bolt member, said sliding bolt member being rigidly connected to said insulator foot included on the supporting insulator, and said sliding bolt member having a free-standing end accommodated in said bearing block groove;

whereby said supporting insulator is capable of motion in the direction of the longitudinal axis of said enclosing pipe and in the direction of the longitudinal axis of said phase conductor.

4,297,524

ELECTRICAL ACTIVATING ASSEMBLY AND RECEPTACLE SUPPORT MEANS THEREFOR


Frank W. Fork, Allison Park, Pa., assignor to H. H. Robertson Company, Pittsburgh, Pa.

Filed Dec. 26, 1979, Ser. No. 107,411

Int. Cl.³ H02G 3/12

U.S. Cl. 174—48

13 Claims



1. A barrier including a barrier outer surface; a chamber in said barrier having a chamber opening at said barrier outer surface; spaced-apart conduit means having conduit openings communicating with said chamber; and an assembly comprising:

rim means presenting a rim opening, said rim means residing within said chamber opening and below but proximate to said barrier outer surface;

a support plate supported in part by said rim means below but proximate to and substantially parallel with said barrier outer surface, said support plate having a central opening and support ears presented at said central opening;

a plate element formed integrally with and extending from one edge of said support plate into said chamber;

a partition element overlapping said plate element and cooperating therewith to divide said chamber into first and second compartments each containing one of said conduit openings;

an electrical receptacle secured to and supported by said support ears within said first compartment and presenting a plug at said barrier outer surface; and

a closure member supported at said barrier outer surface in capping relation with said rim opening.

4,297,525

ELECTRICAL OUTLET BOX AND PAWL MOUNTING DEVICE

Wade R. Bowden, Jr., Northport, N.Y., assignor to Slater Electric Inc., Glen Cove, N.Y.

Filed Mar. 22, 1979, Ser. No. 22,992


Int. Cl.³ H02G 3/08

U.S. Cl. 174—58

14 Claims

1. An electrical outlet box having a wall structure providing front to rear wall means and a bottom wall interconnected therebetween, the front to rear wall means and bottom wall defining a chamber within the wall structure which opens through the front of the box, said front to rear wall means comprising a pair of opposed side walls and a pair of opposed end walls interconnected between said side walls, each of said side and end walls terminating in a common frontal plane defining the front opening of said box, said box further including electrical fixture mounting post members adjacent the inside surface of each opposed end wall in opposed alignment generally centrally of said end walls, said wall means also defining an outermost periphery of said box and including end wall portions which are recessed inwardly from said periphery and inwardly from the remainder of said end wall so as to define recessed areas extending along said periphery of said box from the front to the rear thereof, said recessed areas in

said end walls being in diagonally opposed alignment on opposite sides of said electrical fixture mounting post members, first flange means secured to said front to rear wall means extending laterally outwardly beyond said outermost periphery of said box, pawl means mounted in said recessed areas, said pawl means being rotatably actuable between a retracted position within the confines of said outermost periphery of said box and an extended position beyond said outermost periphery of said box, said pawl means including clamping flange means adapted to engage the wall surface adjacent said wall opening when said pawl means is in said extended position, means restraining rotational movement of said pawl means in both clockwise and



counterclockwise directions in said extended position, said means restraining rotational movement of said pawl means includes a single pawl stop flange member extending in a plane parallel to the plane defined by said pawl arm and pawl tab portions when said pawl means is in said extended position, a hub portion, an arm portion extending tangentially of said hub portion and terminating on one side thereof in said clamping flange means, and a tab portion extending coplanar with said arm portion and terminating on the side of said hub portion opposite said clamping flange means, whereby said pawl means travels linearly both into and out of clamping engagement with said wall surface adjacent said wall opening.

4,297,526

'FIRE RESISTANT ELECTRICAL CABLES

Ottmar Leuchs, Hannover-Bothfeld, and Georg Maltz, Burgdorf, both of Fed. Rep. of Germany, assignors to Kabel-und Metallwerke Gutehoffnungshuette A.G., Hanover, Fed. Rep. of Germany


Filed Feb. 7, 1980, Ser. No. 119,532

Claims priority, application Fed. Rep. of Germany, Feb. 26, 1979, 2907473

Int. Cl.³ H01B 7/20, 7/28

U.S. Cl. 174—102 R

5 Claims



1. An electrical cable comprising a core assembly including at least one insulated conductor, a hermetically closed, tubular metallic sheath concentrically positioned about said core assembly, and a filler material dispersed in and partially occupying the spaces between the inner surface of said metallic sheath and the outer surfaces of said core assembly throughout at least a major portion of the length of said electrical cable, the improvement comprising:

(i) said metallic sheath tightly engaging said core assembly successively along at least a major portion of the length of

said core assembly, thus structurally limiting the hollow or unoccupied spaces within the electrical cable; and

(ii) said filler material being comprised of a thermoplastic admixture which absorbs at least a portion of acids and gases resulting from a decomposition of the insulation of said at least one conductor, and expands in volume upon its temperature exceeding a predetermined limit;

whereby, upon the continued subjection of a segment of said metallic sheath to concentrated heat, at least a portion of the acids and gases resulting from insulation decomposition is absorbed from said filler material within said heated segment, and the volume of said filler material within said heated segment expands to provide substantially complete cross-sectional occupation of any hollow spaces within said heated segment, resulting in a structural blockage to the longitudinal flow of acids and gases from within said heated segment into adjacent segments of said electrical cable.

4,297,527

INPUT GAIN ADJUSTING APPARATUS AND METHOD


Jerry W. Pate, Houston, Tex., assignor to E-Systems, Inc., Dallas, Tex.

Filed May 1, 1979, Ser. No. 35,004

Int. Cl.³ H03G 3/30

U.S. Cl. 179—1 VC

12 Claims



1. A voice operated gain adjust apparatus for use in a voice processor that receives an analog input signal including voice signals and background noise, comprising:

means for converting the analog input signal into a digital input signal;

an amplifier having a variable gain for amplifying the analog input signal, said amplifier includes a plurality of different feedback loops and a switching circuit for connecting any of said feedback loops to the amplifier to determine the gain thereof; and

controller means including a central processing unit, a non-volatile memory for storing a program, and a volatile memory for use in executing the program, each of said memories being interconnected with said central processing unit, said controller means being responsive to the digital input signal and the stored program for detecting the presence and absence of voice signals in the analog input signal and for generating a control signal which is applied to said switching circuit for varying the gain of said amplifier according to the amplitude of the analog input signal occurring in selected time periods only when the presence of voice signals is detected.

4,297,528

TRAINING CIRCUIT FOR AUDIO SIGNAL RECOGNITION COMPUTER

Richard D. Beno, Cerritos, Calif., assignor to Interstate Electronics Corp., Anaheim, Calif.

Filed Sep. 10, 1979, Ser. No. 73,781

Int. Cl.³ G10L 1/00

U.S. Cl. 179—1 SB

16 Claims

1. Apparatus for signal pattern recognition, comprising:

means for storing a plurality of reference data patterns;

means for comparing a signal pattern with said reference data patterns for recognition; and

means for updating a selected one of said reference data patterns comprising:


means for inputting a training signal pattern;

means for comparing said training signal pattern with each said reference data pattern to generate a score signal for

each said reference data pattern indicative of the similarities therebetween;

means for selecting the reference data pattern with the highest score for similarity with said training signal pattern;

means for combining said selected reference data pattern with said training pattern to produce a new reference data pattern; and



means for replacing said reference data pattern with said new reference data pattern in said storing means if said score signal is above a predetermined level without affecting any other said reference data patterns regardless of the scores of said other reference data patterns in comparison with said training signal pattern.

4,297,529

MODULAR TELEPHONE JACK


Gerald F. Webb, Thorndale, Canada, assignor to Northern Telecom Limited, Montreal, Canada

Filed Oct. 29, 1979, Ser. No. 89,224

Int. Cl.³ H01R 13/40, 13/62

U.S. Cl. 179—1 PC

5 Claims



1. A modular telephone jack having two parts, a top part and a bottom part, said parts defining an aperture therebetween for reception of a modular plug, and a plurality of cantilever spring wire contact members extending from a front end of said top part downward and rearward into said aperture, said contact members being molded at a front end integrally with said top part of the jack.

4,297,530

ELECTRONICS PACKAGE

Bayard F. Kessler, Woodland Hills, Calif., assignor to Novation, Inc., Calif.

Filed Dec. 20, 1978, Ser. No. 971,538

Int. Cl.³ H04M 11/00

U.S. Cl. 179—2 C

13 Claims

1. A modem comprising:


an extruded plastic central body having first and second open ends and an approximately rectangular section defining inner and outer section surfaces, said inner section surface having at least two facing disposed slots formed

therein for receiving and supporting the side edges of at least one printed circuit board within said central body, said central body having a pair of openings on the top surface thereof,

at least one printed circuit board fitting within said two facingly disposed slots in central body,

a first and second muff, each fitting within one of said pair of openings on the top surface of said central body and being electrically coupled to said modem circuit board,

a first end cap having a portion thereof fitting within said first end of said central body for alignment therewith, said first end cap enclosing at least a substantial portion of said first end of said central body,



a second end cap having a portion thereof fitting within said second end of said central body for alignment therewith, said second end cap enclosing at least a substantial portion of said second end of said central body, at least one of said end caps having an opening for electrical connection to said printed circuit board therein, and

retaining means for retaining said first and second end caps on said first and second ends, respectively, of said central body.

4,297,531

CIRCUIT FOR SUPPRESSING NOISE INFLUENCES IN THE EVALUATION OF SIGNAL STATES ON TRANSMISSION LINES

Axel Dalhof, Puchheim, and Robert Lechner, Otterfing, both of Fed. Rep. of Germany, assignors to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany


Filed Oct. 10, 1979, Ser. No. 83,250

Claims priority, application Fed. Rep. of Germany, Nov. 24, 1978, 2850929

Int. Cl.³ H04M 3/22

U.S. Cl. 179-16 AA

4 Claims



1. A circuit arrangement for suppressing noise voltage components which are superposed on a DC voltage signal which is to be evaluated as a status signal on a two-wire transmission

line which is connectible to and supplied in symmetrical branches at feed points by a DC voltage supply in a subscriber line circuit of an exchange, comprising:

an impedance connected between a first feed point of the DC voltage supply and a connection point coupled to the two-wire line carrying a first DC voltage superposed with noise voltage components; a high-resistance shunt connected across the feed points and including a tap point;

a first differential amplifier including a first input connected to said tap point to receive a second DC voltage superposed with noise voltage components, a second input connected to a second feed point of the DC voltage supply to receive a third DC voltage which is not influenced by noise, and an output providing the noise voltage components;

first and second input means connecting said first and second inputs, respectively, to said tap and the DC voltage supply and operable to provide the third DC voltage equal to the second DC voltage;

a second differential amplifier including a first input connected to said output of said first differential amplifier for receiving the noise voltage components, a second input, and an output; and

a voltage follower circuit including an input connected to said connection point to receive the first DC voltage superposed with noise voltage components and an output connected to and feeding said second input of said second differential amplifier so that said second differential amplifier provides a fourth DC voltage proportional to the original supply voltage and representing the state of the subscriber line.

4,297,532

INTERFACING CIRCUIT STATUS DETECTION ARRANGEMENT IN A TELEPHONE EXCHANGE

Takeo Fukuda; Kazuhiko Hanawa; Kiyoshi Urui, and Michiko Haseyama, all of Yokohama, Japan, assignors to Tokyo Shibaura Denki Kabushiki Kaisha, Kawasaki, Japan


Filed Jun. 20, 1979, Ser. No. 50,228

Claims priority, application Japan, Jul. 11, 1978, 53-84203

Int. Cl.³ H04M 3/22

U.S. Cl. 179-18 AB

8 Claims



1. A telephone exchange comprising:

a switching network;

a plurality of interface circuits each having a transmit/receive path connected to the switching network;

a plurality of data generating circuits respectively connected to the interface circuits for detecting the states of the interface circuits and for generating state variation information when the state of at least one of these interface circuits is varied from a previous state; and

a control circuit for receiving as an interrupt signal the state variation information from the data generating circuits and for setting the switching network to a state corresponding to the state of that interface circuit whose state variation has been detected.

4,297,533

DETECTOR TO DETERMINE THE PRESENCE OF AN ELECTRICAL SIGNAL IN THE PRESENCE OF NOISE OF PREDETERMINED CHARACTERISTICS

Jean-Gabriel Gander, Rechterswil, and Ralph Aubert, Zug, both of Switzerland, assignors to LGZ Landis & Gyr Zug AG, Zug, Switzerland


Filed Jun. 7, 1979, Ser. No. 46,508

Claims priority, application Switzerland, Aug. 31, 1978, 9196/78

Int. Cl.³ H04M 1/50; H04B 1/06; H04K 5/20

U.S. Cl. 179-84 VF

16 Claims



1. A detector for determining the presence of an electrical signal in the form of a tone in the presence of noise, said electrical signal having at least two predetermined characteristics, comprising in combination:

signal transforming means for obtaining a plurality of independent estimates of each of said characteristics,

classification means connected to said signal transforming means for sorting said plurality of independent estimates into at least two classes, respectively, and

counting means for signaling the presence of said electrical signal when the number of said estimates within one of said classes exceeds a predetermined number.

4,297,534

PUSHBUTTON TELEPHONE SET DISABLING MEANS


Barry M. Epstein, 7523 Cliffbrook, Dallas, Tex. 75240, and Terry M. Gernstein, 6724 Melrose Dr., McLean, Va. 22101

Filed Jan. 3, 1980, Ser. No. 109,255

Int. Cl.³ H04M 1/66

U.S. Cl. 179-90 D

50 Claims



1. A device for preventing unauthorized use of a pushbutton telephone set comprising:

disabling means connected to the telephone set to be electrically interposed between the telephone set and a line connecting that telephone set to a call receiving means such as a central office, PBX, key system centrex, or the like, said disabling means including frequency signal altering means which alters at least one of said intercepted frequency signals in a manner such that the call receiving means is prevented from receiving a set of frequencies in

a form which is required to operate equipment at such call receiving means so that such equipment will not be operated by said at least one altered frequency signal and a call which includes said altered frequency signal will not be completed, said disabling means permitting the telephone set to receive signals incoming thereto; and

connecting means on said disabling means for selectively connecting said frequency signal altering means to the telephone set and disconnecting said frequency signal altering means from the telephone set at any time.

4,297,535

STEREO HEADSET

Gunter Hehemann, Kaiser-Wilhelm Strasse 3B, D-8130 Starnberg, Fed. Rep. of Germany


Filed Jul. 14, 1978, Ser. No. 924,760

Claims priority, application Fed. Rep. of Germany, Jul. 18, 1977, 2732425; Aug. 1, 1977, 2734624; Sep. 12, 1977, 2741049; Sep. 12, 1977, 2741004; Nov. 3, 1977, 2749234

Int. Cl.³ H04R 5/00

U.S. Cl. 179-156 R

10 Claims



1. A stereophonic headphone comprising a pair of earpieces, each having an electro-acoustic main transducer and a sound chamber, a first sound tube coupling each of said sound chambers and a pair of auxiliary electro-acoustic sound transducers each connected electrically in parallel to the main transducer of an associated one of said earpieces, the sound chambers of each earpiece being respectively coupled acoustically to the auxiliary transducer connected to the main transducer of the other earpiece by one of a pair of second sound tubes acting to delay the transmission of said sound for a period of time which corresponds to the rectilinear propagation of the sound in a deflection section of 15 to 25 cm.

4,297,536

SELF-ADJUSTING HYBRID NETWORK

Robert B. Buchner, Bussum, Netherlands, assignor to U.S. Philips Corporation, New York, N.Y.


Filed May 11, 1979, Ser. No. 38,377

Claims priority, application Netherlands, May 19, 1978, 7805416

Int. Cl.³ H04B 1/58

U.S. Cl. 179-170 D

6 Claims



1. A hybrid network for connecting a two-wire subscriber's line to a four-wire line comprising:

a pair of terminals connected to said hybrid network, a d.c. supply source, a two-wire subscriber's line connectible to said pair of terminals, first means for coupling said subscriber line to said four-wire line, second means for coupling said source to said terminals for supplying said subscriber line with d.c. current, an adjustable balancing network having control inputs and an impedance whose value varies in dependence on the direct current supplied to said control inputs, and a third means for coupling said control inputs to said terminals and said d.c. supply source such that the direct current applied to said control inputs is proportional to the direct current supplied by said source to said subscriber's line when said subscriber's line is connected to said terminals, whereby said impedance of said balancing circuit is adjusted to correspond to the impedance of said subscriber's line.

4,297,537


DYNAMIC LOUDSPEAKER

Burton A. Babb, 6618 Briarhaven, Dallas, Tex. 75240

Filed Jul. 16, 1979, Ser. No. 58,105

Int. Cl.³ H04R 7/26

U.S. Cl. 179—180



1. In a loudspeaker of the kind having a frame, a cylindrical center magnetic pole, an outer magnetic pole disposed around the center pole to form an annular flux gap therebetween, said outer pole and center pole being interconnected at their rear ends by a back pole plate, a speaker cone mounted on said frame in front of said poles for acoustically radiative reciprocation with respect thereto, said cone having an axially disposed dust cap thereon, a tubular voice coil mounted on the back of said cone and positioned in said flux gap, and an antifriction bearing member for said coil disposed in continuous sliding contact with said centerpole, the improvement comprising:

a grille positioned on said frame in front of said speaker cone; a first bumper formed of resilient material mounted on the back of said grille, said first bumper being positioned and proportioned to lie forwardly of the largest desired forward excursion of said dust cap, said largest desired forward excursion being insufficient to displace said bearing member from said center pole, and to resiliently and quietly stop forward excursions of said dust cap which are larger than said largest desired forward excursion, said first bumper thereby affecting only those forward excursions which are greater than desired; and

a second bumper formed of resilient material mounted on the forward end of said center pole, said second bumper being positioned and proportioned to lie rearwardly of the largest desired rearward excursion of said dust cap, said largest desired rearward excursion being insufficient to impact said bearing against said back pole plate, and to resiliently and quietly stop rearward excursions of said dust cap which are larger than said largest desired rearward excursion, said second bumper thereby affecting only those rearward excursions which are greater than desired.

4,297,538
RESONANT ELECTROACOUSTIC TRANSDUCER WITH INCREASED BAND WIDTH RESPONSE


Frank Massa, Hingham, Mass., assignor to The Stoneleigh Trust, Cohasset, Mass., Fred M. Dellorano, Jr. and Donald P. Massa, Trustees

Filed Jul. 23, 1979, Ser. No. 59,902

Int. Cl.³ G08B 3/10; H04R 1/28, 1/30

U.S. Cl. 179—180

11 Claims



1. In combination in an electroacoustic transducer including a peripherally-clamped vibratile diaphragm and electromechanical transducer means associated with said diaphragm for converting alternating electrical signals into mechanical vibrations, said peripherally-clamped diaphragm characterized in that its fundamental resonant frequency is greater than 1 kHz, and further characterized in that the clamped diameter of said diaphragm is less than one-half wavelength of the sound generated at said resonant frequency, said electroacoustic transducer characterized in that the band width of the frequency response characteristic in the vicinity of resonance is relatively narrow and is equivalent to a Q factor greater than 20, means for substantially increasing the band width of the response characteristic of said transducer such that the Q factor is reduced to a value less than 8, said means for increasing the band width includes means for damping the acoustic reactance of the peripherally-clamped vibratile diaphragm over a frequency range extending at least $\pm 10\%$ beyond the resonant frequency of said transducer, said damping means characterized in that the damping is not in the form of a mechanical resistance which adds viscosity loss to the vibrating diaphragm, but that said damping is in the form of increased acoustic radiation resistance added to the vibrating diaphragm by means of an acoustic coupler interposed between the radiating surface of said vibratile diaphragm and the medium into which the acoustic energy is radiated.

4,297,539

TELEPHONE SECURITY ATTACHMENT


Thomas L. Fairbanks, 2443 34th St., Santa Monica, Calif. 90405

Filed Feb. 27, 1980, Ser. No. 125,033

Int. Cl.³ H04M 1/66

U.S. Cl. 179—189 D

3 Claims



1. A security attachment for restricting the use of a telephone comprised of a base and a liftable hand-set, the base having a hand-set cradle and a dial extending forwardly from the cradle to the front end of the base and comprised of a plurality of push buttons representing the digits "0" through

"9"; the attachment including integral planar body portions overlying the cradle and dial and front end of the base, the overlying front portion having an extension with hooked engagement beneath a bottom of the base, the body portion overlying the cradle being engageable with the cradle of the base, and the body portion overlying the dial being held in spaced relation from the dial on the base and having at least one finger aperture therethrough for access to a push button, there being lock means carried by the cradle portion of the attachment to releasably hook with the cradle of the base in opposition to said hooked engagement of the front portion.

4,297,541

GANGED PUSH BUTTON SWITCH HAVING MEANS PREVENTING SIMULTANEOUS ACTUATION OF TWO PUSH BUTTONS

Akira Niinuma, Furukawa, Japan, assignor to Alps Electric Co., Ltd., Tokyo, Japan


Filed Oct. 15, 1979, Ser. No. 84,533

Claims priority, application Japan, Oct. 20, 1978, 53-144226[U]

Int. Cl.³ H01H 9/20

U.S. Cl. 200—5 E

4 Claims



1. A ganged push button switch assembly comprising: a plurality of modular switches each including a push button formed with a respective cam surface, and a case formed with slots at positions adjoining said cam surface; coupling means for coupling said plurality of modular switches into an integral switch block; and a plate member slidably held in the slots of the respective modular switches so as to be between the two adjacent modular switches in said switch block, said plate member being formed at its ends with respective cam portions cooperating with the cam surface of said modular switches and being also formed at its central part with engaging portions having an elasticity so as to permit said plate member to be attached to and detached from said slots by deforming said engaging portions.

4,297,540

INTERLOCKING GANG PUSH-BUTTON SWITCH

Kotaro Tsutsui, Furukawa, and Ryoji Kinugawa, Suita, both of Japan, assignors to Alps Electric Co., Ltd., Tokyo, Japan



Filed Jun. 1, 1978, Ser. No. 911,388

Claims priority, application Japan, Jun. 8, 1977, 52-74611[U]

Int. Cl.³ H01H 9/20

U.S. Cl. 200—5 B

7 Claims



1. In a switch assembly comprising a first and a second block of identical push button switches, each said switch including a plurality of fixed terminals arranged along its length and having an operation rod movable inwardly to a latched position electrically contacting a selected one of said terminals, said blocks being arranged generally parallel in back to back relation with their fixed terminals extending oppositely, and means for releasing any switch from its latched position when any other switch is actuated to its latched position, the improvement comprising said releasing means including identical first and second cam portions formed on respective sides of the operation rods of said switches, and a common latch member having first cam parts on one side thereof for engaging said first cam portions and second cam parts on the opposing side thereof engaging said second cam portions.

4,297,542

FOLDED CIRCUIT SWITCH APPARATUS HAVING MULTIPLE CONTACTS

Anthony G. Shumway, 734 W. 6th Ave., Mesa, Ariz. 85202

Filed Dec. 19, 1979, Ser. No. 105,261



Int. Cl.³ H01H 19/70, 25/04

U.S. Cl. 200—6 A

6 Claims

1. Switch apparatus for providing a plurality of output signals, comprising, in combination: a first flexible insulative layer; first conductive means disposed on the first flexible insulative layer including a plurality of arcuate conductive segments disposed symmetrically on the first flexible insulative layer; a second insulative layer; a second conductive means disposed on the second insulative layer and including a circular conductive segment disposed adjacent the plurality of arcuate conductive segments of the first conductive means; a third insulative layer disposed between the first and second insulative layers; opening means in the third insulative layer to allow electrical contact selectively between one conductive segment or with two adjacent conductive segments, of the first conductive means and the circular conductive segment of the second conductive means; and

switch actuation means to provide flexing of the first flexible insulative layer to cause electrical contact between the



first and second conductive means through the opening means.


4,297,543

SAFETY DEVICE FOR CONTAINER FILLER SYSTEMS
Barry Shackcloth, Harpenden, England, assignor to Total Oil Great Britain Limited, London, England
Continuation of Ser. No. 844,041, Oct. 20, 1977, abandoned.
This application Mar. 19, 1979, Ser. No. 21,807
Claims priority, application United Kingdom, Oct. 22, 1976, 43956/76

Int. Cl.³ H01H 35/18

U.S. Cl. 200—18

7 Claims



1. The combination of a safety switch assembly and a container for use with equipment for filling said container with a liquid, the combination comprising:

- a container having a protruding peripheral wall rim defining a filler opening,
- a switch assembly including a body portion having a first electrical switch and also having an elongated channel therein detachably receiving at least a segment of said peripheral wall rim of said container,
- said first electrical switch having an actuator housed in said elongated body portion channel and operative to respond to the insertion of the peripheral wall rim segment of said filler opening into said elongated channel of said body portion whereby said first switch is actuated when said body portion is mounted on said filler opening

peripheral wall rim to allow said liquid to enter said container, and

- a sensing portion attached to said body portion and housing a second switch electrically connected with said first switch and operative to respond to the level of the liquid content in said container to be filled whereby said second switch is actuated and delivery of said liquid to said container is stopped when a predetermined liquid level in said container is reached.


4,297,544

PNEUMATICALLY OPERATING DELAY SWITCHES
Wolfgang Priesemuth, Postkamp 13, D-2210 Itzehoe-Nordsee, Fed. Rep. of Germany
Filed Dec. 26, 1978, Ser. No. 973,132
Claims priority, application Fed. Rep. of Germany, Dec. 24, 1977, 2758082

Int. Cl.³ H01H 7/03

U.S. Cl. 200—34

5 Claims



1. A pneumatically operating delay switch arrangement including a pneumatic piston cylinder means provided with an insulating cylinder bottom and an inner wall having at least partially conducting portion and having a cylinder compartment in communication with outside air through a check valve and a throttle bore connected in parallel therewith and having a piston operatively connected with switch contacts comprising slide contacts as the switch contacts formed by a bracket spring rigidly connected with said piston and engaging the inner wall of the pneumatic piston-cylinder means and formed by said at least partially conducting portion of said inner wall, a first compression spring means as well as a second compression spring means located in the cylinder compartment, said second compression spring means being weaker than the first compression spring means, and an outer connection including a contact lug and a neck portion of a metallic abutment passing through the insulating cylinder bottom along with said second compression spring means having electrically conductive joiner to said bracket spring.

4,297,545

SWITCHING MEANS FOR A TIMING MECHANISM
Ronald G. Darner, Bargersville, Ind., assignor to Emhart Industries, Inc., Indianapolis, Ind.

Filed Jan. 16, 1980, Ser. No. 112,604

Int. Cl.³ H01H 7/00


U.S. Cl. 200—38 R

5 Claims

1. In an electrical switching means wherein cooperating electrical contacts, carried by a fixed contact blade and a pair of movable contact blades, are sequentially opened and closed through movement of said pair of movable contact blades; a means providing individual sequential movement of said pair of movable contact blades with respect to said fixed blade comprising:

- a drive means,
- cam means actuated by said drive means and a lever

engaging said cam means and a first blade of said pair of movable contact blades,
(c) a lost motion linkage means carried by said pair of movable contact blades and linking them together, whereby initial movement of said lever by said cam means



causes movement of said first blade and continued movement thereof due to said lost motion linkage means causes movement of both of said pair of contact blades so as to selectively engage or disengage the electrical contacts carried by the movable blades and the fixed blade from each other.

4,297,546

ACTUATING MEANS FOR SWITCH OPERATION IN TIMING APPARATUS


Claude V. Koch, Two Rivers, Wis., assignor to AMF Incorporated, White Plains, N.Y.

Filed Apr. 14, 1980, Ser. No. 140,357

Int. Cl.³ H01H 43/10

U.S. Cl. 200—38 R

11 Claims



1. Timing apparatus for controlling the energization of an electrical plug receptacle into which the cord of a lamp or appliance, or the like, may be plugged, comprising
a case having front and back walls,
an electrical plug receptacle adapted to receive the prongs of an electrical plug,
electrical switch means within said case having only one movable contact blade that may be selectively moved to open and close contacts of the switch means,
said contact blade normally spring biasing said contacts to their closed positions,
means for connecting said switch means to a source of electrical power,
electrical conductor means connecting said switch means to said plug receptacle for energizing the plug receptacle when the switch means is closed and for deenergizing the plug receptacle when the switch means is open,
a time dial mounted on said case for rotation relative to said case,
an electrical motor mounted in said case,
means for energizing said motor,
gear train means coupling said motor to said time dial to

rotate said time dial as a function to the rotation of said motor,

a plurality of time setting pins slidably mounted on the periphery of the time dial, each pin being slidable between an inner and an outer position, said inner and outer positions being along a path that is parallel to the axis of rotation of the time dial,

said setting pins having peripheral edges that comprise the outermost periphery of the time dial,

a switch actuator pivotally mounted for rotation about an axis that is parallel to, and fixed with respect to, the axis of rotation of said time dial,

said switch actuator having a free end that contacts said peripheral edges of the setting pins at an actuation position when the setting pins are in their inner positions but being out of contact with the peripheral edges of the pins when the setting pins are in their outer positions,

said free end of the switch actuator having such an extent relative to the circumference of the time dial with pins thereon that adjacent pins in their inner positions on the dial will continuously support said free end of the actuator as the adjacent pins pass the actuation position but a setting pin in its outer position that is between two pins in their inner positions will allow the actuator to pivot below the peripheral edges of the two inner pins and into the space therebetween,

push rod means for engaging said movable contact blade of the switch means,

said switch actuator urging said push rod means into engagement with said contact blade to move the blade to open the contacts of the switch means only when the free end of the switch actuator is in contact with the peripheral edge of a setting pin that is in its inner position.


4,297,547

MINIATURE TIMING MECHANISM
Benjamin F. Chestnut, Indianapolis, Ind., assignor to Emhart Industries, Inc., Indianapolis, Ind.
Continuation of Ser. No. 969,349, Dec. 14, 1978, abandoned.
This application May 5, 1980, Ser. No. 146,616

Int. Cl.³ H01H 43/10

U.S. Cl. 200—38 R

4 Claims



1. A timing mechanism comprising:

- a motor and a gear train connected to said motor to be driven thereby,
- a first housing enclosing said gear train,
- a cup shaped second housing carried by said first housing at an open end thereof,
- an electrically insulative member closing said open end,
- a bearing surface provided in said first housing and extending through an opening in said electrically insulative member,
- a gear of said gear train carried within said first housing and having a unitarily constructed hub portion extending through said opening in said insulative member into said cup shaped member and at least one cam lobe unitarily constructed with said hub portion,
- electrical switch means carried in said cup shaped member and responsive to said cam lobe, and

(h) a circular cover carried by said cup shaped member and partially surrounding said cam lobe and in line with said opening and an outer surface of said bearing surface.

4,297,548

VITAL INCIDENTAL MOVEMENT MONITORING ARRANGEMENT


Donald R. Little, Greensburg, Pa., assignor to American Standard Inc., Swissvale, Pa.

Filed Dec. 19, 1979, Ser. No. 105,354

Int. Cl.³ H01H 35/00

U.S. Cl. 200—61.08

10 Claims



1. A vital movement monitor comprising, a support member attached to a housing of a speed measuring device, a carrier member including a sensor adjustably joined to said support member, and an electrical conductor passing through apertures formed in said support and carrier members, said electrical conductor forming part of an electrical circuit which is disrupted when incidental relative rotational movement occurs between said support and carrier members.

4,297,549

DIRECTION INDICATOR SWITCH

Steven J. Tregurtha, Near Ayrington, and Edward Cryer, Burnley, both of England, assignors to Lucas Industries Limited, Birmingham, England


Filed Sep. 7, 1979, Ser. No. 73,557

Claims priority, application United Kingdom, Sep. 12, 1978, 36233/78

Int. Cl.³ H01H 3/16

U.S. Cl. 200—61.27

5 Claims



1. A direction indicator switch and releasable latch means combination including a body, a member carried by the body and movable manually relative thereto from a rest position to either of first and second operative positions on opposite sides respectively of the rest position, a striker collar rotatable in use relative to said body with a steering shaft of a vehicle utilizing

the switch to effect return movement of said member from either of said operative positions to said rest position, and said releasable latch means movably supported by said body whereby the striker collar is retained in a predetermined angular position relative to the body during assembly of the switch in the vehicle, said latch means being released after assembly of the switch in the vehicle to permit the collar to rotate with the steering shaft of the vehicle relative to the body.

4,297,550

METHOD AND CONSTRUCTION FOR VEHICLE BRAKE PEDAL AND SWITCH ASSEMBLY


John D. Leighton, Bloomfield Hills, Mich., assignor to Betty Leighton, Bloomfield Hills, Mich., a part interest

Filed Mar. 1, 1979, Ser. No. 16,434

Int. Cl.³ H01H 3/14

U.S. Cl. 200—61.89

31 Claims



1. In a method for assembly of an automotive brake pedal and switch, the steps of providing a pre-assembled module having a firewall mounting bracket member, a brake pedal lever member hinged thereto, resilient means urging said lever member rearwardly, and a switch carried by one of said members, adjusting said switch so that it will be actuated upon the desired movement of the brake pedal, said adjustment being made prior to mounting of the pre-assembled module upon said firewall, connecting said lever member to a brake system push rod member, mounting said module on a vehicle firewall, and connecting a lead wire to said switch, whereby forward movement of said lever member will actuate said switch.

4,297,551

ELECTRICAL TRANSFER SWITCH


Leroy B. Ronk, Nokomis, Ill., assignor to Ronk Electrical Industries, Inc., Nokomis, Ill.

Filed Mar. 31, 1980, Ser. No. 135,266

Int. Cl.³ H01H 5/08

U.S. Cl. 200—67 B

11 Claims



1. A transfer switch comprising:
a support;
first and second fixed contacts mounted on the support, the first contact being connected to a terminal adapted to be

connected to line power and the second contact being connected to a terminal adapted to be connected to a generator;

a rocker pivotable between first and second positions;

a contactor carried by the rocker, connected by a flexible conductor to a terminal mounted on the support, the contactor being movable with respect to the first and second contacts and being engageable with the first contact when the rocker is in its first position and being engageable with the second contact when the rocker is in its second position, whereby said terminal on the support is adapted to be connected to line power when the rocker is in its first position and to the generator when the rocker is in its second position; and

an actuator for moving the rocker between its first and second positions comprising a shaft rotatably mounted on the support and an overcentering spring, said shaft having a handle and a crank, said spring being secured at one end to the crank and at the other end to the rocker, the rocker being rotatably mounted on the shaft, the shaft being pivotable between first and second angular positions, the spring biasing the rocker to its first position when the shaft is in its first angular position and biasing the rocker to its second position when the shaft is in its second angular position, the spring applying a force to the rocker causing the rocker to snap from one of its positions to the other when the shaft is rotated from one of its angular positions to the other.

4,297,552

VACUUM SWITCH


Richard L. Lauritsen, Hoffman Estates, and Panagiotis K. Mandellos, Chicago, both of Ill., assignors to The Singer Company, Stamford, Conn.

Filed Jan. 30, 1980, Ser. No. 116,860

Int. Cl.³ H01H 35/34

U.S. Cl. 200—83 P

5 Claims



1. A vacuum switch having a housing enclosing a chamber divided by a diaphragm into a vacuum chamber and a switch chamber, a conduit leading from the vacuum chamber for connection to a variable vacuum source, a switch in the switch chamber and having a switch blade provided with a contact moveable between a normally closed and normally open fixed contacts and having a tongue which is moved to cause movement of the blade with a snap action, an actuator connected to said diaphragm and to said tongue and extending through an aperture in the housing, characterized by,

a spring retainer fixed on the outboard end of the actuator, a reset spring bearing against and compressed between the retainer and the housing, said actuator having a shoulder thereon in the region of the actuator passing through the housing aperture, a tubular eyelet slidably mounted on the actuator between said shoulder and the outboard end of the actuator and having a flange engageable with the shoulder and extending beyond the aperture so as to be engageable with the outside of the housing,

a trip spring bearing against and compressed between said flange and said retainer, said trip spring being effective to exert a force on the actuator via the retainer when said flange is in engagement with the housing and being ineffective to exert such a force when the flange is in engagement with said shoulder.

4,297,553

ENCLOSED SWITCHING APPARATUS

Yoshihiro Kawaguchi, Kosuke Higuchi, both of Yokohama, and Yoshiro Kitajima, Nagano, all of Japan, assignors to Tokyo Shibaura Denki Kabushiki Kaisha, Kanagawa, Japan

Filed Feb. 14, 1979, Ser. No. 12,012

Claims priority, application Japan, Feb. 24, 1978, 53/19879

Int. Cl.³ H01H 33/14, 33/54

U.S. Cl. 200—145

6 Claims



1. An enclosed switching apparatus of the type having:
a tank including a main cylindrical portion filled with an insulating gas and provided, at a first end thereof, with a removable cover,
a circuit breaker provided in and concentrically with said main cylindrical portion of said tank and including a housing, a stationary contact provided at a first end of said circuit breaker adjacent to said first end of said tank, and a movable contact provided at a second end of said circuit breaker,

first and second contact pedestals respectively provided at said first and second ends of said circuit breaker, and a disconnecting switch including a stationary contact and a movable contact engageable with said stationary contact, said tank being provided with a lead-out portion extending perpendicularly to the axis of said main cylindrical portion, with the axis of said lead-out portion intersecting the axis of said main cylindrical portion, and disposed adjacent to one of said contact pedestals, and said disconnecting switch being at least partially disposed in said lead-out portion, with the axis of said disconnecting switch being substantially coincident with the axis of said lead-out portion,

said enclosed switching apparatus further comprising:
a disconnecting switch operating device mounted to said main cylindrical portion for operating said movable contact of said disconnecting switch;
a drive bar member mechanically coupling said movable contact to said operating device, said drive bar member extending through said one of said contact pedestals and crossing the axis of said main cylindrical portion of said tank, substantially along a line of extension of the axis of said disconnecting switch, and including a conductor portion electrically connected to said movable contact of said disconnecting switch,
a slide contact mounted on said one of said contact pedestals to slidably receive said conductor portion of said drive bar member,
a circuit breaker operating device provided at a second end of said tank opposite to said first end, and including an insulating member movable for operating said movable contact of said circuit breaker,
said movable contact of said circuit breaker being detachable from said insulating member of said circuit breaker operating device.

4,297,554

TIME DELAY SWITCH MECHANISM


William R. Rueth, Jr., Hazel Crest, Ill., assignor to G & W Electric Specialty Company, Blue Island, Ill.

Filed Jan. 24, 1980, Ser. No. 114,742

Int. Cl.³ H01H 7/03

U.S. Cl. 200—153 SC

16 Claims



1. In electrical switch apparatus including at least one pair of relatively movable switch contacts adapted for connection in an electrical circuit and operative between open and closed circuit conditions, switch transfer means operatively associated with at least one of said pair of contacts and operative between a first stored energy condition and a second condition enabling release of said stored energy so as to effect transfer of said switch contacts between said open and closed circuit conditions, and control means operatively associated with said switch transfer means and including a latching lever selectively operable between a latching position maintaining said switch transfer means in said first energy storing condition and a release position enabling release of said stored energy to cause said transfer of said switch contacts between said open and closed circuit conditions; the combination therewith comprising mechanical time delay means including linkage means operatively associated with said latch lever and having at least one toggle linkage movable between an armed condition operative to maintain said latch lever in its said latching position and a release condition releasing said latch lever from its said latching position, a mechanical time delay operatively associated with said toggle linkage and directly responsive to initiation of movement of said toggle linkage from its said armed condition toward its said released condition so as to effect a predetermined time delay between initial movement of said toggle linkage and complete actuation thereof so as to release said latch lever, and actuator means for initiating movement of said toggle linkage from its said armed to its said released condition.

4,297,555

MOVABLE CONTACT ARM ASSEMBLY

Michinobu Iwai, and Akira Tanimoto, both of Mieken, Japan, assignors to Tokyo Shibaura Denki Kabushiki Kaisha, Kawasaki, Japan

Filed May 14, 1980, Ser. No. 149,753

Claims priority, application Japan, May 14, 1979, 54-063001[U]


Int. Cl.³ H01H 1/22

U.S. Cl. 200—153 G

6 Claims

1. An electric switching device including at least one movable contact and means for moving said movable contact between the open and closed circuit positions comprising:
a movable contact arm having a pair of spaced wall portions including aligned holes therein, one end of said movable contact arm being provided with a hole;
an elongated contact member located between said wall portions of said contact arm;
a supporting member having at least one first generally L-shaped engaging member at one end thereof and including a first portion projecting from said supporting member and a second portion angled with respect to said first

portion, said second portion engaged with said hole at one end of said movable contact arm and at least one engaging member at the other end thereof, said supporting member being mounted on said elongated contact member and being positioned between said elongated contact member and said movable contact arm; and



a pivot pin passing through said aligned holes in said wall portions of said movable contact arm, whereby said at least one engaging member at the other end of said supporting member is engaged with said pivot pin.

4,297,556

PUSHBUTTON OPERATOR


Glenn R. Taylor, 108 Duncan Cir., Beaver, Pa. 15009

Continuation of Ser. No. 13,664, Feb. 21, 1979, abandoned. This application Aug. 25, 1980, Ser. No. 180,629

Int. Cl.³ H01H 3/12

U.S. Cl. 200—330

2 Claims



1. A pushbutton operator for use with an electrical contact block having a stroker for actuating the block comprising:

- A. a base portion and a hollow cylindrical extension made of insulating thermoplastic material having external threads on an end opposite the base portion;
- B. a cap connected to a stem and disposed in the extension, the cap including an annular shoulder on its outside wall;
- C. a base plate connected to the stem and located within the base portion;
- D. means on the base portion for connection to the contact block; and
- E. a clamp ring threaded to the extension to retain the cap, stem and plate in the extension and base portion of the operator, the clamp ring including an internally threaded bore having a pair of annular lips, the first lip comprising a limit for threading the clamp ring to the extension by the abutment of the first lip with the top of the extension and the second lip being of a smaller diameter than the first lip but larger than the annular shoulder on the cap to retain the cap within the extension

whereby when the operator is connected to a contact block the stroker abuts the plate to load the operator and depression of the cap moves the plate against the stroker to actuate the contact block.

4,297,557

MICROWAVE OVEN TEMPERATURE INDICATOR AND CONTROL MEANS


Hugh J. Tyler, Santa Ana, and William H. Conway, Hacienda Heights, both of Calif., assignors to Robertshaw Controls Company, Richmond, Va.

Filed May 3, 1976, Ser. No. 682,198

Int. Cl.³ H05B 6/68

U.S. Cl. 219—10.55 R

6 Claims



1. The combination of a microwave oven and telemetric temperature probe therefor which comprises:

- (a) a microwave oven housing having internal walls defining and providing microwave shielding about an oven cavity;
- (b) a telemetric temperature probe including:
(b1) microwave antenna means and power supply circuit means in circuit therewith to generate a power supply from received microwave radiation;
- (b2) temperature responsive oscillator circuit mean driven by said power supply means to generate an oscillatory signal temperature modulated frequency and of a frequency distinct from said microwave frequency;
- (b3) electromagnetic wave transmission means to broadcast said oscillatory signal; and
- (b4) a probe housing having shielding means surrounding said power supply circuit means, oscillator circuit means and wave transmission means and of selective permeability to limit transmission of microwave energy while permitting transmission of said broadcast oscillatory signal;
- (c) signal receiver means mounted in said oven to receive said broadcast oscillatory signal; and
- (d) shielding means, of selective permeability to limit transmission of microwave energy while permitting transmission of said broadcast oscillatory signal, in said oven and surrounding said signal receiver means.

4,297,558

COMPOSITE COOKING DEVICE

Minoru Inayama, Komaki, and Yukio Furukawa, Konan, both of Japan, assignors to Rinnai Kabushiki Kaisha, Nagoya, Japan


Filed Apr. 25, 1980, Ser. No. 143,873

Claims priority, application Japan, May 1, 1979, 54-57047

Int. Cl.³ H05B 6/64

U.S. Cl. 219—10.55 R

2 Claims



1. A composite cooking device in which the main body of a

box-type cooking device is provided with a heating chamber, a heat source, a magnetron, and a cooling fan for sending air into a cooling duct having the magnetron interposed therein, further in which there is formed, between the cooking device main body and the heating chamber, a one-sided chamber with a front operation panel and an upper space which extends from the space chamber and is in communication with the atmosphere through an exhaust opening made in the upper portion of the main body, yet further in which a control means and a high-voltage element, such as a transformer, is contained in the space chamber in which the improvement comprises:

- (a) said space chamber having its interior divided by at least one partition wall, such division forming (i) a front chamber adapted for containment of said control means and (ii) a rear chamber for containment of said high voltage element; and
- (b) said cooling fan in communication at its intake side with the interior of said rear chamber, wherein the forward end of said cooling duct is in open communication with the exhaust opening of the main body.

4,297,559

APPARATUS FOR CONTROLLED PERFORATION OF MOVING WEBS WITH FIXED FOCUS LASER BEAM


Hobart A. Whitman, III, Asheville, N.C., assignor to Olin Corporation, Pisgah Forest, N.C.

Filed May 10, 1979, Ser. No. 37,727

Int. Cl.³ B23K 26/02; H05B 3/60

U.S. Cl. 219—121 LB

13 Claims



7. A control system for a laser beam perforating apparatus, comprising:

- a porosity feedback arrangement producing an error signal representative of the difference between actual web porosity as measured and desired web porosity as preset, said feedback arrangement including porosity preset means for producing a preset signal corresponding to a predetermined web porosity, porosity sensing means for producing a porosity signal corresponding to actual web porosity after perforation, and a comparator circuit connected to said preset and sensing means for producing the error signal as a function of the difference between said preset signal and said porosity signal;
- velocity sensing means for producing a sensed velocity signal corresponding to actual web velocity; and
- an electronic control circuit connected to said comparator circuit of said porosity feedback arrangement and to said velocity sensing means for producing a continuous pulse train responsive both to said sensed velocity signal and to said error signal and for providing a replica of said pulse train to said fixed focus laser beam perforating apparatus, the repetition rate of said pulse train varying directly in response to the sensed velocity signal and the duration of each pulse in said pulse train varying in response to the error signal, whereby a constant number of elongated perforations per unit length are produced, with the length

of the perforations dependent upon the porosity feedback error signal.

13. In a method for controllably perforating a moving web by a pulsed laser beam, the improvements comprising:

- focusing the pulsed laser beam at a single plane coincident with the surface of said moving web;
- pulsing the laser beam at a repetition rate corresponding to the lineal velocity of the moving web;
- pulsing the laser beam with an individual pulse duration corresponding to the difference between an actual web porosity signal and a preset signal representing desired web porosity; and
- thereby controllably perforating said web by a serially distributed perforation pattern having a desired ratio of perforated to non-perforated area.

4,297,560

PROCESS AND APPARATUS FOR TESTING ARC STUD WELDING GUNS


Hermann Netzsch, Gruening, Fed. Rep. of Germany, assignor to USM Corporation, Farmington, Conn.

Filed Feb. 26, 1979, Ser. No. 14,802

Int. Cl.³ B23K 9/20

U.S. Cl. 219—130.01

7 Claims



1. A test process for drawn arc stud welding guns comprising the steps of:

- generating an electric starting signal which activates at least one electric solenoid associated with a holding means for a clamped-in welding stud, said generating step resulting from a switching operation occurring at the beginning of a welding operation,
- deriving an electric cut-out signal from the short circuiting caused by the impact of the welding stud on its counter-electrodes, and
- measuring the period of time between the electric starting signal and the electric cut-out signal.

4,297,561

SEMI-AUTOMATIC WELDING GUN

Raymond L. Townsend, Jack R. Kester, and Kenneth A. Young, all of Wichita, Kans., assignors to Tweco Products, Inc., Wichita, Kans.

Filed Apr. 23, 1979, Ser. No. 32,350

Int. Cl.³ B23K 9/32

U.S. Cl. 219—137.63


5 Claims

1. A welding gun apparatus to supply welding wire, electrical power and shielding gas to a working area, comprising:

- a supply adapted assembly connected to a welding wire and gas feed unit having shielding gas, welding wire, electrical power and a control circuit;
- a quick connector assembly releasably connected to said supply adapter assembly to receive the shielding gas,

welding wire, electrical power, and a control circuit therefrom;

- a cable assembly having one end connected to said quick connector assembly to convey the shielding gas, welding wire, electrical power, and the control circuit within individual chambers;
- a welding gun assembly connected to the outer end of said cable assembly having control means connected to said control circuit selectively operable to semi-automatically feed the welding wire in conjunction with the electrical power and shielding gas to the working area;
- said welding gun assembly including a handle assembly connected to a conductor and supply tube assembly;
- said handle assembly having a gripper housing enclosing a cable connector assembly having a cable connector threaded on each of two end portions, and an actuator switch assembly;
- said quick connector assembly having a cable connector block to receive one end of a power supply conductor of said cable assembly and said conductor and supply tube therein, a separator member, and setscrews operable on



said power supply conductor and separator member to clamp said power supply conductor and said conductor and supply tube to said connector block for electrical continuity;

- h) said connector block having an elongated slot there-through, and said separator member having upper and lower arcuate surfaces which cooperate with said setscrews and power supply conductor and said conductor and supply tube to firmly clamp said power supply conductor and said conductor supply tube therein for electrical continuity through said conductor and supply tube; and
- i) said cable connector assembly having a cable connector nut threadably engaging one of said two ends of said cable connector to secure thereto said power supply conductors of said cable assembly, said conductor and supply tube assembly including a removably, adjustable tube assembly connected to a nozzle assembly, said tube assembly having a conductor tube retaining nut engaging the other of said two ends of said cable connector in order to remove the tube assembly or to adjust the same with respect to said gun assembly.

4,297,562

HEAT ROLLER TYPE FIXING APPARATUS

Nin-ichi Kamogawa, Tokyo, and Takashi Ito, Hachioji, both of Japan, assignors to Konishiroku Photo Industry Co., Ltd., Tokyo, Japan

Filed Dec. 10, 1979, Ser. No. 101,910

Claims priority, application Japan, Dec. 15, 1978, 53-156161



Int. Cl.³ H05B 1/02

U.S. Cl. 219—216

3 Claims

1. In a heat roller type fixing apparatus having a heat roller with an axial center and two axial ends and accommodating a heating element arranged within said heat roller and adapted for fixing a toner image to a copying paper, a temperature sensing element spaced apart from said heat roller and for sensing the temperature of the heat roller surface and a control circuit adapted to cooperate with the temperature sensing element in controlling the heat roller surface temperature, an

improvement being that said heating element is an infrared ray heater having a temperature distribution property so arranged that the highest temperature is obtained between said axial center and both said axial ends when said heating element is energized, whereby said roller can suppress the overshoot of



roller surface temperature, said heating element providing a predetermined, nonuniform ray density along the axial direction of said roller whereby the energy emitted by said heating element varies axially along said roller, said temperature sensing element being positioned adjacent one of said points of highest temperature.

4,297,563

ELECTRIC STEAM GENERATING UNIT


Clyde F. Berry, R.F.D. 7, Box 169 C, Manchester, N.H. 03104

Filed Mar. 26, 1980, Ser. No. 134,277

Int. Cl.³ F22B 1/28; H05B 3/82

U.S. Cl. 219—275

4 Claims



1. A steam generating unit comprising a housing having an upper end and a lower end,

- a first elongated tubular immersion type electric heating element within said housing and separated therefrom along its length to provide a cylindrical space,
- said first element at its upper end being in fluid tight engage-

ment with said housing to close the upper end of said space,

a second elongated cylindrical rod-shaped immersion type electric heating element within and coaxial with said first element,

the dimensions of said elements providing therebetween a long generally cylindrical second space of which the inner surface of said first element and the outer surface of said second element comprise the walls of said second space, said second space being of such small volume that water therein when subjected to the heat of both elements will turn quickly to steam,

the upper end of said second space being open to allow escape of steam from said space,

a discharge port at the upper end of said housing to receive steam generated in said space, and

a water inlet port into said housing and a passage therefrom to the lower end of said first and second spaces whereby water can be fed to said second space as fast as the water in said second space is being converted to steam and water may be maintained in said first space.

4,297,564

HAIR DRYER


Robert R. Bartolac, 560 Calle La Roda, Camarillo, Calif. 93010

Filed Nov. 29, 1978, Ser. No. 964,721

Int. Cl.³ A45D 20/12

U.S. Cl. 219—367

4 Claims



1. In combination with a hand held, portable hair dryer, said hair dryer having a housing, a motor operated fan mounted within said housing capable of moving air, said housing including a graspable handle, said graspable handle being readily capable of being held within one hand of the operator and said housing to be easily reversibly positioned, said handle including electric switch means to operate said motor operated fan; a first air outlet formed within said housing, an air heating element located within said first air outlet, air moved by said fan to be conducted through said first air outlet and discharged into the ambient, said first air outlet to discharge air in a first direction, the improvement comprising:

- a second air outlet formed within said housing, said second air outlet also to receive air from said fan and conduct such into the ambient, the location of said second air outlet being spaced from said first air outlet, said second air outlet to discharge air in a second direction substantially opposite to said first direction, said second air outlet being void of an air heating device so as to discharge only cool air; and

means to close off said second air outlet, said means being manually movable between a closed position and an open position, said closed position not permitting conducting of air through said second air outlet and permitting the total

volume of air moved by said motor operated fan to be discharged through said first air outlet, said open position permitting conducting of air through said second air outlet resulting in the dividing of the airflow between said first air outlet and said second air outlet.

4,297,565

HEATED WINDOW STRUCTURE WITH AN ELECTRICAL CONNECTOR ASSEMBLY

David Parr, Aberystwyth, England, assignor to David Parr & Associates Limited, GB2


Filed Oct. 3, 1979, Ser. No. 81,388

Claims priority, application United Kingdom, Oct. 5, 1978, 39524/78; Oct. 5, 1978, 39525/78

Int. Cl.³ F27B 3/06

U.S. Cl. 219—522

10 Claims



1. A window heater comprising: a plurality of heating elements for adhesive attachment to a transparent window member; an electrical connector assembly for one end of each of said heating elements, said electrical connector assembly including an elongated resilient synthetic resin channel member for attachment to said window, said channel member having therein a longitudinally extending channel of re-entrant cross-section, and an elongated electrically conductive part arranged to be received as a snap fit in said channel of said channel member so that said one end of each of said heating elements is trapped between said electrically conductive part and the wall of said channel in electrical connection with said electrically conductive part, said channel member including a surface which supports said electrically conductive part within said channel in a position spaced from the base of said channel in a direction towards the open face of said channel.

4,297,566

PUNCH FRAME FOR DATA REGISTERING DEVICE


John E. Ahmann, 1400 Duhig Rd., Napa, Calif. 94558

Filed Mar. 12, 1980, Ser. No. 129,585

Int. Cl.³ G07C 13/00

U.S. Cl. 235—50 R

15 Claims



1. In a data registering device for use with a machine-processable record punch card and including a punch card frame supporting resilient strips for receiving punched-out chad pieces pushed between the strips by a hand-held stylus, and further including a lower card guide attached at a head end of the punch card frame, an upper card guide connected to the lower card guide, said card guides being adapted to receive the punch card between them, and a stylus-guiding template slid-

ably positioned over the resilient strips for receiving in registry the punch card immediately below, the improvement comprising removable press-fit attachment means connecting the lower card guide with the punch card frame, for permitting removal of the lower card guide from the punch card frame and replacement of the resilient strips when required.

4,297,567

APPARATUS FOR RECEIVING STORING AND OUTPUTTING DIGITAL SIGNAL SEQUENCES

Karl H. Herzner, Hamburg, Fed. Rep. of Germany, assignor to U.S. Philips Corporation, New York, N.Y.


Filed Jul. 20, 1979, Ser. No. 59,919

Claims priority, application Fed. Rep. of Germany, Aug. 7, 1978, 2834509

Int. Cl.³ H03K 21/34

U.S. Cl. 235—92 PB

6 Claims



1. Apparatus for receiving, storing and outputting digital signal sequences, said apparatus comprising: a serial first-in-first-out storage means, having a digital signal input and an input clock terminal for storing a digital signal received under control of an input clock signal, a digital signal output and an output clock terminal for outputting and erasing a digital signal stored under control of an output clock signal, retrocoupling means having a first position for interconnecting said digital signal output to said digital signal input and a second position for receiving a digital signal from an external terminal; a control means having a primary clock input, a primary clock output coupled to said input clock and output clock terminals, first and second inhibit lines for selectively inhibiting said input clock terminal and output clock terminal, respectively, a further control output for controlling the position of said retrocoupling means, a first data input connected to said digital signal output and a second data input for receiving a further digital signal to be compared to the signal on said first data input in a first comparing means linked thereto; said control means having furthermore a control signal input for receiving mode control signals, said mode control signals comprising: a first signal for controlling a storing mode by driving said retrocoupling means to said second position while furthermore driving said input clock terminal but inhibiting said output clock terminal; a second signal for controlling an erasing mode by driving said output clock terminal but inhibiting presentation of a digital signal at said digital signal input; a third signal for controlling a modifying mode regarding an individual digital signal as stored in said storage means by driving said retrocoupling means to said second position while furthermore cooperatively driving said input clock terminal and said output clock terminal; a fourth signal for controlling an outputting mode thereby outputting a sequence of digital signals as stored in said storage means by driving said retrocoupling means to said first position

while furthermore cooperatively driving said input clock terminal and said output clock terminal; a fifth signal for controlling a first addressing mode thereby content-addressing said storage means by activating said first comparing means for generating, upon equality detected therein, a first equality signal for co-controlling a further one of said control signals.

4,297,568

COOKING APPARATUS

Hisahi Okatsuka, Tokyo, Japan, assignor to Tokyo Shibaura Denki Kabushiki Kaisha, Kawasaki, Japan


Filed May 10, 1979, Ser. No. 37,953

Claims priority, application Japan, May 16, 1978, 53-57937

Int. Cl.³ H01H 43/08; G06K 7/00, 13/04, 13/06

U.S. Cl. 235—435

6 Claims



1. A cooking apparatus for automatically cooking according to a program fed from a recording medium comprising: a housing having an interior space in which food is cooked, and a front panel; and means secured to said front panel for receiving and reading a program on a recording medium to control heating of food including a support, a pair of spaced apart rockable holding members mounted for pivotable movement between a first position holding the recording medium for reading and a second position releasing the recording medium for insertion and removal, a recording medium receiving member for receiving said medium when it is inserted between said holding members and said support and falls onto said receiving member and detecting means movable along said medium to read a cooking program from said medium.

4,297,569

MICROELECTRONIC MEMORY KEY WITH RECEPTACLE AND SYSTEMS THEREFOR


William P. Flies, Frontenac, Minn., assignor to Datakey, Inc., Minneapolis, Minn.

Filed Jun. 28, 1979, Ser. No. 52,773

Int. Cl.³ G06K 7/06, 19/00; E05B 47/06

U.S. Cl. 235—443

18 Claims



1. In combination: a key-like device having head and insert body portions, the insert body portion being adapted for insertion into a

receptacle and rotation therein to a "locked" position and including in cross section a major dimension with opposing upper and lower surfaces, a smaller minor dimension with opposing side surfaces, and a plurality of spaced transverse grooves formed on the major surfaces, and An electrical circuit element encapsulated within the key, the element including a plurality of electrical leads, each of which extend into one of the grooves and lie therein to form a plurality of electrical contacts; a receptacle defining a keyway for receiving the key insert body portion and the spaced electrical contacts carried thereby, the keyway including a plurality of correspondingly spaced electrical contacts, insertion guide means in the keyway for guiding the insert body portion during insertion with the contacts thereof angularly displaced from the keyway contacts, rotation guide means in the keyway for guiding the insert body portion during rotation to a "locked" position in the receptacle and bringing the insert and keyway contacts together in contacting pairs, and wherein each keyway contact comprises a conductive lead having a resilient bend portion positioned in the keyway for contacting a correspondingly spaced insert body contact upon rotation of the insert body to the "locked" position in the receptacle.

4,297,570

MAGNETIC STRIPE


George A. Kowalski, Deer Park, N.Y.; George Mayer, Hamden, Conn., and Murray Rosenbaum, New York, N.Y., assignors to Koller & Smith Co., Inc., Pelham, N.Y.

Filed Sep. 17, 1979, Ser. No. 76,158

Int. Cl.³ G06K 19/02; G11B 25/04; G06K 19/06

U.S. Cl. 235—493

9 Claims



1. A flexible sheet for use in forming a magnetic recording medium in the form of a stripe on a paper substrate, said sheet comprising a first layer of magnetic-particle-free thermoplastic material, said first thermoplastic layer being bondable to said paper substrate by application of elevated temperature and pressure to a local area thereof, a middle layer of magnetizable material permanently bonded to said first thermoplastic layer, said layer of magnetizable material consisting of a plurality of discrete magnetizable particles dispersed in a thermoplastic matrix, a second layer of magnetic-particle-free thermoplastic material, said second thermoplastic layer being permanently bonded to said middle layer of magnetizable material, said middle layer of magnetizable material being compatible with both said first and second layers of thermoplastic material, and a carrier web detachably bonded to said second layer of thermoplastic material, such that when elevated temperature and pressure is applied to a narrow rectilinear local area of said web while said first layer of thermoplastic material is disposed on said paper substrate, a magnetic stripe composed of superposed portions of said first, middle and second layers is detached in the shape of said area from said carrier web and the portions of said layers remaining on the web and transferred to said paper substrate, said second layer of thermoplastic material in said stripe forming an outer polish layer on the stripe

that reduces irregularities in the outer surface of the stripe due to the magnetic particles and minimizes abrasion of recording, erasing and reading heads, said thermoplastic matrix of the middle layer of said stripe becoming sufficiently plastic under the influence of elevated temperature and pressure during bonding to permit migration of magnetic particles towards said paper substrate during the application of elevated temperature and pressure.

7. A document having a paper substrate and encodable with permanent, machine-readable digital data, said document having an integral permanently attached recording magnetic stripe comprising three successive layers, said three layers comprising a first layer of magnetic-particle-free thermoplastic material permanently bonded to said paper substrate by application of elevated temperature and pressure, a middle layer of magnetizable material permanently bonded to said first layer of thermoplastic material and consisting of a plurality of discrete magnetizable particles dispersed in a thermoplastic matrix, and a second layer of magnetic-particle-free thermoplastic material, said second layer of thermoplastic material being permanently bonded to said layer of magnetizable material and forming an outer polish layer on the stripe that reduces irregularities in the outer surface of the stripe due to the magnetic particles and minimizes abrasion of recording, erasing and reading heads, said thermoplastic matrix of said middle layer having become sufficiently plastic under the influence of elevated temperature and pressure during bonding so as to permit migration of magnetic particles towards said paper substrate during the application of elevated temperature and pressure.

4,297,571

FOCUS DETECTING DEVICE

Ken Utagawa, Yokohama; Kunihi Hoshino; Hiroshi Shirasu, both of Kawasaki, and Akira Ogasawara, Yokohama, all of Japan, assignors to Nippon Kogaku K.K., Tokyo, Japan


Filed Jan. 3, 1980, Ser. No. 109,282

Claims priority, application Japan, Jan. 20, 1979, 54-5269

Int. Cl.³ G01J 1/20

U.S. Cl. 250—201

4 Claims



1. A focus detecting device having first and second photoelectric element arrays each including a plurality of photoelectric elements disposed so as to mutually correspond in position, and optical means for forming a first image and a second image of an object on said first and second photoelectric element arrays, respectively, so that when an objective lens is in focused position with respect to the object, the first image and the second image are positioned on said mutually corresponding photoelectric elements of said first and second photoelectric element arrays, respectively, and that when said objective lens is offset from said focused position, the first image and the second image are positioned on the photoelectric elements of said first and second photoelectric element arrays, respectively, which do not mutually correspond, in accordance with said offset, said device being for detecting the focused condition of the objective lens from the positional relations of said first image and said second image with said first and second

photoelectric element arrays, respectively, the improvement comprising:

- (a) first means for calculating the differences between electrical outputs related to the outputs of the mutually corresponding ones of the photoelectric elements forming said first photoelectric element array and the photoelectric elements forming said second photoelectric element array and adding together the quantities based on said differences;
- (b) second means for calculating the difference between each electrical output related to the output of each of said photoelectric elements and each electrical output related to the output of the photoelectric element spaced apart from each said photoelectric element with a predetermined number of photoelectric elements interposed therebetween in the direction of arrangement of the photoelectric elements of said arrays and adding together the quantities based on said differences; and
- (c) third means for detecting the focused condition of the objective lens on the basis of the outputs of said first means and said second means.

4,297,572

TRACKING SOLAR ENERGY COLLECTOR ASSEMBLY


Richard J. Carlton, Sunnyvale, Calif., assignor to Acurex Corporation, Mountain View, Calif.

Filed Aug. 14, 1979, Ser. No. 66,402

Int. Cl.³ G01J 1/20

U.S. Cl. 250—203 R

22 Claims



1. A tracking type of solar energy collector assembly comprising:

- means including a panel member for collecting solar energy, said panel member being mounted for movement along a tracking path in order to maintain a predetermined orientation with the sun as the latter moves across the sky from an initial position immediately following sunrise to a final position immediately preceding sunset;
- means for moving said panel member along said tracking path;
- solar position sensing means mounted for movement with said panel member and responsive to the position of the sun for producing an output indicating whether or not said panel member is in said predetermined orientation with the sun;
- direct insolation monitoring means including a plurality of fixed light sensing elements positioned in a fixed orientation with the ambient surroundings to receive a limited beam of direct sunlight on at least one of said light sensing elements regardless of the position of the sun as the latter moves from its initial position in the sky to its final position, said monitoring means producing outputs respectively corresponding to the intensity of light received at said light sensing elements; and
- control means connected with said moving means and responsive to the outputs from said solar position sensing means and said monitoring means when operating in an automatic searching and tracking mode for controlling the operation of said moving means to continuously place said panel member in said predetermined orientation with the sun as the latter moves across the sky from its initial posi-

tion to its final position and so long as the intensity of light received on at least one of said sensing elements is at or above the threshold level indicative of the presence of direct sunlight.

4,297,573

POSITION TRANSDUCER FOR A ROTATING MEMBER

Raffaele Becchi, Ivrea; Felice Giaccone, Turin, and Andrea Accattino, Salerano, all of Italy, assignors to Ing. C. Olivetti & C., S.p.A., Italy

Division of Ser. No. 973,011, Dec. 26, 1978. This application


May 16, 1980, Ser. No. 150,441

Claims priority, application Italy, Dec. 30, 1977, 69951 A/77

Int. Cl.³ G01D 5/34

U.S. Cl. 250—231 SE

8 Claims



1. An angular position transducer for a rotating member comprising a disc connected to said member, an index means carried by said disc on its periphery, and a detector responsive to the passage of said index means for detecting the angular position of said disc, and wherein the disc is fixed to said member by means of a thin, flexible lamina and is guided in a peripheral zone thereof by a guide adjacent to said detector, in such a way as to allow the recovery of misalignments and axial displacements of said rotating member by the compliance of said lamina, in order to maintain substantially constant the distance between the detector means and the periphery of the disc.

4,297,574

RADON DETECTION

Jeffrey W. Card, 229 Argyle Ave., Apt. #308, Ottawa, Ontario, Canada (K2P 1B8), and Keith Bell, 295 5th Ave., Ottawa, Ontario, Canada (K1S 2NP)


Filed Apr. 26, 1979, Ser. No. 33,497

Claims priority, application Canada, Feb. 26, 1979, 322299

Int. Cl.³ G01V 5/00; G01T 1/04

U.S. Cl. 250—253

19 Claims



1. A method of exploring for uranium by detecting decay products of radon as an indication of the presence of uranium mineralization, comprising the steps of: providing, at respective spaced-apart locations at a uranium exploration site, a plurality of decay product collectors having at least substantially similar surface areas; enclosing each of said collectors at its respective location in

an air space in which said collectors are exposed to radon migrating from the ground; the enclosure of the air spaces maintaining the air within the air spaces in a substantially undisturbed condition during the exposure of said collectors; continuing the exposure of said collectors for a period of time sufficient for the radon to migrate by natural processes into the air spaces and for the decay products of the migrating radon to become deposited on said collectors; terminating the exposure of said collectors; measuring alpha particles, beta particles or gamma rays emitted by decay of the decay products deposited on said collectors; the measurements of the alpha particles, beta particles or gamma rays being initiated at at least substantially equal respective time intervals following the terminations of the exposures of said collectors and being effected over at least substantially equal measurement periods; and comparing the measurements thus obtained from the spaced-apart locations to provide an indication of the presence or absence of uranium mineralization at, or geologically associated with, the uranium exploration site.

4,297,575

SIMULTANEOUS GAMMA RAY MEASUREMENT OF FORMATION BULK DENSITY AND CASING THICKNESS


Harry D. Smith, Jr.; Dan M. Arnold, both of Houston, and Kenneth J. Smith, Rosenberg, all of Tex., assignors to Halliburton Company, Duncan, Okla.

Filed Aug. 13, 1979, Ser. No. 66,125

Int. Cl.³ G01V 5/00

U.S. Cl. 250—265

15 Claims



1. A method for logging a cased well borehole to determine simultaneously the bulk density of earth formations behind the wall casing and the thickness of the well casing, comprising the steps of:

- emitting low energy gamma radiation from a source of such radiation in a well borehole into the casing and earth formations surrounding a cased well borehole;
- detecting at a first, longitudinally spaced distance from said source, gamma radiation scattered back into the borehole by the casing and earth formations and generating first count rate signals representative thereof;
- detecting at a second, differently longitudinally spaced distance from said source, gamma radiation scattered back into the borehole by the casing and earth formations and generating second count rate signals representative thereof;
- combining said first and second count rate signals according to a predetermined relationship to derive a third signal

representative of the earth formation bulk density compensated for detector standoff from the earth formation caused by the casing and a fourth correction signal representing the correction required to compensate said third signal for the standoff;
combining said third and fourth signals according to a second, different predetermined relationship, to derive a fifth signal representative of the thickness of the casing in the vicinity of said detectors; and
recording at least said third and fifth signals.

4,297,576


DEVICE FOR THE INTERCONNECTION OF CONDUCTIVE TERMINALS LOCATED WITHIN A DEMOUNTABLE ENCLOSURE AND CONDUCTIVE TERMINALS LOCATED OUTSIDE SAID ENCLOSURE
Michel Laval, Saint Martin D'Uriage, and Edmond Tournier, Grenoble, both of France, assignors to Commissariat à l'Energie Atomique, Paris, France

Filed Nov. 23, 1979, Ser. No. 97,051

Claims priority, application France, Nov. 28, 1978, 78 33545

Int. Cl.³ G01T 1/18; G01N 21/00

U.S. Cl. 250—336



6 Claims

1. A device for providing interconnection between conductive terminals, said terminals having variable potentials appearing thereat and being located within a conductive enclosure comprising two demountable portions, and conductive terminals located outside said enclosure, said device comprising conductive layers, a plurality of conductors mutually insulated from one another and lying between said conductive layers, and means for bringing said conductive layers and said conductors to a polarization potential, said conductive layers and said conductors passing through the wall of said enclosure between the two demountable portions thereof and being insulated from said enclosure.

4,297,577

RADIATION DETECTION OF GAS COMPOSITIONS
Charles D. Coe, Barlow, and Philip Wright, Dronfield Woodhouse, both of England, assignors to Land Pyrometers Limited, Sheffield, England

Filed Nov. 29, 1979, Ser. No. 99,008

Claims priority, application United Kingdom, Nov. 29, 1978, 846533/78


Int. Cl.³ G01J 1/00

U.S. Cl. 250—343

1 Claim

1. Equipment for the monitoring of gas in-situ comprising an infra-red source adapted to propagate a radiation beam through ducting or the like through which the gas to be analysed passes, a detector spaced from the infra red source responsive to radiation from the beam, a band-pass filter in the beam path to restrict beam radiation incident on the detector to a predetermined wavelength range, and a filter cell adapted to be positioned in the radiation path between the detector and the source, said cell being filled with the gas component requiring analysis, the detector and source being arranged such that the detector is responsive to beam radiation that passes in the

ducting only through the gas to be analysed and to beam radiation that passes through the gas to be analysed and the cell, the detector being connected in a circuit including first means for measuring radiation passing through a first radiation path, second means for measuring radiation passing through a second radiation path, said gas to be analysed being in said first and second radiation paths, said gas component filter cell being in only said second radiation path, third means responsive to said first means and second means respectively for obtaining



6 Claims

two levels of radiation, fourth means for determining a difference between the two levels of radiation, a fifth means for dividing the difference by either of the two levels of radiation received by the detector, an output of said circuit being a function of the amount of monitored gas present in the gas flow, including calibration means comprising a second infra red source generating radiation along a sight path, said sight path including an enclosure containing a fixed concentration of gas or no gas, said detector being selectively exposed in said sight path for equipment calibration.

4,297,578

AIRBORNE DUST MONITOR


William R. Carter, 5021 Wooddale La., Minneapolis, Minn. 55424

Filed Jan. 9, 1980, Ser. No. 110,601

Int. Cl.³ G01J 1/00; G01N 21/00

U.S. Cl. 250—343

7 Claims



1. In an airborne dust monitor of the type having photosensitive means for detecting a predetermined airborne dust level at a test region, the improvement which comprises generally vertical flue means for establishing a flow of ambient air through said test region, said detecting means being housed within said flue means adjacent said test region, and test means, including test element means, operable from the outside of said flue means for selectively positioning said test element means within said test region.

4,297,579

BI-FREQUENCY INFRARED SPECTROMETER

Tilman P. Spaeth, Sipplingen, Fed. Rep. of Germany, assignor to Bodenseewerk Geosystem GmbH, Überlingen, Fed. Rep. of Germany


Filed Jun. 4, 1980, Ser. No. 156,505

Claims priority, application Fed. Rep. of Germany, Jun. 15, 1979, 2924131; Jun. 15, 1979, 2924132; European Pat. Off., Jun. 15, 1979, 79101976

Int. Cl.³ G01N 21/26

U.S. Cl. 250—343

13 Claims



1. Signal processing circuit for the separation of overlapping signals, which are provided by a detector subjected to alternating measuring quantities and having inertia and/or memory, wherein the detector signal is integrated by an integrator during predetermined reference and measuring time intervals, each of which is associated with one of the alternating measuring quantities, characterized in that

- a clamp circuit acting on the detector signal and controlled by a programmer is provided,
- the output signal of the clamp circuit is applied to the integrator directly through a first switch controlled by the programmer, and inverted through a second switch also controlled by the programmer,
- one switch is closed by the programmer during each reference and measuring time interval and the other switch is closed during compensation time intervals defined before each reference and measuring time interval,
- the clamp circuit is arranged to be actuated by the programmer to clamp the detector signal to a baseline before each reference, measuring and compensation time interval,
- the programmer is arranged to apply the output signal of the integrator or a function of this signal to one memory circuit each, after each reference time interval and after each measuring time interval, and
- furthermore the integrator is arranged to be reset to zero by the programmer after each application of the output signal to one of the memory circuits.

4,297,580

X-RAY OPTICAL SYSTEM FOR ARTICLE INSPECTION, WITH COMPONENTS DISPOSED ON PARALLEL AXES
Adolph Juner, City Island, and David J. Haas, Suffern, both of N.Y., assignors to North American Philips Corporation, New York, N.Y.

Continuation of Ser. No. 864,503, Dec. 27, 1977, abandoned.

This application Sep. 14, 1979, Ser. No. 75,467

Int. Cl.³ G01T 1/00

U.S. Cl. 250—368


20 Claims

1. An X-ray optical system for examining an inanimate article, comprising:

- a source of X-rays directed in a generally downward first direction,
- a fluorescent screen means for converting said X-rays to a light image, said screen means being disposed below said X-ray source,
- means for receiving said article between said X-ray source and said fluorescent screen means such that said X-rays passing through said article reach said screen means to generate thereat a light image of said article,
- a first light reflecting means disposed below said fluorescent

cent screen means for receiving said light image from said fluorescent screen means, said light image being directed in said first direction,

- second light reflecting means disposed opposite and obliquely to said first light reflecting means for receiving said light image reflected from said first light reflecting



means and for redirecting said light image in an upward second direction, and
(f) means for viewing said redirected light image, said viewing means being disposed above said second light reflecting means, said viewing means including an image intensifier for receiving said light image from said second light reflecting means.

4,297,581

METHOD FOR THE FAST AND ACCURATE IDENTIFICATION OF CORE POWER IN NUCLEAR REACTORS


William T. Brunson, and Anthony F. Lexa, both of Lynchburg, Va., assignors to The Babcock & Wilcox Company, New Orleans, La.

Filed Jan. 15, 1979, Ser. No. 3,444

Int. Cl.³ G01T 3/00

U.S. Cl. 250—391

4 Claims



1. A method for accurately and rapidly generating an output signal corresponding to the power of a nuclear reactor having a reactor core and a heat receiving fluid passing through said core in heat transfer relationship therewith which comprises: generating a first neutron flux signal corresponding to reactor power at a first point in time; generating a second neutron flux signal corresponding to reactor power at a subsequent point in time; generating a thermal power signal, at the subsequent point in time, derived from a thermal differential of the fluid cooling the reactor; generating an output signal, at the subsequent point in time, by varying the thermal power signal in

proportion with a predetermined relationship of the first and second neutron flux signals.

4,297,582

RADIATION DIAGNOSTIC DEVICE FOR GENERATING TOMOGRAPHIC IMAGES

Günter Schwierz, Rudolf Schittenhelm, Günter Schmitt, all of Erlangen, and Edgar Tschunt, Rathsberg, all of Fed. Rep. of Germany, assignors to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany


Filed Jul. 18, 1979, Ser. No. 58,464

Claims priority, application Fed. Rep. of Germany, Aug. 9, 1978, 2834934

Int. Cl.³ G03B 41/16

U.S. Cl. 250—445 T

2 Claims



1. A diagnostic device for generating layer images of an exposure subject, said device comprising

- (a) a patient support (2) providing a generally horizontal patient support surface at which a patient is supported so as to position a body layer to be examined in a longitudinally disposed scan plane generally parallel to the plane of said patient support surface and at a predetermined distance above the patient support surface less than the patient thickness,
- (b) a measuring arrangement for the irradiation of the body layer to be examined by means of x-rays to produce a series of scan projections with respective directional axes lying in said scan plane and each projection providing a multiplicity of beam paths in said scan plane and intersecting the body layer in a generally fan shaped beam configuration, said measuring arrangement including an x-ray radiation source (4) which emits x-ray radiation for providing said fan beam configuration in said scan plane with lateral extent corresponding to the extent of said body layer in said scan plane,
- (c) said measuring arrangement further including a radiation receiver (5) disposed in the plane of said fan shaped beam configuration and arranged to intercept the fan shaped beam configuration on the opposite side of the body layer from the radiation source during irradiation of the body layer for each scan projection in said scan plane, and to supply output signals corresponding to the measured radiation intensity for respective beam paths of the fan shaped beam configuration for each scan projection of the body layer,
- (d) a measured value converter (19) connected with the radiation receiver for calculating attenuation values for specific image points of the irradiated body layer from the output signals of the radiation receiver,
- (e) scanning means (8, 10a) coupled with said measuring arrangement and providing for movement thereof in said scan plane so as to irradiate said body layer along the respective directional axes in accordance with said series of scan projections during a scanning operation, and so that the body layer to be examined is scanned by being penetrated exclusively along beam paths of the fan shaped beam configuration each of which is crossed, along its

entire length in the body layer, by a multitude of other beam paths,

- (f) mounting means (9, 12) mounting said scanning means (8, 10a) such that the measuring arrangement moves along a path lying in the scan plane and such that the fan shaped beam configuration sweeps through an arcuate region lying in the scan plane and extending from one side of the patient support to the other over an angular extent of substantially less than 360° to avoid irradiating a patient lying on the patient support except at the body layer, and
- (f) means comprising said scanning means and said mounting means for sweeping the fan beam configuration during a scanning operation in a scan plane lying a distance above the patient support surface less than the patient thickness such that a 360° movement of the measuring arrangement about the body layer, which is prevented by a patient on the patient support, is unnecessary to the production of a layer image of said body layer, said last-mentioned means directing the beam configuration obliquely relative to a radial line from the x-ray radiation source (4) to the center of curvature (10) of the arcuate region swept by the beam configuration such that the arcuate region swept by the beam configuration during the scanning operation is essentially clear of the patient except at the body layer.

4,297,583

ULTRAVIOLET LIGHT APPARATUS

Irving Nerod, Spotswood, N.J., assignor to American Can Company, Greenwich, Conn.


Continuation-in-part of Ser. No. 11,525, Feb. 8, 1979,

abandoned. This application Feb. 28, 1980, Ser. No. 125,373

Int. Cl.³ H01J 37/00; F26B 3/30

U.S. Cl. 250—453

4 Claims



1. Apparatus for curing ink or coatings on a cylindrical container comprising:

- (a) a frame;
- (b) a wheel, mounted on said frame for rotation about an axis;
- (c) a reflector, affixed to said wheel for movement therewith about said axis, said axis being co-incident with a first focus of said reflector and wherein a second focus is outward thereof;
- (d) a radiant energy source fixedly mounted on said frame, substantially co-extensive with said reflector and disposed at said first reflector focus;
- (e) a belt disposed to engage said wheel at the circumference and drive said wheel, said belt including a plurality of carriers mounted thereon for (one of said carriers) supporting and (maintaining said container in confronting alignment with said reflector) conveying said containers, said carriers being disposed along said belt at intervals equal to the circumference of said wheel, said belt engaging said wheel to advance said carriers into individual registration with said reflector wherein said container mounted on said registered carrier is substantially co-extensive with said energy source and is confrontingly aligned with said reflector whereby said confrontingly aligned container intercepts rays from said reflector, prox-

imate the second focus of said reflector, and wherein said rays are maintained substantially in focus on said confrontingly aligned containers as said confrontingly aligned container moves around said energy source; and

(f) means for rotating said carriers as said carriers move around said energy source thereby ensuring uniform irradiation of said confrontingly aligned container by said focused rays of energy.

4,297,584

RARE EARTH PHOSPHORS AND PHOSPHOR SCREENS


Robert A. Buchanan, Palo Alto; T. Grant Maple, and Alden F. Sklensky, both of Sunnyvale, all of Calif., assignors to Lockheed Missiles & Space Company, Inc., Sunnyvale, Calif.

Filed Apr. 11, 1977, Ser. No. 786,227

Int. Cl.³ G01J 1/58

U.S. Cl. 250—483

33 Claims



1. A stabilized rare earth oxybromide phosphor consisting essentially of at least one oxybromide selected from the group consisting of yttrium oxybromide, lanthanum oxybromide and gadolinium oxybromide in which from about 0.001 percent to about 10 percent of the host metal ions have been replaced by trivalent cerium ions and characterized by having an integral, continuous surface layer of at least one rare earth oxychloride selected from the group consisting of yttrium oxychloride, lanthanum oxychloride and gadolinium oxychloride in which from about 0.001 percent to about 10 percent of the host metal ions have been replaced by trivalent cerium ions.

4,297,585

SYSTEM FOR THE DETECTION OF SPLICING DEFECTS IN FILM

Werner Puschmann, Langenfeld, Fed. Rep. of Germany, assignor to AGFA-Gevaert Aktiengesellschaft, Leverkusen, Fed. Rep. of Germany


Filed Dec. 27, 1979, Ser. No. 107,652

Claims priority, application Fed. Rep. of Germany, Dec. 29, 1978, 2856705

Int. Cl.³ G01N 21/86

U.S. Cl. 250—560

16 Claims



1. A system for identifying a defective splice which improperly bridges a gap located between a leading strip of film and a trailing strip of film, and for identifying an improper gap, when the strips are moving at a constant rate past a fixed line segment located on and oriented transversely to a path along which the strips travel, the path dividing an imaginary line which intersects the line segment and is oriented normally with

respect to the path into a first side and a second side, comprising:

- a gap sensor producing a time-varying gap signal with a gap state and a strip state, the gap signal assuming the strip state whenever a strip is located at the line segment and assuming the gap state whenever a gap is located at the line segment;
- a splice sensor producing a time-varying splice signal with a splice state and a non-splice state, the splice signal assuming that splice state whenever a splice is located at the line segment and assuming the non-splice state otherwise; and
- a congruence computer responsive to the gap signal and splice signal and producing an output signal with a congruence state and a discongruence state, the output signal assuming the congruence state when and only when the splice is properly bridging the gap and the gap is proper, and assuming the discongruence state otherwise.

4,297,586

PHOTO-ELECTRIC DIGITAL CIRCUIT FOR MONITORING STRIP LOOP POSITION


John M. Rodgers, 12990 Club Dr., Redlands, Calif. 92373

Filed Feb. 25, 1980, Ser. No. 124,628

Int. Cl.³ G01N 21/86

U.S. Cl. 250—561

5 Claims



1. Apparatus for monitoring strip loop position in a strip loop reservoir comprising:

- a plurality of light sources and a corresponding plurality of photo-detectors spaced from each other on opposite sides of the strip loop path in the strip loop reservoir;
- a plurality of first amplifying means, each said first amplifying means having its input coupled to a corresponding photo-detector, said first amplifying means being normally biased to be driven substantially to positive or negative saturation as a function of the input voltage applied to said first amplifying means through said corresponding photo-detector, the outputs of said plurality of first amplifying means being coupled together at a summing junction;
- second amplifying means having its input coupled to the summing junction for amplifying the voltage and current signals appearing at said summing junction; and
- means coupled to the output of said second amplifying means for remotely visually monitoring the strip loop position as a function of the output of said second amplifying means.

4,297,587

ABSOLUTE DC SYSTEM FOR A LASER INSPECTION SYSTEM

Cole H. Baker, Westport, Conn., assignor to Intec Corporation, Trumbull, Conn.

Filed Mar. 7, 1980, Ser. No. 128,286

Int. Cl.³ G01N 21/30


U.S. Cl. 250—563

7 Claims

1. A stabilized absolute direct current system for controlling the sensitivity of a light inspection system having a laser generating a laser beam and a scanner for scanning said laser beam

over a surface of a moving material being inspected thereby to detect flaws in said material comprising:

- a receiver for collecting laser beam radiation emanating from said material,
- said receiver having a photomultiplier tube for detecting and generating signals in accordance with the intensity of radiation applied thereto,
- means for applying a sample of radiation from said laser beam to said photomultiplier tube for generating a reference pedestal signal dependent on the intensity of said



laser beam which is free of the influence of the characteristics of the material, comparator means having a reference potential and said reference pedestal signal applied thereto for deriving a control signal,

- a power supply for said photomultiplier tube,
- a closed loop feedback circuit for coupling said control signal to said power supply and coupling said power supply to said photomultiplier tube for automatically regulating the power gain to said photomultiplier tube to a constant value thereby providing a stabilized dc system.

4,297,588


ELECTRO-OPTICAL LEVEL

Albin A. Hastbacka, 3 Singlefoot Rd., Chelmsford, Mass. 01824
Filed Feb. 6, 1979, Ser. No. 9,853

Int. Cl.³ G01N 15/06

U.S. Cl. 250—577

3 Claims



1. A level indicating device comprising:
 - a device with two legs joined at one end wherein said legs are spaced to form a slot within which a solid or liquid in a container is capable of being placed;
 - a collimated light source within one leg of said device which is directed to fall upon a light sensor in the second leg of said device in the absence of a solid or liquid in a container within said slot wherein the collimated light beam from said light source is positioned to strike a transparent solid or transparent liquid in a transparent container, inserted into said slot of said device, at an angle which is substantially off of a line perpendicular to the surface of said inserted solid or liquid container so that the refracted light beam passing through said transparent solid or liquid container will not fall upon said light sensor in the pres-

ence of said transparent solid or transparent liquid in transparent container;
a pair of rectangular slots or cylindrical tunnels which aperture limit the light beam emanating from said light source and the received light beam falling upon said light sensor;
means for exciting said light source;
means for detecting the presence or absence of said light beam falling upon said light sensor so as to provide a visible or audible indication of the presence or absence of said solid or liquid between said light source and light sensor.

4,297,589

SPEED GOVERNOR FOR A HYDROELECTRIC UNIT


Oleg I. Bashnin, prospekt Maiorova, 53, kv. 13; Vasily V. Semenov, Moskovsky prospekt, 171, kv. 92; Vasily N. Fedorov, Prazhskaya ulitsa, 23, kv. 61; Nikolai M. Gorbunov, ulitsa Brjusovskaya, 6, kv. 100; Evgeny I. Rodionov, prospekt Raevskogo, 8, kv. 21, and Nikolai A. Sorokin, Sredneokhtinsky prospekt, 46, kv. 4, all of Leningrad, U.S.S.R.

Filed Mar. 14, 1980, Ser. No. 130,267

Int. Cl.³ F01D 17/02

U.S. Cl. 290—40 R

2 Claims



1. A speed governor, for a hydroelectric unit including a hydraulic turbine having a gate apparatus for controlling the flow of water to the hydraulic turbine runner, comprising:
 - an error sensing means having a signal generated at an output which is representative of a deviation of the hydroelectric unit rotational frequency from an assigned value;
 - an integrator having an input and an output;
 - a gate opening control means connected to said output of said integrator and adjusting the degree of opening of said gate apparatus in accordance with the value of the integrator output signal; and
 - a limiter having an input and an output, said input of said limiter being connected to said output of said error sending means, and said output of said limiter being connected to said input of said integrator, said limiter limiting the maximum value of the signal applied to said input of said integrator to a limit value equal to the minimum integrator input signal value which insures a maximum permissible rate of change of the degree of opening of said gate apparatus.

4,297,590

POWER SUPPLY SYSTEM

Ande Vail, 3702 Unit C, Overland Rd., Boise, Id. 84705

Filed Mar. 10, 1980, Ser. No. 128,566


Int. Cl.³ H02J 7/34

U.S. Cl. 307—43

4 Claims

1. A power supply system for supplying direct current to a load, said system comprising:
 - three sets of batteries, with each set of batteries having an ampere/hour rating of at least ten times the value of the load current;
 - circuitry connecting each of the three sets of batteries to the load;
 - three sets of switching means for opening and closing the respective circuits between the load and each set of batteries; and
 - control means for alternating each set of switches in open and closed position, wherein the closed position has a time duration about twice that of the open position, and the switches are switched open and closed in cyclic, predetermined

mined order with the first switch closing at about the same time the second switch opens, the second switch closing



about the same time the third switch opens, the third switch closing about the same time the first switch opens, and then repeating the cycle.

4,297,591

ELECTRONIC COUNTER FOR ELECTRICAL DIGITAL PULSES

Helmut Roesler, and Otto Muehlbauer, both of Munich, Fed. Rep. of Germany, assignors to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany


Filed Jun. 25, 1979, Ser. No. 51,675

Claims priority, application Fed. Rep. of Germany, Jul. 28, 1978, 2833211

Int. Cl.³ H03K 23/08, 21/30, 21/06

U.S. Cl. 307—224 C

9 Claims



1. In a counter of the type in which a plurality of flip-flops each having a pair of inputs and a pair of outputs are provided in a chain connection and a plurality of transfer circuits are respectively interposed between successive flip-flops, the improvement wherein each of said transfer circuits comprises:
 - a plurality of transfer transistors having conduction paths connected between the outputs of one flip-flop and the inputs of the subsequently connected flip-flop and control electrodes for receiving control signals to determine the direction of counting,

- said plurality of transfer transistors comprising
 - a first field effect transistor including a source-drain path connected between a first output of a first flip-flop and a first input of a next successive, second flip-flop, and a gate connected to receive a forward count control signal;
 - a second field effect transistor including a source-drain path connected between a second output of the first flip-flop and a second input of the second flip-flop, and a gate connected to receive the forward count control signal;
 - a third field effect transistor including a source-drain path connected between said second output and said first input, and a gate connected to receive a backward count control signal; and
 - a fourth field effect transistor including a source-drain path connected between said first output and said sec-

ond input, and a gate connected to receive the backward count control signal.

4,297,592

INTEGRATABLE DYNAMIC CURRENT SOURCE FOR SEMICONDUCTOR MODULES

Karlheinz Url, Munich, and Paul W. von Basse, Wolfratshausen, both of Fed. Rep. of Germany, assignors to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany


Filed Aug. 15, 1979, Ser. No. 66,867

Claims priority, application Fed. Rep. of Germany, Sep. 7, 1978, 2839073

Int. Cl.³ H03K 5/00, 5/22

U.S. Cl. 307—583

3 Claims



1. A current source for a read-out amplifier having two transistors cross-coupled to two bit lines of a MOS memory, said transistors having respective source electrodes connected together at a node which is charged before the beginning of a read-out cycle and is successively discharged in a selected manner for the evaluation of a read-out signal, said current source for use with a first and a second clock pulse line and comprising:
 - a capacitor connected between the node and the first clock pulse line;
 - a switching transistor having a control electrode connected to the second clock pulse line and having a first terminal connected to said node and a second terminal connected to a reference potential;

- said first clock pulse line providing a voltage signal during each read-out cycle which changes from a high voltage level to a reference voltage level;
- said second clock pulse line providing a voltage signal during each read-out cycle changing from a reference potential level to a high potential level;
- said capacitor and said switching transistor operating in combination to provide a voltage signal at said node during each read-out cycle, said signal changing from a high potential to a reference potential through a transition portion of said signal, said transition portion having an initial region of slow transition having a low slope followed by a region of rapid transition having a high slope.

4,297,593

GLITCH ELIMINATOR CIRCUIT FOR TTL TRANSPARENT LATCH

Gordon H. Allen, Mesa, Ariz., assignor to Motorola, Inc., Schaumburg, Ill.

Filed Mar. 10, 1980, Ser. No. 128,773

Int. Cl.³ H03K 17/56


U.S. Cl. 307—247 R

11 Claims

1. A latch circuit capable of operating in a transparent mode or a latching mode and having an input terminal for receiving an input data signal which may assume high or low voltage levels and having an output terminal, comprising:
 - an input transistor having base, emitter and collector terminals, said base terminal coupled to said input terminal;
 - a latching transistor having base, emitter and collector terminals, the emitter and collector terminals of said latching transistor being coupled to the emitter and collector ter-

over a surface of a moving material being inspected thereby to detect flaws in said material comprising:

- a receiver for collecting laser beam radiation emanating from said material,
- said receiver having a photomultiplier tube for detecting and generating signals in accordance with the intensity of radiation applied thereto,
- means for applying a sample of radiation from said laser beam to said photomultiplier tube for generating a reference pedestal signal dependent on the intensity of said



laser beam which is free of the influence of the characteristics of the material,
 comparator means having a reference potential and said reference pedestal signal applied thereto for deriving a control signal,

- a power supply for said photomultiplier tube,
- a closed loop feedback circuit for coupling said control signal to said power supply and coupling said power supply to said photomultiplier tube for automatically regulating the power gain to said photomultiplier tube to a constant value thereby providing a stabilized dc system.

4,297,588


ELECTRO-OPTICAL LEVEL

Albin A. Hastbacka, 3 Singlefoot Rd., Chelmsford, Mass. 01824
 Filed Feb. 6, 1979, Ser. No. 9,853

Int. Cl.³ G01N 15/06

U.S. Cl. 250—577

3 Claims



1. A level indicating device comprising:

- a device with two legs joined at one end wherein said legs are spaced to form a slot within which a solid or liquid in a container is capable of being placed;
- a collimated light source within one leg of said device which is directed to fall upon a light sensor in the second leg of said device in the absence of a solid or liquid in a container within said slot wherein the collimated light beam from said light source is positioned to strike a transparent solid or transparent liquid in a transparent container, inserted into said slot of said device, at an angle which is substantially off of a line perpendicular to the surface of said inserted solid or liquid container so that the refracted light beam passing through said transparent solid or liquid container will not fall upon said light sensor in the pres-

ence of said transparent solid or transparent liquid in transparent container;
 a pair of rectangular slots or cylindrical tunnels which aperture limit the light beam emanating from said light source and the received light beam falling upon said light sensor;
 means for exciting said light source;
 means for detecting the presence or absence of said light beam falling upon said light sensor so as to provide a visible or audible indication of the presence or absence of said solid or liquid between said light source and light sensor.

4,297,589

SPEED GOVERNOR FOR A HYDROELECTRIC UNIT


Oleg I. Bashnin, prospekt Maiorova, 53, kv. 13; Vasily V. Semenov, Moskovsky prospekt, 171, kv. 92; Vasily N. Fedorov, Prazhskaya ulitsa, 23, kv. 61; Nikolai M. Gorbunov, ulitsa Brjusovskaya, 6, kv. 100; Evgeny I. Rodionov, prospekt Raevskogo, 8, kv. 21, and Nikolai A. Sorokin, Sredneokhtinsky prospekt, 46, kv. 4, all of Leningrad, U.S.S.R.

Filed Mar. 14, 1980, Ser. No. 130,267

Int. Cl.³ F01D 17/02

U.S. Cl. 290—40 R

2 Claims



1. A speed governor, for a hydroelectric unit including a hydraulic turbine having a gate apparatus for controlling the flow of water to the hydraulic turbine runner, comprising:
 - an error sensing means having a signal generated at an output which is representative of a deviation of the hydroelectric unit rotational frequency from an assigned value;
 - an integrator having an input and an output;
 - a gate opening control means connected to said output of said integrator and adjusting the degree of opening of said gate apparatus in accordance with the value of the integrator output signal; and
 - a limiter having an input and an output, said input of said limiter being connected to said output of said error sending means, and said output of said limiter being connected to said input of said integrator, said limiter limiting the maximum value of the signal applied to said input of said integrator to a limit value equal to the minimum integrator input signal value which insures a maximum permissible rate of change of the degree of opening of said gate apparatus.

4,297,590

POWER SUPPLY SYSTEM

Ande Vail, 3702 Unit C, Overland Rd., Boise, Id. 84705

Filed Mar. 10, 1980, Ser. No. 128,566

Int. Cl.³ H02J 7/34


U.S. Cl. 307—43

4 Claims

1. A power supply system for supplying direct current to a load, said system comprising:
 - three sets of batteries, with each set of batteries having an ampere/hour rating of at least ten times the value of the load current;
 - circuitry connecting each of the three sets of batteries to the load;
 - three sets of switching means for opening and closing the respective circuits between the load and each set of batteries; and
 - control means for alternating each set of switches in open and closed position, wherein the closed position has a time duration about twice that of the open position, and the switches are switched open and closed in cyclic, predetermined

mined order with the first switch closing at about the same time the second switch opens, the second switch closing

and input, and a gate connected to receive the backward count control signal.



about the same time the third switch opens, the third switch closing about the same time the first switch opens, and then repeating the cycle.

4,297,591

ELECTRONIC COUNTER FOR ELECTRICAL DIGITAL PULSES

Helmut Roesler, and Otto Muehlbauer, both of Munich, Fed. Rep. of Germany, assignors to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany


Filed Jun. 25, 1979, Ser. No. 51,675

Claims priority, application Fed. Rep. of Germany, Jul. 28, 1978, 2833211

Int. Cl.³ H03K 23/08, 21/30, 21/06

U.S. Cl. 307—224 C

9 Claims



1. In a counter of the type in which a plurality of flip-flops each having a pair of inputs and a pair of outputs are provided in a chain connection and a plurality of transfer circuits are respectively interposed between successive flip-flops, the improvement wherein each of said transfer circuits comprises:

- a plurality of transfer transistors having conduction paths connected between the outputs of one flip-flop and the inputs of the subsequently connected flip-flop and control electrodes for receiving control signals to determine the direction of counting,
- said plurality of transfer transistors comprising
- a first field effect transistor including a source-drain path connected between a first output of a first flip-flop and a first input of a next successive, second flip-flop, and a gate connected to receive a forward count control signal;
- a second field effect transistor including a source-drain path connected between a second output of the first flip-flop and a second input of the second flip-flop, and a gate connected to receive the forward count control signal;
- a third field effect transistor including a source-drain path connected between said second output and said first input, and a gate connected to receive a backward count control signal; and
- a fourth field effect transistor including a source-drain path connected between said first output and said sec-

4,297,592

INTEGRATABLE DYNAMIC CURRENT SOURCE FOR SEMICONDUCTOR MODULES

Karlheinz Url, Munich, and Paul W. von Basse, Wolfratshausen, both of Fed. Rep. of Germany, assignors to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany


Filed Aug. 15, 1979, Ser. No. 66,867

Claims priority, application Fed. Rep. of Germany, Sep. 7, 1978, 2839073

Int. Cl.³ H03K 5/00, 5/22

U.S. Cl. 307—583

3 Claims



1. A current source for a read-out amplifier having two transistors cross-coupled to two bit lines of a MOS memory, said transistors having respective source electrodes connected together at a node which is charged before the beginning of a read-out cycle and is successively discharged in a selected manner for the evaluation of a read-out signal, said current source for use with a first and a second clock pulse line and comprising:

- a capacitor connected between the node and the first clock pulse line;
- a switching transistor having a control electrode connected to the second clock pulse line and having a first terminal connected to said node and a second terminal connected to a reference potential;
- said first clock pulse line providing a voltage signal during each read-out cycle which changes from a high voltage level to a reference voltage level;
- said second clock pulse line providing a voltage signal during each read-out cycle changing from a reference potential level to a high potential level;
- said capacitor and said switching transistor operating in combination to provide a voltage signal at said node during each read-out cycle, said signal changing from a high potential to a reference potential through a transition portion of said signal, said transition portion having an initial region of slow transition having a low slope followed by a region of rapid transition having a high slope.

4,297,593

GLITCH ELIMINATOR CIRCUIT FOR TTL TRANSPARENT LATCH

Gordon H. Allen, Mesa, Ariz., assignor to Motorola, Inc., Schaumburg, Ill.

Filed Mar. 10, 1980, Ser. No. 128,773

Int. Cl.³ H03K 17/56


U.S. Cl. 307—247 R

11 Claims

1. A latch circuit capable of operating in a transparent mode or a latching mode and having an input terminal for receiving an input data signal which may assume high or low voltage levels and having an output terminal, comprising:
 - an input transistor having base, emitter and collector terminals, said base terminal coupled to said input terminal;
 - a latching transistor having base, emitter and collector terminals, the emitter and collector terminals of said latching transistor being coupled to the emitter and collector ter-

minals respectively of said input transistor, the collector terminals of both said input and said latching transistors being coupled to said output terminal;

a first source of a latch disabling signal coupled to the base of said input transistor, said latch disabling signal capable of assuming high or low voltage levels for placing said latch circuit in the transparent mode when said latch disabling signal is high;



a second source of a latch enabling signal for enabling said latching transistor, said latch enabling signal capable of assuming high or low voltage levels for placing said latch circuit in the latching mode when said latch enabling signal is high, said latch enabling signal occurring prior to said latch disabling signal; and

means for synchronizing said latch disabling signal with said latch enabling signal so as to turn said input transistor on substantially simultaneously with turning said latching transistor off when said input data signal is high.

4,297,594


GATE CIRCUIT FOR A GATE TURN-OFF THYRISTOR
Kenichi Onda, Hitachi; Sadaji Tashiro, Kumagaya, and Hisao Amano, Hitachi, all of Japan, assignors to Hitachi, Ltd. and Hitachi Metals, Ltd., both of Tokyo, Japan

Filed Jun. 21, 1979, Ser. No. 50,522

Claims priority, application Japan, Sep. 27, 1978, 53-119015
Int. Cl.³ H03K 17/72

U.S. Cl. 307—252 C

4 Claims



1. A gate circuit for a gate turn-off thyristor having a cathode, an anode, and a gate, comprising:

a series connection of a d.c. power supply source and a first switching element, said series connection being inserted between the cathode and the gate of said gate turn-off thyristor through a diode, the positive pole of said d.c. power supply source being connected to the cathode of said gate turn-off thyristor, while the negative pole of said d.c. power supply source is connected to the gate of said gate turn-off thyristor through said first switching element and said diode; and

a transformer having a primary winding and a secondary winding both wound with the same polarity, one end of said primary winding being connected to the cathode of said diode through a resistor while the other end of said primary winding is connected to the cathode of said gate turn-off thyristor, and one end of said secondary winding being connected to the anode of said diode through a

second switching element while the other end of said secondary winding is connected to the cathode of said gate turn-off thyristor.

4,297,595

SIGNAL REGENERATING CIRCUIT WITH IMPROVED INPUT-OUTPUT ISOLATION


Josef Huellwegen, Altenbeken, Fed. Rep. of Germany, assignor to Nixdorf Computer AG, Paderborn, Fed. Rep. of Germany
Filed Jun. 18, 1979, Ser. No. 49,136

Claims priority, application Fed. Rep. of Germany, Jun. 19, 1978, 2826897

Int. Cl.³ H03K 5/01

U.S. Cl. 307—268

9 Claims



1. In a regenerating system for generating output signals at a system output terminal corresponding to data signals applied at a system input terminal, said system having transformer means having a primary and a secondary winding, means connected to said primary winding for applying thereto high frequency signals modulated by said data signals, main rectifier means connected to said secondary winding for rectifying said modulated high frequency signals, thereby creating first rectified signals constituting said output signals, and buffer circuit means having a high impedance and a low impedance in the absence and presence of a control signal, respectively: the improvement comprising

additional rectifier means connected to said secondary winding for rectifying said modulated high frequency signals, thereby creating additional rectified signals;

and connecting means for connecting said additional rectifier means to said buffer circuit means so that said additional rectified signals constitute said control signals.

4,297,596

SCHMITT TRIGGER


Kim Eckert, Austin, Tex., assignor to Motorola, Inc., Schaumburg, Ill.

Filed May 1, 1979, Ser. No. 35,050

Int. Cl.³ H03K 3/295, 3/356

U.S. Cl. 307—279

2 Claims



1. A MOS Schmitt trigger circuit comprising:

a first field effect transistor of the enhancement type and having a drain and a gate coupled to a first potential, and a source coupled to an output terminal;

a second field effect transistor of the enhancement type and having a drain coupled to the source of the first transistor, a gate coupled to an input terminal, and a source;

a third field effect transistor of the depletion type and having

a drain coupled to the source of the second transistor, a gate, and a source;

a fourth field effect transistor of the enhancement type and having a drain coupled to the gate and source of the third transistor, a gate coupled to the first potential, and a source coupled to a second potential; and

a fifth field effect transistor of the enhancement type and having a drain coupled to the first potential, a gate coupled to the drain of the second transistor, and a source coupled to the drain of the third transistor.

4,297,597

DARLINGTON-CONNECTED SEMICONDUCTOR DEVICE

Takashi Kimura, Yokohama, Japan, assignor to Tokyo Shibaura Denki Kabushiki Kaisha, Japan


Filed Jun. 13, 1979, Ser. No. 48,003

Claims priority, application Japan, Jun. 20, 1978, 53/73734

Int. Cl.³ H03K 3/26; H01L 29/72

U.S. Cl. 307—315

6 Claims



1. A Darlington-connected semiconductor device for amplifying an input signal, comprising:

a pre-stage transistor circuit portion including at least one pre-stage transistor with a plurality of emitters, a collector, and at least one base;

input terminal means connected to the base of said pre-stage transistor for receiving an input signal to be amplified by said device;

a rear-stage transistor circuit portion including at least one rear-stage transistor with a plurality of bases and emitters, said rear-stage transistor having a collector in common with said collector of said pre-stage transistor;

a plurality of resistors connected respectively between the emitters of said pre-stage transistor and the bases of said rear-stage transistor through the emitters of said pre-stage transistor and said resistors; and

output terminal means connected to the emitters of said rear-stage transistor for receiving an amplified form of said input signal.

4,297,598

I²L SENSING CIRCUIT WITH INCREASED SENSITIVITY
Kent F. Smith, Salt Lake City, Utah, assignor to General Instrument Corporation, Clifton, N.J.


Filed Apr. 5, 1979, Ser. No. 27,507

Int. Cl.³ H03K 5/24; G11C 7/00

U.S. Cl. 307—355

35 Claims

1. An I²L circuit for sensing relatively small differences in signal magnitude between first and second input signals comprising first and second means adapted to receive the first and second input signals, respectively; dual input bistable means for generating an output representative of the relative degree of actuation of said bistable means inputs, subsequent to the resetting of said bistable means; means for supplying current to said bistable means to energize same; means for resetting said bistable means; and means, operably connected to said bistable



means inputs and said receiving means, for actuating said bistable means inputs, respectively, to degrees dependent upon the relative magnitudes of the signals applied at said first and second receiving means.

4,297,599

CIRCUIT ARRANGEMENT FOR OBTAINING AN INTERFERENCE-FREE TRIGGER SIGNAL ESPECIALLY FOR A FUEL APPORTIONMENT DEVICE IN AN INTERNAL COMBUSTION ENGINE

Peter Werner, Wiernsheim-Iptingen; Ulrich Drews, Vaihingen-Pulverdingen; Theodor Elbers, Krodorf-Gleiberg, and Klaus Jäkel, Reutlingen, all of Fed. Rep. of Germany, assignors to Robert Bosch GmbH, Stuttgart, Fed. Rep. of Germany


Filed Aug. 15, 1979, Ser. No. 66,743

Claims priority, application Fed. Rep. of Germany, Oct. 31, 1978, 2847290

Int. Cl.³ H03K 5/153, 19/20

U.S. Cl. 307—355

8 Claims



1. In an interference-free triggering circuit, for regulating ignition current signals to an electronic fuel apportionment device for an internal combustion engine, the triggering circuit including:

a first threshold switch to which a first current signal is applied to generate an output if a first threshold value is exceeded by the first current signal;

a second threshold switch to which a second current signal is applied to generate an output if a second threshold value is exceeded by the second current signal;

a time-lag circuit connected to the second threshold switch to receive and delay the second threshold output;

a logic circuit, connected to the first threshold switch and the time-lag circuit to receive the output of the first threshold switch and the output of the time-lag circuit such that the logic circuit generates a reset signal only when the logic circuit receives no output from the first threshold switch and no output from the time-lag circuit; and

a switching element, connected to the first threshold switch and the logic circuit such that the switching element is set by the first threshold switch output and is reset by the

logic circuit reset signal to generate a command signal to the fuel apportionment device.


4,297,600

MULTIPATH RAMAN CELL FOR WAVELENGTH CONVERSION

William R. Trutna, Jr., Palo Alto, Calif., assignor to Board of Trustees of Leland Stanford University, Stanford, Calif.
Filed Jun. 19, 1978, Ser. No. 916,592
Int. Cl.³ H03F 7/00

U.S. Cl. 307—426

8 Claims



1. In a method for wavelength conversion by Raman scattering, the steps of:

directing a beam of pumping optical radiation of a wavelength greater than 1 micron into an optical resonator defined by the space between a pair of optical reflectors, said beam of optical radiation being directed into the optical resonator at an angle to the optical axis of the resonator such that the optical beam is caused to be reflected to and fro within said resonator between said reflectors over a path which includes a plurality of transits of said resonator and which path walks over the surfaces of the reflectors and out of said resonator;

filling a region of space within said resonator with a Raman active gaseous medium for interaction with said beam of optical radiation for converting pump energy into stimulated Raman scattering radiation of a Stokes wavelength longer than that of said pump wave energy; and focusing the reflected beam on each transit of said resonator at a point within said Raman active gaseous medium for enhancing the Raman scattering interaction.

4,297,601

MONOSTABLE MULTIVIBRATOR CIRCUIT AND FM DETECTOR CIRCUIT EMPLOYING PREDETERMINED LOAD RESISTANCE AND CONSTANT CURRENT TO INCREASE RESPONSE RATE OF DIFFERENTIAL TRANSISTOR PAIR


Takeshi Wada, Kodaira; Yasuo Kominami, Kokubunji; Yukihiko Miyamoto, and Tsuneo Yamada, both of Tokyo, all of Japan, assignors to Hitachi, Ltd. and Trio Kabushiki Kaisha, both of Tokyo, Japan

Filed Jan. 16, 1979, Ser. No. 3,962

Claims priority, application Japan, Mar. 15, 1978, 53/28663
Int. Cl.³ H03K 5/12, 3/284

U.S. Cl. 307—555

5 Claims



1. In a monostable multivibrator circuit having: a time con-

stant circuit which includes a capacitor; an amplifier circuit connected to receive an output signal of the time constant circuit; a positive feedback circuit which is connected between an output of said amplifier circuit and an input of said time constant circuit and which comprises a pair of differential transistors, a constant-current circuit including a constant-current transistor the collector of which is connected to the emitters of said pair of differential transistors and a load resistor connected to the collector of one of the pair of differential transistors, means for supplying the base of said one of said pair of differential transistors with an output signal from the output of said amplifier circuit and means for transmitting the voltage at said load resistor to said input of said time constant circuit; and trigger input terminal means coupled to a circuit loop including said time constant circuit, said amplifier circuit and said positive feedback circuit and to which a trigger signal is applied, characterized in that clamp circuit means is coupled to said one of the differential transistors for clamping the collector potential of said one of said differential transistors to a value higher than the base input potential thereof, wherein said constant-current circuit includes means for setting the constant collector current of said constant-current transistor and the resistance of said load resistor is set so that the falling rate of the voltage at said load resistor during a change of said one of said pair of differential transistors from a non-conductive state to a conductive state is higher than the rising rate of the voltage at said load resistor during a change thereof from a conductive state to a non-conductive state, whereby said monostable multivibrator circuit is triggered by a leading edge in a change of the voltage at said load resistor from a non-conductive state of said one of said pair of differential transistors to a conductive state thereof.

4,297,602

MAGNETOSTRICTIVE CO-ORDINATE PLATE FOR CO-ORDINATE READER

Toshihiko Kobayashi, Mitaka, and Tetsusaburo Kamibayashi, Niza, both of Japan, assignors to Kokusai Denshin Denwa Kabushiki Kaisha, Japan


Continuation-in-part of Ser. No. 14,736, Feb. 23, 1979, abandoned, which is a continuation of Ser. No. 775,465, Mar. 8, 1977, abandoned. This application Mar. 12, 1980, Ser. No. 129,575

Claims priority, application Japan, Mar. 10, 1976, 51-25870; Apr. 23, 1976, 51-46226

Int. Cl.³ H01L 41/12

U.S. Cl. 310—26

16 Claims



1. A co-ordinate plate for a co-ordinate reader, comprising: a pair of thin sheets of magnetostrictive material, each of said sheets of magnetostrictive material having a dimension defined by a preferred direction of magnetostrictive oscillating wave propagation within a sheet, and said pair of sheets of magnetostrictive material superposed and oriented with their respective preferred directions of magnetostrictive oscillating wave propagation defining respective co-ordinate axes of a co-ordinate system; an acoustically insulating sheet of material disposed between said pair of sheets of magnetostrictive material for keeping said pair of sheets of magnetostrictive material from contacting each other, and said pair of thin sheets and said acoustically insulating sheet disposed with said pair of

thin sheets of magnetostrictive material in contact with said acoustically insulating sheet to define a co-ordinate plane; and exciting means for producing magnetostrictive oscillating waves propagating in the respective preferred directions of propagation in said pair of sheets of magnetostrictive material.

4,297,603

ARRANGEMENT FOR COOLING THE ROTOR OF AN ELECTRIC MACHINE WITH A SUPERCONDUCTING FIELD WINDING

Erich Weghaupt, Mulheim an der Ruhr, Fed. Rep. of Germany, assignor to Kraftwerk Union Aktiengesellschaft, Mulheim an der Ruhr, Fed. Rep. of Germany


Filed Nov. 15, 1979, Ser. No. 94,432

Claims priority, application Fed. Rep. of Germany, Nov. 15, 1978, 2849602

Int. Cl.³ H02K 9/00

U.S. Cl. 310—53

6 Claims



1. Arrangement for cooling the rotor of an electric machine, comprising a superconducting field winding, at least one cold shield surrounding said field winding, and a co-rotatable mixing chamber containing a phase mixture of coolant fed thereto from outside said rotor, said coolant mixture having a liquid level and branching into a first stream of liquid coolant for cooling said field winding and a second stream of at least partially evaporated coolant for cooling said cold shield, said second coolant stream being conducted from said mixing chamber through said cold shield and returned from the machine in an outer loop, said first coolant stream being conducted through a multiplicity of parallel-connected open thermal-syphon inner loops from said mixing chamber, through cooling canals subdivided into corresponding cooling canal sections of winding conductors of said field winding, and returned to said mixing chamber, said coolant in said inner and outer loops being transported by the self-pumping effect of rotation of said rotor, said inner loops having radial entrance and exit branches distributed over the length and circumference of said rotor and field winding, mixing chamber sections associated with said respective inner loops, said mixing chamber sections having a given axial length and radial height forming collecting pockets leading into said entrance branches for coolant which is colder than the average temperature of the liquid phase and produced by evaporation at said liquid level, means for fanning-up a directional thermal-syphon loop flow from weight and pressure differences of said radial coolant canal sections of said respective inner loops, said mixing chamber sections being distributed over the axial length and inner circumference of said rotor in accordance with the placement of said thermal-syphon inner loops, and being disposed concentrically about the central longitudinal axis of said mixing chamber of said rotor, each of said mixing chamber sections having at least one loop entrance point spaced from the axis, and at least one loop exit point in vicinity of a thermal-syphon inner loop.

4,297,604

AXIAL AIR GAP ALTERNATORS/GENERATORS OF MODULAR CONSTRUCTION


Ian S. Tawse, Weston, Canada, assignor to Gen-Tech, Inc., Miami, Fla.

Filed May 11, 1979, Ser. No. 38,251

Int. Cl.³ H02K 21/38

U.S. Cl. 310—168

14 Claims



1. An electrical generator comprising:
(a) a generally cylindrical casing including two radially spaced-apart walls,
(b) a plurality of individual elongated magnetic cores located between the casing walls, each core having an electrical coil wound around it, the cores and coils defining the stator of the generator,
(c) a rotor within the inner of the casing walls, the rotor being rotatable about an axis parallel to the axis of the casing, the rotor having a plurality of radially projecting magnetic pole pieces, the magnetic pole pieces extending into axial alignment with the magnetic cores and being axially spaced from the ends of those cores,
(d) whereby as the rotor rotates the magnetic cooperation between the pole pieces and cores generates electric current in the stator coils on the cores.

4,297,605

BRUSH ASSEMBLIES FOR ELECTRIC MOTORS OR GENERATORS

Shiu M. Tak, Kowloon, Hong Kong, assignor to Wah Ming Electrics Limited, Kowloon, Hong Kong


Filed Jan. 22, 1980, Ser. No. 114,317

Claims priority, application United Kingdom, Oct. 30, 1979, 37524/79

Int. Cl.³ H02K 13/00

U.S. Cl. 310—242

4 Claims



1. A brush assembly for one of an electric motor and an electric generator, comprising a brush having a first end for contacting a commutator of the one of the motor and the generator and a second end, a holder for said brush, a contact for connection to a supply of electrical power, conductive restraining means disposed at said second end of said brush, and a conductive spring having a first end which abuts against

said restraining means and a second end which abuts against said contact, whereby said spring urges said brush against the commutator, said restraining means prevents said first end of said spring from contacting the commutator when said brush has worn away, and said spring and said restraining means provide a conductive path between said contact and said brush.

4,297,606

METHOD OF BRACING END TURNS OF AN ELECTRIC MACHINE BY MEANS OF A BINDING BAND; AND DEVICE USED THEREIN

Arnold Wichmann, Mulheim an der Ruhr, Fed. Rep. of Germany, assignor to Kraftwerk Union Aktiengesellschaft, Mulheim an der Ruhr, Fed. Rep. of Germany


Filed Mar. 22, 1978, Ser. No. 889,003

Claims priority, application Fed. Rep. of Germany, Mar. 29, 1977, 2713847

Int. Cl.³ H02K 3/48

U.S. Cl. 310—271

4 Claims



1. In a device for bracing winding end turns of an electric machine wherein a pair of winding bars forming the end turns are disposed spaced from and substantially parallel to one another, a spacer member disposed between and contacting the winding bars and defining and predetermining the spacing between the pair of winding bars, a first binding tape wrapped transversely around the pair of winding bars at the location of said spacer member, a second binding tape wrapped transversely about the wrapped first binding tape in the space between the pair of winding bars, the wrapped first and second binding tapes and mutually opposing surfaces of the parallel winding bars defining a substantially closed inner space there-within wherein said spacer member is disposed, and a cold hardened, flowable-type cement mass injectedly received in said inner space, said spacer member having a shape affording penetration by said flowable-type cement from a given injection point to every part of said inner space unoccupied by said spacer member and to all surfaces defining said unoccupied part of said inner space, said spacer member comprising a substantially parallelepipedal body formed with at least one lateral recess providing a passageway for penetration by a flowing cement mass from one side to another of said body.

4,297,607

SEALED, MATCHED PIEZOELECTRIC TRANSDUCER

Lawrence C. Lynnworth, Waltham; Kenneth A. Fowler, and Dana R. Patch, both of Medfield, all of Mass., assignors to Panametrics, Inc., Waltham, Mass.

Filed Apr. 25, 1980, Ser. No. 143,714


Int. Cl.³ H01L 41/08

U.S. Cl. 310—334

50 Claims

1. A sealed ultrasonic transducer assembly for use adjacent a fluid of characteristic acoustic impedance Z_4 , comprising, an electroacoustic transducer element having a front surface and a rear surface and a characteristic acoustic impedance Z_1 , an impedance-transforming matching element positioned in contact with the front surface of said transducer element, an electrically conductive shielding housing having an aper-

ture for transmitting ultrasonic radiation from said transducer assembly, and a sealing element enclosing said aperture and hermetically sealed to said housing, said matching element being formed of a non-resilient material having an effective characteristic impedance intermediate between that of said transducer element and said fluid; said sealing element having an acoustic impedance higher than that of said matching element by a factor of at least 2



and having a thickness between 1/10th and 1/1000th of a wavelength at the center frequency of ultrasonic waves being transmitted from said transducer element, said sealing element being electrically conductive over at least one surface, said electrically conductive housing being in electrical contact with said electrically conductive surface; the combination of said sealing element, matching element and transducer being restrained axially and radially within said housing.

4,297,608

MEASURING EQUIPMENT FOR ACOUSTIC DETERMINATION OF THE SPECIFIC GRAVITY OF LIQUIDS

Borge R. Jensen, Kobenhavn, Denmark, assignor to Danfoss A/S, Nordborg, Denmark


Filed May 1, 1980, Ser. No. 145,620

Claims priority, application Denmark, May 10, 1979, 01924/79

Int. Cl.³ H01L 41/08

U.S. Cl. 310—335

1 Claim



1. A measuring probe for the acoustic determination of the specific gravity of a liquid, comprising, a holder having a piezoelectric ceramic disc attached at one end thereof and a parallel arranged reflection disc attached at the other end thereof, a reference element having parallel end faces and a known acoustical impedance, said reference element having one of said end faces in abutting engagement with said piezoelectric disc and the other of said end faces in spaced relation to said reflection disc to form a sampling space therebetween, said reference element having an annularly shaped groove formed therein intermeditate said end faces and having a planar surface adjacent to and parallel to said ceramic disc, said holder having wall means bounding and surrounding said annular groove, and said wall means forming an opening to

provide ingress and egress to and from said sampling space for a medium externally of said probe.

4,297,609

HIGH-VOLTAGE GENERATING DEVICE

Tsuneo Hirao, and Masao Onishi, both of Neyagawa, Japan, assignors to Matsushita Electric Industrial Co., Ltd., Osaka, Japan


Filed Apr. 3, 1980, Ser. No. 137,007

Claims priority, application Japan, Apr. 6, 1979, 54-46078[U]

Int. Cl.³ H01L 41/08

U.S. Cl. 310—339

4 Claims



1. A high-voltage generating device comprising a piezoelectric element, a driven member of an electrical conductor disposed on one side of said piezo-electric element, an abutment member of an electrical conductor disposed on the other side of said piezo-electric element, an outer casing of an electrical insulator accommodating said piezo-electric element therein in such a relation that said conductive abutment member is partly exposed to the exterior of said outer casing, an inner casing telescopically received in said outer casing, said inner casing accommodating therein a hammer for imparting an impact to said conductive driven member and a hammer spring for imparting a drive force to said hammer, a return spring for normally biasing said inner casing in a return direction in which said inner casing protrudes partly from said outer casing, and a strip of an electrical conductor pressed at one end thereof against said conductive driven member by said return spring and exposed at the other end thereof to the exterior of said outer casing.

4,297,610

SMALL PIEZOELECTRIC TUNING FORK

Kunimoto Ito, 37-9, 1-chome, Kikunodai, Chofu-shi, Tokyo; Tsutomu Kakizawa, 23-17, 2 chome, Miyasaka, Setagaya-ku, Tokyo; Kengo Yonetani, 23-17, 2 chome, Miyasaka, Setagaya-ku, Tokyo, Japan, and Hiroshi Nariai, 23-17, 2-chome, Miyasaka, Setagaya-ku, Tokyo, all of Japan


Continuation-in-part of Ser. No. 709,067, Jul. 27, 1976, abandoned, which is a continuation of Ser. No. 546,042, Jan. 31, 1975, abandoned. This application Sep. 6, 1977, Ser. No. 830,964

Claims priority, application Japan, Feb. 4, 1974, 49-14354; Jan. 17, 1975, 50-7023

Int. Cl.³ H01L 41/08

U.S. Cl. 310—370

1 Claim



1. A piezoelectric flection vibrator which comprises a tuning fork-type quartz vibrator body having a pair of leg members extending from the base portion of said vibrator body, the lengths of said leg members being equal to each other, said base portion of said vibrator body and said leg members including a pair of generally U-shaped principal faces positioned in parallel to each other, each said leg member having a pair of side faces

each extending between and connecting said principal faces perpendicularly to each other, each said side face and each face on said leg members included in a said principal face of the vibrator body being provided with an electrode formed thereon, characterized in that said length of said leg member is less than six millimeters and the ratio t/w where t and w are the thickness and the width respectively of said leg member is chosen at a value less than one, whereby the point of zero-temperature coefficient of said vibrator body is set at a temperature appearing normally within a wrist watch carried on the human body.

4,297,611

CONTROL OF TUNGSTEN FILAMENT EROSION IN A HALOGEN LAMP


Salvatore F. Cortorillo, Parsippany, N.J., assignor to Wagner Electric Corporation, Parsippany, N.J.

Filed Oct. 2, 1979, Ser. No. 81,270

Int. Cl.³ H01K 1/50, 1/18

U.S. Cl. 313—222

11 Claims



1. In an incandescent lamp of the type having at least two operative tungsten filaments in a bulb enclosing an atmosphere containing a halogen gas, the improvement comprising an inoperative surrogate filament within said bulb comprising a tungsten surface positioned in a region near said tungsten filaments to passively receive chemical attack by said halogen gas whereby said operative tungsten filaments are at least partially protected from attack by said halogen gas and wherein said operative tungsten filaments have two support legs each, said inoperative surrogate filament comprises four tungsten wires, one each positioned near a support leg, each said tungsten wire separated a small distance from said support leg and extending substantially parallel to its associated support leg.

4,297,612

ELECTRON GUN STRUCTURE

Yoshimitsu Anezaki, Fukaya, Japan, assignor to Tokyo Shibaura Electric Co., Ltd., Kawasaki, Japan

Division of Ser. No. 835,062, Sep. 21, 1977, Pat. No. 4,185,223. This application Apr. 4, 1979, Ser. No. 27,036

Claims priority, application Japan, Sep. 27, 1976, 51-114645


Int. Cl.³ H01J 29/02

U.S. Cl. 313—446

5 Claims

1. An electron gun for producing and directing at least one electron beam along a beam path; said structure comprising: a plurality of grid electrodes (18, 20...26) including a first control grid electrode (18), a cathode (16) comprising a cathode sleeve (30), which has an open end and a closed end having an electron emissive coating (34) adjacent to the first control grid electrode, a heater comprising a heater coil (40) made of thin wire, and heater supporting straps (42), which support said heater positioned within said cathode sleeve, having an arcing induction means (46) confronting the open end of said cathode sleeve, wherein: the open end of said cathode sleeve extends toward said

arcing induction (46) means of said heater supporting straps so that the distance between them is smaller than the distance between said cathode sleeve and said heater



coil in order to make an arc between cathode sleeve and said heater supporting straps before inducing an arc between said cathode and the heater coil.

4,297,613

D.C. SCAN PANEL


Mohamed O. Aboufotouh, Poughkeepsie, N.Y., assignor to International Business Machines Corporation, Armonk, N.Y.

Filed May 8, 1979, Ser. No. 37,082

Int. Cl.³ H01J 17/34, 61/067

U.S. Cl. 315—58

14 Claims



1. In a d.c. gaseous discharge display device, an ionizable gaseous medium in a gas chamber formed by a pair of glass plates, a plurality of cathode conductors orthogonal to said anode conductors and disposed on a surface of the other of said glass plates, a quantity of material overlying said cathode conductors to protect said cathode conductors from sputtering during gaseous discharge, said material comprising a doped mixture of a refractory oxide insulator and a metal dopant, said doped refractory oxide material having sufficient conductivity to prevent the build-up of a surface wall charge during d.c. operation of said display device and having sufficient secondary emissivity to reduce the voltage required to sustain gaseous discharge.

4,297,614 EMERGENCY LIGHTING SYSTEM


Edward A. Chandler, Montreal, Canada, assignor to Kaufel Group Ltd., Montreal, Canada

Filed Mar. 12, 1980, Ser. No. 129,696

Int. Cl.³ H05B 37/00

U.S. Cl. 315—86

6 Claims



1. For use with an electric discharge lamp in a fixture, said lamp having a first input terminal and a second input terminal; an emergency lighting unit comprising: a transformer, having two closely coupled windings constituting the primary of said transformer, and a secondary winding, first adjacent ends of said coupled windings comprising the input of said emergency lighting unit, and second adjacent ends of said coupled windings comprising the output terminals of said emergency lighting unit; said input terminals of said emergency lighting unit being adapted to be connected to a source of ac power; said output terminals of said emergency lighting unit being adapted to be connected to respective ones of said first and second input terminals of said lamp; whereby each one of said closely coupled windings is in a different line between said source of ac power and a respective one of said first and second input terminals of said lamp; rectifier means connected across the output of said secondary winding; rechargeable battery means connected across the output of said rectifier means and being rechargeable by the dc output thereof; inverter means connected in parallel with said battery means and adaptable to convert the dc output of said battery means to an ac signal; and means for sensing a loss of ac power from said source of ac power and to, upon such sensing, connecting said inverter in circuit with said input terminals.

4,297,615

HIGH CURRENT DENSITY CATHODE STRUCTURE

Dan M. Goebel, Santa Monica; James T. Crow, Los Angeles, and A. Theodore Forrester, Beverly Hills, all of Calif., assignors to The Regents of the University of California, Berkeley, Calif.

Filed Mar. 19, 1979, Ser. No. 21,461


Int. Cl.³ H01J 1/20; H05H 1/24

U.S. Cl. 315—111.21

16 Claims

1. A system including a compact cathode assembly having high electron emission current densities for producing a dense gas plasma, comprising: a high plasma density cathode enclosure; inlet means connected to said cathode enclosure for supplying gas to said cathode enclosure; a low plasma density utilization chamber coupled to receive

plasma from said cathode enclosure through a restricted opening between said enclosure and said chamber; a cathode element of lanthanum hexaboride having an emitting surface exposed within said cathode enclosure; means for heating said lanthanum hexaboride element to an elevated temperature from a surface of said lanthanum hexaboride away from the emitting surface, whereby contamination of said emitting surface is avoided;



said system including means for establishing a high plasma density, in the order of 2×10^{12} electrons per cubic centimeter or more, within said cathode enclosure, substantially higher than in said utilization chamber; power supply means for drawing current densities greater than five amperes per square centimeter from the emitting surface of said lanthanum hexaboride cathode; and means for mounting said lanthanum hexaboride cathode on carbon material support arrangements.

4,297,616

FLUORESCENT LAMP WITH INCANDESCENT BALLASTING SYSTEMS


Stephen C. Corona, Rochester, N.Y., assignor to Xerox Corporation, Stamford, Conn.

Filed Mar. 17, 1980, Ser. No. 130,929

Int. Cl.³ H05B 35/00, 41/19

U.S. Cl. 315—179

9 Claims



1. An incandescent ballasting circuit for a fluorescent lamp comprising: at least one incandescent device connected between an electrical power source and fluorescent lamp, means for applying a preheat voltage to the fluorescent lamp filaments, and means for applying a trigger voltage to said fluorescent lamp sufficient to initiate lamp discharge said triggering voltage means including: a conductive plane adjacent to said fluorescent lamp, a transformer electrically connected to said conductive plane, and a pulse generating circuit connected between said incandescent device and said transformer, said circuit adapted to operate from said power source to generate a high voltage pulse and apply said pulse to said lamp via the transformer and conductive plane, initiating lamp discharge, said circuit means further adapted to be disabled following initiation of lamp discharge.

4,297,617

LIGHT PRODUCING DEVICE


Charles E. Galasple, Rte. 1, Box 353, Bumpass, Va. 23024

Filed Mar. 24, 1980, Ser. No. 132,742

Int. Cl.³ H01J 61/30; H05B 41/26

U.S. Cl. 315—326

7 Claims



1. A light producing device comprising an elongated flexible transparent thermoplastic tube having sealed proximal and distal ends and containing an electrically excitable gas, and an electrical supply which associates with said proximal end, said tube having a substantially uniform cross sectional configuration along its length, a length to diameter ratio in excess of 20, a flexibility such that said ends can be readily brought into contact, a wall thickness capable of resisting collapse of said tube under a pressure gradient of one atmosphere, and a transparency such that a significant percentage of the light generated within said tube will emerge through the wall of said tube, said electrically excitable gas being a mono or polyatomic gas or gas mixture at a pressure of between about 1 and 7 mm Hg., said electrical supply providing an output current which is a pulsed direct current of sub-ampere intensity having a peak voltage between 20,000 and 50,000 volts and a pulse frequency of about 60 pulses per second, said output current being directed by a single electrical conductor to a pointed metal electrode protruding through the proximal end of said tube and coaxial therewith, and thermal shielding means annularly disposed between said electrode and the adjacent wall of said tube.

4,297,618

ANODE VOLTAGE DEFLECTION GAIN CONTROL FOR CATHODE RAY DISPLAYS


Thomas W. Spilsbury, Phoenix, Ariz., assignor to Sperry Corporation, New York, N.Y.

Filed Sep. 15, 1980, Ser. No. 187,039

Int. Cl.³ H01J 29/56

U.S. Cl. 315—371

8 Claims



1. Cathode ray display apparatus including a cathode ray display tube having at least anode means, cathode means, and associated electron beam deflection coil means, power supply means for supplying an anode voltage to said anode means, sampling circuit means for deriving a sample of said anode voltage, square root signal extractor means responsive to said anode voltage sample, circuit means for generating a sweep signal, and multiplier means responsive to said square root signal and to said sweep signal for generating a compensated electron

beam deflection current for driving said electron beam deflection coil means.

4,297,619

PHOSPHOR PROTECTION CIRCUIT FOR MULTIPLE CRT PROJECTION TELEVISION


Terence J. Kiteley, Schaumburg, Ill., assignor to Zenith Radio Corporation, Glenview, Ill.

Filed Jan. 2, 1981, Ser. No. 222,205

Int. Cl.³ H01J 29/52

U.S. Cl. 315—381

24 Claims



1. In a projection color television system having a projecting screen, three cathode ray tubes each having a phosphor screen for producing, by means of an electron beam incident upon said phosphor screen, and projecting onto said projecting screen a different one of the three primary colors of a light beam containing image information therein, and a vertical deflection coil in each of said cathode ray tubes for deflecting said electron beams across said projecting screen in a vertical direction by means of vertical deflection signals provided to said deflection coils, a protection system comprising:

means for connecting said vertical deflection coils serially; transformer means including a core, three primary windings each connected in parallel across one of said vertical deflection coils and a secondary winding coupled inductively to said primary windings, with two of said primary windings each having N turns and a first winding polarity and the third primary winding having 2 N turns and a second winding polarity opposite to said first polarity, such that said transformer is balanced when all of said deflection coils transmit said vertical deflection signals with no signal induced in said secondary winding; and shutdown means coupled to said secondary winding and to said cathode ray tubes for receiving a signal induced in said secondary winding due to transformer imbalance caused by a discontinuity in the current transmitted by one or more of said primary coils and terminating the electron beam in each said cathode ray tubes in response thereto.

4,297,620

QUASI FEEDBACK HORIZONTAL SCAN LINEARIZATION FOR CATHODE RAY TUBES

Ronald Quan, Cupertino, Calif., assignor to Ampex Corporation, Redwood City, Calif.

Filed Mar. 10, 1980, Ser. No. 129,059

Int. Cl.³ H01J 29/72


U.S. Cl. 315—389

5 Claims

1. A scan circuit for linearizing the non-linear yoke current during the horizontal-scan interval of a horizontal scan circuit including a yoke and serial switching transistor, comprising the combination of;

a current sensing resistor in series with the yoke for generating a non-linear voltage ramp commensurate with the non-linear yoke current;
a resonating capacitor coupled to the yoke opposite the sensing resistor;
linear ramp generator means coupled to the yoke opposite the sensing resistor and including a holding capacitor and

transistor means coupled thereto, wherein the ramp generator means generates a linear voltage ramp in response to a reset pulse due to the yoke inductance during the fly-back interval of the horizontal scan; and



feedback means including the ramp generator means and a damper diode coupled to the yoke opposite the sensing resistor for selectively feeding back the linear voltage ramp to the yoke circuit during the first half of a selected line scan interval to linearize the corresponding non-linear yoke current.

4,297,621

CATHODE RAY TUBE BEAM DEFLECTION AMPLIFIER SYSTEM


Thomas W. Spilsbury, Phoenix, Ariz., assignor to Sperry Corporation, New York, N.Y.

Filed Oct. 2, 1980, Ser. No. 193,236

Int. Cl.³ H01J 29/70, 29/76

U.S. Cl. 315—397

6 Claims



1. A cathode ray tube electron beam deflection control system having linear and non-linear operating modes, comprising:

deflection coil means;
preamplifier means having an input terminal and first and second output terminals, said input terminal responsive to an input sweep signal during said linear mode of operation;
first amplifier means having input and output terminals, said input terminal being coupled to said first output terminal of said preamplifier, for amplifying the current received therefrom;
second amplifier means having input and output terminals, said input terminal being coupled to said second output terminal of said preamplifier, for amplifying the current received therefrom;
fly-back diode means having first and second terminals, said first terminal coupled to said amplifier output terminal for unidirectionally conducting current received from said amplifier output terminal to said flyback diode second terminal;
diode means having first and second terminals, said first

terminal coupled to a first power supply having a first voltage potential and said second terminal coupled to said second amplifier output terminal, for unidirectionally coupling current to said first power supply from said diode means second terminal

fly-back capacitor means coupled in series relationship with said diode means and in shunt relationship with said fly-back diode means and further coupled to said deflection coil; and

switching means responsive to an applied fly-back drive signal for coupling said second amplifier output terminal with said fly-back diode means second terminal in said linear mode of operation and for decoupling said second amplifier output terminal with said fly-back diode means in said non-linear mode of operation.

4,297,622

MOTOR DRIVE


Charles C. Dittman, Dallas, Tex., and Richard C. St. Clair, Ridgecrest, Calif., assignors to The United States of America as represented by the Secretary of the Navy, Washington, D.C.

Filed Oct. 26, 1979, Ser. No. 88,498

Int. Cl.³ H02K 29/02

U.S. Cl. 318—254

3 Claims



1. A two phase sequential bipolar analog drive with closed loop speed control in a motor having a plurality of windings as a stator which interacts with a permanently magnetized gyro rotor which is free to pivot and rotate relative to the stator comprising:

means place about said stator for sensing rotation of said stator which generates a single reference signal of known phase relationship to the plurality of windings of said stator;
means for generating a plurality of gyro motor drive signals properly phased to the rotation of said gyro rotor based on said reference signal comprising:
a buffer circuit receiving said reference signal for filtering and amplifying said reference signal to a predetermined output signal from said buffer circuit;
an oscillator/squaring circuit which inputs said buffer circuit output for emitting a predetermined driving pulse when said buffer output is beneath a present threshold frequency and for squaring up said buffer circuit output when it is above said present threshold frequency;
a phase shifter circuit which inputs said buffer circuit output for changing the phase of said buffer circuit output a predetermined amount when said buffer circuit output frequency is beneath a defined limit;
a squaring circuit connected to said phase shifter circuit for squaring up said phase shifted buffer circuit output and inputting it to said stator for driving said rotor; and
means for controlling the level of said plurality of gyro rotor drive signals based on said reference signal.

4,297,623

SYSTEM FOR CONTROLLING A SEPARATELY EXCITED CONSTANT LOAD DC ELECTRIC MOTOR

Jean M. Dupont, Paris, France, assignor to Compagnie Internationale pour l'Informatique CII-Honeywell Bull, Paris, France


Filed Jun. 12, 1978, Ser. No. 914,987

Claims priority, application France, Jun. 20, 1977, 77 18874

Int. Cl.³ H02P 5/16

U.S. Cl. 318—410

15 Claims



1. A system for controlling a separately excited constant load DC electric motor in response to a source of a control signal defining desired time periods corresponding to desired motor operating conditions and without the use for a feedback circuit responsive to exciting current supplied by the source to the motor, the motor exciting current having a term representing resistive and reactive losses in an electric circuit responsive to the exciting current, comprising simulator means for only the resistive losses, said simulator means being responsive to the control signal for modifying, during at least one of said desired time periods, the magnitude of the control signal in accordance with only the resistive losses the motor is expected to have in response to the control signal during said one time period, and means responsive to said modified control signal for applying a current that is a replica of the modified control signal to the motor armature, and independent of a response from any feedback circuit responsive to the motor armature current to preclude the need for any feedback circuit responsive to the armature current, said control signal being independent of actual motor operating current.

4,297,624

SPINDLE CONTROL SYSTEM

Hidetsugu Komiya, Hino, Japan, assignor to Fujitsu Fanuc Limited, Japan


Filed Apr. 27, 1979, Ser. No. 34,142

Claims priority, application Japan, Apr. 28, 1978, 53-51694

Int. Cl.³ G05B 11/18

U.S. Cl. 318—594

7 Claims



1. A spindle control system for a spindle control arrangement including a first motor for driving a spindle and a second motor for positioning the spindle, comprising:
first clutch means for selectively coupling the first motor with the spindle;
second clutch means for selectively coupling the second motor with the spindle;
a pulse generator coupled with the spindle for generating pulses proportional in number to the rotational angle of the spindle;

counter means for counting the pulses from the pulse generator to detect the rotational position of the spindle; and means responsive to the counter means for controlling the rotational positioning of the spindle by the second motor via the second clutch means with the first clutch means disconnected.

4,297,625


APPARATUS FOR DIVIDING THE STEP ANGLE OF A STEPPING MOTOR

Harold R. Newell, South Newbury, N.H., assignor to Mesur-Matic Electronics Corporation, Salem, Mass.

Filed Apr. 9, 1979, Ser. No. 28,618
Int. Cl.³ G05B 19/40

U.S. Cl. 318—696

1 Claim



1. A step divider apparatus for dividing the primary step of a stepping motor having a plurality of phase windings, comprising:

means for generating input timing signals;
counting means for counting the number of input timing signals from a preset count state;
memory means for storing a plurality of digital words, each digital word defining an incremental current step portion of a non-linear current signal;
means for applying the count state of said counting means to access associated digital words of said memory means;
converter means for generating an analog voltage defined by an accessed digital word;

a driver means for each of said phase windings, each driver means responsive to at least a portion of an accessed digital word for passing a unipolar current that is proportional to the analog voltage associated with the digital word;

phase select means for applying a plurality of sequentially generated analog voltages of said converter means to selected driver means to energize at least one pair of said phase windings, one winding of said at least one pair of windings energized with non-linear current steps defining an increasing non-linear unipolar current signal and the other winding of said at least one pair of windings energized with non-linear current steps defining a decreasing non-linear unipolar current signal;

voltage boost means connected to said phase windings for applying an increased voltage to a phase winding when increasing current is applied to the winding and for applying a reduced voltage to the winding at all other times;
said memory means including a sine programmable memory having stored data words for defining the positive portion of a sine current waveform as a function of the number of input timing signals applied to said counting means and a cosine programmable memory having stored data words for defining the positive portion of a cosine current waveform as a function of the number of input timing signals applied to said counting means;

said motor having four phase windings and including counter reset means for defining a number n of count states of said counting means in an energization cycle for the motor, said number n being equal to the product of a selected step divider factor times four, the step divider

factor being the number by which the step divider apparatus divides the primary step of the motor.

4,297,626

METHOD OF DETERMINING OPERATING CURRENTS FOR STEPPING MOTOR


David Chiang, 649 Caledonia Rd., Dix Hills, N.Y. 11746

Filed Feb. 7, 1980, Ser. No. 119,503

Int. Cl.³ G05B 19/40

U.S. Cl. 318—696

10 Claims



1. For a stepping motor having a rotor which is driven to rotate in response to currents having given waveforms in the stator windings, the method of determining an operating parameter of the motor comprising the steps of: periodically imparting a series of current impulses of alternating polarity to the stator windings so that the rotor can oscillate about a give rest position with the amplitude of the oscillations increasing, each of said current pulses having a duration that is an integer multiple of the resonant period of the motor; monitoring the resulting oscillations; and indicating the operating parameter of the motor in accordance with the amplitude of at least one of said resulting oscillations.

4,297,627

ELECTRIC MOTOR CONSTRUCTION

Edward J. Schaefer, Bluffton, Ind., assignor to Franklin Electric Co., Inc., Bluffton, Ind.


Continuation-in-part of Ser. No. 896,768, Apr. 17, 1978,

abandoned. This application Nov. 7, 1978, Ser. No. 958,534

Int. Cl.³ H02P 1/26, 7/36, 1/42; H02K 11/00

U.S. Cl. 318—778

27 Claims



1. In combination, an electric motor operable as a split phase or as a capacitor start motor, comprising an outer casing, a run winding circuit, a start winding circuit including a start winding cutout switch, said run and start winding circuits being mounted within said casing, power circuit means adapted to connect said start and run winding circuits to a power supply, said start winding and power circuits having an electrical gap formed therebetween, and removable interchangeable attachment means exterior of said casing and connectable to bridge

said gap, one of said attachment means causing said motor to operate as a capacitor start motor and another if said attachment means causing said motor to operate as a split phase motor.

4,297,629

AUTOMATIC SWITCHING ARRANGEMENT FOR TWO BATTERIES WHICH ARE CHARGED IN PARALLEL AND DISCHARGED IN SERIES

Pierre Godard, Tremblay les Gonesse, and Michel Billot, Drancy, both of France, assignors to Saft-Societe des Accumulateurs Fixes et de Traction, Romainville, France


Filed Apr. 1, 1980, Ser. No. 136,355

Claims priority, application France, Apr. 13, 1979, 79 09469; Dec. 6, 1979, 79 29942

Int. Cl.³ H02J 7/04

U.S. Cl. 320—7

15 Claims



1. An automatic switching arrangement for connecting two batteries in parallel between a pair of power supply leads for charging and in series between the same power supply rails for discharging to supply power thereto in the event of a failure of a power supply to the said leads, the switching arrangement comprising:

positive and negative terminals for respective connection to said power supply leads;
first and second storage batteries, the negative pole of the first battery being connected to the negative terminal and the positive pole of the second battery being connected to the positive terminal;

first and second switchable charging circuits, the first switchable charging circuit being connected between the positive pole of the first battery and the positive terminal, and the second switchable charging circuit being connected between the negative pole of the second battery and the negative terminal;

unidirectionally conductive means connected in series between the positive pole of the first battery and the negative pole of the second battery in order to allow a discharge current to flow in series through the batteries but to prevent a charging current from flowing in series through the batteries; and

control means arranged to switch on said first and second switchable charging circuits when there is sufficient externally applied voltage at the positive and negative terminals for the batteries to be charged therefrom, and to switch off said switchable charging circuits otherwise to enable the batteries to supply power in series to said positive and negative terminals;

the control means including a first transistor connected to be turned on and off by the direction of the potential difference between the positive pole of the first battery and the negative pole of the second battery, and positive feedback means arranged to saturate the first transistor when it turns on.

4,297,628

ENERGY ECONOMIZER FOR INDUCTION MOTORS


Rhey W. Hedges, Ft. Lauderdale, Fla., assignor to Louis W. Parker, Fort Lauderdale, Fla.

Filed Jul. 3, 1980, Ser. No. 165,574

Int. Cl.³ H02P 7/36, 1/26

U.S. Cl. 318—798

37 Claims



1. In an energy economizing AC power control system operative to reduce the iron and copper losses in a conventional AC induction motor having a stator winding and a rotor adapted to be coupled to a load, said system being of the type comprising a sine wave power source for energizing said stator winding to effect rotation of said rotor, and a nonlinear closed loop positive feedback control means conditionally operative to control the form and magnitude of energization of said stator winding from said power source, said feedback control means comprising motor load detecting means for producing a control signal which varies as a function of the load of said motor, wave modifier means responsive to said control signal, and switching means disposed between said sine wave power source and said stator winding, the conduction time of said switching means being controllable during each cycle of said power source as a function of said control signal to apply full sine waves of voltage from said power source to said stator winding during rotational start-up and speed build-up of said motor and, as said motor reaches a near synchronous speed, then being operative to provide varying fractions or complete cycles of each sine wave of voltage from said power source to said stator winding in accordance with the inherent electro-mechanical properties of said motor and the energy requirements imposed on said motor by the rotor load at any given moment, the improvement wherein said motor load detecting means comprises a motor current demodulator circuit coupled to said stator winding and jointly responsive to at least two load-related variations of the parameters of the inrush current to said stator winding each time the current in said stator winding increases from zero for producing said variations of said control signal, said parameters including the magnitude of the stator inrush current at the beginning of each current alteration and also including the instantaneous phase of said stator inrush current.

for surroundingly supporting a battery to be inserted into the chamber from the open end;

- (b) a retaining means for retaining said battery in the chamber of said unitary structure, said retaining means characterized by an elongated member of resilient spring material, said elongated member having a lip formed on each end thereof, each lip extending substantially perpendicularly in the same direction from said elongated member and at a predetermined angle with respect thereto; and
- (c) means, including said retaining means and said unitary structure, for mounting said retaining means on said unitary structure with a first lip of said retaining means disposed in the chamber at the first end of said unitary structure and a second lip of said retaining means disposed in the chamber at the second end of said unitary structure, one of the lips of said retaining means providing sufficient clearance in the chamber opening to allow said battery to be inserted into the chamber, whereby, when said battery is being inserted into the chamber, one of the first and second lips contacts one terminal end of said battery, while the other lip slidably engages the outside surface of said battery creating concurrent and opposing forces at opposite ends of said elongated member causing said elongated member to bend and to thereby cause said other lip to slide off of the outside surface of said battery and snap over the other terminal end of said battery, when said battery is fully inserted into the chamber, to thus securely retain said battery in the chamber of said structure.

4,297,636

MAGNET AND PROBE MOUNTING MEANS ON A ROTATING HEAD OF MAGNETIC DEFECT TESTING APPARATUS


Hans Link, Reutlingen, and Ulrich Dreher, Trochelfingen, both of Fed. Rep. of Germany, assignors to Institut Dr. Friedrich Förster Prüfgerätee, Reutlingen, Fed. Rep. of Germany
Filed Aug. 1, 1979, Ser. No. 62,708

Claims priority, application Fed. Rep. of Germany, Sep. 2, 1978, 2838388

Int. Cl.³ G01R 33/00; G01N 27/82

U.S. Cl. 324-262

18 Claims



1. A rotating head for magnetic defect testing of elongated cylindrical ferromagnetic test articles in which a rearwardly closed magnet yoke rotates about the test articles, a winding on said yoke excites magnetic flux therein, pole faces of the said magnet yoke are directed towards the test article surface, and a probe support is arranged between the pole faces including at least one field-responsive test probe, said probe support being fastened to a probe lever mounted to swing in a plane transversely perpendicular to the longitudinal axis of the test article and having a sliding shoe bearing resiliently against the test article surface, the improvement comprising:

a yoke lever mounted on the rotating head for swinging movement in a plane transversely perpendicular to the longitudinal axis of the test article, said yoke lever having one end interconnected with the magnet yoke and an end opposite said magnet yoke carrying a counterweight; and

said probe lever being rotatively mounted on the yoke lever.

4,297,637

METHOD AND APPARATUS FOR MAPPING LINES OF NUCLEAR DENSITY WITHIN AN OBJECT USING NUCLEAR MAGNETIC RESONANCE


Lawrence E. Crooks, Richmond; John C. Hoenninger, III, Berkeley, and Mitsunaki Arakawa, Forest City, all of Calif., assignors to The Regents of the University of California, Berkeley, Calif.

Filed Jul. 20, 1978, Ser. No. 926,571

Int. Cl.³ G01N 27/00

U.S. Cl. 324-309

35 Claims



1. A method for determining the relative densities of nuclei within an object, said nuclei having nuclear spins at Larmor frequencies in accordance with the intensity of a magnetic field operating thereon, the method comprising the steps of: selectively effecting the generation of spin echo signals by nuclei disposed within a predetermined volume of said object by exciting intersecting regions in said object, said predetermined volume being defined by the intersection of said regions; and detecting the intensity of said spin echo signals to obtain a measure of the relative density of nuclei in said predetermined volume.

4,297,638

X-RAY SYSTEM SIGNAL DERIVATION CIRCUITS FOR HEAT UNIT INDICATORS AND/OR CALIBRATION METERS

Robert R. LaFrance, St. Malo, Manitoba, Canada

Continuation-in-part of Ser. No. 914,504, Jun. 12, 1978, abandoned. This application Aug. 30, 1979, Ser. No. 71,252

Claims priority, application United Kingdom, Sep. 15, 1978, 36982/78


Int. Cl.³ G01R 31/024

U.S. Cl. 324-410

12 Claims

1. Signal derivation circuits for X-ray tubes, said tubes including a high tension transformer having a secondary winding and a primary winding, said secondary winding being operatively connected to the X-ray tube, said signal derivation circuits comprising in combination a milliamperage circuit operatively connected to the mid point of the secondary winding of the high tension transformer thereby providing a signal that is proportional to the milliamperes flowing through said mid point of the secondary winding, a kilovolt circuit operatively connected to the primary voltage on the high tension transformer thereby providing, in conjunction with a load compensation signal derived from said milliamperage circuit, a signal proportional to the kilovoltage across the X-ray tube and a multiplier circuit operatively connected to said milliamperage circuit and said kilovolt circuit, and a heat unit indicating module operatively connected to said multiplier, said heat unit

indicator module including a memory unit operatively connected to said multiplier circuit, and read-out means opera-



tively connected to said memory unit, and a source of power for said circuit.

4,297,639

BATTERY TESTING APPARATUS WITH OVERLOAD PROTECTIVE MEANS


Tillman W. Branham, Rte. 1, Box 149, Lugoff, S.C. 29078

Continuation-in-part of Ser. No. 969,066, Dec. 13, 1978, abandoned. This application Jul. 18, 1979, Ser. No. 58,687

Int. Cl.³ G01N 27/42

U.S. Cl. 324-429

11 Claims



1. A battery testing apparatus for evaluating the charge capacity of a storage battery under no-load and load conditions while limiting the duration of the test and protecting both the testing apparatus and battery from excessive and potentially harmful current being drawn from the battery during the test, and comprising

cable means adapted to be connected to the electrodes of the storage battery, voltage indicator means electrically connected to said cable means and operable for detecting the voltage available between the electrodes of the battery, a load circuit including a load resistor connected in parallel with said voltage indicator means and switch means connected in series with said load resistor and positionable between open and closed states so that the relative magnitude of the voltage of the battery under a no-load condition can be determined when said switch means is open and the relative magnitude of the voltage of the battery

under a load condition can be determined when said switch means is closed, and said switch means comprising current responsive means which will open in response to the passage of current of a magnitude exceeding a predetermined amperage rating, the predetermined amperage rating of said current responsive means being correlated to the resistance of said load resistor and to a predetermined acceptable level of battery capability such that a battery undergoing testing and having a capability at or above said predetermined acceptable level will result in a current in the load circuit exceeding said predetermined amperage rating of the current responsive means, thereby opening said load circuit and protecting the battery and the testing apparatus from excessive current.

4,297,640

APPARATUS FOR MEASURING THE ELECTRIC CHARGE CONDITION OF NON-CONDUCTIVE PARTICLES IN A MILDLY CONDUCTIVE ELECTROLYTE


Zack J. Moore, Lake Jackson, Tex., assignor to The Dow Chemical Company, Midland, Mich.

Filed Feb. 11, 1980, Ser. No. 120,405

Int. Cl.³ G01R 5/28

U.S. Cl. 324-458

3 Claims



1. In an apparatus for determining a function of the electrical charge condition in a flowable liquid media containing electrical charge influencing species, said apparatus having: (a) a substantially vertical tubular flowpath member which has walls which are electrically insulating, which tubular flowpath has an open end at its top and a closed end at its bottom, which closed end is also electrically insulating, and which tubular flowpath is disposed so that it may be substantially filled with said flowable liquid media; (b) a block-like reciprocating element whose outer wall, at least, is electrically insulating and which is disposed in slidable relationship within said flowpath member, said reciprocating element having a transverse cross-section such that it fits adjacent to but spaced from said walls of said flowpath member when it reciprocates in said flowpath member; (c) a pair of spaced sensing electrodes located within said flowpath member, the electrodes being made of the same metal, the first of said sensing electrodes being at least near the closed end of said flowpath member and the second of said sensing electrodes being spaced above the first sensing electrode nearer the open end of said flowpath member with both electrodes so disposed as to be contacted by said flowable liquid media entering or leaving said flowpath member; (d) means for reciprocating said reciprocating element in said flowpath member; (e) means for admitting of said flowable liquid media to said flowpath member; and (f) means coupled to said first and second electrodes to detect and amplify any

alternating component of any electrical current flowing between said first and second spaced sensing electrodes; the improvement which comprises:

a guard electrode located inside said tubular flowpath spaced above said second sensing electrode, said second sensing electrode being located below the guard electrode which itself is located at or near the top of said tubular flowpath and above the first sensing electrode which itself is located at or near the bottom of said tubular flowpath with all three electrodes spaced from one another, said guard electrode circling the interior insulating wall of said tubular flowpath means but spaced sufficiently from the block-like reciprocating element to allow free flow of said flowable liquid medium between said guard electrode and said block-like reciprocating element, said guard electrode being electrically grounded and made of the metal as are the said two sensing electrodes, and said guard electrode having a surface and body large enough with respect to the surfaces and bodies of the two sensing electrodes so that its electrical resistivity is negligible with respect to the electrical resistivities of the sensing electrodes in order to shield the sensing electrodes from any galvanic cell-type electrical current which would flow through said flowable liquid media between these sensing electrodes and any external metals different in composition from the sensing electrodes in contact with the flowable liquid.

4,297,641

SERODYNAMIC SYSTEM EMPLOYING AN ADJUSTABLE PHASE SHIFTING CIRCUIT


Fred Sterzer, Princeton, N.J., assignor to RCA Corporation, New York, N.Y.

Filed Sep. 28, 1979, Ser. No. 80,103

Int. Cl.³ H03B 19/00

U.S. Cl. 328—15

1 Claim



1. A phase shifting circuit for producing an output signal adjustably shifted in phase relative to an input alternating frequency signal, comprising in combination:

a first signal path having an input terminal receptive of said input signal and having a first output terminal, said first signal path comprising a first adjustable level signal translating device including a first level control terminal, said device being positioned intermediate said input terminal and output terminal;

a second signal path having an input terminal receptive of said input signal and having a second output terminal, said second signal path comprising a second adjustable level signal translating device including a second level control terminal;

means for effecting a 90° relative phase shift in one signal path relating to the other;

means coupled to said first and second output terminals for producing said output signal which is the vector sum of the signals appearing at said first and second output terminals;

means coupled to said first and second control terminals for respectively applying control signals thereto for controlling the level of signal produced respectively at said first and second output terminals for controlling the phase of said output signal by any amount between 0° and 90° relative to said input signal;

means for selectively shifting said output signal by N·90°

where N=0, 1, 2, or 3 for thereby effecting a 0° to 360° phase shift relative to said input signal; and

means for providing to said phase shifting circuit a signal at a given frequency f_1 , means for continuously and uniformly shifting the phase of said signal in said phase shifting circuit between 0° and 360° and means responsive to said output signal from said phase shifting circuit for producing a signal at frequency f_2 where f_2 differs from f_1 by an amount determined by the rate at which said phase shift occurs in said phase shifting circuit.

4,297,642

OFFSET CORRECTION IN OPERATIONAL AMPLIFIERS


Gary L. Baldwin, Palo Alto, and James L. McCreary, Los Gatos, both of Calif., assignors to Bell Telephone Laboratories, Incorporated, Murray Hill, N.J.

Filed Oct. 31, 1979, Ser. No. 89,851

Int. Cl.³ H03F 1/00

U.S. Cl. 330—9

8 Claims



1. Apparatus including an operational amplifier (101) which is adapted to receive an input signal, said apparatus comprising: means (104, 106) connected with the output of said operational amplifier and operable to cancel d.c. offset in said amplifier,

CHARACTERIZED BY means (110) for operating said cancelling means in response to zero crossings in said input signal.

4,297,643

NOISE OBVIATING ELECTRONIC SIGNAL COUPLING MEANS


Thomas J. Pearson, Jr., Rte. 1, Box 18, Coffeeville, Ala. 36524

Filed Nov. 13, 1979, Ser. No. 93,541

Int. Cl.³ H03F 1/00

U.S. Cl. 330—178

2 Claims



1. An improved coupling means for transferring an electronic signal from the output of any stage of gain to the input of the succeeding stage for obviating the noises as the signal is transferred, said coupling means including a circuit means for extending between the output of the stage of gain and the input of the succeeding stage and capacitor electrically mounted in the circuit means, wherein the improvement comprises: a resistor electrically mounted in the circuit means between the output of the stage of gain and the capacitor with no other electrical components or connections being placed between said resistor and the capacitor, said resistor being in series with the capacitor.

4,297,644

AMPLIFIER WITH CROSS-OVER CURRENT CONTROL


Adel A. A. Ahmed, Clinton Township, Hunterdon County, N.J., assignor to RCA Corporation, New York, N.Y.

Filed Nov. 23, 1979, Ser. No. 96,739

Int. Cl.³ H03F 3/30

U.S. Cl. 330—264

9 Claims



1. A complementary symmetry amplifier comprising: first, second, third, and fourth field-effect transistors, each having respective source and drain electrodes defining the ends of its conduction channel and each having a gate electrode, said first and third transistors being of P-channel type and said second and fourth transistors being of N-channel type; means for applying an operating potential between the source electrodes of said first and second transistors; input and output terminals; respective means for connecting the drain electrodes of said first and second transistors to said output terminal; means for connecting the gate electrode of said first transistor to said input terminal; means for connecting the gate electrode of said second transistor to said input terminal; means for regulating the current flows through the conduction channels of said third and fourth transistors to a prescribed value substantially independent of said operating potential; and means responsive to the resulting gate-to-source voltages of said third and fourth transistors for applying respective potentials proportional to said resulting gate-to-source voltages as the respective gate-to-source voltages of said first and second transistors.

4,297,645

AUTOMATIC GAIN CONTROL CIRCUIT COMPRISING A CIRCUIT FOR COMPARING A MODULATED SIGNAL WITH AN ENVELOPE DETECTED SIGNAL


Kouichi Tanaka, Tokyo, and Kiyoshi Amazawa, Ohmiya, both of Japan, assignors to Nippon Electric Co., Ltd. and Clarion Co., Ltd., both of Tokyo, Japan

Filed Sep. 20, 1979, Ser. No. 77,222

Int. Cl.³ H03G 3/30

U.S. Cl. 330—280

5 Claims



1. An automatic gain control circuit to be coupled to an amplifier having a controllable gain and responsive to an input signal and a gain control signal for amplifying said input signal

with the gain automatically controlled in compliance with said gain control signal to produce an amplified signal, said automatic gain control circuit being responsive to said amplified signal for producing said gain control signal, wherein the improvement comprises:

first means having a first reference level and responsive to said amplified signal for superposing said amplified signal on said first reference level to produce a first signal of a first level variable in compliance with said amplified signal;

second means having a second reference level and responsive to said amplified signal for carrying out envelope detection of said amplified signal to produce a second signal of a second level variable in response to said amplified signal with said second variable level offset by said second reference level so that said second variable level traverses said first variable level during discrete intervals of time;

third means for comparing said first signal with said second signal to produce a pulse signal during said discrete intervals; and fourth means for smoothing said pulse signal to produce said gain control signal.

4,297,646

CURRENT MIRROR CIRCUIT


James J. LoCascio, Mesa, and Robert B. Jarrett, Tempe, both of Ariz., assignors to Motorola Inc., Schaumburg, Ill.

Filed Jan. 25, 1980, Ser. No. 115,522

Int. Cl.³ H03F 3/14

U.S. Cl. 330—288

10 Claims



1. A current mirror, comprising: current turn around means for supplying first, second and third currents at respective outputs, said current turn around means being coupled to a terminal which is adapted to receive an operating potential; current source means coupled to a first one of said outputs of said current turn around means for supplying an input current thereto; output electron control means having a first, a second and a control electrode, said first electrode being connected to a second one of said outputs of said current turn around means, said second electrode being coupled to an output terminal of the current mirror, said control electrode being coupled to said current source means; and first electron control means having first, second, third and control electrodes, said first electrode being coupled to a third one of said outputs of said current turn around means, said second electrode being coupled to said output terminal of the current mirror, and said third and control electrodes each being coupled to said first electrode of said output electron control means.

4,297,647

HYBRID INTEGRATED CIRCUIT AND A METHOD FOR PRODUCING THE SAME

Masahiro Akiyama; Katuzo Kaminishi, and Yasushi Kawakami, all of Tokyo, Japan, assignors to OKI Electric Industry Co., Ltd., Tokyo, Japan


Filed Jun. 15, 1979, Ser. No. 48,849

Claims priority, application Japan, Jun. 16, 1978, 53/81657[U]

Int. Cl.³ H03F 3/14; H05K 5/02

U.S. Cl. 330—307

9 Claims



6. A hybrid integrated circuit comprising of a ceramic substrate, a conductive pattern attached on the ceramic substrate for providing electronic components including an inductor and a connection terminal, a lead frame having a closed frame and being connected to said conductive pattern; gold layer plated on said conductive pattern and the lead frame; electronic components mounted on said conductive pattern; and said electronic components and said conductive pattern being wired with one another, characterized in that the lead frame has an inductance pattern projected inside of the closed frame, and the inductance pattern on the lead frame overlaps on the corresponding inductance pattern of the conductive pattern on the ceramic substrate.

4,297,648

MICROWAVE FREQUENCY DIVISION BY PHASE LOCKED LOOPS

Trevor W. Tucker, and William D. Cornish, both of Ottawa, Canada, assignors to Her Majesty the Queen in right of Canada, as represented by the Minister of National Defence, Ottawa, Canada


Filed Aug. 3, 1979, Ser. No. 63,171

Claims priority, application Canada, Aug. 31, 1978, 310452

Int. Cl.³ H03L 7/00

U.S. Cl. 331—1 R

2 Claims



1. Apparatus for producing a stable microwave frequency signal comprising an rf oscillator for supplying microwave signals of frequency f_1 above 2 GHz to an output terminal of the apparatus and to an input of a microwave analog frequency divider, said frequency divider dividing said microwave signals by N, where N is an integer, and a phase detector having one input connected to receive the output of said frequency divider, said phase detector having another input fed by a reference oscillator of frequency f_2 , wherein $f_2 = f_1/N$, said phase detector having an output connected to a control input of said rf oscillator whereby the output frequency of said rf oscillator is adjustable to equal Nf_2 , said frequency divider comprising resonant circuit means, comprising at least two

microwave transmission lines and a corresponding number of non-linear reactance elements, for receiving said microwave signal and for providing a balanced output signal of a frequency $1/N$ times the input signal, said microwave transmission lines comprising terminated microstrip transmission lines and said non-linear reactance elements comprising varactor diodes located at the terminated ends of the microstrip transmission lines, said frequency divider further comprising a balun electromagnetically coupled to said microstrip transmission lines.

4,297,649

MALFUNCTION DETECTOR FOR A GROUP OF CYCLICALLY INTERCONNECTED PHASE-LOCKED OSCILLATORS

Anes Sbuelz, and Francesco Marchelli, both of Milan, Italy, assignors to Societa Italiana Telecomunicazioni Siemens S.p.A., Milan, Italy


Filed Jun. 29, 1979, Ser. No. 53,280

Claims priority, application Italy, Jul. 3, 1978, 25268 A/78

Int. Cl.³ H03L 7/00

U.S. Cl. 331—2

5 Claims



1. A circuit arrangement for generating a multiplicity of oscillations locked in phase with one another, comprising a multiplicity of cyclically interconnected generator stages each comprising:

- a phase-controlled oscillator with a synchronizing input and with a feedback loop between an output and another input thereof;
- a multiplexer with a first input connected to the output of the oscillator of the immediately preceding stage, a second input connected to said feedback loop and an output connected to said synchronizing input; and
- a control circuit with inputs connected in parallel with those of said oscillator to said feedback loop and to the output of said multiplexer, respectively, said control circuit being responsive to a disparity between the frequencies of feedback and synchronizing oscillations appearing on its said inputs for switching only the multiplexer of the immediately succeeding stage to said second input thereof with concurrent emission of an alarm signal indicative of a malfunction of the associated oscillator.

4,297,650

PHASE LOCKED LOOP CARRIER RECOVERY CIRCUIT WITH FALSE LOCK PREVENTION

Saburo Shinmyo, Tokyo, Japan, assignor to Nippon Electric Co., Ltd., Tokyo, Japan

Filed Dec. 27, 1979, Ser. No. 108,249

Claims priority, application Japan, Dec. 27, 1978, 53-164883

Int. Cl.³ H03L 7/10

U.S. Cl. 331—11

6 Claims

1. A carrier recovery apparatus comprising an input terminal for receiving a phase-modulated carrier, a voltage-controlled oscillator for generating a variable frequency oscillation in response to a control signal, a first phase comparator for pro-

4,297,652

INJECTION-TYPE SEMICONDUCTOR LASER

Izuo Hayashi, and Hiroo Yonezu, both of Tokyo, Japan, assignors to Nippon Electric Co., Ltd., Tokyo, Japan



Filed Oct. 9, 1979, Ser. No. 83,043

Claims priority, application Japan, Oct. 11, 1978, 53-125585

Int. Cl.³ H01S 3/19

U.S. Cl. 331—94.5 H

10 Claims



response to said modulated carrier, a second phase comparator for providing a comparison output representative of the phase difference between the output of said first phase comparator and said clock signal, and means for superimposing the low-frequency component of the output of said second phase comparator on one of the outputs of said first phase comparator and said loop filter.

4,297,651

METHODS FOR SIMULTANEOUS SUPPRESSION OF LASER PULSATIONS AND CONTINUOUS MONITORING OF OUTPUT POWER

John C. Dymont, Kanata, and Kiuchi D. Chik, Nepean, both of Canada, assignors to Northern Telecom Limited, Montreal, Canada


Filed Aug. 23, 1979, Ser. No. 68,887

Int. Cl.³ H01S 3/19

U.S. Cl. 331—94.5 H

6 Claims U.S. Cl. 331—94.5 S

10 Claims



1. A semiconductor laser device adapted for suppression of transient relaxation oscillations and sustained spontaneous pulsations, the device comprising:

- A semiconductor ship having a substrate, a first confining layer, a waveguide layer, an active layer and a second confining layer, the active layer and the second confining layer formed as a laser mesa, the mesa having a metal contact thereon, a corresponding surface area of the substrate also having a metal contact thereon, the waveguide being of higher refractive index than an underlying layer, the waveguide layer having one end of non-linear configuration, the waveguide being longer at a central region than at peripheral regions at said one end, and tapering gradually to zero thickness at said one end whereby collimated light directed along the waveguide towards said one end is reflected back therefrom and is returned to the laser active layer, such reflection occurring between 0.3 and 2 centimeters from the laser active layer.

4,297,653

HYBRID SEMICONDUCTOR LASER/DETECTORS


Donald R. Scifres, and Wolfgang E. Stutius, both of Los Altos, Calif., assignors to Xerox Corporation, Stamford, Conn.

Filed Apr. 30, 1979, Ser. No. 34,238

Int. Cl.³ H01S 3/19

U.S. Cl. 331—94.5 S

10 Claims



1. A hybrid semiconductor laser/detector on a single semiconductor substrate, said laser having front and rear light emitting facets and being mounted on the surface of said substrate, an optical detector integral to said substrate, said detector being adjacent to one of said light emitting facets to detect a small portion of the light emitted therefrom, a bias circuit connected to supply an operating current to said laser, said detector being connected to said bias circuit to provide a feedback signal proportional to the detected light from said one facet to adjust and maintain said operating current to provide a predetermined optical power output level and means formed on said substrate to enhance the light collecting efficiency of said detector, said laser mounted on a metalized region formed on said substrate surface, the elevation of said mounted laser being below said detector, a portion of said metalized region extending on said substrate surface beyond said mounted laser, said extended portion acting as a reflector and constituting said substrate formed means.

4,297,654

CRYSTAL OSCILLATOR INCLUDING A MOS-CAPACITOR

Joachim Goerth, Lüneburg, Fed. Rep. of Germany, assignor to U.S. Philips Corporation, New York, N.Y.

Division of Ser. No. 929,442, Jul. 31, 1978, Pat. No. 4,214,252.


This application Jan. 10, 1980, Ser. No. 111,136

Claims priority, application Fed. Rep. of Germany, Aug. 6, 1977, 2735529; Jun. 15, 1978, 2826192

Int. Cl.³ H03B 5/36

U.S. Cl. 331-108 D

4 Claims



1. A semiconductor device comprising a semiconductor substrate of first conductivity type; a semiconductor layer of second conductivity type overlying said semiconductor substrate; an insulating layer on said semiconductor layer; a conductive layer formed on said insulating layer; a highly doped zone of said second conductivity type formed in the surface of said semiconductor layer; said highly doped zone, said insulating layer, and said conductive layer forming a MOS-capacitor; a further zone of said first conductivity type entirely surrounding said highly doped zone and interposed between said highly doped zone and said semiconductor layer; and a separate connection electrode at each of said highly doped zone, said further zone, and said semiconductor layer; an emitter follower transistor being connected in parallel to the barrier layer capacitance between said highly doped zone and said further zone; and said device further comprising a tunable oscillator including a differential amplifier, a current distributor controlled by a control voltage and being disposed in a branch of said differential amplifier, a phase shifting element including said MOS-capacitor, and a feedback path present between said phase-shifting element and input to said differential amplifier, said feedback path comprising a quartz oscillator and said emitter follower transistor, said barrier layer capacitance between said highly doped zone of said second conductivity type and said further zone of said first conductivity type being connected in parallel to the emitterbase current path of said emitter follower transistor, and the connection point between additional barrier layer capacitances of said device being connected to a supply voltage.

4,297,655

TEMPERATURE COMPENSATED CRYSTAL OSCILLATOR

Shuzo Fujii, and Yoshikatsu Sato, both of Tokyo, Japan, assignors to Nippon Electric Co., Ltd., Tokyo, Japan

Filed Oct. 15, 1979, Ser. No. 84,693

Claims priority, application Japan, Oct. 20, 1978, 53-129260; Dec. 15, 1978, 53-156128


Int. Cl.³ H03B 5/04, 5/36

U.S. Cl. 331-116 R

6 Claims

1. In a temperature compensated crystal oscillator comprising an oscillator section having a crystal resonator and an amplifying element, and a temperature compensating section for compensating for a change in the oscillator frequency due to a temperature change of said oscillator section, the improvement wherein said temperature compensating section comprises: a low temperature compensating circuit comprising a

series circuit including a fixed capacitor connected in series with said crystal resonator and a diode, and a thermistor for



applying a forward-bias temperature-dependent voltage to a connection point between said fixed capacitor and said diode.

4,297,656

PLURAL FREQUENCY OSCILLATOR EMPLOYING MULTIPLE FIBER-OPTIC DELAY LINE


Jing-Jong Pan, Melbourne, Fla., assignor to Harris Corporation, Melbourne, Fla.

Filed Mar. 23, 1979, Ser. No. 23,394

Int. Cl.³ H03B 5/00, 17/00

U.S. Cl. 331-135

7 Claims



6. An oscillator comprising: a gain producing element having an input and an output; a plurality of feedback paths connected between said input and said output of said gain producing element; and frequency determining means within said feedback paths comprising an electrical-to-optical transducer producing a light signal in response to the output of the gain producing element, a plurality of optical fibers responsive to light signals from said transducer, each respective optical fiber having a respectively different phase delay, an optical-to-electric transducer responsive to the outputs of said optical fibers, means for causing the light signals from said electrical-to-optical transducer to be coupled simultaneously through each of said optical fibers, and means for coupling light signals from each of said optical fibers simultaneously to said optical-to-electric transducer.

4,297,657

CLOSED LOOP TEMPERATURE COMPENSATED FREQUENCY REFERENCE

Marvin E. Frerking, Cedar Rapids, Iowa, assignor to Rockwell International Corporation, El Segundo, Calif.

Filed Oct. 29, 1979, Ser. No. 88,908


Int. Cl.³ H03L 1/02

U.S. Cl. 331-176

6 Claims

1. A closed loop temperature compensated frequency reference, comprising: a controllable oscillator means for generating a first frequency; a reference oscillator means for generating a second frequency; a comparator means for comparing the first frequency means with the second frequency means to obtain a composite signal; a sensor means for measuring the temperature of the reference oscillator means and to provide a temperature signal representative of the measured temperature; and

error signal generator means for generating a control signal to control the controllable oscillator means and the first



frequency thereby, the control signal being generated by error signal generator means in response to the composite signal and the temperature signal.

4,297,658

3DB WAVEGUIDE DIRECTIONAL COUPLER

Leo Treczka, Munich, Fed. Rep. of Germany, assignor to Spinnler GmbH Elektrotechnische Fabrik, Munich, Fed. Rep. of Germany


Filed Feb. 1, 1980, Ser. No. 117,472

Claims priority, application Fed. Rep. of Germany, Feb. 2, 1979, 2904054

Int. Cl.³ H01P 5/18

U.S. Cl. 333-113

11 Claims



1. A 3dB waveguide directional coupler, comprising: first and second rectangular waveguides, each of which has a longitudinal axis and each of which extends parallel to its respective said longitudinal axis; each said wave guide comprising four side walls, said four side walls of each said waveguide including two wide side walls having a first width and two narrow side walls having a second width less than said first width; one said wide side wall of said first waveguide and one said wide side wall of said second waveguide being adjacent each other; said adjacent wide side walls each having an aperture formed therein such that the interiors of said waveguides communicate through said aperture; and means disposed in said waveguides and cooperating with said aperture in such a manner that when energy is input from one end of said first waveguide in a direction along said first axis and toward said aperture, substantially all of said input energy is transmitted to said second waveguide via said aperture and is propagated along said second axis, substantially equal amounts of said transmitted energy being propagated along said second axis in a first longitudinal direction and along said second axis in a second longitudinal direction opposite said first longitudinal direction, the energy in each of the longitudinal directions along said second axis being substantially greater than any energy along said first axis propagating away from said aperture.

4,297,659

CRYSTAL FILTER STRUCTURE

Horst G. Augst, Skärholmen, Sweden, assignor to Telefonaktiebolaget L M Ericsson, Stockholm, Sweden


Filed Dec. 10, 1979, Ser. No. 102,032

Claims priority, application Sweden, Dec. 20, 1978, 7813107

Int. Cl.³ H03H 9/50, 9/56, 9/58, 9/60

U.S. Cl. 333-191

6 Claims



5. A crystal filter structure of the polyolithic type comprising an elongated planar support means, first, second and third quartz plates, each including two acoustically coupled resonators, each resonator being defined by first and second electrodes on the first and second sides, respectively of a portion of a quartz plate, means for mounting said first and third resonators on one side of said planar support means, means for mounting said second resonator on the other side of said planar support means axially intermediate said first and second resonators, the first electrode of the first resonator of the first quartz plate being adapted to receive a signal, means for connecting the first electrode of the second resonator of said first quartz plate to the first electrode of the first resonator of said second quartz plate, and means for connecting the first electrode of the second resonator of said second quartz plate to the first electrode of the first resonator of said third quartz plate, and said first electrode of the second resonator of said third quartz plate being adapted to transmit a signal.

4,297,660

ELECTRIC CIRCUIT USING SURFACE ACOUSTIC WAVE DEVICE

Hideharu Ieki, Nagaokakyo, and Seiichi Arai, Muko, both of Japan, assignors to Murata Manufacturing Co., Ltd., Japan


Filed Dec. 7, 1979, Ser. No. 101,279

Claims priority, application Japan, Dec. 14, 1978, 53-173215[U]; Dec. 26, 1978, 53-182526[U]

Int. Cl.³ H03H 9/64, 9/42

U.S. Cl. 333-194

7 Claims



1. An electric circuit including a surface acoustic wave device, comprising: a surface acoustic wave device including an input transducer and an output transducer formed on a piezoelectric substrate, each of said transducers having a respective pair of terminals, and the impedance of each of said transducers as measured across said respective pair of terminals having a respective resistive component and a respective capacitive component; and impedance conversion circuit means, including first capacitor means having one end connected to one terminal of one of said pairs of terminals and inductor means having one end connected to a second end of said first capacitor means and having a second end connected to the other terminal of said one of said pairs of terminals, the value of said first capacitor means being such that the impedance

measured across said ends of said inductor means has a larger resistive component than said resistive component of said transducer impedance measured across said one of said pairs of terminals.

4,297,661

FERRITE SUBSTRATE MICROWAVE FILTER

Ronald E. Stegens, Brookeville, Md., assignor to Communications Satellite Corporation, Washington, D.C.


Filed Dec. 27, 1979, Ser. No. 108,248

Int. Cl.³ H01P 1/203, 1/215, 3/08

U.S. Cl. 333-204

8 Claims

MICROSTRIP ON FERRITE SUBSTRATE



1. A microwave filter comprising:

- a pair of conductors;
- a non-magnetized ferrite material located between said pair of conductors, said ferrite material having a saturation magnetization $4\pi M_s$ chosen to substantially absorb frequencies below a critical frequency f_{CRIT} such that

$$f_{CRIT} \approx 2.8 \cdot 4\pi M_s$$

to produce a first filter characteristic, said ferrite material substantially absorbing frequencies below said critical frequency, wherein said first filter characteristic provides (i) high attenuation below said critical frequency, (ii) low attenuation above said critical frequency, and (iii) low reflected-to-incident power ratio above and below said critical frequency.

4,297,662

GAS-TIGHT-HIGH-FREQUENCY PERMEABLE WINDOW ARRANGEMENT IN A COAXIAL LINE, PARTICULARLY FOR TRAVELING WAVE TUBES

Franz Gross, Loerrach; Gerit Boehme, Germering; Wolf Wiehler, Neubiberg, and Wilhelm Bibracher, Otterloh, all of Fed. Rep. of Germany, assignors to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany


Filed Jan. 24, 1980, Ser. No. 115,011

Claims priority, application Fed. Rep. of Germany, Feb. 28, 1979, 2907808

Int. Cl.³ H01P 1/08, 5/02

U.S. Cl. 333-252

4 Claims



1. A gas-tight, high-frequency permeable window arrangement between a coaxial line on an input side and a coaxial line on an output side, each of the coaxial lines having respective

inner and outer conductors, particularly for traveling wave tubes, comprising:

- a ceramic hollow cylinder arranged between the input side and the output side, said cylinder surrounding the inner conductor of the input side in the area of its transition to the coaxial line of the output side and connected as a continuation of the outer conductor of the coaxial line of the input side; and
- a membrane connected gas-tight to the inner conductor of the coaxial line at the input side and to the inner conductor of the coaxial line of the output side.

4,297,663

CIRCUIT BREAKER ACCESSORIES PACKAGED IN A STANDARDIZED MOLDED CASE


Raymond K. Seymour, Plainville, and Frank H. Murphy, West Hartford, both of Conn., assignors to General Electric Company, New York, N.Y.

Filed Oct. 26, 1979, Ser. No. 88,714

Int. Cl.³ H01H 73/06, 73/08

U.S. Cl. 335-20

8 Claims



1. An accessory for installation within the molded case enclosure of an automatic electric circuit breaker, said accessory comprising, in combination:

- A. a molded insulative case consisting of at least two parts secured together to substantially enclose the accessory operating components;
- B. first mounting provisions provided externally on said case for mounting said accessory within the circuit breaker enclosure;
- C. second mounting provisions preformed in said case parts;
- D. third mounting provisions preformed in said case parts;
- E. at least one auxiliary switch stationarily mounted by said second mounting provisions within said case; and
- F. an actuating arm for said switch mounted within said case by said third mounting provisions for movement between said first and second positions, said arm protruding through an opening in said case into operative relation with the movable contacts of the circuit breaker, said arm being propelled between its first and second positions in response to movement of the breaker movable contacts between their open and closed circuit positions.

4,297,664

ELECTROMAGNETIC OVERCURRENT TRIPPING DEVICE WITH ADJUSTABLE ARMATURE AIR GAP

Manfred Küger, Wolfgang Nawrot, and Bernhard Preuss, all of Berlin, Fed. Rep. of Germany, assignors to Siemens Aktiengesellschaft, Berlin and Munich, Fed. Rep. of Germany

Filed Mar. 28, 1979, Ser. No. 24,511

Claims priority, application Fed. Rep. of Germany, Apr. 5, 1978, 2815130

Int. Cl.³ H01H 69/01

U.S. Cl. 335-176


5 Claims

1. In an electromagnetic overcurrent tripping device for electric circuit breakers having a stationary magnetic yoke with associated pole surfaces, an armature which is supported for motion relative to the pole surfaces, and means for changing

ing the spacing between the pole surfaces and the armature to provide different tripping current levels, the improvement comprising:

- the means for changing the spacing comprising a removable armature stop member and a support means for fixing the

farther from the transformer axis to level off current density per winding.



position of the removable stop member relative to the pole surfaces,

the removable stop member being mounted on the support means in one of a number of predetermined positions to establish a corresponding spacing of the armature relative to the support means.

4,297,665

DOUGHNUT-TYPE TRANSFORMER FOR RESISTANCE BUTT WELDING

Boris E. Paton, ulitsa Chkalova, 41-a, kv. 26; Vladimir K. Lebedev, ulitsa Engelsa, 25, kv. 12; Sergei I. Kuchuk-Yatsenko, ulitsa Filatova, 1/22, kv. 47; Vasily A. Sakharnov, ulitsa Solomenskaya, 41, kv. 93; Boris A. Galyan, ulitsa Lenina, 88/92, kv. 110, and Stanislav D. Dobrovolsky, ulitsa Zhukova, 22, kv. 7, all of Kiev, U.S.S.R.


Filed May 14, 1980, Ser. No. 149,734

Claims priority, application U.S.S.R., Aug. 6, 1979, 2789203

Int. Cl.³ H01F 27/08, 27/28

U.S. Cl. 336-60

3 Claims



1. A doughnut-type transformer for resistance butt welding comprising:

- an annular core,
- an array of annularly disposed transformer sections, each including:
- a primary winding composed of turns each of which shaped as a sector in the plane of the transformer cross-section, and
- a cooled secondary winding composed of a turn shaped as a sector in the plane of the transformer cross-section, and placed between the turns of said primary winding so that the turns of said primary winding with their lateral sides are near the lateral sides of each turn of said secondary winding,
- each turn of both said primary winding and said secondary winding of each said transformer section having an opening forming part of an annular space with said annular core extending therethrough so that the geometric center of each said winding is displaced from the geometric center of said annular core in the cross-sectional plane thereof, the geometric center of said annular core being

4,297,666

SLOW-BLOWING FUSE USING ZINC-MANGANESE ALLOY LINK

Nasrollah Asdollahi, Witten, Fed. Rep. of Germany, assignor to Wickmann Werke AG, Fed. Rep. of Germany


Filed Jan. 26, 1979, Ser. No. 6,779

Claims priority, application Austria, Feb. 3, 1978, 757/78

Int. Cl.³ H01H 85/06

U.S. Cl. 337-163

8 Claims



1. A slow-blowing fuse having a fusible conductor and a carrier body, said fusible conductor comprising a wire wound on said carrier body and said wire consisting of a zinc-manganese alloy which contains 0.005% to 2% by weight of manganese.

4,297,667

FUSIBLE ELECTRIC CABLE PROTECTOR


Frederick J. Kozacka, South Hampton, N.H., assignor to Gould Inc., Rolling Meadows, Ill.

Filed Apr. 2, 1980, Ser. No. 136,629

Int. Cl.³ H01H 85/16

U.S. Cl. 337-251

3 Claims



1. A fusible electric cable protector including a casing of electric insulating material defining a first internal space, a pair of terminal elements each located on one end of said casing and closing said casing, fusible elements conductively interconnecting said pair of terminal elements, a granular arc-quenching filler inside said first space, a pair of connector elements each conductively connected to one of said pair of terminal elements and each extending axially outwardly from one of said pair of terminal elements for connecting said cable protector into an electric circuit, at least one of said pair of connector elements having a cylindrical outer surface wherein the improvement comprises a second internal space defined by said one of said pair of connector elements having a cylindrical outer surface, said second internal space being filled with a granular arc-quenching filler, said second internal space and said first internal space communicating with each other by a passageway extending through one of said pair of terminal elements, and said one of said pair of connector elements having a cylindrical surface being closed at the axially outer end thereof to preclude loss of said granular arc-quenching filler.

4,297,668

THERMOSTAT WITH BRACKET FOR ATTACHMENT TO A TUBULAR MEMBER


Donald E. Place, Mansfield, Ohio, assignor to Therm-O-Disc, Incorporated, Mansfield, Ohio

Filed Feb. 13, 1980, Ser. No. 121,138

Int. Cl.³ H01H 37/04

U.S. Cl. 337—365

10 Claims



1. A thermostat assembly for attachment to a tubular member which comprises a thermostat having a heat-conductive bottom and containing thermal responsive means therein; and means for mounting the thermostat on a tubular member which comprises a base portion adjacent to the bottom of the thermostat and which is adapted to fit against and extend longitudinally along the tubular member and which has a longitudinal opening therein to permit the bottom of the thermostat to directly contact the tubular member, a pair of thermostat-retaining portions which extend from the base portion on either side of the thermostat and which have means for attaching to the thermostat, and a clip portion which extends from the base portion and which is adapted to extend around the tubular member to tightly attach the base portion to the tubular member.

4,297,669

THERMAL CUT-OUTS AND TO THE METHOD OF ASSEMBLING A MULTIPLICITY OF SUCH THERMAL CUT-OUTS

James A. Gale, Warminster, England, assignor to Kenneth E. Beswick Ltd., Somerset, England


Filed Aug. 27, 1979, Ser. No. 70,028

Claims priority, application United Kingdom, Mar. 8, 1978, 34926/78

Int. Cl.³ H01H 37/76, 69/00

U.S. Cl. 337—407

6 Claims



1. A thermal cut-out which is adapted to open an electrical circuit in response to an excessive rise in temperature associated with the circuit protected by said cut-out, said cut-out comprising a hollow body made from electrically insulating

material and having an opening permitting access to the interior of the body, a pair of contact members projecting into the body through said opening and having their inner ends disposed within the body, one of said contact members being bent and hooked over an adjacent bent end portion of the other contact and in surface-to-surface contact therewith, a plug of insulating material being disposed within the opening in the body between said contacts, so as to close said opening and stress the contacts to a condition in which they are biased apart, surfaces of said contact members being retained in engagement by an element bearing with surface contact against one side of one of the contacts as long as its temperature has not risen to a predetermined temperature, said element being made of such a material that having reached said predetermined temperature it deforms and permits the contacts to open.

4,297,670

METAL FOIL RESISTOR

Benjamin Solow, North Hollywood, Calif., assignor to Angstrom Precision, Inc., Hagerstown, Md.


Division of Ser. No. 803,291, Jun. 3, 1977, Pat. No. 4,176,445.

This application May 24, 1979, Ser. No. 41,928

Int. Cl.³ H01C 10/00

U.S. Cl. 338—195

15 Claims



1. A resistor having an insulating substrate, and a metal foil circuit pattern attached to the substrate, wherein at least a portion of the metal foil circuit is reduced in thickness by acid etching to adjust the value of the resistor.

4,297,671

TANDEM INSERT MOLDED ELECTRICAL CONTROLS AND PROCESS FOR PRODUCING SAME


Thomas W. Flanders, Edwardsburg, Mich., assignor to CTS Corporation, Elkhart, Ind.

Filed Jun. 11, 1980, Ser. No. 158,597

Int. Cl.³ H01C 10/50

U.S. Cl. 338—200

20 Claims



1. A process for performing multiple electrical control functions, comprising the steps of aligning linearly at least three insert molded electrical control means within an impact construction, said construction comprising a front plate having side straps extending the cumulative length of said control

means to encompass them longitudinally and disposed exteriorly of said control means, each of said straps including finger ends, and a rear plate, mechanically securing the finger ends to the rear plate positioned against the endmost one of said aligned control means, said control means comprising a variable resistance control, a power control, and a momentary switch, each of which is insert molded and relatively changeable in their relative alignment within said construction, a hollow concentric insulator shaft for operation of said controls, and a longitudinal metallic shaft journaled within said concentric insulator shaft, and rotating the longitudinal metallic shaft which extends through the respective control means.

4,297,672

EARLY WARNING SYSTEM FOR APPROACHING TRANSPORTATION VEHICLES


Russell L. Fruchey, Copley, and Daniel E. Kupar, Barberton, both of Ohio, assignors to D.E.W. Line, Inc., Hiram, Ohio

Filed Feb. 4, 1980, Ser. No. 118,517

Int. Cl.³ G08G 1/12

U.S. Cl. 340—23

21 Claims



1. A radio signaling system for providing advanced warning of an approaching transportation vehicle to passengers within a plurality of predesignated pickup regions, comprising:

transmitting system means on the vehicle for generating a low-frequency-modulated radio-frequency signal including

transmitter means for generating a radio-frequency signal, a plurality of low-frequency generators for generating a plurality of low-frequency modulation signals, and, modulator and control circuit means for modulating said radio-frequency signal with each said plurality of low-frequency modulation signals in a preselected sequence, including

analog switch means for receiving each of said plurality of low-frequency modulation signals and selectively gating the same to said transmitter means,

modulation-pulse time control means for generating an output signal to said analog switch means to control the sequence of and rate at which said low-frequency modulation signals are gated by said analog switch means and generating a cycle-complete output signal after all said plurality of low-frequency modulation signals have been gated to said transmitter means by said analog switch means, and

transmitter operation time control means for selectively gating power to said transmitter means and thereby controlling the duration said transmitter means generates said radio-frequency signal, and receiving said cycle-complete output signal and generating an output signal for controlling said modulation-pulse time control means, said output signal for controlling said modulation-pulse time control means disabling the same upon receipt of said cycle-complete output signal and subsequently enabling the operation of said modulation-pulse time control means in synchroniza-

tion with said gating of power to said transmitter means; and,

receiving system means in proximity to a predesignated pickup region for providing an alarm signal only when the transportation vehicle is approaching the predesignated pickup region with which that particular receiving system means is associated including

receiver means receiving said low-frequency-modulated radio-frequency signal and providing a demodulated output signal,

a plurality of low-frequency decoders receiving said demodulated output signal each of which is tuned to the frequency of one of said plurality of low-frequency generators for providing an output signal upon receipt of that low-frequency signal,

synchronous detector means receiving said output signals from all said plurality of low-frequency decoders and providing an alarm output signal only upon receipt of said output signals from said plurality of low-frequency decoders in said preselected sequence, and,

alarm means receiving said alarm output signal from said synchronous detector means and providing an advanced warning of the approaching vehicle to passengers within the predesignated pickup region with which said receiving system is associated.

4,297,673


OMNIDIRECTIONAL SPEED COCKPIT DISPLAY
David L. Green, Potomac, Md., assignor to Pacer Systems, Inc., Burlington, Mass.

Filed Mar. 14, 1978, Ser. No. 886,485

Int. Cl.³ B64D 45/00; G08G 5/02

U.S. Cl. 340—27 NA

28 Claims



1. Omnidirectional speed cockpit display apparatus for helicopters and the like comprising a drum having markings of lateral speed and forward and rearward speed having shaft means connected to drive means for supporting and turning the drum, a first zero point mark on the drum, and a safe flight envelope marked on the drum, and at least partially surrounding said first zero point; a face plate with a second zero point mark, for indicating forward and rearward speed with the drum a lateral flight indicator means moving left or right of said second zero point as a means cooperating with lateral speed markings and the safe flight envelope for indicating lateral speed and safety of lateral speed.

4,297,674

PASSIVE SECURITY DEVICE

Richard C. Merten, Omaha, Nebr., assignor to Jubilee Manufacturing Co., Omaha, Nebr.

Filed Oct. 18, 1979, Ser. No. 86,117

Int. Cl.³ B60R 25/10


U.S. Cl. 340—63

11 Claims

1. A passive security device, for use with vehicles having an electrical system including a starter, and an ignition switch having "on" and "accessory" contacts, said device comprising: first means for connecting said device to the electrical system;

detection and alarm means including trigger means for detecting voltage variations and producing an electrical

signal in response thereto, said trigger means being connected to said first means, generating means for converting said electrical signal into a square wave signal, said generating means being connected to said trigger means, siren means for sounding an alarm, and activating means connecting said generating means and said siren means and being responsive to said square wave signal to activate said siren means;



first passive means for arming said detection and alarm means;
second passive means for arming an ignition cut-out circuit; and
disarming means connected between said first means and said first and second passive means.

4,297,675

SUPPLEMENTAL RIGHT TURN SIGNAL FOR SEMITRAILERS


Nolan R. Rubottom, 1832 W. Corak, West Covina, Calif. 91790, and Jerry W. Fine, 2105 Vallecito Dr., Hacienda Heights, Calif. 91745

Filed Jan. 21, 1980, Ser. No. 113,740

Int. Cl.³ B60Q 1/00

U.S. Cl. 340—107

5 Claims



1. A supplemental right turn signal unit for mounting on a semitrailer having the bed of the chassis thereof supported by spaced transverse structural beams and having a pair of landing gears attached to the bottom of the bed of said chassis inward of the front end thereof, said signal unit comprising:

- a vertically disposed rectangular sheet metal support member having its marginal top, bottom and side edges bent bak at right angles to the surfaces thereof;
- a socket for a light bulb mounted on the upper right portion of the surface of said support member;
- a translucent cover enclosing said light bulb, said cover having portions of the face thereof made non-translucent to define an arrow pointing to the right side of the support member, and said cover having a translucent cylindrical sidewall disposed normal to the surface of said support member whereby light emitted by said bulb can radiate sidewardly and downwardly to illuminate indicia includ-

ing a pictorial indication of the impending danger provided on the left and bottom portion of the surface of said support member;

- a bracket having an angular intermediate portion with a horizontal lower end portion and an elongated horizontal upper end portion; and
- attachment means for attaching said support member beneath the bed of the semitrailers so that the right side thereof is aligned with the sidewall of said semitrailer by attaching the top marginal edge thereof on a transverse structural beam located to the rear and adjacent to the pair of landing gears and by attaching the horizontal lower end portion of said bracket to the bottom marginal edge of said support member and the horizontal upper end portion of said bracket to the next forward transverse structural beam.

4,297,676

MARK SIGNAL AMPLIFIER

Shigeru Moriya, Hoya; Nobuo Hamamoto; Kazuo Ichino, both of Tokyo, and Kanji Ozawa, Akishima, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed Dec. 26, 1979, Ser. No. 107,087

Claims priority, application Japan, Dec. 22, 1978, 53-157417

Int. Cl.³ G06K 9/32

U.S. Cl. 340—146.3 AG

7 Claims



1. A mark signal amplifier comprising: first means for obtaining the maximum and minimum values of a mark signal from a detector as detected by scanning an electron beam over a mark area formed on a sample;
- second means for obtaining a peak-to-peak value of an amplitude of the detected mark signal from said maximum and minimum values; and
- third means for supplying an output signal of a constant amplitude in accordance with said peak-to-peak value of said amplitude independently of fluctuations in said detected mark signal,

wherein said first means comprises means for amplifying said detected mark signal, an analog-to-digital converter for converting said detected mark signal to a digital signal, comparators for comparing the output digital signals from said analog-to-digital converter with the contents of a maximum value register for storing the maximum value of said detected mark signal and with the contents of a minimum value register for storing the minimum value of said detected mark signal, and means to renew the respective contents of the maximum and minimum value registers in accordance with the comparators outputs, whereby said maximum and minimum values of said detected mark signal are obtained.

4,297,677

PERSONAL AMBIENT SOUND REFERENCED ANNUNCIATOR


John S. Lewis, 8525 Wolftrap Rd., Vienna, Va. 22180; Edmond P. DiGiannantonio, 1638 Wateredge La., Reston, Va. 22070, and Howard R. Boyle, Alexandria, Va., assignors to John S. Lewis, Vienna and Edmond P. DiGiannantonio, Reston, both of, Va.

Filed Dec. 10, 1979, Ser. No. 101,735

Int. Cl.³ G08B 13/00

U.S. Cl. 340—148

9 Claims



1. A personal annunciator responsive to present ambient sound conditions in the immediate vicinity of the user who is unable to recognize changes in ambient sound level, comprising:

- (a) a small portable housing,
- (b) an indicator connected to said housing,
- (c) ambient sound receiving means disposed in the housing for picking up the continually varying present ambient sound in the vicinity of the housing and producing a variable amplitude signal reflecting the varying amplitude of the present ambient sound,
- (d) activating signal generating means disposed in the housing and connected to the output of the ambient sound receiving means for receiving the variable amplitude signal therefrom and producing an activating signal only when an abrupt amplitude increase occurs within a fixed predetermined interval, said amplitude being greater by a fixed predetermined increment than the varying sound level received immediately theretofore to which it is referenced, and
- (e) the activating signal generating means is connected to the indicator, which on receipt of the activating signal gives the user a non-audible type warning signal which he can readily recognize.

4,297,678

AIRCRAFT SAFETY ALARM SYSTEM


Byung H. Lee, Suite 203, 1810 Craig Rd., St. Louis, Mo. 63101

Filed Jan. 29, 1979, Ser. No. 7,195

Int. Cl.³ C08B 3/10

U.S. Cl. 340—328

5 Claims



1. An aircraft safety alarm system for sounding an alarm that the aircraft engine may be started, comprising speaker alarm

means located outside the aircraft and being connected in an electrical circuit to a switch that is automatically activated by the aircraft operator prior to operating the aircraft, said electrical circuit being connected to a battery and including an alarm circuit and a timer device, said timer device being automatically activated by said switch to operate said alarm circuit for a predetermined time period to activate the speaker means, said timer device becoming de-activated after said predetermined time period to de-energize said alarm circuit and said speaker alarm means, said alarm circuit further including a base oscillator circuit and an audio oscillator circuit to produce an intermittent sound through the speaker alarm means, said audio oscillator circuit being operated at a frequency different than the base oscillator circuit, and audio amplifying means for amplifying the audio tone through the speaker alarm means, said speaker alarm means further including means to produce an intermittent sound that is both a safety alarm as well as a travel alert.

4,297,679

CIRCUIT FOR CONTINUOUS CONVERSION OF SIGNALS INTO DIGITAL MAGNITUDES

Arie Arbel, Haifa, Israel, and Rainer Kurz, Jülich, Fed. Rep. of Germany, assignors to Kernforschungsanlage Jülich Gesellschaft mit beschränkter Haftung, Jülich, Fed. Rep. of Germany


Continuation of Ser. No. 541,931, Jan. 17, 1975. This application Jul. 25, 1978, Ser. No. 927,842

Claims priority, application Fed. Rep. of Germany, Jan. 17, 1974, 2402072

Int. Cl.³ H03K 13/02

U.S. Cl. 340—347 AD

12 Claims



1. An apparatus for converting an analog current or voltage signal into a digital representation of that signal, the apparatus consisting of a plurality of stages to receive the signal, each stage comprising an analog-to-digital converter and each stage preceding the last stage having a group of differential amplifiers with input thereof connected in parallel with the analog-to-digital converter and designed to fold the signal received a plurality of times and a selector control unit receiving the signal from the group and transmitting the signal to the next succeeding stage, each analog-to-digital converter being designed to output a plurality of digits representing the binary magnitude of the encoded signal with the digits representing the next most significant binary magnitudes from the preceding stage, the final stage being an analog-to-digital converter designed to output digits representing the least significant binary magnitudes of the encoded signal, all of the digits together forming a complete binary magnitude representation of the encoded signal.

4,297,680

ANALOG WAVEFORM DIGITIZER


Henricus Koeman, Edmonds, Wash., assignor to John Fluke Mfg. Co., Inc., Mountlake Terrace, Wash.

Filed Aug. 3, 1979, Ser. No. 63,521

Int. Cl.³ H03K 13/02

U.S. Cl. 340—347 AD

10 Claims



1. A waveform digitizer for digitizing analog signals comprising:

reference voltage means for sequentially producing a series of digitally derived reference voltages one-at-a-time, each reference voltage having a different voltage value; comparison means coupled to said voltage reference means for sequentially comparing each of said series of digitally derived reference voltages with an analog signal whose waveform is to be digitized during a series of comparison sequences and producing a comparison pulse each time said reference voltage and the analog signal voltage cross during said comparison sequences;

timing means starting at the beginning of each comparison sequence for continuously producing a digital time signal during each comparison sequence; and,

combining means coupled to said comparison means and said timing means for receiving said comparison pulses and said digital time signal and developing a digital word each time a comparison pulse is received, said digital word having a portion related to the value of the digitally derived reference voltage produced by said reference voltage means and a position related to the digital time signal present when said comparison pulse is received.

4,297,681

ELECTROLUMINESCENT RING LIGHT ADAPTER FOR AIRCRAFT INSTRUMENTS


Arnold D. Dirksen, 2974 State Rte. 725, Spring Valley, Ohio 45370

Filed Aug. 11, 1980, Ser. No. 177,241

Int. Cl.³ G01D 11/28

U.S. Cl. 340—366 F

9 Claims



1. In an aircraft indicating instrument having means for displaying information to be viewed externally of the instrument through a substantially planar transparent cover having a peripheral edge and inner and outer surfaces, said cover being arranged in front of the displaying means and means mounted to said instrument for illuminating said displaying means, the

improvement wherein said illuminating means comprises an electroluminescent lamp arranged externally of said instrument, means for removably mounting said electroluminescent lamp in non-sealed, confronting relation with the outer surface of said transparent cover and means connected to said electroluminescent lamp for supplying an electric field thereto, said removable mounting means comprising an adapter element surrounding and in overlapping relation with the peripheral edge of the planar transparent cover, said adapter element having a recess on the side thereof confronting the peripheral edge of the planar transparent cover, said electroluminescent lamp being disposed in said recess such that, upon supply of an electric field to said electroluminescent lamp, said lamp directly illuminates the information displaying means of said instrument.

4,297,682

FLEXIBLE CONVEX DIAPHRAGM SOUND REPRODUCING DEVICE


Barry L. Spletzer, Fremont, Mich., assignor to Gerber Products Company, Fremont, Mich.

Filed Jan. 7, 1980, Ser. No. 110,160

Int. Cl.³ G08B 3/00

U.S. Cl. 340—384 E

9 Claims



1. Apparatus for reproducing the sound produced when a convex, thin, flexible diaphragm is flexed comprising:

an electromagnetic coil; means for mounting a relatively thin electrically conductive flexible plate adjacent to one end of said coil; said coil and said mounting means configured to allow said flexible plate to flex; and means, electrically coupled to said coil and to a power source having a first terminal and a second terminal, for selectively energizing said coil whereby said flexible plate deflects and vibrates thereby reproducing said sound.

4,297,683

VANDAL ALARM SYSTEM FOR PARKING METERS

Ralph R. Roberts, 740 Hillsdale Ave., Hillsdale, N.J. 07642


Continuation-in-part of Ser. No. 23,014, Mar. 22, 1979,

abandoned. This application Mar. 6, 1980, Ser. No. 127,589

Int. Cl.³ G08B 19/00, 25/00

U.S. Cl. 340—539

8 Claims



1. A parking meter vandal alarm apparatus which includes a

radio transmitter secured therein and adapted to send a radio signal in response to an electrical actuation signal to a radio receiver, said signal indicated on a monitor, said apparatus including: (a) a parking meter of conventional construction including a housing and having at least one access door to be opened and closed by a key or the like; (b) a battery within said parking meter housing; (c) a first switch in association with said access door and disposed in a normally open condition, any slight movement toward the opening of the access door causing the switch to close and produce a first electrical actuation signal produced by said battery; (d) a first timer in association with said first switch and having a timed period of selected duration whereby the closing of said first switch causes the electrical actuation signal to continue for said selected time period beyond the closing and then opening of said first switch; (e) a first tilt switch normally in an "open" condition and contained within the parking meter housing and disposed so as to be actuated to a closed condition and produce a second electrical actuation signal produced by said battery when the housing is displaced to an attitude of about twenty to forty-five degrees; (f) a second timer associated with said first tilt switch, said timer delaying the produced signal from the first tilt switch in the closed actuated condition for a selected period of time, this time delay enabling a jarring, shaking and the like of the meter to occur without producing an electrical actuation; (g) a second tilt switch which is within the housing and support, said second tilt switch in a normally "open" condition and being activated to a closed condition when the housing and/or a support is tilted to more than forty-five degrees producing an electronic signal produced by said battery indicating a tilt of the housing beyond said designated angle, such an angle indicating vandalism which may also include cutting of the support; (h) a conducting means in association with this second tilt switch connected to feed a produced signal to and through said first timer and producing an electrical signal persisting for a determined period of time after actuation; (i) a radio transmitter of a relatively short range powered by said battery and arranged so that when a switch is closed an actuation signal produced by said battery is supplied to the transmitter and at least one frequency signal is broadcast from the transmitter, and (j) a radio receiver at a distance from the transmitter and having a constant "on" power source and having means for monitoring said signals.

4,297,684

FIBER OPTIC INTRUDER ALARM SYSTEM


Charles D. Butter, Cologne, Minn., assignor to Honeywell Inc., Minneapolis, Minn.

Filed Mar. 26, 1979, Ser. No. 24,125

Int. Cl.³ G08B 13/22, 13/10

U.S. Cl. 340—557

8 Claims



1. Intruder detector apparatus comprising:

intruder sensor means consisting of a length of multimode optic fiber to be positioned in an area under surveillance for intruders;

means directing a source of coherent light into said optic fiber for transmittal through said length of fiber, said

transmitted coherent light emanating from the end of the fiber in a generally cone-shaped beam; and, light detector means receiving at least a portion of the coherent light beam emanating from said fiber, the cross section of the light beam exhibiting an interference pattern of light intensity, and which interference pattern changes when said sensor means is deformed by the presence of an intruder.

4,297,685

APPARATUS AND METHOD FOR SLEEP DETECTION


Edward C. Brainard, II, Marion, Mass., assignor to Environmental Devices Corporation, Marion, Mass.

Filed May 31, 1979, Ser. No. 44,268

Int. Cl.³ G08B 21/00

U.S. Cl. 340—575

13 Claims



1. Apparatus for detecting the onset of sleep in a human being, said apparatus comprising:

means, including a temperature responsive sensor, for measuring the temperature within the auditory canal of said human being;

differentiator means interconnected with said temperature measuring means for generating the time rate of change of said temperature; and

comparator means for producing an output signal when said time rate of change of said temperature exceeds a predetermined value.

4,297,686

WATER DETECTION DEVICE


M. Dale Tom, R.D. #1, Norwich, Ohio 43767

Filed Oct. 1, 1979, Ser. No. 80,658

Int. Cl.³ G08B 21/00; F16K 23/00

U.S. Cl. 340—604

4 Claims



1. A resistive liquid detection and shut-off system comprising:

means for detecting liquid drips, flows and trickles, but not liquid beads, on a floor area where liquid damage could result, said means including an elongated sensor comprising a flexible plastic tape with an adhesive backing and having a surface thereof with a pair of conductive metal strips thereon spaced apart in a dimension perpendicular to the dimension of elongation of said tape;

detection circuit means operatively connected to said elongated sensor for measuring resistance changes in said elongated sensor;

a solenoid-operated water shut-off valve;

output circuitry means operatively connected to said detec-

tion circuit means and said water shut-off valve for activating said water shut-off valve in response to predetermined resistivity changes in said elongated sensor; a battery for providing power for said detection circuit means, solenoid valve operator, and said output circuitry means; and battery monitoring circuitry means operatively connected to said battery and said shut-off valve for monitoring the strength of said battery and for operating said shut-off valve if said battery strength drops below a predetermined value.

3. A resistive liquid detection system comprising: means for detecting liquid drips, flows and trickles, but not liquid beads, on a floor area where liquid damage could result, said means including an elongated sensor comprising a flexible plastic tape with an adhesive backing and having a surface thereof with a pair of conductive metal strips spaced apart in a dimension perpendicular to the dimension of elongation of said tape, said tape being formed in at least two pieces;

a connector for interconnecting said two pieces of said sensor tape, said connector comprising: a body of electrically insulating material having two pairs of electrically connected electrical terminals mounted thereon, the terminals of each pair being spaced apart a distance corresponding to the spacing of said conductive metal strips; means defining a pair of slots in said body, each for receipt of a piece of said tape for allowing said conductive metal strips of said tape to contact said terminals within said body; and adhesive for maintaining each piece of said tape in contact with said connector body;

detection circuit means operatively connected to said elongated sensor for detecting changes in the resistivity thereof;

an alert means for alerting an individual to resistivity changes in said sensor means;

output circuitry means operatively connected to said detection circuit means and said alert means for activating said alert means in response to predetermined resistivity changes in said elongated sensor; and

power means for providing electrical current for powering said circuitry means and said alert means.

4,297,687

LEAK DETECTION APPARATUS

Joe E. Fuzzell, Peoria, Ill., assignor to Caterpillar Tractor Co., Peoria, Ill.


PCT No. PCT/US80/00180, § 371 Date Feb. 22, 1980, § 102(e) Date Feb. 22, 1980, PCT Pub. No. WO81/02484, PCT Pub. Date Sep. 3, 1981

PCT Filed Feb. 22, 1980, Ser. No. 130,488

Int. Cl.³ G08B 21/00

U.S. Cl. 340—626

15 Claims



1. A leak detection apparatus (18) for a pressurized system having a source of pressurized fluid (12) and a distribution system (14) having at least one outlet (100) for said pressurized fluid, said distribution system (14) being maintained under pressure approximately equal to the pressure of the pressurized fluid in said source comprising:

means (38, 138, 62, 162) for sealing the source of pressurized

fluid (12), said means (38, 138, 62, 162) including a movable member (62, 162) seatable on a seat (68, 168) positioned between said source of pressurized fluid and said distribution system (14);

rod means (60, 160, 260) carried by said movable member (62, 162) and being movable with said movable member (62, 162); and

means (82, 182, 295) operatively conditioned by movement of said movable member (62, 162) and of said rod means (60, 160, 260) for signalling a pressure differential between said source of pressurized fluid (12) and said distribution system (14).

4,297,688

PHOTOELECTRIC SMOKE SENSING AND ALARMING DEVICE

Takao Kakigi, Tokyo, Japan, assignor to Cybernet Electronics Corp., Kawasaki, Japan

Continuation-in-part of Ser. No. 107,041, Dec. 26, 1979, which is a continuation of Ser. No. 942,186, Sep. 14, 1978, abandoned.


This application Jan. 2, 1980, Ser. No. 109,145

Claims priority, application Japan, Sep. 30, 1977, 52-131414[U]

Int. Cl.³ G08B 17/10

U.S. Cl. 340—630

1 Claim



1. A photoelectric smoke sensing and alarming device of a type having a pulse generator, a chamber, a light emitting element disposed in said chamber and adapted to emit a light beam in the form of pulses in cooperation with said pulse generator, and a light-receiving element disposed in said chamber and adapted to receive the light from said pulses of light beam, so as to sense the presence of smoke in said chamber through a detection of scattering of said light beam caused in said chamber by said smoke, comprising:

an amplifier having gain control and connected to said light-receiving element for producing an output upon reception of light by said light-receiving element;

a threshold detecting comparator for producing a pulse output when the output of said amplifier exceeds a predetermined threshold level;

a delay circuit coupled to the pulse generator for producing a delayed pulse output in synchronism with the output of the comparator;

a gate circuit having a pair of inputs respectively connected to the output of the comparator and the output of the delay circuit for delivering a first output upon simultaneous receipt of output pulses from said comparator and said delay circuit and for producing a second output upon the occurrence of the delayed output pulse of the delay circuit in the absence of the output pulse of said comparator; and

a flip-flop circuit coupled to said gate circuit and adapted to be set by the first output from said gate circuit, wherein an alarm is generated over a time length which is at least as long as the time between successive of said pulses generated by said pulse generator, only when at least n ($n > 2$) successive of said first outputs are delivered by said gate circuit to said flip-flop circuit, said second output of said gate circuit being used to reset the flip-flop circuit in the absence of successive first output signals from said gate circuit.

4,297,689

PERSONNEL-CARRIED DOSIMETER


Manuel Shaw, Bel Air, and Imbrie Thatcher, Chatsworth, both of Calif., assignors to Interscan Corporation, Chatsworth, Calif.

Filed Jan. 8, 1980, Ser. No. 110,359

Int. Cl.³ G01N 27/46, 27/54; G08B 23/00

U.S. Cl. 340—632

17 Claims



1. An electrochemical sensing cell for use in a dosimeter, comprising:

a housing including a body having a planar base and upright sides extending therefrom to define an interior region and a lid emplaceable atop said sides to enclose said interior region,

a zigzag recess in said base opening into said interior region, together with a pair of openings through said body at the respective ends of said recess, said openings serving respectively as inlet and outlet ports for the flow of gas through said cell,

a generally planar sensing element disposed in said body interior region atop said base, gas entrant to the cell through said inlet port flowing through said zigzag recess in contact with said sensing electrode along substantially the entire length of said recess, said gas then exiting through said outlet port,

a reference electrode and an electrolyte also disposed within said interior region, the electrical current developed across said sensing and reference electrodes in the presence of a certain contaminant in said gas being indicative of the concentration of that contaminant in the gas,

an annular seal between said base and said sensing electrode and surrounding said zigzag recess, said seal limiting the flow of gas between said base and said sensing electrode to within a perimeter defined by said seal, and

a flow channel extending from said inlet port along the exterior of said base and thence through at least one of said walls and through said lid, gas thereby being supplyable to said recess via said channel from a location atop said lid.

6. A dosimeter comprising:

an electrochemical sensing cell and means for enabling the entry of a gas sample into said sensing cell, the current from said cell indicating the concentration of a certain contaminant species in said gas sample,

a "high level" alarm circuit means, connected to said cell, for providing a first alarm signal when the current from said cell indicates that the present concentration of said certain contaminant species exceeds a first threshold limit value, and

a "time weighted average" alarm circuit means, also connected to said cell and operative over a certain extended time duration, for providing a second alarm signal when the current from said cell, effectively integrated over a time interval less than or equal to said certain duration, indicates that the time weighted average concentration level of said contaminant species has exceeded a second

threshold limit value during that interval, said "time weighted average" alarm circuit means including:

a frequency converter, cooperatively connected to said cell, for providing an output pulse signal having a frequency proportional to the current from said cell, and a counter connected to count the pulses from said frequency converter, said second alarm signal being produced when the count of said counter reaches a preset value within said certain extended time duration.

4,297,690

EARTHQUAKE ALARM SYSTEM


Gerald E. Baker, 23018 Arlington Ave., Torrance, Calif. 90501

Continuation-in-part of Ser. No. 933,166, Aug. 14, 1978. This application Mar. 5, 1980, Ser. No. 127,428

Int. Cl.³ G08B 21/00

U.S. Cl. 340—690

3 Claims



1. An earthquake alarm comprising:

a member having a referenced support at one end, a mass attached at the opposite end of said member a fixed distance from said referenced support,

said mass being supported to have a preferred vertical position for a movement in a lateral direction only,

adjustable mechanical detecting means for limiting the impulse lateral movement of said mass without changing the fixed distance of said mass from said referenced support,

said mass being cylindrical and containing an opening at the lowermost end for accepting a vertically aligned adjustable probe attached to said mechanical detecting means and adapted to be selectively located in said opening without touching said mass, and

electrical means connecting said mechanical detecting means with an audio generating device for translating selected impulse movement of said mass into an audible signal.

4,297,691

FIGURE DISPLAYING DEVICE

Kazuyuki Kodama, Kokubunji; Kunihiro Okada; Takeyuki Endoh, both of Hinode, and Yasutaka Shibuya, Tachikawa, all of Japan, assignors to Hitachi, Ltd. and Hitachi Denshi Kabushiki Kaisha, both of Tokyo, Japan

Filed Aug. 29, 1979, Ser. No. 70,821

Claims priority, application Japan, Aug. 30, 1978, 53-104944


Int. Cl.³ G06F 3/14; G09B 9/00

U.S. Cl. 340—723

4 Claims

1. A figure displaying device comprising display means for displaying information of a figure, first generation means for generating a brightness signal which corresponds to the figure information to be displayed, second generation means for generating a brightness modulation signal which varies continuously in at least one direction within a predetermined first region on a display screen of said display means, third generation means for generating a frequency characteristic control signal which varies continuously in at least one direction within a predetermined second region on said display screen which is in overlapping relationship with at least a portion of said first region, modulation and control means connected to said first, second and third generation means for brightness-modulating the brightness signal from said first generation means in accordance with the signal from said second genera-

tion means and for controlling a frequency characteristic of the brightness signal from said first generation means in accordance with the signal from said third generation means to selectively vary the composition of frequency components in




the brightness signal and thereby affect the resolution of the displayed image, and means for applying the modulated and controlled brightness signal from said modulation and control means to said display means.

4,297,692
SEGMENT FAILURE DETECTOR FOR DIGITAL
DISPLAY

Lawrence C. Maier, Middlebury, Vt., assignor to Simmonds Precision Products, Inc., Tarrytown, N.Y.
Continuation of Ser. No. 18,209, Mar. 7, 1979, abandoned. This application Apr. 8, 1980, Ser. No. 138,474
Int. Cl.⁷ G06F 3/14; G09F 9/32

U.S. Cl. 340—715 **7 Claims**




1. A digital display device including:
 - a power source connected to drive the digital display device;
 - a plurality of character-forming display segments;
 - a driver circuit connected to the plurality of display segments to selectively energize the plurality of display segments;
 - a failure detection circuit connected to the plurality of display segments to detect the failure of any of the plurality of display segments to energize; and to generate a blanking signal indicative of display segment failure;
 - an override circuit to override the blanking signal;
- wherein the driver circuit is connected to the failure detection circuit to receive the blanking signal such that the driver circuit de-energizes the plurality of display segments on receipt of the blanking signal; and
- wherein the override circuit is connected to the driver circuit such that the timer circuit overrides the blanking

signal to permit energizing of the plurality of non-failed display segments by the driver circuit.

4,297,693
APPARATUS FOR DISPLAYING GRAPHICS SYMBOLS
 Robert Parsons, St. Neots, England, assignor to Texas Instruments Incorporated, Dallas, Tex.
 Continuation of Ser. No. 806,415, Jun. 14, 1977, abandoned.
 This application Feb. 2, 1979, Ser. No. 8,722
 Claims priority, application United Kingdom, Jun. 21, 1976,
 25726/76

U.S. Cl. 340—744 Int. Cl.³ G06F 3/14 10 Claims



1. Apparatus for controlling the display of information which is built up line by line on a raster-type display in response to digital coded data and mode control signals selectively occurring during individual lines of said display, there being a plurality of modes including a graphics mode in which data signals can be displayed during a respective line of said display, the mode control signals indicating the mode in which subsequent data signals are to be displayed during at least part of that line but not themselves generating a display, the apparatus including graphics symbol store means for providing in the graphics mode, in parallel, signals representative of the specified graphics symbol until a further data signal is received, parallel to serial converter means for securing the parallel signals from the graphics symbol store means and in response thereto producing in serial form, signals characteristic of the graphics symbol to be displayed, and control logic means for changing the contents of the graphics symbol store means in response to a graphics symbol signal and to cause said store means to continue to produce the parallel signals already stored in the graphics symbol store means for the duration of a mode control signal when the said mode control signal occurs in place of a data signal during the display of graphics symbols and thereby avoid a blank space in said display resulting from occurrence of said mode control signal.

4,297,694

SYMBOL GENERATOR FOR A GRAPHIC CONSOLE

Philippe Matherat, Paris, France, assignor to Thomson-CSF,
Paris, France


Filed May 16, 1979, Ser. No. 39,260
Claims priority, application France, May 18, 1978, 78 14765
Int. Cl.³ G06F 3/153

U.S. Cl. 340—750 18 Claims

1. A symbol generator for tracing, on a sensitive medium, alphanumeric characters and the like, said characters being formed on a grid comprising $l \cdot p$ adjacent columns, each column comprising $m \cdot q$ points, said generator comprising:
- (a) first and second input busses, each connectable to an external control means (MPU), said first bus comprising a data channel (MPDB) and said second bus comprising an address channel (MPAB);
 - (b) means for supplying a clock signal (CKIN) to control the timing of said symbol generator;
 - (c) a character memory (65), connected to said first and

second input busses, said memory having IX memory calls for each character and further comprising:

- (d) a writing pointer circuit (66) connected to said first and second input busses, said pointer circuit comprising first (X) and second (Y) up/down counters connected to said clock signal supplying means, each of said counters having first (ENX) and second (ENY) enabling inputs and a command input (U/DY) for setting the counter to count up or count down, the outputs of said up/down counters




- respectively comprising the X and Y address inputs for the means driving said sensitive medium; and
- (e) a writing circuit (61), connected to said first and second input busses and to said clock signal supplying means, said writing circuit including means, responsive to the factors P and Q, for programming said writing circuit, said writing circuit having first, second, and third outputs respectively corresponding and connected to the first and second enabling inputs and the command input of said writing pointer circuit, and first and second address outputs respectively corresponding and connected to the first and second addressing inputs of said character memory.

4,297,695
ELECTROCHROMIC DISPLAY DEVICE
Richard C. Marshall, Harpenden, England, assignor to Xerox
Corporation, Stamford, Conn.

Filed Dec. 17, 1979, Ser. No. 103,910
Claims priority, application United Kingdom, Dec. 28, 1978,
50066/78

U.S. Cl. 340—752 Int. Cl.³ G02F 1/17 5 Claims



1. A display device including apparatus for electrically addressing a material in matrix fashion wherein each individual point in the matrix is addressable to produce a local change in an optical characteristic of the material by the application at that point of two electrical signals, the improvement comprising

first and second matrix addressing means for sequentially applying first and second electrical signals to said matrix, the combination of which is sufficient to cause said local change,

said first matrix addressing means for selectively applying

said first signals to groups of rows and columns of said matrix defining submatrices,
said second matrix addressing means for selectively applying said second signals to individual rows and columns in said submatrices to select at least one of said individual points in said submatrices and produce said local change thereat.


4,297,696

**COLOR UNIFORMING DRIVE IN AN
ELECTROCHROMIC DISPLAY DEVICE**

Sadakatsu Hashimoto, Nara, Japan, assignor to Sharp Kabu-
shiki Kaisha, Osaka, Japan

Filed Apr. 23, 1980, Ser. No. 143,015
Claims priority, application Japan, Apr. 24, 1979, 54-50968
Int. Cl.³ G06F 3/14

U.S. Cl. 340-785 4 Claims



1. In a drive system for driving an electrochromic display cell during a coloration period, and a bleaching period, said display cell having a memory period when said drive system is not driving said electrochromic display cell, said drive system including an external power source, said cell including an electrochromic material and a predetermined number of display segments, different combinations of said display segments defining different desired display patterns, said drive system comprising:


coloration means for conducting coloration operations by applying a coloration voltage to selected ones of said display segments during said coloration period; holding means for maintaining colored segments in an electrically opened state for a predetermined period of time after completion of said coloration period; and communication means for electrically connecting said colored segments with each other during said memory period after completion of operation of said holding means.

4,297,697
POWER SUPPLY METHOD FOR LIQUID CRYSTAL
DISPLAY

Yoshihiro Mitsui, Shiojiri, Japan, assignor to Kabushiki Kaisha
Suwa Seikosha, Tokyo, Japan

Filed Dec. 29, 1978, Ser. No. 974,402
Claims priority, application Japan, Dec. 29, 1977, 52/159275
Int. Cl.³ G08B 5/36

U.S. Cl. 340—813 3 Claims



1. A power supply for a liquid crystal display, comprising:
DC power source means for delivering a source voltage
larger than the driving voltage for driving said display,

said power source means having first and second reference terminals;
voltage regulator means coupled to said power source means for receiving said source voltage and in response thereto supplying a regulated output voltage having a negative temperature characteristic, said regulated output voltage corresponding to the driving voltage of said display, said voltage regulator means including first and second output terminals for outputting said regulated voltage;
logic circuit means coupled intermediate said first and second output terminals and said liquid crystal display for receiving said regulated output voltage and in response thereto selectively driving said liquid crystal display;
a transistor coupled in series between said second reference terminal and said second output terminal;
said voltage regulator means including constant-current circuit means coupled intermediate said first reference terminal and said transistor, and a plurality of series-connected forward biased diode means coupled between said first reference terminal and said transistor, each of said diode means having the same forward voltage and negative temperature characteristic, said constant-current circuit supplying said forward current to said plurality of series-connected diode means, said regulated output voltage being substantially determined by multiplying the forward voltage of one of said diode means by the number of said diode means, said negative temperature characteristic of said regulated output voltage being substantially determined by multiplying the negative temperature characteristic of said forward voltage of one of said diode means by the number of diode means.

4,297,698


360 DEGREE LINEAR VARIABLE PHASE TRANSFORMER

Michael A. Pauwels, Kalamazoo, and Abraham L. Poot, Portage, both of Mich., assignors to Pneumo Corporation, Boston, Mass.

Filed Nov. 2, 1977, Ser. No. 847,938
Int. Cl.³ G08C 19/06; H01F 21/06

U.S. Cl. 340—870.32

38 Claims



1. A displacement to phase transducer, comprising at least three primary means for producing in response to alternating current excitation alternating magnetic fluxes, combining means for producing an output flux having a phase dependent on the relative positions of said combining means and said primary means, at least one of said primary means and combining means being movable relative to the other, and secondary means for producing an output AC electrical signal having a phase corresponding to the phase of said output flux, and wherein each of said primary means includes a plurality of full layers of circumferentially wound turns and at least one partial layer of circumferentially wound turns so arranged to provide a substantially linear relation between the phase of said output flux with respect to the relative positions of said combining means and said primary means.

4,297,699 RADAR DRILL GUIDANCE SYSTEM


James C. Fowler, Burke; Steven D. Hale, Vienna, both of Va., and Theodore E. Moser, Rockville, Md., assignors to Ensco, Inc., Springfield, Va.

Filed Oct. 24, 1979, Ser. No. 87,811

Int. Cl.³ G01S 13/02

U.S. Cl. 343—5 NA

19 Claims



10. A radar guidance system for determining subterranean distances including a source of electromagnetic pulses, a transmitting means connected to said source of electromagnetic pulses to transmit said electromagnetic pulses into the earth, a receiving means positioned in spaced relationship to said transmitting means to receive electromagnetic energy which returns to said receiving means following the reflection of said electromagnetic pulses from various geological discontinuities within the earth, a control circuit means connected to both said source of electromagnetic pulses and said receiving means for controlling both the transmission of said electromagnetic pulses from said transmitting means and the reception of said electromagnetic energy by said receiving means, said control circuit means being positioned in spaced relationship relative to said transmitting means such that said transmitting means is positioned intermediate said control circuit means and said receiving means, said radar guidance system also including a casing which encloses said source of electromagnetic pulses, said transmitting means, said receiving means and said control circuit means, said casing having a shielding element mounted around the inner surface thereof to prevent direct electromagnetic coupling between said transmitting means and said receiving means.

4,297,700

METHOD AND APPARATUS FOR MEASURING DISTANCES

Georges Nard, Nantes; Jean Rabian, Ste. Luce, and Michel Rouaud, Thouare, all of France, assignors to Societe d'Etudes, Recherches et Constructions Electroniques Sercel, Carquefou, France

Continuation of Ser. No. 517,157, Oct. 22, 1974, abandoned.


This application Jan. 26, 1977, Ser. No. 762,729

Claims priority, application France, Oct. 23, 1973, 73 37740

Int. Cl.³ G01S 13/80

U.S. Cl. 343—6.5 R

14 Claims



1. A ranging method, comprising the following steps:

at a first location;
transmitting during a first time-period a first high frequency wave train comprising a carrier signal of predetermined frequency being phase-reversal modulated according to a first repetitive chain of a known pseudo-random sequence of binary elements,
at a second location:
receiving the first high-frequency wave train and correlating the first repetitive chain of the known pseudo-random sequence, said first chain of the sequence being modulated on said first wave train, with a local second repetitive chain of the same pseudo-random sequence, said second repetitive chain being shifted with respect to time so as to substantially coincide with the first repetitive chain received, and
transmitting during a second time-period a second high frequency wave train comprising a carrier signal of the same predetermined frequency being phase-reversal modulated according to the second local repetitive chain of the pseudo-random sequence thus shifted, said second time-period extending after and disjointed from said first time-period,
at a third location:
receiving the second high-frequency wave train and correlating the second repetitive chain of the known pseudo-random sequence, said second chain of the sequence being modulated on said second wave train, with a third local repetitive chain of the same pseudo-random sequence, said third repetitive chain being shifted with respect to time until it is caused to coincide with the second repetitive chain received, and
sensing the time shift between the thus shifted third repetitive chain of the pseudo-random sequence and a fourth repetitive chain of the pseudo-random sequence, and sequentially repeating these steps with each of the first and second transmission time-periods of the first and second wave trains being disjointed.

4,297,701


RANGEFINDER USING EXPANDED TIME DELAY
Lance Henriques, New York, N.Y., assignor to John D. Angleman, Brookside, N.J.

Filed Aug. 8, 1979, Ser. No. 64,390

Int. Cl.³ G01S 13/78

U.S. Cl. 343—6.5 LC

7 Claims



1. A system for determining the distance between a first point and a second point comprising:
(a) first transceiver means located at the first point for transmitting a first signal burst on a given frequency and for receiving signals on the given frequency;
(b) second transceiver means located at the second point for receiving the first signal burst on the given frequency and for retransmitting a second signal burst on the given frequency in response to the first signal burst; and
(c) timing means for measuring the period of time between the transmission of the first signal burst by the first transceiver means and the receipt of the second signal burst by the second transceiver means, whereby the period of time is directly proportional to the distance between the first

point and the second point, said timing means being comprised of an integrator including a capacitor, a means for linearly charging the capacitor at a charge rate during the period of time, a means for linearly discharging at a slower rate than said charge rate the capacitor after the period of time, a threshold detector for detecting when the state of charge of the capacitor reaches a predetermined value;
(d) and a microprocessor for measuring an amount of time that the capacitor is charged to a value of at least said predetermined value, the amount of time corresponding to said distance between the first point and the second point.

4,297,702

POLYPHASE CODED FUZZING SYSTEM


Irven S. Carnes, Chelmsford, Mass., assignor to Raytheon Company, Lexington, Mass.

Filed May 24, 1978, Ser. No. 909,098

Int. Cl.³ G01S 13/26

U.S. Cl. 343—7 PF

2 Claims



1. In a radar fuzzing system for use in a guided missile, such system being adapted periodically to transmit a radio frequency signal modulated in accordance with a predetermined polyphase code and, after reception of an echo signal, to process such signal in a bank of similar correlator/mixers, each one of such correlator/mixers comprising:

- first and second dual gate field effect transistors;
- means, operative during selected successive intervals of time between the transmission of each predetermined polyphase code, for alternately biasing the first and second dual gate field effect transistors into a conducting state;
- means for applying a local oscillator signal to one of the gates of each one of the first and the second dual gate field effect transistors;
- means for applying the echo signal directly to the second gate of one of the dual gate field effect transistors and for reversing the phase of such signal and applying the resulting signal to the second gate of the second one of such transistors; and
- means for combining the output signals from the dual gate field effect transistors.

4,297,703

TELEMETRY DEVICE FOR TRACKING RADAR AND RADAR SYSTEM COMPRISING SUCH A DEVICE
Philippe Lacomme, Paris, France, assignor to Thomson-CSF, Paris, France

Filed Dec. 4, 1979, Ser. No. 100,143

Claims priority, application France, Dec. 5, 1978, 78 34225


Int. Cl.³ G01S 13/70

U.S. Cl. 343—7.3

7 Claims

4. A telemetry device for tracking radar comprising:
a first loop for tracking the distance of a moving echo comprising

a first deviation detector for determining the position deviation of an echo signal and a telemetry mark, means for the digital calculation of the distance of the echo, means for generating clock pulses of a predetermined repetition frequency, and



generating means for providing a reference tracking window by adding-subtracting clock pulses, and a second analog loop, connected in said first loop between the generating means for providing a reference tracking window and the position deviation detector providing a time filtering in distance of the reference tracking window.

4,297,704


PHASE SENSITIVE SPECTRUM ANALYZER

Emanuel Marom, Los Angeles; Michael K. Barnoski, and Richard L. Abrams, both of Pacific Palisades, all of Calif., assignors to Hughes Aircraft Company, Culver City, Calif.

Filed Aug. 13, 1979, Ser. No. 66,199

Int. Cl.³ G01S 5/02; G01R 23/16; G02B 5/14; G01B 9/02
U.S. Cl. 343-113 R

6 Claims



1. An acousto-optic processing arrangement which determines the direction of arrival of energy applied thereto, said arrangement comprising:

- a laser source;
- a first lens disposed to collimate laser light provided by said laser source;
- a second lens disposed to focus the collimated laser light provided by said first lens;
- a detector array disposed at the focal plane of said second lens;
- two surface acoustic wave transducers disposed between said first and second lenses and adjacent to an optical path between said lenses, said two surface acoustic wave transducers being disposed adjacent to one another and disposed such that the surface acoustic waves radiated thereby are substantially parallel to one another;
- two antennas, each antenna being individually coupled by means of separate downconverters to one of said surface acoustic wave transducers, said antennas being disposed so as to have their respective lines-of-sight substantially parallel to one another; and

computer means coupled to said detector array for determining the direction of arrival of said applied energy.

4,297,705

FREQUENCY AGILITY TECHNIQUE FOR FREQUENCY SCANNED ANTENNA


Robert R. Boothe, Huntsville, Ala., assignor to The United States of America as represented by the Secretary of the Army, Washington, D.C.

Filed Mar. 3, 1980, Ser. No. 126,516

Int. Cl.³ H01Q 3/26, 13/10

U.S. Cl. 343-771

3 Claims



1. A frequency agility circuit for a frequency scanned antenna comprising: bidirectional switching means adapted for coupling electromagnetic radiation therethrough, said switching means being adapted for receiving energy from a source of electromagnetic radiation; a serpentine feed structure coupled to said switching means for directing electromagnetic radiation bidirectionally therethrough, said serpentine feed structure being adapted for coupling said radiation to and from a frequency scanned antenna array, and said serpentine feed structure having first and second feed inputs for directing energy bidirectionally therethrough; and wherein said switching means comprises first, second, and third microwave circulators, each circulator having first, second, and third input-output ports, said first port of the first circulator being adapted for receiving energy from a radiation source, said second circulator having the first input-output port coupled to said second port of the first circulator and having the second port coupled to the first input of said serpentine feed structure, said third circulator having the first port coupled to said third port of the first circulator and having the third input-output port coupled to the second input of said serpentine feed structure; and further comprising a load circuit coupled to the third port of said second circulator and to the second port of said third circulator for absorbing residual energy.

4,297,706

CIRCULARLY POLARIZED SLOTTED PYLON ANTENNA

Nicholas Nikolayuk, Gibbsboro, N.J., assignor to RCA Corporation, New York, N.Y.

Filed Mar. 17, 1980, Ser. No. 131,273


Int. Cl.³ H01Q 13/12

U.S. Cl. 343-771

11 Claims

1. An antenna comprising a conducting vertical cylinder having a plurality of slots, said slots being disposed in a plurality of vertically stacked bays, each bay comprising at least one pair of slots disposed at about right angles to each other, slots of each pair being vertically spaced with respect to each other by about one half of a wavelength of a desired center frequency, said vertical spacing being established between hori-

zontal centers of said slots, and means for exciting said slots so that slots comprising a pair are in about ninety degree time ing slot (7, 14, 43) formed in the side walls for radiating radiant energy.



phase relationship and have about equal amplitudes with respect to each other.

4,297,707

MULTIPLE OMNIDIRECTIONAL ANTENNA

Anton Brunner, Wangen, and Nikolaus Willburger, Olching, both of Fed. Rep. of Germany, assignors to Siemens Aktiengesellschaft, Berlin & Munich, Fed. Rep. of Germany
Continuation of Ser. No. 810,592, Jun. 27, 1977, abandoned.


This application Jun. 4, 1979, Ser. No. 45,228

Claims priority, application Fed. Rep. of Germany, Jun. 30, 1976, 2629502

Int. Cl.³ H01Q 13/12

U.S. Cl. 343-725

5 Claims



1. An omnidirectional end antenna which forms an assembly with one or more other antennas mounted on a common axis comprising a wave shaping base plate member (10, 21, 46), a coaxial feed line having an outer conductor (8, 19, 41) attached to said base plate member (10, 21, 46) on one side thereof and extending through said one or more other antennas, an opening formed in said base plate member (10, 21, 46), a cylindrical shaped radiating member (6, 17, 42) into which the end of feed line extends attached to the second side of said base plate member (10, 21, 46) and formed with a short circuit cover member (11, 23, 49) over its remote end, and at least one radiat-

4,297,708

APPARATUS AND METHODS FOR CORRECTING DISPERSION IN A MICROWAVE ANTENNA SYSTEM

Paul Vidal, Paris, France, assignor to Societe d'Etude du Radant, Orsay, France


Filed Jun. 22, 1978, Ser. No. 918,152

Claims priority, application France, Jun. 24, 1977, 77 19364

Int. Cl.³ H01Q 19/06

U.S. Cl. 343-754

13 Claims



1. A nondispersive microwave antenna system comprising:
 - (a) antenna means for radiating a microwave beam which exhibits variation in the direction of propagation of said beam in a first plane with variation in the frequency of said beam;
 - (b) lens means for controllably deflecting the direction of propagation of said beam in said first plane, said lens means comprising a plurality of networks located one behind the other, each in the direction of propagation of said beam and each network comprising a plurality of portions with said portions comprising first means for conducting said first means for conducting being cut into sections, second means for conducting and a plurality of first means for switching having conductive and non-conductive states, said first means for switching being spaced apart on said second means for conducting to selectively render said second means for conducting discontinuous when said first means for switching is in said non-conductive state to assure a shift in the phase of said beam passing through said portions of said networks depending upon said conductive and non-conductive states of said first means for switching in said portions of said networks; and
 - (c) control means for setting the state of conduction of said first means for switching to establish phase shifts in said beam in said portions which phase shifts correct for said variation in the direction of propagation of said beam with variation in the frequency of said beam.

4,297,709

LUNEBERG LENS ANTENNA

Knut E. Cassel, and Bengt T. Molin, both of Järfälla, Sweden, assignors to U.S. Philips Corporation, New York, N.Y.

Filed Jan. 23, 1980, Ser. No. 114,490

Claims priority, application Sweden, Feb. 6, 1979, 7901047


Int. Cl.³ H01Q 15/08

U.S. Cl. 343-754

7 Claims

1. An antenna comprising a round disc shaped lens element of the Luneberg type, having a radially varying diffraction index decreasing in the peripheral direction, surrounded on its planar sides by two conductive planes and having feeders distributed across at least a portion of the circumference, said feeders being shaped and oriented to transmit and receive, respectively, a polarized wave, the polarization direction of

which forms an angle less than 90° with the plane of the lens element, a substantial portion of the distance between the conductive planes external to said lens element being formed



by a dielectric medium having the dielectric constant of air, the thickness of said medium being substantially constant across the lens.

4,297,710

PARALLEL-PLANE ANTENNA WITH ROTATION OF POLARIZATION

Albert Dupressoir, Paris, France, assignor to Thomson-CSF, Paris, France


Filed Mar. 4, 1980, Ser. No. 127,097

Claims priority, application France, Mar. 9, 1979, 79 06135

Int. Cl.³ H01Q 19/195

U.S. Cl. 343-756

12 Claims



1. A parallel-plane antenna comprising two parallel metal plates limited by a cylindrical-parabolic end-wall illuminated by a source, said source being placed on the focal line of said antenna at an equal distance from the two plates, at the rear of said antenna on the opposite side of the emitted wave and said cylindrical-parabolic end-wall comprising a semitransparent reflector and said plane at right angles to the plates and containing the focal line being formed by a polarizing reflector unit.

4,297,711

OMNIDIRECTIONAL RECEIVING ANTENNA

Hans Ekström, Mankkaanpuro 19, SF-02180 Espoo 18, Finland

Filed Jul. 25, 1979, Ser. No. 60,368

Claims priority, application Finland, Jul. 31, 1978, 782364


Int. Cl.³ G08B 5/22; G09F 9/00

U.S. Cl. 343-794

7 Claims

1. An omnidirectional receiving antenna primarily for receiving TV signals comprising at least one substantially circular antenna element tuned to receive signals in a predetermined frequency range, said at least one element including a substantially circular metal plate having means defining a slot extending along a diameter of the plate, said slot opening at one edge of the plate and extending to a terminus close to but spaced radially inwardly from the opposite edge; an elongated metal band extending circularly around the periphery of said plate and across the open end of said slot, the end portions of said band being bent inwardly to form substantially straight symmetrical leg portions extending

along the edges of said slot from bends therein on opposite sides of the slot opening; means for connecting the distal ends of said leg portions to said plate adjacent said slot; and



means for mounting said band in axially spaced relationship from said plate; an amplifier having input terminals connected to said end portions of said band; and a housing for said antenna element.

4,297,712

AIR FLOW TUNNEL FOR REDUCING INK JET DRAG ON ARRAY HEAD


Gerald B. Lammers, Boulder, and Gordon J. Smith, Longmont, both of Colo., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Sep. 17, 1979, Ser. No. 76,093

Int. Cl.³ G01D 15/18

U.S. Cl. 346-75

13 Claims



1. An integrated ink jet aspirator comprising: a housing means having an air inlet port, an interconnecting flow channel and an outlet port; said interconnecting flow channel includes a first section operable to reduce turbulence in a stream of incoming air, a second section being coupled to the first section and operable to increase the velocity of the incoming air; a third section being coupled to the second section said third section having a noncircular cross section with a constant geometry along its longitudinal axis and operable to maintain a constant velocity in the incoming air; and an ink jet head positioned relative to the housing means and in linear alignment with the third section whereby ink droplets emanating from the ink jet head are being propelled into a nonturbulent uniform velocity air flow.

4,297,713

LASER RECORDING APPARATUS

Junji Ichikawa; Nobuhiro Imai; Kimio Kohno; Koichi Kadokura, and Masaaki Ishii, all of Kawasaki, Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan


Filed May 29, 1979, Ser. No. 43,246

Claims priority, application Japan, Jun. 3, 1978, 53-66858; Sep. 21, 1978, 53-117237

Int. Cl.³ G01D 15/14

U.S. Cl. 346-108

3 Claims



1. A laser recording apparatus, comprising: laser means comprising a laser element for emitting a laser beam; optical means supporting said laser means, said optical means receiving the laser beam therefrom at an entrance end and emitting a collimated laser from an exit end thereof, said optical means being provided with a mounting standard face, wherein the difference between the distance of the laser element from said standard face and the distance of the entrance end from said standard face are maintained within the focal depth of said optical means even in the presence of a temperature change; a support member comprising a mounting standard face on which is affixed said mounting standard face of said optical means; and deflector means for directly receiving the laser beam from said optical means and directing said laser beam toward a recording medium.

4,297,714

THERMAL PEN

Kazunari Ando, Tajimi; Hirokazu Matsunaga, Tsushima, and Hideaki Ayabe, Tokyo, all of Japan, assignors to Nippon Toki Kabushiki Kaisha, Nagoya and Watanabe Instruments Corp., Tokyo, both of Japan

Continuation of Ser. No. 853,874, Nov. 22, 1977, abandoned.


This application Aug. 30, 1979, Ser. No. 71,035

Claims priority, application Japan, Apr. 5, 1977, 52-42519[U]

Int. Cl.³ G01D 15/10

U.S. Cl. 346-139 C

8 Claims



1. A thermal pen of the thick film type for thermal recording, comprising a thermal pen tip and a thermal pen tip holder connected to said thermal pen tip for holding the thermal pen tip, said thermal pen tip comprising a high resistance, low thermal-conductivity, planar substrate formed in the form of a pen point and having a rectangular cross section, a heater element in the form of a thick film having a flat top surface on a portion of the end surface of the pen point of said high resistance, low thermal-conductivity, planar substrate, a generally semispherically prefabricated minute recording piece having a

flat bottom surface and made of a heat-resistant, wear-resistant material having a thermal-conductivity substantially equal to or higher than that of said substrate, said recording piece being attached at its flat bottom surface to a portion of said flat top surface of said heater element and being adapted to be heated by said heater element for performing the thermal recording, and an electrical conductor in the form of a thick film so as to connect to said heater element of the high resistance substrate, said thermal pen tip holder and said planar substrate arranged so that during said thermal recording said substrate moves in the direction of the longitudinal length of said rectangular cross section.

4,297,715

ELECTROSTATIC RECORDING APPARATUS

Masaharu Tadauchi; Kunio Sato, both of Hitachi, and Kiyohiko Tanno, Katsuta, all of Japan, assignors to Hitachi, Ltd., Tokyo, Japan


Filed Jul. 2, 1979, Ser. No. 54,273

Claims priority, application Japan, Jul. 14, 1978, 53-85162

Int. Cl.³ G11B 15/60; G01W 1/02

U.S. Cl. 346-150

9 Claims



1. An electrostatic recording apparatus comprising: a wire electrode row including a multiplicity of wire electrodes which are continuously arranged substantially in a row and are divided into a plurality of wire electrode blocks each having the same number of wire electrodes; a plurality of auxiliary electrodes arranged along said wire electrode row and respectively in opposition to said plurality of wire electrode blocks; a driving circuit for selectively applying driving signals to said wire electrodes and said auxiliary electrodes in response to a recording signal, said driving circuit simultaneously applying said driving signals to the corresponding wire electrodes of the respective wire electrode blocks; an electrostatic recording medium disposed close to said wire electrodes and aid auxiliary electrodes, of which the portion close to both of the driven auxiliary electrode and the driven wire electrode opposite to the driven auxiliary electrode is charged thereby to have an electrostatic latent image thereon; means for relatively moving said wire electrodes, said auxiliary electrodes and said recording medium; a humidity detector for detecting ambient humidity thereby producing a signal representing a detected value; control means for controlling a waveform of at least one of a drive signal applied to said wire electrode and a drive signal applied to said auxiliary electrode in accordance with the output signal from said humidity detector; and means for developing said charged recording medium to obtain a visualized image without formation of a ghost image.

4,297,716

RECORDING APPARATUS INCLUDING A CONTINUOUS TRANSFER WEB

Kazuhiro Hirayama, Yokohama, and Susumu Sugiura, Yamato, both of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan


Continuation of Ser. No. 819,142, Jul. 26, 1977, abandoned. This application Aug. 21, 1979, Ser. No. 68,419

Claims priority, application Japan, Jul. 30, 1976, 51-91836

Int. Cl.³ G01D 15/06

U.S. Cl. 346—153.1

16 Claims



1. A recording apparatus comprising: an image bearing member; means for forming continual images on said image bearing member; means for feeding a continuous transfer material to a transfer station; means for transferring the images formed on said image bearing member onto the continuous transfer material; means for fixing the transferred images on the transfer material; and means, responsive to the start and stop of operation of said image forming means, for controlling the actuation of said feeding means, transferring means, and fixing means at different delayed times from each other to transfer a series of images from said image bearing member onto desired portions of said continuous transfer material irrespective of image location on said image bearing member.

4,297,717

SEMICONDUCTOR DEVICE

Chou H. Li, 379 Elm Dr., Roslyn, N.Y. 11576

Continuation-in-part of Ser. No. 7,584, Jan. 29, 1979, which is a continuation-in-part of Ser. No. 764,433, Jan. 31, 1977, Pat. No. 4,136,435, which is a continuation-in-part of Ser. No. 405,138, Oct. 10, 1973, abandoned, which is a continuation of Ser. No. 190,483, Oct. 19, 1971, Pat. No. 3,765,956, Ser. No. 386,102, Aug. 6, 1973, and Ser. No. 802,018, Feb. 25, 1969, Pat. No. 3,500,135, which is a continuation-in-part of Ser. No. 490,955, Sep. 28, 1965, Pat. No. 3,430,109, said Ser. No. 190,483, is a continuation-in-part of Ser. No. 868,129, Oct. 21, 1969, abandoned, which is a continuation-in-part of Ser. No. 491,718, Sep. 30, 1965, abandoned. This application Aug. 24, 1979, Ser. No. 69,298


Int. Cl.³ H01L 29/64

U.S. Cl. 357—15

17 Claims

1. An active solid state structure comprising: a metal substrate sheet and a layer of solid material adhered to the metal substrate sheet; said solid material comprising a multiplicity of elongated bodies of a single crystal semiconductor device material spaced from each other by similarly elongated bodies of a metal, there being electronic barriers between said elongated bodies of the semiconductor material and elongated bodies of metal; and

said elongated bodies of semiconductor material and of a metal and said electronic barriers therebetween being



formed concurrently with each other as an integral structure by a temperature gradient process.

4,297,718

VERTICAL TYPE FIELD EFFECT TRANSISTOR

Jun-ichi Nishizawa, Sendai, and Takashi Kitsuregawa, Itami, both of Japan, assignors to Semiconductor Research Foundation Mitsubishi Denki K.K., Japan


Continuation-in-part of Ser. No. 469,017, May 10, 1974, abandoned. This application Jun. 8, 1976, Ser. No. 693,894

Claims priority, application Japan, May 22, 1973, 48-58054

Int. Cl.³ H01L 29/80

U.S. Cl. 357—22

3 Claims



1. A vertical type field effect transistor comprising a semiconductor substrate including a pair of main opposite faces, a source electrode, a gate electrode, and a drain electrode, at least one of said source, gate and drain electrodes being disposed on one of said main opposite faces, at least one of the remaining electrodes being disposed on the other main face of the substrate, an input terminal and an output terminal, wherein at least two highly doped semiconductor regions form respective ones of said electrodes and are formed elongated and slender and having a dimension and impurity concentration imparting thereto a low resistance in a direction of travel of an electromagnetic wave traveling therein to form a transmission line whereby the transistor performs in a traveling wave mode of operation, and wherein said transmission line includes a common line defined by one of said source and gate electrodes, an input line defined by said common line and the other of said source and gate electrodes, and an output line defined by said common line and said drain electrode, and said input and output terminals are disposed on opposite sides of said transistor substrate and respectively connected to said input line and said output line.

4,297,719

ELECTRICALLY PROGRAMMABLE CONTROL GATE INJECTED FLOATING GATE SOLID STATE MEMORY TRANSISTOR AND METHOD OF MAKING SAME

Sheng T. Hsu, Lawrenceville, N.J., assignor to RCA Corporation, New York, N.Y.

Filed Aug. 10, 1979, Ser. No. 65,436


Int. Cl.³ H01L 29/78

U.S. Cl. 357—23

11 Claims

1. A non-volatile memory structure of the type including a

conductive floating gate storage device having a floating gate member for storing charge injected thereon, a conductive control gate member, a body of semiconductor material in which spaced drain and source regions of a first conductivity type are embedded at the surface thereof, the drain and source regions spaced a given distance one from the other to define a channel region of an opposite conductivity type therebetween, a drain-channel junction formed at the boundary of the drain and channel regions, a source-channel junction formed at the boundary of the source and channel regions, a first layer of insulating material deposited on the body of semiconductor material over the channel region for insulating the floating gate



1. A semiconductor impedance structure comprising: a substrate of monocrystalline semiconductor material; an insulating layer deposited over a portion of a surface of said substrate; a unitary body of substantially intrinsic polycrystalline semiconductor material disposed on a portion of said insulating layer defining a first conductive path; a doped area of extrinsic impurities of a first conductivity type disposed within a first region of said unitary body defining a second conductive path, an intrinsic-extrinsic junction being defined by the interface of the extrinsic diffusion region within the unitary intrinsic body; the first and second conductive paths defining a series electrical path for the flow of current through the intrinsic-extrinsic junction.

4,297,720

MULTI-PHOTODIODES

Hideaki Nishizawa, and Shin-ichi Iguchi, both of Nishinomiya, Japan, assignors to Sumitomo Electric Industries, Ltd., Osaka, Japan


Filed Jul. 19, 1979, Ser. No. 59,118

Claims priority, application Japan, Jul. 21, 1978, 53-89690

Int. Cl.³ H01L 27/14, 29/161

U.S. Cl. 357—30

5 Claims



1. Multi-photodiodes comprising a first photodiode, having a photo-sensitive region with a forbidden band-gap E_1 , and a second photodiode, having a photo-sensitive region with a forbidden band-gap E_2 , each photodiode consisting of p-n structures or p-i-n structures of semiconductor compounds, said first and second photodiodes integrated into one body with an intermediate connecting semiconductor compound layer of at least one of said photodiodes providing a filter layer

having a forbidden band-gap E_3 , said forbidden band-gaps E_1 , E_2 , and E_3 being under the condition of $E_1 < E_3 < E_2$.

4,297,721

EXTREMELY LOW CURRENT LOAD DEVICE FOR INTEGRATED CIRCUIT


Vernon C. McKenny, and Tsui C. Chan, both of Carrollton, Tex., assignors to Mostek Corporation, Carrollton, Tex.

Division of Ser. No. 957,587, Nov. 3, 1978, which is a continuation of Ser. No. 743,810, Nov. 22, 1976, abandoned. This application May 29, 1979, Ser. No. 43,419

Int. Cl.³ H01L 29/04

U.S. Cl. 357—59

10 Claims



1. A semiconductor impedance structure comprising: a substrate of monocrystalline semiconductor material; an insulating layer deposited over a portion of a surface of said substrate; a unitary body of substantially intrinsic polycrystalline semiconductor material disposed on a portion of said insulating layer defining a first conductive path; a doped area of extrinsic impurities of a first conductivity type disposed within a first region of said unitary body defining a second conductive path, an intrinsic-extrinsic junction being defined by the interface of the extrinsic diffusion region within the unitary intrinsic body; the first and second conductive paths defining a series electrical path for the flow of current through the intrinsic-extrinsic junction.

4,297,722

CERAMIC PACKAGE FOR SEMICONDUCTOR DEVICES HAVING METALIZED LEAD PATTERNS FORMED LIKE A FLOATING ISLAND

Tsutomu Nagahama, Kawasaki, and Michio Ishihara, Yokohama, all of Japan, assignors to Fujitsu Limited, Kawasaki, Japan


Filed Sep. 18, 1979, Ser. No. 76,577

Claims priority, application Japan, Sep. 18, 1978, 53-127835[U]

Int. Cl.³ H01L 23/02, 23/12, 39/02

U.S. Cl. 357—74

6 Claims



1. A transistor device comprising: a first ceramic plate which is provided with an emitter lead, a base lead and a collector lead, these emitter, base and collector leads being formed as metallized layers on the plate and being electrically connected to the correspond-

ing base, emitter and collector areas of a transistor chip element which is also mounted on the first ceramic plate; and
 a second ceramic plate which is provided with an emitter guide lead, a base guide lead and a collector guide lead, these emitter, base and collector guide leads being formed as metallized layers on the plate and having corresponding emitter, base and collector lead terminals, respectively, wherein the emitter, base and collector leads of the first ceramic plate are electrically connected to the corresponding emitter, base and collector guide leads of the second ceramic plate, respectively, by means of respective conductive paths formed longitudinally along and on the side surface of the second ceramic plate.

4,297,723

WIDE ANGLE LASER DISPLAY SYSTEM


Clyde M. Whitby, Duncanville, Tex., assignor to The Singer Company, Binghamton, N.Y.

Filed Jan. 28, 1980, Ser. No. 107,686

Int. Cl.³ H04N 9/31

U.S. Cl. 358—60

4 Claims



1. A scanned light beam video display apparatus for use with a viewing surface, comprising:

- light means for providing three groups of light beams, each group comprising a plurality of beams of substantially monochromatic light such that the light of each group corresponds to a different one of the three primary colors;
- video means for providing three groups of video signals, each group comprising a plurality of primary color video channel signals, such that each group of signals corresponds to a different one of the three color video channels for a plurality of contiguous scene parts to be viewed;
- light modulation means associated with said light means and said video means and responsive to said three groups of video signals for intensity modulating said three groups of light beams in accordance with the video information contained in said signals to produce three groups of intensity modulated light beams, each group of modulated beams comprising a plurality of beams of substantially monochromatic light corresponding to a different one of the three primary colors, each of said plurality of beams within each said group being intensity modulated in accordance with the video information of one of the three color video channels for a different one of said plurality of contiguous scene parts to be viewed;
- light combining and parallelizing means for combining said three groups of modulated light beams such that each of said modulated beams corresponding to the channels of each one of said contiguous scene parts is combined so as to form composite beams of video intensity modulated light for raster scanning to form each of said contiguous scene parts, thereby producing a plurality of said composite beams in parallel relationship;
- single scanning means for scanning simultaneously said

plurality of parallel composite beams in the pattern of a TV raster for each;
 (f) projection means for projecting said plurality of raster scanned composite beams onto the viewing surface; and
 (g) beam separation means for spatially separating said projected plurality of raster scanned composite beams such that said separated beams raster scan said scene parts contiguously onto the viewing surface to form a single continuous scene.

4,297,724

METHOD AND MACHINE FOR TRYING ON A HAIR FORM IN IMAGE

Tatsunosuke Masuda; Yoshio Ono, and Seiya Sakamoto, all of Kyoto, Japan, assignors to Dainippon Screen Seizo Kabushiki Kaisha and Takara Belmont Co., Ltd., both of, Japan


Filed Jan. 23, 1980, Ser. No. 114,947

Claims priority, application Japan, Jan. 24, 1979, 54-7375; Mar. 12, 1979, 54-28454

Int. Cl.³ H04M 7/18

U.S. Cl. 358—93

11 Claims



1. A method for trying on a hair form in image, comprising: photographing a face shape and a hair pattern by a video camera to obtain first and second signals respectively corresponding to face shape and hair pattern; preparing a third signal for masking the hair pattern portion in the face shape by using said second, hair pattern representing signal; combining said third signals with said first signal so as to mask effectively the hair pattern portion of the face shape; adding said second signal to the modified first signal so as to effectively add the hair pattern to partially masked face shape signal, thereby obtaining a fourth composite signal for making the face shape with the hair pattern thereon; and displaying the fourth signal to generate a face shape with the desired hair pattern thereon in a display means.

4,297,725

METHOD FOR MEASUREMENT OF DISPLACEMENT OF MOVING BODY BY USE OF TARGET MARK AND APPARATUS THEREFOR

Ken-Ichi Shimizu, Tokorozawa, and Chuji Ikeya, Higashi-Murayama, both of Japan, assignors to Agency of Industrial Science & Technology and Ministry of International Trade & Industry, both of Tokyo, Japan

Filed Aug. 21, 1979, Ser. No. 68,438

Claims priority, application Japan, Aug. 24, 1978, 53-103211 Int. Cl.³ H04N 7/18


U.S. Cl. 358—125

6 Claims

1. A method for the measurement of the displacement of a moving body by use of a target mark placed on the body, which target mark has two quarter shaded dark areas symmetrically opposed to each other, comprising the steps of:

- taking the image of the target mark with an image pickup tube by causing carriers for circular sweep to be respectively superposed on the relative deflection voltages, thereby to produce video signals;

- (b) shaping an alternating current component of the video signals to produce a bistable video signal;
- (c) subjecting said bistable video signal with each of said carriers and with sub-carriers having a frequency two times that of said carriers to synchronous rectification and smoothing, thereby to produce mean values ($\bar{U}_x$ and $\bar{U}_y$) for said carriers and mean values ($\bar{U}_{x2}$ and $\bar{U}_{y2}$) for said sub-carriers, the ratio of said mean values for the sub-carriers being equivalent to the angular displacement;
- (d) calculating the deviation values (ΔX and ΔY) of the center of the target mark from the center of the circular sweep in accordance with the formulas:



$$\Delta X = \bar{U}_x - \bar{U}_{x2} = \bar{U}_y \bar{U}_{y2}$$

$$\Delta Y = \bar{U}_y - \bar{U}_{y2} = \bar{U}_x \bar{U}_{x2}$$

and

- (e) feeding back to the deflecting system of the image pickup tube said deviation values as deflection-correcting voltages, thereby to cause the center of the circular sweep to coincide with that of the target mark, whereby the positional displacement of the target mark is determined on the basis of said deviation values and the angular displacement is determined on the basis of said mean values for the sub-carriers.

4,297,726

TELEVISION RECEIVER CHASSIS ADAPTED TO BE COMPATIBLE WITH DIFFERENT TUNER AND CABINET CONFIGURATIONS

John E. Nicholson, Indianapolis, and Paul C. Wilmarth, Noblesville, both of Ind., assignors to RCA Corporation, New York, N.Y.

Filed Feb. 7, 1980, Ser. No. 114,872


Int. Cl.³ H04N 5/655

U.S. Cl. 358—254

8 Claims

1. A television receiver chassis containing television signal processing circuits including a plurality of different signal points, adapted for assembly with either a first or a second television receiver subsystem having different signal interface requirements with said chassis to form a television receiver, said first subsystem including a first connector coupled to the subsystem, said first connector including a first array of unblocked contact holes and one blocked contact hole, and said second subsystem including a second connector coupled to said second subsystem, said second connector including a second array of unblocked contact holes and one blocked contact hole; said television receiver chassis comprising: an array of terminal locations, the number of said locations being equal to or greater than the number of contact holes

in each connector, each of said locations being occupied by a terminal, with the exception of a blank terminal location which does not contain a terminal; means for coupling said terminals to respective ones of said plurality of different signal points, wherein a first combination of some of said terminal locations including said blank terminal location is capable of



engaging said first connector when said blank terminal location is aligned with said blocked hole of said first connector, and wherein a second different combination of said terminal locations including said blank terminal location is capable of engaging said second connector when said blank terminal location is aligned with said blocked hole of said second connector.

4,297,727

FACSIMILE APPARATUS

Mutsuo Ogawa; Yuji Koseki; Yuichi Saitoh; Shingo Yamaguchi, and Shigeru Katsuragi, all of Tokyo, Japan, assignors to Ricoh Company, Ltd., Tokyo, Japan


Filed Jun. 30, 1980, Ser. No. 164,466

Claims priority, application Japan, Jul. 9, 1979, 54-85826

Int. Cl.³ H04M 1/00

U.S. Cl. 358—261

12 Claims



1. A facsimile apparatus comprising:

- scanner means;
 - recorder means;
 - microcomputer means having a central processing unit, a read only memory containing an operating program and a random access memory;
 - modem means;
 - first interface means connected between the scanner means and the microcomputer means;
 - second interface means connected between the microcomputer means and the modem means; and
 - third interface means connected between the microcomputer means and the recorder means;
- in a transmission mode, the operating program controlling the microcomputer means to store image data from the scanner means in a first section of the random access memory through the first interface means, encode the data

and store the encoded data in a second section of the random access memory and transfer the encoded data from the second section of the random access memory through the second interface means to the modem for transmission;

in a reception mode, the operating program controlling the microcomputer means to store encoded data received through the modem in the second section of the random access memory through the second interface means, decode the data and store the decoded data in the first section of the random access memory and transfer the decoded data from the first section of the random access memory through the third interface means to the recorder for producing a facsimile reproduction.

4,297,728

CHARGED COUPLED DEVICE TIME BASE CORRECTOR SYSTEM


Virgil L. Lowe, 1411 Noble Forest Dr., Norcross, Ga. 30092

Filed Apr. 6, 1979, Ser. No. 27,926

Int. Cl.³ H04N 5/04, 5/785

U.S. Cl. 360—36

6 Claims



1. An analog video time base corrector system comprising: input circuit means for receiving a video signal including synchronization information from a source, said input circuit means having an output;

analog delay line means coupled to said output of said input circuit means for delaying said video signal and said included synchronization information, said analog delay line means having first and second outputs;

first feedback circuit means coupled to the first output of said analog delay line means for controlling the delay thereof in response to said delayed synchronization information contained in said delayed video signal, said first feedback circuit means including an infinite gain phase detector means coupled to the first output of said delay line means for comparing the delayed synchronization information contained in said delayed video signal with a reference synchronization signal to detect the phase error in said delayed synchronization information, said phase detector means producing an output signal which is coupled through an infinite gain voltage amplifier to an input of a voltage controlled clock generator means, said clock generator means supplying a clock signal to a clock input of said delay line means, said clock signal having a frequency proportional to the phase error of said delayed synchronization information;

second feedback circuit means coupled to receive the output of said infinite gain voltage amplifier of said first feedback circuit means for supplying said reference synchronization signal to said first feedback circuit means, said second feedback circuit means including an adaptive time constant amplifier means coupled to receive the output of said infinite gain voltage amplifier for automatically controlling the response rate of said second feedback circuit means based upon the phase error of said synchronization information, said second feedback circuit means further including a first voltage controlled oscillator means cou-

pled to receive the output of said adaptive amplifier means for generating said reference synchronization signal; and output circuit means coupled to the second output of said analog delay line means and coupled to receive said delayed synchronization information for interfacing the delayed output of said analog delay line means with circuitry external to said video time base corrector system; whereby said system acts to slowly correct small phase errors and to rapidly correct large phase errors in synchronization timing such that a stable output video signal is produced for a wide range of input synchronization errors.

4,297,729

ENCODING AND DECODING OF DIGITAL RECORDINGS

James H. Steynor, High Wycombe, and Frederick Hayes, Southall, both of England, assignors to EMI Limited, Hayes, England


Filed Nov. 20, 1978, Ser. No. 961,933

Claims priority, application United Kingdom, Nov. 24, 1977, 48917/77

Int. Cl.³ G11B 5/09

U.S. Cl. 360—40

11 Claims



1. An arrangement for generating controlled clock pulses synchronized to a signal comprising a sequence of '1's, each indicated by the presence of a signal pulse and '0's each indicated by the absence of a signal pulse, so that in a sequence of consecutive '0's no signal pulses are present, the arrangement including a first counter receiving the said signal and arranged to count for a first predetermined period from a predetermined point in relation to each '1' of said signal and to provide a controlled clock pulse synchronized to said signal at the termination of the first period, a second counter arranged to count for a second and longer predetermined period from a preceding controlled clock pulse or until reset prior to the termination of said period and, if not reset, to provide at the termination of said second period a further controlled clock pulse and means for resetting the second counter on reception of a further '1' at the first counter.

4,297,730

MAGNETIC RECORDING AND REPRODUCING DEVICE
Hidetaka Kadowaki, Akira Inomata, Kiyoshi Yanagida, Tsunao Hasegawa, Satoshi Ishii, and Yasushi Ohtake, all of Tokorozawa, Japan, assignors to Pioneer Electronic Corporation, Tokyo, Japan

PCT No. PCT/JP00051, § 371 Date Nov. 1, 1979, §102(e) Date Oct. 29, 1979, PCT Pub. No. WO79/00715, PCT Pub. Date Oct. 4, 1979.

This PCT application filed Nov. 1, 1979, Ser. No. 174,389

Int. Cl.³ G11B 5/47, 15/12

U.S. Cl. 360—66

11 Claims

1. A magnetic recording and reproducing device comprising: means for setting an optimum recording bias current, said optimum recording bias current being set by varying a record-

ing bias current at arbitrary time intervals and digitally storing and operating reference recording/reproducing signals corresponding to the recording bias current thus varied; means for setting an optimum recording level, said optimum recording level being set by varying a recording level at arbitrary time intervals and comparing reference recording/reproducing signals corresponding to the record level thus varied with a reference level; and means for setting an optimum recording

cent signal tracks and for supplying an output signal of a magnitude and polarity indicative of said phase shift which corresponds to the combined effects of tracking error and length variations of said record carrier, and means for removing from said output signal components due to length variations of said record carrier.

4,297,732

METHOD AND DEVICE FOR LOCATING A SOUND EVENT ON A MAGNETIC TAPE

Otto Freudenschuss, Vienna, Austria, assignor to Karl Vockenhuber and Raimund Hauser, both of Vienna, Austria


Filed May 25, 1979, Ser. No. 42,690

Claims priority, application Austria, Jun. 5, 1978, 4045/78

Int. Cl.³ G11B 15/18, 19/02

U.S. Cl. 360—72.1

26 Claims



equalization characteristic, said optimum recording equalization characteristic being set by varying a recording equalization characteristic at arbitrary time intervals and comparing high frequency band reference recording/reproducing signals corresponding to the record equalization characteristic thus varied.

4,297,731

PLAYBACK APPARATUS FOR CORRECTING LOCKING ERRORS

Harald Melwisch, Vienna, Austria, and Hendrikus Looren de Jong, Eindhoven, Netherlands, assignors to U.S. Philips Corporation, New York, N.Y.

Continuation of Ser. No. 807,976, Jun. 20, 1977, abandoned.


This application Feb. 26, 1979, Ser. No. 15,019

Claims priority, application Austria, Jul. 30, 1976, 5674/76

Int. Cl.³ G11B 27/10, 21/10

U.S. Cl. 360—70

4 Claims



1. A tracking error detector for a playback apparatus having a rotary transducer with at least two magnetic heads whose effective gaps have mutually different azimuth angles for detecting television signals containing synchronizing pulses recorded on a record carrier in oblique signal tracks, said detector comprising means coupled to said magnetic heads for separating said synchronizing pulses from the detected television signal, means coupled to said separating means for detecting the phase shift between two consecutive synchronizing pulse trains each associated with a respective one of a pair of adja-

1. A method for coordination of a location signal to a sound event stored on a magnetic tape in a magnetic tape device, particularly for ascertaining the precise location of the beginning and/or end of the sound event on the tape with respect to a reference point on the tape device, comprising the steps of starting the playback of the tape which contains the sound event from a point before the sound event,

upon hearing the sound event activating a counter to set it to count condition zero and via the counter initiating a detectable location signal automatically when the counter is at the count condition zero and simultaneously causing the counter to count forward with counts of the counter being dependent on the length of tape being transported by the tape device,

subsequently reversing the magnetic tape to travel back at least to the sound event and causing the counter to count backwards dependent on the transported length of the tape in the reverse direction,

repeating playback of the tape together with operation of the counter to count forward, causing the location signal to occur automatically when the counter reaches the count condition zero and the sound event to occur when the sound event plays on the tape device,

perceiving and estimating the time relationship between the played back sound event and the occurring location signal,

changing a count condition of the counter based on the perceived and estimated time relationship between the sound event and the location signal so that a subsequent occurrence of the location signal is shifted vis-a-vis the played back sound event during a subsequently repeated playback step,

repeating the perception and estimation, changing, reversing and repeating playback steps so as to progressively shift the then occurring location signal vis-a-vis the then played back sound event until the location signal and the played back sound event are perceived as substantially concurrent by the user and are thereby correlated, and

positioning the sound event on the magnetic tape with respect to a reference point on the tape device using the correlated location signal.

4,297,733

METHOD OF CONTROLLING THE POSITION OF A WRITE OR READ HEAD AND A DEVICE FOR CARRYING OUT THE METHOD

Hendrik J. Sanderson, Eindhoven, Netherlands, assignor to U.S. Philips Corporation, New York, N.Y.

Continuation of Ser. No. 880,437, Feb. 23, 1978, abandoned.


This application Apr. 1, 1980, Ser. No. 136,235

Claims priority, application Netherlands, Mar. 16, 1977, 7702815

Int. Cl.³ G11B 5/52, 21/10

U.S. Cl. 360—77

6 Claims



1. A method of detecting the position of a magnetic recording/playback head relative to one of four or more tracks on a record carrier, said tracks containing first information signals and at least four consecutive tracks containing second tracking signals having mutually different frequencies recorded therein in cyclic sequence, said frequencies of said tracking signals being different from frequencies of said information signals, said method comprising the steps of generating a third signal having a frequency which changes from track to track in relation to the frequency of said tracking signals such that, for a given pair of adjacent tracks, the frequency of the third signal associated with one track of said pair differs from the frequency of the tracking signal recorded on the other track of said pair by one of a first and second predetermined number of cycles which are different from each other, subtracting the frequency of said third signal associated with said one track from the frequencies of tracking signals in the tracks adjacent said one track to produce a pair of fourth signals each having a frequency corresponding to said first and second number of cycles, respectively, and obtaining from said pair of fourth signals a resultant signal indicative of displacement of said head from the track being read.

4,297,734

SAMPLED DATA SERVO POSITIONING SYSTEM

William J. Laishley, and John R. Taylor, both of Winchester, England, assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Dec. 26, 1979, Ser. No. 107,120

Claims priority, application United Kingdom, Dec. 27, 1978, 49980/78


Int. Cl.³ G11B 21/08, 21/10

U.S. Cl. 360—78

13 Claims

1. A sampled data servo positioning system for moving a member between a current and a target position comprising: an actuator responsive to applied drive signals to move such a member; a position transducer movable with the member for producing signals in response to motion thereof; position signal generating means responsive to the position transducer signals to produce at least one incremental position signal representative of the position of the member at sampling times; a model responsive to an input signal to produce at least one continually available model incremental position signal; profile signal generating means for generating a profile

signal, corresponding to a predetermined velocity profile, as an input signal for the model; phase comparing means for comparing and indicating the phase difference between the sampled and model position signals at the sampling times; actuator feedforward signal generating means for generating a feedforward control signal for the actuator corresponding to the predetermined velocity profile; and stage indicating means for indicating various stages of the motion in accordance with predetermined conditions; the system being characterized by switching means responsive to the stage indicating means to switch the system between first and second operational configurations, by a source of saturation control signals of opposite polarity for application to the actuator to cause maximum acceleration or deceleration thereof,



and by means for deriving a continuous performance signal representative of actuator motion; and wherein, in the first operational configuration, the switching means connects the saturation control signal source to the actuator and connects a combination of the actuator performance signal as a feedforward input and the position phase difference signal as a feedback input to the model so that the model tracks the actuator system, and wherein, in the second operational configuration, the switching means connects the model input profile signal to the model, and connects a combination of the actuator feedforward control signal as a feedforward input and the position phase difference signal as a feedback input to the actuator so that the actuator tracks the model.

4,297,735

MANUALLY OPERABLE MAGNETIC CARD READER AND MAGNETIC HEAD ASSEMBLY THEREFOR


Helmuth Eppich, West Vancouver, Canada, assignor to EBCO Industries, Ltd., Richmond, Canada

Filed Jul. 26, 1979, Ser. No. 60,776

Int. Cl.³ G11B 21/20, 5/48

U.S. Cl. 360—104

24 Claims



1. For use in a magnetic card reader which includes a housing defining a housing slot through which a card is manually moved, by grasping the card and sliding the card along the housing slot, to effect reading of data magnetically recorded

on the card, a magnetic head assembly separate from the housing and comprising:

block means having formed therein a block slot through which the card passes as the card is manually moved through the housing slot, and also having formed therein first and second apertures extending into said block means from said block slot and opposing each other across said block slot;

a magnetic reading head in said first aperture and a pressure pad in said second aperture, and separate means respectively mounting said magnetic reading head and said pressure pad in these respective apertures for reciprocal motion therein to and from said block slot; and means yieldably biasing said magnetic reading head and said pressure pad toward said block slot.

4,297,736

DEVICE FOR ADJUSTING AND FIXING DETECTING MEANS RELATIVE TO THE INDEX MARK ON A RECORDING DISC

Klaus Manzke, Westheim; Roland Brotzler, Hochdorf-Assenheim, and Klaus Schulze-Berge, Ludwigshafen, all of Fed. Rep. of Germany, assignors to BASF Aktiengesellschaft, Fed. Rep. of Germany


Filed Dec. 27, 1979, Ser. No. 106,891

Claims priority, application Fed. Rep. of Germany, Jan. 12, 1979, 7900696[U]

Int. Cl.³ G11B 7/08, 17/00, 3/86

U.S. Cl. 360—109

3 Claims



1. A device for adjusting and fixing an index-mark-detecting means relative to the index mark on a recording disc, which device is arranged on a recording/reproducing apparatus for the recording disc and comprises a holding device for a detecting means, the position of which can be altered and which can be aligned and fixed relative to the index mark on the disc, wherein the holding device for the detecting means is a slidably mounted member which has at least one elongated hole and is spring-loaded against the chassis of the apparatus, said member moving on an arcuate path defined by the curved line passing centrally through the elongated hole and the middle of the detecting means.

4,297,737

SECTOR SERVO WITH SYNC MARKS

Rolf Andresen, and John H. Christian, both of Tucson, Ariz., assignors to International Business Machines Corporation, Armonk, N.Y.

Filed Dec. 26, 1979, Ser. No. 107,104


Int. Cl.³ G11B 5/82, 21/10

U.S. Cl. 360—135

5 Claims

1. A track following disk file including a record storage disk having a plurality of circumferentially spaced apart servo signal sectors, each sector having servo signals identifying a data track location line for track following, said data track locations containing recorded data signals, each of said servo sectors for each of said data track locations lines including a sync signal recorded adjacent a trailing edge of a servo signal and centered on said data track location line, each said sync signal including recorded information rela-

tive to the validity of the servo signals in its associated sector, transducing means for reproducing said servo signals, said sync signals and said data signals, means for separating said sync signals from said reproduced signals,



means operative only during the approximate time interval of occurrence of each of said sync signals for decoding each said sync signal to determine the validity of the servo signals in its associated sector, and means for modifying any of said sync signals indicating valid servo signals if said servo signals subsequently become invalid.

4,297,738

APPARATUS FOR AND METHOD OF DETECTING HIGH IMPEDANCE FAULTS ON DISTRIBUTION CIRCUITS WITH DELTA CONNECTED LOADS


Ilyoung Lee, Pacific Palisades, Calif., assignor to Electric Power Research Institute, Inc., Palo Alto, Calif.

Filed Oct. 29, 1979, Ser. No. 89,202

Int. Cl.³ H02H 3/16

U.S. Cl. 361—42

6 Claims



1. A device for use in detecting high impedance faults in a three-phase distribution circuit with delta connected load, said device comprising first means for providing the third harmonic current component from each three phase line current of said distribution circuit, second means connected with said first means for sensing the presence of a predetermined minimum increase in amplitude in each of said third harmonic components, and third means connected with said second means for producing a signal in response to the presence of said increase in any one of said components for a continuous predetermined period of time, said signal indicating a high impedance fault in the line carrying said one component.

4,297,739


DEVICE FOR EXCITING SYNCHRONOUS MACHINE
Rodion G. Goldin, ulitsa Mamina-Sibiryaka, 8, kv. 56, and
Valentin G. Yakimenko, ulitsa Taganskaya, 48, kv. 89, both of
Sverdlovsk, U.S.S.R.

Filed Jul. 30, 1979, Ser. No. 62,177

Int. Cl.³ H02H 7/06, 7/09

U.S. Cl. 361—55

4 Claims



1. A device for exciting a synchronous machine, comprising: an exciter electrically connected to an exciting winding of said synchronous machine;
- a starting unit connected parallel to said exciter and comprising at least one branch composed of a resistor and a thyristor switch placed in series, each branch protecting said exciting winding of said synchronous machine and said exciter against overvoltages during transient operation conditions; and a control circuit of said thyristor switch including voltage actuated threshold elements making thyristors of said thyristor switch conductive in order to activate said branch when voltage in said exciting winding exceeds the setting of said threshold element;
- at least one safety device connected in series in the circuit of a respective branch of the starting unit and disconnecting said respective branch in case of a fault in said respective branch;
- at least one protective thyristor connected parallel to a respective branch of the starting unit to bypass said respective branch in case of a fault in said respective branch;
- at least one current sensor of a respective branch of the starting unit connected in said respective branch and having a delayed-action commutator;
- at least one control circuit of a respective protective thyristor connected to a control electrode of said respective protective thyristor via a respective delayed-action commutator of said sensor, said control circuit of said protective thyristor producing a control pulse making the protective thyristor conductive when said commutator closes the current flowing in said respective branch of the starting unit increases beyond a permissible level.

4,297,740

PROTECTIVE RELAYING APPARATUS

John E. Hagberg, Mountain Lakes, N.J., assignor to Westinghouse Electric Corp., Pittsburgh, Pa.

Filed Feb. 5, 1979, Ser. No. 9,012

Int. Cl.³ H02H 3/28


U.S. Cl. 361—67

8 Claims

1. Protective relaying apparatus for detecting and clearing high impedance faults on a polyphase electrical distribution circuit, comprising:

- a polyphase source of alternating potential,
- a polyphase distribution circuit,
- a load circuit,
- a first circuit breaker for controlling the connection of the distribution circuit to the source,
- a second circuit breaker for controlling the connection of the distribution circuit to the load circuit,
- first and second ratio ground relays at the first and second

circuit breakers, respectively, for tripping the associated circuit breaker after a predetermined delay time when the ratio of zero sequence current to a predetermined phase current related quantity indicates a fault condition,



and a zero sequence directional relay at the second circuit breaker for coordinating the first and second ratio ground relays by adjusting the trip delay time of the second circuit breaker relative to the trip delay time of the first circuit breaker, in response to the flow direction of a zero sequence quantity at the second circuit breaker.

4,297,741

RATE SENSING INSTANTANEOUS TRIP MODE NETWORK


Edward K. Howell, Simsbury, Conn., assignor to General Electric Company, New York, N.Y.

Filed Sep. 4, 1979, Ser. No. 72,374

Int. Cl.³ H02H 3/08

U.S. Cl. 361—93

10 Claims



1. For protecting an AC electrical power distribution circuit against high level fault currents, an instantaneous trip mode network comprising, in combination:

- A. a separate air-core current transformer linked with each phase conductor of the distribution circuit and including a multi-turn secondary winding in which is developed a sinusoidal secondary voltage signal proportional to the rate of change of the phase current flowing in the linked phase conductor;
- B. a diode rectifying network connected with said secondary winding of each said air-core transformer for developing a rectified voltage signal corresponding to the one of said secondary voltage signals having the greatest magnitude;
- C. a signal input circuit connected to receive said rectified voltage signal, said circuit including
 - (1) an input lead on which appears a voltage input signal proportional to said rectified voltage signal,

4,297,743

CALL AND STACK MECHANISM FOR PROCEDURES EXECUTING IN DIFFERENT RINGS

Marc Appell, Paris; Jean-Louis Bogaert, Clamart; Claude Massuard, Paris; John Bradley, Garches, all of France, and Benjamin S. Franklin, Cambridge, Mass., assignors to Compagnie Honeywell Bull, Paris, France


Continuation of Ser. No. 529,019, Dec. 2, 1974, abandoned. This application Nov. 24, 1976, Ser. No. 744,814

Claims priority, application France, Nov. 30, 1973, 73 42705

Int. Cl.³ G06F 9/46

U.S. Cl. 364—200

32 Claims



4,297,742

ENGINE AND FUEL SHUTDOWN CONTROL

Gary N. Heitzman, Washington; Clay L. Hutchings, Pekin; Gary L. Knepp, Eureka, and Robert G. Miller, East Peoria, all of Ill., assignors to Caterpillar Tractor Co., Peoria, Ill.


Division of Ser. No. 823,770, Aug. 11, 1977, Pat. No. 4,150,654.

This application Jan. 8, 1979, Ser. No. 1,816

Int. Cl.³ H01H 47/04

U.S. Cl. 361—154

30 Claims



1. Apparatus for controlling solenoid operation comprising:

- a solenoid,
- a source of electrical energy,
- a control switch having an operative position,
- a settable and resettable latch means,
- means for setting said latch means in response to movement of said control switch to its operative position,
- means for connecting said solenoid to said source of electrical energy in response to movement of said control switch to its operative position and for supplying full current to said solenoid from said source for a desired period of time following such switch movement,
- means for automatically reducing the level of current flowing from said source to said solenoid at the end of said desired period of time and for maintaining said reduced-level current to said solenoid for as long as said latch means is set,
- means for resetting said latch means and for thereby terminating the flow of current from said source to said solenoid.

1. In combination with an automatic data processing apparatus comprising a virtual memory having a plurality of segments, each of some of said segments storing one of a plurality of procedures to be executed by said automatic data processing apparatus with privilege protection between said procedures, a central processing unit (CPU) connectable with said virtual memory to transfer data to and from said virtual memory, said CPU for processing information under control of a selected one of said plurality of procedures, each of said plurality of procedures having at least one level of privilege, said CPU having a plurality of registers for indicating the state of said selected procedure currently in control of said CPU, said virtual memory further having a push-down store for storing a plurality of different types of groups of information in stacks wherein the last group of information stored is the top of the stack, said groups of information being accessed in last-in-first-out fashion, each of said stacks being included within a uniquely addressable space bounded by one of said plurality of segments having adjustable bounds; a procedure call mechanism comprising:

- (a) first means for initiating a transfer of control of said CPU from a first procedure stored in a first of said plurality of segments to a second of said plurality of procedures, by providing a call signal to said second procedure;
- (b) second means responsive to said call signal for defining a plurality of data organizations, each of said data organizations having a predetermined format and being associated with a corresponding one of said plurality of procedures to receive data facilitating the transfer of control of said CPU from said first, calling procedure to said second, called procedure;
- (c) third means responsive to the level of privilege of a procedure for stacking said data organizations of said procedure into said push-down store of said virtual memory in a manner such that each of said stacks of data organizations is bounded by a predetermined one of said plurality of segments, said predetermined segment being classified with a level of privilege; and
- (d) and fourth means for identifying and storing the first loca-

tion of a top-most stack of data organizations in said push-down store.

4,297,744

PROCESS AND DEVICE FOR MULTIPLYING A STOCHASTIC VALUE BY A COEFFICIENT GREATER THAN THE UNIT

Jean-Claude Hoffmann; Francis Castanie, both of Toulouse; Henri Crabere, L'Union; Jean-Pierre Verdier, Cazeres, and Norbert Voisin, Bruguieres, all of France, assignors to Societe Nationale Industrielle Aerospatiale, Paris, France


Continuation of Ser. No. 956,963, Nov. 2, 1978, abandoned. This application Jun. 19, 1980, Ser. No. 161,009

Claims priority, application France, Nov. 9, 1977, 77 33777

Int. Cl.³ G06F 7/70

U.S. Cl. 364—703

11 Claims



3. A device for multiplying a stochastic value x not greater than 0.5 by a number $(1+K)$ wherein K is positive and not greater than 1, said stochastic value being coded by a random noise and being physically represented by an initial sequence of logic 0 and 1 levels such that in a certain interval of time, N logic 1 levels appear, comprising:

first means for forming, from said initial sequence representing x , a first auxiliary sequence comprising KN logic 1 levels;

second means for forming, from said initial sequence representing x , a second auxiliary sequence comprising N logic 1 levels, wherein each of said N logic 1 levels of said second auxiliary sequence occurs during a logic 0 level of said first auxiliary sequence; and

means for adding said first and second auxiliary sequences.

4,297,745

GAIN RANGING AMPLIFIER

James E. Layton, Ochelata, Okla., assignor to Phillips Petroleum Company, Bartlesville, Okla.

Filed Oct. 30, 1978, Ser. No. 955,903

Int. Cl.³ G01V 1/22; H03F 1/02

U.S. Cl. 367—66

10 Claims

1. In a seismic system for geophysical exploration comprising:

a plurality of remote geophone monitoring means, each of said remote geophone monitoring means being adapted to receive electrical signals from at least one geophone means; and

a central control means for generating electrical signals for initiating the operation of said plurality of remote geophone means;

each of said plurality of remote geophone monitoring means comprising:

a gain ranging amplifier means having a plurality of amplifiers for compressing the dynamic range of electrical analog signals;

means for converting the compressed electrical analog signals into digital seismic data; and

means for transmitting said digital seismic data to said central control means;

said central control means comprising:

means for transmitting commands to said plurality of remote geophone monitoring means; and

means for receiving data from said plurality of remote geophone monitoring means;

the improvement comprising:


means for grounding the input of each one of said plurality of amplifiers for which a voltage offset compensation value is to be calculated;

an analog-to-digital conversion means;

a computer means;

means for providing the output of each one of said plurality of amplifiers, having the inputs thereof grounded, to said analog-to-digital conversion means to therein convert the output of said plurality of amplifiers to digital form;

means for providing the digital output of said analog-to-digital conversion means to said computer means to therein calculate a voltage offset compensation value for each of said plurality of amplifiers for which it is desired to calculate a voltage offset compensation value, each voltage offset compensation value having a voltage level which, if applied to the input of a respective one of said plurality of amplifiers for which the particular voltage offset compensation value was calculated, would drive the output signal from the respec-



tive one of said plurality of amplifiers to essentially zero when no electrical analog input signal is applied to the input of the respective one of said plurality of amplifiers;

a digital memory means associated with said computer means;

means for providing the calculated voltage offset compensation values for each of said plurality of amplifiers to said digital memory means;

a digital-to-analog converter means;

means for providing said calculated voltage offset compensation values from said digital memory means to said digital-to-analog converter means; and

means for providing the particular voltage offset compensation value determined for a particular one of said plurality of amplifiers from said digital-to-analog converter means to that particular one of said plurality of amplifiers, said calculated voltage offset compensation values being transferred from said digital memory means to said digital-to-analog converter means when electrical analog input signals are applied to the input of at least one of said plurality of amplifiers and the particular voltage offset compensation value determined for a particular one of said plurality of amplifiers being transferred from said digital-to-analog converter means to that particular one of said plurality of amplifiers when an electrical analog input signal is applied to the input of that particular one of said plurality of amplifiers to thereby substantially reduce errors caused by voltage offset.

DESIGNS

OCTOBER 27, 1981

261,445

POCKET FOR JEANS OR THE LIKE


Martin Heinfling, Bayside, N.Y., assignor to Englishtown Sportswear, Ltd., New York, N.Y.

Filed Jan. 29, 1980, Ser. No. 116,426

Term of patent 14 years

Int. Cl. D2—02

U.S. Cl. D2—25



261,447

WORKMAN'S VEST

Matti Viio, Box 563, 191 05 Sollentuna, Sweden


Filed May 2, 1978, Ser. No. 902,153

Claims priority, application Sweden, Nov. 2, 1977, 2223

Term of patent 14 years

Int. Cl. D2—02

U.S. Cl. D2—190



261,446

SHOE

Michael W. Schmohl, Nuremberg, Fed. Rep. of Germany, assignor to Uniroyal GmbH, Aachen, Fed. Rep. of Germany


Filed May 26, 1978, Ser. No. 909,878

Claims priority, application Fed. Rep. of Germany, Nov. 29, 1977, 7736457[U]

Term of patent 14 years

Int. Cl. D2—04

U.S. Cl. D2—309



261,448

KEY RING ORNAMENT


Frank M. Liebscher, 298 Live Oak Rd., Watsonville, Calif. 95076

Filed Apr. 18, 1979, Ser. No. 31,071

Term of patent 14 years

Int. Cl. D3—01

U.S. Cl. D3—65



261,449

COUNTER DISPLAY STAND


Sydney Edson, East Meadow, N.Y., assignor to Howard Displays, Inc., New York, N.Y.

Filed Apr. 18, 1979, Ser. No. 31,081

Term of patent 14 years

Int. Cl. D20-02

U.S. Cl. D6-23



261,450

PORTABLE SEAT

Robert J. Jenkins, 5806 Georgia, Kansas City, Kans. 66104

Filed Oct. 13, 1978, Ser. No. 951,065

Term of patent 14 years

Int. Cl. D6-01

U.S. Cl. D6-26



261,451

SOFA


Ramon R. Albert, 630 NW. 7th Ave., Homestead, Fla. 33030

Filed Feb. 6, 1978, Ser. No. 875,581

Term of patent 14 years

Int. Cl. D6-01

U.S. Cl. D6-63



261,452

TOILET TISSUE COVER


Marlene Y. Chandler, 3174 Forest Manor, Indianapolis, Ind. 46218

Filed Oct. 26, 1979, Ser. No. 88,547

Term of patent 14 years

Int. Cl. D23-02

U.S. Cl. D6-86



261,453

COMBINED HOLDER AND DISPENSER FOR COLLAPSIBLE TUBES


Daniel L. Pool, 4414 E. Lincoln Dr., Paradise Valley, Ariz. 85253

Filed Nov. 30, 1979, Ser. No. 98,810

Term of patent 14 years

Int. Cl. D7-99

U.S. Cl. D6-87



261,454

POTTED PLANT HANGER


William Hobrecht, Brockton, Mass., assignor to New England Pottery Co., Stoughton, Mass.

Filed Sep. 24, 1979, Ser. No. 78,652

Term of patent 14 years

Int. Cl. D6-06; D11-02

U.S. Cl. D6-113



261,456

SERVICE COUNTER

James S. Berman, New York, and Sigurd Stegmaier, Malverne, both of N.Y., assignors to Citibank, N.A., New York, N.Y.

Division of Ser. No. 875,952, Feb. 7, 1978. This application Jan. 22, 1980, Ser. No. 114,305

Term of patent 14 years

Int. Cl. D6-04

U.S. Cl. D6-157



261,457

SERVICE COUNTER

James S. Berman, New York, and Sigurd Stegmaier, Malverne, both of N.Y., assignors to Citibank, N.A., New York, N.Y.

Division of Ser. No. 875,952, Feb. 7, 1978. This application Jan. 22, 1980, Ser. No. 114,311

Term of patent 14 years

Int. Cl. D6-04

U.S. Cl. D6-157



261,455

SPICE RACK


Carl H. Ewert, 1201 Monument Blvd., Apartment #76, Concord, Calif. 94520

Filed Aug. 9, 1979, Ser. No. 65,055

Term of patent 14 years

Int. Cl. D06-04; D07-07

U.S. Cl. D6-130



261,458

TELLER COUNTER


James S. Berman, New York, and Sigurd Stegmaier, Malverne, both of N.Y., assignors to Citibank, N.A., New York, N.Y.

Division of Ser. No. 875,944, Feb. 7, 1978. This application Jan. 22, 1980, Ser. No. 114,415

Term of patent 14 years

Int. Cl. D6-04


U.S. Cl. D6-157



261,459
DESK


James S. Berman, New York, and Sigurd Stegmaier, Malverne, both of N.Y., assignors to Citibank, N.A., New York, N.Y. Division of Ser. No. 875,941, Feb. 7, 1978. This application Jan. 22, 1980, Ser. No. 114,422
Term of patent 14 years
Int. Cl. D6—04

U.S. Cl. D6—157

261,460
DESK

James S. Berman, New York, and Sigurd Stegmaier, Malverne, both of N.Y., assignors to Citibank, N.A., New York, N.Y. Division of Ser. No. 875,941, Feb. 7, 1978. This application Jan. 22, 1980, Ser. No. 114,491
Term of patent 14 years
Int. Cl. D6—04

U.S. Cl. D6—157

261,461
SERVICE COUNTER

James S. Berman, New York, and Sigurd Stegmaier, Malverne, both of N.Y., assignors to Citibank, N.A., New York, N.Y. Division of Ser. No. 875,952, Feb. 7, 1978. This application Jan. 22, 1980, Ser. No. 114,304
Term of patent 14 years
Int. Cl. D6—04

U.S. Cl. D6—162

261,462
SERVICE COUNTER

James S. Berman, New York, and Sigurd Stegmaier, Malverne, both of N.Y., assignors to Citibank, N.A., New York, N.Y. Division of Ser. No. 875,952, Feb. 7, 1978. This application Jan. 22, 1980, Ser. No. 114,416
Term of patent 14 years
Int. Cl. D6—04

U.S. Cl. D6—162

261,463
SIMULATIVE PHOTO FRAME

Nick P. Martin, 438 Crescent, Santa Maria, Calif. 93454
Filed Apr. 14, 1980, Ser. No. 140,232
Term of patent 14 years
Int. Cl. D6—07

U.S. Cl. D6—243

261,464
COMBINATION BEACH TOWEL-CARRY BAG

Allan B. Smith, 31 Bathurst St., Woollahra, N.S.W. 2025, Australia
Filed Aug. 14, 1978, Ser. No. 933,650
Term of patent 14 years
Int. Cl. D6—13

U.S. Cl. D6—265

261,465
SERVING BOWL


Scott R. Minchew, 3778 Hillandale, Toledo, Ohio 43606
Filed Nov. 23, 1979, Ser. No. 96,844
Term of patent 14 years
Int. Cl. D07—01

U.S. Cl. D7—19

261,467
COMBINED KNIFE SET AND RACK



Paul P. Alessandrini, and Anna M. Alessandrini, both of 215-55 26th Ave., Bayside, N.Y. 11360
Filed Sep. 21, 1979, Ser. No. 77,619
Term of patent 14 years
Int. Cl. D7—07

U.S. Cl. D7—74

261,466
ICE CREAM CONE SERVING TRAY


Russell W. Harper, Oak Brook, Ill., assignor to Maryland Cup Corporation, Owings Mills, Md.
Filed Aug. 13, 1979, Ser. No. 66,294
Term of patent 14 years
Int. Cl. D07—99

U.S. Cl. D7—38

261,468
MICROWAVE OVEN

Yoichi Takahashi, Koriyama; Mashimichi Yamamura, Osaka; Toshio Harada, and Shigefumi Inoue, both of Nara, all of Japan, assignors to Matsushita Electric Industrial Co., Ltd., Kadoma, Japan
Filed Sep. 17, 1979, Ser. No. 76,006
Claims priority, application Japan, Mar. 16, 1979, 54-10693
Term of patent 14 years
Int. Cl. D7—02

U.S. Cl. D7—128



261,469

COMBINED ROTISSERIE MOTOR AND EXTENDED LIGHT


Walter Koziol, Russell, Ill., assignor to Modern Home Products Corp., Antioch, Ill.

Filed Apr. 2, 1979, Ser. No. 25,789

Term of patent 14 years

Int. Cl. D7-02

U.S. Cl. D7-129



261,470

COMBINED ROTISSERIE MOTOR AND LIGHT


Walter Koziol, Russell, Ill., assignor to Modern Home Products Corp., Antioch, Ill.

Filed Apr. 2, 1979, Ser. No. 26,034

Term of patent 14 years

Int. Cl. D7-02

U.S. Cl. D7-129



261,471

COMBINED ROTISSERIE MOTOR AND LIGHT


Walter Koziol, Russell, Ill., assignor to Modern Home Products Corp., Antioch, Ill.

Filed Dec. 31, 1979, Ser. No. 108,563

Term of patent 14 years

Int. Cl. D7-02

U.S. Cl. D7-129



261,472

FOOD CUTTER


Elwood M. Graham, Ocean Springs, Miss., and John Polivka, Ocean Side, Calif., assignors to M. H. Graham Corporation, Biloxi, Miss.

Filed Mar. 2, 1979, Ser. No. 16,777

Term of patent 14 years

Int. Cl. D07-04

U.S. Cl. D7-155



261,473

SUCTION BRUSH

Niklaus Hug, Romanshorn, Switzerland, assignor to Rommag P. Wörwag & Co., Romanshorn, Switzerland


Filed Jun. 12, 1979, Ser. No. 47,923

Claims priority, application Fed. Rep. of Germany, Dec. 12, 1978, 1218

Term of patent 14 years

Int. Cl. D7-05

U.S. Cl. D32-18



261,474

CLOTHES PIN

Clive E. Joseph, 1 Church Sq., St. Kilda, Victoria, 3182, Australia

Continuation-in-part of Ser. No. 947,697, Oct. 2, 1978, Pat. No. Des. 256,539. This application Oct. 15, 1979, Ser. No. 84,677

Claims priority, application Australia, May 31, 1979, 78011

Term of patent 14 years

Int. Cl. D7-05

U.S. Cl. D32-61



261,475

WOOD BOX


Raymond Wolfe, R.R. #1, Box 198, Farmland, Ind. 47340

Filed Jun. 25, 1979, Ser. No. 51,992

Term of patent 14 years

Int. Cl. D7-07; D6-04

U.S. Cl. D7-212



261,478

TAMPER PROOF STRIKER PLATE

William P. Gauntt, P.O. Box 744, Teague, Tex. 75860

Filed Aug. 20, 1979, Ser. No. 67,831

Term of patent 14 years

Int. Cl. D8-07

U.S. Cl. D8-344



261,479

COMBINED SHIPPING, STORAGE AND SERVING UNIT FOR BOTTLES OF WINE OR THE LIKE


Philip Marks, New York, N.Y., assignor to Advertising Displays Corporation, Englewood Cliffs, N.J.

Filed Jan. 15, 1979, Ser. No. 3,686

Term of patent 14 years

Int. Cl. D9-03

U.S. Cl. D9-341



261,476

WELDING GUN


Thomas P. O'Donnell, Wheaton, Ill., and James A. Howery, Menomonee Falls, Wis., assignors to C-R-O, Inc., Menomonee Falls, Wis.

Filed Aug. 30, 1979, Ser. No. 69,721

Term of patent 14 years

Int. Cl. D8-05

U.S. Cl. D8-30



261,480

COMBINED COSMETIC CONTAINER AND ABRADER
Jana Lowenthal, 8029 Willow Glen Dr., Los Angeles, Calif. 90046

Continuation of Ser. No. 841,330, Nov. 31, 1977. This application Feb. 11, 1980, Ser. No. 120,723

Term of patent 14 years

Int. Cl. D28-03

U.S. Cl. D9-314



261,477

CABLE OR RIVET CUTTER


Frank E. Shaffer, P.O. Box 1546, Costa Mesa, Calif. 92626

Filed Apr. 16, 1979, Ser. No. 29,994

Term of patent 14 years

Int. Cl. D8-03

U.S. Cl. D8-98



261,481

PACKAGING CONTAINER FOR CASSETTES OR THE LIKE


Carol A. Haubert, Upper Grandview, N.Y., assignor to Raytheon Company, Lexington, Mass.

Filed Sep. 4, 1979, Ser. No. 72,266

Term of patent 14 years

Int. Cl. D9-03

U.S. Cl. D9-341



261,483

COMBINED DISPLAY AND PACKAGING CONTAINER FOR A SHAVING UNIT


Donald Thorpe, Madison, Conn., assignor to Warner-Lambert Company, Morris Plains, N.J.

Filed Jun. 18, 1979, Ser. No. 49,685

Term of patent 14 years

Int. Cl. D9-03

U.S. Cl. D9-342



261,482

PACKAGING CONTAINER FOR CASSETTES OR THE LIKE

Carol A. Haubert, Upper Grandview, N.Y., assignor to Raytheon Company, Lexington, Mass.

Filed Sep. 4, 1979, Ser. No. 72,267

Term of patent 14 years

Int. Cl. D9-03

U.S. Cl. D9-341



261,484

PACKAGING CONTAINER FOR CASSETTES OR THE LIKE


Carol A. Haubert, Upper Grandview, N.Y., assignor to Raytheon Company, Lexington, Mass.

Filed Sep. 4, 1979, Ser. No. 72,268

Term of patent 14 years

Int. Cl. D9-03

U.S. Cl. D9-341



261,485

PACKAGING CONTAINER FOR CASSETTES OR THE LIKE


Carol A. Haubert, Upper Grandview, N.Y., assignor to Raytheon Company, Lexington, Mass.

Filed Sep. 4, 1979, Ser. No. 72,269

Term of patent 14 years

Int. Cl. D9-03

U.S. Cl. D9-341



261,487

THERMOMETER

Yoshiharu Kohno, Suita, Japan, assignor to Kohno Plastic Co., Ltd., Osaka, Japan

Filed Dec. 11, 1979, Ser. No. 102,451

Term of patent 14 years

Int. Cl. D10-04

U.S. Cl. D10-58



261,486

CONTAINER CLOSURE OR SIMILAR ARTICLE


Ernest L. Smith, Kansas City, Mo., assignor to Phillips Petroleum Co., Bartlesville, Okla.

Filed Sep. 5, 1979, Ser. No. 72,754

Term of patent 14 years

Int. Cl. D09-07

U.S. Cl. D9-452



261,488

MULTIMETER


James R. Lindsay, Yorba Linda, and Gene D. Vedder, Reseda, both of Calif., assignors to Beckman Instruments, Inc., Fullerton, Calif.

Filed Jul. 9, 1979, Ser. No. 55,940

Term of patent 14 years

Int. Cl. D10-04

U.S. Cl. D10-78




261,489

REFLECTOR

Arthur E. DuBois, Box 707, Dennisport, Mass. 02639
 Filed Dec. 7, 1978, Ser. No. 967,230
 Term of patent 14 years
 Int. Cl. D10—06

U.S. Cl. D10—111



261,490

FIGURINE OF A BASSET HOUND

Jesus A. S. Carbajales, and Javier B. S. Carbajales, both of Montevideo, Uruguay, assignors to John J. Madison Company, Inc., Laguna Hills, Calif.
 Filed Sep. 29, 1978, Ser. No. 946,847
 Term of patent 14 years
 Int. Cl. D11—02

U.S. Cl. D11—158




261,491

TIRE TREAD AND BUTTRESS


Philip S. Hammond, Mogadore, Ohio, assignor to The Goodyear Tire & Rubber Company, Akron, Ohio
 Filed Mar. 16, 1979, Ser. No. 21,138
 Term of patent 14 years
 Int. Cl. D12—15

U.S. Cl. D12—142

261,492
TIRE


Raymond M. Remy, Capellen, Luxembourg, assignor to The Goodyear Tire & Rubber Company, Akron, Ohio
 Filed Jan. 8, 1979, Ser. No. 1,634
 Term of patent 14 years
 Int. Cl. D12—15

U.S. Cl. D12—143

261,493
TIRE

Andre E. J. Baus, Colmar-Berg, Luxembourg, and Robert E. L. A. Pair, Arlon, Belgium, assignors to The Goodyear Tire & Rubber Company, Akron, Ohio
 Filed Jan. 8, 1979, Ser. No. 1,987
 Term of patent 14 years
 Int. Cl. D12—15

U.S. Cl. D12—143




261,494

VEHICLE TIRE

Norio Suzuki, Kodaira, and Hiroshi Kojima, Hino, both of Japan, assignors to Bridgestone Tire Company, Limited, Tokyo, Japan


Filed Apr. 3, 1979, Ser. No. 26,708
 Claims priority, application Japan, Jan. 31, 1979, 542969
 Term of patent 14 years
 Int. Cl. D12—15

U.S. Cl. D12—146

261,496
TIRE

Raymond M. Remy, Capellen, Luxembourg, assignor to The Goodyear Tire & Rubber Company, Akron, Ohio
 Filed Jan. 8, 1979, Ser. No. 1,635
 Term of patent 14 years
 Int. Cl. D12—15


U.S. Cl. D12—147

261,497
TIRE

Andre E. J. Baus, Colmar-Berg; Jean F. L. Fontaine, Ingeldorf, and Brian L. Ham, Mertzig, all of Luxembourg, assignors to The Goodyear Tire & Rubber Company, Akron, Ohio
 Filed Feb. 21, 1979, Ser. No. 13,492
 Claims priority, application United Kingdom, Sep. 27, 1978, 986566

Term of patent 14 years
 Int. Cl. D12—15

U.S. Cl. D12—147



261,495

TIRE TREAD AND BUTTRESS

Charles G. Yurkovich, Boardman, Ohio, assignor to The Goodyear Tire & Rubber Company, Akron, Ohio
 Filed Apr. 30, 1979, Ser. No. 34,703
 Term of patent 14 years
 Int. Cl. D12—15

U.S. Cl. D12—146




261,498
TIRE

Andre E. J. Baus, Colmar-Berg, Luxembourg, assignor to The Goodyear Tire & Rubber Company, Akron, Ohio
Filed Feb. 21, 1979, Ser. No. 13,590
Claims priority, application United Kingdom, Sep. 20, 1978, 986440

Term of patent 14 years
Int. Cl. D12-15


U.S. Cl. D12-148



261,500
VEHICLE VISOR


James P. Butler, Lewisville, Tex., assignor to Affiliated Hatch and Sunroof, Inc., Dallas, Tex.
Filed Dec. 4, 1978, Ser. No. 966,470
Term of patent 14 years
Int. Cl. D12-16

U.S. Cl. D12-191



261,501
COMBINED AIR MUFFLER AND FILTER
Michael Schenker, Warren, N.J., assignor to Coilhose Pneumatics, Inc., Middlesex, N.J.
Filed Aug. 10, 1979, Ser. No. 65,592
Term of patent 14 years
Int. Cl. D12-16

U.S. Cl. D12-194



261,502
WHEEL

Bjorn E. A. Envall, Vanersborg, Sweden, assignor to Saab-Scania Aktiebolag, Trollhattan, Sweden
Filed Oct. 18, 1978, Ser. No. 952,566
Claims priority, application Sweden, Apr. 18, 1978, 78-1085
Term of patent 14 years
Int. Cl. D12-16


U.S. Cl. D12-211



261,499

STORAGE TRUNK FOR A PICKUP TRUCK
Charles J. Sauber, 10 N. Sauber Rd., Virgil, Ill. 60182
Filed Jul. 12, 1979, Ser. No. 56,977
Term of patent 14 years
Int. Cl. D12-16


U.S. Cl. D12-157



261,503

C.A.T.V. SIGNAL SPLITTER
David F. Shu, Hoffman Estate, Ill., assignor to TDS, Inc., Elk Grove Village, Ill.
Filed Apr. 18, 1979, Ser. No. 31,082
Term of patent 14 years
Int. Cl. D13-03


U.S. Cl. D13-11



261,506

TAPE RECORDER AND PLAYER OR SIMILAR ARTICLE
Richard Culbertson, Manlius, N.Y., assignor to General Electric Company, New York, N.Y.
Filed Sep. 10, 1979, Ser. No. 73,741
Term of patent 14 years
Int. Cl. D14-01


U.S. Cl. D14-6



261,504

PIN SOCKET
Gene C. Hollingsworth, Cerritos, Calif., assignor to Zero Corporation, El Monte, Calif.
Filed Oct. 2, 1978, Ser. No. 947,426
Term of patent 14 years
Int. Cl. D13-03


U.S. Cl. D13-24



261,507

TELEPHONE
Wesley L. Thomas, 109 S. Catalina St., Los Angeles, Calif. 90004
Filed May 7, 1979, Ser. No. 36,587
Term of patent 14 years
Int. Cl. D14-03


U.S. Cl. D14-53



261,505

ELECTRICAL CONTROL HOUSING ASSEMBLY
Gerald K. Miller, Hersey, Mich., assignor to Nartron Corporation, Reed City, Mich.
Filed Sep. 12, 1979, Ser. No. 74,635
Term of patent 14 years
Int. Cl. D13-03

U.S. Cl. D13-32



261,508

HAND-HELD TELEPHONE


John Pardo, Yonkers, N.Y., assignor to Leisurecraft Products Ltd., Plainview, N.Y.

Filed Aug. 10, 1979, Ser. No. 65,599

Term of patent 14 years

Int. Cl. D14-03

U.S. Cl. D14-64



261,510

TELEPHONE HANDSET HOLDER


John H. Havens, Los Angeles, Calif., assignor to Antonio M. Escobedo, Sepulveda, Calif.

Filed Jul. 18, 1979, Ser. No. 58,731

Term of patent 14 years

Int. Cl. D14-03

U.S. Cl. D14-65



261,511

RADIO RECEIVER


William J. Hass, 3707 Russett La., Northbrook, Ill. 60062

Filed Dec. 14, 1979, Ser. No. 103,570

Term of patent 14 years

Int. Cl. D14-03

U.S. Cl. D14-68



261,509

WALL MOUNTED HOLDER FOR A TELEPHONE SET

Richard E. Cobb, Western Springs, Ill., assignor to GTE Automatic Electric Labs. Inc., Northlake, Ill.

Filed Jun. 4, 1979, Ser. No. 44,899

Term of patent 14 years

Int. Cl. D14-03; D6-01

U.S. Cl. D14-65



261,512

CLOCK RADIO OR SIMILAR ARTICLE


John S. Kolwaite, Dewitt, N.Y., assignor to General Electric Company, New York, N.Y.

Filed Jan. 23, 1980, Ser. No. 114,712

Term of patent 14 years

Int. Cl. D14-03; D10-01

U.S. Cl. D14-73



261,513

TRANSMISSION DETENT CABLE CONNECTOR


Richard B. Muller, 5415 Providence Rd., Charlotte, N.C. 28211

Filed Jan. 18, 1979, Ser. No. 4,500

Term of patent 14 years

Int. Cl. D15-99

U.S. Cl. D15-5



261,515

PRESSURE SPRAY CARPET CLEANER


Harold W. Schaefer, Bloomington, Ill., and Martin E. Wiese, South Bend, Ind., assignors to National Union Electric Corporation, Greenwich, Conn.

Filed Aug. 20, 1979, Ser. No. 67,730

Term of patent 14 years

Int. Cl. D15-05

U.S. Cl. D32-23



261,516

MACHINE FOR DISPENSING AND INSERTING STICKS IN COMESTIBLES


Edward D. Cottrell, and Michael B. Robbins, both of Cataaugus, N.Y., assignors to Champion International Corporation, Stamford, Conn.

Filed May 24, 1979, Ser. No. 42,002

Term of patent 14 years

Int. Cl. D07-04; D15-08

U.S. Cl. D15-92



261,514

VACUUM CLEANER



Patrick D. Cody, Dollard des Ormeaux, Canada, assignor to Innova Equipment Limited, Quebec, Canada

Filed Dec. 27, 1979, Ser. No. 107,572

Term of patent 14 years

Int. Cl. D15-05

U.S. Cl. D32-21



261,517

FOODSTUFF MILL



Thomas D. Dickson, Jr., 1099 Del Cambre, San Jose, Calif. 95129

Filed Apr. 9, 1979, Ser. No. 28,208

Term of patent 14 years

Int. Cl. D15-08

U.S. Cl. D15-98



261,518

BARRIER FREE DRINKING FOUNTAIN



Ann F. Butter, and Bert Blumberg, both of 12 W. 96th St., New York, N.Y. 10025

Filed Apr. 30, 1979, Ser. No. 34,428

Term of patent 14 years

Int. Cl. D23-01

U.S. Cl. D15-118



261,519

HOUSING FOR A BENCH TOP BAND SAW


Edward A. Irelan, Columbia, Mo., assignor to Benchmark Tool Company, Vandalia, Ohio

Filed Aug. 31, 1979, Ser. No. 71,181

Term of patent 14 years

Int. Cl. D15-09

U.S. Cl. D15-134



261,520

TWO-WHEELED OIL REFINER DOLLY OR THE LIKE


Lester L. Johnson, Sr., 6175 Fordham Cir., East, Jacksonville, Fla. 32217

Filed Aug. 22, 1979, Ser. No. 68,695

Term of patent 14 years

Int. Cl. D15-99

U.S. Cl. D15-150



261,522

PAPER COLLATOR FOR USE WITH OFFICE COPYING MACHINES


Donald L. Snellman, 2807 W. Galer, Seattle, Wash. 98199

Filed Oct. 18, 1979, Ser. No. 86,032

Term of patent 14 years

Int. Cl. D16-03

U.S. Cl. D16-32



261,523

ELECTRONIC FLASH OR SIMILAR ARTICLE


James M. Conner, Harrison, and James M. Ryan, New York, both of N.Y., assignors to Polaroid Corporation, Cambridge, Mass.

Filed Sep. 25, 1978, Ser. No. 945,190

Term of patent 14 years

Int. Cl. D16-05

U.S. Cl. D16-42



261,521

OIL REFINER MOVABLE CARRIAGE OR THE LIKE


Lester L. Johnson, Sr., 6175 Fordham Cir., East, Jacksonville, Fla. 32217

Filed Aug. 22, 1979, Ser. No. 68,696

Term of patent 14 years

Int. Cl. D15-99

U.S. Cl. D15-150



261,524

GRIP FOR A CINECAMERA


Masahiro Kando, Tokyo, and Hiroshi Shinkai, Yokohama, both of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan
Filed Dec. 26, 1978, Ser. No. 973,110

Claims priority, application Japan, Jul. 3, 1978, 53-27956

Term of patent 14 years

Int. Cl. D16—05

U.S. Cl. D16—44



261,527

BRIDGE ASSEMBLY FOR GUITARS


Billie R. Carson, Placentia, Calif., assignor to CBS Inc., New York, N.Y.

Filed Oct. 11, 1979, Ser. No. 83,588

Term of patent 14 years

Int. Cl. D17—03

U.S. Cl. D17—21



261,528

DESK TOP ELECTRONIC CALCULATOR

Masaaki Sakai, Tokyo, and Kunio Hirose, Yokohama, both of Japan, assignors to Canon Kabushiki Kaisha, Tokyo, Japan
Filed Jun. 28, 1979, Ser. No. 52,989

Claims priority, application Japan, Jan. 15, 1979, 54-2567

Term of patent 14 years

Int. Cl. D18—01

U.S. Cl. D18—7



261,525

EYE GLASS FRAME


Irving Rips, Beverly Hills, Calif., assignor to Younger Manufacturing Company, Los Angeles, Calif.

Filed Jun. 11, 1979, Ser. No. 47,789

Term of patent 14 years

Int. Cl. D16—06

U.S. Cl. D16—115



261,526

BRIDGE ASSEMBLY FOR GUITARS


Billie R. Carson, Placentia, Calif., assignor to CBS Inc., New York, N.Y.

Filed Oct. 9, 1979, Ser. No. 82,667

Term of patent 14 years

Int. Cl. D17—03

U.S. Cl. D17—21



261,529

COMBINED PUNCH AND BINDING MACHINE


Herbert H. Hausmann, Prairie View, Ill., assignor to General Binding Corporation, Northbrook, Ill.

Filed Sep. 4, 1979, Ser. No. 72,484

Term of patent 14 years

Int. Cl. D18—04

U.S. Cl. D18—34



261,530

COMBINED ELECTRIC PUNCH AND BINDING MACHINE


Herbert H. Hausmann, Prairie View, Ill., assignor to General Binding Corporation, Northbrook, Ill.

Filed Sep. 4, 1979, Ser. No. 72,486

Term of patent 14 years

Int. Cl. D18—04

U.S. Cl. D18—34



261,532

WRIST-WEARABLE TIME TEACHING INSTRUMENT

Toshinori Tabata, Tokyo, Japan, assignor to Tomy Kogyo Co., Inc., Tokyo, Japan

Filed Nov. 2, 1979, Ser. No. 90,546

Claims priority, application Japan, May 21, 1979, 54-20597

Term of patent 14 years

Int. Cl. D19—07

U.S. Cl. D19—64



261,533

TYPING COPY HOLDER


Bruce K. Nagley, 4765 Kingshill Dr., Columbus, Ohio 43229

Filed Feb. 21, 1980, Ser. No. 123,126

Term of patent 14 years

Int. Cl. D19—02

U.S. Cl. D19—91



261,531

MARKING PEN

Guy Delcroix, Paris, France, assignor to Waterman S.A., Paris, France

Filed Jun. 11, 1979, Ser. No. 47,108

Claims priority, application France, Dec. 12, 1978, 77111

Term of patent 14 years

Int. Cl. D19—06

U.S. Cl. D19—4



261,534

POCKET SIZE GAME BOX

Masaki Mayuzumi, and Masaaki Yoshimura, both of Tokyo, Japan, assignors to Tomy Kogyo Co., Inc., Tokyo, Japan


Filed Nov. 2, 1979, Ser. No. 90,312

Claims priority, application Japan, May 23, 1979, 54-20883

Term of patent 14 years

Int. Cl. D21—01

U.S. Cl. D21—10



261,535

COMBINED BACKGAMMON GAME AND CARRYING CASE


Abraham I. Tawil, New York, N.Y., assignor to H.I.T. Industries Ltd., Avenel, N.J.

Filed May 12, 1977, Ser. No. 796,206

Term of patent 14 years

Int. Cl. D21-01

U.S. Cl. D21-15



261,537

GAME BOARD


Richard D. Homich, Box 600, R.D. 3, Annville, Pa. 17003

Filed Oct. 2, 1979, Ser. No. 81,238

Term of patent 14 years

Int. Cl. D21-01

U.S. Cl. D21-34



261,536

GAME BOARD


Michael C. Cicerella, 1524 Lakeview Rd., #203, Clearwater, Fla. 33516

Filed Dec. 17, 1979, Ser. No. 104,164

Term of patent 14 years

Int. Cl. D21-01

U.S. Cl. D21-20



261,538

AERIAL TOY


James E. Sides, Rte. 3, Western Acres, El Campo, Tex. 77437

Filed Jul. 2, 1979, Ser. No. 54,137

Term of patent 14 years

Int. Cl. D21-01

U.S. Cl. D21-86



261,539

SHILLELAGH OR SIMILAR ARTICLE

Ernest H. Smith, P.O. Box 891, W. Sacramento, Calif. 95691

Filed Dec. 30, 1977, Ser. No. 866,461

Term of patent 14 years

Int. Cl. D21-01

U.S. Cl. D21-211



261,541


COMBINED TOY BUCKET AND TOOLS THEREFOR
Mel Appel, Nine Nottingham Rd., Livingston, N.J. 07039, and George Kress, Scotch Plains, N.J., assignors to Mel Appel, Livingston, N.J.

Filed Feb. 8, 1980, Ser. No. 119,992

Term of patent 14 years

Int. Cl. D21-01

U.S. Cl. D21-120



261,542

INTEGRAL SHOE SOLE AND WHEEL MOUNTING FOR ROLLER SKATE


David L. Landay, Brookline, and Alvan H. Wolf, Worcester, both of Mass., assignors to Brookfield Athletic Shoe Company, Inc., East Brookfield, Mass.

Filed Jul. 18, 1979, Ser. No. 40,115

Term of patent 14 years

Int. Cl. D21-02

U.S. Cl. D21-226



261,540


COMBINED TOY BUCKET AND TOOLS THEREFOR
Mel Appel, Nine Nottingham Rd., Livingston, N.J. 07039, and Paul B. Means, III, Basking Ridge, N.J., assignors to Mel Appel, Livingston, N.J.

Filed Oct. 22, 1979, Ser. No. 87,243

Term of patent 14 years

Int. Cl. D21-01

U.S. Cl. D21-120



261,543

SKATEBOARD


Leonard A. Morris, Sr., 138 Panorama Dr., Benicia, Calif. 94510

Filed Jan. 28, 1980, Ser. No. 115,740

Term of patent 14 years

Int. Cl. D21-02

U.S. Cl. D21-227




261,544

SKATEBOARD

Lyle L. Cramer, 1113 Markham, Flint, Mich. 48507
Continuation-in-part of Ser. No. 900,333, Apr. 26, 1978,
abandoned. This application Sep. 2, 1980, Ser. No. 183,047
Term of patent 7 years
Int. Cl. D21—02

U.S. Cl. D21—227




261,547

AIR REGULATING NOZZLE

W. Rod Parke, R.F.D. No. 3, Dixon, Ill. 61021
Filed May 29, 1979, Ser. No. 42,859
Term of patent 14 years
Int. Cl. D23—01

U.S. Cl. D23—34




261,545

ADJUSTABLE PLUG FOR SHOTGUN SHELL CHAMBER

Larry A. Holmberg, 5765 Main St., Fridley, Minn. 55432
Filed Mar. 3, 1980, Ser. No. 126,533
Term of patent 14 years
Int. Cl. D22—01

U.S. Cl. D22—7



261,548

MODULAR SHOWER STALL

James E. Chisholm, Mariemont, Ohio, assignor to MCC-Powers-Fiat, Skokie, Ill.

Filed Jun. 1, 1979, Ser. No. 44,703

Term of patent 14 years

Int. Cl. D23—02



U.S. Cl. D23—57

261,546

FISH HOLDING TOOL

Ronald W. Smalley, 5415 SE, 174th St., Portland, Oreg. 97236
Filed Apr. 14, 1980, Ser. No. 140,233
Term of patent 14 years
Int. Cl. D22—05; D8—03

U.S. Cl. D22—31




261,549

PEDIATRIC EXAMINATION TABLE

Donald R. Patterson, 2509 Jackson, Joplin, Mo. 64801
Filed Apr. 12, 1979, Ser. No. 29,286
Term of patent 14 years
Int. Cl. D24—01

U.S. Cl. D24—3



261,552

HOUSING FOR AN ELECTRONIC STIMULATOR

Eli Boroda, 3896 Effress Rd., White Bear Lake, Minn. 55110
Filed May 10, 1979, Ser. No. 37,634
Term of patent 14 years
Int. Cl. D24—02

U.S. Cl. D24—41




261,550

CONTACT LENS STERILIZER UNIT

Michael D. Thomas, and Francis E. Ryder, both of Arab, Ala.,
assignors to Ryder International Corporation, Arab, Ala.
Filed Aug. 23, 1979, Ser. No. 69,112
Term of patent 14 years
Int. Cl. D24—02

U.S. Cl. D24—9




261,553

ASPHALT PLANT CONTROL HOUSE

Richard F. Chambers, 8431 Dayton Pike, Daisy, Tenn. 37319
Filed May 2, 1980, Ser. No. 146,001
Term of patent 14 years
Int. Cl. D25—03

U.S. Cl. D25—22



261,551

HOUSING FOR AN ELECTRONIC STIMULATOR


Eli Boroda, 3896 Effress Rd., White Bear Lake, Minn. 55110
Filed May 10, 1979, Ser. No. 37,633
Term of patent 14 years
Int. Cl. D24—02

U.S. Cl. D24—41

**CABLE CHANNEL SHELF**

Bengt E. Legerius, Hagvägen 6, S-611 00 Nyköping, Sweden
Filed Feb. 19, 1980, Ser. No. 122,303
Claims priority, application Sweden, Sep. 7, 1979, 79-1983
Term of patent 14 years
Int. Cl. D25—01

U.S. Cl. D25—74



261,555

EXPANSION JOINT SEALING STRIP FOR ROADWAY JOINTS AND THE LIKE


William E. Bowman, Englewood, Colo., assignor to Bowman Construction Supply, Inc., Denver, Colo.

Filed Mar. 26, 1980, Ser. No. 134,310

Term of patent 14 years

Int. Cl. D25—01

U.S. Cl. D25—74



261,556

COMBINED LAMP BASE AND BALL HOLDER


Bryan O'Reilly, 129 Franklin St., Westfield, Mass. 01085

Filed May 31, 1979, Ser. No. 44,052

Term of patent 14 years

Int. Cl. D26—05; D6—04

U.S. Cl. D26—51



261,557

LIGHTING FIXTURE

James J. Palka, Arlington Heights, and Robert Rekart, Villa Park, both of Ill., assignors to General Bathroom Products Company, Elk Grove Village, Ill.

Filed May 4, 1979, Ser. No. 35,997

Term of patent 3½ years

Int. Cl. D26—05

U.S. Cl. D26—87



261,558

LIGHTING FIXTURE


James J. Palka, Arlington Heights, and Robert Rekart, Villa Park, both of Ill., assignors to General Bathroom Products Company, Elk Grove Village, Ill.

Filed May 4, 1979, Ser. No. 36,000

Term of patent 3½ years

Int. Cl. D26—05

U.S. Cl. D26—87



261,559

LIGHTING FIXTURE


James J. Palka, Arlington Heights, and Robert Rekart, Villa Park, both of Ill., assignors to General Bathroom Products Company, Elk Grove Village, Ill.

Filed May 4, 1979, Ser. No. 36,001

Term of patent 3½ years

Int. Cl. D26—05

U.S. Cl. D26—87



261,560

LIGHTING FIXTURE


James J. Palka, Arlington Heights, and Robert Rekart, Villa Park, both of Ill., assignors to General Bathroom Products Company, Elk Grove Village, Ill.

Filed May 4, 1979, Ser. No. 36,002

Term of patent 3½ years

Int. Cl. D26—05

U.S. Cl. D26—87



261,561

LIGHTING FIXTURE

Marc-André Letourneau, 3600 Park Ave., Apt. 1611, Montreal, Quebec, Canada

Filed Feb. 16, 1979, Ser. No. 12,602

Term of patent 14 years

Int. Cl. D26—05

U.S. Cl. D26—88



261,562

LAMP

Akira Suzuki, Tokyo, Japan, assignor to Kazusuke Takagi, Tokyo, Japan, a part interest

Filed Oct. 4, 1979, Ser. No. 81,679

Term of patent 14 years

Int. Cl. D26—05

U.S. Cl. D26—111



261,563

HAIR DRYER



Ernest Lee, Park Ridge, Ill., assignor to Sunbeam Corporation, Chicago, Ill.

Filed Jun. 30, 1980, Ser. No. 164,191

Term of patent 14 years

Int. Cl. D28—03

U.S. Cl. D28—13



261,564

RAZOR HANDLE

Norman D. Poisson, Andover, Mass., assignor to The Gillette Company, Boston, Mass.

Filed Dec. 7, 1979, Ser. No. 101,164

Term of patent 14 years

Int. Cl. D28—03

U.S. Cl. D28—48



261,565
RAZOR HANDLE

Kenneth H. Grange, London, England, assignor to Wilkinson Sword Ltd., Buckinghamshire, England
Filed Jan. 3, 1980, Ser. No. 109,290
Claims priority, application United Kingdom, Jul. 16, 1979, 990 721/79

Term of patent 14 years
Int. Cl. D28—03

U.S. Cl. D28—48




261,567
MAKE-UP MIRROR

Alfred W. Madl, Glendale, Wis., assignor to Sunbeam Corporation, Chicago, Ill.

Filed Feb. 8, 1980, Ser. No. 119,731
Term of patent 14 years
Int. Cl. D28—03

U.S. Cl. D28—67




261,568
COMBINED CADDY FOR POWDERED PRODUCTS OR THE LIKE AND IMPLEMENTS THEREFOR

Ralph L. Davis, Washington, D.C., assignor to Wilbert A. Payne, Seat Pleasant, Md.

Filed Feb. 14, 1979, Ser. No. 12,031
Term of patent 14 years
Int. Cl. D28—03

U.S. Cl. D28—77





261,569
DRUM

Roger E. Darois, Perryville, Md., assignor to Container Corporation of America, Chicago, Ill.

Filed Sep. 4, 1979, Ser. No. 72,568
Term of patent 14 years
Int. Cl. D99—99

U.S. Cl. D34—39



261,566

COMBINATION FLOSS HOLDER, KEY CHAIN FOB AND DENTAL APPOINTMENT REMINDER

David V. Olson, St. Paul, Minn.
Continuation-in-part of Ser. No. 881,078, Feb. 23, 1978, Pat. No. Des. 255,388. This application Jul. 30, 1979, Ser. No. 62,101

Term of patent 14 years
Int. Cl. D29—99; D3—01

U.S. Cl. D28—64

LIST OF PATENTEEES

TO WHOM

PATENTS WERE ISSUED ON THE 27TH DAY OF OCTOBER, 1981

NOTE.—Arranged in accordance with the first significant character or word of the name (in accordance with city and telephone directory practice).

- A. B. Carl Munters: See—
Norbach, Per, 4,296,780, Cl. 138-40.000.
- AB ASEA-ATOM: See—
Olsson, Torsten, 4,297,171, Cl. 376-440.000.
- AB Jarnkonstruktioner: See—
Jarnum, Lennart, 4,296,516, Cl. 14-71.700.
- AB Volvo: See—
Mattsson, Karl-Erik H., 4,296,679, Cl. 92-52.000.
- Abbott Laboratories: See—
Muettteries, Andrew J.; Vcelka, John L.; and Kelsey, Wayne R., 4,296,949, Cl. 285-18.000.
- Abe, Kazunobu; Nakatsuji, Tadao; and Umaba, Toshikatsu, to Sakai Chemical Industry Co., Ltd. Method for packing catalysts. 4,297,248, Cl. 252-477.00R.
- Abe, Osamu: See—
Furuhashi, Toshio; and Abe, Osamu, 4,296,722, Cl. 123-492.000.
- Abe, Yoshiaki; Inoue, Shigeo; and Ishida, Atsuo, to Kao Soap Co., Ltd. Cosmetic composition for skin and hair treatment. 4,297,340, Cl. 424-70.000.
- Abele, Karl-Heinz: See—
Hoffken, Erich; Kleine-Kleffmann, Werner; Bertram, Rolf; Abele, Karl-Heinz; and Michalski, Gunter, 4,297,151, Cl. 148-9.00R.
- Abeler, Gerd; and Maul, Rudolf, to Ciba-Geigy Corporation. 1,4-Dihydro-2,6-dimethylpyridine-3,5-dicarboxylic acid ester compositions. 4,297,268, Cl. 260-45.80N.
- Abex Corporation: See—
Kennedy, Leroy P., 4,296,707, Cl. 116-58.00A.
- Abo, Toshimi; and Kanegae, Hidetoshi, to Nissan Motor Company, Limited. Fuel control device for a gas turbine. 4,296,600, Cl. 60-39.28R.
- Abolfotoh, Mohamed O., to International Business Machines Corporation. D.C. Scan panel. 4,297,613, Cl. 315-58.000.
- Abramovich, Dan: See—
Yenzer, Dennis E.; Cha, John H.; and Abramovich, Dan, 4,297,054, Cl. 405-168.000.
- Abrams, Richard L.: See—
Marom, Emanuel; Barnoski, Michael K.; and Abrams, Richard L., 4,297,704, Cl. 343-113.00R.
- Accattino, Andrea: See—
Becchi, Raffaele; Giaccone, Felice; and Accattino, Andrea, 4,297,573, Cl. 250-231.05E.
- ACF Chemiefarma NV: See—
van Zorge, Jacob A., 4,297,359, Cl. 424-263.000.
- Achard, Georges; Chion, Pierre; and Menault, Jacques, to Rhone-Poulenc-Textile. Two-component mixed acrylic fibres wherein acrylic components have different amounts of non-ionizable plasticizing comonomer. 4,297,412, Cl. 428-370.000.
- Acurex Corporation: See—
Carlton, Richard J., 4,297,572, Cl. 250-203.00R.
- Adams, James R., Jr., to Rollei of America, Inc. Photoflash device. 4,297,011, Cl. 354-23.00D.
- Adamson, Arthur P., to General Electric Company. Turbine cooling air modulation apparatus. 4,296,599, Cl. 60-39.230.
- Adreas Stihl: See—
Dirks, Rudolf; and Nitschmann, Karl, 4,296,553, Cl. 30-381.000.
- Aeroquip Corporation: See—
Allread, Alan R., 4,296,914, Cl. 251-149.200.
- Gies, Paul E., 4,296,675, Cl. 91-396.000.
- McCracken, Donald G., 4,296,952, Cl. 285-98.000.
- Agence Nationale de valorisation de la Recherche (ANVAR): See—
Monties, Jean R.; and Havlik, Patrick J. C., 4,296,500, Cl. 3-1.700.
- Agency of Industrial Science & Technology: See—
Shimizu, Ken-Ichi; and Ikeya, Chuji, 4,297,725, Cl. 358-125.000.
- AGFA-Gevaert AG: See—
Bergthaller, Peter; Saleck, Wilhelm; Lapp, Otto; and Mucke, Bruno, 4,297,439, Cl. 430-434.000.
- Stemme, Otto; Fergg, Berthold; Osegowitsch, Viktor; and Viehrig, Wolfgang, 4,297,027, Cl. 355-27.000.
- AGFA-Gevaert Aktiengesellschaft: See—
Haseler, Helmut; Meckl, Heinz; Lohmer, Karl; and Pelz, Willibald, 4,297,438, Cl. 430-377.000.
- Puschmann, Werner, 4,297,585, Cl. 250-560.000.
- Aggarwal, Sundar L.: See—
Bingham, Robert E.; Durst, Richard R.; Fabris, Hubert J.; Hargis, Ivan G.; Livigni, Russell A.; and Aggarwal, Sundar L., 4,297,240, Cl. 252-431.00R.
- Agip Nucleare, S.p.A.: See—
Brambilla, Giovanni; and Sartorelli, Adelmo, 4,297,174, Cl. 204-1.500.
- Ahmann, John E. Punch frame for data registering device. 4,297,566, Cl. 235-50.00R.
- Ahmed, Adel A. A., to RCA Corporation. Amplifier with cross-over current control. 4,297,644, Cl. 330-264.000.
- Ahrens, Paul W., to Miracle Recreation Equipment Company. Playground swing. 4,296,923, Cl. 272-85.000.
- Ahrweiler, Karl-Heinz: See—
Kusters, Eduard; and Ahrweiler, Karl-Heinz, 4,296,537, Cl. 29-116.0AD.
- Aikoh Co., Ltd.: See—
Hayashi, Yoshihiro, 4,296,921, Cl. 266-270.000.
- Aimono, Yuji: See—
Koyama, Tohru; Narahara, Toshikazu; and Aimono, Yuji, 4,297,471, Cl. 526-328.000.
- Airey, Frederick K.; and Evans, Arthur R. Apparatus for separating and contacting friable particulate organic matter from and with liquids. 4,297,213, Cl. 210-195.100.
- Aisin Seiki Kabushiki Kaisha: See—
Fujimori, Fumio; Yokoi, Masatada; Ishikawa, Masakazu; Uemura, Hiroshi; and Shirai, Akira, 4,296,841, Cl. 188-73.380.
- Kagata, Tooru; and Goto, Hiromi, 4,296,848, Cl. 192-35.000.
- Kizaki, Jiro; and Fujii, Takashi, 4,296,604, Cl. 60-562.000.
- Terada, Takami, 4,296,966, Cl. 297-369.000.
- Aitken, Inc.: See—
Cusick, Kenneth M., 4,297,116, Cl. 55-319.000.
- Ajinomoto Company, Incorporated: See—
Hikuma, Motohiko; Kubo, Tatsuru; Yasuda, Takeo; Karube, Isao; and Suzuki, Shuichi, 4,297,173, Cl. 204-1.00T.
- Yasuda, Naohiko; and Nakanishi, Eiji, 4,297,279, Cl. 260-239.100.
- Akebono Brake Industry Co., Ltd.: See—
Nakazato, Hiroshi, 4,296,971, Cl. 303-115.000.
- Akimoto, Hidetoshi: See—
Ishibashi, Yoji; Uchiyama, Yoshihiro; Akimoto, Hidetoshi; and Sasaki, Makoto, 4,297,319, Cl. 422-114.000.
- Akiyama, Masahiro; Kaminishi, Katuzo; and Kawakami, Yasushi, to OKI Electric Industry Co., Ltd. Hybrid integrated circuit and a method for producing the same. 4,297,647, Cl. 330-307.000.
- Akkerman, Neil H., to Baker International Corporation. Apparatus for pumping fluid from a well through a tubing string. 4,297,087, Cl. 417-378.000.
- Akkerman, Neil H., to Baker International Corporation. Pump assembly comprising gas spring means. 4,297,088, Cl. 417-378.000.
- Aktiebolaget Electrolux: See—
Kullander, Jan O., 4,296,982, Cl. 312-257.00R.
- Akutsu, Susumu; Isaka, Tsutomu; and Ishioka, Mitsugu, to Mitsubishi Petrochemical Co., Ltd. Process for producing electric conductors coated with crosslinked polyethylene resin. 4,297,310, Cl. 264-83.000.
- Akzona Incorporated: See—
Bohler, Joachim; and Jordon, Hans, 4,296,517, Cl. 15-93.00R.
- Carlyle, Ian C.; Sleight, Thomas; and Savage, David S., 4,297,351, Cl. 424-241.000.
- Albany International Corporation: See—
Bloyce, Lionel T.; and Morley, Michael J., 4,296,886, Cl. 239-264.000.
- Alberto-Culver Company: See—
Dasher, George F.; and Schamper, Thomas J., 4,297,098, Cl. 8-412.000.
- Albrecht, Ernst: See—
Barth, Karl; Albrecht, Ernst; and Stahlschmitt, Horst, 4,296,697, Cl. 112-109.000.
- Alcan Research and Development Limited: See—
Dube, Ghyslain, 4,297,105, Cl. 23-230.00R.
- Aldrich, Frederic C., to General Motors Corporation. Engine fuel system with fuel/water separation. 4,296,723, Cl. 123-510.000.
- Alfa-Pet, Inc.: See—
Schulein, Benjamin M., Jr., 4,296,709, Cl. 119-1.000.
- Allegheny Ludlum Steel Corporation: See—
Patil, Balaji V.; and Tommaney, Joseph W., 4,297,132, Cl. 75-10.00V.
- Allen, Gordon H., to Motorola, Inc. Glitch eliminator circuit for TTL transparent latch. 4,297,593, Cl. 307-247.00R.
- Allied Chemical Corporation: See—
Li, Hsin L.; Oswald, Hendrikus J.; and Liland, Alfred L., 4,296,535, Cl. 28-257.000.
- Allo, Vincent F., to Chicago Bridge & Iron Company. Freeze exchanger with removable tube liner. 4,296,612, Cl. 62-123.000.
- Allport, Maurice J.: See—
Nicol, Thomas; Wiley, David; and Allport, Maurice J., 4,297,631, Cl. 320-64.000.
- Allread, Alan R., to Aeroquip Corporation. Full flow breakaway coupling. 4,296,914, Cl. 251-149.200.
- Alnor Oy: See—
Lindstrom, Yrjo V., 4,296,627, Cl. 73-15.00R.

- Alps Electric Co., Ltd.: See—
Niinuma, Akira, 4,297,541, Cl. 200-5.00E.
Tsutsui, Kotaro; and Kinugawa, Ryoji, 4,297,540, Cl. 200-5.00B.
- Alstom-Atlantique: See—
Roux, Marc, 4,296,692, Cl. 105-397.000.
- Alston, William G. Jump trainer, 4,296,925, Cl. 273-1.50A.
- Altmeyer, Hans J.; and Gebel, Josef, to Hein, Lehmann AG. Belt filter press, 4,297,215, Cl. 210-386.000.
- Aluma Form, Inc.: See—
Farmer, Marion R., 4,296,904, Cl. 248-218.400.
- Aluminum Company of America: See—
Foster, Perry A., Jr., 4,297,180, Cl. 204-67.000.
- Amada Company, Limited: See—
Kaneko, Tomonobu, 4,296,661, Cl. 83-796.000.
- Amano, Hisao: See—
Onda, Kenichi; Tashiro, Sadaji; and Amano, Hisao, 4,297,594, Cl. 307-252.00C.
- Amazawa, Kiyoshi: See—
Tanaka, Kouichi; and Amazawa, Kiyoshi, 4,297,645, Cl. 330-280.000.
- AMCA International Corporation: See—
Heckelsberg, Robert E., 4,296,581, Cl. 52-520.000.
- American Can Company: See—
Detroit, William J.; and Sanford, Michael E., 4,296,813, Cl. 166-293.000.
- Nerod, Irving, 4,297,583, Cl. 250-453.000.
- American Chemical & Refining Company Incorporated: See—
Fletcher, Augustus; and Moriarty, William L., 4,297,177, Cl. 204-43.00N.
- Skomoroski, Robert M., 4,297,179, Cl. 204-47.000.
- American Cyanamid Company: See—
Bernstein, Seymour, 4,297,372, Cl. 424-315.000.
Los, Marinus, 4,297,128, Cl. 71-92.000.
Lutz, Albert W.; and Diehl, Robert E., 4,297,127, Cl. 71-88.000.
O'Neal, Thomas D., 4,297,126, Cl. 71-78.000.
Wissner, Allan, 4,297,516, Cl. 568-330.000.
- American Home Products Corporation: See—
Sulkowski, Theodore S.; Bergey, James L.; and Mascitti, Albert A., 4,297,373, Cl. 424-322.000.
- American Science and Engineering, Inc.: See—
Silk, John K., 4,296,737, Cl. 126-438.000.
- American Standard Inc.: See—
Lippa, Giuseppe, 4,296,908, Cl. 249-58.000.
Little, Donald R., 4,297,548, Cl. 200-61.080.
- AMF Incorporated: See—
Koch, Claude V., 4,297,546, Cl. 200-38.00R.
- Amos, Richard W.: See—
Miller, Kirk D.; Flood, John B.; Dimou, George; Kara, Frederick E.; and Amos, Richard W., 4,296,920, Cl. 266-216.000.
- AMP Incorporated: See—
Herrmann, Henry O., Jr., 4,296,986, Cl. 339-89.00C.
Hughes, Donald W. K.; and Myers, Ronald W., 4,296,991, Cl. 339-176.00P.
- Kobler, Robert J., 4,296,550, Cl. 29-884.000.
Warner, Gary N., 4,296,988, Cl. 339-97.00R.
- Ampex Corporation: See—
Quan, Ronald, 4,297,620, Cl. 315-389.000.
- Anaconda Company, The: See—
Rice, Hoyt G., Jr.; and Reynolds, Daniel J., 4,296,576, Cl. 52-90.000.
- Anderson, Alonzo B. Anti-backflow valve for sewer traps, 4,296,778, Cl. 137-433.000.
- Anderson Company of Indiana, The: See—
Arndt, John J., 4,296,520, Cl. 15-250.320.
- Anderson, Robert L.: See—
Northrup, Robert P.; and Anderson, Robert L., 4,296,670, Cl. 89-43.00R.
- Andersson, Poul G., to Ring Lock Container S. A. Receptacle with a cover of plastics material, 4,296,871, Cl. 220-306.000.
- Ando, Kazunari; Matsunaga, Hirokazu; and Ayabe, Hideaki, to Nippon Toki Kabushiki Kaisha; and Watanabe Instruments Corp. Thermal pen, 4,297,714, Cl. 346-139.00C.
- Ando, Ryo; and Sato, Kazuyoshi, to Nippon Kokan Kabushiki Kaisha. Apparatus for vitrifying blast furnace slag, 4,297,119, Cl. 65-141.000.
- Andreoni, Alessandro: See—
Gandolfi, Carmelo; Passarotti, Carlo; Andreoni, Alessandro; Fumagalli, Angelo; Faustini, Franco; Ceserani, Roberto; and Usardi, Maria M., 4,297,368, Cl. 424-285.000.
- Andresen, Rolf; and Christian, John H., to International Business Machines Corporation. Sector servo with sync marks, 4,297,737, Cl. 360-135.000.
- Andrews, David K.; and Smart, Michael W., to Dowty Fuel Systems Limited. Control mechanism, 4,296,676, Cl. 91-417.00R.
- Anezaki, Yoshimitsu, to Tokyo Shibaura Electric Co., Ltd. Electron gun structure, 4,297,612, Cl. 313-446.000.
- Angleman, John D.: See—
Henriques, Lance, 4,297,701, Cl. 343-6.5LC.
- Angstrom Precision, Inc.: See—
Solow, Benjamin, 4,297,670, Cl. 338-195.000.
- Anic S.p.A.: See—
Corbellini, Margherita; Greco, Alberto; and Osellame, Mirko, 4,297,462, Cl. 526-125.000.
- Anritsu Electric Company Limited: See—
Seki, Yashiro; Kobayashi, Hideo; Kimura, Kiyoshi; and Naito, Masayuki, 4,297,028, Cl. 355-41.000.
- Antes, Gregor; and Greenaway, David L., to LGZ Landis & Gyr Zug AG. Projection screen and method for making same, 4,297,001, Cl. 350-129.000.
- Antonious, Anthony J. Adjustable and flexible closure assembly for shoes with segmented uppers, 4,296,558, Cl. 36-50.000.
- Anzaldua, Alfred B.; Anzaldua, David A.; and Sturgeon, Benjamin R., to Health Innovations, Inc. Torsion exercise apparatus, 4,296,924, Cl. 272-117.000.
- Anzaldua, David A.: See—
Anzaldua, Alfred B.; Anzaldua, David A.; and Sturgeon, Benjamin R., 4,296,924, Cl. 272-117.000.
- Aoki, Harumi: See—
Nakamura, Kazuo; Jyojiki, Masao; and Aoki, Harumi, 4,297,014, Cl. 354-25.000.
- Aoki, Hatsuo: See—
Yoshida, Keizo; Tanaka, Hirokazu; Okamoto, Masanori; Iguchi, Eiko; Kohsaka, Masanobu; Aoki, Hatsuo; and Imanaka, Hiroshi, 4,297,096, Cl. 435-128.000.
- Aoki, Kozo; Sawada, Satoru; Yabuki, Yoshiharu; and Furutachi, Nobuo, to Fuji Photo Film Co., Ltd. Color photographic light-sensitive element, 4,297,440, Cl. 430-505.000.
- Appell, Marc; Bogaert, Jean-Louis; Massuard, Claude; Bradley, John; and Franklin, Benjamin S., to Compagnie Honeywell Bull. Call and stack mechanism for procedures executing in different rings, 4,297,743, Cl. 364-200.000.
- Arai, Seiichi: See—
Ieki, Hideharu; and Arai, Seiichi, 4,297,660, Cl. 333-194.000.
- Arakawa, Mitsuaki: See—
Crooks, Lawrence E.; Hoenninger, John C., III; and Arakawa, Mitsuaki, 4,297,637, Cl. 324-309.000.
- Aratame, Kazuhisa: See—
Yagi, Michio; Nakajima, Kunio; Nakagawa, Yasutsugu; Ishii, Sizuo; and Aratame, Kazuhisa, 4,297,019, Cl. 354-171.000.
- Arbel, Arie; and Kurz, Rainer, to Kernforschungsanlage Julich Gesellschaft mit beschränkter Haftung. Circuit for continuous conversion of signals into digital magnitudes, 4,297,679, Cl. 340-347.0AD.
- Arbit, Harry A.: See—
Frankel, Milton B.; Arbit, Harry A.; Artz, Glen D.; and Gray, John C., 4,297,152, Cl. 149-88.000.
- Archer, Richard W. Beach umbrella support, 4,296,693, Cl. 108-28.000.
- Armbrust, William D.; and McCreery, James F., to Kennametal Inc. Indexable cutting insert, 4,297,058, Cl. 407-113.000.
- Armentrout, James L.; and Schneider, George H. Devious path bacterial barrier, 4,296,862, Cl. 206-439.000.
- Arndt, Frederick P., to General Motors Corporation. Transmission shift lever backdrive and column locking mechanism, 4,296,847, Cl. 192-4.00A.
- Arndt, John J., to Anderson Company of Indiana, The. Pin connector, 4,296,520, Cl. 15-250.320.
- Arnold, Bernhard: See—
Lindner, Christian; Ott, Karl-Heinz; Arnold, Bernhard; Kowitz, Friedrich; Oertel, Harald; and Kuhlmann, Dieter, 4,297,446, Cl. 525-66.000.
- Arnold, Dan M.: See—
Smith, Harry D., Jr.; Arnold, Dan M.; and Smith, Kenneth J., 4,297,575, Cl. 250-265.000.
- Arnold, Harmon W.; and Erwin, Galen B., to Flex-o-lators, Inc. Component strand for wire fabrics, 4,297,418, Cl. 428-595.000.
- Arons, Howard L.: See—
Klein, Gary H.; Arons, Howard L.; Stejskal, Joseph F.; Stevens, Donald G.; and Zobel, Henry F., 4,297,144, Cl. 106-197.00C.
- Arthur Smith Industries, Inc.: See—
Balbach, George C.; and Peterman, Robert J., 4,296,570, Cl. 49-360.000.
- Artz, Glen D.: See—
Frankel, Milton B.; Arbit, Harry A.; Artz, Glen D.; and Gray, John C., 4,297,152, Cl. 149-88.000.
- Asahi Glass Company, Ltd.: See—
Oda, Yoshio; Morimoto, Takeshi; and Suzuki, Kohji, 4,297,182, Cl. 204-98.000.
- Asahi Kasei Kogyo Kabushiki Kaisha: See—
Nishikido, Joji; Tamura, Nobuhiro; Fukuoka, Yohei; and Yamane, Hiroyuki, 4,297,503, Cl. 560-42.000.
- Asahi Kogaku Kogyo Kabushiki Kaisha: See—
Nakamura, Kazuo; Jyojiki, Masao; and Aoki, Harumi, 4,297,014, Cl. 354-25.000.
- Asahi-Seiki Manufacturing Co., Ltd.: See—
Ohdai, Yozo; and Takahata, Yasuyuki, 4,296,621, Cl. 72-130.000.
- Asami, Takayoshi, to Kobe Steel, Limited. Heat transfer tubing for natural gas evaporator, 4,296,539, Cl. 29-157.30A.
- Asano, Masahide: See—
Miki, Tosaku; and Asano, Masahide, 4,297,357, Cl. 424-251.000.
- Asdollahi, Nasrollah, to Wickmann Werke AG. Slow-blowing fuse using zinc-manganese alloy link, 4,297,666, Cl. 337-163.000.
- Ashworth, Denis H., to Simon Engineering Dudley Limited. Hydraulically operated access equipment, 4,296,833, Cl. 182-2.000.
- Atkin, Howard S., to Holset Engineering Company Limited. Sealing assembly, 4,296,934, Cl. 277-81.00R.
- Atlantic Richfield Company: See—
Mooi, John, 4,297,244, Cl. 252-455.00Z.
- Aubert, Ralph: See—
Gander, Jean-Gabriel; and Aubert, Ralph, 4,297,533, Cl. 179-84.0VF.
- Auclair, Christopher J.: See—
Williams, Meurig W.; and Auclair, Christopher J., 4,297,427, Cl. 430-108.000.

- Augat Inc.: See—
Bertoglio, Guido, 4,296,549, Cl. 29-874.000.
Wellington, Roger D., 4,296,993, Cl. 339-275.00B.
- Augst, Horst G., to Telefonaktiebolaget L M Ericsson. Crystal filter structure, 4,297,659, Cl. 333-191.000.
- Autoclave Engineers, Inc.: See—
Ruyak, Robert F., 4,296,912, Cl. 251-65.000.
- Automated Building Components, Inc.: See—
Jureit, John C.; and Greenley, Henry R., 4,297,048, Cl. 403-189.000.
- Automotive Products Limited: See—
Farrant, David J. R., 4,297,047, Cl. 403-138.000.
- Autotote, Ltd.: See—
Lees, Robert, 4,297,039, Cl. 400-120.000.
- Aviram, Ari, to International Business Machines Corporation. Photodeformable article having photoionizable groups on a polymer backbone, 4,297,434, Cl. 430-270.000.
- Ayabe, Hideaki: See—
Ando, Kazunari; Matsunaga, Hirokazu; and Ayabe, Hideaki, 4,297,714, Cl. 346-139.00C.
- B. F. Goodrich Company, The: See—
Blalock, Gary L., 4,296,855, Cl. 198-502.000.
Cohen, Louis, 4,297,320, Cl. 422-131.000.
Lai, John T., 4,297,497, Cl. 544-384.000.
- Babb, Burton A. Dynamic loudspeaker, 4,297,537, Cl. 179-180.000.
- Babcock, John C.; Campbell, J. Allan; and Lobl, Thomas J., to Upjohn Company, The. Male contraceptive steroids and methods of use, 4,297,350, Cl. 424-238.000.
- Babcock & Wilcox Company, The: See—
Brunson, William T.; and Lexa, Anthony F., 4,297,581, Cl. 250-391.000.
Zadiraka, Allan J., 4,296,730, Cl. 126-421.000.
- Bacardit, Juan S., to Bendibérica S.A. Power steering mechanism, 4,296,673, Cl. 91-375.00A.
- Bacchi, Anthony C.: See—
Kress, Robert W.; and Bacchi, Anthony C., 4,296,896, Cl. 244-12.400.
- Bach, Paul S.; Harding, Steven R.; Lamos, Richard A.; Markham, Harvey R.; and Shepherd, Roger D., to International Business Machines Corporation. Document feeder system having a suspending/commencing mode, 4,297,025, Cl. 355-14.0SH.
- Bachofen AG: See—
Kagi, Bruno; Hirrmann, Georg; and Luginbuhl, Rolf, 4,296,774, Cl. 137-322.000.
Kagi, Bruno; Hirrmann, Georg; and Luginbuhl, Rolf, 4,296,775, Cl. 137-322.000.
- Bachtell, Stephen R. Method and apparatus for securing a hairpiece, 4,296,765, Cl. 132-53.000.
- Bagusche, Siegfried, to W. Hegenscheidt Gesellschaft mbH. Smoothing rolling mill, 4,296,620, Cl. 72-100.000.
- Baker, Cole H., to Intec Corporation. Absolute DC system for a laser inspection system, 4,297,587, Cl. 250-563.000.
- Baker, Eugene E.; and Carter, Ernest E., Jr., to Halliburton Services. Isolation packer extension, 4,296,808, Cl. 166-191.000.
- Baker, Gerald E. Earthquake alarm system, 4,297,690, Cl. 340-690.000.
- Baker International Corporation: See—
Akerman, Neil H., 4,297,087, Cl. 417-378.000.
Akerman, Neil H., 4,297,088, Cl. 417-378.000.
- Balbach, George C.; and Peterman, Robert J., to Arthur Smith Industries, Inc. Hydraulic door operator, 4,296,570, Cl. 49-360.000.
- Baldwin, Gary L.; and McCreary, James L., to Bell Telephone Laboratories, Incorporated. Offset correction in operational amplifiers, 4,297,642, Cl. 330-9.000.
- Baldwin Piano & Organ Company: See—
Wade, David R.; and Munch, Walter, 4,296,667, Cl. 84-345.000.
- Balkwill, G. Russell; Robinet, Jules P.; and Tamasovics, John F. Covers for electrical boxes, 4,296,870, Cl. 220-3.300.
- Ballinger, Paul V. Demountable interconnection, 4,297,074, Cl. 414-723.000.
- Ballmann, Josef. Projectile with spin-producing flow passages, 4,296,893, Cl. 244-3.230.
- Bally Manufacturing Corporation: See—
Frederiksen, Jeffrey E., 4,296,930, Cl. 273-313.000.
- Bals, Hans G. Process and apparatus for extracting a substance from a body of water, 4,297,218, Cl. 210-661.000.
- Baltensperger, Rudolf; and Pfister, Hans B. Hanger for track-type suspended railway, 4,296,690, Cl. 104-91.000.
- Bando, Yoshiaki: See—
Fujimaki, Kiyoshi; Bando, Yoshiaki; Okuyama, Takeshi; and Hashimoto, Tutomu, 4,296,954, Cl. 285-331.000.
- Banucci, Eugene G.; and Boldebeck, Edith M., to General Electric Company. Particulated polyetherimide and method for making, 4,297,385, Cl. 427-27.000.
- Barcza, Sandor, to Sandoz, Inc. Silicon-bearing carboxylic acids and amides, 4,297,349, Cl. 424-184.000.
- Barge, Presley O. Spherical living module or space, 4,296,892, Cl. 244-2.000.
- Barmag Barmer Maschinenfabrik Aktiengesellschaft: See—
Martens, Gerhard, 4,296,889, Cl. 242-18.100.
- Barnoski, Michael K.: See—
Marom, Emanuel; Barnoski, Michael K.; and Abrams, Richard L., 4,297,704, Cl. 343-113.00R.
- Barrash, Marshall J., to Coca-Cola Company, The. Elastic band and handle structure for forming packages of groups of containers, 4,296,861, Cl. 206-428.000.
- Barth, Karl; Albrecht, Ernst; and Stahlschmitt, Horst, to Pfaff Industriemaschinen GmbH. Sewing machine with a work holder for wrapping button shanks, 4,296,697, Cl. 112-109.000.
- Bartl, Herbert: See—
Lindner, Christian; Suling, Carlhans; Bartl, Herbert; Schreckenberger, Manfred; Freitag, Dieter; and Konig, Klaus, 4,297,455, Cl. 525-439.000.
- Bartley, Burton H.; and Estes, John H., to Texaco Inc. Catalyst for the preparation of methane, 4,297,245, Cl. 252-460.000.
- Bartolac, Robert R. Hair dryer, 4,297,564, Cl. 219-367.000.
- Barton, C. D. Connection device for golf club head covers, 4,296,787, Cl. 150-52.00G.
- BASF Aktiengesellschaft: See—
Caesar, Arndt C.; Koegel, Wolfram; Zuern, Ludwig; and Gaertner, Friedheim, 4,297,252, Cl. 252-606.000.
Koegel, Karl-Heinz; and Feuerherd, Karl-Heinz, 4,297,300, Cl. 260-544.00C.
Krabetz, Richard; Herrmann, Walter; Engelbach, Heinz; Palm, Peter; Sommer, Karl; and Spahn, Heinrich, 4,297,247, Cl. 252-468.000.
Manzke, Klaus; Brotzler, Roland; and Schulze-Berge, Klaus, 4,297,736, Cl. 360-109.000.
Reissenweber, Gernot; and Mangold, Dietrich, 4,297,491, Cl. 544-105.000.
Richarz, Winfried; Froehlich, Helmut; and Schroeder, Harald, 4,297,493, Cl. 544-241.000.
Sauter, Hubert; Zeeh, Bernd; Rentzea, Costin; and Pommer, Ernst-Heinrich, 4,297,364, Cl. 424-267.000.
Schenck, Hans-Uwe; and Gulbins, Erich, 4,297,255, Cl. 260-18.0PF.
- Bashnin, Oleg I.; Semenov, Vasily V.; Fedorov, Vasily N.; Gorbunov, Nikolai M.; Rodionov, Evgeny I.; and Sorokin, Nikolai A. Speed governor for a hydroelectric unit, 4,297,589, Cl. 290-40.00R.
- Battelle Development Corporation: See—
Beale, Harry A., 4,297,387, Cl. 427-38.000.
- Baugh, Edward D.; and Hoffman, Mark B., to General Motors Corporation. Diesel engine shutdown control system, 4,296,718, Cl. 123-198.00D.
- Baumann, Hans D. Eccentric rotary disk valve with elastic metal seal, 4,296,915, Cl. 251-174.000.
- Baumann, Hans-Peter, to Sandoz Ltd. Quaternized polyamines, 4,297,296, Cl. 260-459.00A.
- Baxter Travenol Laboratories, Inc.: See—
Cunningham, Joel, 4,297,316, Cl. 422-1.000.
Groman, Ernest V.; and Cabelli, Michael D., 4,297,494, Cl. 544-267.000.
- Bayer Aktiengesellschaft: See—
Becker, Robert; Grolig, Johann; and Rasp, Christian, 4,297,501, Cl. 560-24.000.
Boehmke, Gunther, 4,297,107, Cl. 44-51.000.
Buxbaum, Gunter; Schopper, Heinrich-Christian; Leitner, Lutz; and Hahnkamm, Volker, 4,297,395, Cl. 427-127.000.
Eicher, Theobald; and Muller, Friedemann, 4,296,762, Cl. 131-359.000.
Ertel, Werner, 4,297,519, Cl. 568-424.000.
Finke, Ulrich; and Moretto, Hans-Heinrich, 4,297,500, Cl. 556-466.000.
Fuchs, Rainer; Hamann, Ingeborg; Homeyer, Bernhard; Behrenz, Wolfgang; and Stendel, Wilhelm, 4,297,366, Cl. 424-274.000.
Fuchs, Rainer; Gallenkamp, Bernd; and Stendel, Wilhelm, 4,297,371, Cl. 424-304.000.
Hendricks, Udo-Winfried; and Wollny, Klaus, 4,297,103, Cl. 8-534.000.
Lindner, Christian; Ott, Karl-Heinz; Arnold, Bernhard; Kowitz, Friedrich; Oertel, Harald; and Kuhlmann, Dieter, 4,297,446, Cl. 525-66.000.
Lindner, Christian; Suling, Carlhans; Bartl, Herbert; Schreckenberger, Manfred; Freitag, Dieter; and Konig, Klaus, 4,297,455, Cl. 525-439.000.
Nickel, Horst, 4,297,278, Cl. 260-143.000.
Reischl, Artur; and Wagner, Kuno, 4,297,456, Cl. 525-452.000.
Wessling, Dieter, 4,297,281, Cl. 260-314.500.
- BBC Brown, Boveri & Company, Ltd.: See—
Floessel, Carl D.; and Floessel, Klaus, 4,297,523, Cl. 174-27.000.
- Beale, Harry A., to Battelle Development Corporation. Cubic boron nitride preparation, 4,297,387, Cl. 427-38.000.
- Beall, George H.; Grossman, David G.; Hoda, Syed N.; and Kubinski, Karen R., to Corning Glass Works. Inorganic gels and ceramic papers, films, fibers, boards, and coatings made therefrom, 4,297,139, Cl. 501-2.000.
- Becchi, Raffaele; Giaccone, Felice; and Accattino, Andrea, to Ing. C. Olivetti & C., S.p.A. Position transducer for a rotating member, 4,297,573, Cl. 250-231.0SE.
- Bechtel, Wolf D.: See—
Weber, Karl-Heinz; Schneider, Claus; Walther, Gerhard; Pook, Karl-Heinz; Boke, Karin; and Bechtel, Wolf D., 4,297,354, Cl. 424-248.510.
- Becker, Norbert: See—
Hildebrandt, Norbert; Becker, Norbert; Walter, Rolf; and Hoffmann, Manfred, 4,296,981, Cl. 312-194.000.
- Becker, Robert; Grolig, Johann; and Rasp, Christian, to Bayer Aktiengesellschaft. Process for the preparation of urethanes, 4,297,501, Cl. 560-24.000.
- Beckwith, Elaine C.: See—
Chang, Yun-Feng; Oene, Henk V.; and Beckwith, Elaine C., 4,297,448, Cl. 525-162.000.

Becton, Dickinson and Company: See—
Ferguson, James L., 4,296,631, Cl. 73-356.000.
Bedford, Riley: See—
Concha, Edward; Jaffe, Max; and Bedford, Riley, 4,297,068, Cl. 414-458.000.
Beecham Group Limited: See—
Howarth, Thomas T., 4,297,345, Cl. 424-114.000.
Beggs, George R. Rigid shell for building structures. 4,296,797, Cl. 165-48.00S.
Behrenz, Wolfgang: See—
Fuchs, Rainer; Hammann, Ingeborg; Homeyer, Bernhard; Behrenz, Wolfgang; and Stendel, Wilhelm, 4,297,366, Cl. 424-274.000.
Behringwerke Aktiengesellschaft: See—
Bohn, Hans; and Haupt, Heinz, 4,297,274, Cl. 260-112.00B.
Bohn, Hans; and Weinmann, Ernst, 4,297,343, Cl. 424-85.000.
Schwinn, Horst; Heimburger, Norbert; Kumpe, Gerhard; and Herchenhan, Bernd, 4,297,344, Cl. 424-101.000.
Bell, Keith: See—
Card, Jeffrey W.; and Bell, Keith, 4,297,574, Cl. 250-253.000.
Bell Telephone Laboratories, Incorporated: See—
Baldwin, Gary L.; and McCreary, James L., 4,297,642, Cl. 330-9.000.
Dufft, William H., 4,296,998, Cl. 350-96.200.
Johnson, David W., Jr.; Singh, Shobha; Van Uitert, LeGrand G.; and Zydik, George J., 4,297,005, Cl. 350-357.000.
Belles, David E., to Lok-A-Wat, Inc. Chain-lock actuated magnetic switch. 4,296,957, Cl. 292-264.000.
Bendibérica S.A.: See—
Bacardit, Juan S., 4,296,673, Cl. 91-375.00A.
Bendix Corporation, The: See—
Karol, James J.; Normann, Richard W.; and Hotchkiss, Lloyd C., 4,296,985, Cl. 339-48.000.
Monroe, William E., 4,296,674, Cl. 91-391.00R.
Roberts, James K., 4,296,845, Cl. 188-341.000.
Tang, Louis S., 4,296,671, Cl. 91-5.000.
Bengtsson, Sigurd W. Strap fastening means. 4,296,531, Cl. 24-200.000.
Benis, Isak. Manicuring case and supporting apparatus. 4,296,766, Cl. 132-73.000.
Bennett, Stuart C., to Coal Industry (Patents) Limited. Acoustic liner for attenuating noise. 4,296,831, Cl. 181-224.000.
Beno, Richard D., to Interstate Electronics Corp. Training circuit for audio signal recognition computer. 4,297,528, Cl. 179-1.05B.
Benson, Samuel L., to J. I. Case Company. Brake release mechanism. 4,296,846, Cl. 192-4.00A.
Bentley Laboratories, Inc.: See—
Raible, Donald A., 4,297,318, Cl. 422-46.000.
Beranek, Jaroslav, to Československá Akademie Ved. Apparatus having main and auxiliary fluidized beds therein. 4,297,321, Cl. 422-143.000.
Berdan, Gunter, to Custom Rollforming Company Limited. Spacer for double glazed windows incorporating interlock means. 4,296,587, Cl. 52-788.000.
Berezuk, Peter D.: See—
Wolinski, Leon E.; and Berezuk, Peter D., 4,297,158, Cl. 156-305.000.
Bergey, James L.: See—
Sulkowski, Theodore S.; Bergey, James L.; and Mascitti, Albert A., 4,297,373, Cl. 424-322.000.
Bergquist, Daryl J.: See—
Welsh, Luther; Bergquist, Daryl J.; and Watanabe, Hideo, 4,296,752, Cl. 128-635.000.
Bergthaller, Peter; Saleck, Wilhelm; Lapp, Otto; and Mucke, Bruno, to AGFA-Gevaert AG. Production of photographic silver halide emulsion. 4,297,439, Cl. 430-434.000.
Berkhin, Isif M.; Gudze, Robert A.; Kekalo, Vasily I.; Panasenko, Nikolai N.; Podbeltsev, Viktor I.; Tsykina, Zinaida D.; and Mukhin, Vladislav N. Device for locking slewing portion of cargo crane. 4,296,867, Cl. 212-229.000.
Bernardino, Lowell W., to Procter & Gamble Company, The. Process for removing hard-to-remove soils from hardware. 4,297,251, Cl. 252-545.000.
Berndtson, Gene A. Staple-nail for securing ceiling support strip to wallboard. 4,297,064, Cl. 411-470.000.
Bernhardt, Winfried; Grundmann, Edgard; and Kroll, Rudolf, to Volkswagenwerk AG. Solar radiation collector. 4,296,732, Cl. 126-426.000.
Bernstein, Seymour, to American Cyanamid Company. Ureide inhibitors of connective tissue destruction. 4,297,372, Cl. 424-315.000.
Berry, Clyde F. Electric steam generating unit. 4,297,563, Cl. 219-275.000.
Bertoglio, Guido, to Augat Inc. Method of making a lead socket insert. 4,296,549, Cl. 29-874.000.
Bertram, Rolf: See—
Hoffken, Erich; Kleine-Kieffmann, Werner; Bertram, Rolf; Abele, Karl-Heinz; and Michalski, Gunter, 4,297,151, Cl. 148-9.00R.
Bethany Fellowship, Inc.: See—
Harder, Willard J., 4,296,741, Cl. 126-449.000.
Betz Laboratories, Inc.: See—
Vogt, Frederick G., deceased; and Sparrell, Patricia T., 4,297,317, Cl. 422-16.000.
Bibracher, Wilhelm: See—
Gross, Franz; Boehme, Gerit; Wiehler, Wolf; and Bibracher, Wilhelm, 4,297,662, Cl. 333-252.000.
Bickel, Gary W., to International Telephone and Telegraph Corporation. Optical fiber beam splitter couplers employing coatings with dichroic properties. 4,296,995, Cl. 350-96.150.

Bidwell, Robert E.: See—
Kurtz, Leonard D.; and Bidwell, Robert E., 4,296,748, Cl. 128-276.000.
Bilberg, Erik A., to EABVV Utvecklings Aktiebolag. Heating boiler. 4,296,711, Cl. 122-22.000.
Billor, Efim, to Sulzer Brothers Limited. Method for the manufacture of polyarylamines having methylene bridges. 4,297,511, Cl. 564-331.000.
Billot, Michel: See—
Godard, Pierre; and Billot, Michel, 4,297,629, Cl. 320-7.000.
Bingham, Robert E.; Durst, Richard R.; Fabris, Hubert J.; Hargis, Ivan G.; Livigni, Russell A.; and Aggarwal, Sundar L., to General Tire & Rubber Company, The. Solution polymerization. 4,297,240, Cl. 252-431.00R.
Bini, Dante. Permanent weather covers. 4,296,585, Cl. 52-745.000.
Bio-Group, Inc.: See—
Wallace, Christopher B., 4,297,122, Cl. 71-12.000.
Bio Systems Research, Inc.: See—
Lionelle, Joseph E.; and Staffa, Jeffrey A., 4,297,291, Cl. 260-410.90R.
BioResearch Inc.: See—
Kurtz, Leonard D.; and Bidwell, Robert E., 4,296,748, Cl. 128-276.000.
Bird, Richard M.: See—
Stoute, Neville, Sr.; and Pennise, Robert J., 4,296,506, Cl. 4-480.000.
Bishop, John F.: See—
Bowman, Wayne A.; Bishop, John F.; and Noonan, John M., 4,297,432, Cl. 430-215.000.
Bissar, Saadi, to Timex Corporation. Protective membrane for electrochromic displays. 4,297,006, Cl. 350-357.000.
Bjorklund, Gary C., to International Business Machines Corporation. Method and device for detecting a specific spectral feature. 4,297,035, Cl. 356-402.000.
Blahak, Johannes, to Metzeler Kautschuk GmbH. Cellular elastomeric foams and method of production using an expanding agent containing a component reactive with the polyamine chain-lengthening agent. 4,297,442, Cl. 521-107.000.
Blake, Joseph W., III; and Kaufman, Jack W. Surgical device. 4,296,751, Cl. 128-325.000.
Blakeslee, Edward A.: See—
Webb, Bryant F.; Makofka, Stanley J.; Webster, Emmett G.; and Blakeslee, Edward A., 4,296,593, Cl. 56-98.000.
Blalock, Gary L., to B. F. Goodrich Company, The. Electrically conductive fabric. 4,296,855, Cl. 198-502.000.
Blanchard, Kenneth G.; and Ronne, Reuben N. Firearm shooting support table. 4,296,963, Cl. 297-170.000.
Blaser, Don E., to Exxon Research & Engineering Co. Two-stage integrated coking for chemicals and coke gasification process. 4,297,202, Cl. 208-54.000.
Blasingame, Thomas O.: See—
Mundt, Randall S.; Wooldridge, Timothy A.; and Blasingame, Thomas O., 4,297,162, Cl. 156-643.000.
Blaw-Knox Foundry & Mill Machinery, Inc.: See—
Eibe, Werner W., 4,296,623, Cl. 72-227.000.
Bloch, Bertrand; Cavalli born Meyer, Chantal; and Charrier, Denis, to Office National d'Etudes et de Recherches Aérospatiales. Novel acrylic polymers and method of making same. 4,297,466, Cl. 526-218.000.
Bloomer, Milton D.; and Kornrumpf, William P., to General Electric Company. Temperature-to-frequency conversion apparatus. 4,296,632, Cl. 73-362.00AR.
Bloyce, Lionel T.; and Morley, Michael J., to Albany International Corporation. Shower fittings. 4,296,886, Cl. 239-264.000.
Blythin, David J., to Schering Corporation. (1H,3H,5H)-(1)-Benzopyrano-(2,3-d)-pyrimidine-4-one-2-thiones and their use as anti-allergy agents. 4,297,355, Cl. 424-248.540.
Bodenseewerk Geosystem GmbH: See—
Spaeth, Tilman P., 4,297,579, Cl. 250-343.000.
Boehme, Gerit: See—
Gross, Franz; Boehme, Gerit; Wiehler, Wolf; and Bibracher, Wilhelm, 4,297,662, Cl. 333-252.000.
Boehmke, Gunther, to Bayer Aktiengesellschaft. Fuels and their use. 4,297,107, Cl. 44-51.000.
Boehringer Ingelheim GmbH: See—
Weber, Karl-Heinz; Schneider, Claus; Walther, Gerhard; Pook, Karl-Heinz; Boke, Karin; and Bechtel, Wolf D., 4,297,354, Cl. 424-248.510.
Boehringer Mannheim GmbH: See—
Guthlein, Werner; Wielinger, Hans; Rittersdorf, Walter; and Werner, Wolfgang, 4,297,271, Cl. 260-107.000.
Boeing Company, The: See—
Isenberg, Jack M., 4,296,899, Cl. 244-207.000.
Thompson, Bernard B., 4,296,897, Cl. 244-111.000.
Boffardi, Bennett P., to Calgon Corporation. Polyphosphate and poly-maleic anhydride combination for treating corrosion. 4,297,237, Cl. 252-389.00A.
Bogaert, Jean-Louis: See—
Appell, Marc; Bogaert, Jean-Louis; Massuard, Claude; Bradley, John; and Franklin, Benjamin S., 4,297,743, Cl. 364-200.000.
Bohler, Joachim; and Jordon, Hans, to Akzona Incorporated. Portable spinneret cleaner. 4,296,517, Cl. 15-93.00R.
Bohn, Hans; and Haupt, Heinz, to Behringwerke Aktiengesellschaft. Protein from red blood cells and process for isolating it. 4,297,274, Cl. 260-112.00B.
Bohn, Hans; and Weinmann, Ernst, to Behringwerke Aktiengesellschaft. Contraceptive agent. 4,297,343, Cl. 424-85.000.

Boke, Karin: See—
Weber, Karl-Heinz; Schneider, Claus; Walther, Gerhard; Pook, Karl-Heinz; Boke, Karin; and Bechtel, Wolf D., 4,297,354, Cl. 424-248.510.
Boldebeck, Edith M.: See—
Banucci, Eugene G.; and Boldebeck, Edith M., 4,297,385, Cl. 427-27.000.
Bolding, Gaines H. Solar collector using cotton seed oil to transfer heat to heavy oil wells. 4,296,739, Cl. 126-444.000.
Bolton, David H.: See—
Hines, David A.; and Bolton, David H., 4,297,217, Cl. 210-621.000.
Boothe, Robert R., to United States of America, Army. Frequency agility technique for frequency scanned antenna. 4,297,705, Cl. 343-771.000.
Borglum, Richard P., to Richway Industries Ltd. Foam dispensing apparatus for marking on a ground surface the working pattern of a surface working vehicle. 4,296,875, Cl. 222-617.000.
Bortle, Bonnie. Self-packaging urine conduit. 4,296,502, Cl. 4-144.100.
Bostock, James H.: See—
Taylor, Donald F.; and Bostock, James H., 4,296,806, Cl. 166-120.000.
Bosworth, George H.: See—
Halford, David W.; Price, Frank C.; and Bosworth, George H., 4,296,513, Cl. 12-12.000.
Bourdon, Louis P. Apparatus and method for obtaining fingerprints. 4,297,383, Cl. 427-1.000.
Bouygues, Jean: See—
Malsot, Christian; and Bouygues, Jean, 4,296,997, Cl. 350-96.200.
Bowden, Wade R., Jr., to Slater Electric Inc. Electrical outlet box and pawl mounting device. 4,297,525, Cl. 174-58.000.
Bowman, Wayne A.; Bishop, John F.; and Noonan, John M., to Eastman Kodak Company. Two-sheet diffusion transfer assemblies and photographic elements. 4,297,432, Cl. 430-215.000.
Boyd, Leroy. Ratcheting pipe cutter. 4,296,551, Cl. 30-98.000.
Boyle, Howard R.: See—
Lewis, John S.; DiGiannantonio, Edmond P.; and Boyle, Howard R., 4,297,677, Cl. 340-148.000.
Brack, Frederick. Reversible dual windshield wiper. 4,296,522, Cl. 15-250.360.
Bradley, John: See—
Appell, Marc; Bogaert, Jean-Louis; Massuard, Claude; Bradley, John; and Franklin, Benjamin S., 4,297,743, Cl. 364-200.000.
Brainard, Edward C., II, to Environmental Devices Corporation. Apparatus and method for sleep detection. 4,297,685, Cl. 340-575.000.
Brambilla, Giovanni; and Sartorelli, Adelmo, to Agip Nucleare, S.p.A. Pyroelectrochemical process for reprocessing irradiated nuclear fuels. 4,297,174, Cl. 204-1.500.
Brand, Derek A.: See—
Meyer, Burton C.; Licitis, Gunars; and Brand, Derek A., 4,296,929, Cl. 273-310.000.
Brandt, Eckhard: See—
Ramcke, Bernd; Schlottke, Karl-Heinz; Brandt, Eckhard; and Reissmann, Klaus, 4,297,066, Cl. 414-43.000.
Branham, Tillman W. Battery testing apparatus with overload protective means. 4,297,639, Cl. 324-429.000.
Braun AG: See—
Falkenbach, Guenther, 4,297,038, Cl. 366-206.000.
Bray, Lynn W., to United States Steel Corporation. Rod cooling box air wipe nozzle. 4,296,556, Cl. 34-107.000.
Breslow, Jeffrey D.: See—
Erickson, Erick E.; Katzman, Allison W.; and Breslow, Jeffrey D., 4,297,153, Cl. 156-63.000.
Breuckner, Keith A., to KMS Fusion, Inc. Fuel pellets for controlled nuclear fusion. 4,297,165, Cl. 376-103.000.
Brezinski, Donald P.; and Morse, Leroy R., to Corning Glass Works. pH Electrode glass compositions. 4,297,193, Cl. 204-195.00G.
Bridge, John G. Anti-gravity spinner. 4,296,704, Cl. 114-103.000.
Bridgestone Tire Company Limited: See—
Sakai, Yoshihiro; Tanaka, Ryosaku; Kita, Toshio; Shimotake, Munetoshi; Yamada, Tsuguyoshi; and Ueda, Hiroshi, 4,296,790, Cl. 152-354.00R.
Uruta, Hisanari; Takahashi, Kaneaki; Masuda, Hirotsugu; and Kurata, Tomoyuki, 4,296,705, Cl. 114-219.000.
Brignola, Dominic J., to West Company, The. Transfer device for use in mixing a primary solution and a secondary or additive substance. 4,296,786, Cl. 141-309.000.
Briley, Patrick B. Method for hydroconversion of solid carbonaceous materials. 4,297,200, Cl. 208-10.000.
Bristol-Myers Company: See—
Gottstein, William J.; Kaplan, Murray A.; and Granatek, Alphonse P., 4,297,489, Cl. 544-27.000.
Britax Weathershields Limited: See—
Hunt, Keith R.; and Fisher, Sidney E., 4,296,961, Cl. 296-216.000.
British Cellophane Limited: See—
Ward, Herbert J.; Dobbie, Derek J.; and Lyall, Brian, 4,297,415, Cl. 428-516.000.
British Petroleum Company Limited, The: See—
Foster, Alan J.; Sims, Malcolm L.; and Young, Dennis, 4,297,150, Cl. 148-6.300.
Hughes, Eugene M., 4,296,706, Cl. 114-294.000.
Broderick, Ronald J. Archery bow improvement and camera therefor. 4,296,725, Cl. 124-24.00R.
Brotzler, Roland: See—
Manzke, Klaus; Brotzler, Roland; and Schulze-Berge, Klaus, 4,297,736, Cl. 360-109.000.
Brown, Stanley E. Bag sealing device. 4,296,529, Cl. 24-30.50P.

Bruckner, Byron L., to General Motors Corporation. Guide mechanism for compressor socket plate. 4,297,085, Cl. 417-222.000.
Brunner, Anton; and Willburger, Nikolaus, to Siemens Aktiengesellschaft. Multiple omnidirectional antenna. 4,297,707, Cl. 343-725.000.
Brunson, William T.; and Lexa, Anthony F., to Babcock & Wilcox Company, The. Method for the fast and accurate identification of core power in nuclear reactors. 4,297,581, Cl. 250-391.000.
Bryan, Edward L., to Micro-Burner Systems Corporation. Furnace monitoring system. 4,296,727, Cl. 126-116.00A.
Bryant, David R.; and Galley, Richard A., to Union Carbide Corporation. Hydroformylation catalyst reactivation. 4,297,239, Cl. 252-412.000.
BSL Corporation: See—
Gidge, Kenneth N.; and Richard, Henry J., 4,296,792, Cl. 160-332.000.
Buchanan, Robert A.; Maple, T. Grant; and Sklensky, Alden F., to Lockheed Missiles & Space Company, Inc. Rare earth phosphors and phosphor screens. 4,297,584, Cl. 250-483.000.
Buchner, Bernhard. Dual piston two stroke engine. 4,296,714, Cl. 123-53.00B.
Buchner, Robert B., to U.S. Philips Corporation. Self-adjusting hybrid network. 4,297,536, Cl. 179-170.00D.
Buck, Gordon H.; and Hardwick, Martha K., to Mattel, Inc. Red light - green light game. 4,296,926, Cl. 273-86.00R.
Buckler, Robert T.; and Schroeder, Hartmut R., to Miles Laboratories, Inc. Chemiluminescent phthalhydrazide-labeled protein and polypeptide conjugates. 4,297,273, Cl. 260-112.00B.
Buckley, Jack: See—
Schnabele, Werner; Buckley, Jack; and Rieger, Ulrich, 4,296,894, Cl. 244-3.270.
Buckshaw, Thomas M.: See—
Manecke, Siegfried E.; and Buckshaw, Thomas M., 4,296,603, Cl. 60-528.000.
Buhmann, Ulrich: See—
Puttner, Reinhold; Buhmann, Ulrich; and Joppien, Hartmut, 4,297,361, Cl. 424-263.000.
Bunker Ramo Corporation: See—
Gallagher, David A., 4,296,992, Cl. 339-186.00M.
Burdeska, Kurt; and Kabas, Guglielmo, to Ciba-Geigy Corporation. Benzoxazolyl-stilbenes. 4,297,234, Cl. 252-301.240.
Burgmeier, Lyman R.; McCarty, Frederick B.; and Silver, Alexander, to Garrett Corporation, The. Method of making rotor assembly with magnet cushions. 4,296,544, Cl. 29-598.000.
Burleigh, John E.: See—
Uraneck, Carl A.; Burleigh, John E.; and Solomon, Paul W., 4,297,451, Cl. 525-366.000.
Burley Industries, Inc.: See—
Potter, George R., 4,296,540, Cl. 29-460.000.
Burns and Russell Company, The: See—
McClinton, John L., 4,296,859, Cl. 206-219.000.
Burton, Robert L.; and Finan, Thomas P., to International Business Machines Corporation. Paper feed system for a typewriter or the like. 4,297,045, Cl. 400-641.000.
Butter, Charles D., to Honeywell Inc. Fiber optic intruder alarm system. 4,297,684, Cl. 340-557.000.
Butwell, Kenneth F.: See—
Sigmund, Paul W.; and Butwell, Kenneth F., 4,297,329, Cl. 423-228.000.
Buxbaum, Gunter; Schopper, Heinrich-Christian; Leitner, Lutz; and Hahnkamp, Volker, to Bayer Aktiengesellschaft. Production of cobalt-doped ferrimagnetic iron oxides. 4,297,395, Cl. 427-127.000.
Bykov, Igor D.: See—
Yasinsky, Konstantin K.; Glazunov, Sergei G.; Ross, Jury N.; and Bykov, Igor D., 4,296,793, Cl. 164-24.000.
C. & W. Berges Maschinenfabrik, Firma: See—
Schroder, Klaus, 4,297,036, Cl. 366-77.000.
Cabelli, Michael D.: See—
Groman, Ernest V.; and Cabelli, Michael D., 4,297,494, Cl. 544-267.000.
Caesar, Arndt C.; Koegel, Wolfram; Zuern, Ludwig; and Gaertner, Friedhelm, to BASF Aktiengesellschaft. Aging-resistant fireproofing material. 4,297,252, Cl. 252-606.000.
Cairns, James A.; Nelson, Robert L.; and Woodhead, James L., to United Kingdom Atomic Energy Authority. Method of producing dense refractory oxide coatings on metallic substrates and the production of catalysts from the coated substrates. 4,297,246, Cl. 252-465.000.
Calamur, Narasimhan; and Schoenberg, Morris R., to Standard Oil Company (Indiana). Method and apparatus for sampling hot homogeneous mixtures. 4,296,637, Cl. 73-863.110.
Calgon Corporation: See—
Boffardi, Bennett P., 4,297,237, Cl. 252-389.00A.
McConomy, Thomas A.; and Wells, Bruce D., 4,297,334, Cl. 423-321.00R.
Cama, Lovji D.: See—
Christensen, Burton G.; Cama, Lovji D.; Karady, Sandor; and Slettinger, Meyer, 4,297,488, Cl. 544-21.000.
Cameron, John H.: See—
Sherman, Norman; and Cameron, John H., 4,297,311, Cl. 264-109.000.
Camp International, Inc.: See—
Tyo, James H., 4,296,761, Cl. 128-80.00G.
Campagna, Barry A., to Teledyne Industries, Inc. Lockable key holding receptacle. 4,296,617, Cl. 70-63.000.

- Campbell, Billy H.: See—
Debona, Edward J.; Neblett, Boyd L.; Krueger, Walter J.; Laird, William J.; Campbell, Billy H.; and Matthews, Gerald H., 4,296,669, Cl. 89-1.816.
- Campbell, Edward C.: See—
Kirk, Joseph R.; and Campbell, Edward C., 4,297,219, Cl. 210-669.000.
- Campbell, J. Allan: See—
Babcock, John C.; Campbell, J. Allan; and Lobl, Thomas J., 4,297,350, Cl. 424-238.000.
- Campbell, Willis R.: See—
Waldrop, T. William; and Campbell, Willis R., 4,296,596, Cl. 56-341.000.
- Campos, Conrad: Arm or shoulder attachment for gunstocks. 4,296,566, Cl. 42-71.00R.
- Canada, Her Majesty the Queen in right of, as represented by the Minister of National Defence: See—
Tucker, Trevor W.; and Cornish, William D., 4,297,648, Cl. 331-1.00R.
- Canadian General Electric Company Limited: See—
Lee, Harvey R.; Koch, Arnold K.; and Krawczyk, Adam, 4,297,305, Cl. 264-0.500.
- Canon Kabushiki Kaisha: See—
Hirayama, Kazuhiro; and Sugiura, Susumu, 4,297,716, Cl. 346-153.100.
- Ichikawa, Junji; Imai, Nobuhiro; Kohno, Kimio; Kadokura, Koichi; and Ishii, Masaaki, 4,297,713, Cl. 346-108.000.
- Kawamura, Masaharu; Uchidoi, Masanori; Shigeta, Yoshihiro; Sugiura, Yoji; and Yamamoto, Hiroshi, 4,297,013, Cl. 354-23.00D.
- Murakami, Hiroyasu; Ito, Tadashi; and Ito, Fumio, 4,297,018, Cl. 354-50.000.
- Yamada, Yasuyuki; and Okuno, Youichi, 4,297,020, Cl. 354-225.000.
- Canron Inc.: See—
Miller, Kirk D.; Flood, John B.; Dimou, George; Kara, Frederick E.; and Amos, Richard W., 4,296,920, Cl. 266-216.000.
- Card, Jeffrey W.; and Bell, Keith: Radon detection. 4,297,574, Cl. 250-253.000.
- Caribbean Properties Limited: See—
Ross, Leon I., 4,297,111, Cl. 55-92.000.
- Carl Still GmbH & KG, Firma: See—
Offermann, Ludwig; and Wippich, Rheinhold, 4,296,938, Cl. 277-135.000.
- Carlson, Gerald E.; to Xerox Corporation: Apparatus and method for diagnostic entry. 4,297,029, Cl. 355-133.000.
- Carlson, Ronald R.: See—
Wilson, Kermit H.; and Carlson, Ronald R., 4,296,573, Cl. 52-6.000.
- Carlsson, Per-Olov A. V.; and Hakansson, Bo H.; to Gambro AB: Electrical stimulator. 4,296,760, Cl. 128-788.000.
- Carlton, Richard J.; to Acurex Corporation: Tracking solar energy collector assembly. 4,297,572, Cl. 250-203.00R.
- Carlyle, Ian C.; Sleight, Thomas; and Savage, David S.; to Akzona Incorporated: Method of manufacture and use of improved 2 β , 16 β -piperidino androstanes. 4,297,351, Cl. 424-241.000.
- Carnes, Irven S.; to Raytheon Company: Polyphase coded fuzing system. 4,297,702, Cl. 343-7.0PF.
- Carrier Corporation: See—
Straslicka, William A., 4,296,538, Cl. 29-156.40R.
- Carroll, Charles B.; and Scheible, Howard G.; to RCA Corporation: Method for preparing stylus lapping discs. 4,297,312, Cl. 264-134.000.
- Carter, Ernest E., Jr.: See—
Baker, Eugene E.; and Carter, Ernest E., Jr., 4,296,808, Cl. 166-191.000.
- Carter, William R.: Airborne dust monitor. 4,297,578, Cl. 250-343.000.
- Cascade Corporation: See—
Didtel, Stuart R., 4,297,070, Cl. 414-497.000.
- Cassel, Knut E.; and Molin, Bengt T.; to U.S. Philips Corporation: Luneberg lens antenna. 4,297,709, Cl. 343-754.000.
- Castanie, Francis: See—
Hoffmann, Jean-Claude; Castanie, Francis; Crabere, Henri; Verdier, Jean-Pierre; and Voisin, Norbert, 4,297,744, Cl. 364-703.000.
- Caterpillar Tractor Co.: See—
Day, Ralph R.; and Wulff, B. James, 4,296,917, Cl. 254-400.000.
- Fuzzell, Joe E., 4,297,687, Cl. 340-626.000.
- Heitzman, Gary N.; Hutchings, Clay L.; Knepp, Gary L.; and Miller, Robert G., 4,297,742, Cl. 361-154.000.
- Cavalli born Meyer, Chantal: See—
Bloch, Bertrand; Cavalli born Meyer, Chantal; and Charrier, Denis, 4,297,466, Cl. 526-218.000.
- Cazenave, Paul: See—
Horman, Ian; and Cazenave, Paul, 4,297,380, Cl. 426-597.000.
- Centre de Recherches Metallurgiques-Centrum voor Research in de Metallurgie: See—
Paulus, Philippe, 4,297,398, Cl. 427-320.000.
- Centre National de Transfusion Sanguine: See—
Claude, Matte, 4,297,104, Cl. 23-230.00B.
- Centre National pour l'Exploitation des Oceans: See—
Sachetto, Jean-Pierre; and Cuccolo, Sergio, 4,297,137, Cl. 106-15.050.
- Centro Ricerche Fiat S.p.A.: See—
Daolio, Sergio; Mengoli, Guilio; Folonari, Carlo; and Musiani, Marco, 4,297,188, Cl. 204-181.00R.
- Ceserani, Roberto: See—
Gandolfi, Carmelo; Passarotti, Carlo; Andreoni, Alessandro; Fumagalli, Angelo; Faustini, Franco; Ceserani, Roberto; and Usardi, Maria M., 4,297,368, Cl. 424-285.000.
- Ceskoslovenska Akademie Ved: See—
Beranek, Jaroslav, 4,297,321, Cl. 422-143.000.
- Cha, John H.: See—
Yenzer, Dennis E.; Cha, John H.; and Abramovich, Dan, 4,297,054, Cl. 405-168.000.
- Chaborski, Hoiko; to MITEC-Moderne-Industrietechnik GmbH: Method and apparatus for measuring the distance and/or relative elevation between two points. 4,297,030, Cl. 356-5.000.
- Chamberlin, Richard L.; to Dresser Industries, Inc.: Corrosion resistant pipe joint. 4,296,950, Cl. 285-45.000.
- Champeau, Marcel; and Tabutin, Andre; to Societe Anonyme dite: Ramo S.A. Clamping device for simultaneously machining internally and/or externally, the two ends of a workpiece. 4,296,658, Cl. 82-30.000.
- Chan, Tsiu C.: See—
McKenny, Vernon C.; and Chan, Tsiu C., 4,297,721, Cl. 357-59.000.
- Chandler, Edward A.; to Kaufel Group Ltd.: Emergency lighting system. 4,297,614, Cl. 315-86.000.
- Chandler, Ollie W.: See—
Eckler, Paul E.; Summers, William A.; and Chandler, Ollie W., 4,297,443, Cl. 521-129.000.
- Chang, Yun-Feng; Oene, Henk V.; and Beckwith, Elaine C.; to Ford Motor Company: Coating composition of aminoplast, hydroxy polymers and vinylic monomers. 4,297,448, Cl. 525-162.000.
- Charles Stark Draper Laboratory, Inc.: See—
Kumar, Kaplesh; Das, Dilip K.; and Wettstein, Ernest C., 4,297,388, Cl. 427-47.000.
- Charlton, Webster T.; to Stone & Webster Engineering Corp.: Apparatus and process for lubricating electrical cable. 4,296,837, Cl. 184-15.00R.
- Charrier, Denis: See—
Bloch, Bertrand; Cavalli born Meyer, Chantal; and Charrier, Denis, 4,297,466, Cl. 526-218.000.
- Chaumat, Bernard; Gallet, Georges; Lamare, Jacques; and Peyssard, Guy: Folding door or like closure device. 4,296,791, Cl. 160-206.000.
- Chef-Reddy Foods Corporation: See—
Harney, David L.; and Young, Harlow S., 4,297,377, Cl. 426-438.000.
- Chemische Fabrik Stockhausen & Cie: See—
Chmelir, Miroslav; and Dahmen, Kurt, 4,297,468, Cl. 526-276.000.
- Chemische Werke Huels, Aktiengesellschaft: See—
Maahs, Gunther; and Rombusch, Konrad, 4,297,505, Cl. 560-219.000.
- Chen, Cheng-Lin; to Westinghouse Electric Corp.: Isotopic separation. 4,297,191, Cl. 204-193.000.
- Chen, Rocky W.: See—
Haas, Michael J.; Pratt, Paul D.; Chen, Rocky W.; and Fett, Helen M., 4,297,378, Cl. 426-532.000.
- Chenau, Bernard; and Leroux, Alain; to Compagnie Generale d'Electricite: Electrode for a lead accumulator. 4,297,420, Cl. 429-217.000.
- Chern, Mao-Jin; and Lowrey, Robert D.; to Minnesota Mining & Manufacturing Company: Liquid crystal display and photopolymerizable sealant therefor. 4,297,401, Cl. 428-1.000.
- Chesebrough-Pond's Inc.: See—
Pallone, Thomas J.; Lynch, Mark; Corvino, Janice E.; and McCook, John P., 4,296,764, Cl. 132-7.000.
- Chestnut, Benjamin F.; to Emhart Industries, Inc.: Miniature timing mechanism. 4,297,547, Cl. 200-38.00R.
- Chevreaux, Pierre; Nguyen, Van-Tao; Roman, Alain; and Turpin, Daniel; to Techinter S.A.: Photosetting adhesive from unsaturated oligomer, photoinitiator, and betaine-forming mixture of unsaturated tert.amine and unsaturated acid. 4,297,185, Cl. 204-159.150.
- Chevron Research Company: See—
Clark, William J., 4,296,523, Cl. 15-415.00R.
- Edwards, Laroy H., 4,297,124, Cl. 71-66.000.
- Chiang, David: Method of determining operating currents for stepping motor. 4,297,626, Cl. 318-696.000.
- Chiasson, Bertrand A.; to Union Carbide Corporation: Process for preparing alkali metal salts 3-amino-2, 5-dichlorobenzoic acid. 4,297,509, Cl. 562-456.000.
- Chibana, Masanobu; to Nippon Gakki Seizo Kabushiki Kaisha: Electronic musical instrument. 4,296,663, Cl. 84-1.010.
- Chicago Bridge & Iron Company: See—
Allo, Vincent F., 4,296,612, Cl. 62-123.000.
- O'Meara, David M., 4,297,037, Cl. 366-114.000.
- Chien-Sheng, Chiang: Stepless controlled flush closet. 4,296,505, Cl. 4-324.000.
- Chik, Kiuchi D.: See—
Dyment, John C.; and Chik, Kiuchi D., 4,297,651, Cl. 331-94.50H.
- Chion, Pierre: See—
Achard, Georges; Chion, Pierre; and Menault, Jacques, 4,297,412, Cl. 428-370.000.
- Chisso Corporation: See—
Koga, Isao; Terui, Yohji; Ohgushi, Masuhito; and Kitahara, Tohru, 4,297,499, Cl. 556-465.000.
- Chmelir, Miroslav; and Dahmen, Kurt; to Chemische Fabrik Stockhausen & Cie: Allyl amido phosphorous copolymers. 4,297,468, Cl. 526-276.000.
- Christensen, Burton G.; Cama, Lovji D.; Karady, Sandor; and Slettinger, Meyer; to Merck & Co., Inc.: 7- α -Methoxy cephalosporins. 4,297,488, Cl. 544-21.000.

- Christian, John H.: See—
Andresen, Rolf; and Christian, John H., 4,297,737, Cl. 360-135.000.
- Christian, Robert F.; to Jude Engineering, Inc.: Inclined helical flight conveyor. 4,297,208, Cl. 210-94.000.
- Ciba-Geigy Corporation: See—
Abeler, Gerd; and Maul, Rudolf, 4,297,268, Cl. 260-45.80N.
- Burdeska, Kurt; and Kabas, Guglielmo, 4,297,234, Cl. 252-301.240.
- Felder, Louis; and Kirchmayr, Rudolf, 4,297,513, Cl. 568-43.000.
- Haas, Georges; Jaeggi, Knut A.; Rossi, Alberto; and Sele, Alex, 4,297,358, Cl. 424-256.000.
- Kern, Jorg; and Guth, Christian, 4,297,400, Cl. 427-389.000.
- Koci, Zdenek; and Mollet, Hans, 4,297,100, Cl. 8-527.000.
- Rajappa, Srinivasachari; and Sudarsanam, Vasudevan, 4,297,365, Cl. 424-270.000.
- Rasberger, Michael; Rosenberger, Siegfried; and Evans, Samuel, 4,297,492, Cl. 544-211.000.
- CIR - S.p.A. Divisione SASIB: See—
Cristiani, Athos, 4,296,660, Cl. 83-100.000.
- Claassen, Peter; List, Helmut; and Zeiringer, Rudolf; to List, Hans: Transducer device for measuring the internal pressure in pipes. 4,296,635, Cl. 73-730.000.
- Claffy, Richard D.; and Lovelace, Reginald B.; to United States of America, Navy: Quiet impulse steam trap. 4,296,771, Cl. 137-110.000.
- Clarion Co., Ltd.: See—
Tanaka, Kouichi; and Amazawa, Kiyoshi, 4,297,645, Cl. 330-280.000.
- Clark, Michael J.: See—
Ford, William D.; and Clark, Michael J., 4,297,203, Cl. 208-74.000.
- Clark, William J.; to Chevron Research Company: Dust-collection head for a dust collection system. 4,296,523, Cl. 15-415.00R.
- Claude, Matte; to Centre National de Transfusion Sanguine: Method of detecting or identifying virus antigens, erythrocyte or cell antigens or antibodies in a biological medium. 4,297,104, Cl. 23-230.00B.
- Clement, Joseph; to Mead Corporation: The Display device with price change cartridges. 4,296,563, Cl. 40-518.000.
- Clifford, Roy; to Kangel Magnet Limited: Emergency release systems. 4,296,942, Cl. 280-803.000.
- Cluff, C. Brent: Tracking booster and multiple mirror concentrator floating collector. 4,296,731, Cl. 126-424.000.
- CM1 Corporation: See—
Van Wassenhove, Bernard, 4,296,941, Cl. 280-423.00B.
- Coal Industry (Patents) Limited: See—
Bennett, Stuart C., 4,296,831, Cl. 181-224.000.
- Coca-Cola Company, The: See—
Barrash, Marshall J., 4,296,861, Cl. 206-428.000.
- Coe, Charles D.; and Wright, Philip; to Land Pyrometers Limited: Radiation detection of gas compositions. 4,297,577, Cl. 250-343.000.
- Cohen, Louis; to B. F. Goodrich Company: The Coating polymerization reactors with the reaction products of thiodiphenols and a bleach. 4,297,320, Cl. 422-131.000.
- Cohen, Merrill L.: Automotive oil system. 4,296,838, Cl. 184-106.000.
- Coleman, Richard L.: See—
Witte, Arnold C.; and Coleman, Richard L., 4,297,227, Cl. 252-18.000.
- Colleoni, Alec: See—
Mezrich, Reuben S.; Colleoni, Alec; and Lyons, David J., 4,297,009, Cl. 352-86.000.
- Colombo, Angelo; to Valli & Colombo S.p.A.: Cam operated lock, particularly for doors. 4,296,956, Cl. 292-169.180.
- Commissariat a l'Energie Atomique: See—
Laval, Michel; and Tournier, Edmond, 4,297,576, Cl. 250-336.000.
- Sauvage, Henri; and Tarnero, Maurice, 4,297,324, Cl. 422-268.000.
- Communications Satellite Corporation: See—
Stegens, Ronald E., 4,297,661, Cl. 333-204.000.
- Compagnie Generale d'Electricite: See—
Chenau, Bernard; and Leroux, Alain, 4,297,420, Cl. 429-217.000.
- Compagnie Honeywell Bull: See—
Appell, Marc; Bogaert, Jean-Louis; Massuard, Claude; Bradley, John; and Franklin, Benjamin S., 4,297,743, Cl. 364-200.000.
- Compagnie Internationale pour l'Informatique CII-Honeywell Bull: See—
Dupont, Jean M., 4,297,623, Cl. 318-410.000.
- Concha, Edward; Jaffe, Max; and Bedford, Riley; to United States of America, Army: Cargo container transporter. 4,297,068, Cl. 414-458.000.
- Conoco Inc.: See—
Stalder, John L.; and Martin, William L., 4,296,814, Cl. 166-303.000.
- Consiglio Nazionale Delle Ricerche: See—
Daolio, Sergio; Mengoli, Guilio; Folonari, Carlo; and Musiani, Marco, 4,297,188, Cl. 204-181.00R.
- Conway, William H.: See—
Tyler, Hugh J.; and Conway, William H., 4,297,557, Cl. 219-10.55R.
- Conwed Corporation: See—
Sherman, Norman; and Cameron, John H., 4,297,311, Cl. 264-109.000.
- Cook, Edward H., Jr.: See—
Lazarz, Christine A.; and Cook, Edward H., Jr., 4,297,196, Cl. 204-296.000.
- Cooper, George H.; to Suntime, Inc.: Solar hot water heating system. 4,296,729, Cl. 126-421.000.
- Cooper Industries, Inc.: See—
Jameson, James J., 4,296,645, Cl. 74-688.000.
- Cooper, Thomas F.: Sky seat safety descent apparatus. 4,296,836, Cl. 182-193.000.
- Coran, Aubert Y.; and Patel, Raman; to Monsanto Company: Compositions of epichlorohydrin rubber and nylon. 4,297,453, Cl. 525-408.000.
- Corbellini, Margherita; Greco, Alberto; and Osellame, Mirko; to Snamprogetti S.p.A.; and Anic S.p.A.: Polymerization of monoolefins using an aluminum-titanium catalyst system. 4,297,462, Cl. 526-125.000.
- Cordes, Gunter: See—
Sandrock, Klaus; and Cordes, Gunter, 4,297,286, Cl. 260-347.800.
- Cornelius, Morris E.: Motorcycle throttle gripper. 4,296,643, Cl. 74-531.000.
- Corning Glass Works: See—
Beall, George H.; Grossman, David G.; Hoda, Syed N.; and Kubinski, Karen R., 4,297,139, Cl. 501-2.000.
- Brezinski, Donald P.; and Morse, Leroy R., 4,297,193, Cl. 204-195.00G.
- Lawless, William N., 4,296,607, Cl. 62-6.000.
- Lawless, William N., 4,296,608, Cl. 62-6.000.
- Mansfield, Gerald R.; Travis, Karen L.; and Vann, William P., 4,297,337, Cl. 424-1.000.
- Paisley, Robert J., 4,297,140, Cl. 428-310.000.
- Wu, Che-Kuang, 4,297,417, Cl. 428-410.000.
- Cornish, William D.: See—
Tucker, Trevor W.; and Cornish, William D., 4,297,648, Cl. 331-1.00R.
- Corona, Stephen C.; to Xerox Corporation: Fluorescent lamp with incandescent ballasting systems. 4,297,616, Cl. 315-179.000.
- Cortorillo, Salvatore F.; to Wagner Electric Corporation: Control of tungsten filament erosion in a halogen lamp. 4,297,611, Cl. 313-222.000.
- Corvino, Janice E.: See—
Pallone, Thomas J.; Lynch, Mark; Corvino, Janice E.; and McCook, John P., 4,296,764, Cl. 132-7.000.
- Costantini, Michel; and Joffret, Michel; to Rhone-Poulenc Industries: Production of epoxides from lower alkane-1,2-diols. 4,297,287, Cl. 260-348.160.
- Cowan, Kiplin D.; to Phillips Petroleum Co.: Synthesis of esters. 4,297,506, Cl. 560-246.000.
- CPC International Inc.: See—
Klein, Gary H.; Arons, Howard L.; Stejskal, Joseph F.; Stevens, Donald G.; and Zobel, Henry F., 4,297,144, Cl. 106-197.00C.
- Mise, Yoshinari; and Tomimura, Eijiro, 4,297,146, Cl. 127-60.000.
- Crabere, Henri: See—
Hoffmann, Jean-Claude; Castanie, Francis; Crabere, Henri; Verdier, Jean-Pierre; and Voisin, Norbert, 4,297,744, Cl. 364-703.000.
- Craven, Richard L.; to Upjohn Company: The Controlled release cycloheximide compositions. 4,297,339, Cl. 424-19.000.
- Crawford, Roger A.; and Simmons, Robert B.; to PPG Industries, Inc.: Method of decomposing hypochlorite ion in a basic solution. 4,297,333, Cl. 423-241.000.
- Cristiani, Athos; to CIR - S.p.A. Divisione SASIB: Device for feeding rod-like articles. 4,296,660, Cl. 83-100.000.
- Crommelynck, Francois; Granger, Michel; Rio, Michel; and Tournet, Jacques; to L'Air Liquide, Societe Anonyme pour l'Etude Procédes Georges Claude: Method of preparing stable dilute solutions of aliphatic carboxylic peracids, and the resulting solutions. 4,297,298, Cl. 260-502.00R.
- Crone, William F., Jr.: See—
Reed, Ronald R.; Crone, William F., Jr.; and Meyer, G. Robert, 4,296,662, Cl. 83-880.000.
- Crooks, Lawrence E.; Hoenninger, John C., III; and Arakawa, Mitsuki; to University of California: The Regents of the. Method and apparatus for mapping lines of nuclear density within an object using nuclear magnetic resonance. 4,297,637, Cl. 324-309.000.
- Crosby, Jeffrey N.; to International Nickel Company, Inc.: The Ruthenium electroplating and baths and compositions therefor. 4,297,178, Cl. 204-47.000.
- Crow, James T.: See—
Goebel, Dan M.; Crow, James T.; and Forrester, A. Theodore, 4,297,615, Cl. 315-111.210.
- Cryer, Edward: See—
Tregurtha, Steven J.; and Cryer, Edward, 4,297,549, Cl. 200-61.270.
- CTS Corporation: See—
Flanders, Thomas W., 4,297,671, Cl. 338-200.000.
- Cuccolo, Sergio: See—
Sachetto, Jean-Pierre; and Cuccolo, Sergio, 4,297,137, Cl. 106-15.050.
- Cundari, Sante M.: See—
Deardorff, Paul A.; Wood, Robert C.; and Cundari, Sante M., 4,297,303, Cl. 264-3.00R.
- Cunningham, Joel; to Baxter Travenol Laboratories, Inc.: Maintaining the dimensional integrity of thermoplastic tubing ends for receiving a luer. 4,297,316, Cl. 422-1.000.
- Curtill, Remi; and Devaux, Alain; to Societe d'Etudes de Machines Thermiques S.E.M.T.: Apparatus for external cooling of an exhaust valve. 4,296,715, Cl. 123-90.150.
- Cusick, Kenneth M.; to Aitken, Inc.: Apparatus for separating foreign matter from a gas stream. 4,297,116, Cl. 55-319.000.
- Custom Rollforming Company Limited: See—
Berdan, Gunter, 4,296,587, Cl. 52-788.000.
- Cyber Diagnostics, Inc.: See—
Dunning, Ted E.; and Enright, Paul L., 4,296,756, Cl. 128-716.000.
- Cybernet Electronics Corp.: See—
Kakigi, Takao, 4,297,688, Cl. 340-630.000.

D.E.W. Line, Inc.: See—
Fruchey, Russell L.; and Kuper, Daniel E., 4,297,672, Cl. 340-23.000.
Dachtler, William G. Baby bottle support jig. 4,296,902, Cl. 248-102.000.
Dahmen, Kurt: See—
Chmelir, Miroslav; and Dahmen, Kurt, 4,297,468, Cl. 526-276.000.
Daiichi Seiyaku Co., Ltd.: See—
Miki, Tosaku; and Asano, Masahide, 4,297,357, Cl. 424-251.000.
Daimler-Benz Aktiengesellschaft: See—
Wulf, Helmut, 4,296,796, Cl. 165-46.000.
Dainippon Screen Seizo Kabushiki Kaisha: See—
Masuda, Tatsunosuke; Ono, Yoshio; and Sakamoto, Seiya, 4,297,724, Cl. 358-93.000.
Daiwa Chemical Company Ltd.: See—
Nakaoji, Kozo, 4,297,520, Cl. 568-426.000.
Dake Corporation, Division of JSJ Corporation: See—
Kruse, Gary L., 4,296,589, Cl. 53-300.000.
D'Alelio, Gaetano F., deceased: See—
Waikus, Phillip A.; and D'Alelio, Gaetano F., deceased, 4,297,467, Cl. 526-259.000.
Dalhof, Axel; and Lechner, Robert, to Siemens Aktiengesellschaft. Circuit for suppressing noise influences in the evaluation of signal states on transmission lines. 4,297,531, Cl. 179-16.0AA.
Dalle & Cie, S.A.: See—
Dalle, Joel, 4,297,156, Cl. 156-93.000.
Dalle, Joel, to Dalle & Cie, S.A. Process for manufacture of wall coverings and wall coverings thus obtained. 4,297,156, Cl. 156-93.000.
Dana Corporation: See—
Schetter, Thomas C., 4,296,642, Cl. 74-475.000.
Danavox A/S: See—
Pedersen, Jorgen R., 4,296,829, Cl. 181-129.000.
Danfoss A/S: See—
Jensen, Borge R., 4,297,608, Cl. 310-335.000.
Daolio, Sergio; Mengoli, Giuliano; Folonari, Carlo; and Musiani, Marco, to Centro Ricerche Fiat S.p.A.; and Consiglio Nazionale Delle Ricerche. Process for the electrolytic coating of conductive substrates with protective films of phenolic resins. 4,297,188, Cl. 204-181.00R.
Dargatz, Dayton O., to Plessey Peripheral Systems. Impact printer inclined ribbon scanner. 4,297,043, Cl. 400-224.000.
Darner, Ronald G., to Emhart Industries, Inc. Switching means for a timing mechanism. 4,297,545, Cl. 200-38.00R.
Dart Industries Inc.: See—
Elias, Moenes L.; and Shah, Narendra K., 4,297,257, Cl. 260-29.60H.
Das, Dilip K.: See—
Kumar, Kaplesh; Das, Dilip K.; and Wettstein, Ernest C., 4,297,388, Cl. 427-47.000.
Dasher, George F.; and Schamper, Thomas J., to Alberto-Culver Company. Method for gradual coloring of hair to a light brown shade and preparations for use therein. 4,297,098, Cl. 8-412.000.
Datakey, Inc.: See—
Flies, William P., 4,297,569, Cl. 235-443.000.
Datamedix Inc.: See—
Judell, Neil H. K., 4,296,755, Cl. 128-705.000.
David Parr & Associates Limited: See—
Parr, David, 4,297,565, Cl. 219-522.000.
Davidson, Donald R.; and Marsh, Walter H. W., to Singer Company. The Button attaching hand tool with button storage compartment. 4,296,698, Cl. 112-110.000.
Davies, John H.: See—
Davis, Royston H.; and Davies, John H., 4,297,496, Cl. 544-332.000.
Davis, Gerald T.: See—
Spatz, Sydney M.; Hydell, Robert C.; and Davis, Gerald T., 4,296,947, Cl. 282-27.500.
Davis, Michael W.: See—
Simpson, Harold G.; and Davis, Michael W., 4,296,582, Cl. 52-590.000.
Davis, Robert B., to Union Carbide Corporation. Liquid cryogen delivery system. 4,296,610, Cl. 62-55.000.
Davis, Royston H.; and Davies, John H., to Shell Oil Company. Nitrimine derivatives. 4,297,496, Cl. 544-332.000.
Day, Ralph R.; and Wulff, B. James, to Caterpillar Tractor Co. Contoured cable roller. 4,296,917, Cl. 254-400.000.
Deardorff, Paul A.; Wood, Robert C.; and Cundari, Sante M. Preparation and reaction of energy producing waste material composition. 4,297,303, Cl. 264-3.00R.
Debona, Edward J.; Neblett, Boyd L.; Krueger, Walter J.; Laird, William J.; Campbell, Billy H.; and Matthews, Gerald H., to United States of America. Army. Rocket tube launcher with cast-in place tube support bulkhead. 4,296,669, Cl. 89-1.816.
Debono, Manuel, to Eli Lilly and Company. Derivatives of A-30912B nucleus. 4,297,277, Cl. 260-112.50R.
Dec, Anthony F.: See—
Topalian, Harry H.; Wyss, Clement R.; Kenyon, Ralph E.; and Dec, Anthony F., 4,297,379, Cl. 426-565.000.
Deere & Company: See—
Marquart, Gordon L., 4,296,649, Cl. 74-751.000.
Deguchi, Ryuichi: See—
Nakanishi, Kiyoshi; Okumura, Takeshi; Deguchi, Ryuichi; and Tanahashi, Toshio, 4,296,720, Cl. 123-309.000.

Deguchi, Yukichi; Yamagishi, Hideki; and Kimura, Shunichiro, to Toray Industries, Inc. Surface treatment of plastic material. 4,297,187, Cl. 204-165.000.
Degussa Aktiengesellschaft: See—
Kleinschmit, Peter; and Schwarz, Rudolf, 4,297,143, Cl. 501-103.000.
Wolff, Siegfried; Rothbuhr, Lothar; and Grewatta Heinz, 4,297,145, Cl. 106-308.00Q.
Dejneka, Tamara: See—
Sundeen, Joseph E.; and Dejneka, Tamara, 4,297,275, Cl. 260-112.50R.
De Koch, Robert J.; Kolb, Gerald C.; and Lalk, James W., to Dow Chemical Company, The. Process for the manufacture of oxazoline and/or oxazine-modified adsorbent polymer resins. 4,297,452, Cl. 525-367.000.
Delavarenne, Serge Y.; Dubreux, Bernard; and Tellier, Pierre, to P C U K Produits Chimiques Ugine Kuhlmann. 5-Amino-1,2,3,4-tetrahydroanthraquinone and its preparation. 4,297,288, Cl. 260-378.000.
Delfosse, Claude, to Fives-Cail Babcock. Centrifugal separator. 4,297,210, Cl. 210-107.000.
DeLuca, Hector F.; Schnoes, Heinrich K.; Paaren, Herbert E.; and Fivizzani, Mary A., to Wisconsin Alumni Research Foundation. Vitamin D compounds isotopically substituted at carbon T and process for their preparation. 4,297,289, Cl. 260-397.200.
Demers, Daniel E.: See—
Durgin, George A.; and Demers, Daniel E., 4,297,077, Cl. 416-97.00R.
Den-Mat, Inc.: See—
Ibsen, Robert L.; and Glace, William R., 4,297,266, Cl. 260-42.140.
Denack Design Corporation: See—
Haack, Dennis A., 4,296,964, Cl. 297-218.000.
Denning, Richard; Spak, Mark A.; and Polhemus, Barry, to RCA Corporation. Method of applying thin metal deposits to a substrate. 4,297,393, Cl. 427-88.000.
Dennis, Ronald D.: See—
Lawson, John E.; and Dennis, Ronald D., 4,297,498, Cl. 546-116.000.
De Ruitter, Robert S.; and Kambanis, Stamatis M., to Reichhold Limited. Process for preparing alkoxylated cross linking agents by preparing (a) an aqueous alkanolic alkoxylated amino resin (b) azeotropic distillation and (c) distilling excess alcohol. 4,297,264, Cl. 260-33.40R.
Detroit, William J.; and Sanford, Michael E., to American Can Company. Well cementing. 4,296,813, Cl. 166-293.000.
Deubel, Reinhold: See—
Uhlig, Heinz; and Deubel, Reinhold, 4,297,270, Cl. 260-104.000.
Devauux, Alain: See—
Curtill, Remi; and Devauux, Alain, 4,296,715, Cl. 123-90.150.
DeVisser, Richard B.; Rishel, John W.; and Kuiper, Joe A., to Dover Corporation. High solids filter. 4,297,209, Cl. 210-107.000.
D'Hinterland, Lucien D.; Normier, Gerard; Pinel, Anne-Marie; and Durand, Jacques, to Pierre Fabre S.A. Process for the preparation of purified bacterial membranaral proteoglycans. 4,297,272, Cl. 260-112.00R.
Diamond Shamrock Corporation: See—
Dotson, Ronald L.; and O'Leary, Kevin J., 4,297,194, Cl. 204-257.000.
Papalos, John G.; and Kavchok, Ronald W., 4,297,259, Cl. 260-29.6NR.
Dichter, Michael: See—
Horowitz, Carl; and Dichter, Michael, 4,297,108, Cl. 44-1.0SR.
Didtel, Stuart R., to Cascade Corporation. Apparatus for automatically depositing a load in a predetermined position. 4,297,070, Cl. 414-497.000.
Diehl, Robert E.: See—
Lutz, Albert W.; and Diehl, Robert E., 4,297,127, Cl. 71-88.000.
Diery, Helmut; Helwerth, Rainer; Frohlich, Horst; and Lorke, Horst, to Hoechst Aktiengesellschaft. Water miscible corrosion inhibitors. 4,297,236, Cl. 252-389.00R.
Dietrich, Lynn A.: See—
Harshman, Ronald W.; and Dietrich, Lynn A., 4,296,773, Cl. 137-312.000.
DiGiannantonio, Edmond P.: See—
Lewis, John S.; DiGiannantonio, Edmond P.; and Boyle, Howard R., 4,297,677, Cl. 340-148.000.
DiGiannantonio, Edmund P.: See—
Lewis, John S.; DiGiannantonio, Edmond P.; and Boyle, Howard R., 4,297,677, Cl. 340-148.000.
Dimou, George: See—
Miller, Kirk D.; Flood, John B.; Dimou, George; Kara, Frederick E.; and Amos, Richard W., 4,296,920, Cl. 266-216.000.
Dirksen, Arnold D. Electroluminescent ring light adapter for aircraft instruments. 4,297,681, Cl. 340-366.00F.
Dirks, Rudolf; and Nitschmann, Karl, to Adreas Stihl. Portable power chain saw. 4,296,553, Cl. 30-381.000.
Dittman, Charles C.; and St. Clair, Richard C., to United States of America. Navy. Motor drive. 4,297,622, Cl. 318-254.000.
Dobbie, Derek J.: See—
Ward, Herbert J.; Dobbie, Derek J.; and Lyall, Brian, 4,297,415, Cl. 428-516.000.
Dobias, Bohuslav; and Heckmann, Klaus, to Heckmann, Klaus. Method to directly bond rubber to metal. 4,297,159, Cl. 156-307.700.
Dobrovolsky, Stanislav D.: See—
Paton, Boris E.; Lebedev, Vladimir K.; Kuchuk-Yatsenko, Sergei I.; Sakharov, Vasily A.; Galyan, Boris A.; and Dobrovolsky, Stanislav D., 4,297,665, Cl. 336-60.000.

Dr. Johannes Heidenhain GmbH: See—
Nelle, Gunther, 4,297,033, Cl. 356-374.000.
Doerges, Alexander: See—
Schlaue, Johann; Kempf, Georg; and Doerges, Alexander, 4,297,330, Cl. 423-232.000.
Doerter, Randall H., to Talon, Inc. Snap fastener component strip. 4,296,533, Cl. 24-216.000.
Dokoupil, Jiri; and Hacker, Kurt. Method for continuous processing of flexible workpieces. 4,296,514, Cl. 12-142.00R.
Dolenc, Bozidar: See—
Suhac, Peter; Hafner-Milac, Natasa; and Dolenc, Bozidar, 4,297,293, Cl. 260-448.00B.
Donachie, Stephen J.: See—
Pickens, Joseph R.; Schelleng, Robert D.; Donachie, Stephen J.; and Nichol, Thomas J., 4,297,136, Cl. 75-206.000.
Donham, Robert E.; and Heimbald, Richard L., to Lockheed Corporation. Wind turbine. 4,297,076, Cl. 416-37.000.
Dorina Nahmaschinen GmbH: See—
Meier, Willi; and Rojahn, Bernd, 4,296,702, Cl. 112-258.000.
Doster, John L.: See—
Silcox, David R.; and Doster, John L., 4,297,095, Cl. 432-59.000.
Dotson, Ronald L.; and O'Leary, Kevin J., to Diamond Shamrock Corporation. Electrolytic production of high purity alkali metal hydroxide. 4,297,194, Cl. 204-257.000.
Dover Corporation: See—
DeVisser, Richard B.; Rishel, John W.; and Kuiper, Joe A., 4,297,209, Cl. 210-107.000.
Dow Chemical Company, The: See—
De Koch, Robert J.; Kolb, Gerald C.; and Lalk, James W., 4,297,452, Cl. 525-367.000.
Ma, King W., 4,297,514, Cl. 568-321.000.
McDonald, Charles J., 4,297,256, Cl. 260-29.4UA.
Moore, Zack J., 4,297,640, Cl. 324-458.000.
Nelson, Linnea E.; and Reineke, Charles E., 4,297,475, Cl. 528-271.000.
Dowty Fuel Systems Limited: See—
Andrews, David K.; and Smart, Michael W., 4,296,676, Cl. 91-417.00R.
Drabert Sohne Minden: See—
Edel, Hans J., 4,296,903, Cl. 248-162.100.
Dreher, Ulrich: See—
Link, Hans; and Dreher, Ulrich, 4,297,636, Cl. 324-262.000.
Drent, Eit: See—
Van Broekhoven, Johannes A. M.; and Drent, Eit, 4,297,517, Cl. 568-361.000.
Dresser Industries, Inc.: See—
Chamberlin, Richard L., 4,296,950, Cl. 285-45.000.
O'Neil, John C., deceased, 4,297,057, Cl. 405-303.000.
Drews, Ulrich: See—
Werner, Peter; Drews, Ulrich; Elbers, Theodor; and Jackel, Klaus, 4,297,599, Cl. 307-355.000.
Dube, Ghyslain, to Alcan Research and Development Limited. Automatic photometric titrator. 4,297,105, Cl. 23-230.00R.
Dubreux, Bernard: See—
Delavarenne, Serge Y.; Dubreux, Bernard; and Tellier, Pierre, 4,297,288, Cl. 260-378.000.
Duckstein, Stuart S. Method for manufacturing a pacifier. 4,297,313, Cl. 264-273.000.
Duff, William H., to Bell Telephone Laboratories, Incorporated. Encapsulated light source with coupled fiberoptic. 4,296,998, Cl. 350-96.200.
DuJack, George M., Jr.: See—
Goodale, Robert H.; and DuJack, George M., Jr., 4,296,634, Cl. 73-864.860.
Dukes, Jesse M. Agricultural crop cover. 4,296,568, Cl. 47-20.000.
Dunbar, Glenn G. Weight transfer apparatus. 4,297,071, Cl. 414-542.000.
Dunlop Limited: See—
Poppellwell, Frank W., 4,297,308, Cl. 264-46.600.
Dunning, Ted E.; and Enright, Paul L., to Cyber Diagnostics, Inc. Remote pulmonary function tester. 4,296,756, Cl. 128-716.000.
Du Pont de Nemours, E. I., and Company: See—
Phillips, Thomas R., 4,297,262, Cl. 260-31.600.
Soboczenski, Edward J., 4,297,370, Cl. 424-298.000.
Dupont, Jean M., to Compagnie Internationale pour l'Informatique CII-Honeywell Bull. System for controlling a separately excited constant load DC electric motor. 4,297,623, Cl. 318-410.000.
Dupressoir, Albert, to Thomson-CSF. Parallel-plane antenna with rotation of polarization. 4,297,710, Cl. 343-756.000.
Duracell International Inc.: See—
Przybyla, Franciszek J.; and Rossler, Eleanor J., 4,297,249, Cl. 252-518.000.
Durand, Jacques: See—
D'Hinterland, Lucien D.; Normier, Gerard; Pinel, Anne-Marie; and Durand, Jacques, 4,297,272, Cl. 260-112.00R.
Durgin, George A.; and Demers, Daniel E., to Westinghouse Electric Corp. Cooled turbine vane. 4,297,077, Cl. 416-97.00R.
Durst, Richard R.: See—
Bingham, Robert E.; Durst, Richard R.; Fabris, Hubert J.; Hargis, Ivan G.; Livigni, Russell A.; and Aggarwal, Sundar L., 4,297,240, Cl. 252-431.00R.
Dyachkov, Vasily M.: See—
Shlykov, Gennady N.; Zhestkov, Vitaly I.; Tikhonov, Valentin N.; Dyachkov, Vasily M.; Glazov, Vladimir G.; and Krjuk, Timur P., 4,296,528, Cl. 19-255.000.

Dyer, Christopher K., to United Chemi-Con, Inc. Method of etching aluminum. 4,297,184, Cl. 204-129.400.
Dyer, Jack E.: See—
Peller, Robert C.; and Dyer, Jack E., 4,296,839, Cl. 188-378.000.
Dymont, John C.; and Chik, Kiuchi D., to Northern Telecom Limited. Methods for simultaneous suppression of laser pulsations and continuous monitoring of output power. 4,297,651, Cl. 331-94.50H.
Dynamit Nobel Aktiengesellschaft: See—
Herrmann, Hans-Joachim; Meyer, Gunther; and Steffen, Klaus-Dieter, 4,297,502, Cl. 560-35.000.
Simon, Manfred; Moschter, Erwin; Spiess, Karl-Heinz; and Weiss, Richard, 4,297,099, Cl. 8-484.000.
E. C. H. Will (GmbH & Co.): See—
Ramcke, Bernd; Schlottke, Karl-Heinz; Brandt, Eckhard; and Reissmann, Klaus, 4,297,066, Cl. 414-43.000.
E. J. Brooks Company: See—
Guiler, Richard S., 4,296,616, Cl. 70-34.000.
E. R. Squibb & Sons, Inc.: See—
Sundeen, Joseph E.; and Dejneka, Tamara, 4,297,275, Cl. 260-112.50R.
E-Systems, Inc.: See—
Pate, Jerry W., 4,297,527, Cl. 179-1.0VC.
EABVV Utvecklings Aktiebolag: See—
Bilberg, Erik A., 4,296,711, Cl. 122-22.000.
Eadie, Brian K. M., to Eadie Bros. & Co. Limited. Textile combing roller. 4,296,527, Cl. 19-112.000.
Eadie Bros. & Co. Limited: See—
Eadie, Brian K. M., 4,296,527, Cl. 19-112.000.
Eastman Kodak Company: See—
Bowman, Wayne A.; Bishop, John F.; and Noonan, John M., 4,297,432, Cl. 430-215.000.
Smith, Thomas W., 4,297,465, Cl. 526-141.000.
Eaton Corporation: See—
Kains, Ilmars, 4,296,650, Cl. 74-751.000.
Rice, Robert A., 4,296,770, Cl. 137-62.000.
Ebata, Noboru: See—
Kahara, Toshiki; Tamura, Kohki; Ebata, Noboru; Sato, Fumio; and Yoshida, Tomio, 4,297,231, Cl. 252-182.100.
EBCO Industries, Ltd.: See—
Eppich, Helmut, 4,297,735, Cl. 360-104.000.
Eber, Nicholas. Absorption refrigerator. 4,296,613, Cl. 62-515.000.
Ebisawa, Kiyohito; Hisabayashi, Satoshi; Koike, Toshio; and Hashimoto, Kazuyuki, to Iwatsu Electric Co., Ltd. Exposure device of an electrographic copying apparatus. 4,297,024, Cl. 355-14.00E.
EC Erdolchemie GmbH: See—
Mainusch, Klaus; Schleppinghoff, Bernhard; and Munter, Klaus, 4,297,512, Cl. 564-490.000.
Eckert, Kim, to Motorola, Inc. Schmitt trigger. 4,297,596, Cl. 307-279.000.
Eckler, Paul E.; Summers, William A.; and Chandler, Ollie W., to International Minerals & chemical Corporation. Method for polyurethane foam using a tri-tertiary amine catalyst. 4,297,443, Cl. 521-129.000.
Edel, Hans J., to Drabert Sohne Minden. Actuator button apparatus for adjustable chairs. 4,296,903, Cl. 248-162.100.
Edelman, Seymour: See—
Wooden, Bruce J.; and Edelman, Seymour, 4,297,394, Cl. 427-100.000.
Edwards, Bryant, to Illinois Tool Works Inc. Nestable and stackable transplanting system. 4,296,569, Cl. 47-73.000.
Edwards, Laroy H., to Chevron Research Company. N-Tetrachloroethylthio-substituted halomethanesulfonamides as aquatic weed control agents. 4,297,124, Cl. 71-66.000.
Egenlauf, Louis D. Slap trim interior molding. 4,296,583, Cl. 52-717.000.
Eibe, Werner W., to Blaw-Knox Foundry & Mill Machinery, Inc. Semi-continuous hot rolling of metal strip and plates. 4,296,623, Cl. 72-227.000.
Eicher, Theobald; and Muller, Friedemann, to Bayer Aktiengesellschaft. Smokable products. 4,296,762, Cl. 131-359.000.
Eidenschink, Rudolf; and Pohl, Ludwig, to Merck Patent Gesellschaft mit Beschränkter Haftung. Diketones useful as liquid crystals. 4,297,515, Cl. 568-329.000.
Eisele Apparate-und Gerätebau GmbH: See—
Taddicken, Hermann; and Sachs, Wolfgang, 4,296,696, Cl. 112-70.000.
Ekstrom, Hans. Omnidirectional receiving antenna. 4,297,711, Cl. 343-794.000.
Elastoflon Inc.: See—
Yasuda, Toshio, 4,297,447, Cl. 525-133.000.
Elbers, Theodor: See—
Werner, Peter; Drews, Ulrich; Elbers, Theodor; and Jackel, Klaus, 4,297,599, Cl. 307-355.000.
Electric Power Research Institute, Inc.: See—
Lee, Ilyoul, 4,297,738, Cl. 361-42.000.
Electrostatic Equipment Corporation: See—
Gillette, Donald J., 4,297,386, Cl. 427-27.000.
Eli Lilly and Company: See—
Debono, Manuel, 4,297,277, Cl. 260-112.50R.
Elias, Moenes L.; and Shah, Narendra K., to Dart Industries Inc. Metal stripping composition and method. 4,297,257, Cl. 260-29.60H.
Elkem-Spigerverket a/s: See—
Gjelsvik, Norvald; and Hundere, Ingleif, 4,297,326, Cl. 423-126.000.
Gjelsvik, Norvald; Hannestad, Gunnar; Hundere, Ingleif; and Torgersen, Jan H., 4,297,327, Cl. 423-126.000.

- Emhart Industries, Inc.: See—
Chestnut, Benjamin F., 4,297,547, Cl. 200-38.00R.
Darnier, Ronald G., 4,297,545, Cl. 200-38.00R.
- EMI Limited: See—
Steynor, James H.; and Hayes, Frederick, 4,297,729, Cl. 360-40.000.
- Endoh, Hiroyuki: See—
Sasaki, Tohru; Endoh, Hiroyuki; and Ohhira, Hiroshi, 4,297,413, Cl. 428-394.000.
- Endoh, Takeyuki: See—
Kodama, Kazuyuki; Okada, Kunihiro; Endoh, Takeyuki; and Shibuya, Yasutaka, 4,297,691, Cl. 340-723.000.
- Engelbach, Heinz: See—
Krabetz, Richard; Herrmann, Walter; Engelbach, Heinz; Palm, Peter; Sommer, Karl; and Spahn, Heinrich, 4,297,247, Cl. 252-468.000.
- Engelhard Minerals & Chemicals Corporation: See—
Miller, John G.; and Schwab, Thomas C., 4,297,131, Cl. 75-1.00T.
- Engeman, Rock A.: See—
Ward, Franklin D.; and Engeman, Rock A., 4,296,878, Cl. 224-32.00A.
- Enomoto, Yutaka: See—
Takizawa, Hiroshi; Enomoto, Yutaka; Oiji, Yoshimasa; Hirayama, Tatsuyuki; and Hashimoto, Tamotu, 4,297,369, Cl. 424-285.000.
- Enright, Paul L.: See—
Dunning, Ted E.; and Enright, Paul L., 4,296,756, Cl. 128-716.000.
- Enso, Inc.: See—
Fowler, James C.; Hale, Steven D.; and Moser, Theodore E., 4,297,699, Cl. 343-5.0NA.
- Environmental Devices Corporation: See—
Brainard, Edward C., II, 4,297,685, Cl. 340-575.000.
- Envoy U.S.A., Inc.: See—
Gamm, Robert J., 4,296,559, Cl. 36-136.000.
- Eppich, Helmut, to EBCO Industries, Ltd. Manually operable magnetic card reader and magnetic head assembly therefor. 4,297,735, Cl. 360-104.000.
- Epstein, Barry M.; and Gernstein, Terry M. Pushbutton telephone set disabling means. 4,297,534, Cl. 179-90.00D.
- Erickson, Erick E.; Katzman, Allison W.; and Breslow, Jeffrey D., to Marvin Glass & Associates. Method and apparatus for making doll clothing and doll house accessories. 4,297,153, Cl. 156-63.000.
- Ernebrant, Lennart C.: See—
Rossander, Bror L. E.; Ernebrant, Lennart C.; and Lesser, Martin, 4,296,830, Cl. 181-208.000.
- Ernst, Richard J., to Illinois Tool Works Inc. Driver bit attachment. 4,296,656, Cl. 81-429.000.
- Ertel, Werner, to Bayer Aktiengesellschaft. Process for the preparation of 2-nitrobenzaldehyde. 4,297,519, Cl. 568-424.000.
- Erwin, Galen B.: See—
Arnold, Harmon W.; and Erwin, Galen B., 4,297,418, Cl. 428-595.000.
- Esanu, Andre, to Societe d'Etudes de Produits Chimiques. Preparation of 2-isopropylamino pyrimidine. 4,297,495, Cl. 544-330.000.
- Escobosa, Alfonso S. Hydraulic controlled sonic induction system. 4,296,911, Cl. 251-57.000.
- Estes, John H.: See—
Bartley, Burton H.; and Estes, John H., 4,297,245, Cl. 252-460.000.
- Evak Sanitar AB: See—
Nilsson, Robert, 4,296,772, Cl. 137-269.500.
- Evans, Arthur R.: See—
Airey, Frederick K.; and Evans, Arthur R., 4,297,213, Cl. 210-195.100.
- Evans, Roger C. Ball holder. 4,296,874, Cl. 221-307.000.
- Evans, Samuel: See—
Rasberger, Michael; Rosenberger, Siegfried; and Evans, Samuel, 4,297,492, Cl. 544-211.000.
- Ex-Cell-O Corporation: See—
Fleury, James C., 4,296,805, Cl. 165-151.000.
- Exxon Production Research Company: See—
Willman, Bertram T., 4,296,969, Cl. 299-2.000.
- Exxon Research & Engineering Co.: See—
Blaser, Don E., 4,297,202, Cl. 208-54.000.
- Feldman, Nicholas, 4,297,110, Cl. 44-66.000.
- Fabris, Hubert J.: See—
Bingham, Robert E.; Durst, Richard R.; Fabris, Hubert J.; Hargis, Ivan G.; Livigni, Russell A.; and Aggarwal, Sundar L., 4,297,240, Cl. 252-431.00R.
- Fag Kugelfischer Georg Schafer & Co.: See—
Hofmann, Heinrich; and Markfelder, Gunther, 4,296,979, Cl. 308-174.000.
- Fagan, Robert D.: See—
Shah, Siddharth A.; Woodcock, Sidney J.; and Fagan, Robert D., 4,297,072, Cl. 414-684.300.
- Fagersta A.B.: See—
Rossander, Bror L. E.; Ernebrant, Lennart C.; and Lesser, Martin, 4,296,830, Cl. 181-208.000.
- Fairbanks, Thomas L. Telephone security attachment. 4,297,539, Cl. 179-189.00D.
- Falborn, James A.: See—
Stoute, Neville, Sr.; and Pennise, Robert J., 4,296,506, Cl. 4-480.000.
- Falkenbach, Guenther, to Braun AG. Electric blender. 4,297,038, Cl. 366-206.000.
- Farmer, Marion R., to Aluma Form, Inc. Electrical equipment mount. 4,296,904, Cl. 248-218.400.
- Farmer, Zane M., to Polaroid Corporation. Photographic camera apparatus. 4,297,017, Cl. 354-34.000.
- Farmitalia Carlo Erba S.p.A.: See—
Gandolfi, Carmelo; Passarotti, Carlo; Andreoni, Alessandro; Fumagalli, Angelo; Faustini, Franco; Ceserani, Roberto; and Usardi, Maria M., 4,297,368, Cl. 424-285.000.
- Farrant, David J. R., to Automotive Products Limited. Ball and socket joint. 4,297,047, Cl. 403-138.000.
- Faulconer, Richard J. Fruit picker. 4,296,594, Cl. 56-336.000.
- Faure, Jean-Louis. Apparatus for providing false twist to moving yarn. 4,296,598, Cl. 57-284.000.
- Faustini, Franco: See—
Gandolfi, Carmelo; Passarotti, Carlo; Andreoni, Alessandro; Fumagalli, Angelo; Faustini, Franco; Ceserani, Roberto; and Usardi, Maria M., 4,297,368, Cl. 424-285.000.
- Federal-Mogul Corporation: See—
Ladin, Eli M., 4,296,977, Cl. 308-19.000.
- Fedorov, Vasily N.: See—
Bashnin, Oleg I.; Semenov, Vasily V.; Fedorov, Vasily N.; Gorbunov, Nikolai M.; Rodionov, Evgeny I.; and Sorokin, Nikolai A., 4,297,589, Cl. 290-40.00R.
- Felder, Donald W. Polish rod jack system. 4,296,678, Cl. 92-13.100.
- Felder, Louis; and Kirchmayr, Rudolf, to Ciba-Geigy Corporation. Process for the preparation of benzophenone thioethers. 4,297,513, Cl. 568-43.000.
- Feldman, Nicholas, to Exxon Research & Engineering Co. Zirconium additives for residual fuel oil. 4,297,110, Cl. 44-66.000.
- Feldstein, Nathan. Catalytic promoters in electroless plating catalysts in true solutions. 4,297,397, Cl. 427-304.000.
- Ferd, Wagner: See—
Krug, Hans; and Heilmann, Kurt, 4,297,416, Cl. 428-576.000.
- Ferguson, James L., to Becton, Dickinson and Company. Liquid crystal compositions and devices. 4,296,631, Cl. 73-356.000.
- Fergg, Berthold: See—
Stemme, Otto; Fergg, Berthold; Osegowitsch, Viktor; and Viehrig, Wolfgang, 4,297,027, Cl. 355-27.000.
- Ferm, Donald J.: See—
Speak, Richard C.; and Ferm, Donald J., 4,297,229, Cl. 252-109.000.
- Ferree, William L., Jr.; and Nguyen, Giao V., to Liquid Paper Corporation. Erasable writing medium composition. 4,297,260, Cl. 260-29.70H.
- Fett, Helen M.: See—
Haas, Michael J.; Pratt, Paul D.; Chen, Rocky W.; and Fett, Helen M., 4,297,378, Cl. 426-532.000.
- Fetty, Harold D.: See—
Roberts, Charles W.; Kolowski, Michael A.; Lindner, Daniel J.; Lynch, John E.; Ruip, Terrence M.; and Fetty, Harold D., 4,296,789, Cl. 152-209.00R.
- Feuerherd, Karl-Heinz: See—
Koenig, Karl-Heinz; and Feuerherd, Karl-Heinz, 4,297,300, Cl. 260-544.00C.
- Fichet-Bauche: See—
Guiraud, Francois, 4,296,618, Cl. 70-358.000.
- Filtrol Corporation: See—
Scherzer, Julius; Liu, Anh-Thu; and Sun, Yih-Yau, 4,297,325, Cl. 423-122.000.
- Finan, Thomas P.: See—
Burton, Robert L.; and Finan, Thomas P., 4,297,045, Cl. 400-641.000.
- Fine, Jerry W.: See—
Rubottom, Nolan R.; and Fine, Jerry W., 4,297,675, Cl. 340-107.000.
- Fine, Louis B.: See—
Pontifex, Edward J., 4,296,749, Cl. 128-283.000.
- Finke, Ulrich; and Moretto, Hans-Heinrich, to Bayer Aktiengesellschaft. Conversion of low-boiling constituents from alkyl-chlorosilane synthesis. 4,297,500, Cl. 556-466.000.
- Fischer, Michael A., to Grinnell Fire Protection Systems Company, Inc. Horizontal sprinkler deflector with flow lifting formation. 4,296,816, Cl. 169-37.000.
- Fischer & Porter Co.: See—
Mannherz, Elmer D., 4,296,636, Cl. 73-861.120.
- Fisher, Sidney E.: See—
Hunt, Keith R.; and Fisher, Sidney E., 4,296,961, Cl. 296-216.000.
- Fives-Cail Babcock: See—
Delfosse, Claude, 4,297,210, Cl. 210-107.000.
- Fivizzani, Mary A.: See—
DeLuca, Hector F.; Schnoes, Heinrich K.; Paaren, Herbert E.; and Fivizzani, Mary A., 4,297,289, Cl. 260-397.200.
- Flanders, Thomas W., to CTS Corporation. Tandem insert molded electrical controls and process for producing same. 4,297,671, Cl. 338-200.000.
- Fletcher, Augustus; and Moriarty, William L., to American Chemical & Refining Company Incorporated. Method and composition for electrodeposition of palladium/nickel alloys. 4,297,177, Cl. 204-43.00N.
- Fleury, James C., to Ex-Cell-O Corporation. Accessory clearance hole. 4,296,805, Cl. 165-151.000.
- Flex-o-lators, Inc.: See—
Arnold, Harmon W.; and Erwin, Galen B., 4,297,418, Cl. 428-595.000.
- Flies, William P., to Datakey, Inc. Microelectronic memory key with receptacle and systems therefor. 4,297,569, Cl. 235-443.000.
- Floessel, Carl D.; and Floessel, Klaus, to BBC Brown, Boveri & Company, Ltd. Gas pipe cable. 4,297,523, Cl. 174-27.000.
- Floessel, Klaus: See—
Floessel, Carl D.; and Floessel, Klaus, 4,297,523, Cl. 174-27.000.

- Flood, John B.: See—
Miller, Kirk D.; Flood, John B.; Dimou, George; Kara, Frederick E.; and Amos, Richard W., 4,296,920, Cl. 266-216.000.
- Focke & Co.: See—
Focke, Heinz, 4,296,590, Cl. 53-531.000.
- Focke, Heinz, to Focke & Co. Method and apparatus for conveying six-pack containers to carton blank. 4,296,590, Cl. 53-531.000.
- Folonari, Carlo: See—
Daolio, Sergio; Mengoli, Guiliano; Folonari, Carlo; and Musiani, Marco, 4,297,188, Cl. 204-181.00R.
- Fong, Harry H. S.: See—
Waller, Donald P.; Zaneveld, Lourens J. D.; and Fong, Harry H. S., 4,297,341, Cl. 424-80.000.
- Ford Motor Company: See—
Chang, Yun-Feng; Oene, Henk V.; and Beckwith, Elaine C., 4,297,448, Cl. 525-162.000.
- Giardini, Dante S., 4,297,089, Cl. 417-437.000.
- May, James I., 4,296,641, Cl. 74-422.000.
- Ford, William D., and Clark, Michael J., to Standard Oil Company (Indiana). Apparatus for the catalytic cracking of hydrocarbons. 4,297,203, Cl. 208-74.000.
- Forenade Fabriksverken: See—
Hammar, Jan E., 4,296,767, Cl. 134-15.000.
- Fork, Frank W., to H. H. Robertson Company. Electrical activating assembly and receptacle support means therefor. 4,297,524, Cl. 174-48.000.
- Forrester, A. Theodore: See—
Goebel, Dan M.; Crow, James T.; and Forrester, A. Theodore, 4,297,615, Cl. 315-111.210.
- Forsman, Lars O. Device for transmitting linear measuring motion. 4,296,975, Cl. 308-6.00R.
- Foster, Alan I.; Sims, Malcolm L.; and Young, Dennis, to British Petroleum Company Limited. The protective metal oxide films on metal or alloy substrate surfaces susceptible to coking, corrosion or catalytic activity. 4,297,150, Cl. 148-6.300.
- Foster, Perry A., Jr., to Aluminum Company of America. Electrolytic production of metal. 4,297,180, Cl. 204-67.000.
- Fowler, James C.; Hale, Steven D.; and Moser, Theodore E., to Enso, Inc. Radar drill guidance system. 4,297,699, Cl. 343-5.0NA.
- Fowler, Kenneth A.: See—
Lynnworth, Lawrence C.; Fowler, Kenneth A.; and Patch, Dana R., 4,297,607, Cl. 310-334.000.
- Fox, Roland T. V.: See—
Henrick, Clive A.; Labovitz, Jeffrey N.; Fox, Roland T. V.; Rathmell, William G.; and Shephard, Margaret C., 4,297,297, Cl. 260-465.00D.
- Framatome: See—
Leclercq, Joseph, 4,297,170, Cl. 376-442.000.
- Frankel, Milton B.; Arbit, Harry A.; Artz, Glen D.; and Gray, John C., to United States of America, Air Force. Energetic monopropellant. 4,297,152, Cl. 149-88.000.
- Franklin, Benjamin S.: See—
Appell, Marc; Bogaert, Jean-Louis; Massuard, Claude; Bradley, John; and Franklin, Benjamin S., 4,297,743, Cl. 364-200.000.
- Franklin Electric Co., Inc.: See—
Schaefer, Edward J., 4,297,627, Cl. 318-778.000.
- Franz, Karl; and Schonfeld, Bernd, to Riedel-de Haen Aktiengesellschaft. Process for the preparation of a red emitting phosphor coated with red iron oxide and its application. 4,297,390, Cl. 427-64.000.
- Frazier, Stephen E., to Rush-Hampton Industries, Inc. Composition and method for the treatment of acne. 4,297,348, Cl. 424-180.000.
- Frederiksen, Jeffrey E., to Bally Manufacturing Corporation. TV Game apparatus. 4,296,930, Cl. 273-313.000.
- Freed, Donald L., Jr., to National Mine Service Company. Material gathering device for a mining machine. 4,296,856, Cl. 198-514.000.
- Freitag, Dieter: See—
Lindner, Christian; Suling, Carlhans; Bartl, Herbert; Schreckenberger, Manfred; Freitag, Dieter; and Konig, Klaus, 4,297,455, Cl. 525-439.000.
- Frerking, Marvin E., to Rockwell International Corporation. Closed loop temperature compensated frequency reference. 4,297,657, Cl. 331-176.000.
- Freudenschuss, Otto, to Vockenhuber, Karl; and Hauser, Raimund. Method and device for locating a sound event on a magnetic tape. 4,297,732, Cl. 360-72.100.
- Fricke, Gunter: See—
Singewald, Arno; Geisler, Irving; Fricke, Gunter; and Knappe, Rudolf, 4,297,207, Cl. 209-9.000.
- Friedman, Jack S.: See—
Schmitt, Wilhelm E., 4,296,519, Cl. 15-184.000.
- Fries, James E. Solar lighting system. 4,297,000, Cl. 350-96.240.
- Froehlich, Helmut: See—
Richarz, Winfried; Froehlich, Helmut; and Schroeder, Harald, 4,297,493, Cl. 544-241.000.
- Froehlich, Horst: See—
Diery, Helmut; Helwerth, Rainer; Froehlich, Horst; and Lorke, Horst, 4,297,236, Cl. 252-389.00R.
- Fruchey, Russell L.; and Kuper, Daniel E., to D.E.W. Line, Inc. Early warning system for approaching transportation vehicles. 4,297,672, Cl. 340-23.000.
- Fuchs, Rainer; Hammann, Ingeborg; Homeyer, Bernhard; Behrenz, Wolfgang; and Stendel, Wilhelm, to Bayer Aktiengesellschaft. Combating arthropods with 2,2-dimethyl-3-(2-fluoroalkyl-2-oxy-vinyl)-cyclopropane-carboxylic acid esters. 4,297,366, Cl. 424-274.000.
- Fuchs, Rainer; Gallenkamp, Bernd; and Stendel, Wilhelm, to Bayer Aktiengesellschaft. Combating pests with (±)-trans-3-(E/Z-2-chloro-2-(4-chlorophenyl)-vinyl)-2,2-dimethyl-cyclopropanecarboxylic acid (±)-(α-cyano-3-phenoxy-4-fluoro-benzyl) ester and the individual E- and Z-isomers. 4,297,371, Cl. 424-304.000.
- Fuji Kiko Co., Ltd.: See—
Matsuoka, Hideoki; and Kondo, Yoshinobu, 4,296,944, Cl. 280-804.000.
- Fuji Photo Film Co., Ltd.: See—
Aoki, Kozo; Sawada, Satoru; Yabuki, Yoshiharu; and Furutachi, Nobuo, 4,297,440, Cl. 430-505.000.
- Higashi, Akio; Kawaziri, Kazuhiro; and Nakajima, Yosuke, 4,297,392, Cl. 427-75.000.
- Hoshi, Yoshiyuki; Hayashi, Takayuki; and Kakimi, Fujio, 4,297,235, Cl. 252-316.000.
- Kubotera, Kikuo; Sato, Masamichi; Kashiwabara, Akira; and Sato, Kotaro, 4,297,436, Cl. 430-310.000.
- Kudo, Yoshio; Iwasa, Masakazu; and Kato, Hisashi, 4,297,384, Cl. 427-14.100.
- Osada, Chiaki; Satomura, Masato; and Ono, Hisatake, 4,297,470, Cl. 526-304.000.
- Takehara, Nobumitsu; and Isayama, Shogo, 4,297,396, Cl. 427-284.000.
- Fujii, Etsuo: See—
Sato, Makoto; Takamatsu, Hiroshi; Miyagawa, Yoshitaka; and Fujii, Etsuo, 4,296,972, Cl. 303-119.000.
- Fujii, Kenji, to Yoshida Iron Works Co., Ltd. Method and means for adding treating agent for molten metal. 4,297,133, Cl. 75-53.000.
- Fujii, Shuzo; and Sato, Yoshikatsu, to Nippon Electric Co., Ltd. Temperature compensated crystal oscillator. 4,297,655, Cl. 331-116.00R.
- Fujii, Tadashi; Sato, Shuzo; Muto, Naoki; Hayashi, Mitsuo; Kodama, Akira; and Otani, Masaru, to Toyo Jozo Kabushiki Kaisha. Amino-glycoside antibiotic G-367-1 and method for the production thereof. 4,297,486, Cl. 536-17.00R.
- Fujii, Takashi: See—
Kizaki, Jiro; and Fujii, Takashi, 4,296,604, Cl. 60-562.000.
- Fujimaki, Kiyoshi; Bando, Yoshiaki; Okuyama, Takeshi; and Hashimoto, Tutomu, to Sekisui Kagaku Kogyo Kabushiki Kaisha. Pipe coupling and pipe joint connection. 4,296,954, Cl. 285-331.000.
- Fujimori, Fumio; Yokoi, Masatada; Ishikawa, Masakazu; Uemura, Hiroshi; and Shirai, Akira, to Aisin Seiki Kabushiki Kaisha; and Toyota Jidosha Kogyo Kabushiki Kaisha. Antirattle spring for a disc brake of vehicles. 4,296,841, Cl. 188-73.380.
- Fujisawa Pharmaceutical Co. Ltd.: See—
Yoshida, Keizo; Tanaka, Hirokazu; Okamoto, Masanori; Iguchi, Eiko; Kohsaka, Masanobu; Aoki, Hatsu; and Imanaka, Hiroshi, 4,297,096, Cl. 435-128.000.
- Fujitsu Fanuc Limited: See—
Komiya, Hidetsugu, 4,297,624, Cl. 318-594.000.
- Fujitsu Limited: See—
Nagahama, Tsutomu; and Ishihara, Michio, 4,297,722, Cl. 357-74.000.
- Fukuda, Takeo; Hanawa, Kazuhiko; Uru, Kiyoshi; and Haseyama, Michiko, to Tokyo Shibaura Denki Kabushiki Kaisha. Interfacing circuit status detection arrangement in a telephone exchange. 4,297,532, Cl. 179-18.0AB.
- Fukuoka, Yohei: See—
Nishikido, Joji; Tamura, Nobuhiro; Fukuoka, Yohei; and Yamane, Hiroyuki, 4,297,503, Cl. 560-42.000.
- Fumagalli, Angelo: See—
Gandolfi, Carmelo; Passarotti, Carlo; Andreoni, Alessandro; Fumagalli, Angelo; Faustini, Franco; Ceserani, Roberto; and Usardi, Maria M., 4,297,368, Cl. 424-285.000.
- Furrier, Joseph P.; and Gilbert, Allan H., to Lever Brothers Company. Toothbrush and gum massaging accessory. 4,296,518, Cl. 15-110.000.
- Furuhashi, Toshio; and Abe, Osamu, to Hitachi, Ltd. Control apparatus for an internal combustion engine. 4,296,722, Cl. 123-492.000.
- Furukawa, Takashi: See—
Sakurai, Koichi; Furukawa, Takashi; Takechi, Hiroshi; and Matsuo, Munetsugu, 4,296,919, Cl. 266-111.000.
- Furukawa, Takeshi: See—
Misaka, Takaaki; Furukawa, Takeshi; and Onuma, Eiichi, 4,296,864, Cl. 209-144.000.
- Furukawa, Yukio: See—
Inayama, Minoru; and Furukawa, Yukio, 4,297,558, Cl. 219-10.55R.
- Furusawa, Kahei: See—
Niuro, Yasuhiko; Furusawa, Kahei; and Okada, Akira, 4,296,996, Cl. 350-96.200.
- Furutachi, Nobuo: See—
Aoki, Kozo; Sawada, Satoru; Yabuki, Yoshiharu; and Furutachi, Nobuo, 4,297,440, Cl. 430-505.000.
- Furutani, Toshinobu: See—
Shinohara, Hiroshi; Otsuka, Yasuhiro; Matsumoto, Shinichi; Wakasaka, Hiroshi; and Furutani, Toshinobu, 4,297,192, Cl. 204-195.00S.
- Fuzzell, Joe E., to Caterpillar Tractor Co. Leak detection apparatus. 4,297,687, Cl. 340-626.000.
- G. D. Searle & Co.: See—
Mueller, Richard A., 4,297,487, Cl. 542-412.000.
- Raymond, Christopher D., 4,296,745, Cl. 128-156.000.
- G & W Electric Specialty Company: See—
Rueth, William R., Jr., 4,297,554, Cl. 200-153.05C.
- Gaertner, Friedheim: See—
Caesar, Arndt C.; Koegel, Wolfram; Zuern, Ludwig; and Gaertner, Friedheim, 4,297,252, Cl. 252-606.000.
- Gaines, Jack R.: See—
Haissig, Bruce E.; Gaines, Jack R.; and Giacchetto, Glen, 4,297,125, Cl. 71-77.000.

- Galaspie, Charles E. Light producing device. 4,297,617, Cl. 315-326.000.
- Gale, James A., to Kenneth E. Beswick Ltd. Thermal cut-outs and to the method of assembling a multiplicity of such thermal cut-outs. 4,297,669, Cl. 337-407.000.
- Gallagher, David A., to Bunker Ramo Corporation. Electrical connector assembly. 4,296,992, Cl. 339-186.00M.
- Gallenkamp, Bernd: See—
Fuchs, Rainer; Gallenkamp, Bernd; and Stendel, Wilhelm, 4,297,371, Cl. 424-304.000.
- Gallet, Georges: See—
Chaumat, Bernard; Gallet, Georges; Lamare, Jacques; and Peysard, Guy, 4,296,791, Cl. 160-206.000.
- Galley, Richard A.: See—
Bryant, David R.; and Galley, Richard A., 4,297,239, Cl. 252-412.000.
- Galyan, Boris A.: See—
Paton, Boris E.; Lebedev, Vladimir K.; Kuchuk-Yatsenko, Sergei I.; Sakharov, Vasily A.; Galyan, Boris A.; and Dobrovolsky, Stanislav D., 4,297,665, Cl. 336-60.000.
- Gambro AB: See—
Carlsson, Per-Olov A. V.; and Hakansson, Bo H., 4,296,760, Cl. 128-788.000.
Hakansson, Hakan B.; Persson, Lennart P. E.; and Wall, Berth-Ove G., 4,296,633, Cl. 73-362.0AR.
- Gamm, Robert J., to Envoys U.S.A., Inc. Athletic shoe pocket. 4,296,559, Cl. 36-136.000.
- Gander, Jean-Gabriel; and Aubert, Ralph, to LGZ Landis & Gyr Zug AG. Detector to determine the presence of an electrical signal in the presence of noise of predetermined characteristics. 4,297,533, Cl. 179-84.0VF.
- Gandolfi, Carmelo; Passarotti, Carlo; Andreoni, Alessandro; Fumagalli, Angelo; Faustini, Franco; Ceserani, Roberto; and Usardi, Maria M., to Farmitalia Carlo Erba S.p.A. Pharmaceutically useful 5,6-saturated PGI compounds. 4,297,368, Cl. 424-285.000.
- Garbe, Dietmar R. Spirometers. 4,296,758, Cl. 128-728.000.
- Garrett Corporation, The: See—
Burgmeier, Lyman R.; McCarty, Frederick B.; and Silver, Alexander, 4,296,544, Cl. 29-598.000.
McGowan, Peter T., 4,297,086, Cl. 417-271.000.
- Garrett, Harold E., to United States of America, Army. Segmented sabot projectile. 4,296,687, Cl. 102-518.000.
- Garrett, Robert W., to Western Electric Co., Inc. Method for removing heat from a workpiece during processing in a vacuum chamber. 4,297,190, Cl. 204-192.00E.
- Gaughan, Edmund J.; and Kezerian, Charles, to Stauffer Chemical Company. N-(Benzenesulfonyl) thiocarbamates-herbicide antidotes. 4,297,295, Cl. 260-455.00A.
- Gebel, Josef: See—
Altmeyer, Hans J.; and Gebel, Josef, 4,297,215, Cl. 210-386.000.
- Geisler, Irving: See—
Singewald, Arno; Geisler, Irving; Fricke, Gunter; and Knappe, Rudolf, 4,297,207, Cl. 209-9.000.
- Gen-Tech, Inc.: See—
Tawse, Ian S., 4,297,604, Cl. 310-168.000.
- General Atomic Company: See—
Taylor, Edward S.; and Hirschle, George W., 4,296,713, Cl. 122-32.000.
- General Dynamics Corporation: See—
Pazmany, Ladislao, 4,296,895, Cl. 244-3.290.
Peller, Robert C.; and Dyer, Jack E., 4,296,839, Cl. 188-378.000.
- General Electric Company: See—
Adamson, Arthur P., 4,296,599, Cl. 60-39.230.
Banucci, Eugene G.; and Boldebuck, Edith M., 4,297,385, Cl. 427-27.000.
Bloomer, Milton D.; and Kornumpf, William P., 4,296,632, Cl. 73-362.0AR.
Griffin, James R.; and Schreck, Raymond M., 4,296,611, Cl. 62-89.000.
Grubb, Willard T., 4,297,168, Cl. 376-418.000.
Grubb, Willard T., 4,297,169, Cl. 376-418.000.
Hill, Michael S.; and Poff, David A., 4,296,546, Cl. 29-730.000.
Howell, Edward K., 4,297,741, Cl. 361-93.000.
Mullersman, Ferdinand H., 4,297,630, Cl. 320-35.000.
Northup, Robert P.; and Anderson, Robert L., 4,296,670, Cl. 89-43.00R.
Rodenbeck, Philip G.; and Koenig, Fredrick, 4,296,784, Cl. 140-92.200.
Seymour, Raymond K.; and Murphy, Frank H., 4,297,663, Cl. 335-20.000.
Shah, Siddhartha A.; Woodcock, Sidney J.; and Fagan, Robert D., 4,297,072, Cl. 414-684.300.
Smearing, Robert W., 4,297,389, Cl. 427-58.000.
Stark, Charles J., Jr., 4,297,457, Cl. 525-507.000.
Stark, Charles J., Jr., 4,297,458, Cl. 525-507.000.
Stark, Charles J., Jr., 4,297,459, Cl. 525-507.000.
Stevens, Francis J., 4,297,635, Cl. 324-156.000.
Verbicky, John W., 4,297,283, Cl. 260-346.300.
Williams, Frank J., III; and Relles, Howard M., 4,297,474, Cl. 528-170.000.
- General Foods Corporation: See—
Topalian, Harry H.; Wyss, Clement R.; Kenyon, Ralph E.; and Dec, Anthony F., 4,297,379, Cl. 426-565.000.
- General Instrument Corporation: See—
Smith, Kent F., 4,297,598, Cl. 307-355.000.
- General Motors Corporation: See—
Aldrich, Frederic C., 4,296,723, Cl. 123-510.000.
Arndt, Frederick P., 4,296,847, Cl. 192-4.00A.
Baugh, Edward D.; and Hoffman, Mark B., 4,296,718, Cl. 123-198.00D.
Brucken, Byron L., 4,297,085, Cl. 417-222.000.
Kosek, Thomas P.; and Steinhilper, Eric A., 4,296,888, Cl. 239-403.000.
Reider, Samuel B., 4,296,606, Cl. 60-754.000.
Staub, Vincent M., Jr., 4,296,854, Cl. 192-106.100.
- General Tire & Rubber Company, The: See—
Bingham, Robert E.; Durst, Richard R.; Fabris, Hubert J.; Hargis, Ivan G.; Livigni, Russell A.; and Aggarwal, Sundar L., 4,297,240, Cl. 252-431.00R.
- Georgeaux, Andre, to Societe Miniere et Metallurgique de Penarroya. Process for the treatment of solutions of lead chloride. 4,297,183, Cl. 204-117.000.
- Gerber Products Company: See—
Spletzer, Barry L., 4,297,682, Cl. 340-384.00E.
- Gernstein, Terry M.: See—
Epstein, Barry M.; and Gernstein, Terry M., 4,297,534, Cl. 179-90.00D.
- Gholson, Wayne, to Varel Manufacturing Company. Cable tool with circulating drill stem. 4,296,823, Cl. 175-308.000.
- Giacoletto, Glen: See—
Haissig, Bruce E.; Gaines, Jack R.; and Giacoletto, Glen, 4,297,125, Cl. 71-77.000.
- Giacone, Felice: See—
Becchi, Raffaele; Giacone, Felice; and Accattino, Andrea, 4,297,573, Cl. 250-231.0SE.
- Giardini, Dante S., to Ford Motor Company. Arcuate tubular pump. 4,297,089, Cl. 417-437.000.
- Giba-Geigy Corporation: See—
Pfeifer, Josef; and Reinehr, Dieter, 4,297,480, Cl. 528-346.000.
- Gibson, Willie M.: See—
Verable, Diara; and Gibson, Willie M., 4,296,575, Cl. 52-66.000.
- Gidge, Kenneth N.; and Richard, Henry J., to BSL Corporation. Transparent reach-through curtain for open refrigerators. 4,296,792, Cl. 160-332.000.
- Gies, Paul E., to Aeroquip Corporation. Cylinder cushion with contractable ring. 4,296,675, Cl. 91-396.000.
- Giessen, Bill C.; Polk, Donald E.; and Ray, Ranjan, to Marko Materials, Inc. High strength iron, nickel and cobalt base crystalline alloys with ultrafine dispersion of borides and carbides. 4,297,135, Cl. 75-123.00B.
- Gilbert, Allan H.: See—
Furrier, Joseph P.; and Gilbert, Allan H., 4,296,518, Cl. 15-110.000.
- Gilbert, Richard J.; and Rice, Doris M., to Texaco Development Corp. Process for rim elastomers with superior high temperature dimensional stability. 4,297,444, Cl. 521-160.000.
- Gillette, Donald J., to Electrostatic Equipment Corporation. Control grid in electrostatic fluidized bed coater. 4,297,386, Cl. 427-27.000.
- Gist-Brocades N.V.: See—
van der Lugt, Arie, 4,296,769, Cl. 134-68.000.
- Gjelsvik, Norvald; and Hundere, Ingleif, to Elkem-Spigerverket a/s. Method of producing a pure aluminiumoxide from solutions containing dissolved ions of aluminium and iron. 4,297,326, Cl. 423-126.000.
- Gjelsvik, Norvald; Hannestad, Gunnar; Hundere, Ingleif; and Torgersen, Jan H., to Elkem-Spigerverket A/S. Method of precipitation of pure aluminiumchloride from solutions which contain ions of aluminium and magnesium. 4,297,327, Cl. 423-126.000.
- GKN-Stenman AB: See—
Widen, Bo G., 4,296,619, Cl. 70-451.000.
- Glace, William R.: See—
Ibsen, Robert L.; and Glace, William R., 4,297,266, Cl. 260-42.140.
- Glaser, Helmut; and Schick, Ludwig, to Siemens Aktiengesellschaft. Device for monitoring lamp failure in airport navigation lighting. 4,297,632, Cl. 324-51.000.
- Glazov, Vladimir G.: See—
Shlykov, Gennady N.; Zhestkov, Vitaly I.; Tikhonov, Valentin N.; Dyachkov, Vasily M.; Glazov, Vladimir G.; and Krjuk, Timur P., 4,296,528, Cl. 19-255.000.
- Glazunov, Sergei G.: See—
Yasinsky, Konstantin K.; Glazunov, Sergei G.; Ross, Jury N.; and Bykov, Igor D., 4,296,793, Cl. 164-24.000.
- Gliewe, Russell H.: See—
Jaffin, Harry A.; and Gliewe, Russell H., 4,296,565, Cl. 42-1.00T.
- Gmelch, John C. Highway guide post. 4,297,050, Cl. 404-10.000.
- Godard, Pierre; and Billot, Michel, to Saft-Societe des Accumulateurs Fixes et de Traction. Automatic switching arrangement for two batteries which are charged in parallel and discharged in series. 4,297,629, Cl. 320-7.000.
- Goebel, Dan M.; Crow, James T.; and Forrester, A. Theodore, to University of California, The Regents of. High current density cathode structure. 4,297,615, Cl. 315-111.210.
- Goerth, Joachim, to U.S. Philips Corporation. Crystal oscillator including a MOS-capacitor. 4,297,654, Cl. 331-108.00D.
- Goldin, Rodion G.; and Yakimenko, Valentin G. Device for exciting synchronous machine. 4,297,739, Cl. 361-55.000.
- Goldstein, Allan L.; and Low, Teresa L. K., to Hoffman-La Roche Inc. Thymosin beta 3 and beta 4. 4,297,276, Cl. 260-112.50R.
- Good, Maynard: See—
Sidaway, H. John; and Good, Maynard, 4,296,891, Cl. 242-110.000.
- Goodale, Robert H.; and DuJack, George M., Jr. Septum for use in gas chromatography and method of operation. 4,296,634, Cl. 73-864.860.
- Goodall SemiMetallic Hose & Mfg. Co.: See—
Marshall, Don J., 4,297,079, Cl. 416-140.000.

- Goodyear Tire & Rubber Company, The: See—
Roberts, Charles W.; Kolowski, Michael A.; Lindner, Daniel J.; Lynch, John E.; Ruip, Terrence M.; and Fetty, Harold D., 4,296,789, Cl. 152-209.00R.
- Gorbunov, Nikolai M.: See—
Bashnin, Oleg I.; Semenov, Vasily V.; Fedorov, Vasily N.; Gorbunov, Nikolai M.; Rodionov, Evgeny I.; and Sorokin, Nikolai A., 4,297,589, Cl. 290-40.00R.
- Goron, John, to Midland-Ross Corporation. Accumulator head used in the formation of a multi-layer parison. 4,297,092, Cl. 425-133.100.
- Gotman, Alexander, to Presco, Inc. Control of small parts in a manufacturing operation. 4,296,542, Cl. 29-574.000.
- Goto, Hiromi: See—
Kagata, Tooru; and Goto, Hiromi, 4,296,848, Cl. 192-35.000.
- Goto, Jugo; and Saegusa, Takeo, to Takeda Chemical Industries, Ltd. Production of crosslinked polymers using an oxazoline derivative. 4,297,449, Cl. 525-329.000.
- Gottstein, William J.; Kaplan, Murray A.; and Granatek, Alphonse P., to Bristol-Myers Company. 7- α -Amino-substituted acylamino-3-(1-carboxymethyltetrazol-5-ylthiomethyl)-3-cephem-4-carboxylic acids. 4,297,489, Cl. 544-27.000.
- Goudin, Robert, to U.S. Philips Corporation. Support for a transducer for emitting and/or receiving ultrasonic signals in a given angular sector. 4,296,753, Cl. 128-660.000.
- Gould Inc.: See—
Kozacka, Frederick J., 4,297,667, Cl. 337-251.000.
- Graffin, Andre J., to Serac. Method and apparatus for heat-sealing lids on glass containers. 4,297,161, Cl. 156-583.300.
- Graham, Richard H.: See—
Tsai, Shirley C.; Graham, Richard H.; and Oder, Robin R., 4,296,809, Cl. 166-259.000.
- Granatek, Alphonse P.: See—
Gottstein, William J.; Kaplan, Murray A.; and Granatek, Alphonse P., 4,297,489, Cl. 544-27.000.
- Granger, Michel: See—
Crommelynck, Francois; Granger, Michel; Rio, Michel; and Tourdot, Jacques, 4,297,298, Cl. 260-502.00R.
- Gratzmuller, Jean L. Hydraulically controlled safety valve. 4,296,910, Cl. 251-28.000.
- Gray, John C.: See—
Frankel, Milton B.; Arbit, Harry A.; Artz, Glen D.; and Gray, John C., 4,297,152, Cl. 149-88.000.
- Great Lakes Chemical Corporation: See—
Macchiarolo, Nick T.; McGuire, Billy G.; and Scalise, John M., 4,297,224, Cl. 210-755.000.
- Greco, Alberto: See—
Corbellini, Margherita; Greco, Alberto; and Osellame, Mirko, 4,297,462, Cl. 526-125.000.
- Green, David L., to Pacer Systems, Inc. Omnidirectional speed cockpit display. 4,297,673, Cl. 340-27.0NA.
- Greenaway, David L.: See—
Antes, Gregor; and Greenaway, David L., 4,297,001, Cl. 350-129.000.
- Greene, Del F.: See—
Little, Jane; and Greene, Del F., 4,296,677, Cl. 91-510.000.
- Greenley, Henry R.: See—
Jureit, John C.; and Greenley, Henry R., 4,297,048, Cl. 403-189.000.
- Gresch, Heinz: See—
Holter, Heinz; Gresch, Heinz; and Igelbuscher, Heinrich, 4,297,117, Cl. 55-389.000.
- Grewatta Heinz: See—
Wolff, Siegfried; Rothbuhr, Lothar; and Grewatta Heinz, 4,297,145, Cl. 106-308.00Q.
- Griffin, James R.; and Schreck, Raymond M., to General Electric Company. Household refrigerator air flow control and method. 4,296,611, Cl. 62-89.000.
- Grinnell Fire Protection Systems Company, Inc.: See—
Fischer, Michael A., 4,296,816, Cl. 169-37.000.
Mears, James W., 4,296,815, Cl. 169-37.000.
- Griste, Charles R., to Hughes Tool Company. Cable tensioner for a downcrowding device for earth boring machines. 4,296,819, Cl. 173-147.000.
- Grobler, Johannes H. Sealing of leaks in tanks and the like. 4,296,932, Cl. 277-1.000.
- Grohmann, Andreas: See—
Moll, Hans-Georg; Hasselbarth, Ulrich; Grohmann, Andreas; and Marks, Helmut, 4,297,221, Cl. 210-702.000.
- Grolig, Johann: See—
Becker, Robert; Grolig, Johann; and Rasp, Christian, 4,297,501, Cl. 560-24.000.
- Groman, Ernest V.; and Cabelli, Michael D., to Baxter Travenol Laboratories, Inc. Xanthine tracers. 4,297,494, Cl. 544-267.000.
- Gross, Franz; Boehme, Gerit; Wiehler, Wolf; and Bibracher, Wilhelm, to Siemens Aktiengesellschaft. Gas-tight-high-frequency permeable window arrangement in a coaxial line, particularly for traveling wave tubes. 4,297,662, Cl. 333-252.000.
- Grossman, David G.: See—
Beall, George H.; Grossman, David G.; Hoda, Syed N.; and Kubinski, Karen R., 4,297,139, Cl. 501-2.000.
- Grubb, Willard T., to General Electric Company. Nuclear fuel assembly and process. 4,297,168, Cl. 376-418.000.
- Grubb, Willard T., to General Electric Company. Nuclear fuel assembly and process. 4,297,169, Cl. 376-418.000.
- Grumman Aerospace Corporation: See—
Kress, Robert W.; and Bacchi, Anthony C., 4,296,896, Cl. 244-12.400.
- Grummon, Glenn D.: See—
Vitello, John P.; and Grummon, Glenn D., 4,296,785, Cl. 141-105.000.
- Grundmann, Edgard: See—
Bernhardt, Winfried; Grundmann, Edgard; and Kroll, Rudolf, 4,296,732, Cl. 126-426.000.
- Gruner & Jahr AG & Co.: See—
Wangermann, Jochen, 4,296,684, Cl. 100-292.000.
- Gualandi, Paolo. Deodorizing composition for ash trays. 4,297,233, Cl. 252-259.500.
- Guarnaschelli, Claudio. Aerator. 4,297,214, Cl. 210-219.000.
- Gudze, Robert A.: See—
Berkhin, Iosif M.; Gudze, Robert A.; Kekalo, Vasily I.; Panasenko, Nikolai N.; Podbeltsev, Viktor I.; Tsypina, Zinaida D.; and Mukhin, Vladislav N., 4,296,867, Cl. 212-229.000.
- Guex, Woldemar; Klauui, Heinrich; Pauling, Horst; and Voirel, Felix. Reusable heat devices containing xylitol as the heat-storage material. 4,296,801, Cl. 165-104.170.
- Guigues, Francois; and Trinh, Stephane, to Rhone Poulenc Agrochimie. 2-Phenyl-4-pyrone derivatives, their preparation and their use as fungicides. 4,297,367, Cl. 424-283.000.
- Guiler, Richard S., to E. J. Brooks Company. Adaptor for plunger lock operating tool. 4,296,616, Cl. 70-34.000.
- Guiraud, Francois, to Fichet-Bauche. Lock and key device. 4,296,618, Cl. 70-358.000.
- Gulbins, Erich: See—
Schenck, Hans-Uwe; and Gulbins, Erich, 4,297,255, Cl. 260-18.0PF.
- Gulf Research & Development Company: See—
Tsai, Shirley C.; Graham, Richard H.; and Oder, Robin R., 4,296,809, Cl. 166-259.000.
Wu, Ching-Yong; Pretzer, Wayne R.; and Kobylinski, Thaddeus P., 4,297,518, Cl. 568-385.000.
- Gupta, Tapan K.; and Pietsch, Herbert E., to Westinghouse Electric Corp. Method of producing homogeneous ZnO non-linear powder compositions. 4,297,250, Cl. 252-518.000.
- Gutehoffnungshutte Sterkrade A.G.: See—
von Petery, Curt, 4,297,083, Cl. 417-53.000.
- Guth, Christian: See—
Kern, Jorg; and Guth, Christian, 4,297,400, Cl. 427-389.000.
- Guthlein, Werner; Wielinger, Hans; Rittersdorf, Walter; and Werner, Wolfgang, to Boehringer Mannheim GmbH. Guaiconic acid A from guaiaic resin. 4,297,271, Cl. 260-107.000.
- H. Berthold Aktiengesellschaft: See—
Hornberg, Harald; Trotzek, Gunter; and Hahnefeld, Fedor, 4,297,044, Cl. 400-473.000.
- H. H. Robertson Company: See—
Fork, Frank W., 4,297,524, Cl. 174-48.000.
- Haack, Dennis A., to Denack Design Corporation. Structural component for upholstered furniture and method of making. 4,296,964, Cl. 297-218.000.
- Haas, David J.: See—
Juner, Adolph; and Haas, David J., 4,297,580, Cl. 250-368.000.
- Haas, Georges; Jaeggi, Knut A.; Rossi, Alberto; and Sele, Alex, to Ciba-Geigy Corporation. Novel 4,7-phenanthroline derivatives and pharmaceutical compositions containing them and their use. 4,297,358, Cl. 424-256.000.
- Haasi, Michael J.; Pratt, Paul D.; Chen, Rocky W.; and Fett, Helen M., to Pillsbury Company, The. Refrigerated shelf stable pie crust dough. 4,297,378, Cl. 426-532.000.
- Hacker, Kurt: See—
Dokoupil, Jiri; and Hacker, Kurt, 4,296,514, Cl. 12-142.00R.
- Haeussler, Ernst. Apparatus for forming recess around a pickup bolt of a concrete body. 4,296,909, Cl. 249-94.000.
- Hafner-Milac, Natasa: See—
Suhac, Peter; Hafner-Milac, Natasa; and Dolenc, Bozidar, 4,297,293, Cl. 260-448.00B.
- Haga, Ryooichi: See—
Ishida, Masahiko; Haga, Ryooichi; and Odawara, Youji, 4,297,216, Cl. 210-613.000.
- Hagberg, John E., to Westinghouse Electric Corp. Protective relaying apparatus. 4,297,740, Cl. 361-67.000.
- Hahnefeld, Fedor: See—
Hornberg, Harald; Trotzek, Gunter; and Hahnefeld, Fedor, 4,297,044, Cl. 400-473.000.
- Hahnkamm, Volker: See—
Buxbaum, Gunter; Schopper, Heinrich-Christian; Leitner, Lutz; and Hahnkamm, Volker, 4,297,395, Cl. 427-127.000.
- Haissig, Bruce E.; Gaines, Jack R.; and Giacoletto, Glen, to United States of America, Agriculture. Tree rooting using synthetic auxins. 4,297,125, Cl. 71-77.000.
- Hakansson, Bo H.: See—
Carlsson, Per-Olov A. V.; and Hakansson, Bo H., 4,296,760, Cl. 128-788.000.
- Hakansson, Hakan B.; Persson, Lennart P. E.; and Wall, Berth-Ove G., to Gambro AB. Device for temperature measurement. 4,296,633, Cl. 73-362.0AR.
- Hakoi, Tsutomu, to Yoshida Kogyo K.K. Apparatus for loading a pull tab on a slider body. 4,296,547, Cl. 29-766.000.
- Hale, Steven D.: See—
Fowler, James C.; Hale, Steven D.; and Moser, Theodore E., 4,297,699, Cl. 343-5.0NA.
- Hales, Marwood J.; and Thorpe, Cameron L. Apparatus for extracting energy from water waves. 4,296,602, Cl. 60-398.000.

- Halford, David W.; Price, Frank C.; and Bosworth, George H., to USM Corporation. Seat and waist lasting machine-independently pivotable side lasting fingers. 4,296,513, Cl. 12-12.000.
- Halliburton Company: See—
Hendrickson, James D.; and White, Pat M., 4,296,807, Cl. 166-184.000.
- Smith, Harry D., Jr.; Arnold, Dan M.; and Smith, Kenneth J., 4,297,575, Cl. 250-265.000.
- Halliburton Services: See—
Baker, Eugene E.; and Carter, Ernest E., Jr., 4,296,808, Cl. 166-191.000.
- Hamamoto, Nobuo: See—
Moriya, Shigeru; Hamamoto, Nobuo; Ichino, Kazuo; and Ozawa, Kanji, 4,297,676, Cl. 340-146.3AG.
- Hamane, Tokuhito; Kinoshita, Toshio; and Kihira, Masafumi, to Matsushita Electric Industrial Co., Ltd. Method of and apparatus for fabricating stator assemblies of electrical machines. 4,296,543, Cl. 29-596.000.
- Hamar, Martin R. Apparatus and process for sweeping a flat optical light plane. 4,297,031, Cl. 356-247.000.
- Hammann, Ingeborg: See—
Fuchs, Rainer; Hammann, Ingeborg; Homeyer, Bernhard; Behrenz, Wolfgang; and Stendel, Wilhelm, 4,297,366, Cl. 424-274.000.
- Hammar, Jan E., to Forenade Fabriksverken. Method and apparatus for cleaning a continuous web of material. 4,296,767, Cl. 134-15.000.
- Hammerstrom, Everett A. Tape measure and marking device. 4,296,554, Cl. 33-138.000.
- Hanawa, Kazuhiko: See—
Fukuda, Takeo; Hanawa, Kazuhiko; Urui, Kiyoshi; and Haseyama, Michiko, 4,297,532, Cl. 179-18.0AB.
- Hancor, Inc.: See—
Sidaway, H. John; and Good, Maynard, 4,296,891, Cl. 242-110.000.
- Handa, Noritoshi, to Nissan Motor Company, Limited. Rubbing-contact sealing structure for rotary heat regenerator. 4,296,937, Cl. 277-88.000.
- Handler, Michael D.: See—
Mason, Stanley I., Jr.; and Handler, Michael D., 4,296,746, Cl. 128-201.150.
- Hannah, Stephen J.; and Livingstone, Bryan, to National Research Development Corporation. Surface passivation of compound semiconductors. 4,297,176, Cl. 204-37.00R.
- Hannaht, David J., to University of Surrey, a part interest. Manufacture of articles from an organic material and a water-hardenable mass. 4,297,409, Cl. 428-247.000.
- Hannestad, Gunnar: See—
Gjelsvik, Norvald; Hannestad, Gunnar; Hundere, Ingleif; and Torgersen, Jan H., 4,297,327, Cl. 423-126.000.
- Haraikawa, Tetsuo: See—
Tamura, Koichi; and Haraikawa, Tetsuo, 4,296,844, Cl. 188-73.380.
- Harder, Willard J., to Bethany Fellowship, Inc. Solar energy collecting panel assembly. 4,296,741, Cl. 126-449.000.
- Hardesty, Thomas K. C., to United States of America, Navy. Rotary locking mechanism. 4,296,689, Cl. 102-260.000.
- Harding, Steven R.: See—
Bach, Paul S.; Harding, Steven R.; Lamos, Richard A.; Markham, Harvey R.; and Shepherd, Roger D., 4,297,025, Cl. 355-14.0SH.
- Hardwick, Martha K.: See—
Buck, Gordon H.; and Hardwick, Martha K., 4,296,926, Cl. 273-86.00R.
- Hargis, Ivan G.: See—
Bingham, Robert E.; Durst, Richard R.; Fabris, Hubert J.; Hargis, Ivan G.; Livigni, Russell A.; and Aggarwal, Sundar L., 4,297,240, Cl. 252-431.00R.
- Harima, Hiroshi: See—
Kasai, Goro; Takechi, Sanjuro; and Harima, Hiroshi, 4,297,315, Cl. 264-322.000.
- Harney, David L.; and Young, Harlow S., to Chef-Reddy Foods Corporation. Method of making French fryable frozen potato strips. 4,297,377, Cl. 426-438.000.
- Harris Corporation: See—
Pan, Jing-Jong, 4,297,656, Cl. 331-135.000.
- Harshman, Ronald W.; and Dietrich, Lynn A., to Walter Kidde & Company, Inc. Hydraulic selector valve having joy stick control. 4,296,773, Cl. 137-312.000.
- Hart, Dale H., to Hi Shear Corporation. Telescoping self-retaining safety bolt assembly. 4,297,063, Cl. 411-199.000.
- Hartley, Bobby G. Recycling centrifuge for the reduction of viscosity and gel strength of drilling fluids. 4,297,225, Cl. 210-779.000.
- Hartwell, Charles A. Segmented hardfaced collar for tool joints. 4,296,973, Cl. 308-4.00A.
- Hasegawa, Tsunao: See—
Kadowaki, Hidetaka; Inomata, Akira; Yanagida, Kiyoshi; Hasegawa, Tsunao; Ishii, Satoshi; and Ohtake, Yasushi, 4,297,730, Cl. 360-66.000.
- Haseler, Helmut; Meckl, Heinz; Lohmer, Karl; and Pelz, Willibald, to AGFA-Gevaert Aktiengesellschaft. Color-photographic development process. 4,297,438, Cl. 430-377.000.
- Haseyama, Michiko: See—
Fukuda, Takeo; Hanawa, Kazuhiko; Urui, Kiyoshi; and Haseyama, Michiko, 4,297,532, Cl. 179-18.0AB.
- Hashimoto, Kazuyuki: See—
Ebisawa, Kiyohito; Hisabayashi, Satoshi; Koike, Toshio; and Hashimoto, Kazuyuki, 4,297,024, Cl. 355-14.00E.
- Hashimoto, Mitsuru: See—
Sakai, Kiyoshi; Hashimoto, Mitsuru; and Kawakami, Tomiko, 4,297,426, Cl. 430-59.000.
- Hashimoto, Sadakatsu, to Sharp Kabushiki Kaisha. Color uniforming drive in an electrochromic display device. 4,297,696, Cl. 340-785.000.
- Hashimoto, Shunichi: See—
Sanemitsu, Yuzuru; Mizutani, Masato; Sumida, Seizo; Katoh, Haruhiko; Oshio, Hiromichi; and Hashimoto, Shunichi, 4,297,129, Cl. 71-93.000.
- Hashimoto, Tamotu: See—
Takizawa, Hiroshi; Enomoto, Yutaka; Oiji, Yoshimasa; Hirayama, Tatsuyuki; and Hashimoto, Tamotu, 4,297,369, Cl. 424-285.000.
- Hashimoto, Tutomu: See—
Fujimaki, Kiyoshi; Bando, Yoshiaki; Okuyama, Takesi; and Hashimoto, Tutomu, 4,296,954, Cl. 285-331.000.
- Hashizume, Kiyozo: See—
Tani, Tatsuo; Nagahara, Yasumori; Ohta, Sakae; Suzuki, Minoru; and Hashizume, Kiyozo, 4,297,021, Cl. 355-3.00R.
- Hasselbarth, Ulrich: See—
Moll, Hans-Georg; Hasselbarth, Ulrich; Grohmann, Andreas; and Marks, Helmut, 4,297,221, Cl. 210-702.000.
- Haszbacka, Albin A. Electro-optical level. 4,297,588, Cl. 250-577.000.
- Haupt, Heinz: See—
Bohn, Hans; and Haupt, Heinz, 4,297,274, Cl. 260-112.00B.
- Hauser, John. Fastening of shoe uppers for lasting. 4,296,515, Cl. 12-142.0LC.
- Hauser, Raimund: See—
Freudenschuss, Otto, 4,297,732, Cl. 360-72.100.
- Havlik, Patrick J. C.: See—
Monties, Jean R.; and Havlik, Patrick J. C., 4,296,500, Cl. 3-1.700.
- Hayashi, Hideo: See—
Sato, Hisatake; Makino, Masaharu; and Hayashi, Hideo, 4,297,450, Cl. 525-333.000.
- Hayashi, Izu; and Yonezu, Hiroo, to Nippon Electric Co., Ltd. Injection-type semiconductor laser. 4,297,652, Cl. 331-94.50H.
- Hayashi, Mitsuo: See—
Fujii, Tadashi; Sato, Shuzo; Muto, Naoki; Hayashi, Mitsuo; Kodama, Akira; and Otani, Masaru, 4,297,486, Cl. 536-17.00R.
- Hayashi, Shigeyuki: See—
Sada, Kenzo; and Hayashi, Shigeyuki, 4,296,644, Cl. 74-606.00R.
- Hayashi, Takayuki: See—
Hoshi, Yoshiyuki; Hayashi, Takayuki; and Kakimi, Fujio, 4,297,235, Cl. 252-316.000.
- Hayashi, Yoshihiro, to Aikoh Co., Ltd. Lance pipe for refining and method of making the same. 4,296,921, Cl. 266-270.000.
- Hayes, Frederick: See—
Steynor, James H.; and Hayes, Frederick, 4,297,729, Cl. 360-40.000.
- Health Innovations, Inc.: See—
Anzaldua, Alfred B.; Anzaldua, David A.; and Sturgeon, Benjamin R., 4,296,924, Cl. 272-117.000.
- Heckelsberg, Robert E., to AMCA International Corporation. Roofing structure. 4,296,581, Cl. 52-520.000.
- Heckmann, Klaus: See—
Dobias, Bohuslav; and Heckmann, Klaus, 4,297,159, Cl. 156-307.700.
- Hedges, Rhey W., to Parker, Louis W. Energy economizer for induction motors. 4,297,628, Cl. 318-798.000.
- Hehemann, Gunter. Stereo headset. 4,297,535, Cl. 179-156.00R.
- Heilmann, Kurt: See—
Krug, Hans; and Heilmann, Kurt, 4,297,416, Cl. 428-576.000.
- Heimbold, Richard L.: See—
Donham, Robert E.; and Heimbold, Richard L., 4,297,076, Cl. 416-37.000.
- Heimbürger, Norbert: See—
Schwinn, Horst; Heimbürger, Norbert; Kumpe, Gerhardt; and Herchenhan, Bernd, 4,297,344, Cl. 424-101.000.
- Hein, Lehmann AG: See—
Altmeyer, Hans J.; and Gebel, Josef, 4,297,215, Cl. 210-386.000.
- Heinrich Wunder KG: See—
Zoor, Reinhold, 4,296,615, Cl. 70-19.000.
- Heiss, Herbert L., to Mobay Chemical Corporation. Method of producing color stable thermoplastic polymethanes and products made thereby. 4,297,472, Cl. 528-84.000.
- Heitzman, Gary N.; Hutchings, Clay L.; Knepp, Gary L.; and Miller, Robert G., to Caterpillar Tractor Co. Engine and fuel shutdown control. 4,297,742, Cl. 361-154.000.
- Helbig, Rolf W. Rack hanging device for garments. 4,296,959, Cl. 294-143.000.
- Helger, Roland: See—
Vormbrock, Rolf; and Helger, Roland, 4,297,238, Cl. 252-408.000.
- Helwerth, Rainer: See—
Diery, Helmut; Helwerth, Rainer; Frohlich, Horst; and Lorke, Horst, 4,297,236, Cl. 252-389.00R.
- Hendricks, Udo-Winfried; and Wollny, Klaus, to Bayer Aktiengesellschaft. Process for the continuous one-bath dyeing of pile fabrics made of polyacrylonitrile/cotton. 4,297,103, Cl. 8-534.000.
- Hendrickson, James D.; and White, Pat M., to Halliburton Company. Crossover tool. 4,296,807, Cl. 166-184.000.
- Hennig, Ewald M. C.; and Nicol, Klaus. Method for determining the value of cardiologic quantities and apparatus for performing said method. 4,296,754, Cl. 128-694.000.
- Henrick, Clive A.; Labovitz, Jeffrey N.; Fox, Roland T. V.; Rathmell, William G.; and Shephard, Margaret C., to Zococon Corp.; and Imperial Chemical Industries Limited. α -Cyano- β -(substituted-anilino)-N-ethoxycarbonylacrylamide intermediates. 4,297,297, Cl. 260-465.00D.
- Henriques, Lance, to Angleman, John D. Rangefinder using expanded time delay. 4,297,701, Cl. 343-6.5LC.

- Hensley, Albert L., Jr.; and Quick, Leonard M., to Standard Oil Company (Indiana). Process for demetallation and desulfurization of heavy hydrocarbons. 4,297,242, Cl. 252-439.000.
- Herbert, Hugh G. Folding bicycle. 4,296,940, Cl. 280-278.000.
- Herchenhan, Bernd: See—
Schwinn, Horst; Heimbürger, Norbert; Kumpe, Gerhardt; and Herchenhan, Bernd, 4,297,344, Cl. 424-101.000.
- Hercules Incorporated: See—
Jolly, Jennings L.; and Roos, Leo, 4,297,435, Cl. 430-270.000.
- Leardi, Anthony, 4,296,503, Cl. 4-228.000.
- Herman, Seymour S., to Stan Herman Studio, Inc. Hospital patient gown. 4,296,497, Cl. 2-114.000.
- Hermann Rappold & Co. GmbH: See—
Muller, Rudolf; Lengsfeld, Franz; and Uerlich, Johannes, 4,296,776, Cl. 137-340.000.
- Herrmann, Hans-Joachim; Meyer, Gunther; and Steffen, Klaus-Dieter, to Dynamit Nobel Aktiengesellschaft. Aromatic bisazomethines, a method for their preparation, and their use as reactive pigments. 4,297,502, Cl. 560-35.000.
- Herrmann, Henry O., Jr., to AMP Incorporated. High voltage hermetically sealed connector. 4,296,986, Cl. 339-89.00C.
- Herrmann, Walter: See—
Krabetz, Richard; Herrmann, Walter; Engelbach, Heinz; Palm, Peter; Sommer, Karl; and Spahn, Heinrich, 4,297,247, Cl. 252-468.000.
- Herzner, Karl H., to U.S. Philips Corporation. Apparatus for receiving storing and outputting digital signal sequences. 4,297,567, Cl. 235-92.0PB.
- Heshmat, Hooshang, to Mechanical Technology Incorporated. Cross-plies support element for compliant bearings. 4,296,976, Cl. 308-9.000.
- Heslep, Curtis A.: See—
Robertson, Kenneth L.; and Heslep, Curtis A., 4,296,708, Cl. 118-233.000.
- Heurteux, Bernard M., to Shur-Lok International, S.A. Fastening device for a honeycombed panel employed in particular in aeronautic structures. 4,296,586, Cl. 52-787.000.
- Hewitt, Harvey J., to Xerox Corporation. Overcoated photoreceptor containing gold injecting layer. 4,297,424, Cl. 430-58.000.
- Heymes, Rene; and Lutz, Andre, to Roussel Uclaf. Novel oximes. 4,297,352, Cl. 424-246.000.
- Hi Shear Corporation: See—
Hart, Dale H., 4,297,063, Cl. 411-199.000.
- Hicke, David W., to Reagent Chemical and Research, Inc. Method of manufacturing cartridge cases. 4,296,536, Cl. 29-1.300.
- Hiesinger, Edwin; Keplinger, Klaus; and Nessler, Hermann, to Inkomag. Filtering apparatus. 4,297,211, Cl. 210-136.000.
- Higashi, Akio; Kawaziri, Kazuhiro; and Nakajima, Yosuke, to Fuji Photo Film Co., Ltd. High frequency sputtering produces thin film amorphous silicon photoconductor. 4,297,392, Cl. 427-75.000.
- Higuchi, Kosuke: See—
Kawaguchi, Yoshihiro; Higuchi, Kosuke; and Kitajima, Yoshiro, 4,297,553, Cl. 200-145.000.
- Hijkata, Kazuo, to Olympus Optical Company Limited. Specimen applicator. 4,297,199, Cl. 204-299.00R.
- Hikuma, Motohiko; Kubo, Tatsuru; Yasuda, Takeo; Karube, Isao; and Suzuki, Shuichi, to Ajinomoto Company, Incorporated. Method for determining ammonia and sensor therefor. 4,297,173, Cl. 204-1.00T.
- Hildebrandt, Norbert; Becker, Norbert; Walter, Rolf; and Hoffman, Manfred. Desk with a channel for receiving cables, wires etc. 4,296,981, Cl. 312-194.000.
- Hill, Michael S.; and Poff, David A., to General Electric Company. Apparatus for assembling electrochemical cell. 4,296,546, Cl. 29-730.000.
- Hinatase, Fumio: See—
Takahashi, Koichi; Hinatase, Fumio; and Shibana, Akira, 4,296,719, Cl. 123-198.00F.
- Hines, David A.; and Bolton, David H., to Imperial Chemical Industries Limited. Treatment of wastewater. 4,297,217, Cl. 210-621.000.
- Hinson, Virgil H.: See—
Jarman, Davis R.; and Hinson, Virgil H., 4,296,626, Cl. 72-392.000.
- Hirabayashi, Shigeto: See—
Kaneko, Yutaka; Hirabayashi, Shigeto; Kawakatsu, Satoshi; and Ninomiya, Hidetaka, 4,297,437, Cl. 430-376.000.
- Kaneko, Yutaka; Kawakatsu, Satoshi; Hirabayashi, Shigeto; and Ninomiya, Hidetaka, 4,297,441, Cl. 430-543.000.
- Hirai, Kentaro; Matsutani, Shigeru; Ishiba, Teruyuki; and Makino, Itsuo, to Shionogi & Co., Ltd. 4,1-Benzoxazepines. 4,297,280, Cl. 260-245.500.
- Hirao, Tsuneo; and Onishi, Masao, to Matsushita Electric Industrial Co., Ltd. High-voltage generating device. 4,297,609, Cl. 310-339.000.
- Hirayama, Kazuhiro; and Sugiura, Susumu, to Canon Kabushiki Kaisha. Recording apparatus including a continuous transfer web. 4,297,716, Cl. 346-153.100.
- Hirayama, Tatsuyuki: See—
Takizawa, Hiroshi; Enomoto, Yutaka; Oiji, Yoshimasa; Hirayama, Tatsuyuki; and Hashimoto, Tamotu, 4,297,369, Cl. 424-285.000.
- Hirmann, Georg: See—
Kagi, Bruno; Hirmann, Georg; and Luginbuhl, Rolf, 4,296,774, Cl. 137-322.000.
- Kagi, Bruno; Hirmann, Georg; and Luginbuhl, Rolf, 4,296,775, Cl. 137-322.000.
- Hirschberger, August: See—
Jardin, Hans; and Hirschberger, August, 4,296,962, Cl. 296-217.000.
- Hirschle, George W.: See—
Taylor, Edward S.; and Hirschle, George W., 4,296,713, Cl. 122-32.000.
- Hisabayashi, Satoshi: See—
Ebisawa, Kiyohito; Hisabayashi, Satoshi; Koike, Toshio; and Hashimoto, Kazuyuki, 4,297,024, Cl. 355-14.00E.
- Hisaka Works, Ltd.: See—
Sumitomo, Hiroyuki, 4,296,803, Cl. 165-110.000.
- Hitachi Chemical Co., Ltd.: See—
Kahara, Toshiki; Tamura, Kohki; Ebata, Noboru; Sato, Fumio; and Yoshida, Tomio, 4,297,231, Cl. 252-182.100.
- Koyama, Tohru; Narahara, Toshikazu; and Aimon, Yuji, 4,297,471, Cl. 526-328.000.
- Hitachi Denshi Kabushiki Kaisha: See—
Kodama, Kazuyuki; Okada, Kunihiro; Endoh, Takeyuki; and Shibuya, Yasutaka, 4,297,691, Cl. 340-723.000.
- Hitachi, Ltd.: See—
Furuhashi, Toshio; and Abe, Osamu, 4,296,722, Cl. 123-492.000.
- Inouye, Hiroshi, 4,296,935, Cl. 277-81.00R.
- Ishibashi, Yoichi; Uchiyama, Yoshihiro; Akimoto, Hidetoshi; and Sakaki, Makoto, 4,297,319, Cl. 422-114.000.
- Ishida, Masahiko; Haga, Ryooichi; and Odawara, Youji, 4,297,216, Cl. 210-613.000.
- Kahara, Toshiki; Tamura, Kohki; Ebata, Noboru; Sato, Fumio; and Yoshida, Tomio, 4,297,231, Cl. 252-182.100.
- Kodama, Kazuyuki; Okada, Kunihiro; Endoh, Takeyuki; and Shibuya, Yasutaka, 4,297,691, Cl. 340-723.000.
- Moriya, Shigeru; Hamamoto, Nobuo; Ichino, Kazuo; and Ozawa, Kanji, 4,297,676, Cl. 340-146.3AG.
- Onda, Kenichi; Tashiro, Sadaji; and Amano, Hisao, 4,297,594, Cl. 307-252.00C.
- Tadauchi, Masaharu; Sato, Kunio; and Tanno, Kiyohiko, 4,297,715, Cl. 346-150.000.
- Wada, Takeshi; Kominami, Yasuo; Miyamoto, Yukihiro; and Yamada, Tsuneo, 4,297,601, Cl. 307-555.000.
- Hitachi Metals, Ltd.: See—
Onda, Kenichi; Tashiro, Sadaji; and Amano, Hisao, 4,297,594, Cl. 307-252.00C.
- Ho, Kok-Kit, to Timex Corporation. Clasp for watch strap. 4,296,532, Cl. 24-206.00R.
- Hoda, Syed N.: See—
Beall, George H.; Grossman, David G.; Hoda, Syed N.; and Kubinski, Karen R., 4,297,139, Cl. 501-2.000.
- Hodges, Everett L. Hydraulic mining tool apparatus. 4,296,970, Cl. 299-67.000.
- Hoechst Aktiengesellschaft: See—
Diery, Helmut; Helwerth, Rainer; Frohlich, Horst; and Lorke, Horst, 4,297,236, Cl. 252-389.00R.
- Tetzlaff, Karl-Heinz; Riemenschneider, Wilhelm; and Leuschner, Gunter, 4,297,323, Cl. 422-208.000.
- Uhrig, Heinz; and Deubel, Reinhold, 4,297,270, Cl. 260-104.000.
- von der Eltz, Hans-Ulrich; Lehman, Armand; Lehmann, Joachim W.; and Maier, Hans-Peter, 4,297,101, Cl. 8-531.000.
- Hoenninger, John C., III: See—
Crooks, Lawrence E.; Hoenninger, John C., III; and Arakawa, Mitsuaki, 4,297,637, Cl. 324-309.000.
- Hofbauer, Peter; Willmann, Michael; and Wundrak, Egon, to Volkswagenwerk Aktiengesellschaft. Internal combustion engine for an automobile with a divided oil pan. 4,296,716, Cl. 123-195.00C.
- Hoffken, Erich; Kleine-Kleffmann, Werner; Bertram, Rolf; Abele, Karl-Heinz; and Michalski, Gunter, to Thyssen Aktiengesellschaft vormals August Thyssen-Hütte. Method for dividing a strand into slabs. 4,297,151, Cl. 148-9.00R.
- Hoffman-La Roche Inc.: See—
Goldstein, Allan L.; and Low, Teresa L. K., 4,297,276, Cl. 260-112.50R.
- Hoffman, Manfred: See—
Hildebrandt, Norbert; Becker, Norbert; Walter, Rolf; and Hoffman, Manfred, 4,296,981, Cl. 312-194.000.
- Hoffman, Mark B.: See—
Baugh, Edward D.; and Hoffman, Mark B., 4,296,718, Cl. 123-198.00D.
- Hoffmann, Jean-Claude; Castanie, Francis; Crabere, Henri; Verdier, Jean-Pierre; and Voisin, Norbert, to Societe Nationale Industrielle Aerospatiale. Process and device for multiplying a stochastic value by a coefficient greater than the unit. 4,297,744, Cl. 364-703.000.
- Hoffmann, Ralph M., to Trochoid Power Corporation. Rotary expansion power unit with valve disc connected to crankshaft. 4,297,090, Cl. 418-61.00A.
- Hofmann, Heinrich; and Markfelder, Gunther, to Fag Kugelfischer Georg Schafer & Co. Journal bearing for the shaft of a water pump or the like. 4,296,979, Cl. 308-174.000.
- Hofmann, Karl, to Robert Bosch GmbH. Heat protected fuel injection plug for internal combustion engines. 4,296,887, Cl. 239-397.500.
- Hofstetter, Robert A. Energy saving pots, pans and adapter. 4,296,728, Cl. 126-376.000.
- Holscher & Leuschner GmbH & Co.: See—
Holscher, Werner, 4,296,918, Cl. 256-68.000.
- Holscher, Werner, to Holscher & Leuschner GmbH & Co. Animal pen post. 4,296,918, Cl. 256-68.000.
- Holset Engineering Company Limited: See—
Atkin, Howard S., 4,296,934, Cl. 277-81.00R.
- Holter, Heinz; Gresch, Heinz; and Igelbuscher, Heinrich, to Industrie-Wert Beteiligungsgesellschaft mbH. Respiratory device for catastrophic fires and/or smog weather conditions. 4,297,117, Cl. 55-389.000.
- Homeyer, Bernhard: See—
Fuchs, Rainer; Hammann, Ingeborg; Homeyer, Bernhard; Behrenz, Wolfgang; and Stendel, Wilhelm, 4,297,366, Cl. 424-274.000.

- Honda Giken Kogyo Kabushiki Kaisha: See—
Sato, Makoto; Takamatsu, Hiroshi; Miyagawa, Yoshitaka; and Fujii, Etsuo, 4,296,972, Cl. 303-119.000.
- Honda, Hiroyuki; and Ura, Hiroaki, to Konishiroku Photo Industry Co., Ltd. Cleaning apparatus for copy machines. 4,297,026, Cl. 355-15.000.
- Honeywell Inc.: See—
Butter, Charles D., 4,297,684, Cl. 340-557.000.
- Honig, Ernst-August: See—
Oberpichler, Gerd; and Honig, Ernst-August, 4,296,652, Cl. 74-868.000.
- Hooker Chemicals & Plastics Corp.: See—
Lazarz, Christine A.; and Cook, Edward H., Jr., 4,297,196, Cl. 204-296.000.
- Horholt, Anders; and Kvist, Ulrik. Joining member. 4,296,524, Cl. 16-150.000.
- Horman, Ian; and Cazenave, Paul, to Societe d'Assistance Technique pour Produits Nestle S.A. Tea flavoring process and product. 4,297,380, Cl. 426-597.000.
- Hornberg, Harald; Trotzek, Gunter; and Hahnefeld, Fedor, to H. Berthold Aktiengesellschaft. Additional attachment for all types of key operated machines. 4,297,044, Cl. 400-473.000.
- Horowitz, Carl; and Dichter, Michael, to Polymer Research Corp. of America. Desulfurization of coal. 4,297,108, Cl. 44-1.0SR.
- Horton, Herbert D.: See—
Keast, Larry G.; and Horton, Herbert D., 4,296,842, Cl. 188-61.000.
- Horvath, Joseph. Profile grinding apparatus. 4,296,571, Cl. 51-32.000.
- Hosaka, Dennis B., to Stauffer Chemical Company. Process for drying compositions containing derived protein-containing compositions and additives. 4,297,382, Cl. 426-656.000.
- Hoshi, Yoshiyuki; Hayashi, Takayuki; and Kakimi, Fujio, to Fuji Photo Film Co., Ltd. Method of preparing a microcapsule dispersion. 4,297,235, Cl. 252-316.000.
- Hoshino, Kunihisa: See—
Utagawa, Ken; Hoshino, Kunihisa; Shirasu, Hiroshi; and Ogawara, Akira, 4,297,571, Cl. 250-201.000.
- Hotchkiss, Lloyd C.: See—
Karol, James J.; Normann, Richard W.; and Hotchkiss, Lloyd C., 4,296,985, Cl. 339-48.000.
- Housman, Richard J., to Westinghouse Air Brake Company. Housing for draft gear. 4,296,868, Cl. 213-50.000.
- Hoval Interliz AG: See—
Vogt, Alfred, 4,296,712, Cl. 122-22.000.
- Howarth, Thomas T., to Beecham Group Limited. Antibacterial agents. 4,297,345, Cl. 424-114.000.
- Howell, Edward K., to General Electric Company. Rate sensing instantaneous trip mode network. 4,297,741, Cl. 361-93.000.
- Howell, Stephen L., to Kimball International, Inc. Fill note generator for electronic organ. 4,296,665, Cl. 84-1.030.
- Hoyer, Ernst H. J. Ball valve. 4,296,913, Cl. 251-76.000.
- Hsu, Fu-Tong; and Kantz, John F., to Union Carbide Corporation. Bulk material box. 4,296,860, Cl. 206-386.000.
- Hsu, Sheng T., to RCA Corporation. Electrically programmable control gate injected floating gate solid state memory transistor and method of making same. 4,297,719, Cl. 357-23.000.
- Huck, William V., to Minnesota Mining and Manufacturing Company. Protective band for photosensitive film on spools. 4,296,857, Cl. 206-53.000.
- Hudson Products Corporation: See—
Larinoff, Michael W., 4,296,802, Cl. 165-110.000.
- Huellwegen, Josef, to Nixdorf Computer AG. Signal regenerating circuit with improved input-output isolation. 4,297,595, Cl. 307-268.000.
- Hughes Aircraft Company: See—
Marom, Emanuel; Barnoski, Michael K.; and Abrams, Richard L., 4,297,704, Cl. 343-113.00R.
- Wurtz, Howard P.; and Peterson, Eugene W., 4,297,082, Cl. 417-51.000.
- Hughes, Donald W. K.; and Myers, Ronald W., to AMP Incorporated. Electrical connector receptacle. 4,296,991, Cl. 339-176.0MP.
- Hughes, Eugene M., to British Petroleum Company Limited, The. Anchor. 4,296,706, Cl. 114-294.000.
- Hughes Tool Company: See—
Gristle, Charles R., 4,296,819, Cl. 173-147.000.
- Kennington, Kerry S., 4,296,824, Cl. 175-340.000.
- Hull, Michael N.: See—
Turillon, Pierre P.; Hull, Michael N.; and Nordblom, George F., 4,297,421, Cl. 429-225.000.
- Hundere, Ingleif: See—
Gjelsvik, Norvald; and Hundere, Ingleif, 4,297,326, Cl. 423-126.000.
- Gjelsvik, Norvald; Hannestad, Gunnar; Hundere, Ingleif; and Torgersen, Jan H., 4,297,327, Cl. 423-126.000.
- Hunt, Keith R.; and Fisher, Sidney E., to Britax Weathershields Limited. Opening roofs for vehicles. 4,296,961, Cl. 296-216.000.
- Hunter, Walter D., to Texaco Development Corp. Process for secondary recovery. 4,297,226, Cl. 252-8.55D.
- Hunter, Walter D., to Texaco Development Corp. Bipolymer of vinyl sulfonic acid-glycidol adduct and acrylamide. 4,297,469, Cl. 526-287.000.
- Hussmann, Eckart, to JENAer Glaswerk Schott & Gen. Flat solar energy collector with low heat contact between absorber and edge of collector. 4,296,742, Cl. 126-450.000.
- Hutchings, Clay L.: See—
Heitzman, Gary N.; Hutchings, Clay L.; Knepp, Gary L., and Miller, Robert G., 4,297,742, Cl. 361-154.000.
- Hutchins, Alma A., to Hutchins Manufacturing Co. Vacuum cleaner having bag cleaning apparatus. 4,297,114, Cl. 55-299.000.
- Hutchins Manufacturing Co.: See—
Hutchins, Alma A., 4,297,114, Cl. 55-299.000.
- Hutchins, Ned M.: See—
Ricketts, Thomas E.; Hutchins, Ned M.; and Studebaker, Irving G., 4,296,968, Cl. 299-2.000.
- Hutchison, Joseph A., to Solar Kinetics, Inc. Solar collector module. 4,297,003, Cl. 350-292.000.
- Hydell, Robert C.: See—
Spatz, Sydney M.; Hydell, Robert C.; and Davis, Gerald T., 4,296,947, Cl. 282-27.500.
- Ibsen, Robert L.; and Glace, William R., to Den-Mat, Inc. Microfilled dental composite and method using the same. 4,297,266, Cl. 260-42.140.
- Ichikawa, Hideji: See—
Nishiyama, Yukinori; and Ichikawa, Hideji, 4,296,843, Cl. 188-73.430.
- Ichikawa, Junji; Imai, Nobuhiro; Kohno, Kimio; Kadokura, Koichi; and Ishii, Masaaki, to Canon Kabushiki Kaisha. Laser recording apparatus. 4,297,713, Cl. 346-108.000.
- Ichimatsu, Eiji, to Nissan Motor Company, Ltd. Weft yarn end treating device for shuttleless loom. 4,296,783, Cl. 139-302.000.
- Ichino, Kazuo: See—
Moriya, Shigeru; Hamamoto, Nobuo; Ichino, Kazuo; and Ozawa, Kanji, 4,297,676, Cl. 340-146.3AG.
- ICI Americas Inc.: See—
Long, William P., Jr., 4,297,258, Cl. 260-29.6MN.
- Stockburger, George J., 4,297,290, Cl. 260-410.600.
- Ieki, Hideharu; and Arai, Seiichi, to Murata Manufacturing Co., Ltd. Electric circuit using surface acoustic wave device. 4,297,660, Cl. 333-194.000.
- Igelbuscher, Heinrich: See—
Holter, Heinz; Gresch, Heinz; and Igelbuscher, Heinrich, 4,297,117, Cl. 55-389.000.
- Iguchi, Eiko: See—
Yoshida, Keizo; Tanaka, Hirokazu; Okamoto, Masanori; Iguchi, Eiko; Kohsaka, Masanobu; Aoki, Hatsuo; and Imanaka, Hiroshi, 4,297,096, Cl. 435-128.000.
- Iguchi, Shin-Ichi: See—
Nishizawa, Hideaki; and Iguchi, Shin-Ichi, 4,297,720, Cl. 357-30.000.
- Iizuka, Haruhiko; and Sugawara, Fukushima, to Nissan Motor Company, Limited. Internal combustion engine. 4,296,724, Cl. 123-568.000.
- Ikai, Shigeru: See—
Ueno, Haruo; Yano, Takefumi; Inoue, Tokuji; Ikai, Shigeru; Kai, Yoshiyuki; and Shimizu, Michimasa, 4,297,463, Cl. 526-128.000.
- Ikeya, Chuji: See—
Shimizu, Ken-Ichi; and Ikeya, Chuji, 4,297,725, Cl. 358-125.000.
- Illinois Tool Works Inc.: See—
Edwards, Bryant, 4,296,569, Cl. 47-73.000.
- Ernst, Richard J., 4,296,656, Cl. 81-429.000.
- Platt, John R., 4,296,858, Cl. 206-150.000.
- Imai, Nobuhiro: See—
Ichikawa, Junji; Imai, Nobuhiro; Kohno, Kimio; Kadokura, Koichi; and Ishii, Masaaki, 4,297,713, Cl. 346-108.000.
- Imamura, Shinzo: See—
Nakata, Minoru; Sato, Haruyo; and Imamura, Shinzo, 4,297,477, Cl. 528-323.000.
- Imanaka, Hiroshi: See—
Yoshida, Keizo; Tanaka, Hirokazu; Okamoto, Masanori; Iguchi, Eiko; Kohsaka, Masanobu; Aoki, Hatsuo; and Imanaka, Hiroshi, 4,297,096, Cl. 435-128.000.
- Imperial Chemical Industries Limited: See—
Henrick, Clive A.; Labovitz, Jeffrey N.; Fox, Roland T. V.; Rathmell, William G.; and Shephard, Margaret C., 4,297,297, Cl. 260-465.00D.
- Hines, David A.; and Bolton, David H., 4,297,217, Cl. 210-621.000.
- Marsden, Robert S., 4,297,336, Cl. 423-395.000.
- Stead, John C.; and Waghorn, Peter E., 4,297,408, Cl. 428-240.000.
- IMS Limited: See—
Ogle, Robert W., 4,296,747, Cl. 128-220.000.
- Inayama, Minoru; and Furukawa, Yukio, to Rinnai Kabushiki Kaisha. Composite cooking device. 4,297,558, Cl. 219-10.55R.
- Industrie-Wert Beteiligungsgesellschaft mbH: See—
Holter, Heinz; Gresch, Heinz; and Igelbuscher, Heinrich, 4,297,117, Cl. 55-389.000.
- Ing. C. Olivetti & C., S.p.A.: See—
Becchi, Raffaele; Giaccone, Felice; and Accattino, Andrea, 4,297,573, Cl. 250-231.0SE.
- Inhofer, Harold G., to Proteus Corporation. Reciprocating piston-cylinder combination and valving control therefor. 4,296,672, Cl. 91-271.000.
- Inkomag: See—
Hiesinger, Edwin; Keplinger, Klaus; and Nessler, Hermann, 4,297,211, Cl. 210-136.000.
- Innocenti Santeustacchio S.p.A.: See—
Nessi, Aurindo, 4,296,622, Cl. 72-208.000.
- Inomata, Akira: See—
Kadowaki, Hidetaka; Inomata, Akira; Yanagida, Kiyoshi; Hasegawa, Tsunao; Ishii, Satoshi; and Ohtake, Yasushi, 4,297,730, Cl. 360-66.000.
- Inoue, Shigeo: See—
Abe, Yoshiaki; Inoue, Shigeo; and Ishida, Atsuo, 4,297,340, Cl. 424-70.000.

- Inoue, Tokuji: See—
Ueno, Haruo; Yano, Takefumi; Inoue, Tokuji; Ikai, Shigeru; Kai, Yoshiyuki; and Shimizu, Michimasa, 4,297,463, Cl. 526-128.000.
- Inoue, Yoshiaki: See—
Miyamoto, Kinzo; Tanaka, Takayasu; and Inoue, Yoshiaki, 4,297,263, Cl. 260-32.6PQ.
- Inouye, Hiroshi, to Hitachi, Ltd. Mechanical seal. 4,296,935, Cl. 277-81.00R.
- Institut Dr. Friedrich Forster Prüfgeratebau: See—
Link, Hans; and Dreher, Ulrich, 4,297,636, Cl. 324-262.000.
- Institut Francais du Pétrole: See—
Layotte, Pierre-Claude; and James, Andre, 4,296,828, Cl. 181-121.000.
- Institut National de la Sante et de la Recherche Medicale: See—
Rips, Richard; and Morier, Elisabeth, 4,297,346, Cl. 424-177.000.
- Intec Corporation: See—
Baker, Cole H., 4,297,587, Cl. 250-563.000.
- International Business Machines Corporation: See—
Aboelfotoh, Mohamed O., 4,297,613, Cl. 315-58.000.
- Andresen, Rolf; and Christian, John H., 4,297,737, Cl. 360-135.000.
- Aviram, Ari, 4,297,434, Cl. 430-270.000.
- Bach, Paul S.; Harding, Steven R.; Lamos, Richard A.; Markham, Harvey R.; and Shepherd, Roger D., 4,297,025, Cl. 355-14.0SH.
- Bjorklund, Gary C., 4,297,035, Cl. 356-402.000.
- Burton, Robert L.; and Finan, Thomas P., 4,297,045, Cl. 400-641.000.
- Laishley, William J.; and Taylor, John R., 4,297,734, Cl. 360-78.000.
- Lammers, Gerald B.; and Smith, Gordon J., 4,297,712, Cl. 346-75.000.
- Schaefer, John O., 4,297,041, Cl. 400-161.400.
- International Minerals & Chemical Corporation: See—
Eckler, Paul E.; Summers, William A.; and Chandler, Ollie W., 4,297,443, Cl. 521-129.000.
- International Nickel Company, Inc.: See—
Crosby, Jeffrey N., 4,297,178, Cl. 204-47.000.
- Pickens, Joseph R.; Schelleng, Robert D.; Donachie, Stephen J.; and Nichol, Thomas J., 4,297,136, Cl. 75-206.000.
- Turillon, Pierre P.; Hull, Michael N.; and Nordblom, George F., 4,297,421, Cl. 429-225.000.
- International Telephone and Telegraph Corporation: See—
Bickel, Gary W., 4,296,995, Cl. 350-96.150.
- Salman, Syed, 4,297,197, Cl. 204-297.00W.
- Interscan Corporation: See—
Shaw, Manuel; and Thatcher, Imbrie, 4,297,689, Cl. 340-632.000.
- Interstate Electronics Corp.: See—
Benno, Richard D., 4,297,528, Cl. 179-1.0SB.
- Irvin, William A. Liquid level control system. 4,297,081, Cl. 417-2.000.
- Isaka, Tsutomu: See—
Akutsu, Susumu; Isaka, Tsutomu; and Ishioka, Mitsugu, 4,297,310, Cl. 264-83.000.
- Isayama, Shogo: See—
Takehara, Nobumitsu; and Isayama, Shogo, 4,297,396, Cl. 427-284.000.
- Isenberg, Jack M., to Boeing Company, The. Apparatus and method for manufacturing laminar flow control aircraft structure. 4,296,899, Cl. 244-207.000.
- Ishiba, Teruyuki: See—
Hirai, Kentaro; Matsutani, Shigeru; Ishiba, Teruyuki; and Makino, Itsuo, 4,297,280, Cl. 260-245.500.
- Ishibashi, Yoji; Uchiyama, Yoshihiro; Akimoto, Hidetoshi; and Sasaki, Makoto, to Hitachi, Ltd. Apparatus for removing nitrogen oxides from flue gas. 4,297,319, Cl. 422-114.000.
- Ishida, Atsuo: See—
Abe, Yoshiaki; Inoue, Shigeo; and Ishida, Atsuo, 4,297,340, Cl. 424-70.000.
- Ishida, Masahiko; Haga, Ryooichi; and Odawara, Youji, to Hitachi, Ltd. Method for treatment of biochemical waste. 4,297,216, Cl. 210-613.000.
- Ishida, Takashi; and Tanaka, Mamoru, to Nissan Motor Company, Limited. Support assembly for an exhaust system of a motor vehicle. 4,296,907, Cl. 248-573.000.
- Ishihara, Michio: See—
Nagahama, Tsutomu; and Ishihara, Michio, 4,297,722, Cl. 357-74.000.
- Ishii, Masaaki: See—
Ichikawa, Junji; Imai, Nobuhiro; Kohno, Kimio; Kadokura, Koichi; and Ishii, Masaaki, 4,297,713, Cl. 346-108.000.
- Ishii, Satoshi: See—
Kadowaki, Hidetaka; Inomata, Akira; Yanagida, Kiyoshi; Hasegawa, Tsunao; Ishii, Satoshi; and Ohtake, Yasushi, 4,297,730, Cl. 360-66.000.
- Ishii, Sizuo: See—
Yagi, Michio; Nakajima, Kunio; Nakagawa, Yasutsugu; Ishii, Sizuo; and Aratame, Kazuhisa, 4,297,019, Cl. 354-171.000.
- Ishikawa, Masakazu: See—
Fujimori, Fumio; Yokoi, Masatada; Ishikawa, Masakazu; Uemura, Hiroshi; and Shirai, Akira, 4,296,841, Cl. 188-73.380.
- Ishioka, Mitsugu: See—
Akutsu, Susumu; Isaka, Tsutomu; and Ishioka, Mitsugu, 4,297,310, Cl. 264-83.000.
- Isobe, Mitsuhide, to Shimano Industrial Company, Limited. Rear hub having improved mounting of a cylindrical bearing member to an inner member. 4,296,850, Cl. 192-64.000.
- Ito, Fumio: See—
Murakami, Hiroyasu; Ito, Tadashi; and Ito, Fumio, 4,297,018, Cl. 354-50.000.
- Ito, Isao; and Tunashima, Seiichi, to NGK Insulators, Ltd. Apparatus for measuring contour configuration of articles. 4,297,034, Cl. 356-394.000.
- Ito, Kunimoto; Kakizawa, Tsutomu; Yonetani, Kengo; and Nariai, Hiroshi. Small piezoelectric tuning fork. 4,297,610, Cl. 310-370.000.
- Ito, Tadashi: See—
Murakami, Hiroyasu; Ito, Tadashi; and Ito, Fumio, 4,297,018, Cl. 354-50.000.
- Ito, Takaharu: See—
Yasuba, Shoichi; and Ito, Takaharu, 4,296,657, Cl. 82-1.00C.
- Ito, Takashi: See—
Kamogawa, Nin-ichi; and Ito, Takashi, 4,297,562, Cl. 219-216.000.
- Ito, Thomas I.: See—
Paciorek, Kazimiera J. L.; Kratzer, Reinhold H.; Ito, Thomas I.; and Nakahara, James H., 4,297,510, Cl. 564-13.000.
- Iwai, Michinobu; and Tanimoto, Akira, to Tokyo Shibaura Denki Kabushiki Kaisha. Movable contact arm assembly. 4,297,555, Cl. 200-153.00G.
- Iwamoto, Masaru. Speed up device for bicycle. 4,296,939, Cl. 280-212.000.
- Iwanaga, Kazuyoshi; Sugano, Kazuhiko; and Ohtsuka, Kunio, to Nissan Motor Company, Limited. Automatic power transmission shift valve. 4,296,651, Cl. 74-869.000.
- Iwasa, Masakazu: See—
Kudo, Yoshio; Iwasa, Masakazu; and Kato, Hisashi, 4,297,384, Cl. 427-14.100.
- Iwatsu Electric Co., Ltd.: See—
Ebisawa, Kiyohito; Hisabayashi, Satoshi; Koike, Toshio; and Hashimoto, Kazuyuki, 4,297,024, Cl. 355-14.00E.
- Izod, Thomas J. P.: See—
Lok, Brent M. T.; and Izod, Thomas J. P., 4,297,335, Cl. 423-328.000.
- J. I. Case Company: See—
Benson, Samuel L., 4,296,846, Cl. 192-4.00A.
- Jachimowicz, Felek, to W. R. Grace & Co. Process of forming polymeric polyamine/amide. 4,297,481, Cl. 528-392.000.
- Jackel, Klaus: See—
Werner, Peter; Drews, Ulrich; Elbers, Theodor; and Jackel, Klaus, 4,297,599, Cl. 307-355.000.
- Jacobs Manufacturing Company, The: See—
Price, Robert B., 4,296,605, Cl. 60-599.000.
- Jacobs, Marcellus L.; and Jacobs, Paul R. Automatic storm protection control for wind energy system. 4,297,075, Cl. 416-14.000.
- Jacobs, Paul R.: See—
Jacobs, Marcellus L.; and Jacobs, Paul R., 4,297,075, Cl. 416-14.000.
- Jaeggi, Knut A.: See—
Haas, Georges; Jaeggi, Knut A.; Rossi, Alberto; and Sele, Alex, 4,297,358, Cl. 424-256.000.
- Jaffe, Max: See—
Concha, Edward; Jaffe, Max; and Bedford, Riley, 4,297,068, Cl. 414-458.000.
- Jaffin, Harry A.; and Gliewe, Russell H. Apparatus for collecting ejected cartridges. 4,296,565, Cl. 42-1.00T.
- James, Andre: See—
Layotte, Pierre-Claude; and James, Andre, 4,296,828, Cl. 181-121.000.
- James, Kenneth A.: See—
Quick, William H.; James, Kenneth A.; and Strahan, Virgil H., 4,296,994, Cl. 350-3.730.
- Jameson, James J., to Cooper Industries, Inc. Powershift transmission with direct drive and modulated torque converter drive in forward and reverse. 4,296,645, Cl. 74-688.000.
- Janson, Mats O., to Tylo Sauna S.A. Sauna heating unit and shield therefor. 4,296,507, Cl. 4-524.000.
- Jardin, Hans; and Hirschberger, August, to Webasto-Werk W. Baier GmbH & Co. Wind deflector for sliding roofs of motor vehicles. 4,296,962, Cl. 296-217.000.
- Jarman, Davis R.; and Hinson, Virgil H. Wheel alignment apparatus. 4,296,626, Cl. 72-392.000.
- Jarnum, Lennart, to AB Jarnkonstruktioner. Vertically adjustable bridge for connection with ships. 4,296,516, Cl. 14-71.700.
- Jarrett, Robert B.: See—
LoCascio, James J.; and Jarrett, Robert B., 4,297,646, Cl. 330-288.000.
- Jawad, Maan, to Nooter Corporation. Pressure vessel head. 4,296,869, Cl. 220-3.000.
- Jehle, Fritz; and Willenbacher, Erich, to Pfaff Industriemaschinen GmbH. Device for the automatic guiding of a workpiece on a sewing machine. 4,296,700, Cl. 112-153.000.
- JENAer Glaswerk Schott & Gen.: See—
Hussmann, Eckart, 4,296,742, Cl. 126-450.000.
- Ritze, Willy, 4,297,142, Cl. 501-77.000.
- Jensen, Borge R., to Danfoss A/S. Measuring equipment for acoustic determination of the specific gravity of liquids. 4,297,608, Cl. 310-335.000.
- Jensen, Michael E.: See—
Smith, Robert J.; Smith, Mark A.; Jensen, Michael E.; and Smith, Robert L., 4,297,120, Cl. 65-281.000.
- Jervis, James E., to Raychem Corporation. Heat-shrinkable hollow article. 4,297,155, Cl. 156-86.000.
- Jesse, Harold W.; and Jones, Peter M., to TME, Inc. Cable shield. 4,297,522, Cl. 174-36.000.
- Jewett, M. Pearson. Submersible pump puller. 4,296,916, Cl. 254-380.000.

- Jidosha Kiki Co., Ltd.: See—
Ohta, Ryuji; and Kobayashi, Michio, 4,296,680, Cl. 92-98.00D.
- Jikihara, Tomo: See—
Umezawa, Hamao; Umezawa, Sumio; Tsuchiya, Tsutomu; Takagi, Yasushi; and Jikihara, Tomo, 4,297,485, Cl. 536-10.000.
- John C. Lehman, Inc.: See—
Lehman, John C., 4,296,984, Cl. 312-268.000.
- John Fluke Mfg. Co., Inc.: See—
Koeman, Henricus, 4,297,680, Cl. 340-347.0AD.
- John Zink Company: See—
Reed, Robert D.; Schwartz, Robert E.; and Kraft, Raymond D., 4,297,094, Cl. 431-202.000.
- Johnson, Allen S., Jr., to Staclean Diffuser Company. Bag-type filter with air diffuser tubes of helical construction. 4,297,115, Cl. 55-302.000.
- Johnson, Bruce K.; and Whiteside, George D., to Polaroid Corporation. Scanning shutter blade arrangement with dynamic apertures for ambient and flash exposures. 4,297,016, Cl. 354-27.000.
- Johnson, David W., Jr.; Singh, Shobha; Van Uiter, LeGrand G.; and Zydzik, George J., to Bell Telephone Laboratories, Incorporated. Persistent memory cell. 4,297,005, Cl. 350-357.000.
- Johnson & Johnson: See—
Nguyen, Hien V., 4,297,404, Cl. 428-85.000.
- Welsh, Luther; Bergquist, Daryl J.; and Watanabe, Hideo, 4,296,752, Cl. 128-635.000.
- Johnson, Matthew & Co., Limited: See—
Sermon, Paul A., 4,297,331, Cl. 423-239.000.
- Johnson, Paul H., to Phillips Petroleum Company. Waste heat recovery. 4,296,800, Cl. 165-95.000.
- Johnson, Steven A. Focusing cover solar energy collector apparatus. 4,297,521, Cl. 136-248.000.
- Jolly, Jennings L.; and Roos, Leo, to Hercules Incorporated. Contrast colorant for photopolymerizable compositions. 4,297,435, Cl. 430-270.000.
- Jones, John B.; and Kunchal, S. Kumar. Process for oil shale retorting. 4,297,201, Cl. 208-11.00R.
- Jones, Peter M.: See—
Jesse, Harold W.; and Jones, Peter M., 4,297,522, Cl. 174-36.000.
- Joppien, Harmut: See—
Puttner, Reinhold; Buhmann, Ulrich; and Joppien, Harmut, 4,297,361, Cl. 424-263.000.
- Jordening, Harold G. Bike carrying adapter. 4,296,879, Cl. 224-42.45R.
- Jordon, Hans: See—
Bohler, Joachim; and Jordon, Hans, 4,296,517, Cl. 15-93.00R.
- Joslin, Joel A.; and Ranford, Alan B., to Sherwood Medical Industries Inc. Blood collection device and method with anti-backflow means. 4,296,759, Cl. 128-766.000.
- Jouffret, Michel: See—
Costantini, Michel; and Jouffret, Michel, 4,297,287, Cl. 260-348.160.
- Jozwiak, Edward L., Jr., to PPG Industries, Inc. Cationic polymers and their use in electrodeposition. 4,297,261, Cl. 260-29.7RP.
- Jubilee Manufacturing Co.: See—
Merten, Richard C., 4,297,674, Cl. 340-63.000.
- Jude Engineering, Inc.: See—
Christian, Robert F., 4,297,208, Cl. 210-94.000.
- Judell, Neil H. K., to Datamedix Inc. Method and apparatus for determining ventricular fibrillation. 4,296,755, Cl. 128-705.000.
- Juner, Adolph; and Haas, David J., to North American Philips Corporation. X-ray optical system for article inspection, with components disposed on parallel axes. 4,297,580, Cl. 250-368.000.
- Jung, Wilhelm; and Rau, Karl, to VDO Adolf Schindling AG. Apparatus for capacitive filling-level measuring, particularly in a motor vehicle tank. 4,296,630, Cl. 73-304.00C.
- Jureit, John C.; and Greenley, Henry R., to Automated Building Components, Inc. Fasteners for joining angularly related wooden members. 4,297,048, Cl. 403-189.000.
- Jyojiki, Masao: See—
Nakamura, Kazuo; Jyojiki, Masao; and Aoki, Harumi, 4,297,014, Cl. 354-25.000.
- Kabas, Guglielmo: See—
Burdeska, Kurt; and Kabas, Guglielmo, 4,297,234, Cl. 252-301.240.
- Kabel-und Metallwerke Gutehoffnungshuette A.G.: See—
Leuchs, Ottmar; and Maltz, Georg, 4,297,526, Cl. 174-102.00R.
- Kabushiki Kaisha Fujikoshi: See—
Okano, Hiroshi; and Sato, Akira, 4,296,648, Cl. 74-798.000.
- Kabushiki Kaisha Suwa Seikosha: See—
Mitsui, Yoshihiro, 4,297,697, Cl. 340-813.000.
- Kabushiki Kaisha Taiyohatsuyo Seisakusho: See—
Nagano, Kenji, 4,296,534, Cl. 24-270.000.
- Kabushiki Kaisha Asahi Shinbunsha: See—
Miyamoto, Kinzo; Tanaka, Takayasu; and Inoue, Yoshimi, 4,297,263, Cl. 260-32.6PQ.
- Kadokura, Koichi: See—
Ichikawa, Junji; Imai, Nobuhiro; Kohno, Kimio; Kadokura, Koichi; and Ishii, Masaaki, 4,297,713, Cl. 346-108.000.
- Kadowaki, Hidetaka; Inomata, Akira; Yanagida, Kiyoshi; Hasegawa, Tsunao; Ishii, Satoshi; and Ohtake, Yasushi, to Pioneer Electronic Corporation. Magnetic recording and reproducing device. 4,297,730, Cl. 360-66.000.
- Kagata, Tooru; and Goto, Hiromi, to Aisin Seiki Kabushiki Kaisha. Free wheel hub mechanism. 4,296,848, Cl. 192-35.000.
- Kagi, Bruno; Hirmann, Georg; and Luginbuhl, Rolf, to Bachofen AG. Device for detachably coupling the orifice of a branchline to a line carrying a pressure medium. 4,296,774, Cl. 137-322.000.
- Kagi, Bruno; Hirmann, Georg; and Luginbuhl, Rolf, to Bachofen AG. Device for detachably coupling a branchline to a pressure line. 4,296,775, Cl. 137-322.000.
- Kahara, Toshiaki; Tamura, Kohki; Ebata, Noboru; Sato, Fumio; and Yoshida, Tomio, to Hitachi, Ltd.; and Hitachi Chemical Co., Ltd. Process for producing a positive electrode for a non-aqueous electrolytic cell. 4,297,231, Cl. 252-182.100.
- Kai, Yoshiyuki: See—
Ueno, Haruo; Yano, Takefumi; Inoue, Tokuji; Ikai, Shigeru; Kai, Yoshiyuki; and Shimizu, Michimasa, 4,297,463, Cl. 526-128.000.
- Kajavo, Kari: See—
Lampinen, Esko; and Kajavo, Kari, 4,296,545, Cl. 29-602.00R.
- Kakigi, Takao, to Cybernet Electronics Corp. Photoelectric smoke sensing and alarming device. 4,297,688, Cl. 340-630.000.
- Kakimi, Fujio: See—
Hoshi, Yoshiyuki; Hayashi, Takayuki; and Kakimi, Fujio, 4,297,235, Cl. 252-316.000.
- Kakizawa, Tsutomu: See—
Ito, Kunimoto; Kakizawa, Tsutomu; Yonetani, Kengo; and Nariai, Hiroshi, 4,297,610, Cl. 310-370.000.
- Kalfoglou, George, to Texaco Inc. Surfactant waterflooding oil recovery method. 4,296,812, Cl. 166-274.000.
- Kali and Salz AG: See—
Singewald, Arno; Geisler, Irving; Fricke, Gunter; and Knappe, Rudolf, 4,297,207, Cl. 209-9.000.
- Kalns, Ilmars, to Eaton Corporation. Two-speed transaxle. 4,296,650, Cl. 74-751.000.
- Kamada, Masataka; and Satoh, Seiji. Decorated soap and method for producing the same. 4,297,228, Cl. 252-92.000.
- Kamar International, Inc.: See—
Kamar, Pascal M., 4,296,567, Cl. 46-163.000.
- Kamar, Pascal M., to Kamar International, Inc. Figure toy with flexible appendages. 4,296,567, Cl. 46-163.000.
- Kambanis, Stamatis M.: See—
De Ruiter, Robert S.; and Kambanis, Stamatis M., 4,297,264, Cl. 260-33.40R.
- Kamibayashi, Tetsusaburo: See—
Kobayashi, Toshihiko; and Kamibayashi, Tetsusaburo, 4,297,602, Cl. 310-26.000.
- Kaminishi, Katuzo: See—
Akiyama, Masahiro; Kaminishi, Katuzo; and Kawakami, Yasushi, 4,297,647, Cl. 330-307.000.
- Kamogawa, Nin-ichi; and Ito, Takashi, to Konishiroku Photo Industry Co., Ltd. Heat roller type fixing apparatus. 4,297,562, Cl. 219-216.000.
- Kanada, Eiji; Yamada, Shoji; and Tsubai, Yasuo, to Mitsubishi Paper Mills, Ltd. Photographic material and diffusion transfer processing solution for making printing plates and method for making printing plates. 4,297,429, Cl. 430-204.000.
- Kanada, Eiji; Yamada, Shoji; and Tsubai, Yasuo, to Mitsubishi Paper Mills, Ltd. Photographic material for production of printing plates and method for production of printing plates. 4,297,430, Cl. 430-204.000.
- Kanegae, Hidetoshi: See—
Abo, Toshimi; and Kanegae, Hidetoshi, 4,296,600, Cl. 60-39.28R.
- Kaneko, Tomonobu, to Amada Company, Limited. Feed control for horizontal bandsaw machines. 4,296,661, Cl. 83-796.000.
- Kaneko, Yutaka; Hirabayashi, Shigeto; Kawakatsu, Satoshi; and Ninomiya, Hidetaka, to Konishiroku Photo Industry Co., Ltd. Processing method of silver halide color photographic material. 4,297,437, Cl. 430-376.000.
- Kaneko, Yutaka; Kawakatsu, Satoshi; Hirabayashi, Shigeto; and Ninomiya, Hidetaka, to Konishiroku Photo Industry Co., Ltd. Photographic material. 4,297,441, Cl. 430-543.000.
- Kangol Magnet Limited: See—
Clifford, Roy, 4,296,942, Cl. 280-803.000.
- Kansas State University Research Foundation: See—
Kyle, Benjamin G., 4,297,172, Cl. 203-19.000.
- Kantz, John F.: See—
Hsu, Fu-Tong; and Kantz, John F., 4,296,860, Cl. 206-386.000.
- Kao Soap Co., Ltd.: See—
Abe, Yoshiaki; Inoue, Shigeo; and Ishida, Atsuo, 4,297,340, Cl. 424-70.000.
- Tsuchiya, Yoshimi; Sagae, Masayuki; and Mizutani, Hiroshi, 4,297,410, Cl. 428-283.000.
- Kaplan, Murray A.: See—
Gottstein, William J.; Kaplan, Murray A.; and Granatek, Alphonse P., 4,297,489, Cl. 544-27.000.
- Kara, Frederick E.: See—
Miller, Kirk D.; Flood, John B.; Dimou, George; Kara, Frederick E.; and Amos, Richard W., 4,296,920, Cl. 266-216.000.
- Karady, Sandor: See—
Christensen, Burton G.; Cama, Lovji D.; Karady, Sandor; and Slettinger, Meyer, 4,297,488, Cl. 544-21.000.
- Karol, James J.; Normann, Richard W.; and Hotchkiss, Lloyd C., to Bendix Corporation. The integral electrical contact and method of making same. 4,296,985, Cl. 339-48.000.
- Karube, Isao: See—
Hikuma, Motohiko; Kubo, Tatsuru; Yasuda, Takeo; Karube, Isao; and Suzuki, Shuichi, 4,297,173, Cl. 204-1.00T.
- Kasahara, Nobuyoshi; and Nonomura, Koutaro, to Mitsui Mining & Smelting Co., Ltd. Corrosion resistant metallic article having a matte nacreous appearance. 4,297,405, Cl. 428-141.000.
- Kasai, Goro; Takechi, Sanjuro; and Harima, Hiroshi, to Kuraray Company, Ltd. Method of making wig archetype. 4,297,315, Cl. 264-322.000.

- Kashiwabara, Akira: See—
Kubotera, Kikuo; Sato, Masamichi; Kashiwabara, Akira; and Sato, Kotaro, 4,297,436, Cl. 430-310.000.
- Kato, Hisashi: See—
Kudo, Yoshio; Iwasa, Masakazu; and Kato, Hisashi, 4,297,384, Cl. 427-14.100.
- Kato, Makoto; Ueda, Nobuo; and Matsushima, Hiroaki, to Nihon Medi-Physics Co., Ltd. Thallium-carrying target material and its production. 4,297,166, Cl. 376-194.000.
- Kato, Shiro: See—
Tsuboi, Akira; and Kato, Shiro, 4,296,541, Cl. 29-568.000.
- Katoh, Haruhiko: See—
Sanemitsu, Yuzuru; Mizutani, Masato; Sumida, Seizo; Katoh, Haruhiko; Oshio, Hiromichi; and Hashimoto, Shunichi, 4,297,129, Cl. 71-93.000.
- Katsube, Junki: See—
Ohashi, Naohito; Nagata, Shoji; and Katsube, Junki, 4,297,282, Cl. 260-326.200.
- Katsunuma, Nobuhiko. Nucleoside derivatives and an antileukemic agent containing the same as an active ingredient. 4,297,347, Cl. 424-180.000.
- Katsuragi, Shigeru: See—
Ogawa, Mutsuo; Koseki, Yuji; Saitoh, Yuichi; Yamaguchi, Shingo; and Katsuragi, Shigeru, 4,297,727, Cl. 358-261.000.
- Katzman, Allison W.: See—
Erickson, Erick E.; Katzman, Allison W.; and Breslow, Jeffrey D., 4,297,153, Cl. 156-63.000.
- Kaufel Group Ltd.: See—
Chandler, Edward A., 4,297,614, Cl. 315-86.000.
- Kaufman, Jack W.: See—
Blake, Joseph W., III; and Kaufman, Jack W., 4,296,751, Cl. 128-325.000.
- Kavasanek, Percy R.; Stanton, David B.; and Sherman, Paul D., Jr., to Union Carbide Corporation. Method of preparing an olefin hydration catalyst. 4,297,241, Cl. 252-435.000.
- Kavchok, Ronald W.: See—
Papalos, John G.; and Kavchok, Ronald W., 4,297,259, Cl. 260-29.6NR.
- Kawaguchi, Yoshihiro; Higuchi, Kosuke; and Kitajima, Yoshiro, to Tokyo Shibaura Denki Kabushiki Kaisha. Enclosed switching apparatus. 4,297,553, Cl. 200-145.000.
- Kawakami, Tomiko: See—
Sakai, Kiyoshi; Hashimoto, Mitsuru; and Kawakami, Tomiko, 4,297,426, Cl. 430-59.000.
- Kawakami, Yasushi: See—
Akiyama, Masahiro; Kaminishi, Katuzo; and Kawakami, Yasushi, 4,297,647, Cl. 330-307.000.
- Kawakatsu, Satoshi: See—
Kaneko, Yutaka; Hirabayashi, Shigeto; Kawakatsu, Satoshi; and Ninomiya, Hidetaka, 4,297,437, Cl. 430-376.000.
- Kaneko, Yutaka; Kawakatsu, Satoshi; Hirabayashi, Shigeto; and Ninomiya, Hidetaka, 4,297,441, Cl. 430-543.000.
- Kawamura, Masaharu; Uchidoi, Masanori; Shigeta, Yoshihiro; Sugiura, Yoji; and Yamamoto, Hiroshi, to Canon Kabushiki Kaisha. Coordinating control system for camera. 4,297,013, Cl. 354-23.00D.
- Kawaziri, Kazuhiro: See—
Higashi, Akio; Kawaziri, Kazuhiro; and Nakajima, Yosuke, 4,297,392, Cl. 427-75.000.
- KBI Corp.: See—
Kirk, Joseph R.; and Campbell, Edward C., 4,297,219, Cl. 210-669.000.
- Keast, Larry G.; and Horton, Herbert D., to World Wide Oil Tools, Inc. Pawl and ratchet mechanism. 4,296,842, Cl. 188-61.000.
- Keckman, Heikki. Skylight apparatus. 4,296,578, Cl. 52-200.000.
- Kekalo, Vasily I.: See—
Berkhin, Isif M.; Gudze, Robert A.; Kekalo, Vasily I.; Panasenko, Nikolai N.; Podbeltsev, Viktor I.; Tsygina, Zinaida D.; and Mukhin, Vladislav N., 4,296,867, Cl. 212-229.000.
- Kellar, John D.; and Pereman, Gordon F., to PPG Industries, Inc. Controlling overheating of vacuum mold used to shape glass sheets. 4,297,118, Cl. 65-104.000.
- Keller, Robert N., to National Steel Corporation. Method of manufacturing expanded reinforcing sheet material. 4,297,154, Cl. 156-79.000.
- Kelman, Charles D. Intraocular lens and method of making the same. 4,296,501, Cl. 3-13.000.
- Kelsey, Wayne R.: See—
Muetterties, Andrew J.; Vcelka, John L.; and Kelsey, Wayne R., 4,296,949, Cl. 285-18.000.
- Kelton, Wallace G. Cylindrical solar energy collector. 4,296,738, Cl. 126-443.000.
- Kemi-Intressen AB: See—
Lundgren, Sune I.; and Rehnberg, Leif E. L., 4,296,653, Cl. 81-3.46R.
- Kemper, Yves J., to Vadtetec Corporation. Differential transmission drive unit. 4,296,647, Cl. 74-690.000.
- Kempf, Georg: See—
Schlauer, Johann; Kempf, Georg; and Doerges, Alexander, 4,297,330, Cl. 423-232.000.
- Ken-Koat, Inc.: See—
Robertson, Kenneth L.; and Heslep, Curtis A., 4,296,708, Cl. 118-233.000.
- Kennametal Inc.: See—
Armbrust, William D.; and McCreery, James F., 4,297,058, Cl. 407-113.000.
- Kennedy, Leroy P., to Abex Corporation. Railroad car hand brake signal device. 4,296,707, Cl. 116-58.00A.
- Kenneth E. Beswick Ltd.: See—
Gale, James A., 4,297,669, Cl. 337-407.000.
- Kennington, Kerry S., to Hughes Tool Company. Nozzle placement in large diameter earth boring bits. 4,296,824, Cl. 175-340.000.
- Kenyon, Ralph E.: See—
Topalian, Harry H.; Wyss, Clement R.; Kenyon, Ralph E.; and Dec, Anthony F., 4,297,379, Cl. 426-565.000.
- Kepler, Klaus: See—
Hiesinger, Edwin; Kepler, Klaus; and Nessler, Hermann, 4,297,211, Cl. 210-136.000.
- Kern, Jorg; and Guth, Christian, to Ciba-Geigy Corporation. Process for imparting to textile materials a soft handle using unsaturated aliphatic acid amides. 4,297,400, Cl. 427-389.000.
- Kernforschungsanlage Julich Gesellschaft mit beschränkter Haftung: See—
Arbel, Arie; and Kurz, Rainer, 4,297,679, Cl. 340-347.0AD.
- Kernforschungszentrum Karlsruhe, GmbH: See—
Scheffler, Knut; and Riege, Ulrich, 4,297,304, Cl. 264-0.500.
- Kessler, Bayard F., to Novation, Inc. Electronics package. 4,297,530, Cl. 179-2.00C.
- Kester, Jack R.: See—
Townsend, Raymond L.; Kester, Jack R.; and Young, Kenneth A., 4,297,561, Cl. 219-137.630.
- Kezerian, Charles: See—
Gaughan, Edmund J.; and Kezerian, Charles, 4,297,295, Cl. 260-455.00A.
- Kicinski, Kenneth J., to Nelson Industries, Inc. Exhaust muffler. 4,296,832, Cl. 181-255.000.
- Kiekhäfer, Elmer C. Stern drive mechanism. 4,297,097, Cl. 440-59.000.
- Kieserling & Albrecht: See—
Weller, Alois; and Mai, Wolfgang, 4,296,625, Cl. 72-345.000.
- Kihira, Masafumi: See—
Hamane, Tokuhito; Kinoshita, Toshio; and Kihira, Masafumi, 4,296,543, Cl. 29-596.000.
- Kilbourn, Edward E.; Weiler, Ernest D.; and Weir, William D., to Rohm and Haas Company. 3-Pyridylmethylthiocarbamates. 4,297,342, Cl. 424-84.000.
- Kilinskas, William A.; Selnes, Ronald J.; and Vand den Sype, Jaak S., to Union Carbide Corporation. Method for making fasteners. 4,296,512, Cl. 10-27.00E.
- Killer, Walter HP. Method and apparatus for reducing the activation energy of chemical reactions. 4,297,186, Cl. 204-165.000.
- Kimball International, Inc.: See—
Howell, Stephen L., 4,296,665, Cl. 84-1.030.
- Wilcox, Brian N.; and Robinson, John W., 4,296,666, Cl. 84-1.260.
- Kimberly-Clark Corporation: See—
Woon, Lin-Sun; and Wilson, John C., 4,296,750, Cl. 128-287.000.
- Kimura, Kiyoshi: See—
Seki, Yoshiro; Kobayashi, Hideo; Kimura, Kiyoshi; and Naito, Masayuki, 4,297,028, Cl. 355-41.000.
- Kimura, Takashi, to Tokyo Shibaura Denki Kabushiki Kaisha. Darlington-connected semiconductor device. 4,297,597, Cl. 307-315.000.
- Kinbara, Koichi; Sugimoto, Norimaro; and Nakazawa, Toshitaka, to Meito Co. Ltd.; and Toyo Pulp Co. Ltd. Packaging bag. 4,297,402, Cl. 428-35.000.
- Kinoshita, Toshio: See—
Hamane, Tokuhito; Kinoshita, Toshio; and Kihira, Masafumi, 4,296,543, Cl. 29-596.000.
- Kinugawa, Ryoji: See—
Tsutsui, Kotaro; and Kinugawa, Ryoji, 4,297,540, Cl. 200-5.00B.
- Kirchmayr, Rudolf: See—
Felder, Louis; and Kirchmayr, Rudolf, 4,297,513, Cl. 568-43.000.
- Kirimura, Shunichiro: See—
Deguchi, Yukichi; Yamagishi, Hideki; and Kirimura, Shunichiro, 4,297,187, Cl. 204-165.000.
- Kirk, Joseph R.; and Campbell, Edward C., to KBI Corp., The. Temporary stream filtration system. 4,297,219, Cl. 210-669.000.
- Kita, Toshio: See—
Sakai, Yoshihiro; Tanaka, Ryosaku; Kita, Toshio; Shimotake, Munetoshi; Yamada, Tsuguyoshi; and Ueda, Hiroshi, 4,296,790, Cl. 152-354.00R.
- Kitahara, Tooru: See—
Koga, Isao; Terui, Yohji; Ohgushi, Masuhito; and Kitahara, Tooru, 4,297,499, Cl. 556-465.000.
- Kitajima, Yoshiro: See—
Kawaguchi, Yoshihiro; Higuchi, Kosuke; and Kitajima, Yoshiro, 4,297,553, Cl. 200-145.000.
- Kiteley, Terence J., to Zenith Radio Corporation. Phosphor protection circuit for multiple CRT projection television. 4,297,619, Cl. 315-381.000.
- Kitsuregawa, Takashi: See—
Nishizawa, Jun-ichi; and Kitsuregawa, Takashi, 4,297,718, Cl. 357-22.000.
- Kizaki, Jiro; and Fujii, Takashi, to Aisin Seiki Kabushiki Kaisha; and Toyota Jidosha Kogyo Kabushiki Kaisha. Tandem master cylinder. 4,296,604, Cl. 60-562.000.
- Klaui, Heinrich: See—
Guex, Woldemar; Klaui, Heinrich; Pauling, Horst; and Voirol, Felix, 4,296,801, Cl. 165-104.170.
- Klein, Gary H.; Arons, Howard L.; Stejskal, Joseph F.; Stevens, Donald G.; and Zobel, Henry F., to CPC International Inc. High speed corrugating adhesives. 4,297,144, Cl. 106-197.00C.
- Kleine-Kieffmann, Werner: See—
Hoffken, Erich; Kleine-Kieffmann, Werner; Bertram, Rolf; Abele, Karl-Heinz; and Michalski, Gunter, 4,297,151, Cl. 148-9.00R.

Kleinschmit, Peter; and Schwarz, Rudolf, to Degussa Aktiengesellschaft. Temperature stabilized silicon dioxide-mixed oxide, the process for its production and use. 4,297,143, Cl. 501-103.000.

KMS Fusion, Inc.: See—
Breuckner, Keith A., 4,297,165, Cl. 376-103.000.

Knappe, Rudolf: See—
Singewald, Arno; Geisler, Irving; Fricke, Gunter; and Knappe, Rudolf, 4,297,207, Cl. 209-9.000.

Knepp, Gary L.: See—
Heitzman, Gary N.; Hutchings, Clay L.; Knepp, Gary L.; and Miller, Robert G., 4,297,742, Cl. 361-154.000.

Knoll International, Inc.: See—
Stephens, William I., 4,296,574, Cl. 52-27.000.

Kobayashi, Hideo: See—
Seki, Yashiro; Kobayashi, Hideo; Kimura, Kiyoshi; and Naito, Masayuki, 4,297,028, Cl. 355-41.000.

Kobayashi, Itaru. Guitarist's foot-rest. 4,296,694, Cl. 108-116.000.

Kobayashi, Michio: See—
Ohta, Ryuji; and Kobayashi, Michio, 4,296,680, Cl. 92-98.00D.

Kobayashi, Susumu, to Terumo Corporation. Centrifugal fluid processing device. 4,296,882, Cl. 233-21.000.

Kobayashi, Toshihiko; and Kamibayashi, Tetsusaburo, to Kokusai Denshin Denwa Kabushiki Kaisha. Magnetostrictive co-ordinate plate for co-ordinate reader. 4,297,602, Cl. 310-26.000.

Kobe Steel, Limited: See—
Asami, Takayoshi, 4,296,539, Cl. 29-157.30A.

Morimoto, Kotaro; and Suzuki, Tomio, 4,297,093, Cl. 431-10.000.

Kobler, Robert J., to AMP Incorporated. Method of manufacturing electrical connector receptacle. 4,296,550, Cl. 29-884.000.

Kobylnski, Thaddeus P.: See—
Wu, Ching-Yong; Pretzer, Wayne R.; and Kobylnski, Thaddeus P., 4,297,518, Cl. 568-385.000.

Koch, Arnold K.: See—
Lee, Harvey R.; Koch, Arnold K.; and Krawczyk, Adam, 4,297,305, Cl. 264-0.500.

Koch, Claude V., to AMF Incorporated. Actuating means for switch operation in timing apparatus. 4,297,546, Cl. 200-38.00R.

Koci, Zdenek; and Mollet, Hans, to Ciba-Geigy Corporation. Aqueous dye preparations. 4,297,100, Cl. 8-527.000.

Kodama, Akira: See—
Fujii, Tadashi; Sato, Shuzo; Muto, Naoki; Hayashi, Mitsuo; Kodama, Akira; and Otani, Masaru, 4,297,486, Cl. 536-17.00R.

Kodama, Kazuyuki; Okada, Kunihiro; Endoh, Takeyuki; and Shibuya, Yasutaka, to Hitachi, Ltd.; and Hitachi Denshi Kabushiki Kaisha. Figure displaying device. 4,297,691, Cl. 340-723.000.

Koegel, Wolfram: See—
Caesar, Arndt C.; Koegel, Wolfram; Zuern, Ludwig; and Gaertner, Friedhelm, 4,297,252, Cl. 252-606.000.

Koehler, Robert P. Slide tray protector. 4,297,010, Cl. 353-122.000.

Koeman, Henricus, to John Fluke Mfg. Co., Inc. Analog waveform digitizer. 4,297,680, Cl. 340-347.0AD.

Koenig, Fredrick: See—
Rodenbeck, Philip G.; and Koenig, Fredrick, 4,296,784, Cl. 140-92.200.

Koenig, Karl-Heinz; and Feuerherd, Karl-Heinz, to BASF Aktiengesellschaft. Novel α -haloalkylcarbamate acid halides, and a process for the preparation of α -haloalkylcarbamate acid halides. 4,297,300, Cl. 260-544.00C.

Kofski, Leonard E. Bracket. 4,296,835, Cl. 182-184.000.

Koga, Isao; Terui, Yohji; Ohgushi, Masuhito; and Kitahara, Tohru, to Chisso Corporation. Novel substituted dichlorosilane and method for producing same. 4,297,499, Cl. 556-465.000.

Kohn, Kimio: See—
Ichikawa, Junji; Imai, Nobuhiro; Kohn, Kimio; Kadokura, Koichi; and Ishii, Masaaki, 4,297,713, Cl. 346-108.000.

Kohsaka, Masanobu: See—
Yoshida, Keizo; Tanaka, Hirokazu; Okamoto, Masanori; Iguchi, Eiko; Kohsaka, Masanobu; Aoki, Hatsu; and Imanaka, Hiroshi, 4,297,096, Cl. 435-128.000.

Koike, Toshio: See—
Ebisawa, Kiyohito; Hisabayashi, Satoshi; Koike, Toshio; and Hashimoto, Kazuyuki, 4,297,024, Cl. 355-14.00E.

Kokusai Denshin Denwa Kabushiki Kaisha: See—
Kobayashi, Toshihiko; and Kamibayashi, Tetsusaburo, 4,297,602, Cl. 310-26.000.

Niino, Yasuhiko; Furusawa, Kahei; and Okada, Akira, 4,296,996, Cl. 350-96.200.

Kolb, Gerald C.: See—
De Koch, Robert J.; Kolb, Gerald C.; and Lalk, James W., 4,297,452, Cl. 525-367.000.

Kolb, Gustav, to Mannesmann Aktiengesellschaft; and Kolb, Gustav. Sampling molten metal. 4,296,638, Cl. 73-863.210.

Koleske, Joseph V., to Union Carbide Corporation. Ester diol alkoxylate based alkyl resins. 4,297,476, Cl. 528-300.000.

Koller & Smith Co., Inc.: See—
Kowalski, George A.; Mayer, George; and Rosenbaum, Murray, 4,297,570, Cl. 235-493.000.

Kolowski, Michael A.: See—
Roberts, Charles W.; Kolowski, Michael A.; Lindner, Daniel J.; Lynch, John E.; Ruip, Terrence M.; and Fetty, Harold D., 4,296,789, Cl. 152-209.00R.

Komatsu, Makoto; Takamizawa, Yuji; and Ohta, Tazuo, to Mitsubishi Gas Chemical Co. Inc. Process and apparatus for producing terephthalic acid with high purity. 4,297,507, Cl. 562-416.000.

Kominami, Yasuo: See—
Wada, Takeshi; Kominami, Yasuo; Miyamoto, Yukihiko; and Yamada, Tsuneo, 4,297,601, Cl. 307-555.000.

Komiya, Hidetsugu, to Fujitsu Fanuc Limited. Spindle control system. 4,297,624, Cl. 318-594.000.

Kondo, Yoshinobu: See—
Matsuoka, Hideoki; and Kondo, Yoshinobu, 4,296,944, Cl. 280-804.000.

Konig, Klaus: See—
Lindner, Christian; Suling, Carlhans; Bartl, Herbert; Schreckenberger, Manfred; Freitag, Dieter; and Konig, Klaus, 4,297,455, Cl. 525-439.000.

Koning, Menno G., to Northrop Corporation. Free rotor gyro with three torquers and three pickoffs. 4,296,639, Cl. 74-5.460.

Konishiroku Photo Industry Co., Ltd.: See—
Honda, Hiroyuki; and Ura, Hiroaki, 4,297,026, Cl. 355-15.000.

Kamogawa, Nin-ichi; and Ito, Takashi, 4,297,562, Cl. 219-216.000.

Kaneko, Yutaka; Hirabayashi, Shigeto; Kawakatsu, Satoshi; and Ninomiya, Hidetaka, 4,297,437, Cl. 430-376.000.

Kaneko, Yutaka; Kawakatsu, Satoshi; Hirabayashi, Shigeto; and Ninomiya, Hidetaka, 4,297,441, Cl. 430-543.000.

Nagoshi, Mitsuru, 4,297,023, Cl. 355-8.000.

Yagi, Michio; Nakajima, Kunio; Nakagawa, Yasutsugu; Ishii, Sizu; and Aratame, Kazuhisa, 4,297,019, Cl. 354-171.000.

Koons, Patrick R.; and Neilson, John M. S., to RCA Corporation. Method of treating SiPOS passivated high voltage semiconductor device. 4,297,149, Cl. 148-1.500.

Kornrumpf, William P.: See—
Bloomer, Milton D.; and Kornrumpf, William P., 4,296,632, Cl. 73-362.0AR.

Kosek, Thomas P.; and Steinhilper, Eric A., to General Motors Corporation. Powdered coal air dispersion nozzle. 4,296,888, Cl. 239-403.000.

Koseki, Yuji: See—
Ogawa, Mutsuo; Koseki, Yuji; Saitoh, Yuichi; Yamaguchi, Shingo; and Katsuragi, Shigeru, 4,297,727, Cl. 358-261.000.

Koshibe, Shigeru; and Nanjo, Motoyuki, to Sumitomo Bakelite Company Limited. Quick-curing phenolic resin and process for preparing same. 4,297,473, Cl. 528-144.000.

Kowalski, George A.; Mayer, George; and Rosenbaum, Murray, to Koller & Smith Co., Inc. Magnetic stripe. 4,297,570, Cl. 235-493.000.

Kowitz, Friedrich: See—
Lindner, Christian; Ott, Karl-Heinz; Arnold, Bernhard; Kowitz, Friedrich; Oertel, Harald; and Kuhlmann, Dieter, 4,297,446, Cl. 525-66.000.

Koyama, Tohru; Narahara, Toshikazu; and Aimonio, Yuji, to Hitachi Chemical Company, Ltd. Odorless or low-odor crosslinkable compound and resin composition containing the same. 4,297,471, Cl. 526-328.000.

Kozacka, Frederick J., to Gould Inc. Fusible electric cable protector. 4,297,667, Cl. 337-251.000.

Krabetz, Richard; Herrmann, Walter; Engelbach, Heinz; Palm, Peter; Sommer, Karl; and Spahn, Heinrich, to BASF Aktiengesellschaft. Preparation of coated catalysts. 4,297,247, Cl. 252-468.000.

Kraft, Raymond D.: See—
Reed, Robert D.; Schwartz, Robert E.; and Kraft, Raymond D., 4,297,094, Cl. 431-202.000.

Kraftwerk Union Aktiengesellschaft: See—
Schabert, Hans-Peter, 4,297,167, Cl. 376-273.000.

Weghaupt, Erich, 4,297,603, Cl. 310-53.000.

Wichmann, Arnold, 4,297,606, Cl. 310-271.000.

Krall, Kenneth M., to Vought Corporation. Airfoil construction. 4,296,900, Cl. 244-219.000.

Kratzer, Reinhold H.: See—
Paciorek, Kazimiera J. L.; Kratzer, Reinhold H.; Ito, Thomas I.; and Nakahara, James H., 4,297,510, Cl. 564-13.000.

Krauss, Timothy A.; and Roman, Stephan, to United Technologies Corporation. Rotor blade pitch control linkage. 4,297,080, Cl. 416-141.000.

Krawczyk, Adam: See—
Lee, Harvey R.; Koch, Arnold K.; and Krawczyk, Adam, 4,297,305, Cl. 264-0.500.

Kremer, Hubert, to Maschinenfabrik Carl Zangs Aktiengesellschaft. Double-lift open-shed Jacquard machine. 4,296,782, Cl. 139-65.000.

Kress, Robert W.; and Bacchi, Anthony C., to Grumman Aerospace Corporation. VTOL Airplane. 4,296,896, Cl. 244-12.400.

Krjuk, Timur P.: See—
Shlykov, Gennady N.; Zhestkov, Vitaly I.; Tikhonov, Valentin N.; Dyachkov, Vasily M.; Glazov, Vladimir G.; and Krjuk, Timur P., 4,296,528, Cl. 19-255.000.

Kroger, Walter. Folding sawhorse. 4,296,834, Cl. 182-155.000.

Kroll, Rudolf: See—
Bernhardt, Winfried; Grunomann, Edgar; and Kroll, Rudolf, 4,296,732, Cl. 126-426.000.

Kronert, Curt, to Thyssen Industrie AG. Rotation-elastic, shock and vibration damping clutch. 4,296,853, Cl. 192-106.100.

Krueger, Walter J.: See—
Debona, Edward J.; Neblett, Boyd L.; Krueger, Walter J.; Laird, William J.; Campbell, Billy H.; and Matthews, Gerald H., 4,296,669, Cl. 89-1.816.

Krug, Hans; and Heilmann, Kurt, to Ferd. Wagner. Gold alloy wire for jewelry chains. 4,297,416, Cl. 428-576.000.

Kruse, Gary L., to Dake Corporation, Division of JSJ Corporation. Packaging machine with cam-operated cutter and container supports therefor. 4,296,589, Cl. 53-300.000.

Kubinski, Karen R.: See—
Beall, George H.; Grossman, David G.; Hoda, Syed N.; and Kubinski, Karen R., 4,297,139, Cl. 501-2.000.

Kubo, Tatsuru: See—
Hikuma, Motohiko; Kubo, Tatsuru; Yasuda, Takeo; Karube, Isao; and Suzuki, Shuichi, 4,297,173, Cl. 204-1.00T.

Kubota, Ltd.: See—
Nagao, Shozo; Ohashi, Yoshinobu; Watanabe, Yuichi; and Waku-shima, Yoshikazu, 4,296,953, Cl. 285-302.000.

Sada, Kenzo; and Hayashi, Shigeyuki, 4,296,644, Cl. 74-606.00R.

Kubotera, Kikuo; Sato, Masamichi; Kashiwabara, Akira; and Sato, Kotaro, to Fuji Photo Film Co., Ltd. Method for producing a multi-layer printing plate. 4,297,436, Cl. 430-310.000.

Kuchuk-Yatsenko, Sergei I.: See—
Paton, Boris E.; Lebedev, Vladimir K.; Kuchuk-Yatsenko, Sergei I.; Sakharov, Vasily A.; Galyan, Boris A.; and Dobrovolsky, Stanislav D., 4,297,665, Cl. 336-60.000.

Kudo, Yoshio; Iwasa, Masakazu; and Kato, Hisashi, to Fuji Photo Film Co., Ltd. Method of developing electrostatic latent image. 4,297,384, Cl. 427-14.100.

Kuger, Manfred; Nawrot, Wolfgang; and Preuss, Bernhard, to Siemens Aktiengesellschaft. Electromagnetic overcurrent tripping device with adjustable armature air gap. 4,297,664, Cl. 335-176.000.

Kuhlmann, Dieter: See—
Lindner, Christian; Ott, Karl-Heinz; Arnold, Bernhard; Kowitz, Friedrich; Oertel, Harald; and Kuhlmann, Dieter, 4,297,446, Cl. 525-66.000.

Kuiper, Joe A.: See—
DeVisser, Richard B.; Rishel, John W.; and Kuiper, Joe A., 4,297,209, Cl. 210-107.000.

Kullander, Jan O., to Aktiebolaget Electrolux. Knock-down cabinet assembly. 4,296,982, Cl. 312-257.00R.

Kumar, Kaplesh; Das, Dilip K.; and Wettstein, Ernest C., to Charles Stark Draper Laboratory, Inc. The Process of making permanent magnets. 4,297,388, Cl. 427-47.000.

Kumpe, Gerhardt: See—
Schwinn, Horst; Heimbürger, Norbert; Kumpe, Gerhardt; and Herchenhan, Bernd, 4,297,344, Cl. 424-101.000.

Kunchal, S. Kumar: See—
Jones, John B.; and Kunchal, S. Kumar, 4,297,201, Cl. 208-11.00R.

Kupar, Daniel E.: See—
Fruchey, Russell L.; and Kupar, Daniel E., 4,297,672, Cl. 340-23.000.

Kuraray Company, Ltd.: See—
Kasai, Goro; Takechi, Sanjuro; and Harima, Hiroshi, 4,297,315, Cl. 264-322.000.

Kurata, Tomoyuki: See—
Uruta, Hisanari; Takahashi, Kaneaki; Masuda, Hirotugu; and Kurata, Tomoyuki, 4,296,705, Cl. 114-219.000.

Kureha Kagaku Kogyo Kabushiki Kaisha: See—
Sasaki, Tohru; Endoh, Hiroyuki; and Ohhira, Hiroshi, 4,297,413, Cl. 428-394.000.

Kurtz, Leonard D.; and Bidwell, Robert E., to BioResearch Inc. Underwater drainage apparatus with separable suction control chamber. 4,296,748, Cl. 128-276.000.

Kurz, Rainer: See—
Arbel, Arie; and Kurz, Rainer, 4,297,679, Cl. 340-347.0AD.

Kusayama, Senji; Nishi, Eihiro; and Stock, Hugh J., to Pacer Technology and Resources, Inc.; and Sumitomo Chemical Company, Ltd. Locking and sealing compositions and methods for their application. 4,297,160, Cl. 156-331.100.

Kusters, Eduard; and Ahrweiler, Karl-Heinz, to Kusters, Eduard. Variable deflection roll controlled by hydraulically actuated reciprocating elements. 4,296,537, Cl. 29-116.0AD.

Kvist, Ulrik: See—
Horholt, Anders; and Kvist, Ulrik, 4,296,524, Cl. 16-150.000.

Kyle, Benjamin G., to Kansas State University Research Foundation. Low energy process of producing gasoline-ethanol mixtures. 4,297,172, Cl. 203-19.000.

Kyowa Hakko Kogyo Co., Ltd.: See—
Takizawa, Hiroshi; Enomoto, Yutaka; Oiji, Yoshimasa; Hirayama, Tatsuyuki; and Hashimoto, Tamotu, 4,297,369, Cl. 424-285.000.

Labovitz, Jeffrey N.: See—
Henrick, Clive A.; Labovitz, Jeffrey N.; Fox, Roland T. V.; Rathmell, William G.; and Shephard, Margaret C., 4,297,297, Cl. 260-465.00D.

Lacomme, Philippe, to Thomson-CSF. Telemetry device for tracking radar and radar system comprising such a device. 4,297,703, Cl. 343-7.300.

Ladin, Eli M., to Federal-Mogul Corporation. Self-aligning shaft bearing mounting assembly. 4,296,977, Cl. 308-19.000.

Ladish Co.: See—
Zimmerly, Robert D., 4,296,951, Cl. 285-95.000.

LaFrance, Robert R. X-ray system signal derivation circuits for heat unit indicators and/or calibration meters. 4,297,638, Cl. 324-410.000.

Lai, John T., to B. F. Goodrich Company. The Synthesis of 2-keto-1,4-diazacycloalkanes. 4,297,497, Cl. 544-384.000.

L'Air Liquide, Societe Anonyme pour l'Etude Procédés Georges Claude: See—
Crommelynck, Francois; Granger, Michel; Rio, Michel; and Tour-dot, Jacques, 4,297,298, Cl. 260-502.00R.

Laird, William J.: See—
Debona, Edward J.; Neblett, Boyd L.; Krueger, Walter J.; Laird, William J.; Campbell, Billy H.; and Matthews, Gerald H., 4,296,669, Cl. 89-1.816.

Laisley, William J.; and Taylor, John R., to International Business Machines Corporation. Sampled data servo positioning system. 4,297,734, Cl. 360-78.000.

Lalk, James W.: See—
De Koch, Robert J.; Kolb, Gerald C.; and Lalk, James W., 4,297,452, Cl. 525-367.000.

Lamare, Jacques: See—
Chaumat, Bernard; Gallet, Georges; Lamare, Jacques; and Peysard, Guy, 4,296,791, Cl. 160-206.000.

Lammers, Gerald B.; and Smith, Gordon J., to International Business Machines Corporation. Air flow tunnel for reducing ink jet drag on array head. 4,297,712, Cl. 346-75.000.

Lamos, Richard A.: See—
Bach, Paul S.; Harding, Steven R.; Lamos, Richard A.; Markham, Harvey R.; and Shepherd, Roger D., 4,297,025, Cl. 355-14.0SH.

Lampinen, Esko; and Kajava, Kari, to Oy Helvar. Casing hook used to impregnate choke or transformer. 4,296,545, Cl. 29-602.00R.

Land Pyrometers Limited: See—
Coe, Charles D.; and Wright, Philip, 4,297,577, Cl. 250-343.000.

Lange, Kenneth: See—
Malinowski, Leon; and Lange, Kenneth, 4,296,818, Cl. 171-63.000.

Lapp, Otto: See—
Berghaller, Peter; Saleck, Wilhelm; Lapp, Otto; and Mucke, Bruno, 4,297,439, Cl. 430-434.000.

Larinoff, Michael W., to Hudson Products Corporation. Steam condensing apparatus. 4,296,802, Cl. 165-110.000.

Larre, Frank J.; and Larre, Jeannine G. Book support. 4,296,946, Cl. 281-45.000.

Larre, Jeannine G.: See—
Larre, Frank J.; and Larre, Jeannine G., 4,296,946, Cl. 281-45.000.

Larsen, Donald W.: See—
Wood, Louis L.; and Larsen, Donald W., 4,297,482, Cl. 528-405.000.

Larsen, Robert H., to Singer Company. The Threading arrangement for chainstitch sewing on a sewing machine. 4,296,701, Cl. 112-168.000.

Larsen, Russell E. Game board and cards. 4,296,927, Cl. 273-248.000.

Larson, Leslie. Drilling rig and conversion apparatus. 4,296,821, Cl. 175-87.000.

Larson, Roderick W.; and Whaley, Ralph D., to Minnesota Mining and Manufacturing Company. Multi-conductor flat cable connector. 4,296,989, Cl. 339-99.00R.

Larsson, Lars E., to Sandvik Aktiebolag. Rock drill. 4,296,825, Cl. 175-410.000.

Lasley, Robert A. Hyperbaric oxygen chamber with fluidic control. 4,296,743, Cl. 128-30.000.

Lauritsen, Richard L.; and Mandellos, Panagiotis K., to Singer Company. The Vacuum switch. 4,297,552, Cl. 200-83.00P.

Laval, Michel; and Tournier, Edmond, to Commissariat à l'Energie Atomique. Device for the interconnection of conductive terminals located within a demountable enclosure and conductive terminals located outside said enclosure. 4,297,576, Cl. 250-336.000.

Lawless, William N., to Corning Glass Works. Cryogenic ceramic and apparatus. 4,296,607, Cl. 62-6.000.

Lawless, William N., to Corning Glass Works. Cryogenic ceramic and apparatus. 4,296,608, Cl. 62-6.000.

Lawrence, Peter. Picture frame having integral latching means. 4,296,561, Cl. 40-158.00R.

Lawson, Daniel C. Toilet seat lock. 4,296,504, Cl. 4-253.000.

Lawson, John E.; and Dennis, Ronald D., to Mead Johnson & Company. 4-Tertiary-amino-2,6-diaminopyridine 1-oxides. 4,297,498, Cl. 546-116.000.

Layotte, Pierre-Claude; and James, Andre, to Institut Francais du Pétrole. Mobil device for generating acoustic shear waves. 4,296,828, Cl. 181-121.000.

Layton, James E., to Phillips Petroleum Company. Gain ranging amplifier. 4,297,745, Cl. 367-66.000.

Lazarz, Christine A.; and Cook, Edward H., Jr., to Hooker Chemicals & Plastics Corp. Stable low voltage microporous diaphragm for electrolytic cells. 4,297,196, Cl. 204-296.000.

Leardi, Anthony, to Hercules Incorporated. In-tank bathroom deodorizer/cleaner. 4,296,503, Cl. 4-228.000.

Learnard, Stanley J. Article display stand. 4,296,866, Cl. 211-131.000.

Leatherman, Ivan R., to PPG Industries, Inc. Hexavalent chromium internal colorants for diol bis (allyl carbonate) polymerizates. 4,297,267, Cl. 260-42.530.

Lebedev, Vladimir K.: See—
Paton, Boris E.; Lebedev, Vladimir K.; Kuchuk-Yatsenko, Sergei I.; Sakharov, Vasily A.; Galyan, Boris A.; and Dobrovolsky, Stanislav D., 4,297,665, Cl. 336-60.000.

Lechner, Robert: See—
Dalhof, Axel; and Lechner, Robert, 4,297,531, Cl. 179-16.0AA.

Leclercq, Joseph, to Framatome. Devices for transversely holding the fuel rods of a nuclear reactor assembly. 4,297,170, Cl. 376-442.000.

Lecolier, Serge L.; and Senet, Jean-Pierre G., to Societe Nationale des Poudres et Explosifs. Process for the manufacture of organic acid chlorides. 4,297,301, Cl. 260-544.00K.

Lee, Byung H. Aircraft safety alarm system. 4,297,678, Cl. 340-328.000.

Lee, Harvey R.; Koch, Arnold K.; and Krawczyk, Adam, to Canadian General Electric Company Limited. Nuclear fuel recycling system. 4,297,305, Cl. 264-0.500.

Lee, Ilyoul, to Electric Power Research Institute, Inc. Apparatus for and method of detecting high impedance faults on distribution circuits with delta connected loads. 4,297,738, Cl. 361-42.000.

Lee, Peter F., to Weyerhaeuser Company. Process for displacement washing of porous media. 4,297,164, Cl. 162-60.000.

- Lee, Sukoo. Surgical stapler using cartridge. 4,296,881, Cl. 227-30.000.
- Lees, Robert, to Autotote, Ltd. Thermal printer. 4,297,039, Cl. 400-120.000.
- Lefebvre, Henry R., to Sun Aired Bag Co., Inc. Garment checking bag. 4,296,876, Cl. 223-91.000.
- Lehinant, Armand: See—
von der Eltz, Hans-Ulrich; Lehinant, Armand; Lehmann, Joachim W.; and Maier, Hans-Peter, 4,297,101, Cl. 8-531.000.
- Lehman, John C., to John C. Lehman, Inc. Cabinet storage conveyor. 4,296,984, Cl. 312-268.000.
- Lehmann, Joachim W.: See—
von der Eltz, Hans-Ulrich; Lehinant, Armand; Lehmann, Joachim W.; and Maier, Hans-Peter, 4,297,101, Cl. 8-531.000.
- Leighton, Betty: See—
Leighton, John D., 4,297,550, Cl. 200-61.890.
- Leighton, John D., to Leighton, Betty, a part interest. Method and construction for vehicle brake pedal and switch assembly. 4,297,550, Cl. 200-61.890.
- Leitner, Lutz: See—
Buxbaum, Gunter; Schopper, Heinrich-Christian; Leitner, Lutz; and Hahnkamm, Volker, 4,297,395, Cl. 427-127.000.
- LEK, tovarna farmacevtskih in kemskih izdelkov, n.s.o.: See—
Suhac, Peter; Hafner-Milac, Natasa; and Dolenc, Bozidar, 4,297,293, Cl. 260-448.00B.
- Leland Stanford University, Board of Trustees of: See—
Trutna, William R., Jr., 4,297,600, Cl. 307-426.000.
- Leliart, Raymond M., to Wheelabrator-Frye Inc. Method of transmission of sonic energy to work pieces. 4,296,794, Cl. 164-131.000.
- Lempa, Bernard J., Jr. Method for offset anchoring a fence post. 4,296,584, Cl. 52-742.000.
- Lengsfeld, Franz: See—
Muller, Rudolf; Lengsfeld, Franz; and Uerlichs, Johannes, 4,296,776, Cl. 137-340.000.
- Leon's Manufacturing Co., Ltd.: See—
Malinowski, Leon; and Lange, Kenneth, 4,296,818, Cl. 171-63.000.
- Leroux, Alain: See—
Chenau, Bernard; and Leroux, Alain, 4,297,420, Cl. 429-217.000.
- Leshner, George Y.; Opalka, Chester J., Jr.; and Page, Donald F., to Sterling Drug Inc. 5-(Pyridinyl)pyridine-2,3-diamines, preparation thereof and their cardiotonic use. 4,297,360, Cl. 424-263.000.
- Leshner, George Y.; and Singh, Baldev, to Sterling Drug Inc. 4-(3,4-Diaminophenyl)pyridine or salts, and use thereof as cardiotonic. 4,297,362, Cl. 424-263.000.
- Leshner, George Y.; and Singh, Baldev, to Sterling Drug Inc. 2-Amino-3(4 or 5)-(pyridinyl)phenols and their use as cardiotonics. 4,297,363, Cl. 424-263.000.
- Lesser, Martin: See—
Rossander, Bror L. E.; Ermebrant, Lennart C.; and Lesser, Martin, 4,296,830, Cl. 181-208.000.
- Lester, Robert W., to Static Systems Corporation. Light pipe valve liquid crystal transmissive display for direct imaging on photosensitive materials. 4,297,022, Cl. 355-3.00R.
- Leuchs, Ottmar; and Maltz, Georg, to Kabel-und Metallwerke Gutehoffnungshuette A.G. Fire resistant electrical cables. 4,297,526, Cl. 174-102.00R.
- Leuschner, Gunter: See—
Tetzlaff, Karl-Heinz; Riemenschneider, Wilhelm; and Leuschner, Gunter, 4,297,323, Cl. 422-208.000.
- Lever Brothers Company: See—
Furrier, Joseph P.; and Gilbert, Allan H., 4,296,518, Cl. 15-110.000.
- Metcalfe, John L.; and Wraige, Douglas, 4,297,406, Cl. 428-215.000.
- Lewis, Jay L., to Robertshaw Controls Company. Pneumatically operated control system and unit therefor and methods of making the same. 4,296,795, Cl. 165-27.000.
- Lewis, John S.; DiGiannantonio, Edmond P.; and Boyle, Howard R., to Lewis, John S.; and DiGiannantonio, Edmond P. Personal ambient sound referenced annunciator. 4,297,677, Cl. 340-148.000.
- Lexa, Anthony F.: See—
Brunson, William T.; and Lexa, Anthony F., 4,297,581, Cl. 250-391.000.
- LGZ Landis & Gyr Zug AG: See—
Antes, Gregor; and Greenaway, David L., 4,297,001, Cl. 350-129.000.
- Gander, Jean-Gabriel; and Aubert, Ralph, 4,297,533, Cl. 179-84.00F.
- Li, Chou H. Semiconductor device. 4,297,717, Cl. 357-15.000.
- Li, Hsin L.; Oswald, Hendrikus J.; and Liland, Alfred L., to Allied Chemical Corporation. Apparatus for texturizing continuous filaments. 4,296,535, Cl. 28-257.000.
- Libbey-Owens-Ford Company: See—
Reed, Ronald R.; Crone, William F., Jr.; and Meyer, G. Robert, 4,296,662, Cl. 83-880.000.
- Licitis, Gunars: See—
Meyer, Burton C.; Licitis, Gunars; and Brand, Derek A., 4,296,929, Cl. 273-310.000.
- Lidik, Albert F.; and Talley, Randall E., III. Can crusher. 4,296,683, Cl. 100-53.000.
- Liland, Alfred L.: See—
Li, Hsin L.; Oswald, Hendrikus J.; and Liland, Alfred L., 4,296,535, Cl. 28-257.000.
- Lincoln-Helios GmbH: See—
Rodemer, Karl, 4,296,777, Cl. 137-351.000.
- Linde Aktiengesellschaft: See—
Schliebener, Claus; and Wernicke, Hans J., 4,297,204, Cl. 208-95.000.
- Lindmayer, Joseph, to Solarex Corporation. Method of applying electrical contacts to a photovoltaic cell. 4,297,391, Cl. 136-256.000.
- Lindner, Christian; Ott, Karl-Heinz; Arnold, Bernhard; Kowitz, Friedrich; Oertel, Harald; and Kuhlmann, Dieter, to Bayer Aktiengesellschaft. ABS-moulding compositions having high notched impact strength. 4,297,446, Cl. 525-66.000.
- Lindner, Christian; Suling, Carlhans; Bartl, Herbert; Schreckenberger, Manfred; Freitag, Dieter; and Konig, Klaus, to Bayer Aktiengesellschaft. Process for the preparation of carbonic acid aryl esters of polyester-diols lengthened via carbonate groups and their use for the preparation of polyester-diol bis-diphenol carbonates and polyester/polycarbonates. 4,297,455, Cl. 525-439.000.
- Lindner, Daniel J.: See—
Roberts, Charles W.; Kolowski, Michael A.; Lindner, Daniel J.; Lynch, John E.; Ruip, Terrence M.; and Fetty, Harold D., 4,296,789, Cl. 152-209.00R.
- Lindstrom, Yrjo V., to Alnor Oy. Method and device for measuring the required cooling capacity of a cold space and the refrigeration capacity of the refrigerating machinery. 4,296,627, Cl. 73-15.00R.
- Lingaraju, Bhartoor, to Square D Company. Pressure lock terminal. 4,296,987, Cl. 339-95.00D.
- Link, Hans; and Dreher, Ulrich, to Institut Dr. Friedrich Forster Prüfgeratebau. Magnet and probe mounting means on a rotating head of magnetic defect testing apparatus. 4,297,636, Cl. 324-262.000.
- Lionelle, Joseph E.; and Staffa, Jeffrey A., to Bio Systems Research, Inc. Method of preparing the methyl ester of α -eleostearic acid. 4,297,291, Cl. 260-410.90R.
- Lippa, Giuseppe, to American Standard Inc. Mold for integral base for casting ceramic material in the form of a slip. 4,296,908, Cl. 249-58.000.
- Liquid Paper Corporation: See—
Ferree, William I., Jr.; and Nguyen, Giao V., 4,297,260, Cl. 260-29.70H.
- List, Hans: See—
Claassen, Peter; List, Helmut; and Zeiringer, Rudolf, 4,296,635, Cl. 73-730.000.
- List, Helmut: See—
Claassen, Peter; List, Helmut; and Zeiringer, Rudolf, 4,296,635, Cl. 73-730.000.
- Little, Donald R., to American Standard Inc. Vital incidental movement monitoring arrangement. 4,297,548, Cl. 200-61.080.
- Little, Jane; and Greene, Del F., to McDonnell Douglas Corporation. Tandem hydraulic actuator. 4,296,677, Cl. 91-510.000.
- Liu, Anh-Thu: See—
Scherzer, Julius; Liu, Anh-Thu; and Sun, Yih-Yau, 4,297,325, Cl. 423-122.000.
- Liu, Hsin. Equipment for treating and resource recovery from solid waste. 4,297,322, Cl. 422-184.000.
- Livigni, Russell A.: See—
Bingham, Robert E.; Durst, Richard R.; Fabris, Hubert J.; Hargis, Ivan G.; Livigni, Russell A.; and Aggarwal, Sundar L., 4,297,240, Cl. 252-431.00R.
- Livingstone, Bryan: See—
Hannah, Stephen J.; and Livingstone, Bryan, 4,297,176, Cl. 204-37.00R.
- Llorach, Alfredo B. Devices to exploit solar energy. 4,296,735, Cl. 126-438.000.
- Lobl, Thomas J.: See—
Babcock, John C.; Campbell, J. Allan; and Lobl, Thomas J., 4,297,350, Cl. 424-238.000.
- LoCascio, James J.; and Jarrett, Robert B., to Motorola Inc. Current mirror circuit. 4,297,646, Cl. 330-288.000.
- Lockheed Corporation: See—
Donham, Robert E.; and Heimbald, Richard L., 4,297,076, Cl. 416-37.000.
- Lockheed Missiles & Space Company, Inc.: See—
Buchanan, Robert A.; Maple, T. Grant; and Sklensky, Alden F., 4,297,584, Cl. 250-483.000.
- Loftis, James B. Drilling apparatus. 4,296,820, Cl. 175-52.000.
- Logan, Ted J.; and Lubsen, Timothy A., to Procter & Gamble Company, The. Fractionation of triglyceride mixtures. 4,297,292, Cl. 260-428.500.
- Lohmer, Karl: See—
Haseler, Helmut; Meckl, Heinz; Lohmer, Karl; and Pelz, Willibald, 4,297,438, Cl. 430-377.000.
- Lohr, Robert. Apparatus for use on vehicle transporters. 4,296,691, Cl. 105-370.000.
- Lok-A-Wat, Inc.: See—
Belles, David E., 4,296,957, Cl. 292-264.000.
- Lok, Brent M. T.; and Izod, Thomas J. P., to Union Carbide Corporation. Aluminum deficient zeolite compositions and process for preparing same. 4,297,335, Cl. 423-328.000.
- Long, William P., Jr., to ICI Americas Inc. Non-yellowing paint formulations containing iodo substituted alkynyl urethanes as fungicides. 4,297,258, Cl. 260-29.6MN.
- Looren de Jong, Hendrikus: See—
Melwisch, Harald; and Looren de Jong, Hendrikus, 4,297,731, Cl. 360-70.000.
- L'Oreal: See—
Vanlerberghe, Guy; and Sebarg, Henry, 4,297,102, Cl. 8-406.000.
- Lorenzini, Robert A. Reed protector for a woodwind instrument. 4,296,668, Cl. 84-383.00R.
- Lorke, Horst: See—
Diery, Helmut; Helwerth, Rainer; Frohlich, Horst; and Lorke, Horst, 4,297,236, Cl. 252-389.00R.

- Los, Marinus, to American Cyanamid Co. Use of imidazolyl benzoates as herbicidal agents. 4,297,128, Cl. 71-92.000.
- Loser, Norbert; and Tilgner, Leopold, to SKF Kugellagerfabriken GmbH. Sliding bearing. 4,296,978, Cl. 308-37.000.
- Love, Phillip W. Self-loading apparatus for transporting large bales of material. 4,297,065, Cl. 414-24.500.
- Lovelace, Reginald B.: See—
Claffy, Richard D.; and Lovelace, Reginald B., 4,296,771, Cl. 137-110.000.
- Low, Teresa L. K.: See—
Goldstein, Allan L.; and Low, Teresa L. K., 4,297,276, Cl. 260-112.50R.
- Lowe, Virgil L. Charged coupled device time base corrector system. 4,297,728, Cl. 360-36.000.
- Lowrey, Robert D.: See—
Chern, Mao-Jin; and Lowrey, Robert D., 4,297,401, Cl. 428-1.000.
- Lubow, Allen. Needle threader. 4,296,877, Cl. 223-99.000.
- Lubsen, Timothy A.: See—
Logan, Ted J.; and Lubsen, Timothy A., 4,297,292, Cl. 260-428.500.
- Lucas Industries Limited: See—
Nicol, Thomas; Wiley, David; and Allport, Maurice J., 4,297,631, Cl. 320-64.000.
- Tregurtha, Steven J.; and Cryer, Edward, 4,297,549, Cl. 200-61.270.
- Luecke, Robert W., to True Temper Corporation. Containment reservoir and method. 4,296,884, Cl. 238-2.000.
- Luerken, Adolf, to McCulloch Corporation. Automatic two-way centrifugal clutch for motor driven apparatus. 4,296,852, Cl. 192-104.00B.
- Luginbuhl, Rolf: See—
Kagi, Bruno; Hirmann, Georg; and Luginbuhl, Rolf, 4,296,774, Cl. 137-322.000.
- Kagi, Bruno; Hirmann, Georg; and Luginbuhl, Rolf, 4,296,775, Cl. 137-322.000.
- Lundgren, Sune I.; and Rehnberg, Leif E. L., to Kemi-Intressen AB. Method and a device for removing corks from vessels. 4,296,653, Cl. 81-3.46R.
- Lutz, Albert W.; and Diehl, Robert E., to American Cyanamid Company. Herbicidal use of 2,6-dinitroaniline herbicides. 4,297,127, Cl. 71-88.000.
- Lutz, Andre: See—
Heymes, Rene; and Lutz, Andre, 4,297,352, Cl. 424-246.000.
- Lyall, Brian: See—
Ward, Herbert J.; Dobbie, Derek J.; and Lyall, Brian, 4,297,415, Cl. 428-516.000.
- Lynch, John E.: See—
Roberts, Charles W.; Kolowski, Michael A.; Lindner, Daniel J.; Lynch, John E.; Ruip, Terrence M.; and Fetty, Harold D., 4,296,789, Cl. 152-209.00R.
- Lynch, Mark: See—
Pallone, Thomas J.; Lynch, Mark; Corvino, Janice E.; and McCook, John P., 4,296,764, Cl. 132-7.000.
- Lynn, Ray E.: See—
Simmons, Dwane P.; and Lynn, Ray E., 4,296,509, Cl. 5-81.00R.
- Lynnworth, Lawrence C.; Fowler, Kenneth A.; and Patch, Dana R., to Panametrics, Inc. Sealed, matched piezoelectric transducer. 4,297,607, Cl. 310-334.000.
- Lyons, David J.: See—
Mezrich, Reuben S.; Colleoni, Alec; and Lyons, David J., 4,297,009, Cl. 352-86.000.
- M & W Gear Company: See—
Meiners, Elmo R., 4,296,595, Cl. 56-341.000.
- Ma, King W., to Dow Chemical Company, The. Method of oxidizing compounds having activated methylene radicals. 4,297,514, Cl. 568-321.000.
- Maahs, Gunther; and Rombusch, Konrad, to Chemische Werke Huels, Aktiengesellschaft. Process for the preparation of pentachloro-3-butenic acid esters. 4,297,505, Cl. 560-219.000.
- Macchiarolo, Nick T.; McGuire, Billy G.; and Sealise, John M., to Great Lakes Chemical Corporation. Method for the control of biofouling in recirculating water systems. 4,297,224, Cl. 210-755.000.
- Mack, Gerhard: See—
Muller, Klaus; and Mack, Gerhard, 4,296,530, Cl. 24-295.000.
- Maeda, Keisuke: See—
Matsumoto, Toshiaki; and Maeda, Keisuke, 4,297,015, Cl. 354-25.000.
- Maegawa, Yuzo; Masuko, Fujio; and Nakamura, Makoto, to Sumitomo Chemical Company, Limited. Process for producing 2-hydroxy-naphthalene-3-carboxylic acid. 4,297,508, Cl. 562-425.000.
- Maeno, Hiroo: See—
Yamamoto, Minoru; Tachikawa, Shiro; and Maeno, Hiroo, 4,297,356, Cl. 424-248.570.
- Magnus, Paul G., to Magnusystem, Inc. Sectional pipe and tubular members for forming same. 4,296,781, Cl. 138-155.000.
- Magnusystem, Inc.: See—
Magnus, Paul G., 4,296,781, Cl. 138-155.000.
- Mai, Wolfgang: See—
Weller, Alois; and Mai, Wolfgang, 4,296,625, Cl. 72-345.000.
- Maier, Hans-Peter: See—
von der Eltz, Hans-Ulrich; Lehinant, Armand; Lehmann, Joachim W.; and Maier, Hans-Peter, 4,297,101, Cl. 8-531.000.
- Maier, Lawrence C., to Simmonds Precision Products, Inc. Segment failure detector for digital display. 4,297,692, Cl. 340-715.000.
- Mainusch, Klaus; Schleppinghoff, Bernhard; and Munter, Klaus, to EC Erdolchemie GmbH. Process for the preparation of triethylamine. 4,297,512, Cl. 564-490.000.
- Makari, Jack G. Malignant tumor immunity level detection. 4,297,338, Cl. 424-9.000.
- Makino, Akira, to Nisshin Oil Mills, Ltd., The. Rapid method for the measurement of iodine value. 4,297,106, Cl. 23-230.0HC.
- Makino, Itsuo: See—
Hirai, Kentaro; Matsutani, Shigeru; Ishiba, Teruyuki; and Makino, Itsuo, 4,297,280, Cl. 260-245.500.
- Makino, Masaharu: See—
Sato, Hisatake; Makino, Masaharu; and Hayashi, Hideo, 4,297,450, Cl. 525-333.000.
- Makofka, Stanley J.: See—
Webb, Bryant F.; Makofka, Stanley J.; Webster, Emmett G.; and Blakeslee, Edward A., 4,296,593, Cl. 56-98.000.
- Malinowski, Leon; and Lange, Kenneth, to Leon's Manufacturing Co., Ltd. Rotary rock picker. 4,296,818, Cl. 171-63.000.
- Mallinckrodt, Inc.: See—
Vittello, John P.; and Grummon, Glenn D., 4,296,785, Cl. 141-105.000.
- Malsot, Christian; and Bouygues, Jean, to Socapex. Device for centering an optical fiber within a terminal, and a terminal constructed by means of said device. 4,296,997, Cl. 350-96.200.
- Maltz, Georg: See—
Leuchs, Ottmar; and Maltz, Georg, 4,297,526, Cl. 174-102.00R.
- Manca, Francesco, to Sna Viscosa Societa Nazionale Industria Applicazioni Viscosa S.p.A. Finish composition for the spinning of highly crimped cellulose fibers using a composition containing fatty acid ester, organic phosphoric acid ester, fatty acid ethylene oxide cond. prod. and fatty acid salt. 4,297,407, Cl. 428-224.000.
- Mandellos, Panagiotis K.: See—
Lauritsen, Richard L.; and Mandellos, Panagiotis K., 4,297,552, Cl. 200-83.00P.
- Manecke, Siegfried E.; and Buckshaw, Thomas M., to Robertshaw Controls Company. Temperature responsive piston and cylinder unit having a heater carried thereby. 4,296,603, Cl. 60-528.000.
- Mango, Frank D., to Shell Oil Company. Process for making 4,4'-methylene diphenyl diisocyanate. 4,297,294, Cl. 260-453.0PH.
- Mangold, Dietrich: See—
Reissenweber, Gernot; and Mangold, Dietrich, 4,297,491, Cl. 544-105.000.
- Mannesmann Aktiengesellschaft: See—
Kolb, Gustav, 4,296,638, Cl. 73-863.210.
- Mannherz, Elmer D., to Fischer & Porter Co. Noise-reducing electrodes for electromagnetic flowmeter. 4,296,636, Cl. 73-861.120.
- Mansfield, Gerald R.; Travis, Karen L.; and Vann, William P., to Corning Glass Works. Solid-phase immunoassays using magnetic glass. 4,297,337, Cl. 424-1.000.
- Manzke, Klaus; Brotzler, Roland; and Schulze-Berge, Klaus, to BASF Aktiengesellschaft. Device for adjusting and fixing detecting means relative to the index mark on a recording disc. 4,297,736, Cl. 360-109.000.
- Maple, T. Grant: See—
Buchanan, Robert A.; Maple, T. Grant; and Sklensky, Alden F., 4,297,584, Cl. 250-483.000.
- Marchelli, Francesco: See—
Sbuelz, Anes; and Marchelli, Francesco, 4,297,649, Cl. 331-2.000.
- Marer, Joseph, to Redon Trust. Remote control device for activating or inactivating a pneumatic war mine. 4,296,686, Cl. 102-427.000.
- Markfelder, Gunther: See—
Hofmann, Heinrich; and Markfelder, Gunther, 4,296,979, Cl. 308-174.000.
- Markham, Harvey R.: See—
Bach, Paul S.; Harding, Steven R.; Lamos, Richard A.; Markham, Harvey R.; and Shepherd, Roger D., 4,297,025, Cl. 355-14.0SH.
- Marko Materials, Inc.: See—
Giessen, Bill C.; Polk, Donald E.; and Ray, Ranjan, 4,297,135, Cl. 75-123.00B.
- Marks, Helmut: See—
Moll, Hans-Georg; Hasselbarth, Ulrich; Grohmann, Andreas; and Marks, Helmut, 4,297,221, Cl. 210-702.000.
- Marlin Firearms Company, The: See—
Oberst, E. Ernest, 4,296,564, Cl. 42-1.00C.
- Marom, Emanuel; Barnoski, Michael K.; and Abrams, Richard L., to Hughes Aircraft Company. Phase sensitive spectrum analyzer. 4,297,704, Cl. 343-113.00R.
- Marquart, Gordon L., to Deere & Company. Hydraulically operated transmission control. 4,296,649, Cl. 74-751.000.
- Marsden, Robert S., to Imperial Chemical Industries Limited. Preparation of solutions of basic aluminium nitrate. 4,297,336, Cl. 423-395.000.
- Marsh, Walter H. W.: See—
Davidson, Donald R.; and Marsh, Walter H. W., 4,296,698, Cl. 112-110.000.
- Marshall, Don J., to Goodall Semi-Metallic Hose & Mfg. Co. Variable pitch marine propeller. 4,297,079, Cl. 416-140.000.
- Marshall, Richard C., to Xerox Corporation. Electrochromic display device. 4,297,695, Cl. 340-752.000.
- Martenas, Wayne B.; Priepke, Edward H.; and Wagstaff, Robert A., to Sperry Corporation. Damped apparatus for quick-stopping rotating members. 4,296,591, Cl. 56-10.300.
- Martens, Gerhard, to Barmag Barmer Maschinenfabrik Aktiengesellschaft. Method and apparatus for winding textile yarns. 4,296,889, Cl. 242-18.100.
- Martin, Alfred C., to Westland Aircraft Limited. Helicopter rotors. 4,297,078, Cl. 416-134.00A.
- Martin, Anthony N., to Otis Elevator Company. Electronic fuel control system. 4,296,601, Cl. 60-224.000.

- Martin, Charles L., to Raychem Corporation. Composite coupling device with high recovery driver. 4,296,955, Cl. 285-381.000.
- Martin Marietta Corporation: See—
Perz, John S., 4,297,399, Cl. 427-385.500.
- Martin, William L.: See—
Stalder, John L.; and Martin, William L., 4,296,814, Cl. 166-303.000.
- Marui Industry Co., Ltd.: See—
Takeguchi, Masanobu; and Oyobe, Isao, 4,297,222, Cl. 210-748.000.
- Marvin Glass & Associates: See—
Erickson, Erick E.; Katzman, Allison W.; and Breslow, Jeffrey D., 4,297,153, Cl. 156-63.000.
- Meyer, Burton C.; Licitis, Gunars; and Brand, Derek A., 4,296,929, Cl. 273-310.000.
- Maryland Cup Corporation: See—
Stokkers, Henk, 4,296,863, Cl. 206-504.000.
- Maschinenfabrik Carl Zangs Aktiengesellschaft: See—
Kremer, Hubert, 4,296,782, Cl. 139-65.000.
- Mascitti, Albert A.: See—
Sulkowski, Theodore S.; Bergey, James L.; and Mascitti, Albert A., 4,297,373, Cl. 424-322.000.
- Mason, Stanley I., Jr.; and Handler, Michael D., to Surgikos. Disposable full-face surgical mask. 4,296,746, Cl. 128-201.150.
- Massa, Frank, to Stoneleigh Trust, The, Fred M. Dellorfano, Jr. and Donald P. Massa, Trustees. Resonant electroacoustic transducer with increased band width response. 4,297,538, Cl. 179-180.000.
- Massuard, Claude: See—
Appell, Marc; Bogaert, Jean-Louis; Massuard, Claude; Bradley, John; and Franklin, Benjamin S., 4,297,743, Cl. 364-200.000.
- Mast, Harm, to Shell Oil Company. System for detecting particles carried by a fluid flow. 4,296,628, Cl. 73-28.000.
- Masuda, Hirotugu: See—
Uruta, Hisanari; Takahashi, Kaneaki; Masuda, Hirotugu; and Kurata, Tomoyuki, 4,296,705, Cl. 114-219.000.
- Masuda, Tatsunosuke; Ono, Yoshio; and Sakamoto, Seiya, to Dainippon Screen Seizo Kabushiki Kaisha; and Takara Belmont Co., Ltd. Method and machine for trying on a hair form in image. 4,297,724, Cl. 358-93.000.
- Masuko, Fujio: See—
Maegawa, Yuzo; Masuko, Fujio; and Nakamura, Makoto, 4,297,508, Cl. 562-425.000.
- Matherat, Philippe, to Thomson-CSF. Symbol generator for a graphic console. 4,297,694, Cl. 340-750.000.
- Matsumoto, Hisashi, to Mitsui Petrochemical Industries, Ltd. Reinforcing material for hydraulic substances and method for the production thereof. 4,297,414, Cl. 428-400.000.
- Matsumoto, Mitsuo: See—
Tani, Masayuki; Okui, Mitsuhiko; and Matsumoto, Mitsuo, 4,296,597, Cl. 57-205.000.
- Matsumoto, Shinichi: See—
Shinohara, Hiroshi; Otsuka, Yasuhiro; Matsumoto, Shinichi; Wakisaka, Hiroshi; and Furutani, Toshinobu, 4,297,192, Cl. 204-195.000.
- Matsumoto, Toshiaki; and Maeda, Keisuke, to Minolta Camera Kabushiki Kaisha. Camera automatic focus apparatus. 4,297,015, Cl. 354-25.000.
- Matsunaga, Hirokazu: See—
Ando, Kazunari; Matsunaga, Hirokazu; and Ayabe, Hideaki, 4,297,714, Cl. 346-139.000.
- Matsuo, Munetsugu: See—
Sakurai, Koichi; Furukawa, Takashi; Takechi, Hiroshi; and Matsuo, Munetsugu, 4,296,919, Cl. 266-111.000.
- Matsuoka, Hideaki; and Kondo, Yoshinobu, to Nissan Motor Company, Limited; and Fuji Kiko Co., Ltd.. Covering construction of a guide rail. 4,296,944, Cl. 280-80.000.
- Matsushima, Hiroaki: See—
Kato, Makoto; Ueda, Nobuo; and Matsushima, Hiroaki, 4,297,166, Cl. 376-194.000.
- Matsushita Electric Industrial Co., Ltd.: See—
Hamane, Tokuhito; Kinoshita, Toshio; and Kihira, Masafumi, 4,296,543, Cl. 29-596.000.
- Hino, Tsuneco; and Onishi, Masao, 4,297,609, Cl. 310-339.000.
- Matsutani, Shigeru: See—
Hirai, Keitaro; Matsutani, Shigeru; Ishiba, Teruyuki; and Makino, Itsuo, 4,297,280, Cl. 260-245.500.
- Mattel, Inc.: See—
Buck, Gordon H., and Hardwick, Martha K., 4,296,926, Cl. 273-86.000.
- Matthews, Gerald H.: See—
Debona, Edward J.; Neblett, Boyd L.; Krueger, Walter J.; Laird, William J.; Campbell, Billy H.; and Matthews, Gerald H., 4,296,669, Cl. 89-1.816.
- Matthijse, Matthijs, to U.S. Philips Corporation. Device having a balanced pivotable arm. 4,296,906, Cl. 248-280.100.
- Mattsson, Karl-Erik H., to AB Volvo. Cylinder with two-stage movement, especially a welding cylinder. 4,296,679, Cl. 92-52.000.
- Maul, Rudolf: See—
Abeler, Gerd; and Maul, Rudolf, 4,297,268, Cl. 260-45.80N.
- Maulding, Hawkins V., to Sandoz, Inc. Non-irritating injectable dosage forms. 4,297,353, Cl. 424-247.000.
- May, James I., to Ford Motor Company. Rack and pinion gear bearing support. 4,296,641, Cl. 74-422.000.
- Mayer, George: See—
Kowalski, George A.; Mayer, George; and Rosenbaum, Murray, 4,297,570, Cl. 235-493.000.
- McCarty, Frederick B.: See—
Burgmeier, Lyman R.; McCarty, Frederick B.; and Silver, Alexander, 4,296,544, Cl. 29-598.000.
- McClinton, John L., to Burns and Russell Company, The. Pigment package. 4,296,859, Cl. 206-219.000.
- McConomy, Thomas A.; and Wells, Bruce D., to Calgon Corporation. Process for removing color bodies from brown phosphoric acid. 4,297,334, Cl. 423-321.00R.
- McCook, John P.: See—
Pallone, Thomas J.; Lynch, Mark; Corvino, Janice E.; and McCook, John P., 4,296,764, Cl. 132-7.000.
- McCracken, Donald G., to Aeroquip Corporation. Rotary joint. 4,296,952, Cl. 285-98.000.
- McCreary, James L.: See—
Baldwin, Gary L.; and McCreary, James L., 4,297,642, Cl. 330-9.000.
- McCreary, James F.: See—
Armbrust, William D.; and McCreary, James F., 4,297,058, Cl. 407-113.000.
- McCulloch Corporation: See—
Luerken, Adolf, 4,296,852, Cl. 192-104.00B.
- McCutchan, John C.; and Niven, Rex C., to University of Melbourne, The. Electric fence monitoring system with energizer, responder and receiver. 4,297,633, Cl. 324-51.000.
- McDaniel, Max P.; and Welch, Melvin B., to Phillips Petroleum Co. Treatment of silica. 4,297,460, Cl. 526-98.000.
- McDonald, Charles J., to Dow Chemical Company, The. Preparation of water-immiscible, acid-soluble N-(aminomethyl)- α,β -ethylenically unsaturated carboxamides, quaternary derivatives and polymers thereof. 4,297,256, Cl. 260-29.4UA.
- McDonnell Douglas Corporation: See—
Little, Jane; and Greene, Del F., 4,296,677, Cl. 91-510.000.
- McGill, Roy F. Turnbuckle. 4,297,046, Cl. 403-46.000.
- McGowan, Peter T., to Garrett Corporation, The. Fluid motor-pump unit. 4,297,086, Cl. 417-271.000.
- McGrath, Gilbert T.: See—
McGrath, Lindsay T.; and McGrath, Gilbert T., 4,296,922, Cl. 269-211.000.
- McGrath, Lindsay T.; and McGrath, Gilbert T. Bench clamp device. 4,296,922, Cl. 269-211.000.
- McGuire, Billy G.: See—
Macchiarolo, Nick T.; McGuire, Billy G.; and Scalise, John M., 4,297,224, Cl. 210-755.000.
- McIlwain, Irvin D., to Sperry Corporation. Auger floatation limit. 4,296,592, Cl. 56-14.400.
- McKenny, Vernon C.; and Chan, Tsiu C., to Mostek Corporation. Extremely low current load device for integrated circuit. 4,297,721, Cl. 357-59.000.
- Mead Corporation, The: See—
Clement, Joseph, 4,296,563, Cl. 40-518.000.
- Spatz, Sydney M.; Hydel, Robert C.; and Davis, Gerald T., 4,296,947, Cl. 282-27.500.
- Mead, John F., to Plessey Handel und Investments AG. Optical fibre connectors. 4,296,999, Cl. 350-96.210.
- Mead Johnson & Company: See—
Lawson, John E.; and Dennis, Ronald D., 4,297,498, Cl. 546-116.000.
- Mears, James W., to Grinnell Fire Protection Systems Company, Inc. Deflector with converging lower tines for horizontal sprinkler. 4,296,815, Cl. 169-37.000.
- Meatabi, Tsuneyo, to Minolta Camera Kabushiki Kaisha. Arrangement of cylinder elements for a lens barrel. 4,297,002, Cl. 350-255.000.
- Mechanical Technology Incorporated: See—
Heshmat, Hooshang, 4,296,976, Cl. 308-9.000.
- Meckl, Heinz: See—
Haseler, Helmut; Meckl, Heinz; Lohmer, Karl; and Pelz, Willibald, 4,297,438, Cl. 430-377.000.
- Meckler, Milton. Modular solar insulation panels. 4,296,740, Cl. 126-448.000.
- Meier, Willi; and Rojahn, Bernd, to Dorina Nahmaschinen GmbH. Storage compartment for sewing machine foot controller. 4,296,702, Cl. 112-258.000.
- Meiners, Elmo R., to M & W Gear Company. Apparatus for wrapping a cover material around round bales. 4,296,595, Cl. 56-341.000.
- Meito Co. Ltd.: See—
Kinbara, Koichi; Sugimoto, Norimaro; and Nakazawa, Toshitaka, 4,297,402, Cl. 428-35.000.
- Meitzner, Erich F.; and Oline, James A., to Rohm and Haas Company. Macroreticulated copolymer adsorption process. 4,297,220, Cl. 210-690.000.
- Mejdell, Gior T.; Palmgren, Odd E.; Talmoen, Arne; and Vik, Bjarne, to Norsk Hydro a.s. Process for reducing the vinyl chloride content of aqueous dispersions of vinyl chloride polymers. 4,297,483, Cl. 528-500.000.
- Melwisch, Harald; and Looren de Jong, Hendrikus, to U.S. Philips Corporation. Playback apparatus for correcting locking errors. 4,297,731, Cl. 360-70.000.
- Menault, Jacques: See—
Achard, Georges; Chion, Pierre; and Menault, Jacques, 4,297,412, Cl. 428-370.000.
- Mengoli, Guilio: See—
Daolio, Sergio; Mengoli, Guilio; Folonari, Carlo; and Musiani, Marco, 4,297,188, Cl. 204-181.00R.
- Mercer, Albert E. Adjustable angled socket wrench extension. 4,296,654, Cl. 81-57.260.

- Merck & Co., Inc.: See—
Christensen, Burton G.; Cama, Lovji D.; Karady, Sandor; and Sletzing, Meyer, 4,297,488, Cl. 544-21.000.
- Merck Patent Gesellschaft mit Beschränkter Haftung: See—
Eidenschink, Rudolf; and Pohl, Ludwig, 4,297,515, Cl. 568-329.000.
- Vormbrock, Rolf; and Helger, Roland, 4,297,238, Cl. 252-408.000.
- Merrick, George J.: See—
Wolfe, Donald L.; Modglin, Donald D.; and Merrick, George J., 4,297,061, Cl. 409-131.000.
- Merten, Helmut L.; and Wilder, Gene R., to Monsanto Company. N,N'-Bis(1-cyclohexyl-1-ethyl)-p-phenylenediamine, and rubber compounds containing the same. 4,297,269, Cl. 260-45.9QB.
- Merten, Richard C., to Jubilee Manufacturing Co. Passive security device. 4,297,674, Cl. 340-63.000.
- Messerschmitt-Bölkow-Blom GmbH: See—
Schnabele, Werner; Buckley, Jack; and Rieger, Ulrich, 4,296,894, Cl. 244-3.270.
- Mesur-Matic Electronics Corporation: See—
Newell, Harold R., 4,297,625, Cl. 318-696.000.
- Metallgesellschaft AG: See—
Schlauer, Johann; Kempf, Georg; and Doerges, Alexander, 4,297,330, Cl. 423-232.000.
- Metcalfe, John L.; and Wraige, Douglas, to Lever Brothers Company. Product for treating fabric. 4,297,406, Cl. 428-215.000.
- Metzeler Kautschuk GmbH: See—
Blahak, Johannes, 4,297,442, Cl. 521-107.000.
- Meyer, Burton C.; Licitis, Gunars; and Brand, Derek A., to Marvin Glass & Associates. Electric eye actuated gun arcade. 4,296,929, Cl. 273-310.000.
- Meyer, G. Robert: See—
Reed, Ronald R.; Crone, William F., Jr.; and Meyer, G. Robert, 4,296,662, Cl. 83-880.000.
- Meyer, Gunther: See—
Herrmann, Hans-Joachim; Meyer, Gunther; and Steffen, Klaus-Dieter, 4,297,502, Cl. 560-35.000.
- Mezrich, Reuben S.; Colleoni, Alec; and Lyons, David J., to Technicare Corporation. Image storage and display. 4,297,009, Cl. 352-86.000.
- Michalski, Gunter: See—
Hoffken, Erich; Kleins-Kleffmann, Werner; Bertram, Rolf; Abele, Karl-Heinz; and Michalski, Gunter, 4,297,151, Cl. 148-9.00R.
- Michelet, Daniel, to Rhone-Poulenc Agrochimie. Preparation of 2,3-dihydro-2,2-dimethyl-7-hydroxybenzofuran. 4,297,284, Cl. 260-346.220.
- Micro-Burner Systems Corporation: See—
Bryan, Edward L., 4,296,727, Cl. 126-116.00A.
- Midland-Ross Corporation: See—
Goron, John, 4,297,092, Cl. 425-133.100.
- Mieville, Rodney L., to Standard Oil Company (Indiana). Reforming with a catalyst comprising iridium, zirconia, and alumina. 4,297,205, Cl. 208-138.000.
- Miki, Tosaku; and Asano, Masahide, to Daiichi Seiyaku Co., Ltd. N-Phenethylacetamide compounds and process for preparation thereof. 4,297,357, Cl. 424-251.000.
- Miles Laboratories, Inc.: See—
Buckler, Robert T.; and Schroeder, Hartmut R., 4,297,273, Cl. 260-112.00B.
- Miller, John G.; and Schwab, Thomas C., to Engelhard Minerals & Chemicals Corporation. Processing of titaniferous materials. 4,297,131, Cl. 75-1.00T.
- Miller, Kirk D.; Flood, John B.; Dimou, George; Kara, Frederick E.; and Amos, Richard W., to Canron Inc. Molten metal treatment. 4,296,920, Cl. 266-216.000.
- Miller, Robert G.: See—
Heitzman, Gary N.; Hutchings, Clay L.; Knepp, Gary L.; and Miller, Robert G., 4,297,742, Cl. 361-154.000.
- Ministry of International Trade & Industry: See—
Shimizu, Ken-Ichi; and Ikeya, Chuji, 4,297,725, Cl. 358-125.000.
- Minnesota Mining & Manufacturing Company: See—
Chern, Mao-Jin; and Lowrey, Robert D., 4,297,401, Cl. 428-1.000.
- Huck, William V., 4,296,857, Cl. 206-53.000.
- Larson, Roderick W.; and Whaley, Ralph D., 4,296,989, Cl. 339-99.00R.
- Minolta Camera Kabushiki Kaisha: See—
Matsumoto, Toshiaki; and Maeda, Keisuke, 4,297,015, Cl. 354-25.000.
- Meatabi, Tsuneyo, 4,297,002, Cl. 350-255.000.
- Nakai, Masaaki, 4,297,012, Cl. 354-23.00D.
- Miracle Recreation Equipment Company: See—
Ahrens, Paul W., 4,296,923, Cl. 272-85.000.
- Misaka, Takaaki; Furukawa, Takeshi; and Onuma, Eiichi, to Onoda Cement Co., Ltd. Air classifier. 4,296,864, Cl. 209-144.000.
- Mise, Yoshinari; and Tomimura, Eihiro, to CPC International Inc. Method for the production of powdered dextrose. 4,297,146, Cl. 127-60.000.
- Mitchell, Robert P.; and Scalera, Frank T., to Rowe International, Inc. Delivery box assembly for merchandising machine. 4,296,872, Cl. 221-195.000.
- MITEC-Moderne-Industrietechnik GmbH: See—
Chaborski, Hoiko, 4,297,030, Cl. 356-5.000.
- Mitsubishi Gas Chemical Co. Inc.: See—
Komatsu, Makoto; Takamizawa, Yuji; and Ohta, Tazuo, 4,297,507, Cl. 562-416.000.
- Mitsubishi Jukogyo Kabushiki Kaisha: See—
Tanai, Atsushi; and Okino, Susumu, 4,297,332, Cl. 423-240.000.
- Mitsubishi Paper Mills, Ltd.: See—
Kanada, Eiji; Yamada, Shoji; and Tsubai, Yasuo, 4,297,429, Cl. 430-204.000.
- Kanada, Eiji; Yamada, Shoji; and Tsubai, Yasuo, 4,297,430, Cl. 430-204.000.
- Satoh, Tsutomu; Ohye, Hideo; Tsukahara, Hirokazu; Senoh, Hideaki; and Torii, Takahiro, 4,296,948, Cl. 282-27.500.
- Mitsubishi Petrochemical Co., Ltd.: See—
Akutsu, Susumu; Isaka, Tsutomu; and Ishioka, Mitsugu, 4,297,310, Cl. 264-83.000.
- Mitsubishi Belting Ltd.: See—
Nosaka, Soukichi, 4,296,640, Cl. 474-262.000.
- Mitsui Mining & Smelting Co., Ltd.: See—
Kasahara, Nobuyoshi; and Nonomura, Koutaro, 4,297,405, Cl. 428-141.000.
- Mitsui Petrochemical Industries, Ltd.: See—
Matsumoto, Hisashi, 4,297,414, Cl. 428-400.000.
- Mitsui Toatsu Chemicals Inc.: See—
Miyamoto, Kinzo; Tanaka, Takayasu; and Inoue, Yoshimi, 4,297,263, Cl. 260-32.6PQ.
- Mitsui, Yoshihiro, to Kabushiki Kaisha Suwa Seikosha. Power supply method for liquid crystal display. 4,297,697, Cl. 340-813.000.
- Miyagawa, Yoshitaka: See—
Sato, Makoto; Takamatsu, Hiroshi; Miyagawa, Yoshitaka; and Fujii, Etsuo, 4,296,972, Cl. 303-119.000.
- Miyamoto, Kinzo; Tanaka, Takayasu; and Inoue, Yoshimi, to Mitsui Toatsu Chemicals Inc.; and Kabushiki Kaisha Asahi Shinbunsha. Method of making polypropylene printing plate using paper matrix. 4,297,263, Cl. 260-32.6PQ.
- Miyamoto, Yukihiko: See—
Wada, Takeshi; Kominami, Yasuo; Miyamoto, Yukihiko; and Yamada, Tsuneco, 4,297,601, Cl. 307-555.000.
- Miyana, Masaaki. Apparatus for forming holes in plate glass. 4,297,059, Cl. 408-202.000.
- Mizutani, Hiroshi: See—
Tsuchiya, Yoshimi; Sagae, Masayuki; and Mizutani, Hiroshi, 4,297,410, Cl. 428-283.000.
- Mizutani, Masato: See—
Sanemitsu, Yuzuru; Mizutani, Masato; Sumida, Seizo; Katoh, Haruhiko; Oshio, Hiromichi; and Hashimoto, Shunichi, 4,297,129, Cl. 71-93.000.
- Mobay Chemical Corporation: See—
Heiss, Herbert L., 4,297,472, Cl. 528-84.000.
- Mobil Oil Corporation: See—
Weiner, Milton L., 4,297,411, Cl. 428-347.000.
- Modglin, Donald D.: See—
Wolfe, Donald L.; Modglin, Donald D.; and Merrick, George J., 4,297,061, Cl. 409-131.000.
- Molin, Bengt T.: See—
Cassel, Knut E.; and Molin, Bengt T., 4,297,709, Cl. 343-754.000.
- Moll, Hans-Georg; Hasselbarth, Ulrich; Grohmann, Andreas; and Marks, Helmut. Process and apparatus for the treatment of untreated water. 4,297,221, Cl. 210-702.000.
- Mollet, Hans: See—
Koci, Zdenek; and Mollet, Hans, 4,297,100, Cl. 8-527.000.
- Monarch Marking Systems, Inc.: See—
Smith, Thomas M., 4,297,403, Cl. 428-42.000.
- Monroe, William E., to Bendix Corporation, The. Quick take-up brake booster. 4,296,674, Cl. 91-391.00R.
- Monsanto Company: See—
Coran, Aubert Y.; and Patel, Raman, 4,297,453, Cl. 525-408.000.
- Merten, Helmut L.; and Wilder, Gene R., 4,297,269, Cl. 260-45.9QB.
- Monte, Anthony J., to United States of America, Army. Fire suppression system for military tanks. 4,296,817, Cl. 169-62.000.
- Monties, Jean R.; and Havlik, Patrick J. C., to Agence Nationale de valorisation de la Recherche (ANVAR). Artificial heart. 4,296,500, Cl. 3-1.700.
- Mooi, John, to Atlantic Richfield Company. Catalyst and process for conversion of hydrocarbons. 4,297,244, Cl. 252-455.00Z.
- Moore, William P., Jr. Method for increasing the number of pods in legumes by foliar feeding. 4,297,130, Cl. 71-119.000.
- Moore, Zack J., to Dow Chemical Company, The. Apparatus for measuring the electric charge condition of non-conductive particles in a mildly conductive electrolyte. 4,297,640, Cl. 324-458.000.
- Moorehead, Eric L., to Union Oil Company of California. Molybdenum-exchanged crystalline aluminosilicate zeolite. 4,297,243, Cl. 252-455.00Z.
- Moran, Malachy J. Bathtub for invalids. 4,296,508, Cl. 4-540.000.
- Moretto, Hans-Heinrich: See—
Finke, Ulrich; and Moretto, Hans-Heinrich, 4,297,500, Cl. 556-466.000.
- Moriarty, William L.: See—
Fletcher, Augustus; and Moriarty, William L., 4,297,177, Cl. 204-43.00N.
- Morier, Elisabeth: See—
Rips, Richard; and Morier, Elisabeth, 4,297,346, Cl. 424-177.000.
- Morimoto, Kotaro; and Suzuki, Tomio, to Kobe Steel, Ltd. Combustion method for reducing NOx and smoke emission. 4,297,093, Cl. 431-10.000.
- Morimoto, Takeshi: See—
Oda, Yoshio; Morimoto, Takeshi; and Suzuki, Kohji, 4,297,182, Cl. 204-98.000.
- Moriya, Shigeru; Hamamoto, Nobuo; Ichino, Kazuo; and Ozawa, Kanji, to Hitachi, Ltd. Mark signal amplifier. 4,297,676, Cl. 340-146.3AG.

- Morley, Michael J.: See—
Bloyce, Lionel T.; and Morley, Michael J., 4,296,886, Cl. 239-264.000.
- Morris, Charles W.; and Terry, Ronald E., to Phillips Petroleum Company. Method for permeability correction by in situ genesis of macro-emulsions in hard brine. 4,296,811, Cl. 166-273.000.
- Morse, Leroy R.: See—
Brezinski, Donald P.; and Morse, Leroy R., 4,297,193, Cl. 204-195.00G.
- Moschter, Erwin: See—
Simon, Manfred; Moschter, Erwin; Spiess, Karl-Heinz; and Weiss, Richard, 4,297,099, Cl. 8-484.000.
- Moser, Theodore E.: See—
Fowler, James C.; Hale, Steven D.; and Moser, Theodore E., 4,297,699, Cl. 343-5.0NA.
- Mostek Corporation: See—
McKenny, Vernon C.; and Chan, Tsui C., 4,297,721, Cl. 357-59.000.
- Motorola, Inc.: See—
Allen, Gordon H., 4,297,593, Cl. 307-247.00R.
Eckert, Kim, 4,297,596, Cl. 307-279.000.
LoCascio, James J.; and Jarrett, Robert B., 4,297,646, Cl. 330-288.000.
- Mower, Peter, to Trico Products Corporation. Wiper blades. 4,296,521, Cl. 15-250.320.
- Mucke, Bruno: See—
Bergthaller, Peter; Saleck, Wilhelm; Lapp, Otto; and Mucke, Bruno, 4,297,439, Cl. 430-434.000.
- Muehlbauer, Otto: See—
Roesler, Helmut; and Muehlbauer, Otto, 4,297,591, Cl. 307-224.00C.
- Mueller, Richard A., to G. D. Searle & Co. Phosphonium salts. 4,297,487, Cl. 542-412.000.
- Muettteries, Andrew J.; Vcelka, John L.; and Kelsey, Wayne R., to Abbott Laboratories. Rotatable connecting device for I.V. administration set. 4,296,949, Cl. 285-18.000.
- Mukhin, Vladislav N.: See—
Berkhin, Josef M.; Gudze, Robert A.; Kekalo, Vasily I.; Panasenko, Nikolai N.; Podbeltsev, Viktor I.; Tsykina, Zinaida D.; and Mukhin, Vladislav N., 4,296,867, Cl. 212-229.000.
- Muller, Friedemann: See—
Eicher, Theobald; and Muller, Friedemann, 4,296,762, Cl. 131-359.000.
- Muller, Klaus; and Mack, Gerhard, to Raymond, A. Clamp for trim strip. 4,296,530, Cl. 24-295.000.
- Muller, Rudolf; Lengsfeld, Franz; and Uerlichs, Johannes, to Hermann Rappold & Co. GmbH. Gate valve for use in large size conduits. 4,296,776, Cl. 137-340.000.
- Mullersman, Ferdinand H., to General Electric Company. Timed fast charger. 4,297,630, Cl. 320-35.000.
- Multivac Sepp Hagenmuller KG: See—
Vetter, Artur, 4,296,588, Cl. 53-86.000.
- Munch, Walter: See—
Wade, David R.; and Munch, Walter, 4,296,667, Cl. 84-345.000.
- Mundt, Randall S.; Wooldridge, Timothy A.; and Blasingame, Thomas O., to Texas Instruments Incorporated. Plasma etching using improved electrode. 4,297,162, Cl. 156-643.000.
- Munter, Klaus: See—
Mainusch, Klaus; Schleppinghoff, Bernhard; and Munter, Klaus, 4,297,512, Cl. 564-490.000.
- Murakami, Hiroyasu; Ito, Tadashi; and Ito, Fumio, to Canon Kabushiki Kaisha. Printed circuit unit for a camera. 4,297,018, Cl. 354-50.000.
- Murata Manufacturing Co., Ltd.: See—
Ieki, Hideharu; and Arai, Seichi, 4,297,660, Cl. 333-194.000.
- Murphy, Frank H.: See—
Seymour, Raymond K.; and Murphy, Frank H., 4,297,663, Cl. 335-20.000.
- Musiani, Marco: See—
Daolio, Sergio; Mengoli, Giuliano; Folonari, Carlo; and Musiani, Marco, 4,297,188, Cl. 204-181.00R.
- Muto, Naoki: See—
Fujii, Tadashi; Sato, Shuzo; Muto, Naoki; Hayashi, Mitsuo; Kodama, Akira; and Otani, Masaru, 4,297,486, Cl. 536-17.00R.
- Myers, Ronald W.: See—
Hughes, Donald W. K.; and Myers, Ronald W., 4,296,991, Cl. 339-176.00P.
- Nagahama, Tsutomu; and Ishihara, Michio, to Fujitsu Limited. Ceramic package for semiconductor devices having metalized lead patterns formed like a floating island. 4,297,722, Cl. 357-74.000.
- Nagahara, Yasumori: See—
Tani, Tatsu; Nagahara, Yasumori; Ohta, Sakae; Suzuki, Minoru; and Hashizume, Kiyozo, 4,297,021, Cl. 355-3.00R.
- Nagano, Kenji, to Osakasanko Kabushiki Kaisha; and Kabushiki Kaisha Taiyohatsujyo Seisakusho. Clamp for flexible hoses. 4,296,534, Cl. 24-270.000.
- Nagao, Shozo; Ohashi, Yoshinobu; Watanabe, Yuichi; and Wakushima, Yoshikazu, to Kubota, Ltd. Slipping-off preventing pipe joint. 4,296,953, Cl. 285-302.000.
- Nagata, Shoji: See—
Ohashi, Naohito; Nagata, Shoji; and Katsube, Junki, 4,297,282, Cl. 260-326.200.
- Nagoshi, Mitsuru, to Konishiroku Photo Industry Co., Ltd. Electro-photographic copying apparatus. 4,297,023, Cl. 355-8.000.
- Naito, Masayuki: See—
Seki, Yashiro; Kobayashi, Hideo; Kimura, Kiyoshi; and Naito, Masayuki, 4,297,028, Cl. 355-41.000.
- Nakagawa, Yasutsugu: See—
Yagi, Michio; Nakajima, Kunio; Nakagawa, Yasutsugu; Ishii, Sizuo; and Aratame, Kazuhisa, 4,297,019, Cl. 354-171.000.
- Nakahara, James H.: See—
Paciorek, Kazimiera J. L.; Kratzer, Reinhold H.; Ito, Thomas I.; and Nakahara, James H., 4,297,510, Cl. 564-13.000.
- Nakai, Masaaki, to Minolta Camera Kabushiki Kaisha. Exposure control arrangement for photographic cameras. 4,297,012, Cl. 354-23.00D.
- Nakajima, Kunio: See—
Yagi, Michio; Nakajima, Kunio; Nakagawa, Yasutsugu; Ishii, Sizuo; and Aratame, Kazuhisa, 4,297,019, Cl. 354-171.000.
- Nakajima, Yosuke: See—
Higashi, Akio; Kawaziri, Kazuhiro; and Nakajima, Yosuke, 4,297,392, Cl. 427-75.000.
- Nakamura, Kazuo; Jyojiki, Masao; and Aoki, Harumi, to Asahi Kogaku Kogyo Kabushiki Kaisha. Camera focus detecting device. 4,297,014, Cl. 354-25.000.
- Nakamura, Ken; Ofuji, Hiromichi; and Yokoyama, Junichi, to Nissan Motor Company, Limited. Butterfly throttle valve with a raised upper lip. 4,297,302, Cl. 261-65.000.
- Nakamura, Makoto: See—
Maegawa, Yuzo; Masuko, Fujio; and Nakamura, Makoto, 4,297,508, Cl. 562-425.000.
- Nakamura, Yoichi: See—
Tsuda, Minoru; and Nakamura, Yoichi, 4,297,433, Cl. 430-270.000.
- Nakanishi, Eiji: See—
Yasuda, Naohiko; and Nakanishi, Eiji, 4,297,279, Cl. 260-239.100.
- Nakanishi, Kiyoshi; Okumura, Takeshi; Deguchi, Ryuichi; and Tanahashi, Toshio, to Toyota Jidosha Kogyo Kabushiki Kaisha. Combustion chamber of an internal combustion engine. 4,296,720, Cl. 123-309.000.
- Nakaoji, Kozo, to Daiwa Chemical Company Ltd. Process for preparing anisaldehyde. 4,297,520, Cl. 568-426.000.
- Nakata, Minoru; Sato, Haruyo; and Imamura, Shinzo, to Toray Industries, Incorporated. Polyamide having —NH—(CH₂)₄—CH(NRR')—CO—units. 4,297,477, Cl. 528-323.000.
- Nakatsuji, Tadao: See—
Abe, Kazunobu; Nakatsuji, Tadao; and Umaba, Toshikatsu, 4,297,248, Cl. 252-477.00R.
- Nakazato, Hiroshi, to Akebono Brake Industry Co., Ltd. Antiskid device. 4,296,971, Cl. 303-115.000.
- Nakazawa, Toshitaka: See—
Kinbara, Koichi; Sugimoto, Norimaro; and Nakazawa, Toshitaka, 4,297,402, Cl. 428-35.000.
- Nanjo, Motoyuki: See—
Koshibe, Shigeru; and Nanjo, Motoyuki, 4,297,473, Cl. 528-144.000.
- Nanya, Takanori: See—
Nishimura, Katsuo; and Nanya, Takanori, 4,297,004, Cl. 350-336.000.
- Narahara, Toshikazu: See—
Koyama, Tohru; Narahara, Toshikazu; and Aimono, Yuji, 4,297,471, Cl. 526-328.000.
- Nard, Georges; Rabian, Jean; and Rouaud, Michel, to Societe d'Etudes, Recherches et Constructions Electroniques Sercl. Method and apparatus for measuring distances. 4,297,700, Cl. 343-6.50R.
- Nariai, Hiroshi: See—
Ito, Kunimoto; Kakizawa, Tsutomu; Yonetani, Kengo; and Nariai, Hiroshi, 4,297,610, Cl. 310-370.000.
- National Mine Service Company: See—
Freed, Donald L., Jr., 4,296,856, Cl. 198-514.000.
- National Petro Chemicals Corp.: See—
Specia, Anthony N., 4,297,461, Cl. 526-100.000.
- National Research Development Corporation: See—
Hannah, Stephen J.; and Livingstone, Bryan, 4,297,176, Cl. 204-37.00R.
- National Starch and Chemical Corporation: See—
Tessler, Martin M., 4,297,299, Cl. 260-502.500.
- National Steel Corporation: See—
Keller, Robert N., 4,297,154, Cl. 156-79.000.
- Nauman, Christopher A. Jack-O-Lantern forming method. 4,296,659, Cl. 83-54.000.
- Nawrot, Wolfgang: See—
Kuger, Manfred; Nawrot, Wolfgang; and Preuss, Bernhard, 4,297,664, Cl. 335-176.000.
- Naylor, Leonard, to Simon-Rosedowns Limited. Deodorization of edible oils. 4,297,112, Cl. 55-195.000.
- Neblett, Boyd L.: See—
Debona, Edward J.; Neblett, Boyd L.; Krueger, Walter J.; Laird, William J.; Campbell, Billy H.; and Matthews, Gerald H., 4,296,669, Cl. 89-1.816.
- Neilson, John M. S.: See—
Koons, Patrick R.; and Neilson, John M. S., 4,297,149, Cl. 148-1.500.
- Nelle, Gunther, to Dr. Johannes Heidenhain GmbH. Incremental photoelectric measuring device. 4,297,033, Cl. 356-374.000.
- Nelson Industries, Inc.: See—
Kicinski, Kenneth J., 4,296,832, Cl. 181-255.000.
- Nelson, Linnea E.; and Reineke, Charles E., to Dow Chemical Co., The. Flame retardant intumescent polyamide from haloamide. 4,297,475, Cl. 528-271.000.
- Nelson, Richard L.; and Nelson, Walter P. Corn-based snack product of nut-like consistency. 4,297,376, Cl. 426-94.000.
- Nelson, Robert L.: See—
Cairns, James A.; Nelson, Robert L.; and Woodhead, James L., 4,297,246, Cl. 252-465.000.

- Nelson, Stephen J., to Upjohn Company. The. 2,3-Dihydro-2,3-dimethyl-7-benzofuryl N-[(phosphinyl)amino]thio- and N-[(phosphinothioyl)amino]thio- methylcarbamates. 4,297,285, Cl. 260-346.730.
- Nelson, Walter P.: See—
Nelson, Richard L.; and Nelson, Walter P., 4,297,376, Cl. 426-94.000.
- Nerod, Irving, to American Can Company. Ultraviolet light apparatus. 4,297,583, Cl. 250-453.000.
- Nessi, Aurindo, to Innocenti Santeustacchio S.p.A. Device for inserting and thrusting a bar into a press piercing mill. 4,296,622, Cl. 72-208.000.
- Nessler, Hermann: See—
Hiesinger, Edwin; Keplinger, Klaus; and Nessler, Hermann, 4,297,211, Cl. 210-136.000.
- Nettsch, Hermann, to USM Corporation. Process and apparatus for testing arc stud welding guns. 4,297,560, Cl. 219-130.010.
- Neumann, Peter, to Sandoz Ltd. Bicyclic heterocyclic amino derivatives. 4,297,490, Cl. 544-55.000.
- Nevins, Robert L. Solar collector. 4,296,734, Cl. 126-431.000.
- Newell, Harold R., to Mesur-Matic Electronics Corporation. Apparatus for dividing the step angle of a stepping motor. 4,297,625, Cl. 318-696.000.
- NGK Insulators, Ltd.: See—
Ito, Isao; and Tunashima, Seiichi, 4,297,034, Cl. 356-394.000.
- Nguyen, Giao V.: See—
Ferree, William L., Jr.; and Nguyen, Giao V., 4,297,260, Cl. 260-29.70H.
- Nguyen, Hien V., to Johnson & Johnson. Non-woven fabric comprising buds and bundles connected by highly entangled fibrous areas and methods of manufacturing the same. 4,297,404, Cl. 428-85.000.
- Nguyen, Van-Tao: See—
Chevreux, Pierre; Nguyen, Van-Tao; Roman, Alain; and Turpin, Daniel, 4,297,185, Cl. 204-159.150.
- Nichol, Thomas J.: See—
Pickens, Joseph R.; Schelleng, Robert D.; Donachie, Stephen J.; and Nichol, Thomas J., 4,297,136, Cl. 75-206.000.
- Nicholas, Terry G., to Wavin B.V. Guttering. 4,297,053, Cl. 405-121.000.
- Nicholson, John E.; and Wilmarth, Paul C., to RCA Corporation. Television receiver chassis adapted to be compatible with different tuner and cabinet configurations. 4,297,726, Cl. 358-254.000.
- Nick, Howard H. Interplanetary conflict game. 4,296,928, Cl. 273-262.000.
- Nickel, Horst, to Bayer Aktiengesellschaft. Pentakis-and heptakis-azoxy dyestuffs. 4,297,278, Cl. 260-143.000.
- Nickerson, Harvey R.: See—
Press, Irving D.; Nickerson, Harvey R.; and Rink, Helm, 4,296,804, Cl. 165-133.000.
- Nickols, Richard C., Jr.; Trocciola, John C.; and Rourke, James E., to United Technologies Corporation. Anode-matrix composite for molten carbonate fuel cell. 4,297,419, Cl. 429-44.000.
- Nicol, Klaus: See—
Hennig, Ewald M. C.; and Nicol, Klaus, 4,296,754, Cl. 128-694.000.
- Nicol, Thomas; Wiley, David; and Allport, Maurice J., to Lucas Industries Limited. Battery charging systems for road vehicles. 4,297,631, Cl. 320-64.000.
- Nihon Medi-Physics, Co., Ltd.: See—
Kato, Makoto; Ueda, Nobuo; and Matsushima, Hiroaki, 4,297,166, Cl. 376-194.000.
- Niinuma, Akira, to Alps Electric Co., Ltd. Ganged push button switch having means preventing simultaneous actuation of two push buttons. 4,297,541, Cl. 200-5.00E.
- Niuro, Yasuhiko; Furusawa, Kahei; and Okada, Akira, to Kokusai Denshin Denwa Kabushiki Kaisha. Feedthrough for optical fiber. 4,296,996, Cl. 350-96.200.
- Nikolayuk, Nicholas, to RCA Corporation. Circularly polarized slotted pylon antenna. 4,297,706, Cl. 343-771.000.
- Nilsson, Robert, to Evak Sanitar AB. Non-return valve. 4,296,772, Cl. 137-269.500.
- Ninomiya, Hidetaka: See—
Kaneke, Yutaka; Hirabayashi, Shigeto; Kawakatsu, Satoshi; and Ninomiya, Hidetaka, 4,297,437, Cl. 430-376.000.
- Kaneke, Yutaka; Kawakatsu, Satoshi; Hirabayashi, Shigeto; and Ninomiya, Hidetaka, 4,297,441, Cl. 430-543.000.
- Nintendo Co., Ltd.: See—
Yokoi, Gunpei, 4,296,931, Cl. 273-316.000.
- Nippon Electric Co., Ltd.: See—
Fujii, Shuzo; and Sato, Yoshikatsu, 4,297,655, Cl. 331-116.00R.
- Hayashi, Izuo; and Yonezu, Hiroo, 4,297,652, Cl. 331-94.50H.
- Shinmyo, Saburo, 4,297,650, Cl. 331-11.000.
- Tanaka, Kouichi; and Amazawa, Kiyoshi, 4,297,645, Cl. 330-280.000.
- Nippon Gakki Seizo Kabushiki Kaisha: See—
Chibana, Masanobu, 4,296,663, Cl. 84-1.010.
- Nippon Kogaku K.K.: See—
Utagawa, Ken; Hoshino, Kunihiisa; Shirasu, Hiroshi; and Ogawara, Akira, 4,297,571, Cl. 250-201.000.
- Nippon Kokan Kabushiki Kaisha: See—
Ando, Ryo; and Sato, Kazuyoshi, 4,297,119, Cl. 65-141.000.
- Nippon Oil Co. Ltd.: See—
Sato, Hisatake; Makino, Masaharu; and Hayashi, Hideo, 4,297,450, Cl. 525-333.000.
- Nippon Steel Corporation: See—
Sakurai, Koichi; Furukawa, Takashi; Takechi, Hiroshi; and Matsuo, Munetsugu, 4,296,919, Cl. 266-111.000.
- Nippon Toki Kabushiki Kaisha: See—
Ando, Kazunari; Matsunaga, Hirokazu; and Ayabe, Hideaki, 4,297,714, Cl. 346-139.00C.
- Nishi, Eihiro: See—
Kusayama, Senji; Nishi, Eihiro; and Stock, Hugh J., 4,297,160, Cl. 156-331.100.
- Nishikawa, Masaji, to Olympus Optical Company Limited. Electrophotographic process for multiple images. 4,297,423, Cl. 430-54.000.
- Nishikido, Joji; Tamura, Nobuhiro; Fukuoka, Yohei; and Yamane, Hiroyuki, to Asahi Kasei Kogyo Kabushiki Kaisha. Novel benzamide derivative and method of preparing metoclopramide using same. 4,297,503, Cl. 560-42.000.
- Nishimura, Katsuo; and Nanya, Takanori, to Technical Research of Citizen Watch Co., Ltd. Liquid crystal display cell. 4,297,004, Cl. 350-336.000.
- Nishino, Takaichi: See—
Sakurada, Kenichi; and Nishino, Takaichi, 4,296,965, Cl. 297-284.000.
- Nishiyama, Yukinori; and Ichikawa, Hideji, to Sumitomo Electric Industries, Ltd. Disc brake for two-wheeled vehicle. 4,296,843, Cl. 188-73.430.
- Nishizawa, Hideaki; and Iguchi, Shin-Ichi, to Sumitomo Electric Industries, Ltd. Multi-photodiodes. 4,297,720, Cl. 357-30.000.
- Nishizawa, Jun-Ichi; and Kitsuregawa, Takashi, to Semiconductor Research Foundation Mitsubishi Denki K.K. Vertical type field effect transistor. 4,297,718, Cl. 357-22.000.
- Nissan Motor Company, Limited: See—
Abo, Toshimi; and Kanegae, Hidetoshi, 4,296,600, Cl. 60-39.28R.
- Handa, Noritoshi, 4,296,937, Cl. 277-88.000.
- Ichimatsu, Eiji, 4,296,783, Cl. 139-302.000.
- Iizuka, Haruhiko; and Sugawara, Fukashi, 4,296,724, Cl. 123-568.000.
- Ishida, Takashi; and Tanaka, Mamoru, 4,296,907, Cl. 248-573.000.
- Iwanaga, Kazuyoshi; Sugano, Kazuhiko; and Ohtsuka, Kunio, 4,296,651, Cl. 74-869.000.
- Matsuoka, Hideoki; and Kondo, Yoshinobu, 4,296,944, Cl. 280-804.000.
- Nakamura, Ken; Ofuji, Hiromichi; and Yokoyama, Junichi, 4,297,302, Cl. 261-65.000.
- Sakurada, Kenichi; and Nishino, Takaichi, 4,296,965, Cl. 297-284.000.
- Nisshin Oil Mills, Ltd., The: See—
Makino, Akira, 4,297,106, Cl. 23-230.0HC.
- Nitschmann, Karl: See—
Dirks, Rudolf; and Nitschmann, Karl, 4,296,553, Cl. 30-381.000.
- Niven, Rex C.: See—
McCutchan, John C.; and Niven, Rex C., 4,297,633, Cl. 324-51.000.
- Nixdorf Computer AG: See—
Huellwegen, Josef, 4,297,595, Cl. 307-268.000.
- Nonomura, Koutaro: See—
Kasahara, Nobuyoshi; and Nonomura, Koutaro, 4,297,405, Cl. 428-141.000.
- Noonan, John M.: See—
Bowman, Wayne A.; Bishop, John F.; and Noonan, John M., 4,297,432, Cl. 430-215.000.
- Nooter Corporation: See—
Jawad, Maan, 4,296,869, Cl. 220-3.000.
- Norbach, Per, to A. B. Carl Munters. Apparatus including throttling device for use in ventilation duct. 4,296,780, Cl. 138-40.000.
- Nordblom, George F.: See—
Turillon, Pierre P.; Hull, Michael N.; and Nordblom, George F., 4,297,421, Cl. 429-225.000.
- Norden, Jurgen; and Ucinhasza, Bruno, to Ruhr-Stickstoff Aktien-gesellschaft. Procedure for the careful application of liquids to plants in agricultural stands. 4,296,885, Cl. 239-1.000.
- Normann, Richard W.: See—
Karol, James J.; Normann, Richard W.; and Hotchkiss, Lloyd C., 4,296,985, Cl. 339-48.000.
- Normier, Gerard: See—
D'Hinterland, Lucien D.; Normier, Gerard; Pinel, Anne-Marie; and Durand, Jacques, 4,297,272, Cl. 260-112.00R.
- Norsk Hydro a.s.: See—
Mejdell, Gior T.; Palmgren, Odd E.; Talmoen, Arne; and Vik, Bjarne, 4,297,483, Cl. 528-500.000.
- North American Philips Corporation: See—
Juner, Adolph; and Haas, David J., 4,297,580, Cl. 250-368.000.
- North, John W. Process of using and products from fume amorphous silica particulates. 4,297,309, Cl. 264-56.000.
- Northern Telecom Limited: See—
Dyment, John C.; and Chik, Kiuchi D., 4,297,651, Cl. 331-94.50H.
- Webb, Gerald F., 4,297,529, Cl. 179-1.0PC.
- Northrop Corporation: See—
Koning, Menno G., 4,296,639, Cl. 74-5.460.
- Northrup, Robert P.; and Anderson, Robert L., to General Electric Company. Ordnance recoil energy control and recovery system. 4,296,670, Cl. 89-43.00R.
- Norwood, Donald D.: See—
Short, James N.; and Norwood, Donald D., 4,297,445, Cl. 525-52.000.
- Nosaka, Soukichi, to Mitsubishi Belting Ltd. Power transmission V-belt and method of manufacture. 4,296,640, Cl. 474-262.000.
- Nottingham, Dennis. Method and H-pile tip for driving piles in permafrost. 4,297,056, Cl. 405-232.000.
- Novation, Inc.: See—
Kessler, Bayard F., 4,297,530, Cl. 179-2.00C.

- Nowotny, Theodor: *See*—
Schlegel, Hans; and Nowotny, Theodor, 4,297,175, Cl. 204-15.000.
Nunciato, David J.; White, Norman H.; and Woodburn, William A., to Union Carbide Corporation. Method for decoking fired heater tubes. 4,297,147, Cl. 134-7.000.
- Oberpichler, Gerd; and Honig, Ernst-August, to Volkswagenwerk Aktiengesellschaft. Hydraulic control for an automatic vehicle transmission. 4,296,652, Cl. 74-868.000.
- Oberst, E. Ernest, to Marlin Firearms Company, The. Semi-automatic reloading firearm. 4,296,564, Cl. 42-1.00C.
- Occidental Oil Shale, Inc.: *See*—
Ricketts, Thomas E.; Hutchins, Ned M.; and Studebaker, Irving G., 4,296,968, Cl. 299-2.000.
- Oda, Yoshio; Morimoto, Takeshi; and Suzuki, Kohji, to Asahi Glass Company, Ltd. Production of alkali metal hydroxide. 4,297,182, Cl. 204-98.000.
- Odawara, Youji: *See*—
Ishida, Masahiko; Haga, Ryoichi; and Odawara, Youji, 4,297,216, Cl. 210-613.000.
- Oder, Robin R.: *See*—
Tsai, Shirley C.; Graham, Richard H.; and Oder, Robin R., 4,296,809, Cl. 166-259.000.
- Oene, Henk V.: *See*—
Chang, Yun-Feng; Oene, Henk V.; and Beckwith, Elaine C., 4,297,448, Cl. 525-162.000.
- Oertel, Harald: *See*—
Lindner, Christian; Ott, Karl-Heinz; Arnold, Bernhard; Kowitz, Friedrich; Oertel, Harald; and Kuhlmann, Dieter, 4,297,446, Cl. 525-66.000.
- Offermann, Ludwig; and Wippich, Rheinhold, to Carl Still GmbH & KG, Firma. Immersion-type seal for the standpipe opening of coke ovens. 4,296,938, Cl. 277-135.000.
- Office National d'Etudes et de Recherches Aérospatiales: *See*—
Bloch, Bertrand; Cavalli born Meyer, Chantal; and Charrier, Denis, 4,297,466, Cl. 526-218.000.
- Ofuji, Hiromichi: *See*—
Nakamura, Ken; Ofuji, Hiromichi; and Yokoyama, Junichi, 4,297,302, Cl. 261-65.000.
- Ogasawara, Akira: *See*—
Utagawa, Ken; Hoshino, Kunihisa; Shirasu, Hiroshi; and Ogasawara, Akira, 4,297,571, Cl. 250-201.000.
- Ogasawara, Hiroomi; and Ogasawara, Masaomi. Device for measuring the amount of movement of a straightly moving object. 4,297,634, Cl. 324-61.00R.
- Ogasawara, Masaomi: *See*—
Ogasawara, Hiroomi; and Ogasawara, Masaomi, 4,297,634, Cl. 324-61.00R.
- Ogawa, Mutsuo; Koseki, Yuji; Saitoh, Yuichi; Yamaguchi, Shingo; and Katsuragi, Shigeru, to Ricoh Company, Ltd. Facsimile apparatus. 4,297,727, Cl. 358-261.000.
- Ogle, Robert W., to IMS Limited. Cath-a-jet. 4,296,747, Cl. 128-220.000.
- Ohashi, Mochihiko; and Toda, Tosifusa. Concentrating electrophoresis apparatus. 4,297,198, Cl. 204-299.00R.
- Ohashi, Naohito; Nagata, Shoji; and Katsube, Junki, to Sumitomo Chemical Company, Limited. Resolution of mercaptopropionic acids. 4,297,282, Cl. 260-326.200.
- Ohashi, Yoshinobu: *See*—
Nagao, Shozo; Ohashi, Yoshinobu; Watanabe, Yuichi; and Waku-shima, Yoshikazu, 4,296,953, Cl. 285-302.000.
- Ohdoi, Yozo; and Takahata, Yasuyuki, to Asahi-Seiki Manufacturing Co., Ltd. Machines for forming coiled springs. 4,296,621, Cl. 72-130.000.
- Ohgushi, Masuhito: *See*—
Koga, Isao; Terui, Yohji; Ohgushi, Masuhito; and Kitahara, Tohru, 4,297,499, Cl. 556-465.000.
- Ohhira, Hiroshi: *See*—
Sasaki, Tohru; Endoh, Hiroyuki; and Ohhira, Hiroshi, 4,297,413, Cl. 428-394.000.
- Ohta, Ryuji; and Kobayashi, Michio, to Jidosha Kiki Co., Ltd. Coupled shells for vacuum power servo booster. 4,296,680, Cl. 92-98.00D.
- Ohta, Sakae: *See*—
Tani, Tatsuo; Nagahara, Yasumori; Ohta, Sakae; Suzuki, Minoru; and Hashizume, Kiyozo, 4,297,021, Cl. 355-3.00R.
- Ohta, Tazuo: *See*—
Komatsu, Makoto; Takamizawa, Yuji; and Ohta, Tazuo, 4,297,507, Cl. 562-416.000.
- Ohtake, Yasushi: *See*—
Kadowaki, Hidetaka; Inomata, Akira; Yanagida, Kiyoshi; Hasegawa, Tsunao; Ishii, Satoshi; and Ohtake, Yasushi, 4,297,730, Cl. 360-66.000.
- Ohtsuka, Kunio: *See*—
Iwanaga, Kazuyoshi; Sugano, Kazuhiko; and Ohtsuka, Kunio, 4,296,651, Cl. 74-869.000.
- Ohye, Hideo: *See*—
Sato, Tsutomu; Ohye, Hideo; Tsukahara, Hirokazu; Senoh, Hideaki; and Torii, Takahiro, 4,296,948, Cl. 282-27.500.
- Oiji, Yoshimasa: *See*—
Takizawa, Hiroshi; Enomoto, Yutaka; Oiji, Yoshimasa; Hirayama, Tatsuyuki; and Hashimoto, Tamotu, 4,297,369, Cl. 424-285.000.
- Okada, Akira: *See*—
Niuro, Yasuhiko; Furusawa, Kahei; and Okada, Akira, 4,296,996, Cl. 350-96.200.
- Okada, Kunihiro: *See*—
Kodama, Kazuyuki; Okada, Kunihiro; Endoh, Takeyuki; and Shibuya, Yasutaka, 4,297,691, Cl. 340-723.000.
- Okamoto, Masanori: *See*—
Yoshida, Keizo; Tanaka, Hirokazu; Okamoto, Masanori; Iguchi, Eiko; Kohsaka, Masanobu; Aoki, Hatsuo; and Imanaka, Hiroshi, 4,297,096, Cl. 435-128.000.
- Okano, Hiroshi; and Sato, Akira, to Toyota Jidosha Kogyo Kabushiki Kaisha; and Kabushiki Kaisha Fujikoshi. Lubricated friction speed change gearing. 4,296,648, Cl. 74-798.000.
- Okatsuka, Hisahi, to Tokyo Shibaura Denki Kabushiki Kaisha. Cooking apparatus. 4,297,568, Cl. 235-435.000.
- OKI Electric Industry Co., Ltd.: *See*—
Akiyama, Masahiro; Kaminishi, Katuzo; and Kawakami, Yasushi, 4,297,647, Cl. 330-307.000.
- Okino, Susumu: *See*—
Tatani, Atsushi; and Okino, Susumu, 4,297,332, Cl. 423-240.000.
- Okui, Mitsuhiro: *See*—
Tani, Masayuki; Okui, Mitsuhiro; and Matsumoto, Mitsuo, 4,296,597, Cl. 57-205.000.
- Okuma Machinery Works, Ltd.: *See*—
Yasuba, Shoichi; and Ito, Takaharu, 4,296,657, Cl. 82-1.00C.
- Okumura, Takeshi: *See*—
Nakanishi, Kiyoshi; Okumura, Takeshi; Deguchi, Ryuichi; and Tanahashi, Toshio, 4,296,720, Cl. 123-309.000.
- Okuno, Youichi: *See*—
Yamada, Yasuyuki; and Okuno, Youichi, 4,297,020, Cl. 354-225.000.
- Okuyama, Takesi: *See*—
Fujimaki, Kiyoshi; Bando, Yoshiaki; Okuyama, Takesi; and Hashimoto, Tutomu, 4,296,954, Cl. 285-331.000.
- O'Leary, Kevin J.: *See*—
Dotson, Ronald L.; and O'Leary, Kevin J., 4,297,194, Cl. 204-257.000.
- Olin Corporation: *See*—
Whitman, Hobart A., III, 4,297,559, Cl. 219-121.0LB.
- Oline, James A.: *See*—
Meitzner, Erich F.; and Oline, James A., 4,297,220, Cl. 210-690.000.
- Olsen, Thomas O., to Otto Fabric, Inc. Silicone rubber coating material having reduced surface tension. 4,297,265, Cl. 260-33.6SB.
- Olshesky, Frank A. Combination storage and carrying device. 4,296,880, Cl. 294-144.000.
- Olsson, Torsten, to AB ASEA-ATOM. Nuclear reactor fuel assembly. 4,297,171, Cl. 376-440.000.
- Olympus Optical Company Limited: *See*—
Hijikata, Kazuo, 4,297,199, Cl. 204-299.00R.
- Nishikawa, Masaji, 4,297,423, Cl. 430-54.000.
- Sato, Eiichi, 4,297,422, Cl. 430-54.000.
- O'Meara, David M., to Chicago Bridge & Iron Company. Vacuum attached vibrator apparatus. 4,297,037, Cl. 366-114.000.
- Omega Tools International: *See*—
Ormsby, Ronald D., 4,296,822, Cl. 175-249.000.
- Onda, Kenichi; Tashiro, Sadaji; and Amano, Hisao, to Hitachi, Ltd.; and Hitachi Metals, Ltd. Gate circuit for a gate turn-off thyristor. 4,297,594, Cl. 307-252.00C.
- O'Neal, Thomas D., to American Cyanamid Co. Imidazolyl benza-mides as plant growth regulants. 4,297,126, Cl. 71-78.000.
- O'Neil, Jean M., executor: *See*—
O'Neil, John C., deceased, 4,297,057, Cl. 405-303.000.
- O'Neil, John C., deceased (by O'Neil, Jean M., executor), to Dresser Industries, Inc. Pivotal roof bolter and extendable rotatable protective canopy for mining machine. 4,297,057, Cl. 405-303.000.
- Onishi, Masao: *See*—
Hirao, Tsuneko; and Onishi, Masao, 4,297,609, Cl. 310-339.000.
- Ono, Hisatake: *See*—
Osada, Chiaki; Satomura, Masato; and Ono, Hisatake, 4,297,470, Cl. 526-304.000.
- Ono, Yoshio: *See*—
Masuda, Tatsunosuke; Ono, Yoshio; and Sakamoto, Seiya, 4,297,724, Cl. 358-93.000.
- Onoda Cement Co., Ltd.: *See*—
Misaka, Takaaki; Furukawa, Takeshi; and Onuma, Eiichi, 4,296,864, Cl. 209-144.000.
- Onuma, Eiichi: *See*—
Misaka, Takaaki; Furukawa, Takeshi; and Onuma, Eiichi, 4,296,864, Cl. 209-144.000.
- Opalka, Chester J., Jr.: *See*—
Leshner, George Y.; Opalka, Chester J., Jr.; and Page, Donald F., 4,297,360, Cl. 424-263.000.
- Orlandi, Robert G., to S.A. PRB Societe Anonyme. Electric circuit for firing a detonator. 4,296,688, Cl. 102-218.000.
- Ormsby, Ronald D., to Omega Tools International. Multipurpose fluid flow assisted downhole tool. 4,296,822, Cl. 175-249.000.
- Osada, Chiaki; Satomura, Masato; and Ono, Hisatake, to Fuji Photo Film Co., Ltd. Image forming process. 4,297,470, Cl. 526-304.000.
- Osakasanko Kabushiki Kaisha: *See*—
Nagano, Kenji, 4,296,534, Cl. 24-270.000.
- Osegowitsch, Viktor: *See*—
Stemme, Otto; Fergg, Berthold; Osegowitsch, Viktor; and Viehrig, Wolfgang, 4,297,027, Cl. 355-27.000.
- Osellame, Mirko: *See*—
Corbellini, Margherita; Greco, Alberto; and Osellame, Mirko, 4,297,462, Cl. 526-125.000.
- Oshio, Hiromichi: *See*—
Sanemitsu, Yuzuru; Mizutani, Masato; Sumida, Seizo; Katoh, Haruhiko; Oshio, Hiromichi; and Hashimoto, Shunichi, 4,297,129, Cl. 71-93.000.

- Oswald, Hendrikus J.: *See*—
Li, Hsin L.; Oswald, Hendrikus J.; and Liland, Alfred L., 4,296,535, Cl. 28-257.000.
- Otani, Masaru: *See*—
Fujii, Tadashi; Sato, Shuzo; Muto, Naoki; Hayashi, Mitsuo; Kodama, Akira; and Otani, Masaru, 4,297,486, Cl. 536-17.00R.
- Otis Elevator Company: *See*—
Martin, Anthony N., 4,296,601, Cl. 60-224.000.
- Otis Engineering Corporation: *See*—
Taylor, Donald F.; and Bostock, James H., 4,296,806, Cl. 166-120.000.
- Otsuka, Yasuhiro: *See*—
Shinohara, Hiroshi; Otsuka, Yasuhiro; Matsumoto, Shinichi; Wakisaka, Hiroshi; and Furutani, Toshinobu, 4,297,192, Cl. 204-195.00S.
- Ott, Karl-Heinz: *See*—
Lindner, Christian; Ott, Karl-Heinz; Arnold, Bernhard; Kowitz, Friedrich; Oertel, Harald; and Kuhlmann, Dieter, 4,297,446, Cl. 525-66.000.
- Otto Fabric, Inc.: *See*—
Olsen, Thomas O., 4,297,265, Cl. 260-33.6SB.
- Outokumpu Oy: *See*—
Uusitalo, Leo; and Tuominen, Pertti, 4,297,067, Cl. 414-114.000.
- Owen, R. Calvin, Jr., to Polaroid Corporation. Optical apparatus and method for changing a zoom camera to a fixed focus camera. 4,297,007, Cl. 350-432.000.
- Oy Helvar: *See*—
Lampinen, Esko; and Kajava, Kari, 4,296,545, Cl. 29-602.00R.
- Oyobe, Isao: *See*—
Takeguchi, Masanobu; and Oyobe, Isao, 4,297,222, Cl. 210-748.000.
- Ozawa, Kanji: *See*—
Moriya, Shigeru; Hamamoto, Nobuo; Ichino, Kazuo; and Ozawa, Kanji, 4,297,676, Cl. 340-146.3AG.
- P C U K Produits Chimiques Ugine Kuhlmann: *See*—
Delavarenne, Serge Y.; Dubreux, Bernard; and Tellier, Pierre, 4,297,288, Cl. 260-378.000.
- Paaren, Herbert E.: *See*—
DeLuca, Hector F.; Schnoes, Heinrich K.; Paaren, Herbert E.; and Fivizzani, Mary A., 4,297,289, Cl. 260-397.200.
- Pacer Systems, Inc.: *See*—
Green, David L., 4,297,673, Cl. 340-27.0NA.
- Pacer Technology and Resources, Inc.: *See*—
Kusayama, Senji; Nishi, Eijiro; and Stock, Hugh J., 4,297,160, Cl. 156-331.100.
- Paciorek, Kazimiera J. L.; Kratzer, Reinhold H.; Ito, Thomas I.; and Nakahara, James H., to United States of America, Air Force. Unsymmetrical diphosphatetraazacyclooctatetraenes. 4,297,510, Cl. 564-13.000.
- Padgett, Henry A., Sr. Oil filter unit. 4,297,212, Cl. 210-168.000.
- Page, Donald F.: *See*—
Leshner, George Y.; Opalka, Chester J., Jr.; and Page, Donald F., 4,297,360, Cl. 424-263.000.
- Pai, Damodar M.; Pochan, John M.; and Pochan, Darlyn F., to Xerox Corporation. Imaging member. 4,297,425, Cl. 430-58.000.
- Paisley, Robert J., to Corning Glass Works. Ceramic foam cement. 4,297,140, Cl. 428-310.000.
- Pajevic, Paul D. Shoe with sole cushioning assembly. 4,296,557, Cl. 36-7.800.
- Pallone, Thomas J.; Lynch, Mark; Corvino, Janice E.; and McCook, John P., to Chesebrough-Pond's Inc. Hair waving and straightening method. 4,296,764, Cl. 132-7.000.
- Palm, Peter: *See*—
Krabetz, Richard; Herrmann, Walter; Engelbach, Heinz; Palm, Peter; Sommer, Karl; and Spahn, Heinrich, 4,297,247, Cl. 252-468.000.
- Palmgren, Odd E.: *See*—
Mejdell, Gior T.; Palmgren, Odd E.; Talmoen, Arne; and Vik, Bjarne, 4,297,483, Cl. 528-500.000.
- Palumbo, Pasquale M. Dynamic patellar brace. 4,296,744, Cl. 128-80.00C.
- Pan, Jing-Jong, to Harris Corporation. Plural frequency oscillator employing multiple fiber-optic delay line. 4,297,656, Cl. 331-135.000.
- Panametrics, Inc.: *See*—
Lynnworth, Lawrence C.; Fowler, Kenneth A.; and Patch, Dana R., 4,297,607, Cl. 310-334.000.
- Panasenko, Nikolai N.: *See*—
Berkhin, Isif M.; Gudze, Robert A.; Kekalo, Vasily I.; Panasenko, Nikolai N.; Podbeltsev, Viktor I.; Tsykina, Zinaida D.; and Mukhin, Vladislav N., 4,296,867, Cl. 212-229.000.
- Papalos, John G.; and Kavchok, Ronald W., to Diamond Shamrock Corporation. Synthetic polymer emulsifier. 4,297,259, Cl. 260-29.6NR.
- Parker, Louis W.: *See*—
Hedges, Rhey W., 4,297,628, Cl. 318-798.000.
- Parr, David, to David Parr & Associates Limited. Heated window structure with an electrical connector assembly. 4,297,565, Cl. 219-522.000.
- Parsons, Robert, to Texas Instruments Incorporated. Apparatus for displaying graphics symbols. 4,297,693, Cl. 340-744.000.
- Passarotti, Carlo: *See*—
Gandolfi, Carmelo; Passarotti, Carlo; Andreoni, Alessandro; Fumagalli, Angelo; Faustini, Franco; Ceserani, Roberto; and Usardi, Maria M., 4,297,368, Cl. 424-285.000.
- Patch, Dana R.: *See*—
Lynnworth, Lawrence C.; Fowler, Kenneth A.; and Patch, Dana R., 4,297,607, Cl. 310-334.000.
- Pate, Jerry W., to E-Systems, Inc. Input gain adjusting apparatus and method. 4,297,527, Cl. 179-1.0VC.
- Patel, Raman: *See*—
Coran, Aubert Y.; and Patel, Raman, 4,297,453, Cl. 525-408.000.
- Patil, Balaji V.; and Tommaney, Joseph W., to Allegheny Ludlum Steel Corporation. Electroslag remelting method and flux composition. 4,297,132, Cl. 75-10.00V.
- Paton, Boris E.; Lebedev, Vladimir K.; Kuchuk-Yatsenko, Sergei I.; Sakharov, Vasily A.; Galyan, Boris A.; and Dobrovolsky, Stanislav D. Doughnut-type transformer for resistance butt welding. 4,297,665, Cl. 336-60.000.
- Patterson, Theodore P.; and Winner, Stephen E., to Patterson, Theodore P. Blister preventing foot cover. 4,296,499, Cl. 2-239.000.
- Pauling, Horst: *See*—
Guex, Woldemar; Klacui, Heinrich; Pauling, Horst; and Voirol, Felix, 4,296,801, Cl. 165-104.170.
- Paulus, Philippe, to Centre de Recherches Metallurgiques-Centrum voor Research in de Metallurgie. Manufacturing coated steel strip. 4,297,398, Cl. 427-320.000.
- Pauwels, Michael A.; and Poot, Abraham L., to Pneumo Corporation. 360 Degree linear variable phase transformer. 4,297,698, Cl. 340-870.320.
- Pavlik, Kathleen W. Pocket secretary or the like. 4,296,945, Cl. 281-1.000.
- Payne, Richard J. Tractor pull sled. 4,296,840, Cl. 188-8.000.
- Pazmany, Ladislao, to General Dynamics Corporation. Fin erection mechanism. 4,296,895, Cl. 244-3.290.
- Peacock, Richard C. Method of installing underground pipe. 4,297,055, Cl. 405-184.000.
- Pearson, Thomas J., Jr. Noise obviating electronic signal coupling means. 4,297,643, Cl. 330-178.000.
- Pedersen, Jorgen R., to Danavox A/S. Hook-shaped part of a behind-the-ear hearing aid. 4,296,829, Cl. 181-129.000.
- Pellegrino, Luigi. Automatic torque regulator. 4,296,849, Cl. 192-61.000.
- Peller, Robert C.; and Dyer, Jack E., to General Dynamics Corporation. Structurally damped bolt. 4,296,839, Cl. 188-378.000.
- Pelz, Willibald: *See*—
Haseler, Helmut; Meckl, Heinz; Lohmer, Karl; and Pelz, Willibald, 4,297,438, Cl. 430-377.000.
- Pennise, Robert J.: *See*—
Stoute, Neville, Sr.; and Pennise, Robert J., 4,296,506, Cl. 4-480.000.
- Pereman, Gordon F.: *See*—
Kellar, John D.; and Pereman, Gordon F., 4,297,118, Cl. 65-104.000.
- Permelec Electrode Ltd.: *See*—
Sato, Hideo; and Shimamune, Takayuki, 4,297,195, Cl. 204-290.00F.
- Perrott, Francis C. Transportation systems. 4,296,901, Cl. 246-167.00R.
- Persson, Lennart P. E.: *See*—
Hakansson, Hakan B.; Persson, Lennart P. E.; and Wall, Berth-Ove G., 4,296,633, Cl. 73-362.0AR.
- Perz, John S., to Martin Marietta Corporation. Method for curing concrete. 4,297,399, Cl. 427-385.500.
- Peterman, Robert J.: *See*—
Balbach, George C.; and Peterman, Robert J., 4,296,570, Cl. 49-360.000.
- Peterson, Eugene W.: *See*—
Wurtz, Howard P.; and Peterson, Eugene W., 4,297,082, Cl. 417-51.000.
- Petrolite Corporation: *See*—
Quinlan, Patrick M., 4,297,484, Cl. 528-423.000.
- Peysard, Guy: *See*—
Chaumat, Bernard; Gallet, Georges; Lamare, Jacques; and Peysard, Guy, 4,296,791, Cl. 160-206.000.
- Pfaff Industriemaschinen GmbH: *See*—
Barth, Karl; Albrecht, Ernst; and Stahlschmitt, Horst, 4,296,697, Cl. 112-109.000.
- Jehle, Fritz; and Willenbacher, Erich, 4,296,700, Cl. 112-153.000.
- Pfeifer, Josef; and Reinehr, Dieter, to Giba-Geigy Corporation. Transparent polyamide from branched chain C₁₁ diamine. 4,297,480, Cl. 528-346.000.
- Pfister, Hans B.: *See*—
Baltensperger, Rudolf; and Pfister, Hans B., 4,296,690, Cl. 104-91.000.
- Phillips Petroleum Co.: *See*—
Cowan, Kiplin D., 4,297,506, Cl. 560-246.000.
- Johnson, Paul H., 4,296,800, Cl. 165-95.000.
- Layton, James E., 4,297,745, Cl. 367-66.000.
- McDaniel, Max P.; and Welch, Melvin B., 4,297,460, Cl. 526-98.000.
- Morris, Charles W.; and Terry, Ronald E., 4,296,811, Cl. 166-273.000.
- Short, James N.; and Norwood, Donald D., 4,297,445, Cl. 525-52.000.
- Trepka, William J., 4,297,464, Cl. 526-181.000.
- Uraneck, Carl A.; Burleigh, John E.; and Solomon, Paul W., 4,297,451, Cl. 525-366.000.
- Phillips, Raymond M. Anti-surge flotation mattress. 4,296,510, Cl. 5-450.000.
- Phillips, Thomas R., to Du Pont de Nemours, E. I., and Company. Polyvinyl butyral plasticized with tetraethyleneglycol-di-n-heptanoate. 4,297,262, Cl. 260-31.600.

- Pickens, Joseph R.; Schelleng, Robert D.; Donachie, Stephen J.; and Nichol, Thomas J., to International Nickel Co., Inc., The. High strength aluminum alloy and process. 4,297,136, Cl. 75-206.000.
- Pierce, William C., to Pitts Industries, Inc. Drive hub with curved springs and drive keys for electro-magnetic clutch. 4,296,851, Cl. 192-84.00C.
- Pierre Fabre S.A.: See—
D'Hinterland, Lucien D.; Normier, Gerard; Pinel, Anne-Marie; and Durand, Jacques, 4,297,272, Cl. 260-112.00R.
- Pietsch, Herbert E.: See—
Gupta, Tapan K.; and Pietsch, Herbert E., 4,297,250, Cl. 252-518.000.
- Pillsbury Company, The: See—
Haas, Michael J.; Pratt, Paul D.; Chen, Rocky W.; and Fett, Helen M., 4,297,378, Cl. 426-532.000.
- Pinel, Anne-Marie: See—
D'Hinterland, Lucien D.; Normier, Gerard; Pinel, Anne-Marie; and Durand, Jacques, 4,297,272, Cl. 260-112.00R.
- Pioneer Electronic Corporation: See—
Kadowaki, Hidetaka; Inomata, Akira; Yanagida, Kiyoshi; Hasegawa, Tsunao; Ishii, Satoshi; and Ohtake, Yasushi, 4,297,730, Cl. 360-66.000.
- Pitts Industries, Inc.: See—
Pierce, William C., 4,296,851, Cl. 192-84.00C.
- Place, Donald E., to Therm-O-Disc, Incorporated. Thermostat with bracket for attachment to a tubular member. 4,297,668, Cl. 337-365.000.
- Plastics Engineering Company: See—
Waitkus, Phillip A.; and D'Alelio, Gaetano F., deceased, 4,297,467, Cl. 526-259.000.
- Platt, John R., to Illinois Tool Works Inc. Two-way container package. 4,296,858, Cl. 206-150.000.
- Plessey Handel und Investments AG: See—
Mead, John F., 4,296,999, Cl. 350-96.210.
- Plessey Peripheral Systems: See—
Dargatz, Dayton O., 4,297,043, Cl. 400-224.000.
- Pneumo Corporation: See—
Pauwels, Michael A.; and Poot, Abraham L., 4,297,698, Cl. 340-870.320.
- Pochan, Darlyn F.: See—
Pai, Damodar M.; Pochan, John M.; and Pochan, Darlyn F., 4,297,425, Cl. 430-58.000.
- Pochan, John M.: See—
Pai, Damodar M.; Pochan, John M.; and Pochan, Darlyn F., 4,297,425, Cl. 430-58.000.
- Podbeltsev, Viktor I.: See—
Berkhin, Isif M.; Gudze, Robert A.; Kekalo, Vasily I.; Panasenko, Nikolai N.; Podbeltsev, Viktor I.; Tsykina, Zinaida D.; and Mukhin, Vladislav N., 4,296,867, Cl. 212-229.000.
- Poff, David A.: See—
Hill, Michael S.; and Poff, David A., 4,296,546, Cl. 29-730.000.
- Pohl, Ludwig: See—
Eidenschink, Rudolf; and Pohl, Ludwig, 4,297,515, Cl. 568-329.000.
- Polaroid Corporation: See—
Farmer, Zane M., 4,297,017, Cl. 354-34.000.
- Johnson, Bruce K.; and Whiteside, George D., 4,297,016, Cl. 354-27.000.
- Owen, R. Calvin, Jr., 4,297,007, Cl. 350-432.000.
- Sullivan, Charles L., 4,297,431, Cl. 430-215.000.
- Polhemus, Barry: See—
Denning, Richard; Spak, Mark A.; and Polhemus, Barry, 4,297,393, Cl. 427-88.000.
- Polk, Donald E.: See—
Giessen, Bill C.; Polk, Donald E.; and Ray, Ranjan, 4,297,135, Cl. 75-123.00B.
- Polymer Research Corp. of America: See—
Horowitz, Carl; and Dichter, Michael, 4,297,108, Cl. 44-1.0SR.
- Pommer, Ernst-Heinrich: See—
Sauter, Hubert; Zeeh, Bernd; Rentzea, Costin; and Pommer, Ernst-Heinrich, 4,297,364, Cl. 424-267.000.
- Pontifex, Edward J., to Fine, Louis B., a part interest. Colostomy appliance. 4,296,749, Cl. 128-283.000.
- Pook, Karl-Heinz: See—
Weber, Karl-Heinz; Schneider, Claus; Walther, Gerhard; Pook, Karl-Heinz; Boke, Karin; and Bechtel, Wolf D., 4,297,354, Cl. 424-248.510.
- Poot, Abraham L.: See—
Pauwels, Michael A.; and Poot, Abraham L., 4,297,698, Cl. 340-870.320.
- Popplewell, Frank W., to Dunlop Limited. Method of manufacturing games rackets. 4,297,308, Cl. 264-46.600.
- Porter, James A., Jr.: See—
Thigpen, Ben B.; and Porter, James A., Jr., 4,296,827, Cl. 181-107.000.
- Posso, Patrick. Process for the simplified packing of a magnetic tape for computer and winding core for carrying out this process. 4,296,890, Cl. 242-71.800.
- Potter, George R., to Burley Industries, Inc. Method for sealing a dryer. 4,296,540, Cl. 29-460.000.
- Powell, Charles R. Building scaffold support. 4,296,905, Cl. 248-237.000.
- PPG Industries, Inc.: See—
Crawford, Roger A.; and Simmons, Robert B., 4,297,333, Cl. 423-241.000.
- Jozwiak, Edward L., Jr., 4,297,261, Cl. 260-29.7RP.
- Kellar, John D.; and Pereman, Gordon F., 4,297,118, Cl. 65-104.000.
- Leatherman, Ivan R., 4,297,267, Cl. 260-42.530.
- PQ Corporation: See—
Thomas, Jeffrey R., 4,297,163, Cl. 159-48.00R.
- Pratt & Lambert, Inc.: See—
Wolinski, Leon E.; and Berezuk, Peter D., 4,297,158, Cl. 156-305.000.
- Pratt, Paul D.: See—
Haas, Michael J.; Pratt, Paul D.; Chen, Rocky W.; and Fett, Helen M., 4,297,378, Cl. 426-532.000.
- Presco, Inc.: See—
Gotman, Alexander, 4,296,542, Cl. 29-574.000.
- Press, Irving D.; Nickerson, Harvey R.; and Rink, Helm, to Resistoflex Corporation. Corrosion resistant heat exchanger element and method of manufacture. 4,296,804, Cl. 165-133.000.
- Preston, Mark D. Methods and apparatus for conditioning plywood veneer with high frequency radio energy. 4,296,555, Cl. 34-1.000.
- Pretzer, Wayne R.: See—
Wu, Ching-Yong; Pretzer, Wayne R.; and Kobylinski, Thaddeus P., 4,297,518, Cl. 568-385.000.
- Preuss, Bernhard: See—
Kuger, Manfred; Nawrot, Wolfgang; and Preuss, Bernhard, 4,297,664, Cl. 335-176.000.
- Price, Ernest H. Method of producing oil from a formation fluid containing both oil and water. 4,296,810, Cl. 166-265.000.
- Price, Frank C.: See—
Halford, David W.; Price, Frank C.; and Bosworth, George H., 4,296,513, Cl. 12-12.000.
- Price, Robert B., to Jacobs Manufacturing Company, The. Compression relief retarders for supercharged internal combustion engines. 4,296,605, Cl. 60-599.000.
- Priepke, Edward H.: See—
Martenas, Wayne B.; Priepke, Edward H.; and Wagstaff, Robert A., 4,296,591, Cl. 56-10.300.
- Priesemuth, Wolfgang. Pneumatically operating delay switches. 4,297,544, Cl. 200-34.000.
- Priest, Clayton W.; and Solomon, Edward T., to Priest, Clayton W. Hair conditioner. 4,296,763, Cl. 132-7.000.
- Procter & Gamble Company, The: See—
Bernardino, Lowell W., 4,297,251, Cl. 252-545.000.
- Logan, Ted J.; and Lubsen, Timothy A., 4,297,292, Cl. 260-428.500.
- Rasser, Jacobus C., 4,297,230, Cl. 252-117.000.
- Proteus Corporation: See—
Inhofer, Harold G., 4,296,672, Cl. 91-271.000.
- Proud, Norman. Screen panel. 4,296,579, Cl. 52-239.000.
- Przybyla, Franciszek J.; and Rossler, Eleanor J., to Duracell International Inc. Method of treating silver oxide powder and the product formed therefrom. 4,297,249, Cl. 252-518.000.
- Puch, Diethelm; and Will, Norbert F., to Triumph-Werke Nurnberg A.G. Method and apparatus for positioning a type disc in a balanced force system. 4,297,040, Cl. 400-144.200.
- Puschmann, Werner, to AGFA-Gevaert Aktiengesellschaft. System for the detection of splicing defects in film. 4,297,585, Cl. 250-560.000.
- Putner, Reinhold; Buhmann, Ulrich; and Joppien, Harmut, to Schering Aktiengesellschaft. Thiazolidene-oxo-propionitriles, insecticidal composition containing these compounds. 4,297,361, Cl. 424-263.000.
- Quan, Ronald, to Ampex Corporation. Quasi feedback horizontal scan linearization for cathode ray tubes. 4,297,620, Cl. 315-389.000.
- Quanbeck, Sherman H., to Wil-Rich, Inc. Seeding device with air distribution system. 4,296,695, Cl. 111-34.000.
- Quick, Leonard M.: See—
Hensley, Albert L., Jr.; and Quick, Leonard M., 4,297,242, Cl. 252-439.000.
- Quick, William H.; James, Kenneth A.; and Strahan, Virgil H., to Rockwell International Corporation. Method and apparatus for holographic processing. 4,296,994, Cl. 350-3.730.
- Quinlan, Patrick M., to Petrolite Corporation. Quaternized derivatives of polymerized pyridines and quinolines. 4,297,484, Cl. 528-423.000.
- Quintana, Pedro. Dust removing attachment device for automatic air files. 4,296,572, Cl. 51-170.0TL.
- Rabian, Jean: See—
Nard, Georges; Rabian, Jean; and Rouaud, Michel, 4,297,700, Cl. 343-6.50R.
- Raible, Donald A., to Bentley Laboratories, Inc. Blood oxygenator. 4,297,318, Cl. 422-46.000.
- Rajappa, Srinivasachari; and Sudarsanam, Vasudevan, to Ciba-Geigy Corporation. Benzimidazoles and pharmaceutical preparations containing such compounds. 4,297,365, Cl. 424-270.000.
- Ramcke, Bernd; Schlottke, Karl-Heinz; Brandt, Eckhard; and Reissmann, Klaus, to E. C. H. Will (GmbH & Co.). Paper sheet layer forming and transferring arrangement. 4,297,066, Cl. 414-43.000.
- Ranford, Alan B.: See—
Joslin, Joel A.; and Ranford, Alan B., 4,296,759, Cl. 128-766.000.
- Rankin, William J. Bank erosion control units. 4,297,052, Cl. 405-16.000.
- Ransberger, Michael; Rosenberger, Siegfried; and Evans, Samuel, to Ciba-Geigy Corporation. Phenolic-1,3,5-triazines. 4,297,492, Cl. 544-211.000.
- Rasp, Christian: See—
Becker, Robert; Grolog, Johann; and Rasp, Christian, 4,297,501, Cl. 560-24.000.
- Rasser, Jacobus C., to Procter & Gamble Company, The. Non-crystallizing transparent soap bars. 4,297,230, Cl. 252-117.000.

- Rathmell, William G.: See—
Henrick, Clive A.; Labovitz, Jeffrey N.; Fox, Roland T. V.; Rathmell, William G.; and Shephard, Margaret C., 4,297,297, Cl. 260-465.00D.
- Rau, Karl: See—
Jung, Wilhelm; and Rau, Karl, 4,296,630, Cl. 73-304.00C.
- Ray, Ranjan: See—
Giessen, Bill C.; Polk, Donald E.; and Ray, Ranjan, 4,297,135, Cl. 75-123.00B.
- Raychem Corporation: See—
Jervis, James E., 4,297,155, Cl. 156-86.000.
- Martin, Charles L., 4,296,955, Cl. 285-381.000.
- Raymond, A.: See—
Muller, Klaus; and Mack, Gerhard, 4,296,530, Cl. 24-295.000.
- Raymond, Christopher D., to G. D. Searle & Co. Surgical sealant composition. 4,296,745, Cl. 128-156.000.
- Raytheon Company: See—
Carnes, Irven S., 4,297,702, Cl. 343-7.0PF.
- RCA Corporation: See—
Ahmed, Adel A. A., 4,297,644, Cl. 330-264.000.
- Carroll, Charles B.; and Scheible, Howard G., 4,297,312, Cl. 264-134.000.
- Denning, Richard; Spak, Mark A.; and Polhemus, Barry, 4,297,393, Cl. 427-88.000.
- Hsu, Sheng T., 4,297,719, Cl. 357-23.000.
- Koons, Patrick R.; and Neilson, John M. S., 4,297,149, Cl. 148-1.500.
- Nicholson, John E.; and Wilmarth, Paul C., 4,297,726, Cl. 358-254.000.
- Nikolayuk, Nicholas, 4,297,706, Cl. 343-771.000.
- Silcox, David R.; and Doster, John L., 4,297,095, Cl. 432-59.000.
- Sterzer, Fred, 4,297,641, Cl. 328-15.000.
- Reagent Chemical and Research, Inc.: See—
Hicke, David W., 4,296,536, Cl. 29-1.300.
- Redon Trust: See—
Marer, Joseph, 4,296,686, Cl. 102-427.1KPA.
- Reed, Robert D.; Schwartz, Robert E.; and Kraft, Raymond D., to John Zink Company. Free-floating combustion chamber and stack. 4,297,094, Cl. 431-202.000.
- Reed, Ronald R.; Crone, William F., Jr.; and Meyer, G. Robert, to Libbey-Owens-Ford Company. Method of and apparatus for cutting sheets of glass. 4,296,662, Cl. 83-880.000.
- Rehnberg, Leif E. L.: See—
Lundgren, Sune I.; and Rehnberg, Leif E. L., 4,296,653, Cl. 81-3.46R.
- Reichhold Limited: See—
De Ruiter, Robert S.; and Kambanis, Stamatis M., 4,297,264, Cl. 260-33.40R.
- Reider, Samuel B., to General Motors Corporation. Porous laminated material. 4,296,606, Cl. 60-754.000.
- Reinehr, Dieter: See—
Pfeifer, Josef; and Reinehr, Dieter, 4,297,480, Cl. 528-346.000.
- Reineke, Charles E.: See—
Nelson, Linnea E.; and Reineke, Charles E., 4,297,475, Cl. 528-271.000.
- Reischl, Artur; and Wagner, Kuno, to Bayer Aktiengesellschaft. Process for working up isocyanate distillation residues. 4,297,456, Cl. 525-452.000.
- Reissenweber, Gernot; and Mangold, Dietrich, to BASF Aktiengesellschaft. Preparation of 2,3-dioxo-1,4-benzoxazine derivatives. 4,297,491, Cl. 544-105.000.
- Reissmann, Klaus: See—
Ramcke, Bernd; Schlottke, Karl-Heinz; Brandt, Eckhard; and Reissmann, Klaus, 4,297,066, Cl. 414-43.000.
- Relles, Howard M.: See—
Williams, Frank J., III; and Relles, Howard M., 4,297,474, Cl. 528-170.000.
- Rentzea, Costin: See—
Sauter, Hubert; Zeeh, Bernd; Rentzea, Costin; and Pommer, Ernst-Heinrich, 4,297,364, Cl. 424-267.000.
- REPA Feinstanzwerk GmbH: See—
Schmid, Johann, 4,296,525, Cl. 16-174.000.
- Resistoflex Corporation: See—
Press, Irving D.; Nickerson, Harvey R.; and Rink, Helm, 4,296,804, Cl. 165-133.000.
- Reynolds, Daniel J.: See—
Rice, Hoyt G., Jr.; and Reynolds, Daniel J., 4,296,576, Cl. 52-90.000.
- Rheinmetall GmbH: See—
Romer, Rudolf; and Schepp, Hans-Egon, 4,296,685, Cl. 102-387.000.
- Rhone-Poulenc Agrochimie: See—
Guigues, Francois; and Trinh, Stephane, 4,297,367, Cl. 424-283.000.
- Rhone-Poulenc Agrochimie: See—
Michelet, Daniel, 4,297,284, Cl. 260-346.220.
- Rhone-Poulenc Industries: See—
Costantini, Michel; and Jouffret, Michel, 4,297,287, Cl. 260-348.160.
- Rhone-Poulenc-Textile: See—
Achard, Georges; Chion, Pierre; and Menault, Jacques, 4,297,412, Cl. 428-370.000.
- Rochina, Vincent; and Sacco, Jean, 4,297,478, Cl. 528-336.000.
- Rochina, Vincent; and Sacco, Jean, 4,297,479, Cl. 528-336.000.
- Rhonehouse, Donald E., to TGS Systems, Inc. Glass tempering furnaces and systems. 4,297,121, Cl. 65-348.000.
- Rice, Doris M.: See—
Gilbert, Richard J.; and Rice, Doris M., 4,297,444, Cl. 521-160.000.
- Rice, Hoyt G., Jr.; and Reynolds, Daniel J., to Anaconda Company. The. Sloped wall structure and anchor clip. 4,296,576, Cl. 52-90.000.
- Rice, Robert A., to Eaton Corporation. Freeze drain valve. 4,296,770, Cl. 137-62.000.
- Richard, Henry J.: See—
Gidge, Kenneth N.; and Richard, Henry J., 4,296,792, Cl. 160-332.000.
- Richarz, Winfried; Froehlich, Helmut; and Schroeder, Harald, to BASF Aktiengesellschaft. Manufacture of 4-amino-5-chloro-1-phenylpyridaz-6-one using aqueous phenol-4-sulfonic acid. 4,297,493, Cl. 544-241.000.
- Richway Industries Ltd.: See—
Borglum, Richard P., 4,296,875, Cl. 222-617.000.
- Ricketts, Thomas E.; Hutchins, Ned M.; and Studebaker, Irving G., to Occidental Oil Shale, Inc. In situ oil shale retort having horizontally offset pillars. 4,296,968, Cl. 299-2.000.
- Ricoh Company, Ltd.: See—
Ogawa, Mutsuo; Koseki, Yuji; Saitoh, Yuichi; Yamaguchi, Shingo; and Katsuragi, Shigeru, 4,297,727, Cl. 358-261.000.
- Sakai, Kiyoshi; Hashimoto, Mitsuru; and Kawakami, Tomiko, 4,297,426, Cl. 430-59.000.
- Tani, Tatsuo; Nagahara, Yasumori; Ohta, Sakae; Suzuki, Minoru; and Hashizume, Kiyozo, 4,297,021, Cl. 355-3.00R.
- Riedel-de Haen Aktiengesellschaft: See—
Franz, Karl; and Schonfeld, Bernd, 4,297,390, Cl. 427-64.000.
- Riege, Ulrich: See—
Scheffler, Knut; and Riege, Ulrich, 4,297,304, Cl. 264-0.500.
- Rieger, Ulrich: See—
Schnabele, Werner; Buckley, Jack; and Rieger, Ulrich, 4,296,894, Cl. 244-3.270.
- Riemenschneider, Wilhelm: See—
Tetzlaff, Karl-Heinz; Riemenschneider, Wilhelm; and Leuschner, Gunter, 4,297,323, Cl. 422-208.000.
- Ring Lock Container S. A.: See—
Andersson, Poul G., 4,296,871, Cl. 220-306.000.
- Rink, Helm: See—
Press, Irving D.; Nickerson, Harvey R.; and Rink, Helm, 4,296,804, Cl. 165-133.000.
- Rinnai Kabushiki Kaisha: See—
Inayama, Minoru; and Furukawa, Yukio, 4,297,558, Cl. 219-10.55R.
- Rio, Michel: See—
Crommelynck, Francois; Granger, Michel; Rio, Michel; and Tour-dot, Jacques, 4,297,298, Cl. 260-502.00R.
- Rips, Richard; and Morier, Elisabeth, to Institut National de la Sante et de la Recherche Medicale. Pseudopeptides used as medicaments. 4,297,346, Cl. 424-177.000.
- Rishel, John W.: See—
DeVisser, Richard B.; Rishel, John W.; and Kuiper, Joe A., 4,297,209, Cl. 210-107.000.
- Ritscher, James S.; and Sandner, Michael R., to Union Carbide Corporation. Three-way catalytic process for gaseous streams. 4,297,328, Cl. 423-213.200.
- Rittersdorf, Walter: See—
Guthlein, Werner; Wielinger, Hans; Rittersdorf, Walter; and Werner, Wolfgang, 4,297,271, Cl. 260-107.000.
- Ritze, Willy, to Jenaer Glaswerk, Schott & Gen. Optical colored and filter glass. 4,297,142, Cl. 501-77.000.
- Rivenbark, Morrison, to Smith, Douglas R. Method and apparatus for forming a chlorine-water solution and for utilizing the same to disinfect water lines and the like. 4,297,223, Cl. 210-754.000.
- Robert Bosch GmbH: See—
Hofmann, Karl, 4,296,887, Cl. 239-397.500.
- Schlagmuller, Walter, 4,296,717, Cl. 123-195.00A.
- Schmidt, Waldemar, 4,297,314, Cl. 264-320.000.
- Werner, Peter; Drews, Ulrich; Elbers, Theodor; and Jackel, Klaus, 4,297,599, Cl. 307-355.000.
- Roberts, Charles W.; Kolowski, Michael A.; Lindner, Daniel J.; Lynch, John E.; Ruip, Terrence M.; and Petty, Harold D., to Goodyear Tire & Rubber Company, The. Tread for pneumatic tire. 4,296,789, Cl. 152-209.00R.
- Roberts, James K., to Bendix Corporation, The. Anchor plate for a drum brake assembly. 4,296,845, Cl. 188-341.000.
- Roberts, Ralph R. Vandal alarm system for parking meters. 4,297,683, Cl. 340-539.000.
- Robertshaw Controls Company: See—
Lewis, Jay L., 4,296,795, Cl. 165-27.000.
- Manecke, Siegfried E.; and Buckshaw, Thomas M., 4,296,603, Cl. 60-528.000.
- Steele, Everett T., Jr., 4,296,721, Cl. 123-407.000.
- Tyler, Hugh J.; and Conway, William H., 4,297,557, Cl. 219-10.55R.
- Robertson, Kenneth L.; and Heslep, Curtis A., to Ken-Koat, Inc. Apparatus for coating metal substrates with adhesive. 4,296,708, Cl. 118-233.000.
- Robinet, Jules P.: See—
Balkwill, G. Russell; Robinet, Jules P.; and Tamasovics, John F., 4,296,870, Cl. 220-3.300.
- Robinson, Jesse L. Deformable highway marker. 4,297,051, Cl. 404-11.000.
- Robinson, John W.: See—
Wilcox, Brian N.; and Robinson, John W., 4,296,666, Cl. 84-1.260.
- Rochina, Vincent; and Sacco, Jean, to Rhone-Poulenc-Textile. Process for the discontinuous production of aromatic in mixture of polyamides calcium chloride and N-methylpyrrolidone-2. 4,297,478, Cl. 528-336.000.

- Rochina, Vincent; and Sacco, Jean, to Rhone-Poulenc-Textile. Process for the continuous production of aromatic polyamides in a mixture of calcium chloride and N-methylpyrrolidone-2. 4,297,479, Cl. 528-336.000.
- Rockwell International Corporation: See—
Frerking, Marvin E., 4,297,657, Cl. 331-176.000.
Quick, William H.; James, Kenneth A.; and Strahan, Virgil H., 4,296,994, Cl. 350-3.730.
Smith, Elroy C., Jr.; and Yao, Shi K., 4,297,189, Cl. 204-192.0SP.
- Rodemer, Karl, to Lincoln-Helios GmbH. Multiple coupling for lubricating systems. 4,296,777, Cl. 137-351.000.
- Rodenbeck, Philip G.; and Koenig, Fredrick, to General Electric Company. Wire vibration damping device and method for coil winding apparatus. 4,296,784, Cl. 140-92.200.
- Rodgers, John M. Photo-electric digital circuit for monitoring strip loop position. 4,297,586, Cl. 250-561.000.
- Rodionov, Evgeny I.: See—
Bashnin, Oleg I.; Semenov, Vasily V.; Fedorov, Vasily N.; Gorbunov, Nikolai M.; Rodionov, Evgeny I.; and Sorokin, Nikolai A., 4,297,589, Cl. 290-40.00R.
- Roesler, Helmut; and Muehlbauer, Otto, to Siemens Aktiengesellschaft. Electronic counter for electrical digital pulses. 4,297,591, Cl. 307-224.00C.
- Rogers, Stanley J. C.; and Taplin, John F., to Vickers Limited. Edge joint for sheets. 4,296,983, Cl. 312-263.000.
- Rohm and Haas Company: See—
Kilbourn, Edward E.; Weiler, Ernest D.; and Weir, William D., 4,297,342, Cl. 424-84.000.
Meitzner, Erich F.; and Oline, James A., 4,297,220, Cl. 210-690.000.
- Rojahn, Bernd: See—
Meier, Willi; and Rojahn, Bernd, 4,296,702, Cl. 112-258.000.
- Rollei of America, Inc.: See—
Adams, James R., Jr., 4,297,011, Cl. 354-23.00D.
- Rolls-Royce Motors Limited: See—
Thornton, Kenneth, 4,296,646, Cl. 74-688.000.
- Roman, Alain: See—
Chevreux, Pierre; Nguyen, Van-Tao; Roman, Alain; and Turpin, Daniel, 4,297,185, Cl. 204-159.150.
- Roman, Stephan: See—
Krauss, Timothy A.; and Roman, Stephan, 4,297,080, Cl. 416-141.000.
- Rombusch, Konrad: See—
Maahs, Gunther; and Rombusch, Konrad, 4,297,505, Cl. 560-219.000.
- Romer, Rudolf; and Schepp, Hans-Egon, to Rheinmetall GmbH. Warhead with slave missiles disposed in a firing tube. 4,296,685, Cl. 102-387.000.
- Ronk Electrical Industries, Inc.: See—
Ronk, Leroy B., 4,297,551, Cl. 200-67.00B.
- Ronk, Leroy B., to Ronk Electrical Industries, Inc. Electrical transfer switch. 4,297,551, Cl. 200-67.00B.
- Ronne, Reuben N.: See—
Blanchard, Kenneth G.; and Ronne, Reuben N., 4,296,963, Cl. 297-170.000.
- Roos, Leo: See—
Jolly, Jennings L.; and Roos, Leo, 4,297,435, Cl. 430-270.000.
- Rosenbaum, Murray: See—
Kowalski, George A.; Mayer, George; and Rosenbaum, Murray, 4,297,570, Cl. 235-493.000.
- Rosenberger, Siegfried: See—
Rasberger, Michael; Rosenberger, Siegfried; and Evans, Samuel, 4,297,492, Cl. 544-211.000.
- Rosheim, Mark E. Fluid driven servomechanism. 4,296,681, Cl. 92-122.000.
- Ross, Byron W. Engraving machine. 4,297,060, Cl. 409-86.000.
- Ross, Jim; and Vilich, John. Collapsible charcoal lighting holder. 4,296,726, Cl. 126-25.00B.
- Ross, Jury N.: See—
Yasinsky, Konstantin K.; Glazunov, Sergei G.; Ross, Jury N.; and Bykov, Igor D., 4,296,793, Cl. 164-24.000.
- Ross, Leon I., to Caribbean Properties Limited. Process and apparatus for the contact and separation of immiscible fluids. 4,297,111, Cl. 55-92.000.
- Rossander, Bror L. E.; Ermebrant, Lennart C.; and Lesser, Martin, to Fagersta A.B. Product provided with sound damping element. 4,296,830, Cl. 181-208.000.
- Rossi, Alberto: See—
Haas, Georges; Jaeggi, Knut A.; Rossi, Alberto; and Sele, Alex, 4,297,358, Cl. 424-256.000.
- Rossler, Eleanor J.: See—
Przybyla, Franciszek J.; and Rossler, Eleanor J., 4,297,249, Cl. 252-518.000.
- Rothbuhl, Lothar: See—
Wolff, Siegfried; Rothbuhl, Lothar; and Grewatta Heinz, 4,297,145, Cl. 106-308.00Q.
- Rouaud, Michel: See—
Nard, Georges; Rabian, Jean; and Rouaud, Michel, 4,297,700, Cl. 343-6.50R.
- Rourke, James E.: See—
Nickols, Richard C., Jr.; Trociola, John C.; and Rourke, James E., 4,297,419, Cl. 424-84.000.
- Roussel Uclaf: See—
Heymes, Rene; and Lutz, Andre, 4,297,352, Cl. 424-246.000.
- Roux, Marc, to Alstom-Atlantique. Railway car ceiling panel. 4,296,692, Cl. 105-397.000.
- Rowe International, Inc.: See—
Mitchell, Robert P.; and Scalera, Frank T., 4,296,872, Cl. 221-195.000.
- Ruben, Samuel. Glycol-iodine composition and method of preparation. 4,297,232, Cl. 252-187.00R.
- Rubottom, Nolan R.; and Fine, Jerry W. Supplemental right turn signal for semitrailers. 4,297,675, Cl. 340-107.000.
- Rueth, William R., Jr., to G & W Electric Specialty Company. Time delay switch mechanism. 4,297,554, Cl. 200-153.05C.
- Ruhr-Stickstoff Aktiengesellschaft: See—
Norden, Jurgen; and Ucinhazska, Bruno, 4,296,885, Cl. 239-1.000.
- Ruip, Terrence M.: See—
Roberts, Charles W.; Kolowski, Michael A.; Lindner, Daniel J.; Lynch, John E.; Ruip, Terrence M.; and Fetty, Harold D., 4,296,789, Cl. 152-209.00R.
- Rush-Hampton Industries, Inc.: See—
Frazier, Stephen E., 4,297,348, Cl. 424-180.000.
- Ruyak, Robert F., to Autoclave Engineers, Inc. Magnetically actuated metering valve. 4,296,912, Cl. 251-65.000.
- Sabatino, David B. Cutting and splitting tool. 4,296,552, Cl. 30-183.000.
- Sacco, Jean: See—
Rochina, Vincent; and Sacco, Jean, 4,297,478, Cl. 528-336.000.
Rochina, Vincent; and Sacco, Jean, 4,297,479, Cl. 528-336.000.
- Sachetto, Jean-Pierre; and Cuccolo, Sergio, to Centre National pour l'Exploitation des Oceans. Anti-fouling paint. 4,297,137, Cl. 106-15.050.
- Sachs, Wolfgang: See—
Taddicken, Hermann; and Sachs, Wolfgang, 4,296,696, Cl. 112-70.000.
- Sada, Kenzo; and Hayashi, Shigeyuki, to Kubota, Ltd. Casing for a transmission. 4,296,644, Cl. 74-606.00R.
- Saegusa, Takeo: See—
Goto, Jugo; and Saegusa, Takeo, 4,297,449, Cl. 525-329.000.
- Saif-Societe des Accumulateurs Fixes et de Traction: See—
Godard, Pierre; and Billot, Michel, 4,297,629, Cl. 320-7.000.
- Sagae, Masayuki: See—
Tsuchiya, Yoshimi; Sagae, Masayuki; and Mizutani, Hiroshi, 4,297,410, Cl. 428-283.000.
- St. Clair, Richard C.: See—
Dittman, Charles C.; and St. Clair, Richard C., 4,297,622, Cl. 318-254.000.
- St. Joseph Bank and Trust Company, executor: See—
Waikus, Phillip A.; and D'Alelio, Gaetano F., deceased, 4,297,467, Cl. 526-259.000.
- Saitoh, Yuichi: See—
Ogawa, Mutsuo; Koseki, Yuji; Saitoh, Yuichi; Yamaguchi, Shingo; and Katsuragi, Shigeru, 4,297,727, Cl. 358-261.000.
- Sakai Chemical Industry Co., Ltd.: See—
Abe, Kazunobu; Nakatsui, Tadao; and Umaba, Toshikatsu, 4,297,248, Cl. 252-477.00R.
- Sakai, Kiyoshi; Hashimoto, Mitsuru; and Kawakami, Tomiko, to Ricoh Co., Ltd. Electrophotographic element with carbazole hydrazone or anile charge transport compounds. 4,297,426, Cl. 430-59.000.
- Sakai, Yoshihiro; Tanaka, Ryosaku; Kita, Toshio; Shimotake, Munetoshi; Yamada, Tsuguyoshi; and Ueda, Hiroshi, to Bridgestone Tire Company Limited. Light tire bodies using thick cords. 4,296,790, Cl. 152-354.00R.
- Sakamoto, Seiya: See—
Masuda, Tatsunosuke; Ono, Yoshio; and Sakamoto, Seiya, 4,297,724, Cl. 358-93.000.
- Sakharnov, Vasily A.: See—
Paton, Boris E.; Lebedev, Vladimir K.; Kuchuk-Yatsenko, Sergei I.; Sakharnov, Vasily A.; Galyan, Boris A.; and Dobrovolsky, Stanislav D., 4,297,665, Cl. 336-60.000.
- Sakurada, Kenichi; and Nishino, Takaichi, to Nissan Motor Company, Limited; and Tachikawa Spring Company, Limited. Seat with adjustable lumbar supporter. 4,296,965, Cl. 297-284.000.
- Sakurai, Koichi; Furukawa, Takashi; Takechi, Hiroshi; and Matsuo, Munetsugu, to Nippon Steel Corporation. Apparatus for continuously producing a high strength dual-phase steel strip or sheet. 4,296,919, Cl. 266-111.000.
- Saleck, Wilhelm: See—
Bergthaller, Peter; Saleck, Wilhelm; Lapp, Otto; and Mucke, Bruno, 4,297,439, Cl. 430-434.000.
- Salman, Syed, to International Telephone and Telegraph Corp. Electroplating rack. 4,297,197, Cl. 204-297.00W.
- Sanborn, George A. Traveling light display. 4,296,562, Cl. 40-438.000.
- Sanderson, Hendrik J., to U.S. Philips Corporation. Method of controlling the position of a write or read head and a device for carrying out the method. 4,297,733, Cl. 360-77.000.
- Sandner, Michael R.: See—
Ritscher, James S.; and Sandner, Michael R., 4,297,328, Cl. 423-213.200.
- Sandoz, Inc.: See—
Barca, Sandor, 4,297,349, Cl. 424-184.000.
Maulding, Hawkins V., 4,297,353, Cl. 424-247.000.
- Sandoz Ltd.: See—
Baumann, Hans-Peter, 4,297,296, Cl. 260-459.00A.
Neumann, Peter, 4,297,490, Cl. 544-55.000.
- Sandrock, Klaus; and Cordes, Gunter, to Sanol Schwarz-Monheim GmbH. Process for selectively producing isosorbide-5-nitrate. 4,297,286, Cl. 260-347.800.
- Sandvik Aktiebolag: See—
Larsson, Lars E., 4,296,825, Cl. 175-410.000.
- Sanemitsu, Yuzuru; Mizutani, Masato; Sumida, Seizo; Katoh, Haruhiko; Oshio, Hiromichi; and Hashimoto, Shunichi, to Sumitomo Chemical

- Company, Limited. 3,5-Dioxo-1,2,4-triazines. 4,297,129, Cl. 71-93.000.
- Sanford, Michael E.: See—
Detroit, William J.; and Sanford, Michael E., 4,296,813, Cl. 166-293.000.
- Sanol Schwarz-Monheim GmbH: See—
Sandrock, Klaus; and Cordes, Gunter, 4,297,286, Cl. 260-347.800.
- Santa Fe International Corporation: See—
Yenzer, Dennis E.; Cha, John H.; and Abramovich, Dan, 4,297,054, Cl. 405-168.000.
- Sartorelli, Adelmo: See—
Brambilla, Giovanni; and Sartorelli, Adelmo, 4,297,174, Cl. 204-1.500.
- Sasaki, Makoto: See—
Ishibashi, Yoji; Uchiyama, Yoshihiro; Akimoto, Hidetoshi; and Sasaki, Makoto, 4,297,319, Cl. 422-114.000.
- Sasaki, Tohru; Endoh, Hiroyuki; and Ohhira, Hiroshi, to Kureha Kagaku Kogyo Kabushiki Kaisha. Concentric composite conjugate yarns and a process for manufacturing same. 4,297,413, Cl. 428-394.000.
- Sato, Akira: See—
Okano, Hiroshi; and Sato, Akira, 4,296,648, Cl. 74-798.000.
- Sato, Eiichi, to Olympus Optical Company Limited. Electrophotographic process for printing a plurality of copies. 4,297,422, Cl. 430-54.000.
- Sato, Fumio: See—
Kahara, Toshiki; Tamura, Kohki; Ebata, Noboru; Sato, Fumio; and Yoshida, Tomio, 4,297,231, Cl. 252-182.100.
- Sato, Haruyo: See—
Nakata, Minoru; Sato, Haruyo; and Imamura, Shinzo, 4,297,477, Cl. 528-323.000.
- Sato, Hideo; and Shimamune, Takayuki, to Permelec Electrode Ltd. Electrode for use in electrolysis and process for production thereof. 4,297,195, Cl. 204-290.00F.
- Sato, Hisatake; Makino, Masaharu; and Hayashi, Hideo, to Nippon Oil Co. Ltd. Hot melt type traffic paint compositions. 4,297,450, Cl. 525-333.000.
- Sato, Kazuyoshi: See—
Ando, Ryo; and Sato, Kazuyoshi, 4,297,119, Cl. 65-141.000.
- Sato, Kotaro: See—
Kubotera, Kikuo; Sato, Masamichi; Kashiwabara, Akira; and Sato, Kotaro, 4,297,436, Cl. 430-310.000.
- Sato, Kunio: See—
Tadauchi, Masaharu; Sato, Kunio; and Tanno, Kiyohiko, 4,297,715, Cl. 346-150.000.
- Sato, Makoto; Takamatsu, Hiroshi; Miyagawa, Yoshitaka; and Fujii, Etsuo, to Honda Giken Kogyo Kabushiki Kaisha. Anti-skid brake control device. 4,296,972, Cl. 303-119.000.
- Sato, Masamichi: See—
Kubotera, Kikuo; Sato, Masamichi; Kashiwabara, Akira; and Sato, Kotaro, 4,297,436, Cl. 430-310.000.
- Sato, Yoshikatsu: See—
Fujii, Shuzo; and Sato, Yoshikatsu, 4,297,655, Cl. 331-116.00R.
- Sato, Seiji: See—
Kamada, Masataka; and Sato, Seiji, 4,297,228, Cl. 252-92.000.
- Sato, Tsutomu; Ohye, Hideo; Tsukahara, Hirokazu; Senoh, Hideaki; and Torii, Takahiro, to Mitsubishi Paper Mills, Ltd. Color-developing sheet for no-carbon copying process. 4,296,948, Cl. 282-27.500.
- Sato, Shuzo: See—
Fujii, Tadashi; Sato, Shuzo; Muto, Naoki; Hayashi, Mitsuo; Kodama, Akira; and Otani, Masaru, 4,297,486, Cl. 536-17.00R.
- Satomura, Masato: See—
Osada, Chiaki; Satomura, Masato; and Ono, Hisatake, 4,297,470, Cl. 526-304.000.
- Sauber, Charles J. Cargo securing apparatus. 4,297,062, Cl. 410-37.000.
- Saucedo, Rudy E. Portable dishwasher. 4,296,768, Cl. 134-47.000.
- Saunders, Norman B. Heating, lighting and ventilation systems. 4,296,733, Cl. 126-428.000.
- Sauter, Hubert; Zeeh, Bernd; Rentzea, Costin; and Pommer, Ernst-Heinrich, to BASF Aktiengesellschaft. α -Azolyl- α -phenylacetic acid derivatives. 4,297,364, Cl. 424-267.000.
- Sauvage, Henri; and Tarnero, Maurice, to Commissariat a l'Energie Atomique. Apparatus for the continuous processing of compounds in a liquid. 4,297,324, Cl. 422-268.000.
- Savage, David S.: See—
Carlyle, Ian C.; Sleight, Thomas; and Savage, David S., 4,297,351, Cl. 424-241.000.
- Sawada, Satoru: See—
Aoki, Kozo; Sawada, Satoru; Yabuki, Yoshiharu; and Furutachi, Nobuo, 4,297,440, Cl. 430-505.000.
- Sbuelz, Anes; and Marchelli, Francesco, to Societa Italiana Telecomunicazioni Siemens S.p.A. Malfunction detector for a group of cyclically interconnected phase-locked oscillators. 4,297,649, Cl. 331-2.000.
- Scalera, Frank T.: See—
Mitchell, Robert P.; and Scalera, Frank T., 4,296,872, Cl. 221-195.000.
- Scalise, John M.: See—
Macchiariolo, Nick T.; McGuire, Billy G.; and Scalise, John M., 4,297,224, Cl. 210-755.000.
- Schabert, Hans-Peter, to Kraftwerk Union Aktiengesellschaft. Nuclear reactor installation. 4,297,167, Cl. 376-273.000.
- Schaefer, Edward J., to Franklin Electric Co., Inc. Electric motor construction. 4,297,627, Cl. 318-778.000.
- Schaefer, John O., to International Business Machines Corporation. Variable cam profile selection system for single element typewriter. 4,297,041, Cl. 400-161.400.
- Schamper, Thomas J.: See—
Dasher, George F.; and Schamper, Thomas J., 4,297,098, Cl. 8-412.000.
- Scheffler, Knut; and Riege, Ulrich, to Kernforschungszentrum Karlsruhe, GmbH. Method for solidifying aqueous radioactive wastes for non-contaminating storage. 4,297,304, Cl. 264-0.500.
- Scheibel, Edward G., to Suntech, Inc. Solvent extraction of synfuel liquids. 4,297,206, Cl. 208-254.00R.
- Scheible, Howard G.: See—
Carroll, Charles B.; and Scheible, Howard G., 4,297,312, Cl. 264-134.000.
- Schelleng, Robert D.: See—
Pickens, Joseph R.; Schelleng, Robert D.; Donachie, Stephen J.; and Nichol, Thomas J., 4,297,136, Cl. 75-206.000.
- Schenck, Hans-Uwe; and Gulbins, Erich, to BASF Aktiengesellschaft. Adduct and its use. 4,297,255, Cl. 260-18.00F.
- Schepp, Hans-Egon: See—
Romer, Rudolf; and Schepp, Hans-Egon, 4,296,685, Cl. 102-387.000.
- Schering Aktiengesellschaft: See—
Puttner, Reinhold; Buhmann, Ulrich; and Joppien, Harmut, 4,297,361, Cl. 424-263.000.
- Schering Corporation: See—
Blythin, David J., 4,297,355, Cl. 424-248.540.
- Scherzer, Julius; Liu, Anh-Thu; and Sun, Yih-Yau, to Filtrol Corporation. Method of producing pseudoboehmite from aluminum salt solutions. 4,297,325, Cl. 423-122.000.
- Schetter, Thomas C., to Dana Corporation. Transmission interlock. 4,296,642, Cl. 74-475.000.
- Schick, Ludwig: See—
Glaser, Helmut; and Schick, Ludwig, 4,297,632, Cl. 324-51.000.
- Schittenhelm, Rudolf: See—
Schwierz, Gunter; Schittenhelm, Rudolf; Schmitt, Gunter; and Tschunt, Edgar, 4,297,582, Cl. 250-445.00T.
- Schlagmuller, Walter, to Robert Bosch GmbH. Drive arrangement for auxiliary aggregates of an internal combustion engine. 4,296,717, Cl. 123-195.00A.
- Schlauer, Johann; Kempf, Georg; and Doerges, Alexander, to Metallgesellschaft AG. Process of selectively desulfurizing gases. 4,297,330, Cl. 423-232.000.
- Schlegel, Hans; and Nowotny, Theodor, to Wurttembergische Metallwarenfabrik. Process for partially electroplating flat silver. 4,297,175, Cl. 204-15.000.
- Schleppinghoff, Bernhard: See—
Mainusch, Klaus; Schleppinghoff, Bernhard; and Munter, Klaus, 4,297,512, Cl. 564-490.000.
- Schliebener, Claus; and Wernicke, Hans J., to Linde Aktiengesellschaft. Thermal cracking with post hydrogenation and recycle of heavy fractions. 4,297,204, Cl. 208-95.000.
- Schlottke, Karl-Heinz: See—
Ramecke, Bernd; Schlottke, Karl-Heinz; Brandt, Eckhard; and Reissmann, Klaus, 4,297,066, Cl. 414-43.000.
- Schlumpf, Alois, to Tax o mex AG. Automatic vending arrangement. 4,296,873, Cl. 221-213.000.
- Schmid, Franz; and Schmid, Reinhard. Method and apparatus for withdrawing agricultural materials from storage. 4,297,073, Cl. 414-704.000.
- Schmid, Johann, to REPA Feinstanzwerk GmbH. Swivel fitting for fitting parts of a safety belt. 4,296,525, Cl. 16-174.000.
- Schmid, Reinhard: See—
Schmid, Franz; and Schmid, Reinhard, 4,297,073, Cl. 414-704.000.
- Schmidt, Waldemar, to Robert Bosch GmbH. Method for permanent deformation of an elastic member. 4,297,314, Cl. 264-320.000.
- Schmitt, Gunter: See—
Schwierz, Gunter; Schittenhelm, Rudolf; Schmitt, Gunter; and Tschunt, Edgar, 4,297,582, Cl. 250-445.00T.
- Schmitt, Wilhelm E., to Friedman, Jack S. Brush. 4,296,519, Cl. 15-184.000.
- Schnabele, Werner; Buckley, Jack; and Rieger, Ulrich, to Messerschmitt-Bolkow-Blohm GmbH. Drone-type missile. 4,296,894, Cl. 244-3.270.
- Schneider, Claus: See—
Weber, Karl-Heinz; Schneider, Claus; Walther, Gerhard; Pook, Karl-Heinz; Boke, Karin; and Bechtel, Wolf D., 4,297,354, Cl. 424-248.510.
- Schneider, George H.: See—
Armentrout, James L.; and Schneider, George H., 4,296,862, Cl. 206-439.000.
- Schnoes, Heinrich K.: See—
DeLuca, Hector F.; Schnoes, Heinrich K.; Paaren, Herbert E.; and Fivizzani, Mary A., 4,297,289, Cl. 260-397.200.
- Schoenberg, Morris R.: See—
Calamur, Narasimhan; and Schoenberg, Morris R., 4,296,637, Cl. 73-863.110.
- Schonfeld, Bernd: See—
Franz, Karl; and Schonfeld, Bernd, 4,297,390, Cl. 427-64.000.
- Schopper, Heinrich-Christian: See—
Buxbaum, Gunter; Schopper, Heinrich-Christian; Leitner, Lutz; and Hahnkamm, Volker, 4,297,395, Cl. 427-127.000.
- Schramm, Horst. Integrated house. 4,296,798, Cl. 165-56.000.
- Schreck, Raymond M.: See—
Griffin, James R.; and Schreck, Raymond M., 4,296,611, Cl. 62-89.000.

- Schreckenberger, Manfred: See—
Lindner, Christian; Suling, Carlhans; Bartl, Herbert; Schreckenberger, Manfred; Freitag, Dieter; and König, Klaus, 4,297,455, Cl. 525-439.000.
- Schroder, Klaus, to C. & W. Berges Maschinenfabrik, Firma. Extruder for preplasticization of thermoset molding materials. 4,297,036, Cl. 366-77.000.
- Schroeder, Harald: See—
Richarz, Winfried; Froehlich, Helmut; and Schroeder, Harald, 4,297,493, Cl. 544-241.000.
- Schroeder, Hartmut R.: See—
Buckler, Robert T.; and Schroeder, Hartmut R., 4,297,273, Cl. 260-112.00B.
- Schuetz, Heinz G. Helical staircase support. 4,296,577, Cl. 52-187.000.
- Schulein, Benjamin M., Jr., to Alfa-Pet, Inc. Animal litter preparation. 4,296,709, Cl. 119-1.000.
- Schulze-Berge, Klaus: See—
Manzke, Klaus; Brotzler, Roland; and Schulze-Berge, Klaus, 4,297,736, Cl. 360-109.000.
- Schwab, Thomas C.: See—
Miller, John G.; and Schwab, Thomas C., 4,297,131, Cl. 75-1.00T.
- Schwartz, Robert E.: See—
Reed, Robert D.; Schwartz, Robert E.; and Kraft, Raymond D., 4,297,094, Cl. 431-202.000.
- Schwarz, Rudolf: See—
Kleinschmitt, Peter; and Schwarz, Rudolf, 4,297,143, Cl. 501-103.000.
- Schwierz, Gunter; Schittenhelm, Rudolf; Schmitt, Gunter; and Tschunt, Edgar, to Siemens Aktiengesellschaft. Radiation diagnostic device for generating tomographic images. 4,297,582, Cl. 250-445.00T.
- Schwinn, Horst; Heimbürger, Norbert; Kump, Gerhardt; and Herchenhan, Bernd, to Behringwerke Aktiengesellschaft. Blood coagulation factors and process for their manufacture. 4,297,344, Cl. 424-101.000.
- Schwob, Pierre, to SEB S.A. Water injection device for a steam iron. 4,296,560, Cl. 38-77.810.
- Scifres, Donald R.; and Stutius, Wolfgang E., to Xerox Corporation. Hybrid semiconductor laser/detectors. 4,297,653, Cl. 331-94.50S.
- SEB S.A.: See—
Schwob, Pierre, 4,296,560, Cl. 38-77.810.
- Sebag, Henry: See—
Vanlerberghe, Guy; and Sebag, Henry, 4,297,102, Cl. 8-406.000.
- Seidel, Martin P., to Westinghouse Electric Corp. Low temperature curing epoxy resin. 4,297,254, Cl. 260-18.0EP.
- Seki, Yoshiro; Kobayashi, Hideo; Kimura, Kiyoshi; and Naito, Masayuki, to Anritsu Electric Company Limited. Multi-item data input apparatus. 4,297,028, Cl. 355-41.000.
- Sekisui Kagaku Kogyo Kabushiki Kaisha: See—
Fujimaki, Kiyoshi; Bando, Yoshiaki; Okuyama, Takeshi; and Hashimoto, Tutomu, 4,296,954, Cl. 285-331.000.
- Sekisui Kaseihin Kogyo Kabushiki Kaisha: See—
Sugito, Kazuo; and Takeda, Sakuzo, 4,297,109, Cl. 44-56.000.
- Sele, Alex: See—
Haas, Georges; Jaeggi, Knut A.; Rossi, Alberto; and Sele, Alex, 4,297,358, Cl. 424-256.000.
- Selines, Ronald J.: See—
Kilinskas, William A.; Selines, Ronald J.; and Vand den Sype, Jaak S., 4,296,512, Cl. 10-27.00E.
- Semenov, Vasily V.: See—
Bashnin, Oleg I.; Semenov, Vasily V.; Fedorov, Vasily N.; Gorbunov, Nikolai M.; Rodionov, Evgeny I.; and Sorokin, Nikolai A., 4,297,589, Cl. 290-40.00R.
- Semiconductor Research Foundation Mitsubishi Denki K.K.: See—
Nishizawa, Jun-ichi; and Katsuregawa, Takashi, 4,297,718, Cl. 357-22.000.
- Senet, Jean-Pierre G.: See—
Lecolier, Serge L.; and Senet, Jean-Pierre G., 4,297,301, Cl. 260-544.00K.
- Senoh, Hideaki: See—
Satoh, Tsutomu; Ohye, Hideo; Tsukahara, Hirokazu; Senoh, Hideaki; and Torii, Takahiro, 4,296,948, Cl. 282-27.500.
- Serac: See—
Graffin, Andre J., 4,297,161, Cl. 156-583.300.
- Sermon, Paul A., to Johnson, Matthey & Co., Limited. Catalysis. 4,297,331, Cl. 423-239.000.
- Severijns, Adrianus P.; and Staas, Frans A., to U.S. Philips Corporation. ³He-⁴He refrigerator. 4,296,609, Cl. 62-514.00R.
- Seymour, Raymond K.; and Murphy, Frank H., to General Electric Company. Circuit breaker accessories packaged in a standardized molded case. 4,297,663, Cl. 335-20.000.
- Shackcloth, Barry, to Total Oil Great Britain Limited. Safety device for container filler systems. 4,297,543, Cl. 200-18.000.
- Shackelford, John R., to Standard Oil Company (Indiana). Salt substitutes having reduced bitterness. 4,297,375, Cl. 426-62.000.
- Shah, Narendra K.: See—
Elias, Moenes L.; and Shah, Narendra K., 4,297,257, Cl. 260-29.60H.
- Shah, Siddharth A.; Woodcock, Sidney J.; and Fagan, Robert D., to General Electric Company. Manway handling apparatus. 4,297,072, Cl. 414-684.300.
- Sharp Kabushiki Kaisha: See—
Hashimoto, Sadakatsu, 4,297,696, Cl. 340-785.000.
- Shatai Kogyo Kabushiki Kaisha: See—
Terada, Takami, 4,296,966, Cl. 297-369.000.
- Shaw, Manuel; and Thatcher, Imbrie, to Interscan Corporation. Personal-carried dosimeter. 4,297,689, Cl. 340-632.000.
- Shell Oil Company: See—
Davis, Royston H.; and Davies, John H., 4,297,496, Cl. 544-332.000.
- Mango, Frank D., 4,297,294, Cl. 260-453.0PH.
- Mast, Harm, 4,296,628, Cl. 73-28.000.
- Van Broekhoven, Johannes A. M.; and Drent, Eit, 4,297,517, Cl. 568-361.000.
- Shepherd, Margaret C.: See—
Henrick, Clive A.; Labovitz, Jeffrey N.; Fox, Roland T. V.; Rathmell, William G.; and Shepherd, Margaret C., 4,297,297, Cl. 260-465.00D.
- Shepherd, Roger D.: See—
Bach, Paul S.; Harding, Steven R.; Lamos, Richard A.; Markham, Harvey R.; and Shepherd, Roger D., 4,297,025, Cl. 355-14.0SH.
- Sherman, Norman; and Cameron, John H., to Conwed Corporation. Method of manufacturing improved mineral board. 4,297,311, Cl. 264-109.000.
- Sherman, Paul D., Jr.: See—
Kavasanek, Percy R.; Stanton, David B.; and Sherman, Paul D., Jr., 4,297,241, Cl. 252-435.000.
- Sherwood Medical Industries Inc.: See—
Joslin, Joel A.; and Ranford, Alan B., 4,296,759, Cl. 128-766.000.
- Shibanaka, Akira: See—
Takahashi, Koichi; Hinata, Fumio; and Shibanaka, Akira, 4,296,719, Cl. 123-198.00F.
- Shibuya, Yasutaka: See—
Kodama, Kazuyuki; Okada, Kunihiro; Endoh, Takeyuki; and Shibuya, Yasutaka, 4,297,691, Cl. 340-723.000.
- Shigeta, Yoshihiro: See—
Kawamura, Masaharu; Uchidoi, Masanori; Shigeta, Yoshihiro; Sugiura, Yoji; and Yamamoto, Hiroshi, 4,297,013, Cl. 354-23.00D.
- Shiina, Yuichi: See—
Tokunaga, Shinobu; and Shiina, Yuichi, 4,297,141, Cl. 501-67.000.
- Shimamura, Takayuki: See—
Sato, Hideo; and Shimamura, Takayuki, 4,297,195, Cl. 204-290.00F.
- Shimano Industrial Company, Limited: See—
Isobe, Mitsuhide, 4,296,850, Cl. 192-64.000.
- Shimizu, Ken-ichi; and Ikeya, Chuji, to Agency of Industrial Science & Technology; and Ministry of International Trade & Industry. Method for measurement of displacement of moving body by use of target mark and apparatus therefor. 4,297,725, Cl. 358-125.000.
- Shimizu, Michimasa: See—
Ueno, Haruo; Yano, Takefumi; Inoue, Tokuji; Ikai, Shigeru; Kai, Yoshiyuki; and Shimizu, Michimasa, 4,297,463, Cl. 526-128.000.
- Shimotake, Munetoshi: See—
Sakai, Yoshihiro; Tanaka, Ryosaku; Kita, Toshio; Shimotake, Munetoshi; Yamada, Tsuguyoshi; and Ueda, Hiroshi, 4,296,790, Cl. 152-354.00R.
- Shimmyo, Saburo, to Nippon Electric Co., Ltd. Phase locked loop carrier recovery circuit with false lock prevention. 4,297,650, Cl. 331-11.000.
- Shinohara, Hiroshi; Otsuka, Yasuhiro; Matsumoto, Shinichi; Wakisaka, Hiroshi; and Furutani, Toshinobu, to Toyota Jidosha Kogyo Kabushiki Kaisha. Catalyst supported oxygen sensor element and a method of manufacturing same. 4,297,192, Cl. 204-195.00S.
- Shionogi & Co., Ltd.: See—
Hirai, Kentaro; Matsutani, Shigeru; Ishiba, Teruyuki; and Makino, Itsuo, 4,297,280, Cl. 260-245.500.
- Shirai, Akira: See—
Fujimori, Fumio; Yokoi, Masatada; Ishikawa, Masakazu; Uemura, Hiroshi; and Shirai, Akira, 4,296,841, Cl. 188-73.380.
- Shirasu, Hiroshi: See—
Utagawa, Ken; Hoshino, Kunihisa; Shirasu, Hiroshi; and Ogawara, Akira, 4,297,571, Cl. 250-201.000.
- Shlykov, Gennady N.; Zhestkov, Vitaly I.; Tikhonov, Valentin N.; Dyachkov, Vasily M.; Glazov, Vladimir G.; and Krjuk, Timur P. Drawing mechanism. 4,296,528, Cl. 19-255.000.
- Shono, Tatsuya. Process for preparing ketones. 4,297,181, Cl. 204-78.000.
- Short, James N.; and Norwood, Donald D., to Phillips Petroleum Co. Continuous production of olefin block copolymers. 4,297,445, Cl. 525-52.000.
- Shumway, Anthony G. Folded circuit switch apparatus having multiple contacts. 4,297,542, Cl. 200-6.00A.
- Shur-Lok International, S.A.: See—
Heurteux, Bernard M., 4,296,586, Cl. 52-787.000.
- Sico Incorporated: See—
Wilson, Kermit H.; and Carlson, Ronald R., 4,296,573, Cl. 52-6.000.
- Sidaway, H. John; and Good, Maynard, to Hancor, Inc. Expandable core for rolls of tubing. 4,296,891, Cl. 242-110.000.
- Siemens Aktiengesellschaft: See—
Brunner, Anton; and Willburger, Nikolaus, 4,297,707, Cl. 343-725.000.
- Dalhof, Axel; and Lechner, Robert, 4,297,531, Cl. 179-16.0AA.
- Glaser, Helmut; and Schick, Ludwig, 4,297,632, Cl. 324-51.000.
- Gross, Franz; Boehme, Gerit; Wiehler, Wolf; and Bibracher, Wilhelm, 4,297,662, Cl. 333-252.000.
- Kuger, Manfred; Nawrot, Wolfgang; and Preuss, Bernhard, 4,297,664, Cl. 335-176.000.
- Roesler, Helmut; and Muehlbauer, Otto, 4,297,591, Cl. 307-224.00C.

- Schwierz, Gunter; Schittenhelm, Rudolf; Schmitt, Gunter; and Tschunt, Edgar, 4,297,582, Cl. 250-445.00T.
- Url, Karlheinz; and von Basse, Paul W., 4,297,592, Cl. 307-583.000.
- Sigmund, Paul W.; and Butwell, Kenneth F., to Union Carbide Corporation. Vapor-liquid contacting system. 4,297,329, Cl. 423-228.000.
- Sih, John C., to Upjohn Company. The 19-Hydroxy-6a-carba-PG1₁ compounds. 4,297,504, Cl. 560-119.000.
- Silcox, David R.; and Doster, John L., to RCA Corporation. Filament winding apparatus. 4,297,095, Cl. 432-59.000.
- Silk, John K., to American Science and Engineering, Inc. Parabolic trough concentrating solar collector. 4,296,737, Cl. 126-438.000.
- Sillers, William M., III. Automatic feeding apparatus. 4,296,710, Cl. 119-51.110.
- Silver, Alexander: See—
Burgmeier, Lyman R.; McCarty, Frederick B.; and Silver, Alexander, 4,296,544, Cl. 29-598.000.
- Simmonds Precision Products, Inc.: See—
Maier, Lawrence C., 4,297,692, Cl. 340-715.000.
- Simmons, Dwane P.; and Lynn, Ray E. Portable invalid lift. 4,296,509, Cl. 5-81.00R.
- Simmons, Robert B.: See—
Crawford, Roger A.; and Simmons, Robert B., 4,297,333, Cl. 423-241.000.
- Simon Engineering Dudley Limited: See—
Ashworth, Denis H., 4,296,833, Cl. 182-2.000.
- Simon, Manfred; Moschier, Erwin; Spiess, Karl-Heinz; and Weiss, Richard, to Dynatit Nobel Aktiengesellschaft. Process for the production of a synthetic resin sheet material which is dyed unicolor or multicolored in accordance with a pattern. 4,297,099, Cl. 8-484.000.
- Simon-Rosedowns Limited: See—
Naylor, Leonard, 4,297,112, Cl. 55-195.000.
- Simpson, Harold G.; and Davis, Michael W., to Star Manufacturing Company of Oklahoma. Construction system and fasteners therefor. 4,296,582, Cl. 52-590.000.
- Sims, Malcolm L.: See—
Foster, Alan I.; Sims, Malcolm L.; and Young, Dennis, 4,297,150, Cl. 148-6.300.
- Singer Company, The: See—
Davidson, Donald R.; and Marsh, Walter H. W., 4,296,698, Cl. 112-110.000.
- Larsen, Robert H., 4,296,701, Cl. 112-168.000.
- Lauritsen, Richard L.; and Mandellos, Panagiotis K., 4,297,552, Cl. 200-83.00P.
- Vartoukian, Artin G., 4,296,699, Cl. 112-121.150.
- Whitby, Clyde M., 4,297,723, Cl. 358-60.000.
- Singewald, Arno; Geisler, Irving; Fricke, Gunter; and Knappe, Rudolf, to Kali and Salz AG. Process and apparatus for the electrostatic dressing of carnallite-containing crude potassium salts. 4,297,207, Cl. 209-9.000.
- Singh, Baldev: See—
Leshner, George Y.; and Singh, Baldev, 4,297,362, Cl. 424-263.000.
- Leshner, George Y.; and Singh, Baldev, 4,297,363, Cl. 424-263.000.
- Singh, Shobha: See—
Johnson, David W., Jr.; Singh, Shobha; Van Uitert, LeGrand G.; and Zydzik, George J., 4,297,005, Cl. 350-357.000.
- SKF Kugellagerfabriken GmbH: See—
Loser, Norbert; and Tilgner, Leopold, 4,296,978, Cl. 308-37.000.
- Sklenky, Alden F.: See—
Buchanan, Robert A.; Maple, T. Grant; and Sklenky, Alden F., 4,297,584, Cl. 250-483.000.
- Skomoroski, Robert M., to American Chemical & Refining Company Incorporated. Palladium electroplating bath and process. 4,297,179, Cl. 204-47.000.
- Slater Electric Inc.: See—
Bowden, Wade R., Jr., 4,297,525, Cl. 174-58.000.
- Slater, Peter G. Carrying device. 4,296,788, Cl. 150-52.00R.
- Sleigh, Thomas: See—
Carlyle, Ian C.; Sleigh, Thomas; and Savage, David S., 4,297,351, Cl. 424-241.000.
- Slettinger, Meyer: See—
Christensen, Burton G.; Cama, Lovji D.; Karady, Sandor; and Slettinger, Meyer, 4,297,488, Cl. 544-21.000.
- Smart, Michael W.: See—
Andrews, David K.; and Smart, Michael W., 4,296,676, Cl. 91-417.00R.
- Smearing, Robert W., to General Electric Company. Antifoaming resin compositions. 4,297,389, Cl. 427-58.000.
- Smick, Ronald H. Turbulator with ganged strips. 4,296,779, Cl. 138-38.000.
- Smith, Douglas R.: See—
Rivenbark, Morrison, 4,297,223, Cl. 210-754.000.
- Smith, Elroy C., Jr.; and Yao, Shi K., to Rockwell International Corporation. Deposition of ordered crystalline films. 4,297,189, Cl. 204-192.0SP.
- Smith, Gordon J.: See—
Lammers, Gerald B.; and Smith, Gordon J., 4,297,712, Cl. 346-75.000.
- Smith, Harry D., Jr.; Arnold, Dan M.; and Smith, Kenneth J., to Halibuton Company. Simultaneous gamma ray measurement of formation bulk density and casing thickness. 4,297,575, Cl. 250-265.000.
- Smith, Kenneth J.: See—
Smith, Harry D., Jr.; Arnold, Dan M.; and Smith, Kenneth J., 4,297,575, Cl. 250-265.000.
- Smith, Kent F., to General Instrument Corporation. I²L Sensing circuit with increased sensitivity. 4,297,598, Cl. 307-355.000.
- Smith, Mark A.: See—
Smith, Robert J.; Smith, Mark A.; Jensen, Michael E.; and Smith, Robert L., 4,297,120, Cl. 65-281.000.
- Smith, Millard S.: See—
Wyse, Harold G.; and Smith, Millard S., 4,297,123, Cl. 71-58.000.
- Smith, Robert J.; Smith, Mark A.; Jensen, Michael E.; and Smith, Robert L. Glass bending table. 4,297,120, Cl. 65-281.000.
- Smith, Robert L.: See—
Smith, Robert J.; Smith, Mark A.; Jensen, Michael E.; and Smith, Robert L., 4,297,120, Cl. 65-281.000.
- Smith, Thomas M., to Monarch Marking Systems, Inc. Coreless pressure sensitive label supply roll. 4,297,403, Cl. 428-42.000.
- Smith, Thomas W., to Eastman Kodak Company. Catalysts for polymerizing propylene in a high temperature solution process. 4,297,465, Cl. 526-141.000.
- Smitka, Gunter. Device for attaching two metal sheets or blanks together. 4,297,049, Cl. 403-403.000.
- Snamprogetti S.p.A.: See—
Corbellini, Margherita; Greco, Alberto; and Osellame, Mirko, 4,297,462, Cl. 526-125.000.
- Snia Viscosa Società Nazionale Industria Applicazioni Viscosa S.p.A.: See—
Manca, Francesco, 4,297,407, Cl. 428-224.000.
- Soboczenski, Edward J., to Du Pont de Nemours, E. I., and Company. Insecticidal compositions. 4,297,370, Cl. 424-298.000.
- Socapex: See—
Malsot, Christian; and Bouygues, Jean, 4,296,997, Cl. 350-96.200.
- Società Italiana Telecomunicazioni Siemens S.p.A.: See—
Sbuelz, Anes; and Marchelli, Francesco, 4,297,649, Cl. 331-2.000.
- Société Anonyme dite: Ramo S.A.: See—
Champeau, Marcel; and Tabutin, Andre, 4,296,658, Cl. 82-30.000.
- S.A. PRB Société Anonyme: See—
Orlandi, Robert G., 4,296,688, Cl. 102-218.000.
- Société d'Assistance Technique pour Produits Nestlé S.A.: See—
Horman, Ian; and Cazenave, Paul, 4,297,380, Cl. 426-597.000.
- Société d'Etude du Radant: See—
Vidal, Paul, 4,297,708, Cl. 343-754.000.
- Société d'Etudes de Machines Thermiques S.E.M.T.: See—
Curtill, Remi; and Devaux, Alain, 4,296,715, Cl. 123-90.150.
- Société d'Etudes de Produits Chimiques: See—
Esanu, Andre, 4,297,495, Cl. 544-330.000.
- Société d'Etudes, Recherches et Constructions Electroniques Sercel: See—
Nard, Georges; Rabian, Jean; and Rouaud, Michel, 4,297,700, Cl. 343-6.50R.
- Société Minière et Metallurgique de Penarroya: See—
Georgeaux, Andre, 4,297,183, Cl. 204-117.000.
- Société Nationale des Poudres et Explosifs: See—
Lecolier, Serge L.; and Senet, Jean-Pierre G., 4,297,301, Cl. 260-544.00K.
- Société Nationale Industrielle Aérospatiale: See—
Hoffmann, Jean-Claude; Castanie, Francis; Crabere, Henri; Verdier, Jean-Pierre; and Voisin, Norbert, 4,297,744, Cl. 364-703.000.
- Solar Kinetics, Inc.: See—
Hutchison, Joseph A., 4,297,003, Cl. 350-292.000.
- Solarex Corporation: See—
Lindmayer, Joseph, 4,297,391, Cl. 136-256.000.
- Solomon, Edward T.: See—
Priest, Clayton W.; and Solomon, Edward T., 4,296,763, Cl. 132-7.000.
- Solomon, Paul W.: See—
Uranek, Carl A.; Burleigh, John E.; and Solomon, Paul W., 4,297,451, Cl. 525-366.000.
- Solow, Benjamin, to Angstrom Precision, Inc. Metal foil resistor. 4,297,670, Cl. 338-195.000.
- Sommer, Karl: See—
Krabetz, Richard; Herrmann, Walter; Engelbach, Heinz; Palm, Peter; Sommer, Karl; and Spahn, Heinrich, 4,297,247, Cl. 252-468.000.
- Soot, Olaf. Folded plate solar energy collector. 4,296,736, Cl. 126-438.000.
- Sorbier, Pierre. Method of making moldable product. 4,297,253, Cl. 260-17.300.
- Sorokin, Nikolai A.: See—
Bashnin, Oleg I.; Semenov, Vasily V.; Fedorov, Vasily N.; Gorbunov, Nikolai M.; Rodionov, Evgeny I.; and Sorokin, Nikolai A., 4,297,589, Cl. 290-40.00R.
- Spaeth, Tilman P., to Bodenseewerk Geosystem GmbH. Bi-frequency infrared spectrometer. 4,297,579, Cl. 250-343.000.
- Spahn, Heinrich: See—
Krabetz, Richard; Herrmann, Walter; Engelbach, Heinz; Palm, Peter; Sommer, Karl; and Spahn, Heinrich, 4,297,247, Cl. 252-468.000.
- Spak, Mark A.: See—
Denning, Richard; Spak, Mark A.; and Polhemus, Barry, 4,297,393, Cl. 427-88.000.
- Sparrell, Patricia T.: See—
Vogt, Frederick G., deceased; and Sparrell, Patricia T., 4,297,317, Cl. 422-16.000.
- Spatz, Sydney M.; Hydel, Robert C.; and Davis, Gerald T., to Mead Corporation. The Pressure-sensitive transfer sheets using novel radiation curable coatings. 4,296,947, Cl. 282-27.500.
- Speak, Richard C.; and Fern, Donald J., to United States Borax & Chemical Corporation. Particulate borate-soap compositions. 4,297,229, Cl. 252-109.000.

Specia, Anthony N., to National Petro Chemicals Corp. Olefin polymerization catalyst. 4,297,461, Cl. 526-100.000.

Spektor, Gerald A. Accessory for an apparatus for repairing and straightening. 4,296,624, Cl. 72-308.000.

Sperry Corporation: See—
Martens, Wayne B.; Priepke, Edward H.; and Wagstaff, Robert A., 4,296,591, Cl. 56-10.300.
McIlwain, Irwin D., 4,296,592, Cl. 56-14.400.
Spilsbury, Thomas W., 4,297,618, Cl. 315-371.000.
Spilsbury, Thomas W., 4,297,621, Cl. 315-397.000.
Waldrop, T. William; and Campbell, Willis R., 4,296,596, Cl. 56-341.000.

Sperry - New Holland: See—
Webb, Bryant F.; Makofka, Stanley J.; Webster, Emmett G.; and Blakeslee, Edward A., 4,296,593, Cl. 56-98.000.

Spies, Karl-Heinz: See—
Simon, Manfred; Moschter, Erwin; Spiess, Karl-Heinz; and Weiss, Richard, 4,297,099, Cl. 8-484.000.

Spilsbury, Thomas W., to Sperry Corporation. Anode voltage deflection gain control for cathode ray displays. 4,297,618, Cl. 315-371.000.

Spilsbury, Thomas W., to Sperry Corporation. Cathode ray tube beam deflection amplifier system. 4,297,621, Cl. 315-397.000.

Spinner GmbH Elektrotechnische Fabrik: See—
Treczka, Leo, 4,297,658, Cl. 333-113.000.

Spletzer, Barry L., to Gerber Products Company. Flexible convex diaphragm sound reproducing device. 4,297,682, Cl. 340-384.00E.

Spodig, Heinrich. Magnetic separator having two rotating magnetic drums of opposite polarity. 4,296,865, Cl. 209-216.000.

Square D Company: See—
Lingaraju, Bhartoor, 4,296,987, Cl. 339-95.00D.

Staas, Frans A.: See—
Severijns, Adrianus P.; and Staas, Frans A., 4,296,609, Cl. 62-514.00R.

Staclean Diffuser Company: See—
Johnson, Allen S., Jr., 4,297,115, Cl. 55-302.000.

Staffa, Jeffrey A.: See—
Lionelle, Joseph E.; and Staffa, Jeffrey A., 4,297,291, Cl. 260-410.90R.

Stahlschmitt, Horst: See—
Barth, Karl; Albrecht, Ernst; and Stahlschmitt, Horst, 4,296,697, Cl. 112-109.000.

Stalder, John L.; and Martin, William L., to Conoco Inc. Method for thermally insulating wellbores. 4,296,814, Cl. 166-303.000.

Stan Herman Studio, Inc.: See—
Herman, Seymour S., 4,296,497, Cl. 2-114.000.

Standard Oil Company (Indiana): See—
Calamur, Narasimhan; and Schoenberg, Morris R., 4,296,637, Cl. 73-863.110.
Ford, William D.; and Clark, Michael J., 4,297,203, Cl. 208-74.000.
Hensley, Albert L., Jr.; and Quick, Leonard M., 4,297,242, Cl. 252-439.000.
Mieville, Rodney L., 4,297,205, Cl. 208-138.000.
Shackelford, John R., 4,297,375, Cl. 426-62.000.

Stanton, David B.: See—
Kavasmeneck, Percy R.; Stanton, David B.; and Sherman, Paul D., Jr., 4,297,241, Cl. 252-435.000.

Star Manufacturing Company of Oklahoma: See—
Simpson, Harold G.; and Davis, Michael W., 4,296,582, Cl. 52-590.000.

Stark, Charles J., Jr., to General Electric Company. Curable epoxy resin composition. 4,297,457, Cl. 525-507.000.

Stark, Charles J., Jr., to General Electric Company. Curable epoxy resins. 4,297,458, Cl. 525-507.000.

Stark, Charles J., Jr., to General Electric Company. Curable epoxy resins. 4,297,459, Cl. 525-507.000.

Static Systems Corporation: See—
Lester, Robert W., 4,297,022, Cl. 355-3.00R.

Staub, Vincent M., Jr., to General Motors Corporation. Flexible clutch with an elastomeric vibration damper. 4,296,854, Cl. 192-106.100.

Stauffer Chemical Company: See—
Gaughan, Edmund J.; and Kezerian, Charles, 4,297,295, Cl. 260-455.00A.
Hosaka, Dennis B., 4,297,382, Cl. 426-656.000.
Weil, Edward D., 4,297,138, Cl. 106-18.180.

Stead, John C.; and Waghorn, Peter E., to Imperial Chemical Industries Limited. Laminates of cloth and filled crystalline polypropylene and a method for making them. 4,297,408, Cl. 428-240.000.

Steele, Everett T., Jr., to Robertshaw Controls Company. Control system having an improved condition responsive valve construction. 4,296,721, Cl. 123-407.000.

Steele, Richard S. Solar water tank and method of making same. 4,296,799, Cl. 165-74.000.

Steffen, Klaus-Dieter: See—
Herrmann, Hans-Joachim; Meyer, Gunther; and Steffen, Klaus-Dieter, 4,297,502, Cl. 560-35.000.

Stegens, Ronald E., to Communications Satellite Corporation. Ferrite substrate microwave filter. 4,297,661, Cl. 333-204.000.

Steinhilper, Eric A.: See—
Kosek, Thomas P.; and Steinhilper, Eric A., 4,296,888, Cl. 239-403.000.

Stejskal, Joseph F.: See—
Klein, Gary H.; Arons, Howard L.; Stejskal, Joseph F.; Stevens, Donald G.; and Zobel, Henry F., 4,297,144, Cl. 106-197.00C.

Stemme, Otto; Fergg, Berthold; Osegoewitsch, Viktor; and Viehrig, Wolfgang, to Agfa-Gevaert AG. Apparatus for exposing and developing photosensitive material. 4,297,027, Cl. 355-27.000.

Stendel, Wilhelm: See—
Fuchs, Rainer; Hammann, Ingeborg; Homeyer, Bernhard; Behrenz, Wolfgang; and Stendel, Wilhelm, 4,297,366, Cl. 424-274.000.
Fuchs, Rainer; Gallenkamp, Bernd; and Stendel, Wilhelm, 4,297,371, Cl. 424-304.000.

Stephens, William I., to Knoll International, Inc. Floor panel-furniture support system. 4,296,574, Cl. 52-27.000.

Sterling Drug Inc.: See—
Leshner, George Y.; Opalka, Chester J., Jr.; and Page, Donald F., 4,297,360, Cl. 424-263.000.
Leshner, George Y.; and Singh, Baldev, 4,297,362, Cl. 424-263.000.
Leshner, George Y.; and Singh, Baldev, 4,297,363, Cl. 424-263.000.

Sterzer, Fred, to RCA Corporation. Serrodyne system employing an adjustable phase shifting circuit. 4,297,641, Cl. 328-15.000.

Stevens, Donald G.: See—
Klein, Gary H.; Arons, Howard L.; Stejskal, Joseph F.; Stevens, Donald G.; and Zobel, Henry F., 4,297,144, Cl. 106-197.00C.

Stevens, Francis J., to General Electric Company. Watthour meter and battery retaining apparatus therefor. 4,297,635, Cl. 324-156.000.

Steynor, James H.; and Hayes, Frederick, to EMI Limited. Encoding and decoding of digital recordings. 4,297,729, Cl. 360-40.000.

Stock, Hugh J.: See—
Kusayama, Senji; Nishi, Eijiro; and Stock, Hugh J., 4,297,160, Cl. 156-331.100.

Stockburger, George J., to ICI Americas Inc. Process for preparing sorbitan esters. 4,297,290, Cl. 260-410.600.

Stokkers, Henk, to Maryland Cup Corporation. Lidded container structure and package structure for same. 4,296,863, Cl. 206-504.000.

Stone & Webster Engineering Corp.: See—
Charlton, Webster T., 4,296,837, Cl. 184-15.00R.

Stoneleigh Trust, The: See—
Massa, Frank, 4,297,538, Cl. 179-180.000.

Stoute, Neville, Sr.; and Pennise, Robert J., to Falborn, James A.; and Bird, Richard M., part interest to each. Invalid chair. 4,296,506, Cl. 4-480.000.

Stowers, Jeffery P.; and Stowers, Kimball E., to Virginia Panel Corporation. Electrical connector having insulated locking shell for use on panel having metal ground plane. 4,296,990, Cl. 339-128.000.

Stowers, Kimball E.: See—
Stowers, Jeffery P.; and Stowers, Kimball E., 4,296,990, Cl. 339-128.000.

Strahan, Virgil H.: See—
Quick, William H.; James, Kenneth A.; and Strahan, Virgil H., 4,296,994, Cl. 350-3.730.

Stranders, Roelof J., to Werner Weber Holding AB. Holder for liquid packaging containers. 4,296,958, Cl. 294-27.00H.

Straslicka, William A., to Carrier Corporation. Method of providing a sealing assembly between a steam chest and turbine casing. 4,296,538, Cl. 29-156.40R.

Streifling, Michael R. Alfalfa pelletizing apparatus. 4,297,091, Cl. 425-84.000.

Studebaker, Irving G.: See—
Ricketts, Thomas E.; Hutchins, Ned M.; and Studebaker, Irving G., 4,296,968, Cl. 299-2.000.

Sturgeon, Benjamin R.: See—
Anzaldua, Alfred B.; Anzaldua, David A.; and Sturgeon, Benjamin R., 4,296,924, Cl. 272-117.000.

Stutius, Wolfgang E.: See—
Scifres, Donald R.; and Stutius, Wolfgang E., 4,297,653, Cl. 331-94.50S.

Sudarsanam, Vasudevan: See—
Rajappa, Srinivasachari; and Sudarsanam, Vasudevan, 4,297,365, Cl. 424-270.000.

Sugano, Kazuhiko: See—
Iwanaga, Kazuyoshi; Sugano, Kazuhiko; and Ohtsuka, Kunio, 4,296,651, Cl. 74-869.000.

Sugasawa, Fukashi: See—
Iizuka, Haruhiko; and Sugawara, Fukashi, 4,296,724, Cl. 123-568.000.

Sugimoto, Norimaro: See—
Kinbara, Koichi; Sugimoto, Norimaro; and Nakazawa, Toshitaka, 4,297,402, Cl. 428-35.000.

Sugito, Kazuo; and Takeda, Sakuzo, to Sekisui Kaseihin Kogyo Kabushiki Kaisha. Fuel composition. 4,297,109, Cl. 44-56.000.

Sugiura, Susumu: See—
Hirayama, Kazuhiro; and Sugiura, Susumu, 4,297,716, Cl. 346-153.100.

Sugiura, Yoji: See—
Kawamura, Masaharu; Uchidoi, Masanori; Shigeta, Yoshihiro; Sugiura, Yoji; and Yamamoto, Hiroshi, 4,297,013, Cl. 354-23.00D.

Suhac, Peter; Hafner-Milac, Natasa; and Dolenc, Bozidar, to LEK, tovarna farmacevtskih in kemskih izdelkov. n.s.o. Sodium aluminoglucoheptonate and a process for its preparation. 4,297,293, Cl. 260-448.00B.

Suling, Carlhans: See—
Lindner, Christian; Suling, Carlhans; Bartl, Herbert; Schreckenberger, Manfred; Freitag, Dieter; and Konig, Klaus, 4,297,455, Cl. 525-439.000.

Sulkowski, Theodore S.; Bergey, James L.; and Mascitti, Albert A., to American Home Products Corporation. Method of suppressing cardiac arrhythmias. 4,297,373, Cl. 424-322.000.

Sullivan, Charles I., to Polaroid Corporation. Diffusion control layers in diffusion transfer photographic products. 4,297,431, Cl. 430-215.000.

Sulzer Brothers Limited: See—
Billar, Efm, 4,297,511, Cl. 564-331.000.

Sumida, Seizo: See—
Sanemitsu, Yuzuru; Mizutani, Masato; Sumida, Seizo; Katoh, Haruhiko; Oshio, Hiromichi; and Hashimoto, Shunichi, 4,297,129, Cl. 71-93.000.

Sumita Optical Glass Manufacturing Co., Ltd.: See—
Tokunaga, Shinobu; and Shiina, Yuichi, 4,297,141, Cl. 501-67.000.

Sumitomo Bakelite Company Limited: See—
Koshibe, Shigeru; and Nanjo, Motoyuki, 4,297,473, Cl. 528-144.000.

Sumitomo Chemical Company, Ltd.: See—
Kusayama, Senji; Nishi, Eijiro; and Stock, Hugh J., 4,297,160, Cl. 156-331.100.

Maegawa, Yuzo; Masuko, Fujio; and Nakamura, Makoto, 4,297,508, Cl. 562-425.000.

Ohashi, Naohito; Nagata, Shoji; and Katsube, Junki, 4,297,282, Cl. 260-326.200.

Sanemitsu, Yuzuru; Mizutani, Masato; Sumida, Seizo; Katoh, Haruhiko; Oshio, Hiromichi; and Hashimoto, Shunichi, 4,297,129, Cl. 71-93.000.

Sumitomo Electric Industries, Ltd.: See—
Nishiyama, Yukinori; and Ichikawa, Hideji, 4,296,843, Cl. 188-73.430.
Nishizawa, Hideaki; and Iguchi, Shin-Ichi, 4,297,720, Cl. 357-30.000.

Sumitomo, Hiroyuki, to Hisaka Works, Ltd. Plate used in condenser. 4,296,803, Cl. 165-110.000.

Summers, William A.: See—
Eckler, Paul E.; Summers, William A.; and Chandler, Ollie W., 4,297,443, Cl. 521-129.000.

Sun Aired Bag Co., Inc.: See—
Lefebvre, Henry R., 4,296,876, Cl. 223-91.000.

Sun, Yih-Yau: See—
Scherzer, Julius; Liu, Anh-Thu; and Sun, Yih-Yau, 4,297,325, Cl. 423-122.000.

Sundeen, Joseph E.; and Dejneka, Tamara, to E. R. Squibb & Sons, Inc. Inhibitors of mammalian collagenase. 4,297,275, Cl. 260-112.50R.

Suntech, Inc.: See—
Scheibel, Edward G., 4,297,206, Cl. 208-254.00R.
Thompson, Robert M., 4,297,454, Cl. 525-432.000.

Suntime, Inc.: See—
Cooper, George H., 4,296,729, Cl. 126-421.000.

Surgikos: See—
Mason, Stanley I., Jr.; and Handler, Michael D., 4,296,746, Cl. 128-201.150.

Suzuki, Kohji: See—
Oda, Yoshiro; Morimoto, Takeshi; and Suzuki, Kohji, 4,297,182, Cl. 204-98.000.

Suzuki, Minoru: See—
Tani, Tatsuo; Nagahara, Yasumori; Ohta, Sakae; Suzuki, Minoru; and Hashizume, Kiyozo, 4,297,021, Cl. 355-3.00R.

Suzuki, Sadao: See—
Yoshino, Yataro; Suzuki, Sadao; and Takada, Takuzo, 4,297,306, Cl. 264-23.000.

Suzuki, Shuichi: See—
Hikuma, Motohiko; Kubo, Tatsuru; Yasuda, Takeo; Karube, Isao; and Suzuki, Shuichi, 4,297,173, Cl. 204-1.00T.

Suzuki, Tomio: See—
Morimoto, Kotaro; and Suzuki, Tomio, 4,297,093, Cl. 431-10.000.

Tabutin, Andre: See—
Champeau, Marcel; and Tabutin, Andre, 4,296,658, Cl. 82-30.000.

Tachikawa, Shiro: See—
Yamamoto, Minoru; Tachikawa, Shiro; and Maeno, Hiroo, 4,297,356, Cl. 424-248.570.

Tachikawa Spring Company, Limited: See—
Sakurada, Kenichi; and Nishino, Takaichi, 4,296,965, Cl. 297-284.000.

Tadauchi, Masaharu; Sato, Kunio; and Tanno, Kiyohiko, to Hitachi, Ltd. Electrostatic recording apparatus. 4,297,715, Cl. 346-150.000.

Taddicken, Hermann; and Sachs, Wolfgang, to Eisele Apparate-und Geratebau GmbH. Device for producing sewing seam patterns of stitch groups. 4,296,696, Cl. 112-70.000.

Tak, Shiu M., to Wah Ming Electrics Limited. Brush assemblies for electric motors or generators. 4,297,605, Cl. 310-242.000.

Takada, Juichiro. Device for holding a passive vehicle restraint belt at a restraining position. 4,296,943, Cl. 280-804.000.

Takada, Takuzo: See—
Yoshino, Yataro; Suzuki, Sadao; and Takada, Takuzo, 4,297,306, Cl. 264-23.000.

Takagi, Yasushi: See—
Umezawa, Hamao; Umezawa, Sumio; Tsuchiya, Tsutomu; Takagi, Yasushi; and Jikihara, Tomo, 4,297,485, Cl. 536-10.000.

Takahashi, Kaneaki: See—
Uruta, Hisanari; Takahashi, Kaneaki; Masuda, Hirotugu; and Kurata, Tomoyuki, 4,296,705, Cl. 114-219.000.

Takahashi, Koichi; Hinata, Fumio; and Shibana, Akira, to Toyo Kogyo Co., Ltd. Multiple cylinder internal combustion engine having mixture cut off means. 4,296,719, Cl. 123-198.00F.

Takahata, Yasuyuki: See—
Ohdoi, Yozo; and Takahata, Yasuyuki, 4,296,621, Cl. 72-130.000.

Takamatsu, Hiroshi: See—
Sato, Makoto; Takamatsu, Hiroshi; Miyagawa, Yoshitaka; and Fujii, Etsuo, 4,296,972, Cl. 303-119.000.

Takamizawa, Yuji: See—
Komatsu, Makoto; Takamizawa, Yuji; and Ohta, Tazuo, 4,297,507, Cl. 562-416.000.

Takanemi, Tauno K. Automaton for dealing out food and drink. 4,296,980, Cl. 312-35.000.

Takara Belmont Co., Ltd.: See—
Masuda, Tatsunosuke; Ono, Yoshio; and Sakamoto, Seiya, 4,297,724, Cl. 358-93.000.

Takechi, Hiroshi: See—
Sakurai, Koichi; Furukawa, Takashi; Takechi, Hiroshi; and Matsuo, Munetsugu, 4,296,919, Cl. 266-111.000.

Takechi, Sanjuro: See—
Kasai, Goro; Takechi, Sanjuro; and Harima, Hiroshi, 4,297,315, Cl. 264-322.000.

Takeda Chemical Industries, Ltd.: See—
Goto, Jugo; and Saegusa, Takeo, 4,297,449, Cl. 525-329.000.

Takeda, Sakuzo: See—
Sugito, Kazuo; and Takeda, Sakuzo, 4,297,109, Cl. 44-56.000.

Takeguchi, Masanobu; and Oyobe, Isao, to Marui Industry Co., Ltd. Method of purifying water in fish keeping water tank. 4,297,222, Cl. 210-748.000.

Takehara, Nobumitsu; and Isayama, Shogo, to Fuji Photo Film Co., Ltd. Coating method. 4,297,396, Cl. 427-284.000.

Takizawa, Hiroshi; Enomoto, Yutaka; Oji, Yoshimasa; Hirayama, Tatsuyuki; and Hashimoto, Tamotu, to Kyowa Hakko Kogyo Co., Ltd. Certain muscle relaxant 3-methyl-2-benzofuran acetamides. 4,297,369, Cl. 424-285.000.

Talley, Randall E., III: See—
Lidik, Albert F.; and Talley, Randall E., III, 4,296,683, Cl. 100-53.000.

Talmoen, Arne: See—
Mejdell, Gior T.; Palmgren, Odd E.; Talmoen, Arne; and Vik, Bjarne, 4,297,483, Cl. 528-500.000.

Talon, Inc.: See—
Doerter, Randall H., 4,296,533, Cl. 24-216.000.

Tamasovics, John F.: See—
Balkwill, G. Russell; Robinet, Jules P.; and Tamasovics, John F., 4,296,870, Cl. 220-3.300.

Tamura, Kohki: See—
Kahara, Toshiki; Tamura, Kohki; Ebata, Noboru; Sato, Fumio; and Yoshida, Tomio, 4,297,231, Cl. 252-182.100.

Tamura, Koichi; and Harai, Tetsuo, to Tokico Ltd. Floating caliper type disc brake. 4,296,844, Cl. 188-73.380.

Tamura, Nobuhiro: See—
Nishikido, Joji; Tamura, Nobuhiro; Fukuoka, Yohei; and Yamane, Hiroyuki, 4,297,503, Cl. 560-42.000.

Tanahashi, Toshio: See—
Nakanishi, Kiyoshi; Okumura, Takeshi; Deguchi, Ryuichi; and Tanahashi, Toshio, 4,296,720, Cl. 123-309.000.

Tanaka, Hirokazu: See—
Yoshida, Keizo; Tanaka, Hirokazu; Okamoto, Masanori; Iguchi, Eiko; Kohsaka, Masanobu; Aoki, Hatsuo; and Imanaka, Hiroshi, 4,297,096, Cl. 435-128.000.

Tanaka, Kouichi; and Amazawa, Kiyoshi, to Nippon Electric Co., Ltd.; and Clarion Co., Ltd. Automatic gain control circuit comprising a circuit for comparing a modulated signal with an envelope detected signal. 4,297,645, Cl. 330-280.000.

Tanaka, Mamoru: See—
Ishida, Takashi; and Tanaka, Mamoru, 4,296,907, Cl. 248-573.000.

Tanaka, Ryosaku: See—
Sakai, Yoshihiro; Tanaka, Ryosaku; Kita, Toshio; Shimotake, Munetoshi; Yamada, Tsuguyoshi; and Ueda, Hiroshi, 4,296,790, Cl. 152-354.00R.

Tanaka, Takayasu: See—
Miyamoto, Kinzo; Tanaka, Takayasu; and Inoue, Yoshimi, 4,297,263, Cl. 260-32.6PQ.

Tang, Louis S., to Bendix Corporation. The Hydraulic brake booster and control valve therefor. 4,296,671, Cl. 91-5.000.

Tani, Masayuki; Okui, Mitsuhiko; and Matsumoto, Mitsuo, to Teljin Limited. Cotton yarn-like textured composite yarn and a process for manufacturing the same. 4,296,597, Cl. 57-205.000.

Tani, Tatsuo; Nagahara, Yasumori; Ohta, Sakae; Suzuki, Minoru; and Hashizume, Kiyozo, to Ricoh Company, Ltd. Powder material transportation apparatus. 4,297,021, Cl. 355-3.00R.

Tanimoto, Akira: See—
Iwai, Michinobu; and Tanimoto, Akira, 4,297,555, Cl. 200-153.00G.

Tanno, Kiyohiko: See—
Tadauchi, Masaharu; Sato, Kunio; and Tanno, Kiyohiko, 4,297,715, Cl. 346-150.000.

Taplin, John F.: See—
Rogers, Stanley J. C.; and Taplin, John F., 4,296,983, Cl. 312-263.000.

Tarnero, Maurice: See—
Sauvage, Henri; and Tarnero, Maurice, 4,297,324, Cl. 422-268.000.

Tashiro, Sadaji: See—
Onda, Kenichi; Tashiro, Sadaji; and Amano, Hisao, 4,297,594, Cl. 307-252.00C.

Tatani, Atsushi; and Okino, Susumu, to Mitsubishi Jukogyo Kabushiki Kaisha. Method for treatment of a discharge liquid produced in treatment of an exhaust gas. 4,297,332, Cl. 423-240.000.

Tawse, Ian S., to Gen-Tech, Inc. Axial air gap alternators/generators of modular construction. 4,297,604, Cl. 310-168.000.

Tax o mex AG: See—
Schlumpf, Alois, 4,296,873, Cl. 221-213.000.

Taylor, Donald F.; and Bostock, James H., to Otis Engineering Corporation. High temperature well packer. 4,296,806, Cl. 166-120.000.

Taylor, Edward S.; and Hirschle, George W., to General Atomic Company. Vapor generator. 4,296,713, Cl. 122-32.000.
 Taylor, Glenn R. Pushbutton operator. 4,297,556, Cl. 200-330.000.
 Taylor, Gordon J., to Union Carbide Corporation. Process for producing carbon-carbon fiber composites suitable for use as aircraft brake discs. 4,297,307, Cl. 264-29.500.
 Taylor, John R.: See—
 Laishley, William J.; and Taylor, John R., 4,297,734, Cl. 360-78.000.
 Taylor, Thomas. Respiratory monitor and excessive intrathoracic or abdominal pressure indicator. 4,296,757, Cl. 128-721.000.
 Techinter S.A.: See—
 Chevreux, Pierre; Nguyen, Van-Tao; Roman, Alain; and Turpin, Daniel, 4,297,185, Cl. 204-159.150.
 Technical Research of Citizen Watch Co., Ltd.: See—
 Nishimura, Katsuo; and Nanya, Takanori, 4,297,004, Cl. 350-336.000.
 Technicare Corporation: See—
 Mezrich, Reuben S.; Colleoni, Alec; and Lyons, David J., 4,297,009, Cl. 352-86.000.
 Teledyne Industries, Inc.: See—
 Campagna, Barry A., 4,296,617, Cl. 70-63.000.
 Telefonaktiebolaget L M Ericsson: See—
 Augst, Horst G., 4,297,659, Cl. 333-191.000.
 Teljin Limited: See—
 Tani, Masayuki; Okui, Mitsuhiro; and Matsumoto, Mitsuho, 4,296,597, Cl. 57-205.000.
 Tellier, Pierre: See—
 Delavarenne, Serge Y.; Dubreux, Bernard; and Tellier, Pierre, 4,297,288, Cl. 260-378.000.
 Temple, Paul A., to United States of America, Navy. Dark field surface inspection illumination technique. 4,297,032, Cl. 356-366.000.
 Tenuta, Antonio. Method of freezing tomatoes. 4,297,381, Cl. 426-615.000.
 Terada, Takami, to Aisin Seiki Kabushiki Kaisha; and Shatai Kogyo Kabushiki Kaisha. Seat for an automotive vehicle. 4,296,966, Cl. 297-369.000.
 Teramachi, Hiroshi. Linear ball bearing unit. 4,296,974, Cl. 308-6.000.
 Terry, Ronald E.: See—
 Morris, Charles W.; and Terry, Ronald E., 4,296,811, Cl. 166-273.000.
 Terui, Yohji: See—
 Koga, Isao; Terui, Yohji; Ohgushi, Masuhito; and Kitahara, Tohru, 4,297,499, Cl. 556-465.000.
 Terumo Corporation: See—
 Kobayashi, Susumu, 4,296,882, Cl. 233-21.000.
 Tesoro, Joseph. Slip joint pliers. 4,296,655, Cl. 81-405.000.
 Tessier, Martin M., to National Starch and Chemical Corporation. Novel N-(alkyl)-N-(2-haloethyl)-aminomethylphosphonic acids, a method for the preparation thereof and their use in the preparation of starch ether derivatives. 4,297,299, Cl. 260-502.500.
 Tetzlaff, Karl-Heinz; Riemenschneider, Wilhelm; and Leuschner, Gunter, to Hoechst Aktiengesellschaft. Pressure vessel having quick-action locking means. 4,297,323, Cl. 422-208.000.
 Texaco Development Corp.: See—
 Gilbert, Richard J.; and Rice, Doris M., 4,297,444, Cl. 521-160.000.
 Hunter, Walter D., 4,297,226, Cl. 252-8.55D.
 Hunter, Walter D., 4,297,469, Cl. 526-287.000.
 Texaco Inc.: See—
 Bartley, Burton H.; and Estes, John H., 4,297,245, Cl. 252-460.000.
 Kalfoglou, George, 4,296,812, Cl. 166-274.000.
 Witte, Arnold C.; and Coleman, Richard L., 4,297,227, Cl. 252-18.000.
 Texas Instruments Incorporated: See—
 Mundt, Randall S.; Wooldridge, Timothy A.; and Blasingame, Thomas O., 4,297,162, Cl. 156-643.000.
 Parsons, Robert, 4,297,693, Cl. 340-744.000.
 TGS Systems, Inc.: See—
 Rhonehouse, Donald E., 4,297,121, Cl. 65-348.000.
 Thatcher, Imbrie: See—
 Shaw, Manuel; and Thatcher, Imbrie, 4,297,689, Cl. 340-632.000.
 Theodore, Louis. Gas filtration apparatus. 4,297,113, Cl. 55-213.000.
 Therm-O-Disc, Incorporated: See—
 Place, Donald E., 4,297,668, Cl. 337-365.000.
 Thigpen, Ben B.; and Porter, James A., Jr., to Western Geophysical Company of America. Air-gun fire time sensor. 4,296,827, Cl. 181-107.000.
 Thomas, Jeffrey R., to PQ Corporation. Drying of potassium silicate. 4,297,163, Cl. 159-48.000.
 Thompson, Bernard B., to Boeing Company. The Brake torque limiter. 4,296,897, Cl. 244-111.000.
 Thompson, Elmer R. Sewing machine conversion apparatus. 4,296,703, Cl. 112-310.000.
 Thompson, Jerome B. English muffin, method and apparatus. 4,296,682, Cl. 99-426.000.
 Thompson, Robert M., to Suntech, Inc. Manufacture of a block copolymer containing a polyetheramide and a polylactam. 4,297,454, Cl. 525-432.000.
 Thomson-CSF: See—
 Dupressoir, Albert, 4,297,710, Cl. 343-756.000.
 Lacomme, Philippe, 4,297,703, Cl. 343-7.300.
 Matherat, Philippe, 4,297,694, Cl. 340-750.000.
 Thornton, Kenneth, to Rolls-Royce Motors Limited. Automatic transmission. 4,296,646, Cl. 74-688.000.
 Thorpe, Cameron L.: See—
 Hales, Marwood J.; and Thorpe, Cameron L., 4,296,602, Cl. 60-398.000.

Thyssen Aktiengesellschaft vormals August Thyssen-Hütte: See—
 Hoffken, Erich; Kleine-Kleffmann, Werner; Bertram, Rolf; Abele, Karl-Heinz; and Michalski, Gunter, 4,297,151, Cl. 148-9.000.
 Thyssen Industrie AG: See—
 Kronert, Curt, 4,296,853, Cl. 192-106.100.
 Tikhonov, Valentin N.: See—
 Shlykov, Gennady N.; Zhestkov, Vitaly I.; Tikhonov, Valentin N.; Dyachkov, Vasily M.; Glazov, Vladimir G.; and Krjuk, Timur P., 4,296,528, Cl. 19-255.000.
 Tilgner, Leopold: See—
 Loser, Norbert; and Tilgner, Leopold, 4,296,978, Cl. 308-37.000.
 Timex Corporation: See—
 Bissar, Saadi, 4,297,006, Cl. 350-357.000.
 Ho, Kok-Kit, 4,296,532, Cl. 24-206.000.
 TME, Inc.: See—
 Jesse, Harold W.; and Jones, Peter M., 4,297,522, Cl. 174-36.000.
 Toda, Tosifusa: See—
 Ohashi, Mochihiko; and Toda, Tosifusa, 4,297,198, Cl. 204-299.000.
 Tokico Ltd.: See—
 Tamura, Koichi; and Haraikawa, Tetsuo, 4,296,844, Cl. 188-73.380.
 Tokunaga, Shinobu; and Shiina, Yuichi, to Sumita Optical Glass Manufacturing Co., Ltd. Optical glass for optical paths. 4,297,141, Cl. 501-67.000.
 Tokyo Ohka Kogyo Kabushiki Kaisha: See—
 Tsuda, Minoru; and Nakamura, Yoichi, 4,297,433, Cl. 430-270.000.
 Tokyo Shibaura Denki Kabushiki Kaisha: See—
 Fukuda, Takeo; Hanawa, Kazuhiko; Uru, Kiyoshi; and Haseyama, Michiko, 4,297,532, Cl. 179-18.0A.B.
 Iwai, Michinobu; and Tanimoto, Akira, 4,297,555, Cl. 200-153.00G.
 Kawaguchi, Yoshihiro; Higuchi, Kosuke; and Kitajima, Yoshio, 4,297,553, Cl. 200-145.000.
 Kimura, Takashi, 4,297,597, Cl. 307-315.000.
 Okatsuka, Hisahi, 4,297,568, Cl. 235-435.000.
 Tokyo Shibaura Electric Co., Ltd.: See—
 Anezaki, Yoshimitsu, 4,297,612, Cl. 313-446.000.
 Tolliver, Wilbur E. Pipe joint seal. 4,296,933, Cl. 277-34.300.
 Tom, M. Dale. Water detection device. 4,297,686, Cl. 340-604.000.
 Tomimura, Eihiro: See—
 Mise, Yoshinari; and Tomimura, Eihiro, 4,297,146, Cl. 127-60.000.
 Tommaney, Joseph W.: See—
 Patil, Balaji V.; and Tommaney, Joseph W., 4,297,132, Cl. 75-10.00V.
 Topalian, Harry H.; Wyss, Clement R.; Kenyon, Ralph E.; and Dec, Anthony F., to General Foods Corporation. Frozen aerated ready-to-eat gelatin composition. 4,297,379, Cl. 426-565.000.
 Toray Industries, Inc.: See—
 Deguchi, Yukichi; Yamagishi, Hideki; and Kirimura, Shunichiro, 4,297,187, Cl. 204-165.000.
 Nakata, Minoru; Sato, Haruyo; and Imamura, Shinzo, 4,297,477, Cl. 528-323.000.
 Torgersen, Jan H.: See—
 Gjelsvik, Norvald; Hannestad, Gunnar; Hundere, Ingleif; and Torgersen, Jan H., 4,297,327, Cl. 423-126.000.
 Torii, Takahiro: See—
 Satoh, Tsutomu; Ohye, Hideo; Tsukahara, Hirokazu; Senoh, Hideaki; and Torii, Takahiro, 4,296,948, Cl. 282-27.500.
 Total Oil Great Britain Limited: See—
 Shackcloth, Barry, 4,297,543, Cl. 200-18.000.
 Tourdot, Jacques: See—
 Crommelynck, Francois; Granger, Michel; Rio, Michel; and Tourdot, Jacques, 4,297,298, Cl. 260-502.000.
 Tournier, Claude. Skinning machine for the heads and limbs of slaughtered animals. 4,296,526, Cl. 17-21.000.
 Tournier, Edmond: See—
 Laval, Michel; and Tournier, Edmond, 4,297,576, Cl. 250-336.000.
 Townsend, Raymond L.; Kester, Jack R.; and Young, Kenneth A., to Tweco Products, Inc. Semi-automatic welding gun. 4,297,561, Cl. 219-137.630.
 Toyo Jozo Kabushiki Kaisha: See—
 Fujii, Tadashi; Sato, Shuzo; Muto, Naoki; Hayashi, Mitsuho; Kodama, Akira; and Otani, Masaru, 4,297,486, Cl. 536-17.000.
 Toyo Kogyo Co., Ltd.: See—
 Takahashi, Koichi; Hinata, Fumio; and Shibana, Akira, 4,296,719, Cl. 123-198.00F.
 Toyo Pulp Co. Ltd.: See—
 Kinbara, Koichi; Sugimoto, Norimaro; and Nakazawa, Toshitaka, 4,297,402, Cl. 428-35.000.
 Toyoda Koki Kabushiki Kaisha: See—
 Tsuboi, Akira; and Kato, Shiro, 4,296,541, Cl. 29-568.000.
 Toyota Jidosha Kogyo Kabushiki Kaisha: See—
 Fujimori, Fumio; Yokoi, Masatada; Ishikawa, Masakazu; Uemura, Hiroshi; and Shirai, Akira, 4,296,841, Cl. 188-73.380.
 Kizaki, Jiro; and Fujii, Takashi, 4,296,604, Cl. 60-562.000.
 Nakanishi, Kiyoshi; Okumura, Takeshi; Deguchi, Ryuichi; and Tanahashi, Toshio, 4,296,720, Cl. 123-309.000.
 Okano, Hiroshi; and Sato, Akira, 4,296,648, Cl. 74-798.000.
 Shinohara, Hiroshi; Otsuka, Yasuhiro; Matsumoto, Shinichi; Wakasaka, Hiroshi; and Furutani, Toshinobu, 4,297,192, Cl. 204-195.00S.
 Travis, Karen L.: See—
 Mansfield, Gerald R.; Travis, Karen L.; and Vann, William P., 4,297,337, Cl. 424-1.000.
 Treczka, Leo, to Spinner GmbH Elektrotechnische Fabrik. 3dB Waveguide directional coupler. 4,297,658, Cl. 333-113.000.

Tregurtha, Steven J.; and Cryer, Edward, to Lucas Industries Limited. Direction indicator switch. 4,297,549, Cl. 200-61.270.
 Treppa, William J., to Phillips Petroleum Co. Orthoesters as coupling agents for producing monovinylarene homopolymers. 4,297,464, Cl. 526-181.000.
 Trico Products Corporation: See—
 Mower, Peter, 4,296,521, Cl. 15-250.320.
 Trinh, Stephane: See—
 Guigues, Francois; and Trinh, Stephane, 4,297,367, Cl. 424-283.000.
 Trio Kabushiki Kaisha: See—
 Wada, Takeshi; Kominami, Yasuo; Miyamoto, Yukihiko; and Yamada, Tsuneo, 4,297,601, Cl. 307-555.000.
 Triumph-Werke Nurnberg A.G.: See—
 Puch, Diethelm; and Will, Norbert F., 4,297,040, Cl. 400-144.200.
 Trocciola, John C.: See—
 Nickols, Richard C., Jr.; Trocciola, John C.; and Rourke, James E., 4,297,419, Cl. 429-44.000.
 Trochoid Power Corporation: See—
 Hoffmann, Ralph M., 4,297,090, Cl. 418-61.00A.
 Trotsch, Gunter: See—
 Hornberg, Harald; Trotsch, Gunter; and Hahnefeld, Fedor, 4,297,044, Cl. 400-473.000.
 True Temper Corporation: See—
 Luebke, Robert W., 4,296,884, Cl. 238-2.000.
 Trutna, William R., Jr., to Leland Stanford University, Board of Trustees of. Multipath Raman cell for wavelength conversion. 4,297,600, Cl. 307-426.000.
 TRW Inc.: See—
 Zehren, James N., 4,296,548, Cl. 29-871.000.
 Tsai, Shirley C.; Graham, Richard H.; and Oder, Robin R., to Gulf Research & Development Company. In situ gasification of bituminous coal. 4,296,809, Cl. 166-259.000.
 Tschunt, Edgar: See—
 Schwierz, Gunter; Schittenhelm, Rudolf; Schmitt, Gunter; and Tschunt, Edgar, 4,297,582, Cl. 250-445.00T.
 Tsubai, Yasuo: See—
 Kanada, Eiji; Yamada, Shoji; and Tsubai, Yasuo, 4,297,429, Cl. 430-204.000.
 Kanada, Eiji; Yamada, Shoji; and Tsubai, Yasuo, 4,297,430, Cl. 430-204.000.
 Tsuboi, Akira; and Kato, Shiro, to Toyoda Koki Kabushiki Kaisha. Tool storage magazine for a machine tool. 4,296,541, Cl. 29-568.000.
 Tsuchiya, Tsutomu: See—
 Umezawa, Hamao; Umezawa, Sumio; Tsuchiya, Tsutomu; Takagi, Yasushi; and Jikihara, Tomo, 4,297,485, Cl. 536-10.000.
 Tsuchiya, Yoshihiro; Sagae, Masayuki; and Mizutani, Hiroshi, to Kao Soap Co., Ltd. Absorbent material. 4,297,410, Cl. 428-283.000.
 Tsuda, Minoru; and Nakamura, Yoichi, to Tokyo Ohka Kogyo Kabushiki Kaisha. Light sensitive compositions of polymethyl isopropenyl ketone. 4,297,433, Cl. 430-270.000.
 Tsukahara, Hirokazu: See—
 Satoh, Tsutomu; Ohye, Hideo; Tsukahara, Hirokazu; Senoh, Hideaki; and Torii, Takahiro, 4,296,948, Cl. 282-27.500.
 Tsutsui, Kotaro; and Kinugawa, Ryoji, to Alps Electric Co., Ltd. Interlocking gang push-button switch. 4,297,540, Cl. 200-5.00B.
 Tsykina, Zinaida D.: See—
 Berkhin, Isif M.; Gudze, Robert A.; Kekalo, Vasily I.; Panasenko, Nikolai N.; Podbeltsev, Viktor I.; Tsykina, Zinaida D.; and Mukhin, Vladislav N., 4,296,867, Cl. 212-229.000.
 Tucker, Trevor W.; and Cornish, William D., to Canada, Her Majesty the Queen in right of, as represented by the Minister of National Defence. Microwave frequency division by phase locked loops. 4,297,648, Cl. 331-1.00R.
 Tunashima, Seiichi: See—
 Ito, Isao; and Tunashima, Seiichi, 4,297,034, Cl. 356-394.000.
 Tuominen, Pertti: See—
 Uusitalo, Leo; and Tuominen, Pertti, 4,297,067, Cl. 414-114.000.
 Turillon, Pierre P.; Hull, Michael N.; and Nordblom, George F., to International Nickel Co., Inc. The Battery and electrolytic cell electrodes. 4,297,421, Cl. 429-225.000.
 Turpin, Daniel: See—
 Chevreux, Pierre; Nguyen, Van-Tao; Roman, Alain; and Turpin, Daniel, 4,297,185, Cl. 204-159.150.
 Tweco Products, Inc.: See—
 Townsend, Raymond L.; Kester, Jack R.; and Young, Kenneth A., 4,297,561, Cl. 219-137.630.
 Tyler, Hugh J.; and Conway, William H., to Robertshaw Controls Company. Microwave oven temperature indicator and control means. 4,297,557, Cl. 219-10.55R.
 Tylo Sauna S.A.: See—
 Janson, Mats O., 4,296,507, Cl. 4-524.000.
 Tyo, James H., to Camp International, Inc. Convertible parapodium. 4,296,761, Cl. 128-80.00G.
 Ube Industries, Ltd.: See—
 Ueno, Haruo; Yano, Takefumi; Inoue, Tokuji; Ikai, Shigeru; Kai, Yoshiyuki; and Shimizu, Michimasa, 4,297,463, Cl. 526-128.000.
 Uchidoi, Masanori: See—
 Kawamura, Masaharu; Uchidoi, Masanori; Shigeta, Yoshihiro; Sugiura, Yoji; and Yamamoto, Hiroshi, 4,297,013, Cl. 354-23.00D.
 Uchiyama, Yoshihiro: See—
 Ishibashi, Yoji; Uchiyama, Yoshihiro; Akimoto, Hidetoshi; and Sakaki, Makoto, 4,297,319, Cl. 422-114.000.
 Ucinhazska, Bruno: See—
 Norden, Jurgen; and Ucinhazska, Bruno, 4,296,885, Cl. 239-1.000.

Ueda, Hiroshi: See—
 Sakai, Yoshihiro; Tanaka, Ryosaku; Kita, Toshio; Shimotake, Munetoshi; Yamada, Tsuguyoshi; and Ueda, Hiroshi, 4,296,790, Cl. 152-354.00R.
 Ueda, Nobuo: See—
 Kato, Makoto; Ueda, Nobuo; and Matsushima, Hiroaki, 4,297,166, Cl. 376-194.000.
 Uemura, Hiroshi: See—
 Fujimori, Fumio; Yokoi, Masatada; Ishikawa, Masakazu; Uemura, Hiroshi; and Shirai, Akira, 4,296,841, Cl. 188-73.380.
 Ueno, Haruo; Yano, Takefumi; Inoue, Tokuji; Ikai, Shigeru; Kai, Yoshiyuki; and Shimizu, Michimasa, to Ube Industries, Ltd. Method for polymerizing α -olefin. 4,297,463, Cl. 526-128.000.
 Uerlich, Johannes: See—
 Muller, Rudolf; Lengsfeld, Franz; and Uerlich, Johannes, 4,296,776, Cl. 137-340.000.
 Uhrig, Heinz; and Deubel, Reinhold, to Hoechst Aktiengesellschaft. Manufacture and use of non-ionogenic interface-active agents based on modified rosins. 4,297,270, Cl. 260-104.000.
 Umaba, Toshikatsu: See—
 Abe, Kazunobu; Nakatsuji, Tadao; and Umaba, Toshikatsu, 4,297,248, Cl. 252-477.00R.
 Umezawa, Hamao; Umezawa, Sumio; Tsuchiya, Tsutomu; Takagi, Yasushi; and Jikihara, Tomo, to Zaidan Hojin Biseibutsu Kagaku Kenkyu Kai. Production of a selectively protected N-acylated derivative of an aminoglycosidic antibiotic. 4,297,485, Cl. 536-10.000.
 Umezawa, Sumio: See—
 Umezawa, Hamao; Umezawa, Sumio; Tsuchiya, Tsutomu; Takagi, Yasushi; and Jikihara, Tomo, 4,297,485, Cl. 536-10.000.
 Union Carbide Corporation: See—
 Bryant, David R.; and Galley, Richard A., 4,297,239, Cl. 252-412.000.
 Chiasson, Bertrand A., 4,297,509, Cl. 562-456.000.
 Davis, Robert B., 4,296,610, Cl. 62-55.000.
 Hsu, Fu-Tong; and Kantz, John F., 4,296,860, Cl. 206-386.000.
 Kavasmanek, Percy R.; Stanton, David B.; and Sherman, Paul D., Jr., 4,297,241, Cl. 252-435.000.
 Kilinskas, William A.; Selines, Ronald J.; and Vand den Sype, Jaak S., 4,296,512, Cl. 10-27.00E.
 Koleske, Joseph V., 4,297,476, Cl. 528-300.000.
 Lok, Brent M. T.; and Izod, Thomas J. P., 4,297,335, Cl. 423-328.000.
 Nunciato, David J.; White, Norman H.; and Woodburn, William A., 4,297,147, Cl. 134-7.000.
 Ritscher, James S.; and Sandner, Michael R., 4,297,328, Cl. 423-213.200.
 Sigmund, Paul W.; and Butwell, Kenneth F., 4,297,329, Cl. 423-228.000.
 Taylor, Gordon J., 4,297,307, Cl. 264-29.500.
 Union Oil Company of California: See—
 Moorehead, Eric L., 4,297,243, Cl. 252-455.00Z.
 United Chemi-Con, Inc.: See—
 Dyer, Christopher K., 4,297,184, Cl. 204-129.400.
 United Kingdom Atomic Energy Authority: See—
 Cairns, James A.; Nelson, Robert L.; and Woodhead, James L., 4,297,246, Cl. 252-465.000.
 United States Borax & Chemical Corporation: See—
 Speak, Richard C.; and Ferm, Donald J., 4,297,229, Cl. 252-109.000.
 United States of America
 Agriculture: See—
 Haissig, Bruce E.; Gaines, Jack R.; and Giacometto, Glen, 4,297,125, Cl. 71-77.000.
 Air Force: See—
 Frankel, Milton B.; Arbit, Harry A.; Artz, Glen D.; and Gray, John C., 4,297,152, Cl. 149-88.000.
 Paciorek, Kazimiera J. L.; Kratzer, Reinhold H.; Ito, Thomas I.; and Nakahara, James H., 4,297,510, Cl. 564-13.000.
 Army: See—
 Boothe, Robert R., 4,297,705, Cl. 343-771.000.
 Concha, Edward; Jaffe, Max; and Bedford, Riley, 4,297,068, Cl. 414-458.000.
 Debona, Edward J.; Neblett, Boyd L.; Krueger, Walter J.; Laird, William J.; Campbell, Billy H.; and Matthews, Gerald H., 4,296,669, Cl. 89-1.816.
 Garrett, Harold E., 4,296,687, Cl. 102-518.000.
 Monte, Anthony J., 4,296,817, Cl. 169-62.000.
 Navy: See—
 Claffy, Richard D.; and Lovelace, Reginald B., 4,296,771, Cl. 137-110.000.
 Dittman, Charles C.; and St. Clair, Richard C., 4,297,622, Cl. 318-254.000.
 Hardesty, Thomas K. C., 4,296,689, Cl. 102-260.000.
 Temple, Paul A., 4,297,032, Cl. 356-366.000.
 Wooden, Bruce J.; and Edelman, Seymour, 4,297,394, Cl. 427-100.000.
 U.S. Philips Corporation: See—
 Buchner, Robert B., 4,297,536, Cl. 179-170.00D.
 Cassel, Knut E.; and Molin, Bengt T., 4,297,709, Cl. 343-754.000.
 Goerth, Joachim, 4,297,654, Cl. 331-108.00D.
 Goudin, Robert, 4,296,753, Cl. 128-660.000.
 Herzner, Karl H., 4,297,567, Cl. 235-92.0PB.
 Matthijsse, Matthijs, 4,296,906, Cl. 248-280.100.
 Melwisch, Harald; and Looren de Jong, Hendrikus, 4,297,731, Cl. 360-70.000.
 Sanderson, Hendrik J., 4,297,733, Cl. 360-77.000.

- Severijns, Adrianus P.; and Staas, Frans A., 4,296,609, Cl. 62-514.00R.
- United States Steel Corporation: *See—*
Bray, Lynn W., 4,296,556, Cl. 34-107.000.
- United Technologies Corporation: *See—*
Krauss, Timothy A.; and Roman, Stephan, 4,297,080, Cl. 416-141.000.
- Nickols, Richard C., Jr.; Trocciola, John C.; and Rourke, James E., 4,297,419, Cl. 429-44.000.
- University of California, The Regents of the: *See—*
Crooks, Lawrence E.; Hoenninger, John C., III; and Arakawa, Mitsuki, 4,297,637, Cl. 324-309.000.
- Goebel, Dan M.; Crow, James T.; and Forrester, A. Theodore, 4,297,615, Cl. 315-111.210.
- University of Illinois Foundation: *See—*
Waller, Donald P.; Zaneveld, Lourens J. D.; and Fong, Harry H. S., 4,297,341, Cl. 424-80.000.
- University of Melbourne, The: *See—*
McCutchan, John C.; and Niven, Rex C., 4,297,633, Cl. 324-51.000.
- University of Surrey: *See—*
Hannaht, David J., 4,297,409, Cl. 428-247.000.
- Upjohn Company, The: *See—*
Babcock, John C.; Campbell, J. Allan; and Lobl, Thomas J., 4,297,350, Cl. 424-238.000.
- Craven, Richard L., 4,297,339, Cl. 424-19.000.
- Nelson, Stephen J., 4,297,285, Cl. 260-346.730.
- Sih, John C., 4,297,504, Cl. 560-119.000.
- Ura, Hiroaki: *See—*
Honda, Hiroyuki; and Ura, Hiroaki, 4,297,026, Cl. 355-15.000.
- Uranek, Carl A.; Burleigh, John E.; and Solomon, Paul W., to Phillips Petroleum Company, Diethylmethyl initiated polymers, 4,297,451, Cl. 525-366.000.
- Url, Karlheinz; and von Basse, Paul W., to Siemens Aktiengesellschaft, Integratable dynamic current source for semiconductor modules, 4,297,592, Cl. 307-583.000.
- Urui, Kiyoshi: *See—*
Fukuda, Takeo; Hanawa, Kazuhiko; Urui, Kiyoshi; and Haseyama, Michiko, 4,297,532, Cl. 179-18.0AB.
- Uruta, Hisanari; Takahashi, Kaneaki; Masuda, Hirotsugu; and Kurata, Tomoyuki, to Bridgestone Tire Co., Ltd. Pneumatic marine fender, 4,296,705, Cl. 114-219.000.
- Usardi, Maria M.: *See—*
Gandolfi, Carmelo; Passarotti, Carlo; Andreoni, Alessandro; Fumagalli, Angelo; Faustini, Franco; Ceserani, Roberto; and Usardi, Maria M., 4,297,368, Cl. 424-285.000.
- USM Corporation: *See—*
Halford, David W.; Price, Frank C.; and Bosworth, George H., 4,296,513, Cl. 12-12.000.
- Netzsch, Hermann, 4,297,560, Cl. 219-130.010.
- Valks, Robert K., 4,296,614, Cl. 69-48.000.
- Utagawa, Ken; Hoshino, Kunihisa; Shirasu, Hiroshi; and Ogasawara, Akira, to Nippon Kogaku K.K. Focus detecting device, 4,297,571, Cl. 250-201.000.
- Uusitalo, Leo; and Tuominen, Pertti, to Outokumpu Oy, Method and apparatus for handling packed layers of support rods in an electrolytic refining plant, 4,297,067, Cl. 414-114.000.
- Vadotec Corporation: *See—*
Kemper, Yves J., 4,296,647, Cl. 74-690.000.
- Vail, Ande. Power supply system, 4,297,590, Cl. 307-43.000.
- Valks, Robert K., to USM Corporation, Leather press, 4,296,614, Cl. 69-48.000.
- Valli & Colombo S.p.A.: *See—*
Colombo, Angelo, 4,296,956, Cl. 292-169.180.
- Van Broekhoven, Johannes A. M.; and Drent, Eit, to Shell Oil Company, Preparation of carbonyl compounds from allylethers, 4,297,517, Cl. 568-361.000.
- Vand den Syde, Jaak S.: *See—*
Kilinskas, William A.; Selnes, Ronald J.; and Vand den Syde, Jaak S., 4,296,512, Cl. 10-27.00E.
- van der Lely, Cornelis, Vehicle having bogie mounted wheels, 4,296,826, Cl. 180-24.000.
- van der Lugt, Arie, to Gist-Brocades N.V. Closure treatment machine, 4,296,769, Cl. 134-68.000.
- Vanlerberghe, Guy; and Sebag, Henry, to L'Oreal, Cyclical tensio-active polyethers, 4,297,102, Cl. 8-406.000.
- Vann, William P.: *See—*
Mansfield, Gerald R.; Travis, Karen L.; and Vann, William P., 4,297,337, Cl. 424-1.000.
- Van Uitert, LeGrand G.: *See—*
Johnson, David W., Jr.; Singh, Shobha; Van Uitert, LeGrand G.; and Zydik, George J., 4,297,005, Cl. 350-357.000.
- Van Vliet, Raymond A., to Weyerhaeuser Company, Method for application of elastic to articles, 4,297,157, Cl. 156-164.000.
- Van Wassenhove, Bernard, to CMI Corporation, Folding gooseneck assembly, 4,296,941, Cl. 280-423.00B.
- van Zorge, Jacob A., to ACF Chemiefarma NV, Anti-ulcer compositions containing certain pyridyl oxime ethers, 4,297,359, Cl. 424-263.000.
- Varel Manufacturing Company: *See—*
Gholson, Wayne, 4,296,823, Cl. 175-308.000.
- Vartoukian, Artin G., to Singer Company, The, Fabric clamp, 4,296,699, Cl. 112-121.150.
- Vcelka, John L.: *See—*
Muettterties, Andrew J.; Vcelka, John L.; and Kelsey, Wayne R., 4,296,949, Cl. 285-18.000.
- VDO Adolf Schindling AG: *See—*
Jung, Wilhelm; and Rau, Karl, 4,296,630, Cl. 73-304.00C.
- Verable, Diara; and Gibson, Willie M. Automobile shed, 4,296,575, Cl. 52-66.000.
- Verbicky, John W., to General Electric Company, Chlorination of phthalic anhydride, 4,297,283, Cl. 260-346.300.
- Verdier, Jean-Pierre: *See—*
Hoffmann, Jean-Claude; Castanie, Francis; Crabere, Henri; Verdier, Jean-Pierre; and Voisin, Norbert, 4,297,744, Cl. 364-703.000.
- Vetter, Artur, to Multivac Sepp Haggenmuller KG, Sealing station of vacuum packaging machines, 4,296,588, Cl. 53-86.000.
- Vickers Limited: *See—*
Rogers, Stanley J. C.; and Taplin, John F., 4,296,983, Cl. 312-263.000.
- Vidal, Paul, to Societe d'Etude du Radant, Apparatus and methods for correcting dispersion in a microwave antenna system, 4,297,708, Cl. 343-754.000.
- Viehig, Wolfgang: *See—*
Stemme, Otto; Fergg, Berthold; Osegowitsch, Viktor; and Viehig, Wolfgang, 4,297,027, Cl. 355-27.000.
- Vik, Bjarne: *See—*
Mejdell, Glor T.; Palmgren, Odd E.; Talmoen, Arne; and Vik, Bjarne, 4,297,483, Cl. 528-500.000.
- Vilicich, John: *See—*
Ross, Jim; and Vilicich, John, 4,296,726, Cl. 126-25.00B.
- Vinson, Joseph J. Reversible garment, 4,296,498, Cl. 2-115.000.
- Virginia Panel Corporation: *See—*
Stowers, Jeffery P.; and Stowers, Kimball E., 4,296,990, Cl. 339-128.000.
- Viello, John P.; and Grummon, Glenn D., to Mallinckrodt, Inc. System for generating and containerizing radioisotopes, 4,296,785, Cl. 141-105.000.
- Vockenhuber, Karl: *See—*
Freudenschuss, Otto, 4,297,732, Cl. 360-72.100.
- Vogel, Ignaz, Passenger seat, 4,296,967, Cl. 297-451.000.
- Vogt, Alfred, to Hoval Interliz AG, Two-chamber boiler for burner firing and solid fuel firing, 4,296,712, Cl. 122-22.000.
- Vogt, Frederick G., deceased (by Vogt, Mary J., executrix); and Sparrell, Patricia T., to Betz Laboratories, Inc. Low level chromate-based corrosion inhibition in aqueous mediums, 4,297,317, Cl. 422-16.00F.
- Vogt, Mary J., executrix: *See—*
Vogt, Frederick G., deceased; and Sparrell, Patricia T., 4,297,317, Cl. 422-16.000.
- Voirol, Felix: *See—*
Guex, Woldemar; Klauwi, Heinrich; Pauling, Horst; and Voirol, Felix, 4,296,801, Cl. 165-104.170.
- Voisin, Norbert: *See—*
Hoffmann, Jean-Claude; Castanie, Francis; Crabere, Henri; Verdier, Jean-Pierre; and Voisin, Norbert, 4,297,744, Cl. 364-703.000.
- Volkswagenwerk AG: *See—*
Bernhardt, Winfried; Grundmann, Edgar; and Kroll, Rudolf, 4,296,732, Cl. 126-426.000.
- Volkswagenwerk Aktiengesellschaft: *See—*
Hofbauer, Peter; Willmann, Michael; and Wundrak, Egon, 4,296,716, Cl. 123-195.00C.
- Oberpichler, Gerd; and Honig, Ernst-August, 4,296,652, Cl. 74-868.000.
- von Basse, Paul W.: *See—*
Url, Karlheinz; and von Basse, Paul W., 4,297,592, Cl. 307-583.000.
- von der Eltz, Hans-Ulrich; Lehman, Armand; Lehmann, Joachim W.; and Maier, Hans-Peter, to Hoechst Aktiengesellschaft, Process for the dyeing of synthetic polyamide fibers with reactive dyes according to the batchwise exhaustion method, 4,297,101, Cl. 8-531.000.
- von Petery, Curt, to Gutehoffnungshutte Sterkrade A.G. Positive control system for piston compressor valves, 4,297,083, Cl. 417-53.000.
- Vormbrock, Rolf; and Helger, Roland, to Merck Patent Gesellschaft mit beschränkter Haftung, Hemolysing solution preparing hemolysed blood having a stabilized glucose content, 4,297,238, Cl. 252-408.000.
- Vought Corporation: *See—*
Krall, Kenneth M., 4,296,900, Cl. 244-219.000.
- Vuyovich, John M. Piston top-dead-center detector, 4,296,629, Cl. 73-116.000.
- W. Hegenscheidt Gesellschaft mbH: *See—*
Bagusche, Siegfried, 4,296,620, Cl. 72-100.000.
- W. R. Grace & Co.: *See—*
Jachimowicz, Felek, 4,297,481, Cl. 528-392.000.
- Wood, Louis L.; and Larsen, Donald W., 4,297,482, Cl. 528-405.000.
- Wada, Takeshi; Kominami, Yasuo; Miyamoto, Yukihiko; and Yamada, Tsuneo, to Hitachi, Ltd.; and Trio Kabushiki Kaisha, Monostable multivibrator circuit and FM detector circuit employing predetermined load resistance and constant current to increase response rate of differential transistor pair, 4,297,601, Cl. 307-555.000.
- Wade, David R.; and Munch, Walter, to Baldwin Piano & Organ Company, Capture combination action system for electronic organs, 4,296,667, Cl. 84-345.000.
- Waghorn, Peter E.: *See—*
Stead, John C.; and Waghorn, Peter E., 4,297,408, Cl. 428-240.000.
- Wagner Electric Corporation: *See—*
Cortorillo, Salvatore F., 4,297,611, Cl. 313-222.000.
- Wagner, Kuno: *See—*
Reischl, Artur; and Wagner, Kuno, 4,297,456, Cl. 525-452.000.

- Wagstaff, Robert A.: *See—*
Martenas, Wayne B.; Pripke, Edward H.; and Wagstaff, Robert A., 4,296,591, Cl. 56-10.300.
- Wah Ming Electric Limited: *See—*
Tak, Shiu M., 4,297,605, Cl. 310-242.000.
- Waitkus, Phillip A.; and D'Alelio, Gaetano F., deceased (by St. Joseph Bank and Trust Company, executor), to Plastics Engineering Company, Polymerization products of polyimide derivatives having unsaturated terminal amide groups, 4,297,467, Cl. 526-259.000.
- Wakisaka, Hiroshi: *See—*
Shinohara, Hiroshi; Otsuka, Yasuhiro; Matsumoto, Shinichi; Wakisaka, Hiroshi; and Furutani, Toshinobu, 4,297,192, Cl. 204-195.00S.
- Wakushima, Yoshikazu: *See—*
Nagao, Shozo; Ohashi, Yoshinobu; Watanabe, Yuichi; and Wakushima, Yoshikazu, 4,296,953, Cl. 285-302.000.
- Waldrop, T. William; and Campbell, Willis R., to Sperry Corporation, Automatic bale ejection drive, 4,296,596, Cl. 56-341.000.
- Wall, Berth-Ove G.: *See—*
Hakansson, Hakan B.; Persson, Lennart P. E.; and Wall, Berth-Ove G., 4,296,633, Cl. 73-362.0AR.
- Wallace, Christopher B., to Bio-Group, Inc. Process for the biological degradation of organic-containing waste matter, 4,297,122, Cl. 71-12.000.
- Waller, Donald P.; Zaneveld, Lourens J. D.; and Fong, Harry H. S., to University of Illinois Foundation, Spermicidal composition, 4,297,341, Cl. 424-80.000.
- Walter Kidde & Company, Inc.: *See—*
Harshman, Ronald W.; and Dietrich, Lynn A., 4,296,773, Cl. 137-312.000.
- Walter, Rolf: *See—*
Hildebrandt, Norbert; Becker, Norbert; Walter, Rolf; and Hoffmann, Manfred, 4,296,981, Cl. 312-194.000.
- Walther, Gerhard: *See—*
Weber, Karl-Heinz; Schneider, Claus; Walther, Gerhard; Pook, Karl-Heinz; Boke, Karin; and Bechtel, Wolf D., 4,297,354, Cl. 424-248.510.
- Wang, An, to Wang Laboratories, Inc. Helical print head mechanism, 4,297,042, Cl. 400-163.200.
- Wang Laboratories, Inc.: *See—*
Wang, An, 4,297,042, Cl. 400-163.200.
- Wangermann, Jochen; and Gruner & Jahr AG & Co. Apparatus for stacking folded printing products, 4,296,684, Cl. 100-292.000.
- Wankel, Felix, Seal mechanism for the rotor periphery of a rotary piston engine, 4,296,936, Cl. 277-81.00P.
- Ward, Franklin D.; and Engeman, Rock A. Surfboard carrier, 4,296,878, Cl. 224-32.00A.
- Ward, Herbert J.; Dobbie, Derek J.; and Lyall, Brian, to British Cellophane Limited, Heat-sealable polypropylene films, 4,297,415, Cl. 428-516.000.
- Warner, Gary N., to AMP Incorporated, Connector with improved terminal support, 4,296,988, Cl. 339-97.00R.
- Watanabe, Hideo: *See—*
Welsh, Luther; Bergquist, Daryl J.; and Watanabe, Hideo, 4,296,752, Cl. 128-635.000.
- Watanabe Instruments Corp.: *See—*
Ando, Kazunari; Matsunaga, Hirokazu; and Ayabe, Hideaki, 4,297,714, Cl. 346-139.00C.
- Watanabe, Yuichi: *See—*
Nagao, Shozo; Ohashi, Yoshinobu; Watanabe, Yuichi; and Wakushima, Yoshikazu, 4,296,953, Cl. 285-302.000.
- Watson, Ronald S. Anchor device for propeller rotator, 4,296,898, Cl. 244-115.000.
- Wavin B.V.: *See—*
Nicholas, Terry G., 4,297,053, Cl. 405-121.000.
- Wayt, Newell E. Gas anchor, 4,297,084, Cl. 417-179.000.
- Webasto-Werk W. Baier GmbH & Co.: *See—*
Jardin, Hans; and Hirschberger, August, 4,296,962, Cl. 296-217.000.
- Webb, Bryant F.; Makofka, Stanley J.; Webster, Emmett G.; and Blakeslee, Edward A., to Sperry - New Holland, Universal crop divider mechanism, 4,296,593, Cl. 56-98.000.
- Webb, Gerald F., to Northern Telecom Limited, Modular telephone jack, 4,297,529, Cl. 179-1.0PC.
- Weber, Karl-Heinz; Schneider, Claus; Walther, Gerhard; Pook, Karl-Heinz; Boke, Karin; and Bechtel, Wolf D., to Boehringer Ingelheim GmbH, Substituted 4-amino-2,6-diaryl-tetrahydrothiopyrans and salts thereof, and use as antidepressants, 4,297,354, Cl. 424-248.510.
- Webster, Emmett G.: *See—*
Webb, Bryant F.; Makofka, Stanley J.; Webster, Emmett G.; and Blakeslee, Edward A., 4,296,593, Cl. 56-98.000.
- Weghaupt, Erich, to Kraftwerk Union Aktiengesellschaft, Arrangement for cooling the rotor of an electric machine with a superconducting field winding, 4,297,603, Cl. 310-53.000.
- Weil, Edward D., to Stauffer Chemical Company, Copolycondensation products of β -haloalkyl phosphates and dialkyl phosphonates, 4,297,138, Cl. 106-18.180.
- Weiler, Ernest D.: *See—*
Kilbourn, Edward E.; Weiler, Ernest D.; and Weir, William D., 4,297,342, Cl. 424-84.000.
- Weinar, Roger N. Wall constructed from panels held in position with the aid of concealed fasteners and concealable fasteners for use in assembling such wall, 4,296,580, Cl. 52-281.000.
- Weiner, Milton L., to Mobil Oil Corporation, Heat sealable packaging film comprising propylene polymer substrate and a surface layer of an ethylene copolymer and a different olefin copolymer, 4,297,411, Cl. 428-347.000.
- Weinmann, Ernst: *See—*
Bohn, Hans; and Weinmann, Ernst, 4,297,343, Cl. 424-85.000.
- Weir, William D.: *See—*
Kilbourn, Edward E.; Weiler, Ernest D.; and Weir, William D., 4,297,342, Cl. 424-84.000.
- Weiss, Richard: *See—*
Simon, Manfred; Moschter, Erwin; Spiess, Karl-Heinz; and Weiss, Richard, 4,297,099, Cl. 8-484.000.
- Welch, Melvin B.: *See—*
McDaniel, Max P.; and Welch, Melvin B., 4,297,460, Cl. 526-98.000.
- Weller, Alois; and Mai, Wolfgang, to Kieserling & Albrecht, Crank press with lateral rod ejector, 4,296,625, Cl. 72-345.000.
- Wellington, Roger D., to Augat Inc. Electrical contact with improved means for solder wicking and degassing, 4,296,993, Cl. 339-275.00B.
- Wells, Bruce D.: *See—*
McConomy, Thomas A.; and Wells, Bruce D., 4,297,334, Cl. 423-321.00R.
- Welsh, Luther; Bergquist, Daryl J.; and Watanabe, Hideo, to Johnson & Johnson, Transcutaneous oxygen sensor with adjacent heater, 4,296,752, Cl. 128-635.000.
- Werner, Peter; Drews, Ulrich; Elbers, Theodor; and Jackel, Klaus, to Robert Bosch GmbH, Circuit arrangement for obtaining an interference-free trigger signal especially for a fuel apportionment device in an internal combustion engine, 4,297,599, Cl. 307-355.000.
- Werner Weber Holding AB: *See—*
Stranders, Roelof J., 4,296,958, Cl. 294-27.00H.
- Werner, Wolfgang: *See—*
Guthlein, Werner; Wielinger, Hans; Rittersdorf, Walter; and Werner, Wolfgang, 4,297,271, Cl. 260-107.000.
- Wernicke, Hans J.: *See—*
Schliebener, Claus; and Wernicke, Hans J., 4,297,204, Cl. 208-95.000.
- Wess, Beatrice M. Skin moisturizing and cleansing cream, 4,297,374, Cl. 424-364.000.
- Wessling, Diether, to Bayer Aktiengesellschaft, Process for halogenating copper phthalocyanine, 4,297,281, Cl. 260-314.500.
- West Company, The: *See—*
Brignola, Dominic J., 4,296,786, Cl. 141-309.000.
- Western Electric Co., Inc.: *See—*
Garrett, Robert W., 4,297,190, Cl. 204-192.00E.
- Western Geophysical Company of America: *See—*
Thigpen, Ben B.; and Porter, James A., Jr., 4,296,827, Cl. 181-107.000.
- Westinghouse Air Brake Company: *See—*
Housman, Richard J., 4,296,868, Cl. 213-50.000.
- Westinghouse Electric Corp.: *See—*
Chen, Cheng-Lin, 4,297,191, Cl. 204-193.000.
- Durgin, George A.; and Demers, Daniel E., 4,297,077, Cl. 416-97.00R.
- Gupta, Tapan K.; and Pietsch, Herbert E., 4,297,250, Cl. 252-518.000.
- Hagberg, John E., 4,297,740, Cl. 361-67.000.
- Seidel, Martin P., 4,297,254, Cl. 260-18.0EP.
- Wolfe, Donald L.; Modglin, Donald D.; and Merrick, George J., 4,297,061, Cl. 409-131.000.
- Westland Aircraft Limited: *See—*
Martin, Alfred C., 4,297,078, Cl. 416-134.00A.
- Wettstein, Ernest C.: *See—*
Kumar, Kaplesh; Das, Dilip K.; and Wettstein, Ernest C., 4,297,388, Cl. 427-47.000.
- Weyerhaeuser Company: *See—*
Lee, Peter F., 4,297,164, Cl. 162-60.000.
- Van Vliet, Raymond A., 4,297,157, Cl. 156-164.000.
- Whaley, Ralph D.: *See—*
Larson, Roderick W.; and Whaley, Ralph D., 4,296,989, Cl. 339-99.00R.
- Wheelabrator-Frye Inc.: *See—*
Leliaert, Raymond M., 4,296,794, Cl. 164-131.000.
- Whitby, Clyde M., to Singer Company, The, Wide angle laser display system, 4,297,723, Cl. 358-60.000.
- White, Norman H.: *See—*
Nunciato, David J.; White, Norman H.; and Woodburn, William A., 4,297,147, Cl. 134-7.000.
- White, Pat M.: *See—*
Hendrickson, James D.; and White, Pat M., 4,296,807, Cl. 166-184.000.
- Whiteside, George D.: *See—*
Johnson, Bruce K.; and Whiteside, George D., 4,297,016, Cl. 354-27.000.
- Whitman, Hobart A., III, to Olin Corporation, Apparatus for controlled perforation of moving webs with fixed focus laser beam, 4,297,559, Cl. 219-121.0LB.
- Wichmann, Arnold, to Kraftwerk Union Aktiengesellschaft, Method of bracing end turns of an electric machine by means of a binding band; and device used therein, 4,297,606, Cl. 310-271.000.
- Wickmann Werke AG: *See—*
Asdollahi, Nasrollah, 4,297,666, Cl. 337-163.000.
- Widen, Bo G., to GKN-Stenman AB, Anchoring means for door lock plates, 4,296,619, Cl. 70-451.000.
- Wiehler, Wolf: *See—*
Gross, Franz; Boehme, Gerit; Wiehler, Wolf; and Bibracher, Wilhelm, 4,297,662, Cl. 333-252.000.
- Wielinger, Hans: *See—*
Guthlein, Werner; Wielinger, Hans; Rittersdorf, Walter; and Werner, Wolfgang, 4,297,271, Cl. 260-107.000.

- Wil-Rich, Inc.: See—
 Quanbeck, Sherman H., 4,296,695, Cl. 111-34.000.
- Wilcox, Brian N.; and Robinson, John W., to Kimball International, Inc. Solo sustain keyer system. 4,296,666, Cl. 84-1.260.
- Wilder, Gene R.: See—
 Merten, Helmut L.; and Wilder, Gene R., 4,297,269, Cl. 260-45.9QB.
- Wiley, David: See—
 Nicol, Thomas; Wiley, David; and Allport, Maurice J., 4,297,631, Cl. 320-64.000.
- Will, Norbert F.: See—
 Puch, Diethelm; and Will, Norbert F., 4,297,040, Cl. 400-144.200.
- Willburger, Nikolaus: See—
 Brunner, Anton; and Willburger, Nikolaus, 4,297,707, Cl. 343-725.000.
- Willenbacher, Erich: See—
 Jehle, Fritz; and Willenbacher, Erich, 4,296,700, Cl. 112-153.000.
- Williams, Frank J., III; and Relles, Howard M., to General Electric Company. Polyetherimides prepared by self-condensation of hydroxyaryl phthalimide salts. 4,297,474, Cl. 528-170.000.
- Williams, Meurig W.; and Auclair, Christopher J., to Xerox Corporation. Polyblend coated carrier materials. 4,297,427, Cl. 430-108.000.
- Willman, Bertram T., to Exxon Production Research Company. Thermal recovery of viscous hydrocarbons using arrays of radially spaced horizontal wells. 4,296,969, Cl. 299-2.000.
- Willmann, Michael: See—
 Hofbauer, Peter; Willmann, Michael; and Wundrak, Egon, 4,296,716, Cl. 123-195.00C.
- Wilmarth, Paul C.: See—
 Nicholson, John E.; and Wilmarth, Paul C., 4,297,726, Cl. 358-254.000.
- Wilson, John C.: See—
 Woon, Lin-Sun; and Wilson, John C., 4,296,750, Cl. 128-287.000.
- Wilson, Kermit H.; and Carlson, Ronald R., to Sico Incorporated. Audience control barrier. 4,296,573, Cl. 52-6.000.
- Winchester, Loren R. Inflatable camper. 4,296,960, Cl. 296-167.000.
- Winner, Stephen E.: See—
 Patterson, Theodore P.; and Winner, Stephen E., 4,296,499, Cl. 2-239.000.
- Wippich, Rheinhold: See—
 Offermann, Ludwig; and Wippich, Rheinhold, 4,296,938, Cl. 277-135.000.
- Wisconsin Alumni Research Foundation: See—
 DeLuca, Hector F.; Schnoes, Heinrich K.; Paaren, Herbert E.; and Fivizzani, Mary A., 4,297,289, Cl. 260-397.200.
- Wissner, Allan, to American Cyanamid Company. 1-Substituted-1-oxo-propane-derivatives of the E, A and F series. 4,297,516, Cl. 568-330.000.
- Witte, Arnold C.; and Coleman, Richard L., to Texaco Inc. Method for continuous grease manufacture. 4,297,227, Cl. 252-18.000.
- Wolfe, Donald L.; Modglin, Donald D.; and Merrick, George J., to Westinghouse Electric Corp. Steam generator shell parting method and apparatus. 4,297,061, Cl. 409-131.000.
- Wolff, Siegfried; Rothbuh, Lothar; and Grewatta Heinz, to Degussa Aktiengesellschaft. Silane/filler preparations, process for their production and their use. 4,297,145, Cl. 106-308.00Q.
- Wolinski, Leon E.; and Berezuk, Peter D., to Pratt & Lambert, Inc. Non-toxic activators for adhesive compositions. 4,297,158, Cl. 156-305.000.
- Wollny, Klaus: See—
 Hendricks, Udo-Winfried; and Wollny, Klaus, 4,297,103, Cl. 8-534.000.
- Wood, Louis L.; and Larsen, Donald W., to W. R. Grace & Co. Chain-extended polyol compositions and method. 4,297,482, Cl. 528-405.000.
- Wood, Robert C.: See—
 Deardorff, Paul A.; Wood, Robert C.; and Cundari, Sante M., 4,297,303, Cl. 264-3.00R.
- Woodburn, William A.: See—
 Nunciato, David J.; White, Norman H.; and Woodburn, William A., 4,297,147, Cl. 134-7.000.
- Woodcock, Sidney J.: See—
 Shah, Siddharth A.; Woodcock, Sidney J.; and Fagan, Robert D., 4,297,072, Cl. 414-684.300.
- Wooden, Bruce J.; and Edelman, Seymour, to United States of America, Navy. Piezoelectric polymer antifouling coating and method of use and application. 4,297,394, Cl. 427-100.000.
- Woodford, Donald L. Method and apparatus for making a non spherical beveled contact lens. 4,297,008, Cl. 351-177.000.
- Woodhead, James L.: See—
 Cairns, James A.; Nelson, Robert L.; and Woodhead, James L., 4,297,246, Cl. 252-465.000.
- Woolbright, Kenneth O. Sound broadcasting apparatus. 4,296,664, Cl. 84-1.030.
- Wooldridge, Timothy A.: See—
 Mundi, Randall S.; Wooldridge, Timothy A.; and Blasingame, Thomas O., 4,297,162, Cl. 156-643.000.
- Woon, Lin-Sun; and Wilson, John C., to Kimberly-Clark Corporation. Refastenable pressure-sensitive tape closure system for disposable diapers and method for its manufacture. 4,296,750, Cl. 128-287.000.
- World Wide Oil Tools, Inc.: See—
 Keast, Larry G.; and Horton, Herbert D., 4,296,842, Cl. 188-61.000.
- Worthington, Byron C. Chair carrier. 4,297,069, Cl. 414-462.000.
- Wraige, Douglas: See—
 Metcalfe, John L.; and Wraige, Douglas, 4,297,406, Cl. 428-215.000.
- Wright, Joe B. Water ski with increased stability. 4,296,511, Cl. 9-310.00A.
- Wright, Philip: See—
 Coe, Charles D.; and Wright, Philip, 4,297,577, Cl. 250-343.000.
- Wu, Che-Kuang, to Corning Glass Works. Photosensitive colored glasses exhibiting alterable photo-anisotropic effects. 4,297,417, Cl. 428-410.000.
- Wu, Ching-Yong; Pretzer, Wayne R.; and Kobylinski, Thaddeus P., to Gulf Research & Development Company. Decomposition of cumene hydroperoxide with a homogeneous catalyst. 4,297,518, Cl. 568-385.000.
- Wulf, Helmut, to Daimler-Benz Aktiengesellschaft. Heat transfer system. 4,296,796, Cl. 165-46.000.
- Wulff, B. James: See—
 Day, Ralph R.; and Wulff, B. James, 4,296,917, Cl. 254-400.000.
- Wundrak, Egon: See—
 Hofbauer, Peter; Willmann, Michael; and Wundrak, Egon, 4,296,716, Cl. 123-195.00C.
- Wurttembergische Metallwarenfabrik: See—
 Schlegel, Hans; and Nowotny, Theodor, 4,297,175, Cl. 204-15.000.
- Wurtz, Howard P.; and Peterson, Eugene W., to Hughes Aircraft Company. Vacuum gettering arrangement. 4,297,082, Cl. 417-51.000.
- Wyse, Harold G.; and Smith, Millard S. Method and apparatus for producing a nitrate fertilizer. 4,297,123, Cl. 71-58.000.
- Wyss, Clement R.: See—
 Topalian, Harry H.; Wyss, Clement R.; Kenyon, Ralph E.; and Dec, Anthony F., 4,297,379, Cl. 426-565.000.
- Xerox Corporation: See—
 Carlson, Gerald E., 4,297,029, Cl. 355-133.000.
- Corona, Stephen C., 4,297,616, Cl. 315-179.000.
- Hewitt, Harvey J., 4,297,424, Cl. 430-58.000.
- Marshall, Richard C., 4,297,695, Cl. 340-752.000.
- Pai, Damodar M.; Pochan, John M.; and Pochan, Darlyn F., 4,297,425, Cl. 430-58.000.
- Scifres, Donald R.; and Stutius, Wolfgang E., 4,297,653, Cl. 331-94.50S.
- Williams, Meurig W.; and Auclair, Christopher J., 4,297,427, Cl. 430-108.000.
- Yabuki, Yoshiharu: See—
 Aoki, Kojo; Sawada, Satoru; Yabuki, Yoshiharu; and Furutachi, Nobuo, 4,297,440, Cl. 430-505.000.
- Yagi, Michio; Nakajima, Kunio; Nakagawa, Yasutsugu; Ishii, Sizuo; and Aratame, Kazuhisa, to Konishiroku Photo Industry Co., Ltd. Automatic film feeding apparatus for photographic camera. 4,297,019, Cl. 354-171.000.
- Yakimenko, Valentin G.: See—
 Goldin, Rodion G.; and Yakimenko, Valentin G., 4,297,739, Cl. 361-55.000.
- Yamada, Keita. Method of recovering gold. 4,297,134, Cl. 75-118.00R.
- Yamada, Shoji: See—
 Kanada, Eiji; Yamada, Shoji; and Tsubai, Yasuo, 4,297,429, Cl. 430-204.000.
- Kanada, Eiji; Yamada, Shoji; and Tsubai, Yasuo, 4,297,430, Cl. 430-204.000.
- Yamada, Tsuguyoshi: See—
 Sakai, Yoshihiro; Tanaka, Ryosaku; Kita, Toshio; Shimotake, Munetoshi; Yamada, Tsuguyoshi; and Ueda, Hiroshi, 4,296,790, Cl. 152-354.00R.
- Yamada, Tsuneo: See—
 Wada, Takeshi; Kominami, Yasuo; Miyamoto, Yukihiko; and Yamada, Tsuneo, 4,297,601, Cl. 307-555.000.
- Yamada, Yasuyuki; and Okuno, Youichi, to Canon Kabushiki Kaisha. View finder for single-lens reflex camera. 4,297,020, Cl. 354-225.000.
- Yamagishi, Hideki: See—
 Deguchi, Yukichi; Yamagishi, Hideki; and Kirimura, Shunichiro, 4,297,187, Cl. 204-165.000.
- Yamaguchi, Shingo: See—
 Ogawa, Mutsuo; Koseki, Yuji; Saitoh, Yuichi; Yamaguchi, Shingo; and Katsuragi, Shigeru, 4,297,727, Cl. 358-261.000.
- Yamamoto, Hiroshi: See—
 Kawamura, Masaharu; Uchidoi, Masanori; Shigeta, Yoshihiro; Sugiura, Yoji; and Yamamoto, Hiroshi, 4,297,013, Cl. 354-23.00D.
- Yamamoto, Kaneco. Process for making diazo photosensitive paper. 4,297,428, Cl. 430-169.000.
- Yamamoto, Minoru; Tachikawa, Shiro; and Maeno, Hiroo, to Yamanouchi Pharmaceutical Co., Ltd. Memory enhancer containing 2-(7-indenylloxymethyl-morpholine. 4,297,356, Cl. 424-248.570.
- Yamane, Hiroyuki: See—
 Nishikido, Joji; Tamura, Nobuhiro; Fukuoka, Yohei; and Yamane, Hiroyuki, 4,297,503, Cl. 560-42.000.
- Yamanouchi Pharmaceutical Co., Ltd.: See—
 Yamamoto, Minoru; Tachikawa, Shiro; and Maeno, Hiroo, 4,297,356, Cl. 424-248.570.
- Yanagida, Kiyoshi: See—
 Kadowaki, Hidetaka; Inomata, Akira; Yanagida, Kiyoshi; Hasegawa, Tsunao; Ishii, Satoshi; and Ohtake, Yasushi, 4,297,730, Cl. 360-66.000.
- Yanna, Andrew F. Heat generation and distribution system. 4,296,883, Cl. 237-59.000.
- Yano, Takefumi: See—
 Ueno, Haruo; Yano, Takefumi; Inoue, Tokujii; Ikai, Shigeru; Kai, Yoshiyuki; and Shimizu, Michimasa, 4,297,463, Cl. 526-128.000.
- Yao, Shi K.: See—
 Smith, Elroy C., Jr.; and Yao, Shi K., 4,297,189, Cl. 204-192.0SP.

- Yasinsky, Konstantin K.; Glazunov, Sergei G.; Ross, Jury N.; and Bykov, Igor D. Refractory suspension for making foundry moulds. 4,296,793, Cl. 164-24.000.
- Yasuba, Shoichi; and Ito, Takaharu, to Okuma Machinery Works, Ltd. Method and apparatus for positioning work on a numerically controlled lathe. 4,296,657, Cl. 82-1.00C.
- Yasuda, Naohiko; and Nakanishi, Eiji, to Ajinomoto Co., Inc. Imidazoledicarboxylic acid derivative. 4,297,279, Cl. 260-239.100.
- Yasuda, Takeo: See—
 Hikuma, Motohiko; Kubo, Tatsuru; Yasuda, Takeo; Karube, Isao; and Suzuki, Shuichi, 4,297,173, Cl. 204-1.00T.
- Yasuda, Toshio, to Elastoflon Inc. Compound for coating containing fluorocarbonpolymer and method for its manufacture. 4,297,447, Cl. 525-133.000.
- Yenzer, Dennis E.; Cha, John H.; and Abramovich, Dan, to Santa Fe International Corporation. Method of laying offshore pipeline from a reel carrying vessel. 4,297,054, Cl. 405-168.000.
- Yokoi, Gunpei, to Nintendo Co., Ltd. Projecting-type shooting game apparatus. 4,296,931, Cl. 273-316.000.
- Yokoi, Masatada: See—
 Fujimori, Fumio; Yokoi, Masatada; Ishikawa, Masakazu; Uemura, Hiroshi; and Shirai, Akira, 4,296,841, Cl. 188-73.380.
- Yokoyama, Junichi: See—
 Nakamura, Ken; Ofuji, Hiromichi; and Yokoyama, Junichi, 4,297,302, Cl. 261-65.000.
- Yonetani, Kengo: See—
 Ito, Kunimoto; Kakizawa, Tsutomu; Yonetani, Kengo; and Nariai, Hiroshi, 4,297,610, Cl. 310-370.000.
- Yonezu, Hiroo: See—
 Hayashi, Izuo; and Yonezu, Hiroo, 4,297,652, Cl. 331-94.50H.
- Yoshida Iron Works Co., Ltd.: See—
 Fujii, Kenji, 4,297,133, Cl. 75-53.000.
- Yoshida, Keizo; Tanaka, Hirokazu; Okamoto, Masanori; Iguchi, Eiko; Kohsaka, Masanobu; Aoki, Hatsuo; and Imanaka, Hiroshi, to Fujisawa Pharmaceutical Co. Ltd. Alkyl, alkenyl, and aryl substituted triazene compounds, their salts and production thereof. 4,297,096, Cl. 435-128.000.
- Yoshida Kogyo K.K.: See—
 Hakoi, Tsutomu, 4,296,547, Cl. 29-766.000.
- Yoshida, Tomio: See—
 Kahara, Toshiki; Tamura, Kohki; Ebata, Noboru; Sato, Fumio; and Yoshida, Tomio, 4,297,231, Cl. 252-182.100.
- Yoshino Kogyosho Co., Ltd.: See—
 Yoshino, Yataro; Suzuki, Sadao; and Takada, Takuzo, 4,297,306, Cl. 264-23.000.
- Yoshino, Yataro; Suzuki, Sadao; and Takada, Takuzo, to Yoshino Kogyosho Co., Ltd. Neck orienting method of bottles of saturated polyester resins. 4,297,306, Cl. 264-23.000.
- Young, Dennis: See—
 Foster, Alan I.; Sims, Malcolm L.; and Young, Dennis, 4,297,150, Cl. 148-6.300.
- Young, Harlow S.: See—
 Harney, David L.; and Young, Harlow S., 4,297,377, Cl. 426-438.000.
- Young, Kenneth A.: See—
 Townsend, Raymond L.; Kester, Jack R.; and Young, Kenneth A., 4,297,561, Cl. 219-137.630.
- Zadiraka, Allan J., to Babcock & Wilcox Company. The Control system for a solar steam generator. 4,296,730, Cl. 126-421.000.
- Zaidan Hojin Biseibutsu Kagaku Kenkyu Kai: See—
 Umezawa, Hamao; Umezawa, Sumio; Tsuchiya, Tsutomu; Takagi, Yasushi; and Jikihara, Tomo, 4,297,485, Cl. 536-10.000.
- Zaneveld, Lourens J. D.: See—
 Waller, Donald P.; Zaneveld, Lourens J. D.; and Fong, Harry H. S., 4,297,341, Cl. 424-80.000.
- Zeeth, Bernd: See—
 Sauter, Hubert; Zeeth, Bernd; Rentzea, Costin; and Pommer, Ernst-Heinrich, 4,297,364, Cl. 424-267.000.
- Zehren, James N., to TRW Inc. Method for splicing an electrical cable. 4,296,548, Cl. 29-871.000.
- Zeiringer, Rudolf: See—
 Claassen, Peter; List, Helmut; and Zeiringer, Rudolf, 4,296,635, Cl. 73-730.000.
- Zenith Radio Corporation: See—
 Kiteley, Terence J., 4,297,619, Cl. 315-381.000.
- Zervopoulos, Panagiotis. Masonry cleaning process and composition. 4,297,148, Cl. 134-3.000.
- Zhestkov, Vitaly I.: See—
 Shlykov, Gennady N.; Zhestkov, Vitaly I.; Tikhonov, Valentin N.; Dyachkov, Vasily M.; Glazov, Vladimir G.; and Krjuk, Timur P., 4,296,528, Cl. 19-255.000.
- Zimmerly, Robert D., to Ladish Co. Spheroidal interconnector for filtration modules. 4,296,951, Cl. 285-95.000.
- Zobel, Henry F.: See—
 Klein, Gary H.; Arons, Howard L.; Stejskal, Joseph F.; Stevens, Donald G.; and Zobel, Henry F., 4,297,144, Cl. 106-197.00C.
- Zoecon Corp.: See—
 Henrick, Clive A.; Labovitz, Jeffrey N.; Fox, Roland T. V.; Rathmell, William G.; and Shephard, Margaret C., 4,297,297, Cl. 260-465.00D.
- Zoor, Reinhold, to Heinrich Wunder KG. Anti-theft arrangement, particularly for a mast of a sailing craft. 4,296,615, Cl. 70-19.000.
- Zuern, Ludwig: See—
 Caesar, Arndt C.; Koegel, Wolfram; Zuern, Ludwig; and Gaertner, Friedhelm, 4,297,252, Cl. 252-606.000.
- Zydzik, George J.: See—
 Johnson, David W., Jr.; Singh, Shobha; Van Uiter, LeGrand G.; and Zydzik, George J., 4,297,005, Cl. 350-357.000.

LIST OF REISSUE PATENTEEES

TO WHOM

PATENTS WERE ISSUED ON THE 27TH DAY OF OCTOBER, 1981

NOTE—Arranged in accordance with the first significant character or word of the name (in accordance with city and telephone directory practice).

Bollert, Ulrich: See—
Kleiner, Hans-Jerg; Finke, Manfred; Bollert, Ulrich; and Herwig, Walter, Re. 30,783, Cl. 528-287.000.
Bridges, Ronald P. Group operated circuit disconnect apparatus for overhead electric power lines. Re. 30,784, Cl. 200-48.0K.B.
Calfee, Richard W.: See—
Lovercheck, Lawrence R.; Hileman, Russell K.; and Calfee, Richard W., Re. 30,785, Cl. 364-200.000.
Finke, Manfred: See—
Kleiner, Hans-Jerg; Finke, Manfred; Bollert, Ulrich; and Herwig, Walter, Re. 30,783, Cl. 528-287.000.
Herwig, Walter: See—
Kleiner, Hans-Jerg; Finke, Manfred; Bollert, Ulrich; and Herwig, Walter, Re. 30,783, Cl. 528-287.000.
Hileman, Russell K.: See—
Lovercheck, Lawrence R.; Hileman, Russell K.; and Calfee, Richard W., Re. 30,785, Cl. 364-200.000.
Hoechst Aktiengesellschaft: See—
Kleiner, Hans-Jerg; Finke, Manfred; Bollert, Ulrich; and Herwig, Walter, Re. 30,783, Cl. 528-287.000.
Kleiner, Hans-Jerg; Finke, Manfred; Bollert, Ulrich; and Herwig, Walter, to Hoechst Aktiengesellschaft. Flame retarding linear polyesters and shaped articles thereof. Re. 30,783, Cl. 528-287.000.
Lovercheck, Lawrence R.; Hileman, Russell K.; and Calfee, Richard W., to Zentec Corporation. Microcomputer terminal system. Re. 30,785, Cl. 364-200.000.
Minnesota Mining and Manufacturing Company: See—
van Turnhout, Jan, Re. 30,782, Cl. 264-22.000.
van Turnhout, Jan, to Minnesota Mining and Manufacturing Company. Method for the manufacture of an electret fibrous filter. Re. 30,782, Cl. 264-22.000.
Zentec Corporation: See—
Lovercheck, Lawrence R.; Hileman, Russell K.; and Calfee, Richard W., Re. 30,785, Cl. 364-200.000.

LIST OF DESIGN PATENTEEES

Advertising Displays Corporation: See—
Marks, Philip, 261,479, Cl. D9-341.000.
Affiliated Hatch and Sunroof, Inc.: See—
Butler, James P., 261,500, Cl. D12-191.000.
Albert, Ramon R. Sofa. 261,451, 10-27-81, Cl. D6-63.000.
Alessandrini, Anna M.: See—
Alessandrini, Paul P.; and Alessandrini, Anna M., 261,467, Cl. D7-74.000.
Alessandrini, Paul P.; and Alessandrini, Anna M. Combined knife set and rack. 261,467, 10-27-81, Cl. D7-74.000.
Appel, Mel; and Means, Paul B., III, to Appel, Mel. Combined toy bucket and tools therefor. 261,540, 10-27-81, Cl. D21-120.000.
Appel, Mel; and Kress, George, to Appel, Mel. Combined toy bucket and tools therefor. 261,541, 10-27-81, Cl. D21-120.000.
Baus, Andre E. J.; and Pair, Robert E. L. A., to Goodyear Tire & Rubber Company, The. Tire. 261,493, 10-27-81, Cl. D12-143.000.
Baus, Andre E. J.; Fontaine, Jean F. L.; and Ham, Brian L., to Goodyear Tire & Rubber Company, The. Tire. 261,497, 10-27-81, Cl. D12-147.000.
Baus, Andre E. J., to Goodyear Tire & Rubber Company, The. Tire. 261,498, 10-27-81, Cl. D12-148.000.
Beckman Instruments, Inc.: See—
Lindsay, James R.; and Vedder, Gene D., 261,488, Cl. D10-78.000.
Benchmark Tool Company: See—
Ireland, Edward A., 261,519, Cl. D15-134.000.
Berman, James S.; and Stegmaier, Sigurd, to Citibank, N.A. Service counter. 261,456, 10-27-81, Cl. D6-157.000.
Berman, James S.; and Stegmaier, Sigurd, to Citibank, N.A. Service counter. 261,457, 10-27-81, Cl. D6-157.000.
Berman, James S.; and Stegmaier, Sigurd, to Citibank, N.A. Teller counter. 261,458, 10-27-81, Cl. D6-157.000.
Berman, James S.; and Stegmaier, Sigurd, to Citibank, N.A. Desk. 261,459, 10-27-81, Cl. D6-157.000.
Berman, James S.; and Stegmaier, Sigurd, to Citibank, N.A. Desk. 261,460, 10-27-81, Cl. D6-157.000.
Berman, James S.; and Stegmaier, Sigurd, to Citibank, N.A. Service counter. 261,461, 10-27-81, Cl. D6-162.000.
Berman, James S.; and Stegmaier, Sigurd, to Citibank, N.A. Service counter. 261,462, 10-27-81, Cl. D6-162.000.
Blumberg, Bert: See—
Butter, Ann F.; and Blumberg, Bert, 261,518, Cl. D15-118.000.
Boroda, Eli. Housing for an electronic stimulator. 261,551, 10-27-81, Cl. D24-41.000.
Boroda, Eli. Housing for an electronic stimulator. 261,552, 10-27-81, Cl. D24-41.000.
Bowman Construction Supply, Inc.: See—
Bowman, William E., 261,555, Cl. D25-74.000.
Bowman, William E., to Bowman Construction Supply, Inc. Expansion joint sealing strip for roadway joints and the like. 261,555, 10-27-81, Cl. D25-74.000.
Bridgestone Tire Company, Limited: See—
Suzuki, Norio; and Kojima, Hiroshi, 261,494, Cl. D12-146.000.
Brookfield Athletic Shoe Company, Inc.: See—
Landay, David L.; and Wolf, Alvan H., 261,542, Cl. D21-226.000.
Butler, James P., to Affiliated Hatch and Sunroof, Inc. Vehicle visor. 261,500, 10-27-81, Cl. D12-191.000.
Butter, Ann F.; and Blumberg, Bert. Barrier free drinking fountain. 261,518, 10-27-81, Cl. D15-118.000.
C-R-O, Inc.: See—
O'Donnell, Thomas P.; and Howery, James A., 261,476, Cl. D8-30.000.
Canon Kabushiki Kaisha: See—
Kando, Masahiro; and Shinkai, Hiroshi, 261,524, Cl. D16-44.000.
Sakai, Masaaki; and Hirose, Kunio, 261,528, Cl. D18-7.000.
Carbajales, Javier B. S.: See—
Carbajales, Jesus A. S.; and Carbajales, Javier B. S., 261,490, Cl. D11-158.000.
Carbajales, Jesus A. S.; and Carbajales, Javier B. S., to John J. Madison Company, Inc. Figurine of a basset hound. 261,490, 10-27-81, Cl. D11-158.000.
Carson, Billie R., to CBS Inc. Bridge assembly for guitars. 261,526, 10-27-81, Cl. D17-21.000.
Carson, Billie R., to CBS Inc. Bridge assembly for guitars. 261,527, 10-27-81, Cl. D17-21.000.
CBS Inc.: See—
Carson, Billie R., 261,526, Cl. D17-21.000.
Carson, Billie R., 261,527, Cl. D17-21.000.
Chambers, Richard F. Asphalt plant control house. 261,553, 10-27-81, Cl. D25-22.000.
Champion International Corporation: See—
Cottrell, Edward D.; and Robbins, Michael B., 261,516, Cl. D15-92.000.
Chandler, Marlene Y. Toilet tissue cover. 261,452, 10-27-81, Cl. D6-86.000.
Chisholm, James E., to MCC-Powers-Fiat. Modular shower stall. 261,548, 10-27-81, Cl. D23-57.000.
Cicerella, Michael C. Game board. 261,536, 10-27-81, Cl. D21-20.000.
Citibank, N.A.: See—
Berman, James S.; and Stegmaier, Sigurd, 261,456, Cl. D6-157.000.
Berman, James S.; and Stegmaier, Sigurd, 261,457, Cl. D6-157.000.
Berman, James S.; and Stegmaier, Sigurd, 261,458, Cl. D6-157.000.
Berman, James S.; and Stegmaier, Sigurd, 261,459, Cl. D6-157.000.
Berman, James S.; and Stegmaier, Sigurd, 261,460, Cl. D6-157.000.
Berman, James S.; and Stegmaier, Sigurd, 261,461, Cl. D6-162.000.
Berman, James S.; and Stegmaier, Sigurd, 261,462, Cl. D6-162.000.
Cobb, Richard E., to GTE Automatic Electric Labs. Inc. Wall mounted holder for a telephone set. 261,509, 10-27-81, Cl. D14-65.000.
Cody, Patrick D., to Innova Equipment Limited. Vacuum cleaner. 261,514, 10-27-81, Cl. D32-21.000.
Coilhouse Pneumatics, Inc.: See—
Schenker, Michael, 261,501, Cl. D12-194.000.
Conner, James M.; and Ryan, James M., to Polaroid Corporation. Electronic flash or similar article. 261,523, 10-27-81, Cl. D16-42.000.
Container Corporation of America: See—
Darois, Roger E., 261,569, Cl. D34-39.000.
Cottrell, Edward D.; and Robbins, Michael B., to Champion International Corporation. Machine for dispensing and inserting sticks in comestibles. 261,516, 10-27-81, Cl. D15-92.000.
Cramer, Lyle L. Skateboard. 261,544, 10-27-81, Cl. D21-227.000.
Culbertson, Richard, to General Electric Company. Tape recorder and player or similar article. 261,506, 10-27-81, Cl. D14-6.000.

LIST OF DESIGN PATENTEEES

PI 45

Darois, Roger E., to Container Corporation of America. Drum. 261,569, 10-27-81, Cl. D34-39.000.
Davis, Ralph L., to Payne, Wilbert A. Combined caddy for powdered products or the like and implements therefor. 261,568, 10-27-81, Cl. D28-77.000.
Delcroix, Guy, to Waterman S.A. Marking pen. 261,531, 10-27-81, Cl. D19-4.000.
Dickson, Thomas D., Jr. Foodstuff mill. 261,517, 10-27-81, Cl. D15-98.000.
DuBois, Arthur E. Reflector. 261,489, 10-27-81, Cl. D10-111.000.
Edson, Sydney, to Howard Displays, Inc. Counter display stand. 261,449, 10-27-81, Cl. D6-23.000.
Englishtown Sportswear, Ltd.: See—
Heinfling, Martin, 261,445, Cl. D2-25.000.
Envall, Bjorn E. A., to Saab-Scania Aktiebolag. Wheel. 261,502, 10-27-81, Cl. D12-211.000.
Escobedo, Antonio M.: See—
Havens, John H., 261,510, Cl. D14-65.000.
Ewert, Carl H. Spice rack. 261,455, 10-27-81, Cl. D6-130.000.
Fontaine, Jean F. L.: See—
Baus, Andre E. J.; Fontaine, Jean F. L.; and Ham, Brian L., 261,497, Cl. D12-147.000.
Gauntt, William P. Tamper proof striker plate. 261,478, 10-27-81, Cl. D8-344.000.
General Bathroom Products Company: See—
Palka, James J.; and Rekart, Robert, 261,557, Cl. D26-87.000.
Palka, James J.; and Rekart, Robert, 261,558, Cl. D26-87.000.
Palka, James J.; and Rekart, Robert, 261,559, Cl. D26-87.000.
Palka, James J.; and Rekart, Robert, 261,560, Cl. D26-87.000.
General Binding Corporation: See—
Hausmann, Herbert H., 261,529, Cl. D18-34.000.
Hausmann, Herbert H., 261,530, Cl. D18-34.000.
General Electric Company: See—
Culbertson, Richard, 261,506, Cl. D14-6.000.
Kolwaite, John S., 261,512, Cl. D14-73.000.
Gillette Company, The: See—
Poisson, Norman D., 261,564, Cl. D28-48.000.
Goodyear Tire & Rubber Company, The: See—
Baus, Andre E. J.; and Pair, Robert E. L. A., 261,493, Cl. D12-143.000.
Baus, Andre E. J.; Fontaine, Jean F. L.; and Ham, Brian L., 261,497, Cl. D12-147.000.
Baus, Andre E. J., 261,498, Cl. D12-148.000.
Hammond, Philip S., 261,491, Cl. D12-142.000.
Remy, Raymond M., 261,492, Cl. D12-143.000.
Remy, Raymond M., 261,496, Cl. D12-147.000.
Yurkovich, Charles G., 261,495, Cl. D12-146.000.
Graham, Elwood M.; and Polivka, John, to M. H. Graham Corporation. Food cutter. 261,472, 10-27-81, Cl. D7-155.000.
Grange, Kenneth H., to Wilkinson Sword Ltd. Razor handle. 261,565, 10-27-81, Cl. D28-48.000.
GTE Automatic Electric Labs. Inc.: See—
Cobb, Richard E., 261,509, Cl. D14-65.000.
H.I.T. Industries Ltd.: See—
Tawil, Abraham I., 261,535, Cl. D21-15.000.
Ham, Brian L.: See—
Baus, Andre E. J.; Fontaine, Jean F. L.; and Ham, Brian L., 261,497, Cl. D12-147.000.
Hammond, Philip S., to Goodyear Tire & Rubber Company, The. Tire tread and buttress. 261,491, 10-27-81, Cl. D12-142.000.
Harada, Toshio: See—
Takahashi, Yoichi; Yamamura, Mashimichi; Harada, Toshio; and Inoue, Shigefumi, 261,468, Cl. D7-128.000.
Harper, Russell W., to Maryland Cup Corporation. Ice cream cone serving tray. 261,466, 10-27-81, Cl. D7-38.000.
Hass, William J. Radio receiver. 261,511, 10-27-81, Cl. D14-68.000.
Haubert, Carol A., to Raytheon Company. Packaging container for cassettes or the like. 261,481, 10-27-81, Cl. D9-341.000.
Haubert, Carol A., to Raytheon Company. Packaging container for cassettes or the like. 261,482, 10-27-81, Cl. D9-341.000.
Haubert, Carol A., to Raytheon Company. Packaging container for cassettes or the like. 261,484, 10-27-81, Cl. D9-341.000.
Haubert, Carol A., to Raytheon Company. Packaging container for cassettes or the like. 261,485, 10-27-81, Cl. D9-341.000.
Hausmann, Herbert H., to General Binding Corporation. Combined punch and binding machine. 261,529, 10-27-81, Cl. D18-34.000.
Hausmann, Herbert H., to General Binding Corporation. Combined electric punch and binding machine. 261,530, 10-27-81, Cl. D18-34.000.
Havens, John H., to Escobedo, Antonio M. Telephone handset holder. 261,510, 10-27-81, Cl. D14-65.000.
Heinfling, Martin, to Englishtown Sportswear, Ltd. Pocket for jeans or the like. 261,445, 10-27-81, Cl. D2-25.000.
Hirose, Kunio: See—
Sakai, Masaaki; and Hirose, Kunio, 261,528, Cl. D18-7.000.
Hobrecht, William, to New England Pottery Co. Potted plant hanger. 261,454, 10-27-81, Cl. D6-113.000.
Hollingsworth, Gene C., to Zero Corporation. Pin socket. 261,504, 10-27-81, Cl. D13-24.000.
Holmberg, Larry A. Adjustable plug for shotgun shell chamber. 261,545, 10-27-81, Cl. D22-7.000.
Homich, Richard D. Game board. 261,537, 10-27-81, Cl. D21-34.000.
Howard Displays, Inc.: See—
Edson, Sydney, 261,449, Cl. D6-23.000.
Howery, James A.: See—
O'Donnell, Thomas P.; and Howery, James A., 261,476, Cl. D8-30.000.
Hug, Niklaus, to Rommag P. Worwag & Co. Suction brush. 261,473, 10-27-81, Cl. D32-18.000.
Innova Equipment Limited: See—
Cody, Patrick D., 261,514, Cl. D32-21.000.
Inoue, Shigefumi: See—
Takahashi, Yoichi; Yamamura, Mashimichi; Harada, Toshio; and Inoue, Shigefumi, 261,468, Cl. D7-128.000.
Ireland, Edward A., to Benchmark Tool Company. Housing for a bench top band saw. 261,519, 10-27-81, Cl. D15-134.000.
Jenkins, Robert J. Portable seat. 261,450, 10-27-81, Cl. D6-26.000.
John J. Madison Company, Inc.: See—
Carbajales, Jesus A. S.; and Carbajales, Javier B. S., 261,490, Cl. D11-158.000.
Johnson, Lester L., Sr. Two-wheeled oil refiner dolly or the like. 261,520, 10-27-81, Cl. D15-150.000.
Johnson, Lester L., Sr. Oil refiner movable carriage or the like. 261,521, 10-27-81, Cl. D15-150.000.
Joseph, Clive E. Clothes pin. 261,474, 10-27-81, Cl. D32-61.000.
Kando, Masahiro; and Shinkai, Hiroshi, to Canon Kabushiki Kaisha. Grip for a cinecamera. 261,524, 10-27-81, Cl. D16-44.000.
Kohno Plastic Co., Ltd.: See—
Kohno, Yoshiharu, 261,487, Cl. D10-58.000.
Kohno, Yoshiharu, to Kohno Plastic Co., Ltd. Thermometer. 261,487, 10-27-81, Cl. D10-58.000.
Kojima, Hiroshi: See—
Suzuki, Norio; and Kojima, Hiroshi, 261,494, Cl. D12-146.000.
Kolwaite, John S., to General Electric Company. Clock radio or similar article. 261,512, 10-27-81, Cl. D14-73.000.
Koziol, Walter, to Modern Home Products Corp. Combined rotisserie motor and extended light. 261,469, 10-27-81, Cl. D7-129.000.
Koziol, Walter, to Modern Home Products Corp. Combined rotisserie motor and light. 261,470, 10-27-81, Cl. D7-129.000.
Koziol, Walter, to Modern Home Products Corp. Combined rotisserie motor and light. 261,471, 10-27-81, Cl. D7-129.000.
Kress, George: See—
Appel, Mel; and Kress, George, 261,541, Cl. D21-120.000.
Landay, David L.; and Wolf, Alvan H., to Brookfield Athletic Shoe Company, Inc. Integral shoe sole and wheel mounting for roller skate. 261,542, 10-27-81, Cl. D21-226.000.
Lee, Ernest, to Sunbeam Corporation. Hair dryer. 261,563, 10-27-81, Cl. D28-13.000.
Legerius, Bengt E. Cable channel shelf. 261,554, 10-27-81, Cl. D25-74.000.
Leisurecraft Products Ltd.: See—
Pardo, John, 261,508, Cl. D14-64.000.
Letourneau, Marc-Andre. Lighting fixture. 261,561, 10-27-81, Cl. D26-88.000.
Liebscher, Frank M. Key ring ornament. 261,448, 10-27-81, Cl. D3-65.000.
Lindsay, James R.; and Vedder, Gene D., to Beckman Instruments, Inc. Multimeter. 261,488, 10-27-81, Cl. D10-78.000.
Lowenthal, Jana. Combined cosmetic container and abrader. 261,480, 10-27-81, Cl. D9-314.000.
M. H. Graham Corporation: See—
Graham, Elwood M.; and Polivka, John, 261,472, Cl. D7-155.000.
Madl, Alfred W., to Sunbeam Corporation. Make-up mirror. 261,567, 10-27-81, Cl. D28-67.000.
Marks, Philip, to Advertising Displays Corporation. Combined shipping, storage and serving unit for bottles of wine or the like. 261,479, 10-27-81, Cl. D9-341.000.
Martin, Nick P. Simulative photo frame. 261,463, 10-27-81, Cl. D6-243.000.
Maryland Cup Corporation: See—
Harper, Russell W., 261,466, Cl. D7-38.000.
Matsushita Electric Industrial Co., Ltd.: See—
Takahashi, Yoichi; Yamamura, Mashimichi; Harada, Toshio; and Inoue, Shigefumi, 261,468, Cl. D7-128.000.
Mayuzumi, Masaki; and Yoshimura, Masaaki, to Tomy Kogyo Co., Inc. Pocket size game box. 261,534, 10-27-81, Cl. D21-10.000.
MCC-Powers-Fiat: See—
Chisholm, James E., 261,548, Cl. D23-57.000.
Means, Paul B., III: See—
Appel, Mel; and Means, Paul B., III, 261,540, Cl. D21-120.000.
Miller, Gerald K., to Nartron Corporation. Electrical control housing assembly. 261,505, 10-27-81, Cl. D13-32.000.
Minchew, Scott R. Serving bowl. 261,465, 10-27-81, Cl. D7-19.000.
Modern Home Products Corp.: See—
Koziol, Walter, 261,469, Cl. D7-129.000.
Koziol, Walter, 261,470, Cl. D7-129.000.
Koziol, Walter, 261,471, Cl. D7-129.000.
Morris, Leonard A., Sr. Skateboard. 261,543, 10-27-81, Cl. D21-227.000.
Muller, Richard B. Transmission detent cable connector. 261,513, 10-27-81, Cl. D15-5.000.
Nagley, Bruce K. Typing copy holder. 261,533, 10-27-81, Cl. D19-91.000.
Nartron Corporation: See—
Miller, Gerald K., 261,505, Cl. D13-32.000.
National Union Electric Corporation: See—
Schaefer, Harold W.; and Wiese, Martin E., 261,515, Cl. D32-23.000.
New England Pottery Co.: See—
Hobrecht, William, 261,454, Cl. D6-113.000.

LIST OF DESIGN PATENTEES

O'Donnell, Thomas P.; and Howerly, James A., to C-R-O, Inc. Welding gun. 261,476, 10-27-81, Cl. D8-30.000.

Olson, David V. Combination floss holder, key chain fob and dental appointment reminder. 261,566, 10-27-81, Cl. D28-64.000.

O'Reilly, Bryan. Combined lamp base and ball holder. 261,556, 10-27-81, Cl. D26-51.000.

Pair, Robert E. L. A.: See—
Baus, Andre E. J.; and Pair, Robert E. L. A., 261,493, Cl. D12-143.000.

Palka, James J.; and Rekart, Robert, to General Bathroom Products Company. Lighting fixture. 261,557, 10-27-81, Cl. D26-87.000.

Palka, James J.; and Rekart, Robert, to General Bathroom Products Company. Lighting fixture. 261,558, 10-27-81, Cl. D26-87.000.

Palka, James J.; and Rekart, Robert, to General Bathroom Products Company. Lighting fixture. 261,559, 10-27-81, Cl. D26-87.000.

Palka, James J.; and Rekart, Robert, to General Bathroom Products Company. Lighting fixture. 261,560, 10-27-81, Cl. D26-87.000.

Pardo, John, to Leisurecraft Products Ltd. Hand-held telephone. 261,508, 10-27-81, Cl. D14-64.000.

Parke, W. Rod. Air regulating nozzle. 261,547, 10-27-81, Cl. D23-34.000.

Patterson, Donald R. Pediatric examination table. 261,549, 10-27-81, Cl. D24-3.000.

Payne, Wilbert A.: See—
Davis, Ralph L., 261,568, Cl. D28-77.000.

Phillips Petroleum Co.: See—
Smith, Ernest L., 261,486, Cl. D9-452.000.

Poisson, Norman D., to Gillette Company, The. Razor handle. 261,564, 10-27-81, Cl. D28-48.000.

Polaroid Corporation: See—
Conner, James M.; and Ryan, James M., 261,523, Cl. D16-42.000.

Polivka, John: See—
Graham, Elwood M.; and Polivka, John, 261,472, Cl. D7-155.000.

Pool, Daniel L. Combined holder and dispenser for collapsible tubes. 261,453, 10-27-81, Cl. D6-87.000.

Raytheon Company: See—
Haubert, Carol A., 261,481, Cl. D9-341.000.
Haubert, Carol A., 261,482, Cl. D9-341.000.
Haubert, Carol A., 261,484, Cl. D9-341.000.
Haubert, Carol A., 261,485, Cl. D9-341.000.

Rekart, Robert: See—
Palka, James J.; and Rekart, Robert, 261,557, Cl. D26-87.000.
Palka, James J.; and Rekart, Robert, 261,558, Cl. D26-87.000.
Palka, James J.; and Rekart, Robert, 261,559, Cl. D26-87.000.
Palka, James J.; and Rekart, Robert, 261,560, Cl. D26-87.000.

Remy, Raymond M., to Goodyear Tire & Rubber Company, The. Tire. 261,492, 10-27-81, Cl. D12-143.000.

Remy, Raymond M., to Goodyear Tire & Rubber Company, The. Tire. 261,496, 10-27-81, Cl. D12-147.000.

Rips, Irving, to Younger Manufacturing Company. Eye glass frame. 261,525, 10-27-81, Cl. D16-115.000.

Robbins, Michael B.: See—
Cottrell, Edward D.; and Robbins, Michael B., 261,516, Cl. D15-92.000.

Rommag P. Worwag & Co.: See—
Hug, Niklaus, 261,473, Cl. D32-18.000.

Ryan, James M.: See—
Conner, James M.; and Ryan, James M., 261,523, Cl. D16-42.000.

Ryder, Francis E.: See—
Thomas, Michael D.; and Ryder, Francis E., 261,550, Cl. D24-9.000.

Ryder International Corporation: See—
Thomas, Michael D.; and Ryder, Francis E., 261,550, Cl. D24-9.000.

Saab-Scania Aktiebolag: See—
Envall, Bjorn E. A., 261,502, Cl. D12-211.000.

Sakai, Masaaki; and Hirose, Kunio, to Canon Kabushiki Kaisha. Desk top electronic calculator. 261,528, 10-27-81, Cl. D18-7.000.

Sauber, Charles J. Storage trunk for a pickup truck. 261,499, 10-27-81, Cl. D12-157.000.

Schaefer, Harold W.; and Wiese, Martin E., to National Union Electric Corporation. Pressure spray carpet cleaner. 261,515, 10-27-81, Cl. D32-23.000.

Schenker, Michael, to Coilhose Pneumatics, Inc. Combined air muffler and filter. 261,501, 10-27-81, Cl. D12-194.000.

Schmohl, Michael W., to Uniroyal GmbH. Shoe. 261,446, 10-27-81, Cl. D2-309.000.

Shaffer, Frank E. Cable or rivet cutter. 261,477, 10-27-81, Cl. D8-98.000.

Shinkai, Hiroshi: See—
Kando, Masahiro; and Shinkai, Hiroshi, 261,524, Cl. D16-44.000.

Shu, David F., to TDS, Inc. C.A.T.V. Signal splitter. 261,503, 10-27-81, Cl. D13-11.000.

Sides, James E. Aerial toy. 261,538, 10-27-81, Cl. D21-86.000.

Smalley, Ronald W. Fish holding tool. 261,546, 10-27-81, Cl. D22-31.000.

Smith, Allan B. Combination beach towel-carry bag. 261,464, 10-27-81, Cl. D6-265.000.

Smith, Ernest H. Shillelagh or similar article. 261,539, 10-27-81, Cl. D21-211.000.

Smith, Ernest L., to Phillips Petroleum Co. Container closure or similar article. 261,486, 10-27-81, Cl. D9-452.000.

Snellman, Donald L. Paper collator for use with office copying machines. 261,522, 10-27-81, Cl. D16-32.000.

Stegmaier, Sigurd: See—
Berman, James S.; and Stegmaier, Sigurd, 261,456, Cl. D6-157.000.
Berman, James S.; and Stegmaier, Sigurd, 261,457, Cl. D6-157.000.
Berman, James S.; and Stegmaier, Sigurd, 261,458, Cl. D6-157.000.
Berman, James S.; and Stegmaier, Sigurd, 261,459, Cl. D6-157.000.
Berman, James S.; and Stegmaier, Sigurd, 261,460, Cl. D6-157.000.
Berman, James S.; and Stegmaier, Sigurd, 261,461, Cl. D6-162.000.
Berman, James S.; and Stegmaier, Sigurd, 261,462, Cl. D6-162.000.

Sunbeam Corporation: See—
Lee, Ernest, 261,563, Cl. D28-13.000.
Madl, Alfred W., 261,567, Cl. D28-67.000.

Suzuki, Akira, to Takagi, Kazusuke, a part interest. Lamp. 261,562, 10-27-81, Cl. D26-111.000.

Suzuki, Norio; and Kojima, Hiroshi, to Bridgestone Tire Company, Limited. Vehicle tire. 261,494, 10-27-81, Cl. D12-146.000.

Tabata, Toshinori, to Tomy Kogyo Co., Inc. Wrist-wearable time teaching instrument. 261,532, 10-27-81, Cl. D19-64.000.

Takagi, Kazusuke: See—
Suzuki, Akira, 261,562, Cl. D26-111.000.

Takahashi, Yoichi; Yamamura, Mashimichi; Harada, Toshio; and Inoue, Shigefumi, to Matsushita Electric Industrial Co., Ltd. Microwave oven. 261,468, 10-27-81, Cl. D7-128.000.

Tawil, Abraham I., to H.I.T. Industries Ltd. Combined backgammon game and carrying case. 261,535, 10-27-81, Cl. D21-15.000.

TDS, Inc.: See—
Shu, David F., 261,503, Cl. D13-11.000.

Thomas, Michael D.; and Ryder, Francis E., to Ryder International Corporation. Contact lens sterilizer unit. 261,550, 10-27-81, Cl. D24-9.000.

Thomas, Wesley L. Telephone. 261,507, 10-27-81, Cl. D14-53.000.

Thorpe, Donald, to Warner-Lambert Company. Combined display and packaging container for a shaving unit. 261,483, 10-27-81, Cl. D9-342.000.

Tomy Kogyo Co., Inc.: See—
Mayuzumi, Masaki; and Yoshimura, Masaaki, 261,534, Cl. D21-10.000.

Tabata, Toshinori, 261,532, Cl. D19-64.000.

Uniroyal GmbH: See—
Schmohl, Michael W., 261,446, Cl. D2-309.000.

Vedder, Gene D.: See—
Lindsay, James R.; and Vedder, Gene D., 261,488, Cl. D10-78.000.

Vijo, Matti. Workman's vest. 261,447, 10-27-81, Cl. D2-190.000.

Warner-Lambert Company: See—
Thorpe, Donald, 261,483, Cl. D9-342.000.

Waterman S.A.: See—
Delcroix, Guy, 261,531, Cl. D19-4.000.

Wiese, Martin E.: See—
Schaefer, Harold W.; and Wiese, Martin E., 261,515, Cl. D32-23.000.

Wilkinson Sword Ltd.: See—
Grange, Kenneth H., 261,565, Cl. D28-48.000.

Wolf, Alvan H.: See—
Landay, David L.; and Wolf, Alvan H., 261,542, Cl. D21-226.000.

Wolfe, Raymond. Wood box. 261,475, 10-27-81, Cl. D7-212.000.

Yamamura, Mashimichi: See—
Takahashi, Yoichi; Yamamura, Mashimichi; Harada, Toshio; and Inoue, Shigefumi, 261,468, Cl. D7-128.000.

Yoshimura, Masaaki: See—
Mayuzumi, Masaki; and Yoshimura, Masaaki, 261,534, Cl. D21-10.000.

Younger Manufacturing Company: See—
Rips, Irving, 261,525, Cl. D16-115.000.

Yurkovich, Charles G., to Goodyear Tire & Rubber Company, The. Tire tread and buttress. 261,495, 10-27-81, Cl. D12-146.000.

Zero Corporation: See—
Hollingsworth, Gene C., 261,504, Cl. D13-24.000.

LIST OF PLANT PATENTEES

Holtkamp, Reinhold. African violet plant. 4,782, 10-27-81, Cl. 69.000.

Meek, Jack M., to Yoder Brothers, Inc. Carnation plant. 4,783, 10-27-81, Cl. 72.000.

Mikkelsen, James C.; and Van den Berg, Cornelis P., to Mikkelsen Inc. Begonia plant. 4,781, 10-27-81, Cl. 68.000.

Mikkelsen, James C.; and Van den Berg, Cornelis P., to Mikkelsen Inc. Begonia plant. 4,781, 10-27-81, Cl. 68.000.

Mikkelsen, James C.; and Van den Berg, Cornelis P., to Mikkelsen Inc. Begonia plant. 4,781, 10-27-81, Cl. 68.000.

Mikkelsen, James C.; and Van den Berg, Cornelis P., to Mikkelsen Inc. Begonia plant. 4,781, 10-27-81, Cl. 68.000.

Mikkelsen, James C.; and Van den Berg, Cornelis P., to Mikkelsen Inc. Begonia plant. 4,781, 10-27-81, Cl. 68.000.

Mikkelsen, James C.; and Van den Berg, Cornelis P., to Mikkelsen Inc. Begonia plant. 4,781, 10-27-81, Cl. 68.000.

Mikkelsen, James C.; and Van den Berg, Cornelis P., to Mikkelsen Inc. Begonia plant. 4,781, 10-27-81, Cl. 68.000.

Mikkelsen, James C.; and Van den Berg, Cornelis P., to Mikkelsen Inc. Begonia plant. 4,781, 10-27-81, Cl. 68.000.

CLASSIFICATION OF PATENTS

ISSUED OCTOBER 27, 1981

NOTE.—First number, class; second number, subclass; third number, patent number

CLASS 2	884	4,296,550	CLASS 60	57.26	4,296,654	CLASS 119	340	4,296,775
114	4,296,497	CLASS 30	39.23	4,296,599	405	4,296,655	351	4,296,776
115	4,296,498	98	39.28 R	4,296,600	429	4,296,656	433	4,296,778
239	4,296,499	183		4,296,601	CLASS 82			
		381		4,296,602	1 C	4,296,657	CLASS 122	
1.7	4,296,500	CLASS 33	528	4,296,603	30	4,296,658	22	4,296,711
13	4,296,501	138		4,296,604	CLASS 83		32	4,296,712
		CLASS 34	559	4,296,605	54	4,296,659	150	4,296,781
144.1	4,296,502	CLASS 36	754	4,296,606	100	4,296,660	CLASS 123	
228	4,296,503	1		4,296,607	100	4,296,661	53 B	4,296,714
253	4,296,504	107		4,296,608	796	4,296,662	90.15	4,296,715
324	4,296,505	CLASS 36	55	4,296,610	880	4,296,662	195 A	4,296,717
480	4,296,506	7.8		4,296,611	CLASS 84		195 C	4,296,716
524	4,296,507	50		4,296,612	1.01	4,296,663	198 D	4,296,718
540	4,296,508	50		4,296,609	1.03	4,296,664	198 F	4,296,719
		136		4,296,613	1.26	4,296,665	309	4,296,720
81 R	4,296,509	CLASS 38	515	4,296,613	345	4,296,666	407	4,296,721
450	4,296,510	77.81		4,296,610	383 R	4,296,668	492	4,296,722
		CLASS 40	104	4,297,118	CLASS 89		510	4,296,723
406	4,297,102	158 R	141	4,297,119	1.816	4,296,669	568	4,296,724
412	4,297,098	438	281	4,297,120	43 R	4,296,670	24 R	4,296,725
484	4,297,099	518	348	4,297,121	CLASS 91		25 B	4,296,726
527	4,297,100	CLASS 42	48	4,296,614	5	4,296,671	116 A	4,296,727
531	4,297,101	1 C		4,296,614	271	4,296,672	376	4,296,728
534	4,297,103	1 T		4,296,615	375 A	4,296,673	421	4,296,729
310 A	4,296,511	71 R		4,296,616	391 R	4,296,674	424	4,296,730
27 E	4,296,512	CLASS 44	63	4,296,617	396	4,296,675	426	4,296,731
12	4,296,513	1 SR	358	4,296,618	417 R	4,296,676	428	4,296,732
142 LC	4,296,515	51	451	4,296,619	510	4,296,677	431	4,296,733
142 R	4,296,514	56		4,297,122	CLASS 92		438	4,296,734
		66		4,297,123	13.1	4,296,678		
71.7	4,296,516	CLASS 46	58	4,297,123	52	4,296,679	443	4,296,738
93 R	4,296,517	163	66	4,297,124	98 D	4,296,680	444	4,296,739
110	4,296,518	CLASS 47	77	4,297,125	122	4,296,681	448	4,296,740
184	4,296,519	20	78	4,297,126	CLASS 99		449	4,296,741
250.32	4,296,520	73	88	4,297,127	426	4,296,682	450	4,296,742
		CLASS 49	92	4,297,128	53	4,296,683	60	4,297,146
250.36	4,296,521	360	93	4,297,129	292	4,296,684	CLASS 127	
415 R	4,296,523	CLASS 51	119	4,297,130	CLASS 102		30	4,296,743
		32		4,296,620	218	4,296,688	80 C	4,296,744
150	4,296,524	170 TL	100	4,296,621	260	4,296,689	80 G	4,296,745
174	4,296,525	CLASS 52	208	4,296,622	387	4,296,685	156	4,296,746
21	4,296,526	6	227	4,296,623	427	4,296,686	201.15	4,296,747
218	4,296,527	27	308	4,296,624	518	4,296,687	220	4,296,748
239	4,296,528	60	345	4,296,625	CLASS 104		276	4,296,749
255	4,296,528	96	392	4,296,626	91	4,296,690	283	4,296,750
		187	15 R	4,296,627	370	4,296,691	287	4,296,751
230 B	4,297,104	200	28	4,296,628	397	4,296,692	325	4,296,752
230 HC	4,297,106	218	116	4,296,629	370	4,296,691	635	4,296,753
230 R	4,297,105	239	304 C	4,296,630	397	4,296,692	660	4,296,754
30.5 P	4,296,529	281	356	4,296,631	CLASS 106		694	4,296,755
200	4,296,531	520	362 AR	4,296,632	15.05	4,297,137	705	4,296,755
206 R	4,296,532	590		4,296,633	18.18	4,297,138	716	4,296,756
216	4,296,533	520		4,296,635	197 C	4,297,144	721	4,296,757
270	4,296,534	717		4,296,636	308 Q	4,297,145	728	4,296,758
295	4,296,530	742		4,296,637	CLASS 108		766	4,296,759
		745		4,296,638	28	4,296,693	788	4,296,760
257	4,296,535	788		4,296,587	116	4,296,694	359	4,296,762
1.3	4,296,536	CLASS 53	86	4,296,588	CLASS 111		7	4,296,763
116 AD	4,296,537	300	80	4,296,589	34	4,296,695	53	4,296,764
156.4 R	4,296,538	531	366	4,296,590	70	4,296,696	73	4,296,766
157.3 A	4,296,539	CLASS 55	688	4,296,644	109	4,296,697	CLASS 134	
460	4,296,540	92		4,296,645	110	4,296,698	3	4,297,148
568	4,296,541	195		4,296,646	121.15	4,296,699	7	4,297,147
574	4,296,542	213		4,296,647	153	4,296,700	15	4,296,767
596	4,296,543	299		4,296,648	168	4,296,701	47	4,296,768
598	4,296,544	302		4,296,649	258	4,296,702	68	4,296,769
602 R	4,296,545	319		4,296,650	310	4,296,703		
730	4,296,546	389		4,296,651	CLASS 114		248	4,297,521
766	4,296,547	CLASS 56	10.3	4,296,591	103	4,296,704	256	4,297,391
871	4,296,548	14.4		4,296,592	219	4,296,705	62	4,296,770
874	4,296,549	98		4,296,593	294	4,296,706	110	4,296,771
		336		4,296,594	58 A	4,296,707	269.5	4,296,772
		341		4,296,595	CLASS 116		312	4,296,773
205	4,296,597	10.3		4,296,596	103	4,296,704	322	4,296,774
284	4,296,598	14.4		4,296,592	219	4,296,705		
		98		4,296,593	294	4,296,706	62	4,296,770
		336		4,296,594	58 A	4,296,707	110	4,296,771
		341		4,296,595	233	4,296,708	269.5	4,296,772
		205		4,296,596	CLASS 118		312	4,296,773
		284		4,296,598	58 A	4,296,707	322	4,296,774
		CLASS 57	206	4,297,136	CLASS 118		322	4,296,774
		3.46 R		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,774
		CLASS 81		4,296,653	CLASS 118		322	4,296,

CLASS 173	67	4,297,179	CLASS 227	518	4,297,249	81 R	4,296,934	86	4,297,614				
147	4,296,819	78	4,297,180	30	4,296,881	545	4,297,250	111.21	4,297,615				
CLASS 174	98	4,297,182	CLASS 233	606	4,297,252	88	4,296,937	179	4,297,616				
27	4,297,523	117	4,297,183	CLASS 254	380	4,296,916	135	4,296,938	326	4,297,617			
36	4,297,522	129.4	4,297,184	CLASS 235	400	4,296,917	212	4,296,939	371	4,297,618			
48	4,297,524	159.15	4,297,185	50 R	4,297,566	278	4,296,940	381	4,297,619				
58	4,297,525	165	4,297,186	92 PB	4,297,567	423 B	4,296,941	389	4,297,620				
102 R	4,297,526	181 R	4,297,187	435	4,297,568	803	4,296,942	397	4,297,621				
52	4,296,820	192 E	4,297,188	443	4,297,569	804	4,296,943	254	4,297,622				
87	4,296,821	192 SP	4,297,189	493	4,297,570	CLASS 260	4,296,944	410	4,297,623				
249	4,296,822	195 G	4,297,193	CLASS 237	17.3	4,297,253	CLASS 280	4,296,939	594	4,297,624			
308	4,296,823	195 S	4,297,192	59	4,296,883	18 EP	4,297,254	696	4,297,625				
340	4,296,824	257	4,297,194	CLASS 238	29.4 UA	4,297,256	45	4,296,946	778	4,297,626			
410	4,296,825	290 F	4,297,195	2	4,296,884	29.6 H	4,297,257	798	4,297,627				
1 PC	4,297,529	296	4,297,196	CLASS 239	29.6 MN	4,297,258	27.5	4,296,947	798	4,297,628			
1 SB	4,297,528	297 W	4,297,197	CLASS 240	29.6 NR	4,297,259	4,296,948	CLASS 320	7	4,297,629			
1 VC	4,297,527	299 R	4,297,199	1	4,296,885	29.7 H	4,297,260	CLASS 285	35	4,297,630			
2 C	4,297,530	304	4,296,857	264	4,296,886	29.7 RP	4,297,261	18	4,296,949	64	4,297,631		
16 AA	4,297,531	397.5	4,296,887	403	4,296,888	31.6	4,297,262	45	4,296,950	CLASS 324	51	4,297,632	
18 AB	4,297,532	53	4,296,857	CLASS 242	33.4 R	4,297,264	95	4,296,951	98	4,296,952	61 R	4,297,634	
84 VF	4,297,533	150	4,296,858	18.1	4,296,889	33.6 SB	4,297,265	302	4,296,953	331	4,296,954	156	4,297,635
90 D	4,297,534	219	4,296,859	71.8	4,296,890	42.14	4,297,266	381	4,296,955	381	4,296,955	262	4,297,636
156 R	4,297,535	386	4,296,860	110	4,296,891	42.53	4,297,267	CLASS 290	40 R	4,297,589	410	4,297,638	
170 D	4,297,536	428	4,296,861	CLASS 244	2	4,296,892	45.8 N	4,297,268	CLASS 292	169.18	4,296,956	458	4,297,640
180	4,297,537	439	4,296,862	3.23	4,296,893	104	4,297,270	45.9 QB	264	4,296,957	CLASS 328	15	4,297,641
189 D	4,297,538	504	4,296,863	3.27	4,296,894	107	4,297,271	112 B	27 H	4,296,958	CLASS 330	9	4,297,642
CLASS 180	10	4,297,200	CLASS 208	3.29	4,296,895	112 B	4,297,272	112 R	143	4,296,959	178	4,297,643	
24	4,296,826	11 R	4,297,201	12.4	4,296,896	112.5 R	4,297,273	112.5 R	144	4,296,960	280	4,297,644	
CLASS 181	54	4,297,202	CLASS 181	111	4,296,897	143	4,297,274	143	167	4,296,961	288	4,297,645	
107	4,296,827	74	4,297,203	115	4,296,898	245.5	4,297,275	CLASS 296	216	4,296,962	307	4,297,646	
121	4,296,828	95	4,297,204	207	4,296,899	314.5	4,297,280	170	216	4,296,963	337	4,297,647	
129	4,296,829	138	4,297,205	219	4,296,900	326.2	4,297,281	CLASS 297	217	4,296,964	345	4,297,648	
208	4,296,830	254 R	4,297,206	CLASS 246	167 R	4,296,901	346.22	CLASS 299	170	4,296,965	1 R	4,297,649	
224	4,296,831	9	4,297,207	CLASS 248	102	4,296,902	346.3	170	218	4,296,966	2	4,297,649	
255	4,296,832	144	4,296,864	162.1	4,296,903	162.1	4,296,903	218	284	4,296,967	11	4,297,650	
CLASS 182	216	4,296,865	CLASS 210	218.4	4,296,904	237	4,296,905	284	369	4,296,968	94.5 H	4,297,651	
2	4,296,833	94	4,297,208	44.8	4,296,905	280.1	4,296,906	369	451	4,296,969	94.5 S	4,297,652	
155	4,296,834	107	4,297,209	573	4,296,907	573	4,296,907	451	CLASS 299	410.9 R	108 D	4,297,654	
184	4,296,835	136	4,297,210	CLASS 249	58	4,296,908	410.9 R	2	67	4,296,968	116 R	4,297,655	
193	4,296,836	168	4,297,211	CLASS 250	94	4,296,909	428.5	2	115	4,296,969	135	4,297,656	
CLASS 184	195.1	4,297,212	CLASS 184	201	4,297,571	448 B	4,297,292	CLASS 303	115	4,296,971	176	4,297,657	
15 R	4,296,837	386	4,297,215	203 R	4,297,572	453 PH	4,297,293	CLASS 307	119	4,296,972	194	4,297,659	
106	4,296,838	613	4,297,216	231 SE	4,297,573	455 A	4,297,294	224 C	247 R	4,297,590	204	4,297,661	
8	4,296,840	621	4,297,217	253	4,297,574	459 A	4,297,295	252 C	268	4,297,591	252	4,297,662	
61	4,296,842	661	4,297,218	265	4,297,575	465 D	4,297,296	268	279	4,297,592	20	4,297,663	
73.38	4,296,841	690	4,297,219	336	4,297,576	502 R	4,297,297	315	315	4,297,593	60	4,297,665	
73.43	4,296,843	748	4,297,220	343	4,297,577	502.5	4,297,298	355	426	4,297,594	CLASS 336	176	4,297,666
341	4,296,845	754	4,297,221	CLASS 251	4,297,578	544 C	4,297,300	426	555	4,297,595	CLASS 337	163	4,297,667
378	4,296,839	755	4,297,222	368	4,297,579	544 K	4,297,301	583	583	4,297,596	252	4,297,668	
CLASS 192	4 A	4,296,846	4,297,223	391	4,297,580	CLASS 261	4,297,302	4 A	4 A	4,296,973	407	4,297,669	
4 A	4,296,847	779	4,297,225	445 T	4,297,581	CLASS 264	4,297,303	6 C	6 R	4,296,974	195	4,297,670	
35	4,296,848	131	4,296,866	453	4,297,582	0.5	4,297,304	19	37	4,296,975	200	4,297,671	
61	4,296,849	CLASS 211	4,296,867	483	4,297,583	CLASS 266	4,297,305	37	174	4,296,976	48	4,296,980	
64	4,296,850	CLASS 212	4,296,867	560	4,297,584	3 R	4,297,306	426	426	4,296,977	89 C	4,296,981	
84 C	4,296,851	CLASS 213	4,296,868	561	4,297,585	22	4,297,307	555	555	4,296,978	95 D	4,296,982	
104 B	4,296,852	50	4,296,868	563	4,297,586	23	4,297,308	583	583	4,296,979	97 R	4,296,983	
106.1	4,296,854	CLASS 198	4,296,868	577	4,297,587	29.5	4,297,309	4 A	4 A	4,296,980	99 R	4,296,984	
CLASS 198	502	4,296,855	CLASS 219	CLASS 251	4,297,588	46.6	4,297,310	6 C	6 R	4,296,981	128	4,296,985	
514	4,296,856	10.55 R	4,297,557	28	4,296,910	56	4,297,311	19	37	4,296,982	176 MP	4,296,986	
CLASS 200	5 B	4,297,540	4,297,558	57	4,296,911	83	4,297,312	37	174	4,296,983	186 M	4,296,987	
5 B	4,297,541	121 LB	4,297,559	65	4,296,912	109	4,297,313	48	48	4,296,984	275 B	4,296,988	
5 E	4,297,542	130.01	4,297,560	76	4,296,913	134	4,297,314	89 C	89 C	4,296,985	328	4,297,678	
6 A	4,297,543	137.63	4,297,561	149.2	4,296,914	273	4,297,315	95 D	95 D	4,296,986	347 AD	4,297,679	
18	4,297,544	216	4,297,562	174	4,296,915	320	4,297,316	97 R	97 R	4,296,987	366 F	4,297,680	
34	4,297,545	275	4,297,563	CLASS 252	8.55 D	4,297,226	CLASS 266	99 R	99 R	4,296,988	384 E	4,297,681	
38 R	4,297,546	367	4,297,564	111	4,297,227	216	4,296,919	128	128	4,296,989	539	4,297,682	
48 KB	Re.30.784	4,297,547	4,297,565	216	4,297,228	270	4,296,920	176 MP	176 MP	4,296,990	557	4,297,683	
61.08	4,297,548	CLASS 220	4,296,869	270	4,297,229	CLASS 269	4,296,921	186 M	186 M	4,296,991	575	4,297,684	
61.27	4,297,549	3	4,296,870	92	4,297,230	211	4,296,922	275 B	275 B	4,296,992	75	4,297,685	
61.89	4,297,550	306	4,296,871	109	4,297,231	85	4,296,923	328	328	4,296,993	23	4,297,672	
67 B	4,297,551	CLASS 221	4,296,871	182.1	4,297,232	117	4,296,924	347 AD	347 AD	4,297,679	27 NA	4,297,673	
83 P	4,297,552	301.24	4,297,233	187 R	4,297,233	117	4,296,924	366 F	366 F	4,297,680	63	4,297,674	
145	4,297,553	316	4,297,234	259.5	4,297,234	117	4,296,924	384 E	384 E	4,297,681	146.3 AG	4,297,676	
153 G	4,297,555	389 A	4,297,235	301.24	4,297,235	117	4,296,924	539	539	4,297,682	328	4,297,678	
153 SC	4,297,554	389 R	4,297,236	316	4,297,236	117	4,296,924	557	557	4,297,683	347 AD	4,297,679	
330	4,297,556	408	4,297,237	412	4,297,237	117	4,296,924	75	75	4,297,684	366 F	4,297,680	
CLASS 203	19	4,297,172	4,297,238	431 R	4,297,238	117	4,296,924	384 E	384 E	4,297,681	384 E	4,297,682	
CLASS 204	1 T	4,297,173	4,297,239	435	4,297,239	117	4,296,924	539	539	4,297,682	539	4,297,683	
1.5	4,297,174	91	4,296,876	445 Z	4,297,240	117	4,296,924	557	557	4,297,683	557	4,297,684	
15	4,297,175	99	4,296,877	455 Z	4,297,241	117	4,296,924	75	75	4,297,684	75	4,297,685	
37 R	4,297,176	32 A	4,296,878	460	4,297,242	117	4,296,924	75	75	4,297,685	75	4,297,686	
43 N	4,297,177	42.45 R	4,296,879	465	4,297								

604	4,297,686	133	4,297,029	11	4,297,051	395	4,297,336	240	4,297,408	4,297,459		
626	4,297,687		CLASS 356		CLASS 405		CLASS 424	247	4,297,409	CLASS 526		
630	4,297,688							283	4,297,410			
632	4,297,689	5	4,297,030	16	4,297,052	1	4,297,337	310	4,297,411	98	4,297,460	
690	4,297,690	247	4,297,031	121	4,297,053	9	4,297,338	347	4,297,410	100	4,297,461	
715	4,297,692	366	4,297,032	168	4,297,054	19	4,297,339	370	4,297,412	125	4,297,462	
723	4,297,691	374	4,297,033	184	4,297,055	70	4,297,340	394	4,297,413	128	4,297,463	
744	4,297,693	394	4,297,034	232	4,297,056	80	4,297,341	400	4,297,414	141	4,297,465	
750	4,297,694	402	4,297,035	303	4,297,057	84	4,297,342	410	4,297,417	181	4,297,464	
752	4,297,695		CLASS 357		CLASS 407	85	4,297,343	516	4,297,415	218	4,297,466	
785	4,297,696					101	4,297,344	576	4,297,416	259	4,297,467	
813	4,297,697	15	4,297,717	113	4,297,058	114	4,297,345	595	4,297,418	276	4,297,468	
870.32	4,297,698	22	4,297,718		CLASS 408	177	4,297,346			287	4,297,469	
		23	4,297,719	202	4,297,059	180	4,297,347	CLASS 429		304	4,297,470	
CLASS 343		30	4,297,720				4,297,348	44	4,297,419	328	4,297,471	
5 NA	4,297,699	59	4,297,721		CLASS 409	184	4,297,349	217	4,297,420	CLASS 528		
6.5 LC	4,297,701	74	4,297,722	86	4,297,060	238	4,297,350	225	4,297,421	84	4,297,472	
6.5 R	4,297,700		CLASS 358	131	4,297,061	241	4,297,351			144	4,297,473	
7 PF	4,297,702					246	4,297,352	CLASS 430		170	4,297,474	
7.3	4,297,703	60	4,297,723		CLASS 410	247	4,297,353	54	4,297,422	271	4,297,475	
113 R	4,297,704	93	4,297,724	37	4,297,062	248.51	4,297,354		4,297,423	287	Re.30,783	
725	4,297,707	125	4,297,725		CLASS 411	248.54	4,297,355	58	4,297,424	300	4,297,476	
754	4,297,708	254	4,297,726			248.57	4,297,356		4,297,425	323	4,297,477	
	4,297,709	261	4,297,727	199	4,297,063	251	4,297,357	59	4,297,426	336	4,297,478	
756	4,297,710		CLASS 360	470	4,297,064	256	4,297,358	108	4,297,427		4,297,479	
771	4,297,705	36	4,297,728		CLASS 414	263	4,297,359	169	4,297,428	346	4,297,480	
794	4,297,711	40	4,297,729	24.5	4,297,065		4,297,360	204	4,297,429	392	4,297,481	
		66	4,297,730	43	4,297,066		4,297,361	215	4,297,430	405	4,297,482	
CLASS 346		70	4,297,731	114	4,297,067		4,297,362		4,297,431	423	4,297,484	
75	4,297,712	72.1	4,297,732	458	4,297,068		4,297,363		4,297,432	500	4,297,483	
108	4,297,713	77	4,297,733	462	4,297,069	267	4,297,364	270	4,297,433	CLASS 536		
139 C	4,297,714	78	4,297,734	497	4,297,070	270	4,297,365		4,297,434	10	4,297,485	
150	4,297,715	104	4,297,735	542	4,297,071	274	4,297,366		4,297,435	17 R	4,297,486	
153.1	4,297,716	109	4,297,736	684.3	4,297,072	283	4,297,367	310	4,297,436			
		135	4,297,737	704	4,297,073	285	4,297,368	376	4,297,437	CLASS 542		
CLASS 350			CLASS 361	723	4,297,074		4,297,369		4,297,438	412	4,297,487	
3.73	4,296,994	42	4,297,738		CLASS 416	298	4,297,370		4,297,439	CLASS 544		
96.15	4,296,995	55	4,297,739	14	4,297,075	304	4,297,371	505	4,297,440	21	4,297,488	
96.20	4,296,996	67	4,297,740	37	4,297,076	315	4,297,372	543	4,297,441	27	4,297,489	
	4,296,997	93	4,297,741	97 R	4,297,077	322	4,297,373			55	4,297,490	
	4,296,998	154	4,297,742	134 A	4,297,078	364	4,297,374	CLASS 425	10	4,297,491	105	4,297,491
96.21	4,296,999		CLASS 364	140	4,297,079	84	4,297,091	202	4,297,094	211	4,297,492	
96.24	4,297,000			141	4,297,080	133.1	4,297,092			241	4,297,493	
129	4,297,001	200	Re.30,785		CLASS 417		CLASS 426	59	4,297,095	267	4,297,494	
255	4,297,002		4,297,743	2	4,297,081	62	4,297,375			330	4,297,495	
292	4,297,003	703	4,297,744	51	4,297,082	94	4,297,376	CLASS 435		332	4,297,496	
336	4,297,004		CLASS 366	53	4,297,083	438	4,297,377	128	4,297,096	384	4,297,497	
357	4,297,005			179	4,297,084	532	4,297,378	CLASS 440		CLASS 546		
	4,297,006	77	4,297,036	222	4,297,085	565	4,297,379	59	4,297,097	116	4,297,498	
432	4,297,007	114	4,297,037	271	4,297,086	597	4,297,380	CLASS 474		CLASS 556		
CLASS 351		206	4,297,038	378	4,297,087	615	4,297,381	262	4,296,640	465	4,297,499	
177	4,297,008		CLASS 367		4,297,088	656	4,297,382			466	4,297,500	
CLASS 352		66	4,297,745	437	4,297,089		CLASS 427	CLASS 501		CLASS 560		
86	4,297,009		CLASS 376		CLASS 418	1	4,297,383	2	4,297,139	24	4,297,501	
CLASS 353		103	4,297,165	61 A	4,297,090	14.1	4,297,384	67	4,297,141	35	4,297,502	
122	4,297,010	194	4,297,166		CLASS 422	27	4,297,385	77	4,297,142	42	4,297,503	
		273	4,297,167				4,297,386	103	4,297,143	119	4,297,504	
CLASS 354		418	4,297,168	1	4,297,316	38	4,297,387			219	4,297,505	
23 D	4,297,011		4,297,169	16	4,297,317	47	4,297,388	CLASS 521		246	4,297,506	
	4,297,012	440	4,297,171	46	4,297,318	58	4,297,389	107	4,297,442	CLASS 562		
	4,297,013	442	4,297,170	114	4,297,319	64	4,297,390	129	4,297,443	416	4,297,507	
25	4,297,014		CLASS 400	131	4,297,321	75	4,297,392	160	4,297,444	425	4,297,508	
	4,297,015			143	4,297,322	88	4,297,393			456	4,297,509	
27	4,297,016	120	4,297,039	184	4,297,323	100	4,297,394	CLASS 525		CLASS 564		
34	4,297,017	144.2	4,297,040	208	4,297,323	127	4,297,395	52	4,297,445			
50	4,297,018	161.4	4,297,041	268	4,297,324	284	4,297,396	66	4,297,446	13	4,297,510	
171	4,297,019	223.2	4,297,042		CLASS 423	304	4,297,397	133	4,297,447	331	4,297,511	
225	4,297,020	164	4,297,043			320	4,297,398	162	4,297,448	490	4,297,512	
		473	4,297,044	122	4,297,325	385.5	4,297,399	329	4,297,449			
CLASS 355		641	4,297,045	126	4,297,326	389	4,297,400	333	4,297,450	CLASS 568		
					4,297,327			366	4,297,451	43	4,297,513	
3 R	4,297,021		CLASS 403	213.2	4,297,328		CLASS 428	367	4,297,452	421	4,297,514	
	4,297,022	46	4,297,046	228	4,297,329	1	4,297,401	402	4,297,453	329	4,297,515	
8	4,297,023	138	4,297,047	232	4,297,330	35	4,297,402	432	4,297,454	330	4,297,516	
14 E	4,297,024	189	4,297,048	239	4,297,331	42	4,297,403	439	4,297,455	361	4,297,517	
14 SH	4,297,025	403	4,297,049	240	4,297,332	85	4,297,404	452	4,297,456	385	4,297,518	
15	4,297,026			241	4,297,333	141	4,297,405	507	4,297,457	424	4,297,519	
27	4,297,027		CLASS 404	321 R	4,297,334	215	4,297,406		4,297,458	426	4,297,520	
41	4,297,028	10	4,297,050	328	4,297,335	224	4,297,407					

CLASSIFICATION OF DESIGNS

D2—	25	261,445		38	261,466	D11—	111	261,489		91	261,533		74	261,554
	190	261,447		74	261,467		158	261,490		10	261,534		51	261,555
	309	261,446		128	261,468	D12—	142	261,491		15	261,535		87	261,556
D3—	65	261,448		129	261,469		143	261,492	D15—	5	261,513			
D6—	23	261,449			261,470			261,493		92	261,516			261,558
	26	261,450			261,471		146	261,494		98	261,517			261,559
	63	261,451		155	261,472			261,495		118	261,518			261,560
	86	261,452		212	261,475		147	261,496		134	261,519		88	261,561
	87	261,453	D8—	30	261,476			261,497		150	261,520		111	261,562
	113	261,454		98	261,477		148	261,498		211	261,539		13	261,563
	130	261,455		344	261,478		157	261,499	D16—	32	261,522		48	261,564
	157	261,456	D9—	314	261,480		191	261,500		42	261,523			261,565
		261,457		341	261,479		194	261,501		44	261,524		64	261,566
		261,458			261,481		211	261,502		115	261,525		67	261,567
		261,459			261,482	D13—	11	261,503		21	261,526		77	261,568
		261,460			261,484		24	261,504	D17—	7	261,528		18	261,569
	162	261,461			261,485		32	261,505		3	261,549		21	261,514
		261,462		342	261,483	D14—	6	261,506		34	261,529		23	261,515
	243	261,463		452	261,486		53	261,507	D18—	4	261,531		61	261,474
	265	261,464	D10—	58	261,487		64	261,508		64	261,532	D25—	39	261,569
D7—	19	261,465		78	261,488		65	261,509	D19—	22	261,553	D34—		

CLASSIFICATION OF PLANTS

P.—	68	4,781		69	4,782		72	4,783			
-----	----	-------	--	----	-------	--	----	-------	--	--	--

GEOGRAPHICAL INDEX OF RESIDENCE OF INVENTORS

(U.S. States, Territories and Armed Forces, the Commonwealth of Puerto Rico, and the Canal Zone)

Alabama	1	Kentucky	21	Oregon	41
Alaska	2	Louisiana	22	Pennsylvania	42
American Samoa	3	Maine	23	Puerto Rico	43
Arizona	4	Maryland	24	Rhode Island	44
Arkansas	5	Massachusetts	25	South Carolina	45
California	6	Michigan	26	South Dakota	46
Canal Zone	7	Minnesota	27	Tennessee	47
Colorado	8	Mississippi	28	Texas	48
Connecticut	9	Missouri	29	Utah	49
Delaware	10	Montana	30	Vermont	50
District of Columbia	11	Nebraska	31	Virginia	51
Florida	12	Nevada	32	Virgin Islands	52
Georgia	13	New Hampshire	33	Washington	53
Guam	14	New Jersey	34	West Virginia	54
Hawaii	15	New Mexico	35	Wisconsin	55
Idaho	16	New York	36	Wyoming	56
Illinois	17	North Carolina	37	U.S. Air Force	57
Indiana	18	North Dakota	38	U.S. Army	58
Iowa	19	Ohio	39	U.S. Navy	59
Kansas	20	Oklahoma	40		

(First number in listing denotes location according to above key. Refer to patent number in body of the Official Gazette to obtain details as to inventor name, location, etc.)

PATENTS

6 :	4,296,654	4,296,927	4,297,704	4,296,861	4,296,665	4,296,670
	4,296,766	4,296,955	4,297,738	4,297,095	4,296,671	4,296,733
01 :	4,296,669	4,296,968	4,296,634	4,297,309	4,296,674	4,296,737
	4,296,820	4,296,970	4,296,756	4,297,728	4,296,784	4,296,785
	4,297,643	4,296,994	4,296,797	4,297,055	4,296,794	4,296,837
	4,297,705	4,297,000	4,296,799	4,297,521	4,296,805	4,296,838
02 :	4,297,056	4,297,032	4,297,011	4,297,590	4,296,845	4,297,007
	4,297,056	4,297,032	4,297,025	Re.30,784	4,296,846	4,297,016
04 :	4,296,731	4,297,035	4,297,201	4,296,504	4,296,960	4,297,017
	4,297,542	4,297,043	4,297,291	4,296,519	4,297,091	4,297,042
	4,297,593	4,297,051	4,297,712	4,296,552	4,297,242	4,297,050
	4,297,618	4,297,054	4,297,712	4,296,557	4,297,277	4,297,122
	4,297,621	4,297,060	4,296,564	4,296,569	4,297,443	4,297,135
	4,297,646	4,297,063	4,296,601	4,296,570	4,297,498	4,297,388
	4,297,737	4,297,068	4,296,605	4,296,583	4,297,545	4,297,431
05 :	4,297,224	4,297,076	4,296,736	4,296,595	4,297,547	4,297,494
	4,297,224	4,297,082	4,296,746	4,296,612	4,297,627	4,297,538
06 :	Re.30,785	4,297,084	4,296,764	4,296,637	4,297,726	4,297,588
	4,296,508	4,297,114	4,297,006	4,297,031	4,296,656	4,297,607
	4,296,509	4,297,124	4,297,080	4,296,656	4,296,643	4,297,685
	4,296,510	4,297,152	4,297,080	4,296,765	4,296,649	4,297,702
	4,296,511	4,297,155	4,297,177	4,296,779	4,296,675	4,296,554
	4,296,523	4,297,165	4,297,386	4,296,856	4,296,923	4,296,577
	4,296,542	4,297,189	4,297,419	4,296,858	4,297,657	4,296,589
	4,296,544	4,297,208	4,297,587	4,296,868	4,296,645	4,296,617
	4,296,556	4,297,229	4,297,663	4,296,869	4,297,172	4,296,641
	4,296,567	4,297,243	4,297,741	4,296,917	4,297,265	4,296,647
	4,296,568	4,297,266	4,297,039	4,296,924	4,297,561	4,296,650
	4,296,575	4,297,295	4,297,258	4,296,929	4,296,611	4,296,675
	4,296,594	4,297,297	4,297,290	4,296,949	4,296,823	4,296,681
	4,296,629	4,297,316	4,297,379	4,296,992	4,297,041	4,296,718
	4,296,677	4,297,318	4,297,454	4,297,037	4,297,045	4,296,723
	4,296,687	4,297,325	4,296,757	4,297,062	4,297,225	4,296,761
	4,296,713	4,297,435	4,296,546	4,297,064	4,296,729	4,296,817
	4,296,726	4,297,510	4,296,563	4,297,098	4,296,916	4,296,847
	4,296,728	4,297,528	4,296,572	4,297,144	4,297,072	4,296,883
	4,296,740	4,297,530	4,296,683	4,297,153	4,297,635	4,296,888
	4,296,747	4,297,539	4,296,710	4,297,200	4,296,558	4,296,914
	4,296,752	4,297,557	4,296,738	4,297,203	4,296,659	4,296,933
	4,296,763	4,297,566	4,296,874	4,297,205	4,296,682	4,296,952
	4,296,768	4,297,572	4,297,009	4,297,244	4,296,689	4,296,977
	4,296,810	4,297,584	4,297,048	4,297,341	4,296,771	4,296,977
	4,296,811	4,297,586	4,297,069	4,297,375	4,296,859	4,297,089
	4,296,814	4,297,600	4,297,075	4,297,487	4,297,079	4,297,154
	4,296,839	4,297,615	4,297,081	4,297,551	4,297,391	4,297,197
	4,296,852	4,297,620	4,297,086	4,297,552	4,297,394	4,297,209
	4,296,862	4,297,637	4,297,097	4,297,554	4,297,394	4,297,256
	4,296,876	4,297,642	4,297,348	4,297,619	4,297,481	4,297,273
	4,296,878	4,297,653	4,297,628	4,297,687	4,297,482	4,297,285
	4,296,879	4,297,670	4,297,630	4,297,742	4,297,661	4,297,303
	4,296,895	4,297,675	4,296,656	4,296,499	4,297,673	4,297,339
	4,296,898	4,297,689	4,296,576	4,296,520	4,296,502	4,297,350
	4,296,902	4,297,690	4,296,626	4,296,606	4,296,639	4,297,376
	4,296,911				4,296,668	4,297,448
	4,296,926					

GEOGRAPHICAL INDEX OF RESIDENCE OF INVENTORS

4,297,475	4,297,179	4,297,193	4,297,057	4,296,950	4,297,088
4,297,504	4,297,184	4,297,196	4,297,071	4,296,984	4,297,116
4,297,514	4,297,202	4,297,232	4,297,074	4,296,986	4,297,147
4,297,550	4,297,259	4,297,245	4,297,085	4,296,987	4,297,149
4,297,671	4,297,299	4,297,283	4,297,121	4,296,988	4,297,162
4,297,682	4,297,312	4,297,322	4,297,123	4,296,991	4,297,226
4,297,698	4,297,313	4,297,328	4,297,194	4,296,998	4,297,227
4,296,573	4,297,338	4,297,329	4,297,219	4,297,058	4,297,260
4,296,624	4,297,349	4,297,335	4,297,240	4,297,061	4,297,294
4,296,672	4,297,353	4,297,337	4,297,251	4,297,131	4,297,444
4,296,741	4,297,355	4,297,360	4,297,257	4,297,132	4,297,465
4,296,781	4,297,393	4,297,362	4,297,262	4,297,163	4,297,469
4,296,821	4,297,397	4,297,363	4,297,267	4,297,180	4,297,527
4,296,857	4,297,404	4,297,372	4,297,269	4,297,190	4,297,534
4,296,963	4,297,421	4,297,382	4,297,292	4,297,191	4,297,537
4,297,090	4,297,488	4,297,385	4,297,307	4,297,206	4,297,575
4,297,311	4,297,583	4,297,389	4,297,320	4,297,220	4,297,596
4,297,378	4,297,611	4,297,411	4,297,333	4,297,237	4,297,622
4,297,401	4,297,641	4,297,417	4,297,374	4,297,250	4,297,640
4,297,569	4,297,644	4,297,424	4,297,387	4,297,254	4,297,721
4,297,578	4,297,683	4,297,425	4,297,399	4,297,261	4,297,723
4,297,684	4,297,706	4,297,427	4,297,403	4,297,275	4,296,602
4,296,536	4,297,719	4,297,432	4,297,453	4,297,317	4,296,725
4,296,559	4,297,740	4,297,434	4,297,461	4,297,334	4,296,778
4,296,709	4,296,739	4,296,457	4,297,497	4,297,342	4,297,598
4,296,759	4,296,497	4,297,458	4,297,668	4,297,370	4,297,692
4,296,787	4,296,501	4,297,459	4,297,672	4,297,373	4,296,744
4,296,892	4,296,503	4,297,474	4,297,681	4,297,518	4,296,749
4,297,418	4,296,506	4,297,489	4,297,686	4,297,524	4,296,866
4,297,484	4,296,512	4,297,516	4,296,548	4,297,548	4,296,990
4,297,678	4,296,522	4,297,525	4,296,551	4,297,556	4,296,995
4,296,836	4,296,529	4,297,570	4,296,582	4,297,555	4,297,130
4,296,840	4,296,561	4,297,580	4,296,664	4,296,815	4,297,276
4,297,008	4,296,565	4,297,613	4,296,800	4,296,816	4,297,581
4,297,674	4,296,580	4,297,616	4,296,808	4,296,993	4,297,617
4,296,566	4,296,610	4,297,626	4,296,941	4,297,212	4,297,677
4,296,555	4,296,632	4,297,701	4,297,094	4,297,639	4,297,699
4,296,792	4,296,655	4,297,717	4,297,445	4,296,834	4,296,897
4,296,915	4,296,704	4,296,925	4,297,451	4,296,581	4,296,899
4,297,522	4,296,734	4,297,046	4,297,460	4,296,721	4,297,120
4,297,563	4,296,748	4,297,115	4,297,464	4,296,795	4,297,157
4,297,625	4,296,751	4,297,223	4,297,506	4,296,904	4,297,164
4,297,667	4,296,788	4,297,559	4,297,745	4,297,065	4,297,377
4,296,518	4,296,877	4,296,695	4,296,540	4,296,584	4,297,680
4,296,535	4,296,880	4,296,599	4,296,562	4,296,678	4,297,239
4,296,571	4,296,881	4,296,607	4,296,905	4,296,703	4,297,241
4,296,616	4,296,896	4,296,608	4,297,070	4,296,727	4,297,472
4,296,698	4,296,928	4,296,631	4,296,533	4,296,802	4,297,476
4,296,699	4,296,957	4,296,642	4,296,538	4,296,806	4,297,509
4,296,701	4,296,976	4,296,662	4,296,550	4,296,807	4,296,750
4,296,707	4,296,985	4,296,666	4,296,574	4,296,812	4,296,813
4,296,743	4,297,022	4,296,667	4,296,591	4,296,819	4,296,832
4,296,804	4,297,029	4,296,708	4,296,592	4,296,822	4,296,930
4,296,860	4,297,077	4,296,730	4,296,593	4,296,824	4,296,951
4,296,872	4,297,108	4,296,789	4,296,596	4,296,827	4,296,989
4,297,005	4,297,113	4,296,854	4,296,603	4,296,842	4,297,010
4,297,092	4,297,138	4,296,855	4,296,623	4,296,851	4,297,125
4,297,110	4,297,139	4,296,884	4,296,636	4,296,900	4,297,289
4,297,126	4,297,140	4,296,891	4,296,773	4,296,973	4,297,452
4,297,127	4,297,158	4,296,947	4,296,786	4,297,003	4,297,467
4,297,128	4,297,168	4,296,964	4,296,809	4,297,087	4,297,546
4,297,136	4,297,169	4,297,052	4,296,912		

DESIGN PATENTS

01 : 261,550	08 : 261,555	261,529	26 : 261,505	261,458	261,523
04 : 261,453	09 : 261,483	261,530	261,544	261,459	261,535
06 : 261,448	11 : 261,568	261,547	27 : 261,545	261,460	261,513
261,455	12 : 261,451	261,557	261,551	261,461	261,465
261,463	261,520	261,558	261,552	261,462	261,491
261,477	261,521	261,559	261,566	261,467	261,495
261,480	261,536	261,560	261,472	261,479	261,533
261,488	261,466	261,563	261,486	261,481	261,548
261,504	261,469	261,452	261,519	261,482	261,546
261,507	261,470	261,475	261,549	261,484	261,537
261,510	261,471	261,450	261,501	261,485	261,553
261,517	261,476	261,569	261,540	261,506	261,478
261,525	261,499	261,454	261,541	261,508	261,500
261,526	261,503	261,489	261,445	261,512	261,538
261,527	261,509	261,542	261,449	261,516	261,522
261,539	261,511	261,556	261,456	261,518	261,567
261,543	261,515	261,564	261,457		

PLANT PATENTS

06 : 4,783	39 : 4,781			
------------	------------	--	--	--

CHANGE OF ADDRESS FORM

NAME—FIRST, LAST		
COMPANY NAME OR ADDITIONAL ADDRESS LINE		
STREET ADDRESS		
CITY	STATE	ZIP CODE

PLEASE PRINT OR TYPE

(or) COUNTRY

Mail this form to: NEW ADDRESS

Superintendent of Documents
Government Printing Office SSOM
Washington, D.C. 20402

Attach last subscription
label here.

SUBSCRIPTION ORDER FORM

SUBSCRIPTION ORDER FORM

ENTER MY SUBSCRIPTION TO:

@ \$ Domestic; @ \$ Foreign.

NAME—FIRST, LAST		
COMPANY NAME OR ADDITIONAL ADDRESS LINE		
STREET ADDRESS		
CITY	STATE	ZIP CODE

PLEASE PRINT OR TYPE

(or) COUNTRY

☐ Remittance Enclosed (Make
checks payable to Superin-
tendent of Documents)

☐ Charge to my Deposit
Account No.

MAIL ORDER FORM TO:
Superintendent of Documents
Government Printing Office
Washington, D.C. 20402






U S
OFFICIAL GAZETTE
UNITED STATES
PATENT OFFICE

VOL NO 1011

OCTOBER

1981

MICRO PHOTO DIVISION



BELL & HOWELL

BH

END